



May 30, 2014

David Martin and  
Members of the Siting Council  
Connecticut Siting Council  
Ten Franklin Square  
New Britain, CT 06051

RE: Notice of Exempt Modification  
151 Berkshire Road  
Newtown, CT 06470  
Sprint Site #: NV2.5\_CT54XC770  
N 41° 23' 50.55"  
W -73° 14' 09.85"

Dear Mr. Martin and Members of the Siting Council:

On behalf of Sprint Spectrum, SBA Communications is submitting an exempt modification application to the Connecticut Siting Council for modification of existing equipment at a tower facility located at 151 Berkshire Road, Newtown, CT.

The 151 Berkshire Road facility consists of a 149' MONOPOLE Tower owned and operated by SBA Infrastructure, Inc. In order to accommodate technological changes and enhance system performance in the State of Connecticut, Sprint Spectrum plans to modify the equipment configurations at many of its existing cell sites. Please accept this letter and attachments as notification, pursuant to R.C.S.A. Section 16-50j-73, of construction which constitutes an exempt modification pursuant to R.C.S.A. Section 16-50j-72(b)(2). In compliance with R.C.S.A. Section 16-50j-73, a copy of this letter and attachments is being sent to the chief elected official of the municipality in which the affected cell site is located.

As part of Sprint's Network Vision modification project, Sprint desires to upgrade their equipment to meet the new standards of 4G technology. The new equipment will allow customers to download files and browse the internet at a high rate of speed while also allowing their phones to be compatible with the latest 4G technology.

Attached is a summary of the planned modifications, including power density calculations reflecting the change in Sprint's operations at the site along with the required fee of \$625.

The changes to the facility do not constitute modifications as defined in Connecticut General Statutes ("C.G.S.") Section 16-50i(d) because the general physical characteristics of the facility will not be



significantly changed or altered. Rather, the planned changes to the facility fall squarely within those activities explicitly provided for in R.C.S.A. Section 16-50j-72(b)(2).

1. The overall height of the structure will be unaffected.
2. The proposed changes will not extend the site boundaries. There will be no effect on the site compound other than the new equipment cabinets.
3. The proposed changes will not increase the noise level at the existing facility by six decibels or more.
4. The changes in radio frequency power density will not increase the calculated "worst case" power density for the combined operations at the site to a level at or above the applicable standard for uncontrolled environments as calculated for a mixed frequency site.

For the foregoing reasons, SBA Communications on behalf of Sprint Spectrum, respectfully submits that the proposed changes at the referenced site constitute exempt modifications under R.C.S.A. Section 16-50j-72(b)(2).

Please feel free to call me at (508) 251-0720 x 3804 with any questions you may have concerning this matter.

Thank you,

Kri Pelletier  
SBA Communications Corporation  
33 Boston Post Road West Suite 320  
Marlborough, MA 01752  
508-251-0720 x 3804 + T  
508-251-1755 + F  
203-446-7700 + C  
[kpelletier@sbsite.com](mailto:kpelletier@sbsite.com)



**Sprint Spectrum  
Equipment Modification**

151 Berkshire Road, Newtown, CT  
Site number CT54XC770

**Tower Owner:** SBA Infrastructure, Inc.

**Equipment Configuration:** MONOPOLE Tower

**Current and/or approved:**

- (3) RFS APXVSP18-C-A20
- (3) Alcatel Lucent 1900 MHz RRHs
- (3) Alcatel Lucent 800 MHz RRHs
- (3) Alcatel Lucent 800 MHz Filters
- (4) RFS ACU-A20-N RETs
- (3) 1-1/4" Hybrid Lines

**Planned Modifications:**

- (3) RFS APXVSP18-C-A20
- (3) RFS APXVTM14-C-I20
- (3) Alcatel Lucent 1900 MHz RRHs
- (3) Alcatel Lucent 800 MHz RRHs
- (3) Alcatel Lucent 800 MHz Filters
- (3) Alcatel Lucent TD-RRH8x20-25 RRHs
- (4) RFS ACU-A20-N RETs
- (4) 1-1/4" Hybrid Lines

**Structural Information:**

The attached structural analysis demonstrates that the tower and foundation will have adequate structural capacity to accommodate the proposed modifications.

**Power Density:**

The anticipated Maximum Composite contributions from the Sprint facility are 2.74% of the allowable FCC established general public limit. The anticipated composite MPE value for this site assuming all carriers present is 49.02% of the allowable FCC established general public limit sampled at the ground level.

Site Composite MPE %	
Carrier	MPE %
Sprint	2.74%
T-Mobile	10.90%
Town of Newtown	1.60%
Verizon Wireless	19.75%
AT&T	14.03%
<b>Total Site MPE %</b>	<b>49.02%</b>





May 30, 2014

First Selectman E. Patricia Llodra  
Town of Newtown  
Town Hall  
3 Primrose Street  
Newtown, CT 06470

RE: Telecommunications Facility @ 151 Berkshire Road, Newtown CT

Dear Ms. Llodra,

In order to accommodate technological changes and enhance system performance in the State of Connecticut, Sprint Spectrum will be changing its equipment configuration at certain cell sites.

As required by Regulations of Connecticut State Agencies (R.C.S.A.) Section 16-50j-73, the Connecticut Siting Council has been notified of the changes and will review Sprint's proposal. Please accept this letter as notification under Section 16-50j-73 of construction which constitutes an exempt modification pursuant to R.C.S.A. Section 16-50j-72(b)(2).

The accompanying letter to the Siting Council fully describes Sprint's proposal for the referenced cell site. However, if you have any questions or require any further information on our plans or the Siting Council's procedures, please call me at (508) 251-0720 x 3804.

Thank you,

A handwritten signature in black ink, appearing to read "Kri Pelletier", is positioned below the "Thank you," text.

Kri Pelletier  
SBA Communications Company  
33 Boston Post Road West, Suite 320  
Marlborough, MA 01752  
508-251-0720 x 3804 + T  
508-251-1755 + F  
203-446-7700 + C  
[kpelletier@sbsite.com](mailto:kpelletier@sbsite.com)



May 30, 2014

Ms. Kathy Kelly  
Mr. Kevin D. Friedman  
151 Berkshire Road  
Sandy Hook CT 06482

RE: Telecommunications Facility @ 151 Berkshire Road, Newtown CT

Dear Ms. Kelley and Mr. Friedman,

In order to accommodate technological changes and enhance system performance in the State of Connecticut, Sprint Spectrum will be changing its equipment configuration at certain cell sites.

As required by Regulations of Connecticut State Agencies (R.C.S.A.) Section 16-50j-73, the Connecticut Siting Council has been notified of the changes and will review Sprint's proposal. Please accept this letter as notification under Section 16-50j-73 of construction which constitutes an exempt modification pursuant to R.C.S.A. Section 16-50j-72(b)(2).

The accompanying letter to the Siting Council fully describes Sprint's proposal for the referenced cell site. However, if you have any questions or require any further information on our plans or the Siting Council's procedures, please call me at (508) 251-0720 x 3804.

Thank you,

A handwritten signature in black ink, appearing to read "Kri Pelletier", is located below the "Thank you," text.

Kri Pelletier  
SBA Communications Company  
33 Boston Post Road West, Suite 320  
Marlborough, MA 01752  
508-251-0720 x 3804 + T  
508-251-1755 + F  
203-446-7700 + C  
[kpelletier@sbsite.com](mailto:kpelletier@sbsite.com)

RADIO FREQUENCY FCC REGULATORY COMPLIANCE  
MAXIMUM PERMISSIBLE EXPOSURE (MPE) ASSESSMENT

Sprint Existing Facility

Site ID: CT54XC770

Newtown East - Dwyer

151 Berkshire Road  
Newtown, CT 06482

**May 29, 2014**

**EBI Project Number: 62143105**

May 29, 2014

Sprint  
Attn: RF Engineering Manager  
1 International Boulevard, Suite 800  
Mahwah, NJ 07495

Re: Radio Frequency Maximum Permissible Exposure (MPE) Assessment for Site:  
**CT54XC770 - Newtown East - Dwyer**

**Site Total: 49.02% - MPE% in full compliance**

EBI Consulting was directed to analyze the proposed upgrades to the existing Sprint facility located at 151 Berkshire Road, Newtown, CT, for the purpose of determining whether the radio frequency (RF) exposure levels from the proposed Sprint equipment upgrades on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter ( $\mu\text{W}/\text{cm}^2$ ). The number of  $\mu\text{W}/\text{cm}^2$  calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits, therefore it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) – (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general public may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general public would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

Public exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter ( $\mu\text{W}/\text{cm}^2$ ). The general population exposure limit for the cellular band (850 MHz Band) is approximately  $567 \mu\text{W}/\text{cm}^2$ , and the general population exposure limit for the 1900 MHz and 2500 MHz bands is  $1000 \mu\text{W}/\text{cm}^2$ . Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.

Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure. Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

## **CALCULATIONS**

Calculations were done for the proposed upgrades to the existing Sprint Wireless antenna facility located at 151 Berkshire Road, Newtown, CT, using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. All calculations were performed assuming a lobe representing the maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was focused at the base of the tower. For this report the sample point is the top of a 6 foot person standing at the base of the tower.

For all calculations, all emissions were calculated using the following assumptions:

- 1) 3 channels in the 1900 MHz Band were considered for each sector of the proposed installation.
- 2) 1 channel in the 800 MHz Band was considered for each sector of the proposed installation
- 3) 2 channels in the 2500 MHz Band were considered for each sector of the proposed installation.
- 4) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 - Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.
- 5) For the following calculations the sample point was the top of a six foot person standing at the base of the tower. The maximum gain of the antenna per the antenna manufactures supplied specifications minus 10 dB was used in this direction. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.



- 6) The antennas used in this modeling are the RFS APXVSPP18-C-A20 and the RFS APXVTM14-C-I20. This is based on feedback from the carrier with regards to anticipated antenna selection. The RFS APXVSPP18-C-A20 has a 15.9 dBd gain value at its main lobe at 1900 MHz and 13.4 dBd at its main lobe for 850 MHz. The RFS APXVTM14-C-I20 has a 15.9 dBd gain value at its main lobe at 2500 MHz. The maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was used for all calculations. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 7) The antenna mounting height centerline for the proposed antennas is **107.5 feet** above ground level (AGL).
- 8) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.

All calculation were done with respect to uncontrolled / general public threshold limits

Site ID	CT54XC770 - Newtown East - Dwyer
Site Address	151 Berkshire Road, Newtown, CT, 06482
Site Type	Monopole

**Sector 1**

Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain (10 db reduction)	Antenna Height (ft)	analysis height	Cable Size	Cable Loss (dB)	Additional Loss (dB)	ERP	Power Density Percentage
1a	RFS	APXVSP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	3	60	5.9	107.5	101.5	1/2 "	0.5	3	104.27	0.36%
1a	RFS	APXVSP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	3.4	107.5	101.5	1/2 "	0.5	3	19.54	0.12%
1B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	5.9	107.5	101.5	1/2 "	0.5	3	69.51	0.43%
Sector total Power Density Value:																0.91%

**Sector 2**

Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain (10 db reduction)	Antenna Height (ft)	analysis height	Cable Size	Cable Loss (dB)	Additional Loss (dB)	ERP	Power Density Percentage
2a	RFS	APXVSP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	3	60	5.9	107.5	101.5	1/2 "	0.5	3	104.27	0.36%
2a	RFS	APXVSP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	3.4	107.5	101.5	1/2 "	0.5	3	19.54	0.12%
2B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	5.9	107.5	101.5	1/2 "	0.5	3	69.51	0.43%
Sector total Power Density Value:																0.91%

**Sector 3**

Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain (10 db reduction)	Antenna Height (ft)	analysis height	Cable Size	Cable Loss (dB)	Additional Loss (dB)	ERP	Power Density Percentage
3a	RFS	APXVSP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	3	60	5.9	107.5	101.5	1/2 "	0.5	3	104.27	0.36%
3a	RFS	APXVSP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	3.4	107.5	101.5	1/2 "	0.5	3	19.54	0.12%
3B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	5.9	107.5	101.5	1/2 "	0.5	3	69.51	0.43%
Sector total Power Density Value:																0.91%

Site Composite MPE %	
Carrier	MPE %
Sprint	2.74%
T-Mobile	10.90%
Town of Newtown	1.60%
Verizon Wireless	19.75%
AT&T	14.03%
<b>Total Site MPE %</b>	<b>49.02%</b>

## Summary

All calculations performed for this analysis yielded results that were well within the allowable limits for general public Maximum Permissible Exposure (MPE) to radio frequency energy.

The anticipated Maximum Composite contributions from the Sprint facility are **2.74% (0.91% from sector 1, 0.91% from sector 2 and 0.91% from sector 3)** of the allowable FCC established general public limit considering all three sectors simultaneously sampled at the ground level.

The anticipated composite MPE value for this site assuming all carriers present is **49.02%** of the allowable FCC established general public limit sampled at 6 feet above ground level. This total composite site value is based upon MPE values listed in the Connecticut Siting Council database for existing carrier emissions.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.



Scott Heffernan  
RF Engineering Director

### **EBI Consulting**

21 B Street  
Burlington, MA 01803



FDH Engineering, Inc., 6521 Meridien Drive Raleigh, NC 27616, Ph. 919.755.1012

**Structural Analysis for  
SBA Network Services, Inc.**

**149' Monopole Tower**

**SBA Site Name: Newtown  
SBA Site ID: CT13057-A-02  
Sprint Site ID: CT54XC770**

FDH Project Number 14267K1400

**Analysis Results**

Tower Components	94.8%	Sufficient
Foundation	66.7%	Sufficient


Prepared By:

Luis A. Mendoza, EIT  
Project Engineer

Reviewed By:

J. Darrin Holt, PhD, PE  
Principal  
CT PE License No. 22988

**FDH Engineering, Inc.**  
6521 Meridien Drive  
Raleigh, NC 27616  
(919) 755-1012  
info@fdh-inc.com



April 21, 2014

*Prepared pursuant to TIA/EIA-222-F Structural Standards for Steel Antenna Towers and Antenna Supporting Structures and the 2005 Connecticut Building Code*



**TABLE OF CONTENTS**

EXECUTIVE SUMMARY ..... 3

    Conclusions..... 3

    Recommendations..... 3

APPURTENANCE LISTING ..... 4

RESULTS ..... 5

GENERAL COMMENTS ..... 6

LIMITATIONS ..... 6

APPENDIX ..... 7

## EXECUTIVE SUMMARY

At the request of SBA Network Services, Inc., FDH Engineering, Inc. performed a structural analysis of the monopole located in Newtown, CT to determine whether the tower is structurally adequate to support both the existing and proposed loads pursuant to the *Structural Standards for Steel Antenna Towers and Antenna Supporting Structures, TIA/EIA-222-F* and the *2005 Connecticut Building Code*. Information pertaining to the existing/proposed antenna loading, current tower geometry, foundation dimensions, geotechnical data, and member sizes was obtained from:

- Sabre Communications Corp. (Job No. 06-07285) Structural Design Report dated July 28, 2005
- Paul J. Ford & Company (Job No. 29203-0081) Foundation Drawing dated April 28, 2003
- FDH, Inc. (Job No. 08-07122T) TIA Inspection Report dated September 10, 2008
- SBA Network Services, Inc.

The *basic design wind speed* per the *TIA/EIA-222-F* standards and the *2005 Connecticut Building Code* is 85 mph without ice and 38 mph with 3/4" radial ice. Ice is considered to increase in thickness with height.

## Conclusions

With the existing and proposed antennas from Sprint in place at 107.5 ft, the tower meets the requirements of the *TIA/EIA-222-F* standards and the *2005 Connecticut Building Code* provided the **Recommendations** listed below are satisfied. Furthermore, provided the foundation was designed and constructed to support the original design reactions (see Paul J. Ford Job No. 29203-0081), the foundation should have the necessary capacity to support the existing and proposed loading. For a more detailed description of the analysis of the tower, see the **Results** section of this report.

Our structural analysis has been performed assuming all information provided to FDH Engineering, Inc. is accurate (i.e., the steel data, tower layout, existing antenna loading, and proposed antenna loading) and that the tower has been properly erected and maintained per the original design drawings.

## Recommendations

To ensure the requirements of the *TIA/EIA-222-F* standards and the *2005 Connecticut Building Code* are met with the existing and proposed loading in place, we have the following recommendations:

1. The proposed feed line should be installed inside the pole's shaft.
2. RRU/RRH Stipulation: The equipment may be installed in any arrangement as determined by the client.

## APPURTENANCE LISTING

The proposed and existing antennas with their corresponding cables/coax lines are shown in **Table 1**. *If the actual layout determined in the field deviates from the layout, FDH Engineering, Inc. should be contacted to perform a revised analysis.*

**Table 1 - Appurtenance Loading**

### Existing Loading:

Antenna Elevation (ft)	Description	Coax and Lines	Carrier	Mount Elevation (ft)	Mount Type
153	(1) Decibel - TDD6492A-A Dipole	(2) 7/8"	Town of Newtown	149	(1) 2' Standoff
147	(1) Telewave ANT150D				
137.5	(3) Antel BXA-171063-8BF (3) Swedcom SLCP 2X6014 (6) Swedcom SC-E 6014 Rev 2 w (6) RFS FD9R6004/2C-3L Diplexers	(12) 1-5/8"	Verizon	137.5	(1) 13' Low Profile Platform
118.5	(3) Powerwave 7770.00 (3) Powerwave P65-16 (6) Powerwave LGP21401 TMAs (6) Ericsson RRUS-11 RRUs (1) Raycap DC6-48-60-18-8F Surge Arrestor	(6) 1-5/8" (1) 3/8" (2) 5/8"	AT&T	118.5	(1) Low Profile Platform
109	(3) RFS APXVSP18-C-A20 (3) Alcatel Lucent 1900 MHz RRHs (3) Alcatel Lucent 800 MHz RRHs (3) Alcatel Lucent 800 MHz Filters (4) RFS ACU-A20-N RETs	(3) 1-1/4"	Sprint	109	(3) T-Arms w/ Working Platforms
99.5	(6) EMS RR65-18-02DPL2 (6) Remec 520057A1 TMAs	(12) 1-1/4"	T-Mobile	99.5	(1) 14' Low Profile Platform
50.5	(1) Decibel 260B GPS	(1) 1/2"	Sprint	50.5	(1) 3' Standoff

### Proposed Loading:

Antenna Elevation (ft)	Description	Coax and Lines	Carrier	Mount Elevation (ft)	Mount Type
107.5	(3) RFS APXVSP18-C-A20 (3) RFS APXVTM14-C-I20 (3) Alcatel Lucent 1900 MHz RRHs (3) Alcatel Lucent 800 MHz RRHs (3) Alcatel Lucent 800 MHz Filters (3) Alcatel Lucent TD-RRH8x20-25 RRHs (4) RFS ACU-A20-N RETs	(4) 1-1/4"	Sprint	109	(3) T-Arms w/ Working Platforms

## RESULTS

The following yield strength of steel for individual members was used for analysis:

**Table 2 - Material Strength**

Member Type	Yield Strength
Tower Shaft Sections	65 ksi
Flange Plate	60 ksi
Flange Bolts	Fu = 120 ksi
Base Plate	60 ksi
Anchor Bolts	75 ksi

**Table 3** displays the summary of the ratio (as a percentage) of force in the member to their capacities. Values greater than 100% indicate locations where the maximum force in the member exceeds its capacity. **Table 4** displays the maximum foundation reactions.

If the assumptions outlined in this report differ from actual field conditions, FDH Engineering, Inc. should be contacted to perform a revised analysis. Furthermore, as no information pertaining to the allowable twist and sway requirements for the existing or proposed appurtenances was provided, deflection and rotation were not taken into consideration when performing this analysis.

See the **Appendix** for detailed modeling information

**Table 3 - Summary of Working Percentage of Structural Components**

Section No.	Elevation ft	Component Type	Size	% Capacity*	Pass Fail
L1	149 - 139	Pole	TP19.85x17.5x0.1875	2.5	Pass
		Flange Bolts	(8) 1"Ø w/ BC = 22.75"	3.3	Pass
		Flange Plate	27"Ø x 0.75" Thick	5.5	Pass
L2	139 - 129	Pole	TP22.2x19.85x0.1875	15.8	Pass
		Flange Bolts	(8) 1"Ø w/ BC = 25.25"	23.9	Pass
		Flange Plate	29.5"Ø x 0.75" Thick	41.9	Pass
L3	129 - 97.75	Pole	TP29.54x22.2x0.1875	62.1	Pass
L4	97.75 - 48	Pole	TP40.86x28.2842x0.3125	77.9	Pass
L5	48 - 0	Pole	TP51.51x39.0009x0.3125	94.8	Pass
		Anchor Bolts	(12) 2.25"Ø w/ BC = 58"	87.3	Pass
		Base Plate	56" SQ. x 2.75" Thick	37.9	Pass

\* Capacities include 1/3 allowable stress increase for wind per TIA/EIA-222-F.

**Table 4 - Maximum Base Reactions**

Base Reactions	Current Analysis (TIA/EIA-222-F)	Original Design (TIA/EIA-222-F)
Axial	29 k	38 k
Shear	25 k	35 k
Moment	2,503 k-ft	3,750 k-ft



## **GENERAL COMMENTS**

This engineering analysis is based upon the theoretical capacity of the structure. It is not a condition assessment of the tower and its foundation. It is the responsibility of SBA Network Services, Inc. to verify that the tower modeled and analyzed is the correct structure (with accurate antenna loading information) modeled. If there are substantial modifications to be made or the assumptions made in this analysis are not accurate, FDH Engineering, Inc. should be notified immediately to perform a revised analysis.

## **LIMITATIONS**

All opinions and conclusions are considered accurate to a reasonable degree of engineering certainty based upon the evidence available at the time of this report. All opinions and conclusions are subject to revision based upon receipt of new or additional/updated information. All services are provided exercising a level of care and diligence equivalent to the standard and care of our profession. No other warranty or guarantee, expressed or implied, is offered. Our services are confidential in nature and we will not release this report to any other party without the client's consent. The use of this engineering work is limited to the express purpose for which it was commissioned and it may not be reused, copied, or distributed for any other purpose without the written consent of FDH Engineering, Inc.

## **APPENDIX**

## DESIGNED APPURTENANCE LOADING



TYPE	ELEVATION	TYPE	ELEVATION
Lightning Rod	149	1900 MHz RRRH	109
6"x2.38" Pipe Mount	149	1900 MHz RRRH	109
ANT150D	149	1900 MHz RRRH	109
Decibel - TDD6492A-A Dipole	149	800 MHz RRRH	109
2' Standoff	149	800 MHz RRRH	109
13' Low Profile Platform	137.5	800 MHz RRRH	109
Antel BXA-171063-8BF w/ Mount Pipe	137.5	800 MHz Filter	109
Antel BXA-171063-8BF w/ Mount Pipe	137.5	800 MHz Filter	109
Antel BXA-171063-8BF w/ Mount Pipe	137.5	800 MHz Filter	109
SLCP 2X6014 w/Mount Pipe	137.5	(2) ACU-A20-N RET	109
SLCP 2X6014 w/Mount Pipe	137.5	ACU-A20-N RET	109
SLCP 2X6014 w/Mount Pipe	137.5	ACU-A20-N RET	109
(2) SC-E 6014 Rev 2 w/ Mount Pipe	137.5	(3) T-Arms w/ Working Platforms	109
(2) SC-E 6014 Rev 2 w/ Mount Pipe	137.5	Empty Mount Pipe	109
(2) SC-E 6014 Rev 2 w/ Mount Pipe	137.5	Empty Mount Pipe	109
(2) FD9R6004/2C-3L Diplexer	137.5	Empty Mount Pipe	109
(2) FD9R6004/2C-3L Diplexer	137.5	APXVTM14-C-I20 w/ Mount Pipe	109
(2) FD9R6004/2C-3L Diplexer	137.5	APXVTM14-C-I20 w/ Mount Pipe	109
7770.00 w/Mount Pipe	118.5	APXVTM14-C-I20 w/ Mount Pipe	109
7770.00 w/Mount Pipe	118.5	TD-RRH8x20-25	109
7770.00 w/Mount Pipe	118.5	TD-RRH8x20-25	109
P65-16 w/Mount Pipe	118.5	TD-RRH8x20-25	109
P65-16 w/Mount Pipe	118.5	14' Low Profile Platform	99.5
P65-16 w/Mount Pipe	118.5	(2) Empty Mount Pipe	99.5
(2) LGP21401	118.5	(2) Empty Mount Pipe	99.5
(2) LGP21401	118.5	(2) Empty Mount Pipe	99.5
(2) LGP21401	118.5	(2) RR65-18-02DPL2 w/Mount Pipe	99.5
(2) RRUS-11	118.5	(2) RR65-18-02DPL2 w/Mount Pipe	99.5
(2) RRUS-11	118.5	(2) RR65-18-02DPL2 w/Mount Pipe	99.5
(2) RRUS-11	118.5	(2) Remec - 520057A1	99.5
DC6-48-60-18-8F Surge Arrestor	118.5	(2) Remec - 520057A1	99.5
Low Profile Platform	118.5	(2) Remec - 520057A1	99.5
APXVSP18-C-A20 w/Mount Pipe	109	Decibel 260B GPS	50.5
APXVSP18-C-A20 w/Mount Pipe	109	3' Standoff	50.5
APXVSP18-C-A20 w/Mount Pipe	109		

### MATERIAL STRENGTH

GRADE	Fy	Fu	GRADE	Fy	Fu
A572-65	65 ksi	80 ksi			


### TOWER DESIGN NOTES

1. Tower is located in Fairfield County, Connecticut.
2. Tower designed for a 85 mph basic wind in accordance with the TIA/EIA-222-F Standard.
3. Tower is also designed for a 38 mph basic wind with 0.75 in ice. Ice is considered to increase in thickness with height.
4. Deflections are based upon a 50 mph wind.
5. TOWER RATING: 94.8%




Section	Length (ft)	Number of Sides	Thickness (in)	Socket Length (ft)	Top Dia (in)	Bot Dia (in)	Grade	Weight (K)
1	10.00	18	0.1875				A572-65	0.4
2	10.00	18	0.1875				A572-65	0.4
3	31.25	18	0.1875	3.75	22.2000	29.5400	A572-65	1.6
4	53.50	18	0.3125	5.25	28.2842	40.8600	A572-65	6.2
5	53.25	18	0.3125	39.0009	51.5100		A572-65	8.1
								16.7

 Tower Analysis	<b>FDH Engineering, Inc.</b>	Job: <b>Newtown, CT13057-A-02</b>			
	6521 Meridien Drive Raleigh, North Carolina Phone: 9197551012 FAX: 9197551031	Project: <b>14267K1400</b>	Client: SBA Network Services, Inc.	Drawn by: LMendoza	App'd:
		Code: TIA/EIA-222-F	Date: 04/21/14	Scale: NTS	Dwg No. E-1
		Path:			




*Daniel P. Hamm*




**RAN EQUIPMENT PHOTO DETAIL**

SCALE: N.T.S.



**COMPOUND PLAN**

SCALE: 3/16"=1'-0"



CHECKED BY: KB

APPROVED BY: DPH

SUBMITTALS			
REV.	DATE	DESCRIPTION	BY
0	05/21/14	ISSUED FOR CONSTRUCTION	SF

SITE NUMBER:  
NEWTOWN EAST - DWYER

SITE NAME:  
CT54XC770-B

SITE ADDRESS:  
151 BERKSHIRE ROAD  
NEWTOWN, CT 06470

SHEET TITLE  
COMPOUND PLAN

SHEET NUMBER  
A-1




*Daniel P. Hamm*


**SPECIAL CONSTRUCTION NOTE:**  
SPRINT TOWER TOP WORK IS CONTINGENT ON THE FOLLOWING:  
\* COMPLETION OF A GLOBAL STRUCTURAL STABILITY ANALYSIS (PROVIDED BY TOWER OWNER).  
\* COMPLETION OF AN ANTENNA/RRH MOUNT STRUCTURAL ASSESSMENT (PROVIDED BY A&E VENDOR).  
\* GC SHALL FURNISH, INSTALL AND COMPLETE ALL REQUIRED STRUCTURAL MODIFICATIONS AS INDICATED IN BEFORE-MENTIONED ANALYSIS AND ASSESSMENT.  
\* SBA COMMUNICATIONS CORPORATION SHALL PROVIDE WRITTEN ACCEPTANCE/APPROVAL FOR THE COMPLETION OF ALL TOWER/FOUNDATION STRUCTURAL MODIFICATIONS INCLUDING (AS NECESSARY) CONTROLLED CONSTRUCTION INSPECTIONS, SHOP-DRAWING APPROVALS, MATERIALS TEST RESULTS, AND FINAL ENGINEER'S AFFIDAVIT.

**NOTE:**  
EXISTING AZIMUTHS FROM SPRINT  
SITE AUDIT DATED 08/17/13

**NOTE:**  
SPRINT RAD CENTER SHOWN IN RED TEXT BASED ON SBA-PROVIDED COLLOCATION APPLICATION, EQUIPMENT DATABASE, AND STRUCTURAL ANALYSIS. THE SBA-PROVIDED ANTENNA RAD CENTER SHALL SUPERSEDE ANY CONFLICTING INFORMATION DERIVED FROM THE SPRINT NV 2.5 RFDS.



**EXISTING PARTIAL ELEVATION PHOTO DETAIL**  
SCALE: N.T.S.





**SPECIAL WORK NOTE:**  
JUMPERS FROM 2.5 RRH TO 2.5 ANTENNA CAN NOT EXCEED 15'. NOTIFY SPRINT CONSTRUCTION MANAGER OF ANY DISCREPANCY.

**NOTE:**  
VERIFY PROPOSED AZIMUTHS WITH RF ENGINEER PRIOR TO INSTALLATION.

**ANTENNA STATUS LEGEND:**  
EMPTY - EMPTY PIPE  
(E) - EXISTING  
(P) - INSTALL  
NV - SPRINT ANTENNA MODEL APXVSP18-C-A20  
2.5 - SPRINT ANTENNA

**NOTES:**  
GROUND EQUIPMENT NOT SHOWN FOR CLARITY.

**ELEVATION**  
SCALE: 3/32"=1'-0"



CHECKED BY: KB

APPROVED BY: DPH

**SUBMITTALS**

REV.	DATE	DESCRIPTION	BY
0	05/21/14	ISSUED FOR CONSTRUCTION	SF

SITE NUMBER:  
NEWTOWN EAST - DWYER  
SITE NAME:  
CT54XC770-B  
SITE ADDRESS:  
151 BERKSHIRE ROAD  
NEWTOWN, CT 06470

SHEET TITLE  
ELEVATION AND ANTENNA PLANS

SHEET NUMBER  
A-2