

Jerry Feathers Tel (704) 405-6549 Fax (724) 416-6484

Email: Jerry.feathers.contractor@crowncastle.com

February 23, 2015

Melanie A. Bachman Connecticut Siting Council 10 Franklin Square New Britain, CT 06051

**RE:** T-Mobile-Exempt Modification - Crown Site BU: 822765

T-Mobile Site ID: CT11025B

Located at: 201 Main Street, Newtown, CT 06470

Dear Ms. Bachman:

This letter is to confirm that all construction activity has been completed. Pursuant to the Connecticut Siting Council approval of **EM-T-MOBILE-014-141020**, this letter is to satisfy item number three of the approval letter that the CSC will be notified in writing within 45 days after completion of construction.

Please contact me if you have any questions.

Sincerely,

# **Jerry Feathers**

Property Specialist 704-405-6549





10 INDUSTRIAL AVENUE, SUITE 3 MAHWAH, NJ 07430

PHONE: 201.684.0055 FAX: 201.684.0066

April 30, 2015

Attorney Melanie Bachman Acting Executive Director Connecticut Siting Council 10 Franklin Square New Britain, CT 06051

RE: EM-T-Mobile-097-141020

T-Mobile Site ID CT11217A 201 Main Street, Newtown, CT Notice of Construction Complete

Dear Attorney Bachman,

This office represents T-Mobile Northeast LLC ("T-Mobile") and has been retained to notify the Connecticut Siting Council ("Council") that the exempt modification decision conditions have been met and constructed in accordance with the documentation provided at the time of filing.

The Council acknowledged the above referenced T-Mobile notice of exempt modification on November 10, 2014.

The Council imposed the following conditions in its acknowledgment:

- Perform foundation mapping in accordance with the structural analysis report prepared by Paul J. Ford and Co., stamped by Justin Kline on October 6, 2014, prior to the installation of T-Mobile's equipment.
- Within 45 days following completion of the equipment installation, T-Mobile shall provide documentation that its installation complied with the recommendations of the Structural Analysis Report.

The attached Statement of Special Inspections provides evidence of compliance with the conditions outlined by the Council.

In addition, T-Mobile hereby notifies the Council that construction of the acknowledged modifications were complete as of December 31, 2014.

Sincerely,

Jamie Marchini

**Project Manager** 

Transcend Wireless LLC on behalf of T-Mobile

10 Industrial Ave, Suite 3

Mahwah, NJ 07430

Brian Arriaga
Crown Castle
1200 MacArthur Blvd, STE 200
Mahwah, NJ 07430
(201) 316-9172
Brian.Arriaga.Contractor@crowncastle.com

SGS

Sinnott Gering and Schmitt Towers, INC 14301 First National Bank Pkwy STE 100 Omaha, NE 68154 (402) 507-5170 SGS PMI@sgstowers.com

Subject: Modification Inspection Report

Crown Castle Designation: Crown Castle BU Number: 826222

Crown Castle Site Name: Newtown/RT-25

Crown Castle JDE Job Number: 225018

Engineering Firm Designation: SGS Project Number 130625

Site Data: 201 Main St.

Newtown, CT 06470

N 41° 22' 41.32", W -73° 16' 26.94"

150 Foot Monopole

Dear Mr. Arriaga,

Sinnott Gering and Schmitt Towers, Inc. (SGS) is pleased to submit this "Modification Inspection Report" (MI Report) to Crown Castle for the modification/reinforcement to the subject structure. This Modification Inspection (MI) was performed in accordance with Crown Castle ENG-SOW-10007 Modification Inspection SOW, Contract Documents, and Crown Castle Purchase Order number 596145. The purpose of this MI is to confirm that the modification installation configuration and workmanship are in accordance with the contract document(s) listed in Table 2. The MI is not a review of the adequacy or effectiveness of the modification/reinforcement solution.

Table 1 – General Information

	Company	Contact	Dates on Site		
MI Inspector	SGS	Nicholas J. Schmitt, P.E., S.E.	N/A		
MI Inspector Field Representative (if applicable)	SGS	Daniel Sinnott	June 4, 2014		
Independent	□ EOR	☐ Turnkey			
Modification Design EOR	Paul J. Ford	Joseph Jacobs, P.E.	N/A		
General Contractor	LCC	Keith Stackhouse	Unknown		
Sub to the General Contractor	N/A	N/A	N/A		
Field CWI for the General Contractor	N/A	N/A	N/A		
Field NDE for the General Contractor	N/A	N/A	N/A		

Table 2 – Documents

Document(s)	Remarks	Source
Modification Drawings	Creator of Drawings:	CCI Sites
Date: 8/21/2013	Paul J. Ford	Drawing File:
EOR: Joseph Jacobs, P.E.	Job #: 37513-1642	3963744
Job#: 37513-1642	Date of Drawings: 8/21/2013	

Based on our inspection, SGS determines this project:

## X PASSING MI

The configuration, materials and/or workmanship of the modifications are installed in accordance with the Contract Documents and no deficiencies were found.


# **EXECUTIVE SUMMARY**

MODIFICATION	CONFIGURATION	MATERIALS	WORKMANSHIP
Install New Micropiles In Existing Foundation. 0'.	Passing	Passing	Passing
Note: A Thicker Bearing Pl	ate was Installed tha	J	

All observations were performed after the construction was complete. SGS was not present during the construction phase. The onsite PMI was performed by Daniel Sinnott, SGS.

We at SGS appreciate the opportunity of providing our continuing professional services to you and Crown Castle. If you have any questions or need further assistance on this or any other projects please give us a call.

Respectfully submitted,



Nick Schmitt, P.E., S.E.

# Table of Contents

PRE-CONSTRUCTION	5
6.1.1 MI CHECKLIST DRAWING	6
6.1.2 EOR APPROVED SHOP DRAWINGS	7
6.1.3 FABRICATION INSPECTION	8
6.1.4 MATERIAL TEST REPORT (MTR)	9
6.1.5 PACKING SLIPS	14
CONSTRUCTION	18
6.2.1 CONSTRUCTION INSPECTIONS	19
6.2.2 FOUNDATION INSPECTIONS	20
6.2.3 CONCRETE COMP. STRENGTH AND SLUMP TESTS	22
6.2.4 DRILLING LOG	25
6.2.5 GC AS-BUILT DOCUMENTS	27
POST-CONSTRUCTION	35
6.3.1 MI INSPECTOR REDLINE OR RECORD DRAWING(S)	36
6.3.2 PHOTOGRAPHS	44
6.3.3 POST INSTALLED MICROPILE PULL-OUT TESTING	45

# **PRE-CONSTRUCTION**

### NCOFICATION INSPECTION NOTES:

GENERAL THE MODIFI SOSTING.
THE MODIFICATION INSPECTION (M) IS A YEAR. INSPECTION OF TOWER MODIFICATIONS AND A REVIEW OF CONSTRUCTION INSPECTIONS AND OTHER MODIFICATIONS AND OTHER WORK TO TO BROWN THE MESTAL LADOR MAS CONSTRUCTED BY ADDORDINGS WITH THE CONTRACT DOCUMENTS, NAMELY THE MODIFICATION FROM THE CONTRACT DOCUMENTS, NAMELY THE MODIFICATION FROM THE CONTRACT OF RECORDING OF

ALL WIS SHALL BE CONDUCTED BY A CROWN ENGINEERING VEHOOR (AEV) OR ENGINEERING SCHWICE VEHOOR (AEBV) THAT IS APPROPRIETED WORK FOR CROWN, SEE (ING-BUL-INTS LET OF APPROVED M VEHOORS,

TO BRISHE THAT THE REQUIREMENTS OF THE MILABE MET, IT IS MITAL THAT THE GOVERNAL CONTINUATOR (SIGLAND THE MILABERCH BRISH COMMUNICATING AND COORDINATING AS SOON AS A 70 OS RECEIVED. IT IS DEFECTED THAT EACH PRINTY WILL BE PROMOTION TO THE OFFICE OF THE THAT FACILITY OF THE PROMOTION TO THE OFFICE OFFIC

REFER TO ENG-SOW-10007 : MODIFICATION INSPECTION SOW FOR FURTHER DETAILS AND REQUIREMENTS.

MINISPECTOR.
THE UILING PERCENT IS REQUIRED TO CONTACT THE OCAS SOON AS RECEIVING A POFOR THE MITO, AT A NAMEUR.

REVIEW THE REQUIREMENTS OF THE MICHECKLIST
 WORK WITH THE GC TO DEVELOP A SCHEDULE TO CONDUCT ON-SITE INSPECTIONS, INCLUDING FOUNDATION INSPECTIONS

THE MINISPECTOR IS RESPONSIBLE FOR COLLECTING ALL GENERAL CONTRACTOR/COCI RESPECTION AND TEST REPORTS, REVIEWING THE DOCUMENTS FOR ACHIERINGE TO THE CONTRACT DOCUMENTS, CONDUCTING THE IN-FRED RESPECTIONS, AND QUARTITING THE MINISPECT.

GENERAL CONTRACTOR
THE COS REQUIRED TO CONTACT THE MI INSPECTOR AS BOON AS RECEIVING A PO FOR THE INCOMPORTION INSTALLATION OR TURNING!
PORCECT TO, AT A PRIMINGING.

- REVIEW THE REQUIREMENTS OF THE MICHECIALST.
   WORK WITH THE WILMSPECTOR TO DEVELOP A SCHEDULE TO CONDUCT OH-BITE INSPECTIONS, INCLUDING FOUNDATION INSPECTIONS.
   BETTER UNDERSTRING ALL INSPECTION AND TESTING REQUIREMENTS.

THE GC SHALL PERFORM AND RECORD THE TEST AND INSPECTION RESULTS IN ADCORDANCE WITH THE REQUIREMENTS OF THE MI CHECKLIST AN DENG-SOW-10007.

RECOMMENDATIONS
THE FOLLOWING RECOMMENDATIONS AND SUGGESTIONS ARE OFFERED TO DIMANCE THE EFFICIENCY AND EFFECTIVENESS OF DELIVEN

- If it suggested that the GO Provide a ninnan of 5 business data incide pretained in to the in indecederably the THE SIZE WILL BE READY FOR the MIT OF CONDUCTED.
   THE GO ADAY INSTELLED CONCORDING TO COURT THE CONTROL THE CHIRE PROJECT.
   THE GO ADAY IN PRODUCTION CONTROL THE COURT THE CONTROL THE CONTROL SIZE WALL TARGOUGHT FOR AN OUT WIRE TENDING OR THE GOOD CONTROL THE CONTROL THE CONTROL THE COURT THE CONTROL THE CONTR

CASCILLATIVE BLOCK AT A LEVERATION IN THE SHIP IN THE CONTACT BY AND ITHER HAVE CASES OF BLOCK AND IN THE CASES OF BLOCK AND INTERPRET CASES OF BLOCK CHARGE AND IN THE CASES OF BLOCK AND INTERPRET CASES. THE CASES OF BLOCK AND INTERPRET CASES OF BL

- CORRECT FALING SISTING TO COMELY WITH THE SPECIFICATIONS CONTAMED IN THE ORIGINAL CONTRACT COCOMENTS AND CORRECTIVE A SPREAMENT NE.
   OR, WITH CONCENTS AND PROVING. THE GC MAY WORK WITH THE GOOD TO RE-ANALYZE THE MODIFICATION REPROFESSED WITH USING THE A BULL CONCENT.

EN YESPICLTON MERCEDIUS. COMM RESERVES HE ROUT TO CONDUCT AM YESPICLATION IMPECTON TO VERFY THE ACQUIACY AND COMPLETENESS OF PREVADULY COMPLETED UT INSPECTIONS) ON TOWER MODIFICATION PROJECTS.

ALL VERIFICATION INSPECTIONS SHALL BE HELD TO THE SAME SPECIFICATIONS AND REQUIREMENTS IN THE CONTRACT DOCUMENTS AND IN ACCORDANCE WITH DIRESOW-10007.

VERIFICATION INSPECTION MAY BE CONDUCTED BY AN INDEPENDENT ARWALSY FRIM AFTER A MODIFICATION PROJECT IS COMPLETED, AS MARKED BY THE DATE OF AN ACCUPITED <u>"PASSING ME"</u> OR "<u>PASS AS NOTED ME</u>" REPORT FOR THE ORIGINAL PROJECT.

# PHOTOGRAPHS BETWEEN THE GC AND THE MEINSPECTOR THE FOLLOWING PHOTOGRAPHS, AT AMNIMUM, ARE TO BE TAKEN AND INCLUDED IN THE ME

- PRE-CONSTRUCTION GENERAL SITE CONDITION
   PRETOGRAPHS QUENTO THE RESPONDEMENT MODERATION CONSTRUCTIONARECTION AND REPRECTION
   RAW MATERIALS
   PROTOS OF ALL CRITICAL ESTALS
   PROTOS OF ALL CRITICAL CRITICAL
   CONSTRUCTION CONTROL
   CONSTRUCTION CONTROL
   FORMATION AND TOPOUL
   FORMATION CONTROL
   SUBTRACT CONTROL FORMATION
   SUBTRACT CONTROL FORMATION
   SUBTRACT CONTROL FORMATION

HOTO'S OF BLEVATED MODIFICATIONS TAKEN FROM THE GROUND SHALL BE CONSIDERED INADEQUATE.

THIS IS NOT A COMPLETE LIST OF REQUIRED PHOTOS, PLEASE REFER TO ENG-SOW-10007.

	MI CHECKLIST
CONSTRUCTION/INSTALLATION INSPECTIONS AND TESTING REQUIRED (COMPLETED BY EOR)	REPORT ITEM
	PRE-CONSTRUCTION
X	MI CHECKLIST DRAWINGS
×	EOR APPROVED SHOP DRIVWINGS
x	FABRICATION INSPECTION
NA.	FABRICATOR CERTIFIED WELD INSPECTION
x	MATERIAL TEST REPORT (MTR)
NA NA	PARRICATOR NDE INSPECTION
NA NA	NDE REPORT OF MONOPOLE BASE PLATE (AS REQUIRED)
x	PACKING SLIPS

STING PLANTO CROWN AND PUF FOR REVIEW , TESTING PLAN SHALL INCLUDE DETAILS REGARDING HOW CONTRACTOR INTENDS

PREVENT INTERACTION BETWEEN THE TEST PILE AND THE EXISTING FOUNDATION DURING TESTING

	CONSTRUCTION	
x	CONSTRUCTION INSPECTIONS	
X	FOUNDATION INSPECTIONS	
X	CONCRETE COMP, STRENGTH AND SLUMP TESTS	
NA NA	POST INSTALLED ANCHOR ROD VERIFICATION	
NA.	BASE PLATE GROUT VERIFICATION	
NA.	CONTRACTORS CERTIFIED WELD INSPECTION	
NA.	EARTHWORK: LIFT AND DENSITY	
NA.	ON SITE COLD GALVANIZING VERIFICATION	

GC AS-BULLY DOCUMENTS
THERE PARTY DIGITE INSPECTION OF BOLT PRETENSION PER CROWN
REQUIREMENTS
ASSPECTION OF ALAX BOLTS AND DITES PER REQUIREMENTS ON SHEET S-3 ADDITIONAL TESTING AND INSPECTIONS. VERIFY MICROPILE INSTALLATION DETAILS, SPECIFICALLY MICROPILE SIZES, DRILL HOLE DAMSTERS A DEPTHS. GROUT TO AND THAT INSTALLATION WAS DEED MANUFACTURED SECONMEND A DEPTH.

DIAMETERS & DEPTHS, GROUT TO AND THAT	I INSTALLATION WAS PER MANUFACTURER RECOMMENDATION	- 1
	THIS, ORDULT EN AND THAIL THE TALLACION WAS FER NAMEWACTURER RECOMMENDATION  POST-CONSTRUCTION  X BHIRPECTOR REQUIRE OR RECORD DRAWMORS:  NA THIS PARTY ORBITE BOLT MERICIACH REPORT	
x	MI INSPECTOR REQUINE OR RECORD DRAWING(S)	
NA	THIRD PARTY ONSITE BOLT INSPECTION REPORT	
NA.	POST INSTALLED ANCHOR ROD PULL-OUT TESTING	

X PHOTOGRAPHS

ADDITIONAL TESTING AND INSPECTIONS: PROVIDE REPORT DOCUMENTING RESULTS OF MICROPILE INSTALLATION AND PROOF

NOTE: X DENOTES A DOCUMENT NEEDED FOR THE PM REPORT
NA DENOTES A DOCUMENT THAT IS NOT REQUIRED FOR THE DM DEDOCT

AUG 2 1 2013

ASBUILT 5-26-14 R.S.T. LCC DEPLOYMENT

**CROWN CASTLE** 

BU #826222; NEWTOWN/RT-25 NEWTOWN, CT MONOPOLE REINFORCEMENT AND RETROFIT PROJECT

CHECKED BY ROVED B

ISSUE DATE OF PERMIT: 8-20-2013

S-6

## 6.1.2 EOR APPROVED SHOP DRAWINGS

From: Kyle Thorpe [mailto:<u>KThorpe@pifweb.com</u>] Sent: Thursday, January 09, 2014 10:51 AM

To: Klaus Horsch

Cc: James Yavorsky; Jeff Hemmings Subject: RE: Newtown RT 25, BU# 826222

Klaus,

Fab drawings are not required as long as we have some verification of the bearing plates, like shipping slips.

Thank you,

Kyle Thorpe, E.I. Structural Designer

Main: (614) 221-6679 ext. 2168 Direct: (614) 448-4168 Email: kthorpe@pjfweb.com





LCC Deployment Services Inc. 2242 Old Mariton Pike, Mariton, NJ 08053 856-810-1658 (Ph) 856-810-1659 (Fax)

To:

Subject: Newtown RT 25 - 826222

June 17, 2014

Please accept this letter as certification that our work on LCC Job # 131670 Newtown RT 25 - 826222 - was performed in accordance with industry standards and the contractor documents.

Please contact me if you have any questions.

Thank you,

Keith A. Stackhouse

Structural Construction Manager LCC Deployment Services Inc.

# 6.1.4 MATERIAL TEST REPORT (MTR)

Hello Klaus,

The drawings called for 60 ksi material. However, I don't believe these are feasible either. Let's go with 2.5" thick A572-50 steel. Let me know if this will work or not.

Thank you,

Kyle Thorpe, E.I. Structural Designer Main: (614) 221-6679 ext. 2168 Direct: (614) 448-4168 Email: kthorpe@pifweb.com



>>> "Klaus Horsch" <<u>khorsch@telecomcontracting.com</u>> 1/9/2014 10:17 AM >>> Good morning Kyle,

The MI Checklist for this project says that EOR approved shop drawings are needed.

But this project is a micropile installation. Do you want to see the bearing plates on S5 on the shop drawings?

Also, will A572-50 work for the plate mentioned above? A572-65 above 1-1/4" thickness is not readily available, if at all.

Thanks,

Klaus Horsch, E.I.T.
TCCI
2242 Old Marlton Pike
Marlton, NJ 08053-2666
856-810-1658 ext. 239
Cell – 609-257-7683
Khorsch@telecomcontracting.com



# Material Test Report

B/L: 304559

4001 Philadelphia Pike, Claymont DE 19703

05/16/2012

Sold To: CERTIFIED STEEL COMPANY

1333 BRUNSWICK PIKE, SUITE 200, LAWRENCEVILLE, NJ 08648

Order 234453-06

Customer PO 120372

Specifications:

3STM A572/A572M-07 Grade 50(345) Type 2 Fully Killed Fine Grain Practice ASTM A709/A709M-10 Grade 50(345) Type 2 Fully Killed Fine Grain Practice

Products Shipped for Order 234453-06 (sorted by Serial)

	many orange on ag	R/R	Plate Size in Inches	Plate Size in 194	Lbs	Ker
	2PB42-9DB USA	3.9	2.5000 x 96.0000 x 240.0000			7,409
B21709-1	9C674D-602 USA	3.9	2.5000 x 96.0000 x 240.0000			
			Shipment Summary of Order	r 234453-06; 2 pieces 32,670	lbs (14,	,819 kg/

Chemical Analysis for Order 234453-06 (sorted by Heat)

	THE PARTY IN	OT OTHER	×24422-	ne (set	rea by H	eat)					
HeatAnlys	Neat	C	Mrs	P	ŝ	Si	Cu /	Ni.	Cr	Mo	Sn
	2P842	0.09	1.38	0.012	0.008	0.33	0.332	0.159	0.170	0.038	0.016
		A1	v	Nb/Cb	N	Alsol	Ti	В			01020
		0.012	0.12	0.00	0.006	0.011	0.002	0.0004			

BeatAnlys	Heat	C	Mn	Þ	S	Si.	Cu	Ni	Ćr I	Мо	fon
	9C674D	0.12	1.46	0.017	0.008	0.18	0.040	0.020	0.180	0.006	0.010
		Al	v	Nb/Cb	N	Alsol	Ti	В			
		0.033	0.14	0.00	0.006	0.000	0.002	0.0001			

Tensile Tests for Order 234453-06 (sorted by Heat)

		Gaug	Gauge Tens		ile Yield		Elongation		RA	Head						
Berial	Keat-Slab	Inches	3424	KSI	MPA	KSI						Tail		Norm	s/a	Tost ID
B20673~1	2P842-502	3.0000	76.20										Tran			315222
B20674-1	2P842-202	3.0000	76.20	78	536	56							Tran		-	315223
B21709-1	9C674D-602	2.5000	63.50	82						50			2ran		~	315788

Other Information for Order 234453-06

Material is 100% melted and manufactured in the USA. No weld repair has been performed.

Shipment Grand Totals of B/L 304559: 4 pieces 44,105 lbs (20,006 kg)

Unless otherwise specified, Mercury, radium or alpha source materials have not been used.

I certify the above results to be correct as contained in the records of the corporation.

Chief Metallurgist, David J. Cernava D. J. Gernava

1678 RED ROCK ROAD CES GERDAU

ST PAUL MN 55119 USA

(651) 731-5600

Chemical and Physical Test Report MADE IN UNITED STATES

M-116596

Marve Gerein/- Tampa Office Ptl. 1400-237-4230 PRODUCED IN: ST PAUL Medianizal Test: Clearliness Test Comments SOURCE (AAST) CASTRACI STRANG CAST. TO INDUSTRIES Mechanical Test Clearances Test HEAT LD. D317780 PRODUCED IN: ST PAUL Committee: BILISCOOL IN 328 + 3,0M6 CRYSTAL LAKE, IL 60012 4700 HALF MILE TRAIL WILD Red Fl 23.35 kd Dilanc 5.21 Contacion Index: 5.8 Red R 20.55 M Diam; 4.55 Corosion Index; 6.4 SOURCE ON-SILE CASTROL SELECTION CONSTRUCTION CONSTRUCTIO A110 K82 07 181 07 191 07 07 191 07 1 A1140 A22201 A23442504 C5 H3 C3 H3 C3 H3 C3 H3 C3 H3 C3 A231 A011 A141 A17 A22 A21401 A171 A22 A2140 A171 A22 A2140 A171 A22 A2140 A 9000 MINO / SALCHICALION SPECIFICATION **NYONCE TO** KAEHER STEEL COLLC MELROSE PARK, IL 60160 1550 NORTH ZETH AVE May V No N So N 10 10 20 20 20 Co SHP DATE 10/11/12 CUST, ACCOUNT NO Macro Elencis-2, R-2, C-2 SALES ORDER 2077240-01 SALES OFFICE CUST P.O. NUMBER CUST P.O. NUMBER

NO WILLO REPARAMENT PROVIDENCE. STEEL NOT EXPOSED TO MERCURY. This material, including the billion, was mailed and manufactured in the Chilad States of America.

Quality Director Badar Ysberechi

Gerdeu

markon

THE ABOVE FIGURES ARE CERTIFIED CHEMICAL AND PHYSICAL TEST RECORDS AS CONTAINED IN THE PERMANENT RECORDS OF COMPANY.

ST PAUL STEEL MILL Metahurgical Services Managor

Salar variets for all majorial turnished shall comply with specifications extinct installated menufactority excisions. NO OTHER WARRANTIES, EXPRESSED OR NAVIED, AFE MADE BY THE SELECT, AND SPECIFICALLY EXCLUSED ARE WARRANTIES OF MERCHARDULTY AND FRITESSE FOX A PAITHOUAN PARPOSE. In the event shall salar be liable for indirect of positive damagne uning out of or naturals to the installate has been in order to above the explorative to impost the major uning out of or naturals to the installate has been in order to above the explorative to impost the major that damagne for methods to the event in order to above the explorative to impost the major to be sold immediately after damagne in order to above the explorative to impost the major to be sold immediately after damagne in order to above the explorative to impost the major to be sold immediately after damagne in order to above the explorative to impost the major to be sold immediately after damagne in order to above the explorative to impost the major to be sold immediately after damagne in order to above the explorative to impost the major to be sold immediately after damagne in order to be explorated.



TC Industries Test Center 3703 South Route 31 Crystal Lake, IL 60012-1412 Telephone (815) 459-2400 Fax (815) 459-3419 TEST REPORT

REPORT NO: 164913 DATE: OCTOBER 28, 2012 PAGE 1 OF 1

BILL TO: KREHER STEEL CO.

1550 NORTH 25TH AVENUE MELROSE PARK, IL 60160

SHIP TO: KREHER STEEL CO.

1550 NORTH 25TH AVENUE MELROSE PARK, IL 60160

DESC: 272 PCS 1.152'RD X 24' PO: 1-120984							AT: M677107 : 2077240-01		-	RADE: A4				23130 84241
SPEC: QUENCH, TEMPER, STRAIGHTEN ASTM A193B7-11/F1554 GR105 S						5								
PROCESS:	FURN TEMPER STRESS	TE				TEN	URN TIME hh IPER TIME hh RESS TIME hh	umina:	.46 .48		QUENCH	; OIL		
PARAMETER	UNITS		LIMITS			TESTR	ESULTS	(8)	re sam	quing plea o	in back)			
TENSILE YIELD .2% ELONG 2" RED AREA FS YENS FS YLD ELONG 8" FS REDAREA CHARPY CVN TEMP SURFACE H8	KSI KSI % KSI KSI % FT-LB F		125.0 105.0 16.0 50.0 125.0 105.0 12.0 45.0 15	NYA NYA NYA 150.0 NYA NYA NYA NYA NYA NYA	/	131.0 114.0 18.0 56.0 129.0 114.0 17.0 59.0 80 -20 269	130.0 113.0 20.0 59.0	130.0 113.0 21.0 60.0 80		269	269	269		
CORE HB	HBW		0	321		285	285	285				_	2	1201-01

	TO INDUSTRIES AN	d BUBGGRTRAGTED LABS (AZLA ACGREDITED)	
Tensile, Standard TC		Rockwell	Micro Analysis
Tonelle, Full Size MSI		Brinett TC	Decarb Measure
Charpy V Notch TC		Ultra Sonie*	Chemistry*
Microhardness,Knoop*		Bend Test*	
TC: TC Test Center	BE: Barg Eng.	EX: Exova	MSI; Metallurgical Ser.
Cert #1281.01	Cart #L1157-1	Cort #104.02	Cert #0510.01
2/28/13	2/4/14	6/30/14	12/31/12

Time 14:55 DATE IN: 10/12/12 NOTES:

\*not included in our scope of accreditation

FC 4.12.16F 7/15/10

There are no deviations from test methods unless noted. It about out be assumed that mechanish properties of our methods head treated to a featurer standard will have the same properties of a finished featurer viscous original contents of contents of the method featurer in the same appropriate of the same standard featurer of the same



Mill certifica	Nec 3474	Pos.		
To Invoice No.	14400067	Delivery date	08.01.20	014

CON-TECH Systems Ltd.

FI-Order-No.

13206857

Destination

Canada

8150 River Road

CA-V4G 1B5 Delta, B.C.

Purchaser-Order no. 300951

Country of origin

Germany

Date of Order

06.12.2013

Supply plant

Ennepetal

User.

CON-TECH, Elizabethtown User-Order no.

## TITAN Hollow Bar 73/53 with continuous right-hand thread,

steel S 460 NH according to DIN EN 10210-1, height and shape of ribs according to DIN 488 (reinforcing bars), approx. 13,7733 kg/m in bundles of 50 pcs., packed with steel strappin surface untreated

Dimension			Q	Quantity		Total length in m		
O.D.			LD.	Length			kg	
73	mm	x	53 mm	3 m		300	12.396	900

## Results of the ladle analysis (S) %

Batch No.	C	SI	MN	P	S
3349301	0,194	0,466	1,49	0.014	0.0044

## Results of the tensile tests min.

Yield point Re 970 kN Ultimate load Rm 1160 kN

Results of thread testing

Thread is well running over the entire length and fits to the gauges

Friedt Ischeheck Cimbil

D. Grandjean (Manager of quality assurance Department)

Result of the pass through test

Internal section is free from high temperature oxidation and shavings

Further test requirements

The material conforms to the ordering requirements

 EN 14199:2005 Micropiles", 6.2.2.: "Steel bars for the reinforcement of concrete micropiles shall comply with EN 10080 and EN 10210"

 US Department of Transportation, Federal Highway Administration / FHWA, Hollow-Core Soil Nails, April 2006, requires ASTM A 615, which is fulfilled Hollow steel bars for reinforcement of Micropiles or Soil Nails acc. EN 14199:2008 "Micropiles" EN 14490:2010 "Soil Nailing"







# PACKING SLIP

802028/0001

Customer Code Order Number

Ship Date

ZZTELE 802028 Jan 9, 2014

www.contechsystems.com

1832 University Commercial Place Charlotte, NC 28213 Tel:(704) 494-3989 Fax: (704) 494-3990

Sold To:

TELECOMMUNICATIONS CONTRACTING

7900 Westpark Drive Suite A300 McLean VA 22102 USA

NEWTOWN-RT 25

Ship To:

HST # R1011275561

TELECOMMUNICATIONS CONTRACTING 2242 OLD MARLTON PIKE E.

MARLTON NJ 08053

Tel: 856-810-1658

		Tel: 856-810-1658					
PO Number Shipped Via		Shipped Via			Sale	s Rep	Nu.
411963	>	XPO LOGISTICS			806 - C	hris Love	
Item Number		Description		Qty Ordered	Qty Shipped	Qty Bk/ordered	UON
	CHANGE**	WN, CT ESTIMATED AND IS SUBJECT TO NG OUT OF CHARLOTTE**		<b>3</b>	V 4	0	EA
	Nut Dome T7:	Pallet With The for NEWTON 131670	1-14 1:1 a alove N RT	15 PM - 1 PM - 25	24 8 aterial	ه ل	EA EA
		131670					

Packed By	Checked By	Weight	No. of Packages
		1663,382 LBS	

Page 1 of 1



www.contechsystems.com

PACKING SLIP

802028/0002

Customer Code Order Number

Ship Date

ZZTELE 802028 Feb 4, 2014

HST # R1011275561

Sold To:

TELECOMMUNICATIONS CONTRACTING

7900 Westpark Drive Suite A300 McLean VA 22102 USA

Ship To:

TELECOMMUNICATIONS CONTRACTING 2242 OLD MARLTON PIKE E.

MARLTON NJ 08053

	161: 856-810-	1036					
PO Number Shipped Vi				Sale	s Rep		
411963	FedEx Freight		806 - Chris Love				
tem Number	Descriptio	n	Qty Ordered	Qty Shipped	Qty Bk/ordered	UON	
3-0122 Drill Bit	280mm Clay Hardened		0	1	0	EA	
from	Fed Ex on no - Dave	n I Paller	eu?				
Po	Neuloun R	t25			port condition	-	
- U	front of Red las	PO. Per Do	we camps	bell al	In de del	-	
	Red Tai	g on dir	mark				

124,000 LBS

Page 1 of 1

**Customer Copy** 

RUN DATE: 02/12/14 *** J.H. BOTTS, LLC. *** RUN TIME: 12:07:59	
PICKING	T T C K E T
ORDER-NO 68273 ORDER-DATE: 02/12/14	2/17
SOLD-TO: L C C Deployment Services, Inc. 5 7900 Westpark Drive Suite A300 McLean, VA 22102	HIP-TO: L C C Deployment Services, Inc 2242 Old Marlton Pike Marlton, NJ 08053
CUS-NO: LCCDSI PO-NO: 412143 TERMS	11DISC10-NET30 SALESMAN: JERRY
SHIP VIA: CALL WHEN READY SHIP DATE: 02/26/1 ITEM-NO DESCRIPTION 2	OTY CTY UNIT CTY RDERED TO SHIP WEIGHT SHIPPED
*T10105 U2 10-7x282 (182 Str) Fg[105	84.174
	18
FNDOMDHG10 10-7 HHNUt (Dom) GAV DH	76 16 .786
PHWMG10 10 HardenedWasher g F436	16 15 119 🗸
	The state of the s
*NOTE Clean cative length of the threaded rods of threaded rods of the threaded rods of t	
14 LINE ITEMS TOTAL OTY	46 TOTAL WEIGHT 183.150
COMPLETE 05. OZ127114 RT. IBUNDLE	PO # 412143 NE WTOWN RT 25 131670
	REC IN 3-4-14 3:45

May 02, 2014 Page 1 of 1



Po# 411962

Load No. 4415

# FOR NEWTOWN - RT 25 - 13167 Shipper No. 414477

Bill To LCC DEPLOYMENT SERVICES, INC 7900 WESTPARK DR. SUITE A300 MCLEAN, VA 22102

Ship To TELECOMMUNICATIONS CONTR.

customer pick up , NJ

Phone: 858-810-1658

Customer P.O. #, 411962	
Contract:	
Salas 1: Dayon Bala	

Terms: 1/2% 10 DAYS NET 30

Sales Order No: 414477 F.O.B.: Delivered Sales 2: Devon Bole

Due Date: 4/30/14 Ship Via: Our Truck

Ship Pcs 4

4

Description PL 2 1/2 A572-50 A572-50

Length

Weight 16" 726

center hole burnt to sketch

Totals

726

Shipping Instructions:

Messages:

\*CERTS WITH TRUCK & EMAIL \*CONTACT TOM EXT 210 A/P CALLS 708-873-2322

PO# 411962 FOR NEWTOUN-RT 25.131670 Rec In 5.2.14

		4 Plates
Received By:	222	
Signature:	Date: MAY 0 2 2014	21/2 x 16" x 16"
Print Name:		-/2
Trailer #		

\*\*\*NOTICE: NO CLAIMS WILL BE ACCEPTED UNLESS NOTIFIED WITHIN 15 DAYS FROM SHIPMENT DATE \*\*\*

DRIVERS: COPY #1 -WAREHOUSE COPY-MUST GET CUSTMER SIGNATURE. #2- DRIVERS & #3 CUSTOMER'S COPY.

# **CONSTRUCTION**



LCC Deployment Services Inc. 2242 Old Mariton Pike, Mariton, NJ 08053 856-810-1658 (Ph) 856-810-1659 (Fax)

To: Crown Castle

Subject: Construction inspection

Site: Newtown RT 25 - 826222

June 16, 2014

Please be advised that all work was completed per drawings dated <a href="Mailto:08/20/2013"><u>08/20/2013</u></a> by Paul J. Ford Engineering, in accordance with industry standards and contract documents including modification drawings and specifications, state and local regulations, OSHA, and engineering standards. On-site cold galvanizing was applied in accordance with Crown ENG-BUL-10149.

Please let me know if you have any questions.

Thank you,

Keith A. Stackhouse Structural Construction Manager LCC Deployment Services

Reith a. Stackhouse

## 6.2.2 FOUNDATION INSPECTIONS

## Keith\_ Stackhouse

From: Kyle Thorpe

Sent: Thursday, June 26, 2014 5:16 PM

To: Keith\_ Stackhouse

Cc: Jorge Forsythe; Klaus Horsch; Rich Taschek; Stephen Teti

Subject: RE: Newtown RT 25, BU# 826222

Categories: Newtown RT 25 - 826222 - 131670

Hello Keith.

We can waive the foundation inspection requirement given the photo and concrete break tests. We still require the micropile installation documentation as stated in the MI checklist.

My direct number is (614)448-4168 if you ever need to contact me again.

Thank you,

Kyle Thorpe, E.I. Structural Designer

Main: (614) 221-6679 ext. 2168 Direct: (614) 448-4168 Email: kthorpe@pifweb.com




>>> Keith\_Stackhouse <keith\_stackhouse@lcc.com> 6/26/2014 4:32 PM >>> Hello Kyle,

I tried giving you a call to discuss this site,

The MI checklist is as asking for a foundation inspection, the crew installed the concrete cap to micro piling without getting an inspection; they collected concrete samples for break testing. I attached the report for your review, can we have the foundation inspection waved off the MI check list.

See photo attached



Thanks,

## Keith A. Stackhouse Structural Construction Manager



LCC Deployment Services 2242 Old Marlton Pike Marlton,NJ 08053

(Cell) 609-367-6107 keith stackhouse@lcc.com

# 6.2.3 CONCRETE COMP. STRENGTH AND SLUMP TESTS

			Job No.:	160	059	Project:		lewton Rt 25	
Lipping	cott Ja	cohe	Report No.:			Location:			
	CONSULTING		Engineer:			Client:	LCC De	ployment Ser	vices
						Contractor:			
Locatio	on of Material:	AS	ROUT CO	OMPRESS -143, C-511, C	IVE STRE 2-617, C-1010	ENGTH TE 9, C-1064, C-	EST 1093		
	Date Cast:	5/21/14							
I.D. No.	Client I.D. No.	Age of Specimen (Days)	Date Tested	Specimen Size (Ø x H) (In.)	Area of Specimen (In.2)	Maximum Load (Lbs.)	Compressive Strength (PSI)	Type of Fracture	% of Design Strength
1		30	6/20/14	4x8	12.57	60,170	4,790	4	191.6%
2		30	6/20/14	4x8	12.57	56,970	4,530	4	181.2%
					30	Day Avg.:	4,660		186.4%
	equired (PSI):		00					Time Cast	
	of Concrete: sign Number:							Slump (In.) Air Content	
	sign Number: Manufacturer:						Concrete Temp		
	lant Location:						Ambient Temp		
	ruck Number:						Unit W	eight (PCF)	
Ti	cket Number:						Defect in Cy		
	Admixtures:								

## Sketches of Types of Fracture

Field Technician: Lab Technician:


1 N Pavilion Ave Riverside, NJ 08075 (856) 461-1100 (P) (856) 461-3166 (F) www.ljce.net



Job No.:	16059	Project:	Newton Rt 25
Report No.:		Location:	
Engineer:		Client:	LCC Deployment Services
		Contractor	

# GROUT COMPRESSIVE STRENGTH TEST ASTM C-39, C-143, C-511, C-617, C-1019, C-1064, C-1093

	Date Cast:	5/22/14							
I.D. No.	Client I.D. No.	Age of Specimen (Days)	Date Tested	Specimen Size (Ø x H) (In.)	Area of Specimen (In.²)	Maximum Load (Lbs.)	Compressive Strength (PSI)	Type of Fracture	% of Desig Strength
3		29	6/20/14	4x8	12.57	55,700	4,430	4	177.2%
	equired (PSI):		00					Time Cast	
Class	of Concrete:		00					Slump (In.)	
Class Mix De	of Concrete: sign Number:		00					Slump (In.) Air Content	) :
Class Mix De Concrete I	of Concrete: sign Number: Manufacturer:		00				Concrete Temp	Slump (In.) Air Content erature (*F):	) :
Class Mix De Concrete I P	of Concrete: sign Number: Manufacturer: lant Location:		00				Concrete Temp Ambient Temp	Slump (In.) Air Content erature (*F) erature (*F)	:
Class Mix De Concrete I P	of Concrete: sign Number: Manufacturer:		00				Concrete Temp Ambient Temp	Slump (In.) Air Content erature (*F): erature (*F): eight (PCF):	:



## Sketches of Types of Fracture

Field Technician: Lab Technician:


> 1 N Pavilion Ave Riverside, NJ 08075 (856) 461-1100 (P) (856) 461-3166 (F) www.ljce.net




Job No.:	16059	Project:	Newton Rt 25
Report No.:		Location:	
Engineer:		Client:	LCC Deployment Services
		Contractor:	


# GROUT COMPRESSIVE STRENGTH TEST ASTM C-39, C-143, C-511, C-617, C-1019, C-1064, C-1093


	Date Cast:	5/23/14							
I.D. No.	Client I.D. No.	Age of Specimen (Days)	Date Tested	Specimen Size (Ø x H) (In.)	Area of Specimen (In.²)	Maximum Load (Lbs.)	Compressive Strength (PSI)	Type of Fracture	% of Desig Strength
4		28	6/20/14	4x8	12.57	59,410	4,730	4	189.2%
	equired (PSI):		00					Time Cast	
Class	of Concrete:		00					Slump (In.)	
Class Mix De	of Concrete: sign Number:		00					Slump (In.) Air Content	
Class Mix De Concrete I	of Concrete: sign Number: Manufacturer:		00				Concrete Temp	Slump (In.) Air Content erature (*F)	:
Class Mix De Concrete I	of Concrete: sign Number: Manufacturer: lant Location:		00				Concrete Temp Ambient Temp	Slump (In.) Air Content berature (*F) berature (*F)	) : :
Class Mix De Concrete I Pi	of Concrete: sign Number: Manufacturer:		00				Concrete Temp Ambient Temp	Slump (In.) Air Content perature (*F): perature (*F): leight (PCF):	













Sketches of Types of Fracture

Field Technician: Lab Technician:

> 1 N Pavilion Ave Riverside, NJ 08075 (856) 461-1100 (P) (856) 461-3166 (F) www.ljce.net

5853345042

MICROTEL HENRIETTA

PAGE 03/04




## TELECOMMUNICATIONS CONTRACTING CO., INC 2242 OLD MARLTON PIKE MARLTON, NJ 08053 856-810-1658 FAX 856-810-1659

## DRILLERS LOG

	PROJECT NAME:	Durtuun	R+25		TEMPERATURE 57	
	SITE NUMBER:	171670			WEATHER SCHOOL	
		4-14 id Compl	و أا		DRILL UNIT TYPE DTH TOP HEAD ORIFTER ROTARY  DRILL UNIT Pump type Oberman chemgrost schwing Maco	
	LOCATION OR PILE PILE NUMBER	TYPE OF CONTECH		FINISH DEPTH	TIME IN COMMENTS	
Example	\$	103/78	8000 PSI GRADE LEVEL	65'	SOFT MATERIAL THEN HIT COBBLES AT 50° AND SWITCHE TO THE DRIFTER DRILL TO ACHIEVE FINAL DEPTH	D
	1	77.	Portland ++TT Gowle	24	Sand Sand had at July	_
	ı	77	Portland break	34	Soft Califes. 20'	
	J.	77	Portland Grade Level	34	hand at es	
			Level			
	4	77	Portland	γc	hard at 47	
						-
		<u> </u>				_
	Deller Scharung					

Newtown Rt 25



37513-1642 PERMIT.DW

## MONOPOLE REINFORCEMENT AND RETROFIT PROJECT

BU NUMBER; SITE NAME
BU #826222; NEWTOWN/RT-25

APP: 180205 REV. 3; WO: 600035

SITE ADDRESS

# 201 MAIN STREET NEWTOWN, CT 06470 FAIRFIELD COUNTY

## PROJECT NOTES

- I. DETAILED FIELD INFORMATION REGARDING INTERFRENCES AND/OR EXISTING FIELD CONDITIONS MAY BE AVAILABLE ON CROWN'S CCISITES AND FROM CONTRACTOR'S PRE-MOD MAPPING. IT IS THE CONTRACTOR'S RESPONSIBILITY TO FIELD VERIFY ALL EXISTING CONDITIONS AND DIMENSIONS AND COORDINATE WITH THE AVAILABLE SOURCES OF INFORMATION ABOVE AND WITH THE PROJECT PLANS BEFORE PROCEEDING WITH THE WORK. CONTRACTOR SHALL IMMEDIATELY REPORT ANY AND ALL DISCREPANCIES TO PAUL J. FORD AND COMPANY AND CROWN CASTLE FIELD PERSONNEL BEFORE PROCEEDING WITH THE WORK.
- ALL STRUCTURAL BOLTS SHALL BE INSTALLED AND TIGHTENED TO THE PRETENSIONED CONDITION ACCORDING TO THE REQUIREMENTS OF THE AISC "SPECIFICATION FOR STRUCTURAL JOINTS USING HIGH-STRENGTH BOLTS", DEC. 31, 2009.
- ALL STRUCTURAL BOLTS SHALL BE FIELD INSPECTED ACCORDING TO THE REQUIREMENTS OF THE AISC "SPECIFICATION FOR STRUCTURAL JOINTS USING HIGH-STRENGTH BOLTS", DEC. 31, 2009.

## PROJECT CONTACTS:

## MONOPOLE OWNER:

CROWN CASTLE 8 PARKMEADOW DRIVE, PITTSFORD, NY 14534 CONTACT: STEVE TUTTLE PH: (585) 899-3445

## STRUCTURAL ENGINEER OF RECORD (EOR):

PAUL J. FORD AND COMPANY
250 EAST BROAD STREET, SUITE 600
COLUMBUS, OHIO 43215-3708
CONTACT: KYLE THORPE AT KTHORPE@PJFWEB.COM
PHONE: 614-221-6679

### DESIGN STANDARD

THIS REINFORCEMENT DESIGN IS BASED UPON THE REQUIREMENTS OF THE TIAJEIA-222-F-1996 STRUCTURAL STANDARD FOR ANTENNA SUPPORTING STRUCTURES AND ANTENNAS, USING A DESIGN BASIC WIND SPEED OF 85 MPH (FASTEST MILE) WITH NO ICE, 37.6 MPH WITH 34 INCH ICE AND 50 MPH SERVICE LOADS.

REFER TO THE POLE DESIGN AND ANTENNA LOADING DOCUMENTED IN THE PJF STRUCTURAL ANALYSIS FOR THIS SITE (PJF#37513-1642), DATED 8-20-2013.

## THIS PROJECT INCLUDES THE FOLLOWING REINFORCING ELEMENTS:

FOUNDATION AUGMENTATION: MICROPILES

SHEET INDEX				
SHEET NUMBER	DESCRIPTION			
T-1	TITLE SHEET			
S-1	GENERAL NOTES			
S-2	GENERAL NOTES			
S-3	MONOPOLE PROFILE			
S-4	FOUNDATION REINFORCING DETAILS			
S-5	MI CHECKLIST			



ASBUILT 5-26-14 R.S.T. LCC DEPLOYMENT

All highest between the comment and All highest between the comment and the data exclusived treasure, by a procincy to Fay J. 1-bys and Company, steeder to stript condensors and that leave, vibercular to partie withon portilized and of Yau J. Fordi and Company, but improved procincy and of the ray purpose other time the mondal for any purpose other time the hardward and by the region of the ray.

PAUL J. FORD AND COMPANY STRUCTURAL ENGINEERS 200 Gast Rinas Street - Suite 600 - Colambus, Cris 42015 (8/14) 2211-6879 www.g/furth.com

BU #826222; NEWTOWN/RT-25 NEWTOWN, CT

MONOPOLE REINFORCEMENT AND RETROFIT PROJECT

PROJECT No: 37513-1642 DRAWN BY: B.M.S. CHECKED BY: K.A.T. APPROVED BY:

ISSUE DATE OF PERMIT: 8-20-2013

T-1

CROWN CASTLE PROJECT: BU #826222; NEWTOWN/RT-25; NEWTOWN, CT MONOPOLE RETROFIT PROJECT MASTER NOTES DOCUMENT (REV. 2, 1/22/2009)

CROWN OSSTLE PROJECT: BU BRJESCY. NEWTOWNRT-S. NEWTOWN, CT
MONOPOLE RETRORT PROJECT MASTER NOTES DOCUMENT (NEW 2, 122/2039)

A. GENERAL NOTES

A. GENERAL NO

8. (SECTION NOT USED)

C. SPECIAL INSPECTION AND TESTING
ALL WOORK SHALL BE SULECT TO REVIEW AND OBSERVATION BY THE OWNERS REPRESENTATIVE AND
THE COMMENS AUTHORIZED INDEPENDENT RISPECTION AND TESTING AGENCY. REFER TO CROWN
THE COMMENS AUTHORIZED INDEPENDENT RISPECTION AND TESTING AGENCY. REFER TO CROWN
ANY SUPPORT SERVICES PERFORMED BY THE ENGRIERER OURING CONSTRUCTION SHALL BE
DISTINGUISHED FROM CONTINUOUS AND DETAILED INSPECTION. SERVICES WHICH ARE FURNISHED BY
OTHERS. THESE SUPPORT SERVICES PERFORMED BY THE ENGRIERER ARE PERFORMED SOLIELY FOR
THE PURPOSE OF ASSISTED IN COLUMN TO TRICK AND IN A DEVINE COMPONINCE WITH CONTINUOUS
CONSTRUED AS SUPERVISION OF CONSTRUCTION.
OSSERVED DISCORPANCIES BETWEEN THE WORK AND THE CONTRACT DOCUMENTS SHALL BE
CORRECTED BY THE CONTRACTOR AT NO ADDITIONAL COST.
AN INDEPENDENT COLLIFIED BESPECTION TESTING AGENCY SHALL BE SELECTED, RETAINED AND PAID
FOR BY THE OWNER HOW THE SOLE PURPOSE OF INSPECTING, TESTING, DOCUMENTING, AND
APPROVING AUTHORISM OF PURPOSE OF INSPECTING, TESTING, DOCUMENTING, AND
APPROVING AUTHORISM OF THE DEVINE PERFORMENT OF THE OWNER FOR THE
OWNER HOW THE SOLE PURPOSE OF INSPECTING, TESTING, DOCUMENTING, AND
APPROVING AUTHORISM OF THE DEVINE PERFORMENT OF THE OWNER FOR THE THE SOLE PURPOSE
OF THE OWNER HOW THE SOLE PURPOSE OF INSPECTING THE OWNER FOR THE THE SOLE PURPOSE
OF THE OWNER HOW THE SOLE PURPOSE OF THE OWNER FOR THE OWNER THE THE THE OWNER AND THE OWNER FOR THE OWNER THE THE TESTING AGENCY SHALL BY
THE OWNER HOW THE SOLE PURPOSE OF THE OWNER THE TESTING AGENCY SHALL BY
ADDITIONAL OUT THE CONTRICTION DEALERS AND THE TESTING AGENCY SHALL BY
THE MERSON OF THE OWNER THE TESTING AGENCY SHALL BY THE POPENCIAL THE FORM THE FORM THE TESTING AGENCY SHALL BY THE TESTING AGENCY SH

AND COMMENSURATE WITH THE SCOPE AND TYPE OF INSPECTION WORK TO BE PERFORMED.

A. EENERAL.

DEFINION OCCUMENTURS ON OSITE COSSERVATION, INSPECTION, VERFICATION, AND TESTING DEFINING THE TIME THE CONTRACTOR IS WORKING ON-SITE. AGENCY SHALL NOTIFY CWINER IMMEDIATELY WHEN FILE PROBLEMS OR DISCREPANCIES OCCUR.

B. FOUNDATIONS, CONCRETE, AND SOL PREPARATION. (AND TREQUISED)

C. CONCRETE TESTING PER ACT. (NOT REQUIRED)

TO CONCRETE TESTING PER ACT. (NOT REQUIRED)

TO CONCRETE TESTING PER ACT. (NOT REQUIRED)

TO CONCRETE TESTING PER ACT. (NOT REQUIRED)

C. CHECK MILL CERTIFICATIONS.

C. CHECK MILL CERTIFICATIONS.

C. CHECK GRADE OF STEEL MEMBERS, AND BOLTS FOR CONFORMANCE WITH DRAWINGS.

A. CHECK GRADE OF STEEL MEMBERS, AND BOLTS FOR CONFORMANCE WITH DRAWINGS.

A. CHECK GRADE OF STEEL MEMBERS, AND BOLTS FOR CONFORMANCE WITH DRAWINGS.

A. CHECK GRADE OF STEEL MEMBERS, AND BOLTS FOR CONFORMANCE WITH DRAWINGS.

A. CHECK GRADE OF STEEL MEMBERS, AND BOLTS FOR CONFORMANCE WITH DRAWINGS.

A. CHECK GRADE OF STEEL MEMBERS FOR DISTORTION DOUBT.

A. CHECK STEEL MEMBERS FOR SIZES, SWEEP AND DIMENSIONAL TOLERANCES.

A. CHECK BOLT TIGHTENING ACCORDING TO ASSC TURN OF THE NUT! METHOD.

E. WELDING, (NOT REQUIRED)

E. D. CHECK DUC! TIGHTEN AND ASSESSED AS A STATE OF A S

TIL COMPILE AND PERCOUCALLY SUBMIT DALLY INSPECTION REPORTS TO THE OWNER.

THE INSPECTION PLAN OUTLINED HERBING INTENDED AS A DESCRIPTION OF GENERAL AND SPECE OF THIS OF CONCERN. IT IS NOT INTENDED TO BE ALL-INCLUSIVE. IT DOES NOT USE! THE TESTING AND REQUIRED AND SHOULD BE ANTICIPATED. THE TESTING AGENCY SHALL USE THEIR PROFESSIONAL JUGGMENT AND KNOWLEDGE OF THE JOS STICCE CONDITIONS AND THE CONTINGIOUS PERFORMANCE TO DECIDE WHAT OTHER TEMS REQUIRE ADDITIONAL ATTENTION. THE TESTING AGENCYS JUGGMENT MUSS FREVAL ON TIEMS ON SECRETARIOS SAMP PROBLEMS. SHALL BE BROUGHT IMMEDIATELY TO THE OWNERS ATTENTION. RESOLUTIONS ARE NOT TO BE ASKE WITHOUT DETERMINED WHAT OTHER CONTINGION OF SECRETARIOS SAMP PROBLEMS. SHALL BE BROUGHT IMMEDIATELY TO THE OWNERS ATTENTION, RESOLUTIONS ARE NOT TO BE ASKE WITHOUT DETERMINE WHAT IS AN ACCITION, THE TESTING AGENCY WILL PREPARE A WRITTEN ACCEPTANCE OR REJECTION WHICH MUS BE GIVEN TO THE CONTRACTOR AND FILED AS DAN PROPERTS TO THE CONTRACTOR A LIST OF TEURS TO BE CORRECTED, PRIDE TO SOME MUST AND ADDITIONS. THE CONTRACTOR A LIST OF TEURS TO BE CORRECTED, PRIDE TO STATUTIONS. THE CONTRACTOR A LIST OF TEURS TO BE CORRECTED, PRIDE TO STATUTIONS. THE CONTRACTOR A LIST OF TEURS TO BE CORRECTED, PRIDE TO STATUTIONS. THE CONTRACTOR HAS THE SOLE RESPONSIBILITY FOR MY DEWALTONS FROM THE OPPORTUNITY OF THE CONTRACTOR HAS THE SOLE RESPONSIBILITY FOR MY DEWALTONS FROM THE OPPORTUNITY OF THE CONTRACTOR HAS THE SOLE RESPONSIBILITY FOR MY DEWALTONS FROM THE OPPORTUNITY OF THE CONTRACTOR HAS THE SOLE RESPONSIBILITY FOR MY DEWALTONS FROM THE OPPORTUNITY OF THE CONTRACTOR HAS THE SOLE RESPONSIBILITY FOR MY DEWALTONS FROM THE OPPORTUNITY OF THE TESTING AGENCY WILL NOT REPLACE THE CONTRACTOR HAS THE THE TESTING AGENCY WILL NOT REPLACE THE CONTRACTOR THE TESTING AGENCY WILL NOT REPLACE THE CONTRACTOR THE TESTING AGENCY WILL NOT REPLACE THE CONTRACTOR THE CONTRACTOR HAS THE THE TESTING AGENCY WILL NOT REPLACE THE CONTRACTOR THE CONTRACTOR THE TESTING AGENCY WILL NOT REPLACE THE CONTRACTOR THE CONTRACTOR TH



**ASBUILT 5-26-14** R.S.T. LCC DEPLOYMENT

PAUL J. FORD AND COMPANY STRUCTURAL ENGINEERS 200 Date Touck Street - Suite (00) - Columbias, Orio 43315 (1) 14) 221-1-875 CROWN CASTLE B PARKMEADOW DRIVE, PITTSFORD, NY 14534 PK: (585) 589-3445 FAX: (585) 689-3446

BU #826222; NEWTOWN/RT-25 NEWTOWN, CT

MONOPOLE REINFORCEMENT AND RETROFIT PROJECT

37513-1842 СНЕСКЕО ВУ

ISSUE DATE OF PERMIT: 8-20-2013

PH BY

S-1

- 2

- 7.
- 8.
- 10.
- (A.)
- STRUCTURAL STEEL

  STRUCTURAL STEEL

  STRUCTURAL STEEL

  STRUCTURAL STEEL

  STRUCTURAL STEEL

  TO YET THE AMERICAN INSTITUTE OF STEEL CONSTRUCTOR. BETALING, AND WORKMANSHIP SHALL CONFORM
  TO YET AMERICAN INSTITUTE OF STEEL CONSTRUCTOR. 1805.

  (A) THE AMERICAN INSTITUTE OF STEEL COLOR. 1907.

  APPROVED BY THE RESEARCH COUNCIL ON STRUCTURAL CONNECTIONS OF THE

  SPECIFICALLY EXCLUDED.

  SPECIFICALLY EXCLUDE (B.)
- (C.)

### E. BASE PLATE GROUT - (NOT REQUIRED)

- BASE PLATE GROUT (NOT REQUIRED)

  FOUNDATION WORK
  THE CONTRACTOR SHALL PROTECT THE EXISTING MONOPOLE STRUCTURE. AS WELLAS ANY OTHER
  FOUNDATION WORK
  THE CONTRACTOR SHALL PROTECT THE EXISTING MONOPOLE STRUCTURES OR FOUNDAMENT. FROM LOSS OF SOIL
  AROUND AND/OR BERKEATH FOOTINGS DURING ANY REQUIRED EXCAVATION. THE CONTRACTOR
  SHALL BRACE THE SIDES OF THE OPEN EXCAVATION AS REQUIRED.
  THE EFFECT OF ADDITIONAL EXCAVATION WHERE REQUIRED FOR THE NEW MAT FOOTING (WHERE
  REQUIRED) OF OTHER FOUNDATION AUADIENTATION AND REPROPOCING (WHERE REQUIRED) MAY
  HAVE IMPACT ON EXISTING EQUIPMENT AND/OR OTHER EXISTING STRUCTURES NEAR THE
  EXCAVATION. IN ENGINEEROF. RECORD HAS NOT BEEN PROVIDED WITH ANY SPECIFIC INFORMATION
  OR DETAILS REGARDING EXISTING EQUIPMENT OR OTHER EXISTING STRUCTURES ON THE SITE. IT
  STRUCTURES. CONTRACTOR SHALL COORDINATE THIS STRESPECIFIC INFORMATION WITH THE
  OWNER AND TESTING ABOUT PRIOR TO CONSTRUCTION AND FOUNDAMEN AND TESTING ABOUT PRIOR TO CONSTRUCTION AND FOUNDAMEN AND TESTING ABOUT PRIOR TO CONSTRUCTION AND FOUNDAMEN WHITH THE
  OWNER AND TESTING ABOUT PRIOR TO CONSTRUCTION AND FOUNDAMEN ON WORK THE
  CONTRACTOR SHALL ADEQUATELY BRACE, SHORE, AND/OR RELOCATE (AFTER OBTAINING THE
  PRIOR WRITTED PREMISSION OF THE OWNER, AND AND FOUNDAMEN ON WORK THE
  PROOR WRITTED PREMISSION OF THE OWNER, AND AND FOUNDAMEN ON WORK THE
  PROOR WRITTED PREMISSION OF THE OWNER, AND RECORDANT OR WORK THE
  PROOR WRITTED PREMISSION OF THE OWNER, AND RECORDANT OR WORK THE
  PROOR WRITTED PREMISSION OF THE OWNER, AND RECORDANT OR WORK THE
  PROOR WRITTED PREMISSION OF THE OWNER, AND RECESSARY, THE INTERFERING EXISTING NEARBY
  EQUIPMENT AND/OR STRUCTURES.

- CAST-NAPLAGE COMPRETE

  CONDICINE TAX AND HAVE TRIMINAUM COMPRESSING STRENGTH OF 4000 PS. AT 26 DAYS.

  CONDICINE TAX AND HAVE TRIMINAUM COMPRESSING STRENGTH OF 4000 PS. AT 26 DAYS.

  CONTROLLED THE AND AS 25 MAXIMALII.

  ALL REINFORCING STEEL SHALL BE NEW DOMESTIC DEFORMED BILLET STEEL CONFORMING TO ASTM A615 GAPADE 60.

  ALL COMPRETE WORK SHALL BE IN ACCORDANCE WITH "THE BUILDING CODE REQUIREMENTS FOR REINFORCING CONCRETE" AG 315, LATEST EDITION.

  CONTRACTOR SHALL FOLLOW ALL APPLICABLE AD PROCEDURES FOR COLO WEATHER CONCRETE.

  ALL REINFORCION DETAILS SHALL COMPORT OF MANUAL OR STANDARD PRACTICE FOR CETAILING.

- 12.
- REINFORCED CONCRETE" ACI 318, LATEST EDITION
  CONTRACTOR SHALL FOLLOW ALL APPLICABLE ACI PROCEDURES FOR COLD WEATHER CONCRETE PLACEMENT.

  REINFORCED CONCRETE STRUCTURES ACI 316,
  ALTEST EDITION, UNESS DESIALS SHALL COMPOSED TO TO MANUAL OF STANDARD PRACTICE FOR CETALING REINFORCED CONCRETE STRUCTURES ACI 316.
  ALTEST EDITION, UNESS DETAILED OTHERWISE ON THE STRUCTURAL DRAWMAGS,
  CONTRACTOR SHALL VERIFY LOCATIONS OF ALL OPENINGS, SLEEVES, ANCHOR ROOS, INSERTS,
  ETC., AS REQUIRED BEFORE CONCRETE IS PLACED.
  WHERE BAR LENGTHS ARE GIVEN ON THE DRAWMAGS, THE LENGTH OF ANY HOOK, IF REQUIRED, IS NOT INCLUDED.
  CONTRACTOR SHALL PROMISE SPACES, CHARS, SOLISTERS, ETC., NECESSARY TO SUPPORT
  ON TIMELODE.
  CONTRACTOR SHALL PROMISE SPACES, CHARS, SOLISTERS, ETC., NECESSARY TO SUPPORT
  ON THE CONCRETE SUPPOSED.
  ALL STRUCTURAL MEMBERS SHALL BEFORE DISCONSTRUCTION JOINTS. CONTRACTOR SHALL PROMISE PROMISED AND CONSTRUCTION JOINTS. CONTRACTOR SHALL SUBMIT
  PROPOSED CONSTRUCTION JOINT LOCATIONS AND DETAILS TO THE ENGINEER FOR REVIEW.
  CONTRACTOR SHALL PROMISE SHANCH CHARMER ON ALL SEPOSED CONSERS UNLESS OTHERWISE MICHAEL SHANCH SHANCH

### EPOXY GROUTED REINFORCING ANCHOR RODS - (NOT REQUIRED)

TOUCH UP OF GALVANIZING - (NOT REQUIRED)

HOT DIP GALVANIZING - (NOT REQUIRED)

PERPETUAL INSPECTION AND MAINTENANCE BY THE DWINER.
AFTER THE CONTRACTOR THAS SUCCESSFULLY COMPLETED THE INSTALLATION OF THE MONOPOLE REINFORCING SYSTEM AND THE WORK HAS BEEN ACCEPTED BY THE OWNER, THE OWNER WILL BE RESPONSIBLE FOR THE LONG TERM AND PERPETUAL INSPECTION AND MAINTENANCE OF THE FOLL RESPONSIBLE FOR THE LONG TERM AND PERPETUAL INSPECTION AND MAINTENANCE OF THE FOLL THE MONOPOLE REINFORCING SYSTEM MONOPOLE THE STEEL MEMBERS TO THE EXISTING GALVANIZED STEEL POLE STRUCTURE. THESE FIELD WELDED CONNECTIONS ARE SUBJECT TO CORROSION DAMAGE AND DETERIORATION IF THEY ARE NOT PERPETUAL AND AND CONTROL OF THE STEEL OF THE STRUCTURAL LOND CARRYING AND AND THE STRUCTURAL LOND CARRYING CAPACITY OF THE RESPONSED DICLE SYSTEMS EDPENDENT UPON PREVENTIVE COATING SUCH AS THE ZER GALVANIZED COMPONENTS BE DEPENDENT UPON PREVENTIVE COATING SUCH AS THE ZER GALVANIZED COMPONENTS BE DEPENDENT UPON PREVENTIVE COATING SUCH AS THE ZER GALVANIZED COMPONENTS BE DEPENDENT UPON PREVENTIVE COATING SUCH AS THE ZER GALVANIZED COMPONENTS BE DEPENDENT UPON PREVENTIVE COATING SUCH AS THE ZER GALVANIZED COMPONENTS BE DEPENDENT UPON PREVENTIVE COATING SUCH AS THE ZER GALVANIZED COMPONENTS BE DEPENDENT UPON PREVENTIVE COATING SUCH AS THE ZER GALVANIZED COMPONENTS BE DEPENDENT UPON PREVENTIVE COATING SUCH AS THE ZER GALVANIZED COMPONENTS BE DEPENDENT UPON PREVENTIVE DEPENDENT UPON PREVENTIVE SUCH PREVENTIVE SUCH PREVENTIVE AND SUCH PREVENTIVE SUCH



AUG 2 1 2013

ASBUILT 5-26/14 R.S.T. LCC DEPLOYMENT

PAUL J. FORD AND COMPANY STRUCTURAL ENGINEERS 250 Bald Bried Street - Saide 600 - Collaridats, Orio 43101 (014) 221-8670 CROWN CASTLE

: (500) 899-3445


BU #826222; NEWTOWN/RT-25 NEWTOWN, CT


MONOPOLE REINFORCEMENT AND RETROFIT PROJECT

37513-1642 RMS

ISSUE DATE OF PERMIT: 8-20-2013

DATE: S-2






### MICROPILE NOTES:

- ALL HOLLOW BAR STEEL AND ASSOCIATED HARDWARE SHALL BE SUPPLIED BY CON-TECH SYSTEMS OR OWNER/GOR APPROVED EQUIVALENT
- 2. ALL HOLLOW BAR, NUTS AND BEARING PLATES SHALL SE HOT-DIP GALVANIZED PER ASTM A123 OR A153, AS APPROPRIATE.
- 1 CONTACT CONTECH SYSTEMS (OR MANUFACTURER OF APPROVED ALTERNATE) FOR MATERIALS AND INSTALLATION PROCEDURES AND RECOMMENDATIONS.

- 6. CONTACT CONTECH SYSTEMS (OR MANUFACTURER OF APPROVED ALTERNATE) TO VERBY NUT & WASHER CONNECTION ARE COMPATIBLE WITH MICROPILE THREADS.
- 7. ALL MICROPILE SHALL BE GROUTED FOR FULL HEXDIT. CRICUIT TO BE 4,000 PSI VIIN COMPRESSION STRENGTH WITH D.S (MAXIMUM WATERCEMENT) WIC HATIO (TO BE COLLODALLY MIXED FOR MICROPILE).

		PRELIMINAL	RY PILE DESIGN	PARAMETER	R SCHEDULE*		
OPTIONS PARAMETER	WIN. HOLE WISTEEL AREA	ALLOWABLE PILE CAPACITY (Nam)	ULTIMATE SKIN FRICTION (PSI)	FREE STRESS LENGTH	FRICTION DEVELOPMENT LENGTH BOYO LENGTH	ROCK SOCKET/ PLUNGE LENGTH	TOTAL EMBEDMENT LENGTH
MICROPILE	10.5% 2.53 IN <sup>2</sup> MIN	150K	SEE GEOTECH REPORT	5	27° MIN.	N.A.	33° MIN.

"THE FINAL GESIGN GROUT DAMETER IS BASED ON A NUMBER 225M AUGER IN SETY SAND. THE DESIGN REQUEST UNCASED VICKOPES FOR THE LISTED CAPACITY IN TENSION AND COMPRESSION AS LAD OUT PER PLAN. THE CONTRACTOR/MORDERLE INSTITUTE OF THE MEMORS AND CAPACITY FOR THE LISTED OF THE



NEW BEARING PLATE MK~BP1



ASBUILT 5-26-14 R.S.T. LCC DEPLOYMENT

**CROWN CASTLE** 

BU #826222; NEWTOWN/RT-25 NEWTOWN, CT

MONOPOLE REINFORCEMENT AND RETROFIT PROJECT

DRAWN BY: B.M.S. CHECKED BY KA.T.

ISSUE DATE OF PERMIT: 8-20-2013

DATE: 8-20-2013

S-5

### 77613-1642 PERMIT DWG

### NODIFICATION INSPECTION NOTES:

GENERIA, THE BOOKER OF THE BOOKER OF TOWER MODIFICATIONS AND AREYEM OF CONSTRUCTION INSPECTIONS AND AREYEM OF CONSTRUCTION INSPECTIONS AND CHERRESONE TO ENGINE THE INSTALLATION WAS CONSTRUCTED IN ACCORDANCE WITH THE CONTRACT DOCUMENTS, NAMELY THE MODIFICATION GRAWINGS, AS DESIGNED BY THE ENGINEERS OF PECONO (GOID).

ALL WIS SHALL BE COMDUCTED BY A CROWN ENGINEERING VENDOR (VEV) OR ENGINEERING SERVICE VENDOR (AESI) THAT IS APPROVED TO PERFORM ELEVATED WORK FOR CROWN. SEE ENGINE. HIT 2LET OF APPROVED M VENDORS.

TO BISJAR FAAT THE REQUIREMENTS OF THE MI ARE MET, IT IS WITAL THAT THE OBJERRAL CONTRACTOR (SQL) AND THE MI INSPECTION BEGIN COMMANDATING AND CONCRIMING AS SOCIALAD AND IS RECEIVED. IT IS EXPECTED THAT EACH PAINTY WILL BE PROMOTIVE REACHING OUT TO THE OTHER PAINT, IF COURTACT IN EXPONIANCIAL DISTORANCE, CONTRACT VIOUS CRIMINATION OF CONTRACT YOUR

REFER TO ENG-SOW-10007: MODIFICATION INSPECTION SOW FOR FURTHER DETAILS AND REQUIREMENTS.

MINISPECTOR THE UITNEECTOR IS REQUIRED TO CONTACT THE GCAS SOON AS RECEIVING A PO FOR THE MITO, AT A NAMMURE

 REVIEW THE REQUIREMENTS OF THE MICHECKLIST
 WORK WITH THE OC TO DEVELOP A SCHEDULE TO CONDUCT ON-SITE INSPECTIONS, INCLUDING FOUNDATION INSPECTIONS. THE MINISPECTOR IS RESPONSIBLE FOR COLLECTING ALL GENERAL CONTRACTOR (SC) INSPECTION AND TEST REPORTS, REMEMBING THE DOCUMENTS FOR ADHERENCE TO THE CONTRACT DOCUMENTS, CONDUCTING THE IN-FIELD INSPECTIONS, AND SUBJITTING THE MINEPORT

GENERAL CONTRACTOR
THE OLIS REQUIRED TO CONTACT THE MI INSPECTOR AS BOON AS RECEIVING A POPOR THE MODIFICATION INSTALLATION OR TUN
PROJECT OF A NUMBER

- EVEN THE RECUREMENTS OF THE MICHECULET FORM MITH THE MI REPECTION TO DEVILLOR A SOLEDULE TO CONDUCT ON-SITE INSPECTIONS, INCLIDING FOUNDATION INSPEC TITING RECORDS FOR ALL REPECTION AND TESTING REQUIREMENTS

THE GC SHALL PERFORM AND RECORD THE TEST AND INSPECTION RESULTS IN ADCORDANCE WITH THE REQUIREMENTS OF THE MI CHECKLIST AN INDING SOW, YOUR

RECOMMENDATIONS
THE FOLLOWING RECOMMENDATIONS AND SUGGESTIONS ARE OFFERED TO ENHANCE THE EFFICIENCY AND EFFECTIVENESS OF DELIVERING.

- AM REPORT:

  If IS SUSGISTED THAT THE GC PROVIDE A NINNAM OF SIBUSINESS DAYS HOTICE, PREFERABLE 16, TO THE MINOPECTOR AS TO WHEN THE SITE WAS BEEN AND THE MINOPECTOR AS TO WHEN THE SITE WAS BEEN AND THE MINOPECTOR AS TO WHEN THE SITE WAS BEEN AND THE SITE WAS BEEN

CANCELLA TRAILORS AND HIGH CONTRACTOR

"IT HIS CON ON HIGH CONTRACTOR AND THE SHIPPLE SECONDACTED, AND ETHER PARTY CANCELS OR CREATER, CHOOM
SHALL NOT THE RESPONSIBLE FOR HAY COSTS, HERS LOSS OF BEPORTS HANDOW OTHER HEARINGS HEALTHS OT THE CANCELLARISED ON
SHALL NOT THE RESPONSIBLE FOR HAY COSTS, HERS LOSS OF BEPORTS HANDOW OTHER HEALTH TO THE CANCELLARISED ON
SHALL NOT THE PROPERTY OF THE PRAFTY OF ANY THE FE OF A THANKE, AND LOOSED, COSTS OF RESPONSIBLE CANCELLARISED ON HEALTH COLLING THE CANCELLARISED ON HEALTH CONTRACTOR HAVE AND LOOSED, COSTS OF MERCHANIC PROPERTY HEALTH COLLING THE CANCELLARISED ON HEALTH CONTRACTOR HAVE AND LOOSED ON HEAD HAVE AND HAVE A

- CORRECT FALING ISSUES TO COMPLY WITH THE BPECIFICATIONS CONTAINED IN THE ORIGINAL CONTRACT DOCUMENTS AND
  COGREGATE A SUPPLICATION.
   OR, WITH CONVEYS APPROVAL, THE GC MAY WORK WITH THE EOR TO RE-ANALYZE THE MODIFICATION RENFORCEMENT LISTING THE
  AS-BULL CONCIDEN.

# M VENETICATION INSPECTIONS GROWN RESERVES THE WORLT TO COMPUCT A MY VERIFICATION INSPECTION TO VERIFY THE ACQURACY AND COMPLETENESS OF PROVIDENCE OUTPLETED HIS RECEIVABLE OF TOWER MODIFICATION PROJECTS.

ALL VERIFICATION INSPECTIONS SHALL BE HELD TO THE SAME SPECIFICATIONS AND REQUIREMENTS IN THE CONTRACT DOCUMENTS AND IN ACCORDANCE WITH ENG-SOW-10027.

VERFICATION INSPECTION MAY BE CONDUCTED BY AN INDEPENDENT ADMAESTY FRIM AFTER A MODIFICATION PROJECT IS COMPLETED, AS MARKED BY THE DATE OF AN ACCIPITED "PASSING ME" OR "PASS AS NOTED ME REPORT FOR THE ORIGINAL PROJECT.

PHOTOGRAPHS BETWEEN THE GC AND THE NEWSPECTOR THE FOLLOWING PHOTOGRAPHS, AT A MINIMUM, ARE TO BE TAKEN AND INCLUDED IN THE ME

- INSTRUCTION GENERAL SITE CONDITION PRAPHS DURING THE REINFORGEMENT INCOMPICATION CONSTRUCTION/ERECTION AND INSPECTION
- PRE-CONSISTENCY
  PROTOGRAPH'S DURBYD THE REINFORCE
  RAW MATERIALS
  PROTOS OF ALL CRITICAL DETALS
  COLIDATION MODIFICATIONS
  WELD PREPARATION
  BOLT PRISTALL FROM AND TORQUE
  FROM, INSTALLE COLUMN
  SUPPLICE COLUMN SEPARA
  SERVICE SERVICE TO SEPARA
  SERVICE SERVICE TO SERVICE SERVIC

HOTOS OF ELEVATED MODIFICATIONS TAKEN FROM THE GROUND SHALL BE CONSIDERED INADEQUATE

THIS IS NOT A COMPLETE LIST OF REQUIRED PHOTOS, PLEASE REFER TO ENG-SOW-10007.

	MI CHECKLIST
CONSTRUCTION/INSTALLATION INSPECTIONS AND TESTING REQUIRED (COMPLETED BY EOR)	REPORT ITEM
	PRE-CONSTRUCTION
×	MI CHECKLIST DRAWINGS
×	EOR APPROVED SHOP DRAWINGS
x	FABRICATION INSPECTION
NA	FABRICATOR CERTIFIED WELD INSPECTION
×	MATERIAL TEST REPORT (WTR)
NA	FARRICATOR NDE INSPECTION
NA.	NDE REPORT OF MONOPOLE BASE PLATE (AS REQUIRED)
x	PACKING SLIPS

ADDITIONAL TESTING AND INSPECTIONS: PRIOR TO CONSTRUCTION, CONTRACTOR SHALL SUBMIT PILE INSTALLATION AS TESTING PLAN TO CROWN AND PUF FOR REVIEW . TESTING PLAN SHALL INCLUDE DETAILS REGARDING HOW COST

	The second secon
TO PREVENT INTERACTION BETWEEN TO	HE TEST FILE AND THE EXISTING FOUNDATION DURING TESTING.
	CONSTRUCTION
ж	CONSTRUCTION INSPECTIONS
x	FOUNDATION INSPECTIONS
X	CONCRETE COMP. STRENGTH AND SLUMP TESTS
NA NA	POST INSTALLED ANCHOR ROD VERIFICATION
N/A	BASE PLATE GROUT VERIFICATION
NA.	CONTRACTOR'S CERTIFIED WELD INSPECTION
NA.	EARTHWORK: LIFT AND DENSITY
NA.	ON SITE COLD GALWANZING VERIFICATION
MA.	GUY WIRE TENSION REPORT
×	GC AS-BUILT DOCUMENTS
NA	THIRD PARTY ONSITE INSPECTION OF BOLT PRETENSION PER CROWN REQUIREMENTS
MA	INSPECTION OF AJAX BOLTS AND DIT'S PER REQUIREMENTS ON SHEET \$-3

ADDITIONAL TESTING AND INSPECTIONS: VERIFY MICROPILE INSTALLATION DETAILS, SPECIFICALLY INCROPILE SIZES, DRILL HOLE METERS & DEPTHS, GROUT FO AND THAT INSTALLATION WAS PER MANUFACTURER RECOMMENDATION

	POST-CONSTRUCTION	
x	MI INSPECTOR REQUIRE OR RECORD DRAWING(S)	
NA	THIRD PARTY ONSITE BOLT INSPECTION REPORT	
NA.	POST INSTALLED ANCHOR ROD PULL-OUT TESTING	
×	PHOTOGRAPHS	

ADDITIONAL TESTING AND INSPECTIONS: PROVIDE REPORT DOCUMENTING RESULTS OF MICROPILE INSTALLATION AND PROOF TESTING

NOTE: X DENOTES A DOCUMENT NEEDED FOR THE PM REPORT NA DENOTES A DOCUMENT THAT IS NOT REQUIRED FOR THE PM REPORT

OF COMME No. PEN 22731

AUG 2 1 2013

**ASBUILT 5-26-14** R.S.T. LCC DEPLOYMENT

PAUL J. FORD AND COMPANY STRUCTURAL ENGINEERS 256 Last Broad Street - Suffe 900 - Columbias, Orio 42315 www.glybreb.com **CROWN CASTLE** 

8 PARKMEADOW DRIVE, PITTSFORD, NY 14534 Pt. (88) 899-3445 FAX: (88) 899-3446

BU #826222; NEWTOWN/RT-25 NEWTOWN, CT

MONOPOLE REINFORCEMENT AND RETROFIT PROJECT

DRAWN BY: B.M.S CHECKED BY

ISSUE DATE OF PERMIT: 8-20-2013

S-6

### 7613-1642 PERMIT.DWG

# NODIFICATION INSPECTION NOTES:

GENERAL
THE MODIFICATION INSPECTION (MILES A VISUAL INSPECTION OF TOWER MODIFICATIONS AND A REVIEW OF CONSTRUCTION INSPECTIONS
AND OTHER REPORTS TO SHOURE THE RISTALLATION WAS CONSTRUCTED IN ACCORDANCE WITH THE CONTRACT DOCUMENTS, NAMELY THE
MODIFICATION CRAININGS, AS DESIGNED BY THE ENCHREER OF PECCHO (MOR).

ALL MTS SHALL BE CONDUCTED BY A CROWN ENGINEERING VENDOR (NEV) OR ENGINEERING SURVICE VENDOR (AESV) THAT IS APPROVED TO PERFORM ELEVATED WORK FOR CROWN. SEE ENGINE.-HITSLEST OF APPROVED IN VENDORS.

TO ENSURE THAT THE REQUIREMENTS OF THE NEARE MET, IT IS WITH, THAT THE OBJECTAL CONTRACTOR (SC) AND THE MENSPECTOR BEION COMMUNICATION AND COORDINATION AS SOON AS A POLS RECEPTED. IT IS EXPECTED THAT EACH PRITY WILL BE PROMOTIVE IN PREACHING OUT TO THE OTHER PRITY. IF CONTACT PROG.

REFER TO EMS-SOW-10007: MODIFICATION INSPECTION SOW FOR FURTHER DETAILS AND REQUIREMENTS.

MINISPECTOR THE UILNSPECTOR IS REQUIRED TO CONTACT THE OCAS SOON AS RECEIVING A PO FOR THE MITO, AT A NAMMUNI:

REVIEW THE REGUREMENTS OF THE MICHEOLUST
 WORK WITH THE OC TO DEVELOP A SCHEDULE TO CONDUCT ON-SITE INSPECTIONS, INCLUDING FOUNDATION INSPECTIONS.

THE MINISPECTOR IS RESPONSIBLE FOR COLLECTING ALL GENERAL CONTRACTOR (GC) INSPECTION AND TEST REPORTS, REVIEWING THE DOCUMENTS FOR ADHERENCE TO THE CONTRACT DOCUMENTS, CONDUCTING THE IN-FIELD INSPECTIONS, AND SUBJECTION THE MIREPORT

GENERAL CONTRACTOR
THE GCI IS REQUIRED TO CONTACT THE MINISPECTOR AS SOON AS RECEIVING A PO FOR THE MODIFICATION INSTALLATION OR TURKNEY
PROJECT TO, AT MAINIAGE.

- REVIEW THE RECURRENENTS OF THE IN CHECKLIST WORK WITH THE WI INSPECTOR TO DEVICE A SCHEDULE TO CONDUCT ON SITE INSPECTIONS, INCLUDING FOUNDATION INS SETTER INCRESS TWO ALL IMPECTION AND TEXTING REQUIREMENTS

THE GC SHALL PERFORM AND RECORD THE TEST AND INSPECTION RESULTS IN ACCORDANCE WITH THE REQUIREMENTS OF THE MI CHECOLIST AND DENGSOW, 1995?

RECOMMENDATIONS
THE FOLLOWING RECOMMENDATIONS AND SUGGESTIONS ARE OFFERED TO ENHANCE THE EFFICIENCY AND EFFECTIMENESS OF DELIMINARY

- If IS SUGGISTED THAT THE GC PROVIDE A NAMERIN OF 5 BUSINESS DAYS HOTICE PREFERRALE 16, TO THE MINORECTOR AS TO WHEN THE SITE WILL BE READY FOR THE MIT OF ECONOLINE. OF CONDUCTED.

  THE COLD, ON MERPECTAC COORDING CLOSELY THROUGHOUT THE ENTIRE PROJECT.

  THE COLD, ON MERPECTAC CROSS OF ONCE WE GO ALS MINORECTOR ON SITE SAULT AND OBSELY FOR ANY GUY WHE TENSIONED OR BRITEDOWN OF SPECIAL OR THROUGH OF PRACTICE AND THE COLD AND THE CONDUCTION FROM THE CONDUCTION F

CAMEDIA TO LICE OF A HOSPITATION OF A HOSPITATION OF WHICH THE MINNER RECORDS THE AND THE REPORT CAMEDIA OF COMMISSION OF THE COMMISSION OF INTERCOLOGICAL OF THE AND THE REPORT OF THE CAMEDIA OF THE REPORT OF THE CAMEDIA OF THE REPORT OF THE CAMEDIA OF THE AND THE REPORT OF THE CAMEDIA OF THE REPORT OF THE CAMEDIA OF THE REPORT OF THE CAMEDIA OF THE REPORT OF THE PROPERTY OF THE

CORRECTION OF FAILING MIS.

F THE MICHIGATION MISTALLATION WOULD FAIL THE MI ("FAILED MI"), THE GC SHALL WORK WITH CROWN TO COORDINATE A RE

- CORRECT FALING ISSUES TO COMPLY WITH THE SPECIFICATIONS CONTAINED IN THE ORIGINAL CONTRACT COCUMENTS AND
  COGNECATE A SUPPLEMENTAL.
   OR, WITH CROWN'S REPROVAL, THE GC MAY WORK WITH THE BOX TO RE-ANALYZE THE MODIFICATION REPROPEREMENT LISTING THE
  AS WILL COLORDION.

M VERBICATION INSPECTIONS
CROWN RESERVES THE ROBIT TO CONDUCT A M VERBICATION INSPECTION TO VERBY THE ACCURACY AND COMPLETENESS OF PROVINCIALY COMPLETED HIS SPECTION(S) ON TOWER MODIFICATION PROJECTS.

ALL VERIFICATION INSPECTIONS SHALL BE HELD TO THE SAME SPECIFICATIONS AND REQUIREMENTS IN THE CONTRACT DOCUMENTS AND IN ACCORDANCE WITH ENGACYM-10007

VERFICATION INSPECTION MAY BE CONDUCTED BY AN INDEPENDENT ARMAESY FRIM AFTER A MODIFICATION PROJECT IS COMPLETED, AS MARKED BY THE DATE OF AN ACCEPTED <u>"PASSING ME</u>" OR "PASS AS NOTED ME" REPORT FOR THE ORIGINAL PROJECT.

PHOTOGRAPHS
BETWEEN THE GC AND THE MILMSPECTOR THE FOLLOWING PHOTOGRAPHS, AT AMMINIUM, ARE TO BE TAKEN AND INCLUDED IN THE MI

- PRE-CONSTRUCTION GENERAL SITE CONCIDENT MODIFICATION CONSTRUCTIONARRECTION AND INSPECTION
  PROTOGRAPHS QUARMO THE REINFORCHMENT MODIFICATION CONSTRUCTIONARRECTION AND INSPECTION
  PROTOGRAPH CONCIDENT CONCIDENT
  PROFILE CONCIDENT
  P

HOTOS OF ELEVATED MODIFICATIONS TAKEN FROM THE GROUND SHALL BE CONSIDERED INADEQUATE.

THIS IS NOT A COMPLETE LIST OF REQUIRED PHOTOS, PLEASE REFER TO ENG-SOW-10007.

	MI CHECKLIST
CONSTRUCTION/INSTALLATION INSPECTIONS AND TESTING REQUIRED (COMPLETED BY EOR)	REPORTITEM
	PRE-CONSTRUCTION
x	MI CHECKLIST DRAWINGS
x	EOR APPROVED SHOP DRAWINGS
×	FABRICATION INSPECTION
NA.	FABRICATOR CERTIFIED WELD INSPECTION
×	MATERIAL TEST REPORT (MTR)
NA.	FAIRICATOR NDE INSPECTION
NA.	NDE REPORT OF MONOPOLE BASE PLATE (AS REQUIRED)
х	PACKING SLIPS

ADDITIONAL TESTING AND INSPECTIONS: PRIOR TO CONSTRUCTION, CONTRACTOR SHALL SUBMIT PILE INSTALLATION AND TESTING PLAN TO CROWN AND PUF FOR REVIEW . TESTING PLAN SHALL INCLUDE DETAILS REGARDING HOW CONTRACTOR INT

	The state of the s
TO PREVENT INTERACTION BETWEEN TO	HE TEST PILE AND THE EXISTING FOUNDATION DURING TESTING.
	CONSTRUCTION
х	CONSTRUCTION INSPECTIONS
X	FOUNDATION INSPECTIONS
х	CONCRETE COMP. STRENGTH AND SLUMP TESTS
NA NA	POST INSTALLED ANCHOR ROD VERIFICATION
NA.	BASE PLATE GROUT VERIFICATION
NA.	CONTRACTOR'S CERTIFIED WELD INSPECTION
NA.	EARTHWORK: LIFT AND DENSITY
PAA.	ON SITE COLD GALWANZING VERIFICATION
MA	GUY WIRE TENSION REPORT
x	GC AS-BUILT DOCUMENTS
NA.	THIRD PARTY ONSITE INSPECTION OF BOLT PRETENSION PER CROWN REQUIREMENTS
NA.	INSPECTION OF A JAX BOLTS AND DTYS PER REQUIREMENTS ON SHEET \$-3

ADDITIONAL TESTING AND INSPECTIONS: VERIFY INCROPILE INSTALLATION DETAILS, SPECIFICALLY INCROPILE SIZES, ORILL HOLE

POST-CONSTRUCTION			
×	MINSPECTOR REDUKE OR RECORD DRAWING(S)		
NA NA	THIRD PARTY ONSITE BOLT INSPECTION REPORT		
NA.	POST INSTALLED ANCHOR ROD PULL-OUT TESTING		
	PURTOCO I PUR		

NAL TESTING AND INSPECTIONS: PROVIDE REPORT DOCUMENTING RESULTS OF MICROPILE INSTALLATION AND PROOF

NOTE: X DENOTES A DOCUMENT NEEDED FOR THE PM REPORT NA DENOTES A DOCUMENT THAT IS NOT REQUIRED FOR THE PM REPORT

OF CONNEC No. PEN 22731

ASBUILT 5-26-14 R.S.T. LCC DEPLOYMENT

PAUL J. FORD AND COMPANY STRUCTURAL ENGINEERS 250 East Broad Stront - Safe 900 - Columbias, Ohio 42215 www.glyhebic.com

AUG 2 1 2013

**CROWN CASTLE** 8 PARKMEADOW DRIVE, PITTSFORD, NY 14534 Pt. (88) 899-3445 FAX: (88) 899-3446 BU #826222; NEWTOWN/RT-25 NEWTOWN, CT

MONOPOLE REINFORCEMENT AND RETROFIT PROJECT

DRAWN BY: B.M.S CHECKED BY

ISSUE DATE OF PERMIT: 8-20-2013

# **POST-CONSTRUCTION**

# 6.3.1 MI INSPECTOR REDLINE OR RECORD DRAWING(S)

37513-1642 PERMIT.DW

# MONOPOLE REINFORCEMENT AND RETROFIT PROJECT



BU NUMBER; SITE NAME
BU #826222; NEWTOWN/RT-25

APP: 180205 REV. 3; WO: 600035

SITE ADDRESS

# 201 MAIN STREET NEWTOWN, CT 06470 FAIRFIELD COUNTY

# PROJECT NOTES

- 1. DETAILED FIELD INFORMATION REGARDING INTERFERENCES AND/OR EXISTING FIELD CONDITIONS MAY BE AVAILABLE ON CROWN'S CLISITES AND FROM CONTRACTOR'S PRE-MOD MAPPING. IT IS THE CONTRACTOR'S RESPONSIBILITY TO FIELD VERIFY ALL EXISTING CONDITIONS AND DIMENSIONS AND COORDINATE WITH THE AVAILABLE SOURCES OF INFORMATION ABOVE AND WITH THE PROJECT PLANS BEFORE PROCEEDING WITH THE WORK. CONTRACTOR SHALL IMMEDIATELY REPORT ANY AND ALL DISCREPANCIES TO PAUL J. FORD AND COMPANY AND CROWN CASTLE FIELD PERSONNEL BEFORE PROCEEDING WITH THE WORK.
- ALL STRUCTURAL BOLTS SHALL BE INSTALLED AND TIGHTENED TO THE PRETENSIONED CONDITION ACCORDING TO THE REQUIREMENTS OF THE AISC "SPECIFICATION FOR STRUCTURAL JOINTS USING HIGH-STRENGTH BOLTS", DEC. 31, 2009.
- ALL STRUCTURAL BOLTS SHALL BE FIELD INSPECTED ACCORDING TO THE REQUIREMENTS OF THE AISC SPECIFICATION FOR STRUCTURAL JOINTS USING HIGH-STRENGTH BOLTS', DEC. 31, 2009.

# PROJECT CONTACTS:

## MONOPOLE OWNER:

CROWN CASTLE 8 PARKMEADOW DRIVE, PITTSFORD, NY 14534 CONTACT: STEVE TUTTLE PH: (585) 899-3445

# STRUCTURAL ENGINEER OF RECORD (EOR):

PAUL J. FORD AND COMPANY
250 EAST BROAD STREET, SUITE 600
COLUMBUS, CHIO 43215-3708
CONTACT: KYLE THORRE AT KTHORPE@PJFWEB.COM
PHONE: 614-221-6679

# DESIGN STANDARD

THIS REINFORCEMENT DESIGN IS BASED UPON THE REQUIREMENTS OF THE TIAKEIA-222-F-1996 STRUCTURAL STANDARD FOR ANTENNA SUPPORTING STRUCTURES AND ANTENNAS, USING A DESIGN BASIC WIND SPEED OF 85 MPH (FASTEST MILE) WITH NO ICE, 37.6 MPH WITH 34 INCH ICE AND 50 MPH SERVICE I LOADS.

REFER TO THE POLE DESIGN AND ANTENNA LOADING DOCUMENTED IN THE PJF STRUCTURAL ANALYSIS FOR THIS SITE (PJF#37513-1642), DATED 8-20-2013.

# THIS PROJECT INCLUDES THE FOLLOWING REINFORCING ELEMENTS:

FOUNDATION AUGMENTATION: MICROPILES

SHEET INDEX			
SHEET NUMBER	DESCRIPTION		
T-1	TITLE SHEET		
S-1	GENERAL NOTES		
S-2	GENERAL NOTES		
S-3	MONOPOLE PROFILE		
S-4	FOUNDATION REINFORCING DETAILS		
S-5	MI CHECKLIST		



ASBUILT 5-26-14 R.S.T. LCC DEPLOYMENT

of Lightypt 2010, by Hall, and the Composit, Mill Rights Received. This occurrent and No Paul. And and Company, Marcell in Visit conclessors and that and, without the polar without permission of Paul. A. Feet and the unity pulposa datar from the wands for you pulposa datar from the lateral of an for this openition product.

PAUL J. FORD AND COMPANY STRUCTURAL ENGINEERS STRUCTURAL ENGINEERS STRUCTURAL ENGINEERS STRUCTURAL ENGINEERS STRUCTURAL ENGINEERS STRUCTURAL ST

BU #826222; NEWTOWN/RT-25 NEWTOWN, CT

MONOPOLE REINFORCEMENT AND RETROFIT PROJECT

PROJECT No:
37513-1642
DRAWN BY:
B.M.S.
CHECKED BY:
K.A.T.
APPROVED BY:
DATE:

ISSUE DATE OF PERMIT: 8-20-2013

T-1

CROWN GASTLE PROJECT: BU #826222: NEWTOWN/RT-25: NEWTOWN, CT MONOPOLE RETROFIT PROJECT MASTER NOTES DOCUMENT (REV. 2, 1/2/2/2009)

- A. SENERAL NOTES.

  A. SENERAL NOTES.

  J. SARAL BE THE RESPONSIBILITY OF THE CONTRACTOR TO FIELD VERIFY ALL EXISTING CONDITIONS AND DEMENSIONS PRIOR TO FASRICATION AND CONSTRUCTION. THESE DRAWINGS WERE PREPARED FROM INFORMATION AND DOCUMENTS PROVIDED TO PAUL. J. FORD & COMPANY SY CROWN CASTLE. THIS INFORMATION PROVIDED HAS NOT SEEN FIELD VERIFIED BY PAUL. J. FORD & COMPANY FOR ACQUIRACY AND THEREFORE DISCREPANCIES SETWEEN THESE DRAWINGS AND ACTUAL STEE CONDITIONS SHOULD BE ANTICIPATED. ANY DISCREPANCIES NATOR CHANGES SETWEEN THE INFORMATION CONTRINED IN THESE DRAWINGS AND THE ACTUAL VERIFIED SITE OCCUPIED AND SHOULD SHOULD BE ANTICIPATED. ANY DISCREPANCIES NATOR CHANGES SHOWN ANY CHANGES AND CONTRIBUTION OF CHOWN COSTLE AND PAUL. J. FORD & COMPANY SO THAT ANY CHANGES AND/CONTRIBUTION OF CHOWN COSTLE AND PAUL. J. FORD & COMPANY SO THAT ANY CHANGES AND/CONTRIBUTION OF CHOWN COSTLE AND PAUL. J. FORD & COMPANY SO THAT ANY CHANGES AND/CONTRIBUTION OF CHOWN COSTLE AND PAUL. J. FORD & COMPANY SO THAT ANY CHANGES AND/CONTRIBUTED AND CHANGES AND CONTRIBUTED AND CHANGES AND CONTRIBUTED AND CHANGES AND CH

- CORPY ALL OF THE NYTCHIAN AND OLYTCORING LIGHT STREAM THESE DRAWINGS AT THE REQUIRED MINIBILATION AND SECRET STREAM THE REPORT OF THE NYTCHIAN AND PLATFORM LOADS WITH THE MONOPOLE REINFORCING SYSTEM IS COMPLETELY AND SUCCESSFULLY INSTALLED.

  JIE MATERIALS, QUANTITIES, STREMSTHS OR SIZES INDICATED BY THE DRAWINGS OR SPECIFICATIONS ARE NOT AGREEMENT WITH THESE HOTES, THE BETTER COULTY ANDOR GREATER QUANTITY, AND SUCCESSFULLY INSTALLED.

  JIE MATERIALS, QUANTITIES, STREMSTHS OR SIZES INDICATED BY THE DRAWINGS OR SPECIFICATIONS ARE NOT IN AGREEMENT WITH THESE HOTES, THE BETTER COULTY AND CREATER QUANTITY, AND SUCCESSFULLY INSTALLABLE.

  JIE MATERIALS, QUANTITIES, STREMSTHS OR SIZES INDICATED BY THE DRAWINGS OR SPECIFICATIONS ARE NOT ASSESSION.

  ARE DON'T AND CREATER THE SIZE OF THE STREMSTH OF THE MONOPOLE AND THE SIZE OF THE MONOPOLE AND THE SIZE OF THE MONOPOLE AND THE SIZE OF THE MONOPOLE AND THE CONTRACTORS SOLE RESPONSIBILITY TO INSURE THE SAFETY AND STABILITY OF THE MONOPOLE AND THE CONTRACTORS SOLE RESPONSIBILITY TO INSURE THE SAFETY AND STABILITY OF THE MONOPOLE AND THE CONTRACTORS SOLE RESPONSIBILITY TO INSURE THE SAFETY AND STABILITY OF THE MONOPOLE AND THE CONTRACTORS SOLE RESPONSIBILITY TO INSURE THE SAFETY AND STABILITY OF THE MONOPOLE AND THE CONTRACTORS SOLE RESPONSIBILITY TO INSURE THE SAFETY AND STABILITY OF THE MONOPOLE AND ADDITIONAL OF MONOPOLE AND THE CONTRACTOR OF THE MONOPOLE AND THE MONOPOLE A

- 8. (SECTION NOT USED)



- C. SPECIAL INSPECTION AND TESTING
  ACT WORK SHALL BE SUBJECT TO REVIEW AND OBSERVATION BY THE OWNER'S REPRESENTATIVE AND
  THE OWNER'S AUTHORIZED INDEPENDENT INSPECTION AND TESTING AGENCY. REFER TO GROWN
  CASTLE POCUMENT RNA-SOW HOBS PER SPECTICATION.

  DISTINGUISHED FROM CONTINUED AND TESTING AGENCY. REFER TO GROWN
  CASTLE POCUMENTS AND HOBS PER SPECTICATION.

  DISTINGUISHED FROM CONTINUED AND DET NUE IN INSPECTION SERVICES WHICH ARE FURNISHED BY
  OTHERS. THES SUPPORT SERVICES PERFORMED BY THE ENGINEER ARE PERFORMED SHALL BY
  THE DURPOSE OF ASSISTING IN CUMUTY CONTROL AND IN ADHERING CORPORNANCE WITH CONTRACT
  DOCUMENTS. THEY DO NOT CUMPANIFE CONTRACTORS PERFORMENCE WITH CONTRACT
  CONSTRUCTOR. THEY DO NOT CUMPANIFE CONTRACTORS PERFORMENCE AND ANALL NOT BE
  CONSTRUCTOR.

  AN INDEPENDENT CUALIFIED INSPECTIONATESTING AGENCY SHALL BE SELECTED. RETAINED AND PAID
  POR BY THE OWNER FOR THE SOLE PURPOSE OF INSPECTING. ESTING, DOQUMENTING, AND
  APPROVING ALL WELDING AND FIELD WORK PERFORMED BY THE CONTRACTOR.

  (B) THE INSPECTION AGENCY SHALL SO SCHEDULE THIS WORK AS TO CAUSE A MINISHING.

  (B) THE INSPECTION AGENCY SHALL SO SCHEDULE THIS WORK AS TO CAUSE A MINISHING.

  TESTING AGENCY TO PERFORM THE WITH, THE VORK IN PROGRESS IT IS THE
  TESTING AGENCY TO PERFORM THE UNITE.

  AS ENDECTION AND THE TESTING AGENCY SHALL BE PERFORMED AT THE FISHING
  AGENCY. THE CONTRACTOR SHALL ALLOW FOR ADEQUATE TIME AND ACCESS FOR THE
  TESTING AGENCY TO PERFORM THE WITH THE VORK AS TO CAUSE A MINISHING THE TESTING
  AGENCY OF THE CONTRACTOR SHALL ALLOW FOR AGENCY SHALL INSPECT THE AD ACCESS FOR THE
  TESTING AGENCY TO PERFORM THE WITH THE VORK AS TO CAUSE A MINISHING THE TESTING
  AGENCY THE CONTRACTOR SHALL ALLOW FOR AGENCY SHALL INSPECT THE FOLLOWING
  SERVICES FOR THE CONTRACTOR SHALL BE RESPONSIBLE TO PERFORM THE FOSTING AGENCY
  TO COMPANIE THE CONTRACTOR SHALL BE RESPONSIBLE TO PERFORM THE FORM ACCOUNTING THIS IN

  ACCORDANCE WITH THE CONTRACTOR SHALL BE RESPONSIBLE TO PERFORMER. PERFORMENT FOR AND
  ACCOUNTING AGENCY THE TESTING AGENCY SHALL INSPECT THE PROPORMATHE
- AND COMMENSURATE WITH THE SCOPE AND TYPE OF INSPECTION WORK TO BE PERFORMED.

  GENERAL:

  (1) FERFORM COMMINUOUS ON-SITE OBSERVATION, INSPECTION, VERFICATION, AND TESTING DURING THE TIME THE CONTRACTORS WORKING ON-SITE. AGENCY SHALL NOTIFY OWNER IMMEDIATELY WHEN FIELD PROBLEMS OR DISORPEANCIES OCCUR.

  FOUNDATIONS, CONCRETE, AND SOLD PREPARATION: NOTI REQUIRED!

  CONCRETE IS STIRD FOR AGI. INDIT REQUIRED!

  (CONCRETE IS STIRD ON THE JOB WITH THE PRANS.

  (2) CHECK MILL CERT FICATIONS.

  (3) CHECK MILL CERT FICATIONS.

  (4) DISPECT STEEL ON THE JOB WITH THE PRANS.

  (5) CALL FOR LABORATORY TEST REPORTS WHEN IN DOUGH.

  (6) CHECK STEEL MEMBERS FOR DISTORTION, EXCESSIVE RUST, FLAWS AND BURNED HOLES.

  (6) CALL FOR LABORATORY TEST REPORTS WHEN IN DOUGH.

  (6) CHECK STEEL MEMBERS FOR DISTORTION EXCESSIVE RUST, FLAWS AND BURNED HOLES.

  (7) CHECK FOR BURNACE FINGS SUES, SWEEP AND DIZENSIONAL TOLERANCES.

  (7) CHECK FOR BURNACE FINGS SUES, SWEEP AND DIZENSIONAL TOLERANCES.

  (8) CHECK STEEL MEMBERS FOR DUSTS, SWEEP AND TURN OF THE MIT METHOD.

  WELDING-INDIT REQUIRED!

- WELDING NOT REQUIRED SHAPT-TO-FLANGE WELD CONNECTIONS (NOT REQUIRED) REPORTS TO THE OWNER.

  [1,] COMPILE AND PERSONCALLY SUBMIT DAILY INSPECTION REPORTS TO THE OWNER.
- TI, DOMPILE AND PERGOUCALLY SUBMIT DALLY INSPICTION REPORTS TO THE OWNER.

  THE INSPICTION PLAN OUTLINED HERBINIS INTENDED AS A DESCRIPTION OF GENERAL AND SPECEN.

  THESE OF CONCERN, IT IS NOT MITERIORS TO BE ALL-INCLUSIVE. IT DOES NOT LIMIT THE TESTING AND EXPENSE AND ADDRESS OF THE STATE AND ADDRESS OF THE ADDRESS OF THE STATE ADDRESS OF THE PROPERSIONAL LIMIT HIS PROPESSIONAL ADDRESS OF THE ADDRESS ON THE CONTINUOUS ADDRESS OF THE STATE OWNERS OF THE STATE ADDRESS OF THE ADDRESS OF THE ADDRESS ON THE CONTINUOUS ADDRESS OF THE STATE OWNERS OF THE STATE ADDRESS OF THE OWNERS ATTENTION, THE TESTING AGENCY SUDGMENT OF THE ADDRESS OF THE ADDRESS OF THE ADDRESS OF THE OWNERS ATTENTION, THE STATE ADDRESS OF THE ADDRESS OF



**ASBUILT 5-26-14** R.S.T. LCC DEPLOYMENT

PAUL J. FORD AND COMPANY STRUCTURAL ENGINEERS 250 See Stoed Street - Sale 603 - Columbias, Orio 43:15 www.gb/mis.com CROWN CASTLE 8 PARKMEADOW DRIVE, PITTSFORD, NY 14534 PH: (585) 589-3445 FAX: (585) 689-3446

BU #826222; NEWTOWN/RT-25 NEWTOWN, CT

MONOPOLE REINFORCEMENT AND RETROFIT PROJECT

CHECKED BY K.A.T.

ISSUE DATE OF PERMIT: 8-20-2013

RAP

- 2

- 10.
- (A.)
- STRUCTURAL STEEL

  STRUCTURAL STEEL

  MATERIALS, FABRICATION DETALING, AND WORKMANSHIP SHALL CONFORM
  TO THE LATEST STRUCTURAL STEEL

  TO THE LATEST STRUCTURAL STEEL

  AS STRUCTURAL STEEL

  MATERIALS, FABRICATION AND EFFECTION OF STRUCTURAL STEEL

  FOR BULDINGS.

  SPECEPCATION FOR THE DESIGN FABRICATION AND EFECTION OF STRUCTURAL STEEL

  FOR BULDINGS.

  SPECEPCATION FOR STRUCTURAL JOINTS USING ASTM ASS OR A60 BOLTS, AS

  APPROVED BY THE RESEARCH COUNCIL ON STRUCTURAL CONNECTIONS OF THE

  BY THE AMERICAN WELDON SOCIETY (MSS):

  (C) TODG OF STRAMARD PRACTICE FOR STEEL BUILDINGS AND BRIDGES\* (PARAGRAPH 4.2.1

  BY THE AMERICAN WELDON SOCIETY (MSS):

  (A) "STRUCTURAL WELDING CODE: STEEL DI.I."

  AND ACCOMMENT OF THE STRUCTURAL WELDING CONNECTION OF REPACCED AT THE

  CONTRACTOR SEPPENSE.

  TIGHTEN ALL STRUCTURAL BOLTS, INCLUDING THE AMAY MOS BOLTS WITH SHEAR SLEEVES,

  ACCOMMENT OF THE SRUCH MENTS OF THE ABECS CHANG FOR THE NUT! WELFIND. TIGHTEN BOLTS 1/3

  TURN PAST THE SRUCH TIGHT CONDITION AS DEFINED BY ALSO.

  WELDON CONNECTIONS SHALL DO ONE OF THE AMERICAN

  WELDON CONNECTIONS SHALL DO ONE OF THE AMERICAN

  ALL WELDED CONNECTIONS SHALL BOTT ON THE ATERS TRY MED CODE OF THE AMERICAN

  STRUCTURAL STEEL FLATES SHALL CONFORM TO ASTIT AST2 GRADES (F) F 95 KS IMM, U, UHLESS

  OTHERWISE ON THE DRAWMINGS.

  ALL WELDED CONNECTIONS SHALL BE ABELD WELDING FOR FILED WELDING FOR ANY SEE SECTION I NOTES REGARDING TOLICHLY OF GRAUNANCED SUFFACES DAMAGED DURING

  TRANSPORTATION OF REFECTION AND QUALIFICATION DOCUMENTATION TO THE CONNECTION SHALL BUILDINGS OF THE STRUCK AND ASTITUTION FOR THE ATERS HALL CONFORM TO ASTIT AST
- (C.)
- E. BASE PLATE GROUT - (NOT REQUIRED)
- BASE PLATE GROUT. (NOT REQUIRED)

  FOUNDATION WORK
  THE CONTRACTOR SHALL PROTECT THE DOSTING MONOPOULE STRUCTURE. AS WELL AS ANY OTHER
  FOUNDATION WORK
  THE CONTRACTOR SHALL PROTECT THE SOSTING MONOPOULE STRUCTURE. AS WELL AS ANY OTHER
  FLESCON. EDITOR FOUNDATIONS FOR OTHER STRUCTURES OR EQUIPMENT. PROMILES OF SOX.
  AROUND AND/OR RENEATH FOOTINGS DURING ANY REQUIRED.
  THE EFFECT OF ADDITIONAL EXCANATION (WHERE REQUIRED) FOR THE NEW MAT FOOTING (WHERE
  FEGURED) OR OTHER FOUNDATION AUGMENTATION AND REPORCING (WHERE REQUIRED) MAY
  HAVE IMPACT ON EXISTING EQUIPMENT AND/OR OTHER EXISTING STRUCTURES NEAR THE
  EXCANATION. (RIGNIEREOF, PRECORD) HAS NOT BEEN PROVIDED WITH ANY SPECIFIC INFORMATION
  OR DETALS REGARDING EXISTING EQUIPMENT OR OTHER EXISTING STRUCTURES ON THE SITE.
  STRUCTURES. CONTRACTOR SHALL DORDINATE THIS SITE-SPECIFIC INFORMATION WITH THE
  STRUCTURES. CONTRACTOR SHALL DORDINATE THIS SITE-SPECIFIC INFORMATION WITH THE
  CONTRACTOR SHALL ADEQUATELY BRACE. SHORE, AND/OR RELOCATE (AFTER DISTAINS THE
  PRORE WITH PERMISSION OF THE OWNER) AND ADD FOUNDATION WORK. THE
  PORT WITHTEN PERMISSION OF THE OWNER, AND ADD FOUNDATION WORK.

- 12.
- CAST-IN-PLACE CONCRETE
  CONCRETE SYALL HAVE A MINIMUM COMPRESSIVE STRENGTH OF 4000 PS AT 28 DAYS.
  (A) CONCRETE SYALL HAVE A MINIMUM COMPRESSIVE STRENGTH OF 4000 PS AT 28 DAYS.
  (A) CONCRETE EXPOSED TO WEATHER SHALL BE AIR ENTRAINED (6% ++ 1.5%).

  ALL REINFORCING STEEL SHALL BE NEW DOMESTIC DEFORMED BILLET STEEL CONFORMING TO ALL STRING AND STREET STEEL STEEL STEEL STRENGTH OF A STEM AS 15 GOOD ES.

  ASTM AS 15 GOOD ES.

  ASTM AS 15 GOOD ES.

  ALL STANDARD CONFORTER ACT 318, LATEST EDITION.

  CONTRACTOR SHALL FOLLOW ALL APPLICABLE ACT PROCEDURES FOR COLD WEATHER CONCRETE PLACEMENT.

  ALL REINFORCING DETAILS SHALL COMPOSENTO MANUAL OF STANDARD PRACTICE FOR CETALING BLAREST EDITION. UNLESS DETAILS SHALL CONFORCE TO THE STRUCTURAL DRAWINGS.

  CONTRACTOR SHALL VERLIVE COLOTIONS OF ALL OPENINGS, SLEEVES, ANOTHER ONE OF A STANDARD PRACTICE FOR CETALING BLAYERS EDITION. UNLESS DETAIL EDITION SHALL PREVIOUS SHALL VERIFY LOCATIONS OF ALL OPENINGS, SLEEVES, ANOTHER ONE OF A STANDARD PRACTICE FOR CETALING BLAYERS EDITION. UNLESS DETAIL EDITION ON EXPOSED ON THE STRUCTURAL DRAWINGS.

  ETC., AS REQUIRED BEFORE CONDRETE IS PLACED.

  WHERE BAY LENGTHS ARE GIVEN ON THE CHARMINGS, THE LENGTH OF ANY HOOK, IF REQUIRED, IS NOT INCLUDED.

  MINIMUM STRUCTURE SHALL HAVE KINDS WHICH ARE PLASTIC TIPPED OR STANLESS STEEL. ALL STRINGTURAL MEMBERS SHALL BE PURED MONOLITHICALLY, EXCEPT FOR REQUIRED CONCRETE SHALL BE AND SHALL SHARLY AND SHALL SHARLY BE AND SHALLED CONTRACTOR SHALL SHARLY. AND SHALLES OTHERWISE ON THE DRAWINGS. MINIMUM CONTRECTOR SHALL BE MINIMUM AND AS SPECIFIED BY ACL.

  THE FOLLOWING MINIMUM CONCRETE COVER SHALL BE PROVIDED FOR REINFORCEMENT:

  3 CONCRETE CAST ADMINISTRATION BOY FROM THE PROVIDED FOR REINFORCEMENT:

  4 CONCRETE CAST ADMINISTRATION BOY FROM THE PROVIDED FOR REINFORCEMENT:

  5 CONCRETE CAST ADMINISTRATION BOY FOR THE PROVIDED FOR REINFORCEMENT:

  5 CONCRETE CAST ADMINISTRATION BOY FROM THE STANDARD SHALLER OF THE CONTRACTOR SHALL BE EMPTINED AS SPECIFIED BY ACL.

  10 CONCRETE CAST ADMINISTRATION BOY FROM THE PROVIDED FOR RE
  - EPOXY GROUTED REINFORCING ANCHOR RODS (NOT REQUIRED)
  - TOUCH UP OF GALVANIZING (NOT REQUIRED)
  - HOT DIP GALVANIZING (NOT REQUIRED)
- PERPETUAL RISPECTION AND MAINTENANCE BY THE DYINER.
  AFTER THE CONTRICTION AND MAINTENANCE BY THE DYINER.
  AFTER THE CONTRICTION FAS SUCCESSFULLY COMPLETED THE INSTALLATION OF THE MONOPOLE REINFORCING SYSTEM AND THE WORK HAS BEEN ACCEPTED BY THE OWNER, THE OWNER WILL BE RESPONDED FOR THE LONG TERM AND PERPETUAL INSPECTION AND MAINTENANCE OF THE FOLL FOR THE CONTRICT OF THE PERPETUAL PROPERTIES OF THE LONG THE PERPETUAL PROPERTIES OF THE RESPONDED OF THE PERPETUAL PROPERTIES OF THE RESPONDED OF THE PERPETUAL PROPERTIES OF THE PERPETUAL PROPER





AUG 2 1 2013

**ASBUILT 5-26/14** R.S.T. LCC DEPLOYMENT


PAUL J, FORD AND COMPANY STRUCTURAL ENGINEERS 250 based Bried Street - Safe 950 - Openizass, Orio 43216 (514) 221-8679 **CROWN CASTLE** 


BU #826222; NEWTOWN/RT-25 NEWTOWN, CT

MONOPOLE REINFORCEMENT AND RETROFIT PROJECT

ROJECT No 37513-1842 KAT, ROYED BY DATE:

ISSUE DATE OF PERMIT: 8-20-2013





### 37513-1642 PERMIT DWG


### MICROPILE NOTES:

- 1. ALL HOLLOW BAR STEEL AND ASSOCIATED HARDWARE SHALL BE SUPPLIED BY CON-TECH SYSTEMS OR CAMERICOR APPROVED EXCLUSIVE PAIL.
- 2. ALL HOLLOW BAR, NUTS AND BEARING PLATES SHALL BE HOT-DIP GALVANIZED PER ASTM A123 OR A153, AS APPROPRIATE.
- 1 CONTACT CONTECT SYSTEMS (OR MANUFACTURER OF APPROVED ALTERNATE) FOR MATERIALS AND INSTALLATION PROCEDURES AND RECOMMENDATIONS.
- 4. SPECIAL REPECTION OF THE MICROPILES IS REQUIRED AS FOLLOWS: (I) VERIFY THAT MICROPILE NATIFIES, SZZ AND LENGTH COMPLY WITH THE INFORMATION SHOWN ON THIS DRAWNIN, (2) VERIFY PLACEMENT OF EACH MICROPILE, (2) OBSERVE ORILLING, ORDUTING AND TESTING AS A PREPERTATE OPERATIONS FOR EACH MICROPILE AND MAINTAIN COUPLETE AND ADDITIONS FOR EACH MICROPILE.
- FOUNDATION DESIGN IS BASED ON THE GEOTECHNICAL REPORT PREPARED BY FDH, PROJECT NO. 1395759000, DATED 8/19/13.
- 8. CONTACT CONTECH SYSTEMS (OR MANUFACTURER OF APPROVED ALTERNATE) TO VERIFY NUT & WASHER CONNECTION ARE COMPATIBLE WITH MICROPILE THREADS.
- 7. ALL MICROPILE SHALL BE GROUTED FOR FULL HEIGHT. CRIDIT TO 86 4,000 PSI WIN COMPRESSION STRENGTH WITH D.S (MAXIMUM WATERCEMENT) WIC RATIO (TO 86 COLLO GOALLY MAKED FOR MICROPILE).



		PRELIMINAL	RY PILE DESIGN	PARAMETER	R SCHEDULE*		
OPTIONS PARAMETE	WIN. HOLE WISTEEL AREA	ALLOWABLE PILE CAPACITY (Namo	ULTIMATE SKIN FRICTION (PSI)	FREE STRESS LENGTH	FRICTION DEVELOPMENT LENGTH/BOYO LENGTH	ROCK SOCKET/ PLUNGE LENGTH	TOTAL EMBEDMENT LENGTH
MICROPILE	10.5% 2.53 IN <sup>3</sup> MIN	150K	SEE GEOTECH REPORT	5	27 MIN.	NA.	33° MIN.

THE FAIL DESIGN GROUT CAMETER IS EASED ON A WINNIUM ZOMM AUGER IN SETY SAND. THE DESIGN REQUIRES MICASED MICROPIES FOR THE LISTED CAPACITY IN TENSION AND COMPRESSON AS LAD OUT PIRP NAM. THE CONTRACTOR-ACCORDE INSTALLER IS RESPONSIBLE FOR THE MEANS AND METHODS TO PROJECT FOR HISTOSIANY CAPACITY AND WALL DESIGN AS PROMOTIONS. THE MEMORY AND ADDRESS TO THE MEMORY AND ADDRESS TO THE MEMORY AND ADDRESS TO LISTED AS A PROJECT FOR THE MEMORY AND ADDRESS WE RECOVERED TO LISTED AS A PROJECT FOR THE MEMORY AND ADDRESS APPROPRIATE TO LISTED AS A PROJECT FOR THE MEMORY AND ADDRESS APPROPRIATE TO LISTED AS A PROJECT FOR THE MEMORY AND ADDRESS APPROPRIATE ADDRESS APPROPRIATE ADDRESS AND ADDRESS APPROPRIATE ADDRESS AND ADDRESS APPROPRIATE ADDRESS AND ADDRESS APPROPRIATE ADDRESS AND ADDRESS



NEW BEARING PLATE MK~BP1



ASBUILT 5-26-14 R.S.T. LCC DEPLOYMENT

Organy 2010 by Pask First an Company, All Right Research This secured and the date combined trees, is projecting to Pask J Fard and Company, Reseal in sales conference and wall true, when the sales conference and wall true, when the prior wides premission of Pask J. Food and Company, and proper proper ward for true ys, purpose other than the varieties used by the proper proper, in the contraction of the proper proper was the proper proper was the proper proper proper.



BU #826222; NEWTOWN/RT-25 NEWTOWN, CT

MONOPOLE REINFORCEMENT AND RETROFIT PROJECT

PRO. 375		
DRA B	WN.	
CHEC	XE (A.)	
PPR	CNE	T) D

ISSUE DATE OF PERMIT: 8-20-2013

### 7613-1642 PERMIT.DWG

# MODIFICATION INSPECTION NOTES:

GENERAL
THE MODIFICATION INSPECTION (MI) IS A VISUAL INSPECTION OF TOWER MODIFICATIONS AND ARRYEN OF CONSTRUCTION INSPECTIONS
AND OTHER REPORTS TO SHOURE THE INSTALLATION WAS CONSTRUCTED IN ACCORDANCE WITH THE CONTRACT DOCUMENTS, NAMELY THE
MODIFICATION DRAWINGS, AS DESIGNED BY THE ENCINEERS OF RECORD (MOS).

ALL MTS SHALL BE CONDUCTED BY A CROWN ENGINEERING VENDOR (AEV) OR ENGINEERING GETWICE VENDOR (AEBV) THAT IS APPROVED TO PERFORM ELEVATED WORK FOR CROWN. SEE ENG-BUL-MITSLEST OF APPROVED M VENDORS.

TO ENSURE THAT THE REQUIREMENTS OF THE NI ARE MET, IT IS WITH, THAT THE OBJECTAL CONTRACTOR (SC) AND THE MINSPECTOR BEGIN COMMUNICATION AND COORDINATION OF SOON AS A PIOUS RECEIVED. IT SEPERCETED THAT SOOT PROTECTIVE IN REPORTING OUT TO THE OTHER PARTY. IF CONTACT WERE OBTAINED IS NOT INCOME, CONTACT YOUR CROWN POINT OF CONTACT WOOD.

REFER TO ENG-SOW-10007: MODIFICATION INSPECTION SOW FOR FURTHER DETAILS AND REQUIREMENTS.

MINISPECTOR
THE NITHSPECTOR IS REQUIRED TO CONTACT THE GC AS SOON AS RECEIVING A PO FOR THE MITO, AT A NINMARE

 REVIEW THE REQUIREMENTS OF THE MICHECKLIST
 WORK WITH THE DC TO DEVELOP A SCHEDULE TO CONDUCT ON-SITE INSPECTIONS, INCLUDING FOUNDATIONINSPECTIONS THE MINSPECTOR IS RESPONSIBLE FOR COLLECTING ALL GENERAL CONTRACTOR (GC) INSPECTION AND TEST REPORTS, REMEMBING THE DOCUMENTS FOR ADHERENCE TO THE CONTRACT DOCUMENTS, CONDUCTING THE IN-PIELD INSPECTIONS, AND SUBMITTING THE MIREPORT TO CORDINA

GENERAL CONTRACTOR
THE GOLD REQUIRED TO CONTACT THE MILINSPECTOR AS SOON AS RECEIVING A POPOR THE MODIFICATION INSTALLATION OR TURN
PROJECT OF A REMINARY.

- REVIEW THE REQUIREMENTS OF THE MICHECKLIST
   WORK WITH THE WILKINGTON THE OF ADDRESS OF THE OCCUPANT OF MISTER MSPECTIONS, INCLUDING FOUNDATION INSIDE MISTER MSPECTION AND TESTING PROGRESSIAND ALL MORPECTION AND TESTING PROGRESSIANS

THE GC SHALL PERFORM AND RECORD THE TEST AND INSPECTION RESULTS IN ACCORDANCE WITH THE REQUIREMENTS OF THE MI THEORIEST AND DENG-SOW YORK.

# RECOMMENDATIONS THE FOLLOWING RECO

IMMENDATIONS AND SUGGESTIONS ARE OFFERED TO ENHANCE THE EFFICIENCY AND EFFECTIVENESS OF DELIVENING

- IN IT IS SUDDRISTED THAT THE OC PROVIDE A MINIAM OF SINSHLOSS DAYS HOTICL PREFERANCE 16, TO THE MINIPECTOR AS TO WHEN THE SITE WILL BE READY FOR THE MIT OF BECOMPLICED. CONDUCTED.

  THE COST ADMINISTRATORY FOR THE MIT OF BECOMPLICED.

  WHEN POSSIBLE, IT IS INFREDUNDED TO MAKE HE OF ALEM IN IMPRECTOR ON SITE SIMULTANDOUSLY FOR ANY OUT WHEN TENSIONED ON THE CONDUCTION OF THE POSSIBLE. IT IS INFREDUNDED TO MAKE HE OF ALEM IN IMPRECTOR OF THE CONDUCTION OF PORTATION PROPERTIES.

  WHEN POSSIBLE, IT IS PREFERENCE TO HAVE THE OF ALEM INSPECTOR ON SITE SURFAIL THE MIT TO MAKE ANY OFFICED COSTS OF ALEM INTO MAKE HE OF ALEM IN INSPECTOR ON SITE SURFAIL THE MIT TO MAKE ANY OFFICED COSTS OF ALEM IN INSPECTOR ON SITE SURFAIL THE MIT TO MAKE ANY OFFICED COSTS OF ALEM IN INSPECTOR OF ALEM IN INSPECTOR ON SITE SURFAIL THE MIT TO MAKE ANY OFFICED COSTS OF ALEM IN INSPECTOR OF ALEM INSPECTOR OF ALEM IN INSPECTOR OF ALEM IN INSPECTOR OF ALEM INSPECTO

CANCEL ATTAIL OLD ATTAINED FAIL HOSEIGNESS.

If THE CO. ON IN INSECTION ADDRESS OF DESCRIPTION OF THE BUYEL SECONDACTED, AND ETHER PARTY CANCELS OF DELIVEY, ORDINARY OF THE CO. ON IN INSECTION AND ETHER PARTY CANCELS OF DEPOSITS ABOVE OTHER PARTY SERVED TO THE CANCELLARIES OF DEPOSITS AND ON THE PERSON OF THE PARTY OF THE CANCELS OF THE PARTY OF THE PARTE OF THE PARTY OF THE PARTE ON THE PARTY OF THE PARTE ON THE PART

- CORRECT FALING ISSUES TO COMPLY WITH THE SPECIFICATIONS CONTAINED IN THE ORIGINAL CONTRACT COCUMENTS AND
  COORDINATE A SUPPLICATION.
   ON, WITH CONTRACT APPROVAL, THE GC MAY WORK WITH THE GOT TO RE-ANALYZE THE MODIFICATION REINFORCEMENT LISING THE
  AS-BULL CONDITION

M VERPICATION RESPECTIONS
CROWN RESERVES THE MOUT TO COMPUCT A M VERPICATION INSPECTION TO VERFY THE ACQURACY AND COMPLETENESS OF PRIVIOUSLY COMPLETED IN REPECTION(S) ON TOWER MODIFICATION PROJECTS.

ALL VERIFICATION INSPECTIONS SHALL BE HELD TO THE SAME SPECIFICATIONS AND REQUIREMENTS IN THE CONTRACT DOCUMENTS AND IN ACCORDANCE WITH ENGACYM-19007

VERFICATION INSPECTION MAY BE CONDUCTED BY AN INDEPENDENT ARMAESY FRIM AFTER A MODIFICATION PROJECT IS COMPLETED, AS MARKED BY THE DATE OF AN ACCIPITED "PASSING IN" OR "PASS AS NOTED IN" REPORT FOR THE ORGANAL PROJECT.

PHOTOGRAPHS
BETWEEN THE GC AND THE MILISPECTOR THE FOLLOWING PHOTOGRAPHS, AT A MINIMUM, ARE TO BE TAKEN AND INCLUDED IN THE MI

- PRE-CONSTRUCTION GENERAL SITE CONDITION
   PHOTOGRAPHS DURING THE REINFORCEMENT MODIFICATION CONSTRUCTION/ERECTION AND INSPECTION PRIOTOGRAPHS DURING THE REINFORCE
   RAW MATERIALS
   PHOTOS OF ALL ORTICAL DETAILS
   FOLINDATION MIGDIFICATIONS
   WELD PREPARATION
   BOLT INSTALLATION AND TORQUE
   FINAL INSTALLE CONDITION
   SURFACE CONTINUS REPAIR
   POST COMETRICATION PROTOGRAPHS

PHOTOS OF ELEVATED MODIFICATIONS TAKEN FROM THE GROUND SHALL BE CONSIDERED INVOECHMEN

THIS IS NOT A COMPLETE LIST OF REQUIRED PHOTOS, PLEASE REFER TO ENG-SOW-10007.

	MI CHECKLIST	
CONSTRUCTION/INSTALLATION INSPECTIONS AND TESTING REQUIRED (COMPLETED BY EOR)	REPORT ITEM	
	PRE-CONSTRUCTION	
x	MI CHECKLIST DRAWINGS	
x	TIOR APPROVED SHOP DRIVWINGS	
x	FABRICATION INSPECTION	
NA.	FABRICATOR CERTIFIED WELD INSPECTION	
x	MATERIAL TEST REPORT (WTR)	
NA	PARRICATOR NDE INSPECTION	
NA.	NOE REPORT OF MONOPOLE BASE PLATE (AS REQUIRED)	
x	PACKING SLIPS	

TESTING PLAN TO CROWN AND PUF FOR REVIEW . TESTING PLAN SHALL INCLUDE DETAILS REGARDING HOW CONTRACTOR INTEN

TO PREVENT INTERACTION BETWEEN THE TEST FILE AND THE EXISTING FOUNDATION DURING TESTING.				
CONSTRUCTION				
×	CONSTRUCTION INSPECTIONS			
х	FOUNDATION INSPECTIONS			
X	CONCRETE COMP. STRENGTH AND SLUMP TESTS			
NA	POST INSTALLED ANCHOR ROD VERIFICATION			
NA.	BASE PLATE GROUT VERIFICATION			
NA.	CONTRACTOR'S CERTIFIED WELD INSPECTION			
NA.	EARTHWORK: LIFT AND DENSITY			
NA.	ON BITE COLD GALWANZING VERIFICATION			
NA	GUY WIRE TENSION REPORT			
×	GC AS-BUILT DOCUMENTS			
244	THIRD PARTY ONSITE INSPECTION OF BOLT PRETENSION PER CROWN REQUIREMENTS			
NA.	INSPECTION OF AJAX BOLTS AND DTYS PER REQUIREMENTS ON SHEET \$-3			

INSPECTION OF AJAX BOLTS AND DITTS PER REQUIREMENTS ON SHEET \$-3 ADDITIONAL TESTING AND INSPECTIONS. VERFY MICROPILE INSTALLATION DETAILS, SPECIFICALLY MICROPILE SIZES, ORALL HOLE DAMBETERS & DEPTHS, GROUT FO AND THAT INSTALLATION WAS ARRESTED. METERS & DEPTHS, GROUT Fo AND THAT INSTALLATION WAS PER MANUFACTURER RECO

	POST-CONSTRUCTION	
×	MI INSPECTOR REDUNE OR RECORD DRAWING(S)	
NA NA	THIRD PARTY ONSITE BOLT INSPECTION REPORT	
NA.	POST INSTALLED ANCHOR ROD PULL-OUT TESTING	
×	PHOTOGRAPHS	

ADDITIONAL TESTING AND INSPECTIONS: PROVIDE REPORT DOCUMENTING RESULTS OF MICROPILE INSTALLATION AND PROOF TESTING

NOTE: X DENOTES A DOCUMENT NEEDED FOR THE PM REPORT NA DENOTES A DOCUMENT THAT IS NOT REQUIRED FOR THE PM REPORT





AUG 2 1 2013

**ASBUILT 5-26-14** R.S.T. LCC DEPLOYMENT

PAUL J. FORD AND COMPANY STRUCTURAL ENGINEERS 250 faat Broad Stroat - Sarke 900 - Columbias, Otto 43215 www.gbysket.com **CROWN CASTLE** 

8 PARKMEADOW DRIVE, PITTSFORD, NY 14534 PH: (985) 899-3445 FAX: (985) 899-3446

BU #826222; NEWTOWN/RT-25 NEWTOWN, CT

MONOPOLE REINFORCEMENT AND RETROFIT PROJECT

37513-1642 DRAWN BY: B.M.S CHECKED BY K.A.T.

ISSUE DATE OF PERMIT: 8-20-2013

### 7613-1642 PERMIT.DWG

# MODIFICATION INSPECTION NOTES:

GENERAL
THE MODIFICATION INSPECTION (MI) IS A VISUAL INSPECTION OF TOWER MODIFICATIONS AND ARRYEN OF CONSTRUCTION INSPECTIONS
AND OTHER REPORTS TO SHOURE THE INSTALLATION WAS CONSTRUCTED IN ACCORDANCE WITH THE CONTRACT DOCUMENTS, NAMELY THE
MODIFICATION DRAWINGS, AS DESIGNED BY THE ENCINEERS OF RECORD (MOS).

ALL MTS SHALL BE CONDUCTED BY A CROWN ENGINEERING VENDOR (AEV) OR ENGINEERING GETWICE VENDOR (AEBV) THAT IS APPROVED TO PERFORM ELEVATED WORK FOR CROWN. SEE ENG-BUL-MITSLEST OF APPROVED M VENDORS.

TO ENSURE THAT THE REQUIREMENTS OF THE NI ARE MET, IT IS WITH, THAT THE OBJECTAL CONTRACTOR (SC) AND THE MINSPECTOR BEGIN COMMUNICATION AND COORDINATION OF SOON AS A PIOUS RECEIVED. IT SEPERCETED THAT SOOT PROTECTIVE IN REPORTING OUT TO THE OTHER PARTY. IF CONTACT WERE OBTAINED IS NOT INCOME, CONTACT YOUR CROWN POINT OF CONTACT WOOD.

REFER TO ENG-SOW-10007: MODIFICATION INSPECTION SOW FOR FURTHER DETAILS AND REQUIREMENTS.

MINISPECTOR
THE NITHSPECTOR IS REQUIRED TO CONTACT THE GC AS SOON AS RECEIVING A PO FOR THE MITO, AT A NINMARE

 REVIEW THE REQUIREMENTS OF THE NII-OHEORIST
 WORK WITH THE GC TO DEVELOP A SCHEDULE TO CONDUCT ON-SITE INSPECTIONS, INCLUDING FOUNDATION INSPECTIONS THE MINSPECTOR IS RESPONSIBLE FOR COLLECTING ALL GENERAL CONTRACTOR (GC) INSPECTION AND TEST REPORTS, REMEMBING THE DOCUMENTS FOR ADHERENCE TO THE CONTRACT DOCUMENTS, CONDUCTING THE IN-PIELD INSPECTIONS, AND SUBMITTING THE MIREPORT TO CORDINA

GENERAL CONTRACTOR
THE GOLD REQUIRED TO CONTACT THE MILINSPECTOR AS SOON AS RECEIVING A POPOR THE MODIFICATION INSTALLATION OR TURN
PROJECT OF A REMINARY.

- REVIEW THE REQUIREMENTS OF THE MICHECKLIST
   WORK WITH THE WILKINGTON THE OF ADDRESS OF THE OCCUPANT OF MISTER MSPECTIONS, INCLUDING FOUNDATION INSIDE MISTER MSPECTION AND TESTING PROGRESSIAND ALL MORPECTION AND TESTING PROGRESSIANS

THE GC SHALL PERFORM AND RECORD THE TEST AND INSPECTION RESULTS IN ACCORDANCE WITH THE REQUIREMENTS OF THE MI THEORIEST AND DENG-SOW YORK.

# RECOMMENDATIONS THE FOLLOWING RECO

IMMENDATIONS AND SUGGESTIONS ARE OFFERED TO ENHANCE THE EFFICIENCY AND EFFECTIVENESS OF DELIVENING

- IN IT IS SUDDRISTED THAT THE OC PROVIDE A MINIAM OF SINSHLOSS DAYS HOTICL PREFERANCE 16, TO THE MINIPECTOR AS TO WHEN THE SITE WILL BE READY FOR THE MIT OF BECOMPLICED. CONDUCTED.

  THE COST ADMINISTRATORY FOR THE MIT OF BECOMPLICED.

  WHEN POSSIBLE, IT IS INFREDUNDED TO MAKE HE OF ALEM IN IMPRECTOR ON SITE SIMULTANDOUSLY FOR ANY OUT WHEN TENSIONED ON THE CONDUCTION OF THE POSSIBLE. IT IS INFREDUNDED TO MAKE HE OF ALEM IN IMPRECTOR OF THE CONDUCTION OF PORTATION PROPERTIES.

  WHEN POSSIBLE, IT IS PREFERENCE TO HAVE THE OF ALEM INSPECTOR ON SITE SURFAIL THE MIT TO MAKE ANY OFFICED COSTS OF ALEM INTO MAKE HE OF ALEM IN INSPECTOR ON SITE SURFAIL THE MIT TO MAKE ANY OFFICED COSTS OF ALEM IN INSPECTOR ON SITE SURFAIL THE MIT TO MAKE ANY OFFICED COSTS OF ALEM IN INSPECTOR OF ALEM IN INSPECTOR ON SITE SURFAIL THE MIT TO MAKE ANY OFFICED COSTS OF ALEM IN INSPECTOR OF ALEM INSPECTOR OF ALEM IN INSPECTOR OF ALEM IN INSPECTOR OF ALEM INSPECTO

CANCEL ATTAIL OLD ATTAINED FAIL HOSEIGNESS.

If THE CO. ON IN INSECTION ADDRESS OF DESCRIPTION OF THE BUYEL SECONDACTED, AND ETHER PARTY CANCELS OF DELIVEY, ORDINARY OF THE CO. ON IN INSECTION AND ETHER PARTY CANCELS OF DEPOSITS ABOVE OTHER PARTY SERVED TO THE CANCELLARIES OF DEPOSITS AND ON THE PERSON OF THE PARTY OF THE CANCELS OF THE PARTY OF THE PARTE OF THE PARTY OF THE PARTE ON THE PARTY OF THE PARTE ON THE PART

- CORRECT FALING ISSUES TO COMPLY WITH THE SPECIFICATIONS CONTAINED IN THE ORIGINAL CONTRACT COCUMENTS AND
  COORDINATE A SUPPLICATION.
   ON, WITH CONTRACT APPROVAL, THE GC MAY WORK WITH THE GOT TO RE-ANALYZE THE MODIFICATION REINFORCEMENT LISING THE
  AS-BULL CONDITION

# M VERPICATION RESPECTIONS CROWN RESERVES THE MOUT TO COMPUCT A M VERPICATION INSPECTION TO VERFY THE ACQURACY AND COMPLETENESS OF PRIVIOUSLY COMPLETED IN REPECTION(S) ON TOWER MODIFICATION PROJECTS.

ALL VERIFICATION INSPECTIONS SHALL BE HELD TO THE SAME SPECIFICATIONS AND REQUIREMENTS IN THE CONTRACT DOCUMENTS AND IN ACCORDANCE WITH ENGACYM-19007

VERFICATION INSPECTION MAY BE CONDUCTED BY AN INDEPENDENT ARMAESY FRIM AFTER A MODIFICATION PROJECT IS COMPLETED, AS MARKED BY THE DATE OF AN ACCIPITED "PASSING IN" OR "PASS AS NOTED IN" REPORT FOR THE ORGANAL PROJECT.

PHOTOGRAPHS
BETWEEN THE GC AND THE MILISPECTOR THE FOLLOWING PHOTOGRAPHS, AT A MINIMUM, ARE TO BE TAKEN AND INCLUDED IN THE MI

- PRE-CONSTRUCTION GENERAL SITE CONDITION
   PHOTOGRAPHS DURING THE REINFORCEMENT MODIFICATION CONSTRUCTION/ERECTION AND INSPECTION PRIOTOGRAPHS DURING THE REINFORCE
   RAW MATERIALS
   PHOTOS OF ALL ORTICAL DETAILS
   FOLINDATION MIGDIFICATIONS
   WELD PREPARATION
   BOLT INSTALLATION AND TORQUE
   FINAL INSTALLE CONDITION
   SURFACE CONTINUS REPAIR
   POST COMETRICATION PROTOGRAPHS

PHOTOS OF ELEVATED MODIFICATIONS TAKEN FROM THE GROUND SHALL BE CONSIDERED INVOECHMEN

THIS IS NOT A COMPLETE LIST OF REQUIRED PHOTOS, PLEASE REFER TO ENG-SOW-10007.

	MI CHECKLIST	
CONSTRUCTION/INSTALLATION INSPECTIONS AND TESTING REQUIRED (COMPLETED BY EOR)	REPORT ITEM	
	PRE-CONSTRUCTION	
x	MI CHECKLIST DRAWINGS	
×	TIOR APPROVED SHOP DRIVATINGS	
x	FABRICATION INSPECTION	
NA.	FABRICATOR CERTIFIED WELD INSPECTION	
×	MATERIAL TEST REPORT (WTR)	
NA	FARRICATOR NDE INSPECTION	
NA NA	NOE REPORT OF MONOPOLE BASE PLATE (AS REQUIRED)	
×	PACKING SLIPS	

TESTING PLAN TO CROWN AND PUF FOR REVIEW . TESTING PLAN SHALL INCLUDE DETAILS REGARDING HOW CONTRACTOR INTEN

TO PREVENT INTERACTION BETWEEN THE TEST PILE AND THE EXISTING FOUNDATION DURING TESTING.				
	CONSTRUCTION			
×	CONSTRUCTION INSPECTIONS			
х	FOUNDATION INSPECTIONS			
Х	CONCRETE COMP. STRENGTH AND SLUMP TESTS			
NA NA	POST INSTALLED ANCHOR ROD VERIFICATION			
NA.	BASE PLATE GROUT VERIFICATION			
NA.	CONTRACTOR'S CERTIFIED WELD INSPECTION			
MA	EARTHWORK: LIFT AND CENSITY			
NA.	ON SITE COLD GALWANZING VERIFICATION			
NA	GUY WIRE TENSION REPORT			
x	GC AS-BUILT DOCUMENTS			
NA	THIRD PARTY DISITE INSPECTION OF BOLT PRETENSION PER CROWN REQUIREMENTS			
NA.	INSPECTION OF AJAX BOLTS AND DIT'S PER REQUIREMENTS ON SHEET \$-3			

TESTING AND INSPECTIONS: VERIFY MICROPILE INSTALLATION DETAILS, SPECIFICALLY INCROPILE SIZES, ORBLI HOLE AMETERS & DEPTHS, GROUT TO AND THAT INSTALLATION WAS PER MANUFACTURER RECOMMENDATION

	POST-CONSTRUCTION	
×	MI INSPECTOR REDUNE OR RECORD DRAWING(S)	
NA NA	THIRD PARTY ONSITE BOLT INSPECTION REPORT	
NA.	POST INSTALLED ANCHOR ROD PULL-OUT TESTING	
×	PHOTOGRAPHS	

ADDITIONAL TESTING AND INSPECTIONS: PROVIDE REPORT DOCUMENTING RESULTS OF MICROPLE INSTALLATION AND PROOF TESTING

NOTE: X DENOTES A DOCUMENT NEEDED FOR THE PM REPORT NA DENOTES A DOCUMENT THAT IS NOT REQUIRED FOR THE PM REPORT





AUG 2 1 2013

**ASBUILT 5-26-14** R.S.T. LCC DEPLOYMENT

PAUL J. FORD AND COMPANY STRUCTURAL ENGINEERS 250 faat Broad Stroat - Sarke 900 - Columbias, Otto 43215 www.gbysket.com **CROWN CASTLE** 

8 PARKMEADOW DRIVE, PITTSFORD, NY 14534 PH: (985) 899-3445 FAX: (985) 899-3446

BU #826222; NEWTOWN/RT-25 NEWTOWN, CT

MONOPOLE REINFORCEMENT AND RETROFIT PROJECT

37513-1642 DRAWN BY: B.M.S CHECKED BY K.A.T.

ISSUE DATE OF PERMIT: 8-20-2013

# 6.3.2 PHOTOGRAPHS





# 6.3.3 POST INSTALLED MICROPILE PULL-OUT TESTING

# Stephen Teti

From: Kyle Thorpe

Sent: Monday, April 14, 2014 10:31 AM

To: Stephen Teti

Cc: David Campbell; James Yavorsky; Jeff Hemmings; Justin Kline; Keith\_Stackhouse;

rich\_taschek@lcc.com

Subject: Re: Newton - 25 826222 anchor plates

Hey Steve,

The (4) anchors are required since the micropiles are acting in tension and compression. We need the anchors to be embedded into the concrete pad. Let me know if this is not possible or if you have any othr oncerns.

The sacrificial test pile is fine. Are you intending to reduce the embed length? If so, please contact us with the results of the test pile prior to installation of the working piles.

I don't quite understand what you mean by "max of the pump". Feel free to call to discuss.

Thank you,

Kyle Thorpe, E.I. Structural Designer Main: (614) 221-6679 ext. 2168 Direct: (614) 448-4168 Email: kthorpe@pjfweb.com




>>> Stephen Teti <stephen\_teti@lcc.com> 4/14/2014 9:53 AM >>>

Kyle:

As discussed please review and let us know if the bearing plate will still require the 4 anchor bolts or if we can we just push the rods down with drill??

Also might I suggest that we do a sacrificial test pile adjacent to the pad pulled to failure or max of the pump since there is a free zone in the pad and then we can just drive the rod and be done

Thanks



# Stephen J Teti

Sr. Project Manager Structural Division Northern Territory



LCC Deployment Services Inc. 2242 Old Marlton Pike Mariton NJ, 08053 Cell – 609-929-8186 (preferred) Desk - 856-810-1658 ext. 242

Fax- 856-810-1659

Email: stephen\_teti@lcc.com \*\*\*\*\*\*\* please note new email address effective immediately\*\*\*\*\*\*

"Success depends upon previous preparation, and without such preparation there is sure to be failure" ~Confuctus



# Telecommunications Contracting Co., Inc. 2242 Old Mariton Pike, Mariton, NJ 08053 856-810-1658 856-810-1659 (Fax)

# ANCHOR PULL TEST REPORT

SITE NAME: Newtown

ADDRESS: 201 Main Street Newtown CT

CROWN BU #: 826222

**DATE OF TEST: 5/18/14** 

TECHNICIAN: Michael Menzone

SIZE BOLTS: 73/53 Contech Titan Hollow Bar x 34' in depth

QUANTITY OF BOLTS INSTALLED: 4 + 1 Sacrificial Test Pile

**QUANTITY TESTED: 1Test Pile** 

**GROUT USED: Type 2 Portand Cement Colloidal Mixer** 

WEATHER CONDITIONS: 80 Degrees Sunny

JACK TYPE: 150 TON HOLLOW PLUNGER Enerpac RRH-1508

TEST CRITERIA:

PRE TEST 6000 PSI Hold for 5 minutes No Movement - PASS TEST # 1 8800 PSI = 278.5 kips No Movement - PASS TEST # 2 10,000 PSI = 315 Kips No Movement - PASS

COMMENTS: We maxed out the 150 ton RRH 1508 for 5 minutes and could not break the bar. The Contech Hollow bar has a Ultimate capacity of 260.9 Kips.

