



Northeast Site Solutions
Denise Sabo
4 Angela's Way, Burlington CT 06013
203-435-3640
denise@northeastsitesolutions.com

October 7, 2021

Members of the Siting Council
Connecticut Siting Council
Ten Franklin Square
New Britain, CT 06051

RE: Tower Share Application
117 Washington Ave, North Haven, CT 06473
Latitude: 41.396369
Longitude: -72.857686
Site# 806454_Crown_Dish

Dear Ms. Bachman:

This letter and attachments are submitted on behalf of Dish Wireless LLC. Dish Wireless LLC plans to install antennas and related equipment to the tower site located at 117 Washington Ave in North Haven, Connecticut.

Dish Wireless LLC proposes to install three (3) 600/1900 5G MHz antenna and six (6) RRUs, at the 95-foot level of the existing 120-foot monopole tower, one (1) Fiber cables will also be installed. Dish Wireless LLC equipment cabinets will be placed within 7x5 lease area. Included are plans by Infinigy, dated October 6, 2021 Exhibit C. Also included is a structural analysis prepared by Crown Castle, dated June 5, 2021, confirming that the existing tower is structurally capable of supporting the proposed equipment. Attached as Exhibit D. The facility was approved by the CT Siting Council, Docket No. 117 on January 16, 1990. Please see attached Exhibit A.

Please accept this letter as notification pursuant to Regulations of Connecticut State Agencies 16-50aa, of Dish Wireless LLC intent to share a telecommunications facility pursuant to R.C.S.A. 16-50j-88. In accordance with R.C.S.A., a copy of this letter is being sent to First Selectman Michael J. Freda and Laura Magaraci, ZEO for the Town of North Haven, as well as the tower owner (Crown Castle) and property owner (Commercial Investment Group)

The planned modifications of the facility fall squarely within those activities explicitly provided for in R.C.S.A. 16-50j-89.

1. The proposed modification will not result in an increase in the height of the existing structure. The top of the tower is 120-feet; Dish Wireless LLC proposed antennas will be located at a center line height of 95-feet.
2. The proposed modifications will not result in the increase of the site boundary as depicted on the attached site plan.
3. The proposed modifications will not increase noise levels at the facility by six decibels or more, or to levels that exceed local and state criteria. The incremental effect of the proposed changes will be negligible.



4. The operation of the proposed antennas will not increase radio frequency emissions at the facility to a level at or above the Federal Communications Commission safety standard. As indicated in the attached power density calculations, the combined site operations will result in a total power density of 31.42% as evidenced by Exhibit F.

Connecticut General Statutes 16-50aa indicates that the Council must approve the shared use of a telecommunications facility provided it finds the shared use is technically, legally, environmentally, and economically feasible and meets public safety concerns. As demonstrated in this letter, Dish Wireless LLC respectfully indicates that the shared use of this facility satisfies these criteria.

A. Technical Feasibility. The existing monopole has been deemed structurally capable of supporting Dish Wireless LLC proposed loading. The structural analysis is included as Exhibit D.

B. Legal Feasibility. As referenced above, C.G.S. 16-50aa has been authorized to issue orders approving the shared use of an existing tower such as this support tower in North Haven. Under the authority granted to the Council, an order of the Council approving the requested shared use would permit Dish Wireless LLC to obtain a building permit for the proposed installation. Further, a Letter of Authorization is included as Exhibit G, authorizing Dish Wireless LLC to file this application for shared use.

C. Environmental Feasibility. The proposed shared use of this facility would have a minimal environmental impact. The installation of Dish Wireless LLC equipment at the 95-foot level of the existing 120-foot tower would have an insignificant visual impact on the area around the tower. Dish Wireless LLC ground equipment would be installed within the existing facility compound. Dish Wireless LLC shared use would therefore not cause any significant alteration in the physical or environmental characteristics of the existing site. Additionally, as evidenced by Exhibit F, the proposed antennas would not increase radio frequency emissions to a level at or above the Federal Communications Commission safety standard.

D. Economic Feasibility. Dish Wireless LLC will be entering into an agreement with the owner of this facility to mutually agreeable terms. As previously mentioned, the Letter of Authorization has been provided by the owner to assist Dish Wireless LLC with this tower sharing application.

E. Public Safety Concerns. As discussed above, the tower is structurally capable of supporting Dish Wireless LLC proposed loading. Dish Wireless LLC is not aware of any public safety concerns relative to the proposed sharing of the existing guyed tower. Dish Wireless LLC intentions of providing new and improved wireless service through the shared use of this facility is expected to enhance the safety and welfare of local residents and individuals traveling through North Haven.

Sincerely,

Denise Sabo

Denise Sabo
Mobile: 203-435-3640
Fax: 413-521-0558
Office: 4 Angela's Way, Burlington CT 06013
Email: denise@northeastsitesolutions.com



NSS **NORTHEAST**
SITE SOLUTIONS
Turnkey Wireless Development

Attachments cc:

Michael J. Freda, First Selectman
Town of North Haven
5 Linsley Street, North Haven CT 06473

Laura Magaraci, ZEO
Town of North Haven -Annex Building
5 Linsley Street, North Haven CT 06473

Commercial Investment Group LLC
c/o Mr. Joseph Moruzzi
2911 Dixwell Ave, Hamden CT 06518

Crown Castle, Tower Owner

Exhibit A

Original Facility Approval

DOCKET NO. 117 - An application of : Connecticut
Metro Mobile CTS of New Haven, Inc., for a :
Certificate of Environmental Compatibility : Siting
and Public Need for the construction, : Council
operation, and maintenance of a cellular :
telephone tower and associated equipment in :
the Town of North Haven, Connecticut. January 16, 1990

DECISION AND ORDER

Pursuant to the foregoing Findings of Fact and Opinion, the Connecticut Siting Council finds that the effects associated with the construction, operation, and maintenance of cellular telephone facility at the alternate North Haven site, including effects on the natural environment; ecological integrity and balance; public health and safety; scenic, historic, and recreational values; forests and parks; air and water purity; and fish and wildlife are not significant either alone or cumulatively with other effects, are not in conflict with the policies of the State concerning such effects, and are not sufficient reason to deny the application, and therefore directs that a Certificate of Environmental Compatibility and Public Need, as provided by Section 16-50k of the General Statutes of Connecticut (CGS), be issued to Metro Mobile CTS of New Haven, Inc., for the construction, operation, and maintenance of a cellular telecommunications tower, associated equipment, and building at the alternate site in North Haven, Connecticut.

The facility shall be constructed, operated, and maintained substantially as specified in the Council's record in this matter, and subject to the following conditions:

1. The self-supporting, monopole tower including antennas and associated equipment shall not exceed a height of 133 feet AGL.
2. The facility shall be constructed in accordance with the State of Connecticut Basic Building Code.
3. The Certificate Holder shall prepare a Development and Management (D&M) Plan for this site which shall include detailed plans of the site preparation with specifications for the tower foundation.
4. The Certificate Holder shall comply with any future radio frequency (RF) standard, promulgated by State or federal regulatory agencies. Upon the establishment of any new governmental RF standards, the facility granted

in this Decision and Order shall be brought into compliance with such standards.

5. The Certificate Holder or its successor shall provide the Council a recalculated report of power density if and when additional channels over the proposed 90 channels, higher wattage over the proposed 100 watts per channel, or if other circumstances in operation cause a change in power density above the levels originally calculated in the application.
6. The Certificate Holder or its successor shall permit public or private entities to share space on the North Haven tower for fair consideration, or shall provide any requesting entity with specific legal, technical, environmental, or economic reasons precluding such tower sharing.
7. If this facility does not initially provide, or permanently ceases to provide cellular service following completion of construction, this Decision and Order shall be void, and the tower and all associated equipment in this application shall be dismantled and removed or reapplication of any new use shall be made to the Council before any such new use is made.
8. Unless otherwise approved by the Council, this Decision and Order shall be void if all construction authorized herein is not completed within three years of the issuance of this Decision and Order, or within three years after the completion of any appeal to this Decision and Order.
9. The Applicant shall provide a final report to the Council upon completion of construction, including the final construction cost and date of commercial operation.

Pursuant to Section 16-50p we hereby direct that a copy of the Findings of Fact, Opinion, and Decision and Order be served on each person listed below. A notice of issuance shall be published in the New Haven Register.

By this Decision and Order, the Council disposes of the legal rights, duties, and privileges of each party named or admitted to the proceeding in accordance with section 16-50j-17 of the Regulations of State Agencies.

The parties or intervenors to this proceeding are:

Metro Mobile CTS of
New Haven, Inc.
50 Rockland Road
South Norwalk, CT 06854
ATTN: Phillip Mayberry
General Manager

(Applicant)

Robinson and Cole
One Commercial Plaza
Hartford, CT 06103-3597
ATTN: Earl W. Phillips, Jr., Esq.

(Its Representative)

Luke and Angelina Camarota and
Surv Camarota
303 Washington Avenue
North Haven, CT 06473

(Party)

SNET Cellular, Inc.
227 Church Street
New Haven, CT 06506

(Intervenor)

Peter J. Tyrrell
SNET Cellular, Inc.
Room 1021
227 Church Street
New Haven, CT 06506

(its Representative)

3999E
cp

CERTIFICATION

The undersigned members of the Connecticut Siting Council hereby certify that they have heard this case in Docket No. 117 or read the record thereof, and that we voted as follows:

Dated at New Britain, Connecticut the 16th day of January, 1990.






<u>Council Members</u>	<u>Vote Cast</u>
 Gloria Dibble Pond Chairperson	YES
 Commissioner Peter Boucher Designee: Robert A. Pulito	YES
 Commissioner Leslie Carothers Designee: Brian Emerick	YES
 Harry E. Covey	YES
 Mortimer A. Gelston	YES
_____ Daniel P. Lynch, Jr.	ABSENT
_____ Paulann H. Sheets	ABSENT
_____ William H. Smith	ABSENT
_____ Colin C. Tait	ABSENT

Exhibit B

Property Card

Barbadora, Jeff

From: Barbadora, Jeff
Sent: Monday, November 11, 2019 4:13 PM
To: townclerk@northhaven-ct.gov
Subject: 117 Washington Av - Map 073 Lot 009

Good Afternoon,

I have an inquiry regarding original zoning documents for a cell tower and I am hoping you can provide more information.

We are applying for Connecticut Siting Council (CSC) approval to modify antennas on an existing cell tower and a requirement for the filing by the CSC is that we procure original zoning documents from the jurisdiction, if possible. However, if these documents are not available, please let me know.

The cell tower is located at 117 Washington Ave in North Haven, CT and according to lease documents this may have been approved around 1990/92 and the entity leasing the property would have been Metro Mobile CTS of New Haven, Inc. Owner of the property at that time were Luciani Realty Partnership.

If you have any questions, please don't hesitate to call or e-mail me.

Thanks,

Jeffrey Barbadora
781-970-0053
12 Gill Street, Suite 5800, Woburn, MA 01801
CrownCastle.com

117 WASHINGTON AVE

Location 117 WASHINGTON AVE

Mblu 073/ / 009/ /

Acct# 201742

Owner COMMERCIAL INVESTMENT
GROUP LLC

Assessment \$3,416,280

Appraisal \$4,880,400

PID 8732

Building Count 3

Current Value

Appraisal			
Valuation Year	Improvements	Land	Total
2014	\$1,740,100	\$3,140,300	\$4,880,400

Assessment			
Valuation Year	Improvements	Land	Total
2014	\$1,218,070	\$2,198,210	\$3,416,280

Owner of Record

Owner COMMERCIAL INVESTMENT GROUP LLC
Co-Owner C/O JOSEPH MORUZZI
Address P O BOX 185599
HAMDEN, CT 06518

Sale Price \$6,139,443
Certificate
Book & Page 952/ 916
Sale Date 03/30/2017

Ownership History

Ownership History				
Owner	Sale Price	Certificate	Book & Page	Sale Date
COMMERCIAL INVESTMENT GROUP LLC	\$6,139,443		952/ 916	03/30/2017
NORTH HAVEN SHOPPING CENTER LLC	\$0		952/ 912	03/30/2017
NORTH HAVEN SHOPPING CENTER LLC	\$0		918/ 751	03/18/2015
LUCIANI REALTY LIMITED PARTNERSHIP	\$0		900/ 87	12/30/2013
LUCIANI REALTY LIMITED PARTNERSHIP	\$0	1	431/ 862	05/28/1992

Building Information

Building 1 : Section 1

Year Built: 1952
Living Area: 13,800
Replacement Cost: \$872,105

Building Percent 35
Good:
Replacement Cost
Less Depreciation: \$305,200


Building Photo



(<http://images.vgsi.com/photos/NorthHavenCTPhotos/\00\01\98>)

Building Attributes	
Field	Description
STYLE	Shopping Cntr
MODEL	Comm/Ind
Grade	C -
Stories:	1
Occupancy	12
Exterior Wall 1	Concr/Cinder
Exterior Wall 2	
Roof Structure	Gable/Hip
Roof Cover	Asphalt
Interior Wall 1	Drywall
Interior Wall 2	
Interior Floor 1	Carpet
Interior Floor 2	Ceram Clay Til
Heating Fuel	Oil
Heating Type	Forced Air-Duc
AC Type	Central
Bldg Use	SHOPPING CENTER M94
Total Rooms	
Total Bedrms	
Total Baths	
1st Floor Use:	
Heat/AC	HEAT/AC PKGS
Frame Type	FIREPRF STEEL
Baths/Plumbing	AVERAGE
Ceiling/Wall	CEIL & WALLS
Rooms/Prtns	AVERAGE
Wall Height	12
% Comn Wall	

Building Layout



Building Sub-Areas (sq ft)			Legend
Code	Description	Gross Area	Living Area
BAS	First Floor	13,800	13,800
CAN	Canopy	1,840	0
UBM	Basement, Unfinished	13,800	0
		29,440	13,800

Building 2 : Section 1

Year Built: 1962
Living Area: 41,446
Replacement Cost: \$2,429,016
Building Percent 40
Good:
Replacement Cost
Less Depreciation: \$971,600


Field	Description
STYLE	Shopping Cntr
MODEL	Comm/Ind
Grade	C -
Stories:	1
Occupancy	6
Exterior Wall 1	Concr/Cinder
Exterior Wall 2	
Roof Structure	Flat
Roof Cover	T&G/Rubber
Interior Wall 1	Drywall
Interior Wall 2	
Interior Floor 1	Linoleum
Interior Floor 2	Carpet
Heating Fuel	Oil
Heating Type	Forced Air-Duc
AC Type	Central
Bldg Use	SHOPPING CENTER M94
Total Rooms	
Total Bedrms	
Total Baths	
1st Floor Use:	
Heat/AC	HEAT/AC PKGS
Frame Type	WOOD FRAME
Baths/Plumbing	AVERAGE
Ceiling/Wall	CEIL & WALLS
Rooms/Prtns	AVERAGE
Wall Height	16
% Comn Wall	

Building Photo



(<http://images.vgsi.com/photos/NorthHavenCTPhotos/\00\01\98>)

Building Layout



Building Sub-Areas (sq ft)			Legend	
Code	Description	Gross Area	Living Area	
BAS	First Floor	41,446	41,446	
CAN	Canopy	3,564	0	
UBM	Basement, Unfinished	41,446	0	
ULP	Loading Platform, Unfinished	832	0	
		87,288	41,446	

Building 3 : Section 1

Year Built: 2014
Living Area: 5,100
Replacement Cost: \$735,779
Building Percent Good: 75
Replacement Cost Less Depreciation: \$551,800

Building Attributes : Bldg 3 of 3	
Field	Description
STYLE	Branch Bank


Building Photo

Building Photo

(<http://images.vgsi.com/photos/NorthHavenCTPhotos/\00\02\18>)

MODEL	Comm/Ind
Grade	C +
Stories:	2
Occupancy	1
Exterior Wall 1	Clapboard
Exterior Wall 2	
Roof Structure	Gable/Hip
Roof Cover	Asphalt
Interior Wall 1	Drywall
Interior Wall 2	
Interior Floor 1	Carpet
Interior Floor 2	
Heating Fuel	Gas
Heating Type	Forced Air-Duc
AC Type	Central
Bldg Use	BANK BLDG
Total Rooms	
Total Bedrms	
Total Baths	
1st Floor Use:	
Heat/AC	HEAT/AC PKGS
Frame Type	WOOD FRAME
Baths/Plumbing	AVERAGE
Ceiling/Wall	SUS-CEIL & WL
Rooms/Prtns	AVERAGE
Wall Height	8
% Comn Wall	

Building Layout



Building Sub-Areas (sq ft)			Legend
Code	Description	Gross Area	Living Area
AOF	Office	2,550	2,550
BAS	First Floor	2,550	2,550
CAN	Canopy	432	0
		5,532	5,100

© 2010 BENTON & BOWLES, INC. ALL RIGHTS RESERVED. BENTON & BOWLES, INC. IS A TRADEMARK OF BENTON & BOWLES, INC.

Extra Features

Extra Features				Legend
Code	Description	Size	Value	Bldg #
CLR1	COOLER	98 S.F.	\$700	1
OVHD	OVER HEADDOOR	400 S.F.	\$0	2
SPR1	SPRINKLERS-WET	29440 S.F.	\$9,300	1
ATM1	ATM	1 UNITS	\$6,200	2
SPR1	SPRINKLERS-WET	82892 S.F.	\$29,800	2

Land

Land Use

Land Line Valuation

Use Code 3230
Description SHOPPING CENTER M94
Zone IL30
Neighborhood 301
Alt Land Appr No
Category

Size (Acres) 6.09
Frontage
Depth
Assessed Value \$2,198,210
Appraised Value \$3,140,300

Outbuildings

Outbuildings						Legend
Code	Description	Sub Code	Sub Description	Size	Value	Bldg #
PAV1	PAVING-ASPHALT			128300 S.F.	\$86,600	1
PAV1	PAVING-ASPHALT			128300 S.F.	\$86,600	2
TWR1	COMMU-TOWER			1 UNITS	\$125,000	2

Valuation History

Appraisal			
Valuation Year	Improvements	Land	Total
2013	\$2,080,000	\$3,045,000	\$5,125,000
2008	\$2,096,400	\$1,982,400	\$4,078,800
2007		\$1,364,160	\$2,750,160

Assessment			
Valuation Year	Improvements	Land	Total
2013	\$1,456,000	\$2,131,500	\$3,587,500
2008	\$1,467,480	\$1,387,680	\$2,855,160
2007		\$1,364,160	\$2,750,160

(c) 2016 Vision Government Solutions, Inc. All rights reserved.

Site Name: North Haven CT
 Cumulative Power Density

Operator	Operating Frequency (MHz)	Number of Trans.	ERP Per Trans. (watts)	Total ERP (watts)	Distance to Target (feet)	Calculated Power Density (mW/cm ²)	Maximum Permissible Exposure* (mW/cm ²)	Fraction of MPE (%)
VZW 700	746	4	628	2511.04	119	0.0638	0.4973333333	12.82%
VZW Cellular	869	1	643	642.83	119	0.0163	0.5793333333	2.82%
VZW Cellular	880	4	364	1454.32	119	0.0369	0.5866666667	6.30%
VZW PCS	1970	4	1525	6100.4	119	0.1549	1.0	15.49%
VZW AWS	2145	4	1493	5972.52	119	0.1517	1.0	15.17%
VZW CBRS	3550	4	23	93.44	119	0.0024	1.0	0.24%
Total Percentage of Maximum Permissible Exposure								52.83%

*Guidelines adopted by the FCC on August 1, 1996, 47 CFR Section 1.13101 based on NCRP Report 86, 1986 and generally on ANSI/IEEE C95.1-1992

MHz = Megahertz

mW/cm² = milliwatts per square centimeter

ERP = Effective Radiated Power

Absolute worst case maximum values used, including the following assumptions:

1. closest accessible point is distance from antenna to base of pole;
2. continuous transmission from all available channels at full power for indefinite time period; and,
3. all RF energy is assumed to be directed solely to the base of the pole.

Exhibit C

Construction Drawings



DISH Wireless L.L.C. SITE ID:

BOHVN00011A

DISH Wireless L.L.C. SITE ADDRESS:

**117 WASHINGTON AVENUE
NORTH HAVEN, CT 06473**

SCOPE OF WORK

THIS IS NOT AN ALL INCLUSIVE LIST. CONTRACTOR SHALL UTILIZE SPECIFIED EQUIPMENT PART OR ENGINEER APPROVED EQUIVALENT. CONTRACTOR SHALL VERIFY ALL NEEDED EQUIPMENT TO PROVIDE A FUNCTIONAL SITE. THE PROJECT GENERALLY CONSISTS OF THE FOLLOWING:

- TOWER SCOPE OF WORK:**
- INSTALL (3) PROPOSED PANEL ANTENNAS (1 PER SECTOR)
 - INSTALL (1) PROPOSED ANTENNA MOUNTS
 - INSTALL PROPOSED JUMPERS
 - INSTALL (6) PROPOSED RRU's (2 PER SECTOR)
 - INSTALL (1) PROPOSED OVER VOLTAGE PROTECTION DEVICE (OVP)
 - INSTALL (1) PROPOSED HYBRID CABLE
 - REMOVE TOWER MOUNTED EQUIPMENT AT 90'

- GROUND SCOPE OF WORK:**
- INSTALL (1) PROPOSED METAL PLATFORM
 - UTILIZED EXISTING ICE BRIDGE
 - INSTALL (1) PROPOSED PPC CABINET
 - INSTALL (1) PROPOSED EQUIPMENT CABINET
 - INSTALL (1) PROPOSED POWER CONDUIT
 - INSTALL (1) PROPOSED TELCO CONDUIT
 - INSTALL (1) PROPOSED TELCO-FIBER BOX
 - INSTALL (1) PROPOSED GPS UNIT
 - INSTALL (1) PROPOSED SAFETY SWITCH (IF REQUIRED)
 - INSTALL (1) PROPOSED FIBER NID (IF REQUIRED)
 - EXISTING METER SOCKET ON EXISTING H-FRAME TO BE UTILIZED
 - REMOVE EXISTING H-FRAME PIPES AND EQUIPMENT INSTALLED ON H-FRAME
 - REMOVE EXISTING 6 RUNS OF 1-5/8" FEEDLINES

SITE INFORMATION

PROPERTY OWNER: COMMERCIAL INVESTMENT GROUP LLC
 ADDRESS: PO BOX 185599
 HAMDEN, CT 06518
 TOWER TYPE: MONOPOLE
 TOWER CO SITE ID: 806454
 TOWER APP NUMBER: 553355
 COUNTY: NEW HAVEN
 LATITUDE (NAD 83): 41° 23' 46.93" N
 41.396369 N
 LONGITUDE (NAD 83): 72° 51' 27.67" W
 72.857686 W
 ZONING JURISDICTION: TOWN OF NORTH HAVEN
 ZONING DISTRICT: IL30
 PARCEL NUMBER: 201742
 OCCUPANCY GROUP: U
 CONSTRUCTION TYPE: V-B
 POWER COMPANY: UNITED ILLUMINATING COMPANY
 TELEPHONE COMPANY: TBD

PROJECT DIRECTORY

APPLICANT: DISH Wireless L.L.C.
 5701 SOUTH SANTA FE DRIVE
 LITTLETON, CO 80120
 TOWER OWNER: CROWN CASTLE
 2000 CORPORATE DRIVE
 CANONSBURG, PA 15317
 (877) 486-9377
 SITE DESIGNER: INFINIGY
 2500 W. HIGGINS RD. SUITE 500
 HOFFMAN ESTATES, IL 60169
 (847) 648-4068
 SITE ACQUISITION: NICHOLAS CURRY
 NICHOLAS.CURRY@crowncastle.com
 CONSTRUCTION MANAGER: JAVIER SOTO
 JAVIER.SOTO@dish.com
 RF ENGINEER: SYED ZAIDI
 SYED.ZAIDI@dish.com




5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



2000 CORPORATE DRIVE
CANONSBURG, PA 15317



FROM ZERO TO INFINIGY
 the solutions are endless
 2500 W. HIGGINS RD. SUITE 500 |
 HOFFMAN ESTATES, IL 60169
 PHONE: 847-648-4068 | FAX: 518-690-0793
 WWW.INFINIGY.COM



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY: RCD
 CHECKED BY: SS
 APPROVED BY: CJW

RFDS REV #: ---

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	07/01/2021	ISSUED FOR REVIEW
O	08/31/2021	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
6039-Z0001-C

DISH Wireless L.L.C.
PROJECT INFORMATION
BOHVN00011A
117 WASHINGTON AVENUE
NORTH HAVEN, CT 06473

SHEET TITLE
TITLE SHEET

SHEET NUMBER
T-1

CONNECTICUT CODE COMPLIANCE

ALL WORK SHALL BE PERFORMED AND MATERIALS INSTALLED IN ACCORDANCE WITH THE CURRENT EDITIONS OF THE FOLLOWING CODES AS ADOPTED BY THE LOCAL GOVERNING AUTHORITIES. NOTHING IN THESE PLANS IS TO BE CONSTRUED TO PERMIT WORK NOT CONFORMING TO THESE CODES:

CODE TYPE	CODE
BUILDING	2018 CT STATE BUILDING CODE/2015 IBC W/ CT AMENDMENTS
MECHANICAL	2018 CT STATE BUILDING CODE/2015 IMC W/ CT AMENDMENTS
ELECTRICAL	2018 CT STATE BUILDING CODE/2017 NEC W/ CT AMENDMENTS

SITE PHOTO



UNDERGROUND SERVICE ALERT CBYD 811
 UTILITY NOTIFICATION CENTER OF CONNECTICUT
 (800) 922-4455
 WWW.CBYD.COM
 CALL 2 WORKING DAYS UTILITY NOTIFICATION PRIOR TO CONSTRUCTION



GENERAL NOTES

THE FACILITY IS UNMANNED AND NOT FOR HUMAN HABITATION. A TECHNICIAN WILL VISIT THE SITE AS REQUIRED FOR ROUTINE MAINTENANCE. THE PROJECT WILL NOT RESULT IN ANY SIGNIFICANT DISTURBANCE OR EFFECT ON DRAINAGE, NO SANITARY SEWER SERVICE, POTABLE WATER, OR TRASH DISPOSAL IS REQUIRED AND NO COMMERCIAL SIGNAGE IS PROPOSED.


11"x17" PLOT WILL BE HALF SCALE UNLESS OTHERWISE NOTED

CONTRACTOR SHALL VERIFY ALL PLANS, EXISTING DIMENSIONS, AND CONDITIONS ON THE JOB SITE, AND SHALL IMMEDIATELY NOTIFY THE ENGINEER IN WRITING OF ANY DISCREPANCIES BEFORE PROCEEDING WITH THE WORK.

DIRECTIONS

DIRECTIONS FROM TWEED NEW HAVEN AIRPORT:
 DEPART AND HEAD (NORTHEAST), TURN LEFT, AVIS RENT A CAR ON THE CORNER, TURN RIGHT, TURN RIGHT TOWARD FORT HALE RD, BUDGET CAR RENTAL ON THE CORNER, KEEP STRAIGHT TO GET ONTO FORT HALE RD, TURN RIGHT ONTO CT-337 / TOWNSEND AVE, TURN LEFT ONTO MAIN STREET ANNEX, TAKE THE RAMP ON THE RIGHT FOR I-95 S / GOVERNOR JOHN DAVIS LODGE TPKE S, TAKE THE RAMP ON THE RIGHT FOR I-91 NORTH AND HEAD TOWARD DOWNTOWN NEW HAVEN / HARTFORD, AT EXIT 12, HEAD RIGHT ON THE RAMP FOR WASHINGTON AVE TOWARD NORTH HAVEN, TURN LEFT ONTO US-5 S / WASHINGTON AVE TOWARD NORTH HAVEN / WASHINGTON AVE, MINOR CONGESTION, TURN RIGHT, MCDONALD'S ON THE CORNER, UNPAVED ROAD, ARRIVE AT 117 WASHINGTON AVENUE NORTH HAVEN, CT 06473

VICINITY MAP



NOTES

1. CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS.
2. ANTENNAS AND MOUNTS OMITTED FOR CLARITY.

NOTES

1. CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS.
2. CONTRACTOR SHALL MAINTAIN A 10'-0" MINIMUM SEPARATION BETWEEN THE PROPOSED GPS UNIT, TRANSMITTING ANTENNAS AND EXISTING GPS UNITS.
3. ANTENNAS AND MOUNTS OMITTED FOR CLARITY.

dish
wireless.


5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120

CROWN
CASTLE

2000 CORPORATE DRIVE
CANONSBURG, PA 15317

INFINIGY

FROM ZERO TO INFINIGY
the solutions are endless
2500 W. HIGGINS RD., SUITE 500 |
HOFFMAN ESTATES, IL 60169
PHONE: 847-648-4068 | FAX: 518-690-0793
WWW.INFINIGY.COM



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY: CHECKED BY: APPROVED BY:
RCD SS CJW

RFDS REV #: ---

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	07/01/2021	ISSUED FOR REVIEW
0	08/31/2021	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
6039-Z0001-C


DISH Wireless L.L.C.
PROJECT INFORMATION

BOHVN00011A
117 WASHINGTON AVENUE
NORTH HAVEN, CT 06473


SHEET TITLE
OVERALL AND ENLARGED
SITE PLAN

SHEET NUMBER


A-1




OVERALL SITE PLAN



1




ENLARGED SITE PLAN



2




ACCESS PLAN




3

NOTES


1. CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS.
2. ANTENNA SPECIFICATIONS REFER TO ANTENNA SCHEDULE AND TO FINAL CONSTRUCTION RFDS FOR ALL RF DETAILS
3. EXISTING EQUIPMENT AND FENCE OMITTED FOR CLARITY.
4. INFINIGY HAS NOT EVALUATED THE TOWER OR MOUNT STRUCTURE AND ASSUMES NO RESPONSIBILITY FOR THEIR STRUCTURAL INTEGRITY REGARDING PROPOSED LOADINGS. FINAL INSTALLATION SHALL COMPLY WITH RESULTS OF PASSING STRUCTURAL ANALYSES PERFORMED BY OTHERS.




PROPOSED NORTHWEST ELEVATION



1



ANTENNA LAYOUT



2

SECTOR	POSITION	ANTENNA						TRANSMISSION CABLE
		EXISTING OR PROPOSED	MANUFACTURER - MODEL NUMBER	TECHNOLOGY	SIZE (HxW)	AZMUTH	RAD CENTER	FEED LINE TYPE AND LENGTH
ALPHA	A1	PROPOSED	JMA WIRELESS - MX08FRO665-21	5G	72.0" x 20.0"	0°	95'-0"	(1) HIGH-CAPACITY HYBRID CABLE (122' LONG)
BETA	B1	PROPOSED	JMA WIRELESS - MX08FRO665-21	5G	72.0" x 20.0"	120°	95'-0"	
GAMMA	C1	PROPOSED	JMA WIRELESS - MX08FRO665-21	5G	72.0" x 20.0"	240°	95'-0"	

SECTOR	POSITION	RRH		NOTES
		MANUFACTURER - MODEL NUMBER	TECHNOLOGY	
ALPHA	A1	FUJITSU - TA08025-B604	5G	1. CONTRACTOR TO REFER TO FINAL CONSTRUCTION RFDS FOR ALL RF DETAILS. 2. ANTENNA AND RRH MODELS MAY CHANGE DUE TO EQUIPMENT AVAILABILITY. ALL EQUIPMENT CHANGES MUST BE APPROVED AND REMAIN IN COMPLIANCE WITH THE PROPOSED DESIGN AND STRUCTURAL ANALYSES.
	A1	FUJITSU - TA08025-B605	5G	
BETA	B1	FUJITSU - TA08025-B604	5G	
	B1	FUJITSU - TA08025-B605	5G	
GAMMA	C1	FUJITSU - TA08025-B604	5G	
	C1	FUJITSU - TA08025-B605	5G	

ANTENNA SCHEDULE

NO SCALE

3




5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



2000 CORPORATE DRIVE
CANONSBURG, PA 15317



FROM ZERO TO INFINIGY
the solutions are endless
2500 W. HIGGINS RD., SUITE 500 |
HOFFMAN ESTATES, IL 60169
PHONE: 847-648-4068 | FAX: 518-690-0793
WWW.INFINIGY.COM



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY: RCD | CHECKED BY: SS | APPROVED BY: CJW

RFDS REV #: ---

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	07/01/2021	ISSUED FOR REVIEW
0	08/31/2021	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
6039-Z0001-C

DISH Wireless L.L.C.
PROJECT INFORMATION
BOHVN00011A
117 WASHINGTON AVENUE
NORTH HAVEN, CT 06473

SHEET TITLE
ELEVATION, ANTENNA
LAYOUT AND SCHEDULE

SHEET NUMBER

A-2




5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



2000 CORPORATE DRIVE
CANONSBURG, PA 15317



FROM ZERO TO INFINIGY
the solutions are endless
2500 W. HIGGINS RD., SUITE 500 |
HOFFMAN ESTATES, IL 60169
PHONE: 847-648-4068 | FAX: 518-690-0793
WWW.INFINIGY.COM



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY: CHECKED BY: APPROVED BY:
RCD SS CJW

RFDS REV #: ---

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	07/01/2021	ISSUED FOR REVIEW
0	08/31/2021	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
6039-Z0001-C

DISH Wireless L.L.C.
PROJECT INFORMATION
BOHVN00011A
117 WASHINGTON AVENUE
NORTH HAVEN, CT 06473


SHEET TITLE
EQUIPMENT PLATFORM AND
H-FRAME DETAILS

SHEET NUMBER


A-3

NOTES

1. CONTRACTOR TO BURY PLATFORM FEET WITH A MINIMUM OF 2" OF FILL PER EXISTING SITE SURFACE
2. WEED BARRIER FABRIC TO BE ADDED AT DISCRETION OF DISH Wireless L.L.C. CONSTRUCTION MANAGER AT TIME OF CONSTRUCTION. ONE SHEET 8'x8' INSTALLED UNDER ALL FOUR FEET OF THE PLATFORM (4 MIL BLACK PLASTIC)
3. EQUIPMENT CABINET OMITTED FOR CLARITY



PLATFORM EQUIPMENT PLAN




1

**COMMSCOPE MTC4045LP
5X7 PLATFORM**

DIMENSIONS (HxWxD)	16"x84"x60"
TOTAL WEIGHT	423 LBS

NOTE:
GC TO PROVIDE EXTENDED
THREAD FOR PLATFORM IF
REQUIRED HEIGHT EXCEEDS 17"





PLATFORM DETAIL

NO SCALE 2

**COMMSCOPE MTC4045HFLD
H-FRAME**

UNISTRUT/SUPPORT RAILS QTY	5
WEIGHT	59.74 lbs

NOTE:
OR DISH Wireless L.L.C.
APPROVED EQUIVALENT




H-FRAME DETAIL

NO SCALE 3


NOT USED

NO SCALE 4


H-FRAME EQUIPMENT ELEVATION




5




FRONT ELEVATION




BACK ELEVATION



CABINET DETAIL NO SCALE 1




POWER PROTECTION CABINET (PPC) DETAIL NO SCALE 2




SAFETY SWITCH DETAIL NO SCALE 3




NOT USED NO SCALE 4




NETWORK INTERFACE UNIT DETAIL NO SCALE 5




FIBER TELCO ENCLOSURE DETAIL NO SCALE 6



NOT USED NO SCALE 7



NOT USED NO SCALE 8



HYBRID CABLE RUN NO SCALE 9

5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120

2000 CORPORATE DRIVE
CANONSBURG, PA 15317

FROM ZERO TO INFINIGY
the solutions are endless
2500 W. HIGGINS RD., SUITE 500 |
HOFFMAN ESTATES, IL 60169
PHONE: 847-648-4068 | FAX: 518-690-0793
WWW.INFINIGY.COM

STATE OF CONNECTICUT
SHUHEI SAKANOUÉ
34916
LICENSED PROFESSIONAL ENGINEER
10/6/2021

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
RCD	SS	CJW

RFDS REV #: ---

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	07/01/2021	ISSUED FOR REVIEW
0	08/31/2021	ISSUED FOR CONSTRUCTION


A&E PROJECT NUMBER
6039-Z0001-C

DISH Wireless L.L.C.
PROJECT INFORMATION
BOHVN00011A
117 WASHINGTON AVENUE
NORTH HAVEN, CT 06473


SHEET TITLE
EQUIPMENT DETAILS

SHEET NUMBER
A-4


PCTEL GPSGL-TMG-SPI-40NCB	
DIMENSIONS (DIAxH) MM/INCH	81x184mm 3.2"x7.25"
WEIGHT W/ACCESSORIES	075 lbs
CONNECTOR	N-FEMALE
FREQUENCY RANGE	1590 ± 30MHz





TOP



BACK



SIDE



GPS DETAIL

NO SCALE

1

GPS MINIMUM SKY VIEW REQUIREMENTS

NO SCALE

2

CABLES UNLIMITED HYBRID CABLE
MINIMUM BEND RADIUSES

NO SCALE

3

NOT USED

NO SCALE

4

NOT USED

NO SCALE

5

NOT USED

NO SCALE

6

NOT USED

NO SCALE

7

NOT USED

NO SCALE

8

NOT USED

NO SCALE

9

dish
wireless.

5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120


CROWN
CASTLE

2000 CORPORATE DRIVE
CANONSBURG, PA 15317

INFINIGY

FROM ZERO TO INFINIGY

the solutions are endless
2500 W. HIGGINS RD., SUITE 500 |
HOFFMAN ESTATES, IL 60169
PHONE: 847-648-4068 | FAX: 518-690-0793
WWW.INFINIGY.COM



IT IS A VIOLATION OF LAW FOR ANY PERSON,
UNLESS THEY ARE ACTING UNDER THE DIRECTION
OF A LICENSED PROFESSIONAL ENGINEER,
TO ALTER THIS DOCUMENT.

DRAWN BY: CHECKED BY: APPROVED BY:
RCD SS CJW

RFDS REV #: ---

CONSTRUCTION
DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	07/01/2021	ISSUED FOR REVIEW
0	08/31/2021	ISSUED FOR CONSTRUCTION





A&E PROJECT NUMBER
6039-Z0001-C

DISH Wireless L.L.C.
PROJECT INFORMATION
BOHVN00011A
117 WASHINGTON AVENUE
NORTH HAVEN, CT 06473

SHEET TITLE
EQUIPMENT DETAILS

SHEET NUMBER
A-5

FUJITSU TRIPLE BAND TA08025-B605	
DIMENSIONS (HxWxD)	14.9"x15.7"x9"
WEIGHT	74.95 lbs
CONNECTOR TYPE	4.3-10 RF CONNECTOR
POWER SUPPLY	DC -58~-36V







BACK

SIDE

FRONT

FUJITSU DUAL BAND TA08025-B604	
DIMENSIONS (HxWxD)	14.9"x15.7"x7.8"
WEIGHT	63.9 lbs
CONNECTOR TYPE	4.3-10 RF CONNECTOR
POWER SUPPLY	DC -58~-36V





BACK

SIDE

FRONT

SABRE DOUBLE Z-BRACKET C10123155	
DIMENSIONS (HxWxD) (1 BRACKET)	5"x20"x1-13/16"
WEIGHT (FULL ASSEMBLY)	35.79 lbs
PACKAGE QUANTITY	4

#	DESCRIPTION
1	PLATE, CHANNEL BRACKET
2	RRH Z BRACKET, 3/16"
3	THREADED ROD ASSEMBLY 1/2"x12"



NOTE:
OR DISH Wireless L.L.C.
APPROVED EQUIVALENT

RRH DETAIL

NO SCALE

1

RRH DETAIL

NO SCALE





2

RRH MOUNT DETAIL

NO SCALE

3

RAYCAP RDIDC-9181-PF-48 DC SURGE PROTECTION (OVP)	
DIMENSIONS (HxWxD)	18.98"x14.39"x8.15"
WEIGHT	21.82 LBS




SIDE

BACK

FRONT

JMA WIRELESS MX08FR0665-21 ANTENNA	
DIMENSIONS (HxWxD)	72.8"x20.0"x8.0"
TOTAL WEIGHT	64.5 LB
RF PORTS, CONNECTOR TYPE	8 x 4.3-10 FEMALE



BACK

SIDE

FRONT


NOTES

FINAL ANTENNA SPECIFICATIONS
TO BE CONFIRMED BY GC



M04 MOUNTING BRACKET
HPA-33R-BUU-H4-K

WIDTH	5"
DEPTH	2"
HEIGHT	8"
TOTAL WEIGHT	1.5 lbs
HOUSING MATERIAL	ASA/ABS/ALUMINUM
RADOME COLOR	LIGHT GRAY
CONNECTOR	1x8-PIN DAISY CHAIN



NOTE:
OR DISH Wireless L.L.C.
APPROVED EQUIVALENT

SURGE SUPPRESSION DETAIL (OVP)

NO SCALE

4

ANTENNA DETAIL

NO SCALE

5


ANTENNA MOUNTING DETAIL

NO SCALE

6


COMMSCOPE XP-2040 CROSSOVER PLATE	
DIMENSIONS (HxW)	10"x12"
WEIGHT	11 lbs

NOTE:
OR DISH Wireless L.L.C.
APPROVED EQUIVALENT




PLAN PLATE

SIDE PLATE




PLAN U-BOLT

SIDE U-BOLT




COMMSCOPE MC-PK8-DSH	
FACE WIDTH	96"
WEIGHT	1373.08 lbs
NOTE: 15" TO 38" O.D.	

NOTE:
OR DISH Wireless L.L.C.
APPROVED EQUIVALENT



FACE PIPE



96"

ANTENNA PLATFORM DETAIL

NO SCALE

8

NOT USED

NO SCALE

9

dish
wireless.

5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120


**CROWN
CASTLE**

2000 CORPORATE DRIVE
CANONSBURG, PA 15317

INFINIGY

FROM ZERO TO INFINIGY

the solutions are endless
2500 W. HIGGINS RD., SUITE 500 |
HOFFMAN ESTATES, IL 60169
PHONE: 847-648-4068 | FAX: 518-690-0793
WWW.INFINIGY.COM



IT IS A VIOLATION OF LAW FOR ANY PERSON,
UNLESS THEY ARE ACTING UNDER THE DIRECTION
OF A LICENSED PROFESSIONAL ENGINEER,
TO ALTER THIS DOCUMENT.

DRAWN BY: CHECKED BY: APPROVED BY:
RCD SS CJW

RFDS REV #: ---

CONSTRUCTION
DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	07/01/2021	ISSUED FOR REVIEW
0	08/31/2021	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
6039-Z0001-C

DISH Wireless L.L.C.
PROJECT INFORMATION

BOHVN00011A
117 WASHINGTON AVENUE
NORTH HAVEN, CT 06473

SHEET TITLE
EQUIPMENT DETAILS

SHEET NUMBER

A-6

NOTES

1. CONTRACTOR SHALL FIELD VERIFY ALL PROPOSED UNDERGROUND UTILITY CONDUIT ROUTE.
2. ANTENNAS AND MOUNTS OMITTED FOR CLARITY.

DC POWER WIRING SHALL BE COLOR CODED AT EACH END FOR IDENTIFYING +24V AND -48V CONDUCTORS. RED MARKINGS SHALL IDENTIFY +24V AND BLUE MARKINGS SHALL IDENTIFY -48V.

1. CONTRACTOR SHALL INSPECT THE EXISTING CONDITIONS PRIOR TO SUBMITTING A BID. ANY QUESTIONS ARISING DURING THE BID PERIOD IN REGARDS TO THE CONTRACTOR'S FUNCTIONS, THE SCOPE OF WORK, OR ANY OTHER ISSUE RELATED TO THIS PROJECT SHALL BE BROUGHT UP DURING THE BID PERIOD WITH THE PROJECT MANAGER FOR CLARIFICATION, NOT AFTER THE CONTRACT HAS BEEN AWARDED.
2. ALL ELECTRICAL WORK SHALL BE DONE IN ACCORDANCE WITH CURRENT NATIONAL ELECTRICAL CODES AND ALL STATE AND LOCAL CODES, LAWS, AND ORDINANCES. PROVIDE ALL COMPONENTS AND WIRING SIZES AS REQUIRED TO MEET NEC STANDARDS.
3. LOCATION OF EQUIPMENT, CONDUIT AND DEVICES SHOWN ON THE DRAWINGS ARE APPROXIMATE AND SHALL BE COORDINATED WITH FIELD CONDITIONS PRIOR TO CONSTRUCTION.
4. CONDUIT ROUGH-IN SHALL BE COORDINATED WITH THE MECHANICAL EQUIPMENT TO AVOID LOCATION CONFLICTS. VERIFY WITH THE MECHANICAL EQUIPMENT CONTRACTOR AND COMPLY AS REQUIRED.
5. CONTRACTOR SHALL PROVIDE ALL BREAKERS, CONDUITS AND CIRCUITS AS REQUIRED FOR A COMPLETE SYSTEM.
6. CONTRACTOR SHALL PROVIDE PULL BOXES AND JUNCTION BOXES AS REQUIRED BY THE NEC ARTICLE 314.
7. CONTRACTOR SHALL PROVIDE ALL STRAIN RELIEF AND CABLE SUPPORTS FOR ALL CABLE ASSEMBLIES. INSTALLATION SHALL BE IN ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS AND RECOMMENDATIONS.
8. ALL DISCONNECTS AND CONTROLLING DEVICES SHALL BE PROVIDED WITH ENGRAVED PHENOLIC NAMEPLATES INDICATING EQUIPMENT CONTROLLED, BRANCH CIRCUITS INSTALLED ON, AND PANEL FIELD LOCATIONS FED FROM.
9. INSTALL AN EQUIPMENT GROUNDING CONDUCTOR IN ALL CONDUITS PER THE SPECIFICATIONS AND NEC 250. THE EQUIPMENT GROUNDING CONDUCTORS SHALL BE BONDED AT ALL JUNCTION BOXES, PULL BOXES, AND ALL DISCONNECT SWITCHES, AND EQUIPMENT CABINETS.
10. ALL NEW MATERIAL SHALL HAVE A U.L. LABEL.
11. PANEL SCHEDULE LOADING AND CIRCUIT ARRANGEMENTS REFLECT POST-CONSTRUCTION EQUIPMENT.
12. CONTRACTOR SHALL BE RESPONSIBLE FOR AS-BUILT PANEL SCHEDULE AND SITE DRAWINGS.
13. ALL TRENCHES IN COMPOUND TO BE HAND DUG

dish
wireless.


5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120

CROWN
CASTLE

2000 CORPORATE DRIVE
CANONSBURG, PA 15317

INFINIGY
FROM ZERO TO INFINIGY

the solutions are endless
2500 W. HIGGINS RD., SUITE 500 |
HOFFMAN ESTATES, IL 60169
PHONE: 847-648-4068 | FAX: 518-690-0793
WWW.INFINIGY.COM



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY: RCD
CHECKED BY: SS
APPROVED BY: CJW

RFDS REV #: ---

CONSTRUCTION DOCUMENTS


SUBMITTALS		
REV	DATE	DESCRIPTION
A	07/01/2021	ISSUED FOR REVIEW
0	08/31/2021	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
6039-Z0001-C

DISH Wireless L.L.C.
PROJECT INFORMATION
BOHVN00011A
117 WASHINGTON AVENUE
NORTH HAVEN, CT 06473

SHEET TITLE
ELECTRICAL/FIBER ROUTE
PLAN AND NOTES


SHEET NUMBER
E-1



ELECTRICAL NOTES


2

UTILITY ROUTE PLAN



1


ELECTRICAL NOTES



3

CARLON EXPANSION FITTINGS



COUPLING END PART#	MALE TERMINAL ADAPTER END PART#	SIZE	STD CTN QTY.	TRAVEL LENGTH
E945D	E945DX	1/2"	20	4"
E945E	E945EX	3/4"	15	4"
E945F	E945FX	1"	10	4"
E945G	E945GX	1 1/4"	5	4"
E945H	E945HX	1 1/2"	5	4"
E945J	E945JX	2"	15	8"
E945K	E945KX	2 1/2"	10	8"
E945L	E945LX	3"	10	8"
E945M	E945MX	3 1/2"	5	8"
E945N	E945NX	4"	5	8"
E945P	E945PX	5"	1	8"
E945R	E945RX	6"	1	8"



NOTE: CONTRACTOR TO INSTALL EXPANSION FITTING SLIP JOINT AT METER CENTER CONDUIT TERMINATION, AS PER LOCAL UTILITY POLICY, ORDINANCE AND/OR SPECIFIED REQUIREMENT.

TRENCHING NOTES

- CONTRACTOR SHALL RESTORE THE TRENCH TO ITS ORIGINAL CONDITIONS BY EITHER SEEDING OR SODDING GRASS AREAS, OR REPLACING ASPHALT OR CONCRETE AREAS TO ITS ORIGINAL CROSS SECTION.
- TRENCHING SAFETY; INCLUDING, BUT NOT LIMITED TO SOIL CLASSIFICATION, SLOPING, AND SHORING, SHALL BE GOVERNED BY THE CURRENT OSHA TRENCHING AND EXCAVATION SAFETY STANDARDS.
- ALL CONDUITS SHALL BE INSTALLED IN COMPLIANCE WITH THE CURRENT NATIONAL ELECTRIC CODE (NEC) OR AS REQUIRED BY THE LOCAL JURISDICTION, WHICHEVER IS THE MOST STRINGENT.



EXPANSION JOINT DETAIL


NO SCALE 1

TYPICAL UNDERGROUND TRENCH DETAIL

NO SCALE 2

DARK TELCO BOX – INTERIOR WIRING LAYOUT

NO SCALE 3



LIT TELCO BOX – INTERIOR WIRING LAYOUT (OPTIONAL)

NO SCALE 4

NOT USED

NO SCALE 5

NOT USED

NO SCALE 6

NOT USED

NO SCALE 7

NOT USED

NO SCALE 8

NOT USED

NO SCALE 9




5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



2000 CORPORATE DRIVE
CANONSBURG, PA 15317



FROM ZERO TO INFINIGY
the solutions are endless
2500 W. HIGGINS RD., SUITE 500 |
HOFFMAN ESTATES, IL 60169
PHONE: 847-648-4068 | FAX: 518-690-0793
WWW.INFINIGY.COM



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY: CHECKED BY: APPROVED BY:
RCD SS CJW

RFDS REV #: ---

CONSTRUCTION DOCUMENTS


SUBMITTALS		
REV	DATE	DESCRIPTION
A	07/01/2021	ISSUED FOR REVIEW
0	08/31/2021	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
6039-Z0001-C

DISH Wireless L.L.C.
PROJECT INFORMATION
BOHVN00011A
117 WASHINGTON AVENUE
NORTH HAVEN, CT 06473

SHEET TITLE
ELECTRICAL
DETAILS

SHEET NUMBER
E-2




TYPICAL EQUIPMENT GROUNDING PLAN

NO SCALE 1

NOTES

1. ANTENNAS AND OVP SHOWN ARE GENERIC AND NOT REFERENCING TO A SPECIFIC MANUFACTURER. THIS LAYOUT IS FOR REFERENCE ONLY



TYPICAL ANTENNA GROUNDING PLAN

NO SCALE 2

- EXOTHERMIC CONNECTION
- MECHANICAL CONNECTION
- ▬ GROUND BUS BAR
- GROUND ROD
- T TEST GROUND ROD WITH INSPECTION SLEEVE
- #6 AWG STRANDED & INSULATED
- - - #2 AWG SOLID COPPER TINNED
- ▲ BUSS BAR INSULATOR

GROUNDING LEGEND

1. GROUNDING IS SHOWN DIAGRAMMATICALLY ONLY.
2. CONTRACTOR SHALL GROUND ALL EQUIPMENT AS A COMPLETE SYSTEM. GROUNDING SHALL BE IN COMPLIANCE WITH NEC SECTION 250 AND DISH Wireless L.L.C. GROUNDING AND BONDING REQUIREMENTS AND MANUFACTURER'S SPECIFICATIONS.
3. ALL GROUND CONDUCTORS SHALL BE COPPER; NO ALUMINUM CONDUCTORS SHALL BE USED.

GROUNDING KEY NOTES

- (A) **EXTERIOR GROUND RING:** #2 AWG SOLID COPPER, BURIED AT A DEPTH OF AT LEAST 30 INCHES BELOW GRADE, OR 6 INCHES BELOW THE FROST LINE AND APPROXIMATELY 24 INCHES FROM THE EXTERIOR WALL OR FOOTING.
- (B) **TOWER GROUND RING:** THE GROUND RING SYSTEM SHALL BE INSTALLED AROUND AN ANTENNA TOWER'S LEGS, AND/OR GUY ANCHORS. WHERE SEPARATE SYSTEMS HAVE BEEN PROVIDED FOR THE TOWER AND THE BUILDING, AT LEAST TWO BONDS SHALL BE MADE BETWEEN THE TOWER RING GROUND SYSTEM AND THE BUILDING RING GROUND SYSTEM USING MINIMUM #2 AWG SOLID COPPER CONDUCTORS.
- (C) **INTERIOR GROUND RING:** #2 AWG STRANDED GREEN INSULATED COPPER CONDUCTOR EXTENDED AROUND THE PERIMETER OF THE EQUIPMENT AREA. ALL NON-TELECOMMUNICATIONS RELATED METALLIC OBJECTS FOUND WITHIN A SITE SHALL BE GROUND TO THE INTERIOR GROUND RING WITH #6 AWG STRANDED GREEN INSULATED CONDUCTOR.
- (D) **BOND TO INTERIOR GROUND RING:** #2 AWG SOLID TINNED COPPER WIRE PRIMARY BONDS SHALL BE PROVIDED AT LEAST AT FOUR POINTS ON THE INTERIOR GROUND RING, LOCATED AT THE CORNERS OF THE BUILDING.
- (E) **GROUND ROD:** UL LISTED COPPER CLAD STEEL MINIMUM 1/2" DIAMETER BY EIGHT FEET LONG. GROUND RODS SHALL BE INSTALLED WITH INSPECTION SLEEVES. GROUND RODS SHALL BE DRIVEN TO THE DEPTH OF GROUND RING CONDUCTOR.
- (F) **CELL REFERENCE GROUND BAR:** POINT OF GROUND REFERENCE FOR ALL COMMUNICATIONS EQUIPMENT FRAMES. ALL BONDS ARE MADE WITH #2 AWG UNLESS NOTED OTHERWISE STRANDED GREEN INSULATED COPPER CONDUCTORS. BOND TO GROUND RING WITH (2) #2 SOLID TINNED COPPER CONDUCTORS.
- (G) **HATCH PLATE GROUND BAR:** BOND TO THE INTERIOR GROUND RING WITH TWO #2 AWG STRANDED GREEN INSULATED COPPER CONDUCTORS. WHEN A HATCH-PLATE AND A CELL REFERENCE GROUND BAR ARE BOTH PRESENT, THE CRGB MUST BE CONNECTED TO THE HATCH-PLATE AND TO THE INTERIOR GROUND RING USING (2) TWO #2 AWG STRANDED GREEN INSULATED COPPER CONDUCTORS EACH.
- (H) **EXTERIOR CABLE ENTRY PORT GROUND BARS:** LOCATED AT THE ENTRANCE TO THE CELL SITE BUILDING. BOND TO GROUND RING WITH A #2 AWG SOLID TINNED COPPER CONDUCTORS WITH AN EXOTHERMIC WELD AND INSPECTION SLEEVE.
- (I) **TELCO GROUND BAR:** BOND TO BOTH CELL REFERENCE GROUND BAR OR EXTERIOR GROUND RING.
- (J) **FRAME BONDING:** THE BONDING POINT FOR TELECOM EQUIPMENT FRAMES SHALL BE THE GROUND BUS THAT IS NOT ISOLATED FROM THE EQUIPMENTS METAL FRAMEWORK.
- (K) **INTERIOR UNIT BONDS:** METAL FRAMES, CABINETS AND INDIVIDUAL METALLIC UNITS LOCATED WITH THE AREA OF THE INTERIOR GROUND RING REQUIRE A #6 AWG STRANDED GREEN INSULATED COPPER BOND TO THE INTERIOR GROUND RING.
- (L) **FENCE AND GATE GROUNDING:** METAL FENCES WITHIN 7 FEET OF THE EXTERIOR GROUND RING OR OBJECTS BONDED TO THE EXTERIOR GROUND RING SHALL BE BONDED TO THE GROUND RING WITH A #2 AWG SOLID TINNED COPPER CONDUCTOR AT AN INTERVAL NOT EXCEEDING 25 FEET. BONDS SHALL BE MADE AT EACH GATE POST AND ACROSS GATE OPENINGS.
- (M) **EXTERIOR UNIT BONDS:** METALLIC OBJECTS, EXTERNAL TO OR MOUNTED TO THE BUILDING, SHALL BE BONDED TO THE EXTERIOR GROUND RING. USING #2 TINNED SOLID COPPER WIRE
- (N) **ICE BRIDGE SUPPORTS:** EACH ICE BRIDGE LEG SHALL BE BONDED TO THE GROUND RING WITH #2 AWG BARE TINNED COPPER CONDUCTOR. PROVIDE EXOTHERMIC WELDS AT BOTH THE ICE BRIDGE LEG AND BURIED GROUND RING.
- (O) **DURING ALL DC POWER SYSTEM CHANGES INCLUDING DC SYSTEM CHANGE OUTS, RECTIFIER REPLACEMENTS OR ADDITIONS, BREAKER DISTRIBUTION CHANGES, BATTERY ADDITIONS, BATTERY REPLACEMENTS AND INSTALLATIONS OR CHANGES TO DC CONVERTER SYSTEMS IT SHALL BE REQUIRED THAT SERVICE CONTRACTORS VERIFY ALL DC POWER SYSTEMS ARE EQUIPPED WITH A MASTER DC SYSTEM RETURN GROUND CONDUCTOR FROM THE DC POWER SYSTEM COMMON RETURN BUS DIRECTLY CONNECTED TO THE CELL SITE REFERENCE GROUND BAR**
- (P) **TOWER TOP COLLECTOR BUSS BAR IS TO BE MECHANICALLY BONDED TO PROPOSED ANTENNA MOUNT COLLAR. REFER TO DISH Wireless L.L.C. GROUNDING NOTES.**

GROUNDING KEY NOTES

NO SCALE 3




5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



2000 CORPORATE DRIVE
CANONSBURG, PA 15317



FROM ZERO TO INFINIGY
the solutions are endless
2500 W. HIGGINS RD., SUITE 500 |
HOFFMAN ESTATES, IL 60169
PHONE: 847-648-4068 | FAX: 518-690-0793
WWW.INFINIGY.COM



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY: CHECKED BY: APPROVED BY:
RCD SS CJW

RFDS REV #: ---

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	07/01/2021	ISSUED FOR REVIEW
0	08/31/2021	ISSUED FOR CONSTRUCTION


A&E PROJECT NUMBER
6039-Z0001-C

DISH Wireless L.L.C.
PROJECT INFORMATION
BOHVN00011A
117 WASHINGTON AVENUE
NORTH HAVEN, CT 06473

SHEET TITLE
GROUNDING PLANS
AND NOTES

SHEET NUMBER

G-1




NOTES
EQUIPMENT CABINET OMITTED FOR CLARITY

#2 TINNED SOLID IN 1/2" MIN. LIQUID TIGHT CONDUIT FROM 24" BELOW GRADE TO WITHIN 3" TO 6" OF CAD-WELD TERMINATION POINT. EXPOSED END OF THE LIQUID TIGHT CONDUIT MUST BE SEALED WITH SILICONE CAULK. (TYP)

H-FRAME GROUNDING DETAIL


NO SCALE 1



NOTES
CABLE GROUNDING NOT REQUIRED WHEN ANTENNA IS LESS THAN 10' FROM CABINET


TYPICAL GPS UNIT GROUNDING

NO SCALE 2



OUTDOOR CABINET GROUNDING


NO SCALE 3



#2 TINNED SOLID IN 1/2" MIN. LIQUID TIGHT CONDUIT FROM 24" BELOW GRADE TO WITHIN 3" TO 6" OF CAD-WELD TERMINATION POINT. EXPOSED END OF THE LIQUID TIGHT CONDUIT MUST BE SEALED WITH SILICONE CAULK.


TRANSITIONING GROUND DETAIL

NO SCALE 4



TYPICAL TEST GROUND ROD WITH INSPECTION SLEEVE

NO SCALE 5



TYPICAL GROUND RING TRENCH

NO SCALE 6




5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



2000 CORPORATE DRIVE
CANONSBURG, PA 15317



FROM ZERO TO INFINIGY
the solutions are endless
2500 W. HIGGINS RD., SUITE 500 |
HOFFMAN ESTATES, IL 60169
PHONE: 847-648-4068 | FAX: 518-690-0793
WWW.INFINIGY.COM



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY: CHECKED BY: APPROVED BY:
RCD SS CJW

RFDS REV #: ---

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	07/01/2021	ISSUED FOR REVIEW
0	08/31/2021	ISSUED FOR CONSTRUCTION



A&E PROJECT NUMBER
6039-Z0001-C

DISH Wireless L.L.C.
PROJECT INFORMATION
BOHVN00011A
117 WASHINGTON AVENUE
NORTH HAVEN, CT 06473

SHEET TITLE
GROUNDING DETAILS

SHEET NUMBER
G-2

1. EXOTHERMIC WELD (2) TWO, #2 AWG BARE TINNED SOLID COPPER CONDUCTORS TO GROUND BAR. ROUTE CONDUCTORS TO BURIED GROUND RING AND PROVIDE PARALLEL EXOTHERMIC WELD.
2. ALL EXTERIOR GROUNDING HARDWARE SHALL BE STAINLESS STEEL 3/8" DIAMETER OR LARGER. ALL HARDWARE 18-8 STAINLESS STEEL INCLUDING LOCK WASHERS, COAT ALL SURFACES WITH AN ANTI-OXIDANT COMPOUND BEFORE MATING.
3. FOR GROUND BOND TO STEEL ONLY: COAT ALL SURFACES WITH AN ANTI-OXIDANT COMPOUND BEFORE MATING.
4. DO NOT INSTALL CABLE GROUNDING KIT AT A BEND AND ALWAYS DIRECT GROUND CONDUCTOR DOWN TO GROUNDING BUS.
5. NUT & WASHER SHALL BE PLACED ON THE FRONT SIDE OF THE GROUND BAR AND BOLTED ON THE BACK SIDE.
6. ALL GROUNDING PARTS AND EQUIPMENT TO BE SUPPLIED AND INSTALLED BY CONTRACTOR.
7. THE CONTRACTOR SHALL BE RESPONSIBLE FOR INSTALLING ADDITIONAL GROUND BAR AS REQUIRED.
8. ENSURE THE WIRE INSULATION TERMINATION IS WITHIN 1/8" OF THE BARREL (NO SHINERS).



TYPICAL GROUNDING NOTES


NO SCALE 1

TYPICAL EXTERIOR TWO HOLE LUG

NO SCALE 2

TYPICAL INTERIOR TWO HOLE LUG

NO SCALE 3



LUG DETAIL

NO SCALE 4

NOT USED

NO SCALE 5

NOT USED

NO SCALE 6

NOT USED

NO SCALE 7

NOT USED

NO SCALE 8

NOT USED

NO SCALE 9



5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120




2000 CORPORATE DRIVE
CANONSBURG, PA 15317



FROM ZERO TO INFINIGY

the solutions are endless
2500 W. HIGGINS RD., SUITE 500 |
HOFFMAN ESTATES, IL 60169
PHONE: 847-648-4068 | FAX: 518-690-0793
WWW.INFINIGY.COM



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY: RCD
CHECKED BY: SS
APPROVED BY: CJW

RFDS REV #: ---

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	07/01/2021	ISSUED FOR REVIEW
0	08/31/2021	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
6039-Z0001-C

DISH Wireless L.L.C.
PROJECT INFORMATION
BOHVN00011A
117 WASHINGTON AVENUE
NORTH HAVEN, CT 06473

SHEET TITLE
GROUNDING DETAILS

SHEET NUMBER
G-3

RF JUMPER COLOR CODING

3/4" TAPE WIDTHS WITH 3/4" SPACING

LOW-BAND RRH -
(600MHz N71 BASEBAND) +
(850MHz N26 BAND) +
(700MHz N29 BAND) - OPTIONAL PER MARKET

ADD FREQUENCY COLOR TO SECTOR BAND
(CBRS WILL USE YELLOW BANDS)

ALPHA RRH				BETA RRH				GAMMA RRH			
PORT 1 + SLANT	PORT 2 - SLANT	PORT 3 + SLANT	PORT 4 - SLANT	PORT 1 + SLANT	PORT 2 - SLANT	PORT 3 + SLANT	PORT 4 - SLANT	PORT 1 + SLANT	PORT 2 - SLANT	PORT 3 + SLANT	PORT 4 - SLANT
RED	RED	RED	RED	BLUE	BLUE	BLUE	BLUE	GREEN	GREEN	GREEN	GREEN
ORANGE	ORANGE	RED	RED	ORANGE	ORANGE	BLUE	BLUE	ORANGE	ORANGE	GREEN	GREEN
	WHITE (-) PORT	ORANGE	ORANGE		WHITE (-) PORT	ORANGE	ORANGE		WHITE (-) PORT	ORANGE	ORANGE
			WHITE (-) PORT				WHITE (-) PORT				WHITE (-) PORT

MID-BAND RRH -
(AWS BANDS N66+N70)

ADD FREQUENCY COLOR TO SECTOR BAND
(CBRS WILL USE YELLOW BANDS)

RED	RED	RED	RED	BLUE	BLUE	BLUE	BLUE	GREEN	GREEN	GREEN	GREEN
PURPLE	PURPLE	RED	RED	PURPLE	PURPLE	BLUE	BLUE	PURPLE	PURPLE	GREEN	GREEN
	WHITE (-) PORT	PURPLE	PURPLE		WHITE (-) PORT	PURPLE	PURPLE		WHITE (-) PORT	PURPLE	PURPLE
			WHITE (-) PORT				WHITE (-) PORT				WHITE (-) PORT

HYBRID/DISCREET CABLES

INCLUDE SECTOR BANDS BEING SUPPORTED
ALONG WITH FREQUENCY BANDS

EXAMPLE 1 - HYBRID, OR DISCREET, SUPPORTS
ALL SECTORS, BOTH LOW-BANDS AND MID-BANDS

EXAMPLE 2 - HYBRID, OR DISCREET, SUPPORTS
CBRS ONLY, ALL SECTORS

EXAMPLE 1	EXAMPLE 2	EXAMPLE 3
RED	RED	RED
BLUE	BLUE	
GREEN	GREEN	ORANGE
ORANGE	YELLOW	PURPLE
PURPLE		

FIBER JUMPERS TO RRHs

LOW-BAND RRH FIBER CABLES HAVE SECTOR
STRIPE ONLY

LOW BAND RRH	HIGH BAND RRH	LOW BAND RRH	HIGH BAND RRH	LOW BAND RRH	HIGH BAND RRH
RED	RED	BLUE	BLUE	GREEN	GREEN
	PURPLE		PURPLE		PURPLE

POWER CABLES TO RRHs

LOW-BAND RRH POWER CABLES HAVE SECTOR
STRIPE ONLY

LOW BAND RRH	HIGH BAND RRH	LOW BAND RRH	HIGH BAND RRH	LOW BAND RRH	HIGH BAND RRH
RED	RED	BLUE	BLUE	GREEN	GREEN
	PURPLE		PURPLE		PURPLE

RET MOTORS AT ANTENNAS

ANTENNA 1 LOW BAND/ "IN"	ANTENNA 1 HIGH BAND/ "IN"	ANTENNA 1 LOW BAND/ "IN"	ANTENNA 1 HIGH BAND/ "IN"	ANTENNA 1 LOW BAND/ "IN"	ANTENNA 1 HIGH BAND/ "IN"
RED	RED	BLUE	BLUE	GREEN	GREEN
	PURPLE		PURPLE		PURPLE

MICROWAVE RADIO LINKS

LINKS WILL HAVE A 1.5-2 INCH WHITE WRAP WITH
THE AZIMUTH COLOR OVERLAPPING IN THE MIDDLE.
ADD ADDITIONAL SECTOR COLOR BANDS FOR EACH
ADDITIONAL MW RADIO.

MICROWAVE CABLES WILL REQUIRE P-TOUCH
LABELS INSIDE THE CABINET TO IDENTIFY THE
LOCAL AND REMOTE SITE ID'S

FORWARD AZIMUTH OF 0-120 DEGREES		FORWARD AZIMUTH OF 120-240 DEGREES		FORWARD AZIMUTH OF 240-360 DEGREES	
PRIMARY	SECONDARY	PRIMARY	SECONDARY	PRIMARY	SECONDARY
WHITE	WHITE	WHITE	WHITE	WHITE	WHITE
RED	RED	BLUE	BLUE	GREEN	GREEN
WHITE	WHITE	WHITE	WHITE	WHITE	WHITE
	RED		BLUE		GREEN
	WHITE		WHITE		WHITE

RF CABLE COLOR CODES

NO SCALE

1

LOW BANDS (N71+N26)
OPTIONAL - (N29)

ORANGE

AWS
(N66+N70+H-BLOCK)

PURPLE

CBRS TECH
(3 GHz)

YELLOW

NEGATIVE SLANT PORT
ON ANT/RRH

WHITE

ALPHA SECTOR

RED

BETA SECTOR

BLUE

GAMMA SECTOR

GREEN

COLOR IDENTIFIER

NO SCALE

2

NOT USED

NO SCALE

3

NOT USED

NO SCALE

4

dish
wireless.

5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120


CROWN
CASTLE

2000 CORPORATE DRIVE
CANONSBURG, PA 15317

INFINIGY

FROM ZERO TO INFINIGY

the solutions are endless
2500 W. HIGGINS RD., SUITE 500 |
HOFFMAN ESTATES, IL 60169
PHONE: 847-648-4068 | FAX: 518-690-0793
WWW.INFINIGY.COM



IT IS A VIOLATION OF LAW FOR ANY PERSON,
UNLESS THEY ARE ACTING UNDER THE DIRECTION
OF A LICENSED PROFESSIONAL ENGINEER,
TO ALTER THIS DOCUMENT.

DRAWN BY: CHECKED BY: APPROVED BY:
RCD SS CJW

RFDS REV #: ---

CONSTRUCTION
DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	07/01/2021	ISSUED FOR REVIEW
0	08/31/2021	ISSUED FOR CONSTRUCTION


A&E PROJECT NUMBER
6039-Z0001-C

DISH Wireless L.L.C.
PROJECT INFORMATION
BOHVN00011A
117 WASHINGTON AVENUE
NORTH HAVEN, CT 06473


SHEET TITLE
RF
CABLE COLOR CODES

SHEET NUMBER
RF-1

EXOTHERMIC CONNECTION
 MECHANICAL CONNECTION
 BUSS BAR INSULATOR
 CHEMICAL ELECTROLYTIC GROUNDING SYSTEM
 TEST CHEMICAL ELECTROLYTIC GROUNDING SYSTEM
 EXOTHERMIC WITH INSPECTION SLEEVE
 GROUNDING BAR
 GROUND ROD
 TEST GROUND ROD WITH INSPECTION SLEEVE
 SINGLE POLE SWITCH
 DUPLEX RECEPTACLE
 DUPLEX GFCI RECEPTACLE
 FLUORESCENT LIGHTING FIXTURE (2) TWO LAMPS 48-T8
 SMOKE DETECTION (DC)
 EMERGENCY LIGHTING (DC)
 SECURITY LIGHT W/PHOTOCELL LITHONIA ALXW
 LED-1-25A400/51K-SR4-120-PE-DOBTD
 CHAIN LINK FENCE
 WOOD/WROUGHT IRON FENCE
 WALL STRUCTURE
 LEASE AREA
 PROPERTY LINE (PL)
 SETBACKS
 ICE BRIDGE
 CABLE TRAY
 WATER LINE
 UNDERGROUND POWER
 UNDERGROUND TELCO
 OVERHEAD POWER
 OVERHEAD TELCO
 UNDERGROUND TELCO/POWER
 ABOVE GROUND POWER
 ABOVE GROUND TELCO
 ABOVE GROUND TELCO/POWER
 WORKPOINT



SECTION REFERENCE
 DETAIL REFERENCE



LEGEND

AB ANCHOR BOLT	IN INCH
ABV ABOVE	INT INTERIOR
AC ALTERNATING CURRENT	LB(S) POUND(S)
ADDL ADDITIONAL	LF LINEAR FEET
AFF ABOVE FINISHED FLOOR	LTE LONG TERM EVOLUTION
AFG ABOVE FINISHED GRADE	MAS MASONRY
AGL ABOVE GROUND LEVEL	MAX MAXIMUM
AIC AMPERAGE INTERRUPTION CAPACITY	MB MACHINE BOLT
ALUM ALUMINUM	MECH MECHANICAL
ALT ALTERNATE	MFR MANUFACTURER
ANT ANTENNA	MGB MASTER GROUND BAR
APPROX APPROXIMATE	MIN MINIMUM
ARCH ARCHITECTURAL	MISC MISCELLANEOUS
ATS AUTOMATIC TRANSFER SWITCH	MTL METAL
AWG AMERICAN WIRE GAUGE	MTS MANUAL TRANSFER SWITCH
BATT BATTERY	MW MICROWAVE
BLDG BUILDING	NEC NATIONAL ELECTRIC CODE
BLK BLOCK	NM NEWTON METERS
BLKG BLOCKING	NO. NUMBER
BM BEAM	# NUMBER
BTC BARE TINNED COPPER CONDUCTOR	NTS NOT TO SCALE
BOF BOTTOM OF FOOTING	OC ON-CENTER
CAB CABINET	OSHA OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION
CANT CANTILEVERED	OPNG OPENING
CHG CHARGING	P/C PRECAST CONCRETE
CLG CEILING	PCS PERSONAL COMMUNICATION SERVICES
CLR CLEAR	PCU PRIMARY CONTROL UNIT
COL COLUMN	PRC PRIMARY RADIO CABINET
COMM COMMON	PP POLARIZING PRESERVING
CONC CONCRETE	PSF POUNDS PER SQUARE FOOT
CONSTR CONSTRUCTION	PSI POUNDS PER SQUARE INCH
DBL DOUBLE	PT PRESSURE TREATED
DC DIRECT CURRENT	PWR POWER CABINET
DEPT DEPARTMENT	QTY QUANTITY
DF DOUGLAS FIR	RAD RADIUS
DIA DIAMETER	RECT RECTIFIER
DIAG DIAGONAL	REF REFERENCE
DIM DIMENSION	REINF REINFORCEMENT
DWG DRAWING	REQ'D REQUIRED
DWL DOWEL	RET REMOTE ELECTRIC TILT
EA EACH	RF RADIO FREQUENCY
EC ELECTRICAL CONDUCTOR	RMC RIGID METALLIC CONDUIT
EL ELEVATION	RRH REMOTE RADIO HEAD
ELEC ELECTRICAL	RRU REMOTE RADIO UNIT
EMT ELECTRICAL METALLIC TUBING	RWY RACEWAY
ENG ENGINEER	SCH SCHEDULE
EQ EQUAL	SHT SHEET
EXP EXPANSION	SIAD SMART INTEGRATED ACCESS DEVICE
EXT EXTERIOR	SIM SIMILAR
EW EACH WAY	SPEC SPECIFICATION
FAB FABRICATION	SQ SQUARE
FF FINISH FLOOR	SS STAINLESS STEEL
FG FINISH GRADE	STD STANDARD
FIF FACILITY INTERFACE FRAME	STL STEEL
FIN FINISH(ED)	TEMP TEMPORARY
FLR FLOOR	THK THICKNESS
FDN FOUNDATION	TMA TOWER MOUNTED AMPLIFIER
FOC FACE OF CONCRETE	TN TOE NAIL
FOM FACE OF MASONRY	TOA TOP OF ANTENNA
FOS FACE OF STUD	TOC TOP OF CURB
FOW FACE OF WALL	TOF TOP OF FOUNDATION
FS FINISH SURFACE	TOP TOP OF PLATE (PARAPET)
FT FOOT	TOS TOP OF STEEL
FTG FOOTING	TOW TOP OF WALL
GA GAUGE	TVSS TRANSIENT VOLTAGE SURGE SUPPRESSION
GEN GENERATOR	TYP TYPICAL
GFCI GROUND FAULT CIRCUIT INTERRUPTER	UG UNDERGROUND
GLB GLUE LAMINATED BEAM	UL UNDERWRITERS LABORATORY
GLV GALVANIZED	UNO UNLESS NOTED OTHERWISE
GPS GLOBAL POSITIONING SYSTEM	UMTS UNIVERSAL MOBILE TELECOMMUNICATIONS SYSTEM
GND GROUND	UPS UNINTERRUPTIBLE POWER SYSTEM (DC POWER PLANT)
GSM GLOBAL SYSTEM FOR MOBILE	VIF VERIFIED IN FIELD
HDG HOT DIPPED GALVANIZED	W WIDE
HDR HEADER	W/ WITH
HGR HANGER	WD WOOD
HVAC HEAT/VENTILATION/AIR CONDITIONING	WP WEATHERPROOF
HT HEIGHT	WT WEIGHT
IGR INTERIOR GROUND RING	

ABBREVIATIONS




5701 SOUTH SANTA FE DRIVE
 LITTLETON, CO 80120



2000 CORPORATE DRIVE
 CANONSBURG, PA 15317



FROM ZERO TO INFINIGY
 the solutions are endless
 2500 W. HIGGINS RD., SUITE 500 |
 HOFFMAN ESTATES, IL 60169
 PHONE: 847-648-4068 | FAX: 518-690-0793
 WWW.INFINIGY.COM



IT IS A VIOLATION OF LAW FOR ANY PERSON,
 UNLESS THEY ARE ACTING UNDER THE DIRECTION
 OF A LICENSED PROFESSIONAL ENGINEER,
 TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
RCD	SS	CJW

RFDS REV #: ---

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	07/01/2021	ISSUED FOR REVIEW
0	08/31/2021	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
 6039-Z0001-C

DISH Wireless L.L.C.
 PROJECT INFORMATION
 BOHVN00011A
 117 WASHINGTON AVENUE
 NORTH HAVEN, CT 06473

SHEET TITLE
 LEGEND AND ABBREVIATIONS

SHEET NUMBER
GN-1

SITE ACTIVITY REQUIREMENTS:

1. NOTICE TO PROCEED – NO WORK SHALL COMMENCE PRIOR TO CONTRACTOR RECEIVING A WRITTEN NOTICE TO PROCEED (NTP) AND THE ISSUANCE OF A PURCHASE ORDER. PRIOR TO ACCESSING/ENTERING THE SITE YOU MUST CONTACT THE DISH Wireless L.L.C. AND TOWER OWNER NOC & THE DISH Wireless L.L.C. AND TOWER OWNER CONSTRUCTION MANAGER.
2. "LOOK UP" – DISH Wireless L.L.C. AND TOWER OWNER SAFETY CLIMB REQUIREMENT:
THE INTEGRITY OF THE SAFETY CLIMB AND ALL COMPONENTS OF THE CLIMBING FACILITY SHALL BE CONSIDERED DURING ALL STAGES OF DESIGN, INSTALLATION, AND INSPECTION. TOWER MODIFICATION, MOUNT REINFORCEMENTS, AND/OR EQUIPMENT INSTALLATIONS SHALL NOT COMPROMISE THE INTEGRITY OR FUNCTIONAL USE OF THE SAFETY CLIMB OR ANY COMPONENTS OF THE CLIMBING FACILITY ON THE STRUCTURE. THIS SHALL INCLUDE, BUT NOT BE LIMITED TO: PINCHING OF THE WIRE ROPE, BENDING OF THE WIRE ROPE FROM ITS SUPPORTS, DIRECT CONTACT OR CLOSE PROXIMITY TO THE WIRE ROPE WHICH MAY CAUSE FRICTIONAL WEAR, IMPACT TO THE ANCHORAGE POINTS IN ANY WAY, OR TO IMPEDE/BLOCK ITS INTENDED USE. ANY COMPROMISED SAFETY CLIMB, INCLUDING EXISTING CONDITIONS MUST BE TAGGED OUT AND REPORTED TO YOUR DISH Wireless L.L.C. AND DISH Wireless L.L.C. AND TOWER OWNER POC OR CALL THE NOC TO GENERATE A SAFETY CLIMB MAINTENANCE AND CONTRACTOR NOTICE TICKET.
3. PRIOR TO THE START OF CONSTRUCTION, ALL REQUIRED JURISDICTIONAL PERMITS SHALL BE OBTAINED. THIS INCLUDES, BUT IS NOT LIMITED TO, BUILDING, ELECTRICAL, MECHANICAL, FIRE, FLOOD ZONE, ENVIRONMENTAL, AND ZONING. AFTER ONSITE ACTIVITIES AND CONSTRUCTION ARE COMPLETED, ALL REQUIRED PERMITS SHALL BE SATISFIED AND CLOSED OUT ACCORDING TO LOCAL JURISDICTIONAL REQUIREMENTS.
4. ALL CONSTRUCTION MEANS AND METHODS; INCLUDING BUT NOT LIMITED TO, ERECTION PLANS, RIGGING PLANS, CLIMBING PLANS, AND RESCUE PLANS SHALL BE THE RESPONSIBILITY OF THE GENERAL CONTRACTOR RESPONSIBLE FOR THE EXECUTION OF THE WORK CONTAINED HEREIN, AND SHALL MEET ANSI/ASSE A10.48 (LATEST EDITION); FEDERAL, STATE, AND LOCAL REGULATIONS; AND ANY APPLICABLE INDUSTRY CONSENSUS STANDARDS RELATED TO THE CONSTRUCTION ACTIVITIES BEING PERFORMED. ALL RIGGING PLANS SHALL ADHERE TO ANSI/ASSE A10.48 (LATEST EDITION) AND DISH Wireless L.L.C. AND TOWER OWNER STANDARDS, INCLUDING THE REQUIRED INVOLVEMENT OF A QUALIFIED ENGINEER FOR CLASS IV CONSTRUCTION, TO CERTIFY THE SUPPORTING STRUCTURE(S) IN ACCORDANCE WITH ANSI/TIA-322 (LATEST EDITION).
5. ALL SITE WORK TO COMPLY WITH DISH Wireless L.L.C. AND TOWER OWNER INSTALLATION STANDARDS FOR CONSTRUCTION ACTIVITIES ON DISH Wireless L.L.C. AND TOWER OWNER TOWER SITE AND LATEST VERSION OF ANSI/TIA-1019-A-2012 "STANDARD FOR INSTALLATION, ALTERATION, AND MAINTENANCE OF ANTENNA SUPPORTING STRUCTURES AND ANTENNAS."
6. IF THE SPECIFIED EQUIPMENT CAN NOT BE INSTALLED AS SHOWN ON THESE DRAWINGS, THE CONTRACTOR SHALL PROPOSE AN ALTERNATIVE INSTALLATION FOR APPROVAL BY DISH Wireless L.L.C. AND TOWER OWNER PRIOR TO PROCEEDING WITH ANY SUCH CHANGE OF INSTALLATION.
7. ALL MATERIALS FURNISHED AND INSTALLED SHALL BE IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS AND ORDINANCES. CONTRACTOR SHALL ISSUE ALL APPROPRIATE NOTICES AND COMPLY WITH ALL LAWS, ORDINANCES, RULES, REGULATIONS AND LAWFUL ORDERS OF ANY PUBLIC AUTHORITY REGARDING THE PERFORMANCE OF THE WORK. ALL WORK CARRIED OUT SHALL COMPLY WITH ALL APPLICABLE MUNICIPAL AND UTILITY COMPANY SPECIFICATIONS AND LOCAL JURISDICTIONAL CODES, ORDINANCES AND APPLICABLE REGULATIONS.
8. THE CONTRACTOR SHALL INSTALL ALL EQUIPMENT AND MATERIALS IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS UNLESS SPECIFICALLY STATED OTHERWISE.
9. THE CONTRACTOR SHALL CONTACT UTILITY LOCATING SERVICES INCLUDING PRIVATE LOCATES SERVICES PRIOR TO THE START OF CONSTRUCTION.
10. ALL EXISTING ACTIVE SEWER, WATER, GAS, ELECTRIC AND OTHER UTILITIES WHERE ENCOUNTERED IN THE WORK, SHALL BE PROTECTED AT ALL TIMES AND WHERE REQUIRED FOR THE PROPER EXECUTION OF THE WORK, SHALL BE RELOCATED AS DIRECTED BY CONTRACTOR. EXTREME CAUTION SHOULD BE USED BY THE CONTRACTOR WHEN EXCAVATING OR DRILLING PIERS AROUND OR NEAR UTILITIES. CONTRACTOR SHALL PROVIDE SAFETY TRAINING FOR THE WORKING CREW. THIS WILL INCLUDE BUT NOT BE LIMITED TO A) FALL PROTECTION B) CONFINED SPACE C) ELECTRICAL SAFETY D) TRENCHING AND EXCAVATION E) CONSTRUCTION SAFETY PROCEDURES.
11. ALL SITE WORK SHALL BE AS INDICATED ON THE STAMPED CONSTRUCTION DRAWINGS AND DISH PROJECT SPECIFICATIONS, LATEST APPROVED REVISION.
12. CONTRACTOR SHALL KEEP THE SITE FREE FROM ACCUMULATING WASTE MATERIAL, DEBRIS, AND TRASH AT THE COMPLETION OF THE WORK. IF NECESSARY, RUBBISH, STUMPS, DEBRIS, STICKS, STONES AND OTHER REFUSE SHALL BE REMOVED FROM THE SITE AND DISPOSED OF LEGALLY.
13. ALL EXISTING INACTIVE SEWER, WATER, GAS, ELECTRIC AND OTHER UTILITIES, WHICH INTERFERE WITH THE EXECUTION OF THE WORK, SHALL BE REMOVED AND/OR CAPPED, PLUGGED OR OTHERWISE DISCONTINUED AT POINTS WHICH WILL NOT INTERFERE WITH THE EXECUTION OF THE WORK, SUBJECT TO THE APPROVAL OF DISH Wireless L.L.C. AND TOWER OWNER, AND/OR LOCAL UTILITIES.
14. THE CONTRACTOR SHALL PROVIDE SITE SIGNAGE IN ACCORDANCE WITH THE TECHNICAL SPECIFICATION FOR SITE SIGNAGE REQUIRED BY LOCAL JURISDICTION AND SIGNAGE REQUIRED ON INDIVIDUAL PIECES OF EQUIPMENT, ROOMS, AND SHELTERS.
15. THE SITE SHALL BE GRADED TO CAUSE SURFACE WATER TO FLOW AWAY FROM THE CARRIER'S EQUIPMENT AND TOWER AREAS.
16. THE SUB GRADE SHALL BE COMPACTED AND BROUGHT TO A SMOOTH UNIFORM GRADE PRIOR TO FINISHED SURFACE APPLICATION.
17. THE AREAS OF THE OWNERS PROPERTY DISTURBED BY THE WORK AND NOT COVERED BY THE TOWER, EQUIPMENT OR DRIVEWAY, SHALL BE GRADED TO A UNIFORM SLOPE, AND STABILIZED TO PREVENT EROSION AS SPECIFIED ON THE CONSTRUCTION DRAWINGS AND/OR PROJECT SPECIFICATIONS.
18. CONTRACTOR SHALL MINIMIZE DISTURBANCE TO EXISTING SITE DURING CONSTRUCTION. EROSION CONTROL MEASURES, IF REQUIRED DURING CONSTRUCTION, SHALL BE IN CONFORMANCE WITH THE LOCAL GUIDELINES FOR EROSION AND SEDIMENT CONTROL.
19. THE CONTRACTOR SHALL PROTECT EXISTING IMPROVEMENTS, PAVEMENTS, CURBS, LANDSCAPING AND STRUCTURES. ANY DAMAGED PART SHALL BE REPAIRED AT CONTRACTOR'S EXPENSE TO THE SATISFACTION OF OWNER.
20. CONTRACTOR SHALL LEGALLY AND PROPERLY DISPOSE OF ALL SCRAP MATERIALS SUCH AS COAXIAL CABLES AND OTHER ITEMS REMOVED FROM THE EXISTING FACILITY. ANTENNAS AND RADIOS REMOVED SHALL BE RETURNED TO THE OWNER'S DESIGNATED LOCATION.
21. CONTRACTOR SHALL LEAVE PREMISES IN CLEAN CONDITION. TRASH AND DEBRIS SHOULD BE REMOVED FROM SITE ON A DAILY BASIS.
22. NO FILL OR EMBANKMENT MATERIAL SHALL BE PLACED ON FROZEN GROUND. FROZEN MATERIALS, SNOW OR ICE SHALL NOT BE PLACED IN ANY FILL OR EMBANKMENT.

GENERAL NOTES:

1. FOR THE PURPOSE OF CONSTRUCTION DRAWING, THE FOLLOWING DEFINITIONS SHALL APPLY:
CONTRACTOR: GENERAL CONTRACTOR RESPONSIBLE FOR CONSTRUCTION
CARRIER: DISH Wireless L.L.C.
TOWER OWNER: TOWER OWNER
2. THESE DRAWINGS HAVE BEEN PREPARED USING STANDARDS OF PROFESSIONAL CARE AND COMPLETENESS NORMALLY EXERCISED UNDER SIMILAR CIRCUMSTANCES BY REPUTABLE ENGINEERS IN THIS OR SIMILAR LOCALITIES. IT IS ASSUMED THAT THE WORK DEPICTED WILL BE PERFORMED BY AN EXPERIENCED CONTRACTOR AND/OR WORKPEOPLE WHO HAVE A WORKING KNOWLEDGE OF THE APPLICABLE CODE STANDARDS AND REQUIREMENTS AND OF INDUSTRY ACCEPTED STANDARD GOOD PRACTICE. AS NOT EVERY CONDITION OR ELEMENT IS (OR CAN BE) EXPLICITLY SHOWN ON THESE DRAWINGS, THE CONTRACTOR SHALL USE INDUSTRY ACCEPTED STANDARD GOOD PRACTICE FOR MISCELLANEOUS WORK NOT EXPLICITLY SHOWN.
3. THESE DRAWINGS REPRESENT THE FINISHED STRUCTURE. THEY DO NOT INDICATE THE MEANS OR METHODS OF CONSTRUCTION. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR THE CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES. THE CONTRACTOR SHALL PROVIDE ALL MEASURES NECESSARY FOR PROTECTION OF LIFE AND PROPERTY DURING CONSTRUCTION. SUCH MEASURES SHALL INCLUDE, BUT NOT BE LIMITED TO, BRACING, FORMWORK, SHORING, ETC. SITE VISITS BY THE ENGINEER OR HIS REPRESENTATIVE WILL NOT INCLUDE INSPECTION OF THESE ITEMS AND IS FOR STRUCTURAL OBSERVATION OF THE FINISHED STRUCTURE ONLY.
4. NOTES AND DETAILS IN THE CONSTRUCTION DRAWINGS SHALL TAKE PRECEDENCE OVER GENERAL NOTES AND TYPICAL DETAILS. WHERE NO DETAILS ARE SHOWN, CONSTRUCTION SHALL CONFORM TO SIMILAR WORK ON THE PROJECT, AND/OR AS PROVIDED FOR IN THE CONTRACT DOCUMENTS. WHERE DISCREPANCIES OCCUR BETWEEN PLANS, DETAILS, GENERAL NOTES, AND SPECIFICATIONS, THE GREATER, MORE STRICT REQUIREMENTS, SHALL GOVERN. IF FURTHER CLARIFICATION IS REQUIRED CONTACT THE ENGINEER OF RECORD.
5. SUBSTANTIAL EFFORT HAS BEEN MADE TO PROVIDE ACCURATE DIMENSIONS AND MEASUREMENTS ON THE DRAWINGS TO ASSIST IN THE FABRICATION AND/OR PLACEMENT OF CONSTRUCTION ELEMENTS BUT IT IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR TO FIELD VERIFY THE DIMENSIONS, MEASUREMENTS, AND/OR CLEARANCES SHOWN IN THE CONSTRUCTION DRAWINGS PRIOR TO FABRICATION OR CUTTING OF ANY NEW OR EXISTING CONSTRUCTION ELEMENTS. IF IT IS DETERMINED THAT THERE ARE DISCREPANCIES AND/OR CONFLICTS WITH THE CONSTRUCTION DRAWINGS THE ENGINEER OF RECORD IS TO BE NOTIFIED AS SOON AS POSSIBLE.
6. PRIOR TO THE SUBMISSION OF BIDS, THE BIDDING CONTRACTOR SHALL VISIT THE CELL SITE TO FAMILIARIZE WITH THE EXISTING CONDITIONS AND TO CONFIRM THAT THE WORK CAN BE ACCOMPLISHED AS SHOWN ON THE CONSTRUCTION DRAWINGS. ANY DISCREPANCY FOUND SHALL BE BROUGHT TO THE ATTENTION OF CARRIER POC AND TOWER OWNER.
7. ALL MATERIALS FURNISHED AND INSTALLED SHALL BE IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS AND ORDINANCES. CONTRACTOR SHALL ISSUE ALL APPROPRIATE NOTICES AND COMPLY WITH ALL LAWS, ORDINANCES, RULES, REGULATIONS AND LAWFUL ORDERS OF ANY PUBLIC AUTHORITY REGARDING THE PERFORMANCE OF THE WORK. ALL WORK CARRIED OUT SHALL COMPLY WITH ALL APPLICABLE MUNICIPAL AND UTILITY COMPANY SPECIFICATIONS AND LOCAL JURISDICTIONAL CODES, ORDINANCES AND APPLICABLE REGULATIONS.
8. UNLESS NOTED OTHERWISE, THE WORK SHALL INCLUDE FURNISHING MATERIALS, EQUIPMENT, APPURTENANCES AND LABOR NECESSARY TO COMPLETE ALL INSTALLATIONS AS INDICATED ON THE DRAWINGS.
9. THE CONTRACTOR SHALL INSTALL ALL EQUIPMENT AND MATERIALS IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS UNLESS SPECIFICALLY STATED OTHERWISE.
10. IF THE SPECIFIED EQUIPMENT CAN NOT BE INSTALLED AS SHOWN ON THESE DRAWINGS, THE CONTRACTOR SHALL PROPOSE AN ALTERNATIVE INSTALLATION FOR APPROVAL BY THE CARRIER AND TOWER OWNER PRIOR TO PROCEEDING WITH ANY SUCH CHANGE OF INSTALLATION.
11. CONTRACTOR IS TO PERFORM A SITE INVESTIGATION, BEFORE SUBMITTING BIDS, TO DETERMINE THE BEST ROUTING OF ALL CONDUITS FOR POWER, AND TELCO AND FOR GROUNDING CABLES AS SHOWN IN THE POWER, TELCO, AND GROUNDING PLAN DRAWINGS.
12. THE CONTRACTOR SHALL PROTECT EXISTING IMPROVEMENTS, PAVEMENTS, CURBS, LANDSCAPING AND STRUCTURES. ANY DAMAGED PART SHALL BE REPAIRED AT CONTRACTOR'S EXPENSE TO THE SATISFACTION OF DISH Wireless L.L.C. AND TOWER OWNER
13. CONTRACTOR SHALL LEGALLY AND PROPERLY DISPOSE OF ALL SCRAP MATERIALS SUCH AS COAXIAL CABLES AND OTHER ITEMS REMOVED FROM THE EXISTING FACILITY. ANTENNAS REMOVED SHALL BE RETURNED TO THE OWNER'S DESIGNATED LOCATION.
14. CONTRACTOR SHALL LEAVE PREMISES IN CLEAN CONDITION. TRASH AND DEBRIS SHOULD BE REMOVED FROM SITE ON A DAILY BASIS.




5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



2000 CORPORATE DRIVE
CANONSBURG, PA 15317



FROM ZERO TO INFINIGY
the solutions are endless
2500 W. HIGGINS RD., SUITE 500 |
HOFFMAN ESTATES, IL 60169
PHONE: 847-648-4068 | FAX: 518-690-0793
WWW.INFINIGY.COM



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
RCD	SS	CJW

RFDS REV #: ---

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	07/01/2021	ISSUED FOR REVIEW
0	08/31/2021	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
6039-Z0001-C

DISH Wireless L.L.C.
PROJECT INFORMATION
BOHVN00011A
117 WASHINGTON AVENUE
NORTH HAVEN, CT 06473

SHEET TITLE
GENERAL NOTES

SHEET NUMBER
GN-2

CONCRETE, FOUNDATIONS, AND REINFORCING STEEL:

1. ALL CONCRETE WORK SHALL BE IN ACCORDANCE WITH THE ACI 301, ACI 318, ACI 336, ASTM A184, ASTM A185 AND THE DESIGN AND CONSTRUCTION SPECIFICATION FOR CAST-IN-PLACE CONCRETE.
2. UNLESS NOTED OTHERWISE, SOIL BEARING PRESSURE USED FOR DESIGN OF SLABS AND FOUNDATIONS IS ASSUMED TO BE 1000 psf.
3. ALL CONCRETE SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH (f'c) OF 3000 psi AT 28 DAYS, UNLESS NOTED OTHERWISE. NO MORE THAN 90 MINUTES SHALL ELAPSE FROM BATCH TIME TO TIME OF PLACEMENT UNLESS APPROVED BY THE ENGINEER OF RECORD. TEMPERATURE OF CONCRETE SHALL NOT EXCEED 90°f AT TIME OF PLACEMENT.
4. CONCRETE EXPOSED TO FREEZE-THAW CYCLES SHALL CONTAIN AIR ENTRAINING ADMIXTURES. AMOUNT OF AIR ENTRAINMENT TO BE BASED ON SIZE OF AGGREGATE AND F3 CLASS EXPOSURE (VERY SEVERE). CEMENT USED TO BE TYPE II PORTLAND CEMENT WITH A MAXIMUM WATER-TO-CEMENT RATIO (W/C) OF 0.45.
5. ALL STEEL REINFORCING SHALL CONFORM TO ASTM A615. ALL WELDED WIRE FABRIC (WWF) SHALL CONFORM TO ASTM A185. ALL SPLICES SHALL BE CLASS "B" TENSION SPLICES, UNLESS NOTED OTHERWISE. ALL HOOKS SHALL BE STANDARD 90 DEGREE HOOKS, UNLESS NOTED OTHERWISE. YIELD STRENGTH (Fy) OF STANDARD DEFORMED BARS ARE AS FOLLOWS:
 #4 BARS AND SMALLER 40 ksi
 #5 BARS AND LARGER 60 ksi
6. THE FOLLOWING MINIMUM CONCRETE COVER SHALL BE PROVIDED FOR REINFORCING STEEL UNLESS SHOWN OTHERWISE ON DRAWINGS:
 - CONCRETE CAST AGAINST AND PERMANENTLY EXPOSED TO EARTH 3"
 - CONCRETE EXPOSED TO EARTH OR WEATHER:
 - #6 BARS AND LARGER 2"
 - #5 BARS AND SMALLER 1-1/2"
 - CONCRETE NOT EXPOSED TO EARTH OR WEATHER:
 - SLAB AND WALLS 3/4"
 - BEAMS AND COLUMNS 1-1/2"
7. A TOOLED EDGE OR A 3/4" CHAMFER SHALL BE PROVIDED AT ALL EXPOSED EDGES OF CONCRETE, UNLESS NOTED OTHERWISE, IN ACCORDANCE WITH ACI 301 SECTION 4.2.4.

ELECTRICAL INSTALLATION NOTES:

1. ALL ELECTRICAL WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS, NEC AND ALL APPLICABLE FEDERAL, STATE, AND LOCAL CODES/ORDINANCES.
2. CONDUIT ROUTINGS ARE SCHEMATIC. CONTRACTOR SHALL INSTALL CONDUITS SO THAT ACCESS TO EQUIPMENT IS NOT BLOCKED AND TRIP HAZARDS ARE ELIMINATED.
3. WIRING, RACEWAY AND SUPPORT METHODS AND MATERIALS SHALL COMPLY WITH THE REQUIREMENTS OF THE NEC.
4. ALL CIRCUITS SHALL BE SEGREGATED AND MAINTAIN MINIMUM CABLE SEPARATION AS REQUIRED BY THE NEC.
- 4.1. ALL EQUIPMENT SHALL BEAR THE UNDERWRITERS LABORATORIES LABEL OF APPROVAL, AND SHALL CONFORM TO REQUIREMENT OF THE NATIONAL ELECTRICAL CODE.
- 4.2. ALL OVERCURRENT DEVICES SHALL HAVE AN INTERRUPTING CURRENT RATING THAT SHALL BE GREATER THAN THE SHORT CIRCUIT CURRENT TO WHICH THEY ARE SUBJECTED, 22,000 AIC MINIMUM. VERIFY AVAILABLE SHORT CIRCUIT CURRENT DOES NOT EXCEED THE RATING OF ELECTRICAL EQUIPMENT IN ACCORDANCE WITH ARTICLE 110.24 NEC OR THE MOST CURRENT ADOPTED CODE PRE THE GOVERNING JURISDICTION.
5. EACH END OF EVERY POWER PHASE CONDUCTOR, GROUNDING CONDUCTOR, AND TELCO CONDUCTOR OR CABLE SHALL BE LABELED WITH COLOR-CODED INSULATION OR ELECTRICAL TAPE (3M BRAND, 1/2" PLASTIC ELECTRICAL TAPE WITH UV PROTECTION, OR EQUAL). THE IDENTIFICATION METHOD SHALL CONFORM WITH NEC AND OSHA.
6. ALL ELECTRICAL COMPONENTS SHALL BE CLEARLY LABELED WITH LAMICOID TAGS SHOWING THEIR RATED VOLTAGE, PHASE CONFIGURATION, WIRE CONFIGURATION, POWER OR AMPACITY RATING AND BRANCH CIRCUIT ID NUMBERS (i.e. PANEL BOARD AND CIRCUIT ID'S).
7. PANEL BOARDS (ID NUMBERS) SHALL BE CLEARLY LABELED WITH PLASTIC LABELS.
8. TIE WRAPS ARE NOT ALLOWED.
9. ALL POWER AND EQUIPMENT GROUND WIRING IN TUBING OR CONDUIT SHALL BE SINGLE COPPER CONDUCTOR (#14 OR LARGER) WITH TYPE THHW, THWN, THWN-2, XHHW, XHHW-2, THW, THW-2, RHW, OR RHW-2 INSULATION UNLESS OTHERWISE SPECIFIED.
10. SUPPLEMENTAL EQUIPMENT GROUND WIRING LOCATED INDOORS SHALL BE SINGLE COPPER CONDUCTOR (#6 OR LARGER) WITH TYPE THHW, THWN, THWN-2, XHHW, XHHW-2, THW, THW-2, RHW, OR RHW-2 INSULATION UNLESS OTHERWISE SPECIFIED.
11. POWER AND CONTROL WIRING IN FLEXIBLE CORD SHALL BE MULTI-CONDUCTOR, TYPE SOOW CORD (#14 OR LARGER) UNLESS OTHERWISE SPECIFIED.
12. POWER AND CONTROL WIRING FOR USE IN CABLE TRAY SHALL BE MULTI-CONDUCTOR, TYPE TC CABLE (#14 OR LARGER), WITH TYPE THHW, THWN, THWN-2, XHHW, XHHW-2, THW, THW-2, RHW, OR RHW-2 INSULATION UNLESS OTHERWISE SPECIFIED.
13. ALL POWER AND GROUNDING CONNECTIONS SHALL BE CRIMP-STYLE, COMPRESSION WIRE LUGS AND WIRE NUTS BY THOMAS AND BETTS (OR EQUAL). LUGS AND WIRE NUTS SHALL BE RATED FOR OPERATION NOT LESS THAN 75° C (90° C IF AVAILABLE).
14. RACEWAY AND CABLE TRAY SHALL BE LISTED OR LABELED FOR ELECTRICAL USE IN ACCORDANCE WITH NEMA, UL, ANSI/IEEE AND NEC.
15. ELECTRICAL METALLIC TUBING (EMT), INTERMEDIATE METAL CONDUIT (IMC), OR RIGID METAL CONDUIT (RMC) SHALL BE USED FOR EXPOSED INDOOR LOCATIONS.

16. ELECTRICAL METALLIC TUBING (EMT) OR METAL-CLAD CABLE (MC) SHALL BE USED FOR CONCEALED INDOOR LOCATIONS.
17. SCHEDULE 40 PVC UNDERGROUND ON STRAIGHTS AND SCHEDULE 80 PVC FOR ALL ELBOWS/90s AND ALL APPROVED ABOVE GRADE PVC CONDUIT.
18. LIQUID-TIGHT FLEXIBLE METALLIC CONDUIT (LIQUID-TITE FLEX) SHALL BE USED INDOORS AND OUTDOORS, WHERE VIBRATION OCCURS OR FLEXIBILITY IS NEEDED.
19. CONDUIT AND TUBING FITTINGS SHALL BE THREADED OR COMPRESSION-TYPE AND APPROVED FOR THE LOCATION USED. SET SCREW FITTINGS ARE NOT ACCEPTABLE.
20. CABINETS, BOXES AND WIRE WAYS SHALL BE LABELED FOR ELECTRICAL USE IN ACCORDANCE WITH NEMA, UL, ANSI/IEEE AND THE NEC.
21. WIREWAYS SHALL BE METAL WITH AN ENAMEL FINISH AND INCLUDE A HINGED COVER, DESIGNED TO SWING OPEN DOWNWARDS (WIREMOLD SPECMATE WIREWAY).
22. SLOTTED WIRING DUCT SHALL BE PVC AND INCLUDE COVER (PANDUIT TYPE E OR EQUAL).
23. CONDUITS SHALL BE FASTENED SECURELY IN PLACE WITH APPROVED NON-PERFORATED STRAPS AND HANGERS. EXPLOSIVE DEVICES (i.e. POWDER-ACTUATED) FOR ATTACHING HANGERS TO STRUCTURE WILL NOT BE PERMITTED. CLOSELY FOLLOW THE LINES OF THE STRUCTURE, MAINTAIN CLOSE PROXIMITY TO THE STRUCTURE AND KEEP CONDUITS IN TIGHT ENVELOPES. CHANGES IN DIRECTION TO ROUTE AROUND OBSTACLES SHALL BE MADE WITH CONDUIT OUTLET BODIES. CONDUIT SHALL BE INSTALLED IN A NEAT AND WORKMANLIKE MANNER. PARALLEL AND PERPENDICULAR TO STRUCTURE WALL AND CEILING LINES. ALL CONDUIT SHALL BE FISHED TO CLEAR OBSTRUCTIONS. ENDS OF CONDUITS SHALL BE TEMPORARILY CAPPED FLUSH TO FINISH GRADE TO PREVENT CONCRETE, PLASTER OR DIRT FROM ENTERING. CONDUITS SHALL BE RIGIDLY CLAMPED TO BOXES BY GALVANIZED MALLEABLE IRON BUSHING ON INSIDE AND GALVANIZED MALLEABLE IRON LOCKNUT ON OUTSIDE AND INSIDE.
24. EQUIPMENT CABINETS, TERMINAL BOXES, JUNCTION BOXES AND PULL BOXES SHALL BE GALVANIZED OR EPOXY-COATED SHEET STEEL SHALL MEET OR EXCEED UL 50 AND BE RATED NEMA 1 (OR BETTER) FOR INTERIOR LOCATIONS AND NEMA 3 (OR BETTER) FOR EXTERIOR LOCATIONS.
25. METAL RECEPTACLE, SWITCH AND DEVICE BOXES SHALL BE GALVANIZED, EPOXY-COATED OR NON-CORRODING; SHALL MEET OR EXCEED UL 514A AND NEMA OS 1 AND BE RATED NEMA 1 (OR BETTER) FOR INTERIOR LOCATIONS AND WEATHER PROTECTED (WP OR BETTER) FOR EXTERIOR LOCATIONS.
26. NONMETALLIC RECEPTACLE, SWITCH AND DEVICE BOXES SHALL MEET OR EXCEED NEMA OS 2 (NEWEST REVISION) AND BE RATED NEMA 1 (OR BETTER) FOR INTERIOR LOCATIONS AND WEATHER PROTECTED (WP OR BETTER) FOR EXTERIOR LOCATIONS.
27. THE CONTRACTOR SHALL NOTIFY AND OBTAIN NECESSARY AUTHORIZATION FROM THE CARRIER AND/OR DISH Wireless L.L.C. AND TOWER OWNER BEFORE COMMENCING WORK ON THE AC POWER DISTRIBUTION PANELS.
28. THE CONTRACTOR SHALL PROVIDE NECESSARY TAGGING ON THE BREAKERS, CABLES AND DISTRIBUTION PANELS IN ACCORDANCE WITH THE APPLICABLE CODES AND STANDARDS TO SAFEGUARD LIFE AND PROPERTY.
29. INSTALL LAMICOID LABEL ON THE METER CENTER TO SHOW "DISH Wireless L.L.C.".
30. ALL EMPTY/SPARE CONDUITS THAT ARE INSTALLED ARE TO HAVE A METERED MULE TAPE PULL CORD INSTALLED.




5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



2000 CORPORATE DRIVE
CANONSBURG, PA 15317



FROM ZERO TO INFINIGY
the solutions are endless
2500 W. HIGGINS RD., SUITE 500 |
HOFFMAN ESTATES, IL 60169
PHONE: 847-648-4068 | FAX: 518-690-0793
WWW.INFINIGY.COM



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
RCD	SS	CJW

RFDS REV #: ---

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	07/01/2021	ISSUED FOR REVIEW
0	08/31/2021	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
6039-Z0001-C

DISH Wireless L.L.C.
PROJECT INFORMATION
BOHVN00011A
117 WASHINGTON AVENUE
NORTH HAVEN, CT 06473

SHEET TITLE
GENERAL NOTES

SHEET NUMBER
GN-3

GROUNDING NOTES:

1. ALL GROUND ELECTRODE SYSTEMS (INCLUDING TELECOMMUNICATION, RADIO, LIGHTNING PROTECTION AND AC POWER GES'S) SHALL BE BONDED TOGETHER AT OR BELOW GRADE, BY TWO OR MORE COPPER BONDING CONDUCTORS IN ACCORDANCE WITH THE NEC.
2. THE CONTRACTOR SHALL PERFORM IEEE FALL-OF-POTENTIAL RESISTANCE TO EARTH TESTING (PER IEEE 1100 AND 81) FOR GROUND ELECTRODE SYSTEMS, THE CONTRACTOR SHALL FURNISH AND INSTALL SUPPLEMENTAL GROUND ELECTRODES AS NEEDED TO ACHIEVE A TEST RESULT OF 5 OHMS OR LESS.
3. THE CONTRACTOR IS RESPONSIBLE FOR PROPERLY SEQUENCING GROUNDING AND UNDERGROUND CONDUIT INSTALLATION AS TO PREVENT ANY LOSS OF CONTINUITY IN THE GROUNDING SYSTEM OR DAMAGE TO THE CONDUIT AND PROVIDE TESTING RESULTS.
4. METAL CONDUIT AND TRAY SHALL BE GROUNDED AND MADE ELECTRICALLY CONTINUOUS WITH LISTED BONDING FITTINGS OR BY BONDING ACROSS THE DISCONTINUITY WITH #6 COPPER WIRE UL APPROVED GROUNDING TYPE CONDUIT CLAMPS.
5. METAL RACEWAY SHALL NOT BE USED AS THE NEC REQUIRED EQUIPMENT GROUND CONDUCTOR. STRANDED COPPER CONDUCTORS WITH GREEN INSULATION, SIZED IN ACCORDANCE WITH THE NEC, SHALL BE FURNISHED AND INSTALLED WITH THE POWER CIRCUITS TO BTS EQUIPMENT.
6. EACH CABINET FRAME SHALL BE DIRECTLY CONNECTED TO THE MASTER GROUND BAR WITH GREEN INSULATED SUPPLEMENTAL EQUIPMENT GROUND WIRES, #6 STRANDED COPPER OR LARGER FOR INDOOR BTS; #2 BARE SOLID TINNED COPPER FOR OUTDOOR BTS.
7. CONNECTIONS TO THE GROUND BUS SHALL NOT BE DOUBLED UP OR STACKED BACK TO BACK CONNECTIONS ON OPPOSITE SIDE OF THE GROUND BUS ARE PERMITTED.
8. ALL EXTERIOR GROUND CONDUCTORS BETWEEN EQUIPMENT/GROUND BARS AND THE GROUND RING SHALL BE #2 SOLID TINNED COPPER UNLESS OTHERWISE INDICATED.
9. ALUMINUM CONDUCTOR OR COPPER CLAD STEEL CONDUCTOR SHALL NOT BE USED FOR GROUNDING CONNECTIONS.
10. USE OF 90° BENDS IN THE PROTECTION GROUNDING CONDUCTORS SHALL BE AVOIDED WHEN 45° BENDS CAN BE ADEQUATELY SUPPORTED.
11. EXOTHERMIC WELDS SHALL BE USED FOR ALL GROUNDING CONNECTIONS BELOW GRADE.
12. ALL GROUND CONNECTIONS ABOVE GRADE (INTERIOR AND EXTERIOR) SHALL BE FORMED USING HIGH PRESS CRIMPS.
13. COMPRESSION GROUND CONNECTIONS MAY BE REPLACED BY EXOTHERMIC WELD CONNECTIONS.
14. ICE BRIDGE BONDING CONDUCTORS SHALL BE EXOTHERMICALLY BONDED OR BOLTED TO THE BRIDGE AND THE TOWER GROUND BAR.
15. APPROVED ANTIOXIDANT COATINGS (i.e. CONDUCTIVE GEL OR PASTE) SHALL BE USED ON ALL COMPRESSION AND BOLTED GROUND CONNECTIONS.
16. ALL EXTERIOR GROUND CONNECTIONS SHALL BE COATED WITH A CORROSION RESISTANT MATERIAL.
17. MISCELLANEOUS ELECTRICAL AND NON-ELECTRICAL METAL BOXES, FRAMES AND SUPPORTS SHALL BE BONDED TO THE GROUND RING, IN ACCORDANCE WITH THE NEC.
18. BOND ALL METALLIC OBJECTS WITHIN 6 ft OF MAIN GROUND RING WITH (1) #2 BARE SOLID TINNED COPPER GROUND CONDUCTOR.
19. GROUND CONDUCTORS USED FOR THE FACILITY GROUNDING AND LIGHTNING PROTECTION SYSTEMS SHALL NOT BE ROUTED THROUGH METALLIC OBJECTS THAT FORM A RING AROUND THE CONDUCTOR, SUCH AS METALLIC CONDUITS, METAL SUPPORT CLIPS OR SLEEVES THROUGH WALLS OR FLOORS. WHEN IT IS REQUIRED TO BE HOUSED IN CONDUIT TO MEET CODE REQUIREMENTS OR LOCAL CONDITIONS, NON-METALLIC MATERIAL SUCH AS PVC CONDUIT SHALL BE USED. WHERE USE OF METAL CONDUIT IS UNAVOIDABLE (i.e., NONMETALLIC CONDUIT PROHIBITED BY LOCAL CODE) THE GROUND CONDUCTOR SHALL BE BONDED TO EACH END OF THE METAL CONDUIT.
20. ALL GROUNDS THAT TRANSITION FROM BELOW GRADE TO ABOVE GRADE MUST BE #2 BARE SOLID TINNED COPPER IN 3/4" NON-METALLIC, FLEXIBLE CONDUIT FROM 24" BELOW GRADE TO WITHIN 3" TO 6" OF CAD-WELD TERMINATION POINT. THE EXPOSED END OF THE CONDUIT MUST BE SEALED WITH SILICONE CAULK. (ADD TRANSITIONING GROUND STANDARD DETAIL AS WELL).
21. BUILDINGS WHERE THE MAIN GROUNDING CONDUCTORS ARE REQUIRED TO BE ROUTED TO GRADE, THE CONTRACTOR SHALL ROUTE TWO GROUNDING CONDUCTORS FROM THE ROOFTOP, TOWERS, AND WATER TOWERS GROUNDING RING, TO THE EXISTING GROUNDING SYSTEM, THE GROUNDING CONDUCTORS SHALL NOT BE SMALLER THAN 2/0 COPPER. ROOFTOP GROUNDING RING SHALL BE BONDED TO THE EXISTING GROUNDING SYSTEM, THE BUILDING STEEL COLUMNS, LIGHTNING PROTECTION SYSTEM, AND BUILDING MAIN WATER LINE (FERROUS OR NONFERROUS METAL PIPING ONLY). DO NOT ATTACH GROUNDING TO FIRE SPRINKLER SYSTEM PIPES.




5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



2000 CORPORATE DRIVE
CANONSBURG, PA 15317



FROM ZERO TO INFINIGY
the solutions are endless
2500 W. HIGGINS RD., SUITE 500 |
HOFFMAN ESTATES, IL 60169
PHONE: 847-648-4068 | FAX: 518-690-0793
WWW.INFINIGY.COM



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
RCD	SS	CJW

RFDS REV #: ---

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	07/01/2021	ISSUED FOR REVIEW
0	08/31/2021	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
6039-Z0001-C

DISH Wireless L.L.C.
PROJECT INFORMATION
BOHVN00011A
117 WASHINGTON AVENUE
NORTH HAVEN, CT 06473

SHEET TITLE
GENERAL NOTES

SHEET NUMBER
GN-4

Exhibit D

Structural Analysis Report

Date: **June 05, 2021**



Crown Castle
2000 Corporate Drive
Canonsburg, PA 15317
(724) 416-2000

Subject: **Structural Analysis Report**

Carrier Designation: **DISH Network Co-Locate**
Site Number: BOHVN00011A
Site Name: CT-CCI-T-806454

Crown Castle Designation: **BU Number:** 806454
Site Name: NHV 112 948129
JDE Job Number: 645112
Work Order Number: 1966155
Order Number: 553355 Rev. 1

Engineering Firm Designation: **Crown Castle Project Number:** 1966155

Site Data: **117 Washington Avenue, NORTH HAVEN, NEW HAVEN County, CT**
Latitude 41° 23' 46.93", Longitude -72° 51' 27.67"
120 Foot - Monopole Tower

Crown Castle is pleased to submit this "**Structural Analysis Report**" to determine the structural integrity of the above-mentioned tower.

The purpose of the analysis is to determine acceptability of the tower stress level. Based on our analysis we have determined the tower stress level for the structure and foundation, under the following load case, to be:

LC7: Proposed Equipment Configuration

Sufficient Capacity – 58.5%

This analysis utilizes an ultimate 3-second gust wind speed of 125 mph as required by the 2018 Connecticut State Building Code. Applicable Standard references and design criteria are listed in Section 2 - "Analysis Criteria".

Structural analysis prepared by: Roy Zhou

Respectfully submitted by:

Digitally signed by Maham Barimani
Date: 2021.06.06 12:27:26

A circular professional engineer seal for Maham Barimani, State of Connecticut. The seal contains the text 'STATE OF CONNECTICUT', 'MAHAM BARIMANI', '30501', and 'LICENSED PROFESSIONAL ENGINEER'. There is a handwritten signature 'Barimani' in blue ink over the seal.

Maham Barimani, P.E.
Senior Project Engineer

TABLE OF CONTENTS

1) INTRODUCTION

2) ANALYSIS CRITERIA

- Table 1 - Proposed Equipment Configuration
- Table 2 - Non-Carrier Equipment To be Removed
- Table 3 - Other Considered Equipment

3) ANALYSIS PROCEDURE

- Table 4 - Documents Provided
- 3.1) Analysis Method
- 3.2) Assumptions

4) ANALYSIS RESULTS

- Table 5 - Section Capacity (Summary)
- Table 6 – Tower Component Stresses vs. Capacity – LC7
- 4.1) Recommendations

5) APPENDIX A

- tnxTower Output

6) APPENDIX B

- Base Level Drawing

7) APPENDIX C

- Additional Calculations

1) INTRODUCTION

This tower is a 120 ft Monopole tower designed by VALMONT.

2) ANALYSIS CRITERIA

TIA-222 Revision:	TIA-222-H
Risk Category:	II
Wind Speed:	125 mph
Exposure Category:	B
Topographic Factor:	1
Ice Thickness:	1.5 in
Wind Speed with Ice:	50 mph
Service Wind Speed:	60 mph

Table 1 - Proposed Equipment Configuration

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)
95.0	95.0	3	fujitsu	TA08025-B604	1	1-1/2
		3	fujitsu	TA08025-B605		
		3	jma wireless	MX08FRO665-21 w/ Mount Pipe		
		1	raycap	RDIDC-9181-PF-48		
		1	tower mounts	Commscope MC-PK8-DSH		

Table 2 – Non-Carrier Equipment To be Removed

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)
90.0	90.0	3	rfs/celwave	APXV18-206517S-C	-	-
		1	tower mounts	Pipe Mount [PM 601-3]		

Table 3 - Other Considered Equipment

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)
115.0	121.0	3	samsung telecommunications	MT6407-77A w/ Mount Pipe	14	1-5/8
	119.0	6	commscope_cfd	JAHH-65B-R3B		
		6	decibel_cfd	DB844G65ZAXY		
	117.0	3	commscope	CBC78T-DS-43-2X		
		3	commscope_cfd	VVSSP-65S-R1BV2		
		2	raycap	RRFDC-3315-PF-48		
		3	samsung telecommunications	RFV01U-D1A		
	3	samsung telecommunications	RFV01U-D2A			

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)
	115.0	1	tower mounts	Platform Mount [LP 301-1_KCKR]		
107.0	108.0	3	alcatel lucent	800MHZ RRH	-	-
	107.0	1	tower mounts	Pipe Mount [PM 601-3]		
	106.0	3	alcatel lucent	1900MHz RRH (65MHz)		
		3	alcatel lucent	800 EXTERNAL NOTCH FILTER		
105.0	109.0	1		A-ANT-23G-2-C	6 4 4	5/16 1-1/4 7983A
		1		VHLP2-18		
		1	andrew	VHLP800-11		
	106.0	3	alcatel lucent	TD-RRH8x20-25		
		9	rfs celwave	ACU-A20-N		
		3	rfs celwave_cfd	APXVSPP18-C-A20 w/ Mount Pipe		
		3	rfs celwave_cfd	APXVTM14-C-120 w/ Mount Pipe		
	105.0	3	argus technologies_cfd	LLPX310R w/ Mount Pipe		
		3	samsung telecommunications	FDD_R6_RRH		
		1	tower mounts	Platform Mount [LP 713-1]		
90.0	90.0	-	-	-	6	1-5/8

3) ANALYSIS PROCEDURE

Table 4 - Documents Provided

Document	Reference	Source
4-GEOTECHNICAL REPORTS	2294635	CCISITES
4-TOWER FOUNDATION DRAWINGS/DESIGN/SPECS	253930	CCISITES
4-TOWER MANUFACTURER DRAWINGS	253972	CCISITES

3.1) Analysis Method

tnxTower (version 8.0.9.0), a commercially available analysis software package, was used to create a three-dimensional model of the tower and calculate member stresses for various loading cases. Selected output from the analysis is included in Appendix A. When applicable, Crown Castle has calculated and provided the effective area for panel antennas using approved methods following the intent of the TIA-222 standard.

3.2) Assumptions

- 1) Tower and structures were maintained in accordance with the TIA-222 Standard.
- 2) The configuration of antennas, transmission cables, mounts and other appurtenances are as specified in Tables 1 and 2 and the referenced drawings.

This analysis may be affected if any assumptions are not valid or have been made in error. Crown Castle should be notified to determine the effect on the structural integrity of the tower.

4) ANALYSIS RESULTS

Table 5 - Section Capacity (Summary)

Section No.	Elevation (ft)	Component Type	Size	Critical Element	P (K)	SF*P_allow (K)	% Capacity	Pass / Fail
L1	120 - 77.33	Pole	TP30.45x21.91x0.2188	1	-13.59	1267.55	47.8	Pass
L2	77.33 - 34.33	Pole	TP38.61x29.0778x0.3125	2	-20.98	2297.05	57.0	Pass
L3	34.33 - 0	Pole	TP44.85x36.8512x0.375	3	-31.30	3298.74	58.5	Pass
							Summary	
						Pole (L3)	58.5	Pass
						Rating =	58.5	Pass

Table 6 - Tower Component Stresses vs. Capacity – LC7

Notes	Component	Elevation (ft)	% Capacity	Pass / Fail
1	Anchor Rods	0	54.4	Pass
1	Base Plate	0	29.2	Pass
1	Base Foundation (Structure)	0	29.4	Pass
1	Base Foundation (Soil Interaction)	0	25.3	Pass

Structure Rating (max from all components) =	58.5%
-----------------------------------------------------	--------------

Notes:


- 1) See additional documentation in "Appendix C – Additional Calculations" for calculations supporting the % capacity consumed.

4.1) Recommendations

Once the equipment in Table is removed, the tower and its foundation have sufficient capacity to carry the proposed load configuration. No modifications are required at this time.

APPENDIX A
TNXTOWER OUTPUT

Section	1	2	3	14.8
Length (ft)	42.6700	47.6700	40.0000	14.8
Number of Sides	12	12	12	6.7
Thickness (in)	0.2188	0.3125	0.3750	6.7
Socket Length (ft)	4.6700	5.6700	36.8512	6.7
Top Dia (in)	21.9100	29.0778	44.8500	6.7
Bot Dia (in)	30.4500	38.6100	44.8500	6.7
Grade	A572-65	A572-65	A572-65	6.7
Weight (K)	2.7	5.5	6.7	14.8



MATERIAL STRENGTH

GRADE	Fy	Fu	GRADE	Fy	Fu
A572-65	65 ksi	80 ksi			

TOWER DESIGN NOTES



1. Tower designed for Exposure B to the TIA-222-H Standard.
2. Tower designed for a 125 mph basic wind in accordance with the TIA-222-H Standard.
3. Tower is also designed for a 50 mph basic wind with 1.50 in ice. Ice is considered to increase in thickness with height.
4. Deflections are based upon a 60 mph wind.
5. Tower Risk Category II.
6. Topographic Category 1 with Crest Height of 0.0000 ft
7. TOWER RATING: 58.5%

77.3 ft

34.3 ft

0.0 ft

ALL REACTIONS
ARE FACTORED



Crown Castle
2000 Corporate Drive
Canonsburg, PA 15317
The Pathway to Possible Phone: (724) 416-2000
FAX:

Job: NHV 112 948129 (BU 806454)	Project: TEP No. 49925.553279	
Client: Crown Castle	Drawn by: RZhou	App'd:
Code: TIA-222-H	Date: 06/05/21	Scale: NTS
Path: C:\Users\RZhou\Desktop\Work Area\806454\WO 1868158 - SAIProd\806454.dwg	Dwg No. E-1	

Tower Input Data

The tower is a monopole.
 This tower is designed using the TIA-222-H standard.
 The following design criteria apply:

- Tower base elevation above sea level: 33.0000 ft.
- Basic wind speed of 125 mph.
- Risk Category II.
- Exposure Category B.
- Simplified Topographic Factor Procedure for wind speed-up calculations is used.
- Topographic Category: 1.
- Crest Height: 0.0000 ft.
- Nominal ice thickness of 1.5000 in.
- Ice thickness is considered to increase with height.
- Ice density of 56.00 pcf.
- A wind speed of 50 mph is used in combination with ice.
- Temperature drop of 50 °F.
- Deflections calculated using a wind speed of 60 mph.
- A non-linear (P-delta) analysis was used.
- Pressures are calculated at each section.
- Stress ratio used in pole design is 1.
- Tower analysis based on target reliabilities in accordance with Annex S.
- Load Modification Factors used: $K_{es}(F_w) = 0.95$, $K_{es}(t_i) = 0.85$.
- Maximum demand-capacity ratio is: 1.05.
- Local bending stresses due to climbing loads, feed line supports, and appurtenance mounts are not considered.

Options

Consider Moments - Legs Consider Moments - Horizontals Consider Moments - Diagonals Use Moment Magnification ✓ Use Code Stress Ratios ✓ Use Code Safety Factors - Guys Escalate Ice Always Use Max Kz Use Special Wind Profile Include Bolts In Member Capacity Leg Bolts Are At Top Of Section Secondary Horizontal Braces Leg Use Diamond Inner Bracing (4 Sided) SR Members Have Cut Ends SR Members Are Concentric	Distribute Leg Loads As Uniform Assume Legs Pinned ✓ Assume Rigid Index Plate ✓ Use Clear Spans For Wind Area Use Clear Spans For KL/r Retension Guys To Initial Tension ✓ Bypass Mast Stability Checks ✓ Use Azimuth Dish Coefficients ✓ Project Wind Area of Appurt. Autocalc Torque Arm Areas Add IBC .6D+W Combination ✓ Sort Capacity Reports By Component Triangulate Diamond Inner Bracing Treat Feed Line Bundles As Cylinder Ignore KL/ry For 60 Deg. Angle Legs	Use ASCE 10 X-Brace Ly Rules Calculate Redundant Bracing Forces Ignore Redundant Members in FEA SR Leg Bolts Resist Compression All Leg Panels Have Same Allowable Offset Girt At Foundation ✓ Consider Feed Line Torque Include Angle Block Shear Check Use TIA-222-H Bracing Resist. Exemption Use TIA-222-H Tension Splice Exemption <div style="text-align: center; background-color: #e0e0e0; padding: 2px;">Poles</div> ✓ Include Shear-Torsion Interaction Always Use Sub-Critical Flow Use Top Mounted Sockets Pole Without Linear Attachments Pole With Shroud Or No Appurtenances Outside and Inside Corner Radii Are Known
--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------

Tapered Pole Section Geometry

Section	Elevation ft	Section Length ft	Splice Length ft	Number of Sides	Top Diameter in	Bottom Diameter in	Wall Thickness in	Bend Radius in	Pole Grade
L1	120.0000-77.3300	42.6700	4.67	12	21.9100	30.4500	0.2188	0.8750	A572-65 (65 ksi)
L2	77.3300-34.3300	47.6700	5.67	12	29.0778	38.6100	0.3125	1.2500	A572-65 (65 ksi)
L3	34.3300-0.0000	40.0000		12	36.8512	44.8500	0.3750	1.5000	A572-65 (65 ksi)

Tapered Pole Properties

Section	Tip Dia. in	Area in ²	I in ⁴	r in	C in	I/C in ³	J in ⁴	I/Q in ²	w in	w/t
L1	22.6057	15.2788	917.5793	7.7655	11.3494	80.8484	1859.2645	7.5197	5.2856	24.163
	31.4470	21.2941	2484.0378	10.8228	15.7731	157.4857	5033.3340	10.4803	7.5743	34.626
L2	30.9601	28.9451	3057.0357	10.2980	15.0623	202.9591	6194.3832	14.2459	6.9554	22.257
	39.8618	38.5369	7214.4482	13.7105	20.0000	360.7228	14618.4279	18.9667	9.5100	30.432
L3	39.1927	44.0450	7480.0161	13.0585	19.0889	391.8510	15156.5406	21.6776	8.8711	23.656
	46.2999	53.7036	13558.7908	15.9221	23.2323	583.6181	27473.7861	26.4313	11.0148	29.373

Tower Elevation ft	Gusset Area (per face) ft ²	Gusset Thickness in	Gusset Grade	Adjust. Factor A _r	Adjust. Factor A _r	Weight Mult.	Double Angle Stitch Bolt Spacing Diagonals in	Double Angle Stitch Bolt Spacing Horizontals in	Double Angle Stitch Bolt Spacing Redundants in
L1 120.0000-77.3300				1	1	1			
L2 77.3300-34.3300				1	1	1			
L3 34.3300-0.0000				1	1	1			

Feed Line/Linear Appurtenances - Entered As Round Or Flat

Description	Sector	Exclude From Torque Calculation	Component Type	Placement ft	Total Number	Number Per Row	Start/End Position	Width or Diameter r in	Perimeter r in	Weight plf
FXL-1480(1-1/4")	C	No	Surface Ar	105.0000 - 0.0000	4	4	-0.342 -0.217	1.5700		0.45
ATCB-B01-001 (5/16")	C	No	Surface Ar	105.0000 - 0.0000	2	2	0.442 0.467	0.3300		0.06
2" (Nominal) Conduit	C	No	Surface Ar	105.0000 - 0.0000	2	2	0.400 0.442	2.3750		0.72
7983A(ELLIPTICAL)	C	No	Surface Ar	105.0000 - 0.0000	4	2	0.467 0.500	0.5730		0.08
AVA7-50(1-5/8")	C	No	Surface Ar	90.0000 - 0.0000	6	6	0.083 0.333	2.0100		0.70
CU12PSM9P6XXX(1-1/2) ***	A	No	Surface Ar	95.0000 - 0.0000	1	1	0.150 0.150	1.6000		2.35

Feed Line/Linear Appurtenances - Entered As Area

Description	Face or Leg	Allow Shield	Exclude From Torque Calculation	Component Type	Placement ft	Total Number		C _{AA} ft ² /ft	Weight plf
AVA7-50(1-5/8")	C	No	No	Inside Pole	115.0000 - 0.0000	14	No Ice	0.0000	0.70
							1/2" Ice	0.0000	0.70
							1" Ice	0.0000	0.70
							2" Ice	0.0000	0.70
ATCB-B01-001 (5/16")	C	No	No	Inside Pole	105.0000 - 0.0000	4	No Ice	0.0000	0.06
							1/2" Ice	0.0000	0.06
							1" Ice	0.0000	0.06
							2" Ice	0.0000	0.06

Feed Line/Linear Appurtenances Section Areas

Tower Section	Tower Elevation ft	Face	A _R ft ²	A _F ft ²	C _{AA} In Face ft ²	C _{AA} Out Face ft ²	Weight K
L1	120.0000-77.3300	A	0.000	0.000	2.827	0.000	0.04
		B	0.000	0.000	0.000	0.000	0.00
		C	0.000	0.000	50.797	0.000	0.53
L2	77.3300-34.3300	A	0.000	0.000	6.880	0.000	0.10
		B	0.000	0.000	0.000	0.000	0.00
		C	0.000	0.000	107.053	0.000	0.77
L3	34.3300-0.0000	A	0.000	0.000	5.493	0.000	0.08
		B	0.000	0.000	0.000	0.000	0.00
		C	0.000	0.000	85.468	0.000	0.62

Feed Line/Linear Appurtenances Section Areas - With Ice

Tower Section	Tower Elevation ft	Face or Leg	Ice Thickness in	A _R ft ²	A _F ft ²	C _{AA} In Face ft ²	C _{AA} Out Face ft ²	Weight K
L1	120.0000-77.3300	A	1.421	0.000	0.000	7.850	0.000	0.13
		B		0.000	0.000	0.000	0.000	0.00
		C		0.000	0.000	107.328	0.000	1.57
L2	77.3300-34.3300	A	1.343	0.000	0.000	19.104	0.000	0.33
		B		0.000	0.000	0.000	0.000	0.00
		C		0.000	0.000	210.214	0.000	2.82
L3	34.3300-0.0000	A	1.191	0.000	0.000	14.715	0.000	0.25
		B		0.000	0.000	0.000	0.000	0.00
		C		0.000	0.000	164.471	0.000	2.15

Feed Line Center of Pressure

Section	Elevation ft	CP _x in	CP _z in	CP _x Ice in	CP _z Ice in
L1	120.0000-77.3300	-1.3869	3.8699	-1.9306	3.5412
L2	77.3300-34.3300	-2.6277	6.3075	-3.0089	5.2610
L3	34.3300-0.0000	-2.8383	6.8189	-3.3608	5.9449

Note: For pole sections, center of pressure calculations do not consider feed line shielding.

Shielding Factor Ka

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K _a No Ice	K _a Ice
L1	2	FXL-1480(1-1/4")	77.33 - 105.00	1.0000	1.0000
L1	3	ATCB-B01-001 (5/16")	77.33 - 105.00	1.0000	1.0000
L1	4	2" (Nominal) Conduit	77.33 - 105.00	1.0000	1.0000
L1	5	7983A(ELLIPTICAL)	77.33 - 105.00	1.0000	1.0000
L1	6	AVA7-50(1-5/8")	77.33 - 90.00	1.0000	1.0000
L1	7	CU12PSM9P6XXX(1-1/2)	77.33 - 95.00	1.0000	1.0000
L2	2	FXL-1480(1-1/4")	34.33 - 77.33	1.0000	1.0000
L2	3	ATCB-B01-001 (5/16")	34.33 - 77.33	1.0000	1.0000
L2	4	2" (Nominal) Conduit	34.33 - 77.33	1.0000	1.0000
L2	5	7983A(ELLIPTICAL)	34.33 - 77.33	1.0000	1.0000
L2	6	AVA7-50(1-5/8")	34.33 - 77.33	1.0000	1.0000
L2	7	CU12PSM9P6XXX(1-1/2)	34.33 - 77.33	1.0000	1.0000
L3	2	FXL-1480(1-1/4")	0.00 - 34.33	1.0000	1.0000
L3	3	ATCB-B01-001 (5/16")	0.00 - 34.33	1.0000	1.0000
L3	4	2" (Nominal) Conduit	0.00 - 34.33	1.0000	1.0000
L3	5	7983A(ELLIPTICAL)	0.00 - 34.33	1.0000	1.0000
L3	6	AVA7-50(1-5/8")	0.00 - 34.33	1.0000	1.0000
L3	7	CU12PSM9P6XXX(1-1/2)	0.00 - 34.33	1.0000	1.0000

Discrete Tower Loads

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment t °	Placement ft	C _A A _A Front ft ²	C _A A _A Side ft ²	Weight K	
(2) DB844G65ZAXY	A	From Centroid-Leg	4.0000 0.00 4.00	0.00	115.0000	No Ice	4.2400	3.5500	0.02
						1/2" Ice	4.7500	4.0500	0.05
						Ice	5.2800	4.5600	0.09
						1" Ice	6.3800	5.6300	0.17
						2" Ice			
(2) DB844G65ZAXY	B	From Centroid-Leg	4.0000 0.00 4.00	0.00	115.0000	No Ice	4.2400	3.5500	0.02
						1/2" Ice	4.7500	4.0500	0.05
						Ice	5.2800	4.5600	0.09
						1" Ice	6.3800	5.6300	0.17
						2" Ice			
(2) DB844G65ZAXY	C	From Centroid-Leg	4.0000 0.00 4.00	0.00	115.0000	No Ice	4.2400	3.5500	0.02
						1/2" Ice	4.7500	4.0500	0.05
						Ice	5.2800	4.5600	0.09
						1" Ice	6.3800	5.6300	0.17
						2" Ice			
MT6407-77A w/ Mount Pipe	A	From Centroid-Leg	4.0000 0.00 6.00	0.00	115.0000	No Ice	4.9069	2.6821	0.10
						1/2" Ice	5.2559	3.1450	0.14
						Ice	5.6147	3.6241	0.18
						1" Ice	6.3615	4.6310	0.29

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment t °	Placement ft	C _A A _A Front ft ²	C _A A _A Side ft ²	Weight K	
MT6407-77A w/ Mount Pipe	B	From Centroid-Leg	4.0000 0.00 6.00	0.00	115.0000	2" Ice			
						No Ice	4.9069	2.6821	0.10
						1/2"	5.2559	3.1450	0.14
						Ice	5.6147	3.6241	0.18
MT6407-77A w/ Mount Pipe	C	From Centroid-Leg	4.0000 0.00 6.00	0.00	115.0000	1" Ice	6.3615	4.6310	0.29
						2" Ice			
						No Ice	4.9069	2.6821	0.10
						1/2"	5.2559	3.1450	0.14
(2) JAHH-65B-R3B	A	From Centroid-Leg	4.0000 0.00 4.00	0.00	115.0000	Ice	5.6147	3.6241	0.18
						1" Ice	6.3615	4.6310	0.29
						2" Ice			
						No Ice	5.2900	3.0500	0.06
(2) JAHH-65B-R3B	B	From Centroid-Leg	4.0000 0.00 4.00	0.00	115.0000	1/2"	5.7500	3.4800	0.12
						Ice	6.2200	3.9300	0.19
						1" Ice	7.2000	4.8400	0.33
						2" Ice			
(2) JAHH-65B-R3B	C	From Centroid-Leg	4.0000 0.00 4.00	0.00	115.0000	No Ice	5.2900	3.0500	0.06
						1/2"	5.7500	3.4800	0.12
						Ice	6.2200	3.9300	0.19
						1" Ice	7.2000	4.8400	0.33
VVSSP-65S-R1BV2	A	From Centroid-Leg	4.0000 0.00 2.00	0.00	115.0000	2" Ice			
						No Ice	1.8600	0.7200	0.03
						1/2"	2.1000	0.9200	0.04
						Ice	2.3600	1.1200	0.06
VVSSP-65S-R1BV2	B	From Centroid-Leg	4.0000 0.00 2.00	0.00	115.0000	1" Ice	2.9000	1.5700	0.11
						2" Ice			
						No Ice	1.8600	0.7200	0.03
						1/2"	2.1000	0.9200	0.04
VVSSP-65S-R1BV2	C	From Centroid-Leg	4.0000 0.00 2.00	0.00	115.0000	Ice	2.3600	1.1200	0.06
						1" Ice	2.9000	1.5700	0.11
						2" Ice			
						No Ice	1.8600	0.7200	0.03
CBC78T-DS-43-2X	A	From Centroid-Leg	4.0000 0.00 2.00	0.00	115.0000	1/2"	2.1000	0.9200	0.04
						Ice	2.3600	1.1200	0.06
						1" Ice	2.9000	1.5700	0.11
						2" Ice			
(2) CBC78T-DS-43-2X	B	From Centroid-Leg	4.0000 0.00 2.00	0.00	115.0000	No Ice	0.3680	0.5120	0.02
						1/2"	0.4456	0.6046	0.03
						Ice	0.5306	0.7046	0.04
						1" Ice	0.7228	0.9268	0.06
RRFDC-3315-PF-48	A	From Centroid-Leg	4.0000 0.00 2.00	0.00	115.0000	2" Ice			
						No Ice	3.3636	2.1921	0.03
						1/2"	3.5972	2.3950	0.06
						Ice	3.8383	2.6056	0.09
RRFDC-3315-PF-48	B	From Centroid-Leg	4.0000 0.00 2.00	0.00	115.0000	1" Ice	4.3426	3.0491	0.17
						2" Ice			
						No Ice	3.3636	2.1921	0.03
						1/2"	3.5972	2.3950	0.06
RFV01U-D1A	A	From Centroid-Leg	4.0000 0.00 2.00	0.00	115.0000	Ice	3.8383	2.6056	0.09
						1" Ice	4.3426	3.0491	0.17
						2" Ice			
						No Ice	1.8750	1.2500	0.08
						1/2"	2.0454	1.3926	0.10
						Ice	2.2231	1.5426	0.12
						1" Ice	2.6009	1.8648	0.18
						2" Ice			

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment t °	Placement ft	C _A A _A Front ft ²	C _A A _A Side ft ²	Weight K	
(2) RFV01U-D1A	B	From Centroid-Leg	4.0000 0.00 2.00	0.00	115.0000	2" Ice			
						No Ice	1.8750	1.2500	0.08
						1/2" Ice	2.0454	1.3926	0.10
						Ice	2.2231	1.5426	0.12
						1" Ice	2.6009	1.8648	0.18
(2) RFV01U-D2A	B	From Centroid-Leg	4.0000 0.00 2.00	0.00	115.0000	2" Ice			
						No Ice	1.8750	1.0125	0.07
						1/2" Ice	2.0454	1.1445	0.09
						Ice	2.2231	1.2840	0.11
						1" Ice	2.6009	1.5851	0.15
RFV01U-D2A	C	From Centroid-Leg	4.0000 0.00 2.00	0.00	115.0000	2" Ice			
						No Ice	1.8750	1.0125	0.07
						1/2" Ice	2.0454	1.1445	0.09
						Ice	2.2231	1.2840	0.11
						1" Ice	2.6009	1.5851	0.15
Platform Mount [LP 301-1_KCKR]	C	None		0.00	115.0000	2" Ice			
						No Ice	35.0300	35.0300	1.86
						1/2" Ice	44.4600	44.4600	2.52
						Ice	53.7200	53.7200	3.33
						1" Ice	72.2900	72.2900	5.42
** 800MHZ RRH	A	From Leg	1.0000 0.00 1.00	0.00	107.0000	2" Ice			
						No Ice	2.1342	1.7730	0.05
						1/2" Ice	2.3195	1.9461	0.07
						Ice	2.5123	2.1267	0.10
						1" Ice	2.9201	2.5100	0.16
800MHZ RRH	B	From Leg	1.0000 0.00 1.00	0.00	107.0000	2" Ice			
						No Ice	2.1342	1.7730	0.05
						1/2" Ice	2.3195	1.9461	0.07
						Ice	2.5123	2.1267	0.10
						1" Ice	2.9201	2.5100	0.16
800MHZ RRH	C	From Leg	1.0000 0.00 1.00	0.00	107.0000	2" Ice			
						No Ice	2.1342	1.7730	0.05
						1/2" Ice	2.3195	1.9461	0.07
						Ice	2.5123	2.1267	0.10
						1" Ice	2.9201	2.5100	0.16
800 EXTERNAL NOTCH FILTER	A	From Leg	1.0000 0.00 -1.00	0.00	107.0000	2" Ice			
						No Ice	0.6601	0.3211	0.01
						1/2" Ice	0.7627	0.3983	0.02
						Ice	0.8727	0.4830	0.02
						1" Ice	1.1149	0.6744	0.04
800 EXTERNAL NOTCH FILTER	B	From Leg	1.0000 0.00 -1.00	0.00	107.0000	2" Ice			
						No Ice	0.6601	0.3211	0.01
						1/2" Ice	0.7627	0.3983	0.02
						Ice	0.8727	0.4830	0.02
						1" Ice	1.1149	0.6744	0.04
800 EXTERNAL NOTCH FILTER	C	From Leg	1.0000 0.00 -1.00	0.00	107.0000	2" Ice			
						No Ice	0.6601	0.3211	0.01
						1/2" Ice	0.7627	0.3983	0.02
						Ice	0.8727	0.4830	0.02
						1" Ice	1.1149	0.6744	0.04
1900MHz RRH (65MHz)	A	From Leg	1.0000 0.00 -1.00	0.00	107.0000	2" Ice			
						No Ice	2.3125	2.3750	0.06
						1/2" Ice	2.5168	2.5809	0.08
						Ice	2.7284	2.7943	0.11
						1" Ice	3.1740	3.2431	0.18
1900MHz RRH (65MHz)	B	From Leg	1.0000 0.00 -1.00	0.00	107.0000	2" Ice			
						No Ice	2.3125	2.3750	0.06
						1/2" Ice	2.5168	2.5809	0.08
						Ice	2.7284	2.7943	0.11
						1" Ice	3.1740	3.2431	0.18
1900MHz RRH (65MHz)	C	From Leg	1.0000 0.00 -1.00	0.00	107.0000	2" Ice			
						No Ice	2.3125	2.3750	0.06
						1/2" Ice	2.5168	2.5809	0.08
						Ice	2.7284	2.7943	0.11
						1" Ice	3.1740	3.2431	0.18

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment t °	Placement ft	C _{AA} Front ft ²	C _{AA} Side ft ²	Weight K	
						1" Ice 2" Ice	3.1740 3.2431	0.18	
Pipe Mount [PM 601-3]	C	None		0.00	107.0000	No Ice 1/2" Ice 1" Ice 2" Ice	3.1700 3.7900 4.4200 5.7600	0.20 0.23 0.28 0.40	
**									
APXVSPP18-C-A20 w/ Mount Pipe	A	From Centroid-Leg	4.0000 0.00 1.00	0.00	105.0000	No Ice 1/2" Ice 1" Ice 2" Ice	4.6000 5.0500 5.5000 6.4400	4.0100 4.4500 4.8900 5.8200	0.10 0.16 0.23 0.42
APXVSPP18-C-A20 w/ Mount Pipe	B	From Centroid-Leg	4.0000 0.00 1.00	0.00	105.0000	No Ice 1/2" Ice 1" Ice 2" Ice	4.6000 5.0500 5.5000 6.4400	4.0100 4.4500 4.8900 5.8200	0.10 0.16 0.23 0.42
APXVSPP18-C-A20 w/ Mount Pipe	C	From Centroid-Leg	4.0000 0.00 1.00	0.00	105.0000	No Ice 1/2" Ice 1" Ice 2" Ice	4.6000 5.0500 5.5000 6.4400	4.0100 4.4500 4.8900 5.8200	0.10 0.16 0.23 0.42
LLPX310R w/ Mount Pipe	A	From Centroid-Leg	4.0000 0.00 0.00	0.00	105.0000	No Ice 1/2" Ice 1" Ice 2" Ice	3.8800 4.2900 4.7200 5.6100	2.3600 2.7300 3.1200 3.9400	0.06 0.09 0.13 0.24
LLPX310R w/ Mount Pipe	B	From Centroid-Leg	4.0000 0.00 0.00	0.00	105.0000	No Ice 1/2" Ice 1" Ice 2" Ice	3.8800 4.2900 4.7200 5.6100	2.3600 2.7300 3.1200 3.9400	0.06 0.09 0.13 0.24
LLPX310R w/ Mount Pipe	C	From Centroid-Leg	4.0000 0.00 0.00	0.00	105.0000	No Ice 1/2" Ice 1" Ice 2" Ice	3.8800 4.2900 4.7200 5.6100	2.3600 2.7300 3.1200 3.9400	0.06 0.09 0.13 0.24
APXVTM14-C-120 w/ Mount Pipe	A	From Centroid-Leg	4.0000 0.00 1.00	0.00	105.0000	No Ice 1/2" Ice 1" Ice 2" Ice	4.0900 4.4800 4.8800 5.7100	2.8600 3.2300 3.6100 4.4000	0.08 0.13 0.19 0.33
APXVTM14-C-120 w/ Mount Pipe	B	From Centroid-Leg	4.0000 0.00 1.00	0.00	105.0000	No Ice 1/2" Ice 1" Ice 2" Ice	4.0900 4.4800 4.8800 5.7100	2.8600 3.2300 3.6100 4.4000	0.08 0.13 0.19 0.33
APXVTM14-C-120 w/ Mount Pipe	C	From Centroid-Leg	4.0000 0.00 1.00	0.00	105.0000	No Ice 1/2" Ice 1" Ice 2" Ice	4.0900 4.4800 4.8800 5.7100	2.8600 3.2300 3.6100 4.4000	0.08 0.13 0.19 0.33
(3) ACU-A20-N	A	From Centroid-Leg	4.0000 0.00 1.00	0.00	105.0000	No Ice 1/2" Ice 1" Ice 2" Ice	0.0667 0.1037 0.1481 0.2593	0.1167 0.1620 0.2148 0.3426	0.00 0.00 0.00 0.01
(3) ACU-A20-N	B	From Centroid-Leg	4.0000 0.00 1.00	0.00	105.0000	No Ice 1/2" Ice 1" Ice 2" Ice	0.0667 0.1037 0.1481 0.2593	0.1167 0.1620 0.2148 0.3426	0.00 0.00 0.00 0.01

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C _A A _{Front}	C _A A _{Side}	Weight	
			Horz	Lateral						Vert
			ft	ft	°	ft	ft ²	ft ²	K	
(3) ACU-A20-N	C	From Centroid-Leg	4.0000	0.00	0.00	105.0000	No Ice	0.0667	0.1167	0.00
			0.00				1/2"	0.1037	0.1620	0.00
			1.00				Ice	0.1481	0.2148	0.00
							1" Ice	0.2593	0.3426	0.01
							2" Ice			
FDD_R6_RRH	A	From Centroid-Leg	4.0000	0.00	0.00	105.0000	No Ice	1.5333	0.6840	0.03
			0.00				1/2"	1.6898	0.7999	0.04
			0.00				Ice	1.8537	0.9228	0.06
							1" Ice	2.2037	1.1926	0.09
							2" Ice			
FDD_R6_RRH	B	From Centroid-Leg	4.0000	0.00	0.00	105.0000	No Ice	1.5333	0.6840	0.03
			0.00				1/2"	1.6898	0.7999	0.04
			0.00				Ice	1.8537	0.9228	0.06
							1" Ice	2.2037	1.1926	0.09
							2" Ice			
FDD_R6_RRH	C	From Centroid-Leg	4.0000	0.00	0.00	105.0000	No Ice	1.5333	0.6840	0.03
			0.00				1/2"	1.6898	0.7999	0.04
			0.00				Ice	1.8537	0.9228	0.06
							1" Ice	2.2037	1.1926	0.09
							2" Ice			
TD-RRH8x20-25	A	From Centroid-Leg	4.0000	0.00	0.00	105.0000	No Ice	4.0455	1.5345	0.07
			0.00				1/2"	4.2975	1.7142	0.10
			1.00				Ice	4.5570	1.9008	0.13
							1" Ice	5.0981	2.2951	0.20
							2" Ice			
TD-RRH8x20-25	B	From Centroid-Leg	4.0000	0.00	0.00	105.0000	No Ice	4.0455	1.5345	0.07
			0.00				1/2"	4.2975	1.7142	0.10
			1.00				Ice	4.5570	1.9008	0.13
							1" Ice	5.0981	2.2951	0.20
							2" Ice			
TD-RRH8x20-25	C	From Centroid-Leg	4.0000	0.00	0.00	105.0000	No Ice	4.0455	1.5345	0.07
			0.00				1/2"	4.2975	1.7142	0.10
			1.00				Ice	4.5570	1.9008	0.13
							1" Ice	5.0981	2.2951	0.20
							2" Ice			
(2) 6' x 2" Mount Pipe	A	From Centroid-Leg	4.0000	0.00	0.00	105.0000	No Ice	1.4250	1.4250	0.02
			0.00				1/2"	1.9250	1.9250	0.03
			0.00				Ice	2.2939	2.2939	0.05
							1" Ice	3.0596	3.0596	0.09
							2" Ice			
6' x 2" Mount Pipe	C	From Centroid-Leg	4.0000	0.00	0.00	105.0000	No Ice	1.4250	1.4250	0.02
			0.00				1/2"	1.9250	1.9250	0.03
			0.00				Ice	2.2939	2.2939	0.05
							1" Ice	3.0596	3.0596	0.09
							2" Ice			
Platform Mount [LP 713-1]	C	None			0.00	105.0000	No Ice	32.8900	32.8900	1.51
							1/2"	35.7600	35.7600	2.23
							Ice	38.7600	38.7600	3.03
							1" Ice	45.2600	45.2600	4.86
							2" Ice			
** MX08FRO665-21 w/ Mount Pipe	A	From Leg	4.0000	0.00	0.00	95.0000	No Ice	8.0100	4.2300	0.11
			0.00				1/2"	8.5200	4.6900	0.19
			0.00				Ice	9.0400	5.1600	0.29
							1" Ice	10.1100	6.1200	0.52
							2" Ice			
MX08FRO665-21 w/ Mount Pipe	B	From Leg	4.0000	0.00	0.00	95.0000	No Ice	8.0100	4.2300	0.11
			0.00				1/2"	8.5200	4.6900	0.19
			0.00				Ice	9.0400	5.1600	0.29
							1" Ice	10.1100	6.1200	0.52
							2" Ice			
MX08FRO665-21 w/ Mount Pipe	C	From Leg	4.0000	0.00	0.00	95.0000	No Ice	8.0100	4.2300	0.11
			0.00				1/2"	8.5200	4.6900	0.19
			0.00				Ice	9.0400	5.1600	0.29
							1" Ice	10.1100	6.1200	0.52
							2" Ice			

Description	Face or Leg	Offset Type	Offsets:			Azimuth Adjustment	Placement	C _A A _A Front	C _A A _A Side	Weight			
			Horz	Lateral	Vert						ft	ft ²	ft ²
TA08025-B604	A	From Leg	4.0000	0.00	95.0000	0.00	2" Ice	1.9635	0.9811	0.06			
			0.00				No Ice				2.1378	1.1117	0.08
			0.00				1/2"				2.3195	1.2496	0.10
							Ice				2.7052	1.5477	0.15
TA08025-B604	B	From Leg	4.0000	0.00	95.0000	0.00	2" Ice	1.9635	0.9811	0.06			
			0.00				No Ice				2.1378	1.1117	0.08
			0.00				1/2"				2.3195	1.2496	0.10
							Ice				2.7052	1.5477	0.15
TA08025-B604	C	From Leg	4.0000	0.00	95.0000	0.00	2" Ice	1.9635	0.9811	0.06			
			0.00				No Ice				2.1378	1.1117	0.08
			0.00				1/2"				2.3195	1.2496	0.10
							Ice				2.7052	1.5477	0.15
TA08025-B605	A	From Leg	4.0000	0.00	95.0000	0.00	2" Ice	1.9635	1.1295	0.08			
			0.00				No Ice				2.1378	1.2666	0.09
			0.00				1/2"				2.3195	1.4112	0.11
							Ice				2.7052	1.7225	0.16
TA08025-B605	B	From Leg	4.0000	0.00	95.0000	0.00	2" Ice	1.9635	1.1295	0.08			
			0.00				No Ice				2.1378	1.2666	0.09
			0.00				1/2"				2.3195	1.4112	0.11
							Ice				2.7052	1.7225	0.16
TA08025-B605	C	From Leg	4.0000	0.00	95.0000	0.00	2" Ice	1.9635	1.1295	0.08			
			0.00				No Ice				2.1378	1.2666	0.09
			0.00				1/2"				2.3195	1.4112	0.11
							Ice				2.7052	1.7225	0.16
RDIDC-9181-PF-48	B	From Leg	4.0000	0.00	95.0000	0.00	2" Ice	2.3118	1.2931	0.02			
			0.00				No Ice				2.5022	1.4479	0.04
			0.00				1/2"				2.7000	1.6101	0.06
							Ice				3.1179	1.9566	0.12
(2) 8' x 2" Mount Pipe	A	From Leg	4.0000	0.00	95.0000	0.00	2" Ice	1.9000	1.9000	0.03			
			0.00				No Ice				2.7281	2.7281	0.04
			0.00				1/2"				3.4009	3.4009	0.06
							Ice				4.3962	4.3962	0.12
(2) 8' x 2" Mount Pipe	B	From Leg	4.0000	0.00	95.0000	0.00	2" Ice	1.9000	1.9000	0.03			
			0.00				No Ice				2.7281	2.7281	0.04
			0.00				1/2"				3.4009	3.4009	0.06
							Ice				4.3962	4.3962	0.12
(2) 8' x 2" Mount Pipe	C	From Leg	4.0000	0.00	95.0000	0.00	2" Ice	1.9000	1.9000	0.03			
			0.00				No Ice				2.7281	2.7281	0.04
			0.00				1/2"				3.4009	3.4009	0.06
							Ice				4.3962	4.3962	0.12
Commscope MC-PK8-DSH	C	None		0.00	95.0000	0.00	2" Ice	34.2400	34.2400	1.75			
							No Ice				62.9500	62.9500	2.10
							1/2"				91.6600	91.6600	2.45
							Ice				149.0800	149.0800	3.15
						1" Ice							
						2" Ice							

Dishes

Description	Face or Leg	Dish Type	Offset Type	Offsets: Horz Lateral Vert	Azimuth Adjustment °	3 dB Beam Width °	Elevation ft	Outside Diameter ft	Aperture Area ft ²	Weight K	
A-ANT-23G-2-C	A	Paraboloid w/Shroud (HP)	From Centroid-Leg	4.0000	-10.00		105.0000	2.1750	No Ice	3.7200	0.01
				0.00					1/2" Ice	4.0100	0.02
				4.00					1" Ice	4.3000	0.03
									2" Ice	4.8800	0.05
VHLP2-18	A	Paraboloid w/Shroud (HP)	From Centroid-Leg	4.0000	30.00		105.0000	2.0000	No Ice	3.1400	0.03
				0.00					1/2" Ice	3.4100	0.05
				4.00					1" Ice	3.6800	0.07
									2" Ice	4.2100	0.10
VHLP800-11	C	Paraboloid w/Shroud (HP)	From Centroid-Leg	4.0000	-10.00		105.0000	2.9167	No Ice	6.6800	0.02
				0.00					1/2" Ice	7.0700	0.03
				4.00					1" Ice	7.4600	0.03
									2" Ice	8.2300	0.07

Load Combinations

Comb. No.	Description
1	Dead Only
2	1.2 Dead+1.0 Wind 0 deg - No Ice
3	0.9 Dead+1.0 Wind 0 deg - No Ice
4	1.2 Dead+1.0 Wind 30 deg - No Ice
5	0.9 Dead+1.0 Wind 30 deg - No Ice
6	1.2 Dead+1.0 Wind 60 deg - No Ice
7	0.9 Dead+1.0 Wind 60 deg - No Ice
8	1.2 Dead+1.0 Wind 90 deg - No Ice
9	0.9 Dead+1.0 Wind 90 deg - No Ice
10	1.2 Dead+1.0 Wind 120 deg - No Ice
11	0.9 Dead+1.0 Wind 120 deg - No Ice
12	1.2 Dead+1.0 Wind 150 deg - No Ice
13	0.9 Dead+1.0 Wind 150 deg - No Ice
14	1.2 Dead+1.0 Wind 180 deg - No Ice
15	0.9 Dead+1.0 Wind 180 deg - No Ice
16	1.2 Dead+1.0 Wind 210 deg - No Ice
17	0.9 Dead+1.0 Wind 210 deg - No Ice
18	1.2 Dead+1.0 Wind 240 deg - No Ice
19	0.9 Dead+1.0 Wind 240 deg - No Ice
20	1.2 Dead+1.0 Wind 270 deg - No Ice
21	0.9 Dead+1.0 Wind 270 deg - No Ice
22	1.2 Dead+1.0 Wind 300 deg - No Ice
23	0.9 Dead+1.0 Wind 300 deg - No Ice
24	1.2 Dead+1.0 Wind 330 deg - No Ice
25	0.9 Dead+1.0 Wind 330 deg - No Ice
26	1.2 Dead+1.0 Ice+1.0 Temp
27	1.2 Dead+1.0 Wind 0 deg+1.0 Ice+1.0 Temp
28	1.2 Dead+1.0 Wind 30 deg+1.0 Ice+1.0 Temp
29	1.2 Dead+1.0 Wind 60 deg+1.0 Ice+1.0 Temp
30	1.2 Dead+1.0 Wind 90 deg+1.0 Ice+1.0 Temp
31	1.2 Dead+1.0 Wind 120 deg+1.0 Ice+1.0 Temp
32	1.2 Dead+1.0 Wind 150 deg+1.0 Ice+1.0 Temp
33	1.2 Dead+1.0 Wind 180 deg+1.0 Ice+1.0 Temp
34	1.2 Dead+1.0 Wind 210 deg+1.0 Ice+1.0 Temp
35	1.2 Dead+1.0 Wind 240 deg+1.0 Ice+1.0 Temp
36	1.2 Dead+1.0 Wind 270 deg+1.0 Ice+1.0 Temp
37	1.2 Dead+1.0 Wind 300 deg+1.0 Ice+1.0 Temp
38	1.2 Dead+1.0 Wind 330 deg+1.0 Ice+1.0 Temp
39	Dead+Wind 0 deg - Service
40	Dead+Wind 30 deg - Service
41	Dead+Wind 60 deg - Service
42	Dead+Wind 90 deg - Service
43	Dead+Wind 120 deg - Service
44	Dead+Wind 150 deg - Service
45	Dead+Wind 180 deg - Service
46	Dead+Wind 210 deg - Service

Comb. No.	Description
47	Dead+Wind 240 deg - Service
48	Dead+Wind 270 deg - Service
49	Dead+Wind 300 deg - Service
50	Dead+Wind 330 deg - Service

Maximum Member Forces

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Axial K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
L1	120 - 77.33	Pole	Max Tension	14	0.00	-0.00	0.00
			Max. Compression	26	-30.45	-2.41	-1.45
			Max. Mx	8	-13.59	-361.36	2.55
			Max. My	14	-13.59	1.49	-361.68
			Max. Vy	8	14.79	-361.36	2.55
			Max. Vx	14	14.83	1.49	-361.68
			Max. Torque	8			0.97
L2	77.33 - 34.33	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-42.38	-2.12	-4.88
			Max. Mx	8	-20.99	-1059.75	6.92
			Max. My	14	-20.99	5.95	-1062.33
			Max. Vy	8	18.42	-1059.75	6.92
			Max. Vx	14	18.46	5.95	-1062.33
			Max. Torque	8			0.87
L3	34.33 - 0	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-57.09	-1.66	-8.49
			Max. Mx	8	-31.30	-1861.41	10.85
			Max. My	14	-31.30	10.16	-1866.25
			Max. Vy	8	21.64	-1861.41	10.85
			Max. Vx	14	21.68	10.16	-1866.25
			Max. Torque	8			0.87

Maximum Reactions

Location	Condition	Gov. Load Comb.	Vertical K	Horizontal, X K	Horizontal, Z K
Pole	Max. Vert	33	57.09	0.02	-5.23
	Max. H _x	20	31.31	21.58	-0.10
	Max. H _z	2	31.31	-0.14	21.62
	Max. M _x	2	1859.54	-0.14	21.62
	Max. M _z	8	1861.41	-21.62	0.11
	Max. Torsion	8	0.87	-21.62	0.11
	Min. Vert	23	23.48	18.68	10.79
	Min. H _x	8	31.31	-21.62	0.11
	Min. H _z	14	31.31	0.10	-21.66
	Min. M _x	14	-1866.25	0.10	-21.66
	Min. M _z	20	-1854.80	21.58	-0.10
	Min. Torsion	20	-0.80	21.58	-0.10

Tower Mast Reaction Summary

Load Combination	Vertical K	Shear _x K	Shear _z K	Overturing Moment, M _x kip-ft	Overturing Moment, M _z kip-ft	Torque kip-ft
Dead Only	26.09	0.00	0.00	1.20	-0.70	0.00
1.2 Dead+1.0 Wind 0 deg - No Ice	31.31	0.14	-21.62	-1859.54	-17.07	0.14

Load Combination	Vertical K	Shear _x K	Shear _z K	Overturning Moment, M _x kip-ft	Overturning Moment, M _z kip-ft	Torque kip-ft
0.9 Dead+1.0 Wind 0 deg - No Ice	23.48	0.14	-21.62	-1843.07	-16.67	0.15
1.2 Dead+1.0 Wind 30 deg - No Ice	31.31	10.83	-18.76	-1613.78	-932.82	-0.12
0.9 Dead+1.0 Wind 30 deg - No Ice	23.48	10.83	-18.76	-1599.53	-924.14	-0.11
1.2 Dead+1.0 Wind 60 deg - No Ice	31.31	18.71	-10.89	-937.74	-1610.20	-0.52
0.9 Dead+1.0 Wind 60 deg - No Ice	23.48	18.71	-10.89	-929.61	-1595.39	-0.51
1.2 Dead+1.0 Wind 90 deg - No Ice	31.31	21.62	-0.11	-10.85	-1861.41	-0.87
0.9 Dead+1.0 Wind 90 deg - No Ice	23.48	21.62	-0.11	-11.11	-1844.33	-0.87
1.2 Dead+1.0 Wind 120 deg - No Ice	31.31	18.71	10.77	926.80	-1610.90	-0.69
0.9 Dead+1.0 Wind 120 deg - No Ice	23.48	18.71	10.77	918.03	-1596.08	-0.69
1.2 Dead+1.0 Wind 150 deg - No Ice	31.31	10.87	19.09	1636.78	-927.16	-0.05
0.9 Dead+1.0 Wind 150 deg - No Ice	23.48	10.87	19.09	1621.63	-918.58	-0.06
1.2 Dead+1.0 Wind 180 deg - No Ice	31.31	-0.10	21.66	1866.25	10.16	-0.04
0.9 Dead+1.0 Wind 180 deg - No Ice	23.48	-0.10	21.66	1848.98	10.29	-0.05
1.2 Dead+1.0 Wind 210 deg - No Ice	31.31	-10.79	18.77	1617.61	927.06	0.13
0.9 Dead+1.0 Wind 210 deg - No Ice	23.48	-10.79	18.77	1602.58	918.90	0.12
1.2 Dead+1.0 Wind 240 deg - No Ice	31.31	-18.66	10.89	940.31	1603.47	0.40
0.9 Dead+1.0 Wind 240 deg - No Ice	23.48	-18.66	10.89	931.42	1589.19	0.40
1.2 Dead+1.0 Wind 270 deg - No Ice	31.31	-21.58	0.10	12.96	1854.80	0.80
0.9 Dead+1.0 Wind 270 deg - No Ice	23.48	-21.58	0.10	12.46	1838.24	0.80
1.2 Dead+1.0 Wind 300 deg - No Ice	31.31	-18.68	-10.79	-926.60	1605.00	0.50
0.9 Dead+1.0 Wind 300 deg - No Ice	23.48	-18.68	-10.79	-918.57	1590.70	0.50
1.2 Dead+1.0 Wind 330 deg - No Ice	31.31	-10.89	-19.02	-1625.05	927.91	0.23
0.9 Dead+1.0 Wind 330 deg - No Ice	23.48	-10.89	-19.02	-1610.75	919.78	0.24
1.2 Dead+1.0 Ice+1.0 Temp	57.09	0.00	0.00	8.49	-1.66	0.00
1.2 Dead+1.0 Wind 0 deg+1.0 Ice+1.0 Temp	57.09	0.03	-5.22	-468.96	-4.97	0.02
1.2 Dead+1.0 Wind 30 deg+1.0 Ice+1.0 Temp	57.09	2.61	-4.53	-405.75	-240.72	-0.04
1.2 Dead+1.0 Wind 60 deg+1.0 Ice+1.0 Temp	57.09	4.52	-2.63	-232.04	-414.68	-0.12
1.2 Dead+1.0 Wind 90 deg+1.0 Ice+1.0 Temp	57.09	5.22	-0.02	6.02	-478.99	-0.19
1.2 Dead+1.0 Wind 120 deg+1.0 Ice+1.0 Temp	57.09	4.52	2.60	246.27	-414.74	-0.15
1.2 Dead+1.0 Wind 150 deg+1.0 Ice+1.0 Temp	57.09	2.59	4.53	423.75	-237.66	-0.02
1.2 Dead+1.0 Wind 180 deg+1.0 Ice+1.0 Temp	57.09	-0.02	5.23	486.90	0.61	-0.01
1.2 Dead+1.0 Wind 210 deg+1.0 Ice+1.0 Temp	57.09	-2.61	4.53	423.12	236.60	0.04
1.2 Dead+1.0 Wind 240 deg+1.0 Ice+1.0 Temp	57.09	-4.51	2.63	249.14	410.37	0.10
1.2 Dead+1.0 Wind 270 deg+1.0 Ice+1.0 Temp	57.09	-5.21	0.02	10.97	474.70	0.18
1.2 Dead+1.0 Wind 300 deg+1.0 Ice+1.0 Temp	57.09	-4.51	-2.61	-229.69	410.55	0.12

Load Combination	Vertical	Shear _x	Shear _z	Overturning Moment, M _x	Overturning Moment, M _z	Torque
	K	K	K	kip-ft	kip-ft	kip-ft
1.2 Dead+1.0 Wind 330 deg+1.0 Ice+1.0 Temp	57.09	-2.59	-4.52	-404.84	234.81	0.05
Dead+Wind 0 deg - Service	26.09	0.03	-4.69	-400.46	-4.23	0.03
Dead+Wind 30 deg - Service	26.09	2.35	-4.07	-347.41	-201.89	-0.02
Dead+Wind 60 deg - Service	26.09	4.06	-2.36	-201.49	-348.10	-0.11
Dead+Wind 90 deg - Service	26.09	4.69	-0.02	-1.43	-402.32	-0.19
Dead+Wind 120 deg - Service	26.09	4.06	2.34	200.95	-348.25	-0.15
Dead+Wind 150 deg - Service	26.09	2.36	4.14	354.21	-200.67	-0.01
Dead+Wind 180 deg - Service	26.09	-0.02	4.70	403.73	1.65	-0.01
Dead+Wind 210 deg - Service	26.09	-2.34	4.07	350.06	199.56	0.03
Dead+Wind 240 deg - Service	26.09	-4.05	2.36	203.87	345.55	0.09
Dead+Wind 270 deg - Service	26.09	-4.68	0.02	3.71	399.80	0.18
Dead+Wind 300 deg - Service	26.09	-4.05	-2.34	-199.09	345.88	0.11
Dead+Wind 330 deg - Service	26.09	-2.36	-4.13	-349.85	199.74	0.05

Solution Summary

Load Comb.	Sum of Applied Forces			Sum of Reactions			% Error
	PX K	PY K	PZ K	PX K	PY K	PZ K	
1	0.00	-26.09	0.00	0.00	26.09	0.00	0.000%
2	0.14	-31.31	-21.62	-0.14	31.31	21.62	0.000%
3	0.14	-23.48	-21.62	-0.14	23.48	21.62	0.000%
4	10.83	-31.31	-18.76	-10.83	31.31	18.76	0.000%
5	10.83	-23.48	-18.76	-10.83	23.48	18.76	0.000%
6	18.71	-31.31	-10.89	-18.71	31.31	10.89	0.000%
7	18.71	-23.48	-10.89	-18.71	23.48	10.89	0.000%
8	21.62	-31.31	-0.11	-21.62	31.31	0.11	0.000%
9	21.62	-23.48	-0.11	-21.62	23.48	0.11	0.000%
10	18.71	-31.31	10.77	-18.71	31.31	-10.77	0.000%
11	18.71	-23.48	10.77	-18.71	23.48	-10.77	0.000%
12	10.87	-31.31	19.09	-10.87	31.31	-19.09	0.000%
13	10.87	-23.48	19.09	-10.87	23.48	-19.09	0.000%
14	-0.10	-31.31	21.66	0.10	31.31	-21.66	0.000%
15	-0.10	-23.48	21.66	0.10	23.48	-21.66	0.000%
16	-10.79	-31.31	18.77	10.79	31.31	-18.77	0.000%
17	-10.79	-23.48	18.77	10.79	23.48	-18.77	0.000%
18	-18.66	-31.31	10.89	18.66	31.31	-10.89	0.000%
19	-18.66	-23.48	10.89	18.66	23.48	-10.89	0.000%
20	-21.58	-31.31	0.10	21.58	31.31	-0.10	0.000%
21	-21.58	-23.48	0.10	21.58	23.48	-0.10	0.000%
22	-18.68	-31.31	-10.79	18.68	31.31	10.79	0.000%
23	-18.68	-23.48	-10.79	18.68	23.48	10.79	0.000%
24	-10.89	-31.31	-19.02	10.89	31.31	19.02	0.000%
25	-10.89	-23.48	-19.02	10.89	23.48	19.02	0.000%
26	0.00	-57.09	0.00	-0.00	57.09	-0.00	0.000%
27	0.03	-57.09	-5.22	-0.03	57.09	5.22	0.000%
28	2.61	-57.09	-4.53	-2.61	57.09	4.53	0.000%
29	4.52	-57.09	-2.63	-4.52	57.09	2.63	0.000%
30	5.22	-57.09	-0.02	-5.22	57.09	0.02	0.000%
31	4.52	-57.09	2.60	-4.52	57.09	-2.60	0.000%
32	2.59	-57.09	4.53	-2.59	57.09	-4.53	0.000%
33	-0.02	-57.09	5.23	0.02	57.09	-5.23	0.000%
34	-2.61	-57.09	4.53	2.61	57.09	-4.53	0.000%
35	-4.51	-57.09	2.63	4.51	57.09	-2.63	0.000%
36	-5.21	-57.09	0.02	5.21	57.09	-0.02	0.000%
37	-4.51	-57.09	-2.61	4.51	57.09	2.61	0.000%
38	-2.59	-57.09	-4.52	2.59	57.09	4.52	0.000%

Load Comb.	Sum of Applied Forces			Sum of Reactions			% Error
	PX K	PY K	PZ K	PX K	PY K	PZ K	
39	0.03	-26.09	-4.69	-0.03	26.09	4.69	0.000%
40	2.35	-26.09	-4.07	-2.35	26.09	4.07	0.000%
41	4.06	-26.09	-2.36	-4.06	26.09	2.36	0.000%
42	4.69	-26.09	-0.02	-4.69	26.09	0.02	0.000%
43	4.06	-26.09	2.34	-4.06	26.09	-2.34	0.000%
44	2.36	-26.09	4.14	-2.36	26.09	-4.14	0.000%
45	-0.02	-26.09	4.70	0.02	26.09	-4.70	0.000%
46	-2.34	-26.09	4.07	2.34	26.09	-4.07	0.000%
47	-4.05	-26.09	2.36	4.05	26.09	-2.36	0.000%
48	-4.68	-26.09	0.02	4.68	26.09	-0.02	0.000%
49	-4.05	-26.09	-2.34	4.05	26.09	2.34	0.000%
50	-2.36	-26.09	-4.13	2.36	26.09	4.13	0.000%

Non-Linear Convergence Results

Load Combination	Converged?	Number of Cycles	Displacement Tolerance	Force Tolerance
1	Yes	4	0.00000001	0.00000001
2	Yes	4	0.00000001	0.00023526
3	Yes	4	0.00000001	0.00013737
4	Yes	5	0.00000001	0.00025215
5	Yes	5	0.00000001	0.00011541
6	Yes	5	0.00000001	0.00025932
7	Yes	5	0.00000001	0.00011882
8	Yes	4	0.00000001	0.00047122
9	Yes	4	0.00000001	0.00029982
10	Yes	5	0.00000001	0.00024471
11	Yes	5	0.00000001	0.00011179
12	Yes	5	0.00000001	0.00025358
13	Yes	5	0.00000001	0.00011588
14	Yes	4	0.00000001	0.00013477
15	Yes	4	0.00000001	0.00005742
16	Yes	5	0.00000001	0.00025328
17	Yes	5	0.00000001	0.00011603
18	Yes	5	0.00000001	0.00024878
19	Yes	5	0.00000001	0.00011389
20	Yes	4	0.00000001	0.00026814
21	Yes	4	0.00000001	0.00016506
22	Yes	5	0.00000001	0.00025383
23	Yes	5	0.00000001	0.00011672
24	Yes	5	0.00000001	0.00024755
25	Yes	5	0.00000001	0.00011333
26	Yes	4	0.00000001	0.00003113
27	Yes	5	0.00000001	0.00014648
28	Yes	5	0.00000001	0.00016890
29	Yes	5	0.00000001	0.00016985
30	Yes	5	0.00000001	0.00015054
31	Yes	5	0.00000001	0.00017332
32	Yes	5	0.00000001	0.00017400
33	Yes	5	0.00000001	0.00015186
34	Yes	5	0.00000001	0.00017159
35	Yes	5	0.00000001	0.00017065
36	Yes	5	0.00000001	0.00014724
37	Yes	5	0.00000001	0.00016543
38	Yes	5	0.00000001	0.00016473
39	Yes	4	0.00000001	0.00001617
40	Yes	4	0.00000001	0.00007571
41	Yes	4	0.00000001	0.00008258
42	Yes	4	0.00000001	0.00002528
43	Yes	4	0.00000001	0.00007135
44	Yes	4	0.00000001	0.00007826
45	Yes	4	0.00000001	0.00001545
46	Yes	4	0.00000001	0.00007707
47	Yes	4	0.00000001	0.00007272
48	Yes	4	0.00000001	0.00002242
49	Yes	4	0.00000001	0.00007928
50	Yes	4	0.00000001	0.00007229

Maximum Tower Deflections - Service Wind

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
L1	120 - 77.33	12.54	44	0.87	0.00
L2	82 - 34.33	6.05	44	0.69	0.00
L3	40 - 0	1.44	44	0.33	0.00

Critical Deflections and Radius of Curvature - Service Wind

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
115.0000	(2) DB844G65ZAXY	44	11.64	0.85	0.00	53735
109.0000	A-ANT-23G-2-C	44	10.56	0.83	0.00	24425
107.0000	800MHZ RRH	44	10.20	0.82	0.00	20667
105.0000	APXVSPP18-C-A20 w/ Mount Pipe	44	9.85	0.81	0.00	17911
95.0000	MX08FRO665-21 w/ Mount Pipe	44	8.12	0.77	0.00	10747

Maximum Tower Deflections - Design Wind

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
L1	120 - 77.33	57.90	12	4.01	0.01
L2	82 - 34.33	27.98	12	3.20	0.00
L3	40 - 0	6.67	12	1.51	0.00

Critical Deflections and Radius of Curvature - Design Wind

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
115.0000	(2) DB844G65ZAXY	12	53.72	3.93	0.01	11836
109.0000	A-ANT-23G-2-C	12	48.75	3.83	0.01	5379
107.0000	800MHZ RRH	12	47.10	3.79	0.01	4551
105.0000	APXVSPP18-C-A20 w/ Mount Pipe	12	45.47	3.75	0.01	3944
95.0000	MX08FRO665-21 w/ Mount Pipe	12	37.52	3.55	0.01	2365

Compression Checks

Pole Design Data

Section No.	Elevation ft	Size	L ft	L_u ft	KI/r	A in^2	P_u K	ϕP_n K	Ratio $\frac{P_u}{\phi P_n}$
L1	120 - 77.33 (1)	TP30.45x21.91x0.2188	42.670	0.0000	0.0	20.635	-13.59	1207.19	0.011
L2	77.33 - 34.33 (2)	TP38.61x29.0778x0.3125	47.670	0.0000	0.0	37.396	-20.98	2187.67	0.010
L3	34.33 - 0 (3)	TP44.85x36.8512x0.375	40.000	0.0000	0.0	53.703	-31.30	3141.66	0.010

Pole Bending Design Data

Section No.	Elevation ft	Size	M_{ux} kip-ft	ϕM_{nx} kip-ft	Ratio $\frac{M_{ux}}{\phi M_{nx}}$	M_{uy} kip-ft	ϕM_{ny} kip-ft	Ratio $\frac{M_{uy}}{\phi M_{ny}}$
L1	120 - 77.33 (1)	TP30.45x21.91x0.2188	361.69	740.11	0.489	0.00	740.11	0.000

Section No.	Elevation ft	Size	M_{ux} kip-ft	ϕM_{nx} kip-ft	Ratio $\frac{M_{ux}}{\phi M_{nx}}$	M_{uy} kip-ft	ϕM_{ny} kip-ft	Ratio $\frac{M_{uy}}{\phi M_{ny}}$
L2	77.33 - 34.33 (2)	TP38.61x29.0778x0.3125	1065.82	1811.49	0.588	0.00	1811.49	0.000
L3	34.33 - 0 (3)	TP44.85x36.8512x0.375	1881.13	3117.30	0.603	0.00	3117.30	0.000

Pole Shear Design Data

Section No.	Elevation ft	Size	Actual V_u K	ϕV_n K	Ratio $\frac{V_u}{\phi V_n}$	Actual T_u kip-ft	ϕT_n kip-ft	Ratio $\frac{T_u}{\phi T_n}$
L1	120 - 77.33 (1)	TP30.45x21.91x0.2188	14.83	362.16	0.041	0.04	933.28	0.000
L2	77.33 - 34.33 (2)	TP38.61x29.0778x0.3125	18.70	656.30	0.028	0.05	2145.47	0.000
L3	34.33 - 0 (3)	TP44.85x36.8512x0.375	21.99	942.50	0.023	0.05	3687.19	0.000


Pole Interaction Design Data

Section No.	Elevation ft	Ratio P_u	Ratio M_{ux}	Ratio M_{uy}	Ratio V_u	Ratio T_u	Comb. Stress Ratio	Allow. Stress Ratio	Criteria
		ϕP_n	ϕM_{nx}	ϕM_{ny}	ϕV_n	ϕT_n			
L1	120 - 77.33 (1)	0.011	0.489	0.000	0.041	0.000	0.502	1.050	4.8.2
L2	77.33 - 34.33 (2)	0.010	0.588	0.000	0.028	0.000	0.599	1.050	4.8.2
L3	34.33 - 0 (3)	0.010	0.603	0.000	0.023	0.000	0.614	1.050	4.8.2

Section Capacity Table

Section No.	Elevation ft	Component Type	Size	Critical Element	P K	ϕP_{allow} K	% Capacity	Pass Fail	
L1	120 - 77.33	Pole	TP30.45x21.91x0.2188	1	-13.59	1267.55	47.8	Pass	
L2	77.33 - 34.33	Pole	TP38.61x29.0778x0.3125	2	-20.98	2297.05	57.0	Pass	
L3	34.33 - 0	Pole	TP44.85x36.8512x0.375	3	-31.30	3298.74	58.5	Pass	
							Summary		
							Pole (L3)	58.5	Pass
							RATING =	58.5	Pass

APPENDIX B
BASE LEVEL DRAWING



(OTHER CONSIDERED EQUIPMENT)
(14) 1-5/8" TO 115 FT LEVEL

(PROPOSED EQUIPMENT CONFIGURATION)
(1) 1-1/2" TO 95 FT LEVEL

(OTHER CONSIDERED EQUIPMENT)
(4) 1-1/4" TO 105 FT LEVEL

(OTHER CONSIDERED EQUIPMENT--IN CONDUIT)
(4) 5/16" TO 105 FT LEVEL
(OTHER CONSIDERED EQUIPMENT)
(4) 7983A TO 105 FT LEVEL
(2) 5/16" TO 105 FT LEVEL

(OTHER CONSIDERED EQUIPMENT)
(6) 1-5/8" TO 90 FT LEVEL

APPENDIX C
ADDITIONAL CALCULATIONS

Monopole Base Plate Connection




Site Info	
BU #	80654
Site Name	NHV 112 948129
Order #	553355 Rev. 1

Analysis Considerations	
TIA-222 Revision	H
Grout Considered:	Yes
l_{ar} (in)	1.25

Applied Loads	
Moment (kip-ft)	1881.14
Axial Force (kips)	31.30
Shear Force (kips)	21.99

*TIA-222-H Section 15.5 Applied



Connection Properties	Analysis Results
-----------------------	------------------

Anchor Rod Data
(12) 2-1/4" \emptyset bolts (A615-75 N; $F_y=75$ ksi, $F_u=100$ ksi) on 52.97" BC
Base Plate Data
57.16" OD x 2.75" Plate (S-128; $F_y=60$ ksi, $F_u=80$ ksi)
Stiffener Data
N/A
Pole Data
44.85" x 0.375" 12-sided pole (A572-65; $F_y=65$ ksi, $F_u=80$ ksi)

Anchor Rod Summary		(units of kips, kip-in)
$P_{u,t} = 139.34$	$\phi P_{n,t} = 243.75$	Stress Rating
$V_u = 1.83$	$\phi V_n = 149.1$	54.4%
$M_u = n/a$	$\phi M_n = n/a$	Pass
Base Plate Summary		
Max Stress (ksi):	16.56	(Flexural)
Allowable Stress (ksi):	54	
Stress Rating:	29.2%	Pass

Drilled Pier Foundation

BU # :	806454
Site Name:	NHV 112 948129
Order Number:	553355 Rev. 1
TIA-222 Revision:	H
Tower Type:	Monopole



Check Limitation	
Apply TIA-222-H Section 15.5:	<input checked="" type="checkbox"/>
	N/A
Additional Longitudinal Rebar	
Input Effective Depths (else Actual):	<input type="checkbox"/>
Shear Design Options	
Check Shear along Depth of Pier:	<input checked="" type="checkbox"/>
Utilize Shear-Friction Methodology:	<input type="checkbox"/>
Override Critical Depth:	<input type="checkbox"/>

Analysis Results			
Soil Lateral Check		Compression	Uplift
D_{red} (ft from TOC)		14.52	-
Soil Safety Factor		19.46	-
Max Moment (kip-ft)		2108.28	-
Rating*		6.5%	-
Soil Vertical Check		Compression	Uplift
Skin Friction (kips)		592.91	-
End Bearing (kips)		300.00	-
Weight of Concrete (kips)		206.11	-
Total Capacity (kips)		892.91	-
Axial (kips)		237.42	-
Rating*		25.3%	-

Reinforced Concrete Flexure		Compression	Uplift
Critical Depth (ft from TOC)		14.61	-
Critical Moment (kip-ft)		2108.26	-
Critical Moment Capacity		6821.92	-
Rating*		29.4%	-
Reinforced Concrete Shear		Compression	Uplift
Critical Depth (ft from TOC)		44.13	-
Critical Shear (kip)		95.56	-
Critical Shear Capacity		391.39	-
Rating*		23.3%	-

Rebar & Pier Options

Embedded Pole Inputs

Belled Pier Inputs

Pier Design Data	
Depth	59.25 ft
Ext. Above Grade	0.5 ft
Pier Section 1	
<i>From 0.5' above grade to 59.25' below grade</i>	
Pier Diameter	6 ft
Rebar Quantity	36
Rebar Size	11
Clear Cover to Ties	3.5 in
Tie Size	4
Tie Spacing	in

Structural Foundation Rating*	29.4%
Soil Interaction Rating*	25.3%

*Rating per TIA-222-H Section 15.5

Soil Profile	
Groundwater Depth	13
# of Layers	5



Layer	Top (ft)	Bottom (ft)	Thickness (ft)	γ_{soil} (pcf)	$\gamma_{concrete}$ (pcf)	Cohesion (ksf)	Angle of Friction (degrees)	Calculated Ultimate Skin Friction Comp (ksf)	Calculated Ultimate Skin Friction Uplift (ksf)	Ultimate Skin Friction Comp Override (ksf)	Ultimate Skin Friction Uplift Override (ksf)	Ult. Gross Bearing Capacity (ksf)	SPT Blow Count	Soil Type
1	0	3.33	3.33	105	150	0	0	0.000	0.000	0.000	0.000			Cohesionless
2	3.33	12	8.67	105	150	0	25	0.000	0.000	0.75	0.75			Cohesionless
3	12	13	1	110	150	1.25	0	0.688	0.688	0.75	0.75			Cohesive
4	13	42	29	47.6	87.6	1.25	0	0.688	0.688	0.75	0.75			Cohesive
5	42	59.25	17.25	52.6	87.6	2.5	0	1.375	1.375	0.75	0.75	14,147.11		Cohesive

ASCE 7 Hazards Report

Address:
No Address at This
Location

Standard: ASCE/SEI 7-10
Risk Category: II
Soil Class: D - Stiff Soil

Elevation: 33.83 ft (NAVD 88)
Latitude: 41.396369
Longitude: -72.857686



Wind

Results:

Wind Speed:	125 Vmph
10-year MRI	77 Vmph
25-year MRI	87 Vmph
50-year MRI	94 Vmph
100-year MRI	101 Vmph

Data Source: ASCE/SEI 7-10 Fig. 26.5-1A and Figs. CC-1-CC-4, and Section 26.5.2, incorporating errata of March 12, 2014

Value provided is 3-second gust wind speeds at 33 ft above ground for Exposure C Category, based on linear interpolation between contours. Wind speeds are interpolated in accordance with the 7-10 Standard. Wind speeds correspond to approximately a 7% probability of exceedance in 50 years (annual exceedance probability = 0.00143, MRI = 700 years).



Site is in a hurricane-prone region as defined in ASCE/SEI 7-10 Section 26.2. Glazed openings need not be protected against wind-borne debris.

Site Soil Class: D - Stiff Soil

Results:

S_s :	0.184	S_{DS} :	0.196
S_1 :	0.062	S_{D1} :	0.1
F_a :	1.6	T_L :	6
F_v :	2.4	PGA :	0.095
S_{MS} :	0.294	PGA _M :	0.152
S_{M1} :	0.15	F_{PGA} :	1.6
		I_e :	1

Seismic Design Category B



Data Accessed:

Tue May 18 2021

Date Source:

USGS Seismic Design Maps based on ASCE/SEI 7-10, incorporating Supplement 1 and errata of March 31, 2013, and ASCE/SEI 7-10 Table 1.5-2. Additional data for site-specific ground motion procedures in accordance with ASCE/SEI 7-10 Ch. 21 are available from USGS.

Ice

Results:

Ice Thickness: 0.75 in.
Concurrent Temperature: 15 F
Gust Speed: 50 mph

Data Source: Standard ASCE/SEI 7-10, Figs. 10-2 through 10-8

Date Accessed: Tue May 18 2021

Ice thicknesses on structures in exposed locations at elevations higher than the surrounding terrain and in valleys and gorges may exceed the mapped values.

Values provided are equivalent radial ice thicknesses due to freezing rain with concurrent 3-second gust speeds, for a 50-year mean recurrence interval, and temperatures concurrent with ice thicknesses due to freezing rain. Thicknesses for ice accretions caused by other sources shall be obtained from local meteorological studies. Ice thicknesses in exposed locations at elevations higher than the surrounding terrain and in valleys and gorges may exceed the mapped values.

The ASCE 7 Hazard Tool is provided for your convenience, for informational purposes only, and is provided “as is” and without warranties of any kind. The location data included herein has been obtained from information developed, produced, and maintained by third party providers; or has been extrapolated from maps incorporated in the ASCE 7 standard. While ASCE has made every effort to use data obtained from reliable sources or methodologies, ASCE does not make any representations or warranties as to the accuracy, completeness, reliability, currency, or quality of any data provided herein. Any third-party links provided by this Tool should not be construed as an endorsement, affiliation, relationship, or sponsorship of such third-party content by or from ASCE.

ASCE does not intend, nor should anyone interpret, the results provided by this Tool to replace the sound judgment of a competent professional, having knowledge and experience in the appropriate field(s) of practice, nor to substitute for the standard of care required of such professionals in interpreting and applying the contents of this Tool or the ASCE 7 standard.

In using this Tool, you expressly assume all risks associated with your use. Under no circumstances shall ASCE or its officers, directors, employees, members, affiliates, or agents be liable to you or any other person for any direct, indirect, special, incidental, or consequential damages arising from or related to your use of, or reliance on, the Tool or any information obtained therein. To the fullest extent permitted by law, you agree to release and hold harmless ASCE from any and all liability of any nature arising out of or resulting from any use of data provided by the ASCE 7 Hazard Tool.

Exhibit E

Mount Analysis

Date: **July 28, 2021**

Darcy Tarr
Crown Castle
3530 Toringdon Way, Suite 300
Charlotte, NC 28277
(704) 405-6589



Trylon
1825 W. Walnut Hill Lane,
Suite 302
Irving, TX 75038
214-930-1730

Subject: **Mount Replacement Analysis Report**

Carrier Designation: **Dish Network Dish 5G**
Carrier Site Number: BOHVN00011A
Carrier Site Name: CT-CCI-T-806454

Crown Castle Designation: **Crown Castle BU Number:** 806454
Crown Castle Site Name: NHV 112 948129
Crown Castle JDE Job Number: 645112
Crown Castle Order Number: 553355 Rev. 1

Engineering Firm Designation: **Trylon Report Designation:** 189029

Site Data: **117 Washington Avenue, North Haven, New Haven County, CT, 06473**
Latitude 41°23'46.93" Longitude -72°51'27.67"

Structure Information: **Tower Height & Type:** **120.0 ft Monopole**
Mount Elevation: **95.0 ft**
Mount Type: **8.0 ft Platform**

Dear Darcy Tarr,

Trylon is pleased to submit this “**Mount Replacement Analysis Report**” to determine the structural integrity of Dish Network’s antenna mounting system with the proposed appurtenance and equipment addition on the abovementioned supporting tower structure. Analysis of the existing supporting tower structure is to be completed by others and therefore is not part of this analysis. Analysis of the antenna mounting system as a tie-off point for fall protection or rigging is not part of this document.


The purpose of the analysis is to determine acceptability of the mount stress level. Based on our analysis we have determined the mount stress level to be:

Platform **Sufficient***
***Sufficient upon completion of the changes listed in the ‘Recommendations’ section of this report.**

This analysis utilizes an ultimate 3-second gust wind speed of 125 mph as required by the 2018 Connecticut State Building Code. Applicable Standard references and design criteria are listed in Section 2 - Analysis Criteria.

Mount analysis prepared by: Ionela Neamtu

Respectfully Submitted by:
Cliff Abernathy, P.E.



Cliff Abernathy
Digitally signed by Cliff
Abernathy
Date: 2021.07.29 14:51:43 -04'00'

TABLE OF CONTENTS

1) INTRODUCTION

2) ANALYSIS CRITERIA

Table 1 - Proposed Equipment Configuration

3) ANALYSIS PROCEDURE

Table 2 - Documents Provided

3.1) Analysis Method

3.2) Assumptions

4) ANALYSIS RESULTS

Table 3 - Mount Component Stresses vs. Capacity

4.1) Recommendations

5) APPENDIX A

Wire Frame and Rendered Models

6) APPENDIX B

Software Input Calculations

7) APPENDIX C

Software Analysis Output

8) APPENDIX D

Additional Calculations

9) APPENDIX E

Supplemental Drawings

1) INTRODUCTION

This is a proposed 3 sector 8.0 ft Platform, designed by Commscope.

2) ANALYSIS CRITERIA

Building Code:	2015 IBC
TIA-222 Revision:	TIA-222-H
Risk Category:	II
Ultimate Wind Speed:	125 mph
Exposure Category:	B
Topographic Factor at Base:	1.00
Topographic Factor at Mount:	1.00
Ice Thickness:	1.50 in
Wind Speed with Ice:	50 mph
Seismic S_s:	0.184
Seismic S₁:	0.062
Live Loading Wind Speed:	30 mph
Man Live Load at Mid/End-Points:	250 lb
Man Live Load at Mount Pipes:	500 lb

Table 1 - Proposed Equipment Configuration

Mount Centerline (ft)	Antenna Centerline (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Mount / Modification Details
95.0	95.0	3	JMA Wireless	MX08FRO665-21	8.0 ft Platform [Commscope, MC-PK8-C]
		3	Fujitsu	TA08025-B604	
		3	Fujitsu	TA08025-B605	
		1	Raycap	RDIDC-9181-PF-48	

3) ANALYSIS PROCEDURE

Table 2 - Documents Provided

Document	Remarks	Reference	Source
Crown Application	Dish Network Application	553355 Rev. 1	CCI Sites
Mount Manufacturer Drawings	Commscope	MC-PK8-C	Trylon

3.1) Analysis Method

RISA-3D (Version 17.0.4), a commercially available analysis software package, was used to create a three-dimensional model of the antenna mounting system and calculate member stresses for various loading cases.

A tool internally developed, using Microsoft Excel, by Trylon was used to calculate wind loading on all appurtenances, dishes, and mount members for various load cases. Selected output from the analysis is included in Appendix B.

This analysis was performed in accordance with Crown Castle's ENG-SOW-10208 *Tower Mount Analysis* (Revision B).

3.2) Assumptions

- 1) The antenna mounting system was properly fabricated, installed and maintained in good condition in accordance with its original design and manufacturer's specifications.
- 2) The configuration of antennas, mounts, and other appurtenances are as specified in Table 1 and the referenced drawings.
- 3) All member connections are assumed to have been designed to meet or exceed the load carrying capacity of the connected member unless otherwise specified in this report.
- 4) The analysis will be required to be revised if the existing conditions in the field differ from those shown in the above-referenced documents or assumed in this analysis. No allowance was made for any damaged, missing, or rusted members.
- 5) Prior structural modifications to the tower mounting system are assumed to be installed as shown per available data.
- 6) Steel grades have been assumed as follows, unless noted otherwise:

Channel, Solid Round, Angle, Plate	ASTM A36 (GR 36)
HSS (Rectangular)	ASTM A500 (GR B-46)
Pipe	ASTM A53 (GR 35)
Connection Bolts	ASTM A325

This analysis may be affected if any assumptions are not valid or have been made in error. Tylon should be notified to determine the effect on the structural integrity of the antenna mounting system.

4) ANALYSIS RESULTS

Table 3 - Mount Component Stresses vs. Capacity (Platform, All Sectors)

Notes	Component	Critical Member	Centerline (ft)	% Capacity	Pass / Fail
1,2	Mount Pipe(s)	MP1	95.0	27.9	Pass
	Horizontal(s)	H1		10.2	Pass
	Standoff(s)	M2		46.2	Pass
	Bracing(s)	M1		34.6	Pass
	Handrail(s)	M19		11.9	Pass
	Plate(s)	M10		21.0	Pass
	Mount Connection(s)	-		18.7	Pass

Structure Rating (max from all components) =	46.2%
-----------------------------------------------------	--------------

Notes:

- 1) See additional documentation in "Appendix C - Software Analysis Output" for calculations supporting the % capacity consumed.
- 2) Rating per TIA-222-H, Section 15.5



4.1) Recommendations

The mount has sufficient capacity to carry the proposed loading configuration. In order for the results of the analysis to be considered valid, the proposed mount listed below must be installed.

1. Commscope, MC-PK8-C.

No structural modifications are required at this time, provided that the above-listed changes are implemented.

APPENDIX A
WIRE FRAME AND RENDERED MODELS



Envelope Only Solution

Trylon



IN

806454_NHV 112 948129

SK - 1

July 27, 2021 at 4:05 PM

806454_NHV 112 948129.r3d



Envelope Only Solution

Trylon

IN

806454_NHV 112 948129

SK - 2

July 27, 2021 at 4:05 PM

806454_NHV 112 948129.r3d



APPENDIX B
SOFTWARE INPUT CALCULATIONS

ASCE 7 Hazards Report

Address:
No Address at This Location

Standard: ASCE/SEI 7-10
Risk Category: II
Soil Class: D - Stiff Soil

Elevation: 33.83 ft (NAVD 88)
Latitude: 41.396369
Longitude: -72.857686



Wind

Results:

Wind Speed:	125 Vmph
10-year MRI	77 Vmph
25-year MRI	87 Vmph
50-year MRI	94 Vmph
100-year MRI	101 Vmph

Data Source: ASCE/SEI 2010, Fig. 26.5-1A and Figs. CC-1-CC-4, and Section 26.5.2, incorporating errata of March 12, 2014

Value provided is 3-second gust wind speeds at 33 ft above ground for Exposure C Category, based on linear interpolation between contours. Wind speeds are interpolated in accordance with the 7-10 Standard. Wind speeds correspond to approximately a 7% probability of exceedance in 50 years (annual exceedance probability = 0.00143, MRI = 700 years).



Site is in a hurricane-prone region as defined in ASCE/SEI 7-10 Section 26.2. Glazed openings need not be protected against wind-borne debris.

Site Soil Class: D - Stiff Soil

Results:

S_s :	0.184	S_{DS} :	0.196
S_1 :	0.062	S_{D1} :	0.1
F_a :	1.6	T_L :	6
F_v :	2.4	PGA :	0.095
S_{MS} :	0.294	PGA _M :	0.152
S_{M1} :	0.15	F_{PGA} :	1.6
		I_e :	1

Seismic Design Category B



Data Accessed:

Tue Jul 27 2021

Date Source:

USGS Seismic Design Maps based on ASCE/SEI 7-10, incorporating Supplement 1 and errata of March 31, 2013, and ASCE/SEI 7-10 Table 1.5-2. Additional data for site-specific ground motion procedures in accordance with ASCE/SEI 7-10 Ch. 21 are available from USGS.

Ice

Results:

Ice Thickness: 0.75 in.
Concurrent Temperature: 15 F
Gust Speed: 50 mph

Data Source: Standard ASCE/SEI 7-10, Figs. 10-2 through 10-8

Date Accessed: Tue Jul 27 2021

Ice thicknesses on structures in exposed locations at elevations higher than the surrounding terrain and in valleys and gorges may exceed the mapped values.

Values provided are equivalent radial ice thicknesses due to freezing rain with concurrent 3-second gust speeds, for a 50-year mean recurrence interval, and temperatures concurrent with ice thicknesses due to freezing rain. Thicknesses for ice accretions caused by other sources shall be obtained from local meteorological studies. Ice thicknesses in exposed locations at elevations higher than the surrounding terrain and in valleys and gorges may exceed the mapped values.

The ASCE 7 Hazard Tool is provided for your convenience, for informational purposes only, and is provided “as is” and without warranties of any kind. The location data included herein has been obtained from information developed, produced, and maintained by third party providers; or has been extrapolated from maps incorporated in the ASCE 7 standard. While ASCE has made every effort to use data obtained from reliable sources or methodologies, ASCE does not make any representations or warranties as to the accuracy, completeness, reliability, currency, or quality of any data provided herein. Any third-party links provided by this Tool should not be construed as an endorsement, affiliation, relationship, or sponsorship of such third-party content by or from ASCE.

ASCE does not intend, nor should anyone interpret, the results provided by this Tool to replace the sound judgment of a competent professional, having knowledge and experience in the appropriate field(s) of practice, nor to substitute for the standard of care required of such professionals in interpreting and applying the contents of this Tool or the ASCE 7 standard.

In using this Tool, you expressly assume all risks associated with your use. Under no circumstances shall ASCE or its officers, directors, employees, members, affiliates, or agents be liable to you or any other person for any direct, indirect, special, incidental, or consequential damages arising from or related to your use of, or reliance on, the Tool or any information obtained therein. To the fullest extent permitted by law, you agree to release and hold harmless ASCE from any and all liability of any nature arising out of or resulting from any use of data provided by the ASCE 7 Hazard Tool.



TIA LOAD CALCULATOR 2.0

PROJECT DATA		
Job Code:	189029	
Carrier Site ID:	BOHVN00011A	
Carrier Site Name:	CT-CCI-T-806454	

CODES AND STANDARDS		
Building Code:	2015 IBC	
Local Building Code:	Connecticut State Building	
Design Standard:	TIA-222-H	

STRUCTURE DETAILS		
Mount Type:	Platform	--
Mount Elevation:	95.0	ft.
Number of Sectors:	3	--
Structure Type:	Monopole	--
Structure Height:	120.0	ft.

ANALYSIS CRITERIA		
Structure Risk Category:	II	--
Exposure Category:	B	--
Site Class:	D - Stiff Soil	--
Ground Elevation:	33.83	ft.

TOPOGRAPHIC DATA		
Topographic Category:	1.00	--
Topographic Feature:	N/A	--
Crest Point Elevation:	0.00	ft.
Base Point Elevation:	0.00	ft.
Crest to Mid-Height (L/2):	0.00	ft.
Distance from Crest (x):	0.00	ft.
Base Topo Factor (K_{zt}):	1.00	--
Mount Topo Factor (K_{zt}):	1.00	--

WIND PARAMETERS		
Design Wind Speed:	125	mph
Wind Escalation Factor (K_s):	1.00	--
Velocity Coefficient (K_z):	0.97	--
Directionality Factor (K_d):	0.95	--
Gust Effect Factor (G_h):	1.00	--
Shielding Factor (K_a):	0.90	--
Velocity Pressure (q_z):	36.96	psf

ICE PARAMETERS		
Design Ice Wind Speed:	50	mph
Design Ice Thickness (t_i):	1.50	in
Importance Factor (I_i):	1.00	--
Ice Velocity Pressure (q_{zi}):	36.96	psf
Mount Ice Thickness (t_{iz}):	1.67	in

WIND STRUCTURE CALCULATIONS		
Flat Member Pressure:	66.53	psf
Round Member Pressure:	39.92	psf
Ice Wind Pressure:	7.29	psf

SEISMIC PARAMETERS		
Importance Factor (I_e):	1.00	--
Short Period Accel. (S_s):	0.184	g
1 Second Accel (S_1):	0.062	g
Short Period Des. (S_{DS}):	0.20	g
1 Second Des. (S_{D1}):	0.10	g
Short Period Coeff. (F_a):	1.60	--
1 Second Coeff. (F_v):	2.40	--
Response Coefficient (C_s):	0.10	--
Amplification Factor (A_S):	1.20	--

LOAD COMBINATIONS [LRFD]

#	Description
1	1.4DL
2	1.2DL + 1WL 0 AZI
3	1.2DL + 1WL 30 AZI
4	1.2DL + 1WL 45 AZI
5	1.2DL + 1WL 60 AZI
6	1.2DL + 1WL 90 AZI
7	1.2DL + 1WL 120 AZI
8	1.2DL + 1WL 135 AZI
9	1.2DL + 1WL 150 AZI
10	1.2DL + 1WL 180 AZI
11	1.2DL + 1WL 210 AZI
12	1.2DL + 1WL 225 AZI
13	1.2DL + 1WL 240 AZI
14	1.2DL + 1WL 270 AZI
15	1.2DL + 1WL 300 AZI
16	1.2DL + 1WL 315 AZI
17	1.2DL + 1WL 330 AZI
18	0.9DL + 1WL 0 AZI
19	0.9DL + 1WL 30 AZI
20	0.9DL + 1WL 45 AZI
21	0.9DL + 1WL 60 AZI
22	0.9DL + 1WL 90 AZI
23	0.9DL + 1WL 120 AZI
24	0.9DL + 1WL 135 AZI
25	0.9DL + 1WL 150 AZI
26	0.9DL + 1WL 180 AZI
27	0.9DL + 1WL 210 AZI
28	0.9DL + 1WL 225 AZI
29	0.9DL + 1WL 240 AZI
30	0.9DL + 1WL 270 AZI
31	0.9DL + 1WL 300 AZI
32	0.9DL + 1WL 315 AZI
33	0.9DL + 1WL 330 AZI
34	1.2DL + 1DLi + 1WLi 0 AZI
35	1.2DL + 1DLi + 1WLi 30 AZI
36	1.2DL + 1DLi + 1WLi 45 AZI
37	1.2DL + 1DLi + 1WLi 60 AZI
38	1.2DL + 1DLi + 1WLi 90 AZI
39	1.2DL + 1DLi + 1WLi 120 AZI
40	1.2DL + 1DLi + 1WLi 135 AZI
41	1.2DL + 1DLi + 1WLi 150 AZI

#	Description
42	1.2DL + 1DLi + 1WLi 180 AZI
43	1.2DL + 1DLi + 1WLi 210 AZI
44	1.2DL + 1DLi + 1WLi 225 AZI
45	1.2DL + 1DLi + 1WLi 240 AZI
46	1.2DL + 1DLi + 1WLi 270 AZI
47	1.2DL + 1DLi + 1WLi 300 AZI
48	1.2DL + 1DLi + 1WLi 315 AZI
49	1.2DL + 1DLi + 1WLi 330 AZI
50	(1.2+0.2Sds) + 1.0E 0 AZI
51	(1.2+0.2Sds) + 1.0E 30 AZI
52	(1.2+0.2Sds) + 1.0E 45 AZI
53	(1.2+0.2Sds) + 1.0E 60 AZI
54	(1.2+0.2Sds) + 1.0E 90 AZI
55	(1.2+0.2Sds) + 1.0E 120 AZI
56	(1.2+0.2Sds) + 1.0E 135 AZI
57	(1.2+0.2Sds) + 1.0E 150 AZI
58	(1.2+0.2Sds) + 1.0E 180 AZI
59	(1.2+0.2Sds) + 1.0E 210 AZI
60	(1.2+0.2Sds) + 1.0E 225 AZI
61	(1.2+0.2Sds) + 1.0E 240 AZI
62	(1.2+0.2Sds) + 1.0E 270 AZI
63	(1.2+0.2Sds) + 1.0E 300 AZI
64	(1.2+0.2Sds) + 1.0E 315 AZI
65	(1.2+0.2Sds) + 1.0E 330 AZI
66	(0.9-0.2Sds) + 1.0E 0 AZI
67	(0.9-0.2Sds) + 1.0E 30 AZI
68	(0.9-0.2Sds) + 1.0E 45 AZI
69	(0.9-0.2Sds) + 1.0E 60 AZI
70	(0.9-0.2Sds) + 1.0E 90 AZI
71	(0.9-0.2Sds) + 1.0E 120 AZI
72	(0.9-0.2Sds) + 1.0E 135 AZI
73	(0.9-0.2Sds) + 1.0E 150 AZI
74	(0.9-0.2Sds) + 1.0E 180 AZI
75	(0.9-0.2Sds) + 1.0E 210 AZI
76	(0.9-0.2Sds) + 1.0E 225 AZI
77	(0.9-0.2Sds) + 1.0E 240 AZI
78	(0.9-0.2Sds) + 1.0E 270 AZI
79	(0.9-0.2Sds) + 1.0E 300 AZI
80	(0.9-0.2Sds) + 1.0E 315 AZI
81	(0.9-0.2Sds) + 1.0E 330 AZI
82-88	1.2D + 1.5 Lv1

#	Description
89	1.2D + 1.5Lm + 1.0Wm 0 AZI - MP1
90	1.2D + 1.5Lm + 1.0Wm 30 AZI - MP1
91	1.2D + 1.5Lm + 1.0Wm 45 AZI - MP1
92	1.2D + 1.5Lm + 1.0Wm 60 AZI - MP1
93	1.2D + 1.5Lm + 1.0Wm 90 AZI - MP1
94	1.2D + 1.5Lm + 1.0Wm 120 AZI - MP1
95	1.2D + 1.5Lm + 1.0Wm 135 AZI - MP1
96	1.2D + 1.5Lm + 1.0Wm 150 AZI - MP1
97	1.2D + 1.5Lm + 1.0Wm 180 AZI - MP1
98	1.2D + 1.5Lm + 1.0Wm 210 AZI - MP1
99	1.2D + 1.5Lm + 1.0Wm 225 AZI - MP1
100	1.2D + 1.5Lm + 1.0Wm 240 AZI - MP1
101	1.2D + 1.5Lm + 1.0Wm 270 AZI - MP1
102	1.2D + 1.5Lm + 1.0Wm 300 AZI - MP1
103	1.2D + 1.5Lm + 1.0Wm 315 AZI - MP1
104	1.2D + 1.5Lm + 1.0Wm 330 AZI - MP1
105	1.2D + 1.5Lm + 1.0Wm 0 AZI - MP2
106	1.2D + 1.5Lm + 1.0Wm 30 AZI - MP2
107	1.2D + 1.5Lm + 1.0Wm 45 AZI - MP2
108	1.2D + 1.5Lm + 1.0Wm 60 AZI - MP2
109	1.2D + 1.5Lm + 1.0Wm 90 AZI - MP2
110	1.2D + 1.5Lm + 1.0Wm 120 AZI - MP2
111	1.2D + 1.5Lm + 1.0Wm 135 AZI - MP2
112	1.2D + 1.5Lm + 1.0Wm 150 AZI - MP2
113	1.2D + 1.5Lm + 1.0Wm 180 AZI - MP2
114	1.2D + 1.5Lm + 1.0Wm 210 AZI - MP2
115	1.2D + 1.5Lm + 1.0Wm 225 AZI - MP2
116	1.2D + 1.5Lm + 1.0Wm 240 AZI - MP2
117	1.2D + 1.5Lm + 1.0Wm 270 AZI - MP2
118	1.2D + 1.5Lm + 1.0Wm 300 AZI - MP2
119	1.2D + 1.5Lm + 1.0Wm 315 AZI - MP2
120	1.2D + 1.5Lm + 1.0Wm 330 AZI - MP2

#	Description
121	1.2D + 1.5Lm + 1.0Wm 0 AZI - MP3
122	1.2D + 1.5Lm + 1.0Wm 30 AZI - MP3
123	1.2D + 1.5Lm + 1.0Wm 45 AZI - MP3
124	1.2D + 1.5Lm + 1.0Wm 60 AZI - MP3
125	1.2D + 1.5Lm + 1.0Wm 90 AZI - MP3
126	1.2D + 1.5Lm + 1.0Wm 120 AZI - MP3
127	1.2D + 1.5Lm + 1.0Wm 135 AZI - MP3
128	1.2D + 1.5Lm + 1.0Wm 150 AZI - MP3
129	1.2D + 1.5Lm + 1.0Wm 180 AZI - MP3
130	1.2D + 1.5Lm + 1.0Wm 210 AZI - MP3
131	1.2D + 1.5Lm + 1.0Wm 225 AZI - MP3
132	1.2D + 1.5Lm + 1.0Wm 240 AZI - MP3
133	1.2D + 1.5Lm + 1.0Wm 270 AZI - MP3
134	1.2D + 1.5Lm + 1.0Wm 300 AZI - MP3
135	1.2D + 1.5Lm + 1.0Wm 315 AZI - MP3
136	1.2D + 1.5Lm + 1.0Wm 330 AZI - MP3
137	1.2D + 1.5Lm + 1.0Wm 0 AZI - MP4
138	1.2D + 1.5Lm + 1.0Wm 30 AZI - MP4
139	1.2D + 1.5Lm + 1.0Wm 45 AZI - MP4
140	1.2D + 1.5Lm + 1.0Wm 60 AZI - MP4
141	1.2D + 1.5Lm + 1.0Wm 90 AZI - MP4
142	1.2D + 1.5Lm + 1.0Wm 120 AZI - MP4
143	1.2D + 1.5Lm + 1.0Wm 135 AZI - MP4
144	1.2D + 1.5Lm + 1.0Wm 150 AZI - MP4
145	1.2D + 1.5Lm + 1.0Wm 180 AZI - MP4
146	1.2D + 1.5Lm + 1.0Wm 210 AZI - MP4
147	1.2D + 1.5Lm + 1.0Wm 225 AZI - MP4
148	1.2D + 1.5Lm + 1.0Wm 240 AZI - MP4
149	1.2D + 1.5Lm + 1.0Wm 270 AZI - MP4
150	1.2D + 1.5Lm + 1.0Wm 300 AZI - MP4
151	1.2D + 1.5Lm + 1.0Wm 315 AZI - MP4
152	1.2D + 1.5Lm + 1.0Wm 330 AZI - MP4

*This page shows an example of maintenance loads for (4) pipes, the number of mount pipe LCs may vary per site

APPENDIX C
SOFTWARE ANALYSIS OUTPUT

(Global) Model Settings

Display Sections for Member Calcs	5
Max Internal Sections for Member Calcs	97
Include Shear Deformation?	Yes
Increase Nailing Capacity for Wind?	Yes
Include Warping?	Yes
Trans Load Btwn Intersecting Wood Wall?	Yes
Area Load Mesh (in^2)	144
Merge Tolerance (in)	.12
P-Delta Analysis Tolerance	0.50%
Include P-Delta for Walls?	Yes
Automatically Iterate Stiffness for Walls?	Yes
Max Iterations for Wall Stiffness	3
Gravity Acceleration (in/sec^2)	386.4
Wall Mesh Size (in)	24
Eigensolution Convergence Tol. (1.E-)	4
Vertical Axis	Z
Global Member Orientation Plane	XY
Static Solver	Sparse Accelerated
Dynamic Solver	Accelerated Solver

Hot Rolled Steel Code	AISC 15th(360-16): LRFD
Adjust Stiffness?	Yes(Iterative)
RISAC Connection Code	AISC 15th(360-16): LRFD
Cold Formed Steel Code	AISI S100-12: LRFD
Wood Code	None
Wood Temperature	< 100F
Concrete Code	None
Masonry Code	None
Aluminum Code	None - Building
Stainless Steel Code	AISC 14th(360-10): LRFD
Adjust Stiffness?	Yes(Iterative)

Number of Shear Regions	4
Region Spacing Increment (in)	4
Biaxial Column Method	Exact Integration
Parame Beta Factor (PCA)	.65
Concrete Stress Block	Rectangular
Use Cracked Sections?	Yes
Use Cracked Sections Slab?	Yes
Bad Framing Warnings?	No
Unused Force Warnings?	Yes
Min 1 Bar Diam. Spacing?	No
Concrete Rebar Set	REBAR_SET_ASTMA615
Min % Steel for Column	1
Max % Steel for Column	8

(Global) Model Settings, Continued

Seismic Code	ASCE 7-10
Seismic Base Elevation (in)	Not Entered
Add Base Weight?	Yes
Ct X	.02
Ct Z	.02
T X (sec)	Not Entered
T Z (sec)	Not Entered
R X	3
R Z	3
Ct Exp. X	.75
Ct Exp. Z	.75
SD1	1
SDS	1
S1	1
TL (sec)	5
Risk Cat	I or II
Drift Cat	Other
Om Z	1
Om X	1
Cd Z	1
Cd X	1
Rho Z	1
Rho X	1

Hot Rolled Steel Properties

	Label	E [ksi]	G [ksi]	Nu	Them (/...	Density[k/ft^3]	Yield[psi]	Ry	Fu[psi]	Rt
1	A992	29000	11154	.3	.65	.49	50000	1.1	65000	1.1
2	A36 Gr.36	29000	11154	.3	.65	.49	36000	1.5	58000	1.2
3	A572 Gr.50	29000	11154	.3	.65	.49	50000	1.1	65000	1.1
4	A500 Gr.B RND	29000	11154	.3	.65	.527	42000	1.4	58000	1.3
5	A500 Gr.B Rect	29000	11154	.3	.65	.527	46000	1.4	58000	1.3
6	A53 Gr.B	29000	11154	.3	.65	.49	35000	1.6	60000	1.2
7	A1085	29000	11154	.3	.65	.49	50000	1.4	65000	1.3

Cold Formed Steel Properties

	Label	E [ksi]	G [ksi]	Nu	Them (/1E5 F)	Density[k/ft^3]	Yield[psi]	Fu[psi]
1	A653 S S Gr33	29500	11346	.3	.65	.49	33000	45000
2	A653 S S Gr50/1	29500	11346	.3	.65	.49	50000	65000

Hot Rolled Steel Section Sets

	Label	Shape	Type	Design List	Material	Design ...	A [in2]	Iyy [in4]	Izz [in4]	J [in4]
1	Plates	6.5"x0.37" Plate	Beam	RECT	A53 Gr.B	Typical	2.405	.027	8.468	.106
2	Grating Bracing	L2x2x3	Beam	Single Angle	A36 Gr.36	Typical	.722	.271	.271	.009
3	Standoffs	PIPE 3.5	Beam	Pipe	A53 Gr.B	Typical	2.5	4.52	4.52	9.04
4	Standoff Bracing	C3X5	Beam	Channel	A36 Gr.36	Typical	1.47	.241	1.85	.043
5	Handrails	PIPE 2.0	Beam	Pipe	A53 Gr.B	Typical	1.02	.627	.627	1.25
6	Handrail Corners	L6.6"x4.46"x0.25"	Beam	Single Angle	A36 Gr.36	Typical	2.703	4.759	12.473	.055
7	Horizontals	PIPE 3.5	Beam	Pipe	A53 Gr.B	Typical	2.5	4.52	4.52	9.04

Hot Rolled Steel Section Sets (Continued)

	Label	Shape	Type	Design List	Material	Design ...	A [in ²]	I _{yy} [in ⁴]	I _{zz} [in ⁴]	J [in ⁴]
8	Mount Pipes	PIPE 2.0	Beam	Pipe	A53 Gr.B	Typical	1.02	.627	.627	1.25

Cold Formed Steel Section Sets

	Label	Shape	Type	Design List	Material	Design Rules	A [in ²]	I _{yy} [in ⁴]	I _{zz} [in ⁴]	J [in ⁴]
1	CF1A	8CU1.25X057	Beam	None	A653 SS Gr...	Typical	.581	.057	4.41	.00063

Joint Boundary Conditions

	Joint Label	X [k/in]	Y [k/in]	Z [k/in]	X Rot.[k-ft/rad]	Y Rot.[k-ft/rad]	Z Rot.[k-ft/rad]
1	N25	Reaction	Reaction	Reaction	Reaction	Reaction	Reaction
2	N1	Reaction	Reaction	Reaction	Reaction	Reaction	Reaction
3	N13	Reaction	Reaction	Reaction	Reaction	Reaction	Reaction

Basic Load Cases

	BLC Description	Category	X Gravity	Y Gravity	Z Gravity	Joint	Point	Distributed Area (Me...	Surface(...
1	Self Weight	DL			-1		13	3	
2	Structure Wind X	WLX					33		
3	Structure Wind Y	WLY					33		
4	Wind Load 0 AZI	WLX					13		
5	Wind Load 30 AZI	None					26		
6	Wind Load 45 AZI	None					26		
7	Wind Load 60 AZI	None					26		
8	Wind Load 90 AZI	WLY					13		
9	Wind Load 120 AZI	None					26		
10	Wind Load 135 AZI	None					26		
11	Wind Load 150 AZI	None					26		
12	Ice Weight	OL1					13	33	3
13	Structure Ice Wind X	OL2					33		
14	Structure Ice Wind Y	OL3					33		
15	Ice Wind Load 0 AZI	OL2					13		
16	Ice Wind Load 30 AZI	None					26		
17	Ice Wind Load 45 AZI	None					26		
18	Ice Wind Load 60 AZI	None					26		
19	Ice Wind Load 90 AZI	OL3					13		
20	Ice Wind Load 120 AZI	None					26		
21	Ice Wind Load 135 AZI	None					26		
22	Ice Wind Load 150 AZI	None					26		
23	Seismic Load X	ELX	-.118				13		
24	Seismic Load Y	ELY		-.118			13		
25	Live Load 1 (Lv)	LL				1			
26	Live Load 2 (Lv)	LL				1			
27	Live Load 3 (Lv)	LL				1			
28	Live Load 4 (Lv)	LL				1			
29	Live Load 5 (Lv)	LL				1			
30	Live Load 6 (Lv)	LL				1			
31	Maintenance Load 1 (Lm)	None				1			
32	Maintenance Load 2 (Lm)	None				1			
33	Maintenance Load 3 (Lm)	None				1			

Basic Load Cases (Continued)

	BLC Description	Category	X Gravity	Y Gravity	Z Gravity	Joint	Point	Distributed Area (Me... Surface(...
34	Maintenance Load 4 (Lm)	None				1		
35	Maintenance Load 5 (Lm)	None				1		
36	Maintenance Load 6 (Lm)	None				1		
37	Maintenance Load 7 (Lm)	None				1		
38	Maintenance Load 8 (Lm)	None				1		
39	Maintenance Load 9 (Lm)	None				1		
40	BLC 1 Transient Area Loads	None						9
41	BLC 12 Transient Area Loads	None						9

Load Combinations

	Des cription	S... P...	S... B...	Factor	B...	Fac...	B...	Fac...	BLC	Fac...	B...	Fac...	B...	Fac...	B...	Fac...	B...	Fac...
1	1.4DL	Yes	Y	DL	1.4													
2	1.2DL + 1WL 0 AZI	Yes	Y	DL	1.2	2	1	3	4	1								
3	1.2DL + 1WL 30 AZI	Yes	Y	DL	1.2	2	.866	3	.5	5	1							
4	1.2DL + 1WL 45 AZI	Yes	Y	DL	1.2	2	.707	3	.707	6	1							
5	1.2DL + 1WL 60 AZI	Yes	Y	DL	1.2	2	.5	3	.866	7	1							
6	1.2DL + 1WL 90 AZI	Yes	Y	DL	1.2	2		3	1	8	1							
7	1.2DL + 1WL 120 AZI	Yes	Y	DL	1.2	2	-.5	3	.866	9	1							
8	1.2DL + 1WL 135 AZI	Yes	Y	DL	1.2	2	-.707	3	.707	10	1							
9	1.2DL + 1WL 150 AZI	Yes	Y	DL	1.2	2	-.866	3	.5	11	1							
10	1.2DL + 1WL 180 AZI	Yes	Y	DL	1.2	2	-1	3		4	-1							
11	1.2DL + 1WL 210 AZI	Yes	Y	DL	1.2	2	-.866	3	-.5	5	-1							
12	1.2DL + 1WL 225 AZI	Yes	Y	DL	1.2	2	-.707	3	-.707	6	-1							
13	1.2DL + 1WL 240 AZI	Yes	Y	DL	1.2	2	-.5	3	-.866	7	-1							
14	1.2DL + 1WL 270 AZI	Yes	Y	DL	1.2	2		3	-1	8	-1							
15	1.2DL + 1WL 300 AZI	Yes	Y	DL	1.2	2	.5	3	-.866	9	-1							
16	1.2DL + 1WL 315 AZI	Yes	Y	DL	1.2	2	.707	3	-.707	10	-1							
17	1.2DL + 1WL 330 AZI	Yes	Y	DL	1.2	2	.866	3	-.5	11	-1							
18	0.9DL + 1WL 0 AZI	Yes	Y	DL	.9	2	1	3	4	1								
19	0.9DL + 1WL 30 AZI	Yes	Y	DL	.9	2	.866	3	.5	5	1							
20	0.9DL + 1WL 45 AZI	Yes	Y	DL	.9	2	.707	3	.707	6	1							
21	0.9DL + 1WL 60 AZI	Yes	Y	DL	.9	2	.5	3	.866	7	1							
22	0.9DL + 1WL 90 AZI	Yes	Y	DL	.9	2		3	1	8	1							
23	0.9DL + 1WL 120 AZI	Yes	Y	DL	.9	2	-.5	3	.866	9	1							
24	0.9DL + 1WL 135 AZI	Yes	Y	DL	.9	2	-.707	3	.707	10	1							
25	0.9DL + 1WL 150 AZI	Yes	Y	DL	.9	2	-.866	3	.5	11	1							
26	0.9DL + 1WL 180 AZI	Yes	Y	DL	.9	2	-1	3		4	-1							
27	0.9DL + 1WL 210 AZI	Yes	Y	DL	.9	2	-.866	3	-.5	5	-1							
28	0.9DL + 1WL 225 AZI	Yes	Y	DL	.9	2	-.707	3	-.707	6	-1							
29	0.9DL + 1WL 240 AZI	Yes	Y	DL	.9	2	-.5	3	-.866	7	-1							
30	0.9DL + 1WL 270 AZI	Yes	Y	DL	.9	2		3	-1	8	-1							
31	0.9DL + 1WL 300 AZI	Yes	Y	DL	.9	2	.5	3	-.866	9	-1							
32	0.9DL + 1WL 315 AZI	Yes	Y	DL	.9	2	.707	3	-.707	10	-1							
33	0.9DL + 1WL 330 AZI	Yes	Y	DL	.9	2	.866	3	-.5	11	-1							
34	1.2DL + 1DLi + 1WL 0 A...	Yes	Y	DL	1.2	0...	1	13	1	14	15	1						
35	1.2DL + 1DLi + 1WL 30 ...	Yes	Y	DL	1.2	0...	1	13	.866	14	.5	16	1					
36	1.2DL + 1DLi + 1WL 45 ...	Yes	Y	DL	1.2	0...	1	13	.707	14	.707	17	1					
37	1.2DL + 1DLi + 1WL 60 ...	Yes	Y	DL	1.2	0...	1	13	.5	14	.866	18	1					
38	1.2DL + 1DLi + 1WL 90 ...	Yes	Y	DL	1.2	0...	1	13		14	1	19	1					
39	1.2DL + 1DLi + 1WL 12...	Yes	Y	DL	1.2	0...	1	13	-.5	14	.866	20	1					

Load Combinations (Continued)

	Description	S...	P...	S...	B...	Factor	B...	Fac..B...	Fac...BLC	Fac..B...	Fac...B...	Fac..B...	Fac..B...	Fac..B...	Fac..B...	Fac..B...	Fac..B...
92	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	31	1.5	8	.058	2		3	.058			
93	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	31	1.5	9	.058	2	-.029	3	.05			
94	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	31	1.5	10	.058	2	-.041	3	.041			
95	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	31	1.5	11	.058	2	-.05	3	.029			
96	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	31	1.5	4	.058	2	-.058	3				
97	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	31	1.5	5	.058	2	-.05	3	-.029			
98	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	31	1.5	6	.058	2	-.041	3	-.041			
99	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	31	1.5	7	.058	2	-.029	3	-.05			
100	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	31	1.5	8	.058	2		3	-.058			
101	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	31	1.5	9	.058	2	.029	3	-.05			
102	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	31	1.5	10	.058	2	.041	3	-.041			
103	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	31	1.5	11	.058	2	.05	3	-.029			
104	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	32	1.5	4	.058	2	.058	3				
105	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	32	1.5	5	.058	2	.05	3	.029			
106	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	32	1.5	6	.058	2	.041	3	.041			
107	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	32	1.5	7	.058	2	.029	3	.05			
108	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	32	1.5	8	.058	2		3	.058			
109	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	32	1.5	9	.058	2	-.029	3	.05			
110	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	32	1.5	10	.058	2	-.041	3	.041			
111	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	32	1.5	11	.058	2	-.05	3	.029			
112	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	32	1.5	4	.058	2	-.058	3				
113	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	32	1.5	5	.058	2	-.05	3	-.029			
114	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	32	1.5	6	.058	2	-.041	3	-.041			
115	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	32	1.5	7	.058	2	-.029	3	-.05			
116	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	32	1.5	8	.058	2		3	-.058			
117	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	32	1.5	9	.058	2	.029	3	-.05			
118	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	32	1.5	10	.058	2	.041	3	-.041			
119	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	32	1.5	11	.058	2	.05	3	-.029			
120	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	33	1.5	4	.058	2	.058	3				
121	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	33	1.5	5	.058	2	.05	3	.029			
122	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	33	1.5	6	.058	2	.041	3	.041			
123	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	33	1.5	7	.058	2	.029	3	.05			
124	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	33	1.5	8	.058	2		3	.058			
125	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	33	1.5	9	.058	2	-.029	3	.05			
126	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	33	1.5	10	.058	2	-.041	3	.041			
127	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	33	1.5	11	.058	2	-.05	3	.029			
128	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	33	1.5	4	.058	2	-.058	3				
129	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	33	1.5	5	.058	2	-.05	3	-.029			
130	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	33	1.5	6	.058	2	-.041	3	-.041			
131	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	33	1.5	7	.058	2	-.029	3	-.05			
132	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	33	1.5	8	.058	2		3	-.058			
133	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	33	1.5	9	.058	2	.029	3	-.05			
134	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	33	1.5	10	.058	2	.041	3	-.041			
135	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	33	1.5	11	.058	2	.05	3	-.029			
136	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	34	1.5	4	.058	2	.058	3				
137	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	34	1.5	5	.058	2	.05	3	.029			
138	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	34	1.5	6	.058	2	.041	3	.041			
139	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	34	1.5	7	.058	2	.029	3	.05			
140	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	34	1.5	8	.058	2		3	.058			
141	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	34	1.5	9	.058	2	-.029	3	.05			
142	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	34	1.5	10	.058	2	-.041	3	.041			
143	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	34	1.5	11	.058	2	-.05	3	.029			



Company : Trylon
 Designer : IN
 Job Number :
 Model Name : 806454_NHV 112 948129

July 27, 2021
 4:05 PM
 Checked By: CA

Load Combinations (Continued)

	Description	S...	P...	S...	B...	Factor	B...	Fac..B...	Fac...BLC	Fac..B...	Fac..B...	Fac..B...	Fac..B...	Fac..B...	Fac..B...	Fac..B...	Fac..B...
144	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	34	1.5	4	.058	2	-.058	3				
145	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	34	1.5	5	.058	2	-.05	3	-.029			
146	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	34	1.5	6	.058	2	-.041	3	-.041			
147	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	34	1.5	7	.058	2	-.029	3	-.05			
148	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	34	1.5	8	.058	2		3	-.058			
149	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	34	1.5	9	.058	2	.029	3	-.05			
150	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	34	1.5	10	.058	2	.041	3	-.041			
151	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	34	1.5	11	.058	2	.05	3	-.029			
152	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	35	1.5	4	.058	2	.058	3				
153	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	35	1.5	5	.058	2	.05	3	.029			
154	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	35	1.5	6	.058	2	.041	3	.041			
155	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	35	1.5	7	.058	2	.029	3	.05			
156	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	35	1.5	8	.058	2		3	.058			
157	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	35	1.5	9	.058	2	-.029	3	.05			
158	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	35	1.5	10	.058	2	-.041	3	.041			
159	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	35	1.5	11	.058	2	-.05	3	.029			
160	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	35	1.5	4	.058	2	-.058	3				
161	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	35	1.5	5	.058	2	-.05	3	-.029			
162	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	35	1.5	6	.058	2	-.041	3	-.041			
163	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	35	1.5	7	.058	2	-.029	3	-.05			
164	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	35	1.5	8	.058	2		3	-.058			
165	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	35	1.5	9	.058	2	.029	3	-.05			
166	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	35	1.5	10	.058	2	.041	3	-.041			
167	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	35	1.5	11	.058	2	.05	3	-.029			
168	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	36	1.5	4	.058	2	.058	3				
169	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	36	1.5	5	.058	2	.05	3	.029			
170	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	36	1.5	6	.058	2	.041	3	.041			
171	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	36	1.5	7	.058	2	.029	3	.05			
172	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	36	1.5	8	.058	2		3	.058			
173	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	36	1.5	9	.058	2	-.029	3	.05			
174	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	36	1.5	10	.058	2	-.041	3	.041			
175	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	36	1.5	11	.058	2	-.05	3	.029			
176	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	36	1.5	4	.058	2	-.058	3				
177	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	36	1.5	5	.058	2	-.05	3	-.029			
178	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	36	1.5	6	.058	2	-.041	3	-.041			
179	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	36	1.5	7	.058	2	-.029	3	-.05			
180	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	36	1.5	8	.058	2		3	-.058			
181	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	36	1.5	9	.058	2	.029	3	-.05			
182	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	36	1.5	10	.058	2	.041	3	-.041			
183	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	36	1.5	11	.058	2	.05	3	-.029			
184	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	37	1.5	4	.058	2	.058	3				
185	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	37	1.5	5	.058	2	.05	3	.029			
186	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	37	1.5	6	.058	2	.041	3	.041			
187	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	37	1.5	7	.058	2	.029	3	.05			
188	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	37	1.5	8	.058	2		3	.058			
189	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	37	1.5	9	.058	2	-.029	3	.05			
190	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	37	1.5	10	.058	2	-.041	3	.041			
191	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	37	1.5	11	.058	2	-.05	3	.029			
192	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	37	1.5	4	.058	2	-.058	3				
193	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	37	1.5	5	.058	2	-.05	3	-.029			
194	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	37	1.5	6	.058	2	-.041	3	-.041			
195	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	37	1.5	7	.058	2	-.029	3	-.05			

Load Combinations (Continued)

	Description	S...	P...	S...	B...	Factor	B...	Fac..B...	Fac...BLC	Fac..B...	Fac..B...	Fac..B...	Fac..B...	Fac..B...	Fac..B...	Fac..B...
196	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	37	1.5	8	.058	2		3	-.058		
197	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	37	1.5	9	.058	2	.029	3	-.05		
198	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	37	1.5	10	.058	2	.041	3	-.041		
199	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	37	1.5	11	.058	2	.05	3	-.029		
200	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	38	1.5	4	.058	2	.058	3			
201	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	38	1.5	5	.058	2	.05	3	.029		
202	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	38	1.5	6	.058	2	.041	3	.041		
203	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	38	1.5	7	.058	2	.029	3	.05		
204	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	38	1.5	8	.058	2		3	.058		
205	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	38	1.5	9	.058	2	-.029	3	.05		
206	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	38	1.5	10	.058	2	-.041	3	.041		
207	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	38	1.5	11	.058	2	-.05	3	.029		
208	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	38	1.5	4	.058	2	-.058	3			
209	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	38	1.5	5	.058	2	-.05	3	-.029		
210	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	38	1.5	6	.058	2	-.041	3	-.041		
211	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	38	1.5	7	.058	2	-.029	3	-.05		
212	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	38	1.5	8	.058	2		3	-.058		
213	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	38	1.5	9	.058	2	.029	3	-.05		
214	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	38	1.5	10	.058	2	.041	3	-.041		
215	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	38	1.5	11	.058	2	.05	3	-.029		
216	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	39	1.5	4	.058	2	.058	3			
217	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	39	1.5	5	.058	2	.05	3	.029		
218	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	39	1.5	6	.058	2	.041	3	.041		
219	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	39	1.5	7	.058	2	.029	3	.05		
220	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	39	1.5	8	.058	2		3	.058		
221	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	39	1.5	9	.058	2	-.029	3	.05		
222	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	39	1.5	10	.058	2	-.041	3	.041		
223	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	39	1.5	11	.058	2	-.05	3	.029		
224	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	39	1.5	4	.058	2	-.058	3			
225	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	39	1.5	5	.058	2	-.05	3	-.029		
226	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	39	1.5	6	.058	2	-.041	3	-.041		
227	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	39	1.5	7	.058	2	-.029	3	-.05		
228	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	39	1.5	8	.058	2		3	-.058		
229	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	39	1.5	9	.058	2	.029	3	-.05		
230	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	39	1.5	10	.058	2	.041	3	-.041		
231	1.2D + 1.5Lm + 1.0Wm ...	Yes	Y		DL	1.2	39	1.5	11	.058	2	.05	3	-.029		

Envelope Joint Reactions

	Joint		X [lb]	LC	Y [lb]	LC	Z [lb]	LC	MX [lb-ft]	LC	MY [lb-ft]	LC	MZ [lb-ft]	LC
1	N25	max	1208.106	3	799.295	20	1809.69	39	51.552	31	195.058	33	1427.18	19
2		min	-1202.708	27	-803.576	12	83.112	31	-3287.944	39	-1951.229	127	-1430.542	11
3	N1	max	1262.221	17	735.442	8	1859.781	45	3213.564	45	182.179	19	1454.487	25
4		min	-1260.254	25	-728.342	32	92.032	21	-36.04	21	-2193.721	43	-1459.197	17
5	N13	max	341.969	18	1222.358	22	1764.416	34	725.225	192	3639.783	34	1192.249	30
6		min	-349.648	10	-1224.992	14	52.617	26	-612.202	172	-137.548	26	-1195.374	6
7	Totals:	max	2573.249	18	2405.515	6	5226.18	41						
8		min	-2573.249	26	-2405.515	30	1366.261	81						



Envelope AISC 15th(360-16): LRFD Steel Code Checks

Member	Shape	Code Check	Loc[in]	LC	Shea...Loc.....	L...phi*Pn...	phi*Pn...	phi*M...	phi*M...	Eqn					
1	M2	PIPE 3.5	.486	40	45	.163	40	95	64491...78750	7953.75	7953.75	2...	H1-1b		
2	M12	PIPE 3.5	.469	40	39	.157	40	1..	64491...78750	7953.75	7953.75	2...	H1-1b		
3	M7	PIPE 3.5	.458	40	34	.156	40	1..	64491...78750	7953.75	7953.75	2...	H1-1b		
4	M1	C3X5	.364	34.856	45	.131	63....	y	41	32858...47628	981.263	4104	1..	H1-1b	
5	M11	C3X5	.355	34.856	40	.129	63....	y	35	32858...47628	981.263	4104	1..	H1-1b	
6	M6	C3X5	.343	34.856	34	.125	63....	y	46	32858...47628	981.263	4104	1..	H1-1b	
7	MP1	PIPE 2.0	.293	51	15	.035	51	15	20866...32130	1871....	1871....	2...	H1-1b		
8	MP4	PIPE 2.0	.279	51	10	.037	51	11	20866...32130	1871....	1871....	1	H1-1b		
9	MP7	PIPE 2.0	.272	51	3	.030	51	2	20866...32130	1871....	1871....	1	H1-1b		
10	MP3	PIPE 2.0	.270	51	5	.029	51	10	20866...32130	1871....	1871....	1	H1-1b		
11	MP9	PIPE 2.0	.267	51	10	.023	51	3	20866...32130	1871....	1871....	1..	H1-1b		
12	MP2	PIPE 2.0	.264	51	6	.039	51	8	20866...32130	1871....	1871....	1	H1-1b		
13	MP8	PIPE 2.0	.256	51	10	.032	51	11	20866...32130	1871....	1871....	1..	H1-1b		
14	MP5	PIPE 2.0	.240	51	17	.037	51	3	20866...32130	1871....	1871....	2..	H1-1b		
15	MP6	PIPE 2.0	.234	51	16	.025	51	8	20866...32130	1871....	1871....	2..	H1-1b		
16	M10	6.5"x0.37" Plate	.221	21	2	.088	21	y	48	27548...75757.5	583.963	6403....	1..	H1-1b	
17	M15	6.5"x0.37" Plate	.218	21	7	.090	21	y	37	27548...75757.5	583.963	6364....	1..	H1-1b	
18	M5	6.5"x0.37" Plate	.214	21	12	.095	21	y	42	27548...75757.5	583.963	6639....	1..	H1-1b	
19	M13	L2x2x3	.150	0	14	.025	0	z	43	18084.2	23392.8	557.717	1182....	1	H2-1
20	M3	L2x2x3	.141	0	3	.026	0	z	49	18084.2	23392.8	557.717	1182....	1	H2-1
21	M8	L2x2x3	.136	0	10	.025	0	z	38	18084.2	23392.8	557.717	1182....	1	H2-1
22	M19	PIPE 2.0	.125	72	10	.116	72	2	14916...32130	1871....	1871....	1..	H1-1b		
23	M4	L2x2x3	.121	0	13	.028	0	y	42	18084.2	23392.8	557.717	1182....	1	H2-1
24	M20	PIPE 2.0	.115	24	16	.102	72	8	14916...32130	1871....	1871....	1..	H1-1b		
25	M9	L2x2x3	.108	0	2	.027	0	y	47	18084.2	23392.8	557.717	1182....	1	H2-1
26	H1	PIPE 3.5	.108	72	88	.085	24	10	60666...78750	7953.75	7953.75	1	H1-1b		
27	M21	PIPE 2.0	.107	24	5	.102	72	13	14916...32130	1871....	1871....	1..	H1-1b		
28	H3	PIPE 3.5	.105	72	187	.082	24	16	60666...78750	7953.75	7953.75	1	H1-1b		
29	H2	PIPE 3.5	.105	72	143	.076	24	5	60666...78750	7953.75	7953.75	1	H1-1b		
30	M14	L2x2x3	.098	0	7	.028	0	y	36	18084.2	23392.8	557.717	1182....	1	H2-1
31	M22	L6.6"x4.46"x0...	.052	0	21	.029	42	z	4	51170...87561	2464....	7125....	1	H2-1	
32	M23	L6.6"x4.46"x0...	.051	0	26	.030	0	y	9	51170...87561	2464....	7125....	1	H2-1	
33	M24	L6.6"x4.46"x0...	.040	0	32	.026	0	y	14	51170...87561	2464....	7125....	1	H2-1	

Envelope AISI 100-12: LRFD Cold Formed Steel Code Checks

Member	Shape	Code Check	Loc[in]	LC	Shea...Loc[i..Dir	LC	phi*Pn[...phi*Tn[...phi*Mn...phi*Mn...	Cb	Cmy	Cmzz	Eqn
No Data to Print ...											

APPENDIX D
ADDITIONAL CALCUATIONS

BOLT TOOL 1.5.2

Project Data	
Job Code:	-
Carrier Site ID:	BOHVN00011A
Carrier Site Name:	CT-CCI-T-806454


Code	
Design Standard:	TIA-222-H
Slip Check:	No
Pretension Standard:	AISC

Bolt Properties		
Connection Type:	Bolt	
Diameter:	0.625	in
Grade:	A325	--
Yield Strength (Fy):	92	ksi
Ultimate Strength (Fu):	120	ksi
Number of Bolts:	4	--
Threads Included:	No	--
Double Shear:	No	--
Connection Pipe Size:	-	in

Connection Description
Standoff to Monopole

Bolt Check*		
Tensile Capacity (ϕT_n):	20340.1	lbs
Shear Capacity (ϕV_n):	17257.3	lbs
Tension Force (T_u):	3994.4	lbs
Shear Force (V_u):	665.1	lbs
Tension Usage:	18.7%	--
Shear Usage:	3.7%	--
Interaction:	18.7%	Pass
Controlling Member:	M2	--
Controlling LC:	42	--

*Rating per TIA-222-H Section 15.5




APPENDIX E
SUPPLEMENTAL DRAWINGS

ITEM	PART NO.	DESCRIPTION	QTY.	WEIGHT	NOTE NO.
1	MTC3006SB	STEEL BUNDLE FOR SNUB NOSE PLATFORM	1	402.64 LBS	
2	MCPK8CSB	PIPE STEEL BUNDLE FOR MC-PK8-C	1	464.27 LBS	
3	MCPK8CHWK	HARDWARE KIT FOR MC-PK8-C	1	543.22 LBS	



FOR BOM ENTRY ONLY






REV.	ECN	DESCRIPTION	BY	DATE
A		INITIAL RELEASE	DRR	12/27/11
B	8000005979	CHANGE NOSE CORNER BRKT. ADD GUB-4240	MSM	11/25/14
C	8000007579	NEW RINGMOUNT WELDMENT DESIGN	RJC	04/07/15

<p>These drawings are specifications for the assembly property of Andrew Corporation and may be used only for the specific application intended in writing by Andrew Corporation.</p> <p>ALL DIMENSIONS ARE IN INCHES UNLESS OTHERWISE SPECIFIED:</p> <p>X = ± .12 ANGLES ±Z</p> <p>XX = ± .06 FRACTIONS ±1/32</p> <p>XXX = ± .03</p> <p>REMOVE BURRS AND BREAK EDGES 0.05</p> <p>DO NOT SCALE THIS PRINT</p>	<p>REV. BY</p> <p>MSM TP</p> <p>DATE 10/18/11</p> <p>REGION C</p>	<p>REV. BY</p> <p>1 of 3</p> <p>NTS</p> <p>A36, A500</p> <p>GALV. A123</p> <p>1410.14 LBS</p>	<p>REV. BY</p> <p>MC-PK8-C</p> <p>LOW PROFILE PLATFORM KIT 8' FACE</p> <p>ASSEMBLY DRAWING</p>
---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	-------------------------------------------------------------------	-----------------------------------------------------------------------------------------------	------------------------------------------------------------------------------------------------

NOTES:
1. CUSTOMER ASSEMBLY SHEETS 2-3.



ϕ 38 [965.2]
15 [381.0]



NOTES:
1. ALL METRIC DIMENSIONS ARE IN BRACKETS.
2. WILL FIT MONOPOLES 15"-38" OD.

ITEM	PART NO.	DESCRIPTION	QTY.	WEIGHT
1	MC-RM1550-3	12" - 50" OD RINGMOUNT	1	230.42 LBS
2	MTC300601	Low Profile Co-Location Platform Snub Nose	3	134.21 LBS
3	MT1195801	Corner Weldment Snub Nose Handrail	3	27.10 LBS
4	XA2020.01	CROSS OVER ANGLE	9	2.65 LBS
5	GUB-4356	1/2" X 3-5/8" X 6" GALV U-BOLT	18	0.82 LBS
6	GUB-4355	1/2" X 3-5/8" X 5" GALV U-BOLT	12	0.71 LBS
7	GUB-4240	1/2" X 2-1/2" X 4" GALV U-BOLT	48	0.56 LBS
8	GB-04145	1/2" X 1-1/2" GALV BOLT KIT	12	0.13 LBS
9	GW-F-04	1/2" GALV FLAT WASHER	24	0.03 LBS
10	GB-0520A	5/8" X 2" GALV BOLT KIT (A325)	12	0.27 LBS
11	MT154796	3.50" OD X 96" GALV PIPE	3	60.28 LBS
12	MT-651-96	ϕ 2.375" OD X 96" PIPE	3	29.07 LBS
13	MT-651	2.375" OD x 72" PIPE	9	21.80 LBS
14	MT119617	MT196 Pipe Mount Plate	6	2.49 LBS
15	MT21701	PIPE MOUNT PLATE	9	7.93 LBS

These drawings are the property of Andrew Corporation and may be used only for the specific application intended in writing by Andrew Corporation.


ALL DIMENSIONS ARE IN INCHES UNLESS TOLERANCES UNLESS OTHERWISE SPECIFIED:
X = ± .12
XX = ± .06
XXX = ± .03
ANGLES 4/7
FRACTIONS ±1/32
REGION: GALV A123
REVISION: C

DO NOT SCALE THIS PRINT


MSM 2 of 3
NTS
A36, A53
GALV A123
1361.27 LBS

MC-PK8-C
25" OD Snub Nose MT-196
ASSEMBLY DRAWING


WESTCHESTER, IL. 60154
U.S.A.
ANDREW




WITH ANTENNAS



DETAIL A
SCALE 1 : 8



DETAIL C
SCALE 1 : 8



DETAIL B
SCALE 1 : 8

<p>These drawings are specifications on the proprietary property of Andrew Corporation and may be used only for the specific product in which they are used.</p> <p>ALL DIMENSIONS ARE IN INCHES UNLESS OTHERWISE SPECIFIED: X = ± .12 ANGLES ±Z XX = ± .06 FRACTIONS ±1/32 XXX = ± .03 REMOVE BURRS AND BREAK EDGES DGS</p> <p>DO NOT SCALE THIS PRINT</p>	QTY 3 of 3	PART NO. MC-PK8-C
	QTY NTS	QTY A36, A53
	DATE 10/18/11	REGION CALY A123
	WEIGHT 1361.27 LBS	DRAWN BY WESTCHESTER, IL. 60154 U.S.A.

NOTES:
1. ALL METRIC DIMENSIONS ARE IN BRACKETS.



Exhibit F

Power Density/RF Emissions Report

RADIO FREQUENCY EMISSIONS ANALYSIS REPORT
EVALUATION OF HUMAN EXPOSURE POTENTIAL
TO NON-IONIZING EMISSIONS

Dish Wireless Existing Facility

Site ID: BOHVN00011A

806454

117 Washington Avenue
North Haven, Connecticut 06473

September 29, 2021

EBI Project Number: 6221005714

Site Compliance Summary	
Compliance Status:	COMPLIANT
Site total MPE% of FCC general population allowable limit:	31.42%

September 29, 2021

Dish Wireless

Emissions Analysis for Site: BOHVN00011A - 806454

EBI Consulting was directed to analyze the proposed Dish Wireless facility located at **117 Washington Avenue in North Haven, Connecticut** for the purpose of determining whether the emissions from the Proposed Dish Wireless Antenna Installation located on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter ($\mu\text{W}/\text{cm}^2$). The number of $\mu\text{W}/\text{cm}^2$ calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits; therefore, it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) – (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general population may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general population would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

Public exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter ($\mu\text{W}/\text{cm}^2$). The general population exposure limits for the 600 MHz and 700 MHz frequency bands are approximately $400 \mu\text{W}/\text{cm}^2$ and $467 \mu\text{W}/\text{cm}^2$, respectively. The general population exposure limit for the 1900 MHz (PCS), 2100 MHz (AWS) and 11 GHz frequency bands is $1000 \mu\text{W}/\text{cm}^2$. Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.

Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully

aware of the potential for exposure and can exercise control over their exposure. Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

CALCULATIONS

Calculations were done for the proposed Dish Wireless Wireless antenna facility located at 117 Washington Avenue in North Haven, Connecticut using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. Since Dish Wireless is proposing highly focused directional panel antennas, which project most of the emitted energy out toward the horizon, all calculations were performed assuming a lobe representing the maximum gain of the antenna per the antenna manufacturer's supplied specifications, minus 20 dB for directional panel antennas and 20 dB for highly focused parabolic microwave dishes, was focused at the base of the tower. For this report, the sample point is the top of a 6-foot person standing at the base of the tower.

For all calculations, all equipment was calculated using the following assumptions:

- 1) 4 n71 channels (600 MHz Band) were considered for each sector of the proposed installation. These Channels have a transmit power of 30 Watts per Channel.
- 2) 4 n70 channels (PCS Band - 1900 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 40 Watts per Channel.
- 3) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 - Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.
- 4) For the following calculations, the sample point was the top of a 6-foot person standing at the base of the tower. The maximum gain of the antenna per the antenna manufacturer's supplied specifications, minus 20 dB for directional panel antennas and 20 dB for highly focused parabolic microwave dishes, was used in this direction. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.

- 5) The antennas used in this modeling are the JMA MX08FRO665-20 for the 600 MHz / 1900 MHz channel(s) in Sector A, the JMA MX08FRO665-20 for the 600 MHz / 1900 MHz channel(s) in Sector B, the JMA MX08FRO665-20 for the 600 MHz / 1900 MHz channel(s) in Sector C. This is based on feedback from the carrier with regard to anticipated antenna selection. All Antenna gain values and associated transmit power levels are shown in the Site Inventory and Power Data table below. The maximum gain of the antenna per the antenna manufacturer's supplied specifications, minus 20 dB for directional panel antennas and 20 dB for highly focused parabolic microwave dishes, was used for all calculations. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 6) The antenna mounting height centerline of the proposed antennas is 95 feet above ground level (AGL).
- 7) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.
- 8) All calculations were done with respect to uncontrolled / general population threshold limits.

Dish Wireless Site Inventory and Power Data

Sector:	A	Sector:	B	Sector:	C
Antenna #:	I	Antenna #:	I	Antenna #:	I
Make / Model:	JMA MX08FRO665-20	Make / Model:	JMA MX08FRO665-20	Make / Model:	JMA MX08FRO665-20
Frequency Bands:	600 MHz / 1900 MHz	Frequency Bands:	600 MHz / 1900 MHz	Frequency Bands:	600 MHz / 1900 MHz
Gain:	17.45 dBd / 22.65 dBd	Gain:	17.45 dBd / 22.65 dBd	Gain:	17.45 dBd / 22.65 dBd
Height (AGL):	95 feet	Height (AGL):	95 feet	Height (AGL):	95 feet
Channel Count:	8	Channel Count:	8	Channel Count:	8
Total TX Power (W):	280 Watts	Total TX Power (W):	280 Watts	Total TX Power (W):	280 Watts
ERP (W):	3,065.51	ERP (W):	3,065.51	ERP (W):	3,065.51
Antenna AI MPE %:	2.00%	Antenna BI MPE %:	2.00%	Antenna CI MPE %:	2.00%

Site Composite MPE %	
Carrier	MPE %
Dish Wireless (Max at Sector A):	2.00%
Sprint	5.91%
Clearwire	0.19%
Verizon	23.32%
Site Total MPE % :	31.42%

Dish Wireless MPE % Per Sector	
Dish Wireless Sector A Total:	2.00%
Dish Wireless Sector B Total:	2.00%
Dish Wireless Sector C Total:	2.00%
Site Total MPE % :	31.42%

Dish Wireless Maximum MPE Power Values (Sector A)							
Dish Wireless Frequency Band / Technology (Sector A)	# Channels	Watts ERP (Per Channel)	Height (feet)	Total Power Density ($\mu\text{W}/\text{cm}^2$)	Frequency (MHz)	Allowable MPE ($\mu\text{W}/\text{cm}^2$)	Calculated % MPE
Dish Wireless 600 MHz n71	4	223.68	95.0	4.06	600 MHz n71	400	1.02%
Dish Wireless 1900 MHz n70	4	542.70	95.0	9.85	1900 MHz n70	1000	0.99%
						Total:	2.00%

• NOTE: Totals may vary by approximately 0.01% due to summation of remainders in calculations.

Summary

All calculations performed for this analysis yielded results that were **within** the allowable limits for general population exposure to RF Emissions.

The anticipated maximum composite contributions from the Dish Wireless facility as well as the site composite emissions value with regards to compliance with FCC's allowable limits for general population exposure to RF Emissions are shown here:

Dish Wireless Sector	Power Density Value (%)
Sector A:	2.00%
Sector B:	2.00%
Sector C:	2.00%
Dish Wireless Maximum MPE % (Sector A):	2.00%
Site Total:	31.42%
Site Compliance Status:	COMPLIANT

The anticipated composite MPE value for this site assuming all carriers present is **31.42%** of the allowable FCC established general population limit sampled at the ground level. This is based upon values listed in the Connecticut Siting Council database for existing carrier emissions.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.

Exhibit G

Letter of Authorization



4545 E River Rd, Suite 320
West Henrietta, NY 14586

Phone: (585) 445-5896
Fax: (724) 416-4461
www.crowncastle.com

Crown Castle Letter of Authorization

CT - CONNECTICUT SITING COUNCIL

Melanie A. Bachman
Executive Director
Connecticut Siting Council
10 Franklin Square
New Britain, CT 06051

**Re: Tower Share Application
Crown Castle telecommunications site at:
117 WASHINGTON AVENUE, NORTH HAVEN, CT 06473**

CROWN ATLANTIC COMPANY LLC (“Crown Castle”) hereby authorizes DISH Wireless, LLC, including their Agent, to act as our Agent in the processing of all zoning applications, building permits and approvals through the CT - CONNECTICUT SITING COUNCIL for the existing wireless communications site described below:

**Crown Site ID/Name: 806454/NHV 112 948129
Customer Site ID: BOHVN00011A/CT-CCI-T-806454
Site Address: 117 Washington Avenue, NORTH HAVEN, CT 06473**

Crown Castle



By:  _____ Date: 10/4/2021
Richard Zajac
Site Acquisition Specialist

Exhibit H

Recipient Mailings



USPS TRACKING #

9405 5036 9930 0026 4623 00

Electronic Rate Approved #038555749

SHIP

TO: MICHAEL J FRED
FIRST SELECTMAN
5 LINSLEY ST
NORTH HAVEN CT 06473-2505

P

10/07/2021

USPS.com
US POSTAGE
Flat Rate Env

U.S. POSTAGE PAID
click-n-ship®


Mailed from 01566

PRIORITY MAIL 2-DAY™

DEBORAH CHASE
NORTHEAST SITE SOLUTIONS
420 MAIN ST
STE 1
STURBRIDGE MA 01566-1359

Expected Delivery Date: 10/12/21
Ref#: DS-806454
0006

C014



Click-N-Ship®



Cut on dotted line.

Instructions

1. Each Click-N-Ship® label is unique. Labels are to be used as printed and used only once. DO NOT PHOTO COPY OR ALTER LABEL.
2. Place your label so it does not wrap around the edge of the package.
3. Adhere your label to the package. A self-adhesive label is recommended. If tape or glue is used, DO NOT TAPE OVER BARCODE. Be sure all edges are secure.
4. To mail your package with PC Postage®, you may schedule a Package Pickup online, hand to your letter carrier, take to a Post Office™, or drop in a USPS collection box.
5. Mail your package on the "Ship Date" you selected when creating this label.

Click-N-Ship® Label Record

USPS TRACKING # :
9405 5036 9930 0026 4623 00

Trans. #: 545448188	Priority Mail® Postage: \$8.70
Print Date: 10/07/2021	Total: \$8.70
Ship Date: 10/07/2021	
Expected Delivery Date: 10/12/2021	

From: DEBORAH CHASE
NORTHEAST SITE SOLUTIONS
420 MAIN ST
STE 1
STURBRIDGE MA 01566-1359


Ref#: DS-806454

To: MICHAEL J FRED
FIRST SELECTMAN
5 LINSLEY ST
NORTH HAVEN CT 06473-2505

* Retail Pricing Priority Mail rates apply. There is no fee for USPS Tracking® service on Priority Mail service with use of this electronic rate shipping label. Refunds for unused postage paid labels can be requested online 30 days from the print date.



Thank you for shipping with the United States Postal Service!
Check the status of your shipment on the USPS Tracking® page at usps.com



USPS TRACKING #

9405 5036 9930 0026 4623 24

Electronic Rate Approved #038555749

SHIP TO: RICH ZAJAC
CROWN CASTLE
4545 E RIVER RD
STE 320
W HENRIETTA NY 14586-9024

P

10/07/2021

PRIORITY MAIL 2-DAY™

Expected Delivery Date: 10/12/21
Re#: DS-806454
0006

R013

UNITED STATES POSTAL SERVICE®

Click-N-Ship®

usps.com 9405 5036 9930 0026 4623 24 0087 0000 0031 4586

US POSTAGE
Flat Rate Envoy

U.S. POSTAGE PAID
Click-N-Ship®

Mailed from 01566



Cut on dotted line.

Instructions

1. Each Click-N-Ship® label is unique. Labels are to be used as printed and used only once. **DO NOT PHOTO COPY OR ALTER LABEL.**
2. Place your label so it does not wrap around the edge of the package.
3. Adhere your label to the package. A self-adhesive label is recommended. If tape or glue is used, **DO NOT TAPE OVER BARCODE.** Be sure all edges are secure.
4. To mail your package with PC Postage®, you may schedule a Package Pickup online, hand to your letter carrier, take to a Post Office™, or drop in a USPS collection box.
5. Mail your package on the "Ship Date" you selected when creating this label.

Click-N-Ship® Label Record

USPS TRACKING # :
9405 5036 9930 0026 4623 24

Trans. #: 545448188	Priority Mail® Postage: \$8.70
Print Date: 10/07/2021	Total: \$8.70
Ship Date: 10/07/2021	
Expected Delivery Date: 10/12/2021	

From: DEBORAH CHASE
NORTHEAST SITE SOLUTIONS
420 MAIN ST
STE 1
STURBRIDGE MA 01566-1359


Re#: DS-806454

To: RICH ZAJAC
CROWN CASTLE
4545 E RIVER RD
STE 320
W HENRIETTA NY 14586-9024

* Retail Pricing Priority Mail rates apply. There is no fee for USPS Tracking® service on Priority Mail service with use of this electronic rate shipping label. Refunds for unused postage paid labels can be requested online 30 days from the print date.



Thank you for shipping with the United States Postal Service!
Check the status of your shipment on the USPS Tracking® page at usps.com



**UNITED STATES
POSTAL SERVICE®**

Click-N-Ship®

P

10/07/2021

Mailed from 01566

usps.com 9405 5036 9930 0026 4623 48 0087 0000 0010 6473

US POSTAGE

Flat Rate Envoy

U.S. POSTAGE PAID

click-n-ship®

PRIORITY MAIL 2-DAY™


Expected Delivery Date: 10/12/21

Re#: DS-806454

0006

SHIP TO: LAURA MAGARACI
ZONING ENFORCEMENT OFFICER
5 LINSLEY ST
ANNEX BUILDING
NORTH HAVEN CT 06473-2505

USPS TRACKING #



9405 5036 9930 0026 4623 48

Electronic Rate Approved #038555749



Cut on dotted line.

Instructions

1. Each Click-N-Ship® label is unique. Labels are to be used as printed and used only once. DO NOT PHOTO COPY OR ALTER LABEL.
2. Place your label so it does not wrap around the edge of the package.
3. Adhere your label to the package. A self-adhesive label is recommended. If tape or glue is used, DO NOT TAPE OVER BARCODE. Be sure all edges are secure.
4. To mail your package with PC Postage®, you may schedule a Package Pickup online, hand to your letter carrier, take to a Post Office™, or drop in a USPS collection box.
5. Mail your package on the "Ship Date" you selected when creating this label.

Click-N-Ship® Label Record

USPS TRACKING # :
9405 5036 9930 0026 4623 48

Trans. #: 545448188	Priority Mail® Postage: \$8.70
Print Date: 10/07/2021	Total: \$8.70
Ship Date: 10/07/2021	
Expected Delivery Date: 10/12/2021	

From: DEBORAH CHASE
NORTHEAST SITE SOLUTIONS
420 MAIN ST
STE 1
STURBRIDGE MA 01566-1359


Re#: DS-806454

To: LAURA MAGARACI
ZONING ENFORCEMENT OFFICER
5 LINSLEY ST
ANNEX BUILDING
NORTH HAVEN CT 06473-2505

* Retail Pricing Priority Mail rates apply. There is no fee for USPS Tracking® service on Priority Mail service with use of this electronic rate shipping label. Refunds for unused postage paid labels can be requested online 30 days from the print date.



Thank you for shipping with the United States Postal Service!
Check the status of your shipment on the USPS Tracking® page at usps.com



USPS TRACKING #

9405 5036 9930 0026 4623 55

Electronic Rate Approved #038555749

SHIP TO: JOSEPH MORUZZI
COMMERCIAL INVESTMENT GROUP LLC
2911 DIXWELL AVE
HAMDEN CT 06518-3195

SHIP TO: DEBORAH CHASE
NORTHEAST SITE SOLUTIONS
420 MAIN ST
STE 1
STURBRIDGE MA 01566-1359

C052

P

PRIORITY MAIL 2-DAY™

Expected Delivery Date: 10/12/21
Re#: DS-806454
0006

Mailed from 01566

UNITED STATES POSTAL SERVICE®

Click-N-Ship®

usps.com 9405 5036 9930 0026 4623 55 0087 0000 0010 6618
US POSTAGE \$8.70
Flat Rate Envoy

U.S. POSTAGE PAID
click-n-ship®

10/07/2021



Cut on dotted line.

Instructions

1. Each Click-N-Ship® label is unique. Labels are to be used as printed and used only once. DO NOT PHOTO COPY OR ALTER LABEL.
2. Place your label so it does not wrap around the edge of the package.
3. Adhere your label to the package. A self-adhesive label is recommended. If tape or glue is used, DO NOT TAPE OVER BARCODE. Be sure all edges are secure.
4. To mail your package with PC Postage®, you may schedule a Package Pickup online, hand to your letter carrier, take to a Post Office™, or drop in a USPS collection box.
5. Mail your package on the "Ship Date" you selected when creating this label.

Click-N-Ship® Label Record

USPS TRACKING # :
9405 5036 9930 0026 4623 55

Trans. #: 545448188	Priority Mail® Postage: \$8.70
Print Date: 10/07/2021	Total: \$8.70
Ship Date: 10/07/2021	
Expected Delivery Date: 10/12/2021	

From: DEBORAH CHASE
NORTHEAST SITE SOLUTIONS
420 MAIN ST
STE 1
STURBRIDGE MA 01566-1359

Re#: DS-806454

To: JOSEPH MORUZZI
COMMERCIAL INVESTMENT GROUP LLC
2911 DIXWELL AVE
HAMDEN CT 06518-3195

* Retail Pricing Priority Mail rates apply. There is no fee for USPS Tracking® service on Priority Mail service with use of this electronic rate shipping label. Refunds for unused postage paid labels can be requested online 30 days from the print date.



Thank you for shipping with the United States Postal Service!
Check the status of your shipment on the USPS Tracking® page at usps.com

806454



UNIONVILLE
24 MILL ST
UNIONVILLE, CT 06085-9998
(800)275-8777

10/08/2021 01:37 PM

Product	Qty	Unit Price	Price
---------	-----	------------	-------

Prepaid Mail	1		\$0.00
West Henrietta, NY 14586			
Weight: 0 lb 2.00 oz			
Acceptance Date:			
Fri 10/08/2021			
Tracking #:			
9405 5036 9930 0026 4623 24			

Prepaid Mail	1		\$0.00
North Haven, CT 06473			
Weight: 0 lb 11.60 oz			
Acceptance Date:			
Fri 10/08/2021			
Tracking #:			
9405 5036 9930 0026 4623 00			

Prepaid Mail	1		\$0.00
Hamden, CT 06518			
Weight: 0 lb 11.60 oz			
Acceptance Date:			
Fri 10/08/2021			
Tracking #:			
9405 5036 9930 0026 4623 55			

Prepaid Mail	1		\$0.00
North Haven, CT 06473			
Weight: 0 lb 11.60 oz			
Acceptance Date:			
Fri 10/08/2021			
Tracking #:			
9405 5036 9930 0026 4623 48			

Grand Total:			\$0.00
--------------	--	--	--------

USPS is experiencing unprecedented volume
increases and limited employee
availability due to the impacts of
COVID-19. We appreciate your patience.
