HPC Wireless Services
22 Shelter Rock Lane.
Building C
Danbury, CT, 06810
P.: 203.797.1112

HPC
WIRELESS SERVICES

September 29, 2014

VIA OVERNIGHT COURIER

Connecticut Siting Council
10 Franklin Square
New Britain, Connecticut 06051
Attn: Ms. Melanie Bachmann, Acting Executive Director

Re: Sirius XM HAR032A – exempt modification
10 Willard Road, Norwalk, Connecticut

Dear Ms. Bachmann:

This letter and attachments are submitted on behalf of Sirius XM, f/k/a XM Satellite ("Sirius XM"). Sirius XM is making modifications to certain existing sites throughout the country in order to improve its service to subscribers. Please accept this letter and attachments as notification, pursuant to R.C.S.A. Section 16-50j-73, of construction that constitutes an exempt modification pursuant to R.C.S.A. Section 16-50j-72(b)(2). In compliance with R.C.S.A. Section 16-50j-73, a copy of this letter and attachments is being sent to the President of the Common Council of the City of Norwalk.

Sirius XM plans to modify the existing wireless communications facility owned by AT&T Towers and located at 10 Willard Road in the City of Norwalk (coordinates 41°-07'-41.80" N, 73°-23'-24.80" W). Attached are a compound plan and elevation depicting the planned changes, and documentation of the structural sufficiency of the structure to accommodate the revised antenna configuration. Also included is a power density report reflecting the modification to Sirius XM's operations at the site.

The changes to the facility do not constitute a modification as defined in Connecticut General Statutes ("C.G.S.") Section 16-50i(d) because the general physical characteristics of the facility will not be significantly changed. Rather, the planned changes to the facility fall squarely within those activities explicitly provided for in R.C.S.A. Section 16-50j-72(b)(2).

1. Sirius XM will install one (1) 1.8M VSAT Dish on an in-ground mount with a 5' AGL, at grade; one (1) GPS antenna will be installed on a pipe to pipe mount on an existing cable bridge post, with a center line of 13'6" AGL.

2. The proposed changes will not extend the site boundaries. Sirius XM will replace one cabinet inside the existing shelter. These changes will be within the existing compound and will have no effect on the site boundaries.

3. The proposed changes will not increase the noise level at the existing facility by six decibels or more. The incremental effect of the proposed changes will be negligible.

4. The changes to the facility will not increase the calculated "worst case" power density for the combined operations at the site to a level at or above the applicable standard for uncontrolled environments as calculated for a mixed frequency site. As indicated on the attached report prepared by Sitesafe, Inc., Sirius XM's operations at the site will result in a power density of approximately 0.21% of the applicable standard; the combined site operations will result in a total power density of approximately 27.18%.

Please feel free to contact me by phone at (860) 798-65974 or by e-mail at bgaudet@hpcwireless.com with questions concerning this matter. Thank you for your consideration.

Respectfully yours,

Brian Gaudet

cc: Honorable Douglas Hempstead, President, Common Council for City of Norwalk
AT&T Towers (Tower Owner)