



Filed by:
Kri Pelletier, Property Specialist - SBA Communications
134 Flanders Rd., Suite 125, Westborough, MA 01581
508.251.0720 x 3804 - kpelletier@sbsite.com

October 17, 2017

Melanie A. Bachman
Acting Executive Director
Connecticut Siting Council
Ten Franklin Square
New Britain, CT 06051

Notice of Exempt Modification
292 Plain Hill Road, Norwich, CT
41 34 41.52 N
-72 6 13.23 W
Sprint #: CT23XC501_2.5

Dear Ms. Bachman:

Sprint currently maintains antennas at the 177-foot level of the existing 180-foot Monopole Tower at 292 Plain Hill Road in Norwich, CT. The property is owned by Kelvin and Frances Stott. The Tower is owned by SBA Properties LLC. Sprint now intends to add (3) newer technology cell antennas at the 177-foot level of the tower.

Please note: previous approval was given by the Siting Council on 6/16/14 under EM-SPRINT-104-140528. A Notification of Construction Not Complete was sent 9/15/15. Sprint now intends to resume construction. The proposed full scope of work is as follows:

Remove: N/A

Remove and Replace: N/A

Install:

- (3) RFS APXVTM14-C-120 – Panel Antennas
- (3) Alcatel Lucent TD-RRH8x20-25 RRHS
- (1) 1-1/4" Hybrid Line

Existing Equipment to Remain (Including entitlements):

- (3) RFS APXVSP18-C-A20 – Panel Antennas
- (4) RFS ACU-A20-N RET
- (3) Alcatel Lucent 1900 MHz RRHs
- (3) Alcatel-Lucent 800MHZ RRHs
- (3) Alcatel-Lucent 800 MHz Filters
- (3) 1-1/4" Hybrid Lines
- (1) GPS (at 52')
- (1) ½" line (at 52')



This facility was originally approved by the City of Norwich on 4/28/99 under Site Plan Approval #796. Approval was given for a 180' multi-tenant monopole telecommunications facility and placement of associated equipment. There were no post-construction tower conditions set. This modification complies with all aforementioned conditions.

Please accept this letter as notification pursuant to Regulations of Connecticut State Agencies §16-50j-73, for construction that constitutes an exempt modification pursuant to R.C.S.A. §16.50j-72(b)(2). In accordance with R.C.S.A. § 16.50j-73, a copy of this letter is being sent to the City's Mayor, Debercy Hinchey, and Planner, Deanna Rhodes, as well as to the Property Owner. (Separate notice is not being sent to the tower owner, as it belongs to SBA.)

The planned modifications to the facility fall squarely within those activities explicitly provided for in R.C.S.A. §16.50j-72(b)(2).

1. The proposed modifications will not result in an increase in the height of the existing structure.
2. The proposed modification will not require the extension of the site boundary.
3. The proposed modifications will not increase noise levels at the facility by six decibels or more, or to levels that exceed state and local criteria.
4. The operation of the replacement antennas will not increase radio frequency emissions at the facility to a level at or above the Federal Communications Commission safety standard.
5. The proposed modification will not cause a change or alteration in the physical or environmental characteristics of the site.
6. The existing structure and its foundation can support the proposed loading.

For the foregoing reasons, Sprint respectfully submits that the proposed modifications to the above-referenced telecommunication facility constitute an exempt modifications under R.C.S.A. § 16-50j-72(b)(2).

Sincerely,

Kri Pelletier
Property Specialist
SBA COMMUNICATIONS CORPORATION
134 Flanders Rd., Suite 125
Westborough, MA 01581
508.251.0720 x3804 + T
508.366.2610 + F / 203.446.7700 + C
kpelletier@sbsite.com

Attachments

cc: Debercy Hinchey, Mayor / with attachments
City of Norwich, 23 Union Street, Norwich, CT 06360
Deanna Rhodes, City Planner / with attachments
City of Norwich, 23 Union Street, Norwich, CT 06360
Kelvin and Frances Stott / with attachments
292 Plain Hill Rd., Norwich, CT 06360



POWER DENSITY

SPRINT Site Inventory and Power Data by Antenna

Sector:	A	Sector:	B	Sector:	C
Antenna #:	1	Antenna #:	1	Antenna #:	1
Make / Model:	RFS APXVSPP18-C-A20	Make / Model:	RFS APXVSPP18-C-A20	Make / Model:	RFS APXVSPP18-C-A20
Gain:	13.4 / 15.9 dBd	Gain:	13.4 / 15.9 dBd	Gain:	13.4 / 15.9 dBd
Height (AGL):	171 feet	Height (AGL):	171 feet	Height (AGL):	171 feet
Frequency Bands	850 MHz / 1900 MHz (PCS)	Frequency Bands	850 MHz / 1900 MHz (PCS)	Frequency Bands	850 MHz / 1900 MHz (PCS)
Channel Count	10	Channel Count	10	Channel Count	10
Total TX Power(W):	220 Watts	Total TX Power(W):	220 Watts	Total TX Power(W):	220 Watts
ERP (W):	7,537.38	ERP (W):	7,537.38	ERP (W):	7,537.38
Antenna A1 MPE%	1.13 %	Antenna B1 MPE%	1.13 %	Antenna C1 MPE%	1.13 %
Antenna #:	2	Antenna #:	2	Antenna #:	2
Make / Model:	RFS APXVTM14-C-120	Make / Model:	RFS APXVTM14-C-120	Make / Model:	RFS APXVTM14-C-120
Gain:	15.9 dBd	Gain:	15.9 dBd	Gain:	15.9 dBd
Height (AGL):	171 feet	Height (AGL):	171 feet	Height (AGL):	171 feet
Frequency Bands	2500 MHz (BRS)	Frequency Bands	2500 MHz (BRS)	Frequency Bands	2500 MHz (BRS)
Channel Count	8	Channel Count	8	Channel Count	8
Total TX Power(W):	160 Watts	Total TX Power(W):	160 Watts	Total TX Power(W):	160 Watts
ERP (W):	6,224.72	ERP (W):	6,224.72	ERP (W):	6,224.72
Antenna A2 MPE%	0.82 %	Antenna B2 MPE%	0.82 %	Antenna C2 MPE%	0.82 %

Site Composite MPE%	
Carrier	MPE%
SPRINT – Max per sector	1.95 %
Verizon Wireless	2.56 %
AT&T	1.06 %
Site Total MPE %:	5.57 %

SPRINT Sector A Total:	1.95 %
SPRINT Sector B Total:	1.95 %
SPRINT Sector C Total:	1.95 %
Site Total:	5.57 %

SPRINT_ Max Values per Frequency Band / Technology Per Sector	# Channels	Watts ERP (Per Channel)	Height (feet)	Total Power Density (μW/cm ²)	Frequency (MHz)	Allowable MPE (μW/cm ²)	Calculated % MPE
Sprint 850 MHz CDMA	1	437.55	171	0.58	850 MHz	567	0.11%
Sprint 850 MHz LTE	2	437.55	171	1.16	850 MHz	567	0.20%
Sprint 1900 MHz (PCS) CDMA	5	622.47	171	4.11	1900 MHz (PCS)	1000	0.41%
Sprint 1900 MHz (PCS) LTE	2	1,556.18	171	4.11	1900 MHz (PCS)	1000	0.41%
Sprint 2500 MHz (BRS) LTE	8	778.09	171	8.22	2500 MHz (BRS)	1000	0.82%
Total:						1.95%	1.95%


ORIGIN ID:BBFA (508) 614-0389
RICK WOODS
SBA NETWORK SERVICES INC
134 FLANDERS ROAD
SUITE 125
WESTBOROUGH, MA 01581
UNITED STATES US

SHIP DATE: 17OCT17
ACTWGT: 1.00 LB
CAD: 105843304N/ET3920
BILL SENDER

TO **DEBEREY HINCHEY, MAYOR**
CITY OF NORWICH
23 UNION STREET

NORWICH CT 06360
(508) 251-0720 X 3804 REF: 10-56-92009-6089
INV. DEPT:

549J494FC/104C



J172117091301uv

TRK# 7705 1446 9775
0201

WED - 18 OCT 10:30A
PRIORITY OVERNIGHT

EB SKKA

CT-US **06360**
BDL



After printing this label:

1. Use the 'Print' button on this page to print your label to your laser or inkjet printer.
2. Fold the printed page along the horizontal line.
3. Place label in shipping pouch and affix it to your shipment so that the barcode portion of the label can be read and scanned.

Warning: Use only the printed original label for shipping. Using a photocopy of this label for shipping purposes is fraudulent and could result in additional billing charges, along with the cancellation of your FedEx account number.

Use of this system constitutes your agreement to the service conditions in the current FedEx Service Guide, available on fedex.com. FedEx will not be responsible for any claim in excess of \$100 per package, whether the result of loss, damage, delay, non-delivery, misdelivery, or misinformation, unless you declare a higher value, pay an additional charge, document your actual loss and file a timely claim. Limitations found in the current FedEx Service Guide apply. Your right to recover from FedEx for any loss, including intrinsic value of the package, loss of sales, income interest, profit, attorney's fees, costs, and other forms of damage whether direct, incidental, consequential, or special is limited to the greater of \$100 or the authorized declared value. Recovery cannot exceed actual documented loss. Maximum for items of extraordinary value is \$1,000, e.g. jewelry, precious metals, negotiable instruments and other items listed in our ServiceGuide. Written claims must be filed within strict time limits, see current FedEx Service Guide.

ORIGIN ID:BBFA (508) 614-0389
RICK WOODS
SBA NETWORK SERVICES INC
134 FLANDERS ROAD
SUITE 125
WESTBOROUGH MA 01581
UNITED STATES US


SHIP DATE: 17OCT17
ACTWGT: 1.00 LB
CAD: 10584304NET3920

BILL SENDER

TO DEANNA RHODES, CITY PLANNER
CITY OF NORWICH
23 UNION STREET

NORWICH CT 06360
(508) 251-0720 X 3804 REF: 105692009-6039
INV: DEPT:
PO:

549J494FC104C




J172117091301uv

TRK# 7705 1452 1924
#0201

WED - 18 OCT 10:30A
PRIORITY OVERNIGHT

EB SKKA

06360
CT-US BDL



After printing this label:

1. Use the 'Print' button on this page to print your label to your laser or inkjet printer.
2. Fold the printed page along the horizontal line.
3. Place label in shipping pouch and affix it to your shipment so that the barcode portion of the label can be read and scanned.

Warning: Use only the printed original label for shipping. Using a photocopy of this label for shipping purposes is fraudulent and could result in additional billing charges, along with the cancellation of your FedEx account number.

Use of this system constitutes your agreement to the service conditions in the current FedEx Service Guide, available on fedex.com. FedEx will not be responsible for any claim in excess of \$100 per package, whether the result of loss, damage, delay, non-delivery, misdelivery, or misinformation, unless you declare a higher value, pay an additional charge, document your actual loss and file a timely claim. Limitations found in the current FedEx Service Guide apply. Your right to recover from FedEx for any loss, including intrinsic value of the package, loss of sales, income interest, profit, attorney's fees, costs, and other forms of damage whether direct, incidental, consequential, or special is limited to the greater of \$100 or the authorized declared value. Recovery cannot exceed actual documented loss. Maximum for items of extraordinary value is \$1,000, e.g. jewelry, precious metals, negotiable instruments and other items listed in our ServiceGuide. Written claims must be filed within strict time limits, see current FedEx Service Guide.

ORIGIN ID:BBFA (508) 614-0389
RICK WOODS
SBA NETWORK SERVICES INC
134 FLANDERS ROAD
SUITE 125
WESTBOROUGH, MA 01581
UNITED STATES US

SHIP DATE: 17OCT17
ACTWGT: 1.00 LB
CAD: 105843304/NET3920


BILL SENDER

TO **KELVIN AND FRANCES STOTT**

292 PLAIN HILL RD.

NORWICH CT 06360

(508) 251-0720 X 3804 REF: 10-56-92009-6099
INV. DEPT.
PO.



J172117091301uv

549J4/94FC/104C

TRK# 7705 1453 9570
0201

WED - 18 OCT 10:30A
PRIORITY OVERNIGHT

EB SKKA

06360
CT-US BDL



After printing this label:

1. Use the 'Print' button on this page to print your label to your laser or inkjet printer.
2. Fold the printed page along the horizontal line.
3. Place label in shipping pouch and affix it to your shipment so that the barcode portion of the label can be read and scanned.

Warning: Use only the printed original label for shipping. Using a photocopy of this label for shipping purposes is fraudulent and could result in additional billing charges, along with the cancellation of your FedEx account number.

Use of this system constitutes your agreement to the service conditions in the current FedEx Service Guide, available on fedex.com. FedEx will not be responsible for any claim in excess of \$100 per package, whether the result of loss, damage, delay, non-delivery, misdelivery, or misinformation, unless you declare a higher value, pay an additional charge, document your actual loss and file a timely claim. Limitations found in the current FedEx Service Guide apply. Your right to recover from FedEx for any loss, including intrinsic value of the package, loss of sales, income interest, profit, attorney's fees, costs, and other forms of damage whether direct, incidental, consequential, or special is limited to the greater of \$100 or the authorized declared value. Recovery cannot exceed actual documented loss. Maximum for items of extraordinary value is \$1,000, e.g. jewelry, precious metals, negotiable instruments and other items listed in our ServiceGuide. Written claims must be filed within strict time limits, see current FedEx Service Guide.

292 PLAIN HILL RD

Location 292 PLAIN HILL RD

Mblu 28/ 1/ 13/ /

Acct# 0108670001

Owner STOTT KELVIN H +

Assessment \$410,400

Appraisal \$586,400

PID 10711

Building Count 1

Current Value

Appraisal			
Valuation Year	Improvements	Land	Total
2013	\$201,600	\$384,800	\$586,400
Assessment			
Valuation Year	Improvements	Land	Total
2013	\$141,100	\$269,300	\$410,400

Parcel Addresses

Additional Addresses			
Line Number	Address	City, State Zip	Type
1	292 PLAIN HILL RD		Primary

Owner of Record

Owner STOTT KELVIN H +
STOTT FRANCES S
Address 292 PLAIN HILL RD
NORWICH, CT 06360

Sale Price \$0
Certificate
Book & Page 1691/0144
Sale Date 09/11/2002

Ownership History

Ownership History				
Owner	Sale Price	Certificate	Book & Page	Sale Date
STOTT KELVIN H +			1691/0144	09/11/2002
STOTT KELVIN H	\$0		0572/0155	04/12/1982

Building Information


Building 1 : Section 1

Year Built: 1820
Living Area: 2786
Replacement Cost: \$180,506
Building Percent 66
Good:

Building Photo


Replacement Cost
Less Depreciation: \$119,100

Building Attributes	
Field	Description
Style	Colonial
Model	Residential
Grade:	C
Stories:	2 Stories
Occupancy	1
Exterior Wall 1	Wood Shingle
Exterior Wall 2	
Roof Structure:	Gable/Hip
Roof Cover	Asphalt Shingl
Interior Wall 1	Plastered
Interior Wall 2	
Interior Flr 1	Carpet
Interior Flr 2	Pine/Soft Wood
Heat Fuel	Oil
Heat Type:	Hot Water
AC Type:	None
Total Bedrooms:	6 Bedrooms
Total Bthrms:	2
Total Half Baths:	0
Total Xtra Fixtrs:	
Total Rooms:	10 Rooms
Bath Style:	Average
Kitchen Style:	Average
Fireplace (s)	2
Whirlpool	
park	



(<http://images.vgsi.com/photos/NorwichCTPhotos//\00\01\84\48.jpg>)

Building Layout



Building Sub-Areas (sq ft)		Legend	
Code	Description	Gross Area	Living Area
BAS	First Floor	1498	1498
FUS	Upper Story, Finished	1288	1288
FEP	Porch, Enclosed, Finished	112	0
UAT	Attic, Unfinished	1008	0
UBM	Basement, Unfinished	1008	0
WDK	Deck, Wood	264	0
		5178	2786

Extra Features

Extra Features		Legend
No Data for Extra Features		

Land

Land Use

Use Code 1010
Description Single Family

Land Line Valuation

Size (Acres) 21.99
Frontage 0

Zone R40
Neighborhood 0050
Alt Land Appr Category No

Depth 0
Assessed Value \$269,300
Appraised Value \$384,800

Outbuildings

Outbuildings						Legend
Code	Description	Sub Code	Sub Description	Size	Value	Bldg #
BRN1	Barn 1 St.			4752 S.F.	\$14,300	1
SHD1	Shed			280 S.F.	\$700	1
MLK	Milk House			196 S.F.	\$1,400	1
BRN5	Barn 2 St.			2040 S.F.	\$9,200	1
SHD1	Shed			180 S.F.	\$1,100	1
BRN1	Barn 1 St.			4980 S.F.	\$14,900	1
SHD1	Shed			1368 S.F.	\$3,300	1
BRN1	Barn 1 St.			2016 S.F.	\$6,000	1
FGR1	Garage			900 S.F.	\$7,200	1
SHD5	Shed Comm Mas			200 S.F.	\$5,400	1
SPL4	Pool AG rround			18 DIAMETER	\$1,000	1
FN3	Fence Chain 6'			2000 L.F.	\$18,000	1

Valuation History

Appraisal			
Valuation Year	Improvements	Land	Total
2016	\$201,600	\$384,800	\$586,400
2015	\$183,600	\$175,900	\$359,500
2012	\$188,000	\$534,000	\$722,000

Assessment			
Valuation Year	Improvements	Land	Total
2016	\$141,100	\$269,300	\$410,400
2015	\$128,500	\$45,300	\$173,800
2012	\$133,000	\$90,100	\$223,100

(c) 2014 Vision Government Solutions, Inc. All rights reserved.



RADIO FREQUENCY EMISSIONS ANALYSIS REPORT EVALUATION OF HUMAN EXPOSURE POTENTIAL TO NON-IONIZING EMISSIONS

SPRINT Existing Facility

Site ID: CT23XC501

SBA_Norwich 2
300 Plain Hill Road
Norwich, CT 06360

October 3, 2017

EBI Project Number: 6217004338

Site Compliance Summary	
Compliance Status:	COMPLIANT
Site total MPE% of FCC general population allowable limit:	5.57 %



October 3, 2017

SPRINT

Attn: RF Engineering Manager
1 International Boulevard, Suite 800
Mahwah, NJ 07495

Emissions Analysis for Site: **CT23XC501 – SBA_Norwich 2**

EBI Consulting was directed to analyze the proposed SPRINT facility located at **300 Plain Hill Road, Norwich, CT**, for the purpose of determining whether the emissions from the Proposed SPRINT Antenna Installation located on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter ($\mu\text{W}/\text{cm}^2$). The number of $\mu\text{W}/\text{cm}^2$ calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits, therefore it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) – (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general population may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general population would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

Public exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter ($\mu\text{W}/\text{cm}^2$). The general population exposure limits for the 850 MHz Band is approximately $567 \mu\text{W}/\text{cm}^2$. The general population exposure limit for the 1900 MHz (PCS) and 2500 MHz (BRS) bands is $1000 \mu\text{W}/\text{cm}^2$. Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.



Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure. Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

CALCULATIONS

Calculations were done for the proposed SPRINT Wireless antenna facility located at **300 Plain Hill Road, Norwich, CT**, using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. Since SPRINT is proposing highly focused directional panel antennas, which project most of the emitted energy out toward the horizon, all calculations were performed assuming a lobe representing the maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was focused at the base of the tower. For this report the sample point is the top of a 6-foot person standing at the base of the tower.

For all calculations, all equipment was calculated using the following assumptions:

- 1) 1 CDMA channels (850 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 20 Watts per Channel.
- 2) 2 LTE channels (850 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 20 Watts per Channel.
- 3) 5 CDMA channels (1900 MHz (PCS)) were considered for each sector of the proposed installation. These Channels have a transmit power of 16 Watts per Channel.
- 4) 2 LTE channels (1900 MHz (PCS)) were considered for each sector of the proposed installation. These Channels have a transmit power of 40 Watts per Channel.
- 5) 8 LTE channels (2500 MHz (BRS)) were considered for each sector of the proposed installation. These Channels have a transmit power of 20 Watts per Channel.



- 6) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 - Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.
- 7) For the following calculations, the sample point was the top of a 6-foot person standing at the base of the tower. The maximum gain of the antenna per the antenna manufactures supplied specifications minus 10 dB was used in this direction. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 8) The antennas used in this modeling are the **RFS APXVSP18-C-A20** and the **RFS APXVTM14-C-120** for transmission in the 850 MHz, 1900 MHz (PCS) and 2500 MHz (BRS) frequency bands. This is based on feedback from the carrier with regards to anticipated antenna selection. Maximum gain values for all antennas are listed in the Inventory and Power Data table below. The maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was used for all calculations. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 9) The antenna mounting height centerlines of the proposed antennas are **171 feet** above ground level (AGL) for **Sector A**, **171 feet** above ground level (AGL) for **Sector B** and **171 feet** above ground level (AGL) for Sector C.
- 10) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.

All calculations were done with respect to uncontrolled / general population threshold limits.



SPRINT Site Inventory and Power Data by Antenna

Sector:	A	Sector:	B	Sector:	C
Antenna #:	1	Antenna #:	1	Antenna #:	1
Make / Model:	RFS APXVSPPI8-C-A20	Make / Model:	RFS APXVSPPI8-C-A20	Make / Model:	RFS APXVSPPI8-C-A20
Gain:	13.4 / 15.9 dBd	Gain:	13.4 / 15.9 dBd	Gain:	13.4 / 15.9 dBd
Height (AGL):	171 feet	Height (AGL):	171 feet	Height (AGL):	171 feet
Frequency Bands	850 MHz / 1900 MHz (PCS)	Frequency Bands	850 MHz / 1900 MHz (PCS)	Frequency Bands	850 MHz / 1900 MHz (PCS)
Channel Count	10	Channel Count	10	Channel Count	10
Total TX Power(W):	220 Watts	Total TX Power(W):	220 Watts	Total TX Power(W):	220 Watts
ERP (W):	7,537.38	ERP (W):	7,537.38	ERP (W):	7,537.38
Antenna A1 MPE%	1.13 %	Antenna B1 MPE%	1.13 %	Antenna C1 MPE%	1.13 %
Antenna #:	2	Antenna #:	2	Antenna #:	2
Make / Model:	RFS APXVTM14-C-120	Make / Model:	RFS APXVTM14-C-120	Make / Model:	RFS APXVTM14-C-120
Gain:	15.9 dBd	Gain:	15.9 dBd	Gain:	15.9 dBd
Height (AGL):	171 feet	Height (AGL):	171 feet	Height (AGL):	171 feet
Frequency Bands	2500 MHz (BRS)	Frequency Bands	2500 MHz (BRS)	Frequency Bands	2500 MHz (BRS)
Channel Count	8	Channel Count	8	Channel Count	8
Total TX Power(W):	160 Watts	Total TX Power(W):	160 Watts	Total TX Power(W):	160 Watts
ERP (W):	6,224.72	ERP (W):	6,224.72	ERP (W):	6,224.72
Antenna A2 MPE%	0.82 %	Antenna B2 MPE%	0.82 %	Antenna C2 MPE%	0.82 %

Site Composite MPE%	
Carrier	MPE%
SPRINT – Max per sector	1.95 %
Verizon Wireless	2.56 %
AT&T	1.06 %
Site Total MPE %:	5.57 %

SPRINT Sector A Total:	1.95 %
SPRINT Sector B Total:	1.95 %
SPRINT Sector C Total:	1.95 %
Site Total:	5.57 %

SPRINT _ Max Values per Frequency Band / Technology Per Sector	# Channels	Watts ERP (Per Channel)	Height (feet)	Total Power Density ($\mu\text{W}/\text{cm}^2$)	Frequency (MHz)	Allowable MPE ($\mu\text{W}/\text{cm}^2$)	Calculated % MPE
Sprint 850 MHz CDMA	1	437.55	171	0.58	850 MHz	567	0.11%
Sprint 850 MHz LTE	2	437.55	171	1.16	850 MHz	567	0.20%
Sprint 1900 MHz (PCS) CDMA	5	622.47	171	4.11	1900 MHz (PCS)	1000	0.41%
Sprint 1900 MHz (PCS) LTE	2	1,556.18	171	4.11	1900 MHz (PCS)	1000	0.41%
Sprint 2500 MHz (BRS) LTE	8	778.09	171	8.22	2500 MHz (BRS)	1000	0.82%
						Total:	1.95%



Summary

All calculations performed for this analysis yielded results that were **within** the allowable limits for general population exposure to RF Emissions.

The anticipated maximum composite contributions from the SPRINT facility as well as the site composite emissions value with regards to compliance with FCC's allowable limits for general population exposure to RF Emissions are shown here:

SPRINT Sector	Power Density Value (%)
Sector A:	1.95 %
Sector B:	1.95 %
Sector C:	1.95 %
SPRINT Maximum Total (per sector):	1.95 %
Site Total:	5.57 %
Site Compliance Status:	COMPLIANT

The anticipated composite MPE value for this site assuming all carriers present is **5.57 %** of the allowable FCC established general population limit sampled at the ground level. This is based upon values listed in the Connecticut Siting Council database for existing carrier emissions.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.



Tower Engineering Solutions

Phone (972) 483-0607, Fax (972) 975-9615
8445 Freeport Parkway, Suite 375, Irving, Texas 75063

Structural Analysis Report

Existing 180 ft Monopole

Customer Name: SBA Communications Corp

Customer Site Number: CT01365-S

Customer Site Name: Norwich 2 CT

Carrier Name: Sprint Nextel

Carrier Site ID / Name: CT23XC501 / Norwich 2 CT

Site Location: 292 Plain Hill Road

Norwich, Connecticut

New London County

Latitude: 41.578199

Longitude: -72.103675

Analysis Result:

Max Structural Usage: 84.0% [Pass]

Max Foundation Usage: 86% [Pass]

Report Prepared By : Jie Chen



10/13/17

Introduction

The purpose of this report is to summarize the analysis results on the 180 ft Monopole to support the proposed antennas and transmission lines in addition to those currently installed. Any modification listed under Sources of Information was assumed completed and was included in this analysis.

Sources of Information

Tower Drawings	Tower Design prepared by Valmont, job # 18407-99, dated 06/03/1999
Foundation Drawing	Foundation Design prepared by Valmont, job # 18407-99, dated 06/03/1999
Geotechnical Report	Geotechnical Report prepared by FDH, job # 1207121EG1, dated 08/13/2012
Modification Drawings	Modification Design prepared by FDH, job # 1316541400, dated 03/14/13

Analysis Criteria

The rigorous analysis was performed in accordance with the requirements and stipulations of the ANSI/TIA/EIA 222-G. In accordance with this standard, the structure was analyzed using **TESPoles**, a proprietary analysis software. The program considers the structure as an elastic 3-D model with second-order effects and temperature effects incorporated in the analysis. The analysis was performed using multiple wind directions.

Wind Speed Used in the Analysis:	Ultimate Design Wind Speed $V_{ult} = 136.0$ mph (3-Sec. Gust)/ Nominal Design Wind Speed $V_{asd} = 105.0$ mph (3-Sec. Gust)
Wind Speed with Ice:	50 mph (3-Sec. Gust) with 3/4" radial ice concurrent
Operational Wind Speed:	60 mph + 0" Radial ice
Standard/Codes:	ANSI/TIA/EIA 222-G / 2012 IBC / 2016 Connecticut State Building Code
Exposure Category:	C
Structure Class:	II
Topographic Category:	1
Crest Height:	0 ft
Seismic Parameters:	$S_S = 0.17, S_1 = 0.061$

Existing Antennas, Mounts and Transmission Lines

The table below summarizes the antennas, mounts and transmission lines that were considered in the analysis as existing on the tower.

Items	Elevation (ft)	Qty.	Antenna Descriptions	Mount Type & Qty.	Transmission Lines	Owner
-	177.0	3	RFS APXVSP18-C-A20 - Panel	Platform w/ Hand Rails	(4) 1 1/4" Hybrid	Sprint Nextel
-		3	RFS APXVTM14-C-120 - Panel			
-		4	RFS ACU-A20-N RET			
-		3	Alcatel Lucent 1900 MHz RRH			
-		3	Alcatel-Lucent 800MHZ RRH			
-		3	Alcatel Lucent TD-RRH8x20-25			
-		3	Alcatel-Lucent 800 MHz Filter			
8	159.0	3	Antel - BXA-80080/4CF - Panel	Low Profile Platform	(11) 1 5/8" (2) 1 5/8" Fiber	Verizon
9		3	Antel - BXA-171085-8BF-EDIN-2 - Panel			
10		2	RFS - DB-T1-6Z-8AB-0Z - ODU			
11		6	Commscope - SBNHH-1D65B - Panel			
12		3	Alcatel Lucent - B25 RRH4X30 - RRH			
13		3	Alcatel Lucent - B25 RRH4X30 - RRH			
14		3	Alcatel Lucent - RRH 4X45-PCS - RRH			
15	147.0	1	CCI Antennas - HPA-65R-BUU-H6 - Panel	Low Profile Platform	(1) 1/2" Fiber (12) 1 5/8" (2) 3/4" DC	AT&T
16		2	Cci Antennas - HPA-65R-BUU-H8 - Panel			
17		3	Ericsson - RRUS 12 - RRU			
18		3	Ericsson - RRUS A2 - RRU			
19		6	Powerwave Technologies - 7770 - Panel			
20		6	Powerwave Technologies - LGP21401 - TMA			
21		12	Kathrein - 860 10025 RET - RET			
22		6	Ericsson - RRUS 11 - RRU			
23		6	Powerwave - LGP21901 Diplexer - Diplexer			
24		1	Raycap - DC6-48-60-18-8F ("Squid") - DC Surge Suppression System			
-	52.0	1	GPS	-	(1) 1/2"	Sprint Nextel

Proposed Carrier’s Final Configuration of Antennas, Mounts and Transmission Lines

Information pertaining to the proposed carrier’s final configuration of antennas and transmission lines was provided by SBA Communications Corp. The proposed antennas and lines are listed below.

Items	Elevation (ft)	Qty.	Antenna Descriptions	Mount Type & Qty.	Transmission Lines	Owner
1	177.0	3	RFS APXVSP18-C-A20 - Panel	Platform w/ Hand Rail	(4) 1 1/4" Hybrid	Sprint Nextel
2		3	RFS APXVTM14-C-120 - Panel			
3		4	RFS ACU-A20-N RET			
4		3	Alcatel Lucent 1900 MHz RRH			
5		3	Alcatel-Lucent 800MHZ RRH			
6		3	Alcatel Lucent TD-RRH8x20-25			
7		3	Alcatel-Lucent 800 MHz Filter			
25	52.0	1	GPS	-	(1) 1/2"	

See the attached coax layout for the line placement considered in the analysis.

Analysis Results

The results of the structural analysis, performed for the wind and ice loading and antenna equipment as defined above, are summarized as the following:

	Pole shafts	Anchor Bolts	Base Plate
Max. Usage:	84.0%	62.7%	54.1%
Pass/Fail	Pass	Pass	Pass

Foundations

	Moment (Kip-Ft)	Shear (Kips)
Original Design Reactions	4948.0	38.8
Analysis Reactions	5345.8	44.1
Factored Reactions*	6679.8	52.4
% of Design Reactions	80.0%	84.2%

* Per section 15.5.1 of the TIA-222-G standard, factored reactions were obtained by multiplying a 1.35 factor to the original design reactions.

The foundation has been investigated using the supplied documents and soils report and was found adequate. Therefore, no modification to the foundation will be required.

Operational Condition (Rigidity):

Operational characteristics of the tower are found to be within the limits prescribed by ANSI/TIA/EIA 222-G for the installed antennas. The maximum twist/sway at the elevation of the proposed equipment is 1.4424 degrees under the operational wind speed as specified in the Analysis Criteria.

Conclusions

Based on the analysis results, the existing structure and its foundation were found to be adequate to safely support the existing and proposed equipment and meet the minimum requirements per the ANSI/TIA-222-G standards and the 2012 IBC under the design basic wind speed specified in the Analysis Criteria.

Standard Conditions

1. This analysis was performed based on the information supplied to **(TES) Tower Engineering Solutions, LLC**. Verification of the information provided was not included in the Scope of Work for **TES**. The accuracy of the analysis is dependent on the accuracy of the information provided.
2. The analysis is based on the presumption that the tower members and components along with any existing reinforcement items have been correctly and properly designed, manufactured, installed and maintained.
3. All the existing structural members were assumed to be in good condition with no physical damage or deterioration associated with corrosion.
4. An initial tension of 10% of the break strength on all the existing guy wires was assumed in all the structural analyses of guyed towers unless different values were provided by the client. **TES** cannot take responsibility for the deviations in the analysis results because of differences in the initial tension forces of the existing guy wires.
5. Secondary component or connection secondary components, welds and bolts are assumed to be able to carry their intended original design loads. **TES** cannot take responsibility for verification of the adequacy on the connections, bolts and welds present in the structure.
6. The analyses will be performed based on the codes as specified by the client or based on the best knowledge of the engineering staff of **TES**. In the absence of information to the contrary, all work will be performed in accordance with the latest relevant revision of ANSI/TIA-222. If wind speed and/or ice loads are different from the minimum values recommended by the EIA/TIA-222 standard or other codes, **TES** should be notified in writing and the applicable minimum values provided by the client.
7. The configuration of the existing mounts, antennas, coax and other appurtenances were supplied by the customer for the current structural analysis. **TES** has not visited the tower site to verify the adequacy of the information provided. If there is any discrepancy found in the report regarding the existing conditions, **TES** should be notified immediately to evaluate the effect of the discrepancy on the analysis results.
8. The client will assume responsibility for rework associated with the differences in initially provided information, including tower and foundation information, existing and/or proposed equipment and transmission lines.
9. If a feasibility analysis was performed, final acceptance of changed conditions shall be based upon a rigorous structural analysis.

Usage Diagram - Max Ratio 82.81% at 98.9ft

Structure: CT01365-S-SBA
Site Name: Norwich 2 CT
Height: 180.00 (ft)
Base Elev: 0.000 (ft)

Code: EIA/TIA-222-G
Exposure: C
Gh: 1.1


10/13/2017



Page: 1


Dead Load Factor: 1.20
 Wind Load Factor: 1.60

Load Case : 1.2D + 1.6W 105 mph Wind



Iterations: 26

Copyright © 2017 by Tower Engineering Solutions, LLC. All rights reserved.



Structure: CT01365-S-SBA

Type: Tapered
Site Name: Norwich 2 CT
Height: 180.00 (ft)
Base Elev: 0.00 (ft)

Base Shape: 16 Sided
Taper: 0.18500

10/13/2017

Page: 2



Shaft Properties

Seq	Length (ft)	Top (in)	Bottom (in)	Thick (in)	Joint Type	Taper	Grade (ksi)
1	53.00	48.20	58.00	0.438		0.18500	65
2	53.00	40.45	50.26	0.375	Slip	0.18500	65
3	39.17	34.89	42.14	0.281	Slip	0.18500	65
4	53.33	26.45	36.32	0.219	Slip	0.18500	65

Discrete Appurtenances


Attach Elev (ft)	Force Elev (ft)	Qty	Description	Carrier
180.00	180.00	1	Lightning Rod	
177.00	177.00	3	APXVSP18-C-A20	Sprint Nextel
177.00	177.00	3	APXVTM14-C-120	Sprint Nextel
177.00	177.00	3	TD-RRH8x20-25	Sprint Nextel
177.00	177.00	3	1900MHz RRUs	Sprint Nextel
177.00	177.00	3	800 MHz RRUs	Sprint Nextel
177.00	177.00	3	ALU 800MHz External	Sprint Nextel
177.00	177.00	4	ACU-A20-N	Sprint Nextel
177.00	177.00	1	Platform w/ Hand Rail	Sprint Nextel
159.00	159.00	3	B25 RRH4x30	Verizon
159.00	159.00	3	RRH 4X45-PCS	Verizon
159.00	159.00	2	DB-T1-6Z-8AB-0Z	Verizon
159.00	159.00	1	Low Profile	Verizon
159.00	159.00	6	SBNHH-1D65B	Verizon
159.00	159.00	3	B25 RRH4x30	Verizon
159.00	159.00	3	BXA-80080/4CF	Verizon
159.00	159.00	3	BXA-171085-8BF-EDIN-2	Verizon
147.00	147.00	1	HPA-65R-BUU-H6	AT&T
147.00	147.00	2	HPA-65R-BUU-H8	AT&T
147.00	147.00	12	860 10025 RET	AT&T
147.00	147.00	3	RRUS 12	AT&T
147.00	147.00	3	RRUS A2	AT&T
147.00	147.00	6	RRUS-11	AT&T
147.00	147.00	6	LGP21401	AT&T
147.00	147.00	6	LGP21901 Diplexer	AT&T
147.00	147.00	1	DC6-48-60-18-8F("Squid")	AT&T
147.00	147.00	1	Low Profile	AT&T
147.00	147.00	6	7770.00	AT&T
52.00	52.00	1	GPS	Sprint Nextel

Linear Appurtenances

Elev From (ft)	Elev To (ft)	Placement	Description	Carrier
0.00	177.00	Inside	1 1/4" Coax	Sprint Nextel
0.00	159.00	Inside	1 5/8" Coax	Verizon
0.00	159.00	Inside	1 5/8" Fiber	Verizon
0.00	147.00	Inside	0.5" Fiber	AT&T
0.00	147.00	Inside	1 5/8" Coax	AT&T
0.00	147.00	Inside	3/4" DC	AT&T
0.00	127.00	Inside	1/2" Coax	AT&T
0.00	52.00	Outside	1/2" Coax	Sprint Nextel

Anchor Bolts

Qty	Specifications	Grade (ksi)	Arrangement
20	2.25" 18J	75.0	Radial



Structure: CT01365-S-SBA

Type: Tapered
Site Name: Norwich 2 CT
Height: 180.00 (ft)
Base Elev: 0.00 (ft)

Base Shape: 16 Sided
Taper: 0.18500

10/13/2017

Page: 3



Base Plate

Thickness (in)	Specifications (in)	Grade (ksi)	Geometry
2.7500	72.5	60.0	Polygon

Reactions

Load Case	Moment (FT-Kips)	Shear (Kips)	Axial (Kips)
1.2D + 1.6W 105 mph Wind	5345.8	44.1	51.8
0.9D + 1.6W 105 mph Wind	5293.1	44.1	38.8
1.2D + 1.0Di + 1.0Wi 50 mph Wind	1249.7	10.1	77.9
1.2D + 1.0E	211.6	1.7	51.9
0.9D + 1.0E	209.4	1.7	38.9
1.0D + 1.0W 60 mph Wind	1085.9	9.0	43.2


Structure: CT01365-S-SBA - Coax Line Placement

Type: Monopole
Site Name: Norwich 2 CT
Height: 180.00 (ft)

10/13/2017



Page: 4



Shaft Properties

Structure: CT01365-S-SBA	Code: EIA/TIA-222-G	10/13/2017
Site Name: Norwich 2 CT	Exposure: C	
Height: 180.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II



Page: 5

Sec. No.	Shape	Length (ft)	Thick (in)	Fy (ksi)	Joint Type	Overlap (in)	Weight (lb)
1	16	53.000	0.4380	65		0.00	13,269
2	16	53.000	0.3750	65	Slip	85.00	9,704
3	16	39.170	0.2810	65	Slip	73.00	4,568
4	16	53.330	0.2190	65	Slip	64.00	3,951
Total Shaft Weight:							31,492

Bottom

Top

Sec. No.	Dia (in)	Elev (ft)	Area (sqin)	Ix (in^4)	W/t Ratio	D/t Ratio	Dia (in)	Elev (ft)	Area (sqin)	Ix (in^4)	W/t Ratio	D/t Ratio	Taper
1	58.00	0.00	80.43	33665.63	24.75	132.42	48.20	53.00	66.73	19226.0	20.30	110.0	0.185000
2	50.26	45.92	59.67	18755.41	25.07	134.01	40.45	98.92	47.94	9726.81	19.86	107.8	0.185000
3	42.14	92.83	37.52	8304.44	28.24	149.96	34.89	132.00	31.02	4694.95	23.11	124.1	0.185000
4	36.32	126.6	25.22	4151.11	31.39	165.83	26.45	180.00	18.33	1592.92	22.43	120.7	0.185000

Additional Steel

Elev From (ft)	Elev To (ft)	Qty	Description	Fy (ksi)	Fu (ksi)	Offset (in)	Intermediate Connectors			Termination Connectors		
							Spacing (in)	Description	Spacing (in)	Lower Qty	Upper Qty	
0.00	17.00	3	PLT 7.5"x1.25"(1.25"hole)	65	80	0.00	AJM20&sleeve	18.00	AJM20&sleeve	3.00	14	14

Load Summary

Structure: CT01365-S-SBA	Code: EIA/TIA-222-G	10/13/2017
Site Name: Norwich 2 CT	Exposure: C	
Height: 180.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II



Page: 6

Discrete Appurtenances

No.	Elev (ft)	Description	Qty	No Ice			Ice			Hor. Ecc. (ft)	Vert Ecc (ft)
				Weight (lb)	CaAa (sf)	CaAa Factor	Weight (lb)	CaAa (sf)	CaAa Factor		
1	180.00	Lightning Rod	1	5.00	0.50	1.00	26.33	2.277	1.00	0.00	0.00
2	177.00	APXVSP18-C-A20	3	57.00	8.02	0.83	232.74	10.860	0.83	0.00	0.00
3	177.00	APXVTM14-C-120	3	56.00	6.34	0.79	219.64	7.473	0.79	0.00	0.00
4	177.00	TD-RRH8x20-25	3	70.00	4.05	0.69	182.70	4.878	0.69	0.00	0.00
5	177.00	1900MHz RRUs	3	44.00	3.80	0.88	154.99	5.213	0.88	0.00	0.00
6	177.00	800 MHz RRUs	3	53.00	2.49	0.92	128.19	3.653	0.92	0.00	0.00
7	177.00	ALU 800MHz External Notch Filt	3	8.80	0.78	0.69	26.74	1.438	0.69	0.00	0.00
8	177.00	ACU-A20-N	4	1.00	0.14	0.79	5.37	0.442	0.79	0.00	0.00
9	177.00	Platform w/ Hand Rail (round)	1	1600.00	32.00	1.00	3734.89	60.389	1.00	0.00	0.00
10	159.00	B25 RRH4x30	3	51.00	2.14	0.81	109.08	2.752	0.81	0.00	0.00
11	159.00	RRH 4X45-PCS	3	60.00	2.71	0.98	141.23	3.981	0.98	0.00	0.00
12	159.00	DB-T1-6Z-8AB-OZ	2	18.90	4.80	0.71	163.62	5.679	0.71	0.00	0.00
13	159.00	Low Profile Platform-Round	1	1500.00	22.00	1.00	2816.56	39.765	1.00	0.00	0.00
14	159.00	SBNHH-1D65B	6	40.60	8.08	0.83	243.61	9.380	0.83	0.00	0.00
15	159.00	B25 RRH4x30	3	51.00	2.14	0.81	109.08	2.752	0.81	0.00	0.00
16	159.00	BXA-80080/4CF	3	14.30	4.80	0.76	123.13	6.684	0.76	0.00	0.00
17	159.00	BXA-171085-8BF-EDIN-2	3	10.50	2.94	0.84	76.43	4.608	0.84	0.00	0.00
18	147.00	HPA-65R-BUU-H6	1	51.00	9.66	1.00	298.52	11.023	1.00	1.00	0.00
19	147.00	HPA-65R-BUU-H8	2	68.00	12.98	0.89	358.36	14.592	0.89	0.00	0.00
20	147.00	860 10025 RET	12	1.20	0.18	0.92	7.18	0.558	0.92	0.00	0.00
21	147.00	RRUS 12	3	58.00	2.70	0.70	122.65	3.358	0.71	0.00	0.00
22	147.00	RRUS A2	3	22.00	1.86	0.61	59.40	2.832	0.63	0.00	0.00
23	147.00	RRUS-11	6	51.00	2.52	0.67	123.13	3.152	0.67	0.00	0.00
24	147.00	LGP21401	6	14.10	1.29	0.67	39.05	2.124	0.67	0.00	0.00
25	147.00	LGP21901 Diplexer	6	5.50	0.27	0.67	13.91	0.667	0.67	0.00	0.00
26	147.00	DC6-48-60-18-8F("Squid")	1	31.80	0.92	1.00	93.50	1.357	1.00	1.00	0.00
27	147.00	Low Profile Platform-Round	1	1500.00	22.00	1.00	2806.27	39.626	1.00	0.00	0.00
28	147.00	7770.00	6	35.00	5.50	0.75	169.84	6.563	0.75	0.00	0.00
29	52.00	GPS	1	0.20	0.11	1.00	0.92	0.542	1.00	1.00	0.00
Totals:			96	7,424.20			19,523.86				

Linear Appurtenances

Bottom Elev. (ft)	Top Elev. (ft)	Description	Exposed Width	Exposed
0.00	177.00	(4) 1 1/4" Coax	0.00	Inside
0.00	159.00	(11) 1 5/8" Coax	0.00	Inside
0.00	159.00	(2) 1 5/8" Fiber	0.00	Inside
0.00	147.00	(1) 0.5" Fiber	0.00	Inside
0.00	147.00	(12) 1 5/8" Coax	0.00	Inside
0.00	147.00	(2) 3/4" DC	0.00	Inside
0.00	127.00	(1) 1/2" Coax	0.00	Inside
0.00	52.00	(1) 1/2" Coax	1.00	Outside

Shaft Section Properties

Structure: CT01365-S-SBA **Code:** EIA/TIA-222-G 10/13/2017
Site Name: Norwich 2 CT **Exposure:** C
Height: 180.00 (ft) **Crest Height:** 0.00
Base Elev: 0.000 (ft) **Site Class:** D - Stiff Soil
Gh: 1.1 **Topography:** 1 **Struct Class:** II **Page:** 7



Increment Length: 5 (ft)

Elev (ft)	Description	Thick (in)	Flat Dia (in)	Area (in^2)	Ix (in^4)	W/t Ratio	D/t Ratio	Fy (ksi)	Fb (ksi)	Weight (lb)	Additional Reinforcing			
											Area (in^2)	Ixp (in^4)	Iyp (in^4)	Weight (lb)
0.00	RB1	0.4380	58.000	80.427	33665.6	24.75	132.42	65	75	0.0	28.13	14104.8	10646.3	
5.00		0.4380	57.075	79.134	32068.6	24.33	130.31	65	75	1357.4	28.13	13669.6	10318.1	478.5
10.00		0.4380	56.150	77.842	30522.9	23.91	128.20	65	76	1335.4	28.13	13241.3	9995.2	478.5
15.00		0.4380	55.225	76.549	29027.6	23.49	126.08	65	76	1313.4	28.13	12819.9	9677.4	478.5
17.00	RT1	0.4380	54.855	76.033	28443.5	23.32	125.24	65	76	519.2	28.13	12653.2	9551.8	191.4
20.00		0.4380	54.300	75.257	27582.1	23.07	123.97	65	76	772.2				
25.00		0.4380	53.375	73.965	26185.3	22.65	121.86	65	77	1269.4				
30.00		0.4380	52.450	72.672	24836.5	22.23	119.75	65	77	1247.4				
35.00		0.4380	51.525	71.380	23534.8	21.81	117.64	65	78	1225.4				
40.00		0.4380	50.600	70.087	22279.4	21.39	115.53	65	78	1203.5				
45.00		0.4380	49.675	68.795	21069.5	20.97	113.41	65	79	1181.5				
45.92	Bot - Section 2	0.4380	49.505	68.558	20852.5	20.89	113.03	65	79	214.2				
50.00		0.4380	48.750	67.502	19904.2	20.55	111.30	65	79	1768.1				
52.00		0.4380	48.380	66.986	19450.4	20.38	110.46	65	80	856.1				
53.00	Top - Section 1	0.3750	48.945	58.102	17315.7	24.37	130.52	65	75	425.6				
55.00		0.3750	48.575	57.659	16923.0	24.17	129.53	65	75	393.9				
60.00		0.3750	47.650	56.553	15967.3	23.68	127.07	65	76	971.6				
65.00		0.3750	46.725	55.446	15048.2	23.19	124.60	65	76	952.8				
70.00		0.3750	45.800	54.340	14165.1	22.70	122.13	65	77	933.9				
75.00		0.3750	44.875	53.233	13317.3	22.21	119.67	65	77	915.1				
80.00		0.3750	43.950	52.127	12504.0	21.72	117.20	65	78	896.3				
85.00		0.3750	43.025	51.020	11724.5	21.23	114.73	65	79	877.5				
90.00		0.3750	42.100	49.914	10978.1	20.74	112.27	65	79	858.6				
92.83	Bot - Section 3	0.3750	41.576	49.286	10569.5	20.46	110.87	65	79	478.2				
95.00		0.3750	41.175	48.807	10264.0	20.25	109.80	65	80	636.9				
98.92	Top - Section 2	0.2810	41.012	36.511	7652.4	27.44	145.95	65	72	1135.6				
100.00		0.2810	40.812	36.332	7540.0	27.30	145.24	65	72	134.3				
105.00		0.2810	39.887	35.502	7035.5	26.64	141.95	65	72	611.1				
110.00		0.2810	38.962	34.673	6554.0	25.99	138.65	65	73	597.0				
115.00		0.2810	38.037	33.844	6094.9	25.33	135.36	65	74	582.9				
120.00		0.2810	37.112	33.015	5657.9	24.68	132.07	65	75	568.8				
125.00		0.2810	36.187	32.186	5242.2	24.02	128.78	65	75	554.7				
126.67	Bot - Section 4	0.2810	35.878	31.909	5108.0	23.81	127.68	65	76	182.1				
130.00		0.2810	35.262	31.357	4847.4	23.37	125.49	65	76	641.7				
132.00	Top - Section 3	0.2190	35.329	24.528	3819.9	30.50	161.32	65	68	380.7				
135.00		0.2190	34.775	24.141	3641.8	29.99	158.79	65	69	248.1				
140.00		0.2190	33.850	23.495	3357.1	29.15	154.57	65	70	405.2				
145.00		0.2190	32.925	22.849	3087.7	28.31	150.34	65	71	394.2				
147.00		0.2190	32.555	22.590	2984.1	27.98	148.65	65	71	154.6				
150.00		0.2190	32.000	22.203	2833.0	27.47	146.12	65	71	228.6				
155.00		0.2190	31.075	21.556	2592.8	26.63	141.89	65	72	372.3				
159.00		0.2190	30.335	21.039	2410.7	25.96	138.52	65	73	289.9				
160.00		0.2190	30.150	20.910	2366.5	25.79	137.67	65	73	71.4				
165.00		0.2190	29.225	20.264	2153.8	24.95	133.45	65	74	350.3				
170.00		0.2190	28.300	19.618	1954.3	24.11	129.22	65	75	339.3				
175.00		0.2190	27.375	18.971	1767.4	23.27	125.00	65	76	328.3				
177.00		0.2190	27.005	18.713	1696.2	22.94	123.31	65	77	128.2				
180.00		0.2190	26.450	18.325	1592.9	22.43	120.78	65	77	189.0				
Total Weight										31491.9				
											1626.9			

Wind Loading - Shaft


Structure: CT01365-S-SBA	Code: EIA/TIA-222-G	10/13/2017
Site Name: Norwich 2 CT	Exposure: C	
Height: 180.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II



Load Case: 1.2D + 1.6W 105 mph Wind

Iterations 26

Dead Load Factor 1.20
Wind Load Factor 1.60



Elev (ft)	Description	Kzt	Kz	qz (psf)	qzGh (psf)	C (mph-ft)	Cf	Ice Thick (in)	Tributary (ft)	Aa (sf)	CfAa (sf)	Wind Force X (lb)	Dead Load Ice (lb)	Tot Dead Load (lb)
0.00	RB1	1.00	0.85	22.791	25.07	477.06	0.750	0.000	0.00	0.000	0.00	0.0	0.0	0.0
5.00		1.00	0.85	22.791	25.07	469.45	0.750	0.000	5.00	24.444	18.33	735.4	0.0	1628.9
10.00		1.00	0.85	22.791	25.07	461.84	0.750	0.000	5.00	24.051	18.04	723.5	0.0	1602.5
15.00		1.00	0.85	22.791	25.07	454.23	0.750	0.000	5.00	23.658	17.74	711.7	0.0	1576.1
17.00	RT1	1.00	0.87	23.369	25.71	456.87	0.750	0.000	2.00	9.353	7.01	288.5	0.0	623.0
20.00		1.00	0.90	24.182	26.60	460.05	0.750	0.000	3.00	13.912	10.43	444.1	0.0	926.6
25.00		1.00	0.95	25.345	27.88	462.97	0.750	0.000	5.00	22.872	17.15	765.2	0.0	1523.3
30.00		1.00	0.98	26.337	28.97	463.76	0.750	0.000	5.00	22.479	16.86	781.5	0.0	1496.9
35.00		1.00	1.01	27.206	29.93	463.03	0.750	0.000	5.00	22.086	16.56	793.1	0.0	1470.5
40.00		1.00	1.04	27.981	30.78	461.16	0.750	0.000	5.00	21.693	16.27	801.2	0.0	1444.1
45.00		1.00	1.07	28.684	31.55	458.37	0.750	0.000	5.00	21.300	15.97	806.5	0.0	1417.8
45.92	Bot - Section 2	1.00	1.07	28.806	31.69	457.78	0.750	0.000	0.92	3.862	2.90	146.9	0.0	257.1
50.00		1.00	1.09	29.327	32.26	454.85	0.750	0.000	4.08	17.305	12.98	669.9	0.0	2121.7
52.00	Appurtenance(s)	1.00	1.10	29.570	32.53	453.27	0.750	0.000	2.00	8.380	6.29	327.1	0.0	1027.3
53.00	Top - Section 1	1.00	1.11	29.689	32.66	452.44	0.750	0.000	1.00	4.167	3.12	163.3	0.0	510.7
55.00		1.00	1.12	29.922	32.91	457.79	0.750	0.000	2.00	8.286	6.21	327.3	0.0	472.7
60.00		1.00	1.14	30.475	33.52	453.21	0.750	0.000	5.00	20.440	15.33	822.2	0.0	1165.9
65.00		1.00	1.16	30.993	34.09	448.17	0.750	0.000	5.00	20.047	15.03	820.1	0.0	1143.3
70.00		1.00	1.17	31.480	34.63	442.74	0.750	0.000	5.00	19.654	14.74	816.7	0.0	1120.7
75.00		1.00	1.19	31.941	35.13	436.96	0.750	0.000	5.00	19.261	14.45	812.1	0.0	1098.1
80.00		1.00	1.21	32.377	35.62	430.87	0.750	0.000	5.00	18.868	14.15	806.4	0.0	1075.5
85.00		1.00	1.22	32.793	36.07	424.50	0.750	0.000	5.00	18.475	13.86	799.7	0.0	1053.0
90.00		1.00	1.24	33.190	36.51	417.88	0.750	0.000	5.00	18.082	13.56	792.2	0.0	1030.4
92.83	Bot - Section 3	1.00	1.25	33.408	36.75	414.03	0.750	0.000	2.83	10.072	7.55	444.2	0.0	573.8
95.00		1.00	1.25	33.570	36.93	411.03	0.750	0.000	2.17	7.720	5.79	342.1	0.0	764.3
98.92	Top - Section 2	1.00	1.26	33.857	37.24	405.52	0.750	0.000	3.92	13.769	10.33	615.3	0.0	1362.8
100.00		1.00	1.27	33.935	37.33	409.61	0.750	0.000	1.08	3.766	2.82	168.7	0.0	161.1
105.00		1.00	1.28	34.285	37.71	402.39	0.750	0.000	5.00	17.142	12.86	775.8	0.0	733.3
110.00		1.00	1.29	34.623	38.08	394.99	0.750	0.000	5.00	16.749	12.56	765.4	0.0	716.4
115.00		1.00	1.30	34.948	38.44	387.42	0.750	0.000	5.00	16.356	12.27	754.5	0.0	699.4
120.00		1.00	1.32	35.263	38.79	379.69	0.750	0.000	5.00	15.963	11.97	743.0	0.0	682.5
125.00		1.00	1.33	35.567	39.12	371.83	0.750	0.000	5.00	15.570	11.68	731.0	0.0	665.6
126.67	Bot - Section 4	1.00	1.33	35.667	39.23	369.17	0.750	0.000	1.67	5.113	3.83	240.7	0.0	218.5
130.00		1.00	1.34	35.862	39.45	363.82	0.750	0.000	3.33	10.188	7.64	482.3	0.0	770.1
132.00	Top - Section 3	1.00	1.34	35.978	39.58	360.58	0.750	0.000	2.00	6.045	4.53	287.1	0.0	456.9
135.00		1.00	1.35	36.148	39.76	360.22	0.750	0.000	3.00	8.925	6.69	425.8	0.0	297.8
140.00		1.00	1.36	36.426	40.07	351.99	0.750	0.000	5.00	14.577	10.93	700.9	0.0	486.3
145.00		1.00	1.37	36.696	40.37	343.64	0.750	0.000	5.00	14.184	10.64	687.1	0.0	473.1
147.00	Appurtenance(s)	1.00	1.37	36.802	40.48	340.26	0.750	0.000	2.00	5.564	4.17	270.3	0.0	185.5
150.00		1.00	1.38	36.959	40.65	335.17	0.750	0.000	3.00	8.227	6.17	401.4	0.0	274.4
155.00		1.00	1.39	37.215	40.94	326.61	0.750	0.000	5.00	13.398	10.05	658.2	0.0	446.7
159.00	Appurtenance(s)	1.00	1.40	37.415	41.16	319.69	0.750	0.000	4.00	10.436	7.83	515.4	0.0	347.9
160.00		1.00	1.40	37.464	41.21	317.95	0.750	0.000	1.00	2.570	1.93	127.1	0.0	85.6
165.00		1.00	1.41	37.708	41.48	309.20	0.750	0.000	5.00	12.612	9.46	627.8	0.0	420.3
170.00		1.00	1.42	37.946	41.74	300.35	0.750	0.000	5.00	12.219	9.16	612.0	0.0	407.1
175.00		1.00	1.42	38.178	42.00	291.42	0.750	0.000	5.00	11.826	8.87	596.0	0.0	393.9
177.00	Appurtenance(s)	1.00	1.43	38.269	42.10	287.83	0.750	0.000	2.00	4.620	3.47	233.4	0.0	153.9

Wind Loading - Shaft

Structure: CT01365-S-SBA	Code: EIA/TIA-222-G	10/13/2017
Site Name: Norwich 2 CT	Exposure: C	
Height: 180.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II
		Page: 9



180.00 Appurtenance(s)	1.00	1.43	38.405	42.25	282.41	0.750	0.000	3.00	6.813	5.11	345.4	0.0	226.9
							Totals:	180.00			26,705.2		37,790.2

Discrete Appurtenance Forces

Structure: CT01365-S-SBA	Code: EIA/TIA-222-G	10/13/2017
Site Name: Norwich 2 CT	Exposure: C	
Height: 180.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II



Page: 10

Load Case: 1.2D + 1.6W 105 mph Wind

Dead Load Factor 1.20
Wind Load Factor 1.60



Iterations 26

No.	Elev (ft)	Description	Qty	qz (psf)	qzGh (psf)	CaAa x Ka	Ka	Total CaAa (sf)	Dead Load (lb)	Horiz Ecc (ft)	Vert Ecc (ft)	Wind FX (lb)	Mom Y (lb-ft)	Mom Z (lb-ft)
1	180.00	Lightning Rod	1	38.405	42.245	1.00	1.00	0.50	6.00	0.000	0.000	33.80	0.00	0.00
2	177.00	1900MHz RRUs	3	38.269	42.096	0.70	0.80	8.03	158.40	0.000	0.000	540.56	0.00	0.00
3	177.00	APXVSPP18-C-A20	3	38.269	42.096	0.66	0.80	15.98	205.20	0.000	0.000	1076.03	0.00	0.00
4	177.00	APXVTM14-C-120	3	38.269	42.096	0.63	0.80	12.02	201.60	0.000	0.000	809.64	0.00	0.00
5	177.00	TD-RRH8x20-25	3	38.269	42.096	0.55	0.80	6.71	252.00	0.000	0.000	451.73	0.00	0.00
6	177.00	800 MHz RRUs	3	38.269	42.096	0.74	0.80	5.50	190.80	0.000	0.000	370.31	0.00	0.00
7	177.00	ALU 800MHz External	3	38.269	42.096	0.55	0.80	1.29	31.68	0.000	0.000	87.00	0.00	0.00
8	177.00	ACU-A20-N	4	38.269	42.096	0.63	0.80	0.35	4.80	0.000	0.000	23.84	0.00	0.00
9	177.00	Platform w/ Hand Rail	1	38.269	42.096	1.00	1.00	32.00	1920.00	0.000	0.000	2155.32	0.00	0.00
10	159.00	BXA-171085-8BF-EDIN-2	3	37.415	41.156	0.67	0.80	5.93	37.80	0.000	0.000	390.30	0.00	0.00
11	159.00	BXA-80080/4CF	3	37.415	41.156	0.61	0.80	8.76	51.48	0.000	0.000	576.53	0.00	0.00
12	159.00	B25 RRH4x30	3	37.415	41.156	0.65	0.80	4.16	183.60	0.000	0.000	273.95	0.00	0.00
13	159.00	SBNHH-1D65B	6	37.415	41.156	0.66	0.80	32.19	292.32	0.000	0.000	2119.77	0.00	0.00
14	159.00	Low Profile	1	37.415	41.156	1.00	1.00	22.00	1800.00	0.000	0.000	1448.70	0.00	0.00
15	159.00	DB-T1-6Z-8AB-OZ	2	37.415	41.156	0.57	0.80	5.45	45.36	0.000	0.000	359.07	0.00	0.00
16	159.00	B25 RRH4x30	3	37.415	41.156	0.65	0.80	4.16	183.60	0.000	0.000	273.95	0.00	0.00
17	159.00	RRH 4X45-PCS	3	37.415	41.156	0.78	0.80	6.37	216.00	0.000	0.000	419.72	0.00	0.00
18	147.00	RRUS A2	3	36.802	40.482	0.49	0.80	2.73	79.20	0.000	0.000	176.66	0.00	0.00
19	147.00	HPA-65R-BUU-H6	1	36.802	40.482	0.80	0.80	7.73	61.20	2.383	0.000	500.55	745.52	0.00
20	147.00	HPA-65R-BUU-H8	2	36.802	40.482	0.71	0.80	18.50	163.20	0.000	0.000	1198.55	0.00	0.00
21	147.00	860 10025 RET	12	36.802	40.482	0.74	0.80	1.59	17.28	0.000	0.000	102.97	0.00	0.00
22	147.00	RRUS 12	3	36.802	40.482	0.56	0.80	4.56	208.80	0.000	0.000	295.06	0.00	0.00
23	147.00	LGP21401	6	36.802	40.482	0.54	0.80	4.15	101.52	0.000	0.000	268.71	0.00	0.00
24	147.00	RRUS-11	6	36.802	40.482	0.54	0.80	8.10	367.20	0.000	0.000	524.93	0.00	0.00
25	147.00	LGP21901 Diplexer	6	36.802	40.482	0.54	0.80	0.87	39.60	0.000	0.000	56.24	0.00	0.00
26	147.00	DC6-48-60-18-8F("Squid")	1	36.802	40.482	1.00	1.00	0.92	38.16	2.383	0.000	59.59	88.75	0.00
27	147.00	Low Profile	1	36.802	40.482	1.00	1.00	22.00	1800.00	0.000	0.000	1424.97	0.00	0.00
28	147.00	7770.00	6	36.802	40.482	0.60	0.80	19.77	252.00	0.000	0.000	1280.76	0.00	0.00
29	52.00	GPS	1	29.570	32.527	0.80	0.80	0.09	0.24	3.055	0.000	4.58	8.75	0.00
Totals:									8,909.04			17,303.78		

Total Applied Force Summary


Structure: CT01365-S-SBA	Code: EIA/TIA-222-G	10/13/2017
Site Name: Norwich 2 CT	Exposure: C	
Height: 180.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II



Page: 11

Load Case: 1.2D + 1.6W 105 mph Wind

Dead Load Factor 1.20
Wind Load Factor 1.60



Iterations 26

Elev (ft)	Description	Lateral FX (-) (lb)	Axial FY (-) (lb)	Torsion MY (lb-ft)	Moment MZ (lb-ft)
0.00		0.00	0.00	0.00	0.00
5.00		735.36	1796.01	0.00	0.00
10.00		723.54	1769.63	0.00	0.00
15.00		711.72	1743.24	0.00	0.00
17.00		288.51	689.91	0.00	0.00
20.00		444.07	1026.94	0.00	0.00
25.00		765.19	1690.46	0.00	0.00
30.00		781.47	1664.08	0.00	0.00
35.00		793.13	1637.69	0.00	0.00
40.00		801.23	1611.30	0.00	0.00
45.00		806.47	1584.92	0.00	0.00
45.92		146.86	287.71	0.00	0.00
50.00		669.90	2258.20	0.00	0.00
52.00	(1) attachments	331.68	1094.38	8.75	0.00
53.00		163.28	543.94	0.00	0.00
55.00		327.26	539.17	0.00	0.00
60.00		822.22	1332.11	0.00	0.00
65.00		820.11	1309.52	0.00	0.00
70.00		816.68	1286.93	0.00	0.00
75.00		812.06	1264.34	0.00	0.00
80.00		806.37	1241.75	0.00	0.00
85.00		799.72	1219.16	0.00	0.00
90.00		792.19	1196.56	0.00	0.00
92.83		444.15	668.02	0.00	0.00
95.00		342.11	836.31	0.00	0.00
98.92		615.35	1492.95	0.00	0.00
100.00		168.69	197.12	0.00	0.00
105.00		775.77	899.51	0.00	0.00
110.00		765.45	882.58	0.00	0.00
115.00		754.51	865.65	0.00	0.00
120.00		743.01	848.72	0.00	0.00
125.00		730.98	831.79	0.00	0.00
126.67		240.71	274.05	0.00	0.00
130.00		482.28	880.21	0.00	0.00
132.00		287.09	523.06	0.00	0.00
135.00		425.85	396.80	0.00	0.00
140.00		700.89	651.53	0.00	0.00
145.00		687.05	638.33	0.00	0.00
147.00	(47) attachments	6159.27	3379.80	834.27	0.00
150.00		401.38	325.48	0.00	0.00
155.00		658.16	531.90	0.00	0.00
159.00	(24) attachments	6377.37	3226.18	0.00	0.00
160.00		127.07	88.81	0.00	0.00
165.00		627.76	436.16	0.00	0.00
170.00		612.03	422.96	0.00	0.00
175.00		595.98	409.77	0.00	0.00
177.00	(23) attachments	5747.83	3124.69	0.00	0.00

Total Applied Force Summary

Structure: CT01365-S-SBA	Code: EIA/TIA-222-G	10/13/2017
Site Name: Norwich 2 CT	Exposure: C	
Height: 180.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II



Page: 12

180.00	(1) attachments	379.17	232.86	0.00	0.00
	Totals:	44,008.94	51,853.19	843.02	0.00

Linear Appurtenance Segment Forces (Factored)

Structure: CT01365-S-SBA	Code: EIA/TIA-222-G	10/13/2017
Site Name: Norwich 2 CT	Exposure: C	
Height: 180.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II




Page: 13

Load Case: 1.2D + 1.6W 105 mph Wind

Dead Load Factor 1.20

Wind Load Factor 1.60



Iterations 26

Top Elev (ft)	Description	Wind Exposed	Length (ft)	Ca	Exposed Width (in)	Area (sqft)	CaAa (sqft)	Ra	Cf Adjust Factor	qz (psf)	F X (lb)	Dead Load (lb)
5.00	1/2" Coax	Yes	5.00	0.000	0.65	0.27	0.00	0.011	0.000	22.791	0.00	0.96
10.00	1/2" Coax	Yes	5.00	0.000	0.65	0.27	0.00	0.011	0.000	22.791	0.00	0.96
15.00	1/2" Coax	Yes	5.00	0.000	0.65	0.27	0.00	0.011	0.000	22.791	0.00	0.96
17.00	1/2" Coax	Yes	2.00	0.000	0.65	0.11	0.00	0.012	0.000	23.369	0.00	0.38
20.00	1/2" Coax	Yes	3.00	0.000	0.65	0.16	0.00	0.012	0.000	24.182	0.00	0.58
25.00	1/2" Coax	Yes	5.00	0.000	0.65	0.27	0.00	0.012	0.000	25.345	0.00	0.96
30.00	1/2" Coax	Yes	5.00	0.000	0.65	0.27	0.00	0.012	0.000	26.337	0.00	0.96
35.00	1/2" Coax	Yes	5.00	0.000	0.65	0.27	0.00	0.012	0.000	27.206	0.00	0.96
40.00	1/2" Coax	Yes	5.00	0.000	0.65	0.27	0.00	0.012	0.000	27.981	0.00	0.96
45.00	1/2" Coax	Yes	5.00	0.000	0.65	0.27	0.00	0.013	0.000	28.684	0.00	0.96
45.92	1/2" Coax	Yes	0.92	0.000	0.65	0.05	0.00	0.013	0.000	28.806	0.00	0.18
50.00	1/2" Coax	Yes	4.08	0.000	0.65	0.22	0.00	0.013	0.000	29.327	0.00	0.78
52.00	1/2" Coax	Yes	2.00	0.000	0.65	0.11	0.00	0.013	0.000	29.570	0.00	0.38
Totals:											0.0	10.0

Calculated Forces

Structure: CT01365-S-SBA	Code: EIA/TIA-222-G	10/13/2017
Site Name: Norwich 2 CT	Exposure: C	
Height: 180.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II




Page: 14

Load Case: 1.2D + 1.6W 105 mph Wind

Iterations 26

Dead Load Factor 1.20
Wind Load Factor 1.60



Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (-) (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	phi Pn (kips)	phi Vn (kips)	phi Tn (ft-kips)	phi Mn (ft-kips)	Total Deflect (in)	Rotation Sway (deg)	Rotation Twist (deg)	Stress Ratio
0.00	-51.79	-44.09	-0.82	-5345.8	-0.02	5345.81	5397.55	2698.78	12826.5	6367.63	0.00	0.000	0.000	0.645
5.00	-49.86	-43.49	-0.82	-5125.3	-0.01	5125.38	5344.66	2672.33	12495.2	6203.15	0.09	-0.168	0.000	0.632
10.00	-47.97	-42.90	-0.82	-4907.9	-0.01	4907.91	5290.67	2645.34	12165.4	6039.43	0.36	-0.336	0.000	0.619
15.00	-46.15	-42.27	-0.82	-4693.3	-0.01	4693.39	5235.58	2617.79	11837.2	5876.53	0.80	-0.505	0.000	0.605
17.00	-45.40	-42.05	-0.82	-4608.8	-0.01	4608.84	5213.23	2606.61	11706.5	5811.61	1.03	-0.573	0.000	0.600
17.00	-45.40	-42.05	-0.82	-4608.8	-0.01	4608.84	5213.23	2606.61	11706.5	5811.61	1.03	-0.573	0.000	0.600
20.00	-44.26	-41.72	-0.82	-4482.7	-0.01	4482.70	5179.37	2589.69	11510.9	5714.52	1.42	-0.675	0.000	0.793
25.00	-42.41	-41.10	-0.82	-4274.1	-0.01	4274.11	5122.07	2561.03	11186.5	5553.45	2.25	-0.901	0.000	0.778
30.00	-40.60	-40.45	-0.82	-4068.6	-0.02	4068.61	5063.65	2531.83	10864.1	5393.40	3.31	-1.127	0.000	0.763
35.00	-38.83	-39.78	-0.82	-3866.3	-0.02	3866.37	5004.13	2502.07	10543.8	5234.42	4.62	-1.355	0.000	0.747
40.00	-37.08	-39.08	-0.82	-3667.4	-0.02	3667.49	4943.51	2471.75	10225.9	5076.58	6.16	-1.582	0.000	0.730
45.00	-35.43	-38.31	-0.82	-3472.0	-0.02	3472.09	4881.77	2440.89	9910.40	4919.94	7.94	-1.810	0.000	0.713
45.92	-35.07	-38.23	-0.82	-3436.9	-0.02	3436.97	4870.34	2435.17	9852.83	4891.36	8.29	-1.853	0.000	0.710
50.00	-32.75	-37.56	-0.82	-3280.8	-0.02	3280.89	4818.94	2409.47	9597.43	4764.57	9.95	-2.040	0.000	0.696
52.00	-31.62	-37.23	-0.81	-3205.7	-0.02	3205.77	4793.49	2396.75	9472.99	4702.79	10.83	-2.133	0.000	0.689
53.00	-31.04	-37.08	-0.81	-3168.5	-0.02	3168.54	3921.66	1960.83	7862.59	3903.32	11.28	-2.180	0.000	0.820
55.00	-30.40	-36.83	-0.81	-3094.3	-0.02	3094.38	3903.31	1951.65	7765.73	3855.23	12.21	-2.272	0.000	0.811
60.00	-28.94	-36.08	-0.82	-2910.2	-0.02	2910.26	3856.65	1928.33	7524.53	3735.49	14.73	-2.525	-0.001	0.787
65.00	-27.52	-35.32	-0.82	-2729.8	-0.02	2729.88	3808.89	1904.45	7284.80	3616.48	17.51	-2.776	-0.001	0.762
70.00	-26.13	-34.55	-0.82	-2553.3	-0.03	2553.31	3760.03	1880.02	7046.68	3498.27	20.55	-3.026	-0.001	0.737
75.00	-24.76	-33.78	-0.82	-2380.5	-0.03	2380.56	3710.06	1855.03	6810.28	3380.91	23.85	-3.273	-0.001	0.711
80.00	-23.43	-33.00	-0.82	-2211.6	-0.03	2211.69	3658.99	1829.49	6575.75	3264.48	27.41	-3.519	-0.001	0.684
85.00	-22.13	-32.21	-0.82	-2046.7	-0.03	2046.70	3606.81	1803.40	6343.20	3149.03	31.22	-3.761	-0.001	0.656
90.00	-20.89	-31.41	-0.82	-1885.6	-0.03	1885.63	3553.52	1776.76	6112.76	3034.63	35.28	-3.999	-0.001	0.628
92.83	-20.19	-30.96	-0.82	-1796.6	-0.04	1796.64	3522.83	1761.42	5983.17	2970.30	37.70	-4.134	-0.001	0.611
95.00	-19.30	-30.61	-0.82	-1729.5	-0.04	1729.55	3499.13	1749.56	5884.57	2921.35	39.60	-4.237	-0.001	0.598
98.92	-17.80	-29.92	-0.82	-1609.6	-0.04	1609.67	2350.25	1175.12	3954.81	1963.33	43.15	-4.419	-0.001	0.828
100.00	-17.53	-29.79	-0.82	-1577.2	-0.04	1577.26	2343.93	1171.97	3924.64	1948.36	44.15	-4.469	-0.001	0.818
105.00	-16.56	-29.02	-0.82	-1428.3	-0.04	1428.33	2314.11	1157.05	3785.67	1879.37	48.98	-4.753	-0.001	0.768
110.00	-15.61	-28.26	-0.82	-1283.2	-0.05	1283.22	2283.18	1141.59	3647.23	1810.64	54.10	-5.027	-0.002	0.716
115.00	-14.69	-27.49	-0.82	-1141.9	-0.05	1141.93	2251.15	1125.57	3509.45	1742.24	59.50	-5.290	-0.002	0.663
120.00	-13.80	-26.73	-0.83	-1004.4	-0.05	1004.46	2218.01	1109.01	3372.44	1674.22	65.17	-5.540	-0.002	0.607
125.00	-12.98	-25.96	-0.83	-870.80	-0.06	870.80	2183.77	1091.88	3236.35	1606.66	71.09	-5.776	-0.002	0.549
126.67	-12.68	-25.72	-0.83	-827.45	-0.06	827.45	2172.08	1086.04	3191.13	1584.21	73.12	-5.853	-0.002	0.529
130.00	-11.80	-25.17	-0.83	-741.81	-0.06	741.81	2148.42	1074.21	3101.30	1539.62	77.25	-5.999	-0.002	0.488
132.00	-11.27	-24.85	-0.83	-691.39	-0.06	691.39	1502.55	751.27	2180.88	1082.68	79.78	-6.083	-0.003	0.647
135.00	-10.85	-24.42	-0.83	-616.93	-0.07	616.93	1491.20	745.60	2130.02	1057.43	83.63	-6.202	-0.003	0.592
140.00	-10.19	-23.68	-0.83	-494.85	-0.07	494.85	1471.39	735.69	2045.11	1015.28	90.24	-6.419	-0.003	0.495
145.00	-9.59	-22.95	-0.83	-376.44	-0.08	376.44	1450.46	725.23	1960.22	973.13	97.05	-6.603	-0.003	0.394
147.00	-6.92	-16.45	0.00	-330.54	0.02	330.54	1441.79	720.89	1926.30	956.30	99.82	-6.669	-0.003	0.351
150.00	-6.62	-16.02	0.00	-281.19	0.02	281.19	1428.44	714.22	1875.49	931.07	104.04	-6.756	-0.003	0.307
155.00	-6.14	-15.32	0.00	-201.07	0.01	201.07	1405.30	702.65	1791.05	889.15	111.16	-6.877	-0.003	0.231
159.00	-3.70	-8.60	0.00	-139.80	0.01	139.80	1386.00	693.00	1723.78	855.76	116.95	-6.952	-0.003	0.166
160.00	-3.62	-8.47	0.00	-131.20	0.01	131.20	1381.06	690.53	1707.02	847.43	118.40	-6.968	-0.003	0.158
165.00	-3.26	-7.79	0.00	-88.86	0.01	88.86	1355.72	677.86	1623.53	805.99	125.72	-7.034	-0.003	0.113
170.00	-2.91	-7.14	0.00	-49.89	0.00	49.89	1329.27	664.63	1540.71	764.87	133.09	-7.080	-0.003	0.068
175.00	-2.57	-6.50	0.00	-14.21	0.00	14.21	1301.71	650.86	1458.68	724.15	140.50	-7.103	-0.003	0.022
177.00	-0.18	-0.41	0.00	-1.22	0.00	1.22	1290.38	645.19	1426.13	707.99	143.47	-7.106	-0.003	0.002

Calculated Forces

Structure: CT01365-S-SBA	Code: EIA/TIA-222-G	10/13/2017
Site Name: Norwich 2 CT	Exposure: C	
Height: 180.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Page: 15
Struct Class: II		



180.00	0.00	-0.38	0.00	0.00	0.00	0.00	0.00	1273.05	636.53	1377.59	683.89	147.93	-7.106	-0.003	0.000
--------	------	-------	------	------	------	------	------	---------	--------	---------	--------	--------	--------	--------	-------


Wind Loading - Shaft

Structure: CT01365-S-SBA	Code: EIA/TIA-222-G	10/13/2017
Site Name: Norwich 2 CT	Exposure: C	
Height: 180.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II



Load Case: 0.9D + 1.6W 105 mph Wind

Dead Load Factor 0.90
Wind Load Factor 1.60



Iterations 26

Elev (ft)	Description	Kzt	Kz	qz (psf)	qzGh (psf)	C (mph-ft)	Cf	Ice Thick (in)	Tributary (ft)	Aa (sf)	CfAa (sf)	Wind Force X (lb)	Dead Load Ice (lb)	Tot Dead Load (lb)
0.00	RB1	1.00	0.85	22.791	25.07	477.06	0.750	0.000	0.00	0.000	0.00	0.0	0.0	0.0
5.00		1.00	0.85	22.791	25.07	469.45	0.750	0.000	5.00	24.444	18.33	735.4	0.0	1221.6
10.00		1.00	0.85	22.791	25.07	461.84	0.750	0.000	5.00	24.051	18.04	723.5	0.0	1201.8
15.00		1.00	0.85	22.791	25.07	454.23	0.750	0.000	5.00	23.658	17.74	711.7	0.0	1182.1
17.00	RT1	1.00	0.87	23.369	25.71	456.87	0.750	0.000	2.00	9.353	7.01	288.5	0.0	467.3
20.00		1.00	0.90	24.182	26.60	460.05	0.750	0.000	3.00	13.912	10.43	444.1	0.0	695.0
25.00		1.00	0.95	25.345	27.88	462.97	0.750	0.000	5.00	22.872	17.15	765.2	0.0	1142.5
30.00		1.00	0.98	26.337	28.97	463.76	0.750	0.000	5.00	22.479	16.86	781.5	0.0	1122.7
35.00		1.00	1.01	27.206	29.93	463.03	0.750	0.000	5.00	22.086	16.56	793.1	0.0	1102.9
40.00		1.00	1.04	27.981	30.78	461.16	0.750	0.000	5.00	21.693	16.27	801.2	0.0	1083.1
45.00		1.00	1.07	28.684	31.55	458.37	0.750	0.000	5.00	21.300	15.97	806.5	0.0	1063.3
45.92	Bot - Section 2	1.00	1.07	28.806	31.69	457.78	0.750	0.000	0.92	3.862	2.90	146.9	0.0	192.8
50.00		1.00	1.09	29.327	32.26	454.85	0.750	0.000	4.08	17.305	12.98	669.9	0.0	1591.3
52.00	Appurtenance(s)	1.00	1.10	29.570	32.53	453.27	0.750	0.000	2.00	8.380	6.29	327.1	0.0	770.5
53.00	Top - Section 1	1.00	1.11	29.689	32.66	452.44	0.750	0.000	1.00	4.167	3.12	163.3	0.0	383.0
55.00		1.00	1.12	29.922	32.91	457.79	0.750	0.000	2.00	8.286	6.21	327.3	0.0	354.5
60.00		1.00	1.14	30.475	33.52	453.21	0.750	0.000	5.00	20.440	15.33	822.2	0.0	874.4
65.00		1.00	1.16	30.993	34.09	448.17	0.750	0.000	5.00	20.047	15.03	820.1	0.0	857.5
70.00		1.00	1.17	31.480	34.63	442.74	0.750	0.000	5.00	19.654	14.74	816.7	0.0	840.5
75.00		1.00	1.19	31.941	35.13	436.96	0.750	0.000	5.00	19.261	14.45	812.1	0.0	823.6
80.00		1.00	1.21	32.377	35.62	430.87	0.750	0.000	5.00	18.868	14.15	806.4	0.0	806.7
85.00		1.00	1.22	32.793	36.07	424.50	0.750	0.000	5.00	18.475	13.86	799.7	0.0	789.7
90.00		1.00	1.24	33.190	36.51	417.88	0.750	0.000	5.00	18.082	13.56	792.2	0.0	772.8
92.83	Bot - Section 3	1.00	1.25	33.408	36.75	414.03	0.750	0.000	2.83	10.072	7.55	444.2	0.0	430.4
95.00		1.00	1.25	33.570	36.93	411.03	0.750	0.000	2.17	7.720	5.79	342.1	0.0	573.2
98.92	Top - Section 2	1.00	1.26	33.857	37.24	405.52	0.750	0.000	3.92	13.769	10.33	615.3	0.0	1022.1
100.00		1.00	1.27	33.935	37.33	409.61	0.750	0.000	1.08	3.766	2.82	168.7	0.0	120.8
105.00		1.00	1.28	34.285	37.71	402.39	0.750	0.000	5.00	17.142	12.86	775.8	0.0	550.0
110.00		1.00	1.29	34.623	38.08	394.99	0.750	0.000	5.00	16.749	12.56	765.4	0.0	537.3
115.00		1.00	1.30	34.948	38.44	387.42	0.750	0.000	5.00	16.356	12.27	754.5	0.0	524.6
120.00		1.00	1.32	35.263	38.79	379.69	0.750	0.000	5.00	15.963	11.97	743.0	0.0	511.9
125.00		1.00	1.33	35.567	39.12	371.83	0.750	0.000	5.00	15.570	11.68	731.0	0.0	499.2
126.67	Bot - Section 4	1.00	1.33	35.667	39.23	369.17	0.750	0.000	1.67	5.113	3.83	240.7	0.0	163.9
130.00		1.00	1.34	35.862	39.45	363.82	0.750	0.000	3.33	10.188	7.64	482.3	0.0	577.6
132.00	Top - Section 3	1.00	1.34	35.978	39.58	360.58	0.750	0.000	2.00	6.045	4.53	287.1	0.0	342.6
135.00		1.00	1.35	36.148	39.76	360.22	0.750	0.000	3.00	8.925	6.69	425.8	0.0	223.3
140.00		1.00	1.36	36.426	40.07	351.99	0.750	0.000	5.00	14.577	10.93	700.9	0.0	364.7
145.00		1.00	1.37	36.696	40.37	343.64	0.750	0.000	5.00	14.184	10.64	687.1	0.0	354.8
147.00	Appurtenance(s)	1.00	1.37	36.802	40.48	340.26	0.750	0.000	2.00	5.564	4.17	270.3	0.0	139.2
150.00		1.00	1.38	36.959	40.65	335.17	0.750	0.000	3.00	8.227	6.17	401.4	0.0	205.8
155.00		1.00	1.39	37.215	40.94	326.61	0.750	0.000	5.00	13.398	10.05	658.2	0.0	335.0
159.00	Appurtenance(s)	1.00	1.40	37.415	41.16	319.69	0.750	0.000	4.00	10.436	7.83	515.4	0.0	260.9
160.00		1.00	1.40	37.464	41.21	317.95	0.750	0.000	1.00	2.570	1.93	127.1	0.0	64.2
165.00		1.00	1.41	37.708	41.48	309.20	0.750	0.000	5.00	12.612	9.46	627.8	0.0	315.2
170.00		1.00	1.42	37.946	41.74	300.35	0.750	0.000	5.00	12.219	9.16	612.0	0.0	305.3
175.00		1.00	1.42	38.178	42.00	291.42	0.750	0.000	5.00	11.826	8.87	596.0	0.0	295.4
177.00	Appurtenance(s)	1.00	1.43	38.269	42.10	287.83	0.750	0.000	2.00	4.620	3.47	233.4	0.0	115.4

Wind Loading - Shaft

Structure: CT01365-S-SBA	Code: EIA/TIA-222-G	10/13/2017
Site Name: Norwich 2 CT	Exposure: C	
Height: 180.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II
		Page: 17



180.00 Appurtenance(s)	1.00	1.43	38.405	42.25	282.41	0.750	0.000	3.00	6.813	5.11	345.4	0.0	170.1
							Totals:	180.00			26,705.2		28,342.7

Discrete Appurtenance Forces

Structure: CT01365-S-SBA	Code: EIA/TIA-222-G	10/13/2017
Site Name: Norwich 2 CT	Exposure: C	
Height: 180.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II



Page: 18

Load Case: 0.9D + 1.6W 105 mph Wind

Dead Load Factor 0.90
Wind Load Factor 1.60



Iterations 26

No.	Elev (ft)	Description	Qty	qz (psf)	qzGh (psf)	CaAa x Ka	Ka	Total CaAa (sf)	Dead Load (lb)	Horiz Ecc (ft)	Vert Ecc (ft)	Wind FX (lb)	Mom Y (lb-ft)	Mom Z (lb-ft)
1	180.00	Lightning Rod	1	38.405	42.245	1.00	1.00	0.50	4.50	0.000	0.000	33.80	0.00	0.00
2	177.00	1900MHz RRUs	3	38.269	42.096	0.70	0.80	8.03	118.80	0.000	0.000	540.56	0.00	0.00
3	177.00	APXVSPP18-C-A20	3	38.269	42.096	0.66	0.80	15.98	153.90	0.000	0.000	1076.03	0.00	0.00
4	177.00	APXVTM14-C-120	3	38.269	42.096	0.63	0.80	12.02	151.20	0.000	0.000	809.64	0.00	0.00
5	177.00	TD-RRH8x20-25	3	38.269	42.096	0.55	0.80	6.71	189.00	0.000	0.000	451.73	0.00	0.00
6	177.00	800 MHz RRUs	3	38.269	42.096	0.74	0.80	5.50	143.10	0.000	0.000	370.31	0.00	0.00
7	177.00	ALU 800MHz External	3	38.269	42.096	0.55	0.80	1.29	23.76	0.000	0.000	87.00	0.00	0.00
8	177.00	ACU-A20-N	4	38.269	42.096	0.63	0.80	0.35	3.60	0.000	0.000	23.84	0.00	0.00
9	177.00	Platform w/ Hand Rail	1	38.269	42.096	1.00	1.00	32.00	1440.00	0.000	0.000	2155.32	0.00	0.00
10	159.00	BXA-171085-8BF-EDIN-2	3	37.415	41.156	0.67	0.80	5.93	28.35	0.000	0.000	390.30	0.00	0.00
11	159.00	BXA-80080/4CF	3	37.415	41.156	0.61	0.80	8.76	38.61	0.000	0.000	576.53	0.00	0.00
12	159.00	B25 RRH4x30	3	37.415	41.156	0.65	0.80	4.16	137.70	0.000	0.000	273.95	0.00	0.00
13	159.00	SBNHH-1D65B	6	37.415	41.156	0.66	0.80	32.19	219.24	0.000	0.000	2119.77	0.00	0.00
14	159.00	Low Profile	1	37.415	41.156	1.00	1.00	22.00	1350.00	0.000	0.000	1448.70	0.00	0.00
15	159.00	DB-T1-6Z-8AB-OZ	2	37.415	41.156	0.57	0.80	5.45	34.02	0.000	0.000	359.07	0.00	0.00
16	159.00	B25 RRH4x30	3	37.415	41.156	0.65	0.80	4.16	137.70	0.000	0.000	273.95	0.00	0.00
17	159.00	RRH 4X45-PCS	3	37.415	41.156	0.78	0.80	6.37	162.00	0.000	0.000	419.72	0.00	0.00
18	147.00	RRUS A2	3	36.802	40.482	0.49	0.80	2.73	59.40	0.000	0.000	176.66	0.00	0.00
19	147.00	HPA-65R-BUU-H6	1	36.802	40.482	0.80	0.80	7.73	45.90	2.383	0.000	500.55	745.52	0.00
20	147.00	HPA-65R-BUU-H8	2	36.802	40.482	0.71	0.80	18.50	122.40	0.000	0.000	1198.55	0.00	0.00
21	147.00	860 10025 RET	12	36.802	40.482	0.74	0.80	1.59	12.96	0.000	0.000	102.97	0.00	0.00
22	147.00	RRUS 12	3	36.802	40.482	0.56	0.80	4.56	156.60	0.000	0.000	295.06	0.00	0.00
23	147.00	LGP21401	6	36.802	40.482	0.54	0.80	4.15	76.14	0.000	0.000	268.71	0.00	0.00
24	147.00	RRUS-11	6	36.802	40.482	0.54	0.80	8.10	275.40	0.000	0.000	524.93	0.00	0.00
25	147.00	LGP21901 Diplexer	6	36.802	40.482	0.54	0.80	0.87	29.70	0.000	0.000	56.24	0.00	0.00
26	147.00	DC6-48-60-18-8F("Squid")	1	36.802	40.482	1.00	1.00	0.92	28.62	2.383	0.000	59.59	88.75	0.00
27	147.00	Low Profile	1	36.802	40.482	1.00	1.00	22.00	1350.00	0.000	0.000	1424.97	0.00	0.00
28	147.00	7770.00	6	36.802	40.482	0.60	0.80	19.77	189.00	0.000	0.000	1280.76	0.00	0.00
29	52.00	GPS	1	29.570	32.527	0.80	0.80	0.09	0.18	3.055	0.000	4.58	8.75	0.00

Totals: 6,681.78 17,303.78

Total Applied Force Summary

Structure: CT01365-S-SBA	Code: EIA/TIA-222-G	10/13/2017
Site Name: Norwich 2 CT	Exposure: C	
Height: 180.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II



Page: 19

Load Case: 0.9D + 1.6W 105 mph Wind

Dead Load Factor 0.90
Wind Load Factor 1.60



Iterations 26

Elev (ft)	Description	Lateral FX (-) (lb)	Axial FY (-) (lb)	Torsion MY (lb-ft)	Moment MZ (lb-ft)
0.00		0.00	0.00	0.00	0.00
5.00		735.36	1347.01	0.00	0.00
10.00		723.54	1327.22	0.00	0.00
15.00		711.72	1307.43	0.00	0.00
17.00		288.51	517.43	0.00	0.00
20.00		444.07	770.21	0.00	0.00
25.00		765.19	1267.85	0.00	0.00
30.00		781.47	1248.06	0.00	0.00
35.00		793.13	1228.27	0.00	0.00
40.00		801.23	1208.48	0.00	0.00
45.00		806.47	1188.69	0.00	0.00
45.92		146.86	215.78	0.00	0.00
50.00		669.90	1693.65	0.00	0.00
52.00	(1) attachments	331.68	820.78	8.75	0.00
53.00		163.28	407.95	0.00	0.00
55.00		327.26	404.38	0.00	0.00
60.00		822.22	999.09	0.00	0.00
65.00		820.11	982.14	0.00	0.00
70.00		816.68	965.20	0.00	0.00
75.00		812.06	948.25	0.00	0.00
80.00		806.37	931.31	0.00	0.00
85.00		799.72	914.37	0.00	0.00
90.00		792.19	897.42	0.00	0.00
92.83		444.15	501.02	0.00	0.00
95.00		342.11	627.23	0.00	0.00
98.92		615.35	1119.71	0.00	0.00
100.00		168.69	147.84	0.00	0.00
105.00		775.77	674.63	0.00	0.00
110.00		765.45	661.93	0.00	0.00
115.00		754.51	649.24	0.00	0.00
120.00		743.01	636.54	0.00	0.00
125.00		730.98	623.84	0.00	0.00
126.67		240.71	205.54	0.00	0.00
130.00		482.28	660.16	0.00	0.00
132.00		287.09	392.30	0.00	0.00
135.00		425.85	297.60	0.00	0.00
140.00		700.89	488.64	0.00	0.00
145.00		687.05	478.75	0.00	0.00
147.00	(47) attachments	6159.27	2534.85	834.27	0.00
150.00		401.38	244.11	0.00	0.00
155.00		658.16	398.93	0.00	0.00
159.00	(24) attachments	6377.37	2419.64	0.00	0.00
160.00		127.07	66.61	0.00	0.00
165.00		627.76	327.12	0.00	0.00
170.00		612.03	317.22	0.00	0.00
175.00		595.98	307.33	0.00	0.00
177.00	(23) attachments	5747.83	2343.52	0.00	0.00

Total Applied Force Summary

Structure: CT01365-S-SBA	Code: EIA/TIA-222-G	10/13/2017	
Site Name: Norwich 2 CT	Exposure: C		
Height: 180.00 (ft)	Crest Height: 0.00		
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil		
Gh: 1.1	Topography: 1	Struct Class: II	Page: 20



180.00	(1) attachments	379.17	174.64	0.00	0.00
	Totals:	44,008.94	38,889.90	843.02	0.00

Linear Appurtenance Segment Forces (Factored)

Structure: CT01365-S-SBA	Code: EIA/TIA-222-G	10/13/2017
Site Name: Norwich 2 CT	Exposure: C	
Height: 180.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II




Page: 21

Load Case: 0.9D + 1.6W 105 mph Wind

Dead Load Factor 0.90

Wind Load Factor 1.60



Iterations 26

Top Elev (ft)	Description	Wind Exposed	Length (ft)	Ca	Exposed Width (in)	Area (sqft)	CaAa (sqft)	Ra	Cf Adjust Factor	qz (psf)	F X (lb)	Dead Load (lb)
5.00	1/2" Coax	Yes	5.00	0.000	0.65	0.27	0.00	0.011	0.000	22.791	0.00	0.72
10.00	1/2" Coax	Yes	5.00	0.000	0.65	0.27	0.00	0.011	0.000	22.791	0.00	0.72
15.00	1/2" Coax	Yes	5.00	0.000	0.65	0.27	0.00	0.011	0.000	22.791	0.00	0.72
17.00	1/2" Coax	Yes	2.00	0.000	0.65	0.11	0.00	0.012	0.000	23.369	0.00	0.29
20.00	1/2" Coax	Yes	3.00	0.000	0.65	0.16	0.00	0.012	0.000	24.182	0.00	0.43
25.00	1/2" Coax	Yes	5.00	0.000	0.65	0.27	0.00	0.012	0.000	25.345	0.00	0.72
30.00	1/2" Coax	Yes	5.00	0.000	0.65	0.27	0.00	0.012	0.000	26.337	0.00	0.72
35.00	1/2" Coax	Yes	5.00	0.000	0.65	0.27	0.00	0.012	0.000	27.206	0.00	0.72
40.00	1/2" Coax	Yes	5.00	0.000	0.65	0.27	0.00	0.012	0.000	27.981	0.00	0.72
45.00	1/2" Coax	Yes	5.00	0.000	0.65	0.27	0.00	0.013	0.000	28.684	0.00	0.72
45.92	1/2" Coax	Yes	0.92	0.000	0.65	0.05	0.00	0.013	0.000	28.806	0.00	0.13
50.00	1/2" Coax	Yes	4.08	0.000	0.65	0.22	0.00	0.013	0.000	29.327	0.00	0.59
52.00	1/2" Coax	Yes	2.00	0.000	0.65	0.11	0.00	0.013	0.000	29.570	0.00	0.29
Totals:											0.0	7.5

Calculated Forces

Structure: CT01365-S-SBA	Code: EIA/TIA-222-G	10/13/2017
Site Name: Norwich 2 CT	Exposure: C	
Height: 180.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II




Page: 22

Load Case: 0.9D + 1.6W 105 mph Wind

Iterations 26

Dead Load Factor 0.90
Wind Load Factor 1.60



Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (-) (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	phi Pn (kips)	phi Vn (kips)	phi Tn (ft-kips)	phi Mn (ft-kips)	Total Deflect (in)	Rotation Sway (deg)	Rotation Twist (deg)	Stress Ratio
0.00	-38.82	-44.07	-0.82	-5293.1	-0.01	5293.13	5397.55	2698.78	12826.5	6367.63	0.00	0.000	0.000	0.637
5.00	-37.35	-43.44	-0.82	-5072.8	-0.01	5072.80	5344.66	2672.33	12495.2	6203.15	0.09	-0.166	0.000	0.624
10.00	-35.90	-42.81	-0.82	-4855.6	-0.01	4855.61	5290.67	2645.34	12165.4	6039.43	0.35	-0.333	0.000	0.610
15.00	-34.52	-42.16	-0.82	-4641.5	-0.01	4641.55	5235.58	2617.79	11837.2	5876.53	0.79	-0.499	0.000	0.597
17.00	-33.94	-41.92	-0.82	-4557.2	-0.01	4557.23	5213.23	2606.61	11706.5	5811.61	1.02	-0.567	0.000	0.592
17.00	-33.94	-41.92	-0.82	-4557.2	-0.01	4557.23	5213.23	2606.61	11706.5	5811.61	1.02	-0.567	0.000	0.592
20.00	-33.06	-41.56	-0.82	-4431.4	-0.01	4431.48	5179.37	2589.69	11510.9	5714.52	1.40	-0.668	0.000	0.782
25.00	-31.64	-40.90	-0.82	-4223.6	-0.01	4223.68	5122.07	2561.03	11186.5	5553.45	2.22	-0.891	0.000	0.767
30.00	-30.25	-40.22	-0.82	-4019.1	-0.01	4019.17	5063.65	2531.83	10864.1	5393.40	3.28	-1.115	0.000	0.751
35.00	-28.88	-39.51	-0.82	-3818.0	-0.01	3818.09	5004.13	2502.07	10543.8	5234.42	4.57	-1.339	0.000	0.735
40.00	-27.54	-38.79	-0.82	-3620.5	-0.01	3620.53	4943.51	2471.75	10225.9	5076.58	6.09	-1.564	0.000	0.719
45.00	-26.29	-38.01	-0.82	-3426.5	-0.01	3426.59	4881.77	2440.89	9910.40	4919.94	7.85	-1.789	0.000	0.702
45.92	-26.00	-37.91	-0.82	-3391.7	-0.01	3391.75	4870.34	2435.17	9852.83	4891.36	8.20	-1.831	0.000	0.699
50.00	-24.24	-37.24	-0.82	-3236.9	-0.01	3236.97	4818.94	2409.47	9597.43	4764.57	9.84	-2.016	0.000	0.685
52.00	-23.39	-36.91	-0.81	-3162.4	-0.01	3162.49	4793.49	2396.75	9472.99	4702.79	10.71	-2.107	0.000	0.678
53.00	-22.95	-36.75	-0.82	-3125.5	-0.02	3125.59	3921.66	1960.83	7862.59	3903.32	11.15	-2.153	0.000	0.807
55.00	-22.45	-36.48	-0.82	-3052.0	-0.02	3052.08	3903.31	1951.65	7765.73	3855.23	12.08	-2.245	0.000	0.798
60.00	-21.33	-35.71	-0.82	-2869.6	-0.02	2869.68	3856.65	1928.33	7524.53	3735.49	14.56	-2.494	-0.001	0.774
65.00	-20.23	-34.93	-0.82	-2691.1	-0.02	2691.14	3808.89	1904.45	7284.80	3616.48	17.30	-2.741	-0.001	0.750
70.00	-19.16	-34.15	-0.82	-2516.4	-0.02	2516.48	3760.03	1880.02	7046.68	3498.27	20.31	-2.988	-0.001	0.725
75.00	-18.12	-33.37	-0.82	-2345.7	-0.02	2345.73	3710.06	1855.03	6810.28	3380.91	23.57	-3.232	-0.001	0.699
80.00	-17.10	-32.58	-0.82	-2178.9	-0.03	2178.90	3658.99	1829.49	6575.75	3264.48	27.08	-3.473	-0.001	0.672
85.00	-16.11	-31.79	-0.82	-2016.0	-0.03	2016.01	3606.81	1803.40	6343.20	3149.03	30.84	-3.712	-0.001	0.645
90.00	-15.17	-30.99	-0.82	-1857.0	-0.03	1857.06	3553.52	1776.76	6112.76	3034.63	34.85	-3.947	-0.001	0.617
92.83	-14.63	-30.54	-0.82	-1769.2	-0.03	1769.26	3522.83	1761.42	5983.17	2970.30	37.24	-4.080	-0.001	0.600
95.00	-13.96	-30.19	-0.82	-1703.1	-0.03	1703.10	3499.13	1749.56	5884.57	2921.35	39.11	-4.181	-0.001	0.587
98.92	-12.83	-29.52	-0.82	-1584.8	-0.03	1584.86	2350.25	1175.12	3954.81	1963.33	42.61	-4.360	-0.001	0.813
100.00	-12.61	-29.37	-0.82	-1552.8	-0.04	1552.89	2343.93	1171.97	3924.64	1948.36	43.61	-4.410	-0.001	0.803
105.00	-11.86	-28.60	-0.82	-1406.0	-0.04	1406.02	2314.11	1157.05	3785.67	1879.37	48.37	-4.689	-0.001	0.754
110.00	-11.14	-27.84	-0.82	-1263.0	-0.04	1263.01	2283.18	1141.59	3647.23	1810.64	53.42	-4.958	-0.002	0.703
115.00	-10.44	-27.07	-0.83	-1123.8	-0.05	1123.82	2251.15	1125.57	3509.45	1742.24	58.75	-5.218	-0.002	0.650
120.00	-9.77	-26.32	-0.83	-988.45	-0.05	988.45	2218.01	1109.01	3372.44	1674.22	64.34	-5.464	-0.002	0.595
125.00	-9.15	-25.55	-0.83	-856.87	-0.05	856.87	2183.77	1091.88	3236.35	1606.66	70.18	-5.696	-0.002	0.538
126.67	-8.92	-25.31	-0.83	-814.20	-0.06	814.20	2172.08	1086.04	3191.13	1584.21	72.18	-5.772	-0.002	0.519
130.00	-8.26	-24.78	-0.83	-729.92	-0.06	729.92	2148.42	1074.21	3101.30	1539.62	76.25	-5.915	-0.002	0.478
132.00	-7.86	-24.47	-0.83	-680.28	-0.06	680.28	1502.55	751.27	2180.88	1082.68	78.75	-5.998	-0.003	0.635
135.00	-7.54	-24.03	-0.83	-606.97	-0.06	606.97	1491.20	745.60	2130.02	1057.43	82.55	-6.115	-0.003	0.580
140.00	-7.05	-23.31	-0.83	-486.80	-0.07	486.80	1471.39	735.69	2045.11	1015.28	89.06	-6.328	-0.003	0.485
145.00	-6.60	-22.59	-0.83	-370.26	-0.07	370.26	1450.46	725.23	1960.22	973.13	95.77	-6.510	-0.003	0.386
147.00	-4.76	-16.18	0.00	-325.09	0.02	325.09	1441.79	720.89	1926.30	956.30	98.51	-6.574	-0.003	0.344
150.00	-4.54	-15.77	0.00	-276.54	0.02	276.54	1428.44	714.22	1875.49	931.07	102.66	-6.660	-0.003	0.301
155.00	-4.20	-15.07	0.00	-197.71	0.01	197.71	1405.30	702.65	1791.05	889.15	109.69	-6.779	-0.003	0.226
159.00	-2.54	-8.45	0.00	-137.43	0.01	137.43	1386.00	693.00	1723.78	855.76	115.39	-6.853	-0.003	0.163
160.00	-2.49	-8.32	0.00	-128.97	0.01	128.97	1381.06	690.53	1707.02	847.43	116.82	-6.868	-0.003	0.154
165.00	-2.23	-7.66	0.00	-87.36	0.01	87.36	1355.72	677.86	1623.53	805.99	124.04	-6.933	-0.003	0.110
170.00	-1.99	-7.02	0.00	-49.05	0.00	49.05	1329.27	664.63	1540.71	764.87	131.31	-6.978	-0.003	0.066
175.00	-1.75	-6.39	0.00	-13.97	0.00	13.97	1301.71	650.86	1458.68	724.15	138.61	-7.001	-0.003	0.021
177.00	-0.13	-0.40	0.00	-1.19	0.00	1.19	1290.38	645.19	1426.13	707.99	141.54	-7.004	-0.003	0.002

Calculated Forces

Structure: CT01365-S-SBA	Code: EIA/TIA-222-G	10/13/2017
Site Name: Norwich 2 CT	Exposure: C	
Height: 180.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II
		Page: 23



180.00	0.00	-0.38	0.00	0.00	0.00	0.00	0.00	1273.05	636.53	1377.59	683.89	145.93	-7.004	-0.003	0.000
--------	------	-------	------	------	------	------	------	---------	--------	---------	--------	--------	--------	--------	-------

Wind Loading - Shaft


Structure: CT01365-S-SBA	Code: EIA/TIA-222-G	10/13/2017
Site Name: Norwich 2 CT	Exposure: C	
Height: 180.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II



Load Case: 1.2D + 1.0Di + 1.0Wi 50 mph Wind

Iterations 25

Dead Load Factor 1.20
Wind Load Factor 1.00



Elev (ft)	Description	Kzt	Kz	qz (psf)	qzGh (psf)	C (mph-ft)	Cf	Ice Thick (in)	Tributary (ft)	Aa (sf)	CfAa (sf)	Wind Force X (lb)	Dead Load Ice (lb)	Tot Dead Load (lb)
0.00	RB1	1.00	0.85	5.168	5.68	0.00	1.200	0.000	0.00	0.000	0.00	0.0	0.0	0.0
5.00		1.00	0.85	5.168	5.68	0.00	1.200	1.242	5.00	25.479	30.57	173.8	457.9	2086.7
10.00		1.00	0.85	5.168	5.68	0.00	1.200	1.331	5.00	25.160	30.19	171.6	483.7	2086.2
15.00		1.00	0.85	5.168	5.68	0.00	1.200	1.386	5.00	24.813	29.78	169.3	496.1	2072.2
17.00	RT1	1.00	0.87	5.299	5.83	0.00	1.200	1.404	2.00	9.821	11.79	68.7	199.7	822.7
20.00		1.00	0.90	5.483	6.03	0.00	1.200	1.427	3.00	14.625	17.55	105.9	301.5	1228.2
25.00		1.00	0.95	5.747	6.32	0.00	1.200	1.459	5.00	24.088	28.91	182.7	505.7	2029.0
30.00		1.00	0.98	5.972	6.57	0.00	1.200	1.486	5.00	23.717	28.46	187.0	506.5	2003.5
35.00		1.00	1.01	6.169	6.79	0.00	1.200	1.509	5.00	23.343	28.01	190.1	505.8	1976.3
40.00		1.00	1.04	6.345	6.98	0.00	1.200	1.529	5.00	22.967	27.56	192.4	503.8	1948.0
45.00		1.00	1.07	6.504	7.15	0.00	1.200	1.547	5.00	22.589	27.11	193.9	500.9	1918.7
45.92	Bot - Section 2	1.00	1.07	6.532	7.19	0.00	1.200	1.550	0.92	4.099	4.92	35.3	91.7	348.8
50.00		1.00	1.09	6.650	7.32	0.00	1.200	1.564	4.08	18.369	22.04	161.2	412.1	2533.8
52.00	Appurtenance(s)	1.00	1.10	6.705	7.38	0.00	1.200	1.570	2.00	8.903	10.68	78.8	201.2	1228.5
53.00	Top - Section 1	1.00	1.11	6.732	7.41	0.00	1.200	1.573	1.00	4.429	5.31	39.4	100.4	611.1
55.00		1.00	1.12	6.785	7.46	0.00	1.200	1.579	2.00	8.812	10.57	78.9	200.2	672.9
60.00		1.00	1.14	6.910	7.60	0.00	1.200	1.592	5.00	21.767	26.12	198.5	495.6	1661.5
65.00		1.00	1.16	7.028	7.73	0.00	1.200	1.605	5.00	21.384	25.66	198.4	490.3	1633.6
70.00		1.00	1.17	7.138	7.85	0.00	1.200	1.617	5.00	21.001	25.20	197.9	484.6	1605.4
75.00		1.00	1.19	7.243	7.97	0.00	1.200	1.628	5.00	20.618	24.74	197.1	478.6	1576.7
80.00		1.00	1.21	7.342	8.08	0.00	1.200	1.639	5.00	20.233	24.28	196.1	472.2	1547.7
85.00		1.00	1.22	7.436	8.18	0.00	1.200	1.649	5.00	19.849	23.82	194.8	465.5	1518.5
90.00		1.00	1.24	7.526	8.28	0.00	1.200	1.658	5.00	19.464	23.36	193.4	458.6	1488.9
92.83	Bot - Section 3	1.00	1.25	7.575	8.33	0.00	1.200	1.663	2.83	10.857	13.03	108.6	257.6	831.4
95.00		1.00	1.25	7.612	8.37	0.00	1.200	1.667	2.17	8.322	9.99	83.6	198.2	962.5
98.92	Top - Section 2	1.00	1.26	7.677	8.45	0.00	1.200	1.674	3.92	14.862	17.83	150.6	353.7	1716.5
100.00		1.00	1.27	7.695	8.46	0.00	1.200	1.676	1.08	4.068	4.88	41.3	97.5	258.6
105.00		1.00	1.28	7.774	8.55	0.00	1.200	1.684	5.00	18.545	22.25	190.3	442.4	1175.7
110.00		1.00	1.29	7.851	8.64	0.00	1.200	1.692	5.00	18.159	21.79	188.2	434.7	1151.0
115.00		1.00	1.30	7.925	8.72	0.00	1.200	1.699	5.00	17.772	21.33	185.9	426.7	1126.2
120.00		1.00	1.32	7.996	8.80	0.00	1.200	1.707	5.00	17.385	20.86	183.5	418.6	1101.2
125.00		1.00	1.33	8.065	8.87	0.00	1.200	1.714	5.00	16.998	20.40	181.0	410.4	1076.0
126.67	Bot - Section 4	1.00	1.33	8.088	8.90	0.00	1.200	1.716	1.67	5.590	6.71	59.7	136.1	354.7
130.00		1.00	1.34	8.132	8.95	0.00	1.200	1.720	3.33	11.143	13.37	119.6	270.9	1041.0
132.00	Top - Section 3	1.00	1.34	8.158	8.97	0.00	1.200	1.723	2.00	6.620	7.94	71.3	161.6	618.5
135.00		1.00	1.35	8.197	9.02	0.00	1.200	1.727	3.00	9.787	11.74	105.9	238.7	536.5
140.00		1.00	1.36	8.260	9.09	0.00	1.200	1.733	5.00	16.021	19.23	174.7	389.7	876.0
145.00		1.00	1.37	8.321	9.15	0.00	1.200	1.739	5.00	15.633	18.76	171.7	380.9	854.0
147.00	Appurtenance(s)	1.00	1.37	8.345	9.18	0.00	1.200	1.742	2.00	6.144	7.37	67.7	151.0	336.5
150.00		1.00	1.38	8.381	9.22	0.00	1.200	1.745	3.00	9.100	10.92	100.7	223.3	497.6
155.00		1.00	1.39	8.439	9.28	0.00	1.200	1.751	5.00	14.857	17.83	165.5	363.1	809.8
159.00	Appurtenance(s)	1.00	1.40	8.484	9.33	0.00	1.200	1.755	4.00	11.606	13.93	130.0	284.7	632.6
160.00		1.00	1.40	8.495	9.34	0.00	1.200	1.757	1.00	2.862	3.43	32.1	70.8	156.5
165.00		1.00	1.41	8.551	9.41	0.00	1.200	1.762	5.00	14.080	16.90	158.9	344.9	765.2
170.00		1.00	1.42	8.604	9.46	0.00	1.200	1.767	5.00	13.692	16.43	155.5	335.7	742.8
175.00		1.00	1.42	8.657	9.52	0.00	1.200	1.772	5.00	13.303	15.96	152.0	326.3	720.3
177.00	Appurtenance(s)	1.00	1.43	8.678	9.55	0.00	1.200	1.774	2.00	5.212	6.25	59.7	129.0	282.9

Wind Loading - Shaft

Structure: CT01365-S-SBA	Code: EIA/TIA-222-G	10/13/2017
Site Name: Norwich 2 CT	Exposure: C	
Height: 180.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II
		Page: 25



180.00	Appurtenance(s)	1.00	1.43	8.709	9.58	0.00	1.200	1.777	3.00	7.701	9.24	88.5	190.1	417.0
Totals:										180.00	6,531.7	53,639.8		

Discrete Appurtenance Forces

Structure: CT01365-S-SBA	Code: EIA/TIA-222-G	10/13/2017
Site Name: Norwich 2 CT	Exposure: C	
Height: 180.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II



Page: 26

Load Case: 1.2D + 1.0Di + 1.0Wi 50 mph Wind

Dead Load Factor 1.20
Wind Load Factor 1.00



Iterations 25

No.	Elev (ft)	Description	Qty	qz (psf)	qzGh (psf)	CaAa x Ka	Ka	Total CaAa (sf)	Dead Load (lb)	Horiz Ecc (ft)	Vert Ecc (ft)	Wind FX (lb)	Mom Y (lb-ft)	Mom Z (lb-ft)
1	180.00	Lightning Rod	1	8.709	9.579	1.00	1.00	2.28	21.33	0.000	0.000	21.82	0.00	0.00
2	177.00	1900MHz RRUs	3	8.678	9.546	0.70	0.80	11.01	397.76	0.000	0.000	105.10	0.00	0.00
3	177.00	APXVSPP18-C-A20	3	8.678	9.546	0.66	0.80	21.63	583.91	0.000	0.000	206.51	0.00	0.00
4	177.00	APXVTM14-C-120	3	8.678	9.546	0.63	0.80	14.17	692.52	0.000	0.000	135.25	0.00	0.00
5	177.00	TD-RRH8x20-25	3	8.678	9.546	0.55	0.80	8.08	590.09	0.000	0.000	77.11	0.00	0.00
6	177.00	800 MHz RRUs	3	8.678	9.546	0.74	0.80	8.07	353.08	0.000	0.000	76.99	0.00	0.00
7	177.00	ALU 800MHz External	3	8.678	9.546	0.55	0.80	2.38	70.49	0.000	0.000	22.73	0.00	0.00
8	177.00	ACU-A20-N	4	8.678	9.546	0.63	0.80	1.12	17.07	0.000	0.000	10.66	0.00	0.00
9	177.00	Platform w/ Hand Rail	1	8.678	9.546	1.00	1.00	60.39	3454.89	0.000	0.000	576.45	0.00	0.00
10	159.00	BXA-171085-8BF-EDIN-2	3	8.484	9.333	0.67	0.80	9.29	179.48	0.000	0.000	86.70	0.00	0.00
11	159.00	BXA-80080/4CF	3	8.484	9.333	0.61	0.80	12.19	284.98	0.000	0.000	113.78	0.00	0.00
12	159.00	B25 RRH4x30	3	8.484	9.333	0.65	0.80	5.35	316.15	0.000	0.000	49.92	0.00	0.00
13	159.00	SBNHH-1D65B	6	8.484	9.333	0.66	0.80	37.37	1510.39	0.000	0.000	348.76	0.00	0.00
14	159.00	Low Profile	1	8.484	9.333	1.00	1.00	39.76	2816.56	0.000	0.000	371.11	0.00	0.00
15	159.00	DB-T1-6Z-8AB-OZ	2	8.484	9.333	0.57	0.80	6.45	334.80	0.000	0.000	60.21	0.00	0.00
16	159.00	B25 RRH4x30	3	8.484	9.333	0.65	0.80	5.35	316.15	0.000	0.000	49.92	0.00	0.00
17	159.00	RRH 4X45-PCS	3	8.484	9.333	0.78	0.80	9.36	390.38	0.000	0.000	87.39	0.00	0.00
18	147.00	RRUS A2	3	8.345	9.180	0.50	0.80	4.25	160.73	0.000	0.000	38.99	0.00	0.00
19	147.00	HPA-65R-BUU-H6	1	8.345	9.180	0.80	0.80	8.82	308.72	2.383	0.000	80.95	192.91	0.00
20	147.00	HPA-65R-BUU-H8	2	8.345	9.180	0.71	0.80	20.85	743.92	0.000	0.000	191.38	0.00	0.00
21	147.00	860 10025 RET	12	8.345	9.180	0.74	0.80	4.93	69.89	0.000	0.000	45.25	0.00	0.00
22	147.00	RRUS 12	3	8.345	9.180	0.57	0.80	5.74	349.65	0.000	0.000	52.68	0.00	0.00
23	147.00	LGP21401	6	8.345	9.180	0.54	0.80	6.83	208.62	0.000	0.000	62.70	0.00	0.00
24	147.00	RRUS-11	6	8.345	9.180	0.54	0.80	10.14	703.96	0.000	0.000	93.05	0.00	0.00
25	147.00	LGP21901 Diplexer	6	8.345	9.180	0.54	0.80	2.14	75.66	0.000	0.000	19.69	0.00	0.00
26	147.00	DC6-48-60-18-8F("Squid")	1	8.345	9.180	1.00	1.00	1.36	82.16	2.383	0.000	12.46	29.69	0.00
27	147.00	Low Profile	1	8.345	9.180	1.00	1.00	39.63	2806.27	0.000	0.000	363.75	0.00	0.00
28	147.00	7770.00	6	8.345	9.180	0.60	0.80	23.75	1061.03	0.000	0.000	218.04	0.00	0.00
29	52.00	GPS	1	6.705	7.376	0.80	0.80	0.43	0.76	3.055	0.000	3.20	9.77	0.00

Totals: 18,901.44

3,582.53

Total Applied Force Summary

Structure: CT01365-S-SBA	Code: EIA/TIA-222-G	10/13/2017
Site Name: Norwich 2 CT	Exposure: C	
Height: 180.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II



Page: 27

Load Case: 1.2D + 1.0Di + 1.0Wi 50 mph Wind

Dead Load Factor 1.20
Wind Load Factor 1.00



Iterations 25

Elev (ft)	Description	Lateral FX (-) (lb)	Axial FY (-) (lb)	Torsion MY (lb-ft)	Moment MZ (lb-ft)
0.00		0.00	0.00	0.00	0.00
5.00		173.81	2266.65	0.00	0.00
10.00		171.64	2267.70	0.00	0.00
15.00		169.27	2254.75	0.00	0.00
17.00		68.69	895.89	0.00	0.00
20.00		105.86	1338.22	0.00	0.00
25.00		182.74	2213.01	0.00	0.00
30.00		186.96	2188.03	0.00	0.00
35.00		190.09	2161.38	0.00	0.00
40.00		192.36	2133.47	0.00	0.00
45.00		193.94	2104.56	0.00	0.00
45.92		35.34	382.87	0.00	0.00
50.00		161.25	2685.91	0.00	0.00
52.00	(1) attachments	82.00	1303.79	9.77	0.00
53.00		39.36	644.37	0.00	0.00
55.00		78.92	739.34	0.00	0.00
60.00		198.55	1827.72	0.00	0.00
65.00		198.38	1799.85	0.00	0.00
70.00		197.89	1771.56	0.00	0.00
75.00		197.11	1742.91	0.00	0.00
80.00		196.09	1713.94	0.00	0.00
85.00		194.83	1684.68	0.00	0.00
90.00		193.36	1655.15	0.00	0.00
92.83		108.57	925.60	0.00	0.00
95.00		83.63	1034.49	0.00	0.00
98.92		150.61	1846.70	0.00	0.00
100.00		41.32	294.62	0.00	0.00
105.00		190.31	1341.91	0.00	0.00
110.00		188.18	1317.23	0.00	0.00
115.00		185.91	1292.38	0.00	0.00
120.00		183.50	1267.36	0.00	0.00
125.00		180.96	1242.20	0.00	0.00
126.67		59.68	410.19	0.00	0.00
130.00		119.61	1151.13	0.00	0.00
132.00		71.29	684.69	0.00	0.00
135.00		105.90	635.52	0.00	0.00
140.00		174.68	1041.20	0.00	0.00
145.00		171.71	1019.27	0.00	0.00
147.00	(47) attachments	1246.63	6973.24	222.60	0.00
150.00		100.67	548.73	0.00	0.00
155.00		165.50	895.03	0.00	0.00
159.00	(24) attachments	1297.75	6849.63	0.00	0.00
160.00		32.10	159.63	0.00	0.00
165.00		158.92	781.07	0.00	0.00
170.00		155.51	758.62	0.00	0.00
175.00		152.02	736.09	0.00	0.00
177.00	(23) attachments	1270.50	6449.05	0.00	0.00

Total Applied Force Summary

Structure: CT01365-S-SBA	Code: EIA/TIA-222-G	10/13/2017
Site Name: Norwich 2 CT	Exposure: C	
Height: 180.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II



Page: 28

180.00	(1) attachments	110.35	438.33	0.00	0.00
	Totals:	10,114.22	77,869.68	232.37	0.00

Linear Appurtenance Segment Forces (Factored)

Structure: CT01365-S-SBA	Code: EIA/TIA-222-G	10/13/2017
Site Name: Norwich 2 CT	Exposure: C	
Height: 180.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II



Page: 29

Load Case: 1.2D + 1.0Di + 1.0Wi 50 mph Wind

Dead Load Factor 1.20
Wind Load Factor 1.00



Iterations 25

Top Elev (ft)	Description	Wind Exposed	Length (ft)	Ca	Exposed Width (in)	Area (sqft)	CaAa (sqft)	Ra	Cf Adjust Factor	qz (psf)	F X (lb)	Dead Load (lb)
5.00	1/2" Coax	Yes	5.00	0.000	0.65	1.31	0.00	0.011	0.000	5.168	0.00	13.70
10.00	1/2" Coax	Yes	5.00	0.000	0.65	1.38	0.00	0.011	0.000	5.168	0.00	15.33
15.00	1/2" Coax	Yes	5.00	0.000	0.65	1.43	0.00	0.011	0.000	5.168	0.00	16.38
17.00	1/2" Coax	Yes	2.00	0.000	0.65	0.58	0.00	0.012	0.000	5.299	0.00	6.69
20.00	1/2" Coax	Yes	3.00	0.000	0.65	0.88	0.00	0.012	0.000	5.483	0.00	10.31
25.00	1/2" Coax	Yes	5.00	0.000	0.65	1.49	0.00	0.012	0.000	5.747	0.00	17.83
30.00	1/2" Coax	Yes	5.00	0.000	0.65	1.51	0.00	0.012	0.000	5.972	0.00	18.38
35.00	1/2" Coax	Yes	5.00	0.000	0.65	1.53	0.00	0.012	0.000	6.169	0.00	18.86
40.00	1/2" Coax	Yes	5.00	0.000	0.65	1.55	0.00	0.012	0.000	6.345	0.00	19.29
45.00	1/2" Coax	Yes	5.00	0.000	0.65	1.56	0.00	0.013	0.000	6.504	0.00	19.67
45.92	1/2" Coax	Yes	0.92	0.000	0.65	0.29	0.00	0.013	0.000	6.532	0.00	3.62
50.00	1/2" Coax	Yes	4.08	0.000	0.65	1.29	0.00	0.013	0.000	6.650	0.00	16.35
52.00	1/2" Coax	Yes	2.00	0.000	0.65	0.63	0.00	0.013	0.000	6.705	0.00	8.06
Totals:											0.0	184.5

Calculated Forces

Structure: CT01365-S-SBA	Code: EIA/TIA-222-G	10/13/2017
Site Name: Norwich 2 CT	Exposure: C	
Height: 180.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II




Page: 30

Load Case: 1.2D + 1.0Di + 1.0Wi 50 mph Wind

Iterations 25

Dead Load Factor 1.20
Wind Load Factor 1.00



Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (-) (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	phi Pn (kips)	phi Vn (kips)	phi Tn (ft-kips)	phi Mn (ft-kips)	Total Deflect (in)	Rotation Sway (deg)	Rotation Twist (deg)	Stress Ratio
0.00	-77.87	-10.14	-0.23	-1249.7	0.00	1249.70	5397.55	2698.78	12826.5	6367.63	0.00	0.000	0.000	0.160
5.00	-75.59	-10.02	-0.23	-1199.0	0.00	1199.00	5344.66	2672.33	12495.2	6203.15	0.02	-0.039	0.000	0.157
10.00	-73.32	-9.89	-0.23	-1148.9	0.00	1148.91	5290.67	2645.34	12165.4	6039.43	0.08	-0.079	0.000	0.153
15.00	-71.06	-9.76	-0.23	-1099.4	0.00	1099.43	5235.58	2617.79	11837.2	5876.53	0.19	-0.118	0.000	0.150
17.00	-70.16	-9.71	-0.23	-1079.9	0.00	1079.92	5213.23	2606.61	11706.5	5811.61	0.24	-0.134	0.000	0.149
17.00	-70.16	-9.71	-0.23	-1079.9	0.00	1079.92	5213.23	2606.61	11706.5	5811.61	0.24	-0.134	0.000	0.149
20.00	-68.82	-9.65	-0.23	-1050.7	0.00	1050.79	5179.37	2589.69	11510.9	5714.52	0.33	-0.158	0.000	0.197
25.00	-66.59	-9.52	-0.23	-1002.5	0.00	1002.56	5122.07	2561.03	11186.5	5553.45	0.53	-0.211	0.000	0.194
30.00	-64.40	-9.38	-0.23	-954.97	0.00	954.97	5063.65	2531.83	10864.1	5393.40	0.78	-0.264	0.000	0.190
35.00	-62.23	-9.24	-0.23	-908.06	0.00	908.06	5004.13	2502.07	10543.8	5234.42	1.08	-0.317	0.000	0.186
40.00	-60.09	-9.09	-0.23	-861.86	0.00	861.86	4943.51	2471.75	10225.9	5076.58	1.44	-0.371	0.000	0.182
45.00	-57.98	-8.91	-0.23	-816.41	0.00	816.41	4881.77	2440.89	9910.40	4919.94	1.86	-0.425	0.000	0.178
45.92	-57.59	-8.90	-0.23	-808.24	0.00	808.24	4870.34	2435.17	9852.83	4891.36	1.94	-0.435	0.000	0.177
50.00	-54.90	-8.75	-0.23	-771.89	0.00	771.89	4818.94	2409.47	9597.43	4764.57	2.33	-0.479	0.000	0.173
52.00	-53.60	-8.67	-0.22	-754.38	0.00	754.38	4793.49	2396.75	9472.99	4702.79	2.54	-0.500	0.000	0.172
53.00	-52.95	-8.64	-0.22	-745.71	0.00	745.71	3921.66	1960.83	7862.59	3903.32	2.64	-0.511	0.000	0.205
55.00	-52.21	-8.60	-0.22	-728.42	0.00	728.42	3903.31	1951.65	7765.73	3855.23	2.86	-0.533	0.000	0.202
60.00	-50.37	-8.43	-0.22	-685.44	0.00	685.44	3856.65	1928.33	7524.53	3735.49	3.45	-0.593	0.000	0.197
65.00	-48.57	-8.26	-0.22	-643.29	0.00	643.29	3808.89	1904.45	7284.80	3616.48	4.11	-0.652	0.000	0.191
70.00	-46.79	-8.09	-0.22	-601.97	0.00	601.97	3760.03	1880.02	7046.68	3498.27	4.82	-0.711	0.000	0.185
75.00	-45.04	-7.92	-0.22	-561.51	0.00	561.51	3710.06	1855.03	6810.28	3380.91	5.60	-0.769	0.000	0.178
80.00	-43.32	-7.74	-0.22	-521.92	0.00	521.92	3658.99	1829.49	6575.75	3264.48	6.43	-0.827	0.000	0.172
85.00	-41.63	-7.56	-0.22	-483.21	0.00	483.21	3606.81	1803.40	6343.20	3149.03	7.33	-0.884	0.000	0.165
90.00	-39.98	-7.37	-0.22	-445.40	0.00	445.40	3553.52	1776.76	6112.76	3034.63	8.29	-0.940	0.000	0.158
92.83	-39.05	-7.27	-0.22	-424.50	0.00	424.50	3522.83	1761.42	5983.17	2970.30	8.85	-0.972	0.000	0.154
95.00	-38.01	-7.19	-0.22	-408.76	0.00	408.76	3499.13	1749.56	5884.57	2921.35	9.30	-0.997	0.000	0.151
98.92	-36.16	-7.02	-0.22	-380.59	0.00	380.59	2350.25	1175.12	3954.81	1963.33	10.14	-1.040	0.000	0.209
100.00	-35.87	-7.00	-0.22	-372.98	0.00	372.98	2343.93	1171.97	3924.64	1948.36	10.37	-1.052	0.000	0.207
105.00	-34.52	-6.83	-0.22	-337.97	0.00	337.97	2314.11	1157.05	3785.67	1879.37	11.51	-1.119	0.000	0.195
110.00	-33.20	-6.65	-0.22	-303.84	0.00	303.84	2283.18	1141.59	3647.23	1810.64	12.72	-1.183	0.000	0.182
115.00	-31.90	-6.47	-0.22	-270.60	0.00	270.60	2251.15	1125.57	3509.45	1742.24	13.99	-1.246	0.000	0.170
120.00	-30.64	-6.29	-0.22	-238.25	0.00	238.25	2218.01	1109.01	3372.44	1674.22	15.33	-1.305	-0.001	0.156
125.00	-29.39	-6.10	-0.22	-206.81	0.00	206.81	2183.77	1091.88	3236.35	1606.66	16.73	-1.361	-0.001	0.142
126.67	-28.98	-6.04	-0.22	-196.63	0.00	196.63	2172.08	1086.04	3191.13	1584.21	17.21	-1.379	-0.001	0.137
130.00	-27.83	-5.91	-0.22	-176.51	0.00	176.51	2148.42	1074.21	3101.30	1539.62	18.18	-1.414	-0.001	0.128
132.00	-27.15	-5.83	-0.22	-164.68	0.00	164.68	1502.55	751.27	2180.88	1082.68	18.78	-1.434	-0.001	0.170
135.00	-26.51	-5.73	-0.22	-147.21	0.00	147.21	1491.20	745.60	2130.02	1057.43	19.69	-1.462	-0.001	0.157
140.00	-25.47	-5.55	-0.22	-118.57	0.00	118.57	1471.39	735.69	2045.11	1015.28	21.25	-1.514	-0.001	0.134
145.00	-24.45	-5.36	-0.22	-90.84	-0.01	90.84	1450.46	725.23	1960.22	973.13	22.86	-1.559	-0.001	0.110
147.00	-17.51	-3.93	0.00	-80.11	0.00	80.11	1441.79	720.89	1926.30	956.30	23.52	-1.574	-0.001	0.096
150.00	-16.97	-3.82	0.00	-68.33	0.00	68.33	1428.44	714.22	1875.49	931.07	24.51	-1.596	-0.001	0.085
155.00	-16.08	-3.64	0.00	-49.22	0.00	49.22	1405.30	702.65	1791.05	889.15	26.20	-1.625	-0.001	0.067
159.00	-9.26	-2.15	0.00	-34.67	0.00	34.67	1386.00	693.00	1723.78	855.76	27.57	-1.644	-0.001	0.047
160.00	-9.11	-2.11	0.00	-32.53	0.00	32.53	1381.06	690.53	1707.02	847.43	27.91	-1.648	-0.001	0.045
165.00	-8.33	-1.93	0.00	-21.97	0.00	21.97	1355.72	677.86	1623.53	805.99	29.65	-1.664	-0.001	0.033
170.00	-7.58	-1.76	0.00	-12.31	0.00	12.31	1329.27	664.63	1540.71	764.87	31.40	-1.675	-0.001	0.022
175.00	-6.84	-1.58	0.00	-3.53	0.00	3.53	1301.71	650.86	1458.68	724.15	33.16	-1.681	-0.001	0.010
177.00	-0.43	-0.12	0.00	-0.37	0.00	0.37	1290.38	645.19	1426.13	707.99	33.86	-1.682	-0.001	0.001

Calculated Forces

Structure: CT01365-S-SBA	Code: EIA/TIA-222-G	10/13/2017
Site Name: Norwich 2 CT	Exposure: C	
Height: 180.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II
		Page: 31



180.00	0.00	-0.11	0.00	0.00	0.00	0.00	0.00	1273.05	636.53	1377.59	683.89	34.92	-1.682	-0.001	0.000
--------	------	-------	------	------	------	------	------	---------	--------	---------	--------	-------	--------	--------	-------


Seismic Segment Forces (Factored)

Structure: CT01365-S-SBA	Code: EIA/TIA-222-G	10/13/2017
Site Name: Norwich 2 CT	Exposure: C	
Height: 180.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II



Page: 32

Load Case: 1.2D + 1.0E					Iterations 23
Gust Response Factor	1.10			Sds 0.18	Ss 0.17
Dead Load Factor	1.20	Seismic Load Factor	1.00	Sd1 0.10	S1 0.06
Wind Load Factor	0.00	Structure Frequency	0.32	SA 0.03	Seismic Importance Factor 1.00



Top Elev (ft)	Description	Wz (lb)	a	b	c	Lateral Fs (lb)	R: 1.50
0.00	RB1	0.00	0.00	0.00	0.00	0.00	
5.00		1357.3	0.00	0.03	0.02	21.99	
10.00		1335.3	0.01	0.05	0.03	32.24	
15.00		1313.4	0.01	0.06	0.03	37.34	
17.00	RT1	519.20	0.02	0.06	0.04	15.35	
20.00		772.21	0.02	0.07	0.04	23.80	
25.00		1269.4	0.04	0.07	0.04	40.90	
30.00		1247.4	0.05	0.07	0.04	41.33	
35.00		1225.4	0.07	0.07	0.04	41.49	
40.00		1203.4	0.09	0.07	0.04	41.58	
45.00		1181.4	0.12	0.07	0.03	41.63	
45.92	Bot - Section 2	214.22	0.12	0.07	0.03	7.58	
50.00		1768.0	0.15	0.07	0.03	63.43	
52.00	Appurtenance(s)	856.26	0.16	0.07	0.03	30.89	
53.00	Top - Section 1	425.58	0.16	0.07	0.03	15.39	
55.00		393.91	0.18	0.07	0.03	14.30	
60.00		971.59	0.21	0.06	0.02	35.21	
65.00		952.77	0.25	0.06	0.02	33.71	
70.00		933.94	0.29	0.05	0.01	31.07	
75.00		915.12	0.33	0.04	0.01	26.93	
80.00		896.29	0.37	0.03	0.01	21.01	
85.00		877.46	0.42	0.01	0.01	13.26	
90.00		858.64	0.47	-0.01	0.01	4.09	
92.83	Bot - Section 3	478.20	0.50	-0.02	0.01	-0.80	
95.00		636.91	0.53	-0.03	0.01	-4.25	
98.92	Top - Section 2	1135.6	0.57	-0.04	0.01	-17.58	
100.00		134.26	0.58	-0.05	0.01	-2.39	
105.00		611.09	0.64	-0.07	0.02	-16.59	
110.00		596.98	0.71	-0.09	0.03	-20.14	
115.00		582.87	0.77	-0.11	0.05	-21.57	
120.00		568.77	0.84	-0.12	0.07	-20.93	
125.00		554.66	0.91	-0.12	0.09	-18.39	
126.67	Bot - Section 4	182.11	0.94	-0.12	0.10	-5.68	
130.00		641.75	0.99	-0.11	0.12	-16.78	
132.00	Top - Section 3	380.71	1.02	-0.11	0.14	-8.53	
135.00		248.14	1.06	-0.09	0.17	-3.93	
140.00		405.24	1.14	-0.04	0.21	-0.91	
145.00		394.24	1.23	0.03	0.27	5.75	
147.00	Appurtenance(s)	2761.4	1.26	0.07	0.30	61.41	
150.00		228.63	1.31	0.14	0.35	7.94	
155.00		372.25	1.40	0.29	0.43	21.65	
159.00	Appurtenance(s)	2631.6	1.47	0.44	0.51	208.84	
160.00		71.37	1.49	0.48	0.53	6.07	
165.00		350.26	1.59	0.74	0.65	40.38	
170.00		339.27	1.69	1.07	0.79	50.58	
175.00		328.28	1.79	1.48	0.95	61.21	

Seismic Segment Forces (Factored)

Structure: CT01365-S-SBA	Code: EIA/TIA-222-G	10/13/2017
Site Name: Norwich 2 CT	Exposure: C	
Height: 180.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II



Page: 33

177.00	Appurtenance(s)	2598.6	1.83	1.67	1.03	526.04	
180.00	Appurtenance(s)	194.05	1.89	1.98	1.14	44.15	
	Totals:	38,916.1				1,510.1	Total Wind: 44,008.9


Seismic Base Shear is Less Than 50% of Wind Force - An Analysis is NOT Required

Calculated Forces

Structure: CT01365-S-SBA **Code:** EIA/TIA-222-G 10/13/2017
Site Name: Norwich 2 CT **Exposure:** C
Height: 180.00 (ft) **Crest Height:** 0.00
Base Elev: 0.000 (ft) **Site Class:** D - Stiff Soil
Gh: 1.1 **Topography:** 1 **Struct Class:** II Page: 34



Load Case: 1.2D + 1.0E										Iterations 23	
Gust Response Factor	1.10							Sds	0.18	Ss	0.17
Dead Load Factor	1.20	Seismic Load Factor	1.00	Sd1	0.10					S1	0.06
Wind Load Factor	0.00	Structure Frequency	0.32	SA	0.03	Seismic Importance Factor	1.00				



Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (-) (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	phi Pn (kips)	phi Vn (kips)	phi Tn (ft-kips)	phi Mn (ft-kips)	Total Deflect (in)	Rotation Sway (deg)	Rotation Twist (deg)	Stress Ratio
0.00	-51.85	-1.67	0.00	-211.63	0.00	211.63	5397.55	2698.78	12826.5	6367.63	0.00	0.00	0.00	0.032
5.00	-50.06	-1.65	0.00	-203.28	0.00	203.28	5344.66	2672.33	12495.2	6203.15	0.00	-0.01	0.032	
10.00	-48.29	-1.63	0.00	-195.00	0.00	195.00	5290.67	2645.34	12165.4	6039.43	0.01	-0.01	0.031	
15.00	-46.54	-1.59	0.00	-186.87	0.00	186.87	5235.58	2617.79	11837.2	5876.53	0.03	-0.02	0.030	
17.00	-45.85	-1.58	0.00	-183.68	0.00	183.68	5213.23	2606.61	11706.5	5811.61	0.04	-0.02	0.030	
17.00	-45.85	-1.58	0.00	-183.68	0.00	183.68	5213.23	2606.61	11706.5	5811.61	0.04	-0.02	0.030	
20.00	-44.83	-1.56	0.00	-178.94	0.00	178.94	5179.37	2589.69	11510.9	5714.52	0.06	-0.03	0.040	
25.00	-43.14	-1.53	0.00	-171.13	0.00	171.13	5122.07	2561.03	11186.5	5553.45	0.09	-0.04	0.039	
30.00	-41.47	-1.49	0.00	-163.49	0.00	163.49	5063.65	2531.83	10864.1	5393.40	0.13	-0.04	0.039	
35.00	-39.83	-1.45	0.00	-156.04	0.00	156.04	5004.13	2502.07	10543.8	5234.42	0.18	-0.05	0.038	
40.00	-38.22	-1.42	0.00	-148.77	0.00	148.77	4943.51	2471.75	10225.9	5076.58	0.25	-0.06	0.037	
45.00	-36.64	-1.38	0.00	-141.68	0.00	141.68	4881.77	2440.89	9910.40	4919.94	0.32	-0.07	0.036	
45.92	-36.35	-1.37	0.00	-140.42	0.00	140.42	4870.34	2435.17	9852.83	4891.36	0.33	-0.07	0.036	
50.00	-34.09	-1.31	0.00	-134.82	0.00	134.82	4818.94	2409.47	9597.43	4764.57	0.40	-0.08	0.035	
52.00	-33.00	-1.28	0.00	-132.20	0.00	132.20	4793.49	2396.75	9472.99	4702.79	0.43	-0.09	0.035	
53.00	-32.45	-1.26	0.00	-130.92	0.00	130.92	3921.66	1960.83	7862.59	3903.32	0.45	-0.09	0.042	
55.00	-31.91	-1.25	0.00	-128.40	0.00	128.40	3903.31	1951.65	7765.73	3855.23	0.49	-0.09	0.041	
60.00	-30.58	-1.22	0.00	-122.13	0.00	122.13	3856.65	1928.33	7524.53	3735.49	0.59	-0.10	0.041	
65.00	-29.27	-1.19	0.00	-116.03	0.00	116.03	3808.89	1904.45	7284.80	3616.48	0.70	-0.11	0.040	
70.00	-27.98	-1.16	0.00	-110.08	0.00	110.08	3760.03	1880.02	7046.68	3498.27	0.83	-0.12	0.039	
75.00	-26.72	-1.14	0.00	-104.27	0.00	104.27	3710.06	1855.03	6810.28	3380.91	0.96	-0.13	0.038	
80.00	-25.48	-1.12	0.00	-98.59	0.00	98.59	3658.99	1829.49	6575.75	3264.48	1.11	-0.14	0.037	
85.00	-24.26	-1.11	0.00	-93.00	0.00	93.00	3606.81	1803.40	6343.20	3149.03	1.27	-0.16	0.036	
90.00	-23.06	-1.10	0.00	-87.47	0.00	87.47	3553.52	1776.76	6112.76	3034.63	1.43	-0.17	0.035	
92.83	-22.39	-1.10	0.00	-84.35	0.00	84.35	3522.83	1761.42	5983.17	2970.30	1.54	-0.17	0.035	
95.00	-21.56	-1.10	0.00	-81.96	0.00	81.96	3499.13	1749.56	5884.57	2921.35	1.62	-0.18	0.034	
98.92	-20.06	-1.10	0.00	-77.64	0.00	77.64	2350.25	1175.12	3954.81	1963.33	1.76	-0.19	0.048	
100.00	-19.87	-1.10	0.00	-76.45	0.00	76.45	2343.93	1171.97	3924.64	1948.36	1.81	-0.19	0.048	
105.00	-18.97	-1.10	0.00	-70.95	0.00	70.95	2314.11	1157.05	3785.67	1879.37	2.01	-0.20	0.046	
110.00	-18.08	-1.10	0.00	-65.43	0.00	65.43	2283.18	1141.59	3647.23	1810.64	2.23	-0.22	0.044	
115.00	-17.22	-1.10	0.00	-59.91	0.00	59.91	2251.15	1125.57	3509.45	1742.24	2.47	-0.23	0.042	
120.00	-16.37	-1.11	0.00	-54.39	0.00	54.39	2218.01	1109.01	3372.44	1674.22	2.72	-0.24	0.040	
125.00	-15.54	-1.10	0.00	-48.86	0.00	48.86	2183.77	1091.88	3236.35	1606.66	2.98	-0.26	0.038	
126.67	-15.26	-1.10	0.00	-47.02	0.00	47.02	2172.08	1086.04	3191.13	1584.21	3.07	-0.26	0.037	
130.00	-14.38	-1.10	0.00	-43.34	0.00	43.34	2148.42	1074.21	3101.30	1539.62	3.25	-0.27	0.035	
132.00	-13.86	-1.10	0.00	-41.14	0.00	41.14	1502.55	751.27	2180.88	1082.68	3.37	-0.27	0.047	
135.00	-13.46	-1.10	0.00	-37.84	0.00	37.84	1491.20	745.60	2130.02	1057.43	3.54	-0.28	0.045	
140.00	-12.81	-1.10	0.00	-32.33	0.00	32.33	1471.39	735.69	2045.11	1015.28	3.85	-0.30	0.041	
145.00	-12.17	-1.09	0.00	-26.82	0.00	26.82	1450.46	725.23	1960.22	973.13	4.16	-0.31	0.036	
147.00	-8.79	-1.02	0.00	-24.64	0.00	24.64	1441.79	720.89	1926.30	956.30	4.29	-0.31	0.032	
150.00	-8.47	-1.01	0.00	-21.59	0.00	21.59	1428.44	714.22	1875.49	931.07	4.49	-0.32	0.029	
155.00	-7.94	-0.98	0.00	-16.56	0.00	16.56	1405.30	702.65	1791.05	889.15	4.83	-0.33	0.024	
159.00	-4.71	-0.76	0.00	-12.63	0.00	12.63	1386.00	693.00	1723.78	855.76	5.11	-0.34	0.018	
160.00	-4.62	-0.75	0.00	-11.87	0.00	11.87	1381.06	690.53	1707.02	847.43	5.18	-0.34	0.017	
165.00	-4.19	-0.71	0.00	-8.12	0.00	8.12	1355.72	677.86	1623.53	805.99	5.53	-0.34	0.013	
170.00	-3.76	-0.65	0.00	-4.59	0.00	4.59	1329.27	664.63	1540.71	764.87	5.90	-0.35	0.009	
175.00	-3.35	-0.59	0.00	-1.32	0.00	1.32	1301.71	650.86	1458.68	724.15	6.26	-0.35	0.004	

Calculated Forces

Structure: CT01365-S-SBA	Code: EIA/TIA-222-G	10/13/2017
Site Name: Norwich 2 CT	Exposure: C	
Height: 180.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Page: 35
Struct Class: II		



177.00	-0.23	-0.05	0.00	-0.14	0.00	0.14	1290.38	645.19	1426.13	707.99	6.41	-0.35	0.000
180.00	0.00	-0.04	0.00	0.00	0.00	0.00	1273.05	636.53	1377.59	683.89	6.63	-0.35	0.000


Seismic Segment Forces (Factored)

Structure: CT01365-S-SBA	Code: EIA/TIA-222-G	10/13/2017
Site Name: Norwich 2 CT	Exposure: C	
Height: 180.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II



Page: 36

Load Case: 0.9D + 1.0E					Iterations 23
Gust Response Factor	1.10			Sds	0.18
Dead Load Factor	0.90	Seismic Load Factor	1.00	Sd1	0.10
Wind Load Factor	0.00	Structure Frequency	0.32	SA	0.03
				Seismic Importance Factor	1.00



Top Elev (ft)	Description	Wz (lb)	a	b	c	Lateral Fs (lb)	R: 1.50
0.00	RB1	0.00	0.00	0.00	0.00	0.00	
5.00		1357.3	0.00	0.03	0.02	21.99	
10.00		1335.3	0.01	0.05	0.03	32.24	
15.00		1313.4	0.01	0.06	0.03	37.34	
17.00	RT1	519.20	0.02	0.06	0.04	15.35	
20.00		772.21	0.02	0.07	0.04	23.80	
25.00		1269.4	0.04	0.07	0.04	40.90	
30.00		1247.4	0.05	0.07	0.04	41.33	
35.00		1225.4	0.07	0.07	0.04	41.49	
40.00		1203.4	0.09	0.07	0.04	41.58	
45.00		1181.4	0.12	0.07	0.03	41.63	
45.92	Bot - Section 2	214.22	0.12	0.07	0.03	7.58	
50.00		1768.0	0.15	0.07	0.03	63.43	
52.00	Appurtenance(s)	856.26	0.16	0.07	0.03	30.89	
53.00	Top - Section 1	425.58	0.16	0.07	0.03	15.39	
55.00		393.91	0.18	0.07	0.03	14.30	
60.00		971.59	0.21	0.06	0.02	35.21	
65.00		952.77	0.25	0.06	0.02	33.71	
70.00		933.94	0.29	0.05	0.01	31.07	
75.00		915.12	0.33	0.04	0.01	26.93	
80.00		896.29	0.37	0.03	0.01	21.01	
85.00		877.46	0.42	0.01	0.01	13.26	
90.00		858.64	0.47	-0.01	0.01	4.09	
92.83	Bot - Section 3	478.20	0.50	-0.02	0.01	-0.80	
95.00		636.91	0.53	-0.03	0.01	-4.25	
98.92	Top - Section 2	1135.6	0.57	-0.04	0.01	-17.58	
100.00		134.26	0.58	-0.05	0.01	-2.39	
105.00		611.09	0.64	-0.07	0.02	-16.59	
110.00		596.98	0.71	-0.09	0.03	-20.14	
115.00		582.87	0.77	-0.11	0.05	-21.57	
120.00		568.77	0.84	-0.12	0.07	-20.93	
125.00		554.66	0.91	-0.12	0.09	-18.39	
126.67	Bot - Section 4	182.11	0.94	-0.12	0.10	-5.68	
130.00		641.75	0.99	-0.11	0.12	-16.78	
132.00	Top - Section 3	380.71	1.02	-0.11	0.14	-8.53	
135.00		248.14	1.06	-0.09	0.17	-3.93	
140.00		405.24	1.14	-0.04	0.21	-0.91	
145.00		394.24	1.23	0.03	0.27	5.75	
147.00	Appurtenance(s)	2761.4	1.26	0.07	0.30	61.41	
150.00		228.63	1.31	0.14	0.35	7.94	
155.00		372.25	1.40	0.29	0.43	21.65	
159.00	Appurtenance(s)	2631.6	1.47	0.44	0.51	208.84	
160.00		71.37	1.49	0.48	0.53	6.07	
165.00		350.26	1.59	0.74	0.65	40.38	
170.00		339.27	1.69	1.07	0.79	50.58	
175.00		328.28	1.79	1.48	0.95	61.21	

Seismic Segment Forces (Factored)

Structure: CT01365-S-SBA	Code: EIA/TIA-222-G	10/13/2017
Site Name: Norwich 2 CT	Exposure: C	
Height: 180.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II



Page: 37

177.00	Appurtenance(s)	2598.6	1.83	1.67	1.03	526.04	
180.00	Appurtenance(s)	194.05	1.89	1.98	1.14	44.15	
	Totals:	38,916.1				1,510.1	Total Wind: 44,008.9


Seismic Base Shear is Less Than 50% of Wind Force - An Analysis is NOT Required

Calculated Forces

Structure: CT01365-S-SBA	Code: EIA/TIA-222-G	10/13/2017
Site Name: Norwich 2 CT	Exposure: C	
Height: 180.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II



Load Case: 0.9D + 1.0E							Iterations 23
Gust Response Factor	1.10			Sds	0.18		Ss 0.17
Dead Load Factor	0.90	Seismic Load Factor	1.00	Sd1	0.10		S1 0.06
Wind Load Factor	0.00	Structure Frequency	0.32	SA	0.03	Seismic Importance Factor	1.00



Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (-) (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	phi Pn (kips)	phi Vn (kips)	phi Tn (ft-kips)	phi Mn (ft-kips)	Total Deflect (in)	Rotation Sway (deg)	Rotation Twist (deg)	Stress Ratio
0.00	-38.89	-1.67	0.00	-209.37	0.00	209.37	5397.55	2698.78	12826.5	6367.63	0.00	0.00	0.00	0.030
5.00	-37.54	-1.65	0.00	-201.01	0.00	201.01	5344.66	2672.33	12495.2	6203.15	0.00	-0.01	-0.01	0.030
10.00	-36.22	-1.62	0.00	-192.75	0.00	192.75	5290.67	2645.34	12165.4	6039.43	0.01	-0.01	-0.01	0.029
15.00	-34.91	-1.59	0.00	-184.63	0.00	184.63	5235.58	2617.79	11837.2	5876.53	0.03	-0.02	-0.02	0.028
17.00	-34.39	-1.58	0.00	-181.45	0.00	181.45	5213.23	2606.61	11706.5	5811.61	0.04	-0.02	-0.02	0.028
17.00	-34.39	-1.58	0.00	-181.45	0.00	181.45	5213.23	2606.61	11706.5	5811.61	0.04	-0.02	-0.02	0.028
20.00	-33.62	-1.56	0.00	-176.73	0.00	176.73	5179.37	2589.69	11510.9	5714.52	0.06	-0.03	-0.03	0.037
25.00	-32.35	-1.52	0.00	-168.95	0.00	168.95	5122.07	2561.03	11186.5	5553.45	0.09	-0.04	-0.04	0.037
30.00	-31.10	-1.48	0.00	-161.36	0.00	161.36	5063.65	2531.83	10864.1	5393.40	0.13	-0.04	-0.04	0.036
35.00	-29.87	-1.44	0.00	-153.95	0.00	153.95	5004.13	2502.07	10543.8	5234.42	0.18	-0.05	-0.05	0.035
40.00	-28.67	-1.41	0.00	-146.73	0.00	146.73	4943.51	2471.75	10225.9	5076.58	0.24	-0.06	-0.06	0.035
45.00	-27.48	-1.37	0.00	-139.70	0.00	139.70	4881.77	2440.89	9910.40	4919.94	0.31	-0.07	-0.07	0.034
45.92	-27.26	-1.36	0.00	-138.45	0.00	138.45	4870.34	2435.17	9852.83	4891.36	0.33	-0.07	-0.07	0.034
50.00	-25.57	-1.30	0.00	-132.90	0.00	132.90	4818.94	2409.47	9597.43	4764.57	0.39	-0.08	-0.08	0.033
52.00	-24.75	-1.27	0.00	-130.31	0.00	130.31	4793.49	2396.75	9472.99	4702.79	0.43	-0.08	-0.08	0.033
53.00	-24.34	-1.25	0.00	-129.04	0.00	129.04	3921.66	1960.83	7862.59	3903.32	0.45	-0.09	-0.09	0.039
55.00	-23.93	-1.24	0.00	-126.54	0.00	126.54	3903.31	1951.65	7765.73	3855.23	0.48	-0.09	-0.09	0.039
60.00	-22.94	-1.21	0.00	-120.35	0.00	120.35	3856.65	1928.33	7524.53	3735.49	0.58	-0.10	-0.10	0.038
65.00	-21.95	-1.17	0.00	-114.32	0.00	114.32	3808.89	1904.45	7284.80	3616.48	0.69	-0.11	-0.11	0.037
70.00	-20.99	-1.15	0.00	-108.45	0.00	108.45	3760.03	1880.02	7046.68	3498.27	0.82	-0.12	-0.12	0.037
75.00	-20.04	-1.12	0.00	-102.72	0.00	102.72	3710.06	1855.03	6810.28	3380.91	0.95	-0.13	-0.13	0.036
80.00	-19.11	-1.10	0.00	-97.12	0.00	97.12	3658.99	1829.49	6575.75	3264.48	1.09	-0.14	-0.14	0.035
85.00	-18.19	-1.09	0.00	-91.62	0.00	91.62	3606.81	1803.40	6343.20	3149.03	1.25	-0.15	-0.15	0.034
90.00	-17.30	-1.08	0.00	-86.18	0.00	86.18	3553.52	1776.76	6112.76	3034.63	1.42	-0.16	-0.16	0.033
92.83	-16.79	-1.08	0.00	-83.11	0.00	83.11	3522.83	1761.42	5983.17	2970.30	1.52	-0.17	-0.17	0.033
95.00	-16.17	-1.08	0.00	-80.76	0.00	80.76	3499.13	1749.56	5884.57	2921.35	1.59	-0.18	-0.18	0.032
98.92	-15.05	-1.08	0.00	-76.52	0.00	76.52	2350.25	1175.12	3954.81	1963.33	1.74	-0.18	-0.18	0.045
100.00	-14.90	-1.08	0.00	-75.34	0.00	75.34	2343.93	1171.97	3924.64	1948.36	1.78	-0.19	-0.19	0.045
105.00	-14.22	-1.08	0.00	-69.92	0.00	69.92	2314.11	1157.05	3785.67	1879.37	1.99	-0.20	-0.20	0.043
110.00	-13.56	-1.09	0.00	-64.50	0.00	64.50	2283.18	1141.59	3647.23	1810.64	2.20	-0.21	-0.21	0.042
115.00	-12.91	-1.09	0.00	-59.07	0.00	59.07	2251.15	1125.57	3509.45	1742.24	2.43	-0.23	-0.23	0.040
120.00	-12.28	-1.09	0.00	-53.64	0.00	53.64	2218.01	1109.01	3372.44	1674.22	2.68	-0.24	-0.24	0.038
125.00	-11.65	-1.09	0.00	-48.21	0.00	48.21	2183.77	1091.88	3236.35	1606.66	2.94	-0.25	-0.25	0.035
126.67	-11.45	-1.09	0.00	-46.40	0.00	46.40	2172.08	1086.04	3191.13	1584.21	3.03	-0.26	-0.26	0.035
130.00	-10.79	-1.08	0.00	-42.78	0.00	42.78	2148.42	1074.21	3101.30	1539.62	3.21	-0.27	-0.27	0.033
132.00	-10.39	-1.08	0.00	-40.61	0.00	40.61	1502.55	751.27	2180.88	1082.68	3.32	-0.27	-0.27	0.044
135.00	-10.10	-1.08	0.00	-37.36	0.00	37.36	1491.20	745.60	2130.02	1057.43	3.49	-0.28	-0.28	0.042
140.00	-9.61	-1.08	0.00	-31.94	0.00	31.94	1471.39	735.69	2045.11	1015.28	3.79	-0.29	-0.29	0.038
145.00	-9.13	-1.08	0.00	-26.53	0.00	26.53	1450.46	725.23	1960.22	973.13	4.10	-0.30	-0.30	0.034
147.00	-6.59	-1.00	0.00	-24.37	0.00	24.37	1441.79	720.89	1926.30	956.30	4.23	-0.31	-0.31	0.030
150.00	-6.35	-0.99	0.00	-21.36	0.00	21.36	1428.44	714.22	1875.49	931.07	4.43	-0.31	-0.31	0.027
155.00	-5.95	-0.97	0.00	-16.39	0.00	16.39	1405.30	702.65	1791.05	889.15	4.76	-0.32	-0.32	0.023
159.00	-3.53	-0.75	0.00	-12.51	0.00	12.51	1386.00	693.00	1723.78	855.76	5.04	-0.33	-0.33	0.017
160.00	-3.47	-0.74	0.00	-11.76	0.00	11.76	1381.06	690.53	1707.02	847.43	5.11	-0.33	-0.33	0.016
165.00	-3.14	-0.70	0.00	-8.05	0.00	8.05	1355.72	677.86	1623.53	805.99	5.46	-0.34	-0.34	0.012
170.00	-2.82	-0.65	0.00	-4.55	0.00	4.55	1329.27	664.63	1540.71	764.87	5.82	-0.34	-0.34	0.008
175.00	-2.51	-0.59	0.00	-1.31	0.00	1.31	1301.71	650.86	1458.68	724.15	6.18	-0.34	-0.34	0.004

Calculated Forces

Structure: CT01365-S-SBA	Code: EIA/TIA-222-G	10/13/2017
Site Name: Norwich 2 CT	Exposure: C	
Height: 180.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Page: 39
Struct Class: II		



177.00	-0.17	-0.05	0.00	-0.14	0.00	0.14	1290.38	645.19	1426.13	707.99	6.32	-0.34	0.000
180.00	0.00	-0.04	0.00	0.00	0.00	0.00	1273.05	636.53	1377.59	683.89	6.54	-0.34	0.000


Wind Loading - Shaft

Structure: CT01365-S-SBA	Code: EIA/TIA-222-G	10/13/2017
Site Name: Norwich 2 CT	Exposure: C	
Height: 180.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II



Load Case: 1.0D + 1.0W 60 mph Wind

Dead Load Factor 1.00
Wind Load Factor 1.00



Iterations 24

Elev (ft)	Description	Kzt	Kz	qz (psf)	qzGh (psf)	C (mph-ft)	Cf	Ice Thick (in)	Tributary (ft)	Aa (sf)	CfAa (sf)	Wind Force X (lb)	Dead Load Ice (lb)	Tot Dead Load (lb)
0.00	RB1	1.00	0.85	7.442	8.19	272.60	0.750	0.000	0.00	0.000	0.00	0.0	0.0	0.0
5.00		1.00	0.85	7.442	8.19	268.26	0.750	0.000	5.00	24.444	18.33	150.1	0.0	1357.4
10.00		1.00	0.85	7.442	8.19	263.91	0.750	0.000	5.00	24.051	18.04	147.7	0.0	1335.4
15.00		1.00	0.85	7.442	8.19	259.56	0.750	0.000	5.00	23.658	17.74	145.2	0.0	1313.4
17.00	RT1	1.00	0.87	7.631	8.39	261.07	0.750	0.000	2.00	9.353	7.01	58.9	0.0	519.2
20.00		1.00	0.90	7.896	8.69	262.89	0.750	0.000	3.00	13.912	10.43	90.6	0.0	772.2
25.00		1.00	0.95	8.276	9.10	264.55	0.750	0.000	5.00	22.872	17.15	156.2	0.0	1269.4
30.00		1.00	0.98	8.600	9.46	265.00	0.750	0.000	5.00	22.479	16.86	159.5	0.0	1247.4
35.00		1.00	1.01	8.883	9.77	264.59	0.750	0.000	5.00	22.086	16.56	161.9	0.0	1225.4
40.00		1.00	1.04	9.137	10.05	263.52	0.750	0.000	5.00	21.693	16.27	163.5	0.0	1203.5
45.00		1.00	1.07	9.366	10.30	261.93	0.750	0.000	5.00	21.300	15.97	164.6	0.0	1181.5
45.92	Bot - Section 2	1.00	1.07	9.406	10.35	261.59	0.750	0.000	0.92	3.862	2.90	30.0	0.0	214.2
50.00		1.00	1.09	9.576	10.53	259.92	0.750	0.000	4.08	17.305	12.98	136.7	0.0	1768.1
52.00	Appurtenance(s)	1.00	1.10	9.656	10.62	259.01	0.750	0.000	2.00	8.380	6.29	66.8	0.0	856.1
53.00	Top - Section 1	1.00	1.11	9.694	10.66	258.54	0.750	0.000	1.00	4.167	3.12	33.3	0.0	425.6
55.00		1.00	1.12	9.770	10.75	261.60	0.750	0.000	2.00	8.286	6.21	66.8	0.0	393.9
60.00		1.00	1.14	9.951	10.95	258.98	0.750	0.000	5.00	20.440	15.33	167.8	0.0	971.6
65.00		1.00	1.16	10.120	11.13	256.10	0.750	0.000	5.00	20.047	15.03	167.4	0.0	952.8
70.00		1.00	1.17	10.279	11.31	252.99	0.750	0.000	5.00	19.654	14.74	166.7	0.0	933.9
75.00		1.00	1.19	10.430	11.47	249.69	0.750	0.000	5.00	19.261	14.45	165.7	0.0	915.1
80.00		1.00	1.21	10.572	11.63	246.21	0.750	0.000	5.00	18.868	14.15	164.6	0.0	896.3
85.00		1.00	1.22	10.708	11.78	242.57	0.750	0.000	5.00	18.475	13.86	163.2	0.0	877.5
90.00		1.00	1.24	10.838	11.92	238.79	0.750	0.000	5.00	18.082	13.56	161.7	0.0	858.6
92.83	Bot - Section 3	1.00	1.25	10.909	12.00	236.59	0.750	0.000	2.83	10.072	7.55	90.6	0.0	478.2
95.00		1.00	1.25	10.962	12.06	234.87	0.750	0.000	2.17	7.720	5.79	69.8	0.0	636.9
98.92	Top - Section 2	1.00	1.26	11.055	12.16	231.72	0.750	0.000	3.92	13.769	10.33	125.6	0.0	1135.6
100.00		1.00	1.27	11.081	12.19	234.06	0.750	0.000	1.08	3.766	2.82	34.4	0.0	134.3
105.00		1.00	1.28	11.195	12.31	229.94	0.750	0.000	5.00	17.142	12.86	158.3	0.0	611.1
110.00		1.00	1.29	11.305	12.44	225.71	0.750	0.000	5.00	16.749	12.56	156.2	0.0	597.0
115.00		1.00	1.30	11.412	12.55	221.38	0.750	0.000	5.00	16.356	12.27	154.0	0.0	582.9
120.00		1.00	1.32	11.514	12.67	216.97	0.750	0.000	5.00	15.963	11.97	151.6	0.0	568.8
125.00		1.00	1.33	11.614	12.78	212.47	0.750	0.000	5.00	15.570	11.68	149.2	0.0	554.7
126.67	Bot - Section 4	1.00	1.33	11.646	12.81	210.95	0.750	0.000	1.67	5.113	3.83	49.1	0.0	182.1
130.00		1.00	1.34	11.710	12.88	207.90	0.750	0.000	3.33	10.188	7.64	98.4	0.0	641.7
132.00	Top - Section 3	1.00	1.34	11.748	12.92	206.04	0.750	0.000	2.00	6.045	4.53	58.6	0.0	380.7
135.00		1.00	1.35	11.803	12.98	205.84	0.750	0.000	3.00	8.925	6.69	86.9	0.0	248.1
140.00		1.00	1.36	11.894	13.08	201.14	0.750	0.000	5.00	14.577	10.93	143.0	0.0	405.2
145.00		1.00	1.37	11.982	13.18	196.36	0.750	0.000	5.00	14.184	10.64	140.2	0.0	394.2
147.00	Appurtenance(s)	1.00	1.37	12.017	13.22	194.44	0.750	0.000	2.00	5.564	4.17	55.2	0.0	154.6
150.00		1.00	1.38	12.068	13.27	191.53	0.750	0.000	3.00	8.227	6.17	81.9	0.0	228.6
155.00		1.00	1.39	12.152	13.37	186.64	0.750	0.000	5.00	13.398	10.05	134.3	0.0	372.3
159.00	Appurtenance(s)	1.00	1.40	12.217	13.44	182.68	0.750	0.000	4.00	10.436	7.83	105.2	0.0	289.9
160.00		1.00	1.40	12.233	13.46	181.69	0.750	0.000	1.00	2.570	1.93	25.9	0.0	71.4
165.00		1.00	1.41	12.313	13.54	176.68	0.750	0.000	5.00	12.612	9.46	128.1	0.0	350.3
170.00		1.00	1.42	12.390	13.63	171.63	0.750	0.000	5.00	12.219	9.16	124.9	0.0	339.3
175.00		1.00	1.42	12.466	13.71	166.53	0.750	0.000	5.00	11.826	8.87	121.6	0.0	328.3
177.00	Appurtenance(s)	1.00	1.43	12.496	13.75	164.47	0.750	0.000	2.00	4.620	3.47	47.6	0.0	128.2

Wind Loading - Shaft

Structure: CT01365-S-SBA	Code: EIA/TIA-222-G	10/13/2017
Site Name: Norwich 2 CT	Exposure: C	
Height: 180.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II
		Page: 41



180.00	Appurtenance(s)	1.00	1.43	12.540	13.79	161.38	0.750	0.000	3.00	6.813	5.11	70.5	0.0	189.0	
								Totals:	180.00			5,450.0			31,491.9

Discrete Appurtenance Forces

Structure: CT01365-S-SBA	Code: EIA/TIA-222-G	10/13/2017
Site Name: Norwich 2 CT	Exposure: C	
Height: 180.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II



Page: 42

Load Case: 1.0D + 1.0W 60 mph Wind

Dead Load Factor 1.00
Wind Load Factor 1.00



Iterations 24

No.	Elev (ft)	Description	Qty	qz (psf)	qzGh (psf)	CaAa x Ka	Ka	Total CaAa (sf)	Dead Load (lb)	Horiz Ecc (ft)	Vert Ecc (ft)	Wind FX (lb)	Mom Y (lb-ft)	Mom Z (lb-ft)	
1	180.00	Lightning Rod	1	12.540	13.794	1.00	1.00	0.50	5.00	0.000	0.000	6.90	0.00	0.00	
2	177.00	1900MHz RRUs	3	12.496	13.746	0.70	0.80	8.03	132.00	0.000	0.000	110.32	0.00	0.00	
3	177.00	APXVSPP18-C-A20	3	12.496	13.746	0.66	0.80	15.98	171.00	0.000	0.000	219.60	0.00	0.00	
4	177.00	APXVTM14-C-120	3	12.496	13.746	0.63	0.80	12.02	168.00	0.000	0.000	165.23	0.00	0.00	
5	177.00	TD-RRH8x20-25	3	12.496	13.746	0.55	0.80	6.71	210.00	0.000	0.000	92.19	0.00	0.00	
6	177.00	800 MHz RRUs	3	12.496	13.746	0.74	0.80	5.50	159.00	0.000	0.000	75.57	0.00	0.00	
7	177.00	ALU 800MHz External	3	12.496	13.746	0.55	0.80	1.29	26.40	0.000	0.000	17.76	0.00	0.00	
8	177.00	ACU-A20-N	4	12.496	13.746	0.63	0.80	0.35	4.00	0.000	0.000	4.86	0.00	0.00	
9	177.00	Platform w/ Hand Rail	1	12.496	13.746	1.00	1.00	32.00	1600.00	0.000	0.000	439.86	0.00	0.00	
10	159.00	BXA-171085-8BF-EDIN-2	3	12.217	13.439	0.67	0.80	5.93	31.50	0.000	0.000	79.65	0.00	0.00	
11	159.00	BXA-80080/4CF	3	12.217	13.439	0.61	0.80	8.76	42.90	0.000	0.000	117.66	0.00	0.00	
12	159.00	B25 RRH4x30	3	12.217	13.439	0.65	0.80	4.16	153.00	0.000	0.000	55.91	0.00	0.00	
13	159.00	SBNHH-1D65B	6	12.217	13.439	0.66	0.80	32.19	243.60	0.000	0.000	432.61	0.00	0.00	
14	159.00	Low Profile	1	12.217	13.439	1.00	1.00	22.00	1500.00	0.000	0.000	295.65	0.00	0.00	
15	159.00	DB-T1-6Z-8AB-OZ	2	12.217	13.439	0.57	0.80	5.45	37.80	0.000	0.000	73.28	0.00	0.00	
16	159.00	B25 RRH4x30	3	12.217	13.439	0.65	0.80	4.16	153.00	0.000	0.000	55.91	0.00	0.00	
17	159.00	RRH 4X45-PCS	3	12.217	13.439	0.78	0.80	6.37	180.00	0.000	0.000	85.66	0.00	0.00	
18	147.00	RRUS A2	3	12.017	13.219	0.49	0.80	2.73	66.00	0.000	0.000	36.05	0.00	0.00	
19	147.00	HPA-65R-BUU-H6	1	12.017	13.219	0.80	0.80	7.73	51.00	2.383	0.000	102.15	243.44	0.00	
20	147.00	HPA-65R-BUU-H8	2	12.017	13.219	0.71	0.80	18.50	136.00	0.000	0.000	244.60	0.00	0.00	
21	147.00	860 10025 RET	12	12.017	13.219	0.74	0.80	1.59	14.40	0.000	0.000	21.01	0.00	0.00	
22	147.00	RRUS 12	3	12.017	13.219	0.56	0.80	4.56	174.00	0.000	0.000	60.22	0.00	0.00	
23	147.00	LGP21401	6	12.017	13.219	0.54	0.80	4.15	84.60	0.000	0.000	54.84	0.00	0.00	
24	147.00	RRUS-11	6	12.017	13.219	0.54	0.80	8.10	306.00	0.000	0.000	107.13	0.00	0.00	
25	147.00	LGP21901 Diplexer	6	12.017	13.219	0.54	0.80	0.87	33.00	0.000	0.000	11.48	0.00	0.00	
26	147.00	DC6-48-60-18-8F("Squid")	1	12.017	13.219	1.00	1.00	0.92	31.80	2.383	0.000	12.16	28.98	0.00	
27	147.00	Low Profile	1	12.017	13.219	1.00	1.00	22.00	1500.00	0.000	0.000	290.81	0.00	0.00	
28	147.00	7770.00	6	12.017	13.219	0.60	0.80	19.77	210.00	0.000	0.000	261.38	0.00	0.00	
29	52.00	GPS	1	9.656	10.621	0.80	0.80	0.09	0.20	3.055	0.000	0.93	2.86	0.00	
Totals:									7,424.20						3,531.38

Total Applied Force Summary

Structure: CT01365-S-SBA	Code: EIA/TIA-222-G	10/13/2017
Site Name: Norwich 2 CT	Exposure: C	
Height: 180.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II




Page: 43

Load Case: 1.0D + 1.0W 60 mph Wind

Dead Load Factor 1.00

Wind Load Factor 1.00



Iterations 24

Elev (ft)	Description	Lateral FX (-) (lb)	Axial FY (-) (lb)	Torsion MY (lb-ft)	Moment MZ (lb-ft)
0.00		0.00	0.00	0.00	0.00
5.00		150.07	1496.68	0.00	0.00
10.00		147.66	1474.69	0.00	0.00
15.00		145.25	1452.70	0.00	0.00
17.00		58.88	574.92	0.00	0.00
20.00		90.63	855.79	0.00	0.00
25.00		156.16	1408.72	0.00	0.00
30.00		159.48	1386.73	0.00	0.00
35.00		161.86	1364.74	0.00	0.00
40.00		163.52	1342.75	0.00	0.00
45.00		164.59	1320.76	0.00	0.00
45.92		29.97	239.75	0.00	0.00
50.00		136.71	1881.83	0.00	0.00
52.00	(1) attachments	67.69	911.98	2.86	0.00
53.00		33.32	453.28	0.00	0.00
55.00		66.79	449.31	0.00	0.00
60.00		167.80	1110.09	0.00	0.00
65.00		167.37	1091.27	0.00	0.00
70.00		166.67	1072.44	0.00	0.00
75.00		165.73	1053.62	0.00	0.00
80.00		164.57	1034.79	0.00	0.00
85.00		163.21	1015.96	0.00	0.00
90.00		161.67	997.14	0.00	0.00
92.83		90.64	556.69	0.00	0.00
95.00		69.82	696.92	0.00	0.00
98.92		125.58	1244.13	0.00	0.00
100.00		34.43	164.27	0.00	0.00
105.00		158.32	749.59	0.00	0.00
110.00		156.21	735.48	0.00	0.00
115.00		153.98	721.37	0.00	0.00
120.00		151.64	707.27	0.00	0.00
125.00		149.18	693.16	0.00	0.00
126.67		49.12	228.37	0.00	0.00
130.00		98.42	733.51	0.00	0.00
132.00		58.59	435.88	0.00	0.00
135.00		86.91	330.67	0.00	0.00
140.00		143.04	542.94	0.00	0.00
145.00		140.21	531.94	0.00	0.00
147.00	(47) attachments	1256.99	2816.50	272.42	0.00
150.00		81.91	271.23	0.00	0.00
155.00		134.32	443.25	0.00	0.00
159.00	(24) attachments	1301.50	2688.49	0.00	0.00
160.00		25.93	74.01	0.00	0.00
165.00		128.11	363.46	0.00	0.00
170.00		124.91	352.47	0.00	0.00
175.00		121.63	341.48	0.00	0.00
177.00	(23) attachments	1173.03	2603.91	0.00	0.00

Total Applied Force Summary

Structure: CT01365-S-SBA	Code: EIA/TIA-222-G	10/13/2017	
Site Name: Norwich 2 CT	Exposure: C		
Height: 180.00 (ft)	Crest Height: 0.00		
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil		
Gh: 1.1	Topography: 1	Struct Class: II	Page: 44



180.00	(1) attachments	77.38	194.05	0.00	0.00
	Totals:	8,981.42	43,211.00	275.27	0.00

Linear Appurtenance Segment Forces (Factored)

Structure: CT01365-S-SBA	Code: EIA/TIA-222-G	10/13/2017
Site Name: Norwich 2 CT	Exposure: C	
Height: 180.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II




Page: 45

Load Case: 1.0D + 1.0W 60 mph Wind

Dead Load Factor 1.00

Wind Load Factor 1.00



Iterations 24

Top Elev (ft)	Description	Wind Exposed	Length (ft)	Ca	Exposed Width (in)	Area (sqft)	CaAa (sqft)	Ra	Cf Adjust Factor	qz (psf)	F X (lb)	Dead Load (lb)
5.00	1/2" Coax	Yes	5.00	0.000	0.65	0.27	0.00	0.011	0.000	7.442	0.00	0.80
10.00	1/2" Coax	Yes	5.00	0.000	0.65	0.27	0.00	0.011	0.000	7.442	0.00	0.80
15.00	1/2" Coax	Yes	5.00	0.000	0.65	0.27	0.00	0.011	0.000	7.442	0.00	0.80
17.00	1/2" Coax	Yes	2.00	0.000	0.65	0.11	0.00	0.012	0.000	7.631	0.00	0.32
20.00	1/2" Coax	Yes	3.00	0.000	0.65	0.16	0.00	0.012	0.000	7.896	0.00	0.48
25.00	1/2" Coax	Yes	5.00	0.000	0.65	0.27	0.00	0.012	0.000	8.276	0.00	0.80
30.00	1/2" Coax	Yes	5.00	0.000	0.65	0.27	0.00	0.012	0.000	8.600	0.00	0.80
35.00	1/2" Coax	Yes	5.00	0.000	0.65	0.27	0.00	0.012	0.000	8.883	0.00	0.80
40.00	1/2" Coax	Yes	5.00	0.000	0.65	0.27	0.00	0.012	0.000	9.137	0.00	0.80
45.00	1/2" Coax	Yes	5.00	0.000	0.65	0.27	0.00	0.013	0.000	9.366	0.00	0.80
45.92	1/2" Coax	Yes	0.92	0.000	0.65	0.05	0.00	0.013	0.000	9.406	0.00	0.15
50.00	1/2" Coax	Yes	4.08	0.000	0.65	0.22	0.00	0.013	0.000	9.576	0.00	0.65
52.00	1/2" Coax	Yes	2.00	0.000	0.65	0.11	0.00	0.013	0.000	9.656	0.00	0.32
Totals:											0.0	8.3

Calculated Forces

Structure: CT01365-S-SBA	Code: EIA/TIA-222-G	10/13/2017
Site Name: Norwich 2 CT	Exposure: C	
Height: 180.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II



Load Case: 1.0D + 1.0W 60 mph Wind

Iterations 24

Dead Load Factor 1.00
Wind Load Factor 1.00



Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (-) (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	phi Pn (kips)	phi Vn (kips)	phi Tn (ft-kips)	phi Mn (ft-kips)	Total Deflect (in)	Rotation Sway (deg)	Rotation Twist (deg)	Stress Ratio
0.00	-43.21	-8.99	-0.27	-1085.9	0.00	1085.91	5397.55	2698.78	12826.5	6367.63	0.00	0.000	0.000	0.135
5.00	-41.71	-8.87	-0.27	-1040.9	0.00	1040.94	5344.66	2672.33	12495.2	6203.15	0.02	-0.034	0.000	0.133
10.00	-40.23	-8.74	-0.27	-996.60	0.00	996.60	5290.67	2645.34	12165.4	6039.43	0.07	-0.068	0.000	0.130
15.00	-38.77	-8.61	-0.27	-952.89	0.00	952.89	5235.58	2617.79	11837.2	5876.53	0.16	-0.102	0.000	0.127
17.00	-38.19	-8.56	-0.27	-935.67	0.00	935.67	5213.23	2606.61	11706.5	5811.61	0.21	-0.116	0.000	0.126
17.00	-38.19	-8.56	-0.27	-935.67	0.00	935.67	5213.23	2606.61	11706.5	5811.61	0.21	-0.116	0.000	0.126
20.00	-37.33	-8.49	-0.27	-909.98	0.00	909.98	5179.37	2589.69	11510.9	5714.52	0.29	-0.137	0.000	0.166
25.00	-35.92	-8.36	-0.27	-867.52	0.00	867.52	5122.07	2561.03	11186.5	5553.45	0.46	-0.183	0.000	0.163
30.00	-34.52	-8.22	-0.27	-825.71	0.00	825.71	5063.65	2531.83	10864.1	5393.40	0.67	-0.229	0.000	0.160
35.00	-33.15	-8.08	-0.27	-784.59	0.00	784.59	5004.13	2502.07	10543.8	5234.42	0.94	-0.275	0.000	0.157
40.00	-31.81	-7.94	-0.28	-744.17	0.00	744.17	4943.51	2471.75	10225.9	5076.58	1.25	-0.321	0.000	0.153
45.00	-30.48	-7.78	-0.28	-704.48	0.00	704.48	4881.77	2440.89	9910.40	4919.94	1.61	-0.367	0.000	0.149
45.92	-30.24	-7.76	-0.28	-697.35	0.00	697.35	4870.34	2435.17	9852.83	4891.36	1.68	-0.376	0.000	0.149
50.00	-28.36	-7.63	-0.28	-665.66	0.00	665.66	4818.94	2409.47	9597.43	4764.57	2.02	-0.414	0.000	0.146
52.00	-27.44	-7.56	-0.27	-650.41	0.00	650.41	4793.49	2396.75	9472.99	4702.79	2.20	-0.433	0.000	0.144
53.00	-26.99	-7.53	-0.27	-642.85	0.00	642.85	3921.66	1960.83	7862.59	3903.32	2.29	-0.442	0.000	0.172
55.00	-26.53	-7.47	-0.27	-627.80	0.00	627.80	3903.31	1951.65	7765.73	3855.23	2.48	-0.461	0.000	0.170
60.00	-25.42	-7.32	-0.27	-590.43	0.00	590.43	3856.65	1928.33	7524.53	3735.49	2.99	-0.512	0.000	0.165
65.00	-24.32	-7.16	-0.27	-553.83	0.00	553.83	3808.89	1904.45	7284.80	3616.48	3.55	-0.563	0.000	0.160
70.00	-23.25	-7.01	-0.27	-518.02	0.00	518.02	3760.03	1880.02	7046.68	3498.27	4.17	-0.614	0.000	0.154
75.00	-22.19	-6.85	-0.27	-482.99	0.00	482.99	3710.06	1855.03	6810.28	3380.91	4.84	-0.664	0.000	0.149
80.00	-21.15	-6.69	-0.27	-448.75	0.00	448.75	3658.99	1829.49	6575.75	3264.48	5.56	-0.714	0.000	0.143
85.00	-20.13	-6.53	-0.27	-415.30	0.00	415.30	3606.81	1803.40	6343.20	3149.03	6.34	-0.763	0.000	0.137
90.00	-19.13	-6.37	-0.27	-382.65	0.00	382.65	3553.52	1776.76	6112.76	3034.63	7.16	-0.812	0.000	0.131
92.83	-18.57	-6.28	-0.27	-364.61	0.00	364.61	3522.83	1761.42	5983.17	2970.30	7.65	-0.839	0.000	0.128
95.00	-17.87	-6.21	-0.27	-351.01	0.00	351.01	3499.13	1749.56	5884.57	2921.35	8.04	-0.860	0.000	0.125
98.92	-16.63	-6.07	-0.27	-326.71	0.00	326.71	2350.25	1175.12	3954.81	1963.33	8.76	-0.897	0.000	0.174
100.00	-16.46	-6.04	-0.27	-320.14	0.00	320.14	2343.93	1171.97	3924.64	1948.36	8.97	-0.907	0.000	0.171
105.00	-15.71	-5.89	-0.27	-289.94	0.00	289.94	2314.11	1157.05	3785.67	1879.37	9.95	-0.964	0.000	0.161
110.00	-14.97	-5.73	-0.27	-260.51	0.00	260.51	2283.18	1141.59	3647.23	1810.64	10.99	-1.020	-0.001	0.150
115.00	-14.25	-5.58	-0.27	-231.86	0.00	231.86	2251.15	1125.57	3509.45	1742.24	12.08	-1.074	-0.001	0.139
120.00	-13.54	-5.42	-0.27	-203.97	0.00	203.97	2218.01	1109.01	3372.44	1674.22	13.24	-1.124	-0.001	0.128
125.00	-12.85	-5.27	-0.27	-176.86	0.00	176.86	2183.77	1091.88	3236.35	1606.66	14.44	-1.172	-0.001	0.116
126.67	-12.62	-5.22	-0.27	-168.06	0.00	168.06	2172.08	1086.04	3191.13	1584.21	14.85	-1.188	-0.001	0.112
130.00	-11.88	-5.11	-0.27	-150.69	0.00	150.69	2148.42	1074.21	3101.30	1539.62	15.69	-1.217	-0.001	0.103
132.00	-11.45	-5.05	-0.27	-140.45	0.00	140.45	1502.55	751.27	2180.88	1082.68	16.21	-1.235	-0.001	0.137
135.00	-11.12	-4.96	-0.27	-125.33	0.00	125.33	1491.20	745.60	2130.02	1057.43	16.99	-1.259	-0.001	0.126
140.00	-10.57	-4.81	-0.27	-100.54	0.00	100.54	1471.39	735.69	2045.11	1015.28	18.33	-1.303	-0.001	0.106
145.00	-10.04	-4.66	-0.27	-76.49	-0.01	76.49	1450.46	725.23	1960.22	973.13	19.72	-1.340	-0.001	0.086
147.00	-7.25	-3.34	0.00	-67.16	0.00	67.16	1441.79	720.89	1926.30	956.30	20.28	-1.354	-0.001	0.075
150.00	-6.98	-3.26	0.00	-57.14	0.00	57.14	1428.44	714.22	1875.49	931.07	21.14	-1.371	-0.001	0.066
155.00	-6.54	-3.11	0.00	-40.86	0.00	40.86	1405.30	702.65	1791.05	889.15	22.59	-1.396	-0.001	0.051
159.00	-3.89	-1.75	0.00	-28.40	0.00	28.40	1386.00	693.00	1723.78	855.76	23.77	-1.411	-0.001	0.036
160.00	-3.81	-1.72	0.00	-26.66	0.00	26.66	1381.06	690.53	1707.02	847.43	24.06	-1.414	-0.001	0.034
165.00	-3.45	-1.58	0.00	-18.06	0.00	18.06	1355.72	677.86	1623.53	805.99	25.55	-1.428	-0.001	0.025
170.00	-3.10	-1.45	0.00	-10.14	0.00	10.14	1329.27	664.63	1540.71	764.87	27.05	-1.437	-0.001	0.016
175.00	-2.77	-1.32	0.00	-2.89	0.00	2.89	1301.71	650.86	1458.68	724.15	28.56	-1.442	-0.001	0.006
177.00	-0.19	-0.08	0.00	-0.25	0.00	0.25	1290.38	645.19	1426.13	707.99	29.16	-1.442	-0.001	0.000

Calculated Forces

Structure: CT01365-S-SBA	Code: EIA/TIA-222-G	10/13/2017
Site Name: Norwich 2 CT	Exposure: C	
Height: 180.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Page: 47
Struct Class: II		



180.00	0.00	-0.08	0.00	0.00	0.00	0.00	0.00	1273.05	636.53	1377.59	683.89	30.07	-1.442	-0.001	0.000
--------	------	-------	------	------	------	------	------	---------	--------	---------	--------	-------	--------	--------	-------

Final Analysis Summary

Structure: CT01365-S-SBA	Code: EIA/TIA-222-G	10/13/2017
Site Name: Norwich 2 CT	Exposure: C	
Height: 180.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II



Page: 48

Reactions

Load Case	Shear FX (kips)	Shear FZ (kips)	Axial FY (kips)	Moment MX (ft-kips)	Moment MY (ft-kips)	Moment MZ (ft-kips)
1.2D + 1.6W 105 mph Wind	44.1	0.00	51.79	0.02	0.82	5345.81
0.9D + 1.6W 105 mph Wind	44.1	0.00	38.82	0.01	0.82	5293.13
1.2D + 1.0Di + 1.0Wi 50 mph Wind	10.1	0.00	77.87	0.00	0.23	1249.70
1.2D + 1.0E	1.7	0.00	51.85	0.00	0.00	211.63
0.9D + 1.0E	1.7	0.00	38.89	0.00	0.00	209.37
1.0D + 1.0W 60 mph Wind	9.0	0.00	43.21	0.00	0.27	1085.91

Max Stresses

Load Case	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (-) (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	phi Pn (kips)	phi Vn (kips)	phi Tn (ft-kips)	phi Mn (ft-kips)	Elev (ft)	Stress Ratio
1.2D + 1.6W 105 mph Wind	-17.80	-29.92	-0.82	-1609.6	-0.04	-1609.6	2350.25	1175.1	3954.81	1963.33	98.92	0.828
0.9D + 1.6W 105 mph Wind	-12.83	-29.52	-0.82	-1584.8	-0.03	-1584.8	2350.25	1175.1	3954.81	1963.33	98.92	0.813
1.2D + 1.0Di + 1.0Wi 50 mph Wind	-36.16	-7.02	-0.22	-380.59	0.00	-380.59	2350.25	1175.1	3954.81	1963.33	98.92	0.209
1.2D + 1.0E	-20.06	-1.10	0.00	-77.64	0.00	-77.64	2350.25	1175.1	3954.81	1963.33	98.92	0.048
0.9D + 1.0E	-15.05	-1.08	0.00	-76.52	0.00	-76.52	2350.25	1175.1	3954.81	1963.33	98.92	0.045
1.0D + 1.0W 60 mph Wind	-16.63	-6.07	-0.27	-326.71	0.00	-326.71	2350.25	1175.1	3954.81	1963.33	98.92	0.174

Additional Steel Summary

Elev From (ft)	Elev To (ft)	Member	Intermediate Connectors			Lower Termination				Upper Termination				Max Member			
			VQ/I (lb/in)	Vu (kips)	phi Vn (kips)	MQ/I (kips)	phi Vn (kips)	Num Reqd	Num Actual	MQ/I (kips)	phi Vn (kips)	Num Reqd	Num Actual	Pu (kips)	phi Pn (kips)	phi Tn (kips)	Ratio
0.0	17.0	(3) PLT-7.5"x1.25"(1.25"hole)	284.7	5.12	37.1	393.7	37.1	11	14	374.5	37.1	11	14	393.67	516.9	468.75	0.840



Monopole Mat Foundation Design

Date
10/13/2017

Customer Name:	Sprint Nextel	EIA/TIA Standard:	EIA-222-G
Site Name:		Structure Height (Ft.):	180
Site Number:	CT01365-S-SBA	Engineer Name:	J. Chen
Engr. Number:	40634	Engineer Login ID:	

Foundation Info Obtained from:

Drawings/Calculations
Monopole
Analysis

Structure Type:

Analysis or Design?



Base Reactions (Factored):

Axial Load (Kips):	77.9	Shear Force (Kips):	44.1
Uplift Force (Kips):	0.0	Moment (Kips-ft):	5345.8

Allowable overstress %: 5.0%

Foundation Geometries:

		Mods required -Yes/No ?:	No
Diameter of Pier (ft.):	8.0	Depth of Base BG (ft.):	11.0
Pier Height A. G. (ft.):	0.50	Thickness of Pad (ft):	2.50
Length of Pad (ft.):	22.5	Width of Pad (ft.):	22.5
Final Length of pad (ft)	22.5	Final width of pad (ft):	22.5
Control Value for Cell D18:	0	Control Value for Cell F18:	0



Material Properties and Rebar Info:

Concrete Strength (psi):	4000	Steel Elastic Modulus:	29000	ksi
Vertical bar yield (ksi)	60	Tie steel yield (ksi):	40	
Vertical Rebar Size #:	10	Tie / Stirrup Size #:	5	
Qty. of Vertical Rebars:	36	Tie Spacing (in):	12.0	
Pad Rebar Yield (Ksi):	60	Pad Steel Rebar Size (#):	10	
Concrete Cover (in.):	3	Unit Weight of Concrete:	150.0	pcf
Rebar at the bottom of the concrete pad:				
Qty. of Rebar in Pad (L):	20	Qty. of Rebar in Pad (W):	20	
Rebar at the top of the concrete pad:				
Qty. of Rebar in Pad (L):	20	Qty. of Rebar in Pad (W):	20	

Apply 1.35 factor for e/w Per G: 1.35

Soil Design Parameters:

Soil Unit Weight (pcf):	125.0	Soil Buoyant Weight:	50.0	Pcf
Water Table B.G.S. (ft):	7.0	Unit Weight of Water:	62.4	pcf
Ultimate Bearing Pressure (psf):	10000	Ultimate Skin Friction:	175	Psf
Consider Friction for O.T.M. (Y/N):	No	Consider Friction for bearing (Y/N):	No	
Consider soil hor. resist. for OTM.:	No	Reduction factor on the maximum soil bearing pressure:	1.00	
		Angle from Top of Pad:	30	
		Angle from Bottm of Pad:	25	
		Angle from Bottm of Pad:	25	

Foundation Analysis and Design:

Uplift Strength Reduction Factor:	0.75	Compression Strength Reduction Factor:	0.75
Total Dry Soil Volume (cu. Ft.):	3191.89	Total Dry Soil Weight (Kips):	398.99
Total Buoyant Soil Volume (cu. Ft.):	743.18	Total Buoyant Soil Weight (Kips):	37.16
Total Effective Soil Weight (Kips):	436.15	Weight from the Concrete Block at Top (K):	0.00
Total Dry Concrete Volume (cu. Ft.):	376.99	Total Dry Concrete Weight (Kips):	56.55
Total Buoyant Concrete Volume (cu. Ft.):	1341.02	Total Buoyant Concrete Weight (Kips):	117.47
Total Effective Concrete Weight (Kips):	174.02	Total Vertical Load on Base (Kips):	688.07

Check Soil Capacities:

Calculated Maxium Net Soil Pressure under the base (psf):	6449	<	Allowable Factored Soil Bearing (psf):	7500	0.86	OK!
Allowable Foundation Overturning Resistance (kips-ft.):	7024.4	>	Design Factored Momont (kips-ft):	5853	0.83	OK!
Factor of Safety Against Overturning (O. R. Moment/Design Moment):	1.20					OK!

Load/
Capacity
Ratio

Check the capacities of Reinforcing Concrete:

Strength reduction factor (Flexure and axial tension): 0.90 Strength reduction factor (Shear): 0.75
 Strength reduction factor (Axial compression): 0.65 Wind Load Factor on Concrete Design: 1.00

Load/
Capacity
Ratio

(1) Concrete Pier:

Vertical Steel Rebar Area (sq. in./each):	1.27	Tie / Stirrup Area (sq. in./each):	0.31		
Calculated Moment Capacity (Mn,Kips-Ft):	8888.9	> Design Factored Moment (Mu, Kips-Ft)	5742.7	0.65	OK!
Calculated Shear Capacity (Kips):	845.4	> Design Factored Shear (Kips):	44.1	0.05	OK!
Calculated Tension Capacity (Tn, Kips):	2468.9	> Design Factored Tension (Tu Kips):	0.0	0.00	OK!
Calculated Compression Capacity (Pn, Kips):	12716.4	> Design Factored Axial Load (Pu Kips):	77.9	0.01	OK!
Moment & Axial Strength Combination:	0.65	OK! Check Tie Spacing (Design/Required):		1	OK!
Pier Reinforcement Ratio:	0.006	Reinforcement Ratio is satisfied per ACI			

(2).Concrete Pad:

One-Way Design Shear Capacity (L-Direction, Kips):	675.6	> One-Way Factored Shear (L-D. Kips):	388.8	0.58	OK!
One-Way Design Shear Capacity (W-Direction, Kips):	675.6	> One-Way Factored Shear (W-D., Kips)	388.8	0.58	OK!
One-Way Design Shear Capacity (Corner-Corner. Kips):	715.2	> One-Way Factored Shear (C-C, Kips):	392.3	0.55	OK!
Lower Steel Pad Reinforcement Ratio (L-Direct.):	0.0036	OK! Lower Steel Pad Reinf. Ratio (W-Direct	0.0036		
Lower Steel Pad Moment Capacity (L-Direction. Kips-ft):	2919.8	> Moment at Bottom (L-Direct. K-Ft):	982.2	0.34	OK!
Lower Steel Pad Moment Capacity (W-Direction. Kips-ft):	2919.8	> Moment at Bottom (W-Direct. K-Ft):	982.2	0.34	OK!
Lower Steel Pad Moment Capacity (Corner-Corner,K-ft):	4084.1	> Moment at Bottom (C-C Dir. K-Ft):	1389.1	0.34	OK!
Upper Steel Pad Reinforcement Ratio (L-Direct.):	0.0036	OK! Upper Steel Reinf. Ratio (W-Direct.):	0.0036		
Upper Steel Pad Moment Capacity (L-Direction. Kips-ft):	2919.8	> Moment at the top (L-Dir Kips-Ft):	530.8	0.18	OK!
Upper Steel Pad Moment Capacity (W-Direction. Kips-ft):	2919.8	> Moment at the top (W-Dir Kips-Ft):	530.8	0.18	OK!
Upper Steel Pad Moment Capacity (Corner-Corner. K-ft):	4084.1	> Moment at the top (C-C Direc. K-Ft):	489.9	0.12	OK!

SPECIAL CONSTRUCTION NOTE:
 SPRINT TOWER TOP WORK IS CONTINGENT ON THE FOLLOWING:
 * COMPLETION OF A GLOBAL STRUCTURAL STABILITY ANALYSIS (PROVIDED BY TOWER OWNER).
 * COMPLETION OF AN ANTENNA/RRH MOUNT STRUCTURAL ASSESSMENT (PROVIDED BY A&E VENDOR).
 * GC SHALL FURNISH, INSTALL AND COMPLETE ALL REQUIRED STRUCTURAL MODIFICATIONS AS INDICATED IN BEFORE-MENTIONED ANALYSIS AND ASSESSMENT.
 * SBA COMMUNICATIONS CORPORATION SHALL PROVIDE WRITTEN ACCEPTANCE/APPROVAL FOR THE COMPLETION OF ALL TOWER/FOUNDATION STRUCTURAL MODIFICATIONS INCLUDING (AS NECESSARY) CONTROLLED CONSTRUCTION INSPECTIONS, SHOP-DRAWING APPROVALS, MATERIALS TEST RESULTS, AND FINAL ENGINEER'S AFFIDAVIT.



NOTE:
 OWNER AND TENANT MAY, FROM TIME TO TIME AT TENANT'S OPTION, REPLACE THIS EXHIBIT WITH AN EXHIBIT SETTING FORTH THE LEGAL DESCRIPTION OF THE SITE, OR WITH ENGINEERED OR AS-BUILT DRAWING DEPICTING THE SITE OR ILLUSTRATING STRUCTURAL MODIFICATIONS OR CONSTRUCTION PLANS OF THE SITE. ANY VISUAL OR TEXTUAL REPRESENTATION OF THE EQUIPMENT LOCATED WITHIN THE SITE CONTAINED IN THESE OTHER DOCUMENTS IS ILLUSTRATIVE ONLY, AND DOES NOT LIMIT THE RIGHTS OF SPRINT AS PROVIDED FOR IN THE AGREEMENT. THE LOCATIONS OF ANY ACCESS AND UTILITY EASEMENTS ARE ILLUSTRATIVE ONLY. ACTUAL LOCATIONS MAY BE DETERMINED BY TENANT AND/OR THE SERVICING UTILITY COMPANY IN COMPLIANCE WITH LOCAL LAWS AND REGULATIONS.

NOTE:
 THESE PLANS ARE BASED ON INFORMATION OBTAINED FROM PHOTOS BY OTHERS DATED JUNE, 2013. THEY HAVE NOT BEEN FIELD VERIFIED. THE SPRINT CONTRACTOR IS RESPONSIBLE TO VERIFYING ALL ITEMS AND NOTIFYING THE ENGINEER OF RECORD AND DISCREPANCIES.

PROJECT: 2.5 EQUIPMENT DEPLOYMENT
SITE NAME: SBA
SITE CASCADE: CT23XC501-A
MARKET: NORTHERN CONNECTICUT
SBA SITE ID: CT01365-S/NORWICH 2 CT
SITE ADDRESS: 300 PLAN HILL ROAD
 NORWICH, CT 06360
SITE TYPE: 180' MONOPOLE




1 INTERNATIONAL BLVD, SUITE 800
 MAHWAH, NJ 07495
 TEL: (800) 357-7641



SBA COMMUNICATIONS CORP.
 134 FLANDERS ROAD, SUITE 125
 WESTBOROUGH, MA 01581
 TEL: (508) 251-0720
 FAX: (508) 251-1755



45 BEECHWOOD DRIVE
 N. ANDOVER, MA 01845
 TEL: (978) 557-5553
 FAX: (978) 336-5586



SITE INFORMATION

AREA MAP

PROJECT DESCRIPTION

DRAWING INDEX

PROPERTY OWNER:
 KELVIN H STOTT
 300 PLAIN HILL ROAD
 NORWICH, CT 06360

TOWER OWNER:
 SBA PROPERTIES, LLC.
 5900 BROKEN SOUND PARKWAY, NW
 BOCA RATON, FL 33487-2797
 PHONE: 561-226-9523

SBA REGIONAL SITE MANAGER:
 STEPHEN ROTH
 PHONE: 860-539-4920
 SROth@sbasite.com

LATITUDE (NAD83):
GOOGLE EARTH 2-C CONFIRMATION
 41° 34' 41.52" N
 41.576949°

LONGITUDE (NAD83):
GOOGLE EARTH 2-C CONFIRMATION
 -72° 6' 13.23 W
 -72.103620°



SPRINT EQUIPMENT MODIFICATIONS REQUIRED TO SUPPORT MODERNIZATION OF AN EXISTING WIRELESS COMMUNICATIONS FACILITY AND UTILIZATION OF FCC BROADBAND SPECTRUM LICENSE FOR 2.5GHz FREQUENCY, INCLUDING INSTALLATION OF:

GROUND-LEVEL RAN EQUIPMENT, CONSISTING OF:
 * RETROFIT EXISTING MMBTS CABINET WITH (1) RECTIFIER SHELF, (3) RECTIFIERS, 2.5 RADIO ACCESS NETWORK (RAN) EQUIPMENT & BBU KIT
 * INSTALL (1) ADDITIONAL BATTERY STRING INSIDE EXISTING BATTERY CABINET

TOWER-TOP EQUIPMENT, INCLUDING INSTALLATION OF:
 * (3) PANEL ANTENNAS
 * (3) REMOTE RADIO HEADS (RRH)
 * (1) HYBRID CABLE (AND ASSOCIATED FIBER, DC POWER, COAXIAL CABLE JUMPERS AND ANTENNA REMOTE ELECTRICAL-TILT (RET) CABLE

SPECIAL ZONING NOTE:
 BASED ON INFORMATION PROVIDED BY SPRINT REGULATORY COMPLIANCE PROFESSIONALS AND LEGAL COUNSEL, THIS TELECOMMUNICATIONS EQUIPMENT DEPLOYMENT IS CONSIDERED AN ELIGIBLE FACILITY UNDER THE TAX RELIEF ACT OF 2012, 47 USC 1455(A), AND IS SUBJECT TO AN EXPEDITED ELIGIBLE FACILITIES REQUEST/REVIEW AND ZONING PRE-EMPTION FOR LOCAL DISCRETIONARY PERMITS (VARIANCE, SPECIAL PERMIT, SITE PLAN REVIEW, ADMINISTRATIVE REVIEW).

SHEET NO:	SHEET TITLE	REV	CHK	BY
T-1	TITLE SHEET	2	BB	DJM
SP-1	OUTLINE SPECIFICATIONS	2	BB	DJM
SP-2	OUTLINE SPECIFICATIONS	2	BB	DJM
SP-3	OUTLINE SPECIFICATIONS	2	BB	DJM
A-1	COMPOUND PLAN	2	BB	DJM
A-2	ELEVATION AND ANTENNA PLANS	2	BB	DJM
A-3	RF DATA SHEET	2	BB	DJM
A-4	RAN WIRING DIAGRAM	2	BB	DJM
A-5	EQUIPMENT DETAILS	2	BB	DJM
A-6	EQUIPMENT DETAILS	2	BB	DJM
S-1	STRUCTURAL DETAILS	2	BB	DJM
E-1	ONE LINE DIAGRAM	2	BB	DJM
E-2	GROUNDING DETAILS AND NOTES	2	BB	DJM

COUNTY:
 NEW LONDON

POWER COMPANY:
 CL & P

AAV PROVIDER:
 AT&T

SPRINT CONSTRUCTION MANAGER:
 MICHAEL DELIA
 PHONE: 781-316-6348
 Michael.Delia@sprint.com



GENERAL NOTES

- THIS IS AN UNMANNED TELECOMMUNICATION FACILITY AND NOT FOR HUMAN HABITATION:
 - ADA COMPLIANCE NOT REQUIRED.
 - POTABLE WATER OR SANITARY SERVICE IS NOT REQUIRED.
 - NO OUTDOOR STORAGE OR ANY SOLID WASTE RECEPTACLES REQUIRED.
- CONTRACTOR SHALL VERIFY ALL PLANS, EXISTING DIMENSIONS, AND CONDITIONS ON JOB SITE. CONTRACTOR SHALL IMMEDIATELY NOTIFY THE ARCHITECT/ENGINEER IN WRITING OF ANY DISCREPANCIES BEFORE PROCEEDING WITH THE WORK. FAILURE TO NOTIFY THE ARCHITECT/ENGINEER PLACE THE RESPONSIBILITY ON THE CONTRACTOR TO CORRECT THE DISCREPANCIES AT THE CONTRACTOR'S EXPENSE.
- NEW CONSTRUCTION WILL CONFORM TO ALL APPLICABLE CODES AND ORDINANCES.
 BUILDING CODE: IBC 2012 W/ 2016 CT STATE BUILDING CODE AMENDMENTS
 ELECTRICAL CODE: 2014 NATIONAL ELECTRICAL CODE
 STRUCTURAL CODE: (TIA) 222-G STRUCTURAL STANDARDS FOR ANTENNA SUPPORTING STRUCTURES AND ANTENNAS.

APPROVALS

THE FOLLOWING PARTIES HEREBY APPROVE AND ACCEPT THESE DOCUMENTS AND AUTHORIZE THE CONTRACTOR TO PROCEED WITH THE CONSTRUCTION DESCRIBED HEREIN. ALL DOCUMENTS ARE SUBJECT TO REVIEW BY THE LOCAL BUILDING DEPARTMENT AND MAY IMPOSE CHANGES OR MODIFICATIONS.

SPRINT: _____ DATE: _____

CONSTRUCTION MANAGER: _____ DATE: _____

LEASING/SITE ACQUISITION: _____ DATE: _____

RF ENGINEER: _____ DATE: _____

LANDLORD/TOWER OWNER: _____ DATE: _____

CHECKED BY: BB
 APPROVED BY: DJC

SUBMITTALS

REV.	DATE	DESCRIPTION	BY
2	09/28/17	CONSTRUCTION FINAL	DJM
1	05/08/14	ISSUED FOR CONSTRUCTION	SF
0	05/02/14	ISSUED FOR CONSTRUCTION	SF

SITE NUMBER:
 CT23XC501-A

SITE NAME:
 SBA

SITE ADDRESS:
 300 PLAIN HILL ROAD
 NORWICH, CT 06360

SHEET TITLE
 TITLE SHEET

SHEET NUMBER
 T-1



THESE OUTLINE SPECIFICATIONS IN CONJUNCTION WITH THE SPRINT STANDARD CONSTRUCTION SPECIFICATIONS, INCLUDING CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

SECTION 01 100 – SCOPE OF WORK

PART 1 – GENERAL

1.1 **THE WORK:** THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE SPRINT CONSTRUCTION STANDARDS FOR WIRELESS SITES, CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

1.2 **RELATED DOCUMENTS:**

- A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
- B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.

1.3 **PRECEDENCE:** SHOULD CONFLICTS OCCUR BETWEEN THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES INCLUDING THE STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES AND THE CONSTRUCTION DRAWINGS, INFORMATION ON THE CONSTRUCTION DRAWINGS SHALL TAKE PRECEDENCE. NOTIFY SPRINT CONSTRUCTION MANAGER IF THIS OCCURS.

1.4 **NATIONALLY RECOGNIZED CODES AND STANDARDS:**

- A. THE WORK SHALL COMPLY WITH APPLICABLE NATIONAL AND LOCAL CODES AND STANDARDS, LATEST EDITION, AND PORTIONS THEREOF, INCLUDED BUT NOT LIMITED TO THE FOLLOWING:
 1. GR-78-CORE GENERIC REQUIREMENTS FOR THE PHYSICAL DESIGN AND MANUFACTURE OF TELECOMMUNICATIONS EQUIPMENT.
 2. GR-1089 CORE, ELECTROMAGNETIC COMPATIBILITY AND ELECTRICAL SAFETY –GENERIC CRITERIA FOR NETWORK TELECOMMUNICATIONS EQUIPMENT.
 3. NATIONAL FIRE PROTECTION ASSOCIATION CODES AND STANDARDS (NFPA) INCLUDING NFPA 70 (NATIONAL ELECTRICAL CODE – "NEC") AND NFPA 101 (LIFE SAFETY CODE).
 4. AMERICAN SOCIETY FOR TESTING OF MATERIALS (ASTM)
 5. INSTITUTE OF ELECTRONIC AND ELECTRICAL ENGINEERS (IEEE)
 6. AMERICAN CONCRETE INSTITUTE (ACI)
 7. AMERICAN WIRE PRODUCERS ASSOCIATION (AWPA)
 8. CONCRETE REINFORCING STEEL INSTITUTE (CRSI)
 9. AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)
 10. PORTLAND CEMENT ASSOCIATION (PCA)
 11. NATIONAL CONCRETE MASONRY ASSOCIATION (NCMA)
 12. BRICK INDUSTRY ASSOCIATION (BIA)
 13. AMERICAN WELDING SOCIETY (AWS)
 14. NATIONAL ROOFING CONTRACTORS ASSOCIATION (NRCA)
 15. SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)
 16. DOOR AND HARDWARE INSTITUTE (DHI)
 17. OCCUPATIONAL SAFETY AND HEALTH ACT (OSHA)
 18. APPLICABLE BUILDING CODES INCLUDING UNIFORM BUILDING CODE, SOUTHERN BUILDING CODE, BOCA, AND THE INTERNATIONAL BUILDING CODE.

1.5 **DEFINITIONS:**

- A. WORK: THE SUM OF TASKS AND RESPONSIBILITIES IDENTIFIED IN THE CONTRACT DOCUMENTS.
- B. COMPANY: SPRINT CORPORATION
- C. ENGINEER: SYNONYMOUS WITH ARCHITECT & ENGINEER AND "A&E". THE DESIGN PROFESSIONAL HAVING PROFESSIONAL RESPONSIBILITY FOR DESIGN OF THE PROJECT.
- D. CONTRACTOR: CONSTRUCTION CONTRACTOR; CONSTRUCTION VENDOR; INDIVIDUAL OR ENTITY WHO AFTER EXECUTION OF A CONTRACT IS BOUND TO ACCOMPLISH THE WORK.
- E. THIRD PARTY VENDOR OR AGENCY: A VENDOR OR AGENCY ENGAGED SEPARATELY BY THE COMPANY, A&E, OR CONTRACTOR TO PROVIDE MATERIALS OR TO ACCOMPLISH SPECIFIC TASKS RELATED TO BUT NOT INCLUDED IN THE WORK.
- F. OFCI: OWNER FURNISHED, CONTRACTOR INSTALLED EQUIPMENT.
- G. CONSTRUCTION MANAGER – ALL PROJECTS RELATED COMMUNICATION TO FLOW THROUGH SPRINT REPRESENTATIVE IN CHARGE OF PROJECT...

1.6 **SITE FAMILIARITY:** CONTRACTOR SHALL BE RESPONSIBLE FOR FAMILIARIZING HIMSELF WITH ALL CONTRACT DOCUMENTS, FIELD CONDITIONS AND DIMENSIONS PRIOR TO PROCEEDING WITH CONSTRUCTION. ANY DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE SPRINT CONSTRUCTION MANAGER PRIOR TO THE COMMENCEMENT OF WORK. NO COMPENSATION WILL BE AWARDED BASED ON CLAIM OF LACK OF KNOWLEDGE OR FIELD CONDITIONS.

1.7 **POINT OF CONTACT:** COMMUNICATION BETWEEN SPRINT AND THE CONTRACTOR SHALL FLOW THROUGH THE SINGLE SPRINT CONSTRUCTION MANAGER APPOINTED TO MANAGE THE PROJECT FOR SPRINT.

1.8 **ON-SITE SUPERVISION:** THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK AND SHALL BE RESPONSIBLE FOR CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES IN ACCORDANCE WITH THE CONTRACT DOCUMENTS. THE CONTRACTOR SHALL EMPLOY A COMPETENT SUPERINTENDENT WHO SHALL BE IN ATTENDANCE AT THE SITE AT ALL TIMES DURING PERFORMANCE OF THE WORK.

1.9 **DRAWINGS, SPECIFICATIONS AND DETAILS REQUIRED AT JOBSITE:** THE CONSTRUCTION CONTRACTOR SHALL MAINTAIN A FULL SET OF THE CONSTRUCTION DRAWINGS, STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES AND THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES AT THE JOBSITE FROM MOBILIZATION THROUGH CONSTRUCTION COMPLETION.

- A. THE JOBSITE DRAWINGS, SPECIFICATIONS AND DETAILS SHALL BE CLEARLY MARKED DAILY IN RED PENCIL WITH ANY CHANGES IN CONSTRUCTION OVER WHAT IS DEPICTED IN THE DOCUMENTS. AT CONSTRUCTION COMPLETION, THIS JOBSITE MARKUP SET SHALL BE DELIVERED TO THE COMPANY OR COMPANY'S DESIGNATED REPRESENTATIVE TO BE FORWARDED TO THE COMPANY'S A&E VENDOR FOR PRODUCTION OF "AS-BUILT" DRAWINGS.
- B. DETAILS ARE INTENDED TO SHOW DESIGN INTENT. MODIFICATIONS MAY BE REQUIRED TO SUIT JOB DIMENSIONS OR CONDITIONS, AND SUCH MODIFICATIONS SHALL BE INCLUDED AS PART OF THE WORK. CONTRACTOR SHALL NOTIFY SPRINT CONSTRUCTION MANAGER OF ANY VARIATIONS PRIOR TO PROCEEDING WITH THE WORK.
- C. DIMENSIONS SHOWN ARE TO FINISH SURFACES UNLESS NOTED OTHERWISE. SPACING BETWEEN EQUIPMENT IS THE REQUIRED CLEARANCE. SHOULD THERE BE ANY QUESTIONS REGARDING THE CONTRACT DOCUMENTS, EXISTING CONDITIONS AND/OR DESIGN INTENT, THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING A CLARIFICATION FROM THE SPRINT CONSTRUCTION MANAGER PRIOR TO PROCEEDING WITH THE WORK.

1.10 **USE OF JOB SITE:** THE CONTRACTOR SHALL CONFINE ALL CONSTRUCTION AND RELATED OPERATIONS INCLUDING STAGING AND STORAGE OF MATERIALS AND EQUIPMENT, PARKING, TEMPORARY FACILITIES, AND WASTE STORAGE TO THE LEASE PARCEL UNLESS OTHERWISE PERMITTED BY THE CONTRACT DOCUMENTS.

1.11 **UTILITIES SERVICES:** WHERE NECESSARY TO CUT EXISTING PIPES, ELECTRICAL WIRES, CONDUITS, CABLES, ETC., OF UTILITY SERVICES, OR OF FIRE PROTECTION OR COMMUNICATIONS SYSTEMS, THEY SHALL BE CUT AND CAPPED AT SUITABLE PLACES OR WHERE SHOWN. ALL SUCH ACTIONS SHALL BE COORDINATED WITH THE UTILITY COMPANY INVOLVED:

1.12 **PERMITS / FEES:** WHEN REQUIRED THAT A PERMIT OR CONNECTION FEE BE PAID TO A PUBLIC UTILITY PROVIDER FOR NEW SERVICE TO THE CONSTRUCTION PROJECT, PAYMENT OF SUCH FEE SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.

1.13 **CONTRACTOR SHALL TAKE ALL MEASURES AND PROVIDE ALL MATERIAL NECESSARY FOR PROTECTING EXISTING EQUIPMENT AND PROPERTY.**

1.14 **METHODS OF PROCEDURE (MOPS) FOR CONSTRUCTION:** CONTRACTOR SHALL PERFORM WORK AS DESCRIBED IN THE FOLLOWING INSTALLATION AND COMMISSIONING MOPS.

- A. TOP HAT
- B. HOW TO INSTALL A NEW CABINET
- C. BASE BAND UNIT IN EXISTING UNIT
- D. INSTALLATION OF BATTERIES
- E. INSTALLATION OF HYBRID CABLE
- F. INSTALLATION OF RRH'S
- G. CABLING
- H. SPRINT TS-0200 (CURRENT VERSION) – ANTENNA LINE ACCEPTANCE STANDARDS
- I. SPRINT CELL SITE ENGINEERING NOTICE – EN 2012-001, REV 1.
- J. COMMISSIONING MOPS
- K. SPRINT CELL SITE ENGINEERING NOTICE – EN-2013-002
- L. SPRINT ENGINEERING LETTER – EL-0504
- M. SPRINT ENGINEERING LETTER – EL-0568
- N. SPRINT TECHNICAL SPECIFICATION – TS-0193

1.15 **USE OF ELECTRONIC PROJECT MANAGEMENT SYSTEMS:**

- A. CONTRACTOR WILL UTILIZE ITS BEST EFFORTS TO WORK WITH SPRINT ELECTRONIC PROJECT MANAGEMENT SYSTEMS. CONTRACTOR UNDERSTANDS THAT SUFFICIENT INTERNET ACCESS, EQUIVALENT TO "BROADBAND" OR BETTER, IS REQUIRED TO TIMELY AND EFFECTIVELY UTILIZE SPRINT DATA AND DOCUMENT MANAGEMENT SYSTEMS AND AGREES TO MAINTAIN APPROPRIATE CONNECTIONS FOR CONTRACTOR'S STAFF AND OFFICES THAT ARE COMPATIBLE WITH SPRINT DATA AND DOCUMENT MANAGEMENT SYSTEMS

PART 2 – PRODUCTS (NOT USED)

PART 3 – EXECUTION

3.1 **TEMPORARY UTILITIES AND FACILITIES:** THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL TEMPORARY UTILITIES AND FACILITIES NECESSARY EXCEPT AS OTHERWISE INDICATED IN THE CONSTRUCTION DOCUMENTS. TEMPORARY UTILITIES AND FACILITIES INCLUDE POTABLE WATER, HEAT, HVAC, ELECTRICITY, SANITARY FACILITIES, WASTE DISPOSAL FACILITIES, AND TELEPHONE/COMMUNICATION SERVICES. PROVIDE TEMPORARY UTILITIES AND FACILITIES IN ACCORDANCE WITH OSHA AND THE AUTHORITY HAVING JURISDICTION. CONTRACTOR MAY UTILIZE THE COMPANY ELECTRICAL SERVICE IN THE COMPLETION OF THE WORK WHEN IT BECOMES AVAILABLE. USE OF THE LESSORS OR SITE OWNER'S UTILITIES OR FACILITIES IS EXPRESSLY FORBIDDEN EXCEPT AS OTHERWISE ALLOWED IN THE CONTRACT DOCUMENTS.

3.2 **ACCESS TO WORK:** THE CONTRACTOR SHALL PROVIDE ACCESS TO THE JOB SITE FOR AUTHORIZED COMPANY PERSONNEL AND AUTHORIZED REPRESENTATIVES OF THE ARCHITECT/ENGINEER DURING ALL PHASES OF THE WORK.

3.3 **TESTING: REQUIREMENTS FOR TESTING BY THIS CONTRACTOR SHALL BE AS INDICATED HEREWITH, ON THE CONSTRUCTION DRAWINGS, AND IN THE INDIVIDUAL SECTIONS OF THESE SPECIFICATIONS.** SHOULD COMPANY CHOOSE TO ENGAGE ANY THIRD-PARTY TO CONDUCT ADDITIONAL TESTING, THE CONTRACTOR SHALL COOPERATE WITH AND PROVIDE A WORK AREA FOR COMPANY'S TEST AGENCY.

3.4 **DIMENSIONS:** VERIFY DIMENSIONS INDICATED ON DRAWINGS WITH FIELD DIMENSIONS BEFORE FABRICATION OR ORDERING OF MATERIALS. DO NOT SCALE DRAWINGS.

3.5 **EXISTING CONDITIONS:** NOTIFY THE SPRINT CONSTRUCTION MANAGER OF EXISTING CONDITIONS DIFFERING FROM THOSE INDICATED ON THE DRAWINGS. DO NOT REMOVE OR ALTER STRUCTURAL COMPONENTS WITHOUT PRIOR WRITTEN APPROVAL FROM THE ARCHITECT AND ENGINEER.

SECTION 01 200 – COMPANY FURNISHED MATERIAL AND EQUIPMENT

PART 1 – GENERAL

1.1 **THE WORK:** THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

1.2 **RELATED DOCUMENTS:**

- A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
- B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.

PART 2 – PRODUCTS (NOT USED)

PART 3 – EXECUTION

3.1 **RECEIPT OF MATERIAL AND EQUIPMENT:**

- A. COMPANY FURNISHED MATERIAL AND EQUIPMENT IS IDENTIFIED ON THE RF DATA SHEET IN THE CONSTRUCTION DOCUMENTS.
- B. THE CONTRACTOR IS RESPONSIBLE FOR SPRINT PROVIDED MATERIAL AND EQUIPMENT AND UPON RECEIPT SHALL:
 1. ACCEPT DELIVERIES AS SHIPPED AND TAKE RECEIPT.
 2. VERIFY COMPLETENESS AND CONDITION OF ALL DELIVERIES.
 3. TAKE RESPONSIBILITY FOR EQUIPMENT AND PROVIDE INSURANCE PROTECTION AS REQUIRED IN AGREEMENT.
 4. RECORD ANY DEFECTS OR DAMAGES AND WITHIN TWENTY-FOUR HOURS AFTER RECEIPT, REPORT TO SPRINT OR ITS DESIGNATED PROJECT REPRESENTATIVE OF SUCH.
 5. PROVIDE SECURE AND NECESSARY WEATHER PROTECTED WAREHOUSING.
 6. COORDINATE SAFE AND SECURE TRANSPORTATION OF MATERIAL AND EQUIPMENT, DELIVERING AND OFF-LOADING FROM CONTRACTOR'S WAREHOUSE TO SITE.

3.2 **DELIVERABLES:**

- A. COMPLETE SHIPPING AND RECEIPT DOCUMENTATION IN ACCORDANCE WITH COMPANY PRACTICE.
- B. IF APPLICABLE, COMPLETE LOST/STOLEN/DAMAGED DOCUMENTATION REPORT AS NECESSARY IN ACCORDANCE WITH COMPANY PRACTICE, AND AS DIRECTED BY COMPANY.
- C. UPLOAD DOCUMENTATION INTO SPRINT SITE MANAGEMENT SYSTEM (SMS) AND/OR PROVIDE HARD COPY DOCUMENTATION AS REQUESTED.

SECTION 01 300 – CELL SITE CONSTRUCTION

PART 1 – GENERAL

1.1 **THE WORK:** THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

1.2 **RELATED DOCUMENTS:**

- A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
- B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.

1.3 **NOTICE TO PROCEED:**

- A. NO WORK SHALL COMMENCE PRIOR TO COMPANY'S WRITTEN NOTICE TO PROCEED AND THE ISSUANCE OF THE WORK ORDER.
- B. UPON RECEIVING NOTICE TO PROCEED, CONTRACTOR SHALL FULLY PERFORM ALL WORK NECESSARY TO PROVIDE SPRINT WITH AN OPERATIONAL WIRELESS FACILITY.

PART 2 – PRODUCTS (NOT USED)

PART 3 – EXECUTION

3.1 **FUNCTIONAL REQUIREMENTS:**

- A. THE ACTIVITIES DESCRIBED IN THIS PARAGRAPH REPRESENT MINIMUM ACTIONS AND PROCESSES REQUIRED TO SUCCESSFULLY COMPLETE THE WORK. THE ACTIVITIES DESCRIBED ARE NOT EXHAUSTIVE, AND CONTRACTOR SHALL TAKE ANY AND ALL ACTIONS AS NECESSARY TO SUCCESSFULLY COMPLETE THE CONSTRUCTION OF A FULLY FUNCTIONING WIRELESS FACILITY AT THE SITE IN ACCORDANCE WITH COMPANY PROCESSES.
- B. SUBMIT SPECIFIC DOCUMENTATION AS INDICATED HEREIN, AND OBTAIN REQUIRED APPROVALS WHILE THE WORK IS BEING PERFORMED.
- C. MANAGE AND CONDUCT ALL FIELD CONSTRUCTION SERVICE RELATED ACTIVITIES
- D. PROVIDE CONSTRUCTION ACTIVITIES TO THE EXTENT REQUIRED BY THE CONTRACT DOCUMENTS, INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
 1. PERFORM ANY REQUIRED SITE ENVIRONMENTAL MITIGATION.
 2. PREPARE GROUND SITES; PROVIDE DE-GRUBBING; AND ROUGH AND FINAL GRADING, AND COMPOUND SURFACE TREATMENTS.
 3. MANAGE AND CONDUCT ALL ACTIVITIES FOR INSTALLATION OF UTILITIES INCLUDING ELECTRICAL AND TELCO BACKHAUL.
 4. INSTALL UNDERGROUND FACILITIES INCLUDING UNDERGROUND POWER AND COMMUNICATIONS CONDUITS, AND UNDERGROUND GROUNDING SYSTEM.
 5. INSTALL ABOVE GROUND GROUNDING SYSTEMS.
 6. PROVIDE NEW HVAC INSTALLATIONS AND MODIFICATIONS.
 7. INSTALL "H-FRAMES", CABINETS AND SHELTERS AS INDICATED.
 8. INSTALL ROADS, ACCESS WAYS, CURBS AND DRAINS AS INDICATED.
 9. ACCOMPLISH REQUIRED MODIFICATION OF EXISTING FACILITIES.
 10. PROVIDE ANTENNA SUPPORT STRUCTURE FOUNDATIONS.
 11. PROVIDE SLABS AND EQUIPMENT PLATFORMS.
 12. INSTALL COMPOUND FENCING, SIGHT SHIELDING, LANDSCAPING AND ACCESS BARRIERS.
 13. PERFORM INSPECTION AND MATERIAL TESTING AS REQUIRED HEREINAFTER.
 14. CONDUCT SITE RESISTANCE TO EARTH TESTING AS REQUIRED HEREINAFTER.
 15. INSTALL FIXED GENERATOR SETS AND OTHER STANDBY POWER SOLUTIONS.
 16. INSTALL TOWERS, ANTENNA SUPPORT STRUCTURES AND PLATFORMS ON EXISTING TOWERS AS REQUIRED.
 17. INSTALL CELL SITE RADIOS, MICROWAVE, GPS, COAXIAL MAINLINE, ANTENNAS, CROSS BAND COUPLERS, TOWER TOP AMPLIFIERS, LOW NOISE AMPLIFIERS AND RELATED EQUIPMENT.
 18. PERFORM, DOCUMENT, AND CLOSE OUT ANY CONSTRUCTION CONTROL DOCUMENTS THAT MAY BE REQUIRED BY GOVERNMENT AGENCIES AND LANDLORDS.
 19. PERFORM ANTENNA AND COAX SWEEP TESTING AND MAKE ANY AND ALL NECESSARY CORRECTIONS.
 20. REMAIN ON SITE MOBILIZED THROUGHOUT HAND-OFF AND INTEGRATION TO ASSIST AS NEEDED UNTIL SITE IS DEEMED SUBSTANTIALLY COMPLETE AND PLACED "ON AIR."

3.2 **GENERAL REQUIREMENTS FOR CIVIL CONSTRUCTION:**

- A. CONTRACTOR SHALL KEEP THE SITE FREE FROM ACCUMULATING WASTE MATERIAL, DEBRIS, AND TRASH. AT THE COMPLETION OF THE WORK, CONTRACTOR SHALL REMOVE FROM THE SITE ALL REMAINING RUBBISH, IMPLEMENTS, TEMPORARY FACILITIES, AND SURPLUS MATERIALS.
- B. EQUIPMENT ROOMS SHALL AT ALL TIMES BE MAINTAINED "BROOM CLEAN" AND CLEAR OF DEBRIS.
- C. CONTRACTOR SHALL TAKE ALL REASONABLE PRECAUTIONS TO DISCOVER AND LOCATE ANY HAZARDOUS CONDITION.
 1. IN THE EVENT CONTRACTOR ENCOUNTERS ANY HAZARDOUS CONDITION WHICH HAS NOT BEEN ABATED OR OTHERWISE MITIGATED, CONTRACTOR AND ALL OTHER PERSONS SHALL IMMEDIATELY STOP WORK IN THE AFFECTED AREA AND NOTIFY COMPANY IN WRITING. THE WORK IN THE AFFECTED AREA SHALL NOT BE RESUMED EXCEPT BY WRITTEN NOTIFICATION BY COMPANY.
 2. CONTRACTOR AGREES TO USE CARE WHILE ON THE SITE AND SHALL NOT TAKE ANY ACTION THAT WILL OR MAY RESULT IN OR CAUSE THE HAZARDOUS CONDITION TO BE FURTHER RELEASED IN THE ENVIRONMENT, OR TO FURTHER EXPOSE INDIVIDUALS TO THE HAZARD.
- D. CONTRACTOR'S ACTIVITIES SHALL BE RESTRICTED TO THE PROJECT LIMITS. SHOULD AREAS OUTSIDE THE PROJECT LIMITS BE AFFECTED BY CONTRACTOR'S ACTIVITIES, CONTRACTOR SHALL IMMEDIATELY RETURN THEM TO ORIGINAL CONDITION
- E. CONDUCT TESTING AS REQUIRED HEREIN.

3.3 **DELIVERABLES:**

- A. CONTRACTOR SHALL REVIEW, APPROVE, AND SUBMIT TO SPRINT SHOP DRAWINGS, PRODUCT DATA, SAMPLES, AND SIMILAR SUBMITTALS AS REQUIRED HEREINAFTER
- B. PROVIDE DOCUMENTATION INCLUDING, BUT NOT LIMITED TO, THE FOLLOWING. DOCUMENTATION SHALL BE FORWARDED IN ORIGINAL FORMAT AND/OR UPLOADED INTO SMS.
 1. ALL CORRESPONDENCE AND PRELIMINARY CONSTRUCTION REPORTS.
 2. PROJECT PROGRESS REPORTS.
 3. CIVIL CONSTRUCTION START DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
 4. ELECTRICAL SERVICE COMPLETION DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
 5. LINES AND ANTENNA INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
 6. POWER INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
 7. TELCO READY DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
 8. PPC (OR SHELTER) INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
 9. TOWER CONSTRUCTION START DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
 10. TOWER CONSTRUCTION COMPLETE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
 11. BTS AND RADIO EQUIPMENT DELIVERED AT SITE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
 12. NETWORK OPERATIONS HANDOFF CHECKLIST (HOC WALK) COMPLETE (UPLOAD FORM IN SMS)
 13. CIVIL CONSTRUCTION COMPLETE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
 14. SITE CONSTRUCTION PROGRESS PHOTOS UNLOADED INTO SMS.

CONTINUE SHEET SP-2




1 INTERNATIONAL BLVD, SUITE 800
MAHWAH, NJ 07495
TEL: (800) 357-7641



SBA COMMUNICATIONS CORP.
134 FLANDERS ROAD, SUITE 125
WESTBOROUGH, MA 01581
TEL: (508) 251-0720
FAX: (508) 251-1755



45 BEECHWOOD DRIVE
N. ANDOVER, MA 01845
TEL: (978) 557-5553
FAX: (978) 336-5586



CHECKED BY: BB

APPROVED BY: DJC

SUBMITTALS			
REV.	DATE	DESCRIPTION	BY
2	09/28/17	CONSTRUCTION FINAL	DJM
1	05/08/14	ISSUED FOR CONSTRUCTION	SF
0	05/02/14	ISSUED FOR CONSTRUCTION	SF

SITE NUMBER:
CT23XC501-A

SITE NAME:
SBA

SITE ADDRESS:
300 PLAIN HILL ROAD
NORWICH, CT 06360

SHEET TITLE
OUTLINE
SPECIFICATIONS

SHEET NUMBER

SP-1

SECTION 01 400 – SUBMITTALS, TESTS, AND INSPECTIONS

PART 1 – GENERAL

1.1 **THE WORK:** THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

1.2 **RELATED DOCUMENTS:**

- A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
- B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.

1.3 **SUBMITTALS:**

- A. THE WORK IN ALL ASPECTS SHALL COMPLY WITH THE CONSTRUCTION DRAWINGS AND THESE SPECIFICATIONS.
- B. SUBMIT THE FOLLOWING TO COMPANY REPRESENTATIVE FOR APPROVAL.
 - 1. CONCRETE MIX-DESIGNS FOR TOWER FOUNDATIONS, ANCHORS PIERS, AND CONCRETE PAVING.
 - 2. CONCRETE BREAK TESTS AS SPECIFIED HEREIN.
 - 3. SPECIAL FINISHES FOR INTERIOR SPACES, IF ANY.
 - 4. ALL EQUIPMENT AND MATERIALS SO IDENTIFIED ON THE CONSTRUCTION DRAWINGS.
 - 5. CHEMICAL GROUNDING DESIGN.
- C. ALTERNATES: AT THE COMPANY'S REQUEST, ANY ALTERNATIVES TO THE MATERIALS OR METHODS SPECIFIED SHALL BE SUBMITTED TO SPRINT'S CONSTRUCTION MANAGER FOR APPROVAL PRIOR TO BEING SHIPPED TO SITE. SPRINT WILL REVIEW AND APPROVE ONLY THOSE REQUESTS MADE IN WRITING. NO VERBAL APPROVALS WILL BE CONSIDERED. SUBMITTAL FOR APPROVAL SHALL INCLUDE A STATEMENT OF COST REDUCTION PROPOSED FOR USE OF ALTERNATE PRODUCT.

1.4 **TESTS AND INSPECTIONS:**

- A. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CONSTRUCTION TESTS, INSPECTIONS AND PROJECT DOCUMENTATION.
- B. CONTRACTOR SHALL ACCOMPLISH TESTING INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
 - 1. COAX SWEEPS AND FIBER TESTS PER SPRINT TS-0200 (CURRENT VERSION) ANTENNA LINE ACCEPTANCE STANDARDS.
 - 2. AGL, AZIMUTH AND DOWNTILT USING ELECTRONIC COMMERCIAL MADE-FOR-THE-PURPOSE ANTENNA ALIGNMENT TOOL.
 - 3. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN SITE INSPECTION ACTIVITIES AND/OR AS A RESULT OF TESTING.
- C. REQUIRED CLOSEOUT DOCUMENTATION INCLUDES, BUT IS NOT LIMITED TO THE FOLLOWING:
 - 1. AZIMUTH, DOWNTILT, AGL – UPLOAD REPORT FROM ANTENNA ALIGNMENT TOOL TO SITERRA TASK 465. INSTALLED AZIMUTH, DOWNTILT, AND AGL MUST CONFORM TO THE RF DATA SHEETS. SWEEP AND FIBER TESTS
 - 2. SCANABLE BARCODE PHOTOGRAPHS OF TOWER TOP AND INACCESSIBLE SERIALIZED EQUIPMENT
 - 3. ALL AVAILABLE JURISDICTIONAL INFORMATION
 - 4. PDF SCAN OF REDLINES PRODUCED IN FIELD
 - 5. ELECTRONIC AS-BUILT DRAWINGS IN AUTOCAD AND PDF FORMATS. ANY FIELD CHANGE MUST BE REFLECTED BY MODIFYING THE PLANS, ELEVATIONS, AND DETAILS IN THE DRAWING SETS. GENERAL NOTES INDICATING MODIFICATIONS WILL NOT BE ACCEPTED. CHANGES SHALL BE HIGHLIGHTED AS "CLOUDS" IDENTIFIED AS THE "AS-BUILT" CONDITION.
 - 6. LIEN WAIVERS
 - 7. FINAL PAYMENT APPLICATION
 - 8. REQUIRED FINAL CONSTRUCTION PHOTOS
 - 9. CONSTRUCTION AND COMMISSIONING CHECKLIST COMPLETE WITH NO DEFICIENT ITEMS
 - 10. ALL POST NTP TASKS INCLUDING DOCUMENT UPLOADS COMPLETED IN SITERRA (SPRINTS DOCUMENT REPOSITORY OF RECORD).

1.5 **COMMISSIONING:** PERFORM ALL COMMISSIONING AS REQUIRED BY APPLICABLE MOPS

1.6 **INTEGRATION:** PERFORM ALL INTEGRATION ACTIVITIES AS REQUIRED BY APPLICABLE MOPS

PART 2 – PRODUCTS (NOT USED)

PART 3 – EXECUTION

3.1 **REQUIREMENTS FOR TESTING:**

- A. THIRD PARTY TESTING AGENCY: WHEN THE USE OF A THIRD PARTY INDEPENDENT TESTING AGENCY IS REQUIRED, THE AGENCY THAT IS SELECTED MUST PERFORM SUCH WORK ON A REGULAR BASIS IN THE STATE WHERE THE PROJECT IS LOCATED AND HAVE A THOROUGH UNDERSTANDING OF LOCAL AVAILABLE MATERIALS, INCLUDING THE SOIL, ROCK, AND GROUNDWATER CONDITIONS.
 - 1. THE THIRD PARTY TESTING AGENCY IS TO BE FAMILIAR WITH THE APPLICABLE REQUIREMENTS FOR THE TESTS TO BE DONE, EQUIPMENT TO BE USED, AND ASSOCIATED HEALTH AND SAFETY ISSUES.
 - 2. EXPERIENCE IN SOILS, CONCRETE, MASONRY, AGGREGATE, AND ASPHALT TESTING USING ASTM, AASJTO, AND OTHER METHODS IS NEEDED.
 - 3. EXPERIENCE IN SOILS, CONCRETE, MASONRY, AGGREGATE, AND ASPHALT TESTING USING ASTM, AASJTO, AND OTHER METHODS IS NEEDED.

3.2 **REQUIRED TESTS:**

- A. CONTRACTOR SHALL ACCOMPLISH TESTING INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
 - 1. CONCRETE CYLINDER BREAK TESTS FOR THE TOWER AND ANCHOR FOUNDATIONS AS SPECIFIED IN SECTION: PORTLAND CEMENT CONCRETE PAVING.
 - 2. ASPHALT ROADWAY COMPACTED THICKNESS, SURFACE SMOOTHNESS, AND COMPACTED DENSITY TESTING AS SPECIFIED IN SECTION: HOT MIX ASPHALT PAVING.
 - 3. FIELD QUALITY CONTROL TESTING AS SPECIFIED IN SECTION: PORTLAND CEMENT CONCRETE PAVING.
 - 4. TESTING REQUIRED UNDER SECTION: AGGREGATE BASE FOR ACCESS ROADS, PADS AND ANCHOR LOCATIONS
 - 5. STRUCTURAL BACKFILL COMPACTION TESTS FOR THE TOWER FOUNDATION.
 - 6. SITE RESISTANCE TO EARTH TESTING PER EXHIBIT: CELL SITE GROUNDING SYSTEM DESIGN.
 - 7. ANTENNA AND COAX SWEEP TESTS PER EXHIBIT: ANTENNA TRANSMISSION LINE ACCEPTANCE STANDARDS.
 - 8. GROUNDING AT ANTENNA MASTS FOR GPS AND ANTENNAS
 - 9. ALL OTHER TESTS REQUIRED BY COMPANY OR JURISDICTION.

3.3 **REQUIRED INSPECTIONS:**

- A. SCHEDULE INSPECTIONS WITH COMPANY REPRESENTATIVE.
- B. CONDUCT INSPECTIONS INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
 - 1. GROUNDING SYSTEM INSTALLATION PRIOR TO EARTH CONCEALMENT DOCUMENTED WITH DIGITAL PHOTOGRAPHS BY CONTRACTOR, APPROVED BY A&E OR SPRINT REPRESENTATIVE.
 - 2. FORMING FOR CONCRETE AND REBAR PLACEMENT PRIOR TO POUR DOCUMENTED WITH DIGITAL PHOTOGRAPHS BY CONTRACTOR, APPROVED BY A&E OR SPRINT REPRESENTATIVE.
 - 3. COMPACTION OF BACKFILL MATERIALS; AGGREGATE BASE FOR ROADS, PADS, AND ANCHORS; ASPHALT PAVING; AND SHAFT BACKFILL FOR CONCRETE AND WOOD POLES, BY INDEPENDENT THIRD PARTY AGENCY.
 - 4. PRE- AND POST-CONSTRUCTION ROOFTOP AND STRUCTURAL INSPECTIONS ON EXISTING FACILITIES.
 - 5. TOWER ERECTION SECTION STACKING AND PLATFORM ATTACHMENT DOCUMENTED BY DIGITAL PHOTOGRAPHS BY THIRD PARTY AGENCY.
 - 6. ANTENNA AZIMUTH , DOWN TILT AND PER SUNLIGHT TOOL SUNSIGHT INSTRUMENTS – ANTENNALIGN ALIGNMENT TOOL (AAT)
 - 7. VERIFICATION DOCUMENTED WITH THE ANTENNA CHECKLIST REPORT, BY A&E, SITE DEVELOPMENT REP, OR RF REP.
 - 8. FINAL INSPECTION CHECKLIST AND HANDOFF WALK (HOC). SIGNED FORM SHOWING ACCEPTANCE BY FIELD OPS IS TO BE UPLOADED INTO SMS.
 - 9. COAX SWEEP AND FIBER TESTING DOCUMENTS SUBMITTED VIA SMS FOR RF APPROVAL.
 - 10. SCAN-ABLE BARCODE PHOTOGRAPHS OF TOWER TOP AND INACCESSIBLE SERIALIZED EQUIPMENT
 - 11. ALL AVAILABLE JURISDICTIONAL INFORMATION
 - 12. PDF SCAN OF REDLINES PRODUCED IN FIELD
- E. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN SITE INSPECTION ACTIVITIES AND/OR AS A RESULT OF TESTING.
- F. CONSTRUCTION INSPECTIONS AND CORRECTIVE MEASURES SHALL BE DOCUMENTED BY THE CONTRACTOR WITH WRITTEN REPORTS AND PHOTOGRAPHS. PHOTOGRAPHS MUST BE DIGITAL AND OF SUFFICIENT QUALITY TO CLEARLY SHOW THE SITE CONSTRUCTION. PHOTOGRAPHS MUST CLEARLY IDENTIFY THE PHOTOGRAPHED ITEM AND BE LABELED WITH THE SITE CASCADE NUMBER, SITE NAME, DESCRIPTION, AND DATE.

3.4 **DELIVERABLES:** TEST AND INSPECTION REPORTS AND CLOSEOUT DOCUMENTATION SHALL BE UPLOADED TO THE SMS AND/OR FORWARDED TO SPRINT FOR INCLUSION INTO THE PERMANENT SITE FILES.

- A. THE FOLLOWING TEST AND INSPECTION REPORTS SHALL BE PROVIDED AS APPLICABLE.
 - 1. CONCRETE MIX AND CYLINDER BREAK REPORTS.
 - 2. STRUCTURAL BACKFILL COMPACTION REPORTS.
 - 3. SITE RESISTANCE TO EARTH TEST.
 - 4. ANTENNA AZIMUTH AND DOWN TILT VERIFICATION
 - 5. TOWER ERECTION INSPECTIONS AND MEASUREMENTS DOCUMENTING TOWER INSTALLED PER SUPPLIER'S REQUIREMENTS AND THE APPLICABLE SECTIONS HEREIN.
 - 6. COAX CABLE SWEEP TESTS PER COMPANY'S "ANTENNA LINE ACCEPTANCE STANDARDS".
- B. REQUIRED CLOSEOUT DOCUMENTATION INCLUDES THE FOLLOWING:
 - 1. TEST WELLS AND TRENCHES: PHOTOGRAPHS OF ALL TEST WELLS; PHOTOGRAPHS SHOWING ALL OPEN EXCAVATIONS AND TRENCHING PRIOR TO BACKFILLING SHOWING A TAPE MEASURE VISIBLE IN THE EXCAVATIONS INDICATING DEPTH.
 - 2. CONDUITS, CONDUCTORS AND GROUNDING: PHOTOGRAPHS SHOWING TYPICAL INSTALLATION OF CONDUCTORS AND CONNECTORS; PHOTOGRAPHS SHOWING TYPICAL BEND RADIUS OF INSTALLED GROUND WIRES AND GROUND ROD SPACING;
 - 3. CONCRETE FORMS AND REINFORCING: CONCRETE FORMING AT TOWER AND EQUIPMENT/SHELTER PAD/FOUNDATIONS – PHOTOGRAPHS SHOWING ALL REINFORCING STEEL, UTILITY AND CONDUIT STUB OUTS; PHOTOGRAPHS SHOWING CONCRETE POUR OF SHELTER SLAB/FOUNDATION, TOWER FOUNDATION AND GUY ANCHORS WITH VIBRATOR IN USE; PHOTOGRAPHS SHOWING EACH ANCHOR ON GUYED TOWERS, BEFORE CONCRETE POUR.
 - 4. TOWER, ANTENNAS AND MAINLINE: INSPECTION AND PHOTOGRAPHS OF SECTION STACKING; INSPECTION AND PHOTOGRAPHS OF PLATFORM COMPONENT ATTACHMENT POINTS; PHOTOGRAPHS OF TOWER TOP GROUNDING; PHOTOS OF TOWER COAX LINE COLOR CODING AT THE TOP AND AT GROUND LEVEL; INSPECTION AND PHOTOGRAPHS OF OPERATIONAL OF TOWER LIGHTING, AND PLACEMENT OF FAA REGISTRATION SIGN; PHOTOGRAPHS SHOWING ADDITIONAL GROUNDING POINTS FOR TOWERS GREATER THAN 200 FEET.; PHOTOS OF ANTENNA GROUND BAR, EQUIPMENT GROUND BAR, AND MASTER GROUND BAR; PHOTOS OF GPS ANTENNA(S); PHOTOS OF EACH SECTOR OF ANTENNAS; ONE PHOTOGRAPH LOOKING AT THE SECTOR AND ONE FROM BEHIND SHOWING THE PROJECTED COVERAGE AREA; PHOTOS OF COAX WEATHERPROOFING – TOP AND BOTTOM; PHOTOS OF COAX GROUNDING--TOP AND BOTTOM; PHOTOS OF ANTENNA AND MAST GROUNDING; PHOTOS OF COAX CABLE ENTRY INTO SHELTER; PHOTOS OF PLATFORM MECHANICAL CONNECTIONS TO TOWER/MONOPOLE.
 - 5. ROOF TOPS: PRE-CONSTRUCTION AND POST-CONSTRUCTION VISUAL INSPECTION AND PHOTOGRAPHS OF THE ROOF AND INTERIOR TO DETERMINE AND DOCUMENT CONDITIONS; ROOF TOP CONSTRUCTION INSPECTIONS AS REQUIRED BY THE JURISDICTION; PHOTOGRAPHS OF CABLE TRAY AND/OR ICE BRIDGE; PHOTOGRAPHS OF DOGHOUSE/CABLE EXIT FROM ROOF;
 - 6. SITE LAYOUT – PHOTOGRAPHS OF THE OVERALL COMPOUND, INCLUDING EQUIPMENT PLATFORM FROM ALL FOUR CORNERS.
 - 7. FINISHED UTILITIES: CLOSE-UP PHOTOGRAPHS OF THE PPC BREAKER PANEL; CLOSE-UP PHOTOGRAPH OF THE INSIDE OF THE TELCO PANEL AND NIU; CLOSE-UP PHOTOGRAPH OF THE POWER METER AND DISCONNECT; PHOTOS OF POWER AND TELCO ENTRANCE TO COMPANY ENCLOSURE; PHOTOGRAPHS AT METER BOX AND/OR FACILITY DISTRIBUTION PANEL.
 - 8. REQUIRED MATERIALS CERTIFICATIONS: CONCRETE MIX DESIGNS; MILL CERTIFICATION FOR ALL REINFORCING AND STRUCTURAL STEEL; AND ASPHALT PAVING MIX DESIGN.
 - 9. ANY AND ALL SUBMITTALS BY THE JURISDICTION OR COMPANY.

SECTION 01 500 – PROJECT REPORTING

PART 1 – GENERAL

1.1 **THE WORK:** THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

1.2 **RELATED DOCUMENTS:**

- A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
- B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.

PART 2 – PRODUCTS (NOT USED)

PART 3 – EXECUTION

3.1 **WEEKLY REPORTS:**

- A. CONTRACTOR SHALL PROVIDE SPRINT WITH WEEKLY REPORTS SHOWING PROJECT STATUS. THIS STATUS REPORT FORMAT WILL BE PROVIDED TO THE CONTRACTOR BY SPRINT. THE REPORT WILL CONTAIN SITE ID NUMBER, THE MILESTONES FOR EACH SITE, INCLUDING THE BASELINE DATE, ESTIMATED COMPLETION DATE AND ACTUAL COMPLETION DATE.

B. REPORT INFORMATION WILL BE TRANSMITTED TO SPRINT VIA ELECTRONIC MEANS AS REQUIRED. THIS INFORMATION WILL PROVIDE A BASIS FOR PROGRESS MONITORING AND PAYMENT.

3.2 **PROJECT CONFERENCE CALLS:**

- A. SPRINT MAY HOLD WEEKLY PROJECT CONFERENCE CALLS. CONTRACTOR WILL BE REQUIRED TO COMMUNICATE SITE STATUS, MILESTONE COMPLETIONS AND UPCOMING MILESTONE PROJECTIONS, AND ANSWER ANY OTHER SITE STATUS QUESTIONS AS NECESSARY.

3.3 **PROJECT TRACKING IN SMS:**

- A. CONTRACTOR SHALL PROVIDE SCHEDULE UPDATES AND PROJECTIONS IN THE SMS SYSTEM ON A WEEKLY BASIS.

3.4 **ADDITIONAL REPORTING:**

- A. ADDITIONAL OR ALTERNATE REPORTING REQUIREMENTS MAY BE ADDED TO THE REPORT AS DETERMINED TO BE REASONABLY NECESSARY BY COMPANY.

3.5 **PROJECT PHOTOGRAPHS:**

- A. FILE DIGITAL PHOTOGRAPHS OF COMPLETED SITE IN JPEG FORMAT IN THE SMS PHOTO LIBRARY FOR THE RESPECTIVE SITE. PHOTOGRAPHS SHALL BE CLEARLY LABELED WITH SITE NUMBER, NAME AND DESCRIPTION, AND SHALL INCLUDE AT A MINIMUM THE FOLLOWING AS APPLICABLE:
 - 1. SHELTER AND TOWER OVERVIEW.
 - 2. TOWER FOUNDATION(S) – FORMS AND STEEL BEFORE POUR (EACH ANCHOR ON GUYED TOWERS).
 - 3. TOWER FOUNDATION(S) POUR WITH VIBRATOR IN USE (EACH ANCHOR ON GUYED TOWERS).
 - 4. TOWER STEEL AS BEING INSTALLED INTO HOLE (SHOW ANCHOR STEEL ON GUYED TOWERS).
 - 5. PHOTOS OF TOWER SECTION STACKING.
 - 6. CONCRETE TESTING / SAMPLES.
 - 7. PLACING OF ANCHOR BOLTS IN TOWER FOUNDATION.
 - 8. BUILDING/WATER TANK FROM ROAD FOR TENANT IMPROVEMENTS OR COMMENTS.
 - 9. SHELTER FOUNDATION--FORMS AND STEEL BEFORE POURING.
 - 10. SHELTER FOUNDATION POUR WITH VIBRATOR IN USE.
 - 11. COAX CABLE ENTRY INTO SHELTER.
 - 12. PLATFORM MECHANICAL CONNECTIONS TO TOWER/MONOPOLE.
 - 13. ROOFTOP PRE AND POST CONSTRUCTION PHOTOS TO INCLUDE PENETRATIONS AND INTERIOR CEILING.
 - 14. PHOTOS OF TOWER TOP COAX LINE COLOR CODING AND COLOR CODING AT GROUND LEVEL.
 - 15. PHOTOS OF ALL APPROPRIATE COMPANY OR REGULATORY SIGNAGE.
 - 16. PHOTOS OF EQUIPMENT BOLT DOWN INSIDE SHELTER.
 - 17. POWER AND TELCO ENTRANCE TO COMPANY ENCLOSURE AND POWER AND TELCO SUPPLY LOCATIONS INCLUDING METER/DISCONNECT.
 - 18. ELECTRICAL TRENCH(S) WITH ELECTRICAL / CONDUIT BEFORE BACKFILL.
 - 19. ELECTRICAL TRENCH(S) WITH FOIL-BACKED TAPE BEFORE FURTHER BACKFILL.
 - 20. TELCO TRENCH WITH TELEPHONE / CONDUIT BEFORE BACKFILL.
 - 21. TELCO TRENCH WITH FOIL-BACKED TAPE BEFORE FURTHER BACKFILL.
 - 22. SHELTER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADI).
 - 23. TOWER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADI).
 - 24. FENCE GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADI).
 - 25. ALL BTS GROUND CONNECTIONS.
 - 26. ALL GROUND TEST WELLS.
 - 27. ANTENNA GROUND BAR AND EQUIPMENT GROUND BAR.
 - 28. ADDITIONAL GROUNDING POINTS ON TOWERS ABOVE 200'.
 - 29. HVAC UNITS INCLUDING CONDENSERS ON SPLIT SYSTEMS.
 - 30. GPS ANTENNAS.
 - 31. CABLE TRAY AND/OR WAVEGUIDE BRIDGE.
 - 32. DOGHOUSE/CABLE EXIT FROM ROOF.
 - 33. EACH SECTOR OF ANTENNAS; ONE PHOTOGRAPH LOOKING AT THE SECTOR AND ONE FROM BEHIND SHOWING THE PROJECTED COVERAGE AREA.
 - 34. MASTER BUS BAR.
 - 35. TELCO BOARD AND NIU.
 - 36. ELECTRICAL DISTRIBUTION WALL.
 - 37. CABLE ENTRY WITH SURGE SUPPRESSION.
 - 38. ENTRANCE TO EQUIPMENT ROOM.
 - 39. COAX WEATHERPROOFING--TOP AND BOTTOM OF TOWER.
 - 40. COAX GROUNDING --TOP AND BOTTOM OF TOWER.
 - 41. ANTENNA AND MAST GROUNDING.
 - 42. LANDSCAPING – WHERE APPLICABLE.

3.6 **FINAL PROJECT ACCEPTANCE:** COMPLETE ALL REQUIRED REPORTING TASKS PER CONTRACT, CONTRACT DOCUMENTS OR THE SPRINT INTEGRATED CONSTRUCTION STANDARDS FOR WIRELESS SITES AND UPLOAD INTO SITERRA.

SECTION 07 500 – ROOF CUTTING, PATCHING AND REPAIR

SUMMARY:
THIS SECTION SPECIFIES CUTTING AND PATCHING EXISTING ROOFING SYSTEMS WHERE CONDUIT OR CABLES EXIT THE BUILDING ONTO THE ROOF OR BUILDING-MOUNTED ANTENNAS, AND AS REQUIRED FOR WATERTIGHT PERFORMANCE. ROOFTOP ENTRY OPENINGS IN MEMBRANE ROOFTOPS SHALL BE CONSTRUCTED TO COMPLY WITH LANDLORD, ANY EXISTING WARRANTY, AND LOCAL JURISDICTIONAL STANDARDS.

1.4 **SUBMITTALS:**

- A. **PRE-CONSTRUCTION ROOF PHOTOS:** COMPLETE A ROOF INSPECTION PRIOR TO THE INSTALLATION OF SPRINT EQUIPMENT ON ANY ROOFTOP BUILD. AT A MINIMUM INSPECT AND PHOTOGRAPH (MINIMUM 3 EA.) ALL AREAS IMPACTED BY THE ADDITION OF THE SPRINT EQUIPMENT.
- B. PROVIDE SIMILAR PHOTOGRAPHS SHOWING ROOF CONDITIONS AFTER CONSTRUCTION (MINIMUM 3 EA.)
- C. ROOF INSPECTION PHOTOGRAPHS SHOULD BE UPLOADED WITH CLOSEOUT PHOTOGRAPHS.

SECTION 09 900 – PAINTING QUALITY ASSURANCE:

- A. COMPLY WITH GOVERNING CODES AND REGULATIONS. PROVIDE PRODUCTS OF ACCEPTABLE MANUFACTURERS WHICH HAVE BEEN IN SATISFACTORY USE IN SIMILAR SERVICE FOR THREE YEARS. USE EXPERIENCED INSTALLERS. DELIVER, HANDLE, AND STORE MATERIALS IN ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS.
- B. COMPLY WITH ALL ENVIRONMENTAL REGULATIONS FOR VOLATILE ORGANIC COMPOUNDS.




1 INTERNATIONAL BLVD, SUITE 800
MAHWAH, NJ 07495
TEL: (800) 357-7641



SBA COMMUNICATIONS CORP.
134 FLANDERS ROAD, SUITE 125
WESTBOROUGH, MA 01581
TEL: (508) 251-0720
FAX: (508) 251-1755



45 BEECHWOOD DRIVE
N. ANDOVER, MA 01845
TEL: (978) 557-5553
FAX: (978) 336-5586



CHECKED BY: BB

APPROVED BY: DJC

SUBMITTALS

REV.	DATE	DESCRIPTION	BY
2	09/28/17	CONSTRUCTION FINAL	DJM
1	05/08/14	ISSUED FOR CONSTRUCTION	SF
0	05/02/14	ISSUED FOR CONSTRUCTION	SF

SITE NUMBER:
CT23XC501-A

SITE NAME:
SBA

SITE ADDRESS:
300 PLAIN HILL ROAD
NORWICH, CT 06360

SHEET TITLE

OUTLINE
SPECIFICATIONS

SHEET NUMBER

SP-2

CONTINUED FROM SP-2:

MATERIALS:

- A. MANUFACTURERS: BENJAMIN MOORE, ICI DEVOE COATINGS, PPG, SHERWIN WILLIAMS OR APPROVED EQUAL. PROVIDE PREMIUM GRADE, PROFESSIONAL-QUALITY PRODUCTS FOR COATING SYSTEMS.

PAINT SCHEDULE:

- A. EXTERIOR ANTENNAE AND ANTENNA MOUNTING HARDWARE: ONE COAT OF PRIMER AND TWO FINISH COATS. PAINT FOR ANTENNAE SHALL BE NON-METALLIC BASED AND CONTAIN NO METALLIC PARTICLES. PROVIDE COLORS AND PATTERNS AS REQUIRED TO MASK APPEARANCE OF ANTENNAE ON ADJACENT BUILDING SURFACES AND AS ACCEPTABLE TO THE OWNER. REFER TO ANTENNA MANUFACTURER'S INSTRUCTIONS WHENEVER POSSIBLE.

- B. ROOF TOP CONSTRUCTION: TOUCH UP - PREPARE SURFACES TO BE REPAIRED. FOLLOW INDUSTRY STANDARDS AND REQUIREMENTS OF OWNER TO MATCH EXISTING COATING AND FINISH.

PAINTING APPLICATION:

1. INSPECT SURFACES, REPORT UNSATISFACTORY CONDITIONS IN WRITING; BEGINNING WORK MEANS ACCEPTANCE OF SUBSTRATE.
2. COMPLY WITH MANUFACTURER'S INSTRUCTIONS AND RECOMMENDATIONS FOR PREPARATION, PRIMING AND COATING WORK. COORDINATE WITH WORK OF OTHER SECTIONS.
3. MATCH APPROVED MOCK-UPS FOR COLOR, TEXTURE, AND PATTERN. RE-COAT OR REMOVE AND REPLACE WORK WHICH DOES NOT MATCH OR SHOWS LOSS OF ADHESION.
4. CLEAN UP, TOUCH UP AND PROTECT WORK.

TOUCHUP PAINTING:

1. GALVANIZING DAMAGE AND ALL BOLTS AND NUTS SHALL BE TOUCHED UP AFTER TOWER ERECTION WITH "GALVANOX," "DRY GALV," OR "ZINC-IT."
2. FIELD TOUCHUP PAINT SHALL BE DONE IN ACCORDANCE WITH THE MANUFACTURER'S WRITTEN INSTRUCTIONS.
3. ALL METAL COMPONENTS SHALL BE HANDLED WITH CARE TO PREVENT DAMAGE TO THE COMPONENTS, THEIR PRESERVATIVE TREATMENT, OR THEIR PROTECTIVE COATINGS.

SECTION 11 700 - ANTENNA ASSEMBLY, REMOTE RADIO HEADS AND CABLE INSTALLATION

SUMMARY:

THIS SECTION SPECIFIES INSTALLATION OF ANTENNAS, RRH'S, AND CABLE EQUIPMENT, INSTALLATION, AND TESTING OF COAXIAL FIBER CABLE.

ANTENNAS AND RRH'S:

THE NUMBER AND TYPE OF ANTENNAS AND RRH'S TO BE INSTALLED IS DETAILED ON THE CONSTRUCTION DRAWINGS.

HYBRID CABLE:

HYBRID CABLE WILL BE DC/FIBER AND FURNISHED FOR INSTALLATION AT EACH SITE. CABLE SHALL BE INSTALLED PER THE CONSTRUCTION DRAWINGS AND THE APPLICABLE MANUFACTURER'S REQUIREMENTS.

JUMPERS AND CONNECTORS:

FURNISH AND INSTALL 1/2" COAX JUMPER CABLES BETWEEN THE RRH'S AND ANTENNAS. JUMPERS SHALL BE TYPE LDF 4, FLC 12-50, CR 540, OR FXL 540. SUPER-FLEX CABLES ARE NOT ACCEPTABLE. JUMPERS BETWEEN THE RRH'S AND ANTENNAS OR TOWER TOP AMPLIFIERS SHALL CONSIST OF 1/2 INCH FOAM DIELECTRIC, OUTDOOR RATED COAXIAL CABLE. DO NOT USE SUPERFLEX OUTDOORS. JUMPERS SHALL BE FACTORY FABRICATED IN APPROPRIATE LENGTHS WITH A MAXIMUM OF 4 FEET EXCESS PER JUMPER AND HAVE CONNECTORS AT EACH END, MANUFACTURED BY SUPPLIER. IF JUMPERS ARE FIELD FABRICATED, FOLLOW MANUFACTURER'S REQUIREMENTS FOR INSTALLATION OF CONNECTORS

REMOTE ELECTRICAL TILT (RET) CABLES:

MISCELLANEOUS:

INSTALL SPLITTERS, COMBINERS, FILTERS PER RF DATA SHEET, FURNISHED BY SPRINT.

ANTENNA INSTALLATION:

THE CONTRACTOR SHALL ASSEMBLE ALL ANTENNAS ONSITE IN ACCORDANCE WITH THE INSTRUCTIONS SUPPLIED BY THE MANUFACTURER. ANTENNA HEIGHT, AZIMUTH, AND FEED ORIENTATION INFORMATION SHALL BE A DESIGNATED ON THE CONSTRUCTION DRAWINGS.

- A. THE CONTRACTOR SHALL POSITION THE ANTENNA ON TOWER PIPE MOUNTS SO THAT THE BOTTOM STRUT IS LEVEL. THE PIPE MOUNTS SHALL BE PLUMB TO WITHIN 1 DEGREE.
- B. ANTENNA MOUNTING REQUIREMENTS: PROVIDE ANTENNA MOUNTING HARDWARE AS INDICATED ON THE DRAWINGS.

HYBRID CABLES INSTALLATION:

- A. THE CONTRACTOR SHALL ROUTE, TEST, AND INSTALL ALL CABLES AS INDICATED ON THE CONSTRUCTION DRAWINGS AND IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS.
- B. THE INSTALLED RADIUS OF THE CABLES SHALL NOT BE LESS THAN THE MANUFACTURER'S SPECIFICATIONS FOR BENDING RADII.
- C. EXTREME CARE SHALL BE TAKEN TO AVOID DAMAGE TO THE CABLES DURING HANDLING AND INSTALLATION.
 1. FASTENING MAIN HYBRID CABLES: ALL CABLES SHALL BE PERMANENTLY FASTENED TO THE COAX LADDER AT 4'-0" OC USING NON-MAGNETIC STAINLESS STEEL CLIPS.
 2. FASTENING INDIVIDUAL FIBER AND DC CABLES ABOVE BREAKOUT ENCLOSURE (MEDUSA), WITHIN THE MMBTS CABINET AND ANY INTERMEDIATE DISTRIBUTION BOXES:
 - a. FIBER: SUPPORT FIBER BUNDLES USING 1/2" VELCRO STRAPS OF THE REQUIRED LENGTH @ 18" OC. STRAPS SHALL BE UV, OIL AND WATER RESISTANT AND SUITABLE FOR INDUSTRIAL INSTALLATIONS AS MANUFACTURED BY TEXTOL OR APPROVED EQUAL.
 - b. DC: SUPPORT DC BUNDLES WITH ZIP TIES OF THE ADEQUATE LENGTH. ZIP TIES TO BE UV STABILIZED, BLACK NYLON, WITH TENSILE STRENGTH AT 12,000 PSI AS MANUFACTURED BY NELCO PRODUCTS OR EQUAL.
 3. FASTENING JUMPERS: SECURE JUMPERS TO THE SIDE ARMS OR HEAD FRAMES USING STAINLESS STEEL TIE WRAPS OR STAINLESS STEEL BUTTERFLY CLIPS.
 4. CABLE INSTALLATION:
 - a. INSPECT CABLE PRIOR TO USE FOR SHIPPING DAMAGE, NOTIFY THE CONSTRUCTION MANAGER.
 - b. CABLE ROUTING: CABLE INSTALLATION SHALL BE PLANNED TO ENSURE THAT THE LINES WILL BE PROPERLY ROUTED IN THE CABLE ENVELOP AS INDICATED ON THE DRAWINGS. AVOID TWISTING AND CROSSOVERS.
 - c. HOIST CABLE USING PROPER HOISTING GRIPS. DO NOT EXCEED MANUFACTURER'S RECOMMENDED MAXIMUM BEND RADIUS.

5. GROUNDING OF TRANSMISSION LINES: ALL TRANSMISSION LINES SHALL BE GROUNDED AS INDICATED ON DRAWINGS.
6. HYBRID CABLE COLOR CODING: ALL COLOR CODING SHALL BE AS REQUIRED IN TS 0200 REV 4.
7. HYBRID CABLE LABELING: INDIVIDUAL HYBRID AND DC BUNDLES SHALL BE LABELED ALPHA-NUMERICALLY ACCORDING TO SPRINT CELL SITE ENGINEERING NOTICE - EN 2012-001, REV 1

WEATHERPROOFING EXTERIOR CONNECTORS AND HYBRID CABLE GROUND KITS:

- A. ALL FIBER & COAX CONNECTORS AND GROUND KITS SHALL BE WEATHERPROOFED.
- B. WEATHERPROOFED USING ONE OF THE FOLLOWING METHODS. ALL INSTALLATIONS MUST BE DONE IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS AND INDUSTRY BEST PRACTICES.
 1. COLD SHRINK: ENCOMPASS CONNECTOR IN COLD SHRINK TUBING AND PROVIDE A DOUBLE WRAP OF 2" ELECTRICAL TAPE EXTENDING 2" BEYOND TUBING. PROVIDE 3M COLD SHRINK CXS SERIES OR EQUAL.
 2. SELF-AMALGAMATING TAPE: CLEAN SURFACES. APPLY A DOUBLE WRAP OF SELF-AMALGAMATING TAPE 2" BEYOND CONNECTOR. APPLY A SECOND WRAP OF SELF-AMALGAMATING TAPE IN OPPOSITE DIRECTION. APPLY DOUBLE WRAP OF 2" WIDE ELECTRICAL TAPE EXTENDING 2" BEYOND THE SELF-AMALGAMATING TAPE.
 3. 3M SLIM LOCK CLOSURE 716: SUBSTITUTIONS WILL NOT BE ALLOWED.
 4. OPEN FLAME ON JOB SITE IS NOT ACCEPTABLE

SECTION 11 800 - INSTALLATION OF MULTIMODAL BASE STATIONS (MMBTS) AND RELATED EQUIPMENT

SUMMARY:

- A. THIS SECTION SPECIFIES MMBTS CABINETS, POWER CABINETS, AND INTERNAL EQUIPMENT INCLUDING BY NOT LIMITED TO RECTIFIERS, POWER DISTRIBUTION UNITS, BASE BAND UNITS, SURGE ARRESTORS, BATTERIES, AND SIMILAR EQUIPMENT FURNISHED BY THE COMPANY FOR INSTALLATION BY THE CONTRACTOR (OFCL).
- B. CONTRACTOR SHALL PROVIDE AND INSTALL ALL MISCELLANEOUS MATERIALS AND PROVIDE ALL LABOR REQUIRED FOR INSTALLATION EQUIPMENT IN EXISTING CABINET OR NEW CABINET AS SHOWN ON DRAWINGS AND AS REQUIRE BY THE APPLICABLE INSTALLATION MOPS.
- C. COMPLY WITH MANUFACTURERS INSTALLATION AND START-UP REQUIREMENTS

DC CIRCUIT BREAKER LABELING

- A. LABEL CIRCUIT BREAKERS ACCORDING TO SPRINT CELL SITE ENGINEERING NOTICE - EN 2012-001, REV 1.

SECTION 11 800 - INSTALLATION OF MULTIMODAL BASE TRANSCIEVER STATIONS (MMBTS) AND RELATED EQUIPMENT

SUMMARY:

- A. THIS SECTION SPECIFIES MMBTS CABINETS, POWER CABINETS, AND INTERNAL EQUIPMENT INCLUDING BY NOT LIMITED TO RECTIFIERS, POWER DISTRIBUTION UNITS, BASE BAND UNITS, SURGE ARRESTORS, BATTERIES, AND SIMILAR EQUIPMENT FURNISHED BY THE COMPANY FOR INSTALLATION BY THE CONTRACTOR (OFCL).
- B. CONTRACTOR SHALL PROVIDE AND INSTALL ALL MISCELLANEOUS MATERIALS AND PROVIDE ALL LABOR REQUIRED FOR INSTALLATION EQUIPMENT IN EXISTING CABINET OR NEW CABINET AS SHOWN ON DRAWINGS AND AS REQUIRE BY THE APPLICABLE INSTALLATION MOPS.
- C. COMPLY WITH MANUFACTURERS INSTALLATION AND START-UP REQUIREMENTS

SUPPORTING DEVICES:

- A. MANUFACTURED STRUCTURAL SUPPORT MATERIALS: SUBJECT TO COMPLIANCE WITH REQUIREMENTS, PROVIDE PRODUCTS BY THE FOLLOWING:
 1. ALLIED TUBE AND CONDUIT
 2. B-LINE SYSTEM
 3. UNISTRUT DIVERSIFIED PRODUCTS
 4. THOMAS & BETTS
- B. FASTENERS: TYPES, MATERIALS, AND CONSTRUCTION FEATURES AS FOLLOWS:
 1. EXPANSION ANCHORS: CARBON STEEL WEDGE OR SLEEVE TYPE.
 2. POWER-DRIVEN THREADED STUDS: HEAT-TREATED STEEL, DESIGNED SPECIFICALLY FOR THE INTENDED SERVICE.
 3. FASTEN BY MEANS OF WOOD SCREWS ON WOOD.
 4. TOGGLE BOLTS ON HOLLOW MASONRY UNITS.
 5. CONCRETE INSERTS OR EXPANSION BOLTS ON CONCRETE OR SOLID MASONRY.
 6. MACHINE SCREWS, WELDED THREADED STUDS, OR SPRING-TENSION CLAMPS ON STEEL.
 7. EXPLOSIVE DEVICES FOR ATTACHING HANGERS TO STRUCTURE SHALL NOT BE PERMITTED.
 8. DO NOT WELD CONDUIT, PIPE STRAPS, OR ITEMS OTHER THAN THREADED STUDS TO STEEL STRUCTURES.
 9. IN PARTITIONS OF LIGHT STEEL CONSTRUCTION, USE SHEET METAL SCREWS.

SUPPORTING DEVICES:

- A. INSTALL SUPPORTING DEVICES TO FASTEN ELECTRICAL COMPONENTS SECURELY AND PERMANENTLY IN ACCORDANCE WITH NEC.
- B. COORDINATE WITH THE BUILDING STRUCTURAL SYSTEM AND WITH OTHER TRADES.
- C. UNLESS OTHERWISE INDICATED ON THE DRAWINGS, FASTEN ELECTRICAL ITEMS AND THEIR SUPPORTING HARDWARE SECURELY TO THE STRUCTURE IN ACCORDANCE WITH THE FOLLOWING:
- D. ENSURE THAT THE LOAD APPLIED BY ANY FASTENER DOES NOT EXCEED 25 PERCENT OF THE PROOF TEST LOAD.
- E. USE VIBRATION AND SHOCK-RESISTANT FASTENERS FOR ATTACHMENTS TO CONCRETE SLABS.

ELECTRICAL IDENTIFICATION:

- A. UPDATE AND PROVIDE TYPED CIRCUIT BREAKER SCHEDULES IN THE MOUNTING BRACKET, INSIDE DOORS OF AC PANEL BOARDS WITH ANY CHANGES MADE TO THE AC SYSTEM.
- B. BRANCH CIRCUITS FEEDING AVIATION OBSTRUCTION LIGHTING EQUIPMENT SHALL BE CLEARLY IDENTIFIED AS SUCH AT THE BRANCH CIRCUIT PANELBOARD.

SECTION 26 200 - ELECTRICAL MATERIALS AND EQUIPMENT

CONDUIT:

- A. RIGID GALVANIZED STEEL (RGS) CONDUIT SHALL BE USED FOR EXTERIOR LOCATIONS ABOVE GROUND AND IN UNFINISHED INTERIOR LOCATIONS AND FOR ENCASED RUNS IN CONCRETE. RIGID CONDUIT AND FITTINGS SHALL BE STEEL, COATED WITH ZINC EXTERIOR AND INTERIOR BY THE HOT DIP GALVANIZING PROCESS. CONDUIT SHALL BE PRODUCED TO ANSI SPECIFICATIONS C80.1, FEDERAL SPECIFICATION WW-C-581 AND SHALL BE LISTED WITH THE UNDERWRITERS' LABORATORIES. FITTINGS SHALL BE THREADED - SET SCREW OR COMPRESSION FITTINGS WILL NOT BE ACCEPTABLE. RGS CONDUITS SHALL BE MANUFACTURED BY ALLIED, REPUBLIC OR WHEATLAND.
- B. UNDERGROUND CONDUIT IN CONCRETE SHALL BE POLYVINYLCHLORIDE (PVC) SUITABLE FOR DIRECT BURIAL AS APPLICABLE. JOINTS SHALL BE BELLED, AND FLUSH SOLVENT WELDED IN ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS. CONDUIT SHALL BE CARLON ELECTRICAL PRODUCTS OR APPROVED EQUAL.
- C. TRANSITIONS BETWEEN PVC AND RIGID (RGS) SHALL BE MADE WITH PVC COATED METALLIC LONG SWEEP RADIUS ELBOWS.
- D. EMT OR RIGID GALVANIZED STEEL CONDUIT MAY BE USED IN FINISHED SPACES CONCEALED IN WALLS AND CEILINGS. EMT SHALL BE MILD STEEL, ELECTRICALLY WELDED, ELECTRO-GALVANIZED OR HOT-DIPPED GALVANIZED AND PRODUCED TO ANSI SPECIFICATION C80.3, FEDERAL SPECIFICATION WW-C-563, AND SHALL BE UL LISTED. EMT SHALL BE MANUFACTURED BY ALLIED, REPUBLIC OR WHEATLAND, OR APPROVED EQUAL. FITTINGS SHALL BE METALLIC COMPRESSION. SET SCREW CONNECTIONS SHALL NOT BE ACCEPTABLE.
- E. LIQUID TIGHT FLEXIBLE METALLIC CONDUIT SHALL BE USED FOR FINAL CONNECTION TO EQUIPMENT. FITTINGS SHALL BE METALLIC GLAND TYPE COMPRESSION FITTINGS, MAINTAINING THE INTEGRITY OF CONDUIT SYSTEM. SET SCREW CONNECTIONS SHALL NOT BE ACCEPTABLE. MAXIMUM LENGTH OF FLEXIBLE CONDUIT SHALL NOT EXCEED 6- FEET. LFMC SHALL BE PROTECTED AND SUPPORTED AS REQUIRE BY NEC. MANUFACTURERS OF FLEXIBLE CONDUITS SHALL BE CAROL, ANACONDA METAL HOSE OR UNIVERSAL METAL HOSE, OR APPROVED EQUAL.
- F. MINIMUM SIZE CONDUIT SHALL BE 3/4 INCH (21MM).

HUBS AND BOXES:

- A. AT ENTRANCES TO CABINETS OR OTHER EQUIPMENT NOT HAVING INTEGRAL THREADED HUBS PROVIDE METALLIC THREADED HUBS OF THE SIZE AND CONFIGURATION REQUIRED. HUB SHALL INCLUDE LOCKNUT AND NEOPRENE O-RING SEAL. PROVIDE IMPACT RESISTANT 105 DEGREE C PLASTIC BUSHINGS TO PROTECT CABLE INSULATION.
- B. CABLE TERMINATION FITTINGS FOR CONDUIT
 1. CABLE TERMINATORS FOR RGS CONDUITS SHALL BE TYPE CRC BY O-Z/GEDNEY OR EQUAL.
 2. CABLE TERMINATORS FOR LFMC SHALL BE ETCO - CL2075; OR MADE FOR THE PURPOSE PRODUCTS BY ROXTEC.
- C. EXTERIOR PULL BOXES AND PULL BOXES IN INTERIOR INDUSTRIAL AREAS SHALL BE PLATED CAST ALLOY, HEAVY DUTY, WEATHERPROOF, DUST PROOF, WITH GASKET, PLATED IRON ALLOY COVER AND STAINLESS STEEL COVER SCREWS, CROUSE-HINDS WAB SERIES OR EQUAL.
- D. CONDUIT OUTLET BODIES SHALL BE PLATED CAST ALLOY WITH SIMILAR GASKETED COVERS. OUTLET BODIES SHALL BE OF THE CONFIGURATION AND SIZE SUITABLE FOR THE APPLICATION. PROVIDE CROUSE-HINDS FORM 8 OR EQUAL.
- E. MANUFACTURER FOR BOXES AND COVERS SHALL BE HOFFMAN, SQUARE "D", CROUSE-HINDS, COOPER, ADALET, APPLETON, O-Z GEDNEY, RACO, OR APPROVED EQUAL.

SUPPLEMENTAL GROUNDING SYSTEM

- A. FURNISH AND INSTALL A SUPPLEMENTAL GROUNDING SYSTEM AS INDICATED ON THE DRAWINGS. SUPPORT SYSTEM WITH NON-MAGNETIC STAINLESS STEEL CLIPS WITH RUBBER GROMMETS. GROUNDING CONNECTORS SHALL BE TINNED COPPER WIRE, SIZES AS INDICATED ON THE DRAWINGS. PROVIDE STRANDED OR SOLID BARE OR INSULATED CONDUCTORS AS INDICATED.
- B. SUPPLEMENTAL GROUNDING SYSTEM: ALL CONNECTIONS TO BE MADE WITH CAD WELDS, EXCEPT AT EQUIPMENT USE LUGS OR OTHER AVAILABLE GROUNDING MEANS AS REQUIRED BY MANUFACTURER; AT GROUND BARS USE TWO HOLE SPADES WITH NO OX.
- C. STOLEN GROUND-BARS: IN THE EVENT OF STOLEN GROUND BARS, CONTACT SPRINT CM FOR REPLACEMENT INSTRUCTION USING THREADED ROD KITS.

EXISTING STRUCTURE:

- A. EXISTING EXPOSED WIRING AND ALL EXPOSED OUTLETS, RECEPTACLES, SWITCHES, DEVICES, BOXES, AND OTHER EQUIPMENT THAT ARE NOT TO BE UTILIZED IN THE COMPLETED PROJECT SHALL BE REMOVED OR DE-ENERGIZED AND CAPPED IN THE WALL, CEILING, OR FLOOR SO THAT THEY ARE CONCEALED AND SAFE. WALL, CEILING, OR FLOOR SHALL BE PATCHED TO MATCH THE ADJACENT CONSTRUCTION.

CONDUIT AND CONDUCTOR INSTALLATION:

- A. CONDUITS SHALL BE FASTENED SECURELY IN PLACE WITH APPROVED NON-PERFORATED STRAPS AND HANGERS. EXPLOSIVE DEVICES FOR ATTACHING HANGERS TO STRUCTURE WILL NOT BE PERMITTED. CLOSELY FOLLOW THE LINES OF THE STRUCTURE, MAINTAIN CLOSE PROXIMITY TO THE STRUCTURE AND KEEP CONDUITS IN TIGHT ENVELOPES. CHANGES IN DIRECTION TO ROUTE AROUND OBSTACLES SHALL BE MADE WITH CONDUIT OUTLET BODIES. CONDUIT SHALL BE INSTALLED IN A NEAT AND WORKMANLIKE MANNER, PARALLEL AND PERPENDICULAR TO STRUCTURE WALL AND CEILING LINES. ALL CONDUIT SHALL BE FISHED TO CLEAR OBSTRUCTIONS. ENDS OF CONDUITS SHALL BE TEMPORARILY CAPPED TO PREVENT CONCRETE, PLASTER OR DIRT FROM ENTERING. CONDUITS SHALL BE RIGIDLY CLAMPED TO BOXES BY GALVANIZED MALLEABLE IRON BUSHING ON INSIDE AND GALVANIZED MALLEABLE IRON LOCKNUT ON OUTSIDE AND INSIDE.
- B. CONDUCTORS SHALL BE PULLED IN ACCORDANCE WITH ACCEPTED GOOD PRACTICE.




1 INTERNATIONAL BLVD, SUITE 800
MAHWAH, NJ 07495
TEL: (800) 357-7641



SBA COMMUNICATIONS CORP.
134 FLANDERS ROAD, SUITE 125
WESTBOROUGH, MA 01581
TEL: (508) 251-0720
FAX: (508) 251-1755



45 BEECHWOOD DRIVE
N. ANDOVER, MA 01845
TEL: (978) 557-5553
FAX: (978) 336-5586



CHECKED BY: BB

APPROVED BY: DJC

SUBMITTALS			
REV.	DATE	DESCRIPTION	BY
2	09/28/17	CONSTRUCTION FINAL	DJM
1	05/08/14	ISSUED FOR CONSTRUCTION	SF
0	05/02/14	ISSUED FOR CONSTRUCTION	SF

SITE NUMBER:
CT23XC501-A

SITE NAME:
SBA


SITE ADDRESS:
300 PLAIN HILL ROAD
NORWICH, CT 06360

SHEET TITLE

OUTLINE
SPECIFICATIONS

SHEET NUMBER



SP-3




SPECIAL CONSTRUCTION NOTE:
SPRINT TOWER TOP WORK IS CONTINGENT ON THE FOLLOWING:
 * COMPLETION OF A GLOBAL STRUCTURAL STABILITY ANALYSIS (PROVIDED BY TOWER OWNER).
 * COMPLETION OF AN ANTENNA/RRH MOUNT STRUCTURAL ASSESSMENT (PROVIDED BY A&E VENDOR).
 * GC SHALL FURNISH, INSTALL AND COMPLETE ALL REQUIRED STRUCTURAL MODIFICATIONS AS INDICATED IN BEFORE-MENTIONED ANALYSIS AND ASSESSMENT.
 * SBA COMMUNICATIONS CORPORATION SHALL PROVIDE WRITTEN ACCEPTANCE/APPROVAL FOR THE COMPLETION OF ALL TOWER/FOUNDATION STRUCTURAL MODIFICATIONS INCLUDING (AS NECESSARY) CONTROLLED CONSTRUCTION INSPECTIONS, SHOP-DRAWING APPROVALS, MATERIALS TEST RESULTS, AND FINAL ENGINEER'S AFFIDAVIT.

NOTE:
EXISTING AZIMUTHS FROM SPRINT
SITE AUDIT DATED 10/24/13

NOTE:
SPRINT RAD CENTER SHOWN IN RED TEXT BASED ON SBA-PROVIDED COLLOCATION APPLICATION, EQUIPMENT DATABASE, AND STRUCTURAL ANALYSIS. THE SBA-PROVIDED ANTENNA RAD CENTER SHALL SUPERSEDE ANY CONFLICTING INFORMATION DERIVED FROM THE SPRINT NV 2.5 RFDS.



EXISTING PARTIAL ELEVATION PHOTO DETAIL
SCALE: N.T.S.




EXISTING ANTENNA PLAN
SCALE: N.T.S.

SPECIAL WORK NOTE:
JUMPERS FROM 2.5 RRH TO 2.5 ANTENNA CAN NOT EXCEED 15'. NOTIFY SPRINT CONSTRUCTION MANAGER OF ANY DISCREPANCY.

NOTES:
1) VERIFY PROPOSED AZIMUTHS WITH RF ENGINEER PRIOR TO INSTALLATION.

ANTENNA STATUS LEGEND:

EMPTY - EMPTY PIPE
(E) - EXISTING
(P) - INSTALL
NV - SPRINT ANTENNA MODEL APXVSP18-C-A20
2.5 - SPRINT ANTENNA




PROPOSED ANTENNA PLAN
SCALE: N.T.S.

1 A-3 1 A-5
INSTALL HYBRID CABLES INSIDE EXISTING MONOPOLE

NOTES:
GROUND EQUIPMENT NOT SHOWN FOR CLARITY.

ELEVATION
SCALE: 3/32"=1'-0"



CHECKED BY: BB
APPROVED BY: DJC

SUBMITTALS

REV.	DATE	DESCRIPTION	BY
2	09/28/17	CONSTRUCTION FINAL	DJM
1	05/08/14	ISSUED FOR CONSTRUCTION	SF
0	05/02/14	ISSUED FOR CONSTRUCTION	SF

SITE NUMBER:
CT23XC501-A

SITE NAME:
SBA

SITE ADDRESS:
300 PLAIN HILL ROAD
NORWICH, CT 06360

SHEET TITLE
ELEVATION AND ANTENNA PLANS

SHEET NUMBER
A-2



RFDS Sheet

(by SBA Network Services 4/8/14. NOTE: General Contractor/Tower Crew shall verify that the latest RFDS is used for equipment installation.)

General Site Information

Site ID	CT23XC501	Equipment Vendor	ALU
Market	Northern Connecticut	Latitude	41.576949
Region	East	Longitude	-72.103620
MLA	SBA	LL SITE ID	CT01365-S
Structure Type	OTHER		
BTS Type	Outdoor Macro		
Solution ID	Not Available	Siterra SR Equipment Type	Outdoor Macro
		Equipment Vendor	ALU
		Incremental Power Draw Needed by Added Equipment	

Base Equipment

BBU Kit	ALU BBU Kit	Top Hat	None
BBU Kit Qty	1	Top Hat Qty	N/A
Growth Cabinet	None	Top Hat Dimensions (Inches)	N/A
Growth Cabinet Qty	N/A	Top Hat Weight (Lbs.)	N/A
Growth Cabinet Dimensions (Inches)	N/A		
Growth Cabinet Weight (Lbs.)	N/A		

RF Path Information

RRH	TD-RRH8x20-25		
RRH Qty	3		
RRH Dimensions (Inches)	26.1" x 18.6" x 6.7"		
RRH Weight (Lbs.)	70.0		
RRH Mount Weight (Lbs.)	10		
Power and Fiber Cable	ALU Hybrid Cable		
Cable Qty	1		
Weight per Foot (Lbs.)	0.992		
Diameter (Inches)	1.250		
Hybrid Cable Length (Feet) (** A&E 250)	216	(Estimated by Sprint as Antenna CL plus 20%; DO NOT BOM using this length.)	
Coax Jumper	Coax Jumper. Mfg TBD.		
Coax Jumper Qty	27		
Coax Jumper Length (Feet) (** A&E 5)	8		
Coax Jumper Weight (Lbs.)	1.7		
Coax Jumper Diameter (Inches)	0.5		
AISG Cable	Commscope ATCB-B01-006		
AISG Cable Qty	3		
AISG Diameter (Inches)	0.315		
AISG Cable Length (Feet) (** A&E 5)	8		
Weight of Entire AISG Cable (Lbs.)	1.3		

Antenna Sector Information

	Sector 1	Sector 2	Sector 3
Antenna Make/Model	RFS APXV9TM14-ALU-I20	RFS APXV9TM14-ALU-I20	RFS APXV9TM14-ALU-I20
Antenna Qty	1	1	1
Antenna Dimensions (Inches)	56.3 x 12.6 x 6.3	56.3 x 12.6 x 6.3	56.3 x 12.6 x 6.3
Antenna Weight (Lbs.)	55.1	55.1	55.1
Antenna Mounting Kit Weight (Lbs.)	11.5	11.5	11.5
CL Height (Feet) (* SBA171')	180.0	180.0	180.0
Antenna Azimuth (Degrees)	330	80	180
Antenna Mechanical Downtilt (Degrees)	0	0	0
Antenna Etilt (Degrees)	-2	-2	-2
RF Filter Make/Model	N/A	N/A	N/A

Comments

RFDS generated 4/8/14 by SBA Network Services from Sprint Plan of Record dated 4/2/14.

Comments in Red Text provided by A&E Vendor.

IMPORTANT CONSTRUCTION NOTE: General Contractor/Tower Crew shall verify that the latest RFDS is used for equipment installation.

* Note: Antenna Rad Center based on SBA-Provided Collocation Application, Equipment Database, and Structural Analysis. The SBA-Provided Antenna Rad Center shall supersede any conflicting information derived from the Sprint NV 2.5 Database.

** Note: Sprint CM shall confirm Hybrid Cable Length, Coax Jumper Length and AISG Cable Length before preparing BOM. A&E Recommended Hybrid Cable Length based on NV 2.5 Equipment Audit plus 20 Feet for (2) 10-foot coils at each end of the fiber trunk.

SPRINT CONSTRUCTION STANDARDS:

GENERAL CONTRACTOR SHALL ADHERE TO THE FOLLOWING SPRINT CONSTRUCTION STANDARDS.

- CONSTRUCTION STANDARDS: INTEGRATED CONSTRUCTION STANDARDS FOR WIRELESS SITES - (CURRENT VERSION), INCLUDING EXHIBITS A-M.
- CONSTRUCTION SPECIFICATIONS: CONSTRUCTION STANDARDS EXHIBIT A - STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES (CURRENT VERSION).
- GROUNDING STANDARDS: EXTERIOR GROUNDING SYSTEM DESIGN. GROUNDING STANDARDS (SUPPLEMENT): ANTI-THEFT UPDATE TO SPRINT GROUNDING 082412 AND SPRINT ENGINEERING LETTER EL-0504 DATED 04.20.12.
- WEATHER PROOFING STANDARDS: EXCERPT FROM CONSTRUCTION STANDARDS EXHIBIT A, SECTION 3.6 WEATHERPROOFING CONNECTORS AND GROUND KITS.
- COLOR CODING: SPRINT NEXTEL ANT AND LINE COLOR CODING PER SPRINT TS-0200 CURRENT VERSION.
- GENERAL CONTRACTOR TO FIELD VERIFY AZIMUTH AND CL HEIGHT AND MECHANICAL DOWNTILT. IF DIFFERENT THAN CALLED OUT IN RFDS, HALT ANTENNA WORK FOR ONE HOUR, CALL SPRINT RF ENGINEER (OR MANAGER IF RF ENGINEER DOES NOT ANSWER, BUT STILL LEAVE A MESSAGE TO RF ENGINEER) USING SPRINT-PROVIDED CONTACT INFORMATION FOR FURTHER INSTRUCTIONS. IF SPRINT DOES NOT RESPOND WITHIN ONE HOUR, PLACE 2.5G ANTENNA AT SAME CL HEIGHT AS 1.9G ANTENNA AND EMAIL CORRECT CL HEIGHT AND AZIMUTH TO SPRINT RF ENGINEER. UPDATE AS-BUILD DRAWING WITH CORRECT CL HEIGHT. ALSO EMAIL CORRECT 1900 MHZ AND 800 MHZ ANTENNA CL HEIGHT, AZIMUTH AND MECHANICAL DOWNTILT TO RF ENGINEER.
- AISG TESTS TO VERIFY OPERATION IS TO BE PERFORMED AFTER FINAL INSTALLATION OF ANTENNAS AND AISG CABLES HAVE BEEN CONNECTED. VERIFY OPERATION OF ALL EXISTING SPRINT AISG EQUIPMENT INCLUDING 800MHZ, 1.9GHZ AND 2.5G. TEST INCLUDE COMPLETE DOWNTILT, AZIMUTH (IF APPLICABLE) AND BEAMWIDTH SWINGS (IF APPLICABLE). DOCUMENT AISG TEST RESULTS IN COAX SWEEP TEST SPREADSHEET.
- GENERAL CONTRACTOR MUST INSURE THAT NO OBJECT IS LOCATED IN FRONT OF ANTENNA. THIS MEANS NO OBJECT IS TO BE LOCATED 45 DEGREES LEFT AND RIGHT OF FRONT OF ANTENNA OR 7 DEGREES UP AND DOWN FROM CENTER OF ANTENNA. IF THIS IS NOT POSSIBLE, CONTACT RF ENGINEER FOR FURTHER INSTRUCTION. IN ADDITION, 2.5G ANTENNA IS NOT TO BE PLACED IN FRONT OF ANY OTHER ANTENNA USING THE SAME 45 DEGREE RULE. THIS INCLUDES SPRINT AND NON-SPRINT ANTENNAS.
- GENERAL CONTRACTOR IS REQUIRED TO USE A DIGITAL ALIGNMENT TOOL TO SET AZIMUTH, ROLL AND DOWNTILT. AZIMUTH ACCURACY IS TO BE WITHIN 1 DEGREES. DOWNTILT AND ROLL (LEFT TO RIGHT TILT) IS TO BE WITHIN 0.1 DEGREES. IF FOR SOME REASON THIS ACCURACY CANNOT BE ACHIEVED, UPDATE AS-BUILT DRAWINGS AND EMAIL SPRINT RF ENGINEER WITH AS-BUILT SETTINGS. USE 3Z RF ALIGNMENT TOOL OR EQUIVALENT TOOL. [HTTP://WWW.3ZTELECOM.COM/ANTENNA-ALIGNMENT-TOOL/](http://www.3ztelecom.com/antenna-alignment-tool/).




1 INTERNATIONAL BLVD, SUITE 800
MAHWAH, NJ 07495
TEL: (800) 357-7641



SBA COMMUNICATIONS CORP.
134 FLANDERS ROAD, SUITE 125
WESTBOROUGH, MA 01581
TEL: (508) 251-0720
FAX: (508) 251-1755



45 BEECHWOOD DRIVE
N. ANDOVER, MA 01845
TEL: (978) 557-5553
FAX: (978) 336-5586



CHECKED BY: BB

APPROVED BY: DJC

SUBMITTALS

REV.	DATE	DESCRIPTION	BY
2	09/28/17	CONSTRUCTION FINAL	DJM
1	05/08/14	ISSUED FOR CONSTRUCTION	SF
0	05/02/14	ISSUED FOR CONSTRUCTION	SF

SITE NUMBER:
CT23XC501-A

SITE NAME:
SBA

SITE ADDRESS:
300 PLAIN HILL ROAD
NORWICH, CT 06360

SHEET TITLE

RF DATA SHEET


SHEET NUMBER

A-3




RF DATA SHEET

SCALE: N.T.S.


1
A-3



CABLE COLOR CODING DIAGRAM
SCALE: N.T.S.



NOTE:
GENERAL CONTRACTOR SHALL VERIFY THAT THE LATEST RF DATA SHEET IS USED FOR EQUIPMENT INSTALLATION.



CHECKED BY: BB
APPROVED BY: DJC

SUBMITTALS			
REV.	DATE	DESCRIPTION	BY
2	09/28/17	CONSTRUCTION FINAL	DJM
1	05/08/14	ISSUED FOR CONSTRUCTION	SF
0	05/02/14	ISSUED FOR CONSTRUCTION	SF

SITE NUMBER:
CT23XC501-A

SITE NAME:
SBA

SITE ADDRESS:
300 PLAIN HILL ROAD
NORWICH, CT 06360






SHEET TITLE
RAN WIRING DIAGRAM

SHEET NUMBER
A-4

HYBRID CABLE DC CONDUCTOR SIZE GUIDELINE				
MANUF:	RFS			
CABLE	LENGTH	DC CONDUCTOR	CABLE DIAMETER	
FIBER ONLY	VARIES	USE NV HYBRIFLEX	5/8"	
HYBRIFLEX	<200'	8 AWG	1-1/4"	
HYBRIFLEX	225-300'	6 AWG	1-1/4"	
HYBRIFLEX	325-375'	4 AWG	1-1/4"	

RFS HYBRIFLEX RISER CABLE SCHEDULE

Power Type	Hybrid cable	Length
Fiber Only (Existing DC Power)	MN: HB058-M12-050F 12x multi-mode fiber pairs, Top: Outdoor protected connectors, Bottom: LC Connectors, 5/8 cable, 50 ft	50 ft
	MN: HB058-M12-075F	75 ft
	MN: HB058-M12-100F	100 ft
	MN: HB058-M12-125F	125 ft
	MN: HB058-M12-150F	150 ft
	MN: HB058-M12-175F	175 ft
8 AWG Power	MN: HB114-08U3M12-050F 3x 8 AWG power pairs, 12x multi-mode fiber pairs, Outdoor rated connectors & LC Connectors, 1 1/4 cable, 50 ft	50 ft
	MN: HB114-08U3M12-075F	75 ft
	MN: HB114-08U3M12-100F	100 ft
	MN: HB114-08U3M12-125F	125 ft
	MN: HB114-08U3M12-150F	150 ft
	MN: HB114-08U3M12-175F	175 ft
6 AWG Power	MN: HB114-13U3M12-225F 3x 6 AWG power pair, 12x multi-mode fiber pairs, Outdoor rated connectors & LC Connectors, 1 1/4 cable, 225 ft	225 ft
	MN: HB114-13U3M12-250F	250 ft
	MN: HB114-13U3M12-275F	275 ft
	MN: HB114-13U3M12-300F	300 ft
4 AWG Power	MN: HB114-21U3M12-325F 3x 4 AWG power pair, 12x multi-mode fiber pairs, Outdoor rated connectors & LC Connectors, 1 1/4 cable, 325 ft	325 ft
	MN: HB114-21U3M12-350F	350 ft
	MN: HB114-21U3M12-375F	375 ft





2.5 ANTENNA SPECIFICATIONS 2
SCALE: N.T.S. A-5

RFS HYBRIFLEX JUMPER CABLE SCHEDULE

Power Type	Hybrid Jumper cable	Length
Fiber Only	MN: HBF012-M3-5F1 5 ft, 3x multi-mode fiber pairs, Outdoor & LC connectors, 1/2 cable	5 ft
	MN: HBF012-M3-10F1	10 ft
	MN: HBF012-M3-15F1	15 ft
8 AWG Power	MN: HBF058-08U1M3-5F1 5 ft, 1x 8 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 5/8 cable	5 ft
	MN: HBF058-08U1M3-10F1	10 ft
	MN: HBF058-08U1M3-15F1	15 ft
6 AWG Power	MN: HBF058-13U1M3-5F1 5 ft, 1x 6 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 5/8 cable	5 ft
	MN: HBF058-13U1M3-10F1	10 ft
	MN: HBF058-13U1M3-15F1	15 ft
4 AWG Power	MN: HBF078-21U1M3-5F1 5 ft, 1x 4 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 7/8 cable	5 ft
	MN: HBF078-21U1M3-10F1	10 ft
	MN: HBF078-21U1M3-15F1	15 ft

MANUF:	ALCATEL-LUCENT
MODEL:	TD-RRH8x20-25
LENGTH:	26.1
WIDTH:	18.6
DEPTH:	6.7
WEIGHT:	70 LBS
AREA:	3.5 SF



2.5 RRH'S 3
SCALE: N.T.S. A-5

2.5 HYBRID CABLE X-SECTION AND DATA 1
SCALE: N.T.S. A-5

* NOTE: SPRINT CM TO CONFIRM HYBRID RISER CABLE AND HYBRID JUMPER CABLE MODEL NUMBERS BEFORE PREPARING BOM.




1 INTERNATIONAL BLVD, SUITE 800
MAHWAH, NJ 07495
TEL: (800) 357-7641



SBA COMMUNICATIONS CORP.
134 FLANDERS ROAD, SUITE 125
WESTBOROUGH, MA 01581
TEL: (508) 251-0720
FAX: (508) 251-1755



45 BEECHWOOD DRIVE
N. ANDOVER, MA 01845
TEL: (978) 557-5553
FAX: (978) 336-5586



CHECKED BY: BB

APPROVED BY: DJC

SUBMITTALS			
REV.	DATE	DESCRIPTION	BY
2	09/28/17	CONSTRUCTION FINAL	DJM
1	05/08/14	ISSUED FOR CONSTRUCTION	SF
0	05/02/14	ISSUED FOR CONSTRUCTION	SF



SITE NUMBER:
CT23XC501-A

SITE NAME:
SBA

SITE ADDRESS:
300 PLAIN HILL ROAD
NORWICH, CT 06360

SHEET TITLE
EQUIPMENT DETAILS

SHEET NUMBER
A-5



FRONT VIEW

EXISTING MMBTS OUTDOOR CABINET WITH 2.5 EQUIPMENT

SCALE: N.T.S.

1
A-6



SOURCE: SPRINT SITE AUDIT 10-24-13

FRONT VIEW

EXISTING 2.5 POWER BBU CABINET

SCALE: N.T.S.

2
A-6

CHECKED BY: BB

APPROVED BY: DJC

SUBMITTALS			
REV.	DATE	DESCRIPTION	BY
2	09/28/17	CONSTRUCTION FINAL	DJM
1	05/08/14	ISSUED FOR CONSTRUCTION	SF
0	05/02/14	ISSUED FOR CONSTRUCTION	SF


SITE NUMBER:
CT23XC501-A

SITE NAME:
SBA

SITE ADDRESS:
300 PLAIN HILL ROAD
NORWICH, CT 06360

SHEET TITLE
EQUIPMENT
DETAILS

SHEET NUMBER
A-6



NOTE: ONE SECTOR SHOWN FOR CLARITY

INSTALLATION NOTES:

1. CONTRACTOR TO ENSURE THAT RRH MOUNTING DOES NOT INTERFERE WITH CLIMBING LADDER/PEGS, CABLE CLIMB, OR COAX PORTS. MONOPOLE: COLLAR-MOUNT RRH CLUSTER SHALL PROVIDE AN OPENING BETWEEN ADJACENT RRH AT LEAST 30" WIDE CENTERED ON THE EXISTING SAFETY-CLIMB AND 30" DEEP FROM THE FACE OF THE POLE. SELF-SUPPORT: RRH LEG-MOUNT OR FACE-MOUNT SHALL PROVIDE AN UNOBSTRUCTED VERTICAL CLIMBING PASSAGE AT LEAST 30" WIDE AND 30" DEEP CENTERED ON THE LEG WITH THE CLIMBING LADDER/PEGS.
2. CONTRACTOR TO VERIFY DIAMETER OF EXISTING MONOPOLE BEFORE ORDERING PARTS.
3. CONTRACTOR TO VERIFY IN FIELD SIZE OF EXISTING MOUNTING PIPE TO BE 2-1/2" STD (2.88 O.D.) PIPE MAST (6'-0" LONG).
4. VERIFY EXACT RRH AND ANTENNA MODEL & AZIMUTHS WITH RF ENGINEER PRIOR TO INSTALLATION.
5. ROTATE EXISTING ANTENNA FRAME AS NEEDED TO ACCOMMODATE INSTALL ANTENNAS.
6. RRH PLACEMENT FOR REFERENCE ONLY. CONTRACTOR SHALL PLACE RRH IN CORRECT ORDER MATCHING INSTALL ANTENNA PLACEMENT AND ENSURE THAT THERE IS ENOUGH CLEARANCE FOR RRHS TO BE PLACED ON THE INSIDE ON THE ANTENNA FRAME.
7. INSTALL EQUIPMENT TO BE MOUNTED PER MANUFACTURERS SPECIFICATIONS.

SPECIAL CONSTRUCTION NOTE:

- SPRINT TOWER TOP WORK IS CONTINGENT ON THE FOLLOWING:
- * COMPLETION OF A GLOBAL STRUCTURAL STABILITY ANALYSIS (PROVIDED BY TOWER OWNER).
 - * COMPLETION OF AN ANTENNA/RRH MOUNT STRUCTURAL ASSESSMENT (PROVIDED BY A&E VENDOR).
 - * GC SHALL FURNISH, INSTALL AND COMPLETE ALL REQUIRED STRUCTURAL MODIFICATIONS AS INDICATED IN BEFORE-MENTIONED ANALYSIS AND ASSESSMENT.
 - * SBA COMMUNICATIONS CORPORATION SHALL PROVIDE WRITTEN ACCEPTANCE/APPROVAL FOR THE COMPLETION OF ALL TOWER/FOUNDATION STRUCTURAL MODIFICATIONS INCLUDING (AS NECESSARY) CONTROLLED CONSTRUCTION INSPECTIONS, SHOP-DRAWING APPROVALS, MATERIALS TEST RESULTS, AND FINAL ENGINEER'S AFFIDAVIT.





1 INTERNATIONAL BLVD, SUITE 800
MAHWAH, NJ 07495
TEL: (800) 357-7641



SBA COMMUNICATIONS CORP.
134 FLANDERS ROAD, SUITE 125
WESTBOROUGH, MA 01581
TEL: (508) 251-0720
FAX: (508) 251-1755



45 BEECHWOOD DRIVE
N. ANDOVER, MA 01845
TEL: (978) 557-5553
FAX: (978) 336-5586



SECTION A-A

NOTE: ONE SECTOR SHOWN FOR CLARITY

2.5 ANTENNA AND RRH MOUNTING DETAIL

SCALE: N.T.S.

1
S-1

INSTALL 2.5GHz ANTENNA MOUNTED TO EXISTING PIPE (TYP. OF 1 PER SECTOR, TOTAL OF 3)

INSTALL 2.5GHz RRH WITH SOLAR SHIELD AND SMALL PIPE MOUNTING KIT ATTACHED TO EXISTING MOUNTING PIPE. (MOUNT PER MANUFACTURERS SPECIFICATIONS) (SEE INSTALLATION NOTE 1)



SOURCE: SPRINT SITE AUDIT 10-24-13

NOTE: ONE SECTOR SHOWN FOR CLARITY

2.5 ANTENNA AND RRH PHOTO DETAIL AND EQUIPMENT SCHEMATIC

SCALE: N.T.S.

2
S-1

CHECKED BY: BB

APPROVED BY: DJC

SUBMITTALS

REV.	DATE	DESCRIPTION	BY
2	09/28/17	CONSTRUCTION FINAL	DJM
1	05/08/14	ISSUED FOR CONSTRUCTION	SF
0	05/02/14	ISSUED FOR CONSTRUCTION	SF

SITE NUMBER:
CT23XC501-A

SITE NAME:
SBA


SITE ADDRESS:
300 PLAIN HILL ROAD
NORWICH, CT 06360

SHEET TITLE

STRUCTURAL
DETAILS


SHEET NUMBER

S-1



TYPICAL POWER AND GROUNDING ONE LINE DIAGRAMS
SCALE: N.T.S.

1
E-1



EXISTING PPC BREAKER PANEL
SCALE: N.T.S.

ELECTRICAL NOTES

- ALL ELECTRICAL WORK SHALL CONFORM TO THE REQUIREMENTS OF THE NATIONAL ELECTRICAL CODE (NEC) AS WELL AS APPLICABLE STATE AND LOCAL CODES.
- THE ELECTRICAL CONTRACTOR SHALL COORDINATE ALL CONDUIT ROUTING WITH LOCAL UTILITY COMPANIES AND SPRINT CONSTRUCTION MANAGER.
- ALL CONDUITS ROUTED BELOW GRADE SHALL TRANSITION TO RIGID GALVANIZED ELBOWS WITH RIGID GALVANIZED STEEL CONDUIT ABOVE GRADE.
- ALL METAL CONDUITS SHALL BE PROVIDED WITH GROUNDING BUSHINGS.
- GENERAL CONTRACTOR SHALL PROVIDE ALL DIRECT BURIED CONDUITS WITH PLASTIC WARNING TAPE IDENTIFYING CONTENTS. TAPE COLORS SHALL BE ORANGE FOR TELEPHONE AND RED FOR ELECTRIC.
- ALL ELECTRICAL ITEMS SHALL BE U.L. APPROVED OR LISTED AND PROCURED PER SPECIFICATION REQUIREMENTS.
- THE ELECTRICAL WORK INCLUDES ALL LABOR AND MATERIALS DESCRIBED BY DRAWINGS AND SPECIFICATIONS INCLUDING INCIDENTAL WORK TO PROVIDE COMPLETE OPERATING AND APPROVED ELECTRICAL SYSTEM.
- GENERAL CONTRACTOR SHALL PAY FEES FOR PERMITS, AND IS RESPONSIBLE FOR OBTAINING SAID PERMITS AND COORDINATION OF INSPECTIONS.
- ELECTRICAL AND TELCO WIRING OUTSIDE A BUILDING AND EXPOSED TO WEATHER SHALL BE IN WATER TIGHT GALVANIZED RIGID STEEL CONDUITS OR SCHEDULE 80 PVC (AS PERMITTED BY CODE) AND WHERE REQUIRED IN LIQUID TIGHT FLEXIBLE METAL OR NONMETALLIC CONDUITS.
- BURIED CONDUIT SHALL BE SCHEDULE 40 PVC.
- ELECTRICAL WIRING SHALL BE COPPER WITH TYPE XHHW, THWN, OR THIN INSULATION.
- RUN ELECTRICAL CONDUIT OR CABLE BETWEEN ELECTRICAL UTILITY DEMARCATION POINT AND PROJECT OWNER CELL SITE PPC AS INDICATED ON THIS DRAWING. PROVIDE FULL LENGTH PULL ROPE. COORDINATE INSTALLATION WITH UTILITY COMPANY.
- RUN TELCO CONDUIT OR CABLE BETWEEN TELEPHONE UTILITY DEMARCATION POINT AND PROJECT OWNER CELL SITE TELCO CABINET AND BTS CABINET AS INDICATED ON THIS DRAWING. PROVIDE FULL LENGTH PULL ROPE IN INSTALLED TELCO CONDUIT. PROVIDE GREENLEE CONDUIT MEASURING TAPE AT EACH END.
- FIBER OPTIC CIRCUITS SHALL BE IN ACCORDANCE WITH NEC ARTICLE 770-OPTICAL FIBER CABLES AND RACEWAYS.
- COMMUNICATIONS CIRCUITS SHALL BE IN ACCORDANCE WITH NEC ARTICLE 800-COMMUNICATIONS SYSTEMS.



1 INTERNATIONAL BLVD, SUITE 800
MAHWAH, NJ 07495
TEL: (800) 357-7641



SBA COMMUNICATIONS CORP.
134 FLANDERS ROAD, SUITE 125
WESTBOROUGH, MA 01581
TEL: (508) 251-0720
FAX: (508) 251-1755



1600 OSGOOD STREET
BUILDING 20 NORTH, SUITE 3090
ROCKFORD, MA 01845
TEL: (978) 557-5553
FAX: (978) 557-5553



CHECKED BY: BB

APPROVED BY: DJC

SUBMITTALS			
REV.	DATE	DESCRIPTION	BY
2	09/28/17	CONSTRUCTION FINAL	DJM
1	05/08/14	ISSUED FOR CONSTRUCTION	SF
0	05/02/14	ISSUED FOR CONSTRUCTION	SF

SITE NUMBER:
CT23XC501-A

SITE NAME:
SBA

SITE ADDRESS:
300 PLAIN HILL ROAD
NORWICH, CT 06360


SHEET TITLE
ONE LINE DIAGRAM

SHEET NUMBER
E-1

SYMBOL LEGEND

- EXOTHERMIC CONNECTION
- MECHANICAL CONNECTION
- CABLE GROUNDING KIT

UNLESS NOTED OTHERWISE, ALL BONDING CONDUCTORS ARE 2# SOLID TINNED BCW.



NOTE: HYBRIFLEX (FIBER & POWER) AND HYBRIFLEX (FIBER-ONLY) SHOWN. REFER TO RAN EQUIPMENT RFDS FOR SITE-SPECIFIC SCENARIO.

2.5 RAN EQUIPMENT GROUNDING SCHEMATIC 1
SCALE: N.T.S. E-2

PROTECTIVE GROUNDING SYSTEMS GENERAL NOTES:

1. GROUNDING SHALL BE IN ACCORDANCE WITH NEC ARTICLE 250-GROUNDING AND BONDING.
2. GROUNDING SHALL BE IN ACCORDANCE WITH SPRINT SSEO DOCUMENTS 3.018.02.004 "BONDING, GROUNDING AND TRANSIENT PROTECTION FOR CELL SITES" AND 3.018.10.002 "SITE RESISTANCE TO EARTH TESTING".
3. PROVIDE GROUND CONNECTIONS FOR ALL METALLIC STRUCTURES, ENCLOSURES, RACEWAYS AND OTHER CONDUCTIVE ITEMS ASSOCIATED WITH THE INSTALLATION OF CARRIER'S EQUIPMENT.
4. GROUND CONNECTIONS: CLEAN SURFACES THOROUGHLY BEFORE APPLYING GROUND LUGS OR CLAMPS. IF SURFACE IS COATED, REMOVE THE COATING, APPLY A NON-CORROSIVE APPROVED COMPOUND TO CLEAN SURFACE AND INSTALL LUGS OR CLAMPS. WHERE GALVANIZING IS REMOVED FROM METAL, IT SHALL BE PAINTED OR TOUCHED UP WITH "GALVAMOX" OR EQUAL.
5. ALL GROUNDING WIRES SHALL PROVIDE A STRAIGHT, DOWNWARD PATH TO GROUND WITH GRADUAL BENDS AS REQUIRED. GROUND WIRES SHALL NOT BE LOOPED OR SHARPLY BENT.
6. ALL CLAMPS AND SUPPORTS USED TO SUPPORT THE GROUNDING SYSTEM CONDUCTORS AND PVC CONDUITS SHALL BE PVC TYPE (NON CONDUCTIVE). DO NOT USE METAL BRACKETS OR SUPPORTS WHICH WOULD FORM A COMPLETE RING AROUND ANY GROUNDING CONDUCTOR.
7. ALL GROUND WIRES SHALL BE #2 SOLID TINNED BCW UNLESS NOTED OTHERWISE.
8. PROVIDE DEDICATED #2 AWG COPPER GROUND WIRE FROM EACH ANTENNA MOUNTING PIPE TO ASSOCIATED CIGBE.
9. GROUND ANTENNA BASES, FRAMES, CABLE RACKS, AND OTHER METALLIC COMPONENTS WITH #2 INSULATED TINNED STRANDED COPPER GROUNDING CONDUCTORS AND CONNECT TO INSULATED SURFACE MOUNTED GROUND BARS. CONNECTION DETAILS SHALL FOLLOW MANUFACTURER'S SPECIFICATIONS FOR GROUNDING.
10. EACH EQUIPMENT CABINET SHALL BE CONNECTED TO THE MASTER ISOLATION GROUND BAR (MGB) WITH #2 SOLID TINNED BCW EQUIPMENT CABINETS WILL HAVE (2) CONNECTIONS.
11. GROUND HYBRIFLEX SHIELD AT TOP, BOTTOM AND AT TRANSITION TO HYBRIFLEX JUMPER CABLES AT EQUIPMENT CABINET ENTRANCE USING MANUFACTURER'S GUIDELINES. WHEN HYBRIFLEX CABLE EXCEEDS 200', GROUND AT INTERVALS NOT EXCEEDING 100'.
12. THE CONTRACTOR SHALL VERIFY THAT THE EXISTING GROUND BARS HAVE ENOUGH SPACE/HOLES FOR ADDITIONAL TWO HOLE LUGS.
13. EXOTHERMIC WELDING IS RECOMMENDED FOR GROUNDING CONNECTION WHERE PRACTICAL OTHERWISE, THE CONNECTION SHALL BE MADE USING COMPRESSION TYPE-2 HOLES, LONG BARREL LUGS OR DOUBLE CRIMP "C" CLAMP. THE COPPER CABLES SHALL BE COATED WITH AN ANTI-OXIDANT (THOMAS BETTS KOPR-SHILD) BEFORE MAKING THE CRIMP CONNECTIONS THE CONTRACTOR SHALL FOLLOW MANUFACTURER'S RECOMMENDED TORQUES ON THE BOLT ASSEMBLY TO SECURE CONNECTIONS.
14. AT ALL TERMINATIONS AT EQUIPMENT ENCLOSURES, PANEL, AND FRAMES OF EQUIPMENT AND WHERE EXPOSED FOR GROUNDING, CONDUCTOR TERMINATION SHALL BE PERFORMED UTILIZING TWO HOLE BOLTED TONGUE COMPRESSION TYPE LUGS WITH STAINLESS STEEL SELF-TAPPING SCREWS.
15. THE MASTER GROUND BAR (MGB) SHALL BE MADE OF BARE 1/4"x2" COPPER (FOR OUTDOOR APPLICATIONS IT SHALL BE TINNED COPPER) AND LARGE ENOUGH TO ACCOMMODATE THE REQUIRED NUMBER OF GROUND CONNECTIONS. THE HARDWARE SECURING THE MGB SHALL ELECTRICAL INSULATE THE MGB FROM ANY STRUCTURE TO WHICH IT IS FASTENED.
16. ALL BOLTS, WASHERS, AND NUTS USED ON GROUNDING CONNECTIONS SHALL BE STAINLESS STEEL.
17. ALL GROUNDING CONNECTIONS SHALL BE COATED WITH A COPPER SHIELD ANTI-CORROSIVE AGENT SUCH AS T&B KOPR SHIELD. VERIFY PRODUCT WITH SPRINT CONSTRUCTION MANAGER.
18. FOR NEW OR REPAIRED GROUNDING EQUIPMENT. REFER TO SPRINT GROUNDING STANDARDS AND FOLLOWING (SUPPLEMENTS):
-ANTI-THEFT UPDATE TO SPRINT GROUNDING DATED: 08-24-12 (OR CURRENT VERSION)
-SPRINT ENGINEERING LETTER EL-0504 DATED: 04-20-12 (OR CURRENT VERSION)



1 INTERNATIONAL BLVD, SUITE 800
MAHWAH, NJ 07495
TEL: (800) 357-7641



SBA COMMUNICATIONS CORP.
134 FLANDERS ROAD, SUITE 125
WESTBOROUGH, MA 01581
TEL: (508) 251-0720
FAX: (508) 251-1755



45 BEECHWOOD DRIVE
N. ANDOVER, MA 01845
TEL: (978) 557-5553
FAX: (978) 336-5586



CHECKED BY: BB

APPROVED BY: DJC

SUBMITTALS			
REV.	DATE	DESCRIPTION	BY
2	09/28/17	CONSTRUCTION FINAL	DJM
1	05/08/14	ISSUED FOR CONSTRUCTION	SF
0	05/02/14	ISSUED FOR CONSTRUCTION	SF


SITE NUMBER:
CT23XC501-A

SITE NAME:
SBA

SITE ADDRESS:
300 PLAIN HILL ROAD
NORWICH, CT 06360


SHEET TITLE
GROUNDING DETAILS AND NOTES

SHEET NUMBER
E-2



- NOTES**
1. APPLY NO-OX TO LUG AND BAR CONTACT SURFACE. DO NOT COAT INLINE LUG.
 2. IF STOLEN GROUND BARS ARE ENCOUNTERED, CONTACT SPRINT CM FOR REPLACEMENT THREADED ROD KIT.

INSTALLATION OF GROUNDING CONDUCTOR TO GROUNDING BAR 2
SCALE: N.T.S. E-2



TWO HOLE LUG 3
SCALE: N.T.S. E-2