



**Crown Castle**  
3530 Torington Way, Suite 300  
Charlotte, NC 28277

August 29, 2014

Melanie A. Bachman  
Connecticut Siting Council  
10 Franklin Square  
New Britain, CT 06051

**RE: Sprint PCS-Exempt Modification - Crown Site BU: 881541**  
**Sprint PCS Site ID: CT23XC313**  
**Located at: 700 Grassy Hill Road, Orange, CT 06477**

Dear Ms. Bachman:

This letter and exhibits are submitted on behalf of Sprint PCS (Sprint). Sprint is making modifications to certain existing sites in its Connecticut system in order to implement their 2.5GHz LTE technology. Please accept this letter and exhibits as notification, pursuant to § 16-50j-73 of the Regulations of Connecticut State Agencies (“R.C.S.A.”), of construction that constitutes an exempt modification pursuant to R.C.S.A. § 16-50j-72(b)(2). In compliance with R.C.S.A. § 16-50j-73, a copy of this letter is being sent to Mr. James Zeoli, First Selectman for Town of Orange. Town of Orange is also the Property Owner.

Sprint plans to modify the existing wireless communications facility owned by Crown Castle and located at **700 Grassy Hill Road, Orange, CT 06477**. Attached are a compound plan and elevation depicting the planned changes (Exhibit-1), and documentation of the structural sufficiency of the structure to accommodate the revised antenna configuration (Exhibit-2). Also included is a power density table report reflecting the modification to Sprint’s operations at the site (Exhibit-3).

The changes to the facility do not constitute a modification as defined in Connecticut General Statutes (“C.G.S.”) § 16-50i(d) because the general physical characteristics of the facility will not be significantly changed. Rather, the planned changes to the facility fall squarely within those activities explicitly provided for in the R.C.S.A. § 16-50j-72(b)(2).

1. The proposed modifications will not result in an increase in the height of the existing tower. Sprint’s additional antennas will be located at the same elevation on the existing tower.
2. There will be no proposed modifications to the ground and no extension of boundaries.
3. The proposed modifications will not increase noise levels at the facility by six decibels or more.

Melanie A. Bachman

August 29, 2014

Page 2

4. A Structural Modification Report confirming that the tower and foundation can support Sprint's proposed modifications is included as Exhibit-2.
5. The operation of the additional antennas will not increase radio frequency (RF) emissions at the facility to a level at or above the Federal Communications Commission (FCC) adopted safety standard. A cumulative General Power Density table report for Sprint's modified facility is included as Exhibit-3.

For the foregoing reasons, Sprint respectfully submits the proposed modifications to the above-reference telecommunications facility constitutes an exempt modification under R.C.S.A. § 16-50j-72(b)(2). Please send approval/rejection letter to Attn: Donna Neal.

Sincerely,



Jeff Barbadora  
Real Estate Specialist

Enclosures

Tab 1: Exhibit-1: Compound plan and elevation depicting the planned changes

Tab 2: Exhibit-2: Structural Modification Report

Tab 3: Exhibit-3: General Power Density Table Report (RF Emissions Analysis Report)

cc: Mr. James Zeoli, First Selectman  
Orange Town Hall  
617 Orange Center Road  
Orange, CT 06477



# 2.5 EQUIPMENT DEPLOYMENT

SITE NUMBER:  
CT23XC313

SITE NAME:

ORANGE/ROGERS PROPERTY

SITE ADDRESS:

700 GRASSY HILL ROAD  
ORANGE, CT 06477

CROWN ID#: 881541

CROWN SITE NAME: ROGERS PROPERTY



2.5 EQUIPMENT DEPLOYMENT  
6580 SPRINT PARKWAY  
OVERLAND PARK, KANSAS 66251



Tectonic Engineering & Surveying  
Consultants P.C.

1279 Route 300  
Newburgh, NY 12550  
Phone: (845) 567-6656  
Fax: (845) 567-8703  
www.tectonicengineering.com


**APPROVED**

By Jeff Barbadora at 8:21 am, Aug 18, 2014

## SHEET INFORMATION

SITE NUMBER:	CT23XC313	LANDLORD:	CROWN CASTLE USA 2000 CORPORATE DRIVE CANONSBURG, PA
SITE NAME:	ORANGE/ROGERS PROPERTY	LOCAL POWER COMPANY:	CONNECTICUT LIGHT AND POWER CONTACT CUSTOMER SERVICE (800) 286-2000
SITE ADDRESS:	700 GRASSY HILL ROAD ORANGE, CT 06477	APPLICANT:	SPRINT 6580 SPRINT PARKWAY OVERLAND PARK, KANSAS 66251
COUNTY:	NEW HAVEN	ENGINEER:	JAMES QUICKSELL (845) 567-6656 EXT. 2835 jquicksell@tectonicengineering.com
COORDINATES: (NAD 83)	41° 17' 07.75"N 73° 02' 33.27"W	SPRINT CM:	GARY WOOD (860) 940-9168 gary.wood@sprint.com
GROUND ELEV:	100'± AMSL	CROWN CM:	JASON D'AMICO (860) 209-0104 jason.d'amico@crowncastle.com
STRUCTURE TYPE:	MONOPOLE	AAV:	AT&T
STRUCTURE HEIGHT:	139'-6"± AGL		
STRUCTURE RAD CENTER:	130'-0"± AGL		
ZONING CLASSIFICATION:	R-1		
PARCEL ID:	60-6-1		

## VICINITY MAP (NOT TO SCALE)



## SHEET INDEX

SHT. NO.	SHEET DESCRIPTION
T-1	TITLE SHEET
SP-1	GENERAL NOTES
SP-2	GENERAL NOTES
A-1	SITE PLAN
A-2	ELEVATION
A-3	ENLARGED EQUIPMENT LAYOUT PLANS
A-4	ANTENNA LAYOUT PLANS
A-5	RAN WIRING DIAGRAM
A-6	CABLE DETAILS
S-1	EQUIPMENT DETAILS
S-2	EQUIPMENT SCHEMATIC DETAILS
E-1	ELECTRICAL & GROUNDING PLANS
E-2	GROUNDING DETAILS & NOTES

THIS DOCUMENT IS THE CREATION, DESIGN, PROPERTY AND COPYRIGHTED WORK OF SPRINT COMMUNICATIONS, INC. ANY DUPLICATION OR USE WITHOUT EXPRESS WRITTEN CONSENT IS STRICTLY PROHIBITED. DUPLICATION AND USE BY GOVERNMENT AGENCIES FOR THE PURPOSES OF CONDUCTING THEIR LAWFULLY AUTHORIZED REGULATORY AND ADMINISTRATIVE FUNCTIONS IS SPECIFICALLY ALLOWED.

## SUBMITTALS

NO	DATE	DESCRIPTION	BY
0	6/9/14	FOR COMMENT	BY
1	8/15/14	FOR CONSTRUCTION	MP

DATE	REVIEWED BY
8/15/14	JMO

## GENERAL NOTES

- THIS IS AN UNMANNED TELECOMMUNICATION FACILITY AND NOT FOR HUMAN HABITATION; HANDICAP ACCESS REQUIREMENTS ARE NOT REQUIRED. FACILITY HAS NO PLUMBING OR REFRIGERANTS. THIS FACILITY SHALL MEET OR EXCEED ALL FAA AND FCC REGULATOR REQUIREMENTS.
- CONTRACTOR SHALL VERIFY ALL PLANS AND EXISTING DIMENSIONS AND CONDITIONS ON THE JOB SITE AND SHALL IMMEDIATELY NOTIFY THE PROJECT OWNER'S REPRESENTATIVE IN WRITING OF DISCREPANCIES BEFORE PROCEEDING WITH THE WORK OR BE RESPONSIBLE FOR SAME.
- DEVELOPMENT AND USE OF THIS SITE WILL CONFORM TO ALL APPLICABLE CODES AND ORDINANCES.
  - BUILDING CODE OF CONNECTICUT, LATEST EDITION.
  - ANSI/TIA/EIA-222-F-1996.
  - NATIONAL ELECTRICAL CODE, LATEST EDITION.

## AERIAL VIEW (NOT TO SCALE)



## APPROVALS


THE FOLLOWING PARTIES HEREBY APPROVE AND ACCEPT THESE DOCUMENTS AND AUTHORIZE THE CONTRACTOR TO PROCEED WITH THE CONSTRUCTION DESCRIBED HEREIN. ALL DOCUMENTS ARE SUBJECT TO REVIEW BY THE LOCAL BUILDING DEPARTMENT AND MAY IMPOSE CHANGES OR MODIFICATIONS.

CONSTRUCTION: \_\_\_\_\_ DATE: \_\_\_\_\_

LEASING/  
SITE ACQUISITION: \_\_\_\_\_ DATE: \_\_\_\_\_

LANDLORD/  
PROPERTY OWNER: \_\_\_\_\_ DATE: \_\_\_\_\_

R.F. ENGINEER: \_\_\_\_\_ DATE: \_\_\_\_\_



## PROJECT DESCRIPTION

- (1) NEW ALU 9929 EXPANSION CABINET.
- (3) NEW RFS APXVTM14-C-120 ANTENNAS.
- (3) NEW TD-RRH6x20-25 RRH.
- (1) NEW 1-1/4" HYBRID CABLE.

SITE NUMBER:  
CT23XC313

SITE NAME:  
ORANGE/ROGERS PROPERTY

SITE ADDRESS:  
700 GRASSY HILL ROAD  
ORANGE, CT 06477

SHEET TITLE:  
TITLE SHEET

SHEET NO:  
T-1



**DIVISION 01000--GENERAL NOTES**

1. THE CONTRACTOR SHALL GIVE ALL NOTICES AND COMPLY WITH ALL LAWS, ORDINANCES, RULES, REGULATIONS AND LAWFUL ORDERS OF ANY PUBLIC AUTHORITY, MUNICIPAL AND UTILITY COMPANY SPECIFICATIONS, AND LOCAL AND STATE JURISDICTIONAL CODES BEARING ON THE PERFORMANCE OF THE WORK. THE WORK PERFORMED ON THE PROJECT AND THE MATERIALS INSTALLED SHALL BE IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS, AND ORDINANCES.
2. THE ARCHITECT/ENGINEER HAVE MADE EVERY EFFORT TO SET FORTH IN THE CONSTRUCTION AND CONTRACT DOCUMENTS THE COMPLETE SCOPE OF WORK. THE CONTRACTOR BIDDING THE JOB IS NEVERTHELESS CAUTIONED THAT MINOR OMISSIONS OR ERRORS IN THE DRAWINGS AND OR SPECIFICATIONS SHALL NOT EXCUSE SAID CONTRACTOR FROM COMPLETING THE PROJECT AND IMPROVEMENTS IN ACCORDANCE WITH THE INTENT OF THESE DOCUMENTS.
3. THE CONTRACTOR OR BIDDER SHALL BEAR THE RESPONSIBILITY OF NOTIFYING (IN WRITING) THE PROJECT OWNER'S REPRESENTATIVE OF ANY CONFLICTS, ERRORS, OR OMISSIONS PRIOR TO THE SUBMISSION OF CONTRACTOR'S PROPOSAL OR PERFORMANCE OF WORK.
4. THE SCOPE OF WORK SHALL INCLUDE FURNISHING ALL MATERIALS, EQUIPMENT, LABOR AND ALL OTHER MATERIALS AND LABOR DEEMED NECESSARY TO COMPLETE THE WORK/PROJECT AS DESCRIBED HEREIN.
5. THE CONTRACTOR SHALL VISIT THE JOB SITE PRIOR TO THE SUBMISSION OF BIDS OR PERFORMING WORK TO FAMILIARIZE HIMSELF WITH THE FIELD CONDITIONS AND TO VERIFY THAT THE PROJECT CAN BE CONSTRUCTED IN ACCORDANCE WITH THE CONTRACT DOCUMENTS.
6. ONCE THE CONTRACTOR HAS RECEIVED AND ACCEPTED THE NOTICE TO PROCEED, CONTRACTOR WILL CONTACT THE CROWN CASTLE CONSTRUCTION MANAGER OF RECORD (NOTED ON THE FIRST PAGE ON THIS CONSTRUCTION DRAWING) A MINIMUM OF 48 HOURS PRIOR TO WORK START. UPON ARRIVAL TO THE JOB SITE, CONTRACTOR CREW IS REQUIRED TO CALL 1-800-788-7011 TO NOTIFY THE CROWN CASTLE NOC WORK HAS BEGUN.
7. THE CONTRACTOR SHALL INSTALL ALL EQUIPMENT AND MATERIALS ACCORDING TO THE MANUFACTURER'S/VENDOR'S SPECIFICATIONS UNLESS NOTED OTHERWISE OR WHERE LOCAL CODES OR ORDINANCES TAKE PRECEDENCE.
8. THE CONTRACTOR SHALL PROVIDE A FULL SET OF CONSTRUCTION DOCUMENTS AT THE SITE UPDATED WITH THE LATEST REVISIONS AND ADDENDUMS OR CLARIFICATIONS AVAILABLE FOR THE USE BY ALL PERSONNEL INVOLVED WITH THE PROJECT.
9. THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE PROJECT DESCRIBED HEREIN. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR ALL CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES AND PROCEDURES AND FOR COORDINATING ALL PORTIONS OF THE WORK UNDER THE CONTRACT.
10. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL PERMITS AND INSPECTIONS WHICH MAY BE REQUIRED FOR THE WORK BY THE ARCHITECT/ENGINEER, THE STATE, COUNTY OR LOCAL GOVERNMENT AUTHORITY.
11. THE CONTRACTOR SHALL MAKE NECESSARY PROVISIONS TO PROTECT EXISTING IMPROVEMENTS, EASEMENTS, PAVING, CURBING, ETC. DURING CONSTRUCTION. UPON COMPLETION OF WORK, THE CONTRACTOR SHALL REPAIR ANY DAMAGE THAT MAY HAVE OCCURRED DUE TO CONSTRUCTION ON OR ABOUT THE PROPERTY.
12. THE CONTRACTOR SHALL KEEP THE GENERAL WORK AREA CLEAN AND HAZARD FREE DURING CONSTRUCTION AND DISPOSE OF ALL DIRT, DEBRIS, RUBBISH AND REMOVE EQUIPMENT NOT SPECIFIED AS REMAINING ON THE PROPERTY. PREMISES SHALL BE LEFT IN CLEAN CONDITION AND FREE FROM PAINT SPOTS, DUST, OR SMUDGES OF ANY NATURE.
13. THE CONTRACTOR SHALL COMPLY WITH ALL PERTINENT SECTIONS OF THE BASIC STATE BUILDING CODE, LATEST EDITION, AND ALL OSHA REQUIREMENTS AS THEY APPLY TO THIS PROJECT. ALL EXISTING ACTIVE SEWER, WATER, GAS, ELECTRIC, AND OTHER UTILITIES WHERE ENCOUNTERED IN THE WORK SHALL BE PROTECTED AT ALL TIMES, AND WHERE REQUIRED FOR THE PROPER EXECUTION OF THE WORK SHALL BE RELOCATED AS DIRECTED BY THE ARCHITECT/ENGINEER. EXTREME CAUTION SHOULD BE USED BY THE CONTRACTOR WHEN EXCAVATING OR PIER DRILLING AROUND OR NEAR UTILITIES. THE CONTRACTOR SHALL PROVIDE SAFETY TRAINING FOR THE WORKING CREW. THIS WILL INCLUDE BUT NOT LIMITED TO A) FALL PROTECTION, B) CONFINED SPACE, C) ELECTRICAL SAFETY, D) TRENCHING AND EXCAVATION OF ALL EXISTING INACTIVE SEWER, WATER, GAS, ELECTRIC AND OTHER UTILITIES WHICH INTERFERE WITH THE EXECUTION OF THE WORK SHALL BE REMOVED AND OR CAPPED, PLUGGED OR OTHERWISE DISCONTINUED AT THE POINTS WHICH WILL NOT INTERFERE WITH THE EXECUTION OF THE WORK SUBJECT TO THE APPROVAL OF THE ARCHITECT/ENGINEER.
14. THE CONTRACTOR SHALL NOTIFY THE PROJECT OWNER'S REPRESENTATIVE IN WRITING WHERE A CONFLICT OCCURS ON ANY OF THE CONTRACT DOCUMENTS. THE CONTRACTOR IS NOT TO ORDER MATERIAL OR CONSTRUCT ANY PORTION OF THE WORK THAT IS IN CONFLICT UNTIL CONFLICT IS RESOLVED BY THE LESSEE/LICENSEE REPRESENTATIVE.
15. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS, ELEVATIONS, PROPERTY LINES, ETC. ON THE JOB.
16. THE CONTRACTOR SHALL NOTIFY THE THE RF ENGINEER FOR ANTENNA AZIMUTH VERIFICATION (DURING ANTENNA INSTALLATION) PRIOR TO CONDUCTING SWEEP TESTS.
17. THE CONTRACTOR SHALL SUBMIT AT THE END OF THE PROJECT A COMPLETE SET OF AS-BUILT DRAWINGS TO THE CLIENT REPRESENTATIVE.
18. REFER TO: CONSTRUCTION STANDARDS--SPRINT DOCUMENT EXHIBIT A--STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES REV. 4.0-- 02.15.2011.DOCM.
19. REFER TO: WEATHER PROOFING SPECS: EXCERPT EXH A--WIHRPRF--STD CONSTR SPECS...157201110421855492.DOCM.
20. REFER TO: COLOR CODING--SPRINT NEXTEL ANT AND LINE COLOR CODING (DRAFT) V3 09--08--11.PDF
21. REFER TO LATEST DOCUMENTATION REVISION.

**DIVISION 03000--CONCRETE**

- 1.03 APPLICABLE STANDARDS (USE LATEST EDITIONS)
- A. ACI-301 -- SPECIFICATIONS FOR STRUCTURAL CONCRETE FOR BUILDINGS.
  - B. ACI-347 GUIDE TO FORM WORK FOR CONCRETE.
  - C. ASTM C33-- CONCRETE AGGREGATE
  - D. ASTM C94 -- READY MIXED CONCRETE e. ASTM C150 -- PORTLAND CEMENT.
  - E. ASTM C260 -- AIR-ENTRAINING ADMIXTURES FOR CONCRETE
  - F. ASTM C309-- LIQUID MEMBRANE FORMING COMPOUNDS FOR CURING CONCRETE.
  - H. ASTM C494 -- CHEMICAL ADMIXTURES FOR CONCRETE
  - I. ASTM A615-- DEFORMED AND PLAIN BILLET--STEEL BARS FOR CONCRETE REINFORCEMENT
  - J. ASTM A185-- STEEL WELDED WIRE FABRIC (PLAIN) FOR CONCRETE REINFORCEMENT
- 1.04 QUALITY ASSURANCE
- CONCRETE MATERIALS AND OPERATIONS SHALL BE TESTED AND INSPECTED BY THE ARCHITECT/ENGINEER AS DIRECTED BY THE CLIENT'S REPRESENTATIVE.
- 3.04 SURFACE FINISHES
- A. SURFACES AGAINST WHICH BACKFILL OR CONCRETE SHALL BE PLACED REQUIRE NO TREATMENT EXCEPT REPAIR OF DEFECTIVE AREAS.
  - B. SURFACES THAT WILL BE PERMANENTLY EXPOSED SHALL PRESENT A UNIFORM FINISH PROVIDED BY THE REMOVAL OF FINIS AND THE FILLING HOLES AND OTHER IRREGULARITIES WITH DRY PACK GROUT, OR BY SACKING WITH UTILITY OR ORDINARY GROUT.
  - C. SURFACES THAT WOULD NORMALLY BE LEVEL AND WHICH WILL BE PERMANENTLY EXPOSED TO THE WEATHER SHALL BE SLOPED FOR DRAINAGE. UNLESS ENGINEER'S DESIGN DRAWING SPECIFIES A HORIZONTAL SURFACE OR SURFACES SUCH AS STAIR TREADS, WALLS, CURBS, AND PARAPETS SHALL BE SLOPED APPROXIMATELY 1/4" PER FOOT.
  - D. SURFACES THAT WILL BE COVERED BY BACKFILL OR CONCRETE SHALL BE SMOOTH SCREENED.
  - E. EXPOSED SLAB SURFACES SHALL BE CONSOLIDATED, SCREENED, FLOATED, AND STEEL TROWELED. HAND OR POWER-DRIVEN EQUIPMENT MAY BE USED FOR FLOATING. FLOATING SHALL BE STARTED AS SOON AS THE SCREENED SURFACE HAS ATTAINED A STIFFNESS TO PERMIT FINISHING OPERATIONS. OPERATIONS. ALL EDGES MUST HAVE A 3/4" CHAMFER.
- 1.04 QUALITY ASSURANCE CONCRETE MATERIALS AND OPERATIONS SHALL BE TESTED AND INSPECTED BY THE ENGINEER.
- 3.05 PATCHING
- THE CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY UPON REMOVAL OF THE FORMS TO OBSERVE CONCRETE SURFACE CONDITIONS. IMPERFECTIONS SHALL BE PATCHED ACCORDING TO THE ENGINEER'S DIRECTION.
- 3.06 DEFECTIVE CONCRETE
- THE CONTRACTOR SHALL NOTIFY OR REPLACE CONCRETE NOT CONFORMING TO REQUIRED LEVELS AND LINES, DETAILS, AND ELEVATIONS AS SPECIFIED IN ACI 301.
- 3.07 PROTECTION
- A. IMMEDIATELY AFTER PLACEMENT, THE CONTRACTOR SHALL PROTECT THE CONCRETE FROM PREMATURE DRYING, EXCESSIVELY HOT OR COLD TEMPERATURES, AND MECHANICAL INJURY. FINISHED WORK SHALL BE PROTECTED.
  - B. CONCRETE SHALL BE MAINTAINED WITH MINIMAL MOISTURE LOSS AT RELATIVELY CONSTANT TEMPERATURE FOR PERIOD NECESSARY FOR HYDRATION OF CEMENT AND HARDENING OF CONCRETE.
  - C. ALL CONCRETE SHALL BE WATER CURED PER ACCEPTABLE PRACTICES SPECIFIED BY ACI CODE (LATEST EDITION)

**DIVISION 05000 -- METALS**

- PART 1 -- GENERAL
- 1.01 WORK INCLUDED
- A. THE WORK CONSISTS OF THE FABRICATION AND INSTALLATION OF ALL MATERIALS TO BE FURNISHED, AND WITHOUT LIMITING THE GENERALITY THEREOF, INCLUDING ALL EQUIPMENT, LABOR AND SERVICES REQUIRED FOR ALL STRUCTURAL STEEL WORK AND ALL ITEMS INCIDENTAL AS SPECIFIED AND AS SHOWN ON THE DRAWINGS:
1. STEEL FRAMING INCLUDING BEAMS, ANGLES, CHANNELS AND PLATES. WELDING AND BOLTING OF ATTACHMENTS.
- 1.02 REFERENCE STANDARDS
- A. THE WORK SHALL CONFORM TO THE CODES AND STANDARDS OF THE FOLLOWING AGENCIES AS FURTHER CITED HEREIN:
1. ASTM: AMERICAN SOCIETY FOR TESTING AND MATERIALS AS PUBLISHED IN "COMPILATION OF ASTM STANDARDS IN BUILDING CODES" OR LATEST EDITION.
  2. AWS: AMERICAN WELDING SOCIETY CODE OR LATEST EDITION.
  3. AISC: AMERICAN INSTITUTE OF STEEL CONSTRUCTION, "SPECIFICATION FOR THE DESIGN, FABRICATION AND ERECTION OF STRUCTURAL STEEL FOR BUILDINGS" (LATEST EDITION).
- PART 2 -- PRODUCTS
- 2.01 MATERIALS
- A. STRUCTURAL STEEL: SHALL COMPLY WITH THE REQUIREMENTS OF ASTM A36 AND A992 FOR STRUCTURAL STEEL.
- ALL PROPOSED STRUCTURAL STEEL SHALL BE FABRICATED AND ERECTED IN ACCORDANCE WITH AISC CODE AND ASTM SPECIFICATIONS (LATEST EDITION) ALL NEW STEEL SHALL CONFORM TO THE FOLLOWING.
1. STRUCTURAL WIDE FLANGE: ASTM A992 Fy=50KSI.
  2. MISCELLANEOUS STEEL (PLATES), CHANNELS, ANGLES, ETC): ASTM A36 (Fy=36KSI).
  3. STRUCTURAL TUBING: ASTM A500 Gr. B (Fy=46KSI).
  4. STEEL PIPE: ASTM A53 Gr B (Fy=35KSI).
- 2.02 WELDING
- A. ALL WELDING SHALL BE DONE BY CERTIFIED WELDERS. CERTIFICATION DOCUMENTS SHALL BE MADE AVAILABLE FOR ENGINEER'S AND/OR OWNER'S REVIEW IF REQUESTED.
  - B. WELDING ELECTRODES FOR MANUAL SHIELDED METAL ARC WELDING SHALL CONFORM TO ASTM 1-233, E70 SERIES. BARE ELECTRODES AND GRANULAR FLUX USED IN THE SUBMERGED ARC PROCESS SHALL CONFORM TO AISC SPECIFICATIONS.
  - C. FIELD WELDING SHALL BE DONE AS PER AWS D1.1 REQUIREMENTS VISUAL INSPECTION IS ACCEPTABLE.
  - D. STUD WELDING SHALL BE ACCOMPLISHED BY CAPACITOR DISCHARGE (CD) WELDING TECHNIQUE USING CAPACITOR DISCHARGE STUD WELDER.
  - E. PROVIDE STUD FASTENERS OF MATERIALS AND SIZES SHOWN ON DRAWINGS OR AS RECOMMENDED BY THE MANUFACTURER FOR STRUCTURAL LOADINGS REQUIRED.
  - F. FOLLOW MANUFACTURERS SPECIFICATIONS AND INSTRUCTIONS TO PROPERLY SELECT AND INSTALL STUD WELDS.
- 2.03 BOLTING
- A. BOLTS SHALL BE CONFORMING TO ASTM A35 HIGH STRENGTH HOT DIP GALVANIZED WITH ASTM A153 HEAVY HEX TYPE NUTS.
  - B. BOLTS SHALL BE 3/4" (MINIMUM) CONFORMING TO ASTM A325, HOT DIP GALVANIZED, ASTM A153 NUTS SHALL BE HEAVY HEX TYPE.
  - C. ALL CONNECTIONS SHALL BE 2 BOLTS MINIMUM.
  - D. EXCEPT WHERE SHOWN, ALL BEAM TO BEAM AND BEAM TO COLUMN CONNECTIONS TO BE DOUBLE ANGLED CONNECTIONS WITH HIGH STRENGTH BOLTS (THREADS EXCLUDED FROM SHEAR PLANE) AND HARDENED WASHERS.
  - E. STANDARD, OVERSIZED OR HORIZONTAL SHORT SLOTTED HOLES.
  - F. SNUG-TIGHT STRENGTH BEARING BOLTS MAY BE USED IN STANDARD HOLES CONFORMING TO ACIS, USING THE TURN OF THE NUT METHOD.
  - H. FULLY-TENSIONED HIGH STRENGTH (SLIP CRITICAL) SHALL BE USED IN OVERSIZED SLOT HOLES (RESPECTIVE OF SLOT ORIENTATION).
  - I. ALL BRACED CONNECTION, MOMENT CONNECTION AND CONNECTIONS NOTED AS "SLIP CRITICAL" SHALL BE BE SLIP CRITICAL JOINTS WITH CLASS A SURFACE CONDITIONS, UNLESS OTHERWISE NOTED.
  - J. EPOXY ANCHOR ASSEMBLIES SHALL BE AS MANUFACTURED BY HILTI OR ENGINEER APPROVED EQUAL, AS FOLLOWS:
- | BASE MATERIAL                 | ANCHOR SYSTEM    |
|-------------------------------|------------------|
| CONCRETE                      | HILTI HIT-HY 200 |
| HOLLOW & GROUTED CMU OR BRICK | HILTI HIT-HY 70  |
- 2.04 FABRICATION
- A. FABRICATION OF STEEL SHALL CONFORM TO THE AISC AND AWS

- 2.05 FINISH
- A. STRUCTURAL STEEL EXPOSED TO WEATHER SHALL BE HOT-DIP GALVANIZED AFTER FABRICATION IN ACCORDANCE WITH ASTM A123. (LATEST EDITION) UNLESS OTHERWISE NOTED.
- 2.06 PROTECTION
- A. UPON COMPLETION OF ERECTION, INSPECT ALL GALVANIZED STEEL AND PAINT ANY FIELD CUTS, WELDS OR GALVANIZED BREAKS WITH (2) COATS OF ZINC-RICH COLD GALVANIZING PAINT.
- PART 3 -- ERECTION
- A. PROVIDE ALL ERECTION, EQUIPMENT, BRACING, PLANKING, FIELD BOLTS, NUTS, WASHERS, DRIFT PINS, AND SIMILAR MATERIALS WHICH DO NOT FORM A PART OF THE COMPLETED CONSTRUCTION, BUT ARE NECESSARY FOR ITS PROPER ERECTION.
  - B. ERECT AND ANCHOR ALL STRUCTURAL STEEL IN ACCORDANCE WITH AISC REFERENCE STANDARDS. ALL WORK SHALL BE ACCURATELY SET TO ESTABLISHED SUITABLE ATTACHMENTS TO THE CONSTRUCTION OF THE BUILDING
  - C. TEMPORARY BRACING, GUYING, AND SUPPORT SHALL BE PROVIDED TO KEEP THE STRUCTURE SET AND ALIGNED AT ALL TIMES DURING CONSTRUCTION, AND TO PREVENT DANGER TO PERSONS AND PROPERTY. CHECK ALL TEMPORARY LOADS AND STAY WITHIN SAFE CAPACITY OF ALL BUILDING COMPONENTS.



**TECTONIC** ENGINEERING & SURVEYING CONSULTANTS P.C.


1279 Route 300  
Newburgh, NY 12550  
Phone: (845) 567-6656  
Fax: (845) 567-8703  
www.tectonicengineering.com

THIS DOCUMENT IS THE CREATION, DESIGN, PROPERTY AND COPYRIGHTED WORK OF SPRINT COMMUNICATIONS, INC. ANY DUPLICATION OR USE WITHOUT EXPRESS WRITTEN CONSENT IS STRICTLY PROHIBITED. DUPLICATION AND USE BY GOVERNMENT AGENCIES FOR THE PURPOSES OF CONDUCTING THEIR LAWFULLY AUTHORIZED REGULATORY AND ADMINISTRATIVE FUNCTIONS IS SPECIFICALLY ALLOWED.

**SUBMITTALS**

PROJECT NO: 7225.CT23XC313			
NO	DATE	DESCRIPTION	BY
0	6/9/14	FOR COMMENT	BY
1	8/15/14	FOR CONSTRUCTION	MP

DATE	REVIEWED BY
8/15/14	JMG



SITE NUMBER:  
**CT23XC313**

SITE NAME:  
**ORANGE/ROGERS PROPERTY**

SITE ADDRESS:  
**700 GRASSY HILL ROAD  
ORANGE, CT 06477**

SHEET TITLE:  
**GENERAL NOTES**

SHEET NO:  
**SP-1**

DIVISION 13000—SPECIAL CONSTRUCTION ANTENNA INSTALLATION

PART 1 — GENERAL

1.01 WORK INCLUDED

A. ANTENNAS AND HYBRIFLEX CABLES ARE FURNISHED BY CLIENT'S REPRESENTATIVE UNDER SEPARATE CONTRACT. THE CONTRACTOR SHALL ASSIST ANTENNA INSTALLATION CONTRACTOR IN TERMS OF COORDINATION AND SITE ACCESS. ERECTION SUBCONTRACTOR SHALL BE RESPONSIBLE FOR THE PROPERTY.

B. INSTALL ANTENNAS AS INDICATED ON DRAWINGS AND CLIENT'S REPRESENTATIVE SPECIFICATIONS.

C. INSTALL GALVANIZED STEEL ANTENNA MOUNTS AS INDICATED ON DRAWINGS.

D. INSTALL FURNISHED GALVANIZED STEEL OR ALUMINUM WAVEGUIDE AND PROVIDE PRINTOUT OF THAT RESULT

F. INSTALL HYBRIFLEX CABLES AND TERMINATIONS BETWEEN ANTENNAS AND EQUIPMENT PER MANUFACTURER'S RECOMMENDATIONS. WEATHERPROOF ALL CONNECTORS BETWEEN THE ANTENNA AND EQUIPMENT PER MANUFACTURER'S REQUIREMENTS.

G. ANTENNA AND HYBRIFLEX CABLE GROUNDING:

1. ALL EXTERIOR #6 GREEN GROUND WIRE DAISY CHAIN CONNECTIONS ARE TO BE WEATHER SEALED WITH ANDREWS CONNECTOR/SPLICE WEATHERPROOFING KIT TYPE 3221213 OR EQUIVALENT.

2. ALL HYBRIFLEX CABLE GROUNDING KITS ARE TO BE INSTALLED ON STRAIGHT RUNS OF HYBRIFLEX CABLE (NOT WITHIN BENDS). 1.02 RELATED WORK FURNISH THE FOLLOWING WORK AS SPECIFIED UNDER CONSTRUCTION DOCUMENTS, BUT COORDINATE WITH QOTHER TRADES PRIOR TO BID:

1. FLASHING OF OPENING INTO OUTSIDE WALLS.
2. SEALING AND CAULKING ALL OPENINGS.
3. PAINTING.
4. CUTTING AND PATCHING.

1.03 REQUIREMENTS OF REGULATOR AGENCIES

A. FURNISH U.L. LISTED EQUIPMENT WHERE SUCH LABEL IS AVAILABLE. INSTALL IN CONFORMANCE WITH U.L. STANDARDS WHERE APPLICABLE.

B. INSTALL ANTENNA, ANTENNA CABLES, GROUNDING SYSTEM IN ACCORDANCE WITH DRAWINGS AND SPECIFICATIONS IN EFFECT AT PROJECT LOCATION AND RECOMMENDATIONS OF STATE AND LOCAL BUILDING CODES HAVING JURISDICTION OVER SPECIFIC PORTIONS OF WORK. THIS WORK INCLUDES, BUT IS NOT LIMITED TO THE FOLLOWING:

1. EIA — ELECTRONIC INDUSTRIES ASSOCIATION RS-22. STRUCTURAL STANDARDS FOR STEEL ANTENNA TOWERS AND ANTENNA SUPPORTING STRUCTURES.
2. FAA — FEDERAL AVIATION ADMINISTRATION ADVISORY CIRCULAR AC 70/7480-IH, CONSTRUCTION MARKING AND LIGHTING.
3. FCC — FEDERAL COMMUNICATION COMMISSION RULES AND REGULATIONS FORM 715, OBSTRUCTION MARKING AND LIGHTING SPECIFICATION FOR ANTENNA STRUCTURES
4. AISC — AMERICAN INSTITUTE OF STEEL CONSTRUCTION FOR STRUCTURAL JOINTS USING ASTM 1325 OR A490 BOLTS.
5. NEC — NATIONAL ELECTRIC CODE — ON TOWER LIGHTING KITS.
6. UL — UNDERWRITER'S LABORATORIES APPROVED ELECTRICAL PRODUCTS.
7. IN ALL CASES, PART 77 OF THE FAA RULES AND PARTS 17 AND 22 OF THE FCC RULES ARE APPLICABLE AND IN THE EVENT OF CONFLICT, SUPERSEDE ANY OTHER STANDARDS OR SPECIFICATIONS.
8. LIFE SAFETY CODE NFPA, LATEST EDITION.

DIVISION 13000—EARTHWORK

PART 1 GENERAL

1.01 WORK INCLUDED: REFER TO SURVEY AND SITE PLAN FOR WORK INCLUDED.

1.02 RELATED WORK

A. CONSTRUCTION OF EQUIPMENT FOUNDATIONS  
B. INSTALLATION OF ANTENNA SYSTEM

PART 2 PRODUCTS

2.01 MATERIALS

A. ROAD AND SITE MATERIALS; FILL MATERIAL SHALL BE ACCEPTABLE, SELECT FILL SHALL BE IN ACCORDANCE WITH LOCAL DEPARTMENT OF HIGHWAY AND PUBLIC TRANSPORTATION STANDARD SPECIFICATIONS.

B. SOIL STERILIZER SHALL BE EPA REGISTERED OF LIQUID COMPOSITION AND OF PRE-EMERGENCE DESIGN.

C. SOIL STABILIZER FABRIC SHALL BE MIRAFI OR EQUAL — 600X AT ACCESS ROAD AND COMPOUND.

D. GRAVEL FILL; WELL GRADED, HARD, DURABLE, NATURAL SAND AND GRAVEL, FREE FROM ICE AND SNOW, ROOTS, SOD RUBBISH, AND OTHER DELETERIOUS OR ORGANIC MATTER.

MATERIAL SHALL CONFORM TO THE FOLLOWING GRADATION REQUIREMENTS.

GRAVEL FILL TO BE PLACED IN LIFTS OF 9" MAXIMUM THICKNESS AND 90 % DENSITY. COMPACTED TO 95

E. NO FILL OR EMBANKMENT MATERIALS SHALL BE PLACED ON FROZEN GROUND. FROZEN MATERIALS SNOW OR ICE SHALL NOT BE PLACED IN ANY FILL OF EMBANKMENT

2.02 EQUIPMENT

A. COMPACTION SHALL BE ACCOMPLISHED BY MECHANICAL MEANS. LARGER AREAS SHALL BE COMPACTED BY SHEEPS FOOT, VIBRATORY OR RUBBER TIED ROLLERS WEIGHING AT LEAST FIVE TONS. SMALLER AREAS SHALL BE COMPACTED BY POWER-DRIVER, HAND HELD TAMPERS.

B. PRIOR TO OTHER EXCAVATION AND CONSTRUCTION EFFORTS GRUB ORGANIC MATERIAL TO A MINIMUM OF 6" BELOW ORIGINAL GROUND LEVEL.

C. UNLESS OTHERWISE INSTRUCTED BY CLIENT'S REPRESENTATIVE. REMOVE TREES, BRUSH AND DEBRIS FROM THE PROPERTY TO AN AUTHORIZED DISPOSAL LOCATION.

D. PRIOR TO PLACEMENT OF FILL OR BASE MATERIALS, ROLL THE SOIL.

E. WHERE UNSTABLE SOIL CONDITIONS ARE ENCOUNTERED, LINE THE GRUBBED AREAS WITH STABILIZER MAT PRIOR TO PLACEMENT OF FILL OR BASE MATERIAL.

3.03 INSTALLATION

A. THE SITE AND TURNAROUND AREAS SHALL BE AT THE SUB-BASE COURSE ELEVATION PRIOR TO FORMING FOUNDATIONS. GRADE OR FILL THE SITE AND ACCESS ROAD AS REQUIRED TO PRODUCE EVEN DISTRIBUTION OF SPOILS RESULTING FROM FOUNDATION EXCAVATIONS. THE RESULTING GRADE SHALL CORRESPOND WITH SAID SUB-BASE COURSE, ELEVATIONS ARE TO BE CALCULATED FROM FINISHED GRADES OR SLOPES INDICATED.

B. THE ACCESS ROAD SHALL BE BROUGHT TO BASE COURSE ELEVATION PRIOR TO FOUNDATION CONSTRUCTION.

C. DO NOT CREATE DEPRESSIONS WHERE WATER MAY POND.

D. THE CONTRACT INCLUDES ALL NECESSARY GRADING, BANKING, DITCHING AND COMPLETE SURFACE COURSE FOR ACCESS ROAD. ALL ROADS OR ROUTES UTILIZED FOR ACCESS TO PUBLIC THOROUGHFARE IS INCLUDED IN SCOPE OF WORK UNLESS OTHERWISE INDICATED.

E. WHEN IMPROVING AN EXISTING ACCESS ROAD, GRADE THE EXISTING ROAD TO REMOVE ANY ORGANIC MATTER AND SMOOTH THE SURFACE BEFORE PLACING FILL OR STONE.

F. PLACE FILL OR STONE IN 3" MAXIMUM LIFTS AND COMPACT BEFORE PLACING NEXT LIFT.

G. THE FINISH GRADE, INCLUDING TOP SURFACE COURSE, SHALL EXTEND A MINIMUM OF 12" BEYOND THE SITE FENCE AND SHALL COVER THE AREA AS INDICATED.

H. RIPRAP SHALL BE APPLIED TO THE SIDE SLOPES OF ALL FENCED AREAS, PARKING AREAS AND TO ALL OTHER SLOPES GREATER THAN

2:1. RIPRAP SHALL BE APPLIED TO THE SIDES OF DITCHES OR DRAINAGE SWALES AS INDICATED ON PLANS.

J. RIPRAP ENTIRE DITCH FOR 6'-0" IN ALL DIRECTIONS AT CULVERT OPENINGS.

K. SEED, FERTILIZER AND STRAW COVER SHALL BE APPLIED TO ALL OTHER DISTURBED AREAS AND DITCHES, DRAINAGE, SWALES, NOT OTHERWISE RIP-RAPPED.

L. UNDER NO CIRCUMSTANCES SHALL DITCHES, SWALES OR CULVERTS BE PLACED SO THEY DIRECT WATER TOWARDS, OR PERMIT STANDING WATER IMMEDIATELY ADJACENT TO SITE. IF OWNER DESIGNS OR IF DESIGN ELEVATIONS CONFLICT WITH THIS GUIDANCE ADVISE THE OWNER IMMEDIATELY.

M. IF A DITCH LIES WITH SLOPE GREATER THAN TEN PERCENT, MOUND DIVERSIONARY HEADWALL IN THE DITCH AT CULVERT ENTRANCES. RIP-RAP THE UPSTREAM SIDE OF THE HEADWALL AS WELL AS THE DITCH FOR 6'-0" ABOVE THE CULVERT.

N. IF A DITCH LIES WITH SLOPES GREATER THAN TEN PERCENT, MOUND DIVERSIONARY HEADWALLS IN THE DITCH FOR 6'-0" ABOVE THE CULVERT ENTRANCE.

O. SEED AND FERTILIZER SHALL BE APPLIED TO SURFACE CONDITIONS WHICH WILL ENCOURAGE ROOTING. RAKE AREAS TO BE SEEDED TO EVEN THE SURFACE AND TO LOOSEN THE SOIL.

P. SOW SEED IN TWO DIRECTIONS IN TWICE THE QUANTITY RECOMMENDED BY THE SEED PRODUCER.

Q. IT IS THE CONTRACTOR'S RESPONSIBILITY TO ENSURE GROWTH OF SEEDED AND LANDSCAPED AREAS BY WATERING UP TO THE POINT OF RELEASE FROM THE CONTRACT. CONTINUE TO REWORK BARE AREAS UNTIL COMPLETE COVERAGE IS OBTAINED.

3.04 FIELD QUALITY CONTROL

A. COMPACTION SHALL BE D-1557 FOR SITE WORK AND 95 % MAXIMUM DENSITY UNDER SLAB AREAS. AREAS OF SETTLEMENT WILL BE EXCAVATED AND REFILLED AT CONTRACTOR'S EXPENSE. REQUIRED. USE OF EROSION CONTROL MESH OR MULCH NET SHALL BE AN ACCEPTABLE ALTERNATIVE.

B. THE COMPACTION TEST RESULTS SHALL BE AVAILABLE PRIOR TO THE CONCRETE POUR.

3.05 PROTECTION

A. PROTECT SEEDED AREAS FORM EROSION BY SPREADING STRAW TO A UNIFORM LOOSE DEPTH OF 1"-2". STAKE AND TIE DOWN AS REQUIRED. USE OF EROSION CONTROL MESH OR MULCH NET SHALL BE AN ACCEPTABLE ALTERNATIVE.

B. ALL TREES PLACED IN CONJUNCTION WITH A LANDSCAPE CONTRACT SHALL BE WRAPPED, TIED WITH HOSE PROTECTED WIRE AND SECURED TO STAKES EXTENDING 2'-0" INTO THE GROUND ON FOUR SIDES OF THE TREE.

C. ALL EXPOSED AREAS SHALL BE PROTECTED AGAINST WASHOUTS AND SOIL EROSION. STRAW BALES SHALL BE PLACED AT THE INLET APPROACH TO ALL NEW OR EXISTING CULVERTS. REFER TO DETAILS ON DRAWINGS

SYMBOLS	ABBREVIATIONS
— — — — G — — — — G — —	GROUND WIRE
— — — — E — — — — E — —	ELECTRIC
— — — — T — — — — T — —	TELEPHONE
— — — — O — — — — O — —	OVERHEAD WIRE
— — — — — — — — — —	PROPERTY LINE
— X — — — X — — — X — —	CHAIN LINK FENCE
A-1	ANTENNA MARK
(E)	EXISTING
(P)	PROPOSED DETAIL
	REFERENCE
	SURFACE ELEVATION

2.5 EQUIPMENT DEPLOYMENT  
6580 SPRINT PARKWAY  
OVERLAND PARK, KANSAS 66251

TECTONIC Engineering & Surveying Consultants P.C.  
1279 Route 300  
Newburgh, NY 12550  
Phone: (845) 567-6656  
Fax: (845) 567-8703  
www.tectonicengineering.com

THIS DOCUMENT IS THE CREATION, DESIGN, PROPERTY AND COPYRIGHTED WORK OF SPRINT COMMUNICATIONS, INC. ANY DUPLICATION OR USE WITHOUT EXPRESS WRITTEN CONSENT IS STRICTLY PROHIBITED. DUPLICATION AND USE BY GOVERNMENT AGENCIES FOR THE PURPOSES OF CONDUCTING THEIR LAWFULLY AUTHORIZED REGULATORY AND ADMINISTRATIVE FUNCTIONS IS SPECIFICALLY ALLOWED.

SUBMITTALS

PROJECT NO: 7225.CT23XC313

NO	DATE	DESCRIPTION	BY
0	6/9/14	FOR COMMENT	BY
1	8/15/14	FOR CONSTRUCTION	MP




DATE	REVIEWED BY
8/15/14	JMG

SITE NUMBER:  
CT23XC313  
SITE NAME:  
ORANGE/ROGERS PROPERTY  
SITE ADDRESS:  
700 GRASSY HILL ROAD  
ORANGE, CT 06477

SHEET TITLE:  
GENERAL NOTES

SHEET NO:  
SP-2

NORTH NOTE:  
 NORTH SHOWN HAS BEEN  
 ESTABLISHED USING THE USGS  
 QUADRANGLE 7.5 MINUTE MAPS  
 AND IS APPROXIMATE. VERIFY  
 TRUE NORTH PRIOR TO  
 INSTALLATION OF ANTENNAS.



1  
 A-1  
**SITE PLAN**  
 SCALE: 3/8" = 1'-0"

**Sprint**  
 2.5 EQUIPMENT DEPLOYMENT  
 6580 SPRINT PARKWAY  
 OVERLAND PARK, KANSAS 66251

**CROWN CASTLE**

**TECTONIC**  
 PLANNING  
 ENGINEERING  
 SURVEYING  
 CONSTRUCTION MANAGEMENT  
**TECTONIC** Engineering & Surveying  
 Consultants P.C.  
 1279 Route 300  
 Newburgh, NY 12550  
 Phone: (845) 567-6656  
 Fax: (845) 567-8703  
 www.tectoniceengineering.com


THIS DOCUMENT IS THE CREATION, DESIGN, PROPERTY AND COPYRIGHTED WORK OF SPRINT COMMUNICATIONS, INC. ANY DUPLICATION OR USE WITHOUT EXPRESS WRITTEN CONSENT IS STRICTLY PROHIBITED. DUPLICATION AND USE BY GOVERNMENT AGENCIES FOR THE PURPOSES OF CONDUCTING THEIR LAWFULLY AUTHORIZED REGULATORY AND ADMINISTRATIVE FUNCTIONS IS SPECIFICALLY ALLOWED.

**SUBMITTALS**

PROJECT NO: 7225.CT23XC313

NO	DATE	DESCRIPTION	BY
0	6/9/14	FOR COMMENT	BY
1	8/15/14	FOR CONSTRUCTION	MP


DATE: 8/15/14  
 REVIEWED BY: JMG



SITE NUMBER:  
 CT23XC313  
 SITE NAME:  
 ORANGE/ROGERS PROPERTY  
 SITE ADDRESS:  
 700 GRASSY HILL ROAD  
 ORANGE, CT 06477

SHEET TITLE:  
 SITE PLAN


SHEET NO:  
 A-1



1 SITE PLAN  
 A-2 SCALE: 3/16" = 1'-0"

THE EXISTING MOUNT HAS BEEN ANALYZED BY TECTONIC ENGINEERING AND FOUND TO BE ADEQUATE TO SUPPORT THE PROPOSED SPRINT UPGRADE AS DETAILED IN THE STRUCTURAL ANALYSIS EVALUATION LETTER DATED 7/28/14.

THE EXISTING MONOPOLE SHALL BE ANALYZED BY A PROFESSIONAL ENGINEER LICENSED IN THE STATE OF CONNECTICUT (TO BE COORDINATED BY OTHERS).



**Sprint**  
 2.5 EQUIPMENT DEPLOYMENT  
 6580 SPRINT PARKWAY  
 OVERLAND PARK, KANSAS 66251

**CROWN CASTLE**

**TECTONIC**  
 PLANNING  
 ENGINEERING  
 SURVEYING  
 CONSTRUCTION MANAGEMENT  
**TECTONIC Engineering & Surveying Consultants P.C.**  
 1279 Route 300  
 Newburgh, NY 12550  
 Phone: (845) 567-6656  
 Fax: (845) 567-8703  
 www.tectonicengineering.com

THIS DOCUMENT IS THE CREATION, DESIGN, PROPERTY AND COPYRIGHTED WORK OF SPRINT COMMUNICATIONS, INC. ANY DUPLICATION OR USE WITHOUT EXPRESS WRITTEN CONSENT IS STRICTLY PROHIBITED. DUPLICATION AND USE BY GOVERNMENT AGENCIES FOR THE PURPOSES OF CONDUCTING THEIR LAWFULLY AUTHORIZED REGULATORY AND ADMINISTRATIVE FUNCTIONS IS SPECIFICALLY ALLOWED.

**SUBMITTALS**

PROJECT NO: 7225.CT23XC313

NO	DATE	DESCRIPTION	BY
0	6/9/14	FOR COMMENT	BY
1	8/15/14	FOR CONSTRUCTION	MP

DATE: 8/15/14  
 REVIEWED BY: JMQ



SEAL  
 STATE OF CONNECTICUT  
 PROFESSIONAL ENGINEER  
 No. 22033

SITE NUMBER:  
 CT23XC313  
 SITE NAME:  
 ORANGE/ROGERS PROPERTY  
 SITE ADDRESS:  
 700 GRASSY HILL ROAD  
 ORANGE, CT 06477

SHEET TITLE:  
 ELEVATION

SHEET NO:  
 A-2


**NORTH NOTE:**  
 NORTH SHOWN HAS BEEN ESTABLISHED USING THE USGS QUADRANGLE 7.5 MINUTE MAPS AND IS APPROXIMATE. VERIFY TRUE NORTH PRIOR TO INSTALLATION OF ANTENNAS.




**1** EQUIPMENT PLAN (EXIST)  
 A-3 SCALE: 1/2" = 1'-0"



**3** EXIST EQUIPMENT PAD  
 A-3 SCALE: N.T.S.



**2** EQUIPMENT PLAN (FINAL)  
 A-3 SCALE: 1/2" = 1'-0"



**4** EXIST FIBER DISTRIBUTION BOX  
 A-3 SCALE: N.T.S.

**Sprint**  
 2.5 EQUIPMENT DEPLOYMENT  
 6580 SPRINT PARKWAY  
 OVERLAND PARK, KANSAS 66251

**CROWN CASTLE**

**TECTONIC**  
 PLANNING  
 ENGINEERING  
 SURVEYING  
 CONSTRUCTION MANAGEMENT  
**TECTONIC Engineering & Surveying Consultants P.C.**  
 1279 Route 300  
 Newburgh, NY 12550  
 Phone: (845) 567-6656  
 Fax: (845) 567-8703  
 www.tectonicengineering.com


THIS DOCUMENT IS THE CREATION, DESIGN, PROPERTY AND COPYRIGHTED WORK OF SPRINT COMMUNICATIONS, INC. ANY DUPLICATION OR USE WITHOUT EXPRESS WRITTEN CONSENT IS STRICTLY PROHIBITED. DUPLICATION AND USE BY GOVERNMENT AGENCIES FOR THE PURPOSES OF CONDUCTING THEIR LAWFULLY AUTHORIZED REGULATORY AND ADMINISTRATIVE FUNCTIONS IS SPECIFICALLY ALLOWED.

**SUBMITTALS**

PROJECT NO: 7225.CT23XC313

NO	DATE	DESCRIPTION	BY
0	6/9/14	FOR COMMENT	BY
1	8/15/14	FOR CONSTRUCTION	MP

DATE: 8/15/14  
 REVIEWED BY: JMQ



SITE NUMBER:  
 CT23XC313


SITE NAME:  
 ORANGE/ROGERS PROPERTY

SITE ADDRESS:  
 700 GRASSY HILL ROAD  
 ORANGE, CT 06477


SHEET TITLE:  
 ENLARGED EQUIPMENT LAYOUT PLANS

SHEET NO:  
 A-3







1 ANTENNA LAYOUT PLAN (EXIST)  
SCALE: 1/2" = 1'-0"



2 ANTENNA LAYOUT PLAN (FINAL)  
SCALE: 1/2" = 1'-0"

THE EXISTING MOUNT HAS BEEN ANALYZED BY TECTONIC ENGINEERING AND FOUND TO BE ADEQUATE TO SUPPORT THE PROPOSED SPRINT UPGRADE AS DETAILED IN THE STRUCTURAL ANALYSIS EVALUATION LETTER DATED 7/28/14.

THE EXISTING MONOPOLE SHALL BE ANALYZED BY A PROFESSIONAL ENGINEER LICENSED IN THE STATE OF CONNETICUT (TO BE COORDINATED BY OTHERS)



3 RRH MOUNTING DETAIL  
SCALE: 1 1/2" = 1'-0"

**ANTENNA DATA**

Status	Exist	Proposed
Antenna Manufacturer	RFS-CELWAVE	RFS-CELWAVE
Antenna Model Number	APXVSP18-C-A20	APXVTM14-C-A20
Number of Antennas	3	3
Antenna RAD Center	130'	130'
Antenna Azimuth	10/140/220	10/140/220
Antenna RRH Model Number	800MHz/1900MHz	TD-RRH8x20-25
Number of RRH	6	3

**Sprint**  
2.5 EQUIPMENT DEPLOYMENT  
6580 SPRINT PARKWAY  
OVERLAND PARK, KANSAS 66251

**CROWN CASTLE**

**TECTONIC**  
PLANNING  
ENGINEERING  
SURVEYING  
CONSTRUCTION  
MANAGEMENT  
TECTONIC Engineering & Surveying  
Consultants P.C.  
1279 Route 300  
Newburgh, NY 12550  
Phone: (845) 567-6656  
Fax: (845) 567-8703  
www.tectonicengineering.com

THIS DOCUMENT IS THE CREATION, DESIGN, PROPERTY AND COPYRIGHTED WORK OF SPRINT COMMUNICATIONS, INC. ANY DUPLICATION OR USE WITHOUT EXPRESS WRITTEN CONSENT IS STRICTLY PROHIBITED. DUPLICATION AND USE BY GOVERNMENT AGENCIES FOR THE PURPOSES OF CONDUCTING THEIR LAWFULLY AUTHORIZED REGULATORY AND ADMINISTRATIVE FUNCTIONS IS SPECIFICALLY ALLOWED.

**SUBMITTALS**

PROJECT NO: 7225.CT23XC313

NO	DATE	DESCRIPTION	BY
0	6/9/14	FOR COMMENT	JMO
1	8/15/14	FOR CONSTRUCTION	MP


DATE: 8/15/14  
REVIEWED BY: JMO




SITE NUMBER:  
CT23XC313  
SITE NAME:  
ORANGE/ROGERS PROPERTY  
SITE ADDRESS:  
700 GRASSY HILL ROAD  
ORANGE, CT 06477

SHEET TITLE:  
ANTENNA LAYOUT PLANS


SHEET NO:  
A-4




1 2.5 CABLE COLOR CODING  
A-5 SCALE: N.T.S.



2 RRH CONNECTIVITY  
A-5 SCALE: N.T.S.



3 RAN WIRING  
A-5 SCALE: N.T.S.



4 CABLE SCENARIO  
A-5 SCALE: N.T.S.

**Sprint**  
2.5 EQUIPMENT DEPLOYMENT  
6580 SPRINT PARKWAY  
OVERLAND PARK, KANSAS 66251

**CROWN CASTLE**

**TECTONIC**  
PLANNING  
ENGINEERING  
SURVEYING  
CONSTRUCTION MANAGEMENT  
**TECTONIC Engineering & Surveying Consultants P.C.**  
1279 Route 300  
Newburgh, NY 12550  
Phone: (845) 567-6656  
Fax: (845) 567-8703  
www.tectonicengineering.com


THIS DOCUMENT IS THE CREATION, DESIGN, PROPERTY AND COPYRIGHTED WORK OF SPRINT COMMUNICATIONS, INC. ANY DUPLICATION OR USE WITHOUT EXPRESS WRITTEN CONSENT IS STRICTLY PROHIBITED. DUPLICATION AND USE BY GOVERNMENT AGENCIES FOR THE PURPOSES OF CONDUCTING THEIR LAWFULLY AUTHORIZED REGULATORY AND ADMINISTRATIVE FUNCTIONS IS SPECIFICALLY ALLOWED.

**SUBMITTALS**

PROJECT NO: 7225.CT23XC313

NO	DATE	DESCRIPTION	BY
0	6/9/14	FOR COMMENT	BY
1	8/15/14	FOR CONSTRUCTION	MP

DATE	REVIEWED BY
8/15/14	JMQ



SITE NUMBER:  
CT23XC313  
SITE NAME:  
ORANGE/ROGERS PROPERTY  
SITE ADDRESS:  
700 GRASSY HILL ROAD  
ORANGE, CT 06477

SHEET TITLE:  
RAN WIRING DIAGRAM

SHEET NO:  
A-5

THIS DOCUMENT IS THE CREATION, DESIGN, PROPERTY AND COPYRIGHTED WORK OF SPRINT COMMUNICATIONS, INC. ANY DUPLICATION OR USE WITHOUT EXPRESS WRITTEN CONSENT IS STRICTLY PROHIBITED. DUPLICATION AND USE BY GOVERNMENT AGENCIES FOR THE PURPOSES OF CONDUCTING THEIR LAWFULLY AUTHORIZED REGULATORY AND ADMINISTRATIVE FUNCTIONS IS SPECIFICALLY ALLOWED.

**SUBMITTALS**

PROJECT NO: 7225.CT23XC313

NO	DATE	DESCRIPTION	BY
0	6/9/14	FOR COMMENT	BY
1	8/15/14	FOR CONSTRUCTION	MP

DATE: 8/15/14  
 REVIEWED BY: JMG



SITE NUMBER:  
 CT23XC313

SITE NAME:  
 ORANGE/ROGERS PROPERTY

SITE ADDRESS:  
 700 GRASSY HILL ROAD  
 ORANGE, CT 06477

SHEET TITLE:  
 CABLE DETAILS

SHEET NO:  
 A-6

IMPORTANT!! LINE UP WHITE MARKINGS ON JUMPER AND RISER IP-MPO CONNECTOR. PUSH THE WHITE MARK ON THE JUMPER CONNECTOR FLUSH AGAINST THE RED SEAL ON THE RISER CONNECTION




IMPORTANT!! ROTATE THE BAYONET HOUSING CLOCKWISE UNTIL A CLICK SOUND IS HEARD TO ENSURE A GOOD CONNECTION




1 HYBRIFLEX RISER/JUMPER CONNECTION DETAILS  
 A-6 SCALE: N.T.S.

TRUNK-LINE TO JUMPER CONNECTION (MPO) TO BE INSTALLED PER MANUFACTURER REQUIREMENTS. SEE DETAIL.




2.5 HYBRID CABLE W/FIBER & DC FEEDERS



FIBER ONLY TRUNK LINES


2 TRUNK LINE DETAILS (TYPICAL)  
 A-6 SCALE: N.T.S.

- SPECIAL NOTES: CABLE MARKINGS AT RAD CENTER AND ALL WALL/BLDG. PENETRATIONS**
- ALL COLOR CODE TAPE SHALL BE 3M-35 AND SHALL BE INSTALLED USING A MINIMUM OF (3) WRAPS OF TAPE.
  - ALL COLOR BANDS INSTALLED AT THE TOWER TOP SHALL BE A MINIMUM OF 3" WIDE AND SHALL HAVE A MINIMUM OF 3/4" OF SPACING BETWEEN EACH COLOR.
  - ALL COLOR BANDS INSTALLED AT OR NEAR THE GROUND MAY BE ONLY 3/4" WIDE. EACH TOP-JUMPER SHALL BE COLOR CORDED WITH (1) SET OF 3" WIDE BANDS.
  - EACH MAIN COAX SHALL BE COLOR CODED WITH (1) SET OF 3" BANDS NEAR THE TOP-JUMPER CONNECTION AND WITH 3/4" COLOR BANDS JUST PRIOR TO ENTERING THE BTS OR TRANSMITTER BUILDING.
  - ALL BOTTOM JUMPERS SHALL BE COLOR CODED WITH (1) SET OF 3/4" BANDS ON EACH END OF THE BOTTOM JUMPER.
  - ALL COLOR CODES SHALL BE INSTALLED SO AS TO ALIGN NEATLY WITH ONE ANOTHER FROM SIDE-TO-SIDE.
  - EACH COLOR BAND SHALL HAVE A MINIMUM OF (3) WRAPS AND SHALL BE NEATLY TRIMMED AND SMOOTHED OUT AS TO AVOID UNRAVELING.
  - X-POLE ANTENNAS SHOULD USE "XX-1" FOR THE "+45" PORT, "XX-2" FOR THE "-45" PORT.
  - COLOR BAND #4 REFERS TO THE FREQUENCY BAND: ORANGE=850, VIOLET=1900. USED ON JUMPERS ONLY.
  - RF FEEDLINE SHALL BE IDENTIFIED WITH A METAL TAG (STAINLESS OR BRASS) AND STAMPED WITH THE SECTOR, ANTENNA POSITION, AND CABLE NUMBER.
  - ANTENNAS MUST BE IDENTIFIED, USING THE SECTOR LETTER AND ANTENNA NUMBER, WITH A BLACK MARKER PRIOR TO INSTALLATION.




CABINET FRONT 9928 MMBTS MODULAR CELL	
SPECIFICATIONS:	
HEIGHT:	70"
WIDTH:	35"
DEPTH:	37.8"
WEIGHT:	1090 LBS.

1 (EXIST) MMBTS CABINET  
S-1 SCALE: 1" = 1'-0"




ANDREW 60ECv2	
SPECIFICATIONS:	
HEIGHT:	60"
WIDTH:	31"
DEPTH:	30"
WEIGHT:	2430 LBS.

2 (EXIST) BATTERY CABINET  
S-1 SCALE: 1" = 1'-0"





APXVSP18-C-A20

3 (EXIST) ANTENNA DETAIL  
S-1 SCALE: 3/4"=1'-0"




APXVM14-C-120

4 (PROPOSED) ANTENNA DETAIL  
S-1 SCALE: 3/4"=1'-0"




TYPE:	1900 MHz 4x45W
MODEL #:	RRH 1900 4X45 65MHz
HEIGHT:	25.0"
WIDTH:	11.1"
DEPTH:	11.4"
WEIGHT:	±60 LBS.

5 (EXIST) RRH DETAILS  
S-1 SCALE: 1 1/2"=1'-0"



TYPE:	800 MHz 2x50W
MODEL #:	FD-RRH-2x50-800
HEIGHT:	19.7"
WIDTH:	13"
DEPTH:	10.8"
WEIGHT:	±53 LBS

6 (PROPOSED) RRH DETAIL  
S-1 SCALE: N.T.S.



TYPE:	2.5 RRH
MODEL #:	TD-RRH8x20-25
HEIGHT:	26.1"
WIDTH:	18.6"
DEPTH:	6.71"
WEIGHT:	±70 LBS

**Sprint**  
2.5 EQUIPMENT DEPLOYMENT  
6580 SPRINT PARKWAY  
OVERLAND PARK, KANSAS 66251


**CROWN CASTLE**

**TECTONIC** ENGINEERING SURVEYING CONSTRUCTION MANAGEMENT  
TECTONIC Engineering & Surveying Consultants P.C.  
1279 Route 300  
Newburgh, NY 12550  
Phone: (845) 567-6656  
Fax: (845) 567-8703  
www.tectonicengineering.com

THIS DOCUMENT IS THE CREATION, DESIGN, PROPERTY AND COPYRIGHTED WORK OF SPRINT COMMUNICATIONS, INC. ANY DUPLICATION OR USE WITHOUT EXPRESS WRITTEN CONSENT IS STRICTLY PROHIBITED. DUPLICATION AND USE BY GOVERNMENT AGENCIES FOR THE PURPOSES OF CONDUCTING THEIR LAWFULLY AUTHORIZED REGULATORY AND ADMINISTRATIVE FUNCTIONS IS SPECIFICALLY ALLOWED.

SUBMITTALS			
PROJECT NO: 7225.CT23XC313			
NO	DATE	DESCRIPTION	BY
0	6/9/14	FOR COMMENT	BY
1	8/15/14	FOR CONSTRUCTION	MP


DATE	REVIEWED BY
8/15/14	JMG



SITE NUMBER:  
CT23XC313  
SITE NAME:  
ORANGE/ROGERS PROPERTY  
SITE ADDRESS:  
700 GRASSY HILL ROAD  
ORANGE, CT 06477

SHEET TITLE:  
EQUIPMENT DETAILS

SHEET NO:  
S-1



9929 EXPANSION CABINET	
CABINET SPECIFICATIONS	
EXPANSION CABINET:	
- HEIGHT -	63.65"
- WIDTH -	31.5"
- DEPTH -	35.5"
WEIGHT: 1,600 LBS.	




INSTALL NEW 2.5 EQUIPMENT IN PROPOSED 9929 EXPANSION CABINET INCLUDING BUT NOT LIMITED TO BASE BAND UNIT, CELL SITE ROUTER AND SURGE ARRESTORS. GROUND EQUIPMENT TO PROPOSED INTERIOR CABINET GROUND BAR

FRONT ELEVATION  
(CABINET INTERIOR)

1 9929 INTERIOR DETAIL  
S-2 SCALE: N.T.S.

Power	Hybrid cable	Length
Fiber Only (Existing DC Power)	MN: HB058-M12-050F 12x multi-mode fiber pairs, Top: Outdoor protected connectors, Bottom: LC Connectors, 5/8 cable, 50ft	50 ft
	MN: HB058-M12-075F	75 ft
	MN: HB058-M12-100F	100 ft
	MN: HB058-M12-125F	125 ft
	MN: HB058-M12-150F	150 ft
	MN: HB058-M12-175F MN: HB058-M12-200F	175 ft 200 ft
8 AWG Power	MN: HB114-08U3M12-050F 3x 8 AWG power pairs, 12x multi-mode fiber pairs, Outdoor rated connectors & LC Connectors, 1 1/4 cable, 50ft	50 ft
	MN: HB114-08U3M12-075F	75 ft
	MN: HB114-08U3M12-100F	100 ft
	MN: HB114-08U3M12-125F	125 ft
	MN: HB114-08U3M12-150F	150 ft
	MN: HB114-08U3M12-175F MN: HB114-08U3M12-200F	175 ft 200 ft
6 AWG Power	MN: HB114-13U3M12-225F 3x 6 AWG power pairs, 12x multi-mode fiber pairs, Outdoor rated connectors & LC Connectors, 1 1/4 cable, 225ft	225 ft
	MN: HB114-13U3M12-250F	250 ft
	MN: HB114-13U3M12-275F	275 ft
	MN: HB114-13U3M12-300F	300 ft
4 AWG Power	MN: HB114-21U3M12-225F 3x 4 AWG power pairs, 12x multi-mode fiber pairs, Outdoor rated connectors & LC Connectors, 1 1/4 cable, 225ft	325 ft
	MN: HB114-21U3M12-350F	350 ft
	MN: HB114-21U3M12-375F	375 ft

MANUF:	RFS	DC CONDUCTOR	CABLE DIAMETER
CABLE	LENGTH	USE NV HYBRIFLEX	7/8"
FIBER ONLY	VARIES	8 AWG	1-1/4"
HYBRIFLEX	<200'	8 AWG	1-1/4"
HYBRIFLEX	225-300'	6 AWG	1-1/4"
HYBRIFLEX	325-375'	4 AWG	1-1/4"



Power	Hybrid Jumper cable	Length
Fiber Only	MN: HBF012-M3-5F1 5 ft, 3x multi-mode fiber pairs, Outdoor & LC connectors, 1/2 cable	5 ft
	MN: HBF012-M3-10F1	10 ft
	MN: HBF012-M3-15F1	15 ft
	MN: HBF012-M3-20F1	20 ft
	MN: HBF012-M3-25F1	25 ft
	MN: HBF012-M3-30F1	30 ft
8 AWG Power	MN: HBF058-08U1M3-5F1 5 ft, 1x 8 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 5/8 cable	5 ft
	MN: HBF058-08U1M3-10F1	10 ft
	MN: HBF058-08U1M3-15F1	15 ft
	MN: HBF058-08U1M3-20F1	20 ft
	MN: HBF058-08U1M3-25F1	25 ft
	MN: HBF058-08U1M3-30F1	30 ft
6 AWG Power	MN: HBF058-13U1M3-5F1 5 ft, 1x 6 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 5/8 cable	5 ft
	MN: HBF058-13U1M3-10F1	10 ft
	MN: HBF058-13U1M3-15F1	15 ft
	MN: HBF058-13U1M3-20F1	20 ft
	MN: HBF058-13U1M3-25F1	25 ft
	MN: HBF058-13U1M3-30F1	30 ft
4 AWG Power	MN: HBF078-21U1M3-5F1 5 ft, 1x 4 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 7/8 cable	5 ft
	MN: HBF078-21U1M3-10F1	10 ft
	MN: HBF078-21U1M3-15F1	15 ft
	MN: HBF078-21U1M3-20F1	20 ft
	MN: HBF078-21U1M3-25F1	25 ft
	MN: HBF078-21U1M3-30F1	30 ft


Power	Hybrid Jumper cable	Length
8 AWG Power	MN: HBF058-08U1M3-5F1 5 ft, 1x 8 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 5/8 cable	5 ft
	MN: HBF058-08U1M3-10F1	10 ft
	MN: HBF058-08U1M3-15F1	15 ft
	MN: HBF058-08U1M3-20F1	20 ft
	MN: HBF058-08U1M3-25F1	25 ft
	MN: HBF058-08U1M3-30F1	30 ft
6 AWG Power	MN: HBF058-13U1M3-5F1 5 ft, 1x 6 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 5/8 cable	5 ft
	MN: HBF058-13U1M3-10F1	10 ft
	MN: HBF058-13U1M3-15F1	15 ft
	MN: HBF058-13U1M3-20F1	20 ft
	MN: HBF058-13U1M3-25F1	25 ft
	MN: HBF058-13U1M3-30F1	30 ft
4 AWG Power	MN: HBF078-21U1M3-5F1 5 ft, 1x 4 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 7/8 cable	5 ft
	MN: HBF078-21U1M3-10F1	10 ft
	MN: HBF078-21U1M3-15F1	15 ft
	MN: HBF078-21U1M3-20F1	20 ft
	MN: HBF078-21U1M3-25F1	25 ft
	MN: HBF078-21U1M3-30F1	30 ft

Power	Hybrid Jumper cable	Length
8 AWG Power	MN: HBF058-08U1M3-5F1 5 ft, 1x 8 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 5/8 cable	5 ft
	MN: HBF058-08U1M3-10F1	10 ft
	MN: HBF058-08U1M3-15F1	15 ft
	MN: HBF058-08U1M3-20F1	20 ft
	MN: HBF058-08U1M3-25F1	25 ft
	MN: HBF058-08U1M3-30F1	30 ft
6 AWG Power	MN: HBF058-13U1M3-5F1 5 ft, 1x 6 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 5/8 cable	5 ft
	MN: HBF058-13U1M3-10F1	10 ft
	MN: HBF058-13U1M3-15F1	15 ft
	MN: HBF058-13U1M3-20F1	20 ft
	MN: HBF058-13U1M3-25F1	25 ft
	MN: HBF058-13U1M3-30F1	30 ft
4 AWG Power	MN: HBF078-21U1M3-5F1 5 ft, 1x 4 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 7/8 cable	5 ft
	MN: HBF078-21U1M3-10F1	10 ft
	MN: HBF078-21U1M3-15F1	15 ft
	MN: HBF078-21U1M3-20F1	20 ft
	MN: HBF078-21U1M3-25F1	25 ft
	MN: HBF078-21U1M3-30F1	30 ft

Power	Hybrid Jumper cable	Length
8 AWG Power	MN: HBF058-08U1M3-5F1 5 ft, 1x 8 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 5/8 cable	5 ft
	MN: HBF058-08U1M3-10F1	10 ft
	MN: HBF058-08U1M3-15F1	15 ft
	MN: HBF058-08U1M3-20F1	20 ft
	MN: HBF058-08U1M3-25F1	25 ft
	MN: HBF058-08U1M3-30F1	30 ft
6 AWG Power	MN: HBF058-13U1M3-5F1 5 ft, 1x 6 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 5/8 cable	5 ft
	MN: HBF058-13U1M3-10F1	10 ft
	MN: HBF058-13U1M3-15F1	15 ft
	MN: HBF058-13U1M3-20F1	20 ft
	MN: HBF058-13U1M3-25F1	25 ft
	MN: HBF058-13U1M3-30F1	30 ft
4 AWG Power	MN: HBF078-21U1M3-5F1 5 ft, 1x 4 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 7/8 cable	5 ft
	MN: HBF078-21U1M3-10F1	10 ft
	MN: HBF078-21U1M3-15F1	15 ft
	MN: HBF078-21U1M3-20F1	20 ft
	MN: HBF078-21U1M3-25F1	25 ft
	MN: HBF078-21U1M3-30F1	30 ft

2 2.5 HYBRID CABLE X-SECTION AND DATA  
S-2 SCALE: NTS

- LEGEND:
- P1000T-HG UNISTRUT, 12" LONG.
  - 6" PIPE HANGER.
  - EXISTING SUPPORT PIPE.
  - NEW STANDOFF BRACKET, ANDREW PART# 30848-4.
  - NEW ROUND MEMBER ADAPTER SIZED FOR EXISTING PIPE SUPPORT.
  - BREAKOUT UNIT.
  - CABLE.



3 MEDUSA HEAD DETAIL  
S-2 SCALE: NTS

**Sprint**  
2.5 EQUIPMENT DEPLOYMENT  
6580 SPRINT PARKWAY  
OVERLAND PARK, KANSAS 66251


**CROWN CASTLE**

**TECTONIC**  
PLANNING  
ENGINEERING  
SURVEYING  
CONSTRUCTION MANAGEMENT  
TECTONIC Engineering & Surveying Consultants P.C.  
1279 Route 300  
Newburgh, NY 12550  
Phone: (845) 567-6656  
Fax: (845) 567-8703  
www.tectoniceengineering.com

THIS DOCUMENT IS THE CREATION, DESIGN, PROPERTY AND COPYRIGHTED WORK OF SPRINT COMMUNICATIONS, INC. ANY DUPLICATION OR USE WITHOUT EXPRESS WRITTEN CONSENT IS STRICTLY PROHIBITED. DUPLICATION AND USE BY GOVERNMENT AGENCIES FOR THE PURPOSES OF CONDUCTING THEIR LAWFULLY AUTHORIZED REGULATORY AND ADMINISTRATIVE FUNCTIONS IS SPECIFICALLY ALLOWED.

NO	DATE	DESCRIPTION	BY
0	6/9/14	FOR COMMENT	BY
1	8/15/14	FOR CONSTRUCTION	MP

DATE	REVIEWED BY
8/15/14	JMQ



SITE NUMBER:  
CT23XC313  
SITE NAME:  
ORANGE/ROGERS PROPERTY  
SITE ADDRESS:  
700 GRASSY HILL ROAD  
ORANGE, CT 06477

SHEET TITLE:  
EQUIPMENT  
SCHEMATIC DETAILS

SHEET NO:  
S-2

THIS DOCUMENT IS THE CREATION, DESIGN, PROPERTY AND COPYRIGHTED WORK OF SPRINT COMMUNICATIONS, INC. ANY DUPLICATION OR USE WITHOUT EXPRESS WRITTEN CONSENT IS STRICTLY PROHIBITED. DUPLICATION AND USE BY GOVERNMENT AGENCIES FOR THE PURPOSES OF CONDUCTING THEIR LAWFULLY AUTHORIZED REGULATORY AND ADMINISTRATIVE FUNCTIONS IS SPECIFICALLY ALLOWED.

**SUBMITTALS**

PROJECT NO: 7225.CT23XC313

NO	DATE	DESCRIPTION	BY
0	6/9/14	FOR COMMENT	BY
1	8/15/14	FOR CONSTRUCTION	MP

DATE	REVIEWED BY
8/15/14	JMQ




SITE NUMBER:  
**CT23XC313**

SITE NAME:  
**ORANGE/ROGERS PROPERTY**


SITE ADDRESS:  
**700 GRASSY HILL ROAD  
 ORANGE, CT 06477**

SHEET TITLE:  
**ELECTRICAL & GROUNDING PLANS**


SHEET NO:  
**E-1**




**1**  
 E-1  
**TYPICAL GROUNDING ONE LINE DIAGRAM**  
 SCALE: NTS



**2**  
 E-1  
**TYPICAL ANTENNA GROUNDING PLAN**  
 SCALE: NTS



**3**  
 E-1  
**TYPICAL ELECTRICAL & TELCO PLAN**  
 NOTE: FINAL ELECTRICAL DESIGN TO BE DETERMINED BY OTHER.  
 SCALE: NTS



6 AWG STRANDED Cu WIRE WITH GREEN, 600V, THWN INSULATION OR BLACK, MARKED AS REQUIRED BY THE NEC (GROUNDED TO GROUND BAR) (SEE NOTES 1 & 2)


CONNECTION OF CABLE GROUND KIT TO ANTENNA CABLE

NOTES:

- DO NOT INSTALL CABLE GROUND KIT AT A BEND AND ALWAYS DIRECT GROUND WIRE DOWN TO GROUND BAR.
- GROUNTING KIT SHALL BE TYPE AND PART NUMBER AS SUPPLIED OR RECOMMENDED BY CABLE MANUFACTURER.
- WEATHER PROOFING SHALL BE (TYPE AND PART NUMBER) AS SUPPLIED OR RECOMMENDED BY CABLE MANUFACTURER AND APPROVED BY CONTRACTOR.

1 CABLE GROUNDING KIT DETAIL

E-2 SCALE: N.T.S.




NOTE:  
 1. "DOUBLING UP" OR "STACKING" OF CONNECTION IS NOT PERMITTED.  
 2. OXIDE INHIBITING COMPOUND TO BE USED AT ALL LOCATIONS.  
 3. CADWELD DOWNLEADS FROM UPPER EGB, LOWER EGB AND MGB.

SECTION "A-A"

2 GROUNDING BAR CONN. DETAIL

E-2 SCALE: N.T.S.




LEGEND

- 1- COPPER TINNED GROUND BAR, 1/4" X 4" X 20", OR OTHER LENGTH AS REQUIRED, HOLE CENTERS TO MATCH NEMA DOUBLE LUG CONFIGURATION
- 2- INSULATORS, NEWTON INSTRUMENT CAT. NO. 3061-4 OR EQUAL
- 3- 5/8" LOCKWASHERS OR EQUAL
- 4- WALL MOUNTING BRACKET, NEWTON INSTRUMENT CO. CAT NO. A-6056 OR EQUAL
- 5- 5/8-11 X 1" H.C.S. BOLTS

NOTE:  
 ALL BOLTS, NUTS, WASHERS AND LOCK WASHERS SHALL BE 18-8 STAINLESS STEEL.

3 GROUNDING BAR DETAIL

E-2 SCALE: N.T.S.



\*TWO HOLE LUG, OR EXOTHERMIC WELD TO BE USED WITH #2 AWG BCW TO BUILDING, GROUND OR GROUND RING

- \* - GROUND BARS AT THE BOTTOM OF TOWERS/MONOPOLES SHALL ONLY USE EXOTHERMIC WELDS.
- ATTACH "DO NOT DISCONNECT" LABELS TO GROUND BARS. CAN USE BRASS TAG "DO NOT DISCONNECT" AT EACH HYBRID GROUND POINT OR BACK-A-LITE PLATE LABEL ON GROUND BAR.
- CONNECT SEQUENCE- BOLT/WASHER/NO-OX/GROUND BAR/NO-OX/WASHER/LOCK-WASHER/NUT. THIS IS REPEATED FOR EACH LUG CONNECTION POINT.

4 ANTENNA GROUND BAR DETAIL

E-2 SCALE: N.T.S.

GROUNDING NOTES:

- GROUNDING SHALL BE IN ACCORDANCE WITH NEC ARTICLE 250-GROUNDING AND BONDING.
- ALL GROUND WIRES SHALL BE #2 AWG UNLESS NOTED OTHERWISE.
- ALL GROUNDING WIRES SHALL PROVIDE A STRAIGHT, DOWNWARD PATH TO GROUND WITH GRADUAL BENDS AS REQUIRED. GROUND WIRES SHALL NOT BE LOOPED OR SHARPLY BENT.
- EACH EQUIPMENT CABINET SHALL BE CONNECTED TO THE MASTER ISOLATION GROUND BAR (MGB) WITH #2 AWG INSULATED STRANDED COPPER WIRE. EQUIPMENT CABINETS WILL HAVE (2) CONNECTIONS.
- PROVIDE DEDICATED #2 AWG COPPER GROUND WIRE FROM EACH ANTENNA MOUNTING PIPE TO ASSOCIATED CIGBE.
- THE CONTRACTOR SHALL VERIFY THAT THE EXISTING GROUND BARS HAVE ENOUGH SPACE/HOLES FOR ADDITIONAL TWO HOLE LUGS.
- ALL CONDUITS SHALL BE RIGID GALVANIZED STEEL AND SHALL BE PROVIDED WITH GROUNDING BUSHINGS.
- PROVIDE GROUND CONNECTIONS FOR ALL METALLIC STRUCTURES, ENCLOSURES, RACEWAYS AND OTHER CONDUCTIVE ITEMS ASSOCIATED WITH THE INSTALLATION OF CARRIER'S EQUIPMENT.
- WHEN CABLE LENGTH IS OVER 20' THE MANUFACTURERS GROUND KIT MUST BE INSTALLED PER THE MANUFACTURERS SPECIFICATIONS.
- REFER TO "ANTI-THEFT UPDATE TO SPRINT GROUNDING 082412.PDF" FOR GUIDELINE TO SUSPECTED OR ACTUAL THEFT OF GROUNDING.
- HOME RUN GROUNDS ARE NOT APPROVED BY CROWN CASTLE CONSTRUCTION STANDARDS AND THAT ANTENNA BUSS BARS SHOULD BE INSTALLED DIRECTLY TO TOWER STEEL WITHOUT INSULATORS OR DOWN CONDUCTORS.

PROTECTIVE GROUNDING SYSTEM GENERAL NOTES:

- AT ALL TERMINATIONS AT EQUIPMENT ENCLOSURES, PANEL, AND FRAMES OF EQUIPMENT AND WHERE EXPOSED FOR GROUNDING, CONDUCTOR TERMINATION SHALL BE PERFORMED UTILIZING TWO HOLE BOLTED TONGUE COMPRESSION TYPE LUGS WITH STAINLESS STEEL SELF-TAPPING SCREWS.
- ALL CLAMPS AND SUPPORTS USED TO SUPPORT THE GROUNDING SYSTEM CONDUCTORS AND PVC CONDUITS SHALL BE PVC TYPE (NON CONDUCTIVE). DO NOT USE METAL BRACKETS OR SUPPORTS WHICH WOULD FORM A COMPLETE RING AROUND ANY GROUNDING CONDUCTOR.
- ALL GROUNDING CONNECTIONS SHALL BE COATED WITH A COPPER SHIELD ANTI-CORROSIVE AGENT SUCH AS T&B KOPR SHIELD. VERIFY PRODUCT WITH PROJECT MANAGER.
- ALL BOLTS, WASHERS, AND NUTS USED ON GROUNDING CONNECTIONS SHALL BE STAINLESS STEEL.
- INSTALL GROUND BUSHING ON ALL METALLIC CONDUITS AND BOND TO THE EQUIPMENT GROUND BUS IN THE PANEL BOARD.
- GROUND ANTENNA BASES, FRAMES, CABLE RACKS, AND OTHER METALLIC COMPONENTS WITH #2 INSULATED TINNED STRANDED COPPER GROUNDING CONDUCTORS AND CONNECT TO INSULATED SURFACE MOUNTED GROUND BARS. CONNECTION DETAILS SHALL FOLLOW MANUFACTURER'S SPECIFICATIONS FOR GROUNDING.
- GROUND HYBRID CABLE SHIELD AT BOTH ENDS USING MANUFACTURER'S GUIDELINES.

ELECTRICAL AND GROUNDING NOTES

- ALL ELECTRICAL WORK SHALL CONFORM TO THE REQUIREMENTS OF THE NATIONAL ELECTRICAL CODE (NEC) AS WELL AS APPLICABLE STATE AND LOCAL CODES.
- ALL ELECTRICAL ITEMS SHALL BE U.L. APPROVED OR LISTED AND PROCURED PER SPECIFICATION REQUIREMENTS.
- ELECTRICAL AND TELCO WIRING OUTSIDE A BUILDING AND EXPOSED TO WEATHER SHALL BE IN WATER TIGHT GALVANIZED RIGID STEEL CONDUITS OR SCHEDULE 80 PVC (AS PERMITTED BY CODE) AND WHERE REQUIRED IN LIQUID TIGHT FLEXIBLE METAL OR NONMETALLIC CONDUITS.
- BURIED CONDUIT SHALL BE SCHEDULE 40 PVC.
- ELECTRICAL WIRING SHALL BE COPPER WITH TYPE XHHW, THWN, OR THHN INSULATION.
- RUN TELCO CONDUIT OR CABLE BETWEEN TELEPHONE UTILITY DEMARCATION POINT AND PROJECT OWNER CELL SITE TELCO CABINET AND BTS CABINET AS INDICATED ON THIS DRAWING PROVIDE FULL LENGTH PULL ROPE IN INSTALLED TELCO CONDUIT. PROVIDE GREENLEE CONDUIT MEASURING TAPE AT EACH END.
- WHERE CONDUIT BETWEEN BTS AND PROJECT OWNER CELL SITE PPC AND BETWEEN BTS AND PROJECT OWNER CELL SITE TELCO SERVICE CABINET ARE UNDERGROUND USE PVC, SCHEDULE 40 CONDUIT. ABOVE THE GROUND PORTION OF THESE CONDUITS SHALL BE PVC CONDUIT.
- ALL EQUIPMENT LOCATED OUTSIDE SHALL HAVE NEMA 3R ENCLOSURE.
- GROUNDING SHALL COMPLY WITH NEC ART. 250.
- GROUND HYBRID CABLE SHIELDS AT 3 LOCATIONS USING MANUFACTURER'S HYBRID CABLE GROUNDING KITS SUPPLIED BY PROJECT OWNER.
- USE #2 COPPER STRANDED WIRE WITH GREEN COLOR INSULATION FOR ABOVE GRADE GROUNDING (UNLESS OTHERWISE SPECIFIED) AND #2 SOLID TINNED BARE COPPER WIRE FOR BELOW GRADE GROUNDING AS INDICATED ON THE DRAWING.
- ALL GROUND CONNECTIONS TO BE BURNDY HYGROUND COMPRESSION TYPE CONNECTORS OR CADWELD EXOTHERMIC WELD. DO NOT ALLOW BARE COPPER WIRE TO BE IN CONTACT WITH GALVANIZED STEEL.
- ROUTE GROUNDING CONDUCTORS ALONG THE SHORTEST AND STRAIGHTEST PATH POSSIBLE, EXCEPT AS OTHERWISE INDICATED. GROUNDING LEADS SHOULD NEVER BE BENT AT RIGHT ANGLE. ALWAYS MAKE AT LEAST 12" RADIUS BENDS. #2 WIRE CAN BE BENT AT 6" RADIUS WHEN NECESSARY. BOND ANY METAL OBJECTS WITHIN 6 FEET OF PROJECT OWNER EQUIPMENT OR CABINET TO MASTER GROUND BAR OR GROUNDING RING.
- CONNECTIONS TO GROUND BARS SHALL BE MADE WITH TWO HOLE COMPRESSION TYPE COPPER LUGS. APPLY OXIDE INHIBITING COMPOUND TO ALL LOCATIONS.
- APPLY OXIDE INHIBITING COMPOUND TO ALL COMPRESSION TYPE GROUND CONNECTIONS.
- BOND ANTENNA MOUNTING BRACKETS, HYBRID CABLE GROUND KITS, AND RRHs TO EGB PLACED NEAR THE ANTENNA LOCATION.
- BOND ANTENNA EGB'S AND MGB TO GROUND RING.
- CONTRACTOR SHALL TEST COMPLETED GROUND SYSTEM AND RECORD RESULT FOR PROJECT CLOSE-OUT DOCUMENTATION. 5 OHMS MINIMUM RESISTANCE REQUIRED.
- CONTRACTOR SHALL CONDUCT ANTENNA, HYBRID CABLES, GPS COAX AND RRH RETURN-LOSS AND DISTANCE- TO-FAULT MEASUREMENTS (SWEEP TESTS) AND RECORD RESULTS FOR PROJECT CLOSE OUT.
- CONTRACTOR SHALL CHECK CAPACITY OF EXISTING SERVICE & PANEL ON SITE TO DETERMINE IF CAPACITY EXISTS TO ACCOMMODATE THE ADDED LOAD OF THIS PROJECT. ADVISE ENGINEER OF ANY DISCREPANCY.
- LOCATION OF ALL OUTLET, BOXES, ETC, AND THE TYPE OF CONNECTION (PLUG OR DIRECT) SHALL BE CONFIRMED WITH THE OWNER'S REPRESENTATIVE PRIOR TO ROUGH-IN.
- ELECTRICAL CHARACTERISTICS OF ALL EQUIPMENT (NEW AND EXISTING) SHALL BE FIELD VERIFIED WITH THE OWNERS REPRESENTATIVE AND EQUIPMENT SUPPLIER PRIOR TO ROUGH-IN OF CONDUIT AND WIRE. ALL EQUIPMENT SHALL BE PROPERLY CONNECTED ACCORDING TO THE NAMEPLATE DATA FURNISHED ON THE EQUIPMENT.

**Sprint**  
 2.5 EQUIPMENT DEPLOYMENT  
 6580 SPRINT PARKWAY  
 OVERLAND PARK, KANSAS 66251

**CROWN CASTLE**

**TECTONIC**  
 PLANNING  
 ENGINEERING  
 SURVEYING  
 CONSTRUCTION MANAGEMENT

TECTONIC Engineering & Surveying Consultants P.C.  
 1279 Route 300  
 Newburgh, NY 12550  
 Phone: (845) 567-6656  
 Fax: (845) 567-8703  
 www.tectonicengineering.com

THIS DOCUMENT IS THE CREATION, DESIGN, PROPERTY AND COPYRIGHTED WORK OF SPRINT COMMUNICATIONS, INC. ANY DUPLICATION OR USE WITHOUT EXPRESS WRITTEN CONSENT IS STRICTLY PROHIBITED. DUPLICATION AND USE BY GOVERNMENT AGENCIES FOR THE PURPOSES OF CONDUCTING THEIR LAWFULLY AUTHORIZED REGULATORY AND ADMINISTRATIVE FUNCTIONS IS SPECIFICALLY ALLOWED.

**SUBMITTALS**

PROJECT NO: 7225.CT23XC313

NO	DATE	DESCRIPTION	BY
0	6/9/14	FOR COMMENT	BY
1	8/15/14	FOR CONSTRUCTION	MP

DATE	REVIEWED BY
8/15/14	JMQ

SEAL

SITE NUMBER:  
 CT23XC313

SITE NAME:  
 ORANGE/ROGERS PROPERTY

SITE ADDRESS:  
 700 GRASSY HILL ROAD  
 ORANGE, CT 06477

SHEET TITLE:  
 GROUNDING DETAILS & NOTES

SHEET NO:  
 E-2

Date: June 11, 2014



Patrick Byrum  
Crown Castle  
3530 Toringdon Way, Suite 300  
Charlotte, NC 28277  
(704) 405-6532

Vertical Structures, Inc.  
309 Spangler Drive, Suite E  
Richmond, KY 40475  
(859) 624-8360  
amathis@verticalstructures.com

**Subject: Structural Analysis Report**

<b>Carrier Designation:</b>	<b>Sprint PCS Co-Locate</b>	Scenario 2.5B
	<b>Carrier Site Number:</b>	CT23XC313
	<b>Carrier Site Name:</b>	N/A
<b>Crown Castle Designation:</b>	<b>Crown Castle BU Number:</b>	881541
	<b>Crown Castle Site Name:</b>	Rogers Property
	<b>Crown Castle JDE Job Number:</b>	288230
	<b>Crown Castle Work Order Number:</b>	773463
	<b>Crown Castle Application Number:</b>	245874 Rev. 1
<b>Engineering Firm Designation:</b>	<b>Vertical Structures, Inc. Project Number:</b>	2014-004-024
<b>Site Data:</b>	<b>Grassy Hill Road, Orange, CT, New Haven County</b>	
	<b>Latitude 41° 17' 7.75", Longitude -73° 2' 33.27"</b>	
	<b>139.5 Foot - Monopole Tower</b>	

Dear Patrick Byrum,

Vertical Structures, Inc. is pleased to submit this "Structural Analysis Report" to determine the structural integrity of the above mentioned tower. This analysis has been performed in accordance with the Crown Castle Structural 'Statement of Work' and the terms of Crown Castle Purchase Order Number 654290.

The purpose of the analysis is to determine acceptability of the tower stress level. Based on our analysis we have determined the tower stress level for the structure and foundation, under the following load case, to be:

LC7: Existing + Reserved + Proposed Equipment	<b>Sufficient Capacity</b>
Note: See Table I and Table II for the proposed and existing/reserved loading, respectively.	

The analysis has been performed in accordance with the TIA/EIA-222-F standard and the 2005 Connecticut State Building Code based upon a wind speed of 85 mph fastest mile.

All modifications and equipment proposed in this report shall be installed in accordance with the attached drawings for the determined available structural capacity to be effective.

We at Vertical Structures, Inc. appreciate the opportunity of providing our continuing professional services to you and Crown Castle. If you have any questions or need further assistance on this or any other projects please give us a call.

Respectfully submitted by:

Andrew Mathis  
Project Engineer





Date: **June 11, 2014**



Patrick Byrum  
Crown Castle  
3530 Toringdon Way, Suite 300  
Charlotte, NC 28277  
(704) 405-6532

Vertical Structures, Inc.  
309 Spangler Drive, Suite E  
Richmond, KY 40475  
(859) 624-8360  
amathis@verticalstructures.com

**Subject: Structural Analysis Report**

<b>Carrier Designation:</b>	<b>Sprint PCS Co-Locate</b>	Scenario 2.5B
	<b>Carrier Site Number:</b>	CT23XC313
	<b>Carrier Site Name:</b>	N/A
<b>Crown Castle Designation:</b>	<b>Crown Castle BU Number:</b>	881541
	<b>Crown Castle Site Name:</b>	Rogers Property
	<b>Crown Castle JDE Job Number:</b>	288230
	<b>Crown Castle Work Order Number:</b>	773463
	<b>Crown Castle Application Number:</b>	245874 Rev. 1
<b>Engineering Firm Designation:</b>	<b>Vertical Structures, Inc. Project Number:</b>	2014-004-024
<b>Site Data:</b>	<b>Grassy Hill Road, Orange, CT, New Haven County</b> <b>Latitude 41° 17' 7.75", Longitude -73° 2' 33.27"</b> <b>139.5 Foot - Monopole Tower</b>	

Dear Patrick Byrum,

Vertical Structures, Inc. is pleased to submit this "**Structural Analysis Report**" to determine the structural integrity of the above mentioned tower. This analysis has been performed in accordance with the Crown Castle Structural 'Statement of Work' and the terms of Crown Castle Purchase Order Number 654290.

The purpose of the analysis is to determine acceptability of the tower stress level. Based on our analysis we have determined the tower stress level for the structure and foundation, under the following load case, to be:

LC7: Existing + Reserved + Proposed Equipment

**Sufficient Capacity**

Note: See Table I and Table II for the proposed and existing/reserved loading, respectively.

The analysis has been performed in accordance with the TIA/EIA-222-F standard and the 2005 Connecticut State Building Code based upon a wind speed of 85 mph fastest mile.

All modifications and equipment proposed in this report shall be installed in accordance with the attached drawings for the determined available structural capacity to be effective.

We at Vertical Structures, Inc. appreciate the opportunity of providing our continuing professional services to you and Crown Castle. If you have any questions or need further assistance on this or any other projects please give us a call.

Respectfully submitted by:

Andrew Mathis  
Project Engineer

## TABLE OF CONTENTS

### 1) INTRODUCTION

### 2) ANALYSIS CRITERIA

Table 1 - Proposed Antenna and Cable Information

Table 2 - Existing and Reserved Antenna and Cable Information

Table 3 - Design Antenna and Cable Information

### 3) ANALYSIS PROCEDURE

Table 4 - Documents Provided

3.1) Analysis Method

3.2) Assumptions

### 4) ANALYSIS RESULTS

Table 5 - Section Capacity (Summary)

Table 6 – Tower Component Stresses vs. Capacity - LC7

4.1) Recommendations

### 5) APPENDIX A

tnxTower Output

### 6) APPENDIX B

Base Level Drawing

### 7) APPENDIX C

Additional Calculations

## 1) INTRODUCTION

This tower is a 139.5 ft Monopole tower designed by EEI in 2004. The tower was originally designed for a wind speed of 90 mph per TIA/EIA-222-F. The tower was reworked in 2014 to accommodate additional loading.

## 2) ANALYSIS CRITERIA

The structural analysis was performed for this tower in accordance with the requirements of TIA/EIA-222-F Structural Standards for Steel Antenna Towers and Antenna Supporting Structures using a fastest mile wind speed of 85 mph with no ice and 50 mph under service loads. Also, per Crown Castle's direction and in accordance with ASCE-7-05 we have considered a fastest mile wind speed of 38 mph with an escalating 0.75 inch ice thickness.

**Table 1 - Proposed Antenna and Cable Information**

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)	Note
130.0	130.0	3	alcatel lucent	TD-RRH8x20-25 BTS	1	1 1/4	
		3	celwave	APXVTM14-C-120 w/ Mount Pipe			

**Table 2 - Existing and Reserved Antenna and Cable Information**

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)	Note	
136.0	140.0	3	ericsson	RRUS-11 BTS	1 2 6	5/8 3/8 1 5/8	1	
		3	kathrein	800 10121 w/ Mount Pipe				
		6	powerwave technologies	LGP21401 TMA				
		3	powerwave technologies	P65-16-XLH-RR w/ Mount Pipe				
		1	raycap	DC6-48-60-18-8F				
	136.0	1		T-Arm Mount [TA 702-3]				
132.0	132.0	1		Side Arm Mount [SO 102-3]			1	
		3	alcatel lucent	1900MHz RRH (65MHz) TMA				
		3	alcatel lucent	800MHZ RRH TMA				
130.0	134.0	1	andrew	VHLP2-11	3 3 3	1/2 5/16 1 1/4	1	
	132.0	3	argus technologies	LLPX310R w/ Mount Pipe				
		1	dragonwave	A-ANT-23G-2-C				
		3	samsung telecommunications	FDD_R6_RRH TMA				
	130.0	130.0	1					12' (4" Tube) T-Arm (3)
			3	alcatel lucent				800 External Notch Filter
			9	celwave				ACU-A20-N Diplexer
		3	celwave	APXVSPP18-C-A20 w/ Mount Pipe				
124.0	124.0				6	1 5/8	1	

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)	Note
120.0	120.0	1		Side Arm Mount [SO 102-1]			2
		1	rfs celwave	TMA-DB-T1-6Z-8AB-0Z w/ Mount Pipe			
118.0	118.0	1		T-Arm Mount [TA 602-3]			1
		3	alcatel lucent	RRH2X40-AWS BTS	1	1 5/8	2
		3	antel	BXA-171063-8BF-EDIN-0 w/ Mount Pipe			
		3	antel	BXA-70063-6CF-EDIN-0 w/ Mount Pipe	12	1 5/8	1
		6	celwave	FD9R6004/2C-3L Diplexer			
		6	decibel	DB846F65ZAXY w/ Mount Pipe			
108.0	109.0	3	ericsson	AIR 21 B2A B4P w/ Mount Pipe	1	1 5/8	2
		3	ericsson	KRY 112 144/1 TMA			
	108.0	1		T-Arm Mount [TA 602-3]	12	1 5/8	1
100.0	100.0	3	celwave	APXV18-206517-C w/ Mount Pipe	6	1 5/8	1
75.0	77.0	1	lucent	KS24019-L112A	1	1/2	1
	75.0	1		Side Arm Mount [SO 701-1]			

- Notes:  
 1) Existing Equipment  
 2) Reserved Equipment

**Table 3 - Design Antenna and Cable Information**

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)
140	140	12	dapa	48000		
		1	eei	Low Profile Platform		
130	130	12	dapa	48000		
		1	eei	Low Profile Platform		
120	120	12	dapa	48000		
		1	eei	Low Profile Platform		
110	110	12	dapa	48000		
		1	eei	Low Profile Platform		
100	100	12	dapa	48000		
		1	eei	Low Profile Platform		
75	75	1		GPS		

### 3) ANALYSIS PROCEDURE

**Table 4 - Documents Provided**

Document	Remarks	Reference	Source
Online Application	Sprint PCS Co-Locate Revision #1	245874	CCIsites
Tower Drawing	EI Drawing No. GS55077	2207700	CCIsites
Foundation Drawing	EI Drawing No. 12364-140	2208511	CCIsites
Geotechnical Report	Clarence Welti Assoc., Inc. Report Dated 'February 16, 2004'	2245154	CCIsites
Rework Drawings	B&T Project No. 88674.001.01	4024239	CCIsites

#### 3.1) Analysis Method

tnxTower (version 6.1.4.1), a commercially available analysis software package, was used to create a three-dimensional model of the tower and calculate member stresses for various loading cases. Selected output from the analysis is included in Appendix A. Crown Castle's CCIplate 1.5 analysis tool was used to evaluate the anchor bolts, base plate, and any flange splices.

#### 3.2) Assumptions

- 1) Tower and structures were built in accordance with the manufacturer's specifications.
- 2) The tower and structures have been maintained in accordance with the manufacturer's specification.
- 3) The configuration of antennas, transmission cables, mounts and other appurtenances are as specified in Tables 1 and 2 and the referenced drawings.
- 4) When applicable, transmission cables are considered as structural components for calculating wind loads as allowed by TIA/EIA-222-F.

This analysis may be affected if any assumptions are not valid or have been made in error. Vertical Structures, Inc. should be notified to determine the effect on the structural integrity of the tower.

#### 4) ANALYSIS RESULTS

**Table 5 - Section Capacity (Summary)**

Section No.	Elevation (ft)	Component Type	Size	Critical Element	P (lb)	SF*P_allow (lb)	% Capacity	Pass / Fail
L1	139.5 - 93.04	Pole	TP26.99x15.5x0.25	1	-8116.56	1063078.12	94.9	Pass
L2	93.04 - 46.38	Pole	TP37.91x25.5205x0.375	2	-17126.70	2242999.02	92.2	Pass
L3	46.38 - 0	Pole	TP48.5x35.874x0.375	3	-25416.60	2682355.80	98.6	Pass
							Summary	
						Pole (L3)	98.6	Pass
						Rating =	98.6	Pass

**Table 6 - Tower Component Stresses vs. Capacity – LC7**

Notes	Component	Elevation (ft)	% Capacity	Pass / Fail
1	Anchor Rods	0	76.3	Pass
1	Base Plate	0	65.8	Pass
1	Base Foundation Soil Interaction	0	87.6	Pass

<b>Structure Rating (max from all components) =</b>	<b>98.6%</b>
---	--------------

Notes:

- 1) See additional documentation in "Appendix C – Additional Calculations" for calculations supporting the % capacity.
- 2) Capacities up to 105% are considered acceptable based on analysis methods used.

#### 4.1) Recommendations

N/A

**APPENDIX A**  
**TNXTOWER OUTPUT**

**DESIGNED APPURTENANCE LOADING**

TYPE	ELEVATION	TYPE	ELEVATION
T-Arm Mount [TA 702-3]	136	APXVTM14-C-120 w/ Mount Pipe (Sprint PCS)	130
800 10121 w/ mount pipe	136	TD-RRH8x20-25 BTS (Sprint PCS)	130
800 10121 w/ mount pipe	136	TD-RRH8x20-25 BTS (Sprint PCS)	130
800 10121 w/ mount pipe	136	TD-RRH8x20-25 BTS (Sprint PCS)	130
P65-16-XLH-RR w/ Mount Pipe	136	A-ANT-23G-2-C (VSI)	130
P65-16-XLH-RR w/ Mount Pipe	136	VHLP2-11	130
RRUS-11 BTS	136	Side Arm Mount [SO 102-1]	120
RRUS-11 BTS	136	TMA-DB-T1-6Z-8AB-0Z w/ Mount Pipe	120
RRUS-11 BTS	136	(2) DB846F65ZAXY w/Mount Pipe	118
DC6-48-60-18-8F	136	(2) DB846F65ZAXY w/Mount Pipe	118
(2) LGP21401 TMA (VSI)	136	MG D3-800Tx w/ Mount Pipe	118
(2) LGP21401 TMA (VSI)	136	MG D3-800Tx w/ Mount Pipe	118
(2) LGP21401 TMA (VSI)	136	MG D3-800Tx w/ Mount Pipe	118
Side Arm Mount [SO 102-3] (Sprint PCS)	132	(2) FD9R6004/2C-3L Diplexer	118
1900MHz RRH (65MHz) TMA (Sprint PCS)	132	(2) FD9R6004/2C-3L Diplexer	118
1900MHz RRH (65MHz) TMA (Sprint PCS)	132	BXA-171063-8BF-EDIN-0 w/ Mount Pipe	118
1900MHz RRH (65MHz) TMA (Sprint PCS)	132	BXA-171063-8BF-EDIN-0 w/ Mount Pipe	118
800MHZ RRH TMA (Sprint PCS)	132	BXA-171063-8BF-EDIN-0 w/ Mount Pipe	118
800MHZ RRH TMA (Sprint PCS)	132	BXA-70063-6CF-EDIN-0 w/ Mount Pipe	118
800MHZ RRH TMA (Sprint PCS)	132	BXA-70063-6CF-EDIN-0 w/ Mount Pipe	118
APXVSPP18-C-A20 w/ Mount Pipe (Sprint PCS)	130	BXA-70063-6CF-EDIN-0 w/ Mount Pipe	118
APXVSPP18-C-A20 w/ Mount Pipe (Sprint PCS)	130	BXA-70063-6CF-EDIN-0 w/ Mount Pipe	118
APXVSPP18-C-A20 w/ Mount Pipe (Sprint PCS)	130	RRH2X40-AWS BTS	118
800 External Notch Filter (Sprint PCS)	130	RRH2X40-AWS BTS	118
800 External Notch Filter (Sprint PCS)	130	T-Arm Mount [TA 602-3]	118
800 External Notch Filter (Sprint PCS)	130	(2) DB846F65ZAXY w/Mount Pipe	118
(3) ACU-A20-N Diplexer (Sprint PCS)	130	AIR 21 B2A B4P w/ Mount Pipe	108
(3) ACU-A20-N Diplexer (Sprint PCS)	130	AIR 21 B2A B4P w/ Mount Pipe	108
(3) ACU-A20-N Diplexer (Sprint PCS)	130	KRY 112 144/1 TMA (VSI)	108
LLPX310R w/ Mount Pipe	130	KRY 112 144/1 TMA (VSI)	108
LLPX310R w/ Mount Pipe	130	(3) 7x2" Antenna Mount Pipe	108
FDD_R6_RRH TMA	130	(3) 7x2" Antenna Mount Pipe	108
FDD_R6_RRH TMA	130	(3) 7x2" Antenna Mount Pipe	108
FDD_R6_RRH TMA	130	T-Arm Mount [TA 602-3]	108
6x4" Pipe Mount (Sprint PCS)	130	AIR 21 B2A B4P w/ Mount Pipe	108
6x4" Pipe Mount (Sprint PCS)	130	APXV18-206517-C w/Mount Pipe	100
12" (4" Tube) T-Arm (3) (Sprint PCS)	130	APXV18-206517-C w/Mount Pipe	100
APXVTM14-C-120 w/ Mount Pipe (Sprint PCS)	130	Side Arm Mount [SO 701-1] (Sprint PCS)	75
APXVTM14-C-120 w/ Mount Pipe (Sprint PCS)	130	KS24019-L112A (Sprint PCS)	75



**MATERIAL STRENGTH**

GRADE	Fy	Fu	GRADE	Fy	Fu
A572-65	65 ksi	80 ksi			

**TOWER DESIGN NOTES**

1. Tower is located in New Haven County, Connecticut.
2. Tower designed for a 85 mph basic wind in accordance with the TIA/EIA-222-F Standard.
3. Tower is also designed for a 38 mph basic wind with 0.75 in ice. Ice is considered to increase in thickness with height.
4. Deflections are based upon a 50 mph wind.
5. TOWER RATING: 98.6%

Section	1	2	3
Length (ft)	46.46	50.58	51.63
Number of Sides	18	18	18
Thickness (in)	0.2500	0.3750	0.3750
Socket Length (ft)	3.92	5.25	
Top Dia (in)	15.5000	25.5205	35.8740
Bot Dia (in)	26.9900	37.9100	48.5000
Grade		A572-65	
Weight (lb)	2633.8	6420.3	8743.3



<b>Vertical Structures, Inc.</b> 309 Spangler Drive, Suite E Richmond, KY 40475 Phone: (859) 624-8360 FAX: (859) 624-8369	Job: <b>Rogers Property, CT BU#881541</b>
	Project: <b>Vertical Structures Job No. 2014-004-024</b>
	Client: Crown Castle      Drawn by: Bryce Collins      App'd:
	Code: TIA/EIA-222-F      Date: 06/11/14      Scale: NTS
Path: Wnas1\BCollins\2014-003-024 Rogers Property, CT\TXN\881541.eri	Dwg No. <b>E-1</b>



<b>tnxTower</b>  <b>Vertical Structures, Inc.</b> 309 Spangler Drive, Suite E Richmond, KY 40475 Phone: (859) 624-8360 FAX: (859) 624-8369	<b>Job</b>	Rogers Property, CT BU#881541	<b>Page</b>	1 of 13
	<b>Project</b>	Vertical Structures Job No. 2014-004-024	<b>Date</b>	15:12:46 06/11/14
	<b>Client</b>	Crown Castle	<b>Designed by</b>	Bryce Collins

## Tower Input Data

There is a pole section.

This tower is designed using the TIA/EIA-222-F standard.

The following design criteria apply:

Tower is located in New Haven County, Connecticut.

Basic wind speed of 85 mph.

Nominal ice thickness of 0.7500 in.

Ice thickness is considered to increase with height.

Ice density of 56 pcf.

A wind speed of 38 mph is used in combination with ice.

Temperature drop of 50 °F.

Deflections calculated using a wind speed of 50 mph.

A non-linear (P-delta) analysis was used.

Pressures are calculated at each section.

Stress ratio used in pole design is 1.333.

Local bending stresses due to climbing loads, feed line supports, and appurtenance mounts are not considered.

## Options

- |  |  |   |
|--|--|---|
| <ul style="list-style-type: none"> <li>Consider Moments - Legs</li> <li>Consider Moments - Horizontals</li> <li>Consider Moments - Diagonals</li> <li>Use Moment Magnification</li> <li>√ Use Code Stress Ratios</li> <li>√ Use Code Safety Factors - Guys</li> <li>√ Escalate Ice</li> <li>Always Use Max Kz</li> <li>Use Special Wind Profile</li> <li>√ Include Bolts In Member Capacity</li> <li>√ Leg Bolts Are At Top Of Section</li> <li>√ Secondary Horizontal Braces Leg</li> <li>Use Diamond Inner Bracing (4 Sided)</li> <li>Add IBC .6D+W Combination</li> </ul> | <ul style="list-style-type: none"> <li>Distribute Leg Loads As Uniform</li> <li>Assume Legs Pinned</li> <li>√ Assume Rigid Index Plate</li> <li>√ Use Clear Spans For Wind Area</li> <li>√ Use Clear Spans For KL/r</li> <li>Retention Guys To Initial Tension</li> <li>√ Bypass Mast Stability Checks</li> <li>√ Use Azimuth Dish Coefficients</li> <li>√ Project Wind Area of Appurt.</li> <li>√ Autocalc Torque Arm Areas</li> <li>√ SR Members Have Cut Ends</li> <li>Sort Capacity Reports By Component</li> <li>√ Triangulate Diamond Inner Bracing</li> <li>Use TIA-222-G Tension Splice Capacity</li> <li>Exemption</li> </ul> | <ul style="list-style-type: none"> <li>Treat Feedline Bundles As Cylinder</li> <li>Use ASCE 10 X-Brace Ly Rules</li> <li>√ Calculate Redundant Bracing Forces</li> <li>Ignore Redundant Members in FEA</li> <li>√ SR Leg Bolts Resist Compression</li> <li>√ All Leg Panels Have Same Allowable</li> <li>Offset Girt At Foundation</li> <li>√ Consider Feedline Torque</li> <li>Include Angle Block Shear Check</li> <li style="text-align: center;">Poles</li> <li>Include Shear-Torsion Interaction</li> <li>Always Use Sub-Critical Flow</li> <li>Use Top Mounted Sockets</li> </ul> |
|--|--|---|

## Tapered Pole Section Geometry

Section	Elevation <i>ft</i>	Section Length <i>ft</i>	Splice Length <i>ft</i>	Number of Sides	Top Diameter <i>in</i>	Bottom Diameter <i>in</i>	Wall Thickness <i>in</i>	Bend Radius <i>in</i>	Pole Grade
L1	139.50-93.04	46.46	3.92	18	15.5000	26.9900	0.2500	1.0000	A572-65 (65 ksi)
L2	93.04-46.38	50.58	5.25	18	25.5205	37.9100	0.3750	1.5000	A572-65 (65 ksi)
L3	46.38-0.00	51.63		18	35.8740	48.5000	0.3750	1.5000	A572-65 (65 ksi)

<b>tnxTower</b>  <b>Vertical Structures, Inc.</b> 309 Spangler Drive, Suite E Richmond, KY 40475 Phone: (859) 624-8360 FAX: (859) 624-8369	<b>Job</b> Rogers Property, CT BU#881541	<b>Page</b> 2 of 13
	<b>Project</b> Vertical Structures Job No. 2014-004-024	<b>Date</b> 15:12:46 06/11/14
	<b>Client</b> Crown Castle	<b>Designed by</b> Bryce Collins

### Tapered Pole Properties

Section	Tip Dia. in	Area in <sup>2</sup>	I in <sup>4</sup>	r in	C in	I/C in <sup>3</sup>	J in <sup>4</sup>	It/Q in <sup>2</sup>	w in	w/t
L1	15.7391	12.1009	355.5445	5.4138	7.8740	45.1542	711.5567	6.0516	2.2880	9.152
	27.4064	21.2182	1916.7638	9.4927	13.7109	139.7983	3836.0497	10.6111	4.3102	17.241
L2	26.8892	29.9295	2390.8862	8.9267	12.9644	184.4188	4784.9184	14.9676	3.8316	10.218
	38.4948	44.6760	7952.1562	13.3249	19.2583	412.9214	15914.7760	22.3423	6.0122	16.032
L3	37.7311	42.2527	6727.0540	12.6022	18.2240	369.1315	13462.9597	21.1304	5.6538	15.077
	49.2482	57.2808	16760.5346	17.0844	24.6380	680.2717	33543.1232	28.6458	7.8760	21.003

Tower Elevation	Gusset Area (per face)	Gusset Thickness	Gusset Grade	Adjust. Factor A <sub>f</sub>	Adjust. Factor A <sub>r</sub>	Weight Mult.	Double Angle Stitch Bolt Spacing Diagonals	Double Angle Stitch Bolt Spacing Horizontals
ft	ft <sup>2</sup>	in					in	in
L1 139.50-93.04				1	1	1		
L2 93.04-46.38				1	1	1		
L3 46.38-0.00				1	1	1		

### Feed Line/Linear Appurtenances - Entered As Area

Description	Face or Leg	Allow Shield	Component Type	Placement ft	Total Number	C <sub>A</sub> A <sub>A</sub> ft <sup>2</sup> /ft	Weight plf
LDF7-50A (1-5/8 FOAM)	B	No	Inside Pole	139.50 - 0.00	6	No Ice	0.82
						1/2" Ice	0.82
						1" Ice	0.82
						2" Ice	0.82
						4" Ice	0.82
FB-L98-002-XXX (3/8")	B	No	Inside Pole	139.50 - 0.00	2	No Ice	0.10
						1/2" Ice	0.10
						1" Ice	0.10
						2" Ice	0.10
						4" Ice	0.10
WR-VG86ST-BRD (Power Cable)	B	No	Inside Pole	139.50 - 0.00	1	No Ice	0.15
						1/2" Ice	0.15
						1" Ice	0.15
						2" Ice	0.15
						4" Ice	0.15
LDF4-50A (1/2 FOAM) (Sprint PCS)	B	No	Inside Pole	132.00 - 0.00	1	No Ice	0.15
						1/2" Ice	0.15
						1" Ice	0.15
						2" Ice	0.15
						4" Ice	0.15
LDF4-50A (1/2 FOAM)	B	No	CaAa (Out Of Face)	132.00 - 0.00	2	No Ice	0.15
						1/2" Ice	0.84
						1" Ice	2.14
						2" Ice	6.58
						4" Ice	22.78
9207(5/16")	B	No	Inside Pole	132.00 - 0.00	3	No Ice	0.06
						1/2" Ice	0.06
						1" Ice	0.06
						2" Ice	0.06
						4" Ice	0.06
2" Rigid Conduit	B	No	CaAa (Out Of	132.00 - 0.00	2	No Ice	2.80

<b>tnxTower</b>  <b>Vertical Structures, Inc.</b> 309 Spangler Drive, Suite E Richmond, KY 40475 Phone: (859) 624-8360 FAX: (859) 624-8369	<b>Job</b>	Rogers Property, CT BU#881541	<b>Page</b>	3 of 13
	<b>Project</b>	Vertical Structures Job No. 2014-004-024	<b>Date</b>	15:12:46 06/11/14
	<b>Client</b>	Crown Castle	<b>Designed by</b>	Bryce Collins

Description	Face or Leg	Allow Shield	Component Type	Placement ft	Total Number	C <sub>AA</sub>	Weight plf	
			Face)					
						1/2" Ice	0.15	4.33
						1" Ice	0.20	6.47
						2" Ice	0.30	12.57
						4" Ice	0.50	32.12
HB114-1-0813U4-M5J (1-1/4") (Sprint PCS)	B	No	Inside Pole	130.00 - 0.00	4	No Ice	0.00	0.66
						1/2" Ice	0.00	0.66
						1" Ice	0.00	0.66
						2" Ice	0.00	0.66
						4" Ice	0.00	0.66
LDF7-50A (1-5/8 FOAM)	B	No	Inside Pole	124.00 - 0.00	6	No Ice	0.00	0.82
						1/2" Ice	0.00	0.82
						1" Ice	0.00	0.82
						2" Ice	0.00	0.82
						4" Ice	0.00	0.82
561 (1-5/8 AIR)	B	No	Inside Pole	118.00 - 0.00	12	No Ice	0.00	1.35
						1/2" Ice	0.00	1.35
						1" Ice	0.00	1.35
						2" Ice	0.00	1.35
						4" Ice	0.00	1.35
HB158-1-08U8-S8J18 (1 5/8")	B	No	CaAa (Out Of Face)	118.00 - 0.00	1	No Ice	0.20	0.80
						1/2" Ice	0.30	2.31
						1" Ice	0.40	4.44
						2" Ice	0.60	10.52
						4" Ice	1.00	30.02
LDF7-50A (1-5/8 FOAM)	B	No	Inside Pole	109.00 - 0.00	12	No Ice	0.00	0.82
						1/2" Ice	0.00	0.82
						1" Ice	0.00	0.82
						2" Ice	0.00	0.82
						4" Ice	0.00	0.82
MLE Hybrid 9Power/18Fiber RL 2 (1.625" Cable)	B	No	CaAa (Out Of Face)	109.00 - 0.00	1	No Ice	0.16	0.63
						1/2" Ice	0.26	1.92
						1" Ice	0.36	3.83
						2" Ice	0.56	9.48
						4" Ice	0.96	28.11
LDF7-50A (1-5/8 FOAM)	B	No	Inside Pole	100.00 - 0.00	6	No Ice	0.00	0.82
						1/2" Ice	0.00	0.82
						1" Ice	0.00	0.82
						2" Ice	0.00	0.82
						4" Ice	0.00	0.82
LDF4-50A (1/2 FOAM) (Sprint PCS)	B	No	Inside Pole	77.00 - 0.00	1	No Ice	0.00	0.15
						1/2" Ice	0.00	0.15
						1" Ice	0.00	0.15
						2" Ice	0.00	0.15
						4" Ice	0.00	0.15

### Feed Line/Linear Appurtenances Section Areas

Tower Section	Tower Elevation ft	Face	A <sub>R</sub> ft <sup>2</sup>	A <sub>F</sub> ft <sup>2</sup>	C <sub>AA</sub> In Face ft <sup>2</sup>	C <sub>AA</sub> Out Face ft <sup>2</sup>	Weight lb
L1	139.50-93.04	A	0.000	0.000	0.000	0.000	0.00
		B	0.000	0.000	0.000	15.328	1363.05
		C	0.000	0.000	0.000	0.000	0.00
L2	93.04-46.38	A	0.000	0.000	0.000	0.000	0.00
		B	0.000	0.000	0.000	26.153	2405.02
		C	0.000	0.000	0.000	0.000	0.00
L3	46.38-0.00	A	0.000	0.000	0.000	0.000	0.00
		B	0.000	0.000	0.000	25.996	2392.98

<b>tnxTower</b>  <b>Vertical Structures, Inc.</b> 309 Spangler Drive, Suite E Richmond, KY 40475 Phone: (859) 624-8360 FAX: (859) 624-8369	<b>Job</b>	Rogers Property, CT BU#881541	<b>Page</b>	4 of 13
	<b>Project</b>	Vertical Structures Job No. 2014-004-024	<b>Date</b>	15:12:46 06/11/14
	<b>Client</b>	Crown Castle	<b>Designed by</b>	Bryce Collins

Tower Section	Tower Elevation ft	Face	A <sub>R</sub> ft <sup>2</sup>	A <sub>F</sub> ft <sup>2</sup>	C <sub>AA</sub> In Face ft <sup>2</sup>	C <sub>AA</sub> Out Face ft <sup>2</sup>	Weight lb
		C	0.000	0.000	0.000	0.000	0.00

### Feed Line/Linear Appurtenances Section Areas - With Ice

Tower Section	Tower Elevation ft	Face or Leg	Ice Thickness in	A <sub>R</sub> ft <sup>2</sup>	A <sub>F</sub> ft <sup>2</sup>	C <sub>AA</sub> In Face ft <sup>2</sup>	C <sub>AA</sub> Out Face ft <sup>2</sup>	Weight lb
L1	139.50-93.04	A	0.871	0.000	0.000	0.000	0.000	0.00
		B		0.000	0.000	0.000	29.239	1855.01
		C		0.000	0.000	0.000	0.000	0.00
L2	93.04-46.38	A	0.819	0.000	0.000	0.000	0.000	0.00
		B		0.000	0.000	0.000	50.531	3120.79
		C		0.000	0.000	0.000	0.000	0.00
L3	46.38-0.00	A	0.750	0.000	0.000	0.000	0.000	0.00
		B		0.000	0.000	0.000	48.794	3052.32
		C		0.000	0.000	0.000	0.000	0.00

### Feed Line Center of Pressure

Section	Elevation ft	CP <sub>x</sub> in	CP <sub>z</sub> in	CP <sub>x</sub> Ice in	CP <sub>z</sub> Ice in
L1	139.50-93.04	0.3947	0.2279	0.6223	0.3593
L2	93.04-46.38	0.6023	0.3477	0.9651	0.5572
L3	46.38-0.00	0.6293	0.3633	1.0252	0.5919

### Discrete Tower Loads

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment °	Placement ft	C <sub>AA</sub> Front ft <sup>2</sup>	C <sub>AA</sub> Side ft <sup>2</sup>	Weight lb	
T-Arm Mount [TA 702-3]	A	None		0.0000	136.00	No Ice	5.64	5.64	339.00
						1/2" Ice	6.55	6.55	429.00
						1" Ice	7.46	7.46	519.00
						2" Ice	9.28	9.28	699.00
						4" Ice	12.92	12.92	1059.00
800 10121 w/ mount pipe	A	From Centroid-Face	4.00 0.00 4.00	10.0000	136.00	No Ice	5.80	4.71	66.00
						1/2" Ice	6.34	5.56	114.74
						1" Ice	6.86	6.28	169.92
						2" Ice	7.94	7.81	302.91
						4" Ice	10.23	11.23	689.93
800 10121 w/ mount pipe	B	From Centroid-Face	4.00 0.00 4.00	0.0000	136.00	No Ice	5.80	4.71	66.00
						1/2" Ice	6.34	5.56	114.74
						1" Ice	6.86	6.28	169.92
						2" Ice	7.94	7.81	302.91

<b>tnxTower</b>  <b>Vertical Structures, Inc.</b> 309 Spangler Drive, Suite E Richmond, KY 40475 Phone: (859) 624-8360 FAX: (859) 624-8369	<b>Job</b>	Rogers Property, CT BU#881541	<b>Page</b>	5 of 13
	<b>Project</b>	Vertical Structures Job No. 2014-004-024	<b>Date</b>	15:12:46 06/11/14
	<b>Client</b>	Crown Castle	<b>Designed by</b>	Bryce Collins

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C <sub>AA</sub>		Weight	
			Horz	Lateral			Front	Side		
			ft	ft	°	ft	ft <sup>2</sup>	ft <sup>2</sup>	lb	
800 10121 w/ mount pipe	C	From Centroid-Fa ce	4.00		-10.0000	136.00	4" Ice	10.23	11.23	689.93
			0.00				No Ice	5.80	4.71	66.00
			4.00				1/2" Ice	6.34	5.56	114.74
							1" Ice	6.86	6.28	169.92
							2" Ice	7.94	7.81	302.91
P65-16-XLH-RR w/ Mount Pipe	A	From Centroid-Fa ce	4.00		30.0000	136.00	4" Ice	10.23	11.23	689.93
			0.00				No Ice	8.88	6.60	82.20
			4.00				1/2" Ice	9.63	7.88	150.58
							1" Ice	10.36	9.00	227.07
							2" Ice	11.75	10.93	408.37
P65-16-XLH-RR w/ Mount Pipe	B	From Centroid-Fa ce	4.00		30.0000	136.00	4" Ice	14.66	15.02	921.72
			0.00				No Ice	8.88	6.60	82.20
			4.00				1/2" Ice	9.63	7.88	150.58
							1" Ice	10.36	9.00	227.07
							2" Ice	11.75	10.93	408.37
P65-16-XLH-RR w/ Mount Pipe	C	From Centroid-Fa ce	4.00		30.0000	136.00	4" Ice	14.66	15.02	921.72
			0.00				No Ice	8.88	6.60	82.20
			4.00				1/2" Ice	9.63	7.88	150.58
							1" Ice	10.36	9.00	227.07
							2" Ice	11.75	10.93	408.37
RRUS-11 BTS	A	From Centroid-Fa ce	4.00		30.0000	136.00	4" Ice	14.66	15.02	921.72
			0.00				No Ice	4.42	1.19	55.00
			4.00				1/2" Ice	4.71	1.35	80.77
							1" Ice	5.00	1.53	109.98
							2" Ice	5.61	1.90	179.45
RRUS-11 BTS	B	From Centroid-Fa ce	4.00		30.0000	136.00	4" Ice	6.94	2.75	368.09
			0.00				No Ice	4.42	1.19	55.00
			4.00				1/2" Ice	4.71	1.35	80.77
							1" Ice	5.00	1.53	109.98
							2" Ice	5.61	1.90	179.45
RRUS-11 BTS	C	From Centroid-Fa ce	4.00		30.0000	136.00	4" Ice	6.94	2.75	368.09
			0.00				No Ice	4.42	1.19	55.00
			4.00				1/2" Ice	4.71	1.35	80.77
							1" Ice	5.00	1.53	109.98
							2" Ice	5.61	1.90	179.45
DC6-48-60-18-8F	C	From Centroid-Fa ce	4.00		30.0000	136.00	4" Ice	6.94	2.75	368.09
			0.00				No Ice	2.57	4.32	18.90
			4.00				1/2" Ice	2.80	4.60	50.21
							1" Ice	3.04	4.88	85.17
							2" Ice	3.54	5.49	166.87
(2) LGP21401 TMA (VSI)	A	From Centroid-Fa ce	4.00		10.0000	136.00	4" Ice	4.66	6.80	382.77
			0.00				No Ice	1.29	0.36	14.10
			4.00				1/2" Ice	1.45	0.48	21.26
							1" Ice	1.61	0.60	30.32
							2" Ice	1.97	0.87	54.89
(2) LGP21401 TMA (VSI)	B	From Centroid-Fa ce	4.00		0.0000	136.00	4" Ice	2.79	1.52	135.29
			0.00				No Ice	1.29	0.36	14.10
			4.00				1/2" Ice	1.45	0.48	21.26
							1" Ice	1.61	0.60	30.32
							2" Ice	1.97	0.87	54.89
(2) LGP21401 TMA (VSI)	C	From Centroid-Fa ce	4.00		-10.0000	136.00	4" Ice	2.79	1.52	135.29
			0.00				No Ice	1.29	0.36	14.10
			4.00				1/2" Ice	1.45	0.48	21.26
							1" Ice	1.61	0.60	30.32
							2" Ice	1.97	0.87	54.89
				4" Ice	2.79	1.52	135.29			

\*\*

<b>Job</b>	Rogers Property, CT BU#881541	<b>Page</b>	6 of 13
<b>Project</b>	Vertical Structures Job No. 2014-004-024	<b>Date</b>	15:12:46 06/11/14
<b>Client</b>	Crown Castle	<b>Designed by</b>	Bryce Collins

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C <sub>AA</sub> Front	C <sub>AA</sub> Side	Weight						
			Horz	Lateral						Vert	ft	ft	ft	ft	ft
			ft	ft	°	ft	ft <sup>2</sup>	ft <sup>2</sup>	lb						
12' (4" Tube) T-Arm (3) (Sprint PCS)	C	None			0.0000	130.00	No Ice 13.50 1/2" Ice 16.71 1" Ice 19.92 2" Ice 26.34 4" Ice 39.18	No Ice 13.50 1/2" Ice 16.71 1" Ice 19.92 2" Ice 26.34 4" Ice 39.18	600.00 750.00 900.00 1200.00 1800.00						
APXVTM14-C-120 w/ Mount Pipe (Sprint PCS)	A	From Centroid-Fa ce	4.75 2.75 0.00		10.0000	130.00	No Ice 7.68 1/2" Ice 8.48 1" Ice 9.21 2" Ice 10.57 4" Ice 13.43	No Ice 5.51 1/2" Ice 6.69 1" Ice 7.73 2" Ice 9.54 4" Ice 13.47	82.20 142.82 210.60 371.59 832.80						
APXVTM14-C-120 w/ Mount Pipe (Sprint PCS)	B	From Centroid-Fa ce	4.75 2.75 0.00		20.0000	130.00	No Ice 7.68 1/2" Ice 8.48 1" Ice 9.21 2" Ice 10.57 4" Ice 13.43	No Ice 5.51 1/2" Ice 6.69 1" Ice 7.73 2" Ice 9.54 4" Ice 13.47	82.20 142.82 210.60 371.59 832.80						
APXVTM14-C-120 w/ Mount Pipe (Sprint PCS)	C	From Centroid-Fa ce	4.75 2.75 0.00		-20.0000	130.00	No Ice 7.68 1/2" Ice 8.48 1" Ice 9.21 2" Ice 10.57 4" Ice 13.43	No Ice 5.51 1/2" Ice 6.69 1" Ice 7.73 2" Ice 9.54 4" Ice 13.47	82.20 142.82 210.60 371.59 832.80						
TD-RRH8x20-25 BTS (Sprint PCS)	A	From Centroid-Fa ce	4.75 2.75 0.00		10.0000	130.00	No Ice 4.72 1/2" Ice 5.01 1" Ice 5.32 2" Ice 5.95 4" Ice 7.31	No Ice 1.70 1/2" Ice 1.92 1" Ice 2.15 2" Ice 2.62 4" Ice 3.68	70.00 97.15 127.83 200.54 396.84						
TD-RRH8x20-25 BTS (Sprint PCS)	B	From Centroid-Fa ce	4.75 2.75 0.00		20.0000	130.00	No Ice 4.72 1/2" Ice 5.01 1" Ice 5.32 2" Ice 5.95 4" Ice 7.31	No Ice 1.70 1/2" Ice 1.92 1" Ice 2.15 2" Ice 2.62 4" Ice 3.68	70.00 97.15 127.83 200.54 396.84						
TD-RRH8x20-25 BTS (Sprint PCS)	C	From Centroid-Fa ce	4.75 2.75 0.00		-20.0000	130.00	No Ice 4.72 1/2" Ice 5.01 1" Ice 5.32 2" Ice 5.95 4" Ice 7.31	No Ice 1.70 1/2" Ice 1.92 1" Ice 2.15 2" Ice 2.62 4" Ice 3.68	70.00 97.15 127.83 200.54 396.84						
APXVSPP18-C-A20 w/ Mount Pipe (Sprint PCS)	A	From Centroid-Fa ce	4.75 2.75 0.00		10.0000	130.00	No Ice 8.50 1/2" Ice 9.15 1" Ice 9.77 2" Ice 11.03 4" Ice 13.68	No Ice 6.95 1/2" Ice 8.13 1" Ice 9.02 2" Ice 10.84 4" Ice 14.85	82.55 150.56 226.53 405.98 908.95						
APXVSPP18-C-A20 w/ Mount Pipe (Sprint PCS)	B	From Centroid-Fa ce	4.75 2.75 0.00		20.0000	130.00	No Ice 8.50 1/2" Ice 9.15 1" Ice 9.77 2" Ice 11.03 4" Ice 13.68	No Ice 6.95 1/2" Ice 8.13 1" Ice 9.02 2" Ice 10.84 4" Ice 14.85	82.55 150.56 226.53 405.98 908.95						
APXVSPP18-C-A20 w/ Mount Pipe (Sprint PCS)	C	From Centroid-Fa ce	4.75 2.75 0.00		-20.0000	130.00	No Ice 8.50 1/2" Ice 9.15 1" Ice 9.77 2" Ice 11.03 4" Ice 13.68	No Ice 6.95 1/2" Ice 8.13 1" Ice 9.02 2" Ice 10.84 4" Ice 14.85	82.55 150.56 226.53 405.98 908.95						
800 External Notch Filter (Sprint PCS)	A	From Centroid-Fa ce	4.75 2.75 0.00		10.0000	130.00	No Ice 0.77 1/2" Ice 0.89 1" Ice 1.02 2" Ice 1.30 4" Ice 1.97	No Ice 0.37 1/2" Ice 0.46 1" Ice 0.56 2" Ice 0.79 4" Ice 1.34	11.00 16.81 24.26 44.81 114.01						
800 External Notch Filter (Sprint PCS)	B	From Centroid-Fa	4.75 2.75		20.0000	130.00	No Ice 0.77 1/2" Ice 0.89	No Ice 0.37 1/2" Ice 0.46	11.00 16.81						

<b>tnxTower</b>  <b>Vertical Structures, Inc.</b> 309 Spangler Drive, Suite E Richmond, KY 40475 Phone: (859) 624-8360 FAX: (859) 624-8369	<b>Job</b>	Rogers Property, CT BU#881541	<b>Page</b>	7 of 13
	<b>Project</b>	Vertical Structures Job No. 2014-004-024	<b>Date</b>	15:12:46 06/11/14
	<b>Client</b>	Crown Castle	<b>Designed by</b>	Bryce Collins

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment °	Placement ft	C <sub>AA</sub> Front ft <sup>2</sup>	C <sub>AA</sub> Side ft <sup>2</sup>	Weight lb	
			Horz ft	Lateral ft						
		ce	0.00							
						1" Ice	1.02	0.56	24.26	
						2" Ice	1.30	0.79	44.81	
						4" Ice	1.97	1.34	114.01	
800 External Notch Filter (Sprint PCS)	C	From Centroid-Fa ce	4.75 2.75 0.00	-20.0000		130.00	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	0.77 0.89 1.02 1.30 1.97	0.37 0.46 0.56 0.79 1.34	11.00 16.81 24.26 44.81 114.01
(3) ACU-A20-N Diplexer (Sprint PCS)	A	From Centroid-Fa ce	4.75 2.75 0.00	10.0000		130.00	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	0.14 0.19 0.25 0.40 0.80	0.08 0.12 0.17 0.30 0.67	1.04 2.32 4.41 11.80 44.85
(3) ACU-A20-N Diplexer (Sprint PCS)	B	From Centroid-Fa ce	4.75 2.75 0.00	20.0000		130.00	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	0.14 0.19 0.25 0.40 0.80	0.08 0.12 0.17 0.30 0.67	1.04 2.32 4.41 11.80 44.85
(3) ACU-A20-N Diplexer (Sprint PCS)	C	From Centroid-Fa ce	4.75 2.75 0.00	-20.0000		130.00	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	0.14 0.19 0.25 0.40 0.80	0.08 0.12 0.17 0.30 0.67	1.04 2.32 4.41 11.80 44.85
LLPX310R w/ Mount Pipe	A	From Centroid-Fa ce	4.75 2.75 2.00	40.0000		130.00	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	5.43 5.99 6.51 7.57 9.86	3.38 4.15 4.80 6.19 9.25	50.56 92.42 139.94 255.23 597.44
LLPX310R w/ Mount Pipe	B	From Centroid-Fa ce	4.75 2.75 2.00	10.0000		130.00	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	5.43 5.99 6.51 7.57 9.86	3.38 4.15 4.80 6.19 9.25	50.56 92.42 139.94 255.23 597.44
LLPX310R w/ Mount Pipe	C	From Centroid-Fa ce	4.75 2.75 2.00	0.0000		130.00	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	5.43 5.99 6.51 7.57 9.86	3.38 4.15 4.80 6.19 9.25	50.56 92.42 139.94 255.23 597.44
FDD_R6_RRH TMA	A	From Centroid-Fa ce	4.75 2.75 2.00	40.0000		130.00	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	1.79 1.97 2.16 2.57 3.49	0.78 0.92 1.07 1.39 2.14	33.00 44.50 58.31 93.60 200.35
FDD_R6_RRH TMA	B	From Centroid-Fa ce	4.75 2.75 2.00	10.0000		130.00	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	1.79 1.97 2.16 2.57 3.49	0.78 0.92 1.07 1.39 2.14	33.00 44.50 58.31 93.60 200.35
FDD_R6_RRH TMA	C	From Centroid-Fa ce	4.75 2.75 2.00	0.0000		130.00	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	1.79 1.97 2.16 2.57 3.49	0.78 0.92 1.07 1.39 2.14	33.00 44.50 58.31 93.60 200.35
6'x4" Pipe Mount (Sprint PCS)	B	From Centroid-Fa ce	4.75 2.75 0.00	0.0000		130.00	No Ice 1/2" Ice 1" Ice 2" Ice	2.25 2.62 3.00 3.78	2.25 2.62 3.00 3.78	65.00 84.10 107.47 167.65

<b>tnxTower</b>  <b>Vertical Structures, Inc.</b> 309 Spangler Drive, Suite E Richmond, KY 40475 Phone: (859) 624-8360 FAX: (859) 624-8369	<b>Job</b>	Rogers Property, CT BU#881541	<b>Page</b>	8 of 13
	<b>Project</b>	Vertical Structures Job No. 2014-004-024	<b>Date</b>	15:12:46 06/11/14
	<b>Client</b>	Crown Castle	<b>Designed by</b>	Bryce Collins

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C <sub>AA</sub> Front	C <sub>AA</sub> Side	Weight
			Horz	Lateral					
6'x4" Pipe Mount (Sprint PCS)	C	From Centroid-Face	4.75	0.0000	130.00	4" Ice	5.56	5.56	346.05
			2.75	0.0000		No Ice	2.25	2.25	65.00
			0.00	0.0000		1/2" Ice	2.62	2.62	84.10
				0.0000		1" Ice	3.00	3.00	107.47
				0.0000		2" Ice	3.78	3.78	167.65
					4" Ice	5.56	5.56	346.05	
**									
Side Arm Mount [SO 102-3] (Sprint PCS)	C	None		0.0000	132.00	No Ice	3.00	3.00	81.00
				0.0000		1/2" Ice	3.48	3.48	111.00
				0.0000		1" Ice	3.96	3.96	141.00
				0.0000		2" Ice	4.92	4.92	201.00
				0.0000		4" Ice	6.84	6.84	321.00
1900MHz RRH (65MHz) TMA (Sprint PCS)	A	From Centroid-Face	3.50	10.0000	132.00	No Ice	2.77	2.70	60.00
			0.00	10.0000		1/2" Ice	3.01	2.94	83.90
			0.00	10.0000		1" Ice	3.26	3.18	111.08
				10.0000		2" Ice	3.78	3.70	176.02
				10.0000		4" Ice	4.93	4.85	353.75
1900MHz RRH (65MHz) TMA (Sprint PCS)	B	From Centroid-Face	3.50	20.0000	132.00	No Ice	2.77	2.70	60.00
			0.00	20.0000		1/2" Ice	3.01	2.94	83.90
			0.00	20.0000		1" Ice	3.26	3.18	111.08
				20.0000		2" Ice	3.78	3.70	176.02
				20.0000		4" Ice	4.93	4.85	353.75
1900MHz RRH (65MHz) TMA (Sprint PCS)	C	From Centroid-Face	3.50	-20.0000	132.00	No Ice	2.77	2.70	60.00
			0.00	-20.0000		1/2" Ice	3.01	2.94	83.90
			0.00	-20.0000		1" Ice	3.26	3.18	111.08
				-20.0000		2" Ice	3.78	3.70	176.02
				-20.0000		4" Ice	4.93	4.85	353.75
800MHZ RRH TMA (Sprint PCS)	A	From Centroid-Face	3.50	10.0000	132.00	No Ice	2.49	2.07	53.00
			0.00	10.0000		1/2" Ice	2.71	2.27	74.19
			0.00	10.0000		1" Ice	2.93	2.48	98.39
				10.0000		2" Ice	3.41	2.93	156.61
				10.0000		4" Ice	4.46	3.93	317.77
800MHZ RRH TMA (Sprint PCS)	B	From Centroid-Face	3.50	20.0000	132.00	No Ice	2.49	2.07	53.00
			0.00	20.0000		1/2" Ice	2.71	2.27	74.19
			0.00	20.0000		1" Ice	2.93	2.48	98.39
				20.0000		2" Ice	3.41	2.93	156.61
				20.0000		4" Ice	4.46	3.93	317.77
800MHZ RRH TMA (Sprint PCS)	C	From Centroid-Face	3.50	-20.0000	132.00	No Ice	2.49	2.07	53.00
			0.00	-20.0000		1/2" Ice	2.71	2.27	74.19
			0.00	-20.0000		1" Ice	2.93	2.48	98.39
				-20.0000		2" Ice	3.41	2.93	156.61
				-20.0000		4" Ice	4.46	3.93	317.77
**									
Side Arm Mount [SO 102-1]	A	From Centroid-Face	3.50	0.0000	120.00	No Ice	1.50	1.50	25.00
			0.00	0.0000		1/2" Ice	1.74	1.75	35.00
			0.00	0.0000		1" Ice	1.98	2.00	45.00
				0.0000		2" Ice	2.46	2.50	65.00
				0.0000		4" Ice	3.42	3.50	105.00
TMA-DB-T1-6Z-8AB-0Z w/ Mount Pipe	A	From Centroid-Face	3.50	0.0000	120.00	No Ice	7.03	4.23	73.20
			0.00	0.0000		1/2" Ice	7.96	5.29	130.43
			0.00	0.0000		1" Ice	8.79	6.19	193.70
				0.0000		2" Ice	10.21	7.68	342.34
				0.0000		4" Ice	13.24	10.87	765.46
T-Arm Mount [TA 602-3]	C	None		0.0000	118.00	No Ice	11.59	11.59	774.30
				0.0000		1/2" Ice	15.44	15.44	990.35
				0.0000		1" Ice	19.29	19.29	1206.41
				0.0000		2" Ice	26.99	26.99	1638.52





<b>tnxTower</b>  <b>Vertical Structures, Inc.</b> 309 Spangler Drive, Suite E Richmond, KY 40475 Phone: (859) 624-8360 FAX: (859) 624-8369	<b>Job</b>	Rogers Property, CT BU#881541	<b>Page</b>	10 of 13
	<b>Project</b>	Vertical Structures Job No. 2014-004-024	<b>Date</b>	15:12:46 06/11/14
	<b>Client</b>	Crown Castle	<b>Designed by</b>	Bryce Collins

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C <sub>AA</sub> Front	C <sub>AA</sub> Side	Weight	
			Horz	Lateral						°
w/ Mount Pipe		Centroid-Fa	0.00			1/2" Ice	4.27	4.85	73.32	
		ce	0.00			1" Ice	4.80	5.59	116.47	
						2" Ice	5.93	7.12	224.03	
						4" Ice	8.34	10.52	558.26	
BXA-70063-6CF-EDIN-0 w/ Mount Pipe	A	From Centroid-Fa	6.00		-20.0000	118.00	No Ice	8.23	6.06	46.20
		ce	0.00				1/2" Ice	8.98	7.32	109.79
			0.00				1" Ice	9.70	8.44	181.31
							2" Ice	11.08	10.35	352.18
							4" Ice	13.96	14.36	842.64
BXA-70063-6CF-EDIN-0 w/ Mount Pipe	B	From Centroid-Fa	6.00		-20.0000	118.00	No Ice	8.23	6.06	46.20
		ce	0.00				1/2" Ice	8.98	7.32	109.79
			0.00				1" Ice	9.70	8.44	181.31
							2" Ice	11.08	10.35	352.18
							4" Ice	13.96	14.36	842.64
BXA-70063-6CF-EDIN-0 w/ Mount Pipe	C	From Centroid-Fa	6.00		-20.0000	118.00	No Ice	8.23	6.06	46.20
		ce	0.00				1/2" Ice	8.98	7.32	109.79
			0.00				1" Ice	9.70	8.44	181.31
							2" Ice	11.08	10.35	352.18
							4" Ice	13.96	14.36	842.64
RRH2X40-AWS BTS	A	From Centroid-Fa	6.00		-20.0000	118.00	No Ice	2.52	1.59	44.00
		ce	0.00				1/2" Ice	2.75	1.80	61.40
			0.00				1" Ice	2.99	2.01	81.69
							2" Ice	3.50	2.46	131.76
							4" Ice	4.61	3.48	275.24
RRH2X40-AWS BTS	B	From Centroid-Fa	6.00		-20.0000	118.00	No Ice	2.52	1.59	44.00
		ce	0.00				1/2" Ice	2.75	1.80	61.40
			0.00				1" Ice	2.99	2.01	81.69
							2" Ice	3.50	2.46	131.76
							4" Ice	4.61	3.48	275.24
RRH2X40-AWS BTS	C	From Centroid-Fa	6.00		-20.0000	118.00	No Ice	2.52	1.59	44.00
		ce	0.00				1/2" Ice	2.75	1.80	61.40
			0.00				1" Ice	2.99	2.01	81.69
							2" Ice	3.50	2.46	131.76
							4" Ice	4.61	3.48	275.24
**										
T-Arm Mount [TA 602-3]	C	None			0.0000	108.00	No Ice	11.59	11.59	774.30
							1/2" Ice	15.44	15.44	990.35
							1" Ice	19.29	19.29	1206.41
							2" Ice	26.99	26.99	1638.52
							4" Ice	42.39	42.39	2502.73
AIR 21 B2A B4P w/ Mount Pipe	A	From Centroid-Fa	6.00		0.0000	108.00	No Ice	7.14	5.96	117.05
		ce	0.00				1/2" Ice	7.83	7.09	177.37
			1.00				1" Ice	8.43	7.96	244.68
							2" Ice	9.66	9.72	403.93
							4" Ice	12.25	13.45	854.96
AIR 21 B2A B4P w/ Mount Pipe	B	From Centroid-Fa	6.00		0.0000	108.00	No Ice	7.14	5.96	117.05
		ce	0.00				1/2" Ice	7.83	7.09	177.37
			1.00				1" Ice	8.43	7.96	244.68
							2" Ice	9.66	9.72	403.93
							4" Ice	12.25	13.45	854.96
AIR 21 B2A B4P w/ Mount Pipe	C	From Centroid-Fa	6.00		0.0000	108.00	No Ice	7.14	5.96	117.05
		ce	0.00				1/2" Ice	7.83	7.09	177.37
			1.00				1" Ice	8.43	7.96	244.68
							2" Ice	9.66	9.72	403.93
							4" Ice	12.25	13.45	854.96
KRY 112 144/1 TMA (VSI)	A	From Centroid-Fa	6.00		0.0000	108.00	No Ice	0.41	0.19	11.02
			0.00				1/2" Ice	0.50	0.26	14.12

<b>tnxTower</b>  <b>Vertical Structures, Inc.</b> 309 Spangler Drive, Suite E Richmond, KY 40475 Phone: (859) 624-8360 FAX: (859) 624-8369	<b>Job</b>		Rogers Property, CT BU#881541		<b>Page</b>		11 of 13	
	<b>Project</b>		Vertical Structures Job No. 2014-004-024		<b>Date</b>		15:12:46 06/11/14	
	<b>Client</b>		Crown Castle		<b>Designed by</b>		Bryce Collins	

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C <sub>AA</sub> Front	C <sub>AA</sub> Side	Weight
			Horz	Lateral					
		ce	1.00						
						1" Ice	0.60	0.33	18.44
						2" Ice	0.82	0.51	31.51
						4" Ice	1.36	0.97	80.86
KRY 112 144/1 TMA (VSI)	B	From Centroid-Face	6.00	0.0000	108.00	No Ice	0.41	0.19	11.02
			0.00			1/2" Ice	0.50	0.26	14.12
			1.00			1" Ice	0.60	0.33	18.44
						2" Ice	0.82	0.51	31.51
						4" Ice	1.36	0.97	80.86
KRY 112 144/1 TMA (VSI)	C	From Centroid-Face	6.00	0.0000	108.00	No Ice	0.41	0.19	11.02
			0.00			1/2" Ice	0.50	0.26	14.12
			1.00			1" Ice	0.60	0.33	18.44
						2" Ice	0.82	0.51	31.51
						4" Ice	1.36	0.97	80.86
(3) 7x2" Antenna Mount Pipe	A	From Centroid-Face	6.00	0.0000	108.00	No Ice	1.66	1.66	26.00
			0.00			1/2" Ice	2.39	2.39	38.58
			0.00			1" Ice	2.83	2.83	55.84
						2" Ice	3.71	3.71	104.97
						4" Ice	5.58	5.58	266.00
(3) 7x2" Antenna Mount Pipe	B	From Centroid-Face	6.00	0.0000	108.00	No Ice	1.66	1.66	26.00
			0.00			1/2" Ice	2.39	2.39	38.58
			0.00			1" Ice	2.83	2.83	55.84
						2" Ice	3.71	3.71	104.97
						4" Ice	5.58	5.58	266.00
(3) 7x2" Antenna Mount Pipe	C	From Centroid-Face	6.00	0.0000	108.00	No Ice	1.66	1.66	26.00
			0.00			1/2" Ice	2.39	2.39	38.58
			0.00			1" Ice	2.83	2.83	55.84
						2" Ice	3.71	3.71	104.97
						4" Ice	5.58	5.58	266.00
**									
APXV18-206517-C w/Mount Pipe	A	From Centroid-Face	1.75	30.0000	100.00	No Ice	3.95	3.43	48.30
			1.00			1/2" Ice	4.42	4.25	84.04
			0.00			1" Ice	4.90	4.95	125.74
						2" Ice	5.93	6.40	230.26
						4" Ice	8.12	9.51	554.40
APXV18-206517-C w/Mount Pipe	B	From Centroid-Face	1.75	30.0000	100.00	No Ice	3.95	3.43	48.30
			1.00			1/2" Ice	4.42	4.25	84.04
			0.00			1" Ice	4.90	4.95	125.74
						2" Ice	5.93	6.40	230.26
						4" Ice	8.12	9.51	554.40
APXV18-206517-C w/Mount Pipe	C	From Centroid-Face	1.75	30.0000	100.00	No Ice	3.95	3.43	48.30
			1.00			1/2" Ice	4.42	4.25	84.04
			0.00			1" Ice	4.90	4.95	125.74
						2" Ice	5.93	6.40	230.26
						4" Ice	8.12	9.51	554.40
**									
Side Arm Mount [SO 701-1] (Sprint PCS)	C	From Centroid-Leg	2.75	0.0000	75.00	No Ice	0.85	1.67	65.00
			0.00			1/2" Ice	1.14	2.34	79.00
			0.00			1" Ice	1.43	3.01	93.00
						2" Ice	2.01	4.35	121.00
						4" Ice	3.17	7.03	177.00
KS24019-L112A (Sprint PCS)	C	From Centroid-Leg	4.25	0.0000	75.00	No Ice	0.10	0.10	5.00
			0.00			1/2" Ice	0.18	0.18	6.50
			2.00			1" Ice	0.26	0.26	8.00
						2" Ice	0.42	0.42	11.00
						4" Ice	0.74	0.74	17.00

<b>tnxTower</b>  <b>Vertical Structures, Inc.</b> 309 Spangler Drive, Suite E Richmond, KY 40475 Phone: (859) 624-8360 FAX: (859) 624-8369	<b>Job</b> Rogers Property, CT BU#881541	<b>Page</b> 12 of 13
	<b>Project</b> Vertical Structures Job No. 2014-004-024	<b>Date</b> 15:12:46 06/11/14
	<b>Client</b> Crown Castle	<b>Designed by</b> Bryce Collins

### Dishes

Description	Face or Leg	Dish Type	Offset Type	Offsets: Horz Lateral Vert	Azimuth Adjustment	3 dB Beam Width	Elevation	Outside Diameter	Aperture Area	Weight	
				ft	°	°	ft	ft	ft <sup>2</sup>	lb	
A-ANT-23G-2-C (VSI)	B	Paraboloid w/Shroud (HP)	From Centroid	4.75	10.0000		130.00	2.17	No Ice	3.72	12.30
			-Face	2.25					1/2" Ice	4.01	32.88
				2.00					1" Ice	4.30	53.46
									2" Ice	4.88	94.62
VHLP2-11	C	Paraboloid w/Shroud (HP)	From Centroid	4.75	-30.0000		130.00	2.17	No Ice	3.72	31.00
			-Face	2.25					1/2" Ice	4.01	51.56
				4.00					1" Ice	4.30	72.12
									2" Ice	4.88	113.24
								4" Ice	6.04	195.48	

### Compression Checks

### Pole Design Data

Section No.	Elevation	Size	L	L <sub>a</sub>	Kl/r	F <sub>a</sub>	A	Actual P	Allow. P <sub>a</sub>	Ratio P/P <sub>a</sub>
			ft	ft		ksi	in <sup>2</sup>	lb	lb	
L1	139.5 - 93.04 (1)	TP26.99x15.5x0.25	46.46	0.00	0.0	39.000	20.4489	-8116.56	797508.00	0.010
L2	93.04 - 46.38 (2)	TP37.91x25.5205x0.375	50.58	0.00	0.0	39.000	43.1454	-17126.70	1682670.00	0.010
L3	46.38 - 0 (3)	TP48.5x35.874x0.375	51.63	0.00	0.0	39.000	51.5966	-25416.60	2012270.00	0.013

### Pole Bending Design Data

Section No.	Elevation	Size	Actual M <sub>x</sub>	Actual f <sub>bx</sub>	Allow. F <sub>bx</sub>	Ratio f <sub>bx</sub> /F <sub>bx</sub>	Actual M <sub>y</sub>	Actual f <sub>by</sub>	Allow. F <sub>by</sub>	Ratio f <sub>by</sub> /F <sub>by</sub>
			lb-ft	ksi	ksi		lb-ft	ksi	ksi	
L1	139.5 - 93.04 (1)	TP26.99x15.5x0.25	529425.83	-48.945	39.000	1.255	0.00	0.000	39.000	0.000
L2	93.04 - 46.38 (2)	TP37.91x25.5205x0.375	1524183.33	-47.510	39.000	1.218	0.00	0.000	39.000	0.000
L3	46.38 - 0 (3)	TP48.5x35.874x0.375	2332641.67	-50.757	39.000	1.301	0.00	0.000	39.000	0.000

### Pole Interaction Design Data


<b>tnxTower</b>  <b>Vertical Structures, Inc.</b> 309 Spangler Drive, Suite E Richmond, KY 40475 Phone: (859) 624-8360 FAX: (859) 624-8369	<b>Job</b>	Rogers Property, CT BU#881541	<b>Page</b>	13 of 13
	<b>Project</b>	Vertical Structures Job No. 2014-004-024	<b>Date</b>	15:12:46 06/11/14
	<b>Client</b>	Crown Castle	<b>Designed by</b>	Bryce Collins

Section No.	Elevation ft	Size	Ratio $\frac{P}{P_a}$	Ratio $\frac{f_{bx}}{F_{bx}}$	Ratio $\frac{f_{by}}{F_{by}}$	Comb. Stress Ratio	Allow. Stress Ratio	Criteria
L1	139.5 - 93.04 (1)	TP26.99x15.5x0.25	0.010	1.255	0.000	1.265 ✓	1.333	H1-3 ✓
L2	93.04 - 46.38 (2)	TP37.91x25.5205x0.375	0.010	1.218	0.000	1.228 ✓	1.333	H1-3 ✓
L3	46.38 - 0 (3)	TP48.5x35.874x0.375	0.013	1.301	0.000	1.314 ✓	1.333	H1-3 ✓

### Section Capacity Table

Section No.	Elevation ft	Component Type	Size	Critical Element	P lb	SF*P <sub>allow</sub> lb	% Capacity	Pass Fail	
L1	139.5 - 93.04	Pole	TP26.99x15.5x0.25	1	-8116.56	1063078.12	94.9	Pass	
L2	93.04 - 46.38	Pole	TP37.91x25.5205x0.375	2	-17126.70	2242999.02	92.2	Pass	
L3	46.38 - 0	Pole	TP48.5x35.874x0.375	3	-25416.60	2682355.80	98.6	Pass	
							Summary		
							Pole (L3)	98.6	Pass
							<b>RATING =</b>	<b>98.6</b>	<b>Pass</b>

**APPENDIX B**  
**BASE LEVEL DRAWING**



BUSINESS UNIT: 881541 TOWER ID: C\_BASELEVEL

RJK	KKH	AM	AO	ALM	ALM	ALM	TDS	ZMK
14/04/11	AS-BUILT INFORMATION ADDED PER WORK ORDER # 402286							
30/11/11	AS-BUILT INFORMATION ADDED PER WORK ORDER # 488919							
30/05/12	APPLICATION ADDED PER WORK ORDER # 641192							
16/09/13	UPDATED PER WORK ORDER # 651329							
18/09/13	UPDATED PER WORK ORDER # 651329							
18/09/13	UPDATED PER WORK ORDER # 651674							
18/12/13	UPDATED PER WORK ORDER # 674562							
29/8/2014	UPDATED PER WORK ORDER # 72462							

DRAWN BY: VBG  
CHECKED BY: GPK  
DRAWING DATE: 23/02/08

SITE NUMBER:  
SITE NAME:  
SITE NAME

ROGERS PROPERTY  
BUSINESS UNIT NUMBER

881541  
SITE ADDRESS  
NEW HAVEN, CT 06477  
NEW HAVEN  
UNITED STATES COUNTY  
USA

SHEET TITLE

BASE LEVEL

SHEET NUMBER

PORT INFORMATION			
ELEV.	SIZE	LOCATION	STATUS
10'-0"	10"x30"	E & W	.
7'-0"	10"x30"	S	.
3'-3"	10"x30"	E & W	.

SCALE:  
1" = 1'-0"

1

BASE LEVEL DRAWING

A1-0

**APPENDIX C**  
**ADDITIONAL CALCULATIONS**



# Stiffened or Unstiffened, Ungrouted, Circular Base Plate - Any Rod Material

## TIA Rev F

### Site Data

BU#: 881541
Site Name: Rogers Property, CT
App #: 245874, Rev. 1
Pole Manufacturer: <b>Other</b>

Reactions		
Moment:	2860.812	ft-kips
Axial:	30.468	kips
Shear:	27.788	kips

### Anchor Rod Data

Qty:	16	
Diam:	2.25	in
Rod Material:	A615-J	
Strength (Fu):	100	ksi
Yield (Fy):	75	ksi
Bolt Circle:	57	in

If No stiffeners, Criteria: **AISC ASD** <-Only Applicable to Unstiffened Cases

### Anchor Rod Results

Maximum Rod Tension: 148.7 Kips  
 Allowable Tension: 195.0 Kips  
 Anchor Rod Stress Ratio: 76.3% **Pass**

Stiffened
Service, ASD
Ft*ASIF

### Plate Data

Diam:	63	in
Thick:	2	in
Grade:	60	ksi
Single-Rod B-eff:	9.62	in

### Base Plate Results

Base Plate Stress: 39.4 ksi  
 Allowable Plate Stress: 60.0 ksi  
 Base Plate Stress Ratio: 65.8% **Pass**

### Flexural Check

Stiffened
Service, ASD
0.75*Fy*ASIF
Y.L. Length:
N/A, Roark

### Stiffener Data (Welding at both sides)

Config:	1	*
Weld Type:	Both	
Groove Depth:	0.375	in **
Groove Angle:	45	degrees
Fillet H. Weld:	0.3125	in
Fillet V. Weld:	0.3125	in
Width:	6	in
Height:	15	in
Thick:	0.75	in
Notch:	0.75	in
Grade:	50	ksi
Weld str.:	70	ksi

### Stiffener Results

Horizontal Weld : 66.6% **Pass**  
 Vertical Weld: 62.3% **Pass**  
 Plate Flex+Shear, fb/Fb+(fv/Fv)^2: 24.4% **Pass**  
 Plate Tension+Shear, ft/Ft+(fv/Fv)^2: 67.4% **Pass**  
 Plate Comp. (AISC Bracket): 73.6% **Pass**

### Pole Results


Pole Punching Shear Check: 16.0% **Pass**

### Pole Data

Diam:	48.5	in
Thick:	0.375	in
Grade:	65	ksi
# of Sides:	18	"0" IF Round
Fu	80	ksi
Reinf. Fillet Weld	0	"0" if None

### Stress Increase Factor

ASIF:	1.333
-------	-------



\* 0 = none, 1 = every bolt, 2 = every 2 bolts, 3 = 2 per bolt

\*\* Note: for complete joint penetration groove welds the groove depth must be exactly 1/2 the stiffener thickness for calculation purposes



## Overtuning Calculation for Rectangular Mat Foundations (Eccentrically Loaded)

**Customer:** Crown Castle  
**Site Name:** Rogers Property, CT BU#881541  
**Job Number:** 2014-004-024  
**Tower Model:** 140' EEI Monopole  
**Date:** 6/11/2014

Soil Ultimate Bearing	8	ksf
Unit wt soil	0.125	kcf
Unit wt concrete	0.15	kcf

Mat Length (long dimension)	23	ft
Mat Width (short dimension)	23	ft
Mat Thickness	3	ft
Depth of Soil Over Mat	4	ft
Has Pedestals? (Y or N)	Y	
Pedestal Round or Square? (R or S)	S	
Number of Pedestals	1	
Pedestal Height	5	ft
Pedestal Diameter or Width	7	ft

Applied Shear	27.788	kip
Applied Axial Force	30.468	kip
Applied Moment	2860.812	k-ft

**Load Eccentricity on Pad**  
 distance from long axis = 3.5 ft  
 distance from short axis = 3.5 ft

wt. Concrete =	274.800	kip	
wt. Soil =	240.000	kip	
Shear Moment =	222.304	k-ft	
P*e =	106.638	k-ft	106.638 k-ft

	(about long axis)	(about short axis)
Allowable Bearing =	4 ksf	
Mat Width / 6 =	3.83 ft	3.83 ft
e =	5.85 ft	5.85 ft
l =	16.95 ft	16.95 ft
Net Bearing =	1.92 ksf	1.92 ksf

BEARING ADEQUATE

x =	2.963 ft	2.963 ft
Resisting Moment =	5462.655 k-ft	5462.655 k-ft
SF =	1.713	1.713

OVERTURNING ADEQUATE

RADIO FREQUENCY FCC REGULATORY COMPLIANCE  
MAXIMUM PERMISSIBLE EXPOSURE (MPE) ASSESSMENT

Sprint Existing Facility

Site ID: CT23XC313

Orange / Rogers Property

700 Grassy Hill Road  
Orange, CT 06477

**July 14, 2014**

**EBI Project Number: 62143785**

July 14, 2014

Sprint  
Attn: RF Engineering Manager  
1 International Boulevard, Suite 800  
Mahwah, NJ 07495

Re: Radio Frequency Maximum Permissible Exposure (MPE) Assessment for Site:  
**CT23XC313 - Orange / Rogers Property**

**Site Total: 50.73% - MPE% in full compliance**

EBI Consulting was directed to analyze the proposed upgrades to the existing Sprint facility located at 700 Grassy Hill Road, Orange, CT, for the purpose of determining whether the radio frequency (RF) exposure levels from the proposed Sprint equipment upgrades on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter ( $\mu\text{W}/\text{cm}^2$ ). The number of  $\mu\text{W}/\text{cm}^2$  calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits, therefore it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) – (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general public may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general public would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

Public exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter ( $\mu\text{W}/\text{cm}^2$ ). The general population exposure limit for the cellular band (850 MHz Band) is approximately  $567 \mu\text{W}/\text{cm}^2$ , and the general population exposure limit for the 1900 MHz and 2500 MHz bands is  $1000 \mu\text{W}/\text{cm}^2$ . Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.

Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure. Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

## **CALCULATIONS**

Calculations were done for the proposed upgrades to the existing Sprint Wireless antenna facility located at 700 Grassy Hill Road, Orange, CT, using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. All calculations were performed assuming a lobe representing the maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was focused at the base of the tower. For this report the sample point is the top of a 6 foot person standing at the base of the tower.

For all calculations, all emissions were calculated using the following assumptions:

- 1) 2 channels in the 1900 MHz Band were considered for each sector of the proposed installation.
- 2) 1 channel in the 800 MHz Band was considered for each sector of the proposed installation
- 3) 2 channels in the 2500 MHz Band were considered for each sector of the proposed installation.
- 4) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 - Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.
- 5) For the following calculations the sample point was the top of a six foot person standing at the base of the tower. The maximum gain of the antenna per the antenna manufactures supplied specifications minus 10 dB was used in this direction. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.

- 6) The antennas used in this modeling are the RFS APXVSPP18-C-A20 and the RFS APXVTM14-C-I20. This is based on feedback from the carrier with regards to anticipated antenna selection. The RFS APXVSPP18-C-A20 has a 15.9 dBd gain value at its main lobe at 1900 MHz and 13.4 dBd at its main lobe for 850 MHz. The RFS APXVTM14-C-I20 has a 15.9 dBd gain value at its main lobe at 2500 MHz. The maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was used for all calculations. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 7) The antenna mounting height centerline for the proposed antennas is **130 feet** above ground level (AGL).
- 8) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.

All calculation were done with respect to uncontrolled / general public threshold limits

Site ID	CT23XC313 - Orange / Rogers Property
Site Address	700 Grassy Hill Road, Orange, CT, 06477
Site Type	Monopole

**Sector 1**

Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain (10 db reduction)	Antenna Height (ft)	analysis height	Cable Size	Cable Loss (dB)	Additional Loss (dB)	ERP	Power Density Percentage
1a	RFS	APXVSP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	2	40	5.9	130	124	1/2 "	0.5	0	138.69	0.32%
1a	RFS	APXVSP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	3.4	130	124	1/2 "	0.5	0	39.00	0.16%
1B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	5.9	130	124	1/2 "	0.5	0	138.69	0.57%
Sector total Power Density Value:																1.06%

**Sector 2**

Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain (10 db reduction)	Antenna Height (ft)	analysis height	Cable Size	Cable Loss (dB)	Additional Loss (dB)	ERP	Power Density Percentage
2a	RFS	APXVSP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	2	40	5.9	130	124	1/2 "	0.5	0	138.69	0.32%
2a	RFS	APXVSP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	3.4	130	124	1/2 "	0.5	0	39.00	0.16%
2B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	5.9	130	124	1/2 "	0.5	0	138.69	0.57%
Sector total Power Density Value:																1.06%

**Sector 3**

Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain (10 db reduction)	Antenna Height (ft)	analysis height	Cable Size	Cable Loss (dB)	Additional Loss (dB)	ERP	Power Density Percentage
3a	RFS	APXVSP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	2	40	5.9	130	124	1/2 "	0.5	0	138.69	0.32%
3a	RFS	APXVSP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	3.4	130	124	1/2 "	0.5	0	39.00	0.16%
3B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	5.9	130	124	1/2 "	0.5	0	138.69	0.57%
Sector total Power Density Value:																1.06%

Site Composite MPE %	
Carrier	MPE %
Sprint	3.17%
Verizon Wireless	24.81%
MetroPCS	6.81%
Clearwire	1.13%
AT&T	14.59%
T-Mobile	0.22%
<b>Total Site MPE %</b>	<b>50.73%</b>

## Summary

All calculations performed for this analysis yielded results that were well within the allowable limits for general public Maximum Permissible Exposure (MPE) to radio frequency energy.

The anticipated Maximum Composite contributions from the Sprint facility are **3.17% (1.06% from sector 1, 1.06% from sector 2 and 1.06% from sector 3)** of the allowable FCC established general public limit considering all three sectors simultaneously sampled at the ground level.

The anticipated composite MPE value for this site assuming all carriers present is **50.73%** of the allowable FCC established general public limit sampled at 6 feet above ground level. This total composite site value is based upon MPE values listed in the Connecticut Siting Council database for existing carrier emissions.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.



**Scott Heffernan**  
RF Engineering Director

**EBI Consulting**  
21 B Street  
Burlington, MA 01803