

STATE OF CONNECTICUT

CONNECTICUT SITING COUNCIL

Ten Franklin Square, New Britain, CT 06051

Phone: (860) 827-2935 Fax: (860) 827-2950

E-Mail: siting.council@ct.gov

www.ct.gov/csc

April 21, 2011

Douglas L. Culp, Real Estate Consultant
New Cingular Wireless PCS, LLC
500 Enterprise Drive
Rocky Hill, CT 06067-3900

RE: **EM-CING-107-110330** - New Cingular Wireless PCS, LLC notice of intent to modify an existing telecommunications facility located at 525 Orange Center Road, Orange, Connecticut.

Dear Mr. Culp:

The Connecticut Siting Council (Council) hereby acknowledges your notice to modify this existing telecommunications facility, pursuant to Section 16-50j-73 of the Regulations of Connecticut State Agencies with the following conditions:

- Any deviation from the proposed modification as specified in this notice and supporting materials with Council shall render this acknowledgement invalid;
- Any material changes to this modification as proposed shall require the filing of a new notice with the Council;
- Not less than 45 days after completion of construction, the Council shall be notified in writing that construction has been completed;
- The validity of this action shall expire one year from the date of this letter; and
- The applicant may file a request for an extension of time beyond the one year deadline provided that such request is submitted to the Council not less than 60 days prior to the expiration;

The proposed modifications including the placement of all necessary equipment and shelters within the tower compound are to be implemented as specified here and in your notice dated March 30, 2011. The modifications are in compliance with the exception criteria in Section 16-50j-72 (b) of the Regulations of Connecticut State Agencies as changes to an existing facility site that would not increase tower height, extend the boundaries of the tower site, increase noise levels at the tower site boundary by six decibels, and increase the total radio frequencies electromagnetic radiation power density measured at the tower site boundary to or above the standard adopted by the State Department of Environmental Protection pursuant to General Statutes § 22a-162. This facility has also been carefully modeled to ensure that radio frequency emissions are conservatively below State and federal standards applicable to the frequencies now used on this tower.

This decision is under the exclusive jurisdiction of the Council. Please be advised that the validity of this action shall expire one year from the date of this letter. Any additional change to this facility will require explicit notice to this agency pursuant to Regulations of Connecticut State Agencies Section 16-50j-73. Such notice shall include all relevant information regarding the proposed change with cumulative worst-case modeling of radio frequency exposure at the closest point of uncontrolled access to the tower base, consistent with Federal Communications Commission, Office of Engineering and Technology, Bulletin 65. Thank you for your attention and cooperation.

Very truly yours,

Linda Roberts
Executive Director

LR/CDM/laf

c: The Honorable James M. Zeoli, First Selectman, Town of Orange
Paul Dinice, Zoning Enforcement Officer, Town of Orange
Kenneth C. Baldwin, Esq., Robinson & Cole LLP





STATE OF CONNECTICUT

CONNECTICUT SITING COUNCIL

Ten Franklin Square, New Britain, CT 06051

Phone: (860) 827-2935 Fax: (860) 827-2950

E-Mail: siting.council@ct.gov

www.ct.gov/csc

April 7, 2011

The Honorable James M. Zeoli
First Selectman
Town of Orange
Town Hall
617 Orange Center Road
Orange, CT 06477-2423

RE: **EM-CING-107-110330** - New Cingular Wireless PCS, LLC notice of intent to modify an existing telecommunications facility located at 525 Orange Center Road, Orange, Connecticut.

Dear First Selectman Zeoli:

The Connecticut Siting Council (Council) received this request to modify an existing telecommunications facility, pursuant to Regulations of Connecticut State Agencies Section 16-50j-72.

If you have any questions or comments regarding this proposal, please call me or inform the Council by April 21, 2011.

Thank you for your cooperation and consideration.

Very truly yours,

Linda Roberts
Executive Director

LR/jbw

Enclosure: Notice of Intent

c: Paul Dinice, Zoning Enforcement Officer, Town of Orange



New Cingular Wireless PCS, LLC
500 Enterprise Drive
Rocky Hill, Connecticut 06067-3900
Phone: (860) 463-5511
Fax: (860) 513-7190


Douglas L. Culp
Real Estate Consultant

ORIGINAL

HAND DELIVERED

March 30, 2011

Ms. Linda Roberts
Executive Director
Connecticut Siting Council
10 Franklin Square
New Britain, Connecticut 06051



Re: New Cingular Wireless PCS, LLC notice of intent to modify an existing tele-communications facility located at 525 Orange Center Road Orange, CT (owner Verizon Wireless)

Dear Ms. Roberts:

In order to accommodate technological changes, implement Uniform Mobile Telecommunications System ("UMTS") and/or Long Term Evolution ("LTE") capabilities, and enhance system performance in the State of Connecticut, New Cingular Wireless PCS, LLC ("AT&T") plans to modify the equipment configurations at many of its existing cell sites. Please accept this letter and attachments as notification, pursuant to R.C.S.A. Section 16-50j-73, of construction which constitutes an exempt modification pursuant to R.C.S.A. Section 16-50j-72(b)(2). In compliance with R.C.S.A. Section 16-50j-73, a copy of this letter and attachments is being sent to the chief elected official of the municipality in which the affected cell site is located.

UMTS technology offers services to mobile computer and phone users anywhere in the world. Based on the Global System for Mobile ("GSM") communication standard, UMTS is the planned worldwide standard for mobile users. UMTS, fully implemented, gives computer and phone users high-speed access to the Internet as they travel. They have the same capabilities even when they roam, through both terrestrial wireless and satellite transmissions.

LTE is a new high-performance air interface for cellular mobile communications, designed to increase the capacity and speed of mobile telephone networks.

Attached is a summary of the planned modifications, including power density calculations reflecting the change in AT&T's operations at the site. Also included is documentation of the structural sufficiency of the tower to accommodate the revised antenna configuration.


The changes to the facility do not constitute modifications as defined in Connecticut General Statutes ("C.G.S.") Section 16-50i(d) because the general physical characteristics of the facility will not be significantly changed or altered. Rather, the planned changes to the facility fall squarely within those activities explicitly provided for in R.C.S.A. Section 16-50j-72(b)(2).

1. The height of the overall structure will be unaffected.
2. The proposed changes will not extend the site boundaries. There will be no effect on the site compound other than some enlarged equipment pads as may be noted in the attachments.
3. The proposed changes will not increase the noise level at the existing facility by six decibels or more.
4. Radio frequency power density may increase due to use of one or more GSM channel for UMTS transmissions. Moreover, LTE will utilize additional radio frequencies newly-licensed by the FCC for cellular mobile communications. However, the changes will not increase the calculated "worst case" power density for the combined operations at the site to a level at or above the applicable standard for uncontrolled environments as calculated for a mixed frequency site.

For the foregoing reasons, New Cingular Wireless respectfully submits that the proposed changes at the referenced site constitute exempt modifications under R.C.S.A. Section 16-50j-72(b)(2).

Please feel free to call me at (860) 463-5511 with questions concerning this matter. Thank you for your consideration.

Sincerely,



Douglas L. Culp
Real Estate Consultant

Attachments

NEW CINGULAR WIRELESS PCS, LLC
Equipment Modification

525 Orange Center Road
Site Number CT2174

Tower Owner/Manager: Verizon Wireless

Equipment configuration: Monopole

Current and/or approved: Six PowerWave antennas @ 145 ft
PowerWave TMA's (6) and Diplexer's (12) @ 145 ft
Twelve runs 1 1/4 inch coax to 145 ft
Equipment Shelter

Planned Modifications: Retain existing PowerWave Diplexers and TMA's at 145 ft
Retain existing PowerWave Antennas @ 145 ft
Retain all Coax Cabling
Install three PowerWave P65-16 antennas or equivalent @ 145 ft
Install six Ericsson RRUS 11 remote radio heads @ 145 ft
Install one RayCap DC6-48-60-18-8F surge protector @ 145 ft
Install one fiber and two DC power cables to 145 ft

Power Density:

Worst-case calculations for existing wireless operations at the site, using standard parameters for other carriers, indicate a radio frequency electromagnetic radiation power density, measured at ground level beside the Tower, of approximately 31.5% of the standard adopted by the FCC. As depicted in the second table below, the total radio frequency electromagnetic radiation power density following proposed modifications would be approximately 41.6 % of the standard.

Existing

Company	Centerline Ht (feet)	Frequency (MHz)	Number of Channels	Power Per Channel (Watts)	Power Density (mW/cm ²)	Standard Limits (mW/cm ²)	Percent of Limit
Other Users							25.14
AT&T UMTS	145	1900 Band	1	500	0.0086	1.0000	0.86
AT&T UMTS	145	800 Band	1	500	0.0086	0.5867	1.46
AT&T GSM	145	800Band	3	296	0.0152	0.5867	2.59
AT&T GSM	145	1900 Band	2	427	0.0146	1.0000	1.46
Total							31.5%

* Data for other users are from Siting Council records.

Proposed

Company	Centerline Ht (feet)	Frequency (MHz)	Number of Channels	Power Per Channel (Watts)	Power Density (mW/cm ²)	Standard Limits (mW/cm ²)	Percent of Limit
Other Users							25.14
AT&T UMTS	107	800 Band	1	500	0.0157	0.5867	2.68
AT&T UMTS	107	1900 Band	2	500	0.0314	1.0000	3.14
AT&T GSM	107	1900 Band	2	427	0.0268	1.0000	2.68
AT&T GSM	107	880 - 894	3	296	0.0279	0.5867	4.75
AT&T LTE	107	740 - 746	1	500	0.0157	0.4933	3.18
Total							41.6%

* Data for other users are from Siting Council records.

Structural information:

The attached structural analysis demonstrates that the monopole and foundation have adequate structural capacity to accommodate the proposed modifications. (CENTEK dated 3-29-11)



GENERAL NOTES

- ## PROJECT SUMMARY

AT&T SITE NUMBER:	CT2174
AT&T SITE NAME:	ORANGE - CENTRAL
SITE ADDRESS:	525 ORANGE CENTER ROAD ORANGE, CT 06477
LESSOR/APPLICANT:	AT&T MOBILITY 550 ENTERPRISE DRIVE, SUITE 3A ROCKY HILL, CT 06067
ENGINEER:	COTEX ENGINEERING, INC. 53-2 NORTH BRANFORD RD. BRANFORD, CT 06405
PROJECT COORDINATES:	LATITUDE: 41° 16' - 25.3" N LONGITUDE: 72° 57' - 17.2" W GROUND ELEVATION: ±191' AMSL

[illegible]

AT&T MOBILITY SITE NUMBER: CT1714 WIRELESS COMMUNICATIONS FACILITY SITE NAME: ORANGE - CENTRAL 826 ORANGE CENTER ROAD ORANGE, CT 06477 www.Centellog.com		DATE: 02/29/11 SCALE: AS NOTED JOB NO.: 11001.0005	T-1 of 6
DESIGNED BY: [Blank] DRAWN BY: [Blank] CHECKED BY: [Blank]		PROFESSIONAL ENGINEER: [Blank] DATE: 3/15/11 JOB: [Blank] DRAWN BY: [Blank] CHECKED BY: [Blank]	TITLE SHEET

DESIGN BASIS

GOVERNING CODE: 2003 INTERNATIONAL BUILDING CODE (IBC) AS MODIFIED BY THE 2005 CONNECTICUT STATE BUILDING CODE AND 2009 AMENDMENTS.

1. DESIGN CRITERIA
 - WIND LOAD: PER EN13722 F=36 (ANTENNA MOUNTS); 90 MPH (FASTEST MILE), EQUIVALENT TO 110 MPH (3 SECOND GUST).
 - BASIC WIND SPEED (OTHER STRUCTURE): 110 MPH (3 SECOND GUST) (PRESSURE COEFFICIENTS ARE THE SAME AS FOR THE 110 MPH WIND SPEED, INCLUDING CODE 603 AS REPORTED BY THE 2005 CONSTRUCTION SPECIFICATION AND 2009 AMENDMENT).
 - SEISMIC LOAD (BASED NOT CONTROL): PER ASCE 7-95 MINIMUM DESIGN LOADS FOR BUILDINGS AND OTHER STRUCTURES.

1. IF ANY FIELD CONDITIONS NOTED WHICH PRECLUDE COMPLIANCE WITH THE DRAWINGS, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE ENGINEER AND SHALL PROCEED WITH AFFECTED WORK AFTER CONSULT IS SATISFACTORILY RESOLVED.
2. DIMENSIONS AND DETAILS SHALL BE CHECKED AGAINST THE PRE MANUFACTURED EQUIPMENT BUILDING SHOP DRAWINGS.
3. THE CONTRACTOR SHALL VERIFY AND COORDINATE THE SIZE AND LOCATION OF ALL OPENINGS, SLEEVES AND ANCHOR BOLTS AS REQUIRED BY ALL TRUDES.
4. REFER TO DRAWING T1 FOR ADDITIONAL NOTES AND REQUIREMENTS.

1. THE CONTRACTOR SHALL UTILITIES PRIOR TO THE START OF CONSTRUCTION.
2. ACTIVE EXISTING UTILITIES, WHERE ENCOUNTERED IN THE WORK, SHALL BE PROTECTED AT ALL TIMES. THE ENGINEER SHALL BE NOTIFIED IMMEDIATELY, PRIOR TO PROCEEDING, SHOULD ANY UNCOVERED EXISTING UTILITY PRECLUDE COMPLETION OF THE WORK IN ACCORDANCE WITH THE CONTRACT DOCUMENTS.
3. ALL EXISTING STRUCTURES, UTILITIES, AND FOUNDATIONS SHALL BE REMOVED OFF SITE AND THE EXISTING STRUCTURES, UTILITIES, AND FOUNDATIONS REMOVED OFF SITE SHALL BE RELOCATED TO THE TOWER AREAS.
4. THE SITE SHALL BE GRADED TO CAUSE SURFACE WATER TO FLOW AWAY FROM THE EQUIPMENT AND TOWER AREAS.
5. NO FILL OR DRAINAGE MATERIAL SHALL BE PLACED ON FROZEN GROUND, FROZEN MATERIALS, SNOW OR ICE SHALL NOT BE PLACED IN ANY FILL OR DRAINAGE.
6. THE SUBGRADE SHALL BE COMPACTED AND BROUGHT TO A SMOOTH UNIFORM GRADE PRIOR TO FINISHED SURFACE APPLICATION.
7. THE AREAS OF THE COMPOUND DISTURBED BY THE WORK SHALL BE RETURNED TO THEIR ORIGINAL

1. COMPACTED GRAVEL FILL SHALL BE FURNISHED AND PLACED AS A FOUNDATION FOR STRUCTURES, WHERE SHOWN ON THE CONTRACT DRAWINGS OR DIRECTED BY THE ENGINEER.
2. CRUSHED STONE FILL SHALL BE PLACED IN 12" MAX. LIFTS AND CONSOLIDATED USING A HAND OPERATED VIBRATORY PLATE COMPACTOR WITH A MINIMUM OF 2 PASSES OF COMPACTOR PER LIFT.
3. COMPACTED GRAVEL FILL TO BE WELL GRADED BANK RUN GRAVEL MEETING THE FOLLOWING CRADATION REQUIREMENTS:

SIEVE DESIGNATION	% PASSING
1 μ	100
No. 4	40-70
No. 100	5-20
No. 200	1-5

4. CRUSHED STONE TO BE UNIFORMLY GRADED, CLEAN, HARD PROCESS AGGREGATE MEETING THE FOLLOWING GRADATION REQUIREMENTS:
- | SIEVE DESIGNATION | % PASSING |
|-------------------|-----------|
| No. 10 | 100 |
| No. 20 | 98 |
| No. 40 | 96 |
| No. 60 | 94 |
| No. 80 | 92 |
| No. 100 | 90 |
| No. 120 | 87 |
| No. 150 | 84 |
| No. 200 | 80 |
| No. 250 | 75 |
| No. 300 | 70 |
| No. 350 | 65 |
| No. 425 | 60 |
| No. 500 | 55 |
| No. 600 | 50 |
| No. 750 | 45 |
| No. 900 | 40 |
| No. 1060 | 35 |
| No. 1250 | 30 |
| No. 1500 | 25 |
| No. 1800 | 20 |
| No. 2100 | 15 |
| No. 2500 | 10 |
| No. 3000 | 5 |
| No. 3500 | 0 |

SEIF DEFORMATION	% PASSING
1"	100
3/4"	90-100
1/2"	0-15
3/8"	0-5

5. SELECT BACKFILL FOR FOUNDATION WALLS SHALL BE FREE OF ORGANIC MATERIAL, TOPSOIL, DEBRIS AND Boulders LARGER THAN 6".
6. GRAVEL AND GRANULAR FILL SHALL BE INSTALLED IN 8" MAX. LIFTS. COMPACTED TO 95% MIN. AT MAX. DRY DENSITY.
7. NON WOVEN GEOTEXTILE FOR SEPARATION PURPOSES SHALL BE MIRAF 140N, OR ENGINEER APPROVED, EQUAL.

CONTRACTOR TO REFER TO THE GENERAL NOTES ON SHEET T-1 FOR ADDITIONAL INFORMATION.


1. CONCRETE CONSTRUCTION SHALL CONFORM TO THE FOLLOWING STANDARDS:
 - ACI 211 - STANDARD PRACTICE FOR SELECTING PROPORTIONS FOR NORMAL AND HEAVYWEIGHT CONCRETE.
 - ACI 301 - SPECIFICATIONS FOR STRUCTURAL CONCRETE FOR BUILDINGS.
 - ACI 302 - GUIDE FOR CONCRETE FLOOR AND SLAB CONSTRUCTION.
 - ACI 304 - RECOMMENDED PRACTICE FOR MEASURING, MIXING, TRANSPORTING, AND PLACING CONCRETE.
 - ACI 304.1 - STANDARD SPECIFICATION FOR COLD WEATHER CONCRETING
 - ACI 318 - BUILDING CODE REQUIREMENTS FOR REINFORCED CONCRETE.
2. CONCRETE SHALL DEVELOP COMPRESSIVE STRENGTH IN 28 DAYS AS FOLLOWS:

- PORTLAND CEMENT: ASTM C150, TYPE II, (340 LBS./CUBIC YARD)
- AGGREGATE: ASTM C33, No. 67, TYPICAL
- WATER: POTABLE WITH MAXIMUM WATER CEMENT RATIO OF .55
- SLUMP: 3" TO 4"
- ADMIXTURES: USE AIR ENTRAINING AGENT CONFORMING TO ASTM C260 WITH 4 TO 6% TOTAL AIR. USE WATER REDUCING AGENT CONFORMING TO ASTM C494 TYPE I. IN ALL CONCRETE, CALCIUM CHLORIDE MAY NOT BE USED TO ACCELERATE THE CONCRETE SETTING TIME.
- 3. REINFORCING STEEL SHALL BE 60,000 PSI YIELD STRENGTH.

4. WELDED WIRE FABRIC SHALL CONFORM TO ASTM A-185.
5. ALL DETAILING, FABRICATION, AND ERECTION OF REINFORCING BARS, UNLESS OTHERWISE NOTED, MUST FOLLOW THE LATEST ACI CODE AND LATEST ACI MANUAL OF STANDARD PRACTICE FOR DETAILING REINFORCED CONCRETE STRUCTURES.
6. CONCRETE COVER OVER REINFORCING SHALL CONFORM TO THE FOLLOWING, UNLESS OTHERWISE SHOWN:

BOTTOM OF FOOTINGS	3 INCHES	SPACES NOT EXPOSED TO EARTH OR WATER
TOP OF FOOTINGS	1-1/2 INCHES	ON STEEL REIN. METAL FORM TIES, OR ANY OTHER METAL SHALL REMAIN WITHIN THE REQUIRED COVER
7. ALL REINFORCING SHALL BE CONTINUOUS UNLESS OTHERWISE NOTED. SPICES SHALL BE WELDED TOGETHER AT JOINTS. SUCH DETAILS SHALL COMPLY WITH ACI 315 RECOMMENDATIONS UNLESS OTHERWISE SHOWN.
8. NO TACK WELDING OF REINFORCING WILL BE PERMITTED.
9. NO CALCIUM CHLORIDE OR ADMIXTURES CONTAINING MORE THAN 1% CHLORIDE BY WEIGHT OF ADMIXTURE SHALL BE USED IN THE CONCRETE.
10. ALL LAP SPICES SHALL BE 48 BAR DIAMETERS.
11. UNLESS OTHERWISE NOTED, ALL LAP SPICES SHALL BE 48 BAR DIAMETERS.

[illegible]



Structural Analysis Report

160-ft Existing Valmont Monopole

Proposed AT&T Antenna Upgrade

AT&T Site Ref: CT2174: Orange-Central

*525 Orange Center Road
Orange, CT*

CEN TEK Project No. 11021.CO25

Date: March 29, 2011



Prepared for:

**AT&T Mobility
500 Enterprise Drive, Suite 3A
Rocky Hill, CT 06067**

Table of Contents

SECTION 1 - REPORT

- INTRODUCTION.
- ANTENNA AND APPURTENANCE SUMMARY.
- PRIMARY ASSUMPTIONS USED IN THE ANALYSIS.
- ANALYSIS.
- TOWER LOADING.
- TOWER CAPACITY.
- FOUNDATION AND ANCHORS.
- CONCLUSION.

SECTION 2 – CONDITIONS & SOFTWARE

- STANDARD ENGINEERING CONDITIONS.
- GENERAL DESCRIPTION OF STRUCTURAL ANALYSIS PROGRAM.

SECTION 3 – CALCULATIONS

- RISATower INPUT/OUTPUT SUMMARY.
- RISATower DETAILED OUTPUT.
- ANCHOR BOLT AND BASE PLATE ANALYSIS.
- FOUNDATION ANALYSIS.

SECTION 4 – REFERENCE MATERIALS

- AT&T RFDS SHEET.
- ANTENNA CUT SHEETS.

Introduction

The purpose of this report is to summarize the results of the non-linear, P- Δ structural analysis of the antenna installation proposed by AT&T Mobility on the existing monopole (tower), owned and operated by Verizon Wireless, located in Orange, CT.

The host tower is a 160-ft tall, four-section, twelve sided, tapered monopole, originally designed and manufactured by Valmont Structures job no; 16632-97, dated February 25, 1998. The manufacturer's drawings and calculations were unavailable for use in this report. The tower geometry, structure member sizes and foundation system information were obtained from a previous structural analysis report prepared by Centek (Formerly Natcomm); job no; 09009.CO15, dated October 16, 2009. Antenna and appurtenance information were obtained from the aforementioned Centek structural report, an AT&T RFDS sheet and visual verification conducted from grade by Centek personal on March 2, 2011.

The tower is made up of four (4) tapered vertical sections consisting of A572-65 pole sections. The vertical tower sections are slip joint connected. The diameter of the pole (flat-flat) is 21.2-in at the top and 64.0-in at the base.

AT&T Mobility proposes the installation of three (3) panel antennas on an existing 13-ft platform with handrails. Refer to the Antenna and Appurtenance Summary below for a detailed description of the proposed antenna and appurtenance configuration.

Antenna and Appurtenance Summary

The existing tower was designed to support several communication antennas. The existing, proposed and future loads considered in this analysis consist of the following:

- NEXTEL (Existing to Remain):
Antennas: Nine (9) Decibel DB844H90E-XY panel antennas, three (3) Argus LLPX310R panel antennas w/ Samsung WiMax remote radio heads FD_R6_RRH and two (2) Dragonwave A-Ant-23G-2C dish antennas pipe mounted to Verizon's platform with rails with a RAD center elevation of 167-ft above the existing tower base plate.
Coax Cables: Nine (9) 1-1/4", six (6) 5/16" $\varnothing$ and two (2) 1/2" $\varnothing$ coax cables running on the inside of the existing tower.
- VERIZON (Existing):
Antennas: Six (6) Antel LPA-80063/6CF and six (6) Decibel DB948F85T2E-M panel antennas mounted on a 13-ft platform with rails with a RAD center elevation of 155.2-ft above the existing tower base plate.
Coax Cables: Twelve (12) 1-5/8" $\varnothing$ coax cables running on the inside of the existing tower.
- SPRINT (Existing):
Antennas: Six (6) Decibel DB980H90E-M panel antennas mounted on a 13-ft platform with rails with a RAD center elevation of 134.1-ft above the existing tower base plate.
Coax Cables: Six (6) 1-5/8" $\varnothing$ coax cables running on the inside of the existing tower.

- **T-MOBILE (Existing):**
Antennas: Six (6) RR90-17-02DP panel antennas, three (3) RFS APX16DWV-16DWV-S panel antennas and six (6) 10" by 8" by 3" TMA's mounted on a 13-ft platform with rails with a RAD center elevation of 121.9-ft above the existing tower base plate.
Coax Cables: Twelve (12) 1-5/8" Ø coax cables running on the inside of the existing tower.
- **POCKET (Existing):**
Antennas: Three (3) RFS APXV18-206517LS panel antennas flush mounted with a RAD center elevation of 110-ft above the existing tower base plate.
Coax Cables: Six (6) 1-5/8" Ø coax cables running on the inside of the existing tower.
- **SPRINT (Existing):**
Antennas: One (1) GPS antenna on a GPS Stand-off mount with a RAD center elevation of 83.4-ft above the existing tower base plate.
Coax Cables: One (1) 1/2" Ø coax cable running on the inside of the existing tower.
- **AT&T (Existing to Remain):**
Antennas: Six (6) Powerwave 7770 panel antennas, six (6) Powerwave LGP TMA's, and twelve (12) Powerwave LGP diplexers mounted on a 13-ft platform with rails with a RAD center elevation of 145.7-ft above the existing tower base plate.
Coax Cables: Twelve (12) 1-1/4" Ø coax cables running on the inside of the existing tower.
- **AT&T (PROPOSED):**
Antennas: Three (3) Powerwave P65-16-XLH-RR panel antennas mounted on a 13-ft platform with rails with a RAD center elevation of 145.7-ft above the existing tower base plate.
- **AT&T (PROPOSED):**
Antennas: Six (6) Ericsson RRUS-11 and one (1) Raycap DC6-48-60-18-8F surge arrester mounted to one (1) universal ring mount with a RAD center elevation of 147.75-ft above grade level.
Coax Cables: One (1) fiber cable and two (2) dc control cables running inside of the existing tower.

Primary Assumptions Used in the Analysis

- The tower structure's theoretical capacity not including any assessment of the condition of the tower.
- The tower carries the horizontal and vertical loads due to the weight of antennas, ice load and wind.
- Tower is properly installed and maintained.
- Tower is in plumb condition.
- Tower loading for antennas and mounts as listed in this report.
- All bolts are appropriately tightened providing the necessary connection continuity.
- All welds are fabricated with ER-70S-6 electrodes.
- All members are assumed to be as specified in the original tower design documents or reinforcement drawings.
- All members are "hot dipped" galvanized in accordance with ASTM A123 and ASTM A153 Standards.
- All member protective coatings are in good condition.
- All tower members were properly designed, detailed, fabricated, installed and have been properly maintained since erection.
- Any deviation from the analyzed antenna loading will require a new analysis for verification of structural adequacy.
- All coax cables to be installed as indicated in this report.
- Refer to construction drawings dated 2.28.11 for RRU and Surge Arrestor mounting details.

Analysis

The existing tower was analyzed using a comprehensive computer program entitled RISATower. The program analyzes the tower, considering the worst case loading condition. The tower is considered as loaded by concentric forces along the tower shaft, and the model assumes that the shaft members are subjected to bending, axial, and shear forces.

The existing tower was analyzed for 90 mph basic wind speed (fastest mile) with no ice and 75% reduction of wind force with ½ inch accumulative ice to determine stresses in members as per guidelines of TIA/EIA-222-F-96 entitled "Structural Standards for Steel Antenna Towers and Antenna Supporting Structures", the American Institute of Steel Construction (AISC) and the Manual of Steel Construction; Allowable Stress Design (ASD).

Tower Loading

Tower loading was determined by the basic wind speed as applied to projected surface areas with modification factors per TIA/EIA-222-F, gravity loads of the tower structure and its components, and the application of ½" radial ice tower structure and its components.

Basic Wind Speed:	New Haven; v = 85 mph (fastest mile)	[Section 16 of TIA/EIA-222-F-96]
	Orange; v = 110 mph (3 second gust) equivalent to v = 90 mph (fastest mile)	[Appendix K of the 2005 CT Building Code Supplement]
	Appendix K wind speed criteria controls.	
Load Cases:	<u>Load Case 1</u> ; 90 mph wind speed w/ no ice plus gravity load – used in calculation of tower stresses and rotation.	[Section 2.3.16 of TIA/EIA-222-F-96]
	<u>Load Case 2</u> ; 78 mph wind speed w/ ½" radial ice plus gravity load – used in calculation of tower stresses. The 78 mph wind speed velocity represents 75% of the wind pressure generated by the 90 mph wind speed.	[Section 2.3.16 of TIA/EIA-222-F-96]
	<u>Load Case 3</u> ; Seismic – not checked	[Section 1614.5 of State Bldg. Code 2005] does not control in the design of this structure type

Tower Capacity

Tower stresses were calculated utilizing the structural analysis software RISATower. Allowable stresses were determined based on Table 5 of the TIA/EIA code with a 1/3 increase per Section 3.1.1.1 of the same code.

Calculated stresses were found to be within allowable limits. In Load Case 1, per RISATower "Section Capacity Table", this tower was found to be at **81.3%** of its total capacity.

Tower Section	Elevation	Stress Ratio (percentage of capacity)	Result
Pole Shaft (L4)	0'-37.17'	81.3%	PASS

Foundation and Anchors

The existing foundation consists of an 8.0-ft square x 10.0-ft long reinforced concrete pier on a 22.0-ft x 4.0-ft thick reinforce concrete pad. The sub-grade conditions used in the analysis of the existing foundation were obtained from the aforementioned structural report prepared by Centek (Formerly Natcomm); job no; 09009.CO15, dated October 16, 2009. The base of the tower is connected to the foundation by means of (24) 2.25"Ø, ASTM A615-75 anchor bolts embedded approximately 10-ft into the concrete foundation structure.

Review of the foundation and anchor design consisted of verification of applied loads obtained from the tower design calculations and code checks of allowable stresses:

- The tower base reactions developed from the governing Load Case 1 were used in the verification of the foundation and its anchors:

Base Reactions	Vector	Proposed Load (kips/ft-kips)
Base	Shear	45
	Axial	53
	Moment	4862

- The foundation was found to be within allowable limits.

Foundation	Design Limit	IBC 2003/2005 CT State Building Code Section 3108.4.2 FS ⁽¹⁾	Proposed Loading FS ⁽¹⁾	Result
Reinf. Conc. Pad and Pier	OTM ⁽²⁾	2.0	3.67	PASS

Note: 1. FS denote Factor of Safety
 2. OTM denotes Overturning Moment

- The anchor bolts and base plate were found to be within allowable limits.

Tower Component	Design Limit	Stress Ratio (percentage of capacity)	Result
Anchor Bolts	Compression	69.7%	PASS
Base Plate	Bending	43.1%	PASS

Conclusion

This analysis shows that the subject tower is adequate to support the proposed modified AT&T antenna configuration.

The analysis is based, in part, on the information provided to this office by AT&T Mobility. If the existing conditions are different than the information in this report, Centek Engineering, Inc. must be contacted for resolution of any potential issues.

Please feel free to call with any questions or comments.


Respectfully Submitted by:



Carlo F. Centore, PE
Principal ~ Structural Engineer



Prepared by:



Timothy J. Lynn, EIT
Structural Engineer

Standard Conditions for Furnishing of
Professional Engineering Services on
Existing Structures

All engineering services are performed on the basis that the information used is current and correct. This information may consist of, but is not necessarily limited to:


- Information supplied by the client regarding the structure itself, its foundations, the soil conditions, the antenna and feed line loading on the structure and its components, or other relevant information.
- Information from the field and/or drawings in the possession of CENTEK engineering, Inc. or generated by field inspections or measurements of the structure.
- It is the responsibility of the client to ensure that the information provide to CENTEK engineering, Inc. and used in the performance of our engineering services is correct and complete. In the absence of information to the contrary, we assume that all structures were constructed in accordance with the drawings and specifications and are in an un-corroded condition and have not deteriorated. It is therefore assumed that its capacity has not significantly changed from the "as new" condition.
- All services will be performed to the codes specified by the client, and we do not imply to meet any other codes or requirements unless explicitly agreed in writing. If wind and ice loads or other relevant parameters are to be different from the minimum values recommended by the codes, the client shall specify the exact requirement. In the absence of information to the contrary, all work will be performed in accordance with the latest revision of ANSI/ASCE10 & ANSI/EIA-222
- All services performed, results obtained, and recommendations made are in accordance with generally accepted engineering principles and practices. CENTEK engineering, Inc. is not responsible for the conclusions, opinions and recommendations made by others based on the information we supply.

General Description of Structural Analysis Program

RISATower, is an integrated structural analysis and design software package for Designed specifically for the telecommunications industry, RISATower, formerly ERITower, automates much of the tower analysis and design required by the TIA/EIA 222 Standard.

RISATower Features:

- RISATower can analyze and design 3- and 4-sided guyed towers, 3- and 4-sided self-supporting towers and either round or tapered ground mounted poles with or without guys.
- The program analyzes towers using the TIA-222-G (2005) standard or any of the previous TIA/EIA standards back to RS-222 (1959). Steel design is checked using the AISC ASD 9th Edition or the AISC LRFD specifications.
- Linear and non-linear (P-delta) analyses can be used in determining displacements and forces in the structure. Wind pressures and forces are automatically calculated.
- Extensive graphics plots include material take-off, shear-moment, leg compression, displacement, twist, feed line, guy anchor and stress plots.
- RISATower contains unique features such as True Cable behavior, hog rod take-up, foundation stiffness and much more.



DESIGNED APPURTENANCE LOADING


TYPE	ELEVATION	TYPE	ELEVATION
(3) DB844H90E-XY (Nextel Existing)	167	7770.00 (ATTI Existing)	145.7
(3) DB844H90E-XY (Nextel Existing)	167	7770.00 (ATTI Existing)	145.7
(3) DB844H90E-XY (Nextel Existing)	167	P65-16-XLH-RR (ATTI Proposed)	145.7
LLPX310R (Nextel Existing)	167	(2) LGP214nn TMA (ATTI Existing)	145.7
LLPX310R (Nextel Existing)	167	(2) LGP214nn TMA (ATTI Existing)	145.7
LLPX310R (Nextel Existing)	167	(2) LGP214nn TMA (ATTI Existing)	145.7
Remote Radio Head FD R6 RRH (Nextel Existing)	167	(4) LGP21901 Diplexer (ATTI Existing)	145.7
Remote Radio Head FD R6 RRH (Nextel Existing)	167	(4) LGP21901 Diplexer (ATTI Existing)	145.7
Remote Radio Head FD R6 RRH (Nextel Existing)	167	(4) LGP21901 Diplexer (ATTI Existing)	145.7
Remote Radio Head FD R6 RRH (Nextel Existing)	167	7770.00 (ATTI Existing)	145.7
Remote Radio Head FD R6 RRH (Nextel Existing)	167	P65-16-XLH-RR (ATTI Proposed)	145.7
A-Ant-23G-2-C (Nextel Existing)	167	7770.00 (ATTI Existing)	145.7
A-Ant-23G-2-C (Nextel Existing)	167	7770.00 (ATTI Existing)	145.7
(4) 8"x2 1/2" Pipe Mount (Nextel Existing)	163	P65-16-XLH-RR (ATTI Proposed)	145.7
(5) 8"x2 1/2" Pipe Mount (Nextel Existing)	163	7770.00 (ATTI Existing)	145.7
(5) 8"x2 1/2" Pipe Mount (Nextel Existing)	163	13' Platform w/Rails (ATTI Existing)	143.7
DB948F85T2E-M (Verizon Existing)	155.2	(2) DB980H90E-M (Sprint Existing)	134.1
DB948F85T2E-M (Verizon Existing)	155.2	(2) DB980H90E-M (Sprint Existing)	134.1
DB948F85T2E-M (Verizon Existing)	155.2	(2) DB980H90E-M (Sprint Existing)	134.1
DB948F85T2E-M (Verizon Existing)	155.2	13' Platform w/Rails (Sprint Existing)	131.8
DB948F85T2E-M (Verizon Existing)	155.2	APX16DWV-16DWV-S-E-ACU (T-Mobile Existing)	121.9
DB948F85T2E-M (Verizon Existing)	155.2	APX16DWV-16DWV-S-E-ACU (T-Mobile Existing)	121.9
LPA-80063/6CF (Verizon Existing)	155.2	(2) RR90-17-02DP (T-Mobile Existing)	121.9
LPA-80063/6CF (Verizon Existing)	155.2	(2) RR90-17-02DP (T-Mobile Existing)	121.9
LPA-80063/6CF (Verizon Existing)	155.2	(2) RR90-17-02DP (T-Mobile Existing)	121.9
LPA-80063/6CF (Verizon Existing)	155.2	(2) 10"x8"x3" TMA (T-Mobile Existing)	121.9
LPA-80063/6CF (Verizon Existing)	155.2	(2) 10"x8"x3" TMA (T-Mobile Existing)	121.9
LPA-80063/6CF (Verizon Existing)	155.2	(2) 10"x8"x3" TMA (T-Mobile Existing)	121.9
LPA-80063/6CF (Verizon Existing)	155.2	APX16DWV-16DWV-S-E-ACU (T-Mobile Existing)	121.9
13' Platform w/Rails (Verizon Existing)	155.2	13' Platform w/Rails (T-Mobile Existing)	119
DB948F85T2E-M (Verizon Existing)	155.2	APXV18-206517LS (Pocket Existing)	110
(2) RRUS-11 (ATTI - Proposed)	147.75	APXV18-206517LS (Pocket Existing)	110
(2) RRUS-11 (ATTI - Proposed)	147.75	APXV18-206517LS (Pocket Existing)	110
(2) RRUS-11 (ATTI - Proposed)	147.75	APXV18-206517LS (Pocket Existing)	110
DC6-48-60-18-8F Surge Arrestor (ATTI - Proposed)	147.75	GPS (Sprint Existing)	83.4
Valmont Uni-Tri Bracket (ATTI - Proposed)	147.75	Stand-off	83.4
		Stand-off	83.4

MATERIAL STRENGTH

GRADE	Fy	Fu	GRADE	Fy	Fu
A572-65	65 ksi	80 ksi			

TOWER DESIGN NOTES

1. Tower is located in New Haven County, Connecticut.
2. Tower designed for a 90 mph basic wind in accordance with the TIA/EIA-222-F Standard.
3. Tower is also designed for a 78 mph basic wind with 0.50 in ice.
4. Deflections are based upon a 50 mph wind.
5. Weld together tower sections have flange connections.
6. Connections use galvanized A325 bolts, nuts and locking devices. Installation per TIA/EIA-222 and AISC Specifications.
7. Tower members are "hot dipped" galvanized in accordance with ASTM A123 and ASTM A153 Standards.
8. Welds are fabricated with ER-70S-6 electrodes.
9. TOWER RATING: 81.3%



Centek Engineering Inc.
63-2 North Branford Road
Branford, CT 06405
Phone: 203.488.0580
FAX: 203.488.8587

Job: **11021.CO25 - CT2174 ~ Orange-Central**
Project: **160-ft Valmont Monopole - Orange, CT**
Client: **AT&T Mobility** Drawn by: **TJL** App'd:
Code: **TIA/EIA-222-F** Date: **03/29/11** Scale: **NTS**
Path: **J:\06110210\110210\110210-CT2174 - 160 Orange-Central R11 Orange, CT\06110210\110210-CT2174 - 160 Orange-Central R11 Orange, CT.dwg** Dwg No. **E-1**

RISATower Centek Engineering Inc. 63-2 North Branford Road Branford, CT 06405 Phone: 203.488.0580 FAX: 203.488.8587	Job	11021.CO25 - CT2174 ~ Orange-Central	Page	1 of 22
	Project	160-ft Valmont Monopole - Orange, CT	Date	12:21:23 03/29/11
	Client	AT&T Mobility	Designed by	TJL

Tower Input Data

There is a pole section.

This tower is designed using the TIA/EIA-222-F standard.

The following design criteria apply:

Tower is located in New Haven County, Connecticut.

Basic wind speed of 90 mph.

Nominal ice thickness of 0.500 in.

Ice density of 56 pcf.

A wind speed of 78 mph is used in combination with ice.

Temperature drop of 50 °F.

Deflections calculated using a wind speed of 50 mph.

Weld together tower sections have flange connections..

Connections use galvanized A325 bolts, nuts and locking devices. Installation per TIA/EIA-222 and AISC Specifications..

Tower members are "hot dipped" galvanized in accordance with ASTM A123 and ASTM A153 Standards..

Welds are fabricated with ER-70S-6 electrodes..

A non-linear (P-delta) analysis was used.

Pressures are calculated at each section.

Stress ratio used in pole design is 1.333.

Local bending stresses due to climbing loads, feedline supports, and appurtenance mounts are not considered.

Options

Consider Moments - Legs	Distribute Leg Loads As Uniform	Treat Feedline Bundles As Cylinder
Consider Moments - Horizontals	Assume Legs Pinned	Use ASCE 10 X-Brace Ly Rules
Consider Moments - Diagonals	✓ Assume Rigid Index Plate	Calculate Redundant Bracing Forces
Use Moment Magnification	Use Clear Spans For Wind Area	Ignore Redundant Members in FEA
✓ Use Code Stress Ratios	Use Clear Spans For KL/r	SR Leg Bolts Resist Compression
Use Code Safety Factors - Guys	Retension Guys To Initial Tension	All Leg Panels Have Same Allowable
Escalate Ice	✓ Bypass Mast Stability Checks	Offset Girt At Foundation
Always Use Max Kz	Use Azimuth Dish Coefficients	Consider Feedline Torque
Use Special Wind Profile	✓ Project Wind Area of Appurt.	Include Angle Block Shear Check
Include Bolts In Member Capacity	Autocalc Torque Arm Areas	Poles
Leg Bolts Are At Top Of Section	SR Members Have Cut Ends	✓ Include Shear-Torsion Interaction
Secondary Horizontal Braces Leg	✓ Sort Capacity Reports By Component	Always Use Sub-Critical Flow
Use Diamond Inner Bracing (4 Sided)	Triangulate Diamond Inner Bracing	Use Top Mounted Sockets
Add IBC .6D+W Combination		

Tapered Pole Section Geometry

Section	Elevation ft	Section Length ft	Splice Length ft	Number of Sides	Top Diameter in	Bottom Diameter in	Wall Thickness in	Bend Radius in	Pole Grade
L1	160.000-123.330	36.670	4.670	12	21.200	31.460	0.219	0.876	A572-65 (65 ksi)
L2	123.330-86.170	41.830	5.830	12	29.715	41.440	0.344	1.376	A572-65 (65 ksi)
L3	86.170-37.170	54.830	7.330	12	39.118	54.460	0.438	1.752	A572-65

RISATower Centek Engineering Inc. 63-2 North Branford Road Branford, CT 06405 Phone: 203.488.0580 FAX: 203.488.8587	Job	11021.CO25 - CT2174 ~ Orange-Central	Page	2 of 22
	Project	160-ft Valmont Monopole - Orange, CT	Date	12:21:23 03/29/11
	Client	AT&T Mobility	Designed by	TJL

Section	Elevation ft	Section Length ft	Splice Length ft	Number of Sides	Top Diameter in	Bottom Diameter in	Wall Thickness in	Bend Radius in	Pole Grade
L4	37.170-0.000	44.500		12	51.533	64.000	0.469	1.876	(65 ksi) A572-65 (65 ksi)

Tapered Pole Properties

Section	Tip Dia. in	Area in ²	I in ⁴	r in	C in	I/C in ³	J in ⁴	It/Q in ²	w in	w/t
L1	21.948	14.795	831.313	7.511	10.982	75.701	1684.465	7.282	5.095	23.263
	32.570	22.031	2744.484	11.184	16.296	168.412	5561.069	10.843	7.844	35.819
L2	32.119	32.534	3582.389	10.515	15.393	232.735	7258.892	16.012	7.042	20.47
	42.902	45.521	9812.935	14.712	21.466	457.140	19883.667	22.404	10.184	29.605
L3	42.187	54.553	10417.699	13.847	20.263	514.122	21109.082	26.849	9.310	21.255
	56.381	76.190	28381.014	19.340	28.210	1006.052	57507.629	37.499	13.421	30.643
L4	55.477	77.116	25666.021	18.281	26.694	961.487	52006.317	37.954	12.554	26.767
	66.258	95.943	49427.852	22.744	33.152	1490.946	100154.229	47.220	15.895	33.891

Tower Elevation ft	Gusset Area (per face) ft ²	Gusset Thickness in	Gusset Grade	Adjust. Factor A _f	Adjust. Factor A _r	Weight Mult.	Double Angle Stitch Bolt Spacing Diagonals in	Double Angle Stitch Bolt Spacing Horizontals in
L1 160.000- 123.330				1	1	1		
L2 123.330- 86.170				1	1	1		
L3 86.170- 37.170				1	1	1		
L4 37.170- 0.000				1	1	1		

Feed Line/Linear Appurtenances - Entered As Area

Description	Face or Leg	Allow Shield	Component Type	Placement ft	Total Number		C _A A _A ft ² /ft	Weight klf
1 1/4 (Nextel Existing)	A	No	Inside Pole	160.000 - 3.000	9	No Ice	0.000	0.001
1 5/8 (Verizon Existing)	B	No	Inside Pole	156.000 - 3.000	12	1/2" Ice	0.000	0.001
1 1/4 (AT&T Existing)	C	No	Inside Pole	146.000 - 3.000	12	No Ice	0.000	0.001
1 5/8 (Sprint Existing)	A	No	Inside Pole	132.000 - 3.000	6	1/2" Ice	0.000	0.001
1 5/8 (T-Mobile Existing)	B	No	Inside Pole	122.000 - 3.000	12	No Ice	0.000	0.001
1 5/8 (Pocket Existing)	C	No	Inside Pole	110.000 - 3.000	6	1/2" Ice	0.000	0.001
1/2 (Sprint Existing)	A	No	Inside Pole	83.500 - 3.000	1	No Ice	0.000	0.000
5/16 (Nextel Existing)	A	No	Inside Pole	160.000 - 3.000	6	1/2" Ice	0.000	0.002
						1/2" Ice	0.000	0.002

RISATower Centek Engineering Inc. 63-2 North Branford Road Branford, CT 06405 Phone: 203.488.0580 FAX: 203.488.8587	Job	11021.CO25 - CT2174 ~ Orange-Central	Page	3 of 22
	Project	160-ft Valmont Monopole - Orange, CT	Date	12:21:23 03/29/11
	Client	AT&T Mobility	Designed by	TJL

Description	Face or Leg	Allow Shield	Component Type	Placement ft	Total Number		$C_A A_A$ ft ² /ft	Weight klf
1/2 (Nextel Existing)	A	No	Inside Pole	160.000 - 3.000	2	No Ice	0.000	0.000
RG6-Fiber	C	No	Inside Pole	147.750 - 3.000	1	1/2" Ice	0.000	0.000
(AT&T - Propsoed)						No Ice	0.000	0.001
#8 AWG Copper Wire	C	No	Inside Pole	147.750 - 3.000	2	1/2" Ice	0.000	0.001
(AT&T - Propsoed)						No Ice	0.000	0.000
						1/2" Ice	0.000	0.000

Feed Line/Linear Appurtenances Section Areas

Tower Section	Tower Elevation ft	Face	A_R ft ²	A_F ft ²	$C_A A_A$ In Face ft ²	$C_A A_A$ Out Face ft ²	Weight K
L1	160.000-123.330	A	0.000	0.000	0.000	0.000	0.730
		B	0.000	0.000	0.000	0.000	0.408
		C	0.000	0.000	0.000	0.000	0.206
L2	123.330-86.170	A	0.000	0.000	0.000	0.000	0.917
		B	0.000	0.000	0.000	0.000	0.911
		C	0.000	0.000	0.000	0.000	0.484
L3	86.170-37.170	A	0.000	0.000	0.000	0.000	1.221
		B	0.000	0.000	0.000	0.000	1.223
		C	0.000	0.000	0.000	0.000	0.748
L4	37.170-0.000	A	0.000	0.000	0.000	0.000	0.852
		B	0.000	0.000	0.000	0.000	0.853
		C	0.000	0.000	0.000	0.000	0.521

Feed Line/Linear Appurtenances Section Areas - With Ice

Tower Section	Tower Elevation ft	Face or Leg	Ice Thickness in	A_R ft ²	A_F ft ²	$C_A A_A$ In Face ft ²	$C_A A_A$ Out Face ft ²	Weight K
L1	160.000-123.330	A	0.500	0.000	0.000	0.000	0.000	0.730
		B		0.000	0.000	0.000	0.000	0.408
		C		0.000	0.000	0.000	0.000	0.206
L2	123.330-86.170	A	0.500	0.000	0.000	0.000	0.000	0.917
		B		0.000	0.000	0.000	0.000	0.911
		C		0.000	0.000	0.000	0.000	0.484
L3	86.170-37.170	A	0.500	0.000	0.000	0.000	0.000	1.221
		B		0.000	0.000	0.000	0.000	1.223
		C		0.000	0.000	0.000	0.000	0.748
L4	37.170-0.000	A	0.500	0.000	0.000	0.000	0.000	0.852
		B		0.000	0.000	0.000	0.000	0.853
		C		0.000	0.000	0.000	0.000	0.521

Discrete Tower Loads

<i>RISATower</i> <i>Centek Engineering Inc.</i> 63-2 North Branford Road Branford, CT 06405 Phone: 203.488.0580 FAX: 203.488.8587	Job	11021.CO25 - CT2174 ~ Orange-Central	Page 4 of 22
	Project	160-ft Valmont Monopole - Orange, CT	Date 12:21:23 03/29/11
	Client	AT&T Mobility	Designed by TJL

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment °	Placement ft		C _{AA} Front ft ²	C _{AA} Side ft ²	Weight K
(5) 8'x2 1/2" Pipe Mount (Nextel Existing)	A	From Face	3.000 0.000 0.000	0.000	163.000	No Ice 1/2" Ice	2.300 3.132	2.300 3.132	0.041 0.057
(5) 8'x2 1/2" Pipe Mount (Nextel Existing)	B	From Face	3.000 0.000 0.000	0.000	163.000	No Ice 1/2" Ice	2.300 3.132	2.300 3.132	0.041 0.057
(4) 8'x2 1/2" Pipe Mount (Nextel Existing)	C	From Face	3.000 0.000 0.000	0.000	163.000	No Ice 1/2" Ice	2.300 3.132	2.300 3.132	0.041 0.057
(3) DB844H90E-XY (Nextel Existing)	A	From Face	3.000 0.000 0.000	0.000	167.000	No Ice 1/2" Ice	2.867 3.177	3.733 4.101	0.010 0.035
(3) DB844H90E-XY (Nextel Existing)	B	From Face	3.000 0.000 0.000	0.000	167.000	No Ice 1/2" Ice	2.867 3.177	3.733 4.101	0.010 0.035
(3) DB844H90E-XY (Nextel Existing)	C	From Face	3.000 0.000 0.000	0.000	167.000	No Ice 1/2" Ice	2.867 3.177	3.733 4.101	0.010 0.035
LLPX310R (Nextel Existing)	A	From Face	3.000 0.000 0.000	0.000	167.000	No Ice 1/2" Ice	4.830 5.183	1.945 2.214	0.029 0.055
LLPX310R (Nextel Existing)	B	From Face	3.000 0.000 0.000	0.000	167.000	No Ice 1/2" Ice	4.830 5.183	1.945 2.214	0.029 0.055
LLPX310R (Nextel Existing)	C	From Face	3.000 0.000 0.000	0.000	167.000	No Ice 1/2" Ice	4.830 5.183	1.945 2.214	0.029 0.055
Remote Radio Head FD R6 RRH (Nextel Existing)	A	From Face	3.000 0.000 0.000	0.000	167.000	No Ice 1/2" Ice	1.804 1.988	0.778 0.918	0.033 0.045
Remote Radio Head FD R6 RRH (Nextel Existing)	A	From Face	3.000 0.000 0.000	0.000	167.000	No Ice 1/2" Ice	1.804 1.988	0.778 0.918	0.033 0.045
Remote Radio Head FD R6 RRH (Nextel Existing)	A	From Face	3.000 0.000 0.000	0.000	167.000	No Ice 1/2" Ice	1.804 1.988	0.778 0.918	0.033 0.045
13' Platform w/Rails (Verizon Existing)	C	None		0.000	155.200	No Ice 1/2" Ice	23.900 30.800	23.900 30.800	2.000 3.000
DB948F85T2E-M (Verizon Existing)	A	From Face	3.000 -4.000 0.000	0.000	155.200	No Ice 1/2" Ice	1.920 2.219	3.256 3.617	0.009 0.028
DB948F85T2E-M (Verizon Existing)	A	From Face	3.000 4.000 0.000	0.000	155.200	No Ice 1/2" Ice	1.920 2.219	3.256 3.617	0.009 0.028
DB948F85T2E-M (Verizon Existing)	B	From Face	3.000 -4.000 0.000	0.000	155.200	No Ice 1/2" Ice	1.920 2.219	3.256 3.617	0.009 0.028
DB948F85T2E-M (Verizon Existing)	B	From Face	3.000 4.000 0.000	0.000	155.200	No Ice 1/2" Ice	1.920 2.219	3.256 3.617	0.009 0.028
DB948F85T2E-M (Verizon Existing)	C	From Face	3.000 -4.000 0.000	0.000	155.200	No Ice 1/2" Ice	1.920 2.219	3.256 3.617	0.009 0.028
DB948F85T2E-M (Verizon Existing)	C	From Face	3.000 4.000 0.000	0.000	155.200	No Ice 1/2" Ice	1.920 2.219	3.256 3.617	0.009 0.028
LPA-80063/6CF	A	From Face	3.000	0.000	155.200	No Ice	10.308	9.005	0.027

<i>RISATower</i> <i>Centek Engineering Inc.</i> 63-2 North Branford Road Branford, CT 06405 Phone: 203.488.0580 FAX: 203.488.8587	Job	11021.CO25 - CT2174 ~ Orange-Central	Page	5 of 22
	Project	160-ft Valmont Monopole - Orange, CT	Date	12:21:23 03/29/11
	Client	AT&T Mobility	Designed by	TJL

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment °	Placement ft		C _A A _A Front ft ²	C _A A _A Side ft ²	Weight K
(Verizon Existing)			-6.000 0.000			1/2" Ice	10.868	9.554	0.101
LPA-80063/6CF (Verizon Existing)	A	From Face	3.000 6.000 0.000	0.000	155.200	No Ice 1/2" Ice	10.308 10.868	9.005 9.554	0.027 0.101
LPA-80063/6CF (Verizon Existing)	B	From Face	3.000 -6.000 0.000	0.000	155.200	No Ice 1/2" Ice	10.308 10.868	9.005 9.554	0.027 0.101
LPA-80063/6CF (Verizon Existing)	B	From Face	3.000 6.000 0.000	0.000	155.200	No Ice 1/2" Ice	10.308 10.868	9.005 9.554	0.027 0.101
LPA-80063/6CF (Verizon Existing)	C	From Face	3.000 -6.000 0.000	0.000	155.200	No Ice 1/2" Ice	10.308 10.868	9.005 9.554	0.027 0.101
LPA-80063/6CF (Verizon Existing)	C	From Face	3.000 6.000 0.000	0.000	155.200	No Ice 1/2" Ice	10.308 10.868	9.005 9.554	0.027 0.101
13' Platform w/Rails (AT&T Existing)	C	None		0.000	143.700	No Ice	17.200	17.200	2.000
7770.00 (AT&T Existing)	A	From Face	3.000 -6.000 0.000	0.000	145.700	1/2" Ice No Ice 1/2" Ice	22.300 5.882 6.314	22.300 2.928 3.273	3.000 0.035 0.068
7770.00 (AT&T Existing)	A	From Face	3.000 2.000 0.000	0.000	145.700	No Ice 1/2" Ice	5.882 6.314	2.928 3.273	0.035 0.068
P65-16-XLH-RR (AT&T Proposed)	A	From Face	3.000 6.000 0.000	0.000	145.700	No Ice 1/2" Ice	8.400 8.949	4.700 5.147	0.060 0.107
7770.00 (AT&T Existing)	B	From Face	3.000 -6.000 0.000	0.000	145.700	No Ice 1/2" Ice	5.882 6.314	2.928 3.273	0.035 0.068
7770.00 (AT&T Existing)	B	From Face	3.000 2.000 0.000	0.000	145.700	No Ice 1/2" Ice	5.882 6.314	2.928 3.273	0.035 0.068
P65-16-XLH-RR (AT&T Proposed)	B	From Face	3.000 6.000 0.000	0.000	145.700	No Ice 1/2" Ice	8.400 8.949	4.700 5.147	0.060 0.107
7770.00 (AT&T Existing)	C	From Face	3.000 -6.000 0.000	0.000	145.700	No Ice 1/2" Ice	5.882 6.314	2.928 3.273	0.035 0.068
7770.00 (AT&T Existing)	C	From Face	3.000 2.000 0.000	0.000	145.700	No Ice 1/2" Ice	5.882 6.314	2.928 3.273	0.035 0.068
P65-16-XLH-RR (AT&T Proposed)	C	From Face	3.000 6.000 0.000	0.000	145.700	No Ice 1/2" Ice	8.400 8.949	4.700 5.147	0.060 0.107
(2) LGP214nn TMA (AT&T Existing)	A	From Face	3.000 0.000 0.000	0.000	145.700	No Ice 1/2" Ice	1.288 1.445	0.233 0.313	0.014 0.021
(2) LGP214nn TMA (AT&T Existing)	B	From Face	3.000 0.000 0.000	0.000	145.700	No Ice 1/2" Ice	1.288 1.445	0.233 0.313	0.014 0.021
(2) LGP214nn TMA (AT&T Existing)	C	From Face	3.000 0.000 0.000	0.000	145.700	No Ice 1/2" Ice	1.288 1.445	0.233 0.313	0.014 0.021
(4) LGP21901 Diplexer (AT&T Existing)	A	From Face	3.000 0.000	0.000	145.700	No Ice 1/2" Ice	0.233 0.302	0.117 0.166	0.006 0.008

RISATower Centek Engineering Inc. 63-2 North Branford Road Branford, CT 06405 Phone: 203.488.0580 FAX: 203.488.8587	Job	11021.CO25 - CT2174 ~ Orange-Central	Page	6 of 22
	Project	160-ft Valmont Monopole - Orange, CT	Date	12:21:23 03/29/11
	Client	AT&T Mobility	Designed by	TJL

<i>Description</i>	<i>Face or Leg</i>	<i>Offset Type</i>	<i>Offsets: Horz Lateral Vert ft ft ft</i>	<i>Azimuth Adjustment °</i>	<i>Placement ft</i>		<i>C_AA_A Front ft²</i>	<i>C_AA_A Side ft²</i>	<i>Weight K</i>
(4) LGP21901 Diplexer (AT&T Existing)	B	From Face	0.000 3.000 0.000 0.000	0.000	145.700	No Ice 1/2" Ice	0.233 0.302	0.117 0.166	0.006 0.008
(4) LGP21901 Diplexer (AT&T Existing)	C	From Face	0.000 3.000 0.000 0.000	0.000	145.700	No Ice 1/2" Ice	0.233 0.302	0.117 0.166	0.006 0.008
(2) RRUS-11 (AT&T - Proposed)	A	From Face	0.500 0.000 0.000	0.000	147.750	No Ice 1/2" Ice	2.994 3.226	1.246 1.412	0.050 0.070
(2) RRUS-11 (AT&T - Proposed)	B	From Face	0.500 0.000 0.000	0.000	147.750	No Ice 1/2" Ice	2.994 3.226	1.246 1.412	0.050 0.070
(2) RRUS-11 (AT&T - Proposed)	C	From Face	0.500 0.000 0.000	0.000	147.750	No Ice 1/2" Ice	2.994 3.226	1.246 1.412	0.050 0.070
DC6-48-60-18-8F Surge Arrestor (AT&T - Proposed)	C	From Face	0.500 0.000 0.000	0.000	147.750	No Ice 1/2" Ice	2.228 2.447	2.228 2.447	0.020 0.039
Valmont Uni-Tri Bracket (AT&T - Proposed)	C	None		0.000	147.750	No Ice 1/2" Ice	1.750 1.940	1.750 1.940	0.290 0.306
13' Platform w/Rails (Sprint Existing)	C	None		0.000	131.800	No Ice 1/2" Ice	17.200 22.300	17.200 22.300	2.000 3.000
(2) DB980H90E-M (Sprint Existing)	A	From Face	3.000 0.000 0.000	0.000	134.100	No Ice 1/2" Ice	3.799 4.178	2.194 2.556	0.009 0.029
(2) DB980H90E-M (Sprint Existing)	B	From Face	3.000 0.000 0.000	0.000	134.100	No Ice 1/2" Ice	3.799 4.178	2.194 2.556	0.009 0.029
(2) DB980H90E-M (Sprint Existing)	C	From Face	3.000 0.000 0.000	0.000	134.100	No Ice 1/2" Ice	3.799 4.178	2.194 2.556	0.009 0.029
13' Platform w/Rails (T-Mobile Existing)	C	None		0.000	119.000	No Ice 1/2" Ice	17.200 22.300	17.200 22.300	2.000 3.000
APX16DWV-16DWV-S-E- ACU (T-Mobile Existing)	A	From Face	3.000 2.000 0.000	0.000	121.900	No Ice 1/2" Ice	6.699 7.131	2.003 2.326	0.040 0.071
APX16DWV-16DWV-S-E- ACU (T-Mobile Existing)	B	From Face	3.000 2.000 0.000	0.000	121.900	No Ice 1/2" Ice	6.699 7.131	2.003 2.326	0.040 0.071
APX16DWV-16DWV-S-E- ACU (T-Mobile Existing)	C	From Face	3.000 2.000 0.000	0.000	121.900	No Ice 1/2" Ice	6.699 7.131	2.003 2.326	0.040 0.071
(2) RR90-17-02DP (T-Mobile Existing)	A	From Face	3.000 0.000 0.000	0.000	121.900	No Ice 1/2" Ice	4.356 4.775	1.974 2.312	0.018 0.040
(2) RR90-17-02DP (T-Mobile Existing)	B	From Face	3.000 0.000 0.000	0.000	121.900	No Ice 1/2" Ice	4.356 4.775	1.974 2.312	0.018 0.040
(2) RR90-17-02DP (T-Mobile Existing)	C	From Face	3.000 0.000 0.000	0.000	121.900	No Ice 1/2" Ice	4.356 4.775	1.974 2.312	0.018 0.040
(2) 10"x8"x3" TMA (T-Mobile Existing)	A	From Face	3.000 0.000 0.000	0.000	121.900	No Ice 1/2" Ice	0.778 0.899	0.292 0.380	0.015 0.020
(2) 10"x8"x3" TMA (T-Mobile Existing)	B	From Face	3.000 0.000 0.000	0.000	121.900	No Ice 1/2" Ice	0.778 0.899	0.292 0.380	0.015 0.020

RISATower Centek Engineering Inc. 63-2 North Branford Road Branford, CT 06405 Phone: 203.488.0580 FAX: 203.488.8587	Job	11021.CO25 - CT2174 ~ Orange-Central	Page	7 of 22
	Project	160-ft Valmont Monopole - Orange, CT	Date	12:21:23 03/29/11
	Client	AT&T Mobility	Designed by	TJL

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment °	Placement ft		C _{AA} Front ft ²	C _{AA} Side ft ²	Weight K
(2) 10"x8"x3" TMA (T-Mobile Existing)	C	From Face	0.000 3.000 0.000 0.000	0.000	121.900	No Ice 1/2" Ice	0.778 0.899	0.292 0.380	0.015 0.020
Stand-off	C	From Face	0.000 1.000 0.000 0.000	0.000	83.400	No Ice 1/2" Ice	0.750 0.950	0.750 0.950	0.027 0.036
Stand-off	A	From Face	0.000 1.000 0.000 0.000	0.000	83.400	No Ice 1/2" Ice	0.750 0.950	0.750 0.950	0.027 0.036
GPS (Sprint Existing)	A	From Face	0.000 2.000 0.000 0.000	0.000	83.400	No Ice 1/2" Ice	1.000 1.500	1.000 1.500	0.010 0.015
APXV18-206517LS (Pocket Existing)	A	From Face	0.000 1.000 0.000 0.000	0.000	110.000	No Ice 1/2" Ice	5.049 5.497	3.011 3.441	0.028 0.054
APXV18-206517LS (Pocket Existing)	B	From Face	0.000 1.000 0.000 0.000	0.000	110.000	No Ice 1/2" Ice	5.049 5.497	3.011 3.441	0.028 0.054
APXV18-206517LS (Pocket Existing)	C	From Face	0.000 1.000 0.000 0.000	0.000	110.000	No Ice 1/2" Ice	5.049 5.497	3.011 3.441	0.028 0.054

Dishes

Description	Face or Leg	Dish Type	Offset Type	Offsets: Horz Lateral Vert ft	Azimuth Adjustment °	3 dB Beam Width °	Elevation ft	Outside Diameter ft	Aperture Area ft²	Weight K	
A-Ant-23G-2-C (Nextel Existing)	A	Paraboloid w/Radome	From Face	3.000 0.000 0.000	Worst		167.000	2.175	No Ice 1/2" Ice	3.715 4.006	0.027 0.050
A-Ant-23G-2-C (Nextel Existing)	C	Paraboloid w/Radome	From Face	3.000 0.000 0.000	Worst		167.000	2.175	No Ice 1/2" Ice	3.715 4.006	0.027 0.050

Tower Pressures - No Ice

$$G_H = 1.690$$

Section Elevation	z	K _Z	q _z	A _G	F a c e	A _F	A _R	A _{leg}	Leg %	C _{AA} In Face ft ²	C _{AA} Out Face ft ²
ft	ft		ksf	ft ²	e	ft ²	ft ²	ft ²			
L1 160.000- 123.330	140.642	1.513	0.031	80.460	A B	0.000 0.000	80.460 80.460	80.460	100.00 100.00	0.000 0.000	0.000 0.000

RISATower Centek Engineering Inc. 63-2 North Branford Road Branford, CT 06405 Phone: 203.488.0580 FAX: 203.488.8587	Job	11021.CO25 - CT2174 ~ Orange-Central	Page 8 of 22
	Project	160-ft Valmont Monopole - Orange, CT	Date 12:21:23 03/29/11
	Client	AT&T Mobility	Designed by TJL

Section Elevation	z	K _Z	q _z	A _G	F a c e	A _F	A _R	A _{leg}	Leg %	C _A A _A In Face ft ²	C _A A _A Out Face ft ²
ft	ft		ksf	ft ²		ft ²	ft ²	ft ²			
L2 123.330- 86.170	104.095	1.389	0.029	112.199	C	0.000	80.460		100.00	0.000	0.000
					A	0.000	112.199	112.199	100.00	0.000	0.000
					B	0.000	112.199		100.00	0.000	0.000
L3 86.170- 37.170	61.198	1.193	0.025	194.385	C	0.000	112.199		100.00	0.000	0.000
					A	0.000	194.385	194.385	100.00	0.000	0.000
					B	0.000	194.385		100.00	0.000	0.000
L4 37.170- 0.000	18.036	1	0.021	182.112	C	0.000	194.385		100.00	0.000	0.000
					A	0.000	182.112	182.112	100.00	0.000	0.000
					B	0.000	182.112		100.00	0.000	0.000
					C	0.000	182.112		100.00	0.000	0.000

Tower Pressure - With Ice

$$G_H = 1.690$$

Section Elevation	z	K _Z	q _z	t _z	A _G	F a c e	A _F	A _R	A _{leg}	Leg %	C _A A _A In Face ft ²	C _A A _A Out Face ft ²
ft	ft		ksf	in	ft ²		ft ²	ft ²	ft ²			
L1 160.000- 123.330	140.642	1.513	0.024	0.500	83.516	A	0.000	83.516	83.516	100.00	0.000	0.000
						B	0.000	83.516		100.00	0.000	0.000
						C	0.000	83.516		100.00	0.000	0.000
L2 123.330- 86.170	104.095	1.389	0.022	0.500	115.296	A	0.000	115.296	115.296	100.00	0.000	0.000
						B	0.000	115.296		100.00	0.000	0.000
						C	0.000	115.296		100.00	0.000	0.000
L3 86.170- 37.170	61.198	1.193	0.018	0.500	198.469	A	0.000	198.469	198.469	100.00	0.000	0.000
						B	0.000	198.469		100.00	0.000	0.000
						C	0.000	198.469		100.00	0.000	0.000
L4 37.170-0.000	18.036	1	0.016	0.500	185.210	A	0.000	185.210	185.210	100.00	0.000	0.000
						B	0.000	185.210		100.00	0.000	0.000
						C	0.000	185.210		100.00	0.000	0.000

Tower Pressure - Service

$$G_H = 1.690$$

Section Elevation	z	K _Z	q _z	A _G	F a c e	A _F	A _R	A _{leg}	Leg %	C _A A _A In Face ft ²	C _A A _A Out Face ft ²
ft	ft		ksf	ft ²		ft ²	ft ²	ft ²			
L1 160.000- 123.330	140.642	1.513	0.010	80.460	A	0.000	80.460	80.460	100.00	0.000	0.000
					B	0.000	80.460		100.00	0.000	0.000
					C	0.000	80.460		100.00	0.000	0.000
L2 123.330- 86.170	104.095	1.389	0.009	112.199	A	0.000	112.199	112.199	100.00	0.000	0.000
					B	0.000	112.199		100.00	0.000	0.000
					C	0.000	112.199		100.00	0.000	0.000
L3 86.170- 37.170	61.198	1.193	0.008	194.385	A	0.000	194.385	194.385	100.00	0.000	0.000
					B	0.000	194.385		100.00	0.000	0.000
					C	0.000	194.385		100.00	0.000	0.000
L4 37.170- 0.000	18.036	1	0.006	182.112	A	0.000	182.112	182.112	100.00	0.000	0.000
					B	0.000	182.112		100.00	0.000	0.000
					C	0.000	182.112		100.00	0.000	0.000

RISATower Centek Engineering Inc. 63-2 North Branford Road Branford, CT 06405 Phone: 203.488.0580 FAX: 203.488.8587	Job	11021.CO25 - CT2174 ~ Orange-Central	Page	9 of 22
	Project	160-ft Valmont Monopole - Orange, CT	Date	12:21:23 03/29/11
	Client	AT&T Mobility	Designed by	TJL

Tower Forces - No Ice - Wind Normal To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	K	K							ft ²	K	klf	
L1 160.000- 123.330	1.344	2.298	A	1	1.03	1	1	1	80.460	4.391	0.120	C
			B	1	1.03	1	1	1	80.460			
			C	1	1.03	1	1	1	80.460			
L2 123.330- 86.170	2.312	5.555	A	1	1.03	1	1	1	112.199	5.615	0.151	C
			B	1	1.03	1	1	1	112.199			
			C	1	1.03	1	1	1	112.199			
L3 86.170- 37.170	3.192	12.197	A	1	1.03	1	1	1	194.385	8.308	0.170	C
			B	1	1.03	1	1	1	194.385			
			C	1	1.03	1	1	1	194.385			
L4 37.170- 0.000	2.226	13.103	A	1	1.03	1	1	1	182.112	6.573	0.177	C
			B	1	1.03	1	1	1	182.112			
			C	1	1.03	1	1	1	182.112			
Sum Weight:	9.074	33.152						OTM	1829.090 kip-ft	24.888		

Tower Forces - No Ice - Wind 45 To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	K	K							ft ²	K	klf	
L1 160.000- 123.330	1.344	2.298	A	1	1.03	1	1	1	80.460	4.391	0.120	C
			B	1	1.03	1	1	1	80.460			
			C	1	1.03	1	1	1	80.460			
L2 123.330- 86.170	2.312	5.555	A	1	1.03	1	1	1	112.199	5.615	0.151	C
			B	1	1.03	1	1	1	112.199			
			C	1	1.03	1	1	1	112.199			
L3 86.170- 37.170	3.192	12.197	A	1	1.03	1	1	1	194.385	8.308	0.170	C
			B	1	1.03	1	1	1	194.385			
			C	1	1.03	1	1	1	194.385			
L4 37.170- 0.000	2.226	13.103	A	1	1.03	1	1	1	182.112	6.573	0.177	C
			B	1	1.03	1	1	1	182.112			
			C	1	1.03	1	1	1	182.112			
Sum Weight:	9.074	33.152						OTM	1829.090 kip-ft	24.888		

Tower Forces - No Ice - Wind 60 To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	K	K							ft ²	K	klf	
L1 160.000- 123.330	1.344	2.298	A	1	1.03	1	1	1	80.460	4.391	0.120	C
			B	1	1.03	1	1	1	80.460			
			C	1	1.03	1	1	1	80.460			
L2 123.330-	2.312	5.555	A	1	1.03	1	1	1	112.199	5.615	0.151	C

RISATower Centek Engineering Inc. 63-2 North Branford Road Branford, CT 06405 Phone: 203.488.0580 FAX: 203.488.8587	Job	11021.CO25 - CT2174 ~ Orange-Central	Page	10 of 22
	Project	160-ft Valmont Monopole - Orange, CT	Date	12:21:23 03/29/11
	Client	AT&T Mobility	Designed by	TJL

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	K	K							ft ²	K	klf	
86.170			B	1	1.03	1	1	1	112.199			
			C	1	1.03	1	1	1	112.199			
L3 86.170-	3.192	12.197	A	1	1.03	1	1	1	194.385	8.308	0.170	C
37.170			B	1	1.03	1	1	1	194.385			
			C	1	1.03	1	1	1	194.385			
L4 37.170-	2.226	13.103	A	1	1.03	1	1	1	182.112	6.573	0.177	C
0.000			B	1	1.03	1	1	1	182.112			
			C	1	1.03	1	1	1	182.112			
Sum Weight:	9.074	33.152						OTM	1829.090 kip-ft	24.888		

Tower Forces - No Ice - Wind 90 To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	K	K							ft ²	K	klf	
L1 160.000-	1.344	2.298	A	1	1.03	1	1	1	80.460	4.391	0.120	C
123.330			B	1	1.03	1	1	1	80.460			
			C	1	1.03	1	1	1	80.460			
L2 123.330-	2.312	5.555	A	1	1.03	1	1	1	112.199	5.615	0.151	C
86.170			B	1	1.03	1	1	1	112.199			
			C	1	1.03	1	1	1	112.199			
L3 86.170-	3.192	12.197	A	1	1.03	1	1	1	194.385	8.308	0.170	C
37.170			B	1	1.03	1	1	1	194.385			
			C	1	1.03	1	1	1	194.385			
L4 37.170-	2.226	13.103	A	1	1.03	1	1	1	182.112	6.573	0.177	C
0.000			B	1	1.03	1	1	1	182.112			
			C	1	1.03	1	1	1	182.112			
Sum Weight:	9.074	33.152						OTM	1829.090 kip-ft	24.888		

Tower Forces - With Ice - Wind Normal To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	K	K							ft ²	K	klf	
L1 160.000-	1.344	2.914	A	1	1.03	1	1	1	83.516	3.418	0.093	C
123.330			B	1	1.03	1	1	1	83.516			
			C	1	1.03	1	1	1	83.516			
L2 123.330-	2.312	6.410	A	1	1.03	1	1	1	115.296	4.328	0.116	C
86.170			B	1	1.03	1	1	1	115.296			
			C	1	1.03	1	1	1	115.296			
L3 86.170-	3.192	13.673	A	1	1.03	1	1	1	198.469	6.362	0.130	C
37.170			B	1	1.03	1	1	1	198.469			
			C	1	1.03	1	1	1	198.469			
L4 37.170-	2.226	14.483	A	1	1.03	1	1	1	185.210	5.014	0.135	C
0.000			B	1	1.03	1	1	1	185.210			
			C	1	1.03	1	1	1	185.210			
Sum Weight:	9.074	37.478						OTM	1411.032	19.122		

RISATower Centek Engineering Inc. 63-2 North Branford Road Branford, CT 06405 Phone: 203.488.0580 FAX: 203.488.8587	Job	11021.CO25 - CT2174 ~ Orange-Central	Page	11 of 22
	Project	160-ft Valmont Monopole - Orange, CT	Date	12:21:23 03/29/11
	Client	AT&T Mobility	Designed by	TJL

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	K	K							ft ²	K	klf	
									kip-ft			

Tower Forces - With Ice - Wind 45 To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	K	K							ft ²	K	klf	
L1 160.000- 123.330	1.344	2.914	A	1	1.03	1	1	1	83.516	3.418	0.093	C
			B	1	1.03	1	1	1	83.516			
			C	1	1.03	1	1	1	83.516			
L2 123.330- 86.170	2.312	6.410	A	1	1.03	1	1	1	115.296	4.328	0.116	C
			B	1	1.03	1	1	1	115.296			
			C	1	1.03	1	1	1	115.296			
L3 86.170- 37.170	3.192	13.673	A	1	1.03	1	1	1	198.469	6.362	0.130	C
			B	1	1.03	1	1	1	198.469			
			C	1	1.03	1	1	1	198.469			
L4 37.170- 0.000	2.226	14.483	A	1	1.03	1	1	1	185.210	5.014	0.135	C
			B	1	1.03	1	1	1	185.210			
			C	1	1.03	1	1	1	185.210			
Sum Weight:	9.074	37.478						OTM	1411.032 kip-ft	19.122		

Tower Forces - With Ice - Wind 60 To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	K	K							ft ²	K	klf	
L1 160.000- 123.330	1.344	2.914	A	1	1.03	1	1	1	83.516	3.418	0.093	C
			B	1	1.03	1	1	1	83.516			
			C	1	1.03	1	1	1	83.516			
L2 123.330- 86.170	2.312	6.410	A	1	1.03	1	1	1	115.296	4.328	0.116	C
			B	1	1.03	1	1	1	115.296			
			C	1	1.03	1	1	1	115.296			
L3 86.170- 37.170	3.192	13.673	A	1	1.03	1	1	1	198.469	6.362	0.130	C
			B	1	1.03	1	1	1	198.469			
			C	1	1.03	1	1	1	198.469			
L4 37.170- 0.000	2.226	14.483	A	1	1.03	1	1	1	185.210	5.014	0.135	C
			B	1	1.03	1	1	1	185.210			
			C	1	1.03	1	1	1	185.210			
Sum Weight:	9.074	37.478						OTM	1411.032 kip-ft	19.122		

Tower Forces - With Ice - Wind 90 To Face

RISATower Centek Engineering Inc. 63-2 North Branford Road Branford, CT 06405 Phone: 203.488.0580 FAX: 203.488.8587	Job	Page
	11021.CO25 - CT2174 ~ Orange-Central	12 of 22
	Project 160-ft Valmont Monopole - Orange, CT	Date 12:21:23 03/29/11
	Client AT&T Mobility	Designed by TJL

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	K	K							ft ²	K	klf	
L1 160.000- 123.330	1.344	2.914	A	1	1.03	1	1	1	83.516	3.418	0.093	C
			B	1	1.03	1	1	1	83.516			
			C	1	1.03	1	1	1	83.516			
L2 123.330- 86.170	2.312	6.410	A	1	1.03	1	1	1	115.296	4.328	0.116	C
			B	1	1.03	1	1	1	115.296			
			C	1	1.03	1	1	1	115.296			
L3 86.170- 37.170	3.192	13.673	A	1	1.03	1	1	1	198.469	6.362	0.130	C
			B	1	1.03	1	1	1	198.469			
			C	1	1.03	1	1	1	198.469			
L4 37.170- 0.000	2.226	14.483	A	1	1.03	1	1	1	185.210	5.014	0.135	C
			B	1	1.03	1	1	1	185.210			
			C	1	1.03	1	1	1	185.210			
Sum Weight:	9.074	37.478						OTM	1411.032 kip-ft	19.122		

Tower Forces - Service - Wind Normal To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	K	K							ft ²	K	klf	
L1 160.000- 123.330	1.344	2.298	A	1	1.03	1	1	1	80.460	1.355	0.037	C
			B	1	1.03	1	1	1	80.460			
			C	1	1.03	1	1	1	80.460			
L2 123.330- 86.170	2.312	5.555	A	1	1.03	1	1	1	112.199	1.733	0.047	C
			B	1	1.03	1	1	1	112.199			
			C	1	1.03	1	1	1	112.199			
L3 86.170- 37.170	3.192	12.197	A	1	1.03	1	1	1	194.385	2.564	0.052	C
			B	1	1.03	1	1	1	194.385			
			C	1	1.03	1	1	1	194.385			
L4 37.170- 0.000	2.226	13.103	A	1	1.03	1	1	1	182.112	2.029	0.055	C
			B	1	1.03	1	1	1	182.112			
			C	1	1.03	1	1	1	182.112			
Sum Weight:	9.074	33.152						OTM	564.534 kip-ft	7.681		

Tower Forces - Service - Wind 45 To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	K	K							ft ²	K	klf	
L1 160.000- 123.330	1.344	2.298	A	1	1.03	1	1	1	80.460	1.355	0.037	C
			B	1	1.03	1	1	1	80.460			
			C	1	1.03	1	1	1	80.460			
L2 123.330- 86.170	2.312	5.555	A	1	1.03	1	1	1	112.199	1.733	0.047	C
			B	1	1.03	1	1	1	112.199			
			C	1	1.03	1	1	1	112.199			
L3 86.170- 37.170	3.192	12.197	A	1	1.03	1	1	1	194.385	2.564	0.052	C
			B	1	1.03	1	1	1	194.385			
			C	1	1.03	1	1	1	194.385			

RISATower Centek Engineering Inc. 63-2 North Branford Road Branford, CT 06405 Phone: 203.488.0580 FAX: 203.488.8587	Job	11021.CO25 - CT2174 ~ Orange-Central	Page	13 of 22
	Project	160-ft Valmont Monopole - Orange, CT	Date	12:21:23 03/29/11
	Client	AT&T Mobility	Designed by	TJL

Section Elevation	Add Weight	Self Weight	Face	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	K	K							ft ²	K	klf	
L4 37.170-0.000	2.226	13.103	A	1	1.03	1	1	1	182.112	2.029	0.055	C
			B	1	1.03	1	1	1	182.112			
			C	1	1.03	1	1	1	182.112			
Sum Weight:	9.074	33.152						OTM	564.534 kip-ft	7.681		

Tower Forces - Service - Wind 60 To Face

Section Elevation	Add Weight	Self Weight	Face	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	K	K							ft ²	K	klf	
L1 160.000-123.330	1.344	2.298	A	1	1.03	1	1	1	80.460	1.355	0.037	C
			B	1	1.03	1	1	1	80.460			
			C	1	1.03	1	1	1	80.460			
L2 123.330-86.170	2.312	5.555	A	1	1.03	1	1	1	112.199	1.733	0.047	C
			B	1	1.03	1	1	1	112.199			
			C	1	1.03	1	1	1	112.199			
L3 86.170-37.170	3.192	12.197	A	1	1.03	1	1	1	194.385	2.564	0.052	C
			B	1	1.03	1	1	1	194.385			
			C	1	1.03	1	1	1	194.385			
L4 37.170-0.000	2.226	13.103	A	1	1.03	1	1	1	182.112	2.029	0.055	C
			B	1	1.03	1	1	1	182.112			
			C	1	1.03	1	1	1	182.112			
Sum Weight:	9.074	33.152						OTM	564.534 kip-ft	7.681		

Tower Forces - Service - Wind 90 To Face

Section Elevation	Add Weight	Self Weight	Face	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	K	K							ft ²	K	klf	
L1 160.000-123.330	1.344	2.298	A	1	1.03	1	1	1	80.460	1.355	0.037	C
			B	1	1.03	1	1	1	80.460			
			C	1	1.03	1	1	1	80.460			
L2 123.330-86.170	2.312	5.555	A	1	1.03	1	1	1	112.199	1.733	0.047	C
			B	1	1.03	1	1	1	112.199			
			C	1	1.03	1	1	1	112.199			
L3 86.170-37.170	3.192	12.197	A	1	1.03	1	1	1	194.385	2.564	0.052	C
			B	1	1.03	1	1	1	194.385			
			C	1	1.03	1	1	1	194.385			
L4 37.170-0.000	2.226	13.103	A	1	1.03	1	1	1	182.112	2.029	0.055	C
			B	1	1.03	1	1	1	182.112			
			C	1	1.03	1	1	1	182.112			
Sum Weight:	9.074	33.152						OTM	564.534 kip-ft	7.681		

Force Totals

Load Case	Vertical Forces K	Sum of Forces X K	Sum of Forces Z K	Sum of Overturning Moments, M_x kip-ft	Sum of Overturning Moments, M_z kip-ft	Sum of Torques kip-ft
Leg Weight	33.152					
Bracing Weight	0.000					
Total Member Self-Weight	33.152			-0.250	0.520	
Total Weight	53.022			-0.250	0.520	
Wind 0 deg - No Ice		-0.074	-44.582	-4720.844	12.924	-1.266
Wind 30 deg - No Ice		22.269	-38.572	-4082.202	-2356.196	-1.224
Wind 45 deg - No Ice		31.532	-31.471	-3329.442	-3338.801	-1.076
Wind 60 deg - No Ice		38.646	-22.226	-2349.804	-4093.836	-0.854
Wind 90 deg - No Ice		44.667	0.074	12.154	-4734.397	-0.255
Wind 120 deg - No Ice		38.720	22.355	2370.789	-4106.241	0.412
Wind 135 deg - No Ice		31.637	31.576	3346.485	-3356.343	0.715
Wind 150 deg - No Ice		22.398	38.646	4094.106	-2377.681	0.969
Wind 180 deg - No Ice		0.074	44.582	4720.343	-11.885	1.266
Wind 210 deg - No Ice		-22.269	38.572	4081.701	2357.236	1.224
Wind 225 deg - No Ice		-31.532	31.471	3328.942	3339.840	1.076
Wind 240 deg - No Ice		-38.646	22.226	2349.304	4094.876	0.854
Wind 270 deg - No Ice		-44.667	-0.074	-12.655	4735.437	0.255
Wind 300 deg - No Ice		-38.720	-22.355	-2371.290	4107.280	-0.412
Wind 315 deg - No Ice		-31.637	-31.576	-3346.985	3357.383	-0.715
Wind 330 deg - No Ice		-22.398	-38.646	-4094.606	2378.721	-0.969
Member Ice	4.326					
Total Weight Ice	63.554			-0.304	0.751	
Wind 0 deg - Ice		-0.058	-36.274	-3927.994	10.443	-1.116
Wind 30 deg - Ice		18.120	-31.386	-3396.938	-1960.296	-1.140
Wind 45 deg - Ice		25.656	-25.609	-2770.748	-2777.605	-1.035
Wind 60 deg - Ice		31.444	-18.087	-1955.756	-3405.573	-0.859
Wind 90 deg - Ice		36.341	0.058	9.387	-3938.129	-0.348
Wind 120 deg - Ice		31.502	18.187	1971.934	-3415.264	0.256
Wind 135 deg - Ice		25.738	25.691	2783.845	-2791.310	0.543
Wind 150 deg - Ice		18.221	31.444	3406.021	-1977.081	0.792
Wind 180 deg - Ice		0.058	36.274	3927.386	-8.940	1.116
Wind 210 deg - Ice		-18.120	31.386	3396.330	1961.799	1.140
Wind 225 deg - Ice		-25.656	25.609	2770.139	2779.108	1.035
Wind 240 deg - Ice		-31.444	18.087	1955.148	3407.076	0.859
Wind 270 deg - Ice		-36.341	-0.058	-9.995	3939.632	0.348
Wind 300 deg - Ice		-31.502	-18.187	-1972.542	3416.767	-0.256
Wind 315 deg - Ice		-25.738	-25.691	-2784.453	2792.813	-0.543
Wind 330 deg - Ice		-18.221	-31.444	-3406.629	1978.584	-0.792
Total Weight	53.022			-0.250	0.520	
Wind 0 deg - Service		-0.023	-13.760	-1457.224	4.348	-0.391
Wind 30 deg - Service		6.873	-11.905	-1260.112	-726.862	-0.378
Wind 45 deg - Service		9.732	-9.713	-1027.779	-1030.135	-0.332
Wind 60 deg - Service		11.928	-6.860	-725.421	-1263.170	-0.264
Wind 90 deg - Service		13.786	0.023	3.578	-1460.874	-0.079
Wind 120 deg - Service		11.951	6.900	731.552	-1266.999	0.127
Wind 135 deg - Service		9.765	9.746	1032.693	-1035.549	0.221
Wind 150 deg - Service		6.913	11.928	1263.440	-733.493	0.299
Wind 180 deg - Service		0.023	13.760	1456.723	-3.309	0.391
Wind 210 deg - Service		-6.873	11.905	1259.611	727.901	0.378
Wind 225 deg - Service		-9.732	9.713	1027.278	1031.174	0.332
Wind 240 deg - Service		-11.928	6.860	724.921	1264.210	0.264
Wind 270 deg - Service		-13.786	-0.023	-4.079	1461.914	0.079
Wind 300 deg - Service		-11.951	-6.900	-732.053	1268.039	-0.127
Wind 315 deg - Service		-9.765	-9.746	-1033.193	1036.589	-0.221
Wind 330 deg - Service		-6.913	-11.928	-1263.940	734.533	-0.299

<i>RISATower</i> <i>Centek Engineering Inc.</i> 63-2 North Branford Road Branford, CT 06405 Phone: 203.488.0580 FAX: 203.488.8587	Job 11021.CO25 - CT2174 ~ Orange-Central	Page 15 of 22
	Project 160-ft Valmont Monopole - Orange, CT	Date 12:21:23 03/29/11
	Client AT&T Mobility	Designed by TJL

Load Combinations

<i>Comb. No.</i>	<i>Description</i>
1	Dead Only
2	Dead+Wind 0 deg - No Ice
3	Dead+Wind 30 deg - No Ice
4	Dead+Wind 45 deg - No Ice
5	Dead+Wind 60 deg - No Ice
6	Dead+Wind 90 deg - No Ice
7	Dead+Wind 120 deg - No Ice
8	Dead+Wind 135 deg - No Ice
9	Dead+Wind 150 deg - No Ice
10	Dead+Wind 180 deg - No Ice
11	Dead+Wind 210 deg - No Ice
12	Dead+Wind 225 deg - No Ice
13	Dead+Wind 240 deg - No Ice
14	Dead+Wind 270 deg - No Ice
15	Dead+Wind 300 deg - No Ice
16	Dead+Wind 315 deg - No Ice
17	Dead+Wind 330 deg - No Ice
18	Dead+Ice+Temp
19	Dead+Wind 0 deg+Ice+Temp
20	Dead+Wind 30 deg+Ice+Temp
21	Dead+Wind 45 deg+Ice+Temp
22	Dead+Wind 60 deg+Ice+Temp
23	Dead+Wind 90 deg+Ice+Temp
24	Dead+Wind 120 deg+Ice+Temp
25	Dead+Wind 135 deg+Ice+Temp
26	Dead+Wind 150 deg+Ice+Temp
27	Dead+Wind 180 deg+Ice+Temp
28	Dead+Wind 210 deg+Ice+Temp
29	Dead+Wind 225 deg+Ice+Temp
30	Dead+Wind 240 deg+Ice+Temp
31	Dead+Wind 270 deg+Ice+Temp
32	Dead+Wind 300 deg+Ice+Temp
33	Dead+Wind 315 deg+Ice+Temp
34	Dead+Wind 330 deg+Ice+Temp
35	Dead+Wind 0 deg - Service
36	Dead+Wind 30 deg - Service
37	Dead+Wind 45 deg - Service
38	Dead+Wind 60 deg - Service
39	Dead+Wind 90 deg - Service
40	Dead+Wind 120 deg - Service
41	Dead+Wind 135 deg - Service
42	Dead+Wind 150 deg - Service
43	Dead+Wind 180 deg - Service
44	Dead+Wind 210 deg - Service
45	Dead+Wind 225 deg - Service
46	Dead+Wind 240 deg - Service
47	Dead+Wind 270 deg - Service
48	Dead+Wind 300 deg - Service
49	Dead+Wind 315 deg - Service
50	Dead+Wind 330 deg - Service

Maximum Member Forces

RISATower Centek Engineering Inc. 63-2 North Branford Road Branford, CT 06405 Phone: 203.488.0580 FAX: 203.488.8587	Job	11021.CO25 - CT2174 ~ Orange-Central	Page	16 of 22
	Project	160-ft Valmont Monopole - Orange, CT	Date	12:21:23 03/29/11
	Client	AT&T Mobility	Designed by	TJL

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Force K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
L1	160 - 123.33	Pole	Max Tension	1	0.000	0.000	0.000
			Max. Compression	18	-16.831	0.619	0.326
			Max. Mx	14	-9.859	481.502	3.220
			Max. My	2	-9.873	3.340	477.946
			Max. Vy	14	-20.983	481.502	3.220
			Max. Vx	2	-20.894	3.340	477.946
			Max. Torque	11			-1.141
			Max Tension	1	0.000	0.000	0.000
L2	123.33 - 86.17	Pole	Max. Compression	18	-28.496	0.619	0.326
			Max. Mx	14	-19.498	1423.675	6.035
			Max. My	2	-19.508	6.186	1416.896
			Max. Vy	14	-29.748	1423.675	6.035
			Max. Vx	2	-29.658	6.186	1416.896
			Max. Torque	2			1.108
			Max Tension	1	0.000	0.000	0.000
			Max. Compression	18	-44.256	0.752	0.305
L3	86.17 - 37.17	Pole	Max. Mx	14	-34.519	3024.748	9.693
			Max. My	2	-34.523	9.968	3013.620
			Max. Vy	14	-37.573	3024.748	9.693
			Max. Vx	2	-37.484	9.968	3013.620
			Max. Torque	2			1.334
			Max Tension	1	0.000	0.000	0.000
			Max. Compression	18	-63.554	0.752	0.305
			Max. Mx	14	-53.001	4854.795	13.058
L4	37.17 - 0	Pole	Max. My	2	-53.001	13.335	4839.783
			Max. Vy	14	-44.693	4854.795	13.058
			Max. Vx	2	-44.607	13.335	4839.783
			Max. Torque	2			1.331

Maximum Reactions

Location	Condition	Gov. Load Comb.	Vertical K	Horizontal, X K	Horizontal, Z K
Pole	Max. Vert	31	63.554	36.341	0.058
	Max. H _x	14	53.022	44.667	0.074
	Max. H _z	2	53.022	0.074	44.582
	Max. M _x	2	4839.783	0.074	44.582
	Max. M _z	6	4853.707	-44.667	-0.074
	Max. Torsion	2	1.331	0.074	44.582
	Min. Vert	1	53.022	0.000	0.000
	Min. H _x	6	53.022	-44.667	-0.074
	Min. H _z	10	53.022	-0.074	-44.582
	Min. M _x	10	-4839.256	-0.074	-44.582
	Min. M _z	14	-4854.795	44.667	0.074
	Min. Torsion	11	-1.260	22.269	-38.572

Tower Mast Reaction Summary

Load Combination	Vertical K	Shear _x K	Shear _z K	Overturning Moment, M _x kip-ft	Overturning Moment, M _z kip-ft	Torque kip-ft
Dead Only	53.022	0.000	0.000	-0.250	0.520	0.000

RISATower Centek Engineering Inc. 63-2 North Branford Road Branford, CT 06405 Phone: 203.488.0580 FAX: 203.488.8587	Job	Page
	11021.CO25 - CT2174 ~ Orange-Central	17 of 22
	Project	Date
	160-ft Valmont Monopole - Orange, CT	12:21:23 03/29/11
	Client	Designed by
	AT&T Mobility	TJL

Load Combination	Vertical K	Shear _x K	Shear _y K	Overturning Moment, M _x kip-ft	Overturning Moment, M _y kip-ft	Torque kip-ft
Dead+Wind 0 deg - No Ice	53.022	-0.074	-44.582	-4839.783	13.335	-1.331
Dead+Wind 30 deg - No Ice	53.022	22.269	-38.572	-4185.032	-2415.537	-1.260
Dead+Wind 45 deg - No Ice	53.022	31.532	-31.471	-3413.285	-3422.927	-1.091
Dead+Wind 60 deg - No Ice	53.022	38.646	-22.226	-2408.943	-4197.003	-0.851
Dead+Wind 90 deg - No Ice	53.022	44.667	0.074	12.531	-4853.707	-0.242
Dead+Wind 120 deg - No Ice	53.022	38.720	22.355	2430.545	-4209.743	0.404
Dead+Wind 135 deg - No Ice	53.022	31.637	31.576	3430.800	-3440.970	0.694
Dead+Wind 150 deg - No Ice	53.022	22.398	38.646	4197.245	-2437.666	0.942
Dead+Wind 180 deg - No Ice	53.022	0.074	44.582	4839.256	-12.254	1.255
Dead+Wind 210 deg - No Ice	53.022	-22.269	38.572	4184.509	2416.620	1.260
Dead+Wind 225 deg - No Ice	53.022	-31.532	31.471	3412.761	3424.012	1.134
Dead+Wind 240 deg - No Ice	53.022	-38.646	22.226	2408.419	4198.090	0.927
Dead+Wind 270 deg - No Ice	53.022	-44.667	-0.074	-13.058	4854.795	0.318
Dead+Wind 300 deg - No Ice	53.022	-38.720	-22.355	-2431.075	4210.830	-0.404
Dead+Wind 315 deg - No Ice	53.022	-31.637	-31.576	-3431.331	3442.054	-0.738
Dead+Wind 330 deg - No Ice	53.022	-22.398	-38.646	-4197.776	2438.749	-1.017
Dead+Ice+Temp	63.554	0.000	0.000	-0.305	0.752	0.000
Dead+Wind 0 deg+Ice+Temp	63.554	-0.058	-36.274	-4067.015	10.920	-1.182
Dead+Wind 30 deg+Ice+Temp	63.554	18.120	-31.386	-3517.131	-2029.627	-1.190
Dead+Wind 45 deg+Ice+Temp	63.554	25.656	-25.609	-2868.758	-2875.894	-1.070
Dead+Wind 60 deg+Ice+Temp	63.554	31.444	-18.087	-2024.905	-3526.111	-0.879
Dead+Wind 90 deg+Ice+Temp	63.554	36.341	0.058	9.793	-4077.544	-0.351
Dead+Wind 120 deg+Ice+Temp	63.554	31.502	18.187	2041.760	-3536.199	0.252
Dead+Wind 135 deg+Ice+Temp	63.554	25.738	25.691	2882.384	-2890.174	0.537
Dead+Wind 150 deg+Ice+Temp	63.554	18.221	31.444	3526.563	-2047.137	0.788
Dead+Wind 180 deg+Ice+Temp	63.554	0.058	36.274	4066.359	-9.320	1.131
Dead+Wind 210 deg+Ice+Temp	63.554	-18.120	31.386	3516.478	2031.229	1.190
Dead+Wind 225 deg+Ice+Temp	63.554	-25.656	25.609	2868.106	2877.497	1.099
Dead+Wind 240 deg+Ice+Temp	63.554	-31.444	18.087	2024.253	3527.717	0.930
Dead+Wind 270 deg+Ice+Temp	63.554	-36.341	-0.058	-10.447	4079.152	0.402
Dead+Wind 300 deg+Ice+Temp	63.554	-31.502	-18.187	-2042.418	3537.806	-0.252
Dead+Wind 315 deg+Ice+Temp	63.554	-25.738	-25.691	-2883.044	2891.780	-0.566
Dead+Wind 330 deg+Ice+Temp	63.554	-18.221	-31.444	-3527.223	2048.740	-0.839
Dead+Wind 0 deg - Service	53.022	-0.023	-13.760	-1495.328	4.501	-0.406
Dead+Wind 30 deg - Service	53.022	6.873	-11.905	-1293.051	-745.844	-0.392
Dead+Wind 45 deg - Service	53.022	9.732	-9.713	-1054.639	-1057.055	-0.344
Dead+Wind 60 deg - Service	53.022	11.928	-6.860	-744.372	-1296.193	-0.273
Dead+Wind 90 deg - Service	53.022	13.786	0.023	3.689	-1499.081	-0.084
Dead+Wind 120 deg - Service	53.022	11.951	6.900	750.690	-1300.146	0.126
Dead+Wind 135 deg - Service	53.022	9.765	9.746	1059.699	-1062.646	0.221
Dead+Wind 150 deg - Service	53.022	6.913	11.928	1296.474	-752.692	0.301
Dead+Wind 180 deg - Service	53.022	0.023	13.760	1494.799	-3.407	0.399
Dead+Wind 210 deg - Service	53.022	-6.873	11.905	1292.522	746.937	0.392
Dead+Wind 225 deg - Service	53.022	-9.732	9.713	1054.109	1058.149	0.348
Dead+Wind 240 deg - Service	53.022	-11.928	6.860	743.843	1297.287	0.280
Dead+Wind 270 deg - Service	53.022	-13.786	-0.023	-4.219	1500.175	0.091
Dead+Wind 300 deg - Service	53.022	-11.951	-6.900	-751.220	1301.239	-0.126
Dead+Wind 315 deg - Service	53.022	-9.765	-9.746	-1060.229	1063.740	-0.225
Dead+Wind 330 deg - Service	53.022	-6.913	-11.928	-1297.004	753.785	-0.309

Solution Summary

Load Comb.	Sum of Applied Forces			Sum of Reactions			% Error
	PX K	PY K	PZ K	PX K	PY K	PZ K	
1	0.000	-53.022	0.000	0.000	53.022	0.000	0.000%
2	-0.074	-53.022	-44.582	0.074	53.022	44.582	0.000%
3	22.269	-53.022	-38.572	-22.269	53.022	38.572	0.000%

RISATower Centek Engineering Inc. 63-2 North Branford Road Branford, CT 06405 Phone: 203.488.0580 FAX: 203.488.8587	Job	11021.CO25 - CT2174 ~ Orange-Central	Page	18 of 22
	Project	160-ft Valmont Monopole - Orange, CT	Date	12:21:23 03/29/11
	Client	AT&T Mobility	Designed by	TJL

Load Comb.	Sum of Applied Forces			Sum of Reactions			% Error
	PX K	PY K	PZ K	PX K	PY K	PZ K	
4	31.532	-53.022	-31.471	-31.532	53.022	31.471	0.000%
5	38.646	-53.022	-22.226	-38.646	53.022	22.226	0.000%
6	44.667	-53.022	0.074	-44.667	53.022	-0.074	0.000%
7	38.720	-53.022	22.355	-38.720	53.022	-22.355	0.000%
8	31.637	-53.022	31.576	-31.637	53.022	-31.576	0.000%
9	22.398	-53.022	38.646	-22.398	53.022	-38.646	0.000%
10	0.074	-53.022	44.582	-0.074	53.022	-44.582	0.000%
11	-22.269	-53.022	38.572	22.269	53.022	-38.572	0.000%
12	-31.532	-53.022	31.471	31.532	53.022	-31.471	0.000%
13	-38.646	-53.022	22.226	38.646	53.022	-22.226	0.000%
14	-44.667	-53.022	-0.074	44.667	53.022	0.074	0.000%
15	-38.720	-53.022	-22.355	38.720	53.022	22.355	0.000%
16	-31.637	-53.022	-31.576	31.637	53.022	31.576	0.000%
17	-22.398	-53.022	-38.646	22.398	53.022	38.646	0.000%
18	0.000	-63.554	0.000	0.000	63.554	0.000	0.000%
19	-0.058	-63.554	-36.274	0.058	63.554	36.274	0.000%
20	18.120	-63.554	-31.386	-18.120	63.554	31.386	0.000%
21	25.656	-63.554	-25.609	-25.656	63.554	25.609	0.000%
22	31.444	-63.554	-18.087	-31.444	63.554	18.087	0.000%
23	36.341	-63.554	0.058	-36.341	63.554	-0.058	0.000%
24	31.502	-63.554	18.187	-31.502	63.554	-18.187	0.000%
25	25.738	-63.554	25.691	-25.738	63.554	-25.691	0.000%
26	18.221	-63.554	31.444	-18.221	63.554	-31.444	0.000%
27	0.058	-63.554	36.274	-0.058	63.554	-36.274	0.000%
28	-18.120	-63.554	31.386	18.120	63.554	-31.386	0.000%
29	-25.656	-63.554	25.609	25.656	63.554	-25.609	0.000%
30	-31.444	-63.554	18.087	31.444	63.554	-18.087	0.000%
31	-36.341	-63.554	-0.058	36.341	63.554	0.058	0.000%
32	-31.502	-63.554	-18.187	31.502	63.554	18.187	0.000%
33	-25.738	-63.554	-25.691	25.738	63.554	25.691	0.000%
34	-18.221	-63.554	-31.444	18.221	63.554	31.444	0.000%
35	-0.023	-53.022	-13.760	0.023	53.022	13.760	0.000%
36	6.873	-53.022	-11.905	-6.873	53.022	11.905	0.000%
37	9.732	-53.022	-9.713	-9.732	53.022	9.713	0.000%
38	11.928	-53.022	-6.860	-11.928	53.022	6.860	0.000%
39	13.786	-53.022	0.023	-13.786	53.022	-0.023	0.000%
40	11.951	-53.022	6.900	-11.951	53.022	-6.900	0.000%
41	9.765	-53.022	9.746	-9.765	53.022	-9.746	0.000%
42	6.913	-53.022	11.928	-6.913	53.022	-11.928	0.000%
43	0.023	-53.022	13.760	-0.023	53.022	-13.760	0.000%
44	-6.873	-53.022	11.905	6.873	53.022	-11.905	0.000%
45	-9.732	-53.022	9.713	9.732	53.022	-9.713	0.000%
46	-11.928	-53.022	6.860	11.928	53.022	-6.860	0.000%
47	-13.786	-53.022	-0.023	13.786	53.022	0.023	0.000%
48	-11.951	-53.022	-6.900	11.951	53.022	6.900	0.000%
49	-9.765	-53.022	-9.746	9.765	53.022	9.746	0.000%
50	-6.913	-53.022	-11.928	6.913	53.022	11.928	0.000%

Non-Linear Convergence Results

Load Combination	Converged?	Number of Cycles	Displacement Tolerance	Force Tolerance
1	Yes	4	0.00000001	0.00000001
2	Yes	4	0.00000001	0.00030961
3	Yes	5	0.00000001	0.00019918
4	Yes	5	0.00000001	0.00022387

RISATower Centek Engineering Inc. 63-2 North Branford Road Branford, CT 06405 Phone: 203.488.0580 FAX: 203.488.8587	Job	Page
	11021.CO25 - CT2174 ~ Orange-Central	19 of 22
	Project	Date
	160-ft Valmont Monopole - Orange, CT	12:21:23 03/29/11
	Client	Designed by
	AT&T Mobility	TJL

5	Yes	5	0.00000001	0.00020595
6	Yes	4	0.00000001	0.00006459
7	Yes	5	0.00000001	0.00020713
8	Yes	5	0.00000001	0.00022638
9	Yes	5	0.00000001	0.00020285
10	Yes	4	0.00000001	0.00018739
11	Yes	5	0.00000001	0.00020704
12	Yes	5	0.00000001	0.00022390
13	Yes	5	0.00000001	0.00020045
14	Yes	4	0.00000001	0.00013560
15	Yes	5	0.00000001	0.00020503
16	Yes	5	0.00000001	0.00022667
17	Yes	5	0.00000001	0.00020913
18	Yes	4	0.00000001	0.00000001
19	Yes	5	0.00000001	0.00012707
20	Yes	5	0.00000001	0.00046357
21	Yes	5	0.00000001	0.00053057
22	Yes	5	0.00000001	0.00047530
23	Yes	5	0.00000001	0.00012587
24	Yes	5	0.00000001	0.00047790
25	Yes	5	0.00000001	0.00053688
26	Yes	5	0.00000001	0.00047216
27	Yes	5	0.00000001	0.00012624
28	Yes	5	0.00000001	0.00047701
29	Yes	5	0.00000001	0.00053092
30	Yes	5	0.00000001	0.00046556
31	Yes	5	0.00000001	0.00012624
32	Yes	5	0.00000001	0.00047657
33	Yes	5	0.00000001	0.00053813
34	Yes	5	0.00000001	0.00048201
35	Yes	4	0.00000001	0.00004917
36	Yes	4	0.00000001	0.00034444
37	Yes	4	0.00000001	0.00041548
38	Yes	4	0.00000001	0.00037204
39	Yes	4	0.00000001	0.00003085
40	Yes	4	0.00000001	0.00037209
41	Yes	4	0.00000001	0.00042240
42	Yes	4	0.00000001	0.00035479
43	Yes	4	0.00000001	0.00004468
44	Yes	4	0.00000001	0.00037712
45	Yes	4	0.00000001	0.00041594
46	Yes	4	0.00000001	0.00034950
47	Yes	4	0.00000001	0.00003246
48	Yes	4	0.00000001	0.00036433
49	Yes	4	0.00000001	0.00042482
50	Yes	4	0.00000001	0.00038163

Maximum Tower Deflections - Service Wind

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
L1	160 - 123.33	27.581	48	1.711	0.004
L2	128 - 86.17	16.986	48	1.366	0.001
L3	92 - 37.17	8.327	48	0.895	0.001
L4	44.5 - 0	1.880	48	0.385	0.000

<i>RISATower</i> <i>Centek Engineering Inc.</i> 63-2 North Branford Road Branford, CT 06405 Phone: 203.488.0580 FAX: 203.488.8387	Job	11021.CO25 - CT2174 ~ Orange-Central	Page	20 of 22
	Project	160-ft Valmont Monopole - Orange, CT	Date	12:21:23 03/29/11
	Client	AT&T Mobility	Designed by	TJL

Critical Deflections and Radius of Curvature - Service Wind

<i>Elevation</i>	<i>Appurtenance</i>	<i>Gov. Load Comb.</i>	<i>Deflection in</i>	<i>Tilt °</i>	<i>Twist °</i>	<i>Radius of Curvature ft</i>
<i>ft</i>						
167.000	A-Ant-23G-2-C	48	27.581	1.711	0.004	22772
163.000	(5) 8"x2 1/2" Pipe Mount	48	27.581	1.711	0.004	22772
155.200	13' Platform w/Rails	48	25.908	1.663	0.004	22772
147.750	(2) RRUS-11	48	23.337	1.586	0.003	9294
145.700	7770.00	48	22.640	1.565	0.003	7962
143.700	13' Platform w/Rails	48	21.967	1.544	0.002	6985
134.100	(2) DB980H90E-M	48	18.845	1.438	0.002	4395
131.800	13' Platform w/Rails	48	18.130	1.412	0.001	4039
121.900	APX16DWV-16DWV-S-E-ACU	48	15.247	1.290	0.001	3751
119.000	13' Platform w/Rails	48	14.463	1.253	0.001	3851
110.000	APXV18-206517LS	48	12.193	1.133	0.001	4199
83.400	Stand-off	48	6.761	0.790	0.000	5085

Maximum Tower Deflections - Design Wind

<i>Section No.</i>	<i>Elevation ft</i>	<i>Horz. Deflection in</i>	<i>Gov. Load Comb.</i>	<i>Tilt °</i>	<i>Twist °</i>
L1	160 - 123.33	89.018	15	5.521	0.013
L2	128 - 86.17	54.878	15	4.415	0.004
L3	92 - 37.17	26.924	15	2.895	0.002
L4	44.5 - 0	6.083	15	1.246	0.001

Critical Deflections and Radius of Curvature - Design Wind

<i>Elevation</i>	<i>Appurtenance</i>	<i>Gov. Load Comb.</i>	<i>Deflection in</i>	<i>Tilt °</i>	<i>Twist °</i>	<i>Radius of Curvature ft</i>
<i>ft</i>						
167.000	A-Ant-23G-2-C	15	89.018	5.521	0.013	7197
163.000	(5) 8"x2 1/2" Pipe Mount	15	89.018	5.521	0.013	7197
155.200	13' Platform w/Rails	15	83.626	5.365	0.011	7197
147.750	(2) RRUS-11	15	75.346	5.121	0.009	2936
145.700	7770.00	15	73.101	5.052	0.008	2515
143.700	13' Platform w/Rails	15	70.932	4.985	0.008	2206
134.100	(2) DB980H90E-M	15	60.870	4.646	0.005	1386
131.800	13' Platform w/Rails	15	58.568	4.560	0.005	1273
121.900	APX16DWV-16DWV-S-E-ACU	15	49.271	4.169	0.003	1179
119.000	13' Platform w/Rails	15	46.740	4.049	0.003	1210
110.000	APXV18-206517LS	15	39.413	3.663	0.002	1315
83.400	Stand-off	15	21.864	2.555	0.002	1580

Compression Checks

RISATower Centek Engineering Inc. 63-2 North Branford Road Branford, CT 06405 Phone: 203.488.0580 FAX: 203.488.8587	Job	11021.CO25 - CT2174 ~ Orange-Central	Page	21 of 22
	Project	160-ft Valmont Monopole - Orange, CT	Date	12:21:23 03/29/11
	Client	AT&T Mobility	Designed by	TJL

Pole Design Data

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	F _a ksi	A in ²	Actual P K	Allow. P _a K	Ratio P P _a
L1	160 - 123.33 (1)	TP31.46x21.2x0.219	36.670	0.000	0.0	36.424	21.109	-9.852	768.877	0.013
L2	123.33 - 86.17 (2)	TP41.44x29.715x0.344	41.830	0.000	0.0	39.000	43.711	-19.493	1704.730	0.011
L3	86.17 - 37.17 (3)	TP54.46x39.118x0.438	54.830	0.000	0.0	39.000	73.298	-34.516	2858.610	0.012
L4	37.17 - 0 (4)	TP64x51.533x0.469	44.500	0.000	0.0	36.617	95.943	-53.001	3513.170	0.015

Pole Bending Design Data

Section No.	Elevation ft	Size	Actual M _x kip-ft	Actual f _{bx} ksi	Allow. F _{bx} ksi	Ratio f _{bx} F _{bx}	Actual M _y kip-ft	Actual f _{by} ksi	Allow. F _{by} ksi	Ratio f _{by} F _{by}
L1	160 - 123.33 (1)	TP31.46x21.2x0.219	483.281	37.519	36.424	1.030	0.000	0.000	36.424	0.000
L2	123.33 - 86.17 (2)	TP41.44x29.715x0.344	1427.067	40.641	39.000	1.042	0.000	0.000	39.000	0.000
L3	86.17 - 37.17 (3)	TP54.46x39.118x0.438	3030.233	39.066	39.000	1.002	0.000	0.000	39.000	0.000
L4	37.17 - 0 (4)	TP64x51.533x0.469	4862.225	39.134	36.617	1.069	0.000	0.000	36.617	0.000

Pole Shear Design Data

Section No.	Elevation ft	Size	Actual V K	Actual f _v ksi	Allow. F _v ksi	Ratio f _v F _v	Actual T kip-ft	Actual f _{vt} ksi	Allow. F _{vt} ksi	Ratio f _{vt} F _{vt}
L1	160 - 123.33 (1)	TP31.46x21.2x0.219	21.028	0.996	26.000	0.078	0.325	0.012	26.000	0.000
L2	123.33 - 86.17 (2)	TP41.44x29.715x0.344	29.793	0.682	26.000	0.053	0.324	0.004	26.000	0.000
L3	86.17 - 37.17 (3)	TP54.46x39.118x0.438	37.617	0.513	26.000	0.040	0.404	0.002	26.000	0.000
L4	37.17 - 0 (4)	TP64x51.533x0.469	44.736	0.466	26.000	0.036	0.404	0.002	26.000	0.000

Pole Interaction Design Data

Section No.	Elevation ft	Ratio P P _a	Ratio f _{bx} F _{bx}	Ratio f _{by} F _{by}	Ratio f _v F _v	Ratio f _{vt} F _{vt}	Comb. Stress Ratio	Allow. Stress Ratio	Criteria
L1	160 - 123.33 (1)	0.013	1.030	0.000	0.078	0.000	1.044 ✓	1.333	H1-3+VT ✓
L2	123.33 - 86.17 (2)	0.011	1.042	0.000	0.053	0.000	1.054 ✓	1.333	H1-3+VT ✓
L3	86.17 - 37.17 (3)	0.012	1.002	0.000	0.040	0.000	1.014 ✓	1.333	H1-3+VT ✓

RISATower Centek Engineering Inc. 63-2 North Branford Road Branford, CT 06405 Phone: 203.488.0580 FAX: 203.488.8587	Job	11021.CO25 - CT2174 ~ Orange-Central	Page	22 of 22
	Project	160-ft Valmont Monopole - Orange, CT	Date	12:21:23 03/29/11
	Client	AT&T Mobility	Designed by	TJL

Section No.	Elevation ft	Ratio $\frac{P}{P_a}$	Ratio $\frac{f_{bc}}{F_{bc}}$	Ratio $\frac{f_{bv}}{F_{bv}}$	Ratio $\frac{f_v}{F_v}$	Ratio $\frac{f_{vt}}{F_{vt}}$	Comb. Stress Ratio	Allow. Stress Ratio	Criteria
L4	37.17 - 0 (4)	0.015	1.069	0.000	0.036	0.000	1.084 ✓	1.333	H1-3+VT ✓

Section Capacity Table

Section No.	Elevation ft	Component Type	Size	Critical Element	P K	SF* P_{allow} K	% Capacity	Pass Fail
L1	160 - 123.33	Pole	TP31.46x21.2x0.219	1	-9.852	1024.913	78.3	Pass
L2	123.33 - 86.17	Pole	TP41.44x29.715x0.344	2	-19.493	2272.405	79.1	Pass
L3	86.17 - 37.17	Pole	TP54.46x39.118x0.438	3	-34.516	3810.527	76.1	Pass
L4	37.17 - 0	Pole	TP64x51.533x0.469	4	-53.001	4683.055	81.3	Pass
							Summary	
							Pole (L4)	81.3 Pass
							RATING =	81.3 Pass

Anchor Bolt and Base Plate Analysis:**Input Data:**Tower Reactions:

Overturning Moment =	OM := 4862-ft-kips	(Input From RisaTower)
Shear Force =	Shear := 45-kips	(Input From RisaTower)
Axial Force =	Axial := 53-kips	(Input From RisaTower)

Anchor Bolt Data:

Use ASTM A615 Grade 75

Number of Anchor Bolts =	N := 24	(User Input)
Diameter of Bolt Circle =	$D_{bc} := 72.76\text{-in}$	(User Input)
Bolt "Column" Distance =	$l := 3.0\text{-in}$	(User Input)
Bolt Ultimate Strenght =	$F_u := 100\text{-ksi}$	(User Input)
Bolt Yeild Strenght =	$F_y := 75\text{-ksi}$	(User Input)
Bolt Modulus =	$E := 29000\text{-ksi}$	(User Input)
Diameter of Anchor Bolts =	$D := 2.25\text{-in}$	(User Input)
Threads per Inch =	$n := 4.5$	(User Input)

Base Plate Data:

Use ASTM A572 Mod 60

Plate Yield Strength =	$F_{ybp} := 60\text{-ksi}$	(User Input)
Base Plate Thickness =	$t_{bp} := 3.0\text{-in}$	(User Input)
Base Plate Diameter =	$D_{bp} := 78.76\text{-in}$	(User Input)
Outer Pole Diameter =	$D_{pole} := 64.0\text{-in}$	(User Input)

Geometric Layout Data:

Distance from Bolts to Centroid of Pole:

Radius of Bolt Circle =:

$$R_{bc} := \frac{D_{bc}}{2} = 36.38 \cdot \text{in}$$

Distance to Bolts =

$$i := 1 \dots N$$

$$d_i := \begin{cases} \theta \leftarrow 2 \cdot \pi \cdot \left(\frac{i}{N} \right) \\ d \leftarrow R_{bc} \cdot \sin(\theta) \end{cases}$$

$$d_1 = 9.42 \cdot \text{in}$$

$$d_7 = 35.14 \cdot \text{in}$$

$$d_2 = 18.19 \cdot \text{in}$$

$$d_8 = 31.51 \cdot \text{in}$$

$$d_3 = 25.72 \cdot \text{in}$$

$$d_9 = 25.72 \cdot \text{in}$$

$$d_4 = 31.51 \cdot \text{in}$$

$$d_{10} = 18.19 \cdot \text{in}$$

$$d_5 = 35.14 \cdot \text{in}$$

$$d_{11} = 9.42 \cdot \text{in}$$

$$d_6 = 36.38 \cdot \text{in}$$

etc.

Critical Distances For Bending in Plate:

Outer Pole Radius =

$$R_{pole} := \frac{D_{pole}}{2} = 32 \cdot \text{in}$$

Moment Arms of Bolts about Neutral Axis =

$$MA_i := \text{if}(d_i \geq R_{pole}, d_i - R_{pole}, 0 \cdot \text{in})$$

$$MA_1 = 0.00 \cdot \text{in}$$

$$MA_7 = 3.14 \cdot \text{in}$$

$$MA_2 = 0.00 \cdot \text{in}$$

$$MA_8 = 0.00 \cdot \text{in}$$

$$MA_3 = 0.00 \cdot \text{in}$$

$$MA_9 = 0.00 \cdot \text{in}$$

$$MA_4 = 0.00 \cdot \text{in}$$

$$MA_{10} = 0.00 \cdot \text{in}$$

$$MA_5 = 3.14 \cdot \text{in}$$

$$MA_{11} = 0.00 \cdot \text{in}$$

$$MA_6 = 4.38 \cdot \text{in}$$

etc

Effective Width of Baseplate for Bending =

$$B_{eff} := .8 \cdot 2 \cdot \sqrt{\left(\frac{D_{bp}}{2} \right)^2 - \left(\frac{D_{pole}}{2} \right)^2} = 36.7 \cdot \text{in}$$

Anchor Bolt Analysis:

Calculated Anchor Bolt Properties:

Polar Moment of Inertia =

$$I_p := \sum_i (d_i)^2 = 1.588 \times 10^4 \cdot \text{in}^2$$

Gross Area of Bolt =

$$A_g := \frac{\pi}{4} \cdot D^2 = 3.976 \cdot \text{in}^2$$

Net Area of Bolt =

$$A_n := \frac{\pi}{4} \cdot \left(D - \frac{0.9743 \cdot \text{in}}{n} \right)^2 = 3.248 \cdot \text{in}^2$$

Net Diameter =

$$D_n := \frac{2 \cdot \sqrt{A_n}}{\sqrt{\pi}} = 2.033 \cdot \text{in}$$

Radius of Gyration of Bolt =

$$r := \frac{D_n}{4} = 0.508 \cdot \text{in}$$

Section Modulus of Bolt =

$$S_x := \frac{\pi \cdot D_n^3}{32} = 0.826 \cdot \text{in}^3$$

Check Anchor Bolt Tension Force:

Maximum Tensile Force =

$$T_{\text{Max}} := OM \cdot \frac{R_{bc}}{I_p} - \frac{\text{Axial}}{N} = 131.4 \cdot \text{kips}$$

Allowable Tensile Force =

$$T_{\text{ALL.Gross}} := 1.333 \cdot (0.33 \cdot A_g \cdot F_u) = 174.9 \cdot \text{kips} \quad (1.333 \text{ increase allowed per TIA/EIA})$$

$$T_{\text{ALL.Net}} := 1.333 \cdot (0.60 \cdot A_n \cdot F_y) = 194.812 \cdot \text{kips} \quad (1.333 \text{ increase allowed per TIA/EIA})$$

Bolt Tension % of Capacity =

$$\frac{T_{\text{Max}}}{T_{\text{ALL.Net}}} = 67.5\% \quad \text{Bolts are "upset bolts". Use net area per AISC}$$

Condition1 =

$$\text{Condition1} := \text{if} \left(\frac{T_{\text{Max}}}{T_{\text{ALL.Net}}} \leq 1.00, \text{"OK"}, \text{"Overstressed"} \right)$$

Condition1 = "OK"

Check Anchor Bolt Bending Stress:

Maximum Bending Moment =

$$M_x := \left(\frac{\text{Shear}}{N} \right) \cdot l = 0.469 \cdot \text{ft} \cdot \text{kips}$$

Maximum Bending Stress =

$$f_{bx} := \frac{M_x}{S_x} = 6.8 \cdot \text{ksi}$$

Allowable Bending Stress =

$$F_{bx} := 1.333 \cdot 0.6 \cdot F_y = 60 \cdot \text{ksi} \quad (1.333 \text{ increase allowed per TIA/EIA})$$

Check Combined Stress Requirement:

Per ASCE Manual 72: "If the clearance between the base plate and concrete does not exceed two times the bolt diameter a bending stress analysis of the bolts is NOT normally required."

$$l := \begin{cases} l & \text{if } l > 2 \cdot D_n \\ 0 & \text{otherwise} \end{cases} = 0 \cdot \text{in}$$

$$f_{bx} := \begin{cases} f_{bx} & \text{if } l > 2 \cdot D_n \\ 0 & \text{otherwise} \end{cases} = 0 \cdot \text{ksi}$$

Check Anchor Bolt Compression/Combined Stress:

Maximum Compressive Force =

$$C_{Max} := OM \cdot \frac{R_{bc}}{l_p} + \frac{\text{Axial}}{N} = 135.9 \cdot \text{kips}$$

Maximum Compressive Stress =

$$f_a := \frac{C_{Max}}{A_n} = 41.8 \cdot \text{ksi}$$

$$K := 0.65$$

$$C_c := \sqrt{\frac{2 \cdot \pi^2 \cdot E}{F_y}} = 87.364$$

$$F_a := \begin{cases} \frac{\left[1 - \frac{\left(\frac{K \cdot l}{r} \right)^2}{2 \cdot C_c^2} \right] \cdot F_y}{\frac{5}{3} + \frac{3 \cdot \left(\frac{K \cdot l}{r} \right)}{8 \cdot C_c} - \frac{\left(\frac{K \cdot l}{r} \right)^3}{8 \cdot C_c^3}} & \text{if } \frac{K \cdot l}{r} \leq C_c \\ \frac{12 \cdot \pi^2 \cdot E}{23 \cdot \left(\frac{K \cdot l}{r} \right)^2} & \text{if } \frac{K \cdot l}{r} > C_c \end{cases} = 45 \cdot \text{ksi}$$

Allowable Compressive Stress =

$$F_a := 1.333 \cdot F_a = 60 \cdot \text{ksi} \quad (1.333 \text{ increase allowed per TIA/EIA})$$

Combined Stress % of Capacity =

$$\left(\frac{f_a}{F_a} + \frac{f_{bx}}{F_{bx}} \right) = 69.7 \%$$

Condition 2 =

$$\text{Condition2} := \text{if } \left(\frac{f_a}{F_a} + \frac{f_{bx}}{F_{bx}} \leq 1.00, \text{"OK"}, \text{"Overstressed"} \right)$$

Condition2 = "OK"

Base Plate Analysis:

Force from Bolts =
$$C_i := \frac{OM \cdot d_i}{l_p} + \frac{Axial}{N}$$

$C_1 = 36.8\text{-kips}$

$C_7 = 131.3\text{-kips}$

$C_2 = 69.0\text{-kips}$

$C_8 = 117.9\text{-kips}$

$C_3 = 96.7\text{-kips}$

$C_9 = 96.7\text{-kips}$

$C_4 = 117.9\text{-kips}$

$C_{10} = 69.0\text{-kips}$

$C_5 = 131.3\text{-kips}$

$C_{11} = 36.8\text{-kips}$

$C_6 = 135.9\text{-kips}$

etc.

Maximum Bending Stress in Plate =
$$f_{bp} := \sum_i \frac{6 \cdot C_i \cdot MA_i}{(B_{eff} t_{bp})^2} = 25.8\text{-ksi}$$

Allowable Bending Stress in Plate =
$$F_{bp} := 1.33 \cdot 0.75 \cdot F_y = 59.9\text{-ksi}$$

Plate Bending Stress % of Capacity =
$$\frac{f_{bp}}{F_{bp}} = 43.1\%$$

Condition3 =
$$\text{Condition3} := \text{if} \left(\frac{f_{bp}}{F_{bp}} < 1.00, \text{"Ok"}, \text{"Overstressed"} \right)$$

Condition3 = "Ok"

Standard Monopole Foundation:

Input Data:

Tower Data

Overturning Moment =	OM := 4862-ft-kips	(User Input from RISATower)
Shear Force =	Shear := 45-kip	(User Input from RISATower)
Axial Force =	Axial := 53-kip	(User Input from RISATower)
Tower Height =	H _t := 160-ft	(User Input)

Footing Data:

Overall Depth of Footing =	D _f := 14-ft	(User Input)
Length of Pier =	L _p := 10-ft	(User Input)
Extension of Pier Above Grade =	L _{pag} := 0.5-ft	(User Input)
Diameter of Pier =	d _p := 8-ft	(User Input)
Thickness of Footing =	T _f := 4-ft	(User Input)
Width of Footing =	W _f := 22-ft	(User Input)

Anchor Bolt Data:

Length of Anchor Bolts =	L _{st} := 132-in	(User Input)
Projection of Anchor Bolts Above Pier =	A _{BP} := 10-in	(User Input)
Anchor Bolt Diameter =	d _{anchor} := 2.25-in	(User Input)
Base Plate Bolt Circle =	MP := 72.76-in	(User Input)

Material Properties:

Concrete Compressive Strength =	f _c := 4000-psi	(User Input)
Steel Reinforcement Yield Strength =	f _y := 60000-psi	(User Input)
Anchor Bolt Yield Strength =	f _{ya} := 75000-psi	(User Input)
Internal Friction Angle of Soil =	Φ _s := 36-deg	(User Input)
Allowable Soil Bearing Capacity =	q _s := 10000-psf	(User Input)
Unit Weight of Soil =	γ _{soil} := 125-pcf	(User Input)
Unit Weight of Concrete =	γ _{conc} := 150-pcf	(User Input)
Foundation Bouyancy =	Bouyancy := 0	(User Input) (Yes=1 / No=0)
Depth to Neglect =	n := 0-ft	(User Input)
Cohesion of Clay Type Soil =	c := 0-ksf	(User Input) (Use 0 for Sandy Soil)
Seismic Zone Factor =	Z := 2	(User Input) (UBC-1997 Fig 23-2)
Coefficient of Friction Between Concrete =	μ := 0.45	(User Input)

Pier Reinforcement:

Bar Size =	$BS_{\text{pier}} := 11$	(User Input)	
Bar Diameter =	$d_{\text{bpier}} := 1.41 \cdot \text{in}$	(User Input)	
Number of Bars =	$NB_{\text{pier}} := 31$	(User Input)	
Clear Cover of Reinforcement =	$Cvr_{\text{pier}} := 3 \cdot \text{in}$	(User Input)	
Reinforcement Location Factor =	$\alpha_{\text{pier}} := 1.0$	(User Input)	(ACI-2008 12.2.4)
Coating Factor =	$\beta_{\text{pier}} := 1.0$	(User Input)	(ACI-2008 12.2.4)
Concrete Strength Factor =	$\lambda_{\text{pier}} := 1.0$	(User Input)	(ACI-2008 12.2.4)
Reinforcement Size Factor =	$\gamma_{\text{pier}} := 1.0$	(User Input)	(ACI-2008 12.2.4)
Diameter of Tie =	$d_{\text{Tie}} := 3 \cdot \text{in}$	(User Input)	

Pad Reinforcement:

Bar Size =	$BS_{\text{top}} := 9$	(User Input)	(Top of Pad)
Bar Diameter =	$d_{\text{btop}} := 1.128 \cdot \text{in}$	(User Input)	(Top of Pad)
Number of Bars =	$NB_{\text{top}} := 35$	(User Input)	(Top of Pad)
Bar Size =	$BS_{\text{bot}} := 10$	(User Input)	(Bottom of Pad)
Bar Diameter =	$d_{\text{bbot}} := 1.27 \cdot \text{in}$	(User Input)	(Bottom of Pad)
Number of Bars =	$NB_{\text{bot}} := 35$	(User Input)	(Bottom of Pad)
Clear Cover of Reinforcement =	$Cvr_{\text{pad}} := 3.0 \cdot \text{in}$	(User Input)	
Reinforcement Location Factor =	$\alpha_{\text{pad}} := 1.0$	(User Input)	(ACI-2008 12.2.4)
Coating Factor =	$\beta_{\text{pad}} := 1.0$	(User Input)	(ACI-2008 12.2.4)
Concrete Strength Factor =	$\lambda_{\text{pad}} := 1.0$	(User Input)	(ACI-2008 12.2.4)
Reinforcement Size Factor =	$\gamma_{\text{pad}} := 1.0$	(User Input)	(ACI-2008 12.2.4)

Calculated Factors:

Pier Reinforcement Bar Area =	$A_{\text{bpier}} := \frac{\pi \cdot d_{\text{bpier}}^2}{4} = 1.561 \cdot \text{in}^2$	
Pad Top Reinforcement Bar Area =	$A_{\text{btop}} := \frac{\pi \cdot d_{\text{btop}}^2}{4} = 0.999 \cdot \text{in}^2$	
Pad Bottom Reinforcement Bar Area =	$A_{\text{bbot}} := \frac{\pi \cdot d_{\text{bbot}}^2}{4} = 1.267 \cdot \text{in}^2$	
Coefficient of Lateral Soil Pressure =	$K_p := \frac{1 + \sin(\Phi_s)}{1 - \sin(\Phi_s)} = 3.852$	
Load Factor =	$LF := \begin{cases} 1.333 & \text{if } H_t \leq 700 \cdot \text{ft} \\ 1.7 & \text{if } H_t \geq 1200 \cdot \text{ft} \\ 1.333 + \left(\frac{H_t - 700 \cdot \text{ft}}{1200 \cdot \text{ft} - 700 \cdot \text{ft}} \right) \cdot 0.4 & \text{otherwise} \end{cases}$	= 1.333

Stability of Footing:

Adjusted Concrete Unit Weight =

$$\gamma_c := \text{if}(\text{Bouyancy} = 1, \gamma_{\text{conc}} - 62.4 \text{ pcf}, \gamma_{\text{conc}}) = 150 \text{ pcf}$$

Adjusted Soil Unit Weight =

$$\gamma_s := \text{if}(\text{Bouyancy} = 1, \gamma_{\text{soil}} - 62.4 \text{ pcf}, \gamma_{\text{soil}}) = 125 \text{ pcf}$$

Passive Pressure =

$$P_{pn} := K_p \cdot \gamma_s \cdot n + c \cdot 2 \cdot \sqrt{K_p} = 0 \text{ ksf}$$

$$P_{pt} := K_p \cdot \gamma_s \cdot (D_f - T_f) + c \cdot 2 \cdot \sqrt{K_p} = 4.815 \text{ ksf}$$

$$P_{top} := \text{if}[n < (D_f - T_f), P_{pt}, P_{pn}] = 4.815 \text{ ksf}$$

$$P_{bot} := K_p \cdot \gamma_s \cdot D_f + c \cdot 2 \cdot \sqrt{K_p} = 6.741 \text{ ksf}$$

$$P_{ave} := \frac{P_{top} + P_{bot}}{2} = 5.778 \text{ ksf}$$

$$T_p := \text{if}[n < (D_f - T_f), T_f, (D_f - n)] = 4$$

$$A_p := W_f \cdot T_p = 88$$

Ultimate Shear =

$$S_u := P_{ave} \cdot A_p = 508.443 \text{ kip}$$

Weight of Concrete Pad =

$$WT_c := \left[\left(W_f^2 \cdot T_f \right) + \frac{d_p^2 \cdot \pi}{4} L_p \right] \cdot \gamma_c = 365.798 \text{ kip}$$

Weight of Soil Above Footing =

$$WT_{s1} := \left[\left(W_f^2 - \frac{d_p^2 \cdot \pi}{4} \right) \cdot (L_p - L_{pag} - n) \right] \cdot \gamma_s = 515.06 \text{ kip}$$

Weight of Soil Wedge at Back Face =

$$WT_{s2} := \left(\frac{D_f^2 \cdot \tan(\Phi_s)}{2} \cdot W_f \right) \cdot \gamma_s = 195.803 \text{ kip}$$

Weight of Soil Wedge at back face Corners =

$$WT_{s3} := 2 \cdot \left[\left(D_f \right)^3 \cdot \frac{\tan(\Phi_s)}{3} \right] \cdot \gamma_s = 166.136 \text{ kips}$$

Total Weight =

$$WT_{tot} := WT_c + WT_{s1} + \text{Axial} = 933.858 \text{ kip}$$

Resisting Moment =

$$M_r := (WT_{tot}) \cdot \frac{W_f}{2} + S_u \cdot \frac{T_f}{3} + \left[(WT_{s2} + WT_{s3}) \cdot \left(W_f + \frac{D_f \cdot \tan(\Phi_s)}{3} \right) \right] = 20140 \text{ kip}\cdot\text{ft}$$

Overturning Moment =

$$M_{ot} := OM + \text{Shear} \cdot (L_p + T_f) = 5492 \text{ kip}\cdot\text{ft}$$

Factor of Safety Actual =

$$FS := \frac{M_r}{M_{ot}} = 3.67$$

Factor of Safety Required =

$$FS_{req} := 2$$

$$\text{OverTurning_Moment_Check} := \text{if}(FS \geq FS_{req}, \text{"Okay"}, \text{"No Good"})$$

$$\text{OverTurning_Moment_Check} = \text{"Okay"}$$

Shear Capacity in Pier:

Shear Resistance of Pier =

$$S_p := \frac{P_{ave} A_p + \mu \cdot WT_{tot}}{FS_{req}} = 464.339\text{-kips}$$

$$\text{Shear_Check} := \text{if}(S_p > \text{Shear}, \text{"Okay"}, \text{"No Good"})$$

$$\text{Shear_Check} = \text{"Okay"}$$

Bearing Pressure Caused by Footing:

Area of the Mat =

$$A_{mat} := W_f^2 = 484$$

Section Modulus of Mat =

$$S := \frac{W_f^3}{6} = 1774.67\text{-ft}^3$$

Maximum Pressure in Mat =

$$P_{max} := \frac{WT_{tot}}{A_{mat}} + \frac{M_{ot}}{S} = 5.024\text{-ksf}$$

$$\text{Max_Pressure_Check} := \text{if}(P_{max} < q_s, \text{"Okay"}, \text{"No Good"})$$

$$\text{Max_Pressure_Check} = \text{"Okay"}$$

Minimum Pressure in Mat =

$$P_{min} := \frac{WT_{tot}}{A_{mat}} - \frac{M_{ot}}{S} = -1.165\text{-ksf}$$

$$\text{Min_Pressure_Check} := \text{if}[(P_{min} \geq 0) \cdot (P_{min} < q_s), \text{"Okay"}, \text{"No Good"}]$$

$$\text{Min_Pressure_Check} = \text{"No Good"}$$

Distance to Resultant of Pressure Distribution =

$$X_p := \frac{\frac{P_{max}}{P_{max} - P_{min}} \cdot \frac{1}{3}}{\frac{W_f}{W_f}} = 5.953$$

Distance to Kern =

$$X_k := \frac{W_f}{6} = 3.667$$

Since Resultant Force is Not in Kern, Area to which Pressure is Applied Must be Reduced.

Eccentricity =

$$e := \frac{M_{ot}}{WT_{tot}} = 5.881$$

Adjusted Soil Pressure =

$$P_a := \frac{2 \cdot WT_{tot}}{3 \cdot W_f \left(\frac{W_f}{2} - e \right)} = 5.528\text{-ksf}$$

$$q_{adj} := \text{if}(P_{min} < 0, P_a, P_{max}) = 5.528\text{-ksf}$$

$$\text{Pressure_Check} := \text{if}(q_{adj} < q_s, \text{"Okay"}, \text{"No Good"})$$

$$\text{Pressure_Check} = \text{"Okay"}$$

Concrete Bearing Capacity:

Strength Reduction Factor =

$$\Phi_C := 0.65 \quad (\text{ACI-2008 9.3.2.2})$$

Bearing Strength Between Pier and Pad =

$$P_b := \Phi_C \cdot 0.85 \cdot f_c \cdot \frac{\pi \cdot d_p^2}{4} = 1.6 \times 10^4 \cdot \text{kips} \quad (\text{ACI-2008 10.14})$$

$$\text{Bearing_Check} := \text{if}(P_b > \text{LF} \cdot \text{Axial}, \text{"Okay"}, \text{"No Good"})$$

$$\text{Bearing_Check} = \text{"Okay"}$$

Shear Strength of Concrete:

Beam Shear:

(Critical section located at a distance d from the face of Pier) (ACI 11.3.1.1)

$$\phi_C := 0.85 \quad (\text{ACI 9.3.2.5})$$

$$d := T_f - \text{Cvr}_{\text{pad}} - d_{\text{bbot}}$$

$$d_1 := \frac{W_f}{2} - \frac{d_p}{2}$$

$$d_2 := d_1 - d$$

$$L := \left(\frac{W_f}{2} - e \right) \cdot 3$$

$$\text{Slope} := \text{if} \left(L > W_f, \frac{P_{\text{max}} - P_{\text{min}}}{W_f}, \frac{q_{\text{adj}}}{L} \right)$$

$$V_{\text{req}} := \text{LF} \cdot \left[(q_{\text{adj}} - \text{Slope} \cdot d_1) + \left(\frac{\text{Slope} \cdot d_1}{2} \right) \right] \cdot W_f \cdot d_1$$

$$V_{\text{Avail}} := \phi_C \cdot 2 \cdot \sqrt{f_c \cdot \text{psi}} \cdot W_f \cdot d \quad (\text{ACI-2008 11.2.1.1})$$

$$\text{Beam_Shear_Check} := \text{if}(V_{\text{req}} < V_{\text{Avail}}, \text{"Okay"}, \text{"No Good"})$$

$$\text{Beam_Shear_Check} = \text{"Okay"}$$

Punching Shear:

(Critical Section Located at a distance of d/2 from the face of pier) (ACI 11.11.1.2)

Critical Perimeter of Punching Shear =

$$b_o := (d_p + d) \cdot \pi = 36.6$$

Area Included Inside Perimeter =

$$A_{bo} := \frac{\pi \cdot (d_p + d)^2}{4} = 106.5$$

Area Outside of Perimeter =

$$A_{\text{out}} := A_{\text{mat}} - A_{bo} = 377.5$$

Guess Value =

$$v_u := 1 \text{ ksf}$$

(From "Foundation Analysis and design", By Joseph Bowles, Eq. 8-9)

Given

$$d^2 + d_p \cdot d = \frac{W_{T_{tot}}}{\pi \cdot v_u}$$

$$v_u := \text{Find}(v_u) = 7 \cdot \text{ksf}$$

$$V_u := v_u \cdot d \cdot W_f = 561.6 \cdot \text{kips}$$

Required Shear Strength =

$$V_{req} := LF \cdot V_u = 748.6 \cdot \text{kips}$$

Available Shear Strength =

$$V_{Avail} := \phi_c \cdot 4 \cdot \sqrt{f_c \cdot \text{psi} \cdot b_o \cdot d} = 4127.9 \cdot \text{kip} \quad (\text{ACI-2008 11.11.2.1})$$

$$\text{Punching_Shear_Check} := \text{if}(V_{req} < V_{Avail}, \text{"Okay"}, \text{"No Good"})$$

$$\text{Punching_Shear_Check} = \text{"Okay"}$$

Steel Reinforcement in Pad:

Required Reinforcement for Bending:

Strength Reduction Factor =

$$\phi_m := .90 \quad (\text{ACI-2008 9.3.2.1})$$

$$q_b := q_{adj} - d_1 \cdot \text{Slope} = 3.008 \cdot \text{ksf}$$

Maximum Bending at Face of Pier =

$$M_n := \frac{1}{LF \cdot \phi_m} \cdot \left[(q_{adj} - q_b) \cdot \frac{d_1^2}{3} + q_b \cdot \frac{d_1^2}{2} \right] \cdot W_f = 2106.3 \cdot \text{kip} \cdot \text{ft}$$

$$\beta := \begin{cases} 0.85 & \text{if } 2500 \cdot \text{psi} \leq f_c \leq 4000 \cdot \text{psi} \\ 0.65 & \text{if } f_c > 8000 \cdot \text{psi} \\ \left[0.85 - \left[\frac{\left(\frac{f_c}{\text{psi}} - 4000 \right)}{1000} \right] \cdot 0.5 \right] & \text{otherwise} \end{cases} = 0.85 \quad (\text{ACI-2008 10.2.7.3})$$

$$R_u := \frac{M_n}{\phi_m \cdot W_f \cdot d^2} = 55.6 \cdot \text{psi}$$

$$\rho := \frac{0.85 \cdot f_c}{f_y} \left(1 - \sqrt{1 - \frac{2 \cdot R_u}{0.85 \cdot f_c}} \right) = 0.0009$$

$$\rho_{min} := 1.333 \cdot \rho = 0.00125$$

Required Reinforcement for Temperature and Shrinkage:

$$\rho_{sh} := \begin{cases} .0018 & \text{if } f_y \geq 60000\text{-psi} \\ .0020 & \text{otherwise} \end{cases} \quad (\text{ACI-2008 7.12.2.1})$$

Check Bottom Bars:

$$A_s := \max(\rho, \rho_{min}, \rho_{sh}) \cdot W_f \cdot d = 20.8\text{-in}^2$$

$$A_{s\text{prov}} := A_{bbot} \cdot NB_{bot} = 44.3\text{-in}^2$$

$$\text{Pad_Reinforcement_Bot} := \text{if}(A_{s\text{prov}} > A_s, \text{"Okay"}, \text{"No Good"})$$

$$\text{Pad_Reinforcement_Bot} = \text{"Okay"}$$

Check top Bars:

$$A_s := \rho_{sh} \cdot (W_f \cdot d) = 20.8\text{-in}^2$$

$$A_{s\text{prov}} := A_{btop} \cdot NB_{top} = 35\text{-in}^2$$

$$\text{Pad_Reinforcement_Top} := \text{if}(A_{s\text{prov}} > A_s, \text{"Okay"}, \text{"No Good"})$$

$$\text{Pad_Reinforcement_Top} = \text{"Okay"}$$

Development Length Pad Reinforcement:

Bar Spacing =

$$B_{s\text{Pad}} := \frac{W_f - 2 \cdot C_{vr\text{pad}} - NB_{bot} \cdot d_{bbot}}{NB_{bot} - 1} = 6.28\text{-in}$$

Spacing or Cover Dimension =

$$c := \text{if}\left(C_{vr\text{pad}} < \frac{B_{s\text{Pad}}}{2}, C_{vr\text{pad}}, \frac{B_{s\text{Pad}}}{2}\right) = 3\text{-in}$$

Transverse Reinforcement Index =

$$k_{tr} := 0 \quad (\text{ACI-2008 12.2.3})$$

$$L_{dbt} := \frac{3 \cdot f_y \cdot \alpha_{pad} \cdot \beta_{pad} \cdot \gamma_{pad} \cdot \lambda_{pad}}{40 \cdot \sqrt{f_c \text{ psi}} \cdot \frac{c + k_{tr}}{d_{bbot}}} \cdot d_{bbot} = 38.3\text{-in}$$

Minimum Development Length =

$$L_{dbmin} := 12\text{-in} \quad (\text{ACI-2008 12.2.1})$$

$$L_{dbt\text{Check}} := \text{if}(L_{dbt} \geq L_{dbmin}, \text{"Use } L_{dbt}\text{"}, \text{"Use } L_{dbmin}\text{"})$$

Available Length in Pad =

$$L_{\text{Pad}} := \frac{W_f}{2} - \frac{d_p}{2} - C_{vr\text{pad}} = 81\text{-in}$$

$$L_{\text{pad_Check}} := \text{if}(L_{\text{Pad}} > L_{dbt}, \text{"Okay"}, \text{"No Good"})$$

$$L_{\text{pad_Check}} = \text{"Okay"}$$

Steel Reinforcement in Pier:

Area of Pier =

$$A_p := \frac{\pi \cdot d_p^2}{4} = 7238.23 \cdot \text{in}^2$$

$$A_{smin} := 0.01 \cdot 0.05 \cdot A_p = 3.62 \cdot \text{in}^2 \quad (\text{ACI-2008 10.8.4 \& 10.9.1})$$

$$A_{sprov} := NB_{pier} \cdot A_{bpier} = 48.4 \cdot \text{in}^2$$

$$\text{Steel_Area_Check} := \text{if}(A_{sprov} > A_{smin}, \text{"Okay"}, \text{"No Good"})$$

$$\text{Steel_Area_Check} = \text{"Okay"}$$

Bar Spacing In Pier =

$$B_{sPier} := \frac{d_p \cdot \pi}{NB_{pier}} - d_{bpier} = 8.319 \cdot \text{in}$$

Diameter of Reinforcement Cage =

$$\text{Diam}_{cage} := d_p - 2 \cdot C_{vr_{pier}} = 90 \cdot \text{in}$$

Maximum Moment in Pier =

$$M_p := \left[OM + \text{Shear} \cdot \left(L_p + \frac{A_{BP}}{2} \right) \right] \cdot LF = 85270.7 \cdot \text{in-kips}$$

Pier Check evaluated from outside program and results are listed below;

$$(D \ N \ n \ P_u \ M_{xu}) := \left(d_p \cdot 12 \ NB_{pier} \ B_{s_{pier}} \ \frac{\text{Axial} \cdot 1.333}{\text{kips}} \ \frac{M_p}{\text{in-kips}} \right)$$

$$(D \ N \ n \ P_u \ M_{xu}) = (96 \ 31 \ 11 \ 70.6 \ 85270.7)$$

$$(\phi P_n \ \phi M_{xn} \ f_{sp} \ \rho) := (0 \ 0 \ 0 \ 0)$$

$$(\phi P_n \ \phi M_{xn} \ f_{sp} \ \rho) := \phi P'_n (D, N, n, P_u, M_{xu})^T$$

$$(\phi P_n \ \phi M_{xn} \ f_{sp} \ \rho) = (87.9 \ 1.1 \times 10^5 \ -60 \ 0)$$

$$\text{Axial_Load_Check} := \text{if}(\phi P_n \geq P_u, \text{"Okay"}, \text{"No Good"})$$

$$\text{Axial_Load_Check} = \text{"Okay"}$$

$$\text{Bending_Check} := \text{if}(\phi M_{xn} \geq M_{xu}, \text{"Okay"}, \text{"No Good"})$$

$$\text{Bending_Check} = \text{"Okay"}$$

Development Length Pier Reinforcement:Available Length in Foundation:

$$L_{\text{pier}} := L_p - C_{\text{vr}}_{\text{pier}} = 117 \cdot \text{in}$$

$$L_{\text{pad}} := T_f - C_{\text{vr}}_{\text{pad}} = 45 \cdot \text{in}$$

Tension:

(ACI-2008 12.2.3)

Spacing or Cover Dimension =

$$c := \text{if} \left(C_{\text{vr}}_{\text{pier}} < \frac{B_{\text{sPier}}}{2}, C_{\text{vr}}_{\text{pier}}, \frac{B_{\text{sPier}}}{2} \right) = 3 \cdot \text{in}$$

Transverse Reinforcement =

$$k_{\text{tr}} := 0 \quad (\text{ACI-2008 12.2.3})$$

$$L_{\text{dbt}} := \frac{3 \cdot f_y \alpha_{\text{pier}} \beta_{\text{pier}} \gamma_{\text{pier}} \lambda_{\text{pier}}}{40 \cdot \sqrt{f_c \cdot \text{psi}} \cdot \left(\frac{c + k_{\text{tr}}}{d_{\text{bpier}}} \right)} \cdot d_{\text{bpier}} = 47.15 \cdot \text{in}$$

Minimum Development Length =

Pier reinforcement bars are standard 90 degree hooks and therefore development in the pad is computed as follows:

$$L_{\text{dh}} := \frac{1200 \cdot d_{\text{bpier}}}{\sqrt{\frac{f_c}{\text{psi}}}} \cdot .7 = 18.727 \cdot \text{in} \quad (\text{ACI 12.2.1})$$

$$L_{\text{db}} := \max(L_{\text{dbt}}, L_{\text{dbmin}})$$

$$L_{\text{tension_Check}} := \text{if}(L_{\text{pier}} + L_{\text{pad}} > L_{\text{dbt}}, \text{"Okay"}, \text{"No Good"})$$

$$L_{\text{tension_Check}} = \text{"Okay"}$$

Compression:

(ACI-2008 12.3.2)

$$L_{\text{dbc1}} := \frac{.02 \cdot d_{\text{bpier}} \cdot f_y}{\sqrt{f_c \cdot \text{psi}}} = 26.753 \cdot \text{in}$$

$$L_{\text{dbmin}} := 0.0003 \cdot \frac{\text{in}^2}{\text{lb}} \cdot (d_{\text{bpier}} \cdot f_y) = 25.38 \cdot \text{in}$$

$$L_{\text{dbc}} := \text{if}(L_{\text{dbc1}} \geq L_{\text{dbmin}}, L_{\text{dbc1}}, L_{\text{dbmin}}) = 26.753 \cdot \text{in}$$

$$L_{\text{compression_Check}} := \text{if}(L_{\text{pier}} + L_{\text{pad}} > L_{\text{dbc}}, \text{"Okay"}, \text{"No Good"})$$

$$L_{\text{compression_Check}} = \text{"Okay"}$$

Tie Size and Spacing in Column:

Minimum Tie Size =

$$Tie_{min} := \text{if}(BS_{pier} \leq 10, 3, 4) = 4$$

Used #3 Ties

Seismic Factor =

$$z := \text{if}(Z \leq 2, 1, 0.5) = 1 \quad (\text{ACI-2008 21.10.5})$$

$$s_{lim1} := 16 \cdot d_{bpier} \cdot z = 22.56 \cdot \text{in}$$

$$s_{lim2} := \frac{48 \cdot d_{Tie}}{8} \cdot z = 18 \cdot \text{in}$$

$$s_{lim3} := D_f \cdot z = 168 \cdot \text{in}$$

$$s_{lim4} := 18 \cdot \text{in}$$

Maximum Spacing =

$$s_{tie} := \min \left(\begin{matrix} s_{lim1} \\ s_{lim2} \\ s_{lim3} \\ s_{lim4} \end{matrix} \right) = 18 \cdot \text{in}$$

Number of Ties Required =

$$n_{tie} := \frac{L_{pier} - 3 \cdot \text{in}}{s_{tie}} + 1 = 7.333$$

Check Anchor Steel Embedment:

Depth Available =

$$D_{ab} := L_{st} - A_{BP} = 10.167 \cdot \text{ft}$$

Length of Anchor Bolt =

$$L_{anchor} := \frac{(0.11 \cdot f_{ya}) \cdot \text{in}}{\sqrt{f_c \cdot \text{psi}}} = 10.87 \cdot \text{ft}$$

$$\text{Depth_Check} := \text{if}(D_{ab} \geq L_{anchor}, \text{"Okay"}, \text{"No Good"})$$

Depth_Check = "No Good"

Note: Anchor plate is provided

RFDS NAME:		Section 1 - RFDS GENERAL INFORMATION					
ISSUE:	CT2174	DATE:	1/1/2011 0:23	RF DESIGN ENG:	Radu Alecsandru	RF PERF ENG:	TBD
REVISION:	Preliminary	Approved? (Y/N)	Y	RF DESIGN PHONE:	(800) 965-6685	RF PERF PHONE:	TBD
	V04	RF MANAGER:	Walter C. Saddig Jr.	RF DESIGN EMAIL:	ra9161@att.com	RF PERF EMAIL:	TBD
	LTE Addition					TRIDENT:	TBD
						GSM FREQUENCY:	
						UMTS FREQUENCY:	
						LTE FREQUENCY:	
						I-PLAN JOB # 1:	NER-RCTB-10-05775
						I-PLAN JOB # 2:	
						I-PLAN JOB # 3:	
						I-PLAN JOB # 4:	
INITIATIVE / PROJECT:							
Section 2 - LOCATION INFORMATION							
USID:	4557	FA LOCATION CODE:	10035120	LOCATION NAME:	C. ORANGE	ORACLE PRIT # 1:	2051003295
REGION:	North East	MARKET CLUSTER:	New England	MARKET:	CT	ORACLE PRIT # 2:	
ADDRESS:	525 ORANGE CENTER ROAD	CITY:	ORANGE	STATE:	CT	ORACLE PRIT # 3:	
ZIP CODE:	06477	COUNTY:	NEW HAVEN	MSA/MSA:	TBD	ORACLE PRIT # 4:	
LATITUDE (D-M-S):	41° 16' 25.3"	LONGITUDE (D-M-S):	-73° 1' 7.8"	LAT (DEC. DEG.):	41.273694	SEARCH RING NAME:	N/A
						SEARCH RING ID:	N/A
						ITA:	TBD
						LONG (DEC. DEG.):	-73.018833
						BORDER CELL WITH:	TBD
						AM STUDY REQ'D (Y/N):	TBD
						FREQ COORD:	TBD
DIRECTIONS, ACCESS AND EQUIPMENT LOCATION:	TBD						
Section 3 - LICENSE COVERAGE/FILING INFORMATION							
CGSA - NO FILING TRIGGERED:	TBD	CGSA LOSS:	TBD	PCS REDUCED - UPS ZIP:	TBD		
CGSA - MINOR FILING NEEDED:	TBD	CGSA EXT AGMT NEEDED:	TBD	PCS POPS REDUCED:	TBD		
CGSA - MAJOR FILING NEEDED:	TBD	CGSA SCORECARD UPDATED:	TBD				
Section 4 - TOWER/REGULATORY INFORMATION							
STRUCTURE AT&T OWNED:	TBD	GROUND ELEVATION (ft):		STRUCTURE TYPE:	Monopole	MKT LOCATION 850 MHZ CALL SIGN(S):	TBD
ADDITIONAL REGULATORY:	TBD	HEIGHT OVERALL (ft):		FCC ASR NUMBER:	TBD	MKT LOCATION 1900 MHZ CALL SIGN(S):	TBD
SUB-LEASE RIGHTS?:	TBD	STRUCTURE HEIGHT (ft):				MKT LOCATION 700 MHZ CALL SIGN(S):	TBD
LIGHTING TYPE:	TBD					MKT LOCATION AWS MHZ CALL SIGN(S):	TBD
Section 5 - E-911 INFORMATION							
	PSAP NAME:	PSAP ID:	EP911 PHASE:	MPC SVC PROVIDER:	LMU REQUIRED:	ESAM:	DATE LIVE PH1:
ALPHA	TBD	TBD	TBD	TBD	TBD	TBD	TBD
BETA	TBD	TBD	TBD	TBD	TBD	TBD	TBD
GAMMA	TBD	TBD	TBD	TBD	TBD	TBD	TBD
DELTA	TBD	TBD	TBD	TBD	TBD	TBD	TBD
EPSILON							
PSI							
Section 6 - RBS GENERAL INFORMATION							
4-DIGIT SITE ID:	2174	COW OR TOY?	NO	CELLULAR NETWORK:	GOLD	DISASTER PRIORITY:	TBD
CELL SITE TYPE:	SECTORIZED	SITE TYPE:	MACRO	OPS DISTRICT:	CT-South	OPS ZONE:	NE CT_S_NHVN SW_CS
BTS LOCATION ID:	TBD	ORIGINATING CO:	ATT	RF DISTRICT:	Bridgeport	RF ZONE:	BBP03
Section 7 - RBS SPECIFIC INFORMATION							
	GSM RBSs	UMTS 1ST CARRIER RBSs	UMTS 2ND CARRIER RBSs	UMTS 3RD CARRIER RBSs	UMTS 4TH CARRIER RBSs	LTE RBSs	
MSC	MBP01	TBD	TBD	TBD	TBD	TBD	
BSC/RNC	BRPTCTBSC03	BRPTCTGRNC002	TBD	TBD	TBD	TBD	
LAC	05012	TBD	TBD	N/A	N/A	N/A	N/A
RAI	TBD	TBD	TBD	N/A	N/A	N/A	N/A
EQUIPMENT VENDOR	NOKIA	ERICSSON	ERICSSON	N/A	N/A	N/A	N/A
EQUIPMENT TYPE	TBD	TBD	TBD	N/A	N/A	N/A	RBS6601
LOCATION	TBD	TBD	TBD	N/A	N/A	N/A	N/A
CABINET LOCATION	TBD	TBD	TBD	N/A	N/A	N/A	N/A
Section 8 - RBS INDIVIDUAL INFORMATION							
	GSM 850 RBS	GSM 1900 RBS	UMTS 850 RBS	UMTS 1900 RBS	UMTS 2ND 850 RBS	UMTS 2ND 1900 RBS	UMTS 3RD 850 RBS
CELL ID/BCT	TBD	TBD	TBD	TBD	TBD	TBD	TBD
CTS COMMON ID	TBD	TBD	TBD	TBD	TBD	TBD	N/A
							N/A
							N/A
							N/A
							N/A

Section 15A - CURRENT SECTOR/CELL INFORMATION - ALPHA (OR OMNI)

ANTENNA CONFIG (FROM BACK):	ANTENNA 1 GSM, UMTS (850 / 1900) or LTE (700 / AWS)	ANTENNA 2 GSM, UMTS (850 / 1900) or LTE (700 / AWS)	ANTENNA 3 GSM, UMTS (850 / 1900) or LTE (700 / AWS)	ANTENNA 4 GSM, UMTS (850 / 1900) or LTE (700 / AWS)	ANTENNA 5 GSM, UMTS (850 / 1900) or LTE (700 / AWS)
TX/RX?					
TECHNOLOGY					
RRH LOCATION (Top/Bottom/None)					
FEEDERS TYPE	1 1/4" - RFS			1 1/4" - RFS	
Feeder Length (feet)	175'			175'	
ANTENNA ATOLL					
ANTENNA MAKE - MODEL	7770			7770	
ANTENNA VENDOR	Powerwave			Powerwave	
ANTENNA SIZE (H x W x D)					
ANTENNA WEIGHT					
ANTENNA GAIN					
AZIMUTH	138°			138°	
RADIATION CENTER (feet)	148'			148'	
ANTENNA TIP HEIGHT					
ELECTRICAL TILT (700/850/1900/AWS)	6°	2°		TBD	2°
MECHANICAL DOWNTILT					
FEEDER AMOUNT	2			2	
Antenna RET Motor (QTY/MODEL)					
Antenna RET Splitter (QTY/MODEL)					
Antenna RET Earth (Grounding) Clamp (QTY/MODEL)					
Antenna RET Surge Arrestor (QTY/MODEL)					
Antenna RET CONTROL UNIT (QTY/MODEL) usually per site					
DC BLOCK (QTY/MODEL)					
TMA/NA (TYPE/MODEL)	2 / Powerwave / LGP 21401 (Dual Band -			0 / N/A	
CURRENT INJECTORS FOR TMA (QTY/MODEL)					
POU FOR TMA (QTY/MODEL) usually per site	LGP 12104 (1900 AND 850 Bypass TMA)				
SURGE ARRESTOR (QTY/MODEL)					
DUPLEXER (QTY/MODEL)	+ 2 / Powerwave / LGP 21901			+ 2 / Powerwave / LGP 21901	
HYBRID COMBINER (QTY/MODEL)					
DUPLEXER (QTY/MODEL)					
FILTER (QTY/MODEL)					
RXA/T KIT MODULE?					
TRIPLEXER or NARROW BAND LLC (QTY/MODEL)					
SCPA/MCPA MODULE?					
Additional Component1					
Additional Component2					
Additional Component3					
MAGNETIC DECLINATION					
HATCHPLATE POWER (Watts)					
ERP (Watts)					
Local Market Note1					
Local Market Note2					
Local Market Note3					

Section 15B - CURRENT SECTOR/CELL INFORMATION - BETA

ANTENNA CONFIG (FROM BACK):	ANTENNA 1 GSM, UMTS (850 / 1900) or LTE (700 / AWS)	ANTENNA 2 GSM, UMTS (850 / 1900) or LTE (700 / AWS)	ANTENNA 3 GSM, UMTS (850 / 1900) or LTE (700 / AWS)	ANTENNA 4 GSM, UMTS (850 / 1900) or LTE (700 / AWS)	ANTENNA 5 GSM, UMTS (850 / 1900) or LTE (700 / AWS)
TX/RX?					
TECHNOLOGY					
RRH LOCATION (Top/Bottom/None)					
FEEDERS TYPE	1 1/4" - RFS			1 1/4" - RFS	
Feeder Length (feet)	175'			175'	
ANTENNA ATOLL					
ANTENNA MAKE - MODEL	7770			7770	
ANTENNA VENDOR	Powerwave			Powerwave	
ANTENNA SIZE (H x W x D)					
ANTENNA WEIGHT					
ANTENNA GAIN					
AZIMUTH	261°			261°	
RADIATION CENTER (feet)	148'			148'	
ANTENNA TIP HEIGHT					
ELECTRICAL TILT (700/850/1900/AWS)	4°	0°		TBD	0°
MECHANICAL DOWNTILT					
FEEDER AMOUNT	2			2	
Antenna RET Motor (QTY/MODEL)					
Antenna RET Splitter (QTY/MODEL)					
Antenna RET Earth (Grounding) Clamp (QTY/MODEL)					
Antenna RET Surge Arrestor (QTY/MODEL)					
Antenna RET CONTROL UNIT (QTY/MODEL) usually per site					
DC BLOCK (QTY/MODEL)					
TMA/NA (TYPE/MODEL)	2 / Powerwave / LGP 21401 (Dual Band -			0 / N/A	
CURRENT INJECTORS FOR TMA (QTY/MODEL)					
POU FOR TMA (QTY/MODEL) usually per site	LGP 12104 (1900 AND 850 Bypass TMA)				
SURGE ARRESTOR (QTY/MODEL)					
DUPLEXER (QTY/MODEL)	+ 2 / Powerwave / LGP 21901			+ 2 / Powerwave / LGP 21901	
HYBRID COMBINER (QTY/MODEL)					
DUPLEXER (QTY/MODEL)					
FILTER (QTY/MODEL)					
RXA/T KIT MODULE?					
TRIPLEXER or NARROW BAND LLC (QTY/MODEL)					
SCPA/MCPA MODULE?					
Additional Component1					
Additional Component2					
Additional Component3					
MAGNETIC DECLINATION					
HATCHPLATE POWER (Watts)					
ERP (Watts)					
Local Market Note1					
Local Market Note2					
Local Market Note3					

Section 15C - CURRENT SECTOR/CELL INFORMATION - GAMMA

ANTENNA CONFIG (FROM BACK):	ANTENNA 1 GSM, UMTS (850 / 1900) or LTE (700 / AWS)	ANTENNA 2 GSM, UMTS (850 / 1900) or LTE (700 / AWS)	ANTENNA 3 GSM, UMTS (850 / 1900) or LTE (700 / AWS)	ANTENNA 4 GSM, UMTS (850 / 1900) or LTE (700 / AWS)	ANTENNA 5 GSM, UMTS (850 / 1900) or LTE (700 / AWS)
TX/RX?					
TECHNOLOGY					
RRH LOCATION (Top/Bottom/None)					
FEEDERS TYPE	1 1/4" - RFS			1 1/4" - RFS	
Feeder Length (feet)	175'			175'	
ANTENNA ATOLL					
ANTENNA MAKE - MODEL	7770			7770	
ANTENNA VENDOR	Powerwave			Powerwave	
ANTENNA SIZE (H x W x D)					
ANTENNA WEIGHT					
ANTENNA GAIN					
AZIMUTH	25°			25°	
RADIATION CENTER (feet)	148'			148'	
ANTENNA TIP HEIGHT					
ELECTRICAL TILT (700/850/1900/AWS)	4°	0°		TBD	0°
MECHANICAL DOWNTILT					
FEEDER AMOUNT	2			2	
Antenna RET Motor (QTY/MODEL)					
Antenna RET Splitter (QTY/MODEL)					
Antenna RET Earth (Grounding) Clamp (QTY/MODEL)					
Antenna RET Surge Arrestor (QTY/MODEL)					
Antenna RET CONTROL UNIT (QTY/MODEL) usually per site					
DC BLOCK (QTY/MODEL)					
TMA/NA (TYPE/MODEL)	2 / Powerwave / LGP 21401 (Dual Band -			0 / N/A	
CURRENT INJECTORS FOR TMA (QTY/MODEL)					
POU FOR TMA (QTY/MODEL) usually per site	LGP 12104 (1900 AND 850 Bypass TMA)				
SURGE ARRESTOR (QTY/MODEL)					
DUPLEXER (QTY/MODEL)	+ 2 / Powerwave / LGP 21901			+ 2 / Powerwave / LGP 21901	
HYBRID COMBINER (QTY/MODEL)					
DUPLEXER (QTY/MODEL)					
FILTER (QTY/MODEL)					
RXA/T KIT MODULE?					
TRIPLEXER or NARROW BAND LLC (QTY/MODEL)					
SCPA/MCPA MODULE?					
Additional Component1					
Additional Component2					
Additional Component3					
MAGNETIC DECLINATION					
HATCHPLATE POWER (Watts)					
ERP (Watts)					
Local Market Note1					
Local Market Note2					
Local Market Note3					

Section 15D - CURRENT SECTOR/CELL INFORMATION - DELTA					
ANTENNA CONFIG (FROM BACK):	ANTENNA 1 GSM, UMTS (850 / 1900) or LTE (700 / AWS)	ANTENNA 2 GSM, UMTS (850 / 1900) or LTE (700 / AWS)	ANTENNA 3 GSM, UMTS (850 / 1900) or LTE (700 / AWS)	ANTENNA 4 GSM, UMTS (850 / 1900) or LTE (700 / AWS)	ANTENNA 5 GSM, UMTS (850 / 1900) or LTE (700 / AWS)
TX/RX?					
TECHNOLOGY					
RRH LOCATION (Top/Bottom/None)					
FEEDERS TYPE					
Feeder Length (feet)					
ANTENNA ATOLL					
ANTENNA MAKE - MODEL					
ANTENNA VENDOR					
ANTENNA SIZE (H x W x D)					
ANTENNA WEIGHT					
ANTENNA GAIN					
AZIMUTH					
RADIATION CENTER (feet)					
ANTENNA TIP HEIGHT					
ELECTRICAL TILT (700/850/1900/AWS)					
MECHANICAL DOWNTILT					
FEEDER AMOUNT					
Antenna RET Motor (QTY/MODEL)					
Antenna RET Splitter (QTY/MODEL)					
Antenna RET Earth (Grounding) Clamp (QTY/MODEL)					
Antenna RET Surge Arrestor (QTY/MODEL)					
Antenna RET CONTROL UNIT (QTY/MODEL) usually per site					
DC BLOCK (QTY/MODEL)					
TMA/LNA (TYPE/MODEL)					
CURRENT INJECTORS FOR TMA (QTY/MODEL)					
POU FOR TMA (QTY/MODEL) usually per site					
SURGE ARRESTOR (QTY/MODEL)					
DIPLEXER (QTY/MODEL)					
HYBRID COMBINER (QTY/MODEL)					
DUPLEXER (QTY/MODEL)					
FILTER (QTY/MODEL)					
RX/IT KIT MODULE?					
TRIPLEXER or NARROW BAND LLC (QTY/MODEL)					
SCPA/MCPA MODULE?					
Additional Component1					
Additional Component2					
Additional Component3					
MAGNETIC DECLINATION					
HATCHPLATE POWER (Watts)					
ERP (Watts)					
Local Market Note1					
Local Market Note2					
Local Market Note3					

Section 15E - CURRENT SECTOR/CELL INFORMATION - EPSILON					
ANTENNA CONFIG (FROM BACK):	ANTENNA 1 GSM, UMTS (850 / 1900) or LTE (700 / AWS)	ANTENNA 2 GSM, UMTS (850 / 1900) or LTE (700 / AWS)	ANTENNA 3 GSM, UMTS (850 / 1900) or LTE (700 / AWS)	ANTENNA 4 GSM, UMTS (850 / 1900) or LTE (700 / AWS)	ANTENNA 5 GSM, UMTS (850 / 1900) or LTE (700 / AWS)
TX/RX?					
TECHNOLOGY					
RRH LOCATION (Top/Bottom/None)					
FEEDERS TYPE					
Feeder Length (feet)					
ANTENNA ATOLL					
ANTENNA MAKE - MODEL					
ANTENNA VENDOR					
ANTENNA SIZE (H x W x D)					
ANTENNA WEIGHT					
ANTENNA GAIN					
AZIMUTH					
RADIATION CENTER (feet)					
ANTENNA TIP HEIGHT					
ELECTRICAL TILT (700/850/1900/AWS)					
MECHANICAL DOWNTILT					
FEEDER AMOUNT					
Antenna RET Motor (QTY/MODEL)					
Antenna RET Splitter (QTY/MODEL)					
Antenna RET Earth (Grounding) Clamp (QTY/MODEL)					
Antenna RET Surge Arrestor (QTY/MODEL)					
Antenna RET CONTROL UNIT (QTY/MODEL) usually per site					
DC BLOCK (QTY/MODEL)					
TMA/LNA (TYPE/MODEL)					
CURRENT INJECTORS FOR TMA (QTY/MODEL)					
POU FOR TMA (QTY/MODEL) usually per site					
SURGE ARRESTOR (QTY/MODEL)					
DIPLEXER (QTY/MODEL)					
HYBRID COMBINER (QTY/MODEL)					
DUPLEXER (QTY/MODEL)					
FILTER (QTY/MODEL)					
RX/IT KIT MODULE?					
TRIPLEXER or NARROW BAND LLC (QTY/MODEL)					
SCPA/MCPA MODULE?					
Additional Component1					
Additional Component2					
Additional Component3					
MAGNETIC DECLINATION					
HATCHPLATE POWER (Watts)					
ERP (Watts)					
Local Market Note1					
Local Market Note2					
Local Market Note3					

Section 15F - CURRENT SECTOR/CELL INFORMATION - ZETA					
ANTENNA CONFIG (FROM BACK):	ANTENNA 1 GSM, UMTS (850 / 1900) or LTE (700 / AWS)	ANTENNA 2 GSM, UMTS (850 / 1900) or LTE (700 / AWS)	ANTENNA 3 GSM, UMTS (850 / 1900) or LTE (700 / AWS)	ANTENNA 4 GSM, UMTS (850 / 1900) or LTE (700 / AWS)	ANTENNA 5 GSM, UMTS (850 / 1900) or LTE (700 / AWS)
TX/RX?					
TECHNOLOGY					
RRH LOCATION (Top/Bottom/None)					
FEEDERS TYPE					
Feeder Length (feet)					
ANTENNA ATOLL					
ANTENNA MAKE - MODEL					
ANTENNA VENDOR					
ANTENNA SIZE (H x W x D)					
ANTENNA WEIGHT					
ANTENNA GAIN					
AZIMUTH					
RADIATION CENTER (feet)					
ANTENNA TIP HEIGHT					
ELECTRICAL TILT (700/850/1900/AWS)					
MECHANICAL DOWNTILT					
FEEDER AMOUNT					
Antenna RET Motor (QTY/MODEL)					
Antenna RET Splitter (QTY/MODEL)					
Antenna RET Earth (Grounding) Clamp (QTY/MODEL)					
Antenna RET Surge Arrestor (QTY/MODEL)					
Antenna RET CONTROL UNIT (QTY/MODEL) usually per site					
DC BLOCK (QTY/MODEL)					
TMA/LNA (TYPE/MODEL)					
CURRENT INJECTORS FOR TMA (QTY/MODEL)					
POU FOR TMA (QTY/MODEL) usually per site					
SURGE ARRESTOR (QTY/MODEL)					
DIPLEXER (QTY/MODEL)					
HYBRID COMBINER (QTY/MODEL)					
DUPLEXER (QTY/MODEL)					
FILTER (QTY/MODEL)					
RX/IT KIT MODULE?					
TRIPLEXER or NARROW BAND LLC (QTY/MODEL)					
SCPA/MCPA MODULE?					
Additional Component1					
Additional Component2					
Additional Component3					
MAGNETIC DECLINATION					
HATCHPLATE POWER (Watts)					
ERP (Watts)					
Local Market Note1					
Local Market Note2					
Local Market Note3					

Section 16A - NEW PROPOSED SECTOR/CELL INFORMATION - ALPHA (OR GAMMA)									
ANTENNA CONFIG (FROM BACK):	ANTENNA 1 GSM, UMTS (850 / 1900) or LTE (700 / AWS)	ANTENNA 2 GSM, UMTS (850 / 1900) or LTE (700 / AWS)	ANTENNA 3 GSM, UMTS (850 / 1900) or LTE (700 / AWS)	ANTENNA 4 GSM, UMTS (850 / 1900) or LTE (700 / AWS)	ANTENNA 5 GSM, UMTS (850 / 1900) or LTE (700 / AWS)				
TX/RX?									
TECHNOLOGY									
RRH LOCATION (Top/Bottom/None)									
FEEDERS TYPE	1 1/4" - RFS				1 1/4" - RFS				
Feeder Length (feet)	175'				175'				
ANTENNA ATOLL									
ANTENNA MAKE - MODEL	7770		P65-16-XLH-RR 716MHz	P65-16-XLH-RR 716MHz	02DT	7770			
ANTENNA VENDOR	Powerwave					Powerwave			
ANTENNA SIZE (H x W x D)						72.0 x 12.0 x 6.0			
ANTENNA WEIGHT						64			
ANTENNA GAIN			14.0 dBi						
AZIMUTH	138°			30°		138°			
RADIATION CENTER (feet)	148°			150°		148°			
ANTENNA TIP HEIGHT				153°					
ELECTRICAL TILT (700/850/1900/AWS)	6°	2°	2°			TBD	0°	2°	
MECHANICAL DOWNTILT	0°			0°			0°		
FEEDER AMOUNT	2					2			
Antenna RET Motor (QTY/MODEL)									
Antenna RET Splitter (QTY/MODEL)									
Antenna RET Earth (Grounding) Clamp (QTY/MODEL)									
Antenna RET Surge Arrestor (QTY/MODEL)									
Antenna RET CONTROL UNIT (QTY/MODEL) usually per site									
DC BLOCK (QTY/MODEL)									
TMA/LNA (TYPE/MODEL)	2 / Powerwave / LGP 21401 (Dual Band -					0 / N/A			
CURRENT INJECTORS FOR TMA (QTY/MODEL)									
POU FOR TMA (QTY/MODEL) usually per site									
SURGE ARRESTOR (QTY/MODEL)									
DIPLEXER (QTY/MODEL)	* 2 / Powerwave / LGP 21901					* 2 / Powerwave / LGP 21901			
HYBRID COMBINER (QTY/MODEL)									
DUPLEXER (QTY/MODEL)									
FILTER (QTY/MODEL)									
RKAT KIT MODULE?									
TRIPLEXER or NARROW BAND LLC (QTY/MODEL)									
SCPA/MCPA MODULE?									
Additional Component1									
Additional Component2									
Additional Component3									
MAGNETIC DECLINATION									
HATCHPLATE POWER (Watts)									
ERP (Watts)									
Local Market Note1									
Local Market Note2									
Local Market Note3									

Section 16B - NEW PROPOSED SECTOR/CELL INFORMATION - BETA									
ANTENNA CONFIG (FROM BACK):	ANTENNA 1 GSM, UMTS (850 / 1900) or LTE (700 / AWS)	ANTENNA 2 GSM, UMTS (850 / 1900) or LTE (700 / AWS)	ANTENNA 3 GSM, UMTS (850 / 1900) or LTE (700 / AWS)	ANTENNA 4 GSM, UMTS (850 / 1900) or LTE (700 / AWS)	ANTENNA 5 GSM, UMTS (850 / 1900) or LTE (700 / AWS)				
TX/RX?									
TECHNOLOGY									
RRH LOCATION (Top/Bottom/None)									
FEEDERS TYPE	1 1/4" - RFS				1 1/4" - RFS				
Feeder Length (feet)	175'				175'				
ANTENNA ATOLL									
ANTENNA MAKE - MODEL	7770		P65-16-XLH-RR 716MHz	P65-16-XLH-RR 716MHz	06DT	7770			
ANTENNA VENDOR	Powerwave					Powerwave			
ANTENNA SIZE (H x W x D)						72.0 x 12.0 x 6.0			
ANTENNA WEIGHT						64			
ANTENNA GAIN			14.0 dBi						
AZIMUTH	261°			150°		261°			
RADIATION CENTER (feet)	148°			150°		148°			
ANTENNA TIP HEIGHT				153°					
ELECTRICAL TILT (700/850/1900/AWS)	4°	0°	6°			TBD	0°		
MECHANICAL DOWNTILT	0°			0°			0°		
FEEDER AMOUNT	2					2			
Antenna RET Motor (QTY/MODEL)									
Antenna RET Splitter (QTY/MODEL)									
Antenna RET Earth (Grounding) Clamp (QTY/MODEL)									
Antenna RET Surge Arrestor (QTY/MODEL)									
Antenna RET CONTROL UNIT (QTY/MODEL) usually per site									
DC BLOCK (QTY/MODEL)									
TMA/LNA (TYPE/MODEL)	2 / Powerwave / LGP 21401 (Dual Band -					0 / N/A			
CURRENT INJECTORS FOR TMA (QTY/MODEL)									
POU FOR TMA (QTY/MODEL) usually per site									
SURGE ARRESTOR (QTY/MODEL)									
DIPLEXER (QTY/MODEL)	* 2 / Powerwave / LGP 21901					* 2 / Powerwave / LGP 21901			
HYBRID COMBINER (QTY/MODEL)									
DUPLEXER (QTY/MODEL)									
FILTER (QTY/MODEL)									
RKAT KIT MODULE?									
TRIPLEXER or NARROW BAND LLC (QTY/MODEL)									
SCPA/MCPA MODULE?									
Additional Component1									
Additional Component2									
Additional Component3									
MAGNETIC DECLINATION									
HATCHPLATE POWER (Watts)									
ERP (Watts)									
Local Market Note1									
Local Market Note2									
Local Market Note3									

Section 16C - NEW PROPOSED SECTOR/CELL INFORMATION - GAMMA									
ANTENNA CONFIG (FROM BACK):	ANTENNA 1 GSM, UMTS (850 / 1900) or LTE (700 / AWS)	ANTENNA 2 GSM, UMTS (850 / 1900) or LTE (700 / AWS)	ANTENNA 3 GSM, UMTS (850 / 1900) or LTE (700 / AWS)	ANTENNA 4 GSM, UMTS (850 / 1900) or LTE (700 / AWS)	ANTENNA 5 GSM, UMTS (850 / 1900) or LTE (700 / AWS)				
TX/RX?									
TECHNOLOGY									
RRH LOCATION (Top/Bottom/None)									
FEEDERS TYPE	1 1/4" - RFS				1 1/4" - RFS				
Feeder Length (feet)	175'				175'				
ANTENNA ATOLL									
ANTENNA MAKE - MODEL	7770		P65-16-XLH-RR 716MHz	P65-16-XLH-RR 716MHz	08DT	7770			
ANTENNA VENDOR	Powerwave					Powerwave			
ANTENNA SIZE (H x W x D)						72.0 x 12.0 x 6.0			
ANTENNA WEIGHT						64			
ANTENNA GAIN			14.0 dBi						
AZIMUTH	25°			270°		25°			
RADIATION CENTER (feet)	148°			150°		148°			
ANTENNA TIP HEIGHT				153°					
ELECTRICAL TILT (700/850/1900/AWS)	4°	0°	8°			TBD	0°	0°	
MECHANICAL DOWNTILT	0°			0°			0°		
FEEDER AMOUNT	2					2			
Antenna RET Motor (QTY/MODEL)									
Antenna RET Splitter (QTY/MODEL)									
Antenna RET Earth (Grounding) Clamp (QTY/MODEL)									
Antenna RET Surge Arrestor (QTY/MODEL)									
Antenna RET CONTROL UNIT (QTY/MODEL) usually per site									
DC BLOCK (QTY/MODEL)									
TMA/LNA (TYPE/MODEL)	2 / Powerwave / LGP 21401 (Dual Band -					0 / N/A			
CURRENT INJECTORS FOR TMA (QTY/MODEL)									
POU FOR TMA (QTY/MODEL) usually per site									
SURGE ARRESTOR (QTY/MODEL)									
DIPLEXER (QTY/MODEL)	* 2 / Powerwave / LGP 21901					* 2 / Powerwave / LGP 21901			
HYBRID COMBINER (QTY/MODEL)									
DUPLEXER (QTY/MODEL)									
FILTER (QTY/MODEL)									
RKAT KIT MODULE?									
TRIPLEXER or NARROW BAND LLC (QTY/MODEL)									
SCPA/MCPA MODULE?									
Additional Component1									
Additional Component2									
Additional Component3									
MAGNETIC DECLINATION									
HATCHPLATE POWER (Watts)									
ERP (Watts)									
Local Market Note1									
Local Market Note2									
Local Market Note3									

Section 16D - NEW PROPOSED SECTOR/CELL INFORMATION - DELTA					
ANTENNA CONFIG (FROM BACK):	ANTENNA 1 GSM, UMTS (850 / 1900) or LTE (700 / AWS)	ANTENNA 2 GSM, UMTS (850 / 1900) or LTE (700 / AWS)	ANTENNA 3 GSM, UMTS (850 / 1900) or LTE (700 / AWS)	ANTENNA 4 GSM, UMTS (850 / 1900) or LTE (700 / AWS)	ANTENNA 5 GSM, UMTS (850 / 1900) or LTE (700 / AWS)
TX/RX?					
TECHNOLOGY					
RRH LOCATION (Top/Bottom/None)					
FEDERS TYPE					
Feeder Length (feet)					
ANTENNA ATOLL					
ANTENNA MAKE - MODEL					
ANTENNA VENDOR					
ANTENNA SIZE (H x W x D)					
ANTENNA WEIGHT					
ANTENNA GAIN					
AZIMUTH					
RADIATION CENTER (feet)					
ANTENNA TIP HEIGHT					
ELECTRICAL TILT (700/850/1900/AWS)					
MECHANICAL DOWNTILT					
FEDER AMOUNT					
Antenna RET Motor (QTY/MODEL)					
Antenna RET Splitter (QTY/MODEL)					
Antenna RET Earth (Grounding) Clamp (QTY/MODEL)					
Antenna RET Surge Arrestor (QTY/MODEL)					
Antenna RET CONTROL UNIT (QTY/MODEL) usually per site					
DC BLOCK (QTY/MODEL)					
TMA/LNA (TYPE/MODEL)					
CURRENT INJECTORS FOR TMA (QTY/MODEL)					
PDU FOR TMA (QTY/MODEL) usually per site					
SURGE ARRESTOR (QTY/MODEL)					
DUPLEXER (QTY/MODEL)					
HYBRID COMBINER (QTY/MODEL)					
DUPLEXER (QTY/MODEL)					
FILTER (QTY/MODEL)					
RRX/IT MODULE?					
TRIPLEXER or NARROW BAND LLC (QTY/MODEL)					
SCPA/MCPA MODULE?					
Additional Component1					
Additional Component2					
Additional Component3					
MAGNETIC DECLINATION					
HATCHPLATE POWER (Watts)					
ERP (Watts)					
Local Market Note1					
Local Market Note2					
Local Market Note3					

Section 16E - NEW PROPOSED SECTOR/CELL INFORMATION - EPSILON					
ANTENNA CONFIG (FROM BACK):	ANTENNA 1 GSM, UMTS (850 / 1900) or LTE (700 / AWS)	ANTENNA 2 GSM, UMTS (850 / 1900) or LTE (700 / AWS)	ANTENNA 3 GSM, UMTS (850 / 1900) or LTE (700 / AWS)	ANTENNA 4 GSM, UMTS (850 / 1900) or LTE (700 / AWS)	ANTENNA 5 GSM, UMTS (850 / 1900) or LTE (700 / AWS)
TX/RX?					
TECHNOLOGY					
RRH LOCATION (Top/Bottom/None)					
FEDERS TYPE					
Feeder Length (feet)					
ANTENNA ATOLL					
ANTENNA MAKE - MODEL					
ANTENNA VENDOR					
ANTENNA SIZE (H x W x D)					
ANTENNA WEIGHT					
ANTENNA GAIN					
AZIMUTH					
RADIATION CENTER (feet)					
ANTENNA TIP HEIGHT					
ELECTRICAL TILT (700/850/1900/AWS)					
MECHANICAL DOWNTILT					
FEDER AMOUNT					
Antenna RET Motor (QTY/MODEL)					
Antenna RET Splitter (QTY/MODEL)					
Antenna RET Earth (Grounding) Clamp (QTY/MODEL)					
Antenna RET Surge Arrestor (QTY/MODEL)					
Antenna RET CONTROL UNIT (QTY/MODEL) usually per site					
DC BLOCK (QTY/MODEL)					
TMA/LNA (TYPE/MODEL)					
CURRENT INJECTORS FOR TMA (QTY/MODEL)					
PDU FOR TMA (QTY/MODEL) usually per site					
SURGE ARRESTOR (QTY/MODEL)					
DUPLEXER (QTY/MODEL)					
HYBRID COMBINER (QTY/MODEL)					
DUPLEXER (QTY/MODEL)					
FILTER (QTY/MODEL)					
RRX/IT MODULE?					
TRIPLEXER or NARROW BAND LLC (QTY/MODEL)					
SCPA/MCPA MODULE?					
Additional Component1					
Additional Component2					
Additional Component3					
MAGNETIC DECLINATION					
HATCHPLATE POWER (Watts)					
ERP (Watts)					
Local Market Note1					
Local Market Note2					
Local Market Note3					

Section 16F - NEW PROPOSED SECTOR/CELL INFORMATION - ZETA					
ANTENNA CONFIG (FROM BACK):	ANTENNA 1 GSM, UMTS (850 / 1900) or LTE (700 / AWS)	ANTENNA 2 GSM, UMTS (850 / 1900) or LTE (700 / AWS)	ANTENNA 3 GSM, UMTS (850 / 1900) or LTE (700 / AWS)	ANTENNA 4 GSM, UMTS (850 / 1900) or LTE (700 / AWS)	ANTENNA 5 GSM, UMTS (850 / 1900) or LTE (700 / AWS)
TX/RX?					
TECHNOLOGY					
RRH LOCATION (Top/Bottom/None)					
FEDERS TYPE					
Feeder Length (feet)					
ANTENNA ATOLL					
ANTENNA MAKE - MODEL					
ANTENNA VENDOR					
ANTENNA SIZE (H x W x D)					
ANTENNA WEIGHT					
ANTENNA GAIN					
AZIMUTH					
RADIATION CENTER (feet)					
ANTENNA TIP HEIGHT					
ELECTRICAL TILT (700/850/1900/AWS)					
MECHANICAL DOWNTILT					
FEDER AMOUNT					
Antenna RET Motor (QTY/MODEL)					
Antenna RET Splitter (QTY/MODEL)					
Antenna RET Earth (Grounding) Clamp (QTY/MODEL)					
Antenna RET Surge Arrestor (QTY/MODEL)					
Antenna RET CONTROL UNIT (QTY/MODEL) usually per site					
DC BLOCK (QTY/MODEL)					
TMA/LNA (TYPE/MODEL)					
CURRENT INJECTORS FOR TMA (QTY/MODEL)					
PDU FOR TMA (QTY/MODEL) usually per site					
SURGE ARRESTOR (QTY/MODEL)					
DUPLEXER (QTY/MODEL)					
HYBRID COMBINER (QTY/MODEL)					
DUPLEXER (QTY/MODEL)					
FILTER (QTY/MODEL)					
RRX/IT MODULE?					
TRIPLEXER or NARROW BAND LLC (QTY/MODEL)					
SCPA/MCPA MODULE?					
Additional Component1					
Additional Component2					
Additional Component3					
MAGNETIC DECLINATION					
HATCHPLATE POWER (Watts)					
ERP (Watts)					
Local Market Note1					
Local Market Note2					
Local Market Note3					

P65-16-XLH-RR**Dual Broadband Antennas**


POLARIZATION: Dual linear $\pm 45^\circ$
 FREQUENCY (MHz): 698-894, 1710-2170
 HORIZONTAL BEAM WIDTH ($^\circ$): 65, 65
 GAIN (dBi/dBd): 15.5/13.4 17.5/15.4
 TILT: 1-12, 0-8
 LENGTH: 72"

ELECTRICAL SPECIFICATIONS*

	698-894		1710-2170		
Frequency range (MHz)	698-894		1710-2170		
Frequency band (MHz)	698-806	806-894	1710-1880	1850-1990	1900-2170
Gain (dBi/dBd)	14.8/12.7	15.5/13.4	16.9/14.8	17.2/15.1	17.5/15.4
Polarization	Dual Linear +/- 45		Dual Linear +/- 45		
Nominal Impedance (Ω)	50		50		
VSWR	< 1.5:1		< 1.5:1		
Horizontal beam width, -3 dB (°)	66	65	60	63	63
Vertical beam width, -3 dB (°)	14.7	12.5	6.8	6.4	5.7
Electrical down tilt (°)	1 to 12		0 to 8		
Side lobe suppression, vertical 1st upper (dB)	> 16	>16	> 16		
	>16	>16			
Isolation between inputs (dB)	> 30	> 30	> 30	> 30	
Inter band Isolation (dB)	> 40		> 40		
Tracking, horizontal plane ±60° (dB)	< 2		< 2	< 2	< 2
First null fill (dB)			>-20	>-20	>-20
Vertical beam squint (°)	< 0.8	< 0.8	< 0.5	< 0.5	< 0.5
Front to back ratio (dB) 180°±30° copolar	>24	>24	> 30	>30	>28
Front to back ratio (dB) 180°±30° total power					
Cross polar discrimination (XPD) 0° (dB)	> 15	> 15	> 15	> 15	> 15
Cross polar discrimination (XPD) ±60° (dB)	> 10	> 10	> 10	> 10	> 10
Far field coupling					
IM3, 2xTx@43dBm (dBc)	<-153		<-153		
IM7, 2xTx@43dBm (dBc)					
Power handling, average per input (W)	500		250		
Power handling, average total (W)	1000		500		

MECHANICAL SPECIFICATIONS*

Connector	4 X 7/16 DIN Female, IP67
Connector position	Bottom
Dimensions, HxWxD, mm (ft)	72" x 12" x 6" (1829 x 305 x 152)
Mounting	Pre-mounted Tilt Brackets
Weight, with brackets, kg (lbs)	29 (64)
Weight, without brackets, kg (lbs)	24 (53)
Wind load, frontal/lateral/rear side 42 m/s Cd=1.6 (N)	1380
Maximum operational wind speed, m/s (mph)	100 (45)
Survival wind speed, m/s (mph)	150 (67)
Lightning protection	DC Ground
Operating Temperature	-40C to +60C
Radome material	PVC, IP55
Packet size, HxWxD, mm (ft)	87" x 16" x 10" (2225 x 400 x 225)
Radome colour	Light Grey
Shipping weight, kg (lbs)	34 (75)
RET	IRET AISGv1.1, MET and AISGv2.0
Brackets	7256.00, 7454.00



*All specifications subject to change without notice. Please contact your Powerwave representative for complete performance data.

ANTENNA PATTERNS*

For detailed patterns visit <http://www.powerwave.com/rpa/>.

7770.00A**DBB90 Broadband Cross Polarized**

POLARIZATION: XX-Pol

FREQUENCY (MHz): 824-896, 1710-2170

HORIZONTAL BEAM WIDTH (°): 90

GAIN (dBi/dBd): 13.5/11.4, 15.5/13.4

TILT: MET


LENGTH: 1.4m (4'7")

ELECTRICAL SPECIFICATIONS*

Frequency range (MHz)	824-896	1710-1880	1710-2170	
Frequency band (MHz)	824-896	1710-1880	1850-1990	1900-2170
Gain (dBi/dBd)	13.5/11.4	15.5/13.4	15.5/13.4	15.5/13.4
Polarization	Dual linear $\pm 45^\circ$		Dual linear $\pm 45^\circ$	
Nominal Impedance (Ω)	50		50	
VSWR	<1.5:1		<1.5:1	
Horizontal beam width, -3 dB (°)	85	90	90	90
Vertical beam width, -3 dB (°)	15	7	7	7
Electrical down tilt (°)	0 to 10		0 to 8	
Side lobe suppression, vertical 1st upper (dB)	>18	>18	>18	>18
Isolation between inputs (dB)	>30	>30	>30	>25
Inter band Isolation (dB)	>36		>36	
Tracking, horizontal plane $\pm 60^\circ$ (dB)	<2	<2	<2	<2
First null fill (dB)	-	-	-	-
Vertical beam squint (°)	<1.0	<0.5	<0.5	<0.5
Front to back ratio (dB) $180^\circ \pm 30^\circ$ copolar	>25	>25	>25	>25
Front to back ratio (dB) $180^\circ \pm 30^\circ$ total power	>22	>21	>21	>21
Cross polar discrimination (XPD) 0° (dB)	-	-	-	-
Cross polar discrimination (XPD) $\pm 60^\circ$ (dB)	>10	>10	>10	>10
Far field coupling	-	-	-	-
IM3, 2xTx@43dBm (dBc)	<-153		<-153	
IM7, 2xTx@43dBm (dBc)	-		<-160	
Power handling, average per input (W)	500		250	
Power handling, average total (W)	800		500	

MECHANICAL SPECIFICATIONS*

Connector	4 x 7/16 DIN Female
Connector position	Bottom
Dimensions, HxWxD, mm (ft)	1408x280x125mm
Mounting	Pre-mounted heavy duty brackets
Weight, with brackets, kg (lbs)	17.6 (39)
Weight, without brackets, kg (lbs)	12.1 (27)
Wind load, frontal/lateral/rear side 42 m/s Cd=1.6 (N)	415
Maximum operational wind speed, m/s (mph)	42 (93)
Survival wind speed, m/s (mph)	55 (123)
Lightning protection	DC grounded
Operating Temperature	-40°C to +60°C
Radome material	GRP
Package size, HxWxD, mm (ft)	1550x355x255 (61"x1'2"x10")
Radome colour	Light Grey
Shipping weight, kg (lbs)	21.5 (47.4)
RET	8220.10, 8220.40, 8210.10, 8210.40
Brackets	7256.00, 7454.00




*All specifications subject to change without notice. Please contact your Powerwave representative for complete performance data.

ANTENNA PATTERNS*

For detailed patterns visit <http://www.powerwave.com/rpa/>.

Tower Mounted Amplifier



1900/850 MHz

Technical Specifications


Product Number	LGP214nn	
850 MHz	Bypass (MHz)	824-894
	Return loss* (dB)	> 20
	Insertion loss* (dB)	< 0.3
1900 MHz		
Up-link	Frequency range, full band (60 MHz)	1850-1910
	Nominal gain (dB)	12
	Return loss* (dB)	> 20
	Noise figure* (dB)	< 1.7
	Output 3rd order Intercept Point* (dBm)	> +23
Down-link	Frequency range, full band (60 MHz)	1930-1990
	Insertion loss* (dB)	< 0.6
	Return loss* (dB)	> 20
Intermodulation	2 Tx@x43 dBm (dBc)	<-158
Alarm Functionality	Two levels, individually supervised LNAs	
Power Consumption	@12 VDC	1.2 W

* Typical

All specifications subject to change without notice. Please contact your Powerwave representative for complete performance data.

Mechanical Specifications

Size, W x H x D (without mounting plate)	235 x 366 x 66 mm (9.2 x 14.4 x 2.6 in)
Weight	6.4 kg (14.1 lbs)
Color	Off white (NCS 1502-R)
Housing	Aluminum
RF-connectors	DIN 7/16 female.
Mounting kit	Mounting kit for pole and wall is included
Temperature range	-40 °C to +65 °C (-40 °F to +149 °F)
MTBF	>1 million hours
Safety	UL 60 950
Ingress protection, IP 65	EN 60 529
Environmental	ETS 300 019
EMC	FCC Part 15



Corporate Headquarters
Powerwave Technologies, Inc.
1801 East St. Andrew Place
Santa Ana, CA 92705 USA

Tel: 714-466-1000
Fax: 714-466-5800
www.powerwave.com

Main European Office
Antennvägen 6
SE-187 80 Täby
Sweden
Tel: +46 8 540 822 00
Fax: +46 8 540 823 40

Main Asia-Pacific Office
23 F Tai Yau Building
181 Johnston Road
Wanchai, Hong Kong
Tel: +852 2512 6123
Fax: +852 2575 4860



©Copyright 2006, Powerwave Technologies, Inc. All Rights reserved. Powerwave, Powerwave Technologies, The Power in Wireless and the Powerwave logo are registered trademarks of Powerwave Technologies, Inc.

COVERAGE AND CAPACITY

TECHNOLOGY LEADERSHIP

GLOBAL PARTNER

INTEGRATED SOLUTIONS

QUALITY AND RELIABILITY

LGP219nn**Diplex Filter for 800/900 MHz and 1800/1900/2100 MHz with Configurable DC Transparency****TECHNICAL SPECIFICATIONS**


Range (MHz)	800-2170	
Frequency Range (Full Band MHz)	824-960 MHz/1710-2170 MHz	
Frequency Range (MHz)	824-960 Port, 824-960 MHz	1710-2100 Port, 1710-2170 MHz
Insertion Loss (dB)	824-960 Port: <0.1 dB Typical	1710-2100 Port: <0.2 dB Typical
Return Loss (dB)	824-960 Port, 20 dB minimum	1710-2100 Port, 20 dB minimum
Rejection UL	N/A	
Rejection DL	N/A	
Rejection	824-960 Port, 1710-1990 MHz, 52 dB minimum	1710-2170 Port, 824-960 MHz, 52 dB minimum
Transmit Band Rejection (dB)	N/A	N/A
Average Power Handling (dBm)	N/A	N/A
Peak Power (dBm)	824-960 Port, 800 AMPS, 10 kW; 900 MHz, 1600 kW	1710-2100 Port, 1800 MHz, 1600 kW; 1900 MHz, 5 kW
Max Power	824-960 Port, 800 MHz, 500W average; 900 MHz, 200 W average	1710-2100 Port, 1800 MHz, 200 W average; 1900 MHz, 300 W average
Intermodulation (IM) (dBc) (Products, Max)	824-960 Port, -110 dBm (-153 dBc), two/+43 dBm carriers in the Tx band	1710-2100 Port, -110 dBm (-153 dBc), two/+43 dBm carriers in the Tx band
Common+Port	TMA supply voltage, fed via the RF cable, +31 V maximum, 2 A	
DC Bias/AISG Passthru	N/A	

MECHANICAL SPECIFICATIONS

Dimensions mm(ft)	112 x 158 x 74 (4"x 6"x 3")
Weight kg(lbs)	2.5 (5.5) maximum
Volume	1.3 liter single unit
Color	Off White (NCS 1502-R)
Housing	Aluminum
RF Connectors	DIN 7/16 female
Mounting Kit	Hose Clamps in Stainless Steel

ENVIRONMENTAL SPECIFICATIONS

Temperature Range Celsius (Fahrenheit)	-40°to +65°(-40°to +149°)
MTBF	10 Million Hours
Lightning Protection	According to IEC 61312-1, 3kA 10/350 uS:center pin (any port)-shield
Safety	EN 60 950, UL 1950, ETL
Ingress Protection	IP65, EN 60 529
Environmental	ETS 300 019
EMC	ETS 300 342-3



RRUS 11 – Dual PA RRU.

Technical Data

RBS6000


- › Multi standard
- › RF: 2x30 Watts
- › Carrier BW: 1.4 – 20 MHz
- › Alarms: 2
- › Dimensions (with sunshield):
 - Width: 17.0 in
 - Height: 17.8 in
 - Depth: 7.2 in
 - Weight: 55 lbs (Band 12)
 - Weight: 50 lbs (Band 4)
- › Temperature: -40 to +131 F
- › Cooling: Self convection
- › Power: -48 VDC
- › Rec. fuse size 20 Amp
 - Rec. DC cable:
 - › 6 mm² up to 60 meters
 - › 10 mm² over 60 meters
 - › Shielded
- › Power Cons: 200 Watts typ.



RRUS-11 I/F



RBS6000



POWER



DC6-48-60-18-8F

DC Surge Suppression Solution

The DC6-48-60-18 is a dual chambered, DC surge suppression system for use in multi-circuit, Distributed Antenna Systems. The system will protect up to 6 Remote Radio Heads from voltage surges and lightning, and connect up to 18 fiber pairs. The system is enclosed in a NEMA 4 rated, waterproof enclosure.

FEATURES

- Protects up to 6 Remote Radio Heads, each with its own protection circuit.
- Flexible design allows for installation at the top of a tower for Remote Radio Head protection.
- Includes fiber connections for up to 18 pairs of fiber.
- LED indicators on individual circuits provide visual indication of suppressor status.
- Form 'C' relays allow for remote monitoring of the suppressor status.
- Patented Strikesorb technology provides over 60 kA of surge current capacity per circuit.
- Strikesorb suppression modules are fully recognized to UL 1449-3rd Edition Safety Standard, meeting all intermediate and high current fault requirements to facilitate use in OEM applications.
- Raycap recommends that DC protection system be installed within 2 meters or 6 feet of the radio.
- Dome design is lightweight and aerodynamic providing maximum flexibility for installation on top of towers.



Raycap

DC6-48-60-18-8F

DC Power Surge Protection

Electrical Specifications	
Model Number	DC6-48-60-18-8F
Nominal Operating Voltage	48 VDC
Nominal Discharge Current (I_n)	20 kA 8/20 μ s
Maximum Discharge Current (I_{max}) per NEMA LS-1	60 kA 8/20 μ s
Maximum Continuous Operating Voltage (U_c)	75 VDC
Voltage Protection Rating	400 V

Mechanical Specifications	
Suppression Connection Method	Compression lug, #2-#14 AWG Copper, #2-#12 Aluminum
Fiber Connection Method	LC-LC Single mode duplex
Environmental Rating	IP 68, 7m 72hrs
Operating Temperature	-40° C to + 80° C
Storage Temperature	-70° C to + 80° C
Cold Temperature Cycling	IEC 61300-2-22e -30° C to + 60° C 200 hrs @ 5 psi
Resistance to Aggressive Materials	CEI IEC 61073-2 including acids and bases
UV Protection	ISO 4892-2 Method A Xenon-Arc 2160 hrs
Weight	20 lbs without Mounting Bracket

STANDARDS

Strikesorb modules are compliant to the following Surge Protection Device (SPD) Standards:

- ANSI/UL 1449 - 3rd Edition
- IEEE C62.41
- NEMA LS-1, IEC 61643-1:2005 2nd Edition:2005
- IEC 61643-12
- EN 61643-11:2002 (including A11:2007)



Raycap

G02-00-068 REV 050610



GS-07F-0435V



Certified to
ISO 9001:2000



TUV Rheinland
of North America

Raycap, Inc. 806 W. Clearwater Loop • Post Falls • Idaho • 83854 • USA
Phone 208.777.1166 • Toll Free 800.890.2569 • Fax 208.777.4466 • www.raycapsurgeprotection.com

P65-16-XLH-RR**Dual Broadband Antennas**


POLARIZATION: Dual linear $\pm 45^\circ$
 FREQUENCY (MHz): 698-894, 1710-2170
 HORIZONTAL BEAM WIDTH ($^\circ$): 65, 65
 GAIN (dBi/dBd): 15.5/13.4 17.5/15.4
 TILT: 1-12, 0-8
 LENGTH: 72"

ELECTRICAL SPECIFICATIONS*

	698-894			1710-2170	
Frequency range (MHz)	698-806	806-894		1710-1880	1850-1990
Frequency band (MHz)	14.8/12.7	15.5/13.4		16.9/14.8	17.2/15.1
Gain (dBi/dBd)	Dual Linear +/- 45			Dual Linear +/- 45	
Polarization	50			50	
Nominal Impedance (Ω)	< 1.5:1			< 1.5:1	
VSWR	< 1.5:1			< 1.5:1	
Horizontal beam width, -3 dB ($^\circ$)	66	65		60	63
Vertical beam width, -3 dB ($^\circ$)	14.7	12.5		6.8	5.7
Electrical down tilt ($^\circ$)	1 to 12			0 to 8	
Side lobe suppression, vertical 1st upper (dB)	> 16	> 16		> 16	
	> 16	> 16			
Isolation between inputs (dB)	> 30	> 30		> 30	> 30
Inter band isolation (dB)	> 40			> 40	
Tracking, horizontal plane $\pm 60^\circ$ (dB)	< 2			< 2	< 2
First null fill (dB)				> -20	> -20
Vertical beam squint ($^\circ$)	< 0.8	< 0.8		< 0.5	< 0.5
Front to back ratio (dB) $180^\circ \pm 30^\circ$ copolar	> 24	> 24		> 30	> 28
Front to back ratio (dB) $180^\circ \pm 30^\circ$ total power					
Cross polar discrimination (XPD) 0° (dB)	> 15	> 15		> 15	> 15
Cross polar discrimination (XPD) $\pm 60^\circ$ (dB)	> 10	> 10		> 10	> 10
Far field coupling					
IM3, 2xTx@43dBm (dBc)	< -153			< -153	
IM7, 2xTx@43dBm (dBc)					
Power handling, average per input (W)	500			250	
Power handling, average total (W)	1000			500	

MECHANICAL SPECIFICATIONS*

Connector	4 X 7/16 DIN Female, IP67
Connector position	Bottom
Dimensions, HxWxD, mm (ft)	72" x 12" x 6" (1829 x 305 x 152)
Mounting	Pre-mounted Tilt Brackets
Weight, with brackets, kg (lbs)	29 (64)
Weight, without brackets, kg (lbs)	24 (53)
Wind load, frontal/lateral/rear side 42 m/s Cd=1.6 (N)	1380
Maximum operational wind speed, m/s (mph)	100 (45)
Survival wind speed, m/s (mph)	150 (67)
Lightning protection	DC Ground
Operating Temperature	-40C to +60C
Radome material	PVC, IP55
Packet size, HxWxD, mm (ft)	87" x 16" x 10" (2225 x 400 x 225)
Radome colour	Light Grey
Shipping weight, kg (lbs)	34 (75)
RET	iRET AISGv1.1, MET and AISGv2.0
Brackets	7256.00, 7454.00



*All specifications subject to change without notice. Please contact your Powerwave representative for complete performance data.

ANTENNA PATTERNS*

For detailed patterns visit <http://www.powerwave.com/rpa/>.



New Cingular Wireless PCS, LLC
500 Enterprise Drive
Rocky Hill, Connecticut 06067-3900
Phone: (860) 463-5511
Fax: (860) 513-7190

Douglas L. Culp
Real Estate Consultant

March 30, 2011

Honorable Karen Goldberg
1st Selectman, Town of Orange
Orange Town Hall
617 Orange Center Road
Orange, CT 06477

Re: Telecommunications Facility – 525 Orange Center Road Orange, CT

Dear Ms. Goldberg:

In order to accommodate technological changes, implement Uniform Mobile Telecommunications System (“UMTS”) and Long Term Evolution (“LTE”) capabilities, and enhance system performance in the State of Connecticut, New Cingular Wireless PCS, LLC (“AT&T”) will be changing its equipment configuration at certain cell sites.

As required by Regulations of Connecticut State Agencies (“R.C.S.A.”) Section 16-50j-73, the Connecticut Siting Council has been notified of the changes and will review AT&T’s proposal. Please accept this letter as notification under Section 16-50j-73 of construction which constitutes an exempt modification pursuant to R.C.S.A. Section 16-50j-72(b)(2).

The accompanying letter to the Siting Council fully describes Cingular’s proposal for the referenced cell site. However, if you have any questions or require any further information on our plans or the Siting Council’s procedures; please call me at (860) 463-5511 or Ms. Linda Roberts, Executive Director, Connecticut Siting Council at (860) 827-2935.

Sincerely,

Douglas L. Culp
Real Estate Consultant

Enclosure