



Northeast Site Solutions
Victoria Masse
420 Main St Unit 1 Box 2
Sturbridge, MA 01566
victoria@northeastsitesolutions.com

January 31, 2023

Members of the Siting Council
Connecticut Siting Council
Ten Franklin Square
New Britain, CT 06051

RE: Tower Share Application
525 Orange Center Road, New Haven CT 06477
Latitude: 41.273700 N
Longitude: -73.018828 W
Site#: BOHVN00191A

Dear Ms. Bachman:

This letter and attachments are submitted on behalf of Dish Wireless LLC. Dish Wireless LLC plans to install antennas and related equipment to the tower site located at 525 Orange Center Road, New Haven, Connecticut.

Dish Wireless LLC proposes to install three (3) 600/1900/2100 5G MHz antenna and six (6) RRUs, at the 136-foot level of the existing 160-foot monopole tower, one (1) Fiber cable will also be installed. Dish Wireless LLC equipment cabinets will be placed within 7x5 lease area. Included are plans by Infinigy, dated January 25, 2023, Exhibit C. Also included is a structural analysis prepared by Infinigy, dated December 29, 2022 confirming that the existing tower is structurally capable of supporting the proposed equipment. Attached as Exhibit D. This facility was approved by the Connecticut Siting Council, Docket No. 177A on August 6, 1997. Please see attached Exhibit A.

Please accept this letter as notification pursuant to Regulations of Connecticut State Agencies 16-50aa, of Dish Wireless LLC intent to share a telecommunications facility pursuant to R.C.S.A. 16-50j-88. In accordance with R.C.S.A., a copy of this letter is being sent to James M. Zeoli First Selectman, Jack Demirjian, Zoning Administrator & Enforcement Officer, as well as the property owner and tower owner.

The planned modifications of the facility fall squarely within those activities explicitly provided for in R.C.S.A. 16-50j-89.

1. The proposed modifications will not result in an increase in the height of the existing structure. The top of the tower is 160-feet; Dish Wireless LLC proposed antennas will be located at a center line height of 136-feet.
2. The proposed modification will not result in the increase of the site boundary as depicted on the attached site plan.
3. The proposed modification will not increase the noise levels at the facility by six decibels or more, or to levels that exceed local and state criteria. The incremental effect of the proposed changes will be negligible.

420 Main Street, Unit 1 Box 2, Sturbridge, MA 01566



4. The operation of the proposed antennas will not increase radio frequency emissions at the facility to a level at or above the Federal Communications Commission safety standard. As indicated in the attached power density calculations, the combined site operations will result in a total density of 9.18% as evidenced by Exhibit F.

Connecticut General Statutes 16-50-aa indicates that the Council must approve the shared use of a telecommunications facility provided it finds the shared use is technically, legally, environmentally, and economically feasible and meets public safety concerns. As demonstrated in this letter, Dish Wireless LLC respectfully indicates that the shared use of this facility satisfies these criteria.

A. Technical Feasibility. The existing monopole has been deemed structurally capable of supporting Dish Wireless LLC proposed loading. The structural analysis is included in Exhibit D.

B. Legal Feasibility. As referenced above, C.G.S. 16-50aa has been authorized to issue orders approving the shared use of an existing tower such as this monopole in Orange. Under the authority granted to the Council, an order of the Council approving the requested shared use would permit Dish Wireless LLC to obtain a building permit for the proposed installation. Further, a letter of Authorization is included as Exhibit G, authorizing Dish Wireless LLC to file this application for shared use.

C. Environmental Feasibility. The proposed shared use of this facility would have a minimal environmental impact. The installation of Dish Wireless LLC equipment at the 136-foot level of the existing 160-foot tower would have an insignificant visual impact on the area around the monopole. Dish Wireless LLC ground equipment would be installed within the existing facility compound. Dish Wireless LLC shared use would therefore not cause any significant alteration in the physical or environmental characteristics of the existing site. Additionally, as evidenced by Exhibit F, the proposed antennas would not increase radio frequency emissions to a level at or above the Federal Communications Commission safety standard.

D. Economic Feasibility. Dish Wireless LLC will be entering into an agreement with the owner of this facility to mutually agreeable terms. As previously mentioned, the Letter of Authorization has been provided by the owner to assist Dish Wireless LLC with this tower share application.

E. Public Safety Concerns. As discussed above, the tower is structurally capable of supporting Dish Wireless LLC proposed loading. Dish Wireless LLC is not aware of any public safety concerns relative to the proposed sharing of the existing tower. Dish Wireless LLC intentions of providing new and improved wireless service through the shared use of this facility is expected to enhance the safety and welfare of local residents and individuals traveling through Orange.

Sincerely,

Victoria Masse
Mobile: 860-306-2326
Fax: 413-521-0558
Office: 420 Main Street, Unit 1 Box 2, Sturbridge, MA 01566
Email: victoria@northeastsitesolutions.com



Attachments

Cc:

James M. Zeoli, First Selectman – property & tower owner
Orange Town Hall
617 Orange Center Road
Orange, CT 06477

Jack Demirjian, Zoning Administrator & Enforcement Officer
Orange Town Hall
617 Orange Center Road
Orange, CT 06477

Exhibit A

Original Facility Approval



CONNECTICUT SITING COUNCIL

[Home](#)[About Us](#)[Pending Matters](#)[Decisions](#)[Forms](#)[Contact Us](#)**Filing Guides**[Meetings & Minutes](#)[Public Participation](#)[Audio Link to New Britain Hearing Rooms](#)[Programs & Services](#)[Telecommunications Database](#)[Publications](#)[Other Resources](#)[Statutes & Regulations](#)[Electric Transmission Upgrade Projects](#)[Frequently Asked Questions](#)

Melanie Bachman,
Executive Director

NOTICE TO USERS

The Connecticut Siting Council posts filed documents to this site as a public service. The Council disclaims any liability for the content of submissions made by parties, intervenors, public officials, and the general public. Further, while the Council seeks to be complete in its postings, the Council urges users of this site to confirm with the submitter the completeness of the postings made. The posting of any document does not constitute or imply endorsement by the Connecticut Siting Council. Finally, the Connecticut Siting Council assumes no responsibility for the use of documents posted on this site.

For further information about the proper use of material posted on this site, please see the State of Connecticut [disclaimer](#).

DOCKET NO. 177A - An amended application of Cellco Partnership d/b/a Bell Atlantic NYNEX Mobile for a Certificate of Environmental Compatibility and Public Need for a two cell-site configuration in the Town of Orange. The proposed Prime A site would be located approximately 875 feet east of Orange Center Road at the rear of the High Plains Community Center, 525 Orange Center Road, with the Prime B site located approximately 400 feet northwest from the end of Ogg Meadow Road. These sites would replace the previously proposed Camp Cedarcrest site. A proposed alternate site is located within a 5.5 acre parcel of property approximately 250 feet south and west of Robert Treat Drive Extension, Orange, Connecticut.

ConnecticutSitingCouncil**August 6, 1997****Decision and Order**

Pursuant to the foregoing Findings of Fact and Opinion, the Connecticut Siting Council (Council) finds that the effects associated with the construction, operation, and maintenance of a two-cell site configuration consisting of a prime A site at the High Plains Community Center property on Orange Center Road and a prime B site on South Central Regional Water Authority (SCRWA) property located off the end of Ogg Meadow Road in Orange, Connecticut, including effects on the natural environment; ecological integrity and balance; public health and safety; scenic, historic, and recreational values; forests and parks; air and water purity; and fish and wildlife are not disproportionate either alone or cumulatively with other effects when compared to need, are not in conflict with the policies of the State concerning such effects, and are not sufficient reason to deny the application and therefore directs that a Certificate of Environmental Compatibility and Public Need, as provided by General Statutes § 16-50k, be issued to Cellco Partnership d/b/a Bell Atlantic NYNEX Mobile (BANM) for the construction, operation, and maintenance of two cellular telecommunications towers and associated equipment. We deny the alternate site on Robert Treat Drive Extension.

The facilities shall be constructed, operated, and maintained substantially as specified in the Council's record in this matter, and subject to the following conditions:

1. The towers shall be constructed as proposed, no taller than necessary to provide the proposed communications service, sufficient to accommodate the antennas of BANM, Springwiche Cellular Limited Partnership (Springwich), Smart SMR of New York, Inc. d/b/a Nextel Communications (Nextel), and Sprint Spectrum L.P. d/b/a Sprint PCS (Sprint). Neither tower, excluding antennas, shall exceed 160 feet above ground level.
2. The Certificate Holder shall prepare Development and Management (D&M) Plans for the prime A and prime B sites in compliance with Sections 16-50j-75 through 16-50j-77 of the Regulations of Connecticut State Agencies. The D&M Plans shall be submitted to and approved by the Council prior to the commencement of facility construction. The prime A D&M plan shall include a tower and foundation plan, signed by a professionally licensed engineer, designed to be safe and adequate to protect the electric supply system, and provisions for landscaping, architectural treatment, and traffic management consistent with terms established with the Town. The prime B D&M plan shall include relocation of the prime B tower within the leased parcel to prevent the fall zone of the tower from crossing paved sections of the Route 15 right-of-way; a tower and foundation plan, signed by a professionally licensed engineer; plans for dewatering the site if necessary; installation of a propane tank to fuel the emergency generator; placement of a counter-sunk and sealed concrete floor for the equipment building; traffic management with schedule to construct during daytime hours; and best management practices for on-site use of construction equipment. In addition, we will require landscaping and the establishment of vegetation to stabilize the site consistent with watershed management plans. Both site plans shall provide specifications for the placement of all antennas to be attached to the towers, and plans for the equipment buildings, foundation pads for Sprint's equipment, security fencing and gate, access roads, utility lines, site clearing, tree trimming, and erosion and sedimentation control consistent with the Connecticut Guidelines for Soil Erosion and Sediment Control, as amended.
3. Consistent with Section 16-50j-77 of the Regulations of Connecticut State Agencies, the Certificate Holder shall provide the Council notification of:
 - a. commencement of construction;
 - b. completion of construction;
 - c. completion of site rehabilitation;
 - d. commencement of operation;
 - e. transfer of ownership of the prime A tower to the Town of Orange; and
 - f. final construction cost.
4. Upon the establishment of any new State or federal radio frequency power density standards applicable to frequencies of this facility, the facility granted herein shall be brought into compliance with such standards.

5. The Certificate Holder shall provide the Council a recalculated report of electromagnetic radio frequency power density if and when circumstances in operation cause a change in power density above the levels originally calculated and provided in the application.
6. The Certificate Holder shall permit public or private entities to share space on the proposed tower for fair consideration, or shall provide any requesting entity with specific legal, technical, environmental, or economic reasons precluding such tower sharing.
7. If the facility does not initially provide, or permanently ceases to provide telecommunications services following completion of construction, this Decision and Order shall be void, and the Certificate Holder shall dismantle the tower and remove all associated equipment or reapplication for any continued or new use shall be made to the Council before any such use is made.
8. Unless otherwise approved by the Council, this Decision and Order shall be void if all construction authorized herein is not completed within three years of the effective date of this Decision and Order or within three years after all appeals to this Decision and Order have been resolved.

Pursuant to General Statutes § 16-50p, we hereby direct that a copy of the Findings of Fact, Opinion, and Decision and Order be served on each person listed below, and notice of issuance shall be published in the New Haven Register.

By this Decision and Order, the Council disposes of the legal rights, duties, and privileges of each party named or admitted to the proceeding in accordance with Section 16-50j-17 of the Regulations of Connecticut State Agencies.

The parties and intervenors to this proceeding are:

APPLICANT

Cellco Partnership d/b/a

ITS REPRESENTATIVE

Kenneth C. Baldwin, Esq.
Brian C. S. Freeman, Esq.
Bell Atlantic NYNEX Mobile
Robinson & Cole
One Commercial Plaza
Hartford, CT 06103-3597

-
Mr. David S. Malko, P.E.
Jennifer Young Gaudet, Mgr. - Regulatory
Bell Atlantic NYNEX Mobile
20 Alexander Drive
Wallingford, CT 06492

PARTY

Residents of Robert Treat Extension,
Elvera Spinaci
Ross Court, and Mapledale Road
829 Robert Treat Extension
Orange, CT 06477

-

INTERVENOR

Eugene Burshuliak
864 Mapledale Road
Orange, CT 06477

-

INTERVENOR

Springwich Cellular Limited Partnership

ITS REPRESENTATIVE

Peter J. Tyrrell, Esq.
Springwich Cellular Limited Partnership
500 Enterprise Drive
Rocky Hill, CT 06067-3900

ITS REPRESENTATIVE

Francis A. Teodosio, Esq.
Orange Town Hall
617 Orange Center Road
Orange, CT 06477

PARTY

Town of Orange

INTERVENOR

Smart SMR of New York, Inc.

ITS REPRESENTATIVE

Christopher B. Fisher, Esq.
d/b/a Nextel Communications Cuddy, Feder & Worby
90 Maple Avenue
White Plains, NY 10601-5196

PARTY

John Rechi
805 Grassy Hill Road
Orange, CT 06477

-

PARTY

Erwin H. Levine
875 Robert Treat Extension

-

Orange, CT 06477

PARTY

Jeffery Friedrichs

248 Ross Court

Orange, CT 06477

PARTY

Orange Land Trust, Inc.

INTERVENOR

Sprint Spectrum L.P.

PARTY

Jay Nastri

820 Ogg Meadow Road

Orange, CT 06477

-

ITS REPRESENTATIVE

Edmund B. Tucker, President

Orange Land Trust, Inc.

433 Pudden Lane

Orange, CT 06477

ITS REPRESENTATIVE

Elias A. Alexiades, Esq.

d/b/a Sprint PCS Andrew C. Kruger, Esq.

Harris, Beach & Wilcox, LLP

147 North Broad Street

Milford, CT 06460

-

-

Content Last Modified on 8/9/2002 12:03:42 PM

Ten Franklin Square New Britain, CT 06051 / 860- 827-2935

[Home](#) | [CT.gov Home](#) | [Send Feedback](#) | [Login](#) | [Register](#)

State of Connecticut [Disclaimer](#), [Privacy Policy](#), and [Web Site Accessibility Policy](#). Copyright © 2002-2019 State of Connecticut.



Exhibit B

Property Card

525 ORANGE CENTER RD

Location 525 ORANGE CENTER RD

Mblu 41/ 5/ 16/ /

Acct# 360800

Owner ORANGE TOWN OF

Assessment \$6,500,400

Appraisal \$9,286,100

PID 2185

Building Count 2

Current Value

Appraisal			
Valuation Year	Improvements	Land	Total
2017	\$4,606,100	\$4,680,000	\$9,286,100
Assessment			
Valuation Year	Improvements	Land	Total
2017	\$3,224,400	\$3,276,000	\$6,500,400

Owner of Record

Owner ORANGE TOWN OF
Co-Owner HIGH PLAINS CENTER
Address 617 ORANGE CENTER RD
 ORANGE, CT 06477

Sale Price \$0
Certificate
Book & Page 284/1100
Sale Date 06/29/1983
Instrument 00

Ownership History

Ownership History					
Owner	Sale Price	Certificate	Book & Page	Instrument	Sale Date
ORANGE TOWN OF	\$0		284/1100	00	06/29/1983

Building Information

Building 1 : Section 1

Year Built: 1955
Living Area: 40,546
**Replacement Cost
Less Depreciation:** \$3,530,000

Building Attributes	
Field	Description
STYLE	School
MODEL	Comm/Ind
Stories	1
Occupancy	1
Exterior Wall 1	Brick/Masonry
Exterior Wall 2	
Roof Structure	Flat Stl Truss
Roof Cover	BU Comp
Interior Wall 1	Paint
Interior Wall 2	
Interior Floor 1	Vinyl

Building Photo



41-5-16 03/06/2017


(<http://images.vgsi.com/photos/OrangeCTPhotos//\00\01\37\87>).

Interior Floor 2	Ceramic Tile
Heating Fuel	Gas
HVAC	Hot Water
Ceilings	Susp Accous
Partitions	Typical
Bldg Use	Exempt Comm
Full Baths	0
Half Baths	0
Total Fixtures	70
% Sprinkler	0
Elevator	0
1st Floor Use	
Basement	Slab
Foundation	Concrete
Park Spaces	150
Frame Type	Fire Resistant
Footprint	
Wall Height	10
Bldg Adj	2.5

Building 2 : Section 1

Year Built: 1975
Living Area: 5,786
Replacement Cost
Less Depreciation: \$576,800

Building Layout



(<http://images.vgsi.com/photos/OrangeCTPhotos//Sketches/2185>)

Building Sub-Areas (sq ft)			<u>Legend</u>
Code	Description	Gross Area	Living Area
BAS	First Floor	40,546	40,546
CAN	Canopy	2,024	0
FEP	Finished Enclosed Porch	162	0
SLB	Slab	41,466	0
		84,198	40,546

Building Attributes : Bldg 2 of 2


Field	Description
STYLE	Gym/Auditorium
MODEL	Comm/Ind
Stories	1
Occupancy	2
Exterior Wall 1	Wood Frame
Exterior Wall 2	
Roof Structure	Arch -Wd Fr
Roof Cover	BU Comp
Interior Wall 1	Paint
Interior Wall 2	Glass
Interior Floor 1	Concrete
Interior Floor 2	Ceramic Tile
Heating Fuel	Gas
HVAC	Force Air Unit
Ceilings	Drywall
Partitions	Typical
Bldg Use	Exempt Comm
Full Baths	0
Half Baths	0
Total Fixtures	20
% Sprinkler	0
Elevator	0
1st Floor Use	

Building Photo



(<http://images.vgsi.com/photos/OrangeCTPhotos//\00\00\83\07>).

Building Layout



(<http://images.vgsi.com/photos/OrangeCTPhotos//Sketches/2185>).

Building Sub-Areas (sq ft)

Legend

Basement	N/A
Foundation	Concrete
Park Spaces	0
Frame Type	Wood Frame
Footprint	
Wall Height	25
Bldg Adj	1

Code	Description	Gross Area	Living Area
BAS	First Floor	3,766	3,766
FUS	Finished Upper Story	2,020	2,020
EPA	Encl Pool Area	8,080	0
SLB	Slab	3,766	0
		17,632	5,786



Extra Features

Extra Features	Legend
No Data for Extra Features	

Land

Land Use		Land Line Valuation	
Use Code	201E	Size (Acres)	28
Description	Exempt Comm	Frontage	
Zone	RES	Depth	
Neighborhood	C20	Assessed Value	\$3,276,000
Alt Land Appr Category	No	Appraised Value	\$4,680,000

Outbuildings

Outbuildings	Legend
--------------	--------


Code	Description	Sub Code	Sub Description	Size	Value	Bldg #
FGR1	Garage			4410 UNITS	\$55,100	1
FN4	8' Chain Link			400 L.F.	\$1,600	2
FOP	Open sided Porch			140 UNITS	\$1,300	1
PAV1	Concrete Paving			85000 UNITS	\$63,800	2
FGR1	Garage			5670 UNITS	\$70,900	1
PAVC	Paving - Concrete			4000 UNITS	\$6,000	2
LT1	Lights			4 UNITS	\$2,500	2
GAZ	Gazebo			1500 UNITS	\$32,400	1
FGR1	Garage			480 UNITS	\$1,900	1
SHD7	Cell Shed			240 UNITS	\$13,500	1
CNP	Canopy			1236 UNITS	\$13,000	1
TEN	Tennis Court			2 UNITS	\$15,000	1
FGR1	Garage			4410 UNITS	\$82,700	1
BTH1	Pool House with Plumbing			1040 UNITS	\$62,400	1
FOP	Open sided Porch			4392 UNITS	\$71,200	1
SHD0	Shed - Metal Utility			480 UNITS	\$2,200	1
FN1	4' Chain Link			1500 L.F.	\$3,800	1

Valuation History

Appraisal			
Valuation Year	Improvements	Land	Total
2017	\$4,606,100	\$4,680,000	\$9,286,100
2016	\$4,606,100	\$5,506,500	\$10,112,600
2015	\$4,606,100	\$5,506,500	\$10,112,600

Assessment			
Valuation Year	Improvements	Land	Total
2017	\$3,224,400	\$3,276,000	\$6,500,400
2016	\$3,224,400	\$3,854,600	\$7,079,000
2015	\$3,224,400	\$3,854,600	\$7,079,000

(c) 2019 Vision Government Solutions, Inc. All rights reserved.



525 Orange Center Road

6/10/2019 6:21:30 PM

Scale: 1"=1000'

Scale is approximate

The information depicted on this map is for planning purposes only.
It is not adequate for legal boundary definition, regulatory
interpretation, or parcel-level analyses.



Exhibit C

Construction Drawings



DISH WIRELESS, LLC. SITE ID:

BOHVN00191A

DISH WIRELESS, LLC. SITE ADDRESS:

**525 ORANGE CENTER ROAD
ORANGE, CT 06477**

CONNECTICUT CODE OF COMPLIANCE

ALL WORK SHALL BE PERFORMED AND MATERIALS INSTALLED IN ACCORDANCE WITH THE CURRENT EDITIONS OF THE FOLLOWING CODES AS ADOPTED BY THE LOCAL GOVERNING AUTHORITIES. NOTHING IN THESE PLANS IS TO BE CONSTRUED TO PERMIT WORK NOT CONFORMING TO THESE CODES:

CODE TYPE	CODE
BUILDING	2021 IBC W/ CT AMENDMENTS
MECHANICAL	2021 IMC W/ CT AMENDMENTS
ELECTRICAL	2020 NEC

SHEET INDEX

SHEET NO.	SHEET TITLE
T-1	TITLE SHEET
LS1	SITE SURVEY
A-1	OVERALL AND ENLARGED SITE PLAN
A-2	ELEVATION, ANTENNA LAYOUT AND SCHEDULE
A-3	EQUIPMENT PLATFORM AND H-FRAME DETAILS
A-4	EQUIPMENT DETAILS
A-5	EQUIPMENT DETAILS
A-6	EQUIPMENT DETAILS
E-1	ELECTRICAL/FIBER ROUTE PLAN AND NOTES
E-2	ELECTRICAL/FIBER DETAILS
E-3	ELECTRICAL ONE-LINE & PANEL SCHEDULE
G-1	GROUNDING PLANS AND NOTES
G-2	GROUNDING DETAILS
G-3	GROUNDING DETAILS
RF-1	RF CABLE COLOR CODE
GN-1	LEGEND AND ABBREVIATIONS
GN-2	RF SIGNAGE
GN-3	GENERAL NOTES
GN-4	GENERAL NOTES
GN-5	GENERAL NOTES

SCOPE OF WORK

THIS IS NOT AN ALL INCLUSIVE LIST. CONTRACTOR SHALL UTILIZE SPECIFIED EQUIPMENT PARTS OR ENGINEER APPROVED EQUIVALENT. CONTRACTOR SHALL VERIFY ALL NEEDED EQUIPMENT TO PROVIDE A FUNCTIONAL SITE. THE PROJECT GENERALLY CONSISTS OF THE FOLLOWING:

- TOWER SCOPE OF WORK:**
- INSTALL (3) PROPOSED PANEL ANTENNAS (1 PER SECTOR)
 - INSTALL (1) PROPOSED PLATFORM
 - INSTALL PROPOSED JUMPERS
 - INSTALL (6) PROPOSED RRUs (2 PER SECTOR)
 - INSTALL (1) PROPOSED OVER VOLTAGE PROTECTION DEVICE (OVP)
 - INSTALL (1) PROPOSED HYBRID CABLE

- GROUND SCOPE OF WORK:**
- INSTALL (1) PROPOSED METAL PLATFORM
 - INSTALL (1) PROPOSED ICE BRIDGE
 - INSTALL (1) PROPOSED PPC CABINET
 - INSTALL (1) PROPOSED EQUIPMENT CABINET
 - INSTALL (1) PROPOSED POWER CONDUIT
 - INSTALL (1) PROPOSED TELCO CONDUIT
 - INSTALL (1) PROPOSED TELCO-FIBER BOX
 - INSTALL (1) PROPOSED GPS UNIT
 - INSTALL (1) PROPOSED SAFETY SWITCH (IF REQUIRED)
 - INSTALL (1) PROPOSED CIENA BOX (IF REQUIRED)
 - INSTALL (1) PROPOSED METER SOCKET
 - INSTALL (1) PROPOSED H-FRAME

SITE PHOTO



UNDERGROUND SERVICE ALERT CBYD 811
UTILITY NOTIFICATION CENTER OF CONNECTICUT
(800) 922-4455
WWW.CBYD.COM

CALL 2 WORKING DAYS UTILITY NOTIFICATION PRIOR TO CONSTRUCTION



GENERAL NOTES

THE FACILITY IS UNMANNED AND NOT FOR HUMAN HABITATION. A TECHNICIAN WILL VISIT THE SITE AS REQUIRED FOR ROUTINE MAINTENANCE. THE PROJECT WILL NOT RESULT IN ANY SIGNIFICANT DISTURBANCE OR EFFECT ON DRAINAGE. NO SANITARY SEWER SERVICE, POTABLE WATER, OR TRASH DISPOSAL IS REQUIRED AND NO COMMERCIAL SIGNAGE IS PROPOSED.

11"x17" PLOT WILL BE HALF SCALE UNLESS OTHERWISE NOTED

CONTRACTOR SHALL VERIFY ALL PLANS, EXISTING DIMENSIONS, AND CONDITIONS ON THE JOB SITE, AND SHALL IMMEDIATELY NOTIFY THE ENGINEER IN WRITING OF ANY DISCREPANCIES BEFORE PROCEEDING WITH THE WORK.

SITE INFORMATION

PROPERTY OWNER: TOWN OF ORANGE
ADDRESS: 617 ORANGE CENTER ROAD
ORANGE, CT 06477

TOWER TYPE: MONOPOLE

TOWER CO SITE ID: US-CT-5015

TOWER APP NUMBER: TBD

COUNTY: NEW HAVEN

LATITUDE (NAD 83): 41°16'25.32" N
41.273700 N

LONGITUDE (NAD 83): 73°01'07.78" W
-73.018828 W

ZONING JURISDICTION: CONNECTICUT SITING COUNCIL

ZONING DISTRICT: RES

PARCEL NUMBER: 41-5-16

OCCUPANCY GROUP: U

CONSTRUCTION TYPE: V-B

POWER COMPANY: UNITED ILLUMINATING CO

TELEPHONE COMPANY: AT&T

PROJECT DIRECTORY

APPLICANT: DISH WIRELESS, LLC.
5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120

TOWER OWNER: TOWN OF ORANGE
617 ORANGE CENTER ROAD
ORANGE, CT 06477
(203) 891-4700

SITE DESIGNER: INFINIGY
500 WEST OFFICE CENTER DR, STE 150
FORT WASHINGTON, PA 19034
(678) 444-4463

SITE ACQUISITION: JEANNE COTTRELL
(203) 927-4317


CONSTRUCTION MANAGER: CHAD WILCOX
CHAD.WILCOX@DISH.COM

RF ENGINEER: DIPESH PARIKH
DIPESH.PARIKH@DISH.COM

DIRECTIONS

DEPART HIGHWAY I-95 ON EXIT 39B ONTO BOSTON POST ROAD FOR 2.3 MI. TURN LEFT (NORTH) ONTO SR-152 [ORANGE CENTER RD] FOR 1.1 MI. ARRIVE 525 ORANGE CENTER RD, ORANGE, CT 06477.

VICINITY MAP




5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



INFINIGY
FROM ZERO TO INFINIGY

500 W. OFFICE CENTER DR. SUITE 150 |
FORT WASHINGTON, PA 19034



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
RCD	SS	CJW

RFDS REV #: N/A

PRELIMINARY DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	09/03/2021	ISSUED FOR REVIEW
B	12/14/2022	ISSUED FOR REVIEW
O	01/25/2023	ISSUED FOR CONSTRUCTION


A&E PROJECT NUMBER
1197-C0001C

DISH WIRELESS, LLC.
PROJECT INFORMATION
BOHVN00191A
525 ORANGE CENTER ROAD
ORANGE, CT 06477


SHEET TITLE
TITLE SHEET

SHEET NUMBER
T-1


1. CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS.
2. ANTENNAS AND MOUNTS OMITTED FOR CLARITY.




COMPOUND PLAN




1. CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS.
2. CONTRACTOR SHALL MAINTAIN A 10'-0" MINIMUM SEPARATION BETWEEN THE PROPOSED GPS UNIT, TRANSMITTING ANTENNAS AND EXISTING GPS UNITS.
3. ANTENNAS AND MOUNTS OMITTED FOR CLARITY.



ENLARGED SITE PLAN



SITE PLAN




5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



INFINIGY
FROM ZERO TO INFINIGY

500 W. OFFICE CENTER DR. SUITE 150 |
FORT WASHINGTON, PA 19034



IT IS A VIOLATION OF LAW FOR ANY PERSON,
UNLESS THEY ARE ACTING UNDER THE DIRECTION
OF A LICENSED PROFESSIONAL ENGINEER,
TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
-----------	-------------	--------------

RCD	SS	CJW
-----	----	-----

RFDS REV #: N/A

PRELIMINARY
DOCUMENTS

SUBMITTALS

REV	DATE	DESCRIPTION
A	09/03/2021	ISSUED FOR REVIEW
B	12/14/2022	ISSUED FOR REVIEW
0	01/25/2023	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER

1197-C0001C

DISH WIRELESS, LLC.
PROJECT INFORMATION

BOHVN00191A
525 ORANGE CENTER ROAD
ORANGE, CT 06477

SHEET TITLE
OVERALL AND ENLARGED
SITE PLAN

SHEET NUMBER

A-1


- NOTES
1. CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS.

2. ANTENNA AND MW DISH SPECIFICATIONS REFER TO ANTENNA SCHEDULE AND TO FINAL CONSTRUCTION RFDS FOR ALL RF DETAILS



3. EXISTING EQUIPMENT AND FENCE OMITTED FOR CLARITY.

4. MOUNT ANALYSIS COMPLETED BY INFINIGY DATED 12/08/2022.


5. STRUCTURAL ANALYSIS COMPLETED BY INFINIGY DATED 12/29/2022.



PROPOSED NORTHWEST ELEVATION



ANTENNA LAYOUT



SECTOR	POSITION	ANTENNA						TRANSMISSION CABLE
		EXISTING OR PROPOSED	MANUFACTURER – MODEL NUMBER	TECHNOLOGY	SIZE (HxW)	AZMUTH	RAD CENTER	FEED LINE TYPE AND LENGTH
ALPHA	A2	PROPOSED	JMA WIRELESS – MX08FR0665-21	5G	72.0" x 20.0"	0°	136'-0"	(1) HIGH-CAPACITY HYBRID CABLE (180' LONG)
BETA	B2	PROPOSED	JMA WIRELESS – MX08FR0665-21	5G	72.0" x 20.0"	120°	136'-0"	
GAMMA	C2	PROPOSED	JMA WIRELESS – MX08FR0665-21	5G	72.0" x 20.0"	240°	136'-0"	
NOTES								
1. CONTRACTOR TO REFER TO FINAL CONSTRUCTION RFDS FOR ALL RF DETAILS.								
2. ANTENNA OR RRH MODELS MAY CHANGE DUE TO EQUIPMENT AVAILABILITY. ALL EQUIPMENT CHANGES MUST BE APPROVED AND REMAIN IN COMPLIANCE WITH THE PROPOSED DESIGN AND STRUCTURAL ANALYSES.								
SECTOR	POSITION	RRH		NOTES				
		MANUFACTURER – MODEL NUMBER	TECHNOLOGY					
ALPHA	A2	FUJITSU – TA08025-B604	5G	1. CONTRACTOR TO REFER TO FINAL CONSTRUCTION RFDS FOR ALL RF DETAILS. 2. ANTENNA AND RRH MODELS MAY CHANGE DUE TO EQUIPMENT AVAILABILITY. ALL EQUIPMENT CHANGES MUST BE APPROVED AND REMAIN IN COMPLIANCE WITH THE PROPOSED DESIGN AND STRUCTURAL ANALYSES.				
	A2	FUJITSU – TA08025-B605	5G					
BETA	B2	FUJITSU – TA08025-B604	5G					
	B2	FUJITSU – TA08025-B605	5G					
GAMMA	C2	FUJITSU – TA08025-B604	5G					
	C2	FUJITSU – TA08025-B605	5G					

ANTENNA SCHEDULE

dish
wireless.

5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120

NORTHEAST
SITE SOLUTIONS
Turkey Wireless Development
certified
WBENC
MEMBER SINCE 2016

INFINIGY
FROM ZERO TO INFINIGY
500 W. OFFICE CENTER DR. SUITE 150 |
FORT WASHINGTON, PA 19034

STATE OF CONNECTICUT
CHRISTOPHER J. WARREN
No. 23544
1/31/23
LICENSED
PROFESSIONAL ENGINEER

IT IS A VIOLATION OF LAW FOR ANY PERSON,
UNLESS THEY ARE ACTING UNDER THE DIRECTION
OF A LICENSED PROFESSIONAL ENGINEER,
TO ALTER THIS DOCUMENT.

DRAWN BY: CHECKED BY: APPROVED BY:
RCD SS CJW

RFDS REV #: N/A

PRELIMINARY
DOCUMENTS

SUBMITTALS


REV	DATE	DESCRIPTION
A	09/03/2021	ISSUED FOR REVIEW
B	12/14/2022	ISSUED FOR REVIEW
O	01/25/2023	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
1197-C0001C

DISH WIRELESS, LLC.
PROJECT INFORMATION
BOHVN00191A
525 ORANGE CENTER ROAD
ORANGE, CT 06477

SHEET TITLE
ELEVATION, ANTENNA
LAYOUT AND SCHEDULE


SHEET NUMBER
A-2



PLATFORM EQUIPMENT PLAN

12" 9" 6" 3" 0" 1' 2' 1"=1'-0"


COMMSCOPE MTC4045LP 5X7 PLATFORM	
DIMENSIONS (HxWxD)	16"x84"x60"
TOTAL WEIGHT	423 LBS



PLATFORM DETAIL

NO SCALE 2

KENWOOD T1701KT5-5S H-FRAME	
UNISTRUT/SUPPORT RAIL	5
WEIGHT/ VOLUME	173.6 LBS




H-FRAME DETAIL


NO SCALE 3

NOT USED

NO SCALE 4



FRONT ELEVATION



BACK ELEVATION

H-FRAME EQUIPMENT ELEVATION

12" 9" 6" 3" 0" 1' 2' 1"=1'-0"

5

NOTES

1. CONTRACTOR TO BURY PLATFORM FEET WITH A MINIMUM OF 2" OF FILL PER EXISTING SITE SURFACE
2. WEED BARRIER FABRIC TO BE ADDED AT DISCRETION OF DISH WIRELESS, LLC. CONSTRUCTION MANAGER AT TIME OF CONSTRUCTION. ONE SHEET 8'x8' INSTALLED UNDER ALL FOUR FEET OF THE PLATFORM (4 MIL BLACK PLASTIC)
3. EQUIPMENT CABINET OMITTED FOR CLARITY




5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



INFINIGY
FROM ZERO TO INFINIGY

500 W. OFFICE CENTER DR. SUITE 150 |
FORT WASHINGTON, PA 19034



IT IS A VIOLATION OF LAW FOR ANY PERSON,
UNLESS THEY ARE ACTING UNDER THE DIRECTION
OF A LICENSED PROFESSIONAL ENGINEER,
TO ALTER THIS DOCUMENT.

DRAWN BY: CHECKED BY: APPROVED BY:
RCD SS CJW

RFDS REV #: N/A

PRELIMINARY
DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	09/03/2021	ISSUED FOR REVIEW
B	12/14/2022	ISSUED FOR REVIEW
O	01/25/2023	ISSUED FOR CONSTRUCTION


A&E PROJECT NUMBER
1197-C0001C

DISH WIRELESS, LLC.
PROJECT INFORMATION
BOHVN00191A
525 ORANGE CENTER ROAD
ORANGE, CT 06477

SHEET TITLE
EQUIPMENT PLATFORM AND
H-FRAME DETAILS

SHEET NUMBER


A-3



CABINET DETAIL

NO SCALE


1



POWER PROTECTION CABINET (PPC) DETAIL

NO SCALE

2



SAFETY SWITCH DETAIL


NO SCALE

3



NO SCALE


4



NETWORK INTERFACE UNIT DETAIL

NO SCALE


5



FIBER TELCO ENCLOSURE DETAIL

NO SCALE


6



ICE BRIDGE DETAIL

NO SCALE


7



TYPICAL ICE BRIDGE CONCRETE PIER DETAIL

NO SCALE

8



HYBRID CABLE RUN

NO SCALE

9

5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120

certified WBENC

FROM ZERO TO INFINIGY

500 W. OFFICE CENTER DR. SUITE 150 |
FORT WASHINGTON, PA 19034

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
RCD	SS	CJW

RFDS REV #: N/A

PRELIMINARY DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	08/03/2021	ISSUED FOR REVIEW
B	12/14/2022	ISSUED FOR REVIEW
0	01/25/2023	ISSUED FOR CONSTRUCTION





A&E PROJECT NUMBER
1197-C0001C

DISH WIRELESS, LLC.
PROJECT INFORMATION
BOHVN00191A
525 ORANGE CENTER ROAD
ORANGE, CT 06477

SHEET TITLE
EQUIPMENT DETAILS

SHEET NUMBER
A-4

ROSENBERGER GPSGLONASS-36-N-S	
DIMENSION (DIA x H)	69mm x 98.5mm
WEIGHT (WITH ACCESSORIES)	515.74g
CONNECTOR	N-FEMALE
FREQUENCY RANGE	1559 MHz ~ 1610.5MHz



GPS ANTENNA DETAIL

NO SCALE 1

GPS MINIMUM SKY VIEW REQUIREMENTS

NO SCALE 2

CABLES UNLIMITED HYBRID CABLE
MINIMUM BEND RADIUSES

NO SCALE 3

NOT USED

NO SCALE 4

NOT USED

NO SCALE 5

NOT USED

NO SCALE 6

NOT USED

NO SCALE 7

NOT USED

NO SCALE 8

NOT USED

NO SCALE 9




5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



INFINIGY
FROM ZERO TO INFINIGY

500 W. OFFICE CENTER DR. SUITE 150 |
FORT WASHINGTON, PA 19034



IT IS A VIOLATION OF LAW FOR ANY PERSON,
UNLESS THEY ARE ACTING UNDER THE DIRECTION
OF A LICENSED PROFESSIONAL ENGINEER,
TO ALTER THIS DOCUMENT.

DRAWN BY: RCD CHECKED BY: SS APPROVED BY: CJW

RFDS REV #: N/A

PRELIMINARY DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	08/03/2021	ISSUED FOR REVIEW
B	12/14/2022	ISSUED FOR REVIEW
O	01/25/2023	ISSUED FOR CONSTRUCTION


A&E PROJECT NUMBER
1197-C0001C

DISH WIRELESS, LLC.
PROJECT INFORMATION
BOHVN00191A
525 ORANGE CENTER ROAD
ORANGE, CT 06477


SHEET TITLE
EQUIPMENT DETAILS

SHEET NUMBER
A-5


FUJITSU TA08025-B604 RRH	
DIMENSIONS (HxWxD) (KG/IN)	380x400x200/14.9"x15.7"x7.8"
WEIGHT(KG,LB)/ VOLUME	29kg,63.9lb/ 30L
POWER SUPPLY	DC-58~36V



PLAN



SIDE



FRONT

NOTES


FINAL RRH SPECIFICATIONS
TO BE CONFIRMED BY GC

REMOTE RADIO HEAD DETAIL


NO SCALE

1


FUJITSU TA08025-B605 RRH	
DIMENSIONS (HxWxD) (KG/IN)	380x400x230/14.9"x15.7"x9.0"
WEIGHT(KG,LB)/ VOLUME	34kg,74.9lb/ 35L
POWER SUPPLY	DC-58~36V



PLAN



SIDE



FRONT

NOTES

FINAL RRH SPECIFICATIONS
TO BE CONFIRMED BY GC


REMOTE RADIO HEAD DETAIL

NO SCALE

2


SABRE INDUSTRIES RRU BRACKET MOUNT C10123155	
DIMENSIONS (HxWxD) (1 BRACKET)	5"x20"x1-13/16"
WEIGHT (FULL ASSEMBLY)	35.79 lbs
PACKAGE QUANTITY	4

ITEM#	DESCRIPTION
1	PLATE, CHANNEL BRACKET
2	RRH Z BRACKET, 3/16"
3	THREADED ROD ASSEMBLY 1/2"x12"



11MM x 30MM SLOTS
40MM ON CENTER

11MM x 24MM SLOTS




REMOTE RADIO MOUNT DETAIL

NO SCALE


3

RAYCAP RDIDC-9181-PF-48
DC SURGE PROTECTION


DIMENSIONS (HxWxD)	18.98"x14.39"x8.15"
WEIGHT	21.82 LBS




PLAN



SIDE



BACK



FRONT


SURGE SUPPRESSION DETAIL

NO SCALE

4

JMA WIRELESS
MX08FR0665-21 ANTENNA

DIMENSIONS (HxWxD)	72.0"x20.0"x8.0"
TOTAL WEIGHT	64.5 LB
RF PORTS, CONNECTOR TYPE	8 x 4.3-10 FEMALE




PLAN



BACK



SIDE



FRONT

NOTES

FINAL ANTENNA SPECIFICATIONS
TO BE CONFIRMED BY GC


ANTENNA DETAIL

NO SCALE

5

JMA 91900318 MOUNTING BRACKET

WIDTH	8.3" (211mm)
DEPTH	7.5" (191mm)
HEIGHT	11.2" (284mm)
TOTAL WEIGHT (WITH BRACKETS)	18.5 LBS (8.4 Kg)
HOUSING MATERIAL	GALV. HIGH STRENGTH STEEL




ANTENNA MOUNTING DETAIL

NO SCALE

6

COMMSCOPE XP-2040
CROSSOVER PLATE

DIMENSIONS (HxW)	10"x12"
WEIGHT	11.023 LBS




RRH/OVP MOUNT DETAIL

NO SCALE

7

SITEPRO1 SNP8HR-396
SNUB-NOSE PLATFORM

FACE SIZE	8'-0"
WEIGHT	1786.28 LB
ANTENNA PIPE MOUNTS	(6) 2-3/8" O.D.



ANTENNA PLATFORM DETAIL

NO SCALE

8

NOT USED

NO SCALE

9


dish
wireless.

5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



INFINIGY
FROM ZERO TO INFINIGY

500 W. OFFICE CENTER DR. SUITE 150 |
FORT WASHINGTON, PA 19034



IT IS A VIOLATION OF LAW FOR ANY PERSON,
UNLESS THEY ARE ACTING UNDER THE DIRECTION
OF A LICENSED PROFESSIONAL ENGINEER,
TO ALTER THIS DOCUMENT.

DRAWN BY: CHECKED BY: APPROVED BY:

RCD SS CJW

RFDS REV #: N/A

PRELIMINARY
DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	09/03/2021	ISSUED FOR REVIEW
B	12/14/2022	ISSUED FOR REVIEW
O	01/25/2023	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER

1197-C0001C


DISH WIRELESS, LLC.
PROJECT INFORMATION

BOHVN00191A
525 ORANGE CENTER ROAD
ORANGE, CT 06477


SHEET TITLE
EQUIPMENT DETAILS

SHEET NUMBER

A-6



UTILITY ROUTE PLAN




NOTES

1. CONTRACTOR SHALL FIELD VERIFY ALL PROPOSED UNDERGROUND UTILITY CONDUIT ROUTE.
2. ANTENNAS AND MOUNTS OMITTED FOR CLARITY.


DC POWER WIRING SHALL BE COLOR CODED AT EACH END FOR IDENTIFYING +24V AND -48V CONDUCTORS. RED MARKINGS SHALL IDENTIFY +24V AND BLUE MARKINGS SHALL IDENTIFY -48V.

1. CONTRACTOR SHALL INSPECT THE EXISTING CONDITIONS PRIOR TO SUBMITTING A BID. ANY QUESTIONS ARISING DURING THE BID PERIOD IN REGARDS TO THE CONTRACTOR'S FUNCTIONS, THE SCOPE OF WORK, OR ANY OTHER ISSUE RELATED TO THIS PROJECT SHALL BE BROUGHT UP DURING THE BID PERIOD WITH THE PROJECT MANAGER FOR CLARIFICATION, NOT AFTER THE CONTRACT HAS BEEN AWARDED.
2. ALL ELECTRICAL WORK SHALL BE DONE IN ACCORDANCE WITH CURRENT NATIONAL ELECTRICAL CODES AND ALL STATE AND LOCAL CODES, LAWS, AND ORDINANCES. PROVIDE ALL COMPONENTS AND WIRING SIZES AS REQUIRED TO MEET NEC STANDARDS.
3. LOCATION OF EQUIPMENT, CONDUIT AND DEVICES SHOWN ON THE DRAWINGS ARE APPROXIMATE AND SHALL BE COORDINATED WITH FIELD CONDITIONS PRIOR TO CONSTRUCTION.
4. CONDUIT ROUGH-IN SHALL BE COORDINATED WITH THE MECHANICAL EQUIPMENT TO AVOID LOCATION CONFLICTS. VERIFY WITH THE MECHANICAL EQUIPMENT CONTRACTOR AND COMPLY AS REQUIRED.
5. CONTRACTOR SHALL PROVIDE ALL BREAKERS, CONDUITS AND CIRCUITS AS REQUIRED FOR A COMPLETE SYSTEM.
6. CONTRACTOR SHALL PROVIDE PULL BOXES AND JUNCTION BOXES AS REQUIRED BY THE NEC ARTICLE 314.
7. CONTRACTOR SHALL PROVIDE ALL STRAIN RELIEF AND CABLE SUPPORTS FOR ALL CABLE ASSEMBLIES. INSTALLATION SHALL BE IN ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS AND RECOMMENDATIONS.
8. ALL DISCONNECTS AND CONTROLLING DEVICES SHALL BE PROVIDED WITH ENGRAVED PHENOLIC NAMEPLATES INDICATING EQUIPMENT CONTROLLED, BRANCH CIRCUITS INSTALLED ON, AND PANEL FIELD LOCATIONS FED FROM.
9. INSTALL AN EQUIPMENT GROUNDING CONDUCTOR IN ALL CONDUITS PER THE SPECIFICATIONS AND NEC 250. THE EQUIPMENT GROUNDING CONDUCTORS SHALL BE BONDED AT ALL JUNCTION BOXES, PULL BOXES, AND ALL DISCONNECT SWITCHES, AND EQUIPMENT CABINETS.
10. ALL NEW MATERIAL SHALL HAVE A U.L. LABEL.
11. PANEL SCHEDULE LOADING AND CIRCUIT ARRANGEMENTS REFLECT POST-CONSTRUCTION EQUIPMENT.
12. CONTRACTOR SHALL BE RESPONSIBLE FOR AS-BUILT PANEL SCHEDULE AND SITE DRAWINGS.
13. FIBER ROUTE IS PRELIMINARY, FINAL FIBER ROUTE TO BE DETERMINED ONCE UCR (UTILITY COORDINATION REPORT) HAS BEEN FINALIZED.

ELECTRICAL NOTES



OVERALL UTILITY ROUTE PLAN




5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



INFINIGY
FROM ZERO TO INFINIGY

500 W. OFFICE CENTER DR. SUITE 150 |
FORT WASHINGTON, PA 19034



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY: CHECKED BY: APPROVED BY:
RCD SS CJW

RFDS REV #: N/A

PRELIMINARY DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	09/03/2021	ISSUED FOR REVIEW
B	12/14/2022	ISSUED FOR REVIEW
O	01/25/2023	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER

1197-C0001C

DISH WIRELESS, LLC.
PROJECT INFORMATION

BOHVN00191A
525 ORANGE CENTER ROAD
ORANGE, CT 06477

SHEET TITLE
ELECTRICAL/FIBER ROUTE
PLAN AND NOTES

SHEET NUMBER

E-1

CARLON EXPANSION FITTINGS

COUPLING END PART#	MALE TERMINAL ADAPTER END PART#	SIZE	STD CTN QTY.	TRAVEL LENGTH
E945D	E945DX	1/2"	20	4"
E945E	E945EX	3/4"	15	4"
E945F	E945FX	1"	10	4"
E945G	E945GX	1 1/4"	5	4"
E945H	E945HX	1 1/2"	5	4"
E945J	E945JX	2"	15	8"
E945K	E945KX	2 1/2"	10	8"
E945L	E945LX	3"	10	8"
E945M	E945MX	3 1/2"	5	8"
E945N	E945NX	4"	5	8"
E945P	E945PX	5"	1	8"
E945R	E945RX	6"	1	8"

VARIES PER PART NUMBER

2'-0"

SLIP JOINT (SEE CHART FOR PART NUMBER)

NOTE: CONTRACTOR TO INSTALL EXPANSION FITTING SLIP JOINT AT METER CENTER CONDUIT TERMINATION, AS PER LOCAL UTILITY POLICY, ORDINANCE AND/OR SPECIFIED REQUIREMENT.

TRENCHING NOTES

1. CONTRACTOR SHALL RESTORE THE TRENCH TO ITS ORIGINAL CONDITIONS BY EITHER SEEDING OR SODDING GRASS AREAS, OR REPLACING ASPHALT OR CONCRETE AREAS TO ITS ORIGINAL CROSS SECTION.

2. TRENCHING SAFETY; INCLUDING, BUT NOT LIMITED TO SOIL CLASSIFICATION, SLOPING, AND SHORING, SHALL BE GOVERNED BY THE CURRENT OSHA TRENCHING AND EXCAVATION SAFETY STANDARDS.

3. ALL CONDUITS SHALL BE INSTALLED IN COMPLIANCE WITH THE CURRENT NATIONAL ELECTRIC CODE (NEC) OR AS REQUIRED BY THE LOCAL JURISDICTION, WHICHEVER IS THE MOST STRINGENT.

SEE TRENCHING NOTE 1

BACKFILL PER SITE WORK SPECIFICATIONS (SEE GENERAL NOTES)

SLOPE TO SUIT SOIL CONDITION IN ACCORDANCE WITH LOCAL REGULATIONS SEE TRENCHING NOTE 2

30" OR 6" BELOW FROST LINE, WHICHEVER IS GREATER

UTILITY WARNING TAPE

SAND BEDDING PER SITE WORK SPECIFICATIONS

VERTICAL DEPTH SEE TRENCHING NOTE 2

1'-0"

DARK TELCO BOX – INTERIOR WIRING LAYOUT

DISH WIRELESS, LLC. PROVIDES 12AWG WIRE (6' TAIL)

PROPOSED DISH WIRELESS, LLC. UNISTRUT

PROPOSED DISH WIRELESS, LLC. 10 AMP DISTRIBUTION BREAKER

PROPOSED DISH WIRELESS, LLC. 12 AWG WIRE

PROPOSED DISH WIRELESS, LLC. 1-1/2" POWER FROM CABINET

DISH WIRELESS, LLC. INSTALLS 1-1/2" CONDUITS FOR POWER AND FIBER TO CABINET

DISH WIRELESS, LLC. FIBER DISTRIBUTION PANEL

PROPOSED DISH WIRELESS, LLC. TELCO FIBER ENCLOSURE

DISH WIRELESS, LLC. FIBER JUMPER TO CABINET WILL NEED TO BE TERMINATED BY FIBER PROVIDER ON OTHER SIDE OF BULKHEAD/LC TO LC CONNECTOR WHERE CIRCUIT IS TERMINATED.

PROPOSED FIBER PROVIDER FIBER LATERAL FROM RIGHT OF WAY TO STREET, TERMINATED TO FDP

PROPOSED DISH WIRELESS, LLC. 1-1/2" FIBER TO CABINET

PROPOSED DISH WIRELESS, LLC. 2" CONDUIT FROM COMMERCIAL FIBER VAULT

LIT TELCO BOX – INTERIOR WIRING LAYOUT (OPTIONAL)

PROPOSED DISH WIRELESS, LLC. UNISTRUT

PROPOSED FIBER PROVIDER 1-1/4" FLEX CONDUITS

FIBER PROVIDER TO TERMINATE POWER TO FIBER PROVIDER NID

PROPOSED DISH WIRELESS, LLC. 12 AWG WIRE (6' TAIL)

PROPOSED DISH WIRELESS, LLC. 10 AMP DISTRIBUTION BREAKER

PROPOSED DISH WIRELESS, LLC. 12 AWG WIRE

PROPOSED DISH WIRELESS, LLC. 1-1/2" POWER FROM CABINET

NOTE: FIBER PROVIDER WILL NEED TO PROVIDE AN ADDITIONAL 5FT UNISTRUT, 2 U-BOLTS WITH 4 NUTS, IN THE EVENT THE BRACKET SPACING DOESN'T LINE UP WITH CURRENT SPACING BELOW

FIBER PROVIDER TO PUNCH TOP OF TELCO BOX OF NID ENCLOSURE AND INSTALL 1-1/4" LIQUID TIGHT CONNECTORS, UL LISTED, NYLON MATERIAL, WITH O-RING GASKET

FIBER PROVIDER TO INSTALL 1-1/4" FLEX CONDUITS BETWEEN FDP TELCO BOX & NID

PROPOSED DISH WIRELESS, LLC. TELCO FIBER ENCLOSURE

PROPOSED DISH WIRELESS, LLC. 1-1/2" FIBER TO CABINET

PROPOSED DISH WIRELESS, LLC. 2" CONDUIT FROM COMMERCIAL FIBER VAULT

NOT USED

NO SCALE

7

NOT USED

NO SCALE

8

NOT USED

NO SCALE

9

EXPANSION JOINT DETAIL

NO SCALE

1

TYPICAL UNDERGROUND TRENCH DETAIL

NO SCALE

2

DARK TELCO BOX – INTERIOR WIRING LAYOUT

NO SCALE

3

LIT TELCO BOX – INTERIOR WIRING LAYOUT (OPTIONAL)

NO SCALE

4

NOT USED

NO SCALE

5

NOT USED

NO SCALE

6

NOT USED

NO SCALE

7

NOT USED

NO SCALE

8

NOT USED

NO SCALE

9

dish wireless.

5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120

NORTHEAST SITE SOLUTIONS

Turnkey Wireless Development

certified WBENC

MEMBER OF THE NATIONAL WIRELESS

INFINIGY

FROM ZERO TO INFINIGY

500 W. OFFICE CENTER DR. SUITE 150 |
FORT WASHINGTON, PA 19034

STATE OF CONNECTICUT

CHRISTOPHER J. WARREN

No. 23544

1/31/23

PROFESSIONAL ENGINEER

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY: RCD

CHECKED BY: SS

APPROVED BY: CJW

RFDS REV #: N/A

PRELIMINARY DOCUMENTS

SUBMITTALS



REV	DATE	DESCRIPTION
A	09/03/2021	ISSUED FOR REVIEW
B	12/14/2022	ISSUED FOR REVIEW
O	01/25/2023	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
1197-C0001C

DISH WIRELESS, LLC.
PROJECT INFORMATION
BOHVN00191A
525 ORANGE CENTER ROAD
ORANGE, CT 06477

SHEET TITLE
ELECTRICAL/FIBER
DETAILS

SHEET NUMBER
E-2



NOTE:
BRANCH CIRCUIT WIRING SUPPLYING RECTIFIERS ARE TO BE RATED UL1015, 105°C, 600V, AND PVC INSULATED, IN THE SIZES SHOWN IN THE ONE-LINE DIAGRAM. CONTRACTOR MAY SUBSTITUTE UL1015 WIRE FOR THWN-2 FOR CONVENIENCE OUTLET BRANCH CIRCUIT.

BREAKERS REQUIRED: (OR EQUIVALENT MANUFACTURER)
(4) 30A, 2P BREAKER - SQUARE D P/N:Q0230
(1) 15A, 1P BREAKER - SQUARE D P/N:Q0115
(1) 20A, 1P BREAKER - SQUARE D P/N:Q0120

NOTES

THE ENGINEER OF RECORD HAS PERFORMED ALL REQUIRED SHORT CIRCUIT CALCULATIONS AND THE AIC RATINGS FOR EACH DEVICE IS ADEQUATE TO PROTECT THE EQUIPMENT AND THE ELECTRICAL SYSTEM.

THE ENGINEER OF RECORD HAS PERFORMED ALL REQUIRED VOLTAGE DROP CALCULATIONS AND ALL BRANCH CIRCUIT AND FEEDERS COMPLY WITH THE NEC (LISTED ON T-1) ARTICLE 210.19(A)(1) FPN NO. 4.

THE (2) CONDUITS WITH (4) CURRENT CARRYING CONDUCTORS EACH, SHALL APPLY THE ADJUSTMENT FACTOR OF 80% PER 2014/17 NEC TABLE 310.15(B)(3)(a) OR 2020 NEC TABLE 310.15(C)(1) FOR UL1015 WIRE.

#12 FOR 15A-20A/1P BREAKER: 0.8 x 30A = 24.0A
#10 FOR 25A-30A/2P BREAKER: 0.8 x 40A = 32.0A
#8 FOR 35A-40A/2P BREAKER: 0.8 x 55A = 44.0A
#6 FOR 45A-60A/2P BREAKER: 0.8 x 75A = 60.0A

CONDUIT SIZING: AT 40% FILL PER NEC CHAPTER 9, TABLE 4, ARTICLE 358.
0.5" CONDUIT - 0.122 SQ. IN AREA
0.75" CONDUIT - 0.213 SQ. IN AREA
2.0" CONDUIT - 1.316 SQ. IN AREA
3.0" CONDUIT - 2.907 SQ. IN AREA

CABINET CONVENIENCE OUTLET CONDUCTORS (1 CONDUIT): USING THWN-2, CU.

#10 - 0.0211 SQ. IN X 2 = 0.0422 SQ. IN
#10 - 0.0211 SQ. IN X 1 = 0.0211 SQ. IN <GROUND
TOTAL = 0.0633 SQ. IN

0.5" EMT CONDUIT IS ADEQUATE TO HANDLE THE TOTAL OF (3) WIRES, INCLUDING GROUND WIRE, AS INDICATED ABOVE.

RECTIFIER CONDUCTORS (2 CONDUITS): USING UL1015, CU.

#10 - 0.0266 SQ. IN X 4 = 0.1064 SQ. IN
#10 - 0.0082 SQ. IN X 1 = 0.0082 SQ. IN <BARE GROUND
TOTAL = 0.1146 SQ. IN

0.75" EMT CONDUIT IS ADEQUATE TO HANDLE THE TOTAL OF (5) WIRES, INCLUDING GROUND WIRE, AS INDICATED ABOVE.

PPC FEED CONDUCTORS (1 CONDUIT): USING THWN, CU.

3/0 - 0.2679 SQ. IN X 3 = 0.8037 SQ. IN
#6 - 0.0507 SQ. IN X 1 = 0.0507 SQ. IN <GROUND
TOTAL = 0.8544 SQ. IN

3.0" SCH 40 PVC CONDUIT IS ADEQUATE TO HANDLE THE TOTAL OF (4) WIRES, INCLUDING GROUND WIRE, AS INDICATED ABOVE.

1 OPTIONAL ALUMINUM SERVICE CONDUCTOR:
• 4/0 AL + #2 GRD MAY BE USED INSTEAD OF 3/0 CU + #6 GRD IF THE TOTAL LENGTH OF THE CONDUCTOR IS LESS THAN 300 FT FROM THE TRANSFORMER.
• ALUMINUM CONDUCTORS MUST BE 90°C TO CARRY THE FULL 200A LOAD REQUIRED
• ALUMINUM TO COPPER BUSS CONNECTIONS MUST MEET AND CONFORM TO ANSI AND BE UL LISTED. USE ANTI CORROSION CONDUCTIVE LUBRICANT ON CONNECTIONS

PPC ONE-LINE DIAGRAM

NO SCALE 1

PROPOSED CHARLES PANEL SCHEDULE GE ABB INFINITY DC PLANT										
LOAD SERVED	VOLT AMPS (WATTS)		TRIP	CKT #	PHASE	CKT #	TRIP	VOLT AMPS (WATTS)		LOAD SERVED
	L1	L2						L1	L2	
PPC GFCI OUTLET	180		15A	1	A	2	30A	2880	2880	ABB/GE INFINITY RECTIFIER 1
CHARLES GFCI OUTLET		180	15A	3	B	4		2880	2880	ABB/GE INFINITY RECTIFIER 2
-SPACE-				5	A	6	30A	2880	2880	ABB/GE INFINITY RECTIFIER 2
-SPACE-				7	B	8		2880	2880	ABB/GE INFINITY RECTIFIER 3
-SPACE-				9	A	10	30A	2880	2880	ABB/GE INFINITY RECTIFIER 3
-SPACE-				11	B	12		2880	2880	ABB/GE INFINITY RECTIFIER 4
-SPACE-				13	A	14	30A	2880	2880	ABB/GE INFINITY RECTIFIER 4
-SPACE-				15	B	16		2880	2880	-SPACE-
-SPACE-				17	A	18				-SPACE-
-SPACE-				19	B	20				-SPACE-
-SPACE-				21	A	22				-SPACE-
-SPACE-				23	B	24				-SPACE-
VOLTAGE AMPS	180	180						11520	11520	
200A MCB, 1φ, 24 SPACE, 120/240V			L1	L2						
MB RATING: 65,000 AIC			11700	11700		VOLTAGE AMPS				
			98	98		AMPS				
			98			MAX AMPS				
			123			MAX 125%				

PANEL SCHEDULE

NO SCALE

2

NOT USED


NO SCALE 3



5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



INFINIGY
FROM ZERO TO INFINIGY
500 W. OFFICE CENTER DR. SUITE 150 |
FORT WASHINGTON, PA 19034



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY: RCD
CHECKED BY: SS
APPROVED BY: CJW

RFDS REV #: N/A

PRELIMINARY DOCUMENTS


SUBMITTALS		
REV	DATE	DESCRIPTION
A	09/03/2021	ISSUED FOR REVIEW
B	12/14/2022	ISSUED FOR REVIEW
O	01/25/2023	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
1197-C0001C

DISH WIRELESS, LLC.
PROJECT INFORMATION
BOHVN00191A
525 ORANGE CENTER ROAD
ORANGE, CT 06477

SHEET TITLE
ELECTRICAL ONE-LINE
& PANEL SCHEDULE

SHEET NUMBER
E-3




TYPICAL EQUIPMENT GROUNDING PLAN

NO SCALE 1

NOTES

1. ANTENNAS AND OVP SHOWN ARE GENERIC AND NOT REFERENCING TO A SPECIFIC MANUFACTURER. THIS LAYOUT IS FOR REFERENCE ONLY



TYPICAL ANTENNA GROUNDING PLAN

NO SCALE 2

- EXOTHERMIC CONNECTION
- MECHANICAL CONNECTION
- GROUND BUS BAR
- GROUND ROD
- TEST GROUND ROD WITH INSPECTION SLEEVE
- #6 AWG STRANDED & INSULATED
- - - #2 AWG SOLID COPPER TINNED
- ▲ BUSS BAR INSULATOR

GROUNDING LEGEND

1. GROUNDING IS SHOWN DIAGRAMMATICALLY ONLY.
2. CONTRACTOR SHALL GROUND ALL EQUIPMENT AS A COMPLETE SYSTEM. GROUNDING SHALL BE IN COMPLIANCE WITH NEC SECTION 250 AND DISH WIRELESS, LLC. GROUNDING AND BONDING REQUIREMENTS AND MANUFACTURER'S SPECIFICATIONS.
3. ALL GROUND CONDUCTORS SHALL BE COPPER; NO ALUMINUM CONDUCTORS SHALL BE USED.

GROUNDING KEY NOTES

- (A) **EXTERIOR GROUND RING:** #2 AWG SOLID COPPER, BURIED AT A DEPTH OF AT LEAST 30 INCHES BELOW GRADE, OR 6 INCHES BELOW THE FROST LINE AND APPROXIMATELY 24 INCHES FROM THE EXTERIOR WALL OR FOOTING.
- (B) **TOWER GROUND RING:** THE GROUND RING SYSTEM SHALL BE INSTALLED AROUND AN ANTENNA TOWER'S LEGS, AND/OR GUY ANCHORS. WHERE SEPARATE SYSTEMS HAVE BEEN PROVIDED FOR THE TOWER AND THE BUILDING, AT LEAST TWO BONDS SHALL BE MADE BETWEEN THE TOWER RING GROUND SYSTEM AND THE BUILDING RING GROUND SYSTEM USING MINIMUM #2 AWG SOLID COPPER CONDUCTORS.
- (C) **INTERIOR GROUND RING:** #2 AWG STRANDED GREEN INSULATED COPPER CONDUCTOR EXTENDED AROUND THE PERIMETER OF THE EQUIPMENT AREA. ALL NON-TELECOMMUNICATIONS RELATED METALLIC OBJECTS FOUND WITHIN A SITE SHALL BE GROUNDED TO THE INTERIOR GROUND RING WITH #6 AWG STRANDED GREEN INSULATED CONDUCTOR.
- (D) **BOND TO INTERIOR GROUND RING:** #2 AWG SOLID TINNED COPPER WIRE PRIMARY BONDS SHALL BE PROVIDED AT LEAST AT FOUR POINTS ON THE INTERIOR GROUND RING, LOCATED AT THE CORNERS OF THE BUILDING.
- (E) **GROUND ROD:** UL LISTED COPPER CLAD STEEL. MINIMUM 5/8" DIAMETER BY 10' LONG. GROUND RODS SHALL BE INSTALLED WITH INSPECTION SLEEVES. GROUND RODS SHALL BE DRIVEN TO THE DEPTH OF GROUND RING CONDUCTOR.
- (F) **CELL REFERENCE GROUND BAR:** POINT OF GROUND REFERENCE FOR ALL COMMUNICATIONS EQUIPMENT FRAMES. ALL BONDS ARE MADE WITH #2 AWG UNLESS NOTED OTHERWISE STRANDED GREEN INSULATED COPPER CONDUCTORS. BOND TO GROUND RING WITH (2) #2 SOLID TINNED COPPER CONDUCTORS.
- (G) **HATCH PLATE GROUND BAR:** BOND TO THE INTERIOR GROUND RING WITH TWO #2 AWG STRANDED GREEN INSULATED COPPER CONDUCTORS. WHEN A HATCH-PLATE AND A CELL REFERENCE GROUND BAR ARE BOTH PRESENT, THE CRGB MUST BE CONNECTED TO THE HATCH-PLATE AND TO THE INTERIOR GROUND RING USING (2) TWO #2 AWG STRANDED GREEN INSULATED COPPER CONDUCTORS EACH.
- (H) **EXTERIOR CABLE ENTRY PORT GROUND BARS:** LOCATED AT THE ENTRANCE TO THE CELL SITE BUILDING. BOND TO GROUND RING WITH A #2 AWG SOLID TINNED COPPER CONDUCTORS WITH AN EXOTHERMIC WELD AND INSPECTION SLEEVE.
- (I) **TELCO GROUND BAR:** BOND TO BOTH CELL REFERENCE GROUND BAR OR EXTERIOR GROUND RING.
- (J) **FRAME BONDING:** THE BONDING POINT FOR TELECOM EQUIPMENT FRAMES SHALL BE THE GROUND BUS THAT IS NOT ISOLATED FROM THE EQUIPMENTS METAL FRAMEWORK.
- (K) **INTERIOR UNIT BONDS:** METAL FRAMES, CABINETS AND INDIVIDUAL METALLIC UNITS LOCATED WITH THE AREA OF THE INTERIOR GROUND RING REQUIRE A #6 AWG STRANDED GREEN INSULATED COPPER BOND TO THE INTERIOR GROUND RING.
- (L) **FENCE AND GATE GROUNDING:** METAL FENCES WITHIN 7 FEET OF THE EXTERIOR GROUND RING OR OBJECTS BONDED TO THE EXTERIOR GROUND RING SHALL BE BONDED TO THE GROUND RING WITH A #2 AWG SOLID TINNED COPPER CONDUCTOR AT AN INTERVAL NOT EXCEEDING 25 FEET. BONDS SHALL BE MADE AT EACH GATE POST AND ACROSS GATE OPENINGS.
- (M) **EXTERIOR UNIT BONDS:** METALLIC OBJECTS, EXTERNAL TO OR MOUNTED TO THE BUILDING, SHALL BE BONDED TO THE EXTERIOR GROUND RING. USING #2 TINNED SOLID COPPER WIRE
- (N) **ICE BRIDGE SUPPORTS:** EACH ICE BRIDGE LEG SHALL BE BONDED TO THE GROUND RING WITH #2 AWG BARE TINNED COPPER CONDUCTOR. PROVIDE EXOTHERMIC WELDS AT BOTH THE ICE BRIDGE LEG AND BURIED GROUND RING.
- (O) **DURING ALL DC POWER SYSTEM CHANGES** INCLUDING DC SYSTEM CHANGE OUTS, RECTIFIER REPLACEMENTS OR ADDITIONS, BREAKER DISTRIBUTION CHANGES, BATTERY ADDITIONS, BATTERY REPLACEMENTS AND INSTALLATIONS OR CHANGES TO DC CONVERTER SYSTEMS IT SHALL BE REQUIRED THAT SERVICE CONTRACTORS VERIFY ALL DC POWER SYSTEMS ARE EQUIPPED WITH A MASTER DC SYSTEM RETURN GROUND CONDUCTOR FROM THE DC POWER SYSTEM COMMON RETURN BUS DIRECTLY CONNECTED TO THE CELL SITE REFERENCE GROUND BAR
- (P) **TOWER TOP COLLECTOR BUSS BAR** IS TO BE MECHANICALLY BONDED TO PROPOSED ANTENNA MOUNT COLLAR. REFER TO DISH WIRELESS, LLC. GROUNDING NOTES.

GROUNDING KEY NOTES

NO SCALE 3




5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



INFINIGY
FROM ZERO TO INFINIGY

500 W. OFFICE CENTER DR. SUITE 150 |
FORT WASHINGTON, PA 19034



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY: CHECKED BY: APPROVED BY:
RCD SS CJW

RFDS REV #: N/A

PRELIMINARY DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	09/03/2021	ISSUED FOR REVIEW
B	12/14/2022	ISSUED FOR REVIEW
O	01/25/2023	ISSUED FOR CONSTRUCTION



A&E PROJECT NUMBER
1197-C0001C

DISH WIRELESS, LLC.
PROJECT INFORMATION
BOHVN00191A
525 ORANGE CENTER ROAD
ORANGE, CT 06477

SHEET TITLE
GROUNDING PLANS
AND NOTES



SHEET NUMBER

G-1



TRANSITIONING GROUND DETAIL
NO SCALE
4

TYPICAL TEST GROUND ROD WITH INSPECTION SLEEVE
NO SCALE
5



TYPICAL GROUND RING TRENCH
NO SCALE
6


dish
wireless.

5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



INFINIGY
FROM ZERO TO INFINIGY

500 W. OFFICE CENTER DR. SUITE 150 |
FORT WASHINGTON, PA 19034



IT IS A VIOLATION OF LAW FOR ANY PERSON,
UNLESS THEY ARE ACTING UNDER THE DIRECTION
OF A LICENSED PROFESSIONAL ENGINEER,
TO ALTER THIS DOCUMENT.

DRAWN BY: CHECKED BY: APPROVED BY:

RCD SS CJW

RFDS REV #: N/A

PRELIMINARY
DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	09/03/2021	ISSUED FOR REVIEW
B	12/14/2022	ISSUED FOR REVIEW
O	01/25/2023	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
1197-C0001C

DISH WIRELESS, LLC.
PROJECT INFORMATION
BOHVN00191A
525 ORANGE CENTER ROAD
ORANGE, CT 06477

SHEET TITLE
GROUNDING DETAILS

SHEET NUMBER
G-2

RF JUMPER COLOR CODING

3/4" TAPE WIDTHS WITH 3/4" SPACING

LOW-BAND RRH –
(600MHz N71 BASEBAND) +
(850MHz N26 BAND) +
(700MHz N29 BAND) – OPTIONAL PER MARKET

ADD FREQUENCY COLOR TO SECTOR BAND
(CBRS WILL USE YELLOW BANDS)

ALPHA RRH				BETA RRH				GAMMA RRH			
PORT 1 + SLANT	PORT 2 + SLANT	PORT 3 + SLANT	PORT 4 + SLANT	PORT 1 + SLANT	PORT 2 + SLANT	PORT 3 + SLANT	PORT 4 + SLANT	PORT 1 + SLANT	PORT 2 + SLANT	PORT 3 + SLANT	PORT 4 + SLANT
RED	RED	RED	RED	BLUE	BLUE	BLUE	BLUE	GREEN	GREEN	GREEN	GREEN
ORANGE	ORANGE	RED	RED	ORANGE	ORANGE	BLUE	BLUE	ORANGE	ORANGE	GREEN	GREEN
	WHITE (1) PORT	ORANGE	ORANGE		WHITE (1) PORT	ORANGE	ORANGE		WHITE (1) PORT	ORANGE	ORANGE
			WHITE (1) PORT				WHITE (1) PORT				WHITE (1) PORT

MID-BAND RRH –
(AWS BANDS N66+N70)

ADD FREQUENCY COLOR TO SECTOR BAND
(CBRS WILL USE YELLOW BANDS)

RED	RED	RED	RED	BLUE	BLUE	BLUE	BLUE	GREEN	GREEN	GREEN	GREEN
PURPLE	PURPLE	RED	RED	PURPLE	PURPLE	BLUE	BLUE	PURPLE	PURPLE	GREEN	GREEN
	WHITE (1) PORT	PURPLE	PURPLE		WHITE (1) PORT	PURPLE	PURPLE		WHITE (1) PORT	PURPLE	PURPLE
			WHITE (1) PORT				WHITE (1) PORT				WHITE (1) PORT

HYBRID/DISCREET CABLES

INCLUDE SECTOR BANDS BEING SUPPORTED AM
LONG WITH FREQUENCY BANDS

EXAMPLE 1 – HYBRID, OR DISCREET, SUPPORTS
ALL SECTORS, BOTH LOW-BANDS AND MID-BANDS

EXAMPLE 2 – HYBRID, OR DISCREET, SUPPORTS
CBRS ONLY, ALL SECTORS

EXAMPLE 1	EXAMPLE 2
RED	RED
BLUE	BLUE
GREEN	GREEN
ORANGE	YELLOW
PURPLE	

HYBRID/DISCREET CABLES

LOW-BAND RRH FIBER CABLES HAVE SECTOR
STRIPE ONLY

LOW BAND RRH	HIGH BAND RRH	LOW BAND RRH	LOW BAND RRH	LOW BAND RRH	LOW BAND RRH
RED	RED	BLUE	BLUE	GREEN	GREEN
	PURPLE		PURPLE		PURPLE

POWER CABLES TO RRHs

LOW-BAND RRH POWER CABLES HAVE SECTOR
STRIPE ONLY

LOW BAND RRH	HIGH BAND RRH	LOW BAND RRH	LOW BAND RRH	LOW BAND RRH	LOW BAND RRH
RED	RED	BLUE	BLUE	GREEN	GREEN
	PURPLE		PURPLE		PURPLE

RET MOTORS AT ANTENNAS

PORT 1/ ANTENNA 1 "IN"	PORT 1/ ANTENNA 1 "IN"	PORT 1/ ANTENNA 1 "IN"
RED	BLUE	GREEN

MICROWAVE RADIO LINKS

LINKS WILL HAVE A 1.5–2 INCH WHITE WRAP WITH
THE AZIMUTH COLOR OVERLAPPING IN THE MIDDLE.
ADD ADDITIONAL SECTOR COLOR BANDS FOR EACH
ADDITIONAL MW RADIO.

MICROWAVE CABINETS WILL REQUIRE P-TOUCH
LABELS INSIDE THE CABINET TO IDENTIFY THE
LOCAL AND REMOTE SITE ID'S.

PRIMARY	SECONDARY
WHITE	WHITE
RED	RED
WHITE	WHITE
	RED
	WHITE

LOW BANDS (N71–N28)
OPTIONAL – (N29)

ORANGE

AWS
(N65+N70+H–BLOCK)

PURPLE

CBRS TECH
(3 GHz)

YELLOW

NEGATIVE SLANT PORT
ON ANTRRH

WHITE

ALPHA SECTOR

RED

BETA SECTOR

BLUE

GAMMA SECTOR

GREEN

COLOR IDENTIFIER

NO SCALE

2

NOT USED

NO SCALE

3

NOT USED

NO SCALE

4

RF CABLE COLOR CODES

NO SCALE

1


dish
wireless.

5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



INFINIGY
FROM ZERO TO INFINIGY

500 W. OFFICE CENTER DR. SUITE 150 |
FORT WASHINGTON, PA 19034



IT IS A VIOLATION OF LAW FOR ANY PERSON,
UNLESS THEY ARE ACTING UNDER THE DIRECTION
OF A LICENSED PROFESSIONAL ENGINEER,
TO ALTER THIS DOCUMENT.

DRAWN BY: CHECKED BY: APPROVED BY:

RCD

SS

CJW

RFDS REV #: N/A

PRELIMINARY
DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	09/03/2021	ISSUED FOR REVIEW
B	12/14/2022	ISSUED FOR REVIEW
O	01/25/2023	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER

1197–C0001C

DISH WIRELESS, LLC.
PROJECT INFORMATION

BOHVN00191A
525 ORANGE CENTER ROAD
ORANGE, CT 06477

SHEET TITLE

RF
CABLE COLOR CODES

SHEET NUMBER

RF-1

§

F

SD

10

_____ x _____ x _____ x _____ x _____

A horizontal line with six square nodes. The nodes are represented by small squares placed at regular intervals along the line.

— W — W — W — W — W —

— UGP — UGP — UGP — UGP — UGP —

— UGT — UGT — UGT — UGT — UGT —

———— OHP ————— OHP ————— OHP ————— OHP —————

———— OHT ————— OHT ————— OHT ————— OHT —————

— UGT/P — UGT/P — UGT/P — UGT/P —

— AGP — AGP — AGP — AGP — AGP —

— AGT — AGT — AGT — AGT — AGT —

— AGT/P — AGT/P — AGT/P — AGT/P —

W.P.



ABBREVIATIONS

INCH	
INT	INTERIOR
LB(S)	POUND(S)
LF	LINEAR FEET
LTE	LONG TERM EVOLUTION
MAS	MASONRY
MAX	MAXIMUM
MB	MACHINE BOLT
MECH	MECHANICAL
MFR	MANUFACTURER
MGB	MASTER GROUND BAR
MIN	MINIMUM
MISC	MISCELLANEOUS
MTL	METAL
MTS	MANUAL TRANSFER SWITCH
MW	MICROWAVE
NEC	NATIONAL ELECTRIC CODE
NM	NEWTON METERS
NO.	NUMBER
#	NUMBER
NTS	NOT TO SCALE
OC	ON-CENTER
OSHA	OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION
OPNG	OPENING
P/C	PRECAST CONCRETE
PCS	PERSONAL COMMUNICATION SERVICES
PCU	PRIMARY CONTROL UNIT
PRC	PRIMARY RADIO CABINET
PP	POLARIZING PRESERVING
PSF	POUNDS PER SQUARE FOOT
PSI	POUNDS PER SQUARE INCH
PT	PRESSURE TREATED
PWR	POWER CABINET
QTY	QUANTITY
RAD	RADIUS
RECT	RECTIFIER
REF	REFERENCE
REINF	REINFORCEMENT
REQ'D	REQUIRED
RET	REMOTE ELECTRIC TILT
RF	RADIO FREQUENCY
RMC	RIGID METALLIC CONDUIT
RRH	REMOTE RADIO HEAD
RRU	REMOTE RADIO UNIT
RWY	RACEWAY
SCH	SCHEDULE
SHT	SHEET
SIAD	SMART INTEGRATED ACCESS DEVICE
SIM	SIMILAR
SPEC	SPECIFICATION
SQ	SQUARE
SS	STAINLESS STEEL
STD	STANDARD
STL	STEEL
TEMP	TEMPORARY
THK	THICKNESS
TMA	TOWER MOUNTED AMPLIFIER
TN	TOE NAIL
TOA	TOP OF ANTENNA
TOC	TOP OF CURB
TOF	TOP OF FOUNDATION
TOP	TOP OF PLATE (PARAPET)
TOS	TOP OF STEEL
TOW	TOP OF WALL
TVSS	TRANSIENT VOLTAGE SURGE SUPPRESSION
TYP	TYPICAL
UG	UNDERGROUND
UL	UNDERWRITERS LABORATORY
UNO	UNLESS NOTED OTHERWISE
UMTS	UNIVERSAL MOBILE TELECOMMUNICATIONS SYSTEM
UPS	UNINTERRUPTIBLE POWER SYSTEM (DC POWER PLANT)
VIF	VERIFIED IN FIELD
W	WIDE
W/	WITH
WD	WOOD
WP	WEATHERPROOF
WT	WEIGHT

GN-1

SIGN TYPES		
TYPE	COLOR	COLOR CODE PURPOSE
INFORMATION	GREEN	"INFORMATIONAL SIGN" TO NOTIFY OTHERS OF SITE OWNERSHIP & CONTACT NUMBER AND POTENTIAL RF EXPOSURE.
NOTICE	BLUE	"NOTICE BEYOND THIS POINT" RF FIELDS BEYOND THIS POINT MAY EXCEED THE FCC GENERAL PUBLIC EXPOSURE LIMIT. OBEY ALL POSTED SIGNS AND SITE GUIDELINES FOR WORKING IN RF ENVIRONMENTS. IN ACCORDANCE WITH FEDERAL COMMUNICATIONS COMMISSION RULES ON RADIO FREQUENCY EMISSIONS 47 CFR-1.1307(b)
CAUTION	YELLOW	"CAUTION BEYOND THIS POINT" RF FIELDS BEYOND THIS POINT MAY EXCEED THE FCC GENERAL PUBLIC EXPOSURE LIMIT. OBEY ALL POSTED SIGNS AND SITE GUIDELINES FOR WORKING IN RF ENVIRONMENTS. IN ACCORDANCE WITH FEDERAL COMMUNICATIONS COMMISSION RULES ON RADIO FREQUENCY EMISSIONS 47 CFR-1.1307(b)
WARNING	ORANGE/RED	"WARNING BEYOND THIS POINT" RF FIELDS AT THIS SITE EXCEED FCC RULES FOR HUMAN EXPOSURE. FAILURE TO OBEY ALL POSTED SIGNS AND SITE GUIDELINES FOR WORKING IN RF ENVIRONMENTS COULD RESULT IN SERIOUS INJURY. IN ACCORDANCE WITH FEDERAL COMMUNICATIONS COMMISSION RULES ON RADIO FREQUENCY EMISSIONS 47 CFR-1.1307(b)

SIGN PLACEMENT:

- RF SIGNAGE PLACEMENT SHALL FOLLOW THE RECOMMENDATIONS OF AN EXISTING EME REPORT, CREATED BY A THIRD PARTY PREVIOUSLY AUTHORIZED BY DISH Wireless L.L.C.
- INFORMATION SIGN (GREEN) SHALL BE LOCATED ON EXISTING DISH Wireless L.L.C. EQUIPMENT.
 - A) IF THE INFORMATION SIGN IS A STICKER, IT SHALL BE PLACED ON EXISTING DISH Wireless L.L.C. EQUIPMENT CABINET.
 - B) IF THE INFORMATION SIGN IS A METAL SIGN IT SHALL BE PLACED ON EXISTING DISH Wireless L.L.C. H-FRAME WITH A SECURE ATTACH METHOD.
- IF EME REPORT IS NOT AVAILABLE AT THE TIME OF CREATION OF CONSTRUCTION DOCUMENTS; PLEASE CONTACT DISH Wireless L.L.C. CONSTRUCTION MANAGER FOR FURTHER INSTRUCTION ON HOW TO PROCEED.

NOTES:

1. FOR DISH Wireless L.L.C. LOGO, SEE DISH Wireless L.L.C. DESIGN SPECIFICATIONS (PROVIDED BY DISH Wireless L.L.C.)
2. SITE ID SHALL BE APPLIED TO SIGNS USING "LASER ENGRAVING" OR ANY OTHER WEATHER RESISTANT METHOD (DISH Wireless L.L.C. APPROVAL REQUIRED)
3. TEXT FOR SIGNAGE SHALL INDICATE CORRECT SITE NAME AND NUMBER AS PER DISH Wireless L.L.C. CONSTRUCTION MANAGER RECOMMENDATIONS.
4. CABINET/SHELTER MOUNTING APPLICATION REQUIRES ANOTHER PLATE APPLIED TO THE FACE OF THE CABINET WITH WATER PROOF POLYURETHANE ADHESIVE
5. ALL SIGNS WILL BE SECURED WITH EITHER STAINLESS STEEL ZIP TIES OR STAINLESS STEEL TECH SCREWS
6. ALL SIGNS TO BE 8.5"x11" AND MADE WITH 0.04" OF ALUMINUM MATERIAL

INFORMATION

This is an access point to an area with transmitting antennas.

Obey all signs and barriers beyond this point.
Call the DISH Wireless L.L.C. NOC at 1-866-624-6874

Site ID: _____



THIS SIGN IS FOR REFERENCE PURPOSES ONLY

NOTICE



Transmitting Antenna(s)

Radio frequency fields beyond this point **MAY EXCEED** the FCC Occupational exposure limit.

Obey all posted signs and site guidelines for working in radio frequency environments.

Call the DISH Wireless L.L.C. NOC at 1-866-624-6874 prior to working beyond this point.

Site ID: _____

THIS SIGN IS FOR REFERENCE PURPOSES ONLY

CAUTION



Transmitting Antenna(s)

Radio frequency fields beyond this point **MAY EXCEED** the FCC Occupational exposure limit.

Obey all posted signs and site guidelines for working in radio frequency environments.

Call the DISH Wireless L.L.C. NOC at 1-866-624-6874 prior to working beyond this point.

Site ID: _____

THIS SIGN IS FOR REFERENCE PURPOSES ONLY

WARNING



Transmitting Antenna(s)

Radio frequency fields beyond this point **EXCEED** the FCC Occupational exposure limit.

Obey all posted signs and site guidelines for working in radio frequency environments.

Call the DISH Wireless L.L.C. NOC at 1-866-624-6874 prior to working beyond this point.

Site ID: _____

THIS SIGN IS FOR REFERENCE PURPOSES ONLY


dish
wireless.

5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



INFINIGY
FROM ZERO TO INFINIGY

500 W. OFFICE CENTER DR. SUITE 150 |
FORT WASHINGTON, PA 19034



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
RCD	SS	CJW

RFDS REV #: N/A

PRELIMINARY DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	09/03/2021	ISSUED FOR REVIEW
B	12/14/2022	ISSUED FOR REVIEW
0	01/25/2023	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
1197-C0001C

DISH WIRELESS, LLC.
PROJECT INFORMATION
BOHVN00191A
525 ORANGE CENTER ROAD
ORANGE, CT 06477

SHEET TITLE
RF
SIGNAGE

SHEET NUMBER
GN-2

SITE ACTIVITY REQUIREMENTS:

1. NOTICE TO PROCEED – NO WORK SHALL COMMENCE PRIOR TO CONTRACTOR RECEIVING A WRITTEN NOTICE TO PROCEED (NTP) AND THE ISSUANCE OF A PURCHASE ORDER. PRIOR TO ACCESSING/ENTERING THE SITE YOU MUST CONTACT THE DISH Wireless L.L.C. AND TOWER OWNER NOC & THE DISH Wireless L.L.C. AND TOWER OWNER CONSTRUCTION MANAGER.
2. "LOOK UP" – DISH Wireless L.L.C. AND TOWER OWNER SAFETY CLIMB REQUIREMENT:

THE INTEGRITY OF THE SAFETY CLIMB AND ALL COMPONENTS OF THE CLIMBING FACILITY SHALL BE CONSIDERED DURING ALL STAGES OF DESIGN, INSTALLATION, AND INSPECTION. TOWER MODIFICATION, MOUNT REINFORCEMENTS, AND/OR EQUIPMENT INSTALLATIONS SHALL NOT COMPROMISE THE INTEGRITY OR FUNCTIONAL USE OF THE SAFETY CLIMB OR ANY COMPONENTS OF THE CLIMBING FACILITY ON THE STRUCTURE. THIS SHALL INCLUDE, BUT NOT BE LIMITED TO: PINCHING OF THE WIRE ROPE, BENDING OF THE WIRE ROPE FROM ITS SUPPORTS, DIRECT CONTACT OR CLOSE PROXIMITY TO THE WIRE ROPE WHICH MAY CAUSE FRICTIONAL WEAR, IMPACT TO THE ANCHORAGE POINTS IN ANY WAY, OR TO IMPEDE/BLOCK ITS INTENDED USE. ANY COMPROMISED SAFETY CLIMB, INCLUDING EXISTING CONDITIONS MUST BE TAGGED OUT AND REPORTED TO YOUR DISH Wireless L.L.C. AND DISH Wireless L.L.C. AND TOWER OWNER POC OR CALL THE NOC TO GENERATE A SAFETY CLIMB MAINTENANCE AND CONTRACTOR NOTICE TICKET.
3. PRIOR TO THE START OF CONSTRUCTION, ALL REQUIRED JURISDICTIONAL PERMITS SHALL BE OBTAINED. THIS INCLUDES, BUT IS NOT LIMITED TO, BUILDING, ELECTRICAL, MECHANICAL, FIRE, FLOOD ZONE, ENVIRONMENTAL, AND ZONING. AFTER ONSITE ACTIVITIES AND CONSTRUCTION ARE COMPLETED, ALL REQUIRED PERMITS SHALL BE SATISFIED AND CLOSED OUT ACCORDING TO LOCAL JURISDICTIONAL REQUIREMENTS.
4. ALL CONSTRUCTION MEANS AND METHODS; INCLUDING BUT NOT LIMITED TO, ERECTION PLANS, RIGGING PLANS, CLIMBING PLANS, AND RESCUE PLANS SHALL BE THE RESPONSIBILITY OF THE GENERAL CONTRACTOR RESPONSIBLE FOR THE EXECUTION OF THE WORK CONTAINED HEREIN, AND SHALL MEET ANSI/ASSE A10.48 (LATEST EDITION); FEDERAL, STATE, AND LOCAL REGULATIONS; AND ANY APPLICABLE INDUSTRY CONSENSUS STANDARDS RELATED TO THE CONSTRUCTION ACTIVITIES BEING PERFORMED. ALL RIGGING PLANS SHALL ADHERE TO ANSI/ASSE A10.48 (LATEST EDITION) AND DISH Wireless L.L.C. AND TOWER OWNER STANDARDS, INCLUDING THE REQUIRED INVOLVEMENT OF A QUALIFIED ENGINEER FOR CLASS IV CONSTRUCTION, TO CERTIFY THE SUPPORTING STRUCTURE(S) IN ACCORDANCE WITH ANSI/TIA–322 (LATEST EDITION).
5. ALL SITE WORK TO COMPLY WITH DISH Wireless L.L.C. AND TOWER OWNER INSTALLATION STANDARDS FOR CONSTRUCTION ACTIVITIES ON DISH Wireless L.L.C. AND TOWER OWNER TOWER SITE AND LATEST VERSION OF ANSI/TIA–1019–A–2012 "STANDARD FOR INSTALLATION, ALTERATION, AND MAINTENANCE OF ANTENNA SUPPORTING STRUCTURES AND ANTENNAS."
6. IF THE SPECIFIED EQUIPMENT CAN NOT BE INSTALLED AS SHOWN ON THESE DRAWINGS, THE CONTRACTOR SHALL PROPOSE AN ALTERNATIVE INSTALLATION FOR APPROVAL BY DISH Wireless L.L.C. AND TOWER OWNER PRIOR TO PROCEEDING WITH ANY SUCH CHANGE OF INSTALLATION.
7. ALL MATERIALS FURNISHED AND INSTALLED SHALL BE IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS AND ORDINANCES. CONTRACTOR SHALL ISSUE ALL APPROPRIATE NOTICES AND COMPLY WITH ALL LAWS, ORDINANCES, RULES, REGULATIONS AND LAWFUL ORDERS OF ANY PUBLIC AUTHORITY REGARDING THE PERFORMANCE OF THE WORK. ALL WORK CARRIED OUT SHALL COMPLY WITH ALL APPLICABLE MUNICIPAL AND UTILITY COMPANY SPECIFICATIONS AND LOCAL JURISDICTIONAL CODES, ORDINANCES AND APPLICABLE REGULATIONS.
8. THE CONTRACTOR SHALL INSTALL ALL EQUIPMENT AND MATERIALS IN ACCORDANCE WITH MANUFACTURER’S RECOMMENDATIONS UNLESS SPECIFICALLY STATED OTHERWISE.
9. THE CONTRACTOR SHALL CONTACT UTILITY LOCATING SERVICES INCLUDING PRIVATE LOCATES SERVICES PRIOR TO THE START OF CONSTRUCTION.
10. ALL EXISTING ACTIVE SEWER, WATER, GAS, ELECTRIC AND OTHER UTILITIES WHERE ENCOUNTERED IN THE WORK, SHALL BE PROTECTED AT ALL TIMES AND WHERE REQUIRED FOR THE PROPER EXECUTION OF THE WORK, SHALL BE RELOCATED AS DIRECTED BY CONTRACTOR. EXTREME CAUTION SHOULD BE USED BY THE CONTRACTOR WHEN EXCAVATING OR DRILLING PIERS AROUND OR NEAR UTILITIES. CONTRACTOR SHALL PROVIDE SAFETY TRAINING FOR THE WORKING CREW. THIS WILL INCLUDE BUT NOT BE LIMITED TO A) FALL PROTECTION B) CONFINED SPACE C) ELECTRICAL SAFETY D) TRENCHING AND EXCAVATION E) CONSTRUCTION SAFETY PROCEDURES.
11. ALL SITE WORK SHALL BE AS INDICATED ON THE STAMPED CONSTRUCTION DRAWINGS AND DISH PROJECT SPECIFICATIONS, LATEST APPROVED REVISION.
12. CONTRACTOR SHALL KEEP THE SITE FREE FROM ACCUMULATING WASTE MATERIAL, DEBRIS, AND TRASH AT THE COMPLETION OF THE WORK. IF NECESSARY, RUBBISH, STUMPS, DEBRIS, STICKS, STONES AND OTHER REFUSE SHALL BE REMOVED FROM THE SITE AND DISPOSED OF LEGALLY.
13. ALL EXISTING INACTIVE SEWER, WATER, GAS, ELECTRIC AND OTHER UTILITIES, WHICH INTERFERE WITH THE EXECUTION OF THE WORK, SHALL BE REMOVED AND/OR CAPPED, PLUGGED OR OTHERWISE DISCONTINUED AT POINTS WHICH WILL NOT INTERFERE WITH THE EXECUTION OF THE WORK, SUBJECT TO THE APPROVAL OF DISH Wireless L.L.C. AND TOWER OWNER, AND/OR LOCAL UTILITIES.
14. THE CONTRACTOR SHALL PROVIDE SITE SIGNAGE IN ACCORDANCE WITH THE TECHNICAL SPECIFICATION FOR SITE SIGNAGE REQUIRED BY LOCAL JURISDICTION AND SIGNAGE REQUIRED ON INDIVIDUAL PIECES OF EQUIPMENT, ROOMS, AND SHELTERS.
15. THE SITE SHALL BE GRADED TO CAUSE SURFACE WATER TO FLOW AWAY FROM THE CARRIER’S EQUIPMENT AND TOWER AREAS.
16. THE SUB GRADE SHALL BE COMPACTED AND BROUGHT TO A SMOOTH UNIFORM GRADE PRIOR TO FINISHED SURFACE APPLICATION.
17. THE AREAS OF THE OWNERS PROPERTY DISTURBED BY THE WORK AND NOT COVERED BY THE TOWER, EQUIPMENT OR DRIVEWAY, SHALL BE GRADED TO A UNIFORM SLOPE, AND STABILIZED TO PREVENT EROSION AS SPECIFIED ON THE CONSTRUCTION DRAWINGS AND/OR PROJECT SPECIFICATIONS.
18. CONTRACTOR SHALL MINIMIZE DISTURBANCE TO EXISTING SITE DURING CONSTRUCTION. EROSION CONTROL MEASURES, IF REQUIRED DURING CONSTRUCTION, SHALL BE IN CONFORMANCE WITH THE LOCAL GUIDELINES FOR EROSION AND SEDIMENT CONTROL.
19. THE CONTRACTOR SHALL PROTECT EXISTING IMPROVEMENTS, PAVEMENTS, CURBS, LANDSCAPING AND STRUCTURES. ANY DAMAGED PART SHALL BE REPAIRED AT CONTRACTOR’S EXPENSE TO THE SATISFACTION OF OWNER.
20. CONTRACTOR SHALL LEGALLY AND PROPERLY DISPOSE OF ALL SCRAP MATERIALS SUCH AS COAXIAL CABLES AND OTHER ITEMS REMOVED FROM THE EXISTING FACILITY. ANTENNAS AND RADIOS REMOVED SHALL BE RETURNED TO THE OWNER’S DESIGNATED LOCATION.
21. CONTRACTOR SHALL LEAVE PREMISES IN CLEAN CONDITION. TRASH AND DEBRIS SHOULD BE REMOVED FROM SITE ON A DAILY BASIS.
22. NO FILL OR EMBANKMENT MATERIAL SHALL BE PLACED ON FROZEN GROUND. FROZEN MATERIALS, SNOW OR ICE SHALL NOT BE PLACED IN ANY FILL OR EMBANKMENT.

GENERAL NOTES:

- 1.FOR THE PURPOSE OF CONSTRUCTION DRAWING, THE FOLLOWING DEFINITIONS SHALL APPLY:

CONTRACTOR:GENERAL CONTRACTOR RESPONSIBLE FOR CONSTRUCTION

CARRIER:DISH Wireless L.L.C.

TOWER OWNER:TOWER OWNER
2. THESE DRAWINGS HAVE BEEN PREPARED USING STANDARDS OF PROFESSIONAL CARE AND COMPLETENESS NORMALLY EXERCISED UNDER SIMILAR CIRCUMSTANCES BY REPUTABLE ENGINEERS IN THIS OR SIMILAR LOCALITIES. IT IS ASSUMED THAT THE WORK DEPICTED WILL BE PERFORMED BY AN EXPERIENCED CONTRACTOR AND/OR WORKPEOPLE WHO HAVE A WORKING KNOWLEDGE OF THE APPLICABLE CODE STANDARDS AND REQUIREMENTS AND OF INDUSTRY ACCEPTED STANDARD GOOD PRACTICE. AS NOT EVERY CONDITION OR ELEMENT IS (OR CAN BE) EXPLICITLY SHOWN ON THESE DRAWINGS, THE CONTRACTOR SHALL USE INDUSTRY ACCEPTED STANDARD GOOD PRACTICE FOR MISCELLANEOUS WORK NOT EXPLICITLY SHOWN.
3. THESE DRAWINGS REPRESENT THE FINISHED STRUCTURE. THEY DO NOT INDICATE THE MEANS OR METHODS OF CONSTRUCTION. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR THE CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES. THE CONTRACTOR SHALL PROVIDE ALL MEASURES NECESSARY FOR PROTECTION OF LIFE AND PROPERTY DURING CONSTRUCTION. SUCH MEASURES SHALL INCLUDE, BUT NOT BE LIMITED TO, BRACING, FORMWORK, SHORING, ETC. SITE VISITS BY THE ENGINEER OR HIS REPRESENTATIVE WILL NOT INCLUDE INSPECTION OF THESE ITEMS AND IS FOR STRUCTURAL OBSERVATION OF THE FINISHED STRUCTURE ONLY.
4. NOTES AND DETAILS IN THE CONSTRUCTION DRAWINGS SHALL TAKE PRECEDENCE OVER GENERAL NOTES AND TYPICAL DETAILS. WHERE NO DETAILS ARE SHOWN, CONSTRUCTION SHALL CONFORM TO SIMILAR WORK ON THE PROJECT, AND/OR AS PROVIDED FOR IN THE CONTRACT DOCUMENTS. WHERE DISCREPANCIES OCCUR BETWEEN PLANS, DETAILS, GENERAL NOTES, AND SPECIFICATIONS, THE GREATER, MORE STRICT REQUIREMENTS, SHALL GOVERN. IF FURTHER CLARIFICATION IS REQUIRED CONTACT THE ENGINEER OF RECORD.
5. SUBSTANTIAL EFFORT HAS BEEN MADE TO PROVIDE ACCURATE DIMENSIONS AND MEASUREMENTS ON THE DRAWINGS TO ASSIST IN THE FABRICATION AND/OR PLACEMENT OF CONSTRUCTION ELEMENTS BUT IT IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR TO FIELD VERIFY THE DIMENSIONS, MEASUREMENTS, AND/OR CLEARANCES SHOWN IN THE CONSTRUCTION DRAWINGS PRIOR TO FABRICATION OR CUTTING OF ANY NEW OR EXISTING CONSTRUCTION ELEMENTS. IF IT IS DETERMINED THAT THERE ARE DISCREPANCIES AND/OR CONFLICTS WITH THE CONSTRUCTION DRAWINGS THE ENGINEER OF RECORD IS TO BE NOTIFIED AS SOON AS POSSIBLE.
6. PRIOR TO THE SUBMISSION OF BIDS, THE BIDDING CONTRACTOR SHALL VISIT THE CELL SITE TO FAMILIARIZE WITH THE EXISTING CONDITIONS AND TO CONFIRM THAT THE WORK CAN BE ACCOMPLISHED AS SHOWN ON THE CONSTRUCTION DRAWINGS. ANY DISCREPANCY FOUND SHALL BE BROUGHT TO THE ATTENTION OF CARRIER POC AND TOWER OWNER.
7. ALL MATERIALS FURNISHED AND INSTALLED SHALL BE IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS AND ORDINANCES. CONTRACTOR SHALL ISSUE ALL APPROPRIATE NOTICES AND COMPLY WITH ALL LAWS, ORDINANCES, RULES, REGULATIONS AND LAWFUL ORDERS OF ANY PUBLIC AUTHORITY REGARDING THE PERFORMANCE OF THE WORK. ALL WORK CARRIED OUT SHALL COMPLY WITH ALL APPLICABLE MUNICIPAL AND UTILITY COMPANY SPECIFICATIONS AND LOCAL JURISDICTIONAL CODES, ORDINANCES AND APPLICABLE REGULATIONS.
8. UNLESS NOTED OTHERWISE, THE WORK SHALL INCLUDE FURNISHING MATERIALS, EQUIPMENT, APPURTENANCES AND LABOR NECESSARY TO COMPLETE ALL INSTALLATIONS AS INDICATED ON THE DRAWINGS.
9. THE CONTRACTOR SHALL INSTALL ALL EQUIPMENT AND MATERIALS IN ACCORDANCE WITH MANUFACTURER’S RECOMMENDATIONS UNLESS SPECIFICALLY STATED OTHERWISE.
10. IF THE SPECIFIED EQUIPMENT CAN NOT BE INSTALLED AS SHOWN ON THESE DRAWINGS, THE CONTRACTOR SHALL PROPOSE AN ALTERNATIVE INSTALLATION FOR APPROVAL BY THE CARRIER AND TOWER OWNER PRIOR TO PROCEEDING WITH ANY SUCH CHANGE OF INSTALLATION.
11. CONTRACTOR IS TO PERFORM A SITE INVESTIGATION, BEFORE SUBMITTING BIDS, TO DETERMINE THE BEST ROUTING OF ALL CONDUITS FOR POWER, AND TELCO AND FOR GROUNDING CABLES AS SHOWN IN THE POWER, TELCO, AND GROUNDING PLAN DRAWINGS.
12. THE CONTRACTOR SHALL PROTECT EXISTING IMPROVEMENTS, PAVEMENTS, CURBS, LANDSCAPING AND STRUCTURES. ANY DAMAGED PART SHALL BE REPAIRED AT CONTRACTOR’S EXPENSE TO THE SATISFACTION OF DISH Wireless L.L.C. AND TOWER OWNER
13. CONTRACTOR SHALL LEGALLY AND PROPERLY DISPOSE OF ALL SCRAP MATERIALS SUCH AS COAXIAL CABLES AND OTHER ITEMS REMOVED FROM THE EXISTING FACILITY. ANTENNAS REMOVED SHALL BE RETURNED TO THE OWNER’S DESIGNATED LOCATION.
14. CONTRACTOR SHALL LEAVE PREMISES IN CLEAN CONDITION. TRASH AND DEBRIS SHOULD BE REMOVED FROM SITE ON A DAILY BASIS.




5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



INFINIGY
FROM ZERO TO INFINIGY

500 W. OFFICE CENTER DR. SUITE 150 I
FORT WASHINGTON, PA 19034



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
RCD	SS	CJW

RFDS REV #: N/A

PRELIMINARY DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	09/03/2021	ISSUED FOR REVIEW
B	12/14/2022	ISSUED FOR REVIEW
O	01/25/2023	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER

1197–C0001C

DISH WIRELESS, LLC.
PROJECT INFORMATION

BOHVN00191A
525 ORANGE CENTER ROAD
ORANGE, CT 06477

SHEET TITLE

GENERAL NOTES

SHEET NUMBER

GN-3

GROUNDING NOTES:

1. ALL GROUND ELECTRODE SYSTEMS (INCLUDING TELECOMMUNICATION, RADIO, LIGHTNING PROTECTION AND AC POWER GES’S) SHALL BE BONDED TOGETHER AT OR BELOW GRADE, BY TWO OR MORE COPPER BONDING CONDUCTORS IN ACCORDANCE WITH THE NEC.
2. THE CONTRACTOR SHALL PERFORM IEEE FALL–OF–POTENTIAL RESISTANCE TO EARTH TESTING (PER IEEE 1100 AND 81) FOR GROUND ELECTRODE SYSTEMS, THE CONTRACTOR SHALL FURNISH AND INSTALL SUPPLEMENTAL GROUND ELECTRODES AS NEEDED TO ACHIEVE A TEST RESULT OF 5 OHMS OR LESS.
3. THE CONTRACTOR IS RESPONSIBLE FOR PROPERLY SEQUENCING GROUNDING AND UNDERGROUND CONDUIT INSTALLATION AS TO PREVENT ANY LOSS OF CONTINUITY IN THE GROUNDING SYSTEM OR DAMAGE TO THE CONDUIT AND PROVIDE TESTING RESULTS.
4. METAL CONDUIT AND TRAY SHALL BE GROUNDED AND MADE ELECTRICALLY CONTINUOUS WITH LISTED BONDING FITTINGS OR BY BONDING ACROSS THE DISCONTINUITY WITH #6 COPPER WIRE UL APPROVED GROUNDING TYPE CONDUIT CLAMPS.
5. METAL RACEWAY SHALL NOT BE USED AS THE NEC REQUIRED EQUIPMENT GROUND CONDUCTOR. STRANDED COPPER CONDUCTORS WITH GREEN INSULATION, SIZED IN ACCORDANCE WITH THE NEC, SHALL BE FURNISHED AND INSTALLED WITH THE POWER CIRCUITS TO BTS EQUIPMENT.
6. EACH CABINET FRAME SHALL BE DIRECTLY CONNECTED TO THE MASTER GROUND BAR WITH GREEN INSULATED SUPPLEMENTAL EQUIPMENT GROUND WIRES, #6 STRANDED COPPER OR LARGER FOR INDOOR BTS; #2 BARE SOLID TINNED COPPER FOR OUTDOOR BTS.
7. CONNECTIONS TO THE GROUND BUS SHALL NOT BE DOUBLED UP OR STACKED BACK TO BACK CONNECTIONS ON OPPOSITE SIDE OF THE GROUND BUS ARE PERMITTED.
8. ALL EXTERIOR GROUND CONDUCTORS BETWEEN EQUIPMENT/GROUND BARS AND THE GROUND RING SHALL BE #2 SOLID TINNED COPPER UNLESS OTHERWISE INDICATED.
9. ALUMINUM CONDUCTOR OR COPPER CLAD STEEL CONDUCTOR SHALL NOT BE USED FOR GROUNDING CONNECTIONS.
10. USE OF 90° BENDS IN THE PROTECTION GROUNDING CONDUCTORS SHALL BE AVOIDED WHEN 45° BENDS CAN BE ADEQUATELY SUPPORTED.
11. EXOTHERMIC WELDS SHALL BE USED FOR ALL GROUNDING CONNECTIONS BELOW GRADE.
12. ALL GROUND CONNECTIONS ABOVE GRADE (INTERIOR AND EXTERIOR) SHALL BE FORMED USING HIGH PRESS CRIMPS.
13. COMPRESSION GROUND CONNECTIONS MAY BE REPLACED BY EXOTHERMIC WELD CONNECTIONS.
14. ICE BRIDGE BONDING CONDUCTORS SHALL BE EXOTHERMICALLY BONDED OR BOLTED TO THE BRIDGE AND THE TOWER GROUND BAR.
15. APPROVED ANTIOXIDANT COATINGS (i.e. CONDUCTIVE GEL OR PASTE) SHALL BE USED ON ALL COMPRESSION AND BOLTED GROUND CONNECTIONS.
16. ALL EXTERIOR GROUND CONNECTIONS SHALL BE COATED WITH A CORROSION RESISTANT MATERIAL.
17. MISCELLANEOUS ELECTRICAL AND NON–ELECTRICAL METAL BOXES, FRAMES AND SUPPORTS SHALL BE BONDED TO THE GROUND RING, IN ACCORDANCE WITH THE NEC.
18. BOND ALL METALLIC OBJECTS WITHIN 6 ft OF MAIN GROUND RING WITH (1) #2 BARE SOLID TINNED COPPER GROUND CONDUCTOR.
19. GROUND CONDUCTORS USED FOR THE FACILITY GROUNDING AND LIGHTNING PROTECTION SYSTEMS SHALL NOT BE ROUTED THROUGH METALLIC OBJECTS THAT FORM A RING AROUND THE CONDUCTOR, SUCH AS METALLIC CONDUITS, METAL SUPPORT CLIPS OR SLEEVES THROUGH WALLS OR FLOORS. WHEN IT IS REQUIRED TO BE HOUSED IN CONDUIT TO MEET CODE REQUIREMENTS OR LOCAL CONDITIONS, NON–METALLIC MATERIAL SUCH AS PVC CONDUIT SHALL BE USED. WHERE USE OF METAL CONDUIT IS UNAVOIDABLE (i.e., NONMETALLIC CONDUIT PROHIBITED BY LOCAL CODE) THE GROUND CONDUCTOR SHALL BE BONDED TO EACH END OF THE METAL CONDUIT.
20. ALL GROUNDS THAT TRANSITION FROM BELOW GRADE TO ABOVE GRADE MUST BE #2 BARE SOLID TINNED COPPER IN 3/4” NON–METALLIC, FLEXIBLE CONDUIT FROM 24” BELOW GRADE TO WITHIN 3” TO 6” OF CAD–WELD TERMINATION POINT. THE EXPOSED END OF THE CONDUIT MUST BE SEALED WITH SILICONE CAULK. (ADD TRANSITIONING GROUND STANDARD DETAIL AS WELL).
21. BUILDINGS WHERE THE MAIN GROUNDING CONDUCTORS ARE REQUIRED TO BE ROUTED TO GRADE, THE CONTRACTOR SHALL ROUTE TWO GROUNDING CONDUCTORS FROM THE ROOFTOP, TOWERS, AND WATER TOWERS GROUNDING RING, TO THE EXISTING GROUNDING SYSTEM, THE GROUNDING CONDUCTORS SHALL NOT BE SMALLER THAN 2/0 COPPER. ROOFTOP GROUNDING RING SHALL BE BONDED TO THE EXISTING GROUNDING SYSTEM, THE BUILDING STEEL COLUMNS, LIGHTNING PROTECTION SYSTEM, AND BUILDING MAIN WATER LINE (FERROUS OR NONFERROUS METAL PIPING ONLY). DO NOT ATTACH GROUNDING TO FIRE SPRINKLER SYSTEM PIPES.




5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



INFINIGY

FROM ZERO TO INFINIGY

500 W. OFFICE CENTER DR. SUITE 150 |
FORT WASHINGTON, PA 19034



IT IS A VIOLATION OF LAW FOR ANY PERSON,
UNLESS THEY ARE ACTING UNDER THE DIRECTION
OF A LICENSED PROFESSIONAL ENGINEER,
TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
RCD	SS	CJW

RFDS REV #: N/A

PRELIMINARY DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	08/03/2021	ISSUED FOR REVIEW
B	12/14/2022	ISSUED FOR REVIEW
O	01/25/2023	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
1197–C0001C

DISH WIRELESS, LLC.
PROJECT INFORMATION
BOHVN00191A
525 ORANGE CENTER ROAD
ORANGE, CT 06477

SHEET TITLE
GENERAL NOTES

SHEET NUMBER
GN-5

Exhibit D

Structural Analysis Report


INFINIGY

TOWER STRUCTURAL ANALYSIS REPORT

December 29, 2022

DISH Wireless Site Number	BOHVN00191A
Infinigy Job Number	1197-F0001-B
Client	DISH Wireless
Carrier	DISH Wireless
Site Location	525 Orange Center Road New Haven, CT 06477 New Haven County 41° 16' 25.30" N NAD83 73° 1' 7.30" W NAD83
Structure Type	Monopole
Structure Height	160.0 ft
Structural Usage Ratio	70.7%
Overall Result	Pass

The enclosed tower analysis has been performed in accordance with the 2022 Connecticut State Building Code, based on an ultimate 3-second gust wind speed of 120 mph. The evaluation criteria and applicable codes are presented in the next section of this report.



structural@infinigy.com

December 29, 2022

CONTENTS

1. Introduction
2. Design/Analysis Parameters
3. Proposed Loading Configuration
4. Other Considered Loading
5. Supporting Documentation
6. Results
7. Recommendations
8. Assumptions
9. Liability Waiver and Limitations
10. Calculations

December 29, 2022

1. INTRODUCTION

Infinigy Engineering has been requested to perform a structural analysis on the existing 160.0 ft Monopole tower. All referenced supporting documents have been obtained from the client and are assumed to be accurate and applicable to this site. The structure was analyzed using tnxTower version 8.1.1 analysis software.

2. DESIGN/ANALYSIS PARAMETERS

Wind Speed	120 mph (3-Second Gust)
Wind Speed w/ ice	50 mph (3-Second Gust) w/ 1.0" ice
Adopted Code	2021 IBC / 2022 Connecticut State Building Code
Standard(s)	TIA-222-H
Risk Category	II
Exposure Category	B
Topographic Category	1
Seismic Spectral Response	$S_s = 0.201 \text{ g} / S_1 = 0.054 \text{ g}$
Live Load Wind Speed	60 mph
Seismic Soil Class	D-Stiff Soil (Assumed)
HMSL	203.93 ft

3. PROPOSED LOADING CONFIGURATION

RAD Center (ft)	Mount Center (ft)	Qty.	Appurtenance	Mount Type	Coax& Lines	Carrier
136.0	136.0	3	JMA Wireless MX08FRO665-21	Platform Mount	(1) 1-3/4" Coax	Dish Wireless
		3	Fujitsu TA08025-B605			
		3	Fujitsu TA08025-B604			
		1	Raycap RDIDC-9181-PF-48			

December 29, 2022

4. OTHER CONSIDERED LOADING

RAD Center (ft)	Mount Center (ft)	Qty.	Appurtenance	Mount Type	Coax& Lines	Carrier
156.0	168.0	1	GPS	Platform Mount	(9) 1-1/4" (2) 2" (3) 1/2" (12) 1-5/8" (1) Hybrid Cable	--
	167.0	9	DB844H90E-M			
		3	LLPX310R			
		3	RRU			
	164.0	2	VHLP2-11-DW1			Verizon
	158.0	6	JMA Wireless MX06FRO660-03			
		6	LPA-80060-6CF			
		3	Samsung MT6407-77A			
		3	Samsung B5/B23 RRH ORAN			
		3	Samsung B2/B66A RRH			
		1	Raycap DB-C1-12C-24A-0Z			
146.0	150.0	3	Ericsson RRUS-11	Platform Mount	(1) Fiber (2) #8 AWG Copper Wire (12) 1-1/4"	AT&T
		3	Ericsson RRUS-12			
		3	A2			
		1	Raycap DC6-48-60-18-8F			
	148.0	12	LGP21401 TMA			
		6	7770.00			
		3	HPA-65RBUU-H6			
121.0	123.0	3	Ericsson AIR6449	Platform Mount	(6) 1-5/8" (3) 1-1/4" Hybrid Cable	T-Mobile
		3	Ericsson AIR32			
		3	RFS/Celwave APXVAARR24-43			
		3	TMA 10"x8"x3"			
		3	Ericsson Radio 4449 B71 B12			
		3	Ericsson 4415 B25			
		3	Commscope SDX1926Q-43			
75.0	76.0	1	GPS	Side Arm Mount	(1) 1/2"	--

5. SUPPORTING DOCUMENTATION

Construction Drawings	Infinigy, Site ID: BOHVN00191A, Rev.C, dated December 8, 2022
Proposed Loading	DISH Wireless RFDS, dated February 15, 2021
Structural Analysis Report	CEN TEK, Project No.: 22027.11, dated October 6, 2022

December 29, 2022

6. RESULTS

Structural Components	Capacity	Pass/Fail
Pole	64.3%	Pass
Base Plate	20.7%	Pass
Anchor Bolts	49.1%	Pass
Soil Interaction	46.1%	Pass
Structural Foundation	70.7%	Pass
RATING =	70.7%	Pass

6.1 DEFLECTION, TWIST, AND SWAY

Antenna Elevation (ft)	Deflection (in)	Sway (°)	Twist (°)
136.0	14.1190	1.0769	0.0165

*Per ANSI/TIA-222-H Section 2.8.2 maximum serviceability structural deflection limit is 3% of structure height.

*Per ANSI/TIA-222-H Section 2.8.2 maximum serviceability structural twist and sway limit is 4 degrees.

*Per ANSI/TIA-222-H Section 2.8.3 deflection, Twist, and sway values were calculated using a basic 3-second gust wind speed of 60 mph.

*It is the responsibility of the client to ensure their proposed and/or existing equipment will meet ANSI/TIA-222-H Annex D or other appropriate microwave signal degradation limits based on the provided values above.

7. RECOMMENDATIONS

Infinigy recommends installing DISH Wireless' proposed equipment loading configuration on the mounts at 136.0 ft on this structure. The installation shall be performed in accordance with the construction documents issued for this site.

If you have any questions, require additional information, or believe the actual conditions differ from those detailed in this report, please contact us immediately.

Alex Mercado, E.I.T.
Senior Project Engineer | **INFINIGY**

8. ASSUMPTIONS

The structure, its foundation system and related structures were built and maintained in accordance with the manufacturer's specifications and instructions.	
The structure condition is essentially as erected and does not have corrosion, damages or defects that would affect its structural integrity. The structure is plumb and all members and their connections are sound and can fully develop their structural capacities.	
The configuration of antennas, transmission cables, mounts and other appurtenances are as specified in the loading configuration tables.	
Some of the antennas and mounts used in the structure model are similar in size and weight to the actual appurtenances mounted on the structure.	
Steel grades have been assumed as follows, unless noted otherwise:	
Channel, Solid Round, Angle, Plate	ASTM A36
HSS (Rectangular)	ASTM A500-B GR 46
HSS (Circular)	ASTM A500-B GR 42
Pipe	ASTM A53-B GR 35
Connection Bolts	ASTM A325
U-Bolts	ASTM A307
All bolted connections are pretensioned in accordance with Table 8.2 of the RCSC 2014 Standard.	


9. LIABILITY WAIVER AND LIMITATIONS

Our structural calculations are completed assuming all information provided to Infinigy is accurate and applicable to this site. For the purposes of calculations, we assume an overall structure condition as erected and all members and connections to be free of corrosion and/or structural defects. The structure owner and/or contractor shall verify the structure's condition prior to installation of any proposed equipment. If actual conditions differ from those described in this report, Infinigy Engineering should be notified immediately to assess the impact on the results of this report.

Our evaluation is completed using industry standard methods and procedures. The structural results, conclusions and recommendations contained in this report are proprietary and should not be used by others as their own. Infinigy is not responsible for decisions made by others that are or are not based on the stated assumptions and conclusions in this report.

This report is an evaluation of the tower structure only and does not reflect adequacy of any existing antenna mounts, mount connections, or cable mounting attachments. The analysis of these elements is outside the scope of this analysis and are assumed to be adequate for the purposes of this report and are assumed to have been installed per their manufacturer requirements. This document is not for construction purposes.

Section	1	2	3	4	
Length (ft)	36.67	41.83	54.83	44.50	
Number of Sides	12	12	12	12	
Thickness (in)	0.2190	0.3440	0.4380	0.4690	
Socket Length (ft)	4.67	5.83	7.33		
Top Dia (in)	21.2000	29.7154	39.1179	51.5330	
Bot Dia (in)	31.4600	41.4400	54.4600	64.0000	
Grade		A572-65			
Weight (lb)	2412.5	5832.9	12806.5	13757.8	34809.7



DESIGNED APPURTENANCE LOADING


TYPE	ELEVATION	TYPE	ELEVATION
GPS	168	Seismic DB-T1-6Z-8AB-0Z	158
Seismic GPS	168	Seismic Tower Section 1 - 1	156.665
DB844H90E-M	167	13' Platform w/Rails	156
DB844H90E-M	167	Seismic 13' Platform w/Rails	156
DB844H90E-M	167	Seismic (2) 2" Flex From 3 to 160 (150ft to160ft)	155
DB844H90E-M	167	Seismic (3) 1/2 From 3 to 160 (150ft to160ft)	155
DB844H90E-M	167	Seismic (11) 1 5/8 From 3 to 160 (150ft to160ft)	155
DB844H90E-M	167	Seismic (2) 1/2 From 3 to 160 (150ft to160ft)	155
LLPX310R	167	Seismic HYBRIFLEX 1 5/8 From 3 to 156 (150ft to156ft)	153
LLPX310R	167	Seismic * 146 ft * From 3 to 156 (150ft to156ft)	153
RRU	167	RRUS-12	150
RRU	167	RRUS-12	150
Seismic DB844H90E-M	167	RRUS-12	150
Seismic DB844H90E-M	167	A2	150
Seismic DB844H90E-M	167	A2	150
Seismic DB844H90E-M	167	A2	150
Seismic DB844H90E-M	167	RRUS-11	150
Seismic DB844H90E-M	167	RRUS-11	150
Seismic DB844H90E-M	167	RRUS-11	150
Seismic DB844H90E-M	167	DC6-48-60-18-8F Surge Arrestor	150
Seismic DB844H90E-M	167	Valmont Uni-Tri Bracket	150
Seismic LLPX310R	167	Seismic RRUS-12	150
Seismic LLPX310R	167	Seismic RRUS-12	150
Seismic LLPX310R	167	Seismic RRUS-12	150
Seismic RRU	167	Seismic A2	150
Seismic RRU	167	Seismic A2	150
Seismic (4) (4) 8"x2 1/2" Pipe Mount	165	Seismic RRUS-11	150
Seismic (4) (4) 8"x2 1/2" Pipe Mount	165	Seismic RRUS-11	150
Seismic (4) (4) 8"x2 1/2" Pipe Mount	165	Seismic RRUS-11	150
(4) (4) 8"x2 1/2" Pipe Mount	165	Seismic DC6-48-60-18-8F Surge Arrestor	150
(4) (4) 8"x2 1/2" Pipe Mount	165	Seismic Valmont Uni-Tri Bracket	150
VHLP2-11-DW1	164	Seismic Tower Section 1 - 2	148.33
VHLP2-11-DW1	164	7770.00	148
Seismic VHLP2-11-DW1	164	7770.00	148
Seismic VHLP2-11-DW1	164	7770.00	148
DB-T1-6Z-8AB-0Z	158	(4) (4) LGP21401 TMA	148
B5/B13 RRH	158	(4) (4) LGP21401 TMA	148
B5/B13 RRH	158	(4) (4) LGP21401 TMA	148
B5/B13 RRH	158	HPA-65R-BUU-H6	148
B2/B66A RRH	158	HPA-65R-BUU-H6	148
B2/B66A RRH	158	HPA-65R-BUU-H6	148
LPA-80060-6CF-EDIN-0	158	Seismic 7770	148
LPA-80060-6CF-EDIN-0	158	Seismic 7770	148
LPA-80060-6CF-EDIN-0	158	Seismic 7770	148
LPA-80060-6CF-EDIN-0	158	Seismic 7770	148
LPA-80060-6CF-EDIN-0	158	Seismic 7770	148
LPA-80060-6CF-EDIN-0	158	Seismic 7770	148
MT6407-77A	158	Seismic (4) (4) LGP21401 TMA	148
MT6407-77A	158	Seismic (4) (4) LGP21401 TMA	148
MT6407-77A	158	Seismic (4) (4) LGP21401 TMA	148
(2) (2) MX08FRO660	158	7770.00	148
(2) (2) MX08FRO660	158	Seismic HPA-65R-BUU-H6	148
(2) (2) MX08FRO660	158	Seismic HPA-65R-BUU-H6	148
(2) (2) MX08FRO660	158	Seismic HPA-65R-BUU-H6	148
B2/B66A RRH	158	7770.00	148
Seismic LPA-80060-6CF-EDIN-0	158	7770.00	148
Seismic LPA-80060-6CF-EDIN-0	158	Seismic 13' Platform w/Rails	146
Seismic LPA-80060-6CF-EDIN-0	158	13' Platform w/Rails	146
Seismic LPA-80060-6CF-EDIN-0	158	Seismic (2) 2" Flex From 3 to 160 (140ft to150ft)	145
Seismic LPA-80060-6CF-EDIN-0	158	Seismic (3) 1/2 From 3 to 160 (140ft to150ft)	145
Seismic MT6407-77A	158	Seismic (11) 1 5/8 From 3 to 160 (140ft to150ft)	145
Seismic MT6407-77A	158	Seismic HYBRIFLEX 1 5/8 From 3 to 156 (140ft to150ft)	145
Seismic (2) (2) MX08FRO660	158	Seismic * 146 ft * From 3 to 156 (140ft to150ft)	145
Seismic (2) (2) MX08FRO660	158	Seismic (2) #8 AWG Copper Wire From 3 to 150 (140ft to150ft)	145
Seismic B5/B13 RRH	158	Seismic (2) 1/2 From 3 to 160 (140ft to150ft)	145
Seismic B5/B13 RRH	158	Seismic RG6-Fiber From 3 to 146 (140ft to146ft)	143
Seismic B5/B13 RRH	158		
Seismic B2/B66A RRH	158		
Seismic B2/B66A RRH	158		

Infinigy Engineering
26455 Rancho Pkwy. South
Lake Forest, CA
Phone: (518) 690-0790
FAX:




Job: **BOHVN00191A**
Project: **Record ID: 31175**

Client: NSS/Dish	Drawn by: Alex Mercado	App'd:
Code: TIA-222-H	Date: 12/29/22	Scale: NTS
Path:		Dwg No. E-1

Section	1	2	3	4	
Length (ft)	36.67	41.83	54.83	44.50	
Number of Sides	12	12	12	12	
Thickness (in)	0.2190	0.3440	0.4380	0.4690	
Socket Length (ft)	4.67	5.83	7.33		
Top Dia (in)	21.2000	29.7154	39.1179	51.5330	
Bot Dia (in)	31.4600	41.4400	54.4600	64.0000	
Grade			A572-65		
Weight (lb)	2412.5	5832.9	12806.5	13757.8	34809.7



ALL REACTIONS
ARE FACTORED



MATERIAL STRENGTH

GRADE	Fy	Fu	GRADE	Fy	Fu
A572-65	65 ksi	80 ksi			

TOWER DESIGN NOTES

1. Tower is located in New Haven County, Connecticut.
2. Tower designed for Exposure B to the TIA-222-H Standard.
3. Tower designed for a 120 mph basic wind in accordance with the TIA-222-H Standard.
4. Tower is also designed for a 50 mph basic wind with 1.00 in ice. Ice is considered to increase in thickness with height.
5. Deflections are based upon a 60 mph wind.
6. Tower Risk Category II.
7. Topographic Category 1 with Crest Height of 0.00 ft
8. Seismic Note: Seismic loads generated by Seismic 3.2.3
9. Seismic Note: Seismic calculations are in accordance with TIA-222-H

Infinigy Engineering 26455 Rancho Pkwy. South Lake Forest, CA Phone: (518) 690-0790 FAX:			Job: BOHVN00191A Project: Record ID: 31175 Client: NSS/Dish Code: TIA-222-H Path:	Drawn by: Alex Mercado Date: 12/29/22 Scale: NTS Dwg No. E-1
---	--	--	---	---

tnxTower Infinigy Engineering 26455 Rancho Pkwy. South Lake Forest, CA Phone: (518) 690-0790 FAX:	Job	BOHVN00191A	Page	1 of 38
	Project	Record ID: 31175	Date	15:55:42 12/29/22
	Client	NSS/Dish	Designed by	Alex Mercado

Tower Input Data

The tower is a monopole.

This tower is designed using the TIA-222-H standard.

The following design criteria apply:

Tower is located in New Haven County, Connecticut.

Tower base elevation above sea level: 0.00 ft.

Basic wind speed of 120 mph.

Risk Category II.

Exposure Category B.

Simplified Topographic Factor Procedure for wind speed-up calculations is used.

Topographic Category: 1.

Crest Height: 0.00 ft.

Nominal ice thickness of 1.0000 in.

Ice thickness is considered to increase with height.

Ice density of 56 pcf.

A wind speed of 50 mph is used in combination with ice.

Temperature drop of 50 °F.

Deflections calculated using a wind speed of 60 mph.

Seismic Note: Seismic loads generated by Seismic 3.2.3.

Seismic Note: Seismic calculations are in accordance with TIA-222-H.

A non-linear (P-delta) analysis was used.

Pressures are calculated at each section.

Stress ratio used in pole design is 1.

Tower analysis based on target reliabilities in accordance with Annex S.

Load Modification Factors used: $K_{es}(F_w) = 0.95$, $K_{es}(t_i) = 0.85$, $K_{es}(E_v \text{ and } E_h) = 1.0$.

Maximum demand-capacity ratio is: 1.

Local bending stresses due to climbing loads, feed line supports, and appurtenance mounts are not considered.

Options


Consider Moments - Legs	Distribute Leg Loads As Uniform	Use ASCE 10 X-Brace Ly Rules
Consider Moments - Horizontals	Assume Legs Pinned	Calculate Redundant Bracing Forces
Consider Moments - Diagonals	√ Assume Rigid Index Plate	Ignore Redundant Members in FEA
Use Moment Magnification	√ Use Clear Spans For Wind Area	SR Leg Bolts Resist Compression
√ Use Code Stress Ratios	Use Clear Spans For KL/r	All Leg Panels Have Same Allowable
√ Use Code Safety Factors - Guys	Retension Guys To Initial Tension	Offset Girt At Foundation
Escalate Ice	√ Bypass Mast Stability Checks	√ Consider Feed Line Torque
Always Use Max Kz	√ Use Azimuth Dish Coefficients	Include Angle Block Shear Check
Use Special Wind Profile	√ Project Wind Area of Appurt.	Use TIA-222-H Bracing Resist. Exemption
Include Bolts In Member Capacity	Autocalc Torque Arm Areas	Use TIA-222-H Tension Splice Exemption
Leg Bolts Are At Top Of Section	Add IBC .6D+W Combination	Poles
√ Secondary Horizontal Braces Leg	√ Sort Capacity Reports By Component	√ Include Shear-Torsion Interaction
Use Diamond Inner Bracing (4 Sided)	Triangulate Diamond Inner Bracing	Always Use Sub-Critical Flow
SR Members Have Cut Ends	Treat Feed Line Bundles As Cylinder	Use Top Mounted Sockets
SR Members Are Concentric	Ignore KL/ry For 60 Deg. Angle Legs	Pole Without Linear Attachments
		Pole With Shroud Or No Appurtenances
		Outside and Inside Corner Radii Are
		Known

Monopole Base Plate Connection

Site Info	
Site Number	BOHVN00191A
Site Name	
Job No.	

Analysis Considerations	
TIA-222 Revision	H
Grout Considered:	No
l_{ar} (in)	0

Applied Loads	
Moment (kip-ft)	4505.68
Axial Force (kips)	66.95
Shear Force (kips)	38.83



Connection Properties		Analysis Results	
Anchor Rod Data		Anchor Rod Summary <i>(units of kips, kip-in)</i>	
(24) 2-1/4" \varnothing bolts (A615-75 N; Fy=75 ksi, Fu=100 ksi) on 69.83" BC		Pu_c = 131.78	ϕPn_c = 268.39 Stress Rating
Base Plate Data		Vu = 1.62	ϕVn = 120.77 49.1%
75.83" OD x 3.25" Plate (A572-60; Fy=60 ksi, Fu=75 ksi)		Mu = n/a	ϕMn = n/a Pass
Stiffener Data		Base Plate Summary	
N/A		Max Stress (ksi):	11.17 (Flexural)
Pole Data		Allowable Stress (ksi):	54
64" x 0.469" 12-sided pole (A572-65; Fy=65 ksi, Fu=80 ksi)		Stress Rating:	20.7% Pass

Pier and Pad Foundation



TIA-222 Revision: H
Tower Type: Monopole

Top & Bot. Pad Rein. Different?:	<input type="checkbox"/>
Block Foundation?:	<input type="checkbox"/>
Rectangular Pad?:	<input type="checkbox"/>

Superstructure Analysis Reactions		
Compression, P_{comp} :	66.966	kips
Base Shear, Vu_{comp} :	38.798	kips
Moment, M_u :	4505.679	ft-kips
Tower Height, H :	160	ft
BP Dist. Above Fdn, bp_{dist} :	2	in

Pier Properties		
Pier Shape:	Square	
Pier Diameter, $dpier$:	8	ft
Ext. Above Grade, E :	1	ft
Pier Rebar Size, Sc :	11	
Pier Rebar Quantity, mc :	24	
Pier Tie/Spiral Size, St :	4	
Pier Tie/Spiral Quantity, mt :	10	
Pier Reinforcement Type:	Tie	
Pier Clear Cover, cc_{pier} :	3	in

Pad Properties		
Depth, D :	14	ft
Pad Width, W_1 :	22	ft
Pad Thickness, T :	4	ft
Pad Rebar Size (Bottom dir. 2), Sp_2 :	9	
Pad Rebar Quantity (Bottom dir. 2), mp_2 :	22	
Pad Clear Cover, cc_{pad} :	3	in

Material Properties		
Rebar Grade, F_y :	60	ksi
Concrete Compressive Strength, F'_c :	3	ksi
Dry Concrete Density, δc :	150	pcf

Soil Properties		
Total Soil Unit Weight, γ :	125	pcf
Ultimate Gross Bearing, Q_{ult} :	16.000	ksf
Cohesion, C_u :	0.000	ksf
Friction Angle, ϕ :	32	degrees
SPT Blow Count, N_{blows} :		
Base Friction, μ :	0.4	
Neglected Depth, N :		ft
Foundation Bearing on Rock?	No	
Groundwater Depth, gw :	N/A	ft

Foundation Analysis Checks				
	Capacity	Demand	Rating	Check
Lateral (Sliding) (kips)	707.99	38.80	5.5%	Pass
Bearing Pressure (ksf)	12.00	4.42	36.8%	Pass
Overturning (kip*ft)	11056.92	5094.12	46.1%	Pass
Pier Flexure (Comp.) (kip*ft)	6977.15	4932.46	70.7%	Pass
Pier Compression (kip)	30551.04	193.69	0.6%	Pass
Pad Flexure (kip*ft)	4190.43	1448.86	34.6%	Pass
Pad Shear - 1-way (kips)	939.34	216.13	23.0%	Pass
Pad Shear - 2-way (Comp) (ksi)	0.164	0.028	17.1%	Pass
Flexural 2-way (Comp) (kip*ft)	7477.75	2959.47	39.6%	Pass

Structural Rating:	70.7%
Soil Rating:	46.1%

<--Toggle between Gross and Net

Location				
	Decimal Degrees	Deg	Min	Sec
Lat:	<input type="text"/>	+	<input type="text"/>	<input type="text"/>
Long:	<input type="text"/>	-	<input type="text"/>	<input type="text"/>
Code and Site Parameters				
Seismic Design Code:		TIA-222-H		
Site Soil:		D (Default)		Default
Risk Category:		II		
<u>USGS Seismic Reference</u>		S_s :	0.2010	g
		S_1 :	0.0540	g
		T_L :	6	s
Seismic Design Category Determination				
Importance Factor, I_e :		1		
Acceleration-based site coefficient, F_a :		1.6000		
Velocity-based site coefficient, F_v :		2.4000		
Design spectral response acceleration short period, S_{DS} :		0.2144		g
Design spectral response acceleration 1 s period, S_{D1} :		0.0864		g
Seismic Design Category Based on S_{DS} :		B		
Seismic Design Category Based on S_{D1} :		B		
Seismic Design Category Based on S_1 :		N/A		
Controlling Seismic Design Category:		B		



Tower Details			
Tower Type:	Tapered Monopole		
Height, h:	160	ft	
Effective Seismic Weight, W:	53.23	kips	
Amplification Factor, A _s :	1.0		2.7.8.1
Seismic Base Shear			
Response Modification Factor, R:	1.5		
Discrete Appurtenance Weight in Top 1/3 of Structure, W _u :	13.06579	kips	
W _L :	40.16088441	kips	
E:	29000.0	ksi	
g:	386.088	in/s ²	
Average Moment of Inertia, I _{avg} :	16746.67361	in ⁴	
F _a :	0.298828614	hz	
Approximate Fundamental Period Monopole, T _a :	3.3464	s	2.7.7.1.3.3
Seismic Response Coefficient, C _s	0.1429		2.7.7.1.1
Seismic Response Coefficient Max 1, C _{smax}	0.0172		2.7.7.1.1
Seismic Response Coefficient Max 2, C _{smax}	N/A		2.7.7.1.1
Seismic Response Coefficient Min 1, C _{smin}	0.0300		2.7.7.1.1
Seismic Response Coefficient Min 2, C _{smin}	N/A		2.7.7.1.1
Controlling Seismic Response Coefficient, C _{sc}	0.0300		
Seismic Base Shear, V	1.597	kips	2.7.7.1.1
Vertical Distribution Factors			
Period Related Exponent, k:	2.000		2.7.7.1.2
Sum of w _i h _i ^k	483764.15		2.7.7.1.2

ASCE 7 Hazards Report

Address:
No Address at This Location

Standard: ASCE/SEI 7-16
Risk Category: II
Soil Class: D - Default (see
Section 11.4.3)

Latitude: 41.273642
Longitude: -73.021146
Elevation: 203.93 ft (NAVD 88)



Wind

Results:

Wind Speed	120 Vmph
10-year MRI	75 Vmph
25-year MRI	85 Vmph
50-year MRI	91 Vmph
100-year MRI	98 Vmph

Data Source: ASCE/SEI 7-16, Fig. 26.5-1B and Figs. CC.2-1–CC.2-4, and Section 26.5.2

Date Accessed: Tue Dec 06 2022

Value provided is 3-second gust wind speeds at 33 ft above ground for Exposure C Category, based on linear interpolation between contours. Wind speeds are interpolated in accordance with the 7-16 Standard. Wind speeds correspond to approximately a 7% probability of exceedance in 50 years (annual exceedance probability = 0.00143, MRI = 700 years).





Site is in a hurricane-prone region as defined in ASCE/SEI 7-16 Section 26.2. Glazed openings need not be protected against wind-borne debris.

Site Soil Class:

Results:

S_S :	0.201	S_{D1} :	0.086
S_1 :	0.054	T_L :	6
F_a :	1.6	PGA :	0.113
F_v :	2.4	PGA _M :	0.177
S_{MS} :	0.321	F_{PGA} :	1.575
S_{M1} :	0.129	I_e :	1
S_{DS} :	0.214	C_v :	0.702

Seismic Design Category: B



Data Accessed:

Tue Dec 06 2022

Date Source:

USGS Seismic Design Maps based on ASCE/SEI 7-16 and ASCE/SEI 7-16 Table 1.5-2. Additional data for site-specific ground motion procedures in accordance with ASCE/SEI 7-16 Ch. 21 are available from USGS.

Results:

Ice Thickness: 1.00 in.
Concurrent Temperature: 15 F
Gust Speed 50 mph

Data Source: Standard ASCE/SEI 7-16, Figs. 10-2 through 10-8

Date Accessed: Tue Dec 06 2022

Ice thicknesses on structures in exposed locations at elevations higher than the surrounding terrain and in valleys and gorges may exceed the mapped values.

Values provided are equivalent radial ice thicknesses due to freezing rain with concurrent 3-second gust speeds, for a 500-year mean recurrence interval, and temperatures concurrent with ice thicknesses due to freezing rain. Thicknesses for ice accretions caused by other sources shall be obtained from local meteorological studies. Ice thicknesses in exposed locations at elevations higher than the surrounding terrain and in valleys and gorges may exceed the mapped values.

The ASCE 7 Hazard Tool is provided for your convenience, for informational purposes only, and is provided "as is" and without warranties of any kind. The location data included herein has been obtained from information developed, produced, and maintained by third party providers; or has been extrapolated from maps incorporated in the ASCE 7 standard. While ASCE has made every effort to use data obtained from reliable sources or methodologies, ASCE does not make any representations or warranties as to the accuracy, completeness, reliability, currency, or quality of any data provided herein. Any third-party links provided by this Tool should not be construed as an endorsement, affiliation, relationship, or sponsorship of such third-party content by or from ASCE.

ASCE does not intend, nor should anyone interpret, the results provided by this Tool to replace the sound judgment of a competent professional, having knowledge and experience in the appropriate field(s) of practice, nor to substitute for the standard of care required of such professionals in interpreting and applying the contents of this Tool or the ASCE 7 standard.

In using this Tool, you expressly assume all risks associated with your use. Under no circumstances shall ASCE or its officers, directors, employees, members, affiliates, or agents be liable to you or any other person for any direct, indirect, special, incidental, or consequential damages arising from or related to your use of, or reliance on, the Tool or any information obtained therein. To the fullest extent permitted by law, you agree to release and hold harmless ASCE from any and all liability of any nature arising out of or resulting from any use of data provided by the ASCE 7 Hazard Tool.

Exhibit E

Mount Analysis


INFINIGY®

MOUNT ANALYSIS REPORT

December 8, 2022

DISH Wireless Site Number	BOHVN00191A
Infinigy Job Number	1197-F0001-B
Client	DISH Wireless
Carrier	DISH Wireless
Site Location	525 Orange Center Road Orange, CT 06477 New Haven County 41° 16' 25.30" N NAD83 73° 1' 7.30" W NAD83
Structure Type	Monopole
Structure Height	160.0 ft
Mount Type	8.0 ft Platform
Mount Elevation	136.0 ft AGL
Structural Usage Ratio	57.2%
Overall Result	Pass

The enclosed structural analysis has been performed in accordance with the 2022 Connecticut State Building Code based on an ultimate 3-second gust wind speed of 120 mph. The evaluation criteria and applicable standards are presented in the next section of this report.



structural@nfinigy.com

CONTENTS

1. Introduction
2. Design/Analysis Parameters
3. Proposed Loading Configuration
4. Supporting Documentation
5. Results
6. Recommendations
7. Assumptions
8. Liability Waiver and Limitations
9. Calculations

December 8, 2022

1. INTRODUCTION

Infinigy performed a structural analysis on the DISH Wireless proposed telecommunication equipment supporting Platform mounted to the existing structure located at the aforementioned address. All referenced supporting documents have been obtained from the client and are assumed to be accurate and applicable to this site. The mount was analyzed using RISA 3-D version 20.0 analysis software.

2. DESIGN/ANALYSIS PARAMETERS

Wind Speed	120 mph (3-Second Gust)
Wind Speed w/ ice	50 mph (3-Second Gust) w/ 1.0" ice thickness
Adopted Code	2022 Connecticut State Building Code / 2021 IBC
Standard(s)	TIA-222-H
Risk Category	II
Exposure Category	B
Topographic Factor	1.0
Seismic Spectral Response	$S_s = 0.201 \text{ g} / S_1 = 0.054 \text{ g}$
Live Load Wind Speed	30 mph
Man Live Load at Mid/End Points	250 lbs
Man Live Load at Mount Pipes	500 lbs
Ground Elevation (HMSL)	203.93 ft

3. PROPOSED LOADING CONFIGURATION - 136.0 ft. AGL Platform

Centerline (ft)	Qty.	Appurtenance Manufacturers	Appurtenance Models
136.0	3	JMA WIRELESS	MX08FRO665-21
	3	FUJITSU	TA08025-B605
	3	FUJITSU	TA08025-B604
	1	RAYCAP	RDIDC-9181-PF-48

4. SUPPORTING DOCUMENTATION

Construction Drawings	Infinigy, Site ID: BOHVN00191A Rev.C, dated December 8, 2022
DISH Wireless Proposed Loading	DISH Wireless dated February 15, 2021
Mount Manufacturer Drawings	Site Pro 1 SPN8HR-396, dated November 21, 2014

5. RESULTS

Components	Capacity	Pass/Fail
Mount Pipe(s)	57.2%	Pass
Horizontal(s)	15.3%	Pass
Handrail(s)	22.1%	Pass
Standoff(s)	45.1%	Pass
Connection(s)	28.1%	Pass
RATING =	57.2%	Pass

Notes:

- See additional documentation in Appendix for calculations supporting the capacity consumed and detailed mount connection calculations.
- All sectors are typical.

6. RECOMMENDATIONS

Infinigy recommends installing DISH Wireless's proposed equipment loading configuration on the Platform at 136.0 ft. The installation shall be performed in accordance with the construction documents issued for this site.

If you have any questions, require additional information, or believe the actual conditions differ from those detailed in this report, please contact us immediately.

Alex Mercado, E.I.T.
Senior Project Engineer | **INFINIGY**

7. ASSUMPTIONS



The antenna mounting system was properly fabricated, installed and maintained in accordance with its original design and manufacturer's specifications.	
The configuration of antennas, mounts, and other appurtenances are as specified in the proposed loading configuration table.	
All member connections are assumed to have been designed to meet or exceed the load carrying capacity of the connected member unless otherwise specified in this report.	
The analysis will require revisions if the existing conditions in the field differ from those shown in the above-referenced documents or assumed in this analysis. No allowance was made for any damaged, missing, or rusted members.	
Steel grades have been assumed as follows, unless noted otherwise:	
Channel, Solid Round, Angle, Plate	ASTM A36 Q345
HSS (Rectangular)	ASTM A500-B GR 46 Q235-GB
HSS (Circular)	ASTM A500-B GR 42 Q235-GB
Pipe	ASTM A53-B GR 35 Q235-GB
Connection Bolts	ASTM A325
U-Bolts	ASTM A307
All bolted connections are pretensioned in accordance with Table 8.2 of the RCSC 2014 Standard.	

8. LIABILITY WAIVER AND LIMITATIONS

Our structural calculations are completed assuming all information provided to Infinigy is accurate and applicable to this site. For the purposes of calculations, we assume an overall structure condition as erected and all members and connections to be free of corrosion and/or structural defects. The structure owner and/or contractor shall verify the structure's condition prior to installation of any proposed equipment. If actual conditions differ from those described in this report, Infinigy should be notified immediately to assess the impact on the results of this report.

Our evaluation is completed using industry standard methods and procedures. The structural results, conclusions and recommendations contained in this report are proprietary and should not be used by others as their own. Infinigy is not responsible for decisions made by others that are or are not based on the stated assumptions and conclusions in this report.

This report is an evaluation of the mount structure only and does not determine the adequacy of the supporting structure, other carrier mounts or cable mounting attachments. The analysis of these elements is outside the scope of this analysis, are assumed to be adequate for the purpose of this report and to have been installed per their manufacturer requirements. This document is not for construction purposes.



Infinigy Engineering



AM

BOHVN00191A

RENDERED - 1

Dec 08, 2022

BOHVN00191A_loaded.r3d



Program Inputs

PROJECT INFORMATION		
Site Name:	BOHVN00191A	
Carrier:	DISH Wireless	
Engineer:	Alex Mercado	

SITE INFORMATION		
Risk Category:	II	
Exposure Category:	B	
Topo Factor Procedure:	Method 1, Category 1	
Site Class:	D - Stiff Soil (Assumed)	
Ground Elevation:	203.93	ft *Rev H

MOUNT INFORMATION		
Mount Type:	Platform	
Num Sectors:	3	
Centerline AGL:	136.00	ft
Tower Height AGL:	160.00	ft

TOPOGRAPHIC DATA		
Topo Feature:	N/A	
Slope Distance:	N/A	ft
Crest Distance:	N/A	ft
Crest Height:	N/A	ft

FACTORS		
Directionality Fact. (K_d):	0.950	
Ground Ele. Factor (K_e):	0.993	*Rev H Only
Rooftop Speed-Up (K_s):	1.000	*Rev H Only
Topographic Factor (K_{zt}):	1.000	
Height Esc. Fact. (K_{iz}):	1.152	
Gust Effect Factor (G_f):	1.000	
Shielding Factor (K_a):	0.900	
Velocity Pressure Co. (K_z):	1.079	(Mount Elev)

CODE STANDARDS		
Building Code:	2021 IBC	
TIA Standard:	TIA-222-H	
ASCE Standard:	ASCE 7-16	

WIND AND ICE DATA		
Ultimate Wind (V_{ult}):	120	mph
Design Wind (V):	N/A	mph
Ice Wind (V_{ice}):	50	mph
Base Ice Thickness (t_i):	1	in
Radial Ice Thickness (t_{iz}):	1.152	in
Flat Pressure:	75.017	psf
Round Pressure:	45.010	psf
Ice Wind Pressure:	7.814	psf



SEISMIC DATA		
Short-Period Accel. (S_s):	0.201	g
1-Second Accel. (S_1):	0.054	g
Short-Period Design (S_{DS}):	0.214	
1-Second Design (S_{D1}):	0.086	
Short-Period Coeff. (F_a):	1.600	
1-Second Coeff. (F_v):	2.400	
Amplification Factor (A_s):	3.000	
Response Mod. Coeff. (R):	2.000	
Seismic Importance (I_e):	1.000	
Seismic Response Co. (C_s):	0.107	
Total App. Weight:	225.210	lb
Total Shear Force (V_s):	24.143	lb
Hor. Seismic Load (E_h):	24.143	lb
Vert. Seismic Load (E_v):	9.657	lb *

*For reference only. Per TIA rev H section 16.7, E_v is not applicable to mounts

Program Inputs



Infinigy Load Calculator V2.3.3

[illegible]

INFINIGY⁸

Bolt Calculation Tool, V1.6.4

PROJECT DATA		
Site Name:	BOHVN00191A	
Site Number:	BOHVN00191A	
Connection Description:	Platform to Tower	

ENVELOPE BOLT LOADS		
(LC7 S2) Bolt Tension:	5712.02	lbs
(LC181 S3) Bolt Shear:	1268.01	lbs


MAX BOLT USAGE LOADS ¹		
Bolt Tension:	5712.02	lbs
Bolt Shear:	562.20	lbs

BOLT PROPERTIES		
Bolt Type:	Bolt	-
Bolt Diameter:	0.625	in
Bolt Grade:	A325	-
# of Bolts:	4	-
Threads Excluded?	No	-

¹ Max bolt usage loads correspond to Load combination #7 on member S2 in RISA-3D, which causes the maximum demand on the bolts.

Member Information	
I nodes of S1, S3, S2,	

BOLT CHECK		
Tensile Strength	20340.15	
Shear Strength	13805.83	
Max Tensile Usage	28.1%	
Max Shear Usage	9.2%	
Interaction Check (Max Usage)	0.08	≤1.05
Result	Pass	





ASCE 7 Hazards Report

Address:
No Address at This Location

Standard: ASCE/SEI 7-16
Risk Category: II
Soil Class: D - Default (see
Section 11.4.3)

Latitude: 41.273642
Longitude: -73.021146
Elevation: 203.93 ft (NAVD 88)



Wind

Results:

Wind Speed	120 Vmph
10-year MRI	75 Vmph
25-year MRI	85 Vmph
50-year MRI	91 Vmph
100-year MRI	98 Vmph

Data Source: ASCE/SEI 7-16, Fig. 26.5-1B and Figs. CC.2-1–CC.2-4, and Section 26.5.2

Date Accessed: Tue Dec 06 2022

Value provided is 3-second gust wind speeds at 33 ft above ground for Exposure C Category, based on linear interpolation between contours. Wind speeds are interpolated in accordance with the 7-16 Standard. Wind speeds correspond to approximately a 7% probability of exceedance in 50 years (annual exceedance probability = 0.00143, MRI = 700 years).





Site is in a hurricane-prone region as defined in ASCE/SEI 7-16 Section 26.2. Glazed openings need not be protected against wind-borne debris.

Site Soil Class:

Results:

S_S :	0.201	S_{D1} :	0.086
S_1 :	0.054	T_L :	6
F_a :	1.6	PGA :	0.113
F_v :	2.4	PGA _M :	0.177
S_{MS} :	0.321	F_{PGA} :	1.575
S_{M1} :	0.129	I_e :	1
S_{DS} :	0.214	C_v :	0.702

Seismic Design Category: B



Data Accessed:

Tue Dec 06 2022

Date Source:

USGS Seismic Design Maps based on ASCE/SEI 7-16 and ASCE/SEI 7-16 Table 1.5-2. Additional data for site-specific ground motion procedures in accordance with ASCE/SEI 7-16 Ch. 21 are available from USGS.

Results:

Ice Thickness: 1.00 in.
Concurrent Temperature: 15 F
Gust Speed 50 mph

Data Source: Standard ASCE/SEI 7-16, Figs. 10-2 through 10-8

Date Accessed: Tue Dec 06 2022

Ice thicknesses on structures in exposed locations at elevations higher than the surrounding terrain and in valleys and gorges may exceed the mapped values.

Values provided are equivalent radial ice thicknesses due to freezing rain with concurrent 3-second gust speeds, for a 500-year mean recurrence interval, and temperatures concurrent with ice thicknesses due to freezing rain. Thicknesses for ice accretions caused by other sources shall be obtained from local meteorological studies. Ice thicknesses in exposed locations at elevations higher than the surrounding terrain and in valleys and gorges may exceed the mapped values.

The ASCE 7 Hazard Tool is provided for your convenience, for informational purposes only, and is provided "as is" and without warranties of any kind. The location data included herein has been obtained from information developed, produced, and maintained by third party providers; or has been extrapolated from maps incorporated in the ASCE 7 standard. While ASCE has made every effort to use data obtained from reliable sources or methodologies, ASCE does not make any representations or warranties as to the accuracy, completeness, reliability, currency, or quality of any data provided herein. Any third-party links provided by this Tool should not be construed as an endorsement, affiliation, relationship, or sponsorship of such third-party content by or from ASCE.

ASCE does not intend, nor should anyone interpret, the results provided by this Tool to replace the sound judgment of a competent professional, having knowledge and experience in the appropriate field(s) of practice, nor to substitute for the standard of care required of such professionals in interpreting and applying the contents of this Tool or the ASCE 7 standard.

In using this Tool, you expressly assume all risks associated with your use. Under no circumstances shall ASCE or its officers, directors, employees, members, affiliates, or agents be liable to you or any other person for any direct, indirect, special, incidental, or consequential damages arising from or related to your use of, or reliance on, the Tool or any information obtained therein. To the fullest extent permitted by law, you agree to release and hold harmless ASCE from any and all liability of any nature arising out of or resulting from any use of data provided by the ASCE 7 Hazard Tool.

Exhibit F

Power Density/RF Emissions Report



Radio Frequency Emissions Analysis Report



Site ID: BOHVN00191A

525 Orange Center Road
Orange, CT 06477

December 30, 2022

Fox Hill Telecom Project Number: 222142

Site Compliance Summary	
Compliance Status:	COMPLIANT
Site total MPE% of FCC general population allowable limit:	9.18 %



December 30, 2022

Dish Wireless
5701 South Santa Fe Drive
Littleton, CO 80120

Emissions Analysis for Site: **BOHVN00191A**

Fox Hill Telecom, Inc (“Fox Hill”) was directed to analyze the proposed radio installation for Dish Wireless, LLC (Dish) facility located at **525 Orange Center Road, Orange, CT**, for the purpose of determining whether the emissions from the Proposed Dish radio and antenna installation located on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter ($\mu\text{W}/\text{cm}^2$). The number of $\mu\text{W}/\text{cm}^2$ calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits, therefore it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) – (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general population may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general population would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

Population exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter ($\mu\text{W}/\text{cm}^2$). The general population exposure limit for the 600 MHz band is approximately 400 $\mu\text{W}/\text{cm}^2$. The general population exposure limit for the 1900 MHz (PCS) and 2100 MHz (AWS / AWS-4) bands is 1000 $\mu\text{W}/\text{cm}^2$. Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.



Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure. Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.



CALCULATIONS

Calculations were performed for the proposed upgrades to the Dish Wireless antenna facility located at **525 Orange Center Road, Orange, CT**, using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65 for far field modeling calculations.

In OET-65, plane wave power densities in the Far Field of an antenna are calculated by considering antenna gain and reflective waves that would contribute to exposure.

Since the radiation pattern of an antenna has developed in the **Far Field** region the power gain in specific directions needs to be considered in exposure predictions to yield an Effective Radiated Power (ERP) in each specific direction from the antenna. Also, since the vertical radiation pattern of the antenna is considered, the exposure calculations would most likely be reduced significantly at ground level, resulting in a more realistic estimate of the actual exposure levels. To determine a worst-case scenario at each point along the calculation radials, each point was calculated using the antenna gain value at each angle of incident and compared against the result using an isotropic radiator at the antenna height with the greater of the two used to yield the more pessimistic far field value for each point along the calculation radial.

Additionally, to model a truly "worst case" prediction of exposure levels at or near a surface, such as at ground-level or on a rooftop, reflection off the surface of antenna radiation power can be assumed, resulting in a potential 1.6 times increase in power density in calculating far field power density values.

With these factors Considered, the worst case **Far Field prediction model** utilized in this analysis is determined by the following equation:

Equation 9 per FCC OET65 for Far Field Modeling

$$S = \frac{33.4 \text{ ERP}}{R^2}$$

S = Power Density (in $\mu\text{W}/\text{cm}^2$)

ERP = Effective Radiated Power from antenna (watts)

R = Distance from the antenna (meters)

Predicted far field power density values for all carriers identified in this report were calculated 6 feet above the ground level and are displayed as a percentage of the applicable FCC standards. All emissions values for other carriers were calculated using the same Far Field model outlined above, using industry standard radio configurations and frequency band selection based upon available licenses in this geographic area for emissions contribution estimates.



For each Dish sector the following channel counts, frequency bands and power levels were utilized as shown in *Table 1*:

Technology	Frequency Band	Channel Count	Transmit Power per Channel (W)
5G	n71 (600 MHz)	4	61.5
5G	n70 (AWS-4 / 1995-2020)	4	40
5G	n66 (AWS-4 / 2180-2200)	4	40

Table 1: Channel Data Table



The following **Dish** antennas listed in *Table 2* were used in the modeling for transmission in the 600 MHz (n71) frequency band, and the 2100 MHz (AWS 4) frequency bands at 1995-2020 MHz (n70) and 2180-2200 MHz (n66). This is based on feedback from Dish regarding anticipated antenna selection. Maximum gain values for all antennas are listed in the Inventory and Power Data table below.

Sector	Antenna Number	Antenna Make / Model	Antenna Centerline (ft)
A	1	JMA MX08FRO665-21	136
B	1	JMA MX08FRO665-21	136
C	1	JMA MX08FRO665-21	136

Table 2: Antenna Data

All calculations were done with respect to uncontrolled / general population threshold limits.



RESULTS

Per the calculations completed for the proposed **Dish** configurations *Table 3* shows resulting emissions power levels and percentages of the FCC's allowable general population limit.

Antenna ID	Antenna Make / Model	Frequency Bands	Antenna Gain (dBd)	Channel Count	Total TX Power (W)	ERP (W)	MPE %
Antenna A1	JMA MX08FRO665-21	n71 (600 MHz) / n70 (AWS-4 / 1995-2020) / n66 (AWS-4 / 2180-2200)	11.45 / 16.15 / 16.65	12	566	17,426.72	2.01
Sector A Composite MPE%							2.01
Antenna B1	JMA MX08FRO665-21	n71 (600 MHz) / n70 (AWS-4 / 1995-2020) / n66 (AWS-4 / 2180-2200)	11.45 / 16.15 / 16.65	12	566	17,426.72	2.01
Sector B Composite MPE%							2.01
Antenna C1	JMA MX08FRO665-21	n71 (600 MHz) / n70 (AWS-4 / 1995-2020) / n66 (AWS-4 / 2180-2200)	11.45 / 16.15 / 16.65	12	566	17,426.72	2.01
Sector C Composite MPE%							2.01

Table 3: Dish Emissions Levels



The Following table (*Table 4*) shows all additional carriers on site and their emissions contribution estimates, along with the newly calculated **Dish** far field emissions contributions per this report. FCC OET 65 specifies that for carriers utilizing directional antennas that the highest recorded sector value be used for composite site emissions values due to their greatly reduced emissions contributions in the directions of the adjacent sectors. For this site, all three sectors have the same configuration yielding the same results on all three sectors. *Table 5* below shows a summary for each **Dish** Sector as well as the composite emissions value for the site.

Site Composite MPE%	
Carrier	MPE%
Dish – Max Per Sector Value	2.01 %
AT&T	3.25 %
Verizon Wireless	1.73 %
Clearwire	0.07 %
T-Mobile	2.12 %
Site Total MPE %:	9.18 %

Table 4: All Carrier MPE Contributions

Dish Sector A Total:	2.01 %
Dish Sector B Total:	2.01 %
Dish Sector C Total:	2.01 %
Site Total:	9.18 %

Table 5: Site MPE Summary



Table 6 below details a breakdown by frequency band and technology for the MPE power values for the maximum calculated **Dish** sector(s). For this site, all three sectors have the same configuration yielding the same results on all three sectors.

Dish _ Frequency Band / Technology Max Power Values (Per Sector)	# Channels	Watts ERP (Per Channel)	Height (feet)	Total Power Density ($\mu\text{W}/\text{cm}^2$)	Frequency (MHz)	Allowabl e MPE ($\mu\text{W}/\text{cm}^2$)	Calculated % MPE
Dish n71 (600 MHz) 5G	4	858.77	136	5.32	n71 (600 MHz)	400	1.33%
Dish n70 (AWS-4 / 1995-2020) 5G	4	1,648.39	136	3.40	n70 (AWS-4 / 1995-2020)	1000	0.34%
Dish n66 (AWS-4 / 2180-2200) 5G	4	1,849.52	136	3.40	n66 (AWS-4 / 2180-2200)	1000	0.34%
						Total:	2.01%

Table 6: Dish Maximum Sector MPE Power Values



Summary

All calculations performed for this analysis yielded results that were **within** the allowable limits for general population exposure to RF Emissions.

The anticipated maximum composite contributions from the Dish facility as well as the site composite emissions value with regards to compliance with FCC's allowable limits for general population exposure to RF Emissions are shown here:

Dish Sector	Power Density Value (%)
Sector A:	2.01 %
Sector B:	2.01 %
Sector C:	2.01 %
Dish Maximum Total (per sector):	2.01 %
Site Total:	9.18 %
Site Compliance Status:	COMPLIANT

The anticipated composite emissions value for this site, assuming all carriers present, is **9.18 %** of the allowable FCC established general population limit sampled at the ground level. This is based upon the far field calculations performed for all carriers identified in this report.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.

Scott Heffernan
Principal RF Engineer
Fox Hill Telecom, Inc
Worcester, MA 01609
(978)660-3998

Exhibit G

Letter of Authorization



Dish Wireless, LLC Letter of Authorization

CONNECTICUT SITING COUNCIL

Attn: Melanie A. Bachman Executive
Director Connecticut Siting Council
10 Franklin Square
New Britain, CT 06051

Re: Tower Share Application

**Dish Wireless, LLC telecommunications site at:
525 Orange Center Road, Orange, CT 06477**

The owner of **525 Orange Center Road, Orange, CT 06477**, The Town of Orange hereby authorizes DISH Wireless LLC, including their Agent, Northeast Site Solutions, LLC to act as our Agent in the processing of all zoning applications, building permits and approvals through the CONNECTICUT SITING COUNCIL for the existing wireless communications site described below:

**Customer Site ID: BOHVN00191A
525 Orange Center Road, Orange, CT**

Town of Orange

By: 





Title: First Selectman

Printed Name: James M. Zeoli

1-31-2023

Exhibit H

Recipient Mailings

 UNITED STATES POSTAL SERVICE®		Click-N-Ship®	
P		<small>usps.com</small> US POSTAGE Flat Rate Env U.S. POSTAGE PAID <small>Click-N-Ship®</small>	
01/31/2023		Mailed from 01566 986767264483899	
PRIORITY MAIL®		Expected Delivery Date: 02/02/23 Ref#: DS-00191A 0000	
DEBORAH CHASE NORTHEAST SITE SOLUTIONS STE 1 420 MAIN ST STURBRIDGE MA 01566-1359		 JAMES M ZEOLI FIRST SELECTMAN 617 ORANGE CENTER RD ORANGE CT 06477-2432	
		USPS TRACKING #	
9405 5036 9930 0469 4303 48			
Electronic Rate Approved #038555749			

Cut on dotted line.

Instructions




- Each Click-N-Ship® label is unique. Labels are to be used as printed and used only once. DO NOT PHOTO COPY OR ALTER LABEL.
- Place your label so it does not wrap around the edge of the package.
- Adhere your label to the package. A self-adhesive label is recommended. If tape or glue is used, DO NOT TAPE OVER BARCODE. Be sure all edges are secure.
- To mail your package with PC Postage®, you may schedule a Package Pickup online, hand to your letter carrier, take to a Post Office™, or drop in a USPS collection box.
- Mail your package on the "Ship Date" you selected when creating this label.

Click-N-Ship® Label Record

USPS TRACKING # : 9405 5036 9930 0469 4303 48	
Trans. #: 581689875 Print Date: 01/31/2023 Ship Date: 01/31/2023 Expected Delivery Date: 02/02/2023	Priority Mail® Postage: \$9.65 Total: \$9.65
From: DEBORAH CHASE NORTHEAST SITE SOLUTIONS STE 1 420 MAIN ST STURBRIDGE MA 01566-1359	
To: JAMES M ZEOLI FIRST SELECTMAN 617 ORANGE CENTER RD ORANGE CT 06477-2432	
Ref#: DS-00191A	
<small>* Retail Pricing Priority Mail rates apply. There is no fee for USPS Tracking® service on Priority Mail service with use of this electronic rate shipping label. Refunds for unused postage paid labels can be requested online 30 days from the print date.</small>	



Thank you for shipping with the United States Postal Service!
 Check the status of your shipment on the USPS Tracking® page at usps.com

 Click-N-Ship®		P
USPS.com 9405 5036 9930 0469 4303 79 0096 5000 0020 6477 US POSTAGE Flat Rate Env U.S. POSTAGE PAID Click-N-Ship®		01/31/2023 Mailed from 01566 986767264480776
PRIORITY MAIL®		
DEBORAH CHASE NORTHEAST SITE SOLUTIONS STE 1 420 MAIN ST STURBRIDGE MA 01566-1359		Expected Delivery Date: 02/02/23 Ref#: DS-000191A 0000
 JACK DEMIRJIAN ZONING ADMINISTRATOR & ENFORCEMENT 617 ORANGE CENTER RD ORANGE CT 06477-2432		C010
USPS TRACKING #		
		
9405 5036 9930 0469 4303 79		
Electronic Rate Approved #038555749		

✂ ————— Cut on dotted line.

Instructions

- Each Click-N-Ship® label is unique. Labels are to be used as printed and used only once. DO NOT PHOTO COPY OR ALTER LABEL.
- Place your label so it does not wrap around the edge of the package.
- Adhere your label to the package. A self-adhesive label is recommended. If tape or glue is used, DO NOT TAPE OVER BARCODE. Be sure all edges are secure.
- To mail your package with PC Postage®, you may schedule a Package Pickup online, hand to your letter carrier, take to a Post Office™, or drop in a USPS collection box.
- Mail your package on the "Ship Date" you selected when creating this label.

Click-N-Ship® Label Record

USPS TRACKING # : 9405 5036 9930 0469 4303 79	
Trans. #: 581689875 Print Date: 01/31/2023 Ship Date: 01/31/2023 Expected Delivery Date: 02/02/2023	Priority Mail® Postage: \$9.65 Total: \$9.65
From: DEBORAH CHASE NORTHEAST SITE SOLUTIONS STE 1 420 MAIN ST STURBRIDGE MA 01566-1359	
To: JACK DEMIRJIAN ZONING ADMINISTRATOR & ENFORCEMENT OFFICER 617 ORANGE CENTER RD ORANGE CT 06477-2432	
Ref#: DS-000191A	
<small>* Retail Pricing Priority Mail rates apply. There is no fee for USPS Tracking® service on Priority Mail service with use of this electronic rate shipping label. Refunds for unused postage paid labels can be requested online 30 days from the print date.</small>	



Thank you for shipping with the United States Postal Service!
 Check the status of your shipment on the USPS Tracking® page at usps.com

DISH - BOHVN00191A



**UNITED STATES
POSTAL SERVICE.**

LINCOLN MALL
560 LINCOLN ST STE 8
WORCESTER, MA 01605-1925
(800)275-8777

02/01/2023

11:34 AM

Product	Qty	Unit Price	Price
---------	-----	---------------	-------

Prepaid Mail	1		\$0.00
--------------	---	--	--------

Orange, CT 06477

Weight: 0 lb 14.90 oz

Acceptance Date:

Wed 02/01/2023

Tracking #:

9405 5036 9930 0469 4303 48

Prepaid Mail	1		\$0.00
--------------	---	--	--------

Orange, CT 06477

Weight: 0 lb 14.90 oz

Acceptance Date:

Wed 02/01/2023

Tracking #:

9405 5036 9930 0469 4303 79

Grand Total:			\$0.00
--------------	--	--	--------