



Northeast Site Solutions  
Denise Sabo  
4 Angela's Way, Burlington CT 06013  
203-435-3640  
[denise@northeastsitesolutions.com](mailto:denise@northeastsitesolutions.com)

September 17, 2021

Members of the Siting Council  
Connecticut Siting Council  
Ten Franklin Square  
New Britain, CT 06051

RE: Tower Share Application  
171 Town Hill Road, Plymouth, CT 06279  
Latitude: 41.668389  
Longitude: 73.019956  
Site# 826768\_Crown\_Dish

Dear Ms. Bachman:

This letter and attachments are submitted on behalf of Dish Wireless LLC. Dish Wireless LLC plans to install antennas and related equipment to the tower site located at 171 Town Hill Road, Plymouth, Connecticut.

Dish Wireless LLC proposes to install three (3) 600/1900 5G MHz antenna and six (6) RRUs, at the 132-foot level of the existing 169-foot monopole tower, one (1) Fiber cables will also be installed. Dish Wireless LLC equipment cabinets will be placed within 7x5 lease area. Included are plans by Infinigy, dated August 24, 2021 Exhibit C. Also included is a structural analysis prepared by Crown Castle, dated June 6, 2021, confirming that the existing tower is structurally capable of supporting the proposed equipment. Attached as Exhibit D. The facility was approved by the Town of Plymouth Planning and Zoning Commission on June 22, 2000 by way of a Special Permit issuance. Please see attached.

Please accept this letter as notification pursuant to Regulations of Connecticut State Agencies 16-50aa, of Dish Wireless LLC intent to share a telecommunications facility pursuant to R.C.S.A. 16-50j-88. In accordance with R.C.S.A., a copy of this letter is being sent to David V. Merchant, Mayor, for the Town of Plymouth, Margus T. Laan, Planning Director, as well as the tower owner (Crown Castle) and property owner (Terryville Country Fair Inc)

The planned modifications of the facility fall squarely within those activities explicitly provided for in R.C.S.A. 16-50j-89.

1. The proposed modification will not result in an increase in the height of the existing structure. The top of the tower is 169-feet; Dish Wireless LLC proposed antennas will be located at a center line height of 132-feet.
2. The proposed modifications will not result in the increase of the site boundary as depicted on the attached site plan.



3. The proposed modifications will not increase noise levels at the facility by six decibels or more, or to levels that exceed local and state criteria. The incremental effect of the proposed changes will be negligent.

4. The operation of the proposed antennas will not increase radio frequency emissions at the facility to a level at or above the Federal Communications Commission safety standard. As indicated in the attached power density calculations, the combined site operations will result in a total power density of 26.88% as evidenced by Exhibit F.

Connecticut General Statutes 16-50aa indicates that the Council must approve the shared use of a telecommunications facility provided it finds the shared use is technically, legally, environmentally, and economically feasible and meets public safety concerns. As demonstrated in this letter, Dish Wireless LLC respectfully indicates that the shared use of this facility satisfies these criteria.

A. Technical Feasibility. The existing monopole has been deemed structurally capable of supporting Dish Wireless LLC proposed loading. The structural analysis is included as Exhibit D.

B. Legal Feasibility. As referenced above, C.G.S. 16-50aa has been authorized to issue orders approving the shared use of an existing tower such as this support tower in Plymouth. Under the authority granted to the Council, an order of the Council approving the requested shared use would permit Dish Wireless LLC to obtain a building permit for the proposed installation. Further, a Letter of Authorization is included as Exhibit G, authorizing Dish Wireless LLC to file this application for shared use.

C. Environmental Feasibility. The proposed shared use of this facility would have a minimal environmental impact. The installation of Dish Wireless LLC equipment at the 132-foot level of the existing 169-foot tower would have an insignificant visual impact on the area around the tower. Dish Wireless LLC ground equipment would be installed within the existing facility compound. Dish Wireless LLC shared use would therefore not cause any significant alteration in the physical or environmental characteristics of the existing site. Additionally, as evidenced by Exhibit F, the proposed antennas would not increase radio frequency emissions to a level at or above the Federal Communications Commission safety standard.

D. Economic Feasibility. Dish Wireless LLC will be entering into an agreement with the owner of this facility to mutually agreeable terms. As previously mentioned, the Letter of Authorization has been provided by the owner to assist Dish Wireless LLC with this tower sharing application.

E. Public Safety Concerns. As discussed above, the tower is structurally capable of supporting Dish Wireless LLC proposed loading. Dish Wireless LLC is not aware of any public safety concerns relative to the proposed sharing of the existing tower. Dish Wireless LLC intentions of providing new and improved wireless service through the shared use of this facility is expected to enhance the safety and welfare of local residents and individuals traveling through Plymouth.

Sincerely,

*Denise Sabo*

Denise Sabo  
Mobile: 203-435-3640  
Fax: 413-521-0558  
Office: 4 Angela's Way, Burlington CT 06013  
Email: [denise@northeastsitesolutions.com](mailto:denise@northeastsitesolutions.com)



Attachments

cc: David V. Merchant, Mayor  
Town of Plymouth Town Hall – Mayor’s Office  
80 Main Street Terryville, CT 06786

Margus T. Laan, Planning Director  
Town of Plymouth Town Hall – Land Use Office  
80 Main Street Terryville, CT 06786

Terryville Country Fair Inc.  
171 Town Hill Road PO Box 72 Terryville, CT 06786

Crown Castle, Tower Owner

# Exhibit A

## **Original Facility Approval**

## TOWN OF PLYMOUTH, CONNECTICUT

ZONING PERMIT NO. 10-201  
 Fee Paid: \$ 100.00 A 058194  
 Date: July 5 19 2000

Permission is hereby granted to Terryville Lions Club & Omnipoint  
 to erect a Telecommunication Tower on the east side of Town Hall Rd (fair grounds)  
 as follows: Size \_\_\_\_\_ ft. long, \_\_\_\_\_ ft. wide, \_\_\_\_\_ stories high; distance from  
 road center line \_\_\_\_\_ ft.; distance from each lot line: E \_\_\_\_\_ ft.; W \_\_\_\_\_ ft.; S \_\_\_\_\_ ft.;  
 N \_\_\_\_\_ ft.; for the use of the facility as a Telecommunication Tower

as approved by Pt 2 on 6/22/2000 with stipulations

PLANNING AND ZONING COMMISSION, TOWN OF PLYMOUTH  
 CONNECTICUT

A see approved Site Plan

dated 3/2000  
 3/8/2000  
 3/16/2000

Received  
 6/22/2000

Ronald J Mounelle  
 Agent of the Planning and Zoning Commission

The recipient of this permit accepts this permit on the condition that he, as owner or as representing the owner, agrees to comply with all applicable ordinances and regulations of the Town of Plymouth and the State of Connecticut regarding the use, occupancy and type of activity to be instituted. It is furthermore understood that the facility can not be used until a Certificate of Occupancy has been issued by the Planning and Zoning Commission and that any change of use similarly does require a new Certificate of Occupancy. Before a Certificate of Occupancy will be issued a plot plan drawn to a scale of 1" = 50' prepared and certified by a licensed engineer or land surveyor must be submitted to the Planning and Zoning Commission showing all boundaries of the line of any public or private right-of-way, sanitary facilities and water supply. This permit shall be valid for one year.

**MOTION:** Gaye Zukauskas made a motion to add Town Hill Road/Lions back on the agenda. Steve Panasuk seconded. **VOTE:** S. Panasuk – Aye, G. Zukauskas – Aye, W. Radke – Aye and Chairman Herzing so voted.

**MOTION:** Patrick Herzing made a motion for a 5-minute recess at 9:23 p.m. **VOTE:** All in favor.

Chairman Patrick Herzing called the meeting back to order at 9:28 p.m.

**Town Hill Road/Lions - Special Permit – Telecommunication Tower – Omnipoint –**

**MOTION:** Gaye Zukauskas made a motion to approve the application for the telecommunication tower-Town Hill Road-Lions Club and Omnipoint-State ID #CT-11417C consisting of 5 sheets, cover dated 6/20/00, vicinity plan dated 3/8/00, sheet C-1, C-2 and C-3 all dated 6/20/00 with the only stipulation that Plymouth emergency services to have free access as needed with no charge to the Town. Any additional carriers to come in for a special permit. Bond to be set by Public Works in the event of abandonment. Steve Panasuk seconded. **VOTE:** S. Panasuk – Aye, G. Zukauskas – Aye, W. Radke – Aye and Chairman Herzing so voted.

**11. Town Hill/Washington Roads – Pines Subdivision – Bond Reduction – CT Water Co. –**

CT Water Co. has sold most of the lots in the subdivision to Mr. Zappone. Discussion was had. **MOTION:** Wayne Radke made a motion to reduce the bond as requested and get a new bond from Mr. Zappone before reduction of CT Water Co.'s bond. Gaye Zukauskas seconded. **VOTE:** S. Panasuk – Aye, G. Zukauskas – Aye, W. Radke – Aye and Chairman Herzing so voted.

**16. Plymouth Housing Authority – Section 8-24 Review – Yefko Property –** Mr. Kuehn read the memo dated 6/21 from Anthony A. Lorenzetti, PE into the record. He is in support of this proposal. It would be a solution to the parking situation at Gosinski Park. Half of it would be for off street parking and the other half for a minimum 20,000 sq. ft. residential parcel for a low/moderate income housing. The resolution should be 39,100 not 29,100. Mr. Kuehn read the resolution into the record. **MOTION:** Gaye Zukauskas made a motion to accept the resolution for an 8-24 review. Wayne Radke seconded. **VOTE:** S. Panasuk – Aye, G. Zukauskas – Aye, W. Radke – Aye and Chairman Herzing so voted.

**18. Land Use Corner –** Gaye strikes again. The final revision has been faxed to the Plymouth News. Gaye suggested that Mr. Kuehn do one next month on industrial property.

**21. Correspondence from ZBA Chairman Mike Cole –** Patrick Herzing will call Mike Cole and get a time set up – probably in September to get together to discuss the zoning regulations. It was suggested to have Mike come up with an agenda of issues to look at ahead of time.

**22. Proposed ordinance for zoning violations –** The Town Council tabled this item at their last meeting so no public hearing has been scheduled. It recommends a \$150 fine per violation. Maybe we can not issue any permits to people who have not finished and cleaned up their last items.

**STAFF COMMENTS** –Mr. Kuehn informed the Commission that 36 signs will be going up in the industrial park for the public hearing.

# Exhibit B

## **Property Card**



Town of Plymouth  
Property Listing Report

Parcel ID 048-073B-012

Account

00041600

## Property Information

Owner	TERRYVILLE COUNTRY FAIR INC
Address	171 TOWN HILL RD
Mailing Address	PO BOX 72 TERRYVILLE , CT 06786
Land Use	-
Land Class	E

Census Tract	4254
Neighborhood	103
Zoning	RA1
Acreage	20.46
Utilities	
Lot Setting/ Desc	/ 1

## Photo



## PARCEL VALUATIONS (Assessed value = 70% of Appraised Value)

	Appraised	Assessed
Buildings	83250	
Outbuildings		
Improvements		
Extras		
Land	0	
Total	1042260	729580
Previous		

## Construction Details

Year Built	
Stories	
Building Style	
Building Use	
Building Condition	
Total Rooms	
Bedrooms	
Full Bathrooms	
Half Bathrooms	
Bath Style	
Kitchen Style	
Roof Style	
Roof Cover	

### EXTERIOR WALLS:

Primary	
Secondary	

### INTERIOR WALLS:

Primary	
Secondary	

### FLOORS:

Primary	
Secondary	

### HEATING/AC:

Heating Type	
Heating Fuel	
AC Type	

### BUILDING AREA:

Effective Building Area	
Gross Building Area	
Total Living Area	

### SALES HISTORY:


Sale Date	0
Sale Price	0
Book/ Page	152/643



# Town of Plymouth, Connecticut. Assessment Parcel Map

GIS Link 048-073B-012

Address: 171 TOWN HILL RD



1 inch = 200 feet



Disclaimer: This map is for informational purposes only. All information is subject to verification by any user. The Town of Plymouth and its mapping contractors assume no legal responsibility for the information contained herein.

Map Produced: November 2018

# Exhibit C

## **Construction Drawings**



DISH Wireless L.L.C. SITE ID:

**BOHVN00014A**

DISH Wireless L.L.C. SITE ADDRESS:

**171 TOWN HILL ROAD  
PLYMOUTH, CT 06786**

#### CONNECTICUT CODE COMPLIANCE

ALL WORK SHALL BE PERFORMED AND MATERIALS INSTALLED IN ACCORDANCE WITH THE CURRENT EDITIONS OF THE FOLLOWING CODES AS ADOPTED BY THE LOCAL GOVERNING AUTHORITIES. NOTHING IN THESE PLANS IS TO BE CONSTRUED TO PERMIT WORK NOT CONFORMING TO THESE CODES:

CODE TYPE	CODE
BUILDING	2018 CT STATE BUILDING CODE/2015 IBC W/ CT AMENDMENTS
MECHANICAL	2018 CT STATE BUILDING CODE/2015 IMC W/ CT AMENDMENTS
ELECTRICAL	2018 CT STATE BUILDING CODE/2017 NEC W/ CT AMENDMENTS

#### SHEET INDEX

SHEET NO.	SHEET TITLE
T-1	TITLE SHEET
A-1	OVERALL AND ENLARGED SITE PLAN
A-2	ELEVATION, ANTENNA LAYOUT AND SCHEDULE
A-3	EQUIPMENT PLATFORM AND H-FRAME DETAILS
A-4	EQUIPMENT DETAILS
A-5	EQUIPMENT DETAILS
A-6	EQUIPMENT DETAILS
E-1	ELECTRICAL/FIBER ROUTE PLAN AND NOTES
E-2	ELECTRICAL DETAILS
E-3	ELECTRICAL ONE-LINE, FAULT CALCS & PANEL SCHEDULE
G-1	GROUNDING PLANS AND NOTES
G-2	GROUNDING DETAILS
G-3	GROUNDING DETAILS
RF-1	RF CABLE COLOR CODE
GN-1	LEGEND AND ABBREVIATIONS
GN-2	GENERAL NOTES
GN-3	GENERAL NOTES
GN-4	GENERAL NOTES

#### SCOPE OF WORK

THIS IS NOT AN ALL INCLUSIVE LIST. CONTRACTOR SHALL UTILIZE SPECIFIED EQUIPMENT PART OR ENGINEER APPROVED EQUIVALENT. CONTRACTOR SHALL VERIFY ALL NEEDED EQUIPMENT TO PROVIDE A FUNCTIONAL SITE. THE PROJECT GENERALLY CONSISTS OF THE FOLLOWING:

- TOWER SCOPE OF WORK:**
- INSTALL (3) PROPOSED PANEL ANTENNAS (1 PER SECTOR)
  - INSTALL (1) PROPOSED PLATFORM
  - INSTALL PROPOSED JUMPERS
  - INSTALL (6) PROPOSED RRUs (2 PER SECTOR)
  - INSTALL (1) PROPOSED OVER VOLTAGE PROTECTION DEVICE (OVP)
  - INSTALL (1) PROPOSED HYBRID CABLE

- GROUND SCOPE OF WORK:**
- INSTALL (1) PROPOSED METAL PLATFORM
  - INSTALL (1) PROPOSED ICE BRIDGE
  - INSTALL (1) PROPOSED PPC CABINET
  - INSTALL (1) PROPOSED EQUIPMENT CABINET
  - INSTALL (1) PROPOSED POWER CONDUIT
  - INSTALL (1) PROPOSED TELCO CONDUIT
  - INSTALL (1) PROPOSED TELCO-FIBER BOX
  - INSTALL (1) PROPOSED GPS UNIT
  - INSTALL (1) PROPOSED SAFETY SWITCH (IF REQUIRED)
  - INSTALL (1) PROPOSED CIENA BOX (IF REQUIRED)
  - EXISTING METER SOCKET ON EXISTING H-FRAME TO BE UTILIZED

#### SITE PHOTO



UNDERGROUND SERVICE ALERT CBYD 811  
UTILITY NOTIFICATION CENTER OF CONNECTICUT  
(800) 922-4455  
WWW.CBYD.COM

CALL 2 WORKING DAYS UTILITY NOTIFICATION PRIOR TO CONSTRUCTION



#### GENERAL NOTES

THE FACILITY IS UNMANNED AND NOT FOR HUMAN HABITATION. A TECHNICIAN WILL VISIT THE SITE AS REQUIRED FOR ROUTINE MAINTENANCE. THE PROJECT WILL NOT RESULT IN ANY SIGNIFICANT DISTURBANCE OR EFFECT ON DRAINAGE. NO SANITARY SEWER SERVICE, POTABLE WATER, OR TRASH DISPOSAL IS REQUIRED AND NO COMMERCIAL SIGNAGE IS PROPOSED.

11"x17" PLOT WILL BE HALF SCALE UNLESS OTHERWISE NOTED

CONTRACTOR SHALL VERIFY ALL PLANS, EXISTING DIMENSIONS, AND CONDITIONS ON THE JOB SITE, AND SHALL IMMEDIATELY NOTIFY THE ENGINEER IN WRITING OF ANY DISCREPANCIES BEFORE PROCEEDING WITH THE WORK.

#### SITE INFORMATION

PROPERTY OWNER: TERRYVILLE COUNTRY FAIR I  
ADDRESS: PO BOX 76  
TERRYVILLE, CT 06786

TOWER TYPE: MONOPOLE

TOWER CO SITE ID: 826768

TOWER APP NUMBER: 553358

COUNTY: LITCHFIELD

LATITUDE (NAD 83): 41° 40' 6.20" N  
41.668389 N

LONGITUDE (NAD 83): 73° 1' 11.84" W  
73.019956 W

ZONING JURISDICTION: CSC

ZONING DISTRICT: TBD

PARCEL NUMBER: PLYM-000004-001600

OCCUPANCY GROUP: U

CONSTRUCTION TYPE: VB

POWER COMPANY: CL&P

TELEPHONE COMPANY: AT&T

#### PROJECT DIRECTORY

APPLICANT: DISH Wireless L.L.C.  
5701 SOUTH SANTA FE DRIVE  
LITTLETON, CO 80120

TOWER OWNER: CROWN CASTLE  
2000 CORPORATE DRIVE  
CANONSBURG, PA 15317  
(877) 486-9377

SITE DESIGNER: INFINIGY  
2500 W. HIGGINS RD. STE. 500  
HOFFMAN ESTATES, IL 60169  
(847) 648-4068

SITE ACQUISITION: NICHOLAS CURRY  
NICHOLAS.CURRY@CROWNCASTLE.COM

CONSTRUCTION MANAGER: JAVIER SOTO  
JAVIER.SOTO@DISH.COM


RF ENGINEER: SYED ZAIDI  
SYED.ZAIDI@DISH.COM

#### DIRECTIONS

##### DIRECTIONS FROM TOURS OF DISTINCTION AIRPORT:

DEPART AND HEAD TOWARD MASSACO ST, TURN RIGHT ONTO MASSACO ST, TURN RIGHT ONTO US-202 W / CT-10 / HOPMEADOW ST, TURN RIGHT ONTO CT-167 / WEST ST, TURN LEFT TO STAY ON CT-167 / BUSHY HILL RD, TURN RIGHT ONTO CANTON RD, KEEP RIGHT TO GET ONTO WILDWOOD RD, BEAR LEFT ONTO NOTCH RD, ROAD NAME CHANGES TO WASHBURN RD, BEAR LEFT ONTO LAWTON RD, BEAR RIGHT ONTO US-202 E / US-44 E / ALBANY TPKE, TURN LEFT ONTO DOWD AVE, ROAD NAME CHANGES TO MAPLE AVE, KEEP STRAIGHT TO GET ONTO CT-179 / MAPLE AVE, TURN RIGHT ONTO CT-4 / SPIELMAN HWY, TURN LEFT ONTO CT-72 / TERRYVILLE RD, TURN RIGHT ONTO N MAIN ST, TURN RIGHT ONTO US-6 W / MAIN ST, TURN LEFT ONTO S MAIN ST, KEEP RIGHT TO GET ONTO S EAGLE ST, TURN RIGHT ONTO WASHINGTON RD, TURN LEFT, ARRIVE AT, 171 TOWN HILL ROAD, PLYMOUTH, CT 06786.

#### VICINITY MAP



NO SCALE




5701 SOUTH SANTA FE DRIVE  
LITTLETON, CO 80120



2000 CORPORATE DRIVE  
CANONSBURG, PA 15317



FROM ZERO TO INFINIGY  
the solutions are endless  
2500 W. HIGGINS RD. SUITE 500  
HOFFMAN ESTATES, IL 60169  
PHONE: 847-648-4068 | FAX: 518-690-0793  
WWW.INFINIGY.COM



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY: RCD  
CHECKED BY: SS  
APPROVED BY: CJW

RFDS REV #: N/A

#### CONSTRUCTION DOCUMENTS



SUBMITTALS		
REV	DATE	DESCRIPTION
A	06/11/2021	ISSUED FOR REVIEW
0	08/23/2021	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER  
2039-Z5555C

DISH Wireless L.L.C.  
PROJECT INFORMATION  
BOHVN00014A  
171 TOWN HILL ROAD  
PLYMOUTH, CT 06786

SHEET TITLE  
TITLE SHEET

SHEET NUMBER  
**T-1**



**dish**  
wireless.

5701 SOUTH SANTA FE DRIVE  
LITTLETON, CO 80120

**CROWN CASTLE**

2000 CORPORATE DRIVE  
CANONSBURG, PA 15317

**INFINIGY**  
FROM ZERO TO INFINIGY  
the solutions are endless  
2500 W. HIGGINS RD. SUITE 500  
HOFFMAN ESTATES, IL 60169  
PHONE: 847-648-4068 | FAX: 518-690-0793  
WWW.INFINIGY.COM

STATE OF CONNECTICUT  
SHUHEI SAKANAKU  
34916  
LICENSED PROFESSIONAL ENGINEER  
8/24/2021

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY: CHECKED BY: APPROVED BY:  
RCD SS CJW

RFDS REV #: N/A

**CONSTRUCTION DOCUMENTS**

SUBMITTALS		
REV	DATE	DESCRIPTION
A	06/11/2021	ISSUED FOR REVIEW
0	06/23/2021	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER  
2039-Z5555C

DISH Wireless L.L.C.  
PROJECT INFORMATION  
BOHVN00014A  
171 TOWN HILL ROAD  
PLYMOUTH, CT 06786

SHEET TITLE  
OVERALL AND ENLARGED  
SITE PLAN


SHEET NUMBER  
**A-1**

- NOTES
1. CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS.


2. ANTENNA SPECIFICATIONS REFER TO ANTENNA SCHEDULE AND TO FINAL CONSTRUCTION RFDS FOR ALL RF DETAILS

3. EXISTING EQUIPMENT AND FENCE OMITTED FOR CLARITY.


4. INFINIGY HAS NOT EVALUATED THE TOWER OR MOUNT STRUCTURE AND ASSUMES NO RESPONSIBILITY FOR THEIR STRUCTURAL INTEGRITY REGARDING PROPOSED LOADINGS. FINAL INSTALLATION SHALL COMPLY WITH RESULTS OF PASSING STRUCTURAL ANALYSES PERFORMED BY OTHERS.




PROPOSED EAST ELEVATION



1



ANTENNA LAYOUT



2

SECTOR	POSITION	ANTENNA						TRANSMISSION CABLE
		EXISTING OR PROPOSED	MANUFACTURER - MODEL NUMBER	TECHNOLOGY	SIZE (HxW)	AZMUTH	RAD CENTER	FEED LINE TYPE AND LENGTH
ALPHA	A1	PROPOSED	JMA WIRELESS - MX08FRO665-21	5G	72.0" x 20.0"	0°	132'-0"	(1) HIGH-CAPACITY HYBRID CABLE (190' LONG)
BETA	B1	PROPOSED	JMA WIRELESS - MX08FRO665-21	5G	72.0" x 20.0"	120°	132'-0"	
GAMMA	C1	PROPOSED	JMA WIRELESS - MX08FRO665-21	5G	72.0" x 20.0"	240°	132'-0"	

SECTOR	POSITION	RRH		NOTES
		MANUFACTURER - MODEL NUMBER	TECHNOLOGY	
ALPHA	A1	FUJITSU - TA08025-B604	5G	1. CONTRACTOR TO REFER TO FINAL CONSTRUCTION RFDS FOR ALL RF DETAILS. 2. ANTENNA AND RRH MODELS MAY CHANGE DUE TO EQUIPMENT AVAILABILITY. ALL EQUIPMENT CHANGES MUST BE APPROVED AND REMAIN IN COMPLIANCE WITH THE PROPOSED DESIGN AND STRUCTURAL ANALYSES.
	A1	FUJITSU - TA08025-B605	5G	
BETA	B1	FUJITSU - TA08025-B604	5G	
	B1	FUJITSU - TA08025-B605	5G	
GAMMA	G1	FUJITSU - TA08025-B604	5G	
	G1	FUJITSU - TA08025-B605	5G	

ANTENNA SCHEDULE

NO SCALE

3

dish  
wireless.

5701 SOUTH SANTA FE DRIVE  
LITTLETON, CO 80120

CROWN  
CASTLE

2000 CORPORATE DRIVE  
CANONSBURG, PA 15317

INFINIGY

FROM ZERO TO INFINIGY

the solutions are endless

2500 W. HIGGINS RD., SUITE 500 |  
HOFFMAN ESTATES, IL 60169  
PHONE: 847-648-4068 | FAX: 518-690-0793  
WWW.INFINIGY.COM

STATE OF CONNECTICUT  
SHUHEI SAKANAKU  
34916  
LICENSED  
PROFESSIONAL ENGINEER

8/24/2021

IT IS A VIOLATION OF LAW FOR ANY PERSON,  
UNLESS THEY ARE ACTING UNDER THE DIRECTION  
OF A LICENSED PROFESSIONAL ENGINEER,  
TO ALTER THIS DOCUMENT.

DRAWN BY: CHECKED BY: APPROVED BY:  
RCD SS CJW

RFDS REV #: N/A

CONSTRUCTION  
DOCUMENTS

SUBMITTALS

REV	DATE	DESCRIPTION
A	06/11/2021	ISSUED FOR REVIEW
0	08/23/2021	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER

2039-Z5555C

DISH Wireless L.L.C.  
PROJECT INFORMATION

BOHVN00014A  
171 TOWN HILL ROAD  
PLYMOUTH, CT 06786


SHEET TITLE

ELEVATION, ANTENNA  
LAYOUT AND SCHEDULE

SHEET NUMBER


A-2

DISH Wireless L.L.C. TEMPLATE VERSION 39 – 08/06/2021



PLATFORM EQUIPMENT PLAN


1



PLATFORM DETAIL

NO SCALE

2



H-FRAME DETAIL


NO SCALE

3

NOT USED

NO SCALE

4



H-FRAME EQUIPMENT ELEVATION

12" 9" 6" 3" 0" 1' 2' with 1"=1'-0"

5

NOTES

1. CONTRACTOR TO BURY PLATFORM FEET WITH A MINIMUM OF 2" OF FILL PER EXISTING SITE SURFACE
2. WEED BARRIER FABRIC TO BE ADDED AT DISCRETION OF DISH Wireless L.L.C. CONSTRUCTION MANAGER AT TIME OF CONSTRUCTION. ONE SHEET 8'x8' INSTALLED UNDER ALL FOUR FEET OF THE PLATFORM (4 MIL BLACK PLASTIC)
3. EQUIPMENT CABINET OMITTED FOR CLARITY




5701 SOUTH SANTA FE DRIVE  
LITTLETON, CO 80120



2000 CORPORATE DRIVE  
CANONSBURG, PA 15317



FROM ZERO TO INFINIGY  
the solutions are endless  
2500 W. HIGGINS RD., SUITE 500  
HOFFMAN ESTATES, IL 60169  
PHONE: 847-648-4068 | FAX: 518-690-0793  
WWW.INFINIGY.COM



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
RCD	SS	CJW

RFDS REV #: N/A

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	06/11/2021	ISSUED FOR REVIEW
0	08/23/2021	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER  
2039-Z5555C

DISH Wireless L.L.C.  
PROJECT INFORMATION  
BOHVN00014A  
171 TOWN HILL ROAD  
PLYMOUTH, CT 06786

SHEET TITLE  
EQUIPMENT PLATFORM AND  
H-FRAME DETAILS

SHEET NUMBER  
**A-3**

CHARLES INDUSTRY HEX  
CUBE-PM639155N4

DIMENSIONS (HxWxD):	74"x32"x32"
POWER PLANT:	-48VDC ABB/600W
TOTAL WEIGHT (EMPTY)	408 LBS

PLAN

SIDE

BACK

SIDE

FRONT

CABINET DETAIL

NO SCALE

1

RAYCAP PPC  
RDIAC-2465-P-240-MTS

ENCLOSURE DIMENSIONS (HxWxD):	39"x22.855"x12.593
WEIGHT:	80 lbs
OPERATING AC VOLTAGE	240/120 1 PHASE 3W+G

TOP

BACK

SIDE

FRONT

SIDE

POWER PROTECTION CABINET (PPC) DETAIL

NO SCALE

2

SQUARE D SAFETY SWITCHES  
D224NRB

ENCLOSURE DIM (HxWxD)	29.25"x19.00"x8.50"
ENCLOSURE TYPE	NEMA 3R RAINPROOF
UL LISTED	FILE E-2875

SIDE

FRONT

SAFETY SWITCH DETAIL

NO SCALE

3

NOT USED

NO SCALE

4

CHARLES CFIT-PF2020DSH1  
FIBER TELCO ENCLOSURE

ENCLOSURE DIMS (HxWxD)	20"x20"x9"
ENCLOSURE WEIGHT	20 lbs
MOUNTING	WALL
COMPLIANCE	TYPE 4

SIDE

BACK

FRONT

FIBER TELCO ENCLOSURE DETAIL

NO SCALE

6

COMMSCOPE WB-K110-B  
WAVEGUIDE BRIDGE KIT

DIMENSIONS (HxL)	160"x10'
WEIGHT/ VOLUME	325.0 LBS
CABLE RUN (QTY)	12

PLAN

FRONT

SIDE

ICE BRIDGE DETAIL

NO SCALE

7

FINISH SLOPE  
TO DRAIN

A-A

A-A

PROPOSED 3.5" DIA.  
SCH 40 PIPE  
GALVANIZED

PROPOSED 1'-6"  
DIA. CONCRETE  
PIER (TYP)

CONCRETE PIER

3" DIA SCH 40 PIPE

18" DIA DRILLED  
PIER FOUNDATION

A-A SECTION

TYPICAL ICE BRIDGE CONCRETE PIER DETAIL

NO SCALE

8

PROPOSED  
ICE BRIDGE

PROPOSED X" DIA  
HYBRID CABLE  
(OPTION "A")

PROPOSED X" DIA  
HYBRID CABLE  
(OPTION "B")

PROPOSED  
CABLE CLAMP  
Ø 3'-0" O.C.

HYBRID SUPPORT  
BRACKET AND BANDING  
Ø 4'-0" O.C.

EXISTING ENTRY PORT

EXISTING  
MONOPOLE

HYBRID CABLE RUN

NO SCALE

9

DISH Wireless L.L.C. TEMPLATE VERSION 39 - 08/06/2021

5701 SOUTH SANTA FE DRIVE  
LITTLETON, CO 80120

2000 CORPORATE DRIVE  
CANONSBURG, PA 15317

FROM ZERO TO INFINIGY  
the solutions are endless  
2500 W. HIGGINS RD., SUITE 500 |  
HOFFMAN ESTATES, IL 60169  
PHONE: 847-648-4068 | FAX: 518-690-0793  
WWW.INFINIGY.COM

IT IS A VIOLATION OF LAW FOR ANY PERSON,  
UNLESS THEY ARE ACTING UNDER THE DIRECTION  
OF A LICENSED PROFESSIONAL ENGINEER,  
TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
RCD	SS	CJW

RFDS REV #: N/A

CONSTRUCTION  
DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	08/11/2021	ISSUED FOR REVIEW
0	08/23/2021	ISSUED FOR CONSTRUCTION


A&E PROJECT NUMBER  
2039-Z5555C

DISH Wireless L.L.C.  
PROJECT INFORMATION  
BOHVN00014A  
171 TOWN HILL ROAD  
PLYMOUTH, CT 06786


SHEET TITLE  
EQUIPMENT DETAILS

SHEET NUMBER  
**A-4**


PCTEL GPSGL-TMG-SPI-40NCB	
DIMENSIONS (DIAxH) MM/INCH	81x184mm 3.2"x7.25"
WEIGHT W/ACCESSORIES	075 lbs
CONNECTOR	N-FEMALE
FREQUENCY RANGE	1590 ± 30MHz





TOP



BACK



SIDE



GPS DETAIL

NO SCALE

1

GPS MINIMUM SKY VIEW REQUIREMENTS

NO SCALE

2

CABLES UNLIMITED HYBRID CABLE  
MINIMUM BEND RADIUSES

NO SCALE

3

NOT USED

NO SCALE

4

NOT USED

NO SCALE

5

NOT USED

NO SCALE

6

NOT USED

NO SCALE

7

NOT USED

NO SCALE

8

NOT USED

NO SCALE

9

dish  
wireless.

5701 SOUTH SANTA FE DRIVE  
LITTLETON, CO 80120


CROWN  
CASTLE

2000 CORPORATE DRIVE  
CANONSBURG, PA 15317

INFINIGY

FROM ZERO TO INFINIGY

the solutions are endless  
2500 W. HIGGINS RD., SUITE 500 |  
HOFFMAN ESTATES, IL 60169  
PHONE: 847-648-4068 | FAX: 518-690-0793  
WWW.INFINIGY.COM



IT IS A VIOLATION OF LAW FOR ANY PERSON,  
UNLESS THEY ARE ACTING UNDER THE DIRECTION  
OF A LICENSED PROFESSIONAL ENGINEER,  
TO ALTER THIS DOCUMENT.

DRAWN BY: CHECKED BY: APPROVED BY:

RCD SS CJW

RFDS REV #: N/A

CONSTRUCTION  
DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	06/11/2021	ISSUED FOR REVIEW
0	06/23/2021	ISSUED FOR CONSTRUCTION



























A&E PROJECT NUMBER  
2039-Z5555C

DISH Wireless L.L.C.  
PROJECT INFORMATION  
BOHVN00014A  
171 TOWN HILL ROAD  
PLYMOUTH, CT 06786

SHEET TITLE  
EQUIPMENT DETAILS

SHEET NUMBER

A-5

<div><div>FUJITSU TRIPLE BAND TA08025-B605</div><table><tr><td>DIMENSIONS (HxWxD)</td><td>14.9"x15.7"x9"</td></tr><tr><td>WEIGHT</td><td>74.95 lbs</td></tr><tr><td>CONNECTOR TYPE</td><td>4.3-10 RF CONNECTOR</td></tr><tr><td>POWER SUPPLY</td><td>DC -58~-36V</td></tr></table><div><div>PLAN</div><div><div>BACK</div><div>SIDE</div><div>FRONT</div></div></div></div>			DIMENSIONS (HxWxD)	14.9"x15.7"x9"	WEIGHT	74.95 lbs	CONNECTOR TYPE	4.3-10 RF CONNECTOR	POWER SUPPLY	DC -58~-36V	<div><div>FUJITSU DUAL BAND TA08025-B604</div><table><tr><td>DIMENSIONS (HxWxD)</td><td>14.9"x15.7"x7.8"</td></tr><tr><td>WEIGHT</td><td>63.9 lbs</td></tr><tr><td>CONNECTOR TYPE</td><td>4.3-10 RF CONNECTOR</td></tr><tr><td>POWER SUPPLY</td><td>DC -58~-36V</td></tr></table><div><div>PLAN</div><div><div>BACK</div><div>SIDE</div><div>FRONT</div></div></div></div>			DIMENSIONS (HxWxD)	14.9"x15.7"x7.8"	WEIGHT	63.9 lbs	CONNECTOR TYPE	4.3-10 RF CONNECTOR	POWER SUPPLY	DC -58~-36V	<div><div>SABRE DOUBLE Z-BRACKET C10123155</div><table><tr><td>DIMENSIONS (HxWxD) (1 BRACKET)</td><td>5"x20"x1-13/16"</td></tr><tr><td>WEIGHT (FULL ASSEMBLY)</td><td>35.79 lbs</td></tr><tr><td>PACKAGE QUANTITY</td><td>4</td></tr></table><div><table><tr><th>#</th><th>DESCRIPTION</th></tr><tr><td>1</td><td>PLATE, CHANNEL BRACKET</td></tr><tr><td>2</td><td>RRH Z BRACKET, 3/16"</td></tr><tr><td>3</td><td>THREADED ROD ASSEMBLY 1/2"x12"</td></tr></table><div>NOTE: OR DISH Wireless L.L.C. APPROVED EQUIVALENT</div></div></div>			DIMENSIONS (HxWxD) (1 BRACKET)	5"x20"x1-13/16"	WEIGHT (FULL ASSEMBLY)	35.79 lbs	PACKAGE QUANTITY	4	#	DESCRIPTION	1	PLATE, CHANNEL BRACKET	2	RRH Z BRACKET, 3/16"	3	THREADED ROD ASSEMBLY 1/2"x12"	RRH DETAIL			NO SCALE		1	
DIMENSIONS (HxWxD)	14.9"x15.7"x9"																																												
WEIGHT	74.95 lbs																																												
CONNECTOR TYPE	4.3-10 RF CONNECTOR																																												
POWER SUPPLY	DC -58~-36V																																												
DIMENSIONS (HxWxD)	14.9"x15.7"x7.8"																																												
WEIGHT	63.9 lbs																																												
CONNECTOR TYPE	4.3-10 RF CONNECTOR																																												
POWER SUPPLY	DC -58~-36V																																												
DIMENSIONS (HxWxD) (1 BRACKET)	5"x20"x1-13/16"																																												
WEIGHT (FULL ASSEMBLY)	35.79 lbs																																												
PACKAGE QUANTITY	4																																												
#	DESCRIPTION																																												
1	PLATE, CHANNEL BRACKET																																												
2	RRH Z BRACKET, 3/16"																																												
3	THREADED ROD ASSEMBLY 1/2"x12"																																												
<div><div>RAYCAP RDIDC-9181-PF-48 DC SURGE PROTECTION (OVP)</div><table><tr><td>DIMENSIONS (HxWxD)</td><td>18.98"x14.39"x8.15"</td></tr><tr><td>WEIGHT</td><td>21.82 LBS</td></tr></table><div><div>PLAN</div><div><div>SIDE</div><div>BACK</div><div>FRONT</div></div></div></div>			DIMENSIONS (HxWxD)	18.98"x14.39"x8.15"	WEIGHT	21.82 LBS	<div><div>JMA WIRELESS MX08FR0665-21 ANTENNA</div><table><tr><td>DIMENSIONS (HxWxD)</td><td>72.8"x20.0"x8.0"</td></tr><tr><td>TOTAL WEIGHT</td><td>64.5 LB</td></tr><tr><td>RF PORTS, CONNECTOR TYPE</td><td>8 x 4.3-10 FEMALE</td></tr></table><div><div>NOTES</div><div>FINAL ANTENNA SPECIFICATIONS TO BE CONFIRMED BY GC</div><div><div>PLAN</div><div><div>BACK</div><div>SIDE</div><div>FRONT</div></div></div></div></div>			DIMENSIONS (HxWxD)	72.8"x20.0"x8.0"	TOTAL WEIGHT	64.5 LB	RF PORTS, CONNECTOR TYPE	8 x 4.3-10 FEMALE	<div><div>M04 MOUNTING BRACKET HPA-33R-BUU-H4-K</div><table><tr><td>WIDTH</td><td>5"</td></tr><tr><td>DEPTH</td><td>2"</td></tr><tr><td>HEIGHT</td><td>8"</td></tr><tr><td>TOTAL WEIGHT</td><td>1.5 lbs</td></tr><tr><td>HOUSING MATERIAL</td><td>ASA/ABS/ALUMINUM</td></tr><tr><td>RADOME COLOR</td><td>LIGHT GRAY</td></tr><tr><td>CONNECTOR</td><td>1x8-PIN DAISY CHAIN</td></tr></table><div>NOTE: OR DISH Wireless L.L.C. APPROVED EQUIVALENT</div></div>			WIDTH	5"	DEPTH	2"	HEIGHT	8"	TOTAL WEIGHT	1.5 lbs	HOUSING MATERIAL	ASA/ABS/ALUMINUM	RADOME COLOR	LIGHT GRAY	CONNECTOR	1x8-PIN DAISY CHAIN	ANTENNA DETAIL			NO SCALE		2							
DIMENSIONS (HxWxD)	18.98"x14.39"x8.15"																																												
WEIGHT	21.82 LBS																																												
DIMENSIONS (HxWxD)	72.8"x20.0"x8.0"																																												
TOTAL WEIGHT	64.5 LB																																												
RF PORTS, CONNECTOR TYPE	8 x 4.3-10 FEMALE																																												
WIDTH	5"																																												
DEPTH	2"																																												
HEIGHT	8"																																												
TOTAL WEIGHT	1.5 lbs																																												
HOUSING MATERIAL	ASA/ABS/ALUMINUM																																												
RADOME COLOR	LIGHT GRAY																																												
CONNECTOR	1x8-PIN DAISY CHAIN																																												
<div><div>SURGE SUPPRESSION DETAIL (OVP)</div><div>NOTE: OR DISH Wireless L.L.C. APPROVED EQUIVALENT</div></div>			<div><div>COMMSCOPE XP-2040 CROSSOVER PLATE</div><table><tr><td>DIMENSIONS (HxW)</td><td>10"x12"</td></tr><tr><td>WEIGHT</td><td>11 lbs</td></tr></table><div><div>NOTE: OR DISH Wireless L.L.C. APPROVED EQUIVALENT</div><div><div>PLAN PLATE</div><div>SIDE PLATE</div><div>PLAN U-BOLT</div><div>SIDE U-BOLT</div></div></div></div>			DIMENSIONS (HxW)	10"x12"	WEIGHT	11 lbs	<div><div>COMMSCOPE MC-PK8-DSH</div><table><tr><td>FACE WIDTH</td><td>96"</td></tr><tr><td>WEIGHT</td><td>1373.08 lbs</td></tr></table><div>NOTE: 15" TO 38" O.D.</div><div><div>HORIZONTAL PIPE ANTENNA PIPE FACE PIPE</div></div></div>			FACE WIDTH	96"	WEIGHT	1373.08 lbs	ANTENNA MOUNTING DETAIL			NO SCALE		3																							
DIMENSIONS (HxW)	10"x12"																																												
WEIGHT	11 lbs																																												
FACE WIDTH	96"																																												
WEIGHT	1373.08 lbs																																												
RRH/OVP MOUNT DETAIL			NO SCALE		7		ANTENNA PLATFORM DETAIL			NO SCALE		8																																	
NOT USED			NO SCALE		9		NOT USED			NO SCALE		9																																	



5701 SOUTH SANTA FE DRIVE  
LITTLETON, CO 80120




2000 CORPORATE DRIVE  
CANONSBURG, PA 15317



FROM ZERO TO INFINIGY

the solutions are endless

2500 W. HIGGINS RD., SUITE 500  
HOFFMAN ESTATES, IL 60169  
PHONE: 847-648-4068 | FAX: 518-690-0793  
WWW.INFINIGY.COM



IT IS A VIOLATION OF LAW FOR ANY PERSON,  
UNLESS THEY ARE ACTING UNDER THE DIRECTION  
OF A LICENSED PROFESSIONAL ENGINEER,  
TO ALTER THIS DOCUMENT.

DRAWN BY: CHECKED BY: APPROVED BY:

RCD SS CJW

RFDS REV #: N/A

## CONSTRUCTION DOCUMENTS


SUBMITTALS		
REV	DATE	DESCRIPTION
A	06/11/2021	ISSUED FOR REVIEW
0	08/23/2021	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER  
2039-Z5555C


DISH Wireless L.L.C.  
PROJECT INFORMATION  
BOHVN00014A  
171 TOWN HILL ROAD  
PLYMOUTH, CT 06786

SHEET TITLE  
EQUIPMENT DETAILS

SHEET NUMBER  
**A-6**



- DC POWER WIRING SHALL BE COLOR CODED AT EACH END FOR IDENTIFYING +24V AND -48V CONDUCTORS. RED MARKINGS SHALL IDENTIFY +24V AND BLUE MARKINGS SHALL IDENTIFY -48V.
- CONTRACTOR SHALL INSPECT THE EXISTING CONDITIONS PRIOR TO SUBMITTING A BID. ANY QUESTIONS ARISING DURING THE BID PERIOD IN REGARDS TO THE CONTRACTOR'S FUNCTIONS, THE SCOPE OF WORK, OR ANY OTHER ISSUE RELATED TO THIS PROJECT SHALL BE BROUGHT UP DURING THE BID PERIOD WITH THE PROJECT MANAGER FOR CLARIFICATION, NOT AFTER THE CONTRACT HAS BEEN AWARDED.
  - ALL ELECTRICAL WORK SHALL BE DONE IN ACCORDANCE WITH CURRENT NATIONAL ELECTRICAL CODES AND ALL STATE AND LOCAL CODES, LAWS, AND ORDINANCES. PROVIDE ALL COMPONENTS AND WIRING SIZES AS REQUIRED TO MEET NEC STANDARDS.
  - LOCATION OF EQUIPMENT, CONDUIT AND DEVICES SHOWN ON THE DRAWINGS ARE APPROXIMATE AND SHALL BE COORDINATED WITH FIELD CONDITIONS PRIOR TO CONSTRUCTION.
  - CONDUIT ROUGH-IN SHALL BE COORDINATED WITH THE MECHANICAL EQUIPMENT TO AVOID LOCATION CONFLICTS. VERIFY WITH THE MECHANICAL EQUIPMENT CONTRACTOR AND COMPLY AS REQUIRED.
  - CONTRACTOR SHALL PROVIDE ALL BREAKERS, CONDUITS AND CIRCUITS AS REQUIRED FOR A COMPLETE SYSTEM.
  - CONTRACTOR SHALL PROVIDE PULL BOXES AND JUNCTION BOXES AS REQUIRED BY THE NEC ARTICLE 314.
  - CONTRACTOR SHALL PROVIDE ALL STRAIN RELIEF AND CABLE SUPPORTS FOR ALL CABLE ASSEMBLIES. INSTALLATION SHALL BE IN ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS AND RECOMMENDATIONS.
  - ALL DISCONNECTS AND CONTROLLING DEVICES SHALL BE PROVIDED WITH ENGRAVED PHENOLIC NAMEPLATES INDICATING EQUIPMENT CONTROLLED, BRANCH CIRCUITS INSTALLED ON, AND PANEL FIELD LOCATIONS FED FROM.
  - INSTALL AN EQUIPMENT GROUNDING CONDUCTOR IN ALL CONDUITS PER THE SPECIFICATIONS AND NEC 250. THE EQUIPMENT GROUNDING CONDUCTORS SHALL BE BONDED AT ALL JUNCTION BOXES, PULL BOXES, AND ALL DISCONNECT SWITCHES, AND EQUIPMENT CABINETS.
  - ALL NEW MATERIAL SHALL HAVE A U.L. LABEL.
  - PANEL SCHEDULE LOADING AND CIRCUIT ARRANGEMENTS REFLECT POST-CONSTRUCTION EQUIPMENT.
  - CONTRACTOR SHALL BE RESPONSIBLE FOR AS-BUILT PANEL SCHEDULE AND SITE DRAWINGS.
  - ALL TRENCHES IN COMPOUND TO BE HAND DUG



**dish**  
wireless.


5701 SOUTH SANTA FE DRIVE  
LITTLETON, CO 80120

**CROWN**  
**CASTLE**

2000 CORPORATE DRIVE  
CANONSBURG, PA 15317

**INFINIGY**  
FROM ZERO TO INFINIGY

the solutions are endless  
2500 W. HIGGINS RD. SUITE 500 I  
HOFFMAN ESTATES, IL 60169  
PHONE: 847-648-4068 | FAX: 518-690-0793  
WWW.INFINIGY.COM



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY: CHECKED BY: APPROVED BY:  
RCD SS CJW

RFDS REV #: N/A

**CONSTRUCTION**  
**DOCUMENTS**

SUBMITTALS		
REV	DATE	DESCRIPTION
A	06/11/2021	ISSUED FOR REVIEW
0	06/23/2021	ISSUED FOR CONSTRUCTION


A&E PROJECT NUMBER  
2039-Z5555C

DISH Wireless L.L.C.  
PROJECT INFORMATION  
BOHVN00014A  
171 TOWN HILL ROAD  
PLYMOUTH, CT 06786

SHEET TITLE  
ELECTRICAL/FIBER ROUTE  
PLAN AND NOTES

SHEET NUMBER  
**E-1**



CARLON EXPANSION FITTINGS				
COUPLING END PART#	MALE TERMINAL ADAPTER END PART#	SIZE	STD CTN QTY.	TRAVEL LENGTH
E945D	E945DX	1/2"	20	4"
E945E	E945EX	3/4"	15	4"
E945F	E945FX	1"	10	4"
E945G	E945GX	1 1/4"	5	4"
E945H	E945HX	1 1/2"	5	4"
E945J	E945JX	2"	15	8"
E945K	E945KX	2 1/2"	10	8"
E945L	E945LX	3"	10	8"
E945M	E945MX	3 1/2"	5	8"
E945N	E945NX	4"	5	8"
E945P	E945PX	5"	1	8"
E945R	E945RX	6"	1	8"



NOTE: CONTRACTOR TO INSTALL EXPANSION FITTING SLIP JOINT AT METER CENTER CONDUIT TERMINATION, AS PER LOCAL UTILITY POLICY, ORDINANCE AND/OR SPECIFIED REQUIREMENT.

TRENCHING NOTES

1. CONTRACTOR SHALL RESTORE THE TRENCH TO ITS ORIGINAL CONDITIONS BY EITHER SEEDING OR SODDING GRASS AREAS, OR REPLACING ASPHALT OR CONCRETE AREAS TO ITS ORIGINAL CROSS SECTION.
2. TRENCHING SAFETY; INCLUDING, BUT NOT LIMITED TO SOIL CLASSIFICATION, SLOPING, AND SHORING, SHALL BE GOVERNED BY THE CURRENT OSHA TRENCHING AND EXCAVATION SAFETY STANDARDS.
3. ALL CONDUITS SHALL BE INSTALLED IN COMPLIANCE WITH THE CURRENT NATIONAL ELECTRIC CODE (NEC) OR AS REQUIRED BY THE LOCAL JURISDICTION, WHICHEVER IS THE MOST STRINGENT.



EXPANSION JOINT DETAIL

NO SCALE

1

TYPICAL UNDERGROUND TRENCH DETAIL


NO SCALE

2

DARK TELCO BOX – INTERIOR WIRING LAYOUT

NO SCALE

3



LIT TELCO BOX – INTERIOR WIRING LAYOUT (OPTIONAL)

NO SCALE

4

NOT USED

NO SCALE

5

NOT USED

NO SCALE

6

NOT USED

NO SCALE

7

NOT USED

NO SCALE

8

NOT USED

NO SCALE

9




5701 SOUTH SANTA FE DRIVE  
LITTLETON, CO 80120



2000 CORPORATE DRIVE  
CANONSBURG, PA 15317



the solutions are endless  
2500 W. HIGGINS RD. SUITE 500 I  
HOFFMAN ESTATES, IL 60169  
PHONE: 847-648-4068 | FAX: 518-690-0793  
WWW.INFINIGY.COM



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY: CHECKED BY: APPROVED BY:

RCD SS CJW

RFDS REV #: N/A

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	06/11/2021	ISSUED FOR REVIEW
0	06/23/2021	ISSUED FOR CONSTRUCTION




A&E PROJECT NUMBER  
2039-Z5555C

DISH Wireless L.L.C.  
PROJECT INFORMATION  
BOHVN00014A  
171 TOWN HILL ROAD  
PLYMOUTH, CT 06786

SHEET TITLE  
ELECTRICAL  
DETAILS


SHEET NUMBER

E-2




---






H-FRAME GROUNDING DETAIL

NO SCALE 1




TRANSITIONING GROUND DETAIL

NO SCALE 4




TYPICAL TEST GROUND ROD WITH INSPECTION SLEEVE

NO SCALE 5




TYPICAL GPS UNIT GROUNDING

NO SCALE 2



OUTDOOR CABINET GROUNDING

NO SCALE 3



TYPICAL GROUND RING TRENCH

NO SCALE 6

5701 SOUTH SANTA FE DRIVE  
LITTLETON, CO 80120

2000 CORPORATE DRIVE  
CANONSBURG, PA 15317

FROM ZERO TO INFINIGY  
the solutions are endless  
2500 W. HIGGINS RD. SUITE 500 I  
HOFFMAN ESTATES, IL 60169  
PHONE: 847-648-4068 | FAX: 518-690-0793  
WWW.INFINIGY.COM

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
RCD	SS	CJW

RFDS REV #: N/A

CONSTRUCTION DOCUMENTS




SUBMITTALS		
REV	DATE	DESCRIPTION
A	06/11/2021	ISSUED FOR REVIEW
0	08/23/2021	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER  
2039-Z5555C

DISH Wireless L.L.C.  
PROJECT INFORMATION  
BOHVN00014A  
171 TOWN HILL ROAD  
PLYMOUTH, CT 06786

SHEET TITLE  
GROUNDING DETAILS

SHEET NUMBER  
G-2

<div>1. EXOTHERMIC WELD (2) TWO, #2 AWG BARE TINNED SOLID COPPER CONDUCTORS TO GROUND BAR. ROUTE CONDUCTORS TO BURIED GROUND RING AND PROVIDE PARALLEL EXOTHERMIC WELD.</div> <div>2. ALL EXTERIOR GROUNDING HARDWARE SHALL BE STAINLESS STEEL 3/8" DIAMETER OR LARGER. ALL HARDWARE 18-8 STAINLESS STEEL INCLUDING LOCK WASHERS, COAT ALL SURFACES WITH AN ANTI-OXIDANT COMPOUND BEFORE MATING.</div> <div>3. FOR GROUND BOND TO STEEL ONLY: COAT ALL SURFACES WITH AN ANTI-OXIDANT COMPOUND BEFORE MATING.</div> <div>4. DO NOT INSTALL CABLE GROUNDING KIT AT A BEND AND ALWAYS DIRECT GROUND CONDUCTOR DOWN TO GROUNDING BUS.</div> <div>5. NUT &amp; WASHER SHALL BE PLACED ON THE FRONT SIDE OF THE GROUND BAR AND BOLTED ON THE BACK SIDE.</div> <div>6. ALL GROUNDING PARTS AND EQUIPMENT TO BE SUPPLIED AND INSTALLED BY CONTRACTOR.</div> <div>7. THE CONTRACTOR SHALL BE RESPONSIBLE FOR INSTALLING ADDITIONAL GROUND BAR AS REQUIRED.</div> <div>8. ENSURE THE WIRE INSULATION TERMINATION IS WITHIN 1/8" OF THE BARREL (NO SHINERS).</div>														
TYPICAL GROUNDING NOTES			NO SCALE	1	TYPICAL EXTERIOR TWO HOLE LUG			NO SCALE	2	TYPICAL INTERIOR TWO HOLE LUG			NO SCALE	3
														
LUG DETAIL			NO SCALE	4	NOT USED			NO SCALE	5	NOT USED			NO SCALE	6
NOT USED			NO SCALE	7	NOT USED			NO SCALE	8	NOT USED			NO SCALE	9



5701 SOUTH SANTA FE DRIVE  
LITTLETON, CO 80120



2000 CORPORATE DRIVE  
CANONSBURG, PA 15317

INFINIGY

FROM ZERO TO INFINIGY

the solutions are endless

2500 W. HIGGINS RD. SUITE 500 |  
HOFFMAN ESTATES, IL 60169  
PHONE: 847-648-4068 | FAX: 518-690-0793  
WWW.INFINIGY.COM

STATE OF CONNECTICUT

SHUHEI SAKAMOTO

34916

PROFESSIONAL ENGINEER

8/24/2021

IT IS A VIOLATION OF LAW FOR ANY PERSON,  
UNLESS THEY ARE ACTING UNDER THE DIRECTION  
OF A LICENSED PROFESSIONAL ENGINEER,  
TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
RCD	SS	CJW

RFDS REV #: N/A

CONSTRUCTION DOCUMENTS		
SUBMITTALS		
REV	DATE	DESCRIPTION
A	06/11/2021	ISSUED FOR REVIEW
0	06/23/2021	ISSUED FOR CONSTRUCTION
A&E PROJECT NUMBER		
2039-Z5555C		
DISH Wireless L.L.C. PROJECT INFORMATION		
BOHVN00014A 171 TOWN HILL ROAD PLYMOUTH, CT 06786		
SHEET TITLE		
GROUNDING DETAILS		
SHEET NUMBER		
G-3		




DISH Wireless L.L.C. TEMPLATE VERSION 39 – 08/06/2021

## ABBREVIATIONS

5701 SOUTH SANTA FE DRIVE  
LITTLETON, CO 80120

**CC CROWN  
CASTLE**  
2000 CORPORATE DRIVE  
CANONSBURG, PA 15317

**INFINIGY**   
FROM ZERO TO INFINIGY  
**the solutions are endless**  
2500 W. HIGGINS RD. SUITE 500 |  
HOFFMAN ESTATES, IL 60169  
PHONE: 847-648-4068 | FAX: 518-690-0793  
[WWW.INFINIGY.COM](http://WWW.INFINIGY.COM)



IT IS A VIOLATION OF LAW FOR ANY PERSON,  
UNLESS THEY ARE ACTING UNDER THE DIRECTION  
OF A LICENSED PROFESSIONAL ENGINEER,  
TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
RCD	SS	CJW

RFDS REV #: N/A

# CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
<b>A</b>	<b>06/11/2021</b>	<b>ISSUED FOR REVIEW</b>
<b>0</b>	<b>06/23/2021</b>	<b>ISSUED FOR CONSTRUCTION</b>

A&E PROJECT NUMBER  
2039-Z5555C

DISH Wireless L.L.C.  
PROJECT INFORMATION  
BOHVN00014A  
171 TOWN HILL ROAD  
PLYMOUTH, CT 06786

SHEET TITLE

LEGEND AND ABBREVIATIONS

SHEET NUMBER

# GN-1

SITE ACTIVITY REQUIREMENTS:

1. NOTICE TO PROCEED – NO WORK SHALL COMMENCE PRIOR TO CONTRACTOR RECEIVING A WRITTEN NOTICE TO PROCEED (NTP) AND THE ISSUANCE OF A PURCHASE ORDER. PRIOR TO ACCESSING/ENTERING THE SITE YOU MUST CONTACT THE DISH Wireless L.L.C. AND TOWER OWNER NOC & THE DISH Wireless L.L.C. AND TOWER OWNER CONSTRUCTION MANAGER.
2. "LOOK UP" – DISH Wireless L.L.C. AND TOWER OWNER SAFETY CLIMB REQUIREMENT:  
  
THE INTEGRITY OF THE SAFETY CLIMB AND ALL COMPONENTS OF THE CLIMBING FACILITY SHALL BE CONSIDERED DURING ALL STAGES OF DESIGN, INSTALLATION, AND INSPECTION. TOWER MODIFICATION, MOUNT REINFORCEMENTS, AND/OR EQUIPMENT INSTALLATIONS SHALL NOT COMPROMISE THE INTEGRITY OR FUNCTIONAL USE OF THE SAFETY CLIMB OR ANY COMPONENTS OF THE CLIMBING FACILITY ON THE STRUCTURE. THIS SHALL INCLUDE, BUT NOT BE LIMITED TO: PINCHING OF THE WIRE ROPE, BENDING OF THE WIRE ROPE FROM ITS SUPPORTS, DIRECT CONTACT OR CLOSE PROXIMITY TO THE WIRE ROPE WHICH MAY CAUSE FRICTIONAL WEAR, IMPACT TO THE ANCHORAGE POINTS IN ANY WAY, OR TO IMPEDE/BLOCK ITS INTENDED USE. ANY COMPROMISED SAFETY CLIMB, INCLUDING EXISTING CONDITIONS MUST BE TAGGED OUT AND REPORTED TO YOUR DISH Wireless L.L.C. AND DISH Wireless L.L.C. AND TOWER OWNER POC OR CALL THE NOC TO GENERATE A SAFETY CLIMB MAINTENANCE AND CONTRACTOR NOTICE TICKET.
3. PRIOR TO THE START OF CONSTRUCTION, ALL REQUIRED JURISDICTIONAL PERMITS SHALL BE OBTAINED. THIS INCLUDES, BUT IS NOT LIMITED TO, BUILDING, ELECTRICAL, MECHANICAL, FIRE, FLOOD ZONE, ENVIRONMENTAL, AND ZONING. AFTER ONSITE ACTIVITIES AND CONSTRUCTION ARE COMPLETED, ALL REQUIRED PERMITS SHALL BE SATISFIED AND CLOSED OUT ACCORDING TO LOCAL JURISDICTIONAL REQUIREMENTS.
4. ALL CONSTRUCTION MEANS AND METHODS; INCLUDING BUT NOT LIMITED TO, ERECTION PLANS, RIGGING PLANS, CLIMBING PLANS, AND RESCUE PLANS SHALL BE THE RESPONSIBILITY OF THE GENERAL CONTRACTOR RESPONSIBLE FOR THE EXECUTION OF THE WORK CONTAINED HEREIN, AND SHALL MEET ANSI/ASSE A10.48 (LATEST EDITION); FEDERAL, STATE, AND LOCAL REGULATIONS; AND ANY APPLICABLE INDUSTRY CONSENSUS STANDARDS RELATED TO THE CONSTRUCTION ACTIVITIES BEING PERFORMED. ALL RIGGING PLANS SHALL ADHERE TO ANSI/ASSE A10.48 (LATEST EDITION) AND DISH Wireless L.L.C. AND TOWER OWNER STANDARDS, INCLUDING THE REQUIRED INVOLVEMENT OF A QUALIFIED ENGINEER FOR CLASS IV CONSTRUCTION, TO CERTIFY THE SUPPORTING STRUCTURE(S) IN ACCORDANCE WITH ANSI/TIA–322 (LATEST EDITION).
5. ALL SITE WORK TO COMPLY WITH DISH Wireless L.L.C. AND TOWER OWNER INSTALLATION STANDARDS FOR CONSTRUCTION ACTIVITIES ON DISH Wireless L.L.C. AND TOWER OWNER TOWER SITE AND LATEST VERSION OF ANSI/TIA–1019–A–2012 "STANDARD FOR INSTALLATION, ALTERATION, AND MAINTENANCE OF ANTENNA SUPPORTING STRUCTURES AND ANTENNAS."
6. IF THE SPECIFIED EQUIPMENT CAN NOT BE INSTALLED AS SHOWN ON THESE DRAWINGS, THE CONTRACTOR SHALL PROPOSE AN ALTERNATIVE INSTALLATION FOR APPROVAL BY DISH Wireless L.L.C. AND TOWER OWNER PRIOR TO PROCEEDING WITH ANY SUCH CHANGE OF INSTALLATION.
7. ALL MATERIALS FURNISHED AND INSTALLED SHALL BE IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS AND ORDINANCES. CONTRACTOR SHALL ISSUE ALL APPROPRIATE NOTICES AND COMPLY WITH ALL LAWS, ORDINANCES, RULES, REGULATIONS AND LAWFUL ORDERS OF ANY PUBLIC AUTHORITY REGARDING THE PERFORMANCE OF THE WORK. ALL WORK CARRIED OUT SHALL COMPLY WITH ALL APPLICABLE MUNICIPAL AND UTILITY COMPANY SPECIFICATIONS AND LOCAL JURISDICTIONAL CODES, ORDINANCES AND APPLICABLE REGULATIONS.
8. THE CONTRACTOR SHALL INSTALL ALL EQUIPMENT AND MATERIALS IN ACCORDANCE WITH MANUFACTURER’S RECOMMENDATIONS UNLESS SPECIFICALLY STATED OTHERWISE.
9. THE CONTRACTOR SHALL CONTACT UTILITY LOCATING SERVICES INCLUDING PRIVATE LOCATES SERVICES PRIOR TO THE START OF CONSTRUCTION.
10. ALL EXISTING ACTIVE SEWER, WATER, GAS, ELECTRIC AND OTHER UTILITIES WHERE ENCOUNTERED IN THE WORK, SHALL BE PROTECTED AT ALL TIMES AND WHERE REQUIRED FOR THE PROPER EXECUTION OF THE WORK, SHALL BE RELOCATED AS DIRECTED BY CONTRACTOR. EXTREME CAUTION SHOULD BE USED BY THE CONTRACTOR WHEN EXCAVATING OR DRILLING PIERS AROUND OR NEAR UTILITIES. CONTRACTOR SHALL PROVIDE SAFETY TRAINING FOR THE WORKING CREW. THIS WILL INCLUDE BUT NOT BE LIMITED TO A) FALL PROTECTION B) CONFINED SPACE C) ELECTRICAL SAFETY D) TRENCHING AND EXCAVATION E) CONSTRUCTION SAFETY PROCEDURES.
11. ALL SITE WORK SHALL BE AS INDICATED ON THE STAMPED CONSTRUCTION DRAWINGS AND DISH PROJECT SPECIFICATIONS, LATEST APPROVED REVISION.
12. CONTRACTOR SHALL KEEP THE SITE FREE FROM ACCUMULATING WASTE MATERIAL, DEBRIS, AND TRASH AT THE COMPLETION OF THE WORK. IF NECESSARY, RUBBISH, STUMPS, DEBRIS, STICKS, STONES AND OTHER REFUSE SHALL BE REMOVED FROM THE SITE AND DISPOSED OF LEGALLY.
13. ALL EXISTING INACTIVE SEWER, WATER, GAS, ELECTRIC AND OTHER UTILITIES, WHICH INTERFERE WITH THE EXECUTION OF THE WORK, SHALL BE REMOVED AND/OR CAPPED, PLUGGED OR OTHERWISE DISCONTINUED AT POINTS WHICH WILL NOT INTERFERE WITH THE EXECUTION OF THE WORK, SUBJECT TO THE APPROVAL OF DISH Wireless L.L.C. AND TOWER OWNER, AND/OR LOCAL UTILITIES.
14. THE CONTRACTOR SHALL PROVIDE SITE SIGNAGE IN ACCORDANCE WITH THE TECHNICAL SPECIFICATION FOR SITE SIGNAGE REQUIRED BY LOCAL JURISDICTION AND SIGNAGE REQUIRED ON INDIVIDUAL PIECES OF EQUIPMENT, ROOMS, AND SHELTERS.
15. THE SITE SHALL BE GRADED TO CAUSE SURFACE WATER TO FLOW AWAY FROM THE CARRIER’S EQUIPMENT AND TOWER AREAS.
16. THE SUB GRADE SHALL BE COMPACTED AND BROUGHT TO A SMOOTH UNIFORM GRADE PRIOR TO FINISHED SURFACE APPLICATION.
17. THE AREAS OF THE OWNERS PROPERTY DISTURBED BY THE WORK AND NOT COVERED BY THE TOWER, EQUIPMENT OR DRIVEWAY, SHALL BE GRADED TO A UNIFORM SLOPE, AND STABILIZED TO PREVENT EROSION AS SPECIFIED ON THE CONSTRUCTION DRAWINGS AND/OR PROJECT SPECIFICATIONS.
18. CONTRACTOR SHALL MINIMIZE DISTURBANCE TO EXISTING SITE DURING CONSTRUCTION. EROSION CONTROL MEASURES, IF REQUIRED DURING CONSTRUCTION, SHALL BE IN CONFORMANCE WITH THE LOCAL GUIDELINES FOR EROSION AND SEDIMENT CONTROL.
19. THE CONTRACTOR SHALL PROTECT EXISTING IMPROVEMENTS, PAVEMENTS, CURBS, LANDSCAPING AND STRUCTURES. ANY DAMAGED PART SHALL BE REPAIRED AT CONTRACTOR’S EXPENSE TO THE SATISFACTION OF OWNER.
20. CONTRACTOR SHALL LEGALLY AND PROPERLY DISPOSE OF ALL SCRAP MATERIALS SUCH AS COAXIAL CABLES AND OTHER ITEMS REMOVED FROM THE EXISTING FACILITY. ANTENNAS AND RADIOS REMOVED SHALL BE RETURNED TO THE OWNER’S DESIGNATED LOCATION.
21. CONTRACTOR SHALL LEAVE PREMISES IN CLEAN CONDITION. TRASH AND DEBRIS SHOULD BE REMOVED FROM SITE ON A DAILY BASIS.
22. NO FILL OR EMBANKMENT MATERIAL SHALL BE PLACED ON FROZEN GROUND. FROZEN MATERIALS, SNOW OR ICE SHALL NOT BE PLACED IN ANY FILL OR EMBANKMENT.

GENERAL NOTES:

- 1.FOR THE PURPOSE OF CONSTRUCTION DRAWING, THE FOLLOWING DEFINITIONS SHALL APPLY:  
  
CONTRACTOR:GENERAL CONTRACTOR RESPONSIBLE FOR CONSTRUCTION  
  
CARRIER:DISH Wireless L.L.C.  
  
TOWER OWNER:TOWER OWNER
2. THESE DRAWINGS HAVE BEEN PREPARED USING STANDARDS OF PROFESSIONAL CARE AND COMPLETENESS NORMALLY EXERCISED UNDER SIMILAR CIRCUMSTANCES BY REPUTABLE ENGINEERS IN THIS OR SIMILAR LOCALITIES. IT IS ASSUMED THAT THE WORK DEPICTED WILL BE PERFORMED BY AN EXPERIENCED CONTRACTOR AND/OR WORKPEOPLE WHO HAVE A WORKING KNOWLEDGE OF THE APPLICABLE CODE STANDARDS AND REQUIREMENTS AND OF INDUSTRY ACCEPTED STANDARD GOOD PRACTICE. AS NOT EVERY CONDITION OR ELEMENT IS (OR CAN BE) EXPLICITLY SHOWN ON THESE DRAWINGS, THE CONTRACTOR SHALL USE INDUSTRY ACCEPTED STANDARD GOOD PRACTICE FOR MISCELLANEOUS WORK NOT EXPLICITLY SHOWN.
3. THESE DRAWINGS REPRESENT THE FINISHED STRUCTURE. THEY DO NOT INDICATE THE MEANS OR METHODS OF CONSTRUCTION. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR THE CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES. THE CONTRACTOR SHALL PROVIDE ALL MEASURES NECESSARY FOR PROTECTION OF LIFE AND PROPERTY DURING CONSTRUCTION. SUCH MEASURES SHALL INCLUDE, BUT NOT BE LIMITED TO, BRACING, FORMWORK, SHORING, ETC. SITE VISITS BY THE ENGINEER OR HIS REPRESENTATIVE WILL NOT INCLUDE INSPECTION OF THESE ITEMS AND IS FOR STRUCTURAL OBSERVATION OF THE FINISHED STRUCTURE ONLY.
4. NOTES AND DETAILS IN THE CONSTRUCTION DRAWINGS SHALL TAKE PRECEDENCE OVER GENERAL NOTES AND TYPICAL DETAILS. WHERE NO DETAILS ARE SHOWN, CONSTRUCTION SHALL CONFORM TO SIMILAR WORK ON THE PROJECT, AND/OR AS PROVIDED FOR IN THE CONTRACT DOCUMENTS. WHERE DISCREPANCIES OCCUR BETWEEN PLANS, DETAILS, GENERAL NOTES, AND SPECIFICATIONS, THE GREATER, MORE STRICT REQUIREMENTS, SHALL GOVERN. IF FURTHER CLARIFICATION IS REQUIRED CONTACT THE ENGINEER OF RECORD.
5. SUBSTANTIAL EFFORT HAS BEEN MADE TO PROVIDE ACCURATE DIMENSIONS AND MEASUREMENTS ON THE DRAWINGS TO ASSIST IN THE FABRICATION AND/OR PLACEMENT OF CONSTRUCTION ELEMENTS BUT IT IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR TO FIELD VERIFY THE DIMENSIONS, MEASUREMENTS, AND/OR CLEARANCES SHOWN IN THE CONSTRUCTION DRAWINGS PRIOR TO FABRICATION OR CUTTING OF ANY NEW OR EXISTING CONSTRUCTION ELEMENTS. IF IT IS DETERMINED THAT THERE ARE DISCREPANCIES AND/OR CONFLICTS WITH THE CONSTRUCTION DRAWINGS THE ENGINEER OF RECORD IS TO BE NOTIFIED AS SOON AS POSSIBLE.
6. PRIOR TO THE SUBMISSION OF BIDS, THE BIDDING CONTRACTOR SHALL VISIT THE CELL SITE TO FAMILIARIZE WITH THE EXISTING CONDITIONS AND TO CONFIRM THAT THE WORK CAN BE ACCOMPLISHED AS SHOWN ON THE CONSTRUCTION DRAWINGS. ANY DISCREPANCY FOUND SHALL BE BROUGHT TO THE ATTENTION OF CARRIER POC AND TOWER OWNER.
7. ALL MATERIALS FURNISHED AND INSTALLED SHALL BE IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS AND ORDINANCES. CONTRACTOR SHALL ISSUE ALL APPROPRIATE NOTICES AND COMPLY WITH ALL LAWS, ORDINANCES, RULES, REGULATIONS AND LAWFUL ORDERS OF ANY PUBLIC AUTHORITY REGARDING THE PERFORMANCE OF THE WORK. ALL WORK CARRIED OUT SHALL COMPLY WITH ALL APPLICABLE MUNICIPAL AND UTILITY COMPANY SPECIFICATIONS AND LOCAL JURISDICTIONAL CODES, ORDINANCES AND APPLICABLE REGULATIONS.
8. UNLESS NOTED OTHERWISE, THE WORK SHALL INCLUDE FURNISHING MATERIALS, EQUIPMENT, APPURTENANCES AND LABOR NECESSARY TO COMPLETE ALL INSTALLATIONS AS INDICATED ON THE DRAWINGS.
9. THE CONTRACTOR SHALL INSTALL ALL EQUIPMENT AND MATERIALS IN ACCORDANCE WITH MANUFACTURER’S RECOMMENDATIONS UNLESS SPECIFICALLY STATED OTHERWISE.
10. IF THE SPECIFIED EQUIPMENT CAN NOT BE INSTALLED AS SHOWN ON THESE DRAWINGS, THE CONTRACTOR SHALL PROPOSE AN ALTERNATIVE INSTALLATION FOR APPROVAL BY THE CARRIER AND TOWER OWNER PRIOR TO PROCEEDING WITH ANY SUCH CHANGE OF INSTALLATION.
11. CONTRACTOR IS TO PERFORM A SITE INVESTIGATION, BEFORE SUBMITTING BIDS, TO DETERMINE THE BEST ROUTING OF ALL CONDUITS FOR POWER, AND TELCO AND FOR GROUNDING CABLES AS SHOWN IN THE POWER, TELCO, AND GROUNDING PLAN DRAWINGS.
12. THE CONTRACTOR SHALL PROTECT EXISTING IMPROVEMENTS, PAVEMENTS, CURBS, LANDSCAPING AND STRUCTURES. ANY DAMAGED PART SHALL BE REPAIRED AT CONTRACTOR’S EXPENSE TO THE SATISFACTION OF DISH Wireless L.L.C. AND TOWER OWNER
13. CONTRACTOR SHALL LEGALLY AND PROPERLY DISPOSE OF ALL SCRAP MATERIALS SUCH AS COAXIAL CABLES AND OTHER ITEMS REMOVED FROM THE EXISTING FACILITY. ANTENNAS REMOVED SHALL BE RETURNED TO THE OWNER’S DESIGNATED LOCATION.
14. CONTRACTOR SHALL LEAVE PREMISES IN CLEAN CONDITION. TRASH AND DEBRIS SHOULD BE REMOVED FROM SITE ON A DAILY BASIS.




5701 SOUTH SANTA FE DRIVE  
LITTLETON, CO 80120



2000 CORPORATE DRIVE  
CANONSBURG, PA 15317



FROM ZERO TO INFINIGY  
the solutions are endless  
2500 W. HIGGINS RD., SUITE 500 |  
HOFFMAN ESTATES, IL 60169  
PHONE: 847-648-4068 | FAX: 518-690-0793  
WWW.INFINIGY.COM



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
RCD	SS	CJW

RFDS REV #: N/A

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	06/11/2021	ISSUED FOR REVIEW
0	06/23/2021	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER  
2039–Z5555C

DISH Wireless L.L.C.  
PROJECT INFORMATION  
BOHVN00014A  
171 TOWN HILL ROAD  
PLYMOUTH, CT 06786

SHEET TITLE  
GENERAL NOTES

SHEET NUMBER  
GN-2

CONCRETE, FOUNDATIONS, AND REINFORCING STEEL:

1. ALL CONCRETE SHALL BE CAST IN ACCORDANCE WITH THE ACI 301, ACI 318, ACI 336, ASTM A184, ASTM A185 AND THE DESIGN AND CONSTRUCTION SPECIFICATION FOR CAST-IN-PLACE CONCRETE.
2. UNLESS NOTED OTHERWISE, SOIL BEARING PRESSURE USED FOR DESIGN OF SLABS AND FOUNDATIONS IS ASSUMED TO BE 1000 psf.
3. ALL CONCRETE SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH ( $f'_c$ ) OF 3000 psi AT 28 DAYS, UNLESS NOTED OTHERWISE. NO MORE THAN 90 MINUTES SHALL ELAPSE FROM BATCH TIME TO TIME OF PLACEMENT UNLESS APPROVED BY THE ENGINEER OF RECORD. TEMPERATURE OF CONCRETE SHALL NOT EXCEED 90°F AT TIME OF PLACEMENT.
4. CONCRETE EXPOSED TO FREEZE-THAW CYCLES SHALL CONTAIN AIR ENTRAINING ADMIXTURES. AMOUNT OF AIR ENTRAINMENT TO BE BASED ON SIZE OF AGGREGATE AND F3 CLASS EXPOSURE (VERY SEVERE). CEMENT USED TO BE TYPE II PORTLAND CEMENT WITH A MAXIMUM WATER-TO-CEMENT RATIO (W/C) OF 0.45.
5. ALL STEEL REINFORCING SHALL CONFORM TO ASTM A615. ALL WELDED WIRE FABRIC (WWF) SHALL CONFORM TO ASTM A185. ALL SPLICES SHALL BE CLASS "B" TENSION SPLICES, UNLESS NOTED OTHERWISE. ALL HOOKS SHALL BE STANDARD 90 DEGREE HOOKS, UNLESS NOTED OTHERWISE. YIELD STRENGTH ( $F_y$ ) OF STANDARD DEFORMED BARS ARE AS FOLLOWS:  
  - #4 BARS AND SMALLER 40 ksi
  - #5 BARS AND LARGER 60 ksi
6. THE FOLLOWING MINIMUM CONCRETE COVER SHALL BE PROVIDED FOR REINFORCING STEEL UNLESS SHOWN OTHERWISE ON DRAWINGS:
  - CONCRETE CAST AGAINST AND PERMANENTLY EXPOSED TO EARTH 3"
  - CONCRETE EXPOSED TO EARTH OR WEATHER:
    - #6 BARS AND LARGER 2"
    - #5 BARS AND SMALLER 1-1/2"
  - CONCRETE NOT EXPOSED TO EARTH OR WEATHER:
    - SLAB AND WALLS 3/4"
    - BEAMS AND COLUMNS 1-1/2"
7. A TOOLED EDGE OR A 3/4" CHAMFER SHALL BE PROVIDED AT ALL EXPOSED EDGES OF CONCRETE, UNLESS NOTED OTHERWISE, IN ACCORDANCE WITH ACI 301 SECTION 4.2.4.

**ELECTRICAL INSTALLATION NOTES:**

1. ALL ELECTRICAL WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS, NEC AND ALL APPLICABLE FEDERAL, STATE, AND LOCAL CODES/ORDINANCES.
2. CONDUIT ROUTINGS ARE SCHEMATIC. CONTRACTOR SHALL INSTALL CONDUITS SO THAT ACCESS TO EQUIPMENT IS NOT BLOCKED AND TRIP HAZARDS ARE ELIMINATED.
3. WIRING, RACEWAY AND SUPPORT METHODS AND MATERIALS SHALL COMPLY WITH THE REQUIREMENTS OF THE NEC.
4. ALL CIRCUITS SHALL BE SEGREGATED AND MAINTAIN MINIMUM CABLE SEPARATION AS REQUIRED BY THE NEC.
- 4.1. ALL EQUIPMENT SHALL BEAR THE UNDERWRITERS LABORATORIES LABEL OF APPROVAL, AND SHALL CONFORM TO REQUIREMENT OF THE NATIONAL ELECTRICAL CODE.
- 4.2. ALL OVERCURRENT DEVICES SHALL HAVE AN INTERRUPTING CURRENT RATING THAT SHALL BE GREATER THAN THE SHORT CIRCUIT CURRENT TO WHICH THEY ARE SUBJECTED, 22,000 AIC MINIMUM. VERIFY AVAILABLE SHORT CIRCUIT CURRENT DOES NOT EXCEED THE RATING OF ELECTRICAL EQUIPMENT IN ACCORDANCE WITH ARTICLE 110.24 NEC OR THE MOST CURRENT ADOPTED CODE PRE THE GOVERNING JURISDICTION.
5. EACH END OF EVERY POWER PHASE CONDUCTOR, GROUNDING CONDUCTOR, AND TELCO CONDUCTOR OR CABLE SHALL BE LABELED WITH COLOR-CODED INSULATION OR ELECTRICAL TAPE (3M BRAND, 1/2" PLASTIC ELECTRICAL TAPE WITH UV PROTECTION, OR EQUAL). THE IDENTIFICATION METHOD SHALL CONFORM WITH NEC AND OSHA.
6. ALL ELECTRICAL COMPONENTS SHALL BE CLEARLY LABELED WITH LAMICOID TAGS SHOWING THEIR RATED VOLTAGE, PHASE CONFIGURATION, WIRE CONFIGURATION, POWER OR AMPACITY RATING AND BRANCH CIRCUIT ID NUMBERS (i.e. PANEL BOARD AND CIRCUIT ID'S).
7. PANEL BOARDS (ID NUMBERS) SHALL BE CLEARLY LABELED WITH PLASTIC LABELS.
8. TIE WRAPS ARE NOT ALLOWED.
9. ALL POWER AND EQUIPMENT GROUND WIRING IN TUBING OR CONDUIT SHALL BE SINGLE COPPER CONDUCTOR (#14 OR LARGER) WITH TYPE THHW, THWN, THWN-2, XHHW, XHHW-2, THW, THW-2, RHW, OR RHW-2 INSULATION UNLESS OTHERWISE SPECIFIED.
10. SUPPLEMENTAL EQUIPMENT GROUND WIRING LOCATED INDOORS SHALL BE SINGLE COPPER CONDUCTOR (#6 OR LARGER) WITH TYPE THHW, THWN, THWN-2, XHHW, XHHW-2, THW, THW-2, RHW, OR RHW-2 INSULATION UNLESS OTHERWISE SPECIFIED.
11. POWER AND CONTROL WIRING IN FLEXIBLE CORD SHALL BE MULTI-CONDUCTOR, TYPE SOOW CORD (#14 OR LARGER) UNLESS OTHERWISE SPECIFIED.
12. POWER AND CONTROL WIRING FOR USE IN CABLE TRAY SHALL BE MULTI-CONDUCTOR, TYPE TC CABLE (#14 OR LARGER), WITH TYPE THHW, THWN, THWN-2, XHHW, XHHW-2, THW, THW-2, RHW, OR RHW-2 INSULATION UNLESS OTHERWISE SPECIFIED.
13. ALL POWER AND GROUNDING CONNECTIONS SHALL BE CRIMP-STYLE, COMPRESSION WIRE LUGS AND WIRE NUTS BY THOMAS AND BETTS (OR EQUAL). LUGS AND WIRE NUTS SHALL BE RATED FOR OPERATION NOT LESS THAN 75° C (90° C IF AVAILABLE).
14. RACEWAY AND CABLE TRAY SHALL BE LISTED OR LABELED FOR ELECTRICAL USE IN ACCORDANCE WITH NEMA, UL, ANSI/IEEE AND NEC.
15. ELECTRICAL METALLIC TUBING (EMT), INTERMEDIATE METAL CONDUIT (IMC), OR RIGID METAL CONDUIT (RMC) SHALL BE USED FOR EXPOSED INDOOR LOCATIONS.


16. ELECTRICAL METALLIC TUBING (EMT) OR METAL-CLAD CABLE (MC) SHALL BE USED INDOORS AND OUTDOORS, WHERE VIBRATION OCCURS OR FLEXIBILITY IS NEEDED.
17. SCHEDULE 40 PVC UNDERGROUND ON STRAIGHTS AND SCHEDULE 80 PVC FOR ALL ELBOWS/90s AND ALL APPROVED ABOVE GRADE PVC CONDUIT.
18. LIQUID-TIGHT FLEXIBLE METALLIC CONDUIT (LIQUID-TITE FLEX) SHALL BE USED INDOORS AND OUTDOORS, WHERE VIBRATION OCCURS OR FLEXIBILITY IS NEEDED.
19. CONDUIT AND TUBING FITTINGS SHALL BE THREADED OR COMPRESSION-TYPE AND APPROVED FOR THE LOCATION USED. SET SCREW FITTINGS ARE NOT ACCEPTABLE.
20. CABINETS, BOXES AND WIRE WAYS SHALL BE LABELED FOR ELECTRICAL USE IN ACCORDANCE WITH NEMA, UL, ANSI/IEEE AND THE NEC.
21. WIREWAYS SHALL BE METAL WITH AN ENAMEL FINISH AND INCLUDE A HINGED COVER, DESIGNED TO SWING OPEN DOWNWARDS (WIREMOLD SPECIMATE WIREWAY).
22. SLOTTED WIRING DUCT SHALL BE PVC AND INCLUDE COVER (PANDUIT TYPE E OR EQUAL).
23. CONDUITS SHALL BE FASTENED SECURELY IN PLACE WITH APPROVED NON-PERFORATED STRAPS AND HANGERS. EXPLOSIVE DEVICES (i.e. POWDER-ACTUATED) FOR ATTACHING HANGERS TO STRUCTURE WILL NOT BE PERMITTED. CLOSELY FOLLOW THE LINES OF THE STRUCTURE, MAINTAIN CLOSE PROXIMITY TO THE STRUCTURE AND KEEP CONDUITS IN TIGHT ENVELOPES. CHANGES IN DIRECTION TO ROUTE AROUND OBSTACLES SHALL BE MADE WITH CONDUIT OUTLET BODIES. CONDUIT SHALL BE INSTALLED IN A NEAT AND WORKMANLIKE MANNER. PARALLEL AND PERPENDICULAR TO STRUCTURE WALL AND CEILING LINES. ALL CONDUIT SHALL BE FISHED TO CLEAR OBSTRUCTIONS. ENDS OF CONDUITS SHALL BE TEMPORARILY CAPPED FLUSH TO FINISH GRADE TO PREVENT CONCRETE, PLASTER OR DIRT FROM ENTERING. CONDUITS SHALL BE RIGIDLY CLAMPED TO BOXES BY GALVANIZED MALLEABLE IRON BUSHING ON INSIDE AND GALVANIZED MALLEABLE IRON LOCKNUT ON OUTSIDE AND INSIDE.
24. EQUIPMENT CABINETS, TERMINAL BOXES, JUNCTION BOXES AND PULL BOXES SHALL BE GALVANIZED OR EPOXY-COATED SHEET STEEL. SHALL MEET OR EXCEED UL 50 AND BE RATED NEMA 1 (OR BETTER) FOR INTERIOR LOCATIONS AND NEMA 3 (OR BETTER) FOR EXTERIOR LOCATIONS.
25. METAL RECEPTACLE, SWITCH AND DEVICE BOXES SHALL BE GALVANIZED, EPOXY-COATED OR NON-CORRODING; SHALL MEET OR EXCEED UL 514A AND NEMA OS 1 AND BE RATED NEMA 1 (OR BETTER) FOR INTERIOR LOCATIONS AND WEATHER PROTECTED (WP OR BETTER) FOR EXTERIOR LOCATIONS.
26. NONMETALLIC RECEPTACLE, SWITCH AND DEVICE BOXES SHALL MEET OR EXCEED NEMA OS 2 (NEWEST REVISION) AND BE RATED NEMA 1 (OR BETTER) FOR INTERIOR LOCATIONS AND WEATHER PROTECTED (WP OR BETTER) FOR EXTERIOR LOCATIONS.
27. THE CONTRACTOR SHALL NOTIFY AND OBTAIN NECESSARY AUTHORIZATION FROM THE CARRIER AND/OR DISH Wireless L.L.C. AND TOWER OWNER BEFORE COMMENCING WORK ON THE AC POWER DISTRIBUTION PANELS.
28. THE CONTRACTOR SHALL PROVIDE NECESSARY TAGGING ON THE BREAKERS, CABLES AND DISTRIBUTION PANELS IN ACCORDANCE WITH THE APPLICABLE CODES AND STANDARDS TO SAFEGUARD LIFE AND PROPERTY.
29. INSTALL LAMICOID LABEL ON THE METER CENTER TO SHOW "DISH Wireless L.L.C.".
30. ALL EMPTY/SPARE CONDUITS THAT ARE INSTALLED ARE TO HAVE A METERED MULE TAPE PULL CORD INSTALLED.



5701 SOUTH SANTA FE DRIVE  
LITTLETON, CO 80120



2000 CORPORATE DRIVE  
CANONSBURG, PA 15317



IT IS A VIOLATION OF LAW FOR ANY PERSON,  
UNLESS THEY ARE ACTING UNDER THE DIRECTION  
OF A LICENSED PROFESSIONAL ENGINEER,  
TO ALTER THIS DOCUMENT.

DRAWN BY: | CHECKED BY: | APPROVED BY:

RCD	SS	CJW
-----	----	-----

RFDS REV #: N/A

# CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	06/11/2021	ISSUED FOR REVIEW
0	06/23/2021	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER  
2039-Z5555C

DISH Wireless L.L.C.  
PROJECT INFORMATION  
BOHVN00014A  
171 TOWN HILL ROAD  
PLYMOUTH, CT 06786

SHEET TITLE

GENERAL NOTES

SHEET NUMBER

**GN-3**

GROUNDING NOTES:

1. ALL GROUND ELECTRODE SYSTEMS (INCLUDING TELECOMMUNICATION, RADIO, LIGHTNING PROTECTION AND AC POWER GES’S) SHALL BE BONDED TOGETHER AT OR BELOW GRADE, BY TWO OR MORE COPPER BONDING CONDUCTORS IN ACCORDANCE WITH THE NEC.
2. THE CONTRACTOR SHALL PERFORM IEEE FALL–OF–POTENTIAL RESISTANCE TO EARTH TESTING (PER IEEE 1100 AND 81) FOR GROUND ELECTRODE SYSTEMS, THE CONTRACTOR SHALL FURNISH AND INSTALL SUPPLEMENTAL GROUND ELECTRODES AS NEEDED TO ACHIEVE A TEST RESULT OF 5 OHMS OR LESS.
3. THE CONTRACTOR IS RESPONSIBLE FOR PROPERLY SEQUENCING GROUNDING AND UNDERGROUND CONDUIT INSTALLATION AS TO PREVENT ANY LOSS OF CONTINUITY IN THE GROUNDING SYSTEM OR DAMAGE TO THE CONDUIT AND PROVIDE TESTING RESULTS.
4. METAL CONDUIT AND TRAY SHALL BE GROUNDED AND MADE ELECTRICALLY CONTINUOUS WITH LISTED BONDING FITTINGS OR BY BONDING ACROSS THE DISCONTINUITY WITH #6 COPPER WIRE UL APPROVED GROUNDING TYPE CONDUIT CLAMPS.
5. METAL RACEWAY SHALL NOT BE USED AS THE NEC REQUIRED EQUIPMENT GROUND CONDUCTOR. STRANDED COPPER CONDUCTORS WITH GREEN INSULATION, SIZED IN ACCORDANCE WITH THE NEC, SHALL BE FURNISHED AND INSTALLED WITH THE POWER CIRCUITS TO BTS EQUIPMENT.
6. EACH CABINET FRAME SHALL BE DIRECTLY CONNECTED TO THE MASTER GROUND BAR WITH GREEN INSULATED SUPPLEMENTAL EQUIPMENT GROUND WIRES, #6 STRANDED COPPER OR LARGER FOR INDOOR BTS; #2 BARE SOLID TINNED COPPER FOR OUTDOOR BTS.
7. CONNECTIONS TO THE GROUND BUS SHALL NOT BE DOUBLED UP OR STACKED BACK TO BACK CONNECTIONS ON OPPOSITE SIDE OF THE GROUND BUS ARE PERMITTED.
8. ALL EXTERIOR GROUND CONDUCTORS BETWEEN EQUIPMENT/GROUND BARS AND THE GROUND RING SHALL BE #2 SOLID TINNED COPPER UNLESS OTHERWISE INDICATED.
9. ALUMINUM CONDUCTOR OR COPPER CLAD STEEL CONDUCTOR SHALL NOT BE USED FOR GROUNDING CONNECTIONS.
10. USE OF 90° BENDS IN THE PROTECTION GROUNDING CONDUCTORS SHALL BE AVOIDED WHEN 45° BENDS CAN BE ADEQUATELY SUPPORTED.
11. EXOTHERMIC WELDS SHALL BE USED FOR ALL GROUNDING CONNECTIONS BELOW GRADE.
12. ALL GROUND CONNECTIONS ABOVE GRADE (INTERIOR AND EXTERIOR) SHALL BE FORMED USING HIGH PRESS CRIMPS.
13. COMPRESSION GROUND CONNECTIONS MAY BE REPLACED BY EXOTHERMIC WELD CONNECTIONS.
14. ICE BRIDGE BONDING CONDUCTORS SHALL BE EXOTHERMICALLY BONDED OR BOLTED TO THE BRIDGE AND THE TOWER GROUND BAR.
15. APPROVED ANTIOXIDANT COATINGS (i.e. CONDUCTIVE GEL OR PASTE) SHALL BE USED ON ALL COMPRESSION AND BOLTED GROUND CONNECTIONS.
16. ALL EXTERIOR GROUND CONNECTIONS SHALL BE COATED WITH A CORROSION RESISTANT MATERIAL.
17. MISCELLANEOUS ELECTRICAL AND NON–ELECTRICAL METAL BOXES, FRAMES AND SUPPORTS SHALL BE BONDED TO THE GROUND RING, IN ACCORDANCE WITH THE NEC.
18. BOND ALL METALLIC OBJECTS WITHIN 6 ft OF MAIN GROUND RING WITH (1) #2 BARE SOLID TINNED COPPER GROUND CONDUCTOR.
19. GROUND CONDUCTORS USED FOR THE FACILITY GROUNDING AND LIGHTNING PROTECTION SYSTEMS SHALL NOT BE ROUTED THROUGH METALLIC OBJECTS THAT FORM A RING AROUND THE CONDUCTOR, SUCH AS METALLIC CONDUITS, METAL SUPPORT CLIPS OR SLEEVES THROUGH WALLS OR FLOORS. WHEN IT IS REQUIRED TO BE HOUSED IN CONDUIT TO MEET CODE REQUIREMENTS OR LOCAL CONDITIONS, NON–METALLIC MATERIAL SUCH AS PVC CONDUIT SHALL BE USED. WHERE USE OF METAL CONDUIT IS UNAVOIDABLE (i.e., NONMETALLIC CONDUIT PROHIBITED BY LOCAL CODE) THE GROUND CONDUCTOR SHALL BE BONDED TO EACH END OF THE METAL CONDUIT.
20. ALL GROUNDS THAT TRANSITION FROM BELOW GRADE TO ABOVE GRADE MUST BE #2 BARE SOLID TINNED COPPER IN 3/4” NON–METALLIC, FLEXIBLE CONDUIT FROM 24” BELOW GRADE TO WITHIN 3” TO 6” OF CAD–WELD TERMINATION POINT. THE EXPOSED END OF THE CONDUIT MUST BE SEALED WITH SILICONE CAULK. (ADD TRANSITIONING GROUND STANDARD DETAIL AS WELL).
21. BUILDINGS WHERE THE MAIN GROUNDING CONDUCTORS ARE REQUIRED TO BE ROUTED TO GRADE, THE CONTRACTOR SHALL ROUTE TWO GROUNDING CONDUCTORS FROM THE ROOFTOP, TOWERS, AND WATER TOWERS GROUNDING RING, TO THE EXISTING GROUNDING SYSTEM, THE GROUNDING CONDUCTORS SHALL NOT BE SMALLER THAN 2/0 COPPER. ROOFTOP GROUNDING RING SHALL BE BONDED TO THE EXISTING GROUNDING SYSTEM, THE BUILDING STEEL COLUMNS, LIGHTNING PROTECTION SYSTEM, AND BUILDING MAIN WATER LINE (FERROUS OR NONFERROUS METAL PIPING ONLY). DO NOT ATTACH GROUNDING TO FIRE SPRINKLER SYSTEM PIPES.



5701 SOUTH SANTA FE DRIVE  
LITTLETON, CO 80120




2000 CORPORATE DRIVE  
CANONSBURG, PA 15317



FROM ZERO TO INFINIGY

the solutions are endless  
2500 W. HIGGINS RD., SUITE 500 |  
HOFFMAN ESTATES, IL 60169  
PHONE: 847-648-4068 | FAX: 518-690-0793  
WWW.INFINIGY.COM



IT IS A VIOLATION OF LAW FOR ANY PERSON,  
UNLESS THEY ARE ACTING UNDER THE DIRECTION  
OF A LICENSED PROFESSIONAL ENGINEER,  
TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
RCD	SS	CJW

RFDS REV #: N/A

CONSTRUCTION  
DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	06/11/2021	ISSUED FOR REVIEW
0	06/23/2021	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER  
2039–Z5555C

DISH Wireless L.L.C.  
PROJECT INFORMATION  
BOHVN00014A  
171 TOWN HILL ROAD  
PLYMOUTH, CT 06786

SHEET TITLE  
GENERAL NOTES

SHEET NUMBER  
GN-4

# Exhibit D

## **Structural Analysis Report**

Date: **June 06, 2021**



Crown Castle  
2000 Corporate Drive  
Canonsburg, PA 15317  
(724) 416-20000

**Subject:** **Structural Analysis Report**

**Carrier Designation:** **DISH Network Co-Locate**  
**Site Number:** BOHVN00014A  
**Site Name:** CT-CCI-T-826768

**Crown Castle Designation:** **BU Number:** 826768  
**Site Name:** PLYMOUTH/RT 6  
**JDE Job Number:** 645129  
**Work Order Number:** 1966237  
**Order Number:** 553358 Rev. 1

**Engineering Firm Designation:** **Crown Castle Project Number:** 1966237

**Site Data:** **171 Town Hill Road, Plymouth, Litchfield County, CT**  
**Latitude 41° 40' 6.197", Longitude -73° 1' 11.842"**  
**169 Foot - Monopole Tower**

Crown Castle is pleased to submit this "**Structural Analysis Report**" to determine the structural integrity of the above-mentioned tower.

The purpose of the analysis is to determine acceptability of the tower stress level. Based on our analysis we have determined the tower stress level for the structure and foundation, under the following load case, to be:

LC7: Proposed Equipment Configuration


**Sufficient Capacity - 78.5%**

This analysis utilizes an ultimate 3-second gust wind speed of 120 mph as required by the 2018 Connecticut State Building Code. Applicable Standard references and design criteria are listed in Section 2 - "Analysis Criteria".

Structural analysis prepared by: Matthew Hussak

Respectfully submitted by:

Terry P. Styran, P.E.  
Senior Project Engineer



## TABLE OF CONTENTS

### 1) INTRODUCTION

### 2) ANALYSIS CRITERIA

Table 1 - Proposed Equipment Configuration

Table 2 - Other Considered Equipment

### 3) ANALYSIS PROCEDURE

Table 3 - Documents Provided

3.1) Analysis Method

3.2) Assumptions

### 4) ANALYSIS RESULTS

Table 4 - Section Capacity (Summary)

Table 5 - Tower Component Stresses vs. Capacity - LC7

4.1) Recommendations

### 5) APPENDIX A

tnxTower Output

### 6) APPENDIX B

Base Level Drawing

### 7) APPENDIX C

Additional Calculations

## 1) INTRODUCTION

This tower is a 169 ft Monopole tower designed by PIROD MANUFACTURES INC..

## 2) ANALYSIS CRITERIA

<b>TIA-222 Revision:</b>	TIA-222-H
<b>Risk Category:</b>	II
<b>Wind Speed:</b>	120 mph
<b>Exposure Category:</b>	C
<b>Topographic Factor:</b>	1
<b>Ice Thickness:</b>	1.5 in
<b>Wind Speed with Ice:</b>	50 mph
<b>Service Wind Speed:</b>	60 mph

**Table 1 - Proposed Equipment Configuration**

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)
132.0	132.0	3	fujitsu	TA08025-B604	1	1-1/2
		3	fujitsu	TA08025-B605		
		3	jma wireless	MX08FRO665-21 w/ Mount Pipe		
		1	raycap	RDIDC-9181-PF-48		
		1	tower mounts	Commscope MC-PK8-DSH		

**Table 2 - Other Considered Equipment**

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)
164.0	168.0	3	rfi antennas	COL45-70	11 3	7/8 1-5/8
	165.0	3	ericsson	AIR 32 B2A/B66AA w/ Mount Pipe		
		3	ericsson	AIR6449 B41 w/ Mount Pipe		
		3	ericsson	RADIO 4449 B71 B85A_T-MOBILE		
		3	ericsson	RRUS 4415 B25		
		3	rfs celwave	APXVAARR24_43-U-NA20 w/ Mount Pipe		
	164.0	1	tower mounts	Platform Mount [LP 404-1_KCKR]		
155.0	155.0	3	alcatel lucent	1900MHz RRH	4	1-1/4
		3	alcatel lucent	800MHZ RRH		
		3	alcatel lucent	TD-RRH8x20-25		
		3	rfs celwave	APXVSPP18-C-A20 w/ Mount Pipe		
		3	rfs celwave	APXVTM14-C-120 w/ Mount Pipe		
		1	tower mounts	Platform Mount [LP 305-1]		
142.0	142.0	6	antel	LPA-80080/6CF w/ Mount Pipe	8	1-5/8
		3	commscope	SBNHH-1D65B		

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)
		3	commscope	SBNHH-1D65B w/ Mount Pipe		
		2	rfs celwave	DB-T1-6Z-8AB-0Z		
		3	samsung telecommunications	MT6407-77A w/ Mount Pipe		
		3	samsung telecommunications	RFV01U-D1A		
		3	samsung telecommunications	RFV01U-D2A		
		1	tower mounts	Platform Mount [LP 403-1]		
121.0	125.0	1	rfs celwave	201-4	1	1/2
	121.0	1	tower mounts	Side Arm Mount [SO 701-1]		
115.0	115.0	3	cci antennas	DTMABP7819VG12A	12 6 3 2	1-5/8 5/8 3/8 conduit
		6	cci antennas	TPX-070821		
		3	ericsson	RRUS 11		
		3	ericsson	RRUS 12 B2		
		3	ericsson	RRUS 4426 B66		
		3	ericsson	RRUS 4478 B14		
		3	ericsson	RRUS 4478 B5		
		3	ericsson	WCS RRUS-32-B30		
		6	kaelus	DBCT108F1V92-1		
		3	kathrein	80010965		
		3	kmw communications	AM-X-CD-16-65-00T-RET		
		3	powerwave technologies	7770.00		
		3	quintel technology	QS66512-2		
		1	raycap	DC6-48-60-18-8C		
		2	raycap	DC6-48-60-18-8F		
		1	tower mounts	Platform Mount [LP 301-1]		
105.0	105.0	3	rfs celwave	APXV18-206517S-C w/ Mount Pipe	6	1-5/8
74.0	83.0	1	decibel	DB810T3E-XT	1	7/8
	74.0	1	tower mounts	Side Arm Mount [SO 701-1]		

### 3) ANALYSIS PROCEDURE

Table 3 - Documents Provided

Document	Reference	Source
4-GEOTECHNICAL REPORTS	3491991	CCISITES
4-TOWER FOUNDATION DRAWINGS/DESIGN/SPECS	3678682	CCISITES
4-TOWER MANUFACTURER DRAWINGS	3491992	CCISITES

### 3.1) Analysis Method

tnxTower (version 8.0.9.0), a commercially available analysis software package, was used to create a three-dimensional model of the tower and calculate member stresses for various loading cases. Selected output from the analysis is included in Appendix A. When applicable, Crown Castle has calculated and provided the effective area for panel antennas using approved methods following the intent of the TIA-222 standard.

### 3.2) Assumptions

- 1) Tower and structures were maintained in accordance with the TIA-222 Standard.
- 2) The configuration of antennas, transmission cables, mounts and other appurtenances are as specified in Tables 1 and 2 and the referenced drawings.

This analysis may be affected if any assumptions are not valid or have been made in error. Crown Castle should be notified to determine the effect on the structural integrity of the tower.

## 4) ANALYSIS RESULTS

**Table 4 - Section Capacity (Summary)**

Section No.	Elevation (ft)	Component Type	Size	Critical Element	P (K)	SF*P_allow (K)	% Capacity	Pass / Fail
L1	169 - 164.25	Pole	TP26x18x0.25	1	-0.45	1060.11	0.2	Pass
L2	164.25 - 129.75	Pole	TP34.0625x21.5x0.3125	2	-15.10	1976.75	20.6	Pass
L3	129.75 - 96.08	Pole	TP41.75x32.1327x0.375	3	-30.46	2937.41	38.2	Pass
L4	96.08 - 63.25	Pole	TP49.0625x39.8023x0.375	4	-40.29	3460.30	54.9	Pass
L5	63.25 - 31.25	Pole	TP56.125x46.9543x0.375	5	-51.45	3964.20	67.2	Pass
L6	31.25 - 0	Pole	TP62.9375x53.8466x0.375	6	-66.55	4574.01	78.5	Pass
							Summary	
						Pole (L6)	78.5	Pass
						Rating =	78.5	Pass

**Table 5 - Tower Component Stresses vs. Capacity - LC7**

Notes	Component	Elevation (ft)	% Capacity	Pass / Fail
1	Anchor Rods	0	76.1	Pass
1	Base Plate	0	36.9	Pass
1	Base Foundation (Structure)	0	69.3	Pass
1	Base Foundation (Soil Interaction)	0	53.4	Pass

<b>Structure Rating (max from all components) =</b>	<b>78.5%</b>
---	--------------

Notes:

- 1) See additional documentation in "Appendix C – Additional Calculations" for calculations supporting the % capacity consumed.

### 4.1) Recommendations

The tower and its foundation have sufficient capacity to carry the proposed load configuration. No modifications are required at this time.

## **APPENDIX A**

### **TNXTOWER OUTPUT**



## Tower Input Data

The tower is a monopole.

This tower is designed using the TIA-222-H standard.

The following design criteria apply:

- Tower is located in Litchfield County, Connecticut.
- Tower base elevation above sea level: 890.00 ft.
- Basic wind speed of 120 mph.
- Risk Category II.
- Exposure Category C.
- Simplified Topographic Factor Procedure for wind speed-up calculations is used.
- Topographic Category: 1.
- Crest Height: 0.00 ft.
- Nominal ice thickness of 1.5000 in.
- Ice thickness is considered to increase with height.
- Ice density of 56 pcf.
- A wind speed of 50 mph is used in combination with ice.
- Temperature drop of 50 °F.
- Deflections calculated using a wind speed of 60 mph.
- A non-linear (P-delta) analysis was used.
- Pressures are calculated at each section.
- Stress ratio used in pole design is 1.
- Tower analysis based on target reliabilities in accordance with Annex S.
- Load Modification Factors used:  $K_{es}(F_w) = 0.95$ ,  $K_{es}(t_i) = 0.85$ .
- Maximum demand-capacity ratio is: 1.05.
- Local bending stresses due to climbing loads, feed line supports, and appurtenance mounts are not considered.

## Options

Consider Moments - Legs	Distribute Leg Loads As Uniform	Use ASCE 10 X-Brace Ly Rules
Consider Moments - Horizontals	Assume Legs Pinned	Calculate Redundant Bracing Forces
Consider Moments - Diagonals	✓ Assume Rigid Index Plate	Ignore Redundant Members in FEA
Use Moment Magnification	✓ Use Clear Spans For Wind Area	SR Leg Bolts Resist Compression
✓ Use Code Stress Ratios	Use Clear Spans For KL/r	All Leg Panels Have Same Allowable
✓ Use Code Safety Factors - Guys	Retention Guys To Initial Tension	Offset Girt At Foundation
Escalate Ice	✓ Bypass Mast Stability Checks	✓ Consider Feed Line Torque
Always Use Max Kz	✓ Use Azimuth Dish Coefficients	Include Angle Block Shear Check
Use Special Wind Profile	✓ Project Wind Area of Appurt.	Use TIA-222-H Bracing Resist.
Include Bolts In Member Capacity	Autocalc Torque Arm Areas	Exemption
Leg Bolts Are At Top Of Section	Add IBC .6D+W Combination	Use TIA-222-H Tension Splice
Secondary Horizontal Braces Leg	✓ Sort Capacity Reports By Component	Exemption
Use Diamond Inner Bracing (4 Sided)	Triangulate Diamond Inner Bracing	
SR Members Have Cut Ends	Treat Feed Line Bundles As Cylinder	
SR Members Are Concentric	Ignore KL/ry For 60 Deg. Angle Legs	

### Poles

- ✓ Include Shear-Torsion Interaction
- Always Use Sub-Critical Flow
- Use Top Mounted Sockets
- Pole Without Linear Attachments
- Pole With Shroud Or No
- Appurtenances
- Outside and Inside Corner Radii Are Known

## Tapered Pole Section Geometry

Section	Elevation ft	Section Length ft	Splice Length ft	Number of Sides	Top Diameter in	Bottom Diameter in	Wall Thickness in	Bend Radius in	Pole Grade
L1	169.00-164.25	4.75	2.38	18	18.0000	26.0000	0.2500	1.0000	A572-65 (65 ksi)
L2	164.25-129.75	36.88	3.83	18	21.5000	34.0625	0.3125	1.2500	A572-65 (65 ksi)
L3	129.75-96.08	37.50	4.67	18	32.1327	41.7500	0.3750	1.5000	A572-65 (65 ksi)
L4	96.08-63.25	37.50	5.50	18	39.8023	49.0625	0.3750	1.5000	A572-65 (65 ksi)
L5	63.25-31.25	37.50	6.25	18	46.9543	56.1250	0.3750	1.5000	A572-65 (65 ksi)
L6	31.25-0.00	37.50		18	53.8466	62.9375	0.3750	1.5000	A572-65 (65 ksi)

### Tapered Pole Properties

Section	Tip Dia. in	Area in <sup>2</sup>	I in <sup>4</sup>	r in	C in	I/C in <sup>3</sup>	J in <sup>4</sup>	It/Q in <sup>2</sup>	w in	w/t
L1	18.2391	14.0846	560.6340	6.3012	9.1440	61.3117	1122.0058	7.0437	2.7280	10.912
	26.3625	20.4326	1711.6544	9.1412	13.2080	129.5922	3425.5610	10.2183	4.1360	16.544
L2	22.6051	21.0154	1191.8828	7.5216	10.9220	109.1268	2385.3338	10.5097	3.2340	10.349
	34.5398	33.4758	4817.4335	11.9812	17.3038	278.4040	9641.2058	16.7411	5.4450	17.424
L3	33.5680	37.7996	4816.4038	11.2740	16.3234	295.0611	9639.1451	18.9034	4.9954	13.321
	42.3362	49.2466	10650.982	14.6881	21.2090	502.1916	21315.979	24.6280	6.6880	17.835
L4	41.5295	46.9284	9216.5336	13.9967	20.2196	455.8222	18445.194	23.4686	6.3452	16.921
	49.7615	57.9503	17355.137	17.2841	24.9238	696.3293	34733.111	28.9807	7.9750	21.267
L5	48.9866	55.4411	15196.922	16.5357	23.8528	637.1126	30413.842	27.7258	7.6040	20.277
	56.9330	66.3564	26056.150	19.7913	28.5115	913.8821	52146.586	33.1845	9.2180	24.581
L6	56.1579	63.6445	22990.273	18.9824	27.3541	840.4705	46010.797	31.8283	8.8170	23.512
	63.8506	74.4650	36822.894	22.2097	31.9722	1151.7142	73694.241	37.2396	10.4170	27.779

Tower Elevation ft	Gusset Area (per face) ft <sup>2</sup>	Gusset Thickness in	Gusset Grade	Adjust. Factor A <sub>r</sub>	Adjust. Factor A <sub>r</sub>	Weight Mult.	Double Angle Stitch Bolt Spacing Diagonals in	Double Angle Stitch Bolt Spacing Horizontal in	Double Angle Stitch Bolt Spacing Redundants in
L1 169.00- 164.25				1	1	1			
L2 164.25- 129.75				1	1	1			
L3 129.75- 96.08				1	1	1			
L4 96.08- 63.25				1	1	1			
L5 63.25- 31.25				1	1	1			
L6 31.25-0.00				1	1	1			

### Feed Line/Linear Appurtenances - Entered As Round Or Flat

Description	Sector	Exclude From Torque Calculation	Component Type	Placement ft	Total Number	Number Per Row	Start/End Position	Width or Diameter in	Perimeter in	Weight plf
-------------	--------	--	-------------------	-----------------	-----------------	-------------------	-----------------------	----------------------------	-----------------	---------------

Description	Sector	Exclude From Torque Calculation	Component Type	Placement ft	Total Number	Number Per Row	Start/End Position	Width or Diameter in	Perimeter in	Weight plf
Safety Line 3/8	A	No	Surface Ar (CaAa)	169.00 - 0.00	1	1	-0.500 -0.500	0.3750		0.22
PiRod Ladder	A	No	Surface Af (CaAa)	169.00 - 0.00	1	1	-0.500 -0.500	0.5400	1.6965	2.00
***										
CU12PSM9P6XXX(1-1/2)	B	No	Surface Ar (CaAa)	132.00 - 0.00	1	1	-0.450 -0.425	1.6000		2.35
***										
LDF4-50A(1/2)	A	No	Surface Ar (CaAa)	121.00 - 0.00	1	1	-0.210 -0.200	0.6300		0.15
***										
LDF7-50A(1-5/8)	A	No	Surface Ar (CaAa)	115.00 - 0.00	12	6	0.115 0.300	1.9800		0.82
2" Flexible Conduit	A	No	Surface Ar (CaAa)	115.00 - 0.00	2	1	0.310 0.340	2.0000		0.34
***										
LDF7-50A(1-5/8)	B	No	Surface Ar (CaAa)	105.00 - 0.00	6	6	-0.250 -0.060	1.9800		0.82
***										
LDF5-50A(7/8)	A	No	Surface Ar (CaAa)	74.00 - 0.00	1	1	0.000 0.010	1.0900		0.33
*****										

### Feed Line/Linear Appurtenances - Entered As Area

Description	Face or Leg	Allow Shield	Exclude From Torque Calculation	Component Type	Placement ft	Total Number		C <sub>A</sub> A <sub>A</sub> ft <sup>2</sup> /ft	Weight plf
***									
810921-701(7/8)	C	No	No	Inside Pole	164.00 - 0.00	7	No Ice 1/2" Ice 1" Ice 2" Ice	0.00 0.00 0.00 0.00	0.34 0.34 0.34 0.34
HCS 6X12 4AWG(1-5/8)	C	No	No	Inside Pole	164.00 - 0.00	3	No Ice 1/2" Ice 1" Ice 2" Ice	0.00 0.00 0.00 0.00	2.40 2.40 2.40 2.40
***									
HB114-1-08U4-M6F(1-1/4)	C	No	No	Inside Pole	155.00 - 0.00	3	No Ice 1/2" Ice 1" Ice 2" Ice	0.00 0.00 0.00 0.00	1.30 1.30 1.30 1.30
HB114-21U3M12-XXXF(1-1/4)	C	No	No	Inside Pole	155.00 - 0.00	1	No Ice 1/2" Ice 1" Ice 2" Ice	0.00 0.00 0.00 0.00	1.22 1.22 1.22 1.22
***									
HB158-1-08U8-S8J18(1-5/8)	C	No	No	Inside Pole	142.00 - 0.00	2	No Ice 1/2" Ice 1" Ice 2" Ice	0.00 0.00 0.00 0.00	1.30 1.30 1.30 1.30
LDF7-50A(1-5/8)	C	No	No	Inside Pole	142.00 - 0.00	6	No Ice 1/2" Ice 1" Ice 2" Ice	0.00 0.00 0.00 0.00	0.82 0.82 0.82 0.82
FB-L98B-034-XXX(3/8)	A	No	No	Inside Pole	115.00 - 0.00	1	No Ice 1/2" Ice 1" Ice 2" Ice	0.00 0.00 0.00 0.00	0.06 0.06 0.06 0.06
FB-L98B-034-XXX(3/8)	A	No	No	Inside Pole	115.00 - 0.00	2	No Ice 1/2" Ice 1" Ice 2" Ice	0.00 0.00 0.00 0.00	0.06 0.06 0.06 0.06
WR-VG82ST-	A	No	No	Inside Pole	115.00 - 0.00	4	No Ice	0.00	0.31

Description	Face or Leg	Allow Shield	Exclude From Torque Calculation	Component Type	Placement ft	Total Number	C <sub>A</sub> A <sub>A</sub> ft <sup>2</sup> /ft	Weight plf
BRDA(5/8)						1/2" Ice	0.00	0.31
						1" Ice	0.00	0.31
						2" Ice	0.00	0.31
WR-VG82ST- BRDA(5/8)	A	No	No	Inside Pole	115.00 - 0.00	2	No Ice	0.00
						1/2" Ice	0.00	0.31
						1" Ice	0.00	0.31
						2" Ice	0.00	0.31
*****								

### Feed Line/Linear Appurtenances Section Areas

Tower Section n	Tower Elevation ft	Face	A <sub>R</sub> ft <sup>2</sup>	A <sub>F</sub> ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> In Face ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> Out Face ft <sup>2</sup>	Weight K
L1	169.00-164.25	A	0.000	0.000	0.606	0.000	0.01
		B	0.000	0.000	0.000	0.000	0.00
		C	0.000	0.000	0.000	0.000	0.00
L2	164.25-129.75	A	0.000	0.000	4.399	0.000	0.08
		B	0.000	0.000	0.360	0.000	0.01
		C	0.000	0.000	0.000	0.000	0.55
L3	129.75-96.08	A	0.000	0.000	32.124	0.000	0.32
		B	0.000	0.000	15.984	0.000	0.12
		C	0.000	0.000	0.000	0.000	0.75
L4	96.08-63.25	A	0.000	0.000	52.994	0.000	0.49
		B	0.000	0.000	44.255	0.000	0.24
		C	0.000	0.000	0.000	0.000	0.73
L5	63.25-31.25	A	0.000	0.000	54.000	0.000	0.49
		B	0.000	0.000	43.136	0.000	0.23
		C	0.000	0.000	0.000	0.000	0.71
L6	31.25-0.00	A	0.000	0.000	52.734	0.000	0.48
		B	0.000	0.000	42.125	0.000	0.23
		C	0.000	0.000	0.000	0.000	0.69

### Feed Line/Linear Appurtenances Section Areas - With Ice

Tower Section n	Tower Elevation ft	Face or Leg	Ice Thickness in	A <sub>R</sub> ft <sup>2</sup>	A <sub>F</sub> ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> In Face ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> Out Face ft <sup>2</sup>	Weight K
L1	169.00-164.25	A	1.499	0.000	0.000	3.454	0.000	0.05
		B		0.000	0.000	0.000	0.000	0.00
		C		0.000	0.000	0.000	0.000	0.00
L2	164.25-129.75	A	1.479	0.000	0.000	25.085	0.000	0.34
		B		0.000	0.000	1.035	0.000	0.02
		C		0.000	0.000	0.000	0.000	0.55
L3	129.75-96.08	A	1.441	0.000	0.000	77.635	0.000	1.35
		B		0.000	0.000	31.894	0.000	0.48
		C		0.000	0.000	0.000	0.000	0.75
L4	96.08-63.25	A	1.392	0.000	0.000	115.525	0.000	2.05
		B		0.000	0.000	75.297	0.000	1.03
		C		0.000	0.000	0.000	0.000	0.73
L5	63.25-31.25	A	1.321	0.000	0.000	119.181	0.000	2.03
		B		0.000	0.000	72.684	0.000	0.97
		C		0.000	0.000	0.000	0.000	0.71
L6	31.25-0.00	A	1.183	0.000	0.000	113.628	0.000	1.88
		B		0.000	0.000	69.987	0.000	0.91
		C		0.000	0.000	0.000	0.000	0.69

### Feed Line Center of Pressure

Section	Elevation	CP <sub>x</sub>	CP <sub>z</sub>	CP <sub>x</sub> Ice	CP <sub>z</sub> Ice
	ft	in	in	in	in
L1	169.00-164.25	-0.4971	1.0572	-1.5012	2.3869
L2	164.25-129.75	-0.4883	0.9727	-1.5767	2.4086
L3	129.75-96.08	-1.7371	-5.2546	-2.5980	-3.5941
L4	96.08-63.25	-0.5591	-8.7797	-1.7280	-6.5732
L5	63.25-31.25	-0.8365	-9.4110	-2.2487	-7.2494
L6	31.25-0.00	-0.8712	-9.9119	-2.3281	-7.7447

Note: For pole sections, center of pressure calculations do not consider feed line shielding.

### Shielding Factor Ka

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K <sub>a</sub> No Ice	K <sub>a</sub> Ice
L1	1	Safety Line 3/8	164.25 - 169.00	1.0000	1.0000
L1	2	PiRod Ladder	164.25 - 169.00	1.0000	1.0000
L2	1	Safety Line 3/8	129.75 - 164.25	1.0000	1.0000
L2	2	PiRod Ladder	129.75 - 164.25	1.0000	1.0000
L2	13	CU12PSM9P6XXX(1-1/2)	129.75 - 132.00	1.0000	1.0000
L3	1	Safety Line 3/8	96.08 - 129.75	1.0000	1.0000
L3	2	PiRod Ladder	96.08 - 129.75	1.0000	1.0000
L3	13	CU12PSM9P6XXX(1-1/2)	96.08 - 129.75	1.0000	1.0000
L3	15	LDF4-50A(1/2)	96.08 - 121.00	1.0000	1.0000
L3	17	LDF7-50A(1-5/8)	96.08 - 115.00	1.0000	1.0000
L3	18	2" Flexible Conduit	96.08 - 115.00	1.0000	1.0000
L3	24	LDF7-50A(1-5/8)	96.08 - 105.00	1.0000	1.0000
L4	1	Safety Line 3/8	63.25 - 96.08	1.0000	1.0000
L4	2	PiRod Ladder	63.25 - 96.08	1.0000	1.0000
L4	13	CU12PSM9P6XXX(1-1/2)	63.25 - 96.08	1.0000	1.0000
L4	15	LDF4-50A(1/2)	63.25 - 96.08	1.0000	1.0000
L4	17	LDF7-50A(1-5/8)	63.25 - 96.08	1.0000	1.0000
L4	18	2" Flexible Conduit	63.25 - 96.08	1.0000	1.0000
L4	24	LDF7-50A(1-5/8)	63.25 - 96.08	1.0000	1.0000
L4	26	LDF5-50A(7/8)	63.25 - 74.00	1.0000	1.0000
L5	1	Safety Line 3/8	31.25 - 63.25	1.0000	1.0000
L5	2	PiRod Ladder	31.25 - 63.25	1.0000	1.0000
L5	13	CU12PSM9P6XXX(1-1/2)	31.25 -	1.0000	1.0000

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K <sub>a</sub> No Ice	K <sub>a</sub> Ice
L5	15	LDF4-50A(1/2)	63.25 31.25 -	1.0000	1.0000
L5	17	LDF7-50A(1-5/8)	63.25 31.25 -	1.0000	1.0000
L5	18	2" Flexible Conduit	63.25 31.25 -	1.0000	1.0000
L5	24	LDF7-50A(1-5/8)	63.25 31.25 -	1.0000	1.0000
L5	26	LDF5-50A(7/8)	63.25 31.25 -	1.0000	1.0000
L6	1	Safety Line 3/8	0.00 - 31.25	1.0000	1.0000
L6	2	PiRod Ladder	0.00 - 31.25	1.0000	1.0000
L6	13	CU12PSM9P6XXX(1-1/2)	0.00 - 31.25	1.0000	1.0000
L6	15	LDF4-50A(1/2)	0.00 - 31.25	1.0000	1.0000
L6	17	LDF7-50A(1-5/8)	0.00 - 31.25	1.0000	1.0000
L6	18	2" Flexible Conduit	0.00 - 31.25	1.0000	1.0000
L6	24	LDF7-50A(1-5/8)	0.00 - 31.25	1.0000	1.0000
L6	26	LDF5-50A(7/8)	0.00 - 31.25	1.0000	1.0000

### Effective Width of Flat Linear Attachments / Feed Lines

Tower Section	Attachment Record No.	Description	Attachment Segment Elev.	Ratio Calculation Method	Effective Width Ratio
L1	2	PiRod Ladder	164.25 - 169.00	Manual	1.0000
L2	2	PiRod Ladder	129.75 - 164.25	Manual	1.0000
L3	2	PiRod Ladder	96.08 - 129.75	Manual	1.0000
L4	2	PiRod Ladder	63.25 - 96.08	Manual	1.0000
L5	2	PiRod Ladder	31.25 - 63.25	Manual	1.0000
L6	2	PiRod Ladder	0.00 - 31.25	Manual	1.0000

### Discrete Tower Loads

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment °	Placement ft		C <sub>A</sub> A <sub>A</sub> Front ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> Side ft <sup>2</sup>	Weight K
Lightning Rod 5/8" x 4'	C	From Leg	3.00 0.00 2.00	0.0000	169.00	No Ice 1/2" Ice 1" Ice 2" Ice	0.25 0.66 0.97 1.49	0.25 0.66 0.97 1.49	0.03 0.03 0.04 0.06
8' x 3" Mount Pipe	C	From Leg	3.00 0.00 0.00	0.0000	167.00	No Ice 1/2" Ice	2.40 3.19 3.67	2.40 3.19 3.67	0.04 0.06 0.08

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustmen t °	Placement ft		C <sub>A</sub> A <sub>A</sub> Front ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> Side ft <sup>2</sup>	Weight K
						1" Ice 2" Ice	4.68 4.68	4.68	0.14
***									
APXVAARR24_43-U-NA20 w/ Mount Pipe	A	From Leg	4.00 0.00 1.00	0.0000	164.00	No Ice 1/2" Ice 1" Ice 2" Ice	14.69 15.46 16.23 17.82	6.87 7.55 8.25 9.67	0.19 0.31 0.46 0.79
APXVAARR24_43-U-NA20 w/ Mount Pipe	B	From Leg	4.00 0.00 1.00	0.0000	164.00	No Ice 1/2" Ice 1" Ice 2" Ice	14.69 15.46 16.23 17.82	6.87 7.55 8.25 9.67	0.19 0.31 0.46 0.79
APXVAARR24_43-U-NA20 w/ Mount Pipe	C	From Leg	4.00 0.00 1.00	0.0000	164.00	No Ice 1/2" Ice 1" Ice 2" Ice	14.69 15.46 16.23 17.82	6.87 7.55 8.25 9.67	0.19 0.31 0.46 0.79
AIR6449 B41 w/ Mount Pipe	A	From Leg	4.00 0.00 1.00	0.0000	164.00	No Ice 1/2" Ice 1" Ice 2" Ice	5.18 5.59 6.01 6.90	2.72 3.05 3.39 4.13	0.12 0.16 0.22 0.34
AIR6449 B41 w/ Mount Pipe	B	From Leg	4.00 0.00 1.00	0.0000	164.00	No Ice 1/2" Ice 1" Ice 2" Ice	5.18 5.59 6.01 6.90	2.72 3.05 3.39 4.13	0.12 0.16 0.22 0.34
AIR6449 B41 w/ Mount Pipe	C	From Leg	4.00 0.00 1.00	0.0000	164.00	No Ice 1/2" Ice 1" Ice 2" Ice	5.18 5.59 6.01 6.90	2.72 3.05 3.39 4.13	0.12 0.16 0.22 0.34
AIR 32 B2A/B66AA w/ Mount Pipe	A	From Leg	4.00 0.00 1.00	0.0000	164.00	No Ice 1/2" Ice 1" Ice 2" Ice	3.76 4.12 4.48 5.24	3.15 3.49 3.84 4.58	0.19 0.25 0.32 0.48
AIR 32 B2A/B66AA w/ Mount Pipe	B	From Leg	4.00 0.00 1.00	0.0000	164.00	No Ice 1/2" Ice 1" Ice 2" Ice	3.76 4.12 4.48 5.24	3.15 3.49 3.84 4.58	0.19 0.25 0.32 0.48
AIR 32 B2A/B66AA w/ Mount Pipe	C	From Leg	4.00 0.00 1.00	0.0000	164.00	No Ice 1/2" Ice 1" Ice 2" Ice	3.76 4.12 4.48 5.24	3.15 3.49 3.84 4.58	0.19 0.25 0.32 0.48
RADIO 4449 B71 B85A_T- MOBILE	A	From Leg	4.00 0.00 1.00	0.0000	164.00	No Ice 1/2" Ice 1" Ice 2" Ice	1.97 2.15 2.33 2.72	1.59 1.75 1.92 2.28	0.07 0.09 0.12 0.17
RADIO 4449 B71 B85A_T- MOBILE	B	From Leg	4.00 0.00 1.00	0.0000	164.00	No Ice 1/2" Ice 1" Ice 2" Ice	1.97 2.15 2.33 2.72	1.59 1.75 1.92 2.28	0.07 0.09 0.12 0.17
RADIO 4449 B71 B85A_T- MOBILE	C	From Leg	4.00 0.00 1.00	0.0000	164.00	No Ice 1/2" Ice 1" Ice 2" Ice	1.97 2.15 2.33 2.72	1.59 1.75 1.92 2.28	0.07 0.09 0.12 0.17
RRUS 4415 B25	A	From Leg	4.00 0.00	0.0000	164.00	No Ice 1/2"	1.64 1.80	0.68 0.79	0.04 0.06

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustmen t °	Placement ft		C <sub>A</sub> A <sub>A</sub> Front ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> Side ft <sup>2</sup>	Weight K
			1.00			Ice	1.97	0.91	0.07
						1" Ice	2.33	1.18	0.11
						2" Ice			
RRUS 4415 B25	B	From Leg	4.00	0.0000	164.00	No Ice	1.64	0.68	0.04
			0.00			1/2"	1.80	0.79	0.06
			1.00			Ice	1.97	0.91	0.07
						1" Ice	2.33	1.18	0.11
						2" Ice			
RRUS 4415 B25	C	From Leg	4.00	0.0000	164.00	No Ice	1.64	0.68	0.04
			0.00			1/2"	1.80	0.79	0.06
			1.00			Ice	1.97	0.91	0.07
						1" Ice	2.33	1.18	0.11
						2" Ice			
Platform Mount [LP 404-1_KCKR]	C	None		0.0000	164.00	No Ice	35.82	35.82	2.32
						1/2"	45.85	45.85	3.02
						Ice	55.76	55.76	3.89
						1" Ice	75.77	75.77	6.14
						2" Ice			
(2) 4' x 2" Pipe Mount	A	From Leg	4.00	0.0000	164.00	No Ice	0.79	0.79	0.03
			0.00			1/2"	1.03	1.03	0.04
			0.00			Ice	1.28	1.28	0.04
						1" Ice	1.81	1.81	0.07
						2" Ice			
(2) 4' x 2" Pipe Mount	B	From Leg	4.00	0.0000	164.00	No Ice	0.79	0.79	0.03
			0.00			1/2"	1.03	1.03	0.04
			0.00			Ice	1.28	1.28	0.04
						1" Ice	1.81	1.81	0.07
						2" Ice			
(2) 4' x 2" Pipe Mount	C	From Leg	4.00	0.0000	164.00	No Ice	0.79	0.79	0.03
			0.00			1/2"	1.03	1.03	0.04
			0.00			Ice	1.28	1.28	0.04
						1" Ice	1.81	1.81	0.07
						2" Ice			
***									
COL45-70	A	From Leg	4.00	0.0000	164.00	No Ice	1.38	1.38	0.01
			0.00			1/2"	2.32	2.32	0.02
			4.00			Ice	3.27	3.27	0.03
						1" Ice	4.82	4.82	0.09
						2" Ice			
COL45-70	A	From Leg	4.00	0.0000	164.00	No Ice	1.38	1.38	0.01
			0.00			1/2"	2.32	2.32	0.02
			4.00			Ice	3.27	3.27	0.03
						1" Ice	4.82	4.82	0.09
						2" Ice			
COL45-70	B	From Leg	4.00	0.0000	164.00	No Ice	1.38	1.38	0.01
			0.00			1/2"	2.32	2.32	0.02
			4.00			Ice	3.27	3.27	0.03
						1" Ice	4.82	4.82	0.09
						2" Ice			
***									
APXVTM14-C-120 w/ Mount Pipe	A	From Leg	4.00	0.0000	155.00	No Ice	4.09	2.86	0.08
			0.00			1/2"	4.48	3.23	0.13
			0.00			Ice	4.88	3.61	0.19
						1" Ice	5.71	4.40	0.33
						2" Ice			
APXVTM14-C-120 w/ Mount Pipe	B	From Leg	4.00	0.0000	155.00	No Ice	4.09	2.86	0.08
			0.00			1/2"	4.48	3.23	0.13
			0.00			Ice	4.88	3.61	0.19
						1" Ice	5.71	4.40	0.33
						2" Ice			
APXVTM14-C-120 w/ Mount Pipe	C	From Leg	4.00	0.0000	155.00	No Ice	4.09	2.86	0.08
			0.00			1/2"	4.48	3.23	0.13
			0.00			Ice	4.88	3.61	0.19
						1" Ice	5.71	4.40	0.33
						2" Ice			

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustmen t °	Placement ft		C <sub>A</sub> A <sub>A</sub> Front ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> Side ft <sup>2</sup>	Weight K
APXVSPP18-C-A20 w/ Mount Pipe	A	From Leg	4.00 0.00 0.00	0.0000	155.00	No Ice 1/2" Ice 1" Ice 2" Ice	4.60 5.05 5.50 6.44	4.01 4.45 4.89 5.82	0.10 0.16 0.23 0.42
APXVSPP18-C-A20 w/ Mount Pipe	B	From Leg	4.00 0.00 0.00	0.0000	155.00	No Ice 1/2" Ice 1" Ice 2" Ice	4.60 5.05 5.50 6.44	4.01 4.45 4.89 5.82	0.10 0.16 0.23 0.42
APXVSPP18-C-A20 w/ Mount Pipe	C	From Leg	4.00 0.00 0.00	0.0000	155.00	No Ice 1/2" Ice 1" Ice 2" Ice	4.60 5.05 5.50 6.44	4.01 4.45 4.89 5.82	0.10 0.16 0.23 0.42
TD-RRH8x20-25	A	From Leg	4.00 0.00 0.00	0.0000	155.00	No Ice 1/2" Ice 1" Ice 2" Ice	4.05 4.30 4.56 5.10	1.53 1.71 1.90 2.30	0.07 0.10 0.13 0.20
TD-RRH8x20-25	B	From Leg	4.00 0.00 0.00	0.0000	155.00	No Ice 1/2" Ice 1" Ice 2" Ice	4.05 4.30 4.56 5.10	1.53 1.71 1.90 2.30	0.07 0.10 0.13 0.20
TD-RRH8x20-25	C	From Leg	4.00 0.00 0.00	0.0000	155.00	No Ice 1/2" Ice 1" Ice 2" Ice	4.05 4.30 4.56 5.10	1.53 1.71 1.90 2.30	0.07 0.10 0.13 0.20
800MHZ RRH	A	From Leg	4.00 0.00 0.00	0.0000	155.00	No Ice 1/2" Ice 1" Ice 2" Ice	2.13 2.32 2.51 2.92	1.77 1.95 2.13 2.51	0.05 0.07 0.10 0.16
800MHZ RRH	B	From Leg	4.00 0.00 0.00	0.0000	155.00	No Ice 1/2" Ice 1" Ice 2" Ice	2.13 2.32 2.51 2.92	1.77 1.95 2.13 2.51	0.05 0.07 0.10 0.16
800MHZ RRH	C	From Leg	4.00 0.00 0.00	0.0000	155.00	No Ice 1/2" Ice 1" Ice 2" Ice	2.13 2.32 2.51 2.92	1.77 1.95 2.13 2.51	0.05 0.07 0.10 0.16
1900MHz RRH	A	From Leg	4.00 0.00 0.00	0.0000	155.00	No Ice 1/2" Ice 1" Ice 2" Ice	2.49 2.70 2.91 3.35	3.26 3.48 3.72 4.21	0.04 0.08 0.11 0.19
1900MHz RRH	B	From Leg	4.00 0.00 0.00	0.0000	155.00	No Ice 1/2" Ice 1" Ice 2" Ice	2.49 2.70 2.91 3.35	3.26 3.48 3.72 4.21	0.04 0.08 0.11 0.19
1900MHz RRH	C	From Leg	4.00 0.00 0.00	0.0000	155.00	No Ice 1/2" Ice 1" Ice 2" Ice	2.49 2.70 2.91 3.35	3.26 3.48 3.72 4.21	0.04 0.08 0.11 0.19
Platform Mount [LP 305-1]	C	None		0.0000	155.00	No Ice 1/2" Ice 1" Ice 2" Ice	18.04 22.04 26.06 34.16	18.04 22.04 26.06 34.16	1.12 1.47 1.88 2.90

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustmen t °	Placement ft		C <sub>A</sub> A <sub>A</sub> Front ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> Side ft <sup>2</sup>	Weight K
6' x 2" Mount Pipe	A	From Leg	4.00 0.00 0.00	0.0000	155.00	No Ice 1/2" Ice 1" Ice 2" Ice	1.43 1.92 2.29 3.06	1.43 1.92 2.29 3.06	0.02 0.03 0.05 0.09
6' x 2" Mount Pipe	B	From Leg	4.00 0.00 0.00	0.0000	155.00	No Ice 1/2" Ice 1" Ice 2" Ice	1.43 1.92 2.29 3.06	1.43 1.92 2.29 3.06	0.02 0.03 0.05 0.09
6' x 2" Mount Pipe	C	From Leg	4.00 0.00 0.00	0.0000	155.00	No Ice 1/2" Ice 1" Ice 2" Ice	1.43 1.92 2.29 3.06	1.43 1.92 2.29 3.06	0.02 0.03 0.05 0.09
***									
MT6407-77A w/ Mount Pipe	A	From Leg	4.00 0.00 0.00	0.0000	142.00	No Ice 1/2" Ice 1" Ice 2" Ice	4.91 5.26 5.61 6.36	2.68 3.14 3.62 4.63	0.10 0.14 0.18 0.29
MT6407-77A w/ Mount Pipe	B	From Leg	4.00 0.00 0.00	0.0000	142.00	No Ice 1/2" Ice 1" Ice 2" Ice	4.91 5.26 5.61 6.36	2.68 3.14 3.62 4.63	0.10 0.14 0.18 0.29
MT6407-77A w/ Mount Pipe	C	From Leg	4.00 0.00 0.00	0.0000	142.00	No Ice 1/2" Ice 1" Ice 2" Ice	4.91 5.26 5.61 6.36	2.68 3.14 3.62 4.63	0.10 0.14 0.18 0.29
(2) LPA-80080/6CF w/ Mount Pipe	A	From Leg	4.00 0.00 0.00	0.0000	142.00	No Ice 1/2" Ice 1" Ice 2" Ice	4.56 5.11 5.61 6.65	10.26 11.43 12.31 14.13	0.05 0.11 0.19 0.36
(2) LPA-80080/6CF w/ Mount Pipe	B	From Leg	4.00 0.00 0.00	0.0000	142.00	No Ice 1/2" Ice 1" Ice 2" Ice	4.56 5.11 5.61 6.65	10.26 11.43 12.31 14.13	0.05 0.11 0.19 0.36
(2) LPA-80080/6CF w/ Mount Pipe	C	From Leg	4.00 0.00 0.00	0.0000	142.00	No Ice 1/2" Ice 1" Ice 2" Ice	4.56 5.11 5.61 6.65	10.26 11.43 12.31 14.13	0.05 0.11 0.19 0.36
SBNHH-1D65B w/ Mount Pipe	A	From Leg	4.00 0.00 0.00	0.0000	142.00	No Ice 1/2" Ice 1" Ice 2" Ice	4.09 4.49 4.89 5.72	3.30 3.68 4.07 4.87	0.07 0.13 0.20 0.39
SBNHH-1D65B w/ Mount Pipe	B	From Leg	4.00 0.00 0.00	0.0000	142.00	No Ice 1/2" Ice 1" Ice 2" Ice	4.09 4.49 4.89 5.72	3.30 3.68 4.07 4.87	0.07 0.13 0.20 0.39
SBNHH-1D65B w/ Mount Pipe	C	From Leg	4.00 0.00 0.00	0.0000	142.00	No Ice 1/2" Ice 1" Ice 2" Ice	4.09 4.49 4.89 5.72	3.30 3.68 4.07 4.87	0.07 0.13 0.20 0.39
SBNHH-1D65B	A	From Leg	4.00 0.00 0.00	0.0000	142.00	No Ice 1/2" Ice 1" Ice	4.16 4.57 4.99 5.85	2.49 2.88 3.27 4.09	0.04 0.09 0.15 0.28

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustmen t °	Placement ft		C <sub>A</sub> A <sub>A</sub> Front ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> Side ft <sup>2</sup>	Weight K
SBNHH-1D65B	B	From Leg	4.00 0.00 0.00	0.0000	142.00	2" Ice No Ice 1/2" Ice 1" Ice	4.16 4.57 4.99 5.85	2.49 2.88 3.27 4.09	0.04 0.09 0.15 0.28
SBNHH-1D65B	C	From Leg	4.00 0.00 0.00	0.0000	142.00	2" Ice No Ice 1/2" Ice 1" Ice	4.16 4.57 4.99 5.85	2.49 2.88 3.27 4.09	0.04 0.09 0.15 0.28
RFV01U-D1A	A	From Leg	4.00 0.00 0.00	0.0000	142.00	2" Ice No Ice 1/2" Ice 1" Ice	1.88 2.05 2.22 2.60	1.25 1.39 1.54 1.86	0.08 0.10 0.12 0.18
RFV01U-D1A	B	From Leg	4.00 0.00 0.00	0.0000	142.00	2" Ice No Ice 1/2" Ice 1" Ice	1.88 2.05 2.22 2.60	1.25 1.39 1.54 1.86	0.08 0.10 0.12 0.18
RFV01U-D1A	C	From Leg	4.00 0.00 0.00	0.0000	142.00	2" Ice No Ice 1/2" Ice 1" Ice	1.88 2.05 2.22 2.60	1.25 1.39 1.54 1.86	0.08 0.10 0.12 0.18
RFV01U-D2A	A	From Leg	4.00 0.00 0.00	0.0000	142.00	2" Ice No Ice 1/2" Ice 1" Ice	1.88 2.05 2.22 2.60	1.01 1.14 1.28 1.59	0.07 0.09 0.11 0.15
RFV01U-D2A	B	From Leg	4.00 0.00 0.00	0.0000	142.00	2" Ice No Ice 1/2" Ice 1" Ice	1.88 2.05 2.22 2.60	1.01 1.14 1.28 1.59	0.07 0.09 0.11 0.15
RFV01U-D2A	C	From Leg	4.00 0.00 0.00	0.0000	142.00	2" Ice No Ice 1/2" Ice 1" Ice	1.88 2.05 2.22 2.60	1.01 1.14 1.28 1.59	0.07 0.09 0.11 0.15
DB-T1-6Z-8AB-0Z	A	From Leg	4.00 0.00 0.00	0.0000	142.00	2" Ice No Ice 1/2" Ice 1" Ice	4.80 5.07 5.35 5.93	2.00 2.19 2.39 2.81	0.04 0.08 0.12 0.21
DB-T1-6Z-8AB-0Z	C	From Leg	4.00 0.00 0.00	0.0000	142.00	2" Ice No Ice 1/2" Ice 1" Ice	4.80 5.07 5.35 5.93	2.00 2.19 2.39 2.81	0.04 0.08 0.12 0.21
Platform Mount [LP 403-1]	C	None		0.0000	142.00	2" Ice No Ice 1/2" Ice 1" Ice	18.94 23.31 27.74 36.77	18.94 23.31 27.74 36.77	1.50 1.90 2.37 3.53
Dual Antenna Mounting Bracket	A	From Leg	4.00 0.00 0.00	0.0000	142.00	2" Ice No Ice 1/2" Ice 1" Ice	0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00	0.07 0.09 0.11 0.15
Dual Antenna Mounting Bracket	B	From Leg	4.00 0.00 0.00	0.0000	142.00	2" Ice No Ice 1/2" Ice 1" Ice	0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00	0.07 0.09 0.11 0.15

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustmen t °	Placement ft		C <sub>A</sub> A <sub>A</sub> Front ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> Side ft <sup>2</sup>	Weight K
Dual Antenna Mounting Bracket	C	From Leg	4.00 0.00 0.00	0.0000	142.00	2" Ice No Ice 1/2" Ice 1" Ice 2" Ice	0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00	0.07 0.09 0.11 0.15
***									
MX08FRO665-21 w/ Mount Pipe	A	From Leg	4.00 0.00 0.00	0.0000	132.00	No Ice 1/2" Ice 1" Ice 2" Ice	8.01 8.52 9.04 10.11	4.23 4.69 5.16 6.12	0.11 0.19 0.29 0.52
MX08FRO665-21 w/ Mount Pipe	B	From Leg	4.00 0.00 0.00	0.0000	132.00	No Ice 1/2" Ice 1" Ice 2" Ice	8.01 8.52 9.04 10.11	4.23 4.69 5.16 6.12	0.11 0.19 0.29 0.52
MX08FRO665-21 w/ Mount Pipe	C	From Leg	4.00 0.00 0.00	0.0000	132.00	No Ice 1/2" Ice 1" Ice 2" Ice	8.01 8.52 9.04 10.11	4.23 4.69 5.16 6.12	0.11 0.19 0.29 0.52
TA08025-B604	A	From Leg	4.00 0.00 0.00	0.0000	132.00	No Ice 1/2" Ice 1" Ice 2" Ice	1.96 2.14 2.32 2.71	0.98 1.11 1.25 1.55	0.06 0.08 0.10 0.15
TA08025-B604	B	From Leg	4.00 0.00 0.00	0.0000	132.00	No Ice 1/2" Ice 1" Ice 2" Ice	1.96 2.14 2.32 2.71	0.98 1.11 1.25 1.55	0.06 0.08 0.10 0.15
TA08025-B604	C	From Leg	4.00 0.00 0.00	0.0000	132.00	No Ice 1/2" Ice 1" Ice 2" Ice	1.96 2.14 2.32 2.71	0.98 1.11 1.25 1.55	0.06 0.08 0.10 0.15
TA08025-B605	A	From Leg	4.00 0.00 0.00	0.0000	132.00	No Ice 1/2" Ice 1" Ice 2" Ice	1.96 2.14 2.32 2.71	1.13 1.27 1.41 1.72	0.08 0.09 0.11 0.16
TA08025-B605	B	From Leg	4.00 0.00 0.00	0.0000	132.00	No Ice 1/2" Ice 1" Ice 2" Ice	1.96 2.14 2.32 2.71	1.13 1.27 1.41 1.72	0.08 0.09 0.11 0.16
TA08025-B605	C	From Leg	4.00 0.00 0.00	0.0000	132.00	No Ice 1/2" Ice 1" Ice 2" Ice	1.96 2.14 2.32 2.71	1.13 1.27 1.41 1.72	0.08 0.09 0.11 0.16
RDIDC-9181-PF-48	C	From Leg	4.00 0.00 0.00	0.0000	132.00	No Ice 1/2" Ice 1" Ice 2" Ice	2.31 2.50 2.70 3.12	1.29 1.45 1.61 1.96	0.02 0.04 0.06 0.12
Commscope MC-PK8-DSH	C	None		0.0000	132.00	No Ice 1/2" Ice 1" Ice 2" Ice	34.24 62.95 91.66 149.08	34.24 62.95 91.66 149.08	1.75 2.10 2.45 3.15
(2) 8' x 2" Mount Pipe	A	From Leg	4.00 0.00 0.00	0.0000	132.00	No Ice 1/2" Ice	1.90 2.73 3.40	1.90 2.73 3.40	0.03 0.04 0.06

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustmen t °	Placement ft		C <sub>A</sub> A <sub>A</sub> Front ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> Side ft <sup>2</sup>	Weight K
						1" Ice	4.40	4.40	0.12
						2" Ice			
(2) 8' x 2" Mount Pipe	B	From Leg	4.00	0.0000	132.00	No Ice	1.90	1.90	0.03
			0.00			1/2"	2.73	2.73	0.04
			0.00			Ice	3.40	3.40	0.06
						1" Ice	4.40	4.40	0.12
						2" Ice			
(2) 8' x 2" Mount Pipe	C	From Leg	4.00	0.0000	132.00	No Ice	1.90	1.90	0.03
			0.00			1/2"	2.73	2.73	0.04
			0.00			Ice	3.40	3.40	0.06
						1" Ice	4.40	4.40	0.12
						2" Ice			
***									
201-4	A	From Leg	3.00	0.0000	121.00	No Ice	1.13	1.13	0.00
			0.00			1/2"	2.00	2.00	0.01
			4.00			Ice	2.90	2.90	0.03
						1" Ice	4.31	4.31	0.08
						2" Ice			
Side Arm Mount [SO 701-1]	A	From Leg	1.50	0.0000	121.00	No Ice	0.85	1.67	0.07
			0.00			1/2"	1.14	2.34	0.08
			0.00			Ice	1.43	3.01	0.09
						1" Ice	2.01	4.35	0.12
						2" Ice			
4' x 2" Pipe Mount	A	From Leg	3.00	0.0000	121.00	No Ice	0.79	0.79	0.03
			0.00			1/2"	1.03	1.03	0.04
			0.00			Ice	1.28	1.28	0.04
						1" Ice	1.81	1.81	0.07
						2" Ice			
***									
7770.00	A	From Leg	4.00	0.0000	115.00	No Ice	5.51	2.93	0.04
			0.00			1/2"	5.87	3.27	0.07
			0.00			Ice	6.23	3.63	0.11
						1" Ice	6.99	4.35	0.20
						2" Ice			
7770.00	B	From Leg	4.00	0.0000	115.00	No Ice	5.51	2.93	0.04
			0.00			1/2"	5.87	3.27	0.07
			0.00			Ice	6.23	3.63	0.11
						1" Ice	6.99	4.35	0.20
						2" Ice			
7770.00	C	From Leg	4.00	0.0000	115.00	No Ice	5.51	2.93	0.04
			0.00			1/2"	5.87	3.27	0.07
			0.00			Ice	6.23	3.63	0.11
						1" Ice	6.99	4.35	0.20
						2" Ice			
AM-X-CD-16-65-00T-RET	A	From Leg	4.00	0.0000	115.00	No Ice	4.69	2.34	0.05
			0.00			1/2"	5.15	2.77	0.10
			0.00			Ice	5.61	3.20	0.15
						1" Ice	6.57	4.10	0.27
						2" Ice			
AM-X-CD-16-65-00T-RET	B	From Leg	4.00	0.0000	115.00	No Ice	4.69	2.34	0.05
			0.00			1/2"	5.15	2.77	0.10
			0.00			Ice	5.61	3.20	0.15
						1" Ice	6.57	4.10	0.27
						2" Ice			
AM-X-CD-16-65-00T-RET	C	From Leg	4.00	0.0000	115.00	No Ice	4.69	2.34	0.05
			0.00			1/2"	5.15	2.77	0.10
			0.00			Ice	5.61	3.20	0.15
						1" Ice	6.57	4.10	0.27
						2" Ice			
80010965	A	From Leg	4.00	0.0000	115.00	No Ice	12.23	4.21	0.11
			0.00			1/2"	13.00	4.88	0.19
			0.00			Ice	13.79	5.57	0.27
						1" Ice	15.41	6.99	0.46
						2" Ice			
80010965	B	From Leg	4.00	0.0000	115.00	No Ice	12.23	4.21	0.11

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustmen t °	Placement ft		C <sub>A</sub> A <sub>A</sub> Front ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> Side ft <sup>2</sup>	Weight K
			0.00			1/2"	13.00	4.88	0.19
			0.00			Ice	13.79	5.57	0.27
						1" Ice	15.41	6.99	0.46
						2" Ice			
80010965	C	From Leg	4.00	0.0000	115.00	No Ice	12.23	4.21	0.11
			0.00			1/2"	13.00	4.88	0.19
			0.00			Ice	13.79	5.57	0.27
						1" Ice	15.41	6.99	0.46
						2" Ice			
QS66512-2	A	From Leg	4.00	0.0000	115.00	No Ice	4.01	3.37	0.11
			0.00			1/2"	4.41	3.76	0.17
			0.00			Ice	4.81	4.15	0.23
						1" Ice	5.65	4.97	0.38
						2" Ice			
QS66512-2	B	From Leg	4.00	0.0000	115.00	No Ice	4.01	3.37	0.11
			0.00			1/2"	4.41	3.76	0.17
			0.00			Ice	4.81	4.15	0.23
						1" Ice	5.65	4.97	0.38
						2" Ice			
QS66512-2	C	From Leg	4.00	0.0000	115.00	No Ice	4.01	3.37	0.11
			0.00			1/2"	4.41	3.76	0.17
			0.00			Ice	4.81	4.15	0.23
						1" Ice	5.65	4.97	0.38
						2" Ice			
(3) DBCT108F1V92-1	A	From Leg	4.00	0.0000	115.00	No Ice	0.32	0.64	0.03
			0.00			1/2"	0.40	0.74	0.03
			0.00			Ice	0.49	0.85	0.04
						1" Ice	0.69	1.09	0.06
						2" Ice			
(2) DBCT108F1V92-1	B	From Leg	4.00	0.0000	115.00	No Ice	0.32	0.64	0.03
			0.00			1/2"	0.40	0.74	0.03
			0.00			Ice	0.49	0.85	0.04
						1" Ice	0.69	1.09	0.06
						2" Ice			
DBCT108F1V92-1	C	From Leg	4.00	0.0000	115.00	No Ice	0.32	0.64	0.03
			0.00			1/2"	0.40	0.74	0.03
			0.00			Ice	0.49	0.85	0.04
						1" Ice	0.69	1.09	0.06
						2" Ice			
RRUS 12 B2	A	From Leg	4.00	0.0000	115.00	No Ice	3.14	1.28	0.05
			0.00			1/2"	3.36	1.43	0.07
			0.00			Ice	3.59	1.60	0.10
						1" Ice	4.07	1.95	0.16
						2" Ice			
RRUS 12 B2	B	From Leg	4.00	0.0000	115.00	No Ice	3.14	1.28	0.05
			0.00			1/2"	3.36	1.43	0.07
			0.00			Ice	3.59	1.60	0.10
						1" Ice	4.07	1.95	0.16
						2" Ice			
RRUS 12 B2	C	From Leg	4.00	0.0000	115.00	No Ice	3.14	1.28	0.05
			0.00			1/2"	3.36	1.43	0.07
			0.00			Ice	3.59	1.60	0.10
						1" Ice	4.07	1.95	0.16
						2" Ice			
DTMABP7819VG12A	A	From Leg	4.00	0.0000	115.00	No Ice	0.98	0.34	0.02
			0.00			1/2"	1.10	0.42	0.03
			0.00			Ice	1.23	0.51	0.04
						1" Ice	1.52	0.71	0.06
						2" Ice			
DTMABP7819VG12A	B	From Leg	4.00	0.0000	115.00	No Ice	0.98	0.34	0.02
			0.00			1/2"	1.10	0.42	0.03
			0.00			Ice	1.23	0.51	0.04
						1" Ice	1.52	0.71	0.06
						2" Ice			
DTMABP7819VG12A	C	From Leg	4.00	0.0000	115.00	No Ice	0.98	0.34	0.02

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustmen t °	Placement ft		C <sub>A</sub> A <sub>A</sub> Front ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> Side ft <sup>2</sup>	Weight K
			0.00			1/2"	1.10	0.42	0.03
			0.00			Ice	1.23	0.51	0.04
						1" Ice	1.52	0.71	0.06
						2" Ice			
RRUS 4478 B5	A	From Leg	4.00	0.0000	115.00	No Ice	1.84	1.06	0.06
			0.00			1/2"	2.01	1.20	0.08
			0.00			Ice	2.19	1.34	0.09
						1" Ice	2.57	1.66	0.14
						2" Ice			
RRUS 4478 B5	B	From Leg	4.00	0.0000	115.00	No Ice	1.84	1.06	0.06
			0.00			1/2"	2.01	1.20	0.08
			0.00			Ice	2.19	1.34	0.09
						1" Ice	2.57	1.66	0.14
						2" Ice			
RRUS 4478 B5	C	From Leg	4.00	0.0000	115.00	No Ice	1.84	1.06	0.06
			0.00			1/2"	2.01	1.20	0.08
			0.00			Ice	2.19	1.34	0.09
						1" Ice	2.57	1.66	0.14
						2" Ice			
RRUS 4478 B14	A	From Leg	4.00	0.0000	115.00	No Ice	1.84	1.06	0.06
			0.00			1/2"	2.01	1.20	0.08
			0.00			Ice	2.19	1.34	0.09
						1" Ice	2.57	1.66	0.14
						2" Ice			
(2) RRUS 4478 B14	C	From Leg	4.00	0.0000	115.00	No Ice	1.84	1.06	0.06
			0.00			1/2"	2.01	1.20	0.08
			0.00			Ice	2.19	1.34	0.09
						1" Ice	2.57	1.66	0.14
						2" Ice			
WCS RRUS-32-B30	A	From Leg	4.00	0.0000	115.00	No Ice	3.31	2.42	0.08
			0.00			1/2"	3.56	2.64	0.10
			0.00			Ice	3.81	2.86	0.14
						1" Ice	4.33	3.32	0.21
						2" Ice			
WCS RRUS-32-B30	B	From Leg	4.00	0.0000	115.00	No Ice	3.31	2.42	0.08
			0.00			1/2"	3.56	2.64	0.10
			0.00			Ice	3.81	2.86	0.14
						1" Ice	4.33	3.32	0.21
						2" Ice			
WCS RRUS-32-B30	C	From Leg	4.00	0.0000	115.00	No Ice	3.31	2.42	0.08
			0.00			1/2"	3.56	2.64	0.10
			0.00			Ice	3.81	2.86	0.14
						1" Ice	4.33	3.32	0.21
						2" Ice			
(2) TPX-070821	A	From Leg	4.00	0.0000	115.00	No Ice	0.47	0.10	0.01
			0.00			1/2"	0.56	0.15	0.01
			0.00			Ice	0.66	0.20	0.02
						1" Ice	0.87	0.33	0.03
						2" Ice			
(2) TPX-070821	B	From Leg	4.00	0.0000	115.00	No Ice	0.47	0.10	0.01
			0.00			1/2"	0.56	0.15	0.01
			0.00			Ice	0.66	0.20	0.02
						1" Ice	0.87	0.33	0.03
						2" Ice			
(2) TPX-070821	C	From Leg	4.00	0.0000	115.00	No Ice	0.47	0.10	0.01
			0.00			1/2"	0.56	0.15	0.01
			0.00			Ice	0.66	0.20	0.02
						1" Ice	0.87	0.33	0.03
						2" Ice			
(2) RRUS 11	B	From Leg	4.00	0.0000	115.00	No Ice	2.78	1.19	0.05
			0.00			1/2"	2.99	1.33	0.07
			0.00			Ice	3.21	1.49	0.09
						1" Ice	3.66	1.83	0.15
						2" Ice			
RRUS 11	C	From Leg	4.00	0.0000	115.00	No Ice	2.78	1.19	0.05

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustmen t °	Placement ft		C <sub>A</sub> A <sub>A</sub> Front ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> Side ft <sup>2</sup>	Weight K
			0.00			1/2"	2.99	1.33	0.07
			0.00			Ice	3.21	1.49	0.09
						1" Ice	3.66	1.83	0.15
						2" Ice			
RRUS 4426 B66	B	From Leg	4.00	0.0000	115.00	No Ice	1.64	0.73	0.05
			0.00			1/2"	1.80	0.84	0.06
			0.00			Ice	1.97	0.97	0.08
						1" Ice	2.33	1.24	0.11
						2" Ice			
(2) RRUS 4426 B66	C	From Leg	4.00	0.0000	115.00	No Ice	1.64	0.73	0.05
			0.00			1/2"	1.80	0.84	0.06
			0.00			Ice	1.97	0.97	0.08
						1" Ice	2.33	1.24	0.11
						2" Ice			
DC6-48-60-18-8F	A	From Leg	4.00	0.0000	115.00	No Ice	1.21	1.21	0.02
			0.00			1/2"	1.89	1.89	0.04
			0.00			Ice	2.11	2.11	0.07
						1" Ice	2.57	2.57	0.13
						2" Ice			
DC6-48-60-18-8F	B	From Leg	4.00	0.0000	115.00	No Ice	1.21	1.21	0.02
			0.00			1/2"	1.89	1.89	0.04
			0.00			Ice	2.11	2.11	0.07
						1" Ice	2.57	2.57	0.13
						2" Ice			
DC6-48-60-18-8C	B	From Leg	4.00	0.0000	115.00	No Ice	1.14	1.14	0.03
			0.00			1/2"	1.79	1.79	0.05
			0.00			Ice	2.00	2.00	0.07
						1" Ice	2.45	2.45	0.13
						2" Ice			
Platform Mount [LP 301-1]	C	None		0.0000	115.00	No Ice	23.81	23.81	1.59
						1/2"	30.24	30.24	2.10
						Ice	36.33	36.33	2.73
						1" Ice	48.05	48.05	4.34
						2" Ice			
4' x 2" Pipe Mount	A	From Leg	1.00	0.0000	115.00	No Ice	0.79	0.79	0.03
			0.00			1/2"	1.03	1.03	0.04
			0.00			Ice	1.28	1.28	0.04
						1" Ice	1.81	1.81	0.07
						2" Ice			
4' x 2" Pipe Mount	B	From Leg	1.00	0.0000	115.00	No Ice	0.79	0.79	0.03
			0.00			1/2"	1.03	1.03	0.04
			0.00			Ice	1.28	1.28	0.04
						1" Ice	1.81	1.81	0.07
						2" Ice			
4' x 2" Pipe Mount	C	From Leg	1.00	0.0000	115.00	No Ice	0.79	0.79	0.03
			0.00			1/2"	1.03	1.03	0.04
			0.00			Ice	1.28	1.28	0.04
						1" Ice	1.81	1.81	0.07
						2" Ice			
***									
APXV18-206517S-C w/ Mount Pipe	A	From Leg	1.00	0.0000	105.00	No Ice	3.79	3.16	0.05
			0.00			1/2"	4.38	3.75	0.09
			0.00			Ice	4.99	4.35	0.15
						1" Ice	6.25	5.59	0.28
						2" Ice			
APXV18-206517S-C w/ Mount Pipe	B	From Leg	1.00	0.0000	105.00	No Ice	3.79	3.16	0.05
			0.00			1/2"	4.38	3.75	0.09
			0.00			Ice	4.99	4.35	0.15
						1" Ice	6.25	5.59	0.28
						2" Ice			
APXV18-206517S-C w/ Mount Pipe	C	From Leg	1.00	0.0000	105.00	No Ice	3.79	3.16	0.05
			0.00			1/2"	4.38	3.75	0.09
			0.00			Ice	4.99	4.35	0.15
						1" Ice	6.25	5.59	0.28
						2" Ice			

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustmen t °	Placement ft		C <sub>A</sub> A <sub>A</sub> Front ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> Side ft <sup>2</sup>	Weight K
***									
DB810T3E-XT	A	From Leg	3.00 0.00 9.00	0.0000	74.00	No Ice 1/2" Ice 1" Ice 2" Ice	4.53 6.07 7.63 10.79	4.53 6.07 7.63 10.79	0.05 0.08 0.12 0.24
Side Arm Mount [SO 701-1]	A	From Leg	1.50 0.00 0.00	0.0000	74.00	No Ice 1/2" Ice 1" Ice 2" Ice	0.85 1.14 1.43 2.01	1.67 2.34 3.01 4.35	0.07 0.08 0.09 0.12
6' x 2" Mount Pipe	A	From Leg	3.00 0.00 2.00	0.0000	74.00	No Ice 1/2" Ice 1" Ice 2" Ice	1.43 1.92 2.29 3.06	1.43 1.92 2.29 3.06	0.02 0.03 0.05 0.09
***									

## Load Combinations

Comb. No.	Description
1	Dead Only
2	1.2 Dead+1.0 Wind 0 deg - No Ice
3	0.9 Dead+1.0 Wind 0 deg - No Ice
4	1.2 Dead+1.0 Wind 30 deg - No Ice
5	0.9 Dead+1.0 Wind 30 deg - No Ice
6	1.2 Dead+1.0 Wind 60 deg - No Ice
7	0.9 Dead+1.0 Wind 60 deg - No Ice
8	1.2 Dead+1.0 Wind 90 deg - No Ice
9	0.9 Dead+1.0 Wind 90 deg - No Ice
10	1.2 Dead+1.0 Wind 120 deg - No Ice
11	0.9 Dead+1.0 Wind 120 deg - No Ice
12	1.2 Dead+1.0 Wind 150 deg - No Ice
13	0.9 Dead+1.0 Wind 150 deg - No Ice
14	1.2 Dead+1.0 Wind 180 deg - No Ice
15	0.9 Dead+1.0 Wind 180 deg - No Ice
16	1.2 Dead+1.0 Wind 210 deg - No Ice
17	0.9 Dead+1.0 Wind 210 deg - No Ice
18	1.2 Dead+1.0 Wind 240 deg - No Ice
19	0.9 Dead+1.0 Wind 240 deg - No Ice
20	1.2 Dead+1.0 Wind 270 deg - No Ice
21	0.9 Dead+1.0 Wind 270 deg - No Ice
22	1.2 Dead+1.0 Wind 300 deg - No Ice
23	0.9 Dead+1.0 Wind 300 deg - No Ice
24	1.2 Dead+1.0 Wind 330 deg - No Ice
25	0.9 Dead+1.0 Wind 330 deg - No Ice
26	1.2 Dead+1.0 Ice+1.0 Temp
27	1.2 Dead+1.0 Wind 0 deg+1.0 Ice+1.0 Temp
28	1.2 Dead+1.0 Wind 30 deg+1.0 Ice+1.0 Temp
29	1.2 Dead+1.0 Wind 60 deg+1.0 Ice+1.0 Temp
30	1.2 Dead+1.0 Wind 90 deg+1.0 Ice+1.0 Temp
31	1.2 Dead+1.0 Wind 120 deg+1.0 Ice+1.0 Temp
32	1.2 Dead+1.0 Wind 150 deg+1.0 Ice+1.0 Temp
33	1.2 Dead+1.0 Wind 180 deg+1.0 Ice+1.0 Temp
34	1.2 Dead+1.0 Wind 210 deg+1.0 Ice+1.0 Temp
35	1.2 Dead+1.0 Wind 240 deg+1.0 Ice+1.0 Temp
36	1.2 Dead+1.0 Wind 270 deg+1.0 Ice+1.0 Temp
37	1.2 Dead+1.0 Wind 300 deg+1.0 Ice+1.0 Temp

Comb. No.	Description
38	1.2 Dead+1.0 Wind 330 deg+1.0 Ice+1.0 Temp
39	Dead+Wind 0 deg - Service
40	Dead+Wind 30 deg - Service
41	Dead+Wind 60 deg - Service
42	Dead+Wind 90 deg - Service
43	Dead+Wind 120 deg - Service
44	Dead+Wind 150 deg - Service
45	Dead+Wind 180 deg - Service
46	Dead+Wind 210 deg - Service
47	Dead+Wind 240 deg - Service
48	Dead+Wind 270 deg - Service
49	Dead+Wind 300 deg - Service
50	Dead+Wind 330 deg - Service

## Maximum Member Forces

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Axial K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
L1	169 - 164.25	Pole	Max Tension	2	0.00	-0.00	-0.00
			Max. Compression	26	-0.52	0.33	-0.18
			Max. Mx	20	-0.28	0.81	-0.07
			Max. My	14	-0.28	0.13	-0.75
			Max. Vy	8	0.31	-0.51	-0.07
			Max. Vx	2	-0.31	0.13	0.58
			Max. Torque	24			0.52
L2	164.25 - 129.75	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-33.08	1.75	0.68
			Max. Mx	20	-15.12	321.85	-0.47
			Max. My	14	-15.12	1.06	-321.58
			Max. Vy	20	-16.20	321.85	-0.47
			Max. Vx	2	-16.25	0.14	321.57
			Max. Torque	16			-0.68
L3	129.75 - 96.08	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-61.61	3.70	1.20
			Max. Mx	20	-30.49	1101.54	-3.03
			Max. My	14	-30.51	4.26	-1098.55
			Max. Vy	20	-29.12	1101.54	-3.03
			Max. Vx	2	-28.95	-1.62	1098.33
			Max. Torque	19			-1.16
L4	96.08 - 63.25	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-76.32	5.85	5.62
			Max. Mx	20	-40.34	2097.30	-4.56
			Max. My	2	-40.36	-3.92	2087.07
			Max. Vy	20	-33.17	2097.30	-4.56
			Max. Vx	2	-32.80	-3.92	2087.07
			Max. Torque	21			-1.99
L5	63.25 - 31.25	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-92.33	8.21	8.80
			Max. Mx	20	-51.49	3188.51	-6.52
			Max. My	2	-51.51	-6.07	3166.01
			Max. Vy	20	-36.50	3188.51	-6.52
			Max. Vx	2	-36.10	-6.07	3166.01
			Max. Torque	21			-1.99
L6	31.25 - 0	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-112.98	11.06	12.71
			Max. Mx	20	-66.55	4622.16	-8.70
			Max. My	2	-66.55	-8.52	4584.91
			Max. Vy	20	-39.72	4622.16	-8.70
			Max. Vx	2	-39.32	-8.52	4584.91
			Max. Torque	21			-1.99

## Maximum Reactions

Location	Condition	Gov. Load Comb.	Vertical K	Horizontal, X K	Horizontal, Z K
Pole	Max. Vert	36	112.98	11.57	-0.02
	Max. H <sub>x</sub>	21	49.93	39.69	-0.08
	Max. H <sub>z</sub>	2	66.57	-0.08	39.29
	Max. M <sub>x</sub>	2	4584.91	-0.08	39.29
	Max. M <sub>z</sub>	8	4615.92	-39.69	0.08
	Max. Torsion	9	1.99	-39.69	0.08
	Min. Vert	17	49.93	19.81	-34.07
	Min. H <sub>x</sub>	9	49.93	-39.69	0.08
	Min. H <sub>z</sub>	15	49.93	0.08	-39.29
	Min. M <sub>x</sub>	14	-4579.04	0.08	-39.29
	Min. M <sub>z</sub>	20	-4622.16	39.69	-0.08
	Min. Torsion	21	-1.99	39.69	-0.08

## Tower Mast Reaction Summary

Load Combination	Vertical K	Shear <sub>x</sub> K	Shear <sub>z</sub> K	Overturning Moment, M <sub>x</sub> kip-ft	Overturning Moment, M <sub>z</sub> kip-ft	Torque kip-ft
Dead Only	55.48	0.00	0.00	-2.37	2.46	0.00
1.2 Dead+1.0 Wind 0 deg - No Ice	66.57	0.08	-39.29	-4584.91	-8.52	-0.53
0.9 Dead+1.0 Wind 0 deg - No Ice	49.93	0.08	-39.29	-4527.79	-9.18	-0.53
1.2 Dead+1.0 Wind 30 deg - No Ice	66.57	19.81	-34.07	-3976.87	-2308.41	-1.45
0.9 Dead+1.0 Wind 30 deg - No Ice	49.93	19.81	-34.07	-3927.21	-2280.80	-1.45
1.2 Dead+1.0 Wind 60 deg - No Ice	66.57	35.81	-20.63	-2361.70	-4088.86	-1.98
0.9 Dead+1.0 Wind 60 deg - No Ice	49.93	35.81	-20.63	-2332.18	-4039.82	-1.99
1.2 Dead+1.0 Wind 90 deg - No Ice	66.57	39.69	-0.08	-14.59	-4615.92	-1.98
0.9 Dead+1.0 Wind 90 deg - No Ice	49.93	39.69	-0.08	-13.68	-4559.99	-1.99
1.2 Dead+1.0 Wind 120 deg - No Ice	66.57	34.15	19.57	2277.97	-3977.31	-1.45
0.9 Dead+1.0 Wind 120 deg - No Ice	49.93	34.15	19.57	2250.67	-3929.18	-1.46
1.2 Dead+1.0 Wind 150 deg - No Ice	66.57	19.67	33.98	3959.37	-2288.26	-0.53
0.9 Dead+1.0 Wind 150 deg - No Ice	49.93	19.67	33.98	3911.37	-2260.91	-0.53
1.2 Dead+1.0 Wind 180 deg - No Ice	66.57	-0.08	39.29	4579.04	14.77	0.53
0.9 Dead+1.0 Wind 180 deg - No Ice	49.93	-0.08	39.29	4523.41	13.80	0.53
1.2 Dead+1.0 Wind 210 deg - No Ice	66.57	-19.81	34.07	3970.97	2314.66	1.45
0.9 Dead+1.0 Wind 210 deg - No Ice	49.93	-19.81	34.07	3922.83	2285.41	1.45
1.2 Dead+1.0 Wind 240 deg - No Ice	66.57	-35.81	20.63	2355.81	4095.09	1.98
0.9 Dead+1.0 Wind 240 deg - No Ice	49.93	-35.81	20.63	2327.81	4044.42	1.99
1.2 Dead+1.0 Wind 270 deg - No Ice	66.57	-39.69	0.08	8.70	4622.16	1.98
0.9 Dead+1.0 Wind 270 deg - No Ice	49.93	-39.69	0.08	9.31	4564.61	1.99
1.2 Dead+1.0 Wind 300 deg - No Ice	66.57	-34.15	-19.57	-2283.86	3983.56	1.45

Load Combination	Vertical K	Shear <sub>x</sub> K	Shear <sub>z</sub> K	Overturning Moment, M <sub>x</sub> kip-ft	Overturning Moment, M <sub>z</sub> kip-ft	Torque kip-ft
0.9 Dead+1.0 Wind 300 deg	49.93	-34.15	-19.57	-2255.04	3933.80	1.46
- No Ice						
1.2 Dead+1.0 Wind 330 deg	66.57	-19.67	-33.98	-3965.27	2294.52	0.53
- No Ice						
0.9 Dead+1.0 Wind 330 deg	49.93	-19.67	-33.98	-3915.75	2265.53	0.53
- No Ice						
1.2 Dead+1.0 Ice+1.0 Temp	112.98	-0.00	-0.00	-12.71	11.06	-0.00
1.2 Dead+1.0 Wind 0	112.98	0.02	-11.51	-1407.38	8.87	-0.07
deg+1.0 Ice+1.0 Temp						
1.2 Dead+1.0 Wind 30	112.98	5.80	-9.98	-1221.74	-691.03	-0.48
deg+1.0 Ice+1.0 Temp						
1.2 Dead+1.0 Wind 60	112.98	10.02	-5.77	-712.17	-1202.76	-0.76
deg+1.0 Ice+1.0 Temp						
1.2 Dead+1.0 Wind 90	112.98	11.57	-0.02	-15.22	-1389.20	-0.83
deg+1.0 Ice+1.0 Temp						
1.2 Dead+1.0 Wind 120	112.98	10.01	5.74	682.35	-1200.43	-0.69
deg+1.0 Ice+1.0 Temp						
1.2 Dead+1.0 Wind 150	112.98	5.77	9.96	1193.63	-686.98	-0.36
deg+1.0 Ice+1.0 Temp						
1.2 Dead+1.0 Wind 180	112.98	-0.02	11.51	1381.61	13.55	0.07
deg+1.0 Ice+1.0 Temp						
1.2 Dead+1.0 Wind 210	112.98	-5.80	9.98	1195.97	713.45	0.48
deg+1.0 Ice+1.0 Temp						
1.2 Dead+1.0 Wind 240	112.98	-10.02	5.77	686.40	1225.19	0.75
deg+1.0 Ice+1.0 Temp						
1.2 Dead+1.0 Wind 270	112.98	-11.57	0.02	-10.54	1411.62	0.83
deg+1.0 Ice+1.0 Temp						
1.2 Dead+1.0 Wind 300	112.98	-10.01	-5.74	-708.11	1222.85	0.69
deg+1.0 Ice+1.0 Temp						
1.2 Dead+1.0 Wind 330	112.98	-5.77	-9.96	-1219.40	709.40	0.36
deg+1.0 Ice+1.0 Temp						
Dead+Wind 0 deg - Service	55.48	0.02	-9.26	-1073.95	-0.13	-0.11
Dead+Wind 30 deg - Service	55.48	4.67	-8.03	-931.76	-537.97	-0.33
Dead+Wind 60 deg - Service	55.48	8.44	-4.86	-554.09	-954.41	-0.46
Dead+Wind 90 deg - Service	55.48	9.35	-0.02	-5.17	-1077.60	-0.47
Dead+Wind 120 deg - Service	55.48	8.05	4.61	530.95	-928.25	-0.35
Dead+Wind 150 deg - Service	55.48	4.63	8.01	924.14	-533.26	-0.14
Dead+Wind 180 deg - Service	55.48	-0.02	9.26	1069.05	5.31	0.11
Dead+Wind 210 deg - Service	55.48	-4.67	8.03	926.86	543.14	0.33
Dead+Wind 240 deg - Service	55.48	-8.44	4.86	549.20	959.58	0.46
Dead+Wind 270 deg - Service	55.48	-9.35	0.02	0.27	1082.77	0.47
Dead+Wind 300 deg - Service	55.48	-8.05	-4.61	-535.84	933.42	0.35
Dead+Wind 330 deg - Service	55.48	-4.63	-8.01	-929.04	538.43	0.14

## Solution Summary

Load Comb.	Sum of Applied Forces			Sum of Reactions			% Error
	PX K	PY K	PZ K	PX K	PY K	PZ K	
1	0.00	-55.48	0.00	0.00	55.48	0.00	0.000%
2	0.08	-66.57	-39.29	-0.08	66.57	39.29	0.000%
3	0.08	-49.93	-39.29	-0.08	49.93	39.29	0.000%
4	19.81	-66.57	-34.07	-19.81	66.57	34.07	0.000%
5	19.81	-49.93	-34.07	-19.81	49.93	34.07	0.000%
6	35.81	-66.57	-20.63	-35.81	66.57	20.63	0.000%
7	35.81	-49.93	-20.63	-35.81	49.93	20.63	0.000%
8	39.69	-66.57	-0.08	-39.69	66.57	0.08	0.000%
9	39.69	-49.93	-0.08	-39.69	49.93	0.08	0.000%

Load Comb.	Sum of Applied Forces			Sum of Reactions			% Error
	PX K	PY K	PZ K	PX K	PY K	PZ K	
10	34.15	-66.57	19.57	-34.15	66.57	-19.57	0.000%
11	34.15	-49.93	19.57	-34.15	49.93	-19.57	0.000%
12	19.67	-66.57	33.98	-19.67	66.57	-33.98	0.000%
13	19.67	-49.93	33.98	-19.67	49.93	-33.98	0.000%
14	-0.08	-66.57	39.29	0.08	66.57	-39.29	0.000%
15	-0.08	-49.93	39.29	0.08	49.93	-39.29	0.000%
16	-19.81	-66.57	34.07	19.81	66.57	-34.07	0.000%
17	-19.81	-49.93	34.07	19.81	49.93	-34.07	0.000%
18	-35.81	-66.57	20.63	35.81	66.57	-20.63	0.000%
19	-35.81	-49.93	20.63	35.81	49.93	-20.63	0.000%
20	-39.69	-66.57	0.08	39.69	66.57	-0.08	0.000%
21	-39.69	-49.93	0.08	39.69	49.93	-0.08	0.000%
22	-34.15	-66.57	-19.57	34.15	66.57	19.57	0.000%
23	-34.15	-49.93	-19.57	34.15	49.93	19.57	0.000%
24	-19.67	-66.57	-33.98	19.67	66.57	33.98	0.000%
25	-19.67	-49.93	-33.98	19.67	49.93	33.98	0.000%
26	0.00	-112.98	0.00	0.00	112.98	0.00	0.000%
27	0.02	-112.98	-11.51	-0.02	112.98	11.51	0.000%
28	5.80	-112.98	-9.98	-5.80	112.98	9.98	0.000%
29	10.02	-112.98	-5.77	-10.02	112.98	5.77	0.000%
30	11.57	-112.98	-0.02	-11.57	112.98	0.02	0.000%
31	10.01	-112.98	5.74	-10.01	112.98	-5.74	0.000%
32	5.77	-112.98	9.96	-5.77	112.98	-9.96	0.000%
33	-0.02	-112.98	11.51	0.02	112.98	-11.51	0.000%
34	-5.80	-112.98	9.98	5.80	112.98	-9.98	0.000%
35	-10.02	-112.98	5.77	10.02	112.98	-5.77	0.000%
36	-11.57	-112.98	0.02	11.57	112.98	-0.02	0.000%
37	-10.01	-112.98	-5.74	10.01	112.98	5.74	0.000%
38	-5.77	-112.98	-9.96	5.77	112.98	9.96	0.000%
39	0.02	-55.48	-9.26	-0.02	55.48	9.26	0.000%
40	4.67	-55.48	-8.03	-4.67	55.48	8.03	0.000%
41	8.44	-55.48	-4.86	-8.44	55.48	4.86	0.000%
42	9.35	-55.48	-0.02	-9.35	55.48	0.02	0.000%
43	8.05	-55.48	4.61	-8.05	55.48	-4.61	0.000%
44	4.63	-55.48	8.01	-4.63	55.48	-8.01	0.000%
45	-0.02	-55.48	9.26	0.02	55.48	-9.26	0.000%
46	-4.67	-55.48	8.03	4.67	55.48	-8.03	0.000%
47	-8.44	-55.48	4.86	8.44	55.48	-4.86	0.000%
48	-9.35	-55.48	0.02	9.35	55.48	-0.02	0.000%
49	-8.05	-55.48	-4.61	8.05	55.48	4.61	0.000%
50	-4.63	-55.48	-8.01	4.63	55.48	8.01	0.000%

## Non-Linear Convergence Results

Load Combination	Converged?	Number of Cycles	Displacement Tolerance	Force Tolerance
1	Yes	4	0.00000001	0.00000001
2	Yes	4	0.00000001	0.00085388
3	Yes	4	0.00000001	0.00041330
4	Yes	6	0.00000001	0.00012110
5	Yes	5	0.00000001	0.00098131
6	Yes	6	0.00000001	0.00012841
7	Yes	6	0.00000001	0.00004371
8	Yes	5	0.00000001	0.00009185
9	Yes	4	0.00000001	0.00099911
10	Yes	6	0.00000001	0.00011981
11	Yes	5	0.00000001	0.00097122
12	Yes	6	0.00000001	0.00012140
13	Yes	5	0.00000001	0.00098497
14	Yes	5	0.00000001	0.00006002
15	Yes	4	0.00000001	0.00061270
16	Yes	6	0.00000001	0.00012490
17	Yes	6	0.00000001	0.00004274
18	Yes	6	0.00000001	0.00012404
19	Yes	6	0.00000001	0.00004206

20	Yes	5	0.00000001	0.00006913
21	Yes	4	0.00000001	0.00073962
22	Yes	6	0.00000001	0.00012314
23	Yes	5	0.00000001	0.00099783
24	Yes	6	0.00000001	0.00012147
25	Yes	5	0.00000001	0.00098410
26	Yes	4	0.00000001	0.00009639
27	Yes	5	0.00000001	0.00092893
28	Yes	6	0.00000001	0.00013710
29	Yes	6	0.00000001	0.00013842
30	Yes	5	0.00000001	0.00091765
31	Yes	6	0.00000001	0.00013429
32	Yes	6	0.00000001	0.00013486
33	Yes	5	0.00000001	0.00091446
34	Yes	6	0.00000001	0.00013833
35	Yes	6	0.00000001	0.00013739
36	Yes	5	0.00000001	0.00093425
37	Yes	6	0.00000001	0.00014024
38	Yes	6	0.00000001	0.00013923
39	Yes	4	0.00000001	0.00014437
40	Yes	4	0.00000001	0.00058681
41	Yes	4	0.00000001	0.00066430
42	Yes	4	0.00000001	0.00015968
43	Yes	4	0.00000001	0.00057907
44	Yes	4	0.00000001	0.00060010
45	Yes	4	0.00000001	0.00014515
46	Yes	4	0.00000001	0.00063710
47	Yes	4	0.00000001	0.00060684
48	Yes	4	0.00000001	0.00015795
49	Yes	4	0.00000001	0.00062758
50	Yes	4	0.00000001	0.00060264

### Maximum Tower Deflections - Service Wind

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
L1	169 - 164.25	23.303	47	1.1048	0.0013
L2	166.625 - 129.75	22.753	47	1.1047	0.0013
L3	133.58 - 96.08	15.319	47	1.0153	0.0009
L4	100.75 - 63.25	8.925	47	0.8207	0.0006
L5	68.75 - 31.25	4.206	47	0.5668	0.0005
L6	37.5 - 0	1.282	47	0.3067	0.0002

### Critical Deflections and Radius of Curvature - Service Wind

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
169.00	Lightning Rod 5/8" x 4'	47	23.303	1.1048	0.0013	75403
167.00	8' x 3" Mount Pipe	47	22.840	1.1047	0.0013	75403
164.00	APXVAARR24_43-U-NA20 w/ Mount Pipe	47	22.146	1.1035	0.0013	75403
155.00	APXVTM14-C-120 w/ Mount Pipe	47	20.078	1.0905	0.0012	30103
142.00	MT6407-77A w/ Mount Pipe	47	17.151	1.0511	0.0010	16149
132.00	MX08FRO665-21 w/ Mount Pipe	47	14.983	1.0078	0.0009	12101
121.00	201-4	47	12.712	0.9505	0.0008	10103
115.00	7770.00	47	11.533	0.9153	0.0007	9277
105.00	APXV18-206517S-C w/ Mount Pipe	47	9.672	0.8505	0.0007	8165
74.00	DB810T3E-XT	47	4.868	0.6105	0.0005	7479

### Maximum Tower Deflections - Design Wind

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
L1	169 - 164.25	99.603	18	4.7261	0.0056
L2	166.625 - 129.75	97.257	18	4.7258	0.0056
L3	133.58 - 96.08	65.501	18	4.3455	0.0041
L4	100.75 - 63.25	38.168	18	3.5127	0.0027
L5	68.75 - 31.25	17.986	18	2.4255	0.0019
L6	37.5 - 0	5.480	18	1.3115	0.0008

### Critical Deflections and Radius of Curvature - Design Wind

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
169.00	Lightning Rod 5/8" x 4'	18	99.603	4.7261	0.0056	18568
167.00	8' x 3" Mount Pipe	18	97.627	4.7261	0.0056	18568
164.00	APXVAARR24_43-U-NA20 w/ Mount Pipe	18	94.666	4.7212	0.0056	18568
155.00	APXVTM14-C-120 w/ Mount Pipe	18	85.830	4.6667	0.0053	7209
142.00	MT6407-77A w/ Mount Pipe	18	73.329	4.4985	0.0046	3831
132.00	MX08FRO665-21 w/ Mount Pipe	18	64.063	4.3137	0.0040	2863
121.00	201-4	18	54.358	4.0687	0.0034	2387
115.00	7770.00	18	49.316	3.9177	0.0032	2190
105.00	APXV18-206517S-C w/ Mount Pipe	18	41.363	3.6402	0.0029	1925
74.00	DB810T3E-XT	18	20.820	2.6126	0.0021	1754

### Compression Checks

### Pole Design Data

Section No.	Elevation ft	Size	L ft	L <sub>u</sub> ft	KI/r	A in <sup>2</sup>	P <sub>u</sub> K	φP <sub>n</sub> K	Ratio $\frac{P_u}{\phi P_n}$
L1	169 - 164.25 (1)	TP26x18x0.25	4.75	0.00	0.0	17.258 6	-0.45	1009.63	0.000
L2	164.25 - 129.75 (2)	TP34.0625x21.5x0.3125	36.88	0.00	0.0	32.181 6	-15.10	1882.62	0.008
L3	129.75 - 96.08 (3)	TP41.75x32.1327x0.375	37.50	0.00	0.0	47.821 1	-30.46	2797.53	0.011
L4	96.08 - 63.25 (4)	TP49.0625x39.8023x0.37 5	37.50	0.00	0.0	56.333 7	-40.29	3295.52	0.012
L5	63.25 - 31.25 (5)	TP56.125x46.9543x0.375	37.50	0.00	0.0	64.537 2	-51.45	3775.43	0.014
L6	31.25 - 0 (6)	TP62.9375x53.8466x0.37 5	37.50	0.00	0.0	74.465 0	-66.55	4356.20	0.015

### Pole Bending Design Data

Section No.	Elevation ft	Size	$M_{ux}$ kip-ft	$\phi M_{nx}$ kip-ft	Ratio $\frac{M_{ux}}{\phi M_{nx}}$	$M_{uy}$ kip-ft	$\phi M_{ny}$ kip-ft	Ratio $\frac{M_{uy}}{\phi M_{ny}}$
L1	169 - 164.25 (1)	TP26x18x0.25	0.83	571.42	0.001	0.00	571.42	0.000
L2	164.25 - 129.75 (2)	TP34.0625x21.5x0.3125	322.48	1557.39	0.207	0.00	1557.39	0.000
L3	129.75 - 96.08 (3)	TP41.75x32.1327x0.375	1106.18	2842.24	0.389	0.00	2842.24	0.000
L4	96.08 - 63.25 (4)	TP49.0625x39.8023x0.375	2114.76	3754.93	0.563	0.00	3754.93	0.000
L5	63.25 - 31.25 (5)	TP56.125x46.9543x0.375	3236.35	4686.48	0.691	0.00	4686.48	0.000
L6	31.25 - 0 (6)	TP62.9375x53.8466x0.375	4724.37	5847.24	0.808	0.00	5847.24	0.000

### Pole Shear Design Data

Section No.	Elevation ft	Size	Actual $V_u$ K	$\phi V_n$ K	Ratio $\frac{V_u}{\phi V_n}$	Actual $T_u$ kip-ft	$\phi T_n$ kip-ft	Ratio $\frac{T_u}{\phi T_n}$
L1	169 - 164.25 (1)	TP26x18x0.25	0.11	302.89	0.000	0.00	576.93	0.000
L2	164.25 - 129.75 (2)	TP34.0625x21.5x0.3125	16.26	564.79	0.029	0.63	1604.78	0.000
L3	129.75 - 96.08 (3)	TP41.75x32.1327x0.375	29.31	839.26	0.035	0.70	2952.96	0.000
L4	96.08 - 63.25 (4)	TP49.0625x39.8023x0.375	33.88	988.66	0.034	1.98	4097.85	0.000
L5	63.25 - 31.25 (5)	TP56.125x46.9543x0.375	37.74	1132.63	0.033	1.98	5378.23	0.000
L6	31.25 - 0 (6)	TP62.9375x53.8466x0.375	41.36	1306.86	0.032	1.98	7160.17	0.000

### Pole Interaction Design Data

Section No.	Elevation ft	Ratio $\frac{P_u}{\phi P_n}$	Ratio $\frac{M_{ux}}{\phi M_{nx}}$	Ratio $\frac{M_{uy}}{\phi M_{ny}}$	Ratio $\frac{V_u}{\phi V_n}$	Ratio $\frac{T_u}{\phi T_n}$	Comb. Stress Ratio	Allow. Stress Ratio	Criteria
L1	169 - 164.25 (1)	0.000	0.001	0.000	0.000	0.000	0.002	1.050	4.8.2
L2	164.25 - 129.75 (2)	0.008	0.207	0.000	0.029	0.000	0.216	1.050	4.8.2
L3	129.75 - 96.08 (3)	0.011	0.389	0.000	0.035	0.000	0.401	1.050	4.8.2
L4	96.08 - 63.25 (4)	0.012	0.563	0.000	0.034	0.000	0.577	1.050	4.8.2
L5	63.25 - 31.25 (5)	0.014	0.691	0.000	0.033	0.000	0.705	1.050	4.8.2
L6	31.25 - 0 (6)	0.015	0.808	0.000	0.032	0.000	0.824	1.050	4.8.2

### Section Capacity Table

Section No.	Elevation ft	Component Type	Size	Critical Element	P K	$\phi P_{allow}$ K	% Capacity	Pass Fail
-------------	-----------------	-------------------	------	---------------------	--------	-----------------------	---------------	--------------

Section No.	Elevation ft	Component Type	Size	Critical Element	P K	$\phi P_{allow}$ K	% Capacity	Pass Fail
L1	169 - 164.25	Pole	TP26x18x0.25	1	-0.45	1060.11	0.2	Pass
L2	164.25 - 129.75	Pole	TP34.0625x21.5x0.3125	2	-15.10	1976.75	20.6	Pass
L3	129.75 - 96.08	Pole	TP41.75x32.1327x0.375	3	-30.46	2937.41	38.2	Pass
L4	96.08 - 63.25	Pole	TP49.0625x39.8023x0.375	4	-40.29	3460.30	54.9	Pass
L5	63.25 - 31.25	Pole	TP56.125x46.9543x0.375	5	-51.45	3964.20	67.2	Pass
L6	31.25 - 0	Pole	TP62.9375x53.8466x0.375	6	-66.55	4574.01	78.5	Pass
							Summary	
							Pole (L6)	78.5 Pass
							<b>RATING =</b>	<b>78.5 Pass</b>

**APPENDIX B**  
**BASE LEVEL DRAWING**



(OTHER CONSIDERED EQUIPMENT—IN (2) CONDUITS)  
(3) 3/8" TO 115 FT LEVEL  
(6) 5/8" TO 115 FT LEVEL  
(OTHER CONSIDERED EQUIPMENT)  
(12) 1-5/8" TO 115 FT LEVEL

(OTHER CONSIDERED EQUIPMENT)  
(4) 7/8" TO 164 FT LEVEL

(OTHER CONSIDERED EQUIPMENT)  
(1) 7/8" TO 74 FT LEVEL

(OTHER CONSIDERED EQUIPMENT)  
(1) 1/2" TO 121 FT LEVEL

CLIMBING RUNGS  
W/ SAFETY CLIMB

(OTHER CONSIDERED EQUIPMENT)  
(8) 1-5/8" TO 142 FT LEVEL


(PROPOSED EQUIPMENT CONFIGURATION)  
(1) 1-1/2" TO 132 FT LEVEL

(OTHER CONSIDERED EQUIPMENT)  
(6) 1-5/8" TO 105 FT LEVEL

(OTHER CONSIDERED EQUIPMENT)  
(4) 1-1/4" TO 155 FT LEVEL

(OTHER CONSIDERED EQUIPMENT)  
(7) 7/8" TO 164 FT LEVEL

(OTHER CONSIDERED EQUIPMENT)  
(3) 1-5/8" TO 164 FT LEVEL



## **APPENDIX C**

### **ADDITIONAL CALCULATIONS**

# Monopole Base Plate Connection




Site Info	
BU #	826768
Site Name	Plymouth/Rt 6
Order #	553358 Rev. 1

Analysis Considerations	
TIA-222 Revision	H
Grout Considered:	No
$l_{ar}$ (in)	1.5

Applied Loads	
Moment (kip-ft)	4724.37
Axial Force (kips)	66.55
Shear Force (kips)	41.36

\*TIA-222-H Section 15.5 Applied



Connection Properties		Analysis Results	
<b>Anchor Rod Data</b>		<b>Anchor Rod Summary</b> <i>(units of kips, kip-in)</i>	
(45) 1-1/4" $\phi$ bolts (A687 N; $F_y=105$ ksi, $F_u=125$ ksi) on 68" BC		$Pu_t = 72.62$	$\phi Pn_t = 90.84$ <b>Stress Rating</b>
<b>Base Plate Data</b>		$Vu = 0.92$	$\phi Vn = 57.52$ <b>76.1%</b>
73" OD x 2.5" Plate (A572-50; $F_y=50$ ksi, $F_u=65$ ksi)		$Mu = 0.9$	$\phi Mn = 30.76$ <b>Pass</b>
<b>Stiffener Data</b>		<b>Base Plate Summary</b>	
N/A		Max Stress (ksi):	17.45 (Flexural)
<b>Pole Data</b>		Allowable Stress (ksi):	45
62.9375" x 0.375" 18-sided pole (A572-65; $F_y=65$ ksi, $F_u=80$ ksi)		Stress Rating:	<b>36.9%</b> <b>Pass</b>

## Pier and Pad Foundation



BU #: 826768  
 Site Name: Plymouth/Rt. 6  
 App. Number: 553358 Rev. 1

TIA-222 Revision: H  
 Tower Type: Monopole

Top & Bot. Pad Rein. Different?: ☐  
 Block Foundation?: ☐  
 Rectangular Pad?: ☐

Superstructure Analysis Reactions		
Compression, $P_{comp}$ :	66.57	kips
Base Shear, $Vu_{comp}$ :	41.33	kips
Moment, $M_u$ :	4724.36	ft-kips
Tower Height, $H$ :	169	ft
BP Dist. Above Fdn, $bp_{dist}$ :	2.75	in

Pier Properties		
Pier Shape:	Circular	
Pier Diameter, $dpier$ :	7.5	ft
Ext. Above Grade, $E$ :	0.5	ft
Pier Rebar Size, $Sc$ :	9	
Pier Rebar Quantity, $mc$ :	39	
Pier Tie/Spiral Size, $St$ :	4	
Pier Tie/Spiral Quantity, $mt$ :	11	
Pier Reinforcement Type:	Tie	
Pier Clear Cover, $cc_{pier}$ :	3	in

Pad Properties		
Depth, $D$ :	8.5	ft
Pad Width, $W_1$ :	27	ft
Pad Thickness, $T$ :	2.5	ft
Pad Rebar Size (Bottom dir. 2), $Sp_2$ :	9	
Pad Rebar Quantity (Bottom dir. 2), $mp_2$ :	36	
Pad Clear Cover, $cc_{pad}$ :	3	in

Material Properties		
Rebar Grade, $F_y$ :	60	ksi
Concrete Compressive Strength, $F'_c$ :	4	ksi
Dry Concrete Density, $\delta c$ :	150	pcf

Soil Properties		
Total Soil Unit Weight, $\gamma$ :	125	pcf
Ultimate Gross Bearing, $Q_{ult}$ :	12.000	ksf
Cohesion, $C_u$ :		ksf
Friction Angle, $\phi$ :	34	degrees
SPT Blow Count, $N_{blows}$ :	104	
Base Friction, $\mu$ :	0.6	
Neglected Depth, $N$ :	3.75	ft
Foundation Bearing on Rock?	No	
Groundwater Depth, $gw$ :	14	ft

Foundation Analysis Checks				
	Capacity	Demand	Rating*	Check
Lateral (Sliding) (kips)	548.20	41.33	7.2%	Pass
Bearing Pressure (ksf)	9.00	2.54	26.8%	Pass
Overturning (kip*ft)	9553.25	5105.80	53.4%	Pass
Pier Flexure (Comp.) (kip*ft)	6863.08	4993.01	69.3%	Pass
Pier Compression (kip)	28118.83	118.26	0.4%	Pass
Pad Flexure (kip*ft)	3941.07	1717.08	41.5%	Pass
Pad Shear - 1-way (kips)	777.90	260.69	31.9%	Pass
Pad Shear - 2-way (Comp) (ksi)	0.190	0.064	32.0%	Pass
Flexural 2-way (Comp) (kip*ft)	4354.14	2995.80	65.5%	Pass

\*Rating per TIA-222-H Section 15.5

Structural Rating*:	69.3%
Soil Rating*:	53.4%

<--Toggle between Gross and Net

BU:	826768
WO:	1966237
APP:	553358 Rev. 1
TIA:	TIA-222-H



- ☐ Reinforced Tower  
☒ Apply TIA-222-H Section 15.5

**Table 1: Tower Geometry**

	Height Above Ground (ft)	Section Length (ft)	Lap Splice Length (ft)	Number of Sides	Top Diameter (in)	Bottom Diameter (in)	Wall Thickness (in)	Bend Radius (in)	Pole Material
1	169.000	4.750	2.375	18	18.0000	26.0000	0.2500	1.0000	A572-65
2	166.630	36.875	3.830	18	21.5000	34.0625	0.3125	1.2500	A572-65
3	133.580	37.500	4.670	18	32.1327	41.7500	0.3750	1.5000	A572-65
4	100.750	37.500	5.500	18	39.8023	49.0625	0.3750	1.5000	A572-65
5	68.750	37.500	6.250	18	46.9543	56.1250	0.3750	1.5000	A572-65
6	37.500	37.500	0.000	18	53.8466	62.9375	0.3750	1.5000	A572-65

**Table 2: Splice Check**

*(Highlighted values can be taken from the Tapered Pole Properties table of the TNX Output)*

	Lap Splice Length (in)	Bottom Inner Diameter (in)	Required Splice (in)	Splice Check	Tip Diameter (in)	A (in <sup>2</sup> )	I (in <sup>4</sup> )	Bottom w/t	S (in <sup>3</sup> )
1	28.500	25.500	38.250	Reduce Strength	26.363	20.433	1711.654	16.544	129.855
2	45.960	33.438	50.156	Reduce Strength	34.540	33.476	4817.434	17.424	278.950
3	56.040	41.000	61.500	Reduce Strength	42.336	49.247	10650.982	17.835	503.162
4	66.000	48.313	72.469	Reduce Strength	49.762	57.950	17355.138	21.267	697.533
5	75.000	55.375	83.063	Reduce Strength	56.933	66.356	26056.151	24.581	915.327

**Table 3: Loading**

*(Highlighted values can be taken from the MPAUXDATA worksheet created with the TNX output)*

	$\sqrt{(F_y/E)} * (w/t)$	Reduction Factor	F <sub>y</sub> ' (ksi)	ΦP <sub>n</sub> (kip)	ΦM <sub>n</sub> (kip-ft)	ΦV <sub>n</sub> (kip)	P <sub>u</sub> (kip)	M <sub>u</sub> (kip-ft)	V <sub>u</sub> (kip)
1	0.783	0.62	50.61	738	493	221	0.45	0.83	0.11
2	0.825	0.87	70.75	1713	1480	514	15.10	322.48	16.26
3	0.844	0.87	69.71	2497	2631	749	30.46	1106.18	29.31
4	1.007	0.87	66.16	2936	3461	881	40.29	2114.76	33.88
5	1.164	0.85	61.93	3317	4252	995	51.45	3236.35	37.74

### Results


	Ratio (%)
1	0.2%
2	21.7%
3	41.4%
4	59.6%
5	74.1%

# ASCE 7 Hazards Report

**Address:**  
No Address at This  
Location

**Standard:** ASCE/SEI 7-10  
**Risk Category:** II  
**Soil Class:** D - Stiff Soil

**Elevation:** 889.9 ft (NAVD 88)  
**Latitude:** 41.668388  
**Longitude:** -73.019956



## Wind

### Results:

Wind Speed: ~~119 Vmph~~  
10-year MRI 76 Vmph  
25-year MRI 86 Vmph  
50-year MRI 91 Vmph  
100-year MRI 98 Vmph

120 mph per Appendix N of 2018 Connecticut State Building Code

**Data Source:** ASCE/SEI 7-10 Fig. 26.5-1A and Figs. CC-1–CC-4, and Section 26.5.2, incorporating errata of March 12, 2014

Value provided is 3-second gust wind speeds at 33 ft above ground for Exposure C Category, based on linear interpolation between contours. Wind speeds are interpolated in accordance with the 7-10 Standard. Wind speeds correspond to approximately a 7% probability of exceedance in 50 years (annual exceedance probability = 0.00143, MRI = 700 years).



Site is in a hurricane-prone region as defined in ASCE/SEI 7-10 Section 26.2. Glazed openings need not be protected against wind-borne debris.

**Site Soil Class:** D - Stiff Soil

**Results:**

$S_S$ :	0.186	$S_{DS}$ :	0.198
$S_1$ :	0.064	$S_{D1}$ :	0.103
$F_a$ :	1.6	$T_L$ :	6
$F_v$ :	2.4	PGA :	0.095
$S_{MS}$ :	0.297	PGA <sub>M</sub> :	0.152
$S_{M1}$ :	0.154	$F_{PGA}$ :	1.6
		$I_e$ :	1

**Seismic Design Category** B



**Data Accessed:**

Mon May 24 2021

**Date Source:**

USGS Seismic Design Maps based on ASCE/SEI 7-10, incorporating Supplement 1 and errata of March 31, 2013, and ASCE/SEI 7-10 Table 1.5-2. Additional data for site-specific ground motion procedures in accordance with ASCE/SEI 7-10 Ch. 21 are available from USGS.

**Results:**

Ice Thickness: 0.75 in.

Concurrent Temperature: 5 F

Gust Speed: 50 mph

**Data Source:** Standard ASCE/SEI 7-10, Figs. 10-2 through 10-8

**Date Accessed:** Mon May 24 2021

Ice thicknesses on structures in exposed locations at elevations higher than the surrounding terrain and in valleys and gorges may exceed the mapped values.

Values provided are equivalent radial ice thicknesses due to freezing rain with concurrent 3-second gust speeds, for a 50-year mean recurrence interval, and temperatures concurrent with ice thicknesses due to freezing rain. Thicknesses for ice accretions caused by other sources shall be obtained from local meteorological studies. Ice thicknesses in exposed locations at elevations higher than the surrounding terrain and in valleys and gorges may exceed the mapped values.

---

The ASCE 7 Hazard Tool is provided for your convenience, for informational purposes only, and is provided "as is" and without warranties of any kind. The location data included herein has been obtained from information developed, produced, and maintained by third party providers; or has been extrapolated from maps incorporated in the ASCE 7 standard. While ASCE has made every effort to use data obtained from reliable sources or methodologies, ASCE does not make any representations or warranties as to the accuracy, completeness, reliability, currency, or quality of any data provided herein. Any third-party links provided by this Tool should not be construed as an endorsement, affiliation, relationship, or sponsorship of such third-party content by or from ASCE.

ASCE does not intend, nor should anyone interpret, the results provided by this Tool to replace the sound judgment of a competent professional, having knowledge and experience in the appropriate field(s) of practice, nor to substitute for the standard of care required of such professionals in interpreting and applying the contents of this Tool or the ASCE 7 standard.

In using this Tool, you expressly assume all risks associated with your use. Under no circumstances shall ASCE or its officers, directors, employees, members, affiliates, or agents be liable to you or any other person for any direct, indirect, special, incidental, or consequential damages arising from or related to your use of, or reliance on, the Tool or any information obtained therein. To the fullest extent permitted by law, you agree to release and hold harmless ASCE from any and all liability of any nature arising out of or resulting from any use of data provided by the ASCE 7 Hazard Tool.

# Exhibit E

## **Mount Analysis**

Date: **July 29, 2021**

Darcy Tarr  
Crown Castle  
3530 Toringdon Way, Suite 300  
Charlotte, NC 28277  
704-405-6589



Trylon  
1825 W. Walnut Hill Lane,  
Suite 302  
Irving, TX 75038  
214-930-1730

**Subject:** **Mount Replacement Analysis Report**

**Carrier Designation:** **Dish Network Dish 5G**  
**Carrier Site Number:** BOHVN00014A  
**Carrier Site Name:** CT-CCI-T-826768

**Crown Castle Designation:** **Crown Castle BU Number:** 826768  
**Crown Castle Site Name:** PLYMOUTH/RT 6  
**Crown Castle JDE Job Number:** 645129  
**Crown Castle Order Number:** 553358 Rev. 1

**Engineering Firm Designation:** **Trylon Report Designation:** 189031

**Site Data:** **171 Town Hill Road, Plymouth, Litchfield County, CT, 06786**  
**Latitude 41°40'6.20" Longitude -73°1'11.84"**

**Structure Information:** **Tower Height & Type:** 169.0 ft Monopole  
**Mount Elevation:** 132.0 ft  
**Mount Type:** 8.0 ft Platform

Dear Darcy Tarr,

Trylon is pleased to submit this "**Mount Replacement Analysis Report**" to determine the structural integrity of Dish Network's antenna mounting system with the proposed appurtenance and equipment addition on the abovementioned supporting tower structure. Analysis of the existing supporting tower structure is to be completed by others and therefore is not part of this analysis. Analysis of the antenna mounting system as a tie-off point for fall protection or rigging is not part of this document.

The purpose of the analysis is to determine acceptability of the mount stress level. Based on our analysis we have determined the mount stress level to be:

**Platform**


**Sufficient\***

**\*Sufficient upon completion of the changes listed in the 'Recommendations' section of this report.**

This analysis utilizes an ultimate 3-second gust wind speed of 120 mph as required by the 2018 Connecticut State Building Code. Applicable Standard references and design criteria are listed in Section 2 - Analysis Criteria.

Mount analysis prepared by: Marius Balan

Respectfully Submitted by:  
Cliff Abernathy, P.E.



## **TABLE OF CONTENTS**

### **1) INTRODUCTION**

### **2) ANALYSIS CRITERIA**

Table 1 - Proposed Equipment Configuration

### **3) ANALYSIS PROCEDURE**

Table 2 - Documents Provided

3.1) Analysis Method

3.2) Assumptions

### **4) ANALYSIS RESULTS**

Table 3 - Mount Component Stresses vs. Capacity

4.1) Recommendations

### **5) APPENDIX A**

Wire Frame and Rendered Models

### **6) APPENDIX B**

Software Input Calculations

### **7) APPENDIX C**

Software Analysis Output

### **8) APPENDIX D**

Additional Calculations

### **9) APPENDIX E**

Supplemental Drawings

## 1) INTRODUCTION

This is a proposed 3 sector 8.0 ft Platform, designed by Commscope.

## 2) ANALYSIS CRITERIA

<b>Building Code:</b>	2015 IBC
<b>TIA-222 Revision:</b>	TIA-222-H
<b>Risk Category:</b>	II
<b>Ultimate Wind Speed:</b>	120 mph
<b>Exposure Category:</b>	C
<b>Topographic Factor at Base:</b>	1.0
<b>Topographic Factor at Mount:</b>	1.0
<b>Ice Thickness:</b>	1.5 in
<b>Wind Speed with Ice:</b>	50 mph
<b>Seismic <math>S_s</math>:</b>	0.186
<b>Seismic <math>S_1</math>:</b>	0.064
<b>Live Loading Wind Speed:</b>	30 mph
<b>Man Live Load at Mid/End-Points:</b>	250 lb
<b>Man Live Load at Mount Pipes:</b>	500 lb

**Table 1 - Proposed Equipment Configuration**

Mount Centerline (ft)	Antenna Centerline (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Mount / Modification Details
132.0	132.0	3	JMA WIRELESS	MX08FRO665-21	8.0 ft Platform [Commscope MC-PK8-C]
		3	FUJITSU	TA08025-B604	
		3	FUJITSU	TA08025-B605	
		1	RAYCAP	RDIDC-9181-PF-48	

## 3) ANALYSIS PROCEDURE

**Table 2 - Documents Provided**

Document	Remarks	Reference	Source
Crown Application	Dish Network Application	553358, Rev. 1	CCI Sites
Mount Manufacturer Drawings	Commscope	MC-PK8-C	Trylon

### 3.1) Analysis Method

RISA-3D (Version 17.0.4), a commercially available analysis software package, was used to create a three-dimensional model of the antenna mounting system and calculate member stresses for various loading cases.

A tool internally developed, using Microsoft Excel, by Tylon was used to calculate wind loading on all appurtenances, dishes, and mount members for various load cases. Selected output from the analysis is included in Appendix B.

This analysis was performed in accordance with Crown Castle's ENG-SOW-10208 *Tower Mount Analysis* (Revision B).

### 3.2) Assumptions

- 1) The antenna mounting system was properly fabricated, installed and maintained in good condition in accordance with its original design and manufacturer's specifications.
- 2) The configuration of antennas, mounts, and other appurtenances are as specified in Table 1 and the referenced drawings.
- 3) All member connections are assumed to have been designed to meet or exceed the load carrying capacity of the connected member unless otherwise specified in this report.
- 4) The analysis will be required to be revised if the existing conditions in the field differ from those shown in the above-referenced documents or assumed in this analysis. No allowance was made for any damaged, missing, or rusted members.
- 5) Prior structural modifications to the tower mounting system are assumed to be installed as shown per available data.
- 6) Steel grades have been assumed as follows, unless noted otherwise:
 

Channel, Solid Round, Angle, Plate	ASTM A36 (GR 36)
HSS (Rectangular)	ASTM A500 (GR B-46)
Pipe	ASTM A53 (GR 35)
Connection Bolts	ASTM A325

This analysis may be affected if any assumptions are not valid or have been made in error. Tylon should be notified to determine the effect on the structural integrity of the antenna mounting system.

## 4) ANALYSIS RESULTS

**Table 3 - Mount Component Stresses vs. Capacity (Platform, All Sectors)**

Notes	Component	Critical Member	Centerline (ft)	% Capacity	Pass / Fail
1, 2	Mount Pipe(s)	MP8	132.0	26.5	Pass
	Horizontal(s)	H3		11.8	Pass
	Standoff(s)	M7		45.7	Pass
	Bracing(s)	M1		36.8	Pass
	Plate(s)	M10		21.3	Pass
	Handrail(s)	M19		10.5	Pass
	Mount Connection(s)	-		18.6	Pass

<b>Structure Rating (max from all components) =</b>	<b>45.7%</b>
---	--------------

Notes:

- 1) See additional documentation in "Appendix C - Software Analysis Output" for calculations supporting the % capacity consumed.
- 2) Rating per TIA-222-H, Section 15.5



#### **4.1) Recommendations**

The mount has sufficient capacity to carry the proposed loading configuration. In order for the results of the analysis to be considered valid, the proposed mount listed below must be installed.

1. Commscope, part no MC-PK8-C.

No structural modifications are required at this time, provided that the above-listed changes are implemented.

**APPENDIX A**  
**WIRE FRAME AND RENDERED MODELS**



Trylon


MB

826768

SK - 1

July 28, 2021 at 9:37 AM

826768.r3d


$$\dot{U} \dot{a}^* \wedge \dot{A} G$$


**APPENDIX B**  
**SOFTWARE INPUT CALCULATIONS**

# ASCE 7 Hazards Report

**Address:**  
No Address at This  
Location

**Standard:** ASCE/SEI 7-10  
**Risk Category:** II  
**Soil Class:** D - Stiff Soil

**Elevation:** 889.9 ft (NAVD 88)  
**Latitude:** 41.668389  
**Longitude:** -73.019956





**Site Soil Class:** D - Stiff Soil

**Results:**

$S_S$ :	0.186	$S_{DS}$ :	0.198
$S_1$ :	0.064	$S_{D1}$ :	0.103
$F_a$ :	1.6	$T_L$ :	6
$F_v$ :	2.4	PGA :	0.095
$S_{MS}$ :	0.297	$PGA_M$ :	0.152
$S_{M1}$ :	0.154	$F_{PGA}$ :	1.6
		$I_e$ :	1

**Seismic Design Category** B



**Data Accessed:**

Tue Jul 27 2021

**Date Source:**

USGS Seismic Design Maps based on ASCE/SEI 7-10, incorporating Supplement 1 and errata of March 31, 2013, and ASCE/SEI 7-10 Table 1.5-2. Additional data for site-specific ground motion procedures in accordance with ASCE/SEI 7-10 Ch. 21 are available from USGS.

**Results:**

Ice Thickness: 0.75 in.

Concurrent Temperature: 5 F

Gust Speed: 50 mph

**Data Source:** Standard ASCE/SEI 7-10, Figs. 10-2 through 10-8

**Date Accessed:** Tue Jul 27 2021

Ice thicknesses on structures in exposed locations at elevations higher than the surrounding terrain and in valleys and gorges may exceed the mapped values.

Values provided are equivalent radial ice thicknesses due to freezing rain with concurrent 3-second gust speeds, for a 50-year mean recurrence interval, and temperatures concurrent with ice thicknesses due to freezing rain. Thicknesses for ice accretions caused by other sources shall be obtained from local meteorological studies. Ice thicknesses in exposed locations at elevations higher than the surrounding terrain and in valleys and gorges may exceed the mapped values.

---

The ASCE 7 Hazard Tool is provided for your convenience, for informational purposes only, and is provided "as is" and without warranties of any kind. The location data included herein has been obtained from information developed, produced, and maintained by third party providers; or has been extrapolated from maps incorporated in the ASCE 7 standard. While ASCE has made every effort to use data obtained from reliable sources or methodologies, ASCE does not make any representations or warranties as to the accuracy, completeness, reliability, currency, or quality of any data provided herein. Any third-party links provided by this Tool should not be construed as an endorsement, affiliation, relationship, or sponsorship of such third-party content by or from ASCE.

ASCE does not intend, nor should anyone interpret, the results provided by this Tool to replace the sound judgment of a competent professional, having knowledge and experience in the appropriate field(s) of practice, nor to substitute for the standard of care required of such professionals in interpreting and applying the contents of this Tool or the ASCE 7 standard.

In using this Tool, you expressly assume all risks associated with your use. Under no circumstances shall ASCE or its officers, directors, employees, members, affiliates, or agents be liable to you or any other person for any direct, indirect, special, incidental, or consequential damages arising from or related to your use of, or reliance on, the Tool or any information obtained therein. To the fullest extent permitted by law, you agree to release and hold harmless ASCE from any and all liability of any nature arising out of or resulting from any use of data provided by the ASCE 7 Hazard Tool.

## TIA LOAD CALCULATOR 2.0

PROJECT DATA		
Job Code:	189031	
Carrier Site ID:	BOHVN00014A	
Carrier Site Name:	CT-CCI-T826768	

CODES AND STANDARDS		
Building Code:	2015 IBC	
Local Building Code:	18 Connecticut State Buildi	
Design Standard:	TIA-222-H	

STRUCTURE DETAILS		
Mount Type:	Platform	--
Mount Elevation:	132.0	ft.
Number of Sectors:	3	--
Structure Type:	Monopole	--
Structure Height:	169.0	ft.

ANALYSIS CRITERIA		
Structure Risk Category:	II	--
Exposure Category:	C	--
Site Class:	D - Stiff Soil	--
Ground Elevation:	889.9	ft.

TOPOGRAPHIC DATA		
Topographic Category:	1.00	--
Topographic Feature:	N/A	--
Crest Point Elevation:	0.00	ft.
Base Point Elevation:	0.00	ft.
Crest to Mid-Height (L/2):	0.00	ft.
Distance from Crest (x):	0.00	ft.
Base Topo Factor ( $K_{zt}$ ):	1.00	--
Mount Topo Factor ( $K_{zt}$ ):	1.00	--

WIND PARAMETERS		
Design Wind Speed:	120	mph
Wind Escalation Factor ( $K_s$ ):	1.00	--
Velocity Coefficient ( $K_z$ ):	1.34	--
Directionality Factor ( $K_d$ ):	0.95	--
Gust Effect Factor ( $G_h$ ):	1.00	--
Shielding Factor ( $K_a$ ):	0.90	--
Velocity Pressure ( $q_z$ ):	45.50	psf

ICE PARAMETERS		
Design Ice Wind Speed:	50	mph
Design Ice Thickness ( $t_i$ ):	1.50	in
Importance Factor ( $I_i$ ):	1.00	--
Ice Velocity Pressure ( $q_{zi}$ ):	45.50	psf
Mount Ice Thickness ( $t_{iz}$ ):	1.72	in

WIND STRUCTURE CALCULATIONS		
Flat Member Pressure:	81.90	psf
Round Member Pressure:	49.14	psf
Ice Wind Pressure:	7.30	psf

SEISMIC PARAMETERS		
Importance Factor ( $I_e$ ):	1.00	--
Short Period Accel. ( $S_s$ ):	0.186	g
1 Second Accel. ( $S_1$ ):	0.064	g
Short Period Des. ( $S_{DS}$ ):	0.20	g
1 Second Des. ( $S_{D1}$ ):	0.10	g
Short Period Coeff. ( $F_a$ ):	1.60	--
1 Second Coeff. ( $F_v$ ):	2.40	--
Response Coefficient ( $C_s$ ):	0.10	--
Amplification Factor ( $A_s$ ):	1.20	--

## LOAD COMBINATIONS [LRFD]

#	Description
1	1.4DL
2	1.2DL + 1WL 0 AZI
3	1.2DL + 1WL 30 AZI
4	1.2DL + 1WL 45 AZI
5	1.2DL + 1WL 60 AZI
6	1.2DL + 1WL 90 AZI
7	1.2DL + 1WL 120 AZI
8	1.2DL + 1WL 135 AZI
9	1.2DL + 1WL 150 AZI
10	1.2DL + 1WL 180 AZI
11	1.2DL + 1WL 210 AZI
12	1.2DL + 1WL 225 AZI
13	1.2DL + 1WL 240 AZI
14	1.2DL + 1WL 270 AZI
15	1.2DL + 1WL 300 AZI
16	1.2DL + 1WL 315 AZI
17	1.2DL + 1WL 330 AZI
18	0.9DL + 1WL 0 AZI
19	0.9DL + 1WL 30 AZI
20	0.9DL + 1WL 45 AZI
21	0.9DL + 1WL 60 AZI
22	0.9DL + 1WL 90 AZI
23	0.9DL + 1WL 120 AZI
24	0.9DL + 1WL 135 AZI
25	0.9DL + 1WL 150 AZI
26	0.9DL + 1WL 180 AZI
27	0.9DL + 1WL 210 AZI
28	0.9DL + 1WL 225 AZI
29	0.9DL + 1WL 240 AZI
30	0.9DL + 1WL 270 AZI
31	0.9DL + 1WL 300 AZI
32	0.9DL + 1WL 315 AZI
33	0.9DL + 1WL 330 AZI
34	1.2DL + 1DLi + 1WLi 0 AZI
35	1.2DL + 1DLi + 1WLi 30 AZI
36	1.2DL + 1DLi + 1WLi 45 AZI
37	1.2DL + 1DLi + 1WLi 60 AZI
38	1.2DL + 1DLi + 1WLi 90 AZI
39	1.2DL + 1DLi + 1WLi 120 AZI
40	1.2DL + 1DLi + 1WLi 135 AZI
41	1.2DL + 1DLi + 1WLi 150 AZI

#	Description
42	1.2DL + 1DLi + 1WLi 180 AZI
43	1.2DL + 1DLi + 1WLi 210 AZI
44	1.2DL + 1DLi + 1WLi 225 AZI
45	1.2DL + 1DLi + 1WLi 240 AZI
46	1.2DL + 1DLi + 1WLi 270 AZI
47	1.2DL + 1DLi + 1WLi 300 AZI
48	1.2DL + 1DLi + 1WLi 315 AZI
49	1.2DL + 1DLi + 1WLi 330 AZI
50	(1.2+0.2Sds) + 1.0E 0 AZI
51	(1.2+0.2Sds) + 1.0E 30 AZI
52	(1.2+0.2Sds) + 1.0E 45 AZI
53	(1.2+0.2Sds) + 1.0E 60 AZI
54	(1.2+0.2Sds) + 1.0E 90 AZI
55	(1.2+0.2Sds) + 1.0E 120 AZI
56	(1.2+0.2Sds) + 1.0E 135 AZI
57	(1.2+0.2Sds) + 1.0E 150 AZI
58	(1.2+0.2Sds) + 1.0E 180 AZI
59	(1.2+0.2Sds) + 1.0E 210 AZI
60	(1.2+0.2Sds) + 1.0E 225 AZI
61	(1.2+0.2Sds) + 1.0E 240 AZI
62	(1.2+0.2Sds) + 1.0E 270 AZI
63	(1.2+0.2Sds) + 1.0E 300 AZI
64	(1.2+0.2Sds) + 1.0E 315 AZI
65	(1.2+0.2Sds) + 1.0E 330 AZI
66	(0.9-0.2Sds) + 1.0E 0 AZI
67	(0.9-0.2Sds) + 1.0E 30 AZI
68	(0.9-0.2Sds) + 1.0E 45 AZI
69	(0.9-0.2Sds) + 1.0E 60 AZI
70	(0.9-0.2Sds) + 1.0E 90 AZI
71	(0.9-0.2Sds) + 1.0E 120 AZI
72	(0.9-0.2Sds) + 1.0E 135 AZI
73	(0.9-0.2Sds) + 1.0E 150 AZI
74	(0.9-0.2Sds) + 1.0E 180 AZI
75	(0.9-0.2Sds) + 1.0E 210 AZI
76	(0.9-0.2Sds) + 1.0E 225 AZI
77	(0.9-0.2Sds) + 1.0E 240 AZI
78	(0.9-0.2Sds) + 1.0E 270 AZI
79	(0.9-0.2Sds) + 1.0E 300 AZI
80	(0.9-0.2Sds) + 1.0E 315 AZI
81	(0.9-0.2Sds) + 1.0E 330 AZI
82-88	1.2D + 1.5 Lv1

#	Description
89	1.2D + 1.5Lm + 1.0Wm 0 AZI - MP1
90	1.2D + 1.5Lm + 1.0Wm 30 AZI - MP1
91	1.2D + 1.5Lm + 1.0Wm 45 AZI - MP1
92	1.2D + 1.5Lm + 1.0Wm 60 AZI - MP1
93	1.2D + 1.5Lm + 1.0Wm 90 AZI - MP1
94	1.2D + 1.5Lm + 1.0Wm 120 AZI - MP1
95	1.2D + 1.5Lm + 1.0Wm 135 AZI - MP1
96	1.2D + 1.5Lm + 1.0Wm 150 AZI - MP1
97	1.2D + 1.5Lm + 1.0Wm 180 AZI - MP1
98	1.2D + 1.5Lm + 1.0Wm 210 AZI - MP1
99	1.2D + 1.5Lm + 1.0Wm 225 AZI - MP1
100	1.2D + 1.5Lm + 1.0Wm 240 AZI - MP1
101	1.2D + 1.5Lm + 1.0Wm 270 AZI - MP1
102	1.2D + 1.5Lm + 1.0Wm 300 AZI - MP1
103	1.2D + 1.5Lm + 1.0Wm 315 AZI - MP1
104	1.2D + 1.5Lm + 1.0Wm 330 AZI - MP1
105	1.2D + 1.5Lm + 1.0Wm 0 AZI - MP2
106	1.2D + 1.5Lm + 1.0Wm 30 AZI - MP2
107	1.2D + 1.5Lm + 1.0Wm 45 AZI - MP2
108	1.2D + 1.5Lm + 1.0Wm 60 AZI - MP2
109	1.2D + 1.5Lm + 1.0Wm 90 AZI - MP2
110	1.2D + 1.5Lm + 1.0Wm 120 AZI - MP2
111	1.2D + 1.5Lm + 1.0Wm 135 AZI - MP2
112	1.2D + 1.5Lm + 1.0Wm 150 AZI - MP2
113	1.2D + 1.5Lm + 1.0Wm 180 AZI - MP2
114	1.2D + 1.5Lm + 1.0Wm 210 AZI - MP2
115	1.2D + 1.5Lm + 1.0Wm 225 AZI - MP2
116	1.2D + 1.5Lm + 1.0Wm 240 AZI - MP2
117	1.2D + 1.5Lm + 1.0Wm 270 AZI - MP2
118	1.2D + 1.5Lm + 1.0Wm 300 AZI - MP2
119	1.2D + 1.5Lm + 1.0Wm 315 AZI - MP2
120	1.2D + 1.5Lm + 1.0Wm 330 AZI - MP2

#	Description
121	1.2D + 1.5Lm + 1.0Wm 0 AZI - MP3
122	1.2D + 1.5Lm + 1.0Wm 30 AZI - MP3
123	1.2D + 1.5Lm + 1.0Wm 45 AZI - MP3
124	1.2D + 1.5Lm + 1.0Wm 60 AZI - MP3
125	1.2D + 1.5Lm + 1.0Wm 90 AZI - MP3
126	1.2D + 1.5Lm + 1.0Wm 120 AZI - MP3
127	1.2D + 1.5Lm + 1.0Wm 135 AZI - MP3
128	1.2D + 1.5Lm + 1.0Wm 150 AZI - MP3
129	1.2D + 1.5Lm + 1.0Wm 180 AZI - MP3
130	1.2D + 1.5Lm + 1.0Wm 210 AZI - MP3
131	1.2D + 1.5Lm + 1.0Wm 225 AZI - MP3
132	1.2D + 1.5Lm + 1.0Wm 240 AZI - MP3
133	1.2D + 1.5Lm + 1.0Wm 270 AZI - MP3
134	1.2D + 1.5Lm + 1.0Wm 300 AZI - MP3
135	1.2D + 1.5Lm + 1.0Wm 315 AZI - MP3
136	1.2D + 1.5Lm + 1.0Wm 330 AZI - MP3
137	1.2D + 1.5Lm + 1.0Wm 0 AZI - MP4
138	1.2D + 1.5Lm + 1.0Wm 30 AZI - MP4
139	1.2D + 1.5Lm + 1.0Wm 45 AZI - MP4
140	1.2D + 1.5Lm + 1.0Wm 60 AZI - MP4
141	1.2D + 1.5Lm + 1.0Wm 90 AZI - MP4
142	1.2D + 1.5Lm + 1.0Wm 120 AZI - MP4
143	1.2D + 1.5Lm + 1.0Wm 135 AZI - MP4
144	1.2D + 1.5Lm + 1.0Wm 150 AZI - MP4
145	1.2D + 1.5Lm + 1.0Wm 180 AZI - MP4
146	1.2D + 1.5Lm + 1.0Wm 210 AZI - MP4
147	1.2D + 1.5Lm + 1.0Wm 225 AZI - MP4
148	1.2D + 1.5Lm + 1.0Wm 240 AZI - MP4
149	1.2D + 1.5Lm + 1.0Wm 270 AZI - MP4
150	1.2D + 1.5Lm + 1.0Wm 300 AZI - MP4
151	1.2D + 1.5Lm + 1.0Wm 315 AZI - MP4
152	1.2D + 1.5Lm + 1.0Wm 330 AZI - MP4

\*This page shows an example of maintenance loads for (4) pipes, the number of mount pipe LCs may vary per site

## EQUIPMENT LOADING

[illegible]

## EQUIPMENT LOADING [CONT.]

<i>Appurtenance Name/Location</i>	<i>Qty.</i>	<i>Elevation [ft]</i>	<i>--</i>	<i>EPA<sub>N</sub> (ft<sup>2</sup>)</i>	<i>EPA<sub>T</sub> (ft<sup>2</sup>)</i>	<i>Weight (lbs)</i>
			No Ice			
--	--	--	w/ Ice			
			No Ice			
--	--	--	w/ Ice			
			No Ice			
--	--	--	w/ Ice			
			No Ice			
--	--	--	w/ Ice			
			No Ice			
--	--	--	w/ Ice			
			No Ice			
--	--	--	w/ Ice			
			No Ice			
--	--	--	w/ Ice			
			No Ice			
--	--	--	w/ Ice			
			No Ice			
--	--	--	w/ Ice			
			No Ice			
--	--	--	w/ Ice			
			No Ice			
--	--	--	w/ Ice			
			No Ice			
--	--	--	w/ Ice			
			No Ice			
--	--	--	w/ Ice			
			No Ice			
--	--	--	w/ Ice			

## EQUIPMENT WIND CALCULATIONS

[illegible]

## EQUIPMENT LATERAL WIND FORCE CALCULATIONS

[illegible]

## EQUIPMENT LATERAL WIND FORCE CALCULATIONS [CONT.]

<i>Appurtenance Name</i>	<i>Qty.</i>	<i>--</i>	<i>0° 180°</i>	<i>30° 210°</i>	<i>60° 240°</i>	<i>90° 270°</i>	<i>120° 300°</i>	<i>150° 330°</i>
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						

## EQUIPMENT SEISMIC FORCE CALCULATIONS

[illegible]

**APPENDIX C**  
**SOFTWARE ANALYSIS OUTPUT**

P{ ʌ ʌ ʌ@æʌ^* ʌ }•	
ʌ^* ʌ   ʌ] æʌ * ʌQ & ^{ ^ } ʌQ D	
ŌææʌO[  { } ʌ^ ʌQ ʌ ʌ	ŌææʌQ ʌ^  æʌ }
ʌæ{ ^ ʌ^ æʌQæʌ   ʌ] ŌŌD	Ė
Ō[ ] & ^ ʌ ʌJd ʌ•• ʌO[ ] &	ʌ^ &æʌ * ^  æ
W ʌ ʌO:æʌ ^ ʌʌ^ & ʌ }•N	Ÿ ʌ•
W ʌ ʌO:æʌ ^ ʌʌ^ & ʌ }• ʌ]æN	P[
ŌæʌQæʌ ʌ * ʌ^ æ } ʌ *•N	P[
W ^• ʌ ʌQ   & ʌ^ æ } ʌ *•N	Ÿ ʌ•
T ʌ ʌ ʌOæʌOæ ʌ] æʌ *N	P[
Ō[ ] & ^ ʌ ʌJ^ ʌæʌ ʌ^c	ŮŌŌŮ ŮŌŮ ŮŮVT ŮŮ F
T ʌ ʌ ʌJc ʌ   ʌO[  { }	F
T æ ʌ ʌJc ʌ   ʌO[  { }	

U^a{ aA[ a^	œjOœÆi
U^a{ aAœ^A[^çaa } A D	P[œ] ç^â
OâAœ^A^ a @N	ÿ^•
ÖaY	ÆG
ÖaZ	ÆG
VAYG^&D	P[œ] ç^â
VAZG^&D	P[œ] ç^â
ÜAY	H
ÜAZ	H
ÖœÖc] EY	Êi
ÖœÖc] EZ	Êi
ÜÖF	F
ÜÖÜ	F
ÜF	F
VSA^&D	i
Üa\ Aœ	q\Aœ
Ö\äcAœ	Uœ@i
U{ Å	F
U{ Å	F
ÖâZ	F
ÖâY	F
Ü@Å	F
Ü@Å	F

[illegible]

	Ššš\	ÖÅ•š	ÖÅ•š	P~	V@{ (AÖÖÄDÖ)•š ŽĐaHá	Ÿa až•š	Ø ž•š
F	ŒÍHÁUŒ:H	GÍ€	FFHÎ	È	ÊÍ	ÊJ	H€€€
G	ŒÍHÁUŒ:Í	GÍ€	FFHÎ	È	ÊÍ	ÊJ	Í€€€

	S̃a	U@^	V ^	Ö•a Äc	Ta æ	Ö•a ÄÖÄ G Q•Ää	láo:Ää	láo:Ää	Rä ä	
F	Î Ê Ä Ç È Å Ü æ	Î Ê Ä Ç È Å Ü æ	Ó æ	Ü Ö Ö	œ Î Æ Ö: È	V  æ	œ Ê	œ G	Î È	Ê
G	Š G Ç H	Š G Ç H	Ó æ	ù à * ^	œ Î Æ Ö: È	V  æ	Ê G	œ F	œ F	œ J
H	Ú Ö Ö H È	Ú Ö Ö H È	Ó æ	Ú à ^	œ Î Ö: Ö	V  æ	œ	Î È G	Î È G	J È
I	Ô Ý Í	Ô Ý Í	Ó æ	Ö @ } ^	œ Î Æ Ö: È	V  æ	F È	œ F	F È	œ H
Í	Ú Ö Ö G È	Ú Ö Ö G È	Ó æ	Ú à ^	œ Î Ö: Ö	V  æ	F È G	Ê G	Ê G	F È
Î	Š È Ä Ý È Î Ä Ç Ä	Š È Ä Ý È Î Ä Ç Ä	Ó æ	ù à * ^	œ Î Æ Ö: È	V  æ	œ È	Î È J	F È È	œ Í

$$\dot{U} \alpha^* \wedge \dot{A} H$$









[illegible][illegible]

R ā c                      Ý Ā á                      Š Ő                      Ÿ Ā á                      Š Ő                      Z Ā á                      Š Ő                      T Ý Ā á Ě á                      Š Ő                      T Ÿ Ā á Ě á                      Š Ő                      T Z Ā á Ě á                      Š Ő

F	ƆG	{ æ	FÍHĚĬJ	H	JHĚĬH	œ	FĬĚĬĬ	HJ	ĬĬĬH	HĚ	œ	ĬĬĬ	HĚ	FĬĚĬJ	FJ
G		{ ā	ĚÍĜĚĬJ	Ĝ	ĚHĚĜG	FG	JĚĬH	HĚ	ĚĬĚĚĬH	HĬ	ĚĬĬĚĬJ	FG	ĚĬĚĚĬ	Ĝ	
H	ƆF	{ æ	FĬĬJĚĬ	FĬ	JĬĬĚFĬ	Ĭ	FĬĚĚĚ	ĬĬ	HĬĬĚĬ	ĬĬ	œ	ĚĬĬ	FJ	FĬĚĚFĬ	J
I		{ ā	ĚĬĬĬĚĬ	Ĝ	ĚĬJĚFH	HG	FĚĚĬĬ	ĜĚ	ĚĚĬĬ	ĜĚ	ĚĬĬĚĬĬ	JĬ	ĚĬĚĚĬH	HH	
Í	ƆFH	{ æ	ĬĚĚJĬ	FĬ	FĬĚĚĬ	Ĭ	FĬĬĚĬ	HĬ	ĬĚĚJĬ	FĬ	HĬĚĚFG	HĬ	FĬĬĚĬH	HĚ	
Î		{ ā	ĚFĬĚJF	FĚ	ĚĬĚĚĬĬ	HĚ	ĬĬĚĬF	Ĝ	ĚĬĚĬĬ	FĬĜ	ĚĬĚJĜ	Ĝ	ĚĬĬJĚĬH	Ĭ	
Ï	V[æK	{ æ	HĚĚĚFG	G	ĜĬĬĚĬF	Ĭ	ĬHĬĚĚ	ĬH							
Ì		{ ā	ĚĚĚĚFG	FĚ	ĜĬĬĚĬF	HĚ	FĬĬĚĬJ	ĬĬ							

## T{ à^ ù@^ Ôí à^Á@&amp; Š &amp;ž á Šô ù@#Á@&amp; Š ħħħħ ħúħ ħúħ ħĕħ ħĕħ ħħħ ħħħ ò~}

[illegible]



**APPENDIX D**  
**ADDITIONAL CALCUATIONS**

**BOLT TOOL 1.5.2**

Project Data	
Job Code:	189031
Carrier Site ID:	BOHVN00014A
Carrier Site Name:	CT-CCI-T-826768


Code	
Design Standard:	TIA-222-H
Slip Check:	No
Pretension Standard:	AISC

Bolt Properties		
Connection Type:	Bolt	
Diameter:	0.625	in
Grade:	A325	--
Yield Strength (Fy):	92	ksi
Ultimate Strength (Fu):	120	ksi
Number of Bolts:	4	--
Threads Included:	Yes	--
Double Shear:	No	--
Connection Pipe Size:	-	in

Connection Description
Standoff to Collar

Bolt Check*		
Tensile Capacity ( $\phi T_n$ ):	20340.1	lbs
Shear Capacity ( $\phi V_n$ ):	13805.8	lbs
Tension Force ( $T_u$ ):	3968.8	lbs
Shear Force ( $V_u$ ):	470.4	lbs
Tension Usage:	18.6%	--
Shear Usage:	3.2%	--
Interaction:	18.6%	Pass
Controlling Member:	M2	--
Controlling LC:	42	--

\*Rating per TIA-222-H Section 15.5




**APPENDIX E**  
**SUPPLEMENTAL DRAWINGS**


ITEM	PART NO.	DESCRIPTION	QTY.	WEIGHT	NOTE NO.
1	MTC3006SB	STEEL BUNDLE FOR SNUB NOSE PLATFORM	1	402.64 LBS	
2	MCPK8CSB	PIPE STEEL BUNDLE FOR MC-PK8-C	1	464.27 LBS	
3	MCPK8CHWK	HARDWARE KIT FOR MC-PK8-C	1	543.22 LBS	




REVISIONS				
REV.	ECN	DESCRIPTION	BY	DATE
A		INITIAL RELEASE	DRR	12/27/11
B	8000005979	CHANGE NOSE CORNER BRKT, ADD GUB-4240	MSM	11/25/14
C	8000007579	NEW RINGMOUNT WELDMNT DESIGN	RJC	04/07/15

FOR BOM ENTRY ONLY




NOTES:  
1. CUSTOMER ASSEMBLY SHEETS 2-3.

These drawings and specifications are the proprietary property of ANDREW CORPORATION and may be used only for the specific purpose authorized in writing by Andrew Corporation.			DRAWN BY: MSM	SHEET: 1 of 3	PART NUMBER: MC-PK8-C
ALL DIMENSIONS ARE IN INCHES U.S.S. TOLERANCES UNLESS OTHERWISE SPECIFIED: .X = ± .12 .XX = ± .06 .XXX = ± .03  ANGLES ±2° FRACTIONS ±1/32  REMOVE BURRS AND BREAK EDGES .005  DO NOT SCALE THIS PRINT			CHECKED BY: TP	SCALE: NTS	DESCRIPTION: LOW PROFILE PLATFORM KIT 8' FACE
			DATE: 10/18/11	MATERIAL: A36, A500	DRAWING TYPE: ASSEMBLY DRAWING
			REVISION: C	FINISH: GALV A123	 WESTCHESTER, IL. 60154 U.S.A.
				WEIGHT: 1410.14 LBS	




ITEM	PART NO.	DESCRIPTION	QTY.	WEIGHT
1	MC-RM1550-3	12" - 50" OD RINGMOUNT	1	230.42 LBS
2	MTC300601	Low Profile Co-Location Platform Snub Nose	3	134.21 LBS
3	MT195801	Corner Weldment Snub Nose Handrail	3	27.10 LBS
4	XA2020.01	CROSS OVER ANGLE	9	2.65 LBS
5	GUB-4356	1/2" X 3-5/8" X 6" GALV U-BOLT	18	0.82 LBS
6	GUB-4355	1/2" X 3-5/8" X 5" GALV U-BOLT	12	0.71 LBS
7	GUB-4240	1/2" X 2-1/2" X 4" GALV U-BOLT	48	0.56 LBS
8	GB-04145	1/2" X 1-1/2" GALV BOLT KIT	12	0.13 LBS
9	GWF-04	1/2" GALV FLAT WASHER	24	0.03 LBS
10	GB-0520A	5/8" X 2" GALV BOLT KIT (A325)	12	0.27 LBS
11	MT54796	3.50" OD X 96" GALV PIPE	3	60.28 LBS
12	MT-651-96	Ø2.375" OD X 96" PIPE	3	29.07 LBS
13	MT-651	2.375" OD x 72" PIPE	9	21.80 LBS
14	MT19617	MT196 Pipe Mount Plate	6	2.49 LBS
15	MT21701	PIPE MOUNT PLATE	9	7.93 LBS


<small>These drawings and specifications are the proprietary property of ANDREW CORPORATION and may be used only for the specific purpose authorized in writing by Andrew Corporation.</small>			
DESIGNED BY: MSM	DATE: 10/18/11	REVISED: C	WEIGHT: 1361.27 LBS
CHECKED BY: TP	DATE: 10/18/11	REVISED: C	WEIGHT: 1361.27 LBS
<small>ALL DIMENSIONS ARE IN INCHES U.S.S. TOLERANCES UNLESS OTHERWISE SPECIFIED:</small> .X = ± .12 ANGLES ±2° .XX = ± .06 FRACTIONS ±1/32 .XXX = ± .03 REMOVE BURRS AND BREAK EDGES .005		<small>PROJECT: 2 of 3</small> <small>SCALE: NTS</small> <small>DESCRIPTION: 25" OD Snub Nose MT-196</small> <small>MATERIAL: A36, A53</small> <small>DRAWING TYPE: ASSEMBLY DRAWING</small> <small>FINISH: GALV A123</small> <small>WEIGHT: 1361.27 LBS</small>	
DO NOT SCALE THIS PRINT		 WESTCHESTER, IL. 60154 U.S.A.	

# NOTES:


1. ALL METRIC DIMENSIONS ARE IN BRACKETS.
2. WILL FIT MONOPOLES 15"–38" OD.




**WITH ANTENNAS**



**DETAIL A  
SCALE 1:8**




**DETAIL B  
SCALE 1:8**



**DETAIL C  
SCALE 1:8**

NOTES:  
1. ALL METRIC DIMENSIONS ARE IN BRACKETS.

These drawings and specifications are the proprietary property of ANDREW CORPORATION and may be used only for the specific purpose authorized in writing by Andrew Corporation.		DRAWN BY: <b>MSM</b>	SHEET: 3 of 3	PART NUMBER: <b>MC-PK8-C</b>
ALL DIMENSIONS ARE IN INCHES U.S.S. TOLERANCES UNLESS OTHERWISE SPECIFIED:  .X = ± .12 ANGLES ±1/32 .XX = ± .06 FRACTIONS .XXX = ± .03  REMOVE BURRS AND BREAK EDGES .005	CHECKED BY: <b>TP</b>	SCALE: <b>NTS</b>	DESCRIPTION: <b>25" OD Snub Nose MT-196</b>	
	DATE: <b>10/18/11</b>	MATERIAL: <b>A36, A53</b>	DRAWING TYPE: <b>ASSEMBLY DRAWING</b>	
	REVISION: <b>C</b>	FINISH: <b>GALV A123</b>	 <b>ANDREW</b> ® WESTCHESTER, IL. 60154 U.S.A.	
DO NOT SCALE THIS PRINT		WEIGHT: <b>1361.27 LBS</b>		

# Exhibit F

## **Power Density/RF Emissions Report**



# EBI Consulting

environmental | engineering | due diligence

## RADIO FREQUENCY EMISSIONS ANALYSIS REPORT EVALUATION OF HUMAN EXPOSURE POTENTIAL TO NON-IONIZING EMISSIONS

Dish Wireless Existing Facility

Site ID: BOHVN00014A

826768

171 Town Hill Road  
Plymouth, Connecticut 06786

**August 31, 2021**

**EBI Project Number: 6221004807**

Site Compliance Summary	
Compliance Status:	<b>COMPLIANT</b>
Site total MPE% of FCC general population allowable limit:	<b>26.88%</b>

August 31, 2021

Dish Wireless

Emissions Analysis for Site: BOHVN00014A - 826768

EBI Consulting was directed to analyze the proposed Dish Wireless facility located at **171 Town Hill Road in Plymouth, Connecticut** for the purpose of determining whether the emissions from the Proposed Dish Wireless Antenna Installation located on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter ( $\mu\text{W}/\text{cm}^2$ ). The number of  $\mu\text{W}/\text{cm}^2$  calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits; therefore, it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) – (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general population may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general population would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

Public exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter ( $\mu\text{W}/\text{cm}^2$ ). The general population exposure limits for the 600 MHz and 700 MHz frequency bands are approximately  $400 \mu\text{W}/\text{cm}^2$  and  $467 \mu\text{W}/\text{cm}^2$ , respectively. The general population exposure limit for the 1900 MHz (PCS), 2100 MHz (AWS) and 11 GHz frequency bands is  $1000 \mu\text{W}/\text{cm}^2$ . Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.

Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure.



Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

## CALCULATIONS

Calculations were done for the proposed Dish Wireless Wireless antenna facility located at 171 Town Hill Road in Plymouth, Connecticut using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. Since Dish Wireless is proposing highly focused directional panel antennas, which project most of the emitted energy out toward the horizon, all calculations were performed assuming a lobe representing the maximum gain of the antenna per the antenna manufacturer's supplied specifications, minus 20 dB for directional panel antennas and 20 dB for highly focused parabolic microwave dishes, was focused at the base of the tower. For this report, the sample point is the top of a 6-foot person standing at the base of the tower.

For all calculations, all equipment was calculated using the following assumptions:

- 1) 4 n71 channels (600 MHz Band) were considered for each sector of the proposed installation. These Channels have a transmit power of 30 Watts per Channel.
- 2) 4 n70 channels (PCS Band - 1900 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 40 Watts per Channel.
- 3) 4 n66 channels (AWS Band - 2190 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 40 Watts per Channel.
- 4) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 - Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.
- 5) For the following calculations, the sample point was the top of a 6-foot person standing at the base of the tower. The maximum gain of the antenna per the antenna manufacturer's supplied specifications, minus 20 dB for directional panel antennas and 20 dB for highly focused parabolic microwave dishes, was used in this direction. This value is a very conservative



estimate as gain reductions for these particular antennas are typically much higher in this direction.

- 6) The antennas used in this modeling are the JMA MX08FRO665-20 for the 600 MHz / 1900 MHz / 2190 MHz channel(s) in Sector A, the JMA MX08FRO665-20 for the 600 MHz / 1900 MHz / 2190 MHz channel(s) in Sector B, the JMA MX08FRO665-20 for the 600 MHz / 1900 MHz / 2190 MHz channel(s) in Sector C. This is based on feedback from the carrier with regard to anticipated antenna selection. All Antenna gain values and associated transmit power levels are shown in the Site Inventory and Power Data table below. The maximum gain of the antenna per the antenna manufacturer's supplied specifications, minus 20 dB for directional panel antennas and 20 dB for highly focused parabolic microwave dishes, was used for all calculations. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 7) The antenna mounting height centerline of the proposed antennas is 132 feet above ground level (AGL).
- 8) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.
- 9) All calculations were done with respect to uncontrolled / general population threshold limits.



## Dish Wireless Site Inventory and Power Data

Sector:	A	Sector:	B	Sector:	C
Antenna #:	I	Antenna #:	I	Antenna #:	I
Make / Model:	JMA MX08FRO665-20	Make / Model:	JMA MX08FRO665-20	Make / Model:	JMA MX08FRO665-20
Frequency Bands:	600 MHz / 1900 MHz / 2190 MHz	Frequency Bands:	600 MHz / 1900 MHz / 2190 MHz	Frequency Bands:	600 MHz / 1900 MHz / 2190 MHz
Gain:	17.45 dBd / 22.65 dBd / 22.65 dBd	Gain:	17.45 dBd / 22.65 dBd / 22.65 dBd	Gain:	17.45 dBd / 22.65 dBd / 22.65 dBd
Height (AGL):	132 feet	Height (AGL):	132 feet	Height (AGL):	132 feet
Channel Count:	12	Channel Count:	12	Channel Count:	12
Total TX Power (W):	440 Watts	Total TX Power (W):	440 Watts	Total TX Power (W):	440 Watts
ERP (W):	5,236.31	ERP (W):	5,236.31	ERP (W):	5,236.31
Antenna AI MPE %:	1.49%	Antenna BI MPE %:	1.49%	Antenna CI MPE %:	1.49%



# EBI Consulting

environmental | engineering | due diligence

Site Composite MPE %	
Carrier	MPE %
Dish Wireless (Max at Sector A):	1.49%
Sprint	0.79%
T-Mobile	7.58%
Town	2.28%
Verizon	3.46%
Nextel	0.54%
AT&T	10.74%
Site Total MPE % :	26.88%

Dish Wireless MPE % Per Sector	
Dish Wireless Sector A Total:	1.49%
Dish Wireless Sector B Total:	1.49%
Dish Wireless Sector C Total:	1.49%
Site Total MPE % :	26.88%

Dish Wireless Maximum MPE Power Values (Sector A)							
Dish Wireless Frequency Band / Technology (Sector A)	# Channels	Watts ERP (Per Channel)	Height (feet)	Total Power Density ( $\mu\text{W}/\text{cm}^2$ )	Frequency (MHz)	Allowable MPE ( $\mu\text{W}/\text{cm}^2$ )	Calculated % MPE
Dish Wireless 600 MHz n71	4	223.68	132.0	2.03	600 MHz n71	400	0.51%
Dish Wireless 1900 MHz n70	4	542.70	132.0	4.92	1900 MHz n70	1000	0.49%
Dish Wireless 2190 MHz n66	4	542.70	132.0	4.92	2190 MHz n66	1000	0.49%
						Total:	1.49%

• NOTE: Totals may vary by approximately 0.01% due to summation of remainders in calculations.

## Summary

All calculations performed for this analysis yielded results that were **within** the allowable limits for general population exposure to RF Emissions.

The anticipated maximum composite contributions from the Dish Wireless facility as well as the site composite emissions value with regards to compliance with FCC's allowable limits for general population exposure to RF Emissions are shown here:

Dish Wireless Sector	Power Density Value (%)
Sector A:	1.49%
Sector B:	1.49%
Sector C:	1.49%
Dish Wireless Maximum MPE % (Sector A):	1.49%
Site Total:	26.88%
Site Compliance Status:	<b>COMPLIANT</b>

The anticipated composite MPE value for this site assuming all carriers present is **26.88%** of the allowable FCC established general population limit sampled at the ground level. This is based upon values listed in the Connecticut Siting Council database for existing carrier emissions.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.

# Exhibit G

## **Letter of Authorization**



4545 E River Rd, Suite 320  
West Henrietta, NY 14586

Phone: (585) 445-5896  
Fax: (724) 416-4461  
www.crowncastle.com

### **Crown Castle Letter of Authorization**

#### **CT - CONNECTICUT SITING COUNCIL**

Melanie A. Bachman  
Executive Director  
Connecticut Siting Council  
10 Franklin Square  
New Britain, CT 06051

**Re: Tower Share Application**  
**Crown Castle telecommunications site at:**  
**171 TOWN HILL ROAD, PLYMOUTH, CT 06786**

T-MOBILE USA TOWER LLC ("Crown Castle") hereby authorizes DISH Wireless LLC, including their Agent, to act as our Agent in the processing of all zoning applications, building permits and approvals through the CT - CONNECTICUT SITING COUNCIL for the existing wireless communications site described below:



**Crown Site ID/Name: 826768/PLYMOUTH/RT 6**  
**Customer Site ID: BOHVN00014A/CT-CCI-T-826768**  
**Site Address: 171 Town Hill Road, Plymouth, CT 06786**

Crown Castle

By:  Date: 9/7/2021  
Richard Zajac  
Site Acquisition Specialist

# Exhibit H

## **Recipient Mailings**

 <b>UNITED STATES POSTAL SERVICE®</b>		<b>Click-N-Ship®</b>	
<b>P</b>		<small>usps.com</small> <b>US POSTAGE</b> <small>Flat Rate Env</small> <b>U.S. POSTAGE PAID</b> <small>Click-N-Ship®</small>	
09/21/2021		Mailed from 01566	
<b>PRIORITY MAIL 2-DAY™</b>			
DEBORAH CHASE NORTHEAST SITE SOLUTIONS 420 MAIN ST STE 1 STURBRIDGE MA 01566-1359		Expected Delivery Date: 09/24/21 Re#: DS-826768 <b>0006</b>	
<div style="border: 1px solid black; padding: 5px; text-align: center;"> <b>R013</b> </div>			
SHIP TO: RICH ZAJAC CROWN CASTLE 4545 E RIVER RD STE 320 W HENRIETTA NY 14586-9024			
<div style="text-align: center;"> <b>USPS TRACKING #</b>    <b>9405 5036 9930 0010 7002 72</b> </div>			
Electronic Rate Approved #038555749			

✂ ————— Cut on dotted line. —————

## Instructions



- Each Click-N-Ship® label is unique. Labels are to be used as printed and used only once. DO NOT PHOTO COPY OR ALTER LABEL.
- Place your label so it does not wrap around the edge of the package.
- Adhere your label to the package. A self-adhesive label is recommended. If tape or glue is used, DO NOT TAPE OVER BARCODE. Be sure all edges are secure.
- To mail your package with PC Postage®, you may schedule a Package Pickup online, hand to your letter carrier, take to a Post Office™, or drop in a USPS collection box.
- Mail your package on the "Ship Date" you selected when creating this label.

## Click-N-Ship® Label Record

<b>USPS TRACKING # :</b> <b>9405 5036 9930 0010 7002 72</b>	
Trans. #: 544158090 Print Date: 09/21/2021 Ship Date: 09/21/2021 Expected Delivery Date: 09/24/2021	Priority Mail® Postage: <b>\$7.95</b> Total: <b>\$7.95</b>
<b>From:</b> DEBORAH CHASE NORTHEAST SITE SOLUTIONS 420 MAIN ST STE 1 STURBRIDGE MA 01566-1359	
<b>To:</b> RICH ZAJAC CROWN CASTLE 4545 E RIVER RD STE 320 W HENRIETTA NY 14586-9024	
Re#: DS-826768	
<small>* Retail Pricing Priority Mail rates apply. There is no fee for USPS Tracking® service on Priority Mail service with use of this electronic rate shipping label. Refunds for unused postage paid labels can be requested online 30 days from the print date.</small>	



Thank you for shipping with the United States Postal Service!  
Check the status of your shipment on the USPS Tracking® page at usps.com

 <b>Click-N-Ship®</b>	
<b>P</b>	usps.com <b>US POSTAGE</b> Flat Rate Env \$7.95 9405 5036 9930 0010 7002 89 0059 0000 0010 6786
09/21/2021	Mailed from 01566
<b>PRIORITY MAIL 2-DAY™</b>	
DEBORAH CHASE NORTHEAST SITE SOLUTIONS 420 MAIN ST STE 1 STURBRIDGE MA 01566-1359	Expected Delivery Date: 09/24/21 Re#: DS-826768 <b>0006</b>
SHIP TO: DAVID V MERCHANT MAYOR OF PLYMOUTH 80 MAIN ST TERRYVILLE CT 06786-5107	
<b>USPS TRACKING #</b>  <b>9405 5036 9930 0010 7002 89</b>	
Electronic Rate Approved #038555749	

✂ ————— Cut on dotted line.

## Instructions



- Each Click-N-Ship® label is unique. Labels are to be used as printed and used only once. DO NOT PHOTO COPY OR ALTER LABEL.
- Place your label so it does not wrap around the edge of the package.
- Adhere your label to the package. A self-adhesive label is recommended. If tape or glue is used, DO NOT TAPE OVER BARCODE. Be sure all edges are secure.
- To mail your package with PC Postage®, you may schedule a Package Pickup online, hand to your letter carrier, take to a Post Office™, or drop in a USPS collection box.
- Mail your package on the "Ship Date" you selected when creating this label.

## Click-N-Ship® Label Record

<b>USPS TRACKING # :</b> <b>9405 5036 9930 0010 7002 89</b>	
Trans. #: 544158090 Print Date: 09/21/2021 Ship Date: 09/21/2021 Expected Delivery Date: 09/24/2021	Priority Mail® Postage: <b>\$7.95</b> Total: <b>\$7.95</b>
<b>From:</b> DEBORAH CHASE NORTHEAST SITE SOLUTIONS 420 MAIN ST STE 1 STURBRIDGE MA 01566-1359	
<b>To:</b> DAVID V MERCHANT MAYOR OF PLYMOUTH 80 MAIN ST TERRYVILLE CT 06786-5107	
Re#: DS-826768	
<small>* Retail Pricing Priority Mail rates apply. There is no fee for USPS Tracking® service on Priority Mail service with use of this electronic rate shipping label. Refunds for unused postage paid labels can be requested online 30 days from the print date.</small>	



Thank you for shipping with the United States Postal Service!  
 Check the status of your shipment on the USPS Tracking® page at usps.com

 <b>Click-N-Ship®</b>	
<b>P</b>	usps.com <b>US POSTAGE</b> Flat Rate Env \$7.95 9405 5036 9930 0010 7002 96 0059 0000 0010 6786
09/21/2021	Mailed from 01566
<b>PRIORITY MAIL 2-DAY™</b>	
DEBORAH CHASE NORTHEAST SITE SOLUTIONS 420 MAIN ST STE 1 STURBRIDGE MA 01566-1359	Expected Delivery Date: 09/24/21 Re#: DS-826768 <b>0006</b>
<div style="border: 1px solid black; padding: 5px; text-align: center;"> <b>C002</b> </div>	
SHIP MARGUS T LAAN TO: PLANNING DIRECTOR 80 MAIN ST TOWN HALL-LAND USE OFFICE TERRYVILLE CT 06786-5107	
<b>USPS TRACKING #</b>  <b>9405 5036 9930 0010 7002 96</b>	
Electronic Rate Approved #038555749	



Cut on dotted line.

## Instructions



- Each Click-N-Ship® label is unique. Labels are to be used as printed and used only once. DO NOT PHOTO COPY OR ALTER LABEL.
- Place your label so it does not wrap around the edge of the package.
- Adhere your label to the package. A self-adhesive label is recommended. If tape or glue is used, DO NOT TAPE OVER BARCODE. Be sure all edges are secure.
- To mail your package with PC Postage®, you may schedule a Package Pickup online, hand to your letter carrier, take to a Post Office™, or drop in a USPS collection box.
- Mail your package on the "Ship Date" you selected when creating this label.

## Click-N-Ship® Label Record

<b>USPS TRACKING # :</b> <b>9405 5036 9930 0010 7002 96</b>	
Trans. #: 544158090 Print Date: 09/21/2021 Ship Date: 09/21/2021 Expected Delivery Date: 09/24/2021	Priority Mail® Postage: <b>\$7.95</b> Total: <b>\$7.95</b>
<b>From:</b> DEBORAH CHASE NORTHEAST SITE SOLUTIONS 420 MAIN ST STE 1 STURBRIDGE MA 01566-1359	
<b>To:</b> MARGUS T LAAN PLANNING DIRECTOR 80 MAIN ST TOWN HALL-LAND USE OFFICE TERRYVILLE CT 06786-5107	
Re#: DS-826768	
<small>* Retail Pricing Priority Mail rates apply. There is no fee for USPS Tracking® service on Priority Mail service with use of this electronic rate shipping label. Refunds for unused postage paid labels can be requested online 30 days from the print date.</small>	



Thank you for shipping with the United States Postal Service!  
 Check the status of your shipment on the USPS Tracking® page at usps.com

 <b>Click-N-Ship®</b>	
<b>P</b>	usps.com <b>US POSTAGE</b> Flat Rate Env \$7.95 9405 5036 9930 0010 7003 19 0059 0000 0010 6786
09/21/2021	Mailed from 01566
<b>PRIORITY MAIL 2-DAY™</b>	
DEBORAH CHASE NORTHEAST SITE SOLUTIONS 420 MAIN ST STE 1 STURBRIDGE MA 01566-1359	
Expected Delivery Date: 09/24/21 Re#: DS-826768 <b>0006</b>	
<b>B001</b>	
SHIP TO: TERRYVILLE COUNTRY FAIR INC. PO BOX 72 TERRYVILLE CT 06786-0072	
<b>USPS TRACKING #</b>  <b>9405 5036 9930 0010 7003 19</b>	
Electronic Rate Approved #038555749	

— ✂ — Cut on dotted line.

## Instructions

- Each Click-N-Ship® label is unique. Labels are to be used as printed and used only once. DO NOT PHOTO COPY OR ALTER LABEL.
- Place your label so it does not wrap around the edge of the package.
- Adhere your label to the package. A self-adhesive label is recommended. If tape or glue is used, DO NOT TAPE OVER BARCODE. Be sure all edges are secure.
- To mail your package with PC Postage®, you may schedule a Package Pickup online, hand to your letter carrier, take to a Post Office™, or drop in a USPS collection box.
- Mail your package on the "Ship Date" you selected when creating this label.

## Click-N-Ship® Label Record

<b>USPS TRACKING # :</b> <b>9405 5036 9930 0010 7003 19</b>	
Trans. #: 544158090 Print Date: 09/21/2021 Ship Date: 09/21/2021 Expected Delivery Date: 09/24/2021	Priority Mail® Postage: <b>\$7.95</b> Total: <b>\$7.95</b>
<b>From:</b> DEBORAH CHASE NORTHEAST SITE SOLUTIONS 420 MAIN ST STE 1 STURBRIDGE MA 01566-1359	
<b>To:</b> TERRYVILLE COUNTRY FAIR INC. PO BOX 72 TERRYVILLE CT 06786-0072	
Re#: DS-826768	
<small>* Retail Pricing Priority Mail rates apply. There is no fee for USPS Tracking® service on Priority Mail service with use of this electronic rate shipping label. Refunds for unused postage paid labels can be requested online 30 days from the print date.</small>	



Thank you for shipping with the United States Postal Service!  
 Check the status of your shipment on the USPS Tracking® page at usps.com

826768- Plymouth



FISKDALE  
458 MAIN ST  
FISKDALE, MA 01518-9998  
(800)275-8777

09/23/2021

02:06 PM

Product	Qty	Unit Price	Price
Prepaid Mail	1		\$0.00
Terryville, CT 06786			
Weight: 1 lb 5.00 oz			
Acceptance Date:			
Thu 09/23/2021			
Tracking #:			
9405 5036 9930 0010 7003 19			
Prepaid Mail	1		\$0.00
Terryville, CT 06786			
Weight: 1 lb 5.00 oz			
Acceptance Date:			
Thu 09/23/2021			
Tracking #:			
9405 5036 9930 0010 7002 96			
Prepaid Mail	1		\$0.00
Terryville, CT 06786			
Weight: 1 lb 5.20 oz			
Acceptance Date:			
Thu 09/23/2021			
Tracking #:			
9405 5036 9930 0010 7002 89			
Prepaid Mail	1		\$0.00
West Henrietta, NY 14586			
Weight: 0 lb 2.00 oz			
Acceptance Date:			
Thu 09/23/2021			
Tracking #:			
9405 5036 9930 0010 7002 72			
Grand Total:			\$0.00

Date: **June 06, 2021**



Crown Castle  
2000 Corporate Drive  
Canonsburg, PA 15317  
(724) 416-20000

**Subject:** **Structural Analysis Report**

**Carrier Designation:** **DISH Network Co-Locate**  
**Site Number:** BOHVN00014A  
**Site Name:** CT-CCI-T-826768

**Crown Castle Designation:** **BU Number:** 826768  
**Site Name:** PLYMOUTH/RT 6  
**JDE Job Number:** 645129  
**Work Order Number:** 1966237  
**Order Number:** 553358 Rev. 1

**Engineering Firm Designation:** **Crown Castle Project Number:** 1966237

**Site Data:** **171 Town Hill Road, Plymouth, Litchfield County, CT**  
**Latitude 41° 40' 6.197", Longitude -73° 1' 11.842"**  
**169 Foot - Monopole Tower**

Crown Castle is pleased to submit this "**Structural Analysis Report**" to determine the structural integrity of the above-mentioned tower.

The purpose of the analysis is to determine acceptability of the tower stress level. Based on our analysis we have determined the tower stress level for the structure and foundation, under the following load case, to be:

LC7: Proposed Equipment Configuration


**Sufficient Capacity - 78.5%**

This analysis utilizes an ultimate 3-second gust wind speed of 120 mph as required by the 2018 Connecticut State Building Code. Applicable Standard references and design criteria are listed in Section 2 - "Analysis Criteria".

Structural analysis prepared by: Matthew Hussak

Respectfully submitted by:

Terry P. Styran, P.E.  
Senior Project Engineer



## **TABLE OF CONTENTS**

### **1) INTRODUCTION**

### **2) ANALYSIS CRITERIA**

Table 1 - Proposed Equipment Configuration

Table 2 - Other Considered Equipment

### **3) ANALYSIS PROCEDURE**

Table 3 - Documents Provided

3.1) Analysis Method

3.2) Assumptions

### **4) ANALYSIS RESULTS**

Table 4 - Section Capacity (Summary)

Table 5 - Tower Component Stresses vs. Capacity - LC7

4.1) Recommendations

### **5) APPENDIX A**

tnxTower Output

### **6) APPENDIX B**

Base Level Drawing

### **7) APPENDIX C**

Additional Calculations

## 1) INTRODUCTION

This tower is a 169 ft Monopole tower designed by PIROD MANUFACTURES INC..

## 2) ANALYSIS CRITERIA

<b>TIA-222 Revision:</b>	TIA-222-H
<b>Risk Category:</b>	II
<b>Wind Speed:</b>	120 mph
<b>Exposure Category:</b>	C
<b>Topographic Factor:</b>	1
<b>Ice Thickness:</b>	1.5 in
<b>Wind Speed with Ice:</b>	50 mph
<b>Service Wind Speed:</b>	60 mph

**Table 1 - Proposed Equipment Configuration**

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)
132.0	132.0	3	fujitsu	TA08025-B604	1	1-1/2
		3	fujitsu	TA08025-B605		
		3	jma wireless	MX08FRO665-21 w/ Mount Pipe		
		1	raycap	RDIDC-9181-PF-48		
		1	tower mounts	Commscope MC-PK8-DSH		

**Table 2 - Other Considered Equipment**

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)
164.0	168.0	3	rfi antennas	COL45-70	11 3	7/8 1-5/8
	165.0	3	ericsson	AIR 32 B2A/B66AA w/ Mount Pipe		
		3	ericsson	AIR6449 B41 w/ Mount Pipe		
		3	ericsson	RADIO 4449 B71 B85A_T-MOBILE		
		3	ericsson	RRUS 4415 B25		
		3	rfs celwave	APXVAARR24_43-U-NA20 w/ Mount Pipe		
	164.0	1	tower mounts	Platform Mount [LP 404-1_KCKR]		
155.0	155.0	3	alcatel lucent	1900MHz RRH	4	1-1/4
		3	alcatel lucent	800MHZ RRH		
		3	alcatel lucent	TD-RRH8x20-25		
		3	rfs celwave	APXVSPP18-C-A20 w/ Mount Pipe		
		3	rfs celwave	APXVTM14-C-120 w/ Mount Pipe		
		1	tower mounts	Platform Mount [LP 305-1]		
142.0	142.0	6	antel	LPA-80080/6CF w/ Mount Pipe	8	1-5/8
		3	commscope	SBNHH-1D65B		

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)
		3	commscope	SBNHH-1D65B w/ Mount Pipe		
		2	rfs celwave	DB-T1-6Z-8AB-0Z		
		3	samsung telecommunications	MT6407-77A w/ Mount Pipe		
		3	samsung telecommunications	RFV01U-D1A		
		3	samsung telecommunications	RFV01U-D2A		
		1	tower mounts	Platform Mount [LP 403-1]		
121.0	125.0	1	rfs celwave	201-4	1	1/2
	121.0	1	tower mounts	Side Arm Mount [SO 701-1]		
115.0	115.0	3	cci antennas	DTMABP7819VG12A	12 6 3 2	1-5/8 5/8 3/8 conduit
		6	cci antennas	TPX-070821		
		3	ericsson	RRUS 11		
		3	ericsson	RRUS 12 B2		
		3	ericsson	RRUS 4426 B66		
		3	ericsson	RRUS 4478 B14		
		3	ericsson	RRUS 4478 B5		
		3	ericsson	WCS RRUS-32-B30		
		6	kaelus	DBCT108F1V92-1		
		3	kathrein	80010965		
		3	kmw communications	AM-X-CD-16-65-00T-RET		
		3	powerwave technologies	7770.00		
		3	quintel technology	QS66512-2		
		1	raycap	DC6-48-60-18-8C		
		2	raycap	DC6-48-60-18-8F		
		1	tower mounts	Platform Mount [LP 301-1]		
105.0	105.0	3	rfs celwave	APXV18-206517S-C w/ Mount Pipe	6	1-5/8
74.0	83.0	1	decibel	DB810T3E-XT	1	7/8
	74.0	1	tower mounts	Side Arm Mount [SO 701-1]		

### 3) ANALYSIS PROCEDURE

Table 3 - Documents Provided

Document	Reference	Source
4-GEOTECHNICAL REPORTS	3491991	CCISITES
4-TOWER FOUNDATION DRAWINGS/DESIGN/SPECS	3678682	CCISITES
4-TOWER MANUFACTURER DRAWINGS	3491992	CCISITES

### 3.1) Analysis Method

tnxTower (version 8.0.9.0), a commercially available analysis software package, was used to create a three-dimensional model of the tower and calculate member stresses for various loading cases. Selected output from the analysis is included in Appendix A. When applicable, Crown Castle has calculated and provided the effective area for panel antennas using approved methods following the intent of the TIA-222 standard.

### 3.2) Assumptions

- 1) Tower and structures were maintained in accordance with the TIA-222 Standard.
- 2) The configuration of antennas, transmission cables, mounts and other appurtenances are as specified in Tables 1 and 2 and the referenced drawings.

This analysis may be affected if any assumptions are not valid or have been made in error. Crown Castle should be notified to determine the effect on the structural integrity of the tower.

## 4) ANALYSIS RESULTS

**Table 4 - Section Capacity (Summary)**

Section No.	Elevation (ft)	Component Type	Size	Critical Element	P (K)	SF*P_allow (K)	% Capacity	Pass / Fail
L1	169 - 164.25	Pole	TP26x18x0.25	1	-0.45	1060.11	0.2	Pass
L2	164.25 - 129.75	Pole	TP34.0625x21.5x0.3125	2	-15.10	1976.75	20.6	Pass
L3	129.75 - 96.08	Pole	TP41.75x32.1327x0.375	3	-30.46	2937.41	38.2	Pass
L4	96.08 - 63.25	Pole	TP49.0625x39.8023x0.375	4	-40.29	3460.30	54.9	Pass
L5	63.25 - 31.25	Pole	TP56.125x46.9543x0.375	5	-51.45	3964.20	67.2	Pass
L6	31.25 - 0	Pole	TP62.9375x53.8466x0.375	6	-66.55	4574.01	78.5	Pass
							Summary	
						Pole (L6)	78.5	Pass
						Rating =	78.5	Pass

**Table 5 - Tower Component Stresses vs. Capacity - LC7**

Notes	Component	Elevation (ft)	% Capacity	Pass / Fail
1	Anchor Rods	0	76.1	Pass
1	Base Plate	0	36.9	Pass
1	Base Foundation (Structure)	0	69.3	Pass
1	Base Foundation (Soil Interaction)	0	53.4	Pass

<b>Structure Rating (max from all components) =</b>	<b>78.5%</b>
---	--------------

Notes:

- 1) See additional documentation in "Appendix C – Additional Calculations" for calculations supporting the % capacity consumed.

### 4.1) Recommendations

The tower and its foundation have sufficient capacity to carry the proposed load configuration. No modifications are required at this time.

## **APPENDIX A**

### **TNXTOWER OUTPUT**



## Tower Input Data

The tower is a monopole.

This tower is designed using the TIA-222-H standard.

The following design criteria apply:

- Tower is located in Litchfield County, Connecticut.
- Tower base elevation above sea level: 890.00 ft.
- Basic wind speed of 120 mph.
- Risk Category II.
- Exposure Category C.
- Simplified Topographic Factor Procedure for wind speed-up calculations is used.
- Topographic Category: 1.
- Crest Height: 0.00 ft.
- Nominal ice thickness of 1.5000 in.
- Ice thickness is considered to increase with height.
- Ice density of 56 pcf.
- A wind speed of 50 mph is used in combination with ice.
- Temperature drop of 50 °F.
- Deflections calculated using a wind speed of 60 mph.
- A non-linear (P-delta) analysis was used.
- Pressures are calculated at each section.
- Stress ratio used in pole design is 1.
- Tower analysis based on target reliabilities in accordance with Annex S.
- Load Modification Factors used:  $K_{es}(F_w) = 0.95$ ,  $K_{es}(t_i) = 0.85$ .
- Maximum demand-capacity ratio is: 1.05.
- Local bending stresses due to climbing loads, feed line supports, and appurtenance mounts are not considered.

## Options

Consider Moments - Legs	Distribute Leg Loads As Uniform	Use ASCE 10 X-Brace Ly Rules
Consider Moments - Horizontals	Assume Legs Pinned	Calculate Redundant Bracing Forces
Consider Moments - Diagonals	✓ Assume Rigid Index Plate	Ignore Redundant Members in FEA
Use Moment Magnification	✓ Use Clear Spans For Wind Area	SR Leg Bolts Resist Compression
✓ Use Code Stress Ratios	Use Clear Spans For KL/r	All Leg Panels Have Same Allowable
✓ Use Code Safety Factors - Guys	Retention Guys To Initial Tension	Offset Girt At Foundation
Escalate Ice	✓ Bypass Mast Stability Checks	✓ Consider Feed Line Torque
Always Use Max Kz	✓ Use Azimuth Dish Coefficients	Include Angle Block Shear Check
Use Special Wind Profile	✓ Project Wind Area of Appurt.	Use TIA-222-H Bracing Resist.
Include Bolts In Member Capacity	Autocalc Torque Arm Areas	Exemption
Leg Bolts Are At Top Of Section	Add IBC .6D+W Combination	Use TIA-222-H Tension Splice
Secondary Horizontal Braces Leg	✓ Sort Capacity Reports By Component	Exemption
Use Diamond Inner Bracing (4 Sided)	Triangulate Diamond Inner Bracing	
SR Members Have Cut Ends	Treat Feed Line Bundles As Cylinder	
SR Members Are Concentric	Ignore KL/ry For 60 Deg. Angle Legs	

### Poles

- ✓ Include Shear-Torsion Interaction
- Always Use Sub-Critical Flow
- Use Top Mounted Sockets
- Pole Without Linear Attachments
- Pole With Shroud Or No
- Appurtenances
- Outside and Inside Corner Radii Are Known

## Tapered Pole Section Geometry

Section	Elevation ft	Section Length ft	Splice Length ft	Number of Sides	Top Diameter in	Bottom Diameter in	Wall Thickness in	Bend Radius in	Pole Grade
L1	169.00-164.25	4.75	2.38	18	18.0000	26.0000	0.2500	1.0000	A572-65 (65 ksi)
L2	164.25-129.75	36.88	3.83	18	21.5000	34.0625	0.3125	1.2500	A572-65 (65 ksi)
L3	129.75-96.08	37.50	4.67	18	32.1327	41.7500	0.3750	1.5000	A572-65 (65 ksi)
L4	96.08-63.25	37.50	5.50	18	39.8023	49.0625	0.3750	1.5000	A572-65 (65 ksi)
L5	63.25-31.25	37.50	6.25	18	46.9543	56.1250	0.3750	1.5000	A572-65 (65 ksi)
L6	31.25-0.00	37.50		18	53.8466	62.9375	0.3750	1.5000	A572-65 (65 ksi)

### Tapered Pole Properties

Section	Tip Dia. in	Area in <sup>2</sup>	I in <sup>4</sup>	r in	C in	I/C in <sup>3</sup>	J in <sup>4</sup>	It/Q in <sup>2</sup>	w in	w/t
L1	18.2391	14.0846	560.6340	6.3012	9.1440	61.3117	1122.0058	7.0437	2.7280	10.912
	26.3625	20.4326	1711.6544	9.1412	13.2080	129.5922	3425.5610	10.2183	4.1360	16.544
L2	22.6051	21.0154	1191.8828	7.5216	10.9220	109.1268	2385.3338	10.5097	3.2340	10.349
	34.5398	33.4758	4817.4335	11.9812	17.3038	278.4040	9641.2058	16.7411	5.4450	17.424
L3	33.5680	37.7996	4816.4038	11.2740	16.3234	295.0611	9639.1451	18.9034	4.9954	13.321
	42.3362	49.2466	10650.982	14.6881	21.2090	502.1916	21315.979	24.6280	6.6880	17.835
L4	41.5295	46.9284	9216.5336	13.9967	20.2196	455.8222	18445.194	23.4686	6.3452	16.921
	49.7615	57.9503	17355.137	17.2841	24.9238	696.3293	34733.111	28.9807	7.9750	21.267
L5	48.9866	55.4411	15196.922	16.5357	23.8528	637.1126	30413.842	27.7258	7.6040	20.277
	56.9330	66.3564	26056.150	19.7913	28.5115	913.8821	52146.586	33.1845	9.2180	24.581
L6	56.1579	63.6445	22990.273	18.9824	27.3541	840.4705	46010.797	31.8283	8.8170	23.512
	63.8506	74.4650	36822.894	22.2097	31.9722	1151.7142	73694.241	37.2396	10.4170	27.779

Tower Elevation ft	Gusset Area (per face) ft <sup>2</sup>	Gusset Thickness in	Gusset Grade	Adjust. Factor A <sub>r</sub>	Adjust. Factor A <sub>r</sub>	Weight Mult.	Double Angle Stitch Bolt Spacing Diagonals in	Double Angle Stitch Bolt Spacing Horizontal in	Double Angle Stitch Bolt Spacing Redundants in
L1 169.00- 164.25				1	1	1			
L2 164.25- 129.75				1	1	1			
L3 129.75- 96.08				1	1	1			
L4 96.08- 63.25				1	1	1			
L5 63.25- 31.25				1	1	1			
L6 31.25-0.00				1	1	1			

### Feed Line/Linear Appurtenances - Entered As Round Or Flat

Description	Sector	Exclude From Torque Calculation	Component Type	Placement ft	Total Number	Number Per Row	Start/End Position	Width or Diameter in	Perimeter r in	Weight plf
-------------	--------	--	-------------------	-----------------	-----------------	-------------------	-----------------------	----------------------------	----------------------	---------------

Description	Sector	Exclude From Torque Calculation	Component Type	Placement ft	Total Number	Number Per Row	Start/End Position	Width or Diameter in	Perimeter in	Weight plf
Safety Line 3/8	A	No	Surface Ar (CaAa)	169.00 - 0.00	1	1	-0.500 -0.500	0.3750		0.22
PiRod Ladder	A	No	Surface Af (CaAa)	169.00 - 0.00	1	1	-0.500 -0.500	0.5400	1.6965	2.00
***										
CU12PSM9P6XXX(1-1/2)	B	No	Surface Ar (CaAa)	132.00 - 0.00	1	1	-0.450 -0.425	1.6000		2.35
***										
LDF4-50A(1/2)	A	No	Surface Ar (CaAa)	121.00 - 0.00	1	1	-0.210 -0.200	0.6300		0.15
***										
LDF7-50A(1-5/8)	A	No	Surface Ar (CaAa)	115.00 - 0.00	12	6	0.115 0.300	1.9800		0.82
2" Flexible Conduit	A	No	Surface Ar (CaAa)	115.00 - 0.00	2	1	0.310 0.340	2.0000		0.34
***										
LDF7-50A(1-5/8)	B	No	Surface Ar (CaAa)	105.00 - 0.00	6	6	-0.250 -0.060	1.9800		0.82
***										
LDF5-50A(7/8)	A	No	Surface Ar (CaAa)	74.00 - 0.00	1	1	0.000 0.010	1.0900		0.33
*****										

### Feed Line/Linear Appurtenances - Entered As Area

Description	Face or Leg	Allow Shield	Exclude From Torque Calculation	Component Type	Placement ft	Total Number		C <sub>A</sub> A <sub>A</sub> ft <sup>2</sup> /ft	Weight plf
***									
810921-701(7/8)	C	No	No	Inside Pole	164.00 - 0.00	7	No Ice 1/2" Ice 1" Ice 2" Ice	0.00 0.00 0.00 0.00	0.34 0.34 0.34 0.34
HCS 6X12 4AWG(1-5/8)	C	No	No	Inside Pole	164.00 - 0.00	3	No Ice 1/2" Ice 1" Ice 2" Ice	0.00 0.00 0.00 0.00	2.40 2.40 2.40 2.40
***									
HB114-1-08U4-M6F(1-1/4)	C	No	No	Inside Pole	155.00 - 0.00	3	No Ice 1/2" Ice 1" Ice 2" Ice	0.00 0.00 0.00 0.00	1.30 1.30 1.30 1.30
HB114-21U3M12-XXXF(1-1/4)	C	No	No	Inside Pole	155.00 - 0.00	1	No Ice 1/2" Ice 1" Ice 2" Ice	0.00 0.00 0.00 0.00	1.22 1.22 1.22 1.22
***									
HB158-1-08U8-S8J18(1-5/8)	C	No	No	Inside Pole	142.00 - 0.00	2	No Ice 1/2" Ice 1" Ice 2" Ice	0.00 0.00 0.00 0.00	1.30 1.30 1.30 1.30
LDF7-50A(1-5/8)	C	No	No	Inside Pole	142.00 - 0.00	6	No Ice 1/2" Ice 1" Ice 2" Ice	0.00 0.00 0.00 0.00	0.82 0.82 0.82 0.82
FB-L98B-034-XXX(3/8)	A	No	No	Inside Pole	115.00 - 0.00	1	No Ice 1/2" Ice 1" Ice 2" Ice	0.00 0.00 0.00 0.00	0.06 0.06 0.06 0.06
FB-L98B-034-XXX(3/8)	A	No	No	Inside Pole	115.00 - 0.00	2	No Ice 1/2" Ice 1" Ice 2" Ice	0.00 0.00 0.00 0.00	0.06 0.06 0.06 0.06
WR-VG82ST-	A	No	No	Inside Pole	115.00 - 0.00	4	No Ice	0.00	0.31

Description	Face or Leg	Allow Shield	Exclude From Torque Calculation	Component Type	Placement ft	Total Number	C <sub>A</sub> A <sub>A</sub> ft <sup>2</sup> /ft	Weight plf
BRDA(5/8)						1/2" Ice	0.00	0.31
						1" Ice	0.00	0.31
						2" Ice	0.00	0.31
WR-VG82ST- BRDA(5/8)	A	No	No	Inside Pole	115.00 - 0.00	2	No Ice	0.00
						1/2" Ice	0.00	0.31
						1" Ice	0.00	0.31
						2" Ice	0.00	0.31
*****								

### Feed Line/Linear Appurtenances Section Areas

Tower Section n	Tower Elevation ft	Face	A <sub>R</sub> ft <sup>2</sup>	A <sub>F</sub> ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> In Face ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> Out Face ft <sup>2</sup>	Weight K
L1	169.00-164.25	A	0.000	0.000	0.606	0.000	0.01
		B	0.000	0.000	0.000	0.000	0.00
		C	0.000	0.000	0.000	0.000	0.00
L2	164.25-129.75	A	0.000	0.000	4.399	0.000	0.08
		B	0.000	0.000	0.360	0.000	0.01
		C	0.000	0.000	0.000	0.000	0.55
L3	129.75-96.08	A	0.000	0.000	32.124	0.000	0.32
		B	0.000	0.000	15.984	0.000	0.12
		C	0.000	0.000	0.000	0.000	0.75
L4	96.08-63.25	A	0.000	0.000	52.994	0.000	0.49
		B	0.000	0.000	44.255	0.000	0.24
		C	0.000	0.000	0.000	0.000	0.73
L5	63.25-31.25	A	0.000	0.000	54.000	0.000	0.49
		B	0.000	0.000	43.136	0.000	0.23
		C	0.000	0.000	0.000	0.000	0.71
L6	31.25-0.00	A	0.000	0.000	52.734	0.000	0.48
		B	0.000	0.000	42.125	0.000	0.23
		C	0.000	0.000	0.000	0.000	0.69

### Feed Line/Linear Appurtenances Section Areas - With Ice

Tower Section n	Tower Elevation ft	Face or Leg	Ice Thickness in	A <sub>R</sub> ft <sup>2</sup>	A <sub>F</sub> ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> In Face ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> Out Face ft <sup>2</sup>	Weight K
L1	169.00-164.25	A	1.499	0.000	0.000	3.454	0.000	0.05
		B		0.000	0.000	0.000	0.000	0.00
		C		0.000	0.000	0.000	0.000	0.00
L2	164.25-129.75	A	1.479	0.000	0.000	25.085	0.000	0.34
		B		0.000	0.000	1.035	0.000	0.02
		C		0.000	0.000	0.000	0.000	0.55
L3	129.75-96.08	A	1.441	0.000	0.000	77.635	0.000	1.35
		B		0.000	0.000	31.894	0.000	0.48
		C		0.000	0.000	0.000	0.000	0.75
L4	96.08-63.25	A	1.392	0.000	0.000	115.525	0.000	2.05
		B		0.000	0.000	75.297	0.000	1.03
		C		0.000	0.000	0.000	0.000	0.73
L5	63.25-31.25	A	1.321	0.000	0.000	119.181	0.000	2.03
		B		0.000	0.000	72.684	0.000	0.97
		C		0.000	0.000	0.000	0.000	0.71
L6	31.25-0.00	A	1.183	0.000	0.000	113.628	0.000	1.88
		B		0.000	0.000	69.987	0.000	0.91
		C		0.000	0.000	0.000	0.000	0.69

### Feed Line Center of Pressure

Section	Elevation	CP <sub>x</sub>	CP <sub>z</sub>	CP <sub>x</sub> Ice	CP <sub>z</sub> Ice
	ft	in	in	in	in
L1	169.00-164.25	-0.4971	1.0572	-1.5012	2.3869
L2	164.25-129.75	-0.4883	0.9727	-1.5767	2.4086
L3	129.75-96.08	-1.7371	-5.2546	-2.5980	-3.5941
L4	96.08-63.25	-0.5591	-8.7797	-1.7280	-6.5732
L5	63.25-31.25	-0.8365	-9.4110	-2.2487	-7.2494
L6	31.25-0.00	-0.8712	-9.9119	-2.3281	-7.7447

Note: For pole sections, center of pressure calculations do not consider feed line shielding.

### Shielding Factor Ka

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K <sub>a</sub> No Ice	K <sub>a</sub> Ice
L1	1	Safety Line 3/8	164.25 - 169.00	1.0000	1.0000
L1	2	PiRod Ladder	164.25 - 169.00	1.0000	1.0000
L2	1	Safety Line 3/8	129.75 - 164.25	1.0000	1.0000
L2	2	PiRod Ladder	129.75 - 164.25	1.0000	1.0000
L2	13	CU12PSM9P6XXX(1-1/2)	129.75 - 132.00	1.0000	1.0000
L3	1	Safety Line 3/8	96.08 - 129.75	1.0000	1.0000
L3	2	PiRod Ladder	96.08 - 129.75	1.0000	1.0000
L3	13	CU12PSM9P6XXX(1-1/2)	96.08 - 129.75	1.0000	1.0000
L3	15	LDF4-50A(1/2)	96.08 - 121.00	1.0000	1.0000
L3	17	LDF7-50A(1-5/8)	96.08 - 115.00	1.0000	1.0000
L3	18	2" Flexible Conduit	96.08 - 115.00	1.0000	1.0000
L3	24	LDF7-50A(1-5/8)	96.08 - 105.00	1.0000	1.0000
L4	1	Safety Line 3/8	63.25 - 96.08	1.0000	1.0000
L4	2	PiRod Ladder	63.25 - 96.08	1.0000	1.0000
L4	13	CU12PSM9P6XXX(1-1/2)	63.25 - 96.08	1.0000	1.0000
L4	15	LDF4-50A(1/2)	63.25 - 96.08	1.0000	1.0000
L4	17	LDF7-50A(1-5/8)	63.25 - 96.08	1.0000	1.0000
L4	18	2" Flexible Conduit	63.25 - 96.08	1.0000	1.0000
L4	24	LDF7-50A(1-5/8)	63.25 - 96.08	1.0000	1.0000
L4	26	LDF5-50A(7/8)	63.25 - 74.00	1.0000	1.0000
L5	1	Safety Line 3/8	31.25 - 63.25	1.0000	1.0000
L5	2	PiRod Ladder	31.25 - 63.25	1.0000	1.0000
L5	13	CU12PSM9P6XXX(1-1/2)	31.25 -	1.0000	1.0000

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K <sub>a</sub> No Ice	K <sub>a</sub> Ice
L5	15	LDF4-50A(1/2)	63.25 31.25 -	1.0000	1.0000
L5	17	LDF7-50A(1-5/8)	63.25 31.25 -	1.0000	1.0000
L5	18	2" Flexible Conduit	63.25 31.25 -	1.0000	1.0000
L5	24	LDF7-50A(1-5/8)	63.25 31.25 -	1.0000	1.0000
L5	26	LDF5-50A(7/8)	63.25 31.25 -	1.0000	1.0000
L6	1	Safety Line 3/8	0.00 - 31.25	1.0000	1.0000
L6	2	PiRod Ladder	0.00 - 31.25	1.0000	1.0000
L6	13	CU12PSM9P6XXX(1-1/2)	0.00 - 31.25	1.0000	1.0000
L6	15	LDF4-50A(1/2)	0.00 - 31.25	1.0000	1.0000
L6	17	LDF7-50A(1-5/8)	0.00 - 31.25	1.0000	1.0000
L6	18	2" Flexible Conduit	0.00 - 31.25	1.0000	1.0000
L6	24	LDF7-50A(1-5/8)	0.00 - 31.25	1.0000	1.0000
L6	26	LDF5-50A(7/8)	0.00 - 31.25	1.0000	1.0000

### Effective Width of Flat Linear Attachments / Feed Lines

Tower Section	Attachment Record No.	Description	Attachment Segment Elev.	Ratio Calculation Method	Effective Width Ratio
L1	2	PiRod Ladder	164.25 - 169.00	Manual	1.0000
L2	2	PiRod Ladder	129.75 - 164.25	Manual	1.0000
L3	2	PiRod Ladder	96.08 - 129.75	Manual	1.0000
L4	2	PiRod Ladder	63.25 - 96.08	Manual	1.0000
L5	2	PiRod Ladder	31.25 - 63.25	Manual	1.0000
L6	2	PiRod Ladder	0.00 - 31.25	Manual	1.0000

### Discrete Tower Loads

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment °	Placement ft		C <sub>A</sub> A <sub>A</sub> Front ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> Side ft <sup>2</sup>	Weight K
Lightning Rod 5/8" x 4'	C	From Leg	3.00 0.00 2.00	0.0000	169.00	No Ice 1/2" Ice 1" Ice 2" Ice	0.25 0.66 0.97 1.49	0.25 0.66 0.97 1.49	0.03 0.03 0.04 0.06
8' x 3" Mount Pipe	C	From Leg	3.00 0.00 0.00	0.0000	167.00	No Ice 1/2" Ice	2.40 3.19 3.67	2.40 3.19 3.67	0.04 0.06 0.08

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustmen t °	Placement ft		C <sub>A</sub> A <sub>A</sub> Front ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> Side ft <sup>2</sup>	Weight K
						1" Ice	4.68	4.68	0.14
						2" Ice			
***									
APXVAARR24_43-U-NA20 w/ Mount Pipe	A	From Leg	4.00 0.00 1.00	0.0000	164.00	No Ice	14.69	6.87	0.19
						1/2"	15.46	7.55	0.31
						Ice	16.23	8.25	0.46
						1" Ice	17.82	9.67	0.79
						2" Ice			
APXVAARR24_43-U-NA20 w/ Mount Pipe	B	From Leg	4.00 0.00 1.00	0.0000	164.00	No Ice	14.69	6.87	0.19
						1/2"	15.46	7.55	0.31
						Ice	16.23	8.25	0.46
						1" Ice	17.82	9.67	0.79
						2" Ice			
APXVAARR24_43-U-NA20 w/ Mount Pipe	C	From Leg	4.00 0.00 1.00	0.0000	164.00	No Ice	14.69	6.87	0.19
						1/2"	15.46	7.55	0.31
						Ice	16.23	8.25	0.46
						1" Ice	17.82	9.67	0.79
						2" Ice			
AIR6449 B41 w/ Mount Pipe	A	From Leg	4.00 0.00 1.00	0.0000	164.00	No Ice	5.18	2.72	0.12
						1/2"	5.59	3.05	0.16
						Ice	6.01	3.39	0.22
						1" Ice	6.90	4.13	0.34
						2" Ice			
AIR6449 B41 w/ Mount Pipe	B	From Leg	4.00 0.00 1.00	0.0000	164.00	No Ice	5.18	2.72	0.12
						1/2"	5.59	3.05	0.16
						Ice	6.01	3.39	0.22
						1" Ice	6.90	4.13	0.34
						2" Ice			
AIR6449 B41 w/ Mount Pipe	C	From Leg	4.00 0.00 1.00	0.0000	164.00	No Ice	5.18	2.72	0.12
						1/2"	5.59	3.05	0.16
						Ice	6.01	3.39	0.22
						1" Ice	6.90	4.13	0.34
						2" Ice			
AIR 32 B2A/B66AA w/ Mount Pipe	A	From Leg	4.00 0.00 1.00	0.0000	164.00	No Ice	3.76	3.15	0.19
						1/2"	4.12	3.49	0.25
						Ice	4.48	3.84	0.32
						1" Ice	5.24	4.58	0.48
						2" Ice			
AIR 32 B2A/B66AA w/ Mount Pipe	B	From Leg	4.00 0.00 1.00	0.0000	164.00	No Ice	3.76	3.15	0.19
						1/2"	4.12	3.49	0.25
						Ice	4.48	3.84	0.32
						1" Ice	5.24	4.58	0.48
						2" Ice			
AIR 32 B2A/B66AA w/ Mount Pipe	C	From Leg	4.00 0.00 1.00	0.0000	164.00	No Ice	3.76	3.15	0.19
						1/2"	4.12	3.49	0.25
						Ice	4.48	3.84	0.32
						1" Ice	5.24	4.58	0.48
						2" Ice			
RADIO 4449 B71 B85A_T- MOBILE	A	From Leg	4.00 0.00 1.00	0.0000	164.00	No Ice	1.97	1.59	0.07
						1/2"	2.15	1.75	0.09
						Ice	2.33	1.92	0.12
						1" Ice	2.72	2.28	0.17
						2" Ice			
RADIO 4449 B71 B85A_T- MOBILE	B	From Leg	4.00 0.00 1.00	0.0000	164.00	No Ice	1.97	1.59	0.07
						1/2"	2.15	1.75	0.09
						Ice	2.33	1.92	0.12
						1" Ice	2.72	2.28	0.17
						2" Ice			
RADIO 4449 B71 B85A_T- MOBILE	C	From Leg	4.00 0.00 1.00	0.0000	164.00	No Ice	1.97	1.59	0.07
						1/2"	2.15	1.75	0.09
						Ice	2.33	1.92	0.12
						1" Ice	2.72	2.28	0.17
						2" Ice			
RRUS 4415 B25	A	From Leg	4.00 0.00	0.0000	164.00	No Ice	1.64	0.68	0.04
						1/2"	1.80	0.79	0.06

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustmen t °	Placement ft		C <sub>A</sub> A <sub>A</sub> Front ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> Side ft <sup>2</sup>	Weight K
			1.00			Ice	1.97	0.91	0.07
						1" Ice	2.33	1.18	0.11
						2" Ice			
RRUS 4415 B25	B	From Leg	4.00	0.0000	164.00	No Ice	1.64	0.68	0.04
			0.00			1/2"	1.80	0.79	0.06
			1.00			Ice	1.97	0.91	0.07
						1" Ice	2.33	1.18	0.11
						2" Ice			
RRUS 4415 B25	C	From Leg	4.00	0.0000	164.00	No Ice	1.64	0.68	0.04
			0.00			1/2"	1.80	0.79	0.06
			1.00			Ice	1.97	0.91	0.07
						1" Ice	2.33	1.18	0.11
						2" Ice			
Platform Mount [LP 404-1_KCKR]	C	None		0.0000	164.00	No Ice	35.82	35.82	2.32
						1/2"	45.85	45.85	3.02
						Ice	55.76	55.76	3.89
						1" Ice	75.77	75.77	6.14
						2" Ice			
(2) 4' x 2" Pipe Mount	A	From Leg	4.00	0.0000	164.00	No Ice	0.79	0.79	0.03
			0.00			1/2"	1.03	1.03	0.04
			0.00			Ice	1.28	1.28	0.04
						1" Ice	1.81	1.81	0.07
						2" Ice			
(2) 4' x 2" Pipe Mount	B	From Leg	4.00	0.0000	164.00	No Ice	0.79	0.79	0.03
			0.00			1/2"	1.03	1.03	0.04
			0.00			Ice	1.28	1.28	0.04
						1" Ice	1.81	1.81	0.07
						2" Ice			
(2) 4' x 2" Pipe Mount	C	From Leg	4.00	0.0000	164.00	No Ice	0.79	0.79	0.03
			0.00			1/2"	1.03	1.03	0.04
			0.00			Ice	1.28	1.28	0.04
						1" Ice	1.81	1.81	0.07
						2" Ice			
***									
COL45-70	A	From Leg	4.00	0.0000	164.00	No Ice	1.38	1.38	0.01
			0.00			1/2"	2.32	2.32	0.02
			4.00			Ice	3.27	3.27	0.03
						1" Ice	4.82	4.82	0.09
						2" Ice			
COL45-70	A	From Leg	4.00	0.0000	164.00	No Ice	1.38	1.38	0.01
			0.00			1/2"	2.32	2.32	0.02
			4.00			Ice	3.27	3.27	0.03
						1" Ice	4.82	4.82	0.09
						2" Ice			
COL45-70	B	From Leg	4.00	0.0000	164.00	No Ice	1.38	1.38	0.01
			0.00			1/2"	2.32	2.32	0.02
			4.00			Ice	3.27	3.27	0.03
						1" Ice	4.82	4.82	0.09
						2" Ice			
***									
APXVTM14-C-120 w/ Mount Pipe	A	From Leg	4.00	0.0000	155.00	No Ice	4.09	2.86	0.08
			0.00			1/2"	4.48	3.23	0.13
			0.00			Ice	4.88	3.61	0.19
						1" Ice	5.71	4.40	0.33
						2" Ice			
APXVTM14-C-120 w/ Mount Pipe	B	From Leg	4.00	0.0000	155.00	No Ice	4.09	2.86	0.08
			0.00			1/2"	4.48	3.23	0.13
			0.00			Ice	4.88	3.61	0.19
						1" Ice	5.71	4.40	0.33
						2" Ice			
APXVTM14-C-120 w/ Mount Pipe	C	From Leg	4.00	0.0000	155.00	No Ice	4.09	2.86	0.08
			0.00			1/2"	4.48	3.23	0.13
			0.00			Ice	4.88	3.61	0.19
						1" Ice	5.71	4.40	0.33
						2" Ice			

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustmen t °	Placement ft		C <sub>A</sub> A <sub>A</sub> Front ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> Side ft <sup>2</sup>	Weight K
APXVSPP18-C-A20 w/ Mount Pipe	A	From Leg	4.00 0.00 0.00	0.0000	155.00	No Ice 1/2" Ice 1" Ice 2" Ice	4.60 5.05 5.50 6.44	4.01 4.45 4.89 5.82	0.10 0.16 0.23 0.42
APXVSPP18-C-A20 w/ Mount Pipe	B	From Leg	4.00 0.00 0.00	0.0000	155.00	No Ice 1/2" Ice 1" Ice 2" Ice	4.60 5.05 5.50 6.44	4.01 4.45 4.89 5.82	0.10 0.16 0.23 0.42
APXVSPP18-C-A20 w/ Mount Pipe	C	From Leg	4.00 0.00 0.00	0.0000	155.00	No Ice 1/2" Ice 1" Ice 2" Ice	4.60 5.05 5.50 6.44	4.01 4.45 4.89 5.82	0.10 0.16 0.23 0.42
TD-RRH8x20-25	A	From Leg	4.00 0.00 0.00	0.0000	155.00	No Ice 1/2" Ice 1" Ice 2" Ice	4.05 4.30 4.56 5.10	1.53 1.71 1.90 2.30	0.07 0.10 0.13 0.20
TD-RRH8x20-25	B	From Leg	4.00 0.00 0.00	0.0000	155.00	No Ice 1/2" Ice 1" Ice 2" Ice	4.05 4.30 4.56 5.10	1.53 1.71 1.90 2.30	0.07 0.10 0.13 0.20
TD-RRH8x20-25	C	From Leg	4.00 0.00 0.00	0.0000	155.00	No Ice 1/2" Ice 1" Ice 2" Ice	4.05 4.30 4.56 5.10	1.53 1.71 1.90 2.30	0.07 0.10 0.13 0.20
800MHZ RRH	A	From Leg	4.00 0.00 0.00	0.0000	155.00	No Ice 1/2" Ice 1" Ice 2" Ice	2.13 2.32 2.51 2.92	1.77 1.95 2.13 2.51	0.05 0.07 0.10 0.16
800MHZ RRH	B	From Leg	4.00 0.00 0.00	0.0000	155.00	No Ice 1/2" Ice 1" Ice 2" Ice	2.13 2.32 2.51 2.92	1.77 1.95 2.13 2.51	0.05 0.07 0.10 0.16
800MHZ RRH	C	From Leg	4.00 0.00 0.00	0.0000	155.00	No Ice 1/2" Ice 1" Ice 2" Ice	2.13 2.32 2.51 2.92	1.77 1.95 2.13 2.51	0.05 0.07 0.10 0.16
1900MHz RRH	A	From Leg	4.00 0.00 0.00	0.0000	155.00	No Ice 1/2" Ice 1" Ice 2" Ice	2.49 2.70 2.91 3.35	3.26 3.48 3.72 4.21	0.04 0.08 0.11 0.19
1900MHz RRH	B	From Leg	4.00 0.00 0.00	0.0000	155.00	No Ice 1/2" Ice 1" Ice 2" Ice	2.49 2.70 2.91 3.35	3.26 3.48 3.72 4.21	0.04 0.08 0.11 0.19
1900MHz RRH	C	From Leg	4.00 0.00 0.00	0.0000	155.00	No Ice 1/2" Ice 1" Ice 2" Ice	2.49 2.70 2.91 3.35	3.26 3.48 3.72 4.21	0.04 0.08 0.11 0.19
Platform Mount [LP 305-1]	C	None		0.0000	155.00	No Ice 1/2" Ice 1" Ice 2" Ice	18.04 22.04 26.06 34.16	18.04 22.04 26.06 34.16	1.12 1.47 1.88 2.90

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustmen t °	Placement ft		C <sub>A</sub> A <sub>A</sub> Front ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> Side ft <sup>2</sup>	Weight K
6' x 2" Mount Pipe	A	From Leg	4.00 0.00 0.00	0.0000	155.00	No Ice 1/2" Ice 1" Ice 2" Ice	1.43 1.92 2.29 3.06	1.43 1.92 2.29 3.06	0.02 0.03 0.05 0.09
6' x 2" Mount Pipe	B	From Leg	4.00 0.00 0.00	0.0000	155.00	No Ice 1/2" Ice 1" Ice 2" Ice	1.43 1.92 2.29 3.06	1.43 1.92 2.29 3.06	0.02 0.03 0.05 0.09
6' x 2" Mount Pipe	C	From Leg	4.00 0.00 0.00	0.0000	155.00	No Ice 1/2" Ice 1" Ice 2" Ice	1.43 1.92 2.29 3.06	1.43 1.92 2.29 3.06	0.02 0.03 0.05 0.09
***									
MT6407-77A w/ Mount Pipe	A	From Leg	4.00 0.00 0.00	0.0000	142.00	No Ice 1/2" Ice 1" Ice 2" Ice	4.91 5.26 5.61 6.36	2.68 3.14 3.62 4.63	0.10 0.14 0.18 0.29
MT6407-77A w/ Mount Pipe	B	From Leg	4.00 0.00 0.00	0.0000	142.00	No Ice 1/2" Ice 1" Ice 2" Ice	4.91 5.26 5.61 6.36	2.68 3.14 3.62 4.63	0.10 0.14 0.18 0.29
MT6407-77A w/ Mount Pipe	C	From Leg	4.00 0.00 0.00	0.0000	142.00	No Ice 1/2" Ice 1" Ice 2" Ice	4.91 5.26 5.61 6.36	2.68 3.14 3.62 4.63	0.10 0.14 0.18 0.29
(2) LPA-80080/6CF w/ Mount Pipe	A	From Leg	4.00 0.00 0.00	0.0000	142.00	No Ice 1/2" Ice 1" Ice 2" Ice	4.56 5.11 5.61 6.65	10.26 11.43 12.31 14.13	0.05 0.11 0.19 0.36
(2) LPA-80080/6CF w/ Mount Pipe	B	From Leg	4.00 0.00 0.00	0.0000	142.00	No Ice 1/2" Ice 1" Ice 2" Ice	4.56 5.11 5.61 6.65	10.26 11.43 12.31 14.13	0.05 0.11 0.19 0.36
(2) LPA-80080/6CF w/ Mount Pipe	C	From Leg	4.00 0.00 0.00	0.0000	142.00	No Ice 1/2" Ice 1" Ice 2" Ice	4.56 5.11 5.61 6.65	10.26 11.43 12.31 14.13	0.05 0.11 0.19 0.36
SBNHH-1D65B w/ Mount Pipe	A	From Leg	4.00 0.00 0.00	0.0000	142.00	No Ice 1/2" Ice 1" Ice 2" Ice	4.09 4.49 4.89 5.72	3.30 3.68 4.07 4.87	0.07 0.13 0.20 0.39
SBNHH-1D65B w/ Mount Pipe	B	From Leg	4.00 0.00 0.00	0.0000	142.00	No Ice 1/2" Ice 1" Ice 2" Ice	4.09 4.49 4.89 5.72	3.30 3.68 4.07 4.87	0.07 0.13 0.20 0.39
SBNHH-1D65B w/ Mount Pipe	C	From Leg	4.00 0.00 0.00	0.0000	142.00	No Ice 1/2" Ice 1" Ice 2" Ice	4.09 4.49 4.89 5.72	3.30 3.68 4.07 4.87	0.07 0.13 0.20 0.39
SBNHH-1D65B	A	From Leg	4.00 0.00 0.00	0.0000	142.00	No Ice 1/2" Ice 1" Ice	4.16 4.57 4.99 5.85	2.49 2.88 3.27 4.09	0.04 0.09 0.15 0.28

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustmen t °	Placement ft		C <sub>A</sub> A <sub>A</sub> Front ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> Side ft <sup>2</sup>	Weight K
SBNHH-1D65B	B	From Leg	4.00 0.00 0.00	0.0000	142.00	2" Ice No Ice 1/2" Ice 1" Ice	4.16 4.57 4.99 5.85	2.49 2.88 3.27 4.09	0.04 0.09 0.15 0.28
SBNHH-1D65B	C	From Leg	4.00 0.00 0.00	0.0000	142.00	2" Ice No Ice 1/2" Ice 1" Ice	4.16 4.57 4.99 5.85	2.49 2.88 3.27 4.09	0.04 0.09 0.15 0.28
RFV01U-D1A	A	From Leg	4.00 0.00 0.00	0.0000	142.00	2" Ice No Ice 1/2" Ice 1" Ice	1.88 2.05 2.22 2.60	1.25 1.39 1.54 1.86	0.08 0.10 0.12 0.18
RFV01U-D1A	B	From Leg	4.00 0.00 0.00	0.0000	142.00	2" Ice No Ice 1/2" Ice 1" Ice	1.88 2.05 2.22 2.60	1.25 1.39 1.54 1.86	0.08 0.10 0.12 0.18
RFV01U-D1A	C	From Leg	4.00 0.00 0.00	0.0000	142.00	2" Ice No Ice 1/2" Ice 1" Ice	1.88 2.05 2.22 2.60	1.25 1.39 1.54 1.86	0.08 0.10 0.12 0.18
RFV01U-D2A	A	From Leg	4.00 0.00 0.00	0.0000	142.00	2" Ice No Ice 1/2" Ice 1" Ice	1.88 2.05 2.22 2.60	1.01 1.14 1.28 1.59	0.07 0.09 0.11 0.15
RFV01U-D2A	B	From Leg	4.00 0.00 0.00	0.0000	142.00	2" Ice No Ice 1/2" Ice 1" Ice	1.88 2.05 2.22 2.60	1.01 1.14 1.28 1.59	0.07 0.09 0.11 0.15
RFV01U-D2A	C	From Leg	4.00 0.00 0.00	0.0000	142.00	2" Ice No Ice 1/2" Ice 1" Ice	1.88 2.05 2.22 2.60	1.01 1.14 1.28 1.59	0.07 0.09 0.11 0.15
DB-T1-6Z-8AB-0Z	A	From Leg	4.00 0.00 0.00	0.0000	142.00	2" Ice No Ice 1/2" Ice 1" Ice	4.80 5.07 5.35 5.93	2.00 2.19 2.39 2.81	0.04 0.08 0.12 0.21
DB-T1-6Z-8AB-0Z	C	From Leg	4.00 0.00 0.00	0.0000	142.00	2" Ice No Ice 1/2" Ice 1" Ice	4.80 5.07 5.35 5.93	2.00 2.19 2.39 2.81	0.04 0.08 0.12 0.21
Platform Mount [LP 403-1]	C	None		0.0000	142.00	2" Ice No Ice 1/2" Ice 1" Ice	18.94 23.31 27.74 36.77	18.94 23.31 27.74 36.77	1.50 1.90 2.37 3.53
Dual Antenna Mounting Bracket	A	From Leg	4.00 0.00 0.00	0.0000	142.00	2" Ice No Ice 1/2" Ice 1" Ice	0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00	0.07 0.09 0.11 0.15
Dual Antenna Mounting Bracket	B	From Leg	4.00 0.00 0.00	0.0000	142.00	2" Ice No Ice 1/2" Ice 1" Ice	0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00	0.07 0.09 0.11 0.15

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustmen t °	Placement ft		C <sub>A</sub> A <sub>A</sub> Front ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> Side ft <sup>2</sup>	Weight K
Dual Antenna Mounting Bracket	C	From Leg	4.00 0.00 0.00	0.0000	142.00	2" Ice No Ice 1/2" Ice 1" Ice 2" Ice	0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00	0.07 0.09 0.11 0.15
***									
MX08FRO665-21 w/ Mount Pipe	A	From Leg	4.00 0.00 0.00	0.0000	132.00	No Ice 1/2" Ice 1" Ice 2" Ice	8.01 8.52 9.04 10.11	4.23 4.69 5.16 6.12	0.11 0.19 0.29 0.52
MX08FRO665-21 w/ Mount Pipe	B	From Leg	4.00 0.00 0.00	0.0000	132.00	No Ice 1/2" Ice 1" Ice 2" Ice	8.01 8.52 9.04 10.11	4.23 4.69 5.16 6.12	0.11 0.19 0.29 0.52
MX08FRO665-21 w/ Mount Pipe	C	From Leg	4.00 0.00 0.00	0.0000	132.00	No Ice 1/2" Ice 1" Ice 2" Ice	8.01 8.52 9.04 10.11	4.23 4.69 5.16 6.12	0.11 0.19 0.29 0.52
TA08025-B604	A	From Leg	4.00 0.00 0.00	0.0000	132.00	No Ice 1/2" Ice 1" Ice 2" Ice	1.96 2.14 2.32 2.71	0.98 1.11 1.25 1.55	0.06 0.08 0.10 0.15
TA08025-B604	B	From Leg	4.00 0.00 0.00	0.0000	132.00	No Ice 1/2" Ice 1" Ice 2" Ice	1.96 2.14 2.32 2.71	0.98 1.11 1.25 1.55	0.06 0.08 0.10 0.15
TA08025-B604	C	From Leg	4.00 0.00 0.00	0.0000	132.00	No Ice 1/2" Ice 1" Ice 2" Ice	1.96 2.14 2.32 2.71	0.98 1.11 1.25 1.55	0.06 0.08 0.10 0.15
TA08025-B605	A	From Leg	4.00 0.00 0.00	0.0000	132.00	No Ice 1/2" Ice 1" Ice 2" Ice	1.96 2.14 2.32 2.71	1.13 1.27 1.41 1.72	0.08 0.09 0.11 0.16
TA08025-B605	B	From Leg	4.00 0.00 0.00	0.0000	132.00	No Ice 1/2" Ice 1" Ice 2" Ice	1.96 2.14 2.32 2.71	1.13 1.27 1.41 1.72	0.08 0.09 0.11 0.16
TA08025-B605	C	From Leg	4.00 0.00 0.00	0.0000	132.00	No Ice 1/2" Ice 1" Ice 2" Ice	1.96 2.14 2.32 2.71	1.13 1.27 1.41 1.72	0.08 0.09 0.11 0.16
RDIDC-9181-PF-48	C	From Leg	4.00 0.00 0.00	0.0000	132.00	No Ice 1/2" Ice 1" Ice 2" Ice	2.31 2.50 2.70 3.12	1.29 1.45 1.61 1.96	0.02 0.04 0.06 0.12
Commscope MC-PK8-DSH	C	None		0.0000	132.00	No Ice 1/2" Ice 1" Ice 2" Ice	34.24 62.95 91.66 149.08	34.24 62.95 91.66 149.08	1.75 2.10 2.45 3.15
(2) 8' x 2" Mount Pipe	A	From Leg	4.00 0.00 0.00	0.0000	132.00	No Ice 1/2" Ice	1.90 2.73 3.40	1.90 2.73 3.40	0.03 0.04 0.06

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustmen t °	Placement ft		C <sub>A</sub> A <sub>A</sub> Front ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> Side ft <sup>2</sup>	Weight K
						1" Ice	4.40	4.40	0.12
						2" Ice			
(2) 8' x 2" Mount Pipe	B	From Leg	4.00	0.0000	132.00	No Ice	1.90	1.90	0.03
			0.00			1/2"	2.73	2.73	0.04
			0.00			Ice	3.40	3.40	0.06
						1" Ice	4.40	4.40	0.12
						2" Ice			
(2) 8' x 2" Mount Pipe	C	From Leg	4.00	0.0000	132.00	No Ice	1.90	1.90	0.03
			0.00			1/2"	2.73	2.73	0.04
			0.00			Ice	3.40	3.40	0.06
						1" Ice	4.40	4.40	0.12
						2" Ice			
***									
201-4	A	From Leg	3.00	0.0000	121.00	No Ice	1.13	1.13	0.00
			0.00			1/2"	2.00	2.00	0.01
			4.00			Ice	2.90	2.90	0.03
						1" Ice	4.31	4.31	0.08
						2" Ice			
Side Arm Mount [SO 701-1]	A	From Leg	1.50	0.0000	121.00	No Ice	0.85	1.67	0.07
			0.00			1/2"	1.14	2.34	0.08
			0.00			Ice	1.43	3.01	0.09
						1" Ice	2.01	4.35	0.12
						2" Ice			
4' x 2" Pipe Mount	A	From Leg	3.00	0.0000	121.00	No Ice	0.79	0.79	0.03
			0.00			1/2"	1.03	1.03	0.04
			0.00			Ice	1.28	1.28	0.04
						1" Ice	1.81	1.81	0.07
						2" Ice			
***									
7770.00	A	From Leg	4.00	0.0000	115.00	No Ice	5.51	2.93	0.04
			0.00			1/2"	5.87	3.27	0.07
			0.00			Ice	6.23	3.63	0.11
						1" Ice	6.99	4.35	0.20
						2" Ice			
7770.00	B	From Leg	4.00	0.0000	115.00	No Ice	5.51	2.93	0.04
			0.00			1/2"	5.87	3.27	0.07
			0.00			Ice	6.23	3.63	0.11
						1" Ice	6.99	4.35	0.20
						2" Ice			
7770.00	C	From Leg	4.00	0.0000	115.00	No Ice	5.51	2.93	0.04
			0.00			1/2"	5.87	3.27	0.07
			0.00			Ice	6.23	3.63	0.11
						1" Ice	6.99	4.35	0.20
						2" Ice			
AM-X-CD-16-65-00T-RET	A	From Leg	4.00	0.0000	115.00	No Ice	4.69	2.34	0.05
			0.00			1/2"	5.15	2.77	0.10
			0.00			Ice	5.61	3.20	0.15
						1" Ice	6.57	4.10	0.27
						2" Ice			
AM-X-CD-16-65-00T-RET	B	From Leg	4.00	0.0000	115.00	No Ice	4.69	2.34	0.05
			0.00			1/2"	5.15	2.77	0.10
			0.00			Ice	5.61	3.20	0.15
						1" Ice	6.57	4.10	0.27
						2" Ice			
AM-X-CD-16-65-00T-RET	C	From Leg	4.00	0.0000	115.00	No Ice	4.69	2.34	0.05
			0.00			1/2"	5.15	2.77	0.10
			0.00			Ice	5.61	3.20	0.15
						1" Ice	6.57	4.10	0.27
						2" Ice			
80010965	A	From Leg	4.00	0.0000	115.00	No Ice	12.23	4.21	0.11
			0.00			1/2"	13.00	4.88	0.19
			0.00			Ice	13.79	5.57	0.27
						1" Ice	15.41	6.99	0.46
						2" Ice			
80010965	B	From Leg	4.00	0.0000	115.00	No Ice	12.23	4.21	0.11

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustmen t °	Placement ft		C <sub>A</sub> A <sub>A</sub> Front ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> Side ft <sup>2</sup>	Weight K
			0.00			1/2"	13.00	4.88	0.19
			0.00			Ice	13.79	5.57	0.27
						1" Ice	15.41	6.99	0.46
						2" Ice			
80010965	C	From Leg	4.00	0.0000	115.00	No Ice	12.23	4.21	0.11
			0.00			1/2"	13.00	4.88	0.19
			0.00			Ice	13.79	5.57	0.27
						1" Ice	15.41	6.99	0.46
						2" Ice			
QS66512-2	A	From Leg	4.00	0.0000	115.00	No Ice	4.01	3.37	0.11
			0.00			1/2"	4.41	3.76	0.17
			0.00			Ice	4.81	4.15	0.23
						1" Ice	5.65	4.97	0.38
						2" Ice			
QS66512-2	B	From Leg	4.00	0.0000	115.00	No Ice	4.01	3.37	0.11
			0.00			1/2"	4.41	3.76	0.17
			0.00			Ice	4.81	4.15	0.23
						1" Ice	5.65	4.97	0.38
						2" Ice			
QS66512-2	C	From Leg	4.00	0.0000	115.00	No Ice	4.01	3.37	0.11
			0.00			1/2"	4.41	3.76	0.17
			0.00			Ice	4.81	4.15	0.23
						1" Ice	5.65	4.97	0.38
						2" Ice			
(3) DBCT108F1V92-1	A	From Leg	4.00	0.0000	115.00	No Ice	0.32	0.64	0.03
			0.00			1/2"	0.40	0.74	0.03
			0.00			Ice	0.49	0.85	0.04
						1" Ice	0.69	1.09	0.06
						2" Ice			
(2) DBCT108F1V92-1	B	From Leg	4.00	0.0000	115.00	No Ice	0.32	0.64	0.03
			0.00			1/2"	0.40	0.74	0.03
			0.00			Ice	0.49	0.85	0.04
						1" Ice	0.69	1.09	0.06
						2" Ice			
DBCT108F1V92-1	C	From Leg	4.00	0.0000	115.00	No Ice	0.32	0.64	0.03
			0.00			1/2"	0.40	0.74	0.03
			0.00			Ice	0.49	0.85	0.04
						1" Ice	0.69	1.09	0.06
						2" Ice			
RRUS 12 B2	A	From Leg	4.00	0.0000	115.00	No Ice	3.14	1.28	0.05
			0.00			1/2"	3.36	1.43	0.07
			0.00			Ice	3.59	1.60	0.10
						1" Ice	4.07	1.95	0.16
						2" Ice			
RRUS 12 B2	B	From Leg	4.00	0.0000	115.00	No Ice	3.14	1.28	0.05
			0.00			1/2"	3.36	1.43	0.07
			0.00			Ice	3.59	1.60	0.10
						1" Ice	4.07	1.95	0.16
						2" Ice			
RRUS 12 B2	C	From Leg	4.00	0.0000	115.00	No Ice	3.14	1.28	0.05
			0.00			1/2"	3.36	1.43	0.07
			0.00			Ice	3.59	1.60	0.10
						1" Ice	4.07	1.95	0.16
						2" Ice			
DTMABP7819VG12A	A	From Leg	4.00	0.0000	115.00	No Ice	0.98	0.34	0.02
			0.00			1/2"	1.10	0.42	0.03
			0.00			Ice	1.23	0.51	0.04
						1" Ice	1.52	0.71	0.06
						2" Ice			
DTMABP7819VG12A	B	From Leg	4.00	0.0000	115.00	No Ice	0.98	0.34	0.02
			0.00			1/2"	1.10	0.42	0.03
			0.00			Ice	1.23	0.51	0.04
						1" Ice	1.52	0.71	0.06
						2" Ice			
DTMABP7819VG12A	C	From Leg	4.00	0.0000	115.00	No Ice	0.98	0.34	0.02

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustmen t °	Placement ft		C <sub>A</sub> A <sub>A</sub> Front ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> Side ft <sup>2</sup>	Weight K
			0.00			1/2"	1.10	0.42	0.03
			0.00			Ice	1.23	0.51	0.04
						1" Ice	1.52	0.71	0.06
						2" Ice			
RRUS 4478 B5	A	From Leg	4.00	0.0000	115.00	No Ice	1.84	1.06	0.06
			0.00			1/2"	2.01	1.20	0.08
			0.00			Ice	2.19	1.34	0.09
						1" Ice	2.57	1.66	0.14
						2" Ice			
RRUS 4478 B5	B	From Leg	4.00	0.0000	115.00	No Ice	1.84	1.06	0.06
			0.00			1/2"	2.01	1.20	0.08
			0.00			Ice	2.19	1.34	0.09
						1" Ice	2.57	1.66	0.14
						2" Ice			
RRUS 4478 B5	C	From Leg	4.00	0.0000	115.00	No Ice	1.84	1.06	0.06
			0.00			1/2"	2.01	1.20	0.08
			0.00			Ice	2.19	1.34	0.09
						1" Ice	2.57	1.66	0.14
						2" Ice			
RRUS 4478 B14	A	From Leg	4.00	0.0000	115.00	No Ice	1.84	1.06	0.06
			0.00			1/2"	2.01	1.20	0.08
			0.00			Ice	2.19	1.34	0.09
						1" Ice	2.57	1.66	0.14
						2" Ice			
(2) RRUS 4478 B14	C	From Leg	4.00	0.0000	115.00	No Ice	1.84	1.06	0.06
			0.00			1/2"	2.01	1.20	0.08
			0.00			Ice	2.19	1.34	0.09
						1" Ice	2.57	1.66	0.14
						2" Ice			
WCS RRUS-32-B30	A	From Leg	4.00	0.0000	115.00	No Ice	3.31	2.42	0.08
			0.00			1/2"	3.56	2.64	0.10
			0.00			Ice	3.81	2.86	0.14
						1" Ice	4.33	3.32	0.21
						2" Ice			
WCS RRUS-32-B30	B	From Leg	4.00	0.0000	115.00	No Ice	3.31	2.42	0.08
			0.00			1/2"	3.56	2.64	0.10
			0.00			Ice	3.81	2.86	0.14
						1" Ice	4.33	3.32	0.21
						2" Ice			
WCS RRUS-32-B30	C	From Leg	4.00	0.0000	115.00	No Ice	3.31	2.42	0.08
			0.00			1/2"	3.56	2.64	0.10
			0.00			Ice	3.81	2.86	0.14
						1" Ice	4.33	3.32	0.21
						2" Ice			
(2) TPX-070821	A	From Leg	4.00	0.0000	115.00	No Ice	0.47	0.10	0.01
			0.00			1/2"	0.56	0.15	0.01
			0.00			Ice	0.66	0.20	0.02
						1" Ice	0.87	0.33	0.03
						2" Ice			
(2) TPX-070821	B	From Leg	4.00	0.0000	115.00	No Ice	0.47	0.10	0.01
			0.00			1/2"	0.56	0.15	0.01
			0.00			Ice	0.66	0.20	0.02
						1" Ice	0.87	0.33	0.03
						2" Ice			
(2) TPX-070821	C	From Leg	4.00	0.0000	115.00	No Ice	0.47	0.10	0.01
			0.00			1/2"	0.56	0.15	0.01
			0.00			Ice	0.66	0.20	0.02
						1" Ice	0.87	0.33	0.03
						2" Ice			
(2) RRUS 11	B	From Leg	4.00	0.0000	115.00	No Ice	2.78	1.19	0.05
			0.00			1/2"	2.99	1.33	0.07
			0.00			Ice	3.21	1.49	0.09
						1" Ice	3.66	1.83	0.15
						2" Ice			
RRUS 11	C	From Leg	4.00	0.0000	115.00	No Ice	2.78	1.19	0.05

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustmen t °	Placement ft		C <sub>A</sub> A <sub>A</sub> Front ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> Side ft <sup>2</sup>	Weight K
			0.00			1/2"	2.99	1.33	0.07
			0.00			Ice	3.21	1.49	0.09
						1" Ice	3.66	1.83	0.15
						2" Ice			
RRUS 4426 B66	B	From Leg	4.00	0.0000	115.00	No Ice	1.64	0.73	0.05
			0.00			1/2"	1.80	0.84	0.06
			0.00			Ice	1.97	0.97	0.08
						1" Ice	2.33	1.24	0.11
						2" Ice			
(2) RRUS 4426 B66	C	From Leg	4.00	0.0000	115.00	No Ice	1.64	0.73	0.05
			0.00			1/2"	1.80	0.84	0.06
			0.00			Ice	1.97	0.97	0.08
						1" Ice	2.33	1.24	0.11
						2" Ice			
DC6-48-60-18-8F	A	From Leg	4.00	0.0000	115.00	No Ice	1.21	1.21	0.02
			0.00			1/2"	1.89	1.89	0.04
			0.00			Ice	2.11	2.11	0.07
						1" Ice	2.57	2.57	0.13
						2" Ice			
DC6-48-60-18-8F	B	From Leg	4.00	0.0000	115.00	No Ice	1.21	1.21	0.02
			0.00			1/2"	1.89	1.89	0.04
			0.00			Ice	2.11	2.11	0.07
						1" Ice	2.57	2.57	0.13
						2" Ice			
DC6-48-60-18-8C	B	From Leg	4.00	0.0000	115.00	No Ice	1.14	1.14	0.03
			0.00			1/2"	1.79	1.79	0.05
			0.00			Ice	2.00	2.00	0.07
						1" Ice	2.45	2.45	0.13
						2" Ice			
Platform Mount [LP 301-1]	C	None		0.0000	115.00	No Ice	23.81	23.81	1.59
						1/2"	30.24	30.24	2.10
						Ice	36.33	36.33	2.73
						1" Ice	48.05	48.05	4.34
						2" Ice			
4' x 2" Pipe Mount	A	From Leg	1.00	0.0000	115.00	No Ice	0.79	0.79	0.03
			0.00			1/2"	1.03	1.03	0.04
			0.00			Ice	1.28	1.28	0.04
						1" Ice	1.81	1.81	0.07
						2" Ice			
4' x 2" Pipe Mount	B	From Leg	1.00	0.0000	115.00	No Ice	0.79	0.79	0.03
			0.00			1/2"	1.03	1.03	0.04
			0.00			Ice	1.28	1.28	0.04
						1" Ice	1.81	1.81	0.07
						2" Ice			
4' x 2" Pipe Mount	C	From Leg	1.00	0.0000	115.00	No Ice	0.79	0.79	0.03
			0.00			1/2"	1.03	1.03	0.04
			0.00			Ice	1.28	1.28	0.04
						1" Ice	1.81	1.81	0.07
						2" Ice			
***									
APXV18-206517S-C w/ Mount Pipe	A	From Leg	1.00	0.0000	105.00	No Ice	3.79	3.16	0.05
			0.00			1/2"	4.38	3.75	0.09
			0.00			Ice	4.99	4.35	0.15
						1" Ice	6.25	5.59	0.28
						2" Ice			
APXV18-206517S-C w/ Mount Pipe	B	From Leg	1.00	0.0000	105.00	No Ice	3.79	3.16	0.05
			0.00			1/2"	4.38	3.75	0.09
			0.00			Ice	4.99	4.35	0.15
						1" Ice	6.25	5.59	0.28
						2" Ice			
APXV18-206517S-C w/ Mount Pipe	C	From Leg	1.00	0.0000	105.00	No Ice	3.79	3.16	0.05
			0.00			1/2"	4.38	3.75	0.09
			0.00			Ice	4.99	4.35	0.15
						1" Ice	6.25	5.59	0.28
						2" Ice			

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustmen t °	Placement ft		C <sub>A</sub> A <sub>A</sub> Front ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> Side ft <sup>2</sup>	Weight K
***									
DB810T3E-XT	A	From Leg	3.00 0.00 9.00	0.0000	74.00	No Ice 1/2" Ice 1" Ice 2" Ice	4.53 6.07 7.63 10.79	4.53 6.07 7.63 10.79	0.05 0.08 0.12 0.24
Side Arm Mount [SO 701-1]	A	From Leg	1.50 0.00 0.00	0.0000	74.00	No Ice 1/2" Ice 1" Ice 2" Ice	0.85 1.14 1.43 2.01	1.67 2.34 3.01 4.35	0.07 0.08 0.09 0.12
6' x 2" Mount Pipe	A	From Leg	3.00 0.00 2.00	0.0000	74.00	No Ice 1/2" Ice 1" Ice 2" Ice	1.43 1.92 2.29 3.06	1.43 1.92 2.29 3.06	0.02 0.03 0.05 0.09
***									

## Load Combinations

Comb. No.	Description
1	Dead Only
2	1.2 Dead+1.0 Wind 0 deg - No Ice
3	0.9 Dead+1.0 Wind 0 deg - No Ice
4	1.2 Dead+1.0 Wind 30 deg - No Ice
5	0.9 Dead+1.0 Wind 30 deg - No Ice
6	1.2 Dead+1.0 Wind 60 deg - No Ice
7	0.9 Dead+1.0 Wind 60 deg - No Ice
8	1.2 Dead+1.0 Wind 90 deg - No Ice
9	0.9 Dead+1.0 Wind 90 deg - No Ice
10	1.2 Dead+1.0 Wind 120 deg - No Ice
11	0.9 Dead+1.0 Wind 120 deg - No Ice
12	1.2 Dead+1.0 Wind 150 deg - No Ice
13	0.9 Dead+1.0 Wind 150 deg - No Ice
14	1.2 Dead+1.0 Wind 180 deg - No Ice
15	0.9 Dead+1.0 Wind 180 deg - No Ice
16	1.2 Dead+1.0 Wind 210 deg - No Ice
17	0.9 Dead+1.0 Wind 210 deg - No Ice
18	1.2 Dead+1.0 Wind 240 deg - No Ice
19	0.9 Dead+1.0 Wind 240 deg - No Ice
20	1.2 Dead+1.0 Wind 270 deg - No Ice
21	0.9 Dead+1.0 Wind 270 deg - No Ice
22	1.2 Dead+1.0 Wind 300 deg - No Ice
23	0.9 Dead+1.0 Wind 300 deg - No Ice
24	1.2 Dead+1.0 Wind 330 deg - No Ice
25	0.9 Dead+1.0 Wind 330 deg - No Ice
26	1.2 Dead+1.0 Ice+1.0 Temp
27	1.2 Dead+1.0 Wind 0 deg+1.0 Ice+1.0 Temp
28	1.2 Dead+1.0 Wind 30 deg+1.0 Ice+1.0 Temp
29	1.2 Dead+1.0 Wind 60 deg+1.0 Ice+1.0 Temp
30	1.2 Dead+1.0 Wind 90 deg+1.0 Ice+1.0 Temp
31	1.2 Dead+1.0 Wind 120 deg+1.0 Ice+1.0 Temp
32	1.2 Dead+1.0 Wind 150 deg+1.0 Ice+1.0 Temp
33	1.2 Dead+1.0 Wind 180 deg+1.0 Ice+1.0 Temp
34	1.2 Dead+1.0 Wind 210 deg+1.0 Ice+1.0 Temp
35	1.2 Dead+1.0 Wind 240 deg+1.0 Ice+1.0 Temp
36	1.2 Dead+1.0 Wind 270 deg+1.0 Ice+1.0 Temp
37	1.2 Dead+1.0 Wind 300 deg+1.0 Ice+1.0 Temp

Comb. No.	Description
38	1.2 Dead+1.0 Wind 330 deg+1.0 Ice+1.0 Temp
39	Dead+Wind 0 deg - Service
40	Dead+Wind 30 deg - Service
41	Dead+Wind 60 deg - Service
42	Dead+Wind 90 deg - Service
43	Dead+Wind 120 deg - Service
44	Dead+Wind 150 deg - Service
45	Dead+Wind 180 deg - Service
46	Dead+Wind 210 deg - Service
47	Dead+Wind 240 deg - Service
48	Dead+Wind 270 deg - Service
49	Dead+Wind 300 deg - Service
50	Dead+Wind 330 deg - Service

## Maximum Member Forces

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Axial K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
L1	169 - 164.25	Pole	Max Tension	2	0.00	-0.00	-0.00
			Max. Compression	26	-0.52	0.33	-0.18
			Max. Mx	20	-0.28	0.81	-0.07
			Max. My	14	-0.28	0.13	-0.75
			Max. Vy	8	0.31	-0.51	-0.07
			Max. Vx	2	-0.31	0.13	0.58
			Max. Torque	24			0.52
L2	164.25 - 129.75	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-33.08	1.75	0.68
			Max. Mx	20	-15.12	321.85	-0.47
			Max. My	14	-15.12	1.06	-321.58
			Max. Vy	20	-16.20	321.85	-0.47
			Max. Vx	2	-16.25	0.14	321.57
			Max. Torque	16			-0.68
L3	129.75 - 96.08	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-61.61	3.70	1.20
			Max. Mx	20	-30.49	1101.54	-3.03
			Max. My	14	-30.51	4.26	-1098.55
			Max. Vy	20	-29.12	1101.54	-3.03
			Max. Vx	2	-28.95	-1.62	1098.33
			Max. Torque	19			-1.16
L4	96.08 - 63.25	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-76.32	5.85	5.62
			Max. Mx	20	-40.34	2097.30	-4.56
			Max. My	2	-40.36	-3.92	2087.07
			Max. Vy	20	-33.17	2097.30	-4.56
			Max. Vx	2	-32.80	-3.92	2087.07
			Max. Torque	21			-1.99
L5	63.25 - 31.25	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-92.33	8.21	8.80
			Max. Mx	20	-51.49	3188.51	-6.52
			Max. My	2	-51.51	-6.07	3166.01
			Max. Vy	20	-36.50	3188.51	-6.52
			Max. Vx	2	-36.10	-6.07	3166.01
			Max. Torque	21			-1.99
L6	31.25 - 0	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-112.98	11.06	12.71
			Max. Mx	20	-66.55	4622.16	-8.70
			Max. My	2	-66.55	-8.52	4584.91
			Max. Vy	20	-39.72	4622.16	-8.70
			Max. Vx	2	-39.32	-8.52	4584.91
			Max. Torque	21			-1.99

## Maximum Reactions

Location	Condition	Gov. Load Comb.	Vertical K	Horizontal, X K	Horizontal, Z K
Pole	Max. Vert	36	112.98	11.57	-0.02
	Max. H <sub>x</sub>	21	49.93	39.69	-0.08
	Max. H <sub>z</sub>	2	66.57	-0.08	39.29
	Max. M <sub>x</sub>	2	4584.91	-0.08	39.29
	Max. M <sub>z</sub>	8	4615.92	-39.69	0.08
	Max. Torsion	9	1.99	-39.69	0.08
	Min. Vert	17	49.93	19.81	-34.07
	Min. H <sub>x</sub>	9	49.93	-39.69	0.08
	Min. H <sub>z</sub>	15	49.93	0.08	-39.29
	Min. M <sub>x</sub>	14	-4579.04	0.08	-39.29
	Min. M <sub>z</sub>	20	-4622.16	39.69	-0.08
	Min. Torsion	21	-1.99	39.69	-0.08

## Tower Mast Reaction Summary

Load Combination	Vertical K	Shear <sub>x</sub> K	Shear <sub>z</sub> K	Overturning Moment, M <sub>x</sub> kip-ft	Overturning Moment, M <sub>z</sub> kip-ft	Torque kip-ft
Dead Only	55.48	0.00	0.00	-2.37	2.46	0.00
1.2 Dead+1.0 Wind 0 deg - No Ice	66.57	0.08	-39.29	-4584.91	-8.52	-0.53
0.9 Dead+1.0 Wind 0 deg - No Ice	49.93	0.08	-39.29	-4527.79	-9.18	-0.53
1.2 Dead+1.0 Wind 30 deg - No Ice	66.57	19.81	-34.07	-3976.87	-2308.41	-1.45
0.9 Dead+1.0 Wind 30 deg - No Ice	49.93	19.81	-34.07	-3927.21	-2280.80	-1.45
1.2 Dead+1.0 Wind 60 deg - No Ice	66.57	35.81	-20.63	-2361.70	-4088.86	-1.98
0.9 Dead+1.0 Wind 60 deg - No Ice	49.93	35.81	-20.63	-2332.18	-4039.82	-1.99
1.2 Dead+1.0 Wind 90 deg - No Ice	66.57	39.69	-0.08	-14.59	-4615.92	-1.98
0.9 Dead+1.0 Wind 90 deg - No Ice	49.93	39.69	-0.08	-13.68	-4559.99	-1.99
1.2 Dead+1.0 Wind 120 deg - No Ice	66.57	34.15	19.57	2277.97	-3977.31	-1.45
0.9 Dead+1.0 Wind 120 deg - No Ice	49.93	34.15	19.57	2250.67	-3929.18	-1.46
1.2 Dead+1.0 Wind 150 deg - No Ice	66.57	19.67	33.98	3959.37	-2288.26	-0.53
0.9 Dead+1.0 Wind 150 deg - No Ice	49.93	19.67	33.98	3911.37	-2260.91	-0.53
1.2 Dead+1.0 Wind 180 deg - No Ice	66.57	-0.08	39.29	4579.04	14.77	0.53
0.9 Dead+1.0 Wind 180 deg - No Ice	49.93	-0.08	39.29	4523.41	13.80	0.53
1.2 Dead+1.0 Wind 210 deg - No Ice	66.57	-19.81	34.07	3970.97	2314.66	1.45
0.9 Dead+1.0 Wind 210 deg - No Ice	49.93	-19.81	34.07	3922.83	2285.41	1.45
1.2 Dead+1.0 Wind 240 deg - No Ice	66.57	-35.81	20.63	2355.81	4095.09	1.98
0.9 Dead+1.0 Wind 240 deg - No Ice	49.93	-35.81	20.63	2327.81	4044.42	1.99
1.2 Dead+1.0 Wind 270 deg - No Ice	66.57	-39.69	0.08	8.70	4622.16	1.98
0.9 Dead+1.0 Wind 270 deg - No Ice	49.93	-39.69	0.08	9.31	4564.61	1.99
1.2 Dead+1.0 Wind 300 deg - No Ice	66.57	-34.15	-19.57	-2283.86	3983.56	1.45

Load Combination	Vertical K	Shear <sub>x</sub> K	Shear <sub>z</sub> K	Overturning Moment, M <sub>x</sub> kip-ft	Overturning Moment, M <sub>z</sub> kip-ft	Torque kip-ft
0.9 Dead+1.0 Wind 300 deg	49.93	-34.15	-19.57	-2255.04	3933.80	1.46
- No Ice						
1.2 Dead+1.0 Wind 330 deg	66.57	-19.67	-33.98	-3965.27	2294.52	0.53
- No Ice						
0.9 Dead+1.0 Wind 330 deg	49.93	-19.67	-33.98	-3915.75	2265.53	0.53
- No Ice						
1.2 Dead+1.0 Ice+1.0 Temp	112.98	-0.00	-0.00	-12.71	11.06	-0.00
1.2 Dead+1.0 Wind 0	112.98	0.02	-11.51	-1407.38	8.87	-0.07
deg+1.0 Ice+1.0 Temp						
1.2 Dead+1.0 Wind 30	112.98	5.80	-9.98	-1221.74	-691.03	-0.48
deg+1.0 Ice+1.0 Temp						
1.2 Dead+1.0 Wind 60	112.98	10.02	-5.77	-712.17	-1202.76	-0.76
deg+1.0 Ice+1.0 Temp						
1.2 Dead+1.0 Wind 90	112.98	11.57	-0.02	-15.22	-1389.20	-0.83
deg+1.0 Ice+1.0 Temp						
1.2 Dead+1.0 Wind 120	112.98	10.01	5.74	682.35	-1200.43	-0.69
deg+1.0 Ice+1.0 Temp						
1.2 Dead+1.0 Wind 150	112.98	5.77	9.96	1193.63	-686.98	-0.36
deg+1.0 Ice+1.0 Temp						
1.2 Dead+1.0 Wind 180	112.98	-0.02	11.51	1381.61	13.55	0.07
deg+1.0 Ice+1.0 Temp						
1.2 Dead+1.0 Wind 210	112.98	-5.80	9.98	1195.97	713.45	0.48
deg+1.0 Ice+1.0 Temp						
1.2 Dead+1.0 Wind 240	112.98	-10.02	5.77	686.40	1225.19	0.75
deg+1.0 Ice+1.0 Temp						
1.2 Dead+1.0 Wind 270	112.98	-11.57	0.02	-10.54	1411.62	0.83
deg+1.0 Ice+1.0 Temp						
1.2 Dead+1.0 Wind 300	112.98	-10.01	-5.74	-708.11	1222.85	0.69
deg+1.0 Ice+1.0 Temp						
1.2 Dead+1.0 Wind 330	112.98	-5.77	-9.96	-1219.40	709.40	0.36
deg+1.0 Ice+1.0 Temp						
Dead+Wind 0 deg - Service	55.48	0.02	-9.26	-1073.95	-0.13	-0.11
Dead+Wind 30 deg - Service	55.48	4.67	-8.03	-931.76	-537.97	-0.33
Dead+Wind 60 deg - Service	55.48	8.44	-4.86	-554.09	-954.41	-0.46
Dead+Wind 90 deg - Service	55.48	9.35	-0.02	-5.17	-1077.60	-0.47
Dead+Wind 120 deg - Service	55.48	8.05	4.61	530.95	-928.25	-0.35
Dead+Wind 150 deg - Service	55.48	4.63	8.01	924.14	-533.26	-0.14
Dead+Wind 180 deg - Service	55.48	-0.02	9.26	1069.05	5.31	0.11
Dead+Wind 210 deg - Service	55.48	-4.67	8.03	926.86	543.14	0.33
Dead+Wind 240 deg - Service	55.48	-8.44	4.86	549.20	959.58	0.46
Dead+Wind 270 deg - Service	55.48	-9.35	0.02	0.27	1082.77	0.47
Dead+Wind 300 deg - Service	55.48	-8.05	-4.61	-535.84	933.42	0.35
Dead+Wind 330 deg - Service	55.48	-4.63	-8.01	-929.04	538.43	0.14

## Solution Summary

Load Comb.	Sum of Applied Forces			Sum of Reactions			% Error
	PX K	PY K	PZ K	PX K	PY K	PZ K	
1	0.00	-55.48	0.00	0.00	55.48	0.00	0.000%
2	0.08	-66.57	-39.29	-0.08	66.57	39.29	0.000%
3	0.08	-49.93	-39.29	-0.08	49.93	39.29	0.000%
4	19.81	-66.57	-34.07	-19.81	66.57	34.07	0.000%
5	19.81	-49.93	-34.07	-19.81	49.93	34.07	0.000%
6	35.81	-66.57	-20.63	-35.81	66.57	20.63	0.000%
7	35.81	-49.93	-20.63	-35.81	49.93	20.63	0.000%
8	39.69	-66.57	-0.08	-39.69	66.57	0.08	0.000%
9	39.69	-49.93	-0.08	-39.69	49.93	0.08	0.000%

Load Comb.	Sum of Applied Forces			Sum of Reactions			% Error
	PX K	PY K	PZ K	PX K	PY K	PZ K	
10	34.15	-66.57	19.57	-34.15	66.57	-19.57	0.000%
11	34.15	-49.93	19.57	-34.15	49.93	-19.57	0.000%
12	19.67	-66.57	33.98	-19.67	66.57	-33.98	0.000%
13	19.67	-49.93	33.98	-19.67	49.93	-33.98	0.000%
14	-0.08	-66.57	39.29	0.08	66.57	-39.29	0.000%
15	-0.08	-49.93	39.29	0.08	49.93	-39.29	0.000%
16	-19.81	-66.57	34.07	19.81	66.57	-34.07	0.000%
17	-19.81	-49.93	34.07	19.81	49.93	-34.07	0.000%
18	-35.81	-66.57	20.63	35.81	66.57	-20.63	0.000%
19	-35.81	-49.93	20.63	35.81	49.93	-20.63	0.000%
20	-39.69	-66.57	0.08	39.69	66.57	-0.08	0.000%
21	-39.69	-49.93	0.08	39.69	49.93	-0.08	0.000%
22	-34.15	-66.57	-19.57	34.15	66.57	19.57	0.000%
23	-34.15	-49.93	-19.57	34.15	49.93	19.57	0.000%
24	-19.67	-66.57	-33.98	19.67	66.57	33.98	0.000%
25	-19.67	-49.93	-33.98	19.67	49.93	33.98	0.000%
26	0.00	-112.98	0.00	0.00	112.98	0.00	0.000%
27	0.02	-112.98	-11.51	-0.02	112.98	11.51	0.000%
28	5.80	-112.98	-9.98	-5.80	112.98	9.98	0.000%
29	10.02	-112.98	-5.77	-10.02	112.98	5.77	0.000%
30	11.57	-112.98	-0.02	-11.57	112.98	0.02	0.000%
31	10.01	-112.98	5.74	-10.01	112.98	-5.74	0.000%
32	5.77	-112.98	9.96	-5.77	112.98	-9.96	0.000%
33	-0.02	-112.98	11.51	0.02	112.98	-11.51	0.000%
34	-5.80	-112.98	9.98	5.80	112.98	-9.98	0.000%
35	-10.02	-112.98	5.77	10.02	112.98	-5.77	0.000%
36	-11.57	-112.98	0.02	11.57	112.98	-0.02	0.000%
37	-10.01	-112.98	-5.74	10.01	112.98	5.74	0.000%
38	-5.77	-112.98	-9.96	5.77	112.98	9.96	0.000%
39	0.02	-55.48	-9.26	-0.02	55.48	9.26	0.000%
40	4.67	-55.48	-8.03	-4.67	55.48	8.03	0.000%
41	8.44	-55.48	-4.86	-8.44	55.48	4.86	0.000%
42	9.35	-55.48	-0.02	-9.35	55.48	0.02	0.000%
43	8.05	-55.48	4.61	-8.05	55.48	-4.61	0.000%
44	4.63	-55.48	8.01	-4.63	55.48	-8.01	0.000%
45	-0.02	-55.48	9.26	0.02	55.48	-9.26	0.000%
46	-4.67	-55.48	8.03	4.67	55.48	-8.03	0.000%
47	-8.44	-55.48	4.86	8.44	55.48	-4.86	0.000%
48	-9.35	-55.48	0.02	9.35	55.48	-0.02	0.000%
49	-8.05	-55.48	-4.61	8.05	55.48	4.61	0.000%
50	-4.63	-55.48	-8.01	4.63	55.48	8.01	0.000%

## Non-Linear Convergence Results

Load Combination	Converged?	Number of Cycles	Displacement Tolerance	Force Tolerance
1	Yes	4	0.00000001	0.00000001
2	Yes	4	0.00000001	0.00085388
3	Yes	4	0.00000001	0.00041330
4	Yes	6	0.00000001	0.00012110
5	Yes	5	0.00000001	0.00098131
6	Yes	6	0.00000001	0.00012841
7	Yes	6	0.00000001	0.00004371
8	Yes	5	0.00000001	0.00009185
9	Yes	4	0.00000001	0.00099911
10	Yes	6	0.00000001	0.00011981
11	Yes	5	0.00000001	0.00097122
12	Yes	6	0.00000001	0.00012140
13	Yes	5	0.00000001	0.00098497
14	Yes	5	0.00000001	0.00006002
15	Yes	4	0.00000001	0.00061270
16	Yes	6	0.00000001	0.00012490
17	Yes	6	0.00000001	0.00004274
18	Yes	6	0.00000001	0.00012404
19	Yes	6	0.00000001	0.00004206

20	Yes	5	0.00000001	0.00006913
21	Yes	4	0.00000001	0.00073962
22	Yes	6	0.00000001	0.00012314
23	Yes	5	0.00000001	0.00099783
24	Yes	6	0.00000001	0.00012147
25	Yes	5	0.00000001	0.00098410
26	Yes	4	0.00000001	0.00009639
27	Yes	5	0.00000001	0.00092893
28	Yes	6	0.00000001	0.00013710
29	Yes	6	0.00000001	0.00013842
30	Yes	5	0.00000001	0.00091765
31	Yes	6	0.00000001	0.00013429
32	Yes	6	0.00000001	0.00013486
33	Yes	5	0.00000001	0.00091446
34	Yes	6	0.00000001	0.00013833
35	Yes	6	0.00000001	0.00013739
36	Yes	5	0.00000001	0.00093425
37	Yes	6	0.00000001	0.00014024
38	Yes	6	0.00000001	0.00013923
39	Yes	4	0.00000001	0.00014437
40	Yes	4	0.00000001	0.00058681
41	Yes	4	0.00000001	0.00066430
42	Yes	4	0.00000001	0.00015968
43	Yes	4	0.00000001	0.00057907
44	Yes	4	0.00000001	0.00060010
45	Yes	4	0.00000001	0.00014515
46	Yes	4	0.00000001	0.00063710
47	Yes	4	0.00000001	0.00060684
48	Yes	4	0.00000001	0.00015795
49	Yes	4	0.00000001	0.00062758
50	Yes	4	0.00000001	0.00060264

### Maximum Tower Deflections - Service Wind

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
L1	169 - 164.25	23.303	47	1.1048	0.0013
L2	166.625 - 129.75	22.753	47	1.1047	0.0013
L3	133.58 - 96.08	15.319	47	1.0153	0.0009
L4	100.75 - 63.25	8.925	47	0.8207	0.0006
L5	68.75 - 31.25	4.206	47	0.5668	0.0005
L6	37.5 - 0	1.282	47	0.3067	0.0002

### Critical Deflections and Radius of Curvature - Service Wind

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
169.00	Lightning Rod 5/8" x 4'	47	23.303	1.1048	0.0013	75403
167.00	8' x 3" Mount Pipe	47	22.840	1.1047	0.0013	75403
164.00	APXVAARR24_43-U-NA20 w/ Mount Pipe	47	22.146	1.1035	0.0013	75403
155.00	APXVTM14-C-120 w/ Mount Pipe	47	20.078	1.0905	0.0012	30103
142.00	MT6407-77A w/ Mount Pipe	47	17.151	1.0511	0.0010	16149
132.00	MX08FRO665-21 w/ Mount Pipe	47	14.983	1.0078	0.0009	12101
121.00	201-4	47	12.712	0.9505	0.0008	10103
115.00	7770.00	47	11.533	0.9153	0.0007	9277
105.00	APXV18-206517S-C w/ Mount Pipe	47	9.672	0.8505	0.0007	8165
74.00	DB810T3E-XT	47	4.868	0.6105	0.0005	7479

### Maximum Tower Deflections - Design Wind

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
L1	169 - 164.25	99.603	18	4.7261	0.0056
L2	166.625 - 129.75	97.257	18	4.7258	0.0056
L3	133.58 - 96.08	65.501	18	4.3455	0.0041
L4	100.75 - 63.25	38.168	18	3.5127	0.0027
L5	68.75 - 31.25	17.986	18	2.4255	0.0019
L6	37.5 - 0	5.480	18	1.3115	0.0008

### Critical Deflections and Radius of Curvature - Design Wind

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
169.00	Lightning Rod 5/8" x 4'	18	99.603	4.7261	0.0056	18568
167.00	8' x 3" Mount Pipe	18	97.627	4.7261	0.0056	18568
164.00	APXVAARR24_43-U-NA20 w/ Mount Pipe	18	94.666	4.7212	0.0056	18568
155.00	APXVTM14-C-120 w/ Mount Pipe	18	85.830	4.6667	0.0053	7209
142.00	MT6407-77A w/ Mount Pipe	18	73.329	4.4985	0.0046	3831
132.00	MX08FRO665-21 w/ Mount Pipe	18	64.063	4.3137	0.0040	2863
121.00	201-4	18	54.358	4.0687	0.0034	2387
115.00	7770.00	18	49.316	3.9177	0.0032	2190
105.00	APXV18-206517S-C w/ Mount Pipe	18	41.363	3.6402	0.0029	1925
74.00	DB810T3E-XT	18	20.820	2.6126	0.0021	1754

### Compression Checks

### Pole Design Data

Section No.	Elevation ft	Size	L ft	L <sub>u</sub> ft	KI/r	A in <sup>2</sup>	P <sub>u</sub> K	φP <sub>n</sub> K	Ratio $\frac{P_u}{\phi P_n}$
L1	169 - 164.25 (1)	TP26x18x0.25	4.75	0.00	0.0	17.258 6	-0.45	1009.63	0.000
L2	164.25 - 129.75 (2)	TP34.0625x21.5x0.3125	36.88	0.00	0.0	32.181 6	-15.10	1882.62	0.008
L3	129.75 - 96.08 (3)	TP41.75x32.1327x0.375	37.50	0.00	0.0	47.821 1	-30.46	2797.53	0.011
L4	96.08 - 63.25 (4)	TP49.0625x39.8023x0.37 5	37.50	0.00	0.0	56.333 7	-40.29	3295.52	0.012
L5	63.25 - 31.25 (5)	TP56.125x46.9543x0.375	37.50	0.00	0.0	64.537 2	-51.45	3775.43	0.014
L6	31.25 - 0 (6)	TP62.9375x53.8466x0.37 5	37.50	0.00	0.0	74.465 0	-66.55	4356.20	0.015

### Pole Bending Design Data

Section No.	Elevation ft	Size	$M_{ux}$ kip-ft	$\phi M_{nx}$ kip-ft	Ratio $\frac{M_{ux}}{\phi M_{nx}}$	$M_{uy}$ kip-ft	$\phi M_{ny}$ kip-ft	Ratio $\frac{M_{uy}}{\phi M_{ny}}$
L1	169 - 164.25 (1)	TP26x18x0.25	0.83	571.42	0.001	0.00	571.42	0.000
L2	164.25 - 129.75 (2)	TP34.0625x21.5x0.3125	322.48	1557.39	0.207	0.00	1557.39	0.000
L3	129.75 - 96.08 (3)	TP41.75x32.1327x0.375	1106.18	2842.24	0.389	0.00	2842.24	0.000
L4	96.08 - 63.25 (4)	TP49.0625x39.8023x0.375	2114.76	3754.93	0.563	0.00	3754.93	0.000
L5	63.25 - 31.25 (5)	TP56.125x46.9543x0.375	3236.35	4686.48	0.691	0.00	4686.48	0.000
L6	31.25 - 0 (6)	TP62.9375x53.8466x0.375	4724.37	5847.24	0.808	0.00	5847.24	0.000

### Pole Shear Design Data

Section No.	Elevation ft	Size	Actual $V_u$ K	$\phi V_n$ K	Ratio $\frac{V_u}{\phi V_n}$	Actual $T_u$ kip-ft	$\phi T_n$ kip-ft	Ratio $\frac{T_u}{\phi T_n}$
L1	169 - 164.25 (1)	TP26x18x0.25	0.11	302.89	0.000	0.00	576.93	0.000
L2	164.25 - 129.75 (2)	TP34.0625x21.5x0.3125	16.26	564.79	0.029	0.63	1604.78	0.000
L3	129.75 - 96.08 (3)	TP41.75x32.1327x0.375	29.31	839.26	0.035	0.70	2952.96	0.000
L4	96.08 - 63.25 (4)	TP49.0625x39.8023x0.375	33.88	988.66	0.034	1.98	4097.85	0.000
L5	63.25 - 31.25 (5)	TP56.125x46.9543x0.375	37.74	1132.63	0.033	1.98	5378.23	0.000
L6	31.25 - 0 (6)	TP62.9375x53.8466x0.375	41.36	1306.86	0.032	1.98	7160.17	0.000

### Pole Interaction Design Data

Section No.	Elevation ft	Ratio $\frac{P_u}{\phi P_n}$	Ratio $\frac{M_{ux}}{\phi M_{nx}}$	Ratio $\frac{M_{uy}}{\phi M_{ny}}$	Ratio $\frac{V_u}{\phi V_n}$	Ratio $\frac{T_u}{\phi T_n}$	Comb. Stress Ratio	Allow. Stress Ratio	Criteria
L1	169 - 164.25 (1)	0.000	0.001	0.000	0.000	0.000	0.002	1.050	4.8.2
L2	164.25 - 129.75 (2)	0.008	0.207	0.000	0.029	0.000	0.216	1.050	4.8.2
L3	129.75 - 96.08 (3)	0.011	0.389	0.000	0.035	0.000	0.401	1.050	4.8.2
L4	96.08 - 63.25 (4)	0.012	0.563	0.000	0.034	0.000	0.577	1.050	4.8.2
L5	63.25 - 31.25 (5)	0.014	0.691	0.000	0.033	0.000	0.705	1.050	4.8.2
L6	31.25 - 0 (6)	0.015	0.808	0.000	0.032	0.000	0.824	1.050	4.8.2

### Section Capacity Table

Section No.	Elevation ft	Component Type	Size	Critical Element	P K	$\phi P_{allow}$ K	% Capacity	Pass Fail
-------------	-----------------	-------------------	------	---------------------	--------	-----------------------	---------------	--------------

Section No.	Elevation ft	Component Type	Size	Critical Element	P K	$\phi P_{allow}$ K	% Capacity	Pass Fail
L1	169 - 164.25	Pole	TP26x18x0.25	1	-0.45	1060.11	0.2	Pass
L2	164.25 - 129.75	Pole	TP34.0625x21.5x0.3125	2	-15.10	1976.75	20.6	Pass
L3	129.75 - 96.08	Pole	TP41.75x32.1327x0.375	3	-30.46	2937.41	38.2	Pass
L4	96.08 - 63.25	Pole	TP49.0625x39.8023x0.375	4	-40.29	3460.30	54.9	Pass
L5	63.25 - 31.25	Pole	TP56.125x46.9543x0.375	5	-51.45	3964.20	67.2	Pass
L6	31.25 - 0	Pole	TP62.9375x53.8466x0.375	6	-66.55	4574.01	78.5	Pass
							Summary	
							Pole (L6)	78.5 Pass
							<b>RATING =</b>	<b>78.5 Pass</b>

**APPENDIX B**  
**BASE LEVEL DRAWING**



(OTHER CONSIDERED EQUIPMENT—IN (2) CONDUITS)  
(3) 3/8" TO 115 FT LEVEL  
(6) 5/8" TO 115 FT LEVEL  
(OTHER CONSIDERED EQUIPMENT)  
(12) 1-5/8" TO 115 FT LEVEL

(OTHER CONSIDERED EQUIPMENT)  
(4) 7/8" TO 164 FT LEVEL

(OTHER CONSIDERED EQUIPMENT)  
(1) 7/8" TO 74 FT LEVEL

(OTHER CONSIDERED EQUIPMENT)  
(1) 1/2" TO 121 FT LEVEL

CLIMBING RUNGS  
W/ SAFETY CLIMB

(OTHER CONSIDERED EQUIPMENT)  
(8) 1-5/8" TO 142 FT LEVEL


(PROPOSED EQUIPMENT CONFIGURATION)  
(1) 1-1/2" TO 132 FT LEVEL

(OTHER CONSIDERED EQUIPMENT)  
(6) 1-5/8" TO 105 FT LEVEL

(OTHER CONSIDERED EQUIPMENT)  
(4) 1-1/4" TO 155 FT LEVEL

(OTHER CONSIDERED EQUIPMENT)  
(7) 7/8" TO 164 FT LEVEL

(OTHER CONSIDERED EQUIPMENT)  
(3) 1-5/8" TO 164 FT LEVEL



## **APPENDIX C**

### **ADDITIONAL CALCULATIONS**

# Monopole Base Plate Connection




Site Info	
BU #	826768
Site Name	Plymouth/Rt 6
Order #	553358 Rev. 1

Analysis Considerations	
TIA-222 Revision	H
Grout Considered:	No
$l_{ar}$ (in)	1.5

Applied Loads	
Moment (kip-ft)	4724.37
Axial Force (kips)	66.55
Shear Force (kips)	41.36

\*TIA-222-H Section 15.5 Applied



Connection Properties		Analysis Results	
<b>Anchor Rod Data</b>		<b>Anchor Rod Summary</b> <i>(units of kips, kip-in)</i>	
(45) 1-1/4" $\phi$ bolts (A687 N; $F_y=105$ ksi, $F_u=125$ ksi) on 68" BC		$Pu_t = 72.62$	$\phi Pn_t = 90.84$ <b>Stress Rating</b>
<b>Base Plate Data</b>		$Vu = 0.92$	$\phi Vn = 57.52$ <b>76.1%</b>
73" OD x 2.5" Plate (A572-50; $F_y=50$ ksi, $F_u=65$ ksi)		$Mu = 0.9$	$\phi Mn = 30.76$ <b>Pass</b>
<b>Stiffener Data</b>		<b>Base Plate Summary</b>	
N/A		Max Stress (ksi):	17.45 (Flexural)
<b>Pole Data</b>		Allowable Stress (ksi):	45
62.9375" x 0.375" 18-sided pole (A572-65; $F_y=65$ ksi, $F_u=80$ ksi)		Stress Rating:	<b>36.9%</b> <b>Pass</b>

## Pier and Pad Foundation



BU #: 826768  
 Site Name: Plymouth/Rt. 6  
 App. Number: 553358 Rev. 1

TIA-222 Revision: H  
 Tower Type: Monopole

Top & Bot. Pad Rein. Different?: ☐  
 Block Foundation?: ☐  
 Rectangular Pad?: ☐

Superstructure Analysis Reactions		
Compression, $P_{comp}$ :	66.57	kips
Base Shear, $Vu_{comp}$ :	41.33	kips
Moment, $M_u$ :	4724.36	ft-kips
Tower Height, $H$ :	169	ft
BP Dist. Above Fdn, $bp_{dist}$ :	2.75	in

Pier Properties		
Pier Shape:	Circular	
Pier Diameter, $dpier$ :	7.5	ft
Ext. Above Grade, $E$ :	0.5	ft
Pier Rebar Size, $Sc$ :	9	
Pier Rebar Quantity, $mc$ :	39	
Pier Tie/Spiral Size, $St$ :	4	
Pier Tie/Spiral Quantity, $mt$ :	11	
Pier Reinforcement Type:	Tie	
Pier Clear Cover, $cc_{pier}$ :	3	in

Pad Properties		
Depth, $D$ :	8.5	ft
Pad Width, $W_1$ :	27	ft
Pad Thickness, $T$ :	2.5	ft
Pad Rebar Size (Bottom dir. 2), $Sp_2$ :	9	
Pad Rebar Quantity (Bottom dir. 2), $mp_2$ :	36	
Pad Clear Cover, $cc_{pad}$ :	3	in

Material Properties		
Rebar Grade, $F_y$ :	60	ksi
Concrete Compressive Strength, $F'_c$ :	4	ksi
Dry Concrete Density, $\delta c$ :	150	pcf

Soil Properties		
Total Soil Unit Weight, $\gamma$ :	125	pcf
Ultimate Gross Bearing, $Q_{ult}$ :	12.000	ksf
Cohesion, $C_u$ :		ksf
Friction Angle, $\phi$ :	34	degrees
SPT Blow Count, $N_{blows}$ :	104	
Base Friction, $\mu$ :	0.6	
Neglected Depth, $N$ :	3.75	ft
Foundation Bearing on Rock?	No	
Groundwater Depth, $gw$ :	14	ft

Foundation Analysis Checks				
	Capacity	Demand	Rating*	Check
Lateral (Sliding) (kips)	548.20	41.33	7.2%	Pass
Bearing Pressure (ksf)	9.00	2.54	26.8%	Pass
Overturning (kip*ft)	9553.25	5105.80	53.4%	Pass
Pier Flexure (Comp.) (kip*ft)	6863.08	4993.01	69.3%	Pass
Pier Compression (kip)	28118.83	118.26	0.4%	Pass
Pad Flexure (kip*ft)	3941.07	1717.08	41.5%	Pass
Pad Shear - 1-way (kips)	777.90	260.69	31.9%	Pass
Pad Shear - 2-way (Comp) (ksi)	0.190	0.064	32.0%	Pass
Flexural 2-way (Comp) (kip*ft)	4354.14	2995.80	65.5%	Pass

\*Rating per TIA-222-H Section 15.5

Structural Rating*:	69.3%
Soil Rating*:	53.4%

<--Toggle between Gross and Net

BU:	826768
WO:	1966237
APP:	553358 Rev. 1
TIA:	TIA-222-H



- ☐ Reinforced Tower
- ☒ Apply TIA-222-H Section 15.5

**Table 1: Tower Geometry**

	Height Above Ground (ft)	Section Length (ft)	Lap Splice Length (ft)	Number of Sides	Top Diameter (in)	Bottom Diameter (in)	Wall Thickness (in)	Bend Radius (in)	Pole Material
1	169.000	4.750	2.375	18	18.0000	26.0000	0.2500	1.0000	A572-65
2	166.630	36.875	3.830	18	21.5000	34.0625	0.3125	1.2500	A572-65
3	133.580	37.500	4.670	18	32.1327	41.7500	0.3750	1.5000	A572-65
4	100.750	37.500	5.500	18	39.8023	49.0625	0.3750	1.5000	A572-65
5	68.750	37.500	6.250	18	46.9543	56.1250	0.3750	1.5000	A572-65
6	37.500	37.500	0.000	18	53.8466	62.9375	0.3750	1.5000	A572-65

**Table 2: Splice Check**

*(Highlighted values can be taken from the Tapered Pole Properties table of the TNX Output)*

	Lap Splice Length (in)	Bottom Inner Diameter (in)	Required Splice (in)	Splice Check	Tip Diameter (in)	A (in <sup>2</sup> )	I (in <sup>4</sup> )	Bottom w/t	S (in <sup>3</sup> )
1	28.500	25.500	38.250	Reduce Strength	26.363	20.433	1711.654	16.544	129.855
2	45.960	33.438	50.156	Reduce Strength	34.540	33.476	4817.434	17.424	278.950
3	56.040	41.000	61.500	Reduce Strength	42.336	49.247	10650.982	17.835	503.162
4	66.000	48.313	72.469	Reduce Strength	49.762	57.950	17355.138	21.267	697.533
5	75.000	55.375	83.063	Reduce Strength	56.933	66.356	26056.151	24.581	915.327

**Table 3: Loading**

*(Highlighted values can be taken from the MPAUXDATA worksheet created with the TNX output)*

	$\sqrt{(F_y/E)} * (w/t)$	Reduction Factor	F <sub>y</sub> ' (ksi)	ΦP <sub>n</sub> (kip)	ΦM <sub>n</sub> (kip-ft)	ΦV <sub>n</sub> (kip)	P <sub>u</sub> (kip)	M <sub>u</sub> (kip-ft)	V <sub>u</sub> (kip)
1	0.783	0.62	50.61	738	493	221	0.45	0.83	0.11
2	0.825	0.87	70.75	1713	1480	514	15.10	322.48	16.26
3	0.844	0.87	69.71	2497	2631	749	30.46	1106.18	29.31
4	1.007	0.87	66.16	2936	3461	881	40.29	2114.76	33.88
5	1.164	0.85	61.93	3317	4252	995	51.45	3236.35	37.74

### Results

	Ratio (%)
1	0.2%
2	21.7%
3	41.4%
4	59.6%
5	74.1%

# ASCE 7 Hazards Report

**Address:**

No Address at This  
Location

**Standard:**

ASCE/SEI 7-10


**Risk Category:** II**Soil Class:**

D - Stiff Soil

**Elevation:** 889.9 ft (NAVD 88)

**Latitude:** 41.668388

**Longitude:** -73.019956



## Wind

**Results:**

Wind Speed:	119 Vmph
10-year MRI	76 Vmph
25-year MRI	86 Vmph
50-year MRI	91 Vmph
100-year MRI	98 Vmph

120 mph per Appendix N of 2018 Connecticut State Building Code

**Data Source:** ASCE/SEI 7-10 Fig. 26.5-1A and Figs. CC-1–CC-4, and Section 26.5.2, incorporating errata of March 12, 2014

Value provided is 3-second gust wind speeds at 33 ft above ground for Exposure C Category, based on linear interpolation between contours. Wind speeds are interpolated in accordance with the 7-10 Standard. Wind speeds correspond to approximately a 7% probability of exceedance in 50 years (annual exceedance probability = 0.00143, MRI = 700 years).



Site is in a hurricane-prone region as defined in ASCE/SEI 7-10 Section 26.2. Glazed openings need not be protected against wind-borne debris.

**Site Soil Class:** D - Stiff Soil

**Results:**

$S_S$ :	0.186	$S_{DS}$ :	0.198
$S_1$ :	0.064	$S_{D1}$ :	0.103
$F_a$ :	1.6	$T_L$ :	6
$F_v$ :	2.4	PGA :	0.095
$S_{MS}$ :	0.297	$PGA_M$ :	0.152
$S_{M1}$ :	0.154	$F_{PGA}$ :	1.6
		$I_e$ :	1

**Seismic Design Category** B



**Data Accessed:**

Mon May 24 2021

**Date Source:**

USGS Seismic Design Maps based on ASCE/SEI 7-10, incorporating Supplement 1 and errata of March 31, 2013, and ASCE/SEI 7-10 Table 1.5-2. Additional data for site-specific ground motion procedures in accordance with ASCE/SEI 7-10 Ch. 21 are available from USGS.

**Results:**

Ice Thickness: 0.75 in.

Concurrent Temperature: 5 F

Gust Speed: 50 mph

**Data Source:** Standard ASCE/SEI 7-10, Figs. 10-2 through 10-8

**Date Accessed:** Mon May 24 2021

Ice thicknesses on structures in exposed locations at elevations higher than the surrounding terrain and in valleys and gorges may exceed the mapped values.

Values provided are equivalent radial ice thicknesses due to freezing rain with concurrent 3-second gust speeds, for a 50-year mean recurrence interval, and temperatures concurrent with ice thicknesses due to freezing rain. Thicknesses for ice accretions caused by other sources shall be obtained from local meteorological studies. Ice thicknesses in exposed locations at elevations higher than the surrounding terrain and in valleys and gorges may exceed the mapped values.

---

The ASCE 7 Hazard Tool is provided for your convenience, for informational purposes only, and is provided "as is" and without warranties of any kind. The location data included herein has been obtained from information developed, produced, and maintained by third party providers; or has been extrapolated from maps incorporated in the ASCE 7 standard. While ASCE has made every effort to use data obtained from reliable sources or methodologies, ASCE does not make any representations or warranties as to the accuracy, completeness, reliability, currency, or quality of any data provided herein. Any third-party links provided by this Tool should not be construed as an endorsement, affiliation, relationship, or sponsorship of such third-party content by or from ASCE.

ASCE does not intend, nor should anyone interpret, the results provided by this Tool to replace the sound judgment of a competent professional, having knowledge and experience in the appropriate field(s) of practice, nor to substitute for the standard of care required of such professionals in interpreting and applying the contents of this Tool or the ASCE 7 standard.

In using this Tool, you expressly assume all risks associated with your use. Under no circumstances shall ASCE or its officers, directors, employees, members, affiliates, or agents be liable to you or any other person for any direct, indirect, special, incidental, or consequential damages arising from or related to your use of, or reliance on, the Tool or any information obtained therein. To the fullest extent permitted by law, you agree to release and hold harmless ASCE from any and all liability of any nature arising out of or resulting from any use of data provided by the ASCE 7 Hazard Tool.