



Crown Castle  
3 Corporate Park Drive, Suite 101  
Clifton Park, NY 12065

June 8, 2018

Melanie A. Bachman  
Acting Executive Director  
Connecticut Siting Council  
10 Franklin Square  
New Britain, CT 06051

**RE: Notice of Exempt Modification for Sprint Crown Site BU: 876360**  
**Sprint Site ID: CT23XC411**  
**389 Route 2, Preston, New London County, CT 06365**  
**Latitude: 41° 29' 25.25" / Longitude: -71° 59' 29.55"**

Dear Ms. Bachman:

Sprint currently maintains (6) antennas at the 147-foot level of the existing 147-foot monopole at 389 Route 2, Preston, Connecticut 06365. The tower is owned by Crown Castle and the property is owned by The Town of Preston. Sprint intends to install (6) antennas in place of (6) antennas that will be removed, add (12) RRHs, add (4) lines, remove (6) coax, and swap the current antenna platform mount for a new mount with handrail kit.

The Connecticut Siting Council's Telecommunications Database provides the Council approved tower sharing at an existing telecommunications facility located at 389 Route 2, Preston, Connecticut pursuant to TS-VER-114-001117. This only speaks to tower sharing and not the approval of the original tower. A diligent search of available records was not fruitful for obtaining a copy of the original tower approval.

Please accept this letter as notification pursuant to Regulations of Connecticut State Agencies § 16-50j-73, for construction that constitutes an exempt modification pursuant to R.C.S.A. § 16-50j-72(b)(2). In accordance with R.S.C.A. § 16-50j-73, a copy of this letter is being sent to The Honorable Robert Congdon, First Selectman for the Town of Preston, as well as the property owner.

1. The proposed modifications will not result in an increase in the height of the existing tower.
2. The proposed modifications will not require the extension of the site boundary.
3. The proposed modification will not increase noise levels at the facility by six decibels or more, or to levels that exceed state and local criteria.

Melanie A. Bachman

June 8, 2018

Page 2

4. The operation of the replacement antennas will not increase radio frequency emissions at the facility to a level at or above the Federal Communication Commission safety standard.
5. The proposed modifications will not cause a change or alteration in the physical or environmental characteristics of the site.
6. The existing structure and its foundation can support the proposed loading.

For the foregoing reasons, Sprint respectfully submits that the proposed modifications to the above-reference telecommunications facility constitutes an exempt modification under R.C.S.A. § 16-50j-72(b)(2). Please send approval/rejection letter to Attn: Anne Marie Zsamba.

Sincerely,



Anne Marie Zsamba, Esq.

Real Estate Specialist

3 Corporate Park Drive, Suite 101, Clifton Park, NY 12065

(518) 350-3639

annemarie.zsamba.contractor@crowncastle.com

Attachments:

Tab A: Exhibit-1: Compound Plan and Elevation Depicting the Planned Changes

Tab B: Exhibit-2: Structural Modification Report

Tab C: Exhibit-3: General Power Density Table Report (RF Emissions Analysis Report)

cc: The Honorable Robert Congdon, First Selectman

Town of Preston

389 Route 2

Preston, CT 06365

(860) 887-5581 ext. 105

Town of Preston

Town Hall

389 Route 2

Preston, CT 06365

(860) 887-5581



**Property Information**

Owner	PRESTON TOWN OF
Address	389 ROUTE 2
Mailing Address	389 ROUTE 2 PRESTON , CT 06365
Land Use	9035 - MUN TOWN MDL-96
Land Class	E

Census Tract	7001
Neighborhood	8000
Zoning	R-C
Acreage	25.86
Utilities	Well,Septic
Lot Setting/ Desc	Rural / Low

**Photo**

No Photo Available

**PARCEL VALUATIONS** (Assessed value = 70% of Appraised Value)

	Appraised	Assessed
Buildings	475000	332500
Outbuildings	12900	9100
Improvements	496700	347800
Extras	8800	6200
Land	448350	313800
Total	945050	661600
Previous		

**Construction Details**

Year Built	1974
Stories	1
Building Style	City/Town Hall
Building Use	Comm/Ind
Building Condition	Average
Total Rooms	
Bedrooms	
Full Bathrooms	3
Half Bathrooms	
Bath Style	
Kitchen Style	
Roof Style	Gable/Hip
Roof Cover	Asph/F Gls/Cmp

**EXTERIOR WALLS:**

Primary	Brick/Masonry
Secondary	

**INTERIOR WALLS:**

Primary	Drywall/Sheet
Secondary	

**FLOORS:**

Primary	Infaid Sht Gds
Secondary	

**HEATING/AC:**

Heating Type	Electr Basebrd
Heating Fuel	Electric
AC Type	None

**BUILDING AREA:**

Effective Building Area	
Gross Building Area	7056
Total Living Area	5292

**SALES HISTORY:**


Sale Date	9/26/1973
Sale Price	17500
Book/ Page	56/ 174




# Town of Preston, Connecticut - Assessment Parcel Map

Parcel: 24-0-2-389

Address 389 ROUTE 2



Approximate Scale: 1:3,600



Map Produced:  
November 2016

Disclaimer: This map is for informational purposes only. All information is subject to verification by any user. The Town of Preston and its mapping contractors assume no legal responsibility for the information contained herein.

Shawville Book

Ross Rd

876366




Shawville

Shawville Rd

Norwich Western Rd

Norwich Western Rd

Norwich Western Rd



PLANS PREPARED FOR:  
**sprint**  
 6500 Sprint Parkway  
 Overland Park, Kansas 66201

PLANS PREPARED BY:  
**INFINIGY**  
 FROM ZERO TO INFINIGY  
 the solutions case engineers  
 1000 N. 17th Street, Suite 100  
 Overland Park, KS 66202  
 Phone: 913-442-3795 Fax: 913-442-3795  
 www.infinigy.com  
 © 2010 INFINIGY, INC.

MA PARTNER:  
**CROWN CASTLE**



ENGINEERING LICENSE:  
 THESE DRAWINGS ARE PRELIMINARY AND ARE THE SOLE PROPERTY OF SPRINT AND ARE NOT TO BE REPRODUCED, DISSEMINATED OR REUTILIZED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

NO.	DESCRIPTION	DATE	BY	REV.
1	ISSUED FOR CONSTRUCTION	06/27/10	JSP	1
2		06/27/10	JSP	2

SITE NAME:  
**PRESTON / TOWN HALL**

SITE ADDRESS:  
**CT23XC411**

SITE ADDRESS:  
**389 RT 2  
 PRESTON, CT 06365**

SHEET DESCRIPTION:  
**TITLE SHEET & PROJECT DATA**

SHEET NUMBER:  
**T-1**

**PROJECT:** DO MACRO UPGRADE  
**SITE NAME:** PRESTON / TOWN HALL  
**SITE CASCADE:** CT23XC411  
**SITE NUMBER:** 876360  
**SITE ADDRESS:** 389 RT 2  
 PRESTON, CT 06365  
**SITE TYPE:** MONOPOLE  
**MARKET:** N. ENGLAND

SHEET NO.	DRAWING INDEX	SHEET TITLE	REV.
T-1	TITLE SHEET & PROJECT DATA		
SP-1	SPRINT SPECIFICATIONS		
SP-2	SPRINT SPECIFICATIONS		
SP-3	SPRINT SPECIFICATIONS		
A-1	SITE PLAN		
A-2	TOWER ELEVATION & CABLE PLAN		
A-3	FOUNDATION & MOUNTING DETAILS		
A-4	FOUNDATION & MOUNTING DETAILS		
A-5	CWE DETAILS		
A-6	PLANNING DIAGRAM		
E-1	ELECTRICAL & GROUNDING PLAN		
E-2	ELECTRICAL & GROUNDING DETAILS		

**PROJECT DESCRIPTION**  
 VISIT PREVIOUS TO WORK AT EXISTING UNMOUNTED TELECOMMUNICATIONS FACILITY.



- INSTALL 2.5 ELEMENT RISE EXISTING N.V. JAMES CORNET
- INSTALL (2) 100' 4" L-SPRINGS-200' 4" PANEL ANTENNAS
- INSTALL (2) 100' 4" L-SPRINGS-200' 4" PANEL ANTENNAS
- INSTALL (2) COMPOSITE SPRINGS-200' 4" PANEL ANTENNAS
- INSTALL (2) ALL 4-400-800 RISES ON TOWER
- INSTALL (2) ALL 200-800 RISES ON TOWER
- INSTALL (2) 400-800 RISES ON TOWER
- REMOVE (2) PIPED CABLES
- REMOVE (2) CWK
- REMOVE EXISTING ANTENNA PLATFORM MOUNT
- INSTALL NEW ANTENNA PLATFORM MOUNT BY HANDBALL MT

THESE PLANS HAVE BEEN PREPARED FOR THE IMPLEMENTATION OF AN EXISTING UNMOUNTED TELECOMMUNICATIONS FACILITY OWNED OR LEASED BY SPRINT IN ACCORDANCE WITH THE SCOPE OF WORK PROVIDED BY SPRINT. SPRINT HAS THE SOLE RESPONSIBILITY FOR OBTAINING ALL NECESSARY PERMITS AND FOR CONSTRUCTION ACCESS ACCOMPANIED BY A PRESSURE STATEMENT. ALL STRUCTURAL ANALYSIS PREPARED BY A LICENSED STRUCTURAL ENGINEER. STRUCTURAL ANALYSIS MUST INCLUDE BESS STRUCTURE AND MOUNT.

**APPLICABLE CODES**

ALL WORK SHALL BE PERFORMED AND MATERIALS INSTALLED IN ACCORDANCE WITH THE MOST RECENT EDITIONS OF THE FOLLOWING CODES AS ADOPTED BY THE LOCAL GOVERNING AUTHORITY. NOTIFICATIONS IN THESE PLANS IS TO BE CONSIDERED TO PREVENT WORK NOT CONFORMING TO THESE CODES.

- INTERNATIONAL BUILDING CODE (2010 IBC)
- IBC-222-6 OR LATEST EDITION
- NETA AND - LATEST EDITION
- NETA AND - LATEST EDITION
- ANY OTHER NATIONAL OR LOCAL APPLICABLE CODES.
- MOST RECENT EDITIONS
- STATE OF CONNECTICUT
- CITY/TOWN ORDINANCES



**SITE INFORMATION**

**PROPERTY OWNER:**  
 CROWN ATLANTIC COMPANY, LLC  
 2000 CORPORATE DRIVE  
 CHAMBERSBURG, PA 15317  
 (717) 400-0000

**LATITUDE (NAD83):**  
 41.80237  
 29.25

**LONGITUDE (NAD83):**  
 W 71° 59' 29.55"  
 -71.9911442

**COUNTY:**  
 NEW LONDON


**ZONING JURISDICTION:**  
 CONNECTICUT SITING COUNCIL

**ZONING DISTRICT:**  
 MUNICIPAL

**POWER COMPANY:**  
 NORTHEAST UTILITIES  
 800-280-8800

**SPRINT CONSTRUCTION:**  
 TBD

**CROWN PM:**  
 SCOTT WAIKOSKI  
 (817) 250-9228



THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

Table with columns: REVISIONS, DESCRIPTION, DATE, BY. Includes CLIENT RECORDS and USED FOR CONSTRUCTION.

PRESTON / TOWN HALL

CT23XC411

389 RT 2, PRESTON, CT 06365

SPRINT SPECIFICATIONS

SP-1

SECTION 01.100 - SCORE OF WORK

1.1 THE WORK, THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE SPRINT CONSTRUCTION STANDARDS FOR WIRELESS SITES, CONTRACT DOCUMENTS, AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

1.2 RELATED DOCUMENTS:

- A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
B. SPRINT STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.

1.3 PROVISIONS SHALL INCLUDE (SEE REFERENCED) THE STANDARD CONSTRUCTION SPECIFICATIONS FROM WIRELESS SITES INCLUDING THE STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES AND THE CONSTRUCTION DRAWINGS. INFORMATION ON THE CONSTRUCTION DRAWINGS SHALL TAKE PRECEDENCE. NOTIFY SPRINT CONSTRUCTION MANAGER IF THIS OCCURS.

1.4 NATIONALLY RECOGNIZED CODES AND STANDARDS:

- A. THE WORK SHALL COMPLY WITH APPLICABLE NATIONAL AND LOCAL CODES AND STANDARDS, LATEST EDITION, AND PORTIONS THEREOF INCLUDED BUT NOT LIMITED TO THE FOLLOWING:
1. OR-03-CORE NEEDS REQUIREMENTS: PHYSICAL PROTECTION MANUFACTURE OF TELECOMMUNICATIONS EQUIPMENT.
2. OR-78-CORE GENERIC REQUIREMENTS FOR THE PHYSICAL DESIGN AND MANUFACTURE OF TELECOMMUNICATIONS EQUIPMENT.
3. OR-108B CORE: ELECTROMAGNETIC COMPATIBILITY AND ELECTRICAL SAFETY -GENERIC CRITERIA FOR NETWORK TELECOMMUNICATIONS EQUIPMENT.
4. NATIONAL FIRE PROTECTION ASSOCIATION CODES AND STANDARDS (NFPA) INCLUDING NFPA 70 (NATIONAL ELECTRICAL CODE - NEC) AND NFPA 101 (LIFE SAFETY CODE).
5. AMERICAN SOCIETY FOR TESTING OF MATERIALS (ASTM)
6. INSTITUTE OF ELECTRONIC AND ELECTRICAL ENGINEERS (IEEE)
7. AMERICAN CONCRETE INSTITUTE (ACI)
8. AMERICAN WIRE PRODUCERS ASSOCIATION (AWPA)
9. CONCRETE REINFORCING STEEL INSTITUTE (CRSI)
10. ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (ASHTO)
11. PORTLAND CEMENT ASSOCIATION (PCA)
12. NATIONAL CONCRETE MASONRY ASSOCIATION (NCMA)
13. BRICK INDUSTRY ASSOCIATION (BIA)
14. AMERICAN WELDING SOCIETY (AWS)
15. NATIONAL ROOFING CONTRACTORS ASSOCIATION (NRCA)
16. SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)
17. DOOR AND HARDWARE INSTITUTE (DHI)
18. OCCUPATIONAL SAFETY AND HEALTH ACT (OSHA)
19. APPLICABLE BUILDING CODES INCLUDING UNIFORM BUILDING CODE, SOUTHERN BUILDING CODE, BOCA, AND THE INTERNATIONAL BUILDING CODE.

1.5 DEFINITIONS:

- A. WORK: THE SUM OF TASKS AND RESPONSIBILITIES IDENTIFIED IN THE CONTRACT DOCUMENTS.
B. COMPANY: SPRINT CORPORATION
C. ENGINEER: SYNCHRONOUS WITH ARCHITECT & ENGINEER AND HAS THE DESIGN PROFESSIONAL HAVING PROFESSIONAL RESPONSIBILITY FOR DESIGN OF THE PROJECT.
D. CONTRACTOR: CONSTRUCTION CONTRACTOR. CONSTRUCTION VENDOR: INDIVIDUAL OR ENTITY WHO AFTER EXECUTION OF A CONTRACT IS BOUND TO ACCOMPLISH THE WORK.
E. THIRD PARTY VENDOR OR AGENCY: A VENDOR OR AGENCY ENGAGED SEPARATELY BY THE COMPANY, AS OR CONTRACTOR TO PROVIDE MATERIALS OR TO ACCOMPLISH SPECIFIC TASKS RELATED TO BUT NOT INCLUDED IN THE WORK.
F. OTHER OWNER FURNISHED, CONTRACTOR INSTALLED EQUIPMENT.
G. CONSTRUCTION MANAGER - ALL PROJECTS RELATED COMMUNICATION TO FLOW THROUGH SPRINT REPRESENTATIVE IN CHARGE OF PROJECT...

SECTION 01.200 - GENERAL

1.1 THE WORK, THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

1.2 RELATED DOCUMENTS:

- A. SPECIFICATION.
B. SPRINT STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.

1.3 RECEIPT OF MATERIAL AND EQUIPMENT:

- A. COMPANY FURNISHED MATERIAL AND EQUIPMENT IS IDENTIFIED ON THE RF DATA SHEET IN THE CONSTRUCTION DOCUMENTS.
B. THE CONTRACTOR IS RESPONSIBLE FOR SPRINT PROVIDED MATERIAL AND EQUIPMENT AND UPON RECEIPT SHALL:
1. ACCEPT DELIVERIES AS SHIPPED AND TIME RECEIPT.
2. VERIFY COMPLETENESS AND CONDITION OF ALL DELIVERIES.
3. TAKE RESPONSIBILITY FOR EQUIPMENT AND PROVIDE INSURANCE PROTECTION AS REQUIRED IN AGREEMENT.
4. RECORD ANY DEFECTS OR DAMAGES AND WITHIN TWENTY-FOUR HOURS AFTER RECEIPT, REPORT TO SPRINT OR ITS DESIGNATED PROJECT REPRESENTATIVE OF SUCH.
5. PROVIDE SECURE AND NECESSARY WEATHER PROTECTED WAREHOUSING.
6. COORDINATE SAFE AND SECURE TRANSPORTATION OF MATERIAL AND EQUIPMENT, DELIVERING AND OFF-LOADING FROM CONTRACTOR'S WAREHOUSE TO SITE.
7. DELIVERABLES.
A. PACKAGING, SHIPPING AND RECEIPT DOCUMENTATION IN ACCORDANCE WITH COMPANY PRACTICE.
B. ASSISTANT IN ACCORDANCE WITH COMPANY PRACTICE, AND AS DIRECTED BY COMPANY.
C. HEADQUARTERS AND GREAT SITE MANAGEMENT SYSTEM (SMS) AND/OR PROVIDE HARD COPY DOCUMENTATION AS REQUESTED.

1.4 USE OF JOB SITE:

- A. THE CONTRACTOR SHALL COMPREHEND ALL MATERIALS AND RELATED OPERATIONS INCLUDING STAGING AND STORAGE OF MATERIALS AND EQUIPMENT, TEMPORARY FENCES, AND WASTE DISPOSAL TO THE LEASE PARCEL UNLESS OTHERWISE PROVIDED BY THE CONTRACT DOCUMENTS.
B. UTILITIES SERVICES: WHERE NECESSARY TO OBTAIN TYPES ELECTRICAL, WATER, GAS, AND TELEPHONE SERVICES, THE CONTRACTOR SHALL OBTAIN ALL NECESSARY PERMITS AND APPROVALS FROM THE APPLICABLE AGENCIES. ALL SUCH ACTIONS SHALL BE COORDINATED WITH THE UTILITY COMPANY INVOLVED.
C. PERMITS / FEES: WHEN REQUIRED THAT A PERMIT OR CONNECTION FEE BE PAID TO A PUBLIC UTILITY PROVIDER FOR USE OF THE CONSTRUCTION PROJECT, THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE OBTAINING OF SUCH PERMITS AND FEES FOR PROTECTING EXISTING EQUIPMENT AND PROPERTY.
D. METHODS OF PROCEDURE (MOPS) FOR CONSTRUCTION: CONTRACTOR SHALL PERFORM WORK AS DESCRIBED IN THE FOLLOWING INSTALLATION AND COMMISSIONING MOPS.

1.5 USE OF ELECTRONIC PROJECT MANAGEMENT SYSTEMS:

- A. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE CONSTRUCTION DOCUMENTS, LEADWORK, UTILITIES AND REQUIRED INCLUDE PORTABLE WATER, HEAT, WIND, ELEVATION, SHEDDING, WASTE DISPOSAL, AND OTHER INFORMATION. THE CONTRACTOR SHALL OBTAIN ALL NECESSARY PERMITS AND APPROVALS FROM THE APPLICABLE AGENCIES. ALL SUCH ACTIONS SHALL BE COORDINATED WITH THE UTILITY COMPANY INVOLVED.
B. ACCESS TO WORK: THE CONTRACTOR SHALL PROVIDE ACCESS TO THE JOB SITE FOR ARCHITECT/ENGINEER, COMPANY FURNISHED AND AUTHORIZED PERSONNEL OF THE ARCHITECT/ENGINEER DURING ALL PHASES OF THE WORK.
C. TESTING: PROVISIONS FOR TESTING BY THIS CONTRACTOR SHALL BE AS INDICATED HEREWITH. ON THE CONSTRUCTION DOCUMENTS, AND IN THE REMOVAL OF THESE SPECIFICATIONS, SIGNED COMPANY CHANGE TO ENGAGE ANY THIRD-PARTY TO CONDUCT TESTING FOR COMPANY'S TEST AGENCY.

1.6 DIMENSIONS VERIFY DIMENSIONS INDICATED ON DRAWINGS WITH FIELD DIMENSIONS BEFORE PROCEEDING OR ORDERING OF MATERIALS. DO NOT SCALE DRAWINGS.

SECTION 01.500 - CELL SITE CONSTRUCTION CO.

1.1 THE WORK, THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

1.2 RELATED DOCUMENTS:

- A. SPECIFICATION.
B. SPRINT STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.

1.3 RECEIPT OF MATERIAL AND EQUIPMENT:

- A. COMPANY FURNISHED MATERIAL AND EQUIPMENT IS IDENTIFIED ON THE RF DATA SHEET IN THE CONSTRUCTION DOCUMENTS.
B. THE CONTRACTOR IS RESPONSIBLE FOR SPRINT PROVIDED MATERIAL AND EQUIPMENT AND UPON RECEIPT SHALL:
1. ACCEPT DELIVERIES AS SHIPPED AND TIME RECEIPT.
2. VERIFY COMPLETENESS AND CONDITION OF ALL DELIVERIES.
3. TAKE RESPONSIBILITY FOR EQUIPMENT AND PROVIDE INSURANCE PROTECTION AS REQUIRED IN AGREEMENT.
4. RECORD ANY DEFECTS OR DAMAGES AND WITHIN TWENTY-FOUR HOURS AFTER RECEIPT, REPORT TO SPRINT OR ITS DESIGNATED PROJECT REPRESENTATIVE OF SUCH.
5. PROVIDE SECURE AND NECESSARY WEATHER PROTECTED WAREHOUSING.
6. COORDINATE SAFE AND SECURE TRANSPORTATION OF MATERIAL AND EQUIPMENT, DELIVERING AND OFF-LOADING FROM CONTRACTOR'S WAREHOUSE TO SITE.
7. DELIVERABLES.
A. PACKAGING, SHIPPING AND RECEIPT DOCUMENTATION IN ACCORDANCE WITH COMPANY PRACTICE.
B. ASSISTANT IN ACCORDANCE WITH COMPANY PRACTICE, AND AS DIRECTED BY COMPANY.
C. HEADQUARTERS AND GREAT SITE MANAGEMENT SYSTEM (SMS) AND/OR PROVIDE HARD COPY DOCUMENTATION AS REQUESTED.

1.4 USE OF JOB SITE:

- A. THE CONTRACTOR SHALL COMPREHEND ALL MATERIALS AND RELATED OPERATIONS INCLUDING STAGING AND STORAGE OF MATERIALS AND EQUIPMENT, TEMPORARY FENCES, AND WASTE DISPOSAL TO THE LEASE PARCEL UNLESS OTHERWISE PROVIDED BY THE CONTRACT DOCUMENTS.
B. UTILITIES SERVICES: WHERE NECESSARY TO OBTAIN TYPES ELECTRICAL, WATER, GAS, AND TELEPHONE SERVICES, THE CONTRACTOR SHALL OBTAIN ALL NECESSARY PERMITS AND APPROVALS FROM THE APPLICABLE AGENCIES. ALL SUCH ACTIONS SHALL BE COORDINATED WITH THE UTILITY COMPANY INVOLVED.
C. PERMITS / FEES: WHEN REQUIRED THAT A PERMIT OR CONNECTION FEE BE PAID TO A PUBLIC UTILITY PROVIDER FOR USE OF THE CONSTRUCTION PROJECT, THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE OBTAINING OF SUCH PERMITS AND FEES FOR PROTECTING EXISTING EQUIPMENT AND PROPERTY.
D. METHODS OF PROCEDURE (MOPS) FOR CONSTRUCTION: CONTRACTOR SHALL PERFORM WORK AS DESCRIBED IN THE FOLLOWING INSTALLATION AND COMMISSIONING MOPS.

1.5 USE OF ELECTRONIC PROJECT MANAGEMENT SYSTEMS:

- A. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE CONSTRUCTION DOCUMENTS, LEADWORK, UTILITIES AND REQUIRED INCLUDE PORTABLE WATER, HEAT, WIND, ELEVATION, SHEDDING, WASTE DISPOSAL, AND OTHER INFORMATION. THE CONTRACTOR SHALL OBTAIN ALL NECESSARY PERMITS AND APPROVALS FROM THE APPLICABLE AGENCIES. ALL SUCH ACTIONS SHALL BE COORDINATED WITH THE UTILITY COMPANY INVOLVED.
B. ACCESS TO WORK: THE CONTRACTOR SHALL PROVIDE ACCESS TO THE JOB SITE FOR ARCHITECT/ENGINEER, COMPANY FURNISHED AND AUTHORIZED PERSONNEL OF THE ARCHITECT/ENGINEER DURING ALL PHASES OF THE WORK.
C. TESTING: PROVISIONS FOR TESTING BY THIS CONTRACTOR SHALL BE AS INDICATED HEREWITH. ON THE CONSTRUCTION DOCUMENTS, AND IN THE REMOVAL OF THESE SPECIFICATIONS, SIGNED COMPANY CHANGE TO ENGAGE ANY THIRD-PARTY TO CONDUCT TESTING FOR COMPANY'S TEST AGENCY.

1.6 DIMENSIONS VERIFY DIMENSIONS INDICATED ON DRAWINGS WITH FIELD DIMENSIONS BEFORE PROCEEDING OR ORDERING OF MATERIALS. DO NOT SCALE DRAWINGS.

SECTION 01.600 - COMPANY FURNISHED MATERIAL AND EQUIPMENT

1.1 THE WORK, THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

1.2 RELATED DOCUMENTS:

- A. SPECIFICATION.
B. SPRINT STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.

1.3 RECEIPT OF MATERIAL AND EQUIPMENT:

- A. COMPANY FURNISHED MATERIAL AND EQUIPMENT IS IDENTIFIED ON THE RF DATA SHEET IN THE CONSTRUCTION DOCUMENTS.
B. THE CONTRACTOR IS RESPONSIBLE FOR SPRINT PROVIDED MATERIAL AND EQUIPMENT AND UPON RECEIPT SHALL:
1. ACCEPT DELIVERIES AS SHIPPED AND TIME RECEIPT.
2. VERIFY COMPLETENESS AND CONDITION OF ALL DELIVERIES.
3. TAKE RESPONSIBILITY FOR EQUIPMENT AND PROVIDE INSURANCE PROTECTION AS REQUIRED IN AGREEMENT.
4. RECORD ANY DEFECTS OR DAMAGES AND WITHIN TWENTY-FOUR HOURS AFTER RECEIPT, REPORT TO SPRINT OR ITS DESIGNATED PROJECT REPRESENTATIVE OF SUCH.
5. PROVIDE SECURE AND NECESSARY WEATHER PROTECTED WAREHOUSING.
6. COORDINATE SAFE AND SECURE TRANSPORTATION OF MATERIAL AND EQUIPMENT, DELIVERING AND OFF-LOADING FROM CONTRACTOR'S WAREHOUSE TO SITE.
7. DELIVERABLES.
A. PACKAGING, SHIPPING AND RECEIPT DOCUMENTATION IN ACCORDANCE WITH COMPANY PRACTICE.
B. ASSISTANT IN ACCORDANCE WITH COMPANY PRACTICE, AND AS DIRECTED BY COMPANY.
C. HEADQUARTERS AND GREAT SITE MANAGEMENT SYSTEM (SMS) AND/OR PROVIDE HARD COPY DOCUMENTATION AS REQUESTED.

1.4 USE OF JOB SITE:


- A. THE CONTRACTOR SHALL COMPREHEND ALL MATERIALS AND RELATED OPERATIONS INCLUDING STAGING AND STORAGE OF MATERIALS AND EQUIPMENT, TEMPORARY FENCES, AND WASTE DISPOSAL TO THE LEASE PARCEL UNLESS OTHERWISE PROVIDED BY THE CONTRACT DOCUMENTS.
B. UTILITIES SERVICES: WHERE NECESSARY TO OBTAIN TYPES ELECTRICAL, WATER, GAS, AND TELEPHONE SERVICES, THE CONTRACTOR SHALL OBTAIN ALL NECESSARY PERMITS AND APPROVALS FROM THE APPLICABLE AGENCIES. ALL SUCH ACTIONS SHALL BE COORDINATED WITH THE UTILITY COMPANY INVOLVED.
C. PERMITS / FEES: WHEN REQUIRED THAT A PERMIT OR CONNECTION FEE BE PAID TO A PUBLIC UTILITY PROVIDER FOR USE OF THE CONSTRUCTION PROJECT, THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE OBTAINING OF SUCH PERMITS AND FEES FOR PROTECTING EXISTING EQUIPMENT AND PROPERTY.
D. METHODS OF PROCEDURE (MOPS) FOR CONSTRUCTION: CONTRACTOR SHALL PERFORM WORK AS DESCRIBED IN THE FOLLOWING INSTALLATION AND COMMISSIONING MOPS.

1.5 USE OF ELECTRONIC PROJECT MANAGEMENT SYSTEMS:

- A. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE CONSTRUCTION DOCUMENTS, LEADWORK, UTILITIES AND REQUIRED INCLUDE PORTABLE WATER, HEAT, WIND, ELEVATION, SHEDDING, WASTE DISPOSAL, AND OTHER INFORMATION. THE CONTRACTOR SHALL OBTAIN ALL NECESSARY PERMITS AND APPROVALS FROM THE APPLICABLE AGENCIES. ALL SUCH ACTIONS SHALL BE COORDINATED WITH THE UTILITY COMPANY INVOLVED.
B. ACCESS TO WORK: THE CONTRACTOR SHALL PROVIDE ACCESS TO THE JOB SITE FOR ARCHITECT/ENGINEER, COMPANY FURNISHED AND AUTHORIZED PERSONNEL OF THE ARCHITECT/ENGINEER DURING ALL PHASES OF THE WORK.
C. TESTING: PROVISIONS FOR TESTING BY THIS CONTRACTOR SHALL BE AS INDICATED HEREWITH. ON THE CONSTRUCTION DOCUMENTS, AND IN THE REMOVAL OF THESE SPECIFICATIONS, SIGNED COMPANY CHANGE TO ENGAGE ANY THIRD-PARTY TO CONDUCT TESTING FOR COMPANY'S TEST AGENCY.

1.6 DIMENSIONS VERIFY DIMENSIONS INDICATED ON DRAWINGS WITH FIELD DIMENSIONS BEFORE PROCEEDING OR ORDERING OF MATERIALS. DO NOT SCALE DRAWINGS.

PLANS PREPARED FOR:



DRAWING NOTICE: THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, COPIED, DISTRIBUTED OR OTHERWISE TRANSMITTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

Table with columns: REVISION, DESCRIPTION, DATE, BY, REV. Includes rows for CLIENT RESPONSE, SAVED TO DESCRIPTION, and SHEET NO.

PRESTON / TOWN HALL

SITE CHAIRMAN: CT23XC411

SITE ADDRESS: 389 RT 2, PRESTON, CT 06365

SHEET DESCRIPTION: SPRINT SPECIFICATIONS

SHEET NUMBER: SP-2

5. LINES AND ANTENNA INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).

6. POWER INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).

7. TELCO INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).

8. PFC (OR SHEET) INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).

9. TOWER CONSTRUCTION START DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).

10. TOWER CONSTRUCTION COMPLETE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).

11. SIS AND RAMP EQUIPMENT DELIVERED AT SITE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).

12. NETWORK OPERATIONS HANDOFF CHECKLIST (OIC WALK) COMPLETE (UPLOAD FROM IT) DATE

13. CIVIL CONSTRUCTION COMPLETE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).

14. SITE CONSTRUCTION PROGRESS PHOTOS UNLOADED INTO SMS.

15. COMMISSIONING: PERFORM ALL COMMISSIONING AS REQUIRED BY APPLICABLE AGENCY

16. INTERFEROR: PERFORM ALL INTERFEROR ACTIVITIES AS REQUIRED BY APPLICABLE AGENCY

17. PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION

3.1 REQUIREMENTS FOR TESTING:

A. THIRD PARTY TESTING AGENCY:

1. WHEN THE USE OF A THIRD PARTY INDEPENDENT TESTING AGENCY IS REQUIRED, THE AGENCY THAT IS SELECTED MUST PERFORM SUCH TESTING ON A REGULAR BASIS IN THE STATE WHERE THE PROJECT IS LOCATED AND HAVE A COMPREHENSIVE UNDERSTANDING OF LOCAL AVAILABLE MATERIALS, INCLUDING THE SOIL, ROCK, TYPICAL AND UNUSUAL CONDITIONS.

2. THE THIRD PARTY TESTING AGENCY IS TO BE FAMILIAR WITH THE APPLICABLE LOCAL AND STATE REGULATIONS, PERMITS, EQUIPMENT TO BE USED, AND ASSOCIATED HEALTH AND SAFETY ISSUES.

3. EXPERIENCE IN SOILS, CONCRETE, MASONRY, ASPHALT AND ASPHALT TESTING USING ASTM, AASHTO, AND OTHER METHODS IS NEEDED.

4. EXPERIENCE IN SOILS, CONCRETE, MASONRY, ASPHALT AND ASPHALT TESTING USING ASTM, AASHTO, AND OTHER METHODS IS NEEDED.

3.2 REQUIREMENTS FOR TESTING:

A. CONTRACTOR SHALL ACCOMPLISH TESTING INCLUDING BUT NOT LIMITED TO THE FOLLOWING:

1. CONCRETE CUREMENT BREAK TESTS FOR THE TOWER AND ANCHOR FOUNDATIONS AS SPECIFIED IN SECTION PORTLAND CEMENT CONCRETE PARTING.

2. ASPHALT ROADWAY COMPACTED THICKNESS, SURFACE SMOOTHNESS, AND FIELD QUANTITY TESTING AS SPECIFIED IN SECTION HOT MIX ASPHALT CONCRETE PARTING.

3. FIELD QUANTITY TESTING AS SPECIFIED IN SECTION PORTLAND CEMENT CONCRETE PARTING.

4. TESTING REQUIRED UNDER SECTION: AGGREGATE BASE FOR ACCESS ROADS, PAVES AND PAVEMENT LOGGERS

5. STRUCTURAL BACKFILL COMPOSITION TESTS FOR THE TOWER FOUNDATION.

6. SITE RESISTANCE TO EARTH TESTING PER EXHIBIT CELL SITE GROUNDING SYSTEM DESIGN.

7. ANTENNA AND COAX SWEEP TESTS PER EXHIBIT: ANTENNA TRANSMISSION LINE ACCEPTANCE STANDARDS.

8. GROUNDING AT ANTENNA MASTS FOR GPS AND ANTENNAS

9. ALL OTHER TESTS REQUIRED BY COMPANY OR JURISDICTION.

3.3 REQUIRED INSPECTIONS

A. SCHEDULE INSPECTIONS WITH COMPANY REPRESENTATIVE.

B. CONDUCT INSPECTIONS INCLUDING BUT NOT LIMITED TO THE FOLLOWING:

1. CHANGING SYSTEM INSTALLATION PRIOR TO PART CONCRETEMENT OR SPRINT REPRESENTATIVE.

2. FORMING FOR CONCRETE AND REBAR PLACEMENT PRIOR TO POUR FOR SPRINT REPRESENTATIVE.

3. COMPARISON OF BACKFILL MATERIALS, AGGREGATE BASE FOR ROADS, PAVES AND ANCHORS, ASPHALT PAVING AND SHIRT BACKFILL FOR CONCRETE AND EXISTING FACILITIES.

4. PRE- AND POST-CONSTRUCTION ROOFTOP AND STRUCTURAL INSPECTIONS ON EXISTING FACILITIES.

5. TOWER ERECTION SECTION STAGING AND PLATFORM ATTACHMENT DOCUMENTED BY DIGITAL PHOTOGRAPHS BY THIRD PARTY AGENCY.

6. ANTENNA ASSEMBLY, DOWN BIT, AND PEE SUNGLASS TOOL SUNSHOOT INSTRUMENTS - ANTEENALIGN ALIGNMENT TOOL (ANT)

5. LINES AND ANTENNA INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).

6. POWER INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).

7. TELCO INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).

8. PFC (OR SHEET) INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).

9. TOWER CONSTRUCTION START DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).

10. TOWER CONSTRUCTION COMPLETE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).

11. SIS AND RAMP EQUIPMENT DELIVERED AT SITE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).

12. NETWORK OPERATIONS HANDOFF CHECKLIST (OIC WALK) COMPLETE (UPLOAD FROM IT) DATE

13. CIVIL CONSTRUCTION COMPLETE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).

14. SITE CONSTRUCTION PROGRESS PHOTOS UNLOADED INTO SMS.

15. COMMISSIONING: PERFORM ALL COMMISSIONING AS REQUIRED BY APPLICABLE AGENCY

16. INTERFEROR: PERFORM ALL INTERFEROR ACTIVITIES AS REQUIRED BY APPLICABLE AGENCY

17. PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION

3.1 REQUIREMENTS FOR TESTING:

A. THIRD PARTY TESTING AGENCY:

1. WHEN THE USE OF A THIRD PARTY INDEPENDENT TESTING AGENCY IS REQUIRED, THE AGENCY THAT IS SELECTED MUST PERFORM SUCH TESTING ON A REGULAR BASIS IN THE STATE WHERE THE PROJECT IS LOCATED AND HAVE A COMPREHENSIVE UNDERSTANDING OF LOCAL AVAILABLE MATERIALS, INCLUDING THE SOIL, ROCK, TYPICAL AND UNUSUAL CONDITIONS.

2. THE THIRD PARTY TESTING AGENCY IS TO BE FAMILIAR WITH THE APPLICABLE LOCAL AND STATE REGULATIONS, PERMITS, EQUIPMENT TO BE USED, AND ASSOCIATED HEALTH AND SAFETY ISSUES.

3. EXPERIENCE IN SOILS, CONCRETE, MASONRY, ASPHALT AND ASPHALT TESTING USING ASTM, AASHTO, AND OTHER METHODS IS NEEDED.

4. EXPERIENCE IN SOILS, CONCRETE, MASONRY, ASPHALT AND ASPHALT TESTING USING ASTM, AASHTO, AND OTHER METHODS IS NEEDED.

3.2 REQUIREMENTS FOR TESTING:

A. CONTRACTOR SHALL ACCOMPLISH TESTING INCLUDING BUT NOT LIMITED TO THE FOLLOWING:

1. CONCRETE CUREMENT BREAK TESTS AS SPECIFIED HEREIN.

2. SPECIAL FINISHES FOR INTERIOR SPACES, IF ANY.

3. ALL EQUIPMENT AND MATERIALS SO IDENTIFIED ON THE CONSTRUCTION DRAWINGS.

4. CHEMICAL GROUNDING DESIGN

D. ALTERNATES: AT THE COMPANY'S REQUEST, ANY ALTERNATES TO THE MATERIALS OR METHODS SPECIFIED SHALL BE SUBMITTED TO SPRINT'S CONSTRUCTION INSPECTOR AND APPROVED ONLY THOSE REQUESTS MADE IN WRITING. NO VERBAL APPROVALS WILL BE CONSIDERED. SUBMITTALS FOR APPROVAL SHALL INCLUDE A STATEMENT OF COST REDUCTION PROPOSED FOR USE OF ALTERNATE PRODUCT.

1.4 TESTS AND INSPECTIONS

A. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CONSTRUCTION TESTS, INSPECTIONS AND PROTECT DOCUMENTATION.

B. CONTRACTOR SHALL ACCOMPLISH TESTING INCLUDING BUT NOT LIMITED TO THE FOLLOWING:

1. COAX SWEEPS AND TOWER TESTS PER EXHIBIT: ANTENNA TRANSMISSION LINE ACCEPTANCE STANDARDS.

2. ANTENNA AND COAX SWEEP TESTS PER EXHIBIT: ANTENNA TRANSMISSION LINE ACCEPTANCE STANDARDS.

3. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CONNECTIONS TO ANY EXISTING FACILITIES. CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ANY AND/OR AS A RESULT OF TESTING.

C. OBTAIN CLOSEOUT DOCUMENTATION INCLUDING, BUT IS NOT LIMITED TO THE FOLLOWING:

1. AS-BUILT DRAWINGS, AS NEEDED, UPLOADED BEFORE ANTENNA ALIGNMENT TOOL CONFORM TO THE IT DATA SHEETS, SWEEP AND TOWER TEST.

2. SCHEDULE INGRESS PHOTOGRAPHS OF TOWER TOP AND INACCESSIBLE SERIALIZED EQUIPMENT

3. ALL AVAILABLE JURISDICTIONAL INFORMATION

4. PFC SCAN OF REBAR/REINFORCEMENT IN FIELD

1. PERFORM ANY REQUIRED SITE ENVIRONMENTAL MITIGATION.

2. PREPARE GROUND STIES, PRODUCE DE-GRUBBERS AND ROUGH AND FINAL FINISHING, AND COMPAHO SURFACE TREATMENTS.

3. MANAGE AND CONDUCT ALL ACTIVITIES FOR INSTALLATION OF UTILITIES INCLUDING ELECTRICAL AND TELCO BACKFILL.

4. INSTALL UNDERGROUND FACILITIES INCLUDING UNDERGROUND POWER AND COMMUNICATIONS CONDUITS, AND UNDERGROUND GROUNDING SYSTEM.

5. INSTALL ABOVE GROUND GROUNDING SYSTEMS.

6. PROVIDE NEW HVAC INSTALLATIONS AND MODIFICATIONS.

7. INSTALL "H-FRAMES", CABINETS AND SHELTRES AS INDICATED.

8. INSTALL ROADS, ACCESS WAYS, CURBS AND DRAINS AS INDICATED.

9. ACCOMPLISH REQUIRED MODIFICATION OF EXISTING FACILITIES.

10. PROVIDE ANTENNA SUPPORT STRUCTURE FOUNDATIONS.

11. PROVIDE SLABS AND EQUIPMENT PLATFORMS.

12. INSTALL COMPOUND FINISH, SIGHT SHIELDING, LANDSCAPING AND ACCESS BARRIERS.

13. PERFORM INSPECTION AND MATERIAL TESTING AS REQUIRED HEREINAFTER.

14. CONDUCT SITE RESISTANCE TO EARTH TESTING AS REQUIRED HEREINAFTER.

15. INSTALL FIXED GENERATOR SETS AND OTHER STANDBY POWER SOLUTIONS.

16. INSTALL TOWERS, ANTENNA SUPPORT STRUCTURES AND PLATFORMS ON EXISTING TOWERS AS REQUIRED.

17. INSTALL CELL SITE FUNDIC, MICROWAVE, GPS, COMVAL, MANLINE, ANTENNAS, AND/OR OTHER TOWER TOP ACCESSORIES, LOW NOISE AMPLIFIERS AND RELATED EQUIPMENT.

18. PERFORM DOCUMENT AND CLOSE OUT ANY CONSTRUCTION CONTROL DOCUMENTS THAT MAY BE REQUIRED BY GOVERNMENT AGENCIES AND LANDLORDS.

19. PERFORM ANTENNA AND COAX SWEEP TESTING AND MAKE ANY AND ALL NECESSARY CORRECTIONS.

20. REMAIN ON SITE MOBILIZED THROUGHOUT HAND-OFF AND INTERGRATION TO ASSIST AS NEEDED UNTIL SITE IS DEEMED SUBSTANTIALLY COMPLETE AND PLACED "ON AIR."

3.2 GENERAL REQUIREMENTS FOR CIVIL CONSTRUCTION:

A. CONTRACTOR SHALL KEEP THE SITE FREE FROM OBSTACLES, WASTE MATERIAL, DEBRIS AND TRASH AT ALL TIMES. THE CONTRACTOR SHALL MAINTAIN ACCESS TO ALL UTILITIES, FACILITIES, AND SURPLUS MATERIALS.

B. EQUIPMENT ROOMS SHALL AT ALL TIMES BE MAINTAINED "ROOM CLEAN AND CLEAR OF DEBRIS.

C. CONTRACTOR SHALL TAKE ALL REASONABLE PRECAUTIONS TO DISCOVER AND LOCATE ANY HAZARDOUS CONDITION.

1. IN THE EVENT CONTRACTOR ENCOUNTERS ANY HAZARDOUS CONDITION WHICH MAY BE AFFECTIVE TO THE WORK, CONTRACTOR SHALL IMMEDIATELY STOP WORK AND NOTIFY COMPANY IN WRITING. THE WORK IN THE AFFECTED AREA SHALL NOT BE RESUMED EXCEPT BY WRITTEN NOTIFICATION BY COMPANY.

2. CONTRACTOR AGREES TO LEAVE CARE WHILE ON THE SITE AND SHALL NOT TAKE ANY ACTION THAT COULD BE A RESULT IN OR CAUSE THE HAZARDOUS CONDITION TO BECOME A LIABILITY TO THE ENVIRONMENT, OR TO FURTHER EXPOSE INDIVIDUALS TO THE HAZARD.

D. CONTRACTOR'S ACTIVITIES SHALL BE RESTRICTED TO THE PROJECT LIMITS. SHOULD THE CONTRACTOR BE REQUIRED TO WORK OUTSIDE PROJECT LIMITS, CONTRACTOR SHALL IMMEDIATELY RETURN THEM TO ORIGINAL CONDITION.

E. CONDUCT TESTING AS REQUIRED HEREIN.

3.3 DELIVERABLES:

A. CONTRACTOR SHALL REVIEW, APPROVE, AND SUBMIT TO SPRINT SHOP DRAWINGS, PRODUCE DATA SHEETS, AND SUBMIT SUBMITTALS AS REQUIRED HEREINAFTER.

B. PROVIDE DOCUMENTATION INCLUDING, BUT NOT LIMITED TO THE FOLLOWING. CONTRACTOR SHALL BE FURNISHED IN ORIGINAL FORMAT AND/OR UNLOADED INTO SIE.

1. ALL CORRESPONDENCE AND PRELIMINARY CONSTRUCTION REPORTS.

2. PROJECT PROGRESS REPORTS.

3. CIVIL CONSTRUCTION START DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).

4. ELECTRICAL SERVICE COMPLETION DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).











PLANS PREPARED FOR:



6500 South Parkway  
Overland Park, Kansas 66201

PLANS PREPARED FOR:



FROM ZERO TO INFINIGY  
The solutions are endless  
1023 MARKET STREET, SUITE 101, ALBANY, NY 12208  
Phone: 518-862-0790 | Fax: 518-862-0713  
www.infinigy.com

PLANNING:



ENGINEERING LICENSE:



OWNER'S NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISION	DESCRIPTION	DATE	BY	REV
1	ISSUE FOR PERMIT			
2	ISSUE FOR PERMIT			
3	ISSUE FOR PERMIT			
4	ISSUE FOR PERMIT			

SITE NAME:  
**PRESTON / TOWN HALL**

SITE LOCATION:  
**CT23XC411**

SITE ADDRESS:  
**389 RT 2  
PRESTON, CT 06365**


SHEET DESCRIPTION:  
**EQUIPMENT &  
MOUNTING DETAILS**

SHEET NUMBER:  
**A-4**

RRH: ALCATEL LUCENT RRH 800MHZ 2-150W

COLOR: LIGHT GREY  
WEIGHT: 53 LBS.


NOTES  
COMPLY WITH MANUFACTURERS INSTRUCTIONS TO ENSURE THAT ALL RRH'S RECEIVE ELECTRICAL POWER WITHIN 24 HOURS OF BEING REMOVED FROM THE MANUFACTURER'S PACKAGING. DO NOT OPEN RRH PACKAGES IN THE WORK



800\_MHZ\_RRH NO SCALE 2

RRH: ALCATEL LUCENT 1900\_MHZ


COLOR: LIGHT GREY  
WEIGHT: 53 LBS.  
(INCLUDING OPTIONAL SOLAR SHIELD)



1900\_MHZ\_RRH NO SCALE 4

RRH: ALCATEL LUCENT TD-RRH8X20


COLOR: LIGHT GREY  
WEIGHT: 70 LBS.



2.5\_GHZ\_RRH NO SCALE 1

ANTENNA RFS APXSP18-C-A20

RADIOME MATERIAL: ASA  
COLOR: LIGHT GREY  
DIMENSIONS: 72"x11.8"x7.8"  
WEIGHT: 57 lbs



800/1900\_ANTENNA NO SCALE 3

NOTES  
COMPLY WITH MANUFACTURERS INSTRUCTIONS TO ENSURE THAT ALL RRH'S RECEIVE ELECTRICAL POWER WITHIN 24 HOURS OF BEING REMOVED FROM THE MANUFACTURER'S PACKAGING. DO NOT OPEN RRH PACKAGES IN THE WORK



PLANS PREPARED FOR:



1820 South Parkway  
Oxford, CT, 06320

PLANS PREPARED BY:

**INFINIGY**  
FROM ZERO TO INFINIGY  
The solutions are endless  
1822 North Main Street  
Preston, CT 06355  
Phone: 313-412-7750 Fax: 313-412-7753  
www.infinigy.com

PLANNING:

**CROWN CASTLE**

ENGINEERING LICENSE:



DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT. AND MAY NOT BE REPRODUCED, DISSEMINATED OR DISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV

PROJECT NAME:  
PRESTON / TOWN HALL

SITE ADDRESS:

CT23XC411

SHEET ADDRESS:


389 RT 2  
PRESTON, CT 06355

SHEET DESCRIPTION:  
PLUMBING DIAGRAM

SHEET NUMBER:

A-6

ALU 211 DT465B-2XR & APXVSP18-C-A20 wo Filters



NO SCALE

PLUMBING DIAGRAM

1

PLANS PREPARED FOR:



8550 South Parkway  
Overland Park, Kansas 66201

PLANS PREPARED BY:  
**INFINIGY**  
FROM ZERO TO INFINIGY  
ITS BUILDING AND ADDRESS  
1011 Massachusetts Ave. | 1st Fl. | Boston, MA 02118  
PH: 617-452-3734 | FAX: 617-452-3733  
WWW.INFINIGY.COM  
JOB NO: 1011-001



ENGINEERING LICENSE:  
STEVEN J. PIRO  
LICENSE NO. 14824  
STATE OF CONNECTICUT  
REGISTERED PROFESSIONAL ENGINEER  
EXPIRES 06/30/2018

REVISIONS:

NO.	DESCRIPTION	DATE	BY	REV.
1	ISSUED FOR CONSTRUCTION			0
2				1
3				0

SITE NAME:  
**PRESTON / TOWN HALL**

SITE ADDRESS:  
**CT23XC411**

389 RT2  
PRESTON, CT 06365

SHEET DESCRIPTION:  
**ELECTRICAL & GROUNDING DETAILS**

SHEET NUMBER:  
**E-1**

### FINAL EQUIPMENT CONFIGURATION

SECTOR	ANTENNA MANUFACTURER	ANTENNA MODEL	RAD CENTER	RAD ASSEMBLY	ANTENNA MAKE AND MODEL
1	RFS	AP100P18-C-AB	15P	0"	02-ALU1000M1Z-250-AB 07-ALU1000M1Z-KAS0P-COM1Z 07-ALU1250M1Z-RR00P-02S
2	RFS	AP100P18-C-AB	15P	0"	02-ALU1000M1Z-250-AB 07-ALU1000M1Z-KAS0P-COM1Z 07-ALU1250M1Z-RR00P-02S
3	RFS	AP100P18-C-AB	15P	0"	02-ALU1000M1Z-250-AB 07-ALU1000M1Z-KAS0P-COM1Z 07-ALU1250M1Z-RR00P-02S


### FEEDER CABLES

MANUFACTURER	MODEL	LENGTH	UNIT	QTY
RFS	AP100P18-C-AB	15P	200'	0
RFS	AP100P18-C-AB	15P	200'	0
RFS	AP100P18-C-AB	15P	200'	0

NOTES:  
1. CONTRACTOR TO VERIFY ANTENNA ASSEMBLY INFORMATION IS THE SAME AS THE INFORMATION PROVIDED IN THE DRAWINGS.  
2. CONTRACTOR TO VERIFY CABLE LENGTHS PRIOR TO CONSTRUCTION.


ANTENNA/CABLE SCHEDULE

NO SCALE 1



TYPICAL ANTENNA GROUNDING PLAN

NO SCALE 2



TYPICAL EQUIPMENT GROUNDING PLAN (ELEVATION)

NO SCALE 3





Date: **April 10, 2018**

James Williams  
Crown Castle  
3530 Toringdon Way, Suite 300  
Charlotte, NC 28277



Tower Engineering Professionals  
326 Tryon Road  
Raleigh, NC 27603  
(919) 661-6351

**Subject: Structural Modification Analysis Report**

**Carrier Designation:** *Sprint PCS Co-Locate*  
**Carrier Site Number:** CT23XC411  
**Carrier Site Name:** CT23XC411

**Crown Castle Designation:** **Crown Castle BU Number:** 876360  
**Crown Castle Site Name:** Preston / Town Hall  
**Crown Castle JDE Job Number:** 447234  
**Crown Castle Work Order Number:** 1532088  
**Crown Castle Order Number:** 397067 Rev. 1

**Engineering Firm Designation:** **TEP Project Number:** 25620.161151

**Site Data:** **389 Rt. 2, Preston, New London County, CT 06365**  
**Latitude 41° 29' 25.25", Longitude -71° 59' 29.55"**  
**147 Foot - Monopole Tower**

Dear James Williams,

Tower Engineering Professionals is pleased to submit this "**Structural Modification Analysis Report**" to determine the structural integrity of the above mentioned tower. This analysis has been performed in accordance with the Crown Castle Structural 'Statement of Work' and the terms of Crown Castle Purchase Order Number 1148253, in accordance with order 397067, revision 1.

The purpose of the analysis is to determine acceptability of the tower stress level. Based on our analysis we have determined the tower stress level for the structure and foundation, under the following load case, to be:

LC4.7: Existing/Reserved + Proposed Equipment with Proposed Modifications **Sufficient Capacity**  
Note: See Table I and Table II for the proposed and existing/reserved loading, respectively.

This analysis has been performed in accordance with the 2016 Connecticut State Building Code (2012 International Building Code) based upon an ultimate 3-second gust wind speed of 135 mph converted to a nominal 3-second gust wind speed of 105 mph per Section 1609.3 and Appendix N as required for use in the TIA-222-G Standard per Exception #5 of Section 1609.1.1. Exposure Category C and Risk Category II were used in this analysis.


All modifications and equipment proposed in this report shall be installed in accordance with the appurtenances listed in Tables 1 and 2 and the attached drawings for the determined available structural capacity to be effective.

We at Tower Engineering Professionals appreciate the opportunity of providing our continuing professional services to you and Crown Castle. If you have any questions or need further assistance on this or any other projects please give us a call.

Structural analysis prepared by: Riley Eaton, P.E. / JLW

Respectfully submitted by:

Aaron T. Rucker, P.E.



04/11/2018

## TABLE OF CONTENTS

### 1) INTRODUCTION

### 2) ANALYSIS CRITERIA

Table 1 - Proposed Antenna and Cable Information

Table 2 - Existing/Reserved Antenna and Cable Information

Table 3 - Design Antenna and Cable Information

### 3) ANALYSIS PROCEDURE

Table 4 - Documents Provided

3.1) Analysis Method

3.2) Assumptions

### 4) ANALYSIS RESULTS

Table 5 - Section Capacity (Summary)

Table 6 - Tower Component Stresses vs. Capacity

4.1) Recommendations

### 5) APPENDIX A

tnxTower Output

### 6) APPENDIX B

Base Level Drawing

### 7) APPENDIX C

Additional Calculations

### 8) APPENDIX D

Structural Design Drawings

## 1) INTRODUCTION

This tower is a 147-ft monopole tower designed by Engineered Endeavors in May of 2000. The tower was originally designed for a wind speed of 90 mph per TIA/EIA-222-F for the appurtenances listed in Table 3. The tower has been modified multiple times in the past to accommodate additional loading. TEP visited the site in April of 2013 to perform a post modification inspection. All information provided to TEP was assumed to be accurate and complete.

## 2) ANALYSIS CRITERIA

The analysis has been performed in accordance with the ANSI/TIA-222-G-2-2009 Structural Standard for Antenna Supporting Structures and Antennas – Addendum 2 using a nominal 3-second gust wind speed of 105 mph with no ice, 50 mph with 0.75 inch ice thickness, and 60 mph under service loads with the following design criteria:

Type of Analysis: **Rigorous Structural Analysis**

Classification of Structure: **Class II**

Exposure Category: **Exposure C**

Topographic Category: **Category 1**

Earthquake Category: **Not Considered**

Earthquake effects may be ignored per this standard for site locations where  $S_s$  does not exceed 1.0. (Preston  $S_s = 0.167$ ).

**Table 1 - Proposed Antenna and Cable Information**

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)	Note
147.0	150.0	3	RFS Celwave	APXVSP18-C-A20	4	1-1/4	1
		3	Commscope	DT465B-2XR			
		3	Alcatel Lucent	PCS 1900MHZ 4X45W-65MHZ			
		3	Alcatel Lucent	RRH2X50-800			
		3	Alcatel Lucent	TD-RRH8X20-25			
	147.0	1	SitePro 1	HRK12			
		1	SitePro 1	RMQP-496-HK			

Notes:

- 1) See "Appendix B - Base Level Drawing" for assumed feed line configuration.

**Table 2 - Existing/Reserved Antenna and Cable Information**

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)	Note
147.0	147.0	6	Decibel	DB978H90T2E-M w/ Mount Pipe	6	1-5/8	3
		1	Tower Mounts	Platform Mount [LP 601-1]			

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)	Note
136.0	138.0	6	Antel	LPA-80080/4CF w/ Mount Pipe	2	1-5/8	2
		6	Andrew	SBNHH-1D65A w/ Mount Pipe			
		3	Alcatel Lucent	RRH4X45-AWS4 B66			
		3	Alcatel Lucent	RRH2x60-700			
		2	RFS Celwave	DB-B1-6C-12AB-0Z			
	136.0	1	Tower Mounts	Platform Mount [LP 601-1]	12	1-5/8	1
129.0	129.0	3	Ericsson	AIR 21 B2A B4P w/ Mount Pipe	7	1-5/8	1
		3	Ericsson	AIR 21 B4A B2P w/ Mount Pipe			
		3	Andrew	LNx-6515DS-VTM w/ Mount Pipe			
		3	Ericsson	KRY 112 144/1			
		3	Ericsson	RRUS 11 B12			
		1	Tower Mounts	Platform Mount [LP 1201-1]			
120.0	120.0	6	Ericsson	TME-RRUS-11	-	-	1
		1	Tower Mounts	Side Arm Mount [SO 102-3]			
118.0	118.0	3	KMW Communications	AM-X-WM-17-65-00T w/ Mount Pipe	3 6	3/8 1-1/4	1
		3	Powerwave Technologies	RA21.7770.00 w/ Mount Pipe			
		6	Powerwave Technologies	LGP21401			
		1	Raycap	DC6-48-60-18-8F			
		1	Tower Mounts	Platform Mount [LP 303-1]			
50.0	51.0	1	Lucent	KS24019-L112A	1	1/2	1
	50.0	1	Tower Mounts	Side Arm Mount [SO 701-1]			
45.0	46.0	1	Lucent	KS24019-L112A	1	1/2	1
	45.0	1	Tower Mounts	Side Arm Mount [SO 701-1]			

- Notes:  
 1) Existing equipment  
 2) Reserved equipment  
 3) Existing equipment to be removed; not considered in this analysis

**Table 3 - Design Antenna and Cable Information**

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)
147.0	147.0	12	Decibel	DB980	-	-
137.0	137.0	12	Decibel	DB980	-	-
127.0	127.0	12	Decibel	DB980	-	-

### 3) ANALYSIS PROCEDURE

**Table 4 - Documents Provided**

Document	Remarks	Reference	Source
Geotechnical Report	FDH	2192501	CCISites
Tower Foundation Drawings	Engineered Endeavors	1615411	CCISites
Tower Manufacturer Drawings	Engineered Endeavors	1615372	CCISites
Tower Reinforcement Drawings	Vertical Solutions	2331612	CCISites
Post Modification Inspection	Vertical Solutions	2331610	CCISites
Tower Reinforcement Drawings	PJF	3846963	CCISites
Post Modification Inspection	Tower Engineering Professionals	3846952	CCISites
Tower Reinforcement Drawings	PJF	5573224	CCISites
Post Modification Inspection	FDH	5995667	CCISites
Tower Reinforcement Drawings	PJF	5959061	CCISites
Post Modification Inspection	Engineered Tower Solutions	6072770	CCISites
Previous Structural Analysis	Tower Engineering Professionals	7355135	CCISites

#### 3.1) Analysis Method

tnxTower (version 7.0.5.1), a commercially available analysis software package, was used to create a three-dimensional model of the tower and calculate member stresses for various loading cases. Selected output from the analysis is included in Appendix A.

tnxTower was used to determine the loads on the modified structure. Additional calculations were performed to determine the stresses in the pole and in the reinforcing elements. These calculations are presented in Appendix C.

#### 3.2) Assumptions

- 1) The tower and foundation were built in accordance with the manufacturer's specifications.
- 2) The tower and foundation have been maintained in accordance with the manufacturer's specification.
- 3) The configuration of antennas, transmission cables, mounts and other appurtenances are as specified in Tables 1 and 2, and "Appendix B – Base Level Drawing".
- 4) All tower components are in sufficient condition to carry their full design capacity.
- 5) Serviceability with respect to antenna twist, tilt, roll, or lateral translation, is not checked and is left to the carrier or tower owner to ensure conformance.
- 6) All antenna mounts and mounting hardware are structurally sufficient to carry the full design capacity requirements of appurtenance wind area and weight as provided by the original manufacturer specifications. It is the carrier's responsibility to ensure compliance to the structural limitations of the existing and/or proposed antenna mounts. TEP did not analyze antennas supporting mounts as part of this structural analysis report.

This analysis may be affected if any assumptions are not valid or have been made in error. Tower Engineering Professionals should be notified to determine the effect on the structural integrity of the tower.

4) ANALYSIS RESULTS

Table 5 - Section Capacity (Summary)<sup>1</sup>

Elevation (ft)	Component Type	Size	Critical Element	% Capacity	Pass / Fail
147 - 142	Pole	TP17.326x16.25x0.1875	Pole	20.2%	Pass
142 - 137	Pole	TP18.402x17.326x0.1875	Pole	31.4%	Pass
137 - 132	Pole	TP19.478x18.402x0.1875	Pole	51.9%	Pass
132 - 127	Pole	TP20.553x19.478x0.1875	Pole	71.6%	Pass
127 - 123.62	Pole	TP21.98x20.553x0.1875	Pole	85.7%	Pass
123.62 - 118.62	Pole	TP21.856x20.78x0.25	Pole	78.9%	Pass
118.62 - 113.62	Pole	TP22.932x21.856x0.25	Pole	91.9%	Pass
113.62 - 112.41	Pole	TP23.192x22.932x0.25	Pole	94.7%	Pass
112.41 - 112.16	Pole + Reinf.	TP23.246x23.192x0.5375	Reinf. 21 Tension Rupture	82.4%	Pass
112.16 - 110.5	Pole + Reinf.	TP23.603x23.246x0.525	Reinf. 21 Tension Rupture	86.2%	Pass
110.5 - 110.25	Pole + Reinf.	TP23.657x23.603x0.75	Reinf. 21 Tension Rupture	62.1%	Pass
110.25 - 105.25	Pole + Reinf.	TP24.733x23.657x0.725	Reinf. 21 Tension Rupture	70.1%	Pass
105.25 - 105	Pole + Reinf.	TP24.787x24.733x0.725	Reinf. 21 Tension Rupture	70.5%	Pass
105 - 104.75	Pole + Reinf.	TP24.841x24.787x1	Reinf. 6 Tension Rupture	55.2%	Pass
104.75 - 103.5	Pole + Reinf.	TP25.11x24.841x0.975	Reinf. 6 Tension Rupture	56.7%	Pass
103.5 - 103.25	Pole + Reinf.	TP25.163x25.11x0.75	Reinf. 6 Tension Rupture	72.0%	Pass
103.25 - 98.25	Pole + Reinf.	TP26.239x25.163x0.725	Reinf. 6 Tension Rupture	78.9%	Pass
98.25 - 94.83	Pole + Reinf.	TP26.975x26.239x0.7125	Reinf. 6 Tension Rupture	83.2%	Pass
94.83 - 94.58	Pole + Reinf.	TP27.029x26.975x0.7	Reinf. 6 Tension Rupture	87.2%	Pass
94.58 - 94.17	Pole + Reinf.	TP27.117x27.029x0.6875	Reinf. 6 Tension Rupture	87.7%	Pass
94.17 - 93.82	Pole + Reinf.	TP27.193x27.117x0.775	Reinf. 14 Tension Rupture	77.2%	Pass
93.82 - 93.66	Pole + Reinf.	TP27.227x27.193x0.775	Reinf. 14 Tension Rupture	77.3%	Pass
93.66 - 89.08	Pole + Reinf.	TP29.11x27.227x0.75	Reinf. 14 Tension Rupture	82.3%	Pass
89.08 - 83.91	Pole + Reinf.	TP28.692x27.58x0.8375	Reinf. 14 Tension Rupture	80.5%	Pass
83.91 - 78.91	Pole + Reinf.	TP29.768x28.692x0.8125	Reinf. 14 Tension Rupture	84.5%	Pass
78.91 - 73.91	Pole + Reinf.	TP30.844x29.768x0.8	Reinf. 14 Tension Rupture	88.1%	Pass
73.91 - 68.91	Pole + Reinf.	TP31.919x30.844x0.775	Reinf. 14 Tension Rupture	91.4%	Pass
68.91 - 65.5	Pole + Reinf.	TP32.653x31.919x0.7625	Reinf. 14 Tension Rupture	93.5%	Pass
65.5 - 65.25	Pole + Reinf.	TP32.707x32.653x0.9125	Reinf. 14 Tension Rupture	86.7%	Pass
65.25 - 64.5	Pole + Reinf.	TP32.868x32.707x0.9125	Reinf. 14 Tension Rupture	87.1%	Pass
64.5 - 64.25	Pole + Reinf.	TP32.922x32.868x0.8125	Reinf. 14 Tension Rupture	91.6%	Pass
64.25 - 59.25	Pole + Reinf.	TP33.997x32.922x0.8	Reinf. 14 Tension Rupture	94.4%	Pass
59.25 - 58.58	Pole + Reinf.	TP34.142x33.997x0.7875	Reinf. 14 Tension Rupture	94.8%	Pass
58.58 - 58.33	Pole + Reinf.	TP34.195x34.142x0.85	Reinf. 13 Tension Rupture	85.6%	Pass
58.33 - 57.25	Pole + Reinf.	TP34.428x34.195x0.8375	Reinf. 13 Tension Rupture	86.1%	Pass
57.25 - 57	Pole + Reinf.	TP34.481x34.428x0.85	Reinf. 13 Tension Rupture	85.2%	Pass
57 - 52	Pole + Reinf.	TP35.557x34.481x0.8375	Reinf. 13 Tension Rupture	87.5%	Pass
52 - 49.58	Pole + Reinf.	TP37.19x35.557x0.825	Reinf. 13 Tension Rupture	88.6%	Pass
49.58 - 43.41	Pole + Reinf.	TP36.658x35.33x0.875	Reinf. 13 Tension Rupture	86.8%	Pass
43.41 - 38.41	Pole + Reinf.	TP37.734x36.658x0.8625	Reinf. 13 Tension Rupture	88.4%	Pass
38.41 - 34.5	Pole + Reinf.	TP38.575x37.734x0.85	Reinf. 13 Tension Rupture	89.6%	Pass
34.5 - 34.25	Pole + Reinf.	TP38.629x38.575x1.025	Reinf. 18 Tension Rupture	77.2%	Pass
34.25 - 33.5	Pole + Reinf.	TP38.791x38.629x1.0125	Reinf. 18 Tension Rupture	77.4%	Pass
33.5 - 33.25	Pole + Reinf.	TP38.844x38.791x0.8125	Reinf. 4 Tension Rupture	90.5%	Pass

Elevation (ft)	Component Type	Size	Critical Element	% Capacity	Pass / Fail
33.25 - 29.5	Pole + Reinf.	TP39.651x38.844x0.8	Reinf. 4 Tension Rupture	91.6%	Pass
29.5 - 29.25	Pole + Reinf.	TP39.705x39.651x0.8875	Reinf. 13 Tension Rupture	85.5%	Pass
29.25 - 28.5	Pole + Reinf.	TP39.867x39.705x0.8875	Reinf. 13 Tension Rupture	85.7%	Pass
28.5 - 28.25	Pole + Reinf.	TP39.92x39.867x0.9	Reinf. 4 Tension Rupture	84.5%	Pass
28.25 - 27.48	Pole + Reinf.	TP40.086x39.92x0.9	Reinf. 3 Tension Rupture	84.7%	Pass
27.48 - 27.23	Pole + Reinf.	TP40.14x40.086x0.9	Reinf. 3 Tension Rupture	84.8%	Pass
27.23 - 22.23	Pole + Reinf.	TP41.216x40.14x0.875	Reinf. 3 Tension Rupture	86.0%	Pass
22.23 - 17.23	Pole + Reinf.	TP42.292x41.216x0.875	Reinf. 3 Tension Rupture	87.2%	Pass
17.23 - 12.23	Pole + Reinf.	TP43.368x42.292x0.85	Reinf. 3 Tension Rupture	88.2%	Pass
12.23 - 7.23	Pole + Reinf.	TP44.444x43.368x0.8375	Reinf. 3 Tension Rupture	89.2%	Pass
7.23 - 6.9	Pole + Reinf.	TP44.515x44.444x0.8625	Reinf. 10 Tension Rupture	84.9%	Pass
6.9 - 6.55	Pole + Reinf.	TP44.59x44.515x0.7875	Reinf. 2 Tension Rupture	92.4%	Pass
6.55 - 6.33	Pole + Reinf.	TP44.638x44.59x0.7875	Reinf. 2 Tension Rupture	92.4%	Pass
6.33 - 3.25	Pole + Reinf.	TP45.301x44.638x0.775	Reinf. 2 Tension Rupture	93.0%	Pass
3.25 - 3	Pole + Reinf.	TP45.354x45.301x0.975	Reinf. 2 Tension Rupture	75.5%	Pass
3 - 2.75	Pole + Reinf.	TP45.408x45.354x0.875	Reinf. 2 Tension Rupture	84.0%	Pass
2.75 - 2.5	Pole + Reinf.	TP45.462x45.408x0.875	Reinf. 2 Tension Rupture	84.1%	Pass
2.5 - 2.25	Pole + Reinf.	TP45.516x45.462x0.7625	Reinf. 2 Tension Rupture	93.0%	Pass
2.25 - 2	Pole + Reinf.	TP45.57x45.516x0.75	Reinf. 2 Tension Rupture	92.8%	Pass
2 - 0	Pole + Reinf.	TP46x45.57x0.75	Reinf. 2 Tension Rupture	93.1%	Pass
				<b>Summary</b>	
			Pole	94.7%	Pass
			Reinforcement	94.8%	Pass
			<b>Overall</b>	<b>94.8%</b>	<b>Pass</b>

**Table 6 - Tower Component Stresses vs. Capacity – LC4.7**

Notes	Component	Elevation (ft)	% Capacity	Pass / Fail
1	Original Anchor Rods	-	87.4	Pass
1	Reinforcing Anchor Rods	-	87.7	Pass
1	Base Plate	-	87.8	Pass
1	Base Foundation Soil Interaction	-	59.2	Pass
1	Base Foundation Structural	-	95.5	Pass

<b>Structure Rating (max from all components) =</b>	<b>95.5%</b>
---	--------------

Notes:

- 1) See additional documentation in "Appendix C - Additional Calculations" for calculations supporting the % capacity listed.




#### 4.1) Recommendations

- 1) If the load differs from that described in Tables 1 and 2 of this report, "Appendix B – Base Level Drawing" or the provisions of this analysis are found to be invalid, another structural analysis should be performed.
- 2) The modifications depicted in "Appendix D – Structural Design Drawings" shall be installed and, upon completion, inspected. The tower and its foundation have sufficient capacity to carry the proposed load configuration once the proposed modifications are installed.

**APPENDIX A**  
**TNXTOWER OUTPUT**

Length (ft)	Number of Sides	Thickness (in)	Socket Length (ft)	Top Dia (in)	Bot Dia (in)	Grade	Weight (K)
147.0	18	0.1875	3.2500	40.1348	41.2720	A572-65	142.0
137.0	18	0.1875	4.1700	40.1348	41.2720	A572-65	137.0
132.0	18	0.1875	5.1700	40.1348	41.2720	A572-65	132.0
127.0	18	0.1875	6.1700	40.1348	41.2720	A572-65	127.0
120.4	18	0.1875	7.1700	40.1348	41.2720	A572-65	120.4
118.6	18	0.1875	8.1700	40.1348	41.2720	A572-65	118.6
113.6	18	0.1875	9.1700	40.1348	41.2720	A572-65	113.6
112.2	18	0.1875	10.1700	40.1348	41.2720	A572-65	112.2
110.5	18	0.1875	11.1700	40.1348	41.2720	A572-65	110.5
105.3	18	0.1875	12.1700	40.1348	41.2720	A572-65	105.3
103.5	18	0.1875	13.1700	40.1348	41.2720	A572-65	103.5
98.3	18	0.1875	14.1700	40.1348	41.2720	A572-65	98.3
94.8	18	0.1875	15.1700	40.1348	41.2720	A572-65	94.8
84.9	18	0.1875	16.1700	40.1348	41.2720	A572-65	84.9
78.9	18	0.1875	17.1700	40.1348	41.2720	A572-65	78.9
73.9	18	0.1875	18.1700	40.1348	41.2720	A572-65	73.9
68.9	18	0.1875	19.1700	40.1348	41.2720	A572-65	68.9
65.5	18	0.1875	20.1700	40.1348	41.2720	A572-65	65.5
59.3	18	0.1875	21.1700	40.1348	41.2720	A572-65	59.3
57.3	18	0.1875	22.1700	40.1348	41.2720	A572-65	57.3
52.0	18	0.1875	23.1700	40.1348	41.2720	A572-65	52.0
44.4	18	0.1875	24.1700	40.1348	41.2720	A572-65	44.4
38.4	18	0.1875	25.1700	40.1348	41.2720	A572-65	38.4
34.5	18	0.1875	26.1700	40.1348	41.2720	A572-65	34.5
29.5	18	0.1875	27.1700	40.1348	41.2720	A572-65	29.5
27.5	18	0.1875	28.1700	40.1348	41.2720	A572-65	27.5
22.2	18	0.1875	29.1700	40.1348	41.2720	A572-65	22.2
17.2	18	0.1875	30.1700	40.1348	41.2720	A572-65	17.2
12.2	18	0.1875	31.1700	40.1348	41.2720	A572-65	12.2
7.2	18	0.1875	32.1700	40.1348	41.2720	A572-65	7.2
3.3	18	0.1875	33.1700	40.1348	41.2720	A572-65	3.3
0.0	18	0.1875	34.1700	40.1348	41.2720	A572-65	0.0



**DESIGNED APPURTENANCE LOADING**

TYPE	ELEVATION	TYPE	ELEVATION
APXVSP18-C-A20	147	ERICSSON AIR 21 B4A B2P w/ Mount Pipe	129
APXVSP18-C-A20	147	ERICSSON AIR 21 B4A B2P w/ Mount Pipe	129
DT465B-2XR	147	ERICSSON AIR 21 B4A B2P w/ Mount Pipe	129
DT465B-2XR	147	ERICSSON AIR 21 B4A B2P w/ Mount Pipe	129
PCS 1900MHZ 4X45W-65MHZ	147	LNX-6515DS-VTM w/ Mount Pipe	129
PCS 1900MHZ 4X45W-65MHZ	147	LNX-6515DS-VTM w/ Mount Pipe	129
RRH2X50-800	147	KRY 112 144/1	129
RRH2X50-800	147	RRUS 11 B12	129
RRH2X50-800	147	RRUS 11 B12	129
TD-RRH8X20-25	147	RRUS 11 B12	129
TD-RRH8X20-25	147	RRUS 11 B12	129
TD-RRH8X20-25	147	Platform Mount [LP 1201-1]	129
800MHZ RRH	147	(2) TME-RRUS-11	120
800MHZ RRH	147	(2) TME-RRUS-11	120
800MHZ RRH	147	(2) TME-RRUS-11	120
Platform Mount [LP 301-1]	147	2.4" Dia x 3-ft Mount Pipe	120
Miscellaneous [NA 509-3]	147	2.4" Dia x 3-ft Mount Pipe	120
(2) LPA-80080/4CF w/ Mount Pipe	136	2.4" Dia x 3-ft Mount Pipe	120
(2) LPA-80080/4CF w/ Mount Pipe	136	Side Arm Mount [SO 102-3]	120
(2) SBNHH-1D65A w/ Mount Pipe	136	AM-X-WM-17-65-00T w/ Mount Pipe	118
(2) SBNHH-1D65A w/ Mount Pipe	136	AM-X-WM-17-65-00T w/ Mount Pipe	118
(2) SBNHH-1D65A w/ Mount Pipe	136	AM-X-WM-17-65-00T w/ Mount Pipe	118
RRH4X45-AWS4 B66	136	RA21.7770.00 w/ Mount Pipe	118
RRH4X45-AWS4 B66	136	RA21.7770.00 w/ Mount Pipe	118
RRH4X45-AWS4 B66	136	RA21.7770.00 w/ Mount Pipe	118
RRH2x60-700	136	(2) LGP21401	118
RRH2x60-700	136	(2) LGP21401	118
RRH2x60-700	136	(2) LGP21401	118
(2) DB-B1-6C-12AB-0Z	136	DC8-48-60-18-8F	118
Platform Mount [LP 601-1]	136	Platform Mount [LP 303-1]	118
ERICSSON AIR 21 B2A B4P w/ Mount Pipe	129	KS24019-L112A	50
ERICSSON AIR 21 B2A B4P w/ Mount Pipe	129	1.5" Dia. x 17" Pipe	50
ERICSSON AIR 21 B2A B4P w/ Mount Pipe	129	Side Arm Mount [SO 701-1]	50
ERICSSON AIR 21 B2A B4P w/ Mount Pipe	129	KS24019-L112A	45
ERICSSON AIR 21 B2A B4P w/ Mount Pipe	129	1.5" Dia. x 17" Pipe	45
ERICSSON AIR 21 B2A B4P w/ Mount Pipe	129	Side Arm Mount [SO 701-1]	45

**MATERIAL STRENGTH**

GRADE	Fy	Fu	GRADE	Fy	Fu
A572-65	65 ksi	80 ksi			

**TOWER DESIGN NOTES**

1. Tower is located in New London County, Connecticut.
2. Tower designed for Exposure C to the TIA-222-G Standard.
3. Tower designed for a 105.00 mph basic wind in accordance with the TIA-222-G Standard.
4. Tower is also designed for a 50.00 mph basic wind with 0.75 in ice. Ice is considered to increase in thickness with height.
5. Deflections are based upon a 60.00 mph wind.
6. Tower Structure Class II.
7. Topographic Category 1 with Crest Height of 0.0000 ft



**Tower Engineering Professionals**

326 Tryon Road  
Raleigh, N.C.  
Phone: (919) 661-6351  
FAX: (919) 661-6350

Job: **Preston / Town Hall (BU 876360)**

Project: **TEP No. 25620.161151**

Client: Crown Castle	Drawn by: RKE	App'd:
Code: TIA-222-G	Date: 03/21/18	Scale:
Path:		Dwg Ni

C:\Users\piston\Desktop\Preston Town Hall\03/21/18\25620.161151.dwg

<b>tnxTower</b>  <b>Tower Engineering Professionals</b> 326 Tryon Road Raleigh, N.C. Phone: (919) 661-6351 FAX: (919) 661-6350	<b>Job</b> Preston / Town Hall (BU 876360)	<b>Page</b> 1 of 55
	<b>Project</b> TEP No. 25620.161151	<b>Date</b> 10:12:11 03/21/18
	<b>Client</b> Crown Castle	<b>Designed by</b> RKE

## Tower Input Data

There is a pole section.

This tower is designed using the TIA-222-G standard.

The following design criteria apply:

Tower is located in New London County, Connecticut.

Basic wind speed of 105.00 mph.

Structure Class II.

Exposure Category C.

Topographic Category 1.

Crest Height 0.0000 ft.

Nominal ice thickness of 0.7500 in.

Ice thickness is considered to increase with height.

Ice density of 56.00 pcf.

A wind speed of 50.00 mph is used in combination with ice.

Temperature drop of 50.00 °F.

Deflections calculated using a wind speed of 60.00 mph.

A non-linear (P-delta) analysis was used.

Pressures are calculated at each section.

Stress ratio used in pole design is 1.

Local bending stresses due to climbing loads, feed line supports, and appurtenance mounts are not considered.

## Options

- |  |  |  |
|--|--|--|
| <ul style="list-style-type: none"> <li>Consider Moments - Legs</li> <li>Consider Moments - Horizontals</li> <li>Consider Moments - Diagonals</li> <li>Use Moment Magnification</li> <li>√ Use Code Stress Ratios</li> <li>√ Use Code Safety Factors - Guys</li> <li>Escalate Ice</li> <li>Always Use Max Kz</li> <li>Use Special Wind Profile</li> <li>Include Bolts In Member Capacity</li> <li>Leg Bolts Are At Top Of Section</li> <li>Secondary Horizontal Braces Leg</li> <li>Use Diamond Inner Bracing (4 Sided)</li> <li>SR Members Have Cut Ends</li> <li>SR Members Are Concentric</li> </ul> | <ul style="list-style-type: none"> <li>Distribute Leg Loads As Uniform</li> <li>Assume Legs Pinned</li> <li>√ Assume Rigid Index Plate</li> <li>√ Use Clear Spans For Wind Area</li> <li>Use Clear Spans For KL/r</li> <li>Retension Guys To Initial Tension</li> <li>√ Bypass Mast Stability Checks</li> <li>√ Use Azimuth Dish Coefficients</li> <li>√ Project Wind Area of Appurt.</li> <li>Autocalc Torque Arm Areas</li> <li>Add IBC .6D+W Combination</li> <li>√ Sort Capacity Reports By Component</li> <li>Triangulate Diamond Inner Bracing</li> <li>Treat Feed Line Bundles As Cylinder</li> </ul> | <ul style="list-style-type: none"> <li>Use ASCE 10 X-Brace Ly Rules</li> <li>Calculate Redundant Bracing Forces</li> <li>Ignore Redundant Members in FEA</li> <li>SR Leg Bolts Resist Compression</li> <li>All Leg Panels Have Same Allowable</li> <li>Offset Girt At Foundation</li> <li>√ Consider Feed Line Torque</li> <li>Include Angle Block Shear Check</li> <li>Use TIA-222-G Bracing Resist. Exemption</li> <li>Use TIA-222-G Tension Splice Exemption Poles</li> <li>√ Include Shear-Torsion Interaction</li> <li>Always Use Sub-Critical Flow</li> <li>Use Top Mounted Sockets</li> </ul> |
|--|--|--|

## Tapered Pole Section Geometry

Section	Elevation ft	Section Length ft	Splice Length ft	Number of Sides	Top Diameter in	Bottom Diameter in	Wall Thickness in	Bend Radius in	Pole Grade
L1	147.0000-142.000	5.0000	0.00	18	16.2500	17.3259	0.1875	0.7500	A572-65 (65 ksi)
L2	142.0000-137.000	5.0000	0.00	18	17.3259	18.4017	0.1875	0.7500	A572-65 (65 ksi)

<b>tnxTower</b>  <b>Tower Engineering Professionals</b> 326 Tryon Road Raleigh, N.C. Phone: (919) 661-6351 FAX: (919) 661-6350	<b>Job</b>	Preston / Town Hall (BU 876360)	<b>Page</b>	2 of 55
	<b>Project</b>	TEP No. 25620.161151	<b>Date</b>	10:12:11 03/21/18
	<b>Client</b>	Crown Castle	<b>Designed by</b>	RKE

Section	Elevation ft	Section Length ft	Splice Length ft	Number of Sides	Top Diameter in	Bottom Diameter in	Wall Thickness in	Bend Radius in	Pole Grade
L3	137.0000-132.000	5.0000	0.00	18	18.4017	19.4776	0.1875	0.7500	A572-65 (65 ksi)
L4	132.0000-127.000	5.0000	0.00	18	19.4776	20.5534	0.1875	0.7500	A572-65 (65 ksi)
L5	127.0000-120.370	6.6300	3.25	18	20.5534	21.9800	0.1875	0.7500	A572-65 (65 ksi)
L6	120.3700-118.620	5.0000	0.00	18	20.7800	21.8559	0.2500	1.0000	A572-65 (65 ksi)
L7	118.6200-113.620	5.0000	0.00	18	21.8559	22.9319	0.2500	1.0000	A572-65 (65 ksi)
L8	113.6200-112.410	1.2100	0.00	18	22.9319	23.1923	0.2500	1.0000	A572-65 (65 ksi)
L9	112.4100-112.160	0.2500	0.00	18	23.1923	23.2461	0.5375	2.1500	A572-65 (65 ksi)
L10	112.1600-110.500	1.6600	0.00	18	23.2461	23.6033	0.5250	2.1000	A572-65 (65 ksi)
L11	110.5000-110.250	0.2500	0.00	18	23.6033	23.6571	0.7500	3.0000	A572-65 (65 ksi)
L12	110.2500-105.250	5.0000	0.00	18	23.6571	24.7330	0.7250	2.9000	A572-65 (65 ksi)
L13	105.2500-105.000	0.2500	0.00	18	24.7330	24.7868	0.7250	2.9000	A572-65 (65 ksi)
L14	105.0000-104.750	0.2500	0.00	18	24.7868	24.8406	1.0000	4.0000	A572-65 (65 ksi)
L15	104.7500-103.500	1.2500	0.00	18	24.8406	25.1096	0.9750	3.9000	A572-65 (65 ksi)
L16	103.5000-103.250	0.2500	0.00	18	25.1096	25.1634	0.7500	3.0000	A572-65 (65 ksi)
L17	103.2500-98.250	5.0000	0.00	18	25.1634	26.2394	0.7250	2.9000	A572-65 (65 ksi)
L18	98.2500-94.830	3.4200	0.00	18	26.2394	26.9753	0.7125	2.8500	A572-65 (65 ksi)
L19	94.8300-94.580	0.2500	0.00	18	26.9753	27.0291	0.7000	2.8000	A572-65 (65 ksi)
L20	94.5800-94.170	0.4100	0.00	18	27.0291	27.1173	0.6875	2.7500	A572-65 (65 ksi)
L21	94.1700-93.820	0.3500	0.00	18	27.1173	27.1927	0.7750	3.1000	A572-65 (65 ksi)
L22	93.8200-93.660	0.1600	0.00	18	27.1927	27.2271	0.7750	3.1000	A572-65 (65 ksi)
L23	93.6600-84.910	8.7500	4.17	18	27.2271	29.1100	0.7500	3.0000	A572-65 (65 ksi)
L24	84.9100-83.910	5.1700	0.00	18	27.5800	28.6922	0.8375	3.3500	A572-65 (65 ksi)
L25	83.9100-78.910	5.0000	0.00	18	28.6922	29.7679	0.8125	3.2500	A572-65 (65 ksi)
L26	78.9100-73.910	5.0000	0.00	18	29.7679	30.8436	0.8000	3.2000	A572-65 (65 ksi)
L27	73.9100-68.910	5.0000	0.00	18	30.8436	31.9192	0.7750	3.1000	A572-65 (65 ksi)
L28	68.9100-65.500	3.4100	0.00	18	31.9192	32.6528	0.7625	3.0500	A572-65 (65 ksi)
L29	65.5000-65.250	0.2500	0.00	18	32.6528	32.7066	0.9125	3.6500	A572-65 (65 ksi)
L30	65.2500-64.500	0.7500	0.00	18	32.7066	32.8680	0.9125	3.6500	A572-65 (65 ksi)
L31	64.5000-64.250	0.2500	0.00	18	32.8680	32.9218	0.8125	3.2500	A572-65 (65 ksi)
L32	64.2500-59.250	5.0000	0.00	18	32.9218	33.9974	0.8000	3.2000	A572-65 (65 ksi)
L33	59.2500-58.580	0.6700	0.00	18	33.9974	34.1416	0.7875	3.1500	A572-65



<b>tnxTower</b>  <b>Tower Engineering Professionals</b> 326 Tryon Road Raleigh, N.C. Phone: (919) 661-6351 FAX: (919) 661-6350	<b>Job</b> Preston / Town Hall (BU 876360)	<b>Page</b> 4 of 55
	<b>Project</b> TEP No. 25620.161151	<b>Date</b> 10:12:11 03/21/18
	<b>Client</b> Crown Castle	<b>Designed by</b> RKE

Section	Elevation	Section Length	Splice Length	Number of Sides	Top Diameter	Bottom Diameter	Wall Thickness	Bend Radius	Pole Grade
	ft	ft	ft		in	in	in	in	
L64	2.0000-0.0000	2.0000		18	45.5696	46.0000	0.7500	3.0000	A572-65 (65 ksi)

### Tapered Pole Properties

Section	Tip Dia.	Area	I	r	C	I/C	J	I/Q	w	w/t
	in	in <sup>2</sup>	in <sup>4</sup>	in	in	in <sup>3</sup>	in <sup>4</sup>	in <sup>2</sup>	in	
L1	16.5007	9.5592	311.5911	5.7022	8.2550	37.7457	623.5922	4.7805	2.5300	13.493
	17.5931	10.1995	378.4888	6.0841	8.8015	43.0026	757.4756	5.1007	2.7194	14.503
L2	17.5931	10.1995	378.4888	6.0841	8.8015	43.0026	757.4756	5.1007	2.7194	14.503
	18.6856	10.8397	454.3354	6.4660	9.3481	48.6021	909.2686	5.4209	2.9087	15.513
L3	18.6856	10.8397	454.3354	6.4660	9.3481	48.6021	909.2686	5.4209	2.9087	15.513
	19.7780	11.4800	539.6927	6.8480	9.8946	54.5442	1080.0956	5.7411	3.0981	16.523
L4	19.7780	11.4800	539.6927	6.8480	9.8946	54.5442	1080.0956	5.7411	3.0981	16.523
	20.8705	12.1203	635.1226	7.2299	10.4411	60.8289	1271.0809	6.0613	3.2874	17.533
L5	20.8705	12.1203	635.1226	7.2299	10.4411	60.8289	1271.0809	6.0613	3.2874	17.533
	22.3191	12.9693	778.1562	7.7363	11.1658	69.6908	1557.3364	6.4859	3.5385	18.872
L6	21.8107	16.2906	867.4635	7.2881	10.5562	82.1754	1736.0685	8.1468	3.2173	12.869
	22.1931	17.1443	1011.1241	7.6701	11.1028	91.0691	2023.5786	8.5738	3.4066	13.627
L7	22.1931	17.1443	1011.1241	7.6701	11.1028	91.0691	2023.5786	8.5738	3.4066	13.627
	23.2857	17.9981	1169.8296	8.0521	11.6494	100.4197	2341.1985	9.0008	3.5960	14.384
L8	23.2857	17.9981	1169.8296	8.0521	11.6494	100.4197	2341.1985	9.0008	3.5960	14.384
	23.5501	18.2047	1210.5815	8.1445	11.7817	102.7512	2422.7559	9.1041	3.6418	14.567
L9	23.5501	18.2047	1210.5815	8.1445	11.7817	102.7512	2422.7559	9.1041	3.6418	14.567
	23.6047	18.7414	1252.0186	8.0615	11.8090	103.7367	2501.3583	9.1344	3.1453	5.852
L10	23.6047	18.7414	1252.0186	8.0615	11.8090	103.7367	2501.3583	9.1344	3.1453	5.852
	23.9674	19.8613	1469.3938	8.0660	11.8090	103.7367	2501.3583	9.1344	3.1673	6.033
L11	23.9674	19.8613	1469.3938	8.0660	11.8090	103.7367	2501.3583	9.1344	3.1673	6.033
	24.0220	20.4023	1589.6482	8.1129	11.9905	105.3751	2618.0198	9.2703	2.8342	3.779
L12	24.0220	20.4023	1589.6482	8.1129	11.9905	105.3751	2618.0198	9.2703	2.8342	3.779
	24.0220	21.1146	1702.0105	8.1409	12.0178	106.7348	2691.6343	9.3901	2.8876	3.983
L13	24.0220	21.1146	1702.0105	8.1409	12.0178	106.7348	2691.6343	9.3901	2.8876	3.983
	25.1146	22.461	1923.0218	8.5229	12.5644	112.925	2851.3372	9.6283	3.0770	4.244
L14	25.1146	22.461	1923.0218	8.5229	12.5644	112.925	2851.3372	9.6283	3.0770	4.244
	25.1692	23.3699	2120.1270	8.5420	12.5917	113.6502	2885.5832	9.6902	3.0865	4.257
L15	25.1692	23.3699	2120.1270	8.5420	12.5917	113.6502	2885.5832	9.6902	3.0865	4.257
	25.2238	24.558	2314.5666	8.4723	12.6190	114.1545	2936.1263	9.7349	2.6560	2.724
L16	25.2238	24.558	2314.5666	8.4723	12.6190	114.1545	2936.1263	9.7349	2.6560	2.724
	25.4970	26.6882	2596.2996	8.5678	12.7557	116.8901	3099.8314	9.7351	2.7033	2.773
L17	25.4970	26.6882	2596.2996	8.5678	12.7557	116.8901	3099.8314	9.7351	2.7033	2.773
	25.5516	27.9881	2847.2756	8.6477	12.7557	117.8108	3170.2715	9.7995	3.0993	4.132
L18	25.5516	27.9881	2847.2756	8.6477	12.7557	117.8108	3170.2715	9.7995	3.0993	4.132
	25.5516	28.2365	2923.2794	8.6756	12.7830	118.9467	3242.1423	9.8236	3.1528	4.349
L19	25.5516	28.2365	2923.2794	8.6756	12.7830	118.9467	3242.1423	9.8236	3.1528	4.349
	26.6442	28.7124	2982.7729	9.0576	13.3296	122.2594	3363.8996	9.3618	3.3421	4.61
L20	26.6442	28.7124	2982.7729	9.0576	13.3296	122.2594	3363.8996	9.3618	3.3421	4.61
	26.6442	29.7284	3252.4964	9.0620	13.3296	123.5371	3411.2462	9.8697	3.3641	4.722
L21	26.6442	29.7284	3252.4964	9.0620	13.3296	123.5371	3411.2462	9.8697	3.3641	4.722
	27.3915	29.3927	3175.5098	9.3233	13.7035	127.6790	3578.297	9.7020	3.4937	4.903
L22	27.3915	29.3927	3175.5098	9.3233	13.7035	127.6790	3578.297	9.7020	3.4937	4.903
	27.4461	28.4980	3123.3160	9.3468	13.7308	128.1261	3593.3734	9.2546	3.5251	5.036
L23	27.4461	28.4980	3123.3160	9.3468	13.7308	128.1261	3593.3734	9.2546	3.5251	5.036
	27.4461	27.4807	3038.9983	9.3513	13.7308	128.9853	3593.3734	9.2546	3.5471	5.159
L24	27.4461	27.4807	3038.9983	9.3513	13.7308	128.9853	3593.3734	9.2546	3.5471	5.159
	27.5357	27.6732	3089.8006	9.3826	13.7756	129.4792	3608.2984	9.8421	3.5627	5.182
L25	27.5357	27.6732	3089.8006	9.3826	13.7756	129.4792	3608.2984	9.8421	3.5627	5.182
	27.6121	24.9835	2729.6623	9.3783	13.8139	131.7760	3746.8639	9.4979	3.4219	4.415
L26	27.6121	24.9835	2729.6623	9.3783	13.8139	131.7760	3746.8639	9.4979	3.4219	4.415
	27.6471	25.0682	2752.0941	9.3905	13.8314	132.8733	3771.7569	9.5403	3.4280	4.423
L27	27.6471	25.0682	2752.0941	9.3905	13.8314	132.8733	3771.7569	9.5403	3.4280	4.423
	27.6471	26.0287	2882.3405	9.3994	13.8314	133.6002	3771.7569	9.5403	3.4720	4.629
L28	27.6471	26.0287	2882.3405	9.3994	13.8314	133.6002	3771.7569	9.5403	3.4720	4.629
	29.5591	27.5110	2860.0032	10.0678	14.7879	143.8936	4172.0329	9.7619	3.8034	5.071
L29	29.5591	27.5110	2860.0032	10.0678	14.7879	143.8936	4172.0329	9.7619	3.8034	5.071
	28.9164	21.0876	2422.9598	9.4936	14.0106	145.4344	4285.3710	9.5505	3.3801	4.036
L30	28.9164	21.0876	2422.9598	9.4936	14.0106	145.4344	4285.3710	9.5505	3.3801	4.036
	29.1349	24.0442	2258.1586	9.8884	14.5757	149.9644	4525.8676	9.0291	3.5758	4.27
L31	29.1349	24.0442	2258.1586	9.8884	14.5757	149.9644	4525.8676	9.0291	3.5758	4.27
	29.1349	21.8984	2060.4737	9.8973	14.5757	148.4017	4413.2377	9.9560	3.6198	4.455







<b>tnxTower</b>  <b>Tower Engineering Professionals</b> 326 Tryon Road Raleigh, N.C. Phone: (919) 661-6351 FAX: (919) 661-6350	<b>Job</b> Preston / Town Hall (BU 876360)	<b>Page</b> 7 of 55
	<b>Project</b> TEP No. 25620.161151	<b>Date</b> 10:12:11 03/21/18
	<b>Client</b> Crown Castle	<b>Designed by</b> RKE

Tower Elevation	Gusset Area (per face)	Gusset Thickness	Gusset Grade	Adjust. Factor $A_f$	Adjust. Factor $A_r$	Weight Mult.	Double Angle Stitch Bolt Spacing Diagonals in	Double Angle Stitch Bolt Spacing Horizontals in	Double Angle Stitch Bolt Spacing Redundants in
ft	ft <sup>2</sup>	in							
0000									
L14				1	1	0.869918			
105.0000-104.7500									
L15				1	1	0.884213			
104.7500-103.5000									
L16				1	1	0.904783			
103.5000-103.2500									
L17				1	1	0.910136			
103.2500-98.2500									
L18				1	1	0.909543			
98.2500-94.8300									
L19				1	1	0.904951			
94.8300-94.5800									
L20				1	1	0.919107			
94.5800-94.1700									
L21				1	1	0.920509			
94.1700-93.8200									
L22				1	1	0.919731			
93.8200-93.6600									
L23				1	1	0.927379			
93.6600-84.9100									
L24				1	1	0.924625			
84.9100-83.9100									
L25				1	1	0.931135			
83.9100-78.9100									
L26				1	1	0.925417			
78.9100-73.9100									
L27				1	1	0.935436			
73.9100-68.9100									
L28				1	1	0.937955			
68.9100-65.5000									
L29				1	1	0.884461			
65.5000-65.2500									
L30				1	1	0.881725			
65.2500-64.5000									
L31				1	1	0.9318			
64.5000-64.2500									
L32				1	1	0.927996			
64.2500-59.2500									
L33				1	1	0.940014			



<b>tnxTower</b>  <b>Tower Engineering Professionals</b> 326 Tryon Road Raleigh, N.C. Phone: (919) 661-6351 FAX: (919) 661-6350	<b>Job</b> Preston / Town Hall (BU 876360)	<b>Page</b> 9 of 55
	<b>Project</b> TEP No. 25620.161151	<b>Date</b> 10:12:11 03/21/18
	<b>Client</b> Crown Castle	<b>Designed by</b> RKE

Tower Elevation	Gusset Area (per face)	Gusset Thickness	Gusset Grade	Adjust. Factor $A_f$	Adjust. Factor $A_r$	Weight Mult.	Double Angle Stitch Bolt Spacing Diagonals	Double Angle Stitch Bolt Spacing Horizontals	Double Angle Stitch Bolt Spacing Redundants
ft	ft <sup>2</sup>	in					in	in	in
L53				1	1	0.974329			
17.2300-12.2300									
L54				1	1	0.975235			
12.2300-7.2300									
L55				1	1	1.00241			
7.2300-6.9000									
L56				1	1	1.03784			
6.9000-6.5500									
L57				1	1	1.03724			
6.5500-6.3300									
L58				1	1	1.04518			
6.3300-3.2500									
L59				1	1	1.04242			
3.2500-3.0000									
L60				1	1	0.976135			
3.0000-2.7500									
L61				1	1	0.975474			
2.7500-2.5000									
L62				1	1	1.03273			
2.5000-2.2500									
L63				1	1	1.00681			
2.2500-2.0000									
L64				1	1	1.00199			
2.0000-0.0000									

**Feed Line/Linear Appurtenances - Entered As Round Or Flat**

Description	Sector	Component Type	Placement	Total Number	Number Per Row	Start/End Position	Width or Diameter	Perimeter	Weight
			ft				in	in	plf
MLE HYBRID 9POWER/18FIBER RL 2(1-5/8) ***45***	A	Surface Ar (CaAa)	129.0000 - 0.0000	1	1	-0.250 -0.250	1.6250		1.07
LDF4-50A(1/2) ***	B	Surface Ar (CaAa)	45.0000 - 0.0000	1	1	0.250 0.250	0.6250		0.15
Safety Line 3/8	A	Surface Ar (CaAa)	147.0000 - 0.0000	1	1	0.500 0.500	0.3750		0.22
Step Pegs (5/8" SR) 7-in. w/30" step ***Proposed mods888	A	Surface Ar (CaAa)	147.0000 - 0.0000	1	1	0.500 0.500	0.3500		0.49
PL 1.25x5	B	Surface Ar (CaAa)	29.7500 - 0.0000	1	1	0.250 0.250	1.2500		0.00
PL 1.25x5	C	Surface Ar (CaAa)	29.7500 - 0.0000	1	1	0.000 0.000	1.2500		0.00
PL 1.25x5	B	Surface Ar (CaAa)	59.5000 - 29.7500	1	1	0.250 0.250	1.2500		0.00
PL 1.25x5	C	Surface Ar (CaAa)	59.5000 - 29.7500	1	1	0.000 0.000	1.2500		0.00
PL 1.25x4.75	B	Surface Ar (CaAa)	89.2500 - 59.5000	1	1	0.250 0.250	1.2500		0.00

<b>tnxTower</b>  <b>Tower Engineering Professionals</b> 326 Tryon Road Raleigh, N.C. Phone: (919) 661-6351 FAX: (919) 661-6350	<b>Job</b> Preston / Town Hall (BU 876360)	<b>Page</b> 10 of 55
	<b>Project</b> TEP No. 25620.161151	<b>Date</b> 10:12:11 03/21/18
	<b>Client</b> Crown Castle	<b>Designed by</b> RKE

Description	Sector	Component Type	Placement ft	Total Number	Number Per Row	Start/End Position	Width or Diameter in	Perimeter in	Weight plf
PL 1.25x4.75	C	Surface Ar (CaAa)	89.2500 - 59.5000	1	1	0.000 0.000	1.2500		0.00
*									
PL 1.25x4.25	B	Surface Ar (CaAa)	106.5000 - 89.2500	1	1	0.250 0.250	1.2500		0.00
PL 1.25x4.25	C	Surface Ar (CaAa)	106.5000 - 89.2500	1	1	0.000 0.000	1.2500		0.00
***									
(Area) Aero MP3-03	A	Surface Ar (CaAa)	30.7500 - 5.7500	1	1	0.500 0.500	1.5700		0.00
(Area) Aero MP3-03	A	Surface Ar (CaAa)	30.7500 - 5.7500	1	1	-0.250 -0.250	1.5700		0.00
***									
*									
(Area) CCI-65FP-045100	A	Surface Ar (CaAa)	60.5830 - 30.7500	1	1	0.500 0.500	1.0000		0.00
(Area) CCI-65FP-045100	A	Surface Ar (CaAa)	60.5830 - 30.7500	1	1	-0.250 -0.250	1.0000		0.00
*									
(Area) CCI-65FP-040075	A	Surface Ar (CaAa)	95.6670 - 60.5830	1	1	0.500 0.500	0.7500		0.00
(Area) CCI-65FP-040075	A	Surface Ar (CaAa)	95.6670 - 60.5830	1	1	-0.250 -0.250	0.7500		0.00
*									
(Area) CCI-65FP-045100	A	Surface Ar (CaAa)	112.0000 - 106.5000	1	1	0.500 0.500	1.0000		0.00
(Area) CCI-65FP-045100	A	Surface Ar (CaAa)	112.0000 - 106.5000	1	1	-0.250 -0.250	1.0000		0.00
**Proposed Mods**									
(Area) CCI-65FP-045125	A	Surface Ar (CaAa)	5.7500 - 0.0000	1	1	0.500 0.500	1.2500		0.00
(Area) CCI-65FP-045125	A	Surface Ar (CaAa)	5.7500 - 0.0000	1	1	-0.250 -0.250	1.2500		0.00
*									
(Area) CCI-65FP-045125	B	Surface Ar (CaAa)	115.0800 - 106.5000	1	1	0.250 0.250	1.2500		0.00
(Area) CCI-65FP-045125	C	Surface Ar (CaAa)	114.1600 - 106.5000	1	1	0.000 0.000	1.2500		0.00

### Feed Line/Linear Appurtenances - Entered As Area

Description	Face or Leg	Allow Shield	Component Type	Placement ft	Total Number		C <sub>A</sub> A <sub>A</sub> ft <sup>2</sup> /ft	Weight plf
***147***								
HB114-1-0813U4-M5J(1-1/4)	A	No	Inside Pole	147.0000 - 0.0000	3	No Ice 1/2" Ice 1" Ice	0.0000 0.0000 0.0000	1.20 1.20 1.20
HB114-13U3M12-XXX F(1-1/4)	A	No	Inside Pole	147.0000 - 0.0000	1	No Ice 1/2" Ice 1" Ice	0.0000 0.0000 0.0000	0.99 0.99 0.99
***136***								
LDF7-50A(1-5/8)	C	No	Inside Pole	136.0000 - 0.0000	12	No Ice 1/2" Ice 1" Ice	0.0000 0.0000 0.0000	0.82 0.82 0.82
HB158-1-08U8-S8J18(1-5/8)	C	No	Inside Pole	136.0000 - 0.0000	2	No Ice 1/2" Ice 1" Ice	0.0000 0.0000 0.0000	1.30 1.30 1.30

<b>tnxTower</b>  <b>Tower Engineering Professionals</b> 326 Tryon Road Raleigh, N.C. Phone: (919) 661-6351 FAX: (919) 661-6350	<b>Job</b> Preston / Town Hall (BU 876360)	<b>Page</b> 11 of 55
	<b>Project</b> TEP No. 25620.161151	<b>Date</b> 10:12:11 03/21/18
	<b>Client</b> Crown Castle	<b>Designed by</b> RKE

Description	Face or Leg	Allow Shield	Component Type	Placement ft	Total Number		C <sub>AA</sub> ft <sup>2</sup> /ft	Weight plf
***129***								
LDF7-50A(1-5/8)	A	No	Inside Pole	129.0000 - 0.0000	6	No Ice	0.0000	0.82
						1/2" Ice	0.0000	0.82
						1" Ice	0.0000	0.82
***118***								
2" Flexible Conduit	B	No	Inside Pole	118.0000 - 0.0000	1	No Ice	0.0000	0.34
						1/2" Ice	0.0000	0.34
						1" Ice	0.0000	0.34
AVA6-50(1-1/4)	B	No	Inside Pole	118.0000 - 0.0000	6	No Ice	0.0000	0.46
						1/2" Ice	0.0000	0.46
						1" Ice	0.0000	0.46
FB-L98B-002-75000(3/8)	B	No	Inside Pole	118.0000 - 0.0000	3	No Ice	0.0000	0.06
)						1/2" Ice	0.0000	0.06
						1" Ice	0.0000	0.06
***50***								
LDF4-50A(1/2)	C	No	Inside Pole	50.0000 - 0.0000	1	No Ice	0.0000	0.15
						1/2" Ice	0.0000	0.15
						1" Ice	0.0000	0.15

### Feed Line/Linear Appurtenances Section Areas

Tower Section	Tower Elevation ft	Face	A <sub>R</sub> ft <sup>2</sup>	A <sub>F</sub> ft <sup>2</sup>	C <sub>AA</sub> In Face ft <sup>2</sup>	C <sub>AA</sub> Out Face ft <sup>2</sup>	Weight K
L1	147.0000-142.000 0	A	0.000	0.000	0.362	0.000	0.03
		B	0.000	0.000	0.000	0.000	0.00
		C	0.000	0.000	0.000	0.000	0.00
L2	142.0000-137.000 0	A	0.000	0.000	0.362	0.000	0.03
		B	0.000	0.000	0.000	0.000	0.00
		C	0.000	0.000	0.000	0.000	0.00
L3	137.0000-132.000 0	A	0.000	0.000	0.362	0.000	0.03
		B	0.000	0.000	0.000	0.000	0.00
		C	0.000	0.000	0.000	0.000	0.05
L4	132.0000-127.000 0	A	0.000	0.000	0.688	0.000	0.04
		B	0.000	0.000	0.000	0.000	0.00
		C	0.000	0.000	0.000	0.000	0.06
L5	127.0000-120.370 0	A	0.000	0.000	1.558	0.000	0.07
		B	0.000	0.000	0.000	0.000	0.00
		C	0.000	0.000	0.000	0.000	0.08
L6	120.3700-118.620 0	A	0.000	0.000	0.411	0.000	0.02
		B	0.000	0.000	0.000	0.000	0.00
		C	0.000	0.000	0.000	0.000	0.02
L7	118.6200-113.620 0	A	0.000	0.000	1.175	0.000	0.06
		B	0.000	0.000	0.183	0.000	0.01
		C	0.000	0.000	0.068	0.000	0.06
L8	113.6200-112.410 0	A	0.000	0.000	0.284	0.000	0.01
		B	0.000	0.000	0.151	0.000	0.00
		C	0.000	0.000	0.151	0.000	0.02
L9	112.4100-112.160 0	A	0.000	0.000	0.059	0.000	0.00
		B	0.000	0.000	0.031	0.000	0.00
		C	0.000	0.000	0.031	0.000	0.00
L10	112.1600-110.500 0	A	0.000	0.000	0.690	0.000	0.02
		B	0.000	0.000	0.207	0.000	0.01
		C	0.000	0.000	0.207	0.000	0.02
L11	110.5000-110.250 0	A	0.000	0.000	0.109	0.000	0.00
		B	0.000	0.000	0.031	0.000	0.00
		C	0.000	0.000	0.031	0.000	0.00
L12	110.2500-105.250	A	0.000	0.000	1.925	0.000	0.06

<b>tnxTower</b>  <b>Tower Engineering Professionals</b> 326 Tryon Road Raleigh, N.C. Phone: (919) 661-6351 FAX: (919) 661-6350	<b>Job</b>	Preston / Town Hall (BU 876360)	<b>Page</b>	12 of 55
	<b>Project</b>	TEP No. 25620.161151	<b>Date</b>	10:12:11 03/21/18
	<b>Client</b>	Crown Castle	<b>Designed by</b>	RKE

Tower Section	Tower Elevation ft	Face	A <sub>R</sub> ft <sup>2</sup>	A <sub>F</sub> ft <sup>2</sup>	C <sub>AA</sub> In Face ft <sup>2</sup>	C <sub>AA</sub> Out Face ft <sup>2</sup>	Weight K
	0	B	0.000	0.000	0.625	0.000	0.02
		C	0.000	0.000	0.625	0.000	0.06
L13	105.2500-105.0000	A	0.000	0.000	0.059	0.000	0.00
	0	B	0.000	0.000	0.031	0.000	0.00
		C	0.000	0.000	0.031	0.000	0.00
L14	105.0000-104.7500	A	0.000	0.000	0.059	0.000	0.00
	0	B	0.000	0.000	0.031	0.000	0.00
		C	0.000	0.000	0.031	0.000	0.00
L15	104.7500-103.5000	A	0.000	0.000	0.294	0.000	0.01
	0	B	0.000	0.000	0.156	0.000	0.00
		C	0.000	0.000	0.156	0.000	0.02
L16	103.5000-103.2500	A	0.000	0.000	0.059	0.000	0.00
	0	B	0.000	0.000	0.031	0.000	0.00
		C	0.000	0.000	0.031	0.000	0.00
L17	103.2500-98.2500	A	0.000	0.000	1.175	0.000	0.06
		B	0.000	0.000	0.625	0.000	0.02
		C	0.000	0.000	0.625	0.000	0.06
L18	98.2500-94.8300	A	0.000	0.000	0.929	0.000	0.04
		B	0.000	0.000	0.427	0.000	0.01
		C	0.000	0.000	0.427	0.000	0.04
L19	94.8300-94.5800	A	0.000	0.000	0.096	0.000	0.00
		B	0.000	0.000	0.031	0.000	0.00
		C	0.000	0.000	0.031	0.000	0.00
L20	94.5800-94.1700	A	0.000	0.000	0.158	0.000	0.00
		B	0.000	0.000	0.051	0.000	0.00
		C	0.000	0.000	0.051	0.000	0.01
L21	94.1700-93.8200	A	0.000	0.000	0.135	0.000	0.00
		B	0.000	0.000	0.044	0.000	0.00
		C	0.000	0.000	0.044	0.000	0.00
L22	93.8200-93.6600	A	0.000	0.000	0.062	0.000	0.00
		B	0.000	0.000	0.020	0.000	0.00
		C	0.000	0.000	0.020	0.000	0.00
L23	93.6600-84.9100	A	0.000	0.000	3.369	0.000	0.10
		B	0.000	0.000	1.094	0.000	0.03
		C	0.000	0.000	1.094	0.000	0.11
L24	84.9100-83.9100	A	0.000	0.000	0.385	0.000	0.01
		B	0.000	0.000	0.125	0.000	0.00
		C	0.000	0.000	0.125	0.000	0.01
L25	83.9100-78.9100	A	0.000	0.000	1.925	0.000	0.06
		B	0.000	0.000	0.625	0.000	0.02
		C	0.000	0.000	0.625	0.000	0.06
L26	78.9100-73.9100	A	0.000	0.000	1.925	0.000	0.06
		B	0.000	0.000	0.625	0.000	0.02
		C	0.000	0.000	0.625	0.000	0.06
L27	73.9100-68.9100	A	0.000	0.000	1.925	0.000	0.06
		B	0.000	0.000	0.625	0.000	0.02
		C	0.000	0.000	0.625	0.000	0.06
L28	68.9100-65.5000	A	0.000	0.000	1.313	0.000	0.04
		B	0.000	0.000	0.426	0.000	0.01
		C	0.000	0.000	0.426	0.000	0.04
L29	65.5000-65.2500	A	0.000	0.000	0.096	0.000	0.00
		B	0.000	0.000	0.031	0.000	0.00
		C	0.000	0.000	0.031	0.000	0.00
L30	65.2500-64.5000	A	0.000	0.000	0.289	0.000	0.01
		B	0.000	0.000	0.094	0.000	0.00
		C	0.000	0.000	0.094	0.000	0.01
L31	64.5000-64.2500	A	0.000	0.000	0.096	0.000	0.00
		B	0.000	0.000	0.031	0.000	0.00
		C	0.000	0.000	0.031	0.000	0.00
L32	64.2500-59.2500	A	0.000	0.000	1.992	0.000	0.06
		B	0.000	0.000	0.625	0.000	0.02

<b>tnxTower</b>  <b>Tower Engineering Professionals</b> 326 Tryon Road Raleigh, N.C. Phone: (919) 661-6351 FAX: (919) 661-6350	Job	Preston / Town Hall (BU 876360)	Page	13 of 55
	Project	TEP No. 25620.161151	Date	10:12:11 03/21/18
	Client	Crown Castle	Designed by	RKE

Tower Section	Tower Elevation ft	Face	A <sub>R</sub> ft <sup>2</sup>	A <sub>F</sub> ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> In Face ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> Out Face ft <sup>2</sup>	Weight K
L33	59.2500-58.5800	C	0.000	0.000	0.625	0.000	0.06
		A	0.000	0.000	0.291	0.000	0.01
		B	0.000	0.000	0.084	0.000	0.00
		C	0.000	0.000	0.084	0.000	0.01
L34	58.5800-58.3300	A	0.000	0.000	0.109	0.000	0.00
		B	0.000	0.000	0.031	0.000	0.00
		C	0.000	0.000	0.031	0.000	0.00
L35	58.3300-57.2500	A	0.000	0.000	0.470	0.000	0.01
		B	0.000	0.000	0.135	0.000	0.00
		C	0.000	0.000	0.135	0.000	0.01
L36	57.2500-57.0000	A	0.000	0.000	0.109	0.000	0.00
		B	0.000	0.000	0.031	0.000	0.00
		C	0.000	0.000	0.031	0.000	0.00
L37	57.0000-52.0000	A	0.000	0.000	2.175	0.000	0.06
		B	0.000	0.000	0.625	0.000	0.02
		C	0.000	0.000	0.625	0.000	0.06
L38	52.0000-44.4100	A	0.000	0.000	3.302	0.000	0.09
		B	0.000	0.000	0.986	0.000	0.02
		C	0.000	0.000	0.949	0.000	0.10
L39	44.4100-43.4100	A	0.000	0.000	0.435	0.000	0.01
		B	0.000	0.000	0.188	0.000	0.00
		C	0.000	0.000	0.125	0.000	0.01
L40	43.4100-38.4100	A	0.000	0.000	2.175	0.000	0.06
		B	0.000	0.000	0.938	0.000	0.02
		C	0.000	0.000	0.625	0.000	0.06
L41	38.4100-34.5000	A	0.000	0.000	1.701	0.000	0.04
		B	0.000	0.000	0.733	0.000	0.01
		C	0.000	0.000	0.489	0.000	0.05
L42	34.5000-34.2500	A	0.000	0.000	0.109	0.000	0.00
		B	0.000	0.000	0.047	0.000	0.00
		C	0.000	0.000	0.031	0.000	0.00
L43	34.2500-33.5000	A	0.000	0.000	0.326	0.000	0.01
		B	0.000	0.000	0.141	0.000	0.00
		C	0.000	0.000	0.094	0.000	0.01
L44	33.5000-33.2500	A	0.000	0.000	0.109	0.000	0.00
		B	0.000	0.000	0.047	0.000	0.00
		C	0.000	0.000	0.031	0.000	0.00
L45	33.2500-29.5000	A	0.000	0.000	1.774	0.000	0.04
		B	0.000	0.000	0.703	0.000	0.01
		C	0.000	0.000	0.469	0.000	0.05
L46	29.5000-29.2500	A	0.000	0.000	0.137	0.000	0.00
		B	0.000	0.000	0.047	0.000	0.00
		C	0.000	0.000	0.031	0.000	0.00
L47	29.2500-28.5000	A	0.000	0.000	0.412	0.000	0.01
		B	0.000	0.000	0.141	0.000	0.00
		C	0.000	0.000	0.094	0.000	0.01
L48	28.5000-28.2500	A	0.000	0.000	0.137	0.000	0.00
		B	0.000	0.000	0.047	0.000	0.00
		C	0.000	0.000	0.031	0.000	0.00
L49	28.2500-27.4800	A	0.000	0.000	0.423	0.000	0.01
		B	0.000	0.000	0.144	0.000	0.00
		C	0.000	0.000	0.096	0.000	0.01
L50	27.4800-27.2300	A	0.000	0.000	0.137	0.000	0.00
		B	0.000	0.000	0.047	0.000	0.00
		C	0.000	0.000	0.031	0.000	0.00
L51	27.2300-22.2300	A	0.000	0.000	2.745	0.000	0.06
		B	0.000	0.000	0.938	0.000	0.02
		C	0.000	0.000	0.625	0.000	0.06
L52	22.2300-17.2300	A	0.000	0.000	2.745	0.000	0.06
		B	0.000	0.000	0.938	0.000	0.02
		C	0.000	0.000	0.625	0.000	0.06



<b>tnxTower</b>  <b>Tower Engineering Professionals</b> 326 Tryon Road Raleigh, N.C. Phone: (919) 661-6351 FAX: (919) 661-6350	<b>Job</b> Preston / Town Hall (BU 876360)	<b>Page</b> 14 of 55
	<b>Project</b> TEP No. 25620.161151	<b>Date</b> 10:12:11 03/21/18
	<b>Client</b> Crown Castle	<b>Designed by</b> RKE

Tower Section	Tower Elevation ft	Face	A <sub>R</sub> ft <sup>2</sup>	A <sub>F</sub> ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> In Face ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> Out Face ft <sup>2</sup>	Weight K
L53	17.2300-12.2300	A	0.000	0.000	2.745	0.000	0.06
		B	0.000	0.000	0.938	0.000	0.02
		C	0.000	0.000	0.625	0.000	0.06
L54	12.2300-7.2300	A	0.000	0.000	2.745	0.000	0.06
		B	0.000	0.000	0.938	0.000	0.02
		C	0.000	0.000	0.625	0.000	0.06
L55	7.2300-6.9000	A	0.000	0.000	0.181	0.000	0.00
		B	0.000	0.000	0.062	0.000	0.00
		C	0.000	0.000	0.041	0.000	0.00
L56	6.9000-6.5500	A	0.000	0.000	0.192	0.000	0.00
		B	0.000	0.000	0.066	0.000	0.00
		C	0.000	0.000	0.044	0.000	0.00
L57	6.5500-6.3300	A	0.000	0.000	0.121	0.000	0.00
		B	0.000	0.000	0.041	0.000	0.00
		C	0.000	0.000	0.028	0.000	0.00
L58	6.3300-3.2500	A	0.000	0.000	1.531	0.000	0.03
		B	0.000	0.000	0.578	0.000	0.01
		C	0.000	0.000	0.385	0.000	0.04
L59	3.2500-3.0000	A	0.000	0.000	0.121	0.000	0.00
		B	0.000	0.000	0.047	0.000	0.00
		C	0.000	0.000	0.031	0.000	0.00
L60	3.0000-2.7500	A	0.000	0.000	0.121	0.000	0.00
		B	0.000	0.000	0.047	0.000	0.00
		C	0.000	0.000	0.031	0.000	0.00
L61	2.7500-2.5000	A	0.000	0.000	0.121	0.000	0.00
		B	0.000	0.000	0.047	0.000	0.00
		C	0.000	0.000	0.031	0.000	0.00
L62	2.5000-2.2500	A	0.000	0.000	0.121	0.000	0.00
		B	0.000	0.000	0.047	0.000	0.00
		C	0.000	0.000	0.031	0.000	0.00
L63	2.2500-2.0000	A	0.000	0.000	0.121	0.000	0.00
		B	0.000	0.000	0.047	0.000	0.00
		C	0.000	0.000	0.031	0.000	0.00
L64	2.0000-0.0000	A	0.000	0.000	0.970	0.000	0.02
		B	0.000	0.000	0.375	0.000	0.01
		C	0.000	0.000	0.250	0.000	0.03

### Feed Line/Linear Appurtenances Section Areas - With Ice

Tower Section	Tower Elevation ft	Face or Leg	Ice Thickness in	A <sub>R</sub> ft <sup>2</sup>	A <sub>F</sub> ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> In Face ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> Out Face ft <sup>2</sup>	Weight K
L1	147.0000-142.0000	A	1.739	0.000	0.000	3.840	0.000	0.07
	0	B		0.000	0.000	0.000	0.000	0.00
		C		0.000	0.000	0.000	0.000	0.00
L2	142.0000-137.0000	A	1.733	0.000	0.000	3.828	0.000	0.07
	0	B		0.000	0.000	0.000	0.000	0.00
		C		0.000	0.000	0.000	0.000	0.00
L3	137.0000-132.0000	A	1.726	0.000	0.000	3.815	0.000	0.07
	0	B		0.000	0.000	0.000	0.000	0.00
		C		0.000	0.000	0.000	0.000	0.05
L4	132.0000-127.0000	A	1.720	0.000	0.000	4.815	0.000	0.10
	0	B		0.000	0.000	0.000	0.000	0.00
		C		0.000	0.000	0.000	0.000	0.06
L5	127.0000-120.3700	A	1.712	0.000	0.000	8.368	0.000	0.18
	0	B		0.000	0.000	0.000	0.000	0.00
		C		0.000	0.000	0.000	0.000	0.08
L6	120.3700-118.6200	A	1.706	0.000	0.000	2.209	0.000	0.05

<b>tnxTower</b>  <b>Tower Engineering Professionals</b> 326 Tryon Road Raleigh, N.C. Phone: (919) 661-6351 FAX: (919) 661-6350	Job	Preston / Town Hall (BU 876360)	Page	15 of 55
	Project	TEP No. 25620.161151	Date	10:12:11 03/21/18
	Client	Crown Castle	Designed by	RKE

Tower Section	Tower Elevation ft	Face or Leg	Ice Thickness in	A <sub>R</sub> ft <sup>2</sup>	A <sub>F</sub> ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> In Face ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> Out Face ft <sup>2</sup>	Weight K
	0	B		0.000	0.000	0.000	0.000	0.00
		C		0.000	0.000	0.000	0.000	0.02
L7	118.6200-113.620	A	1.701	0.000	0.000	6.278	0.000	0.13
	0	B		0.000	0.000	0.652	0.000	0.02
		C		0.000	0.000	0.230	0.000	0.07
L8	113.6200-112.410	A	1.696	0.000	0.000	1.516	0.000	0.03
	0	B		0.000	0.000	0.540	0.000	0.01
		C		0.000	0.000	0.515	0.000	0.02
L9	112.4100-112.160	A	1.695	0.000	0.000	0.313	0.000	0.01
	0	B		0.000	0.000	0.112	0.000	0.00
		C		0.000	0.000	0.106	0.000	0.00
L10	112.1600-110.500	A	1.694	0.000	0.000	3.170	0.000	0.06
	0	B		0.000	0.000	0.740	0.000	0.02
		C		0.000	0.000	0.706	0.000	0.03
L11	110.5000-110.250	A	1.692	0.000	0.000	0.495	0.000	0.01
	0	B		0.000	0.000	0.111	0.000	0.00
		C		0.000	0.000	0.106	0.000	0.00
L12	110.2500-105.250	A	1.688	0.000	0.000	8.967	0.000	0.17
	0	B		0.000	0.000	2.249	0.000	0.05
		C		0.000	0.000	2.172	0.000	0.09
L13	105.2500-105.000	A	1.684	0.000	0.000	0.311	0.000	0.01
	0	B		0.000	0.000	0.115	0.000	0.00
		C		0.000	0.000	0.115	0.000	0.00
L14	105.0000-104.750	A	1.684	0.000	0.000	0.311	0.000	0.01
	0	B		0.000	0.000	0.115	0.000	0.00
		C		0.000	0.000	0.115	0.000	0.00
L15	104.7500-103.500	A	1.683	0.000	0.000	1.556	0.000	0.03
	0	B		0.000	0.000	0.577	0.000	0.01
		C		0.000	0.000	0.577	0.000	0.02
L16	103.5000-103.250	A	1.681	0.000	0.000	0.311	0.000	0.01
	0	B		0.000	0.000	0.115	0.000	0.00
		C		0.000	0.000	0.115	0.000	0.00
L17	103.2500-98.2500	A	1.677	0.000	0.000	6.206	0.000	0.13
		B		0.000	0.000	2.302	0.000	0.05
		C		0.000	0.000	2.302	0.000	0.09
L18	98.2500-94.8300	A	1.670	0.000	0.000	4.915	0.000	0.10
		B		0.000	0.000	1.570	0.000	0.03
		C		0.000	0.000	1.570	0.000	0.06
L19	94.8300-94.5800	A	1.667	0.000	0.000	0.513	0.000	0.01
		B		0.000	0.000	0.115	0.000	0.00
		C		0.000	0.000	0.115	0.000	0.00
L20	94.5800-94.1700	A	1.666	0.000	0.000	0.841	0.000	0.01
		B		0.000	0.000	0.188	0.000	0.00
		C		0.000	0.000	0.188	0.000	0.01
L21	94.1700-93.8200	A	1.666	0.000	0.000	0.718	0.000	0.01
		B		0.000	0.000	0.160	0.000	0.00
		C		0.000	0.000	0.160	0.000	0.01
L22	93.8200-93.6600	A	1.665	0.000	0.000	0.328	0.000	0.01
		B		0.000	0.000	0.073	0.000	0.00
		C		0.000	0.000	0.073	0.000	0.00
L23	93.6600-84.9100	A	1.657	0.000	0.000	17.867	0.000	0.31
		B		0.000	0.000	3.993	0.000	0.08
		C		0.000	0.000	3.993	0.000	0.16
L24	84.9100-83.9100	A	1.648	0.000	0.000	2.042	0.000	0.04
		B		0.000	0.000	0.456	0.000	0.01
		C		0.000	0.000	0.456	0.000	0.02
L25	83.9100-78.9100	A	1.642	0.000	0.000	10.134	0.000	0.18
		B		0.000	0.000	2.267	0.000	0.05
		C		0.000	0.000	2.267	0.000	0.09
L26	78.9100-73.9100	A	1.631	0.000	0.000	10.082	0.000	0.18
		B		0.000	0.000	2.256	0.000	0.05

<b>tnxTower</b>  <b>Tower Engineering Professionals</b> 326 Tryon Road Raleigh, N.C. Phone: (919) 661-6351 FAX: (919) 661-6350	Job	Preston / Town Hall (BU 876360)	Page	16 of 55
	Project	TEP No. 25620.161151	Date	10:12:11 03/21/18
	Client	Crown Castle	Designed by	RKE

Tower Section	Tower Elevation ft	Face or Leg	Ice Thickness in	A <sub>R</sub> ft <sup>2</sup>	A <sub>F</sub> ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> In Face ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> Out Face ft <sup>2</sup>	Weight K
		C		0.000	0.000	2.256	0.000	0.09
L27	73.9100-68.9100	A	1.620	0.000	0.000	10.027	0.000	0.17
		B		0.000	0.000	2.245	0.000	0.04
		C		0.000	0.000	2.245	0.000	0.09
L28	68.9100-65.5000	A	1.611	0.000	0.000	6.805	0.000	0.12
		B		0.000	0.000	1.525	0.000	0.03
		C		0.000	0.000	1.525	0.000	0.06
L29	65.5000-65.2500	A	1.606	0.000	0.000	0.498	0.000	0.01
		B		0.000	0.000	0.112	0.000	0.00
		C		0.000	0.000	0.112	0.000	0.00
L30	65.2500-64.5000	A	1.605	0.000	0.000	1.492	0.000	0.03
		B		0.000	0.000	0.334	0.000	0.01
		C		0.000	0.000	0.334	0.000	0.01
L31	64.5000-64.2500	A	1.604	0.000	0.000	0.497	0.000	0.01
		B		0.000	0.000	0.111	0.000	0.00
		C		0.000	0.000	0.111	0.000	0.00
L32	64.2500-59.2500	A	1.597	0.000	0.000	9.976	0.000	0.17
		B		0.000	0.000	2.222	0.000	0.04
		C		0.000	0.000	2.222	0.000	0.09
L33	59.2500-58.5800	A	1.590	0.000	0.000	1.356	0.000	0.02
		B		0.000	0.000	0.297	0.000	0.01
		C		0.000	0.000	0.297	0.000	0.01
L34	58.5800-58.3300	A	1.588	0.000	0.000	0.506	0.000	0.01
		B		0.000	0.000	0.111	0.000	0.00
		C		0.000	0.000	0.111	0.000	0.00
L35	58.3300-57.2500	A	1.586	0.000	0.000	2.183	0.000	0.04
		B		0.000	0.000	0.478	0.000	0.01
		C		0.000	0.000	0.478	0.000	0.02
L36	57.2500-57.0000	A	1.585	0.000	0.000	0.505	0.000	0.01
		B		0.000	0.000	0.110	0.000	0.00
		C		0.000	0.000	0.110	0.000	0.00
L37	57.0000-52.0000	A	1.577	0.000	0.000	10.061	0.000	0.17
		B		0.000	0.000	2.202	0.000	0.04
		C		0.000	0.000	2.202	0.000	0.09
L38	52.0000-44.4100	A	1.558	0.000	0.000	15.126	0.000	0.26
		B		0.000	0.000	3.534	0.000	0.07
		C		0.000	0.000	3.314	0.000	0.14
L39	44.4100-43.4100	A	1.543	0.000	0.000	1.993	0.000	0.03
		B		0.000	0.000	0.811	0.000	0.01
		C		0.000	0.000	0.437	0.000	0.02
L40	43.4100-38.4100	A	1.533	0.000	0.000	9.838	0.000	0.17
		B		0.000	0.000	4.003	0.000	0.06
		C		0.000	0.000	2.158	0.000	0.09
L41	38.4100-34.5000	A	1.515	0.000	0.000	7.624	0.000	0.13
		B		0.000	0.000	3.103	0.000	0.05
		C		0.000	0.000	1.673	0.000	0.07
L42	34.5000-34.2500	A	1.506	0.000	0.000	0.485	0.000	0.01
		B		0.000	0.000	0.197	0.000	0.00
		C		0.000	0.000	0.107	0.000	0.00
L43	34.2500-33.5000	A	1.504	0.000	0.000	1.454	0.000	0.02
		B		0.000	0.000	0.592	0.000	0.01
		C		0.000	0.000	0.319	0.000	0.01
L44	33.5000-33.2500	A	1.502	0.000	0.000	0.484	0.000	0.01
		B		0.000	0.000	0.197	0.000	0.00
		C		0.000	0.000	0.106	0.000	0.00
L45	33.2500-29.5000	A	1.492	0.000	0.000	7.370	0.000	0.13
		B		0.000	0.000	2.942	0.000	0.05
		C		0.000	0.000	1.588	0.000	0.07
L46	29.5000-29.2500	A	1.483	0.000	0.000	0.508	0.000	0.01
		B		0.000	0.000	0.195	0.000	0.00
		C		0.000	0.000	0.105	0.000	0.00

<b>tnxTower</b>  <b>Tower Engineering Professionals</b> 326 Tryon Road Raleigh, N.C. Phone: (919) 661-6351 FAX: (919) 661-6350	<b>Job</b> Preston / Town Hall (BU 876360)	<b>Page</b> 17 of 55
	<b>Project</b> TEP No. 25620.161151	<b>Date</b> 10:12:11 03/21/18
	<b>Client</b> Crown Castle	<b>Designed by</b> RKE

Tower Section	Tower Elevation ft	Face or Leg	Ice Thickness in	A <sub>R</sub> ft <sup>2</sup>	A <sub>F</sub> ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> In Face ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> Out Face ft <sup>2</sup>	Weight K
L47	29.2500-28.5000	A	1.480	0.000	0.000	1.522	0.000	0.03
		B		0.000	0.000	0.585	0.000	0.01
		C		0.000	0.000	0.316	0.000	0.01
L48	28.5000-28.2500	A	1.478	0.000	0.000	0.507	0.000	0.01
		B		0.000	0.000	0.195	0.000	0.00
		C		0.000	0.000	0.105	0.000	0.00
L49	28.2500-27.4800	A	1.475	0.000	0.000	1.558	0.000	0.03
		B		0.000	0.000	0.599	0.000	0.01
		C		0.000	0.000	0.323	0.000	0.01
L50	27.4800-27.2300	A	1.472	0.000	0.000	0.505	0.000	0.01
		B		0.000	0.000	0.194	0.000	0.00
		C		0.000	0.000	0.105	0.000	0.00
L51	27.2300-22.2300	A	1.457	0.000	0.000	10.031	0.000	0.17
		B		0.000	0.000	3.852	0.000	0.06
		C		0.000	0.000	2.082	0.000	0.09
L52	22.2300-17.2300	A	1.425	0.000	0.000	9.869	0.000	0.17
		B		0.000	0.000	3.787	0.000	0.06
		C		0.000	0.000	2.050	0.000	0.09
L53	17.2300-12.2300	A	1.384	0.000	0.000	9.663	0.000	0.16
		B		0.000	0.000	3.705	0.000	0.06
		C		0.000	0.000	2.009	0.000	0.09
L54	12.2300-7.2300	A	1.327	0.000	0.000	9.382	0.000	0.15
		B		0.000	0.000	3.592	0.000	0.05
		C		0.000	0.000	1.952	0.000	0.08
L55	7.2300-6.9000	A	1.286	0.000	0.000	0.605	0.000	0.01
		B		0.000	0.000	0.232	0.000	0.00
		C		0.000	0.000	0.126	0.000	0.01
L56	6.9000-6.5500	A	1.279	0.000	0.000	0.640	0.000	0.01
		B		0.000	0.000	0.245	0.000	0.00
		C		0.000	0.000	0.133	0.000	0.01
L57	6.5500-6.3300	A	1.274	0.000	0.000	0.401	0.000	0.01
		B		0.000	0.000	0.153	0.000	0.00
		C		0.000	0.000	0.084	0.000	0.00
L58	6.3300-3.2500	A	1.237	0.000	0.000	5.140	0.000	0.09
		B		0.000	0.000	2.101	0.000	0.03
		C		0.000	0.000	1.147	0.000	0.05
L59	3.2500-3.0000	A	1.185	0.000	0.000	0.400	0.000	0.01
		B		0.000	0.000	0.165	0.000	0.00
		C		0.000	0.000	0.091	0.000	0.00
L60	3.0000-2.7500	A	1.175	0.000	0.000	0.398	0.000	0.01
		B		0.000	0.000	0.164	0.000	0.00
		C		0.000	0.000	0.090	0.000	0.00
L61	2.7500-2.5000	A	1.165	0.000	0.000	0.396	0.000	0.01
		B		0.000	0.000	0.163	0.000	0.00
		C		0.000	0.000	0.089	0.000	0.00
L62	2.5000-2.2500	A	1.153	0.000	0.000	0.393	0.000	0.01
		B		0.000	0.000	0.162	0.000	0.00
		C		0.000	0.000	0.089	0.000	0.00
L63	2.2500-2.0000	A	1.140	0.000	0.000	0.391	0.000	0.01
		B		0.000	0.000	0.161	0.000	0.00
		C		0.000	0.000	0.088	0.000	0.00
L64	2.0000-0.0000	A	1.057	0.000	0.000	2.988	0.000	0.05
		B		0.000	0.000	1.221	0.000	0.02
		C		0.000	0.000	0.673	0.000	0.03

**Feed Line Center of Pressure**

<b>tnxTower</b>  <b>Tower Engineering Professionals</b> 326 Tryon Road Raleigh, N.C. Phone: (919) 661-6351 FAX: (919) 661-6350	Job	Preston / Town Hall (BU 876360)	Page	18 of 55
	Project	TEP No. 25620.161151	Date	10:12:11 03/21/18
	Client	Crown Castle	Designed by	RKE

Section	Elevation	CP <sub>x</sub>	CP <sub>z</sub>	CP <sub>x</sub>	CP <sub>z</sub>
	ft	in	in	Ice in	Ice in
L1	147.0000-142.0000	0.0000	-0.1041	0.0000	-0.6643
L2	142.0000-137.0000	0.0000	-0.1043	0.0000	-0.6797
L3	137.0000-132.0000	0.0000	-0.1044	0.0000	-0.6938
L4	132.0000-127.0000	-0.0975	-0.1009	-0.1890	-0.6581
L5	127.0000-120.3700	-0.2285	-0.0963	-0.4316	-0.6117
L6	120.3700-118.6200	-0.2287	-0.0965	-0.4348	-0.6168
L7	118.6200-113.6200	-0.1735	-0.0759	-0.3095	-0.5547
L8	113.6200-112.4100	-0.0499	0.0688	-0.0441	-0.2076
L9	112.4100-112.1600	-0.0499	0.0688	-0.0441	-0.2083
L10	112.1600-110.5000	-0.1508	-0.0401	-0.2377	-0.3811
L11	110.5000-110.2500	-0.1610	-0.0509	-0.2564	-0.3986
L12	110.2500-105.2500	-0.1349	-0.0223	-0.2073	-0.3531
L13	105.2500-105.0000	-0.0502	0.0693	-0.0320	-0.1852
L14	105.0000-104.7500	-0.0502	0.0693	-0.0320	-0.1854
L15	104.7500-103.5000	-0.0502	0.0693	-0.0321	-0.1860
L16	103.5000-103.2500	-0.0503	0.0694	-0.0322	-0.1866
L17	103.2500-98.2500	-0.0504	0.0695	-0.0324	-0.1886
L18	98.2500-94.8300	-0.0727	0.0460	-0.1023	-0.2546
L19	94.8300-94.5800	-0.1371	-0.0229	-0.2843	-0.4206
L20	94.5800-94.1700	-0.1371	-0.0229	-0.2846	-0.4212
L21	94.1700-93.8200	-0.1372	-0.0229	-0.2851	-0.4218
L22	93.8200-93.6600	-0.1372	-0.0229	-0.2854	-0.4223
L23	93.6600-84.9100	-0.1380	-0.0232	-0.2903	-0.4298
L24	84.9100-83.9100	-0.1383	-0.0233	-0.2926	-0.4334
L25	83.9100-78.9100	-0.1388	-0.0235	-0.2953	-0.4369
L26	78.9100-73.9100	-0.1396	-0.0238	-0.3003	-0.4443
L27	73.9100-68.9100	-0.1403	-0.0240	-0.3051	-0.4513
L28	68.9100-65.5000	-0.1409	-0.0242	-0.3090	-0.4568
L29	65.5000-65.2500	-0.1412	-0.0243	-0.3106	-0.4591
L30	65.2500-64.5000	-0.1412	-0.0243	-0.3110	-0.4597
L31	64.5000-64.2500	-0.1413	-0.0244	-0.3114	-0.4603
L32	64.2500-59.2500	-0.1496	-0.0329	-0.3183	-0.4678
L33	59.2500-58.5800	-0.1714	-0.0556	-0.3334	-0.4828
L34	58.5800-58.3300	-0.1715	-0.0557	-0.3338	-0.4834
L35	58.3300-57.2500	-0.1716	-0.0557	-0.3344	-0.4841
L36	57.2500-57.0000	-0.1717	-0.0558	-0.3350	-0.4849
L37	57.0000-52.0000	-0.1721	-0.0560	-0.3371	-0.4877
L38	52.0000-44.4100	-0.1667	-0.0563	-0.3183	-0.4916
L39	44.4100-43.4100	-0.0947	-0.0555	-0.0596	-0.4670
L40	43.4100-38.4100	-0.0949	-0.0557	-0.0604	-0.4673
L41	38.4100-34.5000	-0.0953	-0.0560	-0.0612	-0.4706
L42	34.5000-34.2500	-0.0954	-0.0562	-0.0616	-0.4720
L43	34.2500-33.5000	-0.0954	-0.0562	-0.0617	-0.4723
L44	33.5000-33.2500	-0.0955	-0.0562	-0.0618	-0.4726
L45	33.2500-29.5000	-0.1191	-0.0802	-0.0777	-0.4868
L46	29.5000-29.2500	-0.1645	-0.1263	-0.1087	-0.5137
L47	29.2500-28.5000	-0.1646	-0.1264	-0.1088	-0.5140
L48	28.5000-28.2500	-0.1646	-0.1264	-0.1090	-0.5143
L49	28.2500-27.4800	-0.1647	-0.1265	-0.1092	-0.5145
L50	27.4800-27.2300	-0.1648	-0.1265	-0.1094	-0.5148
L51	27.2300-22.2300	-0.1651	-0.1269	-0.1103	-0.5158
L52	22.2300-17.2300	-0.1657	-0.1274	-0.1122	-0.5167
L53	17.2300-12.2300	-0.1663	-0.1280	-0.1142	-0.5156
L54	12.2300-7.2300	-0.1669	-0.1285	-0.1167	-0.5110
L55	7.2300-6.9000	-0.1672	-0.1288	-0.1183	-0.5058
L56	6.9000-6.5500	-0.1672	-0.1288	-0.1185	-0.5050
L57	6.5500-6.3300	-0.1673	-0.1288	-0.1187	-0.5042
L58	6.3300-3.2500	-0.1357	-0.0968	-0.0699	-0.4549
L59	3.2500-3.0000	-0.1284	-0.0894	-0.0628	-0.4380
L60	3.0000-2.7500	-0.1284	-0.0894	-0.0637	-0.4366
L61	2.7500-2.5000	-0.1284	-0.0894	-0.0647	-0.4351

<b>tnxTower</b>  <b>Tower Engineering Professionals</b> 326 Tryon Road Raleigh, N.C. Phone: (919) 661-6351 FAX: (919) 661-6350	<b>Job</b> Preston / Town Hall (BU 876360)	<b>Page</b> 19 of 55
	<b>Project</b> TEP No. 25620.161151	<b>Date</b> 10:12:11 03/21/18
	<b>Client</b> Crown Castle	<b>Designed by</b> RKE

Section	Elevation	CP <sub>x</sub>	CP <sub>z</sub>	CP <sub>x</sub> Ice	CP <sub>z</sub> Ice
	ft	in	in	in	in
L62	2.5000-2.2500	-0.1284	-0.0894	-0.0658	-0.4334
L63	2.2500-2.0000	-0.1284	-0.0894	-0.0669	-0.4315
L64	2.0000-0.0000	-0.1285	-0.0895	-0.0748	-0.4184

### Shielding Factor Ka

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K <sub>a</sub> No Ice	K <sub>a</sub> Ice
L1	20	Safety Line 3/8	142.00 - 147.00	1.0000	1.0000
L1	21	Step Pegs (5/8" SR) 7-in. w/30" step	142.00 - 147.00	1.0000	1.0000
L2	20	Safety Line 3/8	137.00 - 142.00	1.0000	1.0000
L2	21	Step Pegs (5/8" SR) 7-in. w/30" step	137.00 - 142.00	1.0000	1.0000
L3	20	Safety Line 3/8	132.00 - 137.00	1.0000	1.0000
L3	21	Step Pegs (5/8" SR) 7-in. w/30" step	132.00 - 137.00	1.0000	1.0000
L4	10	MLE HYBRID 9POWER/18FIBER RL 2(1-5/8)	127.00 - 129.00	1.0000	1.0000
L4	20	Safety Line 3/8	127.00 - 132.00	1.0000	1.0000
L4	21	Step Pegs (5/8" SR) 7-in. w/30" step	127.00 - 132.00	1.0000	1.0000
L5	10	MLE HYBRID 9POWER/18FIBER RL 2(1-5/8)	120.37 - 127.00	1.0000	1.0000
L5	20	Safety Line 3/8	120.37 - 127.00	1.0000	1.0000
L5	21	Step Pegs (5/8" SR) 7-in. w/30" step	120.37 - 127.00	1.0000	1.0000
L7	10	MLE HYBRID 9POWER/18FIBER RL 2(1-5/8)	113.62 - 118.62	1.0000	1.0000
L7	20	Safety Line 3/8	113.62 - 118.62	1.0000	1.0000
L7	21	Step Pegs (5/8" SR) 7-in. w/30" step	113.62 - 118.62	1.0000	1.0000
L7	53	(Area) CCI-65FP-045125	113.62 - 115.08	1.0000	1.0000
L7	54	(Area) CCI-65FP-045125	113.62 - 114.16	1.0000	1.0000
L8	10	MLE HYBRID 9POWER/18FIBER RL 2(1-5/8)	112.41 - 113.62	1.0000	1.0000
L8	20	Safety Line 3/8	112.41 - 113.62	1.0000	1.0000
L8	21	Step Pegs (5/8" SR) 7-in. w/30" step	112.41 - 113.62	1.0000	1.0000
L8	53	(Area) CCI-65FP-045125	112.41 - 113.62	1.0000	1.0000
L8	54	(Area) CCI-65FP-045125	112.41 -	1.0000	1.0000

<b>tnxTower</b>  <b>Tower Engineering Professionals</b> 326 Tryon Road Raleigh, N.C. Phone: (919) 661-6351 FAX: (919) 661-6350	<b>Job</b> Preston / Town Hall (BU 876360)	<b>Page</b> 20 of 55
	<b>Project</b> TEP No. 25620.161151	<b>Date</b> 10:12:11 03/21/18
	<b>Client</b> Crown Castle	<b>Designed by</b> RKE

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K <sub>a</sub> No Ice	K <sub>a</sub> Ice
L9	10	MLE HYBRID 9POWER/18FIBER RL 2(1-5/8)	113.62 112.16 - 112.41	1.0000	1.0000
L9	20	Safety Line 3/8	112.16 - 112.41	1.0000	1.0000
L9	21	Step Pegs (5/8" SR) 7-in. w/30" step	112.16 - 112.41	1.0000	1.0000
L9	53	(Area) CCI-65FP-045125	112.16 - 112.41	1.0000	1.0000
L9	54	(Area) CCI-65FP-045125	112.16 - 112.41	1.0000	1.0000
L10	10	MLE HYBRID 9POWER/18FIBER RL 2(1-5/8)	110.50 - 112.16	1.0000	1.0000
L10	20	Safety Line 3/8	110.50 - 112.16	1.0000	1.0000
L10	21	Step Pegs (5/8" SR) 7-in. w/30" step	110.50 - 112.16	1.0000	1.0000
L10	47	(Area) CCI-65FP-045100	110.50 - 112.00	1.0000	1.0000
L10	48	(Area) CCI-65FP-045100	110.50 - 112.00	1.0000	1.0000
L10	53	(Area) CCI-65FP-045125	110.50 - 112.16	1.0000	1.0000
L10	54	(Area) CCI-65FP-045125	110.50 - 112.16	1.0000	1.0000
L11	10	MLE HYBRID 9POWER/18FIBER RL 2(1-5/8)	110.25 - 110.50	1.0000	1.0000
L11	20	Safety Line 3/8	110.25 - 110.50	1.0000	1.0000
L11	21	Step Pegs (5/8" SR) 7-in. w/30" step	110.25 - 110.50	1.0000	1.0000
L11	47	(Area) CCI-65FP-045100	110.25 - 110.50	1.0000	1.0000
L11	48	(Area) CCI-65FP-045100	110.25 - 110.50	1.0000	1.0000
L11	53	(Area) CCI-65FP-045125	110.25 - 110.50	1.0000	1.0000
L11	54	(Area) CCI-65FP-045125	110.25 - 110.50	1.0000	1.0000
L12	10	MLE HYBRID 9POWER/18FIBER RL 2(1-5/8)	105.25 - 110.25	1.0000	1.0000
L12	20	Safety Line 3/8	105.25 - 110.25	1.0000	1.0000
L12	21	Step Pegs (5/8" SR) 7-in. w/30" step	105.25 - 110.25	1.0000	1.0000
L12	32	PL 1.25x4.25	105.25 - 106.50	1.0000	1.0000
L12	33	PL 1.25x4.25	105.25 - 106.50	1.0000	1.0000
L12	47	(Area) CCI-65FP-045100	106.50 - 110.25	1.0000	1.0000
L12	48	(Area) CCI-65FP-045100	106.50 - 110.25	1.0000	1.0000
L12	53	(Area) CCI-65FP-045125	106.50 - 110.25	1.0000	1.0000
L12	54	(Area) CCI-65FP-045125	106.50 - 110.25	1.0000	1.0000
L13	10	MLE HYBRID	105.00 -	1.0000	1.0000

<b>tnxTower</b>  <b>Tower Engineering Professionals</b> 326 Tryon Road Raleigh, N.C. Phone: (919) 661-6351 FAX: (919) 661-6350	<b>Job</b> Preston / Town Hall (BU 876360)	<b>Page</b> 21 of 55
	<b>Project</b> TEP No. 25620.161151	<b>Date</b> 10:12:11 03/21/18
	<b>Client</b> Crown Castle	<b>Designed by</b> RKE

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K <sub>a</sub> No Ice	K <sub>a</sub> Ice
		9POWER/18FIBER RL 2(1-5/8)	105.25		
L13	20	Safety Line 3/8	105.00 - 105.25	1.0000	1.0000
L13	21	Step Pegs (5/8" SR) 7-in. w/30" step	105.00 - 105.25	1.0000	1.0000
L13	32	PL 1.25x4.25	105.00 - 105.25	1.0000	1.0000
L13	33	PL 1.25x4.25	105.00 - 105.25	1.0000	1.0000
L14	10	MLE HYBRID	104.75 - 105.00	1.0000	1.0000
		9POWER/18FIBER RL 2(1-5/8)	105.00		
L14	20	Safety Line 3/8	104.75 - 105.00	1.0000	1.0000
L14	21	Step Pegs (5/8" SR) 7-in. w/30" step	104.75 - 105.00	1.0000	1.0000
L14	32	PL 1.25x4.25	104.75 - 105.00	1.0000	1.0000
L14	33	PL 1.25x4.25	104.75 - 105.00	1.0000	1.0000
L15	10	MLE HYBRID	103.50 - 104.75	1.0000	1.0000
		9POWER/18FIBER RL 2(1-5/8)	104.75		
L15	20	Safety Line 3/8	103.50 - 104.75	1.0000	1.0000
L15	21	Step Pegs (5/8" SR) 7-in. w/30" step	103.50 - 104.75	1.0000	1.0000
L15	32	PL 1.25x4.25	103.50 - 104.75	1.0000	1.0000
L15	33	PL 1.25x4.25	103.50 - 104.75	1.0000	1.0000
L16	10	MLE HYBRID	103.25 - 103.50	1.0000	1.0000
		9POWER/18FIBER RL 2(1-5/8)	103.50		
L16	20	Safety Line 3/8	103.25 - 103.50	1.0000	1.0000
L16	21	Step Pegs (5/8" SR) 7-in. w/30" step	103.25 - 103.50	1.0000	1.0000
L16	32	PL 1.25x4.25	103.25 - 103.50	1.0000	1.0000
L16	33	PL 1.25x4.25	103.25 - 103.50	1.0000	1.0000
L17	10	MLE HYBRID	98.25 - 103.25	1.0000	1.0000
		9POWER/18FIBER RL 2(1-5/8)			
L17	20	Safety Line 3/8	98.25 - 103.25	1.0000	1.0000
L17	21	Step Pegs (5/8" SR) 7-in. w/30" step	98.25 - 103.25	1.0000	1.0000
L17	32	PL 1.25x4.25	98.25 - 103.25	1.0000	1.0000
L17	33	PL 1.25x4.25	98.25 - 103.25	1.0000	1.0000
L18	10	MLE HYBRID	94.83 - 98.25	1.0000	1.0000
		9POWER/18FIBER RL 2(1-5/8)			
L18	20	Safety Line 3/8	94.83 - 98.25	1.0000	1.0000
L18	21	Step Pegs (5/8" SR) 7-in. w/30" step	94.83 - 98.25	1.0000	1.0000
L18	32	PL 1.25x4.25	94.83 - 98.25	1.0000	1.0000
L18	33	PL 1.25x4.25	94.83 - 98.25	1.0000	1.0000
L18	44	(Area) CCI-65FP-040075	94.83 - 95.67	1.0000	1.0000
L18	45	(Area) CCI-65FP-040075	94.83 - 95.67	1.0000	1.0000
L19	10	MLE HYBRID	94.58 - 94.83	1.0000	1.0000



<b>tnxTower</b>  <b>Tower Engineering Professionals</b> 326 Tryon Road Raleigh, N.C. Phone: (919) 661-6351 FAX: (919) 661-6350	<b>Job</b> Preston / Town Hall (BU 876360)	<b>Page</b> 22 of 55
	<b>Project</b> TEP No. 25620.161151	<b>Date</b> 10:12:11 03/21/18
	<b>Client</b> Crown Castle	<b>Designed by</b> RKE

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K <sub>a</sub> No Ice	K <sub>a</sub> Ice
		9POWER/18FIBER RL 2(1-5/8)			
L19	20	Safety Line 3/8	94.58 - 94.83	1.0000	1.0000
L19	21	Step Pegs (5/8" SR) 7-in. w/30" step	94.58 - 94.83	1.0000	1.0000
L19	32	PL 1.25x4.25	94.58 - 94.83	1.0000	1.0000
L19	33	PL 1.25x4.25	94.58 - 94.83	1.0000	1.0000
L19	44	(Area) CCI-65FP-040075	94.58 - 94.83	1.0000	1.0000
L19	45	(Area) CCI-65FP-040075	94.58 - 94.83	1.0000	1.0000
L20	10	MLE HYBRID	94.17 - 94.58	1.0000	1.0000
		9POWER/18FIBER RL 2(1-5/8)			
L20	20	Safety Line 3/8	94.17 - 94.58	1.0000	1.0000
L20	21	Step Pegs (5/8" SR) 7-in. w/30" step	94.17 - 94.58	1.0000	1.0000
L20	32	PL 1.25x4.25	94.17 - 94.58	1.0000	1.0000
L20	33	PL 1.25x4.25	94.17 - 94.58	1.0000	1.0000
L20	44	(Area) CCI-65FP-040075	94.17 - 94.58	1.0000	1.0000
L20	45	(Area) CCI-65FP-040075	94.17 - 94.58	1.0000	1.0000
L21	10	MLE HYBRID	93.82 - 94.17	1.0000	1.0000
		9POWER/18FIBER RL 2(1-5/8)			
L21	20	Safety Line 3/8	93.82 - 94.17	1.0000	1.0000
L21	21	Step Pegs (5/8" SR) 7-in. w/30" step	93.82 - 94.17	1.0000	1.0000
L21	32	PL 1.25x4.25	93.82 - 94.17	1.0000	1.0000
L21	33	PL 1.25x4.25	93.82 - 94.17	1.0000	1.0000
L21	44	(Area) CCI-65FP-040075	93.82 - 94.17	1.0000	1.0000
L21	45	(Area) CCI-65FP-040075	93.82 - 94.17	1.0000	1.0000
L22	10	MLE HYBRID	93.66 - 93.82	1.0000	1.0000
		9POWER/18FIBER RL 2(1-5/8)			
L22	20	Safety Line 3/8	93.66 - 93.82	1.0000	1.0000
L22	21	Step Pegs (5/8" SR) 7-in. w/30" step	93.66 - 93.82	1.0000	1.0000
L22	32	PL 1.25x4.25	93.66 - 93.82	1.0000	1.0000
L22	33	PL 1.25x4.25	93.66 - 93.82	1.0000	1.0000
L22	44	(Area) CCI-65FP-040075	93.66 - 93.82	1.0000	1.0000
L22	45	(Area) CCI-65FP-040075	93.66 - 93.82	1.0000	1.0000
L23	10	MLE HYBRID	84.91 - 93.66	1.0000	1.0000
		9POWER/18FIBER RL 2(1-5/8)			
L23	20	Safety Line 3/8	84.91 - 93.66	1.0000	1.0000
L23	21	Step Pegs (5/8" SR) 7-in. w/30" step	84.91 - 93.66	1.0000	1.0000
L23	29	PL 1.25x4.75	84.91 - 89.25	1.0000	1.0000
L23	30	PL 1.25x4.75	84.91 - 89.25	1.0000	1.0000
L23	32	PL 1.25x4.25	89.25 - 93.66	1.0000	1.0000
L23	33	PL 1.25x4.25	89.25 - 93.66	1.0000	1.0000
L23	44	(Area) CCI-65FP-040075	84.91 - 93.66	1.0000	1.0000
L23	45	(Area) CCI-65FP-040075	84.91 - 93.66	1.0000	1.0000
L25	10	MLE HYBRID	78.91 - 83.91	1.0000	1.0000
		9POWER/18FIBER RL 2(1-5/8)			
L25	20	Safety Line 3/8	78.91 - 83.91	1.0000	1.0000
L25	21	Step Pegs (5/8" SR) 7-in. w/30" step	78.91 - 83.91	1.0000	1.0000
L25	29	PL 1.25x4.75	78.91 - 83.91	1.0000	1.0000
L25	30	PL 1.25x4.75	78.91 - 83.91	1.0000	1.0000
L25	44	(Area) CCI-65FP-040075	78.91 - 83.91	1.0000	1.0000
L25	45	(Area) CCI-65FP-040075	78.91 - 83.91	1.0000	1.0000
L26	10	MLE HYBRID	73.91 - 78.91	1.0000	1.0000

<b>tnxTower</b>  <b>Tower Engineering Professionals</b> 326 Tryon Road Raleigh, N.C. Phone: (919) 661-6351 FAX: (919) 661-6350	<b>Job</b> Preston / Town Hall (BU 876360)	<b>Page</b> 23 of 55
	<b>Project</b> TEP No. 25620.161151	<b>Date</b> 10:12:11 03/21/18
	<b>Client</b> Crown Castle	<b>Designed by</b> RKE

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K <sub>a</sub> No Ice	K <sub>a</sub> Ice
		9POWER/18FIBER RL 2(1-5/8)			
L26	20	Safety Line 3/8	73.91 - 78.91	1.0000	1.0000
L26	21	Step Pegs (5/8" SR) 7-in. w/30" step	73.91 - 78.91	1.0000	1.0000
L26	29	PL 1.25x4.75	73.91 - 78.91	1.0000	1.0000
L26	30	PL 1.25x4.75	73.91 - 78.91	1.0000	1.0000
L26	44	(Area) CCI-65FP-040075	73.91 - 78.91	1.0000	1.0000
L26	45	(Area) CCI-65FP-040075	73.91 - 78.91	1.0000	1.0000
L27	10	MLE HYBRID	68.91 - 73.91	1.0000	1.0000
		9POWER/18FIBER RL 2(1-5/8)			
L27	20	Safety Line 3/8	68.91 - 73.91	1.0000	1.0000
L27	21	Step Pegs (5/8" SR) 7-in. w/30" step	68.91 - 73.91	1.0000	1.0000
L27	29	PL 1.25x4.75	68.91 - 73.91	1.0000	1.0000
L27	30	PL 1.25x4.75	68.91 - 73.91	1.0000	1.0000
L27	44	(Area) CCI-65FP-040075	68.91 - 73.91	1.0000	1.0000
L27	45	(Area) CCI-65FP-040075	68.91 - 73.91	1.0000	1.0000
L28	10	MLE HYBRID	65.50 - 68.91	1.0000	1.0000
		9POWER/18FIBER RL 2(1-5/8)			
L28	20	Safety Line 3/8	65.50 - 68.91	1.0000	1.0000
L28	21	Step Pegs (5/8" SR) 7-in. w/30" step	65.50 - 68.91	1.0000	1.0000
L28	29	PL 1.25x4.75	65.50 - 68.91	1.0000	1.0000
L28	30	PL 1.25x4.75	65.50 - 68.91	1.0000	1.0000
L28	44	(Area) CCI-65FP-040075	65.50 - 68.91	1.0000	1.0000
L28	45	(Area) CCI-65FP-040075	65.50 - 68.91	1.0000	1.0000
L29	10	MLE HYBRID	65.25 - 65.50	1.0000	1.0000
		9POWER/18FIBER RL 2(1-5/8)			
L29	20	Safety Line 3/8	65.25 - 65.50	1.0000	1.0000
L29	21	Step Pegs (5/8" SR) 7-in. w/30" step	65.25 - 65.50	1.0000	1.0000
L29	29	PL 1.25x4.75	65.25 - 65.50	1.0000	1.0000
L29	30	PL 1.25x4.75	65.25 - 65.50	1.0000	1.0000
L29	44	(Area) CCI-65FP-040075	65.25 - 65.50	1.0000	1.0000
L29	45	(Area) CCI-65FP-040075	65.25 - 65.50	1.0000	1.0000
L30	10	MLE HYBRID	64.50 - 65.25	1.0000	1.0000
		9POWER/18FIBER RL 2(1-5/8)			
L30	20	Safety Line 3/8	64.50 - 65.25	1.0000	1.0000
L30	21	Step Pegs (5/8" SR) 7-in. w/30" step	64.50 - 65.25	1.0000	1.0000
L30	29	PL 1.25x4.75	64.50 - 65.25	1.0000	1.0000
L30	30	PL 1.25x4.75	64.50 - 65.25	1.0000	1.0000
L30	44	(Area) CCI-65FP-040075	64.50 - 65.25	1.0000	1.0000
L30	45	(Area) CCI-65FP-040075	64.50 - 65.25	1.0000	1.0000
L31	10	MLE HYBRID	64.25 - 64.50	1.0000	1.0000
		9POWER/18FIBER RL 2(1-5/8)			
L31	20	Safety Line 3/8	64.25 - 64.50	1.0000	1.0000
L31	21	Step Pegs (5/8" SR) 7-in. w/30" step	64.25 - 64.50	1.0000	1.0000
L31	29	PL 1.25x4.75	64.25 - 64.50	1.0000	1.0000
L31	30	PL 1.25x4.75	64.25 - 64.50	1.0000	1.0000
L31	44	(Area) CCI-65FP-040075	64.25 - 64.50	1.0000	1.0000
L31	45	(Area) CCI-65FP-040075	64.25 - 64.50	1.0000	1.0000
L32	10	MLE HYBRID	59.25 - 64.25	1.0000	1.0000
		9POWER/18FIBER RL 2(1-5/8)			

<b>tnxTower</b>  <b>Tower Engineering Professionals</b> 326 Tryon Road Raleigh, N.C. Phone: (919) 661-6351 FAX: (919) 661-6350	<b>Job</b> Preston / Town Hall (BU 876360)	<b>Page</b> 24 of 55
	<b>Project</b> TEP No. 25620.161151	<b>Date</b> 10:12:11 03/21/18
	<b>Client</b> Crown Castle	<b>Designed by</b> RKE

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K <sub>a</sub> No Ice	K <sub>a</sub> Ice
L32	20	Safety Line 3/8	59.25 - 64.25	1.0000	1.0000
L32	21	Step Pegs (5/8" SR) 7-in. w/30" step	59.25 - 64.25	1.0000	1.0000
L32	26	PL 1.25x5	59.25 - 59.50	1.0000	1.0000
L32	27	PL 1.25x5	59.25 - 59.50	1.0000	1.0000
L32	29	PL 1.25x4.75	59.50 - 64.25	1.0000	1.0000
L32	30	PL 1.25x4.75	59.50 - 64.25	1.0000	1.0000
L32	41	(Area) CCI-65FP-045100	59.25 - 60.58	1.0000	1.0000
L32	42	(Area) CCI-65FP-045100	59.25 - 60.58	1.0000	1.0000
L32	44	(Area) CCI-65FP-040075	60.58 - 64.25	1.0000	1.0000
L32	45	(Area) CCI-65FP-040075	60.58 - 64.25	1.0000	1.0000
L33	10	MLE HYBRID 9POWER/18FIBER RL 2(1-5/8)	58.58 - 59.25	1.0000	1.0000
L33	20	Safety Line 3/8	58.58 - 59.25	1.0000	1.0000
L33	21	Step Pegs (5/8" SR) 7-in. w/30" step	58.58 - 59.25	1.0000	1.0000
L33	26	PL 1.25x5	58.58 - 59.25	1.0000	1.0000
L33	27	PL 1.25x5	58.58 - 59.25	1.0000	1.0000
L33	41	(Area) CCI-65FP-045100	58.58 - 59.25	1.0000	1.0000
L33	42	(Area) CCI-65FP-045100	58.58 - 59.25	1.0000	1.0000
L34	10	MLE HYBRID 9POWER/18FIBER RL 2(1-5/8)	58.33 - 58.58	1.0000	1.0000
L34	20	Safety Line 3/8	58.33 - 58.58	1.0000	1.0000
L34	21	Step Pegs (5/8" SR) 7-in. w/30" step	58.33 - 58.58	1.0000	1.0000
L34	26	PL 1.25x5	58.33 - 58.58	1.0000	1.0000
L34	27	PL 1.25x5	58.33 - 58.58	1.0000	1.0000
L34	41	(Area) CCI-65FP-045100	58.33 - 58.58	1.0000	1.0000
L34	42	(Area) CCI-65FP-045100	58.33 - 58.58	1.0000	1.0000
L35	10	MLE HYBRID 9POWER/18FIBER RL 2(1-5/8)	57.25 - 58.33	1.0000	1.0000
L35	20	Safety Line 3/8	57.25 - 58.33	1.0000	1.0000
L35	21	Step Pegs (5/8" SR) 7-in. w/30" step	57.25 - 58.33	1.0000	1.0000
L35	26	PL 1.25x5	57.25 - 58.33	1.0000	1.0000
L35	27	PL 1.25x5	57.25 - 58.33	1.0000	1.0000
L35	41	(Area) CCI-65FP-045100	57.25 - 58.33	1.0000	1.0000
L35	42	(Area) CCI-65FP-045100	57.25 - 58.33	1.0000	1.0000
L36	10	MLE HYBRID 9POWER/18FIBER RL 2(1-5/8)	57.00 - 57.25	1.0000	1.0000
L36	20	Safety Line 3/8	57.00 - 57.25	1.0000	1.0000
L36	21	Step Pegs (5/8" SR) 7-in. w/30" step	57.00 - 57.25	1.0000	1.0000
L36	26	PL 1.25x5	57.00 - 57.25	1.0000	1.0000
L36	27	PL 1.25x5	57.00 - 57.25	1.0000	1.0000
L36	41	(Area) CCI-65FP-045100	57.00 - 57.25	1.0000	1.0000
L36	42	(Area) CCI-65FP-045100	57.00 - 57.25	1.0000	1.0000
L37	10	MLE HYBRID 9POWER/18FIBER RL 2(1-5/8)	52.00 - 57.00	1.0000	1.0000
L37	20	Safety Line 3/8	52.00 - 57.00	1.0000	1.0000
L37	21	Step Pegs (5/8" SR) 7-in. w/30" step	52.00 - 57.00	1.0000	1.0000
L37	26	PL 1.25x5	52.00 - 57.00	1.0000	1.0000
L37	27	PL 1.25x5	52.00 - 57.00	1.0000	1.0000
L37	41	(Area) CCI-65FP-045100	52.00 - 57.00	1.0000	1.0000
L37	42	(Area) CCI-65FP-045100	52.00 - 57.00	1.0000	1.0000
L38	10	MLE HYBRID	44.41 - 52.00	1.0000	1.0000

<b>tnxTower</b>  <b>Tower Engineering Professionals</b> 326 Tryon Road Raleigh, N.C. Phone: (919) 661-6351 FAX: (919) 661-6350	Job	Preston / Town Hall (BU 876360)	Page	25 of 55
	Project	TEP No. 25620.161151	Date	10:12:11 03/21/18
	Client	Crown Castle	Designed by	RKE

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K <sub>a</sub> No Ice	K <sub>a</sub> Ice
		9POWER/18FIBER RL 2(1-5/8)			
L38	18	LDF4-50A(1/2)	44.41 - 45.00	1.0000	1.0000
L38	20	Safety Line 3/8	44.41 - 52.00	1.0000	1.0000
L38	21	Step Pegs (5/8" SR) 7-in. w/30" step	44.41 - 52.00	1.0000	1.0000
L38	26	PL 1.25x5	44.41 - 52.00	1.0000	1.0000
L38	27	PL 1.25x5	44.41 - 52.00	1.0000	1.0000
L38	41	(Area) CCI-65FP-045100	44.41 - 52.00	1.0000	1.0000
L38	42	(Area) CCI-65FP-045100	44.41 - 52.00	1.0000	1.0000
L40	10	MLE HYBRID	38.41 - 43.41	1.0000	1.0000
		9POWER/18FIBER RL 2(1-5/8)			
L40	18	LDF4-50A(1/2)	38.41 - 43.41	1.0000	1.0000
L40	20	Safety Line 3/8	38.41 - 43.41	1.0000	1.0000
L40	21	Step Pegs (5/8" SR) 7-in. w/30" step	38.41 - 43.41	1.0000	1.0000
L40	26	PL 1.25x5	38.41 - 43.41	1.0000	1.0000
L40	27	PL 1.25x5	38.41 - 43.41	1.0000	1.0000
L40	41	(Area) CCI-65FP-045100	38.41 - 43.41	1.0000	1.0000
L40	42	(Area) CCI-65FP-045100	38.41 - 43.41	1.0000	1.0000
L41	10	MLE HYBRID	34.50 - 38.41	1.0000	1.0000
		9POWER/18FIBER RL 2(1-5/8)			
L41	18	LDF4-50A(1/2)	34.50 - 38.41	1.0000	1.0000
L41	20	Safety Line 3/8	34.50 - 38.41	1.0000	1.0000
L41	21	Step Pegs (5/8" SR) 7-in. w/30" step	34.50 - 38.41	1.0000	1.0000
L41	26	PL 1.25x5	34.50 - 38.41	1.0000	1.0000
L41	27	PL 1.25x5	34.50 - 38.41	1.0000	1.0000
L41	41	(Area) CCI-65FP-045100	34.50 - 38.41	1.0000	1.0000
L41	42	(Area) CCI-65FP-045100	34.50 - 38.41	1.0000	1.0000
L42	10	MLE HYBRID	34.25 - 34.50	1.0000	1.0000
		9POWER/18FIBER RL 2(1-5/8)			
L42	18	LDF4-50A(1/2)	34.25 - 34.50	1.0000	1.0000
L42	20	Safety Line 3/8	34.25 - 34.50	1.0000	1.0000
L42	21	Step Pegs (5/8" SR) 7-in. w/30" step	34.25 - 34.50	1.0000	1.0000
L42	26	PL 1.25x5	34.25 - 34.50	1.0000	1.0000
L42	27	PL 1.25x5	34.25 - 34.50	1.0000	1.0000
L42	41	(Area) CCI-65FP-045100	34.25 - 34.50	1.0000	1.0000
L42	42	(Area) CCI-65FP-045100	34.25 - 34.50	1.0000	1.0000
L43	10	MLE HYBRID	33.50 - 34.25	1.0000	1.0000
		9POWER/18FIBER RL 2(1-5/8)			
L43	18	LDF4-50A(1/2)	33.50 - 34.25	1.0000	1.0000
L43	20	Safety Line 3/8	33.50 - 34.25	1.0000	1.0000
L43	21	Step Pegs (5/8" SR) 7-in. w/30" step	33.50 - 34.25	1.0000	1.0000
L43	26	PL 1.25x5	33.50 - 34.25	1.0000	1.0000
L43	27	PL 1.25x5	33.50 - 34.25	1.0000	1.0000
L43	41	(Area) CCI-65FP-045100	33.50 - 34.25	1.0000	1.0000
L43	42	(Area) CCI-65FP-045100	33.50 - 34.25	1.0000	1.0000
L44	10	MLE HYBRID	33.25 - 33.50	1.0000	1.0000
		9POWER/18FIBER RL 2(1-5/8)			
L44	18	LDF4-50A(1/2)	33.25 - 33.50	1.0000	1.0000
L44	20	Safety Line 3/8	33.25 - 33.50	1.0000	1.0000
L44	21	Step Pegs (5/8" SR) 7-in. w/30" step	33.25 - 33.50	1.0000	1.0000
L44	26	PL 1.25x5	33.25 - 33.50	1.0000	1.0000

<b>tnxTower</b>  <b>Tower Engineering Professionals</b> 326 Tryon Road Raleigh, N.C. Phone: (919) 661-6351 FAX: (919) 661-6350	<b>Job</b> Preston / Town Hall (BU 876360)	<b>Page</b> 26 of 55
	<b>Project</b> TEP No. 25620.161151	<b>Date</b> 10:12:11 03/21/18
	<b>Client</b> Crown Castle	<b>Designed by</b> RKE

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K <sub>a</sub> No Ice	K <sub>a</sub> Ice
L44	27	PL 1.25x5	33.25 - 33.50	1.0000	1.0000
L44	41	(Area) CCI-65FP-045100	33.25 - 33.50	1.0000	1.0000
L44	42	(Area) CCI-65FP-045100	33.25 - 33.50	1.0000	1.0000
L45	10	MLE HYBRID	29.50 - 33.25	1.0000	1.0000
		9POWER/18FIBER RL			
		2(1-5/8)			
L45	18	LDF4-50A(1/2)	29.50 - 33.25	1.0000	1.0000
L45	20	Safety Line 3/8	29.50 - 33.25	1.0000	1.0000
L45	21	Step Pegs (5/8" SR) 7-in.	29.50 - 33.25	1.0000	1.0000
		w/30" step			
L45	23	PL 1.25x5	29.50 - 29.75	1.0000	1.0000
L45	24	PL 1.25x5	29.50 - 29.75	1.0000	1.0000
L45	26	PL 1.25x5	29.75 - 33.25	1.0000	1.0000
L45	27	PL 1.25x5	29.75 - 33.25	1.0000	1.0000
L45	35	(Area) Aero MP3-03	29.50 - 30.75	1.0000	1.0000
L45	36	(Area) Aero MP3-03	29.50 - 30.75	1.0000	1.0000
L45	41	(Area) CCI-65FP-045100	30.75 - 33.25	1.0000	1.0000
L45	42	(Area) CCI-65FP-045100	30.75 - 33.25	1.0000	1.0000
L46	10	MLE HYBRID	29.25 - 29.50	1.0000	1.0000
		9POWER/18FIBER RL			
		2(1-5/8)			
L46	18	LDF4-50A(1/2)	29.25 - 29.50	1.0000	1.0000
L46	20	Safety Line 3/8	29.25 - 29.50	1.0000	1.0000
L46	21	Step Pegs (5/8" SR) 7-in.	29.25 - 29.50	1.0000	1.0000
		w/30" step			
L46	23	PL 1.25x5	29.25 - 29.50	1.0000	1.0000
L46	24	PL 1.25x5	29.25 - 29.50	1.0000	1.0000
L46	35	(Area) Aero MP3-03	29.25 - 29.50	1.0000	1.0000
L46	36	(Area) Aero MP3-03	29.25 - 29.50	1.0000	1.0000
L47	10	MLE HYBRID	28.50 - 29.25	1.0000	1.0000
		9POWER/18FIBER RL			
		2(1-5/8)			
L47	18	LDF4-50A(1/2)	28.50 - 29.25	1.0000	1.0000
L47	20	Safety Line 3/8	28.50 - 29.25	1.0000	1.0000
L47	21	Step Pegs (5/8" SR) 7-in.	28.50 - 29.25	1.0000	1.0000
		w/30" step			
L47	23	PL 1.25x5	28.50 - 29.25	1.0000	1.0000
L47	24	PL 1.25x5	28.50 - 29.25	1.0000	1.0000
L47	35	(Area) Aero MP3-03	28.50 - 29.25	1.0000	1.0000
L47	36	(Area) Aero MP3-03	28.50 - 29.25	1.0000	1.0000
L48	10	MLE HYBRID	28.25 - 28.50	1.0000	1.0000
		9POWER/18FIBER RL			
		2(1-5/8)			
L48	18	LDF4-50A(1/2)	28.25 - 28.50	1.0000	1.0000
L48	20	Safety Line 3/8	28.25 - 28.50	1.0000	1.0000
L48	21	Step Pegs (5/8" SR) 7-in.	28.25 - 28.50	1.0000	1.0000
		w/30" step			
L48	23	PL 1.25x5	28.25 - 28.50	1.0000	1.0000
L48	24	PL 1.25x5	28.25 - 28.50	1.0000	1.0000
L48	35	(Area) Aero MP3-03	28.25 - 28.50	1.0000	1.0000
L48	36	(Area) Aero MP3-03	28.25 - 28.50	1.0000	1.0000
L49	10	MLE HYBRID	27.48 - 28.25	1.0000	1.0000
		9POWER/18FIBER RL			
		2(1-5/8)			
L49	18	LDF4-50A(1/2)	27.48 - 28.25	1.0000	1.0000
L49	20	Safety Line 3/8	27.48 - 28.25	1.0000	1.0000
L49	21	Step Pegs (5/8" SR) 7-in.	27.48 - 28.25	1.0000	1.0000
		w/30" step			
L49	23	PL 1.25x5	27.48 - 28.25	1.0000	1.0000
L49	24	PL 1.25x5	27.48 - 28.25	1.0000	1.0000
L49	35	(Area) Aero MP3-03	27.48 - 28.25	1.0000	1.0000
L49	36	(Area) Aero MP3-03	27.48 - 28.25	1.0000	1.0000

<b>tnxTower</b>  <b>Tower Engineering Professionals</b> 326 Tryon Road Raleigh, N.C. Phone: (919) 661-6351 FAX: (919) 661-6350	<b>Job</b> Preston / Town Hall (BU 876360)	<b>Page</b> 27 of 55
	<b>Project</b> TEP No. 25620.161151	<b>Date</b> 10:12:11 03/21/18
	<b>Client</b> Crown Castle	<b>Designed by</b> RKE

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K <sub>a</sub> No Ice	K <sub>a</sub> Ice
L50	10	MLE HYBRID 9POWER/18FIBER RL 2(1-5/8)	27.23 - 27.48	1.0000	1.0000
L50	18	LDF4-50A(1/2)	27.23 - 27.48	1.0000	1.0000
L50	20	Safety Line 3/8	27.23 - 27.48	1.0000	1.0000
L50	21	Step Pegs (5/8" SR) 7-in. w/30" step	27.23 - 27.48	1.0000	1.0000
L50	23	PL 1.25x5	27.23 - 27.48	1.0000	1.0000
L50	24	PL 1.25x5	27.23 - 27.48	1.0000	1.0000
L50	35	(Area) Aero MP3-03	27.23 - 27.48	1.0000	1.0000
L50	36	(Area) Aero MP3-03	27.23 - 27.48	1.0000	1.0000
L51	10	MLE HYBRID 9POWER/18FIBER RL 2(1-5/8)	22.23 - 27.23	1.0000	1.0000
L51	18	LDF4-50A(1/2)	22.23 - 27.23	1.0000	1.0000
L51	20	Safety Line 3/8	22.23 - 27.23	1.0000	1.0000
L51	21	Step Pegs (5/8" SR) 7-in. w/30" step	22.23 - 27.23	1.0000	1.0000
L51	23	PL 1.25x5	22.23 - 27.23	1.0000	1.0000
L51	24	PL 1.25x5	22.23 - 27.23	1.0000	1.0000
L51	35	(Area) Aero MP3-03	22.23 - 27.23	1.0000	1.0000
L51	36	(Area) Aero MP3-03	22.23 - 27.23	1.0000	1.0000
L52	10	MLE HYBRID 9POWER/18FIBER RL 2(1-5/8)	17.23 - 22.23	1.0000	1.0000
L52	18	LDF4-50A(1/2)	17.23 - 22.23	1.0000	1.0000
L52	20	Safety Line 3/8	17.23 - 22.23	1.0000	1.0000
L52	21	Step Pegs (5/8" SR) 7-in. w/30" step	17.23 - 22.23	1.0000	1.0000
L52	23	PL 1.25x5	17.23 - 22.23	1.0000	1.0000
L52	24	PL 1.25x5	17.23 - 22.23	1.0000	1.0000
L52	35	(Area) Aero MP3-03	17.23 - 22.23	1.0000	1.0000
L52	36	(Area) Aero MP3-03	17.23 - 22.23	1.0000	1.0000
L53	10	MLE HYBRID 9POWER/18FIBER RL 2(1-5/8)	12.23 - 17.23	1.0000	1.0000
L53	18	LDF4-50A(1/2)	12.23 - 17.23	1.0000	1.0000
L53	20	Safety Line 3/8	12.23 - 17.23	1.0000	1.0000
L53	21	Step Pegs (5/8" SR) 7-in. w/30" step	12.23 - 17.23	1.0000	1.0000
L53	23	PL 1.25x5	12.23 - 17.23	1.0000	1.0000
L53	24	PL 1.25x5	12.23 - 17.23	1.0000	1.0000
L53	35	(Area) Aero MP3-03	12.23 - 17.23	1.0000	1.0000
L53	36	(Area) Aero MP3-03	12.23 - 17.23	1.0000	1.0000
L54	10	MLE HYBRID 9POWER/18FIBER RL 2(1-5/8)	7.23 - 12.23	1.0000	1.0000
L54	18	LDF4-50A(1/2)	7.23 - 12.23	1.0000	1.0000
L54	20	Safety Line 3/8	7.23 - 12.23	1.0000	1.0000
L54	21	Step Pegs (5/8" SR) 7-in. w/30" step	7.23 - 12.23	1.0000	1.0000
L54	23	PL 1.25x5	7.23 - 12.23	1.0000	1.0000
L54	24	PL 1.25x5	7.23 - 12.23	1.0000	1.0000
L54	35	(Area) Aero MP3-03	7.23 - 12.23	1.0000	1.0000
L54	36	(Area) Aero MP3-03	7.23 - 12.23	1.0000	1.0000
L55	10	MLE HYBRID 9POWER/18FIBER RL 2(1-5/8)	6.90 - 7.23	1.0000	1.0000
L55	18	LDF4-50A(1/2)	6.90 - 7.23	1.0000	1.0000
L55	20	Safety Line 3/8	6.90 - 7.23	1.0000	1.0000
L55	21	Step Pegs (5/8" SR) 7-in. w/30" step	6.90 - 7.23	1.0000	1.0000

<b>tnxTower</b>  <b>Tower Engineering Professionals</b> 326 Tryon Road Raleigh, N.C. Phone: (919) 661-6351 FAX: (919) 661-6350	<b>Job</b> Preston / Town Hall (BU 876360)	<b>Page</b> 28 of 55
	<b>Project</b> TEP No. 25620.161151	<b>Date</b> 10:12:11 03/21/18
	<b>Client</b> Crown Castle	<b>Designed by</b> RKE

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K <sub>a</sub> No Ice	K <sub>a</sub> Ice
L55	23	PL 1.25x5	6.90 - 7.23	1.0000	1.0000
L55	24	PL 1.25x5	6.90 - 7.23	1.0000	1.0000
L55	35	(Area) Aero MP3-03	6.90 - 7.23	1.0000	1.0000
L55	36	(Area) Aero MP3-03	6.90 - 7.23	1.0000	1.0000
L56	10	MLE HYBRID 9POWER/18FIBER RL 2(1-5/8)	6.55 - 6.90	1.0000	1.0000
L56	18	LDF4-50A(1/2)	6.55 - 6.90	1.0000	1.0000
L56	20	Safety Line 3/8	6.55 - 6.90	1.0000	1.0000
L56	21	Step Pegs (5/8" SR) 7-in. w/30" step	6.55 - 6.90	1.0000	1.0000
L56	23	PL 1.25x5	6.55 - 6.90	1.0000	1.0000
L56	24	PL 1.25x5	6.55 - 6.90	1.0000	1.0000
L56	35	(Area) Aero MP3-03	6.55 - 6.90	1.0000	1.0000
L56	36	(Area) Aero MP3-03	6.55 - 6.90	1.0000	1.0000
L57	10	MLE HYBRID 9POWER/18FIBER RL 2(1-5/8)	6.33 - 6.55	1.0000	1.0000
L57	18	LDF4-50A(1/2)	6.33 - 6.55	1.0000	1.0000
L57	20	Safety Line 3/8	6.33 - 6.55	1.0000	1.0000
L57	21	Step Pegs (5/8" SR) 7-in. w/30" step	6.33 - 6.55	1.0000	1.0000
L57	23	PL 1.25x5	6.33 - 6.55	1.0000	1.0000
L57	24	PL 1.25x5	6.33 - 6.55	1.0000	1.0000
L57	35	(Area) Aero MP3-03	6.33 - 6.55	1.0000	1.0000
L57	36	(Area) Aero MP3-03	6.33 - 6.55	1.0000	1.0000
L58	10	MLE HYBRID 9POWER/18FIBER RL 2(1-5/8)	3.25 - 6.33	1.0000	1.0000
L58	18	LDF4-50A(1/2)	3.25 - 6.33	1.0000	1.0000
L58	20	Safety Line 3/8	3.25 - 6.33	1.0000	1.0000
L58	21	Step Pegs (5/8" SR) 7-in. w/30" step	3.25 - 6.33	1.0000	1.0000
L58	23	PL 1.25x5	3.25 - 6.33	1.0000	1.0000
L58	24	PL 1.25x5	3.25 - 6.33	1.0000	1.0000
L58	35	(Area) Aero MP3-03	5.75 - 6.33	1.0000	1.0000
L58	36	(Area) Aero MP3-03	5.75 - 6.33	1.0000	1.0000
L58	50	(Area) CCI-65FP-045125	3.25 - 5.75	1.0000	1.0000
L58	51	(Area) CCI-65FP-045125	3.25 - 5.75	1.0000	1.0000
L59	10	MLE HYBRID 9POWER/18FIBER RL 2(1-5/8)	3.00 - 3.25	1.0000	1.0000
L59	18	LDF4-50A(1/2)	3.00 - 3.25	1.0000	1.0000
L59	20	Safety Line 3/8	3.00 - 3.25	1.0000	1.0000
L59	21	Step Pegs (5/8" SR) 7-in. w/30" step	3.00 - 3.25	1.0000	1.0000
L59	23	PL 1.25x5	3.00 - 3.25	1.0000	1.0000
L59	24	PL 1.25x5	3.00 - 3.25	1.0000	1.0000
L59	50	(Area) CCI-65FP-045125	3.00 - 3.25	1.0000	1.0000
L59	51	(Area) CCI-65FP-045125	3.00 - 3.25	1.0000	1.0000
L60	10	MLE HYBRID 9POWER/18FIBER RL 2(1-5/8)	2.75 - 3.00	1.0000	1.0000
L60	18	LDF4-50A(1/2)	2.75 - 3.00	1.0000	1.0000
L60	20	Safety Line 3/8	2.75 - 3.00	1.0000	1.0000
L60	21	Step Pegs (5/8" SR) 7-in. w/30" step	2.75 - 3.00	1.0000	1.0000
L60	23	PL 1.25x5	2.75 - 3.00	1.0000	1.0000
L60	24	PL 1.25x5	2.75 - 3.00	1.0000	1.0000
L60	50	(Area) CCI-65FP-045125	2.75 - 3.00	1.0000	1.0000
L60	51	(Area) CCI-65FP-045125	2.75 - 3.00	1.0000	1.0000
L61	10	MLE HYBRID	2.50 - 2.75	1.0000	1.0000

<b>tnxTower</b>  <b>Tower Engineering Professionals</b> 326 Tryon Road Raleigh, N.C. Phone: (919) 661-6351 FAX: (919) 661-6350	<b>Job</b> Preston / Town Hall (BU 876360)	<b>Page</b> 29 of 55
	<b>Project</b> TEP No. 25620.161151	<b>Date</b> 10:12:11 03/21/18
	<b>Client</b> Crown Castle	<b>Designed by</b> RKE

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K <sub>a</sub> No Ice	K <sub>a</sub> Ice
		9POWER/18FIBER RL 2(1-5/8)			
L61	18	LDF4-50A(1/2)	2.50 - 2.75	1.0000	1.0000
L61	20	Safety Line 3/8	2.50 - 2.75	1.0000	1.0000
L61	21	Step Pegs (5/8" SR) 7-in. w/30" step	2.50 - 2.75	1.0000	1.0000
L61	23	PL 1.25x5	2.50 - 2.75	1.0000	1.0000
L61	24	PL 1.25x5	2.50 - 2.75	1.0000	1.0000
L61	50	(Area) CCI-65FP-045125	2.50 - 2.75	1.0000	1.0000
L61	51	(Area) CCI-65FP-045125	2.50 - 2.75	1.0000	1.0000
L62	10	MLE HYBRID	2.25 - 2.50	1.0000	1.0000
		9POWER/18FIBER RL 2(1-5/8)			
L62	18	LDF4-50A(1/2)	2.25 - 2.50	1.0000	1.0000
L62	20	Safety Line 3/8	2.25 - 2.50	1.0000	1.0000
L62	21	Step Pegs (5/8" SR) 7-in. w/30" step	2.25 - 2.50	1.0000	1.0000
L62	23	PL 1.25x5	2.25 - 2.50	1.0000	1.0000
L62	24	PL 1.25x5	2.25 - 2.50	1.0000	1.0000
L62	50	(Area) CCI-65FP-045125	2.25 - 2.50	1.0000	1.0000
L62	51	(Area) CCI-65FP-045125	2.25 - 2.50	1.0000	1.0000
L63	10	MLE HYBRID	2.00 - 2.25	1.0000	1.0000
		9POWER/18FIBER RL 2(1-5/8)			
L63	18	LDF4-50A(1/2)	2.00 - 2.25	1.0000	1.0000
L63	20	Safety Line 3/8	2.00 - 2.25	1.0000	1.0000
L63	21	Step Pegs (5/8" SR) 7-in. w/30" step	2.00 - 2.25	1.0000	1.0000
L63	23	PL 1.25x5	2.00 - 2.25	1.0000	1.0000
L63	24	PL 1.25x5	2.00 - 2.25	1.0000	1.0000
L63	50	(Area) CCI-65FP-045125	2.00 - 2.25	1.0000	1.0000
L63	51	(Area) CCI-65FP-045125	2.00 - 2.25	1.0000	1.0000
L64	10	MLE HYBRID	0.00 - 2.00	1.0000	1.0000
		9POWER/18FIBER RL 2(1-5/8)			
L64	18	LDF4-50A(1/2)	0.00 - 2.00	1.0000	1.0000
L64	20	Safety Line 3/8	0.00 - 2.00	1.0000	1.0000
L64	21	Step Pegs (5/8" SR) 7-in. w/30" step	0.00 - 2.00	1.0000	1.0000
L64	23	PL 1.25x5	0.00 - 2.00	1.0000	1.0000
L64	24	PL 1.25x5	0.00 - 2.00	1.0000	1.0000
L64	50	(Area) CCI-65FP-045125	0.00 - 2.00	1.0000	1.0000
L64	51	(Area) CCI-65FP-045125	0.00 - 2.00	1.0000	1.0000

### Discrete Tower Loads

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert	Azimuth Adjustment	Placement	C <sub>A</sub> A <sub>Front</sub>	C <sub>A</sub> A <sub>Side</sub>	Weight	
			ft ft ft	°	ft	ft <sup>2</sup>	ft <sup>2</sup>	K	
***147*** APXVSPP18-C-A20	A	From	4.0000	0.0000	147.0000	No Ice	8.0244	5.2833	0.06



<b>tnxTower</b>  <b>Tower Engineering Professionals</b> 326 Tryon Road Raleigh, N.C. Phone: (919) 661-6351 FAX: (919) 661-6350	<b>Job</b> Preston / Town Hall (BU 876360)	<b>Page</b> 30 of 55
	<b>Project</b> TEP No. 25620.161151	<b>Date</b> 10:12:11 03/21/18
	<b>Client</b> Crown Castle	<b>Designed by</b> RKE

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C <sub>AA</sub>		Weight
			Horz	Vert			Front	Side	
			ft	ft	°	ft	ft <sup>2</sup>	ft <sup>2</sup>	K
APXVSPP18-C-A20	B	Centroid-Le	-6.00			1/2" Ice	8.4800	5.7360	0.11
		g	3.00			1" Ice	8.9426	6.1960	0.16
		From	4.0000	0.0000	147.0000	No Ice	8.0244	5.2833	0.06
APXVSPP18-C-A20	C	Centroid-Le	-6.00			1/2" Ice	8.4800	5.7360	0.11
		g	3.00			1" Ice	8.9426	6.1960	0.16
		From	4.0000	0.0000	147.0000	No Ice	8.0244	5.2833	0.06
DT465B-2XR	A	Centroid-Le	-6.00			1/2" Ice	8.4800	5.7360	0.11
		g	3.00			1" Ice	8.9426	6.1960	0.16
		From	4.0000	0.0000	147.0000	No Ice	9.0985	5.9734	0.06
DT465B-2XR	B	Centroid-Le	6.00			1/2" Ice	9.5636	6.4319	0.12
		g	3.00			1" Ice	10.0357	6.8978	0.18
		From	4.0000	0.0000	147.0000	No Ice	9.0985	5.9734	0.06
DT465B-2XR	C	Centroid-Le	6.00			1/2" Ice	9.5636	6.4319	0.12
		g	3.00			1" Ice	10.0357	6.8978	0.18
		From	4.0000	0.0000	147.0000	No Ice	9.0985	5.9734	0.06
PCS 1900MHZ 4X45W-65MHZ	A	Centroid-Le	-6.00			1/2" Ice	2.5266	2.4407	0.08
		g	3.00			1" Ice	2.7388	2.6507	0.11
		From	4.0000	0.0000	147.0000	No Ice	2.3218	2.2381	0.06
PCS 1900MHZ 4X45W-65MHZ	B	Centroid-Le	-6.00			1/2" Ice	2.5266	2.4407	0.08
		g	3.00			1" Ice	2.7388	2.6507	0.11
		From	4.0000	0.0000	147.0000	No Ice	2.3218	2.2381	0.06
PCS 1900MHZ 4X45W-65MHZ	C	Centroid-Le	-6.00			1/2" Ice	2.5266	2.4407	0.08
		g	3.00			1" Ice	2.7388	2.6507	0.11
		From	4.0000	0.0000	147.0000	No Ice	2.3218	2.2381	0.06
RRH2X50-800	A	Centroid-Le	6.00			1/2" Ice	2.3195	1.9461	0.07
		g	3.00			1" Ice	2.5123	2.1267	0.10
		From	4.0000	0.0000	147.0000	No Ice	2.1342	1.7730	0.05
RRH2X50-800	B	Centroid-Le	6.00			1/2" Ice	2.3195	1.9461	0.07
		g	3.00			1" Ice	2.5123	2.1267	0.10
		From	4.0000	0.0000	147.0000	No Ice	2.1342	1.7730	0.05
RRH2X50-800	C	Centroid-Le	6.00			1/2" Ice	2.3195	1.9461	0.07
		g	3.00			1" Ice	2.5123	2.1267	0.10
		From	4.0000	0.0000	147.0000	No Ice	2.1342	1.7730	0.05
TD-RRH8X20-25	A	Centroid-Le	6.00			1/2" Ice	4.2975	1.7142	0.10
		g	3.00			1" Ice	4.5570	1.9008	0.13
		From	4.0000	0.0000	147.0000	No Ice	4.0455	1.5345	0.07
TD-RRH8X20-25	B	Centroid-Le	6.00			1/2" Ice	4.2975	1.7142	0.10
		g	3.00			1" Ice	4.5570	1.9008	0.13
		From	4.0000	0.0000	147.0000	No Ice	4.0455	1.5345	0.07
TD-RRH8X20-25	C	Centroid-Le	6.00			1/2" Ice	4.2975	1.7142	0.10
		g	3.00			1" Ice	4.5570	1.9008	0.13
		From	4.0000	0.0000	147.0000	No Ice	4.0455	1.5345	0.07
800MHZ RRH	A	Centroid-Le	-6.00			1/2" Ice	2.3195	1.9461	0.07
		g	3.00			1" Ice	2.5123	2.1267	0.10
		From	4.0000	0.0000	147.0000	No Ice	2.1342	1.7730	0.05
800MHZ RRH	B	Centroid-Le	-6.00			1/2" Ice	2.3195	1.9461	0.07
		g	3.00			1" Ice	2.5123	2.1267	0.10
		From	4.0000	0.0000	147.0000	No Ice	2.1342	1.7730	0.05
800MHZ RRH	C	Centroid-Le	-6.00			1/2" Ice	2.3195	1.9461	0.07
		g	3.00			1" Ice	2.5123	2.1267	0.10
		From	4.0000	0.0000	147.0000	No Ice	2.1342	1.7730	0.05
Platform Mount [LP 301-1]	C	Centroid-Le	-6.00			1/2" Ice	30.1000	30.1000	1.59
		g	3.00			1" Ice	40.8000	40.8000	2.03
		From	4.0000	0.0000	147.0000	No Ice	51.5000	51.5000	2.47
Miscellaneous [NA 509-3]	C	Centroid-Le	-6.00			1/2" Ice	11.8400	11.8400	0.28
		g	3.00			1" Ice	11.8400	11.8400	0.28
		From	4.0000	0.0000	147.0000	No Ice	11.8400	11.8400	0.28

<b>tnxTower</b>  <b>Tower Engineering Professionals</b> 326 Tryon Road Raleigh, N.C. Phone: (919) 661-6351 FAX: (919) 661-6350	<b>Job</b> Preston / Town Hall (BU 876360)	<b>Page</b> 31 of 55
	<b>Project</b> TEP No. 25620.161151	<b>Date</b> 10:12:11 03/21/18
	<b>Client</b> Crown Castle	<b>Designed by</b> RKE

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C <sub>AA</sub> Front	C <sub>AA</sub> Side	Weight
			Horz	Vert					
			ft	ft	°	ft	ft <sup>2</sup>	ft <sup>2</sup>	K
						1/2" Ice	16.9600	16.9600	0.30
						1" Ice	22.0800	22.0800	0.32
***136***									
(2) LPA-80080/4CF w/ Mount Pipe	A	From	4.0000		0.0000	No Ice	3.1098	6.8239	0.03
		Centroid-Le	4.00			1/2" Ice	3.5849	7.6513	0.08
		g	2.00			1" Ice	4.0223	8.3546	0.14
(2) LPA-80080/4CF w/ Mount Pipe	B	From	4.0000		0.0000	No Ice	3.1098	6.8239	0.03
		Centroid-Le	2.00			1/2" Ice	3.5849	7.6513	0.08
		g	2.00			1" Ice	4.0223	8.3546	0.14
(2) LPA-80080/4CF w/ Mount Pipe	C	From	4.0000		0.0000	No Ice	3.1098	6.8239	0.03
		Centroid-Le	2.00			1/2" Ice	3.5849	7.6513	0.08
		g	2.00			1" Ice	4.0223	8.3546	0.14
(2) SBNHH-1D65A w/ Mount Pipe	A	From	4.0000		0.0000	No Ice	6.2901	5.5890	0.07
		Centroid-Le	-4.00			1/2" Ice	6.7393	6.3084	0.13
		g	2.00			1" Ice	7.1973	7.0314	0.19
(2) SBNHH-1D65A w/ Mount Pipe	B	From	4.0000		0.0000	No Ice	6.2901	5.5890	0.07
		Centroid-Le	-2.00			1/2" Ice	6.7393	6.3084	0.13
		g	2.00			1" Ice	7.1973	7.0314	0.19
(2) SBNHH-1D65A w/ Mount Pipe	C	From	4.0000		0.0000	No Ice	6.2901	5.5890	0.07
		Centroid-Le	-2.00			1/2" Ice	6.7393	6.3084	0.13
		g	2.00			1" Ice	7.1973	7.0314	0.19
RRH4X45-AWS4 B66	A	From	4.0000		0.0000	No Ice	2.6600	1.5861	0.06
		Centroid-Le	-2.00			1/2" Ice	2.8781	1.7690	0.08
		g	2.00			1" Ice	3.1037	1.9588	0.11
RRH4X45-AWS4 B66	B	From	4.0000		0.0000	No Ice	2.6600	1.5861	0.06
		Centroid-Le	2.00			1/2" Ice	2.8781	1.7690	0.08
		g	2.00			1" Ice	3.1037	1.9588	0.11
RRH4X45-AWS4 B66	C	From	4.0000		0.0000	No Ice	2.6600	1.5861	0.06
		Centroid-Le	2.00			1/2" Ice	2.8781	1.7690	0.08
		g	2.00			1" Ice	3.1037	1.9588	0.11
RRH2x60-700	A	From	4.0000		0.0000	No Ice	3.5002	1.8157	0.06
		Centroid-Le	-6.00			1/2" Ice	3.7609	2.0519	0.08
		g	2.00			1" Ice	4.0285	2.2894	0.11
RRH2x60-700	B	From	4.0000		0.0000	No Ice	3.5002	1.8157	0.06
		Centroid-Le	-6.00			1/2" Ice	3.7609	2.0519	0.08
		g	2.00			1" Ice	4.0285	2.2894	0.11
RRH2x60-700	C	From	4.0000		0.0000	No Ice	3.5002	1.8157	0.06
		Centroid-Le	-6.00			1/2" Ice	3.7609	2.0519	0.08
		g	2.00			1" Ice	4.0285	2.2894	0.11
(2) DB-B1-6C-12AB-0Z	A	From	4.0000		0.0000	No Ice	3.7922	2.5137	0.03
		Centroid-Le	-6.00			1/2" Ice	4.0441	2.7270	0.06
		g	2.00			1" Ice	4.3033	2.9472	0.10
Platform Mount [LP 601-1]	C	None			0.0000	No Ice	28.4700	28.4700	1.12
						1/2" Ice	33.5900	33.5900	1.51
						1" Ice	38.7100	38.7100	1.91
***129***									
ERICSSON AIR 21 B2A B4P w/ Mount Pipe	A	From	4.0000		30.0000	No Ice	6.3292	5.6424	0.11
		Centroid-Le	-6.00			1/2" Ice	6.7751	6.4259	0.17
		g	0.00			1" Ice	7.2137	7.1313	0.23
ERICSSON AIR 21 B2A B4P w/ Mount Pipe	B	From	4.0000		0.0000	No Ice	6.3292	5.6424	0.11
		Centroid-Le	-6.00			1/2" Ice	6.7751	6.4259	0.17
		g	0.00			1" Ice	7.2137	7.1313	0.23
ERICSSON AIR 21 B2A B4P w/ Mount Pipe	C	From	4.0000		30.0000	No Ice	6.3292	5.6424	0.11
		Centroid-Le	-6.00			1/2" Ice	6.7751	6.4259	0.17
		g	0.00			1" Ice	7.2137	7.1313	0.23
ERICSSON AIR 21 B4A B2P w/ Mount Pipe	A	From	4.0000		30.0000	No Ice	6.3292	5.6424	0.11
		Centroid-Le	6.00			1/2" Ice	6.7751	6.4259	0.17

<b>tnxTower</b>  <b>Tower Engineering Professionals</b> 326 Tryon Road Raleigh, N.C. Phone: (919) 661-6351 FAX: (919) 661-6350	<b>Job</b> Preston / Town Hall (BU 876360)	<b>Page</b> 32 of 55
	<b>Project</b> TEP No. 25620.161151	<b>Date</b> 10:12:11 03/21/18
	<b>Client</b> Crown Castle	<b>Designed by</b> RKE

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C <sub>AA</sub> Front	C <sub>AA</sub> Side	Weight
			Horz	Lateral					
			ft	ft	°	ft	ft <sup>2</sup>	ft <sup>2</sup>	K
ERICSSON AIR 21 B4A B2P w/ Mount Pipe	B	g	0.00			1" Ice	7.2137	7.1313	0.23
		From	4.0000	0.0000	129.0000	No Ice	6.3292	5.6424	0.11
		Centroid-Le	6.00			1/2" Ice	6.7751	6.4259	0.17
ERICSSON AIR 21 B4A B2P w/ Mount Pipe	C	g	0.00			1" Ice	7.2137	7.1313	0.23
		From	4.0000	30.0000	129.0000	No Ice	6.3292	5.6424	0.11
		Centroid-Le	6.00			1/2" Ice	6.7751	6.4259	0.17
LNX-6515DS-VTM w/ Mount Pipe	A	g	0.00			1" Ice	7.2137	7.1313	0.23
		From	4.0000	30.0000	129.0000	No Ice	11.2110	9.3589	0.08
		Centroid-Le	0.00			1/2" Ice	11.8278	10.6795	0.16
LNX-6515DS-VTM w/ Mount Pipe	B	g	0.00			1" Ice	12.4520	11.7139	0.25
		From	4.0000	0.0000	129.0000	No Ice	11.2110	9.3589	0.08
		Centroid-Le	0.00			1/2" Ice	11.8278	10.6795	0.16
LNX-6515DS-VTM w/ Mount Pipe	C	g	0.00			1" Ice	12.4520	11.7139	0.25
		From	4.0000	30.0000	129.0000	No Ice	11.2110	9.3589	0.08
		Centroid-Le	0.00			1/2" Ice	11.8278	10.6795	0.16
KRY 112 144/1	A	g	0.00			1" Ice	12.4520	11.7139	0.25
		From	4.0000	30.0000	129.0000	No Ice	0.3523	0.1617	0.01
		Centroid-Le	-6.00			1/2" Ice	0.4284	0.2195	0.01
KRY 112 144/1	B	g	0.00			1" Ice	0.5119	0.2846	0.02
		From	4.0000	0.0000	129.0000	No Ice	0.3523	0.1617	0.01
		Centroid-Le	-6.00			1/2" Ice	0.4284	0.2195	0.01
KRY 112 144/1	C	g	0.00			1" Ice	0.5119	0.2846	0.02
		From	4.0000	30.0000	129.0000	No Ice	0.3523	0.1617	0.01
		Centroid-Le	-6.00			1/2" Ice	0.4284	0.2195	0.01
RRUS 11 B12	A	g	0.00			1" Ice	0.5119	0.2846	0.02
		From	4.0000	30.0000	129.0000	No Ice	2.7908	1.1923	0.05
		Centroid-Le	0.00			1/2" Ice	2.9984	1.3395	0.07
RRUS 11 B12	B	g	0.00			1" Ice	3.2134	1.4957	0.10
		From	4.0000	0.0000	129.0000	No Ice	2.7908	1.1923	0.05
		Centroid-Le	0.00			1/2" Ice	2.9984	1.3395	0.07
RRUS 11 B12	C	g	0.00			1" Ice	3.2134	1.4957	0.10
		From	4.0000	30.0000	129.0000	No Ice	2.7908	1.1923	0.05
		Centroid-Le	0.00			1/2" Ice	2.9984	1.3395	0.07
Platform Mount [LP 1201-1]	C	g	0.00			1" Ice	3.2134	1.4957	0.10
		None		0.0000	129.0000	No Ice	23.1000	23.1000	2.10
						1/2" Ice	26.8000	26.8000	2.50
***120***									
(2) TME-RRUS-11	A	From Leg	2.0000	35.0000	120.0000	No Ice	2.7845	1.1872	0.05
			0.00			1/2" Ice	2.9919	1.3342	0.07
			0.00			1" Ice	3.2066	1.4897	0.09
(2) TME-RRUS-11	B	From Leg	2.0000	35.0000	120.0000	No Ice	2.7845	1.1872	0.05
			0.00			1/2" Ice	2.9919	1.3342	0.07
			0.00			1" Ice	3.2066	1.4897	0.09
(2) TME-RRUS-11	C	From Leg	2.0000	25.0000	120.0000	No Ice	2.7845	1.1872	0.05
			0.00			1/2" Ice	2.9919	1.3342	0.07
			0.00			1" Ice	3.2066	1.4897	0.09
2.4" Dia x 3-ft Mount Pipe	A	From Leg	2.0000	0.0000	120.0000	No Ice	0.5826	0.5826	0.01
			0.00			1/2" Ice	0.7701	0.7701	0.02
			0.00			1" Ice	0.9669	0.9669	0.02
2.4" Dia x 3-ft Mount Pipe	B	From Leg	2.0000	0.0000	120.0000	No Ice	0.5826	0.5826	0.01
			0.00			1/2" Ice	0.7701	0.7701	0.02
			0.00			1" Ice	0.9669	0.9669	0.02
2.4" Dia x 3-ft Mount Pipe	C	From Leg	2.0000	0.0000	120.0000	No Ice	0.5826	0.5826	0.01
			0.00			1/2" Ice	0.7701	0.7701	0.02
			0.00			1" Ice	0.9669	0.9669	0.02
Side Arm Mount [SO 102-3]	C	None		0.0000	120.0000	No Ice	3.0000	3.0000	0.08

<b>tnxTower</b>  <b>Tower Engineering Professionals</b> 326 Tryon Road Raleigh, N.C. Phone: (919) 661-6351 FAX: (919) 661-6350	<b>Job</b> Preston / Town Hall (BU 876360)	<b>Page</b> 33 of 55
	<b>Project</b> TEP No. 25620.161151	<b>Date</b> 10:12:11 03/21/18
	<b>Client</b> Crown Castle	<b>Designed by</b> RKE

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C <sub>AA</sub> Front	C <sub>AA</sub> Side	Weight	
			Horz	Vert						
			ft	ft	°	ft	ft <sup>2</sup>	ft <sup>2</sup>	K	
							1/2" Ice	3.4800	3.4800	0.11
							1" Ice	3.9600	3.9600	0.14
***118***										
AM-X-WM-17-65-00T w/ Mount Pipe	A	From Centroid-Le	4.0000	-2.00	35.0000	118.0000	No Ice	3.5517	2.9694	0.04
			g	0.00			1/2" Ice	4.0247	3.7612	0.07
							1" Ice	4.4529	4.4294	0.11
AM-X-WM-17-65-00T w/ Mount Pipe	B	From Centroid-Le	4.0000	-2.00	35.0000	118.0000	No Ice	3.5517	2.9694	0.04
			g	0.00			1/2" Ice	4.0247	3.7612	0.07
							1" Ice	4.4529	4.4294	0.11
AM-X-WM-17-65-00T w/ Mount Pipe	C	From Centroid-Le	4.0000	-2.00	25.0000	118.0000	No Ice	3.5517	2.9694	0.04
			g	0.00			1/2" Ice	4.0247	3.7612	0.07
							1" Ice	4.4529	4.4294	0.11
RA21.7770.00 w/ Mount Pipe	A	From Centroid-Le	4.0000	-6.00	35.0000	118.0000	No Ice	6.7663	5.0018	0.06
			g	0.00			1/2" Ice	7.2614	5.9599	0.11
							1" Ice	7.7350	6.7465	0.18
RA21.7770.00 w/ Mount Pipe	B	From Centroid-Le	4.0000	-6.00	35.0000	118.0000	No Ice	6.7663	5.0018	0.06
			g	0.00			1/2" Ice	7.2614	5.9599	0.11
							1" Ice	7.7350	6.7465	0.18
RA21.7770.00 w/ Mount Pipe	C	From Centroid-Le	4.0000	-6.00	25.0000	118.0000	No Ice	6.7663	5.0018	0.06
			g	0.00			1/2" Ice	7.2614	5.9599	0.11
							1" Ice	7.7350	6.7465	0.18
(2) LGP21401	A	From Centroid-Le	4.0000	-6.00	35.0000	118.0000	No Ice	0.0000	0.2070	0.01
			g	0.00			1/2" Ice	0.0000	0.2738	0.02
							1" Ice	0.0000	0.3475	0.03
(2) LGP21401	B	From Centroid-Le	4.0000	-6.00	35.0000	118.0000	No Ice	0.0000	0.2070	0.01
			g	0.00			1/2" Ice	0.0000	0.2738	0.02
							1" Ice	0.0000	0.3475	0.03
(2) LGP21401	C	From Centroid-Le	4.0000	-6.00	25.0000	118.0000	No Ice	0.0000	0.2070	0.01
			g	0.00			1/2" Ice	0.0000	0.2738	0.02
							1" Ice	0.0000	0.3475	0.03
DC6-48-60-18-8F	A	From Centroid-Le	4.0000	-2.00	35.0000	118.0000	No Ice	1.2117	1.2117	0.03
			g	0.00			1/2" Ice	1.8924	1.8924	0.05
							1" Ice	2.1051	2.1051	0.08
Platform Mount [LP 303-1]	C	None	0.0000		0.0000	118.0000	No Ice	14.6600	14.6600	1.25
							1/2" Ice	18.8700	18.8700	1.48
							1" Ice	23.0800	23.0800	1.71
***50***										
KS24019-L112A	C	From Leg	3.0000	0.00	-40.0000	50.0000	No Ice	0.0815	0.0815	0.01
			1.00				1/2" Ice	0.1333	0.1333	0.01
			0.50				1" Ice	0.1944	0.1944	0.01
1.5" Dia. x 17" Pipe	C	From Leg	3.0000	0.00	-40.0000	50.0000	No Ice	0.1587	0.1587	0.00
			0.50				1/2" Ice	0.2514	0.2514	0.01
			0.00				1" Ice	0.3533	0.3533	0.01
Side Arm Mount [SO 701-1]	C	From Leg	1.5000	0.00	-40.0000	50.0000	No Ice	0.8500	1.6700	0.07
			0.00				1/2" Ice	1.1400	2.3400	0.08
			0.00				1" Ice	1.4300	3.0100	0.09
***45***										
KS24019-L112A	A	From Leg	3.0000	0.00	0.0000	45.0000	No Ice	0.0815	0.0815	0.01
			1.00				1/2" Ice	0.1333	0.1333	0.01
			0.50				1" Ice	0.1944	0.1944	0.01
1.5" Dia. x 17" Pipe	A	From Leg	3.0000	0.00	0.0000	45.0000	No Ice	0.1587	0.1587	0.00
			0.50				1/2" Ice	0.2514	0.2514	0.01
			0.00				1" Ice	0.3533	0.3533	0.01
Side Arm Mount [SO 701-1]	A	From Leg	1.5000	0.00	0.0000	45.0000	No Ice	0.8500	1.6700	0.07
			0.00				1/2" Ice	1.1400	2.3400	0.08
			0.00				1" Ice	1.4300	3.0100	0.09

<b>tnxTower</b>  <b>Tower Engineering Professionals</b> 326 Tryon Road Raleigh, N.C. Phone: (919) 661-6351 FAX: (919) 661-6350	<b>Job</b> Preston / Town Hall (BU 876360)	<b>Page</b> 34 of 55
	<b>Project</b> TEP No. 25620.161151	<b>Date</b> 10:12:11 03/21/18
	<b>Client</b> Crown Castle	<b>Designed by</b> RKE

## Load Combinations

Comb. No.	Description
1	Dead Only
2	1.2 Dead+1.6 Wind 0 deg - No Ice
3	0.9 Dead+1.6 Wind 0 deg - No Ice
4	1.2 Dead+1.6 Wind 30 deg - No Ice
5	0.9 Dead+1.6 Wind 30 deg - No Ice
6	1.2 Dead+1.6 Wind 60 deg - No Ice
7	0.9 Dead+1.6 Wind 60 deg - No Ice
8	1.2 Dead+1.6 Wind 90 deg - No Ice
9	0.9 Dead+1.6 Wind 90 deg - No Ice
10	1.2 Dead+1.6 Wind 120 deg - No Ice
11	0.9 Dead+1.6 Wind 120 deg - No Ice
12	1.2 Dead+1.6 Wind 150 deg - No Ice
13	0.9 Dead+1.6 Wind 150 deg - No Ice
14	1.2 Dead+1.6 Wind 180 deg - No Ice
15	0.9 Dead+1.6 Wind 180 deg - No Ice
16	1.2 Dead+1.6 Wind 210 deg - No Ice
17	0.9 Dead+1.6 Wind 210 deg - No Ice
18	1.2 Dead+1.6 Wind 240 deg - No Ice
19	0.9 Dead+1.6 Wind 240 deg - No Ice
20	1.2 Dead+1.6 Wind 270 deg - No Ice
21	0.9 Dead+1.6 Wind 270 deg - No Ice
22	1.2 Dead+1.6 Wind 300 deg - No Ice
23	0.9 Dead+1.6 Wind 300 deg - No Ice
24	1.2 Dead+1.6 Wind 330 deg - No Ice
25	0.9 Dead+1.6 Wind 330 deg - No Ice
26	1.2 Dead+1.0 Ice+1.0 Temp
27	1.2 Dead+1.0 Wind 0 deg+1.0 Ice+1.0 Temp
28	1.2 Dead+1.0 Wind 30 deg+1.0 Ice+1.0 Temp
29	1.2 Dead+1.0 Wind 60 deg+1.0 Ice+1.0 Temp
30	1.2 Dead+1.0 Wind 90 deg+1.0 Ice+1.0 Temp
31	1.2 Dead+1.0 Wind 120 deg+1.0 Ice+1.0 Temp
32	1.2 Dead+1.0 Wind 150 deg+1.0 Ice+1.0 Temp
33	1.2 Dead+1.0 Wind 180 deg+1.0 Ice+1.0 Temp
34	1.2 Dead+1.0 Wind 210 deg+1.0 Ice+1.0 Temp
35	1.2 Dead+1.0 Wind 240 deg+1.0 Ice+1.0 Temp
36	1.2 Dead+1.0 Wind 270 deg+1.0 Ice+1.0 Temp
37	1.2 Dead+1.0 Wind 300 deg+1.0 Ice+1.0 Temp
38	1.2 Dead+1.0 Wind 330 deg+1.0 Ice+1.0 Temp
39	Dead+Wind 0 deg - Service
40	Dead+Wind 30 deg - Service
41	Dead+Wind 60 deg - Service
42	Dead+Wind 90 deg - Service
43	Dead+Wind 120 deg - Service
44	Dead+Wind 150 deg - Service
45	Dead+Wind 180 deg - Service
46	Dead+Wind 210 deg - Service
47	Dead+Wind 240 deg - Service
48	Dead+Wind 270 deg - Service
49	Dead+Wind 300 deg - Service
50	Dead+Wind 330 deg - Service

<b>tnxTower</b>  <b>Tower Engineering Professionals</b> 326 Tryon Road Raleigh, N.C. Phone: (919) 661-6351 FAX: (919) 661-6350	<b>Job</b> Preston / Town Hall (BU 876360)	<b>Page</b> 35 of 55
	<b>Project</b> TEP No. 25620.161151	<b>Date</b> 10:12:11 03/21/18
	<b>Client</b> Crown Castle	<b>Designed by</b> RKE

## Maximum Member Forces

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Axial K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
L1	147 - 142	Pole	Max Tension	26	0.00	-0.00	-0.00
			Max. Compression	26	-8.04	0.03	0.05
			Max. Mx	20	-2.64	52.66	0.02
			Max. My	2	-2.64	0.05	52.67
			Max. Vy	20	-7.98	52.66	0.02
			Max. Vx	2	-7.98	0.05	52.67
			Max. Torque	16			0.00
L2	142 - 137	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-8.54	0.06	0.11
			Max. Mx	20	-2.87	93.40	0.03
			Max. My	2	-2.87	0.09	93.41
			Max. Vy	20	-8.32	93.40	0.03
			Max. Vx	2	-8.32	0.09	93.41
			Max. Torque	16			0.00
L3	137 - 132	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-16.48	3.03	1.49
			Max. Mx	20	-4.95	171.18	0.20
			Max. My	2	-4.93	0.59	171.35
			Max. Vy	20	-15.10	171.18	0.20
			Max. Vx	2	-15.23	0.59	171.35
			Max. Torque	4			3.67
L4	132 - 127	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-25.00	3.10	1.56
			Max. Mx	20	-8.55	258.95	0.24
			Max. My	2	-8.56	0.59	259.26
			Max. Vy	20	-21.16	258.95	0.24
			Max. Vx	2	-21.03	0.59	259.26
			Max. Torque	2			4.06
L5	127 - 120.37	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-25.49	3.16	1.61
			Max. Mx	20	-8.93	330.79	0.25
			Max. My	2	-8.95	0.63	330.69
			Max. Vy	20	-21.37	330.79	0.25
			Max. Vx	2	-21.24	0.63	330.69
			Max. Torque	2			4.05
L6	120.37 - 118.62	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-27.81	3.25	1.69
			Max. Mx	20	-10.08	439.80	0.21
			Max. My	2	-10.10	0.64	439.09
			Max. Vy	20	-22.66	439.80	0.21
			Max. Vx	2	-22.54	0.64	439.09
			Max. Torque	2			4.05
L7	118.62 - 113.62	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-32.81	3.58	2.27
			Max. Mx	20	-12.57	564.97	0.13
			Max. My	2	-12.58	0.54	563.72
			Max. Vy	20	-25.49	564.97	0.13
			Max. Vx	2	-25.37	0.54	563.72
			Max. Torque	4			4.07
L8	113.62 - 112.41	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-33.03	3.59	2.28
			Max. Mx	20	-12.76	595.84	0.08
			Max. My	2	-12.77	0.49	594.44
			Max. Vy	20	-25.56	595.84	0.08
			Max. Vx	2	-25.45	0.49	594.44

<b>tnxTower</b>  <b>Tower Engineering Professionals</b> 326 Tryon Road Raleigh, N.C. Phone: (919) 661-6351 FAX: (919) 661-6350	<b>Job</b> Preston / Town Hall (BU 876360)	<b>Page</b> 36 of 55
	<b>Project</b> TEP No. 25620.161151	<b>Date</b> 10:12:11 03/21/18
	<b>Client</b> Crown Castle	<b>Designed by</b> RKE

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Axial K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
L9	112.41 - 112.16	Pole	Max. Torque	4			4.07
			Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-33.10	3.60	2.28
			Max. Mx	20	-12.84	602.23	0.07
			Max. My	2	-12.85	0.48	600.80
			Max. Vy	20	-25.57	602.23	0.07
			Max. Vx	2	-25.45	0.48	600.80
L10	112.16 - 110.5	Pole	Max. Torque	4			4.06
			Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-33.54	3.62	2.30
			Max. Mx	20	-13.15	644.78	-0.00
			Max. My	2	-13.16	0.42	643.18
			Max. Vy	20	-25.72	644.78	-0.00
			Max. Vx	2	-25.62	0.42	643.18
L11	110.5 - 110.25	Pole	Max. Torque	4			4.06
			Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-33.62	3.63	2.31
			Max. Mx	20	-13.23	651.21	-0.01
			Max. My	2	-13.24	0.41	649.59
			Max. Vy	20	-25.73	651.21	-0.01
			Max. Vx	2	-25.63	0.41	649.59
L12	110.25 - 105.25	Pole	Max. Torque	4			4.06
			Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-35.22	3.69	2.37
			Max. Mx	20	-14.46	780.98	-0.23
			Max. My	2	-14.47	0.22	778.98
			Max. Vy	20	-26.18	780.98	-0.23
			Max. Vx	2	-26.13	0.22	778.98
L13	105.25 - 105	Pole	Max. Torque	4			4.06
			Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-35.30	3.70	2.37
			Max. Mx	20	-14.53	787.53	-0.24
			Max. My	2	-14.54	0.21	785.51
			Max. Vy	20	-26.20	787.53	-0.24
			Max. Vx	2	-26.15	0.21	785.51
L14	105 - 104.75	Pole	Max. Torque	4			4.06
			Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-35.40	3.70	2.37
			Max. Mx	20	-14.61	794.08	-0.25
			Max. My	2	-14.62	0.20	792.05
			Max. Vy	20	-26.23	794.08	-0.25
			Max. Vx	2	-26.17	0.20	792.05
L15	104.75 - 103.5	Pole	Max. Torque	4			4.06
			Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-35.88	3.71	2.38
			Max. Mx	20	-14.99	826.94	-0.30
			Max. My	2	-15.00	0.15	824.85
			Max. Vy	20	-26.35	826.94	-0.30
			Max. Vx	2	-26.30	0.15	824.85
L16	103.5 - 103.25	Pole	Max. Torque	4			4.06
			Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-35.96	3.71	2.38
			Max. Mx	20	-15.07	833.53	-0.32
			Max. My	2	-15.07	0.14	831.43
			Max. Vy	20	-26.37	833.53	-0.32
			Max. Vx	2	-26.32	0.14	831.43
L17	103.25 - 98.25	Pole	Max. Torque	4			4.06
			Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-37.61	3.76	2.42

<b>tnxTower</b>  <b>Tower Engineering Professionals</b> 326 Tryon Road Raleigh, N.C. Phone: (919) 661-6351 FAX: (919) 661-6350	Job	Preston / Town Hall (BU 876360)	Page	37 of 55
	Project	TEP No. 25620.161151	Date	10:12:11 03/21/18
	Client	Crown Castle	Designed by	RKE

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Axial K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
L18	98.25 - 94.83	Pole	Max. Mx	20	-16.38	966.47	-0.53
			Max. My	2	-16.38	-0.06	964.17
			Max. Vy	20	-26.82	966.47	-0.53
			Max. Vx	2	-26.78	-0.06	964.17
			Max. Torque	4			4.06
			Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-38.76	3.79	2.45
			Max. Mx	20	-17.30	1058.68	-0.68
			Max. My	2	-17.30	-0.19	1056.29
			Max. Vy	20	-27.12	1058.68	-0.68
L19	94.83 - 94.58	Pole	Max. Vx	2	-27.10	-0.19	1056.29
			Max. Torque	4			4.06
			Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-38.85	3.80	2.46
			Max. Mx	20	-17.38	1065.46	-0.69
			Max. My	2	-17.38	-0.20	1063.06
			Max. Vy	20	-27.14	1065.46	-0.69
			Max. Vx	2	-27.12	-0.20	1063.06
			Max. Torque	4			4.06
			Max Tension	1	0.00	0.00	0.00
L20	94.58 - 94.17	Pole	Max. Compression	26	-38.99	3.80	2.46
			Max. Mx	20	-17.49	1076.59	-0.71
			Max. My	2	-17.49	-0.22	1074.19
			Max. Vy	20	-27.17	1076.59	-0.71
			Max. Vx	2	-27.16	-0.22	1074.19
			Max. Torque	4			4.06
			Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-39.12	3.81	2.47
			Max. Mx	20	-17.59	1086.11	-0.72
			Max. My	2	-17.59	-0.23	1083.70
L21	94.17 - 93.82	Pole	Max. Vy	20	-27.20	1086.11	-0.72
			Max. Vx	2	-27.19	-0.23	1083.70
			Max. Torque	4			4.06
			Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-39.18	3.81	2.47
			Max. Mx	20	-17.64	1090.46	-0.73
			Max. My	2	-17.64	-0.24	1088.05
			Max. Vy	20	-27.22	1090.46	-0.73
			Max. Vx	2	-27.21	-0.24	1088.05
			Max. Torque	4			4.06
L22	93.82 - 93.66	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-40.89	3.87	2.53
			Max. Mx	20	-18.98	1216.06	-0.93
			Max. My	2	-18.98	-0.42	1213.67
			Max. Vy	20	-27.64	1216.06	-0.93
			Max. Vx	2	-27.66	-0.42	1213.67
			Max. Torque	4			4.06
			Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-44.28	3.95	2.60
			Max. Mx	20	-21.66	1360.50	-1.16
L23	93.66 - 84.91	Pole	Max. My	2	-21.66	-0.63	1358.32
			Max. Vy	20	-28.23	1360.50	-1.16
			Max. Vx	2	-28.29	-0.63	1358.32
			Max. Torque	4			4.05
			Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-46.33	4.02	2.66
			Max. Mx	20	-23.32	1502.73	-1.38
			Max. My	2	-23.31	-0.84	1500.92
			Max. Vy	20	-28.68	1502.73	-1.38
			Max. Vx	2	-28.77	-0.84	1500.92
L24	84.91 - 83.91	Pole	Max. Torque	4			4.05
			Max. Torque	4			4.05
			Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-46.33	4.02	2.66
			Max. Mx	20	-23.32	1502.73	-1.38
			Max. My	2	-23.31	-0.84	1500.92
L25	83.91 - 78.91	Pole	Max. Vy	20	-28.68	1502.73	-1.38
			Max. Vx	2	-28.77	-0.84	1500.92
			Max. Torque	4			4.05
			Max. Torque	4			4.05
			Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-46.33	4.02	2.66



<b>tnxTower</b>  <b>Tower Engineering Professionals</b> 326 Tryon Road Raleigh, N.C. Phone: (919) 661-6351 FAX: (919) 661-6350	<b>Job</b> Preston / Town Hall (BU 876360)	<b>Page</b> 38 of 55
	<b>Project</b> TEP No. 25620.161151	<b>Date</b> 10:12:11 03/21/18
	<b>Client</b> Crown Castle	<b>Designed by</b> RKE

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Axial K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
L26	78.91 - 73.91	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-48.40	4.09	2.73
			Max. Mx	20	-25.00	1647.20	-1.59
			Max. My	2	-25.00	-1.04	1645.91
			Max. Vy	20	-29.13	1647.20	-1.59
			Max. Vx	2	-29.24	-1.04	1645.91
			Max. Torque	4			4.05
L27	73.91 - 68.91	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-50.51	4.16	2.80
			Max. Mx	20	-26.72	1793.89	-1.81
			Max. My	2	-26.71	-1.25	1793.22
			Max. Vy	20	-29.57	1793.89	-1.81
			Max. Vx	2	-29.71	-1.25	1793.22
			Max. Torque	4			4.05
L28	68.91 - 65.5	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-51.96	4.20	2.84
			Max. Mx	20	-27.90	1895.20	-1.96
			Max. My	2	-27.89	-1.39	1895.01
			Max. Vy	20	-29.87	1895.20	-1.96
			Max. Vx	2	-30.02	-1.39	1895.01
			Max. Torque	4			4.05
L29	65.5 - 65.25	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-52.08	4.21	2.85
			Max. Mx	20	-28.01	1902.67	-1.98
			Max. My	2	-28.00	-1.41	1902.51
			Max. Vy	20	-29.88	1902.67	-1.98
			Max. Vx	2	-30.03	-1.41	1902.51
			Max. Torque	4			4.04
L30	65.25 - 64.5	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-52.43	4.21	2.85
			Max. Mx	20	-28.29	1925.10	-2.01
			Max. My	2	-28.28	-1.44	1925.06
			Max. Vy	20	-29.96	1925.10	-2.01
			Max. Vx	2	-30.11	-1.44	1925.06
			Max. Torque	4			4.04
L31	64.5 - 64.25	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-52.54	4.22	2.86
			Max. Mx	20	-28.39	1932.59	-2.02
			Max. My	2	-28.38	-1.45	1932.59
			Max. Vy	20	-29.98	1932.59	-2.02
			Max. Vx	2	-30.12	-1.45	1932.59
			Max. Torque	4			4.04
L32	64.25 - 59.25	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-54.79	4.26	2.91
			Max. Mx	20	-30.22	2083.56	-2.24
			Max. My	2	-30.21	-1.66	2084.34
			Max. Vy	20	-30.43	2083.56	-2.24
			Max. Vx	2	-30.59	-1.66	2084.34
			Max. Torque	4			4.04
L33	59.25 - 58.58	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-55.10	4.27	2.92
			Max. Mx	20	-30.48	2103.96	-2.27
			Max. My	2	-30.47	-1.68	2104.85
			Max. Vy	20	-30.48	2103.96	-2.27
			Max. Vx	2	-30.65	-1.68	2104.85
			Max. Torque	4			4.04
L34	58.58 - 58.33	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-55.22	4.27	2.92
			Max. Mx	20	-30.58	2111.58	-2.28
			Max. My	2	-30.57	-1.70	2112.51
			Max. Vy	20	-30.50	2111.58	-2.28

<b>tnxTower</b>  <b>Tower Engineering Professionals</b> 326 Tryon Road Raleigh, N.C. Phone: (919) 661-6351 FAX: (919) 661-6350	<b>Job</b> Preston / Town Hall (BU 876360)	<b>Page</b> 39 of 55
	<b>Project</b> TEP No. 25620.161151	<b>Date</b> 10:12:11 03/21/18
	<b>Client</b> Crown Castle	<b>Designed by</b> RKE

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Axial K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
L35	58.33 - 57.25	Pole	Max. Vx	2	-30.67	-1.70	2112.51
			Max. Torque	4			4.04
			Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-55.73	4.28	2.93
			Max. Mx	20	-30.99	2144.57	-2.33
			Max. My	2	-30.98	-1.74	2145.68
			Max. Vy	20	-30.61	2144.57	-2.33
			Max. Vx	2	-30.78	-1.74	2145.68
L36	57.25 - 57	Pole	Max. Torque	4			4.04
			Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-55.85	4.29	2.93
			Max. Mx	20	-31.10	2152.23	-2.34
			Max. My	2	-31.09	-1.75	2153.37
			Max. Vy	20	-30.62	2152.23	-2.34
			Max. Vx	2	-30.79	-1.75	2153.37
			Max. Torque	4			4.04
L37	57 - 52	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-58.26	4.34	2.99
			Max. Mx	20	-33.08	2306.43	-2.56
			Max. My	2	-33.07	-1.96	2308.46
			Max. Vy	20	-31.07	2306.43	-2.56
			Max. Vx	2	-31.26	-1.96	2308.46
			Max. Torque	4			4.04
			Max Tension	1	0.00	0.00	0.00
L38	52 - 44.41	Pole	Max. Compression	26	-59.58	4.79	2.77
			Max. Mx	20	-34.13	2382.14	-2.79
			Max. My	2	-34.12	-1.82	2384.23
			Max. Vy	20	-31.38	2382.14	-2.79
			Max. Vx	2	-31.54	-1.82	2384.23
			Max. Torque	2			4.18
			Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-65.12	4.85	3.34
L39	44.41 - 43.41	Pole	Max. Mx	20	-38.63	2578.02	-2.70
			Max. My	2	-38.63	-2.00	2581.33
			Max. Vy	20	-32.16	2578.02	-2.70
			Max. Vx	2	-32.29	-2.00	2581.33
			Max. Torque	4			4.27
			Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-67.74	4.87	3.40
			Max. Mx	20	-40.82	2739.75	-2.86
L40	43.41 - 38.41	Pole	Max. My	2	-40.81	-2.15	2743.79
			Max. Vy	20	-32.57	2739.75	-2.86
			Max. Vx	2	-32.73	-2.15	2743.79
			Max. Torque	4			4.27
			Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-69.81	4.88	3.44
			Max. Mx	20	-42.54	2867.64	-2.97
			Max. My	2	-42.54	-2.26	2872.33
L41	38.41 - 34.5	Pole	Max. Vy	20	-32.88	2867.64	-2.97
			Max. Vx	2	-33.06	-2.26	2872.33
			Max. Torque	4			4.27
			Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-69.97	4.89	3.45
			Max. Mx	20	-42.69	2875.85	-2.98
			Max. My	2	-42.68	-2.27	2880.60
			Max. Vy	20	-32.89	2875.85	-2.98
L42	34.5 - 34.25	Pole	Max. Vx	2	-33.07	-2.27	2880.60
			Max. Torque	4			4.27
			Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-70.44	4.89	3.46
			Max. Mx	20	-43.09	2900.54	-3.00
			Max. My	2			
			Max. Vy	20			
			Max. Vx	20			
L43	34.25 - 33.5	Pole	Max. Torque	4			4.27
			Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-70.44	4.89	3.46
			Max. Mx	20	-43.09	2900.54	-3.00

<b>tnxTower</b>  <b>Tower Engineering Professionals</b> 326 Tryon Road Raleigh, N.C. Phone: (919) 661-6351 FAX: (919) 661-6350	<b>Job</b>	Preston / Town Hall (BU 876360)	<b>Page</b>	40 of 55
	<b>Project</b>	TEP No. 25620.161151	<b>Date</b>	10:12:11 03/21/18
	<b>Client</b>	Crown Castle	<b>Designed by</b>	RKE

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Axial K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
L44	33.5 - 33.25	Pole	Max. My	2	-43.08	-2.29	2905.42
			Max. Vy	20	-32.96	2900.54	-3.00
			Max. Vx	2	-33.14	-2.29	2905.42
			Max. Torque	4			4.27
			Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-70.58	4.89	3.46
			Max. Mx	20	-43.21	2908.78	-3.01
			Max. My	2	-43.20	-2.30	2913.71
			Max. Vy	20	-32.97	2908.78	-3.01
			Max. Vx	2	-33.15	-2.30	2913.71
L45	33.25 - 29.5	Pole	Max. Torque	4			4.27
			Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-72.66	4.91	3.50
			Max. Mx	20	-44.95	3032.93	-3.12
			Max. My	2	-44.94	-2.41	3038.59
			Max. Vy	20	-33.27	3032.93	-3.12
			Max. Vx	2	-33.47	-2.41	3038.59
			Max. Torque	4			4.27
			Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-72.80	4.91	3.51
L46	29.5 - 29.25	Pole	Max. Mx	20	-45.08	3041.25	-3.13
			Max. My	2	-45.08	-2.41	3046.96
			Max. Vy	20	-33.27	3041.25	-3.13
			Max. Vx	2	-33.48	-2.41	3046.96
			Max. Torque	4			4.27
			Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-73.24	4.91	3.52
			Max. Mx	20	-45.45	3066.22	-3.15
			Max. My	2	-45.44	-2.44	3072.09
			Max. Vy	20	-33.34	3066.22	-3.15
L47	29.25 - 28.5	Pole	Max. Vx	2	-33.55	-2.44	3072.09
			Max. Torque	4			4.27
			Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-73.39	4.92	3.52
			Max. Mx	20	-45.58	3074.55	-3.16
			Max. My	2	-45.57	-2.44	3080.47
			Max. Vy	20	-33.35	3074.55	-3.16
			Max. Vx	2	-33.56	-2.44	3080.47
			Max. Torque	4			4.27
			Max Tension	1	0.00	0.00	0.00
L48	28.5 - 28.25	Pole	Max. Compression	26	-73.84	4.92	3.53
			Max. Mx	20	-45.95	3100.25	-3.19
			Max. My	2	-45.95	-2.47	3106.34
			Max. Vy	20	-33.42	3100.25	-3.19
			Max. Vx	2	-33.64	-2.47	3106.34
			Max. Torque	4			4.27
			Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-73.99	4.92	3.54
			Max. Mx	20	-46.08	3108.61	-3.19
			Max. My	2	-46.08	-2.47	3114.75
L49	28.25 - 27.48	Pole	Max. Vy	20	-33.43	3108.61	-3.19
			Max. Vx	2	-33.65	-2.47	3114.75
			Max. Torque	4			4.27
			Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-76.91	4.95	3.60
			Max. Mx	20	-48.55	3276.65	-3.34
			Max. My	2	-48.55	-2.62	3283.99
			Max. Vy	20	-33.81	3276.65	-3.34
			Max. Vx	2	-34.07	-2.62	3283.99
			Max. Torque	4			4.27
L50	27.48 - 27.23	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-76.91	4.95	3.60
L51	27.23 - 22.23	Pole	Max. Mx	20	-48.55	3276.65	-3.34
			Max. My	2	-48.55	-2.62	3283.99
			Max. Vy	20	-33.81	3276.65	-3.34
			Max. Vx	2	-34.07	-2.62	3283.99
			Max. Torque	4			4.27
			Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-76.91	4.95	3.60
			Max. Mx	20	-48.55	3276.65	-3.34
			Max. My	2	-48.55	-2.62	3283.99
			Max. Vy	20	-33.81	3276.65	-3.34
L52	22.23 - 17.23	Pole	Max. Vx	2	-34.07	-2.62	3283.99
			Max. Torque	4			4.27
L52	22.23 - 17.23	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-76.91	4.95	3.60

<b>tnxTower</b>  <b>Tower Engineering Professionals</b> 326 Tryon Road Raleigh, N.C. Phone: (919) 661-6351 FAX: (919) 661-6350	<b>Job</b> Preston / Town Hall (BU 876360)	<b>Page</b> 41 of 55
	<b>Project</b> TEP No. 25620.161151	<b>Date</b> 10:12:11 03/21/18
	<b>Client</b> Crown Castle	<b>Designed by</b> RKE

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Axial K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
L53	17.23 - 12.23	Pole	Max. Compression	26	-79.85	4.98	3.67
			Max. Mx	20	-51.05	3446.49	-3.49
			Max. My	2	-51.05	-2.77	3455.17
			Max. Vy	20	-34.16	3446.49	-3.49
			Max. Vx	2	-34.44	-2.77	3455.17
			Max. Torque	4			4.27
			Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-82.82	5.02	3.74
			Max. Mx	20	-53.58	3617.98	-3.64
			Max. My	2	-53.58	-2.91	3628.14
L54	12.23 - 7.23	Pole	Max. Vy	20	-34.47	3617.98	-3.64
			Max. Vx	2	-34.78	-2.91	3628.14
			Max. Torque	4			4.27
			Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-85.78	5.05	3.80
			Max. Mx	20	-56.14	3791.04	-3.79
			Max. My	2	-56.14	-3.06	3802.79
			Max. Vy	20	-34.79	3791.04	-3.79
			Max. Vx	2	-35.11	-3.06	3802.79
			Max. Torque	4			4.27
L55	7.23 - 6.9	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-85.99	5.05	3.80
			Max. Mx	20	-56.33	3802.51	-3.80
			Max. My	2	-56.33	-3.07	3814.37
			Max. Vy	20	-34.79	3802.51	-3.80
			Max. Vx	2	-35.12	-3.07	3814.37
			Max. Torque	4			4.27
			Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-86.20	5.05	3.81
			Max. Mx	20	-56.51	3814.69	-3.81
L56	6.9 - 6.55	Pole	Max. My	2	-56.51	-3.08	3826.67
			Max. Vy	20	-34.82	3814.69	-3.81
			Max. Vx	2	-35.15	-3.08	3826.67
			Max. Torque	4			4.27
			Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-86.33	5.05	3.81
			Max. Mx	20	-56.63	3822.35	-3.81
			Max. My	2	-56.63	-3.08	3834.40
			Max. Vy	20	-34.83	3822.35	-3.81
			Max. Vx	2	-35.16	-3.08	3834.40
L57	6.55 - 6.33	Pole	Max. Torque	4			4.27
			Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-86.33	5.05	3.81
			Max. Mx	20	-56.63	3822.35	-3.81
			Max. My	2	-56.63	-3.08	3834.40
			Max. Vy	20	-34.83	3822.35	-3.81
			Max. Vx	2	-35.16	-3.08	3834.40
			Max. Torque	4			4.27
			Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-88.16	5.07	3.85
L58	6.33 - 3.25	Pole	Max. Mx	20	-58.22	3929.90	-3.90
			Max. My	2	-58.22	-3.17	3942.96
			Max. Vy	20	-35.03	3929.90	-3.90
			Max. Vx	2	-35.36	-3.17	3942.96
			Max. Torque	4			4.27
			Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-88.34	5.07	3.85
			Max. Mx	20	-58.39	3938.65	-3.91
			Max. My	2	-58.39	-3.18	3951.80
			Max. Vy	20	-35.03	3938.65	-3.91
L59	3.25 - 3	Pole	Max. Vx	2	-35.36	-3.18	3951.80
			Max. Torque	4			4.27
			Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-88.34	5.07	3.85
			Max. Mx	20	-58.39	3938.65	-3.91
			Max. My	2	-58.39	-3.18	3951.80
			Max. Vy	20	-35.03	3938.65	-3.91
			Max. Vx	2	-35.36	-3.18	3951.80
			Max. Torque	4			4.27
			Max Tension	1	0.00	0.00	0.00
L60	3 - 2.75	Pole	Max. Compression	26	-88.49	5.07	3.85
			Max. Mx	20	-58.53	3947.41	-3.92
			Max. My	2	-58.53	-3.19	3960.64
			Max. Vy	20	-35.04	3947.41	-3.92
			Max. Vx	2	-35.38	-3.19	3960.64
			Max. Torque	4			4.27

<b>tnxTower</b>  <b>Tower Engineering Professionals</b> 326 Tryon Road Raleigh, N.C. Phone: (919) 661-6351 FAX: (919) 661-6350	<b>Job</b> Preston / Town Hall (BU 876360)	<b>Page</b> 42 of 55
	<b>Project</b> TEP No. 25620.161151	<b>Date</b> 10:12:11 03/21/18
	<b>Client</b> Crown Castle	<b>Designed by</b> RKE

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Axial K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
L61	2.75 - 2.5	Pole	Max. Torque	4			4.27
			Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-88.65	5.07	3.85
			Max. Mx	20	-58.67	3956.17	-3.93
			Max. My	2	-58.67	-3.20	3969.49
			Max. Vy	20	-35.06	3956.17	-3.93
			Max. Vx	2	-35.39	-3.20	3969.49
L62	2.5 - 2.25	Pole	Max. Torque	4			4.27
			Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-88.79	5.08	3.86
			Max. Mx	20	-58.79	3964.94	-3.93
			Max. My	2	-58.79	-3.20	3978.34
			Max. Vy	20	-35.08	3964.94	-3.93
			Max. Vx	2	-35.41	-3.20	3978.34
L63	2.25 - 2	Pole	Max. Torque	4			4.27
			Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-88.93	5.08	3.86
			Max. Mx	20	-58.92	3973.71	-3.94
			Max. My	2	-58.92	-3.21	3987.19
			Max. Vy	20	-35.09	3973.71	-3.94
			Max. Vx	2	-35.43	-3.21	3987.19
L64	2 - 0	Pole	Max. Torque	4			4.27
			Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-90.04	5.09	3.87
			Max. Mx	20	-59.90	4044.00	-4.00
			Max. My	2	-59.90	-3.27	4058.15
			Max. Vy	20	-35.22	4044.00	-4.00
			Max. Vx	2	-35.56	-3.27	4058.15
			Max. Torque	4			4.27

### Maximum Reactions

Location	Condition	Gov. Load Comb.	Vertical K	Horizontal, X K	Horizontal, Z K
Pole	Max. Vert	26	90.04	0.00	0.00
	Max. H <sub>x</sub>	20	59.92	35.20	-0.03
	Max. H <sub>z</sub>	3	44.94	-0.03	35.54
	Max. M <sub>x</sub>	2	4058.15	-0.03	35.54
	Max. M <sub>z</sub>	8	4040.92	-35.20	0.03
	Max. Torsion	4	4.27	-17.62	30.31
	Min. Vert	5	44.94	-17.62	30.31
	Min. H <sub>x</sub>	8	59.92	-35.20	0.03
	Min. H <sub>z</sub>	15	44.94	0.03	-35.54
	Min. M <sub>x</sub>	14	-4056.59	0.03	-35.54
	Min. M <sub>z</sub>	20	-4044.00	35.20	-0.03
	Min. Torsion	16	-4.23	17.62	-30.31

### Tower Mast Reaction Summary

Load Combination	Vertical K	Shear <sub>x</sub> K	Shear <sub>z</sub> K	Overturning Moment, M <sub>x</sub> kip-ft	Overturning Moment, M <sub>z</sub> kip-ft	Torque kip-ft

<b>tnxTower</b>  <b>Tower Engineering Professionals</b> 326 Tryon Road Raleigh, N.C. Phone: (919) 661-6351 FAX: (919) 661-6350	<b>Job</b>	Preston / Town Hall (BU 876360)	<b>Page</b>	43 of 55
	<b>Project</b>	TEP No. 25620.161151	<b>Date</b>	10:12:11 03/21/18
	<b>Client</b>	Crown Castle	<b>Designed by</b>	RKE

Load Combination	Vertical	Shear <sub>x</sub>	Shear <sub>y</sub>	Overtuning Moment, M <sub>x</sub>	Overtuning Moment, M <sub>y</sub>	Torque
	K	K	K	kip-ft	kip-ft	kip-ft
Dead Only	49.93	0.00	0.00	-0.62	1.22	-0.00
1.2 Dead+1.6 Wind 0 deg - No Ice	59.92	0.03	-35.54	-4058.15	-3.27	-4.18
0.9 Dead+1.6 Wind 0 deg - No Ice	44.94	0.03	-35.54	-4016.13	-3.61	-4.15
1.2 Dead+1.6 Wind 30 deg - No Ice	59.92	17.62	-30.31	-3485.66	-2022.58	-4.27
0.9 Dead+1.6 Wind 30 deg - No Ice	44.94	17.62	-30.31	-3449.43	-2002.06	-4.24
1.2 Dead+1.6 Wind 60 deg - No Ice	59.92	30.48	-17.52	-2015.50	-3499.50	-3.20
0.9 Dead+1.6 Wind 60 deg - No Ice	44.94	30.48	-17.52	-1994.48	-3463.73	-3.18
1.2 Dead+1.6 Wind 90 deg - No Ice	59.92	35.20	-0.03	-5.54	-4040.92	-1.26
0.9 Dead+1.6 Wind 90 deg - No Ice	44.94	35.20	-0.03	-5.29	-3999.57	-1.25
1.2 Dead+1.6 Wind 120 deg - No Ice	59.92	30.45	17.46	2005.71	-3494.75	1.01
0.9 Dead+1.6 Wind 120 deg - No Ice	44.94	30.45	17.46	1985.17	-3459.03	1.00
1.2 Dead+1.6 Wind 150 deg - No Ice	59.92	17.56	30.28	3479.36	-2014.32	3.00
0.9 Dead+1.6 Wind 150 deg - No Ice	44.94	17.56	30.28	3443.59	-1993.90	2.98
1.2 Dead+1.6 Wind 180 deg - No Ice	59.92	-0.03	35.54	4056.59	6.27	4.17
0.9 Dead+1.6 Wind 180 deg - No Ice	44.94	-0.03	35.54	4014.98	5.83	4.14
1.2 Dead+1.6 Wind 210 deg - No Ice	59.92	-17.62	30.31	3484.14	2025.59	4.23
0.9 Dead+1.6 Wind 210 deg - No Ice	44.94	-17.62	30.31	3448.31	2004.28	4.20
1.2 Dead+1.6 Wind 240 deg - No Ice	59.92	-30.48	17.52	2013.99	3502.55	3.17
0.9 Dead+1.6 Wind 240 deg - No Ice	44.94	-30.48	17.52	1993.36	3465.98	3.15
1.2 Dead+1.6 Wind 270 deg - No Ice	59.92	-35.20	0.03	4.00	4044.00	1.27
0.9 Dead+1.6 Wind 270 deg - No Ice	44.94	-35.20	0.03	4.15	4001.84	1.26
1.2 Dead+1.6 Wind 300 deg - No Ice	59.92	-30.45	-17.46	-2007.29	3497.81	-0.97
0.9 Dead+1.6 Wind 300 deg - No Ice	44.94	-30.45	-17.46	-1986.34	3461.29	-0.97
1.2 Dead+1.6 Wind 330 deg - No Ice	59.92	-17.56	-30.28	-3480.95	2017.35	-2.96
0.9 Dead+1.6 Wind 330 deg - No Ice	44.94	-17.56	-30.28	-3444.76	1996.13	-2.95
1.2 Dead+1.0 Ice+1.0 Temp	90.04	-0.00	-0.00	-3.87	5.09	-0.00
1.2 Dead+1.0 Wind 0 deg+1.0 Ice+1.0 Temp	90.04	-0.00	-9.46	-1045.61	5.03	-0.81
1.2 Dead+1.0 Wind 30 deg+1.0 Ice+1.0 Temp	90.04	4.29	-7.41	-857.93	-487.76	-0.88
1.2 Dead+1.0 Wind 60 deg+1.0 Ice+1.0 Temp	90.04	7.42	-4.28	-497.13	-848.46	-0.70
1.2 Dead+1.0 Wind 90 deg+1.0 Ice+1.0 Temp	90.04	9.42	0.00	-4.20	-1042.06	-0.34
1.2 Dead+1.0 Wind 120 deg+1.0 Ice+1.0 Temp	90.04	7.42	4.28	488.79	-848.25	0.11
1.2 Dead+1.0 Wind 150	90.04	4.29	7.41	849.74	-487.40	0.53

<b>tnxTower</b>  <b>Tower Engineering Professionals</b> 326 Tryon Road Raleigh, N.C. Phone: (919) 661-6351 FAX: (919) 661-6350	<b>Job</b> Preston / Town Hall (BU 876360)	<b>Page</b> 44 of 55
	<b>Project</b> TEP No. 25620.161151	<b>Date</b> 10:12:11 03/21/18
	<b>Client</b> Crown Castle	<b>Designed by</b> RKE

Load Combination	Vertical	Shear <sub>x</sub>	Shear <sub>y</sub>	Overturning Moment, M <sub>x</sub>	Overturning Moment, M <sub>y</sub>	Torque
	K	K	K	kip-ft	kip-ft	kip-ft
deg+1.0 Ice+1.0 Temp						
1.2 Dead+1.0 Wind 180	90.04	0.00	9.46	1037.64	5.45	0.81
deg+1.0 Ice+1.0 Temp						
1.2 Dead+1.0 Wind 210	90.04	-4.29	7.41	849.96	498.24	0.87
deg+1.0 Ice+1.0 Temp						
1.2 Dead+1.0 Wind 240	90.04	-7.42	4.28	489.16	858.94	0.70
deg+1.0 Ice+1.0 Temp						
1.2 Dead+1.0 Wind 270	90.04	-9.42	-0.00	-3.78	1052.54	0.34
deg+1.0 Ice+1.0 Temp						
1.2 Dead+1.0 Wind 300	90.04	-7.42	-4.28	-496.77	858.73	-0.11
deg+1.0 Ice+1.0 Temp						
1.2 Dead+1.0 Wind 330	90.04	-4.29	-7.41	-857.72	497.88	-0.53
deg+1.0 Ice+1.0 Temp						
Dead+Wind 0 deg - Service	49.93	0.01	-6.49	-737.80	0.41	-0.77
Dead+Wind 30 deg - Service	49.93	3.22	-5.53	-633.78	-366.45	-0.79
Dead+Wind 60 deg - Service	49.93	5.57	-3.20	-366.69	-634.79	-0.59
Dead+Wind 90 deg - Service	49.93	6.43	-0.01	-1.51	-733.15	-0.23
Dead+Wind 120 deg - Service	49.93	5.56	3.19	363.89	-633.92	0.18
Dead+Wind 150 deg - Service	49.93	3.21	5.53	631.61	-364.95	0.55
Dead+Wind 180 deg - Service	49.93	-0.01	6.49	736.50	2.14	0.77
Dead+Wind 210 deg - Service	49.93	-3.22	5.53	632.48	369.01	0.79
Dead+Wind 240 deg - Service	49.93	-5.57	3.20	365.39	637.34	0.59
Dead+Wind 270 deg - Service	49.93	-6.43	0.01	0.22	735.71	0.23
Dead+Wind 300 deg - Service	49.93	-5.56	-3.19	-365.19	636.48	-0.18
Dead+Wind 330 deg - Service	49.93	-3.21	-5.53	-632.91	367.51	-0.55

## Solution Summary

Load Comb.	Sum of Applied Forces			Sum of Reactions			% Error
	PX K	PY K	PZ K	PX K	PY K	PZ K	
1	0.00	-49.93	0.00	0.00	49.93	0.00	0.000%
2	0.03	-59.92	-35.54	-0.03	59.92	35.54	0.000%
3	0.03	-44.94	-35.54	-0.03	44.94	35.54	0.000%
4	17.62	-59.92	-30.31	-17.62	59.92	30.31	0.000%
5	17.62	-44.94	-30.31	-17.62	44.94	30.31	0.000%
6	30.48	-59.92	-17.52	-30.48	59.92	17.52	0.000%
7	30.48	-44.94	-17.52	-30.48	44.94	17.52	0.000%
8	35.20	-59.92	-0.03	-35.20	59.92	0.03	0.000%
9	35.20	-44.94	-0.03	-35.20	44.94	0.03	0.000%
10	30.45	-59.92	17.46	-30.45	59.92	-17.46	0.000%
11	30.45	-44.94	17.46	-30.45	44.94	-17.46	0.000%
12	17.56	-59.92	30.28	-17.56	59.92	-30.28	0.000%
13	17.56	-44.94	30.28	-17.56	44.94	-30.28	0.000%
14	-0.03	-59.92	35.54	0.03	59.92	-35.54	0.000%
15	-0.03	-44.94	35.54	0.03	44.94	-35.54	0.000%
16	-17.62	-59.92	30.31	17.62	59.92	-30.31	0.000%
17	-17.62	-44.94	30.31	17.62	44.94	-30.31	0.000%
18	-30.48	-59.92	17.52	30.48	59.92	-17.52	0.000%
19	-30.48	-44.94	17.52	30.48	44.94	-17.52	0.000%
20	-35.20	-59.92	0.03	35.20	59.92	-0.03	0.000%
21	-35.20	-44.94	0.03	35.20	44.94	-0.03	0.000%
22	-30.45	-59.92	-17.46	30.45	59.92	17.46	0.000%
23	-30.45	-44.94	-17.46	30.45	44.94	17.46	0.000%
24	-17.56	-59.92	-30.28	17.56	59.92	30.28	0.000%
25	-17.56	-44.94	-30.28	17.56	44.94	30.28	0.000%
26	0.00	-90.04	0.00	0.00	90.04	0.00	0.000%
27	-0.00	-90.04	-9.46	0.00	90.04	9.46	0.000%

<b>tnxTower</b>  <b>Tower Engineering Professionals</b> 326 Tryon Road Raleigh, N.C. Phone: (919) 661-6351 FAX: (919) 661-6350	<b>Job</b> Preston / Town Hall (BU 876360)	<b>Page</b> 45 of 55
	<b>Project</b> TEP No. 25620.161151	<b>Date</b> 10:12:11 03/21/18
	<b>Client</b> Crown Castle	<b>Designed by</b> RKE

Load Comb.	Sum of Applied Forces			Sum of Reactions			% Error
	PX K	PY K	PZ K	PX K	PY K	PZ K	
28	4.29	-90.04	-7.41	-4.29	90.04	7.41	0.000%
29	7.42	-90.04	-4.28	-7.42	90.04	4.28	0.000%
30	9.42	-90.04	0.00	-9.42	90.04	-0.00	0.000%
31	7.42	-90.04	4.28	-7.42	90.04	-4.28	0.000%
32	4.29	-90.04	7.41	-4.29	90.04	-7.41	0.000%
33	0.00	-90.04	9.46	-0.00	90.04	-9.46	0.000%
34	-4.29	-90.04	7.41	4.29	90.04	-7.41	0.000%
35	-7.42	-90.04	4.28	7.42	90.04	-4.28	0.000%
36	-9.42	-90.04	-0.00	9.42	90.04	0.00	0.000%
37	-7.42	-90.04	-4.28	7.42	90.04	4.28	0.000%
38	-4.29	-90.04	-7.41	4.29	90.04	7.41	0.000%
39	0.01	-49.93	-6.49	-0.01	49.93	6.49	0.000%
40	3.22	-49.93	-5.53	-3.22	49.93	5.53	0.000%
41	5.57	-49.93	-3.20	-5.57	49.93	3.20	0.000%
42	6.43	-49.93	-0.01	-6.43	49.93	0.01	0.000%
43	5.56	-49.93	3.19	-5.56	49.93	-3.19	0.000%
44	3.21	-49.93	5.53	-3.21	49.93	-5.53	0.000%
45	-0.01	-49.93	6.49	0.01	49.93	-6.49	0.000%
46	-3.22	-49.93	5.53	3.22	49.93	-5.53	0.000%
47	-5.57	-49.93	3.20	5.57	49.93	-3.20	0.000%
48	-6.43	-49.93	0.01	6.43	49.93	-0.01	0.000%
49	-5.56	-49.93	-3.19	5.56	49.93	3.19	0.000%
50	-3.21	-49.93	-5.53	3.21	49.93	5.53	0.000%

## Non-Linear Convergence Results

Load Combination	Converged?	Number of Cycles	Displacement Tolerance	Force Tolerance
1	Yes	4	0.00000001	0.00000001
2	Yes	6	0.00000001	0.00007966
3	Yes	5	0.00000001	0.00080831
4	Yes	6	0.00000001	0.00080728
5	Yes	6	0.00000001	0.00023602
6	Yes	6	0.00000001	0.00089354
7	Yes	6	0.00000001	0.00026602
8	Yes	5	0.00000001	0.00062933
9	Yes	5	0.00000001	0.00027584
10	Yes	6	0.00000001	0.00086233
11	Yes	6	0.00000001	0.00025577
12	Yes	6	0.00000001	0.00081525
13	Yes	6	0.00000001	0.00023940
14	Yes	6	0.00000001	0.00008535
15	Yes	5	0.00000001	0.00086534
16	Yes	6	0.00000001	0.00090864
17	Yes	6	0.00000001	0.00027127
18	Yes	6	0.00000001	0.00081898
19	Yes	6	0.00000001	0.00023985
20	Yes	5	0.00000001	0.00050254
21	Yes	5	0.00000001	0.00021961
22	Yes	6	0.00000001	0.00083912
23	Yes	6	0.00000001	0.00024725
24	Yes	6	0.00000001	0.00088958
25	Yes	6	0.00000001	0.00026502
26	Yes	4	0.00000001	0.00098389
27	Yes	6	0.00000001	0.00084874
28	Yes	7	0.00000001	0.00010684



<b>tnxTower</b>  <b>Tower Engineering Professionals</b> 326 Tryon Road Raleigh, N.C. Phone: (919) 661-6351 FAX: (919) 661-6350	Job	Preston / Town Hall (BU 876360)	Page	46 of 55
	Project	TEP No. 25620.161151	Date	10:12:11 03/21/18
	Client	Crown Castle	Designed by	RKE

29	Yes	7	0.00000001	0.00010852
30	Yes	6	0.00000001	0.00083413
31	Yes	7	0.00000001	0.00010601
32	Yes	7	0.00000001	0.00010542
33	Yes	6	0.00000001	0.00083649
34	Yes	7	0.00000001	0.00010976
35	Yes	7	0.00000001	0.00010776
36	Yes	6	0.00000001	0.00085341
37	Yes	7	0.00000001	0.00010979
38	Yes	7	0.00000001	0.00011074
39	Yes	5	0.00000001	0.00007936
40	Yes	5	0.00000001	0.00016107
41	Yes	5	0.00000001	0.00021213
42	Yes	4	0.00000001	0.00079365
43	Yes	5	0.00000001	0.00018775
44	Yes	5	0.00000001	0.00016125
45	Yes	5	0.00000001	0.00007999
46	Yes	5	0.00000001	0.00022591
47	Yes	5	0.00000001	0.00016413
48	Yes	4	0.00000001	0.00078447
49	Yes	5	0.00000001	0.00017416
50	Yes	5	0.00000001	0.00021148

### Maximum Tower Deflections - Service Wind

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
L1	147 - 142	19.734	48	1.4914	0.0111
L2	142 - 137	18.183	48	1.4670	0.0111
L3	137 - 132	16.669	48	1.4217	0.0111
L4	132 - 127	15.215	48	1.3516	0.0092
L5	127 - 120.37	13.847	48	1.2569	0.0070
L6	123.62 - 118.62	12.984	48	1.1791	0.0057
L7	118.62 - 113.62	11.783	39	1.1026	0.0047
L8	113.62 - 112.41	10.692	39	0.9826	0.0034
L9	112.41 - 112.16	10.447	39	0.9524	0.0032
L10	112.16 - 110.5	10.398	39	0.9493	0.0031
L11	110.5 - 110.25	10.072	39	0.9285	0.0030
L12	110.25 - 105.25	10.023	39	0.9262	0.0029
L13	105.25 - 105	9.080	39	0.8767	0.0026
L14	105 - 104.75	9.034	39	0.8742	0.0026
L15	104.75 - 103.5	8.988	39	0.8723	0.0025
L16	103.5 - 103.25	8.762	39	0.8627	0.0025
L17	103.25 - 98.25	8.716	39	0.8602	0.0025
L18	98.25 - 94.83	7.843	39	0.8087	0.0022
L19	94.83 - 94.58	7.277	39	0.7725	0.0020
L20	94.58 - 94.17	7.237	39	0.7698	0.0020
L21	94.17 - 93.82	7.171	39	0.7653	0.0019
L22	93.82 - 93.66	7.115	39	0.7619	0.0019
L23	93.66 - 84.91	7.090	39	0.7603	0.0019
L24	89.08 - 83.91	6.383	39	0.7139	0.0017
L25	83.91 - 78.91	5.624	39	0.6834	0.0016
L26	78.91 - 73.91	4.934	39	0.6340	0.0014
L27	73.91 - 68.91	4.296	39	0.5846	0.0012
L28	68.91 - 65.5	3.710	39	0.5347	0.0011
L29	65.5 - 65.25	3.341	39	0.5008	0.0010
L30	65.25 - 64.5	3.315	39	0.4987	0.0010
L31	64.5 - 64.25	3.237	39	0.4925	0.0010
L32	64.25 - 59.25	3.211	39	0.4902	0.0010

<b>tnxTower</b>  <b>Tower Engineering Professionals</b> 326 Tryon Road Raleigh, N.C. Phone: (919) 661-6351 FAX: (919) 661-6350	<b>Job</b> Preston / Town Hall (BU 876360)	<b>Page</b> 47 of 55
	<b>Project</b> TEP No. 25620.161151	<b>Date</b> 10:12:11 03/21/18
	<b>Client</b> Crown Castle	<b>Designed by</b> RKE

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
L33	59.25 - 58.58	2.722	39	0.4437	0.0008
L34	58.58 - 58.33	2.660	39	0.4375	0.0008
L35	58.33 - 57.25	2.637	39	0.4354	0.0008
L36	57.25 - 57	2.540	39	0.4260	0.0008
L37	57 - 52	2.518	39	0.4239	0.0008
L38	52 - 44.41	2.096	39	0.3809	0.0007
L39	49.58 - 43.41	1.909	39	0.3602	0.0006
L40	43.41 - 38.41	1.460	39	0.3301	0.0006
L41	38.41 - 34.5	1.136	39	0.2886	0.0005
L42	34.5 - 34.25	0.913	39	0.2566	0.0004
L43	34.25 - 33.5	0.900	39	0.2549	0.0004
L44	33.5 - 33.25	0.860	39	0.2497	0.0004
L45	33.25 - 29.5	0.847	39	0.2476	0.0004
L46	29.5 - 29.25	0.665	39	0.2160	0.0003
L47	29.25 - 28.5	0.654	39	0.2141	0.0003
L48	28.5 - 28.25	0.621	39	0.2085	0.0003
L49	28.25 - 27.48	0.610	39	0.2066	0.0003
L50	27.48 - 27.23	0.577	39	0.2010	0.0003
L51	27.23 - 22.23	0.566	39	0.1991	0.0003
L52	22.23 - 17.23	0.378	39	0.1618	0.0002
L53	17.23 - 12.23	0.227	39	0.1254	0.0002
L54	12.23 - 7.23	0.115	39	0.0891	0.0001
L55	7.23 - 6.9	0.040	39	0.0533	0.0001
L56	6.9 - 6.55	0.037	39	0.0510	0.0001
L57	6.55 - 6.33	0.033	39	0.0484	0.0001
L58	6.33 - 3.25	0.031	39	0.0468	0.0001
L59	3.25 - 3	0.008	39	0.0237	0.0000
L60	3 - 2.75	0.007	39	0.0222	0.0000
L61	2.75 - 2.5	0.006	39	0.0206	0.0000
L62	2.5 - 2.25	0.005	39	0.0189	0.0000
L63	2.25 - 2	0.004	39	0.0171	0.0000
L64	2 - 0	0.003	39	0.0151	0.0000

### Critical Deflections and Radius of Curvature - Service Wind

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
147.0000	APXVSP18-C-A20	48	19.734	1.4914	0.0111	8085
136.0000	(2) LPA-80080/4CF w/ Mount Pipe	48	16.373	1.4095	0.0108	4703
129.0000	ERICSSON AIR 21 B2A B4P w/ Mount Pipe	48	14.381	1.2991	0.0079	2880
120.0000	(2) TME-RRUS-11	48	12.105	1.1238	0.0049	2987
118.0000	AM-X-WM-17-65-00T w/ Mount Pipe	39	11.641	1.0913	0.0046	2674
50.0000	KS24019-L112A	39	1.941	0.3634	0.0006	8907
45.0000	KS24019-L112A	39	1.571	0.3382	0.0006	9112

### Maximum Tower Deflections - Design Wind

<b>tnxTower</b>  <b>Tower Engineering Professionals</b> 326 Tryon Road Raleigh, N.C. Phone: (919) 661-6351 FAX: (919) 661-6350	<b>Job</b> Preston / Town Hall (BU 876360)	<b>Page</b> 48 of 55
	<b>Project</b> TEP No. 25620.161151	<b>Date</b> 10:12:11 03/21/18
	<b>Client</b> Crown Castle	<b>Designed by</b> RKE

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
L1	147 - 142	108.194	2	8.1595	0.0603
L2	142 - 137	99.737	2	8.0253	0.0603
L3	137 - 132	91.482	2	7.7772	0.0603
L4	132 - 127	83.544	2	7.3999	0.0498
L5	127 - 120.37	76.072	2	6.8886	0.0381
L6	123.62 - 118.62	71.354	2	6.4659	0.0307
L7	118.62 - 113.62	64.778	2	6.0494	0.0254
L8	113.62 - 112.41	58.790	2	5.3952	0.0186
L9	112.41 - 112.16	57.445	2	5.2305	0.0171
L10	112.16 - 110.5	57.172	2	5.2137	0.0169
L11	110.5 - 110.25	55.382	2	5.1002	0.0160
L12	110.25 - 105.25	55.115	2	5.0874	0.0159
L13	105.25 - 105	49.935	2	4.8175	0.0139
L14	105 - 104.75	49.683	2	4.8037	0.0138
L15	104.75 - 103.5	49.432	2	4.7934	0.0138
L16	103.5 - 103.25	48.185	2	4.7411	0.0134
L17	103.25 - 98.25	47.938	2	4.7276	0.0133
L18	98.25 - 94.83	43.139	2	4.4460	0.0117
L19	94.83 - 94.58	40.028	2	4.2479	0.0107
L20	94.58 - 94.17	39.806	2	4.2332	0.0106
L21	94.17 - 93.82	39.444	2	4.2087	0.0105
L22	93.82 - 93.66	39.137	2	4.1899	0.0104
L23	93.66 - 84.91	38.997	2	4.1813	0.0104
L24	89.08 - 83.91	35.111	2	3.9273	0.0092
L25	83.91 - 78.91	30.939	2	3.7606	0.0086
L26	78.91 - 73.91	27.147	2	3.4887	0.0076
L27	73.91 - 68.91	23.638	2	3.2172	0.0067
L28	68.91 - 65.5	20.414	2	2.9427	0.0058
L29	65.5 - 65.25	18.380	2	2.7560	0.0053
L30	65.25 - 64.5	18.236	2	2.7445	0.0053
L31	64.5 - 64.25	17.808	2	2.7103	0.0052
L32	64.25 - 59.25	17.667	2	2.6976	0.0052
L33	59.25 - 58.58	14.977	2	2.4420	0.0045
L34	58.58 - 58.33	14.637	2	2.4079	0.0044
L35	58.33 - 57.25	14.511	2	2.3960	0.0044
L36	57.25 - 57	13.975	2	2.3446	0.0043
L37	57 - 52	13.853	2	2.3328	0.0042
L38	52 - 44.41	11.535	2	2.0963	0.0037
L39	49.58 - 43.41	10.501	2	1.9823	0.0034
L40	43.41 - 38.41	8.034	2	1.8167	0.0031
L41	38.41 - 34.5	6.252	2	1.5884	0.0026
L42	34.5 - 34.25	5.024	2	1.4118	0.0023
L43	34.25 - 33.5	4.950	2	1.4025	0.0022
L44	33.5 - 33.25	4.732	2	1.3743	0.0022
L45	33.25 - 29.5	4.661	2	1.3627	0.0022
L46	29.5 - 29.25	3.659	2	1.1886	0.0018
L47	29.25 - 28.5	3.597	2	1.1782	0.0018
L48	28.5 - 28.25	3.414	2	1.1472	0.0018
L49	28.25 - 27.48	3.355	2	1.1370	0.0018
L50	27.48 - 27.23	3.174	2	1.1058	0.0017
L51	27.23 - 22.23	3.116	2	1.0957	0.0017
L52	22.23 - 17.23	2.077	2	0.8900	0.0013
L53	17.23 - 12.23	1.250	2	0.6900	0.0010
L54	12.23 - 7.23	0.633	2	0.4902	0.0007
L55	7.23 - 6.9	0.223	2	0.2933	0.0004
L56	6.9 - 6.55	0.203	2	0.2808	0.0004
L57	6.55 - 6.33	0.183	2	0.2665	0.0004
L58	6.33 - 3.25	0.171	2	0.2575	0.0004
L59	3.25 - 3	0.046	2	0.1305	0.0002
L60	3 - 2.75	0.039	2	0.1222	0.0002
L61	2.75 - 2.5	0.033	2	0.1132	0.0002

<b>tnxTower</b>  <b>Tower Engineering Professionals</b> 326 Tryon Road Raleigh, N.C. Phone: (919) 661-6351 FAX: (919) 661-6350	Job	Preston / Town Hall (BU 876360)	Page	49 of 55
	Project	TEP No. 25620.161151	Date	10:12:11 03/21/18
	Client	Crown Castle	Designed by	RKE

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
L62	2.5 - 2.25	0.027	2	0.1041	0.0001
L63	2.25 - 2	0.022	2	0.0938	0.0001
L64	2 - 0	0.017	2	0.0833	0.0001

### Critical Deflections and Radius of Curvature - Design Wind

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
147.0000	APXVSPP18-C-A20	2	108.194	8.1595	0.0603	1531
136.0000	(2) LPA-80080/4CF w/ Mount Pipe	2	89.865	7.7113	0.0589	899
129.0000	ERICSSON AIR 21 B2A B4P w/ Mount Pipe	2	78.993	7.1169	0.0428	549
120.0000	(2) TME-RRUS-11	2	66.541	6.1654	0.0266	561
118.0000	AM-X-WM-17-65-00T w/ Mount Pipe	2	64.000	5.9881	0.0247	501
50.0000	KS24019-L112A	2	10.678	1.9997	0.0035	1622
45.0000	KS24019-L112A	2	8.645	1.8610	0.0032	1659

### Compression Checks

### Pole Design Data

Section No.	Elevation ft	Size	L ft	L <sub>u</sub> ft	Kl/r	A in <sup>2</sup>	P <sub>u</sub> K	φP <sub>n</sub> K	Ratio P <sub>u</sub> / φP <sub>n</sub>
L1	147 - 142 (1)	TP17.3259x16.25x0.1875	5.0000	0.0000	0.0	10.1995	-2.64	757.77	0.003
L2	142 - 137 (2)	TP18.4017x17.3259x0.1875	5.0000	0.0000	0.0	10.8397	-2.87	805.34	0.004
L3	137 - 132 (3)	TP19.4776x18.4017x0.1875	5.0000	0.0000	0.0	11.4800	-4.94	846.88	0.006
L4	132 - 127 (4)	TP20.5534x19.4776x0.1875	5.0000	0.0000	0.0	12.1203	-8.57	881.15	0.010
L5	127 - 120.37 (5)	TP21.98x20.5534x0.1875	6.6300	0.0000	0.0	12.5531	-8.95	903.55	0.010
L6	120.37 - 118.62 (6)	TP21.8559x20.78x0.25	5.0000	0.0000	0.0	17.1443	-10.08	1273.74	0.008
L7	118.62 - 113.62 (7)	TP22.9319x21.8559x0.25	5.0000	0.0000	0.0	17.9981	-12.57	1337.17	0.009
L8	113.62 - 112.41 (8)	TP23.1923x22.9319x0.25	1.2100	0.0000	0.0	18.2047	-12.76	1352.52	0.009
L9	112.41 - 112.16 (9)	TP23.2461x23.1923x0.5375	0.2500	0.0000	0.0	38.7414	-12.84	2878.29	0.004
L10	112.16 - 110.5 (10)	TP23.6033x23.2461x0.525	1.6600	0.0000	0.0	38.4565	-13.15	2857.13	0.005
L11	110.5 - 110.25 (11)	TP23.6571x23.6033x0.75	0.2500	0.0000	0.0	54.5303	-13.23	4051.33	0.003
L12	110.25 - 105.25 (12)	TP24.733x23.6571x0.725	5.0000	0.0000	0.0	55.2461	-14.46	4104.51	0.004
L13	105.25 - 105 (13)	TP24.7868x24.733x0.725	0.2500	0.0000	0.0	55.3699	-14.53	4113.71	0.004
L14	105 - 104.75 (14)	TP24.8406x24.7868x1	0.2500	0.0000	0.0	75.6702	-14.61	5621.92	0.003

<b>tnxTower</b>  <b>Tower Engineering Professionals</b> 326 Tryon Road Raleigh, N.C. Phone: (919) 661-6351 FAX: (919) 661-6350	<b>Job</b> Preston / Town Hall (BU 876360)	<b>Page</b> 50 of 55
	<b>Project</b> TEP No. 25620.161151	<b>Date</b> 10:12:11 03/21/18
	<b>Client</b> Crown Castle	<b>Designed by</b> RKE

Section No.	Elevation ft	Size	L ft	L <sub>u</sub> ft	Kl/r	A in <sup>2</sup>	P <sub>u</sub> K	φP <sub>n</sub> K	Ratio $\frac{P_u}{\phi P_n}$
L15	104.75 - 103.5 (15)	TP25.1096x24.8406x0.975	1.2500	0.0000	0.0	74.6882	-14.99	5548.96	0.003
L16	103.5 - 103.25 (16)	TP25.1634x25.1096x0.75	0.2500	0.0000	0.0	58.1161	-15.07	4317.74	0.003
L17	103.25 - 98.25 (17)	TP26.2394x25.1634x0.725	5.0000	0.0000	0.0	58.7124	-16.38	4362.04	0.004
L18	98.25 - 94.83 (18)	TP26.9753x26.2394x0.7125	3.4200	0.0000	0.0	59.3927	-17.30	4412.58	0.004
L19	94.83 - 94.58 (19)	TP27.0291x26.9753x0.7	0.2500	0.0000	0.0	58.4980	-17.38	4346.11	0.004
L20	94.58 - 94.17 (20)	TP27.1173x27.0291x0.6875	0.4100	0.0000	0.0	57.6732	-17.49	4284.83	0.004
L21	94.17 - 93.82 (21)	TP27.1927x27.1173x0.775	0.3500	0.0000	0.0	64.9835	-17.59	4827.95	0.004
L22	93.82 - 93.66 (22)	TP27.2271x27.1927x0.775	0.1600	0.0000	0.0	65.0682	-17.64	4834.24	0.004
L23	93.66 - 84.91 (23)	TP29.11x27.2271x0.75	8.7500	0.0000	0.0	65.3749	-18.98	4857.03	0.004
L24	84.91 - 83.91 (24)	TP28.6922x27.58x0.8375	5.1700	0.0000	0.0	74.0442	-21.66	5501.11	0.004
L25	83.91 - 78.91 (25)	TP29.7679x28.6922x0.8125	5.0000	0.0000	0.0	74.6724	-23.32	5547.78	0.004
L26	78.91 - 73.91 (26)	TP30.8436x29.7679x0.8	5.0000	0.0000	0.0	76.2866	-25.00	5667.72	0.004
L27	73.91 - 68.91 (27)	TP31.9192x30.8436x0.775	5.0000	0.0000	0.0	76.6102	-26.72	5691.75	0.005
L28	68.91 - 65.5 (28)	TP32.6528x31.9192x0.7625	3.4100	0.0000	0.0	77.1802	-27.90	5734.10	0.005
L29	65.5 - 65.25 (29)	TP32.7066x32.6528x0.9125	0.2500	0.0000	0.0	92.0845	-28.01	6841.42	0.004
L30	65.25 - 64.5 (30)	TP32.868x32.7066x0.9125	0.7500	0.0000	0.0	92.5518	-28.29	6876.14	0.004
L31	64.5 - 64.25 (31)	TP32.9218x32.868x0.8125	0.2500	0.0000	0.0	82.8058	-28.38	6152.05	0.005
L32	64.25 - 59.25 (32)	TP33.9974x32.9218x0.8	5.0000	0.0000	0.0	84.2949	-30.21	6262.69	0.005
L33	59.25 - 58.58 (33)	TP34.1416x33.9974x0.7875	0.6700	0.0000	0.0	83.3693	-30.47	6193.92	0.005
L34	58.58 - 58.33 (34)	TP34.1953x34.1416x0.85	0.2500	0.0000	0.0	89.9624	-30.57	6683.76	0.005
L35	58.33 - 57.25 (35)	TP34.4277x34.1953x0.8375	1.0800	0.0000	0.0	89.2903	-30.98	6633.82	0.005
L36	57.25 - 57 (36)	TP34.4815x34.4277x0.85	0.2500	0.0000	0.0	90.7344	-31.09	6741.11	0.005
L37	57 - 52 (37)	TP35.5571x34.4815x0.8375	5.0000	0.0000	0.0	92.2926	-33.07	6856.88	0.005
L38	52 - 44.41 (38)	TP37.19x35.5571x0.825	7.5900	0.0000	0.0	92.3111	-34.12	6858.25	0.005
L39	44.41 - 43.41 (39)	TP36.6578x35.33x0.875	6.1700	0.0000	0.0	99.3779	-38.63	7383.28	0.005
L40	43.41 - 38.41 (40)	TP37.7339x36.6578x0.8625	5.0000	0.0000	0.0	100.938 0	-40.81	7499.20	0.005
L41	38.41 - 34.5 (41)	TP38.5753x37.7339x0.85	3.9100	0.0000	0.0	101.779 0	-42.54	7561.68	0.006
L42	34.5 - 34.25 (42)	TP38.6291x38.5753x1.025	0.2500	0.0000	0.0	122.164 0	-42.56	9076.20	0.005
L43	34.25 - 33.5 (43)	TP38.7905x38.6291x1.0125	0.7500	0.0000	0.0	120.888 0	-42.69	8981.35	0.005
L44	33.5 - 33.25 (44)	TP38.8443x38.7905x0.8125	0.2500	0.0000	0.0	97.9406	-43.09	7276.50	0.006
L45	33.25 - 29.5 (45)	TP39.6514x38.8443x0.8	3.7500	0.0000	0.0	96.6022	-43.22	7177.06	0.006
L46	29.5 - 29.25	TP39.7052x39.6514x0.8875	0.2500	0.0000	0.0	109.195	-44.96	8112.64	0.006

<b>tnxTower</b>  <b>Tower Engineering Professionals</b> 326 Tryon Road Raleigh, N.C. Phone: (919) 661-6351 FAX: (919) 661-6350	<b>Job</b> Preston / Town Hall (BU 876360)	<b>Page</b> 51 of 55
	<b>Project</b> TEP No. 25620.161151	<b>Date</b> 10:12:11 03/21/18
	<b>Client</b> Crown Castle	<b>Designed by</b> RKE

Section No.	Elevation ft	Size	L ft	L <sub>u</sub> ft	Kl/r	A in <sup>2</sup>	P <sub>u</sub> K	φP <sub>n</sub> K	Ratio $\frac{P_u}{\phi P_n}$
L47	29.25 - 28.5 (46)	TP39.8666x39.7052x0.8875	0.7500	0.0000	0.0	109.346	-45.09	8123.90	0.006
L48	28.5 - 28.25 (47)	TP39.9204x39.8666x0.9	0.2500	0.0000	0.0	111.312	-45.45	8269.92	0.005
L49	28.25 - 27.48 (48)	TP40.0861x39.9204x0.9	0.7700	0.0000	0.0	111.466	-45.59	8281.34	0.006
L50	27.48 - 27.23 (49)	TP40.1399x40.0861x0.9	0.2500	0.0000	0.0	111.939	-45.96	8316.51	0.006
L51	27.23 - 22.23 (50)	TP41.2159x40.1399x0.875	5.0000	0.0000	0.0	109.048	-46.09	8101.75	0.006
L52	22.23 - 17.23 (51)	TP42.292x41.2159x0.875	5.0000	0.0000	0.0	112.037	-48.57	8323.78	0.006
L53	17.23 - 12.23 (52)	TP43.368x42.292x0.85	5.0000	0.0000	0.0	111.806	-51.07	8306.65	0.006
L54	12.23 - 7.23 (53)	TP44.444x43.368x0.8375	5.0000	0.0000	0.0	113.056	-53.60	8399.47	0.006
L55	7.23 - 6.9 (54)	TP44.5151x44.444x0.8625	0.3300	0.0000	0.0	119.308	-56.16	8863.97	0.006
L56	6.9 - 6.55 (55)	TP44.5904x44.5151x0.7875	0.3500	0.0000	0.0	109.298	-56.34	8120.31	0.007
L57	6.55 - 6.33 (56)	TP44.6377x44.5904x0.7875	0.2200	0.0000	0.0	109.486	-56.52	8134.29	0.007
L58	6.33 - 3.25 (57)	TP45.3006x44.6377x0.775	3.0800	0.0000	0.0	107.896	-56.64	8016.11	0.007
L59	3.25 - 3 (58)	TP45.3544x45.3006x0.975	0.2500	0.0000	0.0	137.172	-58.24	10191.20	0.006
L60	3 - 2.75 (59)	TP45.4082x45.3544x0.875	0.2500	0.0000	0.0	123.530	-58.40	9177.69	0.006
L61	2.75 - 2.5 (60)	TP45.462x45.4082x0.875	0.2500	0.0000	0.0	123.680	-58.53	9188.79	0.006
L62	2.5 - 2.25 (61)	TP45.5158x45.462x0.7625	0.2500	0.0000	0.0	108.181	-58.67	8037.28	0.007
L63	2.25 - 2 (62)	TP45.5696x45.5158x0.75	0.2500	0.0000	0.0	106.565	-58.80	7917.24	0.007
L64	2 - 0 (63)	TP46x45.5696x0.75	2.0000	0.0000	0.0	106.693	-58.93	7926.76	0.007

### Pole Bending Design Data

Section No.	Elevation ft	Size	M <sub>ux</sub> kip-ft	φM <sub>ux</sub> kip-ft	Ratio $\frac{M_{ux}}{\phi M_{ux}}$	M <sub>uy</sub> kip-ft	φM <sub>uy</sub> kip-ft	Ratio $\frac{M_{uy}}{\phi M_{uy}}$
L1	147 - 142 (1)	TP17.3259x16.25x0.1875	52.67	266.24	0.198	0.00	266.24	0.000
L2	142 - 137 (2)	TP18.4017x17.3259x0.1875	93.41	300.91	0.310	0.00	300.91	0.000
L3	137 - 132 (3)	TP19.4776x18.4017x0.1875	171.55	335.31	0.512	0.00	335.31	0.000
L4	132 - 127 (4)	TP20.5534x19.4776x0.1875	259.42	368.53	0.704	0.00	368.53	0.000
L5	127 - 120.37 (5)	TP21.98x20.5534x0.1875	330.94	391.51	0.845	0.00	391.51	0.000
L6	120.37 - 118.62 (6)	TP21.8559x20.78x0.25	439.80	563.83	0.780	0.00	563.83	0.000
L7	118.62 - 113.62 (7)	TP22.9319x21.8559x0.25	564.97	621.72	0.909	0.00	621.72	0.000
L8	113.62 - 112.41 (8)	TP23.1923x22.9319x0.25	595.84	636.16	0.937	0.00	636.16	0.000
L9	112.41 -	TP23.2461x23.1923x0.5375	602.23	1323.30	0.455	0.00	1323.30	0.000

<b>tnxTower</b>  <b>Tower Engineering Professionals</b> 326 Tryon Road Raleigh, N.C. Phone: (919) 661-6351 FAX: (919) 661-6350	<b>Job</b> Preston / Town Hall (BU 876360)	<b>Page</b> 52 of 55
	<b>Project</b> TEP No. 25620.161151	<b>Date</b> 10:12:11 03/21/18
	<b>Client</b> Crown Castle	<b>Designed by</b> RKE

Section No.	Elevation ft	Size	$M_{ux}$ kip-ft	$\phi M_{ux}$ kip-ft	Ratio $\frac{M_{ux}}{\phi M_{ux}}$	$M_{uy}$ kip-ft	$\phi M_{uy}$ kip-ft	Ratio $\frac{M_{uy}}{\phi M_{uy}}$
L10	112.16 (9) 112.16 - 110.5 (10)	TP23.6033x23.2461x0.525	644.78	1336.16	0.483	0.00	1336.16	0.000
L11	110.5 - 110.25 (11)	TP23.6571x23.6033x0.75	651.21	1862.38	0.350	0.00	1862.38	0.000
L12	110.25 - 105.25 (12)	TP24.733x23.6571x0.725	780.98	1982.39	0.394	0.00	1982.39	0.000
L13	105.25 - 105 (13)	TP24.7868x24.733x0.725	787.53	1991.42	0.395	0.00	1991.42	0.000
L14	105 - 104.75 (14)	TP24.8406x24.7868x1	794.08	2665.93	0.298	0.00	2665.93	0.000
L15	104.75 - 103.5 (15)	TP25.1096x24.8406x0.975	826.94	2667.75	0.310	0.00	2667.75	0.000
L16	103.5 - 103.25 (16)	TP25.1634x25.1096x0.75	833.52	2119.52	0.393	0.00	2119.52	0.000
L17	103.25 - 98.25 (17)	TP26.2394x25.1634x0.725	966.47	2242.84	0.431	0.00	2242.84	0.000
L18	98.25 - 94.83 (18)	TP26.9753x26.2394x0.7125	1058.68	2338.31	0.453	0.00	2338.31	0.000
L19	94.83 - 94.58 (19)	TP27.0291x26.9753x0.7	1065.46	2310.12	0.461	0.00	2310.12	0.000
L20	94.58 - 94.17 (20)	TP27.1173x27.0291x0.6875	1076.59	2287.54	0.471	0.00	2287.54	0.000
L21	94.17 - 93.82 (21)	TP27.1927x27.1173x0.775	1086.11	2567.98	0.423	0.00	2567.98	0.000
L22	93.82 - 93.66 (22)	TP27.2271x27.1927x0.775	1090.46	2574.78	0.424	0.00	2574.78	0.000
L23	93.66 - 84.91 (23)	TP29.11x27.2271x0.75	1216.06	2690.94	0.452	0.00	2690.94	0.000
L24	84.91 - 83.91 (24)	TP28.6922x27.58x0.8375	1360.50	3083.03	0.441	0.00	3083.03	0.000
L25	83.91 - 78.91 (25)	TP29.7679x28.6922x0.8125	1502.72	3238.34	0.464	0.00	3238.34	0.000
L26	78.91 - 73.91 (26)	TP30.8436x29.7679x0.8	1647.20	3437.47	0.479	0.00	3437.47	0.000
L27	73.91 - 68.91 (27)	TP31.9192x30.8436x0.775	1793.89	3584.61	0.500	0.00	3584.61	0.000
L28	68.91 - 65.5 (28)	TP32.6528x31.9192x0.7625	1895.20	3701.31	0.512	0.00	3701.31	0.000
L29	65.5 - 65.25 (29)	TP32.7066x32.6528x0.9125	1902.67	4382.25	0.434	0.00	4382.25	0.000
L30	65.25 - 64.5 (30)	TP32.868x32.7066x0.9125	1925.10	4427.46	0.435	0.00	4427.46	0.000
L31	64.5 - 64.25 (31)	TP32.9218x32.868x0.8125	1932.59	3992.92	0.484	0.00	3992.92	0.000
L32	64.25 - 59.25 (32)	TP33.9974x32.9218x0.8	2084.34	4207.43	0.495	0.00	4207.43	0.000
L33	59.25 - 58.58 (33)	TP34.1416x33.9974x0.7875	2104.85	4182.85	0.503	0.00	4182.85	0.000
L34	58.58 - 58.33 (34)	TP34.1953x34.1416x0.85	2112.51	4504.19	0.469	0.00	4504.19	0.000
L35	58.33 - 57.25 (35)	TP34.4277x34.1953x0.8375	2145.68	4505.82	0.476	0.00	4505.82	0.000
L36	57.25 - 57 (36)	TP34.4815x34.4277x0.85	2153.38	4582.79	0.470	0.00	4582.79	0.000
L37	57 - 52 (37)	TP35.5571x34.4815x0.8375	2308.46	4817.73	0.479	0.00	4817.73	0.000
L38	52 - 44.41 (38)	TP37.19x35.5571x0.825	2384.23	4896.13	0.487	0.00	4896.13	0.000
L39	44.41 - 43.41 (39)	TP36.6578x35.33x0.875	2581.32	5344.72	0.483	0.00	5344.72	0.000
L40	43.41 - 38.41 (40)	TP37.7339x36.6578x0.8625	2743.79	5599.57	0.490	0.00	5599.57	0.000

<b>tnxTower</b>  <b>Tower Engineering Professionals</b> 326 Tryon Road Raleigh, N.C. Phone: (919) 661-6351 FAX: (919) 661-6350	<b>Job</b> Preston / Town Hall (BU 876360)	<b>Page</b> 53 of 55
	<b>Project</b> TEP No. 25620.161151	<b>Date</b> 10:12:11 03/21/18
	<b>Client</b> Crown Castle	<b>Designed by</b> RKE

Section No.	Elevation ft	Size	$M_{ux}$ kip-ft	$\phi M_{ux}$ kip-ft	Ratio $\frac{M_{ux}}{\phi M_{ux}}$	$M_{uy}$ kip-ft	$\phi M_{uy}$ kip-ft	Ratio $\frac{M_{uy}}{\phi M_{uy}}$
L41	38.41 - 34.5 (41)	TP38.5753x37.7339x0.85	2872.33	5781.86	0.497	0.00	5781.86	0.000
L42	34.5 - 34.25 (42)	TP38.6291x38.5753x1.025	2872.33	6875.67	0.418	0.00	6875.67	0.000
L43	34.25 - 33.5 (43)	TP38.7905x38.6291x1.0125	2880.60	6818.34	0.422	0.00	6818.34	0.000
L44	33.5 - 33.25 (44)	TP38.8443x38.7905x0.8125	2905.43	5607.31	0.518	0.00	5607.31	0.000
L45	33.25 - 29.5 (45)	TP39.6514x38.8443x0.8	2913.71	5542.32	0.526	0.00	5542.32	0.000
L46	29.5 - 29.25 (46)	TP39.7052x39.6514x0.8875	3038.59	6371.63	0.477	0.00	6371.63	0.000
L47	29.25 - 28.5 (47)	TP39.8666x39.7052x0.8875	3046.96	6389.52	0.477	0.00	6389.52	0.000
L48	28.5 - 28.25 (48)	TP39.9204x39.8666x0.9	3072.09	6527.84	0.471	0.00	6527.84	0.000
L49	28.25 - 27.48 (49)	TP40.0861x39.9204x0.9	3080.47	6546.08	0.471	0.00	6546.08	0.000
L50	27.48 - 27.23 (50)	TP40.1399x40.0861x0.9	3106.34	6602.42	0.470	0.00	6602.42	0.000
L51	27.23 - 22.23 (51)	TP41.2159x40.1399x0.875	3114.75	6449.17	0.483	0.00	6449.17	0.000
L52	22.23 - 17.23 (52)	TP42.292x41.2159x0.875	3283.99	6811.45	0.482	0.00	6811.45	0.000
L53	17.23 - 12.23 (53)	TP43.368x42.292x0.85	3455.18	6991.03	0.494	0.00	6991.03	0.000
L54	12.23 - 7.23 (54)	TP44.444x43.368x0.8375	3628.14	7260.66	0.500	0.00	7260.66	0.000
L55	7.23 - 6.9 (55)	TP44.5151x44.444x0.8625	3802.78	7850.77	0.484	0.00	7850.77	0.000
L56	6.9 - 6.55 (56)	TP44.5904x44.5151x0.7875	3814.38	7228.83	0.528	0.00	7228.83	0.000
L57	6.55 - 6.33 (57)	TP44.6377x44.5904x0.7875	3826.67	7253.98	0.528	0.00	7253.98	0.000
L58	6.33 - 3.25 (58)	TP45.3006x44.6377x0.775	3834.40	7160.54	0.535	0.00	7160.54	0.000
L59	3.25 - 3 (59)	TP45.3544x45.3006x0.975	3942.97	9160.58	0.430	0.00	9160.58	0.000
L60	3 - 2.75 (60)	TP45.4082x45.3544x0.875	3951.80	8297.05	0.476	0.00	8297.05	0.000
L61	2.75 - 2.5 (61)	TP45.462x45.4082x0.875	3960.64	8317.33	0.476	0.00	8317.33	0.000
L62	2.5 - 2.25 (62)	TP45.5158x45.462x0.7625	3969.49	7320.79	0.542	0.00	7320.79	0.000
L63	2.25 - 2 (63)	TP45.5696x45.5158x0.75	3978.34	7224.32	0.551	0.00	7224.32	0.000
L64	2 - 0 (64)	TP46x45.5696x0.75	3987.19	7241.83	0.551	0.00	7241.83	0.000

### Pole Shear Design Data

Section No.	Elevation ft	Size	Actual $V_u$ K	$\phi V_n$ K	Ratio $\frac{V_u}{\phi V_n}$	Actual $T_u$ kip-ft	$\phi T_n$ kip-ft	Ratio $\frac{T_u}{\phi T_n}$
L1	147 - 142 (1)	TP17.3259x16.25x0.1875	7.98	378.88	0.021	0.00	533.13	0.000
L2	142 - 137 (2)	TP18.4017x17.3259x0.1875	8.32	402.67	0.021	0.00	602.55	0.000
L3	137 - 132 (3)	TP19.4776x18.4017x0.1875	15.20	423.44	0.036	2.58	671.44	0.004
L4	132 - 127 (4)	TP20.5534x19.4776x0.1875	21.06	440.58	0.048	3.08	737.95	0.004
L5	127 - 120.37 (5)	TP21.98x20.5534x0.1875	21.27	451.77	0.047	3.08	783.98	0.004
L6	120.37 - 118.62 (6)	TP21.8559x20.78x0.25	22.66	636.87	0.036	0.90	1129.04	0.001
L7	118.62 - 113.62 (7)	TP22.9319x21.8559x0.25	25.49	668.58	0.038	1.15	1244.97	0.001
L8	113.62 - 112.41 (8)	TP23.1923x22.9319x0.25	25.56	676.26	0.038	1.15	1273.88	0.001




<b>tnxTower</b>  <b>Tower Engineering Professionals</b> 326 Tryon Road Raleigh, N.C. Phone: (919) 661-6351 FAX: (919) 661-6350	<b>Job</b> Preston / Town Hall (BU 876360)	<b>Page</b> 54 of 55
	<b>Project</b> TEP No. 25620.161151	<b>Date</b> 10:12:11 03/21/18
	<b>Client</b> Crown Castle	<b>Designed by</b> RKE

Section No.	Elevation ft	Size	Actual $V_u$ K	$\phi V_n$ K	Ratio $\frac{V_u}{\phi V_n}$	Actual $T_u$ kip-ft	$\phi T_n$ kip-ft	Ratio $\frac{T_u}{\phi T_n}$
L9	112.41 - 112.16 (9)	TP23.2461x23.1923x0.5375	25.57	1439.15	0.018	1.15	2649.83	0.000
L10	112.16 - 110.5 (10)	TP23.6033x23.2461x0.525	25.72	1428.56	0.018	1.15	2675.57	0.000
L11	110.5 - 110.25 (11)	TP23.6571x23.6033x0.75	25.73	2025.67	0.013	1.15	3729.32	0.000
L12	110.25 - 105.25 (12)	TP24.733x23.6571x0.725	26.18	2052.25	0.013	1.15	3969.63	0.000
L13	105.25 - 105 (13)	TP24.7868x24.733x0.725	26.20	2056.85	0.013	1.15	3987.71	0.000
L14	105 - 104.75 (14)	TP24.8406x24.7868x1	26.23	2810.96	0.009	1.15	5338.39	0.000
L15	104.75 - 103.5 (15)	TP25.1096x24.8406x0.975	26.35	2774.48	0.009	1.15	5342.02	0.000
L16	103.5 - 103.25 (16)	TP25.1634x25.1096x0.75	26.37	2158.87	0.012	1.15	4244.22	0.000
L17	103.25 - 98.25 (17)	TP26.2394x25.1634x0.725	26.82	2181.02	0.012	1.14	4491.17	0.000
L18	98.25 - 94.83 (18)	TP26.9753x26.2394x0.7125	27.12	2206.29	0.012	1.14	4682.33	0.000
L19	94.83 - 94.58 (19)	TP27.0291x26.9753x0.7	27.14	2173.06	0.012	1.14	4625.88	0.000
L20	94.58 - 94.17 (20)	TP27.1173x27.0291x0.6875	27.17	2142.42	0.013	1.14	4580.67	0.000
L21	94.17 - 93.82 (21)	TP27.1927x27.1173x0.775	27.20	2413.97	0.011	1.14	5142.24	0.000
L22	93.82 - 93.66 (22)	TP27.2271x27.1927x0.775	27.22	2417.12	0.011	1.14	5155.85	0.000
L23	93.66 - 84.91 (23)	TP29.11x27.2271x0.75	27.64	2428.51	0.011	1.14	5388.46	0.000
L24	84.91 - 83.91 (24)	TP28.6922x27.58x0.8375	28.23	2750.56	0.010	1.14	6173.58	0.000
L25	83.91 - 78.91 (25)	TP29.7679x28.6922x0.8125	28.68	2773.89	0.010	1.14	6484.61	0.000
L26	78.91 - 73.91 (26)	TP30.8436x29.7679x0.8	29.13	2833.86	0.010	1.14	6883.35	0.000
L27	73.91 - 68.91 (27)	TP31.9192x30.8436x0.775	29.57	2845.88	0.010	1.14	7177.97	0.000
L28	68.91 - 65.5 (28)	TP32.6528x31.9192x0.7625	29.87	2867.05	0.010	1.14	7411.67	0.000
L29	65.5 - 65.25 (29)	TP32.7066x32.6528x0.9125	29.88	3420.71	0.009	1.14	8775.25	0.000
L30	65.25 - 64.5 (30)	TP32.868x32.7066x0.9125	29.96	3438.07	0.009	1.14	8865.75	0.000
L31	64.5 - 64.25 (31)	TP32.9218x32.868x0.8125	30.12	3076.03	0.010	3.99	7995.60	0.000
L32	64.25 - 59.25 (32)	TP33.9974x32.9218x0.8	30.59	3131.34	0.010	3.99	8425.17	0.000
L33	59.25 - 58.58 (33)	TP34.1416x33.9974x0.7875	30.65	3096.96	0.010	3.99	8375.92	0.000
L34	58.58 - 58.33 (34)	TP34.1953x34.1416x0.85	30.67	3341.88	0.009	3.99	9019.42	0.000
L35	58.33 - 57.25 (35)	TP34.4277x34.1953x0.8375	30.78	3316.91	0.009	3.99	9022.67	0.000
L36	57.25 - 57 (36)	TP34.4815x34.4277x0.85	30.79	3370.55	0.009	3.99	9176.75	0.000
L37	57 - 52 (37)	TP35.5571x34.4815x0.8375	31.26	3428.44	0.009	3.99	9647.25	0.000
L38	52 - 44.41 (38)	TP37.19x35.5571x0.825	31.54	3403.81	0.009	4.18	9804.25	0.000
L39	44.41 - 43.41 (39)	TP36.6578x35.33x0.875	32.29	3691.64	0.009	4.18	10702.50	0.000
L40	43.41 - 38.41	TP37.7339x36.6578x0.8625	32.73	3749.60	0.009	4.18	11212.83	0.000

<b>tnxTower</b>  <b>Tower Engineering Professionals</b> 326 Tryon Road Raleigh, N.C. Phone: (919) 661-6351 FAX: (919) 661-6350	<b>Job</b>	Preston / Town Hall (BU 876360)	<b>Page</b>	55 of 55
	<b>Project</b>	TEP No. 25620.161151	<b>Date</b>	10:12:11 03/21/18
	<b>Client</b>	Crown Castle	<b>Designed by</b>	RKE

Section No.	Elevation ft	Size	Actual $V_n$ K	$\phi V_n$ K	Ratio $\frac{V_u}{\phi V_n}$	Actual $T_u$ kip-ft	$\phi T_n$ kip-ft	Ratio $\frac{T_u}{\phi T_n}$
L41	(40) 38.41 - 34.5	TP38.5753x37.7339x0.85	33.06	3780.84	0.009	4.18	11577.83	0.000
L42	(41) 34.5 - 34.25	TP38.6291x38.5753x1.025	33.07	4544.60	0.007	4.18	13768.17	0.000
L43	(42) 34.25 - 33.5	TP38.7905x38.6291x1.0125	33.14	4509.94	0.007	4.18	13653.33	0.000
L44	(43) 33.5 - 33.25	TP38.8443x38.7905x0.8125	33.15	3643.40	0.009	4.18	11228.33	0.000
L45	(44) 33.25 - 29.5	TP39.6514x38.8443x0.8	33.27	3613.90	0.009	4.18	11098.17	0.000
L46	(45) 29.5 - 29.25	TP39.7052x39.6514x0.8875	33.48	4061.95	0.008	4.18	12758.83	0.000
L47	(46) 29.25 - 28.5	TP39.8666x39.7052x0.8875	33.55	4078.84	0.008	4.18	12794.67	0.000
L48	(47) 28.5 - 28.25	TP39.9204x39.8666x0.9	33.56	4140.67	0.008	4.18	13071.67	0.000
L49	(48) 28.25 - 27.48	TP40.0861x39.9204x0.9	33.64	4158.25	0.008	4.18	13108.17	0.000
L50	(49) 27.48 - 27.23	TP40.1399x40.0861x0.9	33.65	4163.96	0.008	4.18	13221.00	0.000
L51	(50) 27.23 - 22.23	TP41.2159x40.1399x0.875	33.74	4073.08	0.008	4.18	12914.08	0.000
L52	(51) 22.23 - 17.23	TP42.292x41.2159x0.875	34.14	4184.09	0.008	4.18	13639.58	0.000
L53	(52) 17.23 - 12.23	TP43.368x42.292x0.85	34.51	4174.89	0.008	4.18	13999.17	0.000
L54	(53) 12.23 - 7.23	TP44.444x43.368x0.8375	34.85	4220.99	0.008	4.18	14539.08	0.000
L55	(54) 7.23 - 6.9 (55)	TP44.5151x44.444x0.8625	35.12	4439.21	0.008	4.18	15720.75	0.000
L56	6.9 - 6.55 (56)	TP44.5904x44.5151x0.7875	35.15	4067.15	0.009	4.18	14475.33	0.000
L57	6.55 - 6.33 (57)	TP44.6377x44.5904x0.7875	35.16	4071.54	0.009	4.18	14525.75	0.000
L58	6.33 - 3.25 (58)	TP45.3006x44.6377x0.775	35.24	4028.25	0.009	4.18	14338.58	0.000
L59	3.25 - 3 (59)	TP45.3544x45.3006x0.975	35.36	5101.79	0.007	4.18	18343.58	0.000
L60	3 - 2.75 (60)	TP45.4082x45.3544x0.875	35.38	4594.39	0.008	4.18	16614.42	0.000
L61	2.75 - 2.5 (61)	TP45.462x45.4082x0.875	35.39	4599.95	0.008	4.18	16655.00	0.000
L62	2.5 - 2.25 (62)	TP45.5158x45.462x0.7625	35.41	4023.47	0.009	4.18	14659.50	0.000
L63	2.25 - 2 (63)	TP45.5696x45.5158x0.75	35.43	3963.38	0.009	4.18	14466.33	0.000
L64	2 - 0 (64)	TP46x45.5696x0.75	35.50	3982.41	0.009	4.18	14501.42	0.000

**APPENDIX B**  
**BASE LEVEL DRAWING**



BUSINESS UNIT: 876360 TOWER ID: C\_BASELEVEL

**APPENDIX C**  
**ADDITIONAL CALCULATIONS**

## Reinforcement Configuration

	Bottom Effective Elevation (ft)	Top Effective Elevation (ft)	Type	Model	Number	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18		
1	0	27.5	plate	L1.25"x5" (BAR 1 & 14)	2		0																		
2	0	6.92	plate	L1.25"x5" (BAR 1 & 14)	2						0														
3	6.58	27.5	plate	PL 1.25"x5" (BAR 1B)	1								0												
4	27.5	57.25	plate	PL 1.25"x5" (BAR 2)	3		0						0												
5	57.25	87.25	plate	PL 1.25"x4.75"	3		0						0												
6	87.25	105	plate	PL 1.25"x4.25"	3		0						0												
7	7	29.5	channel	MP3-03 (1.25")	2										0										
8	0	3.25	plate	TS 1.0"x6" (TS1a)	2	-3						3												0	
9	0	3.25	plate	TS 1.0"x6" (TS1b)	1																	1			
10	2.5	28.5	plate	CCI-AFP-045100	2	0						0													
11	2.25	28.5	plate	CCI-CFP-045100	1																	0			
12	27.58	58.58	plate	CCI-AFP-045100	1													0							
13	28.5	58.58	plate	CCI-AFP-045100	2	0						0													
14	58.58	94.17	plate	CCI-AFP-040075	3	0						0													
15	103.5	110.5	plate	CCI-SFP-045100	3	0						0													
16	0	3.25	plate	(TS)1.25x6.00 (65ksi)	2			c																	
17	3	34.5	plate	CCI-CFP-045125	4			1																0	
18	33.5	65.5	plate	CCI-SFP-045100	4			1							0								0		
19	65.5	93.91	plate	CCI-SFP-045100	2							0													
20	64.5	94.83	plate	CCI-SFP-045100	1																			0	
21	93.91	112.41	plate	CCI-CFP-045125	2								0												
22	94.83	112.41	plate	CCI-CFP-045125	1																			0	
23																									

## Reinforcement Details

	B (in)	H (in)	Gross Area (in <sup>2</sup> )	Pole Face to Centroid (in)	Bottom Termination Length (in)	Top Termination Length (in)	L <sub>u</sub> (in)	Net Area (in <sup>2</sup> )	Bolt Hole Size (in)	Reinforcement Material
1	5	1.25	6.25	0.625	n/a	27,000	18,000	4.647	1.2200	A572-65
2	5	1.25	6.25	0.625	n/a	27,000	18,000	4.647	1.2200	A572-65
3	5	1.25	6.25	0.625	27,000	27,000	18,000	4.647	1.2200	A572-65
4	5	1.25	6.25	0.625	n/a	27,000	18,000	4.647	1.2200	A572-65
5	4.75	1.25	5.9375	0.625	n/a	24,000	18,000	4.334	1.2200	A572-65
6	4.25	1.25	5.3125	0.625	n/a	18,000	21,000	3.709	1.2200	A572-65
7	4.06	1.57	2.92	0.59	14,000	14,000	18,000	2.526	1.2500	A572-65
8	1	5.25	5.25	3.375	n/a	n/a	0.750	5.250	0.0000	A572-65

113.02	5		18	21.030	22.732	0.25	A572-6
112.41	1.21		18	22.932	23.192	0.25	A572-6
112.16	0.25		18	23.192	23.246	0.5375	A572-6
110.5	1.66		18	23.246	23.603	0.525	A572-6
110.25	0.25		18	23.603	23.657	0.75	A572-6
105.25	5		18	23.657	24.733	0.725	A572-6
105	0.25		18	24.733	24.787	0.725	A572-6
104.75	0.25		18	24.787	24.841	1	A572-6
103.5	1.25		18	24.841	25.110	0.975	A572-6
103.25	0.25		18	25.110	25.163	0.75	A572-6
98.25	5		18	25.163	26.239	0.725	A572-6
94.83	3.42		18	26.239	26.975	0.7125	A572-6
94.58	0.25		18	26.975	27.029	0.7	A572-6
94.17	0.41		18	27.029	27.117	0.6875	A572-6
93.82	0.35		18	27.117	27.193	0.775	A572-6
93.66	0.16		18	27.193	27.227	0.775	A572-6
89.08	8.75	4.17	18	27.227	29.110	0.75	A572-6
83.91	5.17		18	27.580	28.692	0.8375	A572-6
78.91	5		18	28.692	29.768	0.8125	A572-6
73.91	5		18	29.768	30.844	0.8	A572-6
68.91	5		18	30.844	31.919	0.775	A572-6
65.5	3.41		18	31.919	32.653	0.7625	A572-6
65.25	0.25		18	32.653	32.707	0.9125	A572-6
64.5	0.75		18	32.707	32.868	0.9125	A572-6
64.25	0.25		18	32.868	32.922	0.8125	A572-6
59.25	5		18	32.922	33.997	0.8	A572-6
58.58	0.67		18	33.997	34.142	0.7875	A572-6
58.33	0.25		18	34.142	34.195	0.85	A572-6
57.25	1.08		18	34.195	34.428	0.8375	A572-6
57	0.25		18	34.428	34.481	0.85	A572-6
52	5		18	34.481	35.557	0.8375	A572-6
49.58	7.59	5.17	18	35.557	37.190	0.825	A572-6
43.41	6.17		18	35.330	36.658	0.875	A572-6
38.41	5		18	36.658	37.734	0.8625	A572-6
34.5	3.91		18	37.734	38.575	0.85	A572-6
34.25	0.25		18	38.575	38.629	1.025	A572-6
33.5	0.75		18	38.629	38.791	1.0125	A572-6
33.25	0.25		18	38.791	38.844	0.8125	A572-6
29.5	3.75		18	38.844	39.651	0.8	A572-6
29.25	0.25		18	39.651	39.705	0.8875	A572-6
28.5	0.75		18	39.705	39.867	0.8875	A572-6
28.25	0.25		18	39.867	39.920	0.9	A572-6
27.48	0.77		18	39.920	40.086	0.9	A572-6
27.23	0.25		18	40.086	40.140	0.9	A572-6
22.23	5		18	40.140	41.216	0.875	A572-6
17.23	5		18	41.216	42.292	0.875	A572-6
12.23	5		18	42.292	43.368	0.85	A572-6
7.23	5		18	43.368	44.444	0.8375	A572-6
5.9	0.33		18	44.444	44.515	0.8625	A572-6
6.55	0.35		18	44.515	44.590	0.7875	A572-6
5.22	0.22		18	44.590	44.628	0.7875	A572-6

7	116.02	-	115.02	12.57	504.57	25.45
8	113.62	-	112.41	12.76	595.84	25.56
9	112.41	-	112.16	12.84	602.23	25.57
10	112.16	-	110.5	13.15	644.78	25.72
11	110.5	-	110.25	13.23	651.21	25.73
12	110.25	-	105.25	14.46	780.98	26.18
13	105.25	-	105	14.53	787.53	26.20
14	105	-	104.75	14.61	794.08	26.23
15	104.75	-	103.5	14.99	826.94	26.35
16	103.5	-	103.25	15.07	833.53	26.37
17	103.25	-	98.25	16.38	966.47	26.82
18	98.25	-	94.83	17.30	#####	27.12
19	94.83	-	94.58	17.38	#####	27.14
20	94.58	-	94.17	17.49	#####	27.17
21	94.17	-	93.82	17.59	#####	27.20
22	93.82	-	93.66	17.64	#####	27.22
23	93.66	-	89.08	18.98	#####	27.64
24	89.08	-	83.91	21.66	#####	28.23
25	83.91	-	78.91	23.32	#####	28.68
26	78.91	-	73.91	25.00	#####	29.13
27	73.91	-	68.91	26.72	#####	29.57
28	68.91	-	65.5	27.90	#####	29.87
29	65.5	-	65.25	28.01	#####	29.88
30	65.25	-	64.5	28.29	#####	29.96
31	64.5	-	64.25	28.39	#####	29.98
32	64.25	-	59.25	30.21	#####	30.59
33	59.25	-	58.58	30.47	#####	30.65
34	58.58	-	58.33	30.57	#####	30.67
35	58.33	-	57.25	30.98	#####	30.78
36	57.25	-	57	31.09	#####	30.79
37	57	-	52	33.07	#####	31.26
38	52	-	49.58	34.12	#####	31.54
39	49.58	-	43.41	38.63	#####	32.29
40	43.41	-	38.41	40.81	#####	32.73
41	38.41	-	34.5	42.54	#####	33.06
42	34.5	-	34.25	42.68	#####	33.07
43	34.25	-	33.5	43.08	#####	33.14
44	33.5	-	33.25	43.20	#####	33.15
45	33.25	-	29.5	44.94	#####	33.47
46	29.5	-	29.25	45.08	#####	33.48
47	29.25	-	28.5	45.44	#####	33.55
48	28.5	-	28.25	45.57	#####	33.56
49	28.25	-	27.48	45.95	#####	33.64
50	27.48	-	27.23	46.08	#####	33.65
51	27.23	-	22.23	48.55	#####	34.07
52	22.23	-	17.23	51.05	#####	34.44
53	17.23	-	12.23	53.58	#####	34.78
54	12.23	-	7.23	56.14	#####	35.11
55	7.23	-	6.9	56.33	#####	35.12
56	6.9	-	6.55	56.51	#####	35.15
57	6.55	-	6.22	56.62	#####	35.16



12.41 - 112.16	Pole + Reinf.	TP23.246x23.192x0.5375	Reinf. 21 Tension Rupture	82.4%	Pass
112.16 - 110.5	Pole + Reinf.	TP23.603x23.246x0.525	Reinf. 21 Tension Rupture	86.2%	Pass
110.5 - 110.25	Pole + Reinf.	TP23.657x23.603x0.75	Reinf. 21 Tension Rupture	62.1%	Pass
10.25 - 105.25	Pole + Reinf.	TP24.733x23.657x0.725	Reinf. 21 Tension Rupture	70.1%	Pass
105.25 - 105	Pole + Reinf.	TP24.787x24.733x0.725	Reinf. 21 Tension Rupture	70.5%	Pass
105 - 104.75	Pole + Reinf.	TP24.841x24.787x1	Reinf. 6 Tension Rupture	55.2%	Pass
104.75 - 103.5	Pole + Reinf.	TP25.11x24.841x0.975	Reinf. 6 Tension Rupture	56.7%	Pass
103.5 - 103.25	Pole + Reinf.	TP25.163x25.11x0.75	Reinf. 6 Tension Rupture	72.0%	Pass
103.25 - 98.25	Pole + Reinf.	TP26.239x25.163x0.725	Reinf. 6 Tension Rupture	78.9%	Pass
98.25 - 94.83	Pole + Reinf.	TP26.975x26.239x0.7125	Reinf. 6 Tension Rupture	83.2%	Pass
94.83 - 94.58	Pole + Reinf.	TP27.029x26.975x0.7	Reinf. 6 Tension Rupture	87.2%	Pass
94.58 - 94.17	Pole + Reinf.	TP27.117x27.029x0.6875	Reinf. 6 Tension Rupture	87.7%	Pass
94.17 - 93.82	Pole + Reinf.	TP27.193x27.117x0.775	Reinf. 14 Tension Rupture	77.2%	Pass
93.82 - 93.66	Pole + Reinf.	TP27.227x27.193x0.775	Reinf. 14 Tension Rupture	77.3%	Pass
93.66 - 89.08	Pole + Reinf.	TP29.11x27.227x0.75	Reinf. 14 Tension Rupture	82.3%	Pass
89.08 - 83.91	Pole + Reinf.	TP28.692x27.58x0.8375	Reinf. 14 Tension Rupture	80.5%	Pass
83.91 - 78.91	Pole + Reinf.	TP29.768x28.692x0.8125	Reinf. 14 Tension Rupture	84.5%	Pass
78.91 - 73.91	Pole + Reinf.	TP30.844x29.768x0.8	Reinf. 14 Tension Rupture	88.1%	Pass
73.91 - 68.91	Pole + Reinf.	TP31.919x30.844x0.775	Reinf. 14 Tension Rupture	91.4%	Pass
68.91 - 65.5	Pole + Reinf.	TP32.653x31.919x0.7625	Reinf. 14 Tension Rupture	93.5%	Pass
65.5 - 65.25	Pole + Reinf.	TP32.707x32.653x0.9125	Reinf. 14 Tension Rupture	86.7%	Pass
65.25 - 64.5	Pole + Reinf.	TP32.868x32.707x0.9125	Reinf. 14 Tension Rupture	87.1%	Pass
64.5 - 64.25	Pole + Reinf.	TP32.922x32.868x0.8125	Reinf. 14 Tension Rupture	91.6%	Pass
64.25 - 59.25	Pole + Reinf.	TP33.997x32.922x0.8	Reinf. 14 Tension Rupture	94.4%	Pass
59.25 - 58.58	Pole + Reinf.	TP34.142x33.997x0.7875	Reinf. 14 Tension Rupture	94.8%	Pass
58.58 - 58.33	Pole + Reinf.	TP34.195x34.142x0.85	Reinf. 13 Tension Rupture	85.6%	Pass
58.33 - 57.25	Pole + Reinf.	TP34.428x34.195x0.8375	Reinf. 13 Tension Rupture	86.1%	Pass
57.25 - 57	Pole + Reinf.	TP34.481x34.428x0.85	Reinf. 13 Tension Rupture	85.2%	Pass
57 - 52	Pole + Reinf.	TP35.557x34.481x0.8375	Reinf. 13 Tension Rupture	87.5%	Pass
52 - 49.58	Pole + Reinf.	TP37.19x35.557x0.825	Reinf. 13 Tension Rupture	88.6%	Pass
49.58 - 43.41	Pole + Reinf.	TP36.658x35.33x0.875	Reinf. 13 Tension Rupture	86.8%	Pass
43.41 - 38.41	Pole + Reinf.	TP37.734x36.658x0.8625	Reinf. 13 Tension Rupture	88.4%	Pass
38.41 - 34.5	Pole + Reinf.	TP38.575x37.734x0.85	Reinf. 13 Tension Rupture	89.6%	Pass
34.5 - 34.25	Pole + Reinf.	TP38.629x38.575x1.025	Reinf. 18 Tension Rupture	77.2%	Pass
34.25 - 33.5	Pole + Reinf.	TP38.791x38.629x1.0125	Reinf. 18 Tension Rupture	77.4%	Pass
33.5 - 33.25	Pole + Reinf.	TP38.844x38.791x0.8125	Reinf. 4 Tension Rupture	90.5%	Pass
33.25 - 29.5	Pole + Reinf.	TP39.651x38.844x0.8	Reinf. 4 Tension Rupture	91.6%	Pass
29.5 - 29.25	Pole + Reinf.	TP39.705x39.651x0.8875	Reinf. 13 Tension Rupture	85.5%	Pass
29.25 - 28.5	Pole + Reinf.	TP39.867x39.705x0.8875	Reinf. 13 Tension Rupture	85.7%	Pass
28.5 - 28.25	Pole + Reinf.	TP39.92x39.867x0.9	Reinf. 4 Tension Rupture	84.5%	Pass
28.25 - 27.48	Pole + Reinf.	TP40.086x39.92x0.9	Reinf. 3 Tension Rupture	84.7%	Pass
27.48 - 27.23	Pole + Reinf.	TP40.14x40.086x0.9	Reinf. 3 Tension Rupture	84.8%	Pass
27.23 - 22.23	Pole + Reinf.	TP41.216x40.14x0.875	Reinf. 3 Tension Rupture	86.0%	Pass
22.23 - 17.23	Pole + Reinf.	TP42.292x41.216x0.875	Reinf. 3 Tension Rupture	87.2%	Pass
17.23 - 12.23	Pole + Reinf.	TP43.368x42.292x0.85	Reinf. 3 Tension Rupture	88.2%	Pass
12.23 - 7.23	Pole + Reinf.	TP44.444x43.368x0.8375	Reinf. 3 Tension Rupture	89.2%	Pass
7.23 - 6.9	Pole + Reinf.	TP44.515x44.444x0.8625	Reinf. 10 Tension Rupture	84.9%	Pass
6.9 - 6.55	Pole + Reinf.	TP44.59x44.515x0.7875	Reinf. 2 Tension Rupture	92.4%	Pass
6.55 - 6.33	Pole + Reinf.	TP44.638x44.59x0.7875	Reinf. 2 Tension Rupture	92.4%	Pass

85.21	51.7%			85.0%							85.7
85.72	52.5%			86.0%							86.7
93.43	49.6%			84.3%							85.1
94.71	50.6%			85.9%							86.7
95.72	51.6%			87.0%							87.9
.18.28	45.1%			76.6%							66.9
.18.47	45.3%			76.8%							67.1
00.54	54.1%			90.5%							78.3
01.50	55.1%			91.6%							79.3
07.40	50.4%			85.5%			71.8%				74.5
07.59	50.5%			85.7%			72.0%				74.7
12.16	51.0%			84.5%			71.3%		83.4%	69.2%	70.1
07.85	51.2%	77.0%		84.7%			76.7%		83.3%	74.1%	
07.92	51.3%	77.1%		84.8%			76.8%		83.4%	74.2%	
09.20	52.4%	78.3%		86.0%			77.9%		84.6%	75.4%	
10.48	53.6%	79.4%		87.2%			78.9%		85.8%	76.6%	
11.76	54.7%	80.4%		88.2%			79.8%		86.9%	77.6%	
13.04	55.7%	81.4%		89.2%			80.7%		87.9%	78.6%	
19.79	51.0%	81.0%	82.3%	76.3%					84.9%	79.4%	
13.63	57.7%	82.1%	92.4%						88.0%	81.4%	
13.68	57.8%	82.1%	92.4%						88.1%	81.4%	
14.47	58.4%	82.6%	93.0%						88.6%	82.0%	
43.16	48.1%	61.9%	75.5%				58.1%	52.0%	71.8%	62.6%	
20.72	52.9%	73.0%	84.0%				65.9%	61.3%	80.2%	73.5%	
20.79	52.9%	73.0%	84.1%				66.0%	61.3%	80.3%	73.6%	
11.85	59.4%	81.5%	93.0%				74.4%	65.1%		78.2%	
07.42	59.3%	81.8%	92.8%				76.7%	72.7%			
07.93	59.7%	82.2%	93.1%				76.9%	73.0%			



Capacity: **87.7%** **PASS**

Preston / Town Hall (BU 876360)

TEP #: 25620.161151

Analysis: RKE 3/21/2018

Check: JLW 3/21/2018

Custom Anchor Rod Capacity Check\_v0.0

Factored Tower Base Reactions

	LC1	LC2	
Moment:	4,058.0	1,053.0	kip-ft
Axial (Download):	60.0	90.0	kip
Shear:	36.0	9.0	
Axial (Uplift):			kip

Load Centroid

X: 0.00 in  
Y: 0.00 in

Pole/Base Plate Geometry

Pole Shape: 18  
Pole OD: 46.000 in  
Pole Thickness: 0.375 in  
Plate Shape: Round  
Plate Diameter: 61.00 in  
Plate Thickness: 1.75 in

Code Revision

- TIA-222-G
- TIA-222-F

Anchor Size	A <sub>NET</sub> (in <sup>2</sup> )	F <sub>Y</sub> (ksi)	F <sub>U</sub> (ksi)	Config.	T/C	Qty.	Bolt Circle (in)	Spacing (in)	l <sub>br</sub> (in)	Bolt One Angle (Round) or Locations (Custom) (°)
2-1/4" (A615-J)	3.248	75.0	100.0	Round	T/C	12	55.000		1.000	0
2-1/4" (A615-J)	3.248	75.0	100.0	Round	T/C	4	55.000		1.000	15

Bolt Group	A <sub>NET</sub> (in <sup>2</sup> )	Y <sub>CONT</sub> (in)	T <sub>U</sub> (k)	C <sub>U</sub> (k)	M <sub>U</sub> (k-ft)	V <sub>U</sub> (k)	φ <sub>RNT</sub> (k)	φ <sub>RNM</sub> (k-ft)	φ <sub>RNV</sub> (k)	Orientation (°)	Capacity (%)
1	3.248	-27.496	213.74	220.35	0.29	3.47	259.81	7.88	134.19	179.0	87.4%
2	3.248	-27.500	214.22	220.83	0.30	3.47	259.81	7.88	134.19	165.0	87.7%

# Stiffened or Unstiffened, UngROUTED, Circular Base Plate - Any Rod Material

**TIA Rev G** Assumption: Clear space between bottom of leveling nut and top of concrete **not** exceeding  $(1) \times (\text{Rod Diameter})$

Site Data	
BU#:	876360
Site Name:	Preston / Town Hall
App #:	397067 Rev. 1
Pole Manufacturer:	Other

Reactions		
Mu:	3036.4125	ft-kips
Axial, Pu:	0	kips
Shear, Vu:	0	kips
Eta Factor, $\eta$	0.5	TIA G (Fig. 4-4)

Anchor Rod Data		
Qty:	12	
Diam:	2.25	in
Rod Material:	A615-J	
Strength (Fu):	100	ksi
Yield (Fy):	75	ksi
Bolt Circle:	55	in

If No stiffeners, Criteria: **AISC LRFD** <-Only Applicable to Unstiffened Cases

**Anchor Rod Results**  
Max Rod  $(C_u + V_u/\eta)$ : 220.8 Kips

Stiffened
AISC LRFD
$\phi \cdot T_n$

Plate Data		
Diam:	61	in
Thick:	1.75	in
Grade:	60	ksi
Single-Rod B-eff:	12.17	in



**Base Plate Results**  
Base Plate Stress: 47.4 ksi  
Allowable Plate Stress: 54.0 ksi  
Base Plate Stress Ratio: 87.8% **Pass**

Flexural Check

Stiffened
AISC LRFD
$\phi \cdot F_y$
Y.L. Length:
N/A, Roark

Stiffener Data (Welding at both sides)		
Config:	3	*
Weld Type:	Groove	
Groove Depth:	0.25	in **
Groove Angle:	45	degrees
Fillet H. Weld:		<-- Disregard
Fillet V. Weld:	0.4375	in
Width:	6	in
Height:	14	in
Thick:	0.5	in
Notch:	0.75	in
Grade:	50	ksi
Weld str.:	80	ksi
Clear Space between Stiffeners (b):	6.68	in

Pole Data		
Diam:	46	in
Thick:	0.375	in
Grade:	65	ksi
# of Sides:	18	"0" IF Round
Fu	80	ksi
Reinf. Fillet Weld	0	"0" if None



\* 0 = none, 1 = every bolt, 2 = every 2 bolts, 3 = 2 per bolt

\*\* Note: for complete joint penetration groove welds the groove depth must be exactly 1/2 the stiffener thickness for calculation purposes

# Stiffened or Unstiffened, UngROUTED, Circular Base Plate - Any Rod Material

**TIA Rev G** Assumption: Clear space between bottom of leveling nut and top of concrete **not** exceeding (1)\*(Rod Diameter)

## Site Data

BU#: 876360
Site Name: Preston / Town Hall
App #: 397067 Rev. 1
Pole Manufacturer: Other

## Anchor Rod Data

Qty:	12	
Diam:	2.25	in
Rod Material:	A615-J	
Strength (Fu):	100	ksi
Yield (Fy):	75	ksi
Bolt Circle:	55	in

## Plate Data

Diam:	61	in
Thick:	1.75	in
Grade:	60	ksi
Single-Rod B-eff:	12.17	in

## Stiffener Data (Welding at both sides)

Config:	3	*
Weld Type:	Groove	
Groove Depth:	0.25	in **
Groove Angle:	45	degrees
Fillet H. Weld:		<-- Disregard
Fillet V. Weld:	0.4375	in
Width:	6	in
Height:	14	in
Thick:	0.5	in
Notch:	0.75	in
Grade:	50	ksi
Weld str.:	80	ksi
Clear Space between Stiffeners (b):	6.68	in

## Pole Data

Diam:	46	in
Thick:	0.375	in
Grade:	65	ksi
# of Sides:	18	"0" IF Round
Fu	80	ksi
Reinf. Fillet Weld	0	"0" if None

## Reactions

Mu:	4079	ft-kips
Axial, Pu:	60	kips
Shear, Vu:	36	kips
Eta Factor, η	0.5	TIA G (Fig. 4-4)



If No stiffeners, Criteria: AISC LRFD <-Only Applicable to Unstiffened Cases

## Stiffener Results

Horizontal Weld :	68.9% Pass
Vertical Weld:	29.7% Pass
Plate Flex+Shear, fb/Fb+(fv/Fv)^2:	33.0% Pass
Plate Tension+Shear, ft/Ft+(fv/Fv)^2	74.8% Pass
Plate Comp. (AISC Bracket):	81.1% Pass

## Pole Results

Pole Punching Shear Check:	14.2% Pass
----------------------------	------------



\* 0 = none, 1 = every bolt, 2 = every 2 bolts, 3 = 2 per bolt

\*\* Note: for complete joint penetration groove welds the groove depth must be exactly 1/2 the stiffener thickness for calculation purposes

# Pier and Pad Foundation



BU #: 876360  
 Site Name: Preston / Town Hall  
 App. Number: 397067 Rev. 1

TIA-222 Revision: G  
 Tower Type: Monopole

Block Foundation?:

Superstructure Analysis Reactions		
Compression, $P_{comp}$ :	60	kips
Base Shear, $Vu_{comp}$ :	36	kips
Moment, $M_u$ :	4058	ft-kips
Tower Height, H:	147	ft
BP Dist. Above Fdn, $bp_{dist}$ :	4.5	in

Foundation Analysis Checks				
	Capacity	Demand	Rating	Check
Lateral (Sliding) (kips)	281.42	36.00	12.8%	Pass
Bearing Pressure (ksf)	11.81	2.13	18.1%	Pass
Overtuning (kip*ft)	7306.04	4323.50	59.2%	Pass
Pier Flexure (Comp.) (kip*ft)	4400.04	4202.00	95.5%	Pass
Pier Compression (kip)	31187.52	95.28	0.3%	Pass
Pad Flexure (kip*ft)	2857.85	1690.08	59.1%	Pass
Pad Shear - 1-way (kips)	932.37	249.00	26.7%	Pass
Pad Shear - 2-way (ksf)	0.19	0.04	21.6%	Pass

Soil Rating: 59.2%  
 Structural Rating: 95.5%

Pier Properties		
Pier Shape:	Square	
Pier Diameter, $dpier$ :	7.0	ft
Ext. Above Grade, E:	1.00	ft
Pier Rebar Size, $Sc$ :	8	
Pier Rebar Quantity, $mc$ :	33	
Pier Tie/Spiral Size, $St$ :	4	
Pier Tie/Spiral Quantity, $mt$ :	5	
Pier Reinforcement Type:	Tie	
Pier Clear Cover, $cc_{pier}$ :	3	in

Pad Properties		
Depth, D:	6.0	ft
Pad Width, W:	26.0	ft
Pad Thickness, T:	3.0	ft
Pad Rebar Size, $Sp$ :	8	
Pad Rebar Quantity, $mp$ :	26	
Pad Clear Cover, $cc_{pad}$ :	3	in

Material Properties		
Rebar Grade, $F_y$ :	60000	psi
Concrete Compressive Strength, $F'_c$ :	4000	psi
Dry Concrete Density, $\delta_c$ :	150	pcf

Soil Properties		
Total Soil Unit Weight, $\gamma$ :	123	pcf
Ultimate Net Bearing, $Q_{net}$ :	15.000	ksf
Cohesion, $C_u$ :		ksf
Friction Angle, $\phi$ :	40	degrees
SPT Blow Count, $N_{blows}$ :	64	
Base Friction, $\mu$ :	0.3	
Neglected Depth, N:	2.00	ft
Foundation Bearing on Rock?	No	
Groundwater Depth, $gw$ :	N/A	ft

<--Toggle between Gross and Net

**APPENDIX D**  
**STRUCTURAL DESIGN DRAWINGS**

**SITE NAME:**  
**PRESTON / TOWN HALL**

**CROWN CASTLE BU NUMBER:**  
**876360**

**SITE ADDRESS:**  
**389 RT. 2**  
**PRESTON, CT 06365**  
**(NEW LONDON COUNTY)**  
**N 41° 29' 25.25" , W 71° 59' 29.55"**

**PROVISIONS**

THESE DRAWINGS ARE BASED ON THE STRUCTURAL MODIFICATION BY TEP, JOB NO. 25620.161151

**NOTATION**

ANYTIME YOU ACCESS A CROWN TO CALL THE CROWN NOC UPON 800-788-7011.  
 ARE AVAILABLE FROM TEP TO PROVIDE RIGGING PLAN REVIEWS. FOR RIGGING SERVICES, CONTACT TEP FOR

**INDEX OF SHEETS**

NO.	SHEET TITLE	REV
T-1	TITLE SHEET	0
N-1	MI. CHECKLIST AND NOTES	0
N-2	PROJECT NOTES I	0
N-3	PROJECT NOTES II	0
N-4	NEXGEN2 INSTALLATION DETAILS	0
N-5	AJAX ONESIDE INSTALLATION DETAILS	0
N-6	FORGBOLT INSTALLATION DETAILS	0
S-1	TOWER ELEVATION AND MODIFICATION SCHEDULE	0
S-2	SECTION DETAILS	0
S-3	SHAFT REINFORCEMENT DETAILS	0
S-4	TYP. SHAFT REINFORCEMENT DETAILS I	0
S-5	TYP. SHAFT REINFORCEMENT DETAILS II	0
S-6	TRANSITION STIFFENER DETAILS	0

**PROJECT INFORMATION**

TOWER HEIGHT: 147-FT  
 TOWER MANUFACTURER: EEI  
 CCI DOCUMENT: 1615372  
 WORK ORDER NO.: 1532088  
 ORDER NO.: 397067 REV. 1  
 DESIGN BUILDING CODE: 2016 CONNECTICUT STATE BUILDING CODE  
 DESIGN STANDARD: ANSI/TIA-222-G-2-2009

**PROJECT TEAM**

**CCI MODIFICATION PROJECT MANAGER:**  
 NAME: CROWN CASTLE  
 CONTACT: DAN VADNEY  
 PHONE: (518) 373-3510  
 EMAIL: DAN.VADNEY@CROWNCastle.COM

**CCI MODIFICATION CONSTRUCTION MANAGER:**  
 NAME: CROWN CASTLE  
 CONTACT: JASON D'AMICO  
 PHONE: (860) 209-0104  
 EMAIL: JASON.D'AMICO@CROWNCastle.COM



APPLICABLE CROWN STANDARDS AND AS DESIGNED BY THE ENGINEER OF RECORD (EOR).

NO DOCUMENT, CODE OR POLICY CAN ANTICIPATE EVERY SITUATION THAT MAY ARISE. ACCORDINGLY, THIS CHECKLIST IS INTENDED TO SERVE AS A GUIDING PRINCIPLES IN ESTABLISHING GUIDELINES FOR MODIFICATION INSPECTION.

THE MI IS TO CONFIRM INSTALLATION CONFIGURATION AND WORKMANSHIP ONLY. IT IS NOT A REVIEW OF THE MODIFICATION DESIGN ITSELF, AND THE MI INSPECTOR DOES NOT TAKE OWNERSHIP OF THE MODIFICATION DESIGN. OWNERSHIP OF STRUCTURAL MODIFICATION DESIGN EFFECTIVENESS AND INTEGRITY RESIDES WITH THE EOR AT ALL TIMES. THE MI INSPECTOR SHALL INSPECT AND CONFORMANCE/NONCONFORMANCE AND PROVIDE TO THE CROWN POINT OF CONTACT (CROWN POC) FOR EVALUATION.

ALL MTS SHALL BE CONDUCTED BY A CROWN APPROVED MI INSPECTOR, WHO IS TO BE APPROVED BY THE EOR. SEE CROWN CED-LST-10173, "APPROVE VENDORS".

TO ENSURE THAT THE REQUIREMENTS OF THE MI ARE MET, IT IS VITAL THAT THE GENERAL CONTRACTOR (GC) AND THE MI INSPECTOR BEGIN COMMUNICATING COORDINATING AS SOON AS A PURCHASE ORDER (PO) IS RECEIVED. IT IS EXPECTED THAT EACH PARTY WILL BE PROACTIVE IN REACHING OUT TO THE OTHER PARTY. CONTACT INFORMATION IS NOT KNOWN TO THE GC AND/OR INSPECTOR SHALL CONTACT THE CROWN POINT OF CONTACT (CROWN POC).

REFER TO CROWN CED-SOW-10007, "MODIFICATION INSPECTION SOW", FOR FULL DETAILS AND REQUIREMENTS.

**SERVICE LEVEL COMMITMENT**

THE FOLLOWING RECOMMENDATIONS AND SUGGESTIONS ARE OFFERED TO ENHANCE THE EFFICIENCY AND EFFECTIVENESS OF DELIVERING AN MI REPORT:

- THE GC SHALL PROVIDE A MINIMUM OF 5 BUSINESS DAYS NOTICE, PREFERABLY 10, TO THE MI INSPECTOR AS TO WHEN THE SITE WILL BE READY FOR THE MI TO BE CONDUCTED.
- THE GC AND MI INSPECTOR COORDINATE CLOSELY THROUGHOUT THE ENTIRE PROJECT.
- WHEN POSSIBLE, IT IS PREFERRED TO HAVE THE GC AND MI INSPECTOR ON-SITE TOGETHER FOR ANY GUY WIRE TENSIONING OR RE-TENSIONING OPERATIONS.
- WHEN POSSIBLE, IT IS PREFERRED TO HAVE THE GC AND MI INSPECTOR ON-SITE DURING THE MI TO HAVE ANY MINOR DEFICIENCIES CORRECTED DURING THE INITIAL MI. THEREFORE, THE GC MAY CHOOSE TO COORDINATE THE MI CAREFULLY TO ENSURE ALL CONSTRUCTION FACILITIES ARE AT THEIR DISPOSE WHEN THE MI INSPECTOR IS ON-SITE.

**REQUIRED PHOTOS**

BETWEEN THE GC AND THE MI INSPECTOR THE FOLLOWING PHOTOGRAPHS, AT A MINIMUM, ARE TO BE TAKEN AND INCLUDED IN THE MI REPORT:

- PRE-CONSTRUCTION GENERAL SITE CONDITION PHOTOGRAPHS DURING THE REINFORCEMENT MODIFICATION CONSTRUCTION / ERECTION AND INSPECTION
- RAW MATERIALS
- PHOTOS OF ALL CRITICAL DETAILS
- FOUNDATION MODIFICATIONS
- WELD PREPARATION
- BOLT INSTALLATION
- FINAL INSTALLED CONDITION
- SURFACE COATING REPAIR
- POST CONSTRUCTION PHOTOGRAPHS
- FINAL INFIELD CONDITION

PHOTOS OF ELEVATED MODIFICATIONS TAKEN ONLY FROM THE GROUND SHALL BE CONSIDERED INADEQUATE.

THIS IS NOT A COMPLETE LIST OF REQUIRED PHOTOS. PLEASE REFER TO CROWN DOCUMENT # CED-SOW-10007.

**CONSTRUCTION**

ONCE THE PRE-MODIFICATION MAPPING IS COMPLETE AND PRIOR TO FABRICATION, THE CONTRACTOR SHALL PROVIDE DETAILED ASSEMBLY DRAWINGS AND/OR SHOP DRAWINGS. THESE ARE TO INCLUDE, BUT ARE NOT LIMITED TO, A VISUAL LAYOUT OF NEW REINFORCEMENT, EXISTING REINFORCEMENT CONFIGURATION, PORTHOLES, JOINTS, STEP PEGS, SAFETY CLIMBS AND ANY OTHER MISCELLANEOUS ITEMS WHICH MAY AFFECT SUCCESSFUL INSTALLATION OF MODIFICATIONS ON THE TOWER. THESE DRAWINGS SHALL BE SUBMITTED TO THE EOR FOR APPROVAL. APPROVED ASSEMBLY/SHOP DRAWINGS SHALL BE SUBMITTED TO THE MI INSPECTOR FOR INCLUSION IN THE MI REPORT.

A LETTER FROM THE FABRICATOR, STATING THAT THE WORK WAS PERFORMED IN ACCORDANCE WITH INDUSTRY STANDARDS AND THE CONTRACT DOCUMENTS, SHALL BE PROVIDED TO THE MI INSPECTOR FOR INCLUSION IN THE MI REPORT.

A CWI SHALL INSPECT ALL WELDING PERFORMED ON STRUCTURAL MEMBERS DURING FABRICATION. A WRITTEN REPORT SHALL BE PROVIDED TO THE MI INSPECTOR FOR INCLUSION IN THE MI REPORT.

MATERIAL TEST REPORTS SHALL BE PROVIDED FOR MATERIAL USED AS REQUIRED PER SECTION 9.2.5 OF CED-SOW-10007. MTRS SHALL BE PROVIDED TO THE MI INSPECTOR FOR INCLUSION IN THE MI REPORT.

CRITICAL SHOP WELDS THAT REQUIRE TESTING ARE NOTED ON THESE CONTRACT DRAWINGS. A CERTIFIED NDT INSPECTOR SHALL PERFORM NON-DESTRUCTIVE EXAMINATION AND A REPORT SHALL BE PROVIDED TO THE MI INSPECTOR FOR INCLUSION IN THE MI REPORT.

A NDE OF THE POLE TO BASE PLATE CONNECTION IS REQUIRED AND A WRITTEN REPORT SHALL BE PROVIDED TO THE MI INSPECTOR FOR INCLUSION IN THE MI REPORT.

THE MATERIAL SHIPPING LIST SHALL BE PROVIDED TO THE MI INSPECTOR FOR INCLUSION IN THE MI REPORT.

**POST-CONSTRUCTION**

A LETTER FROM THE GENERAL CONTRACTOR STATING THAT THE WORKMANSHIP WAS PERFORMED IN ACCORDANCE WITH INDUSTRY STANDARDS AND THESE CONTRACT DRAWINGS, INCLUDING LISTING ADDITIONAL PARTIES TO THE MODIFICATION PROCESS.

POST-INSTALLED ANCHOR RODS SHALL BE TESTED BY A CROWN APPROVED PULL TEST INSPECTOR AND A REPORT SHALL BE PROVIDED INDICATING TESTING RESULTS.

PHOTOGRAPHS SHALL BE SUBMITTED TO THE MI. PHOTOS SHALL DOCUMENT ALL PHASES OF THE CONSTRUCTION. THE PHOTOS SHALL BE ORGANIZED IN A MANNER THAT EASILY IDENTIFIES THE EXACT LOCATION OF THE PHOTO.

THE MI INSPECTOR SHALL VERIFY THE INSTALLATION AND TIGHTNESS 10% OF ALL NON PRE-TENSIONED BOLTS INSTALLED AS PART OF THE MODIFICATION. THE MI INSPECTOR SHALL LOOSEN THE NUT AND VERIFY THE BOLT HOLE SIZE AND CONDITION. THE MI REPORT SHALL CONTAIN THE COMPLETED BOLT INSTALLATION VERIFICATION REPORT, INCLUDING THE SUPPORTING PHOTOGRAPHS.

FINAL PUNCHLIST INDICATING ALL NONCONFORMANCE(S) IDENTIFIED AND THE FINAL RESOLUTION AND APPROVAL.

JUST HAVE CONSIDERABLE EXPERIENCE IN PERFORMANCE OF WORK SIMILAR TO THAT REQUIRED BY THIS ASSIGNMENT, THE CONTRACTOR IS ATTESTING THAT HE HAS THE KNOWLEDGE AND ABILITY, THAT HE IS KNOWLEDGEABLE OF THE WORK TO BE PERFORMED AND PROPERLY REGISTERED TO DO THIS WORK IN THE STATE OF CONNECTICUT.

IN ACCORDANCE WITH THE CONNECTICUT STATE BUILDING CODE, 2016 EDITION, THE CONTRACTOR SHALL FOLLOW THE SPECIFICATIONS, THE FOLLOWING MATERIALS LISTED HEREIN, AND TO THE PROCEDURES TO BE USED ON THIS PROJECT.

THE CONTRACTOR'S INSTRUCTIONS SHALL BE FOLLOWED EXACTLY AND SHALL SUPERSEDE ANY OTHER INSTRUCTIONS PROVIDED HEREIN.

THE CONTRACTOR SHALL BE RESPONSIBLE TO DETERMINE ERECTION PROCEDURE AND SEQUENCE TO ENSURE THE PROPER INSTALLATION AND ITS COMPONENT PARTS DURING ERECTION AND/OR FIELD MODIFICATIONS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE ADDITION OF TEMPORARY BRACING, GUYS OR TIE DOWNS THAT ARE NECESSARY TO MAINTAIN THE STRUCTURE AND SHALL REMAIN THE PROPERTY OF THE CONTRACTOR.

EXISTING CONDITIONS SHOWN ON THE DRAWINGS SHALL BE FIELD VERIFIED PRIOR TO BEGINNING ANY MATERIALS ORDERING, FABRICATION OR CONSTRUCTION WORK. THE CONTRACTOR SHALL NOT SCALE CONTRACT DRAWINGS IN LIEU OF FIELD VERIFICATIONS. ANY DISCREPANCIES IMMEDIATELY BROUGHT TO THE ATTENTION OF THE OWNER AND THE OWNER'S REPRESENTATIVE MUST BE RESOLVED BEFORE THE CONTRACTOR IS TO PROCEED WITH THE WORK. THE CONTRACTOR SHALL NOT INDICATE THE METHOD OF CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CONSTRUCTION MEANS, METHODS, AND PROCEDURES. OBSERVATION VISITS TO THE SITE BY THE OWNER OR HIS REPRESENTATIVE SHALL INCLUDE INSPECTION OF THE PROTECTIVE MEASURES OR THE PROCEDURES TO BE USED.

FURNISHED SHALL BE NEW AND OF GOOD QUALITY, FREE FROM FAULTS AND DEFECTS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS IN WRITING BY THE OWNER AND ENGINEER PRIOR TO INSTALLATION. THE CONTRACTOR SHALL PROVIDE SATISFACTORY EVIDENCE AS TO THE KIND AND QUALITY OF THE MATERIALS TO BE USED.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR INITIATING, MAINTAINING, AND SUPERVISING ALL SAFETY PRECAUTIONS DURING THE WORK. THE CONTRACTOR IS RESPONSIBLE FOR ENSURING THAT THIS PROJECT COMPLIES WITH ALL APPLICABLE LOCAL, STATE, AND FEDERAL SAFETY CODES AND REGULATIONS.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS IN WRITING BY THE OWNER AND ENGINEER PRIOR TO INSTALLATION. THE CONTRACTOR SHALL PROVIDE SATISFACTORY EVIDENCE AS TO THE KIND AND QUALITY OF THE MATERIALS TO BE USED.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS IN WRITING BY THE OWNER AND ENGINEER PRIOR TO INSTALLATION. THE CONTRACTOR SHALL PROVIDE SATISFACTORY EVIDENCE AS TO THE KIND AND QUALITY OF THE MATERIALS TO BE USED.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS IN WRITING BY THE OWNER AND ENGINEER PRIOR TO INSTALLATION. THE CONTRACTOR SHALL PROVIDE SATISFACTORY EVIDENCE AS TO THE KIND AND QUALITY OF THE MATERIALS TO BE USED.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS IN WRITING BY THE OWNER AND ENGINEER PRIOR TO INSTALLATION. THE CONTRACTOR SHALL PROVIDE SATISFACTORY EVIDENCE AS TO THE KIND AND QUALITY OF THE MATERIALS TO BE USED.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS IN WRITING BY THE OWNER AND ENGINEER PRIOR TO INSTALLATION. THE CONTRACTOR SHALL PROVIDE SATISFACTORY EVIDENCE AS TO THE KIND AND QUALITY OF THE MATERIALS TO BE USED.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS IN WRITING BY THE OWNER AND ENGINEER PRIOR TO INSTALLATION. THE CONTRACTOR SHALL PROVIDE SATISFACTORY EVIDENCE AS TO THE KIND AND QUALITY OF THE MATERIALS TO BE USED.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS IN WRITING BY THE OWNER AND ENGINEER PRIOR TO INSTALLATION. THE CONTRACTOR SHALL PROVIDE SATISFACTORY EVIDENCE AS TO THE KIND AND QUALITY OF THE MATERIALS TO BE USED.

## ATTENTION

THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS IN WRITING BY THE OWNER AND ENGINEER PRIOR TO INSTALLATION. THE CONTRACTOR SHALL PROVIDE SATISFACTORY EVIDENCE AS TO THE KIND AND QUALITY OF THE MATERIALS TO BE USED.

2. WHEN SPECIFIED IN THE DRAWINGS, CONNECTION BOLTS SHALL BE INSTALLED AND TIGHTENED AS PER SECTION 8.2.1 OF THE AISC SPECIFICATION FOR STRUCTURAL JOINTS USING A325 OR A490 BOLTS, LOCATED IN THE AISC MANUAL OF STEEL CONSTRUCTION. THE INSTALLATION PROCEDURE IS PARAPHRASED AS FOLLOWS:

### 8.2.1 TURN-OF-THE-NUT TIGHTENING

BOLTS SHALL BE INSTALLED IN ALL HOLES OF THE CONNECTION AND BROUGHT TO A SNUG TIGHT CONDITION AS DEFINED IN SECTION 8.1, UNTIL ALL THE BOLTS ARE SIMULTANEOUSLY SNUG TIGHT AND THE CONNECTION IS FULLY COMPACTED. FOLLOWING THIS INITIAL OPERATION ALL BOLTS IN THE CONNECTION SHALL BE TIGHTENED FURTHER BY THE APPLICABLE AMOUNT OF ROTATION SPECIFIED BELOW. DURING THE TIGHTENING OPERATION THERE SHALL BE NO ROTATION OF THE PART NOT TURNED BY THE WRENCH. TIGHTENING SHALL PROGRESS SYSTEMATICALLY FROM THE MOST RIGID PART OF THE JOINT IN A MANNER THAT WILL MINIMIZE RELAXATION OF PREVIOUSLY PRETENSIONED BOLTS.

- PRE-TENSIONED BOLTS AS SPECIFIED ON THE DRAWINGS SHALL BE TIGHTENED IN ACCORDANCE WITH AISC - "TURN OF THE NUT" METHOD, USING THE CHART BELOW.

#### BOLT LENGTHS UP TO AND INCLUDING FOUR DIA.

1/2"	BOLTS UP TO AND INCLUDING 2.0 INCH LENGTH	+1/2 TURN BEYOND SNUG TIGHT
3/8"	BOLTS UP TO AND INCLUDING 2.5 INCH LENGTH	+1/2 TURN BEYOND SNUG TIGHT
3/4"	BOLTS UP TO AND INCLUDING 3.0 INCH LENGTH	+1/2 TURN BEYOND SNUG TIGHT
7/8"	BOLTS UP TO AND INCLUDING 3.5 INCH LENGTH	+1/2 TURN BEYOND SNUG TIGHT
1"	BOLTS UP TO AND INCLUDING 4.0 INCH LENGTH	+1/2 TURN BEYOND SNUG TIGHT

#### BOLT LENGTHS OVER FOUR DIA. BUT NOT EXCEEDING EIGHT DIA.

1/2"	BOLTS 2.25 TO 4.0 INCH LENGTH	+1/2 TURN BEYOND SNUG TIGHT
3/8"	BOLTS 2.75 TO 5.0 INCH LENGTH	+1/2 TURN BEYOND SNUG TIGHT
3/4"	BOLTS 3.25 TO 6.0 INCH LENGTH	+1/2 TURN BEYOND SNUG TIGHT
7/8"	BOLTS 3.75 TO 7.0 INCH LENGTH	+1/2 TURN BEYOND SNUG TIGHT
1"	BOLTS 4.25 TO 8.0 INCH LENGTH	+1/2 TURN BEYOND SNUG TIGHT

- ALL ONE-SIDED BOLTS SHALL BE TIGHTENED IN ACCORDANCE WITH MANUFACTURER RECOMMENDATIONS.

## FIELD NDE MINIMUM REQUIREMENTS:

- ALL NDE SHALL BE IN ACCORDANCE WITH AWS D1.1.
- FOR NEW BASE STIFFENERS (INCLUDING OF TRANSITION STIFFENERS) AND ANCHOR ROD BRACKETS COMPLETE JOINT PENETRATION WELDS SHALL BE 100% INSPECTED BY ULTRASONIC TESTING (UT). ALL PARTIAL JOINT PENETRATION AND FILLET WELDS SHALL BE 100% INSPECTED BY MAGNETIC PARTICLE TESTING (MT).
- FOR NEW FLAT PLATE REINFORCEMENT AT THE BASE OF THE TOWER, COMPLETE JOINT PENETRATION WELDS SHALL BE 100% INSPECTED BY ULTRASONIC TESTING (UT). ALL PARTIAL JOINT PENETRATION AND FILLET WELDS SHALL BE 100% INSPECTED BY MAGNETIC PARTICLE TESTING (MT), BUT MAY BE LIMITED TO A HEIGHT OF 10'-0".
- FOR NDE OF THE EXISTING BASE PLATE CIRCUMFERENTIAL WELD, GC SHALL REFERENCE THE MI CHECKLISTS FOR APPLICABILITY. PLEASE SEE ENG-SOW-10033; TOWER BASE PLATE NDE, AND ENG-BUL-10051; NDE REQUIREMENTS FOR MONOPOLE BASEPLATES TO PREVENT CONNECTION FAILURE. NOTIFY THE EOR AND CROWD ENGINEERING IMMEDIATELY IF ANY CRACKS ARE SUSPECTED OR HAVE BEEN IDENTIFIED. THE NDE SHALL INCLUDE ALL EXISTING MODIFICATIONS THAT HAVE BEEN WELDED TO THE BASE PLATE.
- ALL TESTING LIMITATIONS SHALL BE DETAILED IN THE NDE REPORT.

3. SUPPORTING AND GUYED TOWERS) (NOPOLE) GALVANIZED HIGH STRENGTH BOLTS. DE BY I AND ALLOY STEEL NUTS. FINISHED STEEL WASHERS.

MAILED ON THESE PLANS SHALL BE DETAILED BY THE STEEL FABRICATOR CONSTRUCTION MANUAL, LRFD, 14TH EDITION.

THROUGH STEEL UNLESS APPROVED BY THE ENGINEER.

UNLESS OTHERWISE NOTED, AFTER FABRICATION WHERE PRACTICABLE, 1/53/A153M OR ASTM A653/A653M, G90, AS APPLICABLE. ADDITIONALLY, TO MATCH EXISTING STEEL. CONTRACTOR SHALL OBTAIN WRITTEN PERMISSION MEANS.

GALVANIZING REPAIR METHOD AND PAINT CONFORMING TO ASTM A780 OR PASTED MATERIAL SPECIFICALLY DESIGNED FOR REPAIR OF GALVANIZING. REMOVE SLAG FROM WELDS. HEAT SURFACES TO WHICH STICK OR PASTE CH TO A TEMPERATURE SUFFICIENT TO MELT THE METALLICS IN STICK OR AL UNIFORMLY OVER SURFACES TO BE COATED AND WIPE OFF EXCESS SHALL BE REPAINTED TO MATCH EXISTING FINISH (IF APPLICABLE).

INSTALLED ON ALL PROPOSED AND/OR REPLACED BOLTS.

BOLTS SHALL BE OF SUFFICIENT LENGTH TO EXCLUDE THE THREADS FROM

BOLTS SHALL BE OF SUFFICIENT LENGTH SUCH THAT THE END OF THE FACE OF THE NUT, IT IS NOT PERMITTED FOR THE BOLT END TO BE TIGHTENING IS COMPLETED.

ALL NOT BE REUSED.

CONCORDANCE WITH THE AWS D1.1/D1.1M: 2010 "STRUCTURAL WELDING

BY AWS CERTIFIED WELDERS.

WES CERTIFIED WELD INSPECTOR TO PERFORM VISUAL INSPECTIONS ON FIELD ALL BE ISSUED TO THE CONTRACTOR. CONTRACTOR SHALL SUBMIT LETTER TO PROFESSIONALS.

THE WELD FOR A DISTANCE OF 2" MINIMUM ALL AROUND. GRIND THE TALLE FOR A DISTANCE OF 2" MINIMUM ALL AROUND THE AREA TO BE E 100% FREE OF ALL GALVANIZING. SURFACES TO BE WELDED SHALL BE MOISTURE, GREASE OR ANY OTHER FOREIGN MATERIAL THAT WOULD

PREHEAT AND INTERPASS TEMPERATURE REQUIREMENTS SHALL COMPLY OF THE AWS D1.1/D1.1M:2010.

T-COVERED SURFACES AND PROVIDE ADEQUATE PROTECTION FROM HIGH

W HYDROGEN ELECTRODES. ELECTRODES SHALL BE APPROPRIATE FOR THE MAKE THE JOINT.

EA OF THE WELDS, THE INSTALLATION AND ALL SURFACES DAMAGED BY FIVE A COLD-GALVANIZED COATING. THIS COATING SHALL BE APPLIED BY IND SHALL CONTAIN A MINIMUM OF 95% +/- PURE ZINC. THE FINISHED THICKNESS OF 3 MILS.

CTIONS.

ENT MEMBER SHALL BE REQUIRED WHERE GAPS  
 REINFORCING MEMBER EXIST AT FASTENER LOCATIONS.  
 MINIMUM SHIM LENGTH AND WIDTH SHALL BE THE  
 1/2; FOR TERMINATION CONNECTIONS, A CONTINUOUS  
 ALENT INDIVIDUAL SHIM PLATES THE WIDTH OF THE  
 ADJACENT SHIM PLATE THICKNESSES MAY TAPER  
 BE NO LESS THAN 1/8". STACKING OF SHIMS IS  
 IN THICKNESS LOCATED WITHIN THE TERMINATION  
 MENT PLATE SHALL BE WELDED TO THE SHAFT  
 THE BOLTS TO COLD BEND THE STEEL PLATES  
 ROHIBITED IN LIEU OF SHIMS AND WILL BE CAUSE

**ID PROCEDURES:**

35.


IDS TO ENSURE CORRECT TENSION WAS ACHIEVED.

NTLY COATED WITH A CROWN-APPROVED COLD


**ACT:**

A 44256  
 J-232-6062

[WWW.AFTOWER.COM](http://WWW.AFTOWER.COM)



**NEXGEN2 BOLT DETAILS**



SLEEVE LENGTH	MIN. GRIP RANGE	MAX. GRIP RANGE
1 1/16"	1 5/16"	1 7/16"
1 3/16"	1 7/16"	1 7/8"
1 5/8"	1 7/8"	2 1/4"
2"	2 1/4"	2 13/16"

ENT MEMBER SHALL BE REQUIRED WHERE GAPS  
 NFORCING MEMBER EXIST AT FASTENER LOCATIONS.  
 E MINIMUM SHIM LENGTH AND WIDTH SHALL BE THE  
 2. FOR TERMINATION CONNECTIONS, A CONTINUOUS  
 ALENT INDIVIDUAL SHIM PLATES THE WIDTH OF THE  
 ADJACENT SHIM PLATE THICKNESSES MAY TAPER  
 BE NO LESS THAN 1/8". STACKING OF SHIMS IS  
 IN THICKNESS LOCATED WITHIN THE TERMINATION  
 MENT PLATE SHALL BE WELDED TO THE SHAFT  
 THE BOLTS TO COLD BEND THE STEEL PLATES  
 ROHIBITED IN LIEU OF SHIMS AND WILL BE CAUSE

**INSTALLATION:**

SEMBLED.  
 RS INSTRUCTIONS FOR INSTALLATION.

DTI PROTRUSIONS SHALL BE ENGAGED IN ANY  
 NFORCING MEMBERS. A FEELER GAGE MAY BE  
 ESSION.


ICE WITH THE MANUFACTURERS REQUIREMENTS AND  
 MODIFICATION INSPECTION SOW.

**ACT:**


OM.AU

**T:**

SVENS.COM




**AJAX ONESIDE BOLT DETAILS**



SLEEVE LENGTH	GRIP	GRIP IMP
3.0 (0.236")	12.5/20.0	0.500"/0.787"
4.0 (0.551")	20.0/32.0	0.787"/1.259"
2.0 (0.866")	30.0/50.0	1.181"/1.968"
30.0 (1.181")	40.5/50.0	1.595"/1.968"
9.0 (1.535")	49.0/77.0	1.929"/3.031"
8.0 (1.889")	60.5/77.0	2.375"/3.031"

INSPECTED ACCORDING TO THE REQUIREMENTS OF THE RCSC  
 NTS USING HIGH-STRENGTH BOLTS', DECEMBER 31, 2009.



**FORGBOLT ASSEMBLY DETAIL**


**BOLT HOLE NOTES**

BE NOMINAL 30mm DIAMETER. THE MAXIMUM SHOP-DRILLED HOLE DIAMETER

BE NOMINAL 30mm DIAMETER. THE MAXIMUM FIELD-DRILLED HOLE DIAMETER

**AISC GROUP A MATERIAL: ASTM A325 AND PC8.8  
 (TENSILE STRESS, Fu = 120 ksi MINIMUM)**

OVERALL LENGTH (IN)	ESTIMATED WEIGHT EACH (LBS)	GRIP RANGE (IN)	COMMENT	COLOR CODE
5.31	1.3	3/8" TO 1"	-	RED
6.30	1.6	3/4" TO 1 1/2"	-	GREEN
7.68	1.9	1 1/4" TO 2 1/4"	-	BLUE
10.24	2.6	2" TO 3 1/2"	SPLICE BOLT	YELLOW



**INSTALLED FORGBOLT ASSEMBLY DETAIL**


PRECISION TOWER PRODUCTS:  
 -PHONE: 888-926-4857  
 -EMAIL: INFO@PRECISIONTOWERPRODUCTS.COM  
 -WEB: WWW.PRECISIONTOWERPRODUCTS.COM  
 CONTAINS PROPRIETARY INFORMATION. PATENT PENDING.  
 © COPYRIGHT 2013 TO 2015 BY PTP. ALL RIGHTS RESERVED.

**FORGBOLT™ INSTALLATION**

**FOLLOW ALL MANUFACTURER/DISTRIBUTER  
 RECOMMENDATIONS FOR INSTALLATION, TIGHTENING, AND  
 INSPECTION.**

1. FIELD DRILL HOLES 30mm DIAMETER.
2. SELECT CORRECT BOLT SIZE FOR INSTALLATION GRIP (REFER TO PLANS).
3. INSERT BOLT ASSEMBLY THROUGH HOLES IN SHAFT REINFORCING PLATES AND SEAT THE HARDENED WASHERS WITH FLARED END AGAINST OUTSIDE OF PLATE.

780	29.110	0.2500	ASTM A572-65	-	-
380	37.190	0.3125	ASTM A572-65	-	-
330	46.000	0.3750	ASTM A572-65	ASTM A871-60	ASTM A615-75



2	REMOVE EXISTING BASE PLATE STIFFENERS. (CCI DOC ID 2331612)	0.00	S-2
3	INSTALL PROPOSED MONOPOLE SHAFT REINFORCEMENT.	1.25 - 115.08	S-2 THROUGH S-5
4	REINFORCE EXISTING MONOPOLE SHAFT REINFORCEMENT.	4.33 - 6.58	S-2 AND S-5
5	INSTALL PROPOSED TRANSITION STIFFENERS.	0.00	S-2 AND S-5
6	TEMPORARILY RELOCATE ICE BRIDGE TO ACCOMMODATE PROPOSED REINFORCEMENT.	-	-
7	REMOVE AND REPLACE STEP PEGS AS NECESSARY TO ACCOMMODATE PROPOSED REINFORCEMENT.	-	-
8	CROWN CASTLE WILL CONTRACT WITH A THIRD PARTY VENDOR TO PERFORM THE MODIFICATION INSPECTION. THE CONTRACTOR SHALL COORDINATE THE INSPECTION WITH THE MODIFICATION INSPECTOR AND CROWN CASTLE PROJECT MANAGER. SEE SHEET N-1 FOR DETAILS.	-	-

**NOTES:**

- CONTRACTOR SHALL FIELD VERIFY SPlice ELEVATION PRIOR TO INSTALLATION. CONTACT TOWER OWNER AND ENGINEER OF RECORD IF SPlice ELEVATIONS DIFFER FROM WHAT IS SHOWN. SHAFT REINFORCEMENT ELEVATIONS ARE DEPENDENT ON SPlice ELEVATIONS AND MAY NEED TO BE ADJUSTED TO ACCOMMODATE ACTUAL SPlice ELEVATION.
- IT IS THE CONTRACTOR'S SOLE RESPONSIBILITY TO PROVIDE THE MODIFICATION INSPECTOR/ ENGINEER OF RECORD WITH A SEALED CERTIFIED WELL INSPECTION REPORT. THIS REPORT SHALL DOCUMENT THE ENTIRE WELDING PROCESS (PRE/DURING/POST) WITH PROPER PHOTOS. WELDING SHALL CONFORM TO AWS D1.1/D1.1M: 2010 "STRUCTURAL WELDING CODE-STEEL". FOR ADDITIONAL NOTES, SEE WELDING NOTES.
- ANTENNAS AND OTHER APPURTENANCES MAY NEED TO BE TEMPORARILY REMOVED OR MOVED DURING THE INSTALLATION OF THE MODIFICATION SHOWN ABOVE.
- DUE TO THE MODIFICATIONS REQUIRED, CONTINUOUS INSPECTIONS AND MATERIAL TESTING WILL NEED TO BE PERFORMED.
- CONTRACTOR SHALL ORDER AND INSTALL A NEW TOWER TAG IF THE EXISTING TOWER TAG IS MOVED OR DAMAGED DUE TO THE INSTALLATION OF THE MODIFICATION SHOWN ABOVE.
- PRIOR TO FABRICATION AND INSTALLATION, CONTRACTOR SHALL FIELD VERIFY ALL LENGTHS AND QUANTITIES GIVEN. LENGTH AND QUANTITIES PROVIDED ARE FOR QUOTING PURPOSES ONLY AND SHALL NOT BE USED FOR FABRICATION.
- NO DETAILED INFORMATION REGARDING INTERFERENCES WAS PROVIDED. CONTRACTOR SHALL FIELD VERIFY ALL EXISTING CONDITIONS. REPORT AN AND ALL DISCREPANCIES TO TOWER ENGINEERING PROFESSIONALS, INC. AND CROWN CASTLE CONSTRUCTION MANAGER IMMEDIATELY.
- CONTRACTOR SHALL VERIFY COAX IS CONFIGURED AS SHOWN IN BASE LEVEL DRAWING ON SHEET S-2. CONTACT TEP AND CROWN CASTLE I THERE ARE DISCREPANCIES.

**CROWN CASTLE 65KSI FLAT PLATE REINFORCEMENT SCHEDULE**

QTY.	PART NO.	FLAT/ ANGLE	ELEV (FT.)		PLATE LENGTH (FT.)	TERMINATION BOLTS		MAX. INTERMEDIATE BOLT SPACING (IN.)	TOTAL BOLT QTY.	TOTAL STEEL WEIGHT (LB.)	TERMINATIC DETAIL
			BOT.	TOP		BOT.	TOP				
4	CCI-CFP-04512535	3, 5, 12, 16	1.25	36.25	35.00	7	7	24.00	116	2678.7	2
2	CCI-SFP-04510035	4, 10	32.00	67.00	35.00	6	6	20.00	62	1071.9	5
2	CCI-SFP-04510035	15, 18	32.00	67.00	35.00	6	6	20.00	62	1071.9	5
2	CCI-SFP-04510025	4, 10	67.08	92.08	25.00	6	6	20.00	50	765.6	4
1	CCI-SFP-04510030	16	63.00	93.00	30.00	6	6	20.00	28	459.4	5
2	CCI-CFP-04512522	4, 10	92.16	114.16	22.00	8	8	24.00	48	842.2	4
1	CCI-CFP-04512522	16	93.08	115.08	22.00	8	8	24.00	24	421.1	4
TOTALS:									390	7311.8	


**CROWN CASTLE 65KSI REINFORCEMENT SPlice PLATE SCHEDULE**

QTY.	PART NO.	FLAT/ ANGLE	ELEV (FT.)		QTY. OF BOLT HOLES PER PLATE	TOTAL BOLT HOLE QTY.	ADDITIONAL BOLT QTY. (SEE NOTE 6)	TOTAL STEEL WEIGHT (LB.)	TERMINATIC DETAIL
			BOT.	TOP					
2	CCI-SP-045100-6-6	4, 10	65.25	68.83	12	24	-	109.6	4
2	CCI-SP-045100-6-8	4, 10	90.33	94.42	14	28	-	156.2	4
1	CCI-SP-045100-6-8	16	91.25	95.33	14	14	-	78.1	4
TOTALS:						66	-	343.9	


**NOTES:**

- SEE SHEETS N-4 THROUGH N-6 FOR BOLT INSTALLATION DETAILS. SEE SHEET S-3 FOR PLATE DETAILS. SEE SHEETS S-4 AND S-5 FOR TERMINATION DETAILS.
- FOR FLAT PLATES STARTING AT 6", THE BOTTOM OF THE FLAT PLATE SHALL BEGIN AT 6" +/- 1" FOR SINGLE PLATES OR MULTIPLE PLATE SPliced TOGETHER. THE BOTTOM OF THE FLAT PLATE RUN SHALL BEGIN AT THE PROPOSED ELEVATION +/- 3" FOR MULTIPLE PLATES SPlice TOGETHER. THE TOP OF THE FLAT PLATE IS TO BE PLACED SUCH THAT THERE IS NO MORE THAN A 3" DIFFERENCE BETWEEN THE ACTUA OVERALL LENGTH OF THE SPAN AND THE PROPOSED OVERALL LENGTH OF THE SPAN, FROM THE BOTTOM OF THE BOTTOM PLATE TO THE TOP O THE TOP PLATE.
- SHIMS FOR MONOPOLE REINFORCEMENT MEMBER SHALL BE REQUIRED WHERE GAPS BETWEEN THE POLE SHAFT AND REINFORCING MEMBER EXIST A FASTENER LOCATIONS. FOR INTERMEDIATE CONNECTIONS, THE MINIMUM SHIM LENGTH AND WIDTH SHALL BE THE WIDTH OF THE REINFORC


DISCREPANCIES ARISE. CONTRACTOR TO REMOVE AND REPLACE CLIMBING SYSTEM USING ONLY APPROVED OPTIONS FROM CROWN CASTLE APPROVED REINFORCEMENT CATALOG AS NECESSARY TO INSTALL PROPOSED REINFORCEMENT. IF CLIMBING SYSTEM IS REQUIRED TO BE ATTACHED TO PROPOSED REINFORCEMENT, IT SHALL BE DONE PRIOR TO GALVANIZATION.




DISCREPANCIES ARISE. CONTRACTOR TO REMOVE AND REPLACE CLIMBING SYSTEM USING ONLY APPROVED OPTIONS FROM CROWN CASTLE APPROVED REINFORCEMENT CATALOG AS NECESSARY TO INSTALL PROPOSED REINFORCEMENT. IF CLIMBING SYSTEM IS REQUIRED TO BE ATTACHED TO PROPOSED REINFORCEMENT, IT SHALL BE DONE PRIOR TO GALVANIZATION.



**SECTION**  
SCALE: 3/4" = 1'-0" (B)




**NOTE:**  
BASE LEVEL DRAWING PROVIDED BY CROWN CASTLE.



(REMOVED)  
(1) 3/4" TO 118 FT LEVEL  
(REMOVED)  
(1) 1/2" TO 50 FT LEVEL



DISCREPANCIES ARISE. CONTRACTOR TO REMOVE AND REPLACE CLIMBING SYSTEM USING ONLY APPROVED OPTIONS FROM CROWN FASTLE APPROVED REINFORCEMENT CATALOG AS NECESSARY TO INSTALL PROPOSED REINFORCEMENT. IF CLIMBING SYSTEM IS REQUIRED TO BE ATTACHED TO PROPOSED REINFORCEMENT, IT SHALL BE DONE PRIOR TO GALVANIZATION.





SECTION D  
SCALE: 1" = 1'-0"




TO ACCOMMODATE EXISTING HOLES IN THE TOWER SHAFT, HOWEVER, THE MAXIMUM INTERMEDIATE BOLT SPACING PER SCHEDULE, EXISTING HOLES SHALL NOT BE RE-USED. NEW TOWER SHAFT BOLT HOLES SHALL BE A 30mm DIA. CONTRACTOR TO PROVIDE FLAT PLATE HOISTING DETAIL AND SUBMIT TO EOR PRIOR TO FABRICATION

TO ACCOMMODATE VARYING TERMINATION BOLT HOLE SPACING, TERMINATION BOLTS MAY NOT BE ADJUSTED.




SECTION D  
SCALE: 1" = 1'-0"




TO ACCOMMODATE EXISTING HOLES IN THE TOWER SHAFT, HOWEVER, THE MAXIMUM INTERMEDIATE BOLT SPACING PER SCHEDULE, EXISTING HOLES SHALL NOT BE RE-USED. NEW TOWER SHAFT BOLT HOLES SHALL BE A 30mm DIA. CONTRACTOR TO PROVIDE FLAT PLATE HOISTING DETAIL AND SUBMIT TO EOR PRIOR TO FABRICATION

TO ACCOMMODATE VARYING TERMINATION BOLT HOLE SPACING, TERMINATION BOLTS MAY NOT BE ADJUSTED.







**BOTTOM**


**BOTTOM TERMINATION DETAILS**

3B

SCALE: N.T.S.

**NOTE:**



1. SHIMS GREATER THAN 1/4" IN THICKNESS LOCATED WITHIN THE TERMINATION LENGTH OF THE SH REINFORCEMENT PLATE SHALL BE WELDED TO THE SHAFT REINFORCEMENT PLATE.



**AILS**

3A



THICKNESS LOCATED BETWEEN THE SHAFT REINFORCEMENT PLATE AND THE REINFORCEMENT PLATE SHALL BE WELDED TO THE SHAFT REINFORCEMENT PLATE.



WIDTH	6"
T/ TERMINATION	2'-3"
THICKNESS	1/4"
MATERIAL	ASTM A572-65
TOTAL QUANTITY	2

**NOTE:**

1. WHEN A TWO-SIDED CJP WELD IS UNATTAINABLE DU TO FIT-UP, THE CONTRACTOR SHALL BE PERMITTED TO USE THE ONE-SIDED CJP WELD DEPICTED BELOW. CONTRACTOR SHALL RED-LINE AS-BUILT DRAWING TO INDICATE THE CHOSEN DETAIL.





# EBI Consulting

environmental | engineering | due diligence

---

## RADIO FREQUENCY EMISSIONS ANALYSIS REPORT EVALUATION OF HUMAN EXPOSURE POTENTIAL TO NON-IONIZING EMISSIONS

SPRINT Existing Facility

Site ID: CT23XC411

Preston / Town Hall  
389 Rt 2  
Preston, CT 06365

**May 26, 2018**

**EBI Project Number: 6218004012**

Site Compliance Summary	
Compliance Status:	<b>COMPLIANT</b>
Site total MPE% of FCC general population allowable limit:	<b>11.29 %</b>



May 26, 2018

SPRINT

Attn: RF Engineering Manager  
1 International Boulevard, Suite 800  
Mahwah, NJ 07495

## Emissions Analysis for Site: **CT23XC411 – Preston / Town Hall**

EBI Consulting was directed to analyze the proposed SPRINT facility located at **389 Rt 2, Preston, CT**, for the purpose of determining whether the emissions from the Proposed SPRINT Antenna Installation located on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter ( $\mu\text{W}/\text{cm}^2$ ). The number of  $\mu\text{W}/\text{cm}^2$  calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits, therefore it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) – (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general population may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general population would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

General population exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter ( $\mu\text{W}/\text{cm}^2$ ). The general population exposure limits for the 850 MHz Band is approximately  $567 \mu\text{W}/\text{cm}^2$ . The general population exposure limit for the 1900 MHz (PCS) and 2500 MHz (BRS) bands is  $1000 \mu\text{W}/\text{cm}^2$ . Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.



Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure. Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

## CALCULATIONS

Calculations were done for the proposed SPRINT Wireless antenna facility located at **389 Rt 2, Preston, CT**, using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. Since SPRINT is proposing highly focused directional panel antennas, which project most of the emitted energy out toward the horizon, all calculations were performed assuming a lobe representing the maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was focused at the base of the tower. For this report the sample point is the top of a 6-foot person standing at the base of the tower.

For all calculations, all equipment was calculated using the following assumptions:

- 1) 1 CDMA channels (850 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 20 Watts per Channel.
- 2) 2 LTE channels (850 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 20 Watts per Channel.
- 3) 5 CDMA channels (1900 MHz (PCS)) were considered for each sector of the proposed installation. These Channels have a transmit power of 16 Watts per Channel.
- 4) 2 LTE channels (1900 MHz (PCS)) were considered for each sector of the proposed installation. These Channels have a transmit power of 40 Watts per Channel.
- 5) 8 LTE channels (2500 MHz (BRS)) were considered for each sector of the proposed installation. These Channels have a transmit power of 20 Watts per Channel.



# EBI Consulting

environmental | engineering | due diligence

---

- 6) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 - Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.
- 7) For the following calculations, the sample point was the top of a 6-foot person standing at the base of the tower. The maximum gain of the antenna per the antenna manufactures supplied specifications minus 10 dB was used in this direction. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 8) The antennas used in this modeling are the **RFS APXVSP18-C-A20** and the **Commscope DT465B-2XR** for transmission in the 850 MHz, 1900 MHz (PCS) and 2500 MHz (BRS) frequency bands. This is based on feedback from the carrier with regards to anticipated antenna selection. Maximum gain values for all antennas are listed in the Inventory and Power Data table below. The maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was used for all calculations. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 9) The antenna mounting height centerlines of the proposed antennas are **150 feet** above ground level (AGL) for **Sector A**, **150 feet** above ground level (AGL) for **Sector B** and **150 feet** above ground level (AGL) for Sector C.
- 10) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.

All calculations were done with respect to uncontrolled / general population threshold limits.





# EBI Consulting

environmental | engineering | due diligence

## SPRINT Site Inventory and Power Data by Antenna

Sector:	A	Sector:	B	Sector:	C
Antenna #:	1	Antenna #:	1	Antenna #:	1
Make / Model:	RFS APXVSPP18-C-A20	Make / Model:	RFS APXVSPP18-C-A20	Make / Model:	RFS APXVSPP18-C-A20
Gain:	13.4 / 15.9 dBd	Gain:	13.4 / 15.9 dBd	Gain:	13.4 / 15.9 dBd
Height (AGL):	150 feet	Height (AGL):	150 feet	Height (AGL):	150 feet
Frequency Bands	850 MHz / 1900 MHz (PCS)	Frequency Bands	850 MHz / 1900 MHz (PCS)	Frequency Bands	850 MHz / 1900 MHz (PCS)
Channel Count	8	Channel Count	8	Channel Count	8
Total TX Power(W):	180 Watts	Total TX Power(W):	180 Watts	Total TX Power(W):	180 Watts
ERP (W):	6,662.27	ERP (W):	6,662.27	ERP (W):	6,662.27
Antenna A1 MPE%	1.21 %	Antenna B1 MPE%	1.21 %	Antenna C1 MPE%	1.21 %
Antenna #:	2	Antenna #:	2	Antenna #:	2
Make / Model:	Commscope DT465B-2XR	Make / Model:	Commscope DT465B-2XR	Make / Model:	Commscope DT465B-2XR
Gain:	15.05 dBd	Gain:	15.05 dBd	Gain:	15.05 dBd
Height (AGL):	150 feet	Height (AGL):	150 feet	Height (AGL):	150 feet
Frequency Bands	2500 MHz (BRS) / 850 MHz	Frequency Bands	2500 MHz (BRS) / 850 MHz	Frequency Bands	2500 MHz (BRS) / 850 MHz
Channel Count	10	Channel Count	10	Channel Count	10
Total TX Power(W):	200 Watts	Total TX Power(W):	200 Watts	Total TX Power(W):	200 Watts
ERP (W):	5,983.32	ERP (W):	5,983.32	ERP (W):	5,983.32
Antenna A2 MPE%	1.15 %	Antenna B2 MPE%	1.15 %	Antenna C2 MPE%	1.15 %

Site Composite MPE%	
Carrier	MPE%
SPRINT – Max per sector	2.36 %
AT&T	2.74 %
MetroPCS	0.44 %
T-Mobile	2.66 %
Verizon Wireless	3.09 %
Site Total MPE %:	11.29 %

SPRINT Sector A Total:	2.36 %
SPRINT Sector B Total:	2.36 %
SPRINT Sector C Total:	2.36 %
Site Total:	11.29 %

SPRINT _ Frequency Band / Technology (Per Sector)	# Channels	Watts ERP (Per Channel)	Height (feet)	Total Power Density ( $\mu\text{W}/\text{cm}^2$ )	Frequency (MHz)	Allowable MPE ( $\mu\text{W}/\text{cm}^2$ )	Calculated % MPE
Sprint 850 MHz CDMA	1	437.55	150	0.76	850 MHz	567	0.13%
Sprint 1900 MHz (PCS) CDMA	5	622.47	150	5.40	1900 MHz (PCS)	1000	0.54%
Sprint 1900 MHz (PCS) LTE	2	1,556.18	150	5.40	1900 MHz (PCS)	1000	0.54%
Sprint 2500 MHz (BRS) LTE	8	639.78	150	8.87	2500 MHz (BRS)	1000	0.89%
Sprint 850 MHz LTE	2	432.54	150	1.50	850 MHz	567	0.26%
						<b>Total:</b>	<b>2.36%</b>



## Summary

All calculations performed for this analysis yielded results that were **within** the allowable limits for general population exposure to RF Emissions.

The anticipated maximum composite contributions from the SPRINT facility as well as the site composite emissions value with regards to compliance with FCC's allowable limits for general population exposure to RF Emissions are shown here:

SPRINT Sector	Power Density Value (%)
Sector A:	2.36 %
Sector B:	2.36 %
Sector C:	2.36 %
SPRINT Maximum Total (per sector):	2.36 %
Site Total:	11.29 %
Site Compliance Status:	<b>COMPLIANT</b>

The anticipated composite MPE value for this site assuming all carriers present is **11.29 %** of the allowable FCC established general population limit sampled at the ground level. This is based upon values listed in the Connecticut Siting Council database for existing carrier emissions.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.

**Zsamba, Anne Marie (Contractor)**

---

**From:** TrackingUpdates@fedex.com  
**Sent:** Tuesday, June 12, 2018 9:40 AM  
**To:** Zsamba, Anne Marie (Contractor)  
**Subject:** FedEx Shipment 772428291311 Delivered

## Your package has been delivered

Tracking # 772428291311

Ship date:  
**Fri, 6/8/2018**  
Rebecca Alescio  
Crown Castle  
Clifton Park, NY 12065  
US

Delivery date:  
**Tue, 6/12/2018 9:37 am**  
The Honorable Robert  
Congdon  
Crown Castle  
389 Route 2  
The Town of Preston  
PRESTON, CT 06365  
US



### Shipment Facts

Our records indicate that the following package has been delivered.

**Tracking number:** [772428291311](#)  
**Status:** Delivered: 06/12/2018 09:37 AM Signed for By: M.NANCY  
**Reference:** 1766.668  
**Signed for by:** M.NANCY  
**Delivery location:** Preston, CT  
**Delivered to:** Receptionist/Front Desk  
**Service type:** FedEx Priority Overnight  
**Packaging type:** FedEx Pak  
**Number of pieces:** 1  
**Weight:** 2.00 lb.  
**Special handling/Services:** For Saturday Delivery  
**Standard transit:** 6/12/2018 by 1:30 pm

Please do not respond to this message. This email was sent from an unattended mailbox. This report was generated at approximately 8:40 AM CDT on 06/12/2018.

All weights are estimated.

To track the latest status of your shipment, click on the tracking number above.

## Zsamba, Anne Marie (Contractor)

**From:** TrackingUpdates@fedex.com  
**Sent:** Tuesday, June 12, 2018 9:40 AM  
**To:** Zsamba, Anne Marie (Contractor)  
**Subject:** FedEx Shipment 772428269629 Delivered

# Your package has been delivered

Tracking # 772428269629

Ship date:  
Fri, 6/8/2018

Rebecca Alescio  
Crown Castle  
Clifton Park, NY 12065  
US

Delivery date:  
Tue, 6/12/2018 9:37 am

The Town of Preston  
389 Route 2  
Town Hall  
PRESTON, CT 06365  
US



## Shipment Facts

Our records indicate that the following package has been delivered.

**Tracking number:** [772428269629](#)  
**Status:** Delivered: 06/12/2018 09:37 AM  
Signed for By: M.NANCY  
**Reference:** 1766.668  
**Signed for by:** M.NANCY  
**Delivery location:** Preston, CT  
**Delivered to:** Receptionist/Front Desk  
**Service type:** FedEx Priority Overnight  
**Packaging type:** FedEx Pak  
**Number of pieces:** 1  
**Weight:** 2.00 lb.  
**Special handling/Services:** For Saturday Delivery  
**Standard transit:** 6/12/2018 by 1:30 pm

Please do not respond to this message. This email was sent from an unattended mailbox. This report was generated at approximately 8:40 AM CDT on 06/12/2018.

All weights are estimated.

To track the latest status of your shipment, click on the tracking number above.

Standard transit is the date and time the package is scheduled to be delivered by, based on the selected service, destination and ship date. Limitations and exceptions may apply. Please see the FedEx Service Guide for terms and conditions of service, including the FedEx Money-Back Guarantee, or contact your FedEx Customer Support representative.