

# **CRAIG CODY**

16 Chestnut Street, Suite 421 Foxboro, MA 02035 Tel (781) 831-1281 Fax (774) 215-5423

Melanie Bachman Executive Director Connecticut Siting Counsel 10 Franklin Square New Britain, CT 06051

Re: Notice of Exempt Modification – 151 Waterbury Road, Prospect, CT

Dear Ms. Bachman:

Please accept this letter as notification pursuant to R.C.S.A Section 16-50j-73, for construction that constitutes modification pursuant to R.C.S.A Section 16-50j-72(b) and 16-50j-73. In accordance with R.C.S.A Section 16-50j-73, a copy of this submission is being sent to the Town of Prospect. A copy of this submission is also being sent to Richland Towers Management Parkview LLC d/b/a Clear Channel Management Inc., the property owner on which the tower is located.

# T-Mobile Northeast LLC's Proposed Wireless Modifications

T-Mobile as successor in interest to Omnipoint Communications achieved an initial approval from the Siting Council to install antennas as well as related ground equipment and currently maintains this equipment. The facility consists of a One-Hundred and Fifty(150') foot high communications tower within a fenced in compound. T-Mobile now intends to modify the facility as shown on the enclosed plans prepared by Infinigy Engineering and annexed hereto in Exhibit 1. The modifications will consist of adding three (3) new antennas at the existing AGL of One-Hundred and Thirty feet (130'). A structural analysis has been completed for the site and attached as Exhibit 3.

# T-Mobile's Proposed Wireless Modifications Constitutes An "Exempt Modification"

The proposed modification to the above mentioned Facility constitutes an exempt modification of an existing facility provided for in R.C.S.A Section 16-50j-72(b)(2) and Council regulations promulgated pursuant thereto.

- 1) The proposed modification will not result in an increase in the height of the existing tower.
- 2) The modifications will remain entirely within the limits of the leased area. The modifications therefor, will not require the extension of the boundary.

Tower Resource Management, Inc., 16 Chestnut Street, Suite 421, Foxboro, MA 02035 - 781.831.1281

10					
and the second s					
(Amajorot) (Amajorot)	···· <del>·</del> ··				
(Acceptance of the second					
CONTRACTOR					
WALL SHOW					
(conjugação de la conjugação de la conju					
a house grant and to					
estatisti video est					
publican regulation					
N POZIÁLA LA COLOR					
introduktinjskip.					
erizatora constru					
sintemskists					
Special statistics					
SAMSTANDAMON					
Siddingonio					
Sistematica (Constitution)					
sasinesiera;					
one subject of the					
oddillagosta					
sakanto/spisjo					
ériatalisas/ayó					
vdeselydddialaidd					
atioipapapapap					
especial department					
5000					
idad deski da coo					
SOVISSIGNATURE					
advartici (daylaşı).					
netrinoccia					
okumizempost					
oduciel/segilie					
tive and distribution					
rajobardaniolas.					
Newsonamens.					
Disposition of the Control of the Co					
Windstandation					
Avojanija <u>k</u> ejej					
ovejsevejsko					
Burn Glasson					
First-windings(s))					
emidoetricassis:					
Obbios diago.					
minteracións					
- California (principle)					
Separate and the second					

- 3) The proposed modification does not increase the noise levels at the boundary by six(6) decibels or more under normal conditions.
- 4) T-Mobile's proposed facility will not increase the cumulative radio frequency electromagnetic radiation power density at the Tower sites' boundary to or above the standard adopted by the Connecticut Department of Environmental Protection as set forth in Section 22a-162 of the Connecticut General Statutes and MPE limits established by the Federal Communications Commission. A cumulative General Power Density table for T-Mobile's proposed modified facility is included as Exhibit 2.
- 5) The facility has received all municipal zoning approvals and building permits. (Regs., Conn. State Agencies Section 16-50j-72))

For all the foregoing reasons, T-Mobile Northeast LLC respectfully submits that the proposed modifications to the above-referenced telecommunications facility constitutes an exempt modification under R.C.S.A Section 16-50j-72(b)(2)

Respectfully submitted,

Craig Cody 781.831.4281

On behalf of American Tower Corporation

c/o Tower Resource Management, Inc. 16 Chestnut Street, Suite 421 Foxboro, MA 02035

cc: Town of Prospect
Richland Towers Management Parkview LLC
d/b/a Clear Channel Management Inc.

Site Plan

Power Density Report

	-conserved - and the defendance of the part - the control of the set of the control of the contr	
	Section of	
	1	
	occuliation .	
	T-MINISTER .	
	en-kisser	
	and the second	
	A Parameter	
	District Co.	
	Pera kabiya	
	eastern de constitue de constit	
	No.	
	- Total	
	derawa	
	dan .	
	Bankatak	
	Sales Control	
	and other security of the secu	
	entition.	
	displaying and a second	
	Marian	
	kin nazinin mirin katalim principin namatasi sukan kina tepanjay go	
	a Constitution	
	SA CONTRACTOR OF THE CONTRACTO	
	Mean	
	All belonders difference	
	distraction of the state of the	
	eaptionism eaptionism	
	diskinantisirjen Navyvolitiska politika	
	(A)	
	a) Distriction	
	ZZWIOS	
	Displaying and the property of	
2000		
- Control		
2000		
EMBOOR		
9600000		
97636344		
Wilderson Co.		
20000000		
race constant	144	
000000		
Pinzicaca		
demonstra		
one		
by and		
ikasakimus.		
ACHINEMENT AND A STATE OF THE S		
664/62005		
WHITE OF THE PARTY.		
step tands		
mentage		
relativistica		
ole diological		
KARAGISTON.		
Anglabette		
(MARKET COM)		
- 1		

Structural Analysis

Teastle.		
Was dissensed to the		
To manufacture		
and the second s		
William Control		
and the state of t		
200 A 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1		
Para Para Para Para Para Para Para Para		
40000 - 0.0000		
estate estate		
nacionalism		
Water		
solitors source		
nice database		
Andrew State Control		
W112/3559/ft		
Shartnesselle		
- 1		
ado as cracidos ano proprior de la composição de la compo		
A A A A A A A A A A A A A A A A A A A		
ALCO AND		
Ď.		
- 1		
and the second s		
Accordance to the control of the con		
and the second s		
inconstanting .		
ř.		
Westerna .		
ometical behavior of the control of		
-		
THE PARTY OF THE P		
EAST-SECTION OF THE SECTION OF THE S		
E :		
in a control of the c		

# T-MOBILE NORTHEAST LLC

# CTNH302A CTNH302/CLRCHANNEL/PROSP.

151 WATERBURY ROAD PROSPECT, CT 06712

(702Cu CONFIGURATION)

# VICINITY MAP Beacon Falls

# DO NOT SCALE DRAWINGS

CONTRACTOR SHALL VERIFY PLANS AND EXISTING DIMENSIONS AND CONDITIONS ON THE JOB SITE AND SHALL IMMEDIATELY NOTIFY THE ARCHITECT IN WRITING OF ANY DISCREPANCIES BEFORE PROCEEDING WITH THE WORK OR BE RESPONSIBLE FOR SAME.



# "CALL BEFORE YOU DIG" WWW.CBYD.COM

CALL 81, OR 1-800-922-4455 CALL THREE WORKING DAYS PRIOR TO DIGGING SWELL PREDICTIONS SHELL BE SPECIALIZED BY CONTRACTORIS AT ALL

# COLOR CODE FOR UTILITY LOCATIONS

GAS/OIL - YELLOW SURVEY - PINK
TEL YEATU - ORANGE PROPOSED EXCAVATION - WHITE

# GENERAL NOTES

- 1. THE CONTRACTOR SHALL GIVE ALL NOTICES AND COMPLY WITH ALL LAWS, ORDINANCES. RULES, REGULATIONS AND LAWFUL ORDERS OF ANY PUBLIC AUTHORITY, MUNICIPAL AND UTILITY COMPANY SPECIFICATIONS, AND LOCAL AND STATE JURISDICTIONAL CODES BEARING ON THE PERFORMANCE OF THE WORK, THE WORK PERFORMED ON THE PROJECT AND THE MATERIALS INSTALLED SHALL BE IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS AND ORDINANCES.
- THE ARCHITECT/ENGINEER HAVE MADE EVERY EFFORT TO SET FORTH IN THE CONSTRUCTION AND CONSTRUCT DOCUMENTS THE COMPLETE SCOPE OF WORK. THE CONTRACTOR BIDDING THE JOB IS NEVERTHELESS CAUTIONED THAT MINOR OMISSIONS OR ERRORS IN THE DRAWINGS AND OR SPECIFICATIONS SHALL NOT EXCUSE SAID CONTRACTOR FROM COMPLETING THE PROJECT AND IMPROVEMENTS IN ACCORDANCE WITH THE INTENT OF THESE
- THE CONTRACTOR OR BIDDER SHALL BEAR THE RESPONSIBILITY OF NOTIFYING (IN WRITING) THE T-MOBILE REPRESENTATIVE OF ANY CONFLICTS, ERRORS, OR OMISSIONS PRIOR TO THE SUBMISSION OF THE CONTRACTOR'S PROPOSAL OR PERFORMANCE OF WORK IN THE EVENT OF DISCREPANCIES. THE CONTRACTOR SHALL PRICE THE MORE COSTLY OR EXPENSIVE WORK, UNLESS DIRECTED IN WRITING OTHERWISE.
- THE SCOPE OF WORK SHALL INCLUDE FURNISHING OF ALL MATERIALS, EQUIPMENT, LABOR AND ALL OTHER MATERIALS AND LABOR DEEMED NECESSARY TO COMPLETE THE WORK/PROJECT AS DESCRIBED HEREIN.
- THE CONTRACTOR SHALL VISIT THE JOB SITE PRIOR TO THE SUBMISSION OF BIDS OR PERFORMING WORK TO FAMILIARIZE HIMSELF WITH THE FIELD CONDITIONS AND TO VERIFY THAT THE PROJECT CAN BE CONSTRUCTED IN ACCORDANCE WITH THE CONTRACT DOCUMENTS.
- 6. THE CONTRACTOR SHALL OBTAIN AUTHORIZATION TO PROCEED WITH CONSTRUCTION PRIOR TO STARTING WORK ON ANY ITEM NOT CLEARLY DEFINED BY THE CONSTRUCTION DRAWINGS/CONTRACT DOCUMENTS.
- 7. THE CONTRACTOR SHALL INSTALL ALL EQUIPMENT AND MATERIALS ACCORDING TO THE MANUFACTURER'S/VENDOR'S SPECIFICATIONS UNLESS NOTED OTHERWISE OR WHERE LOCAL CODES OR ORDINANCES TAKE PRECEDENCE.

- 8. THE CONTRACTOR SHALL PROVIDE A FULL SET OF CONSTRUCTION DOCUMENTS AT THE SITE UPDATED WITH THE LATEST REVISIONS AND ADDENDUM OR CLARIFICATIONS AVAILABLE FOR THE USE BY ALL PERSONNEL INVOLVED WITH THE PROJECT.
- 9. THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE PROJECT DESCRIBED HEREIN. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR ALL CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES AND FOR COORDINATING ALL PORTIONS OF THE WORK UNDER CONTRACT.
- 10. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ANY PERMITS AND INSPECTIONS WHICH ARE REQUIRED FOR THE LOCAL GOVERNMENT AUTHORITY.
- PROTECT EXISTING IMPROVEMENTS, EASEMENTS, PAVING, HAVE OCCURRED DUE TO CONSTRUCTION ON OR ABOUT THE
- 13. THE CONTRACTOR SHALL COMPLY WITH ALL OSHA PERTINENT STATE SAFETY REGULATIONS.
- 14. THE CONTRACTOR SHALL NOTIFY THE T-MOBILE REPRESENTATIVE WHERE A CONFLICT OCCURS ON ANY OF THE CONTRACT DOCUMENTS, THE CONTRACTOR IS NOT TO ORDER MATERIAL OR CONSTRUCT ANY PORTION OF THE WORK THAT IS IN CONFLICT UNTIL CONFLICT IS RESOLVED BY THE T-MOBILE
- 15. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS, ELEVATIONS,
- 16. THE CONTRACTOR SHALL RETURN ALL DISTURBED AREAS TO THEIR ORIGINAL CONDITION AT THE COMPLETION OF WORK.

# PROJECT SUMMARY

PROJECT MANAGER:

CONTACT:

CONTACT:

CTNH302A SITE NUMBER: CTNH302/CLRCHANNEL/PROSP. SITE NAME: SITE ADDRESS: 151 WATERBURY ROAD

AMERICAN TOWER CORPORATION

CURRENT ZONING: JURISDICTION:

WORK BY THE ARCHITECT/ENGINEER, THE STATE, COUNTY, OR

- 11. THE CONTRACTOR SHALL MAKE NECESSARY PROVISIONS TO
- 12 THE CONTRACTOR SHALL KEEP THE GENERAL WORK AREA CLEAN AND HAZARD FREE DURING CONSTRUCTION AND DISPOSE OF ALL DIRT, DEBRIS, RUBBISH AND REMOVE EQUIPMENT NOT SPECIFIED AS REMAINING ON PROPERTY, PREMISES SHALL BE LEFT IN CLEAN CONDITION AND FREE FROM PAINT SPOTS, DUST, OR SMUDGES OF ANY NATURE
- REQUIREMENTS, AS WELL AS THE LATEST EDITIONS OF ANY
- PROPERTY LINES, ETC., ON THE JOB.

MAP:104/BLOCK:160/LOT:151

N 41.523006' / W -72.997818'

PROSPECT, CT 06712 PROPERTY OWNER:

TOWN OF PROSPECT

ATC SITE NUMBER:

LAT./LONG.:

CURBING, ETC., DURING CONSTRUCTION, UPON COMPLETION OF WORK, THE CONTRACTOR SHALL REPAIR ANY DAMAGE THAT MAY

# PROJECT DESCRIPTION

282660

CONSTRUCTION TYPE: L700 UPGRADE

OUTDOOR Z EXISTING CABINET(S) ☐ EXISTING LATTICE TOWER EXISTING RBS 3106 ☐ INDOOR EXISTING CONCRETE PAD T EXISTING TRANSMISSION TOWER 12 EXISTING RBS 8102 EXISTING WATER TANK EXISTING \$12000 ☐ EXISTING EXISTING BUILDING SITE SUPPORT KIT STEEL PLATFOR SITE SUPPORT CABINET DE EXISTING PPC T EXISTING FLAGPOLE T EXISTING FORT WORTH ☐ PANELBOARD

T-MOBILE NORTHEAST LLC PROPOSES THE MODIFICATION OF AN UNMANNED WIRELESS BROADBAND FACILITY, ADDITION OF PROPOSED LTE 700 PANEL ANTENNAS & RRUS. REUSE EXISTING HYBRID CABLE GPS ANTENNA AND EXISTING EQUIPMENT CABINETS.

# SHEET INDEX

T-MOBILE NORTHEAST LLC

AMERICAN TOWER CORPORATION

1033 WATERVLIET SHAKER ROAD

400 STREET RD

BENSALEM, PA 19020

319 QUARRY ROAD

BRUCE HOFFMASTER

ALBANY, NY 12205

ALEX WELLER 518-690-0790

484-942-6339

ARCHITECT/ENGINEER: INFINIGY ENGINEERING


SPRING CITY, PA 19475

HEET	DESCRIPTION	KEVISION
Γ <b>–1</b>	TITLE SHEET	0
<b>D-1</b>	SITE PLAN	0
C-2	COMPOUND PLAN & ELEVATION	0
0-3	ANTENNA DETAIL & RF SCHEDULE	0
C-4	EQUIPMENT SPECIFICATIONS	0
E-1	GROUNDING AND POWER DIAGRAMS	0
E-2	COAX/FIBER PLUMBING DIAGRAM	0
N-1	GENERAL AND ELECTRICAL NOTES	0
		11

	SUBMITTALS	
DATE	DESCRIPTION	REVISION
1/2/18	REVISCO/YOR PERMIT	0
		1
	.,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	1
-	A	
		1
		1

DEPT.	DATE	APP'D	REVISIONS
RFE			
RF MAN,			
ZONING			
OPS			
CONSTR.			
SITE AC.			

PROJECT NO: 317-000 DRAWN BY: CHECKED BY:



THIS DOCUMENT IS THE CREATION, FRIGH PROPERTY AND COPYRIGHTED WORK OF T-MOBILE. ANY DUPLICATION OR USE WITHOUT EXPRESS WRITTEN CONSENT IS STRICTLY PROHIBITED.

NOTE: IF DRAWINGS ARE 22"x34", USE GRAPHICAL SCALE AND/OR 1/2 TIMES OF THE NOTED SCALE.

> SITE NUMBER: CTNH302A

SITE NAME: CTNH302/CLRCHANNEL/PROSP.

151 WATERBURY ROAD PROSPECT, CT 06712


SHEET TITLE

TITLE SHEET

SHEET NUMBER

T-1

SHEET 1 OF 8 SHEETS





# GENERAL SITE NOTES:

- A COMPLETE BOUNDARY SURVEY OF THE HOST PARCEL HAS NOT BEEN PERFORMED BY INFINICY, BOUNDARY INFORMATION IF SHOWN WAS OBTAINED FROM INFORMATION PROVIDED BY OTHERS, PROPERTY IS SUBJECT TO ALL EASEMENTS AND RESTRICTIONS OF RECORD.
- BASEMAPPING INFORMATION BASED ON PROVIDED INFORMATION.
- CONTRACTOR TO FIELD VERIFY DIMENSIONS AS NECESSARY BEFORE
- THE PROPOSED DEVELOPMENT DOES NOT INCLUDE SIGNS OF
- THE PROPOSED DEVELOPMENT IS UNMANNED AND THEREFORE DOES NOT REQUIRE A MEANS OF WATER SUPPLY OR SEWAGE DISPOSAL.
- NO LANDSCAPING WORK IS PROPOSED IN CONJUNCTION WITH THIS DEVELOPMENT OTHER THAN THAT WHICH IS SHOWN.
- THE PROPOSED DEVELOPMENT DOES NOT INCLUDE OUTDOOR STORAGE OR ANY SOLID WASTE RECEPTACLES.
- UTILITIES SHOWN ON PLAN ARE TAKEN FROM OWNERS RECORDS AND FIELD LOCATION OF VISIBLE SURFACE FEATURES. THE EXISTENCE, EXTENT AND EXACT HORIZONTAL AND VERTICAL. LOCATIONS OF UTILITIES HAS NOT BEEN VERIFIED. ANY CONTRACTOR
  PERFORMING WORK ON THIS SITE MUST CONTACT MISS UTILITY AT LEAST 48 HOURS PRIOR TO COMMENCING WORK.
- ALL OBSOLETE OR UNUSED FACILITIES SHALL BE REMOVED WITHIN 12 MONTHS OF CESSATION OF OPERATIONS.



STREET OR ROAD -x -- x -- CHAIN LINK FENCE

\_a\_\_a\_ OPAQUE WOODEN FENCE

TREES/SHRUBS TREE LINE

Ø UTILITY POLE

(E) EXISTING

(N) NEW

GRAPHIC SCALE

SCALE (11x17): 1" = 10'-0"SCALE (22x34): 1" = 5'-0"

(F)

(P) PROPOSED

**FUTURE** 

	SUBMIT IALS	
DATE	DESCRIPTION	REVISIO
/2/15	REVISEO/YOR PERMIT	. 6
		-
***************************************		
-		
~~~		

	j
	I
OT NO:	317-000
	OT NO:

DRAWN BY: ASW CHECKED BY:



THIS DOCUMENT IS THE CREATION, DESIGN, PROPERTY AND COPYRIGHTED WORK OF T-MOBILE. ANY DUPLICATION OR USE WITHOUT EXPRESS WRITTEN CONSENT IS STRICTLY PROHIBITED.

NOTE: IF DRAWINGS ARE 22\*x34\*, USE GRAPHICAL SCALE AND/OR 1/2 TIMES OF THE NOTED SCALE.

> SITE NUMBER: CTNH302A

SITE NAME: CTNH302/CLRCHANNEL/PROSP. 151 WATERBURY ROAD PROSPECT, CT 06712


SHEET TITLE SITE PLAN

SHEET NUMBER

C-1

SHEET 2 OF 8 SHEETS





naminina kangana kangan ka	<del>in an de la company de la company de la compa</del> ny de la company de la co	districtivities districtivitita districtivitities districtivities districtivities districtivit	de acresio conservación en	ed berk formeren er er eine in er er en		iain tanàna mandra dia			ters on the terminal state of the terminal s	de et en	minintendenci mitterci mitterprosp <sub>et</sub> stere ten	RF SYS	STEM SO	CHEDULE	(702Cı	CONFIGURAT	ION)				AND THE REAL PROPERTY OF THE P	***************************************			
SECTOR	TECHNOLOGY	ANTENNA PORT	BAND	ANTENNA MODEL #	VENDOR	QTY (REMOVED)	QTY (NEW)	AZIMUTH	M-TILT	E-TILT	ANTENNA CENTERLINE	TMA MODEL #	VENDOR	RRU MODEL #	VENDOR	CABLE CABLE LENGTH DIAMETER	CABLE QTY.	CABLE TYPE	CABLE MODEL #	VENDOR	CABLE TAGGING	COLOR CODING	JUMPER TYPE	JUMPER TAGGING	COLOR CODING
	GSM/UMTS	TBD	B2A	41D04 D04 /D4D	FRIAGRALI	4	Maleuro (no con la comuna constan				4701 0!	**************************************			200		(A)	VTENNA CONN	ECTED VIA PROPOSED	HYBRID CAB	(E)		FIBER	996-440c	
. [	UMTS	TBO	B4P	AIR21 B2A/B4P	ERICSSON	1	1	30*	σ	2*	130'-0"	KRY 112 144/1	ERICSSON	-	-	EXISTING 1-5/8"	4	COAX	EXISTING	N/A		4ye	COAX		_
^ [	LTE	TBD	B4A	AIR21 B4A/B2P	ERICSSON	1	1	30	ď	2"	130'0"	***	***	****			(AI	VIENNA CONN	ECTED VIA PROPOSED	HYBRID CABI	(E)		FIBER	Also, Salp	
ſ	LTE 700	TBD	B12P	LNX-6515DS-VTM	COMMSCOPE	0	1	30"	o	2°	130'0"	***	-	(PROPOSED) RRUS 11	ERICSSON	ON (ANTENNA CONNECTED VIA PROPOSED HYBRID CABLE)						FIBER		•••	
	GSM/UMTS	TBD	B2A	AIR21 B2A/B4P	POLOPONI		4	150		~	4701 08				-	William School and the State Communication C	(AA	VTENNA CONN	ECTED VIA PROPOSED	HYBRID CABI	E)		FIBER		
	UMTS	TBD	B4P	AIRZI BZAY DYF	ERICSSON	1	1	150	σ	2"	130'-0"	KRY 112 144/1	ERICSSON		-	EXISTING 1-5/8"	4	COAX	EXISTING	N/A	, dec sua		COAX		
в	LTE	TBD	B4A	AIR21 B4A/B2P	ERICSSON	1	1	150°	o	2	130'-0"			-	_	**************************************	(AA	VTENNA CONN	ECTED VIA PROPOSED	HYBRID CABI	(E)		FIBER		
Γ	LTE 700	TBD	B12P	LNX-6515DS-VTM	COMMSCOPE	0	1	150°	ď	2°	130'-0"	***	44	(PROPOSED) RRUS 11	ERICSSON		(AN	VTENNA CONN	ECTED VIA PROPOSED	HYBRID CABI	(E)		FIBER		
**************************************	GSM/UMTS	TBD	B2A	Albor Doy /DAD	F2100001	•	4	070	-		4701 08	-			**		(A)	VTENNA CONN	ECTED VIA PROPOSED	HYBRID CABI	(E)	WW	FIBER		_
آ ر	UMTS	TBD	B4P	AIR21 B2A/B4P	ERICSSON	1	1	270	0"	2"	130'0"	KRY 112 144/1	ERICSSON			EXISTING 1-5/8"	4	COAX	EXISTING	N/A		***	COAX		_
	LTE	TBD	B4A	AIR21 B4A/B2P	ERICSSON	1	1	270	o	2°	130'-0"		***	4-2.			(AA	VTENNA CONN	ECTED VIA PROPOSED	HYBRID CABI	' <i>E)</i>		FIBER	· en spec	
ľ	LTE 700	TBD	B12P	LNX-6515DS-VTM	COMMSCOPE	0	1	270	o	2°	130'-0"	ALOU, TO THE OWNER OF THE OWNER OWNER OF THE OWNER OWN	***	(PROPOSED) RRUS 11	ERICSSON		(AA	VITENNA CONN	ECTED VIA PROPOSED	HYBRID CABI	(E)		FIBER		**

RF SCHEDULE

EXISTING R - RED - GSM PROPOSED G - GREEN - UMTS 1900 FIBER CONNECTION B - BLUE - UMTS AWS Y - YELLOW - LTE 0 - ORANGE - FIBER CABLE


TAG #1

TAG #2

#1

TAG

#2



RFS MODEL NO.:	APXVF24-C-A20
RADOME MATERIAL:	ASA
RADOME COLOR:	LICHT CRAY

DIMENSIONS, HxWxD:

93"x14.5"x6.9" (2363 x 368 x 174 mm)

50.7 LBS (23 kg) (2) 7-16 DIN FEMALE

# ERICSSON MODEL NO .:

RADOME MATERIAL: RADOME COLOR: DIMENSIONS, HxWxD:

PRE-MOUNTED BRACKETS:

# AIR21 B2A/B4P

FIBERGLASS, UV RESISTANT LIGHT GRAY 56"x12"x8" (1422 x 307 x 200 mm)


83LBS

# ERICSSON MODEL NO .:

RADOME MATERIAL: RADOME COLOR: DIMENSIONS, HxWxD: WEIGHT, W/ PRE-MOUNTED BRACKETS: CONNECTOR:

# AIR21 B4A/B2P

FIBERGLASS, UV RESISTANT LIGHT GRAY 58"x12"x8" (1473 x 307 x 200 mm)



# METALLIC TAG NOTES:

1. TWO METALLIC TAGS SHALL BE ATTACHED AT EACH END OF EVERY CABLE LONGER THAN (3) THREE FEET.

TAG #1

TAG #2

- 2. CABLES LESS THAN (3) THREE FEET WILL HAVE TWO METALLIC TAGS ATTACHED AT THE CENTER OF THE CABLE.
- 3. TAGS WILL BE FASTENED WITH STAINLESS STEEL ZIP TIES

APPROPRIATE FOR CABLE DIAMETER.

4. STANDARDIZED METALLIC TAG KITS WILL BE ASSEMBLED WITH TAGS ALREADY ENGRAVED TO ACCOMODATE ALL

NOT TO SCALE



00 

SUBMITTALS									
DATE	DESCRIPTION	REVISION							
9/2/15	PENSCO/TOR PERSIT	0							
	······································								

DEPT.	DATE	APP'D	REMISIONS
RTE			
M. MAH			
ZOKING			
OP5			
CONSTR.			
SHE AC.			

DRAWN BY: JLM CHECKED BY



THIS DOCUMENT IS THE CREATION, DESIGN, PROPERTY AND COPYRIGHTED WORK OF T-MOBILE. ANY DUPLICATION OR USE WITHOUT EXPRESS WRITTEN CONSENT IS STRICTLY PROHIBITED.

NOTE: IF DRAWINGS ARE 22"x34", USE GRAPHICAL SCALE AND/OR 1/2 TIMES OF THE NOTED SCALE.

SITE NUMBER: CTNH302A

SITE NAME: CTNH302/CLRCHANNEL/PROSP.

151 WATERBURY ROAD PROSPECT, CT 06712


SHEET TITLE


ANTENNA DETAIL & RF SCHEDULE

SHEET NUMBER


C-3


SHEET 4 OF 8 SHEETS








\_\_\_ NOT TO SCALE















**REAR** 

3 METALLIC TAG DETAIL









PROPOSED ANTENNA ORIENTATION PLAN

PRACTICE."

MATERIALS: -CONCRETE: fc' - 3000psi. (MIN. U.N.O.) -REINFORCING STEEL: ASTM A615, GRADE 60. -WIRE MESH: ASTM A185.

-CONCRETE WORK SHALL BE PERFORMED IN ACCORDANCE WITH LATEST EDITION OF THE ACI CODE.
-STEEL WORK SHALL BE PERFORMED IN ACCORDANCE

WITH AISC STEEL CONSTRUCTION MANUAL,

"STRUCTURAL WELDING" CODE-STEEL. -REINFORCING STEEL SHALL BE PLACED IN

-WELDING SHALL BE PERFORMED IN ACCORDANCE

WITH AMERICAN WELDING SOCIETY (AWS) D1.1-92

ACCORDANCE WITH THE CONCRETE REINFORCING

STEEL INSTITUTE (CRSI), "MANUAL OF STANDARD

STRUCTURAL NOTES:

1. SPECIFICATIONS / CODES:

9th EDITION.

-STRUCTURAL STEEL: ASTM A36. -ELECTRODES FOR WELDING: E 70xx. -GALVANIZING: ASTM A153 (BOLTS) OR ASTM A123

(SHAPES, PLATES).
-EXPANSION BOLTS: HILTI KWIK BOLT II, STAINLESS STEEL, 3/4" 9x43/4" EMBEDMENT OR AN APPROVED EQUAL.

 $\mathbb{C}$ 

	SUBMITTALS	
DATE	DESCRIPTION	REVISION
9/2/15	AKVESED/FOR PERMIT	0
	ELIZABETH STATEMENT OF THE STATEMENT OF	T
	***************************************	
i		

DEPT.	DATE	APP'O	REVISIONS
RFE			
RF WN.		L	
ZONNG			
oes			
CONSTR.		T	
COTE AP		1	

		SINI DV		** *
1	PRO	JECT N	10:	317-000
	SITE AC			
	CONSTR.			i

ASW CHECKED BY:



THIS DOCUMENT IS THE CREATION, DESIGN, PROPERTY AND COPYRIGHTED WORK OF T-MOBILE. ANY DUPLICATION OR USE WITHOUT EXPRESS WRITTEN CONSENT IS STRICTLY PROHIBITED.

NOTE: IF DRAWINGS ARE 22"x34", USE GRAPHICAL SCALE AND/OR 1/2 TIMES OF THE NOTED SCALE.

> SITE NUMBER: CTNH302A

SITE NAME: CTNH302/CLRCHANNEL/PROSP.

151 WATERBURY ROAD PROSPECT, CT 06712


SHEET TITLE

EQUIPMENT **SPECIFICATIONS** 

SHEET NUMBER


C-4


SHEET 5 OF 8 SHEETS



ERICSSON MODEL NO .: RRUS11-B12 19.68"x16.97"x7.17" (500 x 431 x 182 mm) DIMENSIONS, HxWxD: WEIGHT: 50.71 LBS (23 kg)

RRUS 11 DETAIL






	SUBMITTALS						
DATE	DESCRIPTION	REVISIO					
8/2/15	REVISED/FOR PERMIT						
1							
T	100000000000000000000000000000000000000	1					
		1					
		T					
	W23444-H04-K3444-4-4-4-4-4-4-4-4-4-4-4-4-4-4-4-4-						

жгт.	DATE	APP'0	REVISIONS	
REE				
NAN.				
ONING				ŀ
OPS.				
MSTR.				
TE AC.				ı

317-000 PROJECT NO: JLM ASW



THIS DOCUMENT IS THE CREATION, DESIGN, PROPERTY AND COPYRIGHTED WORK OF T-MOBILE. ANY DUPLICATION OR USE WITHOUT EXPRESS WRITTEN CONSENT IS STRICTLY PROHIBITED.

GRAPHICAL SCALE AND/OR 1/2 TIMES OF THE NOTED SCALE.

> SITE NUMBER: CTNH302A

SITE NAME: CTNH302/CLRCHANNEL/PROSP.


151 WATERBURY ROAD PROSPECT, CT 06712

SHEET TITLE

**GROUNDING &** POWER DIAGRAMS

SHEET NUMBER

SHEET 6 OF 8 SHEETS



# **ELECTRICAL NOTES:**

ILLUSTRATIONS.

### WORK INCLUDED

1. INCLUDE ALL LABOR, MATERIALS, EQUIPMENT, PLANT SERVICES AND ADMINISTRATIVE TASKS REQUIRED TO COMPLETE AND MAKE OPERABLE THE ELECTRICAL WORK SHOWN ON THE DRAWINGS AND SPECIFIED HEREIN, INCLUDING BUT NOT LIMITED TO THE

### FOLLOWING: A. PREPARE AND SUBMIT SHOP DRAWINGS, DIAGRAMS AND

- B. PROCURE ALL NECESSARY PERMITS AND APPROVALS AND PAY ALL REQUIRED FEES AND CHARGES IN CONNECTION WITH THE WORK OF THIS CONTRACT
- C. SUBMIT AS-BUILT DRAWINGS, OPERATING AND MAINTENANCE INSTRUCTIONS AND MANUALS.
- D. EXECUTE ALL CUTTING, DRILLING, ROUGH AND FINISH
  PATCHING OF EXISTING OR NEWLY INSTALLED CONSTRUCTION REQUIRED FOR THE WORK OF THIS CONTRACT, FOR SLAB PENETRATIONS THROUGH POST TENSION SLABS, X-RAY EXACT AREA OF PENETRATION PRIOR TO PERFORMING WORK. COORDINATE ALL X-RAY, WORK WITH BUILDING ENGINEER.
- E. PROVIDE HANGERS, SUPPORTS, FOUNDATIONS, STRUCT FRAMING SUPPORTS, AND BASES FOR CONDUIT AND EQUIPMENT PROVIDED OR INSTALLED UNDER THE WORK OF HIS CONTRACT. PROVIDE COUNTER FLASHING, SLEEVES AND SEALS FOR FLOOR AND WALL PENETRATIONS
- F. MAINTAIN ALL EXISTING ELECTRICAL SERVICES IN THE BUILDING AREAS NOT AFFECTED BY THE ALTERATION DURING THE PROGRESS OF THE WORK INCLUDING PROVIDING ALL CONNECTIONS AND EQUIPMENT REQUIRED. PROVIDE TEMPORARY LIGHT AND POWER FOR CONSTRUCTION
- 2. IT IS THE INTENT OF THESE DRAWINGS AND SPECIFICATIONS TO CALL FOR AN INSTALLATION THAT IS COMPLETE IN EVERY RESPECT. IT IS NOT THE INTENT TO GIVE EVERY DETAIL ON THE DRAWINGS AND IN THE SPECIFICATIONS, IF AN ITEM OF WORK IS FOR INCLUSION IN THE CONTRACT, FURNISH AND INSTALL ALL MATERIAL AND EQUIPMENT USUALLY FURNISHED OR NEEDED TO MAKE A COMPLETE INSTALLATION WHETHER OR NOT SPECIFICALLY MENTIONED IN THE CONTRACT DOCUMENTS.

# GENERAL REQUIREMENTS

- PROVIDE ALL WORK IN ACCORDANCE WITH THE NATIONAL ELECTRICAL CODE (NEC) AND LOCAL AND STATE ELECTRICAL
- 2. THE ELECTRICAL PLANS ARE DIAGRAMMATIC ONLY REFER TO THE ARCHITECTURAL PLANS FOR THE EXACT DIMENSIONS OF THE BUILDING.
- LOAD CALCULATIONS ARE BASED ON EXISTING BUILDING INFORMATION/DRAWINGS PROVIDED TO ENGINEERING. CONTRACTOR IS TO VERIFY ALL EXISTING RATINGS AND LOADS PRIOR TO PURCHASING OF SPECIFIED EQUIPMENT FOR COMPLIANCE TO NEC. CONTRACTOR TO NOTIFY ENGINEER OF ANY DISCREPANCIES AND REQUEST FURTHER DIRECTION BY
- 4. EXISTING BUILDING EQUIPMENT IS NOTED ON THE DRAWINGS NEW OR RELOCATED EQUIPMENT IS SHOWN WITH SOLID LINES. FUTURE EQUIPMENT (NOT IN THIS CONTRACT) IS DEPICTED WITH SHADED LINES, REQUEST CLARIFICATION OF DRAWINGS OR OF SPECIFICATIONS PRIOR TO PRICING OR INSTALLATION. 5. GENERAL
- A. AFTER CAREFULLY STUDYING THE DRAWINGS AND SPECIFICATIONS, AND BEFORE SUBMITTING THE PROPOSAL MAKE A MANDATORY SITE VISIT TO ASCERTAIN CONDITIONS OF SITE, AND THE NATURE AND EXACT QUANTITY OF WORK TO BE PERFORMED. NO EXTRA COMPENSATION WILL BE ALLOWED FOR FAILURE TO NOTIFY THE OWNER, IN WRITING, OF ANY DISCREPANCIES THAT MAY HAVE BEEN NOTED BETWEEN THE EXISTING CONDITIONS AND THE DRAWINGS AND
- SPECIFICATIONS.

  B. VERIFY ALL MEASUREMENTS AT THE SITE AND BE
- RESPONSIBLE FOR CORRECTNESS OF SAME.
  6. QUALITY, WORKMANSHIP, MATERIALS AND SAFETY
  A. PROVIDE NEW MATERIALS AND EQUIPMENT OF A DOMESTIC MANUFACTURER BY THOSE REGULARLY ENGAGED IN THE PRODUCTION AND MANUFACTURE OF SPECIFIED MATERIALS AND FOLIPMENT, WHERE UIL OR OTHER AGENCY, HAS ESTABLISHED STANDARDS FOR MATERIALS, PROVIDE MATERIALS WHICH ARE LISTED AND LABELED ACCORDINGLY. THE COMMERCIALLY STANDARD ITEMS OF EQUIPMENT AND THE SPECIFIC NAMES MENTIONED HEREIN ARE INTENDED FOR THE PROPER FUNCTIONING OF THE WORK.
- B. WORK SHALL BE PERFORMED BY WORKMEN SKILLED IN THE TRADE REQUIRED FOR THE WORK, INSTALL MATERIALS AND FOLIPMENT TO PRESENT A NEAT APPEARANCE WHEN COMPLETED AND IN ACCORDANCE WITH THE APPROVED RECOMMENDATIONS OF THE MANUFACTURER AND IN
- ACCORDANCE WITH CONTRACT DOCUMENTS.

  C. PROVIDE LABOR, MATERIALS, APPARATUS AND APPLIANCES
  ESSENTIAL TO THE FUNCTIONING OF THE SYSTEMS DESCRIBED INDICATED HEREIN, OR WHICH MAY BE REASONABLY IMPLIED AS ESSENTIAL WHENEVER MENTIONED IN THE CONTRACT DOCUMENT OR NOT
- D. MAKE WRITTEN REQUESTS FOR SUPPLEMENTARY INSTRUCTIONS TO ARCHITECT/ENGINEER IN CASE OF DOUBT TO WORK INTENDED OR IN EVENT OF NEED FOR
- AS 10 WORK INTENDED OR IN EVENT OF NEED FOR EXPLANATION THEREOF.

  E, PERFORMANCE AND MATERIAL REQUIREMENTS SCHEDULED OR SPECIFIED ARE MINIMUM STANDARD ACCEPTABLE. THE RIGHT TO JUDGE THE QUALITY OF EQUIPMENT THAT DEVIATES FROM THE CONTRACT DOCUMENT REMAINS SOLELY WITH ARCHITECT/ENGINEER, CONTRACT DOCUMENT OR NOT.

1. GUARANTEE MATERIALS, PARTS AND LABOR FOR WORK FOR ONE
YEAR FROM THE DATE OF ISSUANCE OF OCCUPANCY PERMIT. DURING THAT PERIOD, MAKE GOOD FAULTS OR IMPERFECTIONS THAT MAY ARISE DUE TO DEFECTS OR OMISSIONS IN MATERIALS OR WORKMANSHIP WITH NO ADDITIONAL COMPENSATION AND AS

# CLEANING

- 1. REMOVE ALL CONSTRUCTION DEBRIS RESULTING FROM THE
- 2 CLEAN FOURPMENT AND SYSTEMS FOLLOWING THE COMPLETION OF THE PROJECT TO THE SATISFACTION OF THE ENGINEER. COORDINATION AND SUPERVISION
- 1. CAREFULLY LAY OUT ALL WORK IN ADVANCE TO AVOID UNNECESSARY CUTTING, CHANNELING, CHASING OR DRILLING OF FLOORS, WALLS, PARTITIONS, CEILINGS OR OTHER SURFACES. WHERE SUCH WORK IS NECESSARY, HOWEVER, PATCH AND REPAIR THE WORK IN AN APPROVED MANNER BY SKILLED MECHANICS AT NO ADDITIONAL COST TO THE OWNER, RENDER FULL COOPERATION TO OTHER TRADES WHERE WORK WILL BE INSTALLED IN CLOSE PROXIMITY TO WORK OF OTHER TRADES. ASSIST IN WORKING OUT SPACE CONDITIONS, IF WORK IS CAUSES INTERFERENCE, MAKE CHANGES NECESSARY TO CORRECT CONDITIONS WITHOUT EXTRA CHARGE.

### SUBMITTALS

- AS-BUILT DRAWINGS:
   A UPON COMPLETION OF THE WORK, FURNISH TO THE OWNER "AS-BUILT" DRAWINGS.
- A. UPON COMPLETION OF THE WORK, FULLY INSTRUCT T-MOBILE AS TO THE OPERATION AND MAINTENANCE OF ALL MATERIAL, EQUIPMENT AND SYSTEMS.

  B. PROVIDE 3 COMPLETE BOUND SETS OF INSTRUCTIONS FOR
- OPERATING AND MAINTAINING ALL SYSTEMS AND EQUIPMENT

### CUITING AND PATCHING

- 1. PROVIDE ALL CUTTING, DRILLING, ROUGH AND FINISH PATCHING REQUIRED TO COMPLETE THE WORK.

  2. OBTAIN OWNER APPROVAL PRIOR TO CUTTING THROUGH FLOORS

### TESTS INSPECTION AND APPROVAL

- 1. BEFORE ENERGIZING ANY ELECTRICAL INSTALLATION, INSPECT EACH UNIT IN DETAIL, TIGHTEN ALL BOLTS AND CONNECTIONS (TORQUE-TIGHTEN WHERE REQUIRED) AND DETERMINE THAT ALL COMPONENTS ARE ALIGNED, AND THE EQUIPMENT IS IN SAFE, OPERATIONAL CONDITION.
- PROVIDE THE COMPLETE ELECTRICAL SYSTEM FREE OF GROUND FAULTS AND SHORT CIRCUITS SUCH THAT THE SYSTEM WILL OPERATE SATISFACTORILY LINDER FULL LOAD CONDITIONS WITHOUT EXCESSIVE HEATING AT ANY POINT IN THE SYSTEM.

# SPECIAL REQUIREMENTS

- 1. DO NOT LEAVE ANY WORK INCOMPLETE NOR ANY HAZARDOUS SITUATIONS CREATED WHICH WILL AFFECT THE LIFE OR SAFETY OF THE PUBLIC AND/OR BUILDING OCCUPANTS. DO NOT INTERFERE WITH OR CUTOFF ANY OF THE EXISTING SERVICES WITHOUT THE OWNER'S WRITTEN PERMISSION.

  2. WHEN NECESSARY TO TEMPORARILY DISCONNECT ANY EXISTING
- BUILDING LITHLITIES AND SERVICE SYSTEMS, INCLUDING FEFDER CONFER WITH THE OWNER AND ARRANGE THE PERIOD OF INTERRUPTION FOR A TIME MUTUALLY AGREED LIPON SHUTDOWN NOTE: SCHEDULE AND NOTIFY OWNER 48 HOURS PRIOR TO SHUTDOWN, ALL SHUTDOWN WORK TO BE SCHEDULED AT A TIME CONVENIENT TO OWNER

- 1. ROUTE ALL GROUNDING CONDUCTORS AS SHOWN ON
- CONDUT/GROUNDING RISER.

  2. ROUTE 500 KCMIL CU. THIN CONDUCTOR FROM THE MGB LOCATION TO BUILDING STEEL. VERIFY BUILDING STEEL IS EFFECTIVELY GROUNDED PER NEC TO THE MAIN SERVICE
- GROUNDING ELECTRODE CONDUCTOR (GEC).

  3. MAKE ALL GROUND CONNECTIONS FROM MGB TO ELECTRICAL EQUIPMENT WITH 2 HOLE, CRIMP TYPE, BURNDY COMPRESSION
- TERMINATIONS, SIZED AS REQUIRED.

  4. USE 1 HOLE, CRIMP TYPE, BURNDY COMPRESSIONS TERMINATIONS, SIZED AS REQUIRED, AT EQUIPMENT GROUND
- 5. HIRE AN INDEPENDENT LAB TO PERFORM THE SPECIFIED OHMS TESTING. PROVIDE 4 SETS OF THE CERTIFIED DOCUMENTS TO THE OWNER FOR VERIFICATION PRIOR TO THE PROJECT COMPLETION.

- RACEWAYS

  1. ALL WIRING TO BE INSTALLED IN CONDUIT SYSTEMS IN ACCORDANCE WITH THE FOLLOWING:
  A. EXTERIOR FEEDERS AND CONTROL, WHERE UNDERGROUND, TO
- BE IN SCH 40 PVC
- B. EXTERIOR, ABOVE GROUND POWER CONDUITS TO BE CALVANIZED RIGID STEEL (RGS).
  C. ALL TELECOMMUNICATION CONDUITS, INTERIOR/EXTERIOR, TO
- D. INSTALL PULL ROPES IN ALL NEW EMPTY CONDUITS INSTALLED
- ON THIS PROJECT.

  E. ALL TELECOM CONDUITS AND PULL BOXES INSTALLED ON THIS PROJECT TO BE LABELED "T—MOBILE". OWNER WILL PROVIDE LABELS FOR CONTRACTOR TO INSTALL.
- F. INTERIOR FEEDERS TO BE INSTALLED IN E.M.T. WITH STEEL COMPRESSION FITTINGS.
  G. MINIMUM SIZE CONDUIT TO BE \*\frac{1}{2}" TRADE SIZE
- UNLESS OTHERWISE INDICATED ON THE DRAWINGS.
  H. FINAL CONNECTIONS TO MOTORS AND VIBRATING EQUIPMENT TO BE INSTALLED IN LIQUID-TIGHT FLEXIBLE METAL CONDUIT. CONDUIT TO BE RUN CONCEALED IN CEILINGS, FINISHED AREAS OR DRYWALL PARTITIONS, UNLESS OTHERWISE NOTED.
- J. THE POLITING OF CONDUITS INDICATED ON THE DRAWINGS IS DIAGRAMMATIC. BEFORE INSTALLING ANY WORK, EXAMINE THE WORKING LAYOUTS AND SHOP DRAWINGS OF THE OTHER TRADES TO DETERMINE THE EXACT LOCATIONS AND
- K. ALL EXTERIOR MOUNTING HARDWARE TO BE GALVANIZED STEEL COORDINATE WITH BUILDING ENGINEER PRIOR TO ATTACHING TO BUILDING STRUCTURE.

### RACEWAYS CONT'D

- L. PENETRATIONS OF WALLS, FLOORS AND ROOFS, FOR THE PASSAGE OF ELECTRICAL RACEWAYS, TO BE PROPERLY SEALED AFTER INSTALLATION OF RACEWAYS SO AS TO MAINTAIN THE STRUCTURAL OR WATERPROOF INTEGRITY OF THE WALL, FLOOR OR ROOF SYSTEM TO BE PENETRATED. SEAL ALL CONDUIT PENETRATIONS THROUGH FIRE OR SMOKE RATED WALLS, CEILINGS OR SMOKE TIGHT CORRIDOR PARTITIONS TO MAINTAIN PROPER RATING OF WALL OR CEILING.
- M. PROVIDE ALL CONDUIT ENDS WITH INSULATED METALLIC GROUNDING BUSHINGS.
  N. CONDUIT TO BE SUPPORTED AT MAXIMUM DISTANCE OF
- B'-O", OR AS REQUIRED BY NEC, IN HORIZONTAL AND VERTICAL DIRECTIONS.
- O. PROVIDE STAINLESS STEEL BLANK COVER PLATES FOR ALL JUNCTION BOXES AND/OR OUTLET BOXES NOT USED IN EXPOSED AREAS. PROVIDE ALL OTHER UNUSED BOXES WITH STANDARD STEEL COVER PLATES
- P. WHERE APPLICABLE, PROVIDE ROOFTOP CONDUIT SUPPORT SYSTEM, CONFORMING TO ROOFTOP WARRANTY REQUIREMENTS, PER BUILDING.

### WIRES AND CARLES

- 1. CONTRACTOR TO COORDINATE WITH EQUIPMENT SUPPLIER AND VENDOR FOR EXACT EQUIPMENT OVER—CURRENT PROTECTION VOLTAGE, WIRE SIZE AND PLUG CONFIGURATION, IF APPLICABLE,
- 2. ALL EQUIPMENT/DEVICES TO BE PROVIDED WITH INSULATED GROUND CONDUCTOR,
  3. ALL WIRE AND CABLE TO BE 600VOLT, COPPER, WITH THWN/
- THHN INSULATION, EXCEPT AS NOTED.
- 4. WIRE FOR POWER AND LIGHTING WILL NOT BE LESS THAN NO. 12AWG, ALL WIRE NO. 8 AND LARGER TO BE STRANDED.
- 5. CONTROL WIRING IS NOT TO BE LESS THAN NO. 14AWG, FLEXIBLE IN SINGLE CONDUCTORS OR MULTI-CONDUCTOR CABLES. CONTROL WIRING WILL CONSIST OF MULTI-CONDUCTOR CABLES WHEREVER POSSIBLE, CABLES TO BE PROVIDED WITH AN OVERALL FLAME-RETARDANT, EXTRUDED JACKET AND RATED FOR PLENUM USE, ALL CONTROL WIRE TO BE 600VOLT RATED
- WIRE PREVIOUSLY PULLED INTO CONDUIT IS CONSIDERED USED AND IS NOT TO BE RE-PULLED.
- 7. HOME RUNS AND BRANCH CIRCUIT WIRING FOR 20A, 120V

# CIRCUITS: LENGTH (FT.) HOME RUN WIRE SIZE 0 TO 50 51 TO 100 101 TO 150

- 8. VOLTAGE DROP IS NOT TO EXCEED 3% 9. MAKE ALL CONNECTIONS WITH UL APPROVED, SOLDERLESS, PRESSURE TYPE INSULATED CONNECTORS: SCOTCHLOK OR AND
- WIRING DEVICES 1. ALL RECEPTACLES INSTALLED IN THIS PROJECT TO BE GROUNDING TYPE, WITH GROUNDING PIN SLOT CONNECTED TO DEVICE GROUND SCREW FOR GROUND WIRE CONNECTION.
- DISCONNECT SWITCHES AND FUSES

  1. DISCONNECT SWITCHES TO BE VOLTAGE—RATED TO SUIT THE CHARACTERISTICS OF THE SYSTEM FROM WHICH THEY ARE
- 2. PROVIDE HEAVY—DUTY, METAL—FNCLOSED, EXTERNALLY—OPERATED DISCONNECT SWITCHES, FUSED OR UNFUSED, OF SUCH TYPE AND SIZE AS REQUIRED TO PROPERLY PROTECT OR DISCONNECT THE LOAD FOR WHICH THEY ARE INTENDED.
- 3. PROVIDE NEMA 1 DISCONNECT SWITCHES FOR INTERIOR INSTALLATION, NEMA 3R FOR EXTERIOR INSTALLATION. 4 DISCONNECT SWITCHES TO BE MANUFACTURED BY
- A. GENERAL ELECTRIC COMPANY B. SOUARE--D
- 5. PROVIDE RK-1 TYPE FUSES, UNLESS NOTED OTHERWISE. INSTALLATION 1. INSTALL DISCONNECT SWITCHES WHERE INDICATED ON
- DRAWINGS.
  2. INSTALL FUSES IN FUSIBLE DISCONNECT SWITCHES. FUSES
- MUST MATCH IN TYPE AND RATING.

  3. FUSES TO BE MOUNTED SO THAT THE LABELS SHOWING THEIR
- RATINGS CAN BE READ WITHOUT REQUIRING FUSE REMOVAL. . FURNISH AND DEPOSIT SPARE FUSES AT THE JOB SITE AS
- A. THREE SPARES FOR EACH TYPE AND SIZE, IN EXCESS OF 60A, USED FOR INITIAL FUSING.
  B. TEN PERCENT SPARES FOR EACH TYPE AND SIZE, UP TO
- AND INCLUDING BOA, USED FOR INITIAL FUSING, IN NO CASE WILL LESS THAN THREE FUSES OF ONE PARTICULAR TYPE AND SIZE BE FURNISHED.

# **GENERAL NOTES:**

- THESE SPECIFICATIONS AND CONSTRUCTION DRAWINGS
   ACCOMPANYING THEM DESCRIBE THE WORK TO BE DONE AND THE MATERIALS TO BE FURNISHED FOR CONSTRUCTION.
- 2. THE DRAWINGS AND SPECIFICATIONS ARE INTENDED TO BE FULLY EXPLANATORY AND SUPPLEMENTARY, HOWEVER, SHOULD ANYTHING BE SHOWN, INDICATED, OR SPECIFIED ON ONE AND NOT THE OTHER, IT SHALL BE DONE THE SAME AS IF SHOWN, INDICATED OR SPECIFIED IN BOTH
- 3. THE INTENTION OF THE DOCUMENTS IS TO INCLUDE ALL LABOR AND MATERIALS REASONABLY NECESSARY FOR THE PROPER EXECUTION AND COMPLETION OF THE WORK AS STIPULATED IN
- 4. THE PURPOSE OF THE SPECIFICATIONS IS TO INTERPRET THE INTENT OF THE DRAWINGS AND TO DESIGNATE THE METHOD OF THE PROCEDURE, TYPE AND QUALITY OF MATERIALS REQUIRED TO COMPLETE THE WORK.

  5. MINOR DEVIATIONS FROM THE DESIGN LAYOUT ARE ANTICIPATED
- AND SHALL BE CONSIDERED AS PART OF THE WORK, NO CHANGES THAT ALTER THE CHARACTER OF THE WORK WILL BE MADE OR PERMITTED BY THE OWNER WITHOUT ISSUING A

- 1. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFICATIONS OF ALL MEASUREMENTS AT THE SITE BEFORE ORDERING ANY OF ALL MEASUREMENTS AT THE SITE BEFORE ORDERING ANY
  MATERIALS OR DOING ANY WORK, NO EXTRA CHARGE OR
  COMPENSATION SHALL BE ALLOWED DUE TO DIFFERENCE RETWEEN ACTUAL DIMENSIONS AND DIMENSIONS INDICATED ON THE CONSTRUCTION DRAWINGS. ANY SUCH DISCREPANCY IN DIMENSION WHICH MAY BE FOUND SHALL BE SUBMITTED TO THE OWNER FOR CONSIDERATION BEFORE THE CONTRACTOR
- 2. THE BIDDER, IF AWARDED THE CONTRACT, WILL NOT BE ALLOWED ANY EXTRA COMPENSATION BY REASON OF ANY MATTER OR THING CONCERNING SUCH BIDDER MIGHT HAVE FULLY INFORMED THEMSELVES PRIOR TO THE BIDDING.
- 3. NO PLEA OF IGNORANCE OF CONDITIONS THAT EXIST, OR OF DIFFICULTIES OR CONDITIONS THAT MAY BE ENCOUNTERED, OR OF ANY OTHER RELEVANT MATTER CONCERNING THE WORK TO BE PERFORMED IN THE EXECUTION OF THE WORK WILL ACCEPTED AS AN EXCUSE FOR ANY FAILURE OR OMISSION ON THE PART OF THE CONTRACTOR TO FULFILL EVERY DETAIL OF ALL THE REQUIREMENTS OF THE CONTRACT DOCUMENTS GOVERNING THE WORK.

# CONTRACTS AND WARRANTIES

- OF CONTRACTOR IS RESPONSIBLE FOR APPLICATION AND PAYMENT OF CONTRACTOR LICENSES AND BONDS.

  2. SEE MASTER CONTRACTION SERVICES AGREEMENT FOR
- ADDITIONAL DETAILS.

 ALL MATERIALS MUST BE STORED IN A LEVEL AND DRY FASHION
 AND IN A MANNER THAT DOES NOT NECESSARILY OBSTRUCT THE FINW OF OTHER WORK, ANY STORAGE METHOD MUST MEET ALL

- THE CONTRACTORS SHALL, AT ALL TIMES, KEEP THE SITE FREE
   FROM ACCUMULATION OF WASTE MATERIALS OR RUBBISH CAUSED BY THEIR EMPLOYEES AT WORK AND AT THE COMPLETION OF THE WORK. THEY SHALL REMOVE ALL RUBBISH FROM AND ABOUT THE BUILDING AREA, INCLUDING ALL THEIR TOOLS, SCAFFOLDING AND SURPLUS MATERIALS AND SHALL LEAVE THEIR WORK CLEAN AND READY TO USE.
- A. VISUALLY INSPECT EXTERIOR SURFACES AND REMOVE ALL TRACES OF SOIL, WASTE MATERIALS, SMUDGES AND OTHER
- FOREIGN MATTER.

  B. REMOVE ALL TRACES OF SPLASHED MATERIALS FROM ADJACENT SURFACES.
  C. IF NECESSARY, TO ACHIEVE A UNIFORM DEGREE OF
- CLEANLINESS, HOSE DOWN THE EXTERIOR OF THE STRUCTURE.
- A. VISUALLY INSPECT INTERIOR SURFACE AND REMOVE ALL TRACES OF SOIL, WASTE MATERIALS, SMUDGES AND OTHER FOREIGN MATTER FROM WALLS, FLOOR, AND CEILING. B. REMOVE ALL TRACES OF SPLASHED MATERIALS FROM
- ADJACENT SURFACES.
  C. REMOVE PAINT DROPPINGS, SPOTS, STAINS, AND DIRT FROM FINISHED SURFACES.

# CHANGE ORDER PROCEDURE:

1. REFER TO SECTION 17 OF SIGNED MCSA: SEE PROFESSIONAL SERVICE AGREEMENT FOR MCSA.

- RELATED DOCUMENTS AND COORDINATION
  1. GENERAL CARPENTRY, ELECTRICAL AND ANTENNA DRAWINGS ARE INTERRELATED IN PERFORMANCE OF THE WORK THE CONTRACTOR MUST REFER TO ALL DRAWINGS. ALL COORDINATION TO BE THE RESPONSIBILITY OF THE CONTRACTOR.
- 1. CONTRACTOR SHALL SUBMIT SHOP DRAWINGS AS REQUIRED AND USED IN THESE SPECIFICATIONS TO THE OWNER FOR
- 2. ALL SHOP DRAWINGS SHALL BE REVIEWED, CHECKED AND CORRECTED BY CONTRACTOR PRIOR TO SUBMITTAL TO THE

# PRODUCTS AND SUBSTITUTIONS

- SUBMIT 3 COPIES OF EACH REQUEST FOR SUBSTITUTION, IN
   FACH REQUEST, IDENTIFY THE PRODUCT OR FABRICATION OR INSTALLATION METHOD TO BE REPLACED BY THE SUBSTITUTION. INCLUDE RELATED SPECIFICATION SECTION AND DRAWING NUMBERS AND COMPLETE DOCUMENTATION SHOWING COMPLIANCE WITH THE REQUIREMENTS FOR SUBSTITUTIONS
- 2. SUBMIT ALL NECESSARY PRODUCT DATA AND CUT SHEETS WHICH PROPERLY INDICATE AND DESCRIBE THE ITEMS, PRODUCTS AND MATERIALS BEING INSTALLED. THE CONTRACTOR SHALL IF DEFMED NECESSARY BY THE OWNER, SUBMIT ACTUAL SAMPLES TO THE OWNER FOR APPROVAL IN LIEU OF CUT

# **QUALITY ASSURANCE**

1. ALL WORK SHALL BE IN ACCORDANCE WITH APPLICABLE LOCAL STATE AND FEDERAL REGULATIONS: THESE SHALL INCLUDE, BUT NOT BE LIMITED TO THE APPLICABLE CODES SET FORTH BY THE LOCAL GOVERNING BODY, SEE "CODE COMPLIANCE" T-1.

- 1. BEFORE THE COMMENCEMENT OF ANY WORK, THE CONTRACTOR WILL ASSIGN A PROJECT MANAGER WHO WILL ACT AS A SINGLE POINT OF CONTACT FOR ALL PERSONNEL INVOLVED IN THIS PROJECT THIS PROJECT MANAGER WILL DEVELOP A MASTER SCHEDULE FOR THE PROJECT WHICH WILL BE SUBMITTED TO THE OWNER PRIOR TO THE COMMENCEMENT OF ANY WORK
- SUBMIT A BAR TYPE PROGRESS CHART, NOT MORE THAN 3 DAYS AFTER THE DATE ESTABLISHED FOR COMMENCEMENT OF THE WORK ON THE SCHEDULE, INDICATING A TIME BAR FOR EACH MAJOR CATEGORY OR UNIT OF WORK TO BE PERFORMED AT THE SITE, PROPERLY SEQUENCED AND COORDINATED WITH OTHER ELEMENTS OF WORK AND SHOWING COMPLETION OF THE WORK SUFFICIENTLY IN ADVANCE OF THE DATE ESTABLISHED FOR SUBSTANTIAL COMPLETION OF THE WORK.
- 3. PRIOR TO COMMENCING CONSTRUCTION, THE OWNER SHALL SCHEDULE AN ON-SITE MEETING WITH ALL MAJOR PARTIES. THIS WOULD INCLUDE, BUT NOT LIMITED TO, THE OWNER, PROJECT MANAGER, CONTRACTOR, LAND OWNER REPRESENTATIVE, LOCAL TELEPHONE COMPANY, TOWER ERECTION FOREMAN (IF SURCONTRACTED)
- 4. CONTRACTOR SHALL BE EQUIPPED WITH SOME MEANS OF CONSTANT COMMUNICATIONS, SUCH AS A MOBILE PHONE OR A REFPER. THIS EQUIPMENT WILL NOT BE SUPPLIED BY THE OWNER, NOR WILL WIRELESS SERVICE BE ARRANGED
- 5, DURING CONSTRUCTION, CONTRACTOR MUST ENSURE THAT EMPLOYEES AND SUBCONTRACTORS WEAR HARD HATS AT ALL TIMES. CONTRACTOR WILL COMPLY WITH ALL WPCS SAFETY REQUIREMENTS IN THEIR AGREEMENT.
- 6. PROVIDE WRITTEN DAILY UPDATES ON SITE PROGRESS TO THE
- 7. COMPLETE INVENTORY OF CONSTRUCTION MATERIALS AND EQUIPMENT IS REQUIRED PRIOR TO START OF CONSTRUCTION. B. NOTIFY THE OWNER/PROJECT MANAGER IN WRITING NO LESS THAN 48 HOURS IN ADVANCE OF CONCRETE POURS, TOWER ERECTIONS, AND EQUIPMENT CABINET PLACEMENTS.

- INSURANCE AND BONDS

  1. CONTRACTOR, AT THEIR OWN EXPENSE, SHALL CARRY AND MAINTAIN, FOR THE DURATION OF THE PROJECT, ALL INSURANCE, AS REQUIRED AND LISTED, AND SHALL NOT COMMENCE WITH THEIR WORK UNTIL THEY HAVE PRESENTED AN ORIGINAL CERTIFICATE OF INSURANCE STATING ALL COVERAGES TO THE OWNER, REFER TO THE MASTER AGREEMENT FOR
- REQUIRED INSURANCE LIMITS, 2. THE OWNER SHALL BE NAMED AS AN ADDITIONAL INSURED ON ALL POLICIES. 3. CONTRACTOR MUST PROVIDE PROOF OF INSURANCE.

AGL

BTS CAB

CONC

CONT

ELEV

EQUIP

EGB

(E)

GA GALV

GC

LG

GRND

MAX MECH

MW MFR

MIN MTL

(N) NIC NTS

OC OPP

(P) PCS PPC

SHT

SS

STL

TOC

VIF

WWF

FF

FOUIPMENT

FYICTING

EXTERIOR

GAUGE

GROUND

MAXIMUM

MINIMUM

MECHANICAL

MICROWAVE DISH

NOT IN CONTRACT

NOT TO SCALE

SQUARE FOOT

STAINLESS STEEL

TOP OF CONCRETE

TOP OF MASONRY

VERIFY IN FIELD

UNLESS OTHERWISE NOTED

WELDED WIRE FABRIC

ON CENTER

OPPOSITE

PROPOSED

SHEET

SIMILAR

STEEL

TYPICAL

MASTER GROUND BAR

POWER PROTECTION CABINET

MANUFACTURER

LONG

FINISHED FLOOR

GENERAL CONTRACTOR

GALVANIZED

EQUIPMENT GROUND BAR

DIA OR 6

APPROX

# CHECKED BY AECKED BY ABBREVIATIONS w Show ABOVE GROUND LINE APPROXIMATE BASE TRANSMISSION STATION O No. 24705 CENSE ONAL EN PROPERTURE SEAL CEILING CONCRETE CONTINUOUS DIAMETER DRAWING EACH ELECTRICAL FI FVATION

WORK OF T-MOBILE, ANY DUPLICATION OR LISE WITHOUT EXPRESS WRITTEN CONSENT IS STRICTLY PROHIBITED.

00

()

L

L

DEPT. DATE APP'D

PROJECT NO:

DRAWN BY:

RF MAN.

QPS

SITE AC.

SUBMITTALS

REVISIONS

317-000

JLM

ASW

REMSED/TOR PERM

NOTE: IF DRAWINGS ARE 22"x34", USE GRAPHICAL SCALE AND/OR 1/2 TIMES

SITE NUMBER CTNH302A

SITE NAME: CTNH302/CLRCHANNEL/PROSP. 151 WATERBURY ROAD

**GENERAL AND** ELECTRICAL NOTES

SHEFT NUMBER

N-1

SHEET 8 OF 8 SHEETS

### DETAIL REFERENCE KEY - REFER TO DRAWING DETAIL NUMBER RE: 2/A-3 -SHEET NUMBER OF DETAIL-

ARCHITECTURAL SYMBOLS

THIS DOCUMENT IS THE CREATION. DESIGN, PROPERTY AND COPYRIGHTED PERSONAL COMMUNICATION SYSTEM

SHEET TITLE



# RADIO FREQUENCY EMISSIONS ANALYSIS REPORT EVALUATION OF HUMAN EXPOSURE POTENTIAL TO NON-IONIZING EMISSIONS

T-Mobile Existing Facility

Site ID: CTNH302A

CTNH302/ Clr Channel/ Prosp. 151 Waterbury Road Prospect, CT 06712

October 29, 2015

EBI Project Number: 6215005415

Site Complian	ce Summary
Compliance Status:	COMPLIANT
Site total MPE% of	
FCC general public	4.12 %
allowable limit:	



October 29, 2015

T-Mobile USA Attn: Jason Overbey, RF Manager 35 Griffin Road South Bloomfield, CT 06002

Emissions Analysis for Site: CTNH302A - CTNH302/ Clr Channel/ Prosp.


EBI Consulting was directed to analyze the proposed T-Mobile facility located at **151 Waterbury Road**, **Prospect**, **CT**, for the purpose of determining whether the emissions from the Proposed T-Mobile Antenna Installation located on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter ( $\mu$ W/cm<sup>2</sup>). The number of  $\mu$ W/cm<sup>2</sup> calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits, therefore it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) - (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general public may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general public would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

Public exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter ( $\mu$ W/cm²). The general population exposure limit for the 700 MHz Band is approximately 467  $\mu$ W/cm², and the general population exposure limit for the PCS and AWS bands is 1000  $\mu$ W/cm². Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.





Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure. Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

# **CALCULATIONS**

Calculations were done for the proposed T-Mobile Wireless antenna facility located at **151 Waterbury Road, Prospect, CT**, using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. Since T-Mobile is proposing highly focused directional panel antennas, which project most of the emitted energy out toward the horizon, all calculations were performed assuming a lobe representing the maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was focused at the base of the tower. For this report the sample point is the top of a 6 foot person standing at the base of the tower.

For all calculations, all equipment was calculated using the following assumptions:

- 1) 2 GSM / UMTS channels (PCS Band 1900 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 30 Watts per Channel
- 2) 2 UMTS channels (AWS Band 2100 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 30 Watts per Channel.
- 3) 2 LTE channels (AWS Band 2100 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 60 Watts per Channel.
- 4) 1 LTE channel (700 MHz Band) was considered for each sector of the proposed installation. This channel has a transmit power of 30 Watts.
- 5) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.



- 6) For the following calculations the sample point was the top of a six foot person standing at the base of the tower. The maximum gain of the antenna per the antenna manufactures supplied specifications minus 10 dB was used in this direction. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 7) The antennas used in this modeling are the Ericsson AIR21 (B4A/B2P & B2A/B4P) for 1900 MHz (PCS) and 2100 MHz (AWS) channels and the Commscope LNX-6515DS-VTM for 700 MHz channels. This is based on feedback from the carrier with regards to anticipated antenna selection. The Ericsson AIR21 (B4A/B2P & B2A/B4P) have a maximum gain of 15.9 dBd at their main lobe. The Commscope LNX-6515DS-VTM has a maximum gain of 14.6 dBd at its main lobe. The maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was used for all calculations. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 8) The antenna mounting height centerline of the proposed antennas is 137 feet above ground level (AGL).
- 9) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.

All calculations were done with respect to uncontrolled / general public threshold limits.





# T-Mobile Site Inventory and Power Data

Sector	l A	Sector:	В	Sector	С
Antenna #:	1	Antenna#	1	Antenna#:	1
Make / Model:	Ericsson AIR21 B4A/B2P	Make / Model:	Ericsson AIR21 B4A/B2P	Make / Model	Ericsson AIR21 B4A/B2P
Gain:	15.9 dBd	Gain:	15.9 dBd	Gain:	15.9 dBd
Height (AGL)	137	Height (AGL):	137	Height (AGL)	137
Frequency Bands	2100 MHz (AWS)	Frequency Bands	2100 MHz (AWS)	Frequency Bands	2100 MHz (AWS)
Channel Count	2	Channel Count	2	# PCS Channels:	2
Total TX Power:	120	Total TX Power:	120	# AWS Channels:	120
ERP (W).	4,668.54	ERP(W):	4,668.54	ERP(W):	4,668.54
Antenna A1 MPE%	0.98	Antenna B1 MPE%	0.98	Antenna C1 MPE%	0.98
Antenna #:	2	Antenna #:	2	Antenna #	2
Make / Model	Ericsson AIR21 B2A/B4P	Make / Model:	Ericsson AIR21 B2A/B4P	Make / Model:	Ericsson AIR21 B2A/B4P
Gain:	15.9 dBd	Gain:	15.9 dBd	Gain:	15.9 dBd
Height (AGL)	137	Height (AGL).	137	Height (AGL)	137
Frequency Bands	1900 MHz(PCS) / 2100 MHz (AWS)	Frequency Bands	1900 MHz(PCS) / 2100 MHz (AWS)	Frequency Bands	1900 MHz(PCS) / 2100 MHz (AWS)
Channel Count	4	Channel Count	4	Channel Count	4
Total TX Power	120	Total TX Power:	120	Total TX Power	120
ERP(W)	4,668.54	ERP(W):	4,668.54	ERP(W):	4,668.54
Antenna A2 MPE%	0.98	Antenna B2 MPE%	0.98	Antenna C2 MPE%	0.98
Antenna #:	3	Antenna#:	3	Antenna#:	3
Make / Model	Commscope LNX- 6515DS-VTM	Make / Model	Commscope LNX- 6515DS-VTM	Make / Model:	Commscope LNX- 6515DS-VTM
Gain:	14.6 dBd	Gain:	14.6 dBd	Gain	14.6 dBd
Height (AGL):	137	Height (AGL):	137	Height (AGL)	137
Frequency Bands	700 MHz	Frequency Bands	700 MHz	Frequency Bands	700 MHz
Channel Count	1	Channel Count	1	Channel Count	1
Total TX Power	30	Total TX Power:	30	Total TX Power	30
ERP(W):	865.21	ERP (W)	865.21	ERP (W).	865,21
Antenna A3 MPE%	0.39	Antenna B3 MPE%	0.39	Antenna C3 MPE%	0.39

Site Composite	
Carrier T-Mobile (Per Sector Max)	MPE% 2.34 %
AT&T	1.78 %
Site Total MPE %:	4.12 %

T-Mobile Sector 1 Total:	2.34 %
T-Mobile Sector 2 Total:	2.34 %
T-Mobile Sector 3 Total:	2.34 %
Site Total:	4.12 %





T-Mobile _per sector	# Channels	Watts ERP (Per Channel)	Height (feet)	Total Power Density (µW/cm²)	Frequency (MHz)	Allowable MPE (μW/cm²)	Calculated % MPE
T-Mobile 2100 MHz (AWS) LTE	2	2334.27	137	9.78	2100	1000	0.98 %
T-Mobile 1900 MHz (PCS) GSM/UMTS	2	1167.14	137	4.89	1900	1000	0.49 %
T-Mobile 2100 MHz (AWS) UMTS	2	1167.14	137	4.89	2100	1000	0.49 %
T-Mobile 700 MHz LTE	1	865.21	137	1.51	700	467	0.39 %
				1200		Total:	2.34%





# Summary

All calculations performed for this analysis yielded results that were **within** the allowable limits for general public exposure to RF Emissions.

The anticipated maximum composite contributions from the T-Mobile facility as well as the site composite emissions value with regards to compliance with FCC's allowable limits for general public exposure to RF Emissions are shown here:

T-Mobile Sector	Power Density Value (%)
Sector 1:	2.34 %
Sector 2:	2.34 %
Sector 3:	2.34 %
T-Mobile Per Sector Maximum:	2.34 %
Site Total:	4.12 %
Site Compliance Status:	COMPLIANT

The anticipated composite MPE value for this site assuming all carriers present is **4.12%** of the allowable FCC established general public limit sampled at the ground level. This is based upon values listed in the Connecticut Siting Council database for existing carrier emissions.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.

Scott Heffernan

RF Engineering Director

**EBI Consulting** 

21 B Street

Burlington, MA 01803



# **Structural Analysis Report**

Structure

: 150 ft Monopole

**ATC Site Name** 

: Prospect CT, CT

**ATC Site Number** 

: 282660

**Engineering Number** 

: 63634321

**Proposed Carrier** 

: T-Mobile

**Carrier Site Name** 

: N/A

**Carrier Site Number** 

: CTNH302A

**Site Location** 

: 151 Waterbury Prospect road

Prospect, CT 06712-1228

41.523700,-72.995500

County

: New Haven

Date

: September 2, 2015

Max Usage

: 64%

Result

: Pass

Reviewed by: Scott Wirgau, PE

Prepared By: Temitope O. Olaniyan



JONAL EN

Sep 4 2015 5:05 PM

COA: PEC.0001553

A.T. Engineering Service, PLLC - 3500 Regency Parkway, Suite 100 - Cary, NC 27518 - 919-468-0112 Office - 919-466-5414 Fax - www.americantower.com



Eng. Number 63634321 September 2, 2015

# **Table of Contents**

Introduction	1
Supporting Documents	1
Analysis	1
Conclusion	1
Existing and Reserved Equipment	2
Equipment to be Removed	. 2
Proposed Equipment	2
Structure Usages	3
Foundations	3
Deflection, Twist, and Sway	. 3
Standard Conditions	4
Calculations	Attached



A.T. Engineering Service, PLLC - 3500 Regency Parkway, Suite 100 - Cary, NC 27518 - 919-468-0112 Office - 919-466-5414 Fax - www.americantower.com



Eng. Number 63634321 September 2, 2015 Page 1

# Introduction

The purpose of this report is to summarize results of a structural analysis performed on the 150 ft monopole to reflect the change in loading by T-Mobile.

# **Supporting Documents**

Tower Drawings	ERI Project #25148/001, dated November 13, 2009
Foundation Drawing	ERI Project #25148/002, dated November 13, 2009
Geotechnical Report	FDH Project #09-10144E G1, dated November 9, 2009

# <u>Analysis</u>

The tower was analyzed using American Tower Corporation's tower analysis software. This program considers an elastic three-dimensional model and second-order effects per ANSI/TIA-222.

Basic Wind Speed:	100 mph (3-Second Gust)	
Basic Wind Speed w/ Ice:	50 mph (3-Second Gust) w/ 3/4" radial ice concurrent	
Code:	ANSI/TIA-222-G / 2003 IBC w/ 2005 CT Supplement & 2009 CT Amendment	
Structure Class:	II	
Exposure Category:	В	
Topographic Category:	1	
Crest Height:	0 ft	
Spectral Response:	$Ss = 0.19, S_1 = 0.06$	
Site Class:	D - Stiff Soil	

# Conclusion

Based on the analysis results, the structure meets the requirements per the applicable codes listed above. The tower and foundation can support the equipment as described in this report.

If you have any questions or require additional information, please contact American Tower via email at Engineering@americantower.com. Please include the American Tower site name, site number, and engineering number in the subject line for any questions.

A.T. Engineering Service, PLLC - 3500 Regency Parkway, Suite 100 - Cary, NC 27518 - 919-468-0112 Office - 919-466-5414 Fax - www.americantower.com



Eng. Number 63634321 September 2, 2015 Page 2

# **Existing and Reserved Equipment**

Elevation <sup>1</sup> (ft)		Oh Antonno		B.S. a. a. L.T.	1	Coming	
Mount	RAD	Qty	Antenna	Mount Type	Lines	Carrier	
		3	Raycap DC6-48-60-0-8F				
		6	Ericsson RRUS A2				
	i F	6	Ericsson RRUS 12		(12) 1 5/8" Coax (6) 0.78" 8 AWG 6	AT&T Mobility	
150.0	152.0	1	Ericsson RRUS E2 B29	Laur Drafila Diatforms			
150.0	152.0	1	Ericsson RRUS-32	Low Profile Platform			
		6	Ericsson RRUS-11				
		3	CCI HPA-65R-BUU-H6				
		6	CCI HPA-65R-BUU-H8				
135.0	-	-	-	Low Profile Platform	(12) 1 5/8" Coax	T-Mobile	

# **Equipment to be Removed**

Elevation	on¹ (ft)	Qty	Antenna	Mount Type	Lines	Carrier
Mount	RAD	α,,	7 (110011)10		Elites	
130.0	130.0		RFS APX16PV-16PVL-7-00	-	-	T-Mobile

# **Proposed Equipment**

Elevation <sup>1</sup> (ft)		Ct.	tv Antenna	Mayort Typo	Lines	Carrier
Mount	RAD	Qty	Antenna Mount Type			
		3	Ericsson KRY 112 144/1			
		3	Ericsson RRUS 11 B12		(C) 1 F (0!) Coo.	
135.0	137.0	3	3 Ericsson AIR 21, 1.3 M, B2A B4P -	(6) 1 5/8" Coax (1) 1 1/4" Hybriflex	T-Mobile	
		3	Ericsson AIR 21, 1.3M, B4A B2P		(1)11/4 Hybrillex	
		3	Andrew LNX-6515DS-VTM			

<sup>&</sup>lt;sup>1</sup>Mount elevation is defined as height above bottom of steel structure to the bottom of mount, RAD elevation is defined as center of antenna above ground level (AGL).

Install proposed coax inside the pole shaft.

A.T. Engineering Service, PLIC - 3500 Regency Parkvay, Suite 300 - Cary, NC 27518 - 919-468-0112 Office - 919-468-5414 Fax - www.americantower.com



Eng. Number 63634321 September 2, 2015 Page 3

# Structure Usages

Structural Component	Controlling Usage	Pass/Fail
Anchor Bolts	43%	Pass
Shaft	55%	Pass
Base Plate	55%	Pass
Flanges	64%	Pass

Reaction Component	Analysis Reactions	% of Design
Moment (Kips-Ft)	2,463.0	57%
Axial (Kips)	45.9	4%
Shear (Kips)	22.9	28%

Antenna Elevation (ft)	Antenna	Carrier	Deflection (ft)	Sway (Rotation) (°)
	Ericsson KRY 112 144/1			0.469
	Ericsson RRUS 11 B12			
135.0	Ericsson AIR 21, 1.3 M, B2A B4P	T-Mobile	0.571	
	Ericsson AIR 21, 1.3M, B4A B2P			
	Andrew LNX-6515DS-VTM			

<u>Foundations</u>						Sandonovous del Sovieto del So	
Reaction Co	mponent	Analysis Reactions	% of Design			sa weka kina kata kata kata kata kata kata kata ka	
Moment (	Kips-Ft)	2,463.0	57%			A.S. Carlotte and	
Axial (		45.9	4%			ndddines	
Shear (		22.9	28%			SUSSeminoles	
on geotechnica	and foundation. All foundation	n information, there	nalysis were found to be refore no modification or nave a factor of safety eq	reinforcement of th	e foundation	No-normalizaci espera a ser a mortu acceded consistences	
Antenna Elevation (ft)	An	itenna	Carrier	Deflection (ft)	Sway (Rotation)	#trokkeeponalweiden is hall belande in held be	
	Ericsson K	(RY 112 144/1		(10)		hembassin	
		RRUS 11 B12				Weekleedings	
135.0		1, 1.3 M, B2A B4P	T-Mobile	0.571	0.469	800000000000000000000000000000000000000	
	<del></del>	1, 1.3M, B4A B2P				SEELEGERIA	
	Andrew LN	X-6515DS-VTM				N.W. SHIRWAN	
A.T. Enginee	ing Service, PLLC - 3500	) Regency Parkway, Suite 100 -	· Cary, NC 27518 - 919-468-0112 Office ·	919-466-5414 Fax - www.ame	ricantower.com	di Contracti de Co	



# **Standard Conditions**

All engineering services are performed on the basis that the information used is current and correct. This information may consist of, but is not necessary limited, to:

- -- Information supplied by the client regarding the structure itself, antenna, mounts and feed line loading on the structure and its components, or other relevant information.
- -- Information from drawings in the possession of American Tower Corporation, or generated by field inspections or measurements of the structure.

It is the responsibility of the client to ensure that the information provided to A.T. Engineering Service, PLLC and used in the performance of our engineering services is correct and complete. In the absence of information to the contrary, we assume that all structures were constructed in accordance with the drawings and specifications and that their capacity has not significantly changed from the "as new" condition.


Unless explicitly agreed by both the client and American Tower Corporation, all services will be performed in accordance with the current revision of ANSI/TIA -222. The design basic wind speed will be determined based on the minimum basic wind speed as prescribed in ANSI/TIA-222. Although every effort is taken to ensure that the loading considered is adequate to meet the requirements of all applicable regulatory entities, we can provide no assurance to meet any other local and state codes or requirements. If wind and ice loads or other relevant parameters are to be different from the minimum values recommended by the codes, the client shall specify the exact requirement.

All services are performed, results obtained, and recommendations made in accordance with generally accepted engineering principles and practices. A.T. Engineering Service, PLLC is not responsible for the conclusions, opinions and recommendations made by others based on the information we supply.

A.T. Engineering Service, PLLC - 3500 Regency Parkway, Suite 100 - Cary, NC 27518 - 919-468-0112 Office - 919-466-5414 Fax - www.americantower.com



# STATE OF CONNECTICUT



Ten Franklin Square, New Britain, CT 06051
Phone: (860) 827-2935 Fax: (860) 827-2950
E-Mail: siting.council@ct.gov
www.ct.gov/csc

November 11, 2015

Craig Cody Tower Resource Management, Inc. 16 Chestnut Street Suite 421 Foxboro, MA 02035

RE: **EM-T-MOBILE-115-151105 -** T-Mobile notice of intent to modify an existing telecommunications facility located at 151 Waterbury Road, Prospect, Connecticut.

Dear Mr. Cody:

The Connecticut Siting Council (Council) received a notice of intent to modify the above-referenced facility on November 5, 2015.

According to Section 16-50j-73 of the Regulations of Connecticut State Agencies, "...the owner or operator of any tower and associated equipment claiming such tower and associated equipment is exempt pursuant to section 16-50j-72 of the Regulations of Connecticut State Agencies shall give the Council, the property owner of record, if the property owner of record is different from the owner or operator of the tower and associated equipment, and the chief elected official of the municipality in which the facility is to be located, notice in writing prior to construction."

Council staff has identified the following discrepancy:

• The chief elected official of the municipality in which the facility is located must be a recipient of the exempt modification notice. Currently, only the Town of Prospect is mentioned.

Therefore, the notice of intent to modify an existing telecommunications facility is incomplete at this time. This notice of incompletion shall have the effect of tolling the Federal Communications Commission (FCC) 60-day timeframe in accordance with Paragraph 217 of the FCC Wireless Infrastructure Report and Order issued on October 21, 2014 (FCC 14-153).

The Council recommends that T-Mobile provide information to clarify or fulfill the deficiency noted above.

Thank you for your attention to this matter. Should you have any questions, please feel free to contact me at 860-827-2951.

Very truly yours,

Melanie Bachman

Acting Executive Director

MAB/CH

c: The Honorable Robert Chatfield, Mayor, Town of Prospect Tammy DeLoia, Land Use Inspector, Town of Prospect





# **CRAIG CODY**

16 Chestnut Street, Suite 420 Foxboro, MA 02035 Tel (781) 831-1281 Fax (774) 215-5423

Melanie Bachman Executive Director Connecticut Siting Counsel 10 Franklin Square New Britain, CT 06051

Re: Notice of Exempt Modification – 151 Waterbury Road, Prospect, CT

Dear Ms. Bachman:

Please accept this letter as notification pursuant to R.C.S.A Section 16-50j-73, for construction that constitutes modification pursuant to R.C.S.A Section 16-50j-72(b) and 16-50j-73. In accordance with R.C.S.A Section 16-50j-73, a copy of this submission is being sent to the Town of Prospect. A copy of this submission is also being sent to Richland Towers Management Parkview LLC d/b/a Clear Channel Management Inc., the property owner on which the tower is located.

# T-Mobile Northeast LLC's Proposed Wireless Modifications

T-Mobile as successor in interest to Omnipoint Communications achieved an initial approval from the Siting Council to install antennas as well as related ground equipment and currently maintains this equipment. The facility consists of a One-Hundred and Fifty(150') foot high communications tower within a fenced in compound. T-Mobile now intends to modify the facility as shown on the enclosed plans prepared by Infinigy Engineering and annexed hereto in Exhibit 1. The modifications will consist of adding three (3) new antennas at the existing AGL of One-Hundred and Thirty feet (130'). A structural analysis has been completed for the site and attached as Exhibit 3.

# T-Mobile's Proposed Wireless Modifications Constitutes An "Exempt Modification"

The proposed modification to the above mentioned Facility constitutes an exempt modification of an existing facility provided for in R.C.S.A Section 16-50j-72(b)(2) and Council regulations promulgated pursuant thereto.

- 1) The proposed modification will not result in an increase in the height of the existing tower.
- 2) The modifications will remain entirely within the limits of the leased area. The modifications therefor, will not require the extension of the boundary.

- 3) The proposed modification does not increase the noise levels at the boundary by six(6) decibels or more under normal conditions.
- 4) T-Mobile's proposed facility will not increase the cumulative radio frequency electromagnetic radiation power density at the Tower sites' boundary to or above the standard adopted by the Connecticut Department of Environmental Protection as set forth in Section 22a-162 of the Connecticut General Statutes and MPE limits established by the Federal Communications Commission. A cumulative General Power Density table for T-Mobile's proposed modified facility is included as Exhibit 2.
- 5) The facility has received all municipal zoning approvals and building permits. (Regs., Conn. State Agencies Section 16-50j-72))

For all the foregoing reasons, T-Mobile Northeast LLC respectfully submits that the proposed modifications to the above-referenced telecommunications facility constitutes an exempt modification under R.C.S.A Section 16-50j-72(b)(2)

Respectfully submitted

Craig Cody / 81.831.1281

On behalf of American Tower Corporation

c/o Tower Resource Management, Inc. 16 Chestnut Street, Suite 420 Foxboro, MA 02035

cc: Robert Chatfield Chief Elected Official Town of Prospect American Tower Corporation Richland Towers Management Parkview LLC d/b/a Clear Channel Management Inc.

Site Plan

Power Density Report

# Structural Analysis