Melanie A. Bachman Acting Executive Director Connecticut Siting Council 10 Franklin Square New Britain, CT 06051

Notice of Exempt Modification 151 Waterbury Road, Prospect, CT 06712 N 41.52300600 W -72.99781800

Dear Ms. Bachman:

T-Mobile currently maintains 9 antennas at the 137-foot level of the existing 150 foot monopole at 151 Waterbury Road, Prospect, CT 06712. The tower is owned by SBA Properties, LLC. The property is owned by Clear Channel. T-Mobile now intends to replace the 3 existing antennas with 3 new antennas, for a total of 9 antennas. These antennas would be installed at the 137-foot level of the tower. The Structural Analysis is passing with a 74% ratio.

This facility was approved by the Town of Prospect however they have no record of the original zoning dockets number. Please see the attached email from 6/21/2016 provided by the Town of Prospect Land Use Clerk, Rosalyn Moffo, for confirmation.

Please accept this letter as notification pursuant to Regulations of Connecticut State Agencies $^{\sim}$ 16-50j-73, for construction that constitutes an exempt modification pursuant to R.C.S.A. $^{\sim}$ 16-50j-72(b)(2). In accordance with R.C.S.A. g 16-50j-73, a copy of this letter is being sent to Robert Chatfield – Town of Prospect Mayor – as well as the property owner and the tower owner.

The planned modifications to the facility fall squarely within those activities explicitly provided fox its R.C.S:A. \sim 16-50j-72(b)(2).

- 1. The proposed modifications will not result in an increase in the height of the existing structure.
- 2. The proposed modifications will not require the extension of the site boundary.
- 3. The proposed modifications will not increase noise levels at the facility by six decibels ox more, or to levels that exceed state and local criteria.
- 4. The operation of the replacement antennas will not increase radio frequency emissions at the facility to a level at or above the Federal Communications Commission safety standard,
- 5. The proposed modifications wall not cause a change or alteration in the physical ox environmental characteristics of the site.
- 6. The existing structure and its foundation can support the proposed loading

For the foregoing reasons, T-Mobile respectfully submits that the proposed modifications to the above referenced telecommunications facility constitute an exempt modification under R.C.S.A. \sim 16-SOj-72(b)(2).

Sincerely,

Gregg Shappy
10 Industrial Ave.
Suite 3
Mahwah, NJ 07430
(845) 553-2045
gshappy@transcendwireless.com

Attachments cc: Robert Chatfield – Town of Prospect Mayor Michael Villa - SBA Gary Hess – Clear Channel



RADIO FREQUENCY EMISSIONS ANALYSIS REPORT EVALUATION OF HUMAN EXPOSURE POTENTIAL TO NON-IONIZING EMISSIONS

T-Mobile Existing Facility

Site ID: CTNH302A

Clr Channel/Prospect 151 Waterbury Road Prospect, CT 06712

June 2, 2016

EBI Project Number: 6216002646

Site Compliance Summary						
Compliance Status:	COMPLIANT					
Site total MPE% of FCC general public allowable limit:	21.63 %					



June 2, 2016

T-Mobile USA Attn: Jason Overbey, RF Manager 35 Griffin Road South Bloomfield, CT 06002

Emissions Analysis for Site: CTNH302A – Clr Channel/Prospect

EBI Consulting was directed to analyze the proposed T-Mobile facility located at **151 Waterbury Road**, **Prospect**, **CT**, for the purpose of determining whether the emissions from the Proposed T-Mobile Antenna Installation located on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter (μ W/cm²). The number of μ W/cm² calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits, therefore it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) - (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general public may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general public would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

Public exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter (μ W/cm²). The general population exposure limit for the 700 MHz Band is approximately 467 μ W/cm², and the general population exposure limit for the PCS and AWS bands is 1000 μ W/cm². Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.



Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure. Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

CALCULATIONS

Calculations were done for the proposed T-Mobile Wireless antenna facility located at **151 Waterbury Road, Prospect, CT**, using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. Since T-Mobile is proposing highly focused directional panel antennas, which project most of the emitted energy out toward the horizon, all calculations were performed assuming a lobe representing the maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was focused at the base of the tower. For this report the sample point is the top of a 6 foot person standing at the base of the tower.

For all calculations, all equipment was calculated using the following assumptions:

- 1) 2 GSM channels (PCS Band 1900 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 30 Watts per Channel.
- 2) 2 UMTS channels (PCS Band 1900 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 30 Watts per Channel.
- 3) 2 UMTS channels (AWS Band 2100 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 30 Watts per Channel.
- 4) 2 LTE channels (PCS Band 1900 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 60 Watts per Channel.
- 5) 2 LTE channels (AWS Band 2100 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 60 Watts per Channel.
- 6) 1 LTE channel (700 MHz Band) was considered for each sector of the proposed installation. This channel has a transmit power of 30 Watts.



- 7) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.
- 8) For the following calculations the sample point was the top of a six foot person standing at the base of the tower. The maximum gain of the antenna per the antenna manufactures supplied specifications minus 10 dB was used in this direction. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 9) The antennas used in this modeling are the Ericsson AIR32 B66Aa/B2P & Ericsson AIR32 B4A/B2P for 1900 MHz (PCS) and 2100 MHz (AWS) channels and the Commscope LNX-6515DS-VTM for 700 MHz channels. This is based on feedback from the carrier with regards to anticipated antenna selection. The Ericsson AIR32 B66Aa/B2P & Ericsson AIR32 B4A/B2P have a maximum gain of 15.9 dBd at their main lobe at 1900 MHz & 2100 MHz. The Commscope LNX-6515DS-VTM has a maximum gain of 14.6 dBd at its main lobe at 700 MHz. The maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was used for all calculations. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 10) The antenna mounting height centerline of the proposed antennas is **137 feet** above ground level (AGL).
- 11) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.

All calculations were done with respect to uncontrolled / general public threshold limits.



V/O qdkg'Usg'Kpxgpvqt { 'cpf 'Rqy gt 'F cvc''

Sector:	A	Sector:	В	Sector:	С
Antenna #:	3"	Antenna #:	3"	Antenna #:	3"
Make / Model:	Ericsson AIR32	Make / Model:	Ericsson AIR32	Make / Model:	Ericsson AIR32
	B66Aa/B2P		B66Aa/B2P		B66Aa/B2P
Gain:	15.9 dBd	Gain:	15.9 dBd	Gain:	15.9 dBd
Height (AGL):	137	Height (AGL):	137	Height (AGL):	137
Frequency Bands	1900 MHz(PCS) /	Frequency Bands	1900 MHz(PCS) /	Frequency Bands	1900 MHz(PCS) /
1 3	2100 MHz (AWS)	1 3	2100 MHz (AWS)	1 3	2100 MHz (AWS)
Channel Count	4	Channel Count	4	Channel Count	4
Total TX Power(W):	240	Total TX Power(W):	240	Total TX Power(W):	240
ERP (W):	9,337.08	ERP (W):	9,337.08	ERP (W):	9,337.08
Antenna A1 MPE%	1.96	Antenna B1 MPE%	1.96	Antenna C1 MPE%	1.96
Antenna #:	4"	Antenna #:	4"	Antenna #:	4''
Make / Model:	Ericsson AIR21	Make / Model:	Ericsson AIR21	Make / Model:	Ericsson AIR21
IVIAKC / IVIOUCI.	B4A/B2P	Iviake / Iviouei.	B4A/B2P	IVIAKC / IVIOUCI.	B4A/B2P
Gain:	15.9 dBd	Gain:	15.9 dBd	Gain:	15.9 dBd
Height (AGL):	137	Height (AGL):	137	Height (AGL):	137
Frequency Bands	1900 MHz(PCS) /	Frequency Bands	1900 MHz(PCS) /	Frequency Bands	1900 MHz(PCS) /
1 3	2100 MHz (AWS)	1 2	2100 MHz (AWS)	1 2	2100 MHz (AWS)
Channel Count	6	Channel Count	6	Channel Count	6
Total TX Power(W):	180	Total TX Power(W):	180	Total TX Power(W):	180
ERP (W):	7,002.81	ERP (W):	7,002.81	ERP (W):	7,002.81
Antenna A2 MPE%	1.47	Antenna B2 MPE%	1.47	Antenna C2 MPE%	1.47
Antenna #:	5''	Antenna #:	5''	Antenna #:	5''
Make / Model:	Commscope LNX-	Make / Model:	Commscope LNX-	Make / Model:	Commscope LNX-
Make / Model.	6515DS-VTM	Make / Model:	6515DS-VTM	iviake / iviouei.	6515DS-VTM
Gain:	14.6 dBd	Gain:	14.6 dBd	Gain:	14.6 dBd
Height (AGL):	137	Height (AGL):	137	Height (AGL):	137
Frequency Bands	700 MHz	Frequency Bands	700 MHz	Frequency Bands	700 MHz
Channel Count	1	Channel Count	1	Channel Count	1
Total TX Power(W):	30	Total TX Power(W):	30	Total TX Power(W):	30
ERP (W):	865.21	ERP (W):	865.21	ERP (W):	865.21
Antenna A3 MPE%	0.39	Antenna B3 MPE%	0.39	Antenna C3 MPE%	0.39

T-Mobile Sector 1 Total:	3.81 %
T-Mobile Sector 2 Total:	3.81 %
T-Mobile Sector 3 Total:	3.81 %
Site Total:	21.63 %

V/O qdkg'ar gt 'tigevqt''	% Ej cppgm''	Y cwu'GTR'' *Rgt 'Ej cppgn+''	J gkij√'''''' *hggv+''	VqvcriRqy gt'' F gpuls{'' *µY leo ⁴ +''	Ht gs wgpe{ '' *O J +''	Cmpy cdrg'' O RG'' *µY leo ⁴ +''	Ecnewic vgf " " O RG"
V/O qdkrg'3; 22'O J '*CY U+'NVG''	4''	4556049''	357''	; :"	3; 22"	3222"	20; " "
V/O qdkg'4322'O J '*CY U+'NVG''	4''	4556049''	357"	;0:"	4322"	3222"	20; " "
V/O qdkg'3; 22'O J '*REU+'I UO '''	4''	338906"	357"	60;"	3; 22"	3222"	266;" "
V/O qdkrg'3; 22'O J '*REU+'WO VU''	4''	338906"	357"	60;"	3; 22"	3222"	206;" "
V/O qdkg'4322'O J '*CY U+'WO VU''	4''	338906"	357"	60;"	4322"	3222"	206;" "
V/O qdkrg'922'O J 'NVG''	3"	: 87043"	357"	30 3"	922''	689''	265;" "
11	"	"	"	"	"	Vqven, <''	50 3" "

^{, &#}x27;VJ g'tqverkçınıg'o c{'xct{'d{'2023'' 'lt qo 'tj g'iwo 'qlitj g'lpf kxlf werkenngu'dgecwug'qlitj g'iwo o lpi 'qlit go elpf gt u'



Summary

All calculations performed for this analysis yielded results that were **within** the allowable limits for general public exposure to RF Emissions.

The anticipated maximum composite contributions from the T-Mobile facility as well as the site composite emissions value with regards to compliance with FCC's allowable limits for general public exposure to RF Emissions are shown here:

T-Mobile Sector	Power Density Value (%)
Sector 1:	3.81 %
Sector 2:	3.81 %
Sector 3:	3.81 %
T-Mobile Per Sector	3.81 %
Maximum:	
Site Total:	21.63 %
Site Compliance Status:	COMPLIANT

The anticipated composite MPE value for this site assuming all carriers present is **21.63%** of the allowable FCC established general public limit sampled at the ground level. This is based upon values listed in the Connecticut Siting Council database for existing carrier emissions.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.



Structural Analysis Report

Structure : 150 ft Monopole

ATC Site Name : Prospect CT, CT

ATC Site Number : 282660

Engineering Number : 66383921

Proposed Carrier : T-Mobile

Carrier Site Name : CTNH302/CLRChannel/Prosp

Carrier Site Number : CTNH302A

Site Location : 151 Waterbury Prospect road

Prospect, CT 06712-1228 41.523700,-72.995500

County : New Haven

Date : May 6, 2016

Max Usage : 74%


Result : Pass

Prepared By: Felix Buabeng

Felir Gubery



Reviewed by:



COA: PEC.0001553



Table of Contents

ntroduction	1
Supporting Documents	1
Analysis	1
Conclusion	1
Existing and Reserved Equipment	2
Equipment to be Removed	. 2
Proposed Equipment	2
Structure Usages	3
Foundations	3
Deflection, Twist, and Sway	. 3
Standard Conditions	4
Calculations	Attached



Introduction

The purpose of this report is to summarize results of a structural analysis performed on the 150 ft monopole to reflect the change in loading by T-Mobile.

Supporting Documents

Tower Drawings	ERI Project #25148/001, dated November 13, 2009
Foundation Drawing	ERI Project #25148/002, dated November 13, 2009
Geotechnical Report	FDH Project #09-10144E G1, dated November 9, 2009

Analysis

The tower was analyzed using American Tower Corporation's tower analysis software. This program considers an elastic three-dimensional model and second-order effects per ANSI/TIA-222.

Basic Wind Speed:	100 mph (3-Second Gust)		
Basic Wind Speed w/ Ice:	50 mph (3-Second Gust) w/ 3/4" radial ice concurrent		
Code: ANSI/TIA-222-G / 2003 IBC w/ 2005 CT Supplement & 2009 CT Amendment			
Structure Class:			
Exposure Category:	В		
Topographic Category:	1		
Crest Height:	0 ft		
Spectral Response:	$Ss = 0.19, S_1 = 0.06$		
Site Class:	D - Stiff Soil		

Conclusion

Based on the analysis results, the structure meets the requirements per the applicable codes listed above. The tower and foundation can support the equipment as described in this report.

If you have any questions or require additional information, please contact American Tower via email at Engineering@americantower.com. Please include the American Tower site name, site number, and engineering number in the subject line for any questions.



Existing and Reserved Equipment

Elevation	on¹ (ft)	Ot /	Antonno	Mount Tune	Linos	Corrior	
Mount	RAD	Qty Antenna		Mount Type	Lines	Carrier	
		6	Ericsson RRUS A2				
		3	Ericsson RRUS 32 (50.8 lbs)				
	154.0	6	Ericsson RRUS 12				
	150.0 1 153.0 3	1	Ericsson RRUS E2 B29		(6) 1 5/8" Coax (6) 0.78" 8 AWG 6 (2) 0.39" Fiber Trunk	AT&T Mobility	
150.0		6	Ericsson RRUS-11	Low Profile Platform			
		3	CCI HPA-65R-BUU-H6				
	155.0	6	CCI HPA-65R-BUU-H8				
	152.0	3	Powerwave Allgon TT08-19DB111-001				
	149.0	3	Raycap DC6-48-60-0-8F				
	137.0	3	Ericsson AIR 21, 1.3 M, B2A B4P		(12) 1 F /9" Copy		
137.0)	3	Andrew LNX-6515DS-VTM	l and Donafile Diatforms	(12) 1 5/8" Coax	T N4-1-11-	
157.0		3	Ericsson KRY 112 144/1	Low Profile Platform	(1) 1 1/4" Hybriflex Cable	T-Mobile	
	137.0	3	Ericsson RRUS 11 B12		Cable		

Equipment to be Removed

Elevation	on¹ (ft)	Obi	Qty Antenna Mount Type		Linos	Carrier
Mount	RAD	Qty	Antenna	iviount type	Lines	Carrier
137.0	137.0	3	Ericsson AIR 21, 1.3M, B4A B2P	-	-	T-Mobile

Proposed Equipment

Elevation Mount	on¹ (ft) RAD	Qty	Antenna	Mount Type	Lines	Carrier
137.0	137.0	3	Ericsson AIR32 B66Aa/B2a	-	(1) 1 5/8" Hybriflex	T-Mobile

¹Mount elevation is defined as height above bottom of steel structure to the bottom of mount, RAD elevation is defined as center of antenna above ground level (AGL).

Install proposed coax inside the pole shaft.



Structure Usages

Structural Component	Controlling Usage	Pass/Fail
Anchor Bolts	41%	Pass
Shaft	52%	Pass
Base Plate	65%	Pass
Flanges	74%	Pass
Reinforcement	41%	Pass

Foundations

Reaction Component	Analysis Reactions	% of Usage		
Moment (Kips-Ft)	2,334.0	53%		
Axial (Kips)	66.0	26%		
Shear (Kips)	21.9	16%		

The structure base reactions resulting from this analysis were found to be acceptable through analysis based on geotechnical and foundation information, therefore no modification or reinforcement of the foundation will be required.

Deflection and Sway*

Antenna Elevation (ft)	Antenna	Carrier	Deflection (ft)	Sway (Rotation) (°)
137.0	Ericsson AIR32 B66Aa/B2a	T-Mobile	0.557	0.455

^{*}Deflection and Sway was evaluated considering a design wind speed of 60 mph (3-Second Gust) per ANSI/TIA-222-G



Standard Conditions

All engineering services are performed on the basis that the information used is current and correct. This information may consist of, but is not necessary limited, to:


- -- Information supplied by the client regarding the structure itself, antenna, mounts and feed line loading on the structure and its components, or other relevant information.
- Information from drawings in the possession of American Tower Corporation, or generated by field inspections or measurements of the structure.

It is the responsibility of the client to ensure that the information provided to A.T. Engineering Service, PLLC and used in the performance of our engineering services is correct and complete. In the absence of information to the contrary, we assume that all structures were constructed in accordance with the drawings and specifications and that their capacity has not significantly changed from the "as new" condition.

Unless explicitly agreed by both the client and American Tower Corporation, all services will be performed in accordance with the current revision of ANSI/TIA -222. The design basic wind speed will be determined based on the minimum basic wind speed as prescribed in ANSI/TIA-222. Although every effort is taken to ensure that the loading considered is adequate to meet the requirements of all applicable regulatory entities, we can provide no assurance to meet any other local and state codes or requirements. If wind and ice loads or other relevant parameters are to be different from the minimum values recommended by the codes, the client shall specify the exact requirement.

All services are performed, results obtained, and recommendations made in accordance with generally accepted engineering principles and practices. A.T. Engineering Service, PLLC is not responsible for the conclusions, opinions and recommendations made by others based on the information we supply.

© 2007 - 2016 by ATC IP LLC. All rights reserved.



Job Information

Pole: 282660

Code: ANSI/TIA-222-G

Description:

Client: T-MOBILE Struct Class: II

Location: Prospect CT, CT

Shape: Round Exposure: B Height: 150.00 (ft) Topo: 1

Base Elev (ft): 0.00

Taper: 0.00000(in/ft)

	Sections Properties												
		Overlap		Steel									
Shaft	Length	Accro	ss Flats	Thick	Joint	Length	Taper	Grade					
Section	(†t)	Тор	Bottom	(ın)	Type	(in)	(in/ft)	(ksi)					
1	20.000	60.00	60.00	0.500		0.000	0.000000) 45					
2	20.000	60.00	60.00	0.375	Butt Joint	0.000	0.000000	45					
3	20.000	54.00	54.00	0.375	Butt Joint	0.000	0.000000	45					
4	20.000	48.00	48.00	0.375	Butt Joint	0.000	0.000000	45					
5	20.000	42.00	42.00	0.375	Butt Joint	0.000	0.000000	45					
6	15.000	36.00	36.00	0.375	Butt Joint	0.000	0.000000	45					
7	15.000	36.00	36.00	0.375	Butt Joint	0.000	0.000000	45					
8	20.000	24.00	24.00	0.375	Butt Joint	0.000	0.000000	45					


Discrete Appurtenance									
Attach	Force								
Elev (ft)	Elev (ft)	Qty	Description						
150.000	152.000	3	Powerwave TT08-19DB111-001						
150.000	153.000	6	CCI HPA-65R-BUU-H8						
150.000	153.000	3	CCI HPA-65R-BUU-H6						
150.000	154.000	6	Ericsson RRUS-11						
150.000	154.000	3	Ericsson RRUS 32 (50.8 lbs)						
150.000	154.000	1	Ericsson RRUS E2 B29						
150.000	154.000	6	Ericsson RRUS 12						
150.000	154.000	6	Ericsson RRUS A2						
150.000	150.000	1	Round Low Profile Platform						
150.000	149.000	3	Raycap DC6-48-60-0-8F						
137.000	138.000	3	Andrew LNX-6515DS-VTM						
137.000	137.000	3	Ericsson RRUS 11 B12						
137.000	137.000	3	Ericsson KRY 112 144/1						
137.000	138.000	3	Ericsson AIR32 B66Aa/B2a						
137.000	137.000	1	Round Low Profile Platform						
137.000	138.000	3	Ericsson AIR 21, 1.3 M, B2A B4						


	Linear Appurtenance											
Elev	(ft)		Exposed									
From	То	Description	To Wind									
0.000	137.0	1 1/4" Hybriflex	No									
0.000	137.0	1 5/8" Coax	No									
0.000	137.0	1 5/8" Hybriflex	No									
0.000	150.0	0.39" Fiber Trunk	No									
0.000	150.0	0.78" 8 AWG 6	No									
0.000	150.0	1 5/8" Coax	No									


	Load Cases
1.2D + 1.6W	100 mph with No Ice
0.9D + 1.6W	100 mph with No Ice (Reduced DL)
1.2D + 1.0Di + 1.0Wi	50 mph with 0.75 in Radial Ice
(1.2 + 0.2Sds) * DL + E	Seismic Equivalent Lateral Forces Method
(1.2 + 0.2Sds) * DL + E	Seismic Equivalent Modal Analysis Method
1.0D + 1.0W	Serviceability 60 mph

Reactions										
Moment Shear Axial Load Case (kip-ft) (kip) (kip)										
1.2D + 1.6W	2333.99	21.91	44.83							
0.9D + 1.6W	2321.79	21.91	33.62							
1.2D + 1.0Di + 1.0Wi	612.74	6.14	66.01							
(1.2 + 0.2Sds) * DL + E ELFM	241.17	2.08	44.24							
(1.2 + 0.2Sds) * DL + E EM AM	328.49	2.72	44.24							
1.0D + 1.0W	523.31	4.93	37.37							

Dish Deflections									
Load Case	Attach Elev (ft)	Deflection (in)	Rotation (deg)						
	0.00	0.000	0.000						







Site Name: Prospect CT, CT Engineering Number: 66383921 5/6/2016 9:41:26 AM

T-MOBILE Customer:

Analysis Parameters

New Haven County, CT Location:

Height (ft): ANSI/TIA-222-G Code: 150 Shape: Round Base Diameter (in): 60.00 Pole Type: Top Diameter (in): 24.00 Stepped 0.000 Pole Manfacturer: ERI Taper (in/ft):

Ice & Wind Parameters

Structure Class: Ш **Design Wind Speed Without Ice:** 100 mph 50 m ph **Exposure Category:** В Design Wind Speed With Ice: **Topographic Category:** 1 **Operational Wind Speed:** 60 mph Crest Height: 0.0 ft Design Ice Thickness: 0.75 in

Seismic Parameters

Equivalent Modal Analysis & Equivalent Lateral Force Methods **Analysis Method:**

Site Class: D - Stiff Soil

Period Based on Rayleigh Method (sec): 1.60

6 Cs: 0.043 T_I (sec): 1.3 p: C Max: S_s: 0.188 S₁: 0.064 0.043 C Min: F_a: 1.600 F_v: 2.400 0.030

0.201 0.102 S_{ds}: S_{d1}:

Load Cases

1.2D + 1.6W 100 mph with No Ice

0.9D + 1.6W100 mph with No Ice (Reduced DL) 1.2D + 1.0Di + 1.0Wi

50 mph with 0.75 in Radial Ice

(1.2 + 0.2Sds) * DL + E ELFM Seismic Equivalent Lateral Forces Method (1.2 + 0.2 Sds) * DL + E EMAMSeismic Equivalent Modal Analysis Method

1.0D + 1.0W Serviceability 60 mph Site Name: Prospect CT, CT Engineering Number: 66383921 5/6/2016 9:41:26 AM

Customer: T-MOBILE

Sha	ft Sec	tion	Prop	ertie				Bottom				Тор							
Sect Info	Length (ft)			Joint Type	Slip Joint Len (in)	Weight (lb)	Dia (in)	Elev (ft)	Area (in²)	lx (in ⁴)	W/t Ratio	D/t Ratio	Dia (in)	Elev (ft)	Area (in²)	lx (in ⁴)	W/t Ratio	D/t Ratio	Taper (in/ft)
1-R	20.000	0.5000	45		0.00	6,361	60.00	0.00	93.46	41391.7	0.00	120.00	60.00	20.00	93.46	41391.7	0.00	120.00	0.000000
2-R	20.000	0.3750	45	Butt	0.00	4,780	60.00	20.00	70.24	31239.9	0.00	160.00	60.00	40.00	70.24	31239.9	0.00	160.00	0.000000
3-R	20.000	0.3750	45	Butt	0.00	4,299	54.00	40.00	63.18	22726.1	0.00	144.00	54.00	60.00	63.18	22726.1	0.00	144.00	0.000000
4-R	20.000	0.3750	45	Butt	0.00	3,818	48.00	60.00	56.11	15919.5	0.00	128.00	48.00	80.00	56.11	15919.5	0.00	128.00	0.000000
5-R	20.000	0.3750	45	Butt	0.00	3,337	42.00	80.00	49.04	10628.9	0.00	112.00	42.00	100.00	49.04	10628.9	0.00	112.00	0.000000
6-R	15.000	0.3750	45	Butt	0.00	2,142	36.00	100.00	41.97	6663.3	0.00	96.00	36.00	115.00	41.97	6663.3	0.00	96.00	0.000000
7-R	15.000	0.3750	45	Butt	0.00	2,142	36.00	115.00	41.97	6663.3	0.00	96.00	36.00	130.00	41.97	6663.3	0.00	96.00	0.000000
8-R	20.000	0.3750	45	Butt	0.00	1,894	24.00	130.00	27.83	1943.3	0.00	64.00	24.00	150.00	27.83	1943.3	0.00	64.00	0.000000
			Sł	naft We	eight	28,775													

Discrete Appurtenance Properties

Attach Elev (ft)	Description	Qty	Weight (lb)	No Ice EPAa (sf)	Orientation Factor	Weight (lb)	– Ice EPAa (sf)	Orientation Factor	Distance From Face (ft)	Vert Ecc (ft)
150.00	CCI HPA-65R-BUU-H6	3	51.00	9.660	0.83	298.62	11.024	0.83	0.000	3.000
150.00	CCI HPA-65R-BUU-H8	6	68.00	12.980	0.79	358.48	14.592		0.000	3.000
150.00	Ericsson RRUS 12	6	50.00	3.150	0.67	145.19	3.863	0.67	0.000	4.000
150.00	Ericsson RRUS 32 (50.8 lbs)	3	50.80	2.690	0.67	136.07	3.416	0.67	0.000	4.000
150.00	Ericsson RRUS A2	6	15.00	1.600	0.50	61.37	2.131	0.50	0.000	4.000
150.00	Ericsson RRUS E2 B29	1	60.00	3.150	0.67	155.19	3.863	0.67	0.000	4.000
150.00	Ericsson RRUS-11	6	55.00	3.790	0.67	160.06	4.582	0.67	0.000	4.000
150.00	Powerwave TT08-19DB111-	3	22.00	0.920	0.67	57.14	1.203	0.67	0.000	2.000
150.00	Raycap DC6-48-60-0-8F	3	32.80	1.190	1.00	120.73	2.669	1.00	0.000	-1.000
150.00	Round Low Profile Platform	1	1500.00	21.700	1.00	2,148.13	40.906	1.00	0.000	0.000
137.00	Andrew LNX-6515DS-VTM	3	51.30	11.430	0.84	311.69	13.077	0.84	0.000	1.000
137.00	Ericsson AIR 21, 1.3 M, B2A	3	83.00	6.050	0.86	250.08	7.137	0.86	0.000	1.000
137.00	Ericsson AIR32 B66Aa/B2a	3	132.20	6.510	0.86	313.44	7.626	0.86	0.000	1.000
137.00	Ericsson KRY 112 144/1	3	11.00	0.410	0.50	27.15	0.631	0.50	0.000	0.000
137.00	Ericsson RRUS 11 B12	3	50.70	2.790	0.67	136.08	3.462	0.67	0.000	0.000
137.00	Round Low Profile Platform	1	1500.00	21.700	1.00	2,142.89	40.751	1.00	0.000	0.000
	Totals	54	5642.40		13,74	49.75		Number	of Loadings:	16

Linear Appurtenance Properties

Elev From (ft)	Elev To (tt)	Qty Description	Coax Diameter (in)	Coax Weight (lb/ft)	Flat	Projected Width (in)	Exposed To Wind	Carrier
0.00	150.00	2 0.39" Fiber Trunk	0.39	0.06	N	0.00	N	AT&T Mobility
0.00	150.00	6 0.78" 8 AWG 6	0.78	0.59	N	0.00	N	AT&T Mobility
0.00	150.00	6 1 5/8" Coax	1.98	0.82	N	0.00	N	AT&T Mobility
0.00	137.00	1 1 1/4" Hybriflex	1.54	1.00	N	0.00	N	T-Mobile
0.00	137.00	12 1 5/8" Coax	1.98	0.82	N	0.00	N	T-Mobile
0.00	137 00	1 1 5/8" Hybriflex Cable	1 98	1 30	N	0.00	N	T-Mohile

 Site Number:
 282660

 Code:
 ANSI/TIA-222-G

 © 2007 - 2016 by ATC IP LLC.
 All rights reserved.

Site Name: Prospect CT, CT Engineering Number: 66383921 5/6/2016 9:41:26 AM

Customer: T-MOBILE

<u>Segn</u>	nent Properties	(Max L	en : 5.1	ft)								
Seg To	ор	This	Flat									
Elev		Thick	Dia	Area	lx .	W/t	_D/t	Гy	S	Z	Weight	
(ft)	Description	(in)	(in)	(in²)	(in⁴)	Ratio	Ratio	(ksi)	(in ³)	(in³)	(lb)	
0.00		0.5000	60.000	93.462	41,391.7	0.00	120.00	39.2	1379.	1770.	0.0	
5.00			60.000		41,391.7	0.00					1,590.2	
10.00		0.5000	60.000	93.462	41,391.7	0.00	120.00	39.2	1379.	1770.	1,590.2	
15.00		0.5000	60.000	93.462	41,391.7	0.00	120.00	39.2	1379.	1770.	1,590.2	
20.00	Top - Section 1		60.000		41,391.7	0.00					1,590.2	
20.00	Bot - Section 2		60.000		31,239.9	0.00	160.00					
25.00			60.000		31,239.9	0.00					1,195.1	
30.00			60.000		31,239.9	0.00					1,195.1	
35.00			60.000		31,239.9	0.00					1,195.1	
40.00	Top - Section 2	0.3750			31,239.9	0.00					1,195.1	
40.00	Bot - Section 3		54.000		22,726.1	0.00	144.00				4 074 0	
45.00			54.000		22,726.1	0.00					1,074.9	
50.00			54.000		22,726.1	0.00					1,074.9	
55.00 60.00	Top - Section 3		54.000 54.000		22,726.1 22,726.1	0.00 0.00					1,074.9 1,074.9	
60.00	Bot - Section 4	0.3750			15,919.5	0.00	128.00				1,074.9	
65.00	Bot - Section 4		48.000		15,919.5	0.00	128.00				954.6	
70.00			48.000		15,919.5	0.00	128.00				954.6	
75.00			48.000		15,919.5	0.00	128.00				954.6	
80.00	Top - Section 4		48.000		15,919.5	0.00	128.00				954.6	
80.00	Bot - Section 5	0.3750			10,628.9	0.00	112.00				00	
85.00			42.000		10,628.9	0.00	112.00				834.3	
90.00			42.000		10,628.9	0.00	112.00				834.3	
95.00			42.000		10,628.9	0.00	112.00				834.3	
100.0	Top - Section 5	0.3750	42.000		10,628.9	0.00	112.00	39.8	506.1	649.8	834.3	
100.0	Bot - Section 6	0.3750	36.000	41.970	6,663.3	0.00	96.00	41.4	370.2	475.9		
105.0		0.3750		41.970	6,663.3	0.00			370.2		714.1	
110.0		0.3750		41.970	6,663.3	0.00			370.2		714.1	
115.0	Top - Section 6	0.3750		41.970	6,663.3	0.00			370.2		714.1	
115.0	Bot - Section 7	0.3750		41.970	6,663.3	0.00			370.2			
120.0		0.3750		41.970	6,663.3	0.00			370.2		714.1	
125.0		0.3750		41.970	6,663.3	0.00			370.2		714.1	
130.0	Top - Section 7	0.3750		41.970	6,663.3	0.00			370.2		714.1	
130.0	Bot - Section 8	0.3750		27.833	1,943.3	0.00			161.9		470 5	
135.0		0.3750		27.833	1,943.3	0.00			161.9		473.5	
137.0		0.3750		27.833	1,943.3	0.00			161.9		189.4	
140.0		0.3750		27.833	1,943.3	0.00			161.9		284.1	
145.0		0.3750		27.833	1,943.3	0.00 0.00			161.9		473.5	
150.0		0.3750	24.000	27.833	1,943.3	0.00	04.00	45.0	161.9		473.5	
										2	28,774.9	

Site Name: Prospect CT, CT Engineering Number: 66383921 5/6/2016 9:41:26 AM

Customer: T-MOBILE

Load Case: 1.2D + 1.6W 100 mph with No Ice 19 Iterations

Gust Response Factor: 1.10 Wind Importance Factor: 1.00

Dead Load Factor: 1.20 Wind Load Factor: 1.60

Applied Segment Forces Summary

		Shaft F	Forces		Discret	e Forces		Linear F	orces		Sum o	f Forces	
Seg			Dead		Torsion	Moment	Dead		Dead				Moment
Elev		Wind FX	Load	Wind FX		MZ	Load	Wind FX	Load	Wind FX	Load	MY	MZ
(ft)	Description	(lb)	(lb)	(lb)	(lb-ft)	(lb-ft)			(lb)	(lb)	(lb)		
(11)	Description	(10)	(ID)	(ID)	(ID-II)	(16-11)	(lb)	(lb)	(ID)	(ID)	(ID)	(lb-ft)	(lb)
0.00		224.7	0.0					0.0	0.0	224.7	0.0	0.0	0.0
5.00		449.4	1,908.2					0.0	124.3	449.4	2,032.5	0.0	0.0
10.00		449.4	1,908.2					0.0	124.3	449.4	2,032.5	0.0	0.0
15.00		449.4	1,908.2					0.0	124.3	449.4	2,032.5	0.0	0.0
20.00	Top - Section 1	449.4	1,908.2					0.0	124.3	449.4	2,032.5	0.0	0.0
25.00		449.4	1,434.1					0.0	124.3	449.4	1,558.5	0.0	0.0
30.00		454.8	1,434.1					0.0	124.3	454.8	1,558.5	0.0	0.0
35.00		469.8	1,434.1					0.0	124.3	469.8	1,558.5	0.0	0.0
40.00	Top - Section 2	463.3	1,434.1					0.0	124.3	463.3	1,558.5	0.0	0.0
45.00		454.4	1,289.8					0.0	124.3	454.4	1,414.2	0.0	0.0
50.00		468.3	1,289.8					0.0	124.3	468.3	1,414.2	0.0	0.0
55.00		481.3	1,289.8					0.0	124.3	481.3	1,414.2	0.0	0.0
60.00	Top - Section 3	465.7	1,289.8					0.0	124.3	465.7	1,414.2	0.0	0.0
65.00		448.7	1,145.5					0.0	124.3	448.7	1,269.8	0.0	0.0
70.00		458.4	1,145.5					0.0	124.3	458.4	1,269.8	0.0	0.0
75.00		467.5	1,145.5					0.0	124.3	467.5	1,269.8	0.0	0.0
80.00	Top - Section 4	446.2	1,145.5					0.0	124.3	446.2	1,269.8	0.0	0.0
85.00	-	424.0	1,001.2					0.0	124.3	424.0	1,125.5	0.0	0.0
90.00		430.9	1,001.2					0.0	124.3	430.9	1,125.5	0.0	0.0
95.00		437.7	1,001.2					0.0	124.3	437.7	1,125.5	0.0	0.0
100.00	Top - Section 5	412.2	1,001.2					0.0	124.3	412.2	1,125.5	0.0	0.0
105.00	•	386.0	856.9					0.0	124.3	386.0	981.2	0.0	0.0
110.00		391.2	856.9					0.0	124.3	391.2	981.2	0.0	0.0
115.00	Top - Section 6	396.2	856.9					0.0	124.3	396.2	981.2	0.0	0.0
120.00	•	401.0	856.9					0.0	124.3	401.0	981.2	0.0	0.0
125.00		405.7	856.9					0.0	124.3	405.7	981.2	0.0	0.0
130.00	Top - Section 7	341.6	856.9					0.0	124.3	341.6	981.2	0.0	0.0
135.00	•	192.9	568.2					0.0	124.3	192.9	692.6	0.0	0.0
137.00	Appertunance(s)	139.0	227.3	3,505.6	0.0	2,270.9	2,981.5	0.0	49.7	3,644.6	3,258.5	0.0	0.0
140.00		224.0	340.9	0,00010	•	_,	_,000	0.0	30.9	224.0	371.8	0.0	0.0
145.00		282.2	568.2					0.0	51.5	282.2	619.7	0.0	0.0
150.00	Appertunance(s)	141.8	568.2	6,046.2	0.0	15,974.3	3,789.4		51.5	6,188.0	4,409.1	0.0	0.0
								То	tals:	22,108.4	44,840.9	0.00	0.00

Site Name: Prospect CT, CT Engineering Number: 66383921 5/6/2016 9:41:27 AM

Customer: T-MOBILE

Load Case: 1.2D + 1.6W 100 mph with No Ice 19 Iterations

Gust Response Factor: 1.10 Wind Importance Factor: 1.00

Dead Load Factor: 1.20 Wind Load Factor: 1.60

Calculated Forces

Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	t phi Pn (kips)	phi Vn (kips)	phi Tn (ft-kips)	phi Mn (ft-kips)	Total Deflect (in)	Rotation (deg)	Ratio
0.00	-44.83	-21.91	0.00	-2,333.99	0.00	2,333.99	3 293 92	1 646 96	8,093.29	5 174 22	0.00	0.00	0.465
5.00	-42.76	-21.52	0.00	-2,224.43	0.00	2,224.43		•	8,093.29	•	0.04	-0.08	0.443
10.00	-40.71	-21.12	0.00	-2.116.82	0.00	2.116.82			8,093.29		0.16	-0.15	0.422
15.00	-38.65	-20.71	0.00	-2,011.23	0.00	2,011.23			8,093.29		0.36	-0.22	0.401
20.00	-36.60	-20.29	0.00	-1,907.69	0.00	1,907.69	,		8,093.29		0.63	-0.29	0.380
20.00	-36.60	-20.29	0.00	-1,907.69	0.00	1,907.69	,	,	5,751.12	,	0.63	-0.29	0.517
25.00	-35.02	-19.88	0.00	-1,806.23	0.00	1.806.23	,		5,751.12		0.97	-0.36	0.490
30.00	-33.43	-19.46	0.00	-1,706.84	0.00	1,706.84	,	,	5,751.12	,	1.39	-0.44	0.463
35.00	-31.86	-19.02	0.00	-1,609.55	0.00	1,609.55	,	,	5,751.12	,	1.89	-0.51	0.437
40.00	-30.28	-18.57	0.00	-1.514.47	0.00	1.514.47			5.751.12		2.46	-0.58	0.411
40.00	-30.28	-18.57	0.00	-1,514.47	0.00	1,514.47			4,744.89		2.46	-0.58	0.502
45.00	-28.85	-18.14	0.00	-1,421.60	0.00	1,421.60			4,744.89		3.10	-0.65	0.472
50.00	-27.41	-17.70	0.00	-1,330.89	0.00	1,330.89		,	4,744.89	,	3.83	-0.73	0.442
55.00	-25.98	-17.23	0.00	-1,242.40	0.00	1,242.40			4,744.89		4.64	-0.82	0.413
60.00	-24.55	-16.78	0.00	-1,156.24	0.00	1,156.24		1,069.86	4,744.89	3,103.93	5.54	-0.89	0.384
60.00	-24.55	-16.78	0.00	-1,156.24	0.00	1,156.24	1,948.48	974.24	3,834.02	2,471.99	5.54	-0.89	0.481
65.00	-23.27	-16.34	0.00	-1,072.35	0.00	1,072.35	1,948.48		3,834.02		6.51	-0.96	0.446
70.00	-21.98	-15.89	0.00	-990.65	0.00	990.65	1,948.48	974.24	3,834.02	2,471.99	7.56	-1.05	0.412
75.00	-20.70	-15.43	0.00	-911.18	0.00	911.18	1,948.48	974.24	3,834.02	2,471.99	8.71	-1.14	0.379
80.00	-19.42	-14.99	0.00	-834.02	0.00	834.02	1,948.48	974.24	3,834.02	2,471.99	9.94	-1.22	0.348
80.00	-19.42	-14.99	0.00	-834.02	0.00	834.02	1,757.14	878.57	3,018.53	1,911.67	9.94	-1.22	0.448
85.00	-18.28	-14.56	0.00	-759.10	0.00	759.10	1,757.14	878.57	3,018.53	1,911.67	11.26	-1.29	0.408
90.00	-17.14	-14.13	0.00	-686.28	0.00	686.28	1,757.14	878.57	3,018.53	1,911.67	12.66	-1.38	0.369
95.00	-16.01	-13.69	0.00	-615.61	0.00	615.61	1,757.14	878.57	3,018.53	1,911.67	14.15	-1.47	0.331
100.00	-14.88	-13.27	0.00	-547.15	0.00	547.15	1,757.14	878.57	3,018.53	1,911.67	15.73	-1.55	0.295
100.00	-14.88	-13.27	0.00	-547.15	0.00	547.15	1,565.64	782.82	2,298.42	1,422.98	15.73	-1.55	0.394
105.00	-13.89	-12.88	0.00	-480.81	0.00	480.81	1,565.64	782.82	2,298.42	1,422.98	17.39	-1.62	0.347
110.00	-12.90	-12.48	0.00	-416.43	0.00	416.43	,	782.82	2,298.42	1,422.98	19.14	-1.71	0.301
115.00	-11.92	-12.07	0.00	-354.04	0.00	354.04	1,565.64	782.82	2,298.42	1,422.98	20.98	-1.79	0.257
115.00	-11.92	-12.07	0.00	-354.04	0.00	354.04	1,565.64	782.82	2,298.42	1,422.98	20.98	-1.79	0.257
120.00	-10.94	-11.65	0.00	-293.71	0.00	293.71	1,565.64		2,298.42		22.89	-1.86	0.214
125.00	-9.96	-11.22	0.00	-235.48	0.00	235.48	,		2,298.42		24.88	-1.92	0.172
130.00	-8.98	-10.85	0.00	-179.40	0.00	179.40			2,298.42	,	26.91	-1.96	0.132
130.00	-8.98	-10.85	0.00	-179.40	0.00	179.40			1,091.62	660.47	26.91	-1.96	0.280
135.00	-8.29	-10.64	0.00	-125.15	0.00	125.15	1,127.22		1,091.62	660.47	28.99	-2.00	0.197
137.00	-5.16	-6.88	0.00	-101.61	0.00	101.61	1,127.22		1,091.62	660.47	29.83	-2.03	0.159
140.00	-4.79	-6.65	0.00	-80.96	0.00	80.96	1,127.22		1,091.62	660.47	31.12	-2.07	0.127
145.00	-4.18	-6.35	0.00	-47.71	0.00	47.71	1,127.22		1,091.62	660.47	33.32	-2.12	0.076
150.00	0.00	-6.19	0.00	-15.97	0.00	15.97	1,127.22	563.61	1,091.62	660.47	35.55	-2.14	0.024

Site Name: Prospect CT, CT Engineering Number: 66383921 5/6/2016 9:41:27 AM

Customer: T-MOBILE

<u>Load Case:</u> 0.9D + 1.6W 100 mph with No Ice (Reduced DL) 19 Iterations

Gust Response Factor: 1.10 Wind Importance Factor: 1.00

Dead Load Factor: 0.90 Wind Load Factor: 1.60

Applied Segment Forces Summary

		Shaft I	Forces		Discre	te Forces		Linear F	orces		Sum o	f Forces	
Seg			Dead	•	Torsion	Moment	Dead		Dead	•	Dead	Torsion	Moment
Elev		Wind FX	Load	Wind FX	ΜY	ΜZ	Load	Wind FX	Load	Wind FX	Load	MY	ΜZ
(ft)	Description	(lb)	(lb)	(lb)	(lb-ft)	(lb-ft)	(lb)	(lb)	(lb)	(lb)	(lb)	(lb-ft)	(lb)
0.00		224.7	0.0					0.0	0.0	224.7	0.0	0.0	0.0
5.00		449.4	1,431.1					0.0	93.2	449.4	1,524.4	0.0	0.0
10.00		449.4	1,431.1					0.0	93.2	449.4	1,524.4	0.0	0.0
15.00		449.4	1,431.1					0.0	93.2	449.4	1,524.4	0.0	0.0
20.00	Top - Section 1	449.4	1,431.1					0.0	93.2	449.4	1,524.4	0.0	0.0
25.00		449.4	1,075.6					0.0	93.2	449.4	1,168.9	0.0	0.0
30.00		454.8	1,075.6					0.0	93.2	454.8	1,168.9	0.0	0.0
35.00		469.8	1,075.6					0.0	93.2	469.8	1,168.9	0.0	0.0
40.00	Top - Section 2	463.3	1,075.6					0.0	93.2	463.3	1,168.9	0.0	0.0
45.00	•	454.4	967.4					0.0	93.2	454.4	1,060.6	0.0	0.0
50.00		468.3	967.4					0.0	93.2	468.3	1,060.6	0.0	0.0
55.00		481.3	967.4					0.0	93.2	481.3	1,060.6	0.0	
60.00	Top - Section 3	465.7	967.4					0.0	93.2	465.7	1,060.6	0.0	0.0
65.00	•	448.7	859.1					0.0	93.2	448.7	952.4	0.0	
70.00		458.4	859.1					0.0	93.2	458.4	952.4	0.0	
75.00		467.5	859.1					0.0	93.2	467.5	952.4	0.0	
80.00	Top - Section 4	446.2	859.1					0.0	93.2	446.2	952.4	0.0	
85.00	•	424.0	750.9					0.0	93.2	424.0	844.1	0.0	0.0
90.00		430.9	750.9					0.0	93.2	430.9	844.1	0.0	
95.00		437.7	750.9					0.0	93.2	437.7	844.1	0.0	
100.00	Top - Section 5	412.2	750.9					0.0	93.2	412.2	844.1	0.0	
105.00	•	386.0	642.7					0.0	93.2	386.0	735.9	0.0	
110.00		391.2	642.7					0.0	93.2	391.2	735.9	0.0	
115.00	Top - Section 6	396.2	642.7					0.0	93.2	396.2	735.9	0.0	
120.00	•	401.0	642.7					0.0	93.2	401.0	735.9	0.0	
125.00		405.7	642.7					0.0	93.2	405.7	735.9	0.0	
130.00	Top - Section 7	341.6	642.7					0.0	93.2	341.6	735.9	0.0	
135.00		192.9	426.2					0.0	93.2	192.9	519.4	0.0	
137.00	Appertunance(s)	139.0	170.5	3,505.6	0.	0 2,270.9	2,236.1	0.0	37.3	3,644.6	2,443.9	0.0	
140.00	(o)	224.0	255.7	0,000.0	0.	J, J.J	_,_00.1	0.0	23.2	224.0	278.9	0.0	
145.00		282.2	426.2					0.0	38.6	282.2	464.8	0.0	
150.00	Appertunance(s)	141.8	426.2	6,046.2	0.	0 15,974.3	2,842.0		38.6	6,188.0	3,306.8	0.0	
								То	tals:	22,108.4	33,630.6	0.00	0.00

Site Name: Prospect CT, CT Engineering Number: 66383921 5/6/2016 9:41:28 AM

Customer: T-MOBILE

<u>Load Case:</u> 0.9D + 1.6W 100 mph with No Ice (Reduced DL) 19 Iterations

Gust Response Factor: 1.10 Wind Importance Factor: 1.00

Dead Load Factor: 0.90 Wind Load Factor: 1.60

Calculated Forces

Seg	Pu	Vu	Tu	Mu	Mu	Resultant	phi	phi	phi	phi	Total		
Elev	FY (-)	FX (-)	MY	MZ	MX	Moment	Pn	۷n	Tn	Mn		Rotation	
(ft)	(kips)	(kips)	(ft-kips)	(ft-kips)		(ft-kips)	(kips)	(kips)		(ft-kips)	(in)	(deg)	Ratio
(11)	(Kips)	(Kips)	(it kips)	(it kips)	(it kips)	(it kips)	(Kips)	(Kips)	(it kips)	(it kips)	("'')	(acg)	Natio
0.00	-33.62	-21.91	0.00	-2,321.79	0.00	2,321.79	3,293.92	1,646.96	8,093.29	5,174.22	0.00	0.00	0.459
5.00	-32.06	-21.50	0.00	-2,212.26	0.00	2,212.26	3,293.92	1,646.96	8,093.29	5,174.22	0.04	-0.08	0.437
10.00	-30.51	-21.08	0.00	-2,104.77	0.00	2,104.77	3,293.92	1,646.96	8,093.29	5,174.22	0.16	-0.15	0.416
15.00	-28.97	-20.66	0.00	-1,999.35	0.00	1,999.35			8,093.29		0.36	-0.22	0.395
20.00	-27.42	-20.24	0.00	-1,896.03	0.00	1,896.03	3,293.92	1,646.96	8,093.29	5,174.22	0.63	-0.29	0.375
20.00	-27.42	-20.24	0.00	-1,896.03	0.00	1,896.03	2,330.87	1,165.43	5,751.12	3,807.50	0.63	-0.29	0.510
25.00	-26.23	-19.82	0.00	-1,794.84	0.00	1,794.84	2,330.87	1,165.43	5,751.12	3,807.50	0.97	-0.35	0.483
30.00	-25.04	-19.39	0.00	-1,695.75	0.00	1,695.75	2,330.87	1,165.43	5,751.12	3,807.50	1.38	-0.43	0.456
35.00	-23.85	-18.94	0.00	-1,598.82	0.00	1,598.82			5,751.12		1.87	-0.51	0.430
40.00	-22.66	-18.49	0.00	-1,504.13	0.00	1,504.13	2,330.87	1,165.43	5,751.12	3,807.50	2.44	-0.58	0.405
40.00	-22.66	-18.49	0.00	-1,504.13	0.00	1,504.13	2,139.71	1,069.86	4,744.89	3,103.93	2.44	-0.58	0.495
45.00	-21.58	-18.05	0.00	-1,411.68	0.00	1,411.68	2,139.71	1,069.86	4,744.89	3,103.93	3.09	-0.64	0.465
50.00	-20.50	-17.60	0.00	-1,321.41	0.00	1,321.41	2,139.71	1,069.86	4,744.89	3,103.93	3.81	-0.73	0.436
55.00	-19.42	-17.13	0.00	-1,233.40	0.00	1,233.40	2,139.71	1,069.86	4,744.89	3,103.93	4.62	-0.81	0.407
60.00	-18.35	-16.67	0.00	-1,147.73	0.00	1,147.73	2,139.71	1,069.86	4,744.89	3,103.93	5.50	-0.88	0.379
60.00	-18.35	-16.67	0.00	-1,147.73	0.00	1,147.73	1,948.48	974.24	3,834.02	2,471.99	5.50	-0.88	0.474
65.00	-17.38	-16.24	0.00	-1,064.36		1,064.36	1,948.48	974.24	3,834.02	2,471.99	6.47	-0.95	0.440
70.00	-16.41	-15.79	0.00	-983.18	0.00	983.18	1,948.48	974.24	3,834.02	2,471.99	7.52	-1.05	0.406
75.00	-15.45	-15.32	0.00	-904.25	0.00	904.25	1,948.48	974.24	3,834.02	2,471.99	8.66	-1.13	0.374
80.00	-14.49	-14.88	0.00	-827.64	0.00	827.64	1,948.48	974.24	3,834.02	2,471.99	9.88	-1.21	0.342
80.00	-14.49	-14.88	0.00	-827.64	0.00	827.64	1,757.14		3,018.53		9.88	-1.21	0.441
85.00	-13.63	-14.45	0.00	-753.27	0.00	753.27	1,757.14	878.57	3,018.53	1,911.67	11.18	-1.28	0.402
90.00	-12.77	-14.02	0.00	-681.01	0.00	681.01	1,757.14	878.57	3,018.53	1,911.67	12.57	-1.37	0.364
95.00	-11.92	-13.58	0.00	-610.89		610.89	1,757.14	878.57	3,018.53	1,911.67	14.06	-1.46	0.327
100.00	-11.07	-13.16	0.00	-542.98	0.00	542.98	1,757.14	878.57	3,018.53	1,911.67	15.63	-1.54	0.291
100.00	-11.07	-13.16	0.00	-542.98		542.98	1,565.64	782.82	2,298.42	1,422.98	15.63	-1.54	0.389
105.00	-10.33	-12.77	0.00	-477.18		477.18	1,565.64	782.82	2,298.42	1,422.98	17.28	-1.61	0.342
110.00	-9.59	-12.37	0.00	-413.32		413.32	1,565.64		2,298.42		19.01	-1.70	0.297
115.00	-8.85	-11.97	0.00	-351.46	0.00	351.46	1,565.64	782.82	2,298.42	1,422.98	20.84	-1.78	0.253
115.00	-8.85	-11.97	0.00	-351.46		351.46	1,565.64	782.82	2,298.42	1,422.98	20.84	-1.78	0.253
120.00	-8.11	-11.55	0.00	-291.63		291.63	1,565.64	782.82	2,298.42	1,422.98	22.74	-1.85	0.210
125.00	-7.38	-11.13	0.00	-233.88	0.00	233.88	1,565.64	782.82	2,298.42	1,422.98	24.71	-1.91	0.169
130.00	-6.65	-10.77	0.00	-178.24	0.00	178.24	1,565.64	782.82	2,298.42	1,422.98	26.73	-1.95	0.130
130.00	-6.65	-10.77	0.00	-178.24		178.24	1,127.22	563.61	1,091.62	660.47	26.73	-1.95	0.276
135.00	-6.13	-10.56	0.00	-124.41	0.00	124.41	1,127.22	563.61	1,091.62	660.47	28.79	-1.98	0.194
137.00	-3.81	-6.83	0.00	-101.02	0.00	101.02	1,127.22	563.61	1,091.62	660.47	29.63	-2.02	0.156
140.00	-3.53	-6.60	0.00	-80.52		80.52	1,127.22	563.61	1,091.62	660.47	30.91	-2.06	0.125
145.00	-3.08	-6.31	0.00	-47.50		47.50	1,127.22	563.61	1,091.62	660.47	33.09	-2.10	0.075
150.00	0.00	-6.19	0.00	-15.97	0.00	15.97	1,127.22	563.61	1,091.62	660.47	35.31	-2.13	0.024

Site Name: Prospect CT, CT Engineering Number: 66383921 5/6/2016 9:41:29 AM

Customer: T-MOBILE

<u>Load Case</u>: 1.2D + 1.0Di + 1.0Wi 50 mph with 0.75 in Radial Ice 19 Iterations

Wind Load Factor: 1.00

Applied Segment Forces Summary

		Shaft I	Forces		Discret	e Forces		Linear F	orces		Sum o	f Forces	
Seg			Dead			Moment	Dead		Dead				Moment
Elev		Wind FX	Load	Wind FX		MZ	Load	Wind FX		Wind FX	Load	MY	MZ
	Decembelon												
(ft)	Description	(lb)	(lb)	(lb)	(lb-ft)	(lb-ft)	(lb)	(lb)	(lb)	(lb)	(lb)	(lb-ft)	(lb)
0.00		72.9	0.0					0.0	0.0	72.9	0.0	0.0	0.0
5.00		146.2	2,340.9					0.0	124.3	146.2	2,465.2	0.0	0.0
10.00		146.7	2,392.2					0.0	124.3	146.7	2,516.6	0.0	0.0
15.00		146.9	2,418.2					0.0	124.3	146.9	2,542.5	0.0	0.0
20.00	Top - Section 1	147.1	2,436.0					0.0	124.3	147.1	2,560.3	0.0	0.0
25.00		147.3	1,975.7					0.0	124.3	147.3	2,100.0	0.0	0.0
30.00		149.2	1,987.0					0.0	124.3	149.2	2,111.3	0.0	0.0
35.00		154.2	1,996.5					0.0	124.3	154.2	2,120.8	0.0	0.0
40.00	Top - Section 2	152.6	2,004.8					0.0	124.3	152.6	2,129.1	0.0	0.0
45.00		150.1	1,811.5					0.0	124.3	150.1	1,935.8	0.0	0.0
50.00		154.8	1,817.5					0.0	124.3	154.8	1,941.8	0.0	0.0
55.00		159.2	1,823.0					0.0	124.3	159.2	1,947.3	0.0	0.0
60.00	Top - Section 3	154.6	1,828.0					0.0	124.3	154.6	1,952.3	0.0	0.0
65.00		149.6	1,629.7					0.0	124.3	149.6	1,754.0	0.0	0.0
70.00		152.9	1,633.6					0.0	124.3	152.9	1,757.9	0.0	0.0
75.00		156.0	1,637.2					0.0	124.3	156.0	1,761.5	0.0	0.0
80.00	Top - Section 4	149.6	1,640.6					0.0	124.3	149.6	1,764.9	0.0	0.0
85.00		142.9	1,439.3					0.0	124.3	142.9	1,563.6	0.0	0.0
90.00		145.3	1,441.9					0.0	124.3	145.3	1,566.3	0.0	0.0
95.00		147.6	1,444.5					0.0	124.3	147.6	1,568.8	0.0	0.0
100.00	Top - Section 5	139.9	1,446.9					0.0	124.3	139.9	1,571.2	0.0	0.0
105.00		131.9	1,243.4					0.0	124.3	131.9	1,367.7	0.0	0.0
110.00		133.7	1,245.3					0.0	124.3	133.7	1,369.6	0.0	0.0
115.00	Top - Section 6	135.5	1,247.2					0.0	124.3	135.5	1,371.5	0.0	0.0
120.00		137.2	1,248.9					0.0	124.3	137.2	1,373.3	0.0	0.0
125.00		138.9	1,250.6					0.0	124.3	138.9	1,375.0	0.0	0.0
130.00	Top - Section 7	119.0	1,252.3					0.0	124.3	119.0	1,376.6	0.0	0.0
135.00	-	69.0	839.0					0.0	124.3	69.0	963.3	0.0	0.0
137.00	Appertunance(s)	49.7	335.9	752.3	0.0	411.8	5,555.1	0.0	49.7	802.0	5,940.7	0.0	0.0
140.00		80.1	504.2				•	0.0	30.9	80.1	535.0	0.0	0.0
145.00		101.0	841.1					0.0	51.5	101.0	892.6	0.0	0.0
150.00	Appertunance(s)	50.7	842.1	1,240.1	0.0	2,903.3	8,923.1	0.0	51.5	1,290.9	9,816.7	0.0	0.0
								To	tals:	6,204.69	66,013.3	0.00	0.00

Site Name: Prospect CT, CT Engineering Number: 66383921 5/6/2016 9:41:30 AM

Customer: T-MOBILE

<u>Load Case:</u> 1.2D + 1.0Di + 1.0Wi 50 mph with 0.75 in Radial Ice 19 Iterations

Wind Load Factor: 1.00

Calculated Forces

_														
	Seg	Pu	Vu	Tu	Mu	Mu	Resultant	t phi	phi	phi	phi	Total		
	Elev	FY (-)	FX (-)	MY	MZ	MX	Moment	Pn	۷n	Tn	Mn		Rotation	
	(ft)	(kips)	(kips)	(ft-kips)	(ft-kips)		(ft-kips)	(kips)	(kips)		(ft-kips)	(in)	(deg)	Ratio
_	(11)	(Kips)	(Kips)	(it kips)	(it kips)	(it kips)	(it kips)	(Kips)	(Kips)	(it kips)	(it kips)	("')	(acg)	Natio
	0.00	-66.01	-6.14	0.00	-612.74	0.00	612.74	3,293.92	1,646.96	8,093.29	5,174.22	0.00	0.00	0.138
	5.00	-63.54	-6.02	0.00	-582.02	0.00	582.02	3,293.92	1,646.96	8,093.29	5,174.22	0.01	-0.02	0.132
	10.00	-61.03	-5.89	0.00	-551.93	0.00	551.93	3,293.92	1,646.96	8,093.29	5,174.22	0.04	-0.04	0.125
	15.00	-58.48	-5.76	0.00	-522.47	0.00	522.47	3,293.92	1,646.96	8,093.29	5,174.22	0.10	-0.06	0.119
	20.00	-55.92	-5.63	0.00	-493.67	0.00	493.67	3,293.92	1,646.96	8,093.29	5,174.22	0.17	-0.08	0.112
	20.00	-55.92	-5.63	0.00	-493.67	0.00	493.67	2,330.87	1,165.43	5,751.12	3,807.50	0.17	-0.08	0.154
	25.00	-53.82	-5.49	0.00	-465.53	0.00	465.53	2,330.87	1,165.43	5,751.12	3,807.50	0.25	-0.09	0.145
	30.00	-51.71	-5.36	0.00	-438.06	0.00	438.06	2,330.87	1,165.43	5,751.12	3,807.50	0.36	-0.11	0.137
	35.00	-49.58	-5.22	0.00	-411.27	0.00	411.27	2,330.87	1,165.43	5,751.12	3,807.50	0.49	-0.13	0.129
	40.00	-47.45	-5.07	0.00	-385.18	0.00	385.18	2,330.87	1,165.43	5,751.12	3,807.50	0.64	-0.15	0.122
	40.00	-47.45	-5.07	0.00	-385.18	0.00	385.18	2,139.71	1,069.86	4,744.89	3,103.93	0.64	-0.15	0.146
	45.00	-45.52	-4.93	0.00	-359.82	0.00	359.82	2,139.71	1,069.86	4,744.89	3,103.93	0.81	-0.17	0.137
	50.00	-43.57	-4.79	0.00	-335.15	0.00	335.15	2,139.71	1,069.86	4,744.89	3,103.93	0.99	-0.19	0.128
	55.00	-41.63	-4.64	0.00	-311.21	0.00	311.21	2,139.71	1,069.86	4,744.89	3,103.93	1.20	-0.21	0.120
	60.00	-39.67	-4.49	0.00	-288.03	0.00	288.03	2,139.71	1,069.86	4,744.89	3,103.93	1.43	-0.23	0.111
	60.00	-39.67	-4.49	0.00	-288.03	0.00	288.03			3,834.02		1.43	-0.23	0.137
	65.00	-37.92	-4.34	0.00	-265.60	0.00	265.60	1,948.48	974.24	3,834.02	2,471.99	1.68	-0.25	0.127
	70.00	-36.16	-4.20	0.00	-243.88		243.88	1,948.48	974.24	3,834.02	2,471.99	1.95	-0.27	0.117
	75.00	-34.40	-4.04	0.00	-222.90	0.00	222.90	1,948.48	974.24	3,834.02	2,471.99	2.24	-0.29	0.108
	80.00	-32.63	-3.90	0.00	-202.68	0.00	202.68	1,948.48	974.24	3,834.02	2,471.99	2.56	-0.31	0.099
	80.00	-32.63	-3.90	0.00	-202.68	0.00	202.68	1,757.14	878.57	3,018.53	1,911.67	2.56	-0.31	0.125
	85.00	-31.07	-3.75	0.00	-183.20		183.20	1,757.14	878.57	3,018.53	1,911.67	2.89	-0.33	0.114
	90.00	-29.50	-3.61	0.00	-164.43	0.00	164.43			3,018.53		3.24	-0.35	0.103
	95.00	-27.93	-3.46	0.00	-146.37	0.00	146.37	1,757.14		3,018.53		3.62	-0.37	0.092
	100.00	-26.36	-3.32	0.00	-129.06	0.00	129.06	1,757.14	878.57	3,018.53	1,911.67	4.01	-0.39	0.083
	100.00	-26.36	-3.32	0.00	-129.06		129.06		782.82	2,298.42	1,422.98	4.01	-0.39	0.108
	105.00	-24.99	-3.19	0.00	-112.45		112.45			2,298.42		4.43	-0.40	0.095
	110.00	-23.62	-3.05	0.00	-96.51	0.00	96.51	1,565.64		2,298.42	,	4.87	-0.43	0.083
	115.00	-22.25	-2.91	0.00	-81.24		81.24			2,298.42		5.32	-0.45	0.071
	115.00	-22.25	-2.91	0.00	-81.24		81.24			2,298.42		5.32	-0.45	0.071
	120.00	-20.88	-2.77	0.00	-66.67		66.67			2,298.42		5.80	-0.46	0.060
	125.00	-19.50	-2.62	0.00	-52.82		52.82			2,298.42	,	6.29	-0.47	0.050
	130.00	-18.13	-2.50	0.00	-39.69	0.00	39.69	1,565.64		2,298.42	,	6.79	-0.48	0.039
	130.00	-18.13	-2.50	0.00	-39.69		39.69			1,091.62	660.47	6.79	-0.48	0.076
	135.00	-17.16	-2.42	0.00	-27.21		27.21	1,127.22		1,091.62	660.47	7.30	-0.49	0.056
	137.00	-11.23	-1.57	0.00	-21.95		21.95	1,127.22		1,091.62	660.47	7.51	-0.50	0.043
	140.00	-10.70	-1.49	0.00	-17.24		17.24	1,127,22		1.091.62	660.47	7.82	-0.51	0.036
	145.00	-9.80	-1.38	0.00	-9.80		9.80			1,091.62	660.47	8.36	-0.52	0.024
	150.00	0.00	-1.29	0.00	-2.90		2.90			1,091.62	660.47	8.90	-0.52	0.004
								,						

Site Name: Prospect CT, CT Engineering Number: 66383921 5/6/2016 9:41:30 AM

Customer: T-MOBILE

<u>Load Case:</u> 1.0D + 1.0W Serviceability 60 mph 18 Iterations

Gust Response Factor: 1.10 Wind Importance Factor: 1.00

Dead Load Factor: 1.00 Wind Load Factor: 1.00

Applied Segment Forces Summary

		Shaft F	Forces		Discret	e Forces		Linear F	orces		Sum o	f Forces	
Seg			Dead		Torsion	Moment	Dead		Dead				Moment
Elev		Wind FX	Load	Wind FX		MZ	Load	Wind FX	Load	Wind FX	Load	MY	MZ
(ft)	Description	(lb)	(lb)	(lb)	(lb-ft)	(lb-ft)	(lb)	(lb)	(lb)	(lb)	(lb)	(lb-ft)	(lb)
(,	Description	(16)	. ,	(10)	(16 11)	(,	(ID)	(10)	(16)	()	(1.5)	(ID-IL)	(ID)
0.00		50.6	0.0					0.0	0.0	50.6	0.0	0.0	0.0
5.00		101.1	1,590.2					0.0	103.6	101.1	1,693.8	0.0	0.0
10.00		101.1	1,590.2					0.0	103.6	101.1	1,693.8	0.0	0.0
15.00		101.1	1,590.2					0.0	103.6	101.1	1,693.8	0.0	0.0
20.00	Top - Section 1	101.1	1,590.2					0.0	103.6	101.1	1,693.8	0.0	0.0
25.00		101.1	1,195.1					0.0	103.6	101.1	1,298.7	0.0	0.0
30.00		102.3	1,195.1					0.0	103.6	102.3	1,298.7	0.0	0.0
35.00		105.7	1,195.1					0.0	103.6	105.7	1,298.7	0.0	0.0
40.00	Top - Section 2	104.2	1,195.1					0.0	103.6	104.2	1,298.7	0.0	0.0
45.00		102.2	1,074.9					0.0	103.6	102.2	1,178.5	0.0	0.0
50.00		105.4	1,074.9					0.0	103.6	105.4	1,178.5	0.0	0.0
55.00		108.3	1,074.9					0.0	103.6	108.3	1,178.5	0.0	0.0
60.00	Top - Section 3	104.8	1,074.9					0.0	103.6	104.8	1,178.5	0.0	0.0
65.00	•	101.0	954.6					0.0	103.6	101.0	1,058.2	0.0	0.0
70.00		103.1	954.6					0.0	103.6	103.1	1,058.2	0.0	0.0
75.00		105.2	954.6					0.0	103.6	105.2	1,058.2	0.0	0.0
80.00	Top - Section 4	100.4	954.6					0.0	103.6	100.4	1,058.2	0.0	0.0
85.00	•	95.4	834.3					0.0	103.6	95.4	937.9	0.0	0.0
90.00		97.0	834.3					0.0	103.6	97.0	937.9	0.0	0.0
95.00		98.5	834.3					0.0	103.6	98.5	937.9	0.0	0.0
100.00	Top - Section 5	92.7	834.3					0.0	103.6	92.7	937.9	0.0	0.0
105.00	•	86.9	714.1					0.0	103.6	86.9	817.7	0.0	0.0
110.00		88.0	714.1					0.0	103.6	88.0	817.7	0.0	0.0
115.00	Top - Section 6	89.1	714.1					0.0	103.6	89.1	817.7	0.0	0.0
120.00	•	90.2	714.1					0.0	103.6	90.2	817.7	0.0	0.0
125.00		91.3	714.1					0.0	103.6	91.3	817.7	0.0	0.0
130.00	Top - Section 7	76.8	714.1					0.0	103.6	76.8	817.7	0.0	0.0
135.00		43.4	473.5					0.0	103.6	43.4	577.1	0.0	0.0
137.00	Appertunance(s)	31.3	189.4	788.8	0.0	5110	2,484.6	0.0	41.4	820.0	2,715.5	0.0	0.0
140.00	7.ppo.ru(0)	50.4	284.1	7 00.0	0.0	011.0	2,404.0	0.0	25.7	50.4	309.9	0.0	0.0
145.00		63.5	473.5					0.0	42.9	63.5	516.4	0.0	0.0
150.00	Appertunance(s)	31.9	473.5	1,360.4	0.0	3,594.2	3,157.8		42.9	1,392.3	3,674.2	0.0	0.0
	[] - · · · · · · · · · · · · · · · · · ·	00	0.0	.,000.4	0.0	. 0,00	3,			•	•		
								То	tals:	4,974.40	37,367.4	0.00	0.00

Site Name: Prospect CT, CT Engineering Number: 66383921 5/6/2016 9:41:31 AM

Customer: T-MOBILE

<u>Load Case:</u> 1.0D + 1.0W Serviceability 60 mph 18 Iterations

Gust Response Factor: 1.10 Wind Importance Factor: 1.00

Dead Load Factor: 1.00 Wind Load Factor: 1.00

Calculated Forces

Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	phi Pn (kips)	phi Vn (kips)	phi Tn (ft-kips)	phi Mn (ft-kips)	Total Deflect (in)	Rotation (deg)	Ratio
0.00	-37.37	-4.93	0.00	-523.31	0.00	523.31	3 293 92	1 646 96	8,093.29	5 174 22	0.00	0.00	0.112
5.00	-35.67	-4.84	0.00	-498.67		498.67			8,093.29		0.01	-0.02	0.107
10.00	-33.98	-4.75	0.00	-474.48		474.48			8,093.29		0.04	-0.03	0.107
15.00	-32.28	-4.65	0.00	-450.75		450.75			8,093.29		0.08	-0.05	0.097
20.00	-30.59	-4.56	0.00	-427.49		427.49			8,093.29		0.14	-0.07	0.092
20.00	-30.59	-4.56	0.00	-427.49		427.49	,	,	5,751.12	,	0.14	-0.07	0.125
25.00	-29.29	-4.46	0.00	-404.71	0.00	404.71			5,751.12		0.22	-0.08	0.119
30.00	-27.99	-4.37	0.00	-382.39		382.39	,	,	5,751.12	,	0.31	-0.10	0.112
35.00	-26.69	-4.27	0.00	-360.56		360.56	,	,	5,751.12	,	0.42	-0.11	0.106
40.00	-25.39	-4.17	0.00	-339.23		339.23			5.751.12		0.55	-0.13	0.100
40.00	-25.39	-4.17	0.00	-339.23		339.23			4,744.89		0.55	-0.13	0.121
45.00	-24.21	-4.07	0.00	-318.40		318.40			4,744.89		0.70	-0.15	0.114
50.00	-23.03	-3.97	0.00	-298.06	0.00	298.06	,	,	4,744.89	,	0.86	-0.16	0.107
55.00	-21.85	-3.86	0.00	-278.22	0.00	278.22			4,744.89		1.04	-0.18	0.100
60.00	-20.67	-3.76	0.00	-258.91	0.00	258.91	,	,	4,744.89	,	1.24	-0.20	0.093
60.00	-20.67	-3.76	0.00	-258.91	0.00	258.91	1,948.48	974.24	3,834.02	2,471.99	1.24	-0.20	0.115
65.00	-19.61	-3.66	0.00	-240.12	0.00	240.12	1,948.48		3,834.02		1.46	-0.22	0.107
70.00	-18.55	-3.56	0.00	-221.82		221.82	1,948.48	974.24	3,834.02	2,471.99	1.69	-0.24	0.099
75.00	-17.49	-3.46	0.00	-204.02	0.00	204.02	1,948.48	974.24	3,834.02	2,471.99	1.95	-0.25	0.092
80.00	-16.43	-3.36	0.00	-186.74	0.00	186.74	1,948.48	974.24	3,834.02	2,471.99	2.23	-0.27	0.084
80.00	-16.43	-3.36	0.00	-186.74	0.00	186.74	1,757.14	878.57	3,018.53	1,911.67	2.23	-0.27	0.107
85.00	-15.50	-3.26	0.00	-169.96	0.00	169.96	1,757.14	878.57	3,018.53	1,911.67	2.52	-0.29	0.098
90.00	-14.56	-3.16	0.00	-153.66	0.00	153.66	1,757.14	878.57	3,018.53	1,911.67	2.84	-0.31	0.089
95.00	-13.62	-3.06	0.00	-137.84	0.00	137.84	1,757.14	878.57	3,018.53	1,911.67	3.17	-0.33	0.080
100.00	-12.68	-2.97	0.00	-122.52	0.00	122.52	1,757.14	878.57	3,018.53	1,911.67	3.53	-0.35	0.071
100.00	-12.68	-2.97	0.00	-122.52	0.00	122.52	1,565.64	782.82	2,298.42	1,422.98	3.53	-0.35	0.094
105.00	-11.86	-2.88	0.00	-107.67	0.00	107.67	1,565.64	782.82	2,298.42	1,422.98	3.90	-0.36	0.083
110.00	-11.04	-2.79	0.00	-93.26	0.00	93.26	1,565.64	782.82	2,298.42	1,422.98	4.29	-0.38	0.073
115.00	-10.23	-2.70	0.00	-79.30	0.00	79.30	1,565.64	782.82	2,298.42	1,422.98	4.70	-0.40	0.062
115.00	-10.23	-2.70	0.00	-79.30		79.30	1,565.64	782.82	2,298.42	1,422.98	4.70	-0.40	0.062
120.00	-9.41	-2.61	0.00	-65.80		65.80	1,565.64		2,298.42		5.13	-0.42	0.052
125.00	-8.59	-2.51	0.00	-52.76	0.00	52.76	1,565.64	782.82	2,298.42	1,422.98	5.57	-0.43	0.043
130.00	-7.77	-2.43	0.00	-40.21	0.00	40.21	1,565.64	782.82	2,298.42	1,422.98	6.03	-0.44	0.033
130.00	-7.77	-2.43	0.00	-40.21	0.00	40.21	1,127.22		1,091.62	660.47	6.03	-0.44	0.068
135.00	-7.20	-2.38	0.00	-28.06		28.06	1,127.22		1,091.62	660.47	6.49	-0.45	0.049
137.00	-4.49	-1.54	0.00	-22.78		22.78	1,127.22		1,091.62	660.47	6.68	-0.45	0.038
140.00	-4.18	-1.49	0.00	-18.16		18.16	1,127.22		1,091.62	660.47	6.97	-0.46	0.031
145.00	-3.66	-1.42	0.00	-10.71	0.00	10.71	1,127.22		1,091.62	660.47	7.46	-0.47	0.019
150.00	0.00	-1.39	0.00	-3.59	0.00	3.59	1,127.22	563.61	1,091.62	660.47	7.96	-0.48	0.005

Site Name: Prospect CT, CT Engineering Number: 66383921 5/6/2016 9:41:31 AM

Customer: T-MOBILE

Equivalent Lateral Forces Method Analysis

(Based on ASCE7-10 Chapters 11, 12, 15)

Spectral Response Acceleration for Short Period (S _s):	0.19
Spectral Response Acceleration at 1.0 Second Period (S ₁):	0.06
Long-Period Transition Period (T _L):	6
Importance Factor (I _E):	1.00
Site Coefficient F _a :	1.60
Site Coefficient F _v :	2.40
Response Modification Coefficient (R):	1.50
Design Spectral Response Acceleration at Short Period (S _{ds}):	0.20
Design Spectral Response Acceleration at 1.0 Second Period (S _{d1}):	0.10
Seismic Response Coefficient (C _s):	0.04
Upper Limit C _s	0.04
Lower Limit C _s	0.03
Period based on Rayleigh Method (sec):	1.60
Redundancy Factor (p):	1.30
Seismic Force Distribution Exponent (k):	1.55
Total Unfactored Dead Load:	37.37 k
Seismic Base Shear (E):	2.08 k

Site Name: Prospect CT, CT Engineering Number: 66383921 5/6/2016 9:41:31 AM

Customer: T-MOBILE

Equivalent Modal Forces Analysis

(Based on ASCE7-10 Chapters 11, 12 & 15 and ANSI/TIA-G, section 2.7)

Spectral Response Acceleration for Short Period (S _s):	0.19
Spectral Response Acceleration at 1.0 Second Period (S ₁):	0.06
Importance Factor (I _E):	1.00
Site Coefficient F _a :	1.60
Site Coefficient F _v	2.40
Response Modification Coefficient (R):	1.50
Design Spectral Response Acceleration at Short Period (S $_{ m ds}$):	0.20
Desing Spectral Response Acceleration at 1.0 Second Period (S_{d1}):	0.10
Period Based on Rayleigh Method (sec):	1.60
Redundancy Factor (p):	1.30

<u>Load Case</u> (1.2 + 0.2Sds) * DL + E ELFM Seismic Equivalent Lateral Forces Method

	Height Above						Horizontal	Vertical
	Base	Weight					Force	Force
Segment	(ft)	(lb)	а	b	С	Saz	(lb)	(lb)
31	147.50	516	1.828	1.667	1.025	0.350	157	640
30	142.50	516	1.706	1.144	0.823	0.275	123	640
29	138.50	310	1.611	0.814	0.686	0.221	59	384
28	136.00	231	1.554	0.642	0.609	0.190	38	286
27	132.50	577	1.475	0.441	0.513	0.151	76	716
26	127.50	818	1.366	0.222	0.397	0.103	73	1,014
25	122.50	818	1.261	0.069	0.302	0.063	44	1,014
24	117.50	818	1.160	-0.030	0.226	0.031	22	1,014
23	112.50	818	1.063	-0.088	0.165	0.008	6	1,014
22	107.50	818	0.971	-0.116	0.117	-0.007	-5	1,014
21	102.50	818	0.883	-0.121	0.081	-0.015	-10	1,014
20	97.50	938	0.799	-0.112	0.053	-0.015	-12	1,163
19	92.50	938	0.719	-0.092	0.034	-0.010	-8	1,163
18	87.50	938	0.643	-0.068	0.020	-0.001	-1	1,163
17	82.50	938	0.572	-0.043	0.012	0.009	8	1,163
16	77.50	1,058	0.505	-0.018	0.007	0.020	19	1,312
15	72.50	1,058	0.442	0.005	0.006	0.030	28	1,312
14	67.50	1,058	0.383	0.023	0.007	0.038	35	1,312
13	62.50	1,058	0.328	0.039	0.010	0.043	40	1,312
12	57.50	1,178	0.278	0.050	0.014	0.046	47	1,461
11	52.50	1,178	0.232	0.058	0.019	0.047	48	1,461
10	47.50	1,178	0.190	0.064	0.025	0.047	48	1,461
9	42.50	1,178	0.152	0.068	0.030	0.046	47	1,461
8	37.50	1,299	0.118	0.070	0.035	0.045	50	1,611
7	32.50	1,299	0.089	0.071	0.039	0.043	48	1,611
6	27.50	1,299	0.064	0.072	0.041	0.041	47	1,611
5	22.50	1,299	0.043	0.070	0.042	0.040	45	1,611
4	17.50	1,694	0.026	0.067	0.040	0.037	54	2,100
3	12.50	1,694	0.013	0.059	0.034	0.033	48	2,100
2	7.50	1,694	0.005	0.044	0.025	0.025	37	2,100
	2.50	1,694	0.001	0.018	0.010	0.011	16	2,100
Powerwave TT08-	150.00	66	1.890	1.980	1.140	0.391	22	82
Raycap DC6-48-60-0-8	150.00	98	1.890	1.980	1.140	0.391	33	122
Ericsson RRUS A2	150.00	90	1.890	1.980	1.140	0.391	30	112

Site Number: 282660				Code: A	NSI/TIA-222	P-G © 200	07 - 2016 by ATC IP	LLC. All rights reserved.
Site Name: Prospect C	T CT		Engineering N				_	5/6/2016 9:41:31 AM
) i , O i		Engineering is	diliber. o	33033 <u>2</u> 1			0/0/2010 3.41.31 AM
Customer: T-MOBILE								
Ericsson RRUS 32 (50	150.00	152	1.890	1.980	1.140	0.391	52	189
Ericsson RRUS 12	150.00	300	1.890	1.980	1.140	0.391	102	372
Ericsson RRUS E2 B29	150.00	60	1.890	1.980	1.140	0.391	20	74
Ericsson RRUS-11	150.00	330	1.890	1.980	1.140	0.391	112	409
CCI HPA-65R-BUU-H6 CCI HPA-65R-BUU-H8	150.00 150.00	153 408	1.890 1.890	1.980 1.980	1.140 1.140	0.391 0.391	52 138	190 506
Round Low Profile Pl	150.00	1,500	1.890	1.980	1.140	0.391	508	1,860
Ericsson KRY 112 144	137.00	33	1.577	0.708	0.639	0.202	6	41
Ericsson RRUS 11 B12	137.00	152	1.577	0.708	0.639	0.202	27	189
Ericsson AIR 21, 1.3	137.00	249	1.577	0.708	0.639	0.202	44	309
Ericsson AIR32 B66Aa	137.00	397	1.577	0.708	0.639	0.202	70	492
Andrew LNX-6515DS-VT		154	1.577	0.708	0.639	0.202	27	191
Round Low Profile Pl	137.00	1,500	1.577	0.708	0.639	0.202	263	1,860
		37,367	48.831	29.135	20.679	7.069	2,729	46,340
Load Case (1.2 + 0.2Se	ds) * DL + I	E EMAM	Se	eismic Eq	uivalent N	/lodal Analy	sis Method	
	Height							
	Above						Horizontal	Vertical
	Base	Weight					Force	Force
Segment	(ft)	(lb)	а	b	С	Saz	(lb)	(lb)
31	147.50	516	1.828	1.667	1.025	0.350	157	640
30	142.50	516	1.706	1.144	0.823	0.275	123	640
29	138.50	310	1.611	0.814	0.686	0.221	59	384
28	136.00	231	1.554	0.642	0.609	0.190	38	286
27	132.50	577	1.475	0.441	0.513	0.151	76	716
26	127.50	818	1.366	0.222	0.397	0.103	73	1,014
25 24	122.50	818	1.261	0.069	0.302 0.226	0.063	44	1,014
23	117.50 112.50	818 818	1.160 1.063	-0.030 -0.088	0.220	0.031 0.008	22 6	1,014 1,014
22	107.50	818	0.971	-0.116	0.103	-0.007	-5	1,014
21	107.50	818	0.883	-0.121	0.081	-0.015	-10	1,014
20	97.50	938	0.799	-0.112	0.053	-0.015	-12	1,163
19	92.50	938	0.719	-0.092	0.034	-0.010	-8	1,163
18	87.50	938	0.643	-0.068	0.020	-0.001	-1	1,163
17	82.50	938	0.572	-0.043	0.012	0.009	8	1,163
16	77.50	1,058	0.505	-0.018	0.007	0.020	19	1,312
15	72.50	1,058	0.442	0.005	0.006	0.030	28	1,312
14 13	67.50 62.50	1,058 1,058	0.383 0.328	0.023 0.039	0.007 0.010	0.038 0.043	35 40	1,312 1,312
12	57.50	1,038	0.278	0.059	0.014	0.046	40 47	1,461
11	52.50	1,178	0.232	0.058	0.019	0.047	48	1,461
10	47.50	1,178	0.190	0.064	0.025	0.047	48	1,461
9	42.50	1,178	0.152	0.068	0.030	0.046	47	1,461
8	37.50	1,299	0.118	0.070	0.035	0.045	50	1,611
7	32.50	1,299	0.089	0.071	0.039	0.043	48	1,611
6	27.50	1,299	0.064	0.072	0.041	0.041	47	1,611
5	22.50	1,299	0.043	0.070	0.042 0.040	0.040	45 54	1,611
4 3	17.50 12.50	1,694 1,694	0.026 0.013	0.067 0.059	0.040	0.037 0.033	54 48	2,100 2,100
2	7.50	1,694	0.005	0.039	0.025	0.035	37	2,100
1	2.50	1,694	0.003	0.044	0.010	0.023	16	2,100
Powerwave TT08-	150.00	66	1.890	1.980	1.140	0.391	22	82
Raycap DC6-48-60-0-8	150.00	98	1.890	1.980	1.140	0.391	33	122
Ericsson RRUS A2	150.00	90	1.890	1.980	1.140	0.391	30	112
Ericsson RRUS 32 (50	150.00	152	1.890	1.980	1.140	0.391	52	189
Ericsson RRUS 12	150.00	300	1.890	1.980	1.140	0.391	102	372
Ericsson RRUS E2 B29	150.00	60	1.890	1.980	1.140	0.391	20	74
Ericsson RRUS-11	150.00	330	1.890	1.980	1.140 1.140	0.391	112	409
CCI HPA-65R-BUU-H6 CCI HPA-65R-BUU-H8	150.00 150.00	153 408	1.890 1.890	1.980 1.980	1.140	0.391 0.391	52 138	190 506
Round Low Profile Pl	150.00	1,500	1.890	1.980	1.140	0.391	508	1,860
	. 55.55	.,500			-			.,500

Site Number: 282660				Code: A	NSI/TIA-222-0	© 200	07 - 2016 by ATC I	P LLC. All rights reserved.
Site Name: Prospect CT	, CT		Engineering N	lumber: 60	6383921			5/6/2016 9:41:31 AM
Customer: T-MOBILE								
Ericsson KRY 112 144	137.00	33	1.577	0.708	0.639	0.202	6	41
Ericsson RRUS 11 B12	137.00	152	1.577	0.708	0.639	0.202	27	189
Ericsson AIR 21, 1.3	137.00	249	1.577	0.708	0.639	0.202	44	309
Ericsson AIR32 B66Aa	137.00	397	1.577	0.708	0.639	0.202	70	492
Andrew LNX-6515DS-VT	137.00	154	1.577	0.708	0.639	0.202	27	191
Round Low Profile Pl	137.00	1,500	1.577	0.708	0.639	0.202	263	1,860
		37,367	48.831	29.135	20.679	7.069	2,729	46,340

Site Name: Prospect CT, CT Engineering Number: 66383921 5/6/2016 9:41:31 AM


Customer: T-MOBILE

Analysis Summary

	Reactions Max Usag			x Usage				
Load Case	Shear FX (kips)	Shear FZ (kips)	Axial FY (kips)	Moment MX (ft-kips)	Moment MY (ft-kips)	Moment MZ (ft-kips)	Elev (ft)	Interaction Ratio
1.2D + 1.6W	21.91	0.00	44.83	0.00	0.00	2333.99	20.00	0.52
0.9D + 1.6W	21.91	0.00	33.62	0.00	0.00	2321.79	20.00	0.51
1.2D + 1.0Di + 1.0Wi	6.14	0.00	66.01	0.00	0.00	612.74	20.00	0.15
(1.2 + 0.2Sds) * DL + E ELFM	2.08	0.00	44.24	0.00	0.00	241.17	20.00	0.07
(1.2 + 0.2Sds) * DL + E EMAM	2.72	0.00	44.24	0.00	0.00	328.49	20.00	0.09
1.0D + 1.0W	4.93	0.00	37.37	0.00	0.00	523.31	20.00	0.13

	Plate Type	Baseplate	
ь	Pole Diameter	60	in
Base/Flange Plate	Pole Thickness	0.5	in
Je F	Plate Diameter	72	in
anç	Plate Thickness	1.5	in
∌/FI	Plate Fy	50	ksi
ase	Weld Length	0.4375	in
B	φ _s Resistance	132.54	k-in
	Applied	86.19	k-in
	#	0	
S			
Stiffeners			
tiffe			
Ś			

_			
	# Bolt Circle (R)adial / (S)quare	36 66 ir R	n
Bolts •	Diameter Hole Diameter Type Fy Fu	1.5 ir 1.5625 ir A449 81 k 105 k	n (Si
	φ _s Resistance Applied	118.04 k 48.39 k	
Reinforcement	#	0	
Extra Bolts 0	#	0	






Plate Stress Ratio:


0.65 (Pass)

Bolt Stress Ratio:

0.41 (Pass)

	Plate Type	Flange	@ 20.0 ft
	Pole Diameter	60	
Base/Flange Plate	Pole Thickness	0.375	
еЪ	Plate Diameter	60	in
ang	Plate Thickness	1.5	in
Ę	Plate Fy	50	ksi
ase	Weld Length	0.3125	in
Ω	ϕ_s Resistance	134.19	k-in
	Applied	98.80	k-in
	#	0	
ø			
Stiffeners			
iffe			
ß			

	#	32	
	Bolt Circle	54	in
	(R)adial / (S)quare	R	
	(N)adiai / (O)quai c	11	
	Diameter	1.5	in
ts	Hole Diameter		in
Bolts	Туре	A325	
	Fy		ksi
	Fu	120	
	φ _s Resistance	126.47	
	Applied	51.83	k
	#	0	
•			
Jen			
Sem			
Reinforcement			
ein			
I*			
	#	0	
ts (
Bol			
Extra Bolts O			
Ë			
1			



Required Flange Thickness:

1.29 in OK




Plate Stress Ratio:

0.74 (Pass)

Bolt Stress Ratio:

0.41 (Pass)

	D		@ 40.054
	Plate Type		@ 40.0 ft
a	Pole Diameter	54	in
<u>a</u>	Pole Thickness	0.375	in
еВ	Plate Diameter	60	in
l gu	Plate Thickness	1.5	in
崑	Plate Fy	50	ksi
Base/Flange Plate	Weld Length	0.3125	in
ä	ϕ_s Resistance	89.46	k-in
	Applied	16.21	k-in
	#	0	
ω,			
Stiffeners			
Ę			
SE			

_	"		Ī
	# Bolt Circle	48 57	
		57	III
	(R)adial / (S)quare	R	
	Diameter	1	in
Bolts	Hole Diameter		in
ĕ	Туре	A325	
	Fy		ksi
	Fu	120	
	ϕ_s Resistance	54.52	
	Applied	25.94	k
	#	0	
•			
Reinforcement			
Ĭ.			
ž			
ıfe			
Rei			
	#	0	
S			
ğ			
ë B			
Extra Bolts 0			
1"			
1			
1			

 Code Rev.
 G
 Date
 5/6/2016

 Engineer
 ZAM

 Site #
 282660

 Moment
 1514.5 k-ft
 Carrier
 T-Mobile

 Axial
 30.3 k

Required Flange Thickness:

0.64 in OK




Plate Stress Ratio:


0.18 (Pass)

Bolt Stress Ratio:

0.48 (Pass)

	1		
	Plate Type	Flange	@ 60.0 ft
ø	Pole Diameter	48	in
lat	Pole Thickness	0.375	in
е	Plate Diameter	54	in
ang I	Plate Thickness	1.5	in
Æ	Plate Fy	50	ksi
Base/Flange Plate	Weld Length	0.3125	in
Ä	ϕ_s Resistance	95.43	k-in
	Applied	16.62	k-in
	#	0	
S			
Stiffeners			
ffe			
Sti			

	#	40	
	Bolt Circle		in
	(R)adial / (S)quare	R	
	Diameter	4	:
.	Diameter	1 1.125	in in
Bolts	Hole Diameter	1.125 A325	111
m	Type		ksi
	Fy Fu	120	
		54.52	
	φ _s Resistance		
_	Applied #	26.59	K
	#	0	
•			
Jen			
Sen .			
١ĕ			
einfe			
Reinforcement			
Reinfo			
Reinfo	#	0	
Reinfo	#	0	
Reinfe	#	0	
	#	0	
	#	0	
	#	0	
	#	0	
Extra Bolts 0 Reinf	#	0	
	#	0	
	#	0	
	#	0	



0.63 in OK




Plate Stress Ratio:


0.17 (Pass)

Bolt Stress Ratio:

0.49 (Pass)

	Plate Type	Flange	@ 80.0 ft
a	Pole Diameter	42	in
late	Pole Thickness	0.375	in
еР	Plate Diameter	48	in
ng In	Plate Thickness	1.5	in
FI	Plate Fy	50	ksi
Base/Flange Plate	Weld Length	0.3125	in
ä	ϕ_s Resistance	104.13	k-in
	Applied	16.99	k-in
	#	0	
"			
Stiffeners			
fer			
Sŧ			

	#	32	
	Bolt Circle	45	in
	(R)adial / (S)quare	R	
	Diameter	1	in
Bolts	Hole Diameter		in
ĕ	Туре	A325	
	Fy Fu	92 120	ksi
	φ _s Resistance	54.52	
	Applied	27.19	
H	#	0	K
١.	"	· ·	
Reinforcement			
me			
ž			
infe			
Re			
	,,		
	#	0	
s O			
Set			
Extra Bolts 0			
Ext			



0.61 in OK




Plate Stress Ratio:


0.16 (Pass)

Bolt Stress Ratio:

0.50 (Pass)

	Plate Type	Flange	@ 100.01
d)	Pole Diameter	36	in
ate	Pole Thickness	0.375	in
еР	Plate Diameter	42	in
ıng	Plate Thickness	1.5	in
FE	Plate Fy	50	ksi
Base/Flange Plate	Weld Length	0.3125	in
ä	φ _s Resistance	104.13	k-in
	Applied	17.14	k-in
	#	0	
,,			
Stiffeners			
fer			
Stil			

_	1		
	#	24	
	Bolt Circle	39	in
	(R)adial / (S)quare	R	
	Diameter		in
Bolts	Hole Diameter		in
ĕ	Туре	A325	
	Fy	92	
	Fu	120	
	φ _s Resistance	54.52	
	Applied	27.43	k
	#	0	
•			
en			
eπ			
Reinforcement			
ein			
œ			
-	"	0	
	#	0	
0			
쁑			
B			
Extra Bolts 0			
lΨ			



0.61 in OK




Plate Stress Ratio:


0.16 (Pass)

Bolt Stress Ratio:

0.50 (Pass)

	Plate Type	Flange	@ 115.0
a	Pole Diameter	36	in
late	Pole Thickness	0.375	in
еР	Plate Diameter	36	in
ang	Plate Thickness	1.5	in
Ę	Plate Fy	50	ksi
Base/Flange Plate	Weld Length	0.3125	in
Ä	ϕ_s Resistance	99.40	k-in
	Applied	49.08	k-in
	#	0	
,,			
Stiffeners			
fer			
Stii			

	#	24	
	Bolt Circle	30	in
	(R)adial / (S)quare	R	
	Diameter	1	in
Bolts	Hole Diameter		in
B	Type	A325	ادما
	Fy Fu		ksi kai
		120 54.52	
	φ _s Resistance		
	Applied #	23.10 0	K
	#	U	
ı,			
ner			
Reinforcement			
for			
Reir			
"			
	#	0	
0			
ts (
Bol			
Extra Bolts 0			
Ex			



1.05 in OK




Plate Stress Ratio:

0.49 (Pass)

Bolt Stress Ratio:

0.42 (Pass)

	Plate Type	Flange	@ 130.01
d)	Pole Diameter	24	in
ate	Pole Thickness	0.375	in
еР	Plate Diameter	30	in
ıng	Plate Thickness	1.5	in
FE	Plate Fy	50	ksi
Base/Flange Plate	Weld Length	0.3125	in
ä	φ _s Resistance	95.43	k-in
	Applied	9.68	k-in
	#	0	
,,			
Stiffeners			
fer			
Stil			

1	#	20	
	Bolt Circle	27 in	
	(R)adial / (S)quare	R	
	Diameter	1 in	
Bolts	Hole Diameter	1.125 in	
ĕ	Туре	A325	
	Fy	92 ks	
	Fu	120 ks	I
	φ _s Resistance	54.52 k	
	Applied	15.49 k	
	#	0	
•			
en			
Reinforcement			
or or			
ju j			
æ			
	,,		
	#	0	
0			
1 st			
ğ			
Extra Bolts 0			
ωÛ			
I			
		 	

Code Rev.	G	Date	5/6/2016
•		Engineer	ZAM
_		Site #	282660
Moment	179.4 k-ft	Carrier	T-Mobile
Axial	9.0 k	•	

0.48 in OK




Plate Stress Ratio:

0.10 (Pass)

Bolt Stress Ratio:

0.28 (Pass)

Prospect CT, CT Site Name: Site Number: 282660 **Engineering Number:** 66383921 Engineer: FΒ 05/06/16 Date: Tower Type: MP

Program Last Updated:

5/13/2014

Design Loads (Factored) - Analysis per TIA-222-G Standards

Design / Analysis / Mapping:	Analysis			
Compression/Leg:	44.8	k	Concrete Strength (fc):	4000 psi
Uplift/Leg:	0.0	k	Pad Tension Steel Depth:	20.00 in
Total Shear:	21.9	k	ϕ_{Shear} :	0.75
Moment:	2334.0	k-ft	$\phi_{Flexure/Tension}$:	0.90
Tower + Appurtenance Weight:	44.8	k	Φ _{Compression} :	0.65
Depth to Base of Foundation (I + t - h):	4.00	ft	β:	0.85
Diameter of Pier (d):	7.00	ft	Bottom Pad Rebar Size #:	9
Height of Pier above Ground (h):	1.00		# of Bottom Pad Rebar:	27
Width of Pad (W):	25.00	ft	Pad Bottom Steel Area:	27.00 in ²
Length of Pad (L):	25.00	ft	Pad Steel F _v :	60000 psi
Thickness of Pad (t):	2.00	ft	Top Pad Rebar Size #:	9
Tower Leg Center to Center:	0.00	ft	# of Top Pad Rebar:	27
Number of Tower Legs:	1.0	(1 if MP or GT)	Pad Top Steel Area:	27.00 in ²
Tower Center from Mat Center:	0.00	ft	Pier Rebar Size #:	7
Depth Below Ground Surface to Water Table:	99.00	ft	Pier Steel Area (Single Bar):	0.60 in ²
Unit Weight of Concrete:	150.0	pcf	# of Pier Rebar:	60
Unit Weight of Soil Above Water Table:	130.0	pcf	Pier Steel F _y :	60000 psi
Unit Weight of Water:	62.4	pcf	Pier Cage Diameter:	76.0 in
Unit Weight of Soil Below Water Table:	67.6	pcf	Rebar Strain Limit:	0.008
Friction Angle of Uplift:	15.0	Degrees	Steel Elastic Modulus:	29000 ksi
Ultimate Coefficient of Shear Friction:	0.45		Tie Rebar Size #:	4
Ultimate Compressive Bearing Pressure:	50000.0	psf	Tie Steel Area (Single Bar):	0.20 in ²
Ultimate Passive Pressure on Pad Face:	0.0	psf	Tie Spacing:	6 in
φ _{Soil and Concrete Weight} :	0.9		Tie Steel F _y :	60000 psi
ϕ_{Soil} :	0.75			

Overturning Moment Usage

Design OTM: 2443.5 k-ft **OTM** Resistance: 4599.0 k-ft

0.53 Result: OK Design OTM / OTM Resistance:

Soil Bearing Pressure Usage

Net Bearing Pressure: 1467 psf Factored Nominal Bearing Pressure: 37500 psf 0.04 Result: OK Net Bearing Pressure/Factored Nominal Bearing Pressure:

Load Direction Controling Design Bearing Pressure: Diagonal to Pad Edge

Sliding Factor of Safety


Total Factored Sliding Resistance: 133.2 k

Sliding Design / Sliding Resistance: 0.16 Result: OK

One Way Shear, Flexual Capacity, and Punching Shear

Factored One Way Shear (V _u):	150.5 k
One Way Shear Capacity (ϕV_c):	569.2 k - ACI11.3.1.1
$V_u / \phi V_c$:	0.26 Result: OK
Load Direction Controling Shear Capacity:	Parallel to Pad Edge
Lower Steel Pad Factored Moment (M _u):	880.3 k-ft
Lower Steel Pad Moment Capacity (ϕM_n):	2348.0 k-ft - ACI10.3
$M_u / \phi M_n$:	0.37 Result: OK
Load Direction Controling Flexural Capacity:	Parallel to Pad Edge
Upper Steel Pad Factored Moment (M _u):	583.9 k-ft
Upper Steel Pad Moment Capacity (ϕM_n):	2348.0 k-ft
$M_u / \phi M_n$:	0.25 Result: OK
Lower Pad Flexural Reinforcement Ratio:	0.0045 OK - Minimum Reinforcement Ratio Met - ACI10.5.1
Upper Pad Flexural Reinforcement Ratio:	0.0045 OK - Minimum Reinforcement Ratio Met - ACI10.5.1
Lower Pad Reinforcement Spacing:	11 in - Pad Reinforcing Spacing OK - ACI7.12.2.2 & 10.5.4
Upper Pad Reinforcement Spacing:	11 in - Pad Reinforcing Spacing OK - ACI7.12.2.2 & 10.5.4
Factored Punching Shear (V _u):	12.1 k
Nominal Punching Shear Capacity $(\phi_c V_n)$:	1239.8 k - ACI11.12.2.1
$V_u / \phi V_c$:	0.01 Result: OK
Factored Moment in Pier (M _u):	2399.7 k-ft
Pier Moment Capacity (ϕM_n):	6019.8 k-ft
$M_u / \phi M_n$:	0.40 Result: OK
Factored Shear in Pier (V _u):	21.9 k
Pier Shear Capacity (ϕV_n):	527.9 k
$V_u / \phi V_c$:	0.04 Result: OK
Pier Shear Reinforcement Ratio:	0.0004 No Ties Necessary for Shear - ACI11.5.6.1
Factored Tension in Pier (T _u):	0.0 k
Pier Tension Capacity (ϕT_n):	1944.0 k
$T_u / \phi T_n$:	0.00 Result: OK
Factored Compression in Pier (P _u):	44.8 k
Pier Compression Capacity (ϕP_n):	9734.2 k - ACI10.3.6.2
$P_u / \phi P_n$:	0.00 Result: OK
Pier Compression Reinforcement Ratio:	0.006 OK - Reinforcement Ratio Met - ACI10.9.1 & 10.8.4
$M_u/\phi_B M_n + T_u/\phi_T T_n$:	0.40 Result: OK

Nominal and Design Moment Capacity and Factored Design Loads



T - Mobile -T-MOBILE NORTHEAST LLC

SITE #: CTNH302A

SITE NAME: CTNH302/CLRCHANNEL/PROSP

SITE ADDRESS:

151 WATERBURY RD

PROSPECT, CT 06712

EXISTING WIRELESS BROADBAND FACILITY MODIFICATION

CONSTRUCTION DRAWINGS

(EXISITING CONFIGURATION 702CU)

(PROPOSED CONFIGURATION 792DB)

VICINITY MAP SITE LOCATION (* 151 CT-69 Waterbur Rd, Prospect, CT 06712

DO NOT SCALE DRAWINGS

CONTRACTOR SHALL VERIFY PLANS AND EXISTING DIMENSIONS AND CONDITIONS ON THE JOB SITE AND SHALL IMMEDIATELY NOTIFY THE ARCHITECT IN WRITING OF ANY DISCREPANCIES BEFORE PROCEEDING WITH THE WORK OR BE RESPONSIBLE FOR SAME



CALL BEFORE YOU DIG:

CALL 800 922 4455, OR 811

CALL THREE WORKING DAYS PRIOR TO DIGGING SAFETY PRECAUTIONS SHALL BE IMPLEMENTED BY CONTRACTOR(S) AT A TRENCHING IN ACCORDANCE WITH CURRENT OSHA STANDARDS. COLOR CODE FOR UTILITY LOCATIONS

FLECTRIC - RED SEWER

GAS/OIL - YELLOW TEL/CATV - ORANGE RECLAIMED WATER

- GRFFN PROPOSED EXCAVATION - WHITE

WWW CBYD COM

. THE CONTRACTOR SHALL OBTAIN AUTHORIZATION TO PROCEED WITH CONSTRUCTION PRIOR TO STARTING WORK ON ANY ITEM NOT CLEARLY DEFINED BY THE CONSTRUCTION DRAWINGS/CONTRACT

5. THE CONTRACTOR SHALL VISIT THE JOB SITE PRIOR TO THE SUBMISSION OF BIDS OR PERFORMING WORK TO FAMILIARIZE

PROJECT CAN BE CONSTRUCTED IN ACCORDANCE WITH THE

GENERAL NOTES

WRITING OTHERWISE.

CONTRACT DOCUMENTS.

THE CONTRACTOR SHALL GIVE ALL NOTICES AND COMPLY WITH ALL LAWS

THE CONTRACTOR STALE GIVE ALL NOTICES AND COMPLT WITH ALL LAWS, ORDINANCES, ROLLES, REGULATIONS AND LAWFUL ORDERS OF ANY PUBLIC AUTHORITY, MUNICIPAL AND UTILITY COMPANY SPECIFICATIONS, AND LOCAL AND STATE JURISDICTIONAL CODES BEARING ON THE PERFORMANCE OF THE WORK. THE WORK PERFORMED ON THE PROJECT AND THE MATERIALS INSTALLED SHALL

BE IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS AND

THE ARCHITECT/ENGINEER HAVE MADE EVERY EFFORT TO SET

FORTH IN THE CONSTRUCTION AND CONSTRUCT DOCUMENTS THE COMPLETE SCOPE OF WORK. THE CONTRACTOR BIDDING THE JOB IS NEVERTHELESS CAUTIONED THAT MINOR OMISSIONS OR ERRORS

IN THE DRAWINGS AND OR SPECIFICATIONS SHALL NOT EXCUSE

. THE CONTRACTOR OR BIDDER SHALL BEAR THE RESPONSIBILITY OF

OF THE CONTRACTOR'S PROPOSAL OR PERFORMANCE OF WORK, IN

NOTIFYING (IN WRITING) THE T-MOBILE REPRESENTATIVE OF ANY

CONFLICTS, ERRORS, OR OMISSIONS PRIOR TO THE SUBMISSION

THE EVENT OF DISCREPANCIES, THE CONTRACTOR SHALL PRICE

THE MORE COSTLY OR EXPENSIVE WORK, UNLESS DIRECTED IN

. THE SCOPE OF WORK SHALL INCLUDE FURNISHING OF ALL MATERIALS, EQUIPMENT, LABOR AND ALL OTHER MATERIALS AND

HIMSELF WITH THE FIELD CONDITIONS AND TO VERIFY THAT THE

LABOR DEEMED NECESSARY TO COMPLETE THE WORK/PROJECT AS

IMPROVEMENTS IN ACCORDANCE WITH THE INTENT OF THESE

SAID CONTRACTOR FROM COMPLETING THE PROJECT AND

- 7. THE CONTRACTOR SHALL INSTALL ALL EQUIPMENT AND MATERIALS ACCORDING TO THE MANUFACTURER'S/VENDOR'S SPECIFICATIONS UNLESS NOTED OTHERWISE OR WHERE LOCAL CODES OR ORDINANCES TAKE PRECEDENCE.
- . THE CONTRACTOR SHALL PROVIDE A FULL SET OF CONSTRUCTION DOCUMENTS AT THE SITE UPDATED WITH THE LATEST REVISIONS AND ADDENDUM OR CLARIFICATIONS AVAILABLE FOR THE USE BY ALL PERSONNEL INVOLVED WITH THE PROJECT.

- 9. THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE PROJECT DESCRIBED HEREIN. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR ALL CONSTRUCTION MEANS, METHODS, TECHNIQUES SEQUENCES AND PROCEDURES AND FOR COORDINATING ALL PORTIONS OF THE WORK UNDER CONTRACT.
- 10. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ANY PERMITS AND INSPECTIONS WHICH ARE REQUIRED FOR THE WORK BY THE ARCHITECT/ENGINEER, THE STATE, COUNTY, OR LOCAL GOVERNMENT AUTHORITY.
- 11. THE CONTRACTOR SHALL MAKE NECESSARY PROVISIONS TO PROTECT EXISTING IMPROVEMENTS, EASEMENTS, PAVING, CURBING ETC., DURING CONSTRUCTION. UPON COMPLETION OF WORK, THE CONTRACTOR SHALL REPAIR ANY DAMAGE THAT MAY HAVE OCCURRED DUE TO CONSTRUCTION ON OR ABOUT THE PROPERTY
- 12 THE CONTRACTOR SHALL KEEP THE GENERAL WORK AREA CLEAN AND HAZARD FREE DURING CONSTRUCTION AND DISPOSE OF ALL DIRT, DEBRIS, RUBBISH AND REMOVE EQUIPMENT NOT SPECIFIED AS REMAINING ON PROPERTY, PREMISES SHALL BE LEFT IN CLEAN CONDITION AND FREE FROM PAINT SPOTS, DUST, OR SMUDGES O ANY NATURE.
- 13. THE CONTRACTOR SHALL COMPLY WITH ALL OSHA REQUIREMENTS, AS WELL AS THE LATEST EDITIONS OF ANY PERTINENT STATE SAFETY REGULATIONS.
- 14. THE CONTRACTOR SHALL NOTIFY THE T-MOBILE REPRESENTATIVE WHERE A CONFLICT OCCURS ON ANY OF THE CONTRACT DOCUMENTS. THE CONTRACTOR IS NOT TO ORDER MATERIAL OR CONSTRUCT ANY PORTION OF THE WORK THAT IS IN CONFLICT UNTIL CONFLICT IS RESOLVED BY THE T-MOBILE REPRESENTATIVE
- 15. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS, ELEVATIONS, PROPERTY LINES, ETC., ON THE JOB
- 16. THE CONTRACTOR SHALL RETURN ALL DISTURBED AREAS TO THEIR ORIGINAL CONDITION AT THE COMPLETION OF WORK.
- 17. FINAL DESIGN PENDING STRUCTURAL EVALUATION

PROJECT INFORMATION

SITE NUMBER: CTNH302A SITE NAME: CTNH302/CLRCHANNEL/PROSP SITE ADDRESS: 151 WATERBURY RD PROSPECT, CT 06712

N 41.52300600 -72.99781800 LAT./LONG.:

PROPERTY OWNER: CLEAR CHANNEL

SHEET

T-1 TIT

T-MOBILE NORTHEAST, LLC. 35 GRIFFIN ROAD SOUTH BLOOMFIELD CT 06002 (860) 692-7100

PROJECT MANAGER TRANSCEND WRELESS LLC 10 INDUSTRIAL AVE, SUITE #3

ARCHITECT/ENGINEER FORESITE LLC. Site Design Services 462 Walnut Street Newton, MA 02460

PROJECT DESCRIPTION

-MOBILE NORTHEAST LLC PROPOSES THE MODIFICATION OF AN EXISTING WIRELESS BROABAND FACILITY CONSISTING OF REPLACEMENT OF 3 EXISTING AIR21 ANTENNAS WITH (3) AIR32 ANTENNAS, ADD (1) (6×12) FIBER TRUNK

SHEET	INDEX
DESCRIP	TION
TLE SHEET	
NITO LOTOD'C NOTEC	

N-1 CONTRACTOR'S NOTES A-1 SITE PLAN A-2 ELEVATION ANTENNA PLAN AND DETAILS GROUNDING AND POWER ONE LINE DIAGRAM

SHEET NUMBER

| - ′

10 INDUSTRIAL AVE MAHWAH NJ 07430 ANSCEND@TRANSCENDWRELESS.COM TELEPHONE: (201) 684-0066

FORESITE LLC

Transcend Wireless

T - Mobile -

T-MOBILE NORTHEAST, LLC

SITE DESIGN SERVICES 462 WALNUT STREET NEWTON, MA 02460 TEL:617-527-3031

	SUBMITTALS	
DATE	DESCRIPTION	REVISION
05/4/16	ISSUED FOR REVIEW	A

DEPT.	DATE	APP'D	REVISIONS
RFE			
RF MAN.			
ZONING			
OPS			
CONSTR.			
SITE AC.			

PROJECT NO:	CTNH302A
DRAWN BY:	MS
CHECKED BY:	SM

PROFESSIONAL SEAL

THIS DOCUMENT IS THE CREATION, DESIGN, PROPERTY AND COPYRIGHTED WORK OF T-MOBILE. ANY DUPLICATION OR USE WITHOUT EXPRESS WRITTEN CONSENT IS STRICTLY PROHIBITED.

SITE NUMBER CTNH302A

CTNH302/CLRCHANNEL/PROSP

SITE ADDRESS 151 WATERBURY RD PROSPECT, CT 06712

SHEET TITLE

TITLE SHEET

ELECTR<u>ICAL NOTES:</u>

- 1. INCLUDE ALL LABOR, MATERIALS, EQUIPMENT, PLANT SERVICES AND ADMINISTRATIVE TASKS REQUIRED TO COMPLETE AND MAKE OPERABLE THE ELECTRICAL WORK SHOWN ON THE DRAWINGS AND SPECIFIED HEREIN, INCLUDING BUT NOT LIMITED TO THE
- A. PREPARE AND SUBMIT SHOP DRAWINGS. DIAGRAMS AND
- B. PROCURE ALL NECESSARY PERMITS AND APPROVALS AND PAY ALL REQUIRED FEES AND CHARGES IN CONNECTION WITH THE WORK OF THIS CONTRACT.
- C. SUBMIT AS-BUILT DRAWINGS, OPERATING AND MAINTENANCE INSTRUCTIONS AND MANUALS
- D. EXECUTE ALL CUTTING, DRILLING, ROUGH AND FINISH
 PATCHING OF EXISTING OR NEWLY INSTALLED CONSTRUCTION REQUIRED FOR THE WORK OF THIS CONTRACT. FOR SLAB PENETRATIONS THROUGH POST TENSION SLABS, X-RAY EXACT AREA OF PENETRATION PRIOR TO PERFORMING WORK. COORDINATE ALL X-RAY WORK WITH BUILDING ENGINEER. E. PROVIDE HANGERS, SUPPORTS, FOUNDATIONS, STRUCTURAL
- FRAMING SUPPORTS AND BASES FOR CONDUIT AND EQUIPMENT PROVIDED OR INSTALLED UNDER THE WORK OF HIS CONTRACT. PROVIDE COUNTER FLASHING, SLEEVES AND SEALS FOR FLOOR AND WALL PENETRATIONS
- MAINTAIN ALL EXISTING ELECTRICAL SERVICES IN THE
 BUILDING AREAS NOT AFFECTED BY THE ALTERATION DURING THE PROGRESS OF THE WORK INCLUDING PROVIDING ALL TEMPORARY JUMPERS, CONDUITS, CAPS, PROTECTIVE DEVICES, CONNECTIONS AND EQUIPMENT REQUIRED. PROVIDE TEMPORARY LIGHT AND POWER FOR CONSTRUCTION
- 2. IT IS THE INTENT OF THESE DRAWINGS AND SPECIFICATIONS TO CALL FOR AN INSTALLATION THAT IS COMPLETE IN EVERY RESPECT. IT IS NOT THE INTENT TO GIVE EVERY DETAIL ON THE DRAWINGS AND IN THE SPECIFICATIONS, IF AN ITEM OF WORK IS INDICATED IN THE DRAWINGS, IT IS CONSIDERED SUFFICIENT FOR INCLUSION IN THE CONTRACT. FURNISH AND INSTALL ALL MATERIAL AND FOLIPMENT USUALLY FURNISHED OR NEEDED TO MAKE A COMPLETE INSTALLATION WHETHER OR NO SPECIFICALLY MENTIONED IN THE CONTRACT DOCUMENTS.

GENERAL REQUIREMENTS

- 1. PROVIDE ALL WORK IN ACCORDANCE WITH THE NATIONAL ELECTRICAL CODE (NEC) AND LOCAL AND STATE ELECTRICAL
- 2. THE ELECTRICAL PLANS ARE DIAGRAMMATIC ONLY. REFER TO THE ARCHITECTURAL PLANS FOR THE EXACT DIMENSIONS OF THE BUILDING.
- INFORMATION/DRAWINGS PROVIDED TO ENGINEERING.
 CONTRACTOR IS TO VERIFY ALL EXISTING RATINGS AND LOADS PRIOR TO PURCHASING OF SPECIFIED EQUIPMENT FOR COMPLIANCE TO NEC. CONTRACTOR TO NOTIFY ENGINEER OF ANY DISCREPANCIES AND REQUEST FURTHER DIRECTION BY
- 4. EXISTING BUILDING EQUIPMENT IS NOTED ON THE DRAWINGS. NEW OR RELOCATED EQUIPMENT IS SHOWN WITH SOLID LINES.
 FUTURE EQUIPMENT (NOT IN THIS CONTRACT) IS DEPICTED WITH
 SHADED LINES. REQUEST CLARIFICATION OF DRAWINGS OR OF SPECIFICATIONS PRIOR TO PRICING OR INSTALLATION
- A. AFTER CAREFULLY STUDYING THE DRAWINGS AND SPECIFICATIONS, AND BEFORE SUBMITTING THE PROPOSAL, MAKE A MANDATORY SITE VISIT TO ASCERTAIN CONDITIONS OF THE SITE AND THE NATURE AND EXACT QUANTITY OF WORK TO BE PERFORMED. NO EXTRA COMPENSATION WILL BE ALLOWED FOR FAILURE TO NOTIFY THE OWNER, IN WRITING, OF ANY DISCREPANCIES THAT MAY HAVE BEEN NOTED BETWEEN THE EXISTING CONDITIONS AND THE DRAWINGS AND SPECIFICATIONS
- B. VERIFY ALL MEASUREMENTS AT THE SITE AND BE RESPONSIBLE FOR CORRECTNESS OF SAME. 6. QUALITY, WORKMANSHIP, MATERIALS AND SAFETY
- A. PROVIDE NEW MATERIALS AND EQUIPMENT OF A DOMESTIC MANUFACTURER BY THOSE REGULARLY ENGAGED IN THE PRODUCTION AND MANUFACTURE OF SPECIFIED MATERIALS AND EQUIPMENT. WHERE UL, OR OTHER AGENCY, HAS ESTABLISHED STANDARDS FOR MATERIALS, PROVIDE MATERIALS WHICH ARE LISTED AND LABELED ACCORDINGLY. THE COMMERCIALLY STANDARD ITEMS OF EQUIPMENT AND THE SPECIFIC NAMES MENTIONED HEREIN ARE INTENDED FOR THE PROPER FUNCTIONING OF THE WORK.

 B. WORK SHALL BE PERFORMED BY WORKMEN SKILLED IN THE
- TRADE REQUIRED FOR THE WORK, INSTALL MATERIALS AND EQUIPMENT TO PRESENT A NEAT APPEARANCE WHEN COMPLETED AND IN ACCORDANCE WITH THE APPROVED RECOMMENDATIONS OF THE MANUFACTURER AND IN ACCORDANCE WITH CONTRACT DOCUMENTS.
- C. PROVIDE LABOR, MATERIALS, APPARATUS AND APPLIANCES ESSENTIAL TO THE FUNCTIONING OF THE SYSTEMS DESCRIBED OR INDICATED HEREIN, OR WHICH MAY BE REASONABLY IMPLIED AS ESSENTIAL WHENEVER MENTIONED IN THE CONTRACT DOCUMENT OR NOT
- D. MAKE WRITTEN REQUESTS FOR SUPPLEMENTARY INSTRUCTIONS TO ARCHITECT/ENGINEER IN CASE OF DOUBT AS TO WORK INTENDED OR IN EVENT OF NEED FOR EXPLANATION THEREOF.
- EXPLANATION THEREOF.

 E. PERFORMANCE AND MATERIAL REQUIREMENTS SCHEDULED OR SPECIFIED ARE MINIMUM STANDARD ACCEPTABLE. THE RIGHT TO JUDGE THE QUALITY OF EQUIPMENT THAT DEVIATES FROM THE CONTRACT DOCUMENT REMAINS SOLELY WITH ARCHITECT/ENGINEER. CONTRACT DOCUMENT OR NOT.

GUARANTEE

I. GUARANTEE MATERIALS, PARTS AND LABOR FOR WORK FOR ONE YEAR FROM THE DATE OF ISSUANCE OF OCCUPANCY PERMIT.
DURING THAT PERIOD, MAKE GOOD FAULTS OR IMPERFECTIONS THAT MAY ARISE DUE TO DEFECTS OR OMISSIONS IN MATERIALS OR WORKMANSHIP WITH NO ADDITIONAL COMPENSATION AND AS DIRECTED BY ARCHITECT

- . REMOVE ALL CONSTRUCTION DEBRIS RESULTING FROM THE
- 2. CLEAN FOUIPMENT AND SYSTEMS FOLLOWING THE COMPLETION THE PROJECT TO THE SATISFACTION OF THE ENGINEER.

COORDINATION AND SUPERVISION

1. CAREFULLY LAY OUT ALL WORK IN ADVANCE TO AVOID UNNECESSARY CUTTING, CHANNELING, CHASING OR DRILLING OF FLOORS, WALLS, PARTITIONS, CEILINGS OR OTHER SURFACES.
WHERE SUCH WORK IS NECESSARY, HOWEVER, PATCH AND
REPAIR THE WORK IN AN APPROVED MANNER BY SKILLED MECHANICS AT NO ADDITIONAL COST TO THE OWNER. RENDER FULL COOPERATION TO OTHER TRADES WHERE WORK WILL BE INSTALLED IN CLOSE PROXIMITY TO WORK OF OTHER TRADES WORKING OUT SPACE CONDITIONS. IF WORK IS INSTALLED BEFORE COORDINATION WITH OTHER TRADES, OR CAUSES INTERFERENCE, MAKE CHANGES NECESSARY TO CORRECT CONDITIONS WITHOUT EXTRA CHARGE.

2 IATTIMBLI2

- AS-BUILT DRAWINGS:
 A. UPON COMPLETION OF THE WORK, FURNISH TO THE OWNER
- 2. SERVICE MANUALS:
- A. UPON COMPLETION OF THE WORK, FULLY INSTRUCT T-MOBILE EQUIPMENT AND SYSTEMS.
- B. PROVIDE 3 COMPLETE BOUND SETS OF INSTRUCTIONS FOR OPERATING AND MAINTAINING ALL SYSTEMS AND EQUIPMENT.

- CUTTING AND PATCHING

 1. PROVIDE ALL CUTTING, DRILLING, ROUGH AND FINISH PATCHING REQUIRED TO COMPLETE THE WORK.

 2. OBTAIN OWNER APPROVAL PRIOR TO CUTTING THROUGH FLOORS OR WALLS FOR PIPING OR CONDUIT.

- TESTS, INSPECTION AND APPROVAL

 1. BEFORE ENERGIZING ANY ELECTRICAL INSTALLATION, INSPECT EACH UNIT IN DETAIL. TIGHTEN ALL BOLTS AND CONNECTIONS (TORQUE-TIGHTEN WHERE REQUIRED) AND DETERMINE THAT ALL COMPONENTS ARE ALIGNED, AND THE EQUIPMENT IS IN SAFE,
- OPERATIONAL CONDITION.
 2. PROVIDE THE COMPLETE ELECTRICAL SYSTEM FREE OF GROUND FAULTS AND SHORT CIRCUITS SUCH THAT THE SYSTEM WILL OPERATE SATISFACTORILY UNDER FULL LOAD CONDITIONS,
 WITHOUT EXCESSIVE HEATING AT ANY POINT IN THE SYSTEM.

- SPECIAL REQUIREMENTS
 1. DO NOT LEAVE ANY WORK INCOMPLETE NOR ANY HAZARDOUS SITUATIONS CREATED WHICH WILL AFFECT THE LIFE OR SAFETY OF THE PUBLIC AND/OR BUILDING OCCUPANTS. DO NOT INTERFERE WITH OR CUTOFF ANY OF THE EXISTING SERVICES WITHOUT THE OWNER'S WRITTEN PERMISSION.

 2. WHEN NECESSARY TO TEMPORARILY DISCONNECT ANY EXISTING
- BUILDING UTILITIES AND SERVICE SYSTEMS, INCLUDING FEEDER OR BRANCH CIRCUITING SUPPLYING EXISTING FACILITIES,
 CONFER WITH THE OWNER AND ARRANGE THE PERIOD OF INTERRUPTION FOR A TIME MUTUALLY AGREED LIPON SHUTDOWN NOTE: SCHEDULE AND NOTIFY OWNER 48 HOURS PRIOR TO SHUTDOWN. ALL SHUTDOWN WORK TO BE

1. ROUTE ALL GROUNDING CONDUCTORS AS SHOWN ON

SCHEDULED AT A TIME CONVENIENT TO OWNER.

- CONDUIT/GROUNDING RISER.
- CONDUTY/GROUNDING RISER.

 2. ROUTE 500 KCMIL CU. THHN CONDUCTOR FROM THE MGB LOCATION TO BUILDING STEEL. VERIFY BUILDING STEEL IS EFFECTIVELY GROUNDED PER NEC TO THE MAIN SERVICE
- GROUNDING ELECTRODE CONDUCTOR (GEC).

 MAKE ALL GROUND CONNECTIONS FROM MGB TO ELECTRICAL EQUIPMENT WITH 2 HOLE, CRIMP TYPE, BURNDY COMPRESSION
- TERMINATIONS, SIZED AS REQUIRED.

 4. USE 1 HOLE, CRIMP TYPE, BURNDY COMPRESSIONS
 TERMINATIONS, SIZED AS REQUIRED, AT EQUIPMENT GROUND
- 5. HIRE AN INDEPENDENT LAB TO PERFORM THE SPECIFIED OHMS TESTING. PROVIDE 4 SETS OF THE CERTIFIED DOCUMENTS TO THE OWNER FOR VERIFICATION PRIOR TO THE PROJECT COMPLETION.

RACEWAYS 1. ALL WIRING TO BE INSTALLED IN CONDUIT SYSTEMS IN

- ACCORDANCE WITH THE FOLLOWING: A. EXTERIOR FEEDERS AND CONTROL, WHERE UNDERGROUND, TO
- BE IN SCH 40 PVC. B. EXTERIOR. ABOVE GROUND POWER CONDUITS TO BE GALVANIZED RIGID STEEL (RGS).
 C. ALL TELECOMMUNICATION CONDUITS, INTERIOR/EXTERIOR, TO
- D. INSTALL PULL ROPES IN ALL NEW EMPTY CONDUITS INSTALLED
- ON THIS PROJECT. ON THIS PROJECT.

 E. ALL TELECOM CONDUITS AND PULL BOXES INSTALLED ON THIS PROJECT TO BE LABELED "T-MOBILE". OWNER WILL PROVIDE LABELS FOR CONTRACTOR TO INSTALL.
- F. INTERIOR FEEDERS TO BE INSTALLED IN E.M.T. WITH STEEL
- COMPRESSION FITTINGS.
 G. MINIMUM SIZE CONDUIT TO BE ¾" TRADE SIZE
- UNLESS OTHERWISE INDICATED ON THE DRAWINGS.
 H. FINAL CONNECTIONS TO MOTORS AND VIBRATING EQUIPMENT TO BE INSTALLED IN LIQUID-TIGHT FLEXIBLE METAL CONDUIT.
- I. CONDUIT TO BE RUN CONCEALED IN CEILINGS, FINISHED
 AREAS OR DRYWALL PARTITIONS, UNLESS OTHERWISE NOTED.
- J. THE ROUTING OF CONDUITS INDICATED ON THE DRAWINGS IS DIAGRAMMATIC. BEFORE INSTALLING ANY WORK, EXAMINE THE WORKING LAYOUTS AND SHOP DRAWINGS OF THE OTHER TRADES TO DETERMINE THE EXACT LOCATIONS AND
- K ALL EXTERIOR MOUNTING HARDWARE TO BE GALVANIZED STEEL. COORDINATE WITH BUILDING ENGINEER PRIOR TO ATTACHING TO BUILDING STRUCTURE.

RACEWAYS CONT'D

- L. PENETRATIONS OF WALLS, FLOORS AND ROOFS, FOR THE PASSAGE OF ELECTRICAL RACEWAYS. TO BE PROPERLY SEALED AFTER INSTALLATION OF RACEWAYS SO AS TO THE WALL, FLOOR OR ROOF SYSTEM TO BE PENETRATED. SEAL ALL CONDUIT PENETRATIONS THROUGH FIRE OR SMOKE PARTITIONS TO MAINTAIN PROPER RATING OF WALL OR CEILING.
 M. PROVIDE ALL CONDUIT ENDS WITH INSULATED METALLIC
- GROUNDING BUSHINGS
- N. CONDUIT TO BE SUPPORTED AT MAXIMUM DISTANCE OF 8'-0". OR AS REQUIRED BY NEC. IN HORIZONTAL AND VERTICAL DIRECTIONS
- VERTICAL DIRECTIONS.

). PROVIDE STAINLESS STEEL BLANK COVER PLATES FOR ALL JUNCTION BOXES AND/OR DUTLET BOXES NOT USED IN EXPOSED AREAS. PROVIDE ALL OTHER UNUSED BOXES WITH STANDARD STEEL COVER PLATES.
- P. WHERE APPLICABLE, PROVIDE ROOFTOP CONDUIT SUPPORT SYSTEM, CONFORMING TO ROOFTOP WARRANTY REQUIREMENTS,

WIRES AND CABLES

- 1. CONTRACTOR TO COORDINATE WITH EQUIPMENT SUPPLIER AND VENDOR FOR EXACT EQUIPMENT OVER-CURRENT PROTECTION VOLTAGE, WIRE SIZE AND PLUG CONFIGURATION, IF APPLICABLE,
- 2. ALL EQUIPMENT/DEVICES TO BE PROVIDED WITH INSULATED GROUND CONDUCTOR.

 3. ALL WIRE AND CABLE TO BE 600VOLT, COPPER, WITH THWN/

- 3. ALL WIRE AND CABLE TO BE BOUVOLT, COPPER, WITH THWN/
 THHIN INSULATION, EXCEPT AS NOTED.

 4. WIRE FOR POWER AND LIGHTING WILL NOT BE LESS THAN NO.
 12AWG. ALL WIRE NO. 8 AND LARGER TO BE STRANDED.
 5. CONTROL WIRING IS NOT TO BE LESS THAN NO. 14AWG,
 FLEXIBLE IN SINGLE CONDUCTORS OR MULTI—CONDUCTOR CABLES, CONTROL WIRING WILL CONSIST OF MULTI-CONDUCTOR CABLES WHEREVER POSSIBLE. CABLES TO BE PROVIDED WITH AN OVERALL FLAME-RETARDANT. EXTRUDED JACKET AND RATED
- FOR PLENUM USE, ALL CONTROL WIRE TO BE 600VOLT RATED.
 6. WIRE PREVIOUSLY PULLED INTO CONDUIT IS CONSIDERED USED AND IS NOT TO BE RE-PULLED. 7. HOME RUNS AND BRANCH CIRCUIT WIRING FOR 20A, 120V
- LENGTH (FT.) 0 TO 50 51 TO 100 HOME RUN WIRE SIZE NO. 12 NO. 10
- 101 TO 150 VOLTAGE DROP IS NOT TO EXCEED 3%. 9. MAKE ALL CONNECTIONS WITH UL APPROVED, SOLDERLESS, PRESSURE TYPE INSULATED CONNECTORS: SCOTCHLOK OR AND APPROVED EQUAL.
- WIRING DEVICES 1. ALL RECEPTACLES INSTALLED IN THIS PROJECT TO BE GROUNDING TYPE, WITH GROUNDING PIN SLOT CONNECTED TO DEVICE GROUND SCREW FOR GROUND WIRE CONNECTION.
- DISCONNECT SWITCHES AND FUSES

 1. DISCONNECT SWITCHES TO BE VOLTAGE—RATED TO SUIT THE CHARACTERISTICS OF THE SYSTEM FROM WHICH THEY ARE
- 2. PROVIDE HEAVY-DUTY, METAL-ENCLOSED, EXTERNALLY-OPERATED DISCONNECT SWITCHES, FUSED OR UNFUSED, OF SUCH TYPE AND SIZE AS REQUIRED TO PROPERLY PROTECT OR DISCONNECT THE LOAD FOR WHICH THEY ARE INTENDED.
- 3. PROVIDE NEMA 1 DISCONNECT SWITCHES FOR INTERIOR INSTALLATION, NEMA 3R FOR EXTERIOR INSTALLATION.
- 4. DISCONNECT SWITCHES TO BE MANUFACTURED BY A. GENERAL ELECTRIC COMPAN B. SQUARE-D
- 5. PROVIDE RK-1 TYPE FUSES, UNLESS NOTED OTHERWISE. INSTALL DISCONNECT SWITCHES WHERE INDICATED ON
- 2. INSTALL FUSES IN FUSIBLE DISCONNECT SWITCHES. FUSES
- MUST MATCH IN TYPE AND RATING. 3. FUSES TO BE MOUNTED SO THAT THE LABELS SHOWING THEIR RATINGS CAN BE READ WITHOUT REQUIRING FUSE REMOVAL.
- 4. FURNISH AND DEPOSIT SPARE FUSES AT THE JOB SITE AS
- A. THREE SPARES FOR EACH TYPE AND SIZE, IN EXCESS OF 60A, USED FOR INITIAL FUSING.
 B. TEN PERCENT SPARES FOR EACH TYPE AND SIZE, UP TO
- AND INCLUDING 60A, USED FOR INITIAL FUSING, IN NO CASE WILL LESS THAN THREE FUSES OF ONE PARTICULAR TYPE AND SIZE BE FURNISHED.

GENERAL NOTES:

CHANGE ORDER.

1. THESE SPECIFICATIONS AND CONSTRUCTION DRAWINGS ACCOMPANYING THEM DESCRIBE THE WORK TO BE DONE AND

- THE MATERIALS TO BE FURNISHED FOR CONSTRUCTION.
 2. THE DRAWINGS AND SPECIFICATIONS ARE INTENDED TO BE FULLY EXPLANATORY AND SUPPLEMENTARY, HOWEVER, SHOULD ANYTHING BE SHOWN, INDICATED, OR SPECIFIED ON ONE AND NOT THE OTHER, IT SHALL BE DONE THE SAME AS IF SHOWN, INDICATED OR SPECIFIED IN BOTH
- THE INTENTION OF THE DOCUMENTS IS TO INCLUDE ALL LABOR AND MATERIALS REASONABLY NECESSARY FOR THE PROPER EXECUTION AND COMPLETION OF THE WORK AS STIPULATED IN 4. THE PURPOSE OF THE SPECIFICATIONS IS TO INTERPRET THE
- INTENT OF THE DRAWINGS AND TO DESIGNATE THE METHOD OF THE PROCEDURE, TYPE AND QUALITY OF MATERIALS REQUIRED TO COMPLETE THE WORK. O COMPLETE INE WORK.

 MINOR DEVIATIONS FROM THE DESIGN LAYOUT ARE ANTICIPATED AND SHALL BE CONSIDERED AS PART OF THE WORK. NO CHANGES THAT ALTER THE CHARACTER OF THE WORK WILL BE MADE OR PERMITTED BY THE OWNER WITHOUT ISSUING A

CONFLICTS

- THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFICATIONS
 OF ALL MEASUREMENTS AT THE SITE BEFORE ORDERING ANY MATERIALS OR DOING ANY WORK. NO EXTRA CHARGE OR COMPENSATION SHALL BE ALLOWED DUE TO DIFFERENCE BETWEEN ACTUAL DIMENSIONS AND DIMENSIONS INDICATED ON THE CONSTRUCTION DRAWINGS. ANY SUCH DISCREPANCY IN DIMENSION WHICH MAY BE FOUND SHALL BE SUBMITTED TO THE OWNER FOR CONSIDERATION BEFORE THE CONTRACTOR PROCEEDS WITH THE WORK IN THE AFFECTED AREAS.

 2. THE BIDDER, IF AWARDED THE CONTRACT, WILL NOT BE
- ALLOWED ANY EXTRA COMPENSATION BY REASON OF ANY MATTER OR THING CONCERNING SUCH BIDDER MIGHT HAVE FULLY INFORMED THEMSELVES PRIOR TO THE BIDDING.
- 3. NO PLEA OF IGNORANCE OF CONDITIONS THAT FXIST. OR OF DIFFICULTIES OR CONDITIONS THAT MAY BE ENCOUNTERED, OR OF ANY OTHER RELEVANT MATTER CONCERNING THE WORK TO BE PERFORMED IN THE EXECUTION OF THE WORK WILL BE ACCEPTED AS AN EXCUSE FOR ANY FAILURE OR OMISSION THE PART OF THE CONTRACTOR TO FULFILL EVERY DETAIL OF ALL THE REQUIREMENTS OF THE CONTRACT DOCUMENTS

- CONTRACTS AND WARRANTIES
 1. CONTRACTOR IS RESPONSIBLE FOR APPLICATION AND PAYMENT OF CONTRACTOR LICENSES AND BONDS
- 2. SEE MASTER CONTRACTION SERVICES AGREEMENT FOR ADDITIONAL DETAILS.

1. ALL MATERIALS MUST BE STORED IN A LEVEL AND DRY FASHION AND IN A MANNER THAT DOES NOT NECESSARILY OBSTRUCT THE FLOW OF OTHER WORK. ANY STORAGE METHOD MUST MEET ALL RECOMMENDATIONS OF THE ASSOCIATED MANUFACTURER

- 1. THE CONTRACTORS SHALL, AT ALL TIMES, KEEP THE SITE FREE FROM ACCUMULATION OF WASTE MATERIALS OR RUBBISH CAUSED BY THEIR EMPLOYEES AT WORK AND AT THE COMPLETION OF THE WORK. THEY SHALL REMOVE ALL RUBBISH FROM AND ABOUT THE BUILDING AREA, INCLUDING ALL THEIR TOOLS, SCAFFOLDING AND SURPLUS MATERIALS AND SHALL LEAVE THEIR WORK CLEAN AND READY TO USE.
- A. VISUALLY INSPECT EXTERIOR SURFACES AND REMOVE ALL TRACES OF SOIL, WASTE MATERIALS, SMUDGES AND OTHER FOREIGN MATTER.
- B. REMOVE ALL TRACES OF SPLASHED MATERIALS FROM B. REMOVE ALL IRACES OF SPLASHED MATERIALS FROM ADJACENT SURFACES.
 C. IF NECESSARY, TO ACHIEVE A UNIFORM DEGREE OF CLEANLINESS, HOSE DOWN THE EXTERIOR OF THE STRUCTURE.
- A. VISUALLY INSPECT INTERIOR SURFACE AND REMOVE ALL
- TRACES OF SOIL, WASTE MATERIALS, SMUDGES AND OTHER FOREIGN MATTER FROM WALLS, FLOOR, AND CEILING. B. REMOVE ALL TRACES OF SPLASHED MATERIALS FROM
- ADJACENT SURFACES.
 C. REMOVE PAINT DROPPINGS, SPOTS, STAINS, AND DIRT FROM FINISHED SURFACES.

CHANGE ORDER PROCEDURE:

REFER TO SECTION 17 OF SIGNED MCSA: SEE PROFESSIONAL SERVICE AGREEMENT FOR MCSA.

- RELATED DOCUMENTS AND COORDINATION

 1. GENERAL CARPENTRY, ELECTRICAL AND ANTENNA DRAWINGS ARE INTERRELATED. IN PERFORMANCE OF THE WORK, THE CONTRACTOR MUST REFER TO ALL DRAWINGS. ALL COORDINATION TO BE THE RESPONSIBILITY OF THE CONTRACTOR.
- 1. CONTRACTOR SHALL SUBMIT SHOP DRAWINGS AS REQUIRED AND LISTED IN THESE SPECIFICATIONS TO THE OWNER FOR
- ALL SHOP DRAWINGS SHALL BE REVIEWED, CHECKED AND CORRECTED BY CONTRACTOR PRIOR TO SUBMITTAL TO THE

- PRODUCTS AND SUBSTITUTIONS

 1. SUBMIT 3 COPIES OF EACH REQUEST FOR SUBSTITUTION. IN EACH REQUEST, IDENTIFY THE PRODUCT OR FABRICATION OR INSTALLATION METHOD TO BE REPLACED BY THE SUBSTITUTION. INCLUDE RELATED SPECIFICATION SECTION AND DRAWING NUMBERS AND COMPLETE DOCUMENTATION SHOWING COMPLIANCE WITH THE REQUIREMENTS FOR SUBSTITUTIONS.
 2. SUBMIT ALL NECESSARY PRODUCT DATA AND CUT SHEETS
- WHICH PROPERLY INDICATE AND DESCRIBE THE ITEMS. PRODUCTS AND MATERIALS BEING INSTALLED. THE CONTRACTOR SHALL, IF DEEMED NECESSARY BY THE OWNER, SUBMIT ACTUAL SAMPLES TO THE OWNER FOR APPROVAL IN LIEU OF CUT

QUALITY ASSURANCE

1. ALL WORK SHALL BE IN ACCORDANCE WITH APPLICABLE LOCAL, STATE AND FEDERAL REGULATIONS. THESE SHALL INCLUDE, BUT NOT BE LIMITED TO THE APPLICABLE CODES SET FORTH BY THE LOCAL GOVERNING BODY. SEE "CODE COMPLIANCE" T-1.

- MINISTRATION

 1. BEFORE THE COMMENCEMENT OF ANY WORK, THE CONTRACTOR

 WILL ASSIGN A PROJECT MANAGER WHO WILL ACT AS A SINGLE

 POINT OF CONTACT FOR ALL PERSONNEL INVOLVED IN THIS PROJECT. THIS PROJECT MANAGER WILL DEVELOP A MASTER SCHEDULE FOR THE PROJECT WHICH WILL BE SUBMITTED TO THE OWNER PRIOR TO THE COMMENCEMENT OF ANY WORK.
- SUBMIT A BAR TYPE PROGRESS CHART, NOT MORE THAN 3
 DAYS AFTER THE DATE ESTABLISHED FOR COMMENCEMENT OF THE WORK ON THE SCHEDULE, INDICATING A TIME BAR FOR AT THE SITE, PROPERLY SEQUENCED AND COORDINATED WITH OTHER ELEMENTS OF WORK AND SHOWING COMPLETION OF THE WORK SUFFICIENTLY IN ADVANCE OF THE DATE ESTABLISHED FOR SUBSTANTIAL COMPLETION OF THE WORK.
- 3. PRIOR TO COMMENCING CONSTRUCTION, THE OWNER SHALL SCHEDULE AN ON-SITE MEETING WITH ALL MAJOR PARTIES. THIS WOULD INCLUDE, BUT NOT LIMITED TO, THE OWNER, PROJECT MANAGER, CONTRACTOR, LAND OWNER REPRESENTATIVE, LOCAL TELEPHONE COMPANY, TOWER ERECTION FOREMAN (IF SUBCONTRACTED)
- A CONTRACTOR SHALL BE EQUIPPED WITH SOME MEANS OF CONSTANT COMMUNICATIONS, SUCH AS A MOBILE PHONE OR A BEEPER. THIS EQUIPMENT WILL NOT BE SUPPLIED BY THE OWNER, NOR WILL WIRELESS SERVICE BE ARRANGED.
- 5. DURING CONSTRUCTION, CONTRACTOR MUST ENSURE THAT EMPLOYEES AND SUBCONTRACTORS WEAR HARD HATS AT ALL TIMES. CONTRACTOR WILL COMPLY WITH ALL WPCS SAFETY REQUIREMENTS IN THEIR AGREEMENT
- 6. PROVIDE WRITTEN DAILY UPDATES ON SITE PROGRESS TO THE OWNER.
- 7 COMPLETE INVENTORY OF CONSTRUCTION MATERIALS AND EQUIPMENT IS REQUIRED PRIOR TO START OF CONSTRUCTION.

 8. NOTIFY THE OWNER/PROJECT MANAGER IN WRITING NO LESS. THAN 48 HOURS IN ADVANCE OF CONCRETE POURS, TOWER ERECTIONS, AND EQUIPMENT CABINET PLACEMENTS.

INSURANCE AND BONDS

- CONTRACTOR, AT THEIR OWN EXPENSE, SHALL CARRY AND MAINTAIN, FOR THE DURATION OF THE PROJECT, ALL INSURANCE, AS REQUIRED AND LISTED, AND SHALL NOT COMMENCE WITH THEIR WORK UNTIL THEY HAVE PRESENTED AN ORIGINAL CERTIFICATE OF INSURANCE STATING ALL COVERAGES TO THE OWNER. REFER TO THE MASTER AGREEMENT FOR REQUIRED INSURANCE LIMITS.
- 2. THE OWNER SHALL BE NAMED AS AN ADDITIONAL INSURED ON ALL POLICIES.

 3. CONTRACTOR MUST PROVIDE PROOF OF INSURANCE.
- ARCHITECTURAL SYMBOLS STORAGE 38 DETAIL REFERENCE KEY REFER TO - DRAWING DETAIL NUMBER-EXISTING N.I.C. RE: 2/A-3 A-3

LSHEET NUMBER OF DETAIL-

T - Mobile-

T-MOBILE NORTHEAST, LLC



10 INDUSTRIAL AVE MAHWAH NJ 07430 TRANSCEND@TRANSCENDWRELESS.COM TELEPHONE: (201) 684-0066

FORESITE LLC.

SITE DESIGN SERVICES 462 WALNUT STREET NEWTON, MA 02460 TEL: 617-527-3031

L. 017	-327-3031	
	SUBMITTALS	
DATE	DESCRIPTION	REVISION
/4/16	ISSUED FOR REVIEW	A

ı				
ı	DEPT.	DATE	APP'D	REVISIONS
ı	RFE			
ı	RF MAN.			
ı	ZONING			
ı	OPS			
ı	CONSTR.			
ı	SITE AC.			

PROJECT NO:	CTNH302/
DRAWN BY:	MS
CHECKED BY:	SM

PROFESSIONAL SEAL

THIS DOCUMENT IS THE CREATION, DESIGN, PROPERTY AND COPYRIGHTED WORK OF T-MOBILE. ANY DUPLICATION OR USE WITHOUT EXPRESS WRITTEN CONSENT IS STRICTLY PROHIBITED.

SITE NUMBER CTNH302A

SITE NAME


CTNH302/CLRCHANNEL/PROSP


SITE ADDRESS 151 WATERBURY RD PROSPECT, CT 06712


SHEET TITLE

CONTRACTOR'S NOTES

SHEET NUMBER







T - Mobile -

T-MOBILE NORTHEAST, LLC
35 GRIFFIN ROAD SOUTH

BLOOMFIELD, CT 06002 OFFICE: (860) 692-7100 FAX:(860) 692-7159



10 INDUSTRIAL AVE MAHWAH NJ 07430 TRANSCEND@TRANSCENDWIRELESS.COM TELEPHONE:(201) 684-0066

FORESITE LLC.

SITE DESIGN SERVICES 462 WALNUT STREET NEWTON, MA 02460 TEL: 617-527-3031

IEL. UI /	-327-3031		
	SUBMITTALS		
DATE	DESCRIPTION	REVISION	
05/4/16	ISSUED FOR REVIEW	A	
		1	

DEPT.	DATE	APP'D	REVISIONS
RFE			
RF MAN.			
ZONING			
OPS			
CONSTR.			
SITE AC.			

CTNH302A
MS
SM

PROFESSIONAL SEAL

THIS DOCUMENT IS THE CREATION, DESIGN, PROPERTY AND COPYRIGHTED WORK OF T-MOBILE. ANY DUPLICATION OR USE WITHOUT EXPRESS WRITTEN CONSENT IS STRICTLY PROHIBITED.

SITE NUMBER CTNH302A

SITE NAME

CTNH302/CLRCHANNEL/PROSP

SITE ADDRESS 151 WATERBURY RD PROSPECT, CT 06712

SHEET TITLE
GROUNDING AND ONE
LINE DIAGRAM
COAX/FIBER DIAGRAM

SHEET NUMBER

E-

Trenscend Wire

Shappy, Gregg <gshappy@transcendwireless.com>

151 Waterbury Road

3 messages

Rosalyn Moffo <landuse03@sbcglobal.net> Reply-To: Rosalyn Moffo <landuse03@sbcglobal.net>

Tue. Jun 21, 2016 at 3:24 PM

To: "gshappy@transcendwireless.com" <gshappy@transcendwireless.com>

To Whom It May Concern:

All Land Use records for the existing tower at 151 Waterbury Road have been reviewed and the original Zoning decision has not been found.

Please contact the Land Use office if you have any questions @ (203) 758-4461.

Thank you.

Rosalyn Moffo Land Use Clerk

Shappy, Gregg <gshappy@transcendwireless.com> To: Rosalyn Moffo <landuse03@sbcglobal.net>

Tue, Jun 21, 2016 at 3:36 PM

Thank you Rosalyn

Gregg Shappy

Transcend Wireless 10 Industrial Avenue, Suite 3 Mahwah, NJ 07430 gshappy@transcendwireless.com (845)553-2045

[Quoted text hidden]

Rosalyn Moffo <landuse03@sbcglobal.net> Reply-To: Rosalyn Moffo <landuse03@sbcglobal.net> To: "Shappy, Gregg" <gshappy@transcendwireless.com>

No Problem!

[Quoted text hidden]

Wed, Jun 22, 2016 at 10:10 AM