

280 Trumbull Street
Hartford, CT 06103-3597
Main (860) 275-8200
Fax (860) 275-8299
kbaldwin@rc.com
Direct (860) 275-8345

Also admitted in Massachusetts

June 7, 2019

Melanie A. Bachman, Esq.
Executive Director/Staff Attorney
Connecticut Siting Council
10 Franklin Square
New Britain, CT 06051

**Re: EM-VER-119-170327 – Cellco Partnership d/b/a Verizon Wireless (“Cellco”)
901 France Street (a/k/a North Street), Rocky Hill, Connecticut**

Dear Ms. Bachman:

On August 17, 2017, the Siting Council acknowledged receipt of Cellco’s notice of intent to modify its existing telecommunications facility at 901 France Street in Rocky Hill, Connecticut. Cellco’s modifications involved the replacement of antennas and installation of remote radio heads on the existing tower.

As a condition of its approval, Cellco was required to provide the Council with a letter stating that it had complied with the recommendations made in the February 27, 2017 Structural Modification Report, which was attached to the EM-VER-119-170327 filing. In preparation for construction of the approved modifications it was also discovered that Cellco’s antenna mounts would need to be modified.

To avoid any confusion, Cellco had a new structural analysis completed on May 17, 2019, which took into account the modifications approved in EM-VER-119-170327, as well as the modifications to the antenna mounts. A copy of the updated May 17, 2019 structural report is attached. Also attached is the Modification Inspection Report, dated August 21, 2017, verifying that the tower reinforcement, described in the February 27, 2017 Structural Modification Report, was completed.

19424216-v1

Melanie A. Bachman, Esq.
June 7, 2019
Page 2

Finally, attached is a Notice of Completion Certification from Dewberry Engineers Inc. verifying that all of Celco's facility modifications were completed in accordance with the May 17, 2019 Structural Analysis Report.

If you have any questions please do not hesitate to contact me.

Sincerely,



Kenneth C. Baldwin

Attachment
Copy to:
Tim Parks

Structural Modification Analysis Report and Design Calculations For a Wireless Telecommunications Upgrade

Site Name: Rocky Hill CT
Site Address: France Street, Lot 1
Rocky Hill, CT 06067

Prepared for:

Verizon Wireless
99 East River Drive
East Hartford, CT 06108

May 17, 2019
Rev. 1

Prepared by:


Dewberry Engineers Inc.
600 Parsippany Road, Suite 301
Parsippany, NJ 07054
Dewberry Project Number: 50103542

Prepared by:



Deep A. Patel
Graduate Engineer

Reviewed by:



Sahnoune Abed
Project Engineer

Approved by:



Benjamin B. Revette
Connecticut Professional Engineer
License No.: 28971

TABLE OF CONTENTS

<u>Section</u>	<u>Page Number</u>
1.0 INTRODUCTION AND PROJECT SUMMARY	1
2.0 PROPOSED ANTENNAS & EQUIPMENT	1
3.0 CODES, STANDARDS, AND REFERENCES	2
4.0 LOADING AND PERFORMANCE CRITERIA	2
5.0 CALCULATIONS	3
6.0 CONCLUSIONS, COMMENTARY, AND RECOMMENDATIONS	3
APPENDIX A STRUCTURAL ANALYSIS	
APPENDIX B REFERENCE MATERIAL	
APPENDIX C REFERENCE PHOTOS	

1.0 INTRODUCTION AND PROJECT SUMMARY

The objective of this report is to assess the proposed installation of new antennas on the existing monopole. This report is limited to the analysis of the antenna platform only.

The existing structure is a 140 ft tall tower located in Rocky Hill, CT with antennas attached to the existing platform. There are currently existing antennas and support equipment mounted to the platform in sectors Alpha, Beta, & Gamma. The proposed equipment will be attached at an approximate antenna centerline elevation of 138 ft.

2.0 EXISTING & PROPOSED ANTENNAS & EQUIPMENT

Currently, the tower has the following equipment:

- Two (2) Amphenol BXA-70063-6CF-4 panel antennas*
- One (1) Andrew LNX-6514DS-T6M panel antenna*
- Three (3) Amphenol BXA-171063-12BF-2 panel antennas*
- Four (4) Amphenol LPA-80063-4CF-4 panel antennas measuring 47.44"H x 15.2"W x 13.19"D (20 lb).
- Two (2) Swedcom SC-E 6014 panel antennas measuring 43"H x 8.5"W x 8"D (15 lb).

(*) To be removed

The following antennas and equipment are proposed in each sector:

- Sectors Alpha, Beta & Gamma
 - Two (2) SBNHH-1D65B antenna measuring 72.4"H x 11.9" W x 7.1" D (40.6 lb).
 - One (1) 2x60 700 RRH unit measuring 20.9"H x 11.8"W x 7.5"D (55.6 lb).
 - One (1) OVP measuring 28.93"H x 15.73"W x 10.3"D (32 lb). (*Total one*)
 - Miscellaneous equipment and cables negligible in weight and profile.

For the final configuration, refer to the table below:

Table 1: APPURTENANCE LOADING on TOWER			
Elev.	Status	Carrier	Appurtenance Description
138'	Final	Verizon	(6) SBNHH-1D65B
138'	Final	Verizon	(4) Amphenol LPA-80063-4CF-4
138'	Final	Verizon	(2) Swedcom SC-E 6014
138'	Final	Verizon	(3) 2x60 700 RRH
138'	Final	Verizon	(1) OVP
Verizon			

3.0 CODES, STANDARDS, AND REFERENCES

The structure was analyzed and the proposed installation designed per the provisions of the following Codes and standards:

- *International Building Code (IBC) 2015, International Code Council*
- *2018 Connecticut State Building Code – Amendments to IBC 2015*
- *TIA-222-G-4, Structural Standard for Antenna Supporting Structures and Antennas*
- *Steel Construction Manual 14th Ed, American Institute of Steel Construction.*
- *ASCE 7-10 Minimum Design Loads for Buildings and Other Structures, American Society of Civil Engineers.*
- *Construction Drawings by Dewberry Engineers Inc. (Dated: 09/05/17).*
- *Mount Mapping by Northeast Union Inc. (Dated 1/19/18).*
- *Structural Analysis Report by A-Prime Engineering (Dated 02/12/18).*
- *Structural Analysis Report by Dewberry Engineers (Dated 04/12/18).*

4.0 LOADING AND PERFORMANCE CRITERIA

The following Code-specified strength limit state (LRFD) load combinations were considered in the analysis of the antenna mounts (*TIA-222-G*):

1. $1.2D + 1.6W$
2. $1.2D + 1.0D_i + 1.0W_i$

The following Code-specified serviceability load combination was considered in the deflection of the antenna mounts (*TIA-222-G*):

1. $1.0D + 1.0W_{\text{service}}$

Where:

D = dead load of structure, steel, and new equipment.
D_i = dead load of ice
W = design wind load
W_i = design ice wind load
W_{service} = service wind load

The following site-specific design parameters were considered in this analysis per the provisions of *TIA-222-G*:

- Class: II
- Exposure: C
- Design Wind Speed: 96 mph
Converted from 124 mph ASCE 7-10 wind speed
- Design Ice Wind Speed: 50 mph *Annex B*
- Design Ice Thickness: 1.00 in *Annex B*
- Serviceability Wind Speed: 60 mph *Sect. 2.8.3*

5.0 CALCULATIONS

Calculations for this analysis and the design of the installation are included in the Appendices of this report.

6.0 CONCLUSIONS, COMMENTARY, AND RECOMMENDATIONS

Per the original Dewberry evaluation and analysis, it is concluded that the existing mount **does not have sufficient structural capacity** for the proposed installation in regards of stresses and deflections with the most unfavorable loading effects. Under the proposed conditions, the maximum utilization of a single structural member is **110.1%** and the maximum deflection ratio is **208.8%**.

Therefore, Dewberry recommends modifying the existing mount with a proposed support rail kit (P/N SitePro1 HRK14).

With the recommended modifications, the existing mount **does have sufficient structural capacity** for the proposed installation in regards of stresses and deflections with the most unfavorable loading effects. Under the proposed conditions, the maximum utilization of a single structural member is **75.3%** and the maximum deflection ratio is **28.6%**.

Please note this analysis is limited to the existing antenna mount only. If actual field conditions vary from what was assumed in this analysis, the results and conclusions expressed herein are invalid and further evaluation is recommended for any proposed installation to continue.

Dewberry Engineers Inc. reserves the right to add to or modify this report if more information becomes available. The conclusions reached by Dewberry Engineers Inc. in this report are only applicable to the previously mentioned existing structural elements supporting the proposed wireless telecommunications installation. The results of this report are based on the assumption that existing structural elements have been installed per the original design documents, have been well maintained, and are uncompromised. This report does not imply that a thorough inspection of the existing structure has been performed. Any deviation of the support condition, loading, location, placement, equipment configuration, etc., will require Dewberry Engineers Inc. to generate an additional structural analysis.

APPENDIX A



Job Number 50103542
 Made by: DAP
 Date: 5/13/19
 Checked by: BK
 Date: 5/16/19

(Rocky Hill CT) - Design Wind Load

Q:\50095218\50103542\Adm\Reports\MA - Passing\Calculations\50103542 - Rocky Hill CT Analysis Calc. (Co-Location Mount, TIA-222-G).xlsx

Wind Load Design Criteria

Site Name: Rocky Hill CT

General Information & Design Input from TIA-222-G

Item	Value	Description	Reference
V =	124.00	Design Wind Speed	ASCE 7-10, ATC Windspeed
V _{max} =	96.05	(√0.6) * V	Except. #5, Sect. 1609.3.1, Eqn. 16-33, IBC 15
Location =	CT	Hartford County	Annex B, TIA
V _i =	50.00	Design Ice Wind Speed (mph)	
K _d =	0.95	Wind Direction Probability Factor	Table 2-2, TIA
Class	II	Structure Classification	Table 2-1, TIA
I =	1.00	Importance Factor (Without Ice)	Table 2-3, TIA
I _{ice} =	1.00	Importance Factor (Ice Thickness)	Table 2-3, TIA
z = h =	138.00	ft. (A.G.L.)	Max. Center of Appurtenance
Exp. Cat.	C	Exposure Category	Sect. 2.6.5.1, TIA
Z _g =	900.00	Exposure Category Coeff.	Table 2-4, TIA
α' =	9.50	Exposure Category Coeff.	Table 2-4, TIA
K _{z (min)} =	0.85	Exposure Category Coeff.	Table 2-4, TIA
K _e =	1.00	Exposure Category Coeff.	Table 2-4, TIA
K _t =	N/A	Topographic Constant	Table 2-5, TIA ("N/A" if Topo. Cat. = 1)
K _z =	1.35	= 2.01(z/Z _g) ^(2/α')	Sect. 2.6.5.2, TIA
Topo. Cat.	1	Topographic Category (1-5)	Sect. 2.6.6.2, TIA
e =	2.72	Natural Logarithmic base	
f =	N/A	Height Attenuation Factor	Table 2-5, TIA ("N/A" if Topo. Cat. = 1)
H =	N/A	ft. Height of crest above surrounding terrain	
K _h =	N/A	e ^{((f*z)/H)}	Sect. 2.6.6.4, TIA
K _{zt} =	1.00	= [1 + ((K _e *K _t)/K _h)] ²	Sect. 2.6.6.4, TIA
K _{iz} =	1.15	= (z/33) ^{0.10} ≤ 1.4 (Height escalation factor)	Sect. 2.6.8, TIA
G _h =	1.00	Gust Effect Factor	Sect. 2.6.7, TIA
t _i =	1.00	Design Ice Thickness	Annex B, TIA
t _{iz} =	2.3	= 2 t _i (I)K _{iz} (K _{zt}) ^{0.35}	Sect. 2.6.8, TIA
q _{z design} =	30.4 psf	= 0.00256(K _z)(K _{zt})(K _s)(K _e)(K _d)(V ²)(I)	Sect. 2.6.9.6, TIA
q _{z ice} =	8.3 psf	= 0.00256(K _z)(K _{zt})(K _s)(K _e)(K _d)(V _i ²)	Sect. 2.6.9.6, TIA

Design Wind Forces:

Section 2.6.11.2

$$F_A = q_{z \text{ design}} G_h (EPA)_A$$

(where (EPA)_A = effective projected area of the appurtenance = C_s A_a)

$$F_{Ai} = q_{z \text{ ice}} G_h (EPA)_{Ai}$$

(see calculation tables on following pages)

Design Ice Weight:

Section 2.6.10

$$F_i = [\pi(t_{iz})(D_c + t_{iz})] * 56 \text{ lb/ft}^3$$

(where D_c = largest out to out dimension of member)

(see calculation tables on following pages)



Job Number 50103542
Made by: DAP
Date: 5/13/19
Checked by: BK
Date: 5/16/19

(Rocky Hill CT) - Design Wind Load

Q:\50095218\50103542\Adm\Reports\MA - Passing\Calculations\50103542 - Rocky Hill CT Analysis Calc. (Co-Location Mount, TIA-222-G).xlsx

Element Definition


Description	Dimensions (in.)			Weight (lb)	Length / # Supports
	W	D	H		
LPA-80063-4CF-F	15.20	13.19	47.44	20.00	2.00
SC-E 6014	8.50	8.00	43.00	15.00	2.00
SBNHH-1D65B	11.90	7.10	72.90	40.60	2.00
SBNHH-1D65B	11.90	7.10	72.90	40.60	2.00
2x60 700 RRH	11.80	7.50	20.90	55.60	2.00
OVP	15.73	10.30	28.93	32.00	2.00
STRUCTURAL MEMBERS					
2-3/8" OD Pipe	2.38	2.38	12.00	STAAD	Pipe
2-3/8" OD Pipe	2.38	2.38	12.00	STAAD	Pipe
L3x3x1/4	3.00	3.00	12.00	STAAD	Angle
2L3x3x3/16	6.00	3.00	12.00	STAAD	Dbl Angle
HSS4x4x1/4	4.00	4.00	12.00	STAAD	Tube

(Mounting Pipe)


(See Note 2)

Note:

1) For Double Angles assume the following:



2) For mounting pipes that do not support equipment or portions which are not shielded by equipment, create an additional entry below.



Q:\50095218\50103542\Adm\Reports\MA - Passing\Calculations\50103542 - Rocky Hill CT Analysis Calc. (Co-Location Mount, TIA-222-G).xlsx

[illegible][illegible]

[illegible]



Job Number 50103542
 Made by: DAP
 Date: 5/13/19
 Checked by: BK
 Date: 5/16/19

(Rocky Hill CT) - Serviceability Wind Load

Q:\50095218\50103542\Adm\Reports\MA - Passing\Calculations\50103542 - Rocky Hill CT Analysis Calc. (Co-Location Mount, TIA-222-G).xlsx

Serviceability Wind Load Design Criteria

General Information & Design Input from TIA-222-G

Item	Value	Description	Reference
$V_s =$	60.00	Service Wind Speed (mph)	Sect. 2.8.3, TIA
$V_m =$	30.00	Maintenance Wind Speed (mph)	
$K_d =$	0.85	Service Wind Direction Probability Factor	Sect. 2.8.3, TIA
Class	II	Structure Classification	Table 2-1, TIA
$z = h =$	138.00	ft. (A.G.L.)	Max. Center of Appurtenance
Exp. Cat.	C	Exposure Category	Sect. 2.6.5.1, TIA
$z_g =$	900.00	Exposure Category Coeff.	Table 2-4, TIA
$\alpha' =$	9.50	Exposure Category Coeff.	Table 2-4, TIA
$K_{z(min)} =$	0.85	Exposure Category Coeff.	Table 2-4, TIA
$K_e =$	1.00	Exposure Category Coeff.	Table 2-4, TIA
$K_t =$	N/A	Topographic Constant	Table 2-5, TIA ("N/A" if Topo. Cat. = 1)
$K_z =$	1.35	$= 2.01(z/z_g)^{(2/\alpha')}$	Sect. 2.6.5.2, TIA
Topo. Cat.	1	Topographic Category (1-5)	Sect. 2.6.6.2, TIA
$e =$	2.72	Natural Logarithmic base	
$f =$	N/A	Height Attenuation Factor	Table 2-5, TIA ("N/A" if Topo. Cat. = 1)
$H =$	N/A	ft. Height of crest above surrounding terrain	
$K_h =$	N/A	$e^{((f^2 z)/H)}$	Sect. 2.6.6.4, TIA
$K_{zt} =$	1.00	$= [1 + ((K_e * K_t)/K_h)]^2$	Sect. 2.6.6.4, TIA
$G_h =$	1.00	Gust Effect Factor	Sect. 2.6.7, TIA
$q_{z \text{ service}} =$	10.7 psf	$= 0.00256(K_z)(K_{zt})(K_d)(V_s^2)$	Sect. 2.6.9.6, TIA
$q_{z \text{ maint}} =$	3.0 psf	$= 0.00256(K_z)(K_{zt})(K_d)(V_m^2)$	

Design Serviceability and Maintenance Wind Forces:

Section 2.6.11.2

$$F_{As} = q_{z \text{ service}} G_h (EPA)_A$$

$$F_{Am} = q_{z \text{ maint}} G_h (EPA)_A$$

(see calculation tables on following pages)

(where $(EPA)_A$ = effective projected area of the appurtenance = $C_a A_a$)

[illegible]



Job Number 50103542
 Made by: DAP
 Date: 5/13/19
 Checked by: BK
 Date: 5/16/19

(Rocky Hill CT) - Serviceability Wind Load

Q:\50095218\50103542\Adm\Reports\MA - Passing\Calculations\50103542 - Rocky Hill CT Analysis Calc. (Co-Location Mount, TIA-222-G).xlsx

Service Effective Projected Area & Wind Loads

Members	EPA _{as} @ 0.0° (sf)	EPA _{as} @ 30.0° (sf)	EPA _{as} @ 60.0° (sf)	EPA _{as} @ 90.0° (sf)	F _{as} @ 0.0° (lb)	F _{as} @ 30.0° (lb)	F _{as} @ 60.0° (lb)	F _{as} @ 90.0° (lb)
LPA-80063-4CF-F	6.17	5.99	5.62	5.44	33.0	32.0	30.1	29.1
SC-E 6014	3.33	3.29	3.23	3.19	17.8	17.6	17.3	17.1
SBNHH-1D65B	8.19	7.50	6.11	5.42	43.8	40.1	32.7	29.0
SBNHH-1D65B	8.19	7.50	6.11	5.42	43.8	40.1	32.7	29.0
2x60 700 RRH	2.05	1.87	1.51	1.33	11.0	10.0	8.1	7.1
OVP	3.79	3.47	2.83	2.50	20.3	18.6	15.1	13.4
STRUCTURAL MEMBERS								
2-3/8" OD Pipe	0.15	-	-	-	1.6	-	-	-
2-3/8" OD Pipe	0.15	-	-	-	1.6	-	-	-
L3x3x1/4	0.32	-	-	-	3.4	-	-	-
2L3x3x3/16	0.60	-	-	-	6.4	-	-	-
HSS4x4x1/4	0.40	-	-	-	4.3	-	-	-

Maintenance Effective Projected Area & Wind Loads

Members	EPA _{am} @ 0.0° (sf)	EPA _{am} @ 30.0° (sf)	EPA _{am} @ 60.0° (sf)	EPA _{am} @ 90.0° (sf)	F _{am} @ 0.0° (lb)	F _{am} @ 30.0° (lb)	F _{am} @ 60.0° (lb)	F _{am} @ 90.0° (lb)
LPA-80063-4CF-F	6.17	5.99	5.62	5.44	9.3	9.0	8.4	8.2
SC-E 6014	3.33	3.29	3.23	3.19	5.0	4.9	4.8	4.8
SBNHH-1D65B	8.19	7.50	6.11	5.42	12.3	11.2	9.2	8.1
SBNHH-1D65B	8.19	7.50	6.11	5.42	12.3	11.2	9.2	8.1
2x60 700 RRH	2.05	1.87	1.51	1.33	3.1	2.8	2.3	2.0
OVP	3.79	3.47	2.83	2.50	5.7	5.2	4.2	3.8
STRUCTURAL MEMBERS								
2-3/8" OD Pipe	0.15	-	-	-	0.5	-	-	-
2-3/8" OD Pipe	0.15	-	-	-	0.5	-	-	-
L3x3x1/4	0.32	-	-	-	1.0	-	-	-
2L3x3x3/16	0.60	-	-	-	1.8	-	-	-
HSS4x4x1/4	0.40	-	-	-	1.2	-	-	-



Job Number 50103542
Made by: DAP
Date: 5/13/19
Checked by: BK
Date: 5/16/19

(Rocky Hill CT) - Load Input for STAAD Model

Q:\50095218\50103542\Adm\Reports\MA - Passing\Calculations\50103542 - Rocky Hill CT Analysis Calc. (Co-Location Mount, TIA-222-G).xlsx

STAAD Gravity Load Input

Equipment	Dead Load (lb per support)	Ice Load (lb per support)
LPA-80063-4CF-F	10.0	124.6
SC-E 6014	7.5	70.3
SBNHH-1D65B	20.3	137.9
SBNHH-1D65B	20.3	137.9
2x60 700 RRH	27.8	39.8
OVP	16.0	71.5
Platform Grating	8.0	10.7 psf

Maintenance Loads

$L_M =$ 500 lbs - vertical concentrated downward force applied in each mounting pipe location independently
 $L_V =$ 250 lbs - vertical concentrated downward force applied at the center of each simply supported horizontal member and at the end of each horizontal cantilevered members independently (excluding tie-backs)

STAAD Wind Load Calculation

Equipment	Axis	Case #1 0°	Case #2 30°	Case #3 60°	Case #4 90°	Case #5 120°	Case #6 150°	Case #7 180°	Case #8 210°	Case #9 240°	Case #10 270°	Case #11 300°	Case #12 330°
Not Shielded (1 - 4)	Z	-F ₀			-								
	X	-			F ₉₀								
Shielded (1 - 4)	Z	N/A			-								
	X	-	Same as Case #4	Same as Case #1	F ₉₀	Same as Case #1	Same as Case #2	Same as Case #3	Same as Case #4	Same as Case #1	Same as Case #2	Same as Case #3	Same as Case #4
Not Shielded (5 - 12)	Z	-F ₆₀			-								
	X	-			F ₃₀								
Shielded (5 - 12)	Z	-F ₆₀			-								
	X	-			N/A								



Job Number	50103542
Made by:	DAP
Date:	5/13/19
Checked by:	BK
Date:	5/16/19

(Rocky Hill CT) - Load Input for STAAD Model

Q:\50095218\50103542\Adm\Reports\MA - Passing\Calculations\50103542 - Rocky Hill CT Analysis Calc. (Co-Location Mount, TIA-222-G).xlsx

STAAD Load Input (Design Wind Load)

Positions 1 - 4

[illegible]

Positions 5 - 12

[illegible]



Job Number	50103542
Made by:	DAP
Date:	5/13/19
Checked by:	BK
Date:	5/16/19

(Rocky Hill CT) - Load Input for STAAD Model

Q:\50095218\50103542\Adm\Reports\MA - Passing\Calculations\50103542 - Rocky Hill CT Analysis Calc. (Co-Location Mount, TIA-222-G).xlsx

STAAD Load Input (Design Wind on Ice Load)

Positions 1 - 4

Equipment	Axis	Case #1 0°	Case #2 30°	Case #3 60°	Case #4 90°
LPA-80063-4CF-F (Not Shielded)	Z	-36.0			-
	X	-			32.5
SBNHH-1D65B (Not Shielded)	Z	-48.1			-
	X	-			36.3
SBNHH-1D65B (Not Shielded)	Z	-48.1			-
	X	-			36.3
2x60 700 RRH (Shielded)	Z	N/A			-
	X	-	Same as Case #4	Same as Case #1	10.7
OVP (Not Shielded)	Z	-23.5			-
	X	-			17.2

Positions 5 - 12

[illegible]



Job Number	50103542
Made by:	DAP
Date:	5/13/19
Checked by:	BK
Date:	5/16/19

(Rocky Hill CT) - Load Input for STAAD Model

Q:\50095218\50103542\Adm\Reports\MA - Passing\Calculations\50103542 - Rocky Hill CT Analysis Calc. (Co-Location Mount, TIA-222-G).xlsx

STAAD Load Input (Service Wind Load)

Positions 1 - 4

[illegible]

Positions 5 - 12

[illegible]



Job Number	50103542
Made by:	DAP
Date:	5/13/19
Checked by:	BK
Date:	5/16/19

(Rocky Hill CT) - Load Input for STAAD Model

Q:\50095218\50103542\Adm\Reports\IMA - Passing\Calculations\50103542 - Rocky Hill CT Analysis Calc. (Co-Location Mount, TIA-222-G).xlsx

STAAD Load Input (Maintenance Wind Load)

Positions 1 - 4					
Equipment	Axis	Case #1 0°	Case #2 30°	Case #3 60°	Case #4 90°
LPA-80063-4CF-F (Not Shielded)	Z	-9.3			-
	X	-			8.2
SBNHH-1D65B (Not Shielded)	Z	-12.3			-
	X	-			8.1
SBNHH-1D65B (Not Shielded)	Z	-12.3			-
	X	-			8.1
2x60 700 RRH (Shielded)	Z	N/A			-
	X	-	Same as Case #4	Same as Case #1	2.0
OVP (Not Shielded)	Z	-5.7			-
	X	-			3.8

Positions 5 - 12

[illegible]



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No

50103542

Sheet No

1

Rev

1

Part

Job Title Rocky Hill CT

Ref

By DAP

Date 5/13/19

Chd BK

Client VZW

File Rocky Hill CT.std

Date/Time 13-May-2019 16:22

Job Information

	Engineer	Checked	Approved
Name:	DAP	BK	
Date:	5/13/19	5/16/19	

Project ID	
Project Name	

Structure Type	SPACE FRAME
----------------	-------------

Number of Nodes	97	Highest Node	136
Number of Elements	112	Highest Beam	201
Number of Plates	18	Highest Plate	174

Number of Basic Load Cases	12
Number of Combination Load Cases	18

Included in this printout are data for:

All	The Whole Structure
-----	---------------------

Included in this printout are results for load cases:

Type	L/C	Name
Primary	1	DEAD
Primary	2	WL#1
Primary	3	WL#4
Primary	4	DI
Primary	5	WLI#1
Primary	6	WLI#4
Primary	7	WLS#1
Primary	8	WLS#4
Primary	9	WLM#1
Primary	10	WLM#4
Primary	11	LM
Primary	12	LV
Combination	13	1.2D+1.6WL#1
Combination	14	1.2D+1.6WL#4
Combination	15	1.2D-1.6WL#1
Combination	16	1.2D-1.6WL#4
Combination	17	1.2D+1.0DI+1.0WI#1
Combination	18	1.2D+1.0DI+1.0WI#4
Combination	19	1.2D+1.0DI-1.0WI#1
Combination	20	1.2D+1.0DI-1.0WI#4
Combination	21	1.0D+1.0WLS#1
Combination	22	1.0D+1.0WLS#4
Combination	23	1.0D-1.0WLS#1
Combination	24	1.0D-1.0WLS#4



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
2

Rev
1

Job Title **Rocky Hill CT**

Part

Ref

By **DAP**

Date **5/13/19**

Chd **BK**


Client **VZW**

File **Rocky Hill CT.std**

Date/Time **13-May-2019 16:22**

Job Information Cont...

Type	L/C	Name
Combination	28	1.2D+1.5LM-1.0WM#1
Combination	29	1.2D+1.5LM-1.0WM#4
Combination	30	1.2D+1.5LV



3D Rendered View

Nodes

Node	X (ft)	Y (ft)	Z (ft)
1	-0.000	0.000	-4.083
2	-0.000	0.000	-8.083
3	3.536	0.000	2.041
4	7.000	0.000	4.041
5	-7.000	0.000	4.041
6	-3.536	0.000	2.041
7	3.500	0.000	-2.021
8	0.866	0.000	-0.500
9	-0.000	0.000	1.000
10	-0.000	0.000	4.041
11	-0.866	0.000	-0.500
12	-3.500	0.000	-2.021
13	6.333	0.000	2.887
14	1.768	0.000	-1.021
15	-0.000	0.000	2.041
16	-1.768	0.000	-1.021
17	6.333	4.167	2.887
18	6.333	-0.833	2.887
22	0.667	0.000	-6.928
23	0.667	-0.833	-6.928



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No

50103542

Sheet No

3

Rev

1

Part

Ref

By DAP

Date 5/13/19

Chd BK

Client VZW

File Rocky Hill CT.std

Date/Time 13-May-2019 16:22

Nodes Cont...

Node	X (ft)	Y (ft)	Z (ft)
24	0.667	4.167	-6.928
25	3.500	-0.833	-2.021
26	3.500	4.167	-2.021
27	-0.667	0.000	-6.928
28	-0.667	4.167	-6.928
29	-0.667	-0.833	-6.928
33	-6.333	0.000	2.887
34	-6.333	-0.833	2.887
35	-6.333	4.167	2.887
36	-3.500	-0.833	-2.021
37	-3.500	4.167	-2.021
38	-5.667	0.000	4.041
39	-5.667	4.167	4.041
40	-5.667	-0.833	4.041
44	5.667	0.000	4.041
45	5.667	-0.833	4.041
46	5.667	4.167	4.041
47	-0.000	-0.833	4.041
48	-0.000	4.167	4.041
73	6.333	3.667	2.887
74	0.667	3.667	-6.928
75	3.500	3.667	-2.021
76	-0.667	3.667	-6.928
77	-6.333	3.667	2.887
78	-3.500	3.667	-2.021
79	-5.667	3.667	4.041
80	5.667	3.667	4.041
81	-0.000	3.667	4.041
82	3.500	-0.333	-2.021
83	-3.500	-0.333	-2.021
84	-0.000	-0.333	4.041
85	6.333	-0.333	2.887
86	0.667	-0.333	-6.928
87	-0.667	-0.333	-6.928
88	-6.333	-0.333	2.887
89	-5.667	-0.333	4.041
90	5.667	-0.333	4.041
91	3.500	1.500	-2.021
92	-3.500	1.500	-2.021
93	-0.000	1.500	4.041
94	-1.317	0.000	-0.760
95	-2.357	0.000	2.041
96	-1.179	0.000	2.041
97	-3.778	0.000	4.041
98	-1.889	0.000	4.041



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No

50103542

Sheet No

4

Rev

1

Part

Job Title **Rocky Hill CT**

Ref

By **DAP**

Date **5/13/19**

Chd **BK**

Client **VZW**

File **Rocky Hill CT.std**

Date/Time **13-May-2019 16:22**

Nodes Cont...

Node	X (ft)	Y (ft)	Z (ft)
99	1.889	0.000	4.041
100	3.778	0.000	4.041
101	1.179	0.000	2.041
102	2.357	0.000	2.041
103	-4.444	0.000	-0.385
104	-5.389	0.000	1.251
105	-2.357	0.000	-0.000
106	-2.947	0.000	1.021
107	-1.611	0.000	-5.292
108	-2.556	0.000	-3.657
109	-0.589	0.000	-3.062
110	-1.179	0.000	-2.041
111	1.179	0.000	-2.041
112	0.589	0.000	-3.062
113	2.556	0.000	-3.657
114	1.611	0.000	-5.292
115	2.947	0.000	1.021
116	2.357	0.000	-0.000
117	5.389	0.000	1.251
118	4.444	0.000	-0.385
119	7.000	3.000	4.041
120	6.333	3.000	2.887
121	3.500	3.000	-2.021
123	-0.000	3.000	-8.083
124	-0.667	3.000	-6.928
125	-3.500	3.000	-2.021
127	-7.000	3.000	4.041
128	-5.667	3.000	4.041
129	-0.000	3.000	4.041
132	0.667	3.000	-6.928
134	-6.333	3.000	2.887
136	5.667	3.000	4.041



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
5

Rev
1

Job Title **Rocky Hill CT**

Part

Ref

By **DAP**


Date **5/13/19**

Chd **BK**

Client **VZW**

File **Rocky Hill CT.std**

Date/Time **13-May-2019 16:22**



Node Layout

Beams

Beam	Node A	Node B	Length (ft)	Property	β (degrees)
1	1	2	4.000	4	180
2	3	4	4.000	4	180
3	5	6	4.000	4	180
4	7	14	2.000	2	0
5	9	15	1.041	2	0
6	11	94	0.521	2	0
7	18	85	0.500	5	0
9	23	86	0.500	5	0
10	25	82	0.500	5	0
11	29	87	0.500	5	0
13	34	88	0.500	5	0
14	36	83	0.500	5	0
15	40	89	0.500	5	0
17	45	90	0.500	5	0
18	47	84	0.500	5	0
19	4	13	1.333	3	135
20	7	113	1.889	3	135
21	2	27	1.333	3	135
22	12	103	1.889	3	135
23	5	38	1.333	3	135
24	10	99	1.889	3	135



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No

50103542

Sheet No

6

Rev

1

Part

Job Title Rocky Hill CT

Ref

By DAP

Date 5/13/19

Chd BK

Client VZW

File Rocky Hill CT.std

Date/Time 13-May-2019 16:22

Beams Cont...

Beam	Node A	Node B	Length (ft)	Property	β (degrees)
25	3	115	1.179	3	225
26	14	111	1.179	3	225
27	1	109	1.179	3	225
28	16	105	1.179	3	225
29	6	95	1.179	3	225
30	15	101	1.179	3	225
43	14	8	1.041	2	0
44	15	10	2.000	2	0
45	16	12	2.000	2	0
48	7	91	1.500	5	0
51	12	92	1.500	5	0
54	10	93	1.500	5	0
55	13	117	1.889	3	135
56	22	2	1.333	3	135
57	27	107	1.889	3	135
58	33	5	1.333	3	135
59	38	97	1.889	3	135
60	44	4	1.333	3	135
101	73	17	0.500	5	0
102	74	24	0.500	5	0
103	75	26	0.500	5	0
104	76	28	0.500	5	0
105	77	35	0.500	5	0
106	78	37	0.500	5	0
107	79	39	0.500	5	0
108	80	46	0.500	5	0
109	81	48	0.500	5	0
110	82	7	0.333	5	0
111	83	12	0.333	5	0
112	84	10	0.333	5	0
113	85	13	0.333	5	0
114	86	22	0.333	5	0
115	87	27	0.333	5	0
116	88	33	0.333	5	0
117	89	38	0.333	5	0
118	90	44	0.333	5	0
122	94	16	0.521	2	0
123	76	124	0.667	5	0
124	74	132	0.667	5	0
125	75	121	0.667	5	0
127	73	120	0.667	5	0
128	81	129	0.667	5	0
129	79	128	0.667	5	0
130	77	134	0.667	5	0
131	78	125	0.667	5	0



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
7

Rev
1

Part

Job Title **Rocky Hill CT**

Ref

By **DAP**

Date **5/13/19**

Chd **BK**

Client **VZW**

File **Rocky Hill CT.std**

Date/Time **13-May-2019 16:22**

Beams Cont...

Beam	Node A	Node B	Length (ft)	Property	β (degrees)
132	80	136	0.667	5	0
133	95	96	1.179	3	225
134	96	15	1.179	3	225
135	97	98	1.889	3	135
136	98	10	1.889	3	135
137	99	100	1.889	3	135
138	100	44	1.889	3	135
139	101	102	1.179	3	225
140	102	3	1.179	3	225
141	103	104	1.889	3	135
142	104	33	1.889	3	135
143	105	106	1.179	3	225
144	106	6	1.179	3	225
145	107	108	1.889	3	135
146	108	12	1.889	3	135
147	109	110	1.179	3	225
148	110	16	1.179	3	225
149	111	112	1.179	3	225
150	112	1	1.179	3	225
151	113	114	1.889	3	135
152	114	22	1.889	3	135
153	115	116	1.179	3	225
154	116	14	1.179	3	225
155	117	118	1.889	3	135
156	118	7	1.889	3	135
175	120	13	3.000	5	0
176	119	120	1.333	5	135
177	121	91	1.500	5	0
179	124	27	3.000	5	0
180	123	124	1.333	5	135
181	125	92	1.500	5	0
183	128	38	3.000	5	0
184	127	128	1.333	5	135
185	129	93	1.500	5	0
188	132	22	3.000	5	0
189	132	123	1.333	5	135
191	134	33	3.000	5	0
192	134	127	1.333	5	135
194	136	44	3.000	5	0
195	136	119	1.333	5	135
196	134	125	5.667	5	0
197	125	124	5.667	5	0
198	132	121	5.667	5	0
199	121	120	5.667	5	0
200	136	129	5.667	5	0



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
8

Rev
1

Job Title **Rocky Hill CT**

Part

Ref

By **DAP**

Date **5/13/19**

Chd **BK**


Client **VZW**

File **Rocky Hill CT.std**

Date/Time **13-May-2019 16:22**

Beams Cont...

Beam	Node A	Node B	Length (ft)	Property	β (degrees)
201	129	128	5.667	5	0



Beam Layout

Plates

Plate	Node A	Node B	Node C	Node D	Property
157	5	38	95	6	1
158	38	98	96	95	1
159	98	10	15	96	1
160	10	99	101	15	1
161	99	44	102	101	1
162	102	44	4	3	1
163	115	3	4	13	1
164	116	115	13	118	1
165	14	116	118	7	1
166	111	14	7	113	1
167	112	111	113	22	1
168	2	1	112	22	1
169	2	27	109	1	1
170	27	108	110	109	1



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
9

Rev
1

Job Title Rocky Hill CT

Part

Ref

By DAP Date 5/13/19 Chd BK

Client VZW

File Rocky Hill CT.std

Date/Time 13-May-2019 16:22

Plates Cont...

Plate	Node A	Node B	Node C	Node D	Property
171	108	12	16	110	1
172	12	103	105	16	1
173	103	33	106	105	1
174	33	5	6	106	1

Section Properties

Prop	Section	Area (in ²)	I _{yy} (in ⁴)	I _{zz} (in ⁴)	J (in ⁴)	Material
2	HSST4X4X0.25	3.370	7.800	7.800	12.455	STEEL
3	L30304	1.440	1.982	0.506	0.031	STEEL
4	L30303 LD	2.180	3.393	1.928	0.026	STEEL
5	PIPS20	1.020	0.627	0.627	1.262	STEEL

Plate Thickness

Prop	Node A (in)	Node B (in)	Node C (in)	Node D (in)	Material
1	0.062	0.062	0.062	0.062	STEEL

Materials

Mat	Name	E (kip/in ²)	ν	Density (kip/in ³)	α (/°F)
1	STEEL	29E+3	0.300	0.000	6E-6
2	STAINLESSSTEEL	28E+3	0.300	0.000	10E-6
3	ALUMINUM	10E+3	0.330	0.000	13E-6
4	CONCRETE	3.15E+3	0.170	0.000	5E-6

Supports

Node	X (kip/in)	Y (kip/in)	Z (kip/in)	rX (kip*ft/deg)	rY (kip*ft/deg)	rZ (kip*ft/deg)
8	Fixed	Fixed	Fixed	Fixed	Fixed	Fixed
9	Fixed	Fixed	Fixed	Fixed	Fixed	Fixed
11	Fixed	Fixed	Fixed	Fixed	Fixed	Fixed

Releases

There is no data of this type.



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No

50103542

Sheet No

10

Rev

1

Part

Job Title Rocky Hill CT

Ref

By DAP

Date 5/13/19

Chd BK

Client VZW

File Rocky Hill CT.std

Date/Time 13-May-2019 16:22

Primary Load Cases

Number	Name	Type
1	DEAD	Dead
2	WL#1	Wind
3	WL#4	Wind
4	DI	Ice
5	WLI#1	Wind on Ice
6	WLI#4	Wind on Ice
7	WLS#1	Wind
8	WLS#4	Wind
9	WLM#1	Wind
10	WLM#4	Wind
11	LM	Live
12	LV	Live

Combination Load Cases

Comb.	Combination L/C Name	Primary	Primary L/C Name	Factor
13	1.2D+1.6WL#1	1	DEAD	1.20
		2	WL#1	1.60
14	1.2D+1.6WL#4	1	DEAD	1.20
		3	WL#4	1.60
15	1.2D-1.6WL#1	1	DEAD	1.20
		2	WL#1	-1.60
16	1.2D-1.6WL#4	1	DEAD	1.20
		3	WL#4	-1.60
17	1.2D+1.0DI+1.0WI#1	1	DEAD	1.20
		5	WLI#1	1.00
		4	DI	1.00
18	1.2D+1.0DI+1.0WI#4	1	DEAD	1.20
		6	WLI#4	1.00
		4	DI	1.00
19	1.2D+1.0DI-1.0WI#1	1	DEAD	1.20
		5	WLI#1	-1.00
		4	DI	1.00
20	1.2D+1.0DI-1.0WI#4	1	DEAD	1.20
		6	WLI#4	-1.00
		4	DI	1.00
21	1.0D+1.0WLS#1	1	DEAD	1.00
		7	WLS#1	1.00
22	1.0D+1.0WLS#4	1	DEAD	1.00
		8	WLS#4	1.00
23	1.0D-1.0WLS#1	1	DEAD	1.00
		7	WLS#1	-1.00
24	1.0D-1.0WLS#4	1	DEAD	1.00



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
11

Rev
1

Job Title **Rocky Hill CT**

Part

Ref

By **DAP**

Date **5/13/19**

Chd **BK**

Client **VZW**


File **Rocky Hill CT.std**

Date/Time **13-May-2019 16:22**

Combination Load Cases Cont...

Comb.	Combination L/C Name	Primary	Primary L/C Name	Factor
		8	WLS#4	-1.00
25	1.4D	1	DEAD	1.40
26	1.2D+1.5LM+1.0WM#1	1	DEAD	1.20
		11	LM	1.50
		9	WLM#1	1.00
27	1.2D+1.5LM+1.0WM#4	1	DEAD	1.20
		11	LM	1.50
		10	WLM#4	1.00
28	1.2D+1.5LM-1.0WM#1	1	DEAD	1.20
		11	LM	1.50
		9	WLM#1	-1.00
29	1.2D+1.5LM-1.0WM#4	1	DEAD	1.20
		11	LM	1.50
		10	WLM#4	-1.00
30	1.2D+1.5LV	1	DEAD	1.20
		12	LV	1.50

Y
X
Z



Load 1

Dead Load



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No

50103542

Sheet No

12

Rev

1

Part

Ref

By DAP


Date 5/13/19

Chd BK


Client VZW

File Rocky Hill CT.std

Date/Time 13-May-2019 16:22



Wind Load (Z-Direction)



Wind Load (X-Direction)



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
13

Rev
1

Job Title **Rocky Hill CT**

Part

Ref

By **DAP**


Date **5/13/19**

Chd **BK**


Client **VZW**

File **Rocky Hill CT.std**

Date/Time **13-May-2019 16:22**



Dead Ice Load



1.2D+1.6W (TYP.)



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
14

Rev
1

Job Title **Rocky Hill CT**

Part

Ref

By **DAP**


Date **5/13/19**

Chd **BK**

Client **VZW**

File **Rocky Hill CT.std**

Date/Time **13-May-2019 16:22**



1.2D+1.0DI+1.0WI (TYP)

Beam Combined Axial and Bending Stresses Summary

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
1	1:DEAD	4.000	991.802	4.000	3	-353.213	0.000	3
	2:WL#1	4.000	1.09E+3	0.000	1	-3.06E+3	0.000	3
	3:WL#4	4.000	316.702	0.000	1	-315.272	0.000	2
	4:DI	4.000	5.07E+3	4.000	3	-2.45E+3	0.000	3
	5:WLI#1	4.000	511.276	0.000	1	-1.44E+3	0.000	3
	6:WLI#4	4.000	150.449	0.000	1	-150.021	0.000	2
	7:WLS#1	4.000	381.681	0.000	1	-1.07E+3	0.000	3
	8:WLS#4	4.000	111.344	0.000	1	-110.841	0.000	2
	9:WLM#1	4.000	109.361	0.000	1	-307.732	0.000	3
	10:WLM#4	4.000	31.376	0.000	1	-31.232	0.000	2
	11:LM	4.000	22.756	0.000	3	-8.325	0.000	1
	12:LV	4.000	23.299	4.000	3	-10.939	0.000	3
	13:1.2D+1.6WI	4.000	1.93E+3	0.000	1	-5.32E+3	0.000	3
	14:1.2D+1.6WI	4.000	1.22E+3	4.000	3	-692.582	4.000	2
	15:1.2D-1.6WL	4.000	4.47E+3	0.000	3	-1.55E+3	0.000	1
	16:1.2D-1.6WL	4.000	1.19E+3	4.000	3	-656.131	4.000	1
	17:1.2D+1.0DI	4.000	6.33E+3	4.000	3	-4.31E+3	0.000	3
	18:1.2D+1.0DI	4.000	6.27E+3	4.000	3	-2.88E+3	0.000	3
	19:1.2D+1.0DI	4.000	6.19E+3	4.000	3	-2.19E+3	4.000	1



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No 50103542	Sheet No 15	Rev 1
Part		
Ref		
By DAP	Date 5/13/19	Chd BK
File Rocky Hill CT.std	Date/Time 13-May-2019 16:22	

Job Title Rocky Hill CT

Client VZW

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	20:1.2D+1.0DI-	4.000	6.25E+3	4.000	3	-2.88E+3	0.000	3
	21:1.0D+1.0WI	4.000	1.05E+3	4.000	3	-1.43E+3	0.000	3
	22:1.0D+1.0WI	4.000	998.758	4.000	3	-410.944	4.000	2
	23:1.0D-1.0WL	4.000	1.04E+3	2.667	3	-351.060	2.667	1
	24:1.0D-1.0WL	4.000	991.035	4.000	3	-390.550	4.000	1
	25:1.4D	4.000	1.39E+3	4.000	3	-494.499	0.000	3
	26:1.2D+1.5LV	4.000	1.21E+3	4.000	3	-697.445	0.000	3
	27:1.2D+1.5LV	4.000	1.2E+3	4.000	3	-439.796	4.000	2
	28:1.2D+1.5LV	4.000	1.18E+3	4.000	3	-412.358	4.000	2
	29:1.2D+1.5LV	4.000	1.19E+3	4.000	3	-418.188	4.000	1
	30:1.2D+1.5LV	4.000	1.23E+3	4.000	3	-440.215	0.000	3
2	1:DEAD	4.000	991.329	4.000	3	-352.794	0.000	3
	2:WL#1	4.000	1.55E+3	0.000	3	-797.473	0.000	1
	3:WL#4	4.000	1.08E+3	0.000	1	-2.6E+3	0.000	3
	4:DI	4.000	5.04E+3	4.000	3	-2.42E+3	0.000	3
	5:WLI#1	4.000	725.758	0.000	3	-379.536	0.000	1
	6:WLI#4	4.000	503.925	0.000	1	-1.21E+3	0.000	3
	7:WLS#1	4.000	542.902	0.000	3	-280.184	0.000	1
	8:WLS#4	4.000	378.779	0.000	1	-913.555	0.000	3
	9:WLM#1	4.000	155.479	0.000	3	-79.944	0.000	1
	10:WLM#4	4.000	107.923	0.000	1	-260.467	0.000	3
	11:LM	4.000	46.600	4.000	3	-21.873	0.000	3
	12:LV	4.000	11.378	0.000	3	-4.162	0.000	1
	13:1.2D+1.6WI	4.000	2.05E+3	0.000	3	-1.08E+3	0.000	1
	14:1.2D+1.6WI	4.000	1.92E+3	0.000	1	-4.59E+3	0.000	3
	15:1.2D-1.6WL	4.000	1.47E+3	0.000	1	-2.9E+3	0.000	3
	16:1.2D-1.6WL	4.000	3.74E+3	0.000	3	-1.53E+3	0.000	1
	17:1.2D+1.0DI-	4.000	6.21E+3	4.000	3	-2.22E+3	4.000	1
	18:1.2D+1.0DI-	4.000	6.31E+3	4.000	3	-4.05E+3	0.000	3
	19:1.2D+1.0DI-	4.000	6.27E+3	4.000	3	-3.57E+3	0.000	3
	20:1.2D+1.0DI-	4.000	6.16E+3	4.000	3	-2.2E+3	4.000	1
	21:1.0D+1.0WI	4.000	960.211	4.000	3	-381.467	4.000	1
	22:1.0D+1.0WI	4.000	1.05E+3	4.000	3	-1.27E+3	0.000	3
	23:1.0D-1.0WL	4.000	1.03E+3	4.000	3	-895.478	0.000	3
	24:1.0D-1.0WL	4.000	987.567	3.000	3	-352.983	2.667	1
	25:1.4D	4.000	1.39E+3	4.000	3	-493.911	0.000	3
	26:1.2D+1.5LV	4.000	1.25E+3	4.000	3	-441.738	4.000	1
	27:1.2D+1.5LV	4.000	1.28E+3	4.000	3	-716.629	0.000	3
	28:1.2D+1.5LV	4.000	1.27E+3	4.000	3	-611.283	0.000	3
	29:1.2D+1.5LV	4.000	1.24E+3	4.000	3	-444.121	4.000	2
	30:1.2D+1.5LV	4.000	1.19E+3	4.000	3	-420.034	4.000	2
3	1:DEAD	4.000	1.02E+3	0.000	3	-394.893	4.000	3
	2:WL#1	4.000	1.55E+3	4.000	3	-813.194	4.000	1
	3:WL#4	4.000	2.6E+3	4.000	3	-1.06E+3	4.000	2



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
16

Rev
1

Job Title **Rocky Hill CT**

Part

Ref

By **DAP**

Date **5/13/19**

Chd **BK**

Client **VZW**

File **Rocky Hill CT.std**

Date/Time **13-May-2019 16:22**

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	4:DI	4.000	5.42E+3	0.000	3	-3.02E+3	4.000	3
	5:WLI#1	4.000	723.956	4.000	3	-381.615	4.000	1
	6:WLI#4	4.000	1.21E+3	4.000	3	-498.030	4.000	2
	7:WLS#1	4.000	543.913	4.000	3	-285.724	4.000	1
	8:WLS#4	4.000	914.637	4.000	3	-374.017	4.000	2
	9:WLM#1	4.000	155.694	4.000	3	-81.420	4.000	1
	10:WLM#4	4.000	260.772	4.000	3	-106.565	4.000	2
	11:LM	4.000	46.597	0.000	3	-21.874	4.000	3
	12:LV	4.000	23.299	0.000	3	-10.937	4.000	3
	13:1.2D+1.6WI	4.000	2E+3	4.000	3	-1.09E+3	4.000	1
	14:1.2D+1.6WI	4.000	3.69E+3	4.000	3	-1.49E+3	4.000	2
	15:1.2D-1.6WL	4.000	1.51E+3	4.000	1	-2.95E+3	4.000	3
	16:1.2D-1.6WL	4.000	1.92E+3	4.000	2	-4.64E+3	4.000	3
	17:1.2D+1.0DI	4.000	6.6E+3	0.000	3	-2.79E+3	4.000	3
	18:1.2D+1.0DI	4.000	6.56E+3	0.000	3	-2.33E+3	0.000	1
	19:1.2D+1.0DI	4.000	6.68E+3	0.000	3	-4.22E+3	4.000	3
	20:1.2D+1.0DI	4.000	6.72E+3	0.000	3	-4.7E+3	4.000	3
	21:1.0D+1.0WI	4.000	976.988	0.000	3	-383.331	0.000	1
	22:1.0D+1.0WI	4.000	989.898	1.000	3	-350.637	0.000	1
	23:1.0D-1.0WL	4.000	1.06E+3	0.000	3	-938.806	4.000	3
	24:1.0D-1.0WL	4.000	1.09E+3	0.000	3	-1.31E+3	4.000	3
	25:1.4D	4.000	1.42E+3	0.000	3	-552.850	4.000	3
	26:1.2D+1.5LV	4.000	1.28E+3	0.000	3	-457.092	0.000	1
	27:1.2D+1.5LV	4.000	1.27E+3	0.000	3	-449.047	0.000	1
	28:1.2D+1.5LV	4.000	1.3E+3	0.000	3	-662.282	4.000	3
	29:1.2D+1.5LV	4.000	1.31E+3	0.000	3	-767.451	4.000	3
	30:1.2D+1.5LV	4.000	1.25E+3	0.000	3	-490.277	4.000	3
4	1:DEAD	2.000	2.3E+3	2.000	3	-2.24E+3	2.000	1
	2:WL#1	2.000	2.02E+3	2.000	4	-2.2E+3	2.000	2
	3:WL#4	2.000	3.34E+3	2.000	3	-3.68E+3	2.000	1
	4:DI	2.000	9.28E+3	2.000	3	-9.06E+3	2.000	1
	5:WLI#1	2.000	964.701	2.000	4	-1.05E+3	2.000	2
	6:WLI#4	2.000	1.52E+3	2.000	3	-1.68E+3	2.000	1
	7:WLS#1	2.000	707.843	2.000	4	-772.009	2.000	2
	8:WLS#4	2.000	1.17E+3	2.000	3	-1.29E+3	2.000	1
	9:WLM#1	2.000	202.962	2.000	4	-221.308	2.000	2
	10:WLM#4	2.000	333.915	2.000	3	-367.694	2.000	1
	11:LM	2.000	6.536	0.000	1	-6.225	0.000	3
	12:LV	2.000	3.266	0.000	1	-3.111	0.000	3
	13:1.2D+1.6WI	2.000	5.99E+3	2.000	4	-6.21E+3	2.000	2
	14:1.2D+1.6WI	2.000	8.11E+3	2.000	3	-8.58E+3	2.000	1
	15:1.2D-1.6WL	2.000	2.05E+3	0.000	1	-1.7E+3	0.000	3
	16:1.2D-1.6WL	2.000	3.49E+3	0.000	1	-2.9E+3	0.000	3
	17:1.2D+1.0DI	2.000	13E+3	2.000	3	-12.8E+3	2.000	1



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
17

Rev
1

Job Title **Rocky Hill CT**

Part

Ref

By **DAP**

Date **5/13/19**

Chd **BK**

Client **VZW**

File **Rocky Hill CT.std**

Date/Time **13-May-2019 16:22**

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	18:1.2D+1.0DI-	2.000	13.6E+3	2.000	3	-13.4E+3	2.000	1
	19:1.2D+1.0DI-	2.000	11.3E+3	2.000	3	-10.9E+3	2.000	1
	20:1.2D+1.0DI-	2.000	10.7E+3	2.000	3	-10.2E+3	2.000	1
	21:1.0D+1.0WI	2.000	3.01E+3	2.000	3	-3.01E+3	2.000	1
	22:1.0D+1.0WI	2.000	3.48E+3	2.000	3	-3.54E+3	2.000	1
	23:1.0D-1.0WL	2.000	1.76E+3	2.000	3	-1.63E+3	2.000	1
	24:1.0D-1.0WL	2.000	1.24E+3	2.000	3	-1.06E+3	2.000	1
	25:1.4D	2.000	3.22E+3	2.000	3	-3.14E+3	2.000	1
	26:1.2D+1.5LV	2.000	2.97E+3	2.000	3	-2.92E+3	2.000	1
	27:1.2D+1.5LV	2.000	3.09E+3	2.000	3	-3.05E+3	2.000	1
	28:1.2D+1.5LV	2.000	2.6E+3	2.000	3	-2.51E+3	2.000	1
	29:1.2D+1.5LV	2.000	2.46E+3	2.000	3	-2.36E+3	2.000	1
	30:1.2D+1.5LV	2.000	2.77E+3	2.000	3	-2.69E+3	2.000	1
5	1:DEAD	1.041	4.18E+3	0.000	3	-4.14E+3	0.000	1
	2:WL#1	1.041	5.66E+3	0.000	1	-4.91E+3	0.000	3
	3:WL#4	1.041	1.86E+3	0.000	1	-1.86E+3	0.000	2
	4:DI	1.041	16.5E+3	0.000	3	-16.3E+3	0.000	1
	5:WLI#1	1.041	2.53E+3	0.000	1	-2.17E+3	0.000	3
	6:WLI#4	1.041	965.344	0.000	1	-963.530	0.000	2
	7:WLS#1	1.041	1.99E+3	0.000	1	-1.73E+3	0.000	3
	8:WLS#4	1.041	654.451	0.000	1	-653.364	0.000	2
	9:WLM#1	1.041	567.088	0.000	1	-492.317	0.000	3
	10:WLM#4	1.041	188.073	0.000	1	-187.762	0.000	2
	11:LM	1.041	1.55E+3	0.000	3	-1.55E+3	0.000	1
	12:LV	1.041	3.364	0.000	3	-3.415	0.000	1
	13:1.2D+1.6WI	1.041	4.22E+3	1.041	1	-3E+3	1.041	3
	14:1.2D+1.6WI	1.041	8E+3	0.000	3	-7.95E+3	0.000	1
	15:1.2D-1.6WL	1.041	12.9E+3	0.000	3	-14E+3	0.000	1
	16:1.2D-1.6WL	1.041	7.96E+3	0.000	3	-7.92E+3	0.000	1
	17:1.2D+1.0DI-	1.041	19.5E+3	0.000	3	-18.9E+3	0.000	1
	18:1.2D+1.0DI-	1.041	22.5E+3	0.000	3	-22.3E+3	0.000	1
	19:1.2D+1.0DI-	1.041	23.7E+3	0.000	3	-23.8E+3	0.000	1
	20:1.2D+1.0DI-	1.041	22.5E+3	0.000	3	-22.3E+3	0.000	1
	21:1.0D+1.0WI	1.041	2.59E+3	0.000	3	-2.3E+3	0.000	1
	22:1.0D+1.0WI	1.041	4.83E+3	0.000	3	-4.8E+3	0.000	1
	23:1.0D-1.0WL	1.041	5.91E+3	0.000	3	-6.13E+3	0.000	1
	24:1.0D-1.0WL	1.041	4.82E+3	0.000	3	-4.79E+3	0.000	1
	25:1.4D	1.041	5.85E+3	0.000	3	-5.8E+3	0.000	1
	26:1.2D+1.5LV	1.041	6.89E+3	0.000	3	-6.77E+3	0.000	1
	27:1.2D+1.5LV	1.041	7.53E+3	0.000	3	-7.49E+3	0.000	1
	28:1.2D+1.5LV	1.041	7.83E+3	0.000	3	-7.86E+3	0.000	1
	29:1.2D+1.5LV	1.041	7.53E+3	0.000	3	-7.48E+3	0.000	1
	30:1.2D+1.5LV	1.041	5.02E+3	0.000	3	-4.98E+3	0.000	1
	6	1:DEAD	0.521	4.2E+3	0.000	3	-4.17E+3	0.000



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
18

Rev
1

Job Title **Rocky Hill CT**

Part

Ref

By **DAP**

Date **5/13/19**

Chd **BK**

Client **VZW**

File **Rocky Hill CT.std**

Date/Time **13-May-2019 16:22**

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	2:WL#1	0.521	4.27E+3	0.000	3	-4.63E+3	0.000	1
	3:WL#4	0.521	5.79E+3	0.000	1	-5.13E+3	0.000	3
	4:DI	0.521	17E+3	0.000	3	-16.9E+3	0.000	1
	5:WLI#1	0.521	1.99E+3	0.000	3	-2.18E+3	0.000	1
	6:WLI#4	0.521	2.64E+3	0.000	1	-2.32E+3	0.000	3
	7:WLS#1	0.521	1.5E+3	0.000	3	-1.63E+3	0.000	1
	8:WLS#4	0.521	2.03E+3	0.000	1	-1.8E+3	0.000	3
	9:WLM#1	0.521	428.400	0.000	3	-465.387	0.000	1
	10:WLM#4	0.521	577.927	0.000	1	-512.061	0.000	3
	11:LM	0.521	6.731	0.000	3	-6.832	0.000	1
	12:LV	0.521	775.729	0.000	3	-775.524	0.000	1
	13:1.2D+1.6WI	0.521	11.9E+3	0.000	3	-12.4E+3	0.000	1
	14:1.2D+1.6WI	0.521	4.26E+3	0.000	1	-3.16E+3	0.000	4
	15:1.2D-1.6WL	0.521	4.52E+3	0.000	1	-3.88E+3	0.000	2
	16:1.2D-1.6WL	0.521	13.2E+3	0.000	3	-14.3E+3	0.000	1
	17:1.2D+1.0DI	0.521	24.1E+3	0.000	3	-24E+3	0.000	1
	18:1.2D+1.0DI	0.521	20.7E+3	0.000	3	-20.2E+3	0.000	1
	19:1.2D+1.0DI	0.521	21.9E+3	0.000	3	-21.5E+3	0.000	1
	20:1.2D+1.0DI	0.521	24.4E+3	0.000	3	-24.5E+3	0.000	1
	21:1.0D+1.0WI	0.521	5.7E+3	0.000	3	-5.8E+3	0.000	1
	22:1.0D+1.0WI	0.521	3.17E+3	0.000	3	-2.9E+3	0.000	1
	23:1.0D-1.0WL	0.521	4.09E+3	0.000	3	-3.92E+3	0.000	1
	24:1.0D-1.0WL	0.521	6E+3	0.000	3	-6.2E+3	0.000	1
	25:1.4D	0.521	5.89E+3	0.000	3	-5.83E+3	0.000	1
	26:1.2D+1.5LV	0.521	5.48E+3	0.000	3	-5.48E+3	0.000	1
	27:1.2D+1.5LV	0.521	4.76E+3	0.000	3	-4.65E+3	0.000	1
	28:1.2D+1.5LV	0.521	5.01E+3	0.000	3	-4.93E+3	0.000	1
	29:1.2D+1.5LV	0.521	5.56E+3	0.000	3	-5.58E+3	0.000	1
	30:1.2D+1.5LV	0.521	6.21E+3	0.000	3	-6.16E+3	0.000	1
7	1:DEAD	0.500				-1.665	0.500	
	2:WL#1	0.500	13.096	0.500		-13.096	0.500	
	3:WL#4	0.500	13.096	0.500		-13.096	0.500	
	4:DI	0.500	0.000	0.000		-6.471	0.500	
	5:WLI#1	0.500	9.679	0.500		-9.679	0.500	
	6:WLI#4	0.500	9.679	0.500		-9.679	0.500	
	7:WLS#1	0.500	4.555	0.500		-4.555	0.500	
	8:WLS#4	0.500	4.555	0.500		-4.555	0.500	
	9:WLM#1	0.500	1.423	0.500		-1.423	0.500	
	10:WLM#4	0.500	1.423	0.500		-1.423	0.500	
	11:LM	0.500				-0.000	0.500	
	12:LV	0.500	0.000	0.500				
	13:1.2D+1.6WI	0.500	18.955	0.500		-22.951	0.500	
	14:1.2D+1.6WI	0.500	18.955	0.500		-22.951	0.500	
	15:1.2D-1.6WL	0.500	18.955	0.500		-22.951	0.500	



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
19

Rev
1

Job Title Rocky Hill CT

Part

Ref

By DAP

Date 5/13/19

Chd BK

Client VZW

File Rocky Hill CT.std

Date/Time 13-May-2019 16:22

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	16:1.2D-1.6WL	0.500	18.955	0.500		-22.951	0.500	
	17:1.2D+1.0DI	0.500	1.211	0.500		-18.148	0.500	
	18:1.2D+1.0DI	0.500	1.211	0.500		-18.148	0.500	
	19:1.2D+1.0DI	0.500	1.211	0.500		-18.148	0.500	
	20:1.2D+1.0DI	0.500	1.211	0.500		-18.148	0.500	
	21:1.0D+1.0WI	0.500	2.890	0.500		-6.220	0.500	
	22:1.0D+1.0WI	0.500	2.890	0.500		-6.220	0.500	
	23:1.0D-1.0WL	0.500	2.890	0.500		-6.220	0.500	
	24:1.0D-1.0WL	0.500	2.890	0.500		-6.220	0.500	
	25:1.4D	0.500				-2.331	0.500	
	26:1.2D+1.5LM	0.500				-3.421	0.500	
	27:1.2D+1.5LM	0.500				-3.421	0.500	
	28:1.2D+1.5LM	0.500				-3.421	0.500	
	29:1.2D+1.5LM	0.500				-3.421	0.500	
	30:1.2D+1.5LV	0.500				-1.998	0.500	
9	1:DEAD	0.500	0.000	0.000		-1.665	0.500	
	2:WL#1	0.500	13.096	0.500		-13.096	0.500	
	3:WL#4	0.500	13.096	0.500		-13.096	0.500	
	4:DI	0.500	0.000	0.000		-6.471	0.500	
	5:WLI#1	0.500	9.679	0.500		-9.679	0.500	
	6:WLI#4	0.500	9.679	0.500		-9.679	0.500	
	7:WLS#1	0.500	4.555	0.500		-4.555	0.500	
	8:WLS#4	0.500	4.555	0.500		-4.555	0.500	
	9:WLM#1	0.500	1.423	0.500		-1.423	0.500	
	10:WLM#4	0.500	1.423	0.500		-1.423	0.500	
	11:LM	0.500	0.000	0.000				
	12:LV	0.500				-0.000	0.500	
	13:1.2D+1.6WI	0.500	18.955	0.500		-22.951	0.500	
	14:1.2D+1.6WI	0.500	18.955	0.500		-22.951	0.500	
	15:1.2D-1.6WL	0.500	18.955	0.500		-22.951	0.500	
	16:1.2D-1.6WL	0.500	18.955	0.500		-22.951	0.500	
	17:1.2D+1.0DI	0.500	1.211	0.500		-18.148	0.500	
	18:1.2D+1.0DI	0.500	1.211	0.500		-18.148	0.500	
	19:1.2D+1.0DI	0.500	1.211	0.500		-18.148	0.500	
	20:1.2D+1.0DI	0.500	1.211	0.500		-18.148	0.500	
	21:1.0D+1.0WI	0.500	2.890	0.500		-6.220	0.500	
	22:1.0D+1.0WI	0.500	2.890	0.500		-6.220	0.500	
	23:1.0D-1.0WL	0.500	2.890	0.500		-6.220	0.500	
	24:1.0D-1.0WL	0.500	2.890	0.500		-6.220	0.500	
	25:1.4D	0.500	0.000	0.000		-2.331	0.500	
	26:1.2D+1.5LM	0.500				-3.421	0.500	
	27:1.2D+1.5LM	0.500	0.000	0.000		-3.421	0.500	
	28:1.2D+1.5LM	0.500	0.000	0.000		-3.421	0.500	
	29:1.2D+1.5LM	0.500	0.000	0.000		-3.421	0.500	



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No

50103542

Sheet No

20

Rev

1

Part

Ref

By DAP

Date 5/13/19

Chd BK

Client VZW

File Rocky Hill CT.std

Date/Time 13-May-2019 16:22

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
10	30:1.2D+1.5LV	0.500	0.000	0.000		-1.998	0.500	
	1:DEAD	0.500				-1.665	0.500	
	2:WL#1	0.500	13.096	0.500		-13.096	0.500	
	3:WL#4	0.500	13.096	0.500		-13.096	0.500	
	4:DI	0.500	0.000	0.000		-6.471	0.500	
	5:WLI#1	0.500	9.679	0.500		-9.679	0.500	
	6:WLI#4	0.500	9.679	0.500		-9.679	0.500	
	7:WLS#1	0.500	4.555	0.500		-4.555	0.500	
	8:WLS#4	0.500	4.555	0.500		-4.555	0.500	
	9:WLM#1	0.500	1.423	0.500		-1.423	0.500	
	10:WLM#4	0.500	1.423	0.500		-1.423	0.500	
	11:LM	0.500	0.000	0.500		-0.000	0.500	
	12:LV	0.500	0.000	0.500		-0.000	0.500	
	13:1.2D+1.6WI	0.500	18.955	0.500		-22.951	0.500	
	14:1.2D+1.6WI	0.500	18.955	0.500		-22.951	0.500	
	15:1.2D-1.6WL	0.500	18.955	0.500		-22.951	0.500	
	16:1.2D-1.6WL	0.500	18.955	0.500		-22.951	0.500	
	17:1.2D+1.0DI	0.500	1.211	0.500		-18.148	0.500	
	18:1.2D+1.0DI	0.500	1.211	0.500		-18.148	0.500	
	19:1.2D+1.0DI	0.500	1.211	0.500		-18.148	0.500	
	20:1.2D+1.0DI	0.500	1.211	0.500		-18.148	0.500	
	21:1.0D+1.0WI	0.500	2.890	0.500		-6.220	0.500	
	22:1.0D+1.0WI	0.500	2.890	0.500		-6.220	0.500	
	23:1.0D-1.0WL	0.500	2.890	0.500		-6.220	0.500	
	24:1.0D-1.0WL	0.500	2.890	0.500		-6.220	0.500	
	25:1.4D	0.500				-2.331	0.500	
	26:1.2D+1.5LV	0.500				-3.421	0.500	
	27:1.2D+1.5LV	0.500				-3.421	0.500	
	28:1.2D+1.5LV	0.500				-3.421	0.500	
	29:1.2D+1.5LV	0.500				-3.421	0.500	
	30:1.2D+1.5LV	0.500				-1.998	0.500	
11	1:DEAD	0.500	0.000	0.000		-1.665	0.500	
	2:WL#1	0.500	13.096	0.500		-13.096	0.500	
	3:WL#4	0.500	13.096	0.500		-13.096	0.500	
	4:DI	0.500	0.000	0.000		-6.471	0.500	
	5:WLI#1	0.500	9.679	0.500		-9.679	0.500	
	6:WLI#4	0.500	9.679	0.500		-9.679	0.500	
	7:WLS#1	0.500	4.555	0.500		-4.555	0.500	
	8:WLS#4	0.500	4.555	0.500		-4.555	0.500	
	9:WLM#1	0.500	1.423	0.500		-1.423	0.500	
	10:WLM#4	0.500	1.423	0.500		-1.423	0.500	
	11:LM	0.500	0.000	0.500				
	12:LV	0.500	0.000	0.500		-0.000	0.500	
	13:1.2D+1.6WI	0.500	18.955	0.500		-22.951	0.500	



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
21

Rev
1

Job Title **Rocky Hill CT**

Part

Ref

By **DAP**

Date **5/13/19**

Chd **BK**

Client **VZW**

File **Rocky Hill CT.std**

Date/Time **13-May-2019 16:22**

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	14:1.2D+1.6WI	0.500	18.955	0.500		-22.951	0.500	
	15:1.2D-1.6WL	0.500	18.955	0.500		-22.951	0.500	
	16:1.2D-1.6WL	0.500	18.955	0.500		-22.951	0.500	
	17:1.2D+1.0DI-	0.500	1.211	0.500		-18.148	0.500	
	18:1.2D+1.0DI-	0.500	1.211	0.500		-18.148	0.500	
	19:1.2D+1.0DI-	0.500	1.211	0.500		-18.148	0.500	
	20:1.2D+1.0DI-	0.500	1.211	0.500		-18.148	0.500	
	21:1.0D+1.0WI	0.500	2.890	0.500		-6.220	0.500	
	22:1.0D+1.0WI	0.500	2.890	0.500		-6.220	0.500	
	23:1.0D-1.0WL	0.500	2.890	0.500		-6.220	0.500	
	24:1.0D-1.0WL	0.500	2.890	0.500		-6.220	0.500	
	25:1.4D	0.500	0.000	0.000		-2.331	0.500	
	26:1.2D+1.5LM	0.500				-3.421	0.500	
	27:1.2D+1.5LM	0.500	0.000	0.000		-3.421	0.500	
	28:1.2D+1.5LM	0.500	0.000	0.000		-3.421	0.500	
	29:1.2D+1.5LM	0.500	0.000	0.000		-3.421	0.500	
	30:1.2D+1.5LV	0.500	0.000	0.000		-1.998	0.500	
13	1:DEAD	0.500	0.000	0.000		-1.665	0.500	
	2:WL#1	0.500	13.096	0.500		-13.096	0.500	
	3:WL#4	0.500	13.096	0.500		-13.096	0.500	
	4:DI	0.500				-6.471	0.500	
	5:WLI#1	0.500	9.679	0.500		-9.679	0.500	
	6:WLI#4	0.500	9.679	0.500		-9.679	0.500	
	7:WLS#1	0.500	4.555	0.500		-4.555	0.500	
	8:WLS#4	0.500	4.555	0.500		-4.555	0.500	
	9:WLM#1	0.500	1.423	0.500		-1.423	0.500	
	10:WLM#4	0.500	1.423	0.500		-1.423	0.500	
	11:LM	0.500				-0.000	0.458	
	12:LV	0.500				-0.000	0.500	
	13:1.2D+1.6WI	0.500	18.955	0.500		-22.951	0.500	
	14:1.2D+1.6WI	0.500	18.955	0.500		-22.951	0.500	
	15:1.2D-1.6WL	0.500	18.955	0.500		-22.951	0.500	
	16:1.2D-1.6WL	0.500	18.955	0.500		-22.951	0.500	
	17:1.2D+1.0DI-	0.500	1.211	0.500		-18.148	0.500	
	18:1.2D+1.0DI-	0.500	1.211	0.500		-18.148	0.500	
	19:1.2D+1.0DI-	0.500	1.211	0.500		-18.148	0.500	
	20:1.2D+1.0DI-	0.500	1.211	0.500		-18.148	0.500	
	21:1.0D+1.0WI	0.500	2.890	0.500		-6.220	0.500	
	22:1.0D+1.0WI	0.500	2.890	0.500		-6.220	0.500	
	23:1.0D-1.0WL	0.500	2.890	0.500		-6.220	0.500	
	24:1.0D-1.0WL	0.500	2.890	0.500		-6.220	0.500	
	25:1.4D	0.500	0.000	0.000		-2.331	0.500	
	26:1.2D+1.5LM	0.500	0.000	0.000		-3.421	0.500	
	27:1.2D+1.5LM	0.500	0.000	0.000		-3.421	0.500	



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
22

Rev
1

Job Title **Rocky Hill CT**

Part

Ref

By **DAP**

Date **5/13/19**

Chd **BK**

Client **VZW**

File **Rocky Hill CT.std**

Date/Time **13-May-2019 16:22**

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	28:1.2D+1.5LV	0.500	0.000	0.000		-3.421	0.500	
	29:1.2D+1.5LV	0.500	0.000	0.000		-3.421	0.500	
	30:1.2D+1.5LV	0.500	0.000	0.000		-1.998	0.500	
14	1:DEAD	0.500	0.000	0.000		-1.665	0.500	
	2:WL#1	0.500	13.096	0.500		-13.096	0.500	
	3:WL#4	0.500	13.096	0.500		-13.096	0.500	
	4:DI	0.500	0.000	0.000		-6.471	0.500	
	5:WLI#1	0.500	9.679	0.500		-9.679	0.500	
	6:WLI#4	0.500	9.679	0.500		-9.679	0.500	
	7:WLS#1	0.500	4.555	0.500		-4.555	0.500	
	8:WLS#4	0.500	4.555	0.500		-4.555	0.500	
	9:WLM#1	0.500	1.423	0.500		-1.423	0.500	
	10:WLM#4	0.500	1.423	0.500		-1.423	0.500	
	11:LM	0.500	0.000	0.500		-0.000	0.500	
	12:LV	0.500	0.000	0.500		-0.000	0.500	
	13:1.2D+1.6WI	0.500	18.955	0.500		-22.951	0.500	
	14:1.2D+1.6WI	0.500	18.955	0.500		-22.951	0.500	
	15:1.2D-1.6WL	0.500	18.955	0.500		-22.951	0.500	
	16:1.2D-1.6WL	0.500	18.955	0.500		-22.951	0.500	
	17:1.2D+1.0DI	0.500	1.211	0.500		-18.148	0.500	
	18:1.2D+1.0DI	0.500	1.211	0.500		-18.148	0.500	
	19:1.2D+1.0DI	0.500	1.211	0.500		-18.148	0.500	
	20:1.2D+1.0DI	0.500	1.211	0.500		-18.148	0.500	
	21:1.0D+1.0WI	0.500	2.890	0.500		-6.220	0.500	
	22:1.0D+1.0WI	0.500	2.890	0.500		-6.220	0.500	
	23:1.0D-1.0WL	0.500	2.890	0.500		-6.220	0.500	
	24:1.0D-1.0WL	0.500	2.890	0.500		-6.220	0.500	
	25:1.4D	0.500	0.000	0.000		-2.331	0.500	
	26:1.2D+1.5LV	0.500	0.000	0.000		-3.421	0.500	
	27:1.2D+1.5LV	0.500	0.000	0.000		-3.421	0.500	
	28:1.2D+1.5LV	0.500	0.000	0.000		-3.421	0.500	
	29:1.2D+1.5LV	0.500	0.000	0.000		-3.421	0.500	
	30:1.2D+1.5LV	0.500	0.000	0.000		-1.998	0.500	
15	1:DEAD	0.500				-1.665	0.500	
	2:WL#1	0.500	13.096	0.500		-13.096	0.500	
	3:WL#4	0.500	13.096	0.500		-13.096	0.500	
	4:DI	0.500				-6.471	0.500	
	5:WLI#1	0.500	9.679	0.500		-9.679	0.500	
	6:WLI#4	0.500	9.679	0.500		-9.679	0.500	
	7:WLS#1	0.500	4.555	0.500		-4.555	0.500	
	8:WLS#4	0.500	4.555	0.500		-4.555	0.500	
	9:WLM#1	0.500	1.423	0.500		-1.423	0.500	
	10:WLM#4	0.500	1.423	0.500		-1.423	0.500	
	11:LM	0.500	0.000	0.458				



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
23

Rev
1

Job Title **Rocky Hill CT**

Part

Ref

By **DAP**

Date **5/13/19**

Chd **BK**

Client **VZW**

File **Rocky Hill CT.std**

Date/Time **13-May-2019 16:22**

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	12:LV	0.500	0.000	0.500				
	13:1.2D+1.6WI	0.500	18.955	0.500		-22.951	0.500	
	14:1.2D+1.6WI	0.500	18.955	0.500		-22.951	0.500	
	15:1.2D-1.6WL	0.500	18.955	0.500		-22.951	0.500	
	16:1.2D-1.6WL	0.500	18.955	0.500		-22.951	0.500	
	17:1.2D+1.0DI	0.500	1.211	0.500		-18.148	0.500	
	18:1.2D+1.0DI	0.500	1.211	0.500		-18.148	0.500	
	19:1.2D+1.0DI	0.500	1.211	0.500		-18.148	0.500	
	20:1.2D+1.0DI	0.500	1.211	0.500		-18.148	0.500	
	21:1.0D+1.0WI	0.500	2.890	0.500		-6.220	0.500	
	22:1.0D+1.0WI	0.500	2.890	0.500		-6.220	0.500	
	23:1.0D-1.0WL	0.500	2.890	0.500		-6.220	0.500	
	24:1.0D-1.0WL	0.500	2.890	0.500		-6.220	0.500	
	25:1.4D	0.500				-2.331	0.500	
	26:1.2D+1.5LM	0.500				-3.421	0.500	
	27:1.2D+1.5LM	0.500				-3.421	0.500	
	28:1.2D+1.5LM	0.500				-3.421	0.500	
	29:1.2D+1.5LM	0.500				-3.421	0.500	
	30:1.2D+1.5LV	0.500				-1.998	0.500	
17	1:DEAD	0.500	0.000	0.000		-1.665	0.500	
	2:WL#1	0.500	13.096	0.500		-13.096	0.500	
	3:WL#4	0.500	13.096	0.500		-13.096	0.500	
	4:DI	0.500	0.000	0.000		-6.471	0.500	
	5:WLI#1	0.500	9.679	0.500		-9.679	0.500	
	6:WLI#4	0.500	9.679	0.500		-9.679	0.500	
	7:WLS#1	0.500	4.555	0.500		-4.555	0.500	
	8:WLS#4	0.500	4.555	0.500		-4.555	0.500	
	9:WLM#1	0.500	1.423	0.500		-1.423	0.500	
	10:WLM#4	0.500	1.423	0.500		-1.423	0.500	
	11:LM	0.500	0.000	0.458				
	12:LV	0.500				-0.000	0.500	
	13:1.2D+1.6WI	0.500	18.955	0.500		-22.951	0.500	
	14:1.2D+1.6WI	0.500	18.955	0.500		-22.951	0.500	
	15:1.2D-1.6WL	0.500	18.955	0.500		-22.951	0.500	
	16:1.2D-1.6WL	0.500	18.955	0.500		-22.951	0.500	
	17:1.2D+1.0DI	0.500	1.211	0.500		-18.148	0.500	
	18:1.2D+1.0DI	0.500	1.211	0.500		-18.148	0.500	
	19:1.2D+1.0DI	0.500	1.211	0.500		-18.148	0.500	
	20:1.2D+1.0DI	0.500	1.211	0.500		-18.148	0.500	
	21:1.0D+1.0WI	0.500	2.890	0.500		-6.220	0.500	
	22:1.0D+1.0WI	0.500	2.890	0.500		-6.220	0.500	
	23:1.0D-1.0WL	0.500	2.890	0.500		-6.220	0.500	
	24:1.0D-1.0WL	0.500	2.890	0.500		-6.220	0.500	
	25:1.4D	0.500	0.000	0.000		-2.331	0.500	



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
24

Rev
1

Job Title **Rocky Hill CT**

Part

Ref

By **DAP**

Date **5/13/19**

Chd **BK**

Client **VZW**

File **Rocky Hill CT.std**

Date/Time **13-May-2019 16:22**

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	26:1.2D+1.5LM	0.500	0.000	0.000		-3.421	0.500	
	27:1.2D+1.5LM	0.500	0.000	0.000		-3.421	0.500	
	28:1.2D+1.5LM	0.500	0.000	0.000		-3.421	0.500	
	29:1.2D+1.5LM	0.500	0.000	0.000		-3.421	0.500	
	30:1.2D+1.5LV	0.500	0.000	0.000		-1.998	0.500	
18	1:DEAD	0.500				-1.665	0.500	
	2:WL#1	0.500	13.096	0.500		-13.096	0.500	
	3:WL#4	0.500	13.096	0.500		-13.096	0.500	
	4:DI	0.500				-6.471	0.500	
	5:WLI#1	0.500	9.679	0.500		-9.679	0.500	
	6:WLI#4	0.500	9.679	0.500		-9.679	0.500	
	7:WLS#1	0.500	4.555	0.500		-4.555	0.500	
	8:WLS#4	0.500	4.555	0.500		-4.555	0.500	
	9:WLM#1	0.500	1.423	0.500		-1.423	0.500	
	10:WLM#4	0.500	1.423	0.500		-1.423	0.500	
	11:LM	0.500	0.000	0.500				
	12:LV	0.500	0.000	0.500		-0.000	0.500	
	13:1.2D+1.6WI	0.500	18.955	0.500		-22.951	0.500	
	14:1.2D+1.6WI	0.500	18.955	0.500		-22.951	0.500	
	15:1.2D-1.6WL	0.500	18.955	0.500		-22.951	0.500	
	16:1.2D-1.6WL	0.500	18.955	0.500		-22.951	0.500	
	17:1.2D+1.0DI	0.500	1.211	0.500		-18.148	0.500	
	18:1.2D+1.0DI	0.500	1.211	0.500		-18.148	0.500	
	19:1.2D+1.0DI	0.500	1.211	0.500		-18.148	0.500	
	20:1.2D+1.0DI	0.500	1.211	0.500		-18.148	0.500	
	21:1.0D+1.0WI	0.500	2.890	0.500		-6.220	0.500	
	22:1.0D+1.0WI	0.500	2.890	0.500		-6.220	0.500	
	23:1.0D-1.0WL	0.500	2.890	0.500		-6.220	0.500	
	24:1.0D-1.0WL	0.500	2.890	0.500		-6.220	0.500	
	25:1.4D	0.500				-2.331	0.500	
	26:1.2D+1.5LM	0.500				-3.421	0.500	
	27:1.2D+1.5LM	0.500				-3.421	0.500	
	28:1.2D+1.5LM	0.500				-3.421	0.500	
	29:1.2D+1.5LM	0.500				-3.421	0.500	
	30:1.2D+1.5LV	0.500				-1.998	0.500	
19	1:DEAD	1.333	559.224	1.333	3	-1.04E+3	1.333	2
	2:WL#1	1.333	331.106	1.333	2	-593.401	1.333	1
	3:WL#4	1.333	970.635	1.333	2	-656.302	1.333	1
	4:DI	1.333	2.37E+3	1.333	3	-4.47E+3	1.333	2
	5:WLI#1	1.333	99.494	1.333	3	-262.236	1.333	1
	6:WLI#4	1.333	418.504	1.333	2	-303.835	1.333	1
	7:WLS#1	1.333	116.997	1.333	2	-208.607	1.333	1
	8:WLS#4	1.333	341.108	1.333	2	-230.558	1.333	1
	9:WLM#1	1.333	31.809	1.333	2	-59.402	1.333	1



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No 50103542	Sheet No 25	Rev 1
Part		
Ref		
By DAP	Date 5/13/19	Chd BK
File Rocky Hill CT.std	Date/Time 13-May-2019 16:22	

Job Title Rocky Hill CT

Client VZW

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	10:WLM#4	1.333	96.736	1.333	2	-65.683	1.333	1
	11:LM	1.333	16.323	0.000	1	-39.500	0.000	2
	12:LV	1.333	1.941	1.333	3	-3.966	1.333	2
	13:1.2D+1.6WI	1.333	898.271	1.333	3	-764.706	1.333	1
	14:1.2D+1.6WI	1.333	614.700	0.000	1	-1.16E+3	0.000	2
	15:1.2D-1.6WL	1.333	1.13E+3	1.333	1	-1.78E+3	1.333	2
	16:1.2D-1.6WL	1.333	1.23E+3	1.333	1	-2.8E+3	1.333	2
	17:1.2D+1.0DI	1.333	3.14E+3	1.333	3	-5.62E+3	1.333	2
	18:1.2D+1.0DI	1.333	2.96E+3	1.333	3	-5.3E+3	1.333	2
	19:1.2D+1.0DI	1.333	2.94E+3	1.333	3	-5.82E+3	1.333	2
	20:1.2D+1.0DI	1.333	3.12E+3	1.333	3	-6.14E+3	1.333	2
	21:1.0D+1.0WI	1.333	608.733	1.333	3	-924.827	1.333	2
	22:1.0D+1.0WI	1.333	482.091	1.333	3	-843.325	0.000	2
	23:1.0D-1.0WL	1.333	509.715	1.333	3	-1.16E+3	1.333	2
	24:1.0D-1.0WL	1.333	636.357	1.333	3	-1.38E+3	1.333	2
	25:1.4D	1.333	782.913	1.333	3	-1.46E+3	1.333	2
	26:1.2D+1.5LV	1.333	704.104	1.333	3	-1.26E+3	1.333	2
	27:1.2D+1.5LV	1.333	667.312	1.333	3	-1.19E+3	1.333	2
	28:1.2D+1.5LV	1.333	673.883	1.333	3	-1.32E+3	1.333	2
	29:1.2D+1.5LV	1.333	710.675	1.333	3	-1.39E+3	1.333	2
	30:1.2D+1.5LV	1.333	673.980	1.333	3	-1.26E+3	1.333	2
20	1:DEAD	1.889	1.79E+3	0.000	1	-4.25E+3	0.000	2
	2:WL#1	1.889	1.88E+3	0.000	1	-3.37E+3	0.000	2
	3:WL#4	1.889	2.69E+3	0.000	1	-5.24E+3	0.000	2
	4:DI	1.889	6.8E+3	0.000	1	-16.2E+3	0.000	2
	5:WLI#1	1.889	865.710	0.000	1	-1.53E+3	0.000	2
	6:WLI#4	1.889	1.27E+3	0.000	1	-2.41E+3	0.000	2
	7:WLS#1	1.889	658.887	0.000	1	-1.18E+3	0.000	2
	8:WLS#4	1.889	945.448	0.000	1	-1.84E+3	0.000	2
	9:WLM#1	1.889	188.015	0.000	1	-337.932	0.000	2
	10:WLM#4	1.889	269.999	0.000	1	-524.801	0.000	2
	11:LM	1.889	22.198	0.000	2	-10.875	0.000	1
	12:LV	1.889	13.402	0.000	1	-28.013	0.000	2
	13:1.2D+1.6WI	1.889	5.14E+3	0.000	1	-10.5E+3	0.000	2
	14:1.2D+1.6WI	1.889	6.45E+3	0.000	1	-13.5E+3	0.000	2
	15:1.2D-1.6WL	1.889	2.29E+3	1.889	2	-1.52E+3	1.889	3
	16:1.2D-1.6WL	1.889	3.28E+3	0.000	2	-2.17E+3	0.000	1
	17:1.2D+1.0DI	1.889	9.81E+3	0.000	1	-22.9E+3	0.000	2
	18:1.2D+1.0DI	1.889	10.2E+3	0.000	1	-23.8E+3	0.000	2
	19:1.2D+1.0DI	1.889	8.08E+3	0.000	1	-19.8E+3	0.000	2
	20:1.2D+1.0DI	1.889	7.68E+3	0.000	1	-18.9E+3	0.000	2
	21:1.0D+1.0WI	1.889	2.44E+3	0.000	1	-5.44E+3	0.000	2
	22:1.0D+1.0WI	1.889	2.73E+3	0.000	1	-6.09E+3	0.000	2
	23:1.0D-1.0WL	1.889	1.13E+3	0.000	1	-3.07E+3	0.000	2



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
26

Rev
1

Job Title **Rocky Hill CT**

Part

Ref

By **DAP**

Date **5/13/19**

Chd **BK**

Client **VZW**

File **Rocky Hill CT.std**

Date/Time **13-May-2019 16:22**

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	24:1.0D-1.0WL	1.889	839.925	0.000	1	-2.41E+3	0.000	2
	25:1.4D	1.889	2.5E+3	0.000	1	-5.95E+3	0.000	2
	26:1.2D+1.5LV	1.889	2.31E+3	0.000	1	-5.41E+3	0.000	2
	27:1.2D+1.5LV	1.889	2.4E+3	0.000	1	-5.6E+3	0.000	2
	28:1.2D+1.5LV	1.889	1.94E+3	0.000	1	-4.73E+3	0.000	2
	29:1.2D+1.5LV	1.889	1.86E+3	0.000	1	-4.55E+3	0.000	2
	30:1.2D+1.5LV	1.889	2.16E+3	0.000	1	-5.15E+3	0.000	2
21	1:DEAD	1.333	539.803	1.333	3	-996.210	1.333	2
	2:WL#1	1.333	609.203	1.333	2	-248.265	1.333	1
	3:WL#4	1.333	874.757	1.333	1	-788.545	1.333	2
	4:DI	1.333	1.89E+3	1.333	3	-4.18E+3	0.000	2
	5:WLI#1	1.333	290.955	1.333	2	-126.473	1.333	1
	6:WLI#4	1.333	393.145	1.333	1	-335.689	1.333	2
	7:WLS#1	1.333	213.895	1.333	2	-87.189	1.333	1
	8:WLS#4	1.333	307.235	1.333	1	-277.024	1.333	2
	9:WLM#1	1.333	61.536	1.333	2	-25.076	1.333	1
	10:WLM#4	1.333	87.330	1.333	1	-78.146	1.333	2
	11:LM	1.333	3.882	1.333	3	-7.933	1.333	2
	12:LV	1.333	8.690	0.000	1	-20.554	0.000	2
	13:1.2D+1.6WI	1.333	529.239	0.000	1	-1.25E+3	0.000	2
	14:1.2D+1.6WI	1.333	1.56E+3	1.333	1	-2.46E+3	1.333	2
	15:1.2D-1.6WL	1.333	1.01E+3	1.333	3	-2.17E+3	1.333	2
	16:1.2D-1.6WL	1.333	667.948	1.333	3	-1.24E+3	1.333	1
	17:1.2D+1.0DI	1.333	2.43E+3	1.333	3	-5.22E+3	0.000	2
	18:1.2D+1.0DI	1.333	2.51E+3	1.333	3	-5.2E+3	0.000	2
	19:1.2D+1.0DI	1.333	2.64E+3	1.333	3	-5.06E+3	0.000	2
	20:1.2D+1.0DI	1.333	2.56E+3	1.333	3	-5.08E+3	0.000	2
	21:1.0D+1.0WI	1.333	459.693	1.333	3	-864.716	0.000	2
	22:1.0D+1.0WI	1.333	535.436	1.333	3	-1.27E+3	1.333	2
	23:1.0D-1.0WL	1.333	619.913	1.333	3	-1.21E+3	1.333	2
	24:1.0D-1.0WL	1.333	544.170	1.333	3	-753.206	0.000	2
	25:1.4D	1.333	755.724	1.333	3	-1.39E+3	1.333	2
	26:1.2D+1.5LV	1.333	630.510	1.333	3	-1.15E+3	1.333	2
	27:1.2D+1.5LV	1.333	651.892	1.333	3	-1.29E+3	1.333	2
	28:1.2D+1.5LV	1.333	676.663	1.333	3	-1.27E+3	1.333	2
	29:1.2D+1.5LV	1.333	655.281	1.333	3	-1.13E+3	1.333	2
	30:1.2D+1.5LV	1.333	653.019	1.333	3	-1.21E+3	1.333	2
22	1:DEAD	1.889	1.85E+3	0.000	1	-4.4E+3	0.000	2
	2:WL#1	1.889	1.49E+3	0.000	1	-3.02E+3	0.000	2
	3:WL#4	1.889	5.36E+3	0.000	2	-2.9E+3	0.000	1
	4:DI	1.889	7.79E+3	0.000	1	-18.6E+3	0.000	2
	5:WLI#1	1.889	713.713	0.000	1	-1.41E+3	0.000	2
	6:WLI#4	1.889	2.47E+3	0.000	2	-1.36E+3	0.000	1
	7:WLS#1	1.889	523.168	0.000	1	-1.06E+3	0.000	2



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
27

Rev
1

Job Title **Rocky Hill CT**

Part

Ref

By **DAP**

Date **5/13/19**

Chd **BK**

Client **VZW**

File **Rocky Hill CT.std**

Date/Time **13-May-2019 16:22**

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	8:WLS#4	1.889	1.88E+3	0.000	2	-1.02E+3	0.000	1
	9:WLM#1	1.889	150.198	0.000	1	-303.687	0.000	2
	10:WLM#4	1.889	537.127	0.000	2	-290.719	0.000	1
	11:LM	1.889	26.798	0.000	1	-56.018	0.000	2
	12:LV	1.889	42.005	0.000	2	-17.828	0.000	1
	13:1.2D+1.6WI	1.889	4.6E+3	0.000	1	-10.1E+3	0.000	2
	14:1.2D+1.6WI	1.889	3.3E+3	0.000	2	-2.42E+3	0.000	1
	15:1.2D-1.6WL	1.889	648.811	1.889	3	-1.98E+3	1.889	2
	16:1.2D-1.6WL	1.889	6.86E+3	0.000	1	-13.9E+3	0.000	2
	17:1.2D+1.0DI	1.889	10.7E+3	0.000	1	-25.3E+3	0.000	2
	18:1.2D+1.0DI	1.889	8.65E+3	0.000	1	-21.4E+3	0.000	2
	19:1.2D+1.0DI	1.889	9.29E+3	0.000	1	-22.5E+3	0.000	2
	20:1.2D+1.0DI	1.889	11.4E+3	0.000	1	-26.3E+3	0.000	2
	21:1.0D+1.0WI	1.889	2.37E+3	0.000	1	-5.46E+3	0.000	2
	22:1.0D+1.0WI	1.889	830.347	0.000	1	-2.52E+3	0.000	2
	23:1.0D-1.0WL	1.889	1.33E+3	0.000	1	-3.34E+3	0.000	2
	24:1.0D-1.0WL	1.889	2.87E+3	0.000	1	-6.29E+3	0.000	2
	25:1.4D	1.889	2.59E+3	0.000	1	-6.16E+3	0.000	2
	26:1.2D+1.5LV	1.889	2.41E+3	0.000	1	-5.67E+3	0.000	2
	27:1.2D+1.5LV	1.889	1.97E+3	0.000	1	-4.83E+3	0.000	2
	28:1.2D+1.5LV	1.889	2.11E+3	0.000	1	-5.06E+3	0.000	2
	29:1.2D+1.5LV	1.889	2.55E+3	0.000	1	-5.9E+3	0.000	2
	30:1.2D+1.5LV	1.889	2.19E+3	0.000	1	-5.22E+3	0.000	2
23	1:DEAD	1.333	557.818	1.333	3	-1.02E+3	1.333	2
	2:WL#1	1.333	899.531	1.333	1	-1.07E+3	1.333	2
	3:WL#4	1.333	250.846	0.000	2	-245.187	1.333	1
	4:DI	1.333	2.37E+3	1.333	3	-4.43E+3	0.000	2
	5:WLI#1	1.333	392.201	1.333	1	-435.881	1.333	2
	6:WLI#4	1.333	108.062	0.000	1	-101.887	0.000	3
	7:WLS#1	1.333	316.179	1.333	1	-375.792	1.333	2
	8:WLS#4	1.333	88.181	0.000	2	-86.208	1.333	1
	9:WLM#1	1.333	89.872	1.333	1	-106.085	1.333	2
	10:WLM#4	1.333	24.947	0.000	2	-24.403	1.333	1
	11:LM	1.333	17.301	0.000	1	-41.129	0.000	2
	12:LV	1.333	8.156	0.000	1	-19.754	0.000	2
	13:1.2D+1.6WI	1.333	1.61E+3	1.333	1	-2.94E+3	1.333	2
	14:1.2D+1.6WI	1.333	862.410	1.333	3	-1.26E+3	1.333	2
	15:1.2D-1.6WL	1.333	659.822	0.000	1	-1.26E+3	1.333	1
	16:1.2D-1.6WL	1.333	673.405	0.000	1	-1.39E+3	0.000	2
	17:1.2D+1.0DI	1.333	3.06E+3	1.333	3	-5.99E+3	1.333	2
	18:1.2D+1.0DI	1.333	3.12E+3	1.333	3	-5.61E+3	1.333	2
	19:1.2D+1.0DI	1.333	3.01E+3	1.333	3	-5.4E+3	0.000	2
	20:1.2D+1.0DI	1.333	2.95E+3	1.333	3	-5.52E+3	0.000	2
	21:1.0D+1.0WI	1.333	597.619	1.333	3	-1.4E+3	1.333	2



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
28

Rev
1

Part

Job Title Rocky Hill CT

Ref

By DAP

Date 5/13/19

Chd BK

Client VZW

File Rocky Hill CT.std

Date/Time 13-May-2019 16:22

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	22:1.0D+1.0WI	1.333	599.947	1.333	3	-1.03E+3	1.333	2
	23:1.0D-1.0WL	1.333	518.017	1.333	3	-821.902	0.000	2
	24:1.0D-1.0WL	1.333	515.688	1.333	3	-1.01E+3	1.333	2
	25:1.4D	1.333	780.945	1.333	3	-1.43E+3	1.333	2
	26:1.2D+1.5LV	1.333	690.621	1.333	3	-1.36E+3	1.333	2
	27:1.2D+1.5LV	1.333	692.353	1.333	3	-1.26E+3	1.333	2
	28:1.2D+1.5LV	1.333	669.044	1.333	3	-1.15E+3	1.333	2
	29:1.2D+1.5LV	1.333	667.312	1.333	3	-1.26E+3	1.333	2
	30:1.2D+1.5LV	1.333	678.351	1.333	3	-1.25E+3	1.333	2
24	1:DEAD	1.889	1.82E+3	0.000	1	-4.34E+3	0.000	2
	2:WL#1	1.889	6.16E+3	0.000	2	-3.26E+3	0.000	1
	3:WL#4	1.889	737.548	1.889	3	-1.42E+3	1.889	2
	4:DI	1.889	7.4E+3	0.000	1	-17.8E+3	0.000	2
	5:WLI#1	1.889	2.91E+3	0.000	2	-1.57E+3	0.000	1
	6:WLI#4	1.889	339.758	1.889	3	-652.143	1.889	2
	7:WLS#1	1.889	2.16E+3	0.000	2	-1.14E+3	0.000	1
	8:WLS#4	1.889	259.031	1.889	3	-500.023	1.889	2
	9:WLM#1	1.889	620.049	0.000	2	-327.968	0.000	1
	10:WLM#4	1.889	73.733	1.889	3	-142.193	1.889	2
	11:LM	1.889	84.021	0.000	2	-35.659	0.000	1
	12:LV	1.889	11.100	0.000	2	-5.437	0.000	1
	13:1.2D+1.6WI	1.889	4.65E+3	0.000	2	-3.03E+3	0.000	1
	14:1.2D+1.6WI	1.889	2.51E+3	0.000	1	-5.47E+3	0.000	2
	15:1.2D-1.6WL	1.889	7.39E+3	0.000	1	-15.1E+3	0.000	2
	16:1.2D-1.6WL	1.889	1.85E+3	0.000	1	-4.94E+3	0.000	2
	17:1.2D+1.0DI	1.889	8.01E+3	0.000	1	-20.1E+3	0.000	2
	18:1.2D+1.0DI	1.889	9.66E+3	0.000	1	-23E+3	0.000	2
	19:1.2D+1.0DI	1.889	11.1E+3	0.000	1	-25.9E+3	0.000	2
	20:1.2D+1.0DI	1.889	9.5E+3	0.000	1	-22.9E+3	0.000	2
	21:1.0D+1.0WI	1.889	699.226	0.000	1	-2.18E+3	0.000	2
	22:1.0D+1.0WI	1.889	1.89E+3	0.000	1	-4.4E+3	0.000	2
	23:1.0D-1.0WL	1.889	2.96E+3	0.000	1	-6.5E+3	0.000	2
	24:1.0D-1.0WL	1.889	1.75E+3	0.000	1	-4.28E+3	0.000	2
	25:1.4D	1.889	2.55E+3	0.000	1	-6.07E+3	0.000	2
	26:1.2D+1.5LV	1.889	1.8E+3	0.000	1	-4.46E+3	0.000	2
	27:1.2D+1.5LV	1.889	2.15E+3	0.000	1	-5.1E+3	0.000	2
	28:1.2D+1.5LV	1.889	2.46E+3	0.000	1	-5.7E+3	0.000	2
	29:1.2D+1.5LV	1.889	2.11E+3	0.000	1	-5.07E+3	0.000	2
	30:1.2D+1.5LV	1.889	2.17E+3	0.000	1	-5.19E+3	0.000	2
25	1:DEAD	1.179	690.137	1.179	2	-1.03E+3	1.179	1
	2:WL#1	1.179	1.48E+3	1.179	1	-924.610	1.179	3
	3:WL#4	1.179	1.79E+3	1.179	2	-2.91E+3	1.179	1
	4:DI	1.179	3.19E+3	1.179	2	-5.01E+3	1.179	1
	5:WLI#1	1.179	689.376	1.179	1	-432.082	1.179	3



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
29

Rev
1

Part

Job Title Rocky Hill CT

Ref

By DAP

Date 5/13/19

Chd BK

Client VZW

File Rocky Hill CT.std

Date/Time 13-May-2019 16:22

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	6:WLI#4	1.179	839.920	1.179	2	-1.34E+3	1.179	1
	7:WLS#1	1.179	518.196	1.179	1	-324.743	1.179	3
	8:WLS#4	1.179	628.181	1.179	2	-1.02E+3	1.179	1
	9:WLM#1	1.179	148.389	1.179	1	-93.067	1.179	3
	10:WLM#4	1.179	179.120	1.179	2	-291.039	1.179	1
	11:LM	1.179	24.401	1.179	2	-56.326	1.179	1
	12:LV	1.179	12.274	1.179	1	-5.038	1.179	3
	13:1.2D+1.6WI	1.179	1.66E+3	0.000	1	-1.16E+3	1.179	3
	14:1.2D+1.6WI	1.179	3.69E+3	1.179	2	-5.89E+3	1.179	1
	15:1.2D-1.6WL	1.179	1.79E+3	1.179	3	-3.6E+3	1.179	1
	16:1.2D-1.6WL	1.179	3.41E+3	1.179	1	-2.03E+3	1.179	2
	17:1.2D+1.0DI	1.179	4.07E+3	1.179	2	-5.56E+3	1.179	1
	18:1.2D+1.0DI	1.179	4.86E+3	1.179	2	-7.58E+3	1.179	1
	19:1.2D+1.0DI	1.179	3.97E+3	1.179	2	-6.94E+3	1.179	1
	20:1.2D+1.0DI	1.179	3.18E+3	1.179	2	-4.91E+3	1.179	1
	21:1.0D+1.0WI	1.179	718.146	1.179	2	-514.974	1.179	1
	22:1.0D+1.0WI	1.179	1.32E+3	1.179	2	-2.05E+3	1.179	1
	23:1.0D-1.0WL	1.179	662.128	1.179	2	-1.55E+3	1.179	1
	24:1.0D-1.0WL	1.179	434.529	0.000	1	-173.414	0.000	2
	25:1.4D	1.179	966.191	1.179	2	-1.45E+3	1.179	1
	26:1.2D+1.5LM	1.179	873.119	1.179	2	-1.18E+3	1.179	1
	27:1.2D+1.5LM	1.179	1.04E+3	1.179	2	-1.62E+3	1.179	1
	28:1.2D+1.5LM	1.179	856.413	1.179	2	-1.47E+3	1.179	1
	29:1.2D+1.5LM	1.179	685.646	1.179	2	-1.03E+3	1.179	1
	30:1.2D+1.5LV	1.179	822.464	1.179	2	-1.22E+3	1.179	1
26	1:DEAD	1.179	1.61E+3	0.000	2	-3.95E+3	0.000	1
	2:WL#1	1.179	2.28E+3	0.000	2	-4.96E+3	0.000	1
	3:WL#4	1.179	571.214	0.000	2	-1.51E+3	0.000	1
	4:DI	1.179	5.6E+3	0.000	2	-13.9E+3	0.000	1
	5:WLI#1	1.179	1.1E+3	0.000	2	-2.33E+3	0.000	1
	6:WLI#4	1.179	270.669	0.000	2	-706.337	0.000	1
	7:WLS#1	1.179	802.288	0.000	2	-1.74E+3	0.000	1
	8:WLS#4	1.179	200.528	0.000	2	-528.831	0.000	1
	9:WLM#1	1.179	229.840	0.000	2	-499.019	0.000	1
	10:WLM#4	1.179	57.462	0.000	2	-151.090	0.000	1
	11:LM	1.179	33.245	0.000	1	-19.171	0.000	2
	12:LV	1.179	27.478	0.000	2	-62.683	0.000	1
	13:1.2D+1.6WI	1.179	5.38E+3	0.000	2	-12.7E+3	0.000	1
	14:1.2D+1.6WI	1.179	2.64E+3	0.000	2	-7.15E+3	0.000	1
	15:1.2D-1.6WL	1.179	4.55E+3	1.179	1	-1.93E+3	0.000	2
	16:1.2D-1.6WL	1.179	1.22E+3	0.000	2	-2.33E+3	0.000	1
	17:1.2D+1.0DI	1.179	7.98E+3	0.000	2	-20.9E+3	0.000	1
	18:1.2D+1.0DI	1.179	7.72E+3	0.000	2	-19.3E+3	0.000	1
	19:1.2D+1.0DI	1.179	7.18E+3	0.000	2	-16.3E+3	0.000	1



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
30

Rev
1

Part

Job Title Rocky Hill CT

Ref

By DAP

Date 5/13/19

Chd BK

Client VZW

File Rocky Hill CT.std

Date/Time 13-May-2019 16:22

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	20:1.2D+1.0DI	1.179	7.34E+3	0.000	2	-17.9E+3	0.000	1
	21:1.0D+1.0WI	1.179	2.24E+3	0.000	2	-5.69E+3	0.000	1
	22:1.0D+1.0WI	1.179	1.77E+3	0.000	2	-4.48E+3	0.000	1
	23:1.0D-1.0WL	1.179	1.31E+3	0.000	2	-2.2E+3	0.000	1
	24:1.0D-1.0WL	1.179	1.45E+3	0.000	2	-3.42E+3	0.000	1
	25:1.4D	1.179	2.25E+3	0.000	2	-5.53E+3	0.000	1
	26:1.2D+1.5LV	1.179	1.99E+3	0.000	2	-5.18E+3	0.000	1
	27:1.2D+1.5LV	1.179	1.95E+3	0.000	2	-4.84E+3	0.000	1
	28:1.2D+1.5LV	1.179	1.82E+3	0.000	2	-4.19E+3	0.000	1
	29:1.2D+1.5LV	1.179	1.86E+3	0.000	2	-4.53E+3	0.000	1
	30:1.2D+1.5LV	1.179	1.97E+3	0.000	2	-4.83E+3	0.000	1
27	1:DEAD	1.179	696.497	1.179	2	-1.04E+3	1.179	1
	2:WL#1	1.179	1.55E+3	1.179	2	-3.29E+3	1.179	1
	3:WL#4	1.179	419.162	1.179	3	-1.01E+3	1.179	2
	4:DI	1.179	3.28E+3	1.179	2	-5.16E+3	1.179	1
	5:WLI#1	1.179	734.295	1.179	2	-1.54E+3	1.179	1
	6:WLI#4	1.179	196.595	1.179	3	-466.176	1.179	2
	7:WLS#1	1.179	544.086	1.179	2	-1.16E+3	1.179	1
	8:WLS#4	1.179	147.202	1.179	3	-353.998	1.179	2
	9:WLM#1	1.179	155.721	1.179	2	-331.026	1.179	1
	10:WLM#4	1.179	42.051	1.179	3	-100.954	1.179	2
	11:LM	1.179	24.548	1.179	1	-10.078	1.179	3
	12:LV	1.179	4.715	1.179	3	-10.419	1.179	1
	13:1.2D+1.6WI	1.179	3.31E+3	1.179	2	-6.51E+3	1.179	1
	14:1.2D+1.6WI	1.179	989.634	1.179	3	-985.892	1.179	1
	15:1.2D-1.6WL	1.179	4.02E+3	1.080	1	-1.69E+3	0.000	2
	16:1.2D-1.6WL	1.179	2.45E+3	1.179	2	-1.51E+3	1.179	1
	17:1.2D+1.0DI	1.179	4.85E+3	1.179	2	-7.95E+3	1.179	1
	18:1.2D+1.0DI	1.179	3.65E+3	1.179	2	-6.33E+3	1.179	1
	19:1.2D+1.0DI	1.179	3.38E+3	1.179	2	-4.87E+3	1.179	1
	20:1.2D+1.0DI	1.179	4.58E+3	1.179	2	-6.49E+3	1.179	1
	21:1.0D+1.0WI	1.179	1.24E+3	1.179	2	-2.2E+3	1.179	1
	22:1.0D+1.0WI	1.179	413.014	1.179	3	-983.315	1.179	1
	23:1.0D-1.0WL	1.179	577.400	0.000	1	-213.535	0.000	2
	24:1.0D-1.0WL	1.179	1.05E+3	1.179	2	-1.1E+3	1.179	1
	25:1.4D	1.179	975.096	1.179	2	-1.46E+3	1.179	1
	26:1.2D+1.5LV	1.179	980.116	1.179	2	-1.54E+3	1.179	1
	27:1.2D+1.5LV	1.179	723.441	1.179	2	-1.2E+3	1.179	1
	28:1.2D+1.5LV	1.179	668.674	1.179	2	-881.458	1.179	1
	29:1.2D+1.5LV	1.179	925.348	1.179	2	-1.23E+3	1.179	1
	30:1.2D+1.5LV	1.179	840.339	1.179	2	-1.26E+3	1.179	1
28	1:DEAD	1.179	1.65E+3	0.000	2	-4.04E+3	0.000	1
	2:WL#1	1.179	1.37E+3	1.179	1	-702.027	0.000	2
	3:WL#4	1.179	5.03E+3	0.000	1	-2.3E+3	0.000	2



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
31

Rev
1

Part

Job Title Rocky Hill CT

Ref

By DAP

Date 5/13/19

Chd BK

Client VZW

File Rocky Hill CT.std

Date/Time 13-May-2019 16:22

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	4:DI	1.179	6.17E+3	0.000	2	-15.3E+3	0.000	1
	5:WLI#1	1.179	623.420	1.179	1	-326.211	0.000	2
	6:WLI#4	1.179	2.32E+3	0.000	1	-1.07E+3	0.000	2
	7:WLS#1	1.179	482.715	1.179	1	-246.696	0.000	2
	8:WLS#4	1.179	1.77E+3	0.000	1	-808.569	0.000	2
	9:WLM#1	1.179	137.694	1.179	1	-70.268	0.000	2
	10:WLM#4	1.179	503.277	0.000	1	-230.465	0.000	2
	11:LM	1.179	54.954	0.000	2	-125.376	0.000	1
	12:LV	1.179	4.286	1.179	2	-9.295	0.000	1
	13:1.2D+1.6WI	1.179	2.04E+3	0.000	2	-2.93E+3	0.000	1
	14:1.2D+1.6WI	1.179	4.38E+3	1.179	1	-1.91E+3	0.000	2
	15:1.2D-1.6WL	1.179	2.9E+3	0.000	2	-6.77E+3	0.000	1
	16:1.2D-1.6WL	1.179	5.46E+3	0.000	2	-12.9E+3	0.000	1
	17:1.2D+1.0DI	1.179	8.18E+3	0.000	2	-19.6E+3	0.000	1
	18:1.2D+1.0DI	1.179	7.79E+3	0.000	2	-17.8E+3	0.000	1
	19:1.2D+1.0DI	1.179	8.13E+3	0.000	2	-20.6E+3	0.000	1
	20:1.2D+1.0DI	1.179	8.53E+3	0.000	2	-22.4E+3	0.000	1
	21:1.0D+1.0WI	1.179	1.67E+3	0.000	2	-3.62E+3	0.000	1
	22:1.0D+1.0WI	1.179	1.35E+3	0.000	2	-2.28E+3	0.000	1
	23:1.0D-1.0WL	1.179	1.73E+3	0.000	2	-4.46E+3	0.000	1
	24:1.0D-1.0WL	1.179	2.29E+3	0.000	2	-5.81E+3	0.000	1
	25:1.4D	1.179	2.31E+3	0.000	2	-5.66E+3	0.000	1
	26:1.2D+1.5LM	1.179	2.07E+3	0.000	2	-4.92E+3	0.000	1
	27:1.2D+1.5LM	1.179	1.98E+3	0.000	2	-4.54E+3	0.000	1
	28:1.2D+1.5LM	1.179	2.06E+3	0.000	2	-5.16E+3	0.000	1
	29:1.2D+1.5LM	1.179	2.15E+3	0.000	2	-5.54E+3	0.000	1
	30:1.2D+1.5LV	1.179	1.99E+3	0.000	2	-4.87E+3	0.000	1
29	1:DEAD	1.179	726.309	1.179	2	-1.09E+3	1.179	1
	2:WL#1	1.179	1.79E+3	1.179	1	-1.69E+3	1.179	2
	3:WL#4	1.179	2.7E+3	1.179	1	-1.13E+3	1.179	3
	4:DI	1.179	3.66E+3	1.179	2	-5.82E+3	1.179	1
	5:WLI#1	1.179	842.171	1.179	1	-780.415	1.179	2
	6:WLI#4	1.179	1.25E+3	1.179	1	-517.735	1.179	3
	7:WLS#1	1.179	630.097	1.179	1	-594.294	1.179	2
	8:WLS#4	1.179	947.378	1.179	1	-397.329	1.179	3
	9:WLM#1	1.179	180.501	1.179	1	-169.826	1.179	2
	10:WLM#4	1.179	270.124	1.179	1	-113.244	1.179	3
	11:LM	1.179	9.448	1.179	3	-20.869	1.179	1
	12:LV	1.179	12.208	1.179	2	-28.160	1.179	1
	13:1.2D+1.6WI	1.179	1.7E+3	0.098	1	-1.84E+3	1.179	2
	14:1.2D+1.6WI	1.179	3.16E+3	0.000	1	-1.48E+3	1.179	3
	15:1.2D-1.6WL	1.179	3.58E+3	1.179	2	-4.17E+3	1.179	1
	16:1.2D-1.6WL	1.179	2.25E+3	1.179	2	-5.62E+3	1.179	1
	17:1.2D+1.0DI	1.179	3.75E+3	1.179	2	-6.28E+3	1.179	1



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No 50103542	Sheet No 32	Rev 1
Part		
Ref		
By DAP	Date 5/13/19	Chd BK
File Rocky Hill CT.std	Date/Time 13-May-2019 16:22	

Job Title Rocky Hill CT

Client VZW

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	18:1.2D+1.0DI	1.179	4.13E+3	1.179	2	-5.88E+3	1.179	1
	19:1.2D+1.0DI	1.179	5.31E+3	1.179	2	-7.97E+3	1.179	1
	20:1.2D+1.0DI	1.179	4.93E+3	1.179	2	-8.37E+3	1.179	1
	21:1.0D+1.0WI	1.179	209.608	1.179	3	-457.061	1.179	1
	22:1.0D+1.0WI	1.179	424.548	1.179	2	-220.443	0.000	2
	23:1.0D-1.0WL	1.179	1.32E+3	1.179	2	-1.72E+3	1.179	1
	24:1.0D-1.0WL	1.179	1.03E+3	1.179	2	-2.03E+3	1.179	1
	25:1.4D	1.179	1.02E+3	1.179	2	-1.52E+3	1.179	1
	26:1.2D+1.5LV	1.179	710.737	1.179	2	-1.16E+3	1.179	1
	27:1.2D+1.5LV	1.179	794.746	1.179	2	-1.07E+3	1.179	1
	28:1.2D+1.5LV	1.179	1.05E+3	1.179	2	-1.52E+3	1.179	1
	29:1.2D+1.5LV	1.179	966.380	1.179	2	-1.61E+3	1.179	1
	30:1.2D+1.5LV	1.179	889.883	1.179	2	-1.35E+3	1.179	1
30	1:DEAD	1.179	1.62E+3	0.000	2	-3.97E+3	0.000	1
	2:WL#1	1.179	3.86E+3	0.000	1	-1.71E+3	0.000	2
	3:WL#4	1.179	1.67E+3	0.000	2	-3.44E+3	0.000	1
	4:DI	1.179	5.72E+3	0.000	2	-14.2E+3	0.000	1
	5:WLI#1	1.179	1.8E+3	0.000	1	-801.475	0.000	2
	6:WLI#4	1.179	795.757	0.000	2	-1.59E+3	0.000	1
	7:WLS#1	1.179	1.36E+3	0.000	1	-600.977	0.000	2
	8:WLS#4	1.179	586.130	0.000	2	-1.21E+3	0.000	1
	9:WLM#1	1.179	388.240	0.000	1	-172.022	0.000	2
	10:WLM#4	1.179	167.260	0.000	2	-343.936	0.000	1
	11:LM	1.179	8.577	1.179	2	-18.597	0.000	1
	12:LV	1.179	16.622	0.000	1	-9.588	0.000	2
	13:1.2D+1.6WI	1.179	2.58E+3	1.179	1	-992.815	0.000	2
	14:1.2D+1.6WI	1.179	4.42E+3	0.000	2	-10.3E+3	0.000	1
	15:1.2D-1.6WL	1.179	4.48E+3	0.000	2	-10.9E+3	0.000	1
	16:1.2D-1.6WL	1.179	2.55E+3	1.179	1	-925.741	0.000	2
	17:1.2D+1.0DI	1.179	7.34E+3	0.000	2	-17.2E+3	0.000	1
	18:1.2D+1.0DI	1.179	7.88E+3	0.000	2	-20.6E+3	0.000	1
	19:1.2D+1.0DI	1.179	7.97E+3	0.000	2	-20.8E+3	0.000	1
	20:1.2D+1.0DI	1.179	7.49E+3	0.000	2	-17.4E+3	0.000	1
	21:1.0D+1.0WI	1.179	1.38E+3	0.000	2	-2.62E+3	0.000	1
	22:1.0D+1.0WI	1.179	2.04E+3	0.000	2	-5.18E+3	0.000	1
	23:1.0D-1.0WL	1.179	2.05E+3	0.000	2	-5.33E+3	0.000	1
	24:1.0D-1.0WL	1.179	1.45E+3	0.000	2	-2.77E+3	0.000	1
	25:1.4D	1.179	2.27E+3	0.000	2	-5.56E+3	0.000	1
	26:1.2D+1.5LV	1.179	1.89E+3	0.000	2	-4.41E+3	0.000	1
	27:1.2D+1.5LV	1.179	2E+3	0.000	2	-5.14E+3	0.000	1
	28:1.2D+1.5LV	1.179	2.03E+3	0.000	2	-5.18E+3	0.000	1
	29:1.2D+1.5LV	1.179	1.91E+3	0.000	2	-4.45E+3	0.000	1
	30:1.2D+1.5LV	1.179	1.93E+3	0.000	2	-4.74E+3	0.000	1
43	1:DEAD	1.041	4.12E+3	1.041	3	-4.08E+3	1.041	1



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No 50103542	Sheet No 33	Rev 1
Part		
Ref		
By DAP	Date 5/13/19	Chd BK
File Rocky Hill CT.std	Date/Time 13-May-2019 16:22	

Job Title Rocky Hill CT

Client VZW

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	2:WL#1	1.041	3.79E+3	1.041	3	-4.14E+3	1.041	1
	3:WL#4	1.041	5.08E+3	1.041	4	-5.71E+3	1.041	2
	4:DI	1.041	15.9E+3	1.041	3	-15.7E+3	1.041	1
	5:WLI#1	1.041	1.87E+3	1.041	3	-2.04E+3	1.041	1
	6:WLI#4	1.041	2.31E+3	1.041	4	-2.62E+3	1.041	2
	7:WLS#1	1.041	1.33E+3	1.041	3	-1.45E+3	1.041	1
	8:WLS#4	1.041	1.78E+3	1.041	4	-2.01E+3	1.041	2
	9:WLM#1	1.041	381.658	1.041	3	-417.054	1.041	1
	10:WLM#4	1.041	507.236	1.041	4	-570.511	1.041	2
	11:LM	1.041	6.728	1.041	3	-6.826	1.041	1
	12:LV	1.041	3.370	1.041	4	-3.425	1.041	2
	13:1.2D+1.6WI	1.041	11E+3	1.041	3	-11.5E+3	1.041	1
	14:1.2D+1.6WI	1.041	13.1E+3	1.041	4	-14E+3	1.041	2
	15:1.2D-1.6WL	1.041	3.69E+3	1.041	4	-3.08E+3	1.041	2
	16:1.2D-1.6WL	1.041	4.28E+3	0.000	1	-3.24E+3	0.000	3
	17:1.2D+1.0DI	1.041	22.7E+3	1.041	3	-22.7E+3	1.041	1
	18:1.2D+1.0DI	1.041	23.2E+3	1.041	4	-23.3E+3	1.041	2
	19:1.2D+1.0DI	1.041	20.6E+3	1.041	4	-20.2E+3	1.041	2
	20:1.2D+1.0DI	1.041	19.5E+3	1.041	3	-19E+3	1.041	1
	21:1.0D+1.0WI	1.041	5.45E+3	1.041	3	-5.53E+3	1.041	1
	22:1.0D+1.0WI	1.041	5.9E+3	1.041	4	-6.09E+3	1.041	2
	23:1.0D-1.0WL	1.041	3.84E+3	1.041	4	-3.68E+3	1.041	2
	24:1.0D-1.0WL	1.041	3.08E+3	1.041	3	-2.82E+3	1.041	1
	25:1.4D	1.041	5.76E+3	1.041	3	-5.71E+3	1.041	1
	26:1.2D+1.5LV	1.041	5.33E+3	1.041	3	-5.32E+3	1.041	1
	27:1.2D+1.5LV	1.041	5.45E+3	1.041	3	-5.47E+3	1.041	1
	28:1.2D+1.5LV	1.041	4.87E+3	1.041	4	-4.79E+3	1.041	2
	29:1.2D+1.5LV	1.041	4.65E+3	1.041	3	-4.55E+3	1.041	1
	30:1.2D+1.5LV	1.041	4.95E+3	1.041	3	-4.9E+3	1.041	1
44	1:DEAD	2.000	2.34E+3	0.000	3	-2.28E+3	0.000	1
	2:WL#1	2.000	4.15E+3	0.000	1	-3.75E+3	0.000	3
	3:WL#4	2.000	292.491	0.000	2	-292.824	0.000	1
	4:DI	2.000	9.68E+3	0.000	3	-9.44E+3	0.000	1
	5:WLI#1	2.000	1.86E+3	0.000	1	-1.67E+3	0.000	3
	6:WLI#4	2.000	153.954	0.000	2	-153.791	0.000	1
	7:WLS#1	2.000	1.46E+3	0.000	1	-1.32E+3	0.000	3
	8:WLS#4	2.000	102.694	0.000	2	-102.811	0.000	1
	9:WLM#1	2.000	415.982	0.000	1	-376.089	0.000	3
	10:WLM#4	2.000	29.548	0.000	2	-29.581	0.000	1
	11:LM	2.000	38.310	0.000	1	-38.133	0.000	3
	12:LV	2.000	3.267	2.000	2	-3.113	2.000	4
	13:1.2D+1.6WI	2.000	3.94E+3	1.333	1	-3.25E+3	2.000	4
	14:1.2D+1.6WI	2.000	3.28E+3	0.000	3	-3.21E+3	0.000	1
	15:1.2D-1.6WL	2.000	8.82E+3	0.000	3	-9.38E+3	0.000	1



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
34

Rev
1

Job Title **Rocky Hill CT**

Part

Ref

By **DAP**

Date **5/13/19**

Chd **BK**

Client **VZW**

File **Rocky Hill CT.std**

Date/Time **13-May-2019 16:22**

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	16:1.2D-1.6WL	2.000	3.24E+3	0.000	3	-3.16E+3	0.000	1
	17:1.2D+1.0DI	2.000	10.8E+3	0.000	3	-10.3E+3	0.000	1
	18:1.2D+1.0DI	2.000	12.6E+3	0.000	3	-12.3E+3	0.000	1
	19:1.2D+1.0DI	2.000	14.2E+3	0.000	3	-14E+3	0.000	1
	20:1.2D+1.0DI	2.000	12.6E+3	0.000	3	-12.3E+3	0.000	1
	21:1.0D+1.0WI	2.000	1.04E+3	0.000	3	-839.411	0.000	1
	22:1.0D+1.0WI	2.000	2.45E+3	0.000	3	-2.39E+3	0.000	1
	23:1.0D-1.0WL	2.000	3.66E+3	0.000	3	-3.74E+3	0.000	1
	24:1.0D-1.0WL	2.000	2.43E+3	0.000	3	-2.37E+3	0.000	1
	25:1.4D	2.000	3.28E+3	0.000	3	-3.2E+3	0.000	1
	26:1.2D+1.5LV	2.000	2.38E+3	0.000	3	-2.27E+3	0.000	1
	27:1.2D+1.5LV	2.000	2.78E+3	0.000	3	-2.71E+3	0.000	1
	28:1.2D+1.5LV	2.000	3.13E+3	0.000	3	-3.1E+3	0.000	1
	29:1.2D+1.5LV	2.000	2.78E+3	0.000	3	-2.71E+3	0.000	1
	30:1.2D+1.5LV	2.000	2.81E+3	0.000	3	-2.74E+3	0.000	1
45	1:DEAD	2.000	2.34E+3	0.000	3	-2.28E+3	0.000	1
	2:WL#1	2.000	2.1E+3	0.000	3	-2.29E+3	0.000	1
	3:WL#4	2.000	3.72E+3	0.000	1	-3.38E+3	0.000	3
	4:DI	2.000	9.92E+3	0.000	3	-9.69E+3	0.000	1
	5:WLI#1	2.000	985.317	0.000	3	-1.07E+3	0.000	1
	6:WLI#4	2.000	1.7E+3	0.000	1	-1.54E+3	0.000	3
	7:WLS#1	2.000	738.339	0.000	3	-802.630	0.000	1
	8:WLS#4	2.000	1.31E+3	0.000	1	-1.19E+3	0.000	3
	9:WLM#1	2.000	211.362	0.000	3	-229.734	0.000	1
	10:WLM#4	2.000	372.062	0.000	1	-338.042	0.000	3
	11:LM	2.000	6.534	2.000	1	-6.222	2.000	3
	12:LV	2.000	19.156	0.000	1	-19.069	0.000	3
	13:1.2D+1.6WI	2.000	6.17E+3	0.000	3	-6.39E+3	0.000	1
	14:1.2D+1.6WI	2.000	3.57E+3	2.000	2	-2.97E+3	2.000	4
	15:1.2D-1.6WL	2.000	2.12E+3	2.000	1	-1.76E+3	2.000	3
	16:1.2D-1.6WL	2.000	8.22E+3	0.000	3	-8.69E+3	0.000	1
	17:1.2D+1.0DI	2.000	13.7E+3	0.000	3	-13.5E+3	0.000	1
	18:1.2D+1.0DI	2.000	11.3E+3	0.000	3	-10.9E+3	0.000	1
	19:1.2D+1.0DI	2.000	12E+3	0.000	3	-11.6E+3	0.000	1
	20:1.2D+1.0DI	2.000	14.2E+3	0.000	3	-14.1E+3	0.000	1
	21:1.0D+1.0WI	2.000	3.08E+3	0.000	3	-3.08E+3	0.000	1
	22:1.0D+1.0WI	2.000	1.27E+3	0.000	3	-1.09E+3	0.000	1
	23:1.0D-1.0WL	2.000	1.8E+3	0.000	3	-1.68E+3	0.000	1
	24:1.0D-1.0WL	2.000	3.53E+3	0.000	3	-3.59E+3	0.000	1
	25:1.4D	2.000	3.28E+3	0.000	3	-3.19E+3	0.000	1
	26:1.2D+1.5LV	2.000	3.03E+3	0.000	3	-2.97E+3	0.000	1
	27:1.2D+1.5LV	2.000	2.51E+3	0.000	3	-2.4E+3	0.000	1
	28:1.2D+1.5LV	2.000	2.65E+3	0.000	3	-2.56E+3	0.000	1
	29:1.2D+1.5LV	2.000	3.14E+3	0.000	3	-3.1E+3	0.000	1



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
35

Rev
1

Part

Job Title Rocky Hill CT

Ref

By DAP

Date 5/13/19

Chd BK

Client VZW

File Rocky Hill CT.std

Date/Time 13-May-2019 16:22

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
48	30:1.2D+1.5LV	2.000	2.78E+3	0.000	3	-2.71E+3	0.000	1
	1:DEAD	1.500	1.55E+3	0.000		-1.2E+3	0.000	
	2:WL#1	1.500	14.2E+3	0.000		-14.1E+3	0.000	
	3:WL#4	1.500	16.5E+3	0.000		-16.3E+3	0.000	
	4:DI	1.500	6.57E+3	0.000		-5.09E+3	0.000	
	5:WLI#1	1.500	6.76E+3	0.000		-6.71E+3	0.000	
	6:WLI#4	1.500	7.42E+3	0.000		-7.34E+3	0.000	
	7:WLS#1	1.500	4.99E+3	0.000		-4.95E+3	0.000	
	8:WLS#4	1.500	5.8E+3	0.000		-5.74E+3	0.000	
	9:WLM#1	1.500	1.43E+3	0.000		-1.42E+3	0.000	
	10:WLM#4	1.500	1.65E+3	0.000		-1.63E+3	0.000	
	11:LM	1.500	71.805	0.000		-71.159	0.000	
	12:LV	1.500	35.904	0.000		-35.581	0.000	
	13:1.2D+1.6WI	1.500	22.1E+3	0.000		-21.5E+3	0.000	
	14:1.2D+1.6WI	1.500	25.1E+3	0.000		-24.4E+3	0.000	
	15:1.2D-1.6WL	1.500	23.7E+3	0.000		-23.5E+3	0.000	
	16:1.2D-1.6WL	1.500	27.9E+3	0.000		-27.7E+3	0.000	
	17:1.2D+1.0DI	1.500	7.8E+3	0.000		-5.86E+3	0.000	
	18:1.2D+1.0DI	1.500	4.24E+3	0.000		-2.28E+3	0.000	
	19:1.2D+1.0DI	1.500	13.4E+3	0.000		-11.6E+3	0.000	
	20:1.2D+1.0DI	1.500	15.4E+3	0.000		-13.6E+3	0.000	
	21:1.0D+1.0WI	1.500	4.55E+3	0.000		-4.17E+3	0.000	
	22:1.0D+1.0WI	1.500	4.76E+3	0.000		-4.36E+3	0.000	
	23:1.0D-1.0WL	1.500	6E+3	0.000		-5.69E+3	0.000	
	24:1.0D-1.0WL	1.500	7.19E+3	0.000		-6.9E+3	0.000	
	25:1.4D	1.500	2.17E+3	0.000		-1.68E+3	0.000	
	26:1.2D+1.5LM	1.500	1.65E+3	0.000		-1.22E+3	0.000	
	27:1.2D+1.5LM	1.500	1.03E+3	0.000		-598.992	0.000	
	28:1.2D+1.5LM	1.500	3.01E+3	0.000		-2.6E+3	0.000	
	29:1.2D+1.5LM	1.500	3.45E+3	0.000		-3.05E+3	0.000	
	30:1.2D+1.5LV	1.500	1.89E+3	0.000		-1.47E+3	0.000	
51	1:DEAD	1.500	1.53E+3	0.000		-1.18E+3	0.000	
	2:WL#1	1.500	14.7E+3	0.000		-14.6E+3	0.000	
	3:WL#4	1.500	16.7E+3	0.000		-16.9E+3	0.000	
	4:DI	1.500	6.19E+3	0.000		-4.65E+3	0.000	
	5:WLI#1	1.500	6.85E+3	0.000		-6.8E+3	0.000	
	6:WLI#4	1.500	7.46E+3	0.000		-7.54E+3	0.000	
	7:WLS#1	1.500	5.18E+3	0.000		-5.14E+3	0.000	
	8:WLS#4	1.500	5.87E+3	0.000		-5.93E+3	0.000	
	9:WLM#1	1.500	1.48E+3	0.000		-1.47E+3	0.000	
	10:WLM#4	1.500	1.67E+3	0.000		-1.68E+3	0.000	
	11:LM	1.500	71.806	0.000		-71.159	0.000	
	12:LV	1.500	52.140	0.000		-53.360	0.000	
	13:1.2D+1.6WI	1.500	22.9E+3	0.000		-22.3E+3	0.000	



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
36

Rev
1

Job Title **Rocky Hill CT**

Part

Ref

By **DAP**

Date **5/13/19**

Chd **BK**

Client **VZW**

File **Rocky Hill CT.std**

Date/Time **13-May-2019 16:22**

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	14:1.2D+1.6WI	1.500	28.4E+3	0.000		-28.3E+3	0.000	
	15:1.2D-1.6WL	1.500	24.6E+3	0.000		-24.3E+3	0.000	
	16:1.2D-1.6WL	1.500	25.8E+3	0.000		-25.1E+3	0.000	
	17:1.2D+1.0DI	1.500	7.19E+3	0.000		-5.18E+3	0.000	
	18:1.2D+1.0DI	1.500	15E+3	0.000		-13.1E+3	0.000	
	19:1.2D+1.0DI	1.500	13.4E+3	0.000		-11.5E+3	0.000	
	20:1.2D+1.0DI	1.500	4.74E+3	0.000		-2.71E+3	0.000	
	21:1.0D+1.0WI	1.500	4.72E+3	0.000		-4.34E+3	0.000	
	22:1.0D+1.0WI	1.500	7.29E+3	0.000		-6.99E+3	0.000	
	23:1.0D-1.0WL	1.500	6.19E+3	0.000		-5.87E+3	0.000	
	24:1.0D-1.0WL	1.500	4.93E+3	0.000		-4.52E+3	0.000	
	25:1.4D	1.500	2.14E+3	0.000		-1.65E+3	0.000	
	26:1.2D+1.5LV	1.500	1.63E+3	0.000		-1.19E+3	0.000	
	27:1.2D+1.5LV	1.500	3.46E+3	0.000		-3.05E+3	0.000	
	28:1.2D+1.5LV	1.500	3.05E+3	0.000		-2.63E+3	0.000	
	29:1.2D+1.5LV	1.500	1.07E+3	0.000		-630.044	0.000	
	30:1.2D+1.5LV	1.500	1.91E+3	0.000		-1.49E+3	0.000	
54	1:DEAD	1.500	1.53E+3	0.000		-1.18E+3	0.000	
	2:WL#1	1.500	17.4E+3	0.000		-17.6E+3	0.000	
	3:WL#4	1.500	13.7E+3	0.000		-13.7E+3	0.000	
	4:DI	1.500	6.16E+3	0.000		-4.7E+3	0.000	
	5:WLI#1	1.500	7.38E+3	0.000		-7.47E+3	0.000	
	6:WLI#4	1.500	6.4E+3	0.000		-6.4E+3	0.000	
	7:WLS#1	1.500	6.11E+3	0.000		-6.18E+3	0.000	
	8:WLS#4	1.500	4.81E+3	0.000		-4.81E+3	0.000	
	9:WLM#1	1.500	1.73E+3	0.000		-1.75E+3	0.000	
	10:WLM#4	1.500	1.37E+3	0.000		-1.37E+3	0.000	
	11:LM	1.500	104.277	0.000		-106.717	0.000	
	12:LV	1.500	35.902	0.000		-35.579	0.000	
	13:1.2D+1.6WI	1.500	29.6E+3	0.000		-29.5E+3	0.000	
	14:1.2D+1.6WI	1.500	22.1E+3	0.000		-21.7E+3	0.000	
	15:1.2D-1.6WL	1.500	26.7E+3	0.000		-26E+3	0.000	
	16:1.2D-1.6WL	1.500	22.2E+3	0.000		-21.8E+3	0.000	
	17:1.2D+1.0DI	1.500	15.3E+3	0.000		-13.5E+3	0.000	
	18:1.2D+1.0DI	1.500	9.82E+3	0.000		-7.93E+3	0.000	
	19:1.2D+1.0DI	1.500	1.95E+3	0.000				
	20:1.2D+1.0DI	1.500	11.1E+3	0.000		-9.17E+3	0.000	
	21:1.0D+1.0WI	1.500	7.64E+3	0.000		-7.35E+3	0.000	
	22:1.0D+1.0WI	1.500	5.13E+3	0.000		-4.78E+3	0.000	
	23:1.0D-1.0WL	1.500	5E+3	0.000		-4.58E+3	0.000	
	24:1.0D-1.0WL	1.500	5.21E+3	0.000		-4.86E+3	0.000	
	25:1.4D	1.500	2.14E+3	0.000		-1.65E+3	0.000	
	26:1.2D+1.5LV	1.500	3.72E+3	0.000		-3.32E+3	0.000	
	27:1.2D+1.5LV	1.500	2.42E+3	0.000		-2.01E+3	0.000	



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
37

Rev
1

Job Title Rocky Hill CT

Part

Ref

By DAP

Date 5/13/19

Chd BK

Client VZW

File Rocky Hill CT.std

Date/Time 13-May-2019 16:22

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	28:1.2D+1.5LM	1.500	344.203	1.500				
	29:1.2D+1.5LM	1.500	2.49E+3	0.000		-2.07E+3	0.000	
	30:1.2D+1.5LV	1.500	1.86E+3	0.000		-1.44E+3	0.000	
55	1:DEAD	1.889	1.89E+3	0.000	2	-761.121	0.000	1
	2:WL#1	1.889	6.25E+3	0.000	2	-2.38E+3	0.000	1
	3:WL#4	1.889	2.25E+3	0.000	2	-820.477	0.000	1
	4:DI	1.889	7.91E+3	0.000	2	-3.21E+3	0.000	1
	5:WLI#1	1.889	2.96E+3	0.000	2	-1.11E+3	0.000	1
	6:WLI#4	1.889	1.03E+3	0.000	2	-395.980	0.000	1
	7:WLS#1	1.889	2.19E+3	0.000	2	-836.197	0.000	1
	8:WLS#4	1.889	791.986	0.000	2	-288.338	0.000	1
	9:WLM#1	1.889	629.597	0.000	2	-239.685	0.000	1
	10:WLM#4	1.889	225.605	0.000	2	-81.489	0.000	1
	11:LM	1.889	10.519	0.000	2	-12.121	1.889	2
	12:LV	1.889	5.341	1.889	2	-2.073	1.889	1
	13:1.2D+1.6WI	1.889	12.3E+3	0.000	2	-4.72E+3	0.000	1
	14:1.2D+1.6WI	1.889	5.88E+3	0.000	2	-2.23E+3	0.000	1
	15:1.2D-1.6WL	1.889	2.9E+3	0.000	1	-7.73E+3	0.000	2
	16:1.2D-1.6WL	1.889	1.05E+3	1.889	2	-1.33E+3	0.000	2
	17:1.2D+1.0DI	1.889	13.1E+3	0.000	2	-5.23E+3	0.000	1
	18:1.2D+1.0DI	1.889	11.2E+3	0.000	2	-4.46E+3	0.000	1
	19:1.2D+1.0DI	1.889	7.23E+3	0.000	2	-3.02E+3	0.000	1
	20:1.2D+1.0DI	1.889	9.16E+3	0.000	2	-3.78E+3	0.000	1
	21:1.0D+1.0WI	1.889	4.09E+3	0.000	2	-1.6E+3	0.000	1
	22:1.0D+1.0WI	1.889	2.69E+3	0.000	2	-1.05E+3	0.000	1
	23:1.0D-1.0WL	1.889	257.219	1.889	1	-675.380	1.889	2
	24:1.0D-1.0WL	1.889	1.1E+3	0.000	2	-472.782	0.000	1
	25:1.4D	1.889	2.65E+3	0.000	2	-1.07E+3	0.000	1
	26:1.2D+1.5LM	1.889	2.92E+3	0.000	2	-1.16E+3	0.000	1
	27:1.2D+1.5LM	1.889	2.51E+3	0.000	2	-1E+3	0.000	1
	28:1.2D+1.5LM	1.889	1.66E+3	0.000	2	-680.624	0.000	1
	29:1.2D+1.5LM	1.889	2.06E+3	0.000	2	-838.820	0.000	1
	30:1.2D+1.5LV	1.889	2.28E+3	0.000	2	-915.009	0.000	1
56	1:DEAD	1.333	576.151	0.000	1	-1.03E+3	0.000	2
	2:WL#1	1.333	716.434	0.000	2	-293.022	0.000	1
	3:WL#4	1.333	777.860	0.000	2	-861.595	0.000	1
	4:DI	1.333	2.43E+3	0.000	1	-4.41E+3	0.000	2
	5:WLI#1	1.333	337.765	0.000	2	-142.677	0.000	1
	6:WLI#4	1.333	331.932	0.000	2	-388.543	0.000	1
	7:WLS#1	1.333	251.476	0.000	2	-102.900	0.000	1
	8:WLS#4	1.333	273.271	0.000	2	-302.615	0.000	1
	9:WLM#1	1.333	72.338	0.000	2	-29.502	0.000	1
	10:WLM#4	1.333	77.076	0.000	2	-86.023	0.000	1
	11:LM	1.333	4.204	0.000	1	-7.782	0.000	2



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
38

Rev
1

Job Title **Rocky Hill CT**

Part

Ref

By **DAP**

Date **5/13/19**

Chd **BK**

Client **VZW**

File **Rocky Hill CT.std**

Date/Time **13-May-2019 16:22**

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	12:LV	1.333	8.132	1.333	1	-19.790	1.333	2
	13:1.2D+1.6WI	1.333	583.509	1.333	1	-1.18E+3	1.333	2
	14:1.2D+1.6WI	1.333	719.439	0.000	2	-1.2E+3	0.000	1
	15:1.2D-1.6WL	1.333	978.615	0.000	1	-2.38E+3	0.000	2
	16:1.2D-1.6WL	1.333	1.56E+3	0.000	1	-2.48E+3	0.000	2
	17:1.2D+1.0DI	1.333	3.04E+3	0.000	1	-5.31E+3	0.000	2
	18:1.2D+1.0DI	1.333	3.15E+3	0.000	1	-5.32E+3	0.000	2
	19:1.2D+1.0DI	1.333	3.21E+3	0.000	1	-5.99E+3	0.000	2
	20:1.2D+1.0DI	1.333	3.1E+3	0.000	1	-5.98E+3	0.000	2
	21:1.0D+1.0WI	1.333	513.205	0.000	1	-844.532	1.333	2
	22:1.0D+1.0WI	1.333	582.249	0.000	3	-758.884	0.000	1
	23:1.0D-1.0WL	1.333	639.097	0.000	1	-1.28E+3	0.000	2
	24:1.0D-1.0WL	1.333	570.053	0.000	1	-1.31E+3	0.000	2
	25:1.4D	1.333	806.612	0.000	1	-1.45E+3	0.000	2
	26:1.2D+1.5LM	1.333	679.459	0.000	1	-1.18E+3	0.000	2
	27:1.2D+1.5LM	1.333	699.887	0.000	1	-1.17E+3	0.000	2
	28:1.2D+1.5LM	1.333	715.916	0.000	1	-1.32E+3	0.000	2
	29:1.2D+1.5LM	1.333	695.488	0.000	1	-1.33E+3	0.000	2
	30:1.2D+1.5LV	1.333	700.238	0.000	1	-1.26E+3	0.000	2
57	1:DEAD	1.889	1.98E+3	0.000	2	-796.996	0.000	1
	2:WL#1	1.889	811.508	1.889	1	-1.92E+3	1.889	2
	3:WL#4	1.889	2.49E+3	0.000	1	-6.56E+3	0.000	2
	4:DI	1.889	9.44E+3	0.000	2	-3.83E+3	0.000	1
	5:WLI#1	1.889	392.181	1.889	1	-894.086	1.889	2
	6:WLI#4	1.889	1.1E+3	0.000	1	-3E+3	0.000	2
	7:WLS#1	1.889	284.928	1.889	1	-674.740	1.889	2
	8:WLS#4	1.889	873.218	0.000	1	-2.3E+3	0.000	2
	9:WLM#1	1.889	81.889	1.889	1	-193.370	1.889	2
	10:WLM#4	1.889	248.158	0.000	1	-655.723	0.000	2
	11:LM	1.889	10.682	1.889	2	-4.147	1.889	1
	12:LV	1.889	13.524	0.000	1	-34.712	0.000	2
	13:1.2D+1.6WI	1.889	1.17E+3	1.889	1	-2.49E+3	1.889	2
	14:1.2D+1.6WI	1.889	3.02E+3	0.000	1	-8.11E+3	0.000	2
	15:1.2D-1.6WL	1.889	4.33E+3	0.000	2	-1.71E+3	0.000	1
	16:1.2D-1.6WL	1.889	12.9E+3	0.000	2	-4.93E+3	0.000	1
	17:1.2D+1.0DI	1.889	11.2E+3	0.000	2	-4.54E+3	0.000	1
	18:1.2D+1.0DI	1.889	8.82E+3	0.000	2	-3.69E+3	0.000	1
	19:1.2D+1.0DI	1.889	12.4E+3	0.000	2	-5.02E+3	0.000	1
	20:1.2D+1.0DI	1.889	14.8E+3	0.000	2	-5.88E+3	0.000	1
	21:1.0D+1.0WI	1.889	1.56E+3	0.000	2	-632.173	0.000	1
	22:1.0D+1.0WI	1.889	136.889	1.889	1	-440.395	1.889	2
	23:1.0D-1.0WL	1.889	2.41E+3	0.000	2	-961.818	0.000	1
	24:1.0D-1.0WL	1.889	4.29E+3	0.000	2	-1.67E+3	0.000	1
	25:1.4D	1.889	2.78E+3	0.000	2	-1.12E+3	0.000	1



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
39

Rev
1

Job Title Rocky Hill CT

Part

Ref

By DAP

Date 5/13/19

Chd BK

Client VZW

File Rocky Hill CT.std

Date/Time 13-May-2019 16:22

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	26:1.2D+1.5LM	1.889	2.26E+3	0.000	2	-911.896	0.000	1
	27:1.2D+1.5LM	1.889	1.73E+3	0.000	2	-711.565	0.000	1
	28:1.2D+1.5LM	1.889	2.51E+3	0.000	2	-1.01E+3	0.000	1
	29:1.2D+1.5LM	1.889	3.04E+3	0.000	2	-1.21E+3	0.000	1
	30:1.2D+1.5LV	1.889	2.33E+3	0.000	2	-936.110	0.000	1
58	1:DEAD	1.333	557.769	0.000	1	-1.02E+3	0.000	2
	2:WL#1	1.333	453.685	0.000	2	-646.695	0.000	1
	3:WL#4	1.333	674.144	0.000	1	-1.02E+3	0.000	2
	4:DI	1.333	2.04E+3	0.000	1	-4.46E+3	1.333	2
	5:WLI#1	1.333	125.473	0.000	2	-270.081	0.000	1
	6:WLI#4	1.333	308.077	0.000	1	-437.341	0.000	2
	7:WLS#1	1.333	160.042	0.000	2	-227.360	0.000	1
	8:WLS#4	1.333	236.825	0.000	1	-359.136	0.000	2
	9:WLM#1	1.333	43.666	0.000	2	-64.446	0.000	1
	10:WLM#4	1.333	67.466	0.000	1	-101.869	0.000	2
	11:LM	1.333	16.313	1.333	1	-39.508	1.333	2
	12:LV	1.333	8.650	1.333	3	-20.565	1.333	2
	13:1.2D+1.6WI	1.333	797.231	0.000	3	-859.455	0.000	1
	14:1.2D+1.6WI	1.333	1.25E+3	0.000	1	-2.86E+3	0.000	2
	15:1.2D-1.6WL	1.333	1.21E+3	0.000	1	-1.95E+3	0.000	2
	16:1.2D-1.6WL	1.333	615.892	1.333	1	-1.21E+3	1.333	2
	17:1.2D+1.0DI	1.333	2.79E+3	0.000	1	-5.36E+3	1.333	2
	18:1.2D+1.0DI	1.333	2.79E+3	0.000	1	-5.4E+3	1.333	2
	19:1.2D+1.0DI	1.333	2.63E+3	0.000	1	-5.54E+3	1.333	2
	20:1.2D+1.0DI	1.333	2.64E+3	0.000	1	-5.5E+3	1.333	2
	21:1.0D+1.0WI	1.333	585.500	0.000	3	-861.083	0.000	1
	22:1.0D+1.0WI	1.333	630.105	0.000	1	-1.38E+3	0.000	2
	23:1.0D-1.0WL	1.333	530.037	0.000	1	-1.18E+3	0.000	2
	24:1.0D-1.0WL	1.333	485.433	0.000	3	-868.747	1.333	2
	25:1.4D	1.333	780.876	0.000	1	-1.43E+3	0.000	2
	26:1.2D+1.5LM	1.333	696.271	0.000	1	-1.22E+3	0.000	2
	27:1.2D+1.5LM	1.333	707.574	0.000	1	-1.37E+3	0.000	2
	28:1.2D+1.5LM	1.333	678.253	0.000	1	-1.31E+3	0.000	2
	29:1.2D+1.5LM	1.333	666.950	0.000	1	-1.16E+3	0.000	2
	30:1.2D+1.5LV	1.333	674.548	0.000	1	-1.24E+3	0.000	2
59	1:DEAD	1.889	1.99E+3	0.000	2	-800.995	0.000	1
	2:WL#1	1.889	2.02E+3	0.000	1	-5.38E+3	0.000	2
	3:WL#4	1.889	4.08E+3	0.000	2	-1.55E+3	0.000	1
	4:DI	1.889	9.32E+3	0.000	2	-3.79E+3	0.000	1
	5:WLI#1	1.889	872.550	0.000	1	-2.44E+3	0.000	2
	6:WLI#4	1.889	1.93E+3	0.000	2	-734.241	0.000	1
	7:WLS#1	1.889	710.310	0.000	1	-1.89E+3	0.000	2
	8:WLS#4	1.889	1.43E+3	0.000	2	-544.335	0.000	1
	9:WLM#1	1.889	202.138	0.000	1	-539.309	0.000	2



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
40

Rev
1

Part

Job Title Rocky Hill CT

Ref

By DAP

Date 5/13/19

Chd BK

Client VZW

File Rocky Hill CT.std

Date/Time 13-May-2019 16:22

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	10:WLM#4	1.889	409.230	0.000	2	-155.729	0.000	1
	11:LM	1.889	27.045	0.000	1	-69.427	0.000	2
	12:LV	1.889	5.259	0.000	2	-6.061	1.889	2
	13:1.2D+1.6WI	1.889	2.27E+3	0.000	1	-6.21E+3	0.000	2
	14:1.2D+1.6WI	1.889	8.91E+3	0.000	2	-3.44E+3	0.000	1
	15:1.2D-1.6WL	1.889	11E+3	0.000	2	-4.2E+3	0.000	1
	16:1.2D-1.6WL	1.889	1.52E+3	0.000	1	-4.13E+3	0.000	2
	17:1.2D+1.0DI	1.889	9.27E+3	0.000	2	-3.88E+3	0.000	1
	18:1.2D+1.0DI	1.889	13.6E+3	0.000	2	-5.48E+3	0.000	1
	19:1.2D+1.0DI	1.889	14.2E+3	0.000	2	-5.62E+3	0.000	1
	20:1.2D+1.0DI	1.889	9.78E+3	0.000	2	-4.02E+3	0.000	1
	21:1.0D+1.0WI	1.889	104.001	0.157	2	-90.685	0.000	1
	22:1.0D+1.0WI	1.889	3.42E+3	0.000	2	-1.35E+3	0.000	1
	23:1.0D-1.0WL	1.889	3.88E+3	0.000	2	-1.51E+3	0.000	1
	24:1.0D-1.0WL	1.889	560.244	0.000	2	-524.781	1.889	2
	25:1.4D	1.889	2.79E+3	0.000	2	-1.12E+3	0.000	1
	26:1.2D+1.5LM	1.889	1.75E+3	0.000	2	-718.489	0.000	1
	27:1.2D+1.5LM	1.889	2.69E+3	0.000	2	-1.08E+3	0.000	1
	28:1.2D+1.5LM	1.889	2.82E+3	0.000	2	-1.12E+3	0.000	1
	29:1.2D+1.5LM	1.889	1.88E+3	0.000	2	-764.897	0.000	1
	30:1.2D+1.5LV	1.889	2.4E+3	0.000	2	-964.676	0.000	1
60	1:DEAD	1.333	556.341	0.000	1	-986.576	0.000	2
	2:WL#1	1.333	874.827	0.000	1	-972.646	0.000	2
	3:WL#4	1.333	239.665	1.333	3	-207.412	1.333	2
	4:DI	1.333	1.94E+3	0.000	1	-4.14E+3	1.333	2
	5:WLI#1	1.333	399.385	0.000	1	-417.120	0.000	2
	6:WLI#4	1.333	112.836	1.333	3	-90.245	1.333	2
	7:WLS#1	1.333	307.430	0.000	1	-342.086	0.000	2
	8:WLS#4	1.333	84.175	1.333	3	-72.926	1.333	2
	9:WLM#1	1.333	87.769	0.000	1	-96.876	0.000	2
	10:WLM#4	1.333	24.044	1.333	3	-20.599	1.333	2
	11:LM	1.333	17.340	1.333	3	-41.152	1.333	2
	12:LV	1.333	2.102	0.000	1	-3.892	0.000	2
	13:1.2D+1.6WI	1.333	1.56E+3	0.000	1	-2.74E+3	0.000	2
	14:1.2D+1.6WI	1.333	704.687	1.333	3	-1.29E+3	1.333	2
	15:1.2D-1.6WL	1.333	633.652	1.333	1	-1.24E+3	0.000	1
	16:1.2D-1.6WL	1.333	811.756	0.000	3	-1.35E+3	0.000	1
	17:1.2D+1.0DI	1.333	2.61E+3	0.000	1	-5.12E+3	1.333	2
	18:1.2D+1.0DI	1.333	2.55E+3	0.000	1	-5.18E+3	1.333	2
	19:1.2D+1.0DI	1.333	2.61E+3	0.000	1	-5.06E+3	1.333	2
	20:1.2D+1.0DI	1.333	2.67E+3	0.000	1	-5E+3	1.333	2
	21:1.0D+1.0WI	1.333	573.881	0.000	1	-1.33E+3	0.000	2
	22:1.0D+1.0WI	1.333	524.944	0.000	1	-949.965	0.000	2
	23:1.0D-1.0WL	1.333	538.802	0.000	3	-786.611	1.333	2



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
41

Rev
1

Part

Job Title Rocky Hill CT

Ref

By DAP

Date 5/13/19

Chd BK

Client VZW

File Rocky Hill CT.std

Date/Time 13-May-2019 16:22

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	24:1.0D-1.0WL	1.333	587.739	0.000	1	-1.02E+3	0.000	2
	25:1.4D	1.333	778.878	0.000	1	-1.38E+3	0.000	2
	26:1.2D+1.5LM	1.333	682.521	0.000	1	-1.31E+3	0.000	2
	27:1.2D+1.5LM	1.333	668.611	0.000	1	-1.21E+3	0.000	2
	28:1.2D+1.5LM	1.333	673.617	0.000	1	-1.12E+3	0.000	2
	29:1.2D+1.5LM	1.333	687.527	0.000	1	-1.23E+3	0.000	2
	30:1.2D+1.5LV	1.333	670.763	0.000	1	-1.19E+3	0.000	2
101	1:DEAD	0.500	1.665	0.000		-0.000	0.500	
	2:WL#1	0.500	13.096	0.000		-13.096	0.000	
	3:WL#4	0.500	13.096	0.000		-13.096	0.000	
	4:DI	0.500	6.471	0.000		-0.000	0.500	
	5:WLI#1	0.500	9.679	0.000		-9.679	0.000	
	6:WLI#4	0.500	9.679	0.000		-9.679	0.000	
	7:WLS#1	0.500	4.555	0.000		-4.555	0.000	
	8:WLS#4	0.500	4.555	0.000		-4.555	0.000	
	9:WLM#1	0.500	1.423	0.000		-1.423	0.000	
	10:WLM#4	0.500	1.423	0.000		-1.423	0.000	
	11:LM	0.500				-0.000	0.000	
	12:LV	0.500	0.000	0.000				
	13:1.2D+1.6WI	0.500	22.951	0.000		-18.955	0.000	
	14:1.2D+1.6WI	0.500	22.951	0.000		-18.955	0.000	
	15:1.2D-1.6WL	0.500	22.951	0.000		-18.955	0.000	
	16:1.2D-1.6WL	0.500	22.951	0.000		-18.955	0.000	
	17:1.2D+1.0DI	0.500	18.148	0.000		-1.211	0.000	
	18:1.2D+1.0DI	0.500	18.148	0.000		-1.211	0.000	
	19:1.2D+1.0DI	0.500	18.148	0.000		-1.211	0.000	
	20:1.2D+1.0DI	0.500	18.148	0.000		-1.211	0.000	
	21:1.0D+1.0WI	0.500	6.220	0.000		-2.890	0.000	
	22:1.0D+1.0WI	0.500	6.220	0.000		-2.890	0.000	
	23:1.0D-1.0WL	0.500	6.220	0.000		-2.890	0.000	
	24:1.0D-1.0WL	0.500	6.220	0.000		-2.890	0.000	
	25:1.4D	0.500	2.331	0.000		-0.000	0.500	
	26:1.2D+1.5LM	0.500	3.421	0.000		-0.000	0.500	
	27:1.2D+1.5LM	0.500	3.421	0.000		-0.000	0.500	
	28:1.2D+1.5LM	0.500	3.421	0.000		-0.000	0.500	
	29:1.2D+1.5LM	0.500	3.421	0.000		-0.000	0.500	
	30:1.2D+1.5LV	0.500	1.998	0.000		-0.000	0.500	
102	1:DEAD	0.500	1.665	0.000				
	2:WL#1	0.500	13.096	0.000		-13.096	0.000	
	3:WL#4	0.500	13.096	0.000		-13.096	0.000	
	4:DI	0.500	6.471	0.000		-0.000	0.500	
	5:WLI#1	0.500	9.679	0.000		-9.679	0.000	
	6:WLI#4	0.500	9.679	0.000		-9.679	0.000	
	7:WLS#1	0.500	4.555	0.000		-4.555	0.000	



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
42

Rev
1

Job Title Rocky Hill CT

Part

Ref

By DAP

Date 5/13/19

Chd BK

Client VZW

File Rocky Hill CT.std

Date/Time 13-May-2019 16:22

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	8:WLS#4	0.500	4.555	0.000		-4.555	0.000	
	9:WLM#1	0.500	1.423	0.000		-1.423	0.000	
	10:WLM#4	0.500	1.423	0.000		-1.423	0.000	
	11:LM	0.500	0.000	0.000		-0.000	0.000	
	12:LV	0.500	0.000	0.000		-0.000	0.000	
	13:1.2D+1.6WI	0.500	22.951	0.000		-18.955	0.000	
	14:1.2D+1.6WI	0.500	22.951	0.000		-18.955	0.000	
	15:1.2D-1.6WL	0.500	22.951	0.000		-18.955	0.000	
	16:1.2D-1.6WL	0.500	22.951	0.000		-18.955	0.000	
	17:1.2D+1.0DI	0.500	18.148	0.000		-1.211	0.000	
	18:1.2D+1.0DI	0.500	18.148	0.000		-1.211	0.000	
	19:1.2D+1.0DI	0.500	18.148	0.000		-1.211	0.000	
	20:1.2D+1.0DI	0.500	18.148	0.000		-1.211	0.000	
	21:1.0D+1.0WI	0.500	6.220	0.000		-2.890	0.000	
	22:1.0D+1.0WI	0.500	6.220	0.000		-2.890	0.000	
	23:1.0D-1.0WL	0.500	6.220	0.000		-2.890	0.000	
	24:1.0D-1.0WL	0.500	6.220	0.000		-2.890	0.000	
	25:1.4D	0.500	2.331	0.000				
	26:1.2D+1.5LM	0.500	3.421	0.000				
	27:1.2D+1.5LM	0.500	3.421	0.000				
	28:1.2D+1.5LM	0.500	3.421	0.000				
	29:1.2D+1.5LM	0.500	3.421	0.000				
	30:1.2D+1.5LV	0.500	1.998	0.000				
103	1:DEAD	0.500	1.665	0.000		-0.000	0.500	
	2:WL#1	0.500	13.096	0.000		-13.096	0.000	
	3:WL#4	0.500	13.096	0.000		-13.096	0.000	
	4:DI	0.500	6.471	0.000		-0.000	0.500	
	5:WLI#1	0.500	9.679	0.000		-9.679	0.000	
	6:WLI#4	0.500	9.679	0.000		-9.679	0.000	
	7:WLS#1	0.500	4.555	0.000		-4.555	0.000	
	8:WLS#4	0.500	4.555	0.000		-4.555	0.000	
	9:WLM#1	0.500	1.423	0.000		-1.423	0.000	
	10:WLM#4	0.500	1.423	0.000		-1.423	0.000	
	11:LM	0.500	0.000	0.000		-0.000	0.000	
	12:LV	0.500	0.000	0.500		-0.000	0.500	
	13:1.2D+1.6WI	0.500	22.951	0.000		-18.955	0.000	
	14:1.2D+1.6WI	0.500	22.951	0.000		-18.955	0.000	
	15:1.2D-1.6WL	0.500	22.951	0.000		-18.955	0.000	
	16:1.2D-1.6WL	0.500	22.951	0.000		-18.955	0.000	
	17:1.2D+1.0DI	0.500	18.148	0.000		-1.211	0.000	
	18:1.2D+1.0DI	0.500	18.148	0.000		-1.211	0.000	
	19:1.2D+1.0DI	0.500	18.148	0.000		-1.211	0.000	
	20:1.2D+1.0DI	0.500	18.148	0.000		-1.211	0.000	
	21:1.0D+1.0WI	0.500	6.220	0.000		-2.890	0.000	



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
43

Rev
1

Job Title Rocky Hill CT

Part

Ref

By DAP

Date 5/13/19

Chd BK

Client VZW

File Rocky Hill CT.std

Date/Time 13-May-2019 16:22

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	22:1.0D+1.0WI	0.500	6.220	0.000		-2.890	0.000	
	23:1.0D-1.0WL	0.500	6.220	0.000		-2.890	0.000	
	24:1.0D-1.0WL	0.500	6.220	0.000		-2.890	0.000	
	25:1.4D	0.500	2.331	0.000		-0.000	0.500	
	26:1.2D+1.5LM	0.500	3.421	0.000		-0.000	0.500	
	27:1.2D+1.5LM	0.500	3.421	0.000		-0.000	0.500	
	28:1.2D+1.5LM	0.500	3.421	0.000		-0.000	0.500	
	29:1.2D+1.5LM	0.500	3.421	0.000				
	30:1.2D+1.5LV	0.500	1.998	0.000		-0.000	0.500	
104	1:DEAD	0.500	1.665	0.000		-0.000	0.500	
	2:WL#1	0.500	13.096	0.000		-13.096	0.000	
	3:WL#4	0.500	13.096	0.000		-13.096	0.000	
	4:DI	0.500	6.471	0.000		-0.000	0.500	
	5:WLI#1	0.500	9.679	0.000		-9.679	0.000	
	6:WLI#4	0.500	9.679	0.000		-9.679	0.000	
	7:WLS#1	0.500	4.555	0.000		-4.555	0.000	
	8:WLS#4	0.500	4.555	0.000		-4.555	0.000	
	9:WLM#1	0.500	1.423	0.000		-1.423	0.000	
	10:WLM#4	0.500	1.423	0.000		-1.423	0.000	
	11:LM	0.500	0.000	0.000				
	12:LV	0.500				-0.000	0.458	
	13:1.2D+1.6WI	0.500	22.951	0.000		-18.955	0.000	
	14:1.2D+1.6WI	0.500	22.951	0.000		-18.955	0.000	
	15:1.2D-1.6WL	0.500	22.951	0.000		-18.955	0.000	
	16:1.2D-1.6WL	0.500	22.951	0.000		-18.955	0.000	
	17:1.2D+1.0DI	0.500	18.148	0.000		-1.211	0.000	
	18:1.2D+1.0DI	0.500	18.148	0.000		-1.211	0.000	
	19:1.2D+1.0DI	0.500	18.148	0.000		-1.211	0.000	
	20:1.2D+1.0DI	0.500	18.148	0.000		-1.211	0.000	
	21:1.0D+1.0WI	0.500	6.220	0.000		-2.890	0.000	
	22:1.0D+1.0WI	0.500	6.220	0.000		-2.890	0.000	
	23:1.0D-1.0WL	0.500	6.220	0.000		-2.890	0.000	
	24:1.0D-1.0WL	0.500	6.220	0.000		-2.890	0.000	
	25:1.4D	0.500	2.331	0.000		-0.000	0.500	
	26:1.2D+1.5LM	0.500	3.421	0.000		-0.000	0.500	
	27:1.2D+1.5LM	0.500	3.421	0.000		-0.000	0.500	
	28:1.2D+1.5LM	0.500	3.421	0.000				
	29:1.2D+1.5LM	0.500	3.421	0.000		-0.000	0.500	
	30:1.2D+1.5LV	0.500	1.998	0.000		-0.000	0.500	
105	1:DEAD	0.500	1.665	0.000				
	2:WL#1	0.500	13.096	0.000		-13.096	0.000	
	3:WL#4	0.500	13.096	0.000		-13.096	0.000	
	4:DI	0.500	6.471	0.000		-0.000	0.500	
	5:WLI#1	0.500	9.679	0.000		-9.679	0.000	



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
44

Rev
1

Job Title **Rocky Hill CT**

Part

Ref

By **DAP**

Date **5/13/19**

Chd **BK**

Client **VZW**

File **Rocky Hill CT.std**

Date/Time **13-May-2019 16:22**

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	6:WLI#4	0.500	9.679	0.000		-9.679	0.000	
	7:WLS#1	0.500	4.555	0.000		-4.555	0.000	
	8:WLS#4	0.500	4.555	0.000		-4.555	0.000	
	9:WLM#1	0.500	1.423	0.000		-1.423	0.000	
	10:WLM#4	0.500	1.423	0.000		-1.423	0.000	
	11:LM	0.500	0.000	0.000		-0.000	0.000	
	12:LV	0.500				-0.000	0.000	
	13:1.2D+1.6WI	0.500	22.951	0.000		-18.955	0.000	
	14:1.2D+1.6WI	0.500	22.951	0.000		-18.955	0.000	
	15:1.2D-1.6WL	0.500	22.951	0.000		-18.955	0.000	
	16:1.2D-1.6WL	0.500	22.951	0.000		-18.955	0.000	
	17:1.2D+1.0DI	0.500	18.148	0.000		-1.211	0.000	
	18:1.2D+1.0DI	0.500	18.148	0.000		-1.211	0.000	
	19:1.2D+1.0DI	0.500	18.148	0.000		-1.211	0.000	
	20:1.2D+1.0DI	0.500	18.148	0.000		-1.211	0.000	
	21:1.0D+1.0WI	0.500	6.220	0.000		-2.890	0.000	
	22:1.0D+1.0WI	0.500	6.220	0.000		-2.890	0.000	
	23:1.0D-1.0WL	0.500	6.220	0.000		-2.890	0.000	
	24:1.0D-1.0WL	0.500	6.220	0.000		-2.890	0.000	
	25:1.4D	0.500	2.331	0.000				
	26:1.2D+1.5LV	0.500	3.421	0.000				
	27:1.2D+1.5LV	0.500	3.421	0.000				
	28:1.2D+1.5LV	0.500	3.421	0.000				
	29:1.2D+1.5LV	0.500	3.421	0.000				
	30:1.2D+1.5LV	0.500	1.998	0.000				
106	1:DEAD	0.500	1.665	0.000		-0.000	0.500	
	2:WL#1	0.500	13.096	0.000		-13.096	0.000	
	3:WL#4	0.500	13.096	0.000		-13.096	0.000	
	4:DI	0.500	6.471	0.000				
	5:WLI#1	0.500	9.679	0.000		-9.679	0.000	
	6:WLI#4	0.500	9.679	0.000		-9.679	0.000	
	7:WLS#1	0.500	4.555	0.000		-4.555	0.000	
	8:WLS#4	0.500	4.555	0.000		-4.555	0.000	
	9:WLM#1	0.500	1.423	0.000		-1.423	0.000	
	10:WLM#4	0.500	1.423	0.000		-1.423	0.000	
	11:LM	0.500	0.000	0.000		-0.000	0.000	
	12:LV	0.500	0.000	0.458				
	13:1.2D+1.6WI	0.500	22.951	0.000		-18.955	0.000	
	14:1.2D+1.6WI	0.500	22.951	0.000		-18.955	0.000	
	15:1.2D-1.6WL	0.500	22.951	0.000		-18.955	0.000	
	16:1.2D-1.6WL	0.500	22.951	0.000		-18.955	0.000	
	17:1.2D+1.0DI	0.500	18.148	0.000		-1.211	0.000	
	18:1.2D+1.0DI	0.500	18.148	0.000		-1.211	0.000	
	19:1.2D+1.0DI	0.500	18.148	0.000		-1.211	0.000	



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
45

Rev
1

Job Title **Rocky Hill CT**

Part

Ref

By **DAP**

Date **5/13/19**

Chd **BK**

Client **VZW**

File **Rocky Hill CT.std**

Date/Time **13-May-2019 16:22**

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	20:1.2D+1.0DI-	0.500	18.148	0.000		-1.211	0.000	
	21:1.0D+1.0WI	0.500	6.220	0.000		-2.890	0.000	
	22:1.0D+1.0WI	0.500	6.220	0.000		-2.890	0.000	
	23:1.0D-1.0WL	0.500	6.220	0.000		-2.890	0.000	
	24:1.0D-1.0WL	0.500	6.220	0.000		-2.890	0.000	
	25:1.4D	0.500	2.331	0.000		-0.000	0.500	
	26:1.2D+1.5LM	0.500	3.421	0.000		-0.000	0.500	
	27:1.2D+1.5LM	0.500	3.421	0.000		-0.000	0.500	
	28:1.2D+1.5LM	0.500	3.421	0.000		-0.000	0.500	
	29:1.2D+1.5LM	0.500	3.421	0.000		-0.000	0.500	
	30:1.2D+1.5LV	0.500	1.998	0.000		-0.000	0.500	
107	1:DEAD	0.500	1.665	0.000				
	2:WL#1	0.500	13.096	0.000		-13.096	0.000	
	3:WL#4	0.500	13.096	0.000		-13.096	0.000	
	4:DI	0.500	6.471	0.000		-0.000	0.500	
	5:WL#1	0.500	9.679	0.000		-9.679	0.000	
	6:WL#4	0.500	9.679	0.000		-9.679	0.000	
	7:WLS#1	0.500	4.555	0.000		-4.555	0.000	
	8:WLS#4	0.500	4.555	0.000		-4.555	0.000	
	9:WLM#1	0.500	1.423	0.000		-1.423	0.000	
	10:WLM#4	0.500	1.423	0.000		-1.423	0.000	
	11:LM	0.500	0.000	0.500		-0.000	0.500	
	12:LV	0.500				-0.000	0.458	
	13:1.2D+1.6WI	0.500	22.951	0.000		-18.955	0.000	
	14:1.2D+1.6WI	0.500	22.951	0.000		-18.955	0.000	
	15:1.2D-1.6WL	0.500	22.951	0.000		-18.955	0.000	
	16:1.2D-1.6WL	0.500	22.951	0.000		-18.955	0.000	
	17:1.2D+1.0DI-	0.500	18.148	0.000		-1.211	0.000	
	18:1.2D+1.0DI-	0.500	18.148	0.000		-1.211	0.000	
	19:1.2D+1.0DI-	0.500	18.148	0.000		-1.211	0.000	
	20:1.2D+1.0DI-	0.500	18.148	0.000		-1.211	0.000	
	21:1.0D+1.0WI	0.500	6.220	0.000		-2.890	0.000	
	22:1.0D+1.0WI	0.500	6.220	0.000		-2.890	0.000	
	23:1.0D-1.0WL	0.500	6.220	0.000		-2.890	0.000	
	24:1.0D-1.0WL	0.500	6.220	0.000		-2.890	0.000	
	25:1.4D	0.500	2.331	0.000				
	26:1.2D+1.5LM	0.500	3.421	0.000				
	27:1.2D+1.5LM	0.500	3.421	0.000				
	28:1.2D+1.5LM	0.500	3.421	0.000		-0.000	0.500	
	29:1.2D+1.5LM	0.500	3.421	0.000				
	30:1.2D+1.5LV	0.500	1.998	0.000				
108	1:DEAD	0.500	1.665	0.000				
	2:WL#1	0.500	13.096	0.000		-13.096	0.000	
	3:WL#4	0.500	13.096	0.000		-13.096	0.000	



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
46

Rev
1

Job Title **Rocky Hill CT**

Part

Ref

By **DAP**

Date **5/13/19**

Chd **BK**

Client **VZW**

File **Rocky Hill CT.std**

Date/Time **13-May-2019 16:22**

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	4:DI	0.500	6.471	0.000				
	5:WLI#1	0.500	9.679	0.000		-9.679	0.000	
	6:WLI#4	0.500	9.679	0.000		-9.679	0.000	
	7:WLS#1	0.500	4.555	0.000		-4.555	0.000	
	8:WLS#4	0.500	4.555	0.000		-4.555	0.000	
	9:WLM#1	0.500	1.423	0.000		-1.423	0.000	
	10:WLM#4	0.500	1.423	0.000		-1.423	0.000	
	11:LM	0.500	0.000	0.458		-0.000	0.458	
	12:LV	0.500	0.000	0.500		-0.000	0.500	
	13:1.2D+1.6WI	0.500	22.951	0.000		-18.955	0.000	
	14:1.2D+1.6WI	0.500	22.951	0.000		-18.955	0.000	
	15:1.2D-1.6WL	0.500	22.951	0.000		-18.955	0.000	
	16:1.2D-1.6WL	0.500	22.951	0.000		-18.955	0.000	
	17:1.2D+1.0DI	0.500	18.148	0.000		-1.211	0.000	
	18:1.2D+1.0DI	0.500	18.148	0.000		-1.211	0.000	
	19:1.2D+1.0DI	0.500	18.148	0.000		-1.211	0.000	
	20:1.2D+1.0DI	0.500	18.148	0.000		-1.211	0.000	
	21:1.0D+1.0WI	0.500	6.220	0.000		-2.890	0.000	
	22:1.0D+1.0WI	0.500	6.220	0.000		-2.890	0.000	
	23:1.0D-1.0WL	0.500	6.220	0.000		-2.890	0.000	
	24:1.0D-1.0WL	0.500	6.220	0.000		-2.890	0.000	
	25:1.4D	0.500	2.331	0.000				
	26:1.2D+1.5LM	0.500	3.421	0.000				
	27:1.2D+1.5LM	0.500	3.421	0.000				
	28:1.2D+1.5LM	0.500	3.421	0.000				
	29:1.2D+1.5LM	0.500	3.421	0.000				
	30:1.2D+1.5LV	0.500	1.998	0.000				
109	1:DEAD	0.500	1.665	0.000		-0.000	0.500	
	2:WL#1	0.500	13.096	0.000		-13.096	0.000	
	3:WL#4	0.500	13.096	0.000		-13.096	0.000	
	4:DI	0.500	6.471	0.000		-0.000	0.500	
	5:WLI#1	0.500	9.679	0.000		-9.679	0.000	
	6:WLI#4	0.500	9.679	0.000		-9.679	0.000	
	7:WLS#1	0.500	4.555	0.000		-4.555	0.000	
	8:WLS#4	0.500	4.555	0.000		-4.555	0.000	
	9:WLM#1	0.500	1.423	0.000		-1.423	0.000	
	10:WLM#4	0.500	1.423	0.000		-1.423	0.000	
	11:LM	0.500	0.000	0.000				
	12:LV	0.500	0.000	0.000		-0.000	0.000	
	13:1.2D+1.6WI	0.500	22.951	0.000		-18.955	0.000	
	14:1.2D+1.6WI	0.500	22.951	0.000		-18.955	0.000	
	15:1.2D-1.6WL	0.500	22.951	0.000		-18.955	0.000	
	16:1.2D-1.6WL	0.500	22.951	0.000		-18.955	0.000	
	17:1.2D+1.0DI	0.500	18.148	0.000		-1.211	0.000	



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
47

Rev
1

Job Title **Rocky Hill CT**

Part

Ref

By **DAP**

Date **5/13/19**

Chd **BK**

Client **VZW**

File **Rocky Hill CT.std**

Date/Time **13-May-2019 16:22**

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	18:1.2D+1.0DI-	0.500	18.148	0.000		-1.211	0.000	
	19:1.2D+1.0DI-	0.500	18.148	0.000		-1.211	0.000	
	20:1.2D+1.0DI-	0.500	18.148	0.000		-1.211	0.000	
	21:1.0D+1.0WI	0.500	6.220	0.000		-2.890	0.000	
	22:1.0D+1.0WI	0.500	6.220	0.000		-2.890	0.000	
	23:1.0D-1.0WL	0.500	6.220	0.000		-2.890	0.000	
	24:1.0D-1.0WL	0.500	6.220	0.000		-2.890	0.000	
	25:1.4D	0.500	2.331	0.000		-0.000	0.500	
	26:1.2D+1.5LM	0.500	3.421	0.000		-0.000	0.500	
	27:1.2D+1.5LM	0.500	3.421	0.000		-0.000	0.500	
	28:1.2D+1.5LM	0.500	3.421	0.000		-0.000	0.500	
	29:1.2D+1.5LM	0.500	3.421	0.000		-0.000	0.500	
	30:1.2D+1.5LV	0.500	1.998	0.000		-0.000	0.500	
110	1:DEAD	0.333				-42.578	0.333	
	2:WL#1	0.333	1.45E+3	0.333		-1.45E+3	0.333	
	3:WL#4	0.333	1.76E+3	0.333		-1.76E+3	0.333	
	4:DI	0.333				-281.176	0.333	
	5:WLI#1	0.333	622.077	0.333		-622.077	0.333	
	6:WLI#4	0.333	707.357	0.333		-707.357	0.333	
	7:WLS#1	0.333	509.150	0.333		-509.150	0.333	
	8:WLS#4	0.333	619.483	0.333		-619.483	0.333	
	9:WLM#1	0.333	143.641	0.333		-143.641	0.333	
	10:WLM#4	0.333	173.375	0.333		-173.375	0.333	
	11:LM	0.333	0.000	0.333		-0.000	0.333	
	12:LV	0.333	0.000	0.333		-0.000	0.333	
	13:1.2D+1.6WI	0.333	2.26E+3	0.333		-2.37E+3	0.333	
	14:1.2D+1.6WI	0.333	2.76E+3	0.333		-2.87E+3	0.333	
	15:1.2D-1.6WL	0.333	2.26E+3	0.333		-2.37E+3	0.333	
	16:1.2D-1.6WL	0.333	2.76E+3	0.333		-2.87E+3	0.333	
	17:1.2D+1.0DI-	0.333	289.806	0.333		-954.347	0.333	
	18:1.2D+1.0DI-	0.333	375.086	0.333		-1.04E+3	0.333	
	19:1.2D+1.0DI-	0.333	289.806	0.333		-954.347	0.333	
	20:1.2D+1.0DI-	0.333	375.086	0.333		-1.04E+3	0.333	
	21:1.0D+1.0WI	0.333	466.572	0.333		-551.728	0.333	
	22:1.0D+1.0WI	0.333	576.904	0.333		-662.061	0.333	
	23:1.0D-1.0WL	0.333	466.572	0.333		-551.728	0.333	
	24:1.0D-1.0WL	0.333	576.904	0.333		-662.061	0.333	
	25:1.4D	0.333				-59.610	0.333	
	26:1.2D+1.5LM	0.333	92.547	0.333		-194.735	0.333	
	27:1.2D+1.5LM	0.333	122.281	0.333		-224.470	0.333	
	28:1.2D+1.5LM	0.333	92.547	0.333		-194.735	0.333	
	29:1.2D+1.5LM	0.333	122.281	0.333		-224.470	0.333	
	30:1.2D+1.5LV	0.333				-51.094	0.333	
111	1:DEAD	0.333				-42.578	0.333	



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
48

Rev
1

Job Title **Rocky Hill CT**

Part

Ref

By **DAP**

Date **5/13/19**

Chd **BK**

Client **VZW**

File **Rocky Hill CT.std**

Date/Time **13-May-2019 16:22**

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	2:WL#1	0.333	1.45E+3	0.333		-1.45E+3	0.333	
	3:WL#4	0.333	1.76E+3	0.333		-1.76E+3	0.333	
	4:DI	0.333				-281.176	0.333	
	5:WLI#1	0.333	622.077	0.333		-622.077	0.333	
	6:WLI#4	0.333	707.357	0.333		-707.357	0.333	
	7:WLS#1	0.333	509.150	0.333		-509.150	0.333	
	8:WLS#4	0.333	619.483	0.333		-619.483	0.333	
	9:WLM#1	0.333	143.641	0.333		-143.641	0.333	
	10:WLM#4	0.333	173.375	0.333		-173.375	0.333	
	11:LM	0.333	0.000	0.333		-0.000	0.333	
	12:LV	0.333	0.000	0.333				
	13:1.2D+1.6WI	0.333	2.26E+3	0.333		-2.37E+3	0.333	
	14:1.2D+1.6WI	0.333	2.76E+3	0.333		-2.87E+3	0.333	
	15:1.2D-1.6WL	0.333	2.26E+3	0.333		-2.37E+3	0.333	
	16:1.2D-1.6WL	0.333	2.76E+3	0.333		-2.87E+3	0.333	
	17:1.2D+1.0DI	0.333	289.806	0.333		-954.347	0.333	
	18:1.2D+1.0DI	0.333	375.086	0.333		-1.04E+3	0.333	
	19:1.2D+1.0DI	0.333	289.806	0.333		-954.347	0.333	
	20:1.2D+1.0DI	0.333	375.086	0.333		-1.04E+3	0.333	
	21:1.0D+1.0WI	0.333	466.572	0.333		-551.728	0.333	
	22:1.0D+1.0WI	0.333	576.904	0.333		-662.061	0.333	
	23:1.0D-1.0WL	0.333	466.572	0.333		-551.728	0.333	
	24:1.0D-1.0WL	0.333	576.904	0.333		-662.061	0.333	
	25:1.4D	0.333				-59.610	0.333	
	26:1.2D+1.5LV	0.333	92.547	0.333		-194.735	0.333	
	27:1.2D+1.5LV	0.333	122.281	0.333		-224.470	0.333	
	28:1.2D+1.5LV	0.333	92.547	0.333		-194.735	0.333	
	29:1.2D+1.5LV	0.333	122.281	0.333		-224.470	0.333	
	30:1.2D+1.5LV	0.333				-51.094	0.333	
112	1:DEAD	0.333				-42.578	0.333	
	2:WL#1	0.333	1.92E+3	0.333		-1.92E+3	0.333	
	3:WL#4	0.333	1.29E+3	0.333		-1.29E+3	0.333	
	4:DI	0.333				-281.177	0.333	
	5:WLI#1	0.333	752.907	0.333		-752.907	0.333	
	6:WLI#4	0.333	578.045	0.333		-578.045	0.333	
	7:WLS#1	0.333	675.661	0.333		-675.661	0.333	
	8:WLS#4	0.333	452.971	0.333		-452.971	0.333	
	9:WLM#1	0.333	190.077	0.333		-190.077	0.333	
	10:WLM#4	0.333	126.940	0.333		-126.940	0.333	
	11:LM	0.333				-0.000	0.306	
	12:LV	0.333	0.000	0.000		-0.000	0.000	
	13:1.2D+1.6WI	0.333	3.02E+3	0.333		-3.12E+3	0.333	
	14:1.2D+1.6WI	0.333	2.01E+3	0.333		-2.11E+3	0.333	
	15:1.2D-1.6WL	0.333	3.02E+3	0.333		-3.12E+3	0.333	



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
49

Rev
1

Part

Job Title Rocky Hill CT

Ref

By DAP

Date 5/13/19

Chd BK

Client VZW

File Rocky Hill CT.std

Date/Time 13-May-2019 16:22

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	16:1.2D-1.6WL	0.333	2.01E+3	0.333		-2.11E+3	0.333	
	17:1.2D+1.0DI	0.333	420.636	0.333		-1.09E+3	0.333	
	18:1.2D+1.0DI	0.333	245.774	0.333		-910.315	0.333	
	19:1.2D+1.0DI	0.333	420.636	0.333		-1.09E+3	0.333	
	20:1.2D+1.0DI	0.333	245.774	0.333		-910.316	0.333	
	21:1.0D+1.0WI	0.333	633.083	0.333		-718.240	0.333	
	22:1.0D+1.0WI	0.333	410.393	0.333		-495.550	0.333	
	23:1.0D-1.0WL	0.333	633.083	0.333		-718.240	0.333	
	24:1.0D-1.0WL	0.333	410.393	0.333		-495.550	0.333	
	25:1.4D	0.333				-59.610	0.333	
	26:1.2D+1.5LN	0.333	138.983	0.333		-241.171	0.333	
	27:1.2D+1.5LN	0.333	75.845	0.333		-178.034	0.333	
	28:1.2D+1.5LN	0.333	138.983	0.333		-241.171	0.333	
	29:1.2D+1.5LN	0.333	75.845	0.333		-178.034	0.333	
	30:1.2D+1.5LV	0.333				-51.094	0.333	
113	1:DEAD	0.333				-10.127	0.333	
	2:WL#1	0.333	408.370	0.333		-408.370	0.333	
	3:WL#4	0.333	410.901	0.333		-410.901	0.333	
	4:DI	0.333				-79.706	0.333	
	5:WLI#1	0.333	193.905	0.333		-193.905	0.333	
	6:WLI#4	0.333	191.880	0.333		-191.880	0.333	
	7:WLS#1	0.333	143.989	0.333		-143.989	0.333	
	8:WLS#4	0.333	144.242	0.333		-144.242	0.333	
	9:WLM#1	0.333	40.394	0.333		-40.394	0.333	
	10:WLM#4	0.333	40.521	0.333		-40.521	0.333	
	11:LM	0.333	0.000	0.333		-0.000	0.333	
	12:LV	0.333	0.000	0.306				
	13:1.2D+1.6WI	0.333	641.239	0.333		-665.545	0.333	
	14:1.2D+1.6WI	0.333	645.288	0.333		-669.594	0.333	
	15:1.2D-1.6WL	0.333	641.239	0.333		-665.545	0.333	
	16:1.2D-1.6WL	0.333	645.288	0.333		-669.594	0.333	
	17:1.2D+1.0DI	0.333	102.046	0.333		-285.763	0.333	
	18:1.2D+1.0DI	0.333	100.021	0.333		-283.739	0.333	
	19:1.2D+1.0DI	0.333	102.046	0.333		-285.763	0.333	
	20:1.2D+1.0DI	0.333	100.021	0.333		-283.739	0.333	
	21:1.0D+1.0WI	0.333	133.862	0.333		-154.117	0.333	
	22:1.0D+1.0WI	0.333	134.115	0.333		-154.370	0.333	
	23:1.0D-1.0WL	0.333	133.862	0.333		-154.117	0.333	
	24:1.0D-1.0WL	0.333	134.115	0.333		-154.370	0.333	
	25:1.4D	0.333				-14.178	0.333	
	26:1.2D+1.5LN	0.333	28.241	0.333		-52.547	0.333	
	27:1.2D+1.5LN	0.333	28.368	0.333		-52.674	0.333	
	28:1.2D+1.5LN	0.333	28.241	0.333		-52.547	0.333	
	29:1.2D+1.5LN	0.333	28.368	0.333		-52.674	0.333	



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No 50103542	Sheet No 50	Rev 1
Part		
Ref		
By DAP	Date 5/13/19	Chd BK
File Rocky Hill CT.std	Date/Time 13-May-2019 16:22	

Job Title Rocky Hill CT

Client VZW

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
114	30:1.2D+1.5LV	0.333				-12.153	0.333	
	1:DEAD	0.333				-10.127	0.333	
	2:WL#1	0.333	408.370	0.333		-408.370	0.333	
	3:WL#4	0.333	410.901	0.333		-410.901	0.333	
	4:DI	0.333				-79.706	0.333	
	5:WLI#1	0.333	193.905	0.333		-193.905	0.333	
	6:WLI#4	0.333	191.880	0.333		-191.880	0.333	
	7:WLS#1	0.333	143.989	0.333		-143.989	0.333	
	8:WLS#4	0.333	144.242	0.333		-144.242	0.333	
	9:WLM#1	0.333	40.394	0.333		-40.394	0.333	
	10:WLM#4	0.333	40.521	0.333		-40.521	0.333	
	11:LM	0.333	0.000	0.333				
	12:LV	0.333				-0.000	0.000	
	13:1.2D+1.6WI	0.333	641.239	0.333		-665.545	0.333	
	14:1.2D+1.6WI	0.333	645.288	0.333		-669.594	0.333	
	15:1.2D-1.6WL	0.333	641.239	0.333		-665.545	0.333	
	16:1.2D-1.6WL	0.333	645.288	0.333		-669.594	0.333	
	17:1.2D+1.0DI	0.333	102.046	0.333		-285.763	0.333	
	18:1.2D+1.0DI	0.333	100.021	0.333		-283.739	0.333	
	19:1.2D+1.0DI	0.333	102.046	0.333		-285.763	0.333	
	20:1.2D+1.0DI	0.333	100.021	0.333		-283.739	0.333	
	21:1.0D+1.0WI	0.333	133.862	0.333		-154.117	0.333	
	22:1.0D+1.0WI	0.333	134.115	0.333		-154.370	0.333	
	23:1.0D-1.0WL	0.333	133.862	0.333		-154.117	0.333	
	24:1.0D-1.0WL	0.333	134.115	0.333		-154.370	0.333	
	25:1.4D	0.333				-14.178	0.333	
	26:1.2D+1.5LV	0.333	28.241	0.333		-52.547	0.333	
	27:1.2D+1.5LV	0.333	28.368	0.333		-52.674	0.333	
	28:1.2D+1.5LV	0.333	28.241	0.333		-52.547	0.333	
	29:1.2D+1.5LV	0.333	28.368	0.333		-52.674	0.333	
	30:1.2D+1.5LV	0.333				-12.153	0.333	
115	1:DEAD	0.333				-12.578	0.333	
	2:WL#1	0.333	685.467	0.333		-685.467	0.333	
	3:WL#4	0.333	722.160	0.333		-722.160	0.333	
	4:DI	0.333				-132.941	0.333	
	5:WLI#1	0.333	280.450	0.333		-280.450	0.333	
	6:WLI#4	0.333	289.054	0.333		-289.054	0.333	
	7:WLS#1	0.333	241.163	0.333		-241.163	0.333	
	8:WLS#4	0.333	253.563	0.333		-253.563	0.333	
	9:WLM#1	0.333	67.724	0.333		-67.724	0.333	
	10:WLM#4	0.333	71.647	0.333		-71.647	0.333	
	11:LM	0.333	0.000	0.333		-0.000	0.333	
	12:LV	0.333	0.000	0.333		-0.000	0.333	
	13:1.2D+1.6WI	0.333	1.08E+3	0.333		-1.11E+3	0.333	



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
51

Rev
1

Job Title **Rocky Hill CT**

Part

Ref

By **DAP**

Date **5/13/19**

Chd **BK**

Client **VZW**

File **Rocky Hill CT.std**

Date/Time **13-May-2019 16:22**

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	14:1.2D+1.6WI	0.333	1.14E+3	0.333		-1.17E+3	0.333	
	15:1.2D-1.6WL	0.333	1.08E+3	0.333		-1.11E+3	0.333	
	16:1.2D-1.6WL	0.333	1.14E+3	0.333		-1.17E+3	0.333	
	17:1.2D+1.0DI	0.333	132.415	0.333		-428.485	0.333	
	18:1.2D+1.0DI	0.333	141.019	0.333		-437.089	0.333	
	19:1.2D+1.0DI	0.333	132.415	0.333		-428.485	0.333	
	20:1.2D+1.0DI	0.333	141.019	0.333		-437.089	0.333	
	21:1.0D+1.0WI	0.333	228.585	0.333		-253.741	0.333	
	22:1.0D+1.0WI	0.333	240.984	0.333		-266.141	0.333	
	23:1.0D-1.0WL	0.333	228.585	0.333		-253.741	0.333	
	24:1.0D-1.0WL	0.333	240.984	0.333		-266.141	0.333	
	25:1.4D	0.333				-17.610	0.333	
	26:1.2D+1.5LV	0.333	52.630	0.333		-82.818	0.333	
	27:1.2D+1.5LV	0.333	56.553	0.333		-86.741	0.333	
	28:1.2D+1.5LV	0.333	52.630	0.333		-82.818	0.333	
	29:1.2D+1.5LV	0.333	56.553	0.333		-86.741	0.333	
	30:1.2D+1.5LV	0.333				-15.094	0.333	
116	1:DEAD	0.333				-12.578	0.333	
	2:WL#1	0.333	685.467	0.333		-685.467	0.333	
	3:WL#4	0.333	722.160	0.333		-722.160	0.333	
	4:DI	0.333				-132.941	0.333	
	5:WLI#1	0.333	280.450	0.333		-280.450	0.333	
	6:WLI#4	0.333	289.054	0.333		-289.054	0.333	
	7:WLS#1	0.333	241.163	0.333		-241.163	0.333	
	8:WLS#4	0.333	253.563	0.333		-253.563	0.333	
	9:WLM#1	0.333	67.724	0.333		-67.724	0.333	
	10:WLM#4	0.333	71.647	0.333		-71.647	0.333	
	11:LM	0.333				-0.000	0.333	
	12:LV	0.333				-0.000	0.333	
	13:1.2D+1.6WI	0.333	1.08E+3	0.333		-1.11E+3	0.333	
	14:1.2D+1.6WI	0.333	1.14E+3	0.333		-1.17E+3	0.333	
	15:1.2D-1.6WL	0.333	1.08E+3	0.333		-1.11E+3	0.333	
	16:1.2D-1.6WL	0.333	1.14E+3	0.333		-1.17E+3	0.333	
	17:1.2D+1.0DI	0.333	132.415	0.333		-428.485	0.333	
	18:1.2D+1.0DI	0.333	141.019	0.333		-437.089	0.333	
	19:1.2D+1.0DI	0.333	132.415	0.333		-428.485	0.333	
	20:1.2D+1.0DI	0.333	141.019	0.333		-437.089	0.333	
	21:1.0D+1.0WI	0.333	228.585	0.333		-253.741	0.333	
	22:1.0D+1.0WI	0.333	240.984	0.333		-266.141	0.333	
	23:1.0D-1.0WL	0.333	228.585	0.333		-253.741	0.333	
	24:1.0D-1.0WL	0.333	240.984	0.333		-266.141	0.333	
	25:1.4D	0.333				-17.610	0.333	
	26:1.2D+1.5LV	0.333	52.630	0.333		-82.818	0.333	
	27:1.2D+1.5LV	0.333	56.553	0.333		-86.741	0.333	



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
52

Rev
1

Job Title **Rocky Hill CT**

Part

Ref

By **DAP**

Date **5/13/19**

Chd **BK**

Client **VZW**

File **Rocky Hill CT.std**

Date/Time **13-May-2019 16:22**

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	28:1.2D+1.5LM	0.333	52.630	0.333		-82.818	0.333	
	29:1.2D+1.5LM	0.333	56.553	0.333		-86.741	0.333	
	30:1.2D+1.5LV	0.333				-15.094	0.333	
117	1:DEAD	0.333				-12.578	0.333	
	2:WL#1	0.333	743.417	0.333		-743.417	0.333	
	3:WL#4	0.333	664.210	0.333		-664.210	0.333	
	4:DI	0.333				-132.941	0.333	
	5:WLI#1	0.333	295.886	0.333		-295.886	0.333	
	6:WLI#4	0.333	273.618	0.333		-273.618	0.333	
	7:WLS#1	0.333	261.154	0.333		-261.154	0.333	
	8:WLS#4	0.333	233.571	0.333		-233.571	0.333	
	9:WLM#1	0.333	73.924	0.333		-73.924	0.333	
	10:WLM#4	0.333	66.206	0.333		-66.206	0.333	
	11:LM	0.333	0.000	0.333				
	12:LV	0.333	0.000	0.333		-0.000	0.333	
	13:1.2D+1.6WI	0.333	1.17E+3	0.333		-1.2E+3	0.333	
	14:1.2D+1.6WI	0.333	1.05E+3	0.333		-1.08E+3	0.333	
	15:1.2D-1.6WL	0.333	1.17E+3	0.333		-1.2E+3	0.333	
	16:1.2D-1.6WL	0.333	1.05E+3	0.333		-1.08E+3	0.333	
	17:1.2D+1.0DI	0.333	147.851	0.333		-443.922	0.333	
	18:1.2D+1.0DI	0.333	125.582	0.333		-421.653	0.333	
	19:1.2D+1.0DI	0.333	147.851	0.333		-443.922	0.333	
	20:1.2D+1.0DI	0.333	125.582	0.333		-421.653	0.333	
	21:1.0D+1.0WI	0.333	248.576	0.333		-273.733	0.333	
	22:1.0D+1.0WI	0.333	220.993	0.333		-246.150	0.333	
	23:1.0D-1.0WL	0.333	248.576	0.333		-273.733	0.333	
	24:1.0D-1.0WL	0.333	220.993	0.333		-246.150	0.333	
	25:1.4D	0.333				-17.610	0.333	
	26:1.2D+1.5LM	0.333	58.830	0.333		-89.018	0.333	
	27:1.2D+1.5LM	0.333	51.112	0.333		-81.300	0.333	
	28:1.2D+1.5LM	0.333	58.830	0.333		-89.018	0.333	
	29:1.2D+1.5LM	0.333	51.112	0.333		-81.300	0.333	
	30:1.2D+1.5LV	0.333				-15.094	0.333	
118	1:DEAD	0.333				-12.578	0.333	
	2:WL#1	0.333	743.417	0.333		-743.417	0.333	
	3:WL#4	0.333	664.210	0.333		-664.210	0.333	
	4:DI	0.333				-132.941	0.333	
	5:WLI#1	0.333	295.886	0.333		-295.886	0.333	
	6:WLI#4	0.333	273.618	0.333		-273.618	0.333	
	7:WLS#1	0.333	261.154	0.333		-261.154	0.333	
	8:WLS#4	0.333	233.571	0.333		-233.571	0.333	
	9:WLM#1	0.333	73.924	0.333		-73.924	0.333	
	10:WLM#4	0.333	66.206	0.333		-66.206	0.333	
	11:LM	0.333	0.000	0.333				



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
53

Rev
1

Part

Job Title Rocky Hill CT

Ref

By DAP

Date 5/13/19

Chd BK

Client VZW

File Rocky Hill CT.std

Date/Time 13-May-2019 16:22

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	12:LV	0.333	0.000	0.333				
	13:1.2D+1.6WI	0.333	1.17E+3	0.333		-1.2E+3	0.333	
	14:1.2D+1.6WI	0.333	1.05E+3	0.333		-1.08E+3	0.333	
	15:1.2D-1.6WL	0.333	1.17E+3	0.333		-1.2E+3	0.333	
	16:1.2D-1.6WL	0.333	1.05E+3	0.333		-1.08E+3	0.333	
	17:1.2D+1.0DI	0.333	147.851	0.333		-443.922	0.333	
	18:1.2D+1.0DI	0.333	125.582	0.333		-421.653	0.333	
	19:1.2D+1.0DI	0.333	147.851	0.333		-443.922	0.333	
	20:1.2D+1.0DI	0.333	125.582	0.333		-421.653	0.333	
	21:1.0D+1.0WI	0.333	248.576	0.333		-273.733	0.333	
	22:1.0D+1.0WI	0.333	220.993	0.333		-246.150	0.333	
	23:1.0D-1.0WL	0.333	248.576	0.333		-273.733	0.333	
	24:1.0D-1.0WL	0.333	220.993	0.333		-246.150	0.333	
	25:1.4D	0.333				-17.610	0.333	
	26:1.2D+1.5LM	0.333	58.830	0.333		-89.018	0.333	
	27:1.2D+1.5LM	0.333	51.112	0.333		-81.300	0.333	
	28:1.2D+1.5LM	0.333	58.830	0.333		-89.018	0.333	
	29:1.2D+1.5LM	0.333	51.112	0.333		-81.300	0.333	
	30:1.2D+1.5LV	0.333				-15.094	0.333	
122	1:DEAD	0.521	3.25E+3	0.000	3	-3.21E+3	0.000	1
	2:WL#1	0.521	2.99E+3	0.521	4	-3.34E+3	0.521	2
	3:WL#4	0.521	4.42E+3	0.521	1	-3.79E+3	0.521	3
	4:DI	0.521	13.4E+3	0.000	3	-13.2E+3	0.000	1
	5:WLI#1	0.521	1.41E+3	0.521	4	-1.58E+3	0.521	2
	6:WLI#4	0.521	2.03E+3	0.521	1	-1.72E+3	0.521	3
	7:WLS#1	0.521	1.05E+3	0.521	4	-1.17E+3	0.521	2
	8:WLS#4	0.521	1.55E+3	0.521	1	-1.33E+3	0.521	3
	9:WLM#1	0.521	300.722	0.521	4	-335.571	0.521	2
	10:WLM#4	0.521	441.587	0.521	1	-378.450	0.521	3
	11:LM	0.521	4.434	0.000	2	-4.534	0.000	1
	12:LV	0.521	378.271	0.000	3	-378.066	0.000	1
	13:1.2D+1.6WI	0.521	7.63E+3	0.000	3	-8.14E+3	0.000	1
	14:1.2D+1.6WI	0.521	4.32E+3	0.521	1	-3.26E+3	0.521	3
	15:1.2D-1.6WL	0.521	2.59E+3	0.521	2	-1.99E+3	0.521	4
	16:1.2D-1.6WL	0.521	9.88E+3	0.000	3	-10.8E+3	0.000	1
	17:1.2D+1.0DI	0.521	18.4E+3	0.000	3	-18.3E+3	0.000	1
	18:1.2D+1.0DI	0.521	15.8E+3	0.000	3	-15.2E+3	0.000	1
	19:1.2D+1.0DI	0.521	16.5E+3	0.000	3	-16.1E+3	0.000	1
	20:1.2D+1.0DI	0.521	19E+3	0.000	3	-19E+3	0.000	1
	21:1.0D+1.0WI	0.521	4.07E+3	0.000	3	-4.15E+3	0.000	1
	22:1.0D+1.0WI	0.521	2.06E+3	0.000	3	-1.8E+3	0.000	1
	23:1.0D-1.0WL	0.521	2.65E+3	0.000	3	-2.49E+3	0.000	1
	24:1.0D-1.0WL	0.521	4.56E+3	0.000	3	-4.75E+3	0.000	1
	25:1.4D	0.521	4.55E+3	0.000	3	-4.5E+3	0.000	1



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
54

Rev
1

Job Title Rocky Hill CT

Ref

By DAP

Date 5/13/19

Chd BK

Client VZW

File Rocky Hill CT.std

Date/Time 13-May-2019 16:22

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	26:1.2D+1.5LV	0.521	4.14E+3	0.000	3	-4.13E+3	0.000	1
	27:1.2D+1.5LV	0.521	3.57E+3	0.000	3	-3.46E+3	0.000	1
	28:1.2D+1.5LV	0.521	3.73E+3	0.000	3	-3.65E+3	0.000	1
	29:1.2D+1.5LV	0.521	4.27E+3	0.000	3	-4.29E+3	0.000	1
	30:1.2D+1.5LV	0.521	4.47E+3	0.000	3	-4.42E+3	0.000	1
123	1:DEAD	0.667	13.688	0.667				
	2:WL#1	0.667	1.37E+3	0.667		-1.37E+3	0.667	
	3:WL#4	0.667	1.43E+3	0.667		-1.43E+3	0.667	
	4:DI	0.667	137.255	0.667				
	5:WLI#1	0.667	559.828	0.667		-559.828	0.667	
	6:WLI#4	0.667	568.432	0.667		-568.432	0.667	
	7:WLS#1	0.667	481.823	0.667		-481.823	0.667	
	8:WLS#4	0.667	502.573	0.667		-502.573	0.667	
	9:WLM#1	0.667	135.291	0.667		-135.291	0.667	
	10:WLM#4	0.667	141.871	0.667		-141.871	0.667	
	11:LM	0.667	0.000	0.667		-0.000	0.667	
	12:LV	0.667				-0.000	0.000	
	13:1.2D+1.6WI	0.667	2.21E+3	0.667		-2.17E+3	0.667	
	14:1.2D+1.6WI	0.667	2.31E+3	0.667		-2.27E+3	0.667	
	15:1.2D-1.6WL	0.667	2.21E+3	0.667		-2.17E+3	0.667	
	16:1.2D-1.6WL	0.667	2.31E+3	0.667		-2.27E+3	0.667	
	17:1.2D+1.0DI	0.667	713.509	0.667		-406.147	0.667	
	18:1.2D+1.0DI	0.667	722.113	0.667		-414.751	0.667	
	19:1.2D+1.0DI	0.667	713.509	0.667		-406.147	0.667	
	20:1.2D+1.0DI	0.667	722.113	0.667		-414.751	0.667	
	21:1.0D+1.0WI	0.667	495.511	0.667		-468.134	0.667	
	22:1.0D+1.0WI	0.667	516.262	0.667		-488.885	0.667	
	23:1.0D-1.0WL	0.667	495.511	0.667		-468.134	0.667	
	24:1.0D-1.0WL	0.667	516.262	0.667		-488.885	0.667	
	25:1.4D	0.667	19.164	0.667				
	26:1.2D+1.5LV	0.667	151.717	0.667		-118.865	0.667	
	27:1.2D+1.5LV	0.667	158.297	0.667		-125.445	0.667	
	28:1.2D+1.5LV	0.667	151.717	0.667		-118.865	0.667	
	29:1.2D+1.5LV	0.667	158.297	0.667		-125.445	0.667	
	30:1.2D+1.5LV	0.667	16.426	0.667				
124	1:DEAD	0.667	11.237	0.667				
	2:WL#1	0.667	815.290	0.667		-815.290	0.667	
	3:WL#4	0.667	808.710	0.667		-808.710	0.667	
	4:DI	0.667	84.020	0.667				
	5:WLI#1	0.667	386.736	0.667		-386.736	0.667	
	6:WLI#4	0.667	374.083	0.667		-374.083	0.667	
	7:WLS#1	0.667	287.474	0.667		-287.474	0.667	
	8:WLS#4	0.667	283.931	0.667		-283.931	0.667	
	9:WLM#1	0.667	80.631	0.667		-80.631	0.667	



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No 50103542	Sheet No 55	Rev 1
Part		
Ref		
By DAP	Date 5/13/19	Chd BK
File Rocky Hill CT.std	Date/Time 13-May-2019 16:22	

Job Title Rocky Hill CT

Client VZW

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	10:WLM#4	0.667	79.618	0.667		-79.618	0.667	
	11:LM	0.667	0.000	0.667		-0.000	0.667	
	12:LV	0.667	0.000	0.667		-0.000	0.667	
	13:1.2D+1.6WI	0.667	1.32E+3	0.667		-1.29E+3	0.667	
	14:1.2D+1.6WI	0.667	1.31E+3	0.667		-1.28E+3	0.667	
	15:1.2D-1.6WL	0.667	1.32E+3	0.667		-1.29E+3	0.667	
	16:1.2D-1.6WL	0.667	1.31E+3	0.667		-1.28E+3	0.667	
	17:1.2D+1.0DI	0.667	484.240	0.667		-289.232	0.667	
	18:1.2D+1.0DI	0.667	471.587	0.667		-276.579	0.667	
	19:1.2D+1.0DI	0.667	484.240	0.667		-289.232	0.667	
	20:1.2D+1.0DI	0.667	471.587	0.667		-276.579	0.667	
	21:1.0D+1.0WI	0.667	298.711	0.667		-276.237	0.667	
	22:1.0D+1.0WI	0.667	295.168	0.667		-272.694	0.667	
	23:1.0D-1.0WL	0.667	298.711	0.667		-276.237	0.667	
	24:1.0D-1.0WL	0.667	295.168	0.667		-272.694	0.667	
	25:1.4D	0.667	15.732	0.667				
	26:1.2D+1.5LN	0.667	94.115	0.667		-67.146	0.667	
	27:1.2D+1.5LN	0.667	93.103	0.667		-66.134	0.667	
	28:1.2D+1.5LN	0.667	94.115	0.667		-67.146	0.667	
	29:1.2D+1.5LN	0.667	93.103	0.667		-66.134	0.667	
	30:1.2D+1.5LV	0.667	13.485	0.667				
125	1:DEAD	0.667	43.688	0.667				
	2:WL#1	0.667	2.89E+3	0.667		-2.89E+3	0.667	
	3:WL#4	0.667	3.51E+3	0.667		-3.51E+3	0.667	
	4:DI	0.667	285.490	0.667				
	5:WLI#1	0.667	1.24E+3	0.667		-1.24E+3	0.667	
	6:WLI#4	0.667	1.41E+3	0.667		-1.41E+3	0.667	
	7:WLS#1	0.667	1.02E+3	0.667		-1.02E+3	0.667	
	8:WLS#4	0.667	1.23E+3	0.667		-1.23E+3	0.667	
	9:WLM#1	0.667	287.126	0.667		-287.126	0.667	
	10:WLM#4	0.667	345.329	0.667		-345.329	0.667	
	11:LM	0.667	0.000	0.611		-0.000	0.611	
	12:LV	0.667	0.000	0.667		-0.000	0.667	
	13:1.2D+1.6WI	0.667	4.68E+3	0.667		-4.58E+3	0.667	
	14:1.2D+1.6WI	0.667	5.66E+3	0.667		-5.56E+3	0.667	
	15:1.2D-1.6WL	0.667	4.68E+3	0.667		-4.58E+3	0.667	
	16:1.2D-1.6WL	0.667	5.66E+3	0.667		-5.56E+3	0.667	
	17:1.2D+1.0DI	0.667	1.58E+3	0.667		-905.169	0.667	
	18:1.2D+1.0DI	0.667	1.74E+3	0.667		-1.07E+3	0.667	
	19:1.2D+1.0DI	0.667	1.58E+3	0.667		-905.169	0.667	
	20:1.2D+1.0DI	0.667	1.74E+3	0.667		-1.07E+3	0.667	
	21:1.0D+1.0WI	0.667	1.06E+3	0.667		-974.111	0.667	
	22:1.0D+1.0WI	0.667	1.28E+3	0.667		-1.19E+3	0.667	
	23:1.0D-1.0WL	0.667	1.06E+3	0.667		-974.111	0.667	



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
56

Rev
1

Job Title Rocky Hill CT

Part

Ref

By DAP

Date 5/13/19

Chd BK

Client VZW

File Rocky Hill CT.std

Date/Time 13-May-2019 16:22

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	24:1.0D-1.0WL	0.667	1.28E+3	0.667		-1.19E+3	0.667	
	25:1.4D	0.667	61.164	0.667				
	26:1.2D+1.5LV	0.667	339.552	0.667		-234.700	0.667	
	27:1.2D+1.5LV	0.667	397.755	0.667		-292.904	0.667	
	28:1.2D+1.5LV	0.667	339.552	0.667		-234.700	0.667	
	29:1.2D+1.5LV	0.667	397.755	0.667		-292.904	0.667	
	30:1.2D+1.5LV	0.667	52.426	0.667				
127	1:DEAD	0.667	11.237	0.667				
	2:WL#1	0.667	815.290	0.667		-815.290	0.667	
	3:WL#4	0.667	808.710	0.667		-808.710	0.667	
	4:DI	0.667	84.020	0.667				
	5:WLI#1	0.667	386.736	0.667		-386.736	0.667	
	6:WLI#4	0.667	374.083	0.667		-374.083	0.667	
	7:WLS#1	0.667	287.474	0.667		-287.474	0.667	
	8:WLS#4	0.667	283.931	0.667		-283.931	0.667	
	9:WLM#1	0.667	80.631	0.667		-80.631	0.667	
	10:WLM#4	0.667	79.618	0.667		-79.618	0.667	
	11:LM	0.667	0.000	0.611		-0.000	0.611	
	12:LV	0.667	0.000	0.611				
	13:1.2D+1.6WI	0.667	1.32E+3	0.667		-1.29E+3	0.667	
	14:1.2D+1.6WI	0.667	1.31E+3	0.667		-1.28E+3	0.667	
	15:1.2D-1.6WL	0.667	1.32E+3	0.667		-1.29E+3	0.667	
	16:1.2D-1.6WL	0.667	1.31E+3	0.667		-1.28E+3	0.667	
	17:1.2D+1.0DI	0.667	484.240	0.667		-289.232	0.667	
	18:1.2D+1.0DI	0.667	471.587	0.667		-276.579	0.667	
	19:1.2D+1.0DI	0.667	484.240	0.667		-289.232	0.667	
	20:1.2D+1.0DI	0.667	471.587	0.667		-276.579	0.667	
	21:1.0D+1.0WI	0.667	298.711	0.667		-276.237	0.667	
	22:1.0D+1.0WI	0.667	295.168	0.667		-272.694	0.667	
	23:1.0D-1.0WL	0.667	298.711	0.667		-276.237	0.667	
	24:1.0D-1.0WL	0.667	295.168	0.667		-272.694	0.667	
	25:1.4D	0.667	15.732	0.667				
	26:1.2D+1.5LV	0.667	94.115	0.667		-67.146	0.667	
	27:1.2D+1.5LV	0.667	93.103	0.667		-66.134	0.667	
	28:1.2D+1.5LV	0.667	94.115	0.667		-67.146	0.667	
	29:1.2D+1.5LV	0.667	93.103	0.667		-66.134	0.667	
	30:1.2D+1.5LV	0.667	13.485	0.667				
128	1:DEAD	0.667	43.688	0.667				
	2:WL#1	0.667	3.83E+3	0.667		-3.83E+3	0.667	
	3:WL#4	0.667	2.57E+3	0.667		-2.57E+3	0.667	
	4:DI	0.667	285.490	0.667				
	5:WLI#1	0.667	1.5E+3	0.667		-1.5E+3	0.667	
	6:WLI#4	0.667	1.16E+3	0.667		-1.16E+3	0.667	
	7:WLS#1	0.667	1.35E+3	0.667		-1.35E+3	0.667	



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No 50103542	Sheet No 57	Rev 1
Part		
Ref		
By DAP	Date 5/13/19	Chd BK
File Rocky Hill CT.std	Date/Time 13-May-2019 16:22	

Job Title Rocky Hill CT

Client VZW

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	8:WLS#4	0.667	905.442	0.667		-905.442	0.667	
	9:WLM#1	0.667	378.733	0.667		-378.733	0.667	
	10:WLM#4	0.667	253.722	0.667		-253.722	0.667	
	11:LM	0.667				-0.000	0.000	
	12:LV	0.667	0.000	0.000		-0.000	0.000	
	13:1.2D+1.6WI	0.667	6.17E+3	0.667		-6.07E+3	0.667	
	14:1.2D+1.6WI	0.667	4.17E+3	0.667		-4.07E+3	0.667	
	15:1.2D-1.6WL	0.667	6.17E+3	0.667		-6.07E+3	0.667	
	16:1.2D-1.6WL	0.667	4.17E+3	0.667		-4.07E+3	0.667	
	17:1.2D+1.0DI	0.667	1.83E+3	0.667		-1.16E+3	0.667	
	18:1.2D+1.0DI	0.667	1.49E+3	0.667		-817.104	0.667	
	19:1.2D+1.0DI	0.667	1.83E+3	0.667		-1.16E+3	0.667	
	20:1.2D+1.0DI	0.667	1.49E+3	0.667		-817.104	0.667	
	21:1.0D+1.0WI	0.667	1.39E+3	0.667		-1.3E+3	0.667	
	22:1.0D+1.0WI	0.667	949.130	0.667		-861.754	0.667	
	23:1.0D-1.0WL	0.667	1.39E+3	0.667		-1.3E+3	0.667	
	24:1.0D-1.0WL	0.667	949.130	0.667		-861.754	0.667	
	25:1.4D	0.667	61.164	0.667				
	26:1.2D+1.5LV	0.667	431.159	0.667		-326.307	0.667	
	27:1.2D+1.5LV	0.667	306.148	0.667		-201.297	0.667	
	28:1.2D+1.5LV	0.667	431.159	0.667		-326.307	0.667	
	29:1.2D+1.5LV	0.667	306.148	0.667		-201.296	0.667	
	30:1.2D+1.5LV	0.667	52.426	0.667				
129	1:DEAD	0.667	13.688	0.667				
	2:WL#1	0.667	1.47E+3	0.667		-1.47E+3	0.667	
	3:WL#4	0.667	1.33E+3	0.667		-1.33E+3	0.667	
	4:DI	0.667	137.255	0.667				
	5:WLI#1	0.667	582.097	0.667		-582.097	0.667	
	6:WLI#4	0.667	546.163	0.667		-546.163	0.667	
	7:WLS#1	0.667	517.757	0.667		-517.757	0.667	
	8:WLS#4	0.667	466.639	0.667		-466.639	0.667	
	9:WLM#1	0.667	146.426	0.667		-146.426	0.667	
	10:WLM#4	0.667	132.255	0.667		-132.255	0.667	
	11:LM	0.667				-0.000	0.667	
	12:LV	0.667	0.000	0.611		-0.000	0.611	
	13:1.2D+1.6WI	0.667	2.37E+3	0.667		-2.34E+3	0.667	
	14:1.2D+1.6WI	0.667	2.14E+3	0.667		-2.11E+3	0.667	
	15:1.2D-1.6WL	0.667	2.37E+3	0.667		-2.34E+3	0.667	
	16:1.2D-1.6WL	0.667	2.14E+3	0.667		-2.11E+3	0.667	
	17:1.2D+1.0DI	0.667	735.778	0.667		-428.416	0.667	
	18:1.2D+1.0DI	0.667	699.844	0.667		-392.482	0.667	
	19:1.2D+1.0DI	0.667	735.778	0.667		-428.416	0.667	
	20:1.2D+1.0DI	0.667	699.844	0.667		-392.482	0.667	
	21:1.0D+1.0WI	0.667	531.445	0.667		-504.069	0.667	



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No 50103542	Sheet No 58	Rev 1
Part		
Ref		
By DAP	Date 5/13/19	Chd BK
File Rocky Hill CT.std	Date/Time 13-May-2019 16:22	

Job Title Rocky Hill CT

Client VZW

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	22:1.0D+1.0WI	0.667	480.327	0.667		-452.951	0.667	
	23:1.0D-1.0WL	0.667	531.445	0.667		-504.069	0.667	
	24:1.0D-1.0WL	0.667	480.327	0.667		-452.951	0.667	
	25:1.4D	0.667	19.164	0.667				
	26:1.2D+1.5LV	0.667	162.852	0.667		-130.000	0.667	
	27:1.2D+1.5LV	0.667	148.680	0.667		-115.829	0.667	
	28:1.2D+1.5LV	0.667	162.852	0.667		-130.000	0.667	
	29:1.2D+1.5LV	0.667	148.680	0.667		-115.829	0.667	
	30:1.2D+1.5LV	0.667	16.426	0.667				
130	1:DEAD	0.667	13.688	0.667				
	2:WL#1	0.667	1.37E+3	0.667		-1.37E+3	0.667	
	3:WL#4	0.667	1.43E+3	0.667		-1.43E+3	0.667	
	4:DI	0.667	137.255	0.667				
	5:WLI#1	0.667	559.828	0.667		-559.828	0.667	
	6:WLI#4	0.667	568.432	0.667		-568.432	0.667	
	7:WLS#1	0.667	481.823	0.667		-481.823	0.667	
	8:WLS#4	0.667	502.573	0.667		-502.573	0.667	
	9:WLM#1	0.667	135.291	0.667		-135.291	0.667	
	10:WLM#4	0.667	141.871	0.667		-141.871	0.667	
	11:LM	0.667	0.000	0.611		-0.000	0.611	
	12:LV	0.667				-0.000	0.611	
	13:1.2D+1.6WI	0.667	2.21E+3	0.667		-2.17E+3	0.667	
	14:1.2D+1.6WI	0.667	2.31E+3	0.667		-2.27E+3	0.667	
	15:1.2D-1.6WL	0.667	2.21E+3	0.667		-2.17E+3	0.667	
	16:1.2D-1.6WL	0.667	2.31E+3	0.667		-2.27E+3	0.667	
	17:1.2D+1.0DI	0.667	713.509	0.667		-406.147	0.667	
	18:1.2D+1.0DI	0.667	722.113	0.667		-414.751	0.667	
	19:1.2D+1.0DI	0.667	713.509	0.667		-406.147	0.667	
	20:1.2D+1.0DI	0.667	722.113	0.667		-414.751	0.667	
	21:1.0D+1.0WI	0.667	495.511	0.667		-468.134	0.667	
	22:1.0D+1.0WI	0.667	516.262	0.667		-488.885	0.667	
	23:1.0D-1.0WL	0.667	495.511	0.667		-468.134	0.667	
	24:1.0D-1.0WL	0.667	516.262	0.667		-488.885	0.667	
	25:1.4D	0.667	19.164	0.667				
	26:1.2D+1.5LV	0.667	151.717	0.667		-118.865	0.667	
	27:1.2D+1.5LV	0.667	158.297	0.667		-125.445	0.667	
	28:1.2D+1.5LV	0.667	151.717	0.667		-118.865	0.667	
	29:1.2D+1.5LV	0.667	158.297	0.667		-125.445	0.667	
	30:1.2D+1.5LV	0.667	16.426	0.667				
131	1:DEAD	0.667	43.688	0.667				
	2:WL#1	0.667	2.89E+3	0.667		-2.89E+3	0.667	
	3:WL#4	0.667	3.51E+3	0.667		-3.51E+3	0.667	
	4:DI	0.667	285.490	0.667				
	5:WLI#1	0.667	1.24E+3	0.667		-1.24E+3	0.667	



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No

50103542

Sheet No

59

Rev

1

Part

Job Title Rocky Hill CT

Ref

By DAP

Date 5/13/19

Chd BK

Client VZW

File Rocky Hill CT.std

Date/Time 13-May-2019 16:22

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	6:WLI#4	0.667	1.41E+3	0.667		-1.41E+3	0.667	
	7:WLS#1	0.667	1.02E+3	0.667		-1.02E+3	0.667	
	8:WLS#4	0.667	1.23E+3	0.667		-1.23E+3	0.667	
	9:WLM#1	0.667	287.126	0.667		-287.126	0.667	
	10:WLM#4	0.667	345.329	0.667		-345.329	0.667	
	11:LM	0.667	0.000	0.667		-0.000	0.667	
	12:LV	0.667				-0.000	0.667	
	13:1.2D+1.6WI	0.667	4.68E+3	0.667		-4.58E+3	0.667	
	14:1.2D+1.6WI	0.667	5.66E+3	0.667		-5.56E+3	0.667	
	15:1.2D-1.6WL	0.667	4.68E+3	0.667		-4.58E+3	0.667	
	16:1.2D-1.6WL	0.667	5.66E+3	0.667		-5.56E+3	0.667	
	17:1.2D+1.0DI	0.667	1.58E+3	0.667		-905.169	0.667	
	18:1.2D+1.0DI	0.667	1.74E+3	0.667		-1.07E+3	0.667	
	19:1.2D+1.0DI	0.667	1.58E+3	0.667		-905.169	0.667	
	20:1.2D+1.0DI	0.667	1.74E+3	0.667		-1.07E+3	0.667	
	21:1.0D+1.0WI	0.667	1.06E+3	0.667		-974.111	0.667	
	22:1.0D+1.0WI	0.667	1.28E+3	0.667		-1.19E+3	0.667	
	23:1.0D-1.0WL	0.667	1.06E+3	0.667		-974.111	0.667	
	24:1.0D-1.0WL	0.667	1.28E+3	0.667		-1.19E+3	0.667	
	25:1.4D	0.667	61.164	0.667				
	26:1.2D+1.5LM	0.667	339.552	0.667		-234.700	0.667	
	27:1.2D+1.5LM	0.667	397.755	0.667		-292.904	0.667	
	28:1.2D+1.5LM	0.667	339.552	0.667		-234.700	0.667	
	29:1.2D+1.5LM	0.667	397.755	0.667		-292.904	0.667	
	30:1.2D+1.5LV	0.667	52.426	0.667				
132	1:DEAD	0.667	13.688	0.667				
	2:WL#1	0.667	1.47E+3	0.667		-1.47E+3	0.667	
	3:WL#4	0.667	1.33E+3	0.667		-1.33E+3	0.667	
	4:DI	0.667	137.255	0.667				
	5:WLI#1	0.667	582.097	0.667		-582.097	0.667	
	6:WLI#4	0.667	546.163	0.667		-546.163	0.667	
	7:WLS#1	0.667	517.757	0.667		-517.757	0.667	
	8:WLS#4	0.667	466.639	0.667		-466.639	0.667	
	9:WLM#1	0.667	146.426	0.667		-146.426	0.667	
	10:WLM#4	0.667	132.255	0.667		-132.255	0.667	
	11:LM	0.667	0.000	0.667				
	12:LV	0.667	0.000	0.000		-0.000	0.000	
	13:1.2D+1.6WI	0.667	2.37E+3	0.667		-2.34E+3	0.667	
	14:1.2D+1.6WI	0.667	2.14E+3	0.667		-2.11E+3	0.667	
	15:1.2D-1.6WL	0.667	2.37E+3	0.667		-2.34E+3	0.667	
	16:1.2D-1.6WL	0.667	2.14E+3	0.667		-2.11E+3	0.667	
	17:1.2D+1.0DI	0.667	735.778	0.667		-428.416	0.667	
	18:1.2D+1.0DI	0.667	699.844	0.667		-392.482	0.667	
	19:1.2D+1.0DI	0.667	735.778	0.667		-428.416	0.667	



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
60

Rev
1

Job Title **Rocky Hill CT**

Part

Ref

By DAP

Date 5/13/19

Chd BK

Client **VZW**

File Rocky Hill CT.std

Date/Time 13-May-2019 16:22

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	20:1.2D+1.0DI-	0.667	699.844	0.667		-392.482	0.667	
	21:1.0D+1.0WI	0.667	531.445	0.667		-504.069	0.667	
	22:1.0D+1.0WI	0.667	480.327	0.667		-452.951	0.667	
	23:1.0D-1.0WL	0.667	531.445	0.667		-504.069	0.667	
	24:1.0D-1.0WL	0.667	480.327	0.667		-452.951	0.667	
	25:1.4D	0.667	19.164	0.667				
	26:1.2D+1.5LM	0.667	162.852	0.667		-130.000	0.667	
	27:1.2D+1.5LM	0.667	148.680	0.667		-115.829	0.667	
	28:1.2D+1.5LM	0.667	162.852	0.667		-130.000	0.667	
	29:1.2D+1.5LM	0.667	148.680	0.667		-115.829	0.667	
	30:1.2D+1.5LV	0.667	16.426	0.667				
133	1:DEAD	1.179	1.03E+3	1.179	2	-2.3E+3	1.179	1
	2:WL#1	1.179	2.86E+3	1.179	1	-1.6E+3	1.179	2
	3:WL#4	1.179	3.13E+3	1.179	1	-1.11E+3	1.179	2
	4:DI	1.179	4.55E+3	1.179	2	-9.97E+3	1.179	1
	5:WLI#1	1.179	1.34E+3	1.179	1	-749.279	1.179	2
	6:WLI#4	1.179	1.45E+3	1.179	1	-508.580	1.179	2
	7:WLS#1	1.179	1E+3	1.179	1	-562.114	1.179	2
	8:WLS#4	1.179	1.1E+3	1.179	1	-389.179	1.179	2
	9:WLM#1	1.179	287.382	1.179	1	-160.887	1.179	2
	10:WLM#4	1.179	312.997	1.179	1	-110.723	1.179	2
	11:LM	1.179	9.399	0.000	2	-19.138	1.179	1
	12:LV	1.179	18.192	1.179	2	-45.050	1.179	1
	13:1.2D+1.6WI	1.179	2.37E+3	0.000	1	-1.32E+3	1.179	2
	14:1.2D+1.6WI	1.179	2.99E+3	0.000	1	-1.14E+3	0.000	2
	15:1.2D-1.6WL	1.179	3.8E+3	1.179	2	-7.34E+3	1.179	1
	16:1.2D-1.6WL	1.179	3.01E+3	1.179	2	-7.77E+3	1.179	1
	17:1.2D+1.0DI-	1.179	5.04E+3	1.179	2	-11.4E+3	1.179	1
	18:1.2D+1.0DI-	1.179	5.28E+3	1.179	2	-11.3E+3	1.179	1
	19:1.2D+1.0DI-	1.179	6.54E+3	1.179	2	-14.1E+3	1.179	1
	20:1.2D+1.0DI-	1.179	6.3E+3	1.179	2	-14.2E+3	1.179	1
	21:1.0D+1.0WI	1.179	642.177	1.179	3	-1.3E+3	1.179	1
	22:1.0D+1.0WI	1.179	643.151	1.179	2	-1.21E+3	1.179	1
	23:1.0D-1.0WL	1.179	1.59E+3	1.179	2	-3.31E+3	1.179	1
	24:1.0D-1.0WL	1.179	1.42E+3	1.179	2	-3.4E+3	1.179	1
	25:1.4D	1.179	1.45E+3	1.179	2	-3.23E+3	1.179	1
	26:1.2D+1.5LM	1.179	1.09E+3	1.179	2	-2.51E+3	1.179	1
	27:1.2D+1.5LM	1.179	1.14E+3	1.179	2	-2.48E+3	1.179	1
	28:1.2D+1.5LM	1.179	1.41E+3	1.179	2	-3.08E+3	1.179	1
	29:1.2D+1.5LM	1.179	1.36E+3	1.179	2	-3.11E+3	1.179	1
	30:1.2D+1.5LV	1.179	1.27E+3	1.179	2	-2.83E+3	1.179	1
134	1:DEAD	1.179	1.65E+3	1.179	3	-4.04E+3	1.179	1
	2:WL#1	1.179	3.83E+3	1.179	1	-1.66E+3	1.179	2
	3:WL#4	1.179	3.49E+3	1.179	1	-1.69E+3	1.179	2



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
61

Rev
1

Part

Job Title **Rocky Hill CT**

Ref

By **DAP**

Date **5/13/19**

Chd **BK**

Client **VZW**

File **Rocky Hill CT.std**

Date/Time **13-May-2019 16:22**

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	4:DI	1.179	6.18E+3	1.179	3	-15.3E+3	1.179	1
	5:WLI#1	1.179	1.8E+3	1.179	1	-789.107	1.179	2
	6:WLI#4	1.179	1.61E+3	1.179	1	-803.014	1.179	2
	7:WLS#1	1.179	1.35E+3	1.179	1	-584.130	1.179	2
	8:WLS#4	1.179	1.23E+3	1.179	1	-592.478	1.179	2
	9:WLM#1	1.179	385.518	1.179	1	-167.345	1.179	2
	10:WLM#4	1.179	349.354	1.179	1	-169.066	1.179	2
	11:LM	1.179	8.573	0.000	2	-18.591	1.179	1
	12:LV	1.179	27.474	1.179	3	-62.689	1.179	1
	13:1.2D+1.6WI	1.179	2.4E+3	0.000	1	-885.748	1.179	2
	14:1.2D+1.6WI	1.179	2.54E+3	0.000	1	-924.391	1.179	2
	15:1.2D-1.6WL	1.179	4.44E+3	1.179	2	-11E+3	1.179	1
	16:1.2D-1.6WL	1.179	4.47E+3	1.179	2	-10.4E+3	1.179	1
	17:1.2D+1.0DI	1.179	7.81E+3	1.179	3	-18.3E+3	1.179	1
	18:1.2D+1.0DI	1.179	7.99E+3	1.179	3	-18.5E+3	1.179	1
	19:1.2D+1.0DI	1.179	8.52E+3	1.179	3	-21.9E+3	1.179	1
	20:1.2D+1.0DI	1.179	8.34E+3	1.179	2	-21.8E+3	1.179	1
	21:1.0D+1.0WI	1.179	1.36E+3	1.179	3	-2.7E+3	1.179	1
	22:1.0D+1.0WI	1.179	1.48E+3	1.179	3	-2.82E+3	1.179	1
	23:1.0D-1.0WL	1.179	2.06E+3	1.179	2	-5.39E+3	1.179	1
	24:1.0D-1.0WL	1.179	2.07E+3	1.179	2	-5.27E+3	1.179	1
	25:1.4D	1.179	2.31E+3	1.179	3	-5.66E+3	1.179	1
	26:1.2D+1.5LV	1.179	1.91E+3	1.179	3	-4.5E+3	1.179	1
	27:1.2D+1.5LV	1.179	1.95E+3	1.179	3	-4.53E+3	1.179	1
	28:1.2D+1.5LV	1.179	2.08E+3	1.179	3	-5.27E+3	1.179	1
	29:1.2D+1.5LV	1.179	2.04E+3	1.179	3	-5.23E+3	1.179	1
	30:1.2D+1.5LV	1.179	2.02E+3	1.179	3	-4.95E+3	1.179	1
135	1:DEAD	1.889	784.539	1.889	3	-1.48E+3	1.889	2
	2:WL#1	1.889	2.7E+3	1.889	2	-1.69E+3	1.889	3
	3:WL#4	1.889	2.84E+3	0.000	2	-988.057	0.000	1
	4:DI	1.889	3.78E+3	1.889	3	-7.38E+3	1.889	2
	5:WLI#1	1.889	1.27E+3	1.889	2	-828.960	1.889	3
	6:WLI#4	1.889	1.33E+3	0.000	2	-461.392	0.000	1
	7:WLS#1	1.889	947.046	1.889	2	-593.629	1.889	3
	8:WLS#4	1.889	995.587	0.000	2	-346.937	0.000	1
	9:WLM#1	1.889	271.429	1.889	2	-170.486	1.889	3
	10:WLM#4	1.889	284.321	0.000	2	-99.026	0.000	1
	11:LM	1.889	32.479	1.889	2	-18.474	0.000	2
	12:LV	1.889	8.238	1.889	3	-17.381	1.889	2
	13:1.2D+1.6WI	1.889	2.54E+3	1.889	2	-1.76E+3	1.889	3
	14:1.2D+1.6WI	1.889	5.1E+3	0.000	2	-1.74E+3	0.000	1
	15:1.2D-1.6WL	1.889	3.65E+3	1.889	3	-6.09E+3	1.889	2
	16:1.2D-1.6WL	1.889	1.51E+3	1.889	3	-4.33E+3	1.889	2
	17:1.2D+1.0DI	1.889	3.89E+3	1.889	3	-7.88E+3	1.889	2



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No 50103542	Sheet No 62	Rev 1
Part		
Ref		
By DAP	Date 5/13/19	Chd BK
File Rocky Hill CT.std	Date/Time 13-May-2019 16:22	

Job Title Rocky Hill CT

Client VZW

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	18:1.2D+1.0DI-	1.889	4.57E+3	1.889	3	-8.42E+3	1.889	2
	19:1.2D+1.0DI-	1.889	5.55E+3	1.889	3	-10.4E+3	1.889	2
	20:1.2D+1.0DI-	1.889	4.88E+3	1.889	3	-9.88E+3	1.889	2
	21:1.0D+1.0WI	1.889	190.909	1.889	3	-532.136	1.889	2
	22:1.0D+1.0WI	1.889	1.47E+3	0.000	2	-918.724	1.889	2
	23:1.0D-1.0WL	1.889	1.38E+3	1.889	3	-2.43E+3	1.889	2
	24:1.0D-1.0WL	1.889	908.393	1.889	3	-2.04E+3	1.889	2
	25:1.4D	1.889	1.1E+3	1.889	3	-2.07E+3	1.889	2
	26:1.2D+1.5LM	1.889	748.869	1.889	3	-1.45E+3	1.889	2
	27:1.2D+1.5LM	1.889	884.374	1.889	3	-1.57E+3	1.889	2
	28:1.2D+1.5LM	1.889	1.09E+3	1.889	3	-2E+3	1.889	2
	29:1.2D+1.5LM	1.889	954.337	1.889	3	-1.89E+3	1.889	2
	30:1.2D+1.5LV	1.889	953.804	1.889	3	-1.8E+3	1.889	2
136	1:DEAD	1.889	1.85E+3	1.889	3	-4.4E+3	1.889	2
	2:WL#1	1.889	6.34E+3	1.889	2	-3.34E+3	1.889	3
	3:WL#4	1.889	1.46E+3	0.000	2	-733.185	0.000	1
	4:DI	1.889	7.72E+3	1.889	3	-18.4E+3	1.889	2
	5:WLI#1	1.889	2.94E+3	1.889	2	-1.58E+3	1.889	3
	6:WLI#4	1.889	662.116	0.000	2	-336.371	0.000	1
	7:WLS#1	1.889	2.23E+3	1.889	2	-1.17E+3	1.889	3
	8:WLS#4	1.889	511.660	0.000	2	-257.499	0.000	1
	9:WLM#1	1.889	637.358	1.889	2	-336.335	1.889	3
	10:WLM#4	1.889	145.500	0.000	2	-73.294	0.000	1
	11:LM	1.889	84.014	1.889	2	-35.653	1.889	3
	12:LV	1.889	13.401	1.889	3	-28.009	1.889	2
	13:1.2D+1.6WI	1.889	4.86E+3	1.889	2	-3.13E+3	1.889	3
	14:1.2D+1.6WI	1.889	1.85E+3	1.889	1	-4.91E+3	1.889	2
	15:1.2D-1.6WL	1.889	7.57E+3	1.889	3	-15.4E+3	1.889	2
	16:1.2D-1.6WL	1.889	2.59E+3	1.889	3	-5.66E+3	1.889	2
	17:1.2D+1.0DI-	1.889	8.36E+3	1.889	3	-20.8E+3	1.889	2
	18:1.2D+1.0DI-	1.889	9.85E+3	1.889	3	-23.6E+3	1.889	2
	19:1.2D+1.0DI-	1.889	11.5E+3	1.889	3	-26.6E+3	1.889	2
	20:1.2D+1.0DI-	1.889	10E+3	1.889	3	-23.8E+3	1.889	2
	21:1.0D+1.0WI	1.889	698.284	1.889	1	-2.18E+3	1.889	2
	22:1.0D+1.0WI	1.889	1.77E+3	1.889	3	-4.32E+3	1.889	2
	23:1.0D-1.0WL	1.889	3.02E+3	1.889	3	-6.63E+3	1.889	2
	24:1.0D-1.0WL	1.889	1.93E+3	1.889	3	-4.49E+3	1.889	2
	25:1.4D	1.889	2.59E+3	1.889	3	-6.17E+3	1.889	2
	26:1.2D+1.5LM	1.889	1.83E+3	1.889	3	-4.52E+3	1.889	2
	27:1.2D+1.5LM	1.889	2.14E+3	1.889	3	-5.14E+3	1.889	2
	28:1.2D+1.5LM	1.889	2.5E+3	1.889	3	-5.8E+3	1.889	2
	29:1.2D+1.5LM	1.889	2.19E+3	1.889	3	-5.18E+3	1.889	2
	30:1.2D+1.5LV	1.889	2.24E+3	1.889	3	-5.33E+3	1.889	2
137	1:DEAD	1.889	765.005	0.000	1	-1.44E+3	0.000	2

 Software licensed to DEWBERRY CONNECTED User: Deep Patel	Job No 50103542	Sheet No 63	Rev 1
	Part		
Job Title Rocky Hill CT	Ref		
	By DAP	Date 5/13/19	Chd BK
Client VZW	File Rocky Hill CT.std	Date/Time 13-May-2019 16:22	

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	2:WL#1	1.889	2.68E+3	0.000	2	-1.67E+3	0.000	1
	3:WL#4	1.889	992.660	1.889	1	-2.84E+3	1.889	2
	4:DI	1.889	3.53E+3	0.000	1	-6.87E+3	0.000	2
	5:WLI#1	1.889	1.28E+3	0.000	2	-827.638	0.000	1
	6:WLI#4	1.889	462.749	1.889	1	-1.33E+3	1.889	2
	7:WLS#1	1.889	940.881	0.000	2	-586.260	0.000	1
	8:WLS#4	1.889	348.553	1.889	1	-997.860	1.889	2
	9:WLM#1	1.889	269.883	0.000	2	-168.549	0.000	1
	10:WLM#4	1.889	99.488	1.889	1	-284.975	1.889	2
	11:LM	1.889	32.477	0.000	2	-18.482	1.889	2
	12:LV	1.889	8.119	0.000	2	-3.296	0.000	1
	13:1.2D+1.6WI	1.889	2.56E+3	0.000	2	-1.75E+3	0.000	1
	14:1.2D+1.6WI	1.889	1.46E+3	1.889	1	-4.24E+3	0.000	2
	15:1.2D-1.6WL	1.889	3.59E+3	0.000	1	-6.01E+3	0.000	2
	16:1.2D-1.6WL	1.889	5.13E+3	1.889	2	-1.75E+3	1.889	1
	17:1.2D+1.0DI	1.889	3.62E+3	0.000	1	-7.32E+3	0.000	2
	18:1.2D+1.0DI	1.889	4.6E+3	0.000	1	-9.32E+3	0.000	2
	19:1.2D+1.0DI	1.889	5.28E+3	0.000	1	-9.88E+3	0.000	2
	20:1.2D+1.0DI	1.889	4.3E+3	0.000	1	-7.88E+3	0.000	2
	21:1.0D+1.0WI	1.889	178.745	0.000	1	-498.654	0.000	2
	22:1.0D+1.0WI	1.889	884.654	0.000	1	-1.99E+3	0.000	2
	23:1.0D-1.0WL	1.889	1.35E+3	0.000	1	-2.38E+3	0.000	2
	24:1.0D-1.0WL	1.889	1.48E+3	1.889	2	-888.288	0.000	2
	25:1.4D	1.889	1.07E+3	0.000	1	-2.02E+3	0.000	2
	26:1.2D+1.5LM	1.889	727.356	0.000	1	-1.41E+3	0.000	2
	27:1.2D+1.5LM	1.889	929.690	0.000	1	-1.84E+3	0.000	2
	28:1.2D+1.5LM	1.889	1.06E+3	0.000	1	-1.95E+3	0.000	2
	29:1.2D+1.5LM	1.889	862.121	0.000	1	-1.52E+3	0.000	2
	30:1.2D+1.5LV	1.889	913.433	0.000	1	-1.72E+3	0.000	2
138	1:DEAD	1.889	1.98E+3	1.889	2	-799.789	1.889	3
	2:WL#1	1.889	1.93E+3	1.889	3	-5.09E+3	1.889	2
	3:WL#4	1.889	1.55E+3	1.889	3	-4.11E+3	1.889	2
	4:DI	1.889	9.55E+3	1.889	2	-3.89E+3	1.889	3
	5:WLI#1	1.889	865.244	1.889	1	-2.4E+3	1.889	2
	6:WLI#4	1.889	733.382	1.889	3	-1.94E+3	1.889	2
	7:WLS#1	1.889	679.015	1.889	3	-1.79E+3	1.889	2
	8:WLS#4	1.889	545.743	1.889	3	-1.44E+3	1.889	2
	9:WLM#1	1.889	193.844	1.889	3	-512.550	1.889	2
	10:WLM#4	1.889	156.132	1.889	3	-413.155	1.889	2
	11:LM	1.889	27.045	1.889	3	-69.441	1.889	2
	12:LV	1.889	5.334	0.000	2	-2.092	0.000	1
	13:1.2D+1.6WI	1.889	2.13E+3	1.889	3	-5.77E+3	1.889	2
	14:1.2D+1.6WI	1.889	1.53E+3	1.889	3	-4.2E+3	1.889	2
	15:1.2D-1.6WL	1.889	10.5E+3	1.889	2	-4.05E+3	1.889	3



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
64

Rev
1

Job Title Rocky Hill CT

Part

Ref

By DAP

Date 5/13/19

Chd BK

Client VZW

File Rocky Hill CT.std

Date/Time 13-May-2019 16:22

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	16:1.2D-1.6WL	1.889	8.96E+3	1.889	2	-3.45E+3	1.889	3
	17:1.2D+1.0DI	1.889	9.54E+3	1.889	2	-3.98E+3	1.889	3
	18:1.2D+1.0DI	1.889	9.99E+3	1.889	2	-4.11E+3	1.889	3
	19:1.2D+1.0DI	1.889	14.3E+3	1.889	2	-5.71E+3	1.889	3
	20:1.2D+1.0DI	1.889	13.9E+3	1.889	2	-5.58E+3	1.889	3
	21:1.0D+1.0WI	1.889	193.202	1.889	2	-120.774	1.889	3
	22:1.0D+1.0WI	1.889	538.436	1.889	2	-511.255	0.000	2
	23:1.0D-1.0WL	1.889	3.77E+3	1.889	2	-1.48E+3	1.889	3
	24:1.0D-1.0WL	1.889	3.43E+3	1.889	2	-1.35E+3	1.889	3
	25:1.4D	1.889	2.78E+3	1.889	2	-1.12E+3	1.889	3
	26:1.2D+1.5LM	1.889	1.76E+3	1.889	2	-725.335	1.889	3
	27:1.2D+1.5LM	1.889	1.86E+3	1.889	2	-763.047	1.889	3
	28:1.2D+1.5LM	1.889	2.79E+3	1.889	2	-1.11E+3	1.889	3
	29:1.2D+1.5LM	1.889	2.69E+3	1.889	2	-1.08E+3	1.889	3
	30:1.2D+1.5LV	1.889	2.38E+3	1.889	2	-961.449	1.889	3
139	1:DEAD	1.179	997.339	0.000	2	-2.25E+3	0.000	1
	2:WL#1	1.179	2.9E+3	0.000	1	-1.57E+3	0.000	2
	3:WL#4	1.179	1.07E+3	0.000	2	-3.1E+3	0.000	1
	4:DI	1.179	4.13E+3	0.000	2	-9.12E+3	0.000	1
	5:WLI#1	1.179	1.35E+3	0.000	1	-742.324	0.000	2
	6:WLI#4	1.179	489.699	0.000	2	-1.44E+3	0.000	1
	7:WLS#1	1.179	1.02E+3	0.000	1	-551.339	0.000	2
	8:WLS#4	1.179	375.004	0.000	2	-1.09E+3	0.000	1
	9:WLM#1	1.179	291.080	0.000	1	-157.966	0.000	2
	10:WLM#4	1.179	106.684	0.000	2	-310.039	0.000	1
	11:LM	1.179	9.426	1.179	2	-19.147	0.000	1
	12:LV	1.179	14.261	0.000	1	-5.779	0.000	2
	13:1.2D+1.6WI	1.179	2.5E+3	1.179	1	-1.31E+3	0.000	2
	14:1.2D+1.6WI	1.179	2.91E+3	0.000	2	-7.65E+3	0.000	1
	15:1.2D-1.6WL	1.179	3.71E+3	0.000	2	-7.33E+3	0.000	1
	16:1.2D-1.6WL	1.179	3E+3	1.179	1	-1.22E+3	1.179	2
	17:1.2D+1.0DI	1.179	4.59E+3	0.000	2	-10.5E+3	0.000	1
	18:1.2D+1.0DI	1.179	5.82E+3	0.000	2	-13.3E+3	0.000	1
	19:1.2D+1.0DI	1.179	6.07E+3	0.000	2	-13.2E+3	0.000	1
	20:1.2D+1.0DI	1.179	4.84E+3	0.000	2	-10.4E+3	0.000	1
	21:1.0D+1.0WI	1.179	643.038	0.000	2	-1.23E+3	0.000	1
	22:1.0D+1.0WI	1.179	1.37E+3	0.000	2	-3.34E+3	0.000	1
	23:1.0D-1.0WL	1.179	1.55E+3	0.000	2	-3.26E+3	0.000	1
	24:1.0D-1.0WL	1.179	622.335	0.000	2	-1.16E+3	0.000	1
	25:1.4D	1.179	1.4E+3	0.000	2	-3.15E+3	0.000	1
	26:1.2D+1.5LM	1.179	1.05E+3	0.000	2	-2.43E+3	0.000	1
	27:1.2D+1.5LM	1.179	1.31E+3	0.000	2	-3.04E+3	0.000	1
	28:1.2D+1.5LM	1.179	1.36E+3	0.000	2	-3.02E+3	0.000	1
	29:1.2D+1.5LM	1.179	1.1E+3	0.000	2	-2.42E+3	0.000	1



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
65

Rev
1

Job Title **Rocky Hill CT**

Part

Ref

By **DAP**

Date **5/13/19**

Chd **BK**

Client **VZW**

File **Rocky Hill CT.std**

Date/Time **13-May-2019 16:22**

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
140	30:1.2D+1.5LV	1.179	1.19E+3	0.000	2	-2.68E+3	0.000	1
	1:DEAD	1.179	712.606	0.000	2	-1.03E+3	0.000	1
	2:WL#1	1.179	1.8E+3	0.000	1	-1.7E+3	0.000	2
	3:WL#4	1.179	1.14E+3	0.000	2	-2.64E+3	0.000	1
	4:DI	1.179	3.34E+3	0.000	2	-5.1E+3	0.000	1
	5:WLI#1	1.179	839.006	0.000	1	-798.269	0.000	2
	6:WLI#4	1.179	522.970	0.000	2	-1.22E+3	0.000	1
	7:WLS#1	1.179	633.551	0.000	1	-597.420	0.000	2
	8:WLS#4	1.179	401.438	0.000	2	-927.184	0.000	1
	9:WLM#1	1.179	181.342	0.000	1	-171.047	0.000	2
	10:WLM#4	1.179	114.418	0.000	2	-264.374	0.000	1
	11:LM	1.179	9.480	0.000	2	-20.894	0.000	1
	12:LV	1.179	12.357	0.000	1	-5.038	0.000	2
	13:1.2D+1.6WI	1.179	1.8E+3	1.080	1	-1.87E+3	0.000	2
	14:1.2D+1.6WI	1.179	2.3E+3	0.000	2	-5.46E+3	0.000	1
	15:1.2D-1.6WL	1.179	3.58E+3	0.000	2	-4.13E+3	0.000	1
	16:1.2D-1.6WL	1.179	3.17E+3	1.179	1	-1.51E+3	0.000	2
	17:1.2D+1.0DI	1.179	3.4E+3	0.000	2	-5.5E+3	0.000	1
	18:1.2D+1.0DI	1.179	4.62E+3	0.000	2	-7.56E+3	0.000	1
	19:1.2D+1.0DI	1.179	5E+3	0.000	2	-7.18E+3	0.000	1
	20:1.2D+1.0DI	1.179	3.78E+3	0.000	2	-5.12E+3	0.000	1
	21:1.0D+1.0WI	1.179	211.486	0.000	2	-399.539	0.000	1
	22:1.0D+1.0WI	1.179	1.03E+3	0.000	2	-1.96E+3	0.000	1
	23:1.0D-1.0WL	1.179	1.31E+3	0.000	2	-1.67E+3	0.000	1
	24:1.0D-1.0WL	1.179	421.150	1.179	1	-236.142	1.179	2
	25:1.4D	1.179	997.649	0.000	2	-1.45E+3	0.000	1
	26:1.2D+1.5LV	1.179	693.107	0.000	2	-1.09E+3	0.000	1
	27:1.2D+1.5LV	1.179	954.319	0.000	2	-1.54E+3	0.000	1
	28:1.2D+1.5LV	1.179	1.04E+3	0.000	2	-1.45E+3	0.000	1
	29:1.2D+1.5LV	1.179	773.989	0.000	2	-1.01E+3	0.000	1
	30:1.2D+1.5LV	1.179	849.651	0.000	2	-1.22E+3	0.000	1
141	1:DEAD	1.889	784.254	0.000	1	-1.48E+3	0.000	2
	2:WL#1	1.889	3.3E+3	1.889	2	-1.12E+3	1.889	1
	3:WL#4	1.889	3.07E+3	0.000	2	-1.6E+3	0.000	1
	4:DI	1.889	3.77E+3	0.000	1	-7.39E+3	0.000	2
	5:WLI#1	1.889	1.53E+3	1.889	2	-523.111	1.889	3
	6:WLI#4	1.889	1.43E+3	0.000	2	-774.309	0.000	1
	7:WLS#1	1.889	1.16E+3	1.889	2	-392.365	1.889	1
	8:WLS#4	1.889	1.08E+3	0.000	2	-562.541	0.000	1
	9:WLM#1	1.889	331.906	1.889	2	-112.441	1.889	1
	10:WLM#4	1.889	307.799	0.000	2	-160.933	0.000	1
	11:LM	1.889	16.476	0.000	1	-34.761	0.000	2
	12:LV	1.889	16.239	0.000	2	-9.238	1.889	2
	13:1.2D+1.6WI	1.889	5.85E+3	1.889	2	-2.01E+3	1.889	3



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No 50103542	Sheet No 66	Rev 1
Part		
Ref		
By DAP	Date 5/13/19	Chd BK
File Rocky Hill CT.std	Date/Time 13-May-2019 16:22	

Job Title Rocky Hill CT

Client VZW

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	14:1.2D+1.6WI	1.889	3.14E+3	0.000	2	-1.62E+3	0.000	1
	15:1.2D-1.6WL	1.889	1.57E+3	1.889	1	-4.72E+3	1.889	2
	16:1.2D-1.6WL	1.889	3.5E+3	0.000	1	-6.69E+3	0.000	2
	17:1.2D+1.0DI	1.889	4.99E+3	0.000	1	-9.15E+3	0.000	2
	18:1.2D+1.0DI	1.889	3.94E+3	0.000	1	-7.74E+3	0.000	2
	19:1.2D+1.0DI	1.889	4.43E+3	0.000	1	-9.19E+3	0.000	2
	20:1.2D+1.0DI	1.889	5.49E+3	0.000	1	-10.6E+3	0.000	2
	21:1.0D+1.0WI	1.889	1.63E+3	1.889	2	-1.45E+3	0.000	2
	22:1.0D+1.0WI	1.889	568.800	1.889	2	-399.457	0.000	2
	23:1.0D-1.0WL	1.889	596.621	0.000	1	-1.5E+3	0.000	2
	24:1.0D-1.0WL	1.889	1.35E+3	0.000	1	-2.56E+3	0.000	2
	25:1.4D	1.889	1.1E+3	0.000	1	-2.07E+3	0.000	2
	26:1.2D+1.5LM	1.889	1.02E+3	0.000	1	-1.82E+3	0.000	2
	27:1.2D+1.5LM	1.889	804.886	0.000	1	-1.52E+3	0.000	2
	28:1.2D+1.5LM	1.889	911.615	0.000	1	-1.83E+3	0.000	2
	29:1.2D+1.5LM	1.889	1.13E+3	0.000	1	-2.13E+3	0.000	2
	30:1.2D+1.5LV	1.889	930.059	0.000	1	-1.75E+3	0.000	2
142	1:DEAD	1.889	1.99E+3	1.889	2	-800.684	1.889	3
	2:WL#1	1.889	6.42E+3	1.889	2	-2.42E+3	1.889	3
	3:WL#4	1.889	867.881	1.889	3	-2.32E+3	1.889	2
	4:DI	1.889	9.62E+3	1.889	2	-3.92E+3	1.889	3
	5:WLI#1	1.889	2.97E+3	1.889	2	-1.1E+3	1.889	3
	6:WLI#4	1.889	399.138	1.889	1	-1.05E+3	1.889	2
	7:WLS#1	1.889	2.25E+3	1.889	2	-851.221	1.889	3
	8:WLS#4	1.889	304.988	1.889	3	-814.615	1.889	2
	9:WLM#1	1.889	645.247	1.889	2	-243.457	1.889	3
	10:WLM#4	1.889	86.229	1.889	3	-232.045	1.889	2
	11:LM	1.889	10.518	1.889	2	-12.121	0.000	2
	12:LV	1.889	13.523	1.889	3	-34.714	1.889	2
	13:1.2D+1.6WI	1.889	12.7E+3	1.889	2	-4.84E+3	1.889	3
	14:1.2D+1.6WI	1.889	1.01E+3	0.000	2	-1.32E+3	1.889	2
	15:1.2D-1.6WL	1.889	2.92E+3	1.889	3	-7.88E+3	1.889	2
	16:1.2D-1.6WL	1.889	6.1E+3	1.889	2	-2.35E+3	1.889	3
	17:1.2D+1.0DI	1.889	15E+3	1.889	2	-5.98E+3	1.889	3
	18:1.2D+1.0DI	1.889	11E+3	1.889	2	-4.52E+3	1.889	3
	19:1.2D+1.0DI	1.889	9.03E+3	1.889	2	-3.78E+3	1.889	3
	20:1.2D+1.0DI	1.889	13.1E+3	1.889	2	-5.23E+3	1.889	3
	21:1.0D+1.0WI	1.889	4.24E+3	1.889	2	-1.65E+3	1.889	3
	22:1.0D+1.0WI	1.889	1.18E+3	1.889	2	-495.696	1.889	3
	23:1.0D-1.0WL	1.889	256.002	0.000	1	-688.827	0.000	2
	24:1.0D-1.0WL	1.889	2.8E+3	1.889	2	-1.11E+3	1.889	3
	25:1.4D	1.889	2.79E+3	1.889	2	-1.12E+3	1.889	3
	26:1.2D+1.5LM	1.889	3.05E+3	1.889	2	-1.21E+3	1.889	3
	27:1.2D+1.5LM	1.889	2.17E+3	1.889	2	-881.555	1.889	3



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No 50103542	Sheet No 67	Rev 1
Part		
Ref		
By DAP	Date 5/13/19	Chd BK
Client VZW	File Rocky Hill CT.std	Date/Time 13-May-2019 16:22

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	28:1.2D+1.5LM	1.889	1.76E+3	1.889	2	-724.326	1.889	3
	29:1.2D+1.5LM	1.889	2.64E+3	1.889	2	-1.05E+3	1.889	3
	30:1.2D+1.5LV	1.889	2.34E+3	1.889	2	-940.538	1.889	3
143	1:DEAD	1.179	1.03E+3	0.000	2	-2.3E+3	0.000	1
	2:WL#1	1.179	1.36E+3	0.000	1	-758.770	1.179	2
	3:WL#4	1.179	4.02E+3	0.000	1	-1.91E+3	0.000	2
	4:DI	1.179	4.53E+3	0.000	2	-9.96E+3	0.000	1
	5:WLI#1	1.179	618.672	0.000	1	-357.021	1.179	2
	6:WLI#4	1.179	1.85E+3	0.000	1	-889.260	0.000	2
	7:WLS#1	1.179	479.119	0.000	1	-266.510	1.179	2
	8:WLS#4	1.179	1.41E+3	0.000	1	-669.747	0.000	2
	9:WLM#1	1.179	136.775	0.000	1	-76.443	1.179	2
	10:WLM#4	1.179	401.935	0.000	1	-191.034	0.000	2
	11:LM	1.179	36.382	0.000	2	-90.098	0.000	1
	12:LV	1.179	4.702	1.179	2	-9.569	0.000	1
	13:1.2D+1.6WI	1.179	948.868	0.000	2	-874.152	1.179	2
	14:1.2D+1.6WI	1.179	4.06E+3	1.179	1	-1.81E+3	0.000	2
	15:1.2D-1.6WL	1.179	1.89E+3	0.000	2	-4.95E+3	0.000	1
	16:1.2D-1.6WL	1.179	4.29E+3	0.000	2	-9.19E+3	0.000	1
	17:1.2D+1.0DI	1.179	5.69E+3	0.000	2	-12.1E+3	0.000	1
	18:1.2D+1.0DI	1.179	4.88E+3	0.000	2	-10.9E+3	0.000	1
	19:1.2D+1.0DI	1.179	5.84E+3	0.000	2	-13.3E+3	0.000	1
	20:1.2D+1.0DI	1.179	6.66E+3	0.000	2	-14.6E+3	0.000	1
	21:1.0D+1.0WI	1.179	968.241	0.000	2	-1.83E+3	0.000	1
	22:1.0D+1.0WI	1.179	518.477	0.000	2	-893.690	0.000	1
	23:1.0D-1.0WL	1.179	1.1E+3	0.000	2	-2.78E+3	0.000	1
	24:1.0D-1.0WL	1.179	1.7E+3	0.000	2	-3.71E+3	0.000	1
	25:1.4D	1.179	1.44E+3	0.000	2	-3.23E+3	0.000	1
	26:1.2D+1.5LM	1.179	1.27E+3	0.000	2	-2.76E+3	0.000	1
	27:1.2D+1.5LM	1.179	1.1E+3	0.000	2	-2.5E+3	0.000	1
	28:1.2D+1.5LM	1.179	1.31E+3	0.000	2	-3.04E+3	0.000	1
	29:1.2D+1.5LM	1.179	1.48E+3	0.000	2	-3.3E+3	0.000	1
	30:1.2D+1.5LV	1.179	1.24E+3	0.000	2	-2.78E+3	0.000	1
144	1:DEAD	1.179	726.061	0.000	2	-1.09E+3	0.000	1
	2:WL#1	1.179	1.51E+3	0.000	1	-890.800	0.000	3
	3:WL#4	1.179	2.89E+3	0.000	1	-1.86E+3	0.000	2
	4:DI	1.179	3.63E+3	0.000	2	-5.82E+3	0.000	1
	5:WLI#1	1.179	691.677	0.000	1	-419.075	0.000	3
	6:WLI#4	1.179	1.33E+3	0.000	1	-867.721	0.000	2
	7:WLS#1	1.179	529.535	0.000	1	-312.893	0.000	3
	8:WLS#4	1.179	1.01E+3	0.000	1	-653.979	0.000	2
	9:WLM#1	1.179	151.395	0.000	1	-89.685	0.000	3
	10:WLM#4	1.179	288.912	0.000	1	-186.469	0.000	2
	11:LM	1.179	24.415	0.000	2	-56.318	0.000	1



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
68

Rev
1

Job Title **Rocky Hill CT**

Part

Ref

By **DAP**

Date **5/13/19**

Chd **BK**

Client **VZW**

File **Rocky Hill CT.std**

Date/Time **13-May-2019 16:22**

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	12:LV	1.179	4.725	0.000	2	-10.435	0.000	1
	13:1.2D+1.6WI	1.179	1.66E+3	1.179	1	-1.09E+3	0.000	3
	14:1.2D+1.6WI	1.179	3.32E+3	0.196	1	-2.11E+3	0.000	2
	15:1.2D-1.6WL	1.179	1.76E+3	0.000	2	-3.72E+3	0.000	1
	16:1.2D-1.6WL	1.179	3.85E+3	0.000	2	-5.92E+3	0.000	1
	17:1.2D+1.0DI	1.179	4.54E+3	0.000	2	-6.43E+3	0.000	1
	18:1.2D+1.0DI	1.179	3.63E+3	0.000	2	-5.8E+3	0.000	1
	19:1.2D+1.0DI	1.179	4.46E+3	0.000	2	-7.81E+3	0.000	1
	20:1.2D+1.0DI	1.179	5.37E+3	0.000	2	-8.45E+3	0.000	1
	21:1.0D+1.0WI	1.179	755.489	0.000	2	-557.228	0.000	1
	22:1.0D+1.0WI	1.179	398.869	1.179	1	-166.089	1.179	3
	23:1.0D-1.0WL	1.179	696.634	0.000	2	-1.62E+3	0.000	1
	24:1.0D-1.0WL	1.179	1.38E+3	0.000	2	-2.1E+3	0.000	1
	25:1.4D	1.179	1.02E+3	0.000	2	-1.52E+3	0.000	1
	26:1.2D+1.5LM	1.179	916.485	0.000	2	-1.24E+3	0.000	1
	27:1.2D+1.5LM	1.179	721.427	0.000	2	-1.1E+3	0.000	1
	28:1.2D+1.5LM	1.179	899.306	0.000	2	-1.54E+3	0.000	1
	29:1.2D+1.5LM	1.179	1.09E+3	0.000	2	-1.68E+3	0.000	1
	30:1.2D+1.5LV	1.179	875.771	0.000	2	-1.32E+3	0.000	1
145	1:DEAD	1.889	766.253	1.889	3	-1.44E+3	1.889	2
	2:WL#1	1.889	1.14E+3	1.889	3	-2.74E+3	1.889	2
	3:WL#4	1.889	1.47E+3	1.889	2	-2.64E+3	0.000	2
	4:DI	1.889	3.52E+3	1.889	3	-6.84E+3	1.889	2
	5:WLI#1	1.889	550.564	1.889	3	-1.29E+3	1.889	2
	6:WLI#4	1.889	690.770	1.889	2	-1.22E+3	0.000	2
	7:WLS#1	1.889	398.908	1.889	3	-962.127	1.889	2
	8:WLS#4	1.889	514.971	1.889	2	-927.766	0.000	2
	9:WLM#1	1.889	114.446	1.889	3	-275.550	1.889	2
	10:WLM#4	1.889	147.224	1.889	2	-264.306	0.000	2
	11:LM	1.889	16.261	1.889	2	-6.570	1.889	1
	12:LV	1.889	16.241	1.889	2	-9.236	0.000	2
	13:1.2D+1.6WI	1.889	2.74E+3	1.889	3	-6.11E+3	1.889	2
	14:1.2D+1.6WI	1.889	1.25E+3	0.000	1	-3.64E+3	0.000	2
	15:1.2D-1.6WL	1.889	3.66E+3	0.000	2	-1.42E+3	0.000	1
	16:1.2D-1.6WL	1.889	4.81E+3	0.000	2	-4.07E+3	1.889	2
	17:1.2D+1.0DI	1.889	4.99E+3	1.889	3	-9.86E+3	1.889	2
	18:1.2D+1.0DI	1.889	3.83E+3	1.889	3	-7.87E+3	1.889	2
	19:1.2D+1.0DI	1.889	3.89E+3	1.889	3	-7.27E+3	1.889	2
	20:1.2D+1.0DI	1.889	5.06E+3	1.889	3	-9.25E+3	1.889	2
	21:1.0D+1.0WI	1.889	1.17E+3	1.889	3	-2.4E+3	1.889	2
	22:1.0D+1.0WI	1.889	330.505	1.889	3	-923.222	1.889	2
	23:1.0D-1.0WL	1.889	1.16E+3	0.000	2	-476.066	1.889	2
	24:1.0D-1.0WL	1.889	1.42E+3	0.000	2	-1.95E+3	1.889	2
	25:1.4D	1.889	1.07E+3	1.889	3	-2.01E+3	1.889	2



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No 50103542	Sheet No 69	Rev 1
Part		
Ref		
By DAP	Date 5/13/19	Chd BK
File Rocky Hill CT.std	Date/Time 13-May-2019 16:22	

Job Title Rocky Hill CT

Client VZW

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	26:1.2D+1.5LV	1.889	1.02E+3	1.889	3	-1.98E+3	1.889	2
	27:1.2D+1.5LV	1.889	785.436	1.889	3	-1.55E+3	1.889	2
	28:1.2D+1.5LV	1.889	795.947	1.889	3	-1.43E+3	1.889	2
	29:1.2D+1.5LV	1.889	1.04E+3	1.889	3	-1.85E+3	1.889	2
	30:1.2D+1.5LV	1.889	908.457	1.889	3	-1.7E+3	1.889	2
146	1:DEAD	1.889	1.82E+3	1.889	3	-4.34E+3	1.889	2
	2:WL#1	1.889	1.8E+3	1.889	3	-3.19E+3	1.889	2
	3:WL#4	1.889	5.21E+3	1.889	2	-2.68E+3	1.889	3
	4:DI	1.889	7.35E+3	1.889	3	-17.7E+3	1.889	2
	5:WLI#1	1.889	856.424	1.889	3	-1.5E+3	1.889	2
	6:WLI#4	1.889	2.4E+3	1.889	2	-1.26E+3	1.889	3
	7:WLS#1	1.889	632.526	1.889	3	-1.12E+3	1.889	2
	8:WLS#4	1.889	1.83E+3	1.889	2	-939.209	1.889	3
	9:WLM#1	1.889	180.959	1.889	3	-320.252	1.889	2
	10:WLM#4	1.889	521.169	1.889	2	-268.224	1.889	3
	11:LM	1.889	22.199	1.889	2	-10.870	1.889	3
	12:LV	1.889	42.002	1.889	2	-17.825	1.889	3
	13:1.2D+1.6WI	1.889	5.06E+3	1.889	3	-10.3E+3	1.889	2
	14:1.2D+1.6WI	1.889	3.12E+3	1.889	2	-2.1E+3	1.889	3
	15:1.2D-1.6WL	1.889	2.16E+3	0.000	2	-1.47E+3	0.000	1
	16:1.2D-1.6WL	1.889	6.46E+3	1.889	3	-13.5E+3	1.889	2
	17:1.2D+1.0DI	1.889	10.4E+3	1.889	3	-24.4E+3	1.889	2
	18:1.2D+1.0DI	1.889	8.27E+3	1.889	3	-20.5E+3	1.889	2
	19:1.2D+1.0DI	1.889	8.67E+3	1.889	3	-21.4E+3	1.889	2
	20:1.2D+1.0DI	1.889	10.8E+3	1.889	3	-25.3E+3	1.889	2
	21:1.0D+1.0WI	1.889	2.45E+3	1.889	3	-5.46E+3	1.889	2
	22:1.0D+1.0WI	1.889	879.461	1.889	1	-2.51E+3	1.889	2
	23:1.0D-1.0WL	1.889	1.19E+3	1.889	1	-3.22E+3	1.889	2
	24:1.0D-1.0WL	1.889	2.76E+3	1.889	3	-6.17E+3	1.889	2
	25:1.4D	1.889	2.55E+3	1.889	3	-6.07E+3	1.889	2
	26:1.2D+1.5LV	1.889	2.35E+3	1.889	3	-5.49E+3	1.889	2
	27:1.2D+1.5LV	1.889	1.9E+3	1.889	3	-4.65E+3	1.889	2
	28:1.2D+1.5LV	1.889	1.99E+3	1.889	3	-4.85E+3	1.889	2
	29:1.2D+1.5LV	1.889	2.43E+3	1.889	3	-5.69E+3	1.889	2
	30:1.2D+1.5LV	1.889	2.16E+3	1.889	3	-5.14E+3	1.889	2
147	1:DEAD	1.179	1E+3	1.179	2	-2.25E+3	1.179	1
	2:WL#1	1.179	1.73E+3	1.179	2	-4.19E+3	1.179	1
	3:WL#4	1.179	850.681	1.179	1	-792.236	1.179	2
	4:DI	1.179	4.15E+3	1.179	2	-9.15E+3	1.179	1
	5:WLI#1	1.179	817.495	1.179	2	-1.96E+3	1.179	1
	6:WLI#4	1.179	401.843	1.179	1	-373.912	1.179	2
	7:WLS#1	1.179	607.981	1.179	2	-1.47E+3	1.179	1
	8:WLS#4	1.179	298.658	1.179	1	-278.122	1.179	2
	9:WLM#1	1.179	174.062	1.179	2	-421.116	1.179	1



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
70

Rev
1

Job Title **Rocky Hill CT**

Part

Ref

By **DAP**

Date **5/13/19**

Chd **BK**

Client **VZW**

File **Rocky Hill CT.std**

Date/Time **13-May-2019 16:22**

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	10:WLM#4	1.179	85.371	1.179	1	-79.482	1.179	2
	11:LM	1.179	28.545	1.179	1	-11.595	1.179	3
	12:LV	1.179	4.677	0.000	2	-9.555	1.179	1
	13:1.2D+1.6WI	1.179	3.97E+3	1.179	2	-9.4E+3	1.179	1
	14:1.2D+1.6WI	1.179	997.485	1.179	3	-1.34E+3	1.179	1
	15:1.2D-1.6WL	1.179	4.45E+3	0.000	1	-1.57E+3	1.179	2
	16:1.2D-1.6WL	1.179	2.47E+3	1.179	2	-4.06E+3	1.179	1
	17:1.2D+1.0DI	1.179	6.17E+3	1.179	2	-13.8E+3	1.179	1
	18:1.2D+1.0DI	1.179	4.97E+3	1.179	2	-11.4E+3	1.179	1
	19:1.2D+1.0DI	1.179	4.53E+3	1.179	2	-9.88E+3	1.179	1
	20:1.2D+1.0DI	1.179	5.72E+3	1.179	2	-12.3E+3	1.179	1
	21:1.0D+1.0WI	1.179	1.61E+3	1.179	2	-3.72E+3	1.179	1
	22:1.0D+1.0WI	1.179	827.598	1.179	3	-1.95E+3	1.179	1
	23:1.0D-1.0WL	1.179	442.760	1.179	3	-776.350	1.179	1
	24:1.0D-1.0WL	1.179	1.28E+3	1.179	2	-2.55E+3	1.179	1
	25:1.4D	1.179	1.4E+3	1.179	2	-3.15E+3	1.179	1
	26:1.2D+1.5LV	1.179	1.36E+3	1.179	2	-3.07E+3	1.179	1
	27:1.2D+1.5LV	1.179	1.11E+3	1.179	2	-2.57E+3	1.179	1
	28:1.2D+1.5LV	1.179	1.01E+3	1.179	2	-2.23E+3	1.179	1
	29:1.2D+1.5LV	1.179	1.26E+3	1.179	2	-2.74E+3	1.179	1
	30:1.2D+1.5LV	1.179	1.21E+3	1.179	2	-2.71E+3	1.179	1
148	1:DEAD	1.179	1.62E+3	1.179	3	-3.97E+3	1.179	1
	2:WL#1	1.179	2.35E+3	1.179	2	-4.97E+3	1.179	1
	3:WL#4	1.179	1.49E+3	1.179	1	-561.860	1.179	2
	4:DI	1.179	5.73E+3	1.179	3	-14.3E+3	1.179	1
	5:WLI#1	1.179	1.12E+3	1.179	2	-2.33E+3	1.179	1
	6:WLI#4	1.179	701.426	1.179	1	-267.662	1.179	2
	7:WLS#1	1.179	825.458	1.179	2	-1.75E+3	1.179	1
	8:WLS#4	1.179	523.013	1.179	1	-197.244	1.179	2
	9:WLM#1	1.179	236.282	1.179	2	-499.612	1.179	1
	10:WLM#4	1.179	149.432	1.179	1	-56.528	1.179	2
	11:LM	1.179	33.251	1.179	1	-19.179	1.179	3
	12:LV	1.179	4.287	0.000	2	-9.288	1.179	1
	13:1.2D+1.6WI	1.179	5.5E+3	1.179	2	-12.7E+3	1.179	1
	14:1.2D+1.6WI	1.179	1.24E+3	1.179	3	-2.38E+3	1.179	1
	15:1.2D-1.6WL	1.179	4.62E+3	0.000	1	-2.02E+3	1.179	2
	16:1.2D-1.6WL	1.179	2.65E+3	1.179	2	-7.15E+3	1.179	1
	17:1.2D+1.0DI	1.179	8.21E+3	1.179	2	-21.4E+3	1.179	1
	18:1.2D+1.0DI	1.179	7.49E+3	1.179	3	-18.4E+3	1.179	1
	19:1.2D+1.0DI	1.179	7.37E+3	1.179	3	-16.7E+3	1.179	1
	20:1.2D+1.0DI	1.179	7.86E+3	1.179	3	-19.8E+3	1.179	1
	21:1.0D+1.0WI	1.179	2.28E+3	1.179	2	-5.72E+3	1.179	1
	22:1.0D+1.0WI	1.179	1.47E+3	1.179	3	-3.45E+3	1.179	1
	23:1.0D-1.0WL	1.179	1.37E+3	1.179	3	-2.23E+3	1.179	1



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
71

Rev
1

Job Title Rocky Hill CT

Part

Ref

By DAP

Date 5/13/19

Chd BK

Client VZW

File Rocky Hill CT.std

Date/Time 13-May-2019 16:22

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	24:1.0D-1.0WL	1.179	1.77E+3	1.179	3	-4.5E+3	1.179	1
	25:1.4D	1.179	2.27E+3	1.179	3	-5.56E+3	1.179	1
	26:1.2D+1.5LV	1.179	1.99E+3	1.179	2	-5.22E+3	1.179	1
	27:1.2D+1.5LV	1.179	1.87E+3	1.179	3	-4.57E+3	1.179	1
	28:1.2D+1.5LV	1.179	1.84E+3	1.179	3	-4.22E+3	1.179	1
	29:1.2D+1.5LV	1.179	1.96E+3	1.179	3	-4.87E+3	1.179	1
	30:1.2D+1.5LV	1.179	1.95E+3	1.179	3	-4.78E+3	1.179	1
149	1:DEAD	1.179	988.750	0.000	2	-2.23E+3	0.000	1
	2:WL#1	1.179	1.72E+3	0.000	2	-4.18E+3	0.000	1
	3:WL#4	1.179	792.001	0.000	2	-864.651	0.000	1
	4:DI	1.179	4.02E+3	0.000	2	-8.9E+3	0.000	1
	5:WLI#1	1.179	807.300	0.000	2	-1.96E+3	0.000	1
	6:WLI#4	1.179	375.047	0.000	2	-405.587	0.000	1
	7:WLS#1	1.179	603.098	0.000	2	-1.47E+3	0.000	1
	8:WLS#4	1.179	278.036	0.000	2	-303.567	0.000	1
	9:WLM#1	1.179	172.586	0.000	2	-420.395	0.000	1
	10:WLM#4	1.179	79.443	0.000	2	-86.773	0.000	1
	11:LM	1.179	28.524	0.000	1	-11.555	0.000	2
	12:LV	1.179	18.232	0.000	2	-45.032	0.000	1
	13:1.2D+1.6WI	1.179	3.93E+3	0.000	2	-9.36E+3	0.000	1
	14:1.2D+1.6WI	1.179	2.45E+3	0.000	2	-4.06E+3	0.000	1
	15:1.2D-1.6WL	1.179	4.4E+3	1.179	1	-1.56E+3	0.000	2
	16:1.2D-1.6WL	1.179	971.658	0.000	3	-1.29E+3	0.000	1
	17:1.2D+1.0DI	1.179	6.01E+3	0.000	2	-13.5E+3	0.000	1
	18:1.2D+1.0DI	1.179	5.58E+3	0.000	2	-12E+3	0.000	1
	19:1.2D+1.0DI	1.179	4.39E+3	0.000	2	-9.61E+3	0.000	1
	20:1.2D+1.0DI	1.179	4.83E+3	0.000	2	-11.2E+3	0.000	1
	21:1.0D+1.0WI	1.179	1.59E+3	0.000	2	-3.7E+3	0.000	1
	22:1.0D+1.0WI	1.179	1.27E+3	0.000	2	-2.53E+3	0.000	1
	23:1.0D-1.0WL	1.179	412.912	0.000	2	-763.240	0.000	1
	24:1.0D-1.0WL	1.179	817.798	0.000	2	-1.93E+3	0.000	1
	25:1.4D	1.179	1.38E+3	0.000	2	-3.12E+3	0.000	1
	26:1.2D+1.5LV	1.179	1.34E+3	0.000	2	-3.06E+3	0.000	1
	27:1.2D+1.5LV	1.179	1.25E+3	0.000	2	-2.72E+3	0.000	1
	28:1.2D+1.5LV	1.179	998.303	0.000	2	-2.21E+3	0.000	1
	29:1.2D+1.5LV	1.179	1.09E+3	0.000	2	-2.55E+3	0.000	1
	30:1.2D+1.5LV	1.179	1.21E+3	0.000	2	-2.75E+3	0.000	1
150	1:DEAD	1.179	706.815	0.000	2	-1.03E+3	0.000	1
	2:WL#1	1.179	1.61E+3	0.000	2	-3.24E+3	0.000	1
	3:WL#4	1.179	988.815	0.000	2	-396.353	0.000	1
	4:DI	1.179	3.27E+3	0.000	2	-5.01E+3	0.000	1
	5:WLI#1	1.179	763.725	0.000	2	-1.52E+3	0.000	1
	6:WLI#4	1.179	460.188	0.000	2	-190.000	0.000	1
	7:WLS#1	1.179	565.758	0.000	2	-1.14E+3	0.000	1



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
72

Rev
1

Job Title **Rocky Hill CT**

Part

Ref

By **DAP**

Date **5/13/19**

Chd **BK**

Client **VZW**

File **Rocky Hill CT.std**

Date/Time **13-May-2019 16:22**

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	8:WLS#4	1.179	347.216	0.000	2	-139.190	0.000	1
	9:WLM#1	1.179	161.844	0.000	2	-325.846	0.000	1
	10:WLM#4	1.179	99.029	0.000	2	-39.766	0.000	1
	11:LM	1.179	24.713	0.000	1	-10.076	0.000	2
	12:LV	1.179	12.156	0.000	2	-28.201	0.000	1
	13:1.2D+1.6WI	1.179	3.42E+3	0.000	2	-6.41E+3	0.000	1
	14:1.2D+1.6WI	1.179	2.43E+3	0.000	2	-1.51E+3	0.000	1
	15:1.2D-1.6WL	1.179	3.95E+3	0.196	1	-1.83E+3	1.179	3
	16:1.2D-1.6WL	1.179	951.044	0.000	3	-951.828	0.000	1
	17:1.2D+1.0DI	1.179	4.88E+3	0.000	2	-7.76E+3	0.000	1
	18:1.2D+1.0DI	1.179	4.58E+3	0.000	2	-6.33E+3	0.000	1
	19:1.2D+1.0DI	1.179	3.36E+3	0.000	2	-4.73E+3	0.000	1
	20:1.2D+1.0DI	1.179	3.66E+3	0.000	2	-6.16E+3	0.000	1
	21:1.0D+1.0WI	1.179	1.27E+3	0.000	2	-2.16E+3	0.000	1
	22:1.0D+1.0WI	1.179	1.05E+3	0.000	2	-1.09E+3	0.000	1
	23:1.0D-1.0WL	1.179	569.216	1.179	1	-220.600	1.179	2
	24:1.0D-1.0WL	1.179	403.256	0.000	2	-964.871	0.000	1
	25:1.4D	1.179	989.541	0.000	2	-1.44E+3	0.000	1
	26:1.2D+1.5LM	1.179	999.071	0.000	2	-1.52E+3	0.000	1
	27:1.2D+1.5LM	1.179	936.256	0.000	2	-1.21E+3	0.000	1
	28:1.2D+1.5LM	1.179	675.384	0.000	2	-868.523	0.000	1
	29:1.2D+1.5LM	1.179	738.199	0.000	2	-1.18E+3	0.000	1
	30:1.2D+1.5LV	1.179	866.413	0.000	2	-1.27E+3	0.000	1
151	1:DEAD	1.889	752.068	0.000	1	-1.41E+3	0.000	2
	2:WL#1	1.889	1.16E+3	0.000	1	-2.79E+3	0.000	2
	3:WL#4	1.889	2.67E+3	1.889	2	-1.47E+3	0.000	2
	4:DI	1.889	3.32E+3	0.000	1	-6.4E+3	0.000	2
	5:WLI#1	1.889	551.467	0.000	1	-1.3E+3	0.000	2
	6:WLI#4	1.889	1.22E+3	1.889	2	-691.385	0.000	1
	7:WLS#1	1.889	406.217	0.000	1	-979.409	0.000	2
	8:WLS#4	1.889	937.999	1.889	2	-515.749	0.000	2
	9:WLM#1	1.889	116.375	0.000	1	-280.249	0.000	2
	10:WLM#4	1.889	267.219	1.889	2	-147.446	0.000	2
	11:LM	1.889	16.238	0.000	2	-6.593	0.000	1
	12:LV	1.889	8.243	0.000	1	-17.374	0.000	2
	13:1.2D+1.6WI	1.889	2.75E+3	0.000	1	-6.15E+3	0.000	2
	14:1.2D+1.6WI	1.889	4.82E+3	1.889	2	-4.04E+3	0.000	2
	15:1.2D-1.6WL	1.889	3.5E+3	1.889	2	-1.38E+3	1.889	1
	16:1.2D-1.6WL	1.889	1.28E+3	1.889	3	-3.73E+3	1.889	2
	17:1.2D+1.0DI	1.889	4.78E+3	0.000	1	-9.4E+3	0.000	2
	18:1.2D+1.0DI	1.889	4.84E+3	0.000	1	-8.78E+3	0.000	2
	19:1.2D+1.0DI	1.889	3.67E+3	0.000	1	-6.79E+3	0.000	2
	20:1.2D+1.0DI	1.889	3.61E+3	0.000	1	-7.4E+3	0.000	2
	21:1.0D+1.0WI	1.889	1.16E+3	0.000	1	-2.39E+3	0.000	2



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
73

Rev
1

Job Title Rocky Hill CT

Part

Ref

By DAP

Date 5/13/19

Chd BK

Client VZW

File Rocky Hill CT.std

Date/Time 13-May-2019 16:22

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	22:1.0D+1.0WI	1.889	1.39E+3	1.889	2	-1.93E+3	0.000	2
	23:1.0D-1.0WL	1.889	1.1E+3	1.889	2	-432.176	0.000	2
	24:1.0D-1.0WL	1.889	319.600	0.000	1	-895.836	0.000	2
	25:1.4D	1.889	1.05E+3	0.000	1	-1.98E+3	0.000	2
	26:1.2D+1.5LM	1.889	1.01E+3	0.000	1	-1.95E+3	0.000	2
	27:1.2D+1.5LM	1.889	1.02E+3	0.000	1	-1.82E+3	0.000	2
	28:1.2D+1.5LM	1.889	776.962	0.000	1	-1.39E+3	0.000	2
	29:1.2D+1.5LM	1.889	769.317	0.000	1	-1.52E+3	0.000	2
	30:1.2D+1.5LV	1.889	914.846	0.000	1	-1.72E+3	0.000	2
152	1:DEAD	1.889	1.89E+3	1.889	2	-763.806	1.889	3
	2:WL#1	1.889	794.468	0.000	1	-1.85E+3	0.000	2
	3:WL#4	1.889	6.62E+3	1.889	2	-2.51E+3	1.889	3
	4:DI	1.889	7.92E+3	1.889	2	-3.22E+3	1.889	3
	5:WLI#1	1.889	392.456	0.000	1	-888.914	0.000	2
	6:WLI#4	1.889	3.01E+3	1.889	2	-1.11E+3	1.889	3
	7:WLS#1	1.889	278.911	0.000	1	-648.264	0.000	2
	8:WLS#4	1.889	2.32E+3	1.889	2	-880.212	1.889	3
	9:WLM#1	1.889	80.345	0.000	1	-186.380	0.000	2
	10:WLM#4	1.889	661.770	1.889	2	-250.153	1.889	3
	11:LM	1.889	10.667	0.000	2	-4.184	0.000	1
	12:LV	1.889	5.261	1.889	2	-6.056	0.000	2
	13:1.2D+1.6WI	1.889	1.16E+3	0.000	1	-2.41E+3	0.000	2
	14:1.2D+1.6WI	1.889	12.9E+3	1.889	2	-4.93E+3	1.889	3
	15:1.2D-1.6WL	1.889	3.9E+3	1.889	2	-1.57E+3	1.889	3
	16:1.2D-1.6WL	1.889	3.09E+3	1.889	3	-8.31E+3	1.889	2
	17:1.2D+1.0DI	1.889	9.64E+3	1.889	2	-3.91E+3	1.889	3
	18:1.2D+1.0DI	1.889	13.2E+3	1.889	2	-5.25E+3	1.889	3
	19:1.2D+1.0DI	1.889	10.7E+3	1.889	2	-4.37E+3	1.889	3
	20:1.2D+1.0DI	1.889	7.18E+3	1.889	2	-3.04E+3	1.889	3
	21:1.0D+1.0WI	1.889	1.54E+3	1.889	2	-621.284	1.889	3
	22:1.0D+1.0WI	1.889	4.22E+3	1.889	2	-1.64E+3	1.889	3
	23:1.0D-1.0WL	1.889	2.25E+3	1.889	2	-906.327	1.889	3
	24:1.0D-1.0WL	1.889	159.441	1.889	1	-482.118	0.000	2
	25:1.4D	1.889	2.65E+3	1.889	2	-1.07E+3	1.889	3
	26:1.2D+1.5LM	1.889	2.18E+3	1.889	2	-878.025	1.889	3
	27:1.2D+1.5LM	1.889	2.94E+3	1.889	2	-1.17E+3	1.889	3
	28:1.2D+1.5LM	1.889	2.38E+3	1.889	2	-961.922	1.889	3
	29:1.2D+1.5LM	1.889	1.62E+3	1.889	2	-669.820	1.889	3
	30:1.2D+1.5LV	1.889	2.28E+3	1.889	2	-920.023	1.889	3
153	1:DEAD	1.179	991.972	1.179	2	-2.23E+3	1.179	1
	2:WL#1	1.179	1.31E+3	1.179	1	-817.548	0.000	2
	3:WL#4	1.179	1.86E+3	1.179	2	-4.03E+3	1.179	1
	4:DI	1.179	4.01E+3	1.179	2	-8.84E+3	1.179	1
	5:WLI#1	1.179	609.226	1.179	1	-377.149	0.000	2



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
74

Rev
1

Job Title Rocky Hill CT

Part

Ref

By DAP

Date 5/13/19

Chd BK

Client VZW

File Rocky Hill CT.std

Date/Time 13-May-2019 16:22

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	6:WLI#4	1.179	870.095	1.179	2	-1.86E+3	1.179	1
	7:WLS#1	1.179	459.822	1.179	1	-287.135	0.000	2
	8:WLS#4	1.179	652.787	1.179	2	-1.42E+3	1.179	1
	9:WLM#1	1.179	131.536	1.179	1	-82.258	0.000	2
	10:WLM#4	1.179	186.202	1.179	2	-403.420	1.179	1
	11:LM	1.179	36.371	1.179	2	-90.105	1.179	1
	12:LV	1.179	14.273	1.179	1	-5.797	1.179	3
	13:1.2D+1.6WI	1.179	895.437	1.179	2	-984.947	0.000	2
	14:1.2D+1.6WI	1.179	4.16E+3	1.179	2	-9.12E+3	1.179	1
	15:1.2D-1.6WL	1.179	1.94E+3	1.179	3	-4.77E+3	1.179	1
	16:1.2D-1.6WL	1.179	4.11E+3	0.000	1	-1.78E+3	1.179	2
	17:1.2D+1.0DI	1.179	5.13E+3	1.179	2	-10.9E+3	1.179	1
	18:1.2D+1.0DI	1.179	6.08E+3	1.179	2	-13.4E+3	1.179	1
	19:1.2D+1.0DI	1.179	5.28E+3	1.179	2	-12.1E+3	1.179	1
	20:1.2D+1.0DI	1.179	4.33E+3	1.179	2	-9.66E+3	1.179	1
	21:1.0D+1.0WI	1.179	927.105	1.179	2	-1.77E+3	1.179	1
	22:1.0D+1.0WI	1.179	1.64E+3	1.179	2	-3.64E+3	1.179	1
	23:1.0D-1.0WL	1.179	1.06E+3	1.179	2	-2.69E+3	1.179	1
	24:1.0D-1.0WL	1.179	484.244	1.179	3	-813.237	1.179	1
	25:1.4D	1.179	1.39E+3	1.179	2	-3.12E+3	1.179	1
	26:1.2D+1.5LM	1.179	1.23E+3	1.179	2	-2.68E+3	1.179	1
	27:1.2D+1.5LM	1.179	1.43E+3	1.179	2	-3.21E+3	1.179	1
	28:1.2D+1.5LM	1.179	1.26E+3	1.179	2	-2.94E+3	1.179	1
	29:1.2D+1.5LM	1.179	1.06E+3	1.179	2	-2.41E+3	1.179	1
	30:1.2D+1.5LV	1.179	1.18E+3	1.179	2	-2.65E+3	1.179	1
154	1:DEAD	1.179	1.61E+3	1.179	3	-3.94E+3	1.179	1
	2:WL#1	1.179	1.28E+3	0.000	1	-628.285	1.179	2
	3:WL#4	1.179	2.28E+3	1.179	2	-5.03E+3	1.179	1
	4:DI	1.179	5.56E+3	1.179	3	-13.8E+3	1.179	1
	5:WLI#1	1.179	601.482	0.000	1	-306.266	1.179	2
	6:WLI#4	1.179	1.07E+3	1.179	2	-2.32E+3	1.179	1
	7:WLS#1	1.179	448.980	0.000	1	-220.795	1.179	2
	8:WLS#4	1.179	801.699	1.179	2	-1.77E+3	1.179	1
	9:WLM#1	1.179	128.418	0.000	1	-63.086	1.179	2
	10:WLM#4	1.179	228.505	1.179	2	-503.362	1.179	1
	11:LM	1.179	54.952	1.179	3	-125.380	1.179	1
	12:LV	1.179	16.626	1.179	1	-9.592	1.179	3
	13:1.2D+1.6WI	1.179	1.76E+3	1.179	3	-2.91E+3	1.179	1
	14:1.2D+1.6WI	1.179	5.38E+3	1.179	2	-12.8E+3	1.179	1
	15:1.2D-1.6WL	1.179	2.73E+3	1.179	2	-6.55E+3	1.179	1
	16:1.2D-1.6WL	1.179	4.46E+3	0.000	1	-1.92E+3	1.179	2
	17:1.2D+1.0DI	1.179	7.48E+3	1.179	3	-18E+3	1.179	1
	18:1.2D+1.0DI	1.179	7.93E+3	1.179	2	-20.9E+3	1.179	1
	19:1.2D+1.0DI	1.179	7.5E+3	1.179	3	-19.1E+3	1.179	1



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No 50103542	Sheet No 75	Rev 1
Part		
Ref		
By DAP	Date 5/13/19	Chd BK
File Rocky Hill CT.std	Date/Time 13-May-2019 16:22	

Job Title Rocky Hill CT

Client VZW

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	20:1.2D+1.0DI-	1.179	7.12E+3	1.179	3	-16.2E+3	1.179	1
	21:1.0D+1.0WI	1.179	1.57E+3	1.179	3	-3.54E+3	1.179	1
	22:1.0D+1.0WI	1.179	2.24E+3	1.179	2	-5.71E+3	1.179	1
	23:1.0D-1.0WL	1.179	1.66E+3	1.179	2	-4.34E+3	1.179	1
	24:1.0D-1.0WL	1.179	1.31E+3	1.179	3	-2.18E+3	1.179	1
	25:1.4D	1.179	2.25E+3	1.179	3	-5.52E+3	1.179	1
	26:1.2D+1.5LM	1.179	2E+3	1.179	3	-4.81E+3	1.179	1
	27:1.2D+1.5LM	1.179	2.1E+3	1.179	3	-5.42E+3	1.179	1
	28:1.2D+1.5LM	1.179	2.02E+3	1.179	3	-5.04E+3	1.179	1
	29:1.2D+1.5LM	1.179	1.93E+3	1.179	3	-4.42E+3	1.179	1
	30:1.2D+1.5LV	1.179	1.92E+3	1.179	3	-4.71E+3	1.179	1
155	1:DEAD	1.889	753.212	1.889	3	-1.41E+3	1.889	2
	2:WL#1	1.889	3.22E+3	0.000	2	-1.11E+3	0.000	1
	3:WL#4	1.889	1.6E+3	1.889	3	-3.08E+3	1.889	2
	4:DI	1.889	3.32E+3	1.889	3	-6.37E+3	1.889	2
	5:WLI#1	1.889	1.53E+3	0.000	2	-529.173	0.000	1
	6:WLI#4	1.889	773.305	1.889	3	-1.43E+3	1.889	2
	7:WLS#1	1.889	1.13E+3	0.000	2	-390.330	0.000	1
	8:WLS#4	1.889	561.204	1.889	3	-1.08E+3	1.889	2
	9:WLM#1	1.889	324.776	0.000	2	-112.067	0.000	1
	10:WLM#4	1.889	160.554	1.889	3	-308.627	1.889	2
	11:LM	1.889	16.476	1.889	3	-34.762	1.889	2
	12:LV	1.889	8.130	1.889	2	-3.285	1.889	1
	13:1.2D+1.6WI	1.889	5.71E+3	0.000	2	-1.99E+3	0.000	1
	14:1.2D+1.6WI	1.889	3.46E+3	1.889	3	-6.62E+3	1.889	2
	15:1.2D-1.6WL	1.889	1.56E+3	0.000	1	-4.61E+3	0.000	2
	16:1.2D-1.6WL	1.889	3.24E+3	1.889	2	-1.65E+3	1.889	3
	17:1.2D+1.0DI-	1.889	4.49E+3	1.889	3	-8.04E+3	1.889	2
	18:1.2D+1.0DI-	1.889	5E+3	1.889	3	-9.49E+3	1.889	2
	19:1.2D+1.0DI-	1.889	3.95E+3	1.889	3	-8.09E+3	1.889	2
	20:1.2D+1.0DI-	1.889	3.45E+3	1.889	3	-6.63E+3	1.889	2
	21:1.0D+1.0WI	1.889	1.59E+3	0.000	2	-1.38E+3	1.889	2
	22:1.0D+1.0WI	1.889	1.31E+3	1.889	3	-2.49E+3	1.889	2
	23:1.0D-1.0WL	1.889	576.533	1.889	3	-1.44E+3	1.889	2
	24:1.0D-1.0WL	1.889	567.917	0.000	2	-327.936	1.889	2
	25:1.4D	1.889	1.05E+3	1.889	3	-1.97E+3	1.889	2
	26:1.2D+1.5LM	1.889	979.749	1.889	3	-1.74E+3	1.889	2
	27:1.2D+1.5LM	1.889	1.09E+3	1.889	3	-2.05E+3	1.889	2
	28:1.2D+1.5LM	1.889	877.388	1.889	3	-1.75E+3	1.889	2
	29:1.2D+1.5LM	1.889	768.014	1.889	3	-1.44E+3	1.889	2
	30:1.2D+1.5LV	1.889	899.298	1.889	3	-1.68E+3	1.889	2
156	1:DEAD	1.889	1.79E+3	1.889	3	-4.25E+3	1.889	2
	2:WL#1	1.889	1.44E+3	1.889	3	-2.9E+3	1.889	2
	3:WL#4	1.889	2.9E+3	1.889	3	-5.35E+3	1.889	2



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
76

Rev
1

Job Title Rocky Hill CT

Part

Ref

By DAP

Date 5/13/19

Chd BK

Client VZW

File Rocky Hill CT.std

Date/Time 13-May-2019 16:22

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	4:DI	1.889	6.79E+3	1.889	3	-16.2E+3	1.889	2
	5:WLI#1	1.889	707.405	1.889	3	-1.39E+3	1.889	2
	6:WLI#4	1.889	1.36E+3	1.889	3	-2.46E+3	1.889	2
	7:WLS#1	1.889	504.327	1.889	3	-1.02E+3	1.889	2
	8:WLS#4	1.889	1.02E+3	1.889	3	-1.88E+3	1.889	2
	9:WLM#1	1.889	145.155	1.889	3	-292.654	1.889	2
	10:WLM#4	1.889	290.101	1.889	3	-535.999	1.889	2
	11:LM	1.889	26.798	1.889	3	-56.016	1.889	2
	12:LV	1.889	11.099	1.889	2	-5.436	1.889	3
	13:1.2D+1.6WI	1.889	4.44E+3	1.889	3	-9.74E+3	1.889	2
	14:1.2D+1.6WI	1.889	6.78E+3	1.889	3	-13.7E+3	1.889	2
	15:1.2D-1.6WL	1.889	644.111	0.000	1	-1.94E+3	0.000	2
	16:1.2D-1.6WL	1.889	3.46E+3	1.889	2	-2.49E+3	1.889	3
	17:1.2D+1.0DI	1.889	9.64E+3	1.889	3	-22.7E+3	1.889	2
	18:1.2D+1.0DI	1.889	10.3E+3	1.889	3	-23.8E+3	1.889	2
	19:1.2D+1.0DI	1.889	8.22E+3	1.889	3	-19.9E+3	1.889	2
	20:1.2D+1.0DI	1.889	7.57E+3	1.889	3	-18.9E+3	1.889	2
	21:1.0D+1.0WI	1.889	2.29E+3	1.889	3	-5.27E+3	1.889	2
	22:1.0D+1.0WI	1.889	2.8E+3	1.889	3	-6.13E+3	1.889	2
	23:1.0D-1.0WL	1.889	1.28E+3	1.889	3	-3.23E+3	1.889	2
	24:1.0D-1.0WL	1.889	768.665	1.889	1	-2.37E+3	1.889	2
	25:1.4D	1.889	2.5E+3	1.889	3	-5.95E+3	1.889	2
	26:1.2D+1.5LV	1.889	2.33E+3	1.889	3	-5.48E+3	1.889	2
	27:1.2D+1.5LV	1.889	2.47E+3	1.889	3	-5.72E+3	1.889	2
	28:1.2D+1.5LV	1.889	2.04E+3	1.889	3	-4.89E+3	1.889	2
	29:1.2D+1.5LV	1.889	1.89E+3	1.889	3	-4.65E+3	1.889	2
	30:1.2D+1.5LV	1.889	2.13E+3	1.889	3	-5.09E+3	1.889	2
175	1:DEAD	3.000	3.11E+3	3.000		-3.12E+3	3.000	
	2:WL#1	3.000	6.59E+3	3.000		-6.43E+3	3.000	
	3:WL#4	3.000	1.46E+3	0.000		-1.25E+3	0.000	
	4:DI	3.000	13.2E+3	3.000		-13.1E+3	3.000	
	5:WLI#1	3.000	3.19E+3	3.000		-3.12E+3	3.000	
	6:WLI#4	3.000	676.992	0.000		-583.668	0.000	
	7:WLS#1	3.000	2.32E+3	3.000		-2.26E+3	3.000	
	8:WLS#4	3.000	512.903	0.000		-439.884	0.000	
	9:WLM#1	3.000	665.317	3.000		-648.950	3.000	
	10:WLM#4	3.000	145.951	0.000		-125.190	0.000	
	11:LM	3.000	39.613	3.000		-37.424	3.000	
	12:LV	3.000	8.469	0.000		-8.785	0.000	
	13:1.2D+1.6WI	3.000	14.3E+3	3.000		-14E+3	3.000	
	14:1.2D+1.6WI	3.000	5.61E+3	3.000		-5.28E+3	3.000	
	15:1.2D-1.6WL	3.000	7.4E+3	0.000		-7.69E+3	0.000	
	16:1.2D-1.6WL	3.000	2.08E+3	3.000		-2.41E+3	3.000	
	17:1.2D+1.0DI	3.000	20.1E+3	3.000		-20E+3	3.000	



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
77

Rev
1

Job Title Rocky Hill CT

Part

Ref

By DAP

Date 5/13/19

Chd BK

Client VZW

File Rocky Hill CT.std

Date/Time 13-May-2019 16:22

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	18:1.2D+1.0DI-	3.000	17.5E+3	3.000		-17.3E+3	3.000	
	19:1.2D+1.0DI-	3.000	13.8E+3	3.000		-13.8E+3	3.000	
	20:1.2D+1.0DI-	3.000	16.4E+3	3.000		-16.4E+3	3.000	
	21:1.0D+1.0WI	3.000	5.43E+3	3.000		-5.37E+3	3.000	
	22:1.0D+1.0WI	3.000	3.52E+3	3.000		-3.45E+3	3.000	
	23:1.0D-1.0WL	3.000	824.882	3.000		-885.144	3.000	
	24:1.0D-1.0WL	3.000	2.72E+3	3.000		-2.8E+3	3.000	
	25:1.4D	3.000	4.36E+3	3.000		-4.36E+3	3.000	
	26:1.2D+1.5LV	3.000	4.46E+3	3.000		-4.44E+3	3.000	
	27:1.2D+1.5LV	3.000	3.91E+3	3.000		-3.89E+3	3.000	
	28:1.2D+1.5LV	3.000	3.13E+3	3.000		-3.15E+3	3.000	
	29:1.2D+1.5LV	3.000	3.68E+3	3.000		-3.7E+3	3.000	
	30:1.2D+1.5LV	3.000	3.75E+3	3.000		-3.75E+3	3.000	
176	1:DEAD	1.333	654.587	0.000		-667.731	0.000	
	2:WL#1	1.333	4.87E+3	0.000		-4.6E+3	0.000	
	3:WL#4	1.333	2.49E+3	0.000		-2.45E+3	0.000	
	4:DI	1.333	2.71E+3	0.000		-2.76E+3	0.000	
	5:WLI#1	1.333	2.13E+3	0.000		-2.01E+3	0.000	
	6:WLI#4	1.333	1.14E+3	0.000		-1.12E+3	0.000	
	7:WLS#1	1.333	1.71E+3	0.000		-1.61E+3	0.000	
	8:WLS#4	1.333	872.968	0.000		-858.916	0.000	
	9:WLM#1	1.333	487.341	0.000		-459.871	0.000	
	10:WLM#4	1.333	248.100	0.000		-244.095	0.000	
	11:LM	1.333	36.447	1.333		-38.086	1.333	
	12:LV	1.333	6.131	0.000		-6.254	0.000	
	13:1.2D+1.6WI	1.333	7.59E+3	0.000		-7.17E+3	0.000	
	14:1.2D+1.6WI	1.333	4.55E+3	0.000		-4.5E+3	0.000	
	15:1.2D-1.6WL	1.333	7.61E+3	0.000		-8.07E+3	0.000	
	16:1.2D-1.6WL	1.333	3.41E+3	0.000		-3.49E+3	0.000	
	17:1.2D+1.0DI-	1.333	3.77E+3	0.000		-3.72E+3	0.000	
	18:1.2D+1.0DI-	1.333	4.38E+3	0.000		-4.43E+3	0.000	
	19:1.2D+1.0DI-	1.333	4.32E+3	0.000		-4.5E+3	0.000	
	20:1.2D+1.0DI-	1.333	2.8E+3	0.000		-2.89E+3	0.000	
	21:1.0D+1.0WI	1.333	1.64E+3	0.000		-1.56E+3	0.000	
	22:1.0D+1.0WI	1.333	1.41E+3	0.000		-1.41E+3	0.000	
	23:1.0D-1.0WL	1.333	1.9E+3	0.000		-2.01E+3	0.000	
	24:1.0D-1.0WL	1.333	617.300	0.000		-644.497	0.000	
	25:1.4D	1.333	916.421	0.000		-934.823	0.000	
	26:1.2D+1.5LV	1.333	852.355	0.000		-843.117	0.000	
	27:1.2D+1.5LV	1.333	1.02E+3	0.000		-1.04E+3	0.000	
	28:1.2D+1.5LV	1.333	1.05E+3	0.000		-1.1E+3	0.000	
	29:1.2D+1.5LV	1.333	684.360	0.000		-706.597	0.000	
	30:1.2D+1.5LV	1.333	794.700	0.000		-810.657	0.000	
177	1:DEAD	1.500	919.853	1.500		-637.279	1.500	



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
78

Rev
1

Job Title Rocky Hill CT

Part

Ref

By DAP

Date 5/13/19

Chd BK

Client VZW

File Rocky Hill CT.std

Date/Time 13-May-2019 16:22

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	2:WL#1	1.500	7.1E+3	0.000		-7E+3	0.000	
	3:WL#4	1.500	7.3E+3	1.500		-7.13E+3	1.500	
	4:DI	1.500	3.99E+3	1.500		-2.63E+3	1.500	
	5:WLI#1	1.500	3.43E+3	0.000		-3.38E+3	0.000	
	6:WLI#4	1.500	3.2E+3	1.500		-3.13E+3	1.500	
	7:WLS#1	1.500	2.49E+3	0.000		-2.46E+3	0.000	
	8:WLS#4	1.500	2.56E+3	1.500		-2.51E+3	1.500	
	9:WLM#1	1.500	716.689	0.000		-706.829	0.000	
	10:WLM#4	1.500	726.422	1.500		-710.013	1.500	
	11:LM	1.500	28.845	1.500		-28.198	1.500	
	12:LV	1.500	14.423	1.500		-14.099	1.500	
	13:1.2D+1.6WI	1.500	11.5E+3	0.000		-11E+3	0.000	
	14:1.2D+1.6WI	1.500	10.9E+3	1.500		-10.3E+3	1.500	
	15:1.2D-1.6WL	1.500	11.4E+3	0.000		-11.2E+3	0.000	
	16:1.2D-1.6WL	1.500	12.5E+3	1.500		-12.4E+3	1.500	
	17:1.2D+1.0DI	1.500	4.44E+3	0.000		-2.75E+3	0.000	
	18:1.2D+1.0DI	1.500	3.02E+3	0.000		-1.3E+3	0.000	
	19:1.2D+1.0DI	1.500	6.92E+3	1.500		-5.26E+3	1.500	
	20:1.2D+1.0DI	1.500	8.19E+3	1.500		-6.57E+3	1.500	
	21:1.0D+1.0WI	1.500	2.64E+3	0.000		-2.33E+3	0.000	
	22:1.0D+1.0WI	1.500	1.94E+3	1.500		-1.6E+3	1.500	
	23:1.0D-1.0WL	1.500	2.6E+3	0.000		-2.36E+3	0.000	
	24:1.0D-1.0WL	1.500	3.42E+3	1.500		-3.19E+3	1.500	
	25:1.4D	1.500	1.29E+3	1.500		-892.190	1.500	
	26:1.2D+1.5LN	1.500	884.856	0.000		-546.924	0.000	
	27:1.2D+1.5LN	1.500	668.706	0.000		-324.225	0.000	
	28:1.2D+1.5LN	1.500	1.54E+3	1.500		-1.21E+3	1.500	
	29:1.2D+1.5LN	1.500	1.84E+3	1.500		-1.52E+3	1.500	
	30:1.2D+1.5LV	1.500	1.12E+3	1.500		-781.148	1.500	
179	1:DEAD	3.000	3.16E+3	3.000		-3.16E+3	3.000	
	2:WL#1	3.000	2.63E+3	3.000		-2.54E+3	3.000	
	3:WL#4	3.000	6.23E+3	3.000		-6.47E+3	3.000	
	4:DI	3.000	13.7E+3	3.000		-13.6E+3	3.000	
	5:WLI#1	3.000	1.2E+3	3.000		-1.15E+3	3.000	
	6:WLI#4	3.000	2.86E+3	3.000		-2.97E+3	3.000	
	7:WLS#1	3.000	923.957	3.000		-892.009	3.000	
	8:WLS#4	3.000	2.19E+3	3.000		-2.27E+3	3.000	
	9:WLM#1	3.000	264.213	3.000		-255.087	3.000	
	10:WLM#4	3.000	623.334	3.000		-647.924	3.000	
	11:LM	3.000	16.937	0.000		-17.569	0.000	
	12:LV	3.000	26.751	0.000		-27.243	0.000	
	13:1.2D+1.6WI	3.000	1.54E+3	0.000		-1.42E+3	0.000	
	14:1.2D+1.6WI	3.000	7.11E+3	0.000		-7.53E+3	0.000	
	15:1.2D-1.6WL	3.000	7.84E+3	3.000		-7.99E+3	3.000	



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
79

Rev
1

Job Title Rocky Hill CT

Ref

By DAP

Date 5/13/19

Chd BK

Client VZW

File Rocky Hill CT.std

Date/Time 13-May-2019 16:22

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	16:1.2D-1.6WL	3.000	14.1E+3	3.000		-13.7E+3	3.000	
	17:1.2D+1.0DI-	3.000	16.3E+3	3.000		-16.2E+3	3.000	
	18:1.2D+1.0DI-	3.000	14.5E+3	3.000		-14.5E+3	3.000	
	19:1.2D+1.0DI-	3.000	18.6E+3	3.000		-18.6E+3	3.000	
	20:1.2D+1.0DI-	3.000	20.4E+3	3.000		-20.2E+3	3.000	
	21:1.0D+1.0WI	3.000	2.28E+3	3.000		-2.25E+3	3.000	
	22:1.0D+1.0WI	3.000	970.940	3.000		-1.06E+3	3.000	
	23:1.0D-1.0WL	3.000	4.05E+3	3.000		-4.08E+3	3.000	
	24:1.0D-1.0WL	3.000	5.42E+3	3.000		-5.33E+3	3.000	
	25:1.4D	3.000	4.42E+3	3.000		-4.43E+3	3.000	
	26:1.2D+1.5LM	3.000	3.56E+3	3.000		-3.55E+3	3.000	
	27:1.2D+1.5LM	3.000	3.17E+3	3.000		-3.2E+3	3.000	
	28:1.2D+1.5LM	3.000	4.07E+3	3.000		-4.08E+3	3.000	
	29:1.2D+1.5LM	3.000	4.45E+3	3.000		-4.43E+3	3.000	
	30:1.2D+1.5LV	3.000	3.76E+3	3.000		-3.76E+3	3.000	
180	1:DEAD	1.333	654.445	0.000		-668.102	0.000	
	2:WL#1	1.333	1.82E+3	0.000		-1.86E+3	0.000	
	3:WL#4	1.333	4.57E+3	0.000		-4.78E+3	0.000	
	4:DI	1.333	2.72E+3	0.000		-2.78E+3	0.000	
	5:WLI#1	1.333	891.337	0.000		-915.800	0.000	
	6:WLI#4	1.333	2.06E+3	0.000		-2.16E+3	0.000	
	7:WLS#1	1.333	639.114	0.000		-652.122	0.000	
	8:WLS#4	1.333	1.61E+3	0.000		-1.68E+3	0.000	
	9:WLM#1	1.333	183.517	0.000		-187.340	0.000	
	10:WLM#4	1.333	456.508	0.000		-477.181	0.000	
	11:LM	1.333	12.262	0.000		-12.507	0.000	
	12:LV	1.333	18.631	0.000		-18.395	0.000	
	13:1.2D+1.6WI	1.333	3.68E+3	0.000		-3.75E+3	0.000	
	14:1.2D+1.6WI	1.333	7.25E+3	0.000		-7.59E+3	0.000	
	15:1.2D-1.6WL	1.333	2.2E+3	0.000		-2.16E+3	0.000	
	16:1.2D-1.6WL	1.333	7.79E+3	0.000		-7.47E+3	0.000	
	17:1.2D+1.0DI-	1.333	4.38E+3	0.000		-4.48E+3	0.000	
	18:1.2D+1.0DI-	1.333	3.89E+3	0.000		-4.06E+3	0.000	
	19:1.2D+1.0DI-	1.333	2.64E+3	0.000		-2.69E+3	0.000	
	20:1.2D+1.0DI-	1.333	4.28E+3	0.000		-4.26E+3	0.000	
	21:1.0D+1.0WI	1.333	1.28E+3	0.000		-1.31E+3	0.000	
	22:1.0D+1.0WI	1.333	1.64E+3	0.000		-1.73E+3	0.000	
	23:1.0D-1.0WL	1.333	371.774	1.333		-368.800	1.333	
	24:1.0D-1.0WL	1.333	1.88E+3	0.000		-1.82E+3	0.000	
	25:1.4D	1.333	916.223	0.000		-935.343	0.000	
	26:1.2D+1.5LM	1.333	982.720	0.000		-1E+3	0.000	
	27:1.2D+1.5LM	1.333	862.352	0.000		-899.783	0.000	
	28:1.2D+1.5LM	1.333	627.352	0.000		-640.286	0.000	
	29:1.2D+1.5LM	1.333	991.219	0.000		-987.303	0.000	



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No 50103542	Sheet No 80	Rev 1
Part		
Ref		
By DAP	Date 5/13/19	Chd BK
File Rocky Hill CT.std	Date/Time 13-May-2019 16:22	

Job Title Rocky Hill CT

Client VZW

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	30:1.2D+1.5LV	1.333	810.078	0.000		-826.114	0.000	
181	1:DEAD	1.500	906.890	1.500		-620.064	1.500	
	2:WL#1	1.500	7.55E+3	0.000		-7.45E+3	0.000	
	3:WL#4	1.500	7.31E+3	1.500		-7.47E+3	1.500	
	4:DI	1.500	3.76E+3	1.500		-2.34E+3	1.500	
	5:WLI#1	1.500	3.5E+3	0.000		-3.46E+3	0.000	
	6:WLI#4	1.500	3.18E+3	1.500		-3.26E+3	1.500	
	7:WLS#1	1.500	2.65E+3	0.000		-2.62E+3	0.000	
	8:WLS#4	1.500	2.57E+3	1.500		-2.63E+3	1.500	
	9:WLM#1	1.500	758.999	0.000		-749.129	0.000	
	10:WLM#4	1.500	728.005	1.500		-744.251	1.500	
	11:LM	1.500	28.845	1.500		-28.198	1.500	
	12:LV	1.500	30.306	1.500		-31.526	1.500	
	13:1.2D+1.6WI	1.500	12.2E+3	0.000		-11.7E+3	0.000	
	14:1.2D+1.6WI	1.500	12.8E+3	1.500		-12.7E+3	1.500	
	15:1.2D-1.6WL	1.500	12.1E+3	0.000		-11.9E+3	0.000	
	16:1.2D-1.6WL	1.500	11.2E+3	1.500		-10.6E+3	1.500	
	17:1.2D+1.0DI	1.500	4.39E+3	0.000		-2.63E+3	0.000	
	18:1.2D+1.0DI	1.500	7.99E+3	1.500		-6.29E+3	1.500	
	19:1.2D+1.0DI	1.500	6.73E+3	1.500		-5.01E+3	1.500	
	20:1.2D+1.0DI	1.500	3.16E+3	0.000		-1.36E+3	0.000	
	21:1.0D+1.0WI	1.500	2.79E+3	0.000		-2.48E+3	0.000	
	22:1.0D+1.0WI	1.500	3.47E+3	1.500		-3.24E+3	1.500	
	23:1.0D-1.0WL	1.500	2.76E+3	0.000		-2.52E+3	0.000	
	24:1.0D-1.0WL	1.500	2.03E+3	1.500		-1.68E+3	1.500	
	25:1.4D	1.500	1.27E+3	1.500		-868.090	1.500	
	26:1.2D+1.5LV	1.500	918.793	0.000		-575.749	0.000	
	27:1.2D+1.5LV	1.500	1.84E+3	1.500		-1.51E+3	1.500	
	28:1.2D+1.5LV	1.500	1.54E+3	1.500		-1.2E+3	1.500	
	29:1.2D+1.5LV	1.500	685.833	0.000		-336.411	0.000	
	30:1.2D+1.5LV	1.500	1.13E+3	1.500		-791.361	1.500	
183	1:DEAD	3.000	3.2E+3	3.000		-3.2E+3	3.000	
	2:WL#1	3.000	4.5E+3	0.000		-4.78E+3	0.000	
	3:WL#4	3.000	4.95E+3	3.000		-4.91E+3	3.000	
	4:DI	3.000	14.5E+3	3.000		-14.5E+3	3.000	
	5:WLI#1	3.000	2.08E+3	0.000		-2.2E+3	0.000	
	6:WLI#4	3.000	2.36E+3	3.000		-2.34E+3	3.000	
	7:WLS#1	3.000	1.58E+3	0.000		-1.68E+3	0.000	
	8:WLS#4	3.000	1.74E+3	3.000		-1.72E+3	3.000	
	9:WLM#1	3.000	452.446	0.000		-480.023	0.000	
	10:WLM#4	3.000	497.477	3.000		-493.020	3.000	
	11:LM	3.000	53.500	0.000		-54.485	0.000	
	12:LV	3.000	19.809	3.000		-18.714	3.000	
	13:1.2D+1.6WI	3.000	4.54E+3	0.000		-5E+3	0.000	



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
81

Rev
1

Part

Job Title Rocky Hill CT

Ref

By DAP

Date 5/13/19

Chd BK

Client VZW

File Rocky Hill CT.std

Date/Time 13-May-2019 16:22

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	14:1.2D+1.6WI	3.000	11.8E+3	3.000		-11.7E+3	3.000	
	15:1.2D-1.6WL	3.000	11.2E+3	3.000		-10.7E+3	3.000	
	16:1.2D-1.6WL	3.000	4.4E+3	0.000		-4.5E+3	0.000	
	17:1.2D+1.0DI	3.000	16.3E+3	3.000		-16.3E+3	3.000	
	18:1.2D+1.0DI	3.000	20.7E+3	3.000		-20.7E+3	3.000	
	19:1.2D+1.0DI	3.000	20.5E+3	3.000		-20.3E+3	3.000	
	20:1.2D+1.0DI	3.000	16E+3	3.000		-16E+3	3.000	
	21:1.0D+1.0WI	3.000	1.65E+3	3.000		-1.75E+3	3.000	
	22:1.0D+1.0WI	3.000	4.94E+3	3.000		-4.92E+3	3.000	
	23:1.0D-1.0WL	3.000	4.8E+3	3.000		-4.7E+3	3.000	
	24:1.0D-1.0WL	3.000	1.46E+3	3.000		-1.48E+3	3.000	
	25:1.4D	3.000	4.48E+3	3.000		-4.48E+3	3.000	
	26:1.2D+1.5LM	3.000	3.31E+3	3.000		-3.34E+3	3.000	
	27:1.2D+1.5LM	3.000	4.26E+3	3.000		-4.26E+3	3.000	
	28:1.2D+1.5LM	3.000	4.22E+3	3.000		-4.19E+3	3.000	
	29:1.2D+1.5LM	3.000	3.27E+3	3.000		-3.27E+3	3.000	
	30:1.2D+1.5LV	3.000	3.87E+3	3.000		-3.87E+3	3.000	
184	1:DEAD	1.333	647.610	0.000		-660.928	0.000	
	2:WL#1	1.333	4.03E+3	0.000		-4.22E+3	0.000	
	3:WL#4	1.333	3.58E+3	0.000		-3.37E+3	0.000	
	4:DI	1.333	2.63E+3	0.000		-2.69E+3	0.000	
	5:WLI#1	1.333	1.75E+3	0.000		-1.83E+3	0.000	
	6:WLI#4	1.333	1.57E+3	0.000		-1.48E+3	0.000	
	7:WLS#1	1.333	1.42E+3	0.000		-1.48E+3	0.000	
	8:WLS#4	1.333	1.26E+3	0.000		-1.18E+3	0.000	
	9:WLM#1	1.333	402.761	0.000		-421.403	0.000	
	10:WLM#4	1.333	357.236	0.000		-336.075	0.000	
	11:LM	1.333	37.263	0.000		-36.792	0.000	
	12:LV	1.333	18.224	1.333		-19.044	1.333	
	13:1.2D+1.6WI	1.333	6.24E+3	0.000		-6.55E+3	0.000	
	14:1.2D+1.6WI	1.333	5.34E+3	0.000		-5.02E+3	0.000	
	15:1.2D-1.6WL	1.333	7.04E+3	0.000		-6.75E+3	0.000	
	16:1.2D-1.6WL	1.333	5.84E+3	0.000		-6.19E+3	0.000	
	17:1.2D+1.0DI	1.333	3.36E+3	0.000		-3.52E+3	0.000	
	18:1.2D+1.0DI	1.333	3.04E+3	0.000		-3.02E+3	0.000	
	19:1.2D+1.0DI	1.333	4.28E+3	0.000		-4.27E+3	0.000	
	20:1.2D+1.0DI	1.333	4.3E+3	0.000		-4.46E+3	0.000	
	21:1.0D+1.0WI	1.333	1.35E+3	0.000		-1.42E+3	0.000	
	22:1.0D+1.0WI	1.333	1.06E+3	0.000		-1E+3	0.000	
	23:1.0D-1.0WL	1.333	1.8E+3	0.000		-1.75E+3	0.000	
	24:1.0D-1.0WL	1.333	1.62E+3	0.000		-1.71E+3	0.000	
	25:1.4D	1.333	906.654	0.000		-925.299	0.000	
	26:1.2D+1.5LM	1.333	801.967	0.000		-835.884	0.000	
	27:1.2D+1.5LM	1.333	705.419	0.000		-699.532	0.000	



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No 50103542	Sheet No 82	Rev 1
Part		
Ref		
By DAP	Date 5/13/19	Chd BK
Client VZW	File Rocky Hill CT.std	Date/Time 13-May-2019 16:22

Job Title Rocky Hill CT

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	28:1.2D+1.5LM	1.333	1.03E+3	0.000		-1.03E+3	0.000	
	29:1.2D+1.5LM	1.333	1.05E+3	0.000		-1.09E+3	0.000	
	30:1.2D+1.5LV	1.333	801.872	0.000		-819.082	0.000	
185	1:DEAD	1.500	906.547	1.500		-619.709	1.500	
	2:WL#1	1.500	8.7E+3	1.500		-8.89E+3	1.500	
	3:WL#4	1.500	8.17E+3	0.000		-8.17E+3	0.000	
	4:DI	1.500	3.7E+3	1.500		-2.35E+3	1.500	
	5:WLI#1	1.500	3.68E+3	1.500		-3.77E+3	1.500	
	6:WLI#4	1.500	3.79E+3	0.000		-3.79E+3	0.000	
	7:WLS#1	1.500	3.06E+3	1.500		-3.13E+3	1.500	
	8:WLS#4	1.500	2.87E+3	0.000		-2.87E+3	0.000	
	9:WLM#1	1.500	867.914	1.500		-887.332	1.500	
	10:WLM#4	1.500	820.152	0.000		-820.109	0.000	
	11:LM	1.500	60.612	1.500		-63.052	1.500	
	12:LV	1.500	14.422	1.500		-14.099	1.500	
	13:1.2D+1.6WI	1.500	15E+3	1.500		-15E+3	1.500	
	14:1.2D+1.6WI	1.500	13.2E+3	0.000		-12.9E+3	0.000	
	15:1.2D-1.6WL	1.500	13.5E+3	1.500		-12.8E+3	1.500	
	16:1.2D-1.6WL	1.500	13.2E+3	0.000		-12.9E+3	0.000	
	17:1.2D+1.0DI	1.500	8.46E+3	1.500		-6.87E+3	1.500	
	18:1.2D+1.0DI	1.500	4.88E+3	1.500		-3.19E+3	1.500	
	19:1.2D+1.0DI	1.500	1.97E+3	0.000		-241.921	0.000	
	20:1.2D+1.0DI	1.500	5.41E+3	0.000		-3.77E+3	0.000	
	21:1.0D+1.0WI	1.500	3.97E+3	1.500		-3.75E+3	1.500	
	22:1.0D+1.0WI	1.500	3.01E+3	0.000		-2.73E+3	0.000	
	23:1.0D-1.0WL	1.500	2.51E+3	1.500		-2.15E+3	1.500	
	24:1.0D-1.0WL	1.500	3.02E+3	0.000		-2.74E+3	0.000	
	25:1.4D	1.500	1.27E+3	1.500		-867.593	1.500	
	26:1.2D+1.5LM	1.500	2.05E+3	1.500		-1.73E+3	1.500	
	27:1.2D+1.5LM	1.500	1.2E+3	1.500		-855.570	1.500	
	28:1.2D+1.5LM	1.500	399.845	0.000		-51.869	0.000	
	29:1.2D+1.5LM	1.500	1.21E+3	1.500		-872.433	1.500	
	30:1.2D+1.5LV	1.500	1.1E+3	1.500		-760.291	1.500	
188	1:DEAD	3.000	3.11E+3	3.000		-3.12E+3	3.000	
	2:WL#1	3.000	2.26E+3	3.000		-2.16E+3	3.000	
	3:WL#4	3.000	6.41E+3	0.000		-6.16E+3	0.000	
	4:DI	3.000	13.2E+3	3.000		-13.1E+3	3.000	
	5:WLI#1	3.000	1.13E+3	3.000		-1.09E+3	3.000	
	6:WLI#4	3.000	2.95E+3	0.000		-2.84E+3	0.000	
	7:WLS#1	3.000	794.352	3.000		-758.323	3.000	
	8:WLS#4	3.000	2.25E+3	0.000		-2.16E+3	0.000	
	9:WLM#1	3.000	229.080	3.000		-218.823	3.000	
	10:WLM#4	3.000	641.889	0.000		-617.094	0.000	
	11:LM	3.000	16.942	0.000		-17.572	0.000	



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
83

Rev
1

Part

Job Title Rocky Hill CT

Ref

By DAP

Date 5/13/19

Chd BK

Client VZW

File Rocky Hill CT.std

Date/Time 13-May-2019 16:22

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	12:LV	3.000	19.815	3.000		-18.721	3.000	
	13:1.2D+1.6WI	3.000	1.07E+3	0.000		-934.987	0.000	
	14:1.2D+1.6WI	3.000	13.9E+3	3.000		-13.5E+3	3.000	
	15:1.2D-1.6WL	3.000	7.19E+3	3.000		-7.35E+3	3.000	
	16:1.2D-1.6WL	3.000	7.29E+3	0.000		-7.71E+3	0.000	
	17:1.2D+1.0DI	3.000	15.8E+3	3.000		-15.7E+3	3.000	
	18:1.2D+1.0DI	3.000	19.8E+3	3.000		-19.7E+3	3.000	
	19:1.2D+1.0DI	3.000	18E+3	3.000		-18E+3	3.000	
	20:1.2D+1.0DI	3.000	14E+3	3.000		-14E+3	3.000	
	21:1.0D+1.0WI	3.000	2.36E+3	3.000		-2.33E+3	3.000	
	22:1.0D+1.0WI	3.000	5.34E+3	3.000		-5.26E+3	3.000	
	23:1.0D-1.0WL	3.000	3.87E+3	3.000		-3.91E+3	3.000	
	24:1.0D-1.0WL	3.000	921.628	3.000		-1.01E+3	3.000	
	25:1.4D	3.000	4.36E+3	3.000		-4.36E+3	3.000	
	26:1.2D+1.5LM	3.000	3.54E+3	3.000		-3.53E+3	3.000	
	27:1.2D+1.5LM	3.000	4.39E+3	3.000		-4.37E+3	3.000	
	28:1.2D+1.5LM	3.000	3.97E+3	3.000		-3.99E+3	3.000	
	29:1.2D+1.5LM	3.000	3.12E+3	3.000		-3.15E+3	3.000	
	30:1.2D+1.5LV	3.000	3.77E+3	3.000		-3.77E+3	3.000	
189	1:DEAD	1.333	654.789	1.333		-667.959	1.333	
	2:WL#1	1.333	1.81E+3	1.333		-1.91E+3	1.333	
	3:WL#4	1.333	4.96E+3	1.333		-4.72E+3	1.333	
	4:DI	1.333	2.73E+3	1.333		-2.79E+3	1.333	
	5:WLI#1	1.333	891.522	1.333		-933.166	1.333	
	6:WLI#4	1.333	2.21E+3	1.333		-2.1E+3	1.333	
	7:WLS#1	1.333	637.258	1.333		-670.611	1.333	
	8:WLS#4	1.333	1.74E+3	1.333		-1.66E+3	1.333	
	9:WLM#1	1.333	183.041	1.333		-192.562	1.333	
	10:WLM#4	1.333	495.187	1.333		-470.617	1.333	
	11:LM	1.333	12.262	1.333		-12.509	1.333	
	12:LV	1.333	18.222	0.000		-19.042	0.000	
	13:1.2D+1.6WI	1.333	3.66E+3	1.333		-3.83E+3	1.333	
	14:1.2D+1.6WI	1.333	7.94E+3	1.333		-7.57E+3	1.333	
	15:1.2D-1.6WL	1.333	2.3E+3	1.333		-2.17E+3	1.333	
	16:1.2D-1.6WL	1.333	7.6E+3	1.333		-8.01E+3	1.333	
	17:1.2D+1.0DI	1.333	4.38E+3	1.333		-4.49E+3	1.333	
	18:1.2D+1.0DI	1.333	4.21E+3	1.333		-4.17E+3	1.333	
	19:1.2D+1.0DI	1.333	2.69E+3	1.333		-2.72E+3	1.333	
	20:1.2D+1.0DI	1.333	4.03E+3	1.333		-4.21E+3	1.333	
	21:1.0D+1.0WI	1.333	1.28E+3	1.333		-1.32E+3	1.333	
	22:1.0D+1.0WI	1.333	1.84E+3	1.333		-1.77E+3	1.333	
	23:1.0D-1.0WL	1.333	260.079	0.000		-236.272	0.000	
	24:1.0D-1.0WL	1.333	1.8E+3	1.333		-1.89E+3	1.333	
	25:1.4D	1.333	916.705	1.333		-935.143	1.333	



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
84

Rev
1

Job Title Rocky Hill CT

Part

Ref

By DAP

Date 5/13/19

Chd BK

Client VZW

File Rocky Hill CT.std

Date/Time 13-May-2019 16:22

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	26:1.2D+1.5LM	1.333	980.189	1.333		-1.01E+3	1.333	
	27:1.2D+1.5LM	1.333	934.315	1.333		-925.919	1.333	
	28:1.2D+1.5LM	1.333	632.161	1.333		-638.814	1.333	
	29:1.2D+1.5LM	1.333	939.158	1.333		-979.901	1.333	
	30:1.2D+1.5LV	1.333	810.481	1.333		-827.514	1.333	
191	1:DEAD	3.000	3.2E+3	3.000		-3.2E+3	3.000	
	2:WL#1	3.000	6.87E+3	3.000		-6.7E+3	3.000	
	3:WL#4	3.000	1.42E+3	0.000		-1.63E+3	0.000	
	4:DI	3.000	14.2E+3	3.000		-14E+3	3.000	
	5:WLI#1	3.000	3.25E+3	3.000		-3.17E+3	3.000	
	6:WLI#4	3.000	625.641	0.000		-720.853	0.000	
	7:WLS#1	3.000	2.41E+3	3.000		-2.35E+3	3.000	
	8:WLS#4	3.000	498.350	0.000		-573.448	0.000	
	9:WLM#1	3.000	692.111	3.000		-674.573	3.000	
	10:WLM#4	3.000	141.431	0.000		-162.783	0.000	
	11:LM	3.000	39.618	3.000		-37.429	3.000	
	12:LV	3.000	26.750	0.000		-27.243	0.000	
	13:1.2D+1.6WI	3.000	14.8E+3	3.000		-14.5E+3	3.000	
	14:1.2D+1.6WI	3.000	2.53E+3	3.000		-2.87E+3	3.000	
	15:1.2D-1.6WL	3.000	7.43E+3	0.000		-7.73E+3	0.000	
	16:1.2D-1.6WL	3.000	5.58E+3	3.000		-5.24E+3	3.000	
	17:1.2D+1.0DI	3.000	21.2E+3	3.000		-21E+3	3.000	
	18:1.2D+1.0DI	3.000	17.5E+3	3.000		-17.5E+3	3.000	
	19:1.2D+1.0DI	3.000	14.8E+3	3.000		-14.7E+3	3.000	
	20:1.2D+1.0DI	3.000	18.5E+3	3.000		-18.3E+3	3.000	
	21:1.0D+1.0WI	3.000	5.61E+3	3.000		-5.54E+3	3.000	
	22:1.0D+1.0WI	3.000	2.86E+3	3.000		-2.94E+3	3.000	
	23:1.0D-1.0WL	3.000	826.752	3.000		-889.174	3.000	
	24:1.0D-1.0WL	3.000	3.56E+3	3.000		-3.48E+3	3.000	
	25:1.4D	3.000	4.48E+3	3.000		-4.48E+3	3.000	
	26:1.2D+1.5LM	3.000	4.59E+3	3.000		-4.57E+3	3.000	
	27:1.2D+1.5LM	3.000	3.8E+3	3.000		-3.82E+3	3.000	
	28:1.2D+1.5LM	3.000	3.21E+3	3.000		-3.22E+3	3.000	
	29:1.2D+1.5LM	3.000	4E+3	3.000		-3.98E+3	3.000	
	30:1.2D+1.5LV	3.000	3.8E+3	3.000		-3.8E+3	3.000	
192	1:DEAD	1.333	647.605	1.333		-660.906	1.333	
	2:WL#1	1.333	4.79E+3	1.333		-4.53E+3	1.333	
	3:WL#4	1.333	2.79E+3	1.333		-2.86E+3	1.333	
	4:DI	1.333	2.62E+3	1.333		-2.67E+3	1.333	
	5:WLI#1	1.333	2.05E+3	1.333		-1.95E+3	1.333	
	6:WLI#4	1.333	1.23E+3	1.333		-1.26E+3	1.333	
	7:WLS#1	1.333	1.68E+3	1.333		-1.59E+3	1.333	
	8:WLS#4	1.333	979.387	1.333		-1E+3	1.333	
	9:WLM#1	1.333	478.363	1.333		-452.392	1.333	



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
85

Rev
1

Part

Job Title Rocky Hill CT

Ref

By DAP

Date 5/13/19

Chd BK

Client VZW

File Rocky Hill CT.std

Date/Time 13-May-2019 16:22

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	10:WLM#4	1.333	278.361	1.333		-285.554	1.333	
	11:LM	1.333	36.449	0.000		-38.088	0.000	
	12:LV	1.333	18.632	1.333		-18.396	1.333	
	13:1.2D+1.6WI	1.333	7.55E+3	1.333		-7.15E+3	1.333	
	14:1.2D+1.6WI	1.333	3.91E+3	1.333		-4.04E+3	1.333	
	15:1.2D-1.6WL	1.333	7.43E+3	1.333		-7.87E+3	1.333	
	16:1.2D-1.6WL	1.333	5.18E+3	1.333		-5.08E+3	1.333	
	17:1.2D+1.0DI	1.333	3.78E+3	1.333		-3.74E+3	1.333	
	18:1.2D+1.0DI	1.333	2.64E+3	1.333		-2.74E+3	1.333	
	19:1.2D+1.0DI	1.333	4.08E+3	1.333		-4.25E+3	1.333	
	20:1.2D+1.0DI	1.333	4.38E+3	1.333		-4.42E+3	1.333	
	21:1.0D+1.0WI	1.333	1.68E+3	1.333		-1.6E+3	1.333	
	22:1.0D+1.0WI	1.333	755.119	0.000		-791.579	0.000	
	23:1.0D-1.0WL	1.333	1.83E+3	1.333		-1.93E+3	1.333	
	24:1.0D-1.0WL	1.333	1.55E+3	1.333		-1.53E+3	1.333	
	25:1.4D	1.333	906.647	1.333		-925.269	1.333	
	26:1.2D+1.5LV	1.333	886.709	1.333		-879.158	1.333	
	27:1.2D+1.5LV	1.333	639.512	1.333		-665.126	1.333	
	28:1.2D+1.5LV	1.333	1E+3	1.333		-1.05E+3	1.333	
	29:1.2D+1.5LV	1.333	1.06E+3	1.333		-1.07E+3	1.333	
	30:1.2D+1.5LV	1.333	801.822	1.333		-817.430	1.333	
194	1:DEAD	3.000	3.16E+3	3.000		-3.16E+3	3.000	
	2:WL#1	3.000	4.26E+3	0.000		-4.52E+3	0.000	
	3:WL#4	3.000	5.03E+3	3.000		-5.07E+3	3.000	
	4:DI	3.000	13.8E+3	3.000		-13.7E+3	3.000	
	5:WLI#1	3.000	2.03E+3	0.000		-2.15E+3	0.000	
	6:WLI#4	3.000	2.38E+3	3.000		-2.4E+3	3.000	
	7:WLS#1	3.000	1.5E+3	0.000		-1.59E+3	0.000	
	8:WLS#4	3.000	1.77E+3	3.000		-1.78E+3	3.000	
	9:WLM#1	3.000	429.126	0.000		-455.150	0.000	
	10:WLM#4	3.000	505.488	3.000		-509.762	3.000	
	11:LM	3.000	53.498	0.000		-54.483	0.000	
	12:LV	3.000	8.471	0.000		-8.785	0.000	
	13:1.2D+1.6WI	3.000	4.16E+3	0.000		-4.6E+3	0.000	
	14:1.2D+1.6WI	3.000	4.69E+3	0.000		-4.78E+3	0.000	
	15:1.2D-1.6WL	3.000	10.8E+3	3.000		-10.4E+3	3.000	
	16:1.2D-1.6WL	3.000	11.9E+3	3.000		-11.8E+3	3.000	
	17:1.2D+1.0DI	3.000	15.5E+3	3.000		-15.5E+3	3.000	
	18:1.2D+1.0DI	3.000	15.2E+3	3.000		-15.1E+3	3.000	
	19:1.2D+1.0DI	3.000	19.7E+3	3.000		-19.4E+3	3.000	
	20:1.2D+1.0DI	3.000	20E+3	3.000		-19.8E+3	3.000	
	21:1.0D+1.0WI	3.000	1.68E+3	3.000		-1.77E+3	3.000	
	22:1.0D+1.0WI	3.000	1.38E+3	3.000		-1.4E+3	3.000	
	23:1.0D-1.0WL	3.000	4.69E+3	3.000		-4.6E+3	3.000	



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
86

Rev
1

Job Title **Rocky Hill CT**

Part

Ref

By **DAP**

Date **5/13/19**

Chd **BK**

Client **VZW**

File **Rocky Hill CT.std**

Date/Time **13-May-2019 16:22**

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	24:1.0D-1.0WL	3.000	4.94E+3	3.000		-4.93E+3	3.000	
	25:1.4D	3.000	4.42E+3	3.000		-4.43E+3	3.000	
	26:1.2D+1.5LM	3.000	3.28E+3	3.000		-3.31E+3	3.000	
	27:1.2D+1.5LM	3.000	3.21E+3	3.000		-3.22E+3	3.000	
	28:1.2D+1.5LM	3.000	4.15E+3	3.000		-4.13E+3	3.000	
	29:1.2D+1.5LM	3.000	4.23E+3	3.000		-4.23E+3	3.000	
	30:1.2D+1.5LV	3.000	3.8E+3	3.000		-3.8E+3	3.000	
195	1:DEAD	1.333	654.336	1.333		-668.014	1.333	
	2:WL#1	1.333	4.02E+3	1.333		-4.18E+3	1.333	
	3:WL#4	1.333	2.99E+3	1.333		-3.13E+3	1.333	
	4:DI	1.333	2.7E+3	1.333		-2.76E+3	1.333	
	5:WLI#1	1.333	1.78E+3	1.333		-1.86E+3	1.333	
	6:WLI#4	1.333	1.36E+3	1.333		-1.43E+3	1.333	
	7:WLS#1	1.333	1.41E+3	1.333		-1.47E+3	1.333	
	8:WLS#4	1.333	1.05E+3	1.333		-1.1E+3	1.333	
	9:WLM#1	1.333	402.512	1.333		-419.082	1.333	
	10:WLM#4	1.333	298.033	1.333		-312.116	1.333	
	11:LM	1.333	37.265	1.333		-36.794	1.333	
	12:LV	1.333	6.131	1.333		-6.254	1.333	
	13:1.2D+1.6WI	1.333	6.12E+3	1.333		-6.4E+3	1.333	
	14:1.2D+1.6WI	1.333	5.2E+3	1.333		-5.44E+3	1.333	
	15:1.2D-1.6WL	1.333	7.06E+3	1.333		-6.82E+3	1.333	
	16:1.2D-1.6WL	1.333	4.66E+3	1.333		-4.46E+3	1.333	
	17:1.2D+1.0DI	1.333	3.33E+3	1.333		-3.49E+3	1.333	
	18:1.2D+1.0DI	1.333	4.32E+3	1.333		-4.47E+3	1.333	
	19:1.2D+1.0DI	1.333	4.45E+3	1.333		-4.45E+3	1.333	
	20:1.2D+1.0DI	1.333	3.06E+3	1.333		-3.07E+3	1.333	
	21:1.0D+1.0WI	1.333	1.27E+3	1.333		-1.34E+3	1.333	
	22:1.0D+1.0WI	1.333	1.48E+3	1.333		-1.54E+3	1.333	
	23:1.0D-1.0WL	1.333	1.85E+3	1.333		-1.8E+3	1.333	
	24:1.0D-1.0WL	1.333	967.183	1.333		-931.439	1.333	
	25:1.4D	1.333	916.071	1.333		-935.219	1.333	
	26:1.2D+1.5LM	1.333	761.495	1.333		-793.771	1.333	
	27:1.2D+1.5LM	1.333	1.02E+3	1.333		-1.05E+3	1.333	
	28:1.2D+1.5LM	1.333	1.07E+3	1.333		-1.07E+3	1.333	
	29:1.2D+1.5LM	1.333	734.078	1.333		-735.702	1.333	
	30:1.2D+1.5LV	1.333	794.400	1.333		-810.998	1.333	
196	1:DEAD	5.667	2.81E+3	5.667		-2.98E+3	5.667	
	2:WL#1	5.667	6.87E+3	5.667		-6.76E+3	5.667	
	3:WL#4	5.667	986.100	4.250		-876.156	4.250	
	4:DI	5.667	12.2E+3	5.667		-12.9E+3	5.667	
	5:WLI#1	5.667	3.15E+3	5.667		-3.11E+3	5.667	
	6:WLI#4	5.667	429.783	3.306		-376.825	3.306	
	7:WLS#1	5.667	2.41E+3	5.667		-2.38E+3	5.667	



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
87

Rev
1

Job Title **Rocky Hill CT**

Part

Ref

By **DAP**

Date **5/13/19**

Chd **BK**

Client **VZW**

File **Rocky Hill CT.std**

Date/Time **13-May-2019 16:22**

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	8:WLS#4	5.667	347.178	4.250		-308.631	4.250	
	9:WLM#1	5.667	689.514	5.667		-678.967	5.667	
	10:WLM#4	5.667	97.402	4.250		-86.233	4.250	
	11:LM	5.667	23.210	0.000		-26.695	0.000	
	12:LV	5.667	36.372	5.667		-34.662	5.667	
	13:1.2D+1.6WI	5.667	14.3E+3	5.667		-14.3E+3	5.667	
	14:1.2D+1.6WI	5.667	3.5E+3	0.000		-3.56E+3	0.000	
	15:1.2D-1.6WL	5.667	7.68E+3	0.000		-7.98E+3	0.000	
	16:1.2D-1.6WL	5.667	3.93E+3	5.667		-4.32E+3	5.667	
	17:1.2D+1.0DI	5.667	18.6E+3	5.667		-19.5E+3	5.667	
	18:1.2D+1.0DI	5.667	15.4E+3	5.667		-16.3E+3	5.667	
	19:1.2D+1.0DI	5.667	12.5E+3	5.667		-13.5E+3	5.667	
	20:1.2D+1.0DI	5.667	15.7E+3	5.667		-16.7E+3	5.667	
	21:1.0D+1.0WI	5.667	5.19E+3	5.667		-5.32E+3	5.667	
	22:1.0D+1.0WI	5.667	2.75E+3	5.667		-2.88E+3	5.667	
	23:1.0D-1.0WL	5.667	790.137	0.000		-980.190	0.000	
	24:1.0D-1.0WL	5.667	2.9E+3	5.667		-3.11E+3	5.667	
	25:1.4D	5.667	3.94E+3	5.667		-4.17E+3	5.667	
	26:1.2D+1.5LM	5.667	4.05E+3	5.667		-4.25E+3	5.667	
	27:1.2D+1.5LM	5.667	3.36E+3	5.667		-3.55E+3	5.667	
	28:1.2D+1.5LM	5.667	2.72E+3	5.667		-2.93E+3	5.667	
	29:1.2D+1.5LM	5.667	3.4E+3	5.667		-3.62E+3	5.667	
	30:1.2D+1.5LV	5.667	3.35E+3	5.667		-3.55E+3	5.667	
197	1:DEAD	5.667	2.82E+3	0.000		-2.99E+3	0.000	
	2:WL#1	5.667	3.41E+3	5.667		-3.49E+3	5.667	
	3:WL#4	5.667	6.05E+3	0.000		-6.02E+3	0.000	
	4:DI	5.667	12.3E+3	0.000		-13E+3	0.000	
	5:WLI#1	5.667	1.53E+3	5.667		-1.57E+3	5.667	
	6:WLI#4	5.667	2.73E+3	0.000		-2.72E+3	0.000	
	7:WLS#1	5.667	1.2E+3	5.667		-1.23E+3	5.667	
	8:WLS#4	5.667	2.13E+3	0.000		-2.11E+3	0.000	
	9:WLM#1	5.667	340.851	5.667		-349.079	5.667	
	10:WLM#4	5.667	604.110	0.000		-601.319	0.000	
	11:LM	5.667	28.299	0.000		-29.433	0.000	
	12:LV	5.667	36.373	0.000		-34.663	0.000	
	13:1.2D+1.6WI	5.667	2.87E+3	5.667		-3.2E+3	5.667	
	14:1.2D+1.6WI	5.667	6.13E+3	0.000		-6.29E+3	0.000	
	15:1.2D-1.6WL	5.667	8.5E+3	0.000		-8.5E+3	0.000	
	16:1.2D-1.6WL	5.667	13E+3	0.000		-13.2E+3	0.000	
	17:1.2D+1.0DI	5.667	14.3E+3	0.000		-15.3E+3	0.000	
	18:1.2D+1.0DI	5.667	13E+3	0.000		-13.9E+3	0.000	
	19:1.2D+1.0DI	5.667	17.1E+3	0.000		-17.9E+3	0.000	
	20:1.2D+1.0DI	5.667	18.4E+3	0.000		-19.3E+3	0.000	
	21:1.0D+1.0WI	5.667	1.75E+3	0.000		-1.96E+3	0.000	



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No 50103542	Sheet No 88	Rev 1
Part		
Ref		
By DAP	Date 5/13/19	Chd BK
File Rocky Hill CT.std	Date/Time 13-May-2019 16:22	

Job Title Rocky Hill CT

Client VZW

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	22:1.0D+1.0WI	5.667	750.529	0.000		-907.356	0.000	
	23:1.0D-1.0WL	5.667	3.93E+3	0.000		-4.05E+3	0.000	
	24:1.0D-1.0WL	5.667	4.93E+3	0.000		-5.1E+3	0.000	
	25:1.4D	5.667	3.95E+3	0.000		-4.18E+3	0.000	
	26:1.2D+1.5LV	5.667	3.11E+3	0.000		-3.33E+3	0.000	
	27:1.2D+1.5LV	5.667	2.83E+3	0.000		-3.03E+3	0.000	
	28:1.2D+1.5LV	5.667	3.74E+3	0.000		-3.92E+3	0.000	
	29:1.2D+1.5LV	5.667	4.02E+3	0.000		-4.22E+3	0.000	
	30:1.2D+1.5LV	5.667	3.36E+3	0.000		-3.56E+3	0.000	
198	1:DEAD	5.667	2.75E+3	5.667		-2.91E+3	5.667	
	2:WL#1	5.667	3.15E+3	0.000		-3.25E+3	0.000	
	3:WL#4	5.667	5.99E+3	5.667		-6.02E+3	5.667	
	4:DI	5.667	11.2E+3	5.667		-11.9E+3	5.667	
	5:WLI#1	5.667	1.48E+3	0.000		-1.53E+3	0.000	
	6:WLI#4	5.667	2.71E+3	5.667		-2.72E+3	5.667	
	7:WLS#1	5.667	1.11E+3	0.000		-1.14E+3	0.000	
	8:WLS#4	5.667	2.1E+3	5.667		-2.11E+3	5.667	
	9:WLM#1	5.667	316.679	0.000		-326.048	0.000	
	10:WLM#4	5.667	597.947	5.667		-600.810	5.667	
	11:LM	5.667	28.295	5.667		-29.429	5.667	
	12:LV	5.667	11.606	0.000		-13.348	0.000	
	13:1.2D+1.6WI	5.667	2.72E+3	0.000		-3.06E+3	0.000	
	14:1.2D+1.6WI	5.667	12.9E+3	5.667		-13.1E+3	5.667	
	15:1.2D-1.6WL	5.667	8.05E+3	5.667		-8.03E+3	5.667	
	16:1.2D-1.6WL	5.667	6.17E+3	5.667		-6.32E+3	5.667	
	17:1.2D+1.0DI	5.667	13.1E+3	5.667		-14.1E+3	5.667	
	18:1.2D+1.0DI	5.667	17.2E+3	5.667		-18.1E+3	5.667	
	19:1.2D+1.0DI	5.667	15.9E+3	5.667		-16.7E+3	5.667	
	20:1.2D+1.0DI	5.667	11.8E+3	5.667		-12.7E+3	5.667	
	21:1.0D+1.0WI	5.667	1.77E+3	5.667		-1.98E+3	5.667	
	22:1.0D+1.0WI	5.667	4.84E+3	5.667		-5.02E+3	5.667	
	23:1.0D-1.0WL	5.667	3.78E+3	5.667		-3.89E+3	5.667	
	24:1.0D-1.0WL	5.667	696.397	5.667		-849.918	5.667	
	25:1.4D	5.667	3.85E+3	5.667		-4.08E+3	5.667	
	26:1.2D+1.5LV	5.667	3.05E+3	5.667		-3.26E+3	5.667	
	27:1.2D+1.5LV	5.667	3.93E+3	5.667		-4.13E+3	5.667	
	28:1.2D+1.5LV	5.667	3.63E+3	5.667		-3.81E+3	5.667	
	29:1.2D+1.5LV	5.667	2.75E+3	5.667		-2.94E+3	5.667	
	30:1.2D+1.5LV	5.667	3.3E+3	5.667		-3.5E+3	5.667	
199	1:DEAD	5.667	2.75E+3	0.000		-2.91E+3	0.000	
	2:WL#1	5.667	6.64E+3	0.000		-6.57E+3	0.000	
	3:WL#4	5.667	906.032	0.472		-1.01E+3	0.000	
	4:DI	5.667	11.2E+3	0.000		-11.9E+3	0.000	
	5:WLI#1	5.667	3.11E+3	0.000		-3.08E+3	0.000	



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
89

Rev
1

Job Title Rocky Hill CT

Ref

By DAP

Date 5/13/19

Chd BK

Client VZW

File Rocky Hill CT.std

Date/Time 13-May-2019 16:22

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	6:WLI#4	5.667	349.012	1.889		-401.578	1.889	
	7:WLS#1	5.667	2.33E+3	0.000		-2.31E+3	0.000	
	8:WLS#4	5.667	320.370	0.000		-358.923	0.000	
	9:WLM#1	5.667	667.127	0.000		-660.270	0.000	
	10:WLM#4	5.667	86.935	0.472		-97.937	0.472	
	11:LM	5.667	23.211	5.667		-26.696	5.667	
	12:LV	5.667	14.150	0.000		-14.717	0.000	
	13:1.2D+1.6WI	5.667	13.8E+3	0.000		-13.9E+3	0.000	
	14:1.2D+1.6WI	5.667	4.07E+3	0.000		-4.44E+3	0.000	
	15:1.2D-1.6WL	5.667	7.31E+3	5.667		-7.54E+3	5.667	
	16:1.2D-1.6WL	5.667	3.14E+3	5.667		-3.2E+3	5.667	
	17:1.2D+1.0DI	5.667	17.5E+3	0.000		-18.4E+3	0.000	
	18:1.2D+1.0DI	5.667	14.7E+3	0.000		-15.6E+3	0.000	
	19:1.2D+1.0DI	5.667	11.5E+3	0.000		-12.5E+3	0.000	
	20:1.2D+1.0DI	5.667	14.4E+3	0.000		-15.2E+3	0.000	
	21:1.0D+1.0WI	5.667	5.04E+3	0.000		-5.18E+3	0.000	
	22:1.0D+1.0WI	5.667	2.88E+3	0.000		-3.09E+3	0.000	
	23:1.0D-1.0WL	5.667	787.383	5.667		-959.474	5.667	
	24:1.0D-1.0WL	5.667	2.65E+3	0.000		-2.78E+3	0.000	
	25:1.4D	5.667	3.85E+3	0.000		-4.08E+3	0.000	
	26:1.2D+1.5LV	5.667	3.95E+3	0.000		-4.15E+3	0.000	
	27:1.2D+1.5LV	5.667	3.34E+3	0.000		-3.55E+3	0.000	
	28:1.2D+1.5LV	5.667	2.66E+3	0.000		-2.87E+3	0.000	
	29:1.2D+1.5LV	5.667	3.27E+3	0.000		-3.46E+3	0.000	
	30:1.2D+1.5LV	5.667	3.32E+3	0.000		-3.52E+3	0.000	
200	1:DEAD	5.667	2.82E+3	5.667		-2.99E+3	5.667	
	2:WL#1	5.667	3.74E+3	5.667		-3.66E+3	5.667	
	3:WL#4	5.667	5.32E+3	5.667		-5.43E+3	5.667	
	4:DI	5.667	12.1E+3	5.667		-12.9E+3	5.667	
	5:WLI#1	5.667	1.73E+3	5.667		-1.69E+3	5.667	
	6:WLI#4	5.667	2.44E+3	5.667		-2.51E+3	5.667	
	7:WLS#1	5.667	1.31E+3	5.667		-1.29E+3	5.667	
	8:WLS#4	5.667	1.87E+3	5.667		-1.91E+3	5.667	
	9:WLM#1	5.667	375.103	5.667		-366.839	5.667	
	10:WLM#4	5.667	531.297	5.667		-543.409	5.667	
	11:LM	5.667	72.743	5.667		-69.323	5.667	
	12:LV	5.667	14.147	5.667		-14.714	5.667	
	13:1.2D+1.6WI	5.667	2.42E+3	5.667		-2.49E+3	5.667	
	14:1.2D+1.6WI	5.667	5.95E+3	0.000		-6.25E+3	0.000	
	15:1.2D-1.6WL	5.667	9.23E+3	5.667		-9.56E+3	5.667	
	16:1.2D-1.6WL	5.667	12E+3	5.667		-12E+3	5.667	
	17:1.2D+1.0DI	5.667	13.8E+3	5.667		-14.7E+3	5.667	
	18:1.2D+1.0DI	5.667	13.1E+3	5.667		-14.1E+3	5.667	
	19:1.2D+1.0DI	5.667	17.2E+3	5.667		-18.2E+3	5.667	



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
90

Rev
1

Job Title Rocky Hill CT

Ref

By DAP

Date 5/13/19

Chd BK

Client VZW

File Rocky Hill CT.std

Date/Time 13-May-2019 16:22

Beam Combined Axial and Bending Stresses Summary Cont...

Beam	L/C	Length (ft)	Max Comp			Max Tens		
			Stress (psi)	d (ft)	Corner	Stress (psi)	d (ft)	Corner
	20:1.2D+1.0DI-	5.667	18E+3	5.667		-18.8E+3	5.667	
	21:1.0D+1.0WI	5.667	1.54E+3	5.667		-1.68E+3	5.667	
	22:1.0D+1.0WI	5.667	1.07E+3	5.667		-1.27E+3	5.667	
	23:1.0D-1.0WL	5.667	4.1E+3	5.667		-4.3E+3	5.667	
	24:1.0D-1.0WL	5.667	4.69E+3	5.667		-4.82E+3	5.667	
	25:1.4D	5.667	3.95E+3	5.667		-4.18E+3	5.667	
	26:1.2D+1.5LM	5.667	2.97E+3	5.667		-3.16E+3	5.667	
	27:1.2D+1.5LM	5.667	2.82E+3	5.667		-3.03E+3	5.667	
	28:1.2D+1.5LM	5.667	3.71E+3	5.667		-3.91E+3	5.667	
	29:1.2D+1.5LM	5.667	3.87E+3	5.667		-4.05E+3	5.667	
	30:1.2D+1.5LV	5.667	3.4E+3	5.667		-3.6E+3	5.667	
201	1:DEAD	5.667	2.81E+3	0.000		-2.98E+3	0.000	
	2:WL#1	5.667	3.88E+3	0.000		-3.81E+3	0.000	
	3:WL#4	5.667	5.47E+3	5.667		-5.33E+3	5.667	
	4:DI	5.667	11.4E+3	0.000		-12.2E+3	0.000	
	5:WLI#1	5.667	1.75E+3	0.000		-1.71E+3	0.000	
	6:WLI#4	5.667	2.5E+3	0.000		-2.45E+3	0.000	
	7:WLS#1	5.667	1.37E+3	0.000		-1.34E+3	0.000	
	8:WLS#4	5.667	1.92E+3	5.667		-1.87E+3	5.667	
	9:WLM#1	5.667	389.047	0.000		-381.635	0.000	
	10:WLM#4	5.667	547.272	5.667		-532.778	5.667	
	11:LM	5.667	72.742	0.000		-69.323	0.000	
	12:LV	5.667	11.605	5.667		-13.348	5.667	
	13:1.2D+1.6WI	5.667	2.66E+3	0.000		-2.74E+3	0.000	
	14:1.2D+1.6WI	5.667	12E+3	0.000		-12E+3	0.000	
	15:1.2D-1.6WL	5.667	9.47E+3	0.000		-9.79E+3	0.000	
	16:1.2D-1.6WL	5.667	6.04E+3	5.667		-6.48E+3	5.667	
	17:1.2D+1.0DI-	5.667	13.1E+3	0.000		-14E+3	0.000	
	18:1.2D+1.0DI-	5.667	17.2E+3	0.000		-18.1E+3	0.000	
	19:1.2D+1.0DI-	5.667	16.5E+3	0.000		-17.5E+3	0.000	
	20:1.2D+1.0DI-	5.667	12.4E+3	0.000		-13.4E+3	0.000	
	21:1.0D+1.0WI	5.667	1.48E+3	0.000		-1.62E+3	0.000	
	22:1.0D+1.0WI	5.667	4.68E+3	0.000		-4.8E+3	0.000	
	23:1.0D-1.0WL	5.667	4.15E+3	0.000		-4.34E+3	0.000	
	24:1.0D-1.0WL	5.667	1.07E+3	0.000		-1.29E+3	0.000	
	25:1.4D	5.667	3.94E+3	0.000		-4.17E+3	0.000	
	26:1.2D+1.5LM	5.667	2.95E+3	0.000		-3.14E+3	0.000	
	27:1.2D+1.5LM	5.667	3.86E+3	0.000		-4.04E+3	0.000	
	28:1.2D+1.5LM	5.667	3.71E+3	0.000		-3.92E+3	0.000	
	29:1.2D+1.5LM	5.667	2.81E+3	0.000		-3.03E+3	0.000	
	30:1.2D+1.5LV	5.667	3.38E+3	0.000		-3.58E+3	0.000	



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
91

Rev
1

Job Title **Rocky Hill CT**

Part

Ref

By **DAP**


Date **5/13/19**

Chd **BK**

Client **VZW**

File **Rocky Hill CT.std**

Date/Time **13-May-2019 16:22**



Stresses

Utilization Ratio

Beam	Analysis Property	Design Property	Actual Ratio	Allowable Ratio	Ratio (Act./Allow.)	Clause	L/C	Ax (in ²)	Iz (in ⁴)	Iy (in ⁴)	Ix (in ⁴)
1	L30303 LD	L30303 LD	0.197	1.000	0.197	LRFD-H1-1B-	17	2.186	1.928	3.396	0.026
2	L30303 LD	L30303 LD	0.196	1.000	0.196	LRFD-H1-1B-	19	2.186	1.928	3.396	0.026
3	L30303 LD	L30303 LD	0.208	1.000	0.208	LRFD-H1-1B-	20	2.186	1.928	3.396	0.026
4	HSST4X4X0	HSST4X4X0	0.421	1.000	0.421	HSS T+SH+F	18	3.370	7.800	7.800	12.800
5	HSST4X4X0	HSST4X4X0	0.742	1.000	0.742	HSS T+SH+F	19	3.370	7.800	7.800	12.800
6	HSST4X4X0	HSST4X4X0	0.753	1.000	0.753	HSS T+SH+F	20	3.370	7.800	7.800	12.800
7	PIPS20	PIPS20	0.001	1.000	0.001	LRFD-H1-1B-	13	1.000	0.627	0.627	1.254
9	PIPS20	PIPS20	0.001	1.000	0.001	LRFD-H1-1B-	13	1.000	0.627	0.627	1.254
10	PIPS20	PIPS20	0.001	1.000	0.001	LRFD-H1-1B-	13	1.000	0.627	0.627	1.254
11	PIPS20	PIPS20	0.001	1.000	0.001	LRFD-H1-1B-	13	1.000	0.627	0.627	1.254
13	PIPS20	PIPS20	0.001	1.000	0.001	LRFD-H1-1B-	13	1.000	0.627	0.627	1.254
14	PIPS20	PIPS20	0.001	1.000	0.001	LRFD-H1-1B-	13	1.000	0.627	0.627	1.254
15	PIPS20	PIPS20	0.001	1.000	0.001	LRFD-H1-1B-	13	1.000	0.627	0.627	1.254
17	PIPS20	PIPS20	0.001	1.000	0.001	LRFD-H1-1B-	13	1.000	0.627	0.627	1.254
18	PIPS20	PIPS20	0.001	1.000	0.001	LRFD-H1-1B-	13	1.000	0.627	0.627	1.254
19	L30304	L30304	0.141	1.000	0.141	LRFD-H1-1B-	20	1.438	0.504	1.985	0.030
20	L30304	L30304	0.543	1.000	0.543	LRFD-H1-1B-	18	1.438	0.504	1.985	0.030
21	L30304	L30304	0.115	1.000	0.115	LRFD-H1-1B-	17	1.438	0.504	1.985	0.030
22	L30304	L30304	0.602	1.000	0.602	LRFD-H1-1B-	20	1.438	0.504	1.985	0.030
23	L30304	L30304	0.137	1.000	0.137	LRFD-H1-1B-	17	1.438	0.504	1.985	0.030
24	L30304	L30304	0.592	1.000	0.592	LRFD-H1-1B-	19	1.438	0.504	1.985	0.030
25	L30304	L30304	0.169	1.000	0.169	LRFD-H1-1B-	18	1.438	0.504	1.985	0.030
26	L30304	L30304	0.467	1.000	0.467	LRFD-H1-1B-	17	1.438	0.504	1.985	0.030
27	L30304	L30304	0.177	1.000	0.177	LRFD-H1-1B-	17	1.438	0.504	1.985	0.030



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job Title Rocky Hill CT

Client VZW

Job No
50103542

Sheet No
92

Rev
1

Part

Ref

By DAP

Date 5/13/19

Chd BK

File Rocky Hill CT.std

Date/Time 13-May-2019 16:22

Utilization Ratio Cont...

Beam	Analysis Property	Design Property	Actual Ratio	Allowable Ratio	Ratio (Act./Allow.)	Clause	L/C	Ax (in ²)	Iz (in ⁴)	Iy (in ⁴)	Ix (in ⁴)
28	L30304	L30304	0.500	1.000	0.500	LRFD-H1-1B-	20	1.438	0.504	1.985	0.030
29	L30304	L30304	0.187	1.000	0.187	LRFD-H1-1B-	20	1.438	0.504	1.985	0.030
30	L30304	L30304	0.464	1.000	0.464	LRFD-H1-1B-	19	1.438	0.504	1.985	0.030
43	HSST4X4X0	HSST4X4X0	0.712	1.000	0.712	HSS T+SH+F	18	3.370	7.800	7.800	12.800
44	HSST4X4X0	HSST4X4X0	0.441	1.000	0.441	HSS T+SH+F	19	3.370	7.800	7.800	12.800
45	HSST4X4X0	HSST4X4X0	0.444	1.000	0.444	HSS T+SH+F	20	3.370	7.800	7.800	12.800
48	PIPS20	PIPS20	0.635	1.000	0.635	LRFD-H1-1B-	16	1.000	0.627	0.627	1.254
51	PIPS20	PIPS20	0.648	1.000	0.648	LRFD-H1-1B-	14	1.000	0.627	0.627	1.254
54	PIPS20	PIPS20	0.675	1.000	0.675	LRFD-H1-1B-	13	1.000	0.627	0.627	1.254
55	L30304	L30304	0.270	1.000	0.270	LRFD-H1-1B-	17	1.438	0.504	1.985	0.030
56	L30304	L30304	0.139	1.000	0.139	LRFD-H1-1B-	20	1.438	0.504	1.985	0.030
57	L30304	L30304	0.305	1.000	0.305	LRFD-H1-1B-	20	1.438	0.504	1.985	0.030
58	L30304	L30304	0.123	1.000	0.123	LRFD-H1-1B-	19	1.438	0.504	1.985	0.030
59	L30304	L30304	0.291	1.000	0.291	LRFD-H1-1B-	19	1.438	0.504	1.985	0.030
60	L30304	L30304	0.117	1.000	0.117	LRFD-H1-1B-	18	1.438	0.504	1.985	0.030
101	PIPS20	PIPS20	0.001	1.000	0.001	LRFD-H1-1B-	13	1.000	0.627	0.627	1.254
102	PIPS20	PIPS20	0.001	1.000	0.001	LRFD-H1-1B-	13	1.000	0.627	0.627	1.254
103	PIPS20	PIPS20	0.001	1.000	0.001	LRFD-H1-1B-	13	1.000	0.627	0.627	1.254
104	PIPS20	PIPS20	0.001	1.000	0.001	LRFD-H1-1B-	13	1.000	0.627	0.627	1.254
105	PIPS20	PIPS20	0.001	1.000	0.001	LRFD-H1-1B-	13	1.000	0.627	0.627	1.254
106	PIPS20	PIPS20	0.001	1.000	0.001	LRFD-H1-1B-	13	1.000	0.627	0.627	1.254
107	PIPS20	PIPS20	0.001	1.000	0.001	LRFD-H1-1B-	13	1.000	0.627	0.627	1.254
108	PIPS20	PIPS20	0.001	1.000	0.001	LRFD-H1-1B-	13	1.000	0.627	0.627	1.254
109	PIPS20	PIPS20	0.001	1.000	0.001	LRFD-H1-1B-	13	1.000	0.627	0.627	1.254
110	PIPS20	PIPS20	0.065	1.000	0.065	LRFD-H1-1B-	14	1.000	0.627	0.627	1.254
111	PIPS20	PIPS20	0.065	1.000	0.065	LRFD-H1-1B-	14	1.000	0.627	0.627	1.254
112	PIPS20	PIPS20	0.071	1.000	0.071	LRFD-H1-1B-	13	1.000	0.627	0.627	1.254
113	PIPS20	PIPS20	0.015	1.000	0.015	LRFD-H1-1B-	14	1.000	0.627	0.627	1.254
114	PIPS20	PIPS20	0.015	1.000	0.015	LRFD-H1-1B-	14	1.000	0.627	0.627	1.254
115	PIPS20	PIPS20	0.027	1.000	0.027	LRFD-H1-1B-	14	1.000	0.627	0.627	1.254
116	PIPS20	PIPS20	0.027	1.000	0.027	LRFD-H1-1B-	14	1.000	0.627	0.627	1.254
117	PIPS20	PIPS20	0.027	1.000	0.027	LRFD-H1-1B-	13	1.000	0.627	0.627	1.254
118	PIPS20	PIPS20	0.027	1.000	0.027	LRFD-H1-1B-	13	1.000	0.627	0.627	1.254
122	HSST4X4X0	HSST4X4X0	0.598	1.000	0.598	HSS T+SH+F	20	3.370	7.800	7.800	12.800
123	PIPS20	PIPS20	0.053	1.000	0.053	LRFD-H1-1B-	14	1.000	0.627	0.627	1.254
124	PIPS20	PIPS20	0.030	1.000	0.030	LRFD-H1-1B-	13	1.000	0.627	0.627	1.254
125	PIPS20	PIPS20	0.129	1.000	0.129	LRFD-H1-1B-	14	1.000	0.627	0.627	1.254
127	PIPS20	PIPS20	0.030	1.000	0.030	LRFD-H1-1B-	13	1.000	0.627	0.627	1.254
128	PIPS20	PIPS20	0.140	1.000	0.140	LRFD-H1-1B-	13	1.000	0.627	0.627	1.254
129	PIPS20	PIPS20	0.054	1.000	0.054	LRFD-H1-1B-	13	1.000	0.627	0.627	1.254
130	PIPS20	PIPS20	0.053	1.000	0.053	LRFD-H1-1B-	14	1.000	0.627	0.627	1.254
131	PIPS20	PIPS20	0.129	1.000	0.129	LRFD-H1-1B-	14	1.000	0.627	0.627	1.254
132	PIPS20	PIPS20	0.054	1.000	0.054	LRFD-H1-1B-	13	1.000	0.627	0.627	1.254
133	L30304	L30304	0.315	1.000	0.315	LRFD-H1-1B-	20	1.438	0.504	1.985	0.030
134	L30304	L30304	0.490	1.000	0.490	LRFD-H1-1B-	19	1.438	0.504	1.985	0.030

 Software licensed to DEWBERRY CONNECTED User: Deep Patel	Job No 50103542	Sheet No 93	Rev 1
	Part		
Job Title Rocky Hill CT	Ref		
	By DAP	Date 5/13/19	Chd BK
Client VZW	File Rocky Hill CT.std	Date/Time 13-May-2019 16:22	

Utilization Ratio Cont...

Beam	Analysis Property	Design Property	Actual Ratio	Allowable Ratio	Ratio (Act./Allow.)	Clause	L/C	Ax (in ²)	Iz (in ⁴)	Iy (in ⁴)	Ix (in ⁴)
135	L30304	L30304	0.247	1.000	0.247	LRFD-H1-1B-	19	1.438	0.504	1.985	0.030
136	L30304	L30304	0.610	1.000	0.610	LRFD-H1-1B-	19	1.438	0.504	1.985	0.030
137	L30304	L30304	0.234	1.000	0.234	LRFD-H1-1B-	19	1.438	0.504	1.985	0.030
138	L30304	L30304	0.295	1.000	0.295	LRFD-H1-1B-	19	1.438	0.504	1.985	0.030
139	L30304	L30304	0.294	1.000	0.294	LRFD-H1-1B-	18	1.438	0.504	1.985	0.030
140	L30304	L30304	0.171	1.000	0.171	LRFD-H1-1B-	18	1.438	0.504	1.985	0.030
141	L30304	L30304	0.249	1.000	0.249	LRFD-H1-1B-	20	1.438	0.504	1.985	0.030
142	L30304	L30304	0.308	1.000	0.308	LRFD-H1-1B-	17	1.438	0.504	1.985	0.030
143	L30304	L30304	0.323	1.000	0.323	LRFD-H1-1B-	20	1.438	0.504	1.985	0.030
144	L30304	L30304	0.189	1.000	0.189	LRFD-H1-1B-	20	1.438	0.504	1.985	0.030
145	L30304	L30304	0.229	1.000	0.229	LRFD-H1-1B-	17	1.438	0.504	1.985	0.030
146	L30304	L30304	0.576	1.000	0.576	LRFD-H1-1B-	20	1.438	0.504	1.985	0.030
147	L30304	L30304	0.306	1.000	0.306	LRFD-H1-1B-	17	1.438	0.504	1.985	0.030
148	L30304	L30304	0.476	1.000	0.476	LRFD-H1-1B-	17	1.438	0.504	1.985	0.030
149	L30304	L30304	0.300	1.000	0.300	LRFD-H1-1B-	17	1.438	0.504	1.985	0.030
150	L30304	L30304	0.175	1.000	0.175	LRFD-H1-1B-	17	1.438	0.504	1.985	0.030
151	L30304	L30304	0.219	1.000	0.219	LRFD-H1-1B-	17	1.438	0.504	1.985	0.030
152	L30304	L30304	0.272	1.000	0.272	LRFD-H1-1B-	18	1.438	0.504	1.985	0.030
153	L30304	L30304	0.296	1.000	0.296	LRFD-H1-1B-	18	1.438	0.504	1.985	0.030
154	L30304	L30304	0.465	1.000	0.465	LRFD-H1-1B-	18	1.438	0.504	1.985	0.030
155	L30304	L30304	0.224	1.000	0.224	LRFD-H1-1B-	18	1.438	0.504	1.985	0.030
156	L30304	L30304	0.545	1.000	0.545	LRFD-H1-1B-	18	1.438	0.504	1.985	0.030
175	PIPS20	PIPS20	0.459	1.000	0.459	LRFD-H1-1B-	17	1.000	0.627	0.627	1.254
176	PIPS20	PIPS20	0.182	1.000	0.182	LRFD-H1-1B-	15	1.000	0.627	0.627	1.254
177	PIPS20	PIPS20	0.285	1.000	0.285	LRFD-H1-1B-	16	1.000	0.627	0.627	1.254
179	PIPS20	PIPS20	0.465	1.000	0.465	LRFD-H1-1B-	20	1.000	0.627	0.627	1.254
180	PIPS20	PIPS20	0.177	1.000	0.177	LRFD-H1-1B-	16	1.000	0.627	0.627	1.254
181	PIPS20	PIPS20	0.291	1.000	0.291	LRFD-H1-1B-	14	1.000	0.627	0.627	1.254
183	PIPS20	PIPS20	0.473	1.000	0.473	LRFD-H1-1B-	18	1.000	0.627	0.627	1.254
184	PIPS20	PIPS20	0.160	1.000	0.160	LRFD-H1-1B-	15	1.000	0.627	0.627	1.254
185	PIPS20	PIPS20	0.342	1.000	0.342	LRFD-H1-1B-	13	1.000	0.627	0.627	1.254
188	PIPS20	PIPS20	0.452	1.000	0.452	LRFD-H1-1B-	18	1.000	0.627	0.627	1.254
189	PIPS20	PIPS20	0.181	1.000	0.181	LRFD-H1-1B-	16	1.000	0.627	0.627	1.254
191	PIPS20	PIPS20	0.484	1.000	0.484	LRFD-H1-1B-	17	1.000	0.627	0.627	1.254
192	PIPS20	PIPS20	0.178	1.000	0.178	LRFD-H1-1B-	15	1.000	0.627	0.627	1.254
194	PIPS20	PIPS20	0.455	1.000	0.455	LRFD-H1-1B-	20	1.000	0.627	0.627	1.254
195	PIPS20	PIPS20	0.160	1.000	0.160	LRFD-H1-1B-	15	1.000	0.627	0.627	1.254
196	PIPS20	PIPS20	0.442	1.000	0.442	LRFD-H1-1B-	17	1.000	0.627	0.627	1.254
197	PIPS20	PIPS20	0.437	1.000	0.437	LRFD-H1-1B-	20	1.000	0.627	0.627	1.254
198	PIPS20	PIPS20	0.409	1.000	0.409	LRFD-H1-1B-	18	1.000	0.627	0.627	1.254
199	PIPS20	PIPS20	0.417	1.000	0.417	LRFD-H1-1B-	17	1.000	0.627	0.627	1.254
200	PIPS20	PIPS20	0.426	1.000	0.426	LRFD-H1-1B-	20	1.000	0.627	0.627	1.254
201	PIPS20	PIPS20	0.411	1.000	0.411	LRFD-H1-1B-	18	1.000	0.627	0.627	1.254



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
94

Rev
1

Part

Job Title Rocky Hill CT

Ref

By DAP

Date 5/13/19

Chd BK


Client VZW

File Rocky Hill CT.std

Date/Time 13-May-2019 16:22

Failed Members

There is no data of this type.



Utility Ratio



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
1

Rev
1

Job Title **Rocky Hill CT**

Part

Ref

By **DAP**

Date **5/13/19**

Chd **BK**

Client **VZW**

File **Rocky Hill CT.std**

Date/Time **13-May-2019 16:22**

Node Displacements

Node	L/C	X (in)	Y (in)	Z (in)	Resultant (in)	rX (rad)	rY (rad)	rZ (rad)
1	21:1.0D+1.0WI	0.000	-0.074	-0.001	0.074	-0.003	-0.000	0.000
	22:1.0D+1.0WI	0.001	-0.040	0.000	0.040	-0.001	-0.000	0.000
	23:1.0D-1.0WL	-0.000	-0.007	0.001	0.007	-0.000	0.000	-0.000
	24:1.0D-1.0WL	-0.001	-0.040	0.000	0.040	-0.001	0.000	-0.000
2	21:1.0D+1.0WI	0.000	-0.216	-0.001	0.216	-0.003	-0.000	0.000
	22:1.0D+1.0WI	0.001	-0.106	0.000	0.106	-0.001	-0.000	-0.001
	23:1.0D-1.0WL	-0.000	0.005	0.001	0.005	0.001	0.000	0.000
	24:1.0D-1.0WL	-0.001	-0.105	0.000	0.105	-0.001	0.000	0.001
3	21:1.0D+1.0WI	-0.000	-0.024	-0.001	0.024	0.000	0.000	-0.001
	22:1.0D+1.0WI	0.001	-0.069	0.000	0.069	0.001	0.000	-0.002
	23:1.0D-1.0WL	0.000	-0.057	0.000	0.057	0.001	-0.000	-0.002
	24:1.0D-1.0WL	-0.001	-0.012	-0.000	0.012	0.000	-0.000	-0.000
4	21:1.0D+1.0WI	-0.000	-0.050	-0.001	0.050	-0.001	0.000	-0.001
	22:1.0D+1.0WI	0.001	-0.199	-0.000	0.199	0.001	-0.000	-0.002
	23:1.0D-1.0WL	-0.000	-0.161	0.001	0.161	0.002	-0.000	-0.001
	24:1.0D-1.0WL	-0.001	-0.012	0.000	0.012	0.000	-0.000	0.001
5	21:1.0D+1.0WI	-0.000	-0.055	-0.001	0.055	-0.001	-0.000	0.001
	22:1.0D+1.0WI	0.001	-0.016	-0.000	0.016	0.000	0.000	-0.001
	23:1.0D-1.0WL	0.000	-0.166	0.001	0.166	0.002	0.000	0.001
	24:1.0D-1.0WL	-0.001	-0.205	-0.000	0.205	0.001	-0.000	0.003
6	21:1.0D+1.0WI	-0.000	-0.025	-0.001	0.025	0.000	-0.000	0.001
	22:1.0D+1.0WI	0.001	-0.013	-0.000	0.013	0.000	0.000	0.000
	23:1.0D-1.0WL	0.000	-0.059	0.001	0.059	0.001	0.000	0.002
	24:1.0D-1.0WL	-0.001	-0.071	0.000	0.071	0.001	-0.000	0.002
7	21:1.0D+1.0WI	-0.000	-0.037	-0.000	0.037	-0.001	0.000	-0.001
	22:1.0D+1.0WI	0.000	-0.043	0.000	0.043	-0.001	-0.000	-0.002
	23:1.0D-1.0WL	0.000	-0.021	0.001	0.021	0.000	-0.000	-0.001
	24:1.0D-1.0WL	-0.000	-0.015	-0.000	0.015	-0.001	0.000	-0.000
8	21:1.0D+1.0WI	0.000	0.000	0.000	0.000	0.000	0.000	0.000
	22:1.0D+1.0WI	0.000	0.000	0.000	0.000	0.000	0.000	0.000
	23:1.0D-1.0WL	0.000	0.000	0.000	0.000	0.000	0.000	0.000
	24:1.0D-1.0WL	0.000	0.000	0.000	0.000	0.000	0.000	0.000
9	21:1.0D+1.0WI	0.000	0.000	0.000	0.000	0.000	0.000	0.000
	22:1.0D+1.0WI	0.000	0.000	0.000	0.000	0.000	0.000	0.000
	23:1.0D-1.0WL	0.000	0.000	0.000	0.000	0.000	0.000	0.000
	24:1.0D-1.0WL	0.000	0.000	0.000	0.000	0.000	0.000	0.000
10	21:1.0D+1.0WI	-0.000	-0.013	-0.000	0.013	0.000	-0.000	0.000
	22:1.0D+1.0WI	0.001	-0.030	-0.000	0.030	0.001	0.000	-0.001
	23:1.0D-1.0WL	0.000	-0.046	0.000	0.046	0.002	0.000	0.000
	24:1.0D-1.0WL	-0.001	-0.030	-0.000	0.030	0.001	-0.000	0.001
11	21:1.0D+1.0WI	0.000	0.000	0.000	0.000	0.000	0.000	0.000
	22:1.0D+1.0WI	0.000	0.000	0.000	0.000	0.000	0.000	0.000
	23:1.0D-1.0WL	0.000	0.000	0.000	0.000	0.000	0.000	0.000
	24:1.0D-1.0WL	0.000	0.000	0.000	0.000	0.000	0.000	0.000
12	21:1.0D+1.0WI	0.000	-0.038	-0.001	0.038	-0.001	-0.000	0.001



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
2

Rev
1

Part

Job Title **Rocky Hill CT**

Ref

By **DAP**

Date **5/13/19**

Chd **BK**

Client **VZW**

File **Rocky Hill CT.std**

Date/Time **13-May-2019 16:22**

Node Displacements Cont...

Node	L/C	X (in)	Y (in)	Z (in)	Resultant (in)	rX (rad)	rY (rad)	rZ (rad)
	22:1.0D+1.0WI	0.000	-0.015	-0.000	0.015	-0.001	-0.000	0.000
	23:1.0D-1.0WL	-0.000	-0.022	0.001	0.022	0.000	0.000	0.001
	24:1.0D-1.0WL	-0.000	-0.044	0.000	0.044	-0.001	0.000	0.002
13	21:1.0D+1.0WI	-0.000	-0.056	-0.001	0.056	-0.001	-0.000	-0.001
	22:1.0D+1.0WI	0.001	-0.170	-0.000	0.170	0.001	-0.000	-0.002
	23:1.0D-1.0WL	0.000	-0.127	0.001	0.127	0.002	-0.000	0.000
	24:1.0D-1.0WL	-0.001	-0.013	-0.000	0.014	0.001	-0.000	0.002
14	21:1.0D+1.0WI	-0.000	-0.006	-0.000	0.006	-0.001	0.000	-0.001
	22:1.0D+1.0WI	0.000	-0.007	0.000	0.007	-0.000	-0.000	-0.001
	23:1.0D-1.0WL	0.000	-0.004	0.000	0.004	-0.000	-0.000	-0.001
	24:1.0D-1.0WL	-0.000	-0.003	-0.000	0.003	-0.000	0.000	-0.000
15	21:1.0D+1.0WI	-0.000	-0.003	-0.000	0.003	0.000	-0.000	0.000
	22:1.0D+1.0WI	0.001	-0.005	-0.000	0.005	0.001	0.000	-0.000
	23:1.0D-1.0WL	0.000	-0.007	0.000	0.007	0.001	0.000	0.000
	24:1.0D-1.0WL	-0.001	-0.005	-0.000	0.005	0.001	-0.000	0.000
16	21:1.0D+1.0WI	0.000	-0.006	-0.001	0.006	-0.001	-0.000	0.001
	22:1.0D+1.0WI	0.000	-0.003	-0.000	0.003	-0.000	-0.000	0.000
	23:1.0D-1.0WL	-0.000	-0.004	0.001	0.004	-0.000	0.000	0.001
	24:1.0D-1.0WL	-0.000	-0.007	0.000	0.007	-0.000	0.000	0.001
17	21:1.0D+1.0WI	0.015	-0.056	-0.095	0.111	-0.002	-0.001	-0.001
	22:1.0D+1.0WI	0.108	-0.170	-0.001	0.201	0.000	-0.001	-0.002
	23:1.0D-1.0WL	-0.008	-0.127	0.098	0.161	0.002	0.000	0.000
	24:1.0D-1.0WL	-0.101	-0.013	0.005	0.102	0.000	0.000	0.002
18	21:1.0D+1.0WI	-0.008	-0.056	0.010	0.058	-0.001	-0.000	-0.001
	22:1.0D+1.0WI	-0.023	-0.170	-0.006	0.171	0.001	-0.000	-0.002
	23:1.0D-1.0WL	0.000	-0.127	-0.022	0.129	0.002	-0.000	0.000
	24:1.0D-1.0WL	0.015	-0.013	-0.006	0.021	0.001	-0.000	0.002
22	21:1.0D+1.0WI	0.000	-0.178	-0.001	0.178	-0.002	0.000	0.000
	22:1.0D+1.0WI	0.001	-0.101	0.000	0.101	-0.001	0.000	-0.002
	23:1.0D-1.0WL	-0.000	-0.005	0.001	0.005	0.001	0.000	0.000
	24:1.0D-1.0WL	-0.001	-0.082	-0.000	0.082	-0.000	0.000	0.002
23	21:1.0D+1.0WI	0.003	-0.178	0.024	0.180	-0.002	0.000	0.000
	22:1.0D+1.0WI	-0.015	-0.101	0.011	0.103	-0.001	0.000	-0.002
	23:1.0D-1.0WL	0.004	-0.005	-0.011	0.012	0.001	0.000	0.000
	24:1.0D-1.0WL	0.022	-0.082	0.002	0.085	-0.000	0.000	0.002
24	21:1.0D+1.0WI	0.005	-0.178	-0.101	0.205	-0.002	0.000	-0.000
	22:1.0D+1.0WI	0.108	-0.101	-0.017	0.149	-0.001	0.001	-0.002
	23:1.0D-1.0WL	-0.005	-0.005	0.093	0.094	0.002	0.000	0.000
	24:1.0D-1.0WL	-0.107	-0.082	0.009	0.135	0.000	-0.000	0.002
25	21:1.0D+1.0WI	-0.010	-0.037	0.012	0.040	-0.001	0.000	-0.001
	22:1.0D+1.0WI	-0.017	-0.043	0.006	0.047	-0.001	-0.000	-0.002
	23:1.0D-1.0WL	-0.009	-0.021	-0.001	0.023	0.000	-0.000	-0.001
	24:1.0D-1.0WL	-0.003	-0.015	0.005	0.016	-0.001	0.000	-0.000
26	21:1.0D+1.0WI	0.045	-0.037	-0.120	0.134	-0.002	0.000	-0.001
	22:1.0D+1.0WI	0.165	-0.043	-0.040	0.175	-0.001	-0.000	-0.004



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
3

Rev
1

Part

Job Title **Rocky Hill CT**

Ref

By **DAP**

Date **5/13/19**

Chd **BK**

Client **VZW**

File **Rocky Hill CT.std**

Date/Time **13-May-2019 16:22**

Node Displacements Cont...

Node	L/C	X (in)	Y (in)	Z (in)	Resultant (in)	rX (rad)	rY (rad)	rZ (rad)
	23:1.0D-1.0WL	-0.000	-0.021	0.095	0.097	0.002	-0.000	0.001
	24:1.0D-1.0WL	-0.120	-0.015	0.014	0.122	0.001	0.000	0.003
27	21:1.0D+1.0WI	0.000	-0.178	-0.001	0.178	-0.002	-0.000	-0.000
	22:1.0D+1.0WI	0.001	-0.083	-0.000	0.083	-0.000	-0.000	-0.002
	23:1.0D-1.0WL	-0.000	-0.006	0.001	0.006	0.001	-0.000	-0.000
	24:1.0D-1.0WL	-0.001	-0.101	0.000	0.101	-0.001	-0.000	0.002
28	21:1.0D+1.0WI	-0.005	-0.178	-0.103	0.206	-0.002	-0.000	0.000
	22:1.0D+1.0WI	0.107	-0.083	0.009	0.135	0.000	0.000	-0.002
	23:1.0D-1.0WL	0.000	-0.006	0.095	0.095	0.002	-0.000	-0.000
	24:1.0D-1.0WL	-0.112	-0.101	-0.017	0.152	-0.001	-0.001	0.002
29	21:1.0D+1.0WI	-0.002	-0.178	0.023	0.180	-0.002	-0.000	-0.000
	22:1.0D+1.0WI	-0.021	-0.083	0.002	0.085	-0.000	-0.000	-0.002
	23:1.0D-1.0WL	-0.004	-0.006	-0.010	0.012	0.001	-0.000	-0.000
	24:1.0D-1.0WL	0.015	-0.101	0.011	0.103	-0.001	-0.000	0.002
33	21:1.0D+1.0WI	-0.000	-0.061	-0.001	0.061	-0.001	0.000	0.001
	22:1.0D+1.0WI	0.001	-0.017	-0.000	0.017	0.001	0.000	-0.002
	23:1.0D-1.0WL	0.000	-0.131	0.001	0.131	0.002	0.000	0.000
	24:1.0D-1.0WL	-0.001	-0.174	-0.000	0.174	0.001	0.000	0.002
34	21:1.0D+1.0WI	0.009	-0.061	0.009	0.062	-0.001	0.000	0.001
	22:1.0D+1.0WI	-0.014	-0.017	-0.006	0.023	0.001	0.000	-0.002
	23:1.0D-1.0WL	0.001	-0.131	-0.022	0.133	0.002	0.000	0.000
	24:1.0D-1.0WL	0.024	-0.174	-0.007	0.176	0.001	0.000	0.002
35	21:1.0D+1.0WI	-0.019	-0.061	-0.099	0.117	-0.002	0.001	0.001
	22:1.0D+1.0WI	0.102	-0.017	0.006	0.104	0.000	-0.000	-0.002
	23:1.0D-1.0WL	0.007	-0.131	0.103	0.167	0.002	-0.000	-0.000
	24:1.0D-1.0WL	-0.114	-0.175	-0.002	0.209	0.000	0.001	0.003
36	21:1.0D+1.0WI	0.010	-0.038	0.012	0.041	-0.001	-0.000	0.001
	22:1.0D+1.0WI	0.003	-0.015	0.005	0.017	-0.001	-0.000	0.000
	23:1.0D-1.0WL	0.009	-0.022	-0.001	0.024	0.000	0.000	0.001
	24:1.0D-1.0WL	0.017	-0.044	0.006	0.047	-0.001	0.000	0.002
37	21:1.0D+1.0WI	-0.048	-0.038	-0.123	0.137	-0.002	-0.000	0.001
	22:1.0D+1.0WI	0.121	-0.016	0.016	0.123	0.001	-0.000	-0.003
	23:1.0D-1.0WL	-0.001	-0.022	0.098	0.100	0.002	0.000	-0.001
	24:1.0D-1.0WL	-0.170	-0.044	-0.041	0.180	-0.001	0.000	0.004
38	21:1.0D+1.0WI	-0.000	-0.044	-0.001	0.044	-0.002	-0.000	0.001
	22:1.0D+1.0WI	0.001	-0.026	-0.000	0.026	0.000	-0.000	-0.001
	23:1.0D-1.0WL	0.000	-0.148	0.001	0.148	0.002	-0.000	0.001
	24:1.0D-1.0WL	-0.001	-0.165	0.000	0.165	-0.000	-0.000	0.002
39	21:1.0D+1.0WI	-0.001	-0.044	-0.112	0.120	-0.002	0.000	-0.000
	22:1.0D+1.0WI	0.087	-0.026	0.008	0.091	0.000	-0.000	-0.001
	23:1.0D-1.0WL	-0.008	-0.148	0.120	0.191	0.003	-0.001	0.001
	24:1.0D-1.0WL	-0.097	-0.165	0.000	0.191	0.000	-0.000	0.002
40	21:1.0D+1.0WI	0.005	-0.044	0.019	0.048	-0.002	-0.000	0.001
	22:1.0D+1.0WI	-0.007	-0.026	-0.002	0.027	0.000	-0.000	-0.001
	23:1.0D-1.0WL	0.011	-0.148	-0.021	0.150	0.002	-0.000	0.001



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No

50103542

Sheet No

4

Rev

1

Part

Job Title Rocky Hill CT

Ref

By DAP

Date 5/13/19

Chd BK

Client VZW

File Rocky Hill CT.std

Date/Time 13-May-2019 16:22

Node Displacements Cont...

Node	L/C	X (in)	Y (in)	Z (in)	Resultant (in)	rX (rad)	rY (rad)	rZ (rad)
	24:1.0D-1.0WL	0.022	-0.165	0.001	0.167	-0.000	-0.000	0.002
44	21:1.0D+1.0WI	-0.000	-0.041	-0.001	0.041	-0.002	0.000	-0.000
	22:1.0D+1.0WI	0.001	-0.161	0.000	0.161	-0.000	0.000	-0.002
	23:1.0D-1.0WL	-0.000	-0.143	0.001	0.143	0.002	0.000	-0.001
	24:1.0D-1.0WL	-0.001	-0.023	-0.000	0.023	0.000	0.000	0.001
45	21:1.0D+1.0WI	-0.004	-0.041	0.019	0.045	-0.002	0.000	-0.000
	22:1.0D+1.0WI	-0.022	-0.161	0.000	0.163	-0.000	0.000	-0.002
	23:1.0D-1.0WL	-0.010	-0.143	-0.021	0.145	0.002	0.000	-0.001
	24:1.0D-1.0WL	0.007	-0.023	-0.002	0.024	0.000	0.000	0.001
46	21:1.0D+1.0WI	-0.003	-0.041	-0.110	0.117	-0.002	-0.000	0.000
	22:1.0D+1.0WI	0.094	-0.161	0.001	0.186	0.000	0.000	-0.002
	23:1.0D-1.0WL	0.007	-0.143	0.118	0.186	0.002	0.001	-0.001
	24:1.0D-1.0WL	-0.090	-0.023	0.007	0.093	0.000	0.000	0.001
47	21:1.0D+1.0WI	-0.000	-0.013	-0.004	0.014	0.000	-0.000	0.000
	22:1.0D+1.0WI	-0.006	-0.030	-0.011	0.032	0.001	0.000	-0.001
	23:1.0D-1.0WL	0.000	-0.046	-0.019	0.050	0.002	0.000	0.000
	24:1.0D-1.0WL	0.006	-0.030	-0.011	0.032	0.001	-0.000	0.001
48	21:1.0D+1.0WI	-0.002	-0.013	-0.137	0.137	-0.004	0.000	0.000
	22:1.0D+1.0WI	0.091	-0.030	0.028	0.100	0.000	0.000	-0.002
	23:1.0D-1.0WL	-0.001	-0.046	0.191	0.197	0.004	-0.000	0.000
	24:1.0D-1.0WL	-0.094	-0.030	0.026	0.102	0.000	-0.000	0.002
73	21:1.0D+1.0WI	0.012	-0.056	-0.086	0.103	-0.002	-0.001	-0.001
	22:1.0D+1.0WI	0.094	-0.170	-0.002	0.194	0.000	-0.001	-0.002
	23:1.0D-1.0WL	-0.007	-0.127	0.087	0.154	0.002	0.000	0.000
	24:1.0D-1.0WL	-0.089	-0.013	0.004	0.090	0.000	0.000	0.002
74	21:1.0D+1.0WI	0.004	-0.178	-0.088	0.199	-0.002	0.000	-0.000
	22:1.0D+1.0WI	0.096	-0.101	-0.012	0.140	-0.001	0.001	-0.002
	23:1.0D-1.0WL	-0.003	-0.005	0.083	0.083	0.002	0.000	0.000
	24:1.0D-1.0WL	-0.095	-0.082	0.007	0.126	0.000	-0.000	0.002
75	21:1.0D+1.0WI	0.038	-0.037	-0.106	0.118	-0.002	0.000	-0.001
	22:1.0D+1.0WI	0.142	-0.043	-0.034	0.153	-0.001	-0.000	-0.004
	23:1.0D-1.0WL	0.003	-0.021	0.082	0.085	0.002	-0.000	0.001
	24:1.0D-1.0WL	-0.101	-0.015	0.010	0.103	0.001	0.000	0.003
76	21:1.0D+1.0WI	-0.004	-0.178	-0.090	0.200	-0.002	-0.000	0.000
	22:1.0D+1.0WI	0.094	-0.083	0.007	0.126	0.000	0.000	-0.002
	23:1.0D-1.0WL	-0.001	-0.006	0.085	0.085	0.002	-0.000	-0.000
	24:1.0D-1.0WL	-0.099	-0.101	-0.012	0.142	-0.001	-0.001	0.002
77	21:1.0D+1.0WI	-0.016	-0.061	-0.089	0.109	-0.002	0.001	0.001
	22:1.0D+1.0WI	0.089	-0.017	0.004	0.091	0.000	-0.000	-0.002
	23:1.0D-1.0WL	0.006	-0.131	0.091	0.160	0.002	-0.000	-0.000
	24:1.0D-1.0WL	-0.099	-0.175	-0.002	0.201	0.000	0.001	0.003
78	21:1.0D+1.0WI	-0.041	-0.038	-0.108	0.121	-0.002	-0.000	0.001
	22:1.0D+1.0WI	0.102	-0.016	0.011	0.103	0.001	-0.000	-0.003
	23:1.0D-1.0WL	-0.004	-0.022	0.085	0.088	0.002	0.000	-0.001
	24:1.0D-1.0WL	-0.147	-0.044	-0.034	0.157	-0.001	0.000	0.004



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
5

Rev
1

Job Title **Rocky Hill CT**

Part

Ref

By **DAP**

Date **5/13/19**

Chd **BK**

Client **VZW**

File **Rocky Hill CT.std**

Date/Time **13-May-2019 16:22**

Node Displacements Cont...

Node	L/C	X (in)	Y (in)	Z (in)	Resultant (in)	rX (rad)	rY (rad)	rZ (rad)
79	21:1.0D+1.0WI	-0.001	-0.044	-0.098	0.107	-0.002	0.000	-0.000
	22:1.0D+1.0WI	0.079	-0.026	0.007	0.083	0.000	-0.000	-0.001
	23:1.0D-1.0WL	-0.005	-0.148	0.105	0.182	0.003	-0.001	0.001
	24:1.0D-1.0WL	-0.085	-0.165	-0.000	0.186	0.000	-0.000	0.002
80	21:1.0D+1.0WI	-0.002	-0.041	-0.096	0.104	-0.002	-0.000	0.000
	22:1.0D+1.0WI	0.083	-0.161	0.001	0.181	0.000	0.000	-0.002
	23:1.0D-1.0WL	0.004	-0.143	0.103	0.177	0.002	0.001	-0.001
	24:1.0D-1.0WL	-0.081	-0.023	0.006	0.084	0.000	0.000	0.001
81	21:1.0D+1.0WI	-0.002	-0.013	-0.114	0.114	-0.004	0.000	0.000
	22:1.0D+1.0WI	0.081	-0.030	0.026	0.090	0.000	0.000	-0.002
	23:1.0D-1.0WL	-0.001	-0.046	0.164	0.171	0.004	-0.000	0.000
	24:1.0D-1.0WL	-0.083	-0.030	0.025	0.092	0.000	-0.000	0.002
82	21:1.0D+1.0WI	-0.004	-0.037	0.005	0.037	-0.001	0.000	-0.001
	22:1.0D+1.0WI	-0.006	-0.043	0.003	0.044	-0.001	-0.000	-0.002
	23:1.0D-1.0WL	-0.004	-0.021	-0.000	0.022	0.000	-0.000	-0.001
	24:1.0D-1.0WL	-0.001	-0.015	0.002	0.015	-0.001	0.000	-0.000
83	21:1.0D+1.0WI	0.004	-0.038	0.004	0.038	-0.001	-0.000	0.001
	22:1.0D+1.0WI	0.001	-0.015	0.002	0.016	-0.001	-0.000	0.000
	23:1.0D-1.0WL	0.004	-0.022	0.000	0.022	0.000	0.000	0.001
	24:1.0D-1.0WL	0.007	-0.044	0.003	0.044	-0.001	0.000	0.002
84	21:1.0D+1.0WI	-0.000	-0.013	-0.002	0.013	0.000	-0.000	0.000
	22:1.0D+1.0WI	-0.002	-0.030	-0.005	0.030	0.001	0.000	-0.001
	23:1.0D-1.0WL	0.000	-0.046	-0.007	0.047	0.002	0.000	0.000
	24:1.0D-1.0WL	0.002	-0.030	-0.005	0.030	0.001	-0.000	0.001
85	21:1.0D+1.0WI	-0.003	-0.056	0.003	0.056	-0.001	-0.000	-0.001
	22:1.0D+1.0WI	-0.009	-0.170	-0.003	0.170	0.001	-0.000	-0.002
	23:1.0D-1.0WL	0.000	-0.127	-0.008	0.127	0.002	-0.000	0.000
	24:1.0D-1.0WL	0.006	-0.013	-0.002	0.015	0.001	-0.000	0.002
86	21:1.0D+1.0WI	0.001	-0.178	0.009	0.178	-0.002	0.000	0.000
	22:1.0D+1.0WI	-0.005	-0.101	0.005	0.101	-0.001	0.000	-0.002
	23:1.0D-1.0WL	0.001	-0.005	-0.004	0.007	0.001	0.000	0.000
	24:1.0D-1.0WL	0.008	-0.082	0.001	0.082	-0.000	0.000	0.002
87	21:1.0D+1.0WI	-0.001	-0.178	0.009	0.179	-0.002	-0.000	-0.000
	22:1.0D+1.0WI	-0.008	-0.083	0.001	0.083	-0.000	-0.000	-0.002
	23:1.0D-1.0WL	-0.002	-0.006	-0.004	0.007	0.001	-0.000	-0.000
	24:1.0D-1.0WL	0.005	-0.101	0.005	0.101	-0.001	-0.000	0.002
88	21:1.0D+1.0WI	0.003	-0.061	0.003	0.061	-0.001	0.000	0.001
	22:1.0D+1.0WI	-0.005	-0.017	-0.003	0.018	0.001	0.000	-0.002
	23:1.0D-1.0WL	0.000	-0.131	-0.008	0.131	0.002	0.000	0.000
	24:1.0D-1.0WL	0.009	-0.174	-0.003	0.175	0.001	0.000	0.002
89	21:1.0D+1.0WI	0.002	-0.044	0.007	0.045	-0.002	-0.000	0.001
	22:1.0D+1.0WI	-0.002	-0.026	-0.001	0.027	0.000	-0.000	-0.001
	23:1.0D-1.0WL	0.005	-0.148	-0.008	0.148	0.002	-0.000	0.001
	24:1.0D-1.0WL	0.009	-0.165	0.000	0.165	-0.000	-0.000	0.002
90	21:1.0D+1.0WI	-0.002	-0.041	0.007	0.041	-0.002	0.000	-0.000



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
6

Rev
1

Part

Job Title Rocky Hill CT

Ref

By DAP

Date 5/13/19

Chd BK

Client VZW

File Rocky Hill CT.std

Date/Time 13-May-2019 16:22

Node Displacements Cont...

Node	L/C	X (in)	Y (in)	Z (in)	Resultant (in)	rX (rad)	rY (rad)	rZ (rad)
	22:1.0D+1.0WI	-0.008	-0.161	0.000	0.161	-0.000	0.000	-0.002
	23:1.0D-1.0WL	-0.004	-0.143	-0.008	0.144	0.002	0.000	-0.001
	24:1.0D-1.0WL	0.002	-0.023	-0.001	0.023	0.000	0.000	0.001
91	21:1.0D+1.0WI	0.014	-0.037	-0.039	0.056	-0.003	0.000	-0.001
	22:1.0D+1.0WI	0.048	-0.043	-0.010	0.066	-0.001	-0.000	-0.003
	23:1.0D-1.0WL	0.011	-0.021	0.024	0.034	0.002	-0.000	-0.000
	24:1.0D-1.0WL	-0.023	-0.015	-0.004	0.028	0.000	0.000	0.002
92	21:1.0D+1.0WI	-0.015	-0.038	-0.040	0.057	-0.003	-0.000	0.001
	22:1.0D+1.0WI	0.024	-0.016	-0.004	0.029	0.000	-0.000	-0.002
	23:1.0D-1.0WL	-0.011	-0.022	0.026	0.036	0.002	0.000	0.000
	24:1.0D-1.0WL	-0.050	-0.044	-0.010	0.067	-0.001	0.000	0.003
93	21:1.0D+1.0WI	-0.001	-0.013	-0.024	0.027	-0.003	0.000	0.000
	22:1.0D+1.0WI	0.030	-0.030	0.015	0.045	0.001	0.000	-0.002
	23:1.0D-1.0WL	-0.000	-0.046	0.053	0.071	0.004	-0.000	0.000
	24:1.0D-1.0WL	-0.031	-0.030	0.015	0.045	0.001	-0.000	0.002
94	21:1.0D+1.0WI	0.000	-0.002	-0.000	0.002	-0.000	-0.000	0.000
	22:1.0D+1.0WI	0.000	-0.001	-0.000	0.001	-0.000	-0.000	0.000
	23:1.0D-1.0WL	-0.000	-0.001	0.000	0.001	-0.000	0.000	0.000
	24:1.0D-1.0WL	-0.000	-0.002	0.000	0.002	-0.000	0.000	0.001
95	21:1.0D+1.0WI	-0.000	-0.015	-0.001	0.015	0.000	-0.000	0.001
	22:1.0D+1.0WI	0.001	-0.009	-0.000	0.009	0.000	-0.000	0.000
	23:1.0D-1.0WL	0.000	-0.034	0.000	0.034	0.001	-0.000	0.002
	24:1.0D-1.0WL	-0.001	-0.041	0.000	0.041	0.001	-0.000	0.002
96	21:1.0D+1.0WI	-0.000	-0.007	-0.000	0.007	0.000	-0.000	0.000
	22:1.0D+1.0WI	0.001	-0.005	-0.000	0.005	0.001	-0.000	0.000
	23:1.0D-1.0WL	0.000	-0.015	0.000	0.015	0.001	-0.000	0.001
	24:1.0D-1.0WL	-0.001	-0.017	-0.000	0.017	0.001	-0.000	0.001
97	21:1.0D+1.0WI	-0.000	-0.032	-0.001	0.032	-0.001	-0.000	0.001
	22:1.0D+1.0WI	0.001	-0.032	0.000	0.032	0.001	0.000	0.000
	23:1.0D-1.0WL	0.000	-0.112	0.001	0.112	0.002	0.000	0.002
	24:1.0D-1.0WL	-0.001	-0.111	0.000	0.111	0.000	0.000	0.002
98	21:1.0D+1.0WI	-0.000	-0.020	-0.000	0.020	-0.000	-0.000	0.000
	22:1.0D+1.0WI	0.001	-0.027	-0.000	0.027	0.001	-0.000	0.000
	23:1.0D-1.0WL	0.000	-0.069	0.000	0.069	0.002	-0.000	0.002
	24:1.0D-1.0WL	-0.001	-0.062	0.000	0.062	0.001	-0.000	0.002
99	21:1.0D+1.0WI	-0.000	-0.019	-0.000	0.019	-0.000	0.000	-0.000
	22:1.0D+1.0WI	0.001	-0.061	-0.000	0.061	0.001	0.000	-0.002
	23:1.0D-1.0WL	0.000	-0.067	0.000	0.067	0.002	0.000	-0.002
	24:1.0D-1.0WL	-0.001	-0.026	-0.000	0.026	0.001	0.000	-0.000
100	21:1.0D+1.0WI	-0.000	-0.030	-0.001	0.030	-0.001	0.000	-0.000
	22:1.0D+1.0WI	0.001	-0.109	0.000	0.109	0.000	-0.000	-0.002
	23:1.0D-1.0WL	0.000	-0.109	0.001	0.109	0.002	-0.000	-0.002
	24:1.0D-1.0WL	-0.001	-0.030	0.000	0.030	0.001	-0.000	-0.000
101	21:1.0D+1.0WI	-0.000	-0.006	-0.000	0.006	0.000	0.000	-0.000
	22:1.0D+1.0WI	0.001	-0.017	-0.000	0.017	0.001	0.000	-0.001



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No 50103542	Sheet No 7	Rev 1
Part		
Ref		
By DAP	Date 5/13/19	Chd BK
File Rocky Hill CT.std	Date/Time 13-May-2019 16:22	

Job Title Rocky Hill CT

Client VZW

Node Displacements Cont...

Node	L/C	X (in)	Y (in)	Z (in)	Resultant (in)	rX (rad)	rY (rad)	rZ (rad)
	23:1.0D-1.0WL	0.000	-0.015	0.000	0.015	0.001	0.000	-0.001
	24:1.0D-1.0WL	-0.001	-0.004	-0.000	0.004	0.001	0.000	-0.000
102	21:1.0D+1.0WI	-0.000	-0.014	-0.000	0.014	0.000	0.000	-0.001
	22:1.0D+1.0WI	0.001	-0.040	0.000	0.040	0.001	0.000	-0.002
	23:1.0D-1.0WL	0.000	-0.033	0.000	0.033	0.001	0.000	-0.002
	24:1.0D-1.0WL	-0.001	-0.008	-0.000	0.008	0.000	0.000	-0.000
103	21:1.0D+1.0WI	0.000	-0.041	-0.001	0.041	-0.000	0.000	0.002
	22:1.0D+1.0WI	0.000	-0.015	-0.000	0.015	0.000	0.000	-0.000
	23:1.0D-1.0WL	-0.000	-0.048	0.001	0.048	0.001	0.000	0.001
	24:1.0D-1.0WL	-0.000	-0.074	0.000	0.074	0.001	0.000	0.003
104	21:1.0D+1.0WI	-0.000	-0.057	-0.001	0.057	-0.000	-0.000	0.001
	22:1.0D+1.0WI	0.001	-0.018	-0.000	0.018	0.001	0.000	-0.001
	23:1.0D-1.0WL	-0.000	-0.087	0.001	0.087	0.002	0.000	0.001
	24:1.0D-1.0WL	-0.001	-0.125	-0.000	0.125	0.001	-0.000	0.003
105	21:1.0D+1.0WI	0.000	-0.008	-0.001	0.008	-0.000	0.000	0.001
	22:1.0D+1.0WI	0.000	-0.004	-0.000	0.004	0.000	0.000	0.000
	23:1.0D-1.0WL	-0.000	-0.015	0.001	0.015	0.001	0.000	0.001
	24:1.0D-1.0WL	-0.000	-0.018	0.000	0.018	0.000	0.000	0.002
106	21:1.0D+1.0WI	0.000	-0.015	-0.001	0.015	0.000	0.000	0.001
	22:1.0D+1.0WI	0.001	-0.009	-0.000	0.009	0.000	0.000	0.000
	23:1.0D-1.0WL	-0.000	-0.034	0.001	0.034	0.001	0.000	0.002
	24:1.0D-1.0WL	-0.000	-0.041	0.000	0.041	0.001	0.000	0.002
107	21:1.0D+1.0WI	0.000	-0.124	-0.001	0.124	-0.003	0.000	-0.000
	22:1.0D+1.0WI	0.001	-0.055	-0.000	0.055	-0.001	-0.000	-0.001
	23:1.0D-1.0WL	-0.000	-0.015	0.001	0.015	0.000	0.000	-0.000
	24:1.0D-1.0WL	-0.001	-0.084	0.000	0.084	-0.002	0.000	0.001
108	21:1.0D+1.0WI	0.000	-0.070	-0.001	0.070	-0.002	-0.000	0.000
	22:1.0D+1.0WI	0.001	-0.031	-0.000	0.031	-0.001	-0.000	-0.001
	23:1.0D-1.0WL	-0.000	-0.016	0.001	0.016	-0.000	-0.000	0.000
	24:1.0D-1.0WL	-0.000	-0.055	0.000	0.055	-0.002	-0.000	0.001
109	21:1.0D+1.0WI	0.000	-0.042	-0.001	0.042	-0.002	-0.000	0.000
	22:1.0D+1.0WI	0.001	-0.024	-0.000	0.024	-0.001	-0.000	0.000
	23:1.0D-1.0WL	-0.000	-0.005	0.001	0.005	-0.000	-0.000	0.000
	24:1.0D-1.0WL	-0.000	-0.024	0.000	0.024	-0.001	-0.000	0.000
110	21:1.0D+1.0WI	0.000	-0.018	-0.001	0.018	-0.002	-0.000	0.000
	22:1.0D+1.0WI	0.000	-0.010	-0.000	0.010	-0.001	-0.000	0.000
	23:1.0D-1.0WL	-0.000	-0.003	0.001	0.003	-0.000	-0.000	0.000
	24:1.0D-1.0WL	-0.000	-0.011	0.000	0.011	-0.001	-0.000	0.000
111	21:1.0D+1.0WI	-0.000	-0.018	-0.001	0.018	-0.002	0.000	-0.000
	22:1.0D+1.0WI	0.000	-0.011	0.000	0.011	-0.001	0.000	-0.000
	23:1.0D-1.0WL	0.000	-0.003	0.001	0.003	-0.000	0.000	-0.000
	24:1.0D-1.0WL	-0.000	-0.010	-0.000	0.010	-0.001	0.000	-0.000
112	21:1.0D+1.0WI	-0.000	-0.042	-0.001	0.042	-0.002	0.000	-0.000
	22:1.0D+1.0WI	0.000	-0.024	0.000	0.024	-0.001	0.000	-0.000
	23:1.0D-1.0WL	-0.000	-0.005	0.001	0.005	-0.000	0.000	-0.000



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
8

Rev
1

Job Title Rocky Hill CT

Part

Ref

By DAP

Date 5/13/19

Chd BK

Client VZW

File Rocky Hill CT.std

Date/Time 13-May-2019 16:22

Node Displacements Cont...

Node	L/C	X (in)	Y (in)	Z (in)	Resultant (in)	rX (rad)	rY (rad)	rZ (rad)
	24:1.0D-1.0WL	-0.001	-0.024	-0.000	0.024	-0.001	0.000	-0.000
113	21:1.0D+1.0WI	-0.000	-0.070	-0.000	0.070	-0.002	0.000	-0.000
	22:1.0D+1.0WI	0.000	-0.055	0.000	0.055	-0.002	0.000	-0.001
	23:1.0D-1.0WL	-0.000	-0.016	0.001	0.016	-0.000	0.000	-0.000
	24:1.0D-1.0WL	-0.001	-0.031	-0.000	0.031	-0.001	0.000	0.001
114	21:1.0D+1.0WI	0.000	-0.123	-0.001	0.123	-0.003	-0.000	0.000
	22:1.0D+1.0WI	0.001	-0.083	0.000	0.083	-0.002	-0.000	-0.001
	23:1.0D-1.0WL	-0.000	-0.015	0.001	0.015	0.000	-0.000	0.000
	24:1.0D-1.0WL	-0.001	-0.054	-0.000	0.054	-0.000	0.000	0.001
115	21:1.0D+1.0WI	-0.000	-0.014	-0.000	0.014	0.000	-0.000	-0.001
	22:1.0D+1.0WI	0.000	-0.040	0.000	0.040	0.001	-0.000	-0.002
	23:1.0D-1.0WL	0.000	-0.033	0.000	0.033	0.001	-0.000	-0.002
	24:1.0D-1.0WL	-0.001	-0.008	-0.000	0.008	0.000	-0.000	-0.000
116	21:1.0D+1.0WI	-0.000	-0.007	-0.000	0.007	-0.000	-0.000	-0.001
	22:1.0D+1.0WI	0.000	-0.017	0.000	0.017	0.000	-0.000	-0.002
	23:1.0D-1.0WL	0.000	-0.014	0.000	0.014	0.001	-0.000	-0.001
	24:1.0D-1.0WL	-0.000	-0.004	-0.000	0.004	0.000	-0.000	-0.000
117	21:1.0D+1.0WI	-0.000	-0.054	-0.001	0.054	-0.000	0.000	-0.001
	22:1.0D+1.0WI	0.001	-0.122	-0.000	0.122	0.001	0.000	-0.003
	23:1.0D-1.0WL	0.000	-0.084	0.001	0.084	0.002	0.000	-0.001
	24:1.0D-1.0WL	-0.001	-0.016	-0.000	0.016	0.000	-0.000	0.001
118	21:1.0D+1.0WI	-0.000	-0.039	-0.000	0.039	-0.000	-0.000	-0.001
	22:1.0D+1.0WI	0.000	-0.072	0.000	0.072	0.001	-0.000	-0.003
	23:1.0D-1.0WL	0.000	-0.046	0.001	0.046	0.001	-0.000	-0.001
	24:1.0D-1.0WL	-0.000	-0.014	-0.000	0.014	0.000	-0.000	0.000
119	21:1.0D+1.0WI	-0.001	-0.039	-0.068	0.079	-0.002	-0.001	-0.000
	22:1.0D+1.0WI	0.068	-0.191	0.001	0.202	0.000	-0.000	-0.002
	23:1.0D-1.0WL	-0.000	-0.152	0.069	0.167	0.002	0.001	-0.000
	24:1.0D-1.0WL	-0.069	0.000	-0.000	0.069	0.000	0.000	0.002
120	21:1.0D+1.0WI	0.008	-0.056	-0.074	0.093	-0.001	-0.001	-0.001
	22:1.0D+1.0WI	0.075	-0.170	-0.003	0.186	0.000	-0.001	-0.002
	23:1.0D-1.0WL	-0.006	-0.127	0.073	0.146	0.002	0.000	0.000
	24:1.0D-1.0WL	-0.073	-0.013	0.002	0.074	0.000	0.000	0.002
121	21:1.0D+1.0WI	0.030	-0.037	-0.086	0.099	-0.002	0.000	-0.001
	22:1.0D+1.0WI	0.113	-0.043	-0.025	0.124	-0.001	-0.000	-0.004
	23:1.0D-1.0WL	0.007	-0.021	0.065	0.069	0.002	-0.000	0.001
	24:1.0D-1.0WL	-0.076	-0.015	0.004	0.077	0.001	0.000	0.003
123	21:1.0D+1.0WI	0.001	-0.207	-0.070	0.219	-0.002	-0.000	0.000
	22:1.0D+1.0WI	0.069	-0.096	0.000	0.118	-0.000	0.001	-0.002
	23:1.0D-1.0WL	-0.003	0.017	0.071	0.073	0.002	0.000	0.000
	24:1.0D-1.0WL	-0.071	-0.095	0.001	0.119	-0.000	-0.001	0.002
124	21:1.0D+1.0WI	-0.003	-0.178	-0.072	0.192	-0.002	-0.000	0.000
	22:1.0D+1.0WI	0.077	-0.083	0.005	0.114	0.000	0.000	-0.002
	23:1.0D-1.0WL	-0.002	-0.006	0.071	0.071	0.002	-0.000	-0.000
	24:1.0D-1.0WL	-0.083	-0.101	-0.006	0.131	-0.001	-0.001	0.002



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
9

Rev
1

Part

Job Title Rocky Hill CT

Ref

By DAP

Date 5/13/19

Chd BK

Client VZW

File Rocky Hill CT.std

Date/Time 13-May-2019 16:22

Node Displacements Cont...

Node	L/C	X (in)	Y (in)	Z (in)	Resultant (in)	rX (rad)	rY (rad)	rZ (rad)
125	21:1.0D+1.0WI	-0.032	-0.038	-0.088	0.101	-0.002	-0.000	0.001
	22:1.0D+1.0WI	0.076	-0.016	0.004	0.078	0.001	-0.000	-0.003
	23:1.0D-1.0WL	-0.009	-0.022	0.067	0.071	0.002	0.000	-0.001
	24:1.0D-1.0WL	-0.116	-0.044	-0.025	0.127	-0.001	0.000	0.004
127	21:1.0D+1.0WI	-0.002	-0.043	-0.071	0.083	-0.002	0.001	0.000
	22:1.0D+1.0WI	0.067	-0.004	-0.001	0.067	0.000	-0.000	-0.002
	23:1.0D-1.0WL	-0.001	-0.157	0.072	0.173	0.002	-0.001	0.000
	24:1.0D-1.0WL	-0.070	-0.196	0.002	0.208	0.000	0.000	0.002
128	21:1.0D+1.0WI	-0.002	-0.044	-0.080	0.091	-0.002	0.000	-0.000
	22:1.0D+1.0WI	0.067	-0.026	0.006	0.073	0.000	-0.000	-0.001
	23:1.0D-1.0WL	-0.001	-0.148	0.085	0.171	0.002	-0.001	0.001
	24:1.0D-1.0WL	-0.070	-0.165	-0.001	0.179	0.000	-0.000	0.002
129	21:1.0D+1.0WI	-0.002	-0.013	-0.083	0.084	-0.004	0.000	0.000
	22:1.0D+1.0WI	0.067	-0.030	0.023	0.077	0.000	0.000	-0.002
	23:1.0D-1.0WL	-0.000	-0.046	0.129	0.137	0.004	-0.000	0.000
	24:1.0D-1.0WL	-0.069	-0.030	0.022	0.079	0.000	-0.000	0.002
132	21:1.0D+1.0WI	0.003	-0.178	-0.071	0.192	-0.002	0.000	-0.000
	22:1.0D+1.0WI	0.080	-0.101	-0.007	0.129	-0.001	0.001	-0.002
	23:1.0D-1.0WL	-0.001	-0.005	0.070	0.070	0.002	0.000	0.000
	24:1.0D-1.0WL	-0.079	-0.082	0.005	0.114	0.000	-0.000	0.002
134	21:1.0D+1.0WI	-0.011	-0.061	-0.076	0.098	-0.002	0.001	0.001
	22:1.0D+1.0WI	0.073	-0.017	0.003	0.075	0.000	-0.000	-0.002
	23:1.0D-1.0WL	0.005	-0.131	0.076	0.151	0.002	-0.000	-0.000
	24:1.0D-1.0WL	-0.079	-0.175	-0.003	0.192	0.000	0.001	0.002
136	21:1.0D+1.0WI	-0.001	-0.041	-0.078	0.088	-0.002	-0.000	0.000
	22:1.0D+1.0WI	0.068	-0.161	-0.000	0.175	0.000	0.000	-0.002
	23:1.0D-1.0WL	-0.000	-0.143	0.083	0.166	0.002	0.001	-0.001
	24:1.0D-1.0WL	-0.069	-0.023	0.006	0.073	0.000	0.000	0.001



Software licensed to DEWBERRY
CONNECTED User: Deep Patel

Job No
50103542

Sheet No
10

Rev
1

Part

Job Title Rocky Hill CT

Ref

By DAP


Date 5/13/19

Chd BK

Client VZW

File Rocky Hill CT.std

Date/Time 13-May-2019 16:22



Displacement

Displacement Check:

Antenna Pipe Mast (2 3/8" O.D. Pipe):

Max Displacement = 0.197 - 0.137 = 0.06"

(Node 48 with respect to Node 129)

Allowable Displacement = 1.5% cantilever = 0.21"

0.06" < 0.21" -- PASS

APPENDIX B

ASCE 7 Hazards Report

Address:

1 France St
Rocky Hill, Connecticut
06067

Standard:



ASCE/SEI 7-10

Risk Category: II**Soil Class:**

Elevation: 171.05 ft (NAVD 88)

Latitude: 41.650734

Longitude: -72.67939



Wind

Results:

Wind Speed:	124 Vmph
10-year MRI	77 Vmph
25-year MRI	87 Vmph
50-year MRI	93 Vmph
100-year MRI	101 Vmph

Data Source:

ASCE/SEI 7-10, Fig. 26.5-1A and Figs. CC-1–CC-4, incorporating errata of March 12, 2014

Date Accessed:

Mon May 13 2019

Value provided is 3-second gust wind speeds at 33 ft above ground for Exposure C Category, based on linear interpolation between contours. Wind speeds are interpolated in accordance with the 7-10 Standard. Wind speeds correspond to approximately a 7% probability of exceedance in 50 years (annual exceedance probability = 0.00143, MRI = 700 years).

Site is in a hurricane-prone region as defined in ASCE/SEI 7-10 Section 26.2. Glazed openings need not be protected against wind-borne debris.

Mountainous terrain, gorges, ocean promontories, and special wind regions should be examined for unusual wind conditions.

The ASCE 7 Hazard Tool is provided for your convenience, for informational purposes only, and is provided "as is" and without warranties of any kind. The location data included herein has been obtained from information developed, produced, and maintained by third party providers; or has been extrapolated from maps incorporated in the ASCE 7 standard. While ASCE has made every effort to use data obtained from reliable sources or methodologies, ASCE does not make any representations or warranties as to the accuracy, completeness, reliability, currency, or quality of any data provided herein. Any third-party links provided by this Tool should not be construed as an endorsement, affiliation, relationship, or sponsorship of such third-party content by or from ASCE.

ASCE does not intend, nor should anyone interpret, the results provided by this Tool to replace the sound judgment of a competent professional, having knowledge and experience in the appropriate field(s) of practice, nor to substitute for the standard of care required of such professionals in interpreting and applying the contents of this Tool or the ASCE 7 standard.


In using this Tool, you expressly assume all risks associated with your use. Under no circumstances shall ASCE or its officers, directors, employees, members, affiliates, or agents be liable to you or any other person for any direct, indirect, special, incidental, or consequential damages arising from or related to your use of, or reliance on, the Tool or any information obtained therein. To the fullest extent permitted by law, you agree to release and hold harmless ASCE from any and all liability of any nature arising out of or resulting from any use of data provided by the ASCE 7 Hazard Tool.

APPENDIX C

Site Name: Rocky Hill CT

Site Address: France Street, Lot 1
Rocky Hill, CT 06067

Rocky Hill CT –Site Photos



August 21, 2017

Mr. Dan Vadney
Crown Castle USA, Inc.
3 Corporate Park Drive, Suite 101
Clifton Park, NY 12065
(518) 373-3510
Dan.Vadney@crowncastle.com



Tower Engineering Professionals
326 Tryon Road
Raleigh, NC 27603
(919) 661-6351 (office)
(919) 661-6350 (fax)
PMI@tepgroup.net

Subject: Modification Inspection Report

<i>Crown Castle Designation:</i>	Crown Castle BU Number:	806374
	Crown Castle Site Name:	HRT 081
	Crown Castle JDE Job Number:	400014
<i>Engineering Firm Designation:</i>	TEP Project Number:	25657.69403
<i>Site Data:</i>	North Street	
	Rocky Hill, Hartford County, CT 06067	
	Latitude N 41° 38' 23.2", Longitude W 72° 42' 6.83"	
	140 Foot – Monopole Tower	

Dear Mr. Vadney,

Tower Engineering Professionals is pleased to submit this **"Modification Inspection Report"** (MI Report) to Crown Castle for the modification/reinforcement to the subject structure. This Modification Inspection (MI) was performed in accordance with Crown Castle ENG-SOW-10007 Modification Inspection SOW, Contract Documents, and Crown Castle Purchase Order number 1025233. The purpose of this MI is to confirm that the modification installation configuration and workmanship are in accordance with the contract document(s) listed in Table 2. The MI is not a review of the adequacy or effectiveness of the modification/reinforcement solution.

Table 1 – General Information

	Company	Contact	Dates on Site
MI Inspector	Tower Engineering Professionals	Kevin R. Arnett, P.E., C.W.I.	N/A
MI Inspector Field Representative (if applicable)	Tower Engineering Professionals	Scott Coburn & James Harms	8/17/17
☒ Independent ☐ EOR ☐ Turnkey			
Modification Design EOR	Paul J. Ford and Company	Justin T. Kline, P.E.	N/A
General Contractor	Advanced Network Services	Ron Brandon	Unknown
Sub to the General Contractor	N/A	N/A	N/A
Field CWI for the General Contractor	N/A	N/A	N/A
Field NDE for the General Contractor	N/A	N/A	N/A

Table 2 – Documents

Document(s)	Remarks	Source
Modification Drawings Date: March 1, 2017 EOR: Justin T. Kline, P.E. Job#: 37517-0519.002.7700	Creator of Drawings: Paul J. Ford and Company Job #: 37517-0519.002.7700 Date of Drawings: 3/1/17	CCLsites Drawing File: 6720736

Based on our inspection, Tower Engineering Professionals, Inc. determines this project:

☒ **PASSING MI**

The configuration, materials and/or workmanship of the modifications are installed in accordance with the Contract Documents and no deficiencies were found.

☐ **PASS AS NOTED MI**

The configuration, materials and/or workmanship of the modifications are accepted as noted (see detail below).

☐ **FAILED MI**

The configuration, materials and/or workmanship of the modifications are NOT installed in accordance with the Contract Documents. The rejection is based on non-conformance in the following area(s):


- ☐ Materials (see detail below)
- ☐ Workmanship (see detail below)
- ☐ Configuration (see detail below)

Discrepancies were noted between the As-Built field conditions and the structural modification drawings. The As-Built field conditions were approved by the Engineer of Record. All discrepancies are noted in the executive summary.

All observations were performed after the construction was complete. Tower Engineering Professionals, Inc. was not present during the construction phase. The onsite PMI was performed by Scott Coburn and James Harms of Tower Engineering Professionals, Inc., (919) 661-6351.

We at Tower Engineering Professionals, Inc. appreciate the opportunity of providing our continuing professional services to you and Crown Castle. If you have any questions or need further assistance on this or any other projects please give us a call.

Respectfully submitted,



Kevin R. Arnett, P.E., C.W.I.

Table of Contents

PAGE NO.


PRE-CONSTRUCTION.....	5
6.1.1 MI CHECKLIST DRAWING.....	6
6.1.2 EOR REVIEW.....	8
6.1.3 FABRICATION INSPECTION	10
6.1.4 MATERIAL TEST REPORT (MTR)	12
6.1.5 PACKING SLIPS	15
CONSTRUCTION	17
6.2.1 CONSTRUCTION INSPECTIONS	18
6.2.2 ON SITE COLD GALVANIZING VERIFICATION	20
6.2.3 GC AND TEP REDLINE DRAWINGS.....	23
POST-CONSTRUCTION	31
6.3.1 EXECUTIVE SUMMARY.....	32
6.3.2 PHOTOGRAPHS.....	33
6.3.3 CONTRACTOR PHOTOGRAPHS	35
6.3.4 ENGINEER OF RECORD EMAIL	37

PRE-CONSTRUCTION

6.1.1 MI CHECKLIST DRAWING


6.1.2 EOR REVIEW

4 SPACES @ 1'-4" = 5'-4"




5 SPA @ 3" = 1'-3"

5 SPA @ 3" = 1'-3"



DETAIL A
(BOTTOM)



DETAIL B
(TOP)

PAUL J. FORD AND COMPANY
STRUCTURAL ENGINEERS
Columbus, Ohio · Orlando, Florida · Atlanta, Georgia

By:	JWM	Date:	04/14/2017
☒ Reviewed, No exceptions taken			
☐ Reviewed, Make Noted Corrections			
☐ Revise and Resubmit			
☐ Rejected, See Remarks			
☐ Reviewed Only For Loads Imposed on the Structure			

Corrections or comments made on this document do not relieve the contractor from compliance with the requirements of the drawings and specifications. This document was reviewed for general conformance to the design requirements in the contract documents. The contractor is responsible for confirming and correlating all quantities and dimensions, fabrication processes and techniques of construction, coordination of the work with other trades and the satisfactory performance of his work.

- NOTES:
- ALL HOLES ARE TO BE DRILLED. DO NOT BURN OR PUNCH.
 - TOLERANCES: FRACTIONS $\pm 1/16"$
ANGLES $\pm 1/2$ DEGREE
DECIMALS $\pm .010"$
 - THE 65 KSI MATERIAL SHALL CONFORM TO THE FOLLOWING:
 - MATERIAL SHALL BE ASTM A572 HAVING A MINIMUM TENSILE STRENGTH (F_U) OF 80 KSI AND A MINIMUM YIELD STRENGTH (F_y) OF 65 KSI.
 - THE FINISH SHALL BE HOT-DIP GALVANIZED PER ASTM A123



15401 COMMERCE PARK DRIVE - BROOKPARK, OHIO 44142
PH: (440) 232-6060 FX: (440) 232-6062
www.allfasteners.com

CUSTOMER:	HOLE QTY:	17
PROJECT: HRT 081 943236	BLACK WT (LBS):	102.0
LOCATION:	PART QTY:	3
DATE: 4/12/2017	PART #CCI-AFP-04007510	

6.1.3 FABRICATION INSPECTION

To: ANS Advanced Network Services
 12 Elwood Road
 Albany, NY 12204

Subject: PO: 1728251-01

April 18, 2017

Please accept this letter as certification that our work on the Steel Package for HRT 081 was performed in accordance with industry standards and the contractor documents.

Please contact me if you have any questions.

Thank you,

Mark Wootten

Fabrication Manager

Allfasteners USA LLC

New York

69 Orchard Street,
Ramsey, New Jersey 07446

Tel 1-800-577-3171
Fax +1 (201) 783-8840

Cleveland

15401 Commerce Park Drive,
Cleveland, Ohio 44142

Tel 1-888-858-6060
Fax +1 (440) 232-6062

Los Angeles

5450 W. 83rd Street,
Los Angeles, California 90045

Tel +1 (310) 410-5007
Fax +1 (310) 410-5004

Nebraska

102 8th Street,
Gothenburg, Nebraska 69138

Tel 1-855-330-2210
Fax +1 (308) 537-3500

6.1.4 MATERIAL TEST REPORT (MTR)

Certification Report

April 2017

ANS Advanced Network Services

HRT 081

PO: 1728251-01

SO: 121600



Product Certificate of Conformance

AF Lot #: 7941		Customer PO #:		1728251-01				Part #:		2NG2036		
			Test Results									
			Proof Load (Mpa)		Hardness (HRC)				Wedge Tensile Test (psi)			
			Spec		Spec		Sample		Spec	Sample		
			Min	Sample	Min	Max	A	B	Min	A	B	
Lot Number	Component Part Number	Description										
25202	2NG20095A490M	M20 x 95 NexGen2™ Structural Bolt			33	38	Pass	Pass	150000	Pass	Pass	
780167	2HHNM2025G2HM	M20-2.50 Heavy Hex Nut Grade 2H	1165	Pass	24	36	Pass	Pass				
771228	14GLS1116M	11/16" Shear Sleeve			24	33	Pass	Pass				
49075	2NG2SWH	M20 NexGen2™ Collapsible Split Washer			23	34	Pass	Pass				
778601	2NG2CWM	M20 Solid Collar Washer			23	34	Pass	Pass				

New York

69 Orchard Street
 Ramsey, New Jersey 07446
 Tel 800 577 3171
 Fax 201 783 8840

Cleveland

959 Lake Road
 Medina, Ohio 44256
 Tel 888 859 6060
 Fax 440 232 6062

Los Angeles

5450 W 83rd Street
 Los Angeles, California 90045
 Tel 310 410 5007
 Fax 866 553 7702

Nebraska

806 8th Street
 Gothenburg, Nebraska 69138
 Tel 855 330 2210
 Fax 308 537 3500



Ship To: ALL FASTENERS - MEDINA
1021 INDUSTRIAL PARKWAY
MEDINA OH 44256
USA

METALLURGICAL TEST REPORT

We hereby certify that these Chemical and/or Test results are correct as contained in the records

Sold To: ALLFASTENERS USA, LLC
959 LAKE ROAD
MEDINA OH 44256
USA

By: Dick Peoples - Customer Service Metallurgist

Mercury source materials have not been used in the production of this material. No weld repair performed.

Cert #: 22314

Grade: A572 GR 65

Size: 0.750 X 4.000 FL

Item: 113280

Cust Item:

Size(MM): 19.05 X 101.60

A572 GR 65 FL SE 0.75 X 4.35" L 15" L

Length: 421.0000

Length(MM): 10693.4

Heat	Furnace	Melted Source	Cast	CE	DI	Sum	Shpd. Qty
W19685	EAF	USA	Bil			0.0000	3,221

Ladle Chemistry Analysis

C	Mn	P	S	Si	Cu	Ni	Cr	Mo	Sn	Al	V	Nb	B	Ti
0.15	1.15	0.011	0.020	0.26	0.22	0.11	0.11	0.05	0.010	0.004	0.073	0.004	0.0003	0.0007
N	Pb	Q	Ca	Bi	Se	Te	As	Fe	Zn	Zr	Mg	Li	CO	QT
0.0166	0.00		0.000				0.006	0.003					0.0100	

Grains (ASTM A225)

J1	J2	J3	J4	J5	J6	J7	J8	J9	J10	J11	J12	J13	J14	J15	J16	J18	J20	J24	J28	J32	Grain Size
----	----	----	----	----	----	----	----	----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	------------

Notes

Non-Metallic Inclusions (ASTM E45)

Method A				Method C		Magnetic Particle Inspection		ASTM E381			Reduction Ratio 8.8 : 1
A	B	C	D	Q	S	Frequency	Severity	B	C	S	
				T							
				H							
				T							
				H							

Tensile Properties

							Hardness				
Tensile	Yield 0.2%	Yield 0.01%	Yield 0.02%	Elong % 2"	Elong % 8"	ROA %	Decarb	Type	RC	RB	RA
93700	77000			42.00				Surface			
								Mid			
								Core			
								Surface			
								Mid			
								Core			

Charpy

Temp	Size	Longitudinal	Transverse
------	------	--------------	------------

New York

69 Orchard Street
Ramsey, New Jersey 07446
Tel 800 577 3171
Fax 201 783 8840

Cleveland

959 Lake Road
Medina, Ohio 44256
Tel 888 859 6060
Fax 440 232 6062


Los Angeles

5450 W 83rd Street
Los Angeles, California 90045
Tel 310 410 5007
Fax 866 553 7702

Nebraska

806 8th Street
Gothenburg, Nebraska 69138
Tel 855 330 2210
Fax 308 537 3500

6.1.5 PACKING SLIPS



959 Lake Road
Medina, OH 442556
Ph: 888 859 6060
Fax: 440 232 6062
Email: sales@allfasteners.com

69 Orchard Street
Ramsey, NJ 07446
Ph: 800 577 3171
Fax: 201 783 8840
Email: sales@allfasteners.com

5450 W. 83rd Street
Los Angeles, CA 90045
Ph: 800 410 5511
Fax: 310 410 5004
Email: sales@allfasteners.com

ANS Advanced Network Services
12 Elmwood Road
Albany NY 12204-2410

DELIVER
12 Elmwood Road
Albany
NY 12204

Invoice
E 92420
Acc No: 7388

Invoice Date	Customer PO No.	Order	Reference	Ordered By	Contact No.	Shipping Method	Terms
04.19.2017	1728251-01	121600	HRT 081	Ron	800 268 0937	Unishippers	NET 30 Days

Order Code	Description	Qty Ord	Back Ord	Supplied	Unit Price	UOM	Ext. Amount
14CCI-AFP-04007510	3/4 x 4 x 10ft Auxiliary Flat Plate Grade 65 Galvanized with 17 Holes	3		3		1	
2NG2036	M20 x 36 Grip Length NexGen2™ Structural Bolt Assembly Magni 24/Box	72		72		1	
12AF1000-1G	AF1000 Cold Galvanizing Coating 1 Gallon 2/Ctn	1		1		1	
13NG2IT	NexGen2 Bolt Installation Tool	1		1		1	
FREIGHTOUT	Shipping & Handling Charge	1		1		1	

Mail checks to: Allfasteners USA 69 Orchard Street Ramsey, NJ 07446	Freight	
	Subtotal	
	Sales Tax	
	TOTAL	

Allfasteners USA LLC retains title of goods sold until the goods have been paid for in full. Discrepancies must be reported within 7 days.
This invoice is subject to terms and conditions posted on <http://www.allfasteners.com/terms.php>.

CONSTRUCTION

6.2.1 CONSTRUCTION INSPECTIONS

8/11/17

Dan Vadney
Project Manager Structural Upgrades
Crown Castle
3 Corporate Park Drive
Suite 101
Clifton Park, NY 12065

Dan,

This letter is to inform you and CCI that all construction/structural modifications on the Crown Castle BU# 806374 HRT 081 site are complete.
ANS would also like to inform you that all work was performed in accordance with industry standards and contract documents including modification drawings and specifications, state and local regulations, OSHA, and Engineering Standards.

If you have any questions or concerns please contact me.

Sincerely,

Ron Brandon
Advanced Network Services
[P] 607-220-4007
[F] 518-292-6511
[E] Rbrandon@anscorporate.com

6.2.2 ON SITE COLD GALVANIZING VERIFICATION

8/11/17

Dan Vadney
Project Manager Structural Upgrades
Crown Castle
3 Corporate Park Drive
Suite 101
Clifton Park, NY 12065

Dan,

This letter is to inform you and CCI that all construction/structural modifications on the Crown Castle BU# 806374 HRT081 site are complete.

ANS would like to inform you that the cold galvanizing product ZRC Galvilite or AF1000 was used and applied as necessary. This product contains 95% Zinc by DFT and is approved in the Crown Castle Tower Protective Coating Guidelines ENG-STD-10149.

If you have any questions or concerns please contact me.

Sincerely,

Ron Brandon
Advanced Network Services
[P] 607-220-4007
[F] 518-292-6511
[E] Rbrandon@anscorporate.com



CrownCastle.com

**For Lease
Information**

**For 24 Hour Service
Questions or
Emergencies Call**

**Crown Castle
Business Unit**

877-486-9377
800-788-7011
806374

**North Street
Rocky Hill, CT
HRT 081 943236**



6.2.3 GC AND TEP REDLINE DRAWINGS

MODIFICATION OF AN EXISTING 140' MONOPOLE

VALMONT #10604-86

BU #806374; HRT 081 943236

NORTH STREET

ROCKY HILL, CONNECTICUT 06067

HARTFORD COUNTY

LAT: 41° 38' 23.2"; LONG: -72° 42' 6.83"

APP: 363221 REV. 9; WO: 1365734

PROJECT CONTACTS

STRUCTURE OWNER:

CROWN CASTLE

MOD PM: DAN VADNEY AT DAN.VADNEY@CROWNCastle.COM

PH: (518) 373-3510

MOD CM: JASON D'AMICO AT JASON.D'AMICO@CROWNCastle.COM

PH: (860) 209-0104

ENGINEER OF RECORD:

PJFMOD@PJFWEB.COM

THIS PROJECT INCLUDES THE FOLLOWING ITEMS

SHAFT REINFORCING

PAINT MODIFICATIONS TO MATCH EXISTING POLE

SHEET INDEX

SHEET NUMBER	DESCRIPTION
T-1	TITLE SHEET
T-2	MI CHECKLIST
S-1	GENERAL NOTES
S-2A	FORGBOLT™ DETAILS
S-2B	NEXGEN2™ BOLT DETAIL
S-2C	AJAX ONESIDE™ BOLT DETAIL
S-3	MONOPOLE PROFILE

WIND DESIGN DATA

REFERENCE STANDARD	ANSI/TIA-222-G-2-2009 2016 CONNECTICUT BUILDING CODE
LOCAL CODE	
ULTIMATE WIND SPEED (3-SECOND GUST)	125 MPH
CONVERTED NOMINAL WIND SPEED (3-SECOND GUST)	97 MPH
ICE THICKNESS	1.0 IN
ICE WIND SPEED	50 MPH
SERVICE WIND SPEED	60 MPH
RISK CATEGORY	II
EXPOSURE CATEGORY	C
Kz1	1.0

TEP REDLINES
Monday, August 21, 2017
Scott Coburn
X Built As Drawn
Contractor Red Line Verified
Discrepancies Noted

Built per Design
8/11/17
ANS
Ron Brandon

QUALIFIED ENGINEERING SERVICES ARE AVAILABLE FROM PAUL J. FORD & COMPANY TO ASSIST CONTRACTORS IN CLASS IV RIGGING PLAN REVIEWS. FOR REQUESTED QUALIFIED ENGINEERING SERVICES, PLEASE CONTACT RIGGING@PJFWEB.COM.

THE ASSOCIATED FAILING SA WO NUMBER FOR THIS PROJECT IS 1355829

ATTENTION ALL CONTRACTORS, ANYTIME YOU ACCESS A CROWN SITE FOR ANY REASON YOU ARE TO CALL THE CROWN NOC UPON ARRIVAL AND DEPARTURE, DAILY AT (800) 788-7011.

MODIFICATION OF AN EXISTING 140'
MONOPOLE
BU #806374; HRT 081 943236
ROCKY HILL, CONNECTICUT

PJF
PAUL J. FORD & COMPANY
250 E Broad St., Ste 600
Columbus, OH 43215
Phone 614.221.8679
www.pjfford.com


CROWN CASTLE
8 PARKMEADOW DRIVE, PITTSFORD, NY 14534
PH: (685) 889-3445

© Copyright 2017, by Paul J. Ford and Company. All Rights Reserved. This document and the data contained herein, is proprietary to Paul J. Ford and Company, issued in strict confidence and shall not, without the prior written permission of Paul J. Ford and Company, be reproduced, copied or transmitted in any form or by any means, intended for any purpose other than the intended use for this specific project.

PROJECT No: 37517-05/19.002.7700
DRAWN BY: B.M.S.
DESIGNED BY: J.W.M.
CHECKED BY: B.K.K.
DATE: 8-27-2017


TITLE SHEET

T-1



PRE-INSTALLED FORGBOLT™ ASSEMBLY DETAIL 1

TEP REDLINES
Monday, August 21, 2017
Scott Coburn
X Built As Drawn
Contractor Red Line Verified
Discrepancies Noted



INSTALLED FORGBOLT™ ASSEMBLY DETAIL 2

FORGBolt®							AISC Group A Material: ASTM A325 and PC8.8 (Tensile Stress, Fu = 120 ksi minimum)		
GROUP A	FORGBolt® Size (mm)	Overall Length (inches)	Estimated Weight Each (lbs)	Grip Range (inch)	Comment	Color Code			
FORGBolt® A325 - PC8.8	135	5.31	1.3	3/8" to 1"	--	RED			
	160	6.30	1.6	3/4" to 1-1/2"	--	GREEN			
	195	7.68	1.9	1-1/4" to 2-1/4"	--	BLUE			
	260	10.24	2.6	2" to 3-1/2"	Splice Bolt	YELLOW			
	365	14.37	3.6	3-1/2" to 5-1/2"	Flange Jump Bolt	ORANGE			
DTI	440	17.32	4.3	5-1/2" to 8-1/2"	Flange Jump Bolt	BLACK			
Note	Each Group A (A325/PC8.8) FORGBolt® assembly shall have a 'Squirter' DTI that is compatible with a M20-PC8.8 bolt.								

FOLLOW ALL MANUFACTURER / DISTRIBUTOR RECOMMENDATIONS FOR INSTALLATION, TIGHTENING, AND INSPECTION

INSTALLATION NOTES:

1. FIELD DRILL HOLES TO 30 MM DIAMETER.
2. SELECT CORRECT BOLT SIZE FOR INSTALLATION GRIP (REFER TO PLANS).
3. INSERT BOLT ASSEMBLY THROUGH HOLES IN SHAFT REINFORCING PLATES AND SEAT THE HARDENED WASHER W1.
4. FLUSH AGAINST OUTSIDE OF PLATE.
5. HAND TIGHTEN NUT TO FINGER TIGHT.
6. TIGHTEN NUT TO PRETENSIONED CONDITION AND UNTIL DTI SHOWS PROPER INDICATION.
7. PROPERLY DOCUMENT AND INSPECT BOLT TIGHTENING PER PLAN REQUIREMENTS.

BOLT HOLE NOTES:

1. ALL SHOP-DRILLED HOLES SHALL BE NOMINAL 30 MM DIAMETER. THE MAXIMUM SHOP-DRILLED HOLE DIAMETER PERMITTED IS 1-3/16".
2. ALL FIELD-DRILLED HOLES SHALL BE NOMINAL 30 MM DIAMETER. THE MAXIMUM FIELD-DRILLED HOLE DIAMETER PERMITTED IS 30 MM.

BOLT TIGHTENING AND INSPECTION NOTES:

1. ALL STRUCTURAL BOLTS SHALL BE INSTALLED AND TIGHTENED TO THE PRETENSIONED CONDITION ACCORDING TO THE REQUIREMENTS OF THE AISC 'SPECIFICATION FOR STRUCTURAL JOINTS USING HIGH-STRENGTH BOLTS', DEC. 31, 2009.
2. ALL STRUCTURAL BOLTS SHALL BE INSPECTED ACCORDING TO THE REQUIREMENTS OF THE AISC 'SPECIFICATION FOR STRUCTURAL JOINTS USING HIGH-STRENGTH BOLTS', DEC. 31, 2009.

**AISC GROUP A MATERIAL: ASTM A325 AND PC8.8
(Fu = 120 KSI MIN TENSILE STRESS)**

CONTAINS PROPRIETARY INFORMATION PATENT PENDING

© Copyright 2013 to 2015 by PTP, all rights reserved.

DISTRIBUTOR CONTACT:
PRECISION TOWER PRODUCTS
PHONE: 888-926-4857
EMAIL: info@precisiontowerproducts.com
WEB: www.precisiontowerproducts.com

Built per Design
8/11/17
ANS
Ron Brandon

S-2A

**FORGBOLT™
DETAILS**


**MODIFICATION OF AN EXISTING 140'
MONOPOLE
BU #806374; HRT 081 943236
ROCKY HILL, CONNECTICUT**

PJF PAUL J. FORD & COMPANY
250 E Broad St, Ste 400
Columbus, OH 43215
Phone 614.221.8879
www.pauljford.com

8 PARKMEADOW DRIVE, PITTSFORD, NY 14534
PH: (609) 899-9445

© Copyright 2017, by Paul J. Ford and Company. All rights reserved. This document contains proprietary information and is intended for use by the client only. The data contained herein, is proprietary to Paul J. Ford and Company, based in the state of Ohio. No part of this document may be reproduced, stored in a retrieval system, or transmitted, in any form or by any means, electronic, mechanical, photocopying, recording, or by any information storage or retrieval system, without the prior written permission of Paul J. Ford and Company. In reproduction, copied or otherwise, the user shall acknowledge the source and provide credit to the original author. This document is provided for use for this specific project.

1. NOTE: SHEAR SLEEVE LENGTH: THE SHEAR SLEEVE SHALL PROJECT A MINIMUM OF 3/8" BEYOND THE OUTERMOST SHEAR PLANE. THE CONTRACTOR SHALL SUBMIT FABRICATION DRAWINGS SHOWING NEXGEN2® BOLT LENGTHS AND SHEAR SLEEVE LENGTHS TO THE EOR FOR REVIEW AND APPROVAL.



TYPICAL NEXGEN2™ BOLT DETAIL 1
S-2B

TEP REDLINES
Monday, August 21, 2017
Scott Coburn
X Built As Drawn
Contractor Red Line Verified
Discrepancies Noted

DISTRIBUTOR CONTACT DETAILS:
ALLFASTENERS
15401 COMMERCE PARK DR.
BROOKPARK, OHIO 44142
PHONE: 440-232-6060
E-MAIL: SALES@ALLFASTENERS.COM

FOLLOW ALL MANUFACTURER / DISTRIBUTOR RECOMMENDATIONS FOR INSTALLATION, TIGHTENING, AND INSPECTION

BOLT HOLE NOTES:

1. ALL SHOP-DRILLED HOLES SHALL BE NOMINAL 30 MM DIAMETER. THE MAXIMUM SHOP-DRILLED HOLE DIAMETER PERMITTED IS 1-3/16".
2. ALL FIELD-DRILLED HOLES SHALL BE NOMINAL 30 MM DIAMETER. THE MAXIMUM FIELD-DRILLED HOLE DIAMETER PERMITTED IS 30 MM.

BOLT TIGHTENING AND INSPECTION NOTES:

1. ALL NEXGEN2® BOLT ASSEMBLIES SHALL BE INSTALLED AND TIGHTENED TO THE PRETENSIONED CONDITION ACCORDING TO THE REQUIREMENTS OF SECTION 8.2.3 OF THE AISC SPECIFICATION FOR STRUCTURAL JOINTS USING HIGH-STRENGTH BOLTS, DEC. 31, 2009. PER SECTION 8.2.3: ALL FASTENER ASSEMBLIES SHALL BE INSTALLED IN ACCORDANCE WITH THE REQUIREMENTS IN AISC SECTION 8.1 WITHOUT SEVERING THE SPLINED END AND WITH WASHERS POSITIONED AS REQUIRED IN AISC SECTION 6.2. PER REQUIREMENTS IN SECTION 8.1: PRIOR TO BOLT PRETENSIONING, THE JOINT SHALL FIRST BE COMPACTED TO THE SNUG-TIGHT CONDITION. SNUG TIGHT IS THE CONDITION THAT EXISTS WHEN ALL OF THE PLIES IN THE CONNECTION HAVE BEEN PULLED INTO FIRM CONTACT BY THE BOLTS AND THE BOLTS HAVE BEEN TIGHTENED SUFFICIENTLY TO PREVENT THE REMOVAL OF THE NUTS WITHOUT THE USE OF A WRENCH. ONCE THE SNUG TIGHT CONDITION IS ACHIEVED, THEN THE BOLT ASSEMBLY CAN BE TIGHTENED TO THE PRETENSIONED CONDITION.
2. ALL NEXGEN2® BOLT ASSEMBLIES SHALL BE INSPECTED ACCORDING TO THE REQUIREMENTS OF SECTION 9.2.3 OF THE AISC SPECIFICATION FOR STRUCTURAL JOINTS USING HIGH-STRENGTH BOLTS, DEC. 31, 2009. NOTE THAT COMPLETE INSPECTION OF ALL NEXGEN2® BOLT ASSEMBLIES IS REQUIRED IN ADDITION TO ROUTINE OBSERVATION.
3. ALL NEXGEN2® BOLTS SHALL BE INSPECTED BY A QUALIFIED BOLT INSPECTOR PER NOTES 1 AND 2, ABOVE. DURING INSTALLATION, THE BOLT INSPECTOR SHALL VERIFY AND DOCUMENT: THE SHOP-DRILLED AND FIELD-DRILLED HOLE SIZES; THE INSTALLATION OF THE NEXGEN2® BOLT ASSEMBLY, INCLUDING THE SHEAR SLEEVE PLACEMENT AND NUT LUBRICATION; AND THE CONTRACTOR'S TENSIONING PROCEDURE. THE BOLT INSPECTOR SHALL PROVIDE COMPLETE DOCUMENTATION OF ALL BOLTS AFTER TIGHTENING CLEARLY SHOWING THAT THE DOUBLE HEX SPLINED END OF THE BOLTS HAVE BEEN TWISTED OFF AND COATED WITH CROWN APPROVED COLD-GALVANIZING COMPOUND.

PART NUMBER	BOLT LENGTH	SLEEVE LENGTH	MIN GRIP RANGE	MAX GRIP RANGE
M20x36	M20x95	1 3/16"	1 5/16"	1 7/16"
M20x48	M20x95	1 3/16"	1 7/16"	1 7/8"
M20x57	M20x95	1 5/8"	1 7/8"	2 1/4"
M20x68	M20x135	2"	2 1/4"	2 1 1/16"
M20x96	M20x135	2 7/16"	2 1 1/16"	3 3/4"
M20x127	M20x165	3"	3 3/4"	5"
M20x212	M20x250	4"	5"	8 5/16"

NOTE: NEXGEN2® BOLT ASSEMBLY SHALL BE MAGNI 565 COATED PER ASTM F2833 AND MANUFACTURER SPECIFICATIONS.

NOTE: INSTALL NEXGEN2® BOLT ASSEMBLY PER MANUFACTURER'S INSTRUCTIONS.

Built per Design
8/11/17
ANS
Ron Brandon

© Copyright 2011, by Paul J. Ford and Company, Inc. All rights reserved. No part of this document may be reproduced, stored in a retrieval system, or transmitted in any form or by any means, electronic, mechanical, photocopying, recording, or by any information storage and retrieval system, without the prior written permission of Paul J. Ford and Company, Inc. This document is the property of Paul J. Ford and Company, Inc. and is loaned to you for this specific project.

PAUL J. FORD & COMPANY
250 E Broad St., Ste 600 - Columbus, OH 43215
Phone 614.221.6679
www.paulford.com
CROWN CASTLE
8 PARKMEAD DRIVE, PITTSFORD, NY 14534
PIT: (609) 699-3445


MODIFICATION OF AN EXISTING 140' MONOPOLE
BU #806374, HRT 081 943236
ROCKY HILL, CONNECTICUT

PROJECT No: 37514619 (002.7700)
DRAWN BY: B.M.S.
DESIGNED BY: J.W.M.
CHECKED BY: J.K.K.
DATE: 2-27-2017

NEXGEN2™ BOLT
DETAIL

S-2B

1. NOTE: SHEAR SLEEVE LENGTH: THE SHEAR SLEEVE SHALL PROJECT A MINIMUM OF 3/8" BEYOND THE OUTERMOST SHEAR PLANE. THE CONTRACTOR SHALL SUBMIT FABRICATION DRAWINGS SHOWING AJAX ONESIDE™ BOLT LENGTHS AND SHEAR SLEEVE LENGTHS TO THE EOR FOR REVIEW AND APPROVAL.



TYPICAL AJAX ONESIDE™ BOLT DETAIL 1 S-2C

TEP REDLINES
Monday, August 21, 2017
Scott Coburn
X Built As Drawn
— Contractor Red Line Verified
Discrepancies Noted

FOLLOW ALL MANUFACTURER / DISTRIBUTOR RECOMMENDATIONS FOR INSTALLATION, TIGHTENING, AND INSPECTION

- BOLT TIGHTENING AND INSPECTION NOTES:**
- ALL SHOP-DRILLED HOLES SHALL BE NOMINAL 30 MM DIAMETER. THE MAXIMUM SHOP-DRILLED HOLE DIAMETER PERMITTED IS 1-3/16".
 - ALL FIELD-DRILLED HOLES SHALL BE NOMINAL 30 MM DIAMETER. THE MAXIMUM FIELD-DRILLED HOLE DIAMETER PERMITTED IS 30 MM.

- BOLT TIGHTENING AND INSPECTION NOTES:**
- ALL AJAX ONESIDE™ BOLT ASSEMBLIES SHALL BE INSTALLED AND TIGHTENED TO THE PRETENSIONED CONDITION ACCORDING TO THE REQUIREMENTS OF SECTION 8.2.4 OF THE AISC SPECIFICATION FOR STRUCTURAL JOINTS USING HIGH-STRENGTH BOLTS, DEC. 31, 2009. PER SECTION 8.2.4: ALL FASTENER ASSEMBLIES SHALL BE INSTALLED IN ACCORDANCE WITH THE REQUIREMENTS IN AISC SECTION 8.1 WITH WASHERS POSITIONED AS REQUIRED IN AISC SECTION 8.2. PER REQUIREMENTS IN SECTION 8.1: PRIOR TO BOLT PRETENSIONING, THE JOINT SHALL FIRST BE COMPACTED TO THE SNUG-TIGHT CONDITION. SNUG TIGHT IS THE CONDITION THAT EXISTS WHEN ALL OF THE PILES IN THE CONNECTION HAVE BEEN PULLED INTO FIRM CONTACT BY THE BOLTS AND THE BOLTS HAVE BEEN TIGHTENED SUFFICIENTLY TO PREVENT THE REMOVAL OF THE NUTS WITHOUT THE USE OF A WRENCH. ONCE THE SNUG TIGHT CONDITION IS ACHIEVED, THEN THE BOLT ASSEMBLY CAN BE TIGHTENED TO THE PRETENSIONED CONDITION.
 - ALL AJAX ONESIDE™ BOLT ASSEMBLIES SHALL BE INSPECTED ACCORDING TO THE REQUIREMENTS OF SECTION 9.2.4 OF THE AISC SPECIFICATION FOR STRUCTURAL JOINTS USING HIGH-STRENGTH BOLTS, DEC. 31, 2009. NOTE THAT COMPLETE INSPECTION OF ALL AJAX ONESIDE™ BOLT ASSEMBLIES IS REQUIRED IN ADDITION TO ROUTINE OBSERVATION.
 - ALL AJAX ONESIDE™ BOLTS SHALL BE INSPECTED BY A QUALIFIED BOLT INSPECTOR PER NOTES 1 AND 2, ABOVE. DURING INSTALLATION, THE BOLT INSPECTOR SHALL VERIFY AND DOCUMENT: THE SHOP-DRILLED AND FIELD-DRILLED HOLE SIZES; THE INSTALLATION OF THE AJAX ONESIDE™ BOLT ASSEMBLY, INCLUDING THE SHEAR SLEEVE PLACEMENT AND NUT LUBRICATION; AND THE CONTRACTOR'S TENSIONING PROCEDURE. THE BOLT INSPECTOR SHALL PROVIDE COMPLETE DOCUMENTATION OF ALL BOLTS AFTER TIGHTENING CLEARLY SHOWING THAT THE DIRECT TENSION INDICATOR WASHERS SHOW THAT THE PROPER BOLT TENSION HAS BEEN REACHED.
 - A MINIMUM OF 4 OUT OF 5 SQUIRTER® DTI PROTRUSIONS SHALL BE ENGAGED IN ANY AJAX ONESIDE™ DTI BOLT ASSEMBLY IN THE REINFORCING MEMBERS. A FEELER GAGE MAY BE USED TO VERIFY PROTRUSION COMPRESSION.
 - INSPECTIONS SHALL BE IN ACCORDANCE WITH THE MANUFACTURER'S REQUIREMENTS AND CROWN DOCUMENT ENG-SOW-10007: MODIFICATION INSPECTION SOW.

- BOLT ASSEMBLY AND INSTALLATION:**
- BOLT MUST BE PURCHASED PRE-ASSEMBLED.
 - FOLLOW BOLT AND DTI MANUFACTURERS INSTRUCTIONS FOR INSTALLATION.

AJAX ONESIDE™ BOLT DETAIL

CODE	SIZE	COLOR	SLEEVE LENGTH	GRIP	GRIP IMP
OSBA20.65-6	M20 x 65	ORANGE	6.0 (0.236")	12.5 / 20.0	0.500" / 0.787"
OSBA20.95-14	M20 x 95	BLACK	14.0 (0.551")	20.0 / 32.0	0.787" / 1.259"
OSBA20.95-22	M20 x 95	GREEN	22.0 (0.866")	30.0 / 50.0	1.181" / 1.968"
OSBA20.95-30	M20 x 95	YELLOW	30.0 (1.181")	40.5 / 50.0	1.595" / 1.968"
OSBA20.135-39	M20 x 135	BLUE	39.0 (1.535")	49.0 / 77.0	1.929" / 3.031"
OSBA20.135-48	M20 x 135	BROWN	48.0 (1.889")	60.5 / 77.0	2.375" / 3.031"
OSBA20.135-57	M20 x 135	PURPLE	57.0 (2.244")	67.0 / 90.0	2.637" / 3.543"
OSBA20.165-76	M20 x 165	RED	76.0 (3.000")	87.0 / 120.0	3.425" / 4.724"
OSBA20.250	M20 x 250	SILVER	MTD	121.0 / 211.0	4.724" / 8.310"

DISTRIBUTOR
IRA SVENSGAARD AND ASSOCIATES
PETER SVENDSGAARD - PETERS@IRASVENS.COM
JOHN KILLAM - JOHN@IRASVENS.COM
PHONE: (530) 647-8225
FAX: (530) 647-8229

MANUFACTURER
AJAX FASTENERS
SALES • TECH: ONESIDE@AJAXFAST.COM.AU

Built per Design
8/11/17
ANS
Ron Brandon

AJAX ONESIDE™
BOLT DETAIL

S-2C

MODIFICATION OF AN EXISTING 140'
MONOPOLE
BU #806374; HRT 081 943236
ROCKY HILL, CONNECTICUT

PAUL J. FORD & COMPANY
250 E Broad St, Ste 400, Columbus, OH 43215
Phone 614 221 6679
www.pauljford.com
8 PARKMEADOW DRIVE, PITTSFORD, NY 14534
PH: (565) 899 3445

Copyright 2017, by Paul J. Ford and Company. All Rights Reserved. This document and the data contained herein, is proprietary to Paul J. Ford and Company, issued in strict confidence and shall not, without the prior written permission of Paul J. Ford and Company, be reproduced, stored in a retrieval system, or transmitted in any form or by any means, electronic, mechanical, photocopying, recording, or by any information storage and retrieval system, without the prior written permission of Paul J. Ford and Company.

PROJECT NO: 2517-051002.7700
DRAWN BY: S.M.S.
DESIGNED BY: J.W.M.
CHECKED BY: J.C.C.
DATE: 8/1/2017

Copyright 2017 by Paul J. Ford and Company
All Rights Reserved. This document and
the data contained herein, in proprietary
to Paul J. Ford and Company, issued in
confidence and shall not, without the
prior written permission of Paul J. Ford
be reproduced, stored in a retrieval system,
or used for any purpose other than the
intended use for this specific project.

PJF PAUL J. FORD & COMPANY
250 E Broad St, Ste 400 Columbus, OH 43215
Phone 614.221.8679 www.pauljford.com
8 PARKMEADOW DRIVE, PITTSFORD, NY 14534
PH: (565) 899-3445

MODIFICATION OF AN EXISTING 140' MONOPOLE
BU #806374; HRT 081 943236
ROCKY HILL, CONNECTICUT

PROJECT No: 37517-0619-002.7700
DRAWN BY: B.M.S.
DESIGNED BY: J.W.M.
CHECKED BY: B.K.C.
DATE: 2-27-2017

MONOPOLE PROFILE

S-3

SHEET SECTION DATA

SHAFT SECTION	SECTION LENGTH (FT)	PLATE THICKNESS (IN)	DIAMETER ACROSS FLATS (IN)	DIAMETER ACROSS FLATS (IN)	POLE SHAPE
1	54.83	0.1875	18.000	26.260	12-SIDED
2	54.83	0.3125	25.083	35.360	12-SIDED
3	40.00	0.3750	33.750	41.250	12-SIDED

NOTE: DIMENSIONS SHOWN DO NOT INCLUDE GALVANIZING TOLERANCES

TOWER MODIFICATION SCHEDULE


ELEVATION	TOWER MODIFICATION DESCRIPTION	REFERENCE SHEETS
86'-0" TO 96'-0"	INSTALL NEW SHAFT REINFORCING	S-3
86'-0" TO 96'-0"	PAINT MODIFICATIONS TO MATCH EXISTING POLE	S-3

NEW COIL FLAT PLATE (85 KSI) REINFORCING SCHEDULE


BOTTOM ELEVATION	TOP ELEVATION	FLAT #1 DEGREE SEPARATION	ELEMENT LENGTH	ELEMENT QUANTITY	APPROXIMATE TOTAL BOLT QUANTITY	TERMINATION BOLTS (BOTTOM)	TERMINATION BOLTS (TOP)	MAXIMUM INTERMEDIATE BOLT SPACING	ESTIMATED TOTAL STEEL WEIGHT
86'-0"	96'-0"	F2 F6 & F10	10'-0"	3	17	51	6	16"	366 LBS

NOTES:

- 1) ALL STEEL SHALL BE HOT-DIP GALVANIZED AFTER FABRICATION IN ACCORDANCE WITH ASTM A123. ALTERNATIVELY ALL NEW STEEL FENDER PLATE STEEL REINFORCING MAY BE COLD GALVANIZED AS FOLLOWS: 40% MINIMUM OF TWO COATS OF ZINC-RICH COLD GALVANIZING COMPOUND. FILM THICKNESS PER COAT SHALL BE NET 3.0 MILS DRY 15 MILS. APPLY PER ZINC MANUFACTURER'S RECOMMENDED PROCEDURES. CONTACT ZRC AT 1-800-851-3275 FOR PRODUCT INFORMATION.
- 2) ALL REINFORCING SHALL BE ASTM A72 GR. 65.
- 3) WELDS SHALL BE ER70X OR GREATER. TERMINATION WELDS SHALL BE 3/8" FILLET WELDS.
- 4) HOLES FOR BOLTS ARE 3mm UNLESS NOTED OTHERWISE.
- 5) ALL SHIMS SHALL BE ASTM A36.
- 6) ALL HOLES ARE TO BE DRILLED, DO NOT BURN OR PUNCH.
- 7) FOR PLATES STARTING AT 6" THE BOTTOM OF THE FLAT PLATE SHALL BEGIN AT 6" x 1" FOR SINGLE PLATES OR MULTIPLE PLATES SPliced TOGETHER. THE BOTTOM OF THE FLAT PLATE SHALL BEGIN AT THE PROPOSED ELEVATION +3" FOR MULTIPLE PLATES SPliced TOGETHER. THE TOP OF THE FLAT PLATE IS TO BE PLACED SUCH THAT THERE IS NO MORE THAN 3" DIFFERENCE BETWEEN THE ACTUAL OVERALL LENGTH OF THE SPAN AND THE PROPOSED OVERALL LENGTH OF THE SPAN FROM THE BOTTOM OF THE PLATE TO THE TOP OF THE PLATE.



POLE ELEVATION 1
S-3



BASE LEVEL DRAWING


TEP REDLINES
Monday, August 21, 2017
Scott Coburn
Built As Drawn
X Contractor Red Line Verified
The second tower splice was verified at 86'-1" where 85'-2" is shown in the modification drawings.
This was approved by the engineer of record. Please see Section 6.3.4 for correspondence.

SECTION 2
S-3
EL. 96'

NOTE: FLAT LOCATION OF THE EXISTING STEP BOLTS MAY DIFFER FROM SHOWN DEPENDING ON THE LOCATION OF THE EXISTING STEP BOLTS AND REPAIR STEP BOLTS AS REQUIRED FOR REINFORCING INSTALLATION

POST-CONSTRUCTION

6.3.1 EXECUTIVE SUMMARY

Photograph	Observations and Recommendations
	<u>Item 1</u> Observation: New reinforcement plates were installed to the tower from an elevation of 86.5-ft to 96.5-ft. This was completed in accordance with page S-3 of the modification drawings provided by Paul J. Ford and Company dated March 1, 2017 except as noted. Note: The tower splice 2 was field verified at 86'-1" where the drawings state 85'-2". This was approved by the engineer of record. Please see Section 6.3.4 for correspondence.

6.3.2 PHOTOGRAPHS



6.3.3 CONTRACTOR PHOTOGRAPHS



6.3.4 ENGINEER OF RECORD EMAIL

Punchlist BU # 806374 - HRT 081

Status:

Complete

Project Information

Project Contacts	Punchlist Issuance #	Date	Visit	Structural Impact To Capacity
MI Vendor	Tower Engineering Professionals	1	15-Aug	OnSite
MI On-site Inspector	James Harms, Scott Coburn			No
MI WO #	1391964			# of Punchlist Items
General Contractor	ANS			1
Crown POC	Dan Vadney			
EOR	Please Select			
BU	806374			
Site Name	HRT 081			

1 Puchlist Item(s)

NonConformance Impact to Capacity
(Shall Be Provided by EOR)

New Overall Structure Capacity Rating :

MI Checklist Documents

Documentation Complete / Documentation Missing					
MI Checklist Documents	Required	Date Submitted	Requirement Waived	Date Compliance Verified	Status
PRE-CONSTRUCTION					
EOR Approved Shop Drawings	Required	8/11/2017	N/A	8/21/2017	Complete
Foundations Inspection	N/A	N/A	N/A	-	N/A
Fabricator Certified Weld Inspection	N/A	N/A	N/A	-	N/A
Material Test Report (MTR)	Required	8/11/2017	N/A	8/21/2017	Complete
Fabricator NDE Report	N/A	N/A	N/A	-	N/A
NDE Insp. Report of Monopole Base Plate	N/A	N/A	N/A	-	N/A
Packing Slips	Required	8/11/2017	N/A	8/21/2017	Complete
Additional Pre-Construction Inspections	N/A	N/A	N/A	-	N/A
CONSTRUCTION					
Foundation Inspections	N/A	N/A	N/A	-	N/A
Post-Installed Anchor Rod Verification	N/A	N/A	N/A	-	N/A
Base Plate Grout Verification	N/A	N/A	N/A	-	N/A
Contractor's Certified Weld Inspection	N/A	N/A	N/A	-	N/A
Hot Work Permit	N/A	N/A	N/A	-	N/A
On-Site Cold Galvanizing Verification	Required	8/11/2017	N/A	8/21/2017	Complete
Guy Wire Tension Report	N/A	N/A	N/A	-	N/A
GC As-Built Drawings	Required	8/11/2017	N/A	8/21/2017	Complete
Additional Construction Inspections	N/A	N/A	N/A	-	N/A
POST-CONSTRUCTION					
Construction Compliance Verification	Required	8/11/2017	N/A	8/21/2017	Complete
Post-Installed Anchor Rod Pull-Out Testing	N/A	N/A	N/A	-	N/A
Additional Post-Construction Inspections	N/A	N/A	N/A	-	N/A
MI Checklist Comments					

Nonconformance List

Add Punchlist Item

Create PDF

Nonconformance # 1

MI Vendor				Crown	Final Crown Approval	
Nonconformance					Crown Approval By	
Issue Description						
The tower splice shown as 85'-2" was field verified at 86'-1"				EOR Feedback Requested		
Section/Height/Elev	Panel	Leg	Face/Flat	EOR	MI Vendor	
86'-1"					Status of Correction	Type of Verification
					Conformance	EOR/Crown Approved
					Correction Photo (additional photos uploaded to WO)	
				EOR Approved - No Capacity Impact		
				Capacity Impact As Is		
				No Capacity Impact		
				EOR Feedback By		
				Name of Engineer Providing Feedback		
MI Comments:				Enter Comments		
EOR Comments:				Enter Comments		
Crown Comments:				EOR to confirm issue ok or recommend fix in field.		



Dewberry Engineers Inc.
600 Parsippany Road, Suite 301
Parsippany, NJ 07054

973.739.9400
973.739.9710 fax
www.dewberry.com

May 28, 2019

State Of Connecticut
Connecticut Siting Council
10 Franklin Square, New Britain, CT 06051

Re: Letter of Completion
Site Name: Rocky Hill CT
Dewberry Site No. 50091678
France Street, Lot 1
Rocky Hill, CT 06067

To Whom It May Concern:

Verizon Wireless has contracted Dewberry Engineers Inc. (Dewberry) to verify that the tower related construction activities at the above referenced project were completed in general conformance with the requirements of the construction and structural contract documents.

Dewberry referenced the following:

- Construction Drawings Rev. 0. (Dated September 5, 2017) by Dewberry Engineers signed and sealed by Jiang Yu, PE.
- Structural Modification Analysis Report (Dated May 17, 2019) by Dewberry Engineers signed and sealed by Benjamin B. Revette, PE.
- Photos of completed construction activities provided by Verizon Wireless.

Based on the information and photos provided, the mount modification construction on the tower appears to have been completed in general accordance with the Structural Modification Analysis Report.

Please contact me at 973.739.9400 or brevette@dewberry.com should you have any questions on this matter.

Sincerely,
Dewberry Engineers Inc.



Benjamin Revette, PE
Senior Associate
Connecticut License No. 28971