

KENNETH C. BALDWIN

280 Trumbull Street
Hartford, CT 06103-3597
Main (860) 275-8200
Fax (860) 275-8299
kbaldwin@rc.com
Direct (860) 275-8345

Also admitted in Massachusetts
and New York

May 25, 2022

Melanie A. Bachman, Esq.
Executive Director/Staff Attorney
Connecticut Siting Council
10 Franklin Square
New Britain, CT 06051

Re: **Notice of Exempt Modification – Facility Modification
6 Progress Avenue, Seymour, Connecticut**

Dear Attorney Bachman:

Cellco Partnership d/b/a Verizon Wireless (“Cellco”) currently maintains an existing wireless telecommunications facility at the above-referenced address (the “Property”). The facility consists of antennas and remote radio heads attached to a tower and related equipment on the ground, near the base of the tower. The tower was approved by the Town of Seymour (“Town”) in June of 2000. Cellco’s shared use of the tower was approved by the Council in September of 2010. A copy of the Town’s approval and Cellco’s TS-VER-124-100823 approval are included in Attachment 1.

Cellco now intends to modify its facility by replacing nine (9) existing antennas with three (3) Samsung 64T64RMMU antennas; six (6) MX06FRO660 antennas; removing three (3) existing remote radio heads (“RRHs”) and installing six (6) new RRHs on Cellco’s existing antenna mounts. A set of project plans showing Cellco’s proposed facility modifications and new antennas and RRHs specifications are included in Attachment 2.

Please accept this letter as notification pursuant to R.C.S.A. § 16-50j-73, for construction that constitutes an exempt modification pursuant to R.C.S.A. § 16-50j-72(b)(2). In accordance with R.C.S.A. § 16-50j-73, a copy of this letter is being sent to Seymour’s Chief Elected Official and Land Use Officer.

Melanie A. Bachman, Esq.
May 25, 2022
Page 2

The planned modifications to the facility fall squarely within those activities explicitly provided for in R.C.S.A. § 16-50j-72(b)(2).

1. The proposed modifications will not result in an increase in the height of the existing tower. The replacement antennas and RRHs will be installed on Cellco's existing antenna mounts.
2. The proposed modifications will not involve any change to ground-mounted equipment and, therefore, will not require the extension of the site boundary.
3. The proposed modifications will not increase noise levels at the facility by six decibels or more, or to levels that exceed state and local criteria.
4. The installation of Cellco's new antennas and RRHs will not increase radio frequency (RF) emissions at the facility to a level at or above the Federal Communications Commission (FCC) safety standard. A cumulative General Power Density table for the modified facility is included in Attachment 3. The modified facility will be capable of providing Cellco's 5G wireless service.
5. The proposed modifications will not cause a change or alteration in the physical or environmental characteristics of the site.
6. According to the attached Structural Analysis ("SA") and Mount Analysis ("MA"), the existing tower, tower foundation and tower base plate can support Cellco's proposed modifications. Modifications to the antenna mounts are required and proposed in this filing. Copies of the SA and MA are included in Attachment 4. Also included in Attachment 4 is a separate letter prepared by the consulting engineers responsible for the preparation of the SA and MA verifying that the antenna model described in the SA and MA, respectively, as a nL-Sub6 Antenna or License-Sub6 Antenna, is the Samsung 64T64R model antenna and RRH that will be installed on the tower.

A copy of the parcel map and Property owner information is included in Attachment 5. A Certificate of Mailing verifying that this filing was sent to municipal officials and the property owner is included in Attachment 6.

For the foregoing reasons, Cellco respectfully submits that the proposed modifications to the above-referenced telecommunications facility constitutes an exempt modification under R.C.S.A. § 16-50j-72(b)(2).

Melanie A. Bachman, Esq.
May 25, 2022
Page 3

Sincerely,

A handwritten signature in black ink, appearing to read "Kenneth C. Baldwin". The signature is fluid and cursive, with a long horizontal stroke at the end.

Kenneth C. Baldwin

Enclosures

Copy to:

Annmarie Drugonis, Seymour First Selectwoman
Keith Rosenfeld, Seymour Town Planner
EMAC LLC
Aleksey Tyurin

ATTACHMENT 1

Concrete Base for tower

Date 6-20 2000 19

APPLICATION FOR BUILDING PERMIT

B-01711

No. 8571

CD #4502

Estimated Cost \$ 126,000

Fee . . . \$ 20.00

Occupancy Fee \$ 20.00

Additional Cost \$ 1246

ling
ibing
ing
ric
res
avit
Dept.
th Dept.
oved

THE BUILDING DEPARTMENT, TOWN OF SEYMOUR, CONN.

undersigned, hereby applies for a permit to do work according to the following specifications:

2 Progress Ave Lot No. 13 Side of Street R Zone ET

est cross street Silvermine Road

er of building Emac Communication Co Inc Address 50 olivia ST

er Northeast Tower Address 170 River Rd Unionville

itect Pirad Inc Address 1545 Pidco Drive plymouth

Main Bldg.: No. ft. front overall No. ft. deep overall Area

of wings Garages No. of families No. of stories

truction Steel concrete No. of rooms: 1st 2nd 3rd

of Lot 2.11 ac Dist. from Street Line 190' Dist. from Side Line Street

ose of building is concrete tower base as per plans and specs on file

Sewer [] Septic Tank []

ling ERECTION OF STEEL TOWER

Date 6-29-19 2000

APPLICATION FOR BUILDING PERMIT

NO-FEE PD. WITH Bldg. permit.

No. 8581

REC # B-01720

Estimated Cost \$ Permitted

Fee . . . \$

Occupancy Fee \$

Additional Cost \$

ibing
ing
ric
res
avit
Dept.
th Dept.
oved

THE BUILDING DEPARTMENT, TOWN OF SEYMOUR, CONN.

undersigned, hereby applies for a permit to do work according to the following specifications:

2 Progress Ave Lot No. 13 Side of Street R Zone ET2

est cross street Silvermine Rd

er of building Emac Communications Co Inc Address 50 olivia ST Derby

er Northeast Tower Address 170 River Rd Unionville

itect Pirad Inc Address 1545 Pidco DR plymouth

Main Bldg.: No. ft. front overall No. ft. deep overall Area

of wings Garages No. of families No. of stories

truction Steel + concrete No. of rooms: 1st 2nd 3rd

of Lot 2.11 ac Dist. from Street Line 190 Dist. from Side Line Street

ose of building is Erection of steel tower as per plans & specs on file

Sewer [] Septic Tank []

SEYMOUR PLANNING AND ZONING COMMISSION

TOWN HALL

1 FIRST STREET

SEYMOUR, CONNECTICUT

ZONING PERMIT

PROPERTY IDENTIFICATION

Address 2 PROGRESS AV Zone GI-2
Tax Map 1-5 Parcel No 12N Developer's Lot No _____
Name of Applicant EMAC COMMUNICATION Tel No 735 7733

DESCRIPTION OF WORK

Construction of Bldgs and site improvements as shown
on site plan approved by PtZ 11-4-99 + M Foundation
Plans for tower on file with Town Engineer.
Construction of tower NOT authorized until bond for tower received.

PLOT PLAN AND SURVEY

① Attach plot plan prepared at a scale of not more than
60 ft to one inch. Plot plan for a zoning/start permit
shall be prepared using available data, but need not be
an A-2 survey. on file with PtZ

2. As Built- A-2 Survey

_____ Not required to assure zoning compliance

Required before a Certificate of Occupancy
will be authorized.

SOIL EROSION CONTROL PLAN

_____ Not required

Required. Show on plot plan or attach separate plan.

APPROVALS

1. Zoning/Start permit approved. Building permit authorized.

Robert Louie ASST ZEO : 6-20-00 Date

2. Zoning/Development Completion Certificate

Based on a review of the zoning/start permit, building
permit, A-2 survey as required and/or an inspection of
the property, this development conforms to the zoning
regulations and a certificate of occupancy is authorized.

_____ ZEO _____ Date



STATE OF CONNECTICUT

CONNECTICUT SITING COUNCIL

Ten Franklin Square, New Britain, CT 06051

Phone: (860) 827-2935 Fax: (860) 827-2950

E-Mail: siting.council@ct.gov

Internet: ct.gov/csc

Daniel F. Caruso
Chairman

September 24, 2010

Kenneth C. Baldwin, Esq.
Robinson & Cole LLP
280 Trumbull Street
Hartford, CT 06103-3597

RE: **TS-VER-124-100823** - Cellco Partnership d/b/a Verizon Wireless notice of intent to modify an existing telecommunications facility located at 6 Progress Avenue, Seymour, Connecticut.

Dear Attorney Baldwin:

At a public meeting held September 23, 2010, the Connecticut Siting Council (Council) ruled that the shared use of this existing tower site is technically, legally, environmentally, and economically feasible and meets public safety concerns, and therefore, in compliance with General Statutes § 16-50aa, the Council has ordered the shared use of this facility to avoid the unnecessary proliferation of tower structures. This facility has also been carefully modeled to ensure that radio frequency emissions are conservatively below State and federal standards applicable to the frequencies now used on this tower.

This decision is under the exclusive jurisdiction of the Council. Any additional change to this facility may require an explicit request to this agency pursuant to General Statutes § 16-50aa or notice pursuant to Regulations of Connecticut State Agencies Section 16-50j-73, as applicable. Such request or notice shall include all relevant information regarding the proposed change with cumulative worst-case modeling of radio frequency exposure at the closest point of uncontrolled access to the tower base, consistent with Federal Communications Commission, Office of Engineering and Technology, Bulletin 65. Any deviation from this format may result in the Council implementing enforcement proceedings pursuant to General Statutes § 16-50u including, without limitation, imposition of expenses resulting from such failure and of civil penalties in an amount not less than one thousand dollars per day for each day of construction or operation in material violation.

This decision applies only to this request for tower sharing and is not applicable to any other request or construction. Please be advised that the validity of this action shall expire one year from the date of this letter.

The proposed shared use is to be implemented as specified in your letter dated August 23, 2010 and additional correspondence dated August 31, 2010, including the placement of all necessary equipment and shelters within the tower compound.

Thank you for your attention and cooperation.

Very truly yours,

Daniel F. Caruso
Chairman

DFC/CDM/laf

c: The Honorable Paul F. Roy, First Selectman, Town of Seymour
James Baldwin, Sr., Zoning Enforcement Officer, Town of Seymour
EMAC Communications, LLC

ATTACHMENT 2



SITE NAME: WOODBRIDGE NORTH CT

6 PROGRESS AVENUE
SEYMOUR, CT 06483
TOWN OF SEYMOUR,
NEW HAVEN COUNTY



Know what's below.
Call before you dig.

NB+C
TOTALLY COMMITTED.

NB+C ENGINEERING SERVICES, LLC.
10 APOLLO DRIVE
SUITE 200
CHELSEA, MA 01824
(978) 961-8100

verizon

118 FLANDERS ROAD
FLOOR 3
WESTBOROUGH, MA 01581

SITE INFORMATION

SCOPE OF WORK: PROJECT CONSISTS OF INSTALLING ADDITIONAL EQUIPMENT AND/OR ANTENNAS TO AN EXISTING WIRELESS TELECOMMUNICATIONS FACILITY.

SITE ADDRESS: 6 PROGRESS AVENUE SEYMOUR, CT 06483

LATITUDE (NAD 83): 41-23-30.25N (41.391735°)
LONGITUDE (NAD 83): 73-03-10.32W (-73.052867°)

JURISDICTION: TOWN OF SEYMOUR NEW HAVEN COUNTY

PARCEL NUMBER: 1301.01 / 2

PROPERTY OWNER: EDMAC LLC
2702 FOREST VIEW LANE
KISSIMMEE, FL 34744

TOWER OWNER: EDMAC LLC


VZW SITE ID: WOODBRIDGE NORTH CT

STRUCTURE TYPE: SELF-SUPPORT TOWER

CONSTRUCTION TYPE: II B

USE GROUP: U

VICINITY MAP



DIRECTIONS

FROM WALLINGFORD, CT: HEAD NORTH ON US-5 N / N COLONY RD TOWARD NEAL RD. TURN BACK ON US-5 S / N COLONY RD. TAKE RAMP RIGHT FOR CT-15 SOUTH TOWARD NEW HAVEN. AT EXIT 59, TAKE RAMP RIGHT FOR CT-69 TOWARD NEW HAVEN / WOODBRIDGE. TURN LEFT ONTO CT-69 / LITCHFIELD TPKE. TURN LEFT ONTO LINDIN ST. TURN RIGHT ONTO CT-63 / AMITY RD. TURN LEFT ONTO CT-67 / SEYMOUR RD. TURN LEFT ONTO COGWHEEL LN. TURN RIGHT ONTO PROGRESS AVE. ARRIVE AT PROGRESS AVE.

LEADS TO LATITUDE 41.391735° AND LONGITUDE -73.052867°. (FRONT OF BUILDING)

CODE COMPLIANCE

ALL WORK AND MATERIALS SHALL BE PERFORMED AND INSTALLED IN ACCORDANCE WITH THE CURRENT EDITIONS OF THE FOLLOWING CODES AS ADOPTED BY THE LOCAL GOVERNING AUTHORITIES. NOTHING IN THESE PLANS IS TO BE CONSTRUED TO PERMIT WORK NOT CONFORMING TO THE LATEST EDITIONS OF THE FOLLOWING CODES.

- 2015 INTERNATIONAL BUILDING CODE
- 2017 NATIONAL ELECTRICAL CODE
- 2015 NATIONAL STANDARD PLUMBING CODE
- 2009 NFPA 101, LIFE SAFETY CODE
- 2015 IFC
- AMERICAN CONCRETE INSTITUTE
- AMERICAN INSTITUTE OF STEEL CONSTRUCTION
- MANUAL OF STEEL CONSTRUCTION 14TH EDITION
- ANSI/TIA-222-G
- TIA 607
- INSTITUTE FOR ELECTRICAL & ELECTRONICS ENGINEER 81
- IEEE C2 NATIONAL ELECTRIC SAFETY CODE LATEST EDITION
- TELECORDIA GR-1275
- ANSI/T 311

DRAWING INDEX

T-1 TITLE SHEET

C-1 COMPOUND PLAN

C-2 ELEVATION

A-1 EXISTING ANTENNA PLAN AND SCHEDULE

A-2 PROPOSED ANTENNA PLAN AND SCHEDULE

A-3 ANTENNA DETAILS & PLUMBING DIAGRAM

A-4 EQUIPMENT SPECIFICATIONS

A-5 SCOPE OF WORK

G-1 GROUNDING SCHEMATIC & DETAILS

GN-1 PMI REQUIREMENTS

MODIFICATION DRAWING ATTACHED

DO NOT SCALE DRAWINGS

THESE DRAWINGS ARE FORMATTED TO BE FULL-SIZE AT 22"X34". CONTRACTOR SHALL VERIFY ALL PLANS AND EXISTING DIMENSIONS AND CONDITIONS ON THE JOB SITE AND SHALL IMMEDIATELY NOTIFY THE DESIGNER / ENGINEER IN WRITING OF ANY DISCREPANCIES BEFORE PROCEEDING WITH THE WORK OR MATERIAL ORDERS OR BE RESPONSIBLE FOR THE SAME. CONTRACTOR SHALL USE BEST MANAGEMENT PRACTICE TO PREVENT STORM WATER POLLUTION DURING CONSTRUCTION.

APPROVAL BLOCK

| | APPROVED | APPROVED AS NOTED | DISAPPROVED/REVISE |
|---------------------------------------|--------------------------|--------------------------|--------------------------|
| CONSTRUCTION MANAGER _____ DATE _____ | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| SITE ACQUISITION _____ DATE _____ | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| RF ENGINEER _____ DATE _____ | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| LESSOR/LESSOR REP _____ DATE _____ | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |

CONTRACTOR PMI REQUIREMENTS

PMI ACCESSED AT: [HTTPS://PMI.VZWSMART.COM](https://pmi.vzwsmart.com)

SMART TOOL VENDOR PROJECT PROJECT NUMBER: 100765

VERIZON LOCATION CODE (PSLC): 469060

*** PMI AND REQUIREMENTS ALSO EMBEDDED IN MOUNT ANALYSIS REPORT

MOUNT REPLACEMENT REQUIRED

YES

VERIZON APPROVED VENDORS

* REFER TO CONSTRUCTION DRAWINGS.

ENGINEER

APPLICANT

SITE INFORMATION

DESIGN RECORD

PROFESSIONAL STAMP

ENGINEER

SHEET TITLE

SHEET NUMBER

WOODBRIDGE NORTH CT
6 PROGRESS AVENUE
SEYMOUR, CT 06483
TOWN OF SEYMOUR
NEW HAVEN COUNTY

REVISIONS


| REV | DATE | DESCRIPTION | BY |
|-----|----------|-------------------|-----|
| 4 | 5/18/22 | ANTENNA REVISIONS | DC |
| 3 | 5/02/22 | REVISED PER MA | KM |
| 2 | 03/02/21 | FINAL CDR | RAL |
| 1 | 01/29/21 | FINAL CDR | RAL |
| 0 | 12/15/20 | PRELIMINARY CDR | ALM |



DANIEL J. CORNING, P.E.
CT PROFESSIONAL ENGINEER LIC. #34055

TITLE SHEET

T-1



1
C-1
COMPOUND PLAN
SCALE: 1/8" = 1' (23X34)
SCALE: 1/16" = 1' (11X17)

GENERAL NOTES

1. THE CONTRACTOR SHALL COMPLY WITH ALL APPLICABLE CODES ORDINANCES, LAWS AND REGULATIONS OF ALL MUNICIPALITIES, UTILITIES COMPANY OR OTHER PUBLIC AUTHORITIES.
2. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL PERMITS AND INSPECTIONS THAT MAY BE REQUIRED BY ANY FEDERAL, STATE, COUNTY OR MUNICIPAL AUTHORITIES.
3. THE CONTRACTOR SHALL NOTIFY THE CONSTRUCTION MANAGER, IN WRITING, OF ANY CONFLICTS, ERRORS OR OMISSIONS PRIOR TO THE SUBMISSION OF BIDS OR PERFORMANCE OF WORK. MINOR OMISSIONS OR ERRORS IN THE BID DOCUMENTS SHALL NOT RELIEVE THE CONTRACTOR FROM RESPONSIBILITY FOR THE OVERALL INTENT OF THESE DRAWINGS.
4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING ALL EXISTING SITE IMPROVEMENTS PRIOR TO COMMENCING CONSTRUCTION. THE CONTRACTOR SHALL REPAIR ANY DAMAGE CAUSED AS A RESULT OF CONSTRUCTION OF THIS FACILITY.
5. THE SCOPE OF WORK FOR THIS PROJECT SHALL INCLUDE PROVIDING ALL MATERIALS, EQUIPMENT AND LABOR REQUIRED TO COMPLETE THIS PROJECT. ALL EQUIPMENT SHALL BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS.
6. THE CONTRACTOR SHALL VISIT THE PROJECT SITE PRIOR TO SUBMITTING A BID TO VERIFY THAT THE PROJECT CAN BE CONSTRUCTED IN ACCORDANCE WITH THE CONTRACT DOCUMENTS.
7. ALL STRUCTURAL ELEMENTS SHALL BE HOT DIPPED GALVANIZED STEEL.
8. CONTRACTOR SHALL MAKE A UTILITY "ONE CALL" TO LOCATE ALL UTILITIES PRIOR TO EXCAVATING.
9. IF ANY UNDERGROUND UTILITIES OR STRUCTURES EXIST BENEATH THE PROJECT AREA, CONTRACTOR MUST LOCATE IT AND CONTACT THE APPLICANT & THE OWNER'S REPRESENTATIVE.
10. OCCUPANCY IS LIMITED TO PERIODIC MAINTENANCE AND INSPECTION BY TECHNICIANS APPROXIMATELY 2 TIMES PER MONTH.
11. THIS PLAN IS SUBJECT TO ALL EASEMENTS AND RESTRICTIONS OF RECORD.
12. NO SIGNIFICANT NOISE, SMOKE, DUST, OR ODOR WILL RESULT FROM THIS FACILITY.
13. THE FACILITY IS UNMANNED AND NOT INTENDED FOR HUMAN HABITATION (NO HANDICAP ACCESS REQUIRED).
14. THE FACILITY IS UNMANNED AND DOES NOT REQUIRE POTABLE WATER OR SANITARY SERVICE.



NB+C ENGINEERING SERVICES, LLC.
100 APOLLO DRIVE
SUITE 200
CHELSEA, MA 01924
(978) 945-0100



118 FLANDERS ROAD
FLOOR 3
WESTBOROUGH, MA 01581

WOODBIDGE NORTH CT
6 PROGRESS AVENUE
SEYMOUR, CT 06483
TOWN OF SEYMOUR
NEW HAVEN COUNTY

REVISIONS


| REV | DATE | DESCRIPTION | BY |
|-----|----------|-------------------|-----|
| 4 | 5/16/22 | ANTENNA REVISIONS | DC |
| 3 | 6/22/22 | REVISED PER MA | JM |
| 2 | 03/22/21 | FINAL CD# | RAL |
| 1 | 01/28/21 | FINAL CD# | RAL |
| 0 | 12/15/20 | PRELIMINARY CD# | ALM |




DANIEL J. CORNING, P.E.
CT PROFESSIONAL ENGINEER LIC. #34055

COMPOUND PLAN

C-1






NOTE:
 POST-MODIFICATION INSPECTION (PM) REQUIRED ON ALL SITES. REFER TO THE MOUNT ANALYSIS PREPARED BY MASER CONSULTING DATED 04/12/2022 FOR ADDITIONAL DETAILS.

NOTE:
 REPLACEMENT OF THE EXISTING MOUNT IS REQUIRED BEFORE ANY INSTALL CAN OCCUR. PLEASE REFER TO SHEET 10 AND THE MOUNT ANALYSIS REPORT PROVIDED BY MASER CONSULTING DATED, 04/12/2022

1
 ELEVATION
 SCALE: 1" = 20' (22X34)
 SCALE: 1" = 40' (11X17)



ENGINEER

NB+C
 TOTALLY COMMITTED.

NB+C ENGINEERING SERVICES, LLC.
 100 WOLFE DRIVE
 SUITE 200
 CHELSEA, MA 01924
 (978) 541-0100

APPLICANT

verizon

118 FLANDERS ROAD
 FLOOR 3
 WESTBOROUGH, MA 01581

SITE INFORMATION

WOODBIDGE NORTH CT
 6 PROGRESS AVENUE
 SEYMOUR, CT 06483
 TOWN OF SEYMOUR
 NEW HAVEN COUNTY

DESIGN RECORD

| REVISIONS | | | |
|-----------|----------|-------------------|-----|
| REV | DATE | DESCRIPTION | BY |
| 4 | 5/16/22 | ANTENNA REVISIONS | DC |
| 3 | 6/02/22 | REVISED PER MA | KM |
| 2 | 03/02/21 | FINAL CD# | RAL |
| 1 | 01/28/21 | FINAL CD# | RAL |
| 0 | 12/15/20 | PRELIMINARY CD# | ALM |

PROFESSIONAL STAMP

ENGINEER


DANIEL J. CORNING, P.E.
 CT PROFESSIONAL ENGINEER LIC. #34055

SHEET TITLE

ELEVATION

SHEET NUMBER

C-2



1
A-1
EXISTING ANTENNA ORIENTATION PLAN
NTS


| ANTENNA POSITION | ANTENNA MANUFACTURER | ANTENNA MODEL | RAD CENTER | AZIMUTH | DOWN TILT | | RRH QUANTITY & MODEL | TECHNOLOGY | CABLE SIZE, LENGTH & QUANTITY |
|------------------|----------------------|-----------------|------------|---------|-----------|------|----------------------------------|------------|-------------------------------|
| | | | | | MECH | ELEC | | | |
| A-1 | ANTEL | LPA-80063/BCF | 140.00' | 10° | 2" | 0" | - | 850 CDMA | (4) 1-5/8" COAX |
| A-2 | COMMSCOPE | HBXX-6517DS-A2M | 140.00' | 10° | 0" | 2" | UHC B4 RRH 2x60-4R | AWS | |
| A-3 | COMMSCOPE | LNX-6514DS | 140.00' | 10° | 2" | 4" | B5/B13 RRH - BR04C (IN SHELTER) | 700/850 | |
| A-4 | AMPHENOL | BXA-171063-12BF | 140.00' | 10° | 0" | 2" | B2/BB6A RRH - BR049 (IN SHELTER) | PCS | |
| A-5 | ANTEL | LPA-80063/BCF | 140.00' | 10° | 2" | 0" | - | 850 CDMA | |
| B-1 | ANTEL | LPA-80063/BCF | 140.00' | 110° | 4" | 0" | - | 850 CDMA | (4) 1-5/8" COAX |
| B-2 | COMMSCOPE | HBXX-6517DS-A2M | 140.00' | 110° | 0" | 2" | UHC B4 RRH 2x60-4R | AWS | |
| B-3 | COMMSCOPE | LNX-6514DS | 140.00' | 110° | 4" | 4" | B5/B13 RRH - BR04C (IN SHELTER) | 700/850 | |
| B-4 | AMPHENOL | BXA-171063-12BF | 140.00' | 110° | 0" | 2" | B2/BB6A RRH - BR049 (IN SHELTER) | PCS | |
| B-5 | ANTEL | LPA-80063/BCF | 140.00' | 110° | 4" | 0" | - | 850 CDMA | |
| G-1 | ANTEL | LPA-80063/BCF | 140.00' | 240° | 2" | 0" | - | 850 CDMA | (4) 1-5/8" COAX |
| G-2 | COMMSCOPE | HBXX-6517DS-A2M | 140.00' | 240° | 0" | 5" | UHC B4 RRH 2x60-4R | AWS | |
| G-3 | AMPHENOL | BXA-70063-6BF | 140.00' | 240° | 4" | 4" | B5/B13 RRH - BR04C (IN SHELTER) | 700/850 | |
| G-4 | AMPHENOL | BXA-171063-12BF | 140.00' | 240° | 0" | 2" | B2/BB6A RRH - BR049 (IN SHELTER) | PCS | |
| G-5 | ANTEL | LPA-80063/BCF | 140.00' | 240° | 4" | 0" | - | 850 CDMA | |

SHARED THROUGH HYBRIFLEX

| ENGINEER | TOTALLY COMMITTED. NB+C ENGINEERING SERVICES, LLC. <small>10 APOLLO DRIVE SUITE 200 CHELSEA, MA 01934 (978) 962-0000</small> | | | | | | | | | | | | | | | | | | | | | | | | |
|--------------------|---|-------------------|--|--|-----|------|-------------|---|---------|-------------------|---|---------|----------------|---|----------|-----------|---|----------|-----------|---|----------|-----------------|-----|------|-------------|
| APPLICANT | 118 FLANDERS ROAD FLOOR 3 WESTBOROUGH, MA 01581 | | | | | | | | | | | | | | | | | | | | | | | | |
| SITE INFORMATION | WOODBIDGE NORTH CT 6 PROGRESS AVENUE SEYMOUR, CT 06483 TOWN OF SEYMOUR NEW HAVEN COUNTY | | | | | | | | | | | | | | | | | | | | | | | | |
| DESIGN RECORD | <table border="1"> <thead> <tr> <th colspan="3">REVISIONS</th> </tr> <tr> <th>REV</th> <th>DATE</th> <th>DESCRIPTION</th> </tr> </thead> <tbody> <tr> <td>4</td> <td>5/16/22</td> <td>ANTENNA REVISIONS</td> </tr> <tr> <td>3</td> <td>9/20/22</td> <td>REVISED PER MA</td> </tr> <tr> <td>2</td> <td>03/22/21</td> <td>FINAL CD#</td> </tr> <tr> <td>1</td> <td>01/29/21</td> <td>FINAL CD#</td> </tr> <tr> <td>0</td> <td>12/16/20</td> <td>PRELIMINARY CD#</td> </tr> <tr> <td>REV</td> <td>DATE</td> <td>DESCRIPTION</td> </tr> </tbody> </table> | REVISIONS | | | REV | DATE | DESCRIPTION | 4 | 5/16/22 | ANTENNA REVISIONS | 3 | 9/20/22 | REVISED PER MA | 2 | 03/22/21 | FINAL CD# | 1 | 01/29/21 | FINAL CD# | 0 | 12/16/20 | PRELIMINARY CD# | REV | DATE | DESCRIPTION |
| REVISIONS | | | | | | | | | | | | | | | | | | | | | | | | | |
| REV | DATE | DESCRIPTION | | | | | | | | | | | | | | | | | | | | | | | |
| 4 | 5/16/22 | ANTENNA REVISIONS | | | | | | | | | | | | | | | | | | | | | | | |
| 3 | 9/20/22 | REVISED PER MA | | | | | | | | | | | | | | | | | | | | | | | |
| 2 | 03/22/21 | FINAL CD# | | | | | | | | | | | | | | | | | | | | | | | |
| 1 | 01/29/21 | FINAL CD# | | | | | | | | | | | | | | | | | | | | | | | |
| 0 | 12/16/20 | PRELIMINARY CD# | | | | | | | | | | | | | | | | | | | | | | | |
| REV | DATE | DESCRIPTION | | | | | | | | | | | | | | | | | | | | | | | |
| PROFESSIONAL STAMP | | | | | | | | | | | | | | | | | | | | | | | | | |
| ENGINEER | DANIEL J. CORNING, P.E. CT PROFESSIONAL ENGINEER LIC. #34055 | | | | | | | | | | | | | | | | | | | | | | | | |
| SHEET TITLE | EXISTING ANTENNA PLAN AND SCHEDULE | | | | | | | | | | | | | | | | | | | | | | | | |
| SHEET NUMBER | A-1 | | | | | | | | | | | | | | | | | | | | | | | | |

GENERAL ANTENNA NOTES

- ALL ANTENNAS TO BE FURNISHED WITH DOWNTILT BRACKETS. CONTRACTOR IS TO COORDINATE AND VERIFY THE PROPOSED DOWNTILTS WITH VERIZON MANAGER PRIOR TO CONSTRUCTION.
- ANTENNA CENTERLINE HEIGHT IS IN REFERENCE TO ELEVATION 0.0' (EXISTING GRADE).
- CHECK WITH RF ENGINEER FOR LATEST ANTENNA TYPE & AZIMUTH.
- CONTRACTOR SHALL VERIFY ANTENNA TYPE AND AZIMUTH WITH CONSTRUCTION MANAGER PRIOR TO CONSTRUCTION.
- ALL CABLE LENGTHS ARE ESTIMATED AND SHALL BE FIELD VERIFIED BY THE CONTRACTOR.
- COLOR TAPE MARKINGS MUST BE 3/4" WIDE AND UV RESISTANT, SUCH AS SCOTCH 35 VINYL ELECTRICAL COLOR CODING TAPE.
- CONTRACTOR SHALL COORDINATE COLOR CODINGS IN THE FIELD WITH VERIZON REPRESENTATIVE.
- PRIOR TO THE INSTALLATION OF THE PROPOSED EQUIPMENT OR MODIFICATION OF THE EXISTING STRUCTURE, A STRUCTURAL ANALYSIS SHALL BE PERFORMED BY THE OWNER'S AGENT TO CERTIFY THAT THE EXISTING/PROPOSED COMMUNICATION STRUCTURE AND COMPONENTS ARE STRUCTURALLY ADEQUATE TO SUPPORT ALL EXISTING AND PROPOSED ANTENNAS, COAXIAL CABLES AND OTHER APPURTENANCES. THE OWNER'S AGENT SHALL FURNISH A CERTIFICATION LETTER SEALED BY A REGISTERED PROFESSIONAL ENGINEER STATING THAT THIS STRUCTURAL ANALYSIS WAS PREPARED IN ACCORDANCE WITH ALL APPLICABLE CODES AND STANDARDS.



NOTE: POST-MODIFICATION INSPECTION (PMI) REQUIRED ON ALL SITES. REFER TO THE MOUNT ANALYSIS PREPARED BY MASER CONSULTING DATED 04/12/2022 FOR ADDITIONAL DETAILS.

NOTE: REPLACEMENT OF THE EXISTING MOUNT IS REQUIRED BEFORE ANY INSTALL OAH OCCURS. PLEASE REFER TO SHEET 10 AND THE MOUNT ANALYSIS REPORT PROVIDED BY MASER CONSULTING DATED, 04/12/2022.

PROPOSED ANTENNA & RRH SCHEDULE

| ANTENNA POSITION | ANTENNA MANUFACTURER | ANTENNA MODEL | RAD CENTER | AZIMUTH | DOWN TILT | | RRH QUANTITY & MODEL | TECHNOLOGY | CABLE SIZE, LENGTH & QUANTITY |
|------------------|----------------------|----------------|------------|---------|-----------|------|----------------------|------------|---|
| | | | | | MECH | ELEC | | | |
| A-1 | ANTEL | LPA-8006.3/8CF | 140' | 10' | 2' | 0' | - | 850 CDMA | (4) 1-5/8" COAX (1) 1.43" HYBRID CABLE |
| A-2 | JMA WIRELESS | MX06FR080-03 | 140' | 10' | 0' | 2' | B2/B66A RRH - BR048 | AWS/PCS | |
| A-3 | JMA WIRELESS | MX06FR080-03 | 140' | 10' | 0' | 8' | B5/B13 RRH - BR04C | 700/850 | |
| A-4 | SAMSUNG | MT8407-77A | 140' | 10' | 0' | 3' | - | 5G | |
| A-5 | ANTEL | LPA-8006.3/8CF | 140' | 10' | 2' | 0' | - | 850 CDMA | |
| B-1 | ANTEL | LPA-8006.3/8CF | 140' | 110' | 4' | 0' | - | 850 CDMA | (4) 1-5/8" COAX (1) 1.43" HYBRID CABLE |
| B-2 | JMA WIRELESS | MX06FR080-03 | 140' | 110' | 0' | 2' | B2/B66A RRH - BR048 | AWS/PCS | |
| B-3 | JMA WIRELESS | MX06FR080-03 | 140' | 110' | 0' | 8' | B5/B13 RRH - BR04C | 700/850 | |
| B-4 | SAMSUNG | MT8407-77A | 140' | 110' | 0' | 3' | - | 5G | |
| B-5 | ANTEL | LPA-8006.3/8CF | 140' | 110' | 4' | 0' | - | 850 CDMA | |
| G-1 | ANTEL | LPA-8006.3/8CF | 140' | 240' | 4' | 0' | - | 850 CDMA | (4) 1-5/8" COAX SHARED THROUGH HYBRIFLEX |
| G-2 | JMA WIRELESS | MX06FR080-03 | 140' | 240' | 0' | 2' | B2/B66A RRH - BR048 | AWS/PCS | |
| G-3 | JMA WIRELESS | MX06FR080-03 | 140' | 240' | 0' | 8' | B5/B13 RRH - BR04C | 700/850 | |
| G-4 | SAMSUNG | MT8407-77A | 140' | 240' | 0' | 3' | - | 5G | |
| G-5 | ANTEL | LPA-8006.3/8CF | 140' | 240' | 4' | 0' | - | 850 CDMA | |

- NOTES:
 1. CONTRACTOR TO VERIFY PROPOSED ANTENNA INFORMATION IS THE MOST CURRENT DATA AT TIME OF CONSTRUCTION.
 2. CONTRACTOR TO CONFIRM CABLE LENGTHS PRIOR TO CONSTRUCTION.
 3. CONTRACTOR IS RESPONSIBLE TO BUILD FROM THE LATEST RF SHEET.



NB+C ENGINEERING SERVICES, LLC.
 10 APPLE DRIVE
 SUITE 200
 CHESHAM, MA 01524
 (978) 981-0000



118 FLANDERS ROAD
 FLOOR 3
 WESTBOROUGH, MA 01581

WOODBIDGE NORTH CT
 6 PROGRESS AVENUE
 SEYMOUR, CT 06483
 TOWN OF SEYMOUR
 NEW HAVEN COUNTY

REVISIONS



| REV | DATE | DESCRIPTION | BY |
|-----|----------|-------------------|-----|
| 4 | 5/16/22 | ANTENNA REVISIONS | DC |
| 3 | 5/02/22 | REVISED PER MA | JM |
| 2 | 03/02/21 | FINAL CDR | RAL |
| 1 | 01/28/21 | FINAL CDR | RAL |
| 0 | 12/15/20 | PRELIMINARY CDR | ALM |



DANIEL J. CORNING, P.E.
 CT PROFESSIONAL ENGINEER LIC. #34055

PROPOSED ANTENNA PLAN & SCHEDULE

A-2





| PROPOSED ANTENNA SPECIFICATIONS | | | | | | |
|---------------------------------|---------------|----------|--------|--------|--------|----------|
| ANTENNA MANUFACTURER | ANTENNA MODEL | QUANTITY | HEIGHT | WIDTH | DEPTH | WEIGHT |
| SAMSUNG | MT6407-77A | 3 | 35.12" | 16.06" | 5.51" | 87.1 LBS |
| JMA | MX06FRO660-03 | 6 | 71.30" | 15.40" | 10.70" | 60.0 LBS |

| EXISTING ANTENNA SPECIFICATIONS | | | | | | |
|---------------------------------|-------------------|----------|--------|-------|-------|----------|
| ANTENNA MANUFACTURER | ANTENNA MODEL | QUANTITY | HEIGHT | WIDTH | DEPTH | WEIGHT |
| AMPHENOL | LPA-80063/6CF | 6 | 70.9" | 15.0" | 13.1" | 27.0 LBS |
| SWEDCOM | * BXA-171063-12BF | 3 | 72.5" | 6.1" | 4.1" | 12.8 LBS |
| AMPHENOL | * BXA-70063-6CF | 1 | 71.0" | 11.2" | 5.2" | 17.0 LBS |
| COMMSCOPE | * HBXX-631703-A2M | 3 | 75.0" | 12.0" | 6.5" | 40.8 LBS |
| COMMSCOPE | * LHX-651405 | 2 | 72.9" | 11.9" | 7.1" | 31.3 LBS |


* TO BE REMOVED

1 SAMSUNG MT6407-77A INTEGRATED ANTENNA
A-3 NTS

2 ANTENNA MOUNTING DETAILS
A-3 NTS



- Port 1 & 2 are for low band (800-850 MHz).
- Port 3, 4, 5, & 6 are for high band (1875-2380 MHz).
- Smart Bias Tee (SBT) is through port 1 & 5 for low band and port 2 for high band.
- AISG cable is only needed when shown in the diagrams below. If it is not shown then SBT is enough to control all RET motors.
- Not all SBT ports are needed to control RET, only green port connection to green port will control RET.



DC Signal Cabling Fun

AISG Cable

RET Cable for RET (Port that will control RET)

Hydriflex cables

Comments:

Diagram shows antenna port configuration as viewed from below antennas.

Antenna positions are indicated as viewed from IN FRONT of antennas.

Cap and weatherproof unused antenna ports.

All plumbing diagram colors are irrelevant except for AISG & Hydriflex cables. (See the coax colors follow Coax Colors guide above)

3 MX06FRO660-03 ANTENNA DETAILS
A-3 NTS

4 ANTENNA MOUNTING DETAILS
A-3 NTS

RFDS DATED 11/17/20, 10:12:29



NB+C ENGINEERING SERVICES, LLC.
10 APOLLO DRIVE
SUITE 200
CHELSEA, MA 01924
(978) 961-8100



118 FLANDERS ROAD
FLOOR 3
WESTBOROUGH, MA 01581

WOODBIDGE NORTH CT
6 PROGRESS AVENUE
SEYMOUR, CT 06483
TOWN OF SEYMOUR
NEW HAVEN COUNTY

REVISIONS

| REV | DATE | DESCRIPTION | BY |
|-----|----------|-------------------|-----|
| 4 | 5/16/22 | ANTENNA REVISIONS | DC |
| 3 | 9/20/22 | REVISED PER MA | JM |
| 2 | 03/02/21 | FINAL CDR | RAL |
| 1 | 01/29/21 | FINAL CDR | RAL |
| 0 | 12/15/20 | PRELIMINARY CDR | ALM |



DANIEL J. CORNING, P.E.
CT PROFESSIONAL ENGINEER LIC. #34055

ANTENNA DETAILS & PLUMBING DIAGRAM

A-3

RRH EQUIPMENT SPECIFICATIONS

| PROPOSED EQUIPMENT | MANUFACTURER | MODEL # | LOCATION | QUANTITY | HEIGHT | WIDTH | DEPTH | WEIGHT |
|--------------------|--------------|--|-------------------|----------|--------|--------|-------|----------|
| | NOKIA | AHFC AIRSCALE DUAL RRH 4T4R B2/B66a 320W | TOWER (RELOCATED) | 3 | 28.74" | 15.35" | 9.44" | 79.4 LBS |
| | NOKIA | AHFC AIRSCALE DUAL RRH 4T4R B5/B13 320W | TOWER (RELOCATED) | 3 | 28.74" | 15.35" | 9.44" | 72.8 LBS |

| EXISTING EQUIPMENT | MANUFACTURER | MODEL # | LOCATION | QUANTITY | HEIGHT | WIDTH | DEPTH | WEIGHT |
|--------------------|--------------|------------------|----------|----------|--------|-------|-------|----------|
| | LUCENT | * B4-AWS 2x60-4R | TOWER | 3 | 36.6" | 10.6" | 5.75" | 55.0 LBS |

* TO BE REMOVED


DISTRIBUTION BOX EQUIPMENT SPECIFICATIONS

| EXISTING EQUIPMENT | MANUFACTURER | MODEL # | LOCATION | QUANTITY | HEIGHT | WIDTH | DEPTH | WEIGHT |
|--------------------|--------------|------------------|----------|----------|--------|--------|--------|----------|
| | RAYCAP | RRFDC-3115-PF-4B | TOWER | 2 | 29.00" | 15.73" | 10.25" | 32.0 LBS |


DIPLEXER/COMBINER EQUIPMENT SPECIFICATIONS

| EXISTING EQUIPMENT | MANUFACTURER | MODEL # | LOCATION | QUANTITY | HEIGHT | WIDTH | DEPTH | WEIGHT |
|--------------------|--------------|------------------|----------|----------|--------|-------|-------|----------|
| | UNKNOWN | * LB/HB DIPLEXER | TOWER | 3 | - | - | - | - |
| | COMMSCOPE | * CBC721-DF-2X | SHELTER | 3 | 7.2" | 6.0" | 3.7" | 11.5 LBS |
| | COMMSCOPE | * CHB626-43-2X | SHELTER | 3 | 7.1" | 14.6" | 3.4" | 19.4 LBS |


* TO BE REMOVED



WEIGHT = 90.0 LBS




FRONT VIEW




SIDE VIEW

1 SAMSUNG B2/B66A (REMOTE RADIO HEAD)
A-4 NTS



WEIGHT = 74.5 LBS




FRONT VIEW



SIDE VIEW

2 SAMSUNG B5/B13 (REMOTE RADIO HEAD)
A-4 NTS



3 RRH MOUNTING DETAIL
A-4 NTS

ENGINEER

NB+C
TOTALLY COMMITTED.

NB+C ENGINEERING SERVICES, LLC.
10 APOLLO DRIVE
SUITE 200
CHELSEA, MA 01824
(978) 241-2222

APPLICANT

verizon

118 FLANDERS ROAD
FLOOR 3
WESTBOROUGH, MA 01581

SITE INFORMATION

WOODBIDGE NORTH CT
6 PROGRESS AVENUE
SEYMOUR, CT 06483
TOWN OF SEYMOUR
NEW HAVEN COUNTY

DESIGN RECORD

| REVISIONS | | | |
|-----------|----------|-------------------|-----|
| REV | DATE | DESCRIPTION | BY |
| 4 | 5/18/22 | ANTENNA REVISIONS | DC |
| 3 | 9/20/22 | REVISED PER MA | KM |
| 2 | 03/02/21 | FINAL CD# | RAL |
| 1 | 01/29/21 | FINAL CD# | RAL |
| 0 | 12/15/20 | PRELIMINARY CD# | ALM |

PROFESSIONAL STAMP



ENGINEER

DANIEL J. CORNING, P.E.
CT PROFESSIONAL ENGINEER, LIC. #34055

SHEET TITLE

EQUIPMENT SPECIFICATIONS

SHEET NUMBER

A-4

VERIZON WIRELESS CONTRACTOR SCOPE OF WORK

MOP FOR RET INSTALLS

- VERIZON WIRELESS CONTRACTOR IS TO SUPPLY AND INSTALL THE PROPOSED CABLE JUMPER (WITH LC TO LC CONNECTORS) FROM THE PROPOSED FIBER TRAYS TO THE PROPOSED MAIN DISTRIBUTION BOX (BOTTOM).
 - VERIZON WIRELESS CONTRACTOR IS TO SUPPLY AND INSTALL ALL MOUNTING HARDWARE AND 1/2" ANTENNA JUMPER CABLES AS REQUIRED DURING CONSTRUCTION.
 - VERIZON WIRELESS CONTRACTOR IS TO MAKE ALL ALARM CONNECTIONS TO THE DISTRIBUTION BOXES AND LEAVE A 40' COIL FOR OTHERS TO PUNCH INTO ALARM BLOCK.
 - VERIZON WIRELESS CONTRACTOR IS TO INSTALL (6) RUNS OF HELIAX 1/1 HYBRID CABLE FROM THE EXISTING MAIN DISTRIBUTION BOXES TO THE REMOTE RADIO HEAD UNITS.
 - VERIZON WIRELESS CONTRACTOR IS TO SUPPLY AND INSTALL 1/2" ANTENNA JUMPERS FROM EACH PROPOSED REMOTE RADIO HEAD UNIT (RRH) TO THE PROPOSED ANTENNAS IN ALL SECTORS (36 TOTAL 1/2" ANTENNA JUMPERS).
 - VERIZON WIRELESS CONTRACTOR IS TO SEAL ALL DISTRIBUTION BOXES AS REQUIRED DURING CONSTRUCTION.
 - VERIZON WIRELESS CONTRACTOR IS TO INSTALL THE PROPOSED REMOTE RADIO HEAD UNITS IN ALL SECTORS ON THE ANTENNA PIPE.
 - VERIZON WIRELESS CONTRACTOR IS TO GROUND ALL REMOTE RADIO HEAD UNITS (RRH) TO THE EXISTING GROUND BARS AS REQUIRED DURING CONSTRUCTION.
 - VERIZON WIRELESS CONTRACTOR IS TO GROUND ALL PROPOSED ANTENNAS TO THE EXISTING GROUND BARS AS REQUIRED DURING CONSTRUCTION.
 - VERIZON WIRELESS CONTRACTOR IS TO COMPLETE THE INSTALLATION OF THE PROPOSED ANTENNAS.
 - VERIZON WIRELESS CONTRACTOR IS TO PERFORM THE FOLLOWING OPTICAL SWEEP TESTS; OTDR AND OPTICAL LOSS. RECOMMENDED UNITS – ANRITSU MT9090, JDSU, EXFO FTB-1/FTB-720 OTDR.
 - VERIZON WIRELESS CONTRACTOR IS TO PERFORM THE FOLLOWING ANTENNA SYSTEM SWEEP TESTS: SYSTEM VZWR / dB RL.
 - VERIZON WIRELESS CONTRACTOR IS TO PROVIDE ALL CLOSE OUT DOCUMENTS AS REQUIRED BY VERIZON WIRELESS.
- SAMSUNG RRRH
- DUAL RRRH B2/B66A RFV01DU–D1A HELIAX 1/1 HYBRID CABLE CABLE MUST BE CONNECTED TO THE L0 PRIMARY PORT.
 - DUAL RRRH B5/B13 RFV01DU–D2A HELIAX 1/1 HYBRID CABLE MUST BE CONNECTED TO THE L0 PRIMARY PORT.
- INTEGRATED ANTENNA
- VZS01 1/1 HYBRID CABLE MUST BE CONNECTED TO OPT1 PORT AND (1) EXTRA FIBER CABLE TO THE SECONDARY OPT2 PORT.

ANTENNA CREW




1. REVIEW ANTENNA SCHEDULE WITH CELL TECH
2. FOR EACH SECTOR, LAY ANTENNAS OUT ON THE GROUND AS THEY WILL BE INSTALLED ACCORDING TO THE ANTENNA SCHEDULE
3. LABEL EACH ANTENNA WITH FACE AND POSITION WITH A SHARPIE (EX:"ALPHA-4")
4. LABEL ALL MOTORS WITH SHARPIE WITH BAND AND TECHNOLOGY (EX:"700LTE", "AWSLTE", "PCSLTE", "850VOICE", ETC)
5. CONNECT ALL AISG CABLES (INCLUDING JUMPERS THAT WILL BE USED IN FINAL ASSEMBLY) PER THE ANTENNA SCHEDULE
 - A. WHEN DAISY CHAINING IS INEVITABLE, AS A GENERAL RULE...
 - I. KEEP LOW AND HIGH BANDS ON SEPARATE AISG CHAINS AS MUCH AS POSSIBLE
 - II. MINIMIZE AMOUNT OF MOTORS PER CHAIN AS MUCH AS POSSIBLE (MAX IS 6)
 - B. WHEN COMPLETED ALL RET MOTOR PORTS NEED TO BE CONNECTED, INCLUDING THE MOTORS NOT BEING USED YET. THE ONLY UNUSED PORT WILL BE THE LAST IN THE DAISY CHAIN, WHICH NEEDS TO BE CAPPED AND WEATHERPROOFED.
6. ON LAPTOP, FILL OUT THE SOFTCOPY OF THE RET DEPLOYMENT FORM AND SAVE IT, REPLACING THE "#####" WITH THE 6-DIGIT ENB NUMBER IN THE FILENAME (EX: RET DEPLOYMENT FORM_0981234.XLSX")
7. GIVE A SOFTCOPY OF THE RET DEPLOYMENT FORM TO VZW CELL TECH AND GC/CONSULTANT (EITHER BY EMAIL OR USB STICK)
8. USING THE SAME LAPTOP WHICH HAS THE RET DEPLOYMENT FORM OPENED, CONNECT THE CONTROL MODULE AND PROVISION EACH MOTOR RESPECTIVELY

NOTE: CREWS MUST USE SOFTWARE THAT IS SPECIFIC TO THE MOTOR TYPE BEING PROVISIONED (IE- JMA SOFTWARE SHOULD ONLY BE SUED FOR JMA MOTORS)


 - A. COPY AND PASTE "RET FRIENDLY NAME" FROM SPREADSHEET (COLUMN A) TO THE "SECTOR ID" FIELD OF EACH MOTOR
 - B. POPULATE "SET RET TILT"
 - C. POPULATE "MECHANICAL TILT"
9. CALIBRATE ALL MOTORS
10. DISCONNECT NECESSARY AISG JUMPERS TO TRANSPORT ANTENNAS SAFELY TO ASSEMBLY
11. INSTALL ANTENNAS ACCORDING TO THE ANTENNA SCHEDULE, USING THE SHARPIE LABELS AS REFERENCE
12. RECONNECT ALL AISG JUMPERS
13. BEFORE PLUGGING INTO EACH RRRH, CONNECT MAIN AISG CABLE INTO CONTROLLER TO ENSURE ALL MOTORS ARE STILL SEEN IN THE DAISY CHAIN
14. PLUG AISG INTO RRRH AND NOTIFY VZW TECH OF COMPLETION

VZW TECH (USER HELP GUIDE: \\WIN-VZWNET\NORTHEAST\PAPM_IMPLEMENTATION\SYSTEM


- PERFORMANCE\USERS\MOSERGA\RET\)
15. POWER ON RADIO EQUIPMENT AND RUN ANY NECESSARY WOS
 16. "DISCOVER" THE RETS
 - A. LOG INTO SAM
 - I. VERIFY RET LICENSE ALLOCATION IN SAM
 - ENBEQUIPMENT>ENB>ACTIVATIONSERVICE>ISAISALLOWED=CHECKED
 - B. LOG INTO NEM LOCAL
 - I. GO TO TREE VIEW AND HIGHLIGHT RET SUBUNIT
 - II. ENABLE BUS SCAN
 - CONFIGURATION> ENABLE AISG BUS SCAN
 - III. ALLOCATE CONFIG RIGHTS
 - CONFIGURATION>ALLOCATION CONFIGURATION RIGHTS
 - IV. VERIFY CORRECT NUMBER OF RETS ARE DISCOVERED
 17. "COMMISSION" THE RETS
 - A. LOG INTO NEM LOCAL
 - I. STILL IN TREE VIEW, RIGHT CLICK ON "HW MODULES"
 - II. SELECT "CREATE RET MO"
 - II. RELEASE CONFIG RIGHTS
 - CONFIGURATION>RELEASE CONFIGURATION RIGHTS
 - IV. VERIFY RETSUBUNIT:SECTORNAME, ELECTRICAL TILT, AND MECHANICAL TILT ARE POPULATED
 18. "PROVISION" THE RETS
 - A. LOG INTO SAM
 - I. OPEN UP THE ENB PROPERTIES AND COMPLETE A FULL RESYNC
 - II. IN THE SEARCH TEXTBOX, SEARCH FOR "RETSUBUNIT"
 - III. VERIFY ALL RETS ARE ACCOUNTED FOR AND "RETSUBUNIT:SECTORNAME", "ANTENNAELECTICALTILT", AND "RETSUBUNIT:MECHANICALTILT " ARE ACCURATE

| ENGINEER |  NB+C ENGINEERING SERVICES, LLC. <small>10 APPLE DRIVE SUITE 200 CHELSEA, MA 01924 (978) 281-0100</small> | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
|--------------------|---|-------------------|-----|--|--|-----|------|-------------|----|---|---------|-------------------|----|---|---------|----------------|----|---|----------|-----------|-----|---|----------|-----------|-----|---|----------|-----------------|-----|
| APPLICANT |  118 FLANDERS ROAD FLOOR 3 WESTBOROUGH, MA 01581 | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| SITE INFORMATION | WOODBIDGE NORTH CT 6 PROGRESS AVENUE SEYMOUR, CT 06483 TOWN OF SEYMOUR NEW HAVEN COUNTY | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| DESIGN RECORD | <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th colspan="4">REVISIONS</th> </tr> <tr> <th>REV</th> <th>DATE</th> <th>DESCRIPTION</th> <th>BY</th> </tr> </thead> <tbody> <tr> <td>4</td> <td>5/16/22</td> <td>ANTENNA REVISIONS</td> <td>DC</td> </tr> <tr> <td>3</td> <td>5/02/22</td> <td>REVISED PER MA</td> <td>JM</td> </tr> <tr> <td>2</td> <td>03/02/21</td> <td>FINAL CD#</td> <td>RAL</td> </tr> <tr> <td>1</td> <td>01/28/21</td> <td>FINAL CD#</td> <td>RAL</td> </tr> <tr> <td>0</td> <td>12/15/20</td> <td>PRELIMINARY CD#</td> <td>ALM</td> </tr> </tbody> </table> | REVISIONS | | | | REV | DATE | DESCRIPTION | BY | 4 | 5/16/22 | ANTENNA REVISIONS | DC | 3 | 5/02/22 | REVISED PER MA | JM | 2 | 03/02/21 | FINAL CD# | RAL | 1 | 01/28/21 | FINAL CD# | RAL | 0 | 12/15/20 | PRELIMINARY CD# | ALM |
| REVISIONS | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| REV | DATE | DESCRIPTION | BY | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 4 | 5/16/22 | ANTENNA REVISIONS | DC | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 3 | 5/02/22 | REVISED PER MA | JM | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 2 | 03/02/21 | FINAL CD# | RAL | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 1 | 01/28/21 | FINAL CD# | RAL | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 0 | 12/15/20 | PRELIMINARY CD# | ALM | | | | | | | | | | | | | | | | | | | | | | | | | | |
| PROFESSIONAL STAMP |  | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| ENGINEER | DANIEL J. CORNING, P.E. CT PROFESSIONAL ENGINEER LIC. #34055 | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| SHEET TITLE | SCOPE OF WORK | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| SHEET NUMBER | A-5 | | | | | | | | | | | | | | | | | | | | | | | | | | | | |


ANTENNA LOCATION (TYP PER SECTOR ONLY)




- NOTES:
 1. TAG ALL EXISTING AND PROPOSED CABLES/JUMPERS PER V&W SPECIFICATIONS (SEE RF SCHEDULE)
 2. SEE CABLE SCHEDULE FOR CABLE LENGTHS.




1 GROUNDING RISER DIAGRAM
 G-1 NTS




3 GROUND BAR CONNECTION DETAIL
 G-1 NTS



4 COAX CABLE GROUNDING DETAIL
 G-1 NTS




5 GROUND BAR DETAIL
 G-1 NTS



6 GROUNDING STRAP WEATHERPROOFING DETAIL
 G-1 NTS

GROUNDING NOTES

- GROUNDING SHALL COMPLY WITH ARTICLE 250 OF THE NATIONAL ELECTRICAL CODE.
- ALL GROUNDING DEVICES SHALL BE U.L. APPROVED OR LISTED FOR THEIR INTENDED USE.
- ALL WIRES SHALL BE AWG THIN/THIN COPPER UNLESS NOTED OTHERWISE.
- GROUNDING CONNECTIONS TO GROUND RODS, GROUND RING WIRE, TOWER BASE AND FENCE POSTS SHALL BE EXOTHERMIC ("CADWELDS") UNLESS NOTED OTHERWISE. CLEAN SURFACES TO SHINY METAL. WHERE GROUND WIRES ARE CADWELDED TO GALVANIZED SURFACES, SPRAY CADWELD WITH GALVANIZING PAINT.
- GROUNDING CONNECTIONS TO GROUND BARS ARE TO BE TWO-HOLE BRASS MECHANICAL CONNECTORS WITH STAINLESS STEEL HARDWARE (INCLUDING SCREW SET) CLEAN GROUND BAR TO SHINY METAL. AFTER MECHANICAL CONNECTION, TREAT WITH PROTECTIVE ANTI-OXIDANT COATING.
- GROUND COAXIAL CABLE SHIELDS AT BOTH ENDS WITH MANUFACTURER'S GROUNDING KITS.
- ROUTE GROUNDING CONDUCTORS THE SHORTEST AND STRAIGHTEST PATH POSSIBLE. BEND GROUNDING LEADS WITH A MINIMUM 12" RADIUS.
- INSTALL #2 AWG GREEN-INSULATED STRANDED WIRE FOR ABOVE GRADE GROUNDING AND #2 BARE TINNED COPPER WIRE FOR BELOW GRADE GROUNDING UNLESS OTHERWISE NOTED.
- REFER TO GROUNDING PLAN FOR GROUND BAR LOCATIONS. GROUNDING CONNECTIONS SHALL BE EXOTHERMIC TYPE ("CADWELDS") TO ANTENNA MOUNTS AND GROUND RING. REMAINING GROUNDING CONNECTIONS SHALL BE COMPRESSION FITTINGS. CONNECTIONS TO GROUND BARS SHALL BE MADE WITH TWO-HOLE LUGS.
- ALL GROUND LEADS EXCEPT THOSE TO THE EQUIPMENT ARE TO BE #2 BARE TINNED COPPER WIRE. ALL EXTERIOR GROUND BARS TINNED COPPER.
- PRIOR TO INSTALLING LUGS ON GROUND WIRES, APPLY THOMAS & BETTS KOPR-SHIELD (TM OF JET LUBE INC.), PRIOR TO BOLTING GROUND WIRE LUGS TO GROUND BARS, APPLY KOPR-SHIELD OR EQUAL.
- PREPARE ALL BONDING SURFACES FOR GROUNDING CONNECTIONS BY REMOVING ALL PAINT AND CORROSION DOWN TO SHINY METAL. FOLLOWING CONNECTION, APPLY APPROPRIATE ANTI-OXIDIZATION PAINT.



2 CADWELD GROUNDING CONNECTION DETAILS
 G-1 NTS

| ENGINEER | NB+C ENGINEERING SERVICES, LLC. 100 WILLOW DRIVE SUITE 200 CHESHAM, MA 01924 (508) 945-0100 | | | | | | | | | | | | | | | | | | | | | | | | | |
|--------------------|---|-------------------|-----|------|-------------|----|---|---------|-------------------|----|---|---------|----------------|----|---|----------|-----------|-----|---|----------|-----------|-----|---|----------|-----------------|-----|
| APPLICANT | 118 FLANDERS ROAD FLOOR 3 WESTBOROUGH, MA 01581 | | | | | | | | | | | | | | | | | | | | | | | | | |
| SITE INFORMATION | WOODBRIDGE NORTH CT 6 PROGRESS AVENUE SEYMOUR, CT 06483 TOWN OF SEYMOUR NEW HAVEN COUNTY | | | | | | | | | | | | | | | | | | | | | | | | | |
| DESIGN RECORD | REVISIONS <table border="1"> <thead> <tr> <th>REV</th> <th>DATE</th> <th>DESCRIPTION</th> <th>BY</th> </tr> </thead> <tbody> <tr> <td>4</td> <td>5/16/22</td> <td>ANTENNA REVISIONS</td> <td>DC</td> </tr> <tr> <td>3</td> <td>9/22/22</td> <td>REVISED PER MA</td> <td>JM</td> </tr> <tr> <td>2</td> <td>03/22/21</td> <td>FINAL CD#</td> <td>RAL</td> </tr> <tr> <td>1</td> <td>01/29/21</td> <td>FINAL CD#</td> <td>RAL</td> </tr> <tr> <td>0</td> <td>12/15/20</td> <td>PRELIMINARY CD#</td> <td>ALM</td> </tr> </tbody> </table> | | REV | DATE | DESCRIPTION | BY | 4 | 5/16/22 | ANTENNA REVISIONS | DC | 3 | 9/22/22 | REVISED PER MA | JM | 2 | 03/22/21 | FINAL CD# | RAL | 1 | 01/29/21 | FINAL CD# | RAL | 0 | 12/15/20 | PRELIMINARY CD# | ALM |
| REV | DATE | DESCRIPTION | BY | | | | | | | | | | | | | | | | | | | | | | | |
| 4 | 5/16/22 | ANTENNA REVISIONS | DC | | | | | | | | | | | | | | | | | | | | | | | |
| 3 | 9/22/22 | REVISED PER MA | JM | | | | | | | | | | | | | | | | | | | | | | | |
| 2 | 03/22/21 | FINAL CD# | RAL | | | | | | | | | | | | | | | | | | | | | | | |
| 1 | 01/29/21 | FINAL CD# | RAL | | | | | | | | | | | | | | | | | | | | | | | |
| 0 | 12/15/20 | PRELIMINARY CD# | ALM | | | | | | | | | | | | | | | | | | | | | | | |
| PROFESSIONAL STAMP | | | | | | | | | | | | | | | | | | | | | | | | | | |
| ENGINEER | DANIEL J. CORNING, P.E. CT PROFESSIONAL ENGINEER LIC. #34055 | | | | | | | | | | | | | | | | | | | | | | | | | |
| SHEET TITLE | GROUNDING SCHEMATIC & DETAILS | | | | | | | | | | | | | | | | | | | | | | | | | |
| SHEET NUMBER | G-1 | | | | | | | | | | | | | | | | | | | | | | | | | |

POST-MODIFICATION INSPECTION (PMI) REQUIREMENT

1. PMI REQUIRED FOR ALL SITES, REFER TO VERIZON NSTD-446 SECTIONS 1.5 AND 2.3 FOR MORE INFORMATION.
2. REFER TO THE MOUNT ANALYSIS BY XXX DATED XXX FOR ADDITIONAL DETAILS.
3. GENERAL CONTRACTOR SHALL PROVIDE THE BELOW DOCUMENTATION TO THE ENGINEER OF RECORD VIA EMAIL TO VZWMOUNTS@NBCLLC.COM, DROPBOX, OR OTHER FILESHARE METHOD. PROVIDE HIGH RESOLUTION PHOTOS (DO NOT COMPRESS).
4. ENGINEER OF RECORD WILL CONDUCT A REVIEW OF THE PROVIDED DOCUMENTS TO PREPARE A PMI REPORT. ENGINEER OF RECORD WILL NOTIFY GENERAL CONTRACTOR IF ANY ADDITIONAL DOCUMENTATION IS REQUIRED TO COMPLETE THE PMI.
5. PMI DOCUMENTATION SHALL BE SUFFICIENT TO CONFIRM THE UPGRADE WAS BUILT AS DESIGNED, INCLUDING EQUIPMENT CHANGES AND STRUCTURAL MODIFICATIONS, AND IS IN ADDITION TO ANY OTHER REQUIRED CLOSEOUT PACKAGE DOCUMENTATION.
6. REQUIRED DOCUMENTATION FOR PMI INCLUDES THE FOLLOWING AT A MINIMUM. REFER TO THE MOUNT ANALYSIS FOR POSSIBLE ADDITIONAL INFORMATION. IF STRUCTURAL MODIFICATIONS ARE REQUIRED, REFER TO THE MODIFICATION DRAWINGS FOR POSSIBLE ADDITIONAL REQUIREMENTS.

6A. PROVIDE PRE-AND-POST CONSTRUCTION PHOTOS OF EACH SECTOR FROM THE MOUNT ELEVATION AND THE GROUND. CONTRACTOR IS RESPONSIBLE FOR ENSURING THE PHOTOS PROVIDED PROVIDE POSITIVE CONFIRMATION THAT THE MODIFICATION/UPGRADE WAS COMPLETED IN ACCORDANCE WITH THESE CONSTRUCTION DRAWINGS AND ANY STRUCTURAL/MOUNT MODIFICATION DRAWINGS. CONTRACTOR SHALL RELAY ANY DATA THAT CAN IMPACT THE PERFORMANCE OF THE MOUNT OR MOUNT MODIFICATION, INCLUDING SAFETY ISSUES. PHOTOS SHALL HAVE A DATE/TIME STAMP IN THE PHOTO. REFER TO THE MOUNT ANALYSIS FOR FILE STRUCTURE SCHEDULE OF PHOTOS. PROVIDE PHOTOS OF THE GATE SIGNS AND CARRIER SHELTER TO IDENTIFY THE TOWER OWNER, SITE NAME, SITE NUMBER, ETC.

6B. VERIFICATION OF THE MEMBER CONNECTIONS, BRACING, AND RELEVANT DIMENSIONS.

6C. VERIFICATION OF THE ANTENNA AND OTHER EQUIPMENT CONFIGURATION (PHOTOS OF MODEL NUMBERS/TAGS FOR ALL EQUIPMENT, AS WELL AS THE FEEDLINE CONFIGURATION). TAKE PHOTOS OF THE BACK SIDE OF EACH SECTOR AS WELL AS CLOSE-UPS OF ALL EQUIPMENT. PHOTOS SHOULD CONFIRM THE HORIZONTAL AND VERTICAL POSITIONING OF THE ANTENNAS AND EQUIPMENT AND SHALL HAVE TAPE MEASURES IN THE PHOTOS TO CONFIRM.

6D. FOR TIE-BACKS, STRUTS, MOUNT PIPES, PHOTOS TO CONFIRM THE ANGLES AND LOCATION OF ATTACHMENT POINT AT BOTH ENDS OF MEMBER, AS WELL AS DIMENSIONS, THICKNESS, AND LENGTHS OF THE MEMBERS. REFER TO THE CHECKLIST IN THE MOUNT ANALYSIS FOR ADDITIONAL INFORMATION.

6E. MOUNT ATTACHMENT TO THE SUPPORTING STRUCTURE, INCLUDING ANY KICKERS OR SUPPORTS, OR TIEBACKS.

6F. MATERIALS USED (TYPE, STRENGTH, DIMENSIONS, ETC). PROVIDE BILL OF MATERIALS AND MATERIAL SPEC TO CONFIRM MATERIAL GRADES AND SIZES. PROVIDE DOCUMENTATION FOR GALVANIZATION OF MEMBERS WHETHER HOT-DIPPED OR COLD-GALVANIZED. IF MATERIALS DIFFER FROM THOSE SPECIFIED ON THESE DRAWINGS, PROVIDE DOCUMENTATION THAT THE "EQUIVALENT" MATERIAL HAS THE SAME SPECIFICATIONS.

6G. MOUNT ORIENTATION/AZIMUTH AND ELEVATION. PROVIDE TAPE DROP PHOTOS OF ANTENNA CENTERLINE(S) AND MOUNT ATTACHMENT POINTS TO THE SUPPORTING STRUCTURE. IF THERE ARE MULTIPLE RAD CENTERS, PROVIDE PHOTOS OF ALL ELEVATIONS.

POST-MODIFICATION INSPECTION (PMI) REQUIREMENT CONT.

6H. VERIFICATION THAT THE INSTALL HAS NOT CAUSED DAMAGE TO OR UNPLANNED OBSTRUCTION OF THE FOLLOWING:

- CLIMBING FACILITIES
- SAFETY CLIMB IF PRESENT, INCLUDING PHOTOS ABOVE AND BELOW THE MOUNT.
- LIGHTING SYSTEM
- OTHER INSTALLED SYSTEMS ON THE STRUCTURE.
- CONTRACTOR SHALL ENSURE THE SAFETY CLIMB IS SUPPORTED AND NOT ADVERSELY AFFECTED BY THE INSTALLATION OF NEW COMPONENTS. THIS MAY INVOLVE THE INSTALLATION OF WIRE ROPE GUIDES OR OTHER ITEMS TO PROTECT THE WIRE ROPE.

6I. OTHER ITEMS DETERMINED BY THE STRUCTURAL ENGINEER TO ENSURE THE MOUNT WILL PERFORM AS DESIGNED. PHOTOS OF RELEVANT MEASUREMENTS, WITH SUFFICIENT DETAILS TO CONFIRM CONNECTION DETAILS, PLACEMENT OF EQUIPMENT, WALL ANCHOR DETAILS, BALLAST QUANTITIES, STRUCTURAL MODIFICATIONS ETC. DIAMETERS AND THICKNESSES OF BOLTS/THEADED RODS/ANGLES/TUBES ETC SHALL HAVE PHOTOS CONFIRMING CALIPER MEASUREMENTS.

- CONFIRMATION THAT ALL HARDWARE WAS PROPERLY INSTALLED, AND EXISTING HARDWARE WAS INSPECTED FOR ANY ISSUES.
- FOR BALLAST SLEDS, DOCUMENTATION OF THE WEIGHT OF BALLAST IN EACH SECTOR.
- FOR WALL ANCHORS, PHOTOS AND MEASUREMENTS OF OUTSIDE AND INSIDE OF CONNECTIONS. DOCUMENTATION OF ADHESIVE USED, SIZE AND LENGTH OF ANCHORS, EFFECTIVE EMBEDMENT DEPTH OF THE ANCHORS, GROUTING OF HOLLOW WALLS, SPACING AND EDGE DISTANCE MEASUREMENTS, AND ANY THROUGH-BOLTS OR BACKING PLATES.
- FOR STUD WELD CONNECTIONS, DOCUMENTATION TO CONFIRM SURFACE PREPARATION, STUD WELD SIZE, GRADE, LENGTH, AND SPACING.
- FOR FABRICATED PARTS, SHOP DRAWINGS TO BE APPROVED BY THE ENGINEER OF RECORD PRIOR TO CONSTRUCTION.
- FOR WELDED PARTS, CERTIFIED WELD INSPECTION.
- FOR BOLTED PARTS, BOLT INSTALLATION AND TORQUE.

7. CONTRACTOR SHALL PROVIDE, IN ADDITION TO THE ABOVE, AS-BUILT CDS WITH REDLINES IDENTIFYING ANY CHANGES. THE AS-BUILTS SHALL THE CONTRACTOR'S NAME, PREPARER'S SIGNATURE, AND DATE.

8. IF THE MODIFICATION INSTALLATION WOULD FAIL THE PMI ("FAILED PMI"), THE CONTRACTOR SHALL WORK WITH THE ENGINEER OF RECORD TO COORDINATE A REMEDIATION PLAN IN ONE OF TWO WAYS:

8A. CORRECT FAILING ISSUES TO COMPLY WITH THE SPECIFICATIONS CONTAINED IN THE ORIGINAL CONTRACT DOCUMENTS AND COORDINATE A SUPPLEMENTAL PMI.

8B. OR, WITH THE EOR'S APPROVAL, THE GC MAY WORK WITH THE EOR TO RE-ANALYZE THE MODIFICATION/REINFORCEMENT/UPGRADE USING THE AS-BUILT CONDITION.

9. NOTE: IF LOADING IS DIFFERENT THAN THAT SHOWN IN THESE CONSTRUCTION DRAWINGS OR STRUCTURAL/MOUNT MODIFICATION DRAWINGS, CONTRACTOR SHALL NOTIFY THE ENGINEER OF RECORD IMMEDIATELY FOR RESOLUTION.

10. THE ENGINEERING FIRM PERFORMING AN ANALYSIS SHALL PROVIDE A CONTRACTOR'S PHOTO LOG AND CHECKLIST TO BE COMPLETED BY THE INSTALLING CONTRACTOR. THE CONTRACTOR SHALL THEN PROVIDE POST-INSTALLATION INFORMATION TO THE STRUCTURAL ENGINEER. THE STRUCTURAL ENGINEER SHALL REVIEW THE DOCUMENTS FOR ANY DEFICIENCIES THAT CAN BE DETERMINED FROM THE DESKTOP REVIEW OF THE DATA. THE ENGINEERING FIRM SHALL THEN PROVIDE DOCUMENTATION TO VZW THAT THE SITE IS COMPLETED, AND THE PMI REPORT IS APPROVED.

ENGINEER



APPLICANT



118 FLANDERS ROAD
FLOOR 3
WESTBOROUGH, MA 01581


SITE INFORMATION

WOODBIDGE NORTH CT
6 PROGRESS AVENUE
SEYMOUR, CT 06483
TOWN OF SEYMOUR
NEW HAVEN COUNTY

DESIGN RECORD

| REVISIONS | | | |
|-----------|----------|-------------------|-----|
| REV | DATE | DESCRIPTION | BY |
| 4 | 5/16/22 | ANTENNA REVISIONS | DC |
| 3 | 9/22/22 | REVISED PER MA | JM |
| 2 | 03/22/21 | FINAL CDS | RAL |
| 1 | 01/28/21 | FINAL CDS | RAL |
| 0 | 12/15/20 | PRELIMINARY CDS | ALM |
| REV | DATE | DESCRIPTION | BY |

PROFESSIONAL STAMP



ENGINEER

DANIEL J. CORNING, P.E.
CT PROFESSIONAL ENGINEER LIC. #34055

SHEET TITLE

PMI REQUIREMENTS

SHEET NUMBER

GN-1


MX06FRO660-03

NWAV™ X-Pol Hex-Port Antenna

X-Pol Hex-Port 6 ft 60° Fast Roll Off antenna with independent tilt on 700 & 850 MHz:

2 ports 698-798, 824-894 MHz and 4 ports 1695-2180 MHz

- Fast Roll Off (FRO™) azimuth beam pattern improves Intra- and Inter-cell SINR
- Compatible with dual band 700/850 MHz radios with independent low band EDT without external diplexers
- Fully integrated (iRETs) with independent RET control for low and high bands for ease of network optimization
- SON-Ready array spacing supports beamforming capabilities
- Suitable for LTE/CDMA/PCS/UMTS/GSM air interface technologies
- Integrated Smart Bias-Ts reduce leasing costs



NWAV™

Fast Roll-Off antennas increase data throughput without compromising coverage


The horizontal beam produced by Fast Roll-Off (FRO) technology increases the Signal to Interference & Noise Ratio (SINR) by eliminating overlap between sectors.

Non-FRO antenna

Large traditional antenna pattern overlap creates harmful interference.


JMA's FRO antenna pattern minimizes overlap, thereby minimizing interference.

JMA FRO antenna



| LTE throughput | SINR | Speed (bps/Hz) | Speed increase | CQI |
|----------------|-------|----------------|----------------|------|
| Excellent | >18 | >4.5 | 333+% | 8-10 |
| Good | 15-18 | 3.3-4.5 | 277% | 6-7 |
| Fair | 10-15 | 2-3.3 | 160% | 4-6 |
| Poor | <10 | <2 | 0% | 1-3 |


The LTE radio automatically selects the best throughput based on measured SINR.



| Electrical specification (minimum/maximum) | Ports 1, 2 | | Ports 3, 4, 5, 6 | | |
|---|---------------|---------|------------------|-----------|-----------|
| | 698-798 | 824-894 | 1695-1880 | 1850-1990 | 1920-2180 |
| Frequency bands, MHz | 698-798 | 824-894 | 1695-1880 | 1850-1990 | 1920-2180 |
| Polarization | ± 45° | | ± 45° | | |
| Average gain over all tilts, dBi | 14.4 | 14.0 | 17.6 | 18.0 | 18.2 |
| Horizontal beamwidth (HBW), degrees | 60.5 | 53.0 | 55.0 | 55.0 | 55.5 |
| Front-to-back ratio, co-polar power @180°± 30°, dB | >24 | >24.0 | >25.0 | >25.0 | >25.0 |
| X-Pol discrimination (CPR) at boresight, dB | >15.0 | >14.2 | >18 | >18 | >15 |
| Sector power ratio, percent | <3.5 | <3.0 | <3.7 | <3.8 | <3.6 |
| Vertical beamwidth (VBW), degrees ¹ | 13.1 | 11.8 | 6.0 | 5.5 | 5.5 |
| Electrical downtilt (EDT) range, degrees | 2-14 | 2-14 | 0-9 | | |
| First upper side lobe (USLS) suppression, dB ¹ | ≤-15.0 | ≤-16.5 | ≤-16.0 | ≤-16.0 | ≤-16.0 |
| Cross-polar isolation, port-to-port, dB ¹ | 25 | 25 | 25 | 25 | 25 |
| Max VSWR / return loss, dB | 1.5:1 / -14.0 | | 1.5:1 / -14.0 | | |
| Max passive intermodulation (PIM), 2x20W carrier, dBc | -153 | | -153 | | |
| Max input power per any port, watts | 300 | | 250 | | |
| Total composite power all ports, watts | 1500 | | | | |

¹ Typical value over frequency and tilt

| Mechanical specifications | |
|---|-----------------------------------|
| Dimensions height/width/depth, inches (mm) | 71.3/ 15.4/ 10.7 (1811/ 392/ 273) |
| Shipping dimensions length/width/height, inches (mm) | 82/ 20/ 15 (2083/ 508/ 381) |
| No. of RF input ports, connector type, and location | 6 x 4.3-10 female, bottom |
| RF connector torque | 96 lbf-in (10.85 N·m or 8 lbf-ft) |
| Net antenna weight, lb (kg) | 60 (27.0) |
| Shipping weight, lb (kg) | 90 (41.0) |
| Antenna mounting and downtilt kit included with antenna | 91900318 |
| Net weight of the mounting and downtilt kit, lb (kg) | 18 (8.18) |
| Range of mechanical up/down tilt | -2° to 14° |
| Rated wind survival speed, mph (km/h) | 150 (241) |
| Frontal, lateral, and rear wind loading @ 150 km/h, lbf (N) | 154 (685), 73 (325), 158 (703) |
| Equivalent flat plate @ 100 mph and Cd=2, sq ft | 2.6 |



| Ordering information | |
|---|---|
| Antenna model | Description |
| MX06FRO660-03 | 6F X-Pol HEX FRO 60° independent tilt 700/850 RET, 4.3-10 & SBT |
| Optional accessories | |
| AISG cables | M/F cables for AISG connections |
| PCU-1000 RET controller | Stand-alone controller for RET control and configurations |


| Remote electrical tilt (RET 1000) information | |
|---|---|
| RET location | Integrated into antenna |
| RET interface connector type | 8-pin AISG connector per IEC 60130-9 |
| RET connector torque | Min 0.5 N·m to max 1.0 N·m (hand pressure & finger tight) |
| RET interface connector quantity | 2 pairs of AISG male/female connectors |
| RET interface connector location | Bottom of the antenna |
| Total no. of internal RETs (low bands) | 2 |
| Total no. of internal RETs (high bands) | 1 |
| RET input operating voltage, vdc | 10-30 |
| RET max power consumption, idle state, W | ≤ 2.0 |
| RET max power consumption, normal operating conditions, W | ≤ 13.0 |
| RET communication protocol | AISG 2.0 / 3GPP |

RET and RF connector topology

Each RET device can be controlled either via the designated external AISG connector or RF port as shown below:

| RET device | Band | RF port |
|------------|---------|---------|
| R1 | 698-798 | 1-2 |
| R2 | 824-894 | 1-2 |

| RET device | Band | RF port |
|------------|-----------|---------|
| B1/B2 | 1695-2180 | 3-6 |



Array topology


| 3 sets of radiating arrays R1/R2: 698-894 MHz B1: 1695-2180 MHz B2: 1695-2180 MHz | <table border="1"> <thead> <tr> <th>Band</th> <th>RF port</th> </tr> </thead> <tbody> <tr> <td>1695-2180</td> <td>3-4</td> </tr> <tr> <td>698-894</td> <td>1-2</td> </tr> <tr> <td>1695-2180</td> <td>5-6</td> </tr> </tbody> </table> | Band | RF port | 1695-2180 | 3-4 | 698-894 | 1-2 | 1695-2180 | 5-6 | |
|--|--|---------|---------|-----------|-----|---------|-----|-----------|-----|--|
| | Band | RF port | | | | | | | | |
| 1695-2180 | 3-4 | | | | | | | | | |
| 698-894 | 1-2 | | | | | | | | | |
| 1695-2180 | 5-6 | | | | | | | | | |

SAMSUNG C-Band 64T64R Massive MIMO Radio

for High Capacity and Wide Coverage

Samsung C-Band 64T64R Massive MIMO Radio enables mobile operators to increase coverage range, boost data speeds and ultimately offer enriched 5G experiences to users in the U.S..

Model Code : MT6407-77A




Points of Differentiation

Wide Bandwidth

With capability to support up to 2 CC carrier configuration, Samsung C-Band massive MIMO Radio supports 200 MHz bandwidth in the C-Band spectrum.

Samsung C-Band massive MIMO Radio covers the entire C-Band 280 MHz spectrum, so it can meet the operator's needs in current A block and future B/C blocks


C-Band spectrum supported by Massive MIMO Radio



Future Proof Product

Samsung C-Band 64T64R Massive MIMO radio supports not only CPRI but also eCPRI as front-haul interface.

It enables operators can cut down on OPEX/CAPEX by reducing front-haul bandwidth through low layer split and using ethernet based higher efficient line.




Enhanced Performance

C-Band massive MIMO Radio creates sharp beams and extends networks' coverage on the critical mid-band spectrum using a large number of antenna elements and high output power to boost data speeds.

This helps operators reduce their CAPEX as they now need less products to cover the same area than before.


Furthermore, as C-Band massive MIMO Radio supports MU-MIMO (Multi-user MIMO), it enables to increase user throughput by minimizing interference.



Well Matched Design

Samsung C-Band Massive MIMO radio utilizes 64 antennas, supports up to 280MHz bandwidth, and delivers a 200W output power. Despite the above advanced performance, the Radio has a compact size of 50.9L and 79.4lbs. This makes it easy to install the Radio.

It is designed to look solid and compact, with a low profile appearance so that, when installed, harmonizes well with the surrounding environment.



Technical Specifications

| Item | Specification |
|----------------|---|
| Tech | NR |
| Band | n77 |
| Frequency Band | 3700 - 3980 MHz |
| EIRP | 78.5dBm (53.0 dBm+25.5 dBi) |
| IBW/OBW | 280 MHz / 200 MHz |
| Installation | Pole/Wall |
| Size/Weight | 16.06 x 35.06 x 5.51 inch (50.86L) / 79.4 lbs |



SAMSUNG



About Samsung Electronics Co., Ltd.

Samsung inspires the world and shapes the future with transformative ideas and technologies. The company is redefining the worlds of TVs, smartphones, wearable devices, tablets, digital appliances, network systems, and memory, system LSI, foundry and LED solutions.

129 Samsung-ro, Yeongtong-gu, Suwon-si Gyeonggi-do, Korea

© 2021 Samsung Electronics Co., Ltd.

All rights reserved. Information in this leaflet is proprietary to Samsung Electronics Co., Ltd. and is subject to change without notice. No information contained here may be copied, translated, transcribed or duplicated by any form without the prior written consent of Samsung Electronics.

SAMSUNG

Dual-Band Radio Unit AWS/PCS (B66/B2)

RFV01U-D1A

Samsung's RFV01U-D1A is a compact remote Radio Unit (RU) designed for deployments that require flexibility in installation and rapid onlining, without compromising on coverage, capacity or operational expenses.



The RFV01U-D1A RU targets dual-band support across Band 66 (AWS) and Band 2 (PCS), making it an ideal product for broad coverage footprints across multiple common mid-range frequencies.

The RU handles all Radio Frequency (RF) processing in a single, compact unit, and is designed to interface via CPRI with Samsung's CDU baseband offerings, in both distributed- and central-RAN configurations.

In addition to its minimal footprint and ease of installation, the RU is also designed to reduce cost of ownership through its integrated spectrum analyzer, which allows for remote RF monitoring, greatly reducing the need for on-site maintenance visits.

Features and Benefits

- Dual-band support for broad frequency coverage
- Minimal footprint reduces site costs
- Rapid, easy installation
- Flexibly deployable in any location
- Remote RF monitoring capability
- Convection cooled, silent operation
- Built-in Broadcast Auxiliary Services (BAS) filter ensures compliant AWS operation without impacting footprint

Key Technical Specifications

Duplex Type: FDD

Operating Frequencies:

B66: DL(2,110-2,180MHz)/UL(1,710-1,780MHz)

B2: DL(1,930-1,990MHz)/UL(1,850-1,910MHz)

Instantaneous Bandwidth:

70MHz(B66) + 60MHz(B2)

RF Chain: 4T4R/2T4R/2T2R

Output Power: Total 320W

DU-RU Interface: CPRI (10Gbps)

Dimensions: 380 x 380 x 255mm (36.8L)

Weight: 38.3kg

Input Power: -48V DC

Operating Temp.: -40 - 55°(w/o solar load)

Cooling: Natural convection

SAMSUNG

Dual-Band Radio Unit 700/850MHz (B13/B5) RFV01U-D2A

Samsung's RFV01U-D2A is a compact remote Radio Unit (RU) designed for deployments that require flexibility in installation and rapid onlining, without compromising on coverage, capacity or operational expenses.



The RFV01U-D2A RU targets dual-band support across Band 13 (700MHz) and Band 5 (850MHz), making it an ideal product for broad coverage footprints across multiple common low-end, long-range frequencies.

The RU handles all Radio Frequency (RF) processing in a single, compact unit, and is designed to interface via CPRI with Samsung's CDU baseband offerings, in both distributed- and central-RAN configurations.

In addition to its minimal footprint and ease of installation, the RU is also designed to reduce cost of ownership through its integrated spectrum analyzer, which allows for remote RF monitoring, greatly reducing the need for on-site maintenance visits.

Features and Benefits

- Dual-band support for broad frequency coverage
- Minimal footprint reduces site costs
- Rapid, easy installation
- Flexibly deployable in any location
- Remote RF monitoring capability
- Convection cooled, silent operation

Key Technical Specifications

Duplex Type: FDD
Operating Frequencies:
B13: DL(746-756MHz)/UL(777-787MHz)
B5: DL(869-894MHz)/UL(824-849MHz)
Instantaneous Bandwidth: 10MHz(B13) + 25MHz(B5)
RF Chain: 4T4R/2T4R/2T2R
Output Power: Total 320W
DU-RU Interface: CPRI (10Gbps)
Dimensions: 380 x 380 x 207mm (29.9L)
Weight: 31.9kg
Input Power: -48V DC
Operating Temp.: -40 - 55°(w/o solar load)
Cooling: Natural convection

ATTACHMENT 3

| | General | Power | Density | | | | | |
|--------------------------------------|------------|--------------|------------|------------------|--------------|--------------------|--------------|---------------|
| Site Name: Wethersfield 3 | | | | | | | | |
| Tower Height: Verizon @ 130ft | | | | | | | | |
| CARRIER | # OF CHAN. | WATTS ERP | HEIGHT | CALC. POWER DENS | FREQ. | MAX. PERMISS. EXP. | FRACTION MPE | Total |
| AT&T-UMTS | 2 | 419 | 160 | 850 | 0.0127 | 0.5667 | 0.22% | |
| AT&T-UMTS | 4 | 487 | 160 | 700 | 0.0295 | 0.4667 | 0.63% | |
| AT&T-UMTS | 2 | 546 | 160 | 850 | 0.0166 | 0.5667 | 0.29% | |
| AT&T-PCS-UMTS | 4 | 917 | 160 | 2300 | 0.0556 | 1.0000 | 0.56% | |
| AT&T-GSM | 4 | 971 | 160 | 1900 | 0.0589 | 1.0000 | 0.59% | |
| AT&T-WCS-LTE | 2 | 341 | 160 | 850 | 0.0103 | 0.5667 | 0.18% | |
| AT&T-PCS-LTE | 2 | 627 | 160 | 700 | 0.0190 | 0.4667 | 0.41% | |
| AT&T-LTE | 4 | 960 | 160 | 2100 | 0.0582 | 1.0000 | 0.58% | |
| T-Mobile | 1 | 584 | 247 | 1900 | 0.0036 | 1.0000 | 0.04% | |
| T-Mobile | 2 | 1556 | 247 | 1900 | 0.0193 | 1.0000 | 0.19% | |
| T-Mobile | 2 | 2334 | 247 | 2100 | 0.0289 | 1.0000 | 0.29% | |
| T-Mobile | 2 | 2524 | 247 | 2500 | 0.0313 | 1.0000 | 0.31% | |
| T-Mobile | 2 | 2524 | 247 | 2500 | 0.0313 | 1.0000 | 0.31% | |
| T-Mobile | 2 | 789 | 247 | 600 | 0.0098 | 0.4000 | 0.24% | |
| T-Mobile | 2 | 433 | 247 | 700 | 0.0054 | 0.4667 | 0.11% | |
| T-Mobile | 2 | 1469 | 247 | 1900 | 0.0182 | 1.0000 | 0.18% | |
| Sprint | 3 | 693 | 170 | 1900 | 0.0278 | 1.0000 | 0.28% | |
| Sprint | 1 | 390 | 170 | 850 | 0.0052 | 0.5667 | 0.09% | |
| Sprint | 2 | 693 | 170 | 2500 | 0.0185 | 1.0000 | 0.19% | |
| Mike Gardella | 12 | 110 | 280 | 1980 | 0.0063 | 1.0000 | 0.06% | |
| Town | 12 | 80 | 235 | 155 | 0.0066 | 0.2000 | 0.33% | |
| VZW 700 | 4 | 623 | 140 | 0.0046 | 746 | 0.4973 | 0.92% | |
| VZW CDMA | 2 | 500 | 140 | 0.0018 | 869 | 0.5793 | 0.32% | |
| VZW Cellular | 4 | 623 | 140 | 0.0046 | 880 | 0.5867 | 0.78% | |
| VZW PCS | 4 | 1428 | 140 | 0.0105 | 1,970 | 1.0000 | 1.05% | |
| VZW AWS | 4 | 1530 | 140 | 0.0112 | 2,145 | 1.0000 | 1.12% | |
| VZW CBAND | 1 | 26002 | 140 | 0.0477 | 3,700 | 1.0000 | 4.77% | |
| | | | | | | | | 15.06% |
| * Source: Siting Council | | | | | | | | |

ATTACHMENT 4

Date: **May 18, 2022**

Andrew Leone
Verizon Wireless
Construction Manager
118 Flanders Rd, Third Floor
Westborough, MA 01581

NB+C Engineering Services
100 Apollo Drive
Suite 303
Chelmsford, MA 01824

Subject: **Structural Analysis Report**

Carrier Designation: **Verizon 5G L-Sub6 – Carrier Add**
Verizon Site ID: 1126653
Verizon Site Name: Woodbridge North CT

NB+C ES Designation: **Project Number:** 100765

Site Data: **6 Progress Ave., Seymour, CT 06483, New Haven County**
Latitude 41° 23' 29.50", Longitude -73° 03' 12.00"
280.0 Foot – Self Supporting Tower

Dear Mr. Leone,

Network Building + Consulting Engineering Services (“NB+C ES”) is pleased to submit this **“Structural Analysis Report”** to determine the structural integrity of the above-mentioned tower.

The purpose of the analysis is to determine acceptability of the tower stress level. Based on our analysis we have determined the tower stress level for the structure under the following load case, to be:

Existing + Proposed Equipment

Sufficient Capacity: 65.4%

Note: See Table 1 for the proposed final loading.

The analysis has been performed in accordance with the *ANSI/TIA-222-G Structural Standard for Antenna Supporting Structures and Antennas, 2018 Connecticut State Building Code*, and local code requirements based upon an ultimate 3-second gust wind speed of 125 mph.

All equipment proposed in this report shall be installed in accordance with the referenced documents for the determined available structural capacity to be effective.

We at **NB+C Engineering Services** appreciate the opportunity of providing our continuing professional services to Verizon. If you have any questions or need further assistance on this or any other projects please give us a call.

NB+C ENGINEERING SERVICES, LLC

Structural Analysis prepared by: Nick Smith, P.E.

Respectfully submitted by:

Krupakaran Kolandaivelu, P.E.

Associate Director, Chief Engineer - Structural
CT PE License #PEN.0028997



5/18/2022

TABLE OF CONTENTS

1) INTRODUCTION

2) ANALYSIS CRITERIA

Table 1 - Final Equipment Information

3) ANALYSIS PROCEDURE

3.1) Analysis Method

3.2) Assumptions

4) ANALYSIS RESULTS

Table 2 - Tower Section Capacity (Summary)

Table 3 - Foundation Analysis Results

4.1) Recommendations

5) APPENDIX A

tnxTower Output & Additional Calculations

1) INTRODUCTION

This tower is a 280.0 ft self supporting tower located in New Haven County, CT. The tower geometry and existing equipment was based on data available from the structural analysis report by Destek Engineering.

Information **NB+C ES** has received for this analysis includes:

- Previous Structural Analysis Report prepared by Destek Engineering (Job No. 1975056) dated May 28, 2019
- RFDS sheet provided by Verizon dated November 17, 2020
- Mount Analysis Report prepared by Maser Consulting dated April 12, 2022

2) ANALYSIS CRITERIA

| | |
|----------------------------|---|
| TIA-222 Revision: | TIA-222-G |
| Building Code: | 2018 Connecticut State Building Code (2015 IBC) |
| Risk Category: | II |
| Wind Speed: | 125 mph |
| Exposure Category: | B |
| Topographic Factor: | 1 |
| Ice Thickness: | 0.75 in |
| Ice Wind Speed: | 50 mph |
| Service Wind Speed: | 60 mph |
| Seismic Ss: | 0.192 |
| Seismic S1: | 0.064 |

Table 1 - Final Equipment Information

| Mounting Level (ft) | Center Line Elevation (ft) | Qty | Antenna Manufacturer | Antenna Model | Qty | Feed Line Size (in) | Carrier |
|---------------------|----------------------------|-----|----------------------|----------------------------|-----|--------------------------|----------|
| 280.0 | 280.0 | 1 | Decibel | DB420-A | 4 | 1 5/8 | Unknown |
| | | 1 | Decibel | DB586-XC | | | |
| | | 1 | - | 22-ft Halo Mount | | | |
| 250.0 | 250.0 | 3 | Ericsson | AIR32 B66A B2A | 9 | 1 5/8 6x12 HCS | T-Mobile |
| | | 3 | RFS | APXVAARR24 43-U-NA20 | | | |
| | | 3 | Ericsson | AIR 6488 B41 | | | |
| | | 3 | Ericsson | Radio 4449 B71/B12 | 3 | | |
| | | 3 | Ericsson | Radio 4415 B25 | | | |
| | | 3 | - | 15-ft T-Frame Sector Mount | | | |
| 235.0 | 245.0 | 1 | Decibel | DB420-A | - | - | Unknown |
| | 235.0 | 1 | Decibel | DB225-2-F | | | |
| | | 1 | - | 22-ft Halo Mount | | | |
| 200.0 | 200.0 | 9 | Decibel | DB980H120E-M | 9 | 1 5/8 | Unknown |
| | | 3 | - | 10-ft T-Frame Sector Mount | | | |
| 190.0 | 190.0 | 9 | Decibel | DB980H120E-M | 9 | 1 5/8 | Unknown |
| | | 3 | - | 10-ft T-Frame Sector Mount | | | |
| 180.0 | 180.0 | 9 | Decibel | DB980H120E-M | 9 | 1 5/8 | Unknown |
| | | 3 | - | 10-ft T-Frame Sector Mount | | | |
| 170.0 | 170.0 | 3 | RFS | APXVSPP18-C-A20 | 3 | 1 5/8 1 1/4 Hybriflex | Unknown |
| | | 3 | RFS | APXVTM14-C-120 | | | |
| | | 3 | Alcatel Lucent | FD-RRH-2x50-800 | | | |
| | | 3 | Alcatel Lucent | FD-RRH-4x40-1900 | 1 | | |
| | | 3 | Alcatel Lucent | TD-RRH8x20-25 | | | |
| | | 3 | - | 15-ft T-Frame Sector Mount | | | |

Table 1 - Final Antenna and Cable Information

| Mounting Level (ft) | Center Line Elevation (ft) | Qty | Antenna Manufacturer | Antenna Model | Qty | Feed Line Size (in) | Carrier |
|---------------------|----------------------------|----------|----------------------|-------------------------------------|-------------|----------------------|---------|
| 160.0 | 160.0 | 3 | Kathrein | 800 10121 | 6 1 2 | 1 5/8 Fiber DC | Unknown |
| | | 3 | CCI | HPA65R-BU6A | | | |
| | | 3 | Quintel | QS66512-3 | | | |
| | | 3 | Ericsson | RRUS 11 | | | |
| | | 3 | Ericsson | RRUS 32 | | | |
| | | 3 | Ericsson | RRUS 32 B2 | | | |
| | | 3 | Ericsson | RRUS 4478 B5 | | | |
| | | 3 | Ericsson | RRUS 4478 B14 | | | |
| | | 3 | Ericsson | RRUS 4426 B66 | | | |
| | | 6 | Powerwave | LGP21401 | | | |
| | | 3 | Raycap | DC6-48-60-18-8F | | | |
| | | 3 | - | 15-ft T-Frame Sector Mount | | | |
| 150.0 | 150.0 | 3 | RFS | APXV18-206517S-C | 6 | 1 5/8 | Unknown |
| | | 3 | - | 12.5-ft Sector Mount | | | |
| 140.0 | 140.0 | 6 | JMA | MX06FRO660-03 | 12 2 | 1 5/8 6x12 | Verizon |
| | | 3 | Samsung | MT6407-77A | | | |
| | | 3 | Samsung | B2/B66A RRH-BR049 RFV01U-D1A | | | |
| | | 3 | Samsung | B5/B13 RRH-BR04C RFV01U-D2A | | | |
| | | 6 | Antel | LPA-80063/6CF | | | |
| | | 2 | Raycap | RRFDC-3315-PF-48 | | | |
| | | 3 | - | 12-ft T-Frame Sector Mount | | | |

Notes:

- 1) Proposed equipment is shown in **bold** print.

3) ANALYSIS PROCEDURE

3.1) Analysis Method

tnxTower (version 8.0.7.5), a commercially available analysis software package, was used to create a three-dimensional model of the tower and calculate member stresses for various loading cases. Selected output from the analysis is included in the Appendix A.

3.2) Assumptions

This report is based on the theoretical capacity of the existing tower structure and is not an assessment of the overall suitability of the existing tower structure or its components for any particular use other than specified in this report:

- 1) Tower and structures were built in accordance with the manufacturer's specifications.
- 2) The tower and structures have been maintained in accordance with the manufacturer's specification.
- 3) The configuration of antennas, transmission cables, mounts and other appurtenances are as specified in Table 1 and the referenced drawings.
- 4) Tower geometry, existing equipment, and foundation information were obtained from previous structural analysis by Destek Engineering (Job No. 1975056) dated May 28, 2019. If any of this information is inaccurate then the results from analysis are invalid.

This analysis may be affected if any assumptions are not valid or have been made in error. **NB+C Engineering Services** should be notified to determine the effect on the structural integrity of the tower.

4) ANALYSIS RESULTS

Table 2 - Tower Section Capacity (Summary)

| Section No. | Elevation ft | Component Type | Size | Critical Element | P K | ϕP_{allow} K | % Capacity | Pass Fail |
|-------------|--------------|----------------|--------------------|------------------|---------|--------------------|------------------|-----------|
| T1 | 280 - 270 | Leg | 1 3/4 | 2 | -7.89 | 81.93 | 9.6 | Pass |
| T2 | 270 - 250 | Leg | 2 | 41 | -26.93 | 111.48 | 24.2 | Pass |
| T3 | 250 - 230 | Leg | 2 1/2 | 107 | -70.35 | 189.74 | 37.1 | Pass |
| T4 | 230 - 220 | Leg | Pirod 105245 | 171 | -77.36 | 214.86 | 36.0 | Pass |
| T5 | 220 - 200 | Leg | Pirod 105218 | 179 | -105.20 | 300.68 | 35.0 | Pass |
| T6 | 200 - 180 | Leg | Pirod 105218 | 194 | -132.58 | 300.68 | 44.1 | Pass |
| T7 | 180 - 160 | Leg | Pirod 105219 | 215 | -168.13 | 399.87 | 42.0 | Pass |
| T8 | 160 - 140 | Leg | Pirod 105220 | 236 | -214.15 | 512.38 | 41.8 | Pass |
| T9 | 140 - 120 | Leg | Pirod 105220 | 254 | -261.94 | 512.38 | 51.1 | Pass |
| T10 | 120 - 100 | Leg | Pirod 112743 | 269 | -292.10 | 613.14 | 47.6 | Pass |
| T11 | 100 - 80 | Leg | Pirod 112743 | 278 | -339.87 | 613.14 | 55.4 | Pass |
| T12 | 80 - 60 | Leg | Pirod 112744 | 287 | -383.56 | 741.99 | 51.7 | Pass |
| T13 | 60 - 40 | Leg | Pirod 112744 | 296 | -424.45 | 741.99 | 57.2 | Pass |
| T14 | 40 - 20 | Leg | Pirod 112745 | 306 | -468.65 | 883.14 | 53.1 | Pass |
| T15 | 20 - 0 | Leg | Pirod 112740 | 315 | -503.75 | 883.14 | 57.0 | Pass |
| T1 | 280 - 270 | Diagonal | 7/8 | 14 | -1.75 | 7.87 | 22.2 | Pass |
| T2 | 270 - 250 | Diagonal | 7/8 | 52 | -2.30 | 7.79 | 29.5 | Pass |
| T3 | 250 - 230 | Diagonal | 1 | 116 | -5.02 | 13.51 | 37.1 | Pass |
| T4 | 230 - 220 | Diagonal | L2 1/2x2 1/2x3/16 | 174 | -5.48 | 13.38 | 40.9 52.7 (b) | Pass |
| T5 | 220 - 200 | Diagonal | L3x3x3/16 | 183 | -5.18 | 17.29 | 29.9 48.5 (b) | Pass |
| T6 | 200 - 180 | Diagonal | L3x3x3/16 | 204 | -7.67 | 14.78 | 51.9 65.4 (b) | Pass |
| T7 | 180 - 160 | Diagonal | L3x3x5/16 | 225 | -9.87 | 19.26 | 51.2 | Pass |
| T8 | 160 - 140 | Diagonal | L3 1/2x3 1/2x5/16 | 243 | -9.91 | 25.06 | 39.5 48.3 (b) | Pass |
| T9 | 140 - 120 | Diagonal | L3 1/2x3 1/2x5/16 | 258 | -10.98 | 20.49 | 53.6 55.6 (b) | Pass |
| T10 | 120 - 100 | Diagonal | 2L3 1/2x3 1/2x5/16 | 275 | -16.95 | 52.58 | 32.2 | Pass |
| T11 | 100 - 80 | Diagonal | 2L3 1/2x3 1/2x5/16 | 282 | -16.78 | 48.27 | 34.8 | Pass |
| T12 | 80 - 60 | Diagonal | 2L3 1/2x3 1/2x5/16 | 291 | -16.42 | 44.30 | 37.1 | Pass |
| T13 | 60 - 40 | Diagonal | 2L3 1/2x3 1/2x5/16 | 302 | -17.58 | 40.67 | 43.2 | Pass |
| T14 | 40 - 20 | Diagonal | 2L3 1/2x3 1/2x5/16 | 309 | -16.05 | 37.36 | 43.0 | Pass |
| T15 | 20 - 0 | Diagonal | 2L3 1/2x3 1/2x5/16 | 320 | -20.04 | 34.37 | 58.3 | Pass |
| T1 | 280 - 270 | Horizontal | 7/8 | 32 | -0.17 | 3.91 | 4.4 | Pass |
| T2 | 270 - 250 | Horizontal | 7/8 | 98 | -0.33 | 3.94 | 8.3 | Pass |
| T3 | 250 - 230 | Horizontal | 7/8 | 162 | -0.61 | 4.01 | 15.1 | Pass |
| T1 | 280 - 270 | Top Girt | 1 | 5 | -0.71 | 6.67 | 10.7 | Pass |
| T2 | 270 - 250 | Top Girt | 1 | 43 | -0.80 | 6.73 | 11.8 | Pass |
| T3 | 250 - 230 | Top Girt | 1 1/4 | 109 | -1.46 | 16.71 | 8.7 | Pass |
| T6 | 200 - 180 | Top Girt | L3x3x3/16 | 198 | -2.71 | 13.65 | 19.8 33.4 (b) | Pass |
| T7 | 180 - 160 | Top Girt | L4x4x1/4 | 219 | -4.13 | 25.75 | 16.0 32.3 (b) | Pass |
| T8 | 160 - 140 | Top Girt | L3 1/2x3 1/2x5/16 | 240 | -3.39 | 13.88 | 24.4 | Pass |
| T1 | 280 - 270 | Bottom Girt | 1 | 9 | -0.68 | 6.67 | 10.2 | Pass |
| T2 | 270 - 250 | Bottom Girt | 1 | 45 | -0.90 | 6.73 | 13.3 | Pass |
| T3 | 250 - 230 | Bottom Girt | 1 1/4 | 111 | -0.92 | 16.71 | 5.5 | Pass |
| T1 | 280 - 270 | Mid Girt | 1 | 10 | 0.13 | 35.34 | 0.4 | Pass |
| T2 | 270 - 250 | Mid Girt | 1 | 48 | -0.18 | 6.73 | 2.7 | Pass |
| T6 | 200 - 180 | Mid Girt | L3x3x3/16 | 201 | -3.19 | 10.33 | 30.8 40.9 (b) | Pass |
| T7 | 180 - 160 | Mid Girt | L4x4x1/4 | 222 | -4.32 | 20.85 | 20.7 34.2 (b) | Pass |
| | | | | | | | Summary | |
| | | | | | | | Leg (T13) | Pass |
| | | | | | | | Diagonal (T6) | Pass |
| | | | | | | | Horizontal (T3) | Pass |
| | | | | | | | Top Girt (T6) | Pass |

| Section No. | Elevation ft | Component Type | Size | Critical Element | P K | ϕP_{allow} K | % Capacity | Pass Fail |
|-------------|--------------|----------------|------|------------------|-----|--------------------|-------------|-------------|
| | | | | | | Bottom Girt (T2) | 13.3 | Pass |
| | | | | | | Mid Girt (T6) | 40.9 | Pass |
| | | | | | | Bolt Checks | 65.4 | Pass |
| | | | | | | RATING = | 65.4 | Pass |

Notes:

- 1) See additional documentation in "Appendix A - tnxTower Output & Additional Calculations" for calculations supporting the % capacity consumed.

Table 3 – Foundation Analysis Results

| Component | Elevation (ft) | % Capacity | Pass/Fail |
|-------------------------------|----------------|------------|-----------|
| Anchor Rods | - | 34.8 | Pass |
| Foundation – Soil Interaction | - | 57.8 | Pass |
| Foundation - Structural | - | 28.8 | Pass |

| | |
|---|--------------|
| Structure Rating (max from all components) = | 65.4% |
|---|--------------|


4.1) Recommendations

- The tower has sufficient capacity to support the proposed loading configuration. Modifications are not required at this time. The foundation is assumed to be accurate based of a reaction comparison using design results obtained from the previous structural analysis prepared by Destek Engineering (Job No. 1975056) dated May 28, 2019. If foundation design data is unavailable, it is recommended that a subsurface investigation take place in order to obtain a structural capacity for the foundation.

APPENDIX A

TNXTOWER OUTPUT & ADDITIONAL CALCULATIONS

| | | | | | | | | | | | | | | | | | | | | | |
|-----------------|----------|------|---------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Section | T1 | T2 | T3 | T4 | T5 | T6 | T7 | T8 | T9 | T10 | T11 | T12 | T13 | T14 | T15 | T16 | T17 | T18 | T19 | T20 | T21 |
| Legs | SR 1.34 | SR 2 | SR 2.12 | Prod 105945 | Prod 105918 | Prod 105919 | Prod 105920 | Prod 112743 | Prod 112744 | Prod 112745 | Prod 112746 | Prod 112747 | Prod 112748 | Prod 112749 | Prod 112750 | Prod 112751 | Prod 112752 | Prod 112753 | Prod 112754 | Prod 112755 | Prod 112756 |
| Long Chords | | | | | | | | | | | | | | | | | | | | | |
| Diagonals | | | | | | | | | | | | | | | | | | | | | |
| Diagonal Grade | | | | | | | | | | | | | | | | | | | | | |
| Top Girts | | | | | | | | | | | | | | | | | | | | | |
| Mid Girts | | | | | | | | | | | | | | | | | | | | | |
| Bottom Girts | | | | | | | | | | | | | | | | | | | | | |
| Horizontals | | | | | | | | | | | | | | | | | | | | | |
| Face Width (ft) | 5 | | | | | | | | | | | | | | | | | | | | |
| # Panels @ (ft) | 4 @ 2.25 | | | | | | | | | | | | | | | | | | | | |
| Weight (K) | 0.7 | | | | | | | | | | | | | | | | | | | | |



DESIGNED APPURTENANCE LOADING

| TYPE | ELEVATION | TYPE | ELEVATION |
|-----------------------------------|-----------|---------------------------------|-----------|
| Beacon | 280 | 800 10121 w/ Mount Pipe | 160 |
| Lightning Rod 5/8x6' | 280 | HPA65R-BUBAw/ Mount Pipe | 160 |
| DE420-A | 280 | HPA65R-BUBAw/ Mount Pipe | 160 |
| DE586-XC | 280 | HPA65R-BUBAw/ Mount Pipe | 160 |
| Sector Mount [SM 412-1] | 280 | CS66512-3 w/ Mount Pipe | 160 |
| APXWARR24_43-U-NA20 w/ Mount Pipe | 250 | CS66512-3 w/ Mount Pipe | 160 |
| APXWARR24_43-U-NA20 w/ Mount Pipe | 250 | CS66512-3 w/ Mount Pipe | 160 |
| APXWARR24_43-U-NA20 w/ Mount Pipe | 250 | RRUS 11 | 160 |
| AIR 32 B66A12Aw/ Mount Pipe | 250 | RRUS 11 | 160 |
| AIR 32 B66A12Aw/ Mount Pipe | 250 | RRUS 11 | 160 |
| AIR 32 B66A12Aw/ Mount Pipe | 250 | RRUS 32 | 160 |
| AIR 6468 B41 w/ Mount Pipe | 250 | RRUS 32 | 160 |
| AIR 6468 B41 w/ Mount Pipe | 250 | RRUS 32 | 160 |
| AIR 6468 B41 w/ Mount Pipe | 250 | RRUS 32 B2 | 160 |
| RADIO 4449 B12/B71 | 250 | RRUS 32 B2 | 160 |
| RADIO 4449 B12/B71 | 250 | RRUS 32 B2 | 160 |
| RADIO 4449 B12/B71 | 250 | RRUS 4478 B5 | 160 |
| RADIO 4415 B25 | 250 | RRUS 4478 B5 | 160 |
| RADIO 4415 B25 | 250 | RRUS 4478 B14 | 160 |
| RADIO 4415 B25 | 250 | RRUS 4478 B14 | 160 |
| Sector Mount [SM 408-3] | 250 | RRUS 4478 B14 | 160 |
| Sector Mount [SM 412-1] | 235 | RRUS 4478 B14 | 160 |
| DE420-A | 235 | RRUS 4426 B66 | 160 |
| DE586-XC | 235 | RRUS 4426 B66 | 160 |
| (3) DE890H120E-M w/ Mount Pipe | 200 | RRUS 4426 B66 | 160 |
| (3) DE890H120E-M w/ Mount Pipe | 200 | (2) LGP21401 | 160 |
| (3) DE890H120E-M w/ Mount Pipe | 200 | (2) LGP21401 | 160 |
| Sector Mount [SM 405-3] | 200 | (2) LGP21401 | 160 |
| (3) DE890H120E-M w/ Mount Pipe | 190 | DC6-48-60-18-8F | 160 |
| (3) DE890H120E-M w/ Mount Pipe | 190 | DC6-48-60-18-8F | 160 |
| (3) DE890H120E-M w/ Mount Pipe | 190 | DC6-48-60-18-8F | 160 |
| Sector Mount [SM 405-3] | 190 | Sector Mount [SM 408-3] | 160 |
| (3) DE890H120E-M w/ Mount Pipe | 180 | APXV18 206517S-C w/ Mount Pipe | 150 |
| (3) DE890H120E-M w/ Mount Pipe | 180 | APXV18 206517S-C w/ Mount Pipe | 150 |
| (3) DE890H120E-M w/ Mount Pipe | 180 | APXV18 206517S-C w/ Mount Pipe | 150 |
| Sector Mount [SM 405-3] | 180 | Sector Mount [SM 405-3] | 150 |
| APXVSP18-C-A20 w/ Mount Pipe | 170 | (2) MX06FRO660-03 w/ Mount Pipe | 140 |
| APXVSP18-C-A20 w/ Mount Pipe | 170 | (2) MX06FRO660-03 w/ Mount Pipe | 140 |
| APXVSP18-C-A20 w/ Mount Pipe | 170 | (2) MX06FRO660-03 w/ Mount Pipe | 140 |
| APXVTM14-C-120 w/ Mount Pipe | 170 | L-Sub6 Antenna w/ Mount Pipe | 140 |
| APXVTM14-C-120 w/ Mount Pipe | 170 | L-Sub6 Antenna w/ Mount Pipe | 140 |
| APXVTM14-C-120 w/ Mount Pipe | 170 | L-Sub6 Antenna w/ Mount Pipe | 140 |
| FD-RRH-2x50-800 | 170 | RFV01U-D1A | 140 |
| FD-RRH-2x50-800 | 170 | RFV01U-D1A | 140 |
| FD-RRH-2x50-800 | 170 | RFV01U-D1A | 140 |
| 1900MHZ 4X43W RRH | 170 | RFV01U-D2A | 140 |
| 1900MHZ 4X43W RRH | 170 | RFV01U-D2A | 140 |
| 1900MHZ 4X43W RRH | 170 | RFV01U-D2A | 140 |
| TD-RRH-RX20-25 | 170 | (2) LPA-800636CF w/ Mount Pipe | 140 |
| TD-RRH-RX20-25 | 170 | (2) LPA-800636CF w/ Mount Pipe | 140 |
| TD-RRH-RX20-25 | 170 | (2) LPA-800636CF w/ Mount Pipe | 140 |
| Sector Mount [SM 408-3] | 170 | RxdC-3315-PF-48 | 140 |
| 800 10121 w/ Mount Pipe | 160 | RxdC-3315-PF-48 | 140 |
| 800 10121 w/ Mount Pipe | 160 | Sector Mount [SM 406-3] | 140 |

SYMBOL LIST

| MARK | SIZE | MARK | SIZE |
|------|-------------------|------|------|
| A | L2 1/2x2 1/2x3/16 | | |

MATERIAL STRENGTH

| GRADE | Fy | Fu | GRADE | Fy | Fu |
|---------|--------|--------|-------|--------|--------|
| A572-50 | 50 ksi | 65 ksi | A36 | 36 ksi | 58 ksi |


TOWER DESIGN NOTES

1. Tower designed for Exposure B to the TIA-222-G Standard.
2. Tower designed for a 97 mph basic wind in accordance with the TIA-222-G Standard.
3. Tower is also designed for a 50 mph basic wind with 0.75 in ice. Ice is considered to increase in thickness with height.
4. Deflections are based upon a 60 mph wind.
5. Tower Structure Class II.
6. Topographic Category 1 with Crest Height of 0.00 ft
7. Antenna elevations shown above are for mount elevations; differences between mount elevations and antennas have been accounted for using vertical options in the program columns in the report.
8. TOWER RATING: 65.4%


ALL REACTIONS ARE FACTORED

MAX. CORNER REACTIONS AT BASE:
DOWN: 526 K
SHEAR: 55 K

UPLIFT: -437 K
SHEAR: 47 K



TORQUE 13 kip-ft
50 mph WIND - 0.7500 in ICE



TORQUE 45 kip-ft
REACTIONS - 97 mph WIND

| | | | |
|---|---|--|--|
| <p>Network Building + Consulting 8601 Six Forks Road, Suite 540 Raleigh, NC 27615 Phone: 919.657.9131 FAX:</p> | <p>Project: Woodbridge North CT NB-C ES Project Number 100765</p> | | |
| | <p>Client: Verizon Code: TIA-222-G Path:</p> | <p>Drawn by: nsmith Date: 12/14/20</p> | <p>App'd: Scale: NTS Dwg No: E-1</p> |

| | | |
|---|---|----------------------------------|
| tnxTower Network Building + Consulting 8601 Six Forks Road, Suite 540 Raleigh, NC 27615 Phone: 919.657.9131 FAX: | Job Woodbridge North CT | Page 1 of 52 |
| | Project NB+C ES Project Number 100765 | Date 14:34:37 12/14/20 |
| | Client Verizon | Designed by nsmith |

Tower Input Data

The main tower is a 3x free standing tower with an overall height of 280.00 ft above the ground line.

The base of the tower is set at an elevation of 0.00 ft above the ground line.

The face width of the tower is 5.00 ft at the top and 28.00 ft at the base.

This tower is designed using the TIA-222-G standard.

The following design criteria apply:

ASCE 7-10 Wind Data is used (wind speeds converted to nominal values).

Basic wind speed of 97 mph.

Structure Class II.

Exposure Category B.

Topographic Category 1.

Crest Height 0.00 ft.

Nominal ice thickness of 0.7500 in.

Ice thickness is considered to increase with height.

Ice density of 56 pcf.

A wind speed of 50 mph is used in combination with ice.

Temperature drop of 50 °F.

Deflections calculated using a wind speed of 60 mph.

Antenna elevations shown above are for mount elevations; differences between mount elevations and antennas have been accounted for using vertical options in the program columns in the report..

A non-linear (P-delta) analysis was used.

Pressures are calculated at each section.

Stress ratio used in tower member design is 1.

Local bending stresses due to climbing loads, feed line supports, and appurtenance mounts are not considered.

Options

| | | |
|--|---|---|
| <ul style="list-style-type: none"> Consider Moments - Legs Consider Moments - Horizontals Consider Moments - Diagonals Use Moment Magnification √ Use Code Stress Ratios √ Use Code Safety Factors - Guys Escalate Ice Always Use Max Kz Use Special Wind Profile √ Include Bolts In Member Capacity Leg Bolts Are At Top Of Section √ Secondary Horizontal Braces Leg Use Diamond Inner Bracing (4 Sided) √ SR Members Have Cut Ends SR Members Are Concentric | <ul style="list-style-type: none"> Distribute Leg Loads As Uniform Assume Legs Pinned √ Assume Rigid Index Plate √ Use Clear Spans For Wind Area √ Use Clear Spans For KL/r Retension Guys To Initial Tension √ Bypass Mast Stability Checks √ Use Azimuth Dish Coefficients √ Project Wind Area of Appurt. Autocalc Torque Arm Areas Add IBC .6D+W Combination √ Sort Capacity Reports By Component √ Triangulate Diamond Inner Bracing Treat Feed Line Bundles As Cylinder Ignore KL/ry For 60 Deg. Angle Legs | <ul style="list-style-type: none"> Use ASCE 10 X-Brace Ly Rules √ Calculate Redundant Bracing Forces Ignore Redundant Members in FEA √ SR Leg Bolts Resist Compression All Leg Panels Have Same Allowable Offset Girt At Foundation √ Consider Feed Line Torque √ Include Angle Block Shear Check Use TIA-222-G Bracing Resist. Exemption Use TIA-222-G Tension Splice Exemption <li style="text-align: center;">Poles √ Include Shear-Torsion Interaction Always Use Sub-Critical Flow Use Top Mounted Sockets Pole Without Linear Attachments Pole With Shroud Or No Appurtenances Outside and Inside Corner Radii Are Known |
|--|---|---|

| | | | | |
|---|----------------|-------------------------------|--------------------|-------------------|
| tnxTower Network Building + Consulting 8601 Six Forks Road, Suite 540 Raleigh, NC 27615 Phone: 919.657.9131 FAX: | Job | Woodbridge North CT | Page | 3 of 52 |
| | Project | NB+C ES Project Number 100765 | Date | 14:34:37 12/14/20 |
| | Client | Verizon | Designed by | nsmith |

| Tower Section | Tower Elevation | Diagonal Spacing | Bracing Type | Has K Brace End Panels | Has Horizontals | Top Girt Offset | Bottom Girt Offset |
|---------------|-----------------|------------------|--------------|------------------------|-----------------|-----------------|--------------------|
| | ft | ft | | | | in | in |
| T1 | 280.00-270.00 | 2.25 | X Brace | No | Steps | 5.5000 | 6.5000 |
| T2 | 270.00-250.00 | 2.38 | X Brace | No | Steps | 5.5000 | 6.5000 |
| T3 | 250.00-230.00 | 2.38 | X Brace | No | Steps | 5.5000 | 6.5000 |
| T4 | 230.00-220.00 | 10.00 | X Brace | No | No | 0.0000 | 0.0000 |
| T5 | 220.00-200.00 | 10.00 | X Brace | No | No | 0.0000 | 0.0000 |
| T6 | 200.00-180.00 | 10.00 | X Brace | No | No | 0.0000 | 0.0000 |
| T7 | 180.00-160.00 | 10.00 | X Brace | No | No | 0.0000 | 0.0000 |
| T8 | 160.00-140.00 | 10.00 | X Brace | No | No | 0.0000 | 0.0000 |
| T9 | 140.00-120.00 | 10.00 | X Brace | No | No | 0.0000 | 0.0000 |
| T10 | 120.00-100.00 | 20.00 | X Brace | No | No | 0.0000 | 0.0000 |
| T11 | 100.00-80.00 | 20.00 | X Brace | No | No | 0.0000 | 0.0000 |
| T12 | 80.00-60.00 | 20.00 | X Brace | No | No | 0.0000 | 0.0000 |
| T13 | 60.00-40.00 | 20.00 | X Brace | No | No | 0.0000 | 0.0000 |
| T14 | 40.00-20.00 | 20.00 | X Brace | No | No | 0.0000 | 0.0000 |
| T15 | 20.00-0.00 | 20.00 | X Brace | No | No | 0.0000 | 0.0000 |

Tower Section Geometry (cont'd)

| Tower Elevation | Leg Type | Leg Size | Leg Grade | Diagonal Type | Diagonal Size | Diagonal Grade |
|-------------------|-------------|--------------|------------------|--------------------|--------------------|------------------|
| ft | | | | | | |
| T1 280.00-270.00 | Solid Round | 1 3/4 | A572-50 (50 ksi) | Solid Round | 7/8 | A572-50 (50 ksi) |
| T2 270.00-250.00 | Solid Round | 2 | A572-50 (50 ksi) | Solid Round | 7/8 | A572-50 (50 ksi) |
| T3 250.00-230.00 | Solid Round | 2 1/2 | A572-50 (50 ksi) | Solid Round | 1 | A572-50 (50 ksi) |
| T4 230.00-220.00 | Truss Leg | Pirod 105245 | A572-50 (50 ksi) | Equal Angle | L2 1/2x2 1/2x3/16 | A36 (36 ksi) |
| T5 220.00-200.00 | Truss Leg | Pirod 105218 | A572-50 (50 ksi) | Equal Angle | L3x3x3/16 | A36 (36 ksi) |
| T6 200.00-180.00 | Truss Leg | Pirod 105218 | A572-50 (50 ksi) | Equal Angle | L3x3x3/16 | A36 (36 ksi) |
| T7 180.00-160.00 | Truss Leg | Pirod 105219 | A572-50 (50 ksi) | Equal Angle | L3x3x5/16 | A36 (36 ksi) |
| T8 160.00-140.00 | Truss Leg | Pirod 105220 | A572-50 (50 ksi) | Equal Angle | L3 1/2x3 1/2x5/16 | A36 (36 ksi) |
| T9 140.00-120.00 | Truss Leg | Pirod 105220 | A572-50 (50 ksi) | Equal Angle | L3 1/2x3 1/2x5/16 | A36 (36 ksi) |
| T10 120.00-100.00 | Truss Leg | Pirod 112743 | A572-50 (50 ksi) | Double Equal Angle | 2L3 1/2x3 1/2x5/16 | A36 (36 ksi) |
| T11 100.00-80.00 | Truss Leg | Pirod 112743 | A572-50 (50 ksi) | Double Equal Angle | 2L3 1/2x3 1/2x5/16 | A36 (36 ksi) |
| T12 80.00-60.00 | Truss Leg | Pirod 112744 | A572-50 (50 ksi) | Double Equal Angle | 2L3 1/2x3 1/2x5/16 | A36 (36 ksi) |
| T13 60.00-40.00 | Truss Leg | Pirod 112744 | A572-50 (50 ksi) | Double Equal Angle | 2L3 1/2x3 1/2x5/16 | A36 (36 ksi) |
| T14 40.00-20.00 | Truss Leg | Pirod 112745 | A572-50 (50 ksi) | Double Equal Angle | 2L3 1/2x3 1/2x5/16 | A36 (36 ksi) |
| T15 20.00-0.00 | Truss Leg | Pirod 112740 | A572-50 (50 ksi) | Double Equal Angle | 2L3 1/2x3 1/2x5/16 | A36 (36 ksi) |

| | | |
|---|---|----------------------------------|
| tnxTower Network Building + Consulting 8601 Six Forks Road, Suite 540 Raleigh, NC 27615 Phone: 919.657.9131 FAX: | Job Woodbridge North CT | Page 4 of 52 |
| | Project NB+C ES Project Number 100765 | Date 14:34:37 12/14/20 |
| | Client Verizon | Designed by nsmith |

Tower Section Geometry (cont'd)

| Tower Elevation ft | Top Girt Type | Top Girt Size | Top Girt Grade | Bottom Girt Type | Bottom Girt Size | Bottom Girt Grade |
|-----------------------|---------------|-------------------|---------------------|------------------|------------------|---------------------|
| T1 280.00-270.00 | Solid Round | 1 | A572-50 (50 ksi) | Solid Round | 1 | A572-50 (50 ksi) |
| T2 270.00-250.00 | Solid Round | 1 | A572-50 (50 ksi) | Solid Round | 1 | A572-50 (50 ksi) |
| T3 250.00-230.00 | Solid Round | 1 1/4 | A572-50 (50 ksi) | Solid Round | 1 1/4 | A572-50 (50 ksi) |
| T6 200.00-180.00 | Equal Angle | L3x3x3/16 | A36 (36 ksi) | Solid Round | | A36 (36 ksi) |
| T7 180.00-160.00 | Equal Angle | L4x4x1/4 | A36 (36 ksi) | Solid Round | | A36 (36 ksi) |
| T8 160.00-140.00 | Equal Angle | L3 1/2x3 1/2x5/16 | A36 (36 ksi) | Solid Round | | A36 (36 ksi) |

Tower Section Geometry (cont'd)

| Tower Elevation ft | No. of Mid Girts | Mid Girt Type | Mid Girt Size | Mid Girt Grade | Horizontal Type | Horizontal Size | Horizontal Grade |
|-----------------------|------------------|---------------|---------------|---------------------|-----------------|-----------------|---------------------|
| T1 280.00-270.00 | 1 | Solid Round | 1 | A572-50 (50 ksi) | Solid Round | 7/8 | A572-50 (50 ksi) |
| T2 270.00-250.00 | 1 | Solid Round | 1 | A572-50 (50 ksi) | Solid Round | 7/8 | A572-50 (50 ksi) |
| T3 250.00 230.00 | None | Flat Bar | | A36 (36 ksi) | Solid Round | 7/8 | A572 50 (50 ksi) |
| T6 200.00-180.00 | 1 | Equal Angle | L3x3x3/16 | A36 (36 ksi) | Single Angle | | A572-50 (50 ksi) |
| T7 180.00-160.00 | 1 | Equal Angle | L4x4x1/4 | A36 (36 ksi) | Single Angle | | A572-50 (50 ksi) |

Tower Section Geometry (cont'd)

| Tower Elevation ft | Gusset Area (per face) ft ² | Gusset Thickness in | Gusset Grade | Adjust. Factor A _f | Adjust. Factor A _r | Weight Mult. | Double Angle Stitch Bolt Spacing Diagonals in | Double Angle Stitch Bolt Spacing Horizontals in | Double Angle Stitch Bolt Spacing Redundants in |
|-----------------------|--|------------------------|-----------------|----------------------------------|----------------------------------|--------------|---|---|--|
| T1 280.00-270.00 | 0.00 | 0.0000 | A36 (36 ksi) | 1 | 1 | 1 | 36.0000 | 36.0000 | 36.0000 |
| T2 270.00-250.00 | 0.00 | 0.0000 | A36 (36 ksi) | 1 | 1 | 1 | 36.0000 | 36.0000 | 36.0000 |
| T3 250.00-230.00 | 0.00 | 0.0000 | A36 (36 ksi) | 1 | 1 | 1 | 36.0000 | 36.0000 | 36.0000 |
| T4 230.00-220.00 | 0.00 | 0.0000 | A36 (36 ksi) | 1 | 1 | 1 | 36.0000 | 36.0000 | 36.0000 |
| T5 220.00-200.00 | 0.00 | 0.0000 | A36 (36 ksi) | 1 | 1 | 1 | 36.0000 | 36.0000 | 36.0000 |
| T6 | 0.00 | 0.0000 | A36 | 1 | 1 | 1 | 36.0000 | 36.0000 | 36.0000 |

| | | | | |
|---|----------------|-------------------------------|--------------------|-------------------|
| tnxTower Network Building + Consulting 8601 Six Forks Road, Suite 540 Raleigh, NC 27615 Phone: 919.657.9131 FAX: | Job | Woodbridge North CT | Page | 6 of 52 |
| | Project | NB+C ES Project Number 100765 | Date | 14:34:37 12/14/20 |
| | Client | Verizon | Designed by | nsmith |

| Tower Elevation ft | Calc K Single Angles | Calc K Solid Rounds | K Factors ¹ | | | | | | | |
|-----------------------|-------------------------|------------------------|------------------------|---------------------|---------------------|-----------------|--------|--------|----------------|----------------|
| | | | Legs | X Brace Diags | K Brace Diags | Single Diags | Girts | Horiz. | Sec. Horiz. | Inner Brace |
| | | | | X Y | X Y | X Y | X Y | X Y | X Y | X Y |
| 40.00-20.00 T15 | Yes | Yes | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 |
| 20.00-0.00 | | | | 1 | 1 | 1 | 1 | 1 | 1 | 1 |

¹Note: K factors are applied to member segment lengths. K-braces without inner supporting members will have the K factor in the out-of-plane direction applied to the overall length.

Tower Section Geometry (cont'd)

| Tower Elevation ft | Leg Panels | Truss-Leg K Factors | | | | | |
|-----------------------|------------|--------------------------------|-------------------------|---------------|----------------------------------|-------------------------|------|
| | | Truss-Legs Used As Leg Members | | | Truss-Legs Used As Inner Members | | |
| | | X Brace Diagonals | Z Brace Diagonals | Leg Panels | X Brace Diagonals | Z Brace Diagonals | |
| 230.00-220.00 | T4 | 1 | 0.5 | 0.85 | 1 | 0.5 | 0.85 |
| 220.00-200.00 | T5 | 1 | 0.5 | 0.85 | 1 | 0.5 | 0.85 |
| 200.00-180.00 | T6 | 1 | 0.5 | 0.85 | 1 | 0.5 | 0.85 |
| 180.00-160.00 | T7 | 1 | 0.5 | 0.85 | 1 | 0.5 | 0.85 |
| 160.00-140.00 | T8 | 1 | 0.5 | 0.85 | 1 | 0.5 | 0.85 |
| 140.00-120.00 | T9 | 1 | 0.5 | 0.85 | 1 | 0.5 | 0.85 |
| 120.00-100.00 | T10 | 1 | 0.5 | 0.85 | 1 | 0.5 | 0.85 |
| 100.00-80.00 | T11 | 1 | 0.5 | 0.85 | 1 | 0.5 | 0.85 |
| 80.00-60.00 | T12 | 1 | 0.5 | 0.85 | 1 | 0.5 | 0.85 |
| 60.00-40.00 | T13 | 1 | 0.5 | 0.85 | 1 | 0.5 | 0.85 |
| 40.00-20.00 | T14 | 1 | 0.5 | 0.85 | 1 | 0.5 | 0.85 |
| 20.00-0.00 | T15 | 1 | 0.5 | 0.85 | 1 | 0.5 | 0.85 |

Tower Section Geometry (cont'd)

| Tower Elevation ft | Leg | | Diagonal | | Top Girt | | Bottom Girt | | Mid Girt | | Long Horizontal | | Short Horizontal | |
|-----------------------|---------------------------|---|---------------------------|---|---------------------------|---|---------------------------|---|---------------------------|------|---------------------------|---|---------------------------|------|
| | Net Width Deduct in | U | Net Width Deduct in | U | Net Width Deduct in | U | Net Width Deduct in | U | Net Width Deduct in | U | Net Width Deduct in | U | Net Width Deduct in | U |
| T1 280.00-270.00 | 0.0000 | 1 | 0.0000 | 1 | 0.0000 | 1 | 0.0000 | 1 | 0.0000 | 0.75 | 0.0000 | 1 | 0.0000 | 0.75 |

| | | | | |
|---|----------------|-------------------------------|--------------------|-------------------|
| tnxTower Network Building + Consulting 8601 Six Forks Road, Suite 540 Raleigh, NC 27615 Phone: 919.657.9131 FAX: | Job | Woodbridge North CT | Page | 7 of 52 |
| | Project | NB+C ES Project Number 100765 | Date | 14:34:37 12/14/20 |
| | Client | Verizon | Designed by | nsmith |

| Tower Elevation ft | Leg | | Diagonal | | Top Girt | | Bottom Girt | | Mid Girt | | Long Horizontal | | Short Horizontal | |
|-----------------------|---------------------------|---|---------------------------|---|---------------------------|---|------------------------------|---|------------------------------|------|------------------------------|------|------------------------------|------|
| | Net Width Deduct in | U | Net Width Deduct in | U | Net Width Deduct in | U | Net Width Deduct in | U | Net Width Deduct in | U | Net Width Deduct in | U | Net Width Deduct in | U |
| T2 270.00-250.00 | 0.0000 | 1 | 0.0000 | 1 | 0.0000 | 1 | 0.0000 | 1 | 0.0000 | 0.75 | 0.0000 | 1 | 0.0000 | 0.75 |
| T3 250.00-230.00 | 0.0000 | 1 | 0.0000 | 1 | 0.0000 | 1 | 0.0000 | 1 | 0.0000 | 0.75 | 0.0000 | 1 | 0.0000 | 0.75 |
| T4 230.00-220.00 | 0.0000 | 1 | 0.0000 | 1 | 0.0000 | 1 | 0.0000 | 1 | 0.0000 | 0.75 | 0.0000 | 0.75 | 0.0000 | 0.75 |
| T5 220.00-200.00 | 0.0000 | 1 | 0.0000 | 1 | 0.0000 | 1 | 0.0000 | 1 | 0.0000 | 0.75 | 0.0000 | 0.75 | 0.0000 | 0.75 |
| T6 200.00-180.00 | 0.0000 | 1 | 0.0000 | 1 | 0.0000 | 1 | 0.0000 | 1 | 0.0000 | 0.75 | 0.0000 | 0.75 | 0.0000 | 0.75 |
| T7 180.00-160.00 | 0.0000 | 1 | 0.0000 | 1 | 0.0000 | 1 | 0.0000 | 1 | 0.0000 | 0.75 | 0.0000 | 0.75 | 0.0000 | 0.75 |
| T8 160.00-140.00 | 0.0000 | 1 | 0.0000 | 1 | 0.0000 | 1 | 0.0000 | 1 | 0.0000 | 0.75 | 0.0000 | 0.75 | 0.0000 | 0.75 |
| T9 140.00-120.00 | 0.0000 | 1 | 0.0000 | 1 | 0.0000 | 1 | 0.0000 | 1 | 0.0000 | 0.75 | 0.0000 | 0.75 | 0.0000 | 0.75 |
| T10 120.00-100.00 | 0.0000 | 1 | 0.0000 | 1 | 0.0000 | 1 | 0.0000 | 1 | 0.0000 | 0.75 | 0.0000 | 0.75 | 0.0000 | 0.75 |
| T11 100.00-80.00 | 0.0000 | 1 | 0.0000 | 1 | 0.0000 | 1 | 0.0000 | 1 | 0.0000 | 0.75 | 0.0000 | 0.75 | 0.0000 | 0.75 |
| T12 80.00-60.00 | 0.0000 | 1 | 0.0000 | 1 | 0.0000 | 1 | 0.0000 | 1 | 0.0000 | 0.75 | 0.0000 | 0.75 | 0.0000 | 0.75 |
| T13 60.00-40.00 | 0.0000 | 1 | 0.0000 | 1 | 0.0000 | 1 | 0.0000 | 1 | 0.0000 | 0.75 | 0.0000 | 0.75 | 0.0000 | 0.75 |
| T14 40.00-20.00 | 0.0000 | 1 | 0.0000 | 1 | 0.0000 | 1 | 0.0000 | 1 | 0.0000 | 0.75 | 0.0000 | 0.75 | 0.0000 | 0.75 |
| T15 20.00-0.00 | 0.0000 | 1 | 0.0000 | 1 | 0.0000 | 1 | 0.0000 | 1 | 0.0000 | 0.75 | 0.0000 | 0.75 | 0.0000 | 0.75 |

Tower Section Geometry (cont'd)

| Tower Elevation ft | Leg Connection Type | Leg | | Diagonal | | Top Girt | | Bottom Girt | | Mid Girt | | Long Horizontal | | Short Horizontal | |
|-----------------------|------------------------|-----------------|-----|-----------------|-----|-----------------|-----|-----------------|-----|-----------------|-----|-----------------|-----|------------------|-----|
| | | Bolt Size in | No. | Bolt Size in | No. | Bolt Size in | No. | Bolt Size in | No. | Bolt Size in | No. | Bolt Size in | No. | Bolt Size in | No. |
| T1 280.00-270.00 | Sleeve DS | 0.6250 | 5 | 0.6250 | 0 | 0.6250 | 0 | 0.6250 | 0 | 0.6250 | 0 | 0.6250 | 0 | 0.6250 | 0 |
| T2 270.00-250.00 | Sleeve DS | 0.7500 | 5 | 0.6250 | 0 | 0.6250 | 0 | 0.6250 | 0 | 0.6250 | 0 | 0.6250 | 0 | 0.6250 | 0 |
| T3 250.00-230.00 | Flange | 1.0000 | 6 | 1.0000 | 0 | 0.6250 | 0 | 0.6250 | 0 | 0.6250 | 0 | 0.6250 | 0 | 0.6250 | 0 |
| T4 230.00-220.00 | Flange | 1.0000 | 6 | 1.0000 | 1 | 0.6250 | 0 | 0.6250 | 0 | 0.6250 | 0 | 0.6250 | 0 | 0.6250 | 0 |
| T5 220.00-200.00 | Flange | 1.0000 | 6 | 1.0000 | 1 | 0.6250 | 0 | 0.6250 | 0 | 0.6250 | 0 | 0.6250 | 0 | 0.6250 | 0 |
| T6 200.00-180.00 | Flange | 1.0000 | 6 | 1.0000 | 1 | 1.0000 | 1 | 0.6250 | 0 | 1.0000 | 1 | 0.6250 | 0 | 0.6250 | 0 |
| T7 180.00-160.00 | Flange | 1.2500 | 6 | 1.2500 | 1 | 1.2500 | 1 | 0.6250 | 0 | 1.2500 | 1 | 0.6250 | 0 | 0.6250 | 0 |
| T8 160.00-140.00 | Flange | 1.2500 | 6 | 1.2500 | 1 | 1.2500 | 1 | 0.6250 | 0 | 0.6250 | 0 | 0.6250 | 0 | 0.6250 | 0 |

| | | | | |
|---|----------------|-------------------------------|--------------------|-------------------|
| tnxTower Network Building + Consulting 8601 Six Forks Road, Suite 540 Raleigh, NC 27615 Phone: 919.657.9131 FAX: | Job | Woodbridge North CT | Page | 8 of 52 |
| | Project | NB+C ES Project Number 100765 | Date | 14:34:37 12/14/20 |
| | Client | Verizon | Designed by | nsmith |

| Tower Elevation ft | Leg Connection Type | Leg | | Diagonal | | Top Girt | | Bottom Girt | | Mid Girt | | Long Horizontal | | Short Horizontal | |
|----------------------|---------------------|--------------|-----|--------------|-----|--------------|-----|--------------|-----|--------------|-----|-----------------|-----|------------------|-----|
| | | Bolt Size in | No. | Bolt Size in | No. | Bolt Size in | No. | Bolt Size in | No. | Bolt Size in | No. | Bolt Size in | No. | Bolt Size in | No. |
| T9 140.00-120.00 | Flange | 1.2500 | 6 | 1.2500 | 1 | 0.6250 | 0 | 0.6250 | 0 | 0.6250 | 0 | 0.6250 | 0 | 0.6250 | 0 |
| | | A325N | | A325N | | A325N | | A325N | | A325N | | A325N | | A325N | |
| T10 120.00-100.00 | Flange | 1.2500 | 12 | 1.0000 | 2 | 0.6250 | 0 | 0.6250 | 0 | 0.6250 | 0 | 0.6250 | 0 | 0.6250 | 0 |
| | | A325N | | A325N | | A325N | | A325N | | A325N | | A325N | | A325N | |
| T11 100.00-80.00 | Flange | 1.2500 | 12 | 1.0000 | 2 | 0.6250 | 0 | 0.6250 | 0 | 0.6250 | 0 | 0.6250 | 0 | 0.6250 | 0 |
| | | A325N | | A325N | | A325N | | A325N | | A325N | | A325N | | A325N | |
| T12 80.00-60.00 | Flange | 1.2500 | 12 | 1.0000 | 2 | 0.6250 | 0 | 0.6250 | 0 | 0.6250 | 0 | 0.6250 | 0 | 0.6250 | 0 |
| | | A325N | | A325N | | A325N | | A325N | | A325N | | A325N | | A325N | |
| T13 60.00-40.00 | Flange | 1.2500 | 12 | 1.0000 | 2 | 0.6250 | 0 | 0.6250 | 0 | 0.6250 | 0 | 0.6250 | 0 | 0.6250 | 0 |
| | | A325N | | A325N | | A325N | | A325N | | A325N | | A325N | | A325N | |
| T14 40.00-20.00 | Flange | 1.2500 | 12 | 1.0000 | 2 | 0.6250 | 0 | 0.6250 | 0 | 0.6250 | 0 | 0.6250 | 0 | 0.6250 | 0 |
| | | A325N | | A325N | | A325N | | A325N | | A325N | | A325N | | A325N | |
| T15 20.00-0.00 | Flange | 0.7500 | 0 | 1.0000 | 2 | 0.6250 | 0 | 0.6250 | 0 | 0.6250 | 0 | 0.6250 | 0 | 0.6250 | 0 |
| | | A325N | | A325N | | A325N | | A325N | | A325N | | A325N | | A325N | |

Feed Line/Linear Appurtenances - Entered As Round Or Flat

| Description | Face or Leg | Allow Shield | Exclude From Torque Calculation | Component Type | Placement ft | Face Offset in | Lateral Offset (Frac FW) | # | # Per Row | Clear Spacing in | Width or Diameter in | Perimeter in | Weight plf |
|---------------------------|-------------|--------------|---------------------------------|----------------|----------------|----------------|--------------------------|----|-----------|------------------|----------------------|--------------|------------|
| LDF7-50A (1-5/8 FOAM) *** | C | No | No | Ar (CaAa) | 280.00 - 12.00 | -12.000 0 | 0.47 | 4 | 2 | 0.7500 | 1.9800 | | 0.82 |
| LDF7-50A (1-5/8 FOAM) *** | A | No | No | Ar (CaAa) | 250.00 - 12.00 | -12.000 0 | 0.45 | 9 | 8 | 0.7500 | 1.9800 | | 0.82 |
| HCS 6X12 4AWG(1-5/8) *** | C | No | No | Ar (CaAa) | 0.00 - 12.00 | -8.0000 | 0.46 | 3 | 3 | 1.6600 | 1.6600 | | 2.40 |
| LDF7-50A (1-5/8 FOAM) *** | B | No | No | Ar (CaAa) | 200.00 - 12.00 | -15.000 0 | 0.45 | 9 | 3 | 0.7500 | 1.9800 | | 0.82 |
| LDF7-50A (1-5/8 FOAM) *** | C | No | No | Ar (CaAa) | 190.00 - 12.00 | -12.000 0 | 0.45 | 9 | 5 | 0.7500 | 1.9800 | | 0.82 |
| LDF7-50A (1-5/8 FOAM) *** | C | No | No | Ar (CaAa) | 180.00 - 12.00 | -12.000 0 | 0.43 | 9 | 5 | 0.7500 | 1.9800 | | 0.82 |
| LDF7-50A (1-5/8 FOAM) *** | A | No | No | Ar (CaAa) | 170.00 - 12.00 | -12.000 0 | 0.45 | 3 | 3 | 0.7500 | 1.9800 | | 0.82 |
| HCS 6X12 4AWG(1-5/8) *** | A | No | No | Ar (CaAa) | 170.00 - 12.00 | 0.0000 | 0.42 | 1 | 1 | 1.6600 | 1.6600 | | 2.40 |
| LDF7-50A (1-5/8 FOAM) *** | A | No | No | Ar (CaAa) | 160.00 - 12.00 | -12.000 0 | 0.45 | 6 | 6 | 0.7500 | 1.9800 | | 0.82 |
| Fiber Cable (1/4") | C | No | No | Ar (CaAa) | 160.00 - 12.00 | -8.0000 | 0.49 | 1 | 1 | 0.2500 | 0.2500 | | 0.03 |
| DC Power | C | No | No | Ar (CaAa) | 160.00 - 12.00 | -8.0000 | 0.49 | 1 | 1 | 0.8700 | 0.8700 | | 0.15 |
| LDF7-50A (1-5/8 FOAM) *** | A | No | No | Ar (CaAa) | 150.00 - 12.00 | -8.0000 | 0.4 | 6 | 2 | 0.7500 | 1.9800 | | 0.82 |
| LDF7-50A | B | No | No | Ar (CaAa) | 140.00 - | -6.0000 | 0.45 | 12 | 12 | 0.7500 | 1.9800 | | 0.82 |

| | | | | |
|---|----------------|-------------------------------|--------------------|-------------------|
| tnxTower Network Building + Consulting 8601 Six Forks Road, Suite 540 Raleigh, NC 27615 Phone: 919.657.9131 FAX: | Job | Woodbridge North CT | Page | 9 of 52 |
| | Project | NB+C ES Project Number 100765 | Date | 14:34:37 12/14/20 |
| | Client | Verizon | Designed by | nsmith |

| Description | Face or Leg | Allow Shield | Exclude From Torque Calculation | Component Type | Placement ft | Face Offset in | Lateral Offset (Frac FW) | # | # Per Row | Clear Spacing in | Width or Diameter in | Perimeter in | Weight plf |
|--------------|-------------|--------------|---------------------------------|----------------|--------------|----------------|--------------------------|---|-----------|------------------|----------------------|--------------|------------|
| (1-5/8 FOAM) | | | | | 12.00 | | | | | | | | |
| HCS 6X12 | B | No | No | Ar (CaAa) | 140.00 - | -6.0000 | 0.46 | 1 | 1 | 1.6600 | 1.6600 | | 2.40 |
| 4AWG(1-5/8) | | | | | 12.00 | | | | | | | | |

Feed Line/Linear Appurtenances Section Areas

| Tower Section | Tower Elevation ft | Face | A _R ft ² | A _F ft ² | C _{AA} In Face ft ² | C _{AA} Out Face ft ² | Weight K |
|---------------|--------------------|------|--------------------------------|--------------------------------|---|--|----------|
| T1 | 280.00-270.00 | A | 0.000 | 0.000 | 0.000 | 0.000 | 0.00 |
| | | B | 0.000 | 0.000 | 0.000 | 0.000 | 0.00 |
| | | C | 0.000 | 0.000 | 7.920 | 0.000 | 0.03 |
| T2 | 270.00-250.00 | A | 0.000 | 0.000 | 0.000 | 0.000 | 0.00 |
| | | B | 0.000 | 0.000 | 0.000 | 0.000 | 0.00 |
| | | C | 0.000 | 0.000 | 15.840 | 0.000 | 0.07 |
| T3 | 250.00-230.00 | A | 0.000 | 0.000 | 35.640 | 0.000 | 0.15 |
| | | B | 0.000 | 0.000 | 0.000 | 0.000 | 0.00 |
| | | C | 0.000 | 0.000 | 15.840 | 0.000 | 0.07 |
| T4 | 230.00-220.00 | A | 0.000 | 0.000 | 17.820 | 0.000 | 0.07 |
| | | B | 0.000 | 0.000 | 0.000 | 0.000 | 0.00 |
| | | C | 0.000 | 0.000 | 7.920 | 0.000 | 0.03 |
| T5 | 220.00-200.00 | A | 0.000 | 0.000 | 35.640 | 0.000 | 0.15 |
| | | B | 0.000 | 0.000 | 0.000 | 0.000 | 0.00 |
| | | C | 0.000 | 0.000 | 15.840 | 0.000 | 0.07 |
| T6 | 200.00-180.00 | A | 0.000 | 0.000 | 35.640 | 0.000 | 0.15 |
| | | B | 0.000 | 0.000 | 35.640 | 0.000 | 0.15 |
| | | C | 0.000 | 0.000 | 33.660 | 0.000 | 0.14 |
| T7 | 180.00-160.00 | A | 0.000 | 0.000 | 43.240 | 0.000 | 0.20 |
| | | B | 0.000 | 0.000 | 35.640 | 0.000 | 0.15 |
| | | C | 0.000 | 0.000 | 87.120 | 0.000 | 0.36 |
| T8 | 160.00-140.00 | A | 0.000 | 0.000 | 86.480 | 0.000 | 0.39 |
| | | B | 0.000 | 0.000 | 35.640 | 0.000 | 0.15 |
| | | C | 0.000 | 0.000 | 89.360 | 0.000 | 0.36 |
| T9 | 140.00-120.00 | A | 0.000 | 0.000 | 98.360 | 0.000 | 0.44 |
| | | B | 0.000 | 0.000 | 86.480 | 0.000 | 0.39 |
| | | C | 0.000 | 0.000 | 89.360 | 0.000 | 0.36 |
| T10 | 120.00-100.00 | A | 0.000 | 0.000 | 98.360 | 0.000 | 0.44 |
| | | B | 0.000 | 0.000 | 86.480 | 0.000 | 0.39 |
| | | C | 0.000 | 0.000 | 89.360 | 0.000 | 0.36 |
| T11 | 100.00-80.00 | A | 0.000 | 0.000 | 98.360 | 0.000 | 0.44 |
| | | B | 0.000 | 0.000 | 86.480 | 0.000 | 0.39 |
| | | C | 0.000 | 0.000 | 89.360 | 0.000 | 0.36 |
| T12 | 80.00-60.00 | A | 0.000 | 0.000 | 98.360 | 0.000 | 0.44 |
| | | B | 0.000 | 0.000 | 86.480 | 0.000 | 0.39 |
| | | C | 0.000 | 0.000 | 89.360 | 0.000 | 0.36 |
| T13 | 60.00-40.00 | A | 0.000 | 0.000 | 98.360 | 0.000 | 0.44 |
| | | B | 0.000 | 0.000 | 86.480 | 0.000 | 0.39 |
| | | C | 0.000 | 0.000 | 89.360 | 0.000 | 0.36 |
| T14 | 40.00-20.00 | A | 0.000 | 0.000 | 98.360 | 0.000 | 0.44 |
| | | B | 0.000 | 0.000 | 86.480 | 0.000 | 0.39 |
| | | C | 0.000 | 0.000 | 89.360 | 0.000 | 0.36 |
| T15 | 20.00-0.00 | A | 0.000 | 0.000 | 39.344 | 0.000 | 0.18 |
| | | B | 0.000 | 0.000 | 34.592 | 0.000 | 0.16 |
| | | C | 0.000 | 0.000 | 41.720 | 0.000 | 0.23 |

| | | | | |
|---|----------------|-------------------------------|--------------------|-------------------|
| tnxTower Network Building + Consulting 8601 Six Forks Road, Suite 540 Raleigh, NC 27615 Phone: 919.657.9131 FAX: | Job | Woodbridge North CT | Page | 10 of 52 |
| | Project | NB+C ES Project Number 100765 | Date | 14:34:37 12/14/20 |
| | Client | Verizon | Designed by | nsmith |

Feed Line/Linear Appurtenances Section Areas - With Ice

| Tower Section | Tower Elevation ft | Face or Leg | Ice Thickness in | A _R ft ² | A _F ft ² | C _A A _A In Face ft ² | C _A A _A Out Face ft ² | Weight K |
|---------------|-----------------------|-------------|---------------------|-----------------------------------|-----------------------------------|---|--|-------------|
| T1 | 280.00-270.00 | A | 1.854 | 0.000 | 0.000 | 0.000 | 0.000 | 0.00 |
| | | B | | 0.000 | 0.000 | 0.000 | 0.000 | 0.00 |
| | | C | | 0.000 | 0.000 | 14.882 | 0.000 | 0.23 |
| T2 | 270.00-250.00 | A | 1.844 | 0.000 | 0.000 | 0.000 | 0.000 | 0.00 |
| | | B | | 0.000 | 0.000 | 0.000 | 0.000 | 0.00 |
| | | C | | 0.000 | 0.000 | 29.691 | 0.000 | 0.46 |
| T3 | 250.00-230.00 | A | 1.829 | 0.000 | 0.000 | 65.312 | 0.000 | 1.07 |
| | | B | | 0.000 | 0.000 | 0.000 | 0.000 | 0.00 |
| | | C | | 0.000 | 0.000 | 29.587 | 0.000 | 0.46 |
| T4 | 230.00-220.00 | A | 1.817 | 0.000 | 0.000 | 32.619 | 0.000 | 0.53 |
| | | B | | 0.000 | 0.000 | 0.000 | 0.000 | 0.00 |
| | | C | | 0.000 | 0.000 | 14.752 | 0.000 | 0.23 |
| T5 | 220.00-200.00 | A | 1.805 | 0.000 | 0.000 | 65.159 | 0.000 | 1.06 |
| | | B | | 0.000 | 0.000 | 0.000 | 0.000 | 0.00 |
| | | C | | 0.000 | 0.000 | 29.415 | 0.000 | 0.46 |
| T6 | 200.00-180.00 | A | 1.787 | 0.000 | 0.000 | 65.045 | 0.000 | 1.05 |
| | | B | | 0.000 | 0.000 | 38.940 | 0.000 | 0.82 |
| | | C | | 0.000 | 0.000 | 52.337 | 0.000 | 0.89 |
| T7 | 180.00-160.00 | A | 1.767 | 0.000 | 0.000 | 85.467 | 0.000 | 1.34 |
| | | B | | 0.000 | 0.000 | 38.800 | 0.000 | 0.82 |
| | | C | | 0.000 | 0.000 | 121.080 | 0.000 | 2.18 |
| T8 | 160.00-140.00 | A | 1.745 | 0.000 | 0.000 | 172.439 | 0.000 | 2.64 |
| | | B | | 0.000 | 0.000 | 38.645 | 0.000 | 0.81 |
| | | C | | 0.000 | 0.000 | 136.832 | 0.000 | 2.36 |
| T9 | 140.00-120.00 | A | 1.720 | 0.000 | 0.000 | 188.770 | 0.000 | 2.90 |
| | | B | | 0.000 | 0.000 | 138.328 | 0.000 | 2.35 |
| | | C | | 0.000 | 0.000 | 136.125 | 0.000 | 2.33 |
| T10 | 120.00-100.00 | A | 1.692 | 0.000 | 0.000 | 187.910 | 0.000 | 2.86 |
| | | B | | 0.000 | 0.000 | 137.851 | 0.000 | 2.32 |
| | | C | | 0.000 | 0.000 | 135.314 | 0.000 | 2.30 |
| T11 | 100.00-80.00 | A | 1.658 | 0.000 | 0.000 | 186.895 | 0.000 | 2.82 |
| | | B | | 0.000 | 0.000 | 137.287 | 0.000 | 2.29 |
| | | C | | 0.000 | 0.000 | 134.356 | 0.000 | 2.26 |
| T12 | 80.00-60.00 | A | 1.617 | 0.000 | 0.000 | 185.654 | 0.000 | 2.76 |
| | | B | | 0.000 | 0.000 | 136.598 | 0.000 | 2.24 |
| | | C | | 0.000 | 0.000 | 133.185 | 0.000 | 2.22 |
| T13 | 60.00-40.00 | A | 1.564 | 0.000 | 0.000 | 184.043 | 0.000 | 2.68 |
| | | B | | 0.000 | 0.000 | 135.702 | 0.000 | 2.19 |
| | | C | | 0.000 | 0.000 | 131.662 | 0.000 | 2.16 |
| T14 | 40.00-20.00 | A | 1.486 | 0.000 | 0.000 | 181.700 | 0.000 | 2.58 |
| | | B | | 0.000 | 0.000 | 134.399 | 0.000 | 2.11 |
| | | C | | 0.000 | 0.000 | 129.448 | 0.000 | 2.08 |
| T15 | 20.00-0.00 | A | 1.331 | 0.000 | 0.000 | 70.825 | 0.000 | 0.95 |
| | | B | | 0.000 | 0.000 | 52.727 | 0.000 | 0.78 |
| | | C | | 0.000 | 0.000 | 67.698 | 0.000 | 1.03 |

Feed Line Center of Pressure

| Section | Elevation ft | CP _X in | CP _Z in | CP _X Ice in | CP _Z Ice in |
|---------|-----------------|-----------------------|-----------------------|------------------------------|------------------------------|
| T1 | 280.00-270.00 | -6.2398 | 1.2602 | -2.4443 | 0.4937 |

| | | | | |
|---|----------------|-------------------------------|--------------------|-------------------|
| tnxTower Network Building + Consulting 8601 Six Forks Road, Suite 540 Raleigh, NC 27615 Phone: 919.657.9131 FAX: | Job | Woodbridge North CT | Page | 11 of 52 |
| | Project | NB+C ES Project Number 100765 | Date | 14:34:37 12/14/20 |
| | Client | Verizon | Designed by | nsmith |

| Section | Elevation | CP _x | CP _z | CP _x | CP _z |
|---------|---------------|-----------------|-----------------|-----------------|-----------------|
| | ft | in | in | Ice in | Ice in |
| T2 | 270.00-250.00 | -6.1506 | 1.2422 | -2.7537 | 0.5562 |
| T3 | 250.00-230.00 | -1.7591 | -9.1172 | -1.2806 | -4.5295 |
| T4 | 230.00-220.00 | -1.2178 | -6.1334 | -0.5837 | -2.0288 |
| T5 | 220.00-200.00 | -2.0483 | -8.3770 | -1.4416 | -4.2495 |
| T6 | 200.00-180.00 | -2.6014 | -4.5192 | -1.8042 | -2.5968 |
| T7 | 180.00-160.00 | -12.0014 | -4.8171 | -8.8543 | -3.8057 |
| T8 | 160.00-140.00 | -12.5871 | -14.3041 | -11.7504 | -12.5853 |
| T9 | 140.00-120.00 | -7.2632 | -8.4908 | -6.7832 | -7.7235 |
| T10 | 120.00-100.00 | -8.2197 | -9.5628 | -7.4133 | -8.4445 |
| T11 | 100.00-80.00 | -9.1015 | -10.6520 | -8.1990 | -9.3888 |
| T12 | 80.00-60.00 | -9.8464 | -11.5836 | -8.9130 | -10.2721 |
| T13 | 60.00-40.00 | -10.6478 | -12.5858 | -9.6104 | -11.1612 |
| T14 | 40.00-20.00 | -11.2806 | -13.3853 | -10.2388 | -12.0162 |
| T15 | 20.00-0.00 | -9.5027 | -7.1254 | -10.6677 | -5.7677 |

Shielding Factor Ka

| Tower Section | Feed Line Record No. | Description | Feed Line Segment Elev. | K _a No Ice | K _a Ice |
|---------------|----------------------|-----------------------|-------------------------|--------------------------|-----------------------|
| T1 | 1 | LDF7-50A (1-5/8 FOAM) | 270.00 - 280.00 | 0.6000 | 0.4303 |
| T2 | 1 | LDF7-50A (1-5/8 FOAM) | 250.00 - 270.00 | 0.6000 | 0.4777 |
| T3 | 1 | LDF7-50A (1-5/8 FOAM) | 230.00 - 250.00 | 0.6000 | 0.4795 |
| T3 | 3 | LDF7-50A (1-5/8 FOAM) | 230.00 - 250.00 | 0.6000 | 0.4795 |
| T4 | 1 | LDF7-50A (1-5/8 FOAM) | 220.00 - 230.00 | 0.6000 | 0.2579 |
| T4 | 3 | LDF7-50A (1-5/8 FOAM) | 220.00 - 230.00 | 0.6000 | 0.2579 |
| T5 | 1 | LDF7-50A (1-5/8 FOAM) | 200.00 - 220.00 | 0.6000 | 0.4038 |
| T5 | 3 | LDF7-50A (1-5/8 FOAM) | 200.00 - 220.00 | 0.6000 | 0.4038 |
| T6 | 1 | LDF7-50A (1-5/8 FOAM) | 180.00 - 200.00 | 0.6000 | 0.4642 |
| T6 | 3 | LDF7-50A (1-5/8 FOAM) | 180.00 - 200.00 | 0.6000 | 0.4642 |
| T6 | 6 | LDF7-50A (1-5/8 FOAM) | 180.00 - 200.00 | 0.6000 | 0.4642 |
| T6 | 8 | LDF7-50A (1-5/8 FOAM) | 180.00 - 190.00 | 0.6000 | 0.4642 |
| T7 | 1 | LDF7-50A (1-5/8 FOAM) | 160.00 - 180.00 | 0.6000 | 0.5206 |
| T7 | 3 | LDF7-50A (1-5/8 FOAM) | 160.00 - 180.00 | 0.6000 | 0.5206 |
| T7 | 6 | LDF7-50A (1-5/8 FOAM) | 160.00 - 180.00 | 0.6000 | 0.5206 |
| T7 | 8 | LDF7-50A (1-5/8 FOAM) | 160.00 - 180.00 | 0.6000 | 0.5206 |
| T7 | 10 | LDF7-50A (1-5/8 FOAM) | 160.00 - 180.00 | 0.6000 | 0.5206 |
| T7 | 12 | LDF7-50A (1-5/8 FOAM) | 160.00 - 170.00 | 0.6000 | 0.5206 |

| | | | |
|----------------|-------------------------------|--------------------|-------------------|
| Job | Woodbridge North CT | Page | 12 of 52 |
| Project | NB+C ES Project Number 100765 | Date | 14:34:37 12/14/20 |
| Client | Verizon | Designed by | nsmith |

| Tower Section | Feed Line Record No. | Description | Feed Line Segment Elev. | K_a No Ice | K_a Ice |
|---------------|----------------------|-----------------------|-------------------------|--------------|-----------|
| T7 | 13 | HCS 6X12 4AWG(1-5/8) | 160.00 - 170.00 | 0.6000 | 0.5206 |
| T8 | 1 | LDF7-50A (1-5/8 FOAM) | 140.00 - 160.00 | 0.6000 | 0.5841 |
| T8 | 3 | LDF7-50A (1-5/8 FOAM) | 140.00 - 160.00 | 0.6000 | 0.5841 |
| T8 | 6 | LDF7-50A (1-5/8 FOAM) | 140.00 - 160.00 | 0.6000 | 0.5841 |
| T8 | 8 | LDF7-50A (1-5/8 FOAM) | 140.00 - 160.00 | 0.6000 | 0.5841 |
| T8 | 10 | LDF7-50A (1-5/8 FOAM) | 140.00 - 160.00 | 0.6000 | 0.5841 |
| T8 | 12 | LDF7-50A (1-5/8 FOAM) | 140.00 - 160.00 | 0.6000 | 0.5841 |
| T8 | 13 | HCS 6X12 4AWG(1-5/8) | 140.00 - 160.00 | 0.6000 | 0.5841 |
| T8 | 15 | LDF7-50A (1-5/8 FOAM) | 140.00 - 160.00 | 0.6000 | 0.5841 |
| T8 | 16 | Fiber Cable (1/4") | 140.00 - 160.00 | 0.6000 | 0.5841 |
| T8 | 17 | DC Power | 140.00 - 160.00 | 0.6000 | 0.5841 |
| T8 | 19 | LDF7-50A (1-5/8 FOAM) | 140.00 - 150.00 | 0.6000 | 0.5841 |
| T9 | 1 | LDF7-50A (1-5/8 FOAM) | 120.00 - 140.00 | 0.6000 | 0.6000 |
| T9 | 3 | LDF7-50A (1-5/8 FOAM) | 120.00 - 140.00 | 0.6000 | 0.6000 |
| T9 | 6 | LDF7-50A (1-5/8 FOAM) | 120.00 - 140.00 | 0.6000 | 0.6000 |
| T9 | 8 | LDF7-50A (1-5/8 FOAM) | 120.00 - 140.00 | 0.6000 | 0.6000 |
| T9 | 10 | LDF7-50A (1-5/8 FOAM) | 120.00 - 140.00 | 0.6000 | 0.6000 |
| T9 | 12 | LDF7-50A (1-5/8 FOAM) | 120.00 - 140.00 | 0.6000 | 0.6000 |
| T9 | 13 | HCS 6X12 4AWG(1-5/8) | 120.00 - 140.00 | 0.6000 | 0.6000 |
| T9 | 15 | LDF7-50A (1-5/8 FOAM) | 120.00 - 140.00 | 0.6000 | 0.6000 |
| T9 | 16 | Fiber Cable (1/4") | 120.00 - 140.00 | 0.6000 | 0.6000 |
| T9 | 17 | DC Power | 120.00 - 140.00 | 0.6000 | 0.6000 |
| T9 | 19 | LDF7-50A (1-5/8 FOAM) | 120.00 - 140.00 | 0.6000 | 0.6000 |
| T9 | 21 | LDF7-50A (1-5/8 FOAM) | 120.00 - 140.00 | 0.6000 | 0.6000 |
| T9 | 22 | HCS 6X12 4AWG(1-5/8) | 120.00 - 140.00 | 0.6000 | 0.6000 |
| T10 | 1 | LDF7-50A (1-5/8 FOAM) | 100.00 - 120.00 | 0.6000 | 0.6000 |
| T10 | 3 | LDF7-50A (1-5/8 FOAM) | 100.00 - 120.00 | 0.6000 | 0.6000 |
| T10 | 6 | LDF7-50A (1-5/8 FOAM) | 100.00 - 120.00 | 0.6000 | 0.6000 |
| T10 | 8 | LDF7-50A (1-5/8 FOAM) | 100.00 - 120.00 | 0.6000 | 0.6000 |
| T10 | 10 | LDF7-50A (1-5/8 FOAM) | 100.00 - 120.00 | 0.6000 | 0.6000 |
| T10 | 12 | LDF7-50A (1-5/8 FOAM) | 100.00 - 120.00 | 0.6000 | 0.6000 |

| | | | |
|----------------|-------------------------------|--------------------|-------------------|
| Job | Woodbridge North CT | Page | 13 of 52 |
| Project | NB+C ES Project Number 100765 | Date | 14:34:37 12/14/20 |
| Client | Verizon | Designed by | nsmith |

| Tower Section | Feed Line Record No. | Description | Feed Line Segment Elev. | K_a No Ice | K_a Ice |
|---------------|----------------------|-----------------------|-------------------------|--------------|-----------|
| T10 | 13 | HCS 6X12 4AWG(1-5/8) | 100.00 - 120.00 | 0.6000 | 0.6000 |
| T10 | 15 | LDF7-50A (1-5/8 FOAM) | 100.00 - 120.00 | 0.6000 | 0.6000 |
| T10 | 16 | Fiber Cable (1/4") | 100.00 - 120.00 | 0.6000 | 0.6000 |
| T10 | 17 | DC Power | 100.00 - 120.00 | 0.6000 | 0.6000 |
| T10 | 19 | LDF7-50A (1-5/8 FOAM) | 100.00 - 120.00 | 0.6000 | 0.6000 |
| T10 | 21 | LDF7-50A (1-5/8 FOAM) | 100.00 - 120.00 | 0.6000 | 0.6000 |
| T10 | 22 | HCS 6X12 4AWG(1-5/8) | 100.00 - 120.00 | 0.6000 | 0.6000 |
| T11 | 1 | LDF7-50A (1-5/8 FOAM) | 80.00 - 100.00 | 0.6000 | 0.6000 |
| T11 | 3 | LDF7-50A (1-5/8 FOAM) | 80.00 - 100.00 | 0.6000 | 0.6000 |
| T11 | 6 | LDF7-50A (1-5/8 FOAM) | 80.00 - 100.00 | 0.6000 | 0.6000 |
| T11 | 8 | LDF7-50A (1-5/8 FOAM) | 80.00 - 100.00 | 0.6000 | 0.6000 |
| T11 | 10 | LDF7-50A (1-5/8 FOAM) | 80.00 - 100.00 | 0.6000 | 0.6000 |
| T11 | 12 | LDF7-50A (1-5/8 FOAM) | 80.00 - 100.00 | 0.6000 | 0.6000 |
| T11 | 13 | HCS 6X12 4AWG(1-5/8) | 80.00 - 100.00 | 0.6000 | 0.6000 |
| T11 | 15 | LDF7-50A (1-5/8 FOAM) | 80.00 - 100.00 | 0.6000 | 0.6000 |
| T11 | 16 | Fiber Cable (1/4") | 80.00 - 100.00 | 0.6000 | 0.6000 |
| T11 | 17 | DC Power | 80.00 - 100.00 | 0.6000 | 0.6000 |
| T11 | 19 | LDF7-50A (1-5/8 FOAM) | 80.00 - 100.00 | 0.6000 | 0.6000 |
| T11 | 21 | LDF7-50A (1-5/8 FOAM) | 80.00 - 100.00 | 0.6000 | 0.6000 |
| T11 | 22 | HCS 6X12 4AWG(1-5/8) | 80.00 - 100.00 | 0.6000 | 0.6000 |
| T12 | 1 | LDF7-50A (1-5/8 FOAM) | 60.00 - 80.00 | 0.6000 | 0.6000 |
| T12 | 3 | LDF7-50A (1-5/8 FOAM) | 60.00 - 80.00 | 0.6000 | 0.6000 |
| T12 | 6 | LDF7-50A (1-5/8 FOAM) | 60.00 - 80.00 | 0.6000 | 0.6000 |
| T12 | 8 | LDF7-50A (1-5/8 FOAM) | 60.00 - 80.00 | 0.6000 | 0.6000 |
| T12 | 10 | LDF7-50A (1-5/8 FOAM) | 60.00 - 80.00 | 0.6000 | 0.6000 |
| T12 | 12 | LDF7-50A (1-5/8 FOAM) | 60.00 - 80.00 | 0.6000 | 0.6000 |
| T12 | 13 | HCS 6X12 4AWG(1-5/8) | 60.00 - 80.00 | 0.6000 | 0.6000 |
| T12 | 15 | LDF7-50A (1-5/8 FOAM) | 60.00 - 80.00 | 0.6000 | 0.6000 |
| T12 | 16 | Fiber Cable (1/4") | 60.00 - 80.00 | 0.6000 | 0.6000 |
| T12 | 17 | DC Power | 60.00 - 80.00 | 0.6000 | 0.6000 |
| T12 | 19 | LDF7-50A (1-5/8 FOAM) | 60.00 - 80.00 | 0.6000 | 0.6000 |
| T12 | 21 | LDF7-50A (1-5/8 FOAM) | 60.00 - 80.00 | 0.6000 | 0.6000 |
| T12 | 22 | HCS 6X12 4AWG(1-5/8) | 60.00 - 80.00 | 0.6000 | 0.6000 |
| T13 | 1 | LDF7-50A (1-5/8 FOAM) | 40.00 - 60.00 | 0.6000 | 0.6000 |
| T13 | 3 | LDF7-50A (1-5/8 FOAM) | 40.00 - 60.00 | 0.6000 | 0.6000 |
| T13 | 6 | LDF7-50A (1-5/8 FOAM) | 40.00 - 60.00 | 0.6000 | 0.6000 |
| T13 | 8 | LDF7-50A (1-5/8 FOAM) | 40.00 - 60.00 | 0.6000 | 0.6000 |
| T13 | 10 | LDF7-50A (1-5/8 FOAM) | 40.00 - 60.00 | 0.6000 | 0.6000 |
| T13 | 12 | LDF7-50A (1-5/8 FOAM) | 40.00 - 60.00 | 0.6000 | 0.6000 |
| T13 | 13 | HCS 6X12 4AWG(1-5/8) | 40.00 - 60.00 | 0.6000 | 0.6000 |
| T13 | 15 | LDF7-50A (1-5/8 FOAM) | 40.00 - 60.00 | 0.6000 | 0.6000 |
| T13 | 16 | Fiber Cable (1/4") | 40.00 - 60.00 | 0.6000 | 0.6000 |
| T13 | 17 | DC Power | 40.00 - 60.00 | 0.6000 | 0.6000 |
| T13 | 19 | LDF7-50A (1-5/8 FOAM) | 40.00 - 60.00 | 0.6000 | 0.6000 |
| T13 | 21 | LDF7-50A (1-5/8 FOAM) | 40.00 - 60.00 | 0.6000 | 0.6000 |
| T13 | 22 | HCS 6X12 4AWG(1-5/8) | 40.00 - 60.00 | 0.6000 | 0.6000 |
| T14 | 1 | LDF7-50A (1-5/8 FOAM) | 20.00 - 40.00 | 0.6000 | 0.6000 |
| T14 | 3 | LDF7-50A (1-5/8 FOAM) | 20.00 - 40.00 | 0.6000 | 0.6000 |
| T14 | 6 | LDF7-50A (1-5/8 FOAM) | 20.00 - 40.00 | 0.6000 | 0.6000 |
| T14 | 8 | LDF7-50A (1-5/8 FOAM) | 20.00 - 40.00 | 0.6000 | 0.6000 |
| T14 | 10 | LDF7-50A (1-5/8 FOAM) | 20.00 - 40.00 | 0.6000 | 0.6000 |
| T14 | 12 | LDF7-50A (1-5/8 FOAM) | 20.00 - 40.00 | 0.6000 | 0.6000 |
| T14 | 13 | HCS 6X12 4AWG(1-5/8) | 20.00 - 40.00 | 0.6000 | 0.6000 |
| T14 | 15 | LDF7-50A (1-5/8 FOAM) | 20.00 - 40.00 | 0.6000 | 0.6000 |
| T14 | 16 | Fiber Cable (1/4") | 20.00 - 40.00 | 0.6000 | 0.6000 |

| | | |
|---|---|----------------------------------|
| tnxTower Network Building + Consulting 8601 Six Forks Road, Suite 540 Raleigh, NC 27615 Phone: 919.657.9131 FAX: | Job Woodbridge North CT | Page 14 of 52 |
| | Project NB+C ES Project Number 100765 | Date 14:34:37 12/14/20 |
| | Client Verizon | Designed by nsmith |

| Tower Section | Feed Line Record No. | Description | Feed Line Segment Elev. | K_a No Ice | K_a Ice |
|---------------|----------------------|-----------------------|-------------------------|--------------|-----------|
| T14 | 17 | DC Power | 20.00 - 40.00 | 0.6000 | 0.6000 |
| T14 | 19 | LDF7-50A (1-5/8 FOAM) | 20.00 - 40.00 | 0.6000 | 0.6000 |
| T14 | 21 | LDF7-50A (1-5/8 FOAM) | 20.00 - 40.00 | 0.6000 | 0.6000 |
| T14 | 22 | HCS 6X12 4AWG(1-5/8) | 20.00 - 40.00 | 0.6000 | 0.6000 |
| T15 | 1 | LDF7-50A (1-5/8 FOAM) | 12.00 - 20.00 | 0.6000 | 0.6000 |
| T15 | 3 | LDF7-50A (1-5/8 FOAM) | 12.00 - 20.00 | 0.6000 | 0.6000 |
| T15 | 4 | HCS 6X12 4AWG(1-5/8) | 0.00 - 12.00 | 0.6000 | 0.6000 |
| T15 | 6 | LDF7-50A (1-5/8 FOAM) | 12.00 - 20.00 | 0.6000 | 0.6000 |
| T15 | 8 | LDF7-50A (1-5/8 FOAM) | 12.00 - 20.00 | 0.6000 | 0.6000 |
| T15 | 10 | LDF7-50A (1-5/8 FOAM) | 12.00 - 20.00 | 0.6000 | 0.6000 |
| T15 | 12 | LDF7-50A (1-5/8 FOAM) | 12.00 - 20.00 | 0.6000 | 0.6000 |
| T15 | 13 | HCS 6X12 4AWG(1-5/8) | 12.00 - 20.00 | 0.6000 | 0.6000 |
| T15 | 15 | LDF7-50A (1-5/8 FOAM) | 12.00 - 20.00 | 0.6000 | 0.6000 |
| T15 | 16 | Fiber Cable (1/4") | 12.00 - 20.00 | 0.6000 | 0.6000 |
| T15 | 17 | DC Power | 12.00 - 20.00 | 0.6000 | 0.6000 |
| T15 | 19 | LDF7-50A (1-5/8 FOAM) | 12.00 - 20.00 | 0.6000 | 0.6000 |
| T15 | 21 | LDF7-50A (1-5/8 FOAM) | 12.00 - 20.00 | 0.6000 | 0.6000 |
| T15 | 22 | HCS 6X12 4AWG(1-5/8) | 12.00 - 20.00 | 0.6000 | 0.6000 |

Discrete Tower Loads

| Description | Face or Leg | Offset Type | Offsets: Horz Lateral Vert ft ft ft | Azimuth Adjustment ° | Placement ft | C_{AA} Front ft ² | C_{AA} Side ft ² | Weight K |
|------------------------------------|-------------|-------------|--|-------------------------|-----------------|-----------------------------------|----------------------------------|-------------|
| Beacon | B | None | | 0.0000 | 280.00 | No Ice | 2.70 | 0.05 |
| | | | | | | 1/2" Ice | 3.10 | 0.07 |
| | | | | | | 1" Ice | 3.50 | 0.09 |
| Lightning Rod 5/8x6' | B | None | | 0.0000 | 280.00 | No Ice | 0.38 | 0.05 |
| | | | | | | 1/2" Ice | 0.99 | 0.05 |
| | | | | | | 1" Ice | 1.60 | 0.05 |
| *** | | | | | | | | |
| DB420-A | B | From Leg | 8.00 0.00 0.00 | 0.0000 | 280.00 | No Ice | 3.33 | 0.03 |
| | | | | | | 1/2" Ice | 5.99 | 0.04 |
| | | | | | | 1" Ice | 8.66 | 0.05 |
| DB586-XC | B | From Leg | 8.00 0.00 0.00 | 0.0000 | 280.00 | No Ice | 1.01 | 0.01 |
| | | | | | | 1/2" Ice | 1.28 | 0.02 |
| | | | | | | 1" Ice | 1.56 | 0.03 |
| Sector Mount [SM 412-1] | C | None | | 0.0000 | 280.00 | No Ice | 70.47 | 3.08 |
| | | | | | | 1/2" Ice | 100.14 | 4.50 |
| | | | | | | 1" Ice | 129.81 | 5.92 |
| *** | | | | | | | | |
| APXVAARR24_43-U-NA20 w/ Mount Pipe | A | From Leg | 3.00 0.00 0.00 | 0.0000 | 250.00 | No Ice | 14.69 | 0.19 |
| | | | | | | 1/2" Ice | 15.46 | 0.31 |
| | | | | | | 1" Ice | 16.23 | 0.46 |
| APXVAARR24_43-U-NA20 w/ Mount Pipe | B | From Leg | 3.00 0.00 0.00 | 0.0000 | 250.00 | No Ice | 14.69 | 0.19 |
| | | | | | | 1/2" Ice | 15.46 | 0.31 |
| | | | | | | 1" Ice | 16.23 | 0.46 |
| APXVAARR24_43-U-NA20 w/ Mount Pipe | C | From Leg | 3.00 0.00 0.00 | 0.0000 | 250.00 | No Ice | 14.69 | 0.19 |
| | | | | | | 1/2" Ice | 15.46 | 0.31 |
| | | | | | | 1" Ice | 16.23 | 0.46 |
| AIR 32 B66A/B2A w/ Mount | A | From Leg | 3.00 | 0.0000 | 250.00 | No Ice | 6.81 | 0.15 |

| | | | | |
|---|----------------|-------------------------------|--------------------|-------------------|
| tnxTower Network Building + Consulting 8601 Six Forks Road, Suite 540 Raleigh, NC 27615 Phone: 919.657.9131 FAX: | Job | Woodbridge North CT | Page | 15 of 52 |
| | Project | NB+C ES Project Number 100765 | Date | 14:34:37 12/14/20 |
| | Client | Verizon | Designed by | nsmith |

| Description | Face or Leg | Offset Type | Offsets: Horz Lateral Vert ft ft ft | Azimuth Adjustment ° | Placement ft | C _{AA} Front ft ² | C _{AA} Side ft ² | Weight K |
|--------------------------------|-------------|-------------|--|-------------------------|-----------------|---|--|-------------|
| Pipe | | | 0.00 | | | 1/2" Ice 7.30 | 6.99 | 0.22 |
| | | | 0.00 | | | 1" Ice 7.76 | 7.73 | 0.28 |
| AIR 32 B66A/B2A w/ Mount Pipe | B | From Leg | 3.00 | 0.0000 | 250.00 | No Ice 6.81 | 6.14 | 0.15 |
| | | | 0.00 | | | 1/2" Ice 7.30 | 6.99 | 0.22 |
| | | | 0.00 | | | 1" Ice 7.76 | 7.73 | 0.28 |
| AIR 32 B66A/B2A w/ Mount Pipe | C | From Leg | 3.00 | 0.0000 | 250.00 | No Ice 6.81 | 6.14 | 0.15 |
| | | | 0.00 | | | 1/2" Ice 7.30 | 6.99 | 0.22 |
| | | | 0.00 | | | 1" Ice 7.76 | 7.73 | 0.28 |
| AIR 6468 B41 w/ Mount Pipe | A | From Leg | 3.00 | 0.0000 | 250.00 | No Ice 6.26 | 3.61 | 0.15 |
| | | | 0.00 | | | 1/2" Ice 6.65 | 4.10 | 0.20 |
| | | | 0.00 | | | 1" Ice 7.05 | 4.61 | 0.26 |
| AIR 6468 B41 w/ Mount Pipe | B | From Leg | 3.00 | 0.0000 | 250.00 | No Ice 6.26 | 3.61 | 0.15 |
| | | | 0.00 | | | 1/2" Ice 6.65 | 4.10 | 0.20 |
| | | | 0.00 | | | 1" Ice 7.05 | 4.61 | 0.26 |
| AIR 6468 B41 w/ Mount Pipe | C | From Leg | 3.00 | 0.0000 | 250.00 | No Ice 6.26 | 3.61 | 0.15 |
| | | | 0.00 | | | 1/2" Ice 6.65 | 4.10 | 0.20 |
| | | | 0.00 | | | 1" Ice 7.05 | 4.61 | 0.26 |
| RADIO 4449 B12/B71 | A | From Leg | 3.00 | 0.0000 | 250.00 | No Ice 1.64 | 1.15 | 0.08 |
| | | | 0.00 | | | 1/2" Ice 1.80 | 1.29 | 0.09 |
| | | | 0.00 | | | 1" Ice 1.97 | 1.44 | 0.11 |
| RADIO 4449 B12/B71 | B | From Leg | 3.00 | 0.0000 | 250.00 | No Ice 1.64 | 1.15 | 0.08 |
| | | | 0.00 | | | 1/2" Ice 1.80 | 1.29 | 0.09 |
| | | | 0.00 | | | 1" Ice 1.97 | 1.44 | 0.11 |
| RADIO 4449 B12/B71 | C | From Leg | 3.00 | 0.0000 | 250.00 | No Ice 1.64 | 1.15 | 0.08 |
| | | | 0.00 | | | 1/2" Ice 1.80 | 1.29 | 0.09 |
| | | | 0.00 | | | 1" Ice 1.97 | 1.44 | 0.11 |
| RADIO 4415 B25 | A | From Leg | 3.00 | 0.0000 | 250.00 | No Ice 1.84 | 0.82 | 0.05 |
| | | | 0.00 | | | 1/2" Ice 2.01 | 0.94 | 0.06 |
| | | | 0.00 | | | 1" Ice 2.19 | 1.07 | 0.08 |
| RADIO 4415 B25 | B | From Leg | 3.00 | 0.0000 | 250.00 | No Ice 1.84 | 0.82 | 0.05 |
| | | | 0.00 | | | 1/2" Ice 2.01 | 0.94 | 0.06 |
| | | | 0.00 | | | 1" Ice 2.19 | 1.07 | 0.08 |
| RADIO 4415 B25 | C | From Leg | 3.00 | 0.0000 | 250.00 | No Ice 1.84 | 0.82 | 0.05 |
| | | | 0.00 | | | 1/2" Ice 2.01 | 0.94 | 0.06 |
| | | | 0.00 | | | 1" Ice 2.19 | 1.07 | 0.08 |
| Sector Mount [SM 408-3] | C | None | | 0.0000 | 250.00 | No Ice 22.45 | 22.45 | 1.02 |
| | | | | | | 1/2" Ice 33.50 | 33.50 | 1.47 |
| | | | | | | 1" Ice 44.55 | 44.55 | 1.93 |
| *** | | | | | | | | |
| Sector Mount [SM 412-1] | A | None | | 0.0000 | 235.00 | No Ice 70.47 | 70.47 | 3.08 |
| | | | | | | 1/2" Ice 100.14 | 100.14 | 4.50 |
| | | | | | | 1" Ice 129.81 | 129.81 | 5.92 |
| DB420-A | B | From Leg | 8.00 | 0.0000 | 235.00 | No Ice 3.33 | 3.33 | 0.03 |
| | | | 0.00 | | | 1/2" Ice 5.99 | 5.99 | 0.04 |
| | | | 9.00 | | | 1" Ice 8.66 | 8.66 | 0.05 |
| DB586-XC | A | From Leg | 8.00 | 0.0000 | 235.00 | No Ice 1.01 | 1.01 | 0.01 |
| | | | 0.00 | | | 1/2" Ice 1.28 | 1.28 | 0.02 |
| | | | 0.00 | | | 1" Ice 1.56 | 1.56 | 0.03 |
| *** | | | | | | | | |
| (3) DB980H120E-M w/ Mount Pipe | A | From Leg | 3.00 | 0.0000 | 200.00 | No Ice 3.99 | 3.60 | 0.03 |
| | | | 0.00 | | | 1/2" Ice 4.45 | 4.46 | 0.07 |
| | | | 0.00 | | | 1" Ice 4.90 | 5.19 | 0.11 |
| (3) DB980H120E-M w/ Mount Pipe | B | From Leg | 3.00 | 0.0000 | 200.00 | No Ice 3.99 | 3.60 | 0.03 |
| | | | 0.00 | | | 1/2" Ice 4.45 | 4.46 | 0.07 |
| | | | 0.00 | | | 1" Ice 4.90 | 5.19 | 0.11 |
| (3) DB980H120E-M w/ Mount Pipe | C | From Leg | 3.00 | 0.0000 | 200.00 | No Ice 3.99 | 3.60 | 0.03 |
| | | | 0.00 | | | 1/2" Ice 4.45 | 4.46 | 0.07 |

| | | | | |
|---|----------------|-------------------------------|--------------------|-------------------|
| tnxTower Network Building + Consulting 8601 Six Forks Road, Suite 540 Raleigh, NC 27615 Phone: 919.657.9131 FAX: | Job | Woodbridge North CT | Page | 16 of 52 |
| | Project | NB+C ES Project Number 100765 | Date | 14:34:37 12/14/20 |
| | Client | Verizon | Designed by | nsmith |

| Description | Face or Leg | Offset Type | Offsets: | | Azimuth Adjustment | Placement | C _{AA} Front | C _{AA} Side | Weight |
|--------------------------------|-------------|-------------|----------------------|---------|--------------------|--|---|---------------------------------|------------------------------|
| | | | Horz | Lateral | | | | | |
| | | | ft | ft | ° | ft | ft ² | ft ² | K |
| Sector Mount [SM 405-3] | A | None | | 0.00 | 0.0000 | 200.00 | 1" Ice 4.90 No Ice 18.73 1/2" Ice 27.19 1" Ice 35.65 | 5.19 18.73 27.19 35.65 | 0.11 0.86 1.26 1.66 |
| *** | | | | | | | | | |
| (3) DB980H120E-M w/ Mount Pipe | A | From Leg | 3.00 0.00 0.00 | 0.0000 | 190.00 | No Ice 3.99 1/2" Ice 4.45 1" Ice 4.90 | 3.60 4.46 5.19 | 0.03 0.07 0.11 | |
| (3) DB980H120E-M w/ Mount Pipe | B | From Leg | 3.00 0.00 0.00 | 0.0000 | 190.00 | No Ice 3.99 1/2" Ice 4.45 1" Ice 4.90 | 3.60 4.46 5.19 | 0.03 0.07 0.11 | |
| (3) DB980H120E-M w/ Mount Pipe | C | From Leg | 3.00 0.00 0.00 | 0.0000 | 190.00 | No Ice 3.99 1/2" Ice 4.45 1" Ice 4.90 | 3.60 4.46 5.19 | 0.03 0.07 0.11 | |
| Sector Mount [SM 405-3] | A | None | | 0.0000 | 190.00 | No Ice 18.73 1/2" Ice 27.19 1" Ice 35.65 | 18.73 27.19 35.65 | 0.86 1.26 1.66 | |
| *** | | | | | | | | | |
| (3) DB980H120E-M w/ Mount Pipe | A | From Leg | 3.00 0.00 0.00 | 0.0000 | 180.00 | No Ice 3.99 1/2" Ice 4.45 1" Ice 4.90 | 3.60 4.46 5.19 | 0.03 0.07 0.11 | |
| (3) DB980H120E-M w/ Mount Pipe | B | From Leg | 3.00 0.00 0.00 | 0.0000 | 180.00 | No Ice 3.99 1/2" Ice 4.45 1" Ice 4.90 | 3.60 4.46 5.19 | 0.03 0.07 0.11 | |
| (3) DB980H120E-M w/ Mount Pipe | C | From Leg | 3.00 0.00 0.00 | 0.0000 | 180.00 | No Ice 3.99 1/2" Ice 4.45 1" Ice 4.90 | 3.60 4.46 5.19 | 0.03 0.07 0.11 | |
| Sector Mount [SM 405-3] | A | None | | 0.0000 | 180.00 | No Ice 18.73 1/2" Ice 27.19 1" Ice 35.65 | 18.73 27.19 35.65 | 0.86 1.26 1.66 | |
| *** | | | | | | | | | |
| APXVSPP18-C-A20 w/ Mount Pipe | A | From Leg | 3.00 0.00 0.00 | 0.0000 | 170.00 | No Ice 4.60 1/2" Ice 5.05 1" Ice 5.50 | 4.01 4.45 4.89 | 0.10 0.16 0.23 | |
| APXVSPP18-C-A20 w/ Mount Pipe | B | From Leg | 3.00 0.00 0.00 | 0.0000 | 170.00 | No Ice 4.60 1/2" Ice 5.05 1" Ice 5.50 | 4.01 4.45 4.89 | 0.10 0.16 0.23 | |
| APXVSPP18-C-A20 w/ Mount Pipe | C | From Leg | 3.00 0.00 0.00 | 0.0000 | 170.00 | No Ice 4.60 1/2" Ice 5.05 1" Ice 5.50 | 4.01 4.45 4.89 | 0.10 0.16 0.23 | |
| APXVTM14-C-120 w/ Mount Pipe | A | From Leg | 3.00 0.00 0.00 | 0.0000 | 170.00 | No Ice 4.09 1/2" Ice 4.48 1" Ice 4.88 | 2.86 3.23 3.61 | 0.08 0.13 0.19 | |
| APXVTM14-C-120 w/ Mount Pipe | B | From Leg | 3.00 0.00 0.00 | 0.0000 | 170.00 | No Ice 4.09 1/2" Ice 4.48 1" Ice 4.88 | 2.86 3.23 3.61 | 0.08 0.13 0.19 | |
| APXVTM14-C-120 w/ Mount Pipe | C | From Leg | 3.00 0.00 0.00 | 0.0000 | 170.00 | No Ice 4.09 1/2" Ice 4.48 1" Ice 4.88 | 2.86 3.23 3.61 | 0.08 0.13 0.19 | |
| FD-RRH-2x50-800 | A | From Leg | 3.00 0.00 0.00 | 0.0000 | 170.00 | No Ice 2.13 1/2" Ice 2.32 1" Ice 2.51 | 2.49 2.68 2.89 | 0.06 0.09 0.12 | |
| FD-RRH-2x50-800 | B | From Leg | 3.00 0.00 0.00 | 0.0000 | 170.00 | No Ice 2.13 1/2" Ice 2.32 1" Ice 2.51 | 2.49 2.68 2.89 | 0.06 0.09 0.12 | |
| FD-RRH-2x50-800 | C | From Leg | 3.00 0.00 0.00 | 0.0000 | 170.00 | No Ice 2.13 1/2" Ice 2.32 | 2.49 2.68 | 0.06 0.09 | |

| | | | | |
|---|----------------|-------------------------------|--------------------|-------------------|
| tnxTower Network Building + Consulting 8601 Six Forks Road, Suite 540 Raleigh, NC 27615 Phone: 919.657.9131 FAX: | Job | Woodbridge North CT | Page | 17 of 52 |
| | Project | NB+C ES Project Number 100765 | Date | 14:34:37 12/14/20 |
| | Client | Verizon | Designed by | nsmith |

| Description | Face or Leg | Offset Type | Offsets: | | Azimuth Adjustment | Placement | C _{AA} Front | C _{AA} Side | Weight | |
|---------------------------|-------------|-------------|----------|---------|--------------------|-----------|-----------------------|----------------------|--------|------|
| | | | Horz | Lateral | | | | | | |
| | | | ft | ft | ° | ft | ft ² | ft ² | K | |
| 1900MHZ 4X40W RRH | A | From Leg | 0.00 | | 0.0000 | 170.00 | 1" Ice | 2.51 | 2.89 | 0.12 |
| | | | 3.00 | | | | No Ice | 2.32 | 2.24 | 0.06 |
| | | | 0.00 | | | | 1/2" Ice | 2.53 | 2.44 | 0.08 |
| | | | 0.00 | | | | 1" Ice | 2.74 | 2.65 | 0.11 |
| 1900MHZ 4X40W RRH | B | From Leg | 3.00 | | 0.0000 | 170.00 | No Ice | 2.32 | 2.24 | 0.06 |
| | | | 0.00 | | | | 1/2" Ice | 2.53 | 2.44 | 0.08 |
| | | | 0.00 | | | | 1" Ice | 2.74 | 2.65 | 0.11 |
| | | | 0.00 | | | | No Ice | 2.32 | 2.24 | 0.06 |
| 1900MHZ 4X40W RRH | C | From Leg | 3.00 | | 0.0000 | 170.00 | 1/2" Ice | 2.53 | 2.44 | 0.08 |
| | | | 0.00 | | | | 1" Ice | 2.74 | 2.65 | 0.11 |
| | | | 0.00 | | | | No Ice | 2.32 | 2.24 | 0.06 |
| | | | 0.00 | | | | 1/2" Ice | 2.53 | 2.44 | 0.08 |
| TD-RRH8X20-25 | A | From Leg | 3.00 | | 0.0000 | 170.00 | 1" Ice | 2.74 | 2.65 | 0.11 |
| | | | 0.00 | | | | No Ice | 3.70 | 1.29 | 0.07 |
| | | | 0.00 | | | | 1/2" Ice | 3.95 | 1.46 | 0.09 |
| | | | 0.00 | | | | 1" Ice | 4.20 | 1.64 | 0.12 |
| TD-RRH8X20-25 | B | From Leg | 3.00 | | 0.0000 | 170.00 | No Ice | 3.70 | 1.29 | 0.07 |
| | | | 0.00 | | | | 1/2" Ice | 3.95 | 1.46 | 0.09 |
| | | | 0.00 | | | | 1" Ice | 4.20 | 1.64 | 0.12 |
| | | | 0.00 | | | | No Ice | 3.70 | 1.29 | 0.07 |
| TD-RRH8X20-25 | C | From Leg | 3.00 | | 0.0000 | 170.00 | 1/2" Ice | 3.95 | 1.46 | 0.09 |
| | | | 0.00 | | | | 1" Ice | 4.20 | 1.64 | 0.12 |
| | | | 0.00 | | | | No Ice | 3.70 | 1.29 | 0.07 |
| | | | 0.00 | | | | 1/2" Ice | 3.95 | 1.46 | 0.09 |
| Sector Mount [SM 408-3] | C | None | | | 0.0000 | 170.00 | 1" Ice | 4.20 | 1.64 | 0.12 |
| | | | | | | | No Ice | 22.45 | 22.45 | 1.02 |
| | | | | | | | 1/2" Ice | 33.50 | 33.50 | 1.47 |
| | | | | | | | 1" Ice | 44.55 | 44.55 | 1.93 |
| *** | | | | | | | | | | |
| 800 10121 w/ Mount Pipe | A | From Leg | 3.00 | | 0.0000 | 160.00 | No Ice | 3.60 | 2.95 | 0.07 |
| | | | 0.00 | | | | 1/2" Ice | 4.00 | 3.34 | 0.11 |
| | | | 0.00 | | | | 1" Ice | 4.42 | 3.74 | 0.17 |
| | | | 0.00 | | | | No Ice | 3.60 | 2.95 | 0.07 |
| 800 10121 w/ Mount Pipe | B | From Leg | 3.00 | | 0.0000 | 160.00 | 1/2" Ice | 4.00 | 3.34 | 0.11 |
| | | | 0.00 | | | | 1" Ice | 4.42 | 3.74 | 0.17 |
| | | | 0.00 | | | | No Ice | 3.60 | 2.95 | 0.07 |
| | | | 0.00 | | | | 1/2" Ice | 4.00 | 3.34 | 0.11 |
| 800 10121 w/ Mount Pipe | C | From Leg | 3.00 | | 0.0000 | 160.00 | 1" Ice | 4.42 | 3.74 | 0.17 |
| | | | 0.00 | | | | No Ice | 3.60 | 2.95 | 0.07 |
| | | | 0.00 | | | | 1/2" Ice | 4.00 | 3.34 | 0.11 |
| | | | 0.00 | | | | 1" Ice | 4.42 | 3.74 | 0.17 |
| HPA65R-BU6A w/ Mount Pipe | A | From Leg | 3.00 | | 0.0000 | 160.00 | No Ice | 5.83 | 5.00 | 0.08 |
| | | | 0.00 | | | | 1/2" Ice | 6.40 | 5.56 | 0.14 |
| | | | 0.00 | | | | 1" Ice | 6.99 | 6.13 | 0.22 |
| | | | 0.00 | | | | No Ice | 5.83 | 5.00 | 0.08 |
| HPA65R-BU6A w/ Mount Pipe | B | From Leg | 3.00 | | 0.0000 | 160.00 | 1/2" Ice | 6.40 | 5.56 | 0.14 |
| | | | 0.00 | | | | 1" Ice | 6.99 | 6.13 | 0.22 |
| | | | 0.00 | | | | No Ice | 5.83 | 5.00 | 0.08 |
| | | | 0.00 | | | | 1/2" Ice | 6.40 | 5.56 | 0.14 |
| HPA65R-BU6A w/ Mount Pipe | C | From Leg | 3.00 | | 0.0000 | 160.00 | 1" Ice | 6.99 | 6.13 | 0.22 |
| | | | 0.00 | | | | No Ice | 5.83 | 5.00 | 0.08 |
| | | | 0.00 | | | | 1/2" Ice | 6.40 | 5.56 | 0.14 |
| | | | 0.00 | | | | 1" Ice | 6.99 | 6.13 | 0.22 |
| QS66512-3 w/ Mount Pipe | A | From Leg | 3.00 | | 0.0000 | 160.00 | No Ice | 4.04 | 4.18 | 0.13 |
| | | | 0.00 | | | | 1/2" Ice | 4.42 | 4.57 | 0.20 |
| | | | 0.00 | | | | 1" Ice | 4.82 | 4.97 | 0.28 |
| | | | 0.00 | | | | No Ice | 4.04 | 4.18 | 0.13 |
| QS66512-3 w/ Mount Pipe | B | From Leg | 3.00 | | 0.0000 | 160.00 | 1/2" Ice | 4.42 | 4.57 | 0.20 |
| | | | 0.00 | | | | 1" Ice | 4.82 | 4.97 | 0.28 |
| | | | 0.00 | | | | No Ice | 4.04 | 4.18 | 0.13 |
| | | | 0.00 | | | | 1/2" Ice | 4.42 | 4.57 | 0.20 |
| QS66512-3 w/ Mount Pipe | C | From Leg | 3.00 | | 0.0000 | 160.00 | 1" Ice | 4.82 | 4.97 | 0.28 |
| | | | 0.00 | | | | No Ice | 4.04 | 4.18 | 0.13 |
| | | | 0.00 | | | | 1/2" Ice | 4.42 | 4.57 | 0.20 |
| | | | 0.00 | | | | 1" Ice | 4.82 | 4.97 | 0.28 |
| RRUS 11 | A | From Leg | 3.00 | | 0.0000 | 160.00 | No Ice | 2.79 | 1.19 | 0.05 |
| | | | 0.00 | | | | 1/2" Ice | 3.00 | 1.34 | 0.07 |
| | | | 0.00 | | | | 1" Ice | 3.21 | 1.50 | 0.10 |
| | | | 0.00 | | | | No Ice | 2.79 | 1.19 | 0.05 |
| RRUS 11 | B | From Leg | 3.00 | | 0.0000 | 160.00 | 1/2" Ice | 3.00 | 1.34 | 0.07 |
| | | | 0.00 | | | | 1" Ice | 3.21 | 1.50 | 0.10 |
| | | | 0.00 | | | | No Ice | 2.79 | 1.19 | 0.05 |
| | | | 0.00 | | | | 1/2" Ice | 3.00 | 1.34 | 0.07 |
| RRUS 11 | C | From Leg | 3.00 | | 0.0000 | 160.00 | 1" Ice | 3.21 | 1.50 | 0.10 |
| | | | 0.00 | | | | No Ice | 2.79 | 1.19 | 0.05 |
| | | | 0.00 | | | | 1/2" Ice | 3.00 | 1.34 | 0.07 |
| | | | 0.00 | | | | 1" Ice | 3.21 | 1.50 | 0.10 |

| | | | | |
|---|----------------|-------------------------------|--------------------|-------------------|
| tnxTower Network Building + Consulting 8601 Six Forks Road, Suite 540 Raleigh, NC 27615 Phone: 919.657.9131 FAX: | Job | Woodbridge North CT | Page | 18 of 52 |
| | Project | NB+C ES Project Number 100765 | Date | 14:34:37 12/14/20 |
| | Client | Verizon | Designed by | nsmith |

| Description | Face or Leg | Offset Type | Offsets: | | Azimuth Adjustment | Placement | C _{AA} Front | C _{AA} Side | Weight | |
|-----------------|-------------|-------------|----------|---------|--------------------|-----------|-----------------------|----------------------|--------|------|
| | | | Horz | Lateral | | | | | | Vert |
| | | | 0.00 | | | | 1/2" Ice | 3.00 | 1.34 | 0.07 |
| | | | 0.00 | | | | 1" Ice | 3.21 | 1.50 | 0.10 |
| RRUS 32 | A | From Leg | 3.00 | 0.0000 | 160.00 | | No Ice | 2.86 | 1.78 | 0.06 |
| | | | 0.00 | | | | 1/2" Ice | 3.08 | 1.97 | 0.08 |
| | | | 0.00 | | | | 1" Ice | 3.32 | 2.17 | 0.10 |
| RRUS 32 | B | From Leg | 3.00 | 0.0000 | 160.00 | | No Ice | 2.86 | 1.78 | 0.06 |
| | | | 0.00 | | | | 1/2" Ice | 3.08 | 1.97 | 0.08 |
| | | | 0.00 | | | | 1" Ice | 3.32 | 2.17 | 0.10 |
| RRUS 32 | C | From Leg | 3.00 | 0.0000 | 160.00 | | No Ice | 2.86 | 1.78 | 0.06 |
| | | | 0.00 | | | | 1/2" Ice | 3.08 | 1.97 | 0.08 |
| | | | 0.00 | | | | 1" Ice | 3.32 | 2.17 | 0.10 |
| RRUS 32 B2 | A | From Leg | 3.00 | 0.0000 | 160.00 | | No Ice | 2.73 | 1.67 | 0.05 |
| | | | 0.00 | | | | 1/2" Ice | 2.95 | 1.86 | 0.07 |
| | | | 0.00 | | | | 1" Ice | 3.18 | 2.05 | 0.10 |
| RRUS 32 B2 | B | From Leg | 3.00 | 0.0000 | 160.00 | | No Ice | 2.73 | 1.67 | 0.05 |
| | | | 0.00 | | | | 1/2" Ice | 2.95 | 1.86 | 0.07 |
| | | | 0.00 | | | | 1" Ice | 3.18 | 2.05 | 0.10 |
| RRUS 32 B2 | C | From Leg | 3.00 | 0.0000 | 160.00 | | No Ice | 2.73 | 1.67 | 0.05 |
| | | | 0.00 | | | | 1/2" Ice | 2.95 | 1.86 | 0.07 |
| | | | 0.00 | | | | 1" Ice | 3.18 | 2.05 | 0.10 |
| RRUS 4478 B5 | A | From Leg | 3.00 | 0.0000 | 160.00 | | No Ice | 1.84 | 1.06 | 0.06 |
| | | | 0.00 | | | | 1/2" Ice | 2.01 | 1.20 | 0.08 |
| | | | 0.00 | | | | 1" Ice | 2.19 | 1.34 | 0.09 |
| RRUS 4478 B5 | B | From Leg | 3.00 | 0.0000 | 160.00 | | No Ice | 1.84 | 1.06 | 0.06 |
| | | | 0.00 | | | | 1/2" Ice | 2.01 | 1.20 | 0.08 |
| | | | 0.00 | | | | 1" Ice | 2.19 | 1.34 | 0.09 |
| RRUS 4478 B5 | C | From Leg | 3.00 | 0.0000 | 160.00 | | No Ice | 1.84 | 1.06 | 0.06 |
| | | | 0.00 | | | | 1/2" Ice | 2.01 | 1.20 | 0.08 |
| | | | 0.00 | | | | 1" Ice | 2.19 | 1.34 | 0.09 |
| RRUS 4478 B14 | A | From Leg | 3.00 | 0.0000 | 160.00 | | No Ice | 1.84 | 1.06 | 0.06 |
| | | | 0.00 | | | | 1/2" Ice | 2.01 | 1.20 | 0.08 |
| | | | 0.00 | | | | 1" Ice | 2.19 | 1.34 | 0.09 |
| RRUS 4478 B14 | B | From Leg | 3.00 | 0.0000 | 160.00 | | No Ice | 1.84 | 1.06 | 0.06 |
| | | | 0.00 | | | | 1/2" Ice | 2.01 | 1.20 | 0.08 |
| | | | 0.00 | | | | 1" Ice | 2.19 | 1.34 | 0.09 |
| RRUS 4478 B14 | C | From Leg | 3.00 | 0.0000 | 160.00 | | No Ice | 1.84 | 1.06 | 0.06 |
| | | | 0.00 | | | | 1/2" Ice | 2.01 | 1.20 | 0.08 |
| | | | 0.00 | | | | 1" Ice | 2.19 | 1.34 | 0.09 |
| RRUS 4426 B66 | A | From Leg | 3.00 | 0.0000 | 160.00 | | No Ice | 1.64 | 0.73 | 0.05 |
| | | | 0.00 | | | | 1/2" Ice | 1.80 | 0.84 | 0.06 |
| | | | 0.00 | | | | 1" Ice | 1.97 | 0.97 | 0.08 |
| RRUS 4426 B66 | B | From Leg | 3.00 | 0.0000 | 160.00 | | No Ice | 1.64 | 0.73 | 0.05 |
| | | | 0.00 | | | | 1/2" Ice | 1.80 | 0.84 | 0.06 |
| | | | 0.00 | | | | 1" Ice | 1.97 | 0.97 | 0.08 |
| RRUS 4426 B66 | C | From Leg | 3.00 | 0.0000 | 160.00 | | No Ice | 1.64 | 0.73 | 0.05 |
| | | | 0.00 | | | | 1/2" Ice | 1.80 | 0.84 | 0.06 |
| | | | 0.00 | | | | 1" Ice | 1.97 | 0.97 | 0.08 |
| (2) LGP21401 | A | From Leg | 3.00 | 0.0000 | 160.00 | | No Ice | 1.10 | 0.21 | 0.01 |
| | | | 0.00 | | | | 1/2" Ice | 1.24 | 0.27 | 0.02 |
| | | | 0.00 | | | | 1" Ice | 1.38 | 0.35 | 0.03 |
| (2) LGP21401 | B | From Leg | 3.00 | 0.0000 | 160.00 | | No Ice | 1.10 | 0.21 | 0.01 |
| | | | 0.00 | | | | 1/2" Ice | 1.24 | 0.27 | 0.02 |
| | | | 0.00 | | | | 1" Ice | 1.38 | 0.35 | 0.03 |
| (2) LGP21401 | C | From Leg | 3.00 | 0.0000 | 160.00 | | No Ice | 1.10 | 0.21 | 0.01 |
| | | | 0.00 | | | | 1/2" Ice | 1.24 | 0.27 | 0.02 |
| | | | 0.00 | | | | 1" Ice | 1.38 | 0.35 | 0.03 |
| DC6-48-60-18-8F | A | From Leg | 3.00 | 0.0000 | 160.00 | | No Ice | 1.21 | 1.21 | 0.03 |

| | | | | |
|---|----------------|-------------------------------|--------------------|-------------------|
| tnxTower Network Building + Consulting 8601 Six Forks Road, Suite 540 Raleigh, NC 27615 Phone: 919.657.9131 FAX: | Job | Woodbridge North CT | Page | 19 of 52 |
| | Project | NB+C ES Project Number 100765 | Date | 14:34:37 12/14/20 |
| | Client | Verizon | Designed by | nsmith |

| Description | Face or Leg | Offset Type | Offsets: | | Azimuth Adjustment | Placement | C _{AA} Front | C _{AA} Side | Weight |
|---------------------------------|-------------|-------------|----------|---------|--------------------|-----------|-----------------------|----------------------|--------|
| | | | Horz | Lateral | | | | | |
| | | | 0.00 | | | 1/2" Ice | 1.89 | 1.89 | 0.05 |
| | | | 0.00 | | | 1" Ice | 2.11 | 2.11 | 0.08 |
| DC6-48-60-18-8F | B | From Leg | 3.00 | 0.0000 | 160.00 | No Ice | 1.21 | 1.21 | 0.03 |
| | | | 0.00 | | | 1/2" Ice | 1.89 | 1.89 | 0.05 |
| | | | 0.00 | | | 1" Ice | 2.11 | 2.11 | 0.08 |
| DC6-48-60-18-8F | C | From Leg | 3.00 | 0.0000 | 160.00 | No Ice | 1.21 | 1.21 | 0.03 |
| | | | 0.00 | | | 1/2" Ice | 1.89 | 1.89 | 0.05 |
| | | | 0.00 | | | 1" Ice | 2.11 | 2.11 | 0.08 |
| Sector Mount [SM 408-3] | C | None | | 0.0000 | 160.00 | No Ice | 22.45 | 22.45 | 1.02 |
| | | | | | | 1/2" Ice | 33.50 | 33.50 | 1.47 |
| | | | | | | 1" Ice | 44.55 | 44.55 | 1.93 |
| *** | | | | | | | | | |
| APXV18-206517S-C w/ Mount Pipe | A | From Leg | 3.00 | 0.0000 | 150.00 | No Ice | 3.79 | 3.16 | 0.05 |
| | | | 0.00 | | | 1/2" Ice | 4.38 | 3.75 | 0.09 |
| | | | 0.00 | | | 1" Ice | 4.99 | 4.35 | 0.15 |
| APXV18-206517S-C w/ Mount Pipe | B | From Leg | 3.00 | 0.0000 | 150.00 | No Ice | 3.79 | 3.16 | 0.05 |
| | | | 0.00 | | | 1/2" Ice | 4.38 | 3.75 | 0.09 |
| | | | 0.00 | | | 1" Ice | 4.99 | 4.35 | 0.15 |
| APXV18-206517S-C w/ Mount Pipe | C | From Leg | 3.00 | 0.0000 | 150.00 | No Ice | 3.79 | 3.16 | 0.05 |
| | | | 0.00 | | | 1/2" Ice | 4.38 | 3.75 | 0.09 |
| | | | 0.00 | | | 1" Ice | 4.99 | 4.35 | 0.15 |
| Sector Mount [SM 406-3] | C | None | | 0.0000 | 150.00 | No Ice | 19.83 | 19.83 | 0.92 |
| | | | | | | 1/2" Ice | 29.41 | 29.41 | 1.33 |
| | | | | | | 1" Ice | 38.99 | 38.99 | 1.73 |
| *** | | | | | | | | | |
| (2) MX06FRO660-03 w/ Mount Pipe | A | From Leg | 3.00 | 0.0000 | 140.00 | No Ice | 6.54 | 5.55 | 0.10 |
| | | | 0.00 | | | 1/2" Ice | 7.06 | 6.05 | 0.18 |
| | | | 0.00 | | | 1" Ice | 7.60 | 6.57 | 0.28 |
| (2) MX06FRO660-03 w/ Mount Pipe | B | From Leg | 3.00 | 0.0000 | 140.00 | No Ice | 6.54 | 5.55 | 0.10 |
| | | | 0.00 | | | 1/2" Ice | 7.06 | 6.05 | 0.18 |
| | | | 0.00 | | | 1" Ice | 7.60 | 6.57 | 0.28 |
| (2) MX06FRO660-03 w/ Mount Pipe | C | From Leg | 3.00 | 0.0000 | 140.00 | No Ice | 6.54 | 5.55 | 0.10 |
| | | | 0.00 | | | 1/2" Ice | 7.06 | 6.05 | 0.18 |
| | | | 0.00 | | | 1" Ice | 7.60 | 6.57 | 0.28 |
| L-Sub6 Antenna w/ Mount Pipe | A | From Leg | 3.00 | 0.0000 | 140.00 | No Ice | 5.43 | 3.27 | 0.11 |
| | | | 0.00 | | | 1/2" Ice | 5.97 | 3.99 | 0.15 |
| | | | 0.00 | | | 1" Ice | 6.46 | 4.59 | 0.20 |
| L-Sub6 Antenna w/ Mount Pipe | B | From Leg | 3.00 | 0.0000 | 140.00 | No Ice | 5.43 | 3.27 | 0.11 |
| | | | 0.00 | | | 1/2" Ice | 5.97 | 3.99 | 0.15 |
| | | | 0.00 | | | 1" Ice | 6.46 | 4.59 | 0.20 |
| L-Sub6 Antenna w/ Mount Pipe | C | From Leg | 3.00 | 0.0000 | 140.00 | No Ice | 5.43 | 3.27 | 0.11 |
| | | | 0.00 | | | 1/2" Ice | 5.97 | 3.99 | 0.15 |
| | | | 0.00 | | | 1" Ice | 6.46 | 4.59 | 0.20 |
| RFV01U-D1A | A | From Leg | 3.00 | 0.0000 | 140.00 | No Ice | 2.05 | 1.54 | 0.08 |
| | | | 0.00 | | | 1/2" Ice | 2.23 | 1.70 | 0.11 |
| | | | 0.00 | | | 1" Ice | 2.41 | 1.86 | 0.13 |
| RFV01U-D1A | B | From Leg | 3.00 | 0.0000 | 140.00 | No Ice | 2.05 | 1.54 | 0.08 |
| | | | 0.00 | | | 1/2" Ice | 2.23 | 1.70 | 0.11 |
| | | | 0.00 | | | 1" Ice | 2.41 | 1.86 | 0.13 |
| RFV01U-D1A | C | From Leg | 3.00 | 0.0000 | 140.00 | No Ice | 2.05 | 1.54 | 0.08 |
| | | | 0.00 | | | 1/2" Ice | 2.23 | 1.70 | 0.11 |
| | | | 0.00 | | | 1" Ice | 2.41 | 1.86 | 0.13 |
| RFV01U-D2A | A | From Leg | 3.00 | 0.0000 | 140.00 | No Ice | 2.05 | 1.29 | 0.07 |
| | | | 0.00 | | | 1/2" Ice | 2.23 | 1.44 | 0.09 |
| | | | 0.00 | | | 1" Ice | 2.41 | 1.59 | 0.11 |
| RFV01U-D2A | B | From Leg | 3.00 | 0.0000 | 140.00 | No Ice | 2.05 | 1.29 | 0.07 |
| | | | 0.00 | | | 1/2" Ice | 2.23 | 1.44 | 0.09 |

| | | | | |
|---|----------------|-------------------------------|--------------------|-------------------|
| tnxTower Network Building + Consulting 8601 Six Forks Road, Suite 540 Raleigh, NC 27615 Phone: 919.657.9131 FAX: | Job | Woodbridge North CT | Page | 20 of 52 |
| | Project | NB+C ES Project Number 100765 | Date | 14:34:37 12/14/20 |
| | Client | Verizon | Designed by | nsmith |

| Description | Face or Leg | Offset Type | Offsets: | | Azimuth Adjustment | Placement | C _{AA} Front | C _{AA} Side | Weight | |
|---------------------------------|-------------|-------------|----------|---------|--------------------|-----------|-----------------------|----------------------|--------|------|
| | | | Horz | Lateral | | | | | | Vert |
| RFV01U-D2A | C | From Leg | 0.00 | | 0.0000 | 140.00 | 1" Ice | 2.41 | 1.59 | 0.11 |
| | | | 3.00 | | | | No Ice | 2.05 | 1.29 | 0.07 |
| | | | 0.00 | | | | 1/2" Ice | 2.23 | 1.44 | 0.09 |
| | | | 0.00 | | | | 1" Ice | 2.41 | 1.59 | 0.11 |
| (2) LPA-80063/6CF w/ Mount Pipe | A | From Leg | 3.00 | | 0.0000 | 140.00 | No Ice | 9.83 | 10.22 | 0.05 |
| | | | 0.00 | | | | 1/2" Ice | 10.40 | 11.38 | 0.14 |
| | | | 0.00 | | | | 1" Ice | 10.93 | 12.27 | 0.25 |
| | | | 0.00 | | | | No Ice | 9.83 | 10.22 | 0.05 |
| (2) LPA-80063/6CF w/ Mount Pipe | B | From Leg | 3.00 | | 0.0000 | 140.00 | 1/2" Ice | 10.40 | 11.38 | 0.14 |
| | | | 0.00 | | | | 1" Ice | 10.93 | 12.27 | 0.25 |
| | | | 0.00 | | | | No Ice | 9.83 | 10.22 | 0.05 |
| | | | 0.00 | | | | 1/2" Ice | 10.40 | 11.38 | 0.14 |
| (2) LPA-80063/6CF w/ Mount Pipe | C | From Leg | 3.00 | | 0.0000 | 140.00 | 1" Ice | 10.93 | 12.27 | 0.25 |
| | | | 0.00 | | | | No Ice | 9.83 | 10.22 | 0.05 |
| | | | 0.00 | | | | 1/2" Ice | 10.40 | 11.38 | 0.14 |
| | | | 0.00 | | | | 1" Ice | 10.93 | 12.27 | 0.25 |
| RxxDC-3315-PF-48 | A | From Leg | 3.00 | | 0.0000 | 140.00 | No Ice | 2.51 | 1.65 | 0.03 |
| | | | 0.00 | | | | 1/2" Ice | 2.71 | 1.82 | 0.05 |
| | | | 0.00 | | | | 1" Ice | 2.91 | 1.99 | 0.08 |
| | | | 0.00 | | | | No Ice | 2.51 | 1.65 | 0.03 |
| RxxDC-3315-PF-48 | B | From Leg | 3.00 | | 0.0000 | 140.00 | 1/2" Ice | 2.71 | 1.82 | 0.05 |
| | | | 0.00 | | | | 1" Ice | 2.91 | 1.99 | 0.08 |
| | | | 0.00 | | | | No Ice | 19.83 | 19.83 | 0.92 |
| | | | 0.00 | | | | 1/2" Ice | 29.41 | 29.41 | 1.33 |
| Sector Mount [SM 406-3] | C | None | | | 0.0000 | 140.00 | 1" Ice | 38.99 | 38.99 | 1.73 |
| | | | | | | | No Ice | 19.83 | 19.83 | 0.92 |

Truss-Leg Properties

| Section Designation | Area | Area Ice | Self Weight | Ice Weight | Equiv. Diameter | Equiv. Diameter Ice | Leg Area |
|---------------------|-----------------|-----------------|-------------|------------|-----------------|---------------------|-----------------|
| | in ² | in ² | K | K | in | in | in ² |
| Pirod 105245 | 1604.4494 | 3539.3020 | 0.68 | 0.74 | 11.1420 | 24.5785 | 5.3014 |
| Pirod 105218 | 2263.4687 | 6700.6084 | 0.72 | 1.28 | 7.8593 | 23.2660 | 7.2158 |
| Pirod 105218 | 2263.4687 | 6684.7191 | 0.72 | 1.26 | 7.8593 | 23.2108 | 7.2158 |
| Pirod 105219 | 2441.8688 | 6739.2465 | 0.90 | 1.28 | 8.4787 | 23.4002 | 9.4248 |
| Pirod 105220 | 2578.8005 | 6791.8153 | 1.07 | 1.28 | 8.9542 | 23.5827 | 11.9282 |
| Pirod 105220 | 2578.8005 | 6769.8954 | 1.07 | 1.25 | 8.9542 | 23.5066 | 11.9282 |
| Pirod 112743 | 3466.5160 | 8923.4288 | 1.61 | 1.69 | 12.0365 | 30.9841 | 14.7262 |
| Pirod 112743 | 3466.5160 | 8898.2322 | 1.61 | 1.64 | 12.0365 | 30.8966 | 14.7262 |
| Pirod 112744 | 3599.5585 | 8939.3815 | 1.81 | 1.60 | 12.4985 | 31.0395 | 17.8187 |
| Pirod 112744 | 3599.5585 | 8899.2724 | 1.81 | 1.52 | 12.4985 | 30.9003 | 17.8187 |
| Pirod 112745 | 3789.3331 | 8912.9018 | 2.09 | 1.45 | 13.1574 | 30.9476 | 21.2058 |
| Pirod 112740 | 3789.3331 | 8797.0272 | 2.09 | 1.23 | 13.1574 | 30.5452 | 21.2058 |

Tower Pressures - No Ice

$$G_H = 0.850$$

| | | |
|---|---|----------------------------------|
| tnxTower Network Building + Consulting 8601 Six Forks Road, Suite 540 Raleigh, NC 27615 Phone: 919.657.9131 FAX: | Job Woodbridge North CT | Page 21 of 52 |
| | Project NB+C ES Project Number 100765 | Date 14:34:37 12/14/20 |
| | Client Verizon | Designed by nsmith |

| Section Elevation ft | z ft | K _Z | q _z psf | A _G ft ² | F a c e | A _F ft ² | A _R ft ² | A _{leg} ft ² | Leg % | C _A A _A In Face ft ² | C _A A _A Out Face ft ² |
|-------------------------|---------|----------------|-----------------------|-----------------------------------|------------------|-----------------------------------|-----------------------------------|-------------------------------------|----------|--|---|
| T1 280.00-270.00 | 275.00 | 1.319 | 27 | 51.458 | A | 0.000 | 7.235 | 2.917 | 40.31 | 0.000 | 0.000 |
| | | | | | B | 0.000 | 7.235 | | 40.31 | 0.000 | 0.000 |
| | | | | | C | 0.000 | 7.943 | | 36.72 | 7.920 | 0.000 |
| T2 270.00-250.00 | 260.00 | 1.298 | 27 | 103.333 | A | 0.000 | 14.118 | 6.667 | 47.22 | 0.000 | 0.000 |
| | | | | | B | 0.000 | 14.118 | | 47.22 | 0.000 | 0.000 |
| | | | | | C | 0.000 | 16.232 | | 41.07 | 15.840 | 0.000 |
| T3 250.00-230.00 | 240.00 | 1.269 | 26 | 104.167 | A | 0.000 | 16.405 | 8.333 | 50.80 | 35.640 | 0.000 |
| | | | | | B | 0.000 | 16.405 | | 50.80 | 0.000 | 0.000 |
| | | | | | C | 0.000 | 18.850 | | 44.21 | 15.840 | 0.000 |
| T4 230.00-220.00 | 225.00 | 1.246 | 26 | 66.264 | A | 4.235 | 18.601 | 18.601 | 81.45 | 17.820 | 0.000 |
| | | | | | B | 4.235 | 18.601 | | 81.45 | 0.000 | 0.000 |
| | | | | | C | 4.235 | 18.601 | | 81.45 | 7.920 | 0.000 |
| T5 220.00-200.00 | 210.00 | 1.222 | 25 | 162.945 | A | 10.467 | 26.241 | 26.241 | 71.49 | 35.640 | 0.000 |
| | | | | | B | 10.467 | 26.241 | | 71.49 | 0.000 | 0.000 |
| | | | | | C | 10.467 | 26.241 | | 71.49 | 15.840 | 0.000 |
| T6 200.00-180.00 | 190.00 | 1.187 | 24 | 202.945 | A | 15.714 | 26.241 | 26.241 | 62.55 | 35.640 | 0.000 |
| | | | | | B | 15.714 | 26.241 | | 62.55 | 35.640 | 0.000 |
| | | | | | C | 15.714 | 26.241 | | 62.55 | 33.660 | 0.000 |
| T7 180.00-160.00 | 170.00 | 1.15 | 24 | 243.362 | A | 19.853 | 28.309 | 28.309 | 58.78 | 43.240 | 0.000 |
| | | | | | B | 19.853 | 28.309 | | 58.78 | 35.640 | 0.000 |
| | | | | | C | 19.853 | 28.309 | | 58.78 | 87.120 | 0.000 |
| T8 160.00-140.00 | 150.00 | 1.11 | 23 | 283.780 | A | 20.877 | 29.897 | 29.897 | 58.88 | 86.480 | 0.000 |
| | | | | | B | 20.877 | 29.897 | | 58.88 | 35.640 | 0.000 |
| | | | | | C | 20.877 | 29.897 | | 58.88 | 89.360 | 0.000 |
| T9 140.00-120.00 | 130.00 | 1.065 | 22 | 323.780 | A | 19.635 | 29.897 | 29.897 | 60.36 | 98.360 | 0.000 |
| | | | | | B | 19.635 | 29.897 | | 60.36 | 86.480 | 0.000 |
| | | | | | C | 19.635 | 29.897 | | 60.36 | 89.360 | 0.000 |
| T10 120.00-100.00 | 110.00 | 1.016 | 21 | 374.209 | A | 14.190 | 40.189 | 40.189 | 73.91 | 98.360 | 0.000 |
| | | | | | B | 14.190 | 40.189 | | 73.91 | 86.480 | 0.000 |
| | | | | | C | 14.190 | 40.189 | | 73.91 | 89.360 | 0.000 |
| T11 100.00-80.00 | 90.00 | 0.959 | 20 | 414.209 | A | 14.825 | 40.189 | 40.189 | 73.05 | 98.360 | 0.000 |
| | | | | | B | 14.825 | 40.189 | | 73.05 | 86.480 | 0.000 |
| | | | | | C | 14.825 | 40.189 | | 73.05 | 89.360 | 0.000 |
| T12 80.00-60.00 | 70.00 | 0.892 | 18 | 454.627 | A | 15.712 | 41.731 | 41.731 | 72.65 | 98.360 | 0.000 |
| | | | | | B | 15.712 | 41.731 | | 72.65 | 86.480 | 0.000 |
| | | | | | C | 15.712 | 41.731 | | 72.65 | 89.360 | 0.000 |
| T13 60.00-40.00 | 50.00 | 0.811 | 17 | 494.627 | A | 16.624 | 41.731 | 41.731 | 71.51 | 98.360 | 0.000 |
| | | | | | B | 16.624 | 41.731 | | 71.51 | 86.480 | 0.000 |
| | | | | | C | 16.624 | 41.731 | | 71.51 | 89.360 | 0.000 |
| T14 40.00-20.00 | 30.00 | 0.701 | 14 | 535.044 | A | 17.558 | 43.931 | 43.931 | 71.44 | 98.360 | 0.000 |
| | | | | | B | 17.558 | 43.931 | | 71.44 | 86.480 | 0.000 |
| | | | | | C | 17.558 | 43.931 | | 71.44 | 89.360 | 0.000 |
| T15 20.00-0.00 | 10.00 | 0.7 | 14 | 575.044 | A | 18.514 | 43.931 | 43.931 | 70.35 | 39.344 | 0.000 |
| | | | | | B | 18.514 | 43.931 | | 70.35 | 34.592 | 0.000 |
| | | | | | C | 18.514 | 43.931 | | 70.35 | 41.720 | 0.000 |

Tower Pressure - With Ice

$G_H = 0.850$

| Section Elevation ft | z ft | K _Z | q _z psf | t _z in | A _G ft ² | F a c e | A _F ft ² | A _R ft ² | A _{leg} ft ² | Leg % | C _A A _A In Face ft ² | C _A A _A Out Face ft ² |
|-------------------------|---------|----------------|-----------------------|----------------------|-----------------------------------|------------------|-----------------------------------|-----------------------------------|-------------------------------------|----------|--|---|
| T1 280.00-270.00 | 275.00 | 1.319 | 7 | 1.8543 | 54.549 | A | 0.000 | 31.077 | 9.098 | 29.27 | 0.000 | 0.000 |
| | | | | | | B | 0.000 | 31.077 | | 29.27 | 0.000 | 0.000 |

| | | | | |
|---|----------------|-------------------------------|--------------------|-------------------|
| tnxTower Network Building + Consulting 8601 Six Forks Road, Suite 540 Raleigh, NC 27615 Phone: 919.657.9131 FAX: | Job | Woodbridge North CT | Page | 22 of 52 |
| | Project | NB+C ES Project Number 100765 | Date | 14:34:37 12/14/20 |
| | Client | Verizon | Designed by | nsmith |

| Section Elevation ft | z ft | K _Z | q _z psf | t _z in | A _G ft ² | F a c e | A _F ft ² | A _R ft ² | A _{leg} ft ² | Leg % | C _A A _A In Face ft ² | C _A A _A Out Face ft ² | |
|-------------------------|---------|----------------|-----------------------|----------------------|-----------------------------------|------------------|-----------------------------------|-----------------------------------|-------------------------------------|----------|--|---|---------|
| T2 270.00-250.00 | 260.00 | 1.298 | 7 | 1.8439 | 109.480 | C | 0.000 | 34.785 | 18.959 | 26.15 | 14.882 | 0.000 | |
| | | | | | | A | 0.000 | 57.177 | | | | | 0.000 |
| | | | | | | B | 0.000 | 57.177 | | | | | 0.000 |
| T3 250.00-230.00 | 240.00 | 1.269 | 7 | 1.8292 | 110.264 | C | 0.000 | 68.204 | 20.528 | 27.80 | 29.691 | 0.000 | |
| | | | | | | A | 0.000 | 57.397 | | | | | 35.77 |
| | | | | | | B | 0.000 | 57.397 | | | | | 0.000 |
| T4 230.00-220.00 | 225.00 | 1.246 | 7 | 1.8174 | 69.297 | C | 0.000 | 70.068 | 41.032 | 29.30 | 29.587 | 0.000 | |
| | | | | | | A | 4.235 | 47.190 | | | | | 79.79 |
| | | | | | | B | 4.235 | 47.190 | | | | | 0.000 |
| T5 220.00-200.00 | 210.00 | 1.222 | 7 | 1.8049 | 168.969 | C | 0.000 | 47.190 | 77.682 | 79.79 | 14.752 | 0.000 | |
| | | | | | | A | 10.467 | 90.277 | | | | | 77.11 |
| | | | | | | B | 10.467 | 90.277 | | | | | 0.000 |
| T6 200.00-180.00 | 190.00 | 1.187 | 6 | 1.7870 | 208.909 | C | 0.000 | 90.277 | 77.498 | 77.11 | 29.415 | 0.000 | |
| | | | | | | A | 15.714 | 96.219 | | | | | 69.24 |
| | | | | | | B | 15.714 | 96.219 | | | | | 38.940 |
| T7 180.00-160.00 | 170.00 | 1.15 | 6 | 1.7672 | 249.260 | C | 0.000 | 96.219 | 78.130 | 69.24 | 52.337 | 0.000 | |
| | | | | | | A | 19.853 | 99.655 | | | | | 65.38 |
| | | | | | | B | 19.853 | 99.655 | | | | | 38.800 |
| T8 160.00-140.00 | 150.00 | 1.11 | 6 | 1.7452 | 289.604 | C | 0.000 | 99.655 | 78.740 | 65.38 | 121.080 | 0.000 | |
| | | | | | | A | 20.877 | 99.559 | | | | | 65.38 |
| | | | | | | B | 20.877 | 99.559 | | | | | 38.645 |
| T9 140.00-120.00 | 130.00 | 1.065 | 6 | 1.7204 | 329.522 | C | 0.000 | 99.559 | 78.486 | 65.38 | 136.832 | 0.000 | |
| | | | | | | A | 19.635 | 97.789 | | | | | 66.84 |
| | | | | | | B | 19.635 | 97.789 | | | | | 138.328 |
| T10 120.00-100.00 | 110.00 | 1.016 | 6 | 1.6919 | 379.856 | C | 0.000 | 97.789 | 103.452 | 66.84 | 136.125 | 0.000 | |
| | | | | | | A | 14.190 | 117.171 | | | | | 78.75 |
| | | | | | | B | 14.190 | 117.171 | | | | | 137.851 |
| T11 100.00-80.00 | 90.00 | 0.959 | 5 | 1.6583 | 419.744 | C | 0.000 | 117.171 | 103.160 | 78.75 | 135.314 | 0.000 | |
| | | | | | | A | 14.825 | 117.209 | | | | | 78.13 |
| | | | | | | B | 14.825 | 117.209 | | | | | 137.287 |
| T12 80.00-60.00 | 70.00 | 0.892 | 5 | 1.6171 | 460.024 | C | 0.000 | 117.209 | 103.637 | 78.13 | 134.356 | 0.000 | |
| | | | | | | A | 15.712 | 118.156 | | | | | 77.42 |
| | | | | | | B | 15.712 | 118.156 | | | | | 136.598 |
| T13 60.00-40.00 | 50.00 | 0.811 | 4 | 1.5636 | 499.845 | C | 0.000 | 118.156 | 103.172 | 77.42 | 133.185 | 0.000 | |
| | | | | | | A | 16.624 | 118.026 | | | | | 76.62 |
| | | | | | | B | 16.624 | 118.026 | | | | | 135.702 |
| T14 40.00-20.00 | 30.00 | 0.701 | 4 | 1.4858 | 540.002 | C | 0.000 | 118.026 | 103.330 | 76.62 | 131.662 | 0.000 | |
| | | | | | | A | 17.558 | 118.238 | | | | | 76.09 |
| | | | | | | B | 17.558 | 118.238 | | | | | 134.399 |
| T15 20.00-0.00 | 10.00 | 0.7 | 4 | 1.3312 | 579.487 | C | 0.000 | 118.238 | 101.987 | 76.09 | 129.448 | 0.000 | |
| | | | | | | A | 18.514 | 116.071 | | | | | 75.78 |
| | | | | | | B | 18.514 | 116.071 | | | | | 52.727 |
| | | | | | | C | 18.514 | 116.071 | | 75.78 | 67.698 | 0.000 | |

Tower Pressure - Service

$G_H = 0.850$

| Section Elevation ft | z ft | K _Z | q _z psf | A _G ft ² | F a c e | A _F ft ² | A _R ft ² | A _{leg} ft ² | Leg % | C _A A _A In Face ft ² | C _A A _A Out Face ft ² | |
|-------------------------|---------|----------------|-----------------------|-----------------------------------|------------------|-----------------------------------|-----------------------------------|-------------------------------------|----------|--|---|-------|
| T1 280.00-270.00 | 275.00 | 1.319 | 10 | 51.458 | A | 0.000 | 7.235 | 2.917 | 40.31 | 0.000 | 0.000 | |
| | | | | | B | 0.000 | 7.235 | | | | | 40.31 |
| | | | | | C | 0.000 | 7.943 | | | | | 36.72 |

| | | |
|---|---|----------------------------------|
| tnxTower Network Building + Consulting 8601 Six Forks Road, Suite 540 Raleigh, NC 27615 Phone: 919.657.9131 FAX: | Job Woodbridge North CT | Page 23 of 52 |
| | Project NB+C ES Project Number 100765 | Date 14:34:37 12/14/20 |
| | Client Verizon | Designed by nsmith |

| Section Elevation ft | z ft | K _Z | q _z psf | A _G ft ² | F _a c e | A _F ft ² | A _R ft ² | A _{leg} ft ² | Leg % | C _A A _A In Face ft ² | C _A A _A Out Face ft ² |
|-------------------------|---------|----------------|-----------------------|-----------------------------------|--------------------------|-----------------------------------|-----------------------------------|-------------------------------------|-------|--|---|
| T2 270.00-250.00 | 260.00 | 1.298 | 10 | 103.333 | A | 0.000 | 14.118 | 6.667 | 47.22 | 0.000 | 0.000 |
| | | | | | B | 0.000 | 14.118 | | 47.22 | 0.000 | 0.000 |
| | | | | | C | 0.000 | 16.232 | | 41.07 | 15.840 | 0.000 |
| T3 250.00-230.00 | 240.00 | 1.269 | 10 | 104.167 | A | 0.000 | 16.405 | 8.333 | 50.80 | 35.640 | 0.000 |
| | | | | | B | 0.000 | 16.405 | | 50.80 | 0.000 | 0.000 |
| | | | | | C | 0.000 | 18.850 | | 44.21 | 15.840 | 0.000 |
| T4 230.00-220.00 | 225.00 | 1.246 | 10 | 66.264 | A | 4.235 | 18.601 | 18.601 | 81.45 | 17.820 | 0.000 |
| | | | | | B | 4.235 | 18.601 | | 81.45 | 0.000 | 0.000 |
| | | | | | C | 4.235 | 18.601 | | 81.45 | 7.920 | 0.000 |
| T5 220.00-200.00 | 210.00 | 1.222 | 10 | 162.945 | A | 10.467 | 26.241 | 26.241 | 71.49 | 35.640 | 0.000 |
| | | | | | B | 10.467 | 26.241 | | 71.49 | 0.000 | 0.000 |
| | | | | | C | 10.467 | 26.241 | | 71.49 | 15.840 | 0.000 |
| T6 200.00-180.00 | 190.00 | 1.187 | 9 | 202.945 | A | 15.714 | 26.241 | 26.241 | 62.55 | 35.640 | 0.000 |
| | | | | | B | 15.714 | 26.241 | | 62.55 | 35.640 | 0.000 |
| | | | | | C | 15.714 | 26.241 | | 62.55 | 33.660 | 0.000 |
| T7 180.00-160.00 | 170.00 | 1.15 | 9 | 243.362 | A | 19.853 | 28.309 | 28.309 | 58.78 | 43.240 | 0.000 |
| | | | | | B | 19.853 | 28.309 | | 58.78 | 35.640 | 0.000 |
| | | | | | C | 19.853 | 28.309 | | 58.78 | 87.120 | 0.000 |
| T8 160.00-140.00 | 150.00 | 1.11 | 9 | 283.780 | A | 20.877 | 29.897 | 29.897 | 58.88 | 86.480 | 0.000 |
| | | | | | B | 20.877 | 29.897 | | 58.88 | 35.640 | 0.000 |
| | | | | | C | 20.877 | 29.897 | | 58.88 | 89.360 | 0.000 |
| T9 140.00-120.00 | 130.00 | 1.065 | 8 | 323.780 | A | 19.635 | 29.897 | 29.897 | 60.36 | 98.360 | 0.000 |
| | | | | | B | 19.635 | 29.897 | | 60.36 | 86.480 | 0.000 |
| | | | | | C | 19.635 | 29.897 | | 60.36 | 89.360 | 0.000 |
| T10 120.00-100.00 | 110.00 | 1.016 | 8 | 374.209 | A | 14.190 | 40.189 | 40.189 | 73.91 | 98.360 | 0.000 |
| | | | | | B | 14.190 | 40.189 | | 73.91 | 86.480 | 0.000 |
| | | | | | C | 14.190 | 40.189 | | 73.91 | 89.360 | 0.000 |
| T11 100.00-80.00 | 90.00 | 0.959 | 8 | 414.209 | A | 14.825 | 40.189 | 40.189 | 73.05 | 98.360 | 0.000 |
| | | | | | B | 14.825 | 40.189 | | 73.05 | 86.480 | 0.000 |
| | | | | | C | 14.825 | 40.189 | | 73.05 | 89.360 | 0.000 |
| T12 80.00-60.00 | 70.00 | 0.892 | 7 | 454.627 | A | 15.712 | 41.731 | 41.731 | 72.65 | 98.360 | 0.000 |
| | | | | | B | 15.712 | 41.731 | | 72.65 | 86.480 | 0.000 |
| | | | | | C | 15.712 | 41.731 | | 72.65 | 89.360 | 0.000 |
| T13 60.00-40.00 | 50.00 | 0.811 | 6 | 494.627 | A | 16.624 | 41.731 | 41.731 | 71.51 | 98.360 | 0.000 |
| | | | | | B | 16.624 | 41.731 | | 71.51 | 86.480 | 0.000 |
| | | | | | C | 16.624 | 41.731 | | 71.51 | 89.360 | 0.000 |
| T14 40.00-20.00 | 30.00 | 0.701 | 5 | 535.044 | A | 17.558 | 43.931 | 43.931 | 71.44 | 98.360 | 0.000 |
| | | | | | B | 17.558 | 43.931 | | 71.44 | 86.480 | 0.000 |
| | | | | | C | 17.558 | 43.931 | | 71.44 | 89.360 | 0.000 |
| T15 20.00-0.00 | 10.00 | 0.7 | 5 | 575.044 | A | 18.514 | 43.931 | 43.931 | 70.35 | 39.344 | 0.000 |
| | | | | | B | 18.514 | 43.931 | | 70.35 | 34.592 | 0.000 |
| | | | | | C | 18.514 | 43.931 | | 70.35 | 41.720 | 0.000 |

Tower Forces - No Ice - Wind Normal To Face

| Section Elevation ft | Add Weight K | Self Weight K | F _a c e | e | C _F | q _z psf | D _F | D _R | A _E ft ² | F K | w plf | Ctrl. Face |
|-------------------------|-----------------|------------------|--------------------------|-------|----------------|-----------------------|----------------|----------------|-----------------------------------|--------|----------|---------------|
| T1 280.00-270.00 | 0.03 | 0.66 | A | 0.141 | 2.806 | 27 | 1 | 1 | 4.100 | 0.37 | 36.66 | C |
| | | | B | 0.141 | 2.806 | | 1 | 1 | 4.100 | | | |
| | | | C | 0.154 | 2.756 | | 1 | 1 | 4.512 | | | |
| T2 270.00-250.00 | 0.07 | 1.37 | A | 0.137 | 2.821 | 27 | 1 | 1 | 7.995 | 0.73 | 36.60 | C |
| | | | B | 0.137 | 2.821 | | 1 | 1 | 7.995 | | | |
| | | | C | 0.157 | 2.746 | | 1 | 1 | 9.225 | | | |
| T3 250.00-230.00 | 0.21 | 1.91 | A | 0.157 | 2.744 | 26 | 1 | 1 | 9.323 | 1.19 | 59.67 | A |
| | | | B | 0.157 | 2.744 | | 1 | 1 | 9.323 | | | |

| | | |
|---|---|----------------------------------|
| tnxTower Network Building + Consulting 8601 Six Forks Road, Suite 540 Raleigh, NC 27615 Phone: 919.657.9131 FAX: | Job Woodbridge North CT | Page 24 of 52 |
| | Project NB+C ES Project Number 100765 | Date 14:34:37 12/14/20 |
| | Client Verizon | Designed by nsmith |

| Section Elevation ft | Add Weight K | Self Weight K | F a c e | e | C _F | q _z psf | D _F | D _R | A _E ft ² | F K | w plf | Ctrl. Face |
|-------------------------|-----------------|------------------|---------|-------|----------------|-----------------------|----------------|----------------|-----------------------------------|--------|----------|------------|
| T4 230.00-220.00 | 0.11 | 1.23 | C | 0.181 | 2.661 | 26 | 1 | 1 | 10.771 | 1.05 | 104.99 | A |
| | | | A | 0.345 | 2.184 | | | | 15.657 | | | |
| | | | B | 0.345 | 2.184 | | | | 15.657 | | | |
| T5 220.00-200.00 | 0.21 | 2.70 | C | 0.345 | 2.184 | 25 | 1 | 1 | 15.657 | 1.98 | 98.83 | A |
| | | | A | 0.225 | 2.514 | | | | 25.670 | | | |
| | | | B | 0.225 | 2.514 | | | | 25.670 | | | |
| T6 200.00-180.00 | 0.43 | 2.95 | C | 0.225 | 2.514 | 24 | 1 | 1 | 25.670 | 2.56 | 128.09 | A |
| | | | A | 0.207 | 2.574 | | | | 30.821 | | | |
| | | | B | 0.207 | 2.574 | | | | 30.821 | | | |
| T7 180.00-160.00 | 0.70 | 4.20 | C | 0.207 | 2.574 | 24 | 1 | 1 | 30.821 | 3.35 | 167.73 | C |
| | | | A | 0.198 | 2.603 | | | | 36.106 | | | |
| | | | B | 0.198 | 2.603 | | | | 36.106 | | | |
| T8 160.00-140.00 | 0.90 | 4.86 | C | 0.198 | 2.603 | 23 | 1 | 1 | 36.106 | 3.72 | 186.24 | C |
| | | | A | 0.179 | 2.668 | | | | 37.951 | | | |
| | | | B | 0.179 | 2.668 | | | | 37.951 | | | |
| T9 140.00-120.00 | 1.20 | 4.75 | C | 0.179 | 2.668 | 22 | 1 | 1 | 37.951 | 3.97 | 198.35 | C |
| | | | A | 0.153 | 2.761 | | | | 36.612 | | | |
| | | | B | 0.153 | 2.761 | | | | 36.612 | | | |
| T10 120.00-100.00 | 1.20 | 7.08 | C | 0.153 | 2.761 | 21 | 1 | 1 | 36.612 | 3.82 | 190.92 | C |
| | | | A | 0.145 | 2.789 | | | | 36.980 | | | |
| | | | B | 0.145 | 2.789 | | | | 36.980 | | | |
| T11 100.00-80.00 | 1.20 | 7.19 | C | 0.145 | 2.789 | 20 | 1 | 1 | 36.980 | 3.66 | 183.14 | C |
| | | | A | 0.133 | 2.836 | | | | 37.573 | | | |
| | | | B | 0.133 | 2.836 | | | | 37.573 | | | |
| T12 80.00-60.00 | 1.20 | 7.93 | C | 0.133 | 2.836 | 18 | 1 | 1 | 37.573 | 3.50 | 175.03 | C |
| | | | A | 0.126 | 2.86 | | | | 39.313 | | | |
| | | | B | 0.126 | 2.86 | | | | 39.313 | | | |
| T13 60.00-40.00 | 1.20 | 8.05 | C | 0.126 | 2.86 | 17 | 1 | 1 | 39.313 | 3.23 | 161.71 | C |
| | | | A | 0.118 | 2.893 | | | | 40.204 | | | |
| | | | B | 0.118 | 2.893 | | | | 40.204 | | | |
| T14 40.00-20.00 | 1.20 | 9.01 | C | 0.118 | 2.893 | 14 | 1 | 1 | 40.204 | 2.88 | 143.88 | C |
| | | | A | 0.115 | 2.905 | | | | 42.375 | | | |
| | | | B | 0.115 | 2.905 | | | | 42.375 | | | |
| T15 20.00-0.00 | 0.57 | 9.15 | C | 0.115 | 2.905 | 14 | 1 | 1 | 42.375 | 2.14 | 107.00 | C |
| | | | A | 0.109 | 2.93 | | | | 43.319 | | | |
| | | | B | 0.109 | 2.93 | | | | 43.319 | | | |
| Sum Weight: | 10.43 | 73.02 | | | | | | OTM | 4624.47 kip-ft | 38.16 | | |

Tower Forces - No Ice - Wind 60 To Face

| Section Elevation ft | Add Weight K | Self Weight K | F a c e | e | C _F | q _z psf | D _F | D _R | A _E ft ² | F K | w plf | Ctrl. Face |
|-------------------------|-----------------|------------------|---------|-------|----------------|-----------------------|----------------|----------------|-----------------------------------|--------|----------|------------|
| T1 280.00-270.00 | 0.03 | 0.66 | A | 0.141 | 2.806 | 27 | 0.8 | 1 | 4.100 | 0.37 | 36.66 | C |
| | | | B | 0.141 | 2.806 | | | | 4.100 | | | |
| | | | C | 0.154 | 2.756 | | | | 4.512 | | | |
| T2 270.00-250.00 | 0.07 | 1.37 | A | 0.137 | 2.821 | 27 | 0.8 | 1 | 7.995 | 0.73 | 36.60 | C |
| | | | B | 0.137 | 2.821 | | | | 7.995 | | | |
| | | | C | 0.157 | 2.746 | | | | 9.225 | | | |
| T3 250.00-230.00 | 0.21 | 1.91 | A | 0.157 | 2.744 | 26 | 0.8 | 1 | 9.323 | 1.19 | 59.67 | B |
| | | | B | 0.157 | 2.744 | | | | 9.323 | | | |
| | | | C | 0.157 | 2.744 | | | | 9.323 | | | |

| | | |
|---|---|----------------------------------|
| tnxTower Network Building + Consulting 8601 Six Forks Road, Suite 540 Raleigh, NC 27615 Phone: 919.657.9131 FAX: | Job Woodbridge North CT | Page 25 of 52 |
| | Project NB+C ES Project Number 100765 | Date 14:34:37 12/14/20 |
| | Client Verizon | Designed by nsmith |

| Section Elevation ft | Add Weight K | Self Weight K | F a c e | e | C _F | q _z psf | D _F | D _R | A _E ft ² | F K | w plf | Ctrl. Face |
|-------------------------|-----------------|------------------|---------|-------|----------------|-----------------------|----------------|----------------|-----------------------------------|--------|----------|------------|
| T4 230.00-220.00 | 0.11 | 1.23 | C | 0.181 | 2.661 | 26 | 0.8 | 1 | 10.771 | 1.01 | 100.98 | B |
| | | | A | 0.345 | 2.184 | | 0.8 | 1 | 14.810 | | | |
| | | | B | 0.345 | 2.184 | | 0.8 | 1 | 14.810 | | | |
| T5 220.00-200.00 | 0.21 | 2.70 | C | 0.345 | 2.184 | 25 | 0.8 | 1 | 14.810 | 1.86 | 93.24 | B |
| | | | A | 0.225 | 2.514 | | 0.8 | 1 | 23.577 | | | |
| | | | B | 0.225 | 2.514 | | 0.8 | 1 | 23.577 | | | |
| T6 200.00-180.00 | 0.43 | 2.95 | C | 0.225 | 2.514 | 24 | 0.8 | 1 | 23.577 | 2.39 | 119.74 | B |
| | | | A | 0.207 | 2.574 | | 0.8 | 1 | 27.678 | | | |
| | | | B | 0.207 | 2.574 | | 0.8 | 1 | 27.678 | | | |
| T7 180.00-160.00 | 0.70 | 4.20 | C | 0.207 | 2.574 | 24 | 0.8 | 1 | 27.678 | 3.15 | 157.39 | A |
| | | | A | 0.198 | 2.603 | | 0.8 | 1 | 32.135 | | | |
| | | | B | 0.198 | 2.603 | | 0.8 | 1 | 32.135 | | | |
| T8 160.00-140.00 | 0.90 | 4.86 | C | 0.198 | 2.603 | 23 | 0.8 | 1 | 32.135 | 3.51 | 175.49 | A |
| | | | A | 0.179 | 2.668 | | 0.8 | 1 | 33.776 | | | |
| | | | B | 0.179 | 2.668 | | 0.8 | 1 | 33.776 | | | |
| T9 140.00-120.00 | 1.20 | 4.75 | C | 0.179 | 2.668 | 22 | 0.8 | 1 | 33.776 | 3.77 | 188.30 | A |
| | | | A | 0.153 | 2.761 | | 0.8 | 1 | 32.685 | | | |
| | | | B | 0.153 | 2.761 | | 0.8 | 1 | 32.685 | | | |
| T10 120.00-100.00 | 1.20 | 7.08 | C | 0.153 | 2.761 | 21 | 0.8 | 1 | 32.685 | 3.68 | 183.93 | A |
| | | | A | 0.145 | 2.789 | | 0.8 | 1 | 34.142 | | | |
| | | | B | 0.145 | 2.789 | | 0.8 | 1 | 34.142 | | | |
| T11 100.00-80.00 | 1.20 | 7.19 | C | 0.145 | 2.789 | 20 | 0.8 | 1 | 34.142 | 3.52 | 176.12 | A |
| | | | A | 0.133 | 2.836 | | 0.8 | 1 | 34.608 | | | |
| | | | B | 0.133 | 2.836 | | 0.8 | 1 | 34.608 | | | |
| T12 80.00-60.00 | 1.20 | 7.93 | C | 0.133 | 2.836 | 18 | 0.8 | 1 | 34.608 | 3.36 | 168.05 | A |
| | | | A | 0.126 | 2.86 | | 0.8 | 1 | 36.171 | | | |
| | | | B | 0.126 | 2.86 | | 0.8 | 1 | 36.171 | | | |
| T13 60.00-40.00 | 1.20 | 8.05 | C | 0.126 | 2.86 | 17 | 0.8 | 1 | 36.171 | 3.10 | 154.92 | A |
| | | | A | 0.118 | 2.893 | | 0.8 | 1 | 36.879 | | | |
| | | | B | 0.118 | 2.893 | | 0.8 | 1 | 36.879 | | | |
| T14 40.00-20.00 | 1.20 | 9.01 | C | 0.118 | 2.893 | 14 | 0.8 | 1 | 36.879 | 2.75 | 137.67 | A |
| | | | A | 0.115 | 2.905 | | 0.8 | 1 | 38.864 | | | |
| | | | B | 0.115 | 2.905 | | 0.8 | 1 | 38.864 | | | |
| T15 20.00-0.00 | 0.57 | 9.15 | C | 0.115 | 2.905 | 14 | 0.8 | 1 | 38.864 | 2.01 | 100.39 | A |
| | | | A | 0.109 | 2.93 | | 0.8 | 1 | 39.616 | | | |
| | | | B | 0.109 | 2.93 | | 0.8 | 1 | 39.616 | | | |
| Sum Weight: | 10.43 | 73.02 | | | | | | OTM | 4417.02 kip-ft | 36.41 | | |

Tower Forces - No Ice - Wind 90 To Face

| Section Elevation ft | Add Weight K | Self Weight K | F a c e | e | C _F | q _z psf | D _F | D _R | A _E ft ² | F K | w plf | Ctrl. Face |
|-------------------------|-----------------|------------------|---------|-------|----------------|-----------------------|----------------|----------------|-----------------------------------|--------|----------|------------|
| T1 280.00-270.00 | 0.03 | 0.66 | A | 0.141 | 2.806 | 27 | 0.85 | 1 | 4.100 | 0.37 | 36.66 | C |
| | | | B | 0.141 | 2.806 | | 0.85 | 1 | 4.100 | | | |
| | | | C | 0.154 | 2.756 | | 0.85 | 1 | 4.512 | | | |
| T2 270.00-250.00 | 0.07 | 1.37 | A | 0.137 | 2.821 | 27 | 0.85 | 1 | 7.995 | 0.73 | 36.60 | C |
| | | | B | 0.137 | 2.821 | | 0.85 | 1 | 7.995 | | | |
| | | | C | 0.157 | 2.746 | | 0.85 | 1 | 9.225 | | | |
| T3 250.00-230.00 | 0.21 | 1.91 | A | 0.157 | 2.744 | 26 | 0.85 | 1 | 9.323 | 1.26 | 63.06 | C |
| | | | B | 0.157 | 2.744 | | 0.85 | 1 | 9.323 | | | |

| | | |
|---|---|----------------------------------|
| tnxTower Network Building + Consulting 8601 Six Forks Road, Suite 540 Raleigh, NC 27615 Phone: 919.657.9131 FAX: | Job Woodbridge North CT | Page 26 of 52 |
| | Project NB+C ES Project Number 100765 | Date 14:34:37 12/14/20 |
| | Client Verizon | Designed by nsmith |

| Section Elevation ft | Add Weight K | Self Weight K | F a c e | e | C _F | q _z psf | D _F | D _R | A _E ft ² | F K | w plf | Ctrl. Face |
|-------------------------|-----------------|------------------|---------|-------|----------------|-----------------------|----------------|----------------|-----------------------------------|--------|----------|------------|
| T4 230.00-220.00 | 0.11 | 1.23 | C | 0.181 | 2.661 | | 0.85 | 1 | 10.771 | | | |
| | | | A | 0.345 | 2.184 | 26 | 0.85 | 1 | 15.022 | 1.02 | 101.98 | C |
| | | | B | 0.345 | 2.184 | | 0.85 | 1 | 15.022 | | | |
| T5 220.00-200.00 | 0.21 | 2.70 | C | 0.345 | 2.184 | | 0.85 | 1 | 15.022 | | | |
| | | | A | 0.225 | 2.514 | 25 | 0.85 | 1 | 24.100 | 1.89 | 94.63 | C |
| | | | B | 0.225 | 2.514 | | 0.85 | 1 | 24.100 | | | |
| T6 200.00-180.00 | 0.43 | 2.95 | C | 0.225 | 2.514 | | 0.85 | 1 | 24.100 | | | |
| | | | A | 0.207 | 2.574 | 24 | 0.85 | 1 | 28.464 | 2.50 | 125.00 | B |
| | | | B | 0.207 | 2.574 | | 0.85 | 1 | 28.464 | | | |
| T7 180.00-160.00 | 0.70 | 4.20 | C | 0.207 | 2.574 | | 0.85 | 1 | 28.464 | | | |
| | | | A | 0.198 | 2.603 | 24 | 0.85 | 1 | 33.128 | 3.26 | 163.07 | B |
| | | | B | 0.198 | 2.603 | | 0.85 | 1 | 33.128 | | | |
| T8 160.00-140.00 | 0.90 | 4.86 | C | 0.198 | 2.603 | | 0.85 | 1 | 33.128 | | | |
| | | | A | 0.179 | 2.668 | 23 | 0.85 | 1 | 34.819 | 3.74 | 187.14 | B |
| | | | B | 0.179 | 2.668 | | 0.85 | 1 | 34.819 | | | |
| T9 140.00-120.00 | 1.20 | 4.75 | C | 0.179 | 2.668 | | 0.85 | 1 | 34.819 | | | |
| | | | A | 0.153 | 2.761 | 22 | 0.85 | 1 | 33.667 | 3.89 | 194.63 | C |
| | | | B | 0.153 | 2.761 | | 0.85 | 1 | 33.667 | | | |
| T10 120.00-100.00 | 1.20 | 7.08 | C | 0.153 | 2.761 | | 0.85 | 1 | 33.667 | | | |
| | | | A | 0.145 | 2.789 | 21 | 0.85 | 1 | 34.852 | 3.79 | 189.32 | C |
| | | | B | 0.145 | 2.789 | | 0.85 | 1 | 34.852 | | | |
| T11 100.00-80.00 | 1.20 | 7.19 | C | 0.145 | 2.789 | | 0.85 | 1 | 34.852 | | | |
| | | | A | 0.133 | 2.836 | 20 | 0.85 | 1 | 35.349 | 3.63 | 181.31 | C |
| | | | B | 0.133 | 2.836 | | 0.85 | 1 | 35.349 | | | |
| T12 80.00-60.00 | 1.20 | 7.93 | C | 0.133 | 2.836 | | 0.85 | 1 | 35.349 | | | |
| | | | A | 0.126 | 2.86 | 18 | 0.85 | 1 | 36.956 | 3.46 | 173.00 | C |
| | | | B | 0.126 | 2.86 | | 0.85 | 1 | 36.956 | | | |
| T13 60.00-40.00 | 1.20 | 8.05 | C | 0.126 | 2.86 | | 0.85 | 1 | 36.956 | | | |
| | | | A | 0.118 | 2.893 | 17 | 0.85 | 1 | 37.710 | 3.19 | 159.52 | C |
| | | | B | 0.118 | 2.893 | | 0.85 | 1 | 37.710 | | | |
| T14 40.00-20.00 | 1.20 | 9.01 | C | 0.118 | 2.893 | | 0.85 | 1 | 37.710 | | | |
| | | | A | 0.115 | 2.905 | 14 | 0.85 | 1 | 39.741 | 2.83 | 141.73 | C |
| | | | B | 0.115 | 2.905 | | 0.85 | 1 | 39.741 | | | |
| T15 20.00-0.00 | 0.57 | 9.15 | C | 0.115 | 2.905 | | 0.85 | 1 | 39.741 | | | |
| | | | A | 0.109 | 2.93 | 14 | 0.85 | 1 | 40.542 | 2.04 | 101.78 | C |
| | | | B | 0.109 | 2.93 | | 0.85 | 1 | 40.542 | | | |
| Sum Weight: | 10.43 | 73.02 | | | | | | | | | | |
| | | | | | | | | OTM | 4567.60 kip-ft | 37.60 | | |

Tower Forces - With Ice - Wind Normal To Face

| Section Elevation ft | Add Weight K | Self Weight K | F a c e | e | C _F | q _z psf | D _F | D _R | A _E ft ² | F K | w plf | Ctrl. Face |
|-------------------------|-----------------|------------------|---------|-------|----------------|-----------------------|----------------|----------------|-----------------------------------|--------|----------|------------|
| T1 280.00-270.00 | 0.23 | 2.07 | A | 0.57 | 1.826 | 7 | 1 | 1 | 22.531 | 0.32 | 31.87 | C |
| | | | B | 0.57 | 1.826 | | 1 | 1 | 22.531 | | | |
| | | | C | 0.638 | 1.785 | | 1 | 1 | 26.722 | | | |
| T2 270.00-250.00 | 0.46 | 3.99 | A | 0.522 | 1.873 | 7 | 1 | 1 | 39.868 | 0.62 | 30.83 | C |
| | | | B | 0.522 | 1.873 | | 1 | 1 | 39.868 | | | |
| | | | C | 0.623 | 1.792 | | 1 | 1 | 51.734 | | | |
| T3 250.00-230.00 | 1.53 | 4.59 | A | 0.521 | 1.875 | 7 | 1 | 1 | 39.965 | 0.71 | 35.48 | C |
| | | | B | 0.521 | 1.875 | | 1 | 1 | 39.965 | | | |

| | | | | |
|---|----------------|-------------------------------|--------------------|-------------------|
| tnxTower Network Building + Consulting 8601 Six Forks Road, Suite 540 Raleigh, NC 27615 Phone: 919.657.9131 FAX: | Job | Woodbridge North CT | Page | 27 of 52 |
| | Project | NB+C ES Project Number 100765 | Date | 14:34:37 12/14/20 |
| | Client | Verizon | Designed by | nsmith |

| Section Elevation ft | Add Weight K | Self Weight K | F a c e | e | C _F | q _z psf | D _F | D _R | A _E ft ² | F K | w plf | Ctrl. Face |
|-------------------------|-----------------|------------------|---------|-------|----------------|-----------------------|----------------|----------------|-----------------------------------|--------|----------|------------|
| T4 230.00-220.00 | 0.76 | 3.15 | C | 0.635 | 1.786 | 7 | 1 | 1 | 53.723 | 0.51 | 51.33 | A |
| | | | A | 0.742 | 1.785 | | | | 43.951 | | | |
| | | | B | 0.742 | 1.785 | | | | 43.951 | | | |
| T5 220.00-200.00 | 1.52 | 8.50 | C | 0.742 | 1.785 | 7 | 1 | 1 | 43.951 | 0.98 | 48.90 | A |
| | | | A | 0.596 | 1.806 | | | | 77.397 | | | |
| | | | B | 0.596 | 1.806 | | | | 77.397 | | | |
| T6 200.00-180.00 | 2.76 | 9.53 | C | 0.596 | 1.806 | 6 | 1 | 1 | 77.397 | 1.16 | 58.25 | A |
| | | | A | 0.536 | 1.858 | | | | 83.545 | | | |
| | | | B | 0.536 | 1.858 | | | | 83.545 | | | |
| T7 180.00-160.00 | 4.33 | 11.38 | C | 0.536 | 1.858 | 6 | 1 | 1 | 83.545 | 1.39 | 69.53 | A |
| | | | A | 0.479 | 1.928 | | | | 87.032 | | | |
| | | | B | 0.479 | 1.928 | | | | 87.032 | | | |
| T8 160.00-140.00 | 5.81 | 12.04 | C | 0.479 | 1.928 | 6 | 1 | 1 | 87.032 | 1.70 | 85.12 | A |
| | | | A | 0.416 | 2.033 | | | | 84.918 | | | |
| | | | B | 0.416 | 2.033 | | | | 84.918 | | | |
| T9 140.00-120.00 | 7.58 | 11.55 | C | 0.416 | 2.033 | 6 | 1 | 1 | 84.918 | 1.81 | 90.41 | A |
| | | | A | 0.356 | 2.157 | | | | 80.113 | | | |
| | | | B | 0.356 | 2.157 | | | | 80.113 | | | |
| T10 120.00-100.00 | 7.48 | 14.99 | C | 0.356 | 2.157 | 6 | 1 | 1 | 80.113 | 1.79 | 89.52 | A |
| | | | A | 0.346 | 2.181 | | | | 86.193 | | | |
| | | | B | 0.346 | 2.181 | | | | 86.193 | | | |
| T11 100.00-80.00 | 7.36 | 15.02 | C | 0.346 | 2.181 | 5 | 1 | 1 | 86.193 | 1.71 | 85.42 | A |
| | | | A | 0.315 | 2.258 | | | | 85.571 | | | |
| | | | B | 0.315 | 2.258 | | | | 85.571 | | | |
| T12 80.00-60.00 | 7.22 | 15.69 | C | 0.315 | 2.258 | 5 | 1 | 1 | 85.571 | 1.61 | 80.57 | A |
| | | | A | 0.291 | 2.32 | | | | 86.154 | | | |
| | | | B | 0.291 | 2.32 | | | | 86.154 | | | |
| T13 60.00-40.00 | 7.04 | 15.60 | C | 0.291 | 2.32 | 4 | 1 | 1 | 86.154 | 1.48 | 73.84 | A |
| | | | A | 0.269 | 2.381 | | | | 86.259 | | | |
| | | | B | 0.269 | 2.381 | | | | 86.259 | | | |
| T14 40.00-20.00 | 6.77 | 16.32 | C | 0.269 | 2.381 | 4 | 1 | 1 | 86.259 | 1.29 | 64.28 | A |
| | | | A | 0.251 | 2.433 | | | | 86.770 | | | |
| | | | B | 0.251 | 2.433 | | | | 86.770 | | | |
| T15 20.00-0.00 | 2.76 | 15.58 | C | 0.251 | 2.433 | 4 | 1 | 1 | 86.770 | 0.94 | 47.19 | A |
| | | | A | 0.232 | 2.492 | | | | 85.936 | | | |
| | | | B | 0.232 | 2.492 | | | | 85.936 | | | |
| Sum Weight: | 63.63 | 159.99 | | 0.232 | 2.492 | | | OTM | 2272.67 kip-ft | 18.02 | | |

Tower Forces - With Ice - Wind 60 To Face

| Section Elevation ft | Add Weight K | Self Weight K | F a c e | e | C _F | q _z psf | D _F | D _R | A _E ft ² | F K | w plf | Ctrl. Face |
|-------------------------|-----------------|------------------|---------|-------|----------------|-----------------------|----------------|----------------|-----------------------------------|--------|----------|------------|
| T1 280.00-270.00 | 0.23 | 2.07 | A | 0.57 | 1.826 | 7 | 0.8 | 1 | 22.531 | 0.32 | 31.87 | C |
| | | | B | 0.57 | 1.826 | | | | 22.531 | | | |
| | | | C | 0.638 | 1.785 | | | | 26.722 | | | |
| T2 270.00-250.00 | 0.46 | 3.99 | A | 0.522 | 1.873 | 7 | 0.8 | 1 | 39.868 | 0.62 | 30.83 | C |
| | | | B | 0.522 | 1.873 | | | | 39.868 | | | |
| | | | C | 0.623 | 1.792 | | | | 51.734 | | | |
| T3 250.00-230.00 | 1.53 | 4.59 | A | 0.521 | 1.875 | 7 | 0.8 | 1 | 39.965 | 0.71 | 35.48 | C |
| | | | B | 0.521 | 1.875 | | | | 39.965 | | | |
| | | | C | 0.521 | 1.875 | | | | 39.965 | | | |

| | | |
|---|---|----------------------------------|
| tnxTower Network Building + Consulting 8601 Six Forks Road, Suite 540 Raleigh, NC 27615 Phone: 919.657.9131 FAX: | Job Woodbridge North CT | Page 28 of 52 |
| | Project NB+C ES Project Number 100765 | Date 14:34:37 12/14/20 |
| | Client Verizon | Designed by nsmith |

| Section Elevation ft | Add Weight K | Self Weight K | F a c e | e | C _F | q _z psf | D _F | D _R | A _E ft ² | F K | w plf | Ctrl. Face |
|-------------------------|-----------------|------------------|---------|-------|----------------|-----------------------|----------------|----------------|-----------------------------------|--------|----------|------------|
| T4 230.00-220.00 | 0.76 | 3.15 | C | 0.635 | 1.786 | 7 | 0.8 | 1 | 53.723 | 0.50 | 50.46 | B |
| | | | A | 0.742 | 1.785 | | 0.8 | 1 | 43.104 | | | |
| | | | B | 0.742 | 1.785 | | 0.8 | 1 | 43.104 | | | |
| T5 220.00-200.00 | 1.52 | 8.50 | C | 0.742 | 1.785 | 7 | 0.8 | 1 | 43.104 | 0.96 | 47.83 | B |
| | | | A | 0.596 | 1.806 | | 0.8 | 1 | 75.304 | | | |
| | | | B | 0.596 | 1.806 | | 0.8 | 1 | 75.304 | | | |
| T6 200.00-180.00 | 2.76 | 9.53 | C | 0.596 | 1.806 | 6 | 0.8 | 1 | 75.304 | 1.13 | 56.65 | B |
| | | | A | 0.536 | 1.858 | | 0.8 | 1 | 80.402 | | | |
| | | | B | 0.536 | 1.858 | | 0.8 | 1 | 80.402 | | | |
| T7 180.00-160.00 | 4.33 | 11.38 | C | 0.479 | 1.928 | 6 | 0.8 | 1 | 83.061 | 1.35 | 67.49 | B |
| | | | A | 0.479 | 1.928 | | 0.8 | 1 | 83.061 | | | |
| | | | B | 0.479 | 1.928 | | 0.8 | 1 | 83.061 | | | |
| T8 160.00-140.00 | 5.81 | 12.04 | C | 0.479 | 1.928 | 6 | 0.8 | 1 | 83.061 | 1.66 | 82.94 | B |
| | | | A | 0.416 | 2.033 | | 0.8 | 1 | 80.743 | | | |
| | | | B | 0.416 | 2.033 | | 0.8 | 1 | 80.743 | | | |
| T9 140.00-120.00 | 7.58 | 11.55 | C | 0.416 | 2.033 | 6 | 0.8 | 1 | 80.743 | 1.77 | 88.32 | B |
| | | | A | 0.356 | 2.157 | | 0.8 | 1 | 76.186 | | | |
| | | | B | 0.356 | 2.157 | | 0.8 | 1 | 76.186 | | | |
| T10 120.00-100.00 | 7.48 | 14.99 | C | 0.356 | 2.157 | 6 | 0.8 | 1 | 76.186 | 1.76 | 88.07 | B |
| | | | A | 0.346 | 2.181 | | 0.8 | 1 | 83.355 | | | |
| | | | B | 0.346 | 2.181 | | 0.8 | 1 | 83.355 | | | |
| T11 100.00-80.00 | 7.36 | 15.02 | C | 0.346 | 2.181 | 5 | 0.8 | 1 | 83.355 | 1.68 | 83.93 | B |
| | | | A | 0.315 | 2.258 | | 0.8 | 1 | 82.606 | | | |
| | | | B | 0.315 | 2.258 | | 0.8 | 1 | 82.606 | | | |
| T12 80.00-60.00 | 7.22 | 15.69 | C | 0.315 | 2.258 | 5 | 0.8 | 1 | 82.606 | 1.58 | 79.06 | B |
| | | | A | 0.291 | 2.32 | | 0.8 | 1 | 83.011 | | | |
| | | | B | 0.291 | 2.32 | | 0.8 | 1 | 83.011 | | | |
| T13 60.00-40.00 | 7.04 | 15.60 | C | 0.291 | 2.32 | 4 | 0.8 | 1 | 83.011 | 1.45 | 72.35 | B |
| | | | A | 0.269 | 2.381 | | 0.8 | 1 | 82.934 | | | |
| | | | B | 0.269 | 2.381 | | 0.8 | 1 | 82.934 | | | |
| T14 40.00-20.00 | 6.77 | 16.32 | C | 0.269 | 2.381 | 4 | 0.8 | 1 | 82.934 | 1.26 | 62.90 | B |
| | | | A | 0.251 | 2.433 | | 0.8 | 1 | 83.259 | | | |
| | | | B | 0.251 | 2.433 | | 0.8 | 1 | 83.259 | | | |
| T15 20.00-0.00 | 2.76 | 15.58 | C | 0.251 | 2.433 | 4 | 0.8 | 1 | 83.259 | 0.91 | 45.69 | B |
| | | | A | 0.232 | 2.492 | | 0.8 | 1 | 82.233 | | | |
| | | | B | 0.232 | 2.492 | | 0.8 | 1 | 82.233 | | | |
| Sum Weight: | 63.63 | 159.99 | | | | | | OTM | 2230.67 kip-ft | 17.65 | | |

Tower Forces - With Ice - Wind 90 To Face

| Section Elevation ft | Add Weight K | Self Weight K | F a c e | e | C _F | q _z psf | D _F | D _R | A _E ft ² | F K | w plf | Ctrl. Face |
|-------------------------|-----------------|------------------|---------|-------|----------------|-----------------------|----------------|----------------|-----------------------------------|--------|----------|------------|
| T1 280.00-270.00 | 0.23 | 2.07 | A | 0.57 | 1.826 | 7 | 0.85 | 1 | 22.531 | 0.32 | 31.87 | C |
| | | | B | 0.57 | 1.826 | | 0.85 | 1 | 22.531 | | | |
| | | | C | 0.638 | 1.785 | | 0.85 | 1 | 26.722 | | | |
| T2 270.00-250.00 | 0.46 | 3.99 | A | 0.522 | 1.873 | 7 | 0.85 | 1 | 39.868 | 0.62 | 30.83 | C |
| | | | B | 0.522 | 1.873 | | 0.85 | 1 | 39.868 | | | |
| | | | C | 0.623 | 1.792 | | 0.85 | 1 | 51.734 | | | |
| T3 250.00-230.00 | 1.53 | 4.59 | A | 0.521 | 1.875 | 7 | 0.85 | 1 | 39.965 | 0.77 | 38.36 | C |
| | | | B | 0.521 | 1.875 | | 0.85 | 1 | 39.965 | | | |

| | | |
|---|---|----------------------------------|
| tnxTower Network Building + Consulting 8601 Six Forks Road, Suite 540 Raleigh, NC 27615 Phone: 919.657.9131 FAX: | Job Woodbridge North CT | Page 29 of 52 |
| | Project NB+C ES Project Number 100765 | Date 14:34:37 12/14/20 |
| | Client Verizon | Designed by nsmith |

| Section Elevation ft | Add Weight K | Self Weight K | F a c e | e | C _F | q _z psf | D _F | D _R | A _E ft ² | F K | w plf | Ctrl. Face |
|-------------------------|-----------------|------------------|---------|-------|----------------|-----------------------|----------------|----------------|-----------------------------------|--------|----------|------------|
| T4 230.00-220.00 | 0.76 | 3.15 | C | 0.635 | 1.786 | 7 | 0.85 | 1 | 53.723 | 0.50 | 49.91 | C |
| | | | A | 0.742 | 1.785 | | 0.85 | 1 | 43.316 | | | |
| | | | B | 0.742 | 1.785 | | 0.85 | 1 | 43.316 | | | |
| T5 220.00-200.00 | 1.52 | 8.50 | C | 0.742 | 1.785 | 7 | 0.85 | 1 | 43.316 | 0.94 | 46.93 | C |
| | | | A | 0.596 | 1.806 | | 0.85 | 1 | 75.827 | | | |
| | | | B | 0.596 | 1.806 | | 0.85 | 1 | 75.827 | | | |
| T6 200.00-180.00 | 2.76 | 9.53 | C | 0.596 | 1.806 | 6 | 0.85 | 1 | 75.827 | 1.13 | 56.39 | B |
| | | | A | 0.536 | 1.858 | | 0.85 | 1 | 81.188 | | | |
| | | | B | 0.536 | 1.858 | | 0.85 | 1 | 81.188 | | | |
| T7 180.00-160.00 | 4.33 | 11.38 | C | 0.536 | 1.858 | 6 | 0.85 | 1 | 81.188 | 1.38 | 69.18 | B |
| | | | A | 0.479 | 1.928 | | 0.85 | 1 | 84.054 | | | |
| | | | B | 0.479 | 1.928 | | 0.85 | 1 | 84.054 | | | |
| T8 160.00-140.00 | 5.81 | 12.04 | C | 0.479 | 1.928 | 6 | 0.85 | 1 | 84.054 | 1.67 | 83.36 | B |
| | | | A | 0.416 | 2.033 | | 0.85 | 1 | 81.786 | | | |
| | | | B | 0.416 | 2.033 | | 0.85 | 1 | 81.786 | | | |
| T9 140.00-120.00 | 7.58 | 11.55 | C | 0.416 | 2.033 | 6 | 0.85 | 1 | 81.786 | 1.80 | 89.85 | C |
| | | | A | 0.356 | 2.157 | | 0.85 | 1 | 77.168 | | | |
| | | | B | 0.356 | 2.157 | | 0.85 | 1 | 77.168 | | | |
| T10 120.00-100.00 | 7.48 | 14.99 | C | 0.356 | 2.157 | 6 | 0.85 | 1 | 77.168 | 1.79 | 89.39 | C |
| | | | A | 0.346 | 2.181 | | 0.85 | 1 | 84.064 | | | |
| | | | B | 0.346 | 2.181 | | 0.85 | 1 | 84.064 | | | |
| T11 100.00-80.00 | 7.36 | 15.02 | C | 0.346 | 2.181 | 5 | 0.85 | 1 | 84.064 | 1.70 | 85.21 | C |
| | | | A | 0.315 | 2.258 | | 0.85 | 1 | 83.347 | | | |
| | | | B | 0.315 | 2.258 | | 0.85 | 1 | 83.347 | | | |
| T12 80.00-60.00 | 7.22 | 15.69 | C | 0.315 | 2.258 | 5 | 0.85 | 1 | 83.347 | 1.61 | 80.28 | C |
| | | | A | 0.291 | 2.32 | | 0.85 | 1 | 83.797 | | | |
| | | | B | 0.291 | 2.32 | | 0.85 | 1 | 83.797 | | | |
| T13 60.00-40.00 | 7.04 | 15.60 | C | 0.291 | 2.32 | 4 | 0.85 | 1 | 83.797 | 1.47 | 73.49 | C |
| | | | A | 0.269 | 2.381 | | 0.85 | 1 | 83.765 | | | |
| | | | B | 0.269 | 2.381 | | 0.85 | 1 | 83.765 | | | |
| T14 40.00-20.00 | 6.77 | 16.32 | C | 0.269 | 2.381 | 4 | 0.85 | 1 | 83.765 | 1.28 | 63.91 | C |
| | | | A | 0.251 | 2.433 | | 0.85 | 1 | 84.137 | | | |
| | | | B | 0.251 | 2.433 | | 0.85 | 1 | 84.137 | | | |
| T15 20.00-0.00 | 2.76 | 15.58 | C | 0.251 | 2.433 | 4 | 0.85 | 1 | 84.137 | 0.92 | 46.09 | C |
| | | | A | 0.232 | 2.492 | | 0.85 | 1 | 83.159 | | | |
| | | | B | 0.232 | 2.492 | | 0.85 | 1 | 83.159 | | | |
| Sum Weight: | 63.63 | 159.99 | C | 0.232 | 2.492 | | 0.85 | 1 | 83.159 | 17.88 | | |
| | | | | | | | | OTM | 2258.26 kip-ft | | | |

Tower Forces - Service - Wind Normal To Face

| Section Elevation ft | Add Weight K | Self Weight K | F a c e | e | C _F | q _z psf | D _F | D _R | A _E ft ² | F K | w plf | Ctrl. Face |
|-------------------------|-----------------|------------------|---------|-------|----------------|-----------------------|----------------|----------------|-----------------------------------|--------|----------|------------|
| T1 280.00-270.00 | 0.03 | 0.66 | A | 0.141 | 2.806 | 10 | 1 | 1 | 4.100 | 0.14 | 14.03 | C |
| | | | B | 0.141 | 2.806 | | 1 | 1 | 4.100 | | | |
| | | | C | 0.154 | 2.756 | | 1 | 1 | 4.512 | | | |
| T2 270.00-250.00 | 0.07 | 1.37 | A | 0.137 | 2.821 | 10 | 1 | 1 | 7.995 | 0.28 | 14.00 | C |
| | | | B | 0.137 | 2.821 | | 1 | 1 | 7.995 | | | |
| | | | C | 0.157 | 2.746 | | 1 | 1 | 9.225 | | | |
| T3 250.00-230.00 | 0.21 | 1.91 | A | 0.157 | 2.744 | 10 | 1 | 1 | 9.323 | 0.46 | 22.83 | A |
| | | | B | 0.157 | 2.744 | | 1 | 1 | 9.323 | | | |

| | | |
|---|---|----------------------------------|
| tnxTower Network Building + Consulting 8601 Six Forks Road, Suite 540 Raleigh, NC 27615 Phone: 919.657.9131 FAX: | Job Woodbridge North CT | Page 30 of 52 |
| | Project NB+C ES Project Number 100765 | Date 14:34:37 12/14/20 |
| | Client Verizon | Designed by nsmith |

| Section Elevation ft | Add Weight K | Self Weight K | F a c e | e | C _F | q _z psf | D _F | D _R | A _E ft ² | F K | w plf | Ctrl. Face |
|-------------------------|-----------------|------------------|---------|-------|----------------|-----------------------|----------------|----------------|-----------------------------------|--------|----------|------------|
| T4 230.00-220.00 | 0.11 | 1.23 | C | 0.181 | 2.661 | 10 | 1 | 1 | 10.771 | 0.40 | 40.17 | A |
| | | | A | 0.345 | 2.184 | | | | 15.657 | | | |
| | | | B | 0.345 | 2.184 | | | | 15.657 | | | |
| T5 220.00-200.00 | 0.21 | 2.70 | C | 0.345 | 2.184 | 10 | 1 | 1 | 15.657 | 0.76 | 37.81 | A |
| | | | A | 0.225 | 2.514 | | | | 25.670 | | | |
| | | | B | 0.225 | 2.514 | | | | 25.670 | | | |
| T6 200.00-180.00 | 0.43 | 2.95 | C | 0.225 | 2.514 | 9 | 1 | 1 | 25.670 | 0.98 | 49.01 | A |
| | | | A | 0.207 | 2.574 | | | | 30.821 | | | |
| | | | B | 0.207 | 2.574 | | | | 30.821 | | | |
| T7 180.00-160.00 | 0.70 | 4.20 | C | 0.207 | 2.574 | 9 | 1 | 1 | 30.821 | 1.28 | 64.18 | C |
| | | | A | 0.198 | 2.603 | | | | 36.106 | | | |
| | | | B | 0.198 | 2.603 | | | | 36.106 | | | |
| T8 160.00-140.00 | 0.90 | 4.86 | C | 0.198 | 2.603 | 9 | 1 | 1 | 36.106 | 1.43 | 71.26 | C |
| | | | A | 0.179 | 2.668 | | | | 37.951 | | | |
| | | | B | 0.179 | 2.668 | | | | 37.951 | | | |
| T9 140.00-120.00 | 1.20 | 4.75 | C | 0.179 | 2.668 | 8 | 1 | 1 | 37.951 | 1.52 | 75.89 | C |
| | | | A | 0.153 | 2.761 | | | | 36.612 | | | |
| | | | B | 0.153 | 2.761 | | | | 36.612 | | | |
| T10 120.00-100.00 | 1.20 | 7.08 | C | 0.153 | 2.761 | 8 | 1 | 1 | 36.612 | 1.46 | 73.05 | C |
| | | | A | 0.145 | 2.789 | | | | 36.980 | | | |
| | | | B | 0.145 | 2.789 | | | | 36.980 | | | |
| T11 100.00-80.00 | 1.20 | 7.19 | C | 0.145 | 2.789 | 8 | 1 | 1 | 36.980 | 1.40 | 70.07 | C |
| | | | A | 0.133 | 2.836 | | | | 37.573 | | | |
| | | | B | 0.133 | 2.836 | | | | 37.573 | | | |
| T12 80.00-60.00 | 1.20 | 7.93 | C | 0.133 | 2.836 | 7 | 1 | 1 | 37.573 | 1.34 | 66.97 | C |
| | | | A | 0.126 | 2.86 | | | | 39.313 | | | |
| | | | B | 0.126 | 2.86 | | | | 39.313 | | | |
| T13 60.00-40.00 | 1.20 | 8.05 | C | 0.126 | 2.86 | 6 | 1 | 1 | 39.313 | 1.24 | 61.87 | C |
| | | | A | 0.118 | 2.893 | | | | 40.204 | | | |
| | | | B | 0.118 | 2.893 | | | | 40.204 | | | |
| T14 40.00-20.00 | 1.20 | 9.01 | C | 0.118 | 2.893 | 5 | 1 | 1 | 40.204 | 1.10 | 55.05 | C |
| | | | A | 0.115 | 2.905 | | | | 42.375 | | | |
| | | | B | 0.115 | 2.905 | | | | 42.375 | | | |
| T15 20.00-0.00 | 0.57 | 9.15 | C | 0.115 | 2.905 | 5 | 1 | 1 | 42.375 | 0.82 | 40.94 | C |
| | | | A | 0.109 | 2.93 | | | | 43.319 | | | |
| | | | B | 0.109 | 2.93 | | | | 43.319 | | | |
| Sum Weight: | 10.43 | 73.02 | | | | | | OTM | 1769.38 kip-ft | 14.60 | | |

Tower Forces - Service - Wind 60 To Face

| Section Elevation ft | Add Weight K | Self Weight K | F a c e | e | C _F | q _z psf | D _F | D _R | A _E ft ² | F K | w plf | Ctrl. Face |
|-------------------------|-----------------|------------------|---------|-------|----------------|-----------------------|----------------|----------------|-----------------------------------|--------|----------|------------|
| T1 280.00-270.00 | 0.03 | 0.66 | A | 0.141 | 2.806 | 10 | 0.8 | 1 | 4.100 | 0.14 | 14.03 | C |
| | | | B | 0.141 | 2.806 | | | | 4.100 | | | |
| | | | C | 0.154 | 2.756 | | | | 4.512 | | | |
| T2 270.00-250.00 | 0.07 | 1.37 | A | 0.137 | 2.821 | 10 | 0.8 | 1 | 7.995 | 0.28 | 14.00 | C |
| | | | B | 0.137 | 2.821 | | | | 7.995 | | | |
| | | | C | 0.157 | 2.746 | | | | 9.225 | | | |
| T3 250.00-230.00 | 0.21 | 1.91 | A | 0.157 | 2.744 | 10 | 0.8 | 1 | 9.323 | 0.46 | 22.83 | B |
| | | | B | 0.157 | 2.744 | | | | 9.323 | | | |

| | | |
|---|---|----------------------------------|
| tnxTower Network Building + Consulting 8601 Six Forks Road, Suite 540 Raleigh, NC 27615 Phone: 919.657.9131 FAX: | Job Woodbridge North CT | Page 31 of 52 |
| | Project NB+C ES Project Number 100765 | Date 14:34:37 12/14/20 |
| | Client Verizon | Designed by nsmith |

| Section Elevation ft | Add Weight K | Self Weight K | F a c e | e | C _F | q _z psf | D _F | D _R | A _E ft ² | F K | w plf | Ctrl. Face |
|-------------------------|-----------------|------------------|---------|-------|----------------|-----------------------|----------------|----------------|-----------------------------------|--------|----------|------------|
| T4 230.00-220.00 | 0.11 | 1.23 | C | 0.181 | 2.661 | 10 | 0.8 | 1 | 10.771 | 0.39 | 38.63 | B |
| | | | A | 0.345 | 2.184 | | 0.8 | 1 | 14.810 | | | |
| | | | B | 0.345 | 2.184 | | 0.8 | 1 | 14.810 | | | |
| T5 220.00-200.00 | 0.21 | 2.70 | C | 0.345 | 2.184 | 10 | 0.8 | 1 | 14.810 | 0.71 | 35.67 | B |
| | | | A | 0.225 | 2.514 | | 0.8 | 1 | 23.577 | | | |
| | | | B | 0.225 | 2.514 | | 0.8 | 1 | 23.577 | | | |
| T6 200.00-180.00 | 0.43 | 2.95 | C | 0.225 | 2.514 | 9 | 0.8 | 1 | 23.577 | 0.92 | 45.81 | B |
| | | | A | 0.207 | 2.574 | | 0.8 | 1 | 27.678 | | | |
| | | | B | 0.207 | 2.574 | | 0.8 | 1 | 27.678 | | | |
| T7 180.00-160.00 | 0.70 | 4.20 | C | 0.207 | 2.574 | 9 | 0.8 | 1 | 27.678 | 1.20 | 60.22 | A |
| | | | A | 0.198 | 2.603 | | 0.8 | 1 | 32.135 | | | |
| | | | B | 0.198 | 2.603 | | 0.8 | 1 | 32.135 | | | |
| T8 160.00-140.00 | 0.90 | 4.86 | C | 0.198 | 2.603 | 9 | 0.8 | 1 | 32.135 | 1.34 | 67.14 | A |
| | | | A | 0.179 | 2.668 | | 0.8 | 1 | 33.776 | | | |
| | | | B | 0.179 | 2.668 | | 0.8 | 1 | 33.776 | | | |
| T9 140.00-120.00 | 1.20 | 4.75 | C | 0.179 | 2.668 | 8 | 0.8 | 1 | 33.776 | 1.44 | 72.05 | A |
| | | | A | 0.153 | 2.761 | | 0.8 | 1 | 32.685 | | | |
| | | | B | 0.153 | 2.761 | | 0.8 | 1 | 32.685 | | | |
| T10 120.00-100.00 | 1.20 | 7.08 | C | 0.153 | 2.761 | 8 | 0.8 | 1 | 32.685 | 1.41 | 70.37 | A |
| | | | A | 0.145 | 2.789 | | 0.8 | 1 | 34.142 | | | |
| | | | B | 0.145 | 2.789 | | 0.8 | 1 | 34.142 | | | |
| T11 100.00-80.00 | 1.20 | 7.19 | C | 0.145 | 2.789 | 8 | 0.8 | 1 | 34.142 | 1.35 | 67.39 | A |
| | | | A | 0.133 | 2.836 | | 0.8 | 1 | 34.608 | | | |
| | | | B | 0.133 | 2.836 | | 0.8 | 1 | 34.608 | | | |
| T12 80.00-60.00 | 1.20 | 7.93 | C | 0.133 | 2.836 | 7 | 0.8 | 1 | 34.608 | 1.29 | 64.30 | A |
| | | | A | 0.126 | 2.86 | | 0.8 | 1 | 36.171 | | | |
| | | | B | 0.126 | 2.86 | | 0.8 | 1 | 36.171 | | | |
| T13 60.00-40.00 | 1.20 | 8.05 | C | 0.126 | 2.86 | 6 | 0.8 | 1 | 36.171 | 1.19 | 59.28 | A |
| | | | A | 0.118 | 2.893 | | 0.8 | 1 | 36.879 | | | |
| | | | B | 0.118 | 2.893 | | 0.8 | 1 | 36.879 | | | |
| T14 40.00-20.00 | 1.20 | 9.01 | C | 0.118 | 2.893 | 5 | 0.8 | 1 | 36.879 | 1.05 | 52.67 | A |
| | | | A | 0.115 | 2.905 | | 0.8 | 1 | 38.864 | | | |
| | | | B | 0.115 | 2.905 | | 0.8 | 1 | 38.864 | | | |
| T15 20.00-0.00 | 0.57 | 9.15 | C | 0.115 | 2.905 | 5 | 0.8 | 1 | 38.864 | 0.77 | 38.41 | A |
| | | | A | 0.109 | 2.93 | | 0.8 | 1 | 39.616 | | | |
| | | | B | 0.109 | 2.93 | | 0.8 | 1 | 39.616 | | | |
| Sum Weight: | 10.43 | 73.02 | | | | | | OTM | 1690.01 kip-ft | 13.93 | | |

Tower Forces - Service - Wind 90 To Face

| Section Elevation ft | Add Weight K | Self Weight K | F a c e | e | C _F | q _z psf | D _F | D _R | A _E ft ² | F K | w plf | Ctrl. Face |
|-------------------------|-----------------|------------------|---------|-------|----------------|-----------------------|----------------|----------------|-----------------------------------|--------|----------|------------|
| T1 280.00-270.00 | 0.03 | 0.66 | A | 0.141 | 2.806 | 10 | 0.85 | 1 | 4.100 | 0.14 | 14.03 | C |
| | | | B | 0.141 | 2.806 | | 0.85 | 1 | 4.100 | | | |
| | | | C | 0.154 | 2.756 | | 0.85 | 1 | 4.512 | | | |
| T2 270.00-250.00 | 0.07 | 1.37 | A | 0.137 | 2.821 | 10 | 0.85 | 1 | 7.995 | 0.28 | 14.00 | C |
| | | | B | 0.137 | 2.821 | | 0.85 | 1 | 7.995 | | | |
| | | | C | 0.157 | 2.746 | | 0.85 | 1 | 9.225 | | | |
| T3 250.00-230.00 | 0.21 | 1.91 | A | 0.157 | 2.744 | 10 | 0.85 | 1 | 9.323 | 0.48 | 24.13 | C |
| | | | B | 0.157 | 2.744 | | 0.85 | 1 | 9.323 | | | |

| | | | | |
|---|----------------|-------------------------------|--------------------|-------------------|
| tnxTower Network Building + Consulting 8601 Six Forks Road, Suite 540 Raleigh, NC 27615 Phone: 919.657.9131 FAX: | Job | Woodbridge North CT | Page | 32 of 52 |
| | Project | NB+C ES Project Number 100765 | Date | 14:34:37 12/14/20 |
| | Client | Verizon | Designed by | nsmith |

| Section Elevation ft | Add Weight K | Self Weight K | F a c e | e | C _F | q _z psf | D _F | D _R | A _E ft ² | F K | w plf | Ctrl. Face |
|----------------------------|--------------------|---------------------|------------------|-------|----------------|-----------------------|----------------|----------------|-----------------------------------|--------|----------|---------------|
| T4 230.00-220.00 | 0.11 | 1.23 | C | 0.181 | 2.661 | | 0.85 | 1 | 10.771 | | | |
| | | | A | 0.345 | 2.184 | 10 | 0.85 | 1 | 15.022 | 0.39 | 39.02 | C |
| | | | B | 0.345 | 2.184 | | 0.85 | 1 | 15.022 | | | |
| T5 220.00-200.00 | 0.21 | 2.70 | C | 0.345 | 2.184 | | 0.85 | 1 | 15.022 | | | |
| | | | A | 0.225 | 2.514 | 10 | 0.85 | 1 | 24.100 | 0.72 | 36.21 | C |
| | | | B | 0.225 | 2.514 | | 0.85 | 1 | 24.100 | | | |
| T6 200.00-180.00 | 0.43 | 2.95 | C | 0.225 | 2.514 | | 0.85 | 1 | 24.100 | | | |
| | | | A | 0.207 | 2.574 | 9 | 0.85 | 1 | 28.464 | 0.96 | 47.83 | B |
| | | | B | 0.207 | 2.574 | | 0.85 | 1 | 28.464 | | | |
| T7 180.00-160.00 | 0.70 | 4.20 | C | 0.207 | 2.574 | | 0.85 | 1 | 28.464 | | | |
| | | | A | 0.198 | 2.603 | 9 | 0.85 | 1 | 33.128 | 1.25 | 62.39 | B |
| | | | B | 0.198 | 2.603 | | 0.85 | 1 | 33.128 | | | |
| T8 160.00-140.00 | 0.90 | 4.86 | C | 0.198 | 2.603 | | 0.85 | 1 | 33.128 | | | |
| | | | A | 0.179 | 2.668 | 9 | 0.85 | 1 | 34.819 | 1.43 | 71.60 | B |
| | | | B | 0.179 | 2.668 | | 0.85 | 1 | 34.819 | | | |
| T9 140.00-120.00 | 1.20 | 4.75 | C | 0.179 | 2.668 | | 0.85 | 1 | 34.819 | | | |
| | | | A | 0.153 | 2.761 | 8 | 0.85 | 1 | 33.667 | 1.49 | 74.47 | C |
| | | | B | 0.153 | 2.761 | | 0.85 | 1 | 33.667 | | | |
| T10 120.00-100.00 | 1.20 | 7.08 | C | 0.153 | 2.761 | | 0.85 | 1 | 33.667 | | | |
| | | | A | 0.145 | 2.789 | 8 | 0.85 | 1 | 34.852 | 1.45 | 72.44 | C |
| | | | B | 0.145 | 2.789 | | 0.85 | 1 | 34.852 | | | |
| T11 100.00-80.00 | 1.20 | 7.19 | C | 0.145 | 2.789 | | 0.85 | 1 | 34.852 | | | |
| | | | A | 0.133 | 2.836 | 8 | 0.85 | 1 | 35.349 | 1.39 | 69.37 | C |
| | | | B | 0.133 | 2.836 | | 0.85 | 1 | 35.349 | | | |
| T12 80.00-60.00 | 1.20 | 7.93 | C | 0.133 | 2.836 | | 0.85 | 1 | 35.349 | | | |
| | | | A | 0.126 | 2.86 | 7 | 0.85 | 1 | 36.956 | 1.32 | 66.19 | C |
| | | | B | 0.126 | 2.86 | | 0.85 | 1 | 36.956 | | | |
| T13 60.00-40.00 | 1.20 | 8.05 | C | 0.126 | 2.86 | | 0.85 | 1 | 36.956 | | | |
| | | | A | 0.118 | 2.893 | 6 | 0.85 | 1 | 37.710 | 1.22 | 61.04 | C |
| | | | B | 0.118 | 2.893 | | 0.85 | 1 | 37.710 | | | |
| T14 40.00-20.00 | 1.20 | 9.01 | C | 0.118 | 2.893 | | 0.85 | 1 | 37.710 | | | |
| | | | A | 0.115 | 2.905 | 5 | 0.85 | 1 | 39.741 | 1.08 | 54.23 | C |
| | | | B | 0.115 | 2.905 | | 0.85 | 1 | 39.741 | | | |
| T15 20.00-0.00 | 0.57 | 9.15 | C | 0.115 | 2.905 | | 0.85 | 1 | 39.741 | | | |
| | | | A | 0.109 | 2.93 | 5 | 0.85 | 1 | 40.542 | 0.78 | 38.94 | C |
| | | | B | 0.109 | 2.93 | | 0.85 | 1 | 40.542 | | | |
| Sum Weight: | 10.43 | 73.02 | C | 0.109 | 2.93 | | 0.85 | 1 | 40.542 | | | |
| | | | | | | | | OTM | 1747.62 kip-ft | 14.39 | | |

Force Totals

| Load Case | Vertical Forces K | Sum of Forces X K | Sum of Forces Z K | Sum of Overturning Moments, M _x kip-ft | Sum of Overturning Moments, M _z kip-ft | Sum of Torques kip-ft |
|--------------------------|-------------------------|----------------------------|----------------------------|--|--|--------------------------|
| Leg Weight | 49.47 | | | | | |
| Bracing Weight | 23.55 | | | | | |
| Total Member Self-Weight | 73.02 | | | | | |
| Total Weight | 104.93 | | | -4.66 | 1.24 | |
| Wind 0 deg - No Ice | | | | -4.66 | 1.24 | |
| Wind 30 deg - No Ice | | -0.01 | -51.47 | -7285.32 | 2.04 | -24.99 |
| Wind 60 deg - No Ice | | 24.30 | -42.10 | -5968.06 | -3440.81 | 3.41 |
| Wind 90 deg - No Ice | | 41.97 | -24.23 | -3456.75 | -5977.95 | -0.39 |
| Wind 180 deg - No Ice | | 50.54 | 0.01 | -3.86 | -7184.97 | -28.27 |

| | | |
|---|---|----------------------------------|
| tnxTower Network Building + Consulting 8601 Six Forks Road, Suite 540 Raleigh, NC 27615 Phone: 919.657.9131 FAX: | Job Woodbridge North CT | Page 33 of 52 |
| | Project NB+C ES Project Number 100765 | Date 14:34:37 12/14/20 |
| | Client Verizon | Designed by nsmith |

| Load Case | Vertical Forces K | Sum of Forces X K | Sum of Forces Z K | Sum of Overturning Moments, M_x kip-ft | Sum of Overturning Moments, M_z kip-ft | Sum of Torques kip-ft |
|------------------------|----------------------|-------------------------|-------------------------|---|---|--------------------------|
| Wind 120 deg - No Ice | | 44.23 | 25.54 | 3632.95 | -6297.69 | -25.19 |
| Wind 150 deg - No Ice | | 25.27 | 43.76 | 6253.43 | -3611.86 | 7.95 |
| Wind 180 deg - No Ice | | 0.01 | 49.57 | 7030.13 | 0.45 | 24.99 |
| Wind 210 deg - No Ice | | -24.23 | 41.97 | 5925.47 | 3424.09 | -3.41 |
| Wind 240 deg - No Ice | | -43.36 | 25.04 | 3531.94 | 6126.81 | 0.39 |
| Wind 270 deg - No Ice | | -50.38 | -0.01 | -5.45 | 7149.04 | 28.27 |
| Wind 300 deg - No Ice | | -42.71 | -24.67 | -3538.54 | 6120.52 | 25.19 |
| Wind 330 deg - No Ice | | -25.27 | -43.76 | -6262.74 | 3614.35 | -7.95 |
| Member Ice | 86.97 | | | | | |
| Total Weight Ice | 288.31 | | | -44.74 | 17.18 | |
| Wind 0 deg - Ice | | -0.00 | -24.64 | -3747.91 | 17.42 | -8.75 |
| Wind 30 deg - Ice | | 12.11 | -20.98 | -3193.53 | -1800.50 | 0.86 |
| Wind 60 deg - Ice | | 21.19 | -12.23 | -1875.51 | -3153.80 | 2.70 |
| Wind 90 deg - Ice | | 25.05 | 0.00 | -44.50 | -3727.02 | -10.43 |
| Wind 120 deg - Ice | | 21.82 | 12.60 | 1826.88 | -3224.07 | -13.23 |
| Wind 150 deg - Ice | | 12.29 | 21.29 | 3137.95 | -1820.34 | 1.77 |
| Wind 180 deg - Ice | | 0.00 | 24.01 | 3547.64 | 16.95 | 8.75 |
| Wind 210 deg - Ice | | -11.97 | 20.74 | 3044.48 | 1800.47 | -0.86 |
| Wind 240 deg - Ice | | -21.27 | 12.28 | 1772.64 | 3164.97 | -2.70 |
| Wind 270 deg - Ice | | -24.77 | -0.00 | -44.97 | 3692.60 | 10.43 |
| Wind 300 deg - Ice | | -21.50 | -12.42 | -1895.35 | 3222.06 | 13.23 |
| Wind 330 deg - Ice | | -12.29 | -21.29 | -3227.42 | 1854.71 | -1.77 |
| Total Weight | 104.93 | | | -4.66 | 1.24 | |
| Wind 0 deg - Service | | -0.00 | -19.69 | -2785.51 | -0.70 | -9.56 |
| Wind 30 deg - Service | | 9.30 | -16.11 | -2281.51 | -1317.98 | 1.30 |
| Wind 60 deg - Service | | 16.06 | -9.27 | -1320.65 | -2288.72 | -0.15 |
| Wind 90 deg - Service | | 19.34 | 0.00 | 0.46 | -2750.54 | -10.82 |
| Wind 120 deg - Service | | 16.92 | 9.77 | 1391.95 | -2411.06 | -9.64 |
| Wind 150 deg - Service | | 9.67 | 16.74 | 2394.58 | -1383.43 | 3.04 |
| Wind 180 deg - Service | | 0.00 | 18.96 | 2691.76 | -1.31 | 9.56 |
| Wind 210 deg - Service | | -9.27 | 16.06 | 2269.10 | 1308.61 | -1.30 |
| Wind 240 deg - Service | | -16.59 | 9.58 | 1353.31 | 2342.71 | 0.15 |
| Wind 270 deg - Service | | -19.28 | -0.00 | -0.14 | 2733.83 | 10.82 |
| Wind 300 deg - Service | | -16.34 | -9.44 | -1351.95 | 2340.30 | 9.64 |
| Wind 330 deg - Service | | -9.67 | -16.74 | -2394.26 | 1381.41 | -3.04 |

Load Combinations

| Comb. No. | Description |
|-----------|------------------------------------|
| 1 | Dead Only |
| 2 | 1.2 Dead+1.6 Wind 0 deg - No Ice |
| 3 | 0.9 Dead+1.6 Wind 0 deg - No Ice |
| 4 | 1.2 Dead+1.6 Wind 30 deg - No Ice |
| 5 | 0.9 Dead+1.6 Wind 30 deg - No Ice |
| 6 | 1.2 Dead+1.6 Wind 60 deg - No Ice |
| 7 | 0.9 Dead+1.6 Wind 60 deg - No Ice |
| 8 | 1.2 Dead+1.6 Wind 90 deg - No Ice |
| 9 | 0.9 Dead+1.6 Wind 90 deg - No Ice |
| 10 | 1.2 Dead+1.6 Wind 120 deg - No Ice |
| 11 | 0.9 Dead+1.6 Wind 120 deg - No Ice |
| 12 | 1.2 Dead+1.6 Wind 150 deg - No Ice |
| 13 | 0.9 Dead+1.6 Wind 150 deg - No Ice |
| 14 | 1.2 Dead+1.6 Wind 180 deg - No Ice |
| 15 | 0.9 Dead+1.6 Wind 180 deg - No Ice |
| 16 | 1.2 Dead+1.6 Wind 210 deg - No Ice |

| | | |
|---|---|----------------------------------|
| tnxTower Network Building + Consulting 8601 Six Forks Road, Suite 540 Raleigh, NC 27615 Phone: 919.657.9131 FAX: | Job Woodbridge North CT | Page 34 of 52 |
| | Project NB+C ES Project Number 100765 | Date 14:34:37 12/14/20 |
| | Client Verizon | Designed by nsmith |

| Comb. No. | Description |
|-----------|--|
| 17 | 0.9 Dead+1.6 Wind 210 deg - No Ice |
| 18 | 1.2 Dead+1.6 Wind 240 deg - No Ice |
| 19 | 0.9 Dead+1.6 Wind 240 deg - No Ice |
| 20 | 1.2 Dead+1.6 Wind 270 deg - No Ice |
| 21 | 0.9 Dead+1.6 Wind 270 deg - No Ice |
| 22 | 1.2 Dead+1.6 Wind 300 deg - No Ice |
| 23 | 0.9 Dead+1.6 Wind 300 deg - No Ice |
| 24 | 1.2 Dead+1.6 Wind 330 deg - No Ice |
| 25 | 0.9 Dead+1.6 Wind 330 deg - No Ice |
| 26 | 1.2 Dead+1.0 Ice+1.0 Temp |
| 27 | 1.2 Dead+1.0 Wind 0 deg+1.0 Ice+1.0 Temp |
| 28 | 1.2 Dead+1.0 Wind 30 deg+1.0 Ice+1.0 Temp |
| 29 | 1.2 Dead+1.0 Wind 60 deg+1.0 Ice+1.0 Temp |
| 30 | 1.2 Dead+1.0 Wind 90 deg+1.0 Ice+1.0 Temp |
| 31 | 1.2 Dead+1.0 Wind 120 deg+1.0 Ice+1.0 Temp |
| 32 | 1.2 Dead+1.0 Wind 150 deg+1.0 Ice+1.0 Temp |
| 33 | 1.2 Dead+1.0 Wind 180 deg+1.0 Ice+1.0 Temp |
| 34 | 1.2 Dead+1.0 Wind 210 deg+1.0 Ice+1.0 Temp |
| 35 | 1.2 Dead+1.0 Wind 240 deg+1.0 Ice+1.0 Temp |
| 36 | 1.2 Dead+1.0 Wind 270 deg+1.0 Ice+1.0 Temp |
| 37 | 1.2 Dead+1.0 Wind 300 deg+1.0 Ice+1.0 Temp |
| 38 | 1.2 Dead+1.0 Wind 330 deg+1.0 Ice+1.0 Temp |
| 39 | Dead+Wind 0 deg - Service |
| 40 | Dead+Wind 30 deg - Service |
| 41 | Dead+Wind 60 deg - Service |
| 42 | Dead+Wind 90 deg - Service |
| 43 | Dead+Wind 120 deg - Service |
| 44 | Dead+Wind 150 deg - Service |
| 45 | Dead+Wind 180 deg - Service |
| 46 | Dead+Wind 210 deg - Service |
| 47 | Dead+Wind 240 deg - Service |
| 48 | Dead+Wind 270 deg - Service |
| 49 | Dead+Wind 300 deg - Service |
| 50 | Dead+Wind 330 deg - Service |

Maximum Member Forces

| Section No. | Elevation ft | Component Type | Condition | Gov. Load Comb. | Axial K | Major Axis Moment kip-ft | Minor Axis Moment kip-ft |
|-------------|--------------|----------------|------------------|-----------------|---------|--------------------------|--------------------------|
| T1 | 280 - 270 | Leg | Max Tension | 7 | 6.25 | 0.47 | -0.20 |
| | | | Max. Compression | 10 | -9.03 | -0.16 | -0.09 |
| | | | Max. Mx | 8 | -8.07 | 0.52 | -0.01 |
| | | | Max. My | 2 | -1.39 | -0.04 | 0.53 |
| | | | Max. Vy | 8 | 1.30 | -0.18 | -0.01 |
| | | Diagonal | Max. Vx | 2 | -1.29 | 0.02 | 0.19 |
| | | | Max Tension | 8 | 1.70 | 0.00 | 0.00 |
| | | | Max. Compression | 8 | -1.75 | 0.00 | 0.00 |
| | | | Max. Mx | 33 | 0.77 | -0.01 | 0.00 |
| | | | Max. My | 6 | -1.41 | -0.00 | 0.00 |
| | | Horizontal | Max. Vy | 32 | 0.01 | -0.01 | -0.00 |
| | | | Max. Vx | 6 | 0.00 | 0.00 | 0.00 |
| | | | Max Tension | 14 | 0.26 | 0.00 | 0.00 |
| | | | Max. Compression | 3 | -0.17 | 0.00 | 0.00 |
| | | | Max. Mx | 26 | 0.13 | 0.03 | 0.00 |
| | | Top Girt | Max. My | 35 | 0.17 | 0.00 | 0.00 |
| | | | Max. Vy | 26 | -0.02 | 0.00 | 0.00 |
| | | | Max. Vx | 35 | -0.00 | 0.00 | 0.00 |
| | | | Max Tension | 18 | 0.70 | 0.00 | 0.00 |

| | | | | |
|---|----------------|-------------------------------|--------------------|-------------------|
| tnxTower Network Building + Consulting 8601 Six Forks Road, Suite 540 Raleigh, NC 27615 Phone: 919.657.9131 FAX: | Job | Woodbridge North CT | Page | 35 of 52 |
| | Project | NB+C ES Project Number 100765 | Date | 14:34:37 12/14/20 |
| | Client | Verizon | Designed by | nsmith |

| Section No. | Elevation ft | Component Type | Condition | Gov. Load Comb. | Axial K | Major Axis Moment kip-ft | Minor Axis Moment kip-ft | |
|-------------|------------------|------------------|------------------|------------------|---------|--------------------------|--------------------------|-------|
| T2 | 270 - 250 | Bottom Girt | Max. Compression | 6 | -0.71 | 0.00 | 0.00 | |
| | | | Max. Mx | 26 | -0.03 | 0.03 | 0.00 | |
| | | | Max. My | 28 | -0.03 | 0.00 | -0.00 | |
| | | | Max. Vy | 26 | -0.02 | 0.00 | 0.00 | |
| | | | Max. Vx | 28 | 0.00 | 0.00 | 0.00 | |
| | | | Max Tension | 14 | 0.71 | 0.00 | 0.00 | |
| | | | Max. Compression | 10 | -0.68 | 0.00 | 0.00 | |
| | | | Max. Mx | 26 | 0.04 | 0.03 | 0.00 | |
| | | | Max. My | 28 | 0.04 | 0.00 | -0.00 | |
| | | | Max. Vy | 26 | -0.02 | 0.00 | 0.00 | |
| | | | Max. Vx | 28 | 0.00 | 0.00 | 0.00 | |
| | | | Max Tension | 33 | 0.13 | 0.00 | 0.00 | |
| | | Mid Girt | Max. Compression | 3 | -0.01 | 0.00 | 0.00 | |
| | | | Max. Mx | 26 | 0.01 | 0.03 | 0.00 | |
| | | | Max. My | 28 | 0.01 | 0.00 | -0.00 | |
| | | | Max. Vy | 26 | -0.02 | 0.00 | 0.00 | |
| | | | Max. Vx | 28 | 0.00 | 0.00 | 0.00 | |
| | | | Max Tension | 7 | 24.83 | 0.62 | -0.31 | |
| | | | Leg | Max. Compression | 2 | -28.59 | 0.01 | 0.30 |
| | | | | Max. Mx | 8 | -9.24 | -0.78 | -0.00 |
| | | | | Max. My | 2 | -8.88 | 0.08 | 0.78 |
| | | | | Max. Vy | 8 | 1.80 | -0.28 | -0.04 |
| | | | | Max. Vx | 2 | -1.86 | 0.01 | 0.30 |
| | | | | Max Tension | 8 | 2.25 | 0.00 | 0.00 |
| | | Diagonal | | Max. Compression | 8 | -2.30 | 0.00 | 0.00 |
| | | | | Max. Mx | 34 | 0.82 | -0.01 | -0.00 |
| | | | | Max. My | 6 | -1.70 | -0.00 | 0.00 |
| | | | | Max. Vy | 34 | 0.01 | -0.01 | -0.00 |
| | | | | Max. Vx | 6 | 0.00 | 0.00 | 0.00 |
| | | | | Max Tension | 14 | 0.42 | 0.00 | 0.00 |
| | | | Horizontal | Max. Compression | 3 | -0.33 | 0.00 | 0.00 |
| | | | | Max. Mx | 26 | 0.16 | 0.03 | 0.00 |
| | | | | Max. My | 22 | -0.13 | 0.00 | -0.00 |
| | | | | Max. Vy | 26 | -0.02 | 0.00 | 0.00 |
| | | | | Max. Vx | 22 | 0.00 | 0.00 | 0.00 |
| | | | | Max Tension | 10 | 0.79 | 0.00 | 0.00 |
| | | Top Girt | | Max. Compression | 6 | -0.80 | 0.00 | 0.00 |
| | | | | Max. Mx | 26 | -0.01 | 0.03 | 0.00 |
| | | | | Max. My | 28 | -0.02 | 0.00 | -0.00 |
| | | | | Max. Vy | 26 | 0.02 | 0.00 | 0.00 |
| | | | | Max. Vx | 28 | -0.00 | 0.00 | 0.00 |
| | | | | Max Tension | 14 | 0.92 | 0.00 | 0.00 |
| Bottom Girt | Max. Compression | | 3 | -0.90 | 0.00 | 0.00 | | |
| | Max. Mx | | 26 | 0.05 | 0.03 | 0.00 | | |
| | Max. My | | 22 | -0.37 | 0.00 | -0.00 | | |
| | Max. Vy | | 26 | 0.02 | 0.00 | 0.00 | | |
| | Max. Vx | | 22 | 0.00 | 0.00 | 0.00 | | |
| | Max Tension | | 14 | 0.27 | 0.00 | 0.00 | | |
| | Mid Girt | Max. Compression | 3 | -0.18 | 0.00 | 0.00 | | |
| | | Max. Mx | 26 | 0.04 | 0.03 | 0.00 | | |
| | | Max. My | 10 | 0.06 | 0.00 | 0.00 | | |
| | | Max. Vy | 26 | 0.02 | 0.00 | 0.00 | | |
| | | Max. Vx | 10 | 0.00 | 0.00 | 0.00 | | |
| | | Max Tension | 7 | 64.38 | 0.39 | -0.19 | | |
| Leg | | Max. Compression | 2 | -73.97 | 0.06 | 2.68 | | |
| | | Max. Mx | 8 | -65.52 | -2.33 | -0.71 | | |
| | | Max. My | 2 | -73.97 | 0.06 | 2.68 | | |
| | | Max. Vy | 8 | 5.03 | -2.33 | -0.71 | | |
| | | Max. Vx | 2 | -5.71 | 0.06 | 2.68 | | |
| | | Max Tension | 24 | 4.94 | 0.00 | 0.00 | | |
| | Diagonal | Max. Compression | 12 | -5.02 | 0.00 | 0.00 | | |

| | | | | |
|---|----------------|-------------------------------|--------------------|-------------------|
| tnxTower Network Building + Consulting 8601 Six Forks Road, Suite 540 Raleigh, NC 27615 Phone: 919.657.9131 FAX: | Job | Woodbridge North CT | Page | 36 of 52 |
| | Project | NB+C ES Project Number 100765 | Date | 14:34:37 12/14/20 |
| | Client | Verizon | Designed by | nsmith |

| Section No. | Elevation ft | Component Type | Condition | Gov. Load Comb. | Axial K | Major Axis Moment kip-ft | Minor Axis Moment kip-ft | | |
|-------------|------------------|----------------|------------------|-----------------|------------------|--------------------------|--------------------------|-------|-------|
| T4 | 230 - 220 | Horizontal | Max. Mx | 27 | 1.85 | -0.01 | 0.00 | | |
| | | | Max. My | 8 | -3.95 | -0.00 | 0.00 | | |
| | | | Max. Vy | 27 | 0.02 | -0.01 | 0.00 | | |
| | | | Max. Vx | 8 | 0.00 | 0.00 | 0.00 | | |
| | | | Max Tension | 14 | 0.74 | 0.00 | 0.00 | | |
| | | | Max. Compression | 3 | -0.61 | 0.00 | 0.00 | | |
| | | | Max. Mx | 26 | 0.28 | 0.03 | 0.00 | | |
| | | | Max. My | 8 | 0.07 | 0.00 | -0.00 | | |
| | | | Max. Vy | 26 | -0.02 | 0.00 | 0.00 | | |
| | | | Max. Vx | 8 | 0.00 | 0.00 | 0.00 | | |
| | | | Max Tension | 10 | 1.47 | 0.00 | 0.00 | | |
| | | | Max. Compression | 6 | -1.46 | 0.00 | 0.00 | | |
| | | Top Girt | Max. Mx | 26 | 0.02 | 0.04 | 0.00 | | |
| | | | Max. My | 10 | -0.73 | 0.00 | 0.00 | | |
| | | | Max. Vy | 26 | -0.03 | 0.00 | 0.00 | | |
| | | | Max. Vx | 10 | -0.00 | 0.00 | 0.00 | | |
| | | | Max Tension | 14 | 1.03 | 0.00 | 0.00 | | |
| | | | Max. Compression | 3 | -0.92 | 0.00 | 0.00 | | |
| | | Bottom Girt | Max. Mx | 26 | 0.08 | 0.04 | 0.00 | | |
| | | | Max. My | 8 | 0.03 | 0.00 | -0.00 | | |
| | | | Max. Vy | 26 | -0.03 | 0.00 | 0.00 | | |
| | | | Max. Vx | 8 | 0.00 | 0.00 | 0.00 | | |
| | | | Max Tension | 7 | 68.24 | -2.54 | -0.04 | | |
| | | | Max. Compression | 2 | -77.36 | 3.74 | -0.04 | | |
| | | T5 | 220 - 200 | Leg | Max. Mx | 6 | 67.10 | -4.19 | -0.04 |
| | | | | | Max. My | 8 | -5.30 | -0.23 | 6.37 |
| | | | | | Max. Vy | 6 | 0.33 | -4.19 | -0.04 |
| | | | | | Max. Vx | 8 | -0.72 | -0.23 | 6.37 |
| | | | | | Max Tension | 23 | 4.82 | 0.05 | -0.01 |
| | | | | | Max. Compression | 10 | -5.48 | 0.00 | 0.00 |
| Diagonal | Max. Mx | | | 6 | 4.18 | 0.05 | 0.00 | | |
| | Max. My | | | 24 | -4.72 | -0.04 | -0.02 | | |
| | Max. Vy | | | 29 | 0.03 | 0.05 | -0.01 | | |
| | Max. Vx | | | 29 | 0.00 | 0.00 | 0.00 | | |
| | Max Tension | | | 23 | 93.03 | -3.58 | -0.03 | | |
| | Max. Compression | | | 10 | -105.20 | 4.61 | 0.03 | | |
| T6 | 200 - 180 | Leg | Max. Mx | 10 | -105.20 | 4.61 | 0.03 | | |
| | | | Max. My | 8 | -6.30 | -0.23 | 6.37 | | |
| | | | Max. Vy | 10 | -0.24 | 4.61 | 0.03 | | |
| | | | Max. Vx | 8 | 0.49 | -0.07 | 5.19 | | |
| | | | Max Tension | 24 | 4.93 | 0.00 | 0.00 | | |
| | | | Max. Compression | 10 | -5.18 | 0.00 | 0.00 | | |
| | | Diagonal | Max. Mx | 27 | 0.50 | 0.09 | -0.01 | | |
| | | | Max. My | 28 | 0.93 | 0.08 | -0.02 | | |
| | | | Max. Vy | 30 | 0.05 | 0.08 | 0.01 | | |
| | | | Max. Vx | 29 | 0.00 | 0.00 | 0.00 | | |
| | | | Max Tension | 23 | 116.71 | -3.20 | -0.01 | | |
| | | | Max. Compression | 10 | -132.58 | 4.95 | 0.11 | | |
| T6 | 200 - 180 | Leg | Max. Mx | 10 | -132.58 | 4.95 | 0.11 | | |
| | | | Max. My | 8 | -7.50 | -0.10 | 4.31 | | |
| | | | Max. Vy | 6 | -0.79 | -4.28 | 0.01 | | |
| | | | Max. Vx | 8 | 0.67 | -0.10 | 4.31 | | |
| | | | Max Tension | 23 | 6.65 | 0.00 | 0.00 | | |
| | | | Max. Compression | 10 | -7.67 | 0.00 | 0.00 | | |
| | | Diagonal | Max. Mx | 29 | 0.93 | 0.09 | -0.01 | | |
| | | | Max. My | 34 | -1.11 | 0.06 | 0.01 | | |
| | | | Max. Vy | 29 | 0.06 | 0.09 | -0.01 | | |
| | | | Max. Vx | 27 | 0.00 | 0.00 | 0.00 | | |
| | | | Max Tension | 22 | 3.40 | 0.00 | 0.00 | | |
| | | | Max. Compression | 11 | -2.71 | 0.00 | 0.00 | | |
| Top Girt | Max. Mx | 26 | 1.01 | -0.14 | 0.00 | | | | |

| | | | | |
|---|----------------|-------------------------------|--------------------|-------------------|
| tnxTower Network Building + Consulting 8601 Six Forks Road, Suite 540 Raleigh, NC 27615 Phone: 919.657.9131 FAX: | Job | Woodbridge North CT | Page | 37 of 52 |
| | Project | NB+C ES Project Number 100765 | Date | 14:34:37 12/14/20 |
| | Client | Verizon | Designed by | nsmith |

| Section No. | Elevation ft | Component Type | Condition | Gov. Load Comb. | Axial K | Major Axis Moment kip-ft | Minor Axis Moment kip-ft |
|-------------|------------------|----------------|------------------|-----------------|---------|--------------------------|--------------------------|
| T7 | 180 - 160 | Mid Girt | Max. My | 37 | 0.36 | 0.00 | 0.00 |
| | | | Max. Vy | 26 | 0.07 | 0.00 | 0.00 |
| | | | Max. Vx | 37 | 0.00 | 0.00 | 0.00 |
| | | | Max Tension | 22 | 4.16 | 0.00 | 0.00 |
| | | | Max. Compression | 11 | -3.19 | 0.00 | 0.00 |
| | | | Max. Mx | 26 | 1.43 | -0.18 | 0.00 |
| | | Leg | Max. My | 37 | 0.67 | 0.00 | 0.01 |
| | | | Max. Vy | 26 | 0.08 | 0.00 | 0.00 |
| | | | Max. Vx | 37 | -0.00 | 0.00 | 0.00 |
| | | | Max Tension | 23 | 146.36 | -3.34 | 0.02 |
| | | | Max. Compression | 10 | -168.13 | 5.10 | 0.04 |
| | | | Max. Mx | 10 | -168.13 | 5.10 | 0.04 |
| | | Diagonal | Max. My | 8 | -9.91 | -0.12 | 4.36 |
| | | | Max. Vy | 22 | -0.82 | -4.79 | -0.11 |
| | | | Max. Vx | 24 | 1.00 | -0.12 | 4.33 |
| | | | Max Tension | 23 | 8.51 | 0.00 | 0.00 |
| | | | Max. Compression | 10 | -9.87 | 0.00 | 0.00 |
| | | | Max. Mx | 29 | 1.07 | 0.13 | -0.02 |
| | | Top Girt | Max. My | 37 | -2.96 | 0.09 | -0.02 |
| | | | Max. Vy | 29 | 0.08 | 0.13 | -0.02 |
| | | | Max. Vx | 31 | -0.00 | 0.00 | 0.00 |
| | | | Max Tension | 22 | 5.31 | 0.00 | 0.00 |
| | | | Max. Compression | 11 | -4.13 | 0.00 | 0.00 |
| | | | Max. Mx | 26 | 1.81 | -0.30 | 0.00 |
| Mid Girt | Max. My | 37 | 0.85 | 0.00 | 0.01 | | |
| | Max. Vy | 26 | 0.12 | 0.00 | 0.00 | | |
| | Max. Vx | 37 | 0.00 | 0.00 | 0.00 | | |
| | Max Tension | 22 | 5.62 | 0.00 | 0.00 | | |
| | Max. Compression | 11 | -4.32 | 0.00 | 0.00 | | |
| | Max. Mx | 26 | 2.05 | -0.36 | 0.00 | | |
| T8 | 160 - 140 | Leg | Max. My | 37 | 1.07 | 0.00 | 0.01 |
| | | | Max. Vy | 26 | 0.13 | 0.00 | 0.00 |
| | | | Max. Vx | 37 | 0.00 | 0.00 | 0.00 |
| | | | Max Tension | 23 | 182.78 | -3.53 | -0.03 |
| | | | Max. Compression | 10 | -214.15 | 4.14 | 0.02 |
| | | | Max. Mx | 10 | -189.52 | 5.10 | 0.04 |
| | | Diagonal | Max. My | 8 | -14.57 | -0.25 | 6.17 |
| | | | Max. Vy | 6 | -1.23 | -4.56 | 0.03 |
| | | | Max. Vx | 20 | -0.76 | 0.19 | -2.51 |
| | | | Max Tension | 12 | 9.92 | 0.00 | 0.00 |
| | | | Max. Compression | 12 | -9.91 | 0.00 | 0.00 |
| | | | Max. Mx | 27 | 2.91 | 0.20 | 0.02 |
| | | Top Girt | Max. My | 37 | -2.68 | 0.11 | -0.03 |
| | | | Max. Vy | 37 | 0.10 | 0.18 | -0.03 |
| | | | Max. Vx | 37 | 0.01 | 0.00 | 0.00 |
| | | | Max Tension | 22 | 4.37 | 0.00 | 0.00 |
| | | | Max. Compression | 11 | -3.39 | 0.00 | 0.00 |
| | | | Max. Mx | 26 | 1.56 | -0.41 | 0.00 |
| | | Leg | Max. My | 37 | 0.81 | 0.00 | 0.01 |
| | | | Max. Vy | 26 | -0.14 | 0.00 | 0.00 |
| | | | Max. Vx | 37 | -0.00 | 0.00 | 0.00 |
| | | | Max Tension | 23 | 222.74 | -4.11 | 0.00 |
| | | | Max. Compression | 10 | -261.94 | 9.45 | 0.26 |
| | | | Max. Mx | 10 | -261.94 | 9.45 | 0.26 |
| Diagonal | Max. My | 8 | -20.04 | 0.08 | 8.97 | | |
| | Max. Vy | 14 | -1.44 | -4.08 | -0.06 | | |
| | Max. Vx | 8 | 1.64 | -0.07 | 3.97 | | |
| | Max Tension | 13 | 11.41 | 0.00 | 0.00 | | |
| | Max. Compression | 12 | -11.91 | 0.00 | 0.00 | | |
| | Max. Mx | 27 | 3.57 | 0.22 | 0.02 | | |
| T9 | 140 - 120 | | Max. My | 37 | -2.48 | 0.17 | -0.03 |

| | | | | |
|---|----------------|-------------------------------|--------------------|-------------------|
| tnxTower Network Building + Consulting 8601 Six Forks Road, Suite 540 Raleigh, NC 27615 Phone: 919.657.9131 FAX: | Job | Woodbridge North CT | Page | 38 of 52 |
| | Project | NB+C ES Project Number 100765 | Date | 14:34:37 12/14/20 |
| | Client | Verizon | Designed by | nsmith |

| Section No. | Elevation ft | Component Type | Condition | Gov. Load Comb. | Axial K | Major Axis Moment kip-ft | Minor Axis Moment kip-ft |
|-------------|--------------|----------------|------------------|-----------------|---------|--------------------------|--------------------------|
| T10 | 120 - 100 | Leg | Max. Vy | 37 | 0.11 | 0.22 | -0.03 |
| | | | Max. Vx | 37 | 0.01 | 0.00 | 0.00 |
| | | | Max Tension | 23 | 249.21 | -9.07 | -0.26 |
| | | | Max. Compression | 10 | -292.10 | 9.34 | 0.21 |
| | | | Max. Mx | 22 | 243.17 | -11.12 | -0.23 |
| | | | Max. My | 24 | -22.19 | -1.04 | 17.13 |
| | | | Max. Vy | 22 | 0.49 | -11.12 | -0.23 |
| | | Diagonal | Max. Vx | 8 | -0.83 | -1.05 | 17.10 |
| | | | Max Tension | 15 | 15.50 | 0.00 | 0.00 |
| | | | Max. Compression | 2 | -16.95 | 0.00 | 0.00 |
| | | | Max. Mx | 37 | 3.06 | -0.57 | 0.08 |
| | | | Max. My | 37 | -4.59 | -0.40 | 0.11 |
| | | | Max. Vy | 37 | -0.20 | -0.57 | 0.08 |
| | | | Max. Vx | 37 | -0.02 | 0.00 | 0.00 |
| T11 | 100 - 80 | Leg | Max Tension | 23 | 288.84 | -10.83 | -0.23 |
| | | | Max. Compression | 10 | -339.87 | 13.66 | 0.21 |
| | | | Max. Mx | 10 | -339.87 | 13.66 | 0.21 |
| | | | Max. My | 24 | -24.08 | -1.04 | 17.13 |
| | | | Max. Vy | 10 | -0.51 | 13.66 | 0.21 |
| | | | Max. Vx | 8 | 0.87 | -1.05 | 17.10 |
| | | | Max Tension | 12 | 16.15 | 0.00 | 0.00 |
| | | Diagonal | Max. Compression | 12 | -16.78 | 0.00 | 0.00 |
| | | | Max. Mx | 37 | 4.08 | -0.65 | 0.10 |
| | | | Max. My | 37 | 4.08 | -0.65 | 0.10 |
| | | | Max. Vy | 37 | -0.22 | -0.65 | -0.10 |
| | | | Max. Vx | 37 | 0.01 | 0.00 | 0.00 |
| | | | Max Tension | 23 | 324.75 | -12.15 | -0.21 |
| | | | Max. Compression | 10 | -383.56 | 9.78 | 0.18 |
| T12 | 80 - 60 | Leg | Max. Mx | 10 | -381.36 | 13.66 | 0.21 |
| | | | Max. My | 24 | -29.54 | -1.20 | 15.37 |
| | | | Max. Vy | 33 | -0.48 | -5.24 | -0.06 |
| | | | Max. Vx | 8 | -0.77 | -1.20 | 15.36 |
| | | | Max Tension | 12 | 15.86 | 0.00 | 0.00 |
| | | | Max. Compression | 12 | -16.42 | 0.00 | 0.00 |
| | | | Max. Mx | 37 | 2.65 | -0.74 | 0.11 |
| | | Diagonal | Max. My | 31 | -0.86 | -0.60 | -0.11 |
| | | | Max. Vy | 37 | -0.24 | -0.74 | 0.11 |
| | | | Max. Vx | 31 | -0.02 | 0.00 | 0.00 |
| | | | Max Tension | 23 | 358.32 | -11.41 | -0.19 |
| | | | Max. Compression | 10 | -424.45 | 14.20 | 0.16 |
| | | | Max. Mx | 10 | -424.45 | 14.20 | 0.16 |
| | | | Max. My | 24 | -30.70 | -1.20 | 15.37 |
| T13 | 60 - 40 | Leg | Max. Vy | 33 | 0.82 | -12.31 | -0.04 |
| | | | Max. Vx | 8 | 0.84 | -1.20 | 15.36 |
| | | | Max Tension | 13 | 16.17 | 0.00 | 0.00 |
| | | | Max. Compression | 2 | -17.58 | 0.00 | 0.00 |
| | | | Max. Mx | 37 | 4.91 | -0.80 | 0.11 |
| | | | Max. My | 37 | 4.91 | -0.80 | 0.11 |
| | | | Max. Vy | 37 | -0.25 | -0.80 | -0.11 |
| | | Diagonal | Max. Vx | 37 | 0.01 | 0.00 | 0.00 |
| | | | Max Tension | 23 | 392.91 | -12.12 | -0.17 |
| | | | Max. Compression | 2 | -468.65 | 10.01 | 0.10 |
| | | | Max. Mx | 10 | -466.04 | 14.20 | 0.16 |
| | | | Max. My | 24 | -37.63 | -1.76 | 23.38 |
| | | | Max. Vy | 33 | -1.15 | -12.31 | -0.04 |
| | | | Max. Vx | 8 | -1.20 | -1.76 | 23.28 |
| T14 | 40 - 20 | Leg | Max Tension | 2 | 16.73 | 0.00 | 0.00 |
| | | | Max. Compression | 12 | -16.05 | 0.00 | 0.00 |
| | | | Max. Mx | 37 | 0.64 | | |
| | | | Max. My | | | | |
| | | | Max. Vy | | | | |

ERROR: syntaxerror
OFFENDING COMMAND: %ztokenexec_continue

STACK:

-filestream-


Self Support Anchor Rod Capacity

| Analysis Considerations | |
|-------------------------|------|
| TIA-222 Revision | G |
| Grout Considered: | Yes |
| Eta Factor, η | 0.55 |

| Applied Loads | | |
|--------------------|--------|--------|
| | Comp. | Uplift |
| Axial Force (kips) | 526.00 | 437.00 |
| Shear Force (kips) | 55.00 | 47.00 |

| Considered Eccentricity | |
|---------------------------|-------|
| Leg Mod Eccentricity (in) | 0.000 |
| Anchor Rod N.A Shift (in) | 0.000 |
| Total Eccentricity (in) | 0.000 |

*Anchor Rod Eccentricity Applied



| Connection Properties | Analysis Results |
|-----------------------|------------------|
|-----------------------|------------------|

| Anchor Rod Data | |
|--|-----|
| (6) 2" ϕ bolts (A687 N; Fy=105 ksi, Fu=125 ksi) | |
| l_{ar} (in): | 3.5 |

| Anchor Rod Summary | | (units of kips, kip-in) |
|--------------------|----------------------|-------------------------|
| $P_{u,t} = 72.83$ | $\phi P_{n,t} = 250$ | Stress Rating |
| $V_u = 7.83$ | $\phi V_n = n/a$ | 34.8% |
| $M_u = n/a$ | $\phi M_n = n/a$ | Pass |

SST Unit Base Foundation

TIA-222 Revision:

| | |
|----------------------------------|--------------------------|
| Top & Bot. Pad Rein. Different?: | <input type="checkbox"/> |
| Tower Centroid Offset?: | <input type="checkbox"/> |
| Block Foundation?: | <input type="checkbox"/> |

| Superstructure Analysis Reactions | | |
|--|-------|---------|
| Global Moment, M : | 11733 | ft-kips |
| Global Axial, P : | 126 | kips |
| Global Shear, V : | 82 | kips |
| Leg Compression, P_{comp} : | 526 | kips |
| Leg Comp. Shear, V_{u,comp} : | 55 | kips |
| Leg Uplift, P_{uplift} : | 437 | kips |
| Leg Uplift. Shear, V_{u,uplift} : | 47 | kips |
| Tower Height, H : | 280 | ft |
| Base Face Width, BW : | 28 | ft |
| BP Dist. Above Fdn, bp_{dist} : | | in |

| Foundation Analysis Checks | | | | |
|--|----------|----------|--------|-------|
| | Capacity | Demand | Rating | Check |
| <i>Lateral (Sliding) (kips)</i> | 534.06 | 82.00 | 15.4% | Pass |
| <i>Bearing Pressure (ksf)</i> | 7.50 | 2.05 | 27.3% | Pass |
| <i>Overturning (kip*ft)</i> | 21227.83 | 12266.00 | 57.8% | Pass |
| <i>Pier Flexure (Comp.) (kip*ft)</i> | 3284.13 | 178.75 | 5.4% | Pass |
| <i>Pier Flexure (Tension) (kip*ft)</i> | 1790.24 | 152.75 | 8.5% | Pass |
| <i>Pier Compression (kip)</i> | 9815.13 | 540.63 | 5.5% | Pass |
| <i>Pad Flexure (kip*ft)</i> | 13519.41 | 1909.22 | 14.1% | Pass |
| <i>Pad Shear - 1-way (kips)</i> | 1485.15 | 296.40 | 20.0% | Pass |
| <i>Pad Shear - Comp 2-way (ksi)</i> | 0.190 | 0.055 | 28.8% | Pass |

| Pier Properties | | |
|--|--------|----|
| Pier Shape: | Square | |
| Pier Diameter, dpier : | 5.0 | ft |
| Ext. Above Grade, E : | 0.50 | ft |
| Pier Rebar Size, Sc : | 9 | |
| Pier Rebar Quantity, mc : | 23 | |
| Pier Tie/Spiral Size, St : | 4 | |
| Pier Tie/Spiral Quantity, mt : | | |
| Pier Reinforcement Type: | Tie | |
| Pier Clear Cover, cc_{pier} : | 3 | in |

| | |
|--------------------|-------|
| Soil Rating: | 57.8% |
| Structural Rating: | 28.8% |

| Pad Properties | | |
|--|-------|----|
| Depth, D : | 6.00 | ft |
| Pad Width, W : | 38.50 | ft |
| Pad Thickness, T : | 3.25 | ft |
| Pad Rebar Size (Bottom), Sp : | 11 | |
| Pad Rebar Quantity (Bottom), mp : | 60 | |
| Pad Clear Cover, cc_{pad} : | 3 | in |

| Material Properties | | |
|---|-----|-----|
| Rebar Grade, Fy : | 60 | ksi |
| Concrete Compressive Strength, F'c : | 4 | ksi |
| Dry Concrete Density, δc : | 150 | pcf |

| Soil Properties | | |
|--|--------|---------|
| Total Soil Unit Weight, γ : | 120 | pcf |
| Ultimate Gross Bearing, Qult : | 10.000 | ksf |
| Cohesion, Cu : | 0.000 | ksf |
| Friction Angle, φ : | 30 | degrees |
| SPT Blow Count, N_{blows} : | | |
| Base Friction, μ : | 0.45 | |
| Neglected Depth, N : | 3.3 | ft |
| Foundation Bearing on Rock? | No | |
| Groundwater Depth, gw : | None | ft |

<-- Toggle between Gross and Net



Maser Consulting Connecticut
 2000 Midlantic Drive Suite 100
 Mt. Laurel, NJ 08054
 (215)962-5934
 peter.albano@colliersengineering.com

New/Replacement Antenna Mount Analysis Report and PMI Requirements

Mount Analysis-R

SMART Tool Project #: 10143537
 Maser Consulting Connecticut Project #: 20777396A

April 12, 2022

Site Information

Site ID: 469060-VZW / Woodbridge North CT
 Site Name: Woodbridge North CT
 Carrier Name: Verizon Wireless
 Address: 6 Progress Ave
 Seymour, Connecticut 06483
 New Haven County
 Latitude: 41.391528°
 Longitude: -73.053333°

Structure Information

Tower Type: 250-Ft Self Support
 Mount Type: 12.50-Ft Sector Frame

FUZE ID # 16244103

Analysis Results


Sector Frame: **47.3% Pass w/ Mount Replacement***
 (3 VFA12-HD)

***Antennas and equipment to be installed in compliance with PMI Requirements of this mount analysis.**

***Contractor PMI Requirements:

Included at the end of this MA report
 Available & Submitted via portal at <https://pmi.vzwsmart.com>
 For additional questions and support, please reach out to:
pmisupport@colliersengineering.com

Report Prepared By: Garrett Smith



Executive Summary:

The objective of this report is to determine the capacity of the proposed antenna support mount at the subject facility for the final wireless telecommunications configuration, per the applicable codes and standards. The proposed mount was assumed to be installed properly to the existing tower per the manufacturer’s instructions. Maser Consulting Connecticut cannot verify that the proposed mount will fit properly and is not liable for any fit-up issues during installation.

This analysis is inclusive of the mount structure only and does not address the structural capacity of the supporting structure. This mounting frame was not analyzed as an anchor attachment point for fall protection. All climbing activities are required to have a fall protection plan completed by a competent person.

Sources of Information:

| Document Type | Remarks |
|--|---|
| <i>Radio Frequency Data Sheet (RFDS)</i> | <i>Verizon RFDS Site ID: 1126653, dated November 17, 2020</i> |
| <i>Mount Specification</i> | <i>Site Pro 1, P/N: VFA12-HD</i> |
| <i>Mount Specification</i> | <i>Site Pro 1, P/N: BCAM-HDLL</i> |
| <i>Previous Mount Analysis Report</i> | <i>Maser Consulting Connecticut, Project #: 20777396A, dated December 3, 2020</i> |

Analysis Criteria:

| | |
|-------------------------|--|
| Codes and Standards: | ANSI/TIA-222-H |
| Wind Parameters: | Basic Wind Speed (Ultimate 3-sec. Gust), V_{ULT} : 118 mph |
| | Ice Wind Speed (3-sec. Gust): 50 mph |
| | Design Ice Thickness: 1.00 in |
| | Risk Category: II |
| | Exposure Category: B |
| | Topographic Category: 1 |
| | Topographic Feature Considered: N/A |
| | Topographic Method: N/A |
| | Ground Elevation Factor, K_e : 0.983 |
| Seismic Parameters: | S_s : 0.20 g |
| | S_1 : 0.05 g |
| Maintenance Parameters: | Wind Speed (3-sec. Gust): 30 mph |
| | Maintenance Live Load, L_v : 250 lbs. |
| | Maintenance Live Load, L_m : 500 lbs. |
| Analysis Software: | RISA-3D (V17) |

Final Loading Configuration:

The following equipment has been considered for the analysis of the mounts:

| Mount Elevation (ft) | Equipment Elevation (ft) | Quantity | Manufacturer | Model | Status |
|----------------------|--------------------------|----------|--------------|-------------------|----------|
| 140.00 | 140.00 | 6 | JMA Wireless | MX06FRO660-03 | Added |
| | | 3 | Samsung | nL-Sub 6 Antenna | |
| | | 3 | Samsung | B2/B66A RRH-BR049 | |
| | | 3 | Samsung | B5/B13 RRH-BR04C | |
| | | 6 | Antel | LPA-80063/6CF | Retained |
| | | 1 | Raycap | RHSDC-3315-PF-48* | |

* Equipment is flush mounted directly to the Self Support. It is not mounted on the sector frame mounts and is not included in this mount analysis.

Any proposed antennas not currently installed should be mounted such that the centerline of the antennas does not exceed 6 inches vertically from the center of the antenna mounts.

It is acceptable to install up to any three (3) of the OVP model numbers listed below as required at any location other than the mount face without affecting the structural capacity of the mount. If OVP units are installed on the mount face, a mount re-analysis may be required.

| Model Number | Ports | AKA |
|------------------|-------|--------|
| DB-B1-6C-12AB-0Z | 6 | OVP-6 |
| RVZDC-6627-PF-48 | 12 | OVP-12 |

Standard Conditions:

1. All engineering services are performed on the basis that the information provided to Maser Consulting Connecticut and used in this analysis is current and correct. The existing equipment loading has been applied at locations determined from the supplied documentation. Any deviation from the loading locations specified in this report shall be communicated to Maser Consulting Connecticut to verify deviation will not adversely impact the analysis.
2. Mounts are assumed to have been properly fabricated, installed and maintained in good condition, twist free and plumb in accordance with its original design and manufacturer’s specifications.
3. For mount analyses completed from other data sources (including new replacement mounts) and not specifically mapped in accordance with the NSTD-446 Standard, the mounts are assumed to have been properly fabricated, installed and maintained in good condition, twist free and plumb in accordance with its original design and manufacturer’s specifications.
4. All member connections are assumed to have been designed to meet or exceed the load carrying capacity of the connected member unless otherwise specified in this report.
5. The mount was checked up to, and including, the bolts that fasten it to the mount collar/attachment and threaded rod connections in collar members if applicable. Local deformation and interaction between the mount collar/attachment and the supporting tower structure are outside the scope of this analysis.
6. All services are performed, results obtained, and recommendations made in accordance with generally accepted engineering principles and practices. Maser Consulting Connecticut is not responsible for the conclusion, opinions, and recommendations made by others based on the information supplied.

7. Structural Steel Grades have been assumed as follows, if applicable, unless otherwise noted in this analysis:
- Channel, Solid Round, Angle, Plate ASTM A36 (Gr. 36)
 - HSS (Rectangular) ASTM 500 (Gr. B-46)
 - Pipe ASTM A53 (Gr. B-35)
 - Threaded Rod F1554 (Gr. 36)
 - Bolts ASTM A325

Discrepancies between in-field conditions and the assumptions listed above may render this analysis invalid unless explicitly approved by Maser Consulting Connecticut.

Analysis Results:

| Component | Utilization % | Pass/Fail |
|----------------------------|---------------|-------------|
| <i>Tieback</i> | 38.6% | <i>Pass</i> |
| <i>Standoff Vertical</i> | 6.1% | <i>Pass</i> |
| <i>Antenna Pipe</i> | 40.3% | <i>Pass</i> |
| <i>Standoff Diagonal</i> | 8.6% | <i>Pass</i> |
| <i>Standoff Plate</i> | 47.3% | <i>Pass</i> |
| <i>Standoff Horizontal</i> | 19.1% | <i>Pass</i> |
| <i>Face Horizontal</i> | 26.7% | <i>Pass</i> |
| <i>Connection Check</i> | 16.0% | <i>Pass</i> |

| | |
|---|--------------|
| Structure Rating – (Controlling Utilization of all Components) | 47.3% |
|---|--------------|

Mount Steel (EPA)a per ANSI/TIA-222-H Section 2.6.11.2:

| Ice Thickness (In) | Mount Pipes Excluded | | Mount Pipes Included | |
|--------------------|------------------------|-----------------------|------------------------|-----------------------|
| | Front (EPA)a (Sq. Ft.) | Side (EPA)a (Sq. Ft.) | Front (EPA)a (Sq. Ft.) | Side (EPA)a (Sq. Ft.) |
| 0 | 14.5 | 12.4 | 23.6 | 21.5 |
| 0.5 | 22.8 | 20.3 | 35.8 | 33.3 |
| 1 | 30.5 | 27.7 | 47.3 | 44.5 |

Notes:

- (EPA)a values listed above may be used in the absence of more precise information
- (EPA)a values in the table above include 1 sector(s).
- Ka factors included in (EPA)a calculations

Requirements:

The proposed antenna mounts are **SUFFICIENT** for the final loading configuration (attachment 2) upon completion of the mount replacement (attachment 3) and requirements below.

Contractor shall remove existing mounts and all associated hardware. Contractor shall wire brush clean all damaged mount members and protect with two (2) coats of cold galvanization (zinga or zinc kote).

Contractor shall install new mount such that mount centerline matches desired antenna centerline.

Contractor shall install the proposed mount such that mount azimuth matches the desired equipment azimuths listed in the referenced RFDS.

Contractor to attach mount to tower leg using tower leg adapter (Site Pro 1 Part #: BCAM-HDLL)

Install (4) mount pipes (Part #: VZWSMART-P40-238X096) in each sector. Space at 48" (C-C) and 3" from edge of the mount. Ensure the mount pipes extend 68" above the bottom face horizontal. Contractor shall attach mount pipes to face horizontals using crossover plates (VZWSMART – MSK1).

Contractor shall replace tiebacks in proposed mount with (12) new 96" P2X-STR pipes. Contractor to connect (2) pipes using a 36" long P3 STD sleeve pipe. Pipe to be bolted with a min. of (2) 5/8" dia. A325N bolts at each end. Install tiebacks on top face horizontal members, 39" from each end of the face horizontals on all sectors. Connect other end of tiebacks to adjacent tower legs. tieback shall extend no more than 12" beyond the tower leg. Contractor shall trim as required and protect cut end with two (2) coats of cold galvanization (Zinga or Zinc Kote).

ANSI/ASSP rigging plan review services compliant with the requirements of ANSI/TIA 322 are available for a Construction Class IV site or other, if required. Separate review fees will apply.

Attachments:

1. **Contractor Required Post Installation Inspection (PMI) Report Deliverables**
2. Antenna Placement Diagrams
3. Mount Manufacturer Drawings
4. Existing Mount Photos
5. Analysis Calculations

Mount Desktop – Post Modification Inspection (PMI) Report Requirements

Documents & Photos Required from Contractor – **New Mount Passing MA**

Electronic pdf version of this can be downloaded at <https://pmi.vzwsmart.com>

For additional questions and support, please reach out to pmisupport@colliersengineering.com

PSLC #: 469060

SMART Project #: 10143537

Fuze Project ID: 16244103

Purpose – to provide SMART Tool structural vendor the proper documentation in order to complete the required Mount Desktop review of the Post Modification Inspection Report.

- Contractor is responsible for making certain the photos provided as noted below provide confirmation that the installation was completed in accordance with this Passing Mount Analysis.
- Contractor shall relay any data that can impact the performance of the mount, this includes safety issues.

Base Requirements:

- If installation will cause damage to the structure, the climbing facility, or safety climb if present or any installed system, SMART Tool vendor to be notified prior to install. Any special photos outside of the standard requirements will be indicated on the drawings.
- Provide “as built mount drawings” showing contractor’s name, contact information, preparer’s signature, and date. Any deviations from the drawings (Proposed modification) shall be shown. NOTE: If loading is different than what is conveyed in the passing mount analysis (MA) contact the SMART Tool vendor immediately.
- Each photo should be time and date stamped.
- Photos should be high resolution.
- Contractor shall ensure that the safety climb wire rope is supported and not adversely impacted by the install of the modification components. This may involve the install of wire rope guides, or other items to protect the wire rope. If there is conflict, contact the SMART Tool engineer for recommendations.
- The PMI can be accessed at the following portal: <https://pmi.vzwsmart.com>

Photo Requirements:

- Photos taken at ground level
 - Photo of Gate Signs showing the tower owner, site name, and number.
 - Overall tower structure after installation.
 - Photos of the mount after installation; if the mounts are at different rad elevations, pictures must be provided for all elevations that equipment was installed.
- Photos taken at Mount Elevation
 - Photos showing the safety climb wire rope above and below the mount prior to installation.
 - Photos showing the climbing facility and safety climb if present.
 - Photos showing each individual sector after installation of mounts. Each entire sector shall be in one photo to show the interconnection of members.

- These photos shall also certify that the placement and geometry of the equipment on the mount is as depicted in the antenna placement diagram in this form.
- Photos that show the model number of each antenna and piece of equipment installed per sector.
- Photos of each installed mount; pictures shall also include connection hardware (U-bolts, bolts, nuts, all-threaded rods, etc.)
- Photos showing the installed mount elevation.

Antenna & Equipment Placement and Geometry Confirmation:

- The contractor shall certify that the antenna & equipment placement and geometry is in accordance with the sketch and table as included in the mount analysis and noted below.
 - The contractor certifies that the photos support and the equipment on the mount is as depicted on the sketch and table included in this form and with the mount analysis provided.

OR

- The contractor notes that the equipment on the mount is not in accordance with the sketch and has noted the differences below and provided photo documentation of any alterations.

Special Instructions / Validation as required from the MA or any other information the contractor deems necessary to share that was identified:

Issue:

Contractor shall remove existing mounts and all associated hardware. Contractor shall wire brush clean all damaged mount members and protect with two (2) coats of cold galvanization (zinga or zinc kote).

Contractor shall install new mount such that mount centerline matches desired antenna centerline.

Contractor shall install the proposed mount such that mount azimuth matches the desired equipment azimuths listed in the referenced RFDS.

Contractor to attach mount to tower leg using tower leg adapter (Site Pro 1 Part #: BCAM-HDLL)

Install (4) mount pipes (Part #: VZWSMART-P40-238X096) in each sector. Space at 48" (C-C) and 3" from edge of the mount. Ensure the mount pipes extend 68" above the bottom face horizontal. Contractor shall attach mount pipes to face horizontals using crossover plates (VZWSMART – MSK1).

Contractor shall replace tiebacks in proposed mount with (12) new 96" P2X-STR pipes. Contractor to connect (2) pipes using a 36" long P3 STD sleeve pipe. Pipe to be bolted with a min. of (2) 5/8" dia. A325N bolts at each end. Install tiebacks on top face horizontal members, 39" from each end of the face horizontals on all sectors. Connect other end of tiebacks to adjacent tower legs. tieback shall extend no more than 12" beyond the tower leg. Contractor shall trim as required and protect cut end with two (2) coats of cold galvanization (Zinga or Zinc Kote).

Response:

| |
|--|
| |
|--|

Special Instruction Confirmation:

The contractor has read and acknowledges the above special instructions.

Contractor certifies that the climbing facility / safety climb was not damaged prior to starting work:

Yes No

Contractor certifies no new damage created during the current installation:

Yes No

Contractor to certify the condition of the safety climb and verify no damage when leaving the site:

Safety Climb in Good Condition Safety Climb Damaged

Comments:

| |
|--|
| |
|--|

New Mount Certification:


- The contractor certifies that the New Mount installed is as specified in the Passing Mount Analysis.
- The contractor notes that the New Mount installed is not as specified and engineering approval was received for the New Mount installed.

Certifying Individual:


| | |
|----------------|--|
| Company: | |
| Employee Name: | |
| Contact Phone: | |
| Email: | |
| Date: | |



Plan View



Front View - Looking at Structure



| Ref# | Model | Height (in) | Width (in) | H Dist Frm L. | Pipe # | Pipe Pos V | Ant Pos | C. Ant Frm T. | Ant H Off | Status | Validation |
|------|-------------------|-------------|------------|---------------|--------|------------|---------|---------------|-----------|----------|------------|
| A11 | LPA-80063/6CF | 70.9 | 15 | 147 | 1 | a | Front | 48 | 0 | Retained | 11/13/2020 |
| R10 | B5/B13 RRH-BR04C | 15 | 15 | 147 | 1 | a | Behind | 36 | 0 | Added | |
| A1 | MX06FRO660-03 | 71.3 | 15.4 | 99 | 2 | a | Front | 48 | 9 | Added | |
| A1 | MX06FRO660-03 | 71.3 | 15.4 | 99 | 2 | b | Front | 48 | -9 | Added | |
| R9 | B2/B66A RRH-BR049 | 15 | 15 | 99 | 2 | a | Behind | 36 | 0 | Added | |
| A8 | nL-Sub 6 Antenna | 35.1 | 16.1 | 51 | 3 | a | Front | 48 | 0 | Added | |
| A11 | LPA-80063/6CF | 70.9 | 15 | 3 | 4 | a | Front | 48 | 0 | Retained | 11/13/2020 |

Sector: **B**
 Structure Type: Self Support
 Mount Elev: 140.00


10143537

4/11/2022


Page: 2



Plan View




Front View - Looking at Structure




| Ref# | Model | Height (in) | Width (in) | H Dist Frm L. | Pipe # | Pipe Pos V | Ant Pos | C. Ant Frm T. | Ant H Off | Status | Validation |
|------|-------------------|-------------|------------|---------------|--------|------------|---------|---------------|-----------|----------|------------|
| A11 | LPA-80063/6CF | 70.9 | 15 | 147 | 1 | a | Front | 48 | 0 | Retained | 11/13/2020 |
| R10 | B5/B13 RRH-BR04C | 15 | 15 | 147 | 1 | a | Behind | 36 | 0 | Added | |
| A1 | MX06FRO660-03 | 71.3 | 15.4 | 99 | 2 | a | Front | 48 | -9 | Added | |
| A1 | MX06FRO660-03 | 71.3 | 15.4 | 99 | 2 | b | Front | 48 | 9 | Added | |
| R9 | B2/B66A RRH-BR049 | 15 | 15 | 99 | 2 | a | Behind | 36 | 0 | Added | |
| A8 | nL-Sub 6 Antenna | 35.1 | 16.1 | 51 | 3 | a | Front | 48 | 0 | Added | |
| A11 | LPA-80063/6CF | 70.9 | 15 | 3 | 4 | a | Front | 48 | 0 | Retained | 11/13/2020 |




Plan View



Front View - Looking at Structure



| Ref# | Model | Height (in) | Width (in) | H Dist Frm L. | Pipe # | Pipe Pos V | Ant Pos | C. Ant Frm T. | Ant H Off | Status | Validation |
|------|-------------------|-------------|------------|---------------|--------|------------|---------|---------------|-----------|----------|------------|
| A11 | LPA-80063/6CF | 70.9 | 15 | 147 | 1 | a | Front | 48 | 0 | Retained | 11/13/2020 |
| R10 | B5/B13 RRH-BR04C | 15 | 15 | 147 | 1 | a | Behind | 36 | 0 | Added | |
| A1 | MX06FRO660-03 | 71.3 | 15.4 | 99 | 2 | a | Front | 48 | 9 | Added | |
| A1 | MX06FRO660-03 | 71.3 | 15.4 | 99 | 2 | b | Front | 48 | -9 | Added | |
| R9 | B2/B66A RRH-BR049 | 15 | 15 | 99 | 2 | a | Behind | 36 | 0 | Added | |
| A8 | nL-Sub 6 Antenna | 35.1 | 16.1 | 51 | 3 | a | Front | 48 | 0 | Added | |
| A11 | LPA-80063/6CF | 70.9 | 15 | 3 | 4 | a | Front | 48 | 0 | Retained | 11/13/2020 |



| ITEM | QTY | PART NO. | PART DESCRIPTION | LENGTH | UNIT WT. | NET WT. |
|------|-----|------------|--|------------|-------------|---------|
| 1 | 2 | X-VFAW | SUPPORT ARM | | 71.41 | 142.81 |
| 2 | 1 | X-HDCAMTBW | CLAMP WELDMENT FOR BCAM-HD | | 33.86 | 33.86 |
| 3 | 1 | X-MHTPHD | MULTI-HOLE TAPER PLATE WELDMENT | | 36.24 | 36.24 |
| 4 | 2 | X-VFAPL4 | VFA-HD PIVOT PLATE | 12 in | 15.88 | 31.77 |
| 5 | 2 | X-LCBP4 | BENT BACKING PLATE | 13 in | 19.00 | 38.01 |
| 6 | 1 | X-HDCAMSS | ANGLE ADJUSTMENT WELDMENT FOR BCAM-HD | | 16.39 | 16.39 |
| 7 | 4 | X-SPTB | SLIDING PIPE TIE BACK PLATE | 5 1/2 in | 5.87 | 23.49 |
| 8 | 1 | X-HDCAMSP | POSITIONING PLATE WELDMENT FOR BCAM-HD | | 2.58 | 2.58 |
| 9 | 4 | X-TBCA | TIE BACK CLIP ANGLE | | 2.01 | 8.02 |
| 10 | 8 | SCX2 | CROSSOVER PLATE | 7 in | 4.80 | 38.37 |
| 11 | 4 | MCP | CLAMP HALF 1/2" THICK, 11-5/8" LONG | 12 1/16 in | 14.37 | 57.48 |
| 12 | 8 | DCP | 1/2" THICK, 5-3/4" CENTER TO CENTER CLAMP HALF | 8 1/8 in | 2.36 | 18.90 |
| 13 | 2 | P2126 | 2-3/8" X 126" (2" SCH. 40) GALVANIZED PIPE | 126 in | 40.75 | 81.50 |
| 14 | 2 | P30150 | 2-7/8" X 150" (2-1/2" SCH. 40) GALVANIZED PIPE | 150 in | 76.94 | 153.87 |
| 15 | 4 | A34212 | 3/4" x 2-1/2" UNC HEX BOLT (A325) | 2 1/2 in | 0.48 | 1.92 |
| 16 | 4 | G34FW | 3/4" HDG USS FLATWASHER | | 0.06 | 0.24 |
| 17 | 4 | G34LW | 3/4" HDG LOCKWASHER | | 0.04 | 0.17 |
| 18 | 4 | G34NUT | 3/4" HDG HEAVY 2H HEX NUT | | 0.21 | 0.85 |
| 19 | 8 | G58R-18 | 5/8" x 18" THREADED ROD (HDG.) | 18 in | 0.40 | 3.19 |
| 20 | 4 | G58R-12 | 5/8" x 12" THREADED ROD (HDG.) | | 1.05 | 4.18 |
| 21 | 4 | G58R-8 | 5/8" x 8" THREADED ROD (HDG.) | | 0.70 | 2.79 |
| 22 | 4 | X-UB5300 | 5/8" X 3" X 5-1/4" X 2-1/2" U-BOLT (HDG.) | | 1.15 | 4.60 |
| 23 | 8 | X-UB5258 | 5/8" X 2-5/8" X 4-1/2" X 2" U-BOLT (HDG.) | | 1.00 | 8.00 |
| 24 | 2 | G5807 | 5/8" x 7" HDG HEX BOLT GR5 FULL THREAD | 7 in | 0.70 | 1.41 |
| 25 | 1 | G5806 | 5/8" x 6" HDG HEX BOLT GR5 FULL THREAD | 6 in | 0.62 | 0.62 |
| 26 | 8 | G5804 | 5/8" x 4" HDG HEX BOLT GR5 | | 0.44 | 3.55 |
| 27 | 4 | G5802 | 5/8" x 2" HDG HEX BOLT GR5 | | 0.27 | 1.08 |
| 28 | 8 | A582114 | 5/8" x 2-1/4" HDG A325 HEX BOLT | 2 1/4 in | 0.31 | 2.50 |
| 29 | 25 | G58FW | 5/8" HDG USS FLATWASHER | 1/8 in | 0.07 | 1.76 |
| 30 | 66 | G58LW | 5/8" HDG LOCKWASHER | | 0.03 | 1.72 |
| 31 | 71 | G58NUT | 5/8" HDG HEAVY 2H HEX NUT | | 0.13 | 9.22 |
| 32 | 32 | X-UB1300 | 1/2" X 3" X 5" X 2" GALV U-BOLT | | 0.74 | 23.64 |
| 33 | 16 | X-UB1212 | 1/2" X 2" X 3" X 1-1/4" U-BOLT (HDG.) | | 0.60 | 9.56 |
| 34 | 64 | G12FW | 1/2" HDG USS FLATWASHER | 3/32 in | 0.03 | 2.18 |
| 35 | 64 | G12LW | 1/2" HDG LOCKWASHER | 1/8 in | 0.01 | 0.89 |
| 36 | 64 | G12NUT | 1/2" HDG HEAVY 2H HEX NUT | | 0.07 | 4.58 |
| | | | | | TOTAL WT. # | 738.06 |

PARTS LIST

SURE PRO
A Valmont COMPANY

Locations:
New York, NY
Atlanta, GA
Los Angeles, CA
Plymouth, IN
Houston, TX
Dallas, TX

Engineering
Support Team:
1-888-753-7446

Part No. **VFA12-HD**
Dwg. No. **VFA12-HD**

DESCRIPTION
12' 6" HEAVY DUTY V-FRAME ASSEMBLY WITH TWO STIFF ARMS

DRAWN BY: **CEK** 1/25/2017
ENG. APPROVAL

CHECKED BY: **BMC** 12/13/2017

DRAWING USAGE: **CUSTOMER**



CPD NO. **81** SUB **02**

TOLERANCE NOTES
TOLERANCES ON DIMENSIONS, UNLESS OTHERWISE NOTED ARE:
SAWED, SHEARED AND GAS CUT EDGES ($\pm 0.030"$)
DRILLED AND GAS CUT HOLES ($\pm 0.030"$) - NO CONING OF HOLES
LASER CUT EDGES AND HOLES ($\pm 0.010"$) - NO CONING OF HOLES
BENDS ARE $\pm 1/2$ DEGREE
ALL OTHER MACHINING ($\pm 0.030"$)
ALL OTHER ASSEMBLY ($\pm 0.060"$)

PROPRIETARY NOTE: DIMENSIONS CONTAINED IN THIS DRAWING ARE PROPRIETARY INFORMATION OF VALMONT INDUSTRIES AND CONSIDERED A TRADE SECRET. ANY USE OR DISCLOSURE WITHOUT THE CONSENT OF VALMONT INDUSTRIES IS STRICTLY PROHIBITED.


| REV | DESCRIPTION OF REVISIONS | CPD | BY | DATE |
|------------------|--|-----|-----|-----------|
| D | UPDATED BCAM VERSION 1 TO BCAM VERSION 2 | | CEK | 6/29/2018 |
| C | UPDATED PIN LEG CONNECTION TO B-CAM CONNECTION | | CEK | 12/7/2017 |
| B | CHANGED TIE-BACK BACK CONNECTION | | CEK | 7/31/2017 |
| A | CHANGED TIE-BACK FRONT CONNECTION | | CEK | 2/2/2017 |
| REVISION HISTORY | | | | |






| |
|--|
| |
| |
| |

| |
|---------------------------|
| SK - 1 |
| Apr 12, 2022 at 10:37 AM |
| 469060-VZW_MT_LOT_A_H.r3d |






| Code Check (Env) | |
|--------------------|---------|
| Black | No Calc |
| Red | > 1.0 |
| Pink | .90-1.0 |
| Green | .75-.90 |
| Cyan | .50-.75 |
| Blue | 0-.50 |



Member Code Checks Displayed (Enveloped)
Results for LC 1, 1.2D+1.0Wo (0 Deg)

| | | |
|--|--|---------------------------|
| | | SK - 2 |
| | | Apr 12, 2022 at 10:37 AM |
| | | 469060-VZW_MT_LOT_A_H.r3d |



Member Shear Checks Displayed (Enveloped)
Results for LC 1, 1.2D+1.0Wo (0 Deg)

| | | |
|--|--|---------------------------|
| | | SK - 3 |
| | | Apr 12, 2022 at 10:37 AM |
| | | 469060-VZW_MT_LOT_A_H.r3d |

Basic Load Cases

| BLC Description | Category | X Gravity | Y Gravity | Z Gravity | Joint | Point | Distributed Area(Me... | Surface(P... |
|---------------------------|----------|-----------|-----------|-----------|-------|-------|------------------------|--------------|
| 1 Antenna D | None | | | | | 36 | | |
| 2 Antenna Di | None | | | | | 36 | | |
| 3 Antenna Wo (0 Deg) | None | | | | | 36 | | |
| 4 Antenna Wo (30 Deg) | None | | | | | 36 | | |
| 5 Antenna Wo (60 Deg) | None | | | | | 36 | | |
| 6 Antenna Wo (90 Deg) | None | | | | | 36 | | |
| 7 Antenna Wo (120 Deg) | None | | | | | 36 | | |
| 8 Antenna Wo (150 Deg) | None | | | | | 36 | | |
| 9 Antenna Wo (180 Deg) | None | | | | | 36 | | |
| 10 Antenna Wo (210 Deg) | None | | | | | 36 | | |
| 11 Antenna Wo (240 Deg) | None | | | | | 36 | | |
| 12 Antenna Wo (270 Deg) | None | | | | | 36 | | |
| 13 Antenna Wo (300 Deg) | None | | | | | 36 | | |
| 14 Antenna Wo (330 Deg) | None | | | | | 36 | | |
| 15 Antenna Wi (0 Deg) | None | | | | | 36 | | |
| 16 Antenna Wi (30 Deg) | None | | | | | 36 | | |
| 17 Antenna Wi (60 Deg) | None | | | | | 36 | | |
| 18 Antenna Wi (90 Deg) | None | | | | | 36 | | |
| 19 Antenna Wi (120 Deg) | None | | | | | 36 | | |
| 20 Antenna Wi (150 Deg) | None | | | | | 36 | | |
| 21 Antenna Wi (180 Deg) | None | | | | | 36 | | |
| 22 Antenna Wi (210 Deg) | None | | | | | 36 | | |
| 23 Antenna Wi (240 Deg) | None | | | | | 36 | | |
| 24 Antenna Wi (270 Deg) | None | | | | | 36 | | |
| 25 Antenna Wi (300 Deg) | None | | | | | 36 | | |
| 26 Antenna Wi (330 Deg) | None | | | | | 36 | | |
| 27 Antenna Wm (0 Deg) | None | | | | | 36 | | |
| 28 Antenna Wm (30 Deg) | None | | | | | 36 | | |
| 29 Antenna Wm (60 Deg) | None | | | | | 36 | | |
| 30 Antenna Wm (90 Deg) | None | | | | | 36 | | |
| 31 Antenna Wm (120 Deg) | None | | | | | 36 | | |
| 32 Antenna Wm (150 Deg) | None | | | | | 36 | | |
| 33 Antenna Wm (180 Deg) | None | | | | | 36 | | |
| 34 Antenna Wm (210 Deg) | None | | | | | 36 | | |
| 35 Antenna Wm (240 Deg) | None | | | | | 36 | | |
| 36 Antenna Wm (270 Deg) | None | | | | | 36 | | |
| 37 Antenna Wm (300 Deg) | None | | | | | 36 | | |
| 38 Antenna Wm (330 Deg) | None | | | | | 36 | | |
| 39 Structure D | None | | -1 | | | | | |
| 40 Structure Di | None | | | | | | 28 | |
| 41 Structure Wo (0 Deg) | None | | | | | | 56 | |
| 42 Structure Wo (30 Deg) | None | | | | | | 56 | |
| 43 Structure Wo (60 Deg) | None | | | | | | 56 | |
| 44 Structure Wo (90 Deg) | None | | | | | | 56 | |
| 45 Structure Wo (120 D... | None | | | | | | 56 | |
| 46 Structure Wo (150 D... | None | | | | | | 56 | |
| 47 Structure Wo (180 D... | None | | | | | | 56 | |
| 48 Structure Wo (210 D... | None | | | | | | 56 | |
| 49 Structure Wo (240 D... | None | | | | | | 56 | |
| 50 Structure Wo (270 D... | None | | | | | | 56 | |
| 51 Structure Wo (300 D... | None | | | | | | 56 | |
| 52 Structure Wo (330 D... | None | | | | | | 56 | |
| 53 Structure Wi (0 Deg) | None | | | | | | 56 | |
| 54 Structure Wi (30 Deg) | None | | | | | | 56 | |
| 55 Structure Wi (60 Deg) | None | | | | | | 56 | |
| 56 Structure Wi (90 Deg) | None | | | | | | 56 | |



Company :
 Designer :
 Job Number :
 Model Name :

Apr 12, 2022
 10:37 AM
 Checked By: _____

Basic Load Cases (Continued)

| BLC Description | Category | X Gravity | Y Gravity | Z Gravity | Joint | Point | Distributed Area(Me... | Surface(P... |
|---------------------------|----------|-----------|-----------|-----------|-------|-------|------------------------|--------------|
| 57 Structure Wi (120 De.. | None | | | | | | 56 | |
| 58 Structure Wi (150 De.. | None | | | | | | 56 | |
| 59 Structure Wi (180 De.. | None | | | | | | 56 | |
| 60 Structure Wi (210 De.. | None | | | | | | 56 | |
| 61 Structure Wi (240 De.. | None | | | | | | 56 | |
| 62 Structure Wi (270 De.. | None | | | | | | 56 | |
| 63 Structure Wi (300 De.. | None | | | | | | 56 | |
| 64 Structure Wi (330 De.. | None | | | | | | 56 | |
| 65 Structure Wm (0 Deg) | None | | | | | | 56 | |
| 66 Structure Wm (30 De.. | None | | | | | | 56 | |
| 67 Structure Wm (60 De.. | None | | | | | | 56 | |
| 68 Structure Wm (90 De.. | None | | | | | | 56 | |
| 69 Structure Wm (120 D.. | None | | | | | | 56 | |
| 70 Structure Wm (150 D.. | None | | | | | | 56 | |
| 71 Structure Wm (180 D.. | None | | | | | | 56 | |
| 72 Structure Wm (210 D.. | None | | | | | | 56 | |
| 73 Structure Wm (240 D.. | None | | | | | | 56 | |
| 74 Structure Wm (270 D.. | None | | | | | | 56 | |
| 75 Structure Wm (300 D.. | None | | | | | | 56 | |
| 76 Structure Wm (330 D.. | None | | | | | | 56 | |
| 77 Lm1 | None | | | | | 1 | | |
| 78 Lm2 | None | | | | | 1 | | |
| 79 Lv1 | None | | | | | 1 | | |
| 80 Lv2 | None | | | | | 1 | | |
| 81 Antenna Ev | None | | | | | 36 | | |
| 82 Antenna Eh (0 Deg) | None | | | | | 24 | | |
| 83 Antenna Eh (90 Deg) | None | | | | | 24 | | |
| 84 Structure Ev | ELY | | -.043 | | | | | |
| 85 Structure Eh (0 Deg) | ELZ | | | -.107 | | | | |
| 86 Structure Eh (90 Deg) | ELX | .107 | | | | | | |

Load Combinations

| Description | S... | PDelta | S... | B... | Fa... | B... | Fa... | B... | Fa... | B... | Fa... | B... | Fa... | B... | Fa... | B... | Fa... | B... | Fa... | B... |
|-----------------------------------|------|--------|------|------|-------|------|-------|------|-------|------|-------|------|-------|------|-------|------|-------|------|-------|------|
| 1 1.2D+1.0Wo (0 Deg) | Yes | Y | | 1 | 1.2 | 39 | 1.2 | 3 | 1 | 41 | 1 | | | | | | | | | |
| 2 1.2D+1.0Wo (30 Deg) | Yes | Y | | 1 | 1.2 | 39 | 1.2 | 4 | 1 | 42 | 1 | | | | | | | | | |
| 3 1.2D+1.0Wo (60 Deg) | Yes | Y | | 1 | 1.2 | 39 | 1.2 | 5 | 1 | 43 | 1 | | | | | | | | | |
| 4 1.2D+1.0Wo (90 Deg) | Yes | Y | | 1 | 1.2 | 39 | 1.2 | 6 | 1 | 44 | 1 | | | | | | | | | |
| 5 1.2D+1.0Wo (120 Deg) | Yes | Y | | 1 | 1.2 | 39 | 1.2 | 7 | 1 | 45 | 1 | | | | | | | | | |
| 6 1.2D+1.0Wo (150 Deg) | Yes | Y | | 1 | 1.2 | 39 | 1.2 | 8 | 1 | 46 | 1 | | | | | | | | | |
| 7 1.2D+1.0Wo (180 Deg) | Yes | Y | | 1 | 1.2 | 39 | 1.2 | 9 | 1 | 47 | 1 | | | | | | | | | |
| 8 1.2D+1.0Wo (210 Deg) | Yes | Y | | 1 | 1.2 | 39 | 1.2 | 10 | 1 | 48 | 1 | | | | | | | | | |
| 9 1.2D+1.0Wo (240 Deg) | Yes | Y | | 1 | 1.2 | 39 | 1.2 | 11 | 1 | 49 | 1 | | | | | | | | | |
| 10 1.2D+1.0Wo (270 Deg) | Yes | Y | | 1 | 1.2 | 39 | 1.2 | 12 | 1 | 50 | 1 | | | | | | | | | |
| 11 1.2D+1.0Wo (300 Deg) | Yes | Y | | 1 | 1.2 | 39 | 1.2 | 13 | 1 | 51 | 1 | | | | | | | | | |
| 12 1.2D+1.0Wo (330 Deg) | Yes | Y | | 1 | 1.2 | 39 | 1.2 | 14 | 1 | 52 | 1 | | | | | | | | | |
| 13 1.2D + 1.0Di + 1.0Wi (0 Deg) | Yes | Y | | 1 | 1.2 | 39 | 1.2 | 2 | 1 | 40 | 1 | 15 | 1 | 53 | 1 | | | | | |
| 14 1.2D + 1.0Di + 1.0Wi (30 Deg) | Yes | Y | | 1 | 1.2 | 39 | 1.2 | 2 | 1 | 40 | 1 | 16 | 1 | 54 | 1 | | | | | |
| 15 1.2D + 1.0Di + 1.0Wi (60 Deg) | Yes | Y | | 1 | 1.2 | 39 | 1.2 | 2 | 1 | 40 | 1 | 17 | 1 | 55 | 1 | | | | | |
| 16 1.2D + 1.0Di + 1.0Wi (90 Deg) | Yes | Y | | 1 | 1.2 | 39 | 1.2 | 2 | 1 | 40 | 1 | 18 | 1 | 56 | 1 | | | | | |
| 17 1.2D + 1.0Di + 1.0Wi (120 Deg) | Yes | Y | | 1 | 1.2 | 39 | 1.2 | 2 | 1 | 40 | 1 | 19 | 1 | 57 | 1 | | | | | |
| 18 1.2D + 1.0Di + 1.0Wi (150 Deg) | Yes | Y | | 1 | 1.2 | 39 | 1.2 | 2 | 1 | 40 | 1 | 20 | 1 | 58 | 1 | | | | | |
| 19 1.2D + 1.0Di + 1.0Wi (180 Deg) | Yes | Y | | 1 | 1.2 | 39 | 1.2 | 2 | 1 | 40 | 1 | 21 | 1 | 59 | 1 | | | | | |
| 20 1.2D + 1.0Di + 1.0Wi (210 Deg) | Yes | Y | | 1 | 1.2 | 39 | 1.2 | 2 | 1 | 40 | 1 | 22 | 1 | 60 | 1 | | | | | |
| 21 1.2D + 1.0Di + 1.0Wi (240 Deg) | Yes | Y | | 1 | 1.2 | 39 | 1.2 | 2 | 1 | 40 | 1 | 23 | 1 | 61 | 1 | | | | | |
| 22 1.2D + 1.0Di + 1.0Wi (270 Deg) | Yes | Y | | 1 | 1.2 | 39 | 1.2 | 2 | 1 | 40 | 1 | 24 | 1 | 62 | 1 | | | | | |



Company :
 Designer :
 Job Number :
 Model Name :

Apr 12, 2022
 10:37 AM
 Checked By: _____

Joint Coordinates and Temperatures

| | Label | X [ft] | Y [ft] | Z [ft] | Temp [F] | Detach From Diap... |
|----|-------|-----------|----------|----------|----------|---------------------|
| 1 | N1 | 3.416667 | 0.145833 | 8.083333 | 0 | |
| 2 | N2 | -9.083333 | 0.145833 | 8.083333 | 0 | |
| 3 | N3 | 3.416667 | 3.479167 | 8.083333 | 0 | |
| 4 | N4 | -9.083333 | 3.479167 | 8.083333 | 0 | |
| 5 | N5 | -8.833333 | 0.145833 | 8.083333 | 0 | |
| 6 | N6 | -8.833333 | 3.479167 | 8.083333 | 0 | |
| 7 | N7 | -4.833333 | 0.145833 | 8.083333 | 0 | |
| 8 | N8 | -4.833333 | 3.479167 | 8.083333 | 0 | |
| 9 | N9 | -0.833333 | 0.145833 | 8.083333 | 0 | |
| 10 | N10 | -0.833333 | 3.479167 | 8.083333 | 0 | |
| 11 | N11 | 3.166667 | 0.145833 | 8.083333 | 0 | |
| 12 | N12 | 3.166667 | 3.479167 | 8.083333 | 0 | |
| 13 | N13 | -8.833333 | 0.145833 | 8.333333 | 0 | |
| 14 | N14 | -8.833333 | 3.479167 | 8.333333 | 0 | |
| 15 | N15 | -4.833333 | 0.145833 | 8.333333 | 0 | |
| 16 | N16 | -4.833333 | 3.479167 | 8.333333 | 0 | |
| 17 | N17 | -0.833333 | 0.145833 | 8.333333 | 0 | |
| 18 | N18 | -0.833333 | 3.479167 | 8.333333 | 0 | |
| 19 | N19 | 3.166667 | 0.145833 | 8.333333 | 0 | |
| 20 | N20 | 3.166667 | 3.479167 | 8.333333 | 0 | |
| 21 | N21 | -5.333333 | 0 | 8.083333 | 0 | |
| 22 | N22 | -5.333333 | 3.333333 | 8.083333 | 0 | |
| 23 | N23 | -0.333333 | 0 | 8.083333 | 0 | |
| 24 | N24 | -0.333333 | 3.333333 | 8.083333 | 0 | |
| 25 | N25 | -5.333333 | 0 | 7.661458 | 0 | |
| 26 | N26 | -5.333333 | 3.333333 | 7.661458 | 0 | |
| 27 | N27 | -0.333333 | 0 | 7.661458 | 0 | |
| 28 | N28 | -0.333333 | 3.333333 | 7.661458 | 0 | |
| 29 | N29 | -2.833333 | 0 | 6.119792 | 0 | |
| 30 | N30 | -2.833333 | 3.333333 | 6.119792 | 0 | |
| 31 | N31 | -3.364583 | 0 | 6.119792 | 0 | |
| 32 | N32 | -3.364583 | 3.333333 | 6.119792 | 0 | |
| 33 | N33 | -2.302083 | 0 | 6.119792 | 0 | |
| 34 | N34 | -2.302083 | 3.333333 | 6.119792 | 0 | |
| 35 | N35 | -2.833333 | 0 | 5.453125 | 0 | |
| 36 | N36 | -2.833333 | 3.333333 | 5.453125 | 0 | |
| 37 | N39 | -8.833333 | 5.8125 | 8.333333 | 0 | |
| 38 | N40 | -4.833333 | 5.8125 | 8.333333 | 0 | |
| 39 | N41 | -0.833333 | 5.8125 | 8.333333 | 0 | |
| 40 | N42 | 3.166667 | 5.8125 | 8.333333 | 0 | |
| 41 | N43 | -8.833333 | -2.1875 | 8.333333 | 0 | |
| 42 | N44 | -4.833333 | -2.1875 | 8.333333 | 0 | |
| 43 | N45 | -0.833333 | -2.1875 | 8.333333 | 0 | |
| 44 | N46 | 3.166667 | -2.1875 | 8.333333 | 0 | |
| 45 | N58 | -5.333333 | 3.333333 | 7.708333 | 0 | |
| 46 | N76 | -2.927083 | 0 | 6.119792 | 0 | |
| 47 | N77 | -3.229167 | 0 | 6.119792 | 0 | |
| 48 | N78 | -2.739583 | 0 | 6.119792 | 0 | |
| 49 | N79 | -2.4375 | 0 | 6.119792 | 0 | |
| 50 | N80 | -2.927083 | 3.333333 | 6.119792 | 0 | |
| 51 | N81 | -3.229167 | 3.333333 | 6.119792 | 0 | |
| 52 | N82 | -2.739583 | 3.333333 | 6.119792 | 0 | |
| 53 | N83 | -2.4375 | 3.333333 | 6.119792 | 0 | |
| 54 | N58A | -2.833333 | 3.479167 | 8.083333 | 0 | |
| 55 | N59 | -5.333333 | 0.145833 | 8.083333 | 0 | |
| 56 | N60 | -5.333333 | 3.479167 | 8.083333 | 0 | |

Joint Coordinates and Temperatures (Continued)

| | Label | X [ft] | Y [ft] | Z [ft] | Temp [F] | Detach From Diap... |
|----|-------|-----------|----------|-----------|----------|---------------------|
| 57 | N61 | -0.333333 | 0.145833 | 8.083333 | 0 | |
| 58 | N62 | -0.333333 | 3.479167 | 8.083333 | 0 | |
| 59 | N59A | -5.833333 | 3.479167 | 8.083333 | 0 | |
| 60 | N60A | 0.166667 | 3.479167 | 8.083333 | 0 | |
| 61 | N63 | -9.708333 | 3.479167 | -6.454724 | 0 | |
| 62 | N64 | 4.041667 | 3.479167 | -6.454724 | 0 | |

Hot Rolled Steel Section Sets

| | Label | Shape | Type | Design List | Material | Design ... | A [in2] | Iyy [in4] | Izz [in4] | J [in4] |
|---|---------------------|-----------|--------|-------------|-----------|------------|---------|-----------|-----------|---------|
| 1 | Antenna Pipe | PIPE 2.0 | Beam | Pipe | A53 Gr. B | Typical | 1.02 | .627 | .627 | 1.25 |
| 2 | Face Horizontal | PIPE 2.5 | Beam | Pipe | Q235 | Typical | 1.61 | 1.45 | 1.45 | 2.89 |
| 3 | Standoff Horizontal | PIPE 2.0 | Beam | Pipe | Q235 | Typical | 1.02 | .627 | .627 | 1.25 |
| 4 | Standoff Diagonal | SR 0.75 | Beam | BAR | Q235 | Typical | .442 | .016 | .016 | .031 |
| 5 | Tieback | PIPE 2.0X | Beam | Pipe | Q235 | Typical | 1.4 | .827 | .827 | 1.65 |
| 6 | Standoff Vertical | SR 0.625 | Beam | BAR | Q235 | Typical | .307 | .007 | .007 | .015 |
| 7 | Standoff Plate | PL5/8X3.5 | Beam | BAR | Q235 | Typical | 2.188 | .071 | 2.233 | .253 |
| 8 | tower pipe | PIPE 3.0 | Column | Pipe | A53 Gr. B | Typical | 2.07 | 2.85 | 2.85 | 5.69 |

Hot Rolled Steel Properties

| | Label | E [ksi] | G [ksi] | Nu | Therm (/1E... | Density[k/ft... | Yield[ksi] | Ry | Fu[ksi] | Rt |
|---|---------------|---------|---------|----|---------------|-----------------|------------|-----|---------|-----|
| 1 | A36 Gr.36 | 29000 | 11154 | .3 | .65 | .49 | 36 | 1.5 | 58 | 1.2 |
| 2 | A53 Gr. B | 29000 | 11154 | .3 | .65 | .49 | 35 | 1.5 | 60 | 1.2 |
| 3 | A572 Gr.50 | 29000 | 11154 | .3 | .65 | .49 | 50 | 1.1 | 65 | 1.1 |
| 4 | A992 | 29000 | 11154 | .3 | .65 | .49 | 50 | 1.1 | 65 | 1.1 |
| 5 | A500 Gr. B 42 | 29000 | 11154 | .3 | .65 | .49 | 42 | 1.4 | 58 | 1.3 |
| 6 | A500 Gr. B 46 | 29000 | 11154 | .3 | .65 | .49 | 46 | 1.4 | 58 | 1.3 |
| 7 | Q235 | 29000 | 11154 | .3 | .65 | .49 | 35 | 1.5 | 58 | 1.2 |

Member Primary Data

| | Label | I Joint | J Joint | K Joint | Rotate(deg) | Section/Shape | Type | Design List | Material | Design Rules |
|----|-------|---------|---------|---------|-------------|-------------------|------|-------------|----------|--------------|
| 1 | FACE | N2 | N1 | | | Face Horizontal | Beam | Pipe | Q235 | Typical |
| 2 | M2 | N4 | N3 | | | Face Horizontal | Beam | Pipe | Q235 | Typical |
| 3 | M3 | N5 | N13 | | | RIGID | None | None | RIGID | Typical |
| 4 | M4 | N6 | N14 | | | RIGID | None | None | RIGID | Typical |
| 5 | M5 | N8 | N16 | | | RIGID | None | None | RIGID | Typical |
| 6 | M6 | N7 | N15 | | | RIGID | None | None | RIGID | Typical |
| 7 | M9 | N10 | N18 | | | RIGID | None | None | RIGID | Typical |
| 8 | LIVE1 | N9 | N17 | | | RIGID | None | None | RIGID | Typical |
| 9 | M11 | N12 | N20 | | | RIGID | None | None | RIGID | Typical |
| 10 | LIVE2 | N11 | N19 | | | RIGID | None | None | RIGID | Typical |
| 11 | M13 | N22 | N26 | | 90 | Standoff Plate | Beam | BAR | Q235 | Typical |
| 12 | M14 | N21 | N25 | | 90 | Standoff Plate | Beam | BAR | Q235 | Typical |
| 13 | M15 | N23 | N27 | | 90 | Standoff Plate | Beam | BAR | Q235 | Typical |
| 14 | M16 | N24 | N28 | | 90 | Standoff Plate | Beam | BAR | Q235 | Typical |
| 15 | M17 | N26 | N32 | | | Standoff Horiz... | Beam | Pipe | Q235 | Typical |
| 16 | M18 | N25 | N31 | | | Standoff Horiz... | Beam | Pipe | Q235 | Typical |
| 17 | M19 | N27 | N33 | | | Standoff Horiz... | Beam | Pipe | Q235 | Typical |
| 18 | M20 | N28 | N34 | | | Standoff Horiz... | Beam | Pipe | Q235 | Typical |
| 19 | M21 | N32 | N30 | | 90 | Standoff Plate | Beam | BAR | Q235 | Typical |
| 20 | M22 | N34 | N30 | | 90 | Standoff Plate | Beam | BAR | Q235 | Typical |
| 21 | M23 | N31 | N29 | | 90 | Standoff Plate | Beam | BAR | Q235 | Typical |
| 22 | M24 | N33 | N29 | | 90 | Standoff Plate | Beam | BAR | Q235 | Typical |

Member Primary Data (Continued)

| | Label | I Joint | J Joint | K Joint | Rotate(deg) | Section/Shape | Type | Design List | Material | Design Rules |
|----|-------|---------|---------|---------|-------------|-------------------|------|-------------|-----------|--------------|
| 23 | M25 | N31 | N26 | | | Standoff Diago... | Beam | BAR | Q235 | Typical |
| 24 | M26 | N32 | N25 | | | Standoff Diago... | Beam | BAR | Q235 | Typical |
| 25 | M27 | N33 | N28 | | | Standoff Diago... | Beam | BAR | Q235 | Typical |
| 26 | M28 | N27 | N34 | | | Standoff Diago... | Beam | BAR | Q235 | Typical |
| 27 | M29 | N29 | N35 | | | RIGID | None | None | RIGID | Typical |
| 28 | M30 | N30 | N36 | | | RIGID | None | None | RIGID | Typical |
| 29 | MP4A | N39 | N43 | | | Antenna Pipe | Beam | Pipe | A53 Gr. B | Typical |
| 30 | MP3A | N40 | N44 | | | Antenna Pipe | Beam | Pipe | A53 Gr. B | Typical |
| 31 | MP2A | N41 | N45 | | | Antenna Pipe | Beam | Pipe | A53 Gr. B | Typical |
| 32 | MP1A | N42 | N46 | | | Antenna Pipe | Beam | Pipe | A53 Gr. B | Typical |
| 33 | M44 | N25 | N26 | | | Standoff Vertical | Beam | BAR | Q235 | Typical |
| 34 | M45 | N31 | N32 | | | Standoff Vertical | Beam | BAR | Q235 | Typical |
| 35 | M46 | N33 | N34 | | | Standoff Vertical | Beam | BAR | Q235 | Typical |
| 36 | M47 | N27 | N28 | | | Standoff Vertical | Beam | BAR | Q235 | Typical |
| 37 | M47B | N22 | N60 | | | RIGID | None | None | RIGID | Typical |
| 38 | M48A | N21 | N59 | | | RIGID | None | None | RIGID | Typical |
| 39 | M49A | N24 | N62 | | | RIGID | None | None | RIGID | Typical |
| 40 | M50A | N23 | N61 | | | RIGID | None | None | RIGID | Typical |
| 41 | M51A | N30 | N36 | | | RIGID | None | None | RIGID | Typical |
| 42 | M52A | N29 | N35 | | | RIGID | None | None | RIGID | Typical |
| 43 | M43 | N59A | N63 | | | Tieback | Beam | Pipe | Q235 | Typical |
| 44 | M44A | N60A | N64 | | | Tieback | Beam | Pipe | Q235 | Typical |

Member Advanced Data

| | Label | I Release | J Release | I Offset[in] | J Offset[in] | T/C Only | Physical | Defl Rat... | Analysis ... | Inactive | Seismic... |
|----|-------|-----------|-----------|--------------|--------------|----------|----------|-------------|--------------|----------|------------|
| 1 | FACE | | | | | | Yes | | | | None |
| 2 | M2 | | | | | | Yes | | | | None |
| 3 | M3 | | | | | | Yes | ** NA ** | | | None |
| 4 | M4 | | | | | | Yes | ** NA ** | | | None |
| 5 | M5 | | | | | | Yes | ** NA ** | | | None |
| 6 | M6 | | | | | | Yes | ** NA ** | | | None |
| 7 | M9 | | | | | | Yes | ** NA ** | | | None |
| 8 | LIVE1 | | | | | | Yes | ** NA ** | | | None |
| 9 | M11 | | | | | | Yes | ** NA ** | | | None |
| 10 | LIVE2 | | | | | | Yes | ** NA ** | | | None |
| 11 | M13 | | | | | | Yes | Default | | | None |
| 12 | M14 | | | | | | Yes | Default | | | None |
| 13 | M15 | | | | | | Yes | | | | None |
| 14 | M16 | | | | | | Yes | | | | None |
| 15 | M17 | | | | | | Yes | Default | | | None |
| 16 | M18 | | | | | | Yes | | | | None |
| 17 | M19 | | | | | | Yes | | | | None |
| 18 | M20 | | | | | | Yes | Default | | | None |
| 19 | M21 | | | | | | Yes | Default | | | None |
| 20 | M22 | | | | | | Yes | | | | None |
| 21 | M23 | | | | | | Yes | | | | None |
| 22 | M24 | | | | | | Yes | | | | None |
| 23 | M25 | BenPIN | BenPIN | | | | Yes | Default | | | None |
| 24 | M26 | BenPIN | BenPIN | | | | Yes | Default | | | None |
| 25 | M27 | BenPIN | BenPIN | | | | Yes | | | | None |
| 26 | M28 | BenPIN | BenPIN | | | | Yes | | | | None |
| 27 | M29 | | | | | | Yes | ** NA ** | | Inactive | None |
| 28 | M30 | | | | | | Yes | ** NA ** | | Inactive | None |
| 29 | MP4A | | | | | | Yes | | | | None |
| 30 | MP3A | | | | | | Yes | | | | None |

Member Advanced Data (Continued)

| | Label | I Release | J Release | I Offset[in] | J Offset[in] | T/C Only | Physical | Defl Rat... | Analysis ... | Inactive | Seismic... |
|----|-------|-----------|-----------|--------------|--------------|----------|----------|-------------|--------------|----------|------------|
| 31 | MP2A | | | | | | Yes | | | | None |
| 32 | MP1A | | | | | | Yes | | | | None |
| 33 | M44 | BenPIN | BenPIN | | | | Yes | | | | None |
| 34 | M45 | BenPIN | BenPIN | | | | Yes | | | | None |
| 35 | M46 | BenPIN | BenPIN | | | | Yes | | | | None |
| 36 | M47 | BenPIN | BenPIN | | | | Yes | Default | | | None |
| 37 | M47B | | OOOXOO | | | | Yes | ** NA ** | | | None |
| 38 | M48A | | OOOXOO | | | | Yes | ** NA ** | | | None |
| 39 | M49A | | OOOXOO | | | | Yes | ** NA ** | | | None |
| 40 | M50A | | OOOXOO | | | | Yes | ** NA ** | | | None |
| 41 | M51A | | | | | | Yes | ** NA ** | | | None |
| 42 | M52A | | | | | | Yes | ** NA ** | | | None |
| 43 | M43 | BenPIN | | | | | Yes | Default | | | None |
| 44 | M44A | BenPIN | | | | | Yes | Default | | | None |

Member Point Loads (BLC 1 : Antenna D)

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft.%] |
|----|--------------|-----------|--------------------|----------------|
| 1 | MP2A | Y | -23 | 2 |
| 2 | MP2A | My | -.011 | 2 |
| 3 | MP2A | Mz | .017 | 2 |
| 4 | MP2A | Y | -23 | 6 |
| 5 | MP2A | My | -.011 | 6 |
| 6 | MP2A | Mz | .017 | 6 |
| 7 | MP2A | Y | -23 | 2 |
| 8 | MP2A | My | -.011 | 2 |
| 9 | MP2A | Mz | -.017 | 2 |
| 10 | MP2A | Y | -23 | 6 |
| 11 | MP2A | My | -.011 | 6 |
| 12 | MP2A | Mz | -.017 | 6 |
| 13 | MP3A | Y | -43.55 | 3 |
| 14 | MP3A | My | -.022 | 3 |
| 15 | MP3A | Mz | 0 | 3 |
| 16 | MP3A | Y | -43.55 | 5 |
| 17 | MP3A | My | -.022 | 5 |
| 18 | MP3A | Mz | 0 | 5 |
| 19 | MP2A | Y | -84.4 | 3 |
| 20 | MP2A | My | .042 | 3 |
| 21 | MP2A | Mz | 0 | 3 |
| 22 | MP1A | Y | -70.3 | 3 |
| 23 | MP1A | My | .035 | 3 |
| 24 | MP1A | Mz | 0 | 3 |
| 25 | MP1A | Y | -13.5 | 2 |
| 26 | MP1A | My | -.007 | 2 |
| 27 | MP1A | Mz | 0 | 2 |
| 28 | MP1A | Y | -13.5 | 6 |
| 29 | MP1A | My | -.007 | 6 |
| 30 | MP1A | Mz | 0 | 6 |
| 31 | MP4A | Y | -13.5 | 2 |
| 32 | MP4A | My | -.007 | 2 |
| 33 | MP4A | Mz | 0 | 2 |
| 34 | MP4A | Y | -13.5 | 6 |
| 35 | MP4A | My | -.007 | 6 |
| 36 | MP4A | Mz | 0 | 6 |

Member Point Loads (BLC 2 : Antenna Di)

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft. %] |
|----|--------------|-----------|--------------------|-----------------|
| 1 | MP2A | Y | -82.579 | 2 |
| 2 | MP2A | My | -.041 | 2 |
| 3 | MP2A | Mz | .062 | 2 |
| 4 | MP2A | Y | -82.579 | 6 |
| 5 | MP2A | My | -.041 | 6 |
| 6 | MP2A | Mz | .062 | 6 |
| 7 | MP2A | Y | -82.579 | 2 |
| 8 | MP2A | My | -.041 | 2 |
| 9 | MP2A | Mz | -.062 | 2 |
| 10 | MP2A | Y | -82.579 | 6 |
| 11 | MP2A | My | -.041 | 6 |
| 12 | MP2A | Mz | -.062 | 6 |
| 13 | MP3A | Y | -35.664 | 3 |
| 14 | MP3A | My | -.018 | 3 |
| 15 | MP3A | Mz | 0 | 3 |
| 16 | MP3A | Y | -35.664 | 5 |
| 17 | MP3A | My | -.018 | 5 |
| 18 | MP3A | Mz | 0 | 5 |
| 19 | MP2A | Y | -44.965 | 3 |
| 20 | MP2A | My | .022 | 3 |
| 21 | MP2A | Mz | 0 | 3 |
| 22 | MP1A | Y | -40.438 | 3 |
| 23 | MP1A | My | .02 | 3 |
| 24 | MP1A | Mz | 0 | 3 |
| 25 | MP1A | Y | -88.795 | 2 |
| 26 | MP1A | My | -.044 | 2 |
| 27 | MP1A | Mz | 0 | 2 |
| 28 | MP1A | Y | -88.795 | 6 |
| 29 | MP1A | My | -.044 | 6 |
| 30 | MP1A | Mz | 0 | 6 |
| 31 | MP4A | Y | -88.795 | 2 |
| 32 | MP4A | My | -.044 | 2 |
| 33 | MP4A | Mz | 0 | 2 |
| 34 | MP4A | Y | -88.795 | 6 |
| 35 | MP4A | My | -.044 | 6 |
| 36 | MP4A | Mz | 0 | 6 |

Member Point Loads (BLC 3 : Antenna Wo (0 Deg))

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft. %] |
|----|--------------|-----------|--------------------|-----------------|
| 1 | MP2A | X | 0 | 2 |
| 2 | MP2A | Z | -160.848 | 2 |
| 3 | MP2A | Mx | -.121 | 2 |
| 4 | MP2A | X | 0 | 6 |
| 5 | MP2A | Z | -160.848 | 6 |
| 6 | MP2A | Mx | -.121 | 6 |
| 7 | MP2A | X | 0 | 2 |
| 8 | MP2A | Z | -160.848 | 2 |
| 9 | MP2A | Mx | .121 | 2 |
| 10 | MP2A | X | 0 | 6 |
| 11 | MP2A | Z | -160.848 | 6 |
| 12 | MP2A | Mx | .121 | 6 |
| 13 | MP3A | X | 0 | 3 |
| 14 | MP3A | Z | -76.594 | 3 |
| 15 | MP3A | Mx | 0 | 3 |
| 16 | MP3A | X | 0 | 5 |
| 17 | MP3A | Z | -76.594 | 5 |

Member Point Loads (BLC 3 : Antenna Wo (0 Deg)) (Continued)

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft. %] |
|----|--------------|-----------|--------------------|-----------------|
| 18 | MP3A | Mx | 0 | 5 |
| 19 | MP2A | X | 0 | 3 |
| 20 | MP2A | Z | -50.52 | 3 |
| 21 | MP2A | Mx | 0 | 3 |
| 22 | MP1A | X | 0 | 3 |
| 23 | MP1A | Z | -50.52 | 3 |
| 24 | MP1A | Mx | 0 | 3 |
| 25 | MP1A | X | 0 | 2 |
| 26 | MP1A | Z | -156.448 | 2 |
| 27 | MP1A | Mx | 0 | 2 |
| 28 | MP1A | X | 0 | 6 |
| 29 | MP1A | Z | -156.448 | 6 |
| 30 | MP1A | Mx | 0 | 6 |
| 31 | MP4A | X | 0 | 2 |
| 32 | MP4A | Z | -156.448 | 2 |
| 33 | MP4A | Mx | 0 | 2 |
| 34 | MP4A | X | 0 | 6 |
| 35 | MP4A | Z | -156.448 | 6 |
| 36 | MP4A | Mx | 0 | 6 |

Member Point Loads (BLC 4 : Antenna Wo (30 Deg))

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft. %] |
|----|--------------|-----------|--------------------|-----------------|
| 1 | MP2A | X | 75.266 | 2 |
| 2 | MP2A | Z | -130.364 | 2 |
| 3 | MP2A | Mx | -.135 | 2 |
| 4 | MP2A | X | 75.266 | 6 |
| 5 | MP2A | Z | -130.364 | 6 |
| 6 | MP2A | Mx | -.135 | 6 |
| 7 | MP2A | X | 75.266 | 2 |
| 8 | MP2A | Z | -130.364 | 2 |
| 9 | MP2A | Mx | .06 | 2 |
| 10 | MP2A | X | 75.266 | 6 |
| 11 | MP2A | Z | -130.364 | 6 |
| 12 | MP2A | Mx | .06 | 6 |
| 13 | MP3A | X | 32.471 | 3 |
| 14 | MP3A | Z | -56.242 | 3 |
| 15 | MP3A | Mx | -.016 | 3 |
| 16 | MP3A | X | 32.471 | 5 |
| 17 | MP3A | Z | -56.242 | 5 |
| 18 | MP3A | Mx | -.016 | 5 |
| 19 | MP2A | X | 23.182 | 3 |
| 20 | MP2A | Z | -40.152 | 3 |
| 21 | MP2A | Mx | .012 | 3 |
| 22 | MP1A | X | 22.408 | 3 |
| 23 | MP1A | Z | -38.812 | 3 |
| 24 | MP1A | Mx | .011 | 3 |
| 25 | MP1A | X | 76.135 | 2 |
| 26 | MP1A | Z | -131.87 | 2 |
| 27 | MP1A | Mx | -.038 | 2 |
| 28 | MP1A | X | 76.135 | 6 |
| 29 | MP1A | Z | -131.87 | 6 |
| 30 | MP1A | Mx | -.038 | 6 |
| 31 | MP4A | X | 76.135 | 2 |
| 32 | MP4A | Z | -131.87 | 2 |
| 33 | MP4A | Mx | -.038 | 2 |
| 34 | MP4A | X | 76.135 | 6 |



Company :
 Designer :
 Job Number :
 Model Name :

Apr 12, 2022
 10:37 AM
 Checked By: _____

Member Point Loads (BLC 4 : Antenna Wo (30 Deg)) (Continued)

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft.%] |
|----|--------------|-----------|--------------------|----------------|
| 35 | MP4A | Z | -131.87 | 6 |
| 36 | MP4A | Mx | -.038 | 6 |

Member Point Loads (BLC 5 : Antenna Wo (60 Deg))

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft.%] |
|----|--------------|-----------|--------------------|----------------|
| 1 | MP2A | X | 112.497 | 2 |
| 2 | MP2A | Z | -64.95 | 2 |
| 3 | MP2A | Mx | -.105 | 2 |
| 4 | MP2A | X | 112.497 | 6 |
| 5 | MP2A | Z | -64.95 | 6 |
| 6 | MP2A | Mx | -.105 | 6 |
| 7 | MP2A | X | 112.497 | 2 |
| 8 | MP2A | Z | -64.95 | 2 |
| 9 | MP2A | Mx | -.008 | 2 |
| 10 | MP2A | X | 112.497 | 6 |
| 11 | MP2A | Z | -64.95 | 6 |
| 12 | MP2A | Mx | -.008 | 6 |
| 13 | MP3A | X | 36.06 | 3 |
| 14 | MP3A | Z | -20.819 | 3 |
| 15 | MP3A | Mx | -.018 | 3 |
| 16 | MP3A | X | 36.06 | 5 |
| 17 | MP3A | Z | -20.819 | 5 |
| 18 | MP3A | Mx | -.018 | 5 |
| 19 | MP2A | X | 32.955 | 3 |
| 20 | MP2A | Z | -19.026 | 3 |
| 21 | MP2A | Mx | .016 | 3 |
| 22 | MP1A | X | 28.932 | 3 |
| 23 | MP1A | Z | -16.704 | 3 |
| 24 | MP1A | Mx | .014 | 3 |
| 25 | MP1A | X | 124.635 | 2 |
| 26 | MP1A | Z | -71.958 | 2 |
| 27 | MP1A | Mx | -.062 | 2 |
| 28 | MP1A | X | 124.635 | 6 |
| 29 | MP1A | Z | -71.958 | 6 |
| 30 | MP1A | Mx | -.062 | 6 |
| 31 | MP4A | X | 124.635 | 2 |
| 32 | MP4A | Z | -71.958 | 2 |
| 33 | MP4A | Mx | -.062 | 2 |
| 34 | MP4A | X | 124.635 | 6 |
| 35 | MP4A | Z | -71.958 | 6 |
| 36 | MP4A | Mx | -.062 | 6 |

Member Point Loads (BLC 6 : Antenna Wo (90 Deg))

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft.%] |
|----|--------------|-----------|--------------------|----------------|
| 1 | MP2A | X | 119.584 | 2 |
| 2 | MP2A | Z | 0 | 2 |
| 3 | MP2A | Mx | -.06 | 2 |
| 4 | MP2A | X | 119.584 | 6 |
| 5 | MP2A | Z | 0 | 6 |
| 6 | MP2A | Mx | -.06 | 6 |
| 7 | MP2A | X | 119.584 | 2 |
| 8 | MP2A | Z | 0 | 2 |
| 9 | MP2A | Mx | -.06 | 2 |
| 10 | MP2A | X | 119.584 | 6 |
| 11 | MP2A | Z | 0 | 6 |
| 12 | MP2A | Mx | -.06 | 6 |



Company :
 Designer :
 Job Number :
 Model Name :

Apr 12, 2022
 10:37 AM
 Checked By: _____

Member Point Loads (BLC 6 : Antenna Wo (90 Deg)) (Continued)

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft. %] |
|----|--------------|-----------|--------------------|-----------------|
| 13 | MP3A | X | 29.986 | 3 |
| 14 | MP3A | Z | 0 | 3 |
| 15 | MP3A | Mx | -.015 | 3 |
| 16 | MP3A | X | 29.986 | 5 |
| 17 | MP3A | Z | 0 | 5 |
| 18 | MP3A | Mx | -.015 | 5 |
| 19 | MP2A | X | 33.897 | 3 |
| 20 | MP2A | Z | 0 | 3 |
| 21 | MP2A | Mx | .017 | 3 |
| 22 | MP1A | X | 27.704 | 3 |
| 23 | MP1A | Z | 0 | 3 |
| 24 | MP1A | Mx | .014 | 3 |
| 25 | MP1A | X | 139.739 | 2 |
| 26 | MP1A | Z | 0 | 2 |
| 27 | MP1A | Mx | -.07 | 2 |
| 28 | MP1A | X | 139.739 | 6 |
| 29 | MP1A | Z | 0 | 6 |
| 30 | MP1A | Mx | -.07 | 6 |
| 31 | MP4A | X | 139.739 | 2 |
| 32 | MP4A | Z | 0 | 2 |
| 33 | MP4A | Mx | -.07 | 2 |
| 34 | MP4A | X | 139.739 | 6 |
| 35 | MP4A | Z | 0 | 6 |
| 36 | MP4A | Mx | -.07 | 6 |

Member Point Loads (BLC 7 : Antenna Wo (120 Deg))

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft. %] |
|----|--------------|-----------|--------------------|-----------------|
| 1 | MP2A | X | 112.497 | 2 |
| 2 | MP2A | Z | 64.95 | 2 |
| 3 | MP2A | Mx | -.008 | 2 |
| 4 | MP2A | X | 112.497 | 6 |
| 5 | MP2A | Z | 64.95 | 6 |
| 6 | MP2A | Mx | -.008 | 6 |
| 7 | MP2A | X | 112.497 | 2 |
| 8 | MP2A | Z | 64.95 | 2 |
| 9 | MP2A | Mx | -.105 | 2 |
| 10 | MP2A | X | 112.497 | 6 |
| 11 | MP2A | Z | 64.95 | 6 |
| 12 | MP2A | Mx | -.105 | 6 |
| 13 | MP3A | X | 36.06 | 3 |
| 14 | MP3A | Z | 20.819 | 3 |
| 15 | MP3A | Mx | -.018 | 3 |
| 16 | MP3A | X | 36.06 | 5 |
| 17 | MP3A | Z | 20.819 | 5 |
| 18 | MP3A | Mx | -.018 | 5 |
| 19 | MP2A | X | 32.955 | 3 |
| 20 | MP2A | Z | 19.026 | 3 |
| 21 | MP2A | Mx | .016 | 3 |
| 22 | MP1A | X | 28.932 | 3 |
| 23 | MP1A | Z | 16.704 | 3 |
| 24 | MP1A | Mx | .014 | 3 |
| 25 | MP1A | X | 124.635 | 2 |
| 26 | MP1A | Z | 71.958 | 2 |
| 27 | MP1A | Mx | -.062 | 2 |
| 28 | MP1A | X | 124.635 | 6 |
| 29 | MP1A | Z | 71.958 | 6 |

Member Point Loads (BLC 7 : Antenna Wo (120 Deg)) (Continued)

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft.%] |
|----|--------------|-----------|--------------------|----------------|
| 30 | MP1A | Mx | -.062 | 6 |
| 31 | MP4A | X | 124.635 | 2 |
| 32 | MP4A | Z | 71.958 | 2 |
| 33 | MP4A | Mx | -.062 | 2 |
| 34 | MP4A | X | 124.635 | 6 |
| 35 | MP4A | Z | 71.958 | 6 |
| 36 | MP4A | Mx | -.062 | 6 |

Member Point Loads (BLC 8 : Antenna Wo (150 Deg))

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft.%] |
|----|--------------|-----------|--------------------|----------------|
| 1 | MP2A | X | 75.266 | 2 |
| 2 | MP2A | Z | 130.364 | 2 |
| 3 | MP2A | Mx | .06 | 2 |
| 4 | MP2A | X | 75.266 | 6 |
| 5 | MP2A | Z | 130.364 | 6 |
| 6 | MP2A | Mx | .06 | 6 |
| 7 | MP2A | X | 75.266 | 2 |
| 8 | MP2A | Z | 130.364 | 2 |
| 9 | MP2A | Mx | -.135 | 2 |
| 10 | MP2A | X | 75.266 | 6 |
| 11 | MP2A | Z | 130.364 | 6 |
| 12 | MP2A | Mx | -.135 | 6 |
| 13 | MP3A | X | 32.471 | 3 |
| 14 | MP3A | Z | 56.242 | 3 |
| 15 | MP3A | Mx | -.016 | 3 |
| 16 | MP3A | X | 32.471 | 5 |
| 17 | MP3A | Z | 56.242 | 5 |
| 18 | MP3A | Mx | -.016 | 5 |
| 19 | MP2A | X | 23.182 | 3 |
| 20 | MP2A | Z | 40.152 | 3 |
| 21 | MP2A | Mx | .012 | 3 |
| 22 | MP1A | X | 22.408 | 3 |
| 23 | MP1A | Z | 38.812 | 3 |
| 24 | MP1A | Mx | .011 | 3 |
| 25 | MP1A | X | 76.135 | 2 |
| 26 | MP1A | Z | 131.87 | 2 |
| 27 | MP1A | Mx | -.038 | 2 |
| 28 | MP1A | X | 76.135 | 6 |
| 29 | MP1A | Z | 131.87 | 6 |
| 30 | MP1A | Mx | -.038 | 6 |
| 31 | MP4A | X | 76.135 | 2 |
| 32 | MP4A | Z | 131.87 | 2 |
| 33 | MP4A | Mx | -.038 | 2 |
| 34 | MP4A | X | 76.135 | 6 |
| 35 | MP4A | Z | 131.87 | 6 |
| 36 | MP4A | Mx | -.038 | 6 |

Member Point Loads (BLC 9 : Antenna Wo (180 Deg))

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft.%] |
|---|--------------|-----------|--------------------|----------------|
| 1 | MP2A | X | 0 | 2 |
| 2 | MP2A | Z | 160.848 | 2 |
| 3 | MP2A | Mx | .121 | 2 |
| 4 | MP2A | X | 0 | 6 |
| 5 | MP2A | Z | 160.848 | 6 |
| 6 | MP2A | Mx | .121 | 6 |
| 7 | MP2A | X | 0 | 2 |

Member Point Loads (BLC 9 : Antenna Wo (180 Deg)) (Continued)

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft.%] |
|----|--------------|-----------|--------------------|----------------|
| 8 | MP2A | Z | 160.848 | 2 |
| 9 | MP2A | Mx | -.121 | 2 |
| 10 | MP2A | X | 0 | 6 |
| 11 | MP2A | Z | 160.848 | 6 |
| 12 | MP2A | Mx | -.121 | 6 |
| 13 | MP3A | X | 0 | 3 |
| 14 | MP3A | Z | 76.594 | 3 |
| 15 | MP3A | Mx | 0 | 3 |
| 16 | MP3A | X | 0 | 5 |
| 17 | MP3A | Z | 76.594 | 5 |
| 18 | MP3A | Mx | 0 | 5 |
| 19 | MP2A | X | 0 | 3 |
| 20 | MP2A | Z | 50.52 | 3 |
| 21 | MP2A | Mx | 0 | 3 |
| 22 | MP1A | X | 0 | 3 |
| 23 | MP1A | Z | 50.52 | 3 |
| 24 | MP1A | Mx | 0 | 3 |
| 25 | MP1A | X | 0 | 2 |
| 26 | MP1A | Z | 156.448 | 2 |
| 27 | MP1A | Mx | 0 | 2 |
| 28 | MP1A | X | 0 | 6 |
| 29 | MP1A | Z | 156.448 | 6 |
| 30 | MP1A | Mx | 0 | 6 |
| 31 | MP4A | X | 0 | 2 |
| 32 | MP4A | Z | 156.448 | 2 |
| 33 | MP4A | Mx | 0 | 2 |
| 34 | MP4A | X | 0 | 6 |
| 35 | MP4A | Z | 156.448 | 6 |
| 36 | MP4A | Mx | 0 | 6 |

Member Point Loads (BLC 10 : Antenna Wo (210 Deg))

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft.%] |
|----|--------------|-----------|--------------------|----------------|
| 1 | MP2A | X | -75.266 | 2 |
| 2 | MP2A | Z | 130.364 | 2 |
| 3 | MP2A | Mx | .135 | 2 |
| 4 | MP2A | X | -75.266 | 6 |
| 5 | MP2A | Z | 130.364 | 6 |
| 6 | MP2A | Mx | .135 | 6 |
| 7 | MP2A | X | -75.266 | 2 |
| 8 | MP2A | Z | 130.364 | 2 |
| 9 | MP2A | Mx | -.06 | 2 |
| 10 | MP2A | X | -75.266 | 6 |
| 11 | MP2A | Z | 130.364 | 6 |
| 12 | MP2A | Mx | -.06 | 6 |
| 13 | MP3A | X | -32.471 | 3 |
| 14 | MP3A | Z | 56.242 | 3 |
| 15 | MP3A | Mx | .016 | 3 |
| 16 | MP3A | X | -32.471 | 5 |
| 17 | MP3A | Z | 56.242 | 5 |
| 18 | MP3A | Mx | .016 | 5 |
| 19 | MP2A | X | -23.182 | 3 |
| 20 | MP2A | Z | 40.152 | 3 |
| 21 | MP2A | Mx | -.012 | 3 |
| 22 | MP1A | X | -22.408 | 3 |
| 23 | MP1A | Z | 38.812 | 3 |
| 24 | MP1A | Mx | -.011 | 3 |



Company :
 Designer :
 Job Number :
 Model Name :

Apr 12, 2022
 10:37 AM
 Checked By: _____

Member Point Loads (BLC 10 : Antenna Wo (210 Deg)) (Continued)

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft.%] |
|----|--------------|-----------|--------------------|----------------|
| 25 | MP1A | X | -76.135 | 2 |
| 26 | MP1A | Z | 131.87 | 2 |
| 27 | MP1A | Mx | .038 | 2 |
| 28 | MP1A | X | -76.135 | 6 |
| 29 | MP1A | Z | 131.87 | 6 |
| 30 | MP1A | Mx | .038 | 6 |
| 31 | MP4A | X | -76.135 | 2 |
| 32 | MP4A | Z | 131.87 | 2 |
| 33 | MP4A | Mx | .038 | 2 |
| 34 | MP4A | X | -76.135 | 6 |
| 35 | MP4A | Z | 131.87 | 6 |
| 36 | MP4A | Mx | .038 | 6 |

Member Point Loads (BLC 11 : Antenna Wo (240 Deg))

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft.%] |
|----|--------------|-----------|--------------------|----------------|
| 1 | MP2A | X | -112.497 | 2 |
| 2 | MP2A | Z | 64.95 | 2 |
| 3 | MP2A | Mx | .105 | 2 |
| 4 | MP2A | X | -112.497 | 6 |
| 5 | MP2A | Z | 64.95 | 6 |
| 6 | MP2A | Mx | .105 | 6 |
| 7 | MP2A | X | -112.497 | 2 |
| 8 | MP2A | Z | 64.95 | 2 |
| 9 | MP2A | Mx | .008 | 2 |
| 10 | MP2A | X | -112.497 | 6 |
| 11 | MP2A | Z | 64.95 | 6 |
| 12 | MP2A | Mx | .008 | 6 |
| 13 | MP3A | X | -36.06 | 3 |
| 14 | MP3A | Z | 20.819 | 3 |
| 15 | MP3A | Mx | .018 | 3 |
| 16 | MP3A | X | -36.06 | 5 |
| 17 | MP3A | Z | 20.819 | 5 |
| 18 | MP3A | Mx | .018 | 5 |
| 19 | MP2A | X | -32.955 | 3 |
| 20 | MP2A | Z | 19.026 | 3 |
| 21 | MP2A | Mx | -.016 | 3 |
| 22 | MP1A | X | -28.932 | 3 |
| 23 | MP1A | Z | 16.704 | 3 |
| 24 | MP1A | Mx | -.014 | 3 |
| 25 | MP1A | X | -124.635 | 2 |
| 26 | MP1A | Z | 71.958 | 2 |
| 27 | MP1A | Mx | .062 | 2 |
| 28 | MP1A | X | -124.635 | 6 |
| 29 | MP1A | Z | 71.958 | 6 |
| 30 | MP1A | Mx | .062 | 6 |
| 31 | MP4A | X | -124.635 | 2 |
| 32 | MP4A | Z | 71.958 | 2 |
| 33 | MP4A | Mx | .062 | 2 |
| 34 | MP4A | X | -124.635 | 6 |
| 35 | MP4A | Z | 71.958 | 6 |
| 36 | MP4A | Mx | .062 | 6 |

Member Point Loads (BLC 12 : Antenna Wo (270 Deg))

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft.%] |
|---|--------------|-----------|--------------------|----------------|
| 1 | MP2A | X | -119.584 | 2 |
| 2 | MP2A | Z | 0 | 2 |



Company :
 Designer :
 Job Number :
 Model Name :

Apr 12, 2022
 10:37 AM
 Checked By: _____

Member Point Loads (BLC 12 : Antenna Wo (270 Deg)) (Continued)

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft.%] |
|----|--------------|-----------|--------------------|----------------|
| 3 | MP2A | Mx | .06 | 2 |
| 4 | MP2A | X | -119.584 | 6 |
| 5 | MP2A | Z | 0 | 6 |
| 6 | MP2A | Mx | .06 | 6 |
| 7 | MP2A | X | -119.584 | 2 |
| 8 | MP2A | Z | 0 | 2 |
| 9 | MP2A | Mx | .06 | 2 |
| 10 | MP2A | X | -119.584 | 6 |
| 11 | MP2A | Z | 0 | 6 |
| 12 | MP2A | Mx | .06 | 6 |
| 13 | MP3A | X | -29.986 | 3 |
| 14 | MP3A | Z | 0 | 3 |
| 15 | MP3A | Mx | .015 | 3 |
| 16 | MP3A | X | -29.986 | 5 |
| 17 | MP3A | Z | 0 | 5 |
| 18 | MP3A | Mx | .015 | 5 |
| 19 | MP2A | X | -33.897 | 3 |
| 20 | MP2A | Z | 0 | 3 |
| 21 | MP2A | Mx | -.017 | 3 |
| 22 | MP1A | X | -27.704 | 3 |
| 23 | MP1A | Z | 0 | 3 |
| 24 | MP1A | Mx | -.014 | 3 |
| 25 | MP1A | X | -139.739 | 2 |
| 26 | MP1A | Z | 0 | 2 |
| 27 | MP1A | Mx | .07 | 2 |
| 28 | MP1A | X | -139.739 | 6 |
| 29 | MP1A | Z | 0 | 6 |
| 30 | MP1A | Mx | .07 | 6 |
| 31 | MP4A | X | -139.739 | 2 |
| 32 | MP4A | Z | 0 | 2 |
| 33 | MP4A | Mx | .07 | 2 |
| 34 | MP4A | X | -139.739 | 6 |
| 35 | MP4A | Z | 0 | 6 |
| 36 | MP4A | Mx | .07 | 6 |

Member Point Loads (BLC 13 : Antenna Wo (300 Deg))

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft.%] |
|----|--------------|-----------|--------------------|----------------|
| 1 | MP2A | X | -112.497 | 2 |
| 2 | MP2A | Z | -64.95 | 2 |
| 3 | MP2A | Mx | .008 | 2 |
| 4 | MP2A | X | -112.497 | 6 |
| 5 | MP2A | Z | -64.95 | 6 |
| 6 | MP2A | Mx | .008 | 6 |
| 7 | MP2A | X | -112.497 | 2 |
| 8 | MP2A | Z | -64.95 | 2 |
| 9 | MP2A | Mx | .105 | 2 |
| 10 | MP2A | X | -112.497 | 6 |
| 11 | MP2A | Z | -64.95 | 6 |
| 12 | MP2A | Mx | .105 | 6 |
| 13 | MP3A | X | -36.06 | 3 |
| 14 | MP3A | Z | -20.819 | 3 |
| 15 | MP3A | Mx | .018 | 3 |
| 16 | MP3A | X | -36.06 | 5 |
| 17 | MP3A | Z | -20.819 | 5 |
| 18 | MP3A | Mx | .018 | 5 |
| 19 | MP2A | X | -32.955 | 3 |

Member Point Loads (BLC 13 : Antenna Wo (300 Deg)) (Continued)

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft.%] |
|----|--------------|-----------|--------------------|----------------|
| 20 | MP2A | Z | -19.026 | 3 |
| 21 | MP2A | Mx | -.016 | 3 |
| 22 | MP1A | X | -28.932 | 3 |
| 23 | MP1A | Z | -16.704 | 3 |
| 24 | MP1A | Mx | -.014 | 3 |
| 25 | MP1A | X | -124.635 | 2 |
| 26 | MP1A | Z | -71.958 | 2 |
| 27 | MP1A | Mx | .062 | 2 |
| 28 | MP1A | X | -124.635 | 6 |
| 29 | MP1A | Z | -71.958 | 6 |
| 30 | MP1A | Mx | .062 | 6 |
| 31 | MP4A | X | -124.635 | 2 |
| 32 | MP4A | Z | -71.958 | 2 |
| 33 | MP4A | Mx | .062 | 2 |
| 34 | MP4A | X | -124.635 | 6 |
| 35 | MP4A | Z | -71.958 | 6 |
| 36 | MP4A | Mx | .062 | 6 |

Member Point Loads (BLC 14 : Antenna Wo (330 Deg))

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft.%] |
|----|--------------|-----------|--------------------|----------------|
| 1 | MP2A | X | -75.266 | 2 |
| 2 | MP2A | Z | -130.364 | 2 |
| 3 | MP2A | Mx | -.06 | 2 |
| 4 | MP2A | X | -75.266 | 6 |
| 5 | MP2A | Z | -130.364 | 6 |
| 6 | MP2A | Mx | -.06 | 6 |
| 7 | MP2A | X | -75.266 | 2 |
| 8 | MP2A | Z | -130.364 | 2 |
| 9 | MP2A | Mx | .135 | 2 |
| 10 | MP2A | X | -75.266 | 6 |
| 11 | MP2A | Z | -130.364 | 6 |
| 12 | MP2A | Mx | .135 | 6 |
| 13 | MP3A | X | -32.471 | 3 |
| 14 | MP3A | Z | -56.242 | 3 |
| 15 | MP3A | Mx | .016 | 3 |
| 16 | MP3A | X | -32.471 | 5 |
| 17 | MP3A | Z | -56.242 | 5 |
| 18 | MP3A | Mx | .016 | 5 |
| 19 | MP2A | X | -23.182 | 3 |
| 20 | MP2A | Z | -40.152 | 3 |
| 21 | MP2A | Mx | -.012 | 3 |
| 22 | MP1A | X | -22.408 | 3 |
| 23 | MP1A | Z | -38.812 | 3 |
| 24 | MP1A | Mx | -.011 | 3 |
| 25 | MP1A | X | -76.135 | 2 |
| 26 | MP1A | Z | -131.87 | 2 |
| 27 | MP1A | Mx | .038 | 2 |
| 28 | MP1A | X | -76.135 | 6 |
| 29 | MP1A | Z | -131.87 | 6 |
| 30 | MP1A | Mx | .038 | 6 |
| 31 | MP4A | X | -76.135 | 2 |
| 32 | MP4A | Z | -131.87 | 2 |
| 33 | MP4A | Mx | .038 | 2 |
| 34 | MP4A | X | -76.135 | 6 |
| 35 | MP4A | Z | -131.87 | 6 |
| 36 | MP4A | Mx | .038 | 6 |

Member Point Loads (BLC 15 : Antenna Wi (0 Deg))

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft. %] |
|----|--------------|-----------|--------------------|-----------------|
| 1 | MP2A | X | 0 | 2 |
| 2 | MP2A | Z | -31.495 | 2 |
| 3 | MP2A | Mx | -.024 | 2 |
| 4 | MP2A | X | 0 | 6 |
| 5 | MP2A | Z | -31.495 | 6 |
| 6 | MP2A | Mx | -.024 | 6 |
| 7 | MP2A | X | 0 | 2 |
| 8 | MP2A | Z | -31.495 | 2 |
| 9 | MP2A | Mx | .024 | 2 |
| 10 | MP2A | X | 0 | 6 |
| 11 | MP2A | Z | -31.495 | 6 |
| 12 | MP2A | Mx | .024 | 6 |
| 13 | MP3A | X | 0 | 3 |
| 14 | MP3A | Z | -15.538 | 3 |
| 15 | MP3A | Mx | 0 | 3 |
| 16 | MP3A | X | 0 | 5 |
| 17 | MP3A | Z | -15.538 | 5 |
| 18 | MP3A | Mx | 0 | 5 |
| 19 | MP2A | X | 0 | 3 |
| 20 | MP2A | Z | -13.097 | 3 |
| 21 | MP2A | Mx | 0 | 3 |
| 22 | MP1A | X | 0 | 3 |
| 23 | MP1A | Z | -13.097 | 3 |
| 24 | MP1A | Mx | 0 | 3 |
| 25 | MP1A | X | 0 | 2 |
| 26 | MP1A | Z | -30.651 | 2 |
| 27 | MP1A | Mx | 0 | 2 |
| 28 | MP1A | X | 0 | 6 |
| 29 | MP1A | Z | -30.651 | 6 |
| 30 | MP1A | Mx | 0 | 6 |
| 31 | MP4A | X | 0 | 2 |
| 32 | MP4A | Z | -30.651 | 2 |
| 33 | MP4A | Mx | 0 | 2 |
| 34 | MP4A | X | 0 | 6 |
| 35 | MP4A | Z | -30.651 | 6 |
| 36 | MP4A | Mx | 0 | 6 |

Member Point Loads (BLC 16 : Antenna Wi (30 Deg))

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft. %] |
|----|--------------|-----------|--------------------|-----------------|
| 1 | MP2A | X | 14.789 | 2 |
| 2 | MP2A | Z | -25.615 | 2 |
| 3 | MP2A | Mx | -.027 | 2 |
| 4 | MP2A | X | 14.789 | 6 |
| 5 | MP2A | Z | -25.615 | 6 |
| 6 | MP2A | Mx | -.027 | 6 |
| 7 | MP2A | X | 14.789 | 2 |
| 8 | MP2A | Z | -25.615 | 2 |
| 9 | MP2A | Mx | .012 | 2 |
| 10 | MP2A | X | 14.789 | 6 |
| 11 | MP2A | Z | -25.615 | 6 |
| 12 | MP2A | Mx | .012 | 6 |
| 13 | MP3A | X | 6.654 | 3 |
| 14 | MP3A | Z | -11.525 | 3 |
| 15 | MP3A | Mx | -.003 | 3 |
| 16 | MP3A | X | 6.654 | 5 |
| 17 | MP3A | Z | -11.525 | 5 |

Member Point Loads (BLC 16 : Antenna Wi (30 Deg)) (Continued)

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft. %] |
|----|--------------|-----------|--------------------|-----------------|
| 18 | MP3A | Mx | -.003 | 5 |
| 19 | MP2A | X | 6.05 | 3 |
| 20 | MP2A | Z | -10.479 | 3 |
| 21 | MP2A | Mx | .003 | 3 |
| 22 | MP1A | X | 5.861 | 3 |
| 23 | MP1A | Z | -10.151 | 3 |
| 24 | MP1A | Mx | .003 | 3 |
| 25 | MP1A | X | 14.941 | 2 |
| 26 | MP1A | Z | -25.878 | 2 |
| 27 | MP1A | Mx | -.007 | 2 |
| 28 | MP1A | X | 14.941 | 6 |
| 29 | MP1A | Z | -25.878 | 6 |
| 30 | MP1A | Mx | -.007 | 6 |
| 31 | MP4A | X | 14.941 | 2 |
| 32 | MP4A | Z | -25.878 | 2 |
| 33 | MP4A | Mx | -.007 | 2 |
| 34 | MP4A | X | 14.941 | 6 |
| 35 | MP4A | Z | -25.878 | 6 |
| 36 | MP4A | Mx | -.007 | 6 |

Member Point Loads (BLC 17 : Antenna Wi (60 Deg))

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft. %] |
|----|--------------|-----------|--------------------|-----------------|
| 1 | MP2A | X | 22.295 | 2 |
| 2 | MP2A | Z | -12.872 | 2 |
| 3 | MP2A | Mx | -.021 | 2 |
| 4 | MP2A | X | 22.295 | 6 |
| 5 | MP2A | Z | -12.872 | 6 |
| 6 | MP2A | Mx | -.021 | 6 |
| 7 | MP2A | X | 22.295 | 2 |
| 8 | MP2A | Z | -12.872 | 2 |
| 9 | MP2A | Mx | -.001 | 2 |
| 10 | MP2A | X | 22.295 | 6 |
| 11 | MP2A | Z | -12.872 | 6 |
| 12 | MP2A | Mx | -.001 | 6 |
| 13 | MP3A | X | 7.664 | 3 |
| 14 | MP3A | Z | -4.425 | 3 |
| 15 | MP3A | Mx | -.004 | 3 |
| 16 | MP3A | X | 7.664 | 5 |
| 17 | MP3A | Z | -4.425 | 5 |
| 18 | MP3A | Mx | -.004 | 5 |
| 19 | MP2A | X | 8.753 | 3 |
| 20 | MP2A | Z | -5.053 | 3 |
| 21 | MP2A | Mx | .004 | 3 |
| 22 | MP1A | X | 7.769 | 3 |
| 23 | MP1A | Z | -4.485 | 3 |
| 24 | MP1A | Mx | .004 | 3 |
| 25 | MP1A | X | 24.546 | 2 |
| 26 | MP1A | Z | -14.172 | 2 |
| 27 | MP1A | Mx | -.012 | 2 |
| 28 | MP1A | X | 24.546 | 6 |
| 29 | MP1A | Z | -14.172 | 6 |
| 30 | MP1A | Mx | -.012 | 6 |
| 31 | MP4A | X | 24.546 | 2 |
| 32 | MP4A | Z | -14.172 | 2 |
| 33 | MP4A | Mx | -.012 | 2 |
| 34 | MP4A | X | 24.546 | 6 |



Company :
 Designer :
 Job Number :
 Model Name :

Apr 12, 2022
 10:37 AM
 Checked By: _____

Member Point Loads (BLC 17 : Antenna Wi (60 Deg)) (Continued)

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft.%] |
|----|--------------|-----------|--------------------|----------------|
| 35 | MP4A | Z | -14.172 | 6 |
| 36 | MP4A | Mx | -.012 | 6 |

Member Point Loads (BLC 18 : Antenna Wi (90 Deg))

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft.%] |
|----|--------------|-----------|--------------------|----------------|
| 1 | MP2A | X | 23.827 | 2 |
| 2 | MP2A | Z | 0 | 2 |
| 3 | MP2A | Mx | -.012 | 2 |
| 4 | MP2A | X | 23.827 | 6 |
| 5 | MP2A | Z | 0 | 6 |
| 6 | MP2A | Mx | -.012 | 6 |
| 7 | MP2A | X | 23.827 | 2 |
| 8 | MP2A | Z | 0 | 2 |
| 9 | MP2A | Mx | -.012 | 2 |
| 10 | MP2A | X | 23.827 | 6 |
| 11 | MP2A | Z | 0 | 6 |
| 12 | MP2A | Mx | -.012 | 6 |
| 13 | MP3A | X | 6.619 | 3 |
| 14 | MP3A | Z | 0 | 3 |
| 15 | MP3A | Mx | -.003 | 3 |
| 16 | MP3A | X | 6.619 | 5 |
| 17 | MP3A | Z | 0 | 5 |
| 18 | MP3A | Mx | -.003 | 5 |
| 19 | MP2A | X | 9.11 | 3 |
| 20 | MP2A | Z | 0 | 3 |
| 21 | MP2A | Mx | .005 | 3 |
| 22 | MP1A | X | 7.596 | 3 |
| 23 | MP1A | Z | 0 | 3 |
| 24 | MP1A | Mx | .004 | 3 |
| 25 | MP1A | X | 27.574 | 2 |
| 26 | MP1A | Z | 0 | 2 |
| 27 | MP1A | Mx | -.014 | 2 |
| 28 | MP1A | X | 27.574 | 6 |
| 29 | MP1A | Z | 0 | 6 |
| 30 | MP1A | Mx | -.014 | 6 |
| 31 | MP4A | X | 27.574 | 2 |
| 32 | MP4A | Z | 0 | 2 |
| 33 | MP4A | Mx | -.014 | 2 |
| 34 | MP4A | X | 27.574 | 6 |
| 35 | MP4A | Z | 0 | 6 |
| 36 | MP4A | Mx | -.014 | 6 |

Member Point Loads (BLC 19 : Antenna Wi (120 Deg))

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft.%] |
|----|--------------|-----------|--------------------|----------------|
| 1 | MP2A | X | 22.295 | 2 |
| 2 | MP2A | Z | 12.872 | 2 |
| 3 | MP2A | Mx | -.001 | 2 |
| 4 | MP2A | X | 22.295 | 6 |
| 5 | MP2A | Z | 12.872 | 6 |
| 6 | MP2A | Mx | -.001 | 6 |
| 7 | MP2A | X | 22.295 | 2 |
| 8 | MP2A | Z | 12.872 | 2 |
| 9 | MP2A | Mx | -.021 | 2 |
| 10 | MP2A | X | 22.295 | 6 |
| 11 | MP2A | Z | 12.872 | 6 |
| 12 | MP2A | Mx | -.021 | 6 |



Company :
 Designer :
 Job Number :
 Model Name :

Apr 12, 2022
 10:37 AM
 Checked By: _____

Member Point Loads (BLC 19 : Antenna Wi (120 Deg)) (Continued)

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft.%] |
|----|--------------|-----------|--------------------|----------------|
| 13 | MP3A | X | 7.664 | 3 |
| 14 | MP3A | Z | 4.425 | 3 |
| 15 | MP3A | Mx | -.004 | 3 |
| 16 | MP3A | X | 7.664 | 5 |
| 17 | MP3A | Z | 4.425 | 5 |
| 18 | MP3A | Mx | -.004 | 5 |
| 19 | MP2A | X | 8.753 | 3 |
| 20 | MP2A | Z | 5.053 | 3 |
| 21 | MP2A | Mx | .004 | 3 |
| 22 | MP1A | X | 7.769 | 3 |
| 23 | MP1A | Z | 4.485 | 3 |
| 24 | MP1A | Mx | .004 | 3 |
| 25 | MP1A | X | 24.546 | 2 |
| 26 | MP1A | Z | 14.172 | 2 |
| 27 | MP1A | Mx | -.012 | 2 |
| 28 | MP1A | X | 24.546 | 6 |
| 29 | MP1A | Z | 14.172 | 6 |
| 30 | MP1A | Mx | -.012 | 6 |
| 31 | MP4A | X | 24.546 | 2 |
| 32 | MP4A | Z | 14.172 | 2 |
| 33 | MP4A | Mx | -.012 | 2 |
| 34 | MP4A | X | 24.546 | 6 |
| 35 | MP4A | Z | 14.172 | 6 |
| 36 | MP4A | Mx | -.012 | 6 |

Member Point Loads (BLC 20 : Antenna Wi (150 Deg))

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft.%] |
|----|--------------|-----------|--------------------|----------------|
| 1 | MP2A | X | 14.789 | 2 |
| 2 | MP2A | Z | 25.615 | 2 |
| 3 | MP2A | Mx | .012 | 2 |
| 4 | MP2A | X | 14.789 | 6 |
| 5 | MP2A | Z | 25.615 | 6 |
| 6 | MP2A | Mx | .012 | 6 |
| 7 | MP2A | X | 14.789 | 2 |
| 8 | MP2A | Z | 25.615 | 2 |
| 9 | MP2A | Mx | -.027 | 2 |
| 10 | MP2A | X | 14.789 | 6 |
| 11 | MP2A | Z | 25.615 | 6 |
| 12 | MP2A | Mx | -.027 | 6 |
| 13 | MP3A | X | 6.654 | 3 |
| 14 | MP3A | Z | 11.525 | 3 |
| 15 | MP3A | Mx | -.003 | 3 |
| 16 | MP3A | X | 6.654 | 5 |
| 17 | MP3A | Z | 11.525 | 5 |
| 18 | MP3A | Mx | -.003 | 5 |
| 19 | MP2A | X | 6.05 | 3 |
| 20 | MP2A | Z | 10.479 | 3 |
| 21 | MP2A | Mx | .003 | 3 |
| 22 | MP1A | X | 5.861 | 3 |
| 23 | MP1A | Z | 10.151 | 3 |
| 24 | MP1A | Mx | .003 | 3 |
| 25 | MP1A | X | 14.941 | 2 |
| 26 | MP1A | Z | 25.878 | 2 |
| 27 | MP1A | Mx | -.007 | 2 |
| 28 | MP1A | X | 14.941 | 6 |
| 29 | MP1A | Z | 25.878 | 6 |

Member Point Loads (BLC 20 : Antenna Wi (150 Deg)) (Continued)

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft.%] |
|----|--------------|-----------|--------------------|----------------|
| 30 | MP1A | Mx | -.007 | 6 |
| 31 | MP4A | X | 14.941 | 2 |
| 32 | MP4A | Z | 25.878 | 2 |
| 33 | MP4A | Mx | -.007 | 2 |
| 34 | MP4A | X | 14.941 | 6 |
| 35 | MP4A | Z | 25.878 | 6 |
| 36 | MP4A | Mx | -.007 | 6 |

Member Point Loads (BLC 21 : Antenna Wi (180 Deg))

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft.%] |
|----|--------------|-----------|--------------------|----------------|
| 1 | MP2A | X | 0 | 2 |
| 2 | MP2A | Z | 31.495 | 2 |
| 3 | MP2A | Mx | .024 | 2 |
| 4 | MP2A | X | 0 | 6 |
| 5 | MP2A | Z | 31.495 | 6 |
| 6 | MP2A | Mx | .024 | 6 |
| 7 | MP2A | X | 0 | 2 |
| 8 | MP2A | Z | 31.495 | 2 |
| 9 | MP2A | Mx | -.024 | 2 |
| 10 | MP2A | X | 0 | 6 |
| 11 | MP2A | Z | 31.495 | 6 |
| 12 | MP2A | Mx | -.024 | 6 |
| 13 | MP3A | X | 0 | 3 |
| 14 | MP3A | Z | 15.538 | 3 |
| 15 | MP3A | Mx | 0 | 3 |
| 16 | MP3A | X | 0 | 5 |
| 17 | MP3A | Z | 15.538 | 5 |
| 18 | MP3A | Mx | 0 | 5 |
| 19 | MP2A | X | 0 | 3 |
| 20 | MP2A | Z | 13.097 | 3 |
| 21 | MP2A | Mx | 0 | 3 |
| 22 | MP1A | X | 0 | 3 |
| 23 | MP1A | Z | 13.097 | 3 |
| 24 | MP1A | Mx | 0 | 3 |
| 25 | MP1A | X | 0 | 2 |
| 26 | MP1A | Z | 30.651 | 2 |
| 27 | MP1A | Mx | 0 | 2 |
| 28 | MP1A | X | 0 | 6 |
| 29 | MP1A | Z | 30.651 | 6 |
| 30 | MP1A | Mx | 0 | 6 |
| 31 | MP4A | X | 0 | 2 |
| 32 | MP4A | Z | 30.651 | 2 |
| 33 | MP4A | Mx | 0 | 2 |
| 34 | MP4A | X | 0 | 6 |
| 35 | MP4A | Z | 30.651 | 6 |
| 36 | MP4A | Mx | 0 | 6 |

Member Point Loads (BLC 22 : Antenna Wi (210 Deg))

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft.%] |
|---|--------------|-----------|--------------------|----------------|
| 1 | MP2A | X | -14.789 | 2 |
| 2 | MP2A | Z | 25.615 | 2 |
| 3 | MP2A | Mx | .027 | 2 |
| 4 | MP2A | X | -14.789 | 6 |
| 5 | MP2A | Z | 25.615 | 6 |
| 6 | MP2A | Mx | .027 | 6 |
| 7 | MP2A | X | -14.789 | 2 |

Member Point Loads (BLC 22 : Antenna Wi (210 Deg)) (Continued)

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft.%] |
|----|--------------|-----------|--------------------|----------------|
| 8 | MP2A | Z | 25.615 | 2 |
| 9 | MP2A | Mx | -.012 | 2 |
| 10 | MP2A | X | -14.789 | 6 |
| 11 | MP2A | Z | 25.615 | 6 |
| 12 | MP2A | Mx | -.012 | 6 |
| 13 | MP3A | X | -6.654 | 3 |
| 14 | MP3A | Z | 11.525 | 3 |
| 15 | MP3A | Mx | .003 | 3 |
| 16 | MP3A | X | -6.654 | 5 |
| 17 | MP3A | Z | 11.525 | 5 |
| 18 | MP3A | Mx | .003 | 5 |
| 19 | MP2A | X | -6.05 | 3 |
| 20 | MP2A | Z | 10.479 | 3 |
| 21 | MP2A | Mx | -.003 | 3 |
| 22 | MP1A | X | -5.861 | 3 |
| 23 | MP1A | Z | 10.151 | 3 |
| 24 | MP1A | Mx | -.003 | 3 |
| 25 | MP1A | X | -14.941 | 2 |
| 26 | MP1A | Z | 25.878 | 2 |
| 27 | MP1A | Mx | .007 | 2 |
| 28 | MP1A | X | -14.941 | 6 |
| 29 | MP1A | Z | 25.878 | 6 |
| 30 | MP1A | Mx | .007 | 6 |
| 31 | MP4A | X | -14.941 | 2 |
| 32 | MP4A | Z | 25.878 | 2 |
| 33 | MP4A | Mx | .007 | 2 |
| 34 | MP4A | X | -14.941 | 6 |
| 35 | MP4A | Z | 25.878 | 6 |
| 36 | MP4A | Mx | .007 | 6 |

Member Point Loads (BLC 23 : Antenna Wi (240 Deg))

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft.%] |
|----|--------------|-----------|--------------------|----------------|
| 1 | MP2A | X | -22.295 | 2 |
| 2 | MP2A | Z | 12.872 | 2 |
| 3 | MP2A | Mx | .021 | 2 |
| 4 | MP2A | X | -22.295 | 6 |
| 5 | MP2A | Z | 12.872 | 6 |
| 6 | MP2A | Mx | .021 | 6 |
| 7 | MP2A | X | -22.295 | 2 |
| 8 | MP2A | Z | 12.872 | 2 |
| 9 | MP2A | Mx | .001 | 2 |
| 10 | MP2A | X | -22.295 | 6 |
| 11 | MP2A | Z | 12.872 | 6 |
| 12 | MP2A | Mx | .001 | 6 |
| 13 | MP3A | X | -7.664 | 3 |
| 14 | MP3A | Z | 4.425 | 3 |
| 15 | MP3A | Mx | .004 | 3 |
| 16 | MP3A | X | -7.664 | 5 |
| 17 | MP3A | Z | 4.425 | 5 |
| 18 | MP3A | Mx | .004 | 5 |
| 19 | MP2A | X | -8.753 | 3 |
| 20 | MP2A | Z | 5.053 | 3 |
| 21 | MP2A | Mx | -.004 | 3 |
| 22 | MP1A | X | -7.769 | 3 |
| 23 | MP1A | Z | 4.485 | 3 |
| 24 | MP1A | Mx | -.004 | 3 |

Member Point Loads (BLC 23 : Antenna Wi (240 Deg)) (Continued)

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft. %] |
|----|--------------|-----------|--------------------|-----------------|
| 25 | MP1A | X | -24.546 | 2 |
| 26 | MP1A | Z | 14.172 | 2 |
| 27 | MP1A | Mx | .012 | 2 |
| 28 | MP1A | X | -24.546 | 6 |
| 29 | MP1A | Z | 14.172 | 6 |
| 30 | MP1A | Mx | .012 | 6 |
| 31 | MP4A | X | -24.546 | 2 |
| 32 | MP4A | Z | 14.172 | 2 |
| 33 | MP4A | Mx | .012 | 2 |
| 34 | MP4A | X | -24.546 | 6 |
| 35 | MP4A | Z | 14.172 | 6 |
| 36 | MP4A | Mx | .012 | 6 |

Member Point Loads (BLC 24 : Antenna Wi (270 Deg))

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft. %] |
|----|--------------|-----------|--------------------|-----------------|
| 1 | MP2A | X | -23.827 | 2 |
| 2 | MP2A | Z | 0 | 2 |
| 3 | MP2A | Mx | .012 | 2 |
| 4 | MP2A | X | -23.827 | 6 |
| 5 | MP2A | Z | 0 | 6 |
| 6 | MP2A | Mx | .012 | 6 |
| 7 | MP2A | X | -23.827 | 2 |
| 8 | MP2A | Z | 0 | 2 |
| 9 | MP2A | Mx | .012 | 2 |
| 10 | MP2A | X | -23.827 | 6 |
| 11 | MP2A | Z | 0 | 6 |
| 12 | MP2A | Mx | .012 | 6 |
| 13 | MP3A | X | -6.619 | 3 |
| 14 | MP3A | Z | 0 | 3 |
| 15 | MP3A | Mx | .003 | 3 |
| 16 | MP3A | X | -6.619 | 5 |
| 17 | MP3A | Z | 0 | 5 |
| 18 | MP3A | Mx | .003 | 5 |
| 19 | MP2A | X | -9.11 | 3 |
| 20 | MP2A | Z | 0 | 3 |
| 21 | MP2A | Mx | -.005 | 3 |
| 22 | MP1A | X | -7.596 | 3 |
| 23 | MP1A | Z | 0 | 3 |
| 24 | MP1A | Mx | -.004 | 3 |
| 25 | MP1A | X | -27.574 | 2 |
| 26 | MP1A | Z | 0 | 2 |
| 27 | MP1A | Mx | .014 | 2 |
| 28 | MP1A | X | -27.574 | 6 |
| 29 | MP1A | Z | 0 | 6 |
| 30 | MP1A | Mx | .014 | 6 |
| 31 | MP4A | X | -27.574 | 2 |
| 32 | MP4A | Z | 0 | 2 |
| 33 | MP4A | Mx | .014 | 2 |
| 34 | MP4A | X | -27.574 | 6 |
| 35 | MP4A | Z | 0 | 6 |
| 36 | MP4A | Mx | .014 | 6 |

Member Point Loads (BLC 25 : Antenna Wi (300 Deg))

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft. %] |
|---|--------------|-----------|--------------------|-----------------|
| 1 | MP2A | X | -22.295 | 2 |
| 2 | MP2A | Z | -12.872 | 2 |

Member Point Loads (BLC 25 : Antenna Wi (300 Deg)) (Continued)

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft.%] |
|----|--------------|-----------|--------------------|----------------|
| 3 | MP2A | Mx | .001 | 2 |
| 4 | MP2A | X | -22.295 | 6 |
| 5 | MP2A | Z | -12.872 | 6 |
| 6 | MP2A | Mx | .001 | 6 |
| 7 | MP2A | X | -22.295 | 2 |
| 8 | MP2A | Z | -12.872 | 2 |
| 9 | MP2A | Mx | .021 | 2 |
| 10 | MP2A | X | -22.295 | 6 |
| 11 | MP2A | Z | -12.872 | 6 |
| 12 | MP2A | Mx | .021 | 6 |
| 13 | MP3A | X | -7.664 | 3 |
| 14 | MP3A | Z | -4.425 | 3 |
| 15 | MP3A | Mx | .004 | 3 |
| 16 | MP3A | X | -7.664 | 5 |
| 17 | MP3A | Z | -4.425 | 5 |
| 18 | MP3A | Mx | .004 | 5 |
| 19 | MP2A | X | -8.753 | 3 |
| 20 | MP2A | Z | -5.053 | 3 |
| 21 | MP2A | Mx | -.004 | 3 |
| 22 | MP1A | X | -7.769 | 3 |
| 23 | MP1A | Z | -4.485 | 3 |
| 24 | MP1A | Mx | -.004 | 3 |
| 25 | MP1A | X | -24.546 | 2 |
| 26 | MP1A | Z | -14.172 | 2 |
| 27 | MP1A | Mx | .012 | 2 |
| 28 | MP1A | X | -24.546 | 6 |
| 29 | MP1A | Z | -14.172 | 6 |
| 30 | MP1A | Mx | .012 | 6 |
| 31 | MP4A | X | -24.546 | 2 |
| 32 | MP4A | Z | -14.172 | 2 |
| 33 | MP4A | Mx | .012 | 2 |
| 34 | MP4A | X | -24.546 | 6 |
| 35 | MP4A | Z | -14.172 | 6 |
| 36 | MP4A | Mx | .012 | 6 |

Member Point Loads (BLC 26 : Antenna Wi (330 Deg))

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft.%] |
|----|--------------|-----------|--------------------|----------------|
| 1 | MP2A | X | -14.789 | 2 |
| 2 | MP2A | Z | -25.615 | 2 |
| 3 | MP2A | Mx | -.012 | 2 |
| 4 | MP2A | X | -14.789 | 6 |
| 5 | MP2A | Z | -25.615 | 6 |
| 6 | MP2A | Mx | -.012 | 6 |
| 7 | MP2A | X | -14.789 | 2 |
| 8 | MP2A | Z | -25.615 | 2 |
| 9 | MP2A | Mx | .027 | 2 |
| 10 | MP2A | X | -14.789 | 6 |
| 11 | MP2A | Z | -25.615 | 6 |
| 12 | MP2A | Mx | .027 | 6 |
| 13 | MP3A | X | -6.654 | 3 |
| 14 | MP3A | Z | -11.525 | 3 |
| 15 | MP3A | Mx | .003 | 3 |
| 16 | MP3A | X | -6.654 | 5 |
| 17 | MP3A | Z | -11.525 | 5 |
| 18 | MP3A | Mx | .003 | 5 |
| 19 | MP2A | X | -6.05 | 3 |

Member Point Loads (BLC 26 : Antenna Wi (330 Deg)) (Continued)

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft.%] |
|----|--------------|-----------|--------------------|----------------|
| 20 | MP2A | Z | -10.479 | 3 |
| 21 | MP2A | Mx | -.003 | 3 |
| 22 | MP1A | X | -5.861 | 3 |
| 23 | MP1A | Z | -10.151 | 3 |
| 24 | MP1A | Mx | -.003 | 3 |
| 25 | MP1A | X | -14.941 | 2 |
| 26 | MP1A | Z | -25.878 | 2 |
| 27 | MP1A | Mx | .007 | 2 |
| 28 | MP1A | X | -14.941 | 6 |
| 29 | MP1A | Z | -25.878 | 6 |
| 30 | MP1A | Mx | .007 | 6 |
| 31 | MP4A | X | -14.941 | 2 |
| 32 | MP4A | Z | -25.878 | 2 |
| 33 | MP4A | Mx | .007 | 2 |
| 34 | MP4A | X | -14.941 | 6 |
| 35 | MP4A | Z | -25.878 | 6 |
| 36 | MP4A | Mx | .007 | 6 |

Member Point Loads (BLC 27 : Antenna Wm (0 Deg))

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft.%] |
|----|--------------|-----------|--------------------|----------------|
| 1 | MP2A | X | 0 | 2 |
| 2 | MP2A | Z | -10.397 | 2 |
| 3 | MP2A | Mx | -.008 | 2 |
| 4 | MP2A | X | 0 | 6 |
| 5 | MP2A | Z | -10.397 | 6 |
| 6 | MP2A | Mx | -.008 | 6 |
| 7 | MP2A | X | 0 | 2 |
| 8 | MP2A | Z | -10.397 | 2 |
| 9 | MP2A | Mx | .008 | 2 |
| 10 | MP2A | X | 0 | 6 |
| 11 | MP2A | Z | -10.397 | 6 |
| 12 | MP2A | Mx | .008 | 6 |
| 13 | MP3A | X | 0 | 3 |
| 14 | MP3A | Z | -4.951 | 3 |
| 15 | MP3A | Mx | 0 | 3 |
| 16 | MP3A | X | 0 | 5 |
| 17 | MP3A | Z | -4.951 | 5 |
| 18 | MP3A | Mx | 0 | 5 |
| 19 | MP2A | X | 0 | 3 |
| 20 | MP2A | Z | -3.265 | 3 |
| 21 | MP2A | Mx | 0 | 3 |
| 22 | MP1A | X | 0 | 3 |
| 23 | MP1A | Z | -3.265 | 3 |
| 24 | MP1A | Mx | 0 | 3 |
| 25 | MP1A | X | 0 | 2 |
| 26 | MP1A | Z | -10.112 | 2 |
| 27 | MP1A | Mx | 0 | 2 |
| 28 | MP1A | X | 0 | 6 |
| 29 | MP1A | Z | -10.112 | 6 |
| 30 | MP1A | Mx | 0 | 6 |
| 31 | MP4A | X | 0 | 2 |
| 32 | MP4A | Z | -10.112 | 2 |
| 33 | MP4A | Mx | 0 | 2 |
| 34 | MP4A | X | 0 | 6 |
| 35 | MP4A | Z | -10.112 | 6 |
| 36 | MP4A | Mx | 0 | 6 |



Company :
 Designer :
 Job Number :
 Model Name :

Apr 12, 2022
 10:37 AM
 Checked By: _____

Member Point Loads (BLC 28 : Antenna Wm (30 Deg))

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft. %] |
|----|--------------|-----------|--------------------|-----------------|
| 1 | MP2A | X | 4.865 | 2 |
| 2 | MP2A | Z | -8.426 | 2 |
| 3 | MP2A | Mx | -.009 | 2 |
| 4 | MP2A | X | 4.865 | 6 |
| 5 | MP2A | Z | -8.426 | 6 |
| 6 | MP2A | Mx | -.009 | 6 |
| 7 | MP2A | X | 4.865 | 2 |
| 8 | MP2A | Z | -8.426 | 2 |
| 9 | MP2A | Mx | .004 | 2 |
| 10 | MP2A | X | 4.865 | 6 |
| 11 | MP2A | Z | -8.426 | 6 |
| 12 | MP2A | Mx | .004 | 6 |
| 13 | MP3A | X | 2.099 | 3 |
| 14 | MP3A | Z | -3.635 | 3 |
| 15 | MP3A | Mx | -.001 | 3 |
| 16 | MP3A | X | 2.099 | 5 |
| 17 | MP3A | Z | -3.635 | 5 |
| 18 | MP3A | Mx | -.001 | 5 |
| 19 | MP2A | X | 1.498 | 3 |
| 20 | MP2A | Z | -2.595 | 3 |
| 21 | MP2A | Mx | .000749 | 3 |
| 22 | MP1A | X | 1.448 | 3 |
| 23 | MP1A | Z | -2.509 | 3 |
| 24 | MP1A | Mx | .000724 | 3 |
| 25 | MP1A | X | 4.921 | 2 |
| 26 | MP1A | Z | -8.524 | 2 |
| 27 | MP1A | Mx | -.002 | 2 |
| 28 | MP1A | X | 4.921 | 6 |
| 29 | MP1A | Z | -8.524 | 6 |
| 30 | MP1A | Mx | -.002 | 6 |
| 31 | MP4A | X | 4.921 | 2 |
| 32 | MP4A | Z | -8.524 | 2 |
| 33 | MP4A | Mx | -.002 | 2 |
| 34 | MP4A | X | 4.921 | 6 |
| 35 | MP4A | Z | -8.524 | 6 |
| 36 | MP4A | Mx | -.002 | 6 |

Member Point Loads (BLC 29 : Antenna Wm (60 Deg))

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft. %] |
|----|--------------|-----------|--------------------|-----------------|
| 1 | MP2A | X | 7.271 | 2 |
| 2 | MP2A | Z | -4.198 | 2 |
| 3 | MP2A | Mx | -.007 | 2 |
| 4 | MP2A | X | 7.271 | 6 |
| 5 | MP2A | Z | -4.198 | 6 |
| 6 | MP2A | Mx | -.007 | 6 |
| 7 | MP2A | X | 7.271 | 2 |
| 8 | MP2A | Z | -4.198 | 2 |
| 9 | MP2A | Mx | -.000487 | 2 |
| 10 | MP2A | X | 7.271 | 6 |
| 11 | MP2A | Z | -4.198 | 6 |
| 12 | MP2A | Mx | -.000487 | 6 |
| 13 | MP3A | X | 2.331 | 3 |
| 14 | MP3A | Z | -1.346 | 3 |
| 15 | MP3A | Mx | -.001 | 3 |
| 16 | MP3A | X | 2.331 | 5 |
| 17 | MP3A | Z | -1.346 | 5 |

Member Point Loads (BLC 29 : Antenna Wm (60 Deg)) (Continued)

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft. %] |
|----|--------------|-----------|--------------------|-----------------|
| 18 | MP3A | Mx | -.001 | 5 |
| 19 | MP2A | X | 2.13 | 3 |
| 20 | MP2A | Z | -1.23 | 3 |
| 21 | MP2A | Mx | .001 | 3 |
| 22 | MP1A | X | 1.87 | 3 |
| 23 | MP1A | Z | -1.08 | 3 |
| 24 | MP1A | Mx | .000935 | 3 |
| 25 | MP1A | X | 8.056 | 2 |
| 26 | MP1A | Z | -4.651 | 2 |
| 27 | MP1A | Mx | -.004 | 2 |
| 28 | MP1A | X | 8.056 | 6 |
| 29 | MP1A | Z | -4.651 | 6 |
| 30 | MP1A | Mx | -.004 | 6 |
| 31 | MP4A | X | 8.056 | 2 |
| 32 | MP4A | Z | -4.651 | 2 |
| 33 | MP4A | Mx | -.004 | 2 |
| 34 | MP4A | X | 8.056 | 6 |
| 35 | MP4A | Z | -4.651 | 6 |
| 36 | MP4A | Mx | -.004 | 6 |

Member Point Loads (BLC 30 : Antenna Wm (90 Deg))

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft. %] |
|----|--------------|-----------|--------------------|-----------------|
| 1 | MP2A | X | 7.729 | 2 |
| 2 | MP2A | Z | 0 | 2 |
| 3 | MP2A | Mx | -.004 | 2 |
| 4 | MP2A | X | 7.729 | 6 |
| 5 | MP2A | Z | 0 | 6 |
| 6 | MP2A | Mx | -.004 | 6 |
| 7 | MP2A | X | 7.729 | 2 |
| 8 | MP2A | Z | 0 | 2 |
| 9 | MP2A | Mx | -.004 | 2 |
| 10 | MP2A | X | 7.729 | 6 |
| 11 | MP2A | Z | 0 | 6 |
| 12 | MP2A | Mx | -.004 | 6 |
| 13 | MP3A | X | 1.938 | 3 |
| 14 | MP3A | Z | 0 | 3 |
| 15 | MP3A | Mx | -.000969 | 3 |
| 16 | MP3A | X | 1.938 | 5 |
| 17 | MP3A | Z | 0 | 5 |
| 18 | MP3A | Mx | -.000969 | 5 |
| 19 | MP2A | X | 2.191 | 3 |
| 20 | MP2A | Z | 0 | 3 |
| 21 | MP2A | Mx | .001 | 3 |
| 22 | MP1A | X | 1.791 | 3 |
| 23 | MP1A | Z | 0 | 3 |
| 24 | MP1A | Mx | .000895 | 3 |
| 25 | MP1A | X | 9.032 | 2 |
| 26 | MP1A | Z | 0 | 2 |
| 27 | MP1A | Mx | -.005 | 2 |
| 28 | MP1A | X | 9.032 | 6 |
| 29 | MP1A | Z | 0 | 6 |
| 30 | MP1A | Mx | -.005 | 6 |
| 31 | MP4A | X | 9.032 | 2 |
| 32 | MP4A | Z | 0 | 2 |
| 33 | MP4A | Mx | -.005 | 2 |
| 34 | MP4A | X | 9.032 | 6 |



Company :
 Designer :
 Job Number :
 Model Name :

Apr 12, 2022
 10:37 AM
 Checked By: _____

Member Point Loads (BLC 30 : Antenna Wm (90 Deg)) (Continued)

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft. %] |
|----|--------------|-----------|--------------------|-----------------|
| 35 | MP4A | Z | 0 | 6 |
| 36 | MP4A | Mx | -.005 | 6 |

Member Point Loads (BLC 31 : Antenna Wm (120 Deg))

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft. %] |
|----|--------------|-----------|--------------------|-----------------|
| 1 | MP2A | X | 7.271 | 2 |
| 2 | MP2A | Z | 4.198 | 2 |
| 3 | MP2A | Mx | -.000487 | 2 |
| 4 | MP2A | X | 7.271 | 6 |
| 5 | MP2A | Z | 4.198 | 6 |
| 6 | MP2A | Mx | -.000487 | 6 |
| 7 | MP2A | X | 7.271 | 2 |
| 8 | MP2A | Z | 4.198 | 2 |
| 9 | MP2A | Mx | -.007 | 2 |
| 10 | MP2A | X | 7.271 | 6 |
| 11 | MP2A | Z | 4.198 | 6 |
| 12 | MP2A | Mx | -.007 | 6 |
| 13 | MP3A | X | 2.331 | 3 |
| 14 | MP3A | Z | 1.346 | 3 |
| 15 | MP3A | Mx | -.001 | 3 |
| 16 | MP3A | X | 2.331 | 5 |
| 17 | MP3A | Z | 1.346 | 5 |
| 18 | MP3A | Mx | -.001 | 5 |
| 19 | MP2A | X | 2.13 | 3 |
| 20 | MP2A | Z | 1.23 | 3 |
| 21 | MP2A | Mx | .001 | 3 |
| 22 | MP1A | X | 1.87 | 3 |
| 23 | MP1A | Z | 1.08 | 3 |
| 24 | MP1A | Mx | .000935 | 3 |
| 25 | MP1A | X | 8.056 | 2 |
| 26 | MP1A | Z | 4.651 | 2 |
| 27 | MP1A | Mx | -.004 | 2 |
| 28 | MP1A | X | 8.056 | 6 |
| 29 | MP1A | Z | 4.651 | 6 |
| 30 | MP1A | Mx | -.004 | 6 |
| 31 | MP4A | X | 8.056 | 2 |
| 32 | MP4A | Z | 4.651 | 2 |
| 33 | MP4A | Mx | -.004 | 2 |
| 34 | MP4A | X | 8.056 | 6 |
| 35 | MP4A | Z | 4.651 | 6 |
| 36 | MP4A | Mx | -.004 | 6 |

Member Point Loads (BLC 32 : Antenna Wm (150 Deg))

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft. %] |
|----|--------------|-----------|--------------------|-----------------|
| 1 | MP2A | X | 4.865 | 2 |
| 2 | MP2A | Z | 8.426 | 2 |
| 3 | MP2A | Mx | .004 | 2 |
| 4 | MP2A | X | 4.865 | 6 |
| 5 | MP2A | Z | 8.426 | 6 |
| 6 | MP2A | Mx | .004 | 6 |
| 7 | MP2A | X | 4.865 | 2 |
| 8 | MP2A | Z | 8.426 | 2 |
| 9 | MP2A | Mx | -.009 | 2 |
| 10 | MP2A | X | 4.865 | 6 |
| 11 | MP2A | Z | 8.426 | 6 |
| 12 | MP2A | Mx | -.009 | 6 |



Company :
 Designer :
 Job Number :
 Model Name :

Apr 12, 2022
 10:37 AM
 Checked By: _____

Member Point Loads (BLC 32 : Antenna Wm (150 Deg)) (Continued)

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft. %] |
|----|--------------|-----------|--------------------|-----------------|
| 13 | MP3A | X | 2.099 | 3 |
| 14 | MP3A | Z | 3.635 | 3 |
| 15 | MP3A | Mx | -.001 | 3 |
| 16 | MP3A | X | 2.099 | 5 |
| 17 | MP3A | Z | 3.635 | 5 |
| 18 | MP3A | Mx | -.001 | 5 |
| 19 | MP2A | X | 1.498 | 3 |
| 20 | MP2A | Z | 2.595 | 3 |
| 21 | MP2A | Mx | .000749 | 3 |
| 22 | MP1A | X | 1.448 | 3 |
| 23 | MP1A | Z | 2.509 | 3 |
| 24 | MP1A | Mx | .000724 | 3 |
| 25 | MP1A | X | 4.921 | 2 |
| 26 | MP1A | Z | 8.524 | 2 |
| 27 | MP1A | Mx | -.002 | 2 |
| 28 | MP1A | X | 4.921 | 6 |
| 29 | MP1A | Z | 8.524 | 6 |
| 30 | MP1A | Mx | -.002 | 6 |
| 31 | MP4A | X | 4.921 | 2 |
| 32 | MP4A | Z | 8.524 | 2 |
| 33 | MP4A | Mx | -.002 | 2 |
| 34 | MP4A | X | 4.921 | 6 |
| 35 | MP4A | Z | 8.524 | 6 |
| 36 | MP4A | Mx | -.002 | 6 |

Member Point Loads (BLC 33 : Antenna Wm (180 Deg))

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft. %] |
|----|--------------|-----------|--------------------|-----------------|
| 1 | MP2A | X | 0 | 2 |
| 2 | MP2A | Z | 10.397 | 2 |
| 3 | MP2A | Mx | .008 | 2 |
| 4 | MP2A | X | 0 | 6 |
| 5 | MP2A | Z | 10.397 | 6 |
| 6 | MP2A | Mx | .008 | 6 |
| 7 | MP2A | X | 0 | 2 |
| 8 | MP2A | Z | 10.397 | 2 |
| 9 | MP2A | Mx | -.008 | 2 |
| 10 | MP2A | X | 0 | 6 |
| 11 | MP2A | Z | 10.397 | 6 |
| 12 | MP2A | Mx | -.008 | 6 |
| 13 | MP3A | X | 0 | 3 |
| 14 | MP3A | Z | 4.951 | 3 |
| 15 | MP3A | Mx | 0 | 3 |
| 16 | MP3A | X | 0 | 5 |
| 17 | MP3A | Z | 4.951 | 5 |
| 18 | MP3A | Mx | 0 | 5 |
| 19 | MP2A | X | 0 | 3 |
| 20 | MP2A | Z | 3.265 | 3 |
| 21 | MP2A | Mx | 0 | 3 |
| 22 | MP1A | X | 0 | 3 |
| 23 | MP1A | Z | 3.265 | 3 |
| 24 | MP1A | Mx | 0 | 3 |
| 25 | MP1A | X | 0 | 2 |
| 26 | MP1A | Z | 10.112 | 2 |
| 27 | MP1A | Mx | 0 | 2 |
| 28 | MP1A | X | 0 | 6 |
| 29 | MP1A | Z | 10.112 | 6 |

Member Point Loads (BLC 33 : Antenna Wm (180 Deg)) (Continued)

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft.%] |
|----|--------------|-----------|--------------------|----------------|
| 30 | MP1A | Mx | 0 | 6 |
| 31 | MP4A | X | 0 | 2 |
| 32 | MP4A | Z | 10.112 | 2 |
| 33 | MP4A | Mx | 0 | 2 |
| 34 | MP4A | X | 0 | 6 |
| 35 | MP4A | Z | 10.112 | 6 |
| 36 | MP4A | Mx | 0 | 6 |

Member Point Loads (BLC 34 : Antenna Wm (210 Deg))

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft.%] |
|----|--------------|-----------|--------------------|----------------|
| 1 | MP2A | X | -4.865 | 2 |
| 2 | MP2A | Z | 8.426 | 2 |
| 3 | MP2A | Mx | .009 | 2 |
| 4 | MP2A | X | -4.865 | 6 |
| 5 | MP2A | Z | 8.426 | 6 |
| 6 | MP2A | Mx | .009 | 6 |
| 7 | MP2A | X | -4.865 | 2 |
| 8 | MP2A | Z | 8.426 | 2 |
| 9 | MP2A | Mx | -.004 | 2 |
| 10 | MP2A | X | -4.865 | 6 |
| 11 | MP2A | Z | 8.426 | 6 |
| 12 | MP2A | Mx | -.004 | 6 |
| 13 | MP3A | X | -2.099 | 3 |
| 14 | MP3A | Z | 3.635 | 3 |
| 15 | MP3A | Mx | .001 | 3 |
| 16 | MP3A | X | -2.099 | 5 |
| 17 | MP3A | Z | 3.635 | 5 |
| 18 | MP3A | Mx | .001 | 5 |
| 19 | MP2A | X | -1.498 | 3 |
| 20 | MP2A | Z | 2.595 | 3 |
| 21 | MP2A | Mx | -.000749 | 3 |
| 22 | MP1A | X | -1.448 | 3 |
| 23 | MP1A | Z | 2.509 | 3 |
| 24 | MP1A | Mx | -.000724 | 3 |
| 25 | MP1A | X | -4.921 | 2 |
| 26 | MP1A | Z | 8.524 | 2 |
| 27 | MP1A | Mx | .002 | 2 |
| 28 | MP1A | X | -4.921 | 6 |
| 29 | MP1A | Z | 8.524 | 6 |
| 30 | MP1A | Mx | .002 | 6 |
| 31 | MP4A | X | -4.921 | 2 |
| 32 | MP4A | Z | 8.524 | 2 |
| 33 | MP4A | Mx | .002 | 2 |
| 34 | MP4A | X | -4.921 | 6 |
| 35 | MP4A | Z | 8.524 | 6 |
| 36 | MP4A | Mx | .002 | 6 |

Member Point Loads (BLC 35 : Antenna Wm (240 Deg))

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft.%] |
|---|--------------|-----------|--------------------|----------------|
| 1 | MP2A | X | -7.271 | 2 |
| 2 | MP2A | Z | 4.198 | 2 |
| 3 | MP2A | Mx | .007 | 2 |
| 4 | MP2A | X | -7.271 | 6 |
| 5 | MP2A | Z | 4.198 | 6 |
| 6 | MP2A | Mx | .007 | 6 |
| 7 | MP2A | X | -7.271 | 2 |

Member Point Loads (BLC 35 : Antenna Wm (240 Deg)) (Continued)

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft.%] |
|----|--------------|-----------|--------------------|----------------|
| 8 | MP2A | Z | 4.198 | 2 |
| 9 | MP2A | Mx | .000487 | 2 |
| 10 | MP2A | X | -7.271 | 6 |
| 11 | MP2A | Z | 4.198 | 6 |
| 12 | MP2A | Mx | .000487 | 6 |
| 13 | MP3A | X | -2.331 | 3 |
| 14 | MP3A | Z | 1.346 | 3 |
| 15 | MP3A | Mx | .001 | 3 |
| 16 | MP3A | X | -2.331 | 5 |
| 17 | MP3A | Z | 1.346 | 5 |
| 18 | MP3A | Mx | .001 | 5 |
| 19 | MP2A | X | -2.13 | 3 |
| 20 | MP2A | Z | 1.23 | 3 |
| 21 | MP2A | Mx | -.001 | 3 |
| 22 | MP1A | X | -1.87 | 3 |
| 23 | MP1A | Z | 1.08 | 3 |
| 24 | MP1A | Mx | -.000935 | 3 |
| 25 | MP1A | X | -8.056 | 2 |
| 26 | MP1A | Z | 4.651 | 2 |
| 27 | MP1A | Mx | .004 | 2 |
| 28 | MP1A | X | -8.056 | 6 |
| 29 | MP1A | Z | 4.651 | 6 |
| 30 | MP1A | Mx | .004 | 6 |
| 31 | MP4A | X | -8.056 | 2 |
| 32 | MP4A | Z | 4.651 | 2 |
| 33 | MP4A | Mx | .004 | 2 |
| 34 | MP4A | X | -8.056 | 6 |
| 35 | MP4A | Z | 4.651 | 6 |
| 36 | MP4A | Mx | .004 | 6 |

Member Point Loads (BLC 36 : Antenna Wm (270 Deg))

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft.%] |
|----|--------------|-----------|--------------------|----------------|
| 1 | MP2A | X | -7.729 | 2 |
| 2 | MP2A | Z | 0 | 2 |
| 3 | MP2A | Mx | .004 | 2 |
| 4 | MP2A | X | -7.729 | 6 |
| 5 | MP2A | Z | 0 | 6 |
| 6 | MP2A | Mx | .004 | 6 |
| 7 | MP2A | X | -7.729 | 2 |
| 8 | MP2A | Z | 0 | 2 |
| 9 | MP2A | Mx | .004 | 2 |
| 10 | MP2A | X | -7.729 | 6 |
| 11 | MP2A | Z | 0 | 6 |
| 12 | MP2A | Mx | .004 | 6 |
| 13 | MP3A | X | -1.938 | 3 |
| 14 | MP3A | Z | 0 | 3 |
| 15 | MP3A | Mx | .000969 | 3 |
| 16 | MP3A | X | -1.938 | 5 |
| 17 | MP3A | Z | 0 | 5 |
| 18 | MP3A | Mx | .000969 | 5 |
| 19 | MP2A | X | -2.191 | 3 |
| 20 | MP2A | Z | 0 | 3 |
| 21 | MP2A | Mx | -.001 | 3 |
| 22 | MP1A | X | -1.791 | 3 |
| 23 | MP1A | Z | 0 | 3 |
| 24 | MP1A | Mx | -.000895 | 3 |

Member Point Loads (BLC 36 : Antenna Wm (270 Deg)) (Continued)

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft.%] |
|----|--------------|-----------|--------------------|----------------|
| 25 | MP1A | X | -9.032 | 2 |
| 26 | MP1A | Z | 0 | 2 |
| 27 | MP1A | Mx | .005 | 2 |
| 28 | MP1A | X | -9.032 | 6 |
| 29 | MP1A | Z | 0 | 6 |
| 30 | MP1A | Mx | .005 | 6 |
| 31 | MP4A | X | -9.032 | 2 |
| 32 | MP4A | Z | 0 | 2 |
| 33 | MP4A | Mx | .005 | 2 |
| 34 | MP4A | X | -9.032 | 6 |
| 35 | MP4A | Z | 0 | 6 |
| 36 | MP4A | Mx | .005 | 6 |

Member Point Loads (BLC 37 : Antenna Wm (300 Deg))

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft.%] |
|----|--------------|-----------|--------------------|----------------|
| 1 | MP2A | X | -7.271 | 2 |
| 2 | MP2A | Z | -4.198 | 2 |
| 3 | MP2A | Mx | .000487 | 2 |
| 4 | MP2A | X | -7.271 | 6 |
| 5 | MP2A | Z | -4.198 | 6 |
| 6 | MP2A | Mx | .000487 | 6 |
| 7 | MP2A | X | -7.271 | 2 |
| 8 | MP2A | Z | -4.198 | 2 |
| 9 | MP2A | Mx | .007 | 2 |
| 10 | MP2A | X | -7.271 | 6 |
| 11 | MP2A | Z | -4.198 | 6 |
| 12 | MP2A | Mx | .007 | 6 |
| 13 | MP3A | X | -2.331 | 3 |
| 14 | MP3A | Z | -1.346 | 3 |
| 15 | MP3A | Mx | .001 | 3 |
| 16 | MP3A | X | -2.331 | 5 |
| 17 | MP3A | Z | -1.346 | 5 |
| 18 | MP3A | Mx | .001 | 5 |
| 19 | MP2A | X | -2.13 | 3 |
| 20 | MP2A | Z | -1.23 | 3 |
| 21 | MP2A | Mx | -.001 | 3 |
| 22 | MP1A | X | -1.87 | 3 |
| 23 | MP1A | Z | -1.08 | 3 |
| 24 | MP1A | Mx | -.000935 | 3 |
| 25 | MP1A | X | -8.056 | 2 |
| 26 | MP1A | Z | -4.651 | 2 |
| 27 | MP1A | Mx | .004 | 2 |
| 28 | MP1A | X | -8.056 | 6 |
| 29 | MP1A | Z | -4.651 | 6 |
| 30 | MP1A | Mx | .004 | 6 |
| 31 | MP4A | X | -8.056 | 2 |
| 32 | MP4A | Z | -4.651 | 2 |
| 33 | MP4A | Mx | .004 | 2 |
| 34 | MP4A | X | -8.056 | 6 |
| 35 | MP4A | Z | -4.651 | 6 |
| 36 | MP4A | Mx | .004 | 6 |

Member Point Loads (BLC 38 : Antenna Wm (330 Deg))

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft.%] |
|---|--------------|-----------|--------------------|----------------|
| 1 | MP2A | X | -4.865 | 2 |
| 2 | MP2A | Z | -8.426 | 2 |

Member Point Loads (BLC 38 : Antenna Wm (330 Deg)) (Continued)

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft.%] |
|----|--------------|-----------|--------------------|----------------|
| 3 | MP2A | Mx | -.004 | 2 |
| 4 | MP2A | X | -4.865 | 6 |
| 5 | MP2A | Z | -8.426 | 6 |
| 6 | MP2A | Mx | -.004 | 6 |
| 7 | MP2A | X | -4.865 | 2 |
| 8 | MP2A | Z | -8.426 | 2 |
| 9 | MP2A | Mx | .009 | 2 |
| 10 | MP2A | X | -4.865 | 6 |
| 11 | MP2A | Z | -8.426 | 6 |
| 12 | MP2A | Mx | .009 | 6 |
| 13 | MP3A | X | -2.099 | 3 |
| 14 | MP3A | Z | -3.635 | 3 |
| 15 | MP3A | Mx | .001 | 3 |
| 16 | MP3A | X | -2.099 | 5 |
| 17 | MP3A | Z | -3.635 | 5 |
| 18 | MP3A | Mx | .001 | 5 |
| 19 | MP2A | X | -1.498 | 3 |
| 20 | MP2A | Z | -2.595 | 3 |
| 21 | MP2A | Mx | -.000749 | 3 |
| 22 | MP1A | X | -1.448 | 3 |
| 23 | MP1A | Z | -2.509 | 3 |
| 24 | MP1A | Mx | -.000724 | 3 |
| 25 | MP1A | X | -4.921 | 2 |
| 26 | MP1A | Z | -8.524 | 2 |
| 27 | MP1A | Mx | .002 | 2 |
| 28 | MP1A | X | -4.921 | 6 |
| 29 | MP1A | Z | -8.524 | 6 |
| 30 | MP1A | Mx | .002 | 6 |
| 31 | MP4A | X | -4.921 | 2 |
| 32 | MP4A | Z | -8.524 | 2 |
| 33 | MP4A | Mx | .002 | 2 |
| 34 | MP4A | X | -4.921 | 6 |
| 35 | MP4A | Z | -8.524 | 6 |
| 36 | MP4A | Mx | .002 | 6 |

Member Point Loads (BLC 77 : Lm1)

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft.%] |
|---|--------------|-----------|--------------------|----------------|
| 1 | LIVE1 | Y | -500 | 0 |

Member Point Loads (BLC 78 : Lm2)

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft.%] |
|---|--------------|-----------|--------------------|----------------|
| 1 | LIVE2 | Y | -500 | 0 |

Member Point Loads (BLC 79 : Lv1)

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft.%] |
|---|--------------|-----------|--------------------|----------------|
| 1 | FACE | Y | -250 | 0 |

Member Point Loads (BLC 80 : Lv2)

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft.%] |
|---|--------------|-----------|--------------------|----------------|
| 1 | FACE | Y | -250 | %50 |

Member Point Loads (BLC 81 : Antenna Ev)

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft.%] |
|---|--------------|-----------|--------------------|----------------|
| 1 | MP2A | Y | -.981 | 2 |

Member Point Loads (BLC 81 : Antenna Ev) (Continued)

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft.%] |
|----|--------------|-----------|--------------------|----------------|
| 2 | MP2A | My | -.000491 | 2 |
| 3 | MP2A | Mz | .000736 | 2 |
| 4 | MP2A | Y | -.981 | 6 |
| 5 | MP2A | My | -.000491 | 6 |
| 6 | MP2A | Mz | .000736 | 6 |
| 7 | MP2A | Y | -.981 | 2 |
| 8 | MP2A | My | -.000491 | 2 |
| 9 | MP2A | Mz | -.000736 | 2 |
| 10 | MP2A | Y | -.981 | 6 |
| 11 | MP2A | My | -.000491 | 6 |
| 12 | MP2A | Mz | -.000736 | 6 |
| 13 | MP3A | Y | -1.858 | 3 |
| 14 | MP3A | My | -.000929 | 3 |
| 15 | MP3A | Mz | 0 | 3 |
| 16 | MP3A | Y | -1.858 | 5 |
| 17 | MP3A | My | -.000929 | 5 |
| 18 | MP3A | Mz | 0 | 5 |
| 19 | MP2A | Y | -3.601 | 3 |
| 20 | MP2A | My | .002 | 3 |
| 21 | MP2A | Mz | 0 | 3 |
| 22 | MP1A | Y | -2.999 | 3 |
| 23 | MP1A | My | .002 | 3 |
| 24 | MP1A | Mz | 0 | 3 |
| 25 | MP1A | Y | -.576 | 2 |
| 26 | MP1A | My | -.000288 | 2 |
| 27 | MP1A | Mz | 0 | 2 |
| 28 | MP1A | Y | -.576 | 6 |
| 29 | MP1A | My | -.000288 | 6 |
| 30 | MP1A | Mz | 0 | 6 |
| 31 | MP4A | Y | -.576 | 2 |
| 32 | MP4A | My | -.000288 | 2 |
| 33 | MP4A | Mz | 0 | 2 |
| 34 | MP4A | Y | -.576 | 6 |
| 35 | MP4A | My | -.000288 | 6 |
| 36 | MP4A | Mz | 0 | 6 |

Member Point Loads (BLC 82 : Antenna Eh (0 Deg))

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft.%] |
|----|--------------|-----------|--------------------|----------------|
| 1 | MP2A | Z | -2.453 | 2 |
| 2 | MP2A | Mx | -.002 | 2 |
| 3 | MP2A | Z | -2.453 | 6 |
| 4 | MP2A | Mx | -.002 | 6 |
| 5 | MP2A | Z | -2.453 | 2 |
| 6 | MP2A | Mx | .002 | 2 |
| 7 | MP2A | Z | -2.453 | 6 |
| 8 | MP2A | Mx | .002 | 6 |
| 9 | MP3A | Z | -4.645 | 3 |
| 10 | MP3A | Mx | 0 | 3 |
| 11 | MP3A | Z | -4.645 | 5 |
| 12 | MP3A | Mx | 0 | 5 |
| 13 | MP2A | Z | -9.003 | 3 |
| 14 | MP2A | Mx | 0 | 3 |
| 15 | MP1A | Z | -7.499 | 3 |
| 16 | MP1A | Mx | 0 | 3 |
| 17 | MP1A | Z | -1.44 | 2 |
| 18 | MP1A | Mx | 0 | 2 |

Member Point Loads (BLC 82 : Antenna Eh (0 Deg)) (Continued)

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft. %] |
|----|--------------|-----------|--------------------|-----------------|
| 19 | MP1A | Z | -1.44 | 6 |
| 20 | MP1A | Mx | 0 | 6 |
| 21 | MP4A | Z | -1.44 | 2 |
| 22 | MP4A | Mx | 0 | 2 |
| 23 | MP4A | Z | -1.44 | 6 |
| 24 | MP4A | Mx | 0 | 6 |

Member Point Loads (BLC 83 : Antenna Eh (90 Deg))

| | Member Label | Direction | Magnitude[lb.k-ft] | Location[ft. %] |
|----|--------------|-----------|--------------------|-----------------|
| 1 | MP2A | X | 2.453 | 2 |
| 2 | MP2A | Mx | -.001 | 2 |
| 3 | MP2A | X | 2.453 | 6 |
| 4 | MP2A | Mx | -.001 | 6 |
| 5 | MP2A | X | 2.453 | 2 |
| 6 | MP2A | Mx | -.001 | 2 |
| 7 | MP2A | X | 2.453 | 6 |
| 8 | MP2A | Mx | -.001 | 6 |
| 9 | MP3A | X | 4.645 | 3 |
| 10 | MP3A | Mx | -.002 | 3 |
| 11 | MP3A | X | 4.645 | 5 |
| 12 | MP3A | Mx | -.002 | 5 |
| 13 | MP2A | X | 9.003 | 3 |
| 14 | MP2A | Mx | .005 | 3 |
| 15 | MP1A | X | 7.499 | 3 |
| 16 | MP1A | Mx | .004 | 3 |
| 17 | MP1A | X | 1.44 | 2 |
| 18 | MP1A | Mx | -.00072 | 2 |
| 19 | MP1A | X | 1.44 | 6 |
| 20 | MP1A | Mx | -.00072 | 6 |
| 21 | MP4A | X | 1.44 | 2 |
| 22 | MP4A | Mx | -.00072 | 2 |
| 23 | MP4A | X | 1.44 | 6 |
| 24 | MP4A | Mx | -.00072 | 6 |

Member Distributed Loads (BLC 40 : Structure Di)

| | Member Label | Direction | Start Magnitude[...] | End Magnitude[lb/ft.F.ksf] | Start Location[ft. %] | End Location[ft. %] |
|----|--------------|-----------|----------------------|----------------------------|-----------------------|---------------------|
| 1 | FACE | Y | -5.69 | -5.69 | 0 | %100 |
| 2 | M2 | Y | -5.69 | -5.69 | 0 | %100 |
| 3 | M13 | Y | -6.65 | -6.65 | 0 | %100 |
| 4 | M14 | Y | -6.65 | -6.65 | 0 | %100 |
| 5 | M15 | Y | -6.65 | -6.65 | 0 | %100 |
| 6 | M16 | Y | -6.65 | -6.65 | 0 | %100 |
| 7 | M17 | Y | -4.984 | -4.984 | 0 | %100 |
| 8 | M18 | Y | -4.984 | -4.984 | 0 | %100 |
| 9 | M19 | Y | -4.984 | -4.984 | 0 | %100 |
| 10 | M20 | Y | -4.984 | -4.984 | 0 | %100 |
| 11 | M21 | Y | -6.65 | -6.65 | 0 | %100 |
| 12 | M22 | Y | -6.65 | -6.65 | 0 | %100 |
| 13 | M23 | Y | -6.65 | -6.65 | 0 | %100 |
| 14 | M24 | Y | -6.65 | -6.65 | 0 | %100 |
| 15 | M25 | Y | -2.69 | -2.69 | 0 | %100 |
| 16 | M26 | Y | -2.69 | -2.69 | 0 | %100 |
| 17 | M27 | Y | -2.69 | -2.69 | 0 | %100 |
| 18 | M28 | Y | -2.69 | -2.69 | 0 | %100 |
| 19 | MP4A | Y | -4.984 | -4.984 | 0 | %100 |



Company :
 Designer :
 Job Number :
 Model Name :

Apr 12, 2022
 10:37 AM
 Checked By: _____

Member Distributed Loads (BLC 40 : Structure Di) (Continued)

| | Member Label | Direction | Start Magnitude[...] | End Magnitude[lb/ft,F,ksf] | Start Location[ft, %] | End Location[ft, %] |
|----|--------------|-----------|----------------------|----------------------------|-----------------------|---------------------|
| 20 | MP3A | Y | -4.984 | -4.984 | 0 | %100 |
| 21 | MP2A | Y | -4.984 | -4.984 | 0 | %100 |
| 22 | MP1A | Y | -4.984 | -4.984 | 0 | %100 |
| 23 | M44 | Y | -2.513 | -2.513 | 0 | %100 |
| 24 | M45 | Y | -2.513 | -2.513 | 0 | %100 |
| 25 | M46 | Y | -2.513 | -2.513 | 0 | %100 |
| 26 | M47 | Y | -2.513 | -2.513 | 0 | %100 |
| 27 | M43 | Y | -4.984 | -4.984 | 0 | %100 |
| 28 | M44A | Y | -4.984 | -4.984 | 0 | %100 |

Member Distributed Loads (BLC 41 : Structure Wo (0 Deg))

| | Member Label | Direction | Start Magnitude[...] | End Magnitude[lb/ft,F,ksf] | Start Location[ft, %] | End Location[ft, %] |
|----|--------------|-----------|----------------------|----------------------------|-----------------------|---------------------|
| 1 | FACE | X | 0 | 0 | 0 | %100 |
| 2 | FACE | Z | -9.371 | -9.371 | 0 | %100 |
| 3 | M2 | X | 0 | 0 | 0 | %100 |
| 4 | M2 | Z | -9.371 | -9.371 | 0 | %100 |
| 5 | M13 | X | 0 | 0 | 0 | %100 |
| 6 | M13 | Z | 0 | 0 | 0 | %100 |
| 7 | M14 | X | 0 | 0 | 0 | %100 |
| 8 | M14 | Z | 0 | 0 | 0 | %100 |
| 9 | M15 | X | 0 | 0 | 0 | %100 |
| 10 | M15 | Z | 0 | 0 | 0 | %100 |
| 11 | M16 | X | 0 | 0 | 0 | %100 |
| 12 | M16 | Z | 0 | 0 | 0 | %100 |
| 13 | M17 | X | 0 | 0 | 0 | %100 |
| 14 | M17 | Z | -3.7 | -3.7 | 0 | %100 |
| 15 | M18 | X | 0 | 0 | 0 | %100 |
| 16 | M18 | Z | -3.7 | -3.7 | 0 | %100 |
| 17 | M19 | X | 0 | 0 | 0 | %100 |
| 18 | M19 | Z | -3.7 | -3.7 | 0 | %100 |
| 19 | M20 | X | 0 | 0 | 0 | %100 |
| 20 | M20 | Z | -3.7 | -3.7 | 0 | %100 |
| 21 | M21 | X | 0 | 0 | 0 | %100 |
| 22 | M21 | Z | -2.037 | -2.037 | 0 | %100 |
| 23 | M22 | X | 0 | 0 | 0 | %100 |
| 24 | M22 | Z | -2.037 | -2.037 | 0 | %100 |
| 25 | M23 | X | 0 | 0 | 0 | %100 |
| 26 | M23 | Z | -2.037 | -2.037 | 0 | %100 |
| 27 | M24 | X | 0 | 0 | 0 | %100 |
| 28 | M24 | Z | -2.037 | -2.037 | 0 | %100 |
| 29 | M25 | X | 0 | 0 | 0 | %100 |
| 30 | M25 | Z | -2.11 | -2.11 | 0 | %100 |
| 31 | M26 | X | 0 | 0 | 0 | %100 |
| 32 | M26 | Z | -2.11 | -2.11 | 0 | %100 |
| 33 | M27 | X | 0 | 0 | 0 | %100 |
| 34 | M27 | Z | -2.11 | -2.11 | 0 | %100 |
| 35 | M28 | X | 0 | 0 | 0 | %100 |
| 36 | M28 | Z | -2.11 | -2.11 | 0 | %100 |
| 37 | MP4A | X | 0 | 0 | 0 | %100 |
| 38 | MP4A | Z | -7.741 | -7.741 | 0 | %100 |
| 39 | MP3A | X | 0 | 0 | 0 | %100 |
| 40 | MP3A | Z | -7.741 | -7.741 | 0 | %100 |
| 41 | MP2A | X | 0 | 0 | 0 | %100 |
| 42 | MP2A | Z | -7.741 | -7.741 | 0 | %100 |
| 43 | MP1A | X | 0 | 0 | 0 | %100 |
| 44 | MP1A | Z | -7.741 | -7.741 | 0 | %100 |

Member Distributed Loads (BLC 41 : Structure Wo (0 Deg)) (Continued)

| | Member Label | Direction | Start Magnitude[...] | End Magnitude[lb/ft,F,ksf] | Start Location[ft,%] | End Location[ft,%] |
|----|--------------|-----------|----------------------|----------------------------|----------------------|--------------------|
| 45 | M44 | X | 0 | 0 | 0 | %100 |
| 46 | M44 | Z | -2.037 | -2.037 | 0 | %100 |
| 47 | M45 | X | 0 | 0 | 0 | %100 |
| 48 | M45 | Z | -2.037 | -2.037 | 0 | %100 |
| 49 | M46 | X | 0 | 0 | 0 | %100 |
| 50 | M46 | Z | -2.037 | -2.037 | 0 | %100 |
| 51 | M47 | X | 0 | 0 | 0 | %100 |
| 52 | M47 | Z | -2.037 | -2.037 | 0 | %100 |
| 53 | M43 | X | 0 | 0 | 0 | %100 |
| 54 | M43 | Z | -.513 | -.513 | 0 | %100 |
| 55 | M44A | X | 0 | 0 | 0 | %100 |
| 56 | M44A | Z | -.513 | -.513 | 0 | %100 |

Member Distributed Loads (BLC 42 : Structure Wo (30 Deg))

| | Member Label | Direction | Start Magnitude[...] | End Magnitude[lb/ft,F,ksf] | Start Location[ft,%] | End Location[ft,%] |
|----|--------------|-----------|----------------------|----------------------------|----------------------|--------------------|
| 1 | FACE | X | 3.514 | 3.514 | 0 | %100 |
| 2 | FACE | Z | -6.086 | -6.086 | 0 | %100 |
| 3 | M2 | X | 3.514 | 3.514 | 0 | %100 |
| 4 | M2 | Z | -6.086 | -6.086 | 0 | %100 |
| 5 | M13 | X | .255 | .255 | 0 | %100 |
| 6 | M13 | Z | -.441 | -.441 | 0 | %100 |
| 7 | M14 | X | .255 | .255 | 0 | %100 |
| 8 | M14 | Z | -.441 | -.441 | 0 | %100 |
| 9 | M15 | X | .255 | .255 | 0 | %100 |
| 10 | M15 | Z | -.441 | -.441 | 0 | %100 |
| 11 | M16 | X | .255 | .255 | 0 | %100 |
| 12 | M16 | Z | -.441 | -.441 | 0 | %100 |
| 13 | M17 | X | .416 | .416 | 0 | %100 |
| 14 | M17 | Z | -.721 | -.721 | 0 | %100 |
| 15 | M18 | X | .416 | .416 | 0 | %100 |
| 16 | M18 | Z | -.721 | -.721 | 0 | %100 |
| 17 | M19 | X | 2.925 | 2.925 | 0 | %100 |
| 18 | M19 | Z | -5.067 | -5.067 | 0 | %100 |
| 19 | M20 | X | 2.925 | 2.925 | 0 | %100 |
| 20 | M20 | Z | -5.067 | -5.067 | 0 | %100 |
| 21 | M21 | X | .764 | .764 | 0 | %100 |
| 22 | M21 | Z | -1.323 | -1.323 | 0 | %100 |
| 23 | M22 | X | .764 | .764 | 0 | %100 |
| 24 | M22 | Z | -1.323 | -1.323 | 0 | %100 |
| 25 | M23 | X | .764 | .764 | 0 | %100 |
| 26 | M23 | Z | -1.323 | -1.323 | 0 | %100 |
| 27 | M24 | X | .764 | .764 | 0 | %100 |
| 28 | M24 | Z | -1.323 | -1.323 | 0 | %100 |
| 29 | M25 | X | .844 | .844 | 0 | %100 |
| 30 | M25 | Z | -1.461 | -1.461 | 0 | %100 |
| 31 | M26 | X | .844 | .844 | 0 | %100 |
| 32 | M26 | Z | -1.461 | -1.461 | 0 | %100 |
| 33 | M27 | X | 1.214 | 1.214 | 0 | %100 |
| 34 | M27 | Z | -2.102 | -2.102 | 0 | %100 |
| 35 | M28 | X | 1.214 | 1.214 | 0 | %100 |
| 36 | M28 | Z | -2.102 | -2.102 | 0 | %100 |
| 37 | MP4A | X | 3.87 | 3.87 | 0 | %100 |
| 38 | MP4A | Z | -6.704 | -6.704 | 0 | %100 |
| 39 | MP3A | X | 3.87 | 3.87 | 0 | %100 |
| 40 | MP3A | Z | -6.704 | -6.704 | 0 | %100 |
| 41 | MP2A | X | 3.87 | 3.87 | 0 | %100 |

Member Distributed Loads (BLC 42 : Structure Wo (30 Deg)) (Continued)

| | Member Label | Direction | Start Magnitude[...] | End Magnitude[lb/ft,F,ksf] | Start Location[ft,%] | End Location[ft,%] |
|----|--------------|-----------|----------------------|----------------------------|----------------------|--------------------|
| 42 | MP2A | Z | -6.704 | -6.704 | 0 | %100 |
| 43 | MP1A | X | 3.87 | 3.87 | 0 | %100 |
| 44 | MP1A | Z | -6.704 | -6.704 | 0 | %100 |
| 45 | M44 | X | 1.019 | 1.019 | 0 | %100 |
| 46 | M44 | Z | -1.764 | -1.764 | 0 | %100 |
| 47 | M45 | X | 1.019 | 1.019 | 0 | %100 |
| 48 | M45 | Z | -1.764 | -1.764 | 0 | %100 |
| 49 | M46 | X | 1.019 | 1.019 | 0 | %100 |
| 50 | M46 | Z | -1.764 | -1.764 | 0 | %100 |
| 51 | M47 | X | 1.019 | 1.019 | 0 | %100 |
| 52 | M47 | Z | -1.764 | -1.764 | 0 | %100 |
| 53 | M43 | X | 1.93 | 1.93 | 0 | %100 |
| 54 | M43 | Z | -3.343 | -3.343 | 0 | %100 |
| 55 | M44A | X | .262 | .262 | 0 | %100 |
| 56 | M44A | Z | -.453 | -.453 | 0 | %100 |

Member Distributed Loads (BLC 43 : Structure Wo (60 Deg))

| | Member Label | Direction | Start Magnitude[...] | End Magnitude[lb/ft,F,ksf] | Start Location[ft,%] | End Location[ft,%] |
|----|--------------|-----------|----------------------|----------------------------|----------------------|--------------------|
| 1 | FACE | X | 2.029 | 2.029 | 0 | %100 |
| 2 | FACE | Z | -1.171 | -1.171 | 0 | %100 |
| 3 | M2 | X | 2.029 | 2.029 | 0 | %100 |
| 4 | M2 | Z | -1.171 | -1.171 | 0 | %100 |
| 5 | M13 | X | 1.323 | 1.323 | 0 | %100 |
| 6 | M13 | Z | -.764 | -.764 | 0 | %100 |
| 7 | M14 | X | 1.323 | 1.323 | 0 | %100 |
| 8 | M14 | Z | -.764 | -.764 | 0 | %100 |
| 9 | M15 | X | 1.323 | 1.323 | 0 | %100 |
| 10 | M15 | Z | -.764 | -.764 | 0 | %100 |
| 11 | M16 | X | 1.323 | 1.323 | 0 | %100 |
| 12 | M16 | Z | -.764 | -.764 | 0 | %100 |
| 13 | M17 | X | .102 | .102 | 0 | %100 |
| 14 | M17 | Z | -.059 | -.059 | 0 | %100 |
| 15 | M18 | X | .102 | .102 | 0 | %100 |
| 16 | M18 | Z | -.059 | -.059 | 0 | %100 |
| 17 | M19 | X | 4.447 | 4.447 | 0 | %100 |
| 18 | M19 | Z | -2.568 | -2.568 | 0 | %100 |
| 19 | M20 | X | 4.447 | 4.447 | 0 | %100 |
| 20 | M20 | Z | -2.568 | -2.568 | 0 | %100 |
| 21 | M21 | X | .441 | .441 | 0 | %100 |
| 22 | M21 | Z | -.255 | -.255 | 0 | %100 |
| 23 | M22 | X | .441 | .441 | 0 | %100 |
| 24 | M22 | Z | -.255 | -.255 | 0 | %100 |
| 25 | M23 | X | .441 | .441 | 0 | %100 |
| 26 | M23 | Z | -.255 | -.255 | 0 | %100 |
| 27 | M24 | X | .441 | .441 | 0 | %100 |
| 28 | M24 | Z | -.255 | -.255 | 0 | %100 |
| 29 | M25 | X | 1.37 | 1.37 | 0 | %100 |
| 30 | M25 | Z | -.791 | -.791 | 0 | %100 |
| 31 | M26 | X | 1.37 | 1.37 | 0 | %100 |
| 32 | M26 | Z | -.791 | -.791 | 0 | %100 |
| 33 | M27 | X | 2.011 | 2.011 | 0 | %100 |
| 34 | M27 | Z | -1.161 | -1.161 | 0 | %100 |
| 35 | M28 | X | 2.011 | 2.011 | 0 | %100 |
| 36 | M28 | Z | -1.161 | -1.161 | 0 | %100 |
| 37 | MP4A | X | 6.704 | 6.704 | 0 | %100 |
| 38 | MP4A | Z | -3.87 | -3.87 | 0 | %100 |

Member Distributed Loads (BLC 43 : Structure Wo (60 Deg)) (Continued)

| | Member Label | Direction | Start Magnitude[...] | End Magnitude[lb/ft,F,ksf] | Start Location[ft, %] | End Location[ft, %] |
|----|--------------|-----------|----------------------|----------------------------|-----------------------|---------------------|
| 39 | MP3A | X | 6.704 | 6.704 | 0 | %100 |
| 40 | MP3A | Z | -3.87 | -3.87 | 0 | %100 |
| 41 | MP2A | X | 6.704 | 6.704 | 0 | %100 |
| 42 | MP2A | Z | -3.87 | -3.87 | 0 | %100 |
| 43 | MP1A | X | 6.704 | 6.704 | 0 | %100 |
| 44 | MP1A | Z | -3.87 | -3.87 | 0 | %100 |
| 45 | M44 | X | 1.764 | 1.764 | 0 | %100 |
| 46 | M44 | Z | -1.019 | -1.019 | 0 | %100 |
| 47 | M45 | X | 1.764 | 1.764 | 0 | %100 |
| 48 | M45 | Z | -1.019 | -1.019 | 0 | %100 |
| 49 | M46 | X | 1.764 | 1.764 | 0 | %100 |
| 50 | M46 | Z | -1.019 | -1.019 | 0 | %100 |
| 51 | M47 | X | 1.764 | 1.764 | 0 | %100 |
| 52 | M47 | Z | -1.019 | -1.019 | 0 | %100 |
| 53 | M43 | X | 6.25 | 6.25 | 0 | %100 |
| 54 | M43 | Z | -3.609 | -3.609 | 0 | %100 |
| 55 | M44A | X | 3.361 | 3.361 | 0 | %100 |
| 56 | M44A | Z | -1.94 | -1.94 | 0 | %100 |

Member Distributed Loads (BLC 44 : Structure Wo (90 Deg))

| | Member Label | Direction | Start Magnitude[...] | End Magnitude[lb/ft,F,ksf] | Start Location[ft, %] | End Location[ft, %] |
|----|--------------|-----------|----------------------|----------------------------|-----------------------|---------------------|
| 1 | FACE | X | 0 | 0 | 0 | %100 |
| 2 | FACE | Z | 0 | 0 | 0 | %100 |
| 3 | M2 | X | 0 | 0 | 0 | %100 |
| 4 | M2 | Z | 0 | 0 | 0 | %100 |
| 5 | M13 | X | 2.037 | 2.037 | 0 | %100 |
| 6 | M13 | Z | 0 | 0 | 0 | %100 |
| 7 | M14 | X | 2.037 | 2.037 | 0 | %100 |
| 8 | M14 | Z | 0 | 0 | 0 | %100 |
| 9 | M15 | X | 2.037 | 2.037 | 0 | %100 |
| 10 | M15 | Z | 0 | 0 | 0 | %100 |
| 11 | M16 | X | 2.037 | 2.037 | 0 | %100 |
| 12 | M16 | Z | 0 | 0 | 0 | %100 |
| 13 | M17 | X | 2.269 | 2.269 | 0 | %100 |
| 14 | M17 | Z | 0 | 0 | 0 | %100 |
| 15 | M18 | X | 2.269 | 2.269 | 0 | %100 |
| 16 | M18 | Z | 0 | 0 | 0 | %100 |
| 17 | M19 | X | 2.269 | 2.269 | 0 | %100 |
| 18 | M19 | Z | 0 | 0 | 0 | %100 |
| 19 | M20 | X | 2.269 | 2.269 | 0 | %100 |
| 20 | M20 | Z | 0 | 0 | 0 | %100 |
| 21 | M21 | X | 0 | 0 | 0 | %100 |
| 22 | M21 | Z | 0 | 0 | 0 | %100 |
| 23 | M22 | X | 0 | 0 | 0 | %100 |
| 24 | M22 | Z | 0 | 0 | 0 | %100 |
| 25 | M23 | X | 0 | 0 | 0 | %100 |
| 26 | M23 | Z | 0 | 0 | 0 | %100 |
| 27 | M24 | X | 0 | 0 | 0 | %100 |
| 28 | M24 | Z | 0 | 0 | 0 | %100 |
| 29 | M25 | X | 1.899 | 1.899 | 0 | %100 |
| 30 | M25 | Z | 0 | 0 | 0 | %100 |
| 31 | M26 | X | 1.899 | 1.899 | 0 | %100 |
| 32 | M26 | Z | 0 | 0 | 0 | %100 |
| 33 | M27 | X | 1.899 | 1.899 | 0 | %100 |
| 34 | M27 | Z | 0 | 0 | 0 | %100 |
| 35 | M28 | X | 1.899 | 1.899 | 0 | %100 |



Company :
 Designer :
 Job Number :
 Model Name :

Apr 12, 2022
 10:37 AM
 Checked By: _____

Member Distributed Loads (BLC 44 : Structure Wo (90 Deg)) (Continued)

| | Member Label | Direction | Start Magnitude[...] | End Magnitude[lb/ft,F,ksf] | Start Location[ft,%] | End Location[ft,%] |
|----|--------------|-----------|----------------------|----------------------------|----------------------|--------------------|
| 36 | M28 | Z | 0 | 0 | 0 | %100 |
| 37 | MP4A | X | 7.741 | 7.741 | 0 | %100 |
| 38 | MP4A | Z | 0 | 0 | 0 | %100 |
| 39 | MP3A | X | 7.741 | 7.741 | 0 | %100 |
| 40 | MP3A | Z | 0 | 0 | 0 | %100 |
| 41 | MP2A | X | 7.741 | 7.741 | 0 | %100 |
| 42 | MP2A | Z | 0 | 0 | 0 | %100 |
| 43 | MP1A | X | 7.741 | 7.741 | 0 | %100 |
| 44 | MP1A | Z | 0 | 0 | 0 | %100 |
| 45 | M44 | X | 2.037 | 2.037 | 0 | %100 |
| 46 | M44 | Z | 0 | 0 | 0 | %100 |
| 47 | M45 | X | 2.037 | 2.037 | 0 | %100 |
| 48 | M45 | Z | 0 | 0 | 0 | %100 |
| 49 | M46 | X | 2.037 | 2.037 | 0 | %100 |
| 50 | M46 | Z | 0 | 0 | 0 | %100 |
| 51 | M47 | X | 2.037 | 2.037 | 0 | %100 |
| 52 | M47 | Z | 0 | 0 | 0 | %100 |
| 53 | M43 | X | 7.227 | 7.227 | 0 | %100 |
| 54 | M43 | Z | 0 | 0 | 0 | %100 |
| 55 | M44A | X | 7.227 | 7.227 | 0 | %100 |
| 56 | M44A | Z | 0 | 0 | 0 | %100 |

Member Distributed Loads (BLC 45 : Structure Wo (120 Deg))

| | Member Label | Direction | Start Magnitude[...] | End Magnitude[lb/ft,F,ksf] | Start Location[ft,%] | End Location[ft,%] |
|----|--------------|-----------|----------------------|----------------------------|----------------------|--------------------|
| 1 | FACE | X | 2.029 | 2.029 | 0 | %100 |
| 2 | FACE | Z | 1.171 | 1.171 | 0 | %100 |
| 3 | M2 | X | 2.029 | 2.029 | 0 | %100 |
| 4 | M2 | Z | 1.171 | 1.171 | 0 | %100 |
| 5 | M13 | X | 1.323 | 1.323 | 0 | %100 |
| 6 | M13 | Z | .764 | .764 | 0 | %100 |
| 7 | M14 | X | 1.323 | 1.323 | 0 | %100 |
| 8 | M14 | Z | .764 | .764 | 0 | %100 |
| 9 | M15 | X | 1.323 | 1.323 | 0 | %100 |
| 10 | M15 | Z | .764 | .764 | 0 | %100 |
| 11 | M16 | X | 1.323 | 1.323 | 0 | %100 |
| 12 | M16 | Z | .764 | .764 | 0 | %100 |
| 13 | M17 | X | 4.447 | 4.447 | 0 | %100 |
| 14 | M17 | Z | 2.568 | 2.568 | 0 | %100 |
| 15 | M18 | X | 4.447 | 4.447 | 0 | %100 |
| 16 | M18 | Z | 2.568 | 2.568 | 0 | %100 |
| 17 | M19 | X | .102 | .102 | 0 | %100 |
| 18 | M19 | Z | .059 | .059 | 0 | %100 |
| 19 | M20 | X | .102 | .102 | 0 | %100 |
| 20 | M20 | Z | .059 | .059 | 0 | %100 |
| 21 | M21 | X | .441 | .441 | 0 | %100 |
| 22 | M21 | Z | .255 | .255 | 0 | %100 |
| 23 | M22 | X | .441 | .441 | 0 | %100 |
| 24 | M22 | Z | .255 | .255 | 0 | %100 |
| 25 | M23 | X | .441 | .441 | 0 | %100 |
| 26 | M23 | Z | .255 | .255 | 0 | %100 |
| 27 | M24 | X | .441 | .441 | 0 | %100 |
| 28 | M24 | Z | .255 | .255 | 0 | %100 |
| 29 | M25 | X | 2.011 | 2.011 | 0 | %100 |
| 30 | M25 | Z | 1.161 | 1.161 | 0 | %100 |
| 31 | M26 | X | 2.011 | 2.011 | 0 | %100 |
| 32 | M26 | Z | 1.161 | 1.161 | 0 | %100 |



Company :
 Designer :
 Job Number :
 Model Name :

Apr 12, 2022
 10:37 AM
 Checked By: _____

Member Distributed Loads (BLC 45 : Structure Wo (120 Deg)) (Continued)

| | Member Label | Direction | Start Magnitude[...] | End Magnitude[lb/ft.F,ksf] | Start Location[ft.%] | End Location[ft.%] |
|----|--------------|-----------|----------------------|----------------------------|----------------------|--------------------|
| 33 | M27 | X | 1.37 | 1.37 | 0 | %100 |
| 34 | M27 | Z | .791 | .791 | 0 | %100 |
| 35 | M28 | X | 1.37 | 1.37 | 0 | %100 |
| 36 | M28 | Z | .791 | .791 | 0 | %100 |
| 37 | MP4A | X | 6.704 | 6.704 | 0 | %100 |
| 38 | MP4A | Z | 3.87 | 3.87 | 0 | %100 |
| 39 | MP3A | X | 6.704 | 6.704 | 0 | %100 |
| 40 | MP3A | Z | 3.87 | 3.87 | 0 | %100 |
| 41 | MP2A | X | 6.704 | 6.704 | 0 | %100 |
| 42 | MP2A | Z | 3.87 | 3.87 | 0 | %100 |
| 43 | MP1A | X | 6.704 | 6.704 | 0 | %100 |
| 44 | MP1A | Z | 3.87 | 3.87 | 0 | %100 |
| 45 | M44 | X | 1.764 | 1.764 | 0 | %100 |
| 46 | M44 | Z | 1.019 | 1.019 | 0 | %100 |
| 47 | M45 | X | 1.764 | 1.764 | 0 | %100 |
| 48 | M45 | Z | 1.019 | 1.019 | 0 | %100 |
| 49 | M46 | X | 1.764 | 1.764 | 0 | %100 |
| 50 | M46 | Z | 1.019 | 1.019 | 0 | %100 |
| 51 | M47 | X | 1.764 | 1.764 | 0 | %100 |
| 52 | M47 | Z | 1.019 | 1.019 | 0 | %100 |
| 53 | M43 | X | 3.361 | 3.361 | 0 | %100 |
| 54 | M43 | Z | 1.94 | 1.94 | 0 | %100 |
| 55 | M44A | X | 6.25 | 6.25 | 0 | %100 |
| 56 | M44A | Z | 3.609 | 3.609 | 0 | %100 |

Member Distributed Loads (BLC 46 : Structure Wo (150 Deg))

| | Member Label | Direction | Start Magnitude[...] | End Magnitude[lb/ft.F,ksf] | Start Location[ft.%] | End Location[ft.%] |
|----|--------------|-----------|----------------------|----------------------------|----------------------|--------------------|
| 1 | FACE | X | 3.514 | 3.514 | 0 | %100 |
| 2 | FACE | Z | 6.086 | 6.086 | 0 | %100 |
| 3 | M2 | X | 3.514 | 3.514 | 0 | %100 |
| 4 | M2 | Z | 6.086 | 6.086 | 0 | %100 |
| 5 | M13 | X | .255 | .255 | 0 | %100 |
| 6 | M13 | Z | .441 | .441 | 0 | %100 |
| 7 | M14 | X | .255 | .255 | 0 | %100 |
| 8 | M14 | Z | .441 | .441 | 0 | %100 |
| 9 | M15 | X | .255 | .255 | 0 | %100 |
| 10 | M15 | Z | .441 | .441 | 0 | %100 |
| 11 | M16 | X | .255 | .255 | 0 | %100 |
| 12 | M16 | Z | .441 | .441 | 0 | %100 |
| 13 | M17 | X | 2.925 | 2.925 | 0 | %100 |
| 14 | M17 | Z | 5.067 | 5.067 | 0 | %100 |
| 15 | M18 | X | 2.925 | 2.925 | 0 | %100 |
| 16 | M18 | Z | 5.067 | 5.067 | 0 | %100 |
| 17 | M19 | X | .416 | .416 | 0 | %100 |
| 18 | M19 | Z | .721 | .721 | 0 | %100 |
| 19 | M20 | X | .416 | .416 | 0 | %100 |
| 20 | M20 | Z | .721 | .721 | 0 | %100 |
| 21 | M21 | X | .764 | .764 | 0 | %100 |
| 22 | M21 | Z | 1.323 | 1.323 | 0 | %100 |
| 23 | M22 | X | .764 | .764 | 0 | %100 |
| 24 | M22 | Z | 1.323 | 1.323 | 0 | %100 |
| 25 | M23 | X | .764 | .764 | 0 | %100 |
| 26 | M23 | Z | 1.323 | 1.323 | 0 | %100 |
| 27 | M24 | X | .764 | .764 | 0 | %100 |
| 28 | M24 | Z | 1.323 | 1.323 | 0 | %100 |
| 29 | M25 | X | 1.214 | 1.214 | 0 | %100 |

Member Distributed Loads (BLC 46 : Structure Wo (150 Deg)) (Continued)

| | Member Label | Direction | Start Magnitude[...] | End Magnitude[lb/ft,F,ksf] | Start Location[ft,%] | End Location[ft,%] |
|----|--------------|-----------|----------------------|----------------------------|----------------------|--------------------|
| 30 | M25 | Z | 2.102 | 2.102 | 0 | %100 |
| 31 | M26 | X | 1.214 | 1.214 | 0 | %100 |
| 32 | M26 | Z | 2.102 | 2.102 | 0 | %100 |
| 33 | M27 | X | .844 | .844 | 0 | %100 |
| 34 | M27 | Z | 1.461 | 1.461 | 0 | %100 |
| 35 | M28 | X | .844 | .844 | 0 | %100 |
| 36 | M28 | Z | 1.461 | 1.461 | 0 | %100 |
| 37 | MP4A | X | 3.87 | 3.87 | 0 | %100 |
| 38 | MP4A | Z | 6.704 | 6.704 | 0 | %100 |
| 39 | MP3A | X | 3.87 | 3.87 | 0 | %100 |
| 40 | MP3A | Z | 6.704 | 6.704 | 0 | %100 |
| 41 | MP2A | X | 3.87 | 3.87 | 0 | %100 |
| 42 | MP2A | Z | 6.704 | 6.704 | 0 | %100 |
| 43 | MP1A | X | 3.87 | 3.87 | 0 | %100 |
| 44 | MP1A | Z | 6.704 | 6.704 | 0 | %100 |
| 45 | M44 | X | 1.019 | 1.019 | 0 | %100 |
| 46 | M44 | Z | 1.764 | 1.764 | 0 | %100 |
| 47 | M45 | X | 1.019 | 1.019 | 0 | %100 |
| 48 | M45 | Z | 1.764 | 1.764 | 0 | %100 |
| 49 | M46 | X | 1.019 | 1.019 | 0 | %100 |
| 50 | M46 | Z | 1.764 | 1.764 | 0 | %100 |
| 51 | M47 | X | 1.019 | 1.019 | 0 | %100 |
| 52 | M47 | Z | 1.764 | 1.764 | 0 | %100 |
| 53 | M43 | X | .262 | .262 | 0 | %100 |
| 54 | M43 | Z | .453 | .453 | 0 | %100 |
| 55 | M44A | X | 1.93 | 1.93 | 0 | %100 |
| 56 | M44A | Z | 3.343 | 3.343 | 0 | %100 |

Member Distributed Loads (BLC 47 : Structure Wo (180 Deg))

| | Member Label | Direction | Start Magnitude[...] | End Magnitude[lb/ft,F,ksf] | Start Location[ft,%] | End Location[ft,%] |
|----|--------------|-----------|----------------------|----------------------------|----------------------|--------------------|
| 1 | FACE | X | 0 | 0 | 0 | %100 |
| 2 | FACE | Z | 9.371 | 9.371 | 0 | %100 |
| 3 | M2 | X | 0 | 0 | 0 | %100 |
| 4 | M2 | Z | 9.371 | 9.371 | 0 | %100 |
| 5 | M13 | X | 0 | 0 | 0 | %100 |
| 6 | M13 | Z | 0 | 0 | 0 | %100 |
| 7 | M14 | X | 0 | 0 | 0 | %100 |
| 8 | M14 | Z | 0 | 0 | 0 | %100 |
| 9 | M15 | X | 0 | 0 | 0 | %100 |
| 10 | M15 | Z | 0 | 0 | 0 | %100 |
| 11 | M16 | X | 0 | 0 | 0 | %100 |
| 12 | M16 | Z | 0 | 0 | 0 | %100 |
| 13 | M17 | X | 0 | 0 | 0 | %100 |
| 14 | M17 | Z | 3.7 | 3.7 | 0 | %100 |
| 15 | M18 | X | 0 | 0 | 0 | %100 |
| 16 | M18 | Z | 3.7 | 3.7 | 0 | %100 |
| 17 | M19 | X | 0 | 0 | 0 | %100 |
| 18 | M19 | Z | 3.7 | 3.7 | 0 | %100 |
| 19 | M20 | X | 0 | 0 | 0 | %100 |
| 20 | M20 | Z | 3.7 | 3.7 | 0 | %100 |
| 21 | M21 | X | 0 | 0 | 0 | %100 |
| 22 | M21 | Z | 2.037 | 2.037 | 0 | %100 |
| 23 | M22 | X | 0 | 0 | 0 | %100 |
| 24 | M22 | Z | 2.037 | 2.037 | 0 | %100 |
| 25 | M23 | X | 0 | 0 | 0 | %100 |
| 26 | M23 | Z | 2.037 | 2.037 | 0 | %100 |

Member Distributed Loads (BLC 47 : Structure Wo (180 Deg)) (Continued)

| | Member Label | Direction | Start Magnitude[...] | End Magnitude[lb/ft,F,ksf] | Start Location[ft, %] | End Location[ft, %] |
|----|--------------|-----------|----------------------|----------------------------|-----------------------|---------------------|
| 27 | M24 | X | 0 | 0 | 0 | %100 |
| 28 | M24 | Z | 2.037 | 2.037 | 0 | %100 |
| 29 | M25 | X | 0 | 0 | 0 | %100 |
| 30 | M25 | Z | 2.11 | 2.11 | 0 | %100 |
| 31 | M26 | X | 0 | 0 | 0 | %100 |
| 32 | M26 | Z | 2.11 | 2.11 | 0 | %100 |
| 33 | M27 | X | 0 | 0 | 0 | %100 |
| 34 | M27 | Z | 2.11 | 2.11 | 0 | %100 |
| 35 | M28 | X | 0 | 0 | 0 | %100 |
| 36 | M28 | Z | 2.11 | 2.11 | 0 | %100 |
| 37 | MP4A | X | 0 | 0 | 0 | %100 |
| 38 | MP4A | Z | 7.741 | 7.741 | 0 | %100 |
| 39 | MP3A | X | 0 | 0 | 0 | %100 |
| 40 | MP3A | Z | 7.741 | 7.741 | 0 | %100 |
| 41 | MP2A | X | 0 | 0 | 0 | %100 |
| 42 | MP2A | Z | 7.741 | 7.741 | 0 | %100 |
| 43 | MP1A | X | 0 | 0 | 0 | %100 |
| 44 | MP1A | Z | 7.741 | 7.741 | 0 | %100 |
| 45 | M44 | X | 0 | 0 | 0 | %100 |
| 46 | M44 | Z | 2.037 | 2.037 | 0 | %100 |
| 47 | M45 | X | 0 | 0 | 0 | %100 |
| 48 | M45 | Z | 2.037 | 2.037 | 0 | %100 |
| 49 | M46 | X | 0 | 0 | 0 | %100 |
| 50 | M46 | Z | 2.037 | 2.037 | 0 | %100 |
| 51 | M47 | X | 0 | 0 | 0 | %100 |
| 52 | M47 | Z | 2.037 | 2.037 | 0 | %100 |
| 53 | M43 | X | 0 | 0 | 0 | %100 |
| 54 | M43 | Z | .513 | .513 | 0 | %100 |
| 55 | M44A | X | 0 | 0 | 0 | %100 |
| 56 | M44A | Z | .513 | .513 | 0 | %100 |

Member Distributed Loads (BLC 48 : Structure Wo (210 Deg))

| | Member Label | Direction | Start Magnitude[...] | End Magnitude[lb/ft,F,ksf] | Start Location[ft, %] | End Location[ft, %] |
|----|--------------|-----------|----------------------|----------------------------|-----------------------|---------------------|
| 1 | FACE | X | -3.514 | -3.514 | 0 | %100 |
| 2 | FACE | Z | 6.086 | 6.086 | 0 | %100 |
| 3 | M2 | X | -3.514 | -3.514 | 0 | %100 |
| 4 | M2 | Z | 6.086 | 6.086 | 0 | %100 |
| 5 | M13 | X | -.255 | -.255 | 0 | %100 |
| 6 | M13 | Z | .441 | .441 | 0 | %100 |
| 7 | M14 | X | -.255 | -.255 | 0 | %100 |
| 8 | M14 | Z | .441 | .441 | 0 | %100 |
| 9 | M15 | X | -.255 | -.255 | 0 | %100 |
| 10 | M15 | Z | .441 | .441 | 0 | %100 |
| 11 | M16 | X | -.255 | -.255 | 0 | %100 |
| 12 | M16 | Z | .441 | .441 | 0 | %100 |
| 13 | M17 | X | -.416 | -.416 | 0 | %100 |
| 14 | M17 | Z | .721 | .721 | 0 | %100 |
| 15 | M18 | X | -.416 | -.416 | 0 | %100 |
| 16 | M18 | Z | .721 | .721 | 0 | %100 |
| 17 | M19 | X | -2.925 | -2.925 | 0 | %100 |
| 18 | M19 | Z | 5.067 | 5.067 | 0 | %100 |
| 19 | M20 | X | -2.925 | -2.925 | 0 | %100 |
| 20 | M20 | Z | 5.067 | 5.067 | 0 | %100 |
| 21 | M21 | X | -.764 | -.764 | 0 | %100 |
| 22 | M21 | Z | 1.323 | 1.323 | 0 | %100 |
| 23 | M22 | X | -.764 | -.764 | 0 | %100 |

Member Distributed Loads (BLC 48 : Structure Wo (210 Deg)) (Continued)

| | Member Label | Direction | Start Magnitude[...] | End Magnitude[lb/ft,F,ksf] | Start Location[ft, %] | End Location[ft, %] |
|----|--------------|-----------|----------------------|----------------------------|-----------------------|---------------------|
| 24 | M22 | Z | 1.323 | 1.323 | 0 | %100 |
| 25 | M23 | X | -.764 | -.764 | 0 | %100 |
| 26 | M23 | Z | 1.323 | 1.323 | 0 | %100 |
| 27 | M24 | X | -.764 | -.764 | 0 | %100 |
| 28 | M24 | Z | 1.323 | 1.323 | 0 | %100 |
| 29 | M25 | X | -.844 | -.844 | 0 | %100 |
| 30 | M25 | Z | 1.461 | 1.461 | 0 | %100 |
| 31 | M26 | X | -.844 | -.844 | 0 | %100 |
| 32 | M26 | Z | 1.461 | 1.461 | 0 | %100 |
| 33 | M27 | X | -1.214 | -1.214 | 0 | %100 |
| 34 | M27 | Z | 2.102 | 2.102 | 0 | %100 |
| 35 | M28 | X | -1.214 | -1.214 | 0 | %100 |
| 36 | M28 | Z | 2.102 | 2.102 | 0 | %100 |
| 37 | MP4A | X | -3.87 | -3.87 | 0 | %100 |
| 38 | MP4A | Z | 6.704 | 6.704 | 0 | %100 |
| 39 | MP3A | X | -3.87 | -3.87 | 0 | %100 |
| 40 | MP3A | Z | 6.704 | 6.704 | 0 | %100 |
| 41 | MP2A | X | -3.87 | -3.87 | 0 | %100 |
| 42 | MP2A | Z | 6.704 | 6.704 | 0 | %100 |
| 43 | MP1A | X | -3.87 | -3.87 | 0 | %100 |
| 44 | MP1A | Z | 6.704 | 6.704 | 0 | %100 |
| 45 | M44 | X | -1.019 | -1.019 | 0 | %100 |
| 46 | M44 | Z | 1.764 | 1.764 | 0 | %100 |
| 47 | M45 | X | -1.019 | -1.019 | 0 | %100 |
| 48 | M45 | Z | 1.764 | 1.764 | 0 | %100 |
| 49 | M46 | X | -1.019 | -1.019 | 0 | %100 |
| 50 | M46 | Z | 1.764 | 1.764 | 0 | %100 |
| 51 | M47 | X | -1.019 | -1.019 | 0 | %100 |
| 52 | M47 | Z | 1.764 | 1.764 | 0 | %100 |
| 53 | M43 | X | -1.93 | -1.93 | 0 | %100 |
| 54 | M43 | Z | 3.343 | 3.343 | 0 | %100 |
| 55 | M44A | X | -.262 | -.262 | 0 | %100 |
| 56 | M44A | Z | .453 | .453 | 0 | %100 |

Member Distributed Loads (BLC 49 : Structure Wo (240 Deg))

| | Member Label | Direction | Start Magnitude[...] | End Magnitude[lb/ft,F,ksf] | Start Location[ft, %] | End Location[ft, %] |
|----|--------------|-----------|----------------------|----------------------------|-----------------------|---------------------|
| 1 | FACE | X | -2.029 | -2.029 | 0 | %100 |
| 2 | FACE | Z | 1.171 | 1.171 | 0 | %100 |
| 3 | M2 | X | -2.029 | -2.029 | 0 | %100 |
| 4 | M2 | Z | 1.171 | 1.171 | 0 | %100 |
| 5 | M13 | X | -1.323 | -1.323 | 0 | %100 |
| 6 | M13 | Z | .764 | .764 | 0 | %100 |
| 7 | M14 | X | -1.323 | -1.323 | 0 | %100 |
| 8 | M14 | Z | .764 | .764 | 0 | %100 |
| 9 | M15 | X | -1.323 | -1.323 | 0 | %100 |
| 10 | M15 | Z | .764 | .764 | 0 | %100 |
| 11 | M16 | X | -1.323 | -1.323 | 0 | %100 |
| 12 | M16 | Z | .764 | .764 | 0 | %100 |
| 13 | M17 | X | -.102 | -.102 | 0 | %100 |
| 14 | M17 | Z | .059 | .059 | 0 | %100 |
| 15 | M18 | X | -.102 | -.102 | 0 | %100 |
| 16 | M18 | Z | .059 | .059 | 0 | %100 |
| 17 | M19 | X | -4.447 | -4.447 | 0 | %100 |
| 18 | M19 | Z | 2.568 | 2.568 | 0 | %100 |
| 19 | M20 | X | -4.447 | -4.447 | 0 | %100 |
| 20 | M20 | Z | 2.568 | 2.568 | 0 | %100 |

Member Distributed Loads (BLC 49 : Structure Wo (240 Deg)) (Continued)

| | Member Label | Direction | Start Magnitude[...] | End Magnitude[lb/ft,F,ksf] | Start Location[ft, %] | End Location[ft, %] |
|----|--------------|-----------|----------------------|----------------------------|-----------------------|---------------------|
| 21 | M21 | X | -441 | -441 | 0 | %100 |
| 22 | M21 | Z | .255 | .255 | 0 | %100 |
| 23 | M22 | X | -441 | -441 | 0 | %100 |
| 24 | M22 | Z | .255 | .255 | 0 | %100 |
| 25 | M23 | X | -441 | -441 | 0 | %100 |
| 26 | M23 | Z | .255 | .255 | 0 | %100 |
| 27 | M24 | X | -441 | -441 | 0 | %100 |
| 28 | M24 | Z | .255 | .255 | 0 | %100 |
| 29 | M25 | X | -1.37 | -1.37 | 0 | %100 |
| 30 | M25 | Z | .791 | .791 | 0 | %100 |
| 31 | M26 | X | -1.37 | -1.37 | 0 | %100 |
| 32 | M26 | Z | .791 | .791 | 0 | %100 |
| 33 | M27 | X | -2.011 | -2.011 | 0 | %100 |
| 34 | M27 | Z | 1.161 | 1.161 | 0 | %100 |
| 35 | M28 | X | -2.011 | -2.011 | 0 | %100 |
| 36 | M28 | Z | 1.161 | 1.161 | 0 | %100 |
| 37 | MP4A | X | -6.704 | -6.704 | 0 | %100 |
| 38 | MP4A | Z | 3.87 | 3.87 | 0 | %100 |
| 39 | MP3A | X | -6.704 | -6.704 | 0 | %100 |
| 40 | MP3A | Z | 3.87 | 3.87 | 0 | %100 |
| 41 | MP2A | X | -6.704 | -6.704 | 0 | %100 |
| 42 | MP2A | Z | 3.87 | 3.87 | 0 | %100 |
| 43 | MP1A | X | -6.704 | -6.704 | 0 | %100 |
| 44 | MP1A | Z | 3.87 | 3.87 | 0 | %100 |
| 45 | M44 | X | -1.764 | -1.764 | 0 | %100 |
| 46 | M44 | Z | 1.019 | 1.019 | 0 | %100 |
| 47 | M45 | X | -1.764 | -1.764 | 0 | %100 |
| 48 | M45 | Z | 1.019 | 1.019 | 0 | %100 |
| 49 | M46 | X | -1.764 | -1.764 | 0 | %100 |
| 50 | M46 | Z | 1.019 | 1.019 | 0 | %100 |
| 51 | M47 | X | -1.764 | -1.764 | 0 | %100 |
| 52 | M47 | Z | 1.019 | 1.019 | 0 | %100 |
| 53 | M43 | X | -6.25 | -6.25 | 0 | %100 |
| 54 | M43 | Z | 3.609 | 3.609 | 0 | %100 |
| 55 | M44A | X | -3.361 | -3.361 | 0 | %100 |
| 56 | M44A | Z | 1.94 | 1.94 | 0 | %100 |

Member Distributed Loads (BLC 50 : Structure Wo (270 Deg))

| | Member Label | Direction | Start Magnitude[...] | End Magnitude[lb/ft,F,ksf] | Start Location[ft, %] | End Location[ft, %] |
|----|--------------|-----------|----------------------|----------------------------|-----------------------|---------------------|
| 1 | FACE | X | 0 | 0 | 0 | %100 |
| 2 | FACE | Z | 0 | 0 | 0 | %100 |
| 3 | M2 | X | 0 | 0 | 0 | %100 |
| 4 | M2 | Z | 0 | 0 | 0 | %100 |
| 5 | M13 | X | -2.037 | -2.037 | 0 | %100 |
| 6 | M13 | Z | 0 | 0 | 0 | %100 |
| 7 | M14 | X | -2.037 | -2.037 | 0 | %100 |
| 8 | M14 | Z | 0 | 0 | 0 | %100 |
| 9 | M15 | X | -2.037 | -2.037 | 0 | %100 |
| 10 | M15 | Z | 0 | 0 | 0 | %100 |
| 11 | M16 | X | -2.037 | -2.037 | 0 | %100 |
| 12 | M16 | Z | 0 | 0 | 0 | %100 |
| 13 | M17 | X | -2.269 | -2.269 | 0 | %100 |
| 14 | M17 | Z | 0 | 0 | 0 | %100 |
| 15 | M18 | X | -2.269 | -2.269 | 0 | %100 |
| 16 | M18 | Z | 0 | 0 | 0 | %100 |
| 17 | M19 | X | -2.269 | -2.269 | 0 | %100 |

Member Distributed Loads (BLC 50 : Structure Wo (270 Deg)) (Continued)

| | Member Label | Direction | Start Magnitude[...] | End Magnitude[lb/ft.F,ksf] | Start Location[ft.%] | End Location[ft.%] |
|----|--------------|-----------|----------------------|----------------------------|----------------------|--------------------|
| 18 | M19 | Z | 0 | 0 | 0 | %100 |
| 19 | M20 | X | -2.269 | -2.269 | 0 | %100 |
| 20 | M20 | Z | 0 | 0 | 0 | %100 |
| 21 | M21 | X | 0 | 0 | 0 | %100 |
| 22 | M21 | Z | 0 | 0 | 0 | %100 |
| 23 | M22 | X | 0 | 0 | 0 | %100 |
| 24 | M22 | Z | 0 | 0 | 0 | %100 |
| 25 | M23 | X | 0 | 0 | 0 | %100 |
| 26 | M23 | Z | 0 | 0 | 0 | %100 |
| 27 | M24 | X | 0 | 0 | 0 | %100 |
| 28 | M24 | Z | 0 | 0 | 0 | %100 |
| 29 | M25 | X | -1.899 | -1.899 | 0 | %100 |
| 30 | M25 | Z | 0 | 0 | 0 | %100 |
| 31 | M26 | X | -1.899 | -1.899 | 0 | %100 |
| 32 | M26 | Z | 0 | 0 | 0 | %100 |
| 33 | M27 | X | -1.899 | -1.899 | 0 | %100 |
| 34 | M27 | Z | 0 | 0 | 0 | %100 |
| 35 | M28 | X | -1.899 | -1.899 | 0 | %100 |
| 36 | M28 | Z | 0 | 0 | 0 | %100 |
| 37 | MP4A | X | -7.741 | -7.741 | 0 | %100 |
| 38 | MP4A | Z | 0 | 0 | 0 | %100 |
| 39 | MP3A | X | -7.741 | -7.741 | 0 | %100 |
| 40 | MP3A | Z | 0 | 0 | 0 | %100 |
| 41 | MP2A | X | -7.741 | -7.741 | 0 | %100 |
| 42 | MP2A | Z | 0 | 0 | 0 | %100 |
| 43 | MP1A | X | -7.741 | -7.741 | 0 | %100 |
| 44 | MP1A | Z | 0 | 0 | 0 | %100 |
| 45 | M44 | X | -2.037 | -2.037 | 0 | %100 |
| 46 | M44 | Z | 0 | 0 | 0 | %100 |
| 47 | M45 | X | -2.037 | -2.037 | 0 | %100 |
| 48 | M45 | Z | 0 | 0 | 0 | %100 |
| 49 | M46 | X | -2.037 | -2.037 | 0 | %100 |
| 50 | M46 | Z | 0 | 0 | 0 | %100 |
| 51 | M47 | X | -2.037 | -2.037 | 0 | %100 |
| 52 | M47 | Z | 0 | 0 | 0 | %100 |
| 53 | M43 | X | -7.227 | -7.227 | 0 | %100 |
| 54 | M43 | Z | 0 | 0 | 0 | %100 |
| 55 | M44A | X | -7.227 | -7.227 | 0 | %100 |
| 56 | M44A | Z | 0 | 0 | 0 | %100 |

Member Distributed Loads (BLC 51 : Structure Wo (300 Deg))

| | Member Label | Direction | Start Magnitude[...] | End Magnitude[lb/ft.F,ksf] | Start Location[ft.%] | End Location[ft.%] |
|----|--------------|-----------|----------------------|----------------------------|----------------------|--------------------|
| 1 | FACE | X | -2.029 | -2.029 | 0 | %100 |
| 2 | FACE | Z | -1.171 | -1.171 | 0 | %100 |
| 3 | M2 | X | -2.029 | -2.029 | 0 | %100 |
| 4 | M2 | Z | -1.171 | -1.171 | 0 | %100 |
| 5 | M13 | X | -1.323 | -1.323 | 0 | %100 |
| 6 | M13 | Z | -.764 | -.764 | 0 | %100 |
| 7 | M14 | X | -1.323 | -1.323 | 0 | %100 |
| 8 | M14 | Z | -.764 | -.764 | 0 | %100 |
| 9 | M15 | X | -1.323 | -1.323 | 0 | %100 |
| 10 | M15 | Z | -.764 | -.764 | 0 | %100 |
| 11 | M16 | X | -1.323 | -1.323 | 0 | %100 |
| 12 | M16 | Z | -.764 | -.764 | 0 | %100 |
| 13 | M17 | X | -4.447 | -4.447 | 0 | %100 |
| 14 | M17 | Z | -2.568 | -2.568 | 0 | %100 |



Company :
 Designer :
 Job Number :
 Model Name :

Apr 12, 2022
 10:37 AM
 Checked By: _____

Member Distributed Loads (BLC 51 : Structure Wo (300 Deg)) (Continued)

| | Member Label | Direction | Start Magnitude[...] | End Magnitude[lb/ft,F,ksf] | Start Location[ft, %] | End Location[ft, %] |
|----|--------------|-----------|----------------------|----------------------------|-----------------------|---------------------|
| 15 | M18 | X | -4.447 | -4.447 | 0 | %100 |
| 16 | M18 | Z | -2.568 | -2.568 | 0 | %100 |
| 17 | M19 | X | -.102 | -.102 | 0 | %100 |
| 18 | M19 | Z | -.059 | -.059 | 0 | %100 |
| 19 | M20 | X | -.102 | -.102 | 0 | %100 |
| 20 | M20 | Z | -.059 | -.059 | 0 | %100 |
| 21 | M21 | X | -.441 | -.441 | 0 | %100 |
| 22 | M21 | Z | -.255 | -.255 | 0 | %100 |
| 23 | M22 | X | -.441 | -.441 | 0 | %100 |
| 24 | M22 | Z | -.255 | -.255 | 0 | %100 |
| 25 | M23 | X | -.441 | -.441 | 0 | %100 |
| 26 | M23 | Z | -.255 | -.255 | 0 | %100 |
| 27 | M24 | X | -.441 | -.441 | 0 | %100 |
| 28 | M24 | Z | -.255 | -.255 | 0 | %100 |
| 29 | M25 | X | -2.011 | -2.011 | 0 | %100 |
| 30 | M25 | Z | -1.161 | -1.161 | 0 | %100 |
| 31 | M26 | X | -2.011 | -2.011 | 0 | %100 |
| 32 | M26 | Z | -1.161 | -1.161 | 0 | %100 |
| 33 | M27 | X | -1.37 | -1.37 | 0 | %100 |
| 34 | M27 | Z | -.791 | -.791 | 0 | %100 |
| 35 | M28 | X | -1.37 | -1.37 | 0 | %100 |
| 36 | M28 | Z | -.791 | -.791 | 0 | %100 |
| 37 | MP4A | X | -6.704 | -6.704 | 0 | %100 |
| 38 | MP4A | Z | -3.87 | -3.87 | 0 | %100 |
| 39 | MP3A | X | -6.704 | -6.704 | 0 | %100 |
| 40 | MP3A | Z | -3.87 | -3.87 | 0 | %100 |
| 41 | MP2A | X | -6.704 | -6.704 | 0 | %100 |
| 42 | MP2A | Z | -3.87 | -3.87 | 0 | %100 |
| 43 | MP1A | X | -6.704 | -6.704 | 0 | %100 |
| 44 | MP1A | Z | -3.87 | -3.87 | 0 | %100 |
| 45 | M44 | X | -1.764 | -1.764 | 0 | %100 |
| 46 | M44 | Z | -1.019 | -1.019 | 0 | %100 |
| 47 | M45 | X | -1.764 | -1.764 | 0 | %100 |
| 48 | M45 | Z | -1.019 | -1.019 | 0 | %100 |
| 49 | M46 | X | -1.764 | -1.764 | 0 | %100 |
| 50 | M46 | Z | -1.019 | -1.019 | 0 | %100 |
| 51 | M47 | X | -1.764 | -1.764 | 0 | %100 |
| 52 | M47 | Z | -1.019 | -1.019 | 0 | %100 |
| 53 | M43 | X | -3.361 | -3.361 | 0 | %100 |
| 54 | M43 | Z | -1.94 | -1.94 | 0 | %100 |
| 55 | M44A | X | -6.25 | -6.25 | 0 | %100 |
| 56 | M44A | Z | -3.609 | -3.609 | 0 | %100 |

Member Distributed Loads (BLC 52 : Structure Wo (330 Deg))

| | Member Label | Direction | Start Magnitude[...] | End Magnitude[lb/ft,F,ksf] | Start Location[ft, %] | End Location[ft, %] |
|----|--------------|-----------|----------------------|----------------------------|-----------------------|---------------------|
| 1 | FACE | X | -3.514 | -3.514 | 0 | %100 |
| 2 | FACE | Z | -6.086 | -6.086 | 0 | %100 |
| 3 | M2 | X | -3.514 | -3.514 | 0 | %100 |
| 4 | M2 | Z | -6.086 | -6.086 | 0 | %100 |
| 5 | M13 | X | -.255 | -.255 | 0 | %100 |
| 6 | M13 | Z | -.441 | -.441 | 0 | %100 |
| 7 | M14 | X | -.255 | -.255 | 0 | %100 |
| 8 | M14 | Z | -.441 | -.441 | 0 | %100 |
| 9 | M15 | X | -.255 | -.255 | 0 | %100 |
| 10 | M15 | Z | -.441 | -.441 | 0 | %100 |
| 11 | M16 | X | -.255 | -.255 | 0 | %100 |

Member Distributed Loads (BLC 52 : Structure Wo (330 Deg)) (Continued)

| | Member Label | Direction | Start Magnitude[...] | End Magnitude[lb/ft.F,ksf] | Start Location[ft.%] | End Location[ft.%] |
|----|--------------|-----------|----------------------|----------------------------|----------------------|--------------------|
| 12 | M16 | Z | -441 | -441 | 0 | %100 |
| 13 | M17 | X | -2.925 | -2.925 | 0 | %100 |
| 14 | M17 | Z | -5.067 | -5.067 | 0 | %100 |
| 15 | M18 | X | -2.925 | -2.925 | 0 | %100 |
| 16 | M18 | Z | -5.067 | -5.067 | 0 | %100 |
| 17 | M19 | X | -416 | -416 | 0 | %100 |
| 18 | M19 | Z | -721 | -721 | 0 | %100 |
| 19 | M20 | X | -416 | -416 | 0 | %100 |
| 20 | M20 | Z | -721 | -721 | 0 | %100 |
| 21 | M21 | X | -764 | -764 | 0 | %100 |
| 22 | M21 | Z | -1.323 | -1.323 | 0 | %100 |
| 23 | M22 | X | -764 | -764 | 0 | %100 |
| 24 | M22 | Z | -1.323 | -1.323 | 0 | %100 |
| 25 | M23 | X | -764 | -764 | 0 | %100 |
| 26 | M23 | Z | -1.323 | -1.323 | 0 | %100 |
| 27 | M24 | X | -764 | -764 | 0 | %100 |
| 28 | M24 | Z | -1.323 | -1.323 | 0 | %100 |
| 29 | M25 | X | -1.214 | -1.214 | 0 | %100 |
| 30 | M25 | Z | -2.102 | -2.102 | 0 | %100 |
| 31 | M26 | X | -1.214 | -1.214 | 0 | %100 |
| 32 | M26 | Z | -2.102 | -2.102 | 0 | %100 |
| 33 | M27 | X | -844 | -844 | 0 | %100 |
| 34 | M27 | Z | -1.461 | -1.461 | 0 | %100 |
| 35 | M28 | X | -844 | -844 | 0 | %100 |
| 36 | M28 | Z | -1.461 | -1.461 | 0 | %100 |
| 37 | MP4A | X | -3.87 | -3.87 | 0 | %100 |
| 38 | MP4A | Z | -6.704 | -6.704 | 0 | %100 |
| 39 | MP3A | X | -3.87 | -3.87 | 0 | %100 |
| 40 | MP3A | Z | -6.704 | -6.704 | 0 | %100 |
| 41 | MP2A | X | -3.87 | -3.87 | 0 | %100 |
| 42 | MP2A | Z | -6.704 | -6.704 | 0 | %100 |
| 43 | MP1A | X | -3.87 | -3.87 | 0 | %100 |
| 44 | MP1A | Z | -6.704 | -6.704 | 0 | %100 |
| 45 | M44 | X | -1.019 | -1.019 | 0 | %100 |
| 46 | M44 | Z | -1.764 | -1.764 | 0 | %100 |
| 47 | M45 | X | -1.019 | -1.019 | 0 | %100 |
| 48 | M45 | Z | -1.764 | -1.764 | 0 | %100 |
| 49 | M46 | X | -1.019 | -1.019 | 0 | %100 |
| 50 | M46 | Z | -1.764 | -1.764 | 0 | %100 |
| 51 | M47 | X | -1.019 | -1.019 | 0 | %100 |
| 52 | M47 | Z | -1.764 | -1.764 | 0 | %100 |
| 53 | M43 | X | -262 | -262 | 0 | %100 |
| 54 | M43 | Z | -453 | -453 | 0 | %100 |
| 55 | M44A | X | -1.93 | -1.93 | 0 | %100 |
| 56 | M44A | Z | -3.343 | -3.343 | 0 | %100 |

Member Distributed Loads (BLC 53 : Structure Wi (0 Deg))

| | Member Label | Direction | Start Magnitude[...] | End Magnitude[lb/ft.F,ksf] | Start Location[ft.%] | End Location[ft.%] |
|---|--------------|-----------|----------------------|----------------------------|----------------------|--------------------|
| 1 | FACE | X | 0 | 0 | 0 | %100 |
| 2 | FACE | Z | -3.035 | -3.035 | 0 | %100 |
| 3 | M2 | X | 0 | 0 | 0 | %100 |
| 4 | M2 | Z | -3.035 | -3.035 | 0 | %100 |
| 5 | M13 | X | 0 | 0 | 0 | %100 |
| 6 | M13 | Z | 0 | 0 | 0 | %100 |
| 7 | M14 | X | 0 | 0 | 0 | %100 |
| 8 | M14 | Z | 0 | 0 | 0 | %100 |

Member Distributed Loads (BLC 53 : Structure Wi (0 Deg)) (Continued)

| | Member Label | Direction | Start Magnitude[...] | End Magnitude[lb/ft.F,ksf] | Start Location[ft, %] | End Location[ft, %] |
|----|--------------|-----------|----------------------|----------------------------|-----------------------|---------------------|
| 9 | M15 | X | 0 | 0 | 0 | %100 |
| 10 | M15 | Z | 0 | 0 | 0 | %100 |
| 11 | M16 | X | 0 | 0 | 0 | %100 |
| 12 | M16 | Z | 0 | 0 | 0 | %100 |
| 13 | M17 | X | 0 | 0 | 0 | %100 |
| 14 | M17 | Z | -1.316 | -1.316 | 0 | %100 |
| 15 | M18 | X | 0 | 0 | 0 | %100 |
| 16 | M18 | Z | -1.316 | -1.316 | 0 | %100 |
| 17 | M19 | X | 0 | 0 | 0 | %100 |
| 18 | M19 | Z | -1.316 | -1.316 | 0 | %100 |
| 19 | M20 | X | 0 | 0 | 0 | %100 |
| 20 | M20 | Z | -1.316 | -1.316 | 0 | %100 |
| 21 | M21 | X | 0 | 0 | 0 | %100 |
| 22 | M21 | Z | -1.161 | -1.161 | 0 | %100 |
| 23 | M22 | X | 0 | 0 | 0 | %100 |
| 24 | M22 | Z | -1.161 | -1.161 | 0 | %100 |
| 25 | M23 | X | 0 | 0 | 0 | %100 |
| 26 | M23 | Z | -1.161 | -1.161 | 0 | %100 |
| 27 | M24 | X | 0 | 0 | 0 | %100 |
| 28 | M24 | Z | -1.161 | -1.161 | 0 | %100 |
| 29 | M25 | X | 0 | 0 | 0 | %100 |
| 30 | M25 | Z | -1.473 | -1.473 | 0 | %100 |
| 31 | M26 | X | 0 | 0 | 0 | %100 |
| 32 | M26 | Z | -1.473 | -1.473 | 0 | %100 |
| 33 | M27 | X | 0 | 0 | 0 | %100 |
| 34 | M27 | Z | -1.473 | -1.473 | 0 | %100 |
| 35 | M28 | X | 0 | 0 | 0 | %100 |
| 36 | M28 | Z | -1.473 | -1.473 | 0 | %100 |
| 37 | MP4A | X | 0 | 0 | 0 | %100 |
| 38 | MP4A | Z | -2.742 | -2.742 | 0 | %100 |
| 39 | MP3A | X | 0 | 0 | 0 | %100 |
| 40 | MP3A | Z | -2.742 | -2.742 | 0 | %100 |
| 41 | MP2A | X | 0 | 0 | 0 | %100 |
| 42 | MP2A | Z | -2.742 | -2.742 | 0 | %100 |
| 43 | MP1A | X | 0 | 0 | 0 | %100 |
| 44 | MP1A | Z | -2.742 | -2.742 | 0 | %100 |
| 45 | M44 | X | 0 | 0 | 0 | %100 |
| 46 | M44 | Z | -1.526 | -1.526 | 0 | %100 |
| 47 | M45 | X | 0 | 0 | 0 | %100 |
| 48 | M45 | Z | -1.526 | -1.526 | 0 | %100 |
| 49 | M46 | X | 0 | 0 | 0 | %100 |
| 50 | M46 | Z | -1.526 | -1.526 | 0 | %100 |
| 51 | M47 | X | 0 | 0 | 0 | %100 |
| 52 | M47 | Z | -1.526 | -1.526 | 0 | %100 |
| 53 | M43 | X | 0 | 0 | 0 | %100 |
| 54 | M43 | Z | -.182 | -.182 | 0 | %100 |
| 55 | M44A | X | 0 | 0 | 0 | %100 |
| 56 | M44A | Z | -.182 | -.182 | 0 | %100 |

Member Distributed Loads (BLC 54 : Structure Wi (30 Deg))

| | Member Label | Direction | Start Magnitude[...] | End Magnitude[lb/ft.F,ksf] | Start Location[ft, %] | End Location[ft, %] |
|---|--------------|-----------|----------------------|----------------------------|-----------------------|---------------------|
| 1 | FACE | X | 1.138 | 1.138 | 0 | %100 |
| 2 | FACE | Z | -1.971 | -1.971 | 0 | %100 |
| 3 | M2 | X | 1.138 | 1.138 | 0 | %100 |
| 4 | M2 | Z | -1.971 | -1.971 | 0 | %100 |
| 5 | M13 | X | .144 | .144 | 0 | %100 |

Member Distributed Loads (BLC 54 : Structure Wi (30 Deg)) (Continued)

| | Member Label | Direction | Start Magnitude[l...] | End Magnitude[lb/ft,F,ksf] | Start Location[ft,%] | End Location[ft,%] |
|----|--------------|-----------|-----------------------|----------------------------|----------------------|--------------------|
| 6 | M13 | Z | -.25 | -.25 | 0 | %100 |
| 7 | M14 | X | .144 | .144 | 0 | %100 |
| 8 | M14 | Z | -.25 | -.25 | 0 | %100 |
| 9 | M15 | X | .144 | .144 | 0 | %100 |
| 10 | M15 | Z | -.25 | -.25 | 0 | %100 |
| 11 | M16 | X | .144 | .144 | 0 | %100 |
| 12 | M16 | Z | -.25 | -.25 | 0 | %100 |
| 13 | M17 | X | .148 | .148 | 0 | %100 |
| 14 | M17 | Z | -.257 | -.257 | 0 | %100 |
| 15 | M18 | X | .148 | .148 | 0 | %100 |
| 16 | M18 | Z | -.257 | -.257 | 0 | %100 |
| 17 | M19 | X | 1.041 | 1.041 | 0 | %100 |
| 18 | M19 | Z | -1.802 | -1.802 | 0 | %100 |
| 19 | M20 | X | 1.041 | 1.041 | 0 | %100 |
| 20 | M20 | Z | -1.802 | -1.802 | 0 | %100 |
| 21 | M21 | X | .435 | .435 | 0 | %100 |
| 22 | M21 | Z | -.754 | -.754 | 0 | %100 |
| 23 | M22 | X | .435 | .435 | 0 | %100 |
| 24 | M22 | Z | -.754 | -.754 | 0 | %100 |
| 25 | M23 | X | .435 | .435 | 0 | %100 |
| 26 | M23 | Z | -.754 | -.754 | 0 | %100 |
| 27 | M24 | X | .435 | .435 | 0 | %100 |
| 28 | M24 | Z | -.754 | -.754 | 0 | %100 |
| 29 | M25 | X | .589 | .589 | 0 | %100 |
| 30 | M25 | Z | -1.02 | -1.02 | 0 | %100 |
| 31 | M26 | X | .589 | .589 | 0 | %100 |
| 32 | M26 | Z | -1.02 | -1.02 | 0 | %100 |
| 33 | M27 | X | .847 | .847 | 0 | %100 |
| 34 | M27 | Z | -1.468 | -1.468 | 0 | %100 |
| 35 | M28 | X | .847 | .847 | 0 | %100 |
| 36 | M28 | Z | -1.468 | -1.468 | 0 | %100 |
| 37 | MP4A | X | 1.371 | 1.371 | 0 | %100 |
| 38 | MP4A | Z | -2.375 | -2.375 | 0 | %100 |
| 39 | MP3A | X | 1.371 | 1.371 | 0 | %100 |
| 40 | MP3A | Z | -2.375 | -2.375 | 0 | %100 |
| 41 | MP2A | X | 1.371 | 1.371 | 0 | %100 |
| 42 | MP2A | Z | -2.375 | -2.375 | 0 | %100 |
| 43 | MP1A | X | 1.371 | 1.371 | 0 | %100 |
| 44 | MP1A | Z | -2.375 | -2.375 | 0 | %100 |
| 45 | M44 | X | .763 | .763 | 0 | %100 |
| 46 | M44 | Z | -1.321 | -1.321 | 0 | %100 |
| 47 | M45 | X | .763 | .763 | 0 | %100 |
| 48 | M45 | Z | -1.321 | -1.321 | 0 | %100 |
| 49 | M46 | X | .763 | .763 | 0 | %100 |
| 50 | M46 | Z | -1.321 | -1.321 | 0 | %100 |
| 51 | M47 | X | .763 | .763 | 0 | %100 |
| 52 | M47 | Z | -1.321 | -1.321 | 0 | %100 |
| 53 | M43 | X | .684 | .684 | 0 | %100 |
| 54 | M43 | Z | -1.184 | -1.184 | 0 | %100 |
| 55 | M44A | X | .093 | .093 | 0 | %100 |
| 56 | M44A | Z | -.161 | -.161 | 0 | %100 |

Member Distributed Loads (BLC 55 : Structure Wi (60 Deg))

| | Member Label | Direction | Start Magnitude[l...] | End Magnitude[lb/ft,F,ksf] | Start Location[ft,%] | End Location[ft,%] |
|---|--------------|-----------|-----------------------|----------------------------|----------------------|--------------------|
| 1 | FACE | X | .657 | .657 | 0 | %100 |
| 2 | FACE | Z | -.379 | -.379 | 0 | %100 |



Company :
 Designer :
 Job Number :
 Model Name :

Apr 12, 2022
 10:37 AM
 Checked By: _____

Member Distributed Loads (BLC 55 : Structure Wi (60 Deg)) (Continued)

| Member Label | Direction | Start Magnitude[...] | End Magnitude[lb/ft,F,ksf] | Start Location[ft,%] | End Location[ft,%] |
|--------------|-----------|----------------------|----------------------------|----------------------|--------------------|
| 3 | M2 | X | .657 | .657 | 0 %100 |
| 4 | M2 | Z | -.379 | -.379 | 0 %100 |
| 5 | M13 | X | .75 | .75 | 0 %100 |
| 6 | M13 | Z | -.433 | -.433 | 0 %100 |
| 7 | M14 | X | .75 | .75 | 0 %100 |
| 8 | M14 | Z | -.433 | -.433 | 0 %100 |
| 9 | M15 | X | .75 | .75 | 0 %100 |
| 10 | M15 | Z | -.433 | -.433 | 0 %100 |
| 11 | M16 | X | .75 | .75 | 0 %100 |
| 12 | M16 | Z | -.433 | -.433 | 0 %100 |
| 13 | M17 | X | .036 | .036 | 0 %100 |
| 14 | M17 | Z | -.021 | -.021 | 0 %100 |
| 15 | M18 | X | .036 | .036 | 0 %100 |
| 16 | M18 | Z | -.021 | -.021 | 0 %100 |
| 17 | M19 | X | 1.582 | 1.582 | 0 %100 |
| 18 | M19 | Z | -.913 | -.913 | 0 %100 |
| 19 | M20 | X | 1.582 | 1.582 | 0 %100 |
| 20 | M20 | Z | -.913 | -.913 | 0 %100 |
| 21 | M21 | X | .251 | .251 | 0 %100 |
| 22 | M21 | Z | -.145 | -.145 | 0 %100 |
| 23 | M22 | X | .251 | .251 | 0 %100 |
| 24 | M22 | Z | -.145 | -.145 | 0 %100 |
| 25 | M23 | X | .251 | .251 | 0 %100 |
| 26 | M23 | Z | -.145 | -.145 | 0 %100 |
| 27 | M24 | X | .251 | .251 | 0 %100 |
| 28 | M24 | Z | -.145 | -.145 | 0 %100 |
| 29 | M25 | X | .956 | .956 | 0 %100 |
| 30 | M25 | Z | -.552 | -.552 | 0 %100 |
| 31 | M26 | X | .956 | .956 | 0 %100 |
| 32 | M26 | Z | -.552 | -.552 | 0 %100 |
| 33 | M27 | X | 1.404 | 1.404 | 0 %100 |
| 34 | M27 | Z | -.811 | -.811 | 0 %100 |
| 35 | M28 | X | 1.404 | 1.404 | 0 %100 |
| 36 | M28 | Z | -.811 | -.811 | 0 %100 |
| 37 | MP4A | X | 2.375 | 2.375 | 0 %100 |
| 38 | MP4A | Z | -1.371 | -1.371 | 0 %100 |
| 39 | MP3A | X | 2.375 | 2.375 | 0 %100 |
| 40 | MP3A | Z | -1.371 | -1.371 | 0 %100 |
| 41 | MP2A | X | 2.375 | 2.375 | 0 %100 |
| 42 | MP2A | Z | -1.371 | -1.371 | 0 %100 |
| 43 | MP1A | X | 2.375 | 2.375 | 0 %100 |
| 44 | MP1A | Z | -1.371 | -1.371 | 0 %100 |
| 45 | M44 | X | 1.321 | 1.321 | 0 %100 |
| 46 | M44 | Z | -.763 | -.763 | 0 %100 |
| 47 | M45 | X | 1.321 | 1.321 | 0 %100 |
| 48 | M45 | Z | -.763 | -.763 | 0 %100 |
| 49 | M46 | X | 1.321 | 1.321 | 0 %100 |
| 50 | M46 | Z | -.763 | -.763 | 0 %100 |
| 51 | M47 | X | 1.321 | 1.321 | 0 %100 |
| 52 | M47 | Z | -.763 | -.763 | 0 %100 |
| 53 | M43 | X | 2.214 | 2.214 | 0 %100 |
| 54 | M43 | Z | -1.278 | -1.278 | 0 %100 |
| 55 | M44A | X | 1.191 | 1.191 | 0 %100 |
| 56 | M44A | Z | -.687 | -.687 | 0 %100 |

Member Distributed Loads (BLC 56 : Structure Wi (90 Deg))

| Member Label | Direction | Start Magnitude[...] | End Magnitude[lb/ft,F,ksf] | Start Location[ft,%] | End Location[ft,%] |
|--------------|-----------|----------------------|----------------------------|----------------------|--------------------|
|--------------|-----------|----------------------|----------------------------|----------------------|--------------------|

Member Distributed Loads (BLC 56 : Structure Wi (90 Deg)) (Continued)

| | Member Label | Direction | Start Magnitude[...] | End Magnitude[lb/ft,F,ksf] | Start Location[ft,%] | End Location[ft,%] |
|----|--------------|-----------|----------------------|----------------------------|----------------------|--------------------|
| 1 | FACE | X | 0 | 0 | 0 | %100 |
| 2 | FACE | Z | 0 | 0 | 0 | %100 |
| 3 | M2 | X | 0 | 0 | 0 | %100 |
| 4 | M2 | Z | 0 | 0 | 0 | %100 |
| 5 | M13 | X | 1.155 | 1.155 | 0 | %100 |
| 6 | M13 | Z | 0 | 0 | 0 | %100 |
| 7 | M14 | X | 1.155 | 1.155 | 0 | %100 |
| 8 | M14 | Z | 0 | 0 | 0 | %100 |
| 9 | M15 | X | 1.155 | 1.155 | 0 | %100 |
| 10 | M15 | Z | 0 | 0 | 0 | %100 |
| 11 | M16 | X | 1.155 | 1.155 | 0 | %100 |
| 12 | M16 | Z | 0 | 0 | 0 | %100 |
| 13 | M17 | X | .807 | .807 | 0 | %100 |
| 14 | M17 | Z | 0 | 0 | 0 | %100 |
| 15 | M18 | X | .807 | .807 | 0 | %100 |
| 16 | M18 | Z | 0 | 0 | 0 | %100 |
| 17 | M19 | X | .807 | .807 | 0 | %100 |
| 18 | M19 | Z | 0 | 0 | 0 | %100 |
| 19 | M20 | X | .807 | .807 | 0 | %100 |
| 20 | M20 | Z | 0 | 0 | 0 | %100 |
| 21 | M21 | X | 0 | 0 | 0 | %100 |
| 22 | M21 | Z | 0 | 0 | 0 | %100 |
| 23 | M22 | X | 0 | 0 | 0 | %100 |
| 24 | M22 | Z | 0 | 0 | 0 | %100 |
| 25 | M23 | X | 0 | 0 | 0 | %100 |
| 26 | M23 | Z | 0 | 0 | 0 | %100 |
| 27 | M24 | X | 0 | 0 | 0 | %100 |
| 28 | M24 | Z | 0 | 0 | 0 | %100 |
| 29 | M25 | X | 1.326 | 1.326 | 0 | %100 |
| 30 | M25 | Z | 0 | 0 | 0 | %100 |
| 31 | M26 | X | 1.326 | 1.326 | 0 | %100 |
| 32 | M26 | Z | 0 | 0 | 0 | %100 |
| 33 | M27 | X | 1.326 | 1.326 | 0 | %100 |
| 34 | M27 | Z | 0 | 0 | 0 | %100 |
| 35 | M28 | X | 1.326 | 1.326 | 0 | %100 |
| 36 | M28 | Z | 0 | 0 | 0 | %100 |
| 37 | MP4A | X | 2.742 | 2.742 | 0 | %100 |
| 38 | MP4A | Z | 0 | 0 | 0 | %100 |
| 39 | MP3A | X | 2.742 | 2.742 | 0 | %100 |
| 40 | MP3A | Z | 0 | 0 | 0 | %100 |
| 41 | MP2A | X | 2.742 | 2.742 | 0 | %100 |
| 42 | MP2A | Z | 0 | 0 | 0 | %100 |
| 43 | MP1A | X | 2.742 | 2.742 | 0 | %100 |
| 44 | MP1A | Z | 0 | 0 | 0 | %100 |
| 45 | M44 | X | 1.526 | 1.526 | 0 | %100 |
| 46 | M44 | Z | 0 | 0 | 0 | %100 |
| 47 | M45 | X | 1.526 | 1.526 | 0 | %100 |
| 48 | M45 | Z | 0 | 0 | 0 | %100 |
| 49 | M46 | X | 1.526 | 1.526 | 0 | %100 |
| 50 | M46 | Z | 0 | 0 | 0 | %100 |
| 51 | M47 | X | 1.526 | 1.526 | 0 | %100 |
| 52 | M47 | Z | 0 | 0 | 0 | %100 |
| 53 | M43 | X | 2.56 | 2.56 | 0 | %100 |
| 54 | M43 | Z | 0 | 0 | 0 | %100 |
| 55 | M44A | X | 2.56 | 2.56 | 0 | %100 |
| 56 | M44A | Z | 0 | 0 | 0 | %100 |



Company :
 Designer :
 Job Number :
 Model Name :

Apr 12, 2022
 10:37 AM
 Checked By: _____

Member Distributed Loads (BLC 57 : Structure Wi (120 Deg))

| Member Label | Direction | Start Magnitude[...] | End Magnitude[lb/ft,F,ksf] | Start Location[ft,%] | End Location[ft,%] |
|--------------|-----------|----------------------|----------------------------|----------------------|--------------------|
| 1 | FACE | X | .657 | .657 | 0 %100 |
| 2 | FACE | Z | .379 | .379 | 0 %100 |
| 3 | M2 | X | .657 | .657 | 0 %100 |
| 4 | M2 | Z | .379 | .379 | 0 %100 |
| 5 | M13 | X | .75 | .75 | 0 %100 |
| 6 | M13 | Z | .433 | .433 | 0 %100 |
| 7 | M14 | X | .75 | .75 | 0 %100 |
| 8 | M14 | Z | .433 | .433 | 0 %100 |
| 9 | M15 | X | .75 | .75 | 0 %100 |
| 10 | M15 | Z | .433 | .433 | 0 %100 |
| 11 | M16 | X | .75 | .75 | 0 %100 |
| 12 | M16 | Z | .433 | .433 | 0 %100 |
| 13 | M17 | X | 1.582 | 1.582 | 0 %100 |
| 14 | M17 | Z | .913 | .913 | 0 %100 |
| 15 | M18 | X | 1.582 | 1.582 | 0 %100 |
| 16 | M18 | Z | .913 | .913 | 0 %100 |
| 17 | M19 | X | .036 | .036 | 0 %100 |
| 18 | M19 | Z | .021 | .021 | 0 %100 |
| 19 | M20 | X | .036 | .036 | 0 %100 |
| 20 | M20 | Z | .021 | .021 | 0 %100 |
| 21 | M21 | X | .251 | .251 | 0 %100 |
| 22 | M21 | Z | .145 | .145 | 0 %100 |
| 23 | M22 | X | .251 | .251 | 0 %100 |
| 24 | M22 | Z | .145 | .145 | 0 %100 |
| 25 | M23 | X | .251 | .251 | 0 %100 |
| 26 | M23 | Z | .145 | .145 | 0 %100 |
| 27 | M24 | X | .251 | .251 | 0 %100 |
| 28 | M24 | Z | .145 | .145 | 0 %100 |
| 29 | M25 | X | 1.404 | 1.404 | 0 %100 |
| 30 | M25 | Z | .811 | .811 | 0 %100 |
| 31 | M26 | X | 1.404 | 1.404 | 0 %100 |
| 32 | M26 | Z | .811 | .811 | 0 %100 |
| 33 | M27 | X | .956 | .956 | 0 %100 |
| 34 | M27 | Z | .552 | .552 | 0 %100 |
| 35 | M28 | X | .956 | .956 | 0 %100 |
| 36 | M28 | Z | .552 | .552 | 0 %100 |
| 37 | MP4A | X | 2.375 | 2.375 | 0 %100 |
| 38 | MP4A | Z | 1.371 | 1.371 | 0 %100 |
| 39 | MP3A | X | 2.375 | 2.375 | 0 %100 |
| 40 | MP3A | Z | 1.371 | 1.371 | 0 %100 |
| 41 | MP2A | X | 2.375 | 2.375 | 0 %100 |
| 42 | MP2A | Z | 1.371 | 1.371 | 0 %100 |
| 43 | MP1A | X | 2.375 | 2.375 | 0 %100 |
| 44 | MP1A | Z | 1.371 | 1.371 | 0 %100 |
| 45 | M44 | X | 1.321 | 1.321 | 0 %100 |
| 46 | M44 | Z | .763 | .763 | 0 %100 |
| 47 | M45 | X | 1.321 | 1.321 | 0 %100 |
| 48 | M45 | Z | .763 | .763 | 0 %100 |
| 49 | M46 | X | 1.321 | 1.321 | 0 %100 |
| 50 | M46 | Z | .763 | .763 | 0 %100 |
| 51 | M47 | X | 1.321 | 1.321 | 0 %100 |
| 52 | M47 | Z | .763 | .763 | 0 %100 |
| 53 | M43 | X | 1.191 | 1.191 | 0 %100 |
| 54 | M43 | Z | .687 | .687 | 0 %100 |
| 55 | M44A | X | 2.214 | 2.214 | 0 %100 |
| 56 | M44A | Z | 1.278 | 1.278 | 0 %100 |



Company :
 Designer :
 Job Number :
 Model Name :

Apr 12, 2022
 10:37 AM
 Checked By: _____

Member Distributed Loads (BLC 58 : Structure Wi (150 Deg))

| Member Label | Direction | Start Magnitude[...] | End Magnitude[lb/ft,F,ksf] | Start Location[ft,%] | End Location[ft,%] |
|--------------|-----------|----------------------|----------------------------|----------------------|--------------------|
| 1 | FACE | X | 1.138 | 1.138 | 0 %100 |
| 2 | FACE | Z | 1.971 | 1.971 | 0 %100 |
| 3 | M2 | X | 1.138 | 1.138 | 0 %100 |
| 4 | M2 | Z | 1.971 | 1.971 | 0 %100 |
| 5 | M13 | X | .144 | .144 | 0 %100 |
| 6 | M13 | Z | .25 | .25 | 0 %100 |
| 7 | M14 | X | .144 | .144 | 0 %100 |
| 8 | M14 | Z | .25 | .25 | 0 %100 |
| 9 | M15 | X | .144 | .144 | 0 %100 |
| 10 | M15 | Z | .25 | .25 | 0 %100 |
| 11 | M16 | X | .144 | .144 | 0 %100 |
| 12 | M16 | Z | .25 | .25 | 0 %100 |
| 13 | M17 | X | 1.041 | 1.041 | 0 %100 |
| 14 | M17 | Z | 1.802 | 1.802 | 0 %100 |
| 15 | M18 | X | 1.041 | 1.041 | 0 %100 |
| 16 | M18 | Z | 1.802 | 1.802 | 0 %100 |
| 17 | M19 | X | .148 | .148 | 0 %100 |
| 18 | M19 | Z | .257 | .257 | 0 %100 |
| 19 | M20 | X | .148 | .148 | 0 %100 |
| 20 | M20 | Z | .257 | .257 | 0 %100 |
| 21 | M21 | X | .435 | .435 | 0 %100 |
| 22 | M21 | Z | .754 | .754 | 0 %100 |
| 23 | M22 | X | .435 | .435 | 0 %100 |
| 24 | M22 | Z | .754 | .754 | 0 %100 |
| 25 | M23 | X | .435 | .435 | 0 %100 |
| 26 | M23 | Z | .754 | .754 | 0 %100 |
| 27 | M24 | X | .435 | .435 | 0 %100 |
| 28 | M24 | Z | .754 | .754 | 0 %100 |
| 29 | M25 | X | .847 | .847 | 0 %100 |
| 30 | M25 | Z | 1.468 | 1.468 | 0 %100 |
| 31 | M26 | X | .847 | .847 | 0 %100 |
| 32 | M26 | Z | 1.468 | 1.468 | 0 %100 |
| 33 | M27 | X | .589 | .589 | 0 %100 |
| 34 | M27 | Z | 1.02 | 1.02 | 0 %100 |
| 35 | M28 | X | .589 | .589 | 0 %100 |
| 36 | M28 | Z | 1.02 | 1.02 | 0 %100 |
| 37 | MP4A | X | 1.371 | 1.371 | 0 %100 |
| 38 | MP4A | Z | 2.375 | 2.375 | 0 %100 |
| 39 | MP3A | X | 1.371 | 1.371 | 0 %100 |
| 40 | MP3A | Z | 2.375 | 2.375 | 0 %100 |
| 41 | MP2A | X | 1.371 | 1.371 | 0 %100 |
| 42 | MP2A | Z | 2.375 | 2.375 | 0 %100 |
| 43 | MP1A | X | 1.371 | 1.371 | 0 %100 |
| 44 | MP1A | Z | 2.375 | 2.375 | 0 %100 |
| 45 | M44 | X | .763 | .763 | 0 %100 |
| 46 | M44 | Z | 1.321 | 1.321 | 0 %100 |
| 47 | M45 | X | .763 | .763 | 0 %100 |
| 48 | M45 | Z | 1.321 | 1.321 | 0 %100 |
| 49 | M46 | X | .763 | .763 | 0 %100 |
| 50 | M46 | Z | 1.321 | 1.321 | 0 %100 |
| 51 | M47 | X | .763 | .763 | 0 %100 |
| 52 | M47 | Z | 1.321 | 1.321 | 0 %100 |
| 53 | M43 | X | .093 | .093 | 0 %100 |
| 54 | M43 | Z | .161 | .161 | 0 %100 |
| 55 | M44A | X | .684 | .684 | 0 %100 |
| 56 | M44A | Z | 1.184 | 1.184 | 0 %100 |



Company :
 Designer :
 Job Number :
 Model Name :

Apr 12, 2022
 10:37 AM
 Checked By: _____

Member Distributed Loads (BLC 59 : Structure Wi (180 Deg))

| | Member Label | Direction | Start Magnitude[...] | End Magnitude[lb/ft,F,ksf] | Start Location[ft,%] | End Location[ft,%] |
|----|--------------|-----------|----------------------|----------------------------|----------------------|--------------------|
| 1 | FACE | X | 0 | 0 | 0 | %100 |
| 2 | FACE | Z | 3.035 | 3.035 | 0 | %100 |
| 3 | M2 | X | 0 | 0 | 0 | %100 |
| 4 | M2 | Z | 3.035 | 3.035 | 0 | %100 |
| 5 | M13 | X | 0 | 0 | 0 | %100 |
| 6 | M13 | Z | 0 | 0 | 0 | %100 |
| 7 | M14 | X | 0 | 0 | 0 | %100 |
| 8 | M14 | Z | 0 | 0 | 0 | %100 |
| 9 | M15 | X | 0 | 0 | 0 | %100 |
| 10 | M15 | Z | 0 | 0 | 0 | %100 |
| 11 | M16 | X | 0 | 0 | 0 | %100 |
| 12 | M16 | Z | 0 | 0 | 0 | %100 |
| 13 | M17 | X | 0 | 0 | 0 | %100 |
| 14 | M17 | Z | 1.316 | 1.316 | 0 | %100 |
| 15 | M18 | X | 0 | 0 | 0 | %100 |
| 16 | M18 | Z | 1.316 | 1.316 | 0 | %100 |
| 17 | M19 | X | 0 | 0 | 0 | %100 |
| 18 | M19 | Z | 1.316 | 1.316 | 0 | %100 |
| 19 | M20 | X | 0 | 0 | 0 | %100 |
| 20 | M20 | Z | 1.316 | 1.316 | 0 | %100 |
| 21 | M21 | X | 0 | 0 | 0 | %100 |
| 22 | M21 | Z | 1.161 | 1.161 | 0 | %100 |
| 23 | M22 | X | 0 | 0 | 0 | %100 |
| 24 | M22 | Z | 1.161 | 1.161 | 0 | %100 |
| 25 | M23 | X | 0 | 0 | 0 | %100 |
| 26 | M23 | Z | 1.161 | 1.161 | 0 | %100 |
| 27 | M24 | X | 0 | 0 | 0 | %100 |
| 28 | M24 | Z | 1.161 | 1.161 | 0 | %100 |
| 29 | M25 | X | 0 | 0 | 0 | %100 |
| 30 | M25 | Z | 1.473 | 1.473 | 0 | %100 |
| 31 | M26 | X | 0 | 0 | 0 | %100 |
| 32 | M26 | Z | 1.473 | 1.473 | 0 | %100 |
| 33 | M27 | X | 0 | 0 | 0 | %100 |
| 34 | M27 | Z | 1.473 | 1.473 | 0 | %100 |
| 35 | M28 | X | 0 | 0 | 0 | %100 |
| 36 | M28 | Z | 1.473 | 1.473 | 0 | %100 |
| 37 | MP4A | X | 0 | 0 | 0 | %100 |
| 38 | MP4A | Z | 2.742 | 2.742 | 0 | %100 |
| 39 | MP3A | X | 0 | 0 | 0 | %100 |
| 40 | MP3A | Z | 2.742 | 2.742 | 0 | %100 |
| 41 | MP2A | X | 0 | 0 | 0 | %100 |
| 42 | MP2A | Z | 2.742 | 2.742 | 0 | %100 |
| 43 | MP1A | X | 0 | 0 | 0 | %100 |
| 44 | MP1A | Z | 2.742 | 2.742 | 0 | %100 |
| 45 | M44 | X | 0 | 0 | 0 | %100 |
| 46 | M44 | Z | 1.526 | 1.526 | 0 | %100 |
| 47 | M45 | X | 0 | 0 | 0 | %100 |
| 48 | M45 | Z | 1.526 | 1.526 | 0 | %100 |
| 49 | M46 | X | 0 | 0 | 0 | %100 |
| 50 | M46 | Z | 1.526 | 1.526 | 0 | %100 |
| 51 | M47 | X | 0 | 0 | 0 | %100 |
| 52 | M47 | Z | 1.526 | 1.526 | 0 | %100 |
| 53 | M43 | X | 0 | 0 | 0 | %100 |
| 54 | M43 | Z | .182 | .182 | 0 | %100 |
| 55 | M44A | X | 0 | 0 | 0 | %100 |
| 56 | M44A | Z | .182 | .182 | 0 | %100 |



Company :
 Designer :
 Job Number :
 Model Name :

Apr 12, 2022
 10:37 AM
 Checked By: _____

Member Distributed Loads (BLC 60 : Structure Wi (210 Deg))

| Member Label | Direction | Start Magnitude[...] | End Magnitude[lb/ft,F,ksf] | Start Location[ft,%] | End Location[ft,%] |
|--------------|-----------|----------------------|----------------------------|----------------------|--------------------|
| 1 | FACE | X | -1.138 | -1.138 | 0 %100 |
| 2 | FACE | Z | 1.971 | 1.971 | 0 %100 |
| 3 | M2 | X | -1.138 | -1.138 | 0 %100 |
| 4 | M2 | Z | 1.971 | 1.971 | 0 %100 |
| 5 | M13 | X | -.144 | -.144 | 0 %100 |
| 6 | M13 | Z | .25 | .25 | 0 %100 |
| 7 | M14 | X | -.144 | -.144 | 0 %100 |
| 8 | M14 | Z | .25 | .25 | 0 %100 |
| 9 | M15 | X | -.144 | -.144 | 0 %100 |
| 10 | M15 | Z | .25 | .25 | 0 %100 |
| 11 | M16 | X | -.144 | -.144 | 0 %100 |
| 12 | M16 | Z | .25 | .25 | 0 %100 |
| 13 | M17 | X | -.148 | -.148 | 0 %100 |
| 14 | M17 | Z | .257 | .257 | 0 %100 |
| 15 | M18 | X | -.148 | -.148 | 0 %100 |
| 16 | M18 | Z | .257 | .257 | 0 %100 |
| 17 | M19 | X | -1.041 | -1.041 | 0 %100 |
| 18 | M19 | Z | 1.802 | 1.802 | 0 %100 |
| 19 | M20 | X | -1.041 | -1.041 | 0 %100 |
| 20 | M20 | Z | 1.802 | 1.802 | 0 %100 |
| 21 | M21 | X | -.435 | -.435 | 0 %100 |
| 22 | M21 | Z | .754 | .754 | 0 %100 |
| 23 | M22 | X | -.435 | -.435 | 0 %100 |
| 24 | M22 | Z | .754 | .754 | 0 %100 |
| 25 | M23 | X | -.435 | -.435 | 0 %100 |
| 26 | M23 | Z | .754 | .754 | 0 %100 |
| 27 | M24 | X | -.435 | -.435 | 0 %100 |
| 28 | M24 | Z | .754 | .754 | 0 %100 |
| 29 | M25 | X | -.589 | -.589 | 0 %100 |
| 30 | M25 | Z | 1.02 | 1.02 | 0 %100 |
| 31 | M26 | X | -.589 | -.589 | 0 %100 |
| 32 | M26 | Z | 1.02 | 1.02 | 0 %100 |
| 33 | M27 | X | -.847 | -.847 | 0 %100 |
| 34 | M27 | Z | 1.468 | 1.468 | 0 %100 |
| 35 | M28 | X | -.847 | -.847 | 0 %100 |
| 36 | M28 | Z | 1.468 | 1.468 | 0 %100 |
| 37 | MP4A | X | -1.371 | -1.371 | 0 %100 |
| 38 | MP4A | Z | 2.375 | 2.375 | 0 %100 |
| 39 | MP3A | X | -1.371 | -1.371 | 0 %100 |
| 40 | MP3A | Z | 2.375 | 2.375 | 0 %100 |
| 41 | MP2A | X | -1.371 | -1.371 | 0 %100 |
| 42 | MP2A | Z | 2.375 | 2.375 | 0 %100 |
| 43 | MP1A | X | -1.371 | -1.371 | 0 %100 |
| 44 | MP1A | Z | 2.375 | 2.375 | 0 %100 |
| 45 | M44 | X | -.763 | -.763 | 0 %100 |
| 46 | M44 | Z | 1.321 | 1.321 | 0 %100 |
| 47 | M45 | X | -.763 | -.763 | 0 %100 |
| 48 | M45 | Z | 1.321 | 1.321 | 0 %100 |
| 49 | M46 | X | -.763 | -.763 | 0 %100 |
| 50 | M46 | Z | 1.321 | 1.321 | 0 %100 |
| 51 | M47 | X | -.763 | -.763 | 0 %100 |
| 52 | M47 | Z | 1.321 | 1.321 | 0 %100 |
| 53 | M43 | X | -.684 | -.684 | 0 %100 |
| 54 | M43 | Z | 1.184 | 1.184 | 0 %100 |
| 55 | M44A | X | -.093 | -.093 | 0 %100 |
| 56 | M44A | Z | .161 | .161 | 0 %100 |



Company :
 Designer :
 Job Number :
 Model Name :

Apr 12, 2022
 10:37 AM
 Checked By: _____

Member Distributed Loads (BLC 61 : Structure Wi (240 Deg))

| Member Label | Direction | Start Magnitude[...] | End Magnitude[lb/ft,F,ksf] | Start Location[ft,%] | End Location[ft,%] |
|--------------|-----------|----------------------|----------------------------|----------------------|--------------------|
| 1 | FACE | X | -.657 | -.657 | 0 %100 |
| 2 | FACE | Z | .379 | .379 | 0 %100 |
| 3 | M2 | X | -.657 | -.657 | 0 %100 |
| 4 | M2 | Z | .379 | .379 | 0 %100 |
| 5 | M13 | X | -.75 | -.75 | 0 %100 |
| 6 | M13 | Z | .433 | .433 | 0 %100 |
| 7 | M14 | X | -.75 | -.75 | 0 %100 |
| 8 | M14 | Z | .433 | .433 | 0 %100 |
| 9 | M15 | X | -.75 | -.75 | 0 %100 |
| 10 | M15 | Z | .433 | .433 | 0 %100 |
| 11 | M16 | X | -.75 | -.75 | 0 %100 |
| 12 | M16 | Z | .433 | .433 | 0 %100 |
| 13 | M17 | X | -.036 | -.036 | 0 %100 |
| 14 | M17 | Z | .021 | .021 | 0 %100 |
| 15 | M18 | X | -.036 | -.036 | 0 %100 |
| 16 | M18 | Z | .021 | .021 | 0 %100 |
| 17 | M19 | X | -1.582 | -1.582 | 0 %100 |
| 18 | M19 | Z | .913 | .913 | 0 %100 |
| 19 | M20 | X | -1.582 | -1.582 | 0 %100 |
| 20 | M20 | Z | .913 | .913 | 0 %100 |
| 21 | M21 | X | -.251 | -.251 | 0 %100 |
| 22 | M21 | Z | .145 | .145 | 0 %100 |
| 23 | M22 | X | -.251 | -.251 | 0 %100 |
| 24 | M22 | Z | .145 | .145 | 0 %100 |
| 25 | M23 | X | -.251 | -.251 | 0 %100 |
| 26 | M23 | Z | .145 | .145 | 0 %100 |
| 27 | M24 | X | -.251 | -.251 | 0 %100 |
| 28 | M24 | Z | .145 | .145 | 0 %100 |
| 29 | M25 | X | -.956 | -.956 | 0 %100 |
| 30 | M25 | Z | .552 | .552 | 0 %100 |
| 31 | M26 | X | -.956 | -.956 | 0 %100 |
| 32 | M26 | Z | .552 | .552 | 0 %100 |
| 33 | M27 | X | -1.404 | -1.404 | 0 %100 |
| 34 | M27 | Z | .811 | .811 | 0 %100 |
| 35 | M28 | X | -1.404 | -1.404 | 0 %100 |
| 36 | M28 | Z | .811 | .811 | 0 %100 |
| 37 | MP4A | X | -2.375 | -2.375 | 0 %100 |
| 38 | MP4A | Z | 1.371 | 1.371 | 0 %100 |
| 39 | MP3A | X | -2.375 | -2.375 | 0 %100 |
| 40 | MP3A | Z | 1.371 | 1.371 | 0 %100 |
| 41 | MP2A | X | -2.375 | -2.375 | 0 %100 |
| 42 | MP2A | Z | 1.371 | 1.371 | 0 %100 |
| 43 | MP1A | X | -2.375 | -2.375 | 0 %100 |
| 44 | MP1A | Z | 1.371 | 1.371 | 0 %100 |
| 45 | M44 | X | -1.321 | -1.321 | 0 %100 |
| 46 | M44 | Z | .763 | .763 | 0 %100 |
| 47 | M45 | X | -1.321 | -1.321 | 0 %100 |
| 48 | M45 | Z | .763 | .763 | 0 %100 |
| 49 | M46 | X | -1.321 | -1.321 | 0 %100 |
| 50 | M46 | Z | .763 | .763 | 0 %100 |
| 51 | M47 | X | -1.321 | -1.321 | 0 %100 |
| 52 | M47 | Z | .763 | .763 | 0 %100 |
| 53 | M43 | X | -2.214 | -2.214 | 0 %100 |
| 54 | M43 | Z | 1.278 | 1.278 | 0 %100 |
| 55 | M44A | X | -1.191 | -1.191 | 0 %100 |
| 56 | M44A | Z | .687 | .687 | 0 %100 |

Member Distributed Loads (BLC 62 : Structure Wi (270 Deg))

| | Member Label | Direction | Start Magnitude[...] | End Magnitude[lb/ft,F,ksf] | Start Location[ft,%] | End Location[ft,%] |
|----|--------------|-----------|----------------------|----------------------------|----------------------|--------------------|
| 1 | FACE | X | 0 | 0 | 0 | %100 |
| 2 | FACE | Z | 0 | 0 | 0 | %100 |
| 3 | M2 | X | 0 | 0 | 0 | %100 |
| 4 | M2 | Z | 0 | 0 | 0 | %100 |
| 5 | M13 | X | -1.155 | -1.155 | 0 | %100 |
| 6 | M13 | Z | 0 | 0 | 0 | %100 |
| 7 | M14 | X | -1.155 | -1.155 | 0 | %100 |
| 8 | M14 | Z | 0 | 0 | 0 | %100 |
| 9 | M15 | X | -1.155 | -1.155 | 0 | %100 |
| 10 | M15 | Z | 0 | 0 | 0 | %100 |
| 11 | M16 | X | -1.155 | -1.155 | 0 | %100 |
| 12 | M16 | Z | 0 | 0 | 0 | %100 |
| 13 | M17 | X | -807 | -807 | 0 | %100 |
| 14 | M17 | Z | 0 | 0 | 0 | %100 |
| 15 | M18 | X | -807 | -807 | 0 | %100 |
| 16 | M18 | Z | 0 | 0 | 0 | %100 |
| 17 | M19 | X | -807 | -807 | 0 | %100 |
| 18 | M19 | Z | 0 | 0 | 0 | %100 |
| 19 | M20 | X | -807 | -807 | 0 | %100 |
| 20 | M20 | Z | 0 | 0 | 0 | %100 |
| 21 | M21 | X | 0 | 0 | 0 | %100 |
| 22 | M21 | Z | 0 | 0 | 0 | %100 |
| 23 | M22 | X | 0 | 0 | 0 | %100 |
| 24 | M22 | Z | 0 | 0 | 0 | %100 |
| 25 | M23 | X | 0 | 0 | 0 | %100 |
| 26 | M23 | Z | 0 | 0 | 0 | %100 |
| 27 | M24 | X | 0 | 0 | 0 | %100 |
| 28 | M24 | Z | 0 | 0 | 0 | %100 |
| 29 | M25 | X | -1.326 | -1.326 | 0 | %100 |
| 30 | M25 | Z | 0 | 0 | 0 | %100 |
| 31 | M26 | X | -1.326 | -1.326 | 0 | %100 |
| 32 | M26 | Z | 0 | 0 | 0 | %100 |
| 33 | M27 | X | -1.326 | -1.326 | 0 | %100 |
| 34 | M27 | Z | 0 | 0 | 0 | %100 |
| 35 | M28 | X | -1.326 | -1.326 | 0 | %100 |
| 36 | M28 | Z | 0 | 0 | 0 | %100 |
| 37 | MP4A | X | -2.742 | -2.742 | 0 | %100 |
| 38 | MP4A | Z | 0 | 0 | 0 | %100 |
| 39 | MP3A | X | -2.742 | -2.742 | 0 | %100 |
| 40 | MP3A | Z | 0 | 0 | 0 | %100 |
| 41 | MP2A | X | -2.742 | -2.742 | 0 | %100 |
| 42 | MP2A | Z | 0 | 0 | 0 | %100 |
| 43 | MP1A | X | -2.742 | -2.742 | 0 | %100 |
| 44 | MP1A | Z | 0 | 0 | 0 | %100 |
| 45 | M44 | X | -1.526 | -1.526 | 0 | %100 |
| 46 | M44 | Z | 0 | 0 | 0 | %100 |
| 47 | M45 | X | -1.526 | -1.526 | 0 | %100 |
| 48 | M45 | Z | 0 | 0 | 0 | %100 |
| 49 | M46 | X | -1.526 | -1.526 | 0 | %100 |
| 50 | M46 | Z | 0 | 0 | 0 | %100 |
| 51 | M47 | X | -1.526 | -1.526 | 0 | %100 |
| 52 | M47 | Z | 0 | 0 | 0 | %100 |
| 53 | M43 | X | -2.56 | -2.56 | 0 | %100 |
| 54 | M43 | Z | 0 | 0 | 0 | %100 |
| 55 | M44A | X | -2.56 | -2.56 | 0 | %100 |
| 56 | M44A | Z | 0 | 0 | 0 | %100 |

Member Distributed Loads (BLC 63 : Structure Wi (300 Deg))

| | Member Label | Direction | Start Magnitude[...] | End Magnitude[lb/ft,F,ksf] | Start Location[ft,%] | End Location[ft,%] |
|----|--------------|-----------|----------------------|----------------------------|----------------------|--------------------|
| 1 | FACE | X | -.657 | -.657 | 0 | %100 |
| 2 | FACE | Z | -.379 | -.379 | 0 | %100 |
| 3 | M2 | X | -.657 | -.657 | 0 | %100 |
| 4 | M2 | Z | -.379 | -.379 | 0 | %100 |
| 5 | M13 | X | -.75 | -.75 | 0 | %100 |
| 6 | M13 | Z | -.433 | -.433 | 0 | %100 |
| 7 | M14 | X | -.75 | -.75 | 0 | %100 |
| 8 | M14 | Z | -.433 | -.433 | 0 | %100 |
| 9 | M15 | X | -.75 | -.75 | 0 | %100 |
| 10 | M15 | Z | -.433 | -.433 | 0 | %100 |
| 11 | M16 | X | -.75 | -.75 | 0 | %100 |
| 12 | M16 | Z | -.433 | -.433 | 0 | %100 |
| 13 | M17 | X | -1.582 | -1.582 | 0 | %100 |
| 14 | M17 | Z | -.913 | -.913 | 0 | %100 |
| 15 | M18 | X | -1.582 | -1.582 | 0 | %100 |
| 16 | M18 | Z | -.913 | -.913 | 0 | %100 |
| 17 | M19 | X | -.036 | -.036 | 0 | %100 |
| 18 | M19 | Z | -.021 | -.021 | 0 | %100 |
| 19 | M20 | X | -.036 | -.036 | 0 | %100 |
| 20 | M20 | Z | -.021 | -.021 | 0 | %100 |
| 21 | M21 | X | -.251 | -.251 | 0 | %100 |
| 22 | M21 | Z | -.145 | -.145 | 0 | %100 |
| 23 | M22 | X | -.251 | -.251 | 0 | %100 |
| 24 | M22 | Z | -.145 | -.145 | 0 | %100 |
| 25 | M23 | X | -.251 | -.251 | 0 | %100 |
| 26 | M23 | Z | -.145 | -.145 | 0 | %100 |
| 27 | M24 | X | -.251 | -.251 | 0 | %100 |
| 28 | M24 | Z | -.145 | -.145 | 0 | %100 |
| 29 | M25 | X | -1.404 | -1.404 | 0 | %100 |
| 30 | M25 | Z | -.811 | -.811 | 0 | %100 |
| 31 | M26 | X | -1.404 | -1.404 | 0 | %100 |
| 32 | M26 | Z | -.811 | -.811 | 0 | %100 |
| 33 | M27 | X | -.956 | -.956 | 0 | %100 |
| 34 | M27 | Z | -.552 | -.552 | 0 | %100 |
| 35 | M28 | X | -.956 | -.956 | 0 | %100 |
| 36 | M28 | Z | -.552 | -.552 | 0 | %100 |
| 37 | MP4A | X | -2.375 | -2.375 | 0 | %100 |
| 38 | MP4A | Z | -1.371 | -1.371 | 0 | %100 |
| 39 | MP3A | X | -2.375 | -2.375 | 0 | %100 |
| 40 | MP3A | Z | -1.371 | -1.371 | 0 | %100 |
| 41 | MP2A | X | -2.375 | -2.375 | 0 | %100 |
| 42 | MP2A | Z | -1.371 | -1.371 | 0 | %100 |
| 43 | MP1A | X | -2.375 | -2.375 | 0 | %100 |
| 44 | MP1A | Z | -1.371 | -1.371 | 0 | %100 |
| 45 | M44 | X | -1.321 | -1.321 | 0 | %100 |
| 46 | M44 | Z | -.763 | -.763 | 0 | %100 |
| 47 | M45 | X | -1.321 | -1.321 | 0 | %100 |
| 48 | M45 | Z | -.763 | -.763 | 0 | %100 |
| 49 | M46 | X | -1.321 | -1.321 | 0 | %100 |
| 50 | M46 | Z | -.763 | -.763 | 0 | %100 |
| 51 | M47 | X | -1.321 | -1.321 | 0 | %100 |
| 52 | M47 | Z | -.763 | -.763 | 0 | %100 |
| 53 | M43 | X | -1.191 | -1.191 | 0 | %100 |
| 54 | M43 | Z | -.687 | -.687 | 0 | %100 |
| 55 | M44A | X | -2.214 | -2.214 | 0 | %100 |
| 56 | M44A | Z | -1.278 | -1.278 | 0 | %100 |



Company :
 Designer :
 Job Number :
 Model Name :

Apr 12, 2022
 10:37 AM
 Checked By: _____

Member Distributed Loads (BLC 64 : Structure Wi (330 Deg))

| | Member Label | Direction | Start Magnitude[...] | End Magnitude[lb/ft,F,ksf] | Start Location[ft,%] | End Location[ft,%] |
|----|--------------|-----------|----------------------|----------------------------|----------------------|--------------------|
| 1 | FACE | X | -1.138 | -1.138 | 0 | %100 |
| 2 | FACE | Z | -1.971 | -1.971 | 0 | %100 |
| 3 | M2 | X | -1.138 | -1.138 | 0 | %100 |
| 4 | M2 | Z | -1.971 | -1.971 | 0 | %100 |
| 5 | M13 | X | -.144 | -.144 | 0 | %100 |
| 6 | M13 | Z | -.25 | -.25 | 0 | %100 |
| 7 | M14 | X | -.144 | -.144 | 0 | %100 |
| 8 | M14 | Z | -.25 | -.25 | 0 | %100 |
| 9 | M15 | X | -.144 | -.144 | 0 | %100 |
| 10 | M15 | Z | -.25 | -.25 | 0 | %100 |
| 11 | M16 | X | -.144 | -.144 | 0 | %100 |
| 12 | M16 | Z | -.25 | -.25 | 0 | %100 |
| 13 | M17 | X | -1.041 | -1.041 | 0 | %100 |
| 14 | M17 | Z | -1.802 | -1.802 | 0 | %100 |
| 15 | M18 | X | -1.041 | -1.041 | 0 | %100 |
| 16 | M18 | Z | -1.802 | -1.802 | 0 | %100 |
| 17 | M19 | X | -.148 | -.148 | 0 | %100 |
| 18 | M19 | Z | -.257 | -.257 | 0 | %100 |
| 19 | M20 | X | -.148 | -.148 | 0 | %100 |
| 20 | M20 | Z | -.257 | -.257 | 0 | %100 |
| 21 | M21 | X | -.435 | -.435 | 0 | %100 |
| 22 | M21 | Z | -.754 | -.754 | 0 | %100 |
| 23 | M22 | X | -.435 | -.435 | 0 | %100 |
| 24 | M22 | Z | -.754 | -.754 | 0 | %100 |
| 25 | M23 | X | -.435 | -.435 | 0 | %100 |
| 26 | M23 | Z | -.754 | -.754 | 0 | %100 |
| 27 | M24 | X | -.435 | -.435 | 0 | %100 |
| 28 | M24 | Z | -.754 | -.754 | 0 | %100 |
| 29 | M25 | X | -.847 | -.847 | 0 | %100 |
| 30 | M25 | Z | -1.468 | -1.468 | 0 | %100 |
| 31 | M26 | X | -.847 | -.847 | 0 | %100 |
| 32 | M26 | Z | -1.468 | -1.468 | 0 | %100 |
| 33 | M27 | X | -.589 | -.589 | 0 | %100 |
| 34 | M27 | Z | -1.02 | -1.02 | 0 | %100 |
| 35 | M28 | X | -.589 | -.589 | 0 | %100 |
| 36 | M28 | Z | -1.02 | -1.02 | 0 | %100 |
| 37 | MP4A | X | -1.371 | -1.371 | 0 | %100 |
| 38 | MP4A | Z | -2.375 | -2.375 | 0 | %100 |
| 39 | MP3A | X | -1.371 | -1.371 | 0 | %100 |
| 40 | MP3A | Z | -2.375 | -2.375 | 0 | %100 |
| 41 | MP2A | X | -1.371 | -1.371 | 0 | %100 |
| 42 | MP2A | Z | -2.375 | -2.375 | 0 | %100 |
| 43 | MP1A | X | -1.371 | -1.371 | 0 | %100 |
| 44 | MP1A | Z | -2.375 | -2.375 | 0 | %100 |
| 45 | M44 | X | -.763 | -.763 | 0 | %100 |
| 46 | M44 | Z | -1.321 | -1.321 | 0 | %100 |
| 47 | M45 | X | -.763 | -.763 | 0 | %100 |
| 48 | M45 | Z | -1.321 | -1.321 | 0 | %100 |
| 49 | M46 | X | -.763 | -.763 | 0 | %100 |
| 50 | M46 | Z | -1.321 | -1.321 | 0 | %100 |
| 51 | M47 | X | -.763 | -.763 | 0 | %100 |
| 52 | M47 | Z | -1.321 | -1.321 | 0 | %100 |
| 53 | M43 | X | -.093 | -.093 | 0 | %100 |
| 54 | M43 | Z | -.161 | -.161 | 0 | %100 |
| 55 | M44A | X | -.684 | -.684 | 0 | %100 |
| 56 | M44A | Z | -1.184 | -1.184 | 0 | %100 |

Member Distributed Loads (BLC 65 : Structure Wm (0 Deg))

| Member Label | Direction | Start Magnitude[...] | End Magnitude[lb/ft,F,ksf] | Start Location[ft,%] | End Location[ft,%] | |
|--------------|-----------|----------------------|----------------------------|----------------------|--------------------|------|
| 1 | FACE | X | 0 | 0 | %100 | |
| 2 | FACE | Z | -.606 | -.606 | 0 | %100 |
| 3 | M2 | X | 0 | 0 | 0 | %100 |
| 4 | M2 | Z | -.606 | -.606 | 0 | %100 |
| 5 | M13 | X | 0 | 0 | 0 | %100 |
| 6 | M13 | Z | 0 | 0 | 0 | %100 |
| 7 | M14 | X | 0 | 0 | 0 | %100 |
| 8 | M14 | Z | 0 | 0 | 0 | %100 |
| 9 | M15 | X | 0 | 0 | 0 | %100 |
| 10 | M15 | Z | 0 | 0 | 0 | %100 |
| 11 | M16 | X | 0 | 0 | 0 | %100 |
| 12 | M16 | Z | 0 | 0 | 0 | %100 |
| 13 | M17 | X | 0 | 0 | 0 | %100 |
| 14 | M17 | Z | -.239 | -.239 | 0 | %100 |
| 15 | M18 | X | 0 | 0 | 0 | %100 |
| 16 | M18 | Z | -.239 | -.239 | 0 | %100 |
| 17 | M19 | X | 0 | 0 | 0 | %100 |
| 18 | M19 | Z | -.239 | -.239 | 0 | %100 |
| 19 | M20 | X | 0 | 0 | 0 | %100 |
| 20 | M20 | Z | -.239 | -.239 | 0 | %100 |
| 21 | M21 | X | 0 | 0 | 0 | %100 |
| 22 | M21 | Z | -.132 | -.132 | 0 | %100 |
| 23 | M22 | X | 0 | 0 | 0 | %100 |
| 24 | M22 | Z | -.132 | -.132 | 0 | %100 |
| 25 | M23 | X | 0 | 0 | 0 | %100 |
| 26 | M23 | Z | -.132 | -.132 | 0 | %100 |
| 27 | M24 | X | 0 | 0 | 0 | %100 |
| 28 | M24 | Z | -.132 | -.132 | 0 | %100 |
| 29 | M25 | X | 0 | 0 | 0 | %100 |
| 30 | M25 | Z | -.136 | -.136 | 0 | %100 |
| 31 | M26 | X | 0 | 0 | 0 | %100 |
| 32 | M26 | Z | -.136 | -.136 | 0 | %100 |
| 33 | M27 | X | 0 | 0 | 0 | %100 |
| 34 | M27 | Z | -.136 | -.136 | 0 | %100 |
| 35 | M28 | X | 0 | 0 | 0 | %100 |
| 36 | M28 | Z | -.136 | -.136 | 0 | %100 |
| 37 | MP4A | X | 0 | 0 | 0 | %100 |
| 38 | MP4A | Z | -.5 | -.5 | 0 | %100 |
| 39 | MP3A | X | 0 | 0 | 0 | %100 |
| 40 | MP3A | Z | -.5 | -.5 | 0 | %100 |
| 41 | MP2A | X | 0 | 0 | 0 | %100 |
| 42 | MP2A | Z | -.5 | -.5 | 0 | %100 |
| 43 | MP1A | X | 0 | 0 | 0 | %100 |
| 44 | MP1A | Z | -.5 | -.5 | 0 | %100 |
| 45 | M44 | X | 0 | 0 | 0 | %100 |
| 46 | M44 | Z | -.132 | -.132 | 0 | %100 |
| 47 | M45 | X | 0 | 0 | 0 | %100 |
| 48 | M45 | Z | -.132 | -.132 | 0 | %100 |
| 49 | M46 | X | 0 | 0 | 0 | %100 |
| 50 | M46 | Z | -.132 | -.132 | 0 | %100 |
| 51 | M47 | X | 0 | 0 | 0 | %100 |
| 52 | M47 | Z | -.132 | -.132 | 0 | %100 |
| 53 | M43 | X | 0 | 0 | 0 | %100 |
| 54 | M43 | Z | -.033 | -.033 | 0 | %100 |
| 55 | M44A | X | 0 | 0 | 0 | %100 |
| 56 | M44A | Z | -.033 | -.033 | 0 | %100 |



Company :
 Designer :
 Job Number :
 Model Name :

Apr 12, 2022
 10:37 AM
 Checked By: _____

Member Distributed Loads (BLC 66 : Structure Wm (30 Deg))

| | Member Label | Direction | Start Magnitude[...] | End Magnitude[lb/ft,F,ksf] | Start Location[ft,%] | End Location[ft,%] |
|----|--------------|-----------|----------------------|----------------------------|----------------------|--------------------|
| 1 | FACE | X | .227 | .227 | 0 | %100 |
| 2 | FACE | Z | -.393 | -.393 | 0 | %100 |
| 3 | M2 | X | .227 | .227 | 0 | %100 |
| 4 | M2 | Z | -.393 | -.393 | 0 | %100 |
| 5 | M13 | X | .016 | .016 | 0 | %100 |
| 6 | M13 | Z | -.029 | -.029 | 0 | %100 |
| 7 | M14 | X | .016 | .016 | 0 | %100 |
| 8 | M14 | Z | -.029 | -.029 | 0 | %100 |
| 9 | M15 | X | .016 | .016 | 0 | %100 |
| 10 | M15 | Z | -.029 | -.029 | 0 | %100 |
| 11 | M16 | X | .016 | .016 | 0 | %100 |
| 12 | M16 | Z | -.029 | -.029 | 0 | %100 |
| 13 | M17 | X | .027 | .027 | 0 | %100 |
| 14 | M17 | Z | -.047 | -.047 | 0 | %100 |
| 15 | M18 | X | .027 | .027 | 0 | %100 |
| 16 | M18 | Z | -.047 | -.047 | 0 | %100 |
| 17 | M19 | X | .189 | .189 | 0 | %100 |
| 18 | M19 | Z | -.328 | -.328 | 0 | %100 |
| 19 | M20 | X | .189 | .189 | 0 | %100 |
| 20 | M20 | Z | -.328 | -.328 | 0 | %100 |
| 21 | M21 | X | .049 | .049 | 0 | %100 |
| 22 | M21 | Z | -.086 | -.086 | 0 | %100 |
| 23 | M22 | X | .049 | .049 | 0 | %100 |
| 24 | M22 | Z | -.086 | -.086 | 0 | %100 |
| 25 | M23 | X | .049 | .049 | 0 | %100 |
| 26 | M23 | Z | -.086 | -.086 | 0 | %100 |
| 27 | M24 | X | .049 | .049 | 0 | %100 |
| 28 | M24 | Z | -.086 | -.086 | 0 | %100 |
| 29 | M25 | X | .055 | .055 | 0 | %100 |
| 30 | M25 | Z | -.094 | -.094 | 0 | %100 |
| 31 | M26 | X | .055 | .055 | 0 | %100 |
| 32 | M26 | Z | -.094 | -.094 | 0 | %100 |
| 33 | M27 | X | .078 | .078 | 0 | %100 |
| 34 | M27 | Z | -.136 | -.136 | 0 | %100 |
| 35 | M28 | X | .078 | .078 | 0 | %100 |
| 36 | M28 | Z | -.136 | -.136 | 0 | %100 |
| 37 | MP4A | X | .25 | .25 | 0 | %100 |
| 38 | MP4A | Z | -.433 | -.433 | 0 | %100 |
| 39 | MP3A | X | .25 | .25 | 0 | %100 |
| 40 | MP3A | Z | -.433 | -.433 | 0 | %100 |
| 41 | MP2A | X | .25 | .25 | 0 | %100 |
| 42 | MP2A | Z | -.433 | -.433 | 0 | %100 |
| 43 | MP1A | X | .25 | .25 | 0 | %100 |
| 44 | MP1A | Z | -.433 | -.433 | 0 | %100 |
| 45 | M44 | X | .066 | .066 | 0 | %100 |
| 46 | M44 | Z | -.114 | -.114 | 0 | %100 |
| 47 | M45 | X | .066 | .066 | 0 | %100 |
| 48 | M45 | Z | -.114 | -.114 | 0 | %100 |
| 49 | M46 | X | .066 | .066 | 0 | %100 |
| 50 | M46 | Z | -.114 | -.114 | 0 | %100 |
| 51 | M47 | X | .066 | .066 | 0 | %100 |
| 52 | M47 | Z | -.114 | -.114 | 0 | %100 |
| 53 | M43 | X | .125 | .125 | 0 | %100 |
| 54 | M43 | Z | -.216 | -.216 | 0 | %100 |
| 55 | M44A | X | .017 | .017 | 0 | %100 |
| 56 | M44A | Z | -.029 | -.029 | 0 | %100 |

Member Distributed Loads (BLC 67 : Structure Wm (60 Deg))

| Member Label | Direction | Start Magnitude[...] | End Magnitude[lb/ft,F,ksf] | Start Location[ft,%] | End Location[ft,%] |
|--------------|-----------|----------------------|----------------------------|----------------------|--------------------|
| 1 | FACE | X | .131 | .131 | 0 %100 |
| 2 | FACE | Z | -.076 | -.076 | 0 %100 |
| 3 | M2 | X | .131 | .131 | 0 %100 |
| 4 | M2 | Z | -.076 | -.076 | 0 %100 |
| 5 | M13 | X | .086 | .086 | 0 %100 |
| 6 | M13 | Z | -.049 | -.049 | 0 %100 |
| 7 | M14 | X | .086 | .086 | 0 %100 |
| 8 | M14 | Z | -.049 | -.049 | 0 %100 |
| 9 | M15 | X | .086 | .086 | 0 %100 |
| 10 | M15 | Z | -.049 | -.049 | 0 %100 |
| 11 | M16 | X | .086 | .086 | 0 %100 |
| 12 | M16 | Z | -.049 | -.049 | 0 %100 |
| 13 | M17 | X | .007 | .007 | 0 %100 |
| 14 | M17 | Z | -.004 | -.004 | 0 %100 |
| 15 | M18 | X | .007 | .007 | 0 %100 |
| 16 | M18 | Z | -.004 | -.004 | 0 %100 |
| 17 | M19 | X | .287 | .287 | 0 %100 |
| 18 | M19 | Z | -.166 | -.166 | 0 %100 |
| 19 | M20 | X | .287 | .287 | 0 %100 |
| 20 | M20 | Z | -.166 | -.166 | 0 %100 |
| 21 | M21 | X | .029 | .029 | 0 %100 |
| 22 | M21 | Z | -.016 | -.016 | 0 %100 |
| 23 | M22 | X | .029 | .029 | 0 %100 |
| 24 | M22 | Z | -.016 | -.016 | 0 %100 |
| 25 | M23 | X | .029 | .029 | 0 %100 |
| 26 | M23 | Z | -.016 | -.016 | 0 %100 |
| 27 | M24 | X | .029 | .029 | 0 %100 |
| 28 | M24 | Z | -.016 | -.016 | 0 %100 |
| 29 | M25 | X | .089 | .089 | 0 %100 |
| 30 | M25 | Z | -.051 | -.051 | 0 %100 |
| 31 | M26 | X | .089 | .089 | 0 %100 |
| 32 | M26 | Z | -.051 | -.051 | 0 %100 |
| 33 | M27 | X | .13 | .13 | 0 %100 |
| 34 | M27 | Z | -.075 | -.075 | 0 %100 |
| 35 | M28 | X | .13 | .13 | 0 %100 |
| 36 | M28 | Z | -.075 | -.075 | 0 %100 |
| 37 | MP4A | X | .433 | .433 | 0 %100 |
| 38 | MP4A | Z | -.25 | -.25 | 0 %100 |
| 39 | MP3A | X | .433 | .433 | 0 %100 |
| 40 | MP3A | Z | -.25 | -.25 | 0 %100 |
| 41 | MP2A | X | .433 | .433 | 0 %100 |
| 42 | MP2A | Z | -.25 | -.25 | 0 %100 |
| 43 | MP1A | X | .433 | .433 | 0 %100 |
| 44 | MP1A | Z | -.25 | -.25 | 0 %100 |
| 45 | M44 | X | .114 | .114 | 0 %100 |
| 46 | M44 | Z | -.066 | -.066 | 0 %100 |
| 47 | M45 | X | .114 | .114 | 0 %100 |
| 48 | M45 | Z | -.066 | -.066 | 0 %100 |
| 49 | M46 | X | .114 | .114 | 0 %100 |
| 50 | M46 | Z | -.066 | -.066 | 0 %100 |
| 51 | M47 | X | .114 | .114 | 0 %100 |
| 52 | M47 | Z | -.066 | -.066 | 0 %100 |
| 53 | M43 | X | .404 | .404 | 0 %100 |
| 54 | M43 | Z | -.233 | -.233 | 0 %100 |
| 55 | M44A | X | .217 | .217 | 0 %100 |
| 56 | M44A | Z | -.125 | -.125 | 0 %100 |

Member Distributed Loads (BLC 68 : Structure Wm (90 Deg))

| | Member Label | Direction | Start Magnitude[...] | End Magnitude[lb/ft,F,ksf] | Start Location[ft,%] | End Location[ft,%] |
|----|--------------|-----------|----------------------|----------------------------|----------------------|--------------------|
| 1 | FACE | X | 0 | 0 | 0 | %100 |
| 2 | FACE | Z | 0 | 0 | 0 | %100 |
| 3 | M2 | X | 0 | 0 | 0 | %100 |
| 4 | M2 | Z | 0 | 0 | 0 | %100 |
| 5 | M13 | X | .132 | .132 | 0 | %100 |
| 6 | M13 | Z | 0 | 0 | 0 | %100 |
| 7 | M14 | X | .132 | .132 | 0 | %100 |
| 8 | M14 | Z | 0 | 0 | 0 | %100 |
| 9 | M15 | X | .132 | .132 | 0 | %100 |
| 10 | M15 | Z | 0 | 0 | 0 | %100 |
| 11 | M16 | X | .132 | .132 | 0 | %100 |
| 12 | M16 | Z | 0 | 0 | 0 | %100 |
| 13 | M17 | X | .147 | .147 | 0 | %100 |
| 14 | M17 | Z | 0 | 0 | 0 | %100 |
| 15 | M18 | X | .147 | .147 | 0 | %100 |
| 16 | M18 | Z | 0 | 0 | 0 | %100 |
| 17 | M19 | X | .147 | .147 | 0 | %100 |
| 18 | M19 | Z | 0 | 0 | 0 | %100 |
| 19 | M20 | X | .147 | .147 | 0 | %100 |
| 20 | M20 | Z | 0 | 0 | 0 | %100 |
| 21 | M21 | X | 0 | 0 | 0 | %100 |
| 22 | M21 | Z | 0 | 0 | 0 | %100 |
| 23 | M22 | X | 0 | 0 | 0 | %100 |
| 24 | M22 | Z | 0 | 0 | 0 | %100 |
| 25 | M23 | X | 0 | 0 | 0 | %100 |
| 26 | M23 | Z | 0 | 0 | 0 | %100 |
| 27 | M24 | X | 0 | 0 | 0 | %100 |
| 28 | M24 | Z | 0 | 0 | 0 | %100 |
| 29 | M25 | X | .123 | .123 | 0 | %100 |
| 30 | M25 | Z | 0 | 0 | 0 | %100 |
| 31 | M26 | X | .123 | .123 | 0 | %100 |
| 32 | M26 | Z | 0 | 0 | 0 | %100 |
| 33 | M27 | X | .123 | .123 | 0 | %100 |
| 34 | M27 | Z | 0 | 0 | 0 | %100 |
| 35 | M28 | X | .123 | .123 | 0 | %100 |
| 36 | M28 | Z | 0 | 0 | 0 | %100 |
| 37 | MP4A | X | .5 | .5 | 0 | %100 |
| 38 | MP4A | Z | 0 | 0 | 0 | %100 |
| 39 | MP3A | X | .5 | .5 | 0 | %100 |
| 40 | MP3A | Z | 0 | 0 | 0 | %100 |
| 41 | MP2A | X | .5 | .5 | 0 | %100 |
| 42 | MP2A | Z | 0 | 0 | 0 | %100 |
| 43 | MP1A | X | .5 | .5 | 0 | %100 |
| 44 | MP1A | Z | 0 | 0 | 0 | %100 |
| 45 | M44 | X | .132 | .132 | 0 | %100 |
| 46 | M44 | Z | 0 | 0 | 0 | %100 |
| 47 | M45 | X | .132 | .132 | 0 | %100 |
| 48 | M45 | Z | 0 | 0 | 0 | %100 |
| 49 | M46 | X | .132 | .132 | 0 | %100 |
| 50 | M46 | Z | 0 | 0 | 0 | %100 |
| 51 | M47 | X | .132 | .132 | 0 | %100 |
| 52 | M47 | Z | 0 | 0 | 0 | %100 |
| 53 | M43 | X | .467 | .467 | 0 | %100 |
| 54 | M43 | Z | 0 | 0 | 0 | %100 |
| 55 | M44A | X | .467 | .467 | 0 | %100 |
| 56 | M44A | Z | 0 | 0 | 0 | %100 |



Company :
 Designer :
 Job Number :
 Model Name :

Apr 12, 2022
 10:37 AM
 Checked By: _____

Member Distributed Loads (BLC 69 : Structure Wm (120 Deg))

| | Member Label | Direction | Start Magnitude[...] | End Magnitude[lb/ft,F,ksf] | Start Location[ft,%] | End Location[ft,%] |
|----|--------------|-----------|----------------------|----------------------------|----------------------|--------------------|
| 1 | FACE | X | .131 | .131 | 0 | %100 |
| 2 | FACE | Z | .076 | .076 | 0 | %100 |
| 3 | M2 | X | .131 | .131 | 0 | %100 |
| 4 | M2 | Z | .076 | .076 | 0 | %100 |
| 5 | M13 | X | .086 | .086 | 0 | %100 |
| 6 | M13 | Z | .049 | .049 | 0 | %100 |
| 7 | M14 | X | .086 | .086 | 0 | %100 |
| 8 | M14 | Z | .049 | .049 | 0 | %100 |
| 9 | M15 | X | .086 | .086 | 0 | %100 |
| 10 | M15 | Z | .049 | .049 | 0 | %100 |
| 11 | M16 | X | .086 | .086 | 0 | %100 |
| 12 | M16 | Z | .049 | .049 | 0 | %100 |
| 13 | M17 | X | .287 | .287 | 0 | %100 |
| 14 | M17 | Z | .166 | .166 | 0 | %100 |
| 15 | M18 | X | .287 | .287 | 0 | %100 |
| 16 | M18 | Z | .166 | .166 | 0 | %100 |
| 17 | M19 | X | .007 | .007 | 0 | %100 |
| 18 | M19 | Z | .004 | .004 | 0 | %100 |
| 19 | M20 | X | .007 | .007 | 0 | %100 |
| 20 | M20 | Z | .004 | .004 | 0 | %100 |
| 21 | M21 | X | .029 | .029 | 0 | %100 |
| 22 | M21 | Z | .016 | .016 | 0 | %100 |
| 23 | M22 | X | .029 | .029 | 0 | %100 |
| 24 | M22 | Z | .016 | .016 | 0 | %100 |
| 25 | M23 | X | .029 | .029 | 0 | %100 |
| 26 | M23 | Z | .016 | .016 | 0 | %100 |
| 27 | M24 | X | .029 | .029 | 0 | %100 |
| 28 | M24 | Z | .016 | .016 | 0 | %100 |
| 29 | M25 | X | .13 | .13 | 0 | %100 |
| 30 | M25 | Z | .075 | .075 | 0 | %100 |
| 31 | M26 | X | .13 | .13 | 0 | %100 |
| 32 | M26 | Z | .075 | .075 | 0 | %100 |
| 33 | M27 | X | .089 | .089 | 0 | %100 |
| 34 | M27 | Z | .051 | .051 | 0 | %100 |
| 35 | M28 | X | .089 | .089 | 0 | %100 |
| 36 | M28 | Z | .051 | .051 | 0 | %100 |
| 37 | MP4A | X | .433 | .433 | 0 | %100 |
| 38 | MP4A | Z | .25 | .25 | 0 | %100 |
| 39 | MP3A | X | .433 | .433 | 0 | %100 |
| 40 | MP3A | Z | .25 | .25 | 0 | %100 |
| 41 | MP2A | X | .433 | .433 | 0 | %100 |
| 42 | MP2A | Z | .25 | .25 | 0 | %100 |
| 43 | MP1A | X | .433 | .433 | 0 | %100 |
| 44 | MP1A | Z | .25 | .25 | 0 | %100 |
| 45 | M44 | X | .114 | .114 | 0 | %100 |
| 46 | M44 | Z | .066 | .066 | 0 | %100 |
| 47 | M45 | X | .114 | .114 | 0 | %100 |
| 48 | M45 | Z | .066 | .066 | 0 | %100 |
| 49 | M46 | X | .114 | .114 | 0 | %100 |
| 50 | M46 | Z | .066 | .066 | 0 | %100 |
| 51 | M47 | X | .114 | .114 | 0 | %100 |
| 52 | M47 | Z | .066 | .066 | 0 | %100 |
| 53 | M43 | X | .217 | .217 | 0 | %100 |
| 54 | M43 | Z | .125 | .125 | 0 | %100 |
| 55 | M44A | X | .404 | .404 | 0 | %100 |
| 56 | M44A | Z | .233 | .233 | 0 | %100 |



Company :
 Designer :
 Job Number :
 Model Name :

Apr 12, 2022
 10:37 AM
 Checked By: _____

Member Distributed Loads (BLC 70 : Structure Wm (150 Deg))

| Member Label | Direction | Start Magnitude[...] | End Magnitude[lb/ft,F,ksf] | Start Location[ft,%] | End Location[ft,%] |
|--------------|-----------|----------------------|----------------------------|----------------------|--------------------|
| 1 | FACE | X | .227 | .227 | 0 %100 |
| 2 | FACE | Z | .393 | .393 | 0 %100 |
| 3 | M2 | X | .227 | .227 | 0 %100 |
| 4 | M2 | Z | .393 | .393 | 0 %100 |
| 5 | M13 | X | .016 | .016 | 0 %100 |
| 6 | M13 | Z | .029 | .029 | 0 %100 |
| 7 | M14 | X | .016 | .016 | 0 %100 |
| 8 | M14 | Z | .029 | .029 | 0 %100 |
| 9 | M15 | X | .016 | .016 | 0 %100 |
| 10 | M15 | Z | .029 | .029 | 0 %100 |
| 11 | M16 | X | .016 | .016 | 0 %100 |
| 12 | M16 | Z | .029 | .029 | 0 %100 |
| 13 | M17 | X | .189 | .189 | 0 %100 |
| 14 | M17 | Z | .328 | .328 | 0 %100 |
| 15 | M18 | X | .189 | .189 | 0 %100 |
| 16 | M18 | Z | .328 | .328 | 0 %100 |
| 17 | M19 | X | .027 | .027 | 0 %100 |
| 18 | M19 | Z | .047 | .047 | 0 %100 |
| 19 | M20 | X | .027 | .027 | 0 %100 |
| 20 | M20 | Z | .047 | .047 | 0 %100 |
| 21 | M21 | X | .049 | .049 | 0 %100 |
| 22 | M21 | Z | .086 | .086 | 0 %100 |
| 23 | M22 | X | .049 | .049 | 0 %100 |
| 24 | M22 | Z | .086 | .086 | 0 %100 |
| 25 | M23 | X | .049 | .049 | 0 %100 |
| 26 | M23 | Z | .086 | .086 | 0 %100 |
| 27 | M24 | X | .049 | .049 | 0 %100 |
| 28 | M24 | Z | .086 | .086 | 0 %100 |
| 29 | M25 | X | .078 | .078 | 0 %100 |
| 30 | M25 | Z | .136 | .136 | 0 %100 |
| 31 | M26 | X | .078 | .078 | 0 %100 |
| 32 | M26 | Z | .136 | .136 | 0 %100 |
| 33 | M27 | X | .055 | .055 | 0 %100 |
| 34 | M27 | Z | .094 | .094 | 0 %100 |
| 35 | M28 | X | .055 | .055 | 0 %100 |
| 36 | M28 | Z | .094 | .094 | 0 %100 |
| 37 | MP4A | X | .25 | .25 | 0 %100 |
| 38 | MP4A | Z | .433 | .433 | 0 %100 |
| 39 | MP3A | X | .25 | .25 | 0 %100 |
| 40 | MP3A | Z | .433 | .433 | 0 %100 |
| 41 | MP2A | X | .25 | .25 | 0 %100 |
| 42 | MP2A | Z | .433 | .433 | 0 %100 |
| 43 | MP1A | X | .25 | .25 | 0 %100 |
| 44 | MP1A | Z | .433 | .433 | 0 %100 |
| 45 | M44 | X | .066 | .066 | 0 %100 |
| 46 | M44 | Z | .114 | .114 | 0 %100 |
| 47 | M45 | X | .066 | .066 | 0 %100 |
| 48 | M45 | Z | .114 | .114 | 0 %100 |
| 49 | M46 | X | .066 | .066 | 0 %100 |
| 50 | M46 | Z | .114 | .114 | 0 %100 |
| 51 | M47 | X | .066 | .066 | 0 %100 |
| 52 | M47 | Z | .114 | .114 | 0 %100 |
| 53 | M43 | X | .017 | .017 | 0 %100 |
| 54 | M43 | Z | .029 | .029 | 0 %100 |
| 55 | M44A | X | .125 | .125 | 0 %100 |
| 56 | M44A | Z | .216 | .216 | 0 %100 |

Member Distributed Loads (BLC 71 : Structure Wm (180 Deg))

| Member Label | Direction | Start Magnitude[...] | End Magnitude[lb/ft,F,ksf] | Start Location[ft,%] | End Location[ft,%] |
|--------------|-----------|----------------------|----------------------------|----------------------|--------------------|
| 1 | FACE | X | 0 | 0 | %100 |
| 2 | FACE | Z | .606 | .606 | %100 |
| 3 | M2 | X | 0 | 0 | %100 |
| 4 | M2 | Z | .606 | .606 | %100 |
| 5 | M13 | X | 0 | 0 | %100 |
| 6 | M13 | Z | 0 | 0 | %100 |
| 7 | M14 | X | 0 | 0 | %100 |
| 8 | M14 | Z | 0 | 0 | %100 |
| 9 | M15 | X | 0 | 0 | %100 |
| 10 | M15 | Z | 0 | 0 | %100 |
| 11 | M16 | X | 0 | 0 | %100 |
| 12 | M16 | Z | 0 | 0 | %100 |
| 13 | M17 | X | 0 | 0 | %100 |
| 14 | M17 | Z | .239 | .239 | %100 |
| 15 | M18 | X | 0 | 0 | %100 |
| 16 | M18 | Z | .239 | .239 | %100 |
| 17 | M19 | X | 0 | 0 | %100 |
| 18 | M19 | Z | .239 | .239 | %100 |
| 19 | M20 | X | 0 | 0 | %100 |
| 20 | M20 | Z | .239 | .239 | %100 |
| 21 | M21 | X | 0 | 0 | %100 |
| 22 | M21 | Z | .132 | .132 | %100 |
| 23 | M22 | X | 0 | 0 | %100 |
| 24 | M22 | Z | .132 | .132 | %100 |
| 25 | M23 | X | 0 | 0 | %100 |
| 26 | M23 | Z | .132 | .132 | %100 |
| 27 | M24 | X | 0 | 0 | %100 |
| 28 | M24 | Z | .132 | .132 | %100 |
| 29 | M25 | X | 0 | 0 | %100 |
| 30 | M25 | Z | .136 | .136 | %100 |
| 31 | M26 | X | 0 | 0 | %100 |
| 32 | M26 | Z | .136 | .136 | %100 |
| 33 | M27 | X | 0 | 0 | %100 |
| 34 | M27 | Z | .136 | .136 | %100 |
| 35 | M28 | X | 0 | 0 | %100 |
| 36 | M28 | Z | .136 | .136 | %100 |
| 37 | MP4A | X | 0 | 0 | %100 |
| 38 | MP4A | Z | .5 | .5 | %100 |
| 39 | MP3A | X | 0 | 0 | %100 |
| 40 | MP3A | Z | .5 | .5 | %100 |
| 41 | MP2A | X | 0 | 0 | %100 |
| 42 | MP2A | Z | .5 | .5 | %100 |
| 43 | MP1A | X | 0 | 0 | %100 |
| 44 | MP1A | Z | .5 | .5 | %100 |
| 45 | M44 | X | 0 | 0 | %100 |
| 46 | M44 | Z | .132 | .132 | %100 |
| 47 | M45 | X | 0 | 0 | %100 |
| 48 | M45 | Z | .132 | .132 | %100 |
| 49 | M46 | X | 0 | 0 | %100 |
| 50 | M46 | Z | .132 | .132 | %100 |
| 51 | M47 | X | 0 | 0 | %100 |
| 52 | M47 | Z | .132 | .132 | %100 |
| 53 | M43 | X | 0 | 0 | %100 |
| 54 | M43 | Z | .033 | .033 | %100 |
| 55 | M44A | X | 0 | 0 | %100 |
| 56 | M44A | Z | .033 | .033 | %100 |



Company :
 Designer :
 Job Number :
 Model Name :

Apr 12, 2022
 10:37 AM
 Checked By: _____

Member Distributed Loads (BLC 72 : Structure Wm (210 Deg))

| | Member Label | Direction | Start Magnitude[...] | End Magnitude[lb/ft,F,ksf] | Start Location[ft,%] | End Location[ft,%] |
|----|--------------|-----------|----------------------|----------------------------|----------------------|--------------------|
| 1 | FACE | X | -.227 | -.227 | 0 | %100 |
| 2 | FACE | Z | .393 | .393 | 0 | %100 |
| 3 | M2 | X | -.227 | -.227 | 0 | %100 |
| 4 | M2 | Z | .393 | .393 | 0 | %100 |
| 5 | M13 | X | -.016 | -.016 | 0 | %100 |
| 6 | M13 | Z | .029 | .029 | 0 | %100 |
| 7 | M14 | X | -.016 | -.016 | 0 | %100 |
| 8 | M14 | Z | .029 | .029 | 0 | %100 |
| 9 | M15 | X | -.016 | -.016 | 0 | %100 |
| 10 | M15 | Z | .029 | .029 | 0 | %100 |
| 11 | M16 | X | -.016 | -.016 | 0 | %100 |
| 12 | M16 | Z | .029 | .029 | 0 | %100 |
| 13 | M17 | X | -.027 | -.027 | 0 | %100 |
| 14 | M17 | Z | .047 | .047 | 0 | %100 |
| 15 | M18 | X | -.027 | -.027 | 0 | %100 |
| 16 | M18 | Z | .047 | .047 | 0 | %100 |
| 17 | M19 | X | -.189 | -.189 | 0 | %100 |
| 18 | M19 | Z | .328 | .328 | 0 | %100 |
| 19 | M20 | X | -.189 | -.189 | 0 | %100 |
| 20 | M20 | Z | .328 | .328 | 0 | %100 |
| 21 | M21 | X | -.049 | -.049 | 0 | %100 |
| 22 | M21 | Z | .086 | .086 | 0 | %100 |
| 23 | M22 | X | -.049 | -.049 | 0 | %100 |
| 24 | M22 | Z | .086 | .086 | 0 | %100 |
| 25 | M23 | X | -.049 | -.049 | 0 | %100 |
| 26 | M23 | Z | .086 | .086 | 0 | %100 |
| 27 | M24 | X | -.049 | -.049 | 0 | %100 |
| 28 | M24 | Z | .086 | .086 | 0 | %100 |
| 29 | M25 | X | -.055 | -.055 | 0 | %100 |
| 30 | M25 | Z | .094 | .094 | 0 | %100 |
| 31 | M26 | X | -.055 | -.055 | 0 | %100 |
| 32 | M26 | Z | .094 | .094 | 0 | %100 |
| 33 | M27 | X | -.078 | -.078 | 0 | %100 |
| 34 | M27 | Z | .136 | .136 | 0 | %100 |
| 35 | M28 | X | -.078 | -.078 | 0 | %100 |
| 36 | M28 | Z | .136 | .136 | 0 | %100 |
| 37 | MP4A | X | -.25 | -.25 | 0 | %100 |
| 38 | MP4A | Z | .433 | .433 | 0 | %100 |
| 39 | MP3A | X | -.25 | -.25 | 0 | %100 |
| 40 | MP3A | Z | .433 | .433 | 0 | %100 |
| 41 | MP2A | X | -.25 | -.25 | 0 | %100 |
| 42 | MP2A | Z | .433 | .433 | 0 | %100 |
| 43 | MP1A | X | -.25 | -.25 | 0 | %100 |
| 44 | MP1A | Z | .433 | .433 | 0 | %100 |
| 45 | M44 | X | -.066 | -.066 | 0 | %100 |
| 46 | M44 | Z | .114 | .114 | 0 | %100 |
| 47 | M45 | X | -.066 | -.066 | 0 | %100 |
| 48 | M45 | Z | .114 | .114 | 0 | %100 |
| 49 | M46 | X | -.066 | -.066 | 0 | %100 |
| 50 | M46 | Z | .114 | .114 | 0 | %100 |
| 51 | M47 | X | -.066 | -.066 | 0 | %100 |
| 52 | M47 | Z | .114 | .114 | 0 | %100 |
| 53 | M43 | X | -.125 | -.125 | 0 | %100 |
| 54 | M43 | Z | .216 | .216 | 0 | %100 |
| 55 | M44A | X | -.017 | -.017 | 0 | %100 |
| 56 | M44A | Z | .029 | .029 | 0 | %100 |

Member Distributed Loads (BLC 73 : Structure Wm (240 Deg))

| | Member Label | Direction | Start Magnitude[...] | End Magnitude[lb/ft,F,ksf] | Start Location[ft,%] | End Location[ft,%] |
|----|--------------|-----------|----------------------|----------------------------|----------------------|--------------------|
| 1 | FACE | X | -.131 | -.131 | 0 | %100 |
| 2 | FACE | Z | .076 | .076 | 0 | %100 |
| 3 | M2 | X | -.131 | -.131 | 0 | %100 |
| 4 | M2 | Z | .076 | .076 | 0 | %100 |
| 5 | M13 | X | -.086 | -.086 | 0 | %100 |
| 6 | M13 | Z | .049 | .049 | 0 | %100 |
| 7 | M14 | X | -.086 | -.086 | 0 | %100 |
| 8 | M14 | Z | .049 | .049 | 0 | %100 |
| 9 | M15 | X | -.086 | -.086 | 0 | %100 |
| 10 | M15 | Z | .049 | .049 | 0 | %100 |
| 11 | M16 | X | -.086 | -.086 | 0 | %100 |
| 12 | M16 | Z | .049 | .049 | 0 | %100 |
| 13 | M17 | X | -.007 | -.007 | 0 | %100 |
| 14 | M17 | Z | .004 | .004 | 0 | %100 |
| 15 | M18 | X | -.007 | -.007 | 0 | %100 |
| 16 | M18 | Z | .004 | .004 | 0 | %100 |
| 17 | M19 | X | -.287 | -.287 | 0 | %100 |
| 18 | M19 | Z | .166 | .166 | 0 | %100 |
| 19 | M20 | X | -.287 | -.287 | 0 | %100 |
| 20 | M20 | Z | .166 | .166 | 0 | %100 |
| 21 | M21 | X | -.029 | -.029 | 0 | %100 |
| 22 | M21 | Z | .016 | .016 | 0 | %100 |
| 23 | M22 | X | -.029 | -.029 | 0 | %100 |
| 24 | M22 | Z | .016 | .016 | 0 | %100 |
| 25 | M23 | X | -.029 | -.029 | 0 | %100 |
| 26 | M23 | Z | .016 | .016 | 0 | %100 |
| 27 | M24 | X | -.029 | -.029 | 0 | %100 |
| 28 | M24 | Z | .016 | .016 | 0 | %100 |
| 29 | M25 | X | -.089 | -.089 | 0 | %100 |
| 30 | M25 | Z | .051 | .051 | 0 | %100 |
| 31 | M26 | X | -.089 | -.089 | 0 | %100 |
| 32 | M26 | Z | .051 | .051 | 0 | %100 |
| 33 | M27 | X | -.13 | -.13 | 0 | %100 |
| 34 | M27 | Z | .075 | .075 | 0 | %100 |
| 35 | M28 | X | -.13 | -.13 | 0 | %100 |
| 36 | M28 | Z | .075 | .075 | 0 | %100 |
| 37 | MP4A | X | -.433 | -.433 | 0 | %100 |
| 38 | MP4A | Z | .25 | .25 | 0 | %100 |
| 39 | MP3A | X | -.433 | -.433 | 0 | %100 |
| 40 | MP3A | Z | .25 | .25 | 0 | %100 |
| 41 | MP2A | X | -.433 | -.433 | 0 | %100 |
| 42 | MP2A | Z | .25 | .25 | 0 | %100 |
| 43 | MP1A | X | -.433 | -.433 | 0 | %100 |
| 44 | MP1A | Z | .25 | .25 | 0 | %100 |
| 45 | M44 | X | -.114 | -.114 | 0 | %100 |
| 46 | M44 | Z | .066 | .066 | 0 | %100 |
| 47 | M45 | X | -.114 | -.114 | 0 | %100 |
| 48 | M45 | Z | .066 | .066 | 0 | %100 |
| 49 | M46 | X | -.114 | -.114 | 0 | %100 |
| 50 | M46 | Z | .066 | .066 | 0 | %100 |
| 51 | M47 | X | -.114 | -.114 | 0 | %100 |
| 52 | M47 | Z | .066 | .066 | 0 | %100 |
| 53 | M43 | X | -.404 | -.404 | 0 | %100 |
| 54 | M43 | Z | .233 | .233 | 0 | %100 |
| 55 | M44A | X | -.217 | -.217 | 0 | %100 |
| 56 | M44A | Z | .125 | .125 | 0 | %100 |



Company :
 Designer :
 Job Number :
 Model Name :

Apr 12, 2022
 10:37 AM
 Checked By: _____

Member Distributed Loads (BLC 74 : Structure Wm (270 Deg))

| | Member Label | Direction | Start Magnitude[...] | End Magnitude[lb/ft,F,ksf] | Start Location[ft,%] | End Location[ft,%] |
|----|--------------|-----------|----------------------|----------------------------|----------------------|--------------------|
| 1 | FACE | X | 0 | 0 | 0 | %100 |
| 2 | FACE | Z | 0 | 0 | 0 | %100 |
| 3 | M2 | X | 0 | 0 | 0 | %100 |
| 4 | M2 | Z | 0 | 0 | 0 | %100 |
| 5 | M13 | X | -.132 | -.132 | 0 | %100 |
| 6 | M13 | Z | 0 | 0 | 0 | %100 |
| 7 | M14 | X | -.132 | -.132 | 0 | %100 |
| 8 | M14 | Z | 0 | 0 | 0 | %100 |
| 9 | M15 | X | -.132 | -.132 | 0 | %100 |
| 10 | M15 | Z | 0 | 0 | 0 | %100 |
| 11 | M16 | X | -.132 | -.132 | 0 | %100 |
| 12 | M16 | Z | 0 | 0 | 0 | %100 |
| 13 | M17 | X | -.147 | -.147 | 0 | %100 |
| 14 | M17 | Z | 0 | 0 | 0 | %100 |
| 15 | M18 | X | -.147 | -.147 | 0 | %100 |
| 16 | M18 | Z | 0 | 0 | 0 | %100 |
| 17 | M19 | X | -.147 | -.147 | 0 | %100 |
| 18 | M19 | Z | 0 | 0 | 0 | %100 |
| 19 | M20 | X | -.147 | -.147 | 0 | %100 |
| 20 | M20 | Z | 0 | 0 | 0 | %100 |
| 21 | M21 | X | 0 | 0 | 0 | %100 |
| 22 | M21 | Z | 0 | 0 | 0 | %100 |
| 23 | M22 | X | 0 | 0 | 0 | %100 |
| 24 | M22 | Z | 0 | 0 | 0 | %100 |
| 25 | M23 | X | 0 | 0 | 0 | %100 |
| 26 | M23 | Z | 0 | 0 | 0 | %100 |
| 27 | M24 | X | 0 | 0 | 0 | %100 |
| 28 | M24 | Z | 0 | 0 | 0 | %100 |
| 29 | M25 | X | -.123 | -.123 | 0 | %100 |
| 30 | M25 | Z | 0 | 0 | 0 | %100 |
| 31 | M26 | X | -.123 | -.123 | 0 | %100 |
| 32 | M26 | Z | 0 | 0 | 0 | %100 |
| 33 | M27 | X | -.123 | -.123 | 0 | %100 |
| 34 | M27 | Z | 0 | 0 | 0 | %100 |
| 35 | M28 | X | -.123 | -.123 | 0 | %100 |
| 36 | M28 | Z | 0 | 0 | 0 | %100 |
| 37 | MP4A | X | -.5 | -.5 | 0 | %100 |
| 38 | MP4A | Z | 0 | 0 | 0 | %100 |
| 39 | MP3A | X | -.5 | -.5 | 0 | %100 |
| 40 | MP3A | Z | 0 | 0 | 0 | %100 |
| 41 | MP2A | X | -.5 | -.5 | 0 | %100 |
| 42 | MP2A | Z | 0 | 0 | 0 | %100 |
| 43 | MP1A | X | -.5 | -.5 | 0 | %100 |
| 44 | MP1A | Z | 0 | 0 | 0 | %100 |
| 45 | M44 | X | -.132 | -.132 | 0 | %100 |
| 46 | M44 | Z | 0 | 0 | 0 | %100 |
| 47 | M45 | X | -.132 | -.132 | 0 | %100 |
| 48 | M45 | Z | 0 | 0 | 0 | %100 |
| 49 | M46 | X | -.132 | -.132 | 0 | %100 |
| 50 | M46 | Z | 0 | 0 | 0 | %100 |
| 51 | M47 | X | -.132 | -.132 | 0 | %100 |
| 52 | M47 | Z | 0 | 0 | 0 | %100 |
| 53 | M43 | X | -.467 | -.467 | 0 | %100 |
| 54 | M43 | Z | 0 | 0 | 0 | %100 |
| 55 | M44A | X | -.467 | -.467 | 0 | %100 |
| 56 | M44A | Z | 0 | 0 | 0 | %100 |

Member Distributed Loads (BLC 75 : Structure Wm (300 Deg))

| | Member Label | Direction | Start Magnitude[...] | End Magnitude[lb/ft,F,ksf] | Start Location[ft,%] | End Location[ft,%] |
|----|--------------|-----------|----------------------|----------------------------|----------------------|--------------------|
| 1 | FACE | X | -.131 | -.131 | 0 | %100 |
| 2 | FACE | Z | -.076 | -.076 | 0 | %100 |
| 3 | M2 | X | -.131 | -.131 | 0 | %100 |
| 4 | M2 | Z | -.076 | -.076 | 0 | %100 |
| 5 | M13 | X | -.086 | -.086 | 0 | %100 |
| 6 | M13 | Z | -.049 | -.049 | 0 | %100 |
| 7 | M14 | X | -.086 | -.086 | 0 | %100 |
| 8 | M14 | Z | -.049 | -.049 | 0 | %100 |
| 9 | M15 | X | -.086 | -.086 | 0 | %100 |
| 10 | M15 | Z | -.049 | -.049 | 0 | %100 |
| 11 | M16 | X | -.086 | -.086 | 0 | %100 |
| 12 | M16 | Z | -.049 | -.049 | 0 | %100 |
| 13 | M17 | X | -.287 | -.287 | 0 | %100 |
| 14 | M17 | Z | -.166 | -.166 | 0 | %100 |
| 15 | M18 | X | -.287 | -.287 | 0 | %100 |
| 16 | M18 | Z | -.166 | -.166 | 0 | %100 |
| 17 | M19 | X | -.007 | -.007 | 0 | %100 |
| 18 | M19 | Z | -.004 | -.004 | 0 | %100 |
| 19 | M20 | X | -.007 | -.007 | 0 | %100 |
| 20 | M20 | Z | -.004 | -.004 | 0 | %100 |
| 21 | M21 | X | -.029 | -.029 | 0 | %100 |
| 22 | M21 | Z | -.016 | -.016 | 0 | %100 |
| 23 | M22 | X | -.029 | -.029 | 0 | %100 |
| 24 | M22 | Z | -.016 | -.016 | 0 | %100 |
| 25 | M23 | X | -.029 | -.029 | 0 | %100 |
| 26 | M23 | Z | -.016 | -.016 | 0 | %100 |
| 27 | M24 | X | -.029 | -.029 | 0 | %100 |
| 28 | M24 | Z | -.016 | -.016 | 0 | %100 |
| 29 | M25 | X | -.13 | -.13 | 0 | %100 |
| 30 | M25 | Z | -.075 | -.075 | 0 | %100 |
| 31 | M26 | X | -.13 | -.13 | 0 | %100 |
| 32 | M26 | Z | -.075 | -.075 | 0 | %100 |
| 33 | M27 | X | -.089 | -.089 | 0 | %100 |
| 34 | M27 | Z | -.051 | -.051 | 0 | %100 |
| 35 | M28 | X | -.089 | -.089 | 0 | %100 |
| 36 | M28 | Z | -.051 | -.051 | 0 | %100 |
| 37 | MP4A | X | -.433 | -.433 | 0 | %100 |
| 38 | MP4A | Z | -.25 | -.25 | 0 | %100 |
| 39 | MP3A | X | -.433 | -.433 | 0 | %100 |
| 40 | MP3A | Z | -.25 | -.25 | 0 | %100 |
| 41 | MP2A | X | -.433 | -.433 | 0 | %100 |
| 42 | MP2A | Z | -.25 | -.25 | 0 | %100 |
| 43 | MP1A | X | -.433 | -.433 | 0 | %100 |
| 44 | MP1A | Z | -.25 | -.25 | 0 | %100 |
| 45 | M44 | X | -.114 | -.114 | 0 | %100 |
| 46 | M44 | Z | -.066 | -.066 | 0 | %100 |
| 47 | M45 | X | -.114 | -.114 | 0 | %100 |
| 48 | M45 | Z | -.066 | -.066 | 0 | %100 |
| 49 | M46 | X | -.114 | -.114 | 0 | %100 |
| 50 | M46 | Z | -.066 | -.066 | 0 | %100 |
| 51 | M47 | X | -.114 | -.114 | 0 | %100 |
| 52 | M47 | Z | -.066 | -.066 | 0 | %100 |
| 53 | M43 | X | -.217 | -.217 | 0 | %100 |
| 54 | M43 | Z | -.125 | -.125 | 0 | %100 |
| 55 | M44A | X | -.404 | -.404 | 0 | %100 |
| 56 | M44A | Z | -.233 | -.233 | 0 | %100 |



Company :
 Designer :
 Job Number :
 Model Name :

Apr 12, 2022
 10:37 AM
 Checked By: _____

Member Distributed Loads (BLC 76 : Structure Wm (330 Deg))

| | Member Label | Direction | Start Magnitude[...] | End Magnitude[lb/ft,F,ksf] | Start Location[ft,%] | End Location[ft,%] |
|----|--------------|-----------|----------------------|----------------------------|----------------------|--------------------|
| 1 | FACE | X | -.227 | -.227 | 0 | %100 |
| 2 | FACE | Z | -.393 | -.393 | 0 | %100 |
| 3 | M2 | X | -.227 | -.227 | 0 | %100 |
| 4 | M2 | Z | -.393 | -.393 | 0 | %100 |
| 5 | M13 | X | -.016 | -.016 | 0 | %100 |
| 6 | M13 | Z | -.029 | -.029 | 0 | %100 |
| 7 | M14 | X | -.016 | -.016 | 0 | %100 |
| 8 | M14 | Z | -.029 | -.029 | 0 | %100 |
| 9 | M15 | X | -.016 | -.016 | 0 | %100 |
| 10 | M15 | Z | -.029 | -.029 | 0 | %100 |
| 11 | M16 | X | -.016 | -.016 | 0 | %100 |
| 12 | M16 | Z | -.029 | -.029 | 0 | %100 |
| 13 | M17 | X | -.189 | -.189 | 0 | %100 |
| 14 | M17 | Z | -.328 | -.328 | 0 | %100 |
| 15 | M18 | X | -.189 | -.189 | 0 | %100 |
| 16 | M18 | Z | -.328 | -.328 | 0 | %100 |
| 17 | M19 | X | -.027 | -.027 | 0 | %100 |
| 18 | M19 | Z | -.047 | -.047 | 0 | %100 |
| 19 | M20 | X | -.027 | -.027 | 0 | %100 |
| 20 | M20 | Z | -.047 | -.047 | 0 | %100 |
| 21 | M21 | X | -.049 | -.049 | 0 | %100 |
| 22 | M21 | Z | -.086 | -.086 | 0 | %100 |
| 23 | M22 | X | -.049 | -.049 | 0 | %100 |
| 24 | M22 | Z | -.086 | -.086 | 0 | %100 |
| 25 | M23 | X | -.049 | -.049 | 0 | %100 |
| 26 | M23 | Z | -.086 | -.086 | 0 | %100 |
| 27 | M24 | X | -.049 | -.049 | 0 | %100 |
| 28 | M24 | Z | -.086 | -.086 | 0 | %100 |
| 29 | M25 | X | -.078 | -.078 | 0 | %100 |
| 30 | M25 | Z | -.136 | -.136 | 0 | %100 |
| 31 | M26 | X | -.078 | -.078 | 0 | %100 |
| 32 | M26 | Z | -.136 | -.136 | 0 | %100 |
| 33 | M27 | X | -.055 | -.055 | 0 | %100 |
| 34 | M27 | Z | -.094 | -.094 | 0 | %100 |
| 35 | M28 | X | -.055 | -.055 | 0 | %100 |
| 36 | M28 | Z | -.094 | -.094 | 0 | %100 |
| 37 | MP4A | X | -.25 | -.25 | 0 | %100 |
| 38 | MP4A | Z | -.433 | -.433 | 0 | %100 |
| 39 | MP3A | X | -.25 | -.25 | 0 | %100 |
| 40 | MP3A | Z | -.433 | -.433 | 0 | %100 |
| 41 | MP2A | X | -.25 | -.25 | 0 | %100 |
| 42 | MP2A | Z | -.433 | -.433 | 0 | %100 |
| 43 | MP1A | X | -.25 | -.25 | 0 | %100 |
| 44 | MP1A | Z | -.433 | -.433 | 0 | %100 |
| 45 | M44 | X | -.066 | -.066 | 0 | %100 |
| 46 | M44 | Z | -.114 | -.114 | 0 | %100 |
| 47 | M45 | X | -.066 | -.066 | 0 | %100 |
| 48 | M45 | Z | -.114 | -.114 | 0 | %100 |
| 49 | M46 | X | -.066 | -.066 | 0 | %100 |
| 50 | M46 | Z | -.114 | -.114 | 0 | %100 |
| 51 | M47 | X | -.066 | -.066 | 0 | %100 |
| 52 | M47 | Z | -.114 | -.114 | 0 | %100 |
| 53 | M43 | X | -.017 | -.017 | 0 | %100 |
| 54 | M43 | Z | -.029 | -.029 | 0 | %100 |
| 55 | M44A | X | -.125 | -.125 | 0 | %100 |
| 56 | M44A | Z | -.216 | -.216 | 0 | %100 |

Member Area Loads

| Joint A | Joint B | Joint C | Joint D | Direction | Distribution | Magnitude[ksf] |
|----------------------|---------|---------|---------|-----------|--------------|----------------|
| No Data to Print ... | | | | | | |

Envelope Joint Reactions

| Joint | X [lb] | LC | Y [lb] | LC | Z [lb] | LC | MX [k-ft] | LC | MY [k-ft] | LC | MZ [k-ft] | LC | | |
|-------|---------|-----|-----------|----|----------|----|-----------|----|-----------|----|-----------|----|-------|----|
| 1 | N35 | max | 1427.222 | 46 | 1186.15 | 13 | 1744.88 | 13 | -.232 | 70 | 0 | 75 | .305 | 45 |
| 2 | | min | -434.864 | 49 | 344.254 | 70 | -438.371 | 7 | -.829 | 13 | 0 | 1 | -.088 | 49 |
| 3 | N36 | max | 440.071 | 10 | 1182.809 | 19 | 503.978 | 7 | -.234 | 64 | 0 | 75 | .299 | 45 |
| 4 | | min | -1428.879 | 40 | 346.239 | 64 | -1457.417 | 1 | -.809 | 19 | 0 | 1 | -.085 | 49 |
| 5 | N63 | max | 279.195 | 12 | 80.575 | 18 | 1043.625 | 12 | 0 | 75 | 0 | 75 | 0 | 75 |
| 6 | | min | -307.537 | 6 | 30.725 | 74 | -1149.655 | 6 | 0 | 1 | 0 | 1 | 0 | 1 |
| 7 | N64 | max | 407.522 | 8 | 80.665 | 20 | 1418.566 | 2 | 0 | 75 | 0 | 75 | 0 | 75 |
| 8 | | min | -379.094 | 2 | 30.724 | 65 | -1524.708 | 8 | 0 | 1 | 0 | 1 | 0 | 1 |
| 9 | Totals: | max | 1708.998 | 10 | 2504.975 | 21 | 2124.503 | 1 | | | | | | |
| 10 | | min | -1708.997 | 4 | 755.524 | 66 | -2124.507 | 7 | | | | | | |

Envelope AISC 15th(360-16): LRFD Steel Code Checks

| Member | Shape | Code Check | Loc[ft] | LC | Shear Ch... | Loc[ft] | Dir | LC | phi*Pnc ... | phi*Pnt [...] | phi*Mn y... | phi*Mn z... | Cb | Eqn |
|--------|-------|------------|---------|--------|-------------|---------|--------|----|-------------|---------------|-------------|-------------|-------|------------|
| 1 | M24 | PL5/8X3.5 | .476 | .531 | 47 | .084 | .437 | y | 1 | 67591.76 | 68906.25 | .897 | 5.024 | 1...H1-1b |
| 2 | M22 | PL5/8X3.5 | .454 | .531 | 48 | .059 | .443 | y | 39 | 67591.76 | 68906.25 | .897 | 5.024 | 1...H1-1b |
| 3 | MP1A | PIPE 2.0 | .404 | 2.333 | 41 | .059 | 2.333 | | 4 | 14916.0... | 32130 | 1.872 | 1.872 | 4...H1-1b |
| 4 | M44A | PIPE 2.0X | .312 | 7.523 | 2 | .006 | 15.046 | | 22 | 5731.424 | 44100 | 2.531 | 2.531 | 1...H1-1a |
| 5 | M15 | PL5/8X3.5 | .271 | 0 | 45 | .148 | 0 | y | 1 | 66184.77 | 68906.25 | .897 | 5.024 | 1...H1-1b |
| 6 | FACE | PIPE 2.5 | .268 | 8.724 | 47 | .081 | 8.854 | | 44 | 14558.7... | 50715 | 3.596 | 3.596 | 2...H1-1b |
| 7 | M2 | PIPE 2.5 | .263 | 9.245 | 8 | .119 | 9.245 | | 8 | 14558.7... | 50715 | 3.596 | 3.596 | 2...H1-1b |
| 8 | M23 | PL5/8X3.5 | .242 | .531 | 14 | .065 | .531 | y | 1 | 67591.76 | 68906.25 | .897 | 5.024 | 1...H1-1b |
| 9 | M16 | PL5/8X3.5 | .228 | 0 | 45 | .190 | .422 | y | 2 | 66184.77 | 68906.25 | .897 | 5.024 | 1...H1-1b |
| 10 | MP4A | PIPE 2.0 | .227 | 5.667 | 49 | .058 | 2.333 | | 10 | 14916.0... | 32130 | 1.872 | 1.872 | 4...H1-1b |
| 11 | M21 | PL5/8X3.5 | .227 | .531 | 49 | .052 | 0 | y | 12 | 67591.76 | 68906.25 | .897 | 5.024 | 1...H1-1b |
| 12 | MP3A | PIPE 2.0 | .219 | 2.333 | 9 | .090 | 2.333 | | 11 | 14916.0... | 32130 | 1.872 | 1.872 | 4...H1-1b |
| 13 | MP2A | PIPE 2.0 | .206 | 2.333 | 3 | .105 | 5.667 | | 8 | 14916.0... | 32130 | 1.872 | 1.872 | 4...H1-1b |
| 14 | M20 | PIPE 2.0 | .199 | 0 | 2 | .079 | 0 | | 21 | 31128.25 | 32130 | 1.872 | 1.872 | 2...H1-1b |
| 15 | M43 | PIPE 2.0X | .188 | 15.046 | 12 | .006 | 15.046 | | 22 | 5731.425 | 44100 | 2.531 | 2.531 | 1...H1-1b* |
| 16 | M17 | PIPE 2.0 | .170 | 0 | 12 | .054 | 0 | | 17 | 31128.25 | 32130 | 1.872 | 1.872 | 2...H1-1b |
| 17 | M19 | PIPE 2.0 | .144 | 0 | 1 | .087 | 0 | | 48 | 31128.25 | 32130 | 1.872 | 1.872 | 1...H1-1b |
| 18 | M13 | PL5/8X3.5 | .138 | .422 | 12 | .166 | .374 | y | 6 | 66184.77 | 68906.25 | .897 | 5.024 | 1...H1-1b |
| 19 | M14 | PL5/8X3.5 | .130 | 0 | 49 | .115 | .422 | y | 2 | 66184.77 | 68906.25 | .897 | 5.024 | 1...H1-1b |
| 20 | M18 | PIPE 2.0 | .112 | 0 | 2 | .055 | 0 | | 14 | 31128.25 | 32130 | 1.872 | 1.872 | 1...H1-1b |
| 21 | M28 | SR 0.75 | .087 | 4.167 | 45 | .020 | 0 | | 47 | 2863.854 | 13916.2... | .174 | .174 | 1...H1-1b* |
| 22 | M47 | SR 0.625 | .063 | 0 | 2 | .012 | 0 | | 11 | 2158.31 | 9664.079 | .101 | .101 | 1...H1-1b* |
| 23 | M26 | SR 0.75 | .045 | 0 | 49 | .017 | 4.167 | | 3 | 2863.854 | 13916.2... | .174 | .174 | 1...H1-1b* |
| 24 | M44 | SR 0.625 | .040 | 1.667 | 11 | .014 | 0 | | 8 | 2158.31 | 9664.079 | .101 | .101 | 1...H1-1b |
| 25 | M46 | SR 0.625 | .035 | 1.667 | 6 | .024 | 0 | | 9 | 2158.31 | 9664.079 | .101 | .101 | 1...H1-1b |
| 26 | M45 | SR 0.625 | .033 | 1.667 | 10 | .023 | 0 | | 10 | 2158.31 | 9664.079 | .101 | .101 | 1...H1-1b |
| 27 | M25 | SR 0.75 | .003 | 4.167 | 45 | .011 | 0 | | 4 | 2863.854 | 13916.2... | .174 | .174 | 1...H1-1b* |
| 28 | M27 | SR 0.75 | .000 | 0 | 75 | .017 | 0 | | 45 | 2863.854 | 13916.2... | .174 | .174 | 1...H1-1a |

Maser Consulting Connecticut

Subject TIA-222-H Adoption and Wind Speed Usage

Site Information Site ID: 469060-VZW / Woodbridge North CT
Site Name: Woodbridge North CT
Carrier Name: Verizon Wireless
Address: 6 Progress Ave
Seymour, Connecticut 06483
New Haven County

Latitude: 41.391528°
Longitude: -73.053333°

Structure Information Tower Type: 250-Ft Self Support
Mount Type: 12.50-Ft Sector Frame

To Whom It May Concern,

We respectfully submit the above referenced Antenna Mount Structural Analysis report in conformance with ANSI/TIA-222-H, Structural Standard for Antenna Supporting Structures and Antennas and Small Wind Turbine Support Structures.

The 2015 International Building Code states that, in Section 3108, telecommunication towers shall be designed and constructed in accordance with the provisions of TIA-222. The TIA-222-H is the latest revision of the TIA-222 Standard, effective as of January 01, 2018.

As with all ANSI standards and engineering best practice is to apply the most current revision of the standard. This ensures the engineer is applying all updates. As an example, the TIA-222-H standard includes updates to bring it in line with the latest AISC and ACI standards and it also incorporates the latest wind speed maps by ASCE 7 based on updated studies of the wind data.

The TIA-222-H standard clarifies these specific requirements for the antenna mount analysis such as modeling methods, seismic analysis, 30-degree increment wind directions and maintenance loading. Therefore, it is our opinion that TIA-222-H is the most appropriate standard for antenna mount structural analysis and is acceptable for use at this tower site to ensure the engineer is taking into account the most current engineering standard available.

Sincerely,



Dejian Xu, PE
Technical Specialist

March 29, 2021

Mr. Andrew Leone
Verizon Wireless
20 Alexander Dr.
Wallingford, CT 06492

Re: Verizon Wireless antenna Model Clarification for CT Siting Council


Dear Mr. Leone,

This letter is intended to clarify and confirm the antenna naming convention used by Verizon Wireless as a part of an antenna upgrade project on numerous wireless facilities.

The antenna naming convention “Licensed Sub-6, L-Sub6, nL-Sub6, VZS01” and any other slight variants refer to the 64T64RMMU antenna manufactured by Samsung Electronics. These names are interchangeable and are used in various documents, including but not limited to the “Antenna Mount Analysis”.


If you have any questions or comments, or require additional information, please do not hesitate to contact me.

Very truly yours,
MASER CONSULTING CONNECTICUT



Petros I. Ioukalis
Connecticut Professional Engineer
License Number: 32577

ATTACHMENT 5





Town of Seymour, CT

Property Listing Report

Map Block Lot

1-05-12N-0

Building # 1

PID

43

Account

015124

Property Information


| | |
|-------------------|---|
| Property Location | 6 PROGRESS AVE |
| Owner | EDMAC LLC |
| Co-Owner | |
| Mailing Address | 2702 FOREST VIEW LANE KISSIMMEE FL 34744 |
| Land Use | 4330 RAD/TV TR |
| Land Class | I |
| Zoning Code | GI-2 |
| Census Tract | |

| | |
|------------------|----------------|
| Neighborhood | D |
| Acreage | 2.15 |
| Utilities | |
| Lot Setting/Desc | Level |
| Book / Page | 285/679 |
| Additional Info | |

Photo



Sketch



Primary Construction Details

| | |
|-------------------|----------------------|
| Year Built | 2001 |
| Building Desc. | RAD/TV TR |
| Building Style | Com Garage |
| Building Grade | Average |
| Stories | 1 |
| Occupancy | 1.00 |
| Exterior Walls | Concr/Cinder |
| Exterior Walls 2 | NA |
| Roof Style | Flat |
| Roof Cover | Rolled Compos |
| Interior Walls | Minim/Masonry |
| Interior Walls 2 | NA |
| Interior Floors 1 | Precast Concr |
| Interior Floors 2 | NA |

| | |
|----------------|-----------------------|
| Heating Fuel | Gas |
| Heating Type | Hot Air-no Duc |
| AC Type | Central |
| Bedrooms | 0 |
| Full Bathrooms | 0 |
| Half Bathrooms | 0 |
| Extra Fixtures | 0 |
| Total Rooms | |
| Bath Style | NA |
| Kitchen Style | NA |
| Rec Rm Area | NA |
| Rec Rm Quality | NA |
| Bsmt Gar | NA |
| Fireplaces | NA |


(*Industrial / Commercial Details)

| | |
|--------------------|-----------------------|
| Building Use | Comm/Ind |
| Building Condition | A |
| Sprinkler % | NA |
| Heat / AC | Heat /AC Split |
| Frame Type | Masonry |
| Baths / Plumbing | None |
| Ceiling / Wall | None |
| Rooms / Prtns | Light |
| Wall Height | 16.00 |
| First Floor Use | 4330 |
| Foundation | NA |

ATTACHMENT 6



**WOODBIDGE NORTH
Certificate of Mailing — Firm**

| | | | |
|--|---|---|---|
| Name and Address of Sender Kenneth C. Baldwin, Esq. Robinson & Cole LLP 280 Trumbull Street Hartford, CT 06103 | TOTAL NO. of Pieces Listed by Sender | TOTAL NO. of Pieces Received at Post Office™ | Affix Stamp Here <i>Postmark with Date of Receipt.</i> neopost SM 05/25/2022 US POSTAGE \$002.99⁰  ZIP 06103 041L12203937 |
| | | 3 | |
| Postmaster, per (name of receiving employee) | | | |
| NO | | | |

| USPS® Tracking Number Firm-specific Identifier | Address (Name, Street, City, State, and ZIP Code™) | Postage | Fee | Special Handling | Parcel Airlift |
|---|--|---------|-----|------------------|----------------|
| 1. | Annmarie Drugonis, First Selectwoman Town of Seymour 1 First Street Seymour, CT 06483 | | | | |
| 2. | Keith Rosenfeld, Town Planner Town of Seymour 1 First Street Seymour, CT 06483 | | | | |
| 3. | EMAC LLC Attn: Edward MacConnie 2702 Forest View Lane Kissimmee, FL 34744 | | | | |
| 4. | | | | | |
| 5. | | | | | |
| 6. | | | | | |

