



August 15th, 2018

Melanie Bachman, Executive Director
Connecticut Siting Council
10 Franklin Square
New Britain, CT 06051



RE: Notice of Exempt Modification – Antenna Swap for wireless facility located at 14 OXFORD DRIVE, SHELTON, CONNECTICUT – CT03XC366 (lat. 41° 16' 48.741" N, long. -73° 11' 07.441" W)

Dear Ms. Bachman:

Sprint Spectrum, LP ("Sprint") currently maintains wireless telecommunications antennas at the ~~155~~-foot level) on an existing ~~200~~-foot ~~Self-Support~~ Tower) at the above-referenced address. The property and the tower are owned by AMERICAN TOWER CORPORATION.

Sprint's proposed work involves antenna replacement and tower work. Sprint intends to replace three (3) antennas, add an additional three (3) antennas, and add three (3) new RRHs onto the tower. All the proposed work is contained within the existing fenced area. Please refer to the attached drawings for site plans prepared by Infinigy Engineering.

Please accept this letter as notification pursuant to R.C.S.A. § 16-50j-73, for construction that constitutes an exempt modification pursuant to R.C.S.A. § 16-50j-72(b). In accordance with R.C.S.A. § 16-50j-73, a copy of this letter is being sent to MARK LAURETTI, MAYOR and RICK SHULTZ, PLANNING AND ZONING ADMINISTRATOR of the Town of SHELTON. A copy of this letter is also being sent to JUSTINE PAUL the manager for AMERICAN TOWER CORPORATION who manages the tower and owns the land.

The planned modifications to the facility fall squarely within those activities explicitly provided for in R.C.S.A. § 16-50j-72(b).

1. The proposed modifications will not result in an increase in the height of the existing tower.
2. The antennas work is a one-for-one replacement of facility components.
3. The proposed modifications will include the addition of ground base equipment as depicted on the attached drawings; however, the proposed equipment will not require



an extension of the site boundaries.

4. The proposed modifications will not increase noise levels at the facility by six decibels or more.
5. The additional ground based equipment will not increase radio frequency (RF) emissions at the facility to a level at or above the Federal Communications Commission (FCC) adopted safety standard.

For the foregoing reasons, Sprint respectfully submits that the proposed modifications to the above referenced telecommunications facility constitutes an exempt modification under R.C.S.A. § 16-50j-72(b).

If you have any questions or require any additional information regarding this request, please do not hesitate to give me a call at (518) 350-4222 or email me to aperkowski@airosmithdevelopment.com

Kind Regards,

A handwritten signature in black ink, appearing to read 'Arthur Perkowski', is written over a horizontal line.

Arthur Perkowski
Airosmith Development Inc.
32 Clinton Street
Saratoga Springs, NY 12866
518-306-1711 desk & fax
518-871-3707 cell
aperkowski@airosmithdevelopment.com

Attachment

CC: Mark Lauretti (MAYOR, Shelton, CT)
Justine Paul (American Tower Corporation)
Rick Shultz (Planning and Zoning Administrator, Shelton, CT)

7018 0680 0002 1201 5197

U.S. Postal Service™ CERTIFIED MAIL® RECEIPT Domestic Mail Only


For delivery information, visit our website at www.usps.com®.

SHELTON, CT 06484

Certified Mail Fee	\$3.45	0867
Extra Services & Fees (check box, add fee as appropriate)	\$2.75	77
<input type="checkbox"/> Return Receipt (hardcopy)	\$0.00	
<input type="checkbox"/> Return Receipt (electronic)	\$0.00	
<input type="checkbox"/> Certified Mail Restricted Delivery	\$0.00	
<input type="checkbox"/> Adult Signature Required	\$0.00	
<input type="checkbox"/> Adult Signature Restricted Delivery	\$0.00	
Postage	\$0.50	
Total Postage and Fees	\$6.70	

Sent To: **Mark Lausetti** NY 12858 CT03XC266
 Street and Apt. No., or PO Box No.: **521 Hill St**
 City, State, ZIP+4®: **Shelton CT 06484**

PS Form 3800, April 2015 PSN 7530-02-000-9047 See Reverse for Instructions



9175 1202 1201 5166

U.S. Postal Service™ CERTIFIED MAIL® RECEIPT Domestic Mail Only

For delivery information, visit our website at www.usps.com®.

WOBBURN, MA 01801

Certified Mail Fee	\$3.45	0867
Extra Services & Fees (check box, add fee as appropriate)	\$2.75	77
<input type="checkbox"/> Return Receipt (hardcopy)	\$0.00	
<input type="checkbox"/> Return Receipt (electronic)	\$0.00	
<input type="checkbox"/> Certified Mail Restricted Delivery	\$0.00	
<input type="checkbox"/> Adult Signature Required	\$0.00	
<input type="checkbox"/> Adult Signature Restricted Delivery	\$0.00	
Postage	\$0.50	
Total Postage and Fees	\$6.70	

Sent To: **Justice Paul** CT03XC366
 Street and Apt. No., or PO Box No.: **10 Presidential way**
 City, State, ZIP+4®: **Woburn MA 01801**

PS Form 3800, April 2015 PSN 7530-02-000-9047 See Reverse for Instructions



7018 0680 0002 1201 5203

U.S. Postal Service™ CERTIFIED MAIL® RECEIPT Domestic Mail Only

For delivery information, visit our website at www.usps.com®.

SHELTON, CT 06484

Certified Mail Fee	\$3.45	0867
Extra Services & Fees (check box, add fee as appropriate)	\$2.75	77
<input type="checkbox"/> Return Receipt (hardcopy)	\$0.00	
<input type="checkbox"/> Return Receipt (electronic)	\$0.00	
<input type="checkbox"/> Certified Mail Restricted Delivery	\$0.00	
<input type="checkbox"/> Adult Signature Required	\$0.00	
<input type="checkbox"/> Adult Signature Restricted Delivery	\$0.00	
Postage	\$0.50	
Total Postage and Fees	\$6.70	

Sent To: **Ren Shute** CT03XC366
 Street and Apt. No., or PO Box No.: **521 Hill St**
 City, State, ZIP+4®: **Shelton CT 06484**

PS Form 3800, April 2015 PSN 7530-02-000-9047 See Reverse for Instructions







City of Shelton, Connecticut - Parcel Map

Parcels: 33.-13

Address: 20 OXFORD DR



Approximate Scale: 1:1,200



Map Produced
April 2017

Disclaimer: This map is for informational purposes only. All information is subject to verification by any user. The City of Shelton and its mapping contractors assume no legal responsibility for the information contained herein.



RADIO FREQUENCY EMISSIONS ANALYSIS REPORT EVALUATION OF HUMAN EXPOSURE POTENTIAL TO NON-IONIZING EMISSIONS

SPRINT Existing Facility

Site ID: CT03XC366

Booth Hill
14 Oxford Drive
Shelton, CT 06484

August 5, 2018

EBI Project Number: 6218005335

Site Compliance Summary	
Compliance Status:	COMPLIANT
Site total MPE% of FCC general population allowable limit:	7.24 %



August 5, 2018

SPRINT

Attn: RF Engineering Manager
1 International Boulevard, Suite 800
Mahwah, NJ 07495

Emissions Analysis for Site: **CT03XC366 – Booth Hill**

EBI Consulting was directed to analyze the proposed SPRINT facility located at **14 Oxford Drive, Shelton, CT**, for the purpose of determining whether the emissions from the Proposed SPRINT Antenna Installation located on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter ($\mu\text{W}/\text{cm}^2$). The number of $\mu\text{W}/\text{cm}^2$ calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits, therefore it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) – (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general population may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general population would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

General population exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter ($\mu\text{W}/\text{cm}^2$). The general population exposure limits for the 850 MHz Band is approximately $567 \mu\text{W}/\text{cm}^2$. The general population exposure limit for the 1900 MHz (PCS) and 2500 MHz (BRS) bands is $1000 \mu\text{W}/\text{cm}^2$. Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.



Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure. Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

CALCULATIONS

Calculations were done for the proposed SPRINT Wireless antenna facility located at **14 Oxford Drive, Shelton, CT**, using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. Since SPRINT is proposing highly focused directional panel antennas, which project most of the emitted energy out toward the horizon, all calculations were performed assuming a lobe representing the maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB for directional panel antennas, was focused at the base of the tower. For this report the sample point is the top of a 6-foot person standing at the base of the tower.

For all calculations, all equipment was calculated using the following assumptions:

- 1) 1 CDMA channels (850 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 20 Watts per Channel.
- 2) 2 LTE channels (850 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 50 Watts per Channel.
- 3) 5 CDMA channels (1900 MHz (PCS)) were considered for each sector of the proposed installation. These Channels have a transmit power of 16 Watts per Channel.
- 4) 2 LTE channels (1900 MHz (PCS)) were considered for each sector of the proposed installation. These Channels have a transmit power of 40 Watts per Channel.
- 5) 8 LTE channels (2500 MHz (BRS)) were considered for each sector of the proposed installation. These Channels have a transmit power of 20 Watts per Channel.



- 6) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 - Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.
- 7) For the following calculations, the sample point was the top of a 6-foot person standing at the base of the tower. The maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB for directional panel antennas, was used in this direction. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 8) The antennas used in this modeling are the **Commscope NNVV-65B-R4 and the Nokia AAHC** for transmission in the 850 MHz, 1900 MHz (PCS) and 2500 MHz (BRS) frequency bands. This is based on feedback from the carrier with regards to anticipated antenna selection. Maximum gain values for all antennas are listed in the Inventory and Power Data table below. The maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB for directional panel antennas, was used for all calculations. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 9) The antenna mounting height centerlines of the proposed panel antennas are **155 feet** above ground level (AGL) for **Sector A**, **155 feet** above ground level (AGL) for **Sector B** and **155 feet** above ground level (AGL) for Sector C.
- 10) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.

All calculations were done with respect to uncontrolled / general population threshold limits.



SPRINT Site Inventory and Power Data by Antenna

Sector:	A	Sector:	B	Sector:	C
Antenna #:	1	Antenna #:	1	Antenna #:	1
Make / Model:	Commscope NNVV-65B-R4	Make / Model:	Commscope NNVV-65B-R4	Make / Model:	Commscope NNVV-65B-R4
Gain:	12.75 / 15.05 dBd	Gain:	12.75 / 15.05 dBd	Gain:	12.75 / 15.05 dBd
Height (AGL):	155 feet	Height (AGL):	155 feet	Height (AGL):	155 feet
Frequency Bands	850 MHz / 1900 MHz (PCS)	Frequency Bands	850 MHz / 1900 MHz (PCS)	Frequency Bands	850 MHz / 1900 MHz (PCS)
Channel Count	10	Channel Count	10	Channel Count	10
Total TX Power(W):	280 Watts	Total TX Power(W):	280 Watts	Total TX Power(W):	280 Watts
ERP (W):	7,378.61	ERP (W):	7,378.61	ERP (W):	7,378.61
Antenna A1 MPE%	1.47 %	Antenna B1 MPE%	1.47 %	Antenna C1 MPE%	1.47 %
Antenna #:	2	Antenna #:	2	Antenna #:	2
Make / Model:	Nokia AAHC	Make / Model:	Nokia AAHC	Make / Model:	Nokia AAHC
Gain:	15.05 dBd	Gain:	15.05 dBd	Gain:	15.05 dBd
Height (AGL):	155 feet	Height (AGL):	155 feet	Height (AGL):	155 feet
Frequency Bands	2500 MHz (BRS)	Frequency Bands	2500 MHz (BRS)	Frequency Bands	2500 MHz (BRS)
Channel Count	8	Channel Count	8	Channel Count	8
Total TX Power(W):	160 Watts	Total TX Power(W):	160 Watts	Total TX Power(W):	160 Watts
ERP (W):	5,118.23	ERP (W):	5,118.23	ERP (W):	5,118.23
Antenna A2 MPE%	0.83 %	Antenna B2 MPE%	0.83 %	Antenna C2 MPE%	0.83 %

Site Composite MPE%	
Carrier	MPE%
SPRINT – Max per sector	2.30 %
AT&T	3.02 %
Clearwire	0.11 %
Dept. Pub. Safety	0.14 %
PageNet	0.13 %
Nextel	0.56 %
Dept. Homeland Security	0.73 %
Light Squared, Inc	0.25 %
Site Total MPE %:	7.24 %

SPRINT Sector A Total:	2.30 %
SPRINT Sector B Total:	2.30 %
SPRINT Sector C Total:	2.30 %
Site Total:	7.24 %

SPRINT _ Frequency Band / Technology (Per Sector)	# Channels	Watts ERP (Per Channel)	Height (feet)	Total Power Density ($\mu\text{W}/\text{cm}^2$)	Frequency (MHz)	Allowable MPE ($\mu\text{W}/\text{cm}^2$)	Calculated % MPE
Sprint 850 MHz CDMA	1	376.73	155	0.61	850 MHz	567	0.11%
Sprint 850 MHz LTE	2	941.82	155	3.05	850 MHz	567	0.54%
Sprint 1900 MHz (PCS) CDMA	5	511.82	155	4.14	1900 MHz (PCS)	1000	0.41%
Sprint 1900 MHz (PCS) LTE	2	1,279.56	155	4.14	1900 MHz (PCS)	1000	0.41%
Sprint 2500 MHz (BRS) LTE	8	639.78	155	8.29	2500 MHz (BRS)	1000	0.83%
						Total:	2.30%

Summary

All calculations performed for this analysis yielded results that were **within** the allowable limits for general population exposure to RF Emissions.

The anticipated maximum composite contributions from the SPRINT facility as well as the site composite emissions value with regards to compliance with FCC's allowable limits for general population exposure to RF Emissions are shown here:

SPRINT Sector	Power Density Value (%)
Sector A:	2.30 %
Sector B:	2.30 %
Sector C:	2.30 %
SPRINT Maximum MPE % (per sector):	2.30 %
Site Total:	7.24 %
Site Compliance Status:	COMPLIANT

The anticipated composite MPE value for this site assuming all carriers present is **7.24 %** of the allowable FCC established general population limit sampled at the ground level. This is based upon values listed in the Connecticut Siting Council database for existing carrier emissions.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.

INFINIGY®

FROM ZERO TO INFINIGY
the solutions are endless


1033 WATERVLIEET SHAKER RD, ALBANY, NY 12205

Mount Analysis Report

June 2, 2018

Site Number	CT03XC366
Infinigy Job Number	526-104
Client	Airosmith
Carrier	Sprint
Site Location	14 Oxford Drive / Booth Hill Rd Shelton , CT 06484 41.28016° N NAD83 73.18546° W NAD83
Mount Centerline EL.	155.0 ft
Mount Classification	Pipe Mount
Usage	44.7%
Overall Result	Pass
Notes	Install 2.875" OD Sch 40 mount pipe to existing brackets. Bottom of panel to be no greater than 12" from nearest tower bracket.

Upon reviewing the results of this analysis, it is our opinion that the mount meets the specified TIA code requirements. The mounts and connections for the proposed carrier are therefore deemed adequate to support the final loading configuration as listed in this report.



Nathaniel R. Ober, E.I.T.
Northeast Structural Region Lead

AZ CA CO FL GA MD NC NH NJ NY TX WA

INFINIGY®

Contents

Introduction.....	3
Supporting Documentation.....	3
Analysis Code Requirements.....	3
Conclusion.....	3
Final Configuration Loading.....	4
Structure Usages.....	4
Assumptions and Limitations.....	4
Calculations.....	Appended

Introduction

Infinigy Engineering has been requested to perform a mount analysis on the existing Sprint mounts. All supporting documents have been obtained from the client and are assumed to be accurate and applicable to this site. The mount was analyzed using RISA-3D Version 16.0.3 analysis software.

Supporting Documentation

Colo App	ATC Project # OAA715175, dated April 13, 2018
-----------------	---

Analysis Code Requirements

Wind Speed	97 mph (3-Second Gust, V_{ASD}) / 125 mph (3-Second Gust, V_{ULT})
Wind Speed w/ ice	50 mph (3-Second Gust, V_{ASD}) w/ 3/4" ice
TIA Revision	ANSI/TIA-222-G
Adopted IBC	2012 IBC
Structure Class	II
Exposure Category	B
Topographic Category	1
Calculated Crest Height	0 ft

Conclusion

Upon reviewing the results of this analysis, it is our opinion that the mount meets the specified TIA code requirements. The mounts and connections for the proposed carrier are therefore deemed adequate to support the final loading configuration as listed in this report.

If you have any questions, require additional information, or actual conditions differ from those as detailed in this report please contact me via the information below:

Nathaniel R Ober E.I.T.
 Northeast Structural Region Lead | Infinigy
 1033 Watervliet Shaker Road, Albany, NY 12205
 (O) (518) 690-0790 | (M) (303) 704-0322
nober@infinigy.com | www.infinigy.com

Final Configuration Loading

Mount CL (ft)	Rad. HT (ft)	Vert. O/S (ft)	Horiz. O/S (ft) ⁽¹⁾	Qty	Appurtenance ^{(2),(3)}	Carrier
155.0	155.0	0.0	N/A	3	RFS APXVSP18-C-A20	Sprint
				3	Nokia AAHC	
				6	Alcatel-Lucent 800 MHz 2x50 RRH	
				3	Alcatel-Lucent TD-RRH 8x20	

(1)Horizontal Offset is defined as the distance from the left most edge of the mount face horizontal when viewed facing the tower.

(2)Radios are mounted behind antennas at respective locations see appended documents for vertical locations.

Structure Usages


Mount Pipe	44.7	Pass
Results	44.7	Pass

Assumptions and Limitations

Our structural calculations are completed assuming all information provided to Infinigy Engineering is accurate and applicable to this site. For the purposes of calculations, we assume an overall structure condition of “like new” and all members and connections to be free of corrosion and/or structural defects. The structure owner and/or contractor shall verify the structure’s condition prior to installation of any proposed equipment. If actual conditions differ from those described in this report Infinigy Engineering should be notified immediately to complete a revised evaluation.

Our evaluation is completed using standard TIA, AISC, ACI, and ASCE methods and procedures. Our structural results are proprietary and should not be used by others as their own. Infinigy Engineering is not responsible for decisions made by others that are or are not based on our supplied assumptions and conclusions.

This report is an evaluation of the proposed carriers mount structure only and does not reflect adequacy of the existing tower, other mounts, or coax mounting attachments. These elements are assumed to be adequate for the purposes of this analysis and are assumed to have been installed per their manufacturer requirements.



Envelope Only Solution

Infingy Engineering	CT03XC366	
NRO		June 2, 2018 at 8:51 PM
526-104		CT03XC366.r3d

Member Primary Data

	Label	I Joint	J Joint	K Joint	Rotate(deg)	Section/Shape	Type	Design List	Material	Design Rules
1	MP1	N1	N2			HR1	Beam	None	A53 GR B	Typical

Material Takeoff

	Material	Size	Pieces	Length[in]	Weight[LB]
1	Hot Rolled Steel				
2	A53 GR B	PIPE_2.5	1	240	109.6
3	Total HR Steel		1	240	109.6

Basic Load Cases

	BLC Description	Category	X Gravity	Y Gravity	Z Gravity	Joint	Point	Distribut..	Area(M...	Surface...
1	Self Weight	DL		-1			4			
2	Wind Load AZI 000	WLZ					4		1	
3	Wind Load AZI 090	WLX					4		1	
4	Ice Weight	OL1					4			
5	Wind + Ice Load AZI 000	OL2					4		1	
6	Wind + Ice Load AZI 090	OL3					4		1	
7	Service Live 1	LL								
8	BLC 2 Transient Area Loads	None						1		
9	BLC 3 Transient Area Loads	None						1		
10	BLC 5 Transient Area Loads	None						1		

Load Combinations

	Description	So...	P...	S...	BLCFac..	BLCFac..	BLCFac..	BLCFac..	BLCFac..	BLCFac..	BLCFac..	BLCFac..	BLCFac..	BLCFac..	BLCFac..
1	1.4D	Yes	Y		DL	1.4									
2	1.2D + 1.6W AZI 000	Yes	Y		DL	1.2	W...	1.6							
3	1.2D + 1.6W AZI 030	Yes	Y		DL	1.2	W...	1.3...	W...	.8					
4	1.2D + 1.6W AZI 060	Yes	Y		DL	1.2	W...	.8	W...	1.3...					
5	1.2D + 1.6W AZI 090	Yes	Y		DL	1.2			W...	1.6					
6	1.2D + 1.6W AZI 120	Yes	Y		DL	1.2	W...	.8	W...	1.3...					
7	1.2D + 1.6W AZI 150	Yes	Y		DL	1.2	W...	-1.3...	W...	.8					
8	1.2D + 1.6W AZI 180	Yes	Y		DL	1.2	W...	-1.6							
9	1.2D + 1.6W AZI 210	Yes	Y		DL	1.2	W...	-1.3...	W...	-.8					
10	1.2D + 1.6W AZI 240	Yes	Y		DL	1.2	W...	-.8	W...	-1.3...					
11	1.2D + 1.6W AZI 270	Yes	Y		DL	1.2			W...	-1.6					
12	1.2D + 1.6W AZI 300	Yes	Y		DL	1.2	W...	.8	W...	-1.3...					
13	1.2D + 1.6W AZI 330	Yes	Y		DL	1.2	W...	1.3...	W...	-.8					
14	0.9D + 1.6W AZI 000	Yes	Y		DL	.9	W...	1.6							
15	0.9D + 1.6W AZI 030	Yes	Y		DL	.9	W...	1.3...	W...	.8					
16	0.9D + 1.6W AZI 060	Yes	Y		DL	.9	W...	.8	W...	1.3...					
17	0.9D + 1.6W AZI 090	Yes	Y		DL	.9			W...	1.6					
18	0.9D + 1.6W AZI 120	Yes	Y		DL	.9	W...	-.8	W...	1.3...					
19	0.9D + 1.6W AZI 150	Yes	Y		DL	.9	W...	-1.3...	W...	.8					
20	0.9D + 1.6W AZI 180	Yes	Y		DL	.9	W...	-1.6							
21	0.9D + 1.6W AZI 210	Yes	Y		DL	.9	W...	-1.3...	W...	-.8					
22	0.9D + 1.6W AZI 240	Yes	Y		DL	.9	W...	-.8	W...	-1.3...					
23	0.9D + 1.6W AZI 270	Yes	Y		DL	.9			W...	-1.6					
24	0.9D + 1.6W AZI 300	Yes	Y		DL	.9	W...	.8	W...	-1.3...					
25	0.9D + 1.6W AZI 330	Yes	Y		DL	.9	W...	1.3...	W...	-.8					
26	1.2D + 1.0Di	Yes	Y		DL	1.2	OL1	1							
27	1.2D + 1.0Di + 1.0Wi A...	Yes	Y		DL	1.2	OL1	1	OL2	1					
28	1.2D + 1.0Di + 1.0Wi A...	Yes	Y		DL	1.2	OL1	1	OL2	.866	OL3	.5			

Load Combinations (Continued)

	Description	So...	P...	S...	BLCFac..	BLCFac..	BLCFac..	BLCFac..	BLCFac..	BLCFac..	BLCFac..	BLCFac..	BLCFac..	BLCFac..
29	1.2D + 1.0Di + 1.0Wi A...	Yes	Y		DL 1.2	OL1 1	OL2 .5	OL3 .866						
30	1.2D + 1.0Di + 1.0Wi A...	Yes	Y		DL 1.2	OL1 1		OL3 1						
31	1.2D + 1.0Di + 1.0Wi A...	Yes	Y		DL 1.2	OL1 1	OL2 -.5	OL3 .866						
32	1.2D + 1.0Di + 1.0Wi A...	Yes	Y		DL 1.2	OL1 1	OL2 -.866	OL3 .5						
33	1.2D + 1.0Di + 1.0Wi A...	Yes	Y		DL 1.2	OL1 1	OL2 -.1							
34	1.2D + 1.0Di + 1.0Wi A...	Yes	Y		DL 1.2	OL1 1	OL2 -.866	OL3 -.5						
35	1.2D + 1.0Di + 1.0Wi A...	Yes	Y		DL 1.2	OL1 1	OL2 -.5	OL3 -.866						
36	1.2D + 1.0Di + 1.0Wi A...	Yes	Y		DL 1.2	OL1 1		OL3 -.1						
37	1.2D + 1.0Di + 1.0Wi A...	Yes	Y		DL 1.2	OL1 1	OL2 .5	OL3 -.866						
38	1.2D + 1.0Di + 1.0Wi A...	Yes	Y		DL 1.2	OL1 1	OL2 .866	OL3 -.5						
39	1.2D + 1.5L + 1.0WL (...)	Yes	Y		DL 1.2	LL 1.5	W...	.111						
40	1.2D + 1.5L + 1.0WL (...)	Yes	Y		DL 1.2	LL 1.5	W...	.096	W...	.056				
41	1.2D + 1.5L + 1.0WL (...)	Yes	Y		DL 1.2	LL 1.5	W...	.056	W...	.096				
42	1.2D + 1.5L + 1.0WL (...)	Yes	Y		DL 1.2	LL 1.5			W...	.111				
43	1.2D + 1.5L + 1.0WL (...)	Yes	Y		DL 1.2	LL 1.5	W...	-.056	W...	.096				
44	1.2D + 1.5L + 1.0WL (...)	Yes	Y		DL 1.2	LL 1.5	W...	-.096	W...	.056				
45	1.2D + 1.5L + 1.0WL (...)	Yes	Y		DL 1.2	LL 1.5	W...	-.111						
46	1.2D + 1.5L + 1.0WL (...)	Yes	Y		DL 1.2	LL 1.5	W...	-.096	W...	-.056				
47	1.2D + 1.5L + 1.0WL (...)	Yes	Y		DL 1.2	LL 1.5	W...	-.056	W...	-.096				
48	1.2D + 1.5L + 1.0WL (...)	Yes	Y		DL 1.2	LL 1.5			W...	-.111				
49	1.2D + 1.5L + 1.0WL (...)	Yes	Y		DL 1.2	LL 1.5	W...	.056	W...	-.096				
50	1.2D + 1.5L + 1.0WL (...)	Yes	Y		DL 1.2	LL 1.5	W...	.096	W...	-.056				

Envelope Joint Reactions

	Joint		X [lb]	LC	Y [lb]	LC	Z [lb]	LC	MX [lb-ft]	LC	MY [lb-ft]	LC	MZ [lb-ft]	LC
1	N4	max	578.823	5	664.744	26	824.929	2	0	1	0	1	0	1
2		min	-578.823	11	224.036	14	-824.929	8	0	1	0	1	0	1
3	N1	max	16.379	17	110.349	26	9.856	27	0	1	NC	NC	0	1
4		min	-16.379	23	55.297	14	-9.856	33	0	1	NC	NC	0	1
5	Totals:	max	594.973	17	775.093	26	815.597	2						
6		min	-594.973	23	279.333	14	-815.597	8						

Envelope AISC 14th(360-10): LRFD Steel Code Checks

Member	Shape	Code Check	Lo.....	Shear C...	Loc[in]...	LC	phi*Pnc...	phi*Pnt...	phi*...	phi*...	Eqn
1	MP1 PIPE_2.5	.447	15...	.027	157.5	2	5687.028	50715	3596...	3596...	H1-...



AMERICAN TOWER®
CORPORATION

Structural Analysis Report

Structure : 200 ft Self Supported Tower
ATC Site Name : Shelton-Trumbull, CT
ATC Site Number : 88017
Engineering Number : OAA715175_C3_03
Proposed Carrier : Sprint Nextel
Carrier Site Name : Booth Hill
Carrier Site Number : CT03XC366
Site Location : 14 Oxford Drive-Booth Hill RD
Shelton, CT 06484-3455
41.280200,-73.185500
County : Fairfield
Date : March 21, 2018
Max Usage : 95%
Result : Pass

Prepared By:
Charles Dalton Wally, E.I.
Structural Engineer I

Reviewed By:

COA: PEC.0001553



Table of Contents

Introduction	1
Supporting Documents	1
Analysis	1
Conclusion.....	1
Existing and Reserved Equipment.....	2
Equipment to be Removed.....	2
Proposed Equipment	3
Structure Usages	3
Foundations	3
Standard Conditions	4
Calculations	Attached



Introduction

The purpose of this report is to summarize results of a structural analysis performed on the 200 ft self supported tower to reflect the change in loading by Sprint Nextel.

Supporting Documents

Tower Drawings	TEP Job #070851, dated May 30, 2007
Foundation Drawing	Radio Relay Drawing #MS 10478, dated January 27, 1965
Geotechnical Report	Radio Relay Drawing #MS 10478, dated January 27, 1965
Modifications	ATC Project #40480232, dated July 13, 2007

Analysis

The tower was analyzed using Power Lines Systems, Inc.'s tower analysis software. This program considers an elastic three-dimensional model and second-order effects per ANSI/TIA-222.

Basic Wind Speed:	97 mph (3-Second Gust, V_{asd}) / 125 mph (3-Second Gust, V_{ult})
Basic Wind Speed w/ Ice:	50 mph (3-Second Gust) w/ 1/2" radial ice concurrent
Code:	ANSI/TIA-222-G / 2012 IBC / 2016 Connecticut State Building Code
Structure Class:	II
Exposure Category:	B
Topographic Category:	1
Crest Height:	0 ft

Conclusion

Based on the analysis results, the structure meets the requirements per the applicable codes listed above. The tower and foundation can support the equipment as described in this report.

If you have any questions or require additional information, please contact American Tower via email at Engineering@americantower.com. Please include the American Tower site name, site number, and engineering number in the subject line for any questions.



Existing and Reserved Equipment

Elevation ¹ (ft)		Qty	Antenna	Mount Type	Lines	Carrier
Mount	RAD					
200.0	212.0	2	5' Yagi	Platform w/ Handrails	(2) EW65 (3) 1 5/8" Coax (1) 1/2" Coax	Other
	213.0	1	20' Omni			
	210.0	1	Telewave ANT900D6-9			
	206.0	2	RFS PA6-65AC w/ Radome			
	205.0	1	Sinclair SC442D-HF1LDF			
182.0	190.0	6	Sinclair SC479-HF1LDF	Side Arm	(10) 1 5/8" Coax (5) 0.63" LDF4-50A	State Of CT
	185.0	5	TTA			
	180.0	2	Kathrein AP14-850/105			
	177.0	1	5' Dipole			
169.0	169.0	12	TX RX Systems 101-83B-09-0-03	Sector Frame	(12) 1 5/8" Coax	Sprint Nextel
158.0	158.0	4	DragonWave Horizon Compact	Side Arm	(6) 5/16" Coax (4) 1/2" Coax	Clearwire
		1	DragonWave A-ANT-11G-2-C			
		1	Andrew PX2F-52			
		2	DragonWave A-ANT-11G-3-C			
	156.0	3	NextNet BTS-2500			
155.0	155.0	3	Argus LLPX310R			
155.0	155.0	3	Alcatel-Lucent 1900MHz 4X45 RRH	Sector Frames	(3) 1 1/4" Hybriflex	Sprint Nextel
		3	Alcatel-Lucent 800MHz RRH w/ Notch Filter			
		3	RFS APXVSPP18-C-A20			
150.0	150.0	1	18" x 12" Junction Box	Leg	(2) 2" conduit	Clearwire
145.0	144.0	6	Powerwave 7020.00 Dual Band RET	Sector Frames	(6) 1 5/8" Coax (2) 0.78" 8 AWG 6 (2) 0.74" 8 AWG 7 (2) 3" conduit (1) 0.28" RG-6 (1) 0.39" Fiber Trunk	AT&T Mobility
		6	Powerwave LGP21401			
		2	Raycap DC6-48-60-18-8F			
		3	Ericsson RRUS 11 (Band 12) (55 lb)			
		3	Ericsson RRUS 32			
		3	Ericsson RRUS 32 B2			
		3	Ericsson RRUS 32 B66			
		3	Powerwave 7770.00			
		3	Quintel QS66512-6			
3	CCI HPA-65R-BUU-H6					
124.0	124.0	1	RFS PA6-65AC w/ Radome	Leg	(1) EW65	State Of CT
101.0	111.0	1	Andrew DB616E-BC	Leg	(1) 7/8" Coax	US Dept Of Homeland Security
82.0	86.0	1	Kathrein 750 10074	Stand-Off	(1) 1 5/8" Coax	Ligado Networks

Equipment to be Removed

Elevation ¹ (ft)		Qty	Antenna	Mount Type	Lines	Carrier
Mount	RAD					
155.0	155.0	6	Andrew DB980H90E-M	-	(6) 1 5/8" Coax	Sprint Nextel



Proposed Equipment

Elevation ¹ (ft)		Qty	Antenna	Mount Type	Lines	Carrier
Mount	RAD					
155.0	155.0	3	Alcatel-Lucent RRH2x50-08	Sector Frames w/ New Pipes	(1) 1 1/4" Hybriflex	Sprint Nextel
		3	Alcatel-Lucent TD-RRH8x20-25 w/ Solar Shield			
		3	Commscope DT465B-2XR			
56.0	56.0	1	GPS	Side Arm	(1) 1/2" Coax	

¹Mount elevation is defined as height above bottom of steel structure to the bottom of mount, RAD elevation is defined as center of antenna above ground level (AGL).

Install proposed coax stacked on top of existing Sprint Nextel coax.

Structure Usages

Structural Component	Controlling Usage	Pass/Fail
Legs	63%	Pass
Diagonals	94%	Pass
Truss Diagonals	95%	Pass
Horizontals	88%	Pass
Truss Horizontals	47%	Pass
Anchor Bolts	44%	Pass

Foundations

Reaction Component	Analysis Reactions	% of Usage
Uplift (Kips)	185.9	53%
Axial (Kips)	292.8	10%

The structure base reactions resulting from this analysis were found to be acceptable through analysis based on geotechnical and foundation information, therefore no modification or reinforcement of the foundation will be required.



Standard Conditions

All engineering services performed by A.T. Engineering Service, PLLC are prepared on the basis that the information used is current and correct. This information may consist of, but is not limited to the following:



- Information supplied by the client regarding antenna, mounts and feed line loading
- Information from drawings, design and analysis documents, and field notes in the possession of A.T. Engineering Service, PLLC

It is the responsibility of the client to ensure that the information provided to A.T. Engineering Service, PLLC and used in the performance of our engineering services is correct and complete.

All assets of American Tower Corporation, its affiliates and subsidiaries (collectively "American Tower") are inspected at regular intervals. Based upon these inspections and in the absence of information to the contrary, American Tower assumes that all structures were constructed in accordance with the drawings and specifications.

Unless explicitly agreed by both the client and A.T. Engineering Service, PLLC, all services will be performed in accordance with the current revision of ANSI/TIA-222.

All services are performed, results obtained, and recommendations made in accordance with generally accepted engineering principles and practices. A.T. Engineering Service, PLLC is not responsible for the conclusions, opinions and recommendations made by others based on the information supplied herein.



Project Name : 88017 - Shelton/Trumbull
 Project Notes:
 Project File : N:\L2 - ATC\88017\2018.03.12 - Sprint Nextel - OAA715175\2018.03.12 - Sprint Nextel - OAA715175.tow
 Date run : 4:56:08 PM Wednesday, March 21, 2018
 by : Tower Version 15.00
 Licensed to : American Tower Corp.

Successfully performed nonlinear analysis

Member check option: ANSI/TIA 222-G-1
 Connection rupture check: Not Checked
 Crossing diagonal check: Fixed
 Included angle check: None
 Climbing load check: None
 Redundant members checked with: Actual Force
 Loads from file: n:\l2 - atc\88017\2018.03.12 - sprint nextel - oaa715175\2018.03.12 - sprint nextel - oaa715175.eia

*** Analysis Results:

Maximum element usage is 94.96% for Angle 'LD 3X' in load case 'W -90'

Summary of Joint Support Reactions For All Load Cases:

Load Case	Joint Label	Long. Force (kips)	Tran. Force (kips)	Vert. Force (kips)	Shear Force (kips)	Tran. Moment (ft-k)	Long. Moment (ft-k)	Bending Moment (ft-k)	Vert. Moment (ft-k)	Found. Usage %
W 0	OP	-27.66	-16.00	-215.02	31.95	1.38	-5.25	5.43	-1.55	0.00
W 0	OX	-25.50	15.62	-199.19	29.90	-0.46	-4.70	4.73	1.48	0.00
W 0	OXY	-27.02	-8.84	109.58	28.43	0.39	-6.08	6.10	1.60	0.00
W 180	OP	-29.77	8.93	-134.44	30.88	-0.50	-6.78	6.78	-1.52	0.00
W 180	OX	29.77	8.68	113.27	31.00	-0.26	6.89	6.89	1.53	0.00
W 180	OXY	27.25	-8.37	103.59	28.51	0.42	6.35	6.36	-1.62	0.00
W 180	OP	-25.53	-15.43	-202.93	29.83	-0.51	4.93	4.96	-1.50	0.00
W 180	OX	27.59	-15.58	-211.84	31.68	-1.43	5.35	5.54	1.57	0.00
W 45	OP	-29.72	-29.79	-292.82	42.08	3.91	-3.85	5.49	0.00	0.00
W 45	OX	-12.27	-11.57	-42.00	16.86	5.40	-3.33	6.34	2.29	0.00
W 45	OXY	-28.00	-8.84	109.58	29.49	4.30	4.35	6.11	-0.00	0.00
W 45	OP	-11.47	-12.13	-41.08	16.69	3.29	-5.34	6.27	-2.29	0.00
W 45	OX	-13.60	11.76	-51.80	17.98	-5.78	-3.68	6.85	-2.29	0.00
W 45	OXY	-28.00	-8.84	109.58	29.49	-4.25	-3.47	5.49	0.00	0.00
W 45	OXY	-9.82	12.14	-43.46	15.61	-3.22	-4.87	5.83	2.31	0.00
W 45	OX	-29.15	27.39	183.91	40.00	-4.22	-4.78	6.38	0.02	0.00
W 90	OP	-15.97	-27.88	-217.33	32.13	5.26	1.47	5.47	1.56	0.00
W 90	OX	9.17	-29.91	117.63	31.26	6.80	0.27	6.80	-1.52	0.00
W 90	OXY	-8.91	-26.99	109.50	28.43	6.08	-0.42	6.09	-1.61	0.00
W 90	OP	15.76	-25.52	-199.78	30.00	4.70	0.53	4.73	-1.48	0.00
W 90	OX	8.80	30.02	115.64	31.28	-6.89	0.23	6.90	-1.53	0.00
W 90	OXY	-15.50	27.74	-213.51	31.78	-5.36	1.51	5.57	-1.57	0.00
W 90	OXY	15.57	25.51	-195.66	29.89	-4.89	0.58	4.93	1.50	0.00
W 90	OP	-8.47	27.11	-103.52	28.40	-6.30	-0.46	6.32	1.62	0.00
W 0 Ice	OP	-11.66	-8.92	-107.37	14.60	-1.31	0.09	1.32	-0.32	0.00
W 0 Ice	OX	-10.77	8.80	-100.31	13.91	1.02	0.25	1.05	0.30	0.00
W 0 Ice	OXY	-0.56	2.70	-28.93	2.75	1.11	-2.16	2.42	0.33	0.00
W 0 Ice	OP	-2.63	-3.20	-32.50	2.77	-2.25	2.88	2.69	0.31	0.00
W 180 Ice	OP	0.88	-3.21	-37.18	3.33	-1.20	2.52	2.80	0.33	0.00
W 180 Ice	OX	0.84	3.13	-34.95	3.24	1.15	2.44	2.70	-0.35	0.00
W 180 Ice	OXY	-10.73	-9.49	-104.42	13.68	0.97	0.10	0.97	0.32	0.00
W 180 Ice	OP	11.39	-8.38	-102.46	14.14	-1.35	0.05	1.35	0.34	0.00
W 45 Ice	OP	-12.09	-12.11	-124.85	17.12	-0.36	0.38	0.53	0.00	0.00
W 45 Ice	OX	-7.74	2.91	-66.43	8.27	2.09	0.53	2.16	0.47	0.00
W 45 Ice	OXY	-0.95	-0.95	-1.35	1.35	1.81	-1.82	2.87	-0.00	0.00
W 45 Ice	OP	2.92	-7.68	-65.91	8.22	-0.53	-2.07	2.14	-0.47	0.00
W 45 Ice	OX	-8.52	-2.89	-72.41	9.00	-2.29	0.41	2.32	-0.48	0.00
W 45 Ice	OXY	-1.38	11.86	-118.04	16.44	0.19	0.52	0.15	-0.11	0.00
W 45 Ice	OP	3.09	7.77	-61.87	8.36	0.37	-1.89	1.92	0.49	0.00
W 45 Ice	OX	-0.90	0.96	-16.79	1.32	-1.98	-1.95	2.78	0.02	0.00
W 90 Ice	OP	-8.90	-11.61	-107.84	14.63	-0.08	1.34	1.34	0.32	0.00
W 90 Ice	OX	-2.63	3.20	-32.50	2.77	2.25	-2.88	2.69	0.31	0.00
W 90 Ice	OXY	2.69	-0.57	-28.93	2.75	2.16	-1.11	2.43	-0.33	0.00
W 90 Ice	OP	8.81	-10.76	-100.06	13.91	-0.25	-1.00	1.03	-0.30	0.00
W 90 Ice	OX	-3.15	0.92	-26.67	3.31	-2.52	1.30	2.33	0.33	0.00
W 90 Ice	OXY	-8.37	11.43	-103.03	14.16	-0.04	1.37	1.37	-0.34	0.00
W 90 Ice	OP	8.52	10.71	-94.63	13.69	0.01	-0.96	0.96	0.32	0.00
W 90 Ice	OX	3.10	0.81	-34.78	3.21	-2.43	-1.16	2.69	0.35	0.00

Summary of Joint Support Reactions For All Load Cases in Direction of Leg:

Load Case	Support Origin	Joint	Member	Leg Dir.	Perpendicular (kips)	Leg Force (kips)	Residual Shear (kips)	Residual Shear (kips)	Residual Shear (kips)	Residual Shear (kips)	Total Long. Force (kips)	Total Tran. Force (kips)	Total Vert. Force (kips)
W 0	OP	IP	L IP	217.024	12.510	12.545	12.516	0.860	-27.66	-16.00	-215.02		
W 0	OX	LX	L LX	201.090	11.542	11.578	11.468	-1.592	-25.50	15.62	-199.19		
W 0	OXY	LY	L LY	-111.552	19.285	19.338	19.306	1.119	-27.02	-8.84	109.58		
W 180	OP	IP	L IP	-115.408	21.742	21.799	-21.788	-0.701	29.77	8.68	113.27		
W 180	OX	LX	L LX	-105.578	19.931	19.986	-19.956	1.079	27.25	-8.37	103.59		
W 180	OXY	LY	L LY	186.266	11.912	11.919	-11.799	-1.691	25.53	15.43	-195.02		
W 180	OP	IP	L IP	295.550	12.650	12.685	12.668	0.662	27.49	-15.58	-211.84		
W 45	OP	IP	L IP	295.550	12.853	12.916	9.094	9.173	-29.72	-29.79	-292.82		
W 45	OX	LX	L LX	41.840	17.250	17.254	9.315	14.524	-12.27	-11.57	-42.00		
W 45	OXY	LY	L LY	-189.972	20.971	20.974	-20.914	-2.075	-28.00	-8.84	109.58		
W 45	OP	IP	L IP	40.927	17.074	17.078	14.365	9.236	-11.47	-12.13	-41.08		
W 45	OX	LX	L LX	51.670	18.342	18.346	9.955	-15.410	-13.60	11.76	-51.80		
W 45	OXY	LY	L LY	281.266	12.765	12.768	-12.765	0.634	-28.00	-8.84	109.58		
W 45	OP	IP	L IP	43.409	15.756	15.758	12.882	-9.077	-9.82	12.14	-43.46		
W 45	OX	LX	L LX	-186.971	21.596	21.703	16.201	-14.441	-29.15	27.39	183.91		
W 90	OP	IP	L IP	219.330	12.558	12.593	0.661	12.575	-15.97	-27.88	-217.33		
W 90	OX	LX	L LX	-119.768	21.824	21.841	-21.824	-21.873	8.80	30.02	115.64		
W 90	OXY	LY	L LY	-111.475	19.265	19.318	1.201	19.281	-8.91	-26.99	109.50		
W 90	OP	IP	L IP	201.693	11.543	11.579	-1.694	11.455	15.76	-25.52	-199.78		
W 90	OX	LX	L LX	117.794	21.826	21.883	-0.651	-21.873	8.80	30.02	115.64		
W 90	OXY	LY	L LY	215.484	12.680	12.714	0.460	-12.705	-15.50	27.74	-213.51		
W 90	OP	IP	L IP	197.574	11.826	11.864	-1.795	-11.728	15.57	25.51	-195.66		
W 90	OX	LX	L LX	-105.506	19.795	19.850	1.180	-19.815	-8.47	27.11	103.52		
W 0 Ice	OP	IP	L IP	108.280	4.206	4.222	3.997	1.361	-11.56	-8.92	-107.37		
W 0 Ice	OX	LX	L LX	101.190	4.077	4.095	3.708	-1.736	-10.77	8.80	-100.31		
W 0 Ice	OXY	LY	L LY	28.937	2.674	2.677	2.595	-0.659	-0.56	2.70	-28.93		
W 180 Ice	OP	IP	L IP	37.163	3.542	3.547	-3.497	0.595	0.88	-3.21	-37.18		
W 180 Ice	OX	LX	L LX	34.937	3.365	3.370	-3.302	-0.670	0.84	3.13	-34.95		
W 180 Ice	OXY	LY	L LY	95.406	4.443	4.463	-4.069	-1.832	10.73	8.49	104.52		
W 45 Ice	OP	IP	L IP	103.344	3.313	3.313	-3.170	1.166	11.39	-8.38	-102.46		
W 45 Ice	OX	LX	L LX	125.927	4.658	4.681	3.298	3.323	-12.09	-12.11	-124.85		
W 45 Ice	OXY	LY	L LY	106.847	3.532	3.533	3.059	1.768	-7.74	2.91	-66.43		
W 45 Ice	OP	IP	L IP	117.742	2.522	2.524	-2.524	-2.178	-0.95	-0.95	-11.93		
W 45 Ice	OX	LX	L LX	66.330	3.492	3.493	1.720	3.041	2.92	-7.68	-65.91		
W 45 Ice	OXY	LY	L LY	72.856	4.070	4.071	3.420	-2.208	-8.52	-2.89	-72.41		
W 45 Ice	OP	IP	L IP	119.089	4.665	4.688	3.065	-3.547	-11.38	11.86	-118.04		
W 45 Ice	OX	LX	L LX	62.330	3.632	3.635	3.265	-3.408	-0.99	7.77	-61.87		
W 45 Ice	OXY	LY	L LY	16.578	2.978	2.992	2.085	-2.147	-0.90	0.96	-16.79		
W 90 Ice	OP	IP	L IP	108.744	4.204	4.221	1.302	4.015	-8.90	-11.61	-107.84		
W 90 Ice	OX	LX	L LX	32.251	3.208	3.215	0.337	3.197	-2.61	-0.92	-32.29		
W 90 Ice	OXY	LY	L LY	28.938	2.682	2.685	-0.657	2.603	2.69	-0.57	-28.93		
W 90 Ice	OP	IP	L IP	100.937	4.093	4.111	-1.767	3.713	8.81	-10.76	-100.06		
W 90 Ice	OX	LX	L LX	103.913	3.543	3.549	0.598	-3.498	-3.18	0.92	-36.67		
W 90 Ice	OXY	LY	L LY	103.913	4.300	4.316	1.114	-4.170	-8.37	11.43	-103.03		
W 90 Ice	OP	IP	L IP	95.512	4.436	4.455	-1.859	-4.049	8.52	10.71	-94.63		
W 90 Ice	OX	LX	L LX	34.772	3.322	3.327	-0.651	-3.263	3.10	0.81	-34.78		

Overturning Moment Summary For All Load Cases:

Load Case	Transverse Moment (ft-k)	Longitudinal Moment (ft-k)	Torsional Moment (ft-k)	Resultant Moment (ft-k)	Transverse Force (kips)	Longitudinal Force (kips)	Vertical Force (kips)
W 0	223.612	-13247.348	87.868	13249.235	0.294	109.744	189.999
W 180	148.262	12942.276	-85.246	12943.155	-0.149	-110.136	-189.999
W 45	9914.577	-9952.513	-9.855	14048.180	81.334	81.462	189.999
W 45	-9425.357	9771.250	133.248	13576.255	-80.552	80.579	189.999
W 90	13367.587	195.649	-101.23	13369.017	105.305	0.007	189.999
W							

Member	Length	Area	Weight	Modulus	Stress	Strain	Capacity	Factor
125.0-137.5	137.500	125.000	16	24	22.13	23.89	287.67	1.2240
112.5-125.0	125.000	112.500	16	24	25.65	27.42	331.68	1.2450
100.0-112.5	112.500	100.000	16	24	25.65	27.42	331.68	1.2450
75.0-100.0	100.000	75.000	16	24	27.42	30.94	729.39	1.2770
50.0-75.0	75.000	50.000	16	24	30.94	34.46	817.42	1.2930
25.0-50.0	50.000	25.000	16	24	34.46	37.98	905.45	1.3350
0.000-25.00	25.000	0.000	28	56	37.98	41.50	993.48	1.2150

Printed capacities do not include the strength factor entered for each load case.
The Group Summary reports on the member and load case that resulted in maximum usage which may not necessarily be the same as that which produces maximum force.

Group Summary (Compression Portion):

Group Label	Group Desc.	Type	Angle Size	Steel Strength (ksi)	Max Usage %	Max Use Control	Comp. In Member	Comp. Force (kips)	Comp. Control Case	L/r (kips)	Comp. Connect. Shear Capacity (kips)	Comp. Connect. Bearing Capacity (kips)	RLX	RIY	RIZ	L/r	KL/r	Length (ft)	Curve No.	No. Of Bolts Comp.
Leg S1	L 8" x 8" x 1.125"	SAE	8X8X1.13	33.0	63.30	Comp	63.30	1 LP -257.468	W 45	406.720	0.000	0.000	0.333	0.333	0.333	64.41	64.41	25.124	1	0
Leg S2	L 8" x 8" x 1"	SAE	8X8X1	33.0	60.88	Comp	60.88	1 2P -222.017	W 45	364.663	0.000	0.000	0.333	0.333	0.333	64.41	64.41	25.124	1	0
Leg S3	L 8" x 8" x 0.875"	SAE	8X8X0.88	33.0	57.09	Comp	57.09	1 3P -184.084	W 45	322.451	0.000	0.000	0.333	0.333	0.333	64.00	64.00	25.124	1	0
Leg S4	L 8" x 8" x 0.75"	SAE	8X8X0.75	33.0	51.67	Comp	51.67	1 4P -144.439	W 45	279.520	0.000	0.000	0.333	0.333	0.333	63.60	63.60	25.124	1	0
Leg S5	L 6" x 6" x 0.875"	SAE	6X6X0.88	33.0	52.67	Comp	52.67	1 5P -124.573	W 45	236.535	0.000	0.000	0.500	0.500	0.500	64.42	64.42	12.562	1	0
Leg S6	L 6" x 6" x 0.75"	SAE	6X6X0.75	33.0	43.64	Comp	43.64	1 6P -103.217	W 45	236.535	0.000	0.000	0.500	0.500	0.500	64.42	64.42	12.562	1	0
Leg S7	L 6" x 6" x 0.75"	SAE	6X6X0.75	33.0	41.41	Comp	41.41	1 7P -84.962	W 45	205.175	0.000	0.000	0.500	0.500	0.500	64.42	64.42	12.562	1	0
Leg S8	L 6" x 6" x 0.75"	SAE	6X6X0.75	33.0	32.17	Comp	32.17	1 8P -66.001	W 45	205.175	0.000	0.000	0.500	0.500	0.500	64.42	64.42	12.562	1	0
Leg S9	L 6" x 6" x 0.75"	SAE	6X6X0.75	33.0	31.03	Comp	31.03	1 9P -63.664	W 45	205.175	0.000	0.000	0.500	0.500	0.500	64.42	64.42	12.562	1	0
Leg S10	L 6" x 6" x 0.75"	SAE	6X6X0.75	33.0	21.72	Comp	21.72	1 10P -44.557	W 45	205.175	0.000	0.000	0.500	0.500	0.500	64.42	64.42	12.562	1	0
Leg S11	L 6" x 6" x 0.5"	SAE	6X6X0.5	33.0	18.76	Comp	18.76	1 11P -26.312	W 45	140.255	0.000	0.000	0.500	0.500	0.500	63.87	63.87	12.562	1	0
Leg S12	L 6" x 6" x 0.5"	SAE	6X6X0.5	33.0	8.10	Comp	8.10	1 12P -11.367	W 45	140.255	0.000	0.000	0.500	0.500	0.500	63.87	63.87	12.562	1	0
Diag S1	B/B L2.5"x3"x0.25"	DAS	3X2.5X0.25	33.0	87.13	Comp	87.13	1 D 7X -28.743	W 90	32.989	0.000	0.000	0.310	0.620	0.310	151.11	139.14	29.451	6	0
Diag S2	B/B L2.5"x3"x0.25"	DAS	3X2.5X0.25	33.0	85.88	Comp	85.88	1 D 3X -30.004	W 90	34.937	0.000	0.000	0.310	0.620	0.310	160.23	144.74	31.444	6	0
Diag S3	B/B L2.5"x2.5"x0.25"	DAS	3X2.5X0.25	33.0	94.35	Comp	94.35	1 D 5X -29.942	W 90	31.734	0.000	0.000	0.310	0.620	0.310	156.05	142.17	30.413	6	0
Diag S4	B/B L2.5"x2.5"x0.25"	DAS	3X2.5X0.25	33.0	87.13	Comp	87.13	1 D 7X -28.743	W 90	32.989	0.000	0.000	0.310	0.620	0.310	151.11	139.14	29.451	6	0
Diag S5	B/B L2.5"x2.5"x0.25"	DAS	3X2.5X0.25	33.0	89.39	Comp	89.39	1 D 9X -18.456	W 90	20.646	0.000	0.000	0.500	1.000	0.500	187.28	161.38	18.572	6	0
Diag S6	B/B L2.5"x2.5"x0.25"	DAS	3X2.5X0.25	33.0	78.99	Comp	78.99	1 D 11X -17.141	W 90	21.700	0.000	0.000	0.500	1.000	0.500	180.83	157.41	17.932	6	0
Diag S7	B/B L2.5"x2.5"x0.25"	DAS	3X2.5X0.25	33.0	73.46	Comp	73.46	1 D 13X -16.747	W 90	22.798	0.000	0.000	0.500	1.000	0.500	174.59	153.57	17.313	6	0
Diag S8	B/B L2.5"x2.5"x0.25"	DAS	3X2.5X0.25	33.0	71.29	Comp	71.29	1 D 15X -16.064	W 90	23.935	0.000	0.000	0.500	1.000	0.500	168.59	149.88	16.718	6	0
Diag S9	L 3" x 4" x 0.25"	SAU	4X3X0.25	33.0	41.94	Tens	0.00	1 D 18Y 0.000	0.000	0.000	0.000	0.000	100.000	100.000	100.000	42714.51	32577.05	23.173	5	0
Diag S10	L 3" x 4" x 0.25"	SAU	4X3X0.25	33.0	34.41	Tens	0.00	1 D 20Y 0.000	0.000	0.000	0.000	0.000	100.000	100.000	100.000	40023.07	30526.18	21.713	5	0
Diag S11	L 3.5" x 3.5" x 0.25"	SAB	3.5X3.5X0.25	33.0	25.74	Tens	0.00	1 D 22Y 0.000	0.000	0.000	0.000	0.000	100.000	100.000	100.000	35101.11	26775.65	20.300	5	0
Diag S12	L 3.5" x 3.5" x 0.25"	SAB	3.5X3.5X0.25	33.0	25.25	Tens	0.00	1 D 24Y 0.000	0.000	0.000	0.000	0.000	100.000	100.000	100.000	32759.97	24991.70	18.946	5	0
Horiz 1	B/B L3"x2.5"x0.25"	DAL	3X2.5X0.25	33.0	88.12	Comp	88.12	1 H 1P -37.975	W 90	43.092	0.000	0.000	0.950	0.950	0.950	156.53	142.47	12.660	6	0
Horiz 2	B/B L3"x2.5"x0.25"	DAL	3X2.5X0.25	33.0	52.46	Comp	52.46	1 H 3P -16.072	W 90	30.639	0.000	0.000	1.000	1.000	1.000	187.95	161.79	17.229	6	0
Horiz 3	B/B L3"x2.5"x0.25"	DAL	3X2.5X0.25	33.0	70.41	Comp	70.41	1 H 5P -15.001	W 90	21.304	0.000	0.000	1.000	1.000	1.000	196.42	167.00	15.768	6	0
Horiz 4	B/B L3"x2.5"x0.25"	DAL	3X2.5X0.25	33.0	54.07	Comp	54.07	1 H 7P -13.680	W 90	25.299	0.000	0.000	1.000	1.000	1.000	174.06	153.25	13.708	6	0
Horiz 5	B/B L3"x2.5"x0.25"	DAL	3X2.5X0.25	33.0	66.49	Comp	66.49	1 H 9P -12.473	W 90	18.758	0.000	0.000	1.000	1.000	1.000	200.16	169.30	12.827	6	0
Horiz 6	B/B L3"x2.5"x0.25"	DAL	3X2.5X0.25	33.0	53.76	Comp	53.76	1 H 11P -11.711	W 90	20.781	0.000	0.000	1.000	1.000	1.000	186.43	160.85	11.947	6	0
Horiz 7	B/B L3"x2.5"x0.25"	DAL	3X2.5X0.25	33.0	31.07	Comp	31.07	1 H 13P -10.384	W 90	33.425	0.000	0.000	1.000	1.000	1.000	140.53	132.62	11.067	6	0
Horiz 8	B/B L3"x2.5"x0.25"	DAL	3X2.5X0.25	33.0	52.61	Comp	52.61	1 H 15P -19.160	W 90	36.417	0.000	0.000	1.000	1.000	1.000	129.35	125.75	10.186	6	0
Horiz 9	B/B L3"x2.5"x0.25"	DAL	3X2.5X0.25	33.0	27.98	Comp	27.98	1 H 17P -16.519	W 90	21.713	0.000	0.000	1.000	1.000	1.000	167.59	150.89	11.465	6	0
Horiz 10	B/B L3"x2.5"x0.25"	DAL	3X2.5X0.25	33.0	27.98	Comp	27.98	1 H 19P -12.581	W 90	44.957	0.000	0.000	0.500	0.500	0.500	106.99	106.99	16.811	1	0
Horiz 11	L 4" x 3" x 0.3125"	SAU	4X3X0.31	33.0	34.89	Tens	0.00	1 H 21P -8.961	W 90	25.680	0.000	0.000	0.500	0.500	0.500	139.94	135.24	15.091	5	0
Horiz 12	L 4" x 3" x 0.3125"	SAU	4X3X0.31	33.0	45.86	Comp	45.86	1 H 23P -4.958	W 90	10.028	0.000	0.000	0.500	0.500	0.500	247.23	216.99	13.330	5	0
LD 1	B/B L2.5"x2.5"x0.25"	DAS	3X2.5X0.25	33.0	94.35	Comp	94.35	1 LD 1P -27.524	W 90	21.135	0.000	0.000	0.970	0.970	0.970	170.22	150.89	11.465	6	0
LD 2	B/B L2.5"x2.5"x0.25"	DAS	3X2.5X0.25	33.0	94.96	Comp	94.96	1 LD 3P -27.524	W 90	28.984	0.000	0.000	0.970	0.970	0.970	145.88	135.92	9.638	6	0
LD 3	B/B L3"x3"x0.25"	DAS	3X3X0.25	33.0	67.69	Comp	67.69	1 LD 5P -26.626	W 90	39.335	0.000	0.000	0.970	0.970	0.970	131.18	126.88	10.481	6	0
LH 1	B/B L2.5"x2.5"x0.25"	DAS	3X2.5X0.25	33.0	47.01	Tens	0.00	1 LH 1P -32.229	W 90	70.686	0.000	0.000	1.000	1.000	1.000	17377.90	13270.56	11.136	5	0
DUM 1	Dummy Bracing Member	DUM	0.1X0.1X1	36.0	0.00	0.00	0.00	BR 5X -1.096	W 45	0.324	0.000	0.000	1.000	1.000	1.000	2.63	2.63	21.875	1	0

Group Summary (Tension Portion):

Group Label	Group Desc.	Type	Angle Size	Steel Strength (ksi)	Max Usage %	Max Use Control	Tension Member	Tension Force (kips)	Tension Control Case	Net Section Capacity (kips)	Tension Connect. Shear Capacity (kips)	Tension Connect. Bearing Capacity (kips)	Tension Length (ft)	No. Of Bolts	Hole Diameter (in)
Leg S1	L 8" x 8" x 1.125"	SAE	8X8X1.13	33.0	63.30	Comp	26.54	1 LX1 131.877	W 45	496.880	0.000	0.000	0.000	25.124	0.000
Leg S2	L 8" x 8" x 1"	SAE	8X8X1	33.0	60.88	Comp	30.62	1 LX2 136.403	W 45	445.499	0.000	0.000	0.000	25.124	0.000
Leg S3	L 8" x 8" x 0.875"	SAE	8X8X0.88	33.0	57.09	Comp	27.77	1 LX3 109.101	W 45	392.930	0.000	0.000	0.000	25.124	0.000
Leg S4	L 8" x 8" x 0.75"	SAE	8X8X0.75	33.0	51.67	Comp	23.78	1 LX4 80.794	W 45	339.767	0.000	0.000	0.000	25.124	0.000
Leg S5	L 6" x 6" x 0.875"	SAE	6X6X0.88	33.0	52.67	Comp	23.29	1 LX5 67.292	W 45	288.981	0.000	0.000			

Site #: 88017
 Name: Shelton/Trumbull, CT

Engineer: CDW
 Date: 03/21/18

Windspeed: No Ice: 97 mph Ice: 50 mph
 Carrier: Sprint Nextel

Taper: -0.14085
 FW @ Base: 41.50 ft

Taper Change: 200 ft
 FW @ Top: 13.33 ft

Joint Label	Symmetry Code	X Coord. (ft)	Y Coord. (ft)	Z Coord. (ft)	X Disp. Rest.	Y Disp. Rest.	Z Disp. Rest.	X Rot. Rest.	Y Rot. Rest.	Z Rot. Rest.	Drop		Spreadsheet Version Last Updated: 11/12/2014					
											Sub-Brace (Y or Blank)	# Vert	Drop (ft)	Height (ft)	Type	Count	Z-Elev. (ft)	FW (ft)
0	XY-Symmetry	20.75	20.75	0	Fixed	Fixed	Fixed	Fixed	Fixed	Fixed		8.333	25	2	1	0	41.5	3
1	XY-Symmetry	18.989375	18.989375	25	Free	Free	Free	Free	Free	Free			25	A	2	25	37.97875	2
2	XY-Symmetry	17.22875	17.22875	50	Free	Free	Free	Free	Free	Free			25	A	3	50	34.4575	2
3	XY-Symmetry	15.468125	15.468125	75	Free	Free	Free	Free	Free	Free			25	A	4	75	30.93625	2
4	XY-Symmetry	13.7075	13.7075	100	Free	Free	Free	Free	Free	Free			12.5	A	5	100	27.415	1
5	XY-Symmetry	12.8271875	12.8271875	112.5	Free	Free	Free	Free	Free	Free			12.5	A	6	112.5	25.654375	1
6	XY-Symmetry	11.946875	11.946875	125	Free	Free	Free	Free	Free	Free			12.5	A	7	125	23.89375	1
7	XY-Symmetry	11.0665625	11.0665625	137.5	Free	Free	Free	Free	Free	Free			12.5	A	8	137.5	22.133125	1
8	XY-Symmetry	10.18625	10.18625	150	Free	Free	Free	Free	Free	Free	1		12.5	X	9	150	20.3725	1
9	XY-Symmetry	9.3059375	9.3059375	162.5	Free	Free	Free	Free	Free	Free	1		12.5	X	10	162.5	18.611875	1
10	XY-Symmetry	8.425625	8.425625	175	Free	Free	Free	Free	Free	Free	1		12.5	X	11	175	16.85125	1
11	XY-Symmetry	7.5453125	7.5453125	187.5	Free	Free	Free	Free	Free	Free			12.5	X	12	187.5	15.090625	1
12	XY-Symmetry	6.665	6.665	200	Free	Free	Free	Free	Free	Free					13	200	13.33	
A1	XY-Symmetry	18.989375	6.329791667	25	Free	Free	Free	Free	Free	Free								
A2	XY-Symmetry	6.329791667	18.989375	25	Free	Free	Free	Free	Free	Free								
A3	Y-Symmetry	17.22875	0	50	Free	Free	Free	Free	Free	Free								
A4	X-Symmetry	0	17.22875	50	Free	Free	Free	Free	Free	Free								
A5	Y-Symmetry	15.468125	0	75	Free	Free	Free	Free	Free	Free								
A6	X-Symmetry	0	15.468125	75	Free	Free	Free	Free	Free	Free								
A7	Y-Symmetry	13.7075	0	100	Free	Free	Free	Free	Free	Free								
A8	X-Symmetry	0	13.7075	100	Free	Free	Free	Free	Free	Free								
A9	Y-Symmetry	12.8271875	0	112.5	Free	Free	Free	Free	Free	Free								
A10	X-Symmetry	0	12.8271875	112.5	Free	Free	Free	Free	Free	Free								
A11	Y-Symmetry	11.946875	0	125	Free	Free	Free	Free	Free	Free								
A12	X-Symmetry	0	11.946875	125	Free	Free	Free	Free	Free	Free								
A13	Y-Symmetry	11.0665625	0	137.5	Free	Free	Free	Free	Free	Free								
A14	X-Symmetry	0	11.0665625	137.5	Free	Free	Free	Free	Free	Free								
A15	Y-Symmetry	10.18625	0	150	Free	Free	Free	Free	Free	Free								
A16	X-Symmetry	0	10.18625	150	Free	Free	Free	Free	Free	Free								
H1	XY-Symmetry	19.57622653	11.13633551	16.667	Free	Free	Free	Free	Free	Free								
H2	XY-Symmetry	11.13633551	19.57622653	16.667	Free	Free	Free	Free	Free	Free								
H3	Y-Symmetry	19.57622653	0	16.667	Free	Free	Free	Free	Free	Free								
H4	X-Symmetry	0	19.57622653	16.667	Free	Free	Free	Free	Free	Free								

NOTES
 Types:
 1: Built up Horiz. w/ A
 2: Built up Horiz. w/ M
 A: Typical A brace
 X: Typical X brace
 Drop: Use only for types 1 & 2
 # Sections: 12

Legs

Site No.:	88017
Engineer:	CDW
Date:	03/21/2018
Carrier:	Sprint Nextel

When inputting thickness values, include all decimal places.

Tower Section #	Section Elevations (ft)	Type of Shape ^[1]	Diameter or Length (in)	Thickness ^[2] (in)	F _y (ksi)
1	0.000-25.00	L	8	1.125	33
2	25.00-50.00	L	8	1	33
3	50.00-75.00	L	8	0.875	33
4	75.00-100.0	L	8	0.75	33
5	100.0-112.5	L	6	0.875	33
6	112.5-125.0	L	6	0.875	33
7	125.0-137.5	L	6	0.75	33
8	137.5-150.0	L	6	0.75	33
9	150.0-162.5	L	6	0.75	33
10	162.5-175.0	L	6	0.75	33
11	175.0-187.5	L	6	0.5	33
12	187.5-200.0	L	6	0.5	33

Notes:

^[1] Type of Leg Shape: **R** = Round or **P** = Bent Plate or **S** = Schifflerized Angle. **L** = Even Leg

^[2] For Solid Round Leg Shapes Thickness Equals Zero.

^[3] Adjust for Bent Plate Leg Shapes.

Diagonals

Site No.:	88017
Engineer:	CDW
Date:	03/21/2018
Carrier:	Sprint Nextel

When inputting thickness values, include all decimal places.

Tower Section #	Section Elevations (ft)	Type of Shape ^[1]	Diameter ^[2] (in)	Web Length ^[3] (in)	Flange Length ^[3] (in)	Thickness (in)	F _y (ksi)	Is Diag. Tension Only? (Y/N)
1	0.000-25.00	2L		3	3	0.25	33	
2	25.00-50.00	2L		2.5	3	0.3125	33	
3	50.00-75.00	2L		2.5	3	0.25	33	
4	75.00-100.0	2L		2.5	3	0.25	33	
5	100.0-112.5	2L		2.5	2.5	0.25	33	
6	112.5-125.0	2L		2.5	2.5	0.25	33	
7	125.0-137.5	2L		2.5	2.5	0.25	33	
8	137.5-150.0	2L		2.5	2.5	0.25	33	
9	150.0-162.5	L		3	4	0.25	33	Y
10	162.5-175.0	L		3	4	0.25	33	Y
11	175.0-187.5	L		3.5	3.5	0.25	33	Y
12	187.5-200.0	L		3.5	3.5	0.25	33	Y

Notes:

^[1] Type of Diagonal Shape: R = Round, L = Single-Angle or 2L = Double-Angle.

^[2] Applies to Pipes and Solid Round Shapes only. For Solid Round Shapes Thickness Equals Zero.

^[3] Applies to Single-Angle and Double-Angle Shapes only.

^[4] Applies to Double-Angle Shapes only.

^[5] Applies to Single-Angle Shapes only.

Horizontals

Site No.:	88017
Engineer:	CDW
Date:	03/21/2018
Carrier:	Sprint Nextel

When inputting thickness values, include all decimal places.

Tower Section #	Section Elevations (ft)	Type of Shape ^[1]	Diameter ^[2] (in)	Web Length ^[3] (in)	Flange Length ^[3] (in)	Thickness (in)	F _y (ksi)	
1	0.000-25.00	2L		3	3	0.3125	33	
2	25.00-50.00	2L		3.5	2.5	0.3125	33	
3	50.00-75.00	2L		3	2.5	0.25	33	
4	75.00-100.0	2L		3	2.5	0.25	33	
5	100.0-112.5	2L		2.5	2.5	0.25	33	
6	112.5-125.0	2L		2.5	2.5	0.25	33	
7	125.0-137.5	2L		3	2.5	0.25	33	
8	137.5-150.0	2L		3	2.5	0.25	33	
9	150.0-162.5	2L		3	2.5	0.25	33	
10	162.5-175.0	2L		3	2.5	0.25	33	
11	175.0-187.5	L		4	3	0.3125	33	
12	187.5-200.0	L		4	3	0.3125	33	

Notes:

^[1] Type of Horizontal Shape: **R** = Round, **L** = Single-Angle, **2L** = Double-Angle, **C** = Channel, **W** = W Shape

^[2] Applies to Pipes and Solid Round Shapes only. For Solid Round Shapes Thickness Equals Zero.

^[3] Applies to Single-Angle and Double-Angle Shapes only.

^[4] Applies to Double-Angle Shapes only.

^[5] Applies to Single-Angle Shapes only.

Built-up Diagonals

Site No.:	88017
Engineer:	CDW
Date:	03/21/2018
Carrier:	Sprint Nextel

When inputting thickness values, include all decimal places.
Input diags. from left to center & from base section upward.

Tower Built-up Diag. #	Section Elevations (ft)	Type of Shape ^[1]	Diameter ^[2] (in)	Web Length ^[3] (in)	Flange Length ^[3] (in)	Thickness (in)	F _y (ksi)
1	0.000-25.00	2L		2.5	2	0.25	33
2	0.000-25.00	2L		2.5	2.5	0.25	33
3	0.000-25.00	2L		3	3	0.25	33

Notes:

^[1] Type of Diagonal Shape: **R** = Round, **L** = Single-Angle or **2L** = Double-Angle.

^[2] Applies to Pipes and Solid Round Shapes only. For Solid Round Shapes Thickness Equals Zero.

^[3] Applies to Single-Angle and Double-Angle Shapes only.

^[4] Applies to Double-Angle Shapes only.

^[5] Applies to Single-Angle Shapes only.

Built-up Horizontals

Site No.:	88017
Engineer:	CDW
Date:	03/21/2018
Carrier:	Sprint Nextel

When inputting thickness values, include all decimal places.

Tower Section #	Section Elevations (ft)	Type of Shape ^[1]	Diameter ^[2] (in)	Web Length ^[3] (in)	Flange Length ^[3] (in)	Thickness (in)	F _y (ksi)	Is Horiz. Tension Only? (Y/N)
1	0.000-25.00	2L		2.5	2.5	0.25	33	Y

Notes:

^[1] Type of Horizontal Shape: R = Round, L = Single-Angle or 2L = Double-Angle.

^[2] Applies to Pipes and Solid Round Shapes only. For Solid Round Shapes Thickness Equals Zero.

^[3] Applies to Single-Angle and Double-Angle Shapes only.

^[4] Applies to Double-Angle Shapes only.

^[5] Applies to Single-Angle Shapes only.

Site No.:	88017
Engineer:	CDW
Date:	03/21/18
Carrier:	Sprint Nextel

Description	From (ft)	To (ft)	Quantity	Shape	Width or Diameter (in)	Perimeter (in)	Unit Weight (lb/ft)	Part of Face Solidity Ratio (Yes/No)	Include in Wind Load (Yes/No)
1 Ladder	0	200	1	Flat	2	8.0	6	Yes	Yes
2 OTHER	10	200	1	Round	0.63	2.0	0.15	Yes	Yes
3 STATE OF CT	10	200	1	Round	1.98	6.2	0.82	Yes	Yes
4 STATE OF CT	10	200	1	Round	1.98	6.2	0.82	Yes	Yes
5 STATE OF CT	10	200	2	Round	2.01	6.3	0.57	Yes	Yes
6 STATE OF CT	10	182	1	Flat	4.8375	25.8	4.1	Yes	Yes
7 STATE OF CT	10	182	1	Flat	2.30625	12.3	0.75	Yes	Yes
8 STATE OF CT	10	182	1	Flat	3.72	19.8	3.28	Yes	Yes
9 SPRINT NEXTEL	10	169	1	Flat	12.66	43.7	9.84	Yes	Yes
10 CLEARWIRE	10	158	1	Round	2.52	5.8	0.6	No	No
11 CLEARWIRE	10	158	1	Round	1.86	4.1	0.3	No	No
12 SPRINT NEXTEL	10	155	3	Round	1.54	4.8	1	Yes	Yes
13 SPRINT NEXTEL	10	155	1	Round	1.54	4.8	1	No	No
14 CLEARWIRE	10	150	1	Round	2.38	14.3	7.3	Yes	Yes
15 AT&T MOBILITY	10	145	6	Round	1.98	6.2	0.82	Yes	Yes
16 AT&T MOBILITY	10	145	2	Round	0.78	2.5	0.59	Yes	Yes
17 AT&T MOBILITY	10	145	1	Round	1.11	3.8	0.98	No	No
18 AT&T MOBILITY	10	145	2	Round	3.5	11.0	7.58	Yes	Yes
19 AT&T MOBILITY	10	145	1	Round	0.28	0.9	0.03	No	No
20 AT&T MOBILITY	10	145	1	Round	0.39	1.2	0.17	Yes	Yes
21 STATE OF CT	10	127	2	Round	2.01	6.3	0.57	Yes	Yes
22 US DEPT OF HS	10	101	1	Round	1.09	4.4	0.33	Yes	Yes
23 LIGADO	10	82	1	Round	1.98	7.9	0.82	Yes	Yes
24 SPRINT NEXTEL	10	56	1	Round	0.63	2.0	0.15	Yes	Yes
35 Waveguide	10	176	1	Flat	2	8.0	6	Yes	Yes
36 Waveguide	10	165	1	Flat	2	8.0	6	Yes	Yes
37 Waveguide	10	155	1	Flat	2	8.0	6	Yes	Yes
38 Waveguide	10	143	1	Flat	2	8.0	6	Yes	Yes


Dishes

Dish Types	
S	Standard
R	Standard w/ Radome
H	High Performance
G	Grid

Site No.:	88017
Engineer:	CDW
Date:	03/21/18
Carrier:	Sprint Nextel

Dish Number	Dish Elevation (ft)	Dish Dia. (ft)	Dish Angle (deg)	Dish Type	Joint Orientation	Equipment Status
1	200	8	68	R	XY	
2	200	8	240	R	P	
3	158	2	343.6664	H	XY	
4	158	2	126.6024	S	XY	
5	158	3	212.6351	H	P	
6	158	3	212.6351	H	X	
7	127	6	182	R	P	
8						
9						
10						
11						
12						
13						
14						
15						
16						
17						
18						
19						
20						
21						
22						
23						
24						
25						
26						
27						
28						
29						
30						
31						
32						
33						
34						
35						
36						
37						
38						
39						
40						
41						
42						
43						
44						
45						
46						
47						
48						
49						
50						

Equipment Label	Attach Label	Equipment Property Set	EIA Antenna Orientation Angle (deg)
8' RAD 1 @ 200'	12XY	8 ft RAD Dish	68
8' RAD 2 @ 200'	12P	8 ft RAD Dish	240
2' HP 3 @ 158'	9XY	2 ft HP Dish	343.6664
2' STD 4 @ 158'	9XY	2 ft STD Dish	126.6024
3' HP 5 @ 158'	9P	3 ft HP Dish	212.6351
3' HP 6 @ 158'	9X	3 ft HP Dish	212.6351
6' RAD 7 @ 127'	6P	6 ft RAD Dish	182



Foundation


Design Loads (Factored)

Compression/Leg:	292.82	k
Uplift/Leg:	185.90	k
Shear/Leg:	42.08	k

Face Width @ Top of Pier (d_1):	3.50	ft
Face Width @ Bottom of Pier (d_2):	7.00	ft
Total Length of Pier (l):	7.00	ft
Height of Pedestal Above Ground (h):	0.50	ft
Width of Pad (W):	16.00	ft
Length of Pad (L):	16.00	ft
Thickness of Pad (t):	2.50	ft
Water Table Depth (w):	99.00	ft
Unit Weight of Concrete:	150.0	pcf
Unit Weight of Soil (Above Water Table):	120.0	pcf
Unit Weight of Soil (Below Water Table):	57.6	pcf
Friction Angle of Uplift (A):	30	°
Ultimate Compressive Bearing Pressure:	16000	psf
Ultimate Skin Friction:	500	psf

Volume Pier (Total):	200.08	ft ³
Volume Pad (Total):	640.00	ft ³
Volume Soil (Total):	2346.93	ft ³
Volume Pier (Buoyant):	0.00	ft ³
Volume Pad (Buoyant):	0.00	ft ³
Volume Soil (Buoyant):	0.00	ft ³
Weight Pier:	30.01	k
Weight Pad:	96.00	k
Weight Soil:	281.63	k
Uplift Skin Friction:	60.00	k

Site No.:	88017
Engineer:	CDW
Date:	03/21/18
Carrier:	Sprint Nextel



Uplift Check

ϕ s Uplift Resistance (k)	Ratio	Result
350.73	0.53	OK

Axial Check

ϕ s Axial Resistance (k)	Ratio	Result
3072.00	0.10	OK

Anchor Bolt Check

Bolt Diameter (in)	2.25
# of Bolts	4
Steel Grade	A36
Steel Fy	36
Steel Fu	58
Detail Type	C

Usage Ratio	Result
0.44	OK

Sprint



PROJECT: DO MACRO UPGRADE
 SITE NAME: BOOTH HILL
 SITE CASCADE: CT03XC366
 SITE ADDRESS: 14 OXFORD DRIVE
 SHELTON, CT 06484
 SITE TYPE: SELF SUPPORT TOWER
 MARKET: NORTHERN CONNECTICUT

PLANS PREPARED FOR:


PLANS PREPARED BY:
INFINIGY
 FROM ZERO TO INFINIGY
 the solutions are endless
 1033 Watervliet Shaker Rd | Albany, NY 12205
 Phone: 518-690-0790 | Fax: 518-690-0793
 www.infinigy.com
 JOB NUMBER 526-104

PROJECT MANAGER:

 32 CLINTON ST.
 SARATOGA SPRINGS, NY 12866
 OFFICE: (518) 308-3740

ENGINEERING LICENSE:


DRAWING NOTICE:
 THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:	DESCRIPTION	DATE	BY	REV
ISSUED FOR PERMIT		07/18/18	ETC	0

SITE NAME:
BOOTH HILL

SITE NUMBER:
CT03XC366

SITE ADDRESS:
**14 OXFORD DRIVE
 SHELTON, CT 06484**

SHEET DESCRIPTION:
**TITLE SHEET
 & PROJECT DATA**

SHEET NUMBER:
T-1

SITE INFORMATION

TOWER OWNER:
 AMERICAN TOWER CORPORATION
 10 PRESIDENTIAL WAY
 WOBURN, MA 01801

LATITUDE (NAD83):
 41° 16' 48.741" N
 41.28020583

LONGITUDE (NAD83):
 73° 11' 07.441" W
 -73.18540027

COUNTY:
 FAIRFIELD

ZONING JURISDICTION:
 CONNECTICUT SITING COUNCIL


ZONING DISTRICT:
 R-1 RESIDENTIAL

POWER COMPANY:
 CL&P
 PHONE: (800) 286-2000


AAV PROVIDER:
 AT&T
 PHONE: (800) 288-2020

PROJECT MANAGER:
 AIROSMITH DEVELOPMENT
 TERRI BURKHOLDER
 (315) 719-2928
 TBURKHOLDER@AIROSMITHDEVELOPMENT.COM

AREA MAP



LOCATION MAP



PROJECT DESCRIPTION

SPRINT PROPOSES TO MODIFY AN EXISTING UNMANNED TELECOMMUNICATIONS FACILITY.

- REMOVE (3) PANEL ANTENNAS
- INSTALL (6) PANEL ANTENNAS
- INSTALL (3) 800 MHz RRH'S BELOW ANTENNAS
- INSTALL (30) JUMPER CABLES
- INSTALL (2) 1.689" HYBRID CABLES
- INSTALL 2.5 EQUIPMENT INSIDE EXISTING N.V. MMBS CABINET

THESE PLANS HAVE BEEN DEVELOPED FOR THE MODIFICATION OF AN EXISTING UNMANNED TELECOMMUNICATIONS FACILITY OWNED OR LEASED BY SPRINT IN ACCORDANCE WITH THE SCOPE OF WORK PROVIDED BY SPRINT. INFINIGY HAS INCORPORATED THIS SCOPE OF WORK IN THE PLANS. THESE PLANS ARE NOT FOR CONSTRUCTION UNLESS ACCOMPANIED BY A PASSING STRUCTURAL STABILITY ANALYSIS PREPARED BY A LICENSED STRUCTURAL ENGINEER. STRUCTURAL ANALYSIS MUST INCLUDE BOTH TOWER AND MOUNT.

APPLICABLE CODES

- ALL WORK SHALL BE PERFORMED AND MATERIALS INSTALL IN ACCORDANCE WITH THE CURRENT EDITIONS OF THE FOLLOWING CODES AS ADOPTED BY THE LOCAL GOVERNING AUTHORITIES. NOTHING IN THESE PLANS IS TO BE CONSTRUED TO PERMIT WORK NOT CONFORMING TO THESE CODES.
- INTERNATIONAL BUILDING CODE (2015 IBC)
 - TIA-222-G OR LATEST EDITION
 - NFPA 780 - LIGHTNING PROTECTION CODE
 - 2011 NATIONAL ELECTRIC CODE OR LATEST EDITION
 - ANY OTHER NATIONAL OR LOCAL APPLICABLE CODES, MOST RECENT EDITIONS
 - CT BUILDING CODE
 - LOCAL BUILDING CODE
 - CITY/COUNTY ORDINANCES

DRAWING INDEX

SHEET NO.	SHEET TITLE	REV.
T-1	TITLE SHEET & PROJECT DATA	0
SP-1	SPRINT SPECIFICATIONS	0
SP-2	SPRINT SPECIFICATIONS	0
SP-3	SPRINT SPECIFICATIONS	0
A-1	SITE PLAN	0
A-2	TOWER ELEVATION	0
A-3	ANTENNA LAYOUT & MOUNTING DETAILS	0
A-4	EQUIPMENT & MOUNTING DETAILS	0
A-5	CIVIL DETAILS	0
A-6	PLUMBING DIAGRAM	0
E-1	ELECTRICAL & GROUNDING PLAN	0
E-2	ELECTRICAL & GROUNDING DETAILS	0



THESE OUTLINE SPECIFICATIONS IN CONJUNCTION WITH THE SPRINT STANDARD CONSTRUCTION SPECIFICATIONS, INCLUDING CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

SECTION 01 100 - SCOPE OF WORK

PART 1 - GENERAL

- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE SPRINT CONSTRUCTION STANDARDS FOR WIRELESS SITES, CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
 - A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
 - B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.
- 1.3 PRECEDENCE: SHOULD CONFLICTS OCCUR BETWEEN THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES INCLUDING THE STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES AND THE CONSTRUCTION DRAWINGS, INFORMATION ON THE CONSTRUCTION DRAWINGS SHALL TAKE PRECEDENCE. NOTIFY SPRINT CONSTRUCTION MANAGER IF THIS OCCURS.
- 1.4 NATIONALLY RECOGNIZED CODES AND STANDARDS:
 - A. THE WORK SHALL COMPLY WITH APPLICABLE NATIONAL AND LOCAL CODES AND STANDARDS, LATEST EDITION, AND PORTIONS THEREOF, INCLUDED BUT NOT LIMITED TO THE FOLLOWING:
 1. GR-63-CORE NEBS REQUIREMENTS: PHYSICAL PROTECTION
 5. GR-78-CORE GENERIC REQUIREMENTS FOR THE PHYSICAL DESIGN AND MANUFACTURE OF TELECOMMUNICATIONS EQUIPMENT.
 3. GR-1089 CORE, ELECTROMAGNETIC COMPATIBILITY AND ELECTRICAL SAFETY -GENERIC CRITERIA FOR NETWORK TELECOMMUNICATIONS EQUIPMENT.
 4. NATIONAL FIRE PROTECTION ASSOCIATION CODES AND STANDARDS (NFPA) INCLUDING NFPA 70 (NATIONAL ELECTRICAL CODE - "NEC") AND NFPA 101 (LIFE SAFETY CODE).
 5. AMERICAN SOCIETY FOR TESTING OF MATERIALS (ASTM)
 6. INSTITUTE OF ELECTRONIC AND ELECTRICAL ENGINEERS (IEEE)
 7. AMERICAN CONCRETE INSTITUTE (ACI)
 8. AMERICAN WIRE PRODUCERS ASSOCIATION (AWPA)
 9. CONCRETE REINFORCING STEEL INSTITUTE (CRSI)
 10. AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)
 11. PORTLAND CEMENT ASSOCIATION (PCA)
 12. NATIONAL CONCRETE MASONRY ASSOCIATION (NCMA)
 13. BRICK INDUSTRY ASSOCIATION (BIA)
 14. AMERICAN WELDING SOCIETY (AWS)
 15. NATIONAL ROOFING CONTRACTORS ASSOCIATION (NRCA)
 16. SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)
 17. DOOR AND HARDWARE INSTITUTE (DHI)
 18. OCCUPATIONAL SAFETY AND HEALTH ACT (OSHA)
 19. APPLICABLE BUILDING CODES INCLUDING UNIFORM BUILDING CODE, SOUTHERN BUILDING CODE, BOCA, AND THE INTERNATIONAL BUILDING CODE.

1.5 DEFINITIONS:

- A. WORK: THE SUM OF TASKS AND RESPONSIBILITIES IDENTIFIED IN THE CONTRACT DOCUMENTS.
- B. COMPANY: SPRINT CORPORATION
- C. ENGINEER: SYNONYMOUS WITH ARCHITECT & ENGINEER AND "A&E". THE DESIGN PROFESSIONAL HAVING PROFESSIONAL RESPONSIBILITY FOR DESIGN OF THE PROJECT.
- D. CONTRACTOR: CONSTRUCTION CONTRACTOR; CONSTRUCTION VENDOR; INDIVIDUAL OR ENTITY WHO AFTER EXECUTION OF A CONTRACT IS BOUND TO ACCOMPLISH THE WORK.
- E. THIRD PARTY VENDOR OR AGENCY: A VENDOR OR AGENCY ENGAGED SEPARATELY BY THE COMPANY, A&E, OR CONTRACTOR TO PROVIDE MATERIALS OR TO ACCOMPLISH SPECIFIC TASKS RELATED TO BUT NOT INCLUDED IN THE WORK.
- F. OFC: OWNER FURNISHED, CONTRACTOR INSTALLED EQUIPMENT.
- G. CONSTRUCTION MANAGER - ALL PROJECTS RELATED COMMUNICATION TO FLOW THROUGH SPRINT REPRESENTATIVE IN CHARGE OF PROJECT...

- 1.6 SITE FAMILIARITY: CONTRACTOR SHALL BE RESPONSIBLE FOR FAMILIARIZING HIMSELF WITH ALL CONTRACT DOCUMENTS, FIELD CONDITIONS AND DIMENSIONS PRIOR TO PROCEEDING WITH CONSTRUCTION. ANY DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE SPRINT CONSTRUCTION MANAGER PRIOR TO THE COMMENCEMENT OF WORK. NO COMPENSATION WILL BE AWARDED BASED ON CLAIM OF LACK OF KNOWLEDGE OR FIELD CONDITIONS.
- 1.7 POINT OF CONTACT: COMMUNICATION BETWEEN SPRINT AND THE CONTRACTOR SHALL FLOW THROUGH THE SINGLE SPRINT CONSTRUCTION MANAGER APPOINTED TO MANAGE THE PROJECT FOR SPRINT.
- 1.8 ON-SITE SUPERVISION: THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK AND SHALL BE RESPONSIBLE FOR CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES IN ACCORDANCE WITH THE CONTRACT DOCUMENTS. THE CONTRACTOR SHALL EMPLOY A COMPETENT SUPERINTENDENT WHO SHALL BE IN ATTENDANCE AT THE SITE AT ALL TIMES DURING PERFORMANCE OF THE WORK.
- 1.9 DRAWINGS, SPECIFICATIONS AND DETAILS REQUIRED AT JOBSITE: THE CONSTRUCTION CONTRACTOR SHALL MAINTAIN A FULL SET OF THE CONSTRUCTION DRAWINGS, STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES AND THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES AT THE JOBSITE FROM MOBILIZATION THROUGH CONSTRUCTION COMPLETION.
 - A. THE JOBSITE DRAWINGS, SPECIFICATIONS AND DETAILS SHALL BE CLEARLY MARKED DAILY IN RED PENCIL WITH ANY CHANGES IN CONSTRUCTION OVER WHAT IS DEPICTED IN THE DOCUMENTS. AT CONSTRUCTION COMPLETION, THIS JOBSITE MARKUP SET SHALL BE DELIVERED TO THE COMPANY OR COMPANY'S DESIGNATED REPRESENTATIVE TO BE FORWARDED TO THE COMPANY'S A&E VENDOR FOR PRODUCTION OF "AS-BUILT" DRAWINGS.
 - B. DETAILS ARE INTENDED TO SHOW DESIGN INTENT. MODIFICATIONS MAY BE REQUIRED TO SUIT JOB DIMENSIONS OR CONDITIONS, AND SUCH MODIFICATIONS SHALL BE INCLUDED AS PART OF THE WORK. CONTRACTOR SHALL NOTIFY SPRINT CONSTRUCTION MANAGER OF ANY VARIATIONS PRIOR TO PROCEEDING WITH THE WORK.
 - C. DIMENSIONS SHOWN ARE TO FINISH SURFACES UNLESS NOTED OTHERWISE. SPACING BETWEEN EQUIPMENT IS THE REQUIRED CLEARANCE. SHOULD THERE BE ANY QUESTIONS REGARDING THE CONTRACT DOCUMENTS, EXISTING CONDITIONS AND/OR DESIGN INTENT, THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING A CLARIFICATION FROM THE SPRINT CONSTRUCTION MANAGER PRIOR TO PROCEEDING WITH THE WORK.
- 1.10 USE OF JOB SITE: THE CONTRACTOR SHALL CONFINE ALL CONSTRUCTION AND RELATED OPERATIONS INCLUDING STAGING AND STORAGE OF MATERIALS AND EQUIPMENT, PARKING, TEMPORARY FACILITIES, AND WASTE STORAGE TO THE LEASE PARCEL UNLESS OTHERWISE PERMITTED BY THE CONTRACT DOCUMENTS.
- 1.11 UTILITIES SERVICES: WHERE NECESSARY TO CUT EXISTING PIPES, ELECTRICAL WIRES, CONDUITS, CABLES, ETC., OF UTILITY SERVICES, OR OF FIRE PROTECTION OR COMMUNICATIONS SYSTEMS, THEY SHALL BE CUT AND CAPPED AT SUITABLE PLACES OR WHERE SHOWN. ALL SUCH ACTIONS SHALL BE COORDINATED WITH THE UTILITY COMPANY INVOLVED:
- 1.12 PERMITS / FEES: WHEN REQUIRED THAT A PERMIT OR CONNECTION FEE BE PAID TO A PUBLIC UTILITY PROVIDER FOR NEW SERVICE TO THE CONSTRUCTION PROJECT, PAYMENT OF SUCH FEE SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.
- 1.13 CONTRACTOR SHALL TAKE ALL MEASURES AND PROVIDE ALL MATERIAL NECESSARY FOR PROTECTING EXISTING EQUIPMENT AND PROPERTY.
- 1.14 METHODS OF PROCEDURE (MOPS) FOR CONSTRUCTION: CONTRACTOR SHALL PERFORM WORK AS DESCRIBED IN THE FOLLOWING INSTALLATION AND COMMISSIONING MOPS.

NOTE: IN SHORT-FORM SPECIFICATIONS ON THE DRAWINGS, A/E TO INSERT LIST OF APPLICABLE MOPS INCLUDING EN-2012-001, EN-2013-002, EL-0568, AND TS-0193
- 1.15 USE OF ELECTRONIC PROJECT MANAGEMENT SYSTEMS:

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION

- 3.1 TEMPORARY UTILITIES AND FACILITIES: THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL TEMPORARY UTILITIES AND FACILITIES NECESSARY EXCEPT AS OTHERWISE INDICATED IN THE CONSTRUCTION DOCUMENTS. TEMPORARY UTILITIES AND FACILITIES INCLUDE POTABLE WATER, HEAT, HVAC, ELECTRICITY, SANITARY FACILITIES, WASTE DISPOSAL FACILITIES, AND TELEPHONE/COMMUNICATION SERVICES. PROVIDE TEMPORARY UTILITIES AND FACILITIES IN ACCORDANCE WITH OSHA AND THE AUTHORITY HAVING JURISDICTION. CONTRACTOR MAY UTILIZE THE COMPANY ELECTRICAL SERVICE IN THE COMPLETION OF THE WORK WHEN IT BECOMES AVAILABLE. USE OF THE LESSORS OR SITE OWNER'S UTILITIES OR FACILITIES IS EXPRESSLY FORBIDDEN EXCEPT AS OTHERWISE ALLOWED IN THE CONTRACT DOCUMENTS.
- 3.2 ACCESS TO WORK: THE CONTRACTOR SHALL PROVIDE ACCESS TO THE JOB SITE FOR AUTHORIZED COMPANY PERSONNEL AND AUTHORIZED REPRESENTATIVES OF THE ARCHITECT/ENGINEER DURING ALL PHASES OF THE WORK.
- 3.3 TESTING: REQUIREMENTS FOR TESTING BY THIS CONTRACTOR SHALL BE AS INDICATED HEREWITH, ON THE CONSTRUCTION DRAWINGS, AND IN THE INDIVIDUAL SECTIONS OF THESE SPECIFICATIONS. SHOULD COMPANY CHOOSE TO ENGAGE ANY THIRD-PARTY TO CONDUCT ADDITIONAL TESTING, THE CONTRACTOR SHALL COOPERATE WITH AND PROVIDE A WORK AREA FOR COMPANY'S TEST AGENCY.
- 3.4 DIMENSIONS: VERIFY DIMENSIONS INDICATED ON DRAWINGS WITH FIELD DIMENSIONS BEFORE FABRICATION OR ORDERING OF MATERIALS. DO NOT SCALE DRAWINGS.

3.5 EXISTING CONDITIONS: NOTIFY THE SPRINT CONSTRUCTION MANAGER OF EXISTING CONDITIONS DIFFERING FROM THOSE INDICATED ON THE DRAWINGS. DO NOT REMOVE OR ALTER STRUCTURAL COMPONENTS WITHOUT PRIOR WRITTEN APPROVAL FROM THE ARCHITECT AND ENGINEER.

SECTION 01 200 - COMPANY FURNISHED MATERIAL AND EQUIPMENT

PART 1 - GENERAL

- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
 - A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
 - B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION

- 3.1 RECEIPT OF MATERIAL AND EQUIPMENT:
 - A. A COMPANY FURNISHED MATERIAL AND EQUIPMENT IS IDENTIFIED ON THE RF DATA SHEET IN THE CONSTRUCTION DOCUMENTS.
 - B. THE CONTRACTOR IS RESPONSIBLE FOR SPRINT PROVIDED MATERIAL AND EQUIPMENT AND UPON RECEIPT SHALL:
 1. ACCEPT DELIVERIES AS SHIPPED AND TAKE RECEIPT.
 2. VERIFY COMPLETENESS AND CONDITION OF ALL DELIVERIES.
 3. TAKE RESPONSIBILITY FOR EQUIPMENT AND PROVIDE INSURANCE PROTECTION AS REQUIRED IN AGREEMENT.
 4. RECORD ANY DEFECTS OR DAMAGES AND WITHIN TWENTY-FOUR HOURS AFTER RECEIPT, REPORT TO SPRINT OR ITS DESIGNATED PROJECT REPRESENTATIVE OF SUCH.
 5. PROVIDE SECURE AND NECESSARY WEATHER PROTECTED WAREHOUSING.
 6. COORDINATE SAFE AND SECURE TRANSPORTATION OF MATERIAL AND EQUIPMENT, DELIVERING AND OFF-LOADING FROM CONTRACTOR'S WAREHOUSE TO SITE.
- 3.2 DELIVERABLES:
 - A. COMPLETE SHIPPING AND RECEIPT DOCUMENTATION IN ACCORDANCE WITH COMPANY PRACTICE.
 - B. IF APPLICABLE, COMPLETE LOST/STOLEN/DAMAGED DOCUMENTATION REPORT AS NECESSARY IN ACCORDANCE WITH COMPANY PRACTICE, AND AS DIRECTED BY COMPANY.
 - C. UPLOAD DOCUMENTATION INTO SPRINT SITE MANAGEMENT SYSTEM (SMS) AND/OR PROVIDE HARD COPY DOCUMENTATION AS REQUESTED.

SECTION 01 300 - CELL SITE CONSTRUCTION CO.

PART 1 - GENERAL

- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
 - A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
 - B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.
- 1.3 NOTICE TO PROCEED
 - A. NO WORK SHALL COMMENCE PRIOR TO COMPANY'S WRITTEN NOTICE TO PROCEED AND THE ISSUANCE OF THE WORK ORDER.
 - B. UPON RECEIVING NOTICE TO PROCEED, CONTRACTOR SHALL FULLY PERFORM ALL WORK NECESSARY TO PROVIDE SPRINT WITH AN OPERATIONAL WIRELESS FACILITY.

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION

- 3.1 FUNCTIONAL REQUIREMENTS:
 - A. THE ACTIVITIES DESCRIBED IN THIS PARAGRAPH REPRESENT MINIMUM ACTIONS AND PROCESSES REQUIRED TO SUCCESSFULLY COMPLETE THE WORK. THE ACTIVITIES DESCRIBED ARE NOT EXHAUSTIVE, AND CONTRACTOR SHALL TAKE ANY AND ALL ACTIONS AS NECESSARY TO SUCCESSFULLY COMPLETE THE CONSTRUCTION OF A FULLY FUNCTIONING WIRELESS FACILITY AT THE SITE IN ACCORDANCE WITH COMPANY PROCESSES.
 - B. SUBMIT SPECIFIC DOCUMENTATION AS INDICATED HEREIN, AND OBTAIN REQUIRED APPROVALS WHILE THE WORK IS BEING PERFORMED.
 - C. MANAGE AND CONDUCT ALL FIELD CONSTRUCTION SERVICE RELATED ACTIVITIES
 - D. PROVIDE CONSTRUCTION ACTIVITIES TO THE EXTENT REQUIRED BY THE CONTRACT DOCUMENTS, INCLUDING BUT NOT LIMITED TO THE FOLLOWING:

PLANS PREPARED FOR:



PLANS PREPARED BY:

INFINIGY
FROM ZERO TO INFINIGY
the solutions are endless
1033 Watervliet Shaker Rd | Albany, NY 12209
Phone: 518-690-0790 | Fax: 518-690-0793
www.infinigy.com
JOB NUMBER: 526-104

PROJECT MANAGER:

AIRSMITH DEVELOPMENT
32 CLINTON ST.
SARATOGA SPRINGS, NY 12866
OFFICE# (518) 306-3740

ENGINEERING LICENSE:



DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV.
ISSUED FOR PERMIT	07/18/18	ETC	0

SITE NAME:

BOOTH HILL

SITE NUMBER:

CT03XC366

SITE ADDRESS:

**14 OXFORD DRIVE
SHELTON, CT 06484**

SHEET DESCRIPTION:

SPRINT SPECIFICATIONS

SHEET NUMBER:

SP-1

CONTINUE FROM SP-1

1. PERFORM ANY REQUIRED SITE ENVIRONMENTAL MITIGATION.
2. PREPARE GROUND SITES; PROVIDE DE-GRUBBING; AND ROUGH AND FINAL GRADING, AND COMPOUND SURFACE TREATMENTS.
3. MANAGE AND CONDUCT ALL ACTIVITIES FOR INSTALLATION OF UTILITIES INCLUDING ELECTRICAL AND TELCO BACKHAUL.
4. INSTALL UNDERGROUND FACILITIES INCLUDING UNDERGROUND POWER AND COMMUNICATIONS CONDUITS, AND UNDERGROUND GROUNDING SYSTEM.
5. INSTALL ABOVE GROUND GROUNDING SYSTEMS.
6. PROVIDE NEW HVAC INSTALLATIONS AND MODIFICATIONS.
7. INSTALL "H-FRAMES", CABINETS AND SHELTERS AS INDICATED.
8. INSTALL ROADS, ACCESS WAYS, CURBS AND DRAINS AS INDICATED.
9. ACCOMPLISH REQUIRED MODIFICATION OF EXISTING FACILITIES.
10. PROVIDE ANTENNA SUPPORT STRUCTURE FOUNDATIONS.
11. PROVIDE SLABS AND EQUIPMENT PLATFORMS.
12. INSTALL COMPOUND FENCING, SIGHT SHIELDING, LANDSCAPING AND ACCESS BARRIERS.
13. PERFORM INSPECTION AND MATERIAL TESTING AS REQUIRED HEREINAFTER.
14. CONDUCT SITE RESISTANCE TO EARTH TESTING AS REQUIRED HEREINAFTER.
15. INSTALL FIXED GENERATOR SETS AND OTHER STANDBY POWER SOLUTIONS.
16. INSTALL TOWERS, ANTENNA SUPPORT STRUCTURES AND PLATFORMS ON EXISTING TOWERS AS REQUIRED.
17. INSTALL CELL SITE RADIOS, MICROWAVE, GPS, COAXIAL MAINLINE, ANTENNAS, CROSS BAND COUPLERS, TOWER TOP AMPLIFIERS, LOW NOISE AMPLIFIERS AND RELATED EQUIPMENT.
18. PERFORM, DOCUMENT, AND CLOSE OUT ANY CONSTRUCTION CONTROL DOCUMENTS THAT MAY BE REQUIRED BY GOVERNMENT AGENCIES AND LANDLORDS.
19. PERFORM ANTENNA AND COAX SWEEP TESTING AND MAKE ANY AND ALL NECESSARY CORRECTIONS.
20. REMAIN ON SITE MOBILIZED THROUGHOUT HAND-OFF AND INTEGRATION TO ASSIST AS NEEDED UNTIL SITE IS DEEMED SUBSTANTIALLY COMPLETE AND PLACED "ON AIR."

3.2 GENERAL REQUIREMENTS FOR CIVIL CONSTRUCTION:

- A. CONTRACTOR SHALL KEEP THE SITE FREE FROM ACCUMULATING WASTE MATERIAL, DEBRIS, AND TRASH. AT THE COMPLETION OF THE WORK, CONTRACTOR SHALL REMOVE FROM THE SITE ALL REMAINING RUBBISH, IMPLEMENTS, TEMPORARY FACILITIES, AND SURPLUS MATERIALS.
- B. EQUIPMENT ROOMS SHALL AT ALL TIMES BE MAINTAINED "BROOM CLEAN" AND CLEAR OF DEBRIS.
- C. CONTRACTOR SHALL TAKE ALL REASONABLE PRECAUTIONS TO DISCOVER AND LOCATE ANY HAZARDOUS CONDITION.
 1. IN THE EVENT CONTRACTOR ENCOUNTERS ANY HAZARDOUS CONDITION WHICH HAS NOT BEEN ABATED OR OTHERWISE MITIGATED, CONTRACTOR AND ALL OTHER PERSONS SHALL IMMEDIATELY STOP WORK IN THE AFFECTED AREA AND NOTIFY COMPANY IN WRITING. THE WORK IN THE AFFECTED AREA SHALL NOT BE RESUMED EXCEPT BY WRITTEN NOTIFICATION BY COMPANY.
 2. CONTRACTOR AGREES TO USE CARE WHILE ON THE SITE AND SHALL NOT TAKE ANY ACTION THAT WILL OR MAY RESULT IN OR CAUSE THE HAZARDOUS CONDITION TO BE FURTHER RELEASED IN THE ENVIRONMENT, OR TO FURTHER EXPOSE INDIVIDUALS TO THE HAZARD.
- D. CONTRACTOR'S ACTIVITIES SHALL BE RESTRICTED TO THE PROJECT LIMITS. SHOULD AREAS OUTSIDE THE PROJECT LIMITS BE AFFECTED BY CONTRACTOR'S ACTIVITIES, CONTRACTOR SHALL IMMEDIATELY RETURN THEM TO ORIGINAL CONDITION
- E. CONDUCT TESTING AS REQUIRED HEREIN.

3.3 DELIVERABLES:

- A. CONTRACTOR SHALL REVIEW, APPROVE, AND SUBMIT TO SPRINT SHOP DRAWINGS, PRODUCT DATA, SAMPLES, AND SIMILAR SUBMITTALS AS REQUIRED HEREINAFTER
- B. PROVIDE DOCUMENTATION INCLUDING, BUT NOT LIMITED TO, THE FOLLOWING. DOCUMENTATION SHALL BE FORWARDED IN ORIGINAL FORMAT AND/OR UPLOADED INTO SMS.
 1. ALL CORRESPONDENCE AND PRELIMINARY CONSTRUCTION REPORTS.
 2. PROJECT PROGRESS REPORTS.
 3. CIVIL CONSTRUCTION START DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
 4. ELECTRICAL SERVICE COMPLETION DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).

5. LINES AND ANTENNA INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
6. POWER INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
7. TELCO READY DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
8. PPC (OR SHELTER) INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
9. TOWER CONSTRUCTION START DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
10. TOWER CONSTRUCTION COMPLETE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
11. BTS AND RADIO EQUIPMENT DELIVERED AT SITE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
12. NETWORK OPERATIONS HANDOFF CHECKLIST (HOC WALK) COMPLETE (UPLOAD FORM IN SMS)
13. CIVIL CONSTRUCTION COMPLETE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
14. SITE CONSTRUCTION PROGRESS PHOTOS UNLOADED INTO SMS.

SECTION 01 400 - SUBMITTALS & TESTS

PART 1 - GENERAL

- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
 - A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
 - B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.
- 1.3 SUBMITTALS:
 - A. THE WORK IN ALL ASPECTS SHALL COMPLY WITH THE CONSTRUCTION DRAWINGS AND THESE SPECIFICATIONS.
 - B. SUBMIT THE FOLLOWING TO COMPANY REPRESENTATIVE FOR APPROVAL.
 1. CONCRETE MIX-DESIGNS FOR TOWER FOUNDATIONS, ANCHORS PIERS, AND CONCRETE PAVING.
 2. CONCRETE BREAK TESTS AS SPECIFIED HEREIN.
 3. SPECIAL FINISHES FOR INTERIOR SPACES, IF ANY.
 4. ALL EQUIPMENT AND MATERIALS SO IDENTIFIED ON THE CONSTRUCTION DRAWINGS.
 5. CHEMICAL GROUNDING DESIGN
 - D. ALTERNATES: AT THE COMPANY'S REQUEST, ANY ALTERNATIVES TO THE MATERIALS OR METHODS SPECIFIED SHALL BE SUBMITTED TO SPRINT'S CONSTRUCTION MANAGER FOR APPROVAL PRIOR TO BEING SHIPPED TO SITE. SPRINT WILL REVIEW AND APPROVE ONLY THOSE REQUESTS MADE IN WRITING. NO VERBAL APPROVALS WILL BE CONSIDERED. SUBMITTAL FOR APPROVAL SHALL INCLUDE A STATEMENT OF COST REDUCTION PROPOSED FOR USE OF ALTERNATE PRODUCT.

1.4 TESTS AND INSPECTIONS:

- A. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CONSTRUCTION TESTS, INSPECTIONS AND PROJECT DOCUMENTATION.
- B. CONTRACTOR SHALL ACCOMPLISH TESTING INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
 1. COAX SWEEPS AND FIBER TESTS PER TS-0200 REV 4 ANTENNA LINE ACCEPTANCE STANDARDS.
 2. AGL, AZIMUTH AND DOWNTILT USING ELECTRONIC COMMERCIAL MADE-FOR-THE-PURPOSE ANTENNA ALIGNMENT TOOL.
 3. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN SITE INSPECTION ACTIVITIES AND/OR AS A RESULT OF TESTING.
- C. REQUIRED CLOSEOUT DOCUMENTATION INCLUDES, BUT IS NOT LIMITED TO THE FOLLOWING:
 1. AZIMUTH, DOWNTILT, AGL - UPLOAD REPORT FROM ANTENNA ALIGNMENT TOOL TO SITERRA TASK 465. INSTALLED AZIMUTH, DOWNTILT, AND AGL MUST CONFORM TO THE RF DATA SHEETS. SWEEP AND FIBER TESTS
 2. SCANABLE BARCODE PHOTOGRAPHS OF TOWER TOP AND INACCESSIBLE SERIALIZED EQUIPMENT
 3. ALL AVAILABLE JURISDICTIONAL INFORMATION
 4. PDF SCAN OF REDLINES PRODUCED IN FIELD

5. ELECTRONIC AS-BUILT DRAWINGS IN AUTOCAD AND PDF FORMATS. ANY FIELD CHANGE MUST BE REFLECTED BY MODIFYING THE PLANS, ELEVATIONS, AND DETAILS IN THE DRAWING SETS. GENERAL NOTES INDICATING MODIFICATIONS WILL NOT BE ACCEPTED. CHANGES SHALL BE HIGHLIGHTED AS "CLOUDS" IDENTIFIED AS THE "AS-BUILT" CONDITION.
6. LIEN WAIVERS
7. FINAL PAYMENT APPLICATION
8. REQUIRED FINAL CONSTRUCTION PHOTOS
9. CONSTRUCTION AND COMMISSIONING CHECKLIST COMPLETE WITH NO DEFICIENT ITEMS
10. ALL POST NTP TASKS INCLUDING DOCUMENT UPLOADS COMPLETED IN SITERRA (SPRINTS DOCUMENT REPOSITORY OF RECORD).

1.5 COMMISSIONING: PERFORM ALL COMMISSIONING AS REQUIRED BY APPLICABLE MOPs

1.6 INTEGRATION: PERFORM ALL INTEGRATION ACTIVITIES AS REQUIRED BY APPLICABLE MOPs

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION

3.1 REQUIREMENTS FOR TESTING:

A. THIRD PARTY TESTING AGENCY:

1. WHEN THE USE OF A THIRD PARTY INDEPENDENT TESTING AGENCY IS REQUIRED, THE AGENCY THAT IS SELECTED MUST PERFORM SUCH WORK ON A REGULAR BASIS IN THE STATE WHERE THE PROJECT IS LOCATED AND HAVE A THOROUGH UNDERSTANDING OF LOCAL AVAILABLE MATERIALS, INCLUDING THE SOIL, ROCK, AND GROUNDWATER CONDITIONS.
2. THE THIRD PARTY TESTING AGENCY IS TO BE FAMILIAR WITH THE APPLICABLE REQUIREMENTS FOR THE TESTS TO BE DONE, EQUIPMENT TO BE USED, AND ASSOCIATED HEALTH AND SAFETY ISSUES.
3. EXPERIENCE IN SOILS, CONCRETE, MASONRY, AGGREGATE, AND ASPHALT TESTING USING ASTM, AASJTO, AND OTHER METHODS IS NEEDED.
4. EXPERIENCE IN SOILS, CONCRETE, MASONRY, AGGREGATE, AND ASPHALT TESTING USING ASTM, AASJTO, AND OTHER METHODS IS NEEDED.

3.2 REQUIRED TESTS:

- A. CONTRACTOR SHALL ACCOMPLISH TESTING INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
 1. CONCRETE CYLINDER BREAK TESTS FOR THE TOWER AND ANCHOR FOUNDATIONS AS SPECIFIED IN SECTION: PORTLAND CEMENT CONCRETE PAVING.
 2. ASPHALT ROADWAY COMPACTED THICKNESS, SURFACE SMOOTHNESS, AND COMPACTED DENSITY TESTING AS SPECIFIED IN SECTION: HOT MIX ASPHALT PAVING.
 3. FIELD QUALITY CONTROL TESTING AS SPECIFIED IN SECTION: PORTLAND CEMENT CONCRETE PAVING.
 4. TESTING REQUIRED UNDER SECTION: AGGREGATE BASE FOR ACCESS ROADS, PADS AND ANCHOR LOCATIONS
 5. STRUCTURAL BACKFILL COMPACTION TESTS FOR THE TOWER FOUNDATION.
 6. SITE RESISTANCE TO EARTH TESTING PER EXHIBIT: CELL SITE GROUNDING SYSTEM DESIGN.
 7. ANTENNA AND COAX SWEEP TESTS PER EXHIBIT: ANTENNA TRANSMISSION LINE ACCEPTANCE STANDARDS.
 8. GROUNDING AT ANTENNA MASTS FOR GPS AND ANTENNAS
 9. ALL OTHER TESTS REQUIRED BY COMPANY OR JURISDICTION.

3.3 REQUIRED INSPECTIONS

- A. SCHEDULE INSPECTIONS WITH COMPANY REPRESENTATIVE.
- B. CONDUCT INSPECTIONS INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
 1. GROUNDING SYSTEM INSTALLATION PRIOR TO EARTH CONCEALMENT DOCUMENTED WITH DIGITAL PHOTOGRAPHS BY CONTRACTOR, APPROVED BY A&E OR SPRINT REPRESENTATIVE.
 2. FORMING FOR CONCRETE AND REBAR PLACEMENT PRIOR TO POUR DOCUMENTED WITH DIGITAL PHOTOGRAPHS BY CONTRACTOR, APPROVED BY A&E OR SPRINT REPRESENTATIVE.
 3. COMPACTION OF BACKFILL MATERIALS; AGGREGATE BASE FOR ROADS, PADS, AND ANCHORS; ASPHALT PAVING; AND SHAFT BACKFILL FOR CONCRETE AND WOOD POLES, BY INDEPENDENT THIRD PARTY AGENCY.
 4. PRE- AND POST-CONSTRUCTION ROOFTOP AND STRUCTURAL INSPECTIONS ON EXISTING FACILITIES.
 5. TOWER ERECTION SECTION STACKING AND PLATFORM ATTACHMENT DOCUMENTED BY DIGITAL PHOTOGRAPHS BY THIRD PARTY AGENCY.
 6. ANTENNA AZIMUTH, DOWN TILT AND PER SUNLIGHT TOOL SUNSIGHT INSTRUMENTS - ANTENNA ALIGNMENT TOOL (AAT)

PLANS PREPARED FOR:



PLANS PREPARED BY:

INFINIGY
FROM ZERO TO INFINIGY
the solutions are endless
1033 Watervliet Shaker Rd | Albany, NY 12205
Phone: 518-690-0790 | Fax: 518-690-0793
www.infinigy.com
JOB NUMBER 526-104

PROJECT MANAGER:

AIRSMITH
DEVELOPMENT
32 CLINTON ST.
SARATOGA SPRINGS, NY 12866
OFFICE# (518) 306-3740

ENGINEERING LICENSE:



DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV.
ISSUED FOR PERMIT	07/18/18	ETC	0

SITE NAME:

BOOTH HILL

SITE NUMBER:

CT03XC366

SITE ADDRESS:

**14 OXFORD DRIVE
SHELTON, CT 06484**

SHEET DESCRIPTION:

SPRINT SPECIFICATIONS

SHEET NUMBER:

SP-2

CONTINUE FROM SP-2

7. VERIFICATION DOCUMENTED WITH THE ANTENNA CHECKLIST REPORT, BY A&E, SITE DEVELOPMENT REP, OR RF REP.
 8. FINAL INSPECTION CHECKLIST AND HANDOFF WALK (HOC). SIGNED FORM SHOWING ACCEPTANCE BY FIELD OPS IS TO BE UPLOADED INTO SMS.
 9. COAX SWEEP AND FIBER TESTING DOCUMENTS SUBMITTED VIA SMS FOR RF APPROVAL.
 10. SCAN-ABLE BARCODE PHOTOGRAPHS OF TOWER TOP AND INACCESSIBLE SERIALIZED EQUIPMENT
 11. ALL AVAILABLE JURISDICTIONAL INFORMATION
 12. PDF SCAN OF REDLINES PRODUCED IN FIELD
- C. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN SITE INSPECTION ACTIVITIES AND/OR AS A RESULT OF TESTING.
- D. CONSTRUCTION INSPECTIONS AND CORRECTIVE MEASURES SHALL BE DOCUMENTED BY THE CONTRACTOR WITH WRITTEN REPORTS AND PHOTOGRAPHS. PHOTOGRAPHS MUST BE DIGITAL AND OF SUFFICIENT QUALITY TO CLEARLY SHOW THE SITE CONSTRUCTION. PHOTOGRAPHS MUST CLEARLY IDENTIFY THE PHOTOGRAPHED ITEM AND BE LABELED WITH THE SITE CASCADE NUMBER, SITE NAME, DESCRIPTION, AND DATE.
- 3.4 DELIVERABLES: TEST AND INSPECTION REPORTS AND CLOSEOUT DOCUMENTATION SHALL BE UPLOADED TO THE SMS AND/OR FORWARDED TO SPRINT FOR INCLUSION INTO THE PERMANENT SITE FILES.
- A. THE FOLLOWING TEST AND INSPECTION REPORTS SHALL BE PROVIDED AS APPLICABLE.
1. CONCRETE MIX AND CYLINDER BREAK REPORTS.
 2. STRUCTURAL BACKFILL COMPACTION REPORTS.
 3. SITE RESISTANCE TO EARTH TEST.
 4. ANTENNA AZIMUTH AND DOWN TILT VERIFICATION
 5. TOWER ERECTION INSPECTIONS AND MEASUREMENTS DOCUMENTING TOWER INSTALLED PER SUPPLIER'S REQUIREMENTS AND THE APPLICABLE SECTIONS HEREIN.
 6. COAX CABLE SWEEP TESTS PER COMPANY'S "ANTENNA LINE ACCEPTANCE STANDARDS".
- B. REQUIRED CLOSEOUT DOCUMENTATION INCLUDES THE FOLLOWING;
1. TEST WELLS AND TRENCHES: PHOTOGRAPHS OF ALL TEST WELLS; PHOTOGRAPHS SHOWING ALL OPEN EXCAVATIONS AND TRENCHING PRIOR TO BACKFILLING SHOWING A TAPE MEASURE VISIBLE IN THE EXCAVATIONS INDICATING DEPTH.
 2. CONDUITS, CONDUCTORS AND GROUNDING: PHOTOGRAPHS SHOWING TYPICAL INSTALLATION OF CONDUCTORS AND CONNECTORS; PHOTOGRAPHS SHOWING TYPICAL BEND RADIUS OF INSTALLED GROUND WIRES AND GROUND ROD SPACING;
 3. CONCRETE FORMS AND REINFORCING: CONCRETE FORMING AT TOWER AND EQUIPMENT/SHELTER PAD/FOUNDATIONS - PHOTOGRAPHS SHOWING ALL REINFORCING STEEL, UTILITY AND CONDUIT STUB OUTS; PHOTOGRAPHS SHOWING CONCRETE POUR OF SHELTER SLAB/FOUNDATION, TOWER FOUNDATION AND GUY ANCHORS WITH VIBRATOR IN USE; PHOTOGRAPHS SHOWING EACH ANCHOR ON GUYED TOWERS, BEFORE CONCRETE POUR.
 4. TOWER, ANTENNAS AND MAINLINE: INSPECTION AND PHOTOGRAPHS OF SECTION STACKING; INSPECTION AND PHOTOGRAPHS OF PLATFORM COMPONENT ATTACHMENT POINTS; PHOTOGRAPHS OF TOWER TOP GROUNDING; PHOTOS OF TOWER COAX LINE COLOR CODING AT THE TOP AND AT GROUND LEVEL; INSPECTION AND PHOTOGRAPHS OF OPERATIONAL OF TOWER LIGHTING, AND PLACEMENT OF FAA REGISTRATION SIGN; PHOTOGRAPHS SHOWING ADDITIONAL GROUNDING POINTS FOR TOWERS GREATER THAN 200 FEET.; PHOTOS OF ANTENNA GROUND BAR, EQUIPMENT GROUND BAR, AND MASTER GROUND BAR; PHOTOS OF GPS ANTENNA(S); PHOTOS OF EACH SECTOR OF ANTENNAS; ONE PHOTOGRAPH LOOKING AT THE SECTOR AND ONE FROM BEHIND SHOWING THE PROJECTED COVERAGE AREA; PHOTOS OF COAX WEATHERPROOFING - TOP AND BOTTOM; PHOTOS OF COAX GROUNDING--TOP AND BOTTOM; PHOTOS OF ANTENNA AND MAST GROUNDING; PHOTOS OF COAX CABLE ENTRY INTO SHELTER; PHOTOS OF PLATFORM MECHANICAL CONNECTIONS TO TOWER/MONOPOLE.
 5. ROOF TOPS: PRE-CONSTRUCTION AND POST-CONSTRUCTION VISUAL INSPECTION AND PHOTOGRAPHS OF THE ROOF AND INTERIOR TO DETERMINE AND DOCUMENT CONDITIONS; ROOF TOP CONSTRUCTION INSPECTIONS AS REQUIRED BY THE JURISDICTION; PHOTOGRAPHS OF CABLE TRAY AND/OR ICE BRIDGE; PHOTOGRAPHS OF DOGHOUSE/CABLE EXIT FROM ROOF;
 6. SITE LAYOUT - PHOTOGRAPHS OF THE OVERALL COMPOUND, INCLUDING EQUIPMENT PLATFORM FROM ALL FOUR CORNERS.
 7. FINISHED UTILITIES: CLOSE-UP PHOTOGRAPHS OF THE PPC BREAKER PANEL; CLOSE-UP PHOTOGRAPH OF THE INSIDE OF THE TELCO PANEL AND NIU; CLOSE-UP PHOTOGRAPH OF THE POWER METER AND DISCONNECT; PHOTOS OF POWER AND TELCO ENTRANCE TO COMPANY ENCLOSURE; PHOTOGRAPHS AT METER BOX AND/OR FACILITY DISTRIBUTION PANEL.
 8. REQUIRED MATERIALS CERTIFICATIONS: CONCRETE MIX DESIGNS; MILL CERTIFICATION FOR ALL REINFORCING AND STRUCTURAL STEEL; AND ASPHALT PAVING MIX DESIGN.
 9. ANY AND ALL SUBMITTALS BY THE JURISDICTION OR COMPANY.

SECTION 01 400 - SUBMITTALS & TESTS

PART 1 - GENERAL

- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
 - A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
 - B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HERewith.

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION

- 3.1 WEEKLY REPORTS:
 - A. CONTRACTOR SHALL PROVIDE SPRINT WITH WEEKLY REPORTS SHOWING PROJECT STATUS. THIS STATUS REPORT FORMAT WILL BE PROVIDED TO THE CONTRACTOR BY SPRINT. THE REPORT WILL CONTAIN SITE ID NUMBER, THE MILESTONES FOR EACH SITE, INCLUDING THE BASELINE DATE, ESTIMATED COMPLETION DATE AND ACTUAL COMPLETION DATE.
 - B. REPORT INFORMATION WILL BE TRANSMITTED TO SPRINT VIA ELECTRONIC MEANS AS REQUIRED. THIS INFORMATION WILL PROVIDE A BASIS FOR PROGRESS MONITORING AND PAYMENT.
- 3.2 PROJECT CONFERENCE CALLS:
 - A. SPRINT MAY HOLD WEEKLY PROJECT CONFERENCE CALLS. CONTRACTOR WILL BE REQUIRED TO COMMUNICATE SITE STATUS, MILESTONE COMPLETIONS AND UPCOMING MILESTONE PROJECTIONS, AND ANSWER ANY OTHER SITE STATUS QUESTIONS AS NECESSARY.
- 3.3 PROJECT TRACKING IN SMS:
 - A. CONTRACTOR SHALL PROVIDE SCHEDULE UPDATES AND PROJECTIONS IN THE SMS SYSTEM ON A WEEKLY BASIS.
- 3.4 ADDITIONAL REPORTING:
 - A. ADDITIONAL OR ALTERNATE REPORTING REQUIREMENTS MAY BE ADDED TO THE REPORT AS DETERMINED TO BE REASONABLY NECESSARY BY COMPANY.
- 3.5 PROJECT PHOTOGRAPHS:
 - A. FILE DIGITAL PHOTOGRAPHS OF COMPLETED SITE IN JPEG FORMAT IN THE SMS PHOTO LIBRARY FOR THE RESPECTIVE SITE. PHOTOGRAPHS SHALL BE CLEARLY LABELED WITH SITE NUMBER, NAME AND DESCRIPTION, AND SHALL INCLUDE AT A MINIMUM THE FOLLOWING AS APPLICABLE:
 1. SHELTER AND TOWER OVERVIEW.
 2. TOWER FOUNDATION(S) - FORMS AND STEEL BEFORE POUR (EACH ANCHOR ON GUYED TOWERS).
 3. TOWER FOUNDATION(S) POUR WITH VIBRATOR IN USE (EACH ANCHOR ON GUYED TOWERS).
 4. TOWER STEEL AS BEING INSTALLED INTO HOLE (SHOW ANCHOR STEEL ON GUYED TOWERS).
 5. PHOTOS OF TOWER SECTION STACKING.
 6. CONCRETE TESTING / SAMPLES.
 7. PLACING OF ANCHOR BOLTS IN TOWER FOUNDATION.
 8. BUILDING/WATER TANK FROM ROAD FOR TENANT IMPROVEMENTS OR COMMENTS.
 9. SHELTER FOUNDATION--FORMS AND STEEL BEFORE POURING.
 10. SHELTER FOUNDATION POUR WITH VIBRATOR IN USE.
 11. COAX CABLE ENTRY INTO SHELTER.
 12. PLATFORM MECHANICAL CONNECTIONS TO TOWER/MONOPOLE.
 13. ROOFTOP PRE AND POST CONSTRUCTION PHOTOS TO INCLUDE PENETRATIONS AND INTERIOR CEILING.
 14. PHOTOS OF TOWER TOP COAX LINE COLOR CODING AND COLOR CODING AT GROUND LEVEL.
 15. PHOTOS OF ALL APPROPRIATE COMPANY OR REGULATORY SIGNAGE.
 16. PHOTOS OF EQUIPMENT BOLT DOWN INSIDE SHELTER.
 17. POWER AND TELCO ENTRANCE TO COMPANY ENCLOSURE AND POWER AND TELCO SUPPLY LOCATIONS INCLUDING METER/DISCONNECT.
 18. ELECTRICAL TRENCH(S) WITH ELECTRICAL / CONDUIT BEFORE BACKFILL.
 19. ELECTRICAL TRENCH(S) WITH FOIL-BACKED TAPE BEFORE FURTHER BACKFILL.
 20. TELCO TRENCH WITH TELEPHONE / CONDUIT BEFORE BACKFILL.
 21. TELCO TRENCH WITH FOIL-BACKED TAPE BEFORE FURTHER BACKFILL.
 22. SHELTER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADII).
 23. TOWER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADII).

24. FENCE GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADII).
 25. ALL BTS GROUND CONNECTIONS.
 26. ALL GROUND TEST WELLS.
 27. ANTENNA GROUND BAR AND EQUIPMENT GROUND BAR.
 28. ADDITIONAL GROUNDING POINTS ON TOWERS ABOVE 200'.
 29. HVAC UNITS INCLUDING CONDENSERS ON SPLIT SYSTEMS.
 30. GPS ANTENNAS.
 31. CABLE TRAY AND/OR WAVEGUIDE BRIDGE.
 32. DOGHOUSE/CABLE EXIT FROM ROOF.
 33. EACH SECTOR OF ANTENNAS; ONE PHOTOGRAPH LOOKING AT THE SECTOR AND ONE FROM BEHIND SHOWING THE PROJECTED COVERAGE AREA.
 34. MASTER BUS BAR.
 35. TELCO BOARD AND NIU.
 36. ELECTRICAL DISTRIBUTION WALL.
 37. CABLE ENTRY WITH SURGE SUPPRESSION.
 38. ENTRANCE TO EQUIPMENT ROOM.
 39. COAX WEATHERPROOFING--TOP AND BOTTOM OF TOWER.
 40. COAX GROUNDING --TOP AND BOTTOM OF TOWER.
 41. ANTENNA AND MAST GROUNDING.
 42. LANDSCAPING - WHERE APPLICABLE.
- 3.6 FINAL PROJECT ACCEPTANCE: COMPLETE ALL REQUIRED REPORTING TASKS PER CONTRACT, CONTRACT DOCUMENTS OR THE SPRINT INTEGRATED CONSTRUCTION STANDARDS FOR WIRELESS SITES AND UPLOAD INTO SITERRA.

PLANS PREPARED FOR:




PLANS PREPARED BY:



PROJECT MANAGER:



ENGINEERING LICENSE:



DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:	DESCRIPTION	DATE	BY	REV
ISSUED FOR PERMIT		07/18/18	ETC	0

SITE NAME:

BOOTH HILL

SITE NUMBER:

CT03XC366

SITE ADDRESS:


14 OXFORD DRIVE
SHELTON, CT 06484

SHEET DESCRIPTION:


SPRINT SPECIFICATIONS

SHEET NUMBER:

SP-3




INSTALL (2) 1.689" HYBRID CABLES FROM EXISTING SPRINT FIBER JUNCTION BOX TO PROPOSED RRH UNIT TO BE ROUTED WITH EXISTING (3) HYBRID CABLES (SEE SHEET A-5 DETAIL 2)



INFORMATION CONTAINED WITHIN DRAWINGS ARE BASED ON PROVIDED INFORMATION AND ARE NOT THE RESULT OF A FIELD SURVEY.


OVERALL SITE PLAN

SCALE: AS NOTED 1



INSTALL (3) NEW RECTIFIERS AND EQUIPMENT IN EXISTING CABINET INCLUDING BUT NOT LIMITED TO BASE BAND UNIT, CELL SITE ROUTER, SURGE ARRESTERS AND CONNECT POWER AND FIBER UNIT INSIDE EXISTING N.V. MMBS (SEE SHEET A-5 DETAIL 3)

INSTALL (2) 1.689" HYBRID CABLES FROM EXISTING SPRINT FIBER JUNCTION BOX TO PROPOSED RRH UNIT TO BE ROUTED WITH EXISTING (3) HYBRID CABLES (SEE SHEET A-5 DETAIL 2)



SPRINT EQUIPMENT PLAN

SCALE: AS NOTED 2

PLANS PREPARED FOR:

PLANS PREPARED BY:

FROM ZERO TO INFINIGY
the solutions are endless

1033 Watervliet Shaker Rd | Albany, NY 12205
Phone: 518-690-0790 | Fax: 518-690-0793
www.infinigy.com
JOB NUMBER 526-104

PROJECT MANAGER:

32 CLINTON ST.
SARATOGA SPRINGS, NY 12866
OFFICER, (518) 306-3740

ENGINEERING LICENSE:

DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:	DESCRIPTION	DATE	BY	REV.
ISSUED FOR PERMIT		07/18/18	ETC	0

SITE NAME:

BOOTH HILL

SITE NUMBER:

CT03XC366

SITE ADDRESS:

14 OXFORD DRIVE
SHELTON, CT 06484


SHEET DESCRIPTION:

SITE PLAN

SHEET NUMBER:

A-1

NOTE:
SEE DETAIL 2 ON A-3
FOR ANTENNA LAYOUT



NOTE:

- ANTENNA AND RRH SUPPORT EVALUATION COMPLETED BY INFINIGY. FOR ADDITIONAL INFORMATION SEE REPORT TITLED: "SPRINT DO MACRO PROJECT MOUNT ANALYSIS", DATED: "JUNE 2 2018". ACCORDING TO THE RESULTS OF REVIEW, THE ANTENNA AND RRH SUPPORTS ARE SUFFICIENT TO SUPPORT THE PROPOSED LOADING.

TOWER ELEVATION

NO SCALE 1

SITE LOADING CHART										
SECTOR	EXISTING/PROPOSED	ANTENNA MODEL #	VENDOR	AZIMUTH	QTY.	REMAIN/REMOVED	RRH (QTY/MODEL)	CABLE	CABLE LENGTH	RAD CENTER
ALPHA	PROPOSED	AAHC	NOKIA	0°	1	-	(2) 800 MHZ 2X50W RRH (1) 1900 MHZ 4X45 RRH	SEE SHEET A-5 DETAIL 1	±155' AGL	
	EXISTING	APXVSP18-C-A20	RFS	0°	1	REMOVE		EXISTING HYBRID		
	PROPOSED	NNVV-65B-R4	COMMSCOPE	0°	1	-		EXISTING HYBRID		
BETA	PROPOSED	AAHC	NOKIA	140°	1	-	(2) 800 MHZ 2X50W RRH (1) 1900 MHZ 4X45 RRH	SEE SHEET A-5 DETAIL 1	±235'	±155' AGL
	EXISTING	APXVSP18-C-A20	RFS	140°	1	REMOVE		EXISTING HYBRID		
	PROPOSED	NNVV-65B-R4	COMMSCOPE	140°	1	-		EXISTING HYBRID		
GAMMA	PROPOSED	AAHC	NOKIA	220°	1	-	(2) 800 MHZ 2X50W RRH (1) 1900 MHZ 4X45 RRH	SEE SHEET A-5 DETAIL 1	±155' AGL	
	EXISTING	APXVSP18-C-A20	RFS	220°	1	REMOVE		EXISTING HYBRID		
	PROPOSED	NNVV-65B-R4	COMMSCOPE	220°	1	-		EXISTING HYBRID		

PROJECT SCOPE:
INSTALL: (6) PANEL ANTENNAS AND (3) RRH'S

* PROPOSED CABLE LENGTH WAS DETERMINED USING THE SUM OF THE RAD CENTER OF ANTENNAS, AND DISTANCE FROM EXISTING EQUIPMENT AREA TO TOWER BASE WITH AN ADDITIONAL 20' BUFFER. LENGTH TO BE VERIFIED IN FIELD PRIOR TO ORDERING MATERIALS.

SITE LOADING CHART

NO SCALE 2

DETAIL NOT USED

NO SCALE 3



PLANS PREPARED BY:
INFINIGY
FROM ZERO TO INFINIGY
the solutions are endless
1033 Watervliet Shaker Rd | Albany, NY 12205
Phone: 518-690-0790 | Fax: 518-690-0793
www.infinigy.com
JOB NUMBER: 526-104

PROJECT MANAGER:
AIRSMITH DEVELOPMENT
32 CLINTON ST.
SARATOGA SPRINGS, NY 12866
OFFICER: (518) 306-3740



DRAWING NOTICE:
THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:	DESCRIPTION	DATE	BY	REV.


SITE NAME:
BOOTH HILL

SITE NUMBER:
CT03XC366

SITE ADDRESS:
**14 OXFORD DRIVE
SHELTON, CT 06484**

SHEET DESCRIPTION:
TOWER ELEVATION


SHEET NUMBER:
A-2



EXISTING ANTENNA LAYOUT

NO SCALE 1


NOTE:
JUMPERS FROM 2.5 RRH TO THE 2.5 ANTENNA CANNOT EXCEED 15 FEET



FINAL ANTENNA & RRH LAYOUT

NO SCALE 2

THE CONFIGURATION PLANS ARE BASED ON PROVIDED INFORMATION AND ARE FOR CONCEPTUAL PURPOSES ONLY. CONTRACTOR TO VERIFY FIELD CONDITIONS PRIOR TO CONSTRUCTION.




TYPICAL DUAL BAND ANTENNA & RRH MOUNTING DETAILS

NO SCALE 3

NOTE:
CONTRACTOR TO POSITION RRH ON MOUNT BEHIND ANTENNA SUCH THAT THE RRH DOES NOT INTERFERE WITH THE EXISTING PLATFORM/T-ARM MOUNTING HARDWARE.

NOTE:
THE DIAGRAM IS FOR CONCEPTUAL PURPOSES ONLY. CONTRACTOR IS TO REFER TO PASSING STRUCTURAL ANALYSIS FOR ANTENNA AND RRH MOUNTING DETAILS.

- NOTES:
1. CUT DC CONDUCTORS TO LENGTH.
 2. COIL FIBER CABLE AND SECURE AT SIDE OF RRH.
 3. DO NO EXCEED BEND RADIUS.



TYPICAL MIMO ANTENNA & RRH MOUNTING DETAILS

NO SCALE 4

NOTE:
CONTRACTOR TO POSITION RRH ON MOUNT BEHIND ANTENNA SUCH THAT THE RRH DOES NOT INTERFERE WITH THE EXISTING PLATFORM/T-ARM MOUNTING HARDWARE.

NOTE:
THE DIAGRAM IS FOR CONCEPTUAL PURPOSES ONLY. CONTRACTOR IS TO REFER TO PASSING STRUCTURAL ANALYSIS FOR ANTENNA AND RRH MOUNTING DETAILS.

- NOTES:
1. CUT DC CONDUCTORS TO LENGTH.
 2. COIL FIBER CABLE AND SECURE AT SIDE OF RRH.
 3. DO NO EXCEED BEND RADIUS.

PLANS PREPARED FOR:

PLANS PREPARED BY:

FROM ZERO TO INFINIGY
the solutions are endless

1033 Watervliet Shaker Rd | Albany, NY 12205
Phone: 518-690-0790 | Fax: 518-690-0793
www.infinigy.com
JOB NUMBER: 526-104

PROJECT MANAGER:

32 CLINTON ST.
SARATOGA SPRINGS, NY 12866
OFFICE: (518) 306-3740

ENGINEERING LICENSE:

DRAWING NOTICE:
THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV.
ISSUED FOR PERMIT	07/16/18	ETC	0

SITE NAME:
BOOTH HILL

SITE NUMBER:
CT03XC366

SITE ADDRESS:
14 OXFORD DRIVE
SHELTON, CT 06484

SHEET DESCRIPTION:
ANTENNA LAYOUT & MOUNTING DETAILS

SHEET NUMBER:
A-3

DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR PERMIT	07/18/18	ETC	0

SITE NAME:

BOOTH HILL

SITE NUMBER:

CT03XC366

SITE ADDRESS:

**14 OXFORD DRIVE
SHELTON, CT 06484**


SHEET DESCRIPTION:

**EQUIPMENT &
MOUNTING DETAILS**

SHEET NUMBER:

A-4

RRH: ALCATEL LUCENT 1900 MHz
COLOR: LIGHT GREY
WEIGHT: 70 LBS.
(INCLUDING OPTIONAL SOLAR SHIELD)



DUAL BAND ANTENNA DETAIL



NO SCALE 1

EXISTING 1900 MHz RRH

NO SCALE 2


ANTENNA COMMSCOPE: NNVV-65B-R4

RADOME MATERIAL: FIBER GLASS
RADOME COLOR: LIGHT GREY
DIMENSIONS, HxWxD.In(mim): 72"x19.6"x7.8" (1828x498x197mm)
WEIGHT: 77.4 lbs
CONNECTORS: (8) 4.3-10 FEMALE
(2) AISG CONNECTORS



ANTENNA NOPIKA AAHC

RADOME MATERIAL: FIBERGLASS
RADOME COLOR: LIGHT GREY
DIMENSIONS, HxWxD.In(mim): 25.6"x19.7"x9.9" (651x501x245mm)
WEIGHT: 99.2 lbs
CONNECTORS: (2) 7/16" DIN FEMALE
(8) 4.1/9.5 DIN FEMALE




2.5 ANTENNA DETAIL

NO SCALE 3

RRH: ALCATEL LUCENT RRH 800 MHz 2x50W
COLOR: LIGHT GREY
WEIGHT: 53 LBS.

NOTES
COMPLY WITH MANUFACTURERS INSTRUCTIONS TO ENSURE THAT ALL RRH'S RECEIVE ELECTRICAL POWER WITHIN 24 HOURS OF BEING REMOVED FROM THE MANUFACTURER'S PACKAGING. DO NOT OPEN RRH PACKAGES IN THE RAIN.



800 MHz RRH

NO SCALE 4





RFS HYBRIFLEX RISER CABLE SCHEDULE

Fiber Only (Existing DC Power)	Hybrid cable MN: HB058-M12-050F 12x multi-mode fiber pairs, Top: Outdoor protected connectors, Bottom: LC Connectors, 5/8 cable, 50 ft	50 ft	
	MN: HB058-M12-075F	75 ft	
	MN: HB058-M12-100F	100 ft	
	MN: HB058-M12-125F	125 ft	
	MN: HB058-M12-150F	150 ft	
	MN: HB058-M12-175F	175 ft	
8 AWG Power	Hybrid cable MN: HB114-08U3M12-050F 3x 8 AWG power pairs, 12x multi-mode fiber pairs, Outdoor rated connectors & LC Connectors, 1 1/4 cable, 50 ft	50 ft	
	MN: HB114-08U3M12-075F	75 ft	
	MN: HB114-08U3M12-100F	100 ft	
	MN: HB114-08U3M12-125F	125 ft	
	MN: HB114-08U3M12-150F	150 ft	
	MN: HB114-08U3M12-175F	175 ft	
6 AWG Power	Hybrid cable MN: HB114-13U3M12-25F 3x 6 AWG power pair, 12x multi-mode fiber pairs, Outdoor rated connectors & LC Connectors, 1 1/4 cable, 275 ft	225 ft	
	MN: HB114-13U3M12-250F	250 ft	
	MN: HB114-13U3M12-275F	275 ft	
	MN: HB114-13U3M12-300F	300 ft	
	4 AWG Power	Hybrid cable MN: HB114-21U3M12-325F 3x 4 AWG power pair, 12x multi-mode fiber pairs, Outdoor rated connectors & LC Connectors, 1 1/4 cable, 375 ft	325 ft
		MN: HB114-21U3M12-375F	375 ft

RFS HYBRIFLEX JUMPER CABLE SCHEDULE

Fiber Only	Hybrid Jumper cable MN: HBF012-M3-SF1 5 ft, 3x multi-mode fiber pairs, Outdoor & LC connectors, 1/2 cable	5 ft
	MN: HBF012-M3-10F1	10 ft
	MN: HBF012-M3-15F1	15 ft
	MN: HBF012-M3-20F1	20 ft
	MN: HBF012-M3-25F1	25 ft
	MN: HBF012-M3-30F1	30 ft
8 AWG Power	Hybrid Jumper cable MN: HBF058-08U1M3-SF1 5 ft, 1x 8 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 5/8 cable	5 ft
	MN: HBF058-08U1M3-10F1	10 ft
	MN: HBF058-08U1M3-15F1	15 ft
	MN: HBF058-08U1M3-20F1	20 ft
	MN: HBF058-08U1M3-25F1	25 ft
	MN: HBF058-08U1M3-30F1	30 ft
6 AWG Power	Hybrid Jumper cable MN: HBF058-13U1M3-SF1 5 ft, 1x 6 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 5/8 cable	5 ft
	MN: HBF058-13U1M3-10F1	10 ft
	MN: HBF058-13U1M3-15F1	15 ft
	MN: HBF058-13U1M3-20F1	20 ft
	MN: HBF058-13U1M3-25F1	25 ft
	MN: HBF058-13U1M3-30F1	30 ft
4 AWG Power	Hybrid Jumper cable MN: HBF078-21U1M3-SF1 5 ft, 1x 4 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 7/8 cable	5 ft
	MN: HBF078-21U1M3-10F1	10 ft
	MN: HBF078-21U1M3-15F1	15 ft
	MN: HBF078-21U1M3-20F1	20 ft
	MN: HBF078-21U1M3-25F1	25 ft
	MN: HBF078-21U1M3-30F1	30 ft


NOTE:
SPRINT CM TO CONFIRM HYBRID OR FIBER RISER CABLE AND HYBRID OR FIBER JUMPER CABLE MODEL NUMBERS IF HYBRID CABLES ARE REQUIRED BEFORE PREPARING BOM.



FIBER JUNCTION BOX & PENETRATION

NO SCALE

2



FRONT VIEW

NEW EQUIPMENT IN EXISTING CABINET

NO SCALE

3

800/1900/2500 CABLE CROSS SECTION DATA

NO SCALE

1

PLANS PREPARED FOR:



PLANS PREPARED BY:

INFINIGY
FROM ZERO TO INFINIGY
the solutions are endless
1033 Watervliet Shaker Rd | Albany, NY 12205
Phone: 518-690-0790 | Fax: 518-690-0793
www.infinigy.com
JOB NUMBER 526-104

PROJECT MANAGER:

AIRSMITH DEVELOPMENT
32 CLINTON ST.
SARATOGA SPRINGS, NY 12866
OFFICER, (518) 306-3740

ENGINEERING LICENSE:

DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:	DESCRIPTION	DATE	BY	REV.
ISSUED FOR PERMIT		07/18/18	ETC	0

SITE NAME:
BOOTH HILL

SITE NUMBER:
CT03XC366


SITE ADDRESS:
**14 OXFORD DRIVE
SHELTON, CT 06484**

SHEET DESCRIPTION:
CIVIL DETAILS

SHEET NUMBER:
A-5

* PROPOSED CABLE LENGTH WAS DETERMINED USING THE SUM OF THE RAD CENTER OF ANTENNAS, AND DISTANCE FROM EXISTING EQUIPMENT AREA TO TOWER BASE WITH AN ADDITIONAL 20' BUFFER. LENGTH TO BE VERIFIED IN FIELD PRIOR TO ORDERING MATERIALS.

ALU 21-MIMO NNVV-65B-R4 wo Filters



Not to Scale

PLUMBING DIAGRAM

NO SCALE

1

PLANS PREPARED FOR:



PLANS PREPARED BY:



FROM ZERO TO INFINIGY
the solutions are endless

1033 Watervliet Shaker Rd | Albany, NY 12205
Phone: 518-690-0790 | Fax: 518-690-0793
www.infinigy.com
JOB NUMBER 526-104

PROJECT MANAGER:



32 CLINTON ST.
SARATOGA SPRINGS, NY 12866
OFFICER, (518) 306-3740

ENGINEERING LICENSE:



DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV.

ISSUED FOR PERMIT 07/18/18 ETC 0

SITE NAME:

BOOTH HILL

SITE NUMBER:

CT03XC366

SITE ADDRESS:


14 OXFORD DRIVE
SHELTON, CT 06484

SHEET DESCRIPTION:

PLUMBING DIAGRAM

SHEET NUMBER:

A-6









RRH TO DISTRIBUTION BOX POWER CONNECTIVITY

NO SCALE

1

LEGEND:


-  EXISTING GROUND RING
-  CADWELD CONNECTION (EXOTHERMIC WELD)
-  MECHANICAL CONNECTION
-  GROUND ROD
-  CABLE GROUND KIT



TYPICAL ANTENNA GROUNDING PLAN

NO SCALE

2



NOTE: DEPICTION IS FOR CONCEPTUAL PURPOSES ONLY. CONTRACTOR IS TO FIELD VERIFY PRIOR TO CONSTRUCTION

TYPICAL EQUIPMENT GROUNDING PLAN (ELEVATION)

NO SCALE

3

PLANS PREPARED FOR:



PLANS PREPARED BY:

INFINIGY
FROM ZERO TO INFINIGY
the solutions are endless
1033 Watervliet Shaker Rd | Albany, NY 12205
Phone: 518-690-0790 | Fax: 518-690-0793
www.infinigy.com
JOB NUMBER 526-104

PROJECT MANAGER:

AIRSMITH DEVELOPMENT
32 CLINTON ST.
SARATOGA SPRINGS, NY 12866
OFFICER (518) 308-3740

ENGINEERING LICENSE:

DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:	DESCRIPTION	DATE	BY	REV.
ISSUED FOR PERMIT		07/18/18	ETC	0

SITE NAME:

BOOTH HILL

SITE NUMBER:

CT03XC366

SITE ADDRESS:

14 OXFORD DRIVE
SHELTON, CT 06484


SHEET DESCRIPTION:

ELECTRICAL &
GROUNDING PLAN

SHEET NUMBER:

E-1

NOTES
 CG SHALL REFERENCE ALL SPECS FOR "CONNECTING THE POWER SUPPLY" OF THE NEW INSTALLATION DOCUMENTS, FOR ALL CONNECTION SPECIFICATIONS.



CIRCUIT SCHEDULE			
NO	FROM	TO	CONFIGURATION
①	UTILITY SOURCE	METER/DISCONNECT	EXISTING
②	METER/DISCONNECT	TRANSFER & LOAD CENTER	EXISTING
③	TRANSFER & LOAD CENTER	GENERATOR RECEPTACLE	EXISTING
④	TRANSFER & LOAD CENTER	EXISTING SPRINT BBU CABINET	EXISTING
⑤	TRANSFER & LOAD CENTER	EXISTING SPRINT MMBS CABINET	EXISTING

PLANS PREPARED FOR:

PLANS PREPARED BY:

FROM ZERO TO INFINIGY
 the solutions are endless

1033 Watervliet Shaker Rd | Albany, NY 12209
 Phone: 518-690-0790 | Fax: 518-690-0793
 www.infinigy.com
 JOB NUMBER 526-104

PROJECT MANAGER:

32 CLINTON ST.
 SARATOGA SPRINGS, NY 12866
 OFFICE# (518) 308-3740

ENGINEERING LICENSE:

DRAWING NOTICE:
 THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV.

ISSUED FOR PERMIT: 07/18/18 ETC 0

SITE NAME:
BOOTH HILL

SITE NUMBER:
CT03XC366


SITE ADDRESS:
**14 OXFORD DRIVE
 SHELTON, CT 06484**

SHEET DESCRIPTION:
**ELECTRICAL &
 GROUNDING PLAN**

SHEET NUMBER:
E-2

ELECTRICAL ONE-LINE DIAGRAM


NO SCALE 1



NOTES
 1. APPLY NO-OX TO LUG AND BAR CONTACT SURFACE. DO NOT COAT INLINE LUG.
 2. IF STOLEN GROUND BARS ARE ENCOUNTERED, CONTACT SPRINT CM FOR REPLACEMENT THREADED ROD KIT.

INSTALLATION OF GROUNDING CONDUCTOR TO GROUNDING BAR


NO SCALE 2



"DO NOT DISCONNECT" TAG ON ALL GROUNDING BAR INTERCONNECTS AND EQUALIZERS

TWO HOLE LUG

NO SCALE 3



NOTE: USE #6 AWG BARE SOLID TINNED COPPER UNLESS NOTED OTHERWISE

- LEGEND:**
- G EXISTING GROUND RING
 - CADWELD CONNECTION (EXOTHERMIC WELD)
 - ▲ MECHANICAL CONNECTION
 - ⊗ GROUND ROD
 - CABLE GROUND KIT

GROUNDING RISER DIAGRAM

NO SCALE 4