



September 19 2014

Melanie A. Bachman  
Executive Director  
Connecticut Siting Council  
10 Franklin Street  
New Britain, CT 06051

Regarding : Notice of Exempt Modification – Addition of 3 radio heads previously approved

Property Address: 225 Grist Mill Road Simsbury, CT (the “Property”)

Applicant: New Cingular Wireless PC, LLC (“AT&T”)

Dear Ms. Bachman:

AT&T currently maintains a wireless telecommunications facility on an existing 150 foot Monopole (“tower”) location on the Property. AT&T’s facility consist of nine (9) wireless telecommunications antenna at 151 feet. The tower is owned by SBA Towers, Inc.. The Council approved the previous application on August 10th 2012 reference number EM-CING-128-120720. This application (attached) granted AT&T the use of 6 radio heads at this location. The approval expired one year from the issue date. During that time AT&T made the changes to the site per the approval but only installed three(3) of the six (6) radio heads that they received approval. AT&T would now like to install the additional three(3) radio heads that were originally approved under EM-CING-128120720.

Please accept this application as notification pursuant to R.C.S.A. § 16-50j-73, for construction that constitutes an exempt modification pursuant to R.C.S.A. § 16-50j-72 (b)(2). In accordance with R.C.S.A. § 16-50j-73, a copy of this letter is being sent to the Mary A. Glassman First Selectman Town of Simsbury, Michael Paine Chairman of the Planning Commission, Town of Simsbury. A copy of this letter is also being sent to SBA Towers, Inc., the owner of the structure that AT&T is located.

The planned modifications to AT&T’s facility fall squarely within those activities explicitly provided for in R.C.S.A. § 16-50j-72 (b)(2).

1. The planned modifications will not result in an increase in the height of the existing structure. AT&T’s additional, previously approved 3 radio heads will be installed at 151 foot level of the 150 foot monopole.
2. The proposed modifications will not involve any changes to ground-mounted equipment and, therefore will not require an extension of the site boundary
3. The proposed modification will not increase the noise level at the facility by six decibel or more, or to levels that exceed state and local criteria.
4. The operation of the modified facility will not increase radio frequency (RF) emissions at the facility to a level at or above the Federal Communications Commission (FCC) safety standard. An RF emissions calculation (attached) for AT&T’s modified facility was provided in the application which led to the August 10th 2012 Decision.

5. The proposed modifications will not cause a change or alteration in the physical or environmental characteristics of the site.
6. The tower and its foundation can support AT&T's proposed modifications (please see attached structural analysis completed by FDH Engineering on July 11th 2012


For the foregoing reasons AT&T respectfully request that the proposed addition of 3 radio heads previously approved be allowed within the exempt modifications under R.C.S.A. § 16-50j-72 (b)(2).

Sincerely,



David P. Cooper  
Director of Site Acquisition  
Empire Telecom

CC: Mary A. Glassman First Selectman Town of Simsbury, Michael Paine Chairman of the Planning Commission, Town of Simsbury., SBA Towers, Inc.  
CT1151 file



STATE OF CONNECTICUT  
CONNECTICUT SITING COUNCIL

Ten Franklin Square, New Britain, CT 06051  
Phone: (860) 827-2935 Fax: (860) 827-2950  
E-Mail: [siting.council@ct.gov](mailto:siting.council@ct.gov)  
[www.ct.gov/csc](http://www.ct.gov/csc)

August 10, 2012

Peter LaMontagne  
New Cingular Wireless PCS, LLC  
95 Ryan Drive, Suite #1  
Raynham, MA 02767

RE: **EM-CING-128-120720** – New Cingular Wireless PCS, LLC notice of intent to modify an existing telecommunications facility located at 225 Grist Mill Road, Simsbury, Connecticut.

Dear Mr. LaMontagne:

The Connecticut Siting Council (Council) hereby acknowledges your notice to modify this existing telecommunications facility, pursuant to Section 16-50j-73 of the Regulations of Connecticut State Agencies with the following conditions:


- The proposed coax and auxiliary equipment be installed in accordance with the recommendations made in the Structural Analysis Report prepared by FDH Engineering dated July 11, 2012 and stamped by Christopher Murphy; and
- Following the installation of the proposed equipment, AT&T shall provide documentation certifying that the installation complied with the engineer's recommendation.
- Any deviation from the proposed modification as specified in this notice and supporting materials with Council shall render this acknowledgement invalid;
- Any material changes to this modification as proposed shall require the filing of a new notice with the Council;
- Not less than 45 days after completion of construction, the Council shall be notified in writing that construction has been completed;
- The validity of this action shall expire one year from the date of this letter; and
- The applicant may file a request for an extension of time beyond the one year deadline provided that such request is submitted to the Council not less than 60 days prior to the expiration;

The proposed modifications including the placement of all necessary equipment and shelters within the tower compound are to be implemented as specified here and in your notice dated July 20, 2012. The modifications are in compliance with the exception criteria in Section 16-50j-72 (b) of the Regulations of Connecticut State Agencies as changes to an existing facility site that would not increase tower height, extend the boundaries of the tower site, increase noise levels at the tower site boundary by six decibels, and increase the total radio frequencies electromagnetic radiation power density measured at the tower site boundary to or above the standard adopted by the State Department of Environmental Protection pursuant to General Statutes § 22a-162. This facility has also been carefully modeled to ensure that radio frequency emissions are

conservatively below State and federal standards applicable to the frequencies now used on this tower.

This decision is under the exclusive jurisdiction of the Council. Please be advised that the validity of this action shall expire one year from the date of this letter. Any additional change to this facility will require explicit notice to this agency pursuant to Regulations of Connecticut State Agencies Section 16-50j-73. Such notice shall include all relevant information regarding the proposed change with cumulative worst-case modeling of radio frequency exposure at the closest point of uncontrolled access to the tower base, consistent with Federal Communications Commission, Office of Engineering and Technology, Bulletin 65. Thank you for your attention and cooperation.

Very truly yours,



Linda Roberts  
Executive Director

LR/CDM/cm

c: The Honorable Mary A. Glassman, First Selectman, Town of Simsbury  
Michael Paine, Chairman of the Planning Commission, Town of Simsbury

## Martin, David C.

---

**From:** Dan Goulet <Dan.Goulet@csquaredsystems.com>  
**Sent:** Sunday, July 29, 2012 8:00 AM  
**To:** Martin, David C.  
**Cc:** Keith Vellante  
**Subject:** AT&T Simsbury MPE Submission  
**Attachments:** CT1151\_MPEReport\_20120727.pdf

Dave,


It has come to our attention that the MPE Report for 225 Grist Mill Rd in Simsbury dated 3/27/2012 was submitted to your office prematurely. We just received a revised structural analysis for this tower which shows a centerline height of 151'.

We believe that your team, in checking our reported results, took the reported power density values and used them to derive the %MPE values shown in the CSC database, a logical step. Unfortunately in this instance, the engineer preparing the report at our end had applied the off-beam loss factor of 10 to the “%MPE” value rather than including the  $10^{-1}$  in the **power density equation**, as is normally done. The end result was that when your team applied the factor of 10 to the power density values, the resultant %MPE was overstated by a factor of 10.

Please accept the enclosed updated MPE Report with the corrected centerlines and power density values which already account for the factor of 10 in the power density values listed and the nominal 10dB off beam pattern loss.

Please feel free to contact me if you have any questions.


Dan Goulet  
C Squared Systems  
65 Dartmouth Drive, A3  
Auburn, NH 03032  
OFC 603 644 2800  
PCS 978 204 4895  
[dan.goulet@csquaredsystems.com](mailto:dan.goulet@csquaredsystems.com)



C Squared Systems, LLC  
65 Dartmouth Drive, Unit A3  
Auburn, NH 03032  
(603) 644-2800  
support@csquaredsystems.com

---

Calculated Radio Frequency Emissions



at&t

CT1151

(Simsbury Power Forest)

225 Grist Mill Rd, Simsbury, CT 06070

(a.k.a. Grist Mill Road)

---

July 27, 2012

## Table of Contents

1. Introduction.....	1
2. FCC Guidelines for Evaluating RF Radiation Exposure Limits.....	1
3. RF Exposure Prediction Methods.....	2
4. Calculation Results.....	3
5. Conclusion.....	4
6. Statement of Certification.....	4
Attachment A: References.....	5
Attachment B: FCC Limits for Maximum Permissible Exposure (MPE).....	6
Attachment C: AT&T Antenna Data Sheets and Electrical Patterns.....	8

## List of Tables

Table 1: Carrier Information.....	3
Table 2: FCC Limits for Maximum Permissible Exposure (MPE).....	6

## List of Figures

Figure 1: Graph of FCC Limits for Maximum Permissible Exposure (MPE).....	7
---	---

## 1. Introduction

The purpose of this report is to investigate compliance with applicable FCC regulations for the proposed modifications to the existing AT&T antenna arrays mounted on the monopole tower located at 225 Grist Mill Rd in Simsbury, CT. The coordinates of the tower are 41-52-0.2 N, 72-48-56.9 W.

AT&T is proposing the following modifications:

- 1) Replace six of nine existing dual-band (850/1900 MHz) panel antennas with six multi-band (700/850/1900/2100 MHz) antennas (two per sector);

## 2. FCC Guidelines for Evaluating RF Radiation Exposure Limits

In 1985, the FCC established rules to regulate radio frequency (RF) exposure from FCC licensed antenna facilities. In 1996, the FCC updated these rules, which were further amended in August 1997 by OET Bulletin 65 Edition 97-01. These new rules include Maximum Permissible Exposure (MPE) limits for transmitters operating between 300 kHz and 100 GHz. The FCC MPE limits are based upon those recommended by the National Council on Radiation Protection and Measurements (NCRP), developed by the Institute of Electrical and Electronics Engineers, Inc., (IEEE) and adopted by the American National Standards Institute (ANSI).

The FCC general population/uncontrolled limits set the maximum exposure to which most people may be subjected. General population/uncontrolled exposures apply in situations in which the general public may be exposed, or in which persons that are exposed as a consequence of their employment may not be fully aware of the potential for exposure or cannot exercise control over their exposure.

Public exposure to radio frequencies is regulated and enforced in units of milliwatts per square centimeter ( $mW/cm^2$ ). The general population exposure limits for the various frequency ranges are defined in the attached "FCC Limits for Maximum Permissible Exposure (MPE)" in Attachment B of this report.

Higher exposure limits are permitted under the occupational/controlled exposure category, but only for persons who are exposed as a consequence of their employment and who have been made fully aware of the potential for exposure, and they must be able to exercise control over their exposure. General population/uncontrolled limits are five times more stringent than the levels that are acceptable for occupational, or radio frequency trained individuals. Attachment B contains excerpts from OET Bulletin 65 and defines the Maximum Exposure Limit.

Finally, it should be noted that the MPE limits adopted by the FCC for both general population/uncontrolled exposure and for occupational/controlled exposure incorporate a substantial margin of safety and have been established to be well below levels generally accepted as having the potential to cause adverse health effects.



### 3. RF Exposure Prediction Methods

The emission field calculation results displayed in the following figures were generated using the following formula as outlined in FCC bulletin OET 65:

$$\text{Power Density} = \left( \frac{1.6^2 \times \text{EIRP}}{4\pi \times R^2} \right) \times \text{Off Beam Loss}$$

Where:

EIRP = Effective Isotropic Radiated Power

R = Radial Distance =  $\sqrt{H^2 + V^2}$

H = Horizontal Distance from antenna in meters

V = Vertical Distance from radiation center of antenna in meters

Ground reflection factor of 1.6

Off Beam Loss is determined by the selected antenna pattern

These calculations assume that the antennas are operating at 100 percent capacity and power, and that all channels are transmitting simultaneously. Obstructions (trees, buildings, etc.) that would normally attenuate the signal are not taken into account. The calculations assume even terrain in the area of study and do not take into account actual terrain elevations which could attenuate the signal. As a result, the predicted signal levels reported below are much higher than the actual signal levels will be from the finished modifications.

#### 4. Calculation Results

Table 1 below outlines the power density information for the site. Because the proposed AT&T antennas are directional in nature, the majority of the RF power is focused out towards the horizon. As a result, there will be less RF power directed below the antennas relative to the horizon, and consequently lower power density levels around the base of the tower. Please refer to Attachment C for the vertical pattern of the proposed AT&T antennas. The calculated results for AT&T in Table 1 include a nominal 10 dB off-beam pattern loss to account for the lower relative gain below the antennas.

Carrier	Antenna Height (Feet)	Operating Frequency (MHz)	Number of Trans.	ERP Per Transmitter (Watts)	Power Density (mw/cm <sup>2</sup> )	Limit	%MPE
AT&T UMTS	150	880	2	565	0.0181	0.5867	3.08%
AT&T UMTS	150	1900	2	1077	0.0344	1.0000	3.44%
AT&T GSM	150	880	1	647	0.0103	0.5867	1.76%
AT&T GSM	150	1900	4	813	0.0520	1.0000	5.20%
AT&T LTE	150	734	1	1615	0.0258	0.4893	5.27%
Verizon cellular	141	869	9	268	0.0436	0.5793	7.53%
Verizon PCS	141	1970	7	177	0.0224	1.0000	2.24%
Verizon AWS	141	2145	1	443	0.0080	1.0000	0.80%
Verizon LTE	141	698	2	627	0.0227	0.4653	4.87%
Pocket	131	2130	3	631	0.0397	1.0000	3.97%
Nextel	111	851	9	100	0.0263	0.5673	4.63%
Sprint	123	1962.5	11	122	0.0319	1.0000	3.19%
Voicestream	Numbers not provided						3.00%
New Engl. Site Mngmt	Numbers not provided						
Town of Simsbury	Numbers not provided						
AT&T UMTS	151	880	2	565	0.0018	0.5867	0.30%
AT&T UMTS	151	1900	2	1077	0.0034	1.0000	0.34%
AT&T LTE	151	734	1	1615	0.0025	0.4893	0.52%
AT&T GSM	151	880	1	647	0.0010	0.5867	0.17%
AT&T GSM	151	1900	4	813	0.0051	1.0000	0.51%
						<b>Total</b>	<b>32.08%</b>

Table 1: Carrier Information<sup>1 2 3</sup>

<sup>1</sup> The existing CSC filing for AT&T should be removed and replaced with the updated AT&T technologies and values provided in Table 1. The power density information for carriers other than AT&T was taken directly from the CSC database dated 7/26/2012. Please note that %MPE values listed are rounded to two decimal points. The total %MPE listed is a summation of each unrounded contribution. Therefore, summing each rounded value may not identically match the total value reflected in the table.

<sup>2</sup> In the case where antenna models are not uniform across all 3 sectors for the same frequency band, the antenna model with the highest gain was used for the calculations to present a worse-case scenario.

<sup>3</sup> Antenna height listed for AT&T is in reference to the B&T Engineering, Inc Structural Analysis dated July 11, 2012.

## 5. Conclusion

The above analysis verifies that emissions from the existing site will be below the maximum power density levels as outlined by the FCC in the OET Bulletin 65 Ed. 97-01. Even when using conservative methods, the cumulative power density from the proposed transmit antennas at the existing facility is well below the limits for the general public. The highest expected percent of Maximum Permissible Exposure at ground level is **32.08% of the FCC limit**.

As noted previously, obstructions (trees, buildings, etc.) that would normally attenuate the signal are not taken into account. As a result, the predicted signal levels are more conservative (higher) than the actual signal levels will be from the finished modifications.

## 6. Statement of Certification

I certify to the best of my knowledge that the statements in this report are true and accurate. The calculations follow guidelines set forth in ANSI/IEEE Std. C95.3, ANSI/IEEE Std. C95.1 and FCC OET Bulletin 65 Edition 97-01.



Daniel L. Goulet  
C Squared Systems, LLC

July 27, 2012

Date

**Attachment A: References**

OET Bulletin 65 - Edition 97-01 - August 1997 Federal Communications Commission Office of Engineering & Technology

ANSI C95.1-1982. American National Standard Safety Levels With Respect to Human Exposure to Radio Frequency Electromagnetic Fields. 300 kHz to 100 GHz. IEEE-SA Standards Board

IEEE Std C95.3-1991 (Reaff 1997). IEEE Recommended Practice for the Measurement of Potentially Hazardous Electromagnetic Fields - RF and Microwave. IEEE-SA Standards Board

**Attachment B: FCC Limits for Maximum Permissible Exposure (MPE)**

**(A) Limits for Occupational/Controlled Exposure<sup>4</sup>**

Frequency Range (MHz)	Electric Field Strength (E) (V/m)	Magnetic Field Strength (E) (A/m)	Power Density (S) (mW/cm <sup>2</sup> )	Averaging Time  E  <sup>2</sup> ,  H  <sup>2</sup> or S (minutes)
0.3-3.0	614	1.63	(100)*	6
3.0-30	1842/f	4.89/f	(900/f <sup>2</sup> )*	6
30-300	61.4	0.163	1.0	6
300-1500	-	-	f/300	6
1500-100,000	-	-	5	6

**(B) Limits for General Population/Uncontrolled Exposure<sup>5</sup>**

Frequency Range (MHz)	Electric Field Strength (E) (V/m)	Magnetic Field Strength (E) (A/m)	Power Density (S) (mW/cm <sup>2</sup> )	Averaging Time  E  <sup>2</sup> ,  H  <sup>2</sup> or S (minutes)
0.3-1.34	614	1.63	(100)*	30
1.34-30	824/f	2.19/f	(180/f <sup>2</sup> )*	30
30-300	27.5	0.073	0.2	30
300-1500	-	-	f/1500	30
1500-100,000	-	-	1.0	30

f = frequency in MHz \* Plane-wave equivalent power density

**Table 2: FCC Limits for Maximum Permissible Exposure (MPE)**

<sup>4</sup> Occupational/controlled limits apply in situations in which persons are exposed as a consequence of their employment provided those persons are fully aware of the potential for exposure and can exercise control over their exposure. Limits for occupational/controlled exposure also apply in situations when an individual is transient through a location where occupational/controlled limits apply provided he or she is made aware of the potential for exposure

<sup>5</sup> General population/uncontrolled exposures apply in situations in which the general public may be exposed, or in which persons that are exposed as a consequence of their employment may not be fully aware of the potential for exposure or cannot exercise control over their exposure








Figure 1: Graph of FCC Limits for Maximum Permissible Exposure (MPE)

**Attachment C: AT&T Antenna Data Sheets and Electrical Patterns**

<p><b>700 MHz:</b></p> <p>Manufacturer: Powerwave            Model #: P65-17-XLH-RR            Frequency Band: 698-806 MHz            Gain: 14.3 dBd            Vertical Beamwidth: 8.4°            Horizontal Beamwidth: 70°            Polarization: Dual Linear ± 45°            Size L x W x D: 96.0" x 12.0" x 6.0"</p>	 <p>A polar plot showing the radiation pattern for a 700 MHz antenna. The plot is circular with concentric dashed lines representing gain levels. The main lobe is centered at 0 degrees and extends to approximately 10 dBd. The horizontal beamwidth is 70 degrees, and the vertical beamwidth is 8.4 degrees. The plot shows a main lobe and several side lobes.</p>
<p><b>850 MHz GSM</b></p> <p>Manufacturer: Powerwave            Model #: P65-17-XLH-RR            Frequency Band: 806-894 MHz            Gain: 15.1 dBd            Vertical Beamwidth: 8.4°            Horizontal Beamwidth: 63°            Polarization: Dual Linear ± 45°            Size L x W x D: 96.0" x 12.0" x 6.0"</p>	 <p>A polar plot showing the radiation pattern for an 850 MHz GSM antenna. The plot is circular with concentric dashed lines representing gain levels. The main lobe is centered at 0 degrees and extends to approximately 10 dBd. The horizontal beamwidth is 63 degrees, and the vertical beamwidth is 8.4 degrees. The plot shows a main lobe and several side lobes.</p>
<p><b>1900 MHz GSM</b></p> <p>Manufacturer: KMW Communications            Model #: AM-X-CD-16-65-00T            Frequency Band: 1850-1900 MHz            Gain: 15.25 dBd            Vertical Beamwidth: 6°            Horizontal Beamwidth: 67°            Polarization: Dual Slant ± 45°            Size L x W x D: 72.0" x 11.8" x 5.9"</p>	 <p>A polar plot showing the radiation pattern for a 1900 MHz GSM antenna. The plot is circular with concentric dashed lines representing gain levels. The main lobe is centered at 0 degrees and extends to approximately 10 dBd. The horizontal beamwidth is 67 degrees, and the vertical beamwidth is 6 degrees. The plot shows a main lobe and several side lobes.</p>


## 850 MHz UMTS

Manufacturer: Kathrein-Scala  
 Model #: 80010121  
 Frequency Band: 824-896 MHz  
 Gain: 11.5 dBd  
 Vertical Beamwidth: 14.5°  
 Horizontal Beamwidth: 86°  
 Polarization: ±45°  
 Size L x W x D: 54.5" x 10.3" x 5.9"



## 1900 MHz UMTS

Manufacturer: Kathrein-Scala  
 Model #: 80010121  
 Frequency Band: 1850-1990 MHz  
 Gain: 14.3 dBd  
 Vertical Beamwidth: 6.6°  
 Horizontal Beamwidth: 85°  
 Polarization: ±45°  
 Size L x W x D: 54.5" x 10.3" x 5.9"







EM-CING-128-120720

New Cingular Wireless  
PCS, LLC  
500 Enterprise Drive  
Rocky Hill, Connecticut 06067

**Peter LaMontagne**  
Real Estate Consultant  
95 Ryan Drive, Suite #1  
Raynham, MA 02767  
Phone: (508)341-7854  
[plamontagne@clinellc.com](mailto:plamontagne@clinellc.com)

July 20, 2012

Honorable Robert Stein, Chairman,  
and Members of the Connecticut Siting Council  
Connecticut Siting Council  
10 Franklin Square  
New Britain, Connecticut 06051

ORIGINAL

RECEIVED  
JUL 20 2012

CONNECTICUT  
SITING COUNCIL

**Re: Notice of Exempt Modification – Existing AT&T Tower Facility at 225 Grist Mill Road, Simsbury, CT 06070**

Dear Chairman Stein and Members of the Council:

New Cingular Wireless PCS, LLC (“AT&T”) intends to modify the existing telecommunications antennas and associated equipment at an existing multicarrier telecommunications tower at 225 Grist Mill Road in Simsbury, Connecticut. AT&T operates under licenses issued by the Federal Communications Commission (“FCC”) to provide cellular and PCS mobile telephone service in Hartford County, which includes the area to be served by AT&T’s proposed installation.

In order to accommodate technological changes, implement Long Term Evolution (“LTE”) capabilities, and enhance system performance in the State of Connecticut, New Cingular Wireless PCS, LLC (“AT&T”) plans to modify the equipment configurations at many of its existing cell sites. LTE is a new high-performance air interface for cellular mobile communications. It is designed to increase the capacity and speed of mobile telephone networks.

Please accept this letter as notification to the Council, pursuant to R.C.S.A. Section 16-50j-73, of construction which constitutes an exempt modification pursuant to R.C.S.A. Section 16-50j-72(b)(2). In compliance with R.C.S.A. Section 16-50j-73, a copy of this letter is being sent to Mary Glassman, First Selectmen for the Town of Simsbury.

Attached is a summary of the planned modifications, including power density calculations, reflecting the change in AT&T’s operations at the facility. Also included is documentation of the structural sufficiency of the tower to accommodate the revised antenna configuration.

### Existing Facility

The Simsbury Facility is located at 225 Grist Mill Road on the south side of Route 167. Site coordinates (NAD83) are N41° 52' 0.2" and W72° 48' 56.9".

The facility is owned by SBA Properties, Inc of 5900 Broken Sound Parkway, N.W, Boca Raton, Florida 33487-2797.

The existing facility consists of a one hundred and fifty foot (150') monopole tower located within a fenced in compound surrounded by a chain link fence. AT&T currently operates wireless communications equipment at the facility.


### Statutory Considerations

The changes to the Simsbury tower facility do not constitute a modification as defined in Connecticut General Statutes ("C.G.S.") Section 16-50i(d) because the general physical characteristics of the facility will not be significantly changed or altered. Rather, the planned changes to the facility fall squarely within those activities explicitly provided for in R.C.S.A. Section 16-50j-72(b)(2) because they will not result in any substantial adverse environmental effect.

1. The height of the overall structure will be unaffected.
2. The proposed changes will not affect the property boundaries. All new construction will take place inside the existing fenced compound.
3. The proposed additions will not increase the noise level at the existing facility by six decibels or more.
4. LTE will utilize additional radio frequencies newly licensed by the FCC for cellular mobile communications. However, the changes will not increase the calculated "worst case" power density for the combined operations at the site to a level at or above the applicable standard for uncontrolled environments as calculated for a mixed frequency site.

For the foregoing reasons, New Cingular Wireless respectfully submits that the proposed changes at the referenced site constitute exempt modifications under R.C.S.A Section §16-50j-72(b)(2).

Respectfully yours,



Peter LaMontagne  
Real Estate Consultant

Enclosures:

Mary Glassman, First Selectmen for the Town of Simsbury



**New Cingular Wireless  
PCS, LLC**  
500 Enterprise Drive  
Rocky Hill, Connecticut 06067

**Peter LaMontagne**  
Real Estate Consultant  
95 Ryan Drive, Suite #1  
Raynham, MA 02767  
Phone: (508)341-7854  
[plamontagne@clinellc.com](mailto:plamontagne@clinellc.com)

July , 2012

Mary A. Glassman  
First Selectmen, Simsbury  
993 Hopmeadow Street  
Simsbury, CT0600

**Re: Notice of Exempt Modification – Existing Telecommunications Facility at 225 Grist Mill Road, Simsbury, CT 06070**

Dear Mary Glassman, First Selectmen of Simsbury,

New Cingular Wireless PCS, LLC (“AT&T”) intends to replace telecommunications antennas and associated equipment at an existing telecommunications tower, owned by SBA Properties, Inc and situated at 225 Grist Mill Road in Simsbury, Connecticut.

A Notice of Exempt Modification has been filed with the Connecticut Siting Council as required by Regulations of Connecticut State Agencies (“R.C.S.A.”) Section 16-50j-73. Please accept this letter as notification to the Town of Simsbury under Section 16-50j-73 of construction which constitutes an exempt modification pursuant to R.C.S.A. Section 16-50j-72(b)(2).

The attached letter fully sets forth the AT&T proposal. However, if you have any questions or require any further information on the plans for the site or the Siting Council’s procedures, please contact Peter LaMontagne at (508) 341-7854 or Linda Roberts, Executive Director of the Connecticut Siting Council, at (860) 827-2935.

Sincerely,

Peter LaMontagne  
Real Estate Consultant

Enclosure  
Honorable Robert Stein, Chairmen of the Connecticut Siting Council

**CT1151 – 225 Gristmill Road, Sismbury, CT**

**Aerial Location Map**







FDH Engineering, Inc., 6521 Meridien Drive Raleigh, NC 27616, Ph. 919.755.1012

**Structural Analysis for  
SBA Network Services, Inc.**

**150' Monopole Tower**

**SBA Site Name: Simsbury 2  
SBA Site ID: CT10022-A  
AT&T Site ID: CT1151  
AT&T Site Name: Simsbury Central**

**FDH Project Number 12-06947E S1**

**Analysis Results**

Tower Components	83.4 %	Sufficient
Foundation	85.3 %	Sufficient

Prepared By:

Zachary Sherman  
Structural Engineering Intern

Reviewed By:

Christopher M Murphy, PE  
President  
CT PE License No. 25842

**FDH Engineering, Inc.**  
6521 Meridien Drive  
Raleigh, NC 27616  
(919) 755-1012  
info@fdh-inc.com



July 11, 2012

*Prepared pursuant to TIA/EIA-222-F Structural Standards for Steel Antenna Towers and Antenna Supporting Structures and 2005 Connecticut State Building Code*

**TABLE OF CONTENTS**

EXECUTIVE SUMMARY ..... 3  
    Conclusions ..... 3  
    Recommendation ..... 3  
APPURTENANCE LISTING ..... 4  
RESULTS ..... 4  
GENERAL COMMENTS ..... 6  
LIMITATIONS ..... 6  
APPENDIX ..... 7

## EXECUTIVE SUMMARY

At the request of SBA Network Services, Inc., FDH Engineering, Inc. performed a structural analysis of the monopole located in Simsbury, CT to determine whether the tower is structurally adequate to support both the existing and proposed loads pursuant to the *Structural Standards for Steel Antenna Towers and Antenna Supporting Structures, TIA/EIA-222-F*. Information pertaining to the existing/proposed antenna loading, current tower geometry, and member sizes was obtained from:

- Rohn Industries (File No. 50754AE) original design drawings dated February 13, 2002
- FDH Engineering, Inc. (Job No. 07-0321T) TIA Inspection Report dated April 10, 2007
- SBA Network Service, Inc.

The *basic design wind speed* per the *TIA/EIA-222-F* standards is 80 mph without ice and 38 mph with 1" radial ice. Ice is considered to increase in thickness with height.

## Conclusions

With the existing and proposed antennas from AT&T in place at 151 ft, the tower meets the requirements of the *TIA/EIA-222-F* standards and *2005 Connecticut State Building Code* provided the **Recommendations** listed below are satisfied. Furthermore, provided the foundation was designed and constructed to support the original design reactions (See Rohn Industries File No. 50754AE), the foundation should have the necessary capacity to support the existing and proposed loading. For a more detailed description of the analysis of the tower, see the **Results** section of this report.

Our structural analysis has been performed assuming all information provided to FDH Engineering, Inc. is accurate (i.e., the steel data, tower layout, existing antenna loading, and proposed antenna loading) and that the tower has been properly erected and maintained per the original design drawings.

## Recommendations

To ensure the requirements of the *TIA/EIA-222-F* standards and *2005 Connecticut State Building Code* are met with the existing and proposed loading in place, we have the following recommendations:

1. The proposed coax should be installed inside the pole's shaft.
2. The proposed TMAs should be installed directly behind the proposed panel antennas.



**APPURTENANCE LISTING**

The proposed and existing antennas with their corresponding cables/coax lines are shown in **Table 1**. *If the actual layout determined in the field deviates from the layout, FDH Engineering, Inc. should be contacted to perform a revised analysis.*

**Table 1 - Appurtenance Loading**

**Existing Loading:**

Antenna Elevation (ft)	Description	Coax and Lines	Carrier	Mount Elevation (ft)	Mount Type
153	(1) GPS				
151	(9) CSS DU04-8670 (3) Powerwave 7770 (8) ADC CG1900W/850 TMAs (6) CSS DBC-750 Combiners (3) Powerwave LPG 13519 Diplexers (1) LMU	(16) 1 5/8 (1) 1/2	Cingular	151	(1) 12.5' Low Profile Platform
143	(1) GPS				
141	(3) Antel BXA-70063/4CF_2 (3) Antel BXA-171085-8BF (6) Antel LPA-80080/4CF (6) RFS FD9R6004/2C-3L Diplexers	(12) 1 5/8 (1) 7/8	Verizon	141	(1) 15' Low Profile Platform
131	(3) Kathrein 742 213	(6) 1 5/8	Pocket	131	Direct Mount
123	(6) Decibel DB950F85T2E-M	(6) 1 5/8	Sprint	123	(1) 14' Low Profile Platform
111	(12) Decibel DB844H90E-XY	(12) 1 1/4	Nextel	111	(1) 14' Low Profile Platform

**Proposed Loading:**

Antenna Elevation (ft)	Description	Coax and Lines	Carrier	Mount Elevation (ft)	Mount Type
151	(2) KMW AM-X-CD-16-65-00T-RET (4) Powerwave P65-17-XLH-RR (3) Kathrein 800-10121 (3) CCI DTMABP7819VG12A TMAs (12) Kathrein 860-1006 RETs (6) Ericsson RUS-01 RRUs (3) Andrew ABT-DRDM-ADBH RRUs (1) Raycap DC-6-48-60-18-8F Surge Arrestor (3) Kathrein 782-10250 Diplexers (3) CSS DBC-750 Combiners (1) LMU	(12) 1 5/8 (1) 3" Conduit (1) 10mm Fiber (2) 12 Gauge DC Cables	Cingular	151	(1) 12.5' Low Profile Platform

**RESULTS**

The following yield strength of steel for individual members was used for analysis:

**Table 2 - Material Strength**

Member Type	Yield Strength
Tower Shaft Sections	65 ksi
Base Plate	60 ksi
Anchor Bolts	75 ksi

**Table 3** displays the summary of the ratio (as a percentage) of force in the member to their capacities. Values greater than 100% indicate locations where the maximum force in the member exceeds its capacity. **Table 4** displays the maximum foundation reactions.

If the assumptions outlined in this report differ from actual field conditions, FDH Engineering, Inc. should be contacted to perform a revised analysis. Furthermore, as no information pertaining to the allowable twist and sway requirements for the existing or proposed appurtenances was provided, deflection and rotation were not taken into consideration when performing this analysis.

See the **Appendix** for detailed modeling information

**Table 3 - Summary of Working Percentage of Structural Components**

Section No.	Elevation ft	Component Type	Size	% Capacity	Pass/Fail
L1	150 - 127.92	Pole	TP33.46x28.3x0.1875	22.8	Pass
L2	127.92 - 84.0867	Pole	TP43.21x32.1113x0.25	57.2	Pass
L3	84.0867 - 41.5033	Pole	TP52.55x41.4575x0.3125	64.0	Pass
L4	41.5033 - 0	Pole	TP61.5x50.4229x0.3125	83.4	Pass
		Anchor Bolts	(14) 2.25" $\phi$ w/ BC = 67.625"	72.5	Pass
		Base Plate	73.5" $\phi$ x 2" Thick PL	56.2	Pass

\* Capacities include a 1/3 allowable stress increase for wind.

**Table 4 - Maximum Base Reactions**

Base Reactions	Current Analysis (TIA/EIA-222-F)	Original Design (TIA/EIA-222-F)
Axial	36 k	66 k
Shear	26 k	26 k
Moment	2,837 k-ft	3,324 k-ft

## **GENERAL COMMENTS**


This engineering analysis is based upon the theoretical capacity of the structure. It is not a condition assessment of the tower and its foundation. It is the responsibility of SBA Network Services, Inc. to verify that the tower modeled and analyzed is the correct structure (with accurate antenna loading information) modeled. If there are substantial modifications to be made or the assumptions made in this analysis are not accurate, FDH Engineering, Inc. should be notified immediately to perform a revised analysis.

## **LIMITATIONS**

All opinions and conclusions are considered accurate to a reasonable degree of engineering certainty based upon the evidence available at the time of this report. All opinions and conclusions are subject to revision based upon receipt of new or additional/updated information. All services are provided exercising a level of care and diligence equivalent to the standard and care of our profession. No other warranty or guarantee, expressed or implied, is offered. Our services are confidential in nature and we will not release this report to any other party without the client's consent. The use of this engineering work is limited to the express purpose for which it was commissioned and it may not be reused, copied, or distributed for any other purpose without the written consent of FDH Engineering, Inc.

## APPENDIX

Section	1	2	3	4
Length (ft)	22.08	48.00	48.00	48.00
Number of Sides	18	18	18	18
Thickness (in)	0.1875	0.2500	0.3125	0.3125
Socket Length (ft)	4.17	5.42	6.50	50.4229
Top Dia (in)	28.3000	32.1113	41.4575	61.5000
Bot Dia (in)	33.4600	43.2100	52.5500	9.0
Grade		A572-65		
Weight (K)	1.4	4.8	7.6	22.8



### DESIGNED APPURTENANCE LOADING


TYPE	ELEVATION	TYPE	ELEVATION
(1) 12.5 Low Profile Platform	151	BXA-70063/4CF W/ Mount Pipe	141
AM-X-CW-16-65-00T-RET w/Mount Pipe	151	BXA-70063/4CF W/ Mount Pipe	141
AM-X-CW-16-65-00T-RET w/Mount Pipe	151	BXA-70063/4CF W/ Mount Pipe	141
(2) P65-17-XLH-RR w/Mount Pipe	151	BXA-171085-8BF-EDIN-X w/ Mount Pipe	141
P65-17-XLH-RR w/Mount Pipe	151	BXA-171085-8BF-EDIN-X w/ Mount Pipe	141
P65-17-XLH-RR w/Mount Pipe	151	BXA-171085-8BF-EDIN-X w/ Mount Pipe	141
800 10121 w/ Mount Pipe	151	(2) LPA-80080/4CF W/Mount Pipe	141
800 10121 w/ Mount Pipe	151	(2) LPA-80080/4CF W/Mount Pipe	141
800 10121 w/ Mount Pipe	151	(2) LPA-80080/4CF W/Mount Pipe	141
DTMABP7819VG12A TMA	151	(2) FD9R6004/2C-3L	141
DTMABP7819VG12A TMA	151	(2) FD9R6004/2C-3L	141
DTMABP7819VG12A TMA	151	(2) FD9R6004/2C-3L	141
(4) 860 10006 CCU	151	(1) 15' Low Profile Platform	141
(4) 860 10006 CCU	151	742 213 w/Mount Pipe	131
(4) 860 10006 CCU	151	742 213 w/Mount Pipe	131
(2) RRUS-11	151	742 213 w/Mount Pipe	131
(2) RRUS-11	151	(2) DB950F85T2E-M w/Mount Pipe	123
(2) RRUS-11	151	(2) Empty Mount Pipe	123
ABT-DRDM-ADBH	151	(2) Empty Mount Pipe	123
ABT-DRDM-ADBH	151	(2) Empty Mount Pipe	123
ABT-DRDM-ADBH	151	(2) Empty Mount Pipe	123
DC6-48-60-18-8F Surge Arrestor	151	(1) 14' Low Profile Platform	123
782 10250 Diplexer	151	(2) DB950F85T2E-M w/Mount Pipe	123
782 10250 Diplexer	151	(2) DB950F85T2E-M w/Mount Pipe	123
782 10250 Diplexer	151	(4) DB844H90E-XY w/Mount Pipe	111
DBC-750	151	(1) 14' Low Profile Platform	111
DBC-750	151	(4) DB844H90E-XY w/Mount Pipe	111
DBC-750	151	(4) DB844H90E-XY w/Mount Pipe	111
LMU	151		

### MATERIAL STRENGTH

GRADE	Fy	Fu	GRADE	Fy	Fu
A572-65	65 ksi	80 ksi			

### TOWER DESIGN NOTES

1. Tower is located in Hartford County, Connecticut.
2. Tower designed for a 80 mph basic wind in accordance with the TIA/EIA-222-F Standard.
3. Tower is also designed for a 38 mph basic wind with 1.00 in ice. Ice is considered to increase in thickness with height.
4. Deflections are based upon a 50 mph wind.
5. TOWER RATING: 83.4%



 <b>FDH Engineering, Inc.</b> 6521 Meridian Drive Raleigh, NC 27616 Phone: 919-7551012 FAX: 919-7551031	<b>Job:</b> Simsbury 2-CT10022-A
	<b>Project:</b> 12-06947E S1
	<b>Client:</b> SBA Communications, Inc. <b>Drawn by:</b> Zachary Sherman <b>App'd:</b>
	<b>Code:</b> TIA/EIA-222-F <b>Date:</b> 07/11/12 <b>Scale:</b> NTS
	<b>Path:</b> \\dh-server\Projects\2012\Projects\6 - June\12-06947E\S1-SA_ATT\Analysis\Simsbury 2-CT.ed

**PROJECT INFORMATION**


SCOPE OF WORK: UNMANNED TELECOMMUNICATIONS FACILITY MODIFICATIONS  
 SITE ADDRESS: 225 GRIST MILL ROAD, SIMSBURY, CT 06070  
 LATITUDE: 41° 52' 0.2" N  
 LONGITUDE: 72° 48' 56.9" W  
 JURISDICTION: NATIONAL, STATE & LOCAL CODES OR ORDINANCES  
 CURRENT USE: TELECOMMUNICATIONS FACILITY  
 PROPOSED USE: TELECOMMUNICATIONS FACILITY



**SITE NUMBER: CT1151**  
**SITE NAME: SIMSBURY CENTRAL**

**VICINITY MAP**

DIRECTIONS TO SITE:  
 FROM ROCKY HILL: MERGE ONTO I-91 N. VIA THE RAMP ON THE LEFT TOWARD HARTFORD. 9.2 MILES TAKE THE RAMP ON THE LEFT TOWARD WATERBURY. 0.1 MILES KEEP RIGHT AT THE RAMP. TAKE THE RAMP ON THE LEFT TOWARD WATERBURY. 0.1 MILES TURN SLIGHT LEFT ONTO TRUMBULL ST. 0.1 MILES KEEP LEFT AT THE FORK IN THE RAMP. 0.1 MILES TURN SLIGHT LEFT ONTO TRUMBULL ST. 0.1 MILES TURN RIGHT ONTO US-44 / MAIN ST. CONTINUE TO FOLLOW US-44. 2.3 MILES TURN SLIGHT RIGHT ONTO BLOOMFIELD AVE / CT-189. 0.8 MILES TURN SLIGHT LEFT ONTO CT-185 / SIMSBURY RD. CONTINUE TO FOLLOW CT-185. 0.6 MILES TURN SLIGHT RIGHT ONTO HOPMEADOW ST / US-202 / CT-01. 1.7 MILES SHARP LEFT ONTO WEST ST / CT-167 / CT-308. 0.4 MILES TURN LEFT ONTO GRIST MILL RD.



**GENERAL NOTES**

- THIS DOCUMENT IS THE CREATION, DESIGN, PROPERTY AND COPYRIGHTED WORK OF AT&T. ANY DUPLICATION OR USE WITHOUT EXPRESS WRITTEN CONSENT IS STRICTLY PROHIBITED. THE FACILITY IS AN UNMANNED PRIVATE AND SECURED EQUIPMENT INSTALLATION. IT IS ONLY TO BE OPERATED BY TRAINED TECHNICIANS FOR PERIODIC ROUTINE MAINTENANCE AND THEREFORE DOES NOT REQUIRE ANY WATER OR SANITARY SEWER SERVICE. THE FACILITY IS NOT GOVERNED BY REGULATIONS REQUIRING PUBLIC ACCESS PER ADA REQUIREMENTS.
- CONTRACTOR SHALL VERIFY ALL PLANS AND EXISTING DIMENSIONS AND CONDITIONS ON THE JOB SITE AND SHALL IMMEDIATELY REPORT ANY DISCREPANCIES IN WRITING OF DISCREPANCIES BEFORE PROCEEDING WITH THE WORK OR BE RESPONSIBLE FOR SAME.
- 72 HOURS BEFORE YOU DIG CALL TOLL FREE 800-922-4455

72 HOURS



BEFORE YOU DIG

CALL TOLL FREE 800-922-4455

UNDERGROUND SERVICE ALERT

**DRAWING INDEX**

	REV
T-1 TITLE SHEET	1
GN-1 GENERAL NOTES	1
A-1 COMPOUND & EQUIPMENT PLAN	1
A-2 ANTENNA LAYOUT AND ELEVATION	1
A-3 DETAILS	1
G-1 PLUMBING DIAGRAM & GROUNDING DETAILS	1

**Hudson**  
 Design Group  
 1400 COCO PART  
 1600 W. NORTH WIRE 2-01  
 N. ANDOVER, MASS. 01860  
 TEL: (978) 552-5553  
 FAX: (978) 552-5554

**NEXLINK**  
 A UNICORP. GENERAL SERVICES COMPANY  
 800 MARSHALL PHELPS ROAD UNIT# 2A  
 WINDSOR, CT 06095

**at&t**  
 500 ENTERPRISE DRIVE, SUITE 3A  
 ROCKY HILL, CT 04067

**STATE OF CONNECTICUT**  
 REGISTERED PROFESSIONAL ENGINEER  
 NO. 26220  
 DATE 03/07/12  
 ISSUED FOR REVIEW  
 BY CHM/STP/STB  
 REVISIONS  
 DESIGNED BY: DC  
 DRAWN BY: DB  
 SCALE: AS SHOWN

NO.	DATE	ISSUED FOR REVIEW	ISSUED FOR CONSTRUCTION
1	03/07/12	ISSUED FOR REVIEW	ISSUED FOR CONSTRUCTION

AT&T  
 TITLE SHEET (LIE)  
 DRAWING NUMBER  
 T-1  
 1

**GROUNDING NOTES**

1. THE SUBCONTRACTOR SHALL REVIEW AND INSPECT THE EXISTING FACILITY GROUNDING SYSTEM AND LIGHTNING PROTECTION SYSTEM (AS DESIGNED AND INSTALLED) FOR STRICT COMPLIANCE WITH THE NEC (AS ADOPTED BY THE AHJ), THE SITE-SPECIFIC (UL, LPI, OR NFPA) LIGHTNING PROTECTION CODE, AND GENERAL COMPANIES. THE TELLORDIA AND TA GROUNDING STANDARDS. THE SUBCONTRACTOR SHALL REPORT ANY VIOLATIONS OR ADVERSE FINDINGS TO THE CONTRACTOR FOR RESOLUTION.
2. ALL GROUND ELECTRODE SYSTEMS INCLUDING TELECOMMUNICATION, RADIO, LIGHTNING PROTECTION, AND AC POWER (GES'S) SHALL BE BONDED TOGETHER, AT OR BELOW GRADE, BY TWO OR MORE COPPER BONDING CONDUCTORS IN ACCORDANCE WITH THE NEC.
3. THE SUBCONTRACTOR SHALL REFORM IEEE 1140-1-2011 POTENTIAL RESISTANCE TO EARTH TESTING (PER IEEE 1140-1-2011 AND 81) FOR NEW GROUND ELECTRODE SYSTEMS. THE SUBCONTRACTOR SHALL FURNISH AND INSTALL SUPPLEMENTAL GROUND ELECTRODES AS NEEDED TO ACHIEVE A TEST RESULT OF 5 OHMS OR LESS.
4. METAL BACKWAY SHALL NOT BE USED AS THE NEC REQUIRED EQUIPMENT GROUND CONDUCTOR. STRANDED COPPER CONDUCTORS WITH GREEN INSULATION, SIZED IN ACCORDANCE WITH THE NEC, SHALL BE FURNISHED AND INSTALLED WITH THE POWER CIRCUITS TO BITS EQUIPMENT.
5. EACH BITS CABINET FRAME SHALL BE DIRECTLY CONNECTED TO THE MASTER GROUND BAR WITH GREEN INSULATED SUPPLEMENTAL EQUIPMENT GROUND WIRES. 6 AWG STRANDED COPPER OR LARGER FOR INDOOR BITS 2 AWG STRANDED COPPER FOR OUTDOOR BITS.
6. EXOTHERMIC WELDS SHALL BE USED FOR ALL GROUNDING CONNECTIONS BELOW GRADE.
7. APPROVED ANTIOXIDANT COATINGS (I.E., CONDUCTIVE GEL OR PASTE) SHALL BE USED ON ALL COMPRESSION AND BOLTED GROUND CONNECTIONS.
8. ICE BRIDGE BONDING CONDUCTORS SHALL BE EXOTHERMICALLY BONDED OR BOLTED TO THE BRIDGE AND THE TOWER GROUND BAR.
9. ALUMINUM CONDUCTOR OR COPPER CLAD STEEL CONDUCTOR SHALL NOT BE USED FOR GROUNDING CONNECTIONS.
10. MISCELLANEOUS ELECTRICAL AND NON-ELECTRICAL METAL BOXES, FRAMES AND SUPPORTS SHALL BE BONDED TO THE GROUND RING, IN ACCORDANCE WITH THE NEC.
11. METAL CONDUIT SHALL BE MADE ELECTRICALLY CONTINUOUS WITH LISTED BONDING FITTINGS OR BY BONDING ACROSS THE DISCONTINUITY WITH 6 AWG COPPER WIRE UL APPROVED GROUNDING TYPE CONDUIT CLAMPS.
12. ALL NEW STRUCTURES WITH A FOUNDATION AND/OR FOOTING SHALL BE MADE ELECTRICALLY CONTINUOUS WITH 6 AWG COPPER WIRE UL APPROVED GROUNDING TYPE CONDUIT CLAMPS. ALL NEW STRUCTURES WITH A FOUNDATION AND/OR FOOTING SHALL BE MADE ELECTRICALLY CONTINUOUS WITH 6 AWG COPPER WIRE UL APPROVED GROUNDING TYPE CONDUIT CLAMPS. ALL NEW STRUCTURES WITH A FOUNDATION AND/OR FOOTING SHALL BE MADE ELECTRICALLY CONTINUOUS WITH 6 AWG COPPER WIRE UL APPROVED GROUNDING TYPE CONDUIT CLAMPS.

**GENERAL NOTES**

1. FOR THE PURPOSE OF CONSTRUCTION DRAWING, THE FOLLOWING DEFINITIONS SHALL APPLY:
  - CONTRACTOR - GENERAL CONTRACTOR (CONSTRUCTION)
  - SUBCONTRACTOR - NEXLINK OWNER - AT&T MOBILITY
2. PRIOR TO THE SUBMISSION OF BIDS, THE BIDDING SUBCONTRACTOR SHALL VISIT THE CELL SITE TO FAMILIARIZE WITH THE EXISTING CONDITIONS AND TO CONFIRM THAT THE WORK CAN BE ACCOMPLISHED AS SHOWN ON THE CONSTRUCTION DRAWINGS. ANY DISCREPANCY FOUND SHALL BE BROUGHT TO THE ATTENTION OF CONTRACTOR.
3. ALL MATERIALS FURNISHED AND INSTALLED SHALL BE IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS, AND ORDINANCES. SUBCONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS, REGULATIONS, AND LAWFUL ORDERS OF ANY PUBLIC AUTHORITY REGARDING THE PERFORMANCE OF THE WORK. ALL WORK CARRIED OUT SHALL COMPLY WITH ALL APPLICABLE MUNICIPAL AND UTILITY COMPANY SPECIFICATIONS AND LOCAL JURISDICTIONAL CODES, ORDINANCES AND APPLICABLE REGULATIONS.
4. DRAWINGS PROVIDED HERE ARE NOT TO BE SCALED AND ARE INTENDED TO SHOW OUTLINE ONLY.
5. UNLESS NOTED OTHERWISE, THE WORK SHALL INCLUDE FURNISHING MATERIALS, EQUIPMENT, APPURTENANCES, AND LABOR NECESSARY TO COMPLETE ALL INSTALLATIONS AS INDICATED ON THE DRAWINGS.
6. NOTHING LIST SUPPLIED WITH THE BID PACKAGE IDENTIFIES ITEMS THAT WILL BE PROVIDED BY THE CONTRACTOR. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL MATERIALS AND FITTING LIST SHALL BE SUPPLIED BY THE SUBCONTRACTOR.
7. THE SUBCONTRACTOR SHALL INSTALL ALL EQUIPMENT AND MATERIALS IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS UNLESS SPECIFICALLY STATED OTHERWISE.
8. IF THE SPECIFIED EQUIPMENT CANNOT BE INSTALLED AS SHOWN ON THESE DRAWINGS, THE SUBCONTRACTOR SHALL PROPOSE AN ALTERNATIVE INSTALLATION SPACE FOR APPROVAL BY THE CONTRACTOR.
9. SUBCONTRACTOR SHALL DETERMINE ACTUAL ROUTING OF CONDUIT, POWER AND T1 CABLES, DRAWING CABLES AS SHOWN ON THE POWER, GROUNDING AND TELCO PLAN DRAWING. SUBCONTRACTOR SHALL UTILIZE EXISTING TRAYS AND/OR SHALL ADD NEW TRAYS AS NECESSARY. SUBCONTRACTOR SHALL CONFIRM THE ACTUAL ROUTING WITH THE CONTRACTOR.
10. THE SUBCONTRACTOR SHALL PROTECT EXISTING IMPROVEMENTS, PAVEMENTS, CURBS, LANDSCAPING AND STRUCTURES. ANY DAMAGED PART SHALL BE REPAIRED AT SUBCONTRACTOR'S EXPENSE TO THE SATISFACTION OF OWNER.
11. SUBCONTRACTOR SHALL LEGALLY AND PROPERLY DISPOSE OF ALL SCRAP MATERIALS SUCH AS COAXIAL CABLES AND OTHER ITEMS REMOVED FROM THE EXISTING FACILITY. ANTENNAS REMOVED SHALL BE RETURNED TO THE OWNER'S DESIGNATED LOCATION.
12. SUBCONTRACTOR SHALL LEAVE PREMISES IN CLEAN CONDITION.
13. ALL CONCRETE REPAIR WORK SHALL BE DONE IN ACCORDANCE WITH AMERICAN CONCRETE INSTITUTE (ACI) 301.
14. ANY NEW CONCRETE NEEDED FOR THE CONSTRUCTION SHALL BE AIR-ENTRAINED AND SHALL HAVE 4000 PSI STRENGTH AT 28 DAYS. ALL CONCRETE WORK SHALL BE DONE IN ACCORDANCE WITH ACI 318 CODE REQUIREMENTS.

**ABBREVIATIONS**

AGL	ABOVE GRADE LEVEL	G.C.	GENERAL CONTRACTOR	RF	RADIO FREQUENCY
AWG	AMERICAN WIRE GAUGE	MGB	MASTER GROUND BUS	TBD	TO BE DETERMINED
BCW	BARE COPPER WIRE	MIN	MINIMUM	TBR	TO BE REMOVED
BTS	BASE TRANSCENDER STATION	PROPOSED	NEW	TBR	TO BE REMOVED
EX	EXISTING	N.T.S.	NOT TO SCALE	TBR	TO BE REMOVED AND REPLACED
EC	EQUIPMENT GROUND	REL	REFERENCE	TP	TYPICAL
EGR	EQUIPMENT GROUND RING	RE	REWORK		

**GENERAL NOTES (LITE)**

NO.	DATE	REVISIONS	DESIGNED BY: DC	DRAWN BY: DB	SCALE: AS SHOWN
1	10/17/22	ISSUED FOR CONSTRUCTION			
2	10/27/22	ISSUED FOR REVIEW			

**at&t**

500 ENTERPRISE DRIVE, SUITE 3A  
ROCKY HILL, CT 06067

**Site Number: CT1151**  
**Site Name: SIMSBURY CENTRAL**  
225 GIBBS MILL ROAD  
SIMSBURY, CT 06070  
HARTFORD COUNTY

**NEW LINK**  
A HUBER+SUHNER COMPANY  
800 MARSHALL PHELPS ROAD UNIT# 2A  
WINDSOR, CT 06095

**Hudson**  
Design Group, Inc.  
140 OLDGARD STREET  
MIDDLETOWN, CT 06457  
TEL: (860) 341-1500  
WWW.HUDSONDESIGN.COM

**AT&T**  
GENERAL NOTES (LITE)  
DRAWN NUMBER: 011  
G11-1

**ABBREVIATIONS**

AGL	ABOVE GRADE LEVEL	G.C.	GENERAL CONTRACTOR	RF	RADIO FREQUENCY
AWG	AMERICAN WIRE GAUGE	MGB	MASTER GROUND BUS	TBD	TO BE DETERMINED
BCW	BARE COPPER WIRE	MIN	MINIMUM	TBR	TO BE REMOVED
BTS	BASE TRANSCENDER STATION	PROPOSED	NEW	TBR	TO BE REMOVED
EX	EXISTING	N.T.S.	NOT TO SCALE	TBR	TO BE REMOVED AND REPLACED
EC	EQUIPMENT GROUND	REL	REFERENCE	TP	TYPICAL
EGR	EQUIPMENT GROUND RING	RE	REWORK		



FOR ANY CONFLICTS BETWEEN SECTIONS OF LISTED CODES AND STANDARDS REGARDING MATERIAL METHODS OF CONSTRUCTION, OR OTHER REQUIREMENTS, THE MOST RESTRICTIVE REQUIREMENT SHALL GOVERN. WHERE THERE IS CONFLICT BETWEEN A GENERAL REQUIREMENT AND A SPECIFIC REQUIREMENT, THE SPECIFIC REQUIREMENT SHALL GOVERN.

AMERICAN CONCRETE INSTITUTE (ACI) 318; BUILDING CODE REQUIREMENTS FOR STRUCTURAL CONCRETE;  
AMERICAN INSTITUTE OF STEEL CONSTRUCTION (AISC) MANUAL OF STEEL CONSTRUCTION, ASD, NINTH EDITION;  
TELECOMMUNICATIONS INDUSTRY ASSOCIATION (TIA) 222-F, STRUCTURAL STANDARDS FOR STEEL  
ANTENNA TOWER AND ANTENNA SUPPORTING STRUCTURES; REFER TO ELECTRICAL DRAWINGS FOR SPECIFIC ELECTRICAL STANDARDS.  
FOR ANY CONFLICTS BETWEEN SECTIONS OF LISTED CODES AND STANDARDS REGARDING MATERIAL METHODS OF CONSTRUCTION, OR OTHER REQUIREMENTS, THE MOST RESTRICTIVE REQUIREMENT SHALL GOVERN. WHERE THERE IS CONFLICT BETWEEN A GENERAL REQUIREMENT AND A SPECIFIC REQUIREMENT, THE SPECIFIC REQUIREMENT SHALL GOVERN.





**NOTE:**  
REFER TO THE FINAL RF DATA SHEET FOR FINAL ANTENNA SETTINGS.

**NOTE:**  
AN ANALYSIS FOR THE CAPACITY OF THE EXISTING STRUCTURES TO SUPPORT THE PROPOSED EQUIPMENT SHALL BE DETERMINED PRIOR TO CONSTRUCTION.



**COMPOUND PLAN**  
SCALE: 1/8"=1'-0"



**EQUIPMENT PLAN**  
SCALE: 1/2"=1'-0"



**Hudson**  
Design Group  
1000 GARDNER STREET  
MIDDLETOWN, CT 06457  
TEL: 878-557-5333  
FAX: 878-557-5334

**NEALINK**  
A UNIFIBER GLOBAL SERVICES COMPANY  
800 MARSHFIELD PHOENIX ROAD, UNIT # 2A  
WINDSOR, CT 06095

**at&t**  
SITE NUMBER: CT1151  
SITE NAME: SIMSBURY CENTRAL  
225 GRIST MILL ROAD  
SIMSBURY, CT 06070  
HARTFORD COUNTY

**at&t**  
500 ENTERPRISE DRIVE, SUITE 3A  
ROCKY HILL, CT 06067




PROJECT	AS SHOWN	DESIGNED BY:	DC	PERMANENT BY:	DD
NO.	DATE	REVISIONS	BY:	CHK:	APP:
1	04/15/13	ISSUED FOR CONSTRUCTION	DB	DC	DB
0	03/07/13	ISSUED FOR REVIEW	DB	DC	DB
AT&T COMPOUND & EQUIPMENT PLAN (LIE)					
REV	NO.	DATE	DESCRIPTION	BY	CHK
1	A-1		DRAWING NUMBER		




**NOTE:**  
REFER TO THE FINAL RF DATA SHEET FOR FINAL ANTENNA SETTINGS.


**NOTE:**  
AN ANALYSIS FOR THE CAPACITY OF THE EXISTING STRUCTURES TO SUPPORT THE PROPOSED EQUIPMENT SHALL BE DETERMINED PRIOR TO CONSTRUCTION.



**EXISTING UMTS/GSM ANTENNA PLAN**  
SCALE: N.T.S.



**PROPOSED LTE ANTENNA PLAN**  
SCALE: N.T.S.



**SOUTH ELEVATION**  
SCALE: 3/32"=1'-0"

Hudson Design Group  
1000 SHAWMUT LANE # 200  
WINDSOR, CONNECTICUT 06095

NextLink  
A Unit of GCI/Verizon  
800 MANSFIELD BLVD SUITE 200  
WINDSOR, CT 06095

**at&t**

500 ENTERPRISE DRIVE, SUITE 3A  
ROCKY HILL, CT 06867

**SITE NUMBER: CT1151**  
**SITE NAME: SIMSBURY CENTRAL**  
225 GRIST MILL ROAD  
SIMSBURY, CT 06070  
HARTFORD COUNTY

NO.	DATE	REVISIONS	BY	CHK	APP	SCALE
1	04/18/13	ISSUED FOR CONSTRUCTION	DB	DC	DB	AT&T
0	03/27/13	ISSUED FOR REVIEW	DB	DC	DB	AT&T


AT&T

ANTENNA LAYOUT AND ELEVATION (LIE)

SCALE: AS SHOWN

DESIGNED BY: DC

DRAWN BY: DB



**NOTE:**  
AN ANALYSIS FOR THE CAPACITY OF THE EXISTING STRUCTURES TO SUPPORT THE ANTENNA SHALL BE DETERMINED PRIOR TO CONSTRUCTION.

**NOTE:**  
REFER TO THE FINAL RF DATA SHEET FOR FINAL ANTENNA SETTINGS.

**GPS MOUNTING DETAIL**  
SCALE: N.T.S.

**PROPOSED GSM ANTENNA MOUNTING DETAIL**  
SCALE: N.T.S.

**PROPOSED LTE ANTENNA, RRH & SURGE ARRESTOR MOUNTING DETAIL**  
SCALE: N.T.S.


**DC SURGE SUPPRESSOR DETAIL**  
SCALE: N.T.S.

**NOTE:**  
MOUNT PER MANUFACTURER'S SPECIFICATIONS.

**NOTE:**  
MOUNT PER MANUFACTURER'S SPECIFICATIONS.



**SITE NUMBER: CT1151**  
**SITE NAME: SIMSBURY CENTRAL**  
225 CRIST MILL ROAD  
SIMSBURY, CT 06070  
HARTFORD COUNTY



NO.	DATE	ISSUED FOR CONSTRUCTION	ISSUED FOR REVIEW	BY	CHK	APP	REVISIONS	DESIGNED BY: DC	DRAWN BY: DB
1	04/18/12	ISSUED FOR CONSTRUCTION		DC	DC	DC			
2	03/07/12	ISSUED FOR REVIEW		DC	DC	DC			

SCALE: AS SHOWN

AT&T  
DETAILS (LIE)  
DRAWING NUMBER: A-3  
REV: 1