



Northeast Site Solutions
Denise Sabo
4 Angela's Way, Burlington CT 06013
203-435-3640
denise@northeastsitesolutions.com

October 7, 2021

Members of the Siting Council
Connecticut Siting Council
Ten Franklin Square
New Britain, CT 06051

RE: Tower Share Application
1432 Old Waterbury Road, Southbury, CT 06488
Latitude: 41.493583
Longitude: -73.165278
Site# 806358_Crown_Dish

Dear Ms. Bachman:

This letter and attachments are submitted on behalf of Dish Wireless LLC. Dish Wireless LLC plans to install antennas and related equipment to the tower site located at 1432 Old Waterbury Road in Southbury, Connecticut.

Dish Wireless LLC proposes to install three (3) 600/1900 5G MHz antenna and six (6) RRUs, at the 218-foot level of the existing 226-foot monopole tower, one (1) Fiber cables will also be installed. Dish Wireless LLC equipment cabinets will be placed within 7x5 lease area. Included are plans by Infinigy, dated August 24, 2021 Exhibit C. Also included is a structural analysis prepared by Crown Castle, dated June 4, 2021, confirming that the existing tower is structurally capable of supporting the proposed equipment. Attached as Exhibit D. The facility was approved by the Connecticut Siting Council in Docket No. 88 on March 3, 1988. Please see attached Exhibit A.

Please accept this letter as notification pursuant to Regulations of Connecticut State Agencies 16-50aa, of Dish Wireless LLC intent to share a telecommunications facility pursuant to R.C.S.A. 16-50j-88. In accordance with R.C.S.A., a copy of this letter is being sent to The Honorable Jeff Manville, First Selectman, for the Town of Southbury Kathy Castagnetta, AICP, Land Use Administrator, as well as the tower owner (Crown Castle) and property owner (Crown Castle)

The planned modifications of the facility fall squarely within those activities explicitly provided for in R.C.S.A. 16-50j-89.

1. The proposed modification will not result in an increase in the height of the existing structure. The top of the tower is 226-feet; Dish Wireless LLC proposed antennas will be located at a center line height of 218-feet.
2. The proposed modifications will not result in the increase of the site boundary as depicted on the attached site plan.
3. The proposed modifications will not increase noise levels at the facility by six decibels or more, or to levels that exceed local and state criteria. The incremental effect of the proposed changes will be negligible.



4. The operation of the proposed antennas will not increase radio frequency emissions at the facility to a level at or above the Federal Communications Commission safety standard. As indicated in the attached power density calculations, the combined site operations will result in a total power density of 10.40% as evidenced by Exhibit F.

Connecticut General Statutes 16-50aa indicates that the Council must approve the shared use of a telecommunications facility provided it finds the shared use is technically, legally, environmentally, and economically feasible and meets public safety concerns. As demonstrated in this letter, Dish Wireless LLC respectfully indicates that the shared use of this facility satisfies these criteria.

A. Technical Feasibility. The existing monopole has been deemed structurally capable of supporting Dish Wireless LLC proposed loading. The structural analysis is included as Exhibit D.

B. Legal Feasibility. As referenced above, C.G.S. 16-50aa has been authorized to issue orders approving the shared use of an existing tower such as this support tower in Southbury. Under the authority granted to the Council, an order of the Council approving the requested shared use would permit Dish Wireless LLC to obtain a building permit for the proposed installation. Further, a Letter of Authorization is included as Exhibit G, authorizing Dish Wireless LLC to file this application for shared use.

C. Environmental Feasibility. The proposed shared use of this facility would have a minimal environmental impact. The installation of Dish Wireless LLC equipment at the 218-foot level of the existing 226-foot tower would have an insignificant visual impact on the area around the tower. Dish Wireless LLC ground equipment would be installed within the existing facility compound. Dish Wireless LLC shared use would therefore not cause any significant alteration in the physical or environmental characteristics of the existing site. Additionally, as evidenced by Exhibit F, the proposed antennas would not increase radio frequency emissions to a level at or above the Federal Communications Commission safety standard.

D. Economic Feasibility. Dish Wireless LLC will be entering into an agreement with the owner of this facility to mutually agreeable terms. As previously mentioned, the Letter of Authorization has been provided by the owner to assist Dish Wireless LLC with this tower sharing application.

E. Public Safety Concerns. As discussed above, the tower is structurally capable of supporting Dish Wireless LLC proposed loading. Dish Wireless LLC is not aware of any public safety concerns relative to the proposed sharing of the existing guyed tower. Dish Wireless LLC intentions of providing new and improved wireless service through the shared use of this facility is expected to enhance the safety and welfare of local residents and individuals traveling through Southbury.

Sincerely,

Denise Sabo

Denise Sabo
Mobile: 203-435-3640
Fax: 413-521-0558
Office: 4 Angela's Way, Burlington CT 06013
Email: denise@northeastsitesolutions.com



NSS **NORTHEAST**
SITE SOLUTIONS
Turnkey Wireless Development

Attachments cc:

The Honorable Jeff Manville, First Selectman
Southbury Town Hall
501 Main Street South Southbury, CT 06488

Kathy Castagnetta, AICP, Land Use Administrator
Southbury Town Hall
501 Main Street South Southbury, CT 06488

Crown Castle, Tower & Property Owner

Exhibit A

Original Facility Approval

DOCKET NO. 88 - AN APPLICATION OF : CONNECTICUT SITING
METRO MOBILE CTS OF NEW HAVEN, INC.,
FOR A CERTIFICATE OF ENVIRONMENTAL :
COMPATIBILITY AND PUBLIC NEED FOR : COUNCIL
CELLULAR TELEPHONE ANTENNAS AND
ASSOCIATED EQUIPMENT IN THE TOWN OF :
SOUTHBURY, CONNECTICUT : MARCH 3, 1988

D E C I S I O N A N D O R D E R

Pursuant to the forgoing opinion, the Connecticut Siting Council hereby directs that a Certificate of Environmental Compatibility and Public Need as provided by Section 16-50k of the General Statutes of Connecticut (CGS) be issued to Metro Mobile CTS of New Haven, Inc. for the construction, operation, and maintenance of a cellular telephone tower site and associated equipment at the "M/A-Southbury" alternative site on Old Waterbury Road in the Town of Southbury, Connecticut. The "M-Southbury" site on Luther Drive is hereby denied.

The facility shall be constructed, operated, and maintained as specified in the Council's record in this matter, and subject to the following conditions:

1. The monopole tower at the Southbury site shall be no taller than necessary to provide the proposed service, and in no event shall exceed a total height of 243 feet, including antennas and associated equipment, or violate the air space of Oxford Airport as determined by the Federal Aviation Administration (FAA).
2. The facility shall be constructed in accordance with all applicable federal, state, and municipal laws and regulations.
3. Unless necessary to comply with condition number 2, above, no lights shall be installed on this tower.

4. The Certificate Holder shall prepare a development and management (D&M) plan for the Southbury site in compliance with sections 16-50j-75 through 16-50j-77 of the Regulations of State Agencies. The D&M plan shall provide for permanent evergreen screening around the outside perimeter of the eight-foot chain link fence which will surround the site. The D&M shall also document the final height of the tower as approved by the FAA.
5. The Certificate Holder or its successor shall notify the Council if and when directional antennas or any equipment other than that listed in this application is added to this facility.
6. The Certificate Holder or its successor shall permit public or private entities to share space on the Southbury tower for due consideration, or shall provide any requesting entity with specific legal, technical, environmental, or economic reasons precluding such tower sharing.
7. If this facility does not provide or permanently ceases to provide cellular service following completion of construction, this Decision and Order shall be void, and the tower and all associated equipment in this application shall be dismantled and removed or reapplication for any new use shall be made to the Council before any such new use is made.

8. The Certificate Holder shall comply with any future radio frequency (RF) standards promulgated by State or federal regulatory agencies. Upon the establishment of any new governmental RF standards, the facility granted in this Decision and Order shall be brought into compliance with such standards.
9. Unless otherwise approved by the Council, this Decision and Order shall be void if all construction authorized herein is not completed within three years of the issuance of this Decision and Order, or within three years of the completion of any appeal taken in this Decision and Order.

Pursuant to CGS Section 16-50p, we hereby direct that a copy of this Decision and Order be served on each person listed below. A notice of the issuance shall be published in the Waterbury Republican and Newtown Bee.

By this Decision and Order, the Council disposes of the legal rights, duties, and privileges of each party named or admitted to the proceeding in accordance with Section 16-50j-17 of the Regulations of State Agencies.

The parties or intervenors to this proceeding are:

Metro Mobile CTS of
New Haven, Inc.
50 Rockland Road
South Norwalk, CT 06854

(applicant)

Mr. Howard L. Slater, Esq. (its representative)
Ms. Jennifer Young Gaudet
Byrne, Slater, Sandler,
Shulman & Rouse, P.C.
330 Main Street
P.O. Box 3216
Hartford, CT 06103

Fleishman and Walsh, P.C. (party)
1725 N Street, N.W.
Washington, D.C. 20036

SNET Cellular, Inc. (intervenor)
Peter J. Tyrrell, Esq.
227 Church Street
New Haven, CT 06506

Dennis Roberts (intervenor)
Martha J. Roberts
306 Luther Drive
Southbury, CT 06488

Carol A. Herskowitz (intervenor)
First Selectman
Town of Southbury
Town Hall
501 Main Street South
Southbury, CT 06488

Duncan M. Graham (party)
Executive Director
Council of Governments
Of The Central Naugatuck Valley
20 East Main Street
Waterbury, CT 06702

CERTIFICATION

The undersigned members of the Connecticut Siting Council hereby certify that they have heard this case in Docket 88 or read the record thereof, and that we voted as follows:

Dated at New Britain, Connecticut the 3rd day of March, 1988.

<u>Council Members</u>	<u>Vote Cast</u>
<u><i>Gloria Dibble Pond</i></u> Gloria Dibble Pond Chairperson	Yes
<u><i>Roland A. Miller</i></u> Commissioner Peter Boucher Designee: Roland Miller	Yes
<u><i>Brian J. Emerick</i></u> Commissioner Leslie Carothers Designee: Brian Emerick	Yes
<u>Owen L. Clark</u>	Absent
<u><i>Fred J. Doocy</i></u> Fred J. Doocy	Yes
<u><i>Mortimer A. Gelston</i></u> Mortimer A. Gelston	Yes
<u><i>James G. Horsfall</i></u> James G. Horsfall	Yes
<u><i>William H. Smith</i></u> William H. Smith	Yes
<u>Colin C. Tait</u>	Absent

Exhibit B

Property Card



Town of Southbury, CT

Property Listing Report

Map Block Lot

46-8-10A-?

Building #

Section #

Account

00537703

Property Information

Property Location	1432 OLD WATERBURY ROAD #?
Owner	CROWN ATLANTIC CO LLC
Co-Owner	4017 WASHINGTON RD
Mailing Address	P M BOX 353 MCMURRAY PA 15317
Land Use	300 Ind Land
Land Class	I
Zoning Code	M-2
Census Tract	3411

Street Index	
Acreage	0
Utilities	
Lot Setting/Desc	
Additional Info	

Photo



Sketch

Primary Construction Details

Year Built	
Stories	
Building Style	
Building Use	
Building Condition	
Interior Floors 1	
Interior Floors 2	
Percent Good	
Total Rooms	
Basement Garages	
Occupancy	
Building Grade	
Foundation	

Bedrooms	
Full Bathrooms	
Half Bathrooms	
Extra Fixtures	
Bath Style	
Kitchen Style	
Roof Style	
Roof Cover	
AC Percent	
PLN FPL	
DET FPL	
Gas Fireplace	

Exterior Walls	
Exterior Walls 2	
Interior Walls	
Interior Walls 2	
Heating Type	
Heating Fuel	
Sq. Ft. Basement	
Fin BSMT Quality	
Percent Basement	
Basement Access	
% Attic Finished	
LF Dormer	



Town of Southbury, CT

Property Listing Report

Map Block Lot **46-8-10A-?**

Building #

Section #

Account **00537703**

Valuation Summary (Assessed value = 70% of Appraised Value)

Item	Appraised	Assessed
Buildings	0	0
Extras	0	0
Improvements		
Outbuildings	0	0
Land	160000	112000
Total	160000	112000

Sub Areas


Subarea Type	Gross Area (sq ft)	Living Area (sq ft)
Total Area		

Outbuilding and Extra Features

Type	Description

Sales History

Owner of Record	Book/ Page	Sale Date	Sale Price
VOLPE BUILDERS INC	297/1245	6/25/1995	0
CROWN ATLANTIC CO LLC	484/ 720	4/11/2005	220000





SHEET NO. 46

- Tax Map Grid
- Townline
- Historic Parcel Line
- Misc. Easements
- Parcels
- Pavement
- Decks
- Rivers / Streams
- Buildings
- Lakes / Ponds



Town of Southbury, CT Assessor Tax Map

1 inch = 350 feet



SHEET NO. 46

MAP DATE : GL October 2018

THIS MAP HAS BEEN COMPILED FROM RECORDED SURVEYS, DEED DIMENSIONS AND OTHER SOURCES OF INFORMATION. THE DELINEATION OF BOUNDARY LINES IS APPROXIMATE. THIS MAP SHOULD NOT BE RELIED UPON FOR PROPERTY CONVEYANCES.

Print Date: August 2019



Exhibit C

Construction Drawings



DISH Wireless L.L.C. SITE ID:

BOHVN00009A

DISH Wireless L.L.C. SITE ADDRESS:

**1432 OLD WATERBURY ROAD
SOUTHBURY, CT 06488**

CONNECTICUT CODE COMPLIANCE

ALL WORK SHALL BE PERFORMED AND MATERIALS INSTALLED IN ACCORDANCE WITH THE CURRENT EDITIONS OF THE FOLLOWING CODES AS ADOPTED BY THE LOCAL GOVERNING AUTHORITIES. NOTHING IN THESE PLANS IS TO BE CONSTRUED TO PERMIT WORK NOT CONFORMING TO THESE CODES:

CODE TYPE	CODE
BUILDING	2018 CT STATE BUILDING CODE/2015 IBC W/ CT AMENDMENTS
MECHANICAL	2018 CT STATE BUILDING CODE/2015 IMC W/ CT AMENDMENTS
ELECTRICAL	2018 CT STATE BUILDING CODE/2017 NEC W/ CT AMENDMENTS

SHEET INDEX

SHEET NO.	SHEET TITLE
T-1	TITLE SHEET
A-1	OVERALL AND ENLARGED SITE PLAN
A-2	ELEVATION, ANTENNA LAYOUT AND SCHEDULE
A-3	EQUIPMENT PLATFORM AND H-FRAME DETAILS
A-4	EQUIPMENT DETAILS
A-5	EQUIPMENT DETAILS
A-6	EQUIPMENT DETAILS
E-1	ELECTRICAL/FIBER ROUTE PLAN AND NOTES
E-2	ELECTRICAL DETAILS
E-3	ELECTRICAL ONE-LINE, FAULT CALCS & PANEL SCHEDULE
G-1	GROUNDING PLANS AND NOTES
G-2	GROUNDING DETAILS
G-3	GROUNDING DETAILS
RF-1	RF CABLE COLOR CODE
GN-1	LEGEND AND ABBREVIATIONS
GN-2	GENERAL NOTES
GN-3	GENERAL NOTES
GN-4	GENERAL NOTES

SCOPE OF WORK

THIS IS NOT AN ALL INCLUSIVE LIST. CONTRACTOR SHALL UTILIZE SPECIFIED EQUIPMENT PART OR ENGINEER APPROVED EQUIVALENT. CONTRACTOR SHALL VERIFY ALL NEEDED EQUIPMENT TO PROVIDE A FUNCTIONAL SITE. THE PROJECT GENERALLY CONSISTS OF THE FOLLOWING:

- TOWER SCOPE OF WORK:**
- INSTALL (3) PROPOSED PANEL ANTENNAS (1 PER SECTOR)
 - INSTALL (1) PROPOSED PLATFORM
 - INSTALL (1) PROPOSED JUMPERS
 - INSTALL (6) PROPOSED RRUs (2 PER SECTOR)
 - INSTALL (1) PROPOSED OVER VOLTAGE PROTECTION DEVICE (OVP)
 - INSTALL (1) PROPOSED HYBRID CABLE

- GROUND SCOPE OF WORK:**
- INSTALL (1) PROPOSED METAL PLATFORM
 - INSTALL (1) PROPOSED ICE BRIDGE
 - INSTALL (1) PROPOSED PPC CABINET
 - INSTALL (1) PROPOSED EQUIPMENT CABINET
 - INSTALL (1) PROPOSED POWER CONDUIT
 - INSTALL (1) PROPOSED TELCO CONDUIT
 - INSTALL (1) PROPOSED TELCO-FIBER BOX
 - INSTALL (1) PROPOSED GPS UNIT
 - INSTALL (1) PROPOSED SAFETY SWITCH (IF REQUIRED)
 - INSTALL (1) PROPOSED CIENA BOX (IF REQUIRED)
 - INSTALL (1) PROPOSED METER SOCKET

SITE PHOTO



UNDERGROUND SERVICE ALERT CBYD 811
UTILITY NOTIFICATION CENTER OF CONNECTICUT
(800) 922-4455
WWW.CBYD.COM
CALL 2 WORKING DAYS UTILITY NOTIFICATION PRIOR TO CONSTRUCTION



GENERAL NOTES

THE FACILITY IS UNMANNED AND NOT FOR HUMAN HABITATION. A TECHNICIAN WILL VISIT THE SITE AS REQUIRED FOR ROUTINE MAINTENANCE. THE PROJECT WILL NOT RESULT IN ANY SIGNIFICANT DISTURBANCE OR EFFECT ON DRAINAGE, NO SANITARY SEWER SERVICE, POTABLE WATER, OR TRASH DISPOSAL IS REQUIRED AND NO COMMERCIAL SIGNAGE IS PROPOSED.

11"x17" PLOT WILL BE HALF SCALE UNLESS OTHERWISE NOTED

CONTRACTOR SHALL VERIFY ALL PLANS, EXISTING DIMENSIONS, AND CONDITIONS ON THE JOB SITE, AND SHALL IMMEDIATELY NOTIFY THE ENGINEER IN WRITING OF ANY DISCREPANCIES BEFORE PROCEEDING WITH THE WORK.

SITE INFORMATION

PROPERTY OWNER: CROWN ATLANTIC COMPANY LLC
ADDRESS: PO BOX 203127
HOUSTON, TX 77216-3127
TOWER TYPE: MONOPOLE
TOWER CO SITE ID: 806358
TOWER APP NUMBER: 553354
COUNTY: NEW HAVEN
LATITUDE (NAD 83): 41° 29' 36.92" N
41.493583 N
LONGITUDE (NAD 83): 73° 9' 54.98" W
73.165278 W
ZONING JURISDICTION: TBD
ZONING DISTRICT: CT CITING COUNSEL
PARCEL NUMBER: SBUR-537700-000000
OCCUPANCY GROUP: U
CONSTRUCTION TYPE: V-B
POWER COMPANY: TBD
TELEPHONE COMPANY: TBD


PROJECT DIRECTORY

APPLICANT: DISH Wireless L.L.C.
5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120
TOWER OWNER: CROWN CASTLE
2000 CORPORATE DRIVE
CANONSBURG, PA 15317
(877) 486-9377
SITE DESIGNER: INFINIGY
2500 W. HIGGINS RD. STE. 500
HOFFMAN ESTATES, IL 60169
(847) 648-4068
SITE ACQUISITION: NICHOLAS CURRY
NICHOLAS.CURRY@CROWNCASTLE.COM
CONSTRUCTION MANAGER: JAVIER SOTO
JAVIER.SOTO@DISH.COM
(617) 839-6514
RF ENGINEER: SYED ZAIDI
SYED.ZAIDI@DISH.COM

DIRECTIONS

DIRECTIONS FROM WATERBURY-OXFORD AIRPORT:
DEPART AND HEAD NORTHWEST ON PROKOP RD, ROAD NAME CHANGES TO JULIANO DR, TURN LEFT ONTO CHRISTIAN ST, TURN RIGHT ONTO OXFORD AIRPORT RD, TURN RIGHT ONTO CT-188 / STRONGTOWN RD TURN LEFT ONTO OLD WATERBURY RD, ARRIVE AT

VICINITY MAP




5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



2000 CORPORATE DRIVE
CANONSBURG, PA 15317



FROM ZERO TO INFINIGY
the solutions are endless
2500 W. HIGGINS RD., SUITE 500 |
HOFFMAN ESTATES, IL 60169
PHONE: 847-648-4068 | FAX: 518-690-0793
WWW.INFINIGY.COM



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
RCD	SS	CJW

RFDS REV #: N/A

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	06/11/2021	ISSUED FOR REVIEW
0	08/23/2021	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
6039-20001C


DISH Wireless L.L.C.
PROJECT INFORMATION
BOHVN00009A
1432 OLD WATERBURY ROAD
SOUTHBURY, CT 06488

SHEET TITLE
TITLE SHEET


SHEET NUMBER
T-1

NOTES

1. CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS.
2. ANTENNAS AND MOUNTS OMITTED FOR CLARITY.




COMPOUND PLAN




1

NOTES


1. CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS.
2. CONTRACTOR SHALL MAINTAIN A 10'-0" MINIMUM SEPARATION BETWEEN THE PROPOSED GPS UNIT, TRANSMITTING ANTENNAS AND EXISTING GPS UNITS.
3. ANTENNAS AND MOUNTS OMITTED FOR CLARITY.




ENLARGED SITE PLAN



2



SITE PLAN



3




5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



2000 CORPORATE DRIVE
CANONSBURG, PA 15317



FROM ZERO TO INFINIGY
the solutions are endless
2500 W. HIGGINS RD., SUITE 500 |
HOFFMAN ESTATES, IL 60169
PHONE: 847-648-4068 | FAX: 518-690-0793
WWW.INFINIGY.COM



8/24/2021
IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY: RCD
CHECKED BY: SS
APPROVED BY: CJW

RFDS REV #: N/A

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	06/11/2021	ISSUED FOR REVIEW
0	08/23/2021	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
6039-20001C


DISH Wireless L.L.C.
PROJECT INFORMATION
BOHVN00009A
1432 OLD WATERBURY ROAD
SOUTHURY, CT 06488

SHEET TITLE
OVERALL AND ENLARGED
SITE PLAN


SHEET NUMBER
A-1

NOTES


1. CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS.
2. ANTENNA SPECIFICATIONS REFER TO ANTENNA SCHEDULE AND TO FINAL CONSTRUCTION RFDS FOR ALL RF DETAILS
3. EXISTING EQUIPMENT AND FENCE OMITTED FOR CLARITY.
4. INFINIGY HAS NOT EVALUATED THE TOWER OR MOUNT STRUCTURE AND ASSUMES NO RESPONSIBILITY FOR THEIR STRUCTURAL INTEGRITY REGARDING PROPOSED LOADINGS. FINAL INSTALLATION SHALL COMPLY WITH RESULTS OF PASSING STRUCTURAL ANALYSES PERFORMED BY OTHERS.




PROPOSED NORTHWEST ELEVATION



1



ANTENNA LAYOUT



2

SECTOR	POSITION	ANTENNA						TRANSMISSION CABLE
		EXISTING OR PROPOSED	MANUFACTURER - MODEL NUMBER	TECHNOLOGY	SIZE (HxW)	AZMUTH	RAD CENTER	FEED LINE TYPE AND LENGTH
ALPHA	A1	PROPOSED	JMA WIRELESS - MX08FRO665-21	5G	72.0" x 20.0"	0°	218'-0"	(1) HIGH-CAPACITY HYBRID CABLE (241' LONG)
BETA	B1	PROPOSED	JMA WIRELESS - MX08FRO665-21	5G	72.0" x 20.0"	120°	218'-0"	
GAMMA	G1	PROPOSED	JMA WIRELESS - MX08FRO665-21	5G	72.0" x 20.0"	240°	218'-0"	

SECTOR	POSITION	RRH		NOTES
		MANUFACTURER - MODEL NUMBER	TECHNOLOGY	
ALPHA	A1	FUJITSU - TA08025-B604	5G	1. CONTRACTOR TO REFER TO FINAL CONSTRUCTION RFDS FOR ALL RF DETAILS. 2. ANTENNA AND RRH MODELS MAY CHANGE DUE TO EQUIPMENT AVAILABILITY. ALL EQUIPMENT CHANGES MUST BE APPROVED AND REMAIN IN COMPLIANCE WITH THE PROPOSED DESIGN AND STRUCTURAL ANALYSES.
	A1	FUJITSU - TA08025-B605	5G	
BETA	B1	FUJITSU - TA08025-B604	5G	
	B1	FUJITSU - TA08025-B605	5G	
GAMMA	G1	FUJITSU - TA08025-B604	5G	
	G1	FUJITSU - TA08025-B605	5G	

ANTENNA SCHEDULE

NO SCALE

3




5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



2000 CORPORATE DRIVE
CANONSBURG, PA 15317



FROM ZERO TO INFINIGY
the solutions are endless
2500 W. HIGGINS RD., SUITE 500 |
HOFFMAN ESTATES, IL 60169
PHONE: 847-648-4068 | FAX: 518-690-0793
WWW.INFINIGY.COM



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY: RCD | CHECKED BY: SS | APPROVED BY: CJW

RFDS REV #: N/A

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	06/11/2021	ISSUED FOR REVIEW
0	08/23/2021	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
6039-20001C

DISH Wireless L.L.C.
PROJECT INFORMATION
BOHVN00009A
1432 OLD WATERBURY ROAD
SOUTHURY, CT 06488

SHEET TITLE
ELEVATION, ANTENNA
LAYOUT AND SCHEDULE

SHEET NUMBER

A-2




5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



2000 CORPORATE DRIVE
CANONSBURG, PA 15317



FROM ZERO TO INFINIGY
the solutions are endless
2500 W. HIGGINS RD., SUITE 500 |
HOFFMAN ESTATES, IL 60169
PHONE: 847-648-4068 | FAX: 518-690-0793
WWW.INFINIGY.COM



8/24/2021
IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY: CHECKED BY: APPROVED BY:
RCD SS CJW

RFDS REV #: N/A

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	06/11/2021	ISSUED FOR REVIEW
0	08/23/2021	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
6039-Z0001C


DISH Wireless L.L.C.
PROJECT INFORMATION
BOHVN00009A
1432 OLD WATERBURY ROAD
SOUTHURY, CT 06488

SHEET TITLE
EQUIPMENT PLATFORM AND
H-FRAME DETAILS


SHEET NUMBER
A-3

NOTES

1. CONTRACTOR TO BURY PLATFORM FEET WITH A MINIMUM OF 2" OF FILL PER EXISTING SITE SURFACE
2. WEED BARRIER FABRIC TO BE ADDED AT DISCRETION OF DISH Wireless L.L.C. CONSTRUCTION MANAGER AT TIME OF CONSTRUCTION. ONE SHEET 8'x8' INSTALLED UNDER ALL FOUR FEET OF THE PLATFORM (4 MIL BLACK PLASTIC)
3. EQUIPMENT CABINET OMITTED FOR CLARITY



PLATFORM EQUIPMENT PLAN




1

**COMMSCOPE MTC4045LP
5X7 PLATFORM**

DIMENSIONS (HxWxD)	16"x84"x60"
TOTAL WEIGHT	423 LBS

NOTE:
GC TO PROVIDE EXTENDED
THREAD FOR PLATFORM IF
REQUIRED HEIGHT EXCEEDS 17"





PLATFORM DETAIL

NO SCALE 2

**COMMSCOPE MTC4045HFLD
H-FRAME**

UNISTRUT/SUPPORT RAILS QTY	5
WEIGHT	59.74 lbs

NOTE:
OR DISH Wireless L.L.C.
APPROVED EQUIVALENT




H-FRAME DETAIL


NO SCALE 3

NOT USED

NO SCALE 4




FRONT ELEVATION




BACK ELEVATION


H-FRAME EQUIPMENT ELEVATION




5




CABINET DETAIL NO SCALE 1



POWER PROTECTION CABINET (PPC) DETAIL NO SCALE 2




SAFETY SWITCH DETAIL NO SCALE 3




METER SOCKET DETAIL NO SCALE 4




NOT USED NO SCALE 5




FIBER TELCO ENCLOSURE DETAIL NO SCALE 6



ICE BRIDGE DETAIL NO SCALE 7



TYPICAL ICE BRIDGE CONCRETE PIER DETAIL NO SCALE 8



HYBRID CABLE RUN NO SCALE 9

5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120

2000 CORPORATE DRIVE
CANONSBURG, PA 15317

FROM ZERO TO INFINIGY

the solutions are endless

2500 W. HIGGINS RD., SUITE 500 |
HOFFMAN ESTATES, IL 60169
PHONE: 847-648-4068 | FAX: 518-690-0793
WWW.INFINIGY.COM

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY: CHECKED BY: APPROVED BY:

RCD SS CJW

RFDS REV #: N/A

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	06/11/2021	ISSUED FOR REVIEW
0	08/23/2021	ISSUED FOR CONSTRUCTION


A&E PROJECT NUMBER
6039-20001C

DISH Wireless L.L.C.
PROJECT INFORMATION
BOHVN00009A
1432 OLD WATERBURY ROAD
SOUTHURY, CT 06488


SHEET TITLE
EQUIPMENT DETAILS

SHEET NUMBER
A-4


PCTEL GPSGL-TMG-SPI-40NCB	
DIMENSIONS (DIAxH) MM/INCH	81x184mm 3.2"x7.25"
WEIGHT W/ACCESSORIES	075 lbs
CONNECTOR	N-FEMALE
FREQUENCY RANGE	1590 ± 30MHz





TOP



BACK



SIDE



GPS DETAIL

NO SCALE

1

GPS MINIMUM SKY VIEW REQUIREMENTS

NO SCALE

2

CABLES UNLIMITED HYBRID CABLE
MINIMUM BEND RADIUSES

NO SCALE

3

NOT USED

NO SCALE

4

NOT USED

NO SCALE

5

NOT USED

NO SCALE

6

NOT USED

NO SCALE

7

NOT USED

NO SCALE

8

NOT USED

NO SCALE

9

dish
wireless.

5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120


CROWN CASTLE

2000 CORPORATE DRIVE
CANONSBURG, PA 15317

INFINIGY

FROM ZERO TO INFINIGY

the solutions are endless
2500 W. HIGGINS RD., SUITE 500 |
HOFFMAN ESTATES, IL 60169
PHONE: 847-648-4068 | FAX: 518-690-0793
WWW.INFINIGY.COM



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY: RCD
CHECKED BY: SS
APPROVED BY: CJW

RFDS REV #: N/A

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	06/11/2021	ISSUED FOR REVIEW
0	06/23/2021	ISSUED FOR CONSTRUCTION


A&E PROJECT NUMBER
6039-Z0001C

DISH Wireless L.L.C.
PROJECT INFORMATION
BOHVN00009A
1432 OLD WATERBURY ROAD
SOUTHURY, CT 06488


SHEET TITLE
EQUIPMENT DETAILS

SHEET NUMBER
A-5

FUJITSU TRIPLE BAND TA08025-B605	
DIMENSIONS (HxWxD)	14.9"x15.7"x9"
WEIGHT	74.95 lbs
CONNECTOR TYPE	4.3-10 RF CONNECTOR
POWER SUPPLY	DC -58~-36V




PLAN



BACK



SIDE




FRONT

RRH DETAIL


NO SCALE

1


FUJITSU DUAL BAND TA08025-B604	
DIMENSIONS (HxWxD)	14.9"x15.7"x7.8"
WEIGHT	63.9 lbs
CONNECTOR TYPE	4.3-10 RF CONNECTOR
POWER SUPPLY	DC -58~-36V




PLAN



BACK



SIDE



FRONT


RRH DETAIL

NO SCALE


2

SABRE DOUBLE Z-BRACKET C10123155	
DIMENSIONS (HxWxD) (1 BRACKET)	5"x20"x1-13/16"
WEIGHT (FULL ASSEMBLY)	35.79 lbs
PACKAGE QUANTITY	4

#	DESCRIPTION
1	PLATE, CHANNEL BRACKET
2	RRH Z BRACKET, 3/16"
3	THREADED ROD ASSEMBLY 1/2"x12"



NOTE:
OR DISH Wireless L.L.C.
APPROVED EQUIVALENT




RRH MOUNT DETAIL


NO SCALE

3


RAYCAP RDIDC-9181-PF-48 DC SURGE PROTECTION (OVP)	
DIMENSIONS (HxWxD)	18.98"x14.39"x8.15"
WEIGHT	21.82 LBS




PLAN



SIDE



BACK




FRONT

SURGE SUPPRESSION DETAIL (OVP)

NO SCALE


4

JMA WIRELESS MX08FR0665-21 ANTENNA	
DIMENSIONS (HxWxD)	72.8"x20.0"x8.0"
TOTAL WEIGHT	64.5 LB
RF PORTS, CONNECTOR TYPE	8 x 4.3-10 FEMALE



BACK

SIDE



FRONT

NOTES

FINAL ANTENNA SPECIFICATIONS
TO BE CONFIRMED BY GC


ANTENNA DETAIL

NO SCALE

5

M04 MOUNTING BRACKET HPA-33R-BUU-H4-K	
WIDTH	5"
DEPTH	2"
HEIGHT	8"
TOTAL WEIGHT	1.5 lbs
HOUSING MATERIAL	ASA/ABS/ALUMINUM
RADOME COLOR	LIGHT GRAY
CONNECTOR	1x8-PIN DAISY CHAIN

NOTE:
OR DISH Wireless L.L.C.
APPROVED EQUIVALENT




ANTENNA MOUNTING DETAIL

NO SCALE

6


COMMSCOPE XP-2040 CROSSOVER PLATE	
DIMENSIONS (HxW)	10"x12"
WEIGHT	11 lbs

NOTE:
OR DISH Wireless L.L.C.
APPROVED EQUIVALENT




PLAN PLATE

SIDE PLATE



PLAN U-BOLT

SIDE U-BOLT




RRH/OVP MOUNT DETAIL

NO SCALE

7

COMMSCOPE MC-PK8-DSH	
FACE WIDTH	96"
WEIGHT	1373.08 lbs
NOTE: 15" TO 38" O.D.	

NOTE:
OR DISH Wireless L.L.C.
APPROVED EQUIVALENT




FACE PIPE

HORIZONTAL PIPE

ANTENNA PIPE

40"
96"



96"

ANTENNA PLATFORM DETAIL

NO SCALE

8

NOT USED

NO SCALE

9

dish
wireless.

5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120


**CROWN
CASTLE**

2000 CORPORATE DRIVE
CANONSBURG, PA 15317

INFINIGY

FROM ZERO TO INFINIGY

the solutions are endless
2500 W. HIGGINS RD., SUITE 500 |
HOFFMAN ESTATES, IL 60169
PHONE: 847-648-4068 | FAX: 518-690-0793
WWW.INFINIGY.COM



IT IS A VIOLATION OF LAW FOR ANY PERSON,
UNLESS THEY ARE ACTING UNDER THE DIRECTION
OF A LICENSED PROFESSIONAL ENGINEER,
TO ALTER THIS DOCUMENT.

DRAWN BY: CHECKED BY: APPROVED BY:

RCD SS CJW

RFDS REV #: N/A

CONSTRUCTION
DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	06/11/2021	ISSUED FOR REVIEW
0	08/23/2021	ISSUED FOR CONSTRUCTION


A&E PROJECT NUMBER
6039-Z0001C

DISH Wireless L.L.C.
PROJECT INFORMATION
BOHVN00009A
1432 OLD WATERBURY ROAD
SOUTHURY, CT 06488

SHEET TITLE
EQUIPMENT DETAILS

SHEET NUMBER

A-6



NOTES


1. CONTRACTOR SHALL FIELD VERIFY ALL PROPOSED UNDERGROUND UTILITY CONDUIT ROUTE.
2. ANTENNAS AND MOUNTS OMITTED FOR CLARITY.

UTILITY ROUTE PLAN

- DC POWER WIRING SHALL BE COLOR CODED AT EACH END FOR IDENTIFYING +24V AND -48V CONDUCTORS. RED MARKINGS SHALL IDENTIFY +24V AND BLUE MARKINGS SHALL IDENTIFY -48V.
1. CONTRACTOR SHALL INSPECT THE EXISTING CONDITIONS PRIOR TO SUBMITTING A BID. ANY QUESTIONS ARISING DURING THE BID PERIOD IN REGARDS TO THE CONTRACTOR'S FUNCTIONS, THE SCOPE OF WORK, OR ANY OTHER ISSUE RELATED TO THIS PROJECT SHALL BE BROUGHT UP DURING THE BID PERIOD WITH THE PROJECT MANAGER FOR CLARIFICATION, NOT AFTER THE CONTRACT HAS BEEN AWARDED.
 2. ALL ELECTRICAL WORK SHALL BE DONE IN ACCORDANCE WITH CURRENT NATIONAL ELECTRICAL CODES AND ALL STATE AND LOCAL CODES, LAWS, AND ORDINANCES. PROVIDE ALL COMPONENTS AND WIRING SIZES AS REQUIRED TO MEET NEC STANDARDS.
 3. LOCATION OF EQUIPMENT, CONDUIT AND DEVICES SHOWN ON THE DRAWINGS ARE APPROXIMATE AND SHALL BE COORDINATED WITH FIELD CONDITIONS PRIOR TO CONSTRUCTION.
 4. CONDUIT ROUGH-IN SHALL BE COORDINATED WITH THE MECHANICAL EQUIPMENT TO AVOID LOCATION CONFLICTS. VERIFY WITH THE MECHANICAL EQUIPMENT CONTRACTOR AND COMPLY AS REQUIRED.
 5. CONTRACTOR SHALL PROVIDE ALL BREAKERS, CONDUITS AND CIRCUITS AS REQUIRED FOR A COMPLETE SYSTEM.
 6. CONTRACTOR SHALL PROVIDE PULL BOXES AND JUNCTION BOXES AS REQUIRED BY THE NEC ARTICLE 314.
 7. CONTRACTOR SHALL PROVIDE ALL STRAIN RELIEF AND CABLE SUPPORTS FOR ALL CABLE ASSEMBLIES. INSTALLATION SHALL BE IN ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS AND RECOMMENDATIONS.
 8. ALL DISCONNECTS AND CONTROLLING DEVICES SHALL BE PROVIDED WITH ENGRAVED PHENOLIC NAMEPLATES INDICATING EQUIPMENT CONTROLLED, BRANCH CIRCUITS INSTALLED ON, AND PANEL FIELD LOCATIONS FED FROM.
 9. INSTALL AN EQUIPMENT GROUNDING CONDUCTOR IN ALL CONDUITS PER THE SPECIFICATIONS AND NEC 250. THE EQUIPMENT GROUNDING CONDUCTORS SHALL BE BONDED AT ALL JUNCTION BOXES, PULL BOXES, AND ALL DISCONNECT SWITCHES, AND EQUIPMENT CABINETS.
 10. ALL NEW MATERIAL SHALL HAVE A U.L. LABEL.
 11. PANEL SCHEDULE LOADING AND CIRCUIT ARRANGEMENTS REFLECT POST-CONSTRUCTION EQUIPMENT.
 12. CONTRACTOR SHALL BE RESPONSIBLE FOR AS-BUILT PANEL SCHEDULE AND SITE DRAWINGS.
 13. ALL TRENCHES IN COMPOUND TO BE HAND DUG

ELECTRICAL NOTES

2



OVERALL UTILITY ROUTE PLAN




5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



2000 CORPORATE DRIVE
CANONSBURG, PA 15317



FROM ZERO TO INFINIGY
the solutions are endless
2500 W. HIGGINS RD., SUITE 500 |
HOFFMAN ESTATES, IL 60169
PHONE: 847-648-4068 | FAX: 518-690-0793
WWW.INFINIGY.COM



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY: RCD | CHECKED BY: SS | APPROVED BY: CJW

RFDS REV #: N/A

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	06/11/2021	ISSUED FOR REVIEW
0	08/23/2021	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
6039-Z0001C


DISH Wireless L.L.C.
PROJECT INFORMATION
BOHVN00009A
1432 OLD WATERBURY ROAD
SOUTHBURY, CT 06488

SHEET TITLE
ELECTRICAL/FIBER ROUTE
PLAN AND NOTES

SHEET NUMBER
E-1

CARLON EXPANSION FITTINGS



COUPLING END PART#	MALE TERMINAL ADAPTER END PART#	SIZE	STD CTN QTY.	TRAVEL LENGTH
E945D	E945DX	1/2"	20	4"
E945E	E945EX	3/4"	15	4"
E945F	E945FX	1"	10	4"
E945G	E945GX	1 1/4"	5	4"
E945H	E945HX	1 1/2"	5	4"
E945J	E945JX	2"	15	8"
E945K	E945KX	2 1/2"	10	8"
E945L	E945LX	3"	10	8"
E945M	E945MX	3 1/2"	5	8"
E945N	E945NX	4"	5	8"
E945P	E945PX	5"	1	8"
E945R	E945RX	6"	1	8"



NOTE: CONTRACTOR TO INSTALL EXPANSION FITTING SLIP JOINT AT METER CENTER CONDUIT TERMINATION, AS PER LOCAL UTILITY POLICY, ORDINANCE AND/OR SPECIFIED REQUIREMENT.

TRENCHING NOTES

- CONTRACTOR SHALL RESTORE THE TRENCH TO ITS ORIGINAL CONDITIONS BY EITHER SEEDING OR SODDING GRASS AREAS, OR REPLACING ASPHALT OR CONCRETE AREAS TO ITS ORIGINAL CROSS SECTION.
- TRENCHING SAFETY; INCLUDING, BUT NOT LIMITED TO SOIL CLASSIFICATION, SLOPING, AND SHORING, SHALL BE GOVERNED BY THE CURRENT OSHA TRENCHING AND EXCAVATION SAFETY STANDARDS.
- ALL CONDUITS SHALL BE INSTALLED IN COMPLIANCE WITH THE CURRENT NATIONAL ELECTRIC CODE (NEC) OR AS REQUIRED BY THE LOCAL JURISDICTION, WHICHEVER IS THE MOST STRINGENT.



EXPANSION JOINT DETAIL


NO SCALE 1

TYPICAL UNDERGROUND TRENCH DETAIL

NO SCALE 2

DARK TELCO BOX – INTERIOR WIRING LAYOUT

NO SCALE 3



NOTE: FIBER PROVIDER WILL NEED TO PROVIDE AN ADDITIONAL 5FT UNISTRUT, 2 U-BOLTS WITH 4 NUTS, IN THE EVENT THE BRACKET SPACING DOESN'T LINE UP WITH CURRENT SPACING BELOW

LIT TELCO BOX – INTERIOR WIRING LAYOUT (OPTIONAL)

NO SCALE 4

NOT USED

NO SCALE 5

NOT USED

NO SCALE 6

NOT USED

NO SCALE 7

NOT USED

NO SCALE 8

NOT USED

NO SCALE 9




5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



2000 CORPORATE DRIVE
CANONSBURG, PA 15317



FROM ZERO TO INFINIGY
the solutions are endless
2500 W. HIGGINS RD., SUITE 500 |
HOFFMAN ESTATES, IL 60169
PHONE: 847-648-4068 | FAX: 518-690-0793
WWW.INFINIGY.COM



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
RCD	SS	CJW
RFDS REV #:	N/A	

CONSTRUCTION DOCUMENTS



SUBMITTALS		
REV	DATE	DESCRIPTION
A	06/11/2021	ISSUED FOR REVIEW
0	08/23/2021	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
6039-Z0001C

DISH Wireless L.L.C.
PROJECT INFORMATION
BOHVN00009A
1432 OLD WATERBURY ROAD
SOUTHBURY, CT 06488

SHEET TITLE
ELECTRICAL
DETAILS

SHEET NUMBER
E-2



NOTES

THE (2) CONDUITS WITH (4) CURRENT CARRYING CONDUCTORS EACH, SHALL APPLY THE ADJUSTMENT FACTOR OF 80% PER 2014/17 NEC TABLE 310.15(B)(3)(g) OR 2020 NEC TABLE 310.15(C)(1) FOR UL1015 WIRE.

#12 FOR 15A-20A/1P BREAKER: 0.8 x 30A = 24.0A
#10 FOR 25A-30A/2P BREAKER: 0.8 x 40A = 32.0A
#8 FOR 35A-40A/2P BREAKER: 0.8 x 55A = 44.0A
#6 FOR 45A-60A/2P BREAKER: 0.8 x 75A = 60.0A

CONDUIT SIZING: AT 40% FILL PER NEC CHAPTER 9, TABLE 4, ARTICLE 358.
0.5" CONDUIT - 0.122 SQ. IN AREA
0.75" CONDUIT - 0.213 SQ. IN AREA
2.0" CONDUIT - 1.316 SQ. IN AREA
3.0" CONDUIT - 2.907 SQ. IN AREA

CABINET CONVENIENCE OUTLET CONDUCTORS (1 CONDUIT): USING THWN-2, CU.
#10 - 0.0211 SQ. IN X 2 = 0.0422 SQ. IN
#10 - 0.0211 SQ. IN X 1 = 0.0211 SQ. IN <GROUND
TOTAL = 0.0633 SQ. IN

0.5" EMT CONDUIT IS ADEQUATE TO HANDLE THE TOTAL OF (3) WIRES, INCLUDING GROUND WIRE, AS INDICATED ABOVE.

RECTIFIER CONDUCTORS (2 CONDUITS): USING UL1015, CU.
#10 - 0.0266 SQ. IN X 4 = 0.1064 SQ. IN
#10 - 0.0082 SQ. IN X 1 = 0.0082 SQ. IN <BARE GROUND
TOTAL = 0.1146 SQ. IN

0.75" EMT CONDUIT IS ADEQUATE TO HANDLE THE TOTAL OF (5) WIRES, INCLUDING GROUND WIRE, AS INDICATED ABOVE.

PPC FEED CONDUCTORS (1 CONDUIT): USING THWN, CU.
3/0 - 0.2679 SQ. IN X 3 = 0.8037 SQ. IN
#6 - 0.0507 SQ. IN X 1 = 0.0507 SQ. IN <GROUND
TOTAL = 0.8544 SQ. IN

3.0" SCH 40 PVC CONDUIT IS ADEQUATE TO HANDLE THE TOTAL OF (4) WIRES, INCLUDING GROUND WIRE, AS INDICATED ABOVE.

PPC ONE-LINE DIAGRAM

NO SCALE 1

PROPOSED CHARLES PANEL SCHEDULE

LOAD SERVED	VOLT AMPS (WATTS)		TRIP	CKT #	PHASE	CKT #	TRIP	VOLT AMPS (WATTS)		LOAD SERVED
	L1	L2						L1	L2	
PPC GFCI OUTLET	180	180	15A	1	A	2	30A	2880	2880	ABB/GE INFINITY RECTIFIER 1
CHARLES GFCI OUTLET			15A	3	B	4	30A	2880	2880	ABB/GE INFINITY RECTIFIER 1
-SPACE-				5	A	6	30A	2880	2880	ABB/GE INFINITY RECTIFIER 2
-SPACE-				7	B	8	30A	2880	2880	ABB/GE INFINITY RECTIFIER 2
-SPACE-				9	A	10	30A	2880	2880	ABB/GE INFINITY RECTIFIER 3
-SPACE-				11	B	12	30A	2880	2880	ABB/GE INFINITY RECTIFIER 3
-SPACE-				13	A	14	30A	2880	2880	ABB/GE INFINITY RECTIFIER 4
-SPACE-				15	B	16	30A	2880	2880	ABB/GE INFINITY RECTIFIER 4
-SPACE-				17	A	18				-SPACE-
-SPACE-				19	B	20				-SPACE-
-SPACE-				21	A	22				-SPACE-
-SPACE-				23	B	24				-SPACE-
VOLTAGE AMPS								11520	11520	
200A MCB, 1ϕ, 24 SPACE, 120/240V				L1	L2					
MB RATING: 65,000 AIC				11700	11700					
				98	98					VOLTAGE AMPS
										AMPS
										MAX AMPS
										MAX 125%

PANEL SCHEDULE

NO SCALE 2

NOT USED

NO SCALE 3




5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



2000 CORPORATE DRIVE
CANONSBURG, PA 15317



FROM ZERO TO INFINIGY
the solutions are endless
2500 W. HIGGINS RD., SUITE 500 |
HOFFMAN ESTATES, IL 60169
PHONE: 847-648-4068 | FAX: 518-690-0793
WWW.INFINIGY.COM



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY: CHECKED BY: APPROVED BY:
RCD SS CJW
RFDS REV #: N/A

CONSTRUCTION DOCUMENTS

SUBMITTALS


REV	DATE	DESCRIPTION
A	06/11/2021	ISSUED FOR REVIEW
0	08/23/2021	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
6039-20001C

DISH Wireless L.L.C.
PROJECT INFORMATION
BOHVN00009A
1432 OLD WATERBURY ROAD
SOUTHBRURY, CT 06488

SHEET TITLE
ELECTRICAL ONE-LINE, FAULT
CALCS & PANEL SCHEDULE

SHEET NUMBER
E-3




TYPICAL EQUIPMENT GROUNDING PLAN

NO SCALE 1


NOTES

1. ANTENNAS AND OVP SHOWN ARE GENERIC AND NOT REFERENCING TO A SPECIFIC MANUFACTURER. THIS LAYOUT IS FOR REFERENCE ONLY



TYPICAL ANTENNA GROUNDING PLAN

NO SCALE 2



GROUNDING LEGEND

1. GROUNDING IS SHOWN DIAGRAMMATICALLY ONLY.
2. CONTRACTOR SHALL GROUND ALL EQUIPMENT AS A COMPLETE SYSTEM. GROUNDING SHALL BE IN COMPLIANCE WITH NEC SECTION 250 AND DISH Wireless L.L.C. GROUNDING AND BONDING REQUIREMENTS AND MANUFACTURER'S SPECIFICATIONS.
3. ALL GROUND CONDUCTORS SHALL BE COPPER; NO ALUMINUM CONDUCTORS SHALL BE USED.

GROUNDING KEY NOTES

- (A) **EXTERIOR GROUND RING:** #2 AWG SOLID COPPER, BURIED AT A DEPTH OF AT LEAST 30 INCHES BELOW GRADE, OR 6 INCHES BELOW THE FROST LINE AND APPROXIMATELY 24 INCHES FROM THE EXTERIOR WALL OR FOOTING.
- (B) **TOWER GROUND RING:** THE GROUND RING SYSTEM SHALL BE INSTALLED AROUND AN ANTENNA TOWER'S LEGS, AND/OR GUY ANCHORS. WHERE SEPARATE SYSTEMS HAVE BEEN PROVIDED FOR THE TOWER AND THE BUILDING, AT LEAST TWO BONDS SHALL BE MADE BETWEEN THE TOWER RING GROUND SYSTEM AND THE BUILDING RING GROUND SYSTEM USING MINIMUM #2 AWG SOLID COPPER CONDUCTORS.
- (C) **INTERIOR GROUND RING:** #2 AWG STRANDED GREEN INSULATED COPPER CONDUCTOR EXTENDED AROUND THE PERIMETER OF THE EQUIPMENT AREA. ALL NON-TELECOMMUNICATIONS RELATED METALLIC OBJECTS FOUND WITHIN A SITE SHALL BE GROUND TO THE INTERIOR GROUND RING WITH #6 AWG STRANDED GREEN INSULATED CONDUCTOR.
- (D) **BOND TO INTERIOR GROUND RING:** #2 AWG SOLID TINNED COPPER WIRE PRIMARY BONDS SHALL BE PROVIDED AT LEAST AT FOUR POINTS ON THE INTERIOR GROUND RING, LOCATED AT THE CORNERS OF THE BUILDING.
- (E) **GROUND ROD:** UL LISTED COPPER CLAD STEEL MINIMUM 1/2" DIAMETER BY EIGHT FEET LONG. GROUND RODS SHALL BE INSTALLED WITH INSPECTION SLEEVES. GROUND RODS SHALL BE DRIVEN TO THE DEPTH OF GROUND RING CONDUCTOR.
- (F) **CELL REFERENCE GROUND BAR:** POINT OF GROUND REFERENCE FOR ALL COMMUNICATIONS EQUIPMENT FRAMES. ALL BONDS ARE MADE WITH #2 AWG UNLESS NOTED OTHERWISE STRANDED GREEN INSULATED COPPER CONDUCTORS. BOND TO GROUND RING WITH (2) #2 SOLID TINNED COPPER CONDUCTORS.
- (G) **HATCH PLATE GROUND BAR:** BOND TO THE INTERIOR GROUND RING WITH TWO #2 AWG STRANDED GREEN INSULATED COPPER CONDUCTORS. WHEN A HATCH-PLATE AND A CELL REFERENCE GROUND BAR ARE BOTH PRESENT, THE CRGB MUST BE CONNECTED TO THE HATCH-PLATE AND TO THE INTERIOR GROUND RING USING (2) TWO #2 AWG STRANDED GREEN INSULATED COPPER CONDUCTORS EACH.
- (H) **EXTERIOR CABLE ENTRY PORT GROUND BARS:** LOCATED AT THE ENTRANCE TO THE CELL SITE BUILDING. BOND TO GROUND RING WITH A #2 AWG SOLID TINNED COPPER CONDUCTORS WITH AN EXOTHERMIC WELD AND INSPECTION SLEEVE.
- (I) **TELCO GROUND BAR:** BOND TO BOTH CELL REFERENCE GROUND BAR OR EXTERIOR GROUND RING.
- (J) **FRAME BONDING:** THE BONDING POINT FOR TELECOM EQUIPMENT FRAMES SHALL BE THE GROUND BUS THAT IS NOT ISOLATED FROM THE EQUIPMENTS METAL FRAMEWORK.
- (K) **INTERIOR UNIT BONDS:** METAL FRAMES, CABINETS AND INDIVIDUAL METALLIC UNITS LOCATED WITH THE AREA OF THE INTERIOR GROUND RING REQUIRE A #6 AWG STRANDED GREEN INSULATED COPPER BOND TO THE INTERIOR GROUND RING.
- (L) **FENCE AND GATE GROUNDING:** METAL FENCES WITHIN 7 FEET OF THE EXTERIOR GROUND RING OR OBJECTS BONDED TO THE EXTERIOR GROUND RING SHALL BE BONDED TO THE GROUND RING WITH A #2 AWG SOLID TINNED COPPER CONDUCTOR AT AN INTERVAL NOT EXCEEDING 25 FEET. BONDS SHALL BE MADE AT EACH GATE POST AND ACROSS GATE OPENINGS.
- (M) **EXTERIOR UNIT BONDS:** METALLIC OBJECTS, EXTERNAL TO OR MOUNTED TO THE BUILDING, SHALL BE BONDED TO THE EXTERIOR GROUND RING. USING #2 TINNED SOLID COPPER WIRE
- (N) **ICE BRIDGE SUPPORTS:** EACH ICE BRIDGE LEG SHALL BE BONDED TO THE GROUND RING WITH #2 AWG BARE TINNED COPPER CONDUCTOR. PROVIDE EXOTHERMIC WELDS AT BOTH THE ICE BRIDGE LEG AND BURIED GROUND RING.
- (O) **DURING ALL DC POWER SYSTEM CHANGES INCLUDING DC SYSTEM CHANGE OUTS, RECTIFIER REPLACEMENTS OR ADDITIONS, BREAKER DISTRIBUTION CHANGES, BATTERY ADDITIONS, BATTERY REPLACEMENTS AND INSTALLATIONS OR CHANGES TO DC CONVERTER SYSTEMS IT SHALL BE REQUIRED THAT SERVICE CONTRACTORS VERIFY ALL DC POWER SYSTEMS ARE EQUIPPED WITH A MASTER DC SYSTEM RETURN GROUND CONDUCTOR FROM THE DC POWER SYSTEM COMMON RETURN BUS DIRECTLY CONNECTED TO THE CELL SITE REFERENCE GROUND BAR**
- (P) **TOWER TOP COLLECTOR BUSS BAR IS TO BE MECHANICALLY BONDED TO PROPOSED ANTENNA MOUNT COLLAR. REFER TO DISH Wireless L.L.C. GROUNDING NOTES.**

GROUNDING KEY NOTES

NO SCALE 3




5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



2000 CORPORATE DRIVE
CANONSBURG, PA 15317



FROM ZERO TO INFINIGY
the solutions are endless
2500 W. HIGGINS RD., SUITE 500 |
HOFFMAN ESTATES, IL 60169
PHONE: 847-648-4068 | FAX: 518-690-0793
WWW.INFINIGY.COM



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY: CHECKED BY: APPROVED BY:
RCD SS CJW

RFDS REV #: N/A

CONSTRUCTION DOCUMENTS


SUBMITTALS		
REV	DATE	DESCRIPTION
A	06/11/2021	ISSUED FOR REVIEW
0	08/23/2021	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
6039-20001C

DISH Wireless L.L.C.
PROJECT INFORMATION
BOHVN00009A
1432 OLD WATERBURY ROAD
SOUTHBURY, CT 06488


SHEET TITLE
GROUNDING PLANS AND NOTES

SHEET NUMBER
G-1




H-FRAME GROUNDING DETAIL

NO SCALE 1




TYPICAL GPS UNIT GROUNDING

NO SCALE 2




OUTDOOR CABINET GROUNDING

NO SCALE 3




TRANSITIONING GROUND DETAIL

NO SCALE 4



TYPICAL TEST GROUND ROD WITH INSPECTION SLEEVE

NO SCALE 5



TYPICAL GROUND RING TRENCH

NO SCALE 6




5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



2000 CORPORATE DRIVE
CANONSBURG, PA 15317



FROM ZERO TO INFINIGY
the solutions are endless
2500 W. HIGGINS RD., SUITE 500 |
HOFFMAN ESTATES, IL 60169
PHONE: 847-648-4068 | FAX: 518-690-0793
WWW.INFINIGY.COM



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY: CHECKED BY: APPROVED BY:
RCD SS CJW

RFDS REV #: N/A

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	06/11/2021	ISSUED FOR REVIEW
0	08/23/2021	ISSUED FOR CONSTRUCTION



A&E PROJECT NUMBER
6039-20001C

DISH Wireless L.L.C.
PROJECT INFORMATION
BOHVN00009A
1432 OLD WATERBURY ROAD
SOUTHURY, CT 06488

SHEET TITLE
GROUNDING DETAILS

SHEET NUMBER
G-2

1. EXOTHERMIC WELD (2) TWO, #2 AWG BARE TINNED SOLID COPPER CONDUCTORS TO GROUND BAR. ROUTE CONDUCTORS TO BURIED GROUND RING AND PROVIDE PARALLEL EXOTHERMIC WELD.
2. ALL EXTERIOR GROUNDING HARDWARE SHALL BE STAINLESS STEEL 3/8" DIAMETER OR LARGER. ALL HARDWARE 18-8 STAINLESS STEEL INCLUDING LOCK WASHERS, COAT ALL SURFACES WITH AN ANTI-OXIDANT COMPOUND BEFORE MATING.
3. FOR GROUND BOND TO STEEL ONLY: COAT ALL SURFACES WITH AN ANTI-OXIDANT COMPOUND BEFORE MATING.
4. DO NOT INSTALL CABLE GROUNDING KIT AT A BEND AND ALWAYS DIRECT GROUND CONDUCTOR DOWN TO GROUNDING BUS.
5. NUT & WASHER SHALL BE PLACED ON THE FRONT SIDE OF THE GROUND BAR AND BOLTED ON THE BACK SIDE.
6. ALL GROUNDING PARTS AND EQUIPMENT TO BE SUPPLIED AND INSTALLED BY CONTRACTOR.
7. THE CONTRACTOR SHALL BE RESPONSIBLE FOR INSTALLING ADDITIONAL GROUND BAR AS REQUIRED.
8. ENSURE THE WIRE INSULATION TERMINATION IS WITHIN 1/8" OF THE BARREL (NO SHINERS).



TYPICAL GROUNDING NOTES


NO SCALE 1

TYPICAL EXTERIOR TWO HOLE LUG

NO SCALE 2

TYPICAL INTERIOR TWO HOLE LUG

NO SCALE 3



LUG DETAIL

NO SCALE 4

NOT USED

NO SCALE 5

NOT USED

NO SCALE 6

NOT USED

NO SCALE 7

NOT USED

NO SCALE 8

NOT USED

NO SCALE 9




5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



2000 CORPORATE DRIVE
CANONSBURG, PA 15317



FROM ZERO TO INFINIGY
the solutions are endless
2500 W. HIGGINS RD., SUITE 500 |
HOFFMAN ESTATES, IL 60169
PHONE: 847-648-4068 | FAX: 518-690-0793
WWW.INFINIGY.COM



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY: RCD
CHECKED BY: SS
APPROVED BY: CJW

RFDS REV #: N/A

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	06/11/2021	ISSUED FOR REVIEW
0	08/23/2021	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
6039-Z0001C

DISH Wireless L.L.C.
PROJECT INFORMATION
BOHVN00009A
1432 OLD WATERBURY ROAD
SOUTHURY, CT 06488

SHEET TITLE
GROUNDING DETAILS

SHEET NUMBER
G-3

RF JUMPER COLOR CODING

3/4" TAPE WIDTHS WITH 3/4" SPACING

LOW-BAND RRH -
(600MHz N71 BASEBAND) +
(850MHz N26 BAND) +
(700MHz N29 BAND) - OPTIONAL PER MARKET

ADD FREQUENCY COLOR TO SECTOR BAND
(CBRS WILL USE YELLOW BANDS)

ALPHA RRH				BETA RRH				GAMMA RRH			
PORT 1 + SLANT	PORT 2 - SLANT	PORT 3 + SLANT	PORT 4 - SLANT	PORT 1 + SLANT	PORT 2 - SLANT	PORT 3 + SLANT	PORT 4 - SLANT	PORT 1 + SLANT	PORT 2 - SLANT	PORT 3 + SLANT	PORT 4 - SLANT
RED	RED	RED	RED	BLUE	BLUE	BLUE	BLUE	GREEN	GREEN	GREEN	GREEN
ORANGE	ORANGE	RED	RED	ORANGE	ORANGE	BLUE	BLUE	ORANGE	ORANGE	GREEN	GREEN
	WHITE (-) PORT	ORANGE	ORANGE		WHITE (-) PORT	ORANGE	ORANGE		WHITE (-) PORT	ORANGE	ORANGE
			WHITE (-) PORT				WHITE (-) PORT				WHITE (-) PORT

MID-BAND RRH -
(AWS BANDS N66+N70)

ADD FREQUENCY COLOR TO SECTOR BAND
(CBRS WILL USE YELLOW BANDS)

RED	RED	RED	RED	BLUE	BLUE	BLUE	BLUE	GREEN	GREEN	GREEN	GREEN
PURPLE	PURPLE	RED	RED	PURPLE	PURPLE	BLUE	BLUE	PURPLE	PURPLE	GREEN	GREEN
	WHITE (-) PORT	PURPLE	PURPLE		WHITE (-) PORT	PURPLE	PURPLE		WHITE (-) PORT	PURPLE	PURPLE
			WHITE (-) PORT				WHITE (-) PORT				WHITE (-) PORT

HYBRID/DISCREET CABLES

INCLUDE SECTOR BANDS BEING SUPPORTED
ALONG WITH FREQUENCY BANDS

EXAMPLE 1 - HYBRID, OR DISCREET, SUPPORTS
ALL SECTORS, BOTH LOW-BANDS AND MID-BANDS

EXAMPLE 2 - HYBRID, OR DISCREET, SUPPORTS
CBRS ONLY, ALL SECTORS

EXAMPLE 1	EXAMPLE 2	EXAMPLE 3
RED	RED	RED
BLUE	BLUE	
GREEN	GREEN	ORANGE
ORANGE	YELLOW	PURPLE
PURPLE		

FIBER JUMPERS TO RRHs

LOW-BAND RRH FIBER CABLES HAVE SECTOR
STRIPE ONLY

LOW BAND RRH	HIGH BAND RRH	LOW BAND RRH	HIGH BAND RRH	LOW BAND RRH	HIGH BAND RRH
RED	RED	BLUE	BLUE	GREEN	GREEN
	PURPLE		PURPLE		PURPLE

POWER CABLES TO RRHs

LOW-BAND RRH POWER CABLES HAVE SECTOR
STRIPE ONLY

LOW BAND RRH	HIGH BAND RRH	LOW BAND RRH	HIGH BAND RRH	LOW BAND RRH	HIGH BAND RRH
RED	RED	BLUE	BLUE	GREEN	GREEN
	PURPLE		PURPLE		PURPLE

RET MOTORS AT ANTENNAS

ANTENNA 1 LOW BAND/ "IN"	ANTENNA 1 HIGH BAND/ "IN"	ANTENNA 1 LOW BAND/ "IN"	ANTENNA 1 HIGH BAND/ "IN"	ANTENNA 1 LOW BAND/ "IN"	ANTENNA 1 HIGH BAND/ "IN"
RED	RED	BLUE	BLUE	GREEN	GREEN
	PURPLE		PURPLE		PURPLE

MICROWAVE RADIO LINKS

LINKS WILL HAVE A 1.5-2 INCH WHITE WRAP WITH
THE AZIMUTH COLOR OVERLAPPING IN THE MIDDLE.
ADD ADDITIONAL SECTOR COLOR BANDS FOR EACH
ADDITIONAL MW RADIO.

MICROWAVE CABLES WILL REQUIRE P-TOUCH
LABELS INSIDE THE CABINET TO IDENTIFY THE
LOCAL AND REMOTE SITE ID'S

FORWARD AZIMUTH OF 0-120 DEGREES		FORWARD AZIMUTH OF 120-240 DEGREES		FORWARD AZIMUTH OF 240-360 DEGREES	
PRIMARY	SECONDARY	PRIMARY	SECONDARY	PRIMARY	SECONDARY
WHITE	WHITE	WHITE	WHITE	WHITE	WHITE
RED	RED	BLUE	BLUE	GREEN	GREEN
WHITE	WHITE	WHITE	WHITE	WHITE	WHITE
	RED		BLUE		GREEN
	WHITE		WHITE		WHITE

RF CABLE COLOR CODES

NO SCALE

1


LOW BANDS (N71+N26)
OPTIONAL - (N29)



AWS
(N66+N70+H-BLOCK)



CBRS TECH
(3 GHz)



NEGATIVE SLANT PORT
ON ANT/RRH



ALPHA SECTOR



BETA SECTOR



GAMMA SECTOR



COLOR IDENTIFIER

NO SCALE

2

NOT USED

NO SCALE

3

NOT USED

NO SCALE

4

dish
wireless.

5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120


CROWN
CASTLE

2000 CORPORATE DRIVE
CANONSBURG, PA 15317

INFINIGY

FROM ZERO TO INFINIGY

the solutions are endless
2500 W. HIGGINS RD., SUITE 500 |
HOFFMAN ESTATES, IL 60169
PHONE: 847-648-4068 | FAX: 518-690-0793
WWW.INFINIGY.COM



IT IS A VIOLATION OF LAW FOR ANY PERSON,
UNLESS THEY ARE ACTING UNDER THE DIRECTION
OF A LICENSED PROFESSIONAL ENGINEER,
TO ALTER THIS DOCUMENT.

DRAWN BY: CHECKED BY: APPROVED BY:

RCD SS CJW

RFDS REV #: N/A

CONSTRUCTION
DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	06/11/2021	ISSUED FOR REVIEW
0	08/23/2021	ISSUED FOR CONSTRUCTION


A&E PROJECT NUMBER
6039-20001C

DISH Wireless L.L.C.
PROJECT INFORMATION
BOHVN00009A
1432 OLD WATERBURY ROAD
SOUTHURY, CT 06488


SHEET TITLE
RF
CABLE COLOR CODES

SHEET NUMBER
RF-1

EXOTHERMIC CONNECTION
 MECHANICAL CONNECTION
 BUSS BAR INSULATOR
 CHEMICAL ELECTROLYTIC GROUNDING SYSTEM
 TEST CHEMICAL ELECTROLYTIC GROUNDING SYSTEM
 EXOTHERMIC WITH INSPECTION SLEEVE
 GROUNDING BAR
 GROUND ROD
 TEST GROUND ROD WITH INSPECTION SLEEVE
 SINGLE POLE SWITCH
 DUPLEX RECEPTACLE
 DUPLEX GFCI RECEPTACLE
 FLUORESCENT LIGHTING FIXTURE (2) TWO LAMPS 48-T8
 SMOKE DETECTION (DC)
 EMERGENCY LIGHTING (DC)
 SECURITY LIGHT W/PHOTOCELL LITHONIA ALXW
 LED-1-25A400/51K-SR4-120-PE-DOBTD
 CHAIN LINK FENCE
 WOOD/WROUGHT IRON FENCE
 WALL STRUCTURE
 LEASE AREA
 PROPERTY LINE (PL)
 SETBACKS
 ICE BRIDGE
 CABLE TRAY
 WATER LINE
 UNDERGROUND POWER
 UNDERGROUND TELCO
 OVERHEAD POWER
 OVERHEAD TELCO
 UNDERGROUND TELCO/POWER
 ABOVE GROUND POWER
 ABOVE GROUND TELCO
 ABOVE GROUND TELCO/POWER
 WORKPOINT



SECTION REFERENCE
 DETAIL REFERENCE



LEGEND

AB ANCHOR BOLT	IN INCH
ABV ABOVE	INT INTERIOR
AC ALTERNATING CURRENT	LB(S) POUND(S)
ADDL ADDITIONAL	LF LINEAR FEET
AFF ABOVE FINISHED FLOOR	LTE LONG TERM EVOLUTION
AFG ABOVE FINISHED GRADE	MAS MASONRY
AGL ABOVE GROUND LEVEL	MAX MAXIMUM
AIC AMPERAGE INTERRUPTION CAPACITY	MB MACHINE BOLT
ALUM ALUMINUM	MECH MECHANICAL
ALT ALTERNATE	MFR MANUFACTURER
ANT ANTENNA	MGB MASTER GROUND BAR
APPROX APPROXIMATE	MIN MINIMUM
ARCH ARCHITECTURAL	MISC MISCELLANEOUS
ATS AUTOMATIC TRANSFER SWITCH	MTL METAL
AWG AMERICAN WIRE GAUGE	MTS MANUAL TRANSFER SWITCH
BATT BATTERY	MW MICROWAVE
BLDG BUILDING	NEC NATIONAL ELECTRIC CODE
BLK BLOCK	NM NEWTON METERS
BLKG BLOCKING	NO. NUMBER
BM BEAM	# NUMBER
BTC BARE TINNED COPPER CONDUCTOR	NTS NOT TO SCALE
BOF BOTTOM OF FOOTING	OC ON-CENTER
CAB CABINET	OSHA OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION
CANT CANTILEVERED	OPNG OPENING
CHG CHARGING	P/C PRECAST CONCRETE
CLG CEILING	PCS PERSONAL COMMUNICATION SERVICES
CLR CLEAR	PCU PRIMARY CONTROL UNIT
COL COLUMN	PRC PRIMARY RADIO CABINET
COMM COMMON	PP POLARIZING PRESERVING
CONC CONCRETE	PSF POUNDS PER SQUARE FOOT
CONSTR CONSTRUCTION	PSI POUNDS PER SQUARE INCH
DBL DOUBLE	PT PRESSURE TREATED
DC DIRECT CURRENT	PWR POWER CABINET
DEPT DEPARTMENT	QTY QUANTITY
DF DOUGLAS FIR	RAD RADIUS
DIA DIAMETER	RECT RECTIFIER
DIAG DIAGONAL	REF REFERENCE
DIM DIMENSION	REINF REINFORCEMENT
DWG DRAWING	REQ'D REQUIRED
DWL DOWEL	RET REMOTE ELECTRIC TILT
EA EACH	RF RADIO FREQUENCY
EC ELECTRICAL CONDUCTOR	RMC RIGID METALLIC CONDUIT
EL ELEVATION	RRH REMOTE RADIO HEAD
ELEC ELECTRICAL	RRU REMOTE RADIO UNIT
EMT ELECTRICAL METALLIC TUBING	RWY RACEWAY
ENG ENGINEER	SCH SCHEDULE
EQ EQUAL	SHT SHEET
EXP EXPANSION	SIAD SMART INTEGRATED ACCESS DEVICE
EXT EXTERIOR	SIM SIMILAR
EW EACH WAY	SPEC SPECIFICATION
FAB FABRICATION	SQ SQUARE
FF FINISH FLOOR	SS STAINLESS STEEL
FG FINISH GRADE	STD STANDARD
FIF FACILITY INTERFACE FRAME	STL STEEL
FIN FINISH(ED)	TEMP TEMPORARY
FLR FLOOR	THK THICKNESS
FDN FOUNDATION	TMA TOWER MOUNTED AMPLIFIER
FOC FACE OF CONCRETE	TN TOE NAIL
FOM FACE OF MASONRY	TOA TOP OF ANTENNA
FOS FACE OF STUD	TOC TOP OF CURB
FOW FACE OF WALL	TOF TOP OF FOUNDATION
FS FINISH SURFACE	TOP TOP OF PLATE (PARAPET)
FT FOOT	TOS TOP OF STEEL
FTG FOOTING	TOW TOP OF WALL
GA GAUGE	TVSS TRANSIENT VOLTAGE SURGE SUPPRESSION
GEN GENERATOR	TYP TYPICAL
GFCI GROUND FAULT CIRCUIT INTERRUPTER	UG UNDERGROUND
GLB GLUE LAMINATED BEAM	UL UNDERWRITERS LABORATORY
GLV GALVANIZED	UNO UNLESS NOTED OTHERWISE
GPS GLOBAL POSITIONING SYSTEM	UMTS UNIVERSAL MOBILE TELECOMMUNICATIONS SYSTEM
GND GROUND	UPS UNINTERRUPTIBLE POWER SYSTEM (DC POWER PLANT)
GSM GLOBAL SYSTEM FOR MOBILE	VIF VERIFIED IN FIELD
HDG HOT DIPPED GALVANIZED	W WIDE
HDR HEADER	W/ WITH
HGR HANGER	WD WOOD
HVAC HEAT/VENTILATION/AIR CONDITIONING	WP WEATHERPROOF
HT HEIGHT	WT WEIGHT
IGR INTERIOR GROUND RING	

ABBREVIATIONS




5701 SOUTH SANTA FE DRIVE
 LITTLETON, CO 80120



2000 CORPORATE DRIVE
 CANONSBURG, PA 15317



the solutions are endless
 2500 W. HIGGINS RD., SUITE 500 |
 HOFFMAN ESTATES, IL 60169
 PHONE: 847-648-4068 | FAX: 518-690-0793
 WWW.INFINIGY.COM



IT IS A VIOLATION OF LAW FOR ANY PERSON,
 UNLESS THEY ARE ACTING UNDER THE DIRECTION
 OF A LICENSED PROFESSIONAL ENGINEER,
 TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
RCD	SS	CJW

RFDS REV #: N/A

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	06/11/2021	ISSUED FOR REVIEW
0	08/23/2021	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
 6039-20001C

DISH Wireless L.L.C.
 PROJECT INFORMATION
 BOHVN00009A
 1432 OLD WATERBURY ROAD
 SOUTHURY, CT 06488

SHEET TITLE
 LEGEND AND ABBREVIATIONS

SHEET NUMBER
GN-1

SITE ACTIVITY REQUIREMENTS:

1. NOTICE TO PROCEED – NO WORK SHALL COMMENCE PRIOR TO CONTRACTOR RECEIVING A WRITTEN NOTICE TO PROCEED (NTP) AND THE ISSUANCE OF A PURCHASE ORDER. PRIOR TO ACCESSING/ENTERING THE SITE YOU MUST CONTACT THE DISH Wireless L.L.C. AND TOWER OWNER NOC & THE DISH Wireless L.L.C. AND TOWER OWNER CONSTRUCTION MANAGER.
2. "LOOK UP" – DISH Wireless L.L.C. AND TOWER OWNER SAFETY CLIMB REQUIREMENT:
THE INTEGRITY OF THE SAFETY CLIMB AND ALL COMPONENTS OF THE CLIMBING FACILITY SHALL BE CONSIDERED DURING ALL STAGES OF DESIGN, INSTALLATION, AND INSPECTION. TOWER MODIFICATION, MOUNT REINFORCEMENTS, AND/OR EQUIPMENT INSTALLATIONS SHALL NOT COMPROMISE THE INTEGRITY OR FUNCTIONAL USE OF THE SAFETY CLIMB OR ANY COMPONENTS OF THE CLIMBING FACILITY ON THE STRUCTURE. THIS SHALL INCLUDE, BUT NOT BE LIMITED TO: PINCHING OF THE WIRE ROPE, BENDING OF THE WIRE ROPE FROM ITS SUPPORTS, DIRECT CONTACT OR CLOSE PROXIMITY TO THE WIRE ROPE WHICH MAY CAUSE FRICTIONAL WEAR, IMPACT TO THE ANCHORAGE POINTS IN ANY WAY, OR TO IMPEDE/BLOCK ITS INTENDED USE. ANY COMPROMISED SAFETY CLIMB, INCLUDING EXISTING CONDITIONS MUST BE TAGGED OUT AND REPORTED TO YOUR DISH Wireless L.L.C. AND DISH Wireless L.L.C. AND TOWER OWNER POC OR CALL THE NOC TO GENERATE A SAFETY CLIMB MAINTENANCE AND CONTRACTOR NOTICE TICKET.
3. PRIOR TO THE START OF CONSTRUCTION, ALL REQUIRED JURISDICTIONAL PERMITS SHALL BE OBTAINED. THIS INCLUDES, BUT IS NOT LIMITED TO, BUILDING, ELECTRICAL, MECHANICAL, FIRE, FLOOD ZONE, ENVIRONMENTAL, AND ZONING. AFTER ONSITE ACTIVITIES AND CONSTRUCTION ARE COMPLETED, ALL REQUIRED PERMITS SHALL BE SATISFIED AND CLOSED OUT ACCORDING TO LOCAL JURISDICTIONAL REQUIREMENTS.
4. ALL CONSTRUCTION MEANS AND METHODS; INCLUDING BUT NOT LIMITED TO, ERECTION PLANS, RIGGING PLANS, CLIMBING PLANS, AND RESCUE PLANS SHALL BE THE RESPONSIBILITY OF THE GENERAL CONTRACTOR RESPONSIBLE FOR THE EXECUTION OF THE WORK CONTAINED HEREIN, AND SHALL MEET ANSI/ASSE A10.48 (LATEST EDITION); FEDERAL, STATE, AND LOCAL REGULATIONS; AND ANY APPLICABLE INDUSTRY CONSENSUS STANDARDS RELATED TO THE CONSTRUCTION ACTIVITIES BEING PERFORMED. ALL RIGGING PLANS SHALL ADHERE TO ANSI/ASSE A10.48 (LATEST EDITION) AND DISH Wireless L.L.C. AND TOWER OWNER STANDARDS, INCLUDING THE REQUIRED INVOLVEMENT OF A QUALIFIED ENGINEER FOR CLASS IV CONSTRUCTION, TO CERTIFY THE SUPPORTING STRUCTURE(S) IN ACCORDANCE WITH ANSI/TIA-322 (LATEST EDITION).
5. ALL SITE WORK TO COMPLY WITH DISH Wireless L.L.C. AND TOWER OWNER INSTALLATION STANDARDS FOR CONSTRUCTION ACTIVITIES ON DISH Wireless L.L.C. AND TOWER OWNER TOWER SITE AND LATEST VERSION OF ANSI/TIA-1019-A-2012 "STANDARD FOR INSTALLATION, ALTERATION, AND MAINTENANCE OF ANTENNA SUPPORTING STRUCTURES AND ANTENNAS."
6. IF THE SPECIFIED EQUIPMENT CAN NOT BE INSTALLED AS SHOWN ON THESE DRAWINGS, THE CONTRACTOR SHALL PROPOSE AN ALTERNATIVE INSTALLATION FOR APPROVAL BY DISH Wireless L.L.C. AND TOWER OWNER PRIOR TO PROCEEDING WITH ANY SUCH CHANGE OF INSTALLATION.
7. ALL MATERIALS FURNISHED AND INSTALLED SHALL BE IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS AND ORDINANCES. CONTRACTOR SHALL ISSUE ALL APPROPRIATE NOTICES AND COMPLY WITH ALL LAWS, ORDINANCES, RULES, REGULATIONS AND LAWFUL ORDERS OF ANY PUBLIC AUTHORITY REGARDING THE PERFORMANCE OF THE WORK. ALL WORK CARRIED OUT SHALL COMPLY WITH ALL APPLICABLE MUNICIPAL AND UTILITY COMPANY SPECIFICATIONS AND LOCAL JURISDICTIONAL CODES, ORDINANCES AND APPLICABLE REGULATIONS.
8. THE CONTRACTOR SHALL INSTALL ALL EQUIPMENT AND MATERIALS IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS UNLESS SPECIFICALLY STATED OTHERWISE.
9. THE CONTRACTOR SHALL CONTACT UTILITY LOCATING SERVICES INCLUDING PRIVATE LOCATES SERVICES PRIOR TO THE START OF CONSTRUCTION.
10. ALL EXISTING ACTIVE SEWER, WATER, GAS, ELECTRIC AND OTHER UTILITIES WHERE ENCOUNTERED IN THE WORK, SHALL BE PROTECTED AT ALL TIMES AND WHERE REQUIRED FOR THE PROPER EXECUTION OF THE WORK, SHALL BE RELOCATED AS DIRECTED BY CONTRACTOR. EXTREME CAUTION SHOULD BE USED BY THE CONTRACTOR WHEN EXCAVATING OR DRILLING PIERS AROUND OR NEAR UTILITIES. CONTRACTOR SHALL PROVIDE SAFETY TRAINING FOR THE WORKING CREW. THIS WILL INCLUDE BUT NOT BE LIMITED TO A) FALL PROTECTION B) CONFINED SPACE C) ELECTRICAL SAFETY D) TRENCHING AND EXCAVATION E) CONSTRUCTION SAFETY PROCEDURES.
11. ALL SITE WORK SHALL BE AS INDICATED ON THE STAMPED CONSTRUCTION DRAWINGS AND DISH PROJECT SPECIFICATIONS, LATEST APPROVED REVISION.
12. CONTRACTOR SHALL KEEP THE SITE FREE FROM ACCUMULATING WASTE MATERIAL, DEBRIS, AND TRASH AT THE COMPLETION OF THE WORK. IF NECESSARY, RUBBISH, STUMPS, DEBRIS, STICKS, STONES AND OTHER REFUSE SHALL BE REMOVED FROM THE SITE AND DISPOSED OF LEGALLY.
13. ALL EXISTING INACTIVE SEWER, WATER, GAS, ELECTRIC AND OTHER UTILITIES, WHICH INTERFERE WITH THE EXECUTION OF THE WORK, SHALL BE REMOVED AND/OR CAPPED, PLUGGED OR OTHERWISE DISCONTINUED AT POINTS WHICH WILL NOT INTERFERE WITH THE EXECUTION OF THE WORK, SUBJECT TO THE APPROVAL OF DISH Wireless L.L.C. AND TOWER OWNER, AND/OR LOCAL UTILITIES.
14. THE CONTRACTOR SHALL PROVIDE SITE SIGNAGE IN ACCORDANCE WITH THE TECHNICAL SPECIFICATION FOR SITE SIGNAGE REQUIRED BY LOCAL JURISDICTION AND SIGNAGE REQUIRED ON INDIVIDUAL PIECES OF EQUIPMENT, ROOMS, AND SHELTERS.
15. THE SITE SHALL BE GRADED TO CAUSE SURFACE WATER TO FLOW AWAY FROM THE CARRIER'S EQUIPMENT AND TOWER AREAS.
16. THE SUB GRADE SHALL BE COMPACTED AND BROUGHT TO A SMOOTH UNIFORM GRADE PRIOR TO FINISHED SURFACE APPLICATION.
17. THE AREAS OF THE OWNERS PROPERTY DISTURBED BY THE WORK AND NOT COVERED BY THE TOWER, EQUIPMENT OR DRIVEWAY, SHALL BE GRADED TO A UNIFORM SLOPE, AND STABILIZED TO PREVENT EROSION AS SPECIFIED ON THE CONSTRUCTION DRAWINGS AND/OR PROJECT SPECIFICATIONS.
18. CONTRACTOR SHALL MINIMIZE DISTURBANCE TO EXISTING SITE DURING CONSTRUCTION. EROSION CONTROL MEASURES, IF REQUIRED DURING CONSTRUCTION, SHALL BE IN CONFORMANCE WITH THE LOCAL GUIDELINES FOR EROSION AND SEDIMENT CONTROL.
19. THE CONTRACTOR SHALL PROTECT EXISTING IMPROVEMENTS, PAVEMENTS, CURBS, LANDSCAPING AND STRUCTURES. ANY DAMAGED PART SHALL BE REPAIRED AT CONTRACTOR'S EXPENSE TO THE SATISFACTION OF OWNER.
20. CONTRACTOR SHALL LEGALLY AND PROPERLY DISPOSE OF ALL SCRAP MATERIALS SUCH AS COAXIAL CABLES AND OTHER ITEMS REMOVED FROM THE EXISTING FACILITY. ANTENNAS AND RADIOS REMOVED SHALL BE RETURNED TO THE OWNER'S DESIGNATED LOCATION.
21. CONTRACTOR SHALL LEAVE PREMISES IN CLEAN CONDITION. TRASH AND DEBRIS SHOULD BE REMOVED FROM SITE ON A DAILY BASIS.
22. NO FILL OR EMBANKMENT MATERIAL SHALL BE PLACED ON FROZEN GROUND. FROZEN MATERIALS, SNOW OR ICE SHALL NOT BE PLACED IN ANY FILL OR EMBANKMENT.

GENERAL NOTES:

- 1.FOR THE PURPOSE OF CONSTRUCTION DRAWING, THE FOLLOWING DEFINITIONS SHALL APPLY:
CONTRACTOR:GENERAL CONTRACTOR RESPONSIBLE FOR CONSTRUCTION
CARRIER:DISH Wireless L.L.C.
TOWER OWNER:TOWER OWNER
2. THESE DRAWINGS HAVE BEEN PREPARED USING STANDARDS OF PROFESSIONAL CARE AND COMPLETENESS NORMALLY EXERCISED UNDER SIMILAR CIRCUMSTANCES BY REPUTABLE ENGINEERS IN THIS OR SIMILAR LOCALITIES. IT IS ASSUMED THAT THE WORK DEPICTED WILL BE PERFORMED BY AN EXPERIENCED CONTRACTOR AND/OR WORKPEOPLE WHO HAVE A WORKING KNOWLEDGE OF THE APPLICABLE CODE STANDARDS AND REQUIREMENTS AND OF INDUSTRY ACCEPTED STANDARD GOOD PRACTICE. AS NOT EVERY CONDITION OR ELEMENT IS (OR CAN BE) EXPLICITLY SHOWN ON THESE DRAWINGS, THE CONTRACTOR SHALL USE INDUSTRY ACCEPTED STANDARD GOOD PRACTICE FOR MISCELLANEOUS WORK NOT EXPLICITLY SHOWN.
3. THESE DRAWINGS REPRESENT THE FINISHED STRUCTURE. THEY DO NOT INDICATE THE MEANS OR METHODS OF CONSTRUCTION. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR THE CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES. THE CONTRACTOR SHALL PROVIDE ALL MEASURES NECESSARY FOR PROTECTION OF LIFE AND PROPERTY DURING CONSTRUCTION. SUCH MEASURES SHALL INCLUDE, BUT NOT BE LIMITED TO, BRACING, FORMWORK, SHORING, ETC. SITE VISITS BY THE ENGINEER OR HIS REPRESENTATIVE WILL NOT INCLUDE INSPECTION OF THESE ITEMS AND IS FOR STRUCTURAL OBSERVATION OF THE FINISHED STRUCTURE ONLY.
4. NOTES AND DETAILS IN THE CONSTRUCTION DRAWINGS SHALL TAKE PRECEDENCE OVER GENERAL NOTES AND TYPICAL DETAILS. WHERE NO DETAILS ARE SHOWN, CONSTRUCTION SHALL CONFORM TO SIMILAR WORK ON THE PROJECT, AND/OR AS PROVIDED FOR IN THE CONTRACT DOCUMENTS. WHERE DISCREPANCIES OCCUR BETWEEN PLANS, DETAILS, GENERAL NOTES, AND SPECIFICATIONS, THE GREATER, MORE STRICT REQUIREMENTS, SHALL GOVERN. IF FURTHER CLARIFICATION IS REQUIRED CONTACT THE ENGINEER OF RECORD.
5. SUBSTANTIAL EFFORT HAS BEEN MADE TO PROVIDE ACCURATE DIMENSIONS AND MEASUREMENTS ON THE DRAWINGS TO ASSIST IN THE FABRICATION AND/OR PLACEMENT OF CONSTRUCTION ELEMENTS BUT IT IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR TO FIELD VERIFY THE DIMENSIONS, MEASUREMENTS, AND/OR CLEARANCES SHOWN IN THE CONSTRUCTION DRAWINGS PRIOR TO FABRICATION OR CUTTING OF ANY NEW OR EXISTING CONSTRUCTION ELEMENTS. IF IT IS DETERMINED THAT THERE ARE DISCREPANCIES AND/OR CONFLICTS WITH THE CONSTRUCTION DRAWINGS THE ENGINEER OF RECORD IS TO BE NOTIFIED AS SOON AS POSSIBLE.
6. PRIOR TO THE SUBMISSION OF BIDS, THE BIDDING CONTRACTOR SHALL VISIT THE CELL SITE TO FAMILIARIZE WITH THE EXISTING CONDITIONS AND TO CONFIRM THAT THE WORK CAN BE ACCOMPLISHED AS SHOWN ON THE CONSTRUCTION DRAWINGS. ANY DISCREPANCY FOUND SHALL BE BROUGHT TO THE ATTENTION OF CARRIER POC AND TOWER OWNER.
7. ALL MATERIALS FURNISHED AND INSTALLED SHALL BE IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS AND ORDINANCES. CONTRACTOR SHALL ISSUE ALL APPROPRIATE NOTICES AND COMPLY WITH ALL LAWS, ORDINANCES, RULES, REGULATIONS AND LAWFUL ORDERS OF ANY PUBLIC AUTHORITY REGARDING THE PERFORMANCE OF THE WORK. ALL WORK CARRIED OUT SHALL COMPLY WITH ALL APPLICABLE MUNICIPAL AND UTILITY COMPANY SPECIFICATIONS AND LOCAL JURISDICTIONAL CODES, ORDINANCES AND APPLICABLE REGULATIONS.
8. UNLESS NOTED OTHERWISE, THE WORK SHALL INCLUDE FURNISHING MATERIALS, EQUIPMENT, APPURTENANCES AND LABOR NECESSARY TO COMPLETE ALL INSTALLATIONS AS INDICATED ON THE DRAWINGS.
9. THE CONTRACTOR SHALL INSTALL ALL EQUIPMENT AND MATERIALS IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS UNLESS SPECIFICALLY STATED OTHERWISE.
10. IF THE SPECIFIED EQUIPMENT CAN NOT BE INSTALLED AS SHOWN ON THESE DRAWINGS, THE CONTRACTOR SHALL PROPOSE AN ALTERNATIVE INSTALLATION FOR APPROVAL BY THE CARRIER AND TOWER OWNER PRIOR TO PROCEEDING WITH ANY SUCH CHANGE OF INSTALLATION.
11. CONTRACTOR IS TO PERFORM A SITE INVESTIGATION, BEFORE SUBMITTING BIDS, TO DETERMINE THE BEST ROUTING OF ALL CONDUITS FOR POWER, AND TELCO AND FOR GROUNDING CABLES AS SHOWN IN THE POWER, TELCO, AND GROUNDING PLAN DRAWINGS.
12. THE CONTRACTOR SHALL PROTECT EXISTING IMPROVEMENTS, PAVEMENTS, CURBS, LANDSCAPING AND STRUCTURES. ANY DAMAGED PART SHALL BE REPAIRED AT CONTRACTOR'S EXPENSE TO THE SATISFACTION OF DISH Wireless L.L.C. AND TOWER OWNER
13. CONTRACTOR SHALL LEGALLY AND PROPERLY DISPOSE OF ALL SCRAP MATERIALS SUCH AS COAXIAL CABLES AND OTHER ITEMS REMOVED FROM THE EXISTING FACILITY. ANTENNAS REMOVED SHALL BE RETURNED TO THE OWNER'S DESIGNATED LOCATION.
14. CONTRACTOR SHALL LEAVE PREMISES IN CLEAN CONDITION. TRASH AND DEBRIS SHOULD BE REMOVED FROM SITE ON A DAILY BASIS.




5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



2000 CORPORATE DRIVE
CANONSBURG, PA 15317



FROM ZERO TO INFINIGY
the solutions are endless
2500 W. HIGGINS RD., SUITE 500 |
HOFFMAN ESTATES, IL 60169
PHONE: 847-648-4068 | FAX: 518-690-0793
WWW.INFINIGY.COM



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
RCD	SS	CJW

RFDS REV #: N/A

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	06/11/2021	ISSUED FOR REVIEW
0	08/23/2021	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
6039-20001C

DISH Wireless L.L.C.
PROJECT INFORMATION
BOHVN00009A
1432 OLD WATERBURY ROAD
SOUTHBURY, CT 06488

SHEET TITLE
GENERAL NOTES

SHEET NUMBER
GN-2

CONCRETE, FOUNDATIONS, AND REINFORCING STEEL:

1. ALL CONCRETE WORK SHALL BE IN ACCORDANCE WITH THE ACI 301, ACI 318, ACI 336, ASTM A184, ASTM A185 AND THE DESIGN AND CONSTRUCTION SPECIFICATION FOR CAST-IN-PLACE CONCRETE.
2. UNLESS NOTED OTHERWISE, SOIL BEARING PRESSURE USED FOR DESIGN OF SLABS AND FOUNDATIONS IS ASSUMED TO BE 1000 psf.
3. ALL CONCRETE SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH (f'c) OF 3000 psi AT 28 DAYS, UNLESS NOTED OTHERWISE. NO MORE THAN 90 MINUTES SHALL ELAPSE FROM BATCH TIME TO TIME OF PLACEMENT UNLESS APPROVED BY THE ENGINEER OF RECORD. TEMPERATURE OF CONCRETE SHALL NOT EXCEED 90°F AT TIME OF PLACEMENT.
4. CONCRETE EXPOSED TO FREEZE-THAW CYCLES SHALL CONTAIN AIR ENTRAINING ADMIXTURES. AMOUNT OF AIR ENTRAINMENT TO BE BASED ON SIZE OF AGGREGATE AND F3 CLASS EXPOSURE (VERY SEVERE). CEMENT USED TO BE TYPE II PORTLAND CEMENT WITH A MAXIMUM WATER-TO-CEMENT RATIO (W/C) OF 0.45.
5. ALL STEEL REINFORCING SHALL CONFORM TO ASTM A615. ALL WELDED WIRE FABRIC (WWF) SHALL CONFORM TO ASTM A185. ALL SPLICES SHALL BE CLASS "B" TENSION SPLICES, UNLESS NOTED OTHERWISE. ALL HOOKS SHALL BE STANDARD 90 DEGREE HOOKS, UNLESS NOTED OTHERWISE. YIELD STRENGTH (Fy) OF STANDARD DEFORMED BARS ARE AS FOLLOWS:
 #4 BARS AND SMALLER 40 ksi
 #5 BARS AND LARGER 60 ksi
6. THE FOLLOWING MINIMUM CONCRETE COVER SHALL BE PROVIDED FOR REINFORCING STEEL UNLESS SHOWN OTHERWISE ON DRAWINGS:
 - CONCRETE CAST AGAINST AND PERMANENTLY EXPOSED TO EARTH 3"
 - CONCRETE EXPOSED TO EARTH OR WEATHER:
 - #6 BARS AND LARGER 2"
 - #5 BARS AND SMALLER 1-1/2"
 - CONCRETE NOT EXPOSED TO EARTH OR WEATHER:
 - SLAB AND WALLS 3/4"
 - BEAMS AND COLUMNS 1-1/2"
7. A TOOLED EDGE OR A 3/4" CHAMFER SHALL BE PROVIDED AT ALL EXPOSED EDGES OF CONCRETE, UNLESS NOTED OTHERWISE, IN ACCORDANCE WITH ACI 301 SECTION 4.2.4.

ELECTRICAL INSTALLATION NOTES:

1. ALL ELECTRICAL WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS, NEC AND ALL APPLICABLE FEDERAL, STATE, AND LOCAL CODES/ORDINANCES.
2. CONDUIT ROUTINGS ARE SCHEMATIC. CONTRACTOR SHALL INSTALL CONDUITS SO THAT ACCESS TO EQUIPMENT IS NOT BLOCKED AND TRIP HAZARDS ARE ELIMINATED.
3. WIRING, RACEWAY AND SUPPORT METHODS AND MATERIALS SHALL COMPLY WITH THE REQUIREMENTS OF THE NEC.
4. ALL CIRCUITS SHALL BE SEGREGATED AND MAINTAIN MINIMUM CABLE SEPARATION AS REQUIRED BY THE NEC.
- 4.1. ALL EQUIPMENT SHALL BEAR THE UNDERWRITERS LABORATORIES LABEL OF APPROVAL, AND SHALL CONFORM TO REQUIREMENT OF THE NATIONAL ELECTRICAL CODE.
- 4.2. ALL OVERCURRENT DEVICES SHALL HAVE AN INTERRUPTING CURRENT RATING THAT SHALL BE GREATER THAN THE SHORT CIRCUIT CURRENT TO WHICH THEY ARE SUBJECTED, 22,000 AIC MINIMUM. VERIFY AVAILABLE SHORT CIRCUIT CURRENT DOES NOT EXCEED THE RATING OF ELECTRICAL EQUIPMENT IN ACCORDANCE WITH ARTICLE 110.24 NEC OR THE MOST CURRENT ADOPTED CODE PRE THE GOVERNING JURISDICTION.
5. EACH END OF EVERY POWER PHASE CONDUCTOR, GROUNDING CONDUCTOR, AND TELCO CONDUCTOR OR CABLE SHALL BE LABELED WITH COLOR-CODED INSULATION OR ELECTRICAL TAPE (3M BRAND, 1/2" PLASTIC ELECTRICAL TAPE WITH UV PROTECTION, OR EQUAL). THE IDENTIFICATION METHOD SHALL CONFORM WITH NEC AND OSHA.
6. ALL ELECTRICAL COMPONENTS SHALL BE CLEARLY LABELED WITH LAMICOID TAGS SHOWING THEIR RATED VOLTAGE, PHASE CONFIGURATION, WIRE CONFIGURATION, POWER OR AMPACITY RATING AND BRANCH CIRCUIT ID NUMBERS (i.e. PANEL BOARD AND CIRCUIT ID'S).
7. PANEL BOARDS (ID NUMBERS) SHALL BE CLEARLY LABELED WITH PLASTIC LABELS.
8. TIE WRAPS ARE NOT ALLOWED.
9. ALL POWER AND EQUIPMENT GROUND WIRING IN TUBING OR CONDUIT SHALL BE SINGLE COPPER CONDUCTOR (#14 OR LARGER) WITH TYPE THHW, THWN, THWN-2, XHHW, XHHW-2, THW, THW-2, RHW, OR RHW-2 INSULATION UNLESS OTHERWISE SPECIFIED.
10. SUPPLEMENTAL EQUIPMENT GROUND WIRING LOCATED INDOORS SHALL BE SINGLE COPPER CONDUCTOR (#6 OR LARGER) WITH TYPE THHW, THWN, THWN-2, XHHW, XHHW-2, THW, THW-2, RHW, OR RHW-2 INSULATION UNLESS OTHERWISE SPECIFIED.
11. POWER AND CONTROL WIRING IN FLEXIBLE CORD SHALL BE MULTI-CONDUCTOR, TYPE SOOW CORD (#14 OR LARGER) UNLESS OTHERWISE SPECIFIED.
12. POWER AND CONTROL WIRING FOR USE IN CABLE TRAY SHALL BE MULTI-CONDUCTOR, TYPE TC CABLE (#14 OR LARGER), WITH TYPE THHW, THWN, THWN-2, XHHW, XHHW-2, THW, THW-2, RHW, OR RHW-2 INSULATION UNLESS OTHERWISE SPECIFIED.
13. ALL POWER AND GROUNDING CONNECTIONS SHALL BE CRIMP-STYLE, COMPRESSION WIRE LUGS AND WIRE NUTS BY THOMAS AND BETTS (OR EQUAL). LUGS AND WIRE NUTS SHALL BE RATED FOR OPERATION NOT LESS THAN 75° C (90° C IF AVAILABLE).
14. RACEWAY AND CABLE TRAY SHALL BE LISTED OR LABELED FOR ELECTRICAL USE IN ACCORDANCE WITH NEMA, UL, ANSI/IEEE AND NEC.
15. ELECTRICAL METALLIC TUBING (EMT), INTERMEDIATE METAL CONDUIT (IMC), OR RIGID METAL CONDUIT (RMC) SHALL BE USED FOR EXPOSED INDOOR LOCATIONS.

16. ELECTRICAL METALLIC TUBING (EMT) OR METAL-CLAD CABLE (MC) SHALL BE USED FOR CONCEALED INDOOR LOCATIONS.
17. SCHEDULE 40 PVC UNDERGROUND ON STRAIGHTS AND SCHEDULE 80 PVC FOR ALL ELBOWS/90s AND ALL APPROVED ABOVE GRADE PVC CONDUIT.
18. LIQUID-TIGHT FLEXIBLE METALLIC CONDUIT (LIQUID-TITE FLEX) SHALL BE USED INDOORS AND OUTDOORS, WHERE VIBRATION OCCURS OR FLEXIBILITY IS NEEDED.
19. CONDUIT AND TUBING FITTINGS SHALL BE THREADED OR COMPRESSION-TYPE AND APPROVED FOR THE LOCATION USED. SET SCREW FITTINGS ARE NOT ACCEPTABLE.
20. CABINETS, BOXES AND WIRE WAYS SHALL BE LABELED FOR ELECTRICAL USE IN ACCORDANCE WITH NEMA, UL, ANSI/IEEE AND THE NEC.
21. WIREWAYS SHALL BE METAL WITH AN ENAMEL FINISH AND INCLUDE A HINGED COVER, DESIGNED TO SWING OPEN DOWNWARDS (WIREMOLD SPECMATE WIREWAY).
22. SLOTTED WIRING DUCT SHALL BE PVC AND INCLUDE COVER (PANDUIT TYPE E OR EQUAL).
23. CONDUITS SHALL BE FASTENED SECURELY IN PLACE WITH APPROVED NON-PERFORATED STRAPS AND HANGERS. EXPLOSIVE DEVICES (i.e. POWDER-ACTUATED) FOR ATTACHING HANGERS TO STRUCTURE WILL NOT BE PERMITTED. CLOSELY FOLLOW THE LINES OF THE STRUCTURE, MAINTAIN CLOSE PROXIMITY TO THE STRUCTURE AND KEEP CONDUITS IN TIGHT ENVELOPES. CHANGES IN DIRECTION TO ROUTE AROUND OBSTACLES SHALL BE MADE WITH CONDUIT OUTLET BODIES. CONDUIT SHALL BE INSTALLED IN A NEAT AND WORKMANLIKE MANNER. PARALLEL AND PERPENDICULAR TO STRUCTURE WALL AND CEILING LINES. ALL CONDUIT SHALL BE FISHED TO CLEAR OBSTRUCTIONS. ENDS OF CONDUITS SHALL BE TEMPORARILY CAPPED FLUSH TO FINISH GRADE TO PREVENT CONCRETE, PLASTER OR DIRT FROM ENTERING. CONDUITS SHALL BE RIGIDLY CLAMPED TO BOXES BY GALVANIZED MALLEABLE IRON BUSHING ON INSIDE AND GALVANIZED MALLEABLE IRON LOCKNUT ON OUTSIDE AND INSIDE.
24. EQUIPMENT CABINETS, TERMINAL BOXES, JUNCTION BOXES AND PULL BOXES SHALL BE GALVANIZED OR EPOXY-COATED SHEET STEEL SHALL MEET OR EXCEED UL 50 AND BE RATED NEMA 1 (OR BETTER) FOR INTERIOR LOCATIONS AND NEMA 3 (OR BETTER) FOR EXTERIOR LOCATIONS.
25. METAL RECEPTACLE, SWITCH AND DEVICE BOXES SHALL BE GALVANIZED, EPOXY-COATED OR NON-CORRODING; SHALL MEET OR EXCEED UL 514A AND NEMA OS 1 AND BE RATED NEMA 1 (OR BETTER) FOR INTERIOR LOCATIONS AND WEATHER PROTECTED (WP OR BETTER) FOR EXTERIOR LOCATIONS.
26. NONMETALLIC RECEPTACLE, SWITCH AND DEVICE BOXES SHALL MEET OR EXCEED NEMA OS 2 (NEWEST REVISION) AND BE RATED NEMA 1 (OR BETTER) FOR INTERIOR LOCATIONS AND WEATHER PROTECTED (WP OR BETTER) FOR EXTERIOR LOCATIONS.
27. THE CONTRACTOR SHALL NOTIFY AND OBTAIN NECESSARY AUTHORIZATION FROM THE CARRIER AND/OR DISH Wireless L.L.C. AND TOWER OWNER BEFORE COMMENCING WORK ON THE AC POWER DISTRIBUTION PANELS.
28. THE CONTRACTOR SHALL PROVIDE NECESSARY TAGGING ON THE BREAKERS, CABLES AND DISTRIBUTION PANELS IN ACCORDANCE WITH THE APPLICABLE CODES AND STANDARDS TO SAFEGUARD LIFE AND PROPERTY.
29. INSTALL LAMICOID LABEL ON THE METER CENTER TO SHOW "DISH Wireless L.L.C.".
30. ALL EMPTY/SPARE CONDUITS THAT ARE INSTALLED ARE TO HAVE A METERED MULE TAPE PULL CORD INSTALLED.




5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



2000 CORPORATE DRIVE
CANONSBURG, PA 15317



FROM ZERO TO INFINIGY
the solutions are endless
2500 W. HIGGINS RD., SUITE 500 |
HOFFMAN ESTATES, IL 60169
PHONE: 847-648-4068 | FAX: 518-690-0793
WWW.INFINIGY.COM



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
RCD	SS	CJW

RFDS REV #: N/A

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	06/11/2021	ISSUED FOR REVIEW
0	08/23/2021	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
6039-20001C

DISH Wireless L.L.C.
PROJECT INFORMATION
BOHVN00009A
1432 OLD WATERBURY ROAD
SOUTHBURY, CT 06488

SHEET TITLE
GENERAL NOTES

SHEET NUMBER
GN-3

GROUNDING NOTES:

1. ALL GROUND ELECTRODE SYSTEMS (INCLUDING TELECOMMUNICATION, RADIO, LIGHTNING PROTECTION AND AC POWER GES'S) SHALL BE BONDED TOGETHER AT OR BELOW GRADE, BY TWO OR MORE COPPER BONDING CONDUCTORS IN ACCORDANCE WITH THE NEC.
2. THE CONTRACTOR SHALL PERFORM IEEE FALL-OF-POTENTIAL RESISTANCE TO EARTH TESTING (PER IEEE 1100 AND 81) FOR GROUND ELECTRODE SYSTEMS, THE CONTRACTOR SHALL FURNISH AND INSTALL SUPPLEMENTAL GROUND ELECTRODES AS NEEDED TO ACHIEVE A TEST RESULT OF 5 OHMS OR LESS.
3. THE CONTRACTOR IS RESPONSIBLE FOR PROPERLY SEQUENCING GROUNDING AND UNDERGROUND CONDUIT INSTALLATION AS TO PREVENT ANY LOSS OF CONTINUITY IN THE GROUNDING SYSTEM OR DAMAGE TO THE CONDUIT AND PROVIDE TESTING RESULTS.
4. METAL CONDUIT AND TRAY SHALL BE GROUNDED AND MADE ELECTRICALLY CONTINUOUS WITH LISTED BONDING FITTINGS OR BY BONDING ACROSS THE DISCONTINUITY WITH #6 COPPER WIRE UL APPROVED GROUNDING TYPE CONDUIT CLAMPS.
5. METAL RACEWAY SHALL NOT BE USED AS THE NEC REQUIRED EQUIPMENT GROUND CONDUCTOR. STRANDED COPPER CONDUCTORS WITH GREEN INSULATION, SIZED IN ACCORDANCE WITH THE NEC, SHALL BE FURNISHED AND INSTALLED WITH THE POWER CIRCUITS TO BTS EQUIPMENT.
6. EACH CABINET FRAME SHALL BE DIRECTLY CONNECTED TO THE MASTER GROUND BAR WITH GREEN INSULATED SUPPLEMENTAL EQUIPMENT GROUND WIRES, #6 STRANDED COPPER OR LARGER FOR INDOOR BTS; #2 BARE SOLID TINNED COPPER FOR OUTDOOR BTS.
7. CONNECTIONS TO THE GROUND BUS SHALL NOT BE DOUBLED UP OR STACKED BACK TO BACK CONNECTIONS ON OPPOSITE SIDE OF THE GROUND BUS ARE PERMITTED.
8. ALL EXTERIOR GROUND CONDUCTORS BETWEEN EQUIPMENT/GROUND BARS AND THE GROUND RING SHALL BE #2 SOLID TINNED COPPER UNLESS OTHERWISE INDICATED.
9. ALUMINUM CONDUCTOR OR COPPER CLAD STEEL CONDUCTOR SHALL NOT BE USED FOR GROUNDING CONNECTIONS.
10. USE OF 90° BENDS IN THE PROTECTION GROUNDING CONDUCTORS SHALL BE AVOIDED WHEN 45° BENDS CAN BE ADEQUATELY SUPPORTED.
11. EXOTHERMIC WELDS SHALL BE USED FOR ALL GROUNDING CONNECTIONS BELOW GRADE.
12. ALL GROUND CONNECTIONS ABOVE GRADE (INTERIOR AND EXTERIOR) SHALL BE FORMED USING HIGH PRESS CRIMPS.
13. COMPRESSION GROUND CONNECTIONS MAY BE REPLACED BY EXOTHERMIC WELD CONNECTIONS.
14. ICE BRIDGE BONDING CONDUCTORS SHALL BE EXOTHERMICALLY BONDED OR BOLTED TO THE BRIDGE AND THE TOWER GROUND BAR.
15. APPROVED ANTIOXIDANT COATINGS (i.e. CONDUCTIVE GEL OR PASTE) SHALL BE USED ON ALL COMPRESSION AND BOLTED GROUND CONNECTIONS.
16. ALL EXTERIOR GROUND CONNECTIONS SHALL BE COATED WITH A CORROSION RESISTANT MATERIAL.
17. MISCELLANEOUS ELECTRICAL AND NON-ELECTRICAL METAL BOXES, FRAMES AND SUPPORTS SHALL BE BONDED TO THE GROUND RING, IN ACCORDANCE WITH THE NEC.
18. BOND ALL METALLIC OBJECTS WITHIN 6 ft OF MAIN GROUND RING WITH (1) #2 BARE SOLID TINNED COPPER GROUND CONDUCTOR.
19. GROUND CONDUCTORS USED FOR THE FACILITY GROUNDING AND LIGHTNING PROTECTION SYSTEMS SHALL NOT BE ROUTED THROUGH METALLIC OBJECTS THAT FORM A RING AROUND THE CONDUCTOR, SUCH AS METALLIC CONDUITS, METAL SUPPORT CLIPS OR SLEEVES THROUGH WALLS OR FLOORS. WHEN IT IS REQUIRED TO BE HOUSED IN CONDUIT TO MEET CODE REQUIREMENTS OR LOCAL CONDITIONS, NON-METALLIC MATERIAL SUCH AS PVC CONDUIT SHALL BE USED. WHERE USE OF METAL CONDUIT IS UNAVOIDABLE (i.e., NONMETALLIC CONDUIT PROHIBITED BY LOCAL CODE) THE GROUND CONDUCTOR SHALL BE BONDED TO EACH END OF THE METAL CONDUIT.
20. ALL GROUNDS THAT TRANSITION FROM BELOW GRADE TO ABOVE GRADE MUST BE #2 BARE SOLID TINNED COPPER IN 3/4" NON-METALLIC, FLEXIBLE CONDUIT FROM 24" BELOW GRADE TO WITHIN 3" TO 6" OF CAD-WELD TERMINATION POINT. THE EXPOSED END OF THE CONDUIT MUST BE SEALED WITH SILICONE CAULK. (ADD TRANSITIONING GROUND STANDARD DETAIL AS WELL).
21. BUILDINGS WHERE THE MAIN GROUNDING CONDUCTORS ARE REQUIRED TO BE ROUTED TO GRADE, THE CONTRACTOR SHALL ROUTE TWO GROUNDING CONDUCTORS FROM THE ROOFTOP, TOWERS, AND WATER TOWERS GROUNDING RING, TO THE EXISTING GROUNDING SYSTEM, THE GROUNDING CONDUCTORS SHALL NOT BE SMALLER THAN 2/0 COPPER. ROOFTOP GROUNDING RING SHALL BE BONDED TO THE EXISTING GROUNDING SYSTEM, THE BUILDING STEEL COLUMNS, LIGHTNING PROTECTION SYSTEM, AND BUILDING MAIN WATER LINE (FERROUS OR NONFERROUS METAL PIPING ONLY). DO NOT ATTACH GROUNDING TO FIRE SPRINKLER SYSTEM PIPES.




5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



2000 CORPORATE DRIVE
CANONSBURG, PA 15317



FROM ZERO TO INFINIGY
the solutions are endless
2500 W. HIGGINS RD., SUITE 500 |
HOFFMAN ESTATES, IL 60169
PHONE: 847-648-4068 | FAX: 518-690-0793
WWW.INFINIGY.COM



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
RCD	SS	CJW

RFDS REV #: N/A

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	06/11/2021	ISSUED FOR REVIEW
0	08/23/2021	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
6039-Z0001C

DISH Wireless L.L.C.
PROJECT INFORMATION
BOHVN00009A
1432 OLD WATERBURY ROAD
SOUTHBURY, CT 06488

SHEET TITLE
GENERAL NOTES

SHEET NUMBER
GN-4

Exhibit D

Structural Analysis Report

Date: **June 04, 2021**



Crown Castle
2000 Corporate Dr.
Canonsburg, PA
(724) 416-2000

Subject: **Structural Analysis Report**

Carrier Designation: **DISH Network Co-Locate**
Site Number: BOHVN00009A
Site Name: CT-CCI-T-806358

Crown Castle Designation: **BU Number:** 806358
Site Name: NHV 109 943107
JDE Job Number: 645107
Work Order Number: 1966319
Order Number: 553354 Rev. 1

Engineering Firm Designation: **Crown Castle Project Number:** 1966319

Site Data: **1432 Old Waterbury Road, SOUTHURY, New Haven County, CT**
Latitude 41° 29' 36.92", Longitude -73° 9' 54.98"
225.79 Foot - Monopole Tower

Crown Castle is pleased to submit this "**Structural Analysis Report**" to determine the structural integrity of the above-mentioned tower.

The purpose of the analysis is to determine acceptability of the tower stress level. Based on our analysis we have determined the tower stress level for the structure and foundation, under the following load case, to be:



LC7: Proposed Equipment Configuration

Sufficient Capacity

This analysis utilizes an ultimate 3-second gust wind speed of 120 mph as required by the 2015 International Building Code. Applicable Standard references and design criteria are listed in Section 2 - "Analysis Criteria".

Structural analysis prepared by: Alexander Greguric, E.I.T.

Respectfully submitted by:


Digitally signed by Maham Barimani
Date: 2021.06.04 17:57:20


Maham Barimani, P.E.
Senior Project Engineer

TABLE OF CONTENTS

1) INTRODUCTION

2) ANALYSIS CRITERIA

- Table 1 - Proposed Equipment Configuration
- Table 2 - Other Considered Equipment

3) ANALYSIS PROCEDURE

- Table 3 - Documents Provided
- 3.1) Analysis Method
- 3.2) Assumptions

4) ANALYSIS RESULTS

- Table 4 - Section Capacity (Summary)
- Table 5 - Tower Component Stresses vs. Capacity - LC7
- 4.1) Recommendations

5) APPENDIX A

- tnxTower Output

6) APPENDIX B

- Base Level Drawing

7) APPENDIX C

- Additional Calculations

1) INTRODUCTION

This tower is a 225.79 ft Monopole tower designed by ENGINEERED ENDEAVORS, INC. The tower has been modified multiple times in the past to accommodate additional loading.

2) ANALYSIS CRITERIA

TIA-222 Revision:	TIA-222-H
Risk Category:	II
Wind Speed:	120 mph
Exposure Category:	B
Topographic Factor:	1
Ice Thickness:	1.5 in
Wind Speed with Ice:	50 mph
Service Wind Speed:	60 mph

Table 1 - Proposed Equipment Configuration

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)
218.0	218.0	3	fujitsu	TA08025-B604	1	1-3/4
		3	fujitsu	TA08025-B605		
		3	jma wireless	MX08FRO665-21 w/ Mount Pipe		
		1	raycap	RDIDC-9181-PF-48		
		1	tower mounts	Commscope MC-PK8-DSH		

Table 2 - Other Considered Equipment

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)
228.0	228.0	1	Tower mounts	Platform Mount (10' LP 101-1)	14	1-5/8
		3	alcatel lucent	B13 RRH 4X30		
		3	alcatel lucent	B4 RRH2X60-4R		
		6	antel	LPA-80080/6CF w/ Mount Pipe		
		6	commscope	SBNHH-1D65B w/ Mount Pipe		
		2	raycap	RRFDC-3315-PF-48		
		6	rfs celwave	FD9R6004/2C-3L		
		1	tower mounts	Side Arm Mount [SO 203-3]		
205.0	207.0	3	commscope	ATSBT-TOP-MF-4G	14	1-5/8
		3	ericsson	AIR6449 B41 w/ Mount Pipe		
		3	ericsson	RADIO 4415 B66A_CCIV3		
		3	ericsson	RADIO 4424		
		3	ericsson	RADIO 4449 B71 B85A_T-MOBILE		
		3	rfs celwave	APX16DWV-16DWV-S-E-A20 w/ Mount Pipe		
	3	rfs celwave	APXVAARR24_43-U-NA20_T-MOBILE w/ Mount Pipe			
	205.0	1	Tower mounts	Platform Mount [10.8' LP 712-1]		

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)
196.0	196.0	1	Tower mounts	Sabre C10857333C [SM 504-3]	2 6 12	3/8 5/8 1-1/4
		3	cci antennas	DTMABP7819VG12A		
		3	cci antennas	OPA-65R-LCUU-H6 w/ Mount Pipe		
		3	cci antennas	OPA65R-BU6D w/ Mount Pipe		
		3	ericsson	RRUS 11 B12		
		3	ericsson	RRUS 32 B2_CCIV2		
		3	ericsson	RRUS 4426 B66		
		3	ericsson	RRUS 4478 B14_CCIV2		
		3	ericsson	WCS RRUS-32-B30		
		3	kaelus	DBC0061F1V51-2		
		3	kathrein	800 10121 w/ Mount Pipe		
		3	kathrein	80010798 w/ Mount Pipe		
		6	kathrein	860 10025		
		3	raycap	DC6-48-60-18-8F		
185.0	187.0	3	decibel	978QNB120E-M w/ Mount Pipe	1 6	1/2 1-5/8
		6	ems wireless	FV90-16-02DP w/ Mount Pipe		
		3	nokia	CS72993.07		
		3	rfs celwave	APXV18-206517S-C w/ Mount Pipe		
	185.0	1	tower mounts	Platform Mount [LP 712-1]		
173.0	173.0	3	alcatel lucent	1900MHz RRH (65MHz)	4	1-1/4
		3	alcatel lucent	800 EXTERNAL NOTCH FILTER		
		3	alcatel lucent	800MHZ RRH		
		9	rfs celwave	ACU-A20-N		
		1	tower mounts	Side Arm Mount [SO 102-3]		
172.0	173.0	3	alcatel lucent	TD-RRH8x20-25	4	1-1/4
		3	rfs celwave	APXVSPP18-C-A20 w/ Mount Pipe		
		3	rfs celwave	APXVTM14-C-120 w/ Mount Pipe		
	172.0	1	tower mounts	Platform Mount [LP 1201-1]		
72.0	73.0	1	gps	GPS_A	2	1/2
	72.0	1	tower mounts	Side Arm Mount [SO 701-1]		

3) ANALYSIS PROCEDURE

Table 3 - Documents Provided

Document	Reference	Source
4-GEOTECHNICAL REPORTS	217688	CCISITES
4-TOWER FOUNDATION DRAWINGS/DESIGN/SPECS	821496	CCISITES
4-TOWER MANUFACTURER DRAWINGS	821494	CCISITES
4-TOWER REINFORCEMENT DESIGN/DRAWINGS/DATA	1276594	CCISITES
4-POST-MODIFICATION INSPECTION	1863184	CCISITES
4-TOWER REINFORCEMENT DESIGN/DRAWINGS/DATA	4062841	CCISITES
4-POST-MODIFICATION INSPECTION	4062849	CCISITES

3.1) Analysis Method

tnxTower (version 8.0.9.0), a commercially available analysis software package, was used to create a three-dimensional model of the tower and calculate member stresses for various loading cases. Selected output from the analysis is included in Appendix A. When applicable, Crown Castle has calculated and provided the effective area for panel antennas using approved methods following the intent of the TIA-222 standard.

3.2) Assumptions

- 1) Tower and structures were maintained in accordance with the TIA-222 Standard.
- 2) The configuration of antennas, transmission cables, mounts and other appurtenances are as specified in Tables 1 and 2 and the referenced drawings.

This analysis may be affected if any assumptions are not valid or have been made in error. Crown Castle should be notified to determine the effect on the structural integrity of the tower.

4) ANALYSIS RESULTS

Table 4 - Section Capacity (Summary)

Section No.	Elevation (ft)	Component Type	Size	Critical Element	P (K)	SF*P_allow (K)	% Capacity	Pass / Fail
L1	225.79 - 197.75	Pole	TP28.6563x21.5x0.1875	1	-11.09	1002.63	44.0	Pass
L2	197.75 - 162.72	Pole	TP37.0938x27.24x0.375	2	-28.78	2589.87	47.2	Pass
L3	162.72 - 120.09	Pole	TP47.1563x35.0487x0.4375	3	-43.00	3846.79	58.2	Pass
L4	120.09 - 78.99	Pole	TP56.6563x44.6617x0.5	4	-60.90	5287.57	57.7	Pass
L5	78.99 - 38.92	Pole	TP65.7813x53.7418x0.5625	5	-83.44	6910.70	54.3	Pass
L6	38.92 - 0	Pole	TP74.5x62.453x0.5625	6	-115.05	8108.48	57.6	Pass
							Summary	
						Pole (L3)	58.2	Pass
						Rating =	58.2	Pass

Table 5 - Tower Component Stresses vs. Capacity - LC7

Notes	Component	Elevation (ft)	% Capacity	Pass / Fail
1	Anchor Rods	0	62.1	Pass
1	Base Plate	0	46.5	Pass
1	Base Foundation (Compared w/ Design Loads)	0	66.8	Pass

Structure Rating (max from all components) =	66.8%
---	--------------

Notes:


- 1) See additional documentation in "Appendix C – Additional Calculations" for calculations supporting the % capacity consumed.

4.1) Recommendations

The tower and its foundation have sufficient capacity to carry the proposed load configuration. No modifications are required at this time.

APPENDIX A
TNXTOWER OUTPUT

Section	1	2	3	4	5	6	
Length (ft)	28.04	39.11	47.77	47.49	47.65	47.64	
Number of Sides	18	18	18	18	18	18	
Thickness (in)	0.1875	0.3750	0.4375	0.5000	0.5625	0.5625	
Socket Length (ft)	4.08	5.14	6.39	7.58	8.72		
Top Dia (in)	21.5000	27.2400	35.0487	44.6617	53.7418	62.4530	
Bot Dia (in)	28.6563	37.0938	47.1563	56.6563	65.7813	74.5000	
Grade				A572-65			
Weight (K)	1.4	5.0	9.2	12.9	17.1	19.7	65.3




MATERIAL STRENGTH					
GRADE	Fy	Fu	GRADE	Fy	Fu
A572-65	65 ksi	80 ksi			

TOWER DESIGN NOTES

1. Tower is located in New Haven County, Connecticut.
2. Tower designed for Exposure B to the TIA-222-H Standard.
3. Tower designed for a 120 mph basic wind in accordance with the TIA-222-H Standard.
4. Tower is also designed for a 50 mph basic wind with 1.50 in ice. Ice is considered to increase in thickness with height.
5. Deflections are based upon a 60 mph wind.
6. Tower Risk Category II.
7. Topographic Category 1 with Crest Height of 0.00 ft
8. TOWER RATING: 58.2%

ALL REACTIONS ARE FACTORED



<p align="center">Crown Castle 2000 Corporate Dr. Canonsburg, PA The Pathway to Possible Phone: (724) 416-2000 FAX:</p>		Job: BU# 806358	
		Project:	
Client: Crown Castle	Drawn by: AGreguric	App'd:	
Code: TIA-222-H	Date: 06/04/21	Scale: NTS	
Path:		Dwg No. E-1	

© Usps/agreguric/Dwt/Dive - Crown Castle USA Inc/Design/Work Area/030320/WO 1668319 - SA/Prep/030320_BPA.plt

Tower Input Data

The tower is a monopole.
 This tower is designed using the TIA-222-H standard.
 The following design criteria apply:

- Tower is located in New Haven County, Connecticut.
- Tower base elevation above sea level: 666.00 ft.
- Basic wind speed of 120 mph.
- Risk Category II.
- Exposure Category B.
- Simplified Topographic Factor Procedure for wind speed-up calculations is used.
- Topographic Category: 1.
- Crest Height: 0.00 ft.
- Nominal ice thickness of 1.5000 in.
- Ice thickness is considered to increase with height.
- Ice density of 56 pcf.
- A wind speed of 50 mph is used in combination with ice.
- Temperature drop of 50 °F.
- Deflections calculated using a wind speed of 60 mph.
- A non-linear (P-delta) analysis was used.
- Pressures are calculated at each section.
- Stress ratio used in pole design is 1.
- Tower analysis based on target reliabilities in accordance with Annex S.
- Load Modification Factors used: $K_{es}(F_w) = 0.95$, $K_{es}(t_i) = 0.85$.
- Maximum demand-capacity ratio is: 1.05.
- Local bending stresses due to climbing loads, feed line supports, and appurtenance mounts are not considered.

Options

Consider Moments - Legs Consider Moments - Horizontals Consider Moments - Diagonals Use Moment Magnification ✓ Use Code Stress Ratios ✓ Use Code Safety Factors - Guys Escalate Ice Always Use Max Kz Use Special Wind Profile Include Bolts In Member Capacity Leg Bolts Are At Top Of Section Secondary Horizontal Braces Leg Use Diamond Inner Bracing (4 Sided) SR Members Have Cut Ends SR Members Are Concentric	Distribute Leg Loads As Uniform Assume Legs Pinned ✓ Assume Rigid Index Plate ✓ Use Clear Spans For Wind Area Use Clear Spans For KL/r Retension Guys To Initial Tension ✓ Bypass Mast Stability Checks ✓ Use Azimuth Dish Coefficients ✓ Project Wind Area of Appurt. Autocalc Torque Arm Areas Add IBC .6D+W Combination ✓ Sort Capacity Reports By Component Triangulate Diamond Inner Bracing Treat Feed Line Bundles As Cylinder Ignore KL/ry For 60 Deg. Angle Legs	Use ASCE 10 X-Brace Ly Rules Calculate Redundant Bracing Forces Ignore Redundant Members in FEA SR Leg Bolts Resist Compression All Leg Panels Have Same Allowable Offset Girt At Foundation ✓ Consider Feed Line Torque Include Angle Block Shear Check Use TIA-222-H Bracing Resist. Exemption Use TIA-222-H Tension Splice Exemption <div style="text-align: center; background-color: #e0e0e0; padding: 2px;">Poles</div> ✓ Include Shear-Torsion Interaction Always Use Sub-Critical Flow Use Top Mounted Sockets Pole Without Linear Attachments Pole With Shroud Or No Appurtenances Outside and Inside Corner Radii Are Known
--	---	---

Tapered Pole Section Geometry

Section	Elevation ft	Section Length ft	Splice Length ft	Number of Sides	Top Diameter in	Bottom Diameter in	Wall Thickness in	Bend Radius in	Pole Grade
L1	225.79-197.75	28.04	4.08	18	21.5000	28.6563	0.1875	0.7500	A572-65 (65 ksi)
L2	197.75-162.72	39.11	5.14	18	27.2400	37.0938	0.3750	1.5000	A572-65 (65 ksi)
L3	162.72-120.09	47.77	6.39	18	35.0487	47.1563	0.4375	1.7500	A572-65 (65 ksi)
L4	120.09-78.99	47.49	7.58	18	44.6617	56.6563	0.5000	2.0000	A572-65 (65 ksi)
L5	78.99-38.92	47.65	8.72	18	53.7418	65.7813	0.5625	2.2500	A572-65 (65 ksi)
L6	38.92-0.00	47.64		18	62.4530	74.5000	0.5625	2.2500	A572-65 (65 ksi)

Tapered Pole Properties

Section	Tip Dia. in	Area in ²	I in ⁴	r in	C in	I/C in ³	J in ⁴	It/Q in ²	w in	w/t
L1	21.8027	12.6836	727.8616	7.5659	10.9220	66.6418	1456.6810	6.3430	3.4540	18.421
	29.0694	16.9425	1734.8057	10.1064	14.5574	119.1702	3471.8941	8.4728	4.7135	25.139
L2	28.6462	31.9760	2915.6454	9.5371	13.8379	210.6999	5835.1273	15.9911	4.1342	11.025
	37.6081	43.7045	7444.5646	13.0352	18.8436	395.0707	14898.925	21.8564	5.8685	15.649
L3	36.8448	48.0620	7274.0007	12.2870	17.8048	408.5427	14557.572	24.0356	5.3986	12.34
	47.8162	64.8748	17889.412	16.5852	23.9554	746.7807	35802.363	32.4436	7.5295	17.21
L4	46.9123	70.0846	17268.356	15.6774	22.6881	761.1185	34559.434	35.0489	6.9805	13.961
	57.4531	89.1200	35506.566	19.9355	28.7814	1233.6647	71059.852	44.5685	9.0915	18.183
L5	56.4288	94.9449	33922.972	18.8786	27.3008	1242.5625	67890.581	47.4815	8.4686	15.055
	66.7093	116.4399	62572.615	23.1527	33.4169	1872.4856	125227.56	58.2310	10.5875	18.822
L6	65.5688	110.4978	53473.562	21.9711	31.7261	1685.4739	107017.48	55.2594	10.0017	17.781
	75.5625	132.0062	91171.937	26.2478	37.8460	2409.0244	182463.84	66.0156	12.1220	21.55

Tower Elevation ft	Gusset Area (per face) ft ²	Gusset Thickness in	Gusset Grade	Adjust. Factor A _r	Adjust. Factor A _r	Weight Mult.	Double Angle Stitch Bolt Spacing Diagonals in	Double Angle Stitch Bolt Spacing Horizontal in	Double Angle Stitch Bolt Spacing Redundants in
L1 225.79-197.75				1	1	1			
L2 197.75-162.72				1	1	1			
L3 162.72-120.09				1	1	1			
L4 120.09-78.99				1	1	1			
L5 78.99-38.92				1	1	1			
L6 38.92-0.00				1	1	1			

Feed Line/Linear Appurtenances - Entered As Round Or Flat

Description	Sector	Exclude From Torque Calculation	Component Type	Placement ft	Total Number	Number Per Row	Start/End Position	Width or Diameter in	Perimeter in	Weight plf
Safety Line 3/8	A	No	Surface Ar (CaAa)	225.78 - 8.00	1	1	-0.080 -0.070	0.3750		0.22
HB158-1-08U8-S8J18(1-5/8)	C	No	Surface Ar (CaAa)	225.78 - 8.00	2	1	0.220 0.260	1.9800		1.30
WR-VG82ST-BRDA(5/8)	A	No	Surface Ar (CaAa)	196.00 - 8.00	2	2	-0.300 -0.280	0.6450		0.31
WR-VG82ST-BRDA(5/8)	A	No	Surface Ar (CaAa)	196.00 - 8.00	2	2	-0.320 -0.300	0.6450		0.31
LDF6-50A(1-1/4)	A	No	Surface Ar (CaAa)	196.00 - 8.00	3	3	-0.410 -0.320	1.5500		0.60
LDF7-50A(1-5/8)	C	No	Surface Ar (CaAa)	185.00 - 8.00	6	6	-0.070 0.350	1.9800		0.82
LDF4-50A(1/2)	C	No	Surface Ar (CaAa)	185.00 - 8.00	1	1	0.480 0.490	0.6300		0.15
PL1x6 Reinforcement - Wind Area/Weight	A	No	Surface Af (CaAa)	134.00 - 124.00	1	1	0.000 0.000	6.0000	14.0000	20.41
PL1x6 Reinforcement - Wind Area/Weight	B	No	Surface Af (CaAa)	134.00 - 124.00	1	1	0.000 0.000	6.0000	14.0000	20.41
PL1x6 Reinforcement - Wind Area/Weight	C	No	Surface Af (CaAa)	134.00 - 124.00	1	1	0.000 0.000	6.0000	14.0000	20.41
CU12PSM6P4XXX(1-3/4)	A	No	Surface Ar (CaAa)	218.00 - 0.00	1	1	0.000 0.500	1.7500		2.72

Feed Line/Linear Appurtenances - Entered As Area

Description	Face or Leg	Allow Shield	Exclude From Torque Calculation	Component Type	Placement ft	Total Number	CAAA	Weight	
							ft ² /ft	plf	
561(1-5/8)	C	No	No	Inside Pole	225.78 - 0.00	12	No Ice 1/2" Ice 1" Ice 2" Ice	0.00 0.00 0.00 0.00	1.35 1.35 1.35 1.35
HCS 6X12 4AWG(1-5/8)	C	No	No	Inside Pole	205.00 - 0.00	2	No Ice 1/2" Ice 1" Ice 2" Ice	0.00 0.00 0.00 0.00	2.40 2.40 2.40 2.40
LDF7-50A(1-5/8)	C	No	No	Inside Pole	205.00 - 0.00	6	No Ice 1/2" Ice 1" Ice 2" Ice	0.00 0.00 0.00 0.00	0.82 0.82 0.82 0.82
AVA7-50(1-5/8)	C	No	No	Inside Pole	205.00 - 0.00	6	No Ice 1/2" Ice 1" Ice 2" Ice	0.00 0.00 0.00 0.00	0.70 0.70 0.70 0.70
LDF6-50A(1-1/4)	C	No	No	Inside Pole	196.00 - 0.00	9	No Ice 1/2" Ice 1" Ice 2" Ice	0.00 0.00 0.00 0.00	0.60 0.60 0.60 0.60
WR-VG82ST-BRDA(5/8)	C	No	No	Inside Pole	196.00 - 0.00	2	No Ice 1/2" Ice 1" Ice 2" Ice	0.00 0.00 0.00 0.00	0.31 0.31 0.31 0.31
FB-L98B-034-XXX(3/8)	C	No	No	Inside Pole	196.00 - 0.00	2	No Ice 1/2" Ice 1" Ice 2" Ice	0.00 0.00 0.00 0.00	0.06 0.06 0.06 0.06
2" innerduct	C	No	No	Inside Pole	196.00 - 0.00	1	No Ice	0.00	0.20

Description	Face or Leg	Allow Shield	Exclude From Torque Calculation	Component Type	Placement ft	Total Number		C _A A _A ft ² /ft	Weight plf
conduit							1/2" Ice	0.00	0.20
							1" Ice	0.00	0.20
							2" Ice	0.00	0.20

HB114-21U3M12-XXXF(1-1/4)	C	No	No	Inside Pole	172.00 - 0.00	1	No Ice	0.00	1.22
							1/2" Ice	0.00	1.22
							1" Ice	0.00	1.22
							2" Ice	0.00	1.22
HB114-1-0813U4-M5J(1-1/4)	C	No	No	Inside Pole	172.00 - 0.00	3	No Ice	0.00	1.20
							1/2" Ice	0.00	1.20
							1" Ice	0.00	1.20
							2" Ice	0.00	1.20

LDF4-50A(1/2)	C	No	No	Inside Pole	72.00 - 0.00	1	No Ice	0.00	0.15
							1/2" Ice	0.00	0.15
							1" Ice	0.00	0.15
							2" Ice	0.00	0.15

Feed Line/Linear Appurtenances Section Areas

Tower Section	Tower Elevation ft	Face	A _R ft ²	A _F ft ²	C _A A _A In Face ft ²	C _A A _A Out Face ft ²	Weight K
L1	225.79-197.75	A	0.000	0.000	4.595	0.000	0.06
		B	0.000	0.000	0.000	0.000	0.00
		C	0.000	0.000	5.550	0.000	0.63
L2	197.75-162.72	A	0.000	0.000	31.505	0.000	0.20
		B	0.000	0.000	0.000	0.000	0.00
		C	0.000	0.000	34.808	0.000	1.51
L3	162.72-120.09	A	0.000	0.000	49.002	0.000	0.46
		B	0.000	0.000	9.121	0.000	0.20
		C	0.000	0.000	70.892	0.000	2.29
L4	120.09-78.99	A	0.000	0.000	38.449	0.000	0.25
		B	0.000	0.000	0.000	0.000	0.00
		C	0.000	0.000	59.554	0.000	2.01
L5	78.99-38.92	A	0.000	0.000	37.485	0.000	0.24
		B	0.000	0.000	0.000	0.000	0.00
		C	0.000	0.000	58.061	0.000	1.97
L6	38.92-0.00	A	0.000	0.000	30.326	0.000	0.21
		B	0.000	0.000	0.000	0.000	0.00
		C	0.000	0.000	44.803	0.000	1.85

Feed Line/Linear Appurtenances Section Areas - With Ice

Tower Section	Tower Elevation ft	Face or Leg	Ice Thickness in	A _R ft ²	A _F ft ²	C _A A _A In Face ft ²	C _A A _A Out Face ft ²	Weight K
L1	225.79-197.75	A	1.535	0.000	0.000	19.417	0.000	0.29
		B		0.000	0.000	0.000	0.000	0.00
		C		0.000	0.000	14.155	0.000	1.00
L2	197.75-162.72	A	1.510	0.000	0.000	97.343	0.000	1.20
		B		0.000	0.000	0.000	0.000	0.00
		C		0.000	0.000	67.569	0.000	2.51
L3	162.72-120.09	A	1.474	0.000	0.000	132.373	0.000	1.80
		B		0.000	0.000	10.743	0.000	0.32
		C		0.000	0.000	127.026	0.000	3.96
L4	120.09-78.99	A	1.423	0.000	0.000	115.546	0.000	1.38
		B		0.000	0.000	0.000	0.000	0.00
		C		0.000	0.000	111.138	0.000	3.47

Tower Section	Tower Elevation ft	Face or Leg	Ice Thickness in	A _R ft ²	A _F ft ²	C _A A _A In Face ft ²	C _A A _A Out Face ft ²	Weight K
L5	78.99-38.92	A	1.351	0.000	0.000	110.313	0.000	1.29
		B		0.000	0.000	0.000	0.000	0.00
		C		0.000	0.000	107.032	0.000	3.33
L6	38.92-0.00	A	1.207	0.000	0.000	86.116	0.000	1.00
		B		0.000	0.000	0.000	0.000	0.00
		C		0.000	0.000	81.139	0.000	2.83

Feed Line Center of Pressure

Section	Elevation ft	CP _X in	CP _Z in	CP _X Ice in	CP _Z Ice in
L1	225.79-197.75	-1.4189	0.4320	-2.4813	0.1628
L2	197.75-162.72	-5.0829	4.1138	-5.5391	2.6845
L3	162.72-120.09	-5.1201	5.1651	-6.0564	3.7660
L4	120.09-78.99	-6.3149	6.3550	-7.2551	4.5265
L5	78.99-38.92	-6.7251	6.7569	-7.8915	4.9620
L6	38.92-0.00	-6.0343	5.7591	-7.3773	4.3924

Note: For pole sections, center of pressure calculations do not consider feed line shielding.

Shielding Factor Ka

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K _a No Ice	K _a Ice
L1	1	Safety Line 3/8	197.75 - 225.78	1.0000	1.0000
L1	4	HB158-1-08U8-S8J18(1-5/8)	197.75 - 225.78	1.0000	1.0000
L1	30	CU12PSM6P4XXX(1-3/4)	197.75 - 218.00	1.0000	1.0000
L2	1	Safety Line 3/8	162.72 - 197.75	1.0000	1.0000
L2	4	HB158-1-08U8-S8J18(1-5/8)	162.72 - 197.75	1.0000	1.0000
L2	10	WR-VG82ST-BRDA(5/8)	162.72 - 196.00	1.0000	1.0000
L2	11	WR-VG82ST-BRDA(5/8)	162.72 - 196.00	1.0000	1.0000
L2	12	LDF6-50A(1-1/4)	162.72 - 196.00	1.0000	1.0000
L2	18	LDF7-50A(1-5/8)	162.72 - 185.00	1.0000	1.0000
L2	19	LDF4-50A(1/2)	162.72 - 185.00	1.0000	1.0000
L2	30	CU12PSM6P4XXX(1-3/4)	162.72 - 197.75	1.0000	1.0000
L3	1	Safety Line 3/8	120.09 - 162.72	1.0000	1.0000
L3	4	HB158-1-08U8-S8J18(1-5/8)	120.09 - 162.72	1.0000	1.0000
L3	10	WR-VG82ST-BRDA(5/8)	120.09 - 162.72	1.0000	1.0000
L3	11	WR-VG82ST-BRDA(5/8)	120.09 - 162.72	1.0000	1.0000
L3	12	LDF6-50A(1-1/4)	120.09 - 162.72	1.0000	1.0000

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K _a No Ice	K _a Ice
L3	18	LDF7-50A(1-5/8)	120.09 - 162.72	1.0000	1.0000
L3	19	LDF4-50A(1/2)	120.09 - 162.72	1.0000	1.0000
L3	26	PL1x6 Reinforcement - Wind Area/Weight	124.00 - 134.00	1.0000	1.0000
L3	27	PL1x6 Reinforcement - Wind Area/Weight	124.00 - 134.00	1.0000	1.0000
L3	28	PL1x6 Reinforcement - Wind Area/Weight	124.00 - 134.00	1.0000	1.0000
L3	30	CU12PSM6P4XXX(1-3/4)	120.09 - 162.72	1.0000	1.0000
L4	1	Safety Line 3/8	78.99 - 120.09	1.0000	1.0000
L4	4	HB158-1-08U8-S8J18(1-5/8)	78.99 - 120.09	1.0000	1.0000
L4	10	WR-VG82ST-BRDA(5/8)	78.99 - 120.09	1.0000	1.0000
L4	11	WR-VG82ST-BRDA(5/8)	78.99 - 120.09	1.0000	1.0000
L4	12	LDF6-50A(1-1/4)	78.99 - 120.09	1.0000	1.0000
L4	18	LDF7-50A(1-5/8)	78.99 - 120.09	1.0000	1.0000
L4	19	LDF4-50A(1/2)	78.99 - 120.09	1.0000	1.0000
L4	30	CU12PSM6P4XXX(1-3/4)	78.99 - 120.09	1.0000	1.0000
L5	1	Safety Line 3/8	38.92 - 78.99	1.0000	1.0000
L5	4	HB158-1-08U8-S8J18(1-5/8)	38.92 - 78.99	1.0000	1.0000
L5	10	WR-VG82ST-BRDA(5/8)	38.92 - 78.99	1.0000	1.0000
L5	11	WR-VG82ST-BRDA(5/8)	38.92 - 78.99	1.0000	1.0000
L5	12	LDF6-50A(1-1/4)	38.92 - 78.99	1.0000	1.0000
L5	18	LDF7-50A(1-5/8)	38.92 - 78.99	1.0000	1.0000
L5	19	LDF4-50A(1/2)	38.92 - 78.99	1.0000	1.0000
L5	30	CU12PSM6P4XXX(1-3/4)	38.92 - 78.99	1.0000	1.0000
L6	1	Safety Line 3/8	8.00 - 38.92	1.0000	1.0000
L6	4	HB158-1-08U8-S8J18(1-5/8)	8.00 - 38.92	1.0000	1.0000
L6	10	WR-VG82ST-BRDA(5/8)	8.00 - 38.92	1.0000	1.0000
L6	11	WR-VG82ST-BRDA(5/8)	8.00 - 38.92	1.0000	1.0000
L6	12	LDF6-50A(1-1/4)	8.00 - 38.92	1.0000	1.0000
L6	18	LDF7-50A(1-5/8)	8.00 - 38.92	1.0000	1.0000
L6	19	LDF4-50A(1/2)	8.00 - 38.92	1.0000	1.0000
L6	30	CU12PSM6P4XXX(1-3/4)	0.00 - 38.92	1.0000	1.0000

Effective Width of Flat Linear Attachments / Feed Lines

Tower Section	Attachment Record No.	Description	Attachment Segment Elev.	Ratio Calculation Method	Effective Width Ratio
L3	26	PL1x6 Reinforcement -	124.00 -	Manual	1.0000

Tower Section	Attachment Record No.	Description	Attachment Segment Elev.	Ratio Calculation Method	Effective Width Ratio
L3	27	Wind Area/Weight PL1x6 Reinforcement - Wind Area/Weight	134.00 124.00 - 134.00	Manual	1.0000
L3	28	PL1x6 Reinforcement - Wind Area/Weight	124.00 - 134.00	Manual	1.0000

Discrete Tower Loads

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment °	Placement ft
Lightning Rod 5/8"x5'	C	From Leg	4.00 0.00 2.00	0.00	226.00
Flash Beacon Lighting	B	From Leg	4.00 0.00 2.00	0.00	226.00
Beacon side markers	A	From Face	3.00 0.00 0.00	0.00	113.00
Beacon side markers	B	From Face	3.00 0.00 0.00	0.00	113.00
Beacon side markers	C	From Face	3.00 0.00 0.00	0.00	113.00

LPA-80080/6CF w/ Mount Pipe	A	From Leg	3.00 0.00 0.00	0.00	228.00
LPA-80080/6CF w/ Mount Pipe	B	From Leg	3.00 0.00 0.00	0.00	228.00
LPA-80080/6CF w/ Mount Pipe	C	From Leg	3.00 0.00 0.00	0.00	228.00
LPA-80080/6CF w/ Mount Pipe	A	From Face	3.00 0.00 0.00	0.00	228.00
LPA-80080/6CF w/ Mount Pipe	B	From Face	3.00 0.00 0.00	0.00	228.00
LPA-80080/6CF w/ Mount Pipe	C	From Face	3.00 0.00 0.00	0.00	228.00
SBNHH-1D65B w/ Mount Pipe	A	From Leg	3.00 0.00 0.00	0.00	228.00
SBNHH-1D65B w/ Mount Pipe	B	From Leg	3.00 0.00 0.00	0.00	228.00
SBNHH-1D65B w/ Mount Pipe	C	From Leg	3.00 0.00 0.00	0.00	228.00
SBNHH-1D65B w/ Mount Pipe	A	From Leg	3.00 0.00 0.00	0.00	228.00

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment °	Placement ft
			Horz Lateral ft	Vert ft		
SBNHH-1D65B w/ Mount Pipe	B	From Leg	3.00	0.00	0.00	228.00
			0.00			
			0.00			
SBNHH-1D65B w/ Mount Pipe	C	From Leg	3.00	0.00	0.00	228.00
			0.00			
			0.00			
B4 RRH2X60-4R	A	From Leg	3.00	0.00	0.00	228.00
			0.00			
			0.00			
B4 RRH2X60-4R	B	From Leg	3.00	0.00	0.00	228.00
			0.00			
			0.00			
B4 RRH2X60-4R	C	From Leg	3.00	0.00	0.00	228.00
			0.00			
			0.00			
B13 RRH 4X30	A	From Leg	3.00	0.00	0.00	228.00
			0.00			
			0.00			
B13 RRH 4X30	B	From Leg	3.00	0.00	0.00	228.00
			0.00			
			0.00			
B13 RRH 4X30	C	From Leg	3.00	0.00	0.00	228.00
			0.00			
			0.00			
(2) FD9R6004/2C-3L	A	From Leg	3.00	0.00	0.00	228.00
			0.00			
			0.00			
(2) FD9R6004/2C-3L	B	From Leg	3.00	0.00	0.00	228.00
			0.00			
			0.00			
(2) FD9R6004/2C-3L	C	From Leg	3.00	0.00	0.00	228.00
			0.00			
			0.00			
RRFDC-3315-PF-48	B	From Leg	3.00	0.00	0.00	228.00
			0.00			
			0.00			
RRFDC-3315-PF-48	C	From Leg	3.00	0.00	0.00	228.00
			0.00			
			0.00			
Platform Mount (10' LP 101-1)	C	None		0.00		228.00
Side Arm Mount [SO 203-3]	C	None		0.00		228.00
Transition Ladder	C	From Leg	2.00	0.00		228.00
			0.00			
			-2.00			

MX08FRO665-21 w/ Mount Pipe	A	From Leg	4.00	0.00	0.00	218.00
			0.00			
			0.00			
MX08FRO665-21 w/ Mount Pipe	B	From Leg	4.00	0.00	0.00	218.00
			0.00			
			0.00			
MX08FRO665-21 w/ Mount Pipe	C	From Leg	4.00	0.00	0.00	218.00
			0.00			
			0.00			
TA08025-B604	A	From Leg	4.00	0.00	0.00	218.00
			0.00			
			0.00			
TA08025-B604	B	From Leg	4.00	0.00	0.00	218.00
			0.00			
			0.00			
TA08025-B604	C	From Leg	4.00	0.00	0.00	218.00
			0.00			
			0.00			
TA08025-B605	A	From Leg	4.00	0.00	0.00	218.00
			0.00			

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement
			Horz Lateral ft	Vert ft		
TA08025-B605	B	From Leg	0.00	4.00	0.00	218.00
			0.00	0.00		
TA08025-B605	C	From Leg	0.00	4.00	0.00	218.00
			0.00	0.00		
RDIDC-9181-PF-48	A	From Leg	0.00	4.00	0.00	218.00
			0.00	0.00		
(2) 8' x 2" Mount Pipe	A	From Leg	0.00	4.00	0.00	218.00
			0.00	0.00		
(2) 8' x 2" Mount Pipe	B	From Leg	0.00	4.00	0.00	218.00
			0.00	0.00		
(2) 8' x 2" Mount Pipe	C	From Leg	0.00	4.00	0.00	218.00
			0.00	0.00		
Commscope MC-PK8-DSH	C	From Leg	0.00	4.00	0.00	218.00
			0.00	0.00		
*			0.00	0.00		
APX16DWV-16DWV-S-E-A20 w/ Mount Pipe	A	From Leg	3.00	-5.00	0.00	205.00
			2.00	2.00		
APX16DWV-16DWV-S-E-A20 w/ Mount Pipe	B	From Leg	3.00	-5.00	0.00	205.00
			2.00	2.00		
APX16DWV-16DWV-S-E-A20 w/ Mount Pipe	C	From Leg	3.00	-5.00	0.00	205.00
			2.00	2.00		
APXVAARR24_43-U-NA20_T-MOBILE w/ Mount Pipe	A	From Leg	3.00	0.00	0.00	205.00
			2.00	2.00		
APXVAARR24_43-U-NA20_T-MOBILE w/ Mount Pipe	B	From Leg	3.00	0.00	0.00	205.00
			2.00	2.00		
APXVAARR24_43-U-NA20_T-MOBILE w/ Mount Pipe	C	From Leg	3.00	0.00	0.00	205.00
			2.00	2.00		
AIR6449 B41 w/ Mount Pipe	A	From Leg	3.00	5.00	0.00	205.00
			2.00	2.00		
AIR6449 B41 w/ Mount Pipe	B	From Leg	3.00	5.00	0.00	205.00
			2.00	2.00		
AIR6449 B41 w/ Mount Pipe	C	From Leg	3.00	5.00	0.00	205.00
			2.00	2.00		
RADIO 4424	A	From Leg	3.00	0.00	0.00	205.00
			2.00	2.00		
RADIO 4424	B	From Leg	3.00	0.00	0.00	205.00
			2.00	2.00		
RADIO 4424	C	From Leg	3.00	0.00	0.00	205.00
			2.00	2.00		
RADIO 4449 B71 B85A_T-MOBILE	A	From Leg	3.00	0.00	0.00	205.00
			2.00	2.00		
RADIO 4449 B71 B85A_T-MOBILE	B	From Leg	3.00	0.00	0.00	205.00
			2.00	2.00		

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement
			Horz Lateral	Vert ft ft		
RADIO 4449 B71 B85A_T-MOBILE	C	From Leg	3.00	0.00	0.00	205.00
			0.00			
			2.00			
RADIO 4415 B66A_CCIV3	A	From Leg	3.00	0.00	0.00	205.00
			0.00			
			2.00			
RADIO 4415 B66A_CCIV3	B	From Leg	3.00	0.00	0.00	205.00
			0.00			
			2.00			
RADIO 4415 B66A_CCIV3	C	From Leg	3.00	0.00	0.00	205.00
			0.00			
			2.00			
ATSBT-TOP-MF-4G	A	From Face	3.00	0.00	0.00	205.00
			0.00			
			2.00			
ATSBT-TOP-MF-4G	B	From Face	3.00	0.00	0.00	205.00
			0.00			
			2.00			
ATSBT-TOP-MF-4G	C	From Face	3.00	0.00	0.00	205.00
			0.00			
			2.00			
Platform Mount [10.8' LP 712-1]	C	None		0.00	0.00	205.00
Transition Ladder	C	From Leg	2.00	0.00	0.00	205.00
			0.00			
			-4.50			
12.5' x 2.375" Horizontal Mount Pipe	A	From Leg	4.00	0.00	0.00	205.00
			0.00			
			0.00			
12.5' x 2.375" Horizontal Mount Pipe	B	From Leg	4.00	0.00	0.00	205.00
			0.00			
			0.00			
12.5' x 2.375" Horizontal Mount Pipe	C	From Leg	4.00	0.00	0.00	205.00
			0.00			
			0.00			
6' x 2" Horizontal Mount Pipe	A	From Face	2.00	0.00	0.00	205.00
			0.00			
			0.00			
6' x 2" Horizontal Mount Pipe	B	From Face	2.00	0.00	0.00	205.00
			0.00			
			0.00			
6' x 2" Horizontal Mount Pipe	C	From Face	2.00	0.00	0.00	205.00
			0.00			
			0.00			

800 10121 w/ Mount Pipe	A	From Leg	4.00	0.00	0.00	196.00
			0.00			
			0.00			
800 10121 w/ Mount Pipe	B	From Leg	4.00	0.00	0.00	193.00
			0.00			
			0.00			
800 10121 w/ Mount Pipe	C	From Leg	4.00	0.00	0.00	193.00
			0.00			
			0.00			
OPA-65R-LCUU-H6 w/ Mount Pipe	A	From Leg	4.00	0.00	0.00	193.00
			0.00			
			0.00			
OPA-65R-LCUU-H6 w/ Mount Pipe	B	From Leg	4.00	0.00	0.00	193.00
			0.00			
			0.00			
OPA-65R-LCUU-H6 w/ Mount Pipe	C	From Leg	4.00	0.00	0.00	193.00
			0.00			
			0.00			
OPA65R-BU6D w/ Mount Pipe	A	From Leg	4.00	0.00	0.00	193.00
			0.00			
			0.00			

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement
			Horz Lateral ft	Vert ft		
OPA65R-BU6D w/ Mount Pipe	B	From Leg	4.00	0.00	0.00	193.00
			0.00			
			0.00			
OPA65R-BU6D w/ Mount Pipe	C	From Leg	4.00	0.00	0.00	193.00
			0.00			
			0.00			
80010798 w/ Mount Pipe	A	From Leg	4.00	0.00	0.00	193.00
			0.00			
			0.00			
80010798 w/ Mount Pipe	B	From Leg	4.00	0.00	0.00	193.00
			0.00			
			0.00			
80010798 w/ Mount Pipe	C	From Leg	4.00	0.00	0.00	193.00
			0.00			
			0.00			
DTMABP7819VG12A	A	From Leg	4.00	0.00	0.00	193.00
			0.00			
			0.00			
DTMABP7819VG12A	B	From Leg	4.00	0.00	0.00	193.00
			0.00			
			0.00			
DTMABP7819VG12A	C	From Leg	4.00	0.00	0.00	193.00
			0.00			
			0.00			
(2) 860 10025	A	From Leg	4.00	0.00	0.00	193.00
			0.00			
			0.00			
(2) 860 10025	B	From Leg	4.00	0.00	0.00	193.00
			0.00			
			0.00			
(2) 860 10025	C	From Leg	4.00	0.00	0.00	193.00
			0.00			
			0.00			
RRUS 11 B12	A	From Leg	4.00	0.00	0.00	193.00
			0.00			
			0.00			
RRUS 11 B12	B	From Leg	4.00	0.00	0.00	193.00
			0.00			
			0.00			
RRUS 11 B12	C	From Leg	4.00	0.00	0.00	193.00
			0.00			
			0.00			
WCS RRUS-32-B30	A	From Leg	4.00	0.00	0.00	193.00
			0.00			
			0.00			
WCS RRUS-32-B30	B	From Leg	4.00	0.00	0.00	193.00
			0.00			
			0.00			
WCS RRUS-32-B30	C	From Leg	4.00	0.00	0.00	193.00
			0.00			
			0.00			
DC6-48-60-18-8F	B	From Leg	1.00	0.00	0.00	193.00
			0.00			
			0.00			
DC6-48-60-18-8F	A	From Leg	1.00	0.00	0.00	193.00
			0.00			
			0.00			
DC6-48-60-18-8F	B	From Leg	1.00	0.00	0.00	193.00
			0.00			
			0.00			
RRUS 4478 B14_CCIV2	A	From Leg	4.00	0.00	0.00	193.00
			0.00			
			0.00			
RRUS 4478 B14_CCIV2	B	From Leg	4.00	0.00	0.00	193.00

Description	Face or Leg	Offset Type	Offsets:			Azimuth Adjustment	Placement
			Horz	Lateral	Vert		
			ft	ft	ft		
RRUS 4478 B14_CCIV2	C	From Leg	0.00	4.00	0.00	0.00	193.00
			0.00	0.00	0.00		
RRUS 32 B2_CCIV2	A	From Leg	4.00	0.00	0.00	0.00	193.00
			0.00	0.00	0.00		
RRUS 32 B2_CCIV2	B	From Leg	4.00	0.00	0.00	0.00	193.00
			0.00	0.00	0.00		
RRUS 32 B2_CCIV2	C	From Leg	4.00	0.00	0.00	0.00	193.00
			0.00	0.00	0.00		
DBC0061F1V51-2	A	From Leg	4.00	0.00	0.00	0.00	193.00
			0.00	0.00	0.00		
DBC0061F1V51-2	B	From Leg	4.00	0.00	0.00	0.00	193.00
			0.00	0.00	0.00		
DBC0061F1V51-2	C	From Leg	4.00	0.00	0.00	0.00	193.00
			0.00	0.00	0.00		
RRUS 4426 B66	A	From Leg	4.00	0.00	0.00	0.00	193.00
			0.00	0.00	0.00		
RRUS 4426 B66	B	From Leg	4.00	0.00	0.00	0.00	193.00
			0.00	0.00	0.00		
RRUS 4426 B66	C	From Leg	4.00	0.00	0.00	0.00	193.00
			0.00	0.00	0.00		
Sabre C10857333C [SM 504-3] Transition Ladder	C	None				0.00	193.00
	C	From Leg	2.00	0.00	0.00	0.00	193.00
			0.00	0.00	0.00		
***			-2.00				
APXV18-206517S-C w/ Mount Pipe	A	From Leg	3.00	0.00	0.00	0.00	185.00
			0.00	0.00	0.00		
APXV18-206517S-C w/ Mount Pipe	B	From Leg	3.00	0.00	0.00	0.00	185.00
			0.00	0.00	0.00		
APXV18-206517S-C w/ Mount Pipe	C	From Leg	3.00	0.00	0.00	0.00	185.00
			0.00	0.00	0.00		
978QNB120E-M w/ Mount Pipe	A	From Leg	3.00	0.00	0.00	0.00	185.00
			0.00	0.00	0.00		
978QNB120E-M w/ Mount Pipe	B	From Leg	3.00	0.00	0.00	0.00	185.00
			0.00	0.00	0.00		
978QNB120E-M w/ Mount Pipe	C	From Leg	3.00	0.00	0.00	0.00	185.00
			0.00	0.00	0.00		
FV90-16-02DP w/ Mount Pipe	A	From Leg	3.00	0.00	0.00	0.00	185.00
			0.00	0.00	0.00		
FV90-16-02DP w/ Mount Pipe	B	From Leg	3.00	0.00	0.00	0.00	185.00
			0.00	0.00	0.00		
FV90-16-02DP w/ Mount Pipe	C	From Leg	3.00	0.00	0.00	0.00	185.00
			0.00	0.00	0.00		
FV90-16-02DP w/ Mount Pipe	A	From Leg	3.00	0.00	0.00	0.00	185.00
			0.00	0.00	0.00		

Description	Face or Leg	Offset Type	Offsets:			Azimuth Adjustment	Placement
			Horz	Lateral	Vert		
			ft	ft	ft		
FV90-16-02DP w/ Mount Pipe	B	From Leg	2.00	3.00	0.00	185.00	
			0.00	2.00			
FV90-16-02DP w/ Mount Pipe	C	From Leg	3.00	0.00	0.00	185.00	
			2.00	3.00			
CS72993.07	A	From Leg	3.00	0.00	0.00	185.00	
			2.00	3.00			
CS72993.07	B	From Leg	3.00	0.00	0.00	185.00	
			2.00	3.00			
CS72993.07	C	From Leg	3.00	0.00	0.00	185.00	
			2.00	3.00			
Platform Mount [LP 712-1]	C	None	2.00	0.00	0.00	185.00	
Transition Ladder	C	From Leg	0.00	2.00	0.00	185.00	
			-2.00				

800 EXTERNAL NOTCH FILTER	A	From Leg	1.00	0.00	0.00	173.00	
			0.00	1.00			
800 EXTERNAL NOTCH FILTER	B	From Leg	1.00	0.00	0.00	173.00	
			0.00	1.00			
800 EXTERNAL NOTCH FILTER	C	From Leg	1.00	0.00	0.00	173.00	
			0.00	1.00			
(3) ACU-A20-N	A	From Leg	1.00	0.00	0.00	173.00	
			0.00	1.00			
(3) ACU-A20-N	B	From Leg	1.00	0.00	0.00	173.00	
			0.00	1.00			
(3) ACU-A20-N	C	From Leg	1.00	0.00	0.00	173.00	
			0.00	1.00			
1900MHz RRH (65MHz)	A	From Leg	1.00	0.00	0.00	173.00	
			0.00	1.00			
1900MHz RRH (65MHz)	B	From Leg	1.00	0.00	0.00	173.00	
			0.00	1.00			
1900MHz RRH (65MHz)	C	From Leg	1.00	0.00	0.00	173.00	
			0.00	1.00			
800MHZ RRH	A	From Leg	1.00	0.00	0.00	173.00	
			0.00	1.00			
800MHZ RRH	B	From Leg	1.00	0.00	0.00	173.00	
			0.00	1.00			
800MHZ RRH	C	From Leg	1.00	0.00	0.00	173.00	
			0.00	1.00			
6'x2" Mount Pipe	A	From Leg	0.50	0.00	0.00	173.00	
			0.00	0.50			
6'x2" Mount Pipe	B	From Leg	0.50	0.00	0.00	173.00	
			0.00	0.50			
6'x2" Mount Pipe	C	From Leg	0.50	0.00	0.00	173.00	
			0.00	0.50			

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment °	Placement ft
			Horz Lateral ft	Vert ft		
Side Arm Mount [SO 102-3] ***	C	None		0.00	0.00	173.00
APXVTM14-C-120 w/ Mount Pipe	A	From Leg	4.00	0.00	0.00	172.00
APXVTM14-C-120 w/ Mount Pipe	B	From Leg	4.00	0.00	0.00	172.00
APXVTM14-C-120 w/ Mount Pipe	C	From Leg	4.00	0.00	0.00	172.00
APXVSP18-C-A20 w/ Mount Pipe	A	From Leg	4.00	0.00	0.00	172.00
APXVSP18-C-A20 w/ Mount Pipe	B	From Leg	4.00	0.00	0.00	172.00
APXVSP18-C-A20 w/ Mount Pipe	C	From Leg	4.00	0.00	0.00	172.00
TD-RRH8x20-25	A	From Leg	4.00	0.00	0.00	172.00
TD-RRH8x20-25	B	From Leg	4.00	0.00	0.00	172.00
TD-RRH8x20-25	C	From Leg	4.00	0.00	0.00	172.00
Platform Mount [LP 1201-1] 6"x2" Mount Pipe	C	None			0.00	172.00
6"x2" Mount Pipe	A	From Leg	4.00	0.00	0.00	172.00
6"x2" Mount Pipe	B	From Leg	4.00	0.00	0.00	172.00
6"x2" Mount Pipe	C	From Leg	4.00	0.00	0.00	172.00
6"x2" Mount Pipe	A	From Leg	4.00	0.00	0.00	172.00
6"x2" Mount Pipe	B	From Leg	4.00	0.00	0.00	172.00
6"x2" Mount Pipe	C	From Leg	4.00	0.00	0.00	172.00
*** Side Arm Mount [SO 701-1]	A	From Leg	0.00	0.00	0.00	72.00
GPS_A	A	From Leg	3.00	0.00	0.00	72.00
***			1.00			

Load Combinations

Comb. No.	Description
1	Dead Only
2	1.2 Dead+1.0 Wind 0 deg - No Ice
3	0.9 Dead+1.0 Wind 0 deg - No Ice
4	1.2 Dead+1.0 Wind 30 deg - No Ice
5	0.9 Dead+1.0 Wind 30 deg - No Ice
6	1.2 Dead+1.0 Wind 60 deg - No Ice
7	0.9 Dead+1.0 Wind 60 deg - No Ice
8	1.2 Dead+1.0 Wind 90 deg - No Ice
9	0.9 Dead+1.0 Wind 90 deg - No Ice
10	1.2 Dead+1.0 Wind 120 deg - No Ice
11	0.9 Dead+1.0 Wind 120 deg - No Ice
12	1.2 Dead+1.0 Wind 150 deg - No Ice
13	0.9 Dead+1.0 Wind 150 deg - No Ice
14	1.2 Dead+1.0 Wind 180 deg - No Ice
15	0.9 Dead+1.0 Wind 180 deg - No Ice
16	1.2 Dead+1.0 Wind 210 deg - No Ice
17	0.9 Dead+1.0 Wind 210 deg - No Ice
18	1.2 Dead+1.0 Wind 240 deg - No Ice
19	0.9 Dead+1.0 Wind 240 deg - No Ice
20	1.2 Dead+1.0 Wind 270 deg - No Ice
21	0.9 Dead+1.0 Wind 270 deg - No Ice
22	1.2 Dead+1.0 Wind 300 deg - No Ice
23	0.9 Dead+1.0 Wind 300 deg - No Ice
24	1.2 Dead+1.0 Wind 330 deg - No Ice
25	0.9 Dead+1.0 Wind 330 deg - No Ice
26	1.2 Dead+1.0 Ice+1.0 Temp
27	1.2 Dead+1.0 Wind 0 deg+1.0 Ice+1.0 Temp
28	1.2 Dead+1.0 Wind 30 deg+1.0 Ice+1.0 Temp
29	1.2 Dead+1.0 Wind 60 deg+1.0 Ice+1.0 Temp
30	1.2 Dead+1.0 Wind 90 deg+1.0 Ice+1.0 Temp
31	1.2 Dead+1.0 Wind 120 deg+1.0 Ice+1.0 Temp
32	1.2 Dead+1.0 Wind 150 deg+1.0 Ice+1.0 Temp
33	1.2 Dead+1.0 Wind 180 deg+1.0 Ice+1.0 Temp
34	1.2 Dead+1.0 Wind 210 deg+1.0 Ice+1.0 Temp
35	1.2 Dead+1.0 Wind 240 deg+1.0 Ice+1.0 Temp
36	1.2 Dead+1.0 Wind 270 deg+1.0 Ice+1.0 Temp
37	1.2 Dead+1.0 Wind 300 deg+1.0 Ice+1.0 Temp
38	1.2 Dead+1.0 Wind 330 deg+1.0 Ice+1.0 Temp
39	Dead+Wind 0 deg - Service
40	Dead+Wind 30 deg - Service
41	Dead+Wind 60 deg - Service
42	Dead+Wind 90 deg - Service
43	Dead+Wind 120 deg - Service
44	Dead+Wind 150 deg - Service
45	Dead+Wind 180 deg - Service
46	Dead+Wind 210 deg - Service
47	Dead+Wind 240 deg - Service
48	Dead+Wind 270 deg - Service
49	Dead+Wind 300 deg - Service
50	Dead+Wind 330 deg - Service

Maximum Member Forces

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Axial K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
L1	225.79 - 197.75	Pole	Max Tension	26	0.00	-0.00	0.00
			Max. Compression	26	-30.58	16.74	-10.58
			Max. Mx	20	-11.08	265.56	-5.68
			Max. My	14	-11.10	9.38	-260.77
			Max. Vy	20	-15.66	265.56	-5.68
			Max. Vx	14	15.63	9.38	-260.77
			Max. Torque	24			8.90
L2	197.75 - 162.72	Pole	Max Tension	1	0.00	0.00	0.00

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Axial K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
L3	162.72 - 120.09	Pole	Max. Compression	26	-69.71	22.12	-14.23
			Max. Mx	20	-28.90	1082.62	-6.86
			Max. My	14	-28.94	11.23	-1073.66
			Max. Vy	20	-31.62	1082.62	-6.86
			Max. Vx	14	31.40	11.23	-1073.66
			Max. Torque	24			10.22
			Max Tension	1	0.00	0.00	0.00
L4	120.09 - 78.99	Pole	Max. Compression	26	-89.82	26.49	-17.73
			Max. Mx	20	-43.10	2480.96	-7.71
			Max. My	14	-43.15	12.35	-2457.81
			Max. Vy	20	-35.89	2480.96	-7.71
			Max. Vx	14	35.43	12.35	-2457.81
			Max. Torque	24			10.20
			Max Tension	1	0.00	0.00	0.00
L5	78.99 - 38.92	Pole	Max. Compression	26	-113.86	30.45	-21.12
			Max. Mx	20	-60.98	4000.53	-8.47
			Max. My	14	-61.02	13.28	-3957.34
			Max. Vy	20	-40.03	4000.53	-8.47
			Max. Vx	14	39.53	13.28	-3957.34
			Max. Torque	24			10.16
			Max Tension	1	0.00	0.00	0.00
L6	38.92 - 0	Pole	Max. Compression	26	-142.86	34.16	-24.04
			Max. Mx	20	-83.48	5637.40	-9.00
			Max. My	14	-83.50	14.12	-5573.88
			Max. Vy	20	-43.80	5637.40	-9.00
			Max. Vx	14	43.28	14.12	-5573.88
			Max. Torque	24			10.14
			Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-181.79	37.63	-27.02
			Max. Mx	20	-115.05	7813.24	-9.67
			Max. My	14	-115.05	14.98	-7725.10
			Max. Vy	20	-47.29	7813.24	-9.67
			Max. Vx	14	46.78	14.98	-7725.10
			Max. Torque	24			10.04

Maximum Reactions

Location	Condition	Gov. Load Comb.	Vertical K	Horizontal, X K	Horizontal, Z K
Pole	Max. Vert	35	181.79	11.78	-6.80
	Max. H _x	20	115.07	47.24	-0.00
	Max. H _z	2	115.07	0.00	46.73
	Max. M _x	2	7705.71	0.00	46.73
	Max. M _z	8	7783.25	-47.24	-0.00
	Max. Torsion	24	10.04	23.39	40.47
	Min. Vert	17	86.31	23.39	-40.47
	Min. H _x	8	115.07	-47.24	-0.00
	Min. H _z	14	115.07	0.00	-46.73
	Min. M _x	14	-7725.10	0.00	-46.73
	Min. M _z	20	-7813.24	47.24	-0.00
	Min. Torsion	12	-10.02	-23.39	-40.47

Tower Mast Reaction Summary

Load Combination	Vertical K	Shear _x K	Shear _z K	Overtuning Moment, M _x kip-ft	Overtuning Moment, M _z kip-ft	Torque kip-ft

Load Combination	Vertical K	Shear _x K	Shear _z K	Overturning Moment, M _x kip-ft	Overturning Moment, M _z kip-ft	Torque kip-ft
Dead Only	95.89	-0.00	0.00	7.89	12.21	-0.00
1.2 Dead+1.0 Wind 0 deg - No Ice	115.07	-0.00	-46.73	-7705.71	14.98	-8.39
0.9 Dead+1.0 Wind 0 deg - No Ice	86.31	-0.00	-46.73	-7585.61	10.90	-8.37
1.2 Dead+1.0 Wind 30 deg - No Ice	115.07	23.39	-40.47	-6672.04	-3845.85	-4.50
0.9 Dead+1.0 Wind 30 deg - No Ice	86.31	23.39	-40.47	-6568.38	-3788.52	-4.49
1.2 Dead+1.0 Wind 60 deg - No Ice	115.07	40.51	-23.37	-3848.01	-6672.17	0.59
0.9 Dead+1.0 Wind 60 deg - No Ice	86.31	40.51	-23.37	-3789.27	-6569.87	0.59
1.2 Dead+1.0 Wind 90 deg - No Ice	115.07	47.24	0.00	9.67	-7783.25	5.52
0.9 Dead+1.0 Wind 90 deg - No Ice	86.31	47.24	0.00	7.04	-7663.44	5.50
1.2 Dead+1.0 Wind 120 deg - No Ice	115.07	41.84	24.13	3999.00	-6900.19	8.97
0.9 Dead+1.0 Wind 120 deg - No Ice	86.31	41.84	24.13	3933.07	-6794.55	8.94
1.2 Dead+1.0 Wind 150 deg - No Ice	115.07	23.39	40.47	6691.42	-3845.87	10.02
0.9 Dead+1.0 Wind 150 deg - No Ice	86.31	23.39	40.47	6582.49	-3788.53	9.99
1.2 Dead+1.0 Wind 180 deg - No Ice	115.07	-0.00	46.73	7725.10	14.98	8.39
0.9 Dead+1.0 Wind 180 deg - No Ice	86.31	-0.00	46.73	7599.73	10.90	8.36
1.2 Dead+1.0 Wind 210 deg - No Ice	115.07	-23.39	40.47	6691.44	3875.84	4.51
0.9 Dead+1.0 Wind 210 deg - No Ice	86.31	-23.39	40.47	6582.51	3810.33	4.50
1.2 Dead+1.0 Wind 240 deg - No Ice	115.07	-40.51	23.37	3867.38	6702.17	-0.58
0.9 Dead+1.0 Wind 240 deg - No Ice	86.31	-40.51	23.37	3803.38	6591.70	-0.57
1.2 Dead+1.0 Wind 270 deg - No Ice	115.07	-47.24	0.00	9.67	7813.24	-5.52
0.9 Dead+1.0 Wind 270 deg - No Ice	86.31	-47.24	0.00	7.04	7685.27	-5.50
1.2 Dead+1.0 Wind 300 deg - No Ice	115.07	-41.84	-24.13	-3979.67	6930.14	-8.98
0.9 Dead+1.0 Wind 300 deg - No Ice	86.31	-41.84	-24.13	-3919.00	6816.34	-8.95
1.2 Dead+1.0 Wind 330 deg - No Ice	115.07	-23.39	-40.47	-6672.06	3875.82	-10.04
0.9 Dead+1.0 Wind 330 deg - No Ice	86.31	-23.39	-40.47	-6568.40	3810.32	-10.00
1.2 Dead+1.0 Ice+1.0 Temp	181.79	-0.00	0.00	27.02	37.63	-0.00
1.2 Dead+1.0 Wind 0 deg+1.0 Ice+1.0 Temp	181.79	-0.00	-13.59	-2365.84	37.82	-4.86
1.2 Dead+1.0 Wind 30 deg+1.0 Ice+1.0 Temp	181.79	6.80	-11.77	-2045.22	-1159.49	-2.72
1.2 Dead+1.0 Wind 60 deg+1.0 Ice+1.0 Temp	181.79	11.78	-6.80	-1169.33	-2035.97	0.15
1.2 Dead+1.0 Wind 90 deg+1.0 Ice+1.0 Temp	181.79	13.61	0.00	27.15	-2356.80	2.98
1.2 Dead+1.0 Wind 120 deg+1.0 Ice+1.0 Temp	181.79	11.78	6.80	1223.65	-2036.00	5.01
1.2 Dead+1.0 Wind 150 deg+1.0 Ice+1.0 Temp	181.79	6.80	11.77	2099.57	-1159.52	5.69
1.2 Dead+1.0 Wind 180 deg+1.0 Ice+1.0 Temp	181.79	-0.00	13.59	2420.19	37.81	4.86
1.2 Dead+1.0 Wind 210 deg+1.0 Ice+1.0 Temp	181.79	-6.80	11.77	2099.60	1235.16	2.72
1.2 Dead+1.0 Wind 240 deg+1.0 Ice+1.0 Temp	181.79	-11.78	6.80	1223.68	2111.68	-0.15
1.2 Dead+1.0 Wind 270 deg+1.0 Ice+1.0 Temp	181.79	-13.61	0.00	27.15	2432.51	-2.98

Load Combination	Vertical K	Shear _x K	Shear _z K	Overturning Moment, M _x kip-ft	Overturning Moment, M _z kip-ft	Torque kip-ft
deg+1.0 Ice+1.0 Temp						
1.2 Dead+1.0 Wind 300	181.79	-11.78	-6.80	-1169.37	2111.67	-5.01
deg+1.0 Ice+1.0 Temp						
1.2 Dead+1.0 Wind 330	181.79	-6.80	-11.77	-2045.26	1235.14	-5.70
deg+1.0 Ice+1.0 Temp						
Dead+Wind 0 deg - Service	95.89	-0.00	-11.01	-1792.98	12.42	-2.00
Dead+Wind 30 deg - Service	95.89	5.51	-9.53	-1551.71	-888.83	-1.07
Dead+Wind 60 deg - Service	95.89	9.54	-5.50	-892.49	-1548.58	0.14
Dead+Wind 90 deg - Service	95.89	11.13	0.00	8.02	-1807.98	1.32
Dead+Wind 120 deg - Service	95.89	9.85	5.68	939.36	-1601.97	2.14
Dead+Wind 150 deg - Service	95.89	5.51	9.53	1567.75	-888.83	2.39
Dead+Wind 180 deg - Service	95.89	-0.00	11.01	1809.02	12.42	2.00
Dead+Wind 210 deg - Service	95.89	-5.51	9.53	1567.75	913.66	1.07
Dead+Wind 240 deg - Service	95.89	-9.54	5.50	908.53	1573.42	-0.14
Dead+Wind 270 deg - Service	95.89	-11.13	0.00	8.02	1832.81	-1.32
Dead+Wind 300 deg - Service	95.89	-9.85	-5.68	-923.31	1626.80	-2.14
Dead+Wind 330 deg - Service	95.89	-5.51	-9.53	-1551.71	913.66	-2.39

Solution Summary

Load Comb.	Sum of Applied Forces			Sum of Reactions			% Error
	PX K	PY K	PZ K	PX K	PY K	PZ K	
1	0.00	-95.89	0.00	0.00	95.89	-0.00	0.000%
2	0.00	-115.07	-46.73	0.00	115.07	46.73	0.000%
3	0.00	-86.31	-46.73	0.00	86.31	46.73	0.000%
4	23.39	-115.07	-40.47	-23.39	115.07	40.47	0.000%
5	23.39	-86.31	-40.47	-23.39	86.31	40.47	0.000%
6	40.51	-115.07	-23.37	-40.51	115.07	23.37	0.000%
7	40.51	-86.31	-23.37	-40.51	86.31	23.37	0.000%
8	47.24	-115.07	0.00	-47.24	115.07	-0.00	0.000%
9	47.24	-86.31	0.00	-47.24	86.31	-0.00	0.000%
10	41.84	-115.07	24.13	-41.84	115.07	-24.13	0.000%
11	41.84	-86.31	24.13	-41.84	86.31	-24.13	0.000%
12	23.39	-115.07	40.47	-23.39	115.07	-40.47	0.000%
13	23.39	-86.31	40.47	-23.39	86.31	-40.47	0.000%
14	0.00	-115.07	46.73	0.00	115.07	-46.73	0.000%
15	0.00	-86.31	46.73	0.00	86.31	-46.73	0.000%
16	-23.39	-115.07	40.47	23.39	115.07	-40.47	0.000%
17	-23.39	-86.31	40.47	23.39	86.31	-40.47	0.000%
18	-40.51	-115.07	23.37	40.51	115.07	-23.37	0.000%
19	-40.51	-86.31	23.37	40.51	86.31	-23.37	0.000%
20	-47.24	-115.07	0.00	47.24	115.07	-0.00	0.000%
21	-47.24	-86.31	0.00	47.24	86.31	-0.00	0.000%
22	-41.84	-115.07	-24.13	41.84	115.07	24.13	0.000%
23	-41.84	-86.31	-24.13	41.84	86.31	24.13	0.000%
24	-23.39	-115.07	-40.47	23.39	115.07	40.47	0.000%
25	-23.39	-86.31	-40.47	23.39	86.31	40.47	0.000%
26	0.00	-181.79	0.00	0.00	181.79	-0.00	0.000%
27	0.00	-181.79	-13.59	0.00	181.79	13.59	0.000%
28	6.80	-181.79	-11.77	-6.80	181.79	11.77	0.000%
29	11.78	-181.79	-6.80	-11.78	181.79	6.80	0.000%
30	13.61	-181.79	0.00	-13.61	181.79	-0.00	0.000%
31	11.78	-181.79	6.80	-11.78	181.79	-6.80	0.000%
32	6.80	-181.79	11.77	-6.80	181.79	-11.77	0.000%
33	0.00	-181.79	13.59	0.00	181.79	-13.59	0.000%
34	-6.80	-181.79	11.77	6.80	181.79	-11.77	0.000%
35	-11.78	-181.79	6.80	11.78	181.79	-6.80	0.000%

Load Comb.	Sum of Applied Forces			Sum of Reactions			% Error
	PX K	PY K	PZ K	PX K	PY K	PZ K	
36	-13.61	-181.79	0.00	13.61	181.79	-0.00	0.000%
37	-11.78	-181.79	-6.80	11.78	181.79	6.80	0.000%
38	-6.80	-181.79	-11.77	6.80	181.79	11.77	0.000%
39	0.00	-95.89	-11.01	0.00	95.89	11.01	0.000%
40	5.51	-95.89	-9.53	-5.51	95.89	9.53	0.000%
41	9.54	-95.89	-5.50	-9.54	95.89	5.50	0.000%
42	11.13	-95.89	0.00	-11.13	95.89	-0.00	0.000%
43	9.85	-95.89	5.68	-9.85	95.89	-5.68	0.000%
44	5.51	-95.89	9.53	-5.51	95.89	-9.53	0.000%
45	0.00	-95.89	11.01	0.00	95.89	-11.01	0.000%
46	-5.51	-95.89	9.53	5.51	95.89	-9.53	0.000%
47	-9.54	-95.89	5.50	9.54	95.89	-5.50	0.000%
48	-11.13	-95.89	0.00	11.13	95.89	-0.00	0.000%
49	-9.85	-95.89	-5.68	9.85	95.89	5.68	0.000%
50	-5.51	-95.89	-9.53	5.51	95.89	9.53	0.000%

Non-Linear Convergence Results

Load Combination	Converged?	Number of Cycles	Displacement Tolerance	Force Tolerance
1	Yes	4	0.00000001	0.00000379
2	Yes	5	0.00000001	0.00082353
3	Yes	5	0.00000001	0.00040329
4	Yes	6	0.00000001	0.00040681
5	Yes	6	0.00000001	0.00013749
6	Yes	6	0.00000001	0.00041960
7	Yes	6	0.00000001	0.00014235
8	Yes	5	0.00000001	0.00056084
9	Yes	5	0.00000001	0.00027384
10	Yes	6	0.00000001	0.00048920
11	Yes	6	0.00000001	0.00016554
12	Yes	6	0.00000001	0.00039367
13	Yes	6	0.00000001	0.00013197
14	Yes	5	0.00000001	0.00082549
15	Yes	5	0.00000001	0.00040355
16	Yes	6	0.00000001	0.00044955
17	Yes	6	0.00000001	0.00015208
18	Yes	6	0.00000001	0.00043534
19	Yes	6	0.00000001	0.00014658
20	Yes	5	0.00000001	0.00056282
21	Yes	5	0.00000001	0.00027403
22	Yes	6	0.00000001	0.00042374
23	Yes	6	0.00000001	0.00014027
24	Yes	6	0.00000001	0.00046954
25	Yes	6	0.00000001	0.00016053
26	Yes	4	0.00000001	0.00045554
27	Yes	6	0.00000001	0.00037102
28	Yes	6	0.00000001	0.00045823
29	Yes	6	0.00000001	0.00046772
30	Yes	6	0.00000001	0.00034620
31	Yes	6	0.00000001	0.00054413
32	Yes	6	0.00000001	0.00048225
33	Yes	6	0.00000001	0.00038675
34	Yes	6	0.00000001	0.00056000
35	Yes	6	0.00000001	0.00053702
36	Yes	6	0.00000001	0.00036798
37	Yes	6	0.00000001	0.00049235
38	Yes	6	0.00000001	0.00056720
39	Yes	4	0.00000001	0.00065585
40	Yes	5	0.00000001	0.00007056
41	Yes	5	0.00000001	0.00007632
42	Yes	4	0.00000001	0.00046577
43	Yes	5	0.00000001	0.00011463
44	Yes	5	0.00000001	0.00007172
45	Yes	4	0.00000001	0.00067089

46	Yes	5	0.00000001	0.00009921
47	Yes	5	0.00000001	0.00008970
48	Yes	4	0.00000001	0.00048295
49	Yes	5	0.00000001	0.00007956
50	Yes	5	0.00000001	0.00011278

Maximum Tower Deflections - Service Wind

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
L1	225.79 - 197.75	38.9892	49	1.75	0.02
L2	201.83 - 162.72	30.5337	49	1.58	0.01
L3	167.86 - 120.09	20.2216	49	1.28	0.01
L4	126.48 - 78.99	10.7797	49	0.87	0.00
L5	86.57 - 38.92	4.8334	49	0.54	0.00
L6	47.64 - 0	1.4580	49	0.28	0.00

Critical Deflections and Radius of Curvature - Service Wind

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
228.00	LPA-80080/6CF w/ Mount Pipe	49	38.9892	1.75	0.02	27001
226.00	Lightning Rod 5/8"x5'	49	38.9892	1.75	0.02	27001
218.00	MX08FRO665-21 w/ Mount Pipe	49	36.1853	1.70	0.02	17331
205.00	APX16DWV-16DWV-S-E-A20 w/ Mount Pipe	49	31.6119	1.60	0.01	6506
196.00	800 10121 w/ Mount Pipe	49	28.6015	1.53	0.01	5707
193.00	800 10121 w/ Mount Pipe	49	27.6335	1.51	0.01	5745
185.00	APXV18-206517S-C w/ Mount Pipe	49	25.1389	1.44	0.01	5850
173.00	800 EXTERNAL NOTCH FILTER	49	21.6350	1.33	0.01	6015
172.00	APXVTM14-C-120 w/ Mount Pipe	49	21.3559	1.32	0.01	6030
113.00	Beacon side markers	49	8.4529	0.75	0.00	6476
72.00	Side Arm Mount [SO 701-1]	49	3.2992	0.43	0.00	7934

Maximum Tower Deflections - Design Wind

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
L1	225.79 - 197.75	165.7163	22	7.38	0.09
L2	201.83 - 162.72	130.0911	22	6.71	0.05
L3	167.86 - 120.09	86.3136	22	5.48	0.02
L4	126.48 - 78.99	46.0623	22	3.72	0.01
L5	86.57 - 38.92	20.6602	22	2.29	0.01
L6	47.64 - 0	6.2316	22	1.18	0.00

Critical Deflections and Radius of Curvature - Design Wind

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
228.00	LPA-80080/6CF w/ Mount Pipe	22	165.7163	7.38	0.09	7424

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
226.00	Lightning Rod 5/8"x5'	22	165.7163	7.38	0.09	7424
218.00	MX08FRO665-21 w/ Mount Pipe	22	153.9169	7.17	0.07	4765
205.00	APX16DWV-16DWV-S-E-A20 w/ Mount Pipe	22	134.6446	6.80	0.05	1785
196.00	800 10121 w/ Mount Pipe	22	121.9185	6.52	0.04	1532
193.00	800 10121 w/ Mount Pipe	22	117.8175	6.42	0.04	1525
185.00	APXV18-206517S-C w/ Mount Pipe	22	107.2328	6.14	0.03	1504
173.00	800 EXTERNAL NOTCH FILTER	22	92.3314	5.69	0.03	1462
172.00	APXVTM14-C-120 w/ Mount Pipe	22	91.1433	5.65	0.03	1459
113.00	Beacon side markers	22	36.1273	3.20	0.01	1530
72.00	Side Arm Mount [SO 701-1]	22	14.1020	1.85	0.00	1859

Compression Checks

Pole Design Data

Section No.	Elevation ft	Size	L ft	L_u ft	KI/r	A in^2	P_u K	ϕP_n K	Ratio $\frac{P_u}{\phi P_n}$
L1	225.79 - 197.75 (1)	TP28.6563x21.5x0.1875	28.04	0.00	0.0	16.322 8	-11.09	954.88	0.012
L2	197.75 - 162.72 (2)	TP37.0938x27.24x0.375	39.11	0.00	0.0	42.163 1	-28.78	2466.54	0.012
L3	162.72 - 120.09 (3)	TP47.1563x35.0487x0.43 75	47.77	0.00	0.0	62.625 8	-43.00	3663.61	0.012
L4	120.09 - 78.99 (4)	TP56.6563x44.6617x0.5	47.49	0.00	0.0	86.081 7	-60.90	5035.78	0.012
L5	78.99 - 38.92 (5)	TP65.7813x53.7418x0.56 25	47.65	0.00	0.0	112.50 60	-83.44	6581.62	0.013
L6	38.92 - 0 (6)	TP74.5x62.453x0.5625	47.64	0.00	0.0	132.00 60	-115.05	7722.36	0.015

Pole Bending Design Data

Section No.	Elevation ft	Size	M_{ux} kip-ft	ϕM_{nx} kip-ft	Ratio $\frac{M_{ux}}{\phi M_{nx}}$	M_{uy} kip-ft	ϕM_{ny} kip-ft	Ratio $\frac{M_{uy}}{\phi M_{ny}}$
L1	225.79 - 197.75 (1)	TP28.6563x21.5x0.1875	266.97	596.72	0.447	0.00	596.72	0.000
L2	197.75 - 162.72 (2)	TP37.0938x27.24x0.375	1096.24	2275.65	0.482	0.00	2275.65	0.000
L3	162.72 - 120.09 (3)	TP47.1563x35.0487x0.43 75	2525.68	4220.43	0.598	0.00	4220.43	0.000
L4	120.09 - 78.99 (4)	TP56.6563x44.6617x0.5	4084.65	6884.04	0.593	0.00	6884.04	0.000
L5	78.99 - 38.92 (5)	TP65.7813x53.7418x0.56 25	5764.42	10359.42	0.556	0.00	10359.42	0.000
L6	38.92 - 0 (6)	TP74.5x62.453x0.5625	7991.53	13554.17	0.590	0.00	13554.17	0.000

Pole Shear Design Data

Section No.	Elevation ft	Size	Actual V_u K	ϕV_n K	Ratio V_u ϕV_n	Actual T_u kip-ft	ϕT_n kip-ft	Ratio T_u ϕT_n
L1	225.79 - 197.75 (1)	TP28.6563x21.5x0.1875	15.65	286.46	0.055	0.68	688.08	0.001
L2	197.75 - 162.72 (2)	TP37.0938x27.24x0.375	32.24	739.96	0.044	9.21	2295.53	0.004
L3	162.72 - 120.09 (3)	TP47.1563x35.0487x0.4375	36.79	1099.08	0.033	9.17	4340.89	0.002
L4	120.09 - 78.99 (4)	TP56.6563x44.6617x0.5	41.12	1510.73	0.027	9.15	7176.32	0.001
L5	78.99 - 38.92 (5)	TP65.7813x53.7418x0.5625	44.90	1974.49	0.023	8.98	10896.33	0.001
L6	38.92 - 0 (6)	TP74.5x62.453x0.5625	48.35	2316.71	0.021	8.98	15000.83	0.001

Pole Interaction Design Data


Section No.	Elevation ft	Ratio P_u ϕP_n	Ratio M_{ux} ϕM_{nx}	Ratio M_{uy} ϕM_{ny}	Ratio V_u ϕV_n	Ratio T_u ϕT_n	Comb. Stress Ratio	Allow. Stress Ratio	Criteria
L1	225.79 - 197.75 (1)	0.012	0.447	0.000	0.055	0.001	0.462	1.050	4.8.2
L2	197.75 - 162.72 (2)	0.012	0.482	0.000	0.044	0.004	0.496	1.050	4.8.2
L3	162.72 - 120.09 (3)	0.012	0.598	0.000	0.033	0.002	0.611	1.050	4.8.2
L4	120.09 - 78.99 (4)	0.012	0.593	0.000	0.027	0.001	0.606	1.050	4.8.2
L5	78.99 - 38.92 (5)	0.013	0.556	0.000	0.023	0.001	0.570	1.050	4.8.2
L6	38.92 - 0 (6)	0.015	0.590	0.000	0.021	0.001	0.605	1.050	4.8.2

Section Capacity Table

Section No.	Elevation ft	Component Type	Size	Critical Element	P K	ϕP_{allow} K	% Capacity	Pass Fail
L1	225.79 - 197.75	Pole	TP28.6563x21.5x0.1875	1	-11.09	1002.63	44.0	Pass
L2	197.75 - 162.72	Pole	TP37.0938x27.24x0.375	2	-28.78	2589.87	47.2	Pass
L3	162.72 - 120.09	Pole	TP47.1563x35.0487x0.4375	3	-43.00	3846.79	58.2	Pass
L4	120.09 - 78.99	Pole	TP56.6563x44.6617x0.5	4	-60.90	5287.57	57.7	Pass
L5	78.99 - 38.92	Pole	TP65.7813x53.7418x0.5625	5	-83.44	6910.70	54.3	Pass
L6	38.92 - 0	Pole	TP74.5x62.453x0.5625	6	-115.05	8108.48	57.6	Pass
Summary								
Pole (L3)							58.2	Pass
RATING =							58.2	Pass

***NOTE: Above stress ratios for reinforced sections are approximate. More exact calculations are presented in Appendix C.**

APPENDIX B
BASE LEVEL DRAWING



CLIMBING PEGS
W/ SAFETY CLIMB

- (PROPOSED EQUIPMENT CONFIGURATION)**
 (1) 1-3/4" TO 218 FT LEVEL
 (OTHER CONSIDERED EQUIPMENT)
 (1) 1/2" TO 72 FT LEVEL
 (OTHER CONSIDERED EQUIPMENT-IN CONDUIT)
 (2) 3/8" TO 196 FT LEVEL
 (4) 5/8" TO 196 FT LEVEL
 (OTHER CONSIDERED EQUIPMENT)
 (2) 5/8" TO 196 FT LEVEL
 (12) 1-1/4" TO 196 FT LEVEL

- (OTHER CONSIDERED EQUIPMENT)
 (1) 1/2" TO 185 FT LEVEL
 (6) 1-5/8" TO 185 FT LEVEL
 (OTHER CONSIDERED EQUIPMENT)
 (14) 1-5/8" TO 228 FT LEVEL

- (OTHER CONSIDERED EQUIPMENT)
 (14) 1-5/8" TO 205 FT LEVEL
 (OTHER CONSIDERED EQUIPMENT)
 (1) 1/2" TO 72 FT LEVEL
 (4) 1-1/4" TO 172 FT LEVEL

APPENDIX C
ADDITIONAL CALCULATIONS

Monopole Base Plate Connection




Site Info	
BU #	806358
Site Name	NHV 109 943107
Order #	553354 rev. 1

Analysis Considerations	
TIA-222 Revision	H
Grout Considered:	No
I_{ar} (in)	1.5625

Applied Loads	
Moment (kip-ft)	7991.53
Axial Force (kips)	115.05
Shear Force (kips)	48.35

*TIA-222-H Section 15.5 Applied



Connection Properties	Analysis Results
-----------------------	------------------

Anchor Rod Data

(28) 2-1/4" \varnothing bolts (A615-75 N; $F_y=75$ ksi, $F_u=100$ ksi) on 84" BC

Base Plate Data

90" OD x 2.5" Plate (A572-50; $F_y=50$ ksi, $F_u=65$ ksi)

Stiffener Data

(28) 18"H x 6"W x 1"T, Notch: 1"
 plate: $F_y= 50$ ksi ; weld: $F_y= 70$ ksi
 horiz. weld: 0.5" groove, 45° dbl bevel, 0.5" fillet
 vert. weld: 0.5" fillet

Pole Data

74.5" x 0.5625" 18-sided pole (A572-65; $F_y=65$ ksi, $F_u=80$ ksi)

Anchor Rod Summary (units of kips, kip-in)

$P_{u,t} = 158.94$	$\phi P_{n,t} = 243.75$	Stress Rating
$V_u = 1.73$	$\phi V_n = 149.1$	62.1%
$\mu = n/a$	$\phi M_n = n/a$	Pass

Base Plate Summary

Max Stress (ksi):	21.96	(Roark's Flexural)
Allowable Stress (ksi):	45	
Stress Rating:	46.5%	Pass

Stiffener Summary

Horizontal Weld:	43.8%	Pass
Vertical Weld:	27.6%	Pass
Plate Flexure+Shear:	10.0%	Pass
Plate Tension+Shear:	44.1%	Pass
Plate Compression:	43.1%	Pass

Pole Summary

Punching Shear:	6.8%	Pass
-----------------	-------------	-------------

Monopole Base Reaction Comparison Test



BU # :	806358
Site Name:	NHV 109 943107
Order Number:	553354 rev. 1
Design TIA:	TIA-222-F
Current TIA:	TIA-222-H
Component:	Monopole Base
Reference Doc ID:	821496

TIA-222-F Compared To TIA-222-H

MONOPOLE BASE FOUNDATION REACTION COMPARISON

REACTIONS	DESIGN REACTIONS	*MODIFIED DESIGN REACTIONS	CURRENT REACTIONS	% CAPACITY
MOMENT (kip-ft)	8439.1	11392.8	7992.0	66.8%
SHEAR (kips)	50.8	68.6	48.0	66.7%

Design loads from: CClites Doc #821496



*Design loads were multiplied by 1.35 for comparison as allowed by TIA-222-H, Section 15.6.

ASCE 7 Hazards Report

Address:
No Address at This
Location

Standard: ASCE/SEI 7-10
Risk Category: II
Soil Class: D - Stiff Soil

Elevation: 666.03 ft (NAVD 88)
Latitude: 41.493589
Longitude: -73.165272



Wind

Results:

Wind Speed:	119 Vmph
10-year MRI	76 Vmph
25-year MRI	86 Vmph
50-year MRI	91 Vmph
100-year MRI	98 Vmph

120mph per Southbury, CT requirement

Data Source: ASCE/SEI 7-10, Fig. 26.5-1A and Figs. CC-1–CC-4, and Section 26.5.2, incorporating errata of March 12, 2014

Value provided is 3-second gust wind speeds at 33 ft above ground for Exposure C Category, based on linear interpolation between contours. Wind speeds are interpolated in accordance with the 7-10 Standard. Wind speeds correspond to approximately a 7% probability of exceedance in 50 years (annual exceedance probability = 0.00143, MRI = 700 years).



Site is in a hurricane-prone region as defined in ASCE/SEI 7-10 Section 26.2. Glazed openings need not be protected against wind-borne debris.

Site Soil Class: D - Stiff Soil

Results:

S_s :	0.195	S_{DS} :	0.208
S_1 :	0.065	S_{D1} :	0.103
F_a :	1.6	T_L :	6
F_v :	2.4	PGA :	0.102
S_{MS} :	0.312	PGA _M :	0.163
S_{M1} :	0.155	F_{PGA} :	1.595
		I_e :	1

Seismic Design Category B



Data Accessed:

Sat May 22 2021

Date Source:

USGS Seismic Design Maps based on ASCE/SEI 7-10, incorporating Supplement 1 and errata of March 31, 2013, and ASCE/SEI 7-10 Table 1.5-2. Additional data for site-specific ground motion procedures in accordance with ASCE/SEI 7-10 Ch. 21 are available from USGS.

Ice

Results:

Ice Thickness: 0.75 in.
Concurrent Temperature: 15 F
Gust Speed: 50 mph

Data Source: Standard ASCE/SEI 7-10, Figs. 10-2 through 10-8

Date Accessed: Sat May 22 2021

Ice thicknesses on structures in exposed locations at elevations higher than the surrounding terrain and in valleys and gorges may exceed the mapped values.

Values provided are equivalent radial ice thicknesses due to freezing rain with concurrent 3-second gust speeds, for a 50-year mean recurrence interval, and temperatures concurrent with ice thicknesses due to freezing rain. Thicknesses for ice accretions caused by other sources shall be obtained from local meteorological studies. Ice thicknesses in exposed locations at elevations higher than the surrounding terrain and in valleys and gorges may exceed the mapped values.

The ASCE 7 Hazard Tool is provided for your convenience, for informational purposes only, and is provided “as is” and without warranties of any kind. The location data included herein has been obtained from information developed, produced, and maintained by third party providers; or has been extrapolated from maps incorporated in the ASCE 7 standard. While ASCE has made every effort to use data obtained from reliable sources or methodologies, ASCE does not make any representations or warranties as to the accuracy, completeness, reliability, currency, or quality of any data provided herein. Any third-party links provided by this Tool should not be construed as an endorsement, affiliation, relationship, or sponsorship of such third-party content by or from ASCE.

ASCE does not intend, nor should anyone interpret, the results provided by this Tool to replace the sound judgment of a competent professional, having knowledge and experience in the appropriate field(s) of practice, nor to substitute for the standard of care required of such professionals in interpreting and applying the contents of this Tool or the ASCE 7 standard.

In using this Tool, you expressly assume all risks associated with your use. Under no circumstances shall ASCE or its officers, directors, employees, members, affiliates, or agents be liable to you or any other person for any direct, indirect, special, incidental, or consequential damages arising from or related to your use of, or reliance on, the Tool or any information obtained therein. To the fullest extent permitted by law, you agree to release and hold harmless ASCE from any and all liability of any nature arising out of or resulting from any use of data provided by the ASCE 7 Hazard Tool.

Exhibit E

Mount Analysis

Date: **July 28, 2021**

Darcy Tarr
Crown Castle
3530 Toringdon Way, Suite 300
Charlotte, NC 28277
(704) 405-6589



Trylon
1825 W. Walnut Hill Lane,
Suite 302
Irving, TX 75038
214-930-1730

Subject: **Mount Replacement Analysis Report**

Carrier Designation: **Dish Network Dish 5G**
Carrier Site Number: BOHVN00009A
Carrier Site Name: CT-CCI-T-806358

Crown Castle Designation: **Crown Castle BU Number:** 806358
Crown Castle Site Name: NHV 109 943107
Crown Castle JDE Job Number: 645107
Crown Castle Order Number: 553354 Rev. 1

Engineering Firm Designation: **Trylon Report Designation:** 189028

Site Data: **1432 Old Waterbury Road, Southbury, New Haven County, CT, 06488**
Latitude 41°29'36.92" Longitude -73°9'54.98"

Structure Information: **Tower Height & Type:** **225.8 ft Monopole**
Mount Elevation: **218.0 ft**
Mount Type: **8.0 ft Platform**

Dear Darcy Tarr,

Trylon is pleased to submit this "**Mount Replacement Analysis Report**" to determine the structural integrity of Dish Network's antenna mounting system with the proposed appurtenance and equipment addition on the abovementioned supporting tower structure. Analysis of the existing supporting tower structure is to be completed by others and therefore is not part of this analysis. Analysis of the antenna mounting system as a tie-off point for fall protection or rigging is not part of this document.


The purpose of the analysis is to determine acceptability of the mount stress level. Based on our analysis we have determined the mount stress level to be:

Platform **Sufficient***
***Sufficient upon completion of the changes listed in the 'Recommendations' section of this report.**

This analysis utilizes an ultimate 3-second gust wind speed of 120 mph as required by the 2018 Connecticut State Building Code. Applicable Standard references and design criteria are listed in Section 2 - Analysis Criteria.

Mount analysis prepared by: Aura Baltoiu

Respectfully Submitted by:
Cliff Abernathy, P.E.



Cliff Abernathy
Digitally signed by Cliff
Abernathy
Date: 2021.07.29 14:53:37
-04'00'

TABLE OF CONTENTS

1) INTRODUCTION

2) ANALYSIS CRITERIA

Table 1 - Proposed Equipment Configuration

3) ANALYSIS PROCEDURE

Table 2 - Documents Provided

3.1) Analysis Method

3.2) Assumptions

4) ANALYSIS RESULTS

Table 3 - Mount Component Stresses vs. Capacity

4.1) Recommendations

5) APPENDIX A

Wire Frame and Rendered Models

6) APPENDIX B

Software Input Calculations

7) APPENDIX C

Software Analysis Output

8) APPENDIX D

Additional Calculations

9) APPENDIX E

Supplemental Drawings

1) INTRODUCTION

This is a proposed 3 sector 8.0 ft Platform, designed by Commscope.

2) ANALYSIS CRITERIA

Building Code:	2015 IBC
TIA-222 Revision:	TIA-222-H
Risk Category:	II
Ultimate Wind Speed:	120 mph
Exposure Category:	B
Topographic Factor at Base:	1.00
Topographic Factor at Mount:	1.00
Ice Thickness:	1.5 in
Wind Speed with Ice:	50 mph
Seismic S_s:	0.198
Seismic S₁:	0.065
Live Loading Wind Speed:	30 mph
Man Live Load at Mid/End-Points:	250 lb
Man Live Load at Mount Pipes:	500 lb

Table 1 - Proposed Equipment Configuration

Mount Centerline (ft)	Antenna Centerline (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Mount / Modification Details
218.0	218.0	3	JMA WIRELESS	MX08FRO665-21	8.0 ft Platform [Commscope, MC-PK8-C]
		3	FUJITSU	TA08025-B604	
		3	FUJITSU	TA08025-B605	
		1	RAYCAP	RDIDC-9181-PF-48	

3) ANALYSIS PROCEDURE

Table 2 - Documents Provided

Document	Remarks	Reference	Source
Crown Application	Dish Network Application	553354, Rev.1	CCI Sites
Mount Manufacturer Drawings	Commscope	MC-PK8-C	Trylon

3.1) Analysis Method

RISA-3D (Version 17.0.4), a commercially available analysis software package, was used to create a three-dimensional model of the antenna mounting system and calculate member stresses for various loading cases.

A tool internally developed, using Microsoft Excel, by Trylon was used to calculate wind loading on all appurtenances, dishes, and mount members for various load cases. Selected output from the analysis is included in Appendix B.

This analysis was performed in accordance with Crown Castle's ENG-SOW-10208 *Tower Mount Analysis* (Revision B).

3.2) Assumptions

- 1) The antenna mounting system was properly fabricated, installed and maintained in good condition in accordance with its original design and manufacturer's specifications.
- 2) The configuration of antennas, mounts, and other appurtenances are as specified in Table 1 and the referenced drawings.
- 3) All member connections are assumed to have been designed to meet or exceed the load carrying capacity of the connected member unless otherwise specified in this report.
- 4) The analysis will be required to be revised if the existing conditions in the field differ from those shown in the above-referenced documents or assumed in this analysis. No allowance was made for any damaged, missing, or rusted members.
- 5) Prior structural modifications to the tower mounting system are assumed to be installed as shown per available data.
- 6) Steel grades have been assumed as follows, unless noted otherwise:

Channel, Solid Round, Angle, Plate	ASTM A36 (GR 36)
HSS (Rectangular)	ASTM A500 (GR B-46)
Pipe	ASTM A53 (GR 35)
Connection Bolts	ASTM A325

This analysis may be affected if any assumptions are not valid or have been made in error. Tylon should be notified to determine the effect on the structural integrity of the antenna mounting system.

4) ANALYSIS RESULTS

Table 3 - Mount Component Stresses vs. Capacity (Platform, All Sectors)

Notes	Component	Critical Member	Centerline (ft)	% Capacity	Pass / Fail
1,2	Mount Pipe(s)	MP3	218.0	32.7	Pass
	Horizontal(s)	H1		10.0	Pass
	Standoff(s)	SA2		52.1	Pass
	Bracing(s)	PB2		36.5	Pass
	Handrail(s)	M19		16.5	Pass
	Corner Angle(s)	CP3		8.4	Pass
	Plate(s)	CP5		22.8	Pass
	Mount Connection(s)	-		21.1	Pass

Structure Rating (max from all components) =	52.1%
---	--------------

Notes:

- 1) See additional documentation in "Appendix C - Software Analysis Output" for calculations supporting the % capacity consumed.
- 2) Rating per TIA-222-H, Section 15.5



4.1) Recommendations

The mount has sufficient capacity to carry the proposed loading configuration. In order for the results of the analysis to be considered valid, the proposed mount listed below must be installed.

1. Commscope, MC-PK8-C.



No structural modifications are required at this time, provided that the above-listed changes are implemented.

APPENDIX A
WIRE FRAME AND RENDERED MODELS



Envelope Only Solution

Trylon	806358	SK - 1
AB		July 28, 2021 at 6:29 AM
189028		806358.r3d



Envelope Only Solution

Trylon	806358	SK - 2
AB		July 28, 2021 at 6:29 AM
189028		806358.r3d



APPENDIX B
SOFTWARE INPUT CALCULATIONS

ASCE 7 Hazards Report

Address:
No Address at This
Location

Standard: ASCE/SEI 7-10
Risk Category: II
Soil Class: D - Stiff Soil

Elevation: 666.03 ft (NAVD 88)
Latitude: 41.493589
Longitude: -73.165272



Ice

Results:

Ice Thickness: 0.75 in.
Concurrent Temperature: 15 F
Gust Speed: 50 mph

Data Source: Standard ASCE/SEI 7-10, Figs. 10-2 through 10-8

Date Accessed: Tue Jul 27 2021

Ice thicknesses on structures in exposed locations at elevations higher than the surrounding terrain and in valleys and gorges may exceed the mapped values.

Values provided are equivalent radial ice thicknesses due to freezing rain with concurrent 3-second gust speeds, for a 50-year mean recurrence interval, and temperatures concurrent with ice thicknesses due to freezing rain. Thicknesses for ice accretions caused by other sources shall be obtained from local meteorological studies. Ice thicknesses in exposed locations at elevations higher than the surrounding terrain and in valleys and gorges may exceed the mapped values.

The ASCE 7 Hazard Tool is provided for your convenience, for informational purposes only, and is provided “as is” and without warranties of any kind. The location data included herein has been obtained from information developed, produced, and maintained by third party providers; or has been extrapolated from maps incorporated in the ASCE 7 standard. While ASCE has made every effort to use data obtained from reliable sources or methodologies, ASCE does not make any representations or warranties as to the accuracy, completeness, reliability, currency, or quality of any data provided herein. Any third-party links provided by this Tool should not be construed as an endorsement, affiliation, relationship, or sponsorship of such third-party content by or from ASCE.

ASCE does not intend, nor should anyone interpret, the results provided by this Tool to replace the sound judgment of a competent professional, having knowledge and experience in the appropriate field(s) of practice, nor to substitute for the standard of care required of such professionals in interpreting and applying the contents of this Tool or the ASCE 7 standard.

In using this Tool, you expressly assume all risks associated with your use. Under no circumstances shall ASCE or its officers, directors, employees, members, affiliates, or agents be liable to you or any other person for any direct, indirect, special, incidental, or consequential damages arising from or related to your use of, or reliance on, the Tool or any information obtained therein. To the fullest extent permitted by law, you agree to release and hold harmless ASCE from any and all liability of any nature arising out of or resulting from any use of data provided by the ASCE 7 Hazard Tool.



Trylon

1825 W. Walnut Hill Lane Suite 120
Irving, TX 75038

TIA LOAD CALCULATOR 2.0

PROJECT DATA	
Job Code:	189028
Carrier Site ID:	BOHVN00009A
Carrier Site Name:	CT-CCI-T-806358

CODES AND STANDARDS	
Building Code:	2015 IBC
Local Building Code:	2018 CSBC
Design Standard:	TIA-222-H

STRUCTURE DETAILS		
Mount Type:	Platform	--
Mount Elevation:	218.0	ft.
Number of Sectors:	3	--
Structure Type:	Monopole	--
Structure Height:	225.8	ft.

ANALYSIS CRITERIA		
Structure Risk Category:	II	--
Exposure Category:	B	--
Site Class:	D - Stiff Soil	--
Ground Elevation:	666.03	ft.

TOPOGRAPHIC DATA		
Topographic Category:	1.00	--
Topographic Feature:	N/A	--
Crest Point Elevation:	0.00	ft.
Base Point Elevation:	0.00	ft.
Crest to Mid-Height (L/2):	0.00	ft.
Distance from Crest (x):	0.00	ft.
Base Topo Factor (K_{zt}):	1.00	--
Mount Topo Factor (K_{zt}):	1.00	--

WIND PARAMETERS		
Design Wind Speed:	120	mph
Wind Escalation Factor (K_s):	1.00	--
Velocity Coefficient (K_z):	1.23	--
Directionality Factor (K_d):	0.95	--
Gust Effect Factor (G_h):	1.00	--
Shielding Factor (K_a):	0.90	--
Velocity Pressure (q_z):	42.21	psf

ICE PARAMETERS		
Design Ice Wind Speed:	50	mph
Design Ice Thickness (t_i):	1.50	in
Importance Factor (I_i):	1.00	--
Ice Velocity Pressure (q_{zi}):	42.21	psf
Mount Ice Thickness (t_{iz}):	1.81	in

WIND STRUCTURE CALCULATIONS		
Flat Member Pressure:	75.98	psf
Round Member Pressure:	45.59	psf
Ice Wind Pressure:	7.74	psf

SEISMIC PARAMETERS		
Importance Factor (I_e):	1.00	--
Short Period Accel. (S_s):	0.198	g
1 Second Accel. (S_1):	0.065	g
Short Period Des. (S_{DS}):	0.21	g
1 Second Des. (S_{D1}):	0.10	g
Short Period Coeff. (F_a):	1.60	--
1 Second Coeff. (F_v):	2.40	--
Response Coefficient (C_s):	0.11	--
Amplification Factor (A_S):	1.20	--

LOAD COMBINATIONS [LRFD]

#	Description
1	1.4DL
2	1.2DL + 1WL 0 AZI
3	1.2DL + 1WL 30 AZI
4	1.2DL + 1WL 45 AZI
5	1.2DL + 1WL 60 AZI
6	1.2DL + 1WL 90 AZI
7	1.2DL + 1WL 120 AZI
8	1.2DL + 1WL 135 AZI
9	1.2DL + 1WL 150 AZI
10	1.2DL + 1WL 180 AZI
11	1.2DL + 1WL 210 AZI
12	1.2DL + 1WL 225 AZI
13	1.2DL + 1WL 240 AZI
14	1.2DL + 1WL 270 AZI
15	1.2DL + 1WL 300 AZI
16	1.2DL + 1WL 315 AZI
17	1.2DL + 1WL 330 AZI
18	0.9DL + 1WL 0 AZI
19	0.9DL + 1WL 30 AZI
20	0.9DL + 1WL 45 AZI
21	0.9DL + 1WL 60 AZI
22	0.9DL + 1WL 90 AZI
23	0.9DL + 1WL 120 AZI
24	0.9DL + 1WL 135 AZI
25	0.9DL + 1WL 150 AZI
26	0.9DL + 1WL 180 AZI
27	0.9DL + 1WL 210 AZI
28	0.9DL + 1WL 225 AZI
29	0.9DL + 1WL 240 AZI
30	0.9DL + 1WL 270 AZI
31	0.9DL + 1WL 300 AZI
32	0.9DL + 1WL 315 AZI
33	0.9DL + 1WL 330 AZI
34	1.2DL + 1DLi + 1WLi 0 AZI
35	1.2DL + 1DLi + 1WLi 30 AZI
36	1.2DL + 1DLi + 1WLi 45 AZI
37	1.2DL + 1DLi + 1WLi 60 AZI
38	1.2DL + 1DLi + 1WLi 90 AZI
39	1.2DL + 1DLi + 1WLi 120 AZI
40	1.2DL + 1DLi + 1WLi 135 AZI
41	1.2DL + 1DLi + 1WLi 150 AZI

#	Description
42	1.2DL + 1DLi + 1WLi 180 AZI
43	1.2DL + 1DLi + 1WLi 210 AZI
44	1.2DL + 1DLi + 1WLi 225 AZI
45	1.2DL + 1DLi + 1WLi 240 AZI
46	1.2DL + 1DLi + 1WLi 270 AZI
47	1.2DL + 1DLi + 1WLi 300 AZI
48	1.2DL + 1DLi + 1WLi 315 AZI
49	1.2DL + 1DLi + 1WLi 330 AZI
50	(1.2+0.2Sds) + 1.0E 0 AZI
51	(1.2+0.2Sds) + 1.0E 30 AZI
52	(1.2+0.2Sds) + 1.0E 45 AZI
53	(1.2+0.2Sds) + 1.0E 60 AZI
54	(1.2+0.2Sds) + 1.0E 90 AZI
55	(1.2+0.2Sds) + 1.0E 120 AZI
56	(1.2+0.2Sds) + 1.0E 135 AZI
57	(1.2+0.2Sds) + 1.0E 150 AZI
58	(1.2+0.2Sds) + 1.0E 180 AZI
59	(1.2+0.2Sds) + 1.0E 210 AZI
60	(1.2+0.2Sds) + 1.0E 225 AZI
61	(1.2+0.2Sds) + 1.0E 240 AZI
62	(1.2+0.2Sds) + 1.0E 270 AZI
63	(1.2+0.2Sds) + 1.0E 300 AZI
64	(1.2+0.2Sds) + 1.0E 315 AZI
65	(1.2+0.2Sds) + 1.0E 330 AZI
66	(0.9-0.2Sds) + 1.0E 0 AZI
67	(0.9-0.2Sds) + 1.0E 30 AZI
68	(0.9-0.2Sds) + 1.0E 45 AZI
69	(0.9-0.2Sds) + 1.0E 60 AZI
70	(0.9-0.2Sds) + 1.0E 90 AZI
71	(0.9-0.2Sds) + 1.0E 120 AZI
72	(0.9-0.2Sds) + 1.0E 135 AZI
73	(0.9-0.2Sds) + 1.0E 150 AZI
74	(0.9-0.2Sds) + 1.0E 180 AZI
75	(0.9-0.2Sds) + 1.0E 210 AZI
76	(0.9-0.2Sds) + 1.0E 225 AZI
77	(0.9-0.2Sds) + 1.0E 240 AZI
78	(0.9-0.2Sds) + 1.0E 270 AZI
79	(0.9-0.2Sds) + 1.0E 300 AZI
80	(0.9-0.2Sds) + 1.0E 315 AZI
81	(0.9-0.2Sds) + 1.0E 330 AZI
82-88	1.2D + 1.5 Lv1

#	Description
89	1.2D + 1.5Lm + 1.0Wm 0 AZI - MP1
90	1.2D + 1.5Lm + 1.0Wm 30 AZI - MP1
91	1.2D + 1.5Lm + 1.0Wm 45 AZI - MP1
92	1.2D + 1.5Lm + 1.0Wm 60 AZI - MP1
93	1.2D + 1.5Lm + 1.0Wm 90 AZI - MP1
94	1.2D + 1.5Lm + 1.0Wm 120 AZI - MP1
95	1.2D + 1.5Lm + 1.0Wm 135 AZI - MP1
96	1.2D + 1.5Lm + 1.0Wm 150 AZI - MP1
97	1.2D + 1.5Lm + 1.0Wm 180 AZI - MP1
98	1.2D + 1.5Lm + 1.0Wm 210 AZI - MP1
99	1.2D + 1.5Lm + 1.0Wm 225 AZI - MP1
100	1.2D + 1.5Lm + 1.0Wm 240 AZI - MP1
101	1.2D + 1.5Lm + 1.0Wm 270 AZI - MP1
102	1.2D + 1.5Lm + 1.0Wm 300 AZI - MP1
103	1.2D + 1.5Lm + 1.0Wm 315 AZI - MP1
104	1.2D + 1.5Lm + 1.0Wm 330 AZI - MP1
105	1.2D + 1.5Lm + 1.0Wm 0 AZI - MP2
106	1.2D + 1.5Lm + 1.0Wm 30 AZI - MP2
107	1.2D + 1.5Lm + 1.0Wm 45 AZI - MP2
108	1.2D + 1.5Lm + 1.0Wm 60 AZI - MP2
109	1.2D + 1.5Lm + 1.0Wm 90 AZI - MP2
110	1.2D + 1.5Lm + 1.0Wm 120 AZI - MP2
111	1.2D + 1.5Lm + 1.0Wm 135 AZI - MP2
112	1.2D + 1.5Lm + 1.0Wm 150 AZI - MP2
113	1.2D + 1.5Lm + 1.0Wm 180 AZI - MP2
114	1.2D + 1.5Lm + 1.0Wm 210 AZI - MP2
115	1.2D + 1.5Lm + 1.0Wm 225 AZI - MP2
116	1.2D + 1.5Lm + 1.0Wm 240 AZI - MP2
117	1.2D + 1.5Lm + 1.0Wm 270 AZI - MP2
118	1.2D + 1.5Lm + 1.0Wm 300 AZI - MP2
119	1.2D + 1.5Lm + 1.0Wm 315 AZI - MP2
120	1.2D + 1.5Lm + 1.0Wm 330 AZI - MP2

#	Description
121	1.2D + 1.5Lm + 1.0Wm 0 AZI - MP3
122	1.2D + 1.5Lm + 1.0Wm 30 AZI - MP3
123	1.2D + 1.5Lm + 1.0Wm 45 AZI - MP3
124	1.2D + 1.5Lm + 1.0Wm 60 AZI - MP3
125	1.2D + 1.5Lm + 1.0Wm 90 AZI - MP3
126	1.2D + 1.5Lm + 1.0Wm 120 AZI - MP3
127	1.2D + 1.5Lm + 1.0Wm 135 AZI - MP3
128	1.2D + 1.5Lm + 1.0Wm 150 AZI - MP3
129	1.2D + 1.5Lm + 1.0Wm 180 AZI - MP3
130	1.2D + 1.5Lm + 1.0Wm 210 AZI - MP3
131	1.2D + 1.5Lm + 1.0Wm 225 AZI - MP3
132	1.2D + 1.5Lm + 1.0Wm 240 AZI - MP3
133	1.2D + 1.5Lm + 1.0Wm 270 AZI - MP3
134	1.2D + 1.5Lm + 1.0Wm 300 AZI - MP3
135	1.2D + 1.5Lm + 1.0Wm 315 AZI - MP3
136	1.2D + 1.5Lm + 1.0Wm 330 AZI - MP3
137	1.2D + 1.5Lm + 1.0Wm 0 AZI - MP4
138	1.2D + 1.5Lm + 1.0Wm 30 AZI - MP4
139	1.2D + 1.5Lm + 1.0Wm 45 AZI - MP4
140	1.2D + 1.5Lm + 1.0Wm 60 AZI - MP4
141	1.2D + 1.5Lm + 1.0Wm 90 AZI - MP4
142	1.2D + 1.5Lm + 1.0Wm 120 AZI - MP4
143	1.2D + 1.5Lm + 1.0Wm 135 AZI - MP4
144	1.2D + 1.5Lm + 1.0Wm 150 AZI - MP4
145	1.2D + 1.5Lm + 1.0Wm 180 AZI - MP4
146	1.2D + 1.5Lm + 1.0Wm 210 AZI - MP4
147	1.2D + 1.5Lm + 1.0Wm 225 AZI - MP4
148	1.2D + 1.5Lm + 1.0Wm 240 AZI - MP4
149	1.2D + 1.5Lm + 1.0Wm 270 AZI - MP4
150	1.2D + 1.5Lm + 1.0Wm 300 AZI - MP4
151	1.2D + 1.5Lm + 1.0Wm 315 AZI - MP4
152	1.2D + 1.5Lm + 1.0Wm 330 AZI - MP4

*This page shows an example of maintenance loads for (4) pipes, the number of mount pipe LCs may vary per site

EQUIPMENT LOADING [CONT.]

<i>Appurtenance Name/Location</i>	<i>Qty.</i>	<i>Elevation [ft]</i>	<i>--</i>	<i>EPA_N (ft²)</i>	<i>EPA_T (ft²)</i>	<i>Weight (lbs)</i>
			No Ice			
--	--	--	w/ Ice			
			No Ice			
--	--	--	w/ Ice			
			No Ice			
--	--	--	w/ Ice			
			No Ice			
--	--	--	w/ Ice			
			No Ice			
--	--	--	w/ Ice			
			No Ice			
--	--	--	w/ Ice			
			No Ice			
--	--	--	w/ Ice			
			No Ice			
--	--	--	w/ Ice			
			No Ice			
--	--	--	w/ Ice			
			No Ice			
--	--	--	w/ Ice			
			No Ice			
--	--	--	w/ Ice			
			No Ice			
--	--	--	w/ Ice			

EQUIPMENT LATERAL WIND FORCE CALCULATIONS [CONT.]

<i>Appurtenance Name</i>	<i>Qty.</i>	<i>--</i>	<i>0° 180°</i>	<i>30° 210°</i>	<i>60° 240°</i>	<i>90° 270°</i>	<i>120° 300°</i>	<i>150° 330°</i>
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						

APPENDIX C
SOFTWARE ANALYSIS OUTPUT

(Global) Model Settings

Display Sections for Member Calcs	5
Max Internal Sections for Member Calcs	97
Include Shear Deformation?	Yes
Increase Nailing Capacity for Wind?	Yes
Include Warping?	Yes
Trans Load Btwn Intersecting Wood Wall?	Yes
Area Load Mesh (in^2)	144
Merge Tolerance (in)	.12
P-Delta Analysis Tolerance	0.50%
Include P-Delta for Walls?	Yes
Automatically Iterate Stiffness for Walls?	Yes
Max Iterations for Wall Stiffness	3
Gravity Acceleration (in/sec^2)	386.4
Wall Mesh Size (in)	24
Eigensolution Convergence Tol. (1.E-)	4
Vertical Axis	Z
Global Member Orientation Plane	XY
Static Solver	Sparse Accelerated
Dynamic Solver	Accelerated Solver

Hot Rolled Steel Code	AISC 15th(360-16): LRFD
Adjust Stiffness?	Yes(Iterative)
RISAC Connection Code	AISC 15th(360-16): LRFD
Cold Formed Steel Code	AISI S100-12: LRFD
Wood Code	AWC NDS-15: ASD
Wood Temperature	< 100F
Concrete Code	ACI 318-14
Masonry Code	ACI 530-13: Strength
Aluminum Code	AA ADM 1-10: LRFD - Building
Stainless Steel Code	AISC 14th(360-10): LRFD
Adjust Stiffness?	Yes(Iterative)

Number of Shear Regions	4
Region Spacing Increment (in)	4
Biaxial Column Method	Exact Integration
Parame Beta Factor (PCA)	.65
Concrete Stress Block	Rectangular
Use Cracked Sections?	Yes
Use Cracked Sections Slab?	Yes
Bad Framing Warnings?	No
Unused Force Warnings?	Yes
Min 1 Bar Diam. Spacing?	No
Concrete Rebar Set	REBAR_SET_ASTMA615
Min % Steel for Column	1
Max % Steel for Column	8

(Global) Model Settings, Continued

Seismic Code	ASCE 7-10
Seismic Base Elevation (in)	Not Entered
Add Base Weight?	Yes
Ct X	.02
Ct Z	.02
T X (sec)	Not Entered
T Z (sec)	Not Entered
R X	3
R Z	3
Ct Exp. X	.75
Ct Exp. Z	.75
SD1	1
SDS	1
S1	1
TL (sec)	5
Risk Cat	I or II
Drift Cat	Other
Om Z	1
Om X	1
Cd Z	1
Cd X	1
Rho Z	1
Rho X	1

Hot Rolled Steel Properties

	Label	E [ksi]	G [ksi]	Nu	Therm (/1E5 F)	Density[k/ft^3]	Yield[psi]	Ry	Fu[psi]	Rt
1	A992	29000	11154	.3	.65	.49	50000	1.1	65000	1.1
2	A36 Gr.36	29000	11154	.3	.65	.49	36000	1.5	58000	1.2
3	A572 Gr.50	29000	11154	.3	.65	.49	50000	1.1	65000	1.1
4	A500 Gr.B RND	29000	11154	.3	.65	.527	42000	1.4	58000	1.3
5	A500 Gr.B Rect	29000	11154	.3	.65	.527	46000	1.4	58000	1.3
6	A53 Gr.B	29000	11154	.3	.65	.49	35000	1.6	60000	1.2
7	A1085	29000	11154	.3	.65	.49	50000	1.4	65000	1.3

Cold Formed Steel Properties

	Label	E [ksi]	G [ksi]	Nu	Therm (/1E5 F)	Density[k/ft^3]	Yield[psi]	Fu[psi]
1	A653 SS Gr33	29500	11346	.3	.65	.49	33000	45000
2	A653 SS Gr50/1	29500	11346	.3	.65	.49	50000	65000

Hot Rolled Steel Section Sets

	Label	Shape	Type	Design List	Material	Design ...	A [in2]	Iyy [in4]	Izz [in4]	J [in4]
1	Plates	6.5"x0.37" Plate	Beam	RECT	A53 Gr.B	Typical	2.405	.027	8.468	.106
2	Grating Bracing	L2x2x3	Beam	Single Angle	A36 Gr.36	Typical	.722	.271	.271	.009
3	Standoffs	PIPE 3.5	Beam	Pipe	A53 Gr.B	Typical	2.5	4.52	4.52	9.04
4	Standoff Bracing	C3X5	Beam	Channel	A36 Gr.36	Typical	1.47	.241	1.85	.043
5	Handrails	PIPE 2.0	Beam	Pipe	A53 Gr.B	Typical	1.02	.627	.627	1.25
6	Handrail Corners	6.6x4.46x0.25	Beam	Single Angle	A36 Gr.36	Typical	2.702	4.759	12.473	.055
7	Horizontals	PIPE 3.5	Beam	Pipe	A53 Gr.B	Typical	2.5	4.52	4.52	9.04



Company : Trylon
 Designer : AB
 Job Number : 189028
 Model Name : 806358

July 28, 2021
 6:29 AM
 Checked By: CA

Hot Rolled Steel Section Sets (Continued)

	Label	Shape	Type	Design List	Material	Design ...	A [in2]	Iyy [in4]	Izz [in4]	J [in4]
8	Mount Pipes	PIPE 2.0	Beam	Pipe	A53 Gr.B	Typical	1.02	.627	.627	1.25

Cold Formed Steel Section Sets

	Label	Shape	Type	Design List	Material	Design R...	A [in2]	Iyy [in4]	Izz [in4]	J [in4]
1	CF1A	8CU1.25X057	Beam	None	A653 SS Gr33	Typical	.581	.057	4.41	.00063

Joint Boundary Conditions

	Joint Label	X [k/in]	Y [k/in]	Z [k/in]	X Rot.[k-ft/rad]	Y Rot.[k-ft/rad]	Z Rot.[k-ft/rad]
1	N25	Reaction	Reaction	Reaction	Reaction	Reaction	Reaction
2	N1	Reaction	Reaction	Reaction	Reaction	Reaction	Reaction
3	N13	Reaction	Reaction	Reaction	Reaction	Reaction	Reaction

Basic Load Cases

	BLC Description	Category	X Gravity	Y Gravity	Z Gravity	Joint	Point	Distribu...	Area(M...	Surface...
1	Self Weight	DL			-1		13		3	
2	Structure Wind X	WLX						33		
3	Structure Wind Y	WLY						33		
4	Wind Load 0 AZI	WLX					13			
5	Wind Load 30 AZI	None					26			
6	Wind Load 45 AZI	None					26			
7	Wind Load 60 AZI	None					26			
8	Wind Load 90 AZI	WLY					13			
9	Wind Load 120 AZI	None					26			
10	Wind Load 135 AZI	None					26			
11	Wind Load 150 AZI	None					26			
12	Ice Weight	OL1					13	33	3	
13	Structure Ice Wind X	OL2						33		
14	Structure Ice Wind Y	OL3						33		
15	Ice Wind Load 0 AZI	OL2					13			
16	Ice Wind Load 30 AZI	None					26			
17	Ice Wind Load 45 AZI	None					26			
18	Ice Wind Load 60 AZI	None					26			
19	Ice Wind Load 90 AZI	OL3					13			
20	Ice Wind Load 120 AZI	None					26			
21	Ice Wind Load 135 AZI	None					26			
22	Ice Wind Load 150 AZI	None					26			
23	Seismic Load X	ELX	-.127				13			
24	Seismic Load Y	ELY		-.127			13			
25	Live Load 1 (Lv)	LL					1			
26	Live Load 2 (Lv)	LL					1			
27	Live Load 3 (Lv)	LL					1			
28	Live Load 4 (Lv)	LL					1			
29	Live Load 5 (Lv)	LL					1			
30	Live Load 6 (Lv)	LL					1			
31	Maintenance Load 1 (Lm)	None					1			
32	Maintenance Load 2 (Lm)	None					1			
33	Maintenance Load 3 (Lm)	None					1			



Company : Trylon
 Designer : AB
 Job Number : 189028
 Model Name : 806358

July 28, 2021
 6:29 AM
 Checked By: CA

Basic Load Cases (Continued)

	BLC Description	Category	X Gravity	Y Gravity	Z Gravity	Joint	Point	Distribu...	Area(M...	Surface...
34	Maintenance Load 4 (Lm)	None					1			
35	Maintenance Load 5 (Lm)	None					1			
36	Maintenance Load 6 (Lm)	None					1			
37	Maintenance Load 7 (Lm)	None					1			
38	Maintenance Load 8 (Lm)	None					1			
39	Maintenance Load 9 (Lm)	None					1			
40	Maintenance Load 7 (Lm)	None					1			
41	Maintenance Load 8 (Lm)	None					1			
42	Maintenance Load 9 (Lm)	None					1			
43	BLC 1 Transient Area Loads	None						9		
44	BLC 12 Transient Area Loads	None						9		

Load Combinations

	Description	Solve	PD...	SR...	B...	Factor	BLC	Factor	B...	Fa...	B...	Fa...	BLC	Fa...	B...	Fa...	B...	Fa...	B...	Fa...	
1	1.4DL	Yes	Y		DL	1.4															
2	1.2DL + 1WL 0 AZI	Yes	Y		DL	1.2	2	1	3		4	1									
3	1.2DL + 1WL 30 AZI	Yes	Y		DL	1.2	2	.866	3	.5	5	1									
4	1.2DL + 1WL 45 AZI	Yes	Y		DL	1.2	2	.707	3	.707	6	1									
5	1.2DL + 1WL 60 AZI	Yes	Y		DL	1.2	2	.5	3	.866	7	1									
6	1.2DL + 1WL 90 AZI	Yes	Y		DL	1.2	2		3	1	8	1									
7	1.2DL + 1WL 120 AZI	Yes	Y		DL	1.2	2	-.5	3	.866	9	1									
8	1.2DL + 1WL 135 AZI	Yes	Y		DL	1.2	2	-.707	3	.707	10	1									
9	1.2DL + 1WL 150 AZI	Yes	Y		DL	1.2	2	-.866	3	.5	11	1									
10	1.2DL + 1WL 180 AZI	Yes	Y		DL	1.2	2	-1	3		4	-1									
11	1.2DL + 1WL 210 AZI	Yes	Y		DL	1.2	2	-.866	3	-.5	5	-1									
12	1.2DL + 1WL 225 AZI	Yes	Y		DL	1.2	2	-.707	3	-.7	6	-1									
13	1.2DL + 1WL 240 AZI	Yes	Y		DL	1.2	2	-.5	3	-.8	7	-1									
14	1.2DL + 1WL 270 AZI	Yes	Y		DL	1.2	2		3	-1	8	-1									
15	1.2DL + 1WL 300 AZI	Yes	Y		DL	1.2	2	.5	3	-.8	9	-1									
16	1.2DL + 1WL 315 AZI	Yes	Y		DL	1.2	2	.707	3	-.7	10	-1									
17	1.2DL + 1WL 330 AZI	Yes	Y		DL	1.2	2	.866	3	-.5	11	-1									
18	0.9DL + 1WL 0 AZI	Yes	Y		DL	.9	2	1	3		4	1									
19	0.9DL + 1WL 30 AZI	Yes	Y		DL	.9	2	.866	3	.5	5	1									
20	0.9DL + 1WL 45 AZI	Yes	Y		DL	.9	2	.707	3	.707	6	1									
21	0.9DL + 1WL 60 AZI	Yes	Y		DL	.9	2	.5	3	.866	7	1									
22	0.9DL + 1WL 90 AZI	Yes	Y		DL	.9	2		3	1	8	1									
23	0.9DL + 1WL 120 AZI	Yes	Y		DL	.9	2	-.5	3	.866	9	1									
24	0.9DL + 1WL 135 AZI	Yes	Y		DL	.9	2	-.707	3	.707	10	1									
25	0.9DL + 1WL 150 AZI	Yes	Y		DL	.9	2	-.866	3	.5	11	1									
26	0.9DL + 1WL 180 AZI	Yes	Y		DL	.9	2	-1	3		4	-1									
27	0.9DL + 1WL 210 AZI	Yes	Y		DL	.9	2	-.866	3	-.5	5	-1									
28	0.9DL + 1WL 225 AZI	Yes	Y		DL	.9	2	-.707	3	-.7	6	-1									
29	0.9DL + 1WL 240 AZI	Yes	Y		DL	.9	2	-.5	3	-.8	7	-1									
30	0.9DL + 1WL 270 AZI	Yes	Y		DL	.9	2		3	-1	8	-1									
31	0.9DL + 1WL 300 AZI	Yes	Y		DL	.9	2	.5	3	-.8	9	-1									
32	0.9DL + 1WL 315 AZI	Yes	Y		DL	.9	2	.707	3	-.7	10	-1									
33	0.9DL + 1WL 330 AZI	Yes	Y		DL	.9	2	.866	3	-.5	11	-1									
34	1.2DL + 1DLi + 1WL...	Yes	Y		DL	1.2	OL1	1	13	1	14		15	1							
35	1.2DL + 1DLi + 1WL...	Yes	Y		DL	1.2	OL1	1	13.866	14	.5	16	1								
36	1.2DL + 1DLi + 1WL...	Yes	Y		DL	1.2	OL1	1	13.707	14.707	17	1									



Load Combinations (Continued)

	Description	Solve	PD...	SR...	B...	Factor	BLC	Factor	B...	Fa...	B...	Fa...	BLC	Fa...	B...	Fa...	B...	Fa...	B...	Fa...
37	1.2DL + 1DLi + 1WL...	Yes	Y		DL	1.2	OL1	1	13	.5	14.866	18	1							
38	1.2DL + 1DLi + 1WL...	Yes	Y		DL	1.2	OL1	1	13		14	1	19	1						
39	1.2DL + 1DLi + 1WL...	Yes	Y		DL	1.2	OL1	1	13	-.5	14.866	20	1							
40	1.2DL + 1DLi + 1WL...	Yes	Y		DL	1.2	OL1	1	13	-.7	14.707	21	1							
41	1.2DL + 1DLi + 1WL...	Yes	Y		DL	1.2	OL1	1	13	-.8	14.5	22	1							
42	1.2DL + 1DLi + 1WL...	Yes	Y		DL	1.2	OL1	1	13	-1	14		15	-1						
43	1.2DL + 1DLi + 1WL...	Yes	Y		DL	1.2	OL1	1	13	-.8	14	-.5	16	-1						
44	1.2DL + 1DLi + 1WL...	Yes	Y		DL	1.2	OL1	1	13	-.7	14	-.7	17	-1						
45	1.2DL + 1DLi + 1WL...	Yes	Y		DL	1.2	OL1	1	13	-.5	14	-.8	18	-1						
46	1.2DL + 1DLi + 1WL...	Yes	Y		DL	1.2	OL1	1	13		14	-1	19	-1						
47	1.2DL + 1DLi + 1WL...	Yes	Y		DL	1.2	OL1	1	13	.5	14	-.8	20	-1						
48	1.2DL + 1DLi + 1WL...	Yes	Y		DL	1.2	OL1	1	13	.707	14	-.7	21	-1						
49	1.2DL + 1DLi + 1WL...	Yes	Y		DL	1.2	OL1	1	13	.866	14	-.5	22	-1						
50	(1.2+0.2Sds) + 1.0E...	Yes	Y		DL	1.242	ELX	1	E...											
51	(1.2+0.2Sds) + 1.0E...	Yes	Y		DL	1.242	ELX	.866	E...	.5										
52	(1.2+0.2Sds) + 1.0E...	Yes	Y		DL	1.242	ELX	.707	E...	.707										
53	(1.2+0.2Sds) + 1.0E...	Yes	Y		DL	1.242	ELX	.5	E...	.866										
54	(1.2+0.2Sds) + 1.0E...	Yes	Y		DL	1.242	ELX		E...	1										
55	(1.2+0.2Sds) + 1.0E...	Yes	Y		DL	1.242	ELX	-.5	E...	.866										
56	(1.2+0.2Sds) + 1.0E...	Yes	Y		DL	1.242	ELX	-.707	E...	.707										
57	(1.2+0.2Sds) + 1.0E...	Yes	Y		DL	1.242	ELX	-.866	E...	.5										
58	(1.2+0.2Sds) + 1.0E...	Yes	Y		DL	1.242	ELX	-1	E...											
59	(1.2+0.2Sds) + 1.0E...	Yes	Y		DL	1.242	ELX	-.866	E...	-.5										
60	(1.2+0.2Sds) + 1.0E...	Yes	Y		DL	1.242	ELX	-.707	E...	-.7										
61	(1.2+0.2Sds) + 1.0E...	Yes	Y		DL	1.242	ELX	-.5	E...	-.8										
62	(1.2+0.2Sds) + 1.0E...	Yes	Y		DL	1.242	ELX		E...	-1										
63	(1.2+0.2Sds) + 1.0E...	Yes	Y		DL	1.242	ELX	.5	E...	-.8										
64	(1.2+0.2Sds) + 1.0E...	Yes	Y		DL	1.242	ELX	.707	E...	-.7										
65	(1.2+0.2Sds) + 1.0E...	Yes	Y		DL	1.242	ELX	.866	E...	-.5										
66	(0.9-0.2Sds) + 1.0E...	Yes	Y		DL	.858	ELX	1	E...											
67	(0.9-0.2Sds) + 1.0E...	Yes	Y		DL	.858	ELX	.866	E...	.5										
68	(0.9-0.2Sds) + 1.0E...	Yes	Y		DL	.858	ELX	.707	E...	.707										
69	(0.9-0.2Sds) + 1.0E...	Yes	Y		DL	.858	ELX	.5	E...	.866										
70	(0.9-0.2Sds) + 1.0E...	Yes	Y		DL	.858	ELX		E...	1										
71	(0.9-0.2Sds) + 1.0E...	Yes	Y		DL	.858	ELX	-.5	E...	.866										
72	(0.9-0.2Sds) + 1.0E...	Yes	Y		DL	.858	ELX	-.707	E...	.707										
73	(0.9-0.2Sds) + 1.0E...	Yes	Y		DL	.858	ELX	-.866	E...	.5										
74	(0.9-0.2Sds) + 1.0E...	Yes	Y		DL	.858	ELX	-1	E...											
75	(0.9-0.2Sds) + 1.0E...	Yes	Y		DL	.858	ELX	-.866	E...	-.5										
76	(0.9-0.2Sds) + 1.0E...	Yes	Y		DL	.858	ELX	-.707	E...	-.7										
77	(0.9-0.2Sds) + 1.0E...	Yes	Y		DL	.858	ELX	-.5	E...	-.8										
78	(0.9-0.2Sds) + 1.0E...	Yes	Y		DL	.858	ELX		E...	-1										
79	(0.9-0.2Sds) + 1.0E...	Yes	Y		DL	.858	ELX	.5	E...	-.8										
80	(0.9-0.2Sds) + 1.0E...	Yes	Y		DL	.858	ELX	.707	E...	-.7										
81	(0.9-0.2Sds) + 1.0E...	Yes	Y		DL	.858	ELX	.866	E...	-.5										
82	1.2D + 1.5 Lv1	Yes	Y		DL	1.2	25	1.5												
83	1.2D + 1.5 Lv2	Yes	Y		DL	1.2	26	1.5												
84	1.2D + 1.5 Lv3	Yes	Y		DL	1.2	27	1.5												
85	1.2D + 1.5 Lv4	Yes	Y		DL	1.2	28	1.5												
86	1.2D + 1.5 Lv5	Yes	Y		DL	1.2	29	1.5												
87	1.2D + 1.5 Lv6	Yes	Y		DL	1.2	30	1.5												
88	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	31	1.5	4	.063	2	.063	3							



Company : Trylon
 Designer : AB
 Job Number : 189028
 Model Name : 806358

July 28, 2021
 6:29 AM
 Checked By: CA

Load Combinations (Continued)

	Description	Solve	PD...	SR...	B...	Factor	BLC	Factor	B...	Fa...	B...	Fa...	BLC	Fa...	B...	Fa...	B...	Fa...	B...	Fa...
89	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	31	1.5	5	.063	2	.054	3	.031						
90	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	31	1.5	6	.063	2	.044	3	.044						
91	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	31	1.5	7	.063	2	.031	3	.054						
92	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	31	1.5	8	.063	2		3	.063						
93	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	31	1.5	9	.063	2	-0...	3	.054						
94	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	31	1.5	10	.063	2	-0...	3	.044						
95	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	31	1.5	11	.063	2	-0...	3	.031						
96	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	31	1.5	4	.063	2	-0...	3							
97	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	31	1.5	5	.063	2	-0...	3	-0...						
98	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	31	1.5	6	.063	2	-0...	3	-0...						
99	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	31	1.5	7	.063	2	-0...	3	-0...						
100	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	31	1.5	8	.063	2		3	-0...						
101	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	31	1.5	9	.063	2	.031	3	-0...						
102	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	31	1.5	10	.063	2	.044	3	-0...						
103	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	31	1.5	11	.063	2	.054	3	-0...						
104	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	32	1.5	4	.063	2	.063	3							
105	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	32	1.5	5	.063	2	.054	3	.031						
106	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	32	1.5	6	.063	2	.044	3	.044						
107	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	32	1.5	7	.063	2	.031	3	.054						
108	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	32	1.5	8	.063	2		3	.063						
109	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	32	1.5	9	.063	2	-0...	3	.054						
110	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	32	1.5	10	.063	2	-0...	3	.044						
111	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	32	1.5	11	.063	2	-0...	3	.031						
112	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	32	1.5	4	.063	2	-0...	3							
113	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	32	1.5	5	.063	2	-0...	3	-0...						
114	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	32	1.5	6	.063	2	-0...	3	-0...						
115	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	32	1.5	7	.063	2	-0...	3	-0...						
116	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	32	1.5	8	.063	2		3	-0...						
117	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	32	1.5	9	.063	2	.031	3	-0...						
118	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	32	1.5	10	.063	2	.044	3	-0...						
119	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	32	1.5	11	.063	2	.054	3	-0...						
120	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	33	1.5	4	.063	2	.063	3							
121	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	33	1.5	5	.063	2	.054	3	.031						
122	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	33	1.5	6	.063	2	.044	3	.044						
123	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	33	1.5	7	.063	2	.031	3	.054						
124	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	33	1.5	8	.063	2		3	.063						
125	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	33	1.5	9	.063	2	-0...	3	.054						
126	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	33	1.5	10	.063	2	-0...	3	.044						
127	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	33	1.5	11	.063	2	-0...	3	.031						
128	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	33	1.5	4	.063	2	-0...	3							
129	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	33	1.5	5	.063	2	-0...	3	-0...						
130	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	33	1.5	6	.063	2	-0...	3	-0...						
131	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	33	1.5	7	.063	2	-0...	3	-0...						
132	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	33	1.5	8	.063	2		3	-0...						
133	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	33	1.5	9	.063	2	.031	3	-0...						
134	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	33	1.5	10	.063	2	.044	3	-0...						
135	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	33	1.5	11	.063	2	.054	3	-0...						
136	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	34	1.5	4	.063	2	.063	3							
137	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	34	1.5	5	.063	2	.054	3	.031						
138	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	34	1.5	6	.063	2	.044	3	.044						
139	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	34	1.5	7	.063	2	.031	3	.054						
140	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	34	1.5	8	.063	2		3	.063						

Load Combinations (Continued)

	Description	Solve	PD...	SR...	B...	Factor	BLC	Factor	B...	Fa...	B...	Fa...	BLC	Fa...	B...	Fa...	B...	Fa...	B...	Fa...
141	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	34	1.5	9	.063	2	-0...	3	.054						
142	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	34	1.5	10	.063	2	-0...	3	.044						
143	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	34	1.5	11	.063	2	-0...	3	.031						
144	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	34	1.5	4	.063	2	-0...	3							
145	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	34	1.5	5	.063	2	-0...	3	-0...						
146	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	34	1.5	6	.063	2	-0...	3	-0...						
147	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	34	1.5	7	.063	2	-0...	3	-0...						
148	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	34	1.5	8	.063	2		3	-0...						
149	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	34	1.5	9	.063	2	.031	3	-0...						
150	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	34	1.5	10	.063	2	.044	3	-0...						
151	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	34	1.5	11	.063	2	.054	3	-0...						
152	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	35	1.5	4	.063	2	.063	3							
153	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	35	1.5	5	.063	2	.054	3	.031						
154	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	35	1.5	6	.063	2	.044	3	.044						
155	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	35	1.5	7	.063	2	.031	3	.054						
156	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	35	1.5	8	.063	2		3	.063						
157	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	35	1.5	9	.063	2	-0...	3	.054						
158	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	35	1.5	10	.063	2	-0...	3	.044						
159	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	35	1.5	11	.063	2	-0...	3	.031						
160	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	35	1.5	4	.063	2	-0...	3							
161	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	35	1.5	5	.063	2	-0...	3	-0...						
162	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	35	1.5	6	.063	2	-0...	3	-0...						
163	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	35	1.5	7	.063	2	-0...	3	-0...						
164	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	35	1.5	8	.063	2		3	-0...						
165	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	35	1.5	9	.063	2	.031	3	-0...						
166	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	35	1.5	10	.063	2	.044	3	-0...						
167	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	35	1.5	11	.063	2	.054	3	-0...						
168	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	36	1.5	4	.063	2	.063	3							
169	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	36	1.5	5	.063	2	.054	3	.031						
170	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	36	1.5	6	.063	2	.044	3	.044						
171	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	36	1.5	7	.063	2	.031	3	.054						
172	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	36	1.5	8	.063	2		3	.063						
173	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	36	1.5	9	.063	2	-0...	3	.054						
174	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	36	1.5	10	.063	2	-0...	3	.044						
175	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	36	1.5	11	.063	2	-0...	3	.031						
176	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	36	1.5	4	.063	2	-0...	3							
177	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	36	1.5	5	.063	2	-0...	3	-0...						
178	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	36	1.5	6	.063	2	-0...	3	-0...						
179	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	36	1.5	7	.063	2	-0...	3	-0...						
180	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	36	1.5	8	.063	2		3	-0...						
181	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	36	1.5	9	.063	2	.031	3	-0...						
182	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	36	1.5	10	.063	2	.044	3	-0...						
183	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	36	1.5	11	.063	2	.054	3	-0...						
184	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	37	1.5	4	.063	2	.063	3							
185	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	37	1.5	5	.063	2	.054	3	.031						
186	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	37	1.5	6	.063	2	.044	3	.044						
187	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	37	1.5	7	.063	2	.031	3	.054						
188	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	37	1.5	8	.063	2		3	.063						
189	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	37	1.5	9	.063	2	-0...	3	.054						
190	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	37	1.5	10	.063	2	-0...	3	.044						
191	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	37	1.5	11	.063	2	-0...	3	.031						
192	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	37	1.5	4	.063	2	-0...	3							

Load Combinations (Continued)

	Description	Solve	PD...	SR...	B...	Factor	BLC	Factor	B...	Fa...	B...	Fa...	BLC	Fa...	B...	Fa...	B...	Fa...	B...	Fa...	
193	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	37	1.5	5	.063	2	-0...	3	-0...							
194	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	37	1.5	6	.063	2	-0...	3	-0...							
195	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	37	1.5	7	.063	2	-0...	3	-0...							
196	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	37	1.5	8	.063	2		3	-0...							
197	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	37	1.5	9	.063	2	.031	3	-0...							
198	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	37	1.5	10	.063	2	.044	3	-0...							
199	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	37	1.5	11	.063	2	.054	3	-0...							
200	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	38	1.5	4	.063	2	.063	3								
201	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	38	1.5	5	.063	2	.054	3	.031							
202	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	38	1.5	6	.063	2	.044	3	.044							
203	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	38	1.5	7	.063	2	.031	3	.054							
204	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	38	1.5	8	.063	2		3	.063							
205	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	38	1.5	9	.063	2	-0...	3	.054							
206	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	38	1.5	10	.063	2	-0...	3	.044							
207	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	38	1.5	11	.063	2	-0...	3	.031							
208	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	38	1.5	4	.063	2	-0...	3								
209	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	38	1.5	5	.063	2	-0...	3	-0...							
210	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	38	1.5	6	.063	2	-0...	3	-0...							
211	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	38	1.5	7	.063	2	-0...	3	-0...							
212	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	38	1.5	8	.063	2		3	-0...							
213	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	38	1.5	9	.063	2	.031	3	-0...							
214	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	38	1.5	10	.063	2	.044	3	-0...							
215	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	38	1.5	11	.063	2	.054	3	-0...							
216	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	39	1.5	4	.063	2	.063	3								
217	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	39	1.5	5	.063	2	.054	3	.031							
218	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	39	1.5	6	.063	2	.044	3	.044							
219	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	39	1.5	7	.063	2	.031	3	.054							
220	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	39	1.5	8	.063	2		3	.063							
221	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	39	1.5	9	.063	2	-0...	3	.054							
222	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	39	1.5	10	.063	2	-0...	3	.044							
223	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	39	1.5	11	.063	2	-0...	3	.031							
224	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	39	1.5	4	.063	2	-0...	3								
225	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	39	1.5	5	.063	2	-0...	3	-0...							
226	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	39	1.5	6	.063	2	-0...	3	-0...							
227	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	39	1.5	7	.063	2	-0...	3	-0...							
228	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	39	1.5	8	.063	2		3	-0...							
229	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	39	1.5	9	.063	2	.031	3	-0...							
230	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	39	1.5	10	.063	2	.044	3	-0...							
231	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	39	1.5	11	.063	2	.054	3	-0...							

Envelope Joint Reactions

	Joint		X [lb]	LC	Y [lb]	LC	Z [lb]	LC	MX [lb-ft]	LC	MY [lb-ft]	LC	MZ [lb-ft]	LC
1	N25	max	1483.16	3	947.5	20	2000.91	39	403.24	30	395.31	33	1757.46	19
2		min	-1476.25	27	-951.06	12	-61.39	31	-3696.72	38	-2040.58	41	-1763.15	11
3	N1	max	1537.62	17	877.89	8	2056.19	45	3640.55	45	452.79	19	1803.19	25
4		min	-1537.18	25	-869.49	32	-51.21	21	-340.73	21	-2446.93	43	-1809.94	17
5	N13	max	329.97	18	1507.42	22	1952.51	34	697.01	14	4102.02	34	1483.99	30
6		min	-337.61	10	-1512.15	14	-90.73	26	-591.32	22	-511.22	26	-1488.89	6
7	Totals:	max	2939.66	18	2745.56	6	5714.8	45						
8		min	-2939.66	10	-2745.56	30	1361.32	69						



Envelope AISC 15th(360-16): LRFD Steel Code Checks

Member	Shape	Code Check	Loc[in]	LC	Shea...	Lo...	phi*P...	phi*P...	phi*M...	phi*M...	Eqn		
1	SA2	PIPE 3.5	.548	40	45	.185	40	9	64491...	78750	7953...	7953...	H1-1b
2	SA3	PIPE 3.5	.528	40	39	.177	40	3	64491...	78750	7953...	7953...	H1-1b
3	SA1	PIPE 3.5	.516	40	34	.167	40	14	64491...	78750	7953...	7953...	H1-1b
4	PB2	C3X5	.384	34.86	45	.143	63...y	41	32858...	47628	981.26	4104	H1-1b
5	PB3	C3X5	.381	34.86	40	.144	63...y	36	32858...	47628	981.26	4104	H1-1b
6	PB1	C3X5	.365	34.86	34	.137	63...y	46	32858...	47628	981.26	4104	H1-1b
7	MP3	PIPE 2.0	.344	57	5	.037	57	10	20866...	32130	1871...	1871...	1 H1-1b
8	MP9	PIPE 2.0	.343	57	10	.035	57	3	20866...	32130	1871...	1871...	H1-1b
9	MP8	PIPE 2.0	.337	57	10	.040	57	14	20866...	32130	1871...	1871...	H1-1b
10	MP2	PIPE 2.0	.334	57	5	.048	57	9	20866...	32130	1871...	1871...	1 H1-1b
11	MP1	PIPE 2.0	.331	57	16	.042	57	17	20866...	32130	1871...	1871...	H1-1b
12	MP5	PIPE 2.0	.319	57	16	.048	57	3	20866...	32130	1871...	1871...	H1-1b
13	MP6	PIPE 2.0	.318	57	7	.036	57	8	20866...	32130	1871...	1871...	1 H1-1b
14	MP4	PIPE 2.0	.310	57	11	.039	57	11	20866...	32130	1871...	1871...	H1-1b
15	MP7	PIPE 2.0	.308	57	10	.031	57	9	20866...	32130	1871...	1871...	H1-1b
16	CP5	6.5"x0.37" Plate	.240	21	12	.104	21 y	42	27548...	75757...	583.96	6626...	H1-1b
17	CP6	6.5"x0.37" Plate	.238	21	7	.102	21 y	37	27548...	75757...	583.96	6365.2	H1-1b
18	CP4	6.5"x0.37" Plate	.238	21	2	.097	21 y	48	27548...	75757...	583.96	6391...	H1-1b
19	M19	PIPE 2.0	.167	72	10	.174	72	2	14916...	32130	1871...	1871...	H1-1b
20	M21	PIPE 2.0	.166	72	5	.172	72	13	14916...	32130	1871...	1871...	H1-1b
21	M20	PIPE 2.0	.158	72	15	.170	72	8	14916...	32130	1871...	1871...	H1-1b
22	IFH11	L2x2x3	.150	0	3	.027	0 z	49	18084...	23392...	557.72	1179...	1 H2-1
23	IFH21	L2x2x3	.148	0	14	.027	0 z	43	18084...	23392...	557.72	1182...	1 H2-1
24	IFH 31	L2x2x3	.123	0	9	.027	0 z	38	18084...	23392...	557.72	1182...	1 H2-1
25	IFH32	L2x2x3	.107	0	13	.030	0 y	42	18084...	23392...	557.72	1182...	1 H2-1
26	H1	PIPE 3.5	.099	34	12	.105	24	10	60666...	78750	7953...	7953...	H1-1b
27	H3	PIPE 3.5	.098	34	2	.104	24	16	60666...	78750	7953...	7953...	H1-1b
28	IFH22	L2x2x3	.092	0	2	.029	0 y	47	18084...	23392...	557.72	1182...	1 H2-1
29	H2	PIPE 3.5	.092	34	7	.097	24	5	60666...	78750	7953...	7953...	H1-1b
30	IFH12	L2x2x3	.092	0	8	.029	0 y	36	18084...	23392...	557.72	1179...	1 H2-1
31	CP3	6.6x4.46x0.25	.089	0	21	.039	42 z	4	51170...	87561	2464...	7125...	1 H2-1
32	CP2	6.6x4.46x0.25	.087	0	26	.038	0 y	9	51170...	87561	2464...	7125...	1 H2-1
33	CP1	6.6x4.46x0.25	.080	0	32	.036	0 y	14	51170...	87561	2464...	7125...	1 H2-1

Envelope AISI 100-12: LRFD Cold Formed Steel Code Checks

Member	Shape	Code Check	Loc[in]	LC	Shea...	Loc[i..Dir	LC	phi*Pn[...	phi*Tn[...	phi*Mn...	phi*Mn...	Cb	Cmy	Cmzz	Eqn
No Data to Print ...															

APPENDIX D
ADDITIONAL CALCUATIONS

BOLT TOOL 1.5.2

Project Data	
Job Code:	189028
Carrier Site ID:	BOHVN00009A
Carrier Site Name:	CT-CCI-T-806358


Code	
Design Standard:	TIA-222-H
Slip Check:	No
Pretension Standard:	AISC

Bolt Properties		
Connection Type:	Bolt	
Diameter:	0.625	in
Grade:	A325	--
Yield Strength (Fy):	92	ksi
Ultimate Strength (Fu):	120	ksi
Number of Bolts:	4	--
Threads Included:	No	--
Double Shear:	No	--
Connection Pipe Size:	-	in

Connection Description
Standoff to Monopole

Bolt Check*		
Tensile Capacity (ϕT_n):	20340.1	lbs
Shear Capacity (ϕV_n):	17257.3	lbs
Tension Force (T_u):	4497.9	lbs
Shear Force (V_u):	727.8	lbs
Tension Usage:	21.1%	--
Shear Usage:	4.0%	--
Interaction:	21.1%	Pass
Controlling Member:	SA2	--
Controlling LC:	42	--

*Rating per TIA-222-H Section 15.5




APPENDIX E
SUPPLEMENTAL DRAWINGS

ITEM	PART NO.	DESCRIPTION	QTY.	WEIGHT	NOTE NO.
1	MTC3006SB	STEEL BUNDLE FOR SNUB NOSE PLATFORM	1	402.64 LBS	
2	MCPK8CSB	PIPE STEEL BUNDLE FOR MC-PK8-C	1	464.27 LBS	
3	MCPK8CHWK	HARDWARE KIT FOR MC-PK8-C	1	543.22 LBS	



FOR BOM ENTRY ONLY



REV.	ECN	DESCRIPTION	BY	DATE
A		INITIAL RELEASE	DRR	12/27/11
B	8000005979	CHANGE NOSE CORNER BRKT. ADD GUB-4240	MSM	11/25/14
C	8000007579	NEW RINGMOUNT WELDMENT DESIGN	RJC	04/07/15

These drawings are specifications for the assembly property of Andrew Corporation and may be used only for the specific application intended in writing by Andrew Corporation.

ALL DIMENSIONS ARE IN INCHES UNLESS OTHERWISE SPECIFIED:
 X = ± .12 ANGLES ±Z
 XX = ± .06 FRACTIONS ±1/32
 XXX = ± .03
 REMOVE BURRS AND BREAK EDGES 0.05




DO NOT SCALE THIS PRINT

DATE OF ISSUE	MSM	1 of 3	REV. NO.	MC-PK8-C
DATE OF ISSUE	TP	NTS	DESCRIPTION	LOW PROFILE PLATFORM KIT 8' FACE ASSEMBLY DRAWING
DATE OF ISSUE	10/18/11	A36, A500	REGION	GALV. A123
DATE OF ISSUE	C	1410.14 LBS		

NOTES:
 1. CUSTOMER ASSEMBLY SHEETS 2-3.

WESTCHESTER, IL. 60154
ANDREW®
 U.S.A.

38 [965.2]
15 [381.0]



NOTES:
1. ALL METRIC DIMENSIONS ARE IN BRACKETS.
2. WILL FIT MONOPOLES 15"-38" OD.

ITEM	PART NO.	DESCRIPTION	QTY.	WEIGHT
1	MC-RM1550-3	12" - 50" OD RINGMOUNT	1	230.42 LBS
2	MTC300601	Low Profile Co-Location Platform Snub Nose	3	134.21 LBS
3	MT1195801	Corner Weldment Snub Nose Handrail	3	27.10 LBS
4	XA2020.01	CROSS OVER ANGLE	9	2.65 LBS
5	GUB-4356	1/2" X 3-5/8" X 6" GALV U-BOLT	18	0.82 LBS
6	GUB-4355	1/2" X 3-5/8" X 5" GALV U-BOLT	12	0.71 LBS
7	GUB-4240	1/2" X 2-1/2" X 4" GALV U-BOLT	48	0.56 LBS
8	GB-04145	1/2" X 1-1/2" GALV BOLT KIT	12	0.13 LBS
9	GW-F-04	1/2" GALV FLAT WASHER	24	0.03 LBS
10	GB-0520A	5/8" X 2" GALV BOLT KIT (A325)	12	0.27 LBS
11	MT154796	3.50" OD X 96" GALV PIPE	3	60.28 LBS
12	MT-651-96	Ø2.375" OD X 96" PIPE	3	29.07 LBS
13	MT-651	2.375" OD x 72" PIPE	9	21.80 LBS
14	MT119617	MT196 Pipe Mount Plate	6	2.49 LBS
15	MT21701	PIPE MOUNT PLATE	9	7.93 LBS

These drawings are the property of Andrew Corporation and may be used only for the specific application intended in writing by Andrew Corporation.


ALL DIMENSIONS ARE IN INCHES UNLESS OTHERWISE SPECIFIED:
 X = ± .12
 XX = ± .06
 XXX = ± .03
 FEMME BURRS AND BREAK EDGES DES

ANGLES 4Z
 FRACTIONS ±1/32
 REGION C


DO NOT SCALE THIS PRINT

REV. NO.	MSM	QTY.	2 of 3	REV. NO.	MC-PK8-C
DATE	NTS	QTY.		DATE	25" OD Snub Nose MT-196
BY	A36, A53	QTY.		BY	ASSEMBLY DRAWING
CHECKED	GALV A123	QTY.		CHECKED	
APPROVED	136127 LBS	QTY.		APPROVED	


WESTCHESTER, IL. 60154
ANDREW®
 U.S.A.




WITH ANTENNAS



DETAIL A
SCALE 1 : 8



DETAIL C
SCALE 1 : 8



DETAIL B
SCALE 1 : 8

<p>These drawings are specifications on the proprietary property of Andrew Corporation and may be used only for the specific application intended in writing by Andrew Corporation.</p> <p>ALL DIMENSIONS ARE IN INCHES UNLESS OTHERWISE SPECIFIED: X = ± .12 ANGLES ±Z XX = ± .06 FRACTIONS ±1/32 XXX = ± .03 REMOVE BURRS AND BREAK EDGES D05</p>	<p>QUANTITY 3 of 3</p>	<p>REV. 10/18/11</p>	<p>DATE 10/18/11</p>	<p>SCALE 25" OD Sub. Nose W1-196</p>	<p>MODEL NO. MC-PK8-C</p>
	<p>STANDARD NTS</p>	<p>TP</p>	<p>REVISION C</p>	<p>ASSEMBLY DRAWING</p>	<p>WESTCHESTER, ILL. 60154 U.S.A.</p>
	<p>UNIT A36, A53</p>	<p>REGION GALV. A123</p>	<p>WEIGHT 1361.27 LBS</p>	<p>ANDREW®</p>	<p>WESTCHESTER, ILL. 60154 U.S.A.</p>
	<p>DO NOT SCALE THIS PRINT</p>				

NOTES:
1. ALL METRIC DIMENSIONS ARE IN BRACKETS.

Exhibit F

Power Density/RF Emissions Report

RADIO FREQUENCY EMISSIONS ANALYSIS REPORT
EVALUATION OF HUMAN EXPOSURE POTENTIAL
TO NON-IONIZING EMISSIONS

Dish Wireless Existing Facility

Site ID: BOHVN00009A

806358

1432 Old Waterbury Road
Southbury, Connecticut 06488

September 29, 2021

EBI Project Number: 6221005713

Site Compliance Summary	
Compliance Status:	COMPLIANT
Site total MPE% of FCC general population allowable limit:	10.40%

September 29, 2021

Dish Wireless

Emissions Analysis for Site: BOHVN00009A - 806358

EBI Consulting was directed to analyze the proposed Dish Wireless facility located at **1432 Old Waterbury Road in Southbury, Connecticut** for the purpose of determining whether the emissions from the Proposed Dish Wireless Antenna Installation located on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter ($\mu\text{W}/\text{cm}^2$). The number of $\mu\text{W}/\text{cm}^2$ calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits; therefore, it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) – (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general population may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general population would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

Public exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter ($\mu\text{W}/\text{cm}^2$). The general population exposure limits for the 600 MHz and 700 MHz frequency bands are approximately $400 \mu\text{W}/\text{cm}^2$ and $467 \mu\text{W}/\text{cm}^2$, respectively. The general population exposure limit for the 1900 MHz (PCS), 2100 MHz (AWS) and 11 GHz frequency bands is $1000 \mu\text{W}/\text{cm}^2$. Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.

Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully

aware of the potential for exposure and can exercise control over their exposure. Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

CALCULATIONS

Calculations were done for the proposed Dish Wireless antenna facility located at 1432 Old Waterbury Road in Southbury, Connecticut using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. Since Dish Wireless is proposing highly focused directional panel antennas, which project most of the emitted energy out toward the horizon, all calculations were performed assuming a lobe representing the maximum gain of the antenna per the antenna manufacturer's supplied specifications, minus 20 dB for directional panel antennas and 20 dB for highly focused parabolic microwave dishes, was focused at the base of the tower. For this report, the sample point is the top of a 6-foot person standing at the base of the tower.

For all calculations, all equipment was calculated using the following assumptions:

- 1) 4 n71 channels (600 MHz Band) were considered for each sector of the proposed installation. These Channels have a transmit power of 30 Watts per Channel.
- 2) 4 n70 channels (PCS Band - 1900 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 40 Watts per Channel.
- 3) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 - Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.
- 4) For the following calculations, the sample point was the top of a 6-foot person standing at the base of the tower. The maximum gain of the antenna per the antenna manufacturer's supplied specifications, minus 20 dB for directional panel antennas and 20 dB for highly focused parabolic microwave dishes, was used in this direction. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.

- 5) The antennas used in this modeling are the JMA MX08FRO665-20 for the 600 MHz / 1900 MHz channel(s) in Sector A, the JMA MX08FRO665-20 for the 600 MHz / 1900 MHz channel(s) in Sector B, the JMA MX08FRO665-20 for the 600 MHz / 1900 MHz channel(s) in Sector C. This is based on feedback from the carrier with regard to anticipated antenna selection. All Antenna gain values and associated transmit power levels are shown in the Site Inventory and Power Data table below. The maximum gain of the antenna per the antenna manufacturer's supplied specifications, minus 20 dB for directional panel antennas and 20 dB for highly focused parabolic microwave dishes, was used for all calculations. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 6) The antenna mounting height centerline of the proposed antennas is 218 feet above ground level (AGL).
- 7) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.
- 8) All calculations were done with respect to uncontrolled / general population threshold limits.

Dish Wireless Site Inventory and Power Data

Sector:	A	Sector:	B	Sector:	C
Antenna #:	1	Antenna #:	1	Antenna #:	1
Make / Model:	JMA MX08FRO665-20	Make / Model:	JMA MX08FRO665-20	Make / Model:	JMA MX08FRO665-20
Frequency Bands:	600 MHz / 1900 MHz	Frequency Bands:	600 MHz / 1900 MHz	Frequency Bands:	600 MHz / 1900 MHz
Gain:	17.45 dBd / 22.65 dBd	Gain:	17.45 dBd / 22.65 dBd	Gain:	17.45 dBd / 22.65 dBd
Height (AGL):	218 feet	Height (AGL):	218 feet	Height (AGL):	218 feet
Channel Count:	8	Channel Count:	8	Channel Count:	8
Total TX Power (W):	280 Watts	Total TX Power (W):	280 Watts	Total TX Power (W):	280 Watts
ERP (W):	3,065.51	ERP (W):	3,065.51	ERP (W):	3,065.51
Antenna AI MPE %:	0.35%	Antenna BI MPE %:	0.35%	Antenna CI MPE %:	0.35%

Site Composite MPE %	
Carrier	MPE %
Dish Wireless (Max at Sector A):	0.35%
AT&T	2.56%
Metro PCS	0.27%
Sprint	1.86%
T-Mobile	4.44%
Verizon	0.92%
Site Total MPE % :	10.40%

Dish Wireless MPE % Per Sector	
Dish Wireless Sector A Total:	0.35%
Dish Wireless Sector B Total:	0.35%
Dish Wireless Sector C Total:	0.35%
Site Total MPE % :	10.40%

Dish Wireless Maximum MPE Power Values (Sector A)							
Dish Wireless Frequency Band / Technology (Sector A)	# Channels	Watts ERP (Per Channel)	Height (feet)	Total Power Density ($\mu\text{W}/\text{cm}^2$)	Frequency (MHz)	Allowable MPE ($\mu\text{W}/\text{cm}^2$)	Calculated % MPE
Dish Wireless 600 MHz n71	4	223.68	218.0	0.72	600 MHz n71	400	0.18%
Dish Wireless 1900 MHz n70	4	542.70	218.0	1.74	1900 MHz n70	1000	0.17%
						Total:	0.35%

• NOTE: Totals may vary by approximately 0.01% due to summation of remainders in calculations.

Summary

All calculations performed for this analysis yielded results that were **within** the allowable limits for general population exposure to RF Emissions.

The anticipated maximum composite contributions from the Dish Wireless facility as well as the site composite emissions value with regards to compliance with FCC's allowable limits for general population exposure to RF Emissions are shown here:

Dish Wireless Sector	Power Density Value (%)
Sector A:	0.35%
Sector B:	0.35%
Sector C:	0.35%
Dish Wireless Maximum MPE % (Sector A):	0.35%
Site Total:	10.40%
Site Compliance Status:	COMPLIANT

The anticipated composite MPE value for this site assuming all carriers present is **10.40%** of the allowable FCC established general population limit sampled at the ground level. This is based upon values listed in the Connecticut Siting Council database for existing carrier emissions.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.

Exhibit G

Letter of Authorization



4545 E River Rd, Suite 320
West Henrietta, NY 14586

Phone: (585) 445-5896
Fax: (724) 416-4461
www.crowncastle.com

Crown Castle Letter of Authorization

CT - CONNECTICUT SITING COUNCIL

Melanie A. Bachman
Executive Director
Connecticut Siting Council
10 Franklin Square
New Britain, CT 06051

**Re: Tower Share Application
Crown Castle telecommunications site at:
1432 OLD WATERBURY ROAD, SOUTHURY, CT 06488**

CROWN ATLANTIC COMPANY LLC (“Crown Castle”) hereby authorizes DISH Wireless, LLC, including their Agent, to act as our Agent in the processing of all zoning applications, building permits and approvals through the CT - CONNECTICUT SITING COUNCIL for the existing wireless communications site described below:

**Crown Site ID/Name: 806358/NHV 109 943107
Customer Site ID: BOHVN00009A/CT-CCI-T-806358
Site Address: 1432 Old Waterbury Road, SOUTHURY, CT 06488**

Crown Castle



By:  _____ Date: 10/4/2021
Richard Zajac
Site Acquisition Specialist

Exhibit H

Recipient Mailings



**UNITED STATES
POSTAL SERVICE®**

Click-N-Ship®

P

usps.com 9405 5036 9930 0026 0278 68 0087 0000 0010 6488
US POSTAGE
 Flat Rate Env
U.S. POSTAGE PAID
click-n-ship®

10/07/2021 Mailed from 01566


PRIORITY MAIL 2-DAY™

Expected Delivery Date: 10/12/21
 Ref#: DS-806358
0006

C008

SHIP TO: JEFF MANVILLE
 FIRST SELECTMAN-SOUTHBURY
 501 MAIN ST S
 SOUTHBURY CT 06488-4217

USPS TRACKING #



9405 5036 9930 0026 0278 68

Electronic Rate Approved #038555749



Cut on dotted line.

Instructions

1. Each Click-N-Ship® label is unique. Labels are to be used as printed and used only once. DO NOT PHOTO COPY OR ALTER LABEL.
2. Place your label so it does not wrap around the edge of the package.
3. Adhere your label to the package. A self-adhesive label is recommended. If tape or glue is used, DO NOT TAPE OVER BARCODE. Be sure all edges are secure.
4. To mail your package with PC Postage®, you may schedule a Package Pickup online, hand to your letter carrier, take to a Post Office™, or drop in a USPS collection box.
5. Mail your package on the "Ship Date" you selected when creating this label.

Click-N-Ship® Label Record

USPS TRACKING # :
9405 5036 9930 0026 0278 68

Trans. #: 545413463	Priority Mail® Postage: \$8.70
Print Date: 10/07/2021	Total: \$8.70
Ship Date: 10/07/2021	
Expected Delivery Date: 10/12/2021	


From: DEBORAH CHASE
 NORTHEAST SITE SOLUTIONS
 420 MAIN ST
 STE 1
 STURBRIDGE MA 01566-1359
 Ref#: DS-806358

To: JEFF MANVILLE
 FIRST SELECTMAN-SOUTHBURY
 501 MAIN ST S
 SOUTHBURY CT 06488-4217

* Retail Pricing Priority Mail rates apply. There is no fee for USPS Tracking® service on Priority Mail service with use of this electronic rate shipping label. Refunds for unused postage paid labels can be requested online 30 days from the print date.



Thank you for shipping with the United States Postal Service!
 Check the status of your shipment on the USPS Tracking® page at usps.com



USPS TRACKING #

9405 5036 9930 0026 0278 75

Electronic Rate Approved #038555749

SHIP TO: KATHY CASTAGNETTA
AICP, LAND USE ADMINISTRATOR
501 MAIN ST S
SOUTHURY CT 06488-4217

C008

P

10/07/2021

USPS.com
US POSTAGE
Flat Rate Env
\$8.70

9405 5036 9930 0026 0278 75 0087 0000 0010 6488


Mailed from 01566

U.S. POSTAGE PAID
click-n-ship®

PRIORITY MAIL 2-DAY™

Expected Delivery Date: 10/12/21
Re#: DS-806358
0006

DEBORAH CHASE
NORTHEAST SITE SOLUTIONS
420 MAIN ST
STE 1
STURBRIDGE MA 01566-1359



Click-N-Ship®



Cut on dotted line.

Instructions

1. Each Click-N-Ship® label is unique. Labels are to be used as printed and used only once. DO NOT PHOTO COPY OR ALTER LABEL.
2. Place your label so it does not wrap around the edge of the package.
3. Adhere your label to the package. A self-adhesive label is recommended. If tape or glue is used, DO NOT TAPE OVER BARCODE. Be sure all edges are secure.
4. To mail your package with PC Postage®, you may schedule a Package Pickup online, hand to your letter carrier, take to a Post Office™, or drop in a USPS collection box.
5. Mail your package on the "Ship Date" you selected when creating this label.

Click-N-Ship® Label Record

USPS TRACKING # :
9405 5036 9930 0026 0278 75

Trans. #: 545413463	Priority Mail® Postage: \$8.70
Print Date: 10/07/2021	Total: \$8.70
Ship Date: 10/07/2021	
Expected Delivery Date: 10/12/2021	


From: DEBORAH CHASE Re#: DS-806358
NORTHEAST SITE SOLUTIONS
420 MAIN ST
STE 1
STURBRIDGE MA 01566-1359

To: KATHY CASTAGNETTA
AICP, LAND USE ADMINISTRATOR
501 MAIN ST S
SOUTHURY CT 06488-4217

* Retail Pricing Priority Mail rates apply. There is no fee for USPS Tracking® service on Priority Mail service with use of this electronic rate shipping label. Refunds for unused postage paid labels can be requested online 30 days from the print date.



Thank you for shipping with the United States Postal Service!
Check the status of your shipment on the USPS Tracking® page at usps.com



USPS TRACKING #

9405 5036 9930 0026 0278 82

Electronic Rate Approved #038555749

P

10/07/2021


PRIORITY MAIL 2-DAY™

Expected Delivery Date: 10/12/21
Re#: DS-806358
0006

R013

SHIP TO: RICH ZAJAC
CROWN CASTLE
4545 E RIVER RD
STE 320
W HENRIETTA NY 14586-9024

DEBORAH CHASE
NORTHEAST SITE SOLUTIONS
420 MAIN ST
STE 1
STURBRIDGE MA 01566-1359



UNITED STATES POSTAL SERVICE®

Click-N-Ship®

usps.com 9405 5036 9930 0026 0278 82 0087 0000 0031 4586
US POSTAGE \$8.70
 Flat Rate Envoy

U.S. POSTAGE PAID
Click-N-Ship®

Mailed from 01566



Cut on dotted line.

Instructions

1. Each Click-N-Ship® label is unique. Labels are to be used as printed and used only once. DO NOT PHOTO COPY OR ALTER LABEL.
2. Place your label so it does not wrap around the edge of the package.
3. Adhere your label to the package. A self-adhesive label is recommended. If tape or glue is used, DO NOT TAPE OVER BARCODE. Be sure all edges are secure.
4. To mail your package with PC Postage®, you may schedule a Package Pickup online, hand to your letter carrier, take to a Post Office™, or drop in a USPS collection box.
5. Mail your package on the "Ship Date" you selected when creating this label.

Click-N-Ship® Label Record

USPS TRACKING # :
9405 5036 9930 0026 0278 82

Trans. #: 545413463	Priority Mail® Postage: \$8.70
Print Date: 10/07/2021	Total: \$8.70
Ship Date: 10/07/2021	
Expected Delivery Date: 10/12/2021	

From: DEBORAH CHASE
NORTHEAST SITE SOLUTIONS
420 MAIN ST
STE 1
STURBRIDGE MA 01566-1359

Re#: DS-806358

To: RICH ZAJAC
CROWN CASTLE
4545 E RIVER RD
STE 320
W HENRIETTA NY 14586-9024

* Retail Pricing Priority Mail rates apply. There is no fee for USPS Tracking® service on Priority Mail service with use of this electronic rate shipping label. Refunds for unused postage paid labels can be requested online 30 days from the print date.



Thank you for shipping with the United States Postal Service!
 Check the status of your shipment on the USPS Tracking® page at usps.com