



April 3rd, 2019

Melanie Bachman, Executive Director
Connecticut Siting Council
10 Franklin Square
New Britain, CT 06051

RE: Notice of Exempt Modification – Antenna Modification for wireless facility located at 80 Shuttle Meadow Road, Southington, CT 06489 - CT52XC108 (lat. 41.638600 N, long. -72.841100 W)

Dear Ms. Bachman:

Sprint Spectrum, LP ("Sprint") currently maintains wireless telecommunications antennas at the (120-foot level) on an existing (150-foot monopole tower) at the above-referenced address. The property is owned by Enfield School District and the tower is owned by American Tower Corporation.

Sprint's proposed work involves antenna replacement and tower work. Sprint intends to replace three (3) antennas with six (6) new antennas and add nine (9) RRHs onto the tower. All the proposed work is contained within the existing fenced area. Please refer to the attached drawings for site plans prepared by Infinigy Engineering.

Please accept this letter as notification pursuant to R.C.S.A. § 16-50j-73, for construction that constitutes an exempt modification pursuant to R.C.S.A. § 16-50j-72(b). In accordance with R.C.S.A. § 16-50j-73, a copy of this letter is being sent to MICHAEL LUDWICK, MAYOR and LAURIE WHITTEN, DIRECTOR OF DEVELOPMENT SERVICES for the TOWN OF ENFIELD. A copy of this letter is also being sent to AMERICAN TOWER CORPORATION the owner of the tower, and The ENFIELD SCHOOL DISTRICT who owns the property.

The planned modifications to the facility fall squarely within those activities explicitly provided for in R.C.S.A. § 16-50j-72(b).

1. The proposed modifications will not result in an increase in the height of the existing tower.
2. The antennas work is a like-for-like replacement of existing facility components and additional components to increase capacity and employ updated technologies.



3. The proposed modifications will include the addition of ground base equipment as depicted on the attached drawings; however, the proposed equipment will not require an extension of the site boundaries.
4. The proposed modifications will not increase noise levels at the facility by six decibels or more.
5. The additional ground based equipment will not increase radio frequency (RF) emissions at the facility to a level at or above the Federal Communications Commission (FCC) adopted safety standard.

For the foregoing reasons, Sprint respectfully submits that the proposed modifications to the above referenced telecommunications facility constitutes an exempt modification under R.C.S.A. § 16-50j-72(b).

If you have any questions or require any additional information regarding this request, please do not hesitate to give me a call at (518) 796-9165 or email me to rperry@airosmithdevelopment.com

Kind Regards,

Raymond A Perry

Ray Perry
Airosmith Development Inc.
32 Clinton Street
Saratoga Springs, NY 12866
518-796-9165 cell
518-306-1711 fax
rperry@airosmithdevelopment.com

Attachment

CC: MARK SCIOTA (Town Manager, Southington, CT)
KEITH HAYDEN P.E. (Director of Public Works, Southington, CT)
JUSTINE PAUL (Property & Tower Owner – Southern New England Telephone Co. C/O American Tower Corporation)



7018 2290 0000 8504 6644

U.S. Postal Service™
CERTIFIED MAIL® RECEIPT
Domestic Mail Only

For delivery information, visit our website at www.usps.com®.

WOUBURN, MA 01891


OFFICIAL USE

| | |
|--|--------|
| Certified Mail Fee | \$3.50 |
| Extra Services & Fees (check box, add fee as appropriate) | \$2.80 |
| <input type="checkbox"/> Return Receipt (hardcopy) | \$0.00 |
| <input type="checkbox"/> Return Receipt (electronic) | \$0.00 |
| <input type="checkbox"/> Certified Mail Restricted Delivery | \$0.00 |
| <input type="checkbox"/> Adult Signature Required | \$0.00 |
| <input type="checkbox"/> Adult Signature Restricted Delivery | \$0.00 |

| | |
|------------------------|--------|
| Postage | \$0.55 |
| Total Postage and Fees | \$6.85 |

Sent To Joshua Paul
 Street and Apt. No., or PO Box No. 10 President Way
 City, State, ZIP+4® Woburn MA 01801

PS Form 3800, April 2015 PSN 7530-02-000-9047 See Reverse for Instructions



7018 2290 0000 8504 6675

U.S. Postal Service™
CERTIFIED MAIL® RECEIPT
Domestic Mail Only

For delivery information, visit our website at www.usps.com®.

SOUTHINGTON, CT 06489

OFFICIAL USE

| | |
|--|--------|
| Certified Mail Fee | \$3.50 |
| Extra Services & Fees (check box, add fee as appropriate) | \$2.80 |
| <input type="checkbox"/> Return Receipt (hardcopy) | \$0.00 |
| <input type="checkbox"/> Return Receipt (electronic) | \$0.00 |
| <input type="checkbox"/> Certified Mail Restricted Delivery | \$0.00 |
| <input type="checkbox"/> Adult Signature Required | \$0.00 |
| <input type="checkbox"/> Adult Signature Restricted Delivery | \$0.00 |

| | |
|------------------------|--------|
| Postage | \$0.55 |
| Total Postage and Fees | \$6.85 |

Sent To Mark Sciotto
 Street and Apt. No., or PO Box No. 75 Main St
 City, State, ZIP+4® Southington, CT 06489

PS Form 3800, April 2015 PSN 7530-02-000-9047 See Reverse for Instructions



7018 2290 0000 8504 6668

U.S. Postal Service™
CERTIFIED MAIL® RECEIPT
Domestic Mail Only

For delivery information, visit our website at www.usps.com®.

SOUTHINGTON, CT 06489

OFFICIAL USE

| | |
|--|--------|
| Certified Mail Fee | \$3.50 |
| Extra Services & Fees (check box, add fee as appropriate) | \$2.80 |
| <input type="checkbox"/> Return Receipt (hardcopy) | \$0.00 |
| <input type="checkbox"/> Return Receipt (electronic) | \$0.00 |
| <input type="checkbox"/> Certified Mail Restricted Delivery | \$0.00 |
| <input type="checkbox"/> Adult Signature Required | \$0.00 |
| <input type="checkbox"/> Adult Signature Restricted Delivery | \$0.00 |

| | |
|------------------------|--------|
| Postage | \$0.55 |
| Total Postage and Fees | \$6.85 |

Sent To Keith Hayden
 Street and Apt. No., or PO Box No. 196 North Main St Lower Level
 City, State, ZIP+4® Southington, CT 06489

PS Form 3800, April 2015 PSN 7530-02-000-9047 See Reverse for Instructions





PROJECT: DO MACRO UPGRADE
 SITE NAME: STTN - SOUTHINGTON
 SITE CASCADE: CT52XC108
 SITE ADDRESS: 80 SHUTTLE MEADOW ROAD
 SOUTHINGTON, CT 06489
 SITE TYPE: MONOPOLE TOWER
 MARKET: NORTHERN CONNECTICUT

PLANS PREPARED FOR:



PLANS PREPARED BY:



PROJECT MANAGER:



ENGINEERING LICENSE:



DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

| DESCRIPTION | DATE | BY | REV. |
|-------------------|----------|-----|------|
| ISSUED FOR PERMIT | 02/22/19 | MAP | 0 |

SITE NAME:

STTN - SOUTHINGTON

SITE NUMBER:

CT52XC108

SITE ADDRESS:

80 SHUTTLE MEADOW ROAD
SOUTHINGTON, CT 06489

SHEET DESCRIPTION:

TITLE SHEET & PROJECT DATA

SHEET NUMBER:

T-1

SITE INFORMATION

TOWER OWNER:
AMERICAN TOWER CORPORATION
10 PRESIDENTIAL WAY
WOBURN, MA 01801

LATITUDE (NAD83):
41° 38' 18.9" N
41.63858333

LONGITUDE (NAD83):
72° 50' 28.0" W
-72.8411

COUNTY:
HARTFORD

ZONING JURISDICTION:
CONNECTICUT SITING COUNCIL


ZONING DISTRICT:
TBD

POWER COMPANY:
CL&P
PHONE: (800) 286-2000

AAV PROVIDER:
AT&T
PHONE: (800) 288-2020

PROJECT MANAGER:
AIROSMITH DEVELOPMENT
TERRI BURKHOLDER
(315) 719-2928
TBURKHOLDER@AIROSMITHDEVELOPMENT.COM

AREA MAP



LOCATION MAP



PROJECT DESCRIPTION

SPRINT PROPOSES TO MODIFY AN EXISTING UNMANNED TELECOMMUNICATIONS FACILITY.

- REMOVE (3) PANEL ANTENNAS AND RRH'S
- INSTALL (6) PANEL ANTENNAS
- INSTALL (3) 1900 MHz RRH'S BEHIND ANTENNAS
- INSTALL (6) 800 MHz RRH'S BEHIND ANTENNAS
- INSTALL (3) 2.5 GHz RRH'S BEHIND ANTENNAS
- INSTALL (48) JUMPER CABLES
- INSTALL (4) HYBRID CABLES
- REMOVE EXISTING CLEARWIRE GROUND EQUIPMENT
- INSTALL (2) EQUIPMENT CABINETS WITHIN EXISTING LEASE AREA
- INSTALL 7'x7' CONCRETE EQUIPMENT PAD

THESE PLANS HAVE BEEN DEVELOPED FOR THE MODIFICATION OF AN EXISTING UNMANNED TELECOMMUNICATIONS FACILITY OWNED OR LEASED BY SPRINT IN ACCORDANCE WITH THE SCOPE OF WORK PROVIDED BY SPRINT. INFINIGY HAS INCORPORATED THIS SCOPE OF WORK IN THE PLANS. THESE PLANS ARE NOT FOR CONSTRUCTION UNLESS ACCOMPANIED BY A PASSING STRUCTURAL STABILITY ANALYSIS PREPARED BY A LICENSED STRUCTURAL ENGINEER. STRUCTURAL ANALYSIS MUST INCLUDE BOTH TOWER AND MOUNT.

APPLICABLE CODES

ALL WORK SHALL BE PERFORMED AND MATERIALS INSTALL IN ACCORDANCE WITH THE CURRENT EDITIONS OF THE FOLLOWING CODES AS ADOPTED BY THE LOCAL GOVERNING AUTHORITIES. NOTHING IN THESE PLANS IS TO BE CONSTRUED TO PERMIT WORK NOT CONFORMING TO THESE CODES.

- INTERNATIONAL BUILDING CODE (2015 IBC)
- TIA-222-G OR LATEST EDITION
- NFPA 780 - LIGHTNING PROTECTION CODE
- 2011 NATIONAL ELECTRIC CODE OR LATEST EDITION
- ANY OTHER NATIONAL OR LOCAL APPLICABLE CODES, MOST RECENT EDITIONS
- CT BUILDING CODE
- LOCAL BUILDING CODE
- CITY/COUNTY ORDINANCES

DRAWING INDEX

| SHEET NO. | SHEET TITLE | REV. |
|-----------|-----------------------------------|------|
| T-1 | TITLE SHEET & PROJECT DATA | 0 |
| SP-1 | SPRINT SPECIFICATIONS | 0 |
| SP-2 | SPRINT SPECIFICATIONS | 0 |
| SP-3 | SPRINT SPECIFICATIONS | 0 |
| A-1 | SITE PLAN | 0 |
| A-2 | TOWER ELEVATION | 0 |
| A-3 | ANTENNA LAYOUT & MOUNTING DETAILS | 0 |
| A-4 | EQUIPMENT & MOUNTING DETAILS | 0 |
| A-5 | EQUIPMENT & MOUNTING DETAILS | 0 |
| A-6 | EQUIPMENT DETAILS | 0 |
| A-7 | CIVIL DETAILS | 0 |
| A-8 | PLUMBING DIAGRAM | 0 |
| E-1 | ONE LINE & NOTES | 0 |
| E-2 | ELECTRICAL & GROUNDING DETAILS | 0 |
| E-3 | ELECTRICAL & GROUNDING DETAILS | 0 |



THESE OUTLINE SPECIFICATIONS IN CONJUNCTION WITH THE SPRINT STANDARD CONSTRUCTION SPECIFICATIONS, INCLUDING CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

SECTION 01 100 – SCOPE OF WORK

PART 1 – GENERAL

- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE SPRINT CONSTRUCTION STANDARDS FOR WIRELESS SITES, CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
 - A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
 - B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.
- 1.3 PRECEDENCE: SHOULD CONFLICTS OCCUR BETWEEN THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES INCLUDING THE STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES AND THE CONSTRUCTION DRAWINGS, INFORMATION ON THE CONSTRUCTION DRAWINGS SHALL TAKE PRECEDENCE. NOTIFY SPRINT CONSTRUCTION MANAGER IF THIS OCCURS.
- 1.4 NATIONALLY RECOGNIZED CODES AND STANDARDS:
 - A. THE WORK SHALL COMPLY WITH APPLICABLE NATIONAL AND LOCAL CODES AND STANDARDS, LATEST EDITION, AND PORTIONS THEREOF, INCLUDED BUT NOT LIMITED TO THE FOLLOWING:
 - 1. GR-63-CORE NEBS REQUIREMENTS: PHYSICAL PROTECTION
 - 5. GR-78-CORE GENERIC REQUIREMENTS FOR THE PHYSICAL DESIGN AND MANUFACTURE OF TELECOMMUNICATIONS EQUIPMENT.
 - 3. GR-1089 CORE, ELECTROMAGNETIC COMPATIBILITY AND ELECTRICAL SAFETY –GENERIC CRITERIA FOR NETWORK TELECOMMUNICATIONS EQUIPMENT.
 - 4. NATIONAL FIRE PROTECTION ASSOCIATION CODES AND STANDARDS (NFPA) INCLUDING NFPA 70 (NATIONAL ELECTRICAL CODE – 'NEC') AND NFPA 101 (LIFE SAFETY CODE).
 - 5. AMERICAN SOCIETY FOR TESTING OF MATERIALS (ASTM)
 - 6. INSTITUTE OF ELECTRONIC AND ELECTRICAL ENGINEERS (IEEE)
 - 7. AMERICAN CONCRETE INSTITUTE (ACI)
 - 8. AMERICAN WIRE PRODUCERS ASSOCIATION (AWPA)
 - 9. CONCRETE REINFORCING STEEL INSTITUTE (CRSI)
 - 10. AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (ASHTO)
 - 11. PORTLAND CEMENT ASSOCIATION (PCA)
 - 12. NATIONAL CONCRETE MASONRY ASSOCIATION (NCMA)
 - 13. BRICK INDUSTRY ASSOCIATION (BIA)
 - 14. AMERICAN WELDING SOCIETY (AWS)
 - 15. NATIONAL ROOFING CONTRACTORS ASSOCIATION (NRCA)
 - 16. SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)
 - 17. DOOR AND HARDWARE INSTITUTE (DHI)
 - 18. OCCUPATIONAL SAFETY AND HEALTH ACT (OSHA)
 - 19. APPLICABLE BUILDING CODES INCLUDING UNIFORM BUILDING CODE, SOUTHERN BUILDING CODE, BOCA, AND THE INTERNATIONAL BUILDING CODE.
- 1.5 DEFINITIONS:
 - A. WORK: THE SUM OF TASKS AND RESPONSIBILITIES IDENTIFIED IN THE CONTRACT DOCUMENTS.
 - B. COMPANY: SPRINT CORPORATION
 - C. ENGINEER: SYNONYMOUS WITH ARCHITECT & ENGINEER AND "A&E". THE DESIGN PROFESSIONAL HAVING PROFESSIONAL RESPONSIBILITY FOR DESIGN OF THE PROJECT.
 - D. CONTRACTOR: CONSTRUCTION CONTRACTOR; CONSTRUCTION VENDOR; INDIVIDUAL OR ENTITY WHO AFTER EXECUTION OF A CONTRACT IS BOUND TO ACCOMPLISH THE WORK.
 - E. THIRD PARTY VENDOR OR AGENCY: A VENDOR OR AGENCY ENGAGED SEPARATELY BY THE COMPANY, A&E, OR CONTRACTOR TO PROVIDE MATERIALS OR TO ACCOMPLISH SPECIFIC TASKS RELATED TO BUT NOT INCLUDED IN THE WORK.
 - F. OFCI: OWNER FURNISHED, CONTRACTOR INSTALLED EQUIPMENT.
 - G. CONSTRUCTION MANAGER – ALL PROJECTS RELATED COMMUNICATION TO FLOW THROUGH SPRINT REPRESENTATIVE IN CHARGE OF PROJECT...

- 1.6 SITE FAMILIARITY: CONTRACTOR SHALL BE RESPONSIBLE FOR FAMILIARIZING HIMSELF WITH ALL CONTRACT DOCUMENTS, FIELD CONDITIONS AND DIMENSIONS PRIOR TO PROCEEDING WITH CONSTRUCTION. ANY DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE SPRINT CONSTRUCTION MANAGER PRIOR TO THE COMMENCEMENT OF WORK. NO COMPENSATION WILL BE AWARDED BASED ON CLAIM OF LACK OF KNOWLEDGE OR FIELD CONDITIONS.
- 1.7 POINT OF CONTACT: COMMUNICATION BETWEEN SPRINT AND THE CONTRACTOR SHALL FLOW THROUGH THE SINGLE SPRINT CONSTRUCTION MANAGER APPOINTED TO MANAGE THE PROJECT FOR SPRINT.
- 1.8 ON-SITE SUPERVISION: THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK AND SHALL BE RESPONSIBLE FOR CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES IN ACCORDANCE WITH THE CONTRACT DOCUMENTS. THE CONTRACTOR SHALL EMPLOY A COMPETENT SUPERINTENDENT WHO SHALL BE IN ATTENDANCE AT THE SITE AT ALL TIMES DURING PERFORMANCE OF THE WORK.
- 1.9 DRAWINGS, SPECIFICATIONS AND DETAILS REQUIRED AT JOBSITE: THE CONSTRUCTION CONTRACTOR SHALL MAINTAIN A FULL SET OF THE CONSTRUCTION DRAWINGS, STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES AND THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES AT THE JOBSITE FROM MOBILIZATION THROUGH CONSTRUCTION COMPLETION.
 - A. THE JOBSITE DRAWINGS, SPECIFICATIONS AND DETAILS SHALL BE CLEARLY MARKED DAILY IN RED PENCIL WITH ANY CHANGES IN CONSTRUCTION OVER WHAT IS DEPICTED IN THE DOCUMENTS. AT CONSTRUCTION COMPLETION, THIS JOBSITE MARKUP SET SHALL BE DELIVERED TO THE COMPANY OR COMPANY'S DESIGNATED REPRESENTATIVE TO BE FORWARDED TO THE COMPANY'S A&E VENDOR FOR PRODUCTION OF "AS-BUILT" DRAWINGS.
 - B. DETAILS ARE INTENDED TO SHOW DESIGN INTENT. MODIFICATIONS MAY BE REQUIRED TO SUIT JOB DIMENSIONS OR CONDITIONS, AND SUCH MODIFICATIONS SHALL BE INCLUDED AS PART OF THE WORK. CONTRACTOR SHALL NOTIFY SPRINT CONSTRUCTION MANAGER OF ANY VARIATIONS PRIOR TO PROCEEDING WITH THE WORK.
 - C. DIMENSIONS SHOWN ARE TO FINISH SURFACES UNLESS NOTED OTHERWISE. SPACING BETWEEN EQUIPMENT IS THE REQUIRED CLEARANCE. SHOULD THERE BE ANY QUESTIONS REGARDING THE CONTRACT DOCUMENTS, EXISTING CONDITIONS AND/OR DESIGN INTENT, THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING A CLARIFICATION FROM THE SPRINT CONSTRUCTION MANAGER PRIOR TO PROCEEDING WITH THE WORK.
- 1.10 USE OF JOB SITE: THE CONTRACTOR SHALL CONFINE ALL CONSTRUCTION AND RELATED OPERATIONS INCLUDING STAGING AND STORAGE OF MATERIALS AND EQUIPMENT, PARKING, TEMPORARY FACILITIES, AND WASTE STORAGE TO THE LEASE PARCEL UNLESS OTHERWISE PERMITTED BY THE CONTRACT DOCUMENTS.
- 1.11 UTILITIES SERVICES: WHERE NECESSARY TO CUT EXISTING PIPES, ELECTRICAL WIRES, CONDUITS, CABLES, ETC., OF UTILITY SERVICES, OR OF FIRE PROTECTION OR COMMUNICATIONS SYSTEMS, THEY SHALL BE CUT AND CAPPED AT SUITABLE PLACES OR WHERE SHOWN. ALL SUCH ACTIONS SHALL BE COORDINATED WITH THE UTILITY COMPANY INVOLVED:
- 1.12 PERMITS / FEES: WHEN REQUIRED THAT A PERMIT OR CONNECTION FEE BE PAID TO A PUBLIC UTILITY PROVIDER FOR NEW SERVICE TO THE CONSTRUCTION PROJECT, PAYMENT OF SUCH FEE SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.
- 1.13 CONTRACTOR SHALL TAKE ALL MEASURES AND PROVIDE ALL MATERIAL NECESSARY FOR PROTECTING EXISTING EQUIPMENT AND PROPERTY.
- 1.14 METHODS OF PROCEDURE (MOPS) FOR CONSTRUCTION: CONTRACTOR SHALL PERFORM WORK AS DESCRIBED IN THE FOLLOWING INSTALLATION AND COMMISSIONING MOPS.

NOTE: IN SHORT-FORM SPECIFICATIONS ON THE DRAWINGS, A/E TO INSERT LIST OF APPLICABLE MOPS INCLUDING EN-2012-001, EN-2013-002, EL-0568, AND TS-0193
- 1.15 USE OF ELECTRONIC PROJECT MANAGEMENT SYSTEMS:

PART 2 – PRODUCTS (NOT USED)

PART 3 – EXECUTION

- 3.1 TEMPORARY UTILITIES AND FACILITIES: THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL TEMPORARY UTILITIES AND FACILITIES NECESSARY EXCEPT AS OTHERWISE INDICATED IN THE CONSTRUCTION DOCUMENTS. TEMPORARY UTILITIES AND FACILITIES INCLUDE POTABLE WATER, HEAT, HVAC, ELECTRICITY, SANITARY FACILITIES, WASTE DISPOSAL FACILITIES, AND TELEPHONE/COMMUNICATION SERVICES. PROVIDE TEMPORARY UTILITIES AND FACILITIES IN ACCORDANCE WITH OSHA AND THE AUTHORITY HAVING JURISDICTION. CONTRACTOR MAY UTILIZE THE COMPANY ELECTRICAL SERVICE IN THE COMPLETION OF THE WORK WHEN IT BECOMES AVAILABLE. USE OF THE LESSORS OR SITE OWNER'S UTILITIES OR FACILITIES IS EXPRESSLY FORBIDDEN EXCEPT AS OTHERWISE ALLOWED IN THE CONTRACT DOCUMENTS.
- 3.2 ACCESS TO WORK: THE CONTRACTOR SHALL PROVIDE ACCESS TO THE JOB SITE FOR AUTHORIZED COMPANY PERSONNEL AND AUTHORIZED REPRESENTATIVES OF THE ARCHITECT/ENGINEER DURING ALL PHASES OF THE WORK.
- 3.3 TESTING: REQUIREMENTS FOR TESTING BY THIS CONTRACTOR SHALL BE AS INDICATED HEREWITH, ON THE CONSTRUCTION DRAWINGS, AND IN THE INDIVIDUAL SECTIONS OF THESE SPECIFICATIONS. SHOULD COMPANY CHOOSE TO ENGAGE ANY THIRD-PARTY TO CONDUCT ADDITIONAL TESTING, THE CONTRACTOR SHALL COOPERATE WITH AND PROVIDE A WORK AREA FOR COMPANY'S TEST AGENCY.
- 3.4 DIMENSIONS: VERIFY DIMENSIONS INDICATED ON DRAWINGS WITH FIELD DIMENSIONS BEFORE FABRICATION OR ORDERING OF MATERIALS. DO NOT SCALE DRAWINGS.

- 3.5 EXISTING CONDITIONS: NOTIFY THE SPRINT CONSTRUCTION MANAGER OF EXISTING CONDITIONS DIFFERING FROM THOSE INDICATED ON THE DRAWINGS. DO NOT REMOVE OR ALTER STRUCTURAL COMPONENTS WITHOUT PRIOR WRITTEN APPROVAL FROM THE ARCHITECT AND ENGINEER.

SECTION 01 200 – COMPANY FURNISHED MATERIAL AND EQUIPMENT

PART 1 – GENERAL

- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
 - A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
 - B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.

PART 2 – PRODUCTS (NOT USED)

PART 3 – EXECUTION

- 3.1 RECEIPT OF MATERIAL AND EQUIPMENT:
 - A. A COMPANY FURNISHED MATERIAL AND EQUIPMENT IS IDENTIFIED ON THE RF DATA SHEET IN THE CONSTRUCTION DOCUMENTS.
 - B. THE CONTRACTOR IS RESPONSIBLE FOR SPRINT PROVIDED MATERIAL AND EQUIPMENT AND UPON RECEIPT SHALL:
 - 1. ACCEPT DELIVERIES AS SHIPPED AND TAKE RECEIPT.
 - 2. VERIFY COMPLETENESS AND CONDITION OF ALL DELIVERIES.
 - 3. TAKE RESPONSIBILITY FOR EQUIPMENT AND PROVIDE INSURANCE PROTECTION AS REQUIRED IN AGREEMENT.
 - 4. RECORD ANY DEFECTS OR DAMAGES AND WITHIN TWENTY-FOUR HOURS AFTER RECEIPT, REPORT TO SPRINT OR ITS DESIGNATED PROJECT REPRESENTATIVE OF SUCH.
 - 5. PROVIDE SECURE AND NECESSARY WEATHER PROTECTED WAREHOUSING.
 - 6. COORDINATE SAFE AND SECURE TRANSPORTATION OF MATERIAL AND EQUIPMENT, DELIVERING AND OFF-LOADING FROM CONTRACTOR'S WAREHOUSE TO SITE.
- 3.2 DELIVERABLES:
 - A. COMPLETE SHIPPING AND RECEIPT DOCUMENTATION IN ACCORDANCE WITH COMPANY PRACTICE.
 - B. IF APPLICABLE, COMPLETE LOST/STOLEN/DAMAGED DOCUMENTATION REPORT AS NECESSARY IN ACCORDANCE WITH COMPANY PRACTICE, AND AS DIRECTED BY COMPANY.
 - C. UPLOAD DOCUMENTATION INTO SPRINT SITE MANAGEMENT SYSTEM (SMS) AND/OR PROVIDE HARD COPY DOCUMENTATION AS REQUESTED.

SECTION 01 300 – CELL SITE CONSTRUCTION CO.

PART 1 – GENERAL

- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
 - A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
 - B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.
- 1.3 NOTICE TO PROCEED
 - A. NO WORK SHALL COMMENCE PRIOR TO COMPANY'S WRITTEN NOTICE TO PROCEED AND THE ISSUANCE OF THE WORK ORDER.
 - B. UPON RECEIVING NOTICE TO PROCEED, CONTRACTOR SHALL FULLY PERFORM ALL WORK NECESSARY TO PROVIDE SPRINT WITH AN OPERATIONAL WIRELESS FACILITY.

PART 2 – PRODUCTS (NOT USED)

PART 3 – EXECUTION

- 3.1 FUNCTIONAL REQUIREMENTS:
 - A. THE ACTIVITIES DESCRIBED IN THIS PARAGRAPH REPRESENT MINIMUM ACTIONS AND PROCESSES REQUIRED TO SUCCESSFULLY COMPLETE THE WORK. THE ACTIVITIES DESCRIBED ARE NOT EXHAUSTIVE, AND CONTRACTOR SHALL TAKE ANY AND ALL ACTIONS AS NECESSARY TO SUCCESSFULLY COMPLETE THE CONSTRUCTION OF A FULLY FUNCTIONING WIRELESS FACILITY AT THE SITE IN ACCORDANCE WITH COMPANY PROCESSES.
 - B. SUBMIT SPECIFIC DOCUMENTATION AS INDICATED HEREIN, AND OBTAIN REQUIRED APPROVALS WHILE THE WORK IS BEING PERFORMED.
 - C. MANAGE AND CONDUCT ALL FIELD CONSTRUCTION SERVICE RELATED ACTIVITIES
 - D. PROVIDE CONSTRUCTION ACTIVITIES TO THE EXTENT REQUIRED BY THE CONTRACT DOCUMENTS, INCLUDING BUT NOT LIMITED TO THE FOLLOWING:

PLANS PREPARED FOR:



PLANS PREPARED BY:




INFINIGY ENGINEERING, PLLC
1033 Watervliet Shaker Rd
Albany, NY 12205
Office # (518) 690-0790
Fax # (518) 690-0793
JOB NUMBER 526-104

PROJECT MANAGER:



32 CLINTON ST.
SARATOGA SPRINGS, NY 12866
OFFICE#, (518) 306-3740

ENGINEERING LICENSE:



03/13/2019

DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

| DESCRIPTION | DATE | BY | REV. |
|-------------------|----------|-----|------|
| | | | |
| | | | |
| | | | |
| ISSUED FOR PERMIT | 02/22/19 | MAP | 0 |

SITE NAME:

STTN - SOUTHINGTON

SITE NUMBER:

CT52XC108

SITE ADDRESS:

80 SHUTTLE MEADOW ROAD
SOUTHINGTON, CT 06489

SHEET DESCRIPTION:

SPRINT SPECIFICATIONS

SHEET NUMBER:

SP-1

CONTINUE FROM SP-1

1. PERFORM ANY REQUIRED SITE ENVIRONMENTAL MITIGATION.
2. PREPARE GROUND SITES; PROVIDE DE-GRUBBING; AND ROUGH AND FINAL GRADING, AND COMPOUND SURFACE TREATMENTS.
3. MANAGE AND CONDUCT ALL ACTIVITIES FOR INSTALLATION OF UTILITIES INCLUDING ELECTRICAL AND TELCO BACKHAUL.
4. INSTALL UNDERGROUND FACILITIES INCLUDING UNDERGROUND POWER AND COMMUNICATIONS CONDUITS, AND UNDERGROUND GROUNDING SYSTEM.
5. INSTALL ABOVE GROUND GROUNDING SYSTEMS.
6. PROVIDE NEW HVAC INSTALLATIONS AND MODIFICATIONS.
7. INSTALL "H-FRAMES", CABINETS AND SHELTERS AS INDICATED.
8. INSTALL ROADS, ACCESS WAYS, CURBS AND DRAINS AS INDICATED.
9. ACCOMPLISH REQUIRED MODIFICATION OF EXISTING FACILITIES.
10. PROVIDE ANTENNA SUPPORT STRUCTURE FOUNDATIONS.
11. PROVIDE SLABS AND EQUIPMENT PLATFORMS.
12. INSTALL COMPOUND FENCING, SIGHT SHIELDING, LANDSCAPING AND ACCESS BARRIERS.
13. PERFORM INSPECTION AND MATERIAL TESTING AS REQUIRED HEREINAFTER.
14. CONDUCT SITE RESISTANCE TO EARTH TESTING AS REQUIRED HEREINAFTER
15. INSTALL FIXED GENERATOR SETS AND OTHER STANDBY POWER SOLUTIONS.
16. INSTALL TOWERS, ANTENNA SUPPORT STRUCTURES AND PLATFORMS ON EXISTING TOWERS AS REQUIRED.
17. INSTALL CELL SITE RADIOS, MICROWAVE, GPS, COAXIAL MAINLINE, ANTENNAS, CROSS BAND COUPLERS, TOWER TOP AMPLIFIERS, LOW NOISE AMPLIFIERS AND RELATED EQUIPMENT.
18. PERFORM, DOCUMENT, AND CLOSE OUT ANY CONSTRUCTION CONTROL DOCUMENTS THAT MAY BE REQUIRED BY GOVERNMENT AGENCIES AND LANDLORDS.
19. PERFORM ANTENNA AND COAX SWEEP TESTING AND MAKE ANY AND ALL NECESSARY CORRECTIONS.
20. REMAIN ON SITE MOBILIZED THROUGHOUT HAND-OFF AND INTEGRATION TO ASSIST AS NEEDED UNTIL SITE IS DEEMED SUBSTANTIALLY COMPLETE AND PLACED "ON AIR."

3.2 GENERAL REQUIREMENTS FOR CIVIL CONSTRUCTION:

- A. CONTRACTOR SHALL KEEP THE SITE FREE FROM ACCUMULATING WASTE MATERIAL, DEBRIS, AND TRASH. AT THE COMPLETION OF THE WORK, CONTRACTOR SHALL REMOVE FROM THE SITE ALL REMAINING RUBBISH, IMPLEMENTS, TEMPORARY FACILITIES, AND SURPLUS MATERIALS.
- B. EQUIPMENT ROOMS SHALL AT ALL TIMES BE MAINTAINED "BROOM CLEAN" AND CLEAR OF DEBRIS.
- C. CONTRACTOR SHALL TAKE ALL REASONABLE PRECAUTIONS TO DISCOVER AND LOCATE ANY HAZARDOUS CONDITION.
 1. IN THE EVENT CONTRACTOR ENCOUNTERS ANY HAZARDOUS CONDITION WHICH HAS NOT BEEN ABATED OR OTHERWISE MITIGATED, CONTRACTOR AND ALL OTHER PERSONS SHALL IMMEDIATELY STOP WORK IN THE AFFECTED AREA AND NOTIFY COMPANY IN WRITING. THE WORK IN THE AFFECTED AREA SHALL NOT BE RESUMED EXCEPT BY WRITTEN NOTIFICATION BY COMPANY.
 2. CONTRACTOR AGREES TO USE CARE WHILE ON THE SITE AND SHALL NOT TAKE ANY ACTION THAT WILL OR MAY RESULT IN OR CAUSE THE HAZARDOUS CONDITION TO BE FURTHER RELEASED IN THE ENVIRONMENT, OR TO FURTHER EXPOSE INDIVIDUALS TO THE HAZARD.

D. CONTRACTOR'S ACTIVITIES SHALL BE RESTRICTED TO THE PROJECT LIMITS. SHOULD AREAS OUTSIDE THE PROJECT LIMITS BE AFFECTED BY CONTRACTOR'S ACTIVITIES, CONTRACTOR SHALL IMMEDIATELY RETURN THEM TO ORIGINAL CONDITION

E. CONDUCT TESTING AS REQUIRED HEREIN.

3.3 DELIVERABLES:

- A. CONTRACTOR SHALL REVIEW, APPROVE, AND SUBMIT TO SPRINT SHOP DRAWINGS, PRODUCT DATA, SAMPLES, AND SIMILAR SUBMITTALS AS REQUIRED HEREINAFTER
- B. PROVIDE DOCUMENTATION INCLUDING, BUT NOT LIMITED TO, THE FOLLOWING. DOCUMENTATION SHALL BE FORWARDED IN ORIGINAL FORMAT AND/OR UPLOADED INTO SMS.
 1. ALL CORRESPONDENCE AND PRELIMINARY CONSTRUCTION REPORTS.
 2. PROJECT PROGRESS REPORTS.
 3. CIVIL CONSTRUCTION START DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
 4. ELECTRICAL SERVICE COMPLETION DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).

5. LINES AND ANTENNA INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
6. POWER INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
7. TELCO READY DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
8. PPC (OR SHELTER) INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
9. TOWER CONSTRUCTION START DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
10. TOWER CONSTRUCTION COMPLETE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
11. BTS AND RADIO EQUIPMENT DELIVERED AT SITE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
12. NETWORK OPERATIONS HANDOFF CHECKLIST (HOC WALK) COMPLETE (UPLOAD FORM IN SMS)
13. CIVIL CONSTRUCTION COMPLETE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
14. SITE CONSTRUCTION PROGRESS PHOTOS UNLOADED INTO SMS.

SECTION 01 400 - SUBMITTALS & TESTS

PART 1 - GENERAL

1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

1.2 RELATED DOCUMENTS:

- A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
- B. SPRINT STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HERewith.

1.3 SUBMITTALS:

- A. THE WORK IN ALL ASPECTS SHALL COMPLY WITH THE CONSTRUCTION DRAWINGS AND THESE SPECIFICATIONS.
- B. SUBMIT THE FOLLOWING TO COMPANY REPRESENTATIVE FOR APPROVAL.
 1. CONCRETE MIX-DESIGNS FOR TOWER FOUNDATIONS, ANCHORS PIERS, AND CONCRETE PAVING.
 2. CONCRETE BREAK TESTS AS SPECIFIED HEREIN.
 3. SPECIAL FINISHES FOR INTERIOR SPACES, IF ANY.
 4. ALL EQUIPMENT AND MATERIALS SO IDENTIFIED ON THE CONSTRUCTION DRAWINGS.
 5. CHEMICAL GROUNDING DESIGN
- D. ALTERNATES: AT THE COMPANY'S REQUEST, ANY ALTERNATIVES TO THE MATERIALS OR METHODS SPECIFIED SHALL BE SUBMITTED TO SPRINT'S CONSTRUCTION MANAGER FOR APPROVAL PRIOR TO BEING SHIPPED TO SITE. SPRINT WILL REVIEW AND APPROVE ONLY THOSE REQUESTS MADE IN WRITING. NO VERBAL APPROVALS WILL BE CONSIDERED. SUBMITTAL FOR APPROVAL SHALL INCLUDE A STATEMENT OF COST REDUCTION PROPOSED FOR USE OF ALTERNATE PRODUCT.

1.4 TESTS AND INSPECTIONS:

- A. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CONSTRUCTION TESTS, INSPECTIONS AND PROJECT DOCUMENTATION.
- B. CONTRACTOR SHALL ACCOMPLISH TESTING INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
 1. COAX SWEEPS AND FIBER TESTS PER TS-0200 REV 4 ANTENNA LINE ACCEPTANCE STANDARDS.
 2. AGL, AZIMUTH AND DOWNTILT USING ELECTRONIC COMMERCIAL MADE-FOR-THE-PURPOSE ANTENNA ALIGNMENT TOOL.
 3. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN SITE INSPECTION ACTIVITIES AND/OR AS A RESULT OF TESTING.
- C. REQUIRED CLOSEOUT DOCUMENTATION INCLUDES, BUT IS NOT LIMITED TO THE FOLLOWING:
 1. AZIMUTH, DOWNTILT, AGL - UPLOAD REPORT FROM ANTENNA ALIGNMENT TOOL TO SITERRA TASK 465. INSTALLED AZIMUTH, DOWNTILT, AND AGL MUST CONFORM TO THE RF DATA SHEETS. SWEEP AND FIBER TESTS
 2. SCANABLE BARCODE PHOTOGRAPHS OF TOWER TOP AND INACCESSIBLE EQUIPMENT
 3. ALL AVAILABLE JURISDICTIONAL INFORMATION
 4. PDF SCAN OF REDLINES PRODUCED IN FIELD

5. ELECTRONIC AS-BUILT DRAWINGS IN AUTOCAD AND PDF FORMATS. ANY FIELD CHANGE MUST BE REFLECTED BY MODIFYING THE PLANS, ELEVATIONS, AND DETAILS IN THE DRAWING SETS. GENERAL NOTES INDICATING MODIFICATIONS WILL NOT BE ACCEPTED. CHANGES SHALL BE HIGHLIGHTED AS "CLOUDS" IDENTIFIED AS THE "AS-BUILT" CONDITION.
6. LIEN WAIVERS
7. FINAL PAYMENT APPLICATION
8. REQUIRED FINAL CONSTRUCTION PHOTOS
9. CONSTRUCTION AND COMMISSIONING CHECKLIST COMPLETE WITH NO DEFICIENT ITEMS
10. ALL POST NTP TASKS INCLUDING DOCUMENT UPLOADS COMPLETED IN SITERRA (SPRINTS DOCUMENT REPOSITORY OF RECORD).

1.5 COMMISSIONING: PERFORM ALL COMMISSIONING AS REQUIRED BY APPLICABLE MOPs

1.6 INTEGRATION: PERFORM ALL INTEGRATION ACTIVITIES AS REQUIRED BY APPLICABLE MOPs

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION

3.1 REQUIREMENTS FOR TESTING:

A. THIRD PARTY TESTING AGENCY:

1. WHEN THE USE OF A THIRD PARTY INDEPENDENT TESTING AGENCY IS REQUIRED, THE AGENCY THAT IS SELECTED MUST PERFORM SUCH WORK ON A REGULAR BASIS IN THE STATE WHERE THE PROJECT IS LOCATED AND HAVE A THOROUGH UNDERSTANDING OF LOCAL AVAILABLE MATERIALS, INCLUDING THE SOIL, ROCK, AND GROUNDWATER CONDITIONS.
2. THE THIRD PARTY TESTING AGENCY IS TO BE FAMILIAR WITH THE APPLICABLE REQUIREMENTS FOR THE TESTS TO BE DONE, EQUIPMENT TO BE USED, AND ASSOCIATED HEALTH AND SAFETY ISSUES.
3. EXPERIENCE IN SOILS, CONCRETE, MASONRY, AGGREGATE, AND ASPHALT TESTING USING ASTM, AASJTO, AND OTHER METHODS IS NEEDED.
4. EXPERIENCE IN SOILS, CONCRETE, MASONRY, AGGREGATE, AND ASPHALT TESTING USING ASTM, AASJTO, AND OTHER METHODS IS NEEDED.

3.2 REQUIRED TESTS:

- A. CONTRACTOR SHALL ACCOMPLISH TESTING INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
 1. CONCRETE CYLINDER BREAK TESTS FOR THE TOWER AND ANCHOR FOUNDATIONS AS SPECIFIED IN SECTION: PORTLAND CEMENT CONCRETE PAVING.
 2. ASPHALT ROADWAY COMPACTED THICKNESS, SURFACE SMOOTHNESS, AND COMPACTED DENSITY TESTING AS SPECIFIED IN SECTION: HOT MIX ASPHALT PAVING.
 3. FIELD QUALITY CONTROL TESTING AS SPECIFIED IN SECTION: PORTLAND CEMENT CONCRETE PAVING.
 4. TESTING REQUIRED UNDER SECTION: AGGREGATE BASE FOR ACCESS ROADS, PADS AND ANCHOR LOCATIONS
 5. STRUCTURAL BACKFILL COMPACTION TESTS FOR THE TOWER FOUNDATION.
 6. SITE RESISTANCE TO EARTH TESTING PER EXHIBIT: CELL SITE GROUNDING SYSTEM DESIGN.
 7. ANTENNA AND COAX SWEEP TESTS PER EXHIBIT: ANTENNA TRANSMISSION LINE ACCEPTANCE STANDARDS.
 8. GROUNDING AT ANTENNA MASTS FOR GPS AND ANTENNAS
 9. ALL OTHER TESTS REQUIRED BY COMPANY OR JURISDICTION.

3.3 REQUIRED INSPECTIONS

- A. SCHEDULE INSPECTIONS WITH COMPANY REPRESENTATIVE.
- B. CONDUCT INSPECTIONS INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
 1. GROUNDING SYSTEM INSTALLATION PRIOR TO EARTH CONCEALMENT DOCUMENTED WITH DIGITAL PHOTOGRAPHS BY CONTRACTOR, APPROVED BY A&E OR SPRINT REPRESENTATIVE.
 2. FORMING FOR CONCRETE AND REBAR PLACEMENT PRIOR TO POUR DOCUMENTED WITH DIGITAL PHOTOGRAPHS BY CONTRACTOR, APPROVED BY A&E OR SPRINT REPRESENTATIVE.
 3. COMPACTION OF BACKFILL MATERIALS; AGGREGATE BASE FOR ROADS, PADS, AND ANCHORS; ASPHALT PAVING; AND SHAFT BACKFILL FOR CONCRETE AND WOOD POLES, BY INDEPENDENT THIRD PARTY AGENCY.
 4. PRE- AND POST-CONSTRUCTION ROOFTOP AND STRUCTURAL INSPECTIONS ON EXISTING FACILITIES.
 5. TOWER ERECTION SECTION STACKING AND PLATFORM ATTACHMENT DOCUMENTED BY DIGITAL PHOTOGRAPHS BY THIRD PARTY AGENCY.
 6. ANTENNA AZIMUTH, DOWN TILT AND PER SUNLIGHT TOOL SUNSIGHT INSTRUMENTS - ANTENNA ALIGNMENT TOOL (AAT)

PLANS PREPARED FOR:



PLANS PREPARED BY:




INFINIGY ENGINEERING, PLLC
1033 Watervliet Shaker Rd
Albany, NY 12205
Office # (518) 690-0790
Fax # (518) 690-0793
JOB NUMBER 526-104

PROJECT MANAGER:



32 CLINTON ST.
SARATOGA SPRINGS, NY 12866
OFFICE#, (518) 306-3740

ENGINEERING LICENSE:



DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

| DESCRIPTION | DATE | BY | REV. |
|-------------------|----------|-----|------|
| ISSUED FOR PERMIT | 02/22/19 | MAP | 0 |

SITE NAME:

STTN - SOUTHINGTON

SITE NUMBER:

CT52XC108

SITE ADDRESS:

80 SHUTTLE MEADOW ROAD
SOUTHINGTON, CT 06489

SHEET DESCRIPTION:

SPRINT SPECIFICATIONS

SHEET NUMBER:

SP-2

CONTINUE FROM SP-2

- 7. VERIFICATION DOCUMENTED WITH THE ANTENNA CHECKLIST REPORT, BY A&E, SITE DEVELOPMENT REP, OR RF REP.
 - 8. FINAL INSPECTION CHECKLIST AND HANDOFF WALK (HOC). SIGNED FORM SHOWING ACCEPTANCE BY FIELD OPS IS TO BE UPLOADED INTO SMS.
 - 9. COAX SWEEP AND FIBER TESTING DOCUMENTS SUBMITTED VIA SMS FOR RF APPROVAL.
 - 10. SCAN-ABLE BARCODE PHOTOGRAPHS OF TOWER TOP AND INACCESSIBLE SERIALIZED EQUIPMENT
 - 11. ALL AVAILABLE JURISDICTIONAL INFORMATION
 - 12. PDF SCAN OF REDLINES PRODUCED IN FIELD
 - C. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN SITE INSPECTION ACTIVITIES AND/OR AS A RESULT OF TESTING.
 - D. CONSTRUCTION INSPECTIONS AND CORRECTIVE MEASURES SHALL BE DOCUMENTED BY THE CONTRACTOR WITH WRITTEN REPORTS AND PHOTOGRAPHS. PHOTOGRAPHS MUST BE DIGITAL AND OF SUFFICIENT QUALITY TO CLEARLY SHOW THE SITE CONSTRUCTION. PHOTOGRAPHS MUST CLEARLY IDENTIFY THE PHOTOGRAPHED ITEM AND BE LABELED WITH THE SITE CASCADE NUMBER, SITE NAME, DESCRIPTION, AND DATE.
- 3.4 DELIVERABLES: TEST AND INSPECTION REPORTS AND CLOSEOUT DOCUMENTATION SHALL BE UPLOADED TO THE SMS AND/OR FORWARDED TO SPRINT FOR INCLUSION INTO THE PERMANENT SITE FILES.
- A. THE FOLLOWING TEST AND INSPECTION REPORTS SHALL BE PROVIDED AS APPLICABLE.
 - 1. CONCRETE MIX AND CYLINDER BREAK REPORTS.
 - 2. STRUCTURAL BACKFILL COMPACTION REPORTS.
 - 3. SITE RESISTANCE TO EARTH TEST.
 - 4. ANTENNA AZIMUTH AND DOWN TILT VERIFICATION
 - 5. TOWER ERECTION INSPECTIONS AND MEASUREMENTS DOCUMENTING TOWER INSTALLED PER SUPPLIER'S REQUIREMENTS AND THE APPLICABLE SECTIONS HEREIN.
 - 6. COAX CABLE SWEEP TESTS PER COMPANY'S "ANTENNA LINE ACCEPTANCE STANDARDS".
 - B. REQUIRED CLOSEOUT DOCUMENTATION INCLUDES THE FOLLOWING;
 - 1. TEST WELLS AND TRENCHES: PHOTOGRAPHS OF ALL TEST WELLS; PHOTOGRAPHS SHOWING ALL OPEN EXCAVATIONS AND TRENCHING PRIOR TO BACKFILLING SHOWING A TAPE MEASURE VISIBLE IN THE EXCAVATIONS INDICATING DEPTH.
 - 2. CONDUITS, CONDUCTORS AND GROUNDING: PHOTOGRAPHS SHOWING TYPICAL INSTALLATION OF CONDUCTORS AND CONNECTORS; PHOTOGRAPHS SHOWING TYPICAL BEND RADIUS OF INSTALLED GROUND WIRES AND GROUND ROD SPACING;
 - 3. CONCRETE FORMS AND REINFORCING: CONCRETE FORMING AT TOWER AND EQUIPMENT/SHELTER PAD/FOUNDATIONS – PHOTOGRAPHS SHOWING ALL REINFORCING STEEL, UTILITY AND CONDUIT STUB OUTS; PHOTOGRAPHS SHOWING CONCRETE POUR OF SHELTER SLAB/FOUNDATION, TOWER FOUNDATION AND GUY ANCHORS WITH VIBRATOR IN USE; PHOTOGRAPHS SHOWING EACH ANCHOR ON GUYED TOWERS, BEFORE CONCRETE POUR.
 - 4. TOWER, ANTENNAS AND MAINLINE: INSPECTION AND PHOTOGRAPHS OF SECTION STACKING; INSPECTION AND PHOTOGRAPHS OF PLATFORM COMPONENT ATTACHMENT POINTS; PHOTOGRAPHS OF TOWER TOP GROUNDING; PHOTOS OF TOWER COAX LINE COLOR CODING AT THE TOP AND AT GROUND LEVEL; INSPECTION AND PHOTOGRAPHS OF OPERATIONAL OF TOWER LIGHTING, AND PLACEMENT OF FAA REGISTRATION SIGN; PHOTOGRAPHS SHOWING ADDITIONAL GROUNDING POINTS FOR TOWERS GREATER THAN 200 FEET.; PHOTOS OF ANTENNA GROUND BAR, EQUIPMENT GROUND BAR, AND MASTER GROUND BAR; PHOTOS OF GPS ANTENNA(S); PHOTOS OF EACH SECTOR OF ANTENNAS; ONE PHOTOGRAPH LOOKING AT THE SECTOR AND ONE FROM BEHIND SHOWING THE PROJECTED COVERAGE AREA; PHOTOS OF COAX WEATHERPROOFING – TOP AND BOTTOM; PHOTOS OF COAX GROUNDING—TOP AND BOTTOM; PHOTOS OF ANTENNA AND MAST GROUNDING; PHOTOS OF COAX CABLE ENTRY INTO SHELTER; PHOTOS OF PLATFORM MECHANICAL CONNECTIONS TO TOWER/MONOPOLE.
 - 5. ROOF TOPS: PRE-CONSTRUCTION AND POST-CONSTRUCTION VISUAL INSPECTION AND PHOTOGRAPHS OF THE ROOF AND INTERIOR TO DETERMINE AND DOCUMENT CONDITIONS; ROOF TOP CONSTRUCTION INSPECTIONS AS REQUIRED BY THE JURISDICTION; PHOTOGRAPHS OF CABLE TRAY AND/OR ICE BRIDGE; PHOTOGRAPHS OF DOGHOUSE/CABLE EXIT FROM ROOF;
 - 6. SITE LAYOUT – PHOTOGRAPHS OF THE OVERALL COMPOUND, INCLUDING EQUIPMENT PLATFORM FROM ALL FOUR CORNERS.
 - 7. FINISHED UTILITIES: CLOSE-UP PHOTOGRAPHS OF THE PPC BREAKER PANEL; CLOSE-UP PHOTOGRAPH OF THE INSIDE OF THE TELCO PANEL AND NIU; CLOSE-UP PHOTOGRAPH OF THE POWER METER AND DISCONNECT; PHOTOS OF POWER AND TELCO ENTRANCE TO COMPANY ENCLOSURE; PHOTOGRAPHS AT METER BOX AND/OR FACILITY DISTRIBUTION PANEL.
 - 8. REQUIRED MATERIALS CERTIFICATIONS: CONCRETE MIX DESIGNS; MILL CERTIFICATION FOR ALL REINFORCING AND STRUCTURAL STEEL; AND ASPHALT PAVING MIX DESIGN.
 - 9. ANY AND ALL SUBMITTALS BY THE JURISDICTION OR COMPANY.

SECTION 01 400 – SUBMITTALS & TESTS

PART 1 – GENERAL

- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
 - A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
 - B. SPRINT 'STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES' ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.

PART 2 – PRODUCTS (NOT USED)

PART 3 – EXECUTION

- 3.1 WEEKLY REPORTS:
 - A. CONTRACTOR SHALL PROVIDE SPRINT WITH WEEKLY REPORTS SHOWING PROJECT STATUS. THIS STATUS REPORT FORMAT WILL BE PROVIDED TO THE CONTRACTOR BY SPRINT. THE REPORT WILL CONTAIN SITE ID NUMBER, THE MILESTONES FOR EACH SITE, INCLUDING THE BASELINE DATE, ESTIMATED COMPLETION DATE AND ACTUAL COMPLETION DATE.
 - B. REPORT INFORMATION WILL BE TRANSMITTED TO SPRINT VIA ELECTRONIC MEANS AS REQUIRED. THIS INFORMATION WILL PROVIDE A BASIS FOR PROGRESS MONITORING AND PAYMENT.
- 3.2 PROJECT CONFERENCE CALLS:
 - A. SPRINT MAY HOLD WEEKLY PROJECT CONFERENCE CALLS. CONTRACTOR WILL BE REQUIRED TO COMMUNICATE SITE STATUS, MILESTONE COMPLETIONS AND UPCOMING MILESTONE PROJECTIONS, AND ANSWER ANY OTHER SITE STATUS QUESTIONS AS NECESSARY.
- 3.3 PROJECT TRACKING IN SMS:
 - A. CONTRACTOR SHALL PROVIDE SCHEDULE UPDATES AND PROJECTIONS IN THE SMS SYSTEM ON A WEEKLY BASIS.
- 3.4 ADDITIONAL REPORTING:
 - A. ADDITIONAL OR ALTERNATE REPORTING REQUIREMENTS MAY BE ADDED TO THE REPORT AS DETERMINED TO BE REASONABLY NECESSARY BY COMPANY.
- 3.5 PROJECT PHOTOGRAPHS:
 - A. FILE DIGITAL PHOTOGRAPHS OF COMPLETED SITE IN JPEG FORMAT IN THE SMS PHOTO LIBRARY FOR THE RESPECTIVE SITE. PHOTOGRAPHS SHALL BE CLEARLY LABELED WITH SITE NUMBER, NAME AND DESCRIPTION, AND SHALL INCLUDE AT A MINIMUM THE FOLLOWING AS APPLICABLE:
 - 1. SHELTER AND TOWER OVERVIEW.
 - 2. TOWER FOUNDATION(S) – FORMS AND STEEL BEFORE POUR (EACH ANCHOR ON GUYED TOWERS).
 - 3. TOWER FOUNDATION(S) POUR WITH VIBRATOR IN USE (EACH ANCHOR ON GUYED TOWERS).
 - 4. TOWER STEEL AS BEING INSTALLED INTO HOLE (SHOW ANCHOR STEEL ON GUYED TOWERS).
 - 5. PHOTOS OF TOWER SECTION STACKING.
 - 6. CONCRETE TESTING / SAMPLES.
 - 7. PLACING OF ANCHOR BOLTS IN TOWER FOUNDATION.
 - 8. BUILDING/WATER TANK FROM ROAD FOR TENANT IMPROVEMENTS OR COMMENTS.
 - 9. SHELTER FOUNDATION--FORMS AND STEEL BEFORE POURING.
 - 10. SHELTER FOUNDATION POUR WITH VIBRATOR IN USE.
 - 11. COAX CABLE ENTRY INTO SHELTER.
 - 12. PLATFORM MECHANICAL CONNECTIONS TO TOWER/MONOPOLE.
 - 13. ROOFTOP PRE AND POST CONSTRUCTION PHOTOS TO INCLUDE PENETRATIONS AND INTERIOR CEILING.
 - 14. PHOTOS OF TOWER TOP COAX LINE COLOR CODING AND COLOR CODING AT GROUND LEVEL.
 - 15. PHOTOS OF ALL APPROPRIATE COMPANY OR REGULATORY SIGNAGE.
 - 16. PHOTOS OF EQUIPMENT BOLT DOWN INSIDE SHELTER.
 - 17. POWER AND TELCO ENTRANCE TO COMPANY ENCLOSURE AND POWER AND TELCO SUPPLY LOCATIONS INCLUDING METER/DISCONNECT.
 - 18. ELECTRICAL TRENCH(S) WITH ELECTRICAL / CONDUIT BEFORE BACKFILL.
 - 19. ELECTRICAL TRENCH(S) WITH FOIL-BACKED TAPE BEFORE FURTHER BACKFILL.
 - 20. TELCO TRENCH WITH TELEPHONE / CONDUIT BEFORE BACKFILL.
 - 21. TELCO TRENCH WITH FOIL-BACKED TAPE BEFORE FURTHER BACKFILL.
 - 22. SHELTER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADII).
 - 23. TOWER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADII).

- 24. FENCE GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADII).
 - 25. ALL BTS GROUND CONNECTIONS.
 - 26. ALL GROUND TEST WELLS.
 - 27. ANTENNA GROUND BAR AND EQUIPMENT GROUND BAR.
 - 28. ADDITIONAL GROUNDING POINTS ON TOWERS ABOVE 200'.
 - 29. HVAC UNITS INCLUDING CONDENSERS ON SPLIT SYSTEMS.
 - 30. GPS ANTENNAS.
 - 31. CABLE TRAY AND/OR WAVEGUIDE BRIDGE.
 - 32. DOGHOUSE/CABLE EXIT FROM ROOF.
 - 33. EACH SECTOR OF ANTENNAS; ONE PHOTOGRAPH LOOKING AT THE SECTOR AND ONE FROM BEHIND SHOWING THE PROJECTED COVERAGE AREA.
 - 34. MASTER BUS BAR.
 - 35. TELCO BOARD AND NIU.
 - 36. ELECTRICAL DISTRIBUTION WALL.
 - 37. CABLE ENTRY WITH SURGE SUPPRESSION.
 - 38. ENTRANCE TO EQUIPMENT ROOM.
 - 39. COAX WEATHERPROOFING--TOP AND BOTTOM OF TOWER.
 - 40. COAX GROUNDING –TOP AND BOTTOM OF TOWER.
 - 41. ANTENNA AND MAST GROUNDING.
 - 42. LANDSCAPING – WHERE APPLICABLE.
- 3.6 FINAL PROJECT ACCEPTANCE: COMPLETE ALL REQUIRED REPORTING TASKS PER CONTRACT, CONTRACT DOCUMENTS OR THE SPRINT INTEGRATED CONSTRUCTION STANDARDS FOR WIRELESS SITES AND UPLOAD INTO SITERRA.

PLANS PREPARED FOR:



PLANS PREPARED BY:




INFINIGY ENGINEERING, PLLC
1033 Watervliet Shaker Rd
Albany, NY 12205
Office # (518) 690-0790
Fax # (518) 690-0793
JOB NUMBER 526-104

PROJECT MANAGER:



32 CLINTON ST.
SARATOGA SPRINGS, NY 12866
OFFICE#, (518) 306-3740

ENGINEERING LICENSE:



DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

| REVISIONS: | DESCRIPTION | DATE | BY | REV. |
|-------------------|-------------|----------|-----|------|
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| ISSUED FOR PERMIT | | 02/22/19 | MAP | 0 |

SITE NAME:

STTN - SOUTHTON

SITE NUMBER:

CT52XC108

SITE ADDRESS:



80 SHUTTLE MEADOW ROAD
SOUTHTON, CT 06489

SHEET DESCRIPTION:

SPRINT SPECIFICATIONS

SHEET NUMBER:



SP-3



INFORMATION CONTAINED WITHIN DRAWINGS ARE BASED ON PROVIDED INFORMATION AND ARE NOT THE RESULT OF A FIELD SURVEY.

OVERALL SITE PLAN

SCALE: AS NOTED 1



SPRINT EQUIPMENT PLAN

SCALE: AS NOTED 2

PLANS PREPARED FOR:



PLANS PREPARED BY:



INFINIGY ENGINEERING, PLLC
1033 Watervliet Shaker Rd
Albany, NY 12205
Office # (518) 690-0790
Fax # (518) 690-0793
JOB NUMBER 526-104

PROJECT MANAGER:



32 CLINTON ST.
SARATOGA SPRINGS, NY 12866
OFFICE#, (518) 306-3740

ENGINEERING LICENSE:

DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

| DESCRIPTION | DATE | BY | REV. |
|-------------------|----------|-----|------|
| | | | |
| | | | |
| | | | |
| ISSUED FOR PERMIT | 02/22/19 | MAP | 0 |

SITE NAME:

STTN - SOUTHINGTON

SITE NUMBER:

CT52XC108

SITE ADDRESS:

**80 SHUTTLE MEADOW ROAD
SOUTHINGTON, CT 06489**


SHEET DESCRIPTION:

SITE PLAN

SHEET NUMBER:

A-1

NOTE:
SEE DETAIL 2 ON A-3
FOR ANTENNA LAYOUT





NOTE:

- STRUCTURAL ANALYSIS COMPLETED BY AMERICAN TOWER CORPORATION. FOR ADDITIONAL INFORMATION SEE REPORT TITLED: "STRUCTURAL ANALYSIS REPORT, CARRIER SITE NUMBER: CT52XC108," DATED: "JANUARY 4, 2019". ACCORDING TO THE RESULTS OF STRUCTURAL MODIFICATION REPORT, THE STRUCTURE HAS SUFFICIENT CAPACITY TO SUPPORT THE PROPOSED LOADING.
- MOUNT ANALYSIS COMPLETED BY INFINIGY ENGINEERING. FOR ADDITIONAL INFORMATION SEE REPORT TITLED: "MOUNT ANALYSIS REPORT, CARRIER SITE ID: CT52XC108," DATED: "JANUARY 8, 2019". ACCORDING TO THE RESULTS OF MOUNT ANALYSIS, THE STRUCTURE HAS SUFFICIENT CAPACITY TO SUPPORT THE PROPOSED LOADING.

| SECTOR | EXISTING/PROPOSED | ANTENNA MODEL # | VENDOR | AZIMUTH | QTY. | REMAIN/REMOVED | RRH (QTY/MODEL) | CABLE | CABLE LENGTH | RAD CENTER |
|--------|-------------------|------------------|-----------|---------|------|----------------|-----------------------------------|------------------------|--------------|------------|
| ALPHA | PROPOSED | APXVTM14-ALU-120 | RFS | 0° | 1 | - | (2) 800 MHz 2X50W RRH W/ FILTER | SEE SHEET A-5 DETAIL 1 | ±120' AGL | ±120' AGL |
| | PROPOSED | NNVV-65B-R4 | COMMSCOPE | 0° | 1 | - | (1) FZHN FLEXI RRH 8TR 2600 9*20W | SEE SHEET A-5 DETAIL 1 | | |
| | EXISTING | LLPX310R | ARGUS | 30° | 1 | REMOVE | (1) 1900 MHz 4X45 RRH | EXISTING COAX | | |
| BETA | PROPOSED | APXVTM14-ALU-120 | RFS | 120° | 1 | - | (2) 800 MHz 2X50W RRH W/ FILTER | SEE SHEET A-5 DETAIL 1 | ±153* | ±120' AGL |
| | PROPOSED | NNVV-65B-R4 | COMMSCOPE | 120° | 1 | - | (1) FZHN FLEXI RRH 8TR 2600 9*20W | SEE SHEET A-5 DETAIL 1 | | |
| | EXISTING | LLPX310R | ARGUS | 150° | 1 | REMOVE | (1) 1900 MHz 4X45 RRH | EXISTING COAX | | |
| GAMMA | PROPOSED | APXVTM14-ALU-120 | RFS | 240° | 1 | - | (2) 800 MHz 2X50W RRH W/ FILTER | SEE SHEET A-5 DETAIL 1 | ±120' AGL | ±120' AGL |
| | PROPOSED | NNVV-65B-R4 | COMMSCOPE | 240° | 1 | - | (1) FZHN FLEXI RRH 8TR 2600 9*20W | SEE SHEET A-5 DETAIL 1 | | |
| | EXISTING | LLPX310R | ARGUS | 270° | 1 | REMOVE | (1) 1900 MHz 4X45 RRH | EXISTING COAX | | |

PROJECT SCOPE:
REMOVE: (3) PANEL ANTENNAS INSTALL: (6) PANEL ANTENNAS AND (9) RRH'S RELOCATE: (3) EXISTING RRH'S

* PROPOSED CABLE LENGTH WAS DETERMINED USING THE SUM OF THE RAD CENTER OF ANTENNAS, AND DISTANCE FROM EXISTING EQUIPMENT AREA TO TOWER BASE WITH AN ADDITIONAL 20' BUFFER. LENGTH TO BE VERIFIED IN FIELD PRIOR TO ORDERING MATERIALS.



NOTE:
CONCRETE SHALL BE 4,000 PSI AFTER 28 DAY TEST

PLANS PREPARED FOR:

PLANS PREPARED BY:

INFINIGY ENGINEERING, PLLC
1033 Watervliet Shaker Rd
Albany, NY 12205
Office # (518) 690-0790
Fax # (518) 690-0793
JOB NUMBER 526-104

PROJECT MANAGER:

32 CLINTON ST.
SARATOGA SPRINGS, NY 12866
OFFICE#, (518) 306-3740

ENGINEERING LICENSE:

DRAWING NOTICE:
THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

| REVISIONS: | DESCRIPTION | DATE | BY | REV. |
|------------|-------------|------|----|------|
| | | | | |
| | | | | |
| | | | | |
| | | | | |

ISSUED FOR PERMIT: 02/22/19 MAP 0

SITE NAME:
STTN - SOUTHINGTON

SITE NUMBER:
CT52XC108


SITE ADDRESS:
**80 SHUTTLE MEADOW ROAD
SOUTHINGTON, CT 06489**

SHEET DESCRIPTION:
TOWER ELEVATION

SHEET NUMBER:
A-2

TOWER ELEVATION NO SCALE 1

EQUIPMENT CABINET FOUNDATION NO SCALE 4



EXISTING ANTENNA LAYOUT

NO SCALE

1


THE CONFIGURATION PLANS ARE BASED ON PROVIDED INFORMATION AND ARE FOR CONCEPTUAL PURPOSES ONLY. CONTRACTOR TO VERIFY FIELD CONDITIONS PRIOR TO CONSTRUCTION.

INSTALL (1) SPRINT 2.5 GHz RRH MOUNTED BEHIND PROPOSED ANTENNA EACH SECTOR (SEE SHEET A-4 DETAIL 1)

EXISTING CLEARWIRE MICROWAVE DISH TO REMAIN (TYP. OF (1) TOTAL)

INSTALL (1) SITEPRO1 P/N: RMQP-NP (SEE SHEET A-2 DETAIL 3)


NOTE: JUMPERS FROM 2.5 RRH TO THE 2.5 ANTENNA CANNOT EXCEED 15 FEET



FINAL ANTENNA & RRH LAYOUT

NO SCALE

2



TYPICAL 2.5 ANTENNA & RRH MOUNTING DETAILS

NO SCALE


3

NOTE: CONTRACTOR TO POSITION RRH ON MOUNT BEHIND ANTENNA SUCH THAT THE RRH DOES NOT INTERFERE WITH THE EXISTING PLATFORM/T-ARM MOUNTING HARDWARE.

NOTE: THE DIAGRAM IS FOR CONCEPTUAL PURPOSES ONLY. CONTRACTOR IS TO REFER TO PASSING STRUCTURAL ANALYSIS FOR ANTENNA AND RRH MOUNTING DETAILS.

NOTES:

1. CUT DC CONDUCTORS TO LENGTH.
2. COIL FIBER CABLE AND SECURE AT SIDE OF RRH.
3. DO NOT EXCEED BEND RADIUS.



TYPICAL DUAL BAND ANTENNA & RRH MOUNTING DETAILS

NO SCALE

4

NOTE: CONTRACTOR TO POSITION RRH ON MOUNT BEHIND ANTENNA SUCH THAT THE RRH DOES NOT INTERFERE WITH THE EXISTING PLATFORM/T-ARM MOUNTING HARDWARE.

NOTE: THE DIAGRAM IS FOR CONCEPTUAL PURPOSES ONLY. CONTRACTOR IS TO REFER TO PASSING STRUCTURAL ANALYSIS FOR ANTENNA AND RRH MOUNTING DETAILS.

NOTES:

1. CUT DC CONDUCTORS TO LENGTH.
2. COIL FIBER CABLE AND SECURE AT SIDE OF RRH.
3. DO NOT EXCEED BEND RADIUS.

PLANS PREPARED FOR:

PLANS PREPARED BY:

INFINIGY ENGINEERING, PLLC
1033 Watervliet Shaker Rd
Albany, NY 12205
Office # (518) 690-0790
Fax # (518) 690-0793
JOB NUMBER 526-104

PROJECT MANAGER:

32 CLINTON ST.
SARATOGA SPRINGS, NY 12866
OFFICE#, (518) 306-3740

ENGINEERING LICENSE:

DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

| DESCRIPTION | DATE | BY | REV. |
|-------------------|----------|-----|------|
| ISSUED FOR PERMIT | 02/22/19 | MAP | 0 |

SITE NAME:
STTN - SOUTHINGTON


SITE NUMBER:
CT52XC108

SITE ADDRESS:
80 SHUTTLE MEADOW ROAD
SOUTHINGTON, CT 06489

SHEET DESCRIPTION:
ANTENNA LAYOUT & MOUNTING DETAILS

SHEET NUMBER:
A-3

RRH: NOKIA FLEXI RRH 8TR 2600
 COLOR: LIGHT GREY
 WEIGHT: 44 LBS.




2.5 GHz RRH'S

NO SCALE

1

RRH: ALCATEL LUCENT 1900 MHz
 COLOR: LIGHT GREY
 WEIGHT: 70 LBS.
 (INCLUDING OPTIONAL SOLAR SHIELD)




1900 MHz RRH

NO SCALE

2

RRH: ALCATEL LUCENT RRH 800 MHz 2x50W
 COLOR: LIGHT GREY
 WEIGHT: 53 LBS.



NOTES

COMPLY WITH MANUFACTURERS INSTRUCTIONS TO ENSURE THAT ALL RRH'S RECEIVE ELECTRICAL POWER WITHIN 24 HOURS OF BEING REMOVED FROM THE MANUFACTURER'S PACKAGING. DO NOT OPEN RRH PACKAGES IN THE RAIN.

DETAIL NOT USED

NO SCALE

3

800 MHz RRH

NO SCALE

4

PLANS PREPARED FOR:



PLANS PREPARED BY:




INFINIGY ENGINEERING, PLLC
 1033 Watervliet Shaker Rd
 Albany, NY 12205
 Office # (518) 690-0790
 Fax # (518) 690-0793
 JOB NUMBER 526-104

PROJECT MANAGER:



32 CLINTON ST.
 SARATOGA SPRINGS, NY 12866
 OFFICE#, (518) 306-3740

ENGINEERING LICENSE:



03/13/2019

DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

| REVISIONS: | DESCRIPTION | DATE | BY | REV. |
|-------------------|-------------|----------|-----|------|
| | | | | |
| | | | | |
| | | | | |
| ISSUED FOR PERMIT | | 02/22/19 | MAP | 0 |

SITE NAME:

STTN - SOUTHTON

SITE NUMBER:

CT52XC108

SITE ADDRESS:

80 SHUTTLE MEADOW ROAD
 SOUTHTON, CT 06489

SHEET DESCRIPTION:

EQUIPMENT & MOUNTING DETAILS

SHEET NUMBER:

A-4

PLANS PREPARED FOR:



PLANS PREPARED BY:

INFINIGY
 INFINIGY ENGINEERING, PLLC
 1033 Watervliet Shaker Rd
 Albany, NY 12205
 Office # (518) 690-0790
 Fax # (518) 690-0793
 JOB NUMBER 526-104

PROJECT MANAGER:

AIRSMITH DEVELOPMENT
 32 CLINTON ST.
 SARATOGA SPRINGS, NY 12866
 OFFICE#, (518) 306-3740

ENGINEERING LICENSE:

03/13/2019

DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

| REVISIONS: | DESCRIPTION | DATE | BY | REV. |
|-------------------|-------------|----------|-----|------|
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| ISSUED FOR PERMIT | | 02/22/19 | MAP | 0 |

SITE NAME:

STTN - SOUTHINGTON

SITE NUMBER:

CT52XC108

SITE ADDRESS:

80 SHUTTLE MEADOW ROAD
 SOUTHINGTON, CT 06489

SHEET DESCRIPTION:



EQUIPMENT & MOUNTING DETAILS

SHEET NUMBER:

A-5



ANTENNA RFS APXVTM14-ALU-120

RADOME MATERIAL: ASA
 RADOME COLOR: LIGHT GREY
 DIMENSIONS, HxWxD.in(mim): 56.3"x12.6"x6.3" (1549x439x300mm)
 WEIGHT: 56.2 lbs
 CONNECTORS: (8) 4.1/9.5 DIN FEMALE
 (1) NF - CALIBRATION CONNECTOR



ANTENNA COMMSCOPE NNVV-65B-R4

RADOME MATERIAL: FIBERGLASS
 RADOME COLOR: LIGHT GREY
 DIMENSIONS, HxWxD.in(mim): 72"x19.6"x7.8" (1829x498x198mm)
 WEIGHT: 77.4 lbs
 CONNECTORS: (8) PIN DIN FEMALE
 (8) 8 PIN DIN MALE



2.5 ANTENNA DETAIL

NO SCALE

1

DUAL BAND ANTENNA DETAIL

NO SCALE

2

DETAIL NOT USED


NO SCALE

3

DETAIL NOT USED

NO SCALE

4




ELTEK ECAB EXTERIOR CABINET
P/N: ESOA220-SCA02

EQUIPMENT CABINET DETAIL

NO SCALE

1



ELTEK POWER PROTECTION CABINET
P/N: 5811122212

EQUIPMENT CABINET DETAIL

NO SCALE

2

PLANS PREPARED FOR:



PLANS PREPARED BY:




INFINIGY ENGINEERING, PLLC
1033 Watervliet Shaker Rd
Albany, NY 12205
Office # (518) 690-0790
Fax # (518) 690-0793
JOB NUMBER 526-104

PROJECT MANAGER:



32 CLINTON ST.
SARATOGA SPRINGS, NY 12866
OFFICE#, (518) 306-3740

ENGINEERING LICENSE:



03/13/2019

DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

| DESCRIPTION | DATE | BY | REV. |
|-------------------|----------|-----|------|
| ISSUED FOR PERMIT | 02/22/19 | MAP | 0 |

SITE NAME:

STTN - SOUTHINGTON

SITE NUMBER:

CT52XC108

SITE ADDRESS:


80 SHUTTLE MEADOW ROAD
SOUTHINGTON, CT 06489

SHEET DESCRIPTION:

EQUIPMENT & MOUNTING DETAILS

SHEET NUMBER:


A-6



H-FRAME DETAIL

NO SCALE

3



SUPPORT POST MOUNTING DETAIL

NO SCALE

4


RFS HYBRIFLEX RISER CABLE SCHEDULE

| | | |
|-----------------------------------|---|--------|
| Fiber Only (Existing DC Power) | Hybrid cable MN: HB058-M12-050F 12x multi-mode fiber pairs, Top: Outdoor protected connectors, Bottom: LC Connectors, 5/8 cable, 50 ft | 50 ft |
| | MN: HB058-M12-075F | 75 ft |
| | MN: HB058-M12-100F | 100 ft |
| | MN: HB058-M12-125F | 125 ft |
| | MN: HB058-M12-150F | 150 ft |
| | MN: HB058-M12-175F | 175 ft |
| MN: HB058-M12-200F | 200 ft | |
| 8 AWG Power | Hybrid cable MN: HB114-08U3M12-050F 3x 8 AWG power pairs, 12x multi-mode fiber pairs, Outdoor rated connectors & LC Connectors, 1 1/4 cable, 50 ft | 50 ft |
| | MN: HB114-08U3M12-075F | 75 ft |
| | MN: HB114-08U3M12-100F | 100 ft |
| | MN: HB114-08U3M12-125F | 125 ft |
| | MN: HB114-08U3M12-150F | 150 ft |
| | MN: HB114-08U3M12-175F | 175 ft |
| MN: HB114-08U3M12-200F | 200 ft | |
| 6 AWG Power | Hybrid cable MN: HB114-13U3M12-225F 3x 6 AWG power pair, 12x multi-mode fiber pairs, Outdoor rated connectors & LC Connectors, 1 1/4 cable, 225 ft | 225 ft |
| | MN: HB114-13U3M12-250F | 250 ft |
| | MN: HB114-13U3M12-275F | 275 ft |
| 4 AWG Power | Hybrid cable MN: HB114-21U3M12-325F 3x 4 AWG power pair, 12x multi-mode fiber pairs, Outdoor rated connectors & LC Connectors, 1 1/4 cable, 325 ft | 325 ft |
| | MN: HB114-21U3M12-350F | 350 ft |
| | MN: HB114-21U3M12-375F | 375 ft |


RFS HYBRIFLEX JUMPER CABLE SCHEDULE

| | | |
|-------------|---|-------|
| Fiber Only | Hybrid Jumper cable MN: HBF012-M3-5F1 5 ft, 3x multi-mode fiber pairs, Outdoor & LC connectors, 1/2 cable | 5 ft |
| | MN: HBF012-M3-10F1 | 10 ft |
| | MN: HBF012-M3-15F1 | 15 ft |
| | MN: HBF012-M3-20F1 | 20 ft |
| | MN: HBF012-M3-25F1 | 25 ft |
| | MN: HBF012-M3-30F1 | 30 ft |
| 8 AWG Power | Hybrid Jumper cable MN: HBF058-08U1M3-5F1 5 ft, 1x 8 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 5/8 cable | 5 ft |
| | MN: HBF058-08U1M3-10F1 | 10 ft |
| | MN: HBF058-08U1M3-15F1 | 15 ft |
| | MN: HBF058-08U1M3-20F1 | 20 ft |
| | MN: HBF058-08U1M3-25F1 | 25 ft |
| | MN: HBF058-08U1M3-30F1 | 30 ft |
| 6 AWG Power | Hybrid Jumper cable MN: HBF058-13U1M3-5F1 5 ft, 1x 6 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 5/8 cable | 5 ft |
| | MN: HBF058-13U1M3-10F1 | 10 ft |
| | MN: HBF058-13U1M3-15F1 | 15 ft |
| | MN: HBF058-13U1M3-20F1 | 20 ft |
| | MN: HBF058-13U1M3-25F1 | 25 ft |
| | MN: HBF058-13U1M3-30F1 | 30 ft |
| 4 AWG Power | Hybrid Jumper cable MN: HBF078-21U1M3-5F1 5 ft, 1x 4 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 7/8 cable | 5 ft |
| | MN: HBF078-21U1M3-10F1 | 10 ft |
| | MN: HBF078-21U1M3-15F1 | 15 ft |
| | MN: HBF078-21U1M3-20F1 | 20 ft |
| | MN: HBF078-21U1M3-25F1 | 25 ft |
| | MN: HBF078-21U1M3-30F1 | 30 ft |


NOTE:
SPRINT CM TO CONFIRM HYBRID OR FIBER RISER CABLE
AND HYBRID OR FIBER JUMPER CABLE MODEL NUMBERS IF
HYBRID CABLES ARE REQUIRED BEFORE PREPARING BOM.




4 AWG



8 & 6 AWG



FIBER ONLY



PROPOSED 3X3 HOFFMAN BOX TO COIL
EXCESS HYBRID THROUGH. (CONTRACTOR
TO INSTALL AS REQUIRED)

PROPOSED (4) HYBRID CABLES
FROM FIBER DISTRIBUTION BOX
TO NEW PANEL ANTENNAS

OPTIONAL HYBRID SLACK BOX

NO SCALE

2

800/1900/2500 CABLE CROSS SECTION DATA

NO SCALE

1

DETAIL NOT USED

NO SCALE

3

PLANS PREPARED FOR:



PLANS PREPARED BY:




INFINIGY ENGINEERING, PLLC
1033 Watervliet Shaker Rd
Albany, NY 12205
Office # (518) 690-0790
Fax # (518) 690-0793
JOB NUMBER 526-104

PROJECT MANAGER:



32 CLINTON ST.
SARATOGA SPRINGS, NY 12866
OFFICE#, (518) 306-3740

ENGINEERING LICENSE:



03/13/2019

DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE
THE SOLE PROPERTY OF SPRINT AND MAY NOT BE
REPRODUCED, DISSEMINATED OR REDISTRIBUTED
WITHOUT THE EXPRESS WRITTEN CONSENT OF
SPRINT.

REVISIONS:

| DESCRIPTION | DATE | BY | REV. |
|-------------------|----------|-----|------|
| | | | |
| | | | |
| | | | |
| ISSUED FOR PERMIT | 02/22/19 | MAP | 0 |

SITE NAME:

STTN - SOUTHINGTON

SITE NUMBER:

CT52XC108

SITE ADDRESS:

80 SHUTTLE MEADOW
ROAD
SOUTHINGTON, CT 06489

SHEET DESCRIPTION:


CIVIL DETAILS

SHEET NUMBER:

A-7

* PROPOSED CABLE LENGTH WAS DETERMINED USING THE SUM OF THE RAD CENTER OF
ANTENNAS, AND DISTANCE FROM EXISTING EQUIPMENT AREA TO TOWER BASE WITH AN
ADDITIONAL 20' BUFFER. LENGTH TO BE VERIFIED IN FIELD PRIOR TO ORDERING MATERIALS.

ALU-NSN 211 APXVTM14-ALU-I20 & NNVV-65B-R4 wo Filters



PLUMBING DIAGRAM

NO SCALE

1

PLANS PREPARED FOR:



PLANS PREPARED BY:




INFINIGY ENGINEERING, PLLC
1033 Watervliet Shaker Rd
Albany, NY 12205
Office # (518) 690-0790
Fax # (518) 690-0793
JOB NUMBER 526-104

PROJECT MANAGER:



32 CLINTON ST.
SARATOGA SPRINGS, NY 12866
OFFICE#, (518) 306-3740

ENGINEERING LICENSE:



DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

| DESCRIPTION | DATE | BY | REV. |
|-------------------|----------|-----|------|
| ISSUED FOR PERMIT | 02/22/19 | MAP | 0 |

SITE NAME:

STTN - SOUTHINGTON

SITE NUMBER:

CT52XC108

SITE ADDRESS:


80 SHUTTLE MEADOW ROAD
SOUTHINGTON, CT 06489

SHEET DESCRIPTION:

PLUMBING DIAGRAM

SHEET NUMBER:

A-8



ONE LINE DIAGRAM

NO SCALE

1

GENERAL ELECTRICAL NOTES:

- ALL ELECTRICAL WORK SHALL BE IN ACCORDANCE WITH THE LATEST VERSION OF THE NATIONAL ELECTRICAL CODE AND ALL LOCAL AND STATE CODES, LAWS, AND ORDINANCES.
- ALL UNDERGROUND CONDUIT SHALL BE PVC SCHEDULE 40 UNLESS OTHERWISE INDICATED. CONDUITS EXPOSED ABOVE GROUND SHALL BE RIGID GALVANIZED STEEL. ALL UNDERGROUND CONDUIT SHALL TRANSITION FROM PVC TO RIGID ABOVE GRADE. PROVIDE 36" SEPARATION BETWEEN UNDERGROUND POWER AND TELEPHONE CONDUITS. SUPPLY UTILITY MARKING TAPE BURIED 12" BELOW GRADE ALONG ENTIRE LENGTH OF UNDERGROUND CONDUITS.
- ALL CONDUCTORS SHALL BE COPPER WITH THHN/THWN INSULATION. CONTROL CONDUCTORS SHALL BE STRANDED, POWER & LIGHTING CONDUCTORS SHALL BE SOLID FOR #10 & #12 CONDUCTORS AND STRANDED FOR ALL OTHER SIZES.
- ELECTRICAL DRAWINGS ARE IN PART DIAGRAMMATIC. COORDINATE ELECTRICAL WORK WITH SITE CONDITIONS.
- LOCATE ALL UNDERGROUND UTILITIES BEFORE TRENCHING. IF CONFLICTS ARISE, CONTACT UTILITY COMPANY AND ENGINEER IMMEDIATELY.
- ALL EXPOSED CONDUITS SHALL HAVE WEATHERPROOF CAPS NOT DUCT TAPE.
- PROVIDE 200 LB TEST PULL WIRES IN EACH TELEPHONE AND POWER CONDUIT.
- PULL BOXES SHALL BE INSTALLED AS NEEDED PER NEC UTILITY REQUIREMENTS.

GENERAL GROUNDING NOTES:

- TO ENSURE PROPER BONDING, ALL CONNECTIONS SHALL BE AS FOLLOWS:
 - #2/0 BARE TINNED SOLID COPPER CONDUCTOR: CADWELDED TO RODS OR GROUND RING
 - LUGS AND BUS BAR (UNLESS NOTED OTHERWISE): SANDED CLEAN, COATED WITH OXIDE INHIBITOR AND BOLTED FOR MAXIMUM SURFACE CONTACT. ALL LUGS SHALL BE COPPER (NO ALUMINUM SHALL BE PERMITTED). PROVIDE LOCK WASHERS FOR ALL MECHANICAL CONNECTIONS FOR GROUND CONDUCTORS. USE STAINLESS STEEL HARDWARE THROUGHOUT.
- ALL GROUNDING CABLE IN CONCRETE OR THROUGH WALLS SHALL BE IN 3/4" PVC CONDUIT. SEAL AROUND CONDUIT THROUGH WALLS. NO METALLIC CONDUIT SHALL BE USED FOR GROUNDING CONDUCTORS.
- OWNER'S REPRESENTATIVE WILL INSPECT CADWELDS AND CONDUCT MEGGER TEST PRIOR TO BURIAL. MAXIMUM 5 OHMS RESISTANCE IS REQUIRED.
- DO NOT INSTALL GROUND RING OUTSIDE OF LEASED AREA.
- MAKE ALL GROUND CONNECTIONS AS SHORT AND DIRECT AS POSSIBLE. AVOID SHARP BENDS. ALL BENDS SHALL BE A MINIMUM 8" RADIUS AND NO GREATER THAN 90 DEGREES.
- ALL CADWELDS TO BURIED GROUND RING SHALL BE THE PARALLEL TYPE, EXCEPT FOR THE GROUND RODS WHICH SHALL BE THE TEE TYPE.
- BOND SERVICE CONDUITS TO GROUND RING AS THEY CROSS. DO NOT EXOTHERMICALLY WELD TO CONDUITS.
- THE CONTRACTOR SHALL NOTIFY THE CONSTRUCTION MANAGER WHEN THE GROUNDING SYSTEM IS COMPLETE. THE CONSTRUCTION MANAGER SHALL INSPECT THE GROUNDING SYSTEM PRIOR TO BACKFILLING.
- THE MINIMUM SPACING BETWEEN GROUND RODS SHALL BE 10'-0" (MAX. 15'-0").
- BOND CIGBE TO EXTERNAL GROUND RING WITH 2 RUNS OF #2 BARE, TINNED, SOLID COPPER CONDUCTOR IN PVC. CONNECT BAR END WITH 2 HOLE LUG, AND "CADWELD" THE OTHER END TO THE EXTERNAL GROUND ROD.
- THE PREFERRED LOCATION FOR COAX GROUNDING IS AT THE BASE OF THE TOWER PRIOR TO THE COAX BEND. BONDING IS SHOWN ON THE ICE BRIDGE DUE TO DIFFICULTY WITH WELDING OR ATTACHING TO TOWER LEGS. CONTRACTOR SHALL ADVISE CONSTRUCTION MANAGER PRIOR TO PLACING CIGBE ON ICE BRIDGE IF MOUNTING TO TOWER LEG IS POSSIBLE.
- BONDING OF THE GROUNDED CONDUCTOR (NEUTRAL) AND THE GROUNDING CONDUCTOR SHALL BE AT THE SERVICE DISCONNECTING MEANS. BONDING JUMPER SHALL BE INSTALLED PER N.E.C. ARTICLE 250-30.

ELECTRICAL NOTES

NO SCALE

2

GROUNDING NOTES

NO SCALE

3

PLANS PREPARED FOR:



PLANS PREPARED BY:




INFINIGY ENGINEERING, PLLC
1033 Watervliet Shaker Rd
Albany, NY 12205
Office # (518) 690-0790
Fax # (518) 690-0793
JOB NUMBER 526-104

PROJECT MANAGER:



32 CLINTON ST.
SARATOGA SPRINGS, NY 12866
OFFICE#, (518) 306-3740

ENGINEERING LICENSE:



03/13/2019

DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

| DESCRIPTION | DATE | BY | REV. |
|-------------------|----------|-----|------|
| ISSUED FOR PERMIT | 02/22/19 | MAP | 0 |

SITE NAME:

STTN - SOUTHINGTON

SITE NUMBER:

CT52XC108

SITE ADDRESS:


80 SHUTTLE MEADOW ROAD
SOUTHINGTON, CT 06489

SHEET DESCRIPTION:

ELECTRICAL & GROUNDING PLAN


SHEET NUMBER:

E-1



INFINIGY
 INFINIGY ENGINEERING, PLLC
 1033 Watervliet Shaker Rd
 Albany, NY 12205
 Office # (518) 690-0790
 Fax # (518) 690-0793
 JOB NUMBER 526-104

AIROSMITH
 DEVELOPMENT
 32 CLINTON ST.
 SARATOGA SPRINGS, NY 12866
 OFFICE#, (518) 306-3740



THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

| REVISIONS: | DESCRIPTION | DATE | BY | REV. |
|-------------------|-------------|----------|-----|------|
| ISSUED FOR PERMIT | | 02/22/19 | MAP | 0 |


STTN - SOUTHINGTON

CT52XC108

**80 SHUTTLE MEADOW ROAD
 SOUTHINGTON, CT 06489**

ELECTRICAL & GROUNDING PLAN


E-2



- LEGEND:**
- · - · - · EXISTING GROUND RING
 - CADWELD CONNECTION (EXOTHERMIC WELD)
 - ▲ MECHANICAL CONNECTION
 - ⊗ GROUND ROD

GROUNDING PLAN


NO SCALE 1




- LEGEND**
- 1 - TINNED COPPER GROUND BAR, 1/4"x 4"x 24"
 - 2 - INSULATORS (NO INSULATORS ON TOWER)
 - 3 - 5/8" LOCK WASHERS
 - 4 - MOUNTING BRACKET (MOUNT HORIZONTAL ON VERTICAL CABLE LADDER)
 - 5 - 5/8-11 X 1" H.H.C.S.BOLTS
 - 6 - "LOCTITE" THREAD LOCK (RED) ON ALL REMOVABLE BOLTS

TINNED GROUND BAR DETAIL NO SCALE 2

- NOTE:**
1. COPPER GROUND BAR 1/4"x4"x24" 2-HOLE CENTERS TO MATCH NEMA DOUBLE LUG CONFIGURATION.
 2. SIMILAR INSTALLATION FOR TOP AND BOTTOM TOWER GROUND BARS AND FOR COAX ENTRY PORT GROUND BARS.




ANTENNA GROUND WIRE INSTALLATION NO SCALE 3



- NOTE:** ALL MECHANICAL EXTERNAL TERMINATION SURFACES SHALL BE TREATED WITH T&B KOPR-SHIELD CP8 ANTI-OXIDATION COMPOUND.
- "DO NOT DISCONNECT" TAG ON ALL GROUND BAR INTERCONNECTS

EQUIPMENT GROUND CONNECTION

NO SCALE 4



- NOTE:** DO NOT INSTALL CABLE GROUND KIT AT A BEND AND ALWAYS DIRECT GROUND WIRE DOWN TO GROUND BAR.


CABLE GROUND KIT CONNECTION NO SCALE 5



INFINIGY ENGINEERING, PLLC
1033 Watervliet Shaker Rd
Albany, NY 12205
Office # (518) 690-0790
Fax # (518) 690-0793
JOB NUMBER 526-104



32 CLINTON ST.
SARATOGA SPRINGS, NY 12866
OFFICE#, (518) 306-3740



THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

| DESCRIPTION | DATE | BY | REV. |
|-------------------|----------|-----|------|
| ISSUED FOR PERMIT | 02/22/19 | MAP | 0 |


STTN - SOUTHINGTON

CT52XC108

80 SHUTTLE MEADOW ROAD
SOUTHINGTON, CT 06489


ELECTRICAL & GROUNDING DETAILS

E-3



GROUND ROD & INSPECTION SLEEVE DETAIL


NO SCALE 1



CONNECTION OF GROUND WIRES TO GROUND BARS @ ANTENNAS


NO SCALE 2

- LEGEND:**
- - - - - EXISTING GROUND RING
 - CADWELD CONNECTION (EXOTHERMIC WELD)
 - ▲ MECHANICAL CONNECTION
 - ⊗ GROUND ROD
 - CABLE GROUND KIT



TYPICAL ANTENNA GROUNDING PLAN

NO SCALE 3



GROUNDING RISER DIAGRAM

NO SCALE 4



AMERICAN TOWER®
CORPORATION

Structural Analysis Report

Structure : 150 ft Monopole
ATC Site Name : Sttn - Southington, CT
ATC Site Number : 302475
Engineering Number : OAA713367_C3_07
Proposed Carrier : Clearwire Corporation
Carrier Site Name : Sttn - Southington
Carrier Site Number : CT52XC108
Site Location : 80 Shuttle Meadow Road
Southington, CT 06489-1313
41.638600,-72.841100
County : Hartford
Date : January 4, 2019
Max Usage : 100%
Result : Pass

Prepared By:
Zackaryah Hughes
Structural Engineer I

Reviewed By:

COA: PEC.0001553



Table of Contents

| | |
|--------------------------------------|----------|
| Introduction | 1 |
| Supporting Documents | 1 |
| Analysis | 1 |
| Conclusion..... | 1 |
| Existing and Reserved Equipment..... | 2 |
| Equipment to be Removed..... | 2 |
| Proposed Equipment | 2 |
| Structure Usages | 3 |
| Foundations | 3 |
| Deflection and Sway | 3 |
| Standard Conditions | 4 |
| Calculations | Attached |



Introduction

The purpose of this report is to summarize results of a structural analysis performed on the 150 ft monopole to reflect the change in loading by Clearwire Corporation.

Supporting Documents

| | |
|----------------------------|---|
| Tower Drawings | SpectraSite Mapping Site #CT-0011, dated May 29, 2002 AT&T Technologies Project #AT-8935, dated April 13, 1984 |
| Foundation Drawing | Girard & Co. Engineers Project #38922, dated May 18, 1983 |
| Geotechnical Report | GeoTechnologies Project #1-02-0934-EA, dated July 12, 2002 |
| Modifications | ATC Job #40480332, dated May 25, 2007 ATC Job #42608538, dated April 22, 2009 |

Analysis

The tower was analyzed using American Tower Corporation's tower analysis software. This program considers an elastic three-dimensional model and second-order effects per ANSI/TIA-222.

| | |
|---------------------------------|--|
| Basic Wind Speed: | 97 mph (3-Second Gust, Vasd) / 125 mph (3-Second Gust, Vult) |
| Basic Wind Speed w/ Ice: | 50 mph (3-Second Gust) w/ 1" radial ice concurrent |
| Code: | ANSI/TIA-222-G / 2015 IBC / 2018 Connecticut State Building Code |
| Structure Class: | II |
| Exposure Category: | B |
| Topographic Category: | 1 |
| Crest Height: | 0 ft |
| Spectral Response: | $S_s = 0.18, S_1 = 0.06$ |
| Site Class: | D - Stiff Soil |

Conclusion

Based on the analysis results, the structure meets the requirements per the applicable codes listed above. The tower and foundation can support the equipment as described in this report.

If you have any questions or require additional information, please contact American Tower via email at Engineering@americantower.com. Please include the American Tower site name, site number, and engineering number in the subject line for any questions.



Existing and Reserved Equipment

| Elevation ¹ (ft) | | Qty | Antenna | Mount Type | Lines | Carrier |
|-----------------------------|-------|-------|---------------------------------------|-----------------------|---|-------------------------------|
| Mount | RAD | | | | | |
| 150.0 | 153.0 | 6 | CCI TPX-070821 | Platform w/ Handrails | (3) 1 5/8" Coax (12) 7/8" Coax (6) 0.78" 8 AWG 6 (2) 0.39" Fiber Trunk (1) 3" conduit | AT&T Mobility |
| | | 2 | Raycap DC6-48-60-18-8F (23.5" Height) | | | |
| | | 6 | CCI DTMABP7819VG12A (w/ Bracket) | | | |
| | | 3 | Ericsson RRUS-11 (50 lbs.) | | | |
| | | 3 | Ericsson RRUS 32 B2 | | | |
| | | 3 | Ericsson RRUS-32 (77 lbs) | | | |
| | | 3 | Powerwave 7770.00 | | | |
| | | 2 | KMW AM-X-CD-16-65-00T-RET | | | |
| | | 3 | Quintel QS66512-3 (112 lbs.) | | | |
| | | 1 | Andrew SBNH-1D6565C (60.8 lbs) | | | |
| | | 154.0 | 1 | | | 10' Omni |
| 134.0 | 134.0 | 3 | Kathrein Smart Bias Tee | Site-Pro UWS6-NPs | (12) 1 5/8" Coax | Metro PCS |
| | | 3 | RFS APXV18-206517S-C | | | |
| | | 3 | Andrew LNX-6515DS-VTM | | | |
| 120.0 | 120.0 | 1 | DragonWave Horizon Compact | Flush | (1) 1/2" Coax | Clearwire |
| | | 1 | DragonWave A-ANT-11G-2.5-C | | | |
| 105.0 | 109.0 | 1 | dB Systems 5100A | Side Arms | (6) 7/8" Coax | M/A Com Private Radio Systems |
| | | 4 | dB Systems 5100A-D | | | |
| | | 104.0 | 1 | | | |

Equipment to be Removed

| Elevation ¹ (ft) | | Qty | Antenna | Mount Type | Lines | Carrier |
|-----------------------------|-------|-----|------------------|------------|----------------|-----------|
| Mount | RAD | | | | | |
| 120.0 | 120.0 | 3 | Argus LLPX310R | - | (6) 5/16" Coax | Clearwire |
| | | 3 | NextNet BTS-2500 | | | |

Proposed Equipment

| Elevation ¹ (ft) | | Qty | Antenna | Mount Type | Lines | Carrier |
|-----------------------------|-------|-----|-------------------------------------|------------|--|-----------|
| Mount | RAD | | | | | |
| 120.0 | 120.0 | 1 | 12" x 12" Junction Box | Flush | (4) 1 1/4" Hybriflex (2) 2" conduit | Clearwire |
| | | 6 | Alcatel-Lucent RRH2x50-08 | | | |
| | | 3 | Nokia FZHN Flexi RRH 8TR 2600 9*20W | | | |
| | | 3 | Alcatel-Lucent 1900MHz 4X45 RRH | | | |
| | | 3 | RFS APXVTM14-ALU-I20 | | | |
| | | 3 | Commscope NNVV-65B-R4 | | | |

¹Mount elevation is defined as height above bottom of steel structure to the bottom of mount, RAD elevation is defined as center of antenna above ground level (AGL).

Install proposed coax outside the pole shaft. Stacking coax is not allowed.

Structure Usages

| Structural Component | Controlling Usage | Pass/Fail |
|----------------------|-------------------|-----------|
| Anchor Bolts | 73% | Pass |
| Shaft | 100% | Pass |
| Base Plate | 53% | Pass |
| Flanges | 78% | Pass |
| Reinforcement | 73% | Pass |

Foundations

| Reaction Component | Analysis Reactions | % of Usage |
|--------------------|--------------------|------------|
| Moment (Kips-Ft) | 2,279.2 | 84% |
| Axial (Kips) | 35.1 | 49% |
| Shear (Kips) | 24.0 | 33% |

The structure base reactions resulting from this analysis were found to be acceptable through analysis based on geotechnical and foundation information, therefore no modification or reinforcement of the foundation will be required.

Deflection and Sway*

| Antenna Elevation (ft) | Antenna | Carrier | Deflection (ft) | Sway (Rotation) (°) |
|------------------------|-------------------------------------|-----------------------|-----------------|---------------------|
| 120.0 | 12" x 12" Junction Box | Clearwire Corporation | 1.689 | 1.908 |
| | Alcatel-Lucent RRH2x50-08 | | | |
| | Nokia FZHN Flexi RRH 8TR 2600 9*20W | | | |
| | Alcatel-Lucent 1900 MHz 4X45 RRH | | | |
| | RFS APXVTM14-ALU-I20 | | | |
| | DragonWave A-ANT-11G-2.5-C | | | |
| Commscope NNVV-65B-R4 | | | | |

*Deflection and Sway was evaluated considering a design wind speed of 60 mph (3-Second Gust) per ANSI/TIA-222-G



Standard Conditions

All engineering services performed by A.T. Engineering Service, PLLC are prepared on the basis that the information used is current and correct. This information may consist of, but is not limited to the following:

- Information supplied by the client regarding antenna, mounts and feed line loading
- Information from drawings, design and analysis documents, and field notes in the possession of A.T. Engineering Service, PLLC


It is the responsibility of the client to ensure that the information provided to A.T. Engineering Service, PLLC and used in the performance of our engineering services is correct and complete.

All assets of American Tower Corporation, its affiliates and subsidiaries (collectively "American Tower") are inspected at regular intervals. Based upon these inspections and in the absence of information to the contrary, American Tower assumes that all structures were constructed in accordance with the drawings and specifications.

Unless explicitly agreed by both the client and A.T. Engineering Service, PLLC, all services will be performed in accordance with the current revision of ANSI/TIA-222.

All services are performed, results obtained, and recommendations made in accordance with generally accepted engineering principles and practices. A.T. Engineering Service, PLLC is not responsible for the conclusions, opinions and recommendations made by others based on the information supplied herein.

© 2007 - 2019 by ATC IP LLC. All rights reserved.




| Job Information | |
|--|----------------------|
| Pole : 302475 | Code: ANSI/TIA-222-G |
| Location : Sttn - Southington, CT | |
| Description : 150' ITT Meyer Type "B" Monopole | |
| Client : CLEARWIRE CORPORATION | Structure Class : II |
| Shape : 12 Sides | Exposure : B |
| Height : 150.00 (ft) | Topo : 1 |
| Base Elev (ft): 0.00 | |
| Taper: 0.160834in/ft | |

| Sections Properties | | | | | | | |
|---------------------|-------------|---------------|---------------|------------|------------|---------------------|-------------------|
| Shaft Section | Length (ft) | Diameter (in) | | Thick (in) | Joint Type | Overlap Length (in) | Steel Grade (ksi) |
| | | Across Top | Across Bottom | | | | |
| 1 | 35.667 | 31.26 | 37.00 | 0.375 | | 0.000 | 12 Sides 65 |
| 2 | 42.000 | 25.80 | 32.55 | 0.313 | Slip Joint | 50.000 | 12 Sides 65 |
| 3 | 40.000 | 20.43 | 26.86 | 0.250 | Slip Joint | 42.000 | 12 Sides 65 |
| 4 | 40.000 | 14.00 | 20.43 | 0.188 | Butt Joint | 0.000 | 12 Sides 65 |

| Discrete Appurtenance | | | |
|-----------------------|-----------------|-----|-------------------------------|
| Attach Elev (ft) | Force Elev (ft) | Qty | Description |
| 150.000 | 150.000 | 1 | Round Platform w/ Handrails |
| 150.000 | 153.000 | 1 | Andrew SBNH-1D6565C (60.8 |
| 150.000 | 153.000 | 3 | Quintel QS66512-3 (112 lbs.) |
| 150.000 | 153.000 | 2 | KMW AM-X-CD-16-65-00T-RET |
| 150.000 | 153.000 | 3 | Powerwave Allgon 7770.00 |
| 150.000 | 153.000 | 3 | Ericsson RRUS-32 (77 lbs) |
| 150.000 | 154.000 | 1 | 10' Omni |
| 150.000 | 153.000 | 3 | Ericsson RRUS 32 B2 |
| 150.000 | 153.000 | 3 | Ericsson RRUS-11 (50 lbs.) |
| 150.000 | 153.000 | 6 | CCI DTMABP7819VG12A (w/ |
| 150.000 | 153.000 | 2 | Raycap DC6-48-60-18-8F (23.5" |
| 150.000 | 153.000 | 6 | CCI TPX-070821 |
| 134.000 | 134.000 | 3 | Andrew LNX-6515DS-VTM |
| 134.000 | 134.000 | 3 | RFS APXV18-206517S-C |
| 134.000 | 134.000 | 3 | Site-Pro UWS6-NP |
| 134.000 | 134.000 | 3 | Kathrein Smart Bias Tee |
| 120.000 | 120.000 | 3 | Nokia FZHN Flexi RRH 8TR 2600 |
| 120.000 | 120.000 | 1 | DragonWave A-ANT-11G-2.5-C |
| 120.000 | 120.000 | 3 | Commscope NNVV-65B-R4 |
| 120.000 | 120.000 | 3 | RFS APXVTM14-ALU-I20 |
| 120.000 | 120.000 | 3 | Alcatel-Lucent 1900 MHz 4X45 |
| 120.000 | 120.000 | 6 | Alcatel-Lucent RRH2x50-08 |
| 120.000 | 120.000 | 1 | DragonWave Horizon Compact |
| 120.000 | 120.000 | 1 | 12" x 12" Junction Box |
| 105.000 | 105.000 | 3 | Round Side Arm |
| 105.000 | 109.000 | 4 | dB Systems 5100A-D |
| 105.000 | 104.000 | 1 | VertexRSI 101V VPD |
| 105.000 | 109.000 | 1 | dB Systems 5100A |

| Linear Appurtenance | | | |
|---------------------|--------|------------------|-----------------|
| Elev (ft) From | To | Description | Exposed To Wind |
| 0.000 | 82.500 | #20 Dywidag Bars | Yes |
| 0.000 | 105.0 | 7/8" Coax | Yes |
| 0.000 | 120.0 | 1 1/4" Hybriflex | Yes |
| 0.000 | 120.0 | 1/2" Coax | Yes |
| 0.000 | 120.0 | 2" conduit | Yes |
| 0.000 | 134.0 | 1 5/8" Coax | Yes |
| 0.000 | 134.0 | 1 5/8" Coax | Yes |
| 0.000 | 150.0 | 0.39" (10mm) | No |



| | | | |
|-------|-------|------------------|----|
| 0.000 | 150.0 | 0.78" (19.7mm) 8 | No |
| 0.000 | 150.0 | 0.78" (19.7mm) 8 | No |
| 0.000 | 150.0 | 1 5/8" Coax | No |
| 0.000 | 150.0 | 3" conduit | No |
| 0.000 | 150.0 | 7/8" Coax | No |

Load Cases

| | |
|-------------------------|--|
| 1.2D + 1.6W | 97 mph with No Ice |
| 0.9D + 1.6W | 97 mph with No Ice (Reduced DL) |
| 1.2D + 1.0Di + 1.0Wi | 50 mph with 1.00 in Radial Ice |
| (1.2 + 0.2Sds) * DL + E | Seismic Equivalent Lateral Forces Method |
| (1.2 + 0.2Sds) * DL + E | Seismic Equivalent Modal Analysis Method |
| (0.9 - 0.2Sds) * DL + E | Seismic (Reduced DL) Equivalent Lateral |
| (0.9 - 0.2Sds) * DL + E | Seismic (Reduced DL) Equivalent Modal |
| 1.0D + 1.0W | Serviceability 60 mph |


Reactions

| Load Case | Moment (kip-ft) | Shear (kip) | Axial (kip) |
|------------------------------|--------------------|----------------|----------------|
| 1.2D + 1.6W | 2279.16 | 23.98 | 35.08 |
| 0.9D + 1.6W | 2245.15 | 23.96 | 26.30 |
| 1.2D + 1.0Di + 1.0Wi | 650.15 | 5.96 | 73.90 |
| (1.2 + 0.2Sds) * DL + E ELFM | 110.91 | 0.88 | 34.70 |
| (1.2 + 0.2Sds) * DL + E EMAM | 176.62 | 1.48 | 34.70 |
| (0.9 - 0.2Sds) * DL + E ELFM | 108.65 | 0.88 | 24.10 |
| (0.9 - 0.2Sds) * DL + E EMAM | 172.62 | 1.48 | 24.10 |
| 1.0D + 1.0W | 543.16 | 5.75 | 29.28 |

Dish Deflections

| Load Case | Attach Elev (ft) | Deflection (in) | Rotation (deg) |
|-------------|---------------------|--------------------|-------------------|
| 1.0D + 1.0W | 120.00 | 20.272 | 1.908 |

Load Case : 1.2D + 1.6W
Max Ratio 100.11% at 75.8 ft



Site Number: 302475

Code: ANSI/TIA-222-G

© 2007 - 2019 by ATC IP LLC. All rights reserved.

Site Name: Sttn - Southington, CT

Engineering Number: OAA713367_C3_07

1/4/2019 4:03:07 PM

Customer: CLEARWIRE

Analysis Parameters

| | | | |
|---------------------|---------------------|----------------------|-------|
| Location : | HARTFORD County, CT | Height (ft) : | 150 |
| Code : | ANSI/TIA-222-G | Base Diameter (in) : | 37.00 |
| Shape : | 12 Sides | Top Diameter (in) : | 14.00 |
| Pole Type : | Taper | Taper (in/ft) : | 0.161 |
| Pole Manufacturer : | ITT Meyer | Rotation (deg) : | 0.00 |

Ice & Wind Parameters

| | | | |
|-----------------------|------|--------------------------------|---------|
| Structure Class: | II | Design Wind Speed Without Ice: | 97 mph |
| Exposure Category: | B | Design Wind Speed With Ice: | 50 mph |
| Topographic Category: | 1 | Operational Wind Speed: | 60 mph |
| Crest Height: | 0 ft | Design Ice Thickness: | 1.00 in |

Seismic Parameters

| | | | |
|--|--|---------------------|-------|
| Analysis Method: | Equivalent Modal Analysis & Equivalent Lateral Force Methods | | |
| Site Class: | D - Stiff Soil | | |
| Period Based on Rayleigh Method (sec): | 2.80 | | |
| T _L (sec): | 6 | p: | 1 |
| S _s : | 0.184 | S ₁ : | 0.064 |
| F _a : | 1.600 | F _v : | 2.400 |
| S _{ds} : | 0.196 | S _{d1} : | 0.102 |
| | | C _s : | 0.030 |
| | | C _s Max: | 0.030 |
| | | C _s Min: | 0.030 |

Load Cases

| | |
|---|---|
| 1.2D + 1.6W | 97 mph with No Ice |
| 0.9D + 1.6W | 97 mph with No Ice (Reduced DL) |
| 1.2D + 1.0Di + 1.0Wi | 50 mph with 1.00 in Radial Ice |
| (1.2 + 0.2S _{ds}) * DL + E ELFM | Seismic Equivalent Lateral Forces Method |
| (1.2 + 0.2S _{ds}) * DL + E EMAM | Seismic Equivalent Modal Analysis Method |
| (0.9 - 0.2S _{ds}) * DL + E ELFM | Seismic (Reduced DL) Equivalent Lateral Forces Method |
| (0.9 - 0.2S _{ds}) * DL + E EMAM | Seismic (Reduced DL) Equivalent Modal Analysis Method |
| 1.0D + 1.0W | Serviceability 60 mph |

Site Number: 302475

Code: ANSI/TIA-222-G

© 2007 - 2019 by ATC IP LLC. All rights reserved.

Site Name: Sttn - Southington, CT

Engineering Number: OAA713367_C3_07

1/4/2019 4:03:07 PM

Customer: CLEARWIRE

Shaft Section Properties

| Sect Info | Length (ft) | Thick (in) | Fy (ksi) | Joint Type | Joint Len (in) | Weight (lb) | Bottom | | | | | | Top | | | | | | |
|--------------|-------------|------------|----------|------------|----------------|-------------|----------|-----------|-------------------------|-----------------------|-----------|-----------|----------|-----------|-------------------------|-----------------------|-----------|-----------|---------------|
| | | | | | | | Dia (in) | Elev (ft) | Area (in ²) | Ix (in ⁴) | W/t Ratio | D/t Ratio | Dia (in) | Elev (ft) | Area (in ²) | Ix (in ⁴) | W/t Ratio | D/t Ratio | Taper (in/ft) |
| 1-12 | 35.667 | 0.3750 | 65 | | 0.00 | 4,947 | 37.00 | 0.00 | 44.22 | 7571.9 | 23.76 | 98.67 | 31.26 | 35.67 | 37.30 | 4542.2 | 19.66 | 83.37 | 0.160833 |
| 2-12 | 42.000 | 0.3125 | 65 | Slip | 50.00 | 4,152 | 32.55 | 31.50 | 32.45 | 4306.6 | 25.24 | 104.19 | 25.80 | 73.50 | 25.65 | 2127.5 | 19.45 | 82.57 | 0.160833 |
| 3-12 | 40.000 | 0.2500 | 65 | Slip | 42.00 | 2,564 | 26.86 | 70.00 | 21.43 | 1937.5 | 26.12 | 107.47 | 20.43 | 110.00 | 16.25 | 844.8 | 19.22 | 81.73 | 0.160833 |
| 4-12 | 40.000 | 0.1875 | 65 | Butt | 0.00 | 1,399 | 20.43 | 110.00 | 12.22 | 639.5 | 26.52 | 108.98 | 14.00 | 150.00 | 8.34 | 203.1 | 17.33 | 74.67 | 0.160833 |
| Shaft Weight | | | | | | 13,062 | | | | | | | | | | | | | |

Discrete Appurtenance Properties

| Attach Elev (ft) | Description | Qty | Distance From Face (ft) | Vert Ecc (ft) | Weight (lb) | No Ice EPAa (sf) | Orientation Factor |
|------------------|--------------------------------|-----|-------------------------|---------------|-------------|------------------|--------------------|
| 150.00 | 10' Omni | 1 | 0.000 | 4.000 | 25.00 | 3.000 | 1.00 |
| 150.00 | Andrew SBNH-1D6565C (60.8 lbs) | 1 | 0.000 | 3.000 | 60.80 | 11.450 | 0.70 |
| 150.00 | CCI DTMABP7819VG12A (w/ | 6 | 0.000 | 3.000 | 19.20 | 1.370 | 0.50 |
| 150.00 | CCI TPX-070821 | 6 | 0.000 | 3.000 | 7.50 | 0.550 | 0.50 |
| 150.00 | Ericsson RRUS 32 B2 | 3 | 0.000 | 3.000 | 53.00 | 2.740 | 0.50 |
| 150.00 | Ericsson RRUS-11 (50 lbs.) | 3 | 0.000 | 3.000 | 50.00 | 2.570 | 0.50 |
| 150.00 | Ericsson RRUS-32 (77 lbs) | 3 | 0.000 | 3.000 | 77.00 | 3.310 | 0.50 |
| 150.00 | KMW AM-X-CD-16-65-00T-RET | 2 | 0.000 | 3.000 | 48.50 | 8.020 | 0.67 |
| 150.00 | Powerwave Allgon 7770.00 | 3 | 0.000 | 3.000 | 35.00 | 5.510 | 0.65 |
| 150.00 | Quintel QS66512-3 (112 lbs.) | 3 | 0.000 | 3.000 | 112.00 | 8.130 | 0.74 |
| 150.00 | Raycap DC6-48-60-18-8F (23.5" | 2 | 0.000 | 3.000 | 20.00 | 1.110 | 0.50 |
| 150.00 | Round Platform w/ Handrails | 1 | 0.000 | 0.000 | 2000.00 | 17.700 | 1.00 |
| 134.00 | Andrew LNX-6515DS-VTM | 3 | 0.000 | 0.000 | 51.30 | 11.430 | 0.70 |
| 134.00 | Kathrein Smart Bias Tee | 3 | 0.000 | 0.000 | 3.31 | 0.090 | 0.50 |
| 134.00 | RFS APXV18-206517S-C | 3 | 0.000 | 0.000 | 26.40 | 5.170 | 0.68 |
| 134.00 | Site-Pro UWS6-NP | 3 | 0.000 | 0.000 | 92.00 | 1.500 | 0.50 |
| 120.00 | 12" x 12" Junction Box | 1 | 0.000 | 0.000 | 10.00 | 1.200 | 0.50 |
| 120.00 | Alcatel-Lucent 1900 MHz 4X45 R | 3 | 0.000 | 0.000 | 60.00 | 2.320 | 0.50 |
| 120.00 | Alcatel-Lucent RRH2x50-08 | 6 | 0.000 | 0.000 | 52.90 | 1.700 | 0.50 |
| 120.00 | Commscope NNVV-65B-R4 | 3 | 0.000 | 0.000 | 77.40 | 12.270 | 0.64 |
| 120.00 | DragonWave A-ANT-11G-2.5-C | 1 | 0.000 | 0.000 | 47.60 | 8.670 | 1.00 |
| 120.00 | DragonWave Horizon Compact | 1 | 0.000 | 0.000 | 10.60 | 0.840 | 0.50 |
| 120.00 | Nokia FZHN Flexi RRH 8TR 2600 | 3 | 0.000 | 0.000 | 44.10 | 2.020 | 0.50 |
| 120.00 | RFS APXVTM14-ALU-I20 | 3 | 0.000 | 0.000 | 56.20 | 6.340 | 0.66 |
| 105.00 | dB Systems 5100A | 1 | 0.000 | 4.000 | 21.00 | 2.070 | 1.00 |
| 105.00 | dB Systems 5100A-D | 4 | 0.000 | 4.000 | 38.00 | 3.110 | 1.00 |
| 105.00 | Round Side Arm | 3 | 0.000 | 0.000 | 150.00 | 5.200 | 0.67 |
| 105.00 | VertexRSI 101V VPD | 1 | 0.000 | -1.000 | 4.00 | 2.540 | 1.00 |
| Totals | Num Loadings:28 | 76 | | | 5608.73 | | |

Linear Appurtenance Properties

| Elev From (ft) | Elev To (ft) | Qty | Description | Coax Diameter (in) | Coax Weight (lb/ft) | Projected Width Flat (in) | Exposed To Wind | Carrier | |
|----------------|--------------|-----|----------------------|--------------------|---------------------|---------------------------|-----------------|---------|---------------|
| 0.00 | 150.00 | 2 | 0.39" (10mm) Fiber | 0.39 | 0.06 | N | 0.00 | N | AT&T Mobility |
| 0.00 | 150.00 | 4 | 0.78" (19.7mm) 8 AWG | 0.78 | 0.59 | N | 0.00 | N | AT&T Mobility |
| 0.00 | 150.00 | 2 | 0.78" (19.7mm) 8 AWG | 0.78 | 0.59 | N | 0.00 | N | AT&T Mobility |
| 0.00 | 150.00 | 3 | 1 5/8" Coax | 1.98 | 0.82 | N | 0.00 | N | Other |
| 0.00 | 150.00 | 1 | 3" conduit | 3.50 | 7.58 | N | 0.00 | N | AT&T Mobility |
| 0.00 | 150.00 | 12 | 7/8" Coax | 1.09 | 0.33 | N | 0.00 | N | AT&T Mobility |
| 0.00 | 134.00 | 6 | 1 5/8" Coax | 1.98 | 0.82 | N | 3.96 | Y | Metro PCS |

Site Number: 302475

Code: ANSI/TIA-222-G

© 2007 - 2019 by ATC IP LLC. All rights reserved.

Site Name: Sttn - Southington, CT

Engineering Number: OAA713367_C3_07

1/4/2019 4:03:07 PM

Customer: CLEARWIRE

| | | | | | | | | | |
|------|--------|---|------------------------|------|------|---|------|---|-----------------------|
| 0.00 | 134.00 | 6 | 1 5/8" Coax | 1.98 | 0.82 | N | 0.00 | Y | Metro PCS |
| 0.00 | 120.00 | 4 | 1 1/4" Hybriflex Cable | 1.54 | 1.00 | N | 0.00 | Y | Clearwire Corporation |
| 0.00 | 120.00 | 1 | 1/2" Coax | 0.63 | 0.15 | N | 0.00 | Y | Clearwire Corporation |
| 0.00 | 120.00 | 2 | 2" conduit | 2.38 | 3.65 | N | 2.38 | Y | Clearwire Corporation |
| 0.00 | 105.00 | 6 | 7/8" Coax | 1.09 | 0.33 | N | 0.00 | Y | ITT Corporation |
| 0.00 | 82.50 | 4 | #20 Dywidag Bars | 2.72 | 0.00 | N | 1.70 | Y | - |

Additional Steel

| Elev From (ft) | Elev To (ft) | Qty | Description | Fy (ksi) | Offset (in) | Intermediate Connections | | | Connectors | Continuation? |
|----------------|--------------|-----|--------------------|----------|-------------|--------------------------|----------|------|-----------------|---------------|
| | | | | | Description | Spacing (in) | Len (in) | | | |
| 0.00 | 75.75 | 4 | SOL #20 All Thread | 80 | 2.19 | 6" Angle Bracket | 30.0 | 3.31 | 5/8" A36 U-Bolt | No |

Segment Properties (Max Len : 5. ft)

| Seg Top Elev (ft) | Description | Thick (in) | Flat Dia (in) | Area (in ²) | Ix (in ⁴) | W/t Ratio | D/t Ratio | F'y (ksi) | S (in ³) | Z (in ³) | Weight (lb) | Additional Reinforcing | | |
|-------------------|-----------------|------------|---------------|-------------------------|-----------------------|-----------|-----------|-----------|----------------------|----------------------|-------------|-------------------------|-----------------------|-------------|
| | | | | | | | | | | | | Area (in ²) | Ix (in ⁴) | Weight (lb) |
| 0.00 | | 0.3750 | 37.000 | 44.225 | 7,571.9 | 23.76 | 98.67 | 78.8 | 395.3 | 0.0 | 0.0 | 19.64 | 4,734 | 0.0 |
| 5.00 | | 0.3750 | 36.196 | 43.254 | 7,084.0 | 23.18 | 96.52 | 79.4 | 378.1 | 0.0 | 744.2 | 19.64 | 4,563 | 334.0 |
| 10.00 | | 0.3750 | 35.392 | 42.283 | 6,617.6 | 22.61 | 94.38 | 80.1 | 361.2 | 0.0 | 727.7 | 19.64 | 4,394 | 334.0 |
| 15.00 | | 0.3750 | 34.588 | 41.312 | 6,172.0 | 22.03 | 92.23 | 80.7 | 344.7 | 0.0 | 711.1 | 19.64 | 4,229 | 334.0 |
| 20.00 | | 0.3750 | 33.783 | 40.341 | 5,747.0 | 21.46 | 90.09 | 81.3 | 328.6 | 0.0 | 694.6 | 19.64 | 4,067 | 334.0 |
| 25.00 | | 0.3750 | 32.979 | 39.370 | 5,341.9 | 20.89 | 87.94 | 81.9 | 312.9 | 0.0 | 678.1 | 19.64 | 3,908 | 334.0 |
| 30.00 | | 0.3750 | 32.175 | 38.398 | 4,956.3 | 20.31 | 85.80 | 81.9 | 297.6 | 0.0 | 661.6 | 19.64 | 3,752 | 334.0 |
| 31.50 | Bot - Section 2 | 0.3750 | 31.934 | 38.107 | 4,844.3 | 20.14 | 85.16 | 81.9 | 293.1 | 0.0 | 195.2 | 19.64 | 3,706 | 100.2 |
| 35.00 | | 0.3750 | 31.371 | 37.427 | 4,589.7 | 19.74 | 83.66 | 81.9 | 282.6 | 0.0 | 832.9 | 19.64 | 3,718 | 233.8 |
| 35.67 | Top - Section 1 | 0.3125 | 31.889 | 31.773 | 4,043.6 | 24.66 | 102.04 | 77.8 | 245.0 | 0.0 | 157.0 | 19.64 | 3,697 | 44.5 |
| 40.00 | | 0.3125 | 31.192 | 31.072 | 3,781.7 | 24.07 | 99.81 | 78.5 | 234.2 | 0.0 | 463.3 | 19.64 | 3,566 | 289.5 |
| 45.00 | | 0.3125 | 30.388 | 30.263 | 3,493.9 | 23.38 | 97.24 | 79.2 | 222.1 | 0.0 | 521.8 | 19.64 | 3,417 | 334.0 |
| 50.00 | | 0.3125 | 29.583 | 29.454 | 3,221.0 | 22.69 | 94.67 | 80.0 | 210.3 | 0.0 | 508.0 | 19.64 | 3,271 | 334.0 |
| 55.00 | | 0.3125 | 28.779 | 28.645 | 2,962.8 | 22.00 | 92.09 | 80.7 | 198.9 | 0.0 | 494.2 | 19.64 | 3,129 | 334.0 |
| 60.00 | | 0.3125 | 27.975 | 27.835 | 2,718.7 | 21.31 | 89.52 | 81.5 | 187.7 | 0.0 | 480.5 | 19.64 | 2,990 | 334.0 |
| 65.00 | | 0.3125 | 27.171 | 27.026 | 2,488.5 | 20.62 | 86.95 | 81.9 | 176.9 | 0.0 | 466.7 | 19.64 | 2,854 | 334.0 |
| 70.00 | Bot - Section 3 | 0.3125 | 26.367 | 26.217 | 2,271.6 | 19.93 | 84.37 | 81.9 | 166.4 | 0.0 | 452.9 | 19.64 | 2,721 | 334.0 |
| 73.50 | Top - Section 2 | 0.2500 | 26.304 | 20.973 | 1,817.2 | 25.51 | 105.22 | 76.9 | 133.5 | 0.0 | 561.3 | 19.64 | 2,711 | 233.8 |
| 75.00 | | 0.2500 | 26.063 | 20.779 | 1,767.1 | 25.25 | 104.25 | 77.2 | 131.0 | 0.0 | 106.6 | 19.64 | 2,671 | 100.2 |
| 75.75 | Reinf. Top | 0.2500 | 25.942 | 20.682 | 1,742.5 | 25.12 | 103.77 | 77.3 | 129.8 | 0.0 | 52.9 | 19.64 | 2,652 | 50.1 |
| 80.00 | | 0.2500 | 25.258 | 20.132 | 1,607.1 | 24.39 | 101.03 | 78.1 | 122.9 | 0.0 | 295.1 | | | |
| 85.00 | | 0.2500 | 24.454 | 19.484 | 1,457.0 | 23.53 | 97.82 | 79.1 | 115.1 | 0.0 | 337.0 | | | |
| 90.00 | | 0.2500 | 23.650 | 18.837 | 1,316.5 | 22.67 | 94.60 | 80.0 | 107.5 | 0.0 | 326.0 | | | |
| 95.00 | | 0.2500 | 22.846 | 18.190 | 1,185.4 | 21.81 | 91.38 | 80.9 | 100.2 | 0.0 | 315.0 | | | |
| 100.0 | | 0.2500 | 22.042 | 17.542 | 1,063.3 | 20.94 | 88.17 | 81.9 | 93.2 | 0.0 | 304.0 | | | |
| 105.0 | | 0.2500 | 21.238 | 16.895 | 949.9 | 20.08 | 84.95 | 81.9 | 86.4 | 0.0 | 293.0 | | | |
| 110.0 | Top - Section 3 | 0.2500 | 20.433 | 16.248 | 844.8 | 19.22 | 81.73 | 81.9 | 79.9 | 0.0 | 281.9 | | | |
| 110.0 | Bot - Section 4 | 0.1875 | 20.433 | 12.223 | 639.5 | 26.52 | 108.98 | 75.8 | 60.5 | 0.0 | | | | |
| 115.0 | | 0.1875 | 19.629 | 11.738 | 566.3 | 25.37 | 104.69 | 77.0 | 55.7 | 0.0 | 203.8 | | | |
| 120.0 | | 0.1875 | 18.825 | 11.252 | 498.9 | 24.22 | 100.40 | 78.3 | 51.2 | 0.0 | 195.6 | | | |
| 125.0 | | 0.1875 | 18.021 | 10.767 | 437.1 | 23.07 | 96.11 | 79.5 | 46.9 | 0.0 | 187.3 | | | |
| 130.0 | | 0.1875 | 17.217 | 10.281 | 380.6 | 21.92 | 91.82 | 80.8 | 42.7 | 0.0 | 179.1 | | | |
| 134.0 | | 0.1875 | 16.573 | 9.893 | 339.0 | 21.00 | 88.39 | 81.8 | 39.5 | 0.0 | 137.3 | | | |
| 135.0 | | 0.1875 | 16.413 | 9.796 | 329.2 | 20.77 | 87.53 | 81.9 | 38.7 | 0.0 | 33.5 | | | |
| 140.0 | | 0.1875 | 15.608 | 9.310 | 282.6 | 19.63 | 83.24 | 81.9 | 35.0 | 0.0 | 162.5 | | | |
| 145.0 | | 0.1875 | 14.804 | 8.825 | 240.7 | 18.48 | 78.96 | 81.9 | 31.4 | 0.0 | 154.3 | | | |
| 150.0 | | 0.1875 | 14.000 | 8.339 | 203.1 | 17.33 | 74.67 | 81.9 | 28.0 | 0.0 | 146.0 | | | |
| | | | | | | | | | | | 13,062.0 | | | 5,060.1 |

| | | |
|-------------------------------|--------------------|------------------------------|
| Load Case: 1.2D + 1.6W | 97 mph with No Ice | 27 Iterations |
| Gust Response Factor :1.10 | | Wind Importance Factor :1.00 |
| Dead Load Factor :1.20 | | |
| Wind Load Factor :1.60 | | |

Applied Segment Forces Summary

| Seg Elev (ft) | Description | Shaft Forces | | Discrete Forces | | | Linear Forces | | Sum of Forces | | | | |
|---------------|-----------------|--------------|----------------|-----------------|--------------------|-------------------|----------------|--------------|----------------|--------------|----------------|--------------------|----------------|
| | | Wind FX (lb) | Dead Load (lb) | Wind FX (lb) | Torsion MY (lb-ft) | Moment MZ (lb-ft) | Dead Load (lb) | Wind FX (lb) | Dead Load (lb) | Wind FX (lb) | Dead Load (lb) | Torsion MY (lb-ft) | Moment MZ (lb) |
| 0.00 | | 266.0 | 0.0 | | | | | 0.0 | 0.0 | 266.0 | 0.0 | 0.0 | 0.0 |
| 5.00 | | 526.2 | 893.0 | | | | | 112.9 | 646.4 | 639.2 | 1,539.4 | 0.0 | 0.0 |
| 10.00 | | 514.6 | 873.2 | | | | | 112.9 | 646.4 | 627.5 | 1,519.6 | 0.0 | 0.0 |
| 15.00 | | 502.9 | 853.4 | | | | | 112.9 | 646.4 | 615.8 | 1,499.7 | 0.0 | 0.0 |
| 20.00 | | 491.2 | 833.5 | | | | | 112.9 | 646.4 | 604.1 | 1,479.9 | 0.0 | 0.0 |
| 25.00 | | 479.5 | 813.7 | | | | | 112.9 | 646.4 | 592.4 | 1,460.1 | 0.0 | 0.0 |
| 30.00 | | 307.3 | 793.9 | | | | | 112.9 | 646.4 | 420.2 | 1,440.3 | 0.0 | 0.0 |
| 31.50 | Bot - Section 2 | 239.7 | 234.3 | | | | | 34.1 | 193.9 | 273.9 | 428.2 | 0.0 | 0.0 |
| 35.00 | | 201.8 | 999.4 | | | | | 81.5 | 452.5 | 283.2 | 1,451.9 | 0.0 | 0.0 |
| 35.67 | Top - Section 1 | 245.0 | 188.4 | | | | | 15.8 | 86.2 | 260.8 | 274.5 | 0.0 | 0.0 |
| 40.00 | | 460.0 | 556.0 | | | | | 104.6 | 560.2 | 564.6 | 1,116.2 | 0.0 | 0.0 |
| 45.00 | | 496.2 | 626.1 | | | | | 124.8 | 646.4 | 621.1 | 1,272.5 | 0.0 | 0.0 |
| 50.00 | | 497.9 | 609.6 | | | | | 128.9 | 646.4 | 626.8 | 1,256.0 | 0.0 | 0.0 |
| 55.00 | | 497.8 | 593.1 | | | | | 132.6 | 646.4 | 630.4 | 1,239.5 | 0.0 | 0.0 |
| 60.00 | | 496.0 | 576.6 | | | | | 136.1 | 646.4 | 632.1 | 1,222.9 | 0.0 | 0.0 |
| 65.00 | | 493.0 | 560.0 | | | | | 139.4 | 646.4 | 632.3 | 1,206.4 | 0.0 | 0.0 |
| 70.00 | Bot - Section 3 | 419.2 | 543.5 | | | | | 142.5 | 646.4 | 561.7 | 1,189.9 | 0.0 | 0.0 |
| 73.50 | Top - Section 2 | 247.7 | 673.6 | | | | | 101.5 | 452.5 | 349.2 | 1,126.1 | 0.0 | 0.0 |
| 75.00 | | 111.0 | 127.9 | | | | | 43.9 | 193.9 | 154.9 | 321.8 | 0.0 | 0.0 |
| 75.75 | Reinf. Top | 244.8 | 63.5 | | | | | 22.1 | 97.0 | 266.9 | 160.4 | 0.0 | 0.0 |
| 80.00 | | 449.4 | 354.1 | | | | | 126.1 | 208.7 | 575.5 | 562.9 | 0.0 | 0.0 |
| 85.00 | | 479.0 | 404.4 | | | | | 134.9 | 245.6 | 614.0 | 650.0 | 0.0 | 0.0 |
| 90.00 | | 470.9 | 391.2 | | | | | 121.0 | 245.6 | 591.9 | 636.8 | 0.0 | 0.0 |
| 95.00 | | 462.0 | 378.0 | | | | | 122.9 | 245.6 | 584.9 | 623.6 | 0.0 | 0.0 |
| 100.00 | | 452.3 | 364.8 | | | | | 124.8 | 245.6 | 577.1 | 610.3 | 0.0 | 0.0 |
| 105.00 | Appurtenance(s) | 441.9 | 351.5 | 973.5 | 0.0 | 1,805.5 | 752.4 | 126.6 | 245.6 | 1,542.0 | 1,349.5 | 0.0 | 0.0 |
| 110.00 | Top - Section 3 | 430.9 | 338.3 | | | | | 128.1 | 233.7 | 559.0 | 572.0 | 0.0 | 0.0 |
| 115.00 | | 419.2 | 244.6 | | | | | 129.2 | 233.7 | 548.5 | 478.3 | 0.0 | 0.0 |
| 120.00 | Appurtenance(s) | 407.0 | 234.7 | 1,918.6 | 0.0 | 0.0 | 1,318.4 | 130.4 | 233.7 | 2,455.9 | 1,786.8 | 0.0 | 0.0 |
| 125.00 | | 394.2 | 224.8 | | | | | 81.4 | 165.0 | 475.6 | 389.8 | 0.0 | 0.0 |
| 130.00 | | 344.0 | 214.9 | | | | | 81.9 | 165.0 | 425.9 | 379.9 | 0.0 | 0.0 |
| 134.00 | Appurtenance(s) | 180.9 | 164.8 | 1,269.0 | 0.0 | 0.0 | 622.8 | 65.8 | 132.0 | 1,515.7 | 919.6 | 0.0 | 0.0 |
| 135.00 | | 180.7 | 40.2 | | | | | 0.0 | 21.2 | 180.7 | 61.4 | 0.0 | 0.0 |
| 140.00 | | 293.9 | 195.0 | | | | | 0.0 | 106.0 | 293.9 | 301.0 | 0.0 | 0.0 |
| 145.00 | | 281.5 | 185.1 | | | | | 0.0 | 106.0 | 281.5 | 291.1 | 0.0 | 0.0 |
| 150.00 | Appurtenance(s) | 137.6 | 175.2 | 3,184.5 | 0.0 | 7,323.9 | 4,036.8 | 0.0 | 106.0 | 3,322.1 | 4,318.0 | 0.0 | 0.0 |
| Totals: | | | | | | | | | | 24,167.0 | 35,136.2 | 0.00 | 0.00 |

Load Case: 1.2D + 1.6W

97 mph with No Ice

27 Iterations

Gust Response Factor :1.10

Wind Importance Factor :1.00

Dead Load Factor :1.20

Wind Load Factor :1.60

Calculated Forces

| Seg Elev (ft) | Pu FY (-) (kips) | Vu FX (-) (kips) | Tu MY (ft-kips) | Mu MZ (ft-kips) | Mu MX (ft-kips) | Resultant Moment (ft-kips) | phi Pn (kips) | phi Vn (kips) | phi Tn (ft-kips) | phi Mn (ft-kips) | Total Deflect (in) | Rotation (deg) | Ratio |
|---------------|------------------|------------------|-----------------|-----------------|-----------------|----------------------------|---------------|---------------|------------------|------------------|--------------------|----------------|-------|
| 0.00 | -35.08 | -23.98 | 0.00 | -2,279.16 | 0.00 | 2,279.16 | 3,136.53 | 1,568.27 | 4,731.25 | 2,336.59 | 0.00 | 0.00 | 0.608 |
| 5.00 | -33.44 | -23.49 | 0.00 | -2,159.26 | 0.00 | 2,159.26 | 3,092.06 | 1,546.03 | 4,560.72 | 2,252.37 | 0.14 | -0.26 | 0.591 |
| 10.00 | -31.82 | -22.99 | 0.00 | -2,041.82 | 0.00 | 2,041.82 | 3,046.49 | 1,523.25 | 4,391.58 | 2,168.84 | 0.54 | -0.51 | 0.573 |
| 15.00 | -30.23 | -22.50 | 0.00 | -1,926.86 | 0.00 | 1,926.86 | 2,999.83 | 1,499.91 | 4,223.96 | 2,086.05 | 1.22 | -0.77 | 0.555 |
| 20.00 | -28.66 | -22.00 | 0.00 | -1,814.38 | 0.00 | 1,814.38 | 2,952.07 | 1,476.04 | 4,057.95 | 2,004.07 | 2.16 | -1.03 | 0.537 |
| 25.00 | -27.12 | -21.50 | 0.00 | -1,704.40 | 0.00 | 1,704.40 | 2,901.93 | 1,450.96 | 3,891.94 | 1,922.08 | 3.37 | -1.28 | 0.519 |
| 30.00 | -25.63 | -21.11 | 0.00 | -1,596.92 | 0.00 | 1,596.92 | 2,830.35 | 1,415.18 | 3,701.25 | 1,827.91 | 4.85 | -1.53 | 0.503 |
| 31.50 | -25.16 | -20.88 | 0.00 | -1,565.25 | 0.00 | 1,565.25 | 2,808.88 | 1,404.44 | 3,644.98 | 1,800.12 | 5.35 | -1.61 | 0.499 |
| 35.00 | -23.68 | -20.60 | 0.00 | -1,492.16 | 0.00 | 1,492.16 | 2,758.78 | 1,379.39 | 3,515.36 | 1,736.10 | 6.59 | -1.79 | 0.481 |
| 35.67 | -23.37 | -20.38 | 0.00 | -1,478.42 | 0.00 | 1,478.42 | 2,225.24 | 1,112.62 | 2,894.88 | 1,429.67 | 6.85 | -1.82 | 0.547 |
| 40.00 | -22.19 | -19.87 | 0.00 | -1,390.09 | 0.00 | 1,390.09 | 2,194.35 | 1,097.17 | 2,791.07 | 1,378.40 | 8.60 | -2.04 | 0.526 |
| 45.00 | -20.85 | -19.30 | 0.00 | -1,290.73 | 0.00 | 1,290.73 | 2,157.69 | 1,078.84 | 2,672.25 | 1,319.72 | 10.87 | -2.30 | 0.501 |
| 50.00 | -19.54 | -18.71 | 0.00 | -1,194.23 | 0.00 | 1,194.23 | 2,119.93 | 1,059.96 | 2,554.56 | 1,261.60 | 13.42 | -2.55 | 0.475 |
| 55.00 | -18.26 | -18.10 | 0.00 | -1,100.70 | 0.00 | 1,100.70 | 2,081.07 | 1,040.54 | 2,438.12 | 1,204.10 | 16.23 | -2.80 | 0.450 |
| 60.00 | -16.99 | -17.48 | 0.00 | -1,010.21 | 0.00 | 1,010.21 | 2,041.12 | 1,020.56 | 2,323.03 | 1,147.26 | 19.30 | -3.05 | 0.425 |
| 65.00 | -15.75 | -16.84 | 0.00 | -922.83 | 0.00 | 922.83 | 1,992.10 | 996.05 | 2,200.59 | 1,086.79 | 22.62 | -3.29 | 0.400 |
| 70.00 | -14.54 | -16.26 | 0.00 | -838.61 | 0.00 | 838.61 | 1,932.46 | 966.23 | 2,070.05 | 1,022.32 | 26.19 | -3.53 | 0.378 |
| 73.50 | -13.41 | -15.87 | 0.00 | -781.69 | 0.00 | 781.69 | 1,451.36 | 725.68 | 1,558.37 | 769.62 | 28.84 | -3.69 | 0.413 |
| 75.00 | -13.09 | -15.71 | 0.00 | -757.88 | 0.00 | 757.88 | 1,443.19 | 721.60 | 1,535.11 | 758.14 | 30.01 | -3.76 | 0.403 |
| 75.75 | -12.91 | -15.46 | 0.00 | -746.10 | 0.00 | 746.10 | 1,439.07 | 719.54 | 1,523.51 | 752.40 | 30.60 | -3.79 | 0.398 |
| 75.75 | -12.91 | -15.46 | 0.00 | -746.10 | 0.00 | 746.10 | 1,439.07 | 719.54 | 1,523.51 | 752.40 | 30.60 | -3.79 | 1.001 |
| 80.00 | -12.29 | -14.93 | 0.00 | -680.42 | 0.00 | 680.42 | 1,415.26 | 707.63 | 1,458.06 | 720.08 | 34.06 | -3.99 | 0.954 |
| 85.00 | -11.54 | -14.38 | 0.00 | -605.78 | 0.00 | 605.78 | 1,386.24 | 693.12 | 1,381.78 | 682.41 | 38.54 | -4.56 | 0.896 |
| 90.00 | -10.83 | -13.84 | 0.00 | -533.88 | 0.00 | 533.88 | 1,356.12 | 678.06 | 1,306.38 | 645.17 | 43.61 | -5.11 | 0.836 |
| 95.00 | -10.14 | -13.29 | 0.00 | -464.68 | 0.00 | 464.68 | 1,324.90 | 662.45 | 1,231.99 | 608.43 | 49.25 | -5.65 | 0.772 |
| 100.00 | -9.48 | -12.74 | 0.00 | -398.21 | 0.00 | 398.21 | 1,293.04 | 646.52 | 1,159.10 | 572.44 | 55.44 | -6.17 | 0.703 |
| 105.00 | -8.22 | -11.13 | 0.00 | -332.69 | 0.00 | 332.69 | 1,245.33 | 622.66 | 1,074.67 | 530.74 | 62.16 | -6.66 | 0.634 |
| 110.00 | -7.64 | -10.56 | 0.00 | -277.06 | 0.00 | 277.06 | 1,197.61 | 598.80 | 993.42 | 490.61 | 69.36 | -7.12 | 0.571 |
| 110.00 | -7.64 | -10.56 | 0.00 | -277.06 | 0.00 | 277.06 | 833.77 | 416.88 | 695.90 | 343.68 | 69.36 | -7.12 | 0.816 |
| 115.00 | -7.15 | -10.01 | 0.00 | -224.26 | 0.00 | 224.26 | 813.89 | 406.95 | 652.08 | 322.04 | 77.03 | -7.54 | 0.706 |
| 120.00 | -5.66 | -7.39 | 0.00 | -174.18 | 0.00 | 174.18 | 792.92 | 396.46 | 608.75 | 300.64 | 85.17 | -8.04 | 0.587 |
| 125.00 | -5.29 | -6.90 | 0.00 | -137.25 | 0.00 | 137.25 | 770.85 | 385.43 | 566.02 | 279.54 | 93.81 | -8.48 | 0.498 |
| 130.00 | -4.94 | -6.45 | 0.00 | -102.77 | 0.00 | 102.77 | 747.69 | 373.84 | 524.00 | 258.78 | 102.87 | -8.88 | 0.404 |
| 134.00 | -4.26 | -4.82 | 0.00 | -76.97 | 0.00 | 76.97 | 728.37 | 364.19 | 490.97 | 242.47 | 110.40 | -9.14 | 0.323 |
| 135.00 | -4.21 | -4.64 | 0.00 | -72.16 | 0.00 | 72.16 | 722.05 | 361.03 | 481.88 | 237.98 | 112.31 | -9.21 | 0.309 |
| 140.00 | -3.95 | -4.32 | 0.00 | -48.94 | 0.00 | 48.94 | 686.26 | 343.13 | 435.03 | 214.85 | 122.06 | -9.47 | 0.234 |
| 145.00 | -3.69 | -4.00 | 0.00 | -27.34 | 0.00 | 27.34 | 650.48 | 325.24 | 390.59 | 192.90 | 132.04 | -9.66 | 0.148 |
| 150.00 | 0.00 | -3.32 | 0.00 | -7.32 | 0.00 | 7.32 | 614.69 | 307.34 | 348.53 | 172.13 | 142.17 | -9.76 | 0.043 |

| | | |
|-------------------------------|---------------------------------|------------------------------|
| Load Case: 0.9D + 1.6W | 97 mph with No Ice (Reduced DL) | 27 Iterations |
| Gust Response Factor :1.10 | | Wind Importance Factor :1.00 |
| Dead Load Factor :0.90 | | |
| Wind Load Factor :1.60 | | |

Applied Segment Forces Summary

| Seg Elev (ft) | Description | Shaft Forces | | Discrete Forces | | | Linear Forces | | Sum of Forces | | | | |
|---------------|-----------------|--------------|----------------|-----------------|--------------------|-------------------|----------------|--------------|----------------|--------------|----------------|--------------------|----------------|
| | | Wind FX (lb) | Dead Load (lb) | Wind FX (lb) | Torsion MY (lb-ft) | Moment MZ (lb-ft) | Dead Load (lb) | Wind FX (lb) | Dead Load (lb) | Wind FX (lb) | Dead Load (lb) | Torsion MY (lb-ft) | Moment MZ (lb) |
| 0.00 | | 266.0 | 0.0 | | | | | 0.0 | 0.0 | 266.0 | 0.0 | 0.0 | 0.0 |
| 5.00 | | 526.2 | 669.8 | | | | | 112.9 | 484.8 | 639.2 | 1,154.5 | 0.0 | 0.0 |
| 10.00 | | 514.6 | 654.9 | | | | | 112.9 | 484.8 | 627.5 | 1,139.7 | 0.0 | 0.0 |
| 15.00 | | 502.9 | 640.0 | | | | | 112.9 | 484.8 | 615.8 | 1,124.8 | 0.0 | 0.0 |
| 20.00 | | 491.2 | 625.1 | | | | | 112.9 | 484.8 | 604.1 | 1,109.9 | 0.0 | 0.0 |
| 25.00 | | 479.5 | 610.3 | | | | | 112.9 | 484.8 | 592.4 | 1,095.1 | 0.0 | 0.0 |
| 30.00 | | 307.3 | 595.4 | | | | | 112.9 | 484.8 | 420.2 | 1,080.2 | 0.0 | 0.0 |
| 31.50 | Bot - Section 2 | 239.7 | 175.7 | | | | | 34.1 | 145.4 | 273.9 | 321.2 | 0.0 | 0.0 |
| 35.00 | | 201.8 | 749.6 | | | | | 81.5 | 339.3 | 283.2 | 1,088.9 | 0.0 | 0.0 |
| 35.67 | Top - Section 1 | 245.0 | 141.3 | | | | | 15.8 | 64.6 | 260.8 | 205.9 | 0.0 | 0.0 |
| 40.00 | | 460.0 | 417.0 | | | | | 104.6 | 420.1 | 564.6 | 837.2 | 0.0 | 0.0 |
| 45.00 | | 496.2 | 469.6 | | | | | 124.8 | 484.8 | 621.1 | 954.4 | 0.0 | 0.0 |
| 50.00 | | 497.9 | 457.2 | | | | | 128.9 | 484.8 | 626.8 | 942.0 | 0.0 | 0.0 |
| 55.00 | | 497.8 | 444.8 | | | | | 132.6 | 484.8 | 630.4 | 929.6 | 0.0 | 0.0 |
| 60.00 | | 496.0 | 432.4 | | | | | 136.1 | 484.8 | 632.1 | 917.2 | 0.0 | 0.0 |
| 65.00 | | 493.0 | 420.0 | | | | | 139.4 | 484.8 | 632.3 | 904.8 | 0.0 | 0.0 |
| 70.00 | Bot - Section 3 | 419.2 | 407.6 | | | | | 142.5 | 484.8 | 561.7 | 892.4 | 0.0 | 0.0 |
| 73.50 | Top - Section 2 | 247.7 | 505.2 | | | | | 101.5 | 339.3 | 349.2 | 844.6 | 0.0 | 0.0 |
| 75.00 | | 111.0 | 95.9 | | | | | 43.9 | 145.4 | 154.9 | 241.3 | 0.0 | 0.0 |
| 75.75 | Reinf. Top | 244.8 | 47.6 | | | | | 22.1 | 72.7 | 266.9 | 120.3 | 0.0 | 0.0 |
| 80.00 | | 449.4 | 265.6 | | | | | 126.1 | 156.6 | 575.5 | 422.2 | 0.0 | 0.0 |
| 85.00 | | 479.0 | 303.3 | | | | | 134.9 | 184.2 | 614.0 | 487.5 | 0.0 | 0.0 |
| 90.00 | | 470.9 | 293.4 | | | | | 121.0 | 184.2 | 591.9 | 477.6 | 0.0 | 0.0 |
| 95.00 | | 462.0 | 283.5 | | | | | 122.9 | 184.2 | 584.9 | 467.7 | 0.0 | 0.0 |
| 100.00 | | 452.3 | 273.6 | | | | | 124.8 | 184.2 | 577.1 | 457.8 | 0.0 | 0.0 |
| 105.00 | Appurtenance(s) | 441.9 | 263.7 | 973.5 | 0.0 | 1,805.5 | 564.3 | 126.6 | 184.2 | 1,542.0 | 1,012.1 | 0.0 | 0.0 |
| 110.00 | Top - Section 3 | 430.9 | 253.7 | | | | | 128.1 | 175.3 | 559.0 | 429.0 | 0.0 | 0.0 |
| 115.00 | | 419.2 | 183.5 | | | | | 129.2 | 175.3 | 548.5 | 358.7 | 0.0 | 0.0 |
| 120.00 | Appurtenance(s) | 407.0 | 176.0 | 1,918.6 | 0.0 | 0.0 | 988.8 | 130.4 | 175.3 | 2,455.9 | 1,340.1 | 0.0 | 0.0 |
| 125.00 | | 394.2 | 168.6 | | | | | 81.4 | 123.7 | 475.6 | 292.3 | 0.0 | 0.0 |
| 130.00 | | 344.0 | 161.2 | | | | | 81.9 | 123.7 | 425.9 | 284.9 | 0.0 | 0.0 |
| 134.00 | Appurtenance(s) | 180.9 | 123.6 | 1,269.0 | 0.0 | 0.0 | 467.1 | 65.8 | 99.0 | 1,515.7 | 689.7 | 0.0 | 0.0 |
| 135.00 | | 180.7 | 30.1 | | | | | 0.0 | 15.9 | 180.7 | 46.0 | 0.0 | 0.0 |
| 140.00 | | 293.9 | 146.3 | | | | | 0.0 | 79.5 | 293.9 | 225.8 | 0.0 | 0.0 |
| 145.00 | | 281.5 | 138.8 | | | | | 0.0 | 79.5 | 281.5 | 218.3 | 0.0 | 0.0 |
| 150.00 | Appurtenance(s) | 137.6 | 131.4 | 3,184.5 | 0.0 | 7,323.9 | 3,027.6 | 0.0 | 79.5 | 3,322.1 | 3,238.5 | 0.0 | 0.0 |
| Totals: | | | | | | | | | | 24,167.0 | 26,352.2 | 0.00 | 0.00 |

Load Case: 0.9D + 1.6W

97 mph with No Ice (Reduced DL)

27 Iterations

Gust Response Factor :1.10

Wind Importance Factor :1.00

Dead Load Factor :0.90

Wind Load Factor :1.60

Calculated Forces

| Seg Elev (ft) | Pu FY (-) (kips) | Vu FX (-) (kips) | Tu MY (ft-kips) | Mu MZ (ft-kips) | Mu MX (ft-kips) | Resultant Moment (ft-kips) | phi Pn (kips) | phi Vn (kips) | phi Tn (ft-kips) | phi Mn (ft-kips) | Total Deflect (in) | Rotation (deg) | Ratio |
|---------------|------------------|------------------|-----------------|-----------------|-----------------|----------------------------|---------------|---------------|------------------|------------------|--------------------|----------------|-------|
| 0.00 | -26.30 | -23.96 | 0.00 | -2,245.15 | 0.00 | 2,245.15 | 3,136.53 | 1,568.27 | 4,731.25 | 2,336.59 | 0.00 | 0.00 | 0.597 |
| 5.00 | -25.04 | -23.43 | 0.00 | -2,125.35 | 0.00 | 2,125.35 | 3,092.06 | 1,546.03 | 4,560.72 | 2,252.37 | 0.14 | -0.25 | 0.580 |
| 10.00 | -23.81 | -22.90 | 0.00 | -2,008.21 | 0.00 | 2,008.21 | 3,046.49 | 1,523.25 | 4,391.58 | 2,168.84 | 0.54 | -0.51 | 0.562 |
| 15.00 | -22.59 | -22.37 | 0.00 | -1,893.72 | 0.00 | 1,893.72 | 2,999.83 | 1,499.91 | 4,223.96 | 2,086.05 | 1.20 | -0.76 | 0.544 |
| 20.00 | -21.39 | -21.84 | 0.00 | -1,781.87 | 0.00 | 1,781.87 | 2,952.07 | 1,476.04 | 4,057.95 | 2,004.07 | 2.13 | -1.01 | 0.526 |
| 25.00 | -20.22 | -21.32 | 0.00 | -1,672.65 | 0.00 | 1,672.65 | 2,901.93 | 1,450.96 | 3,891.94 | 1,922.08 | 3.32 | -1.26 | 0.507 |
| 30.00 | -19.09 | -20.92 | 0.00 | -1,566.07 | 0.00 | 1,566.07 | 2,830.35 | 1,415.18 | 3,701.25 | 1,827.91 | 4.77 | -1.51 | 0.492 |
| 31.50 | -18.73 | -20.68 | 0.00 | -1,534.68 | 0.00 | 1,534.68 | 2,808.88 | 1,404.44 | 3,644.98 | 1,800.12 | 5.26 | -1.58 | 0.488 |
| 35.00 | -17.61 | -20.40 | 0.00 | -1,462.29 | 0.00 | 1,462.29 | 2,758.78 | 1,379.39 | 3,515.36 | 1,736.10 | 6.48 | -1.76 | 0.470 |
| 35.67 | -17.37 | -20.17 | 0.00 | -1,448.69 | 0.00 | 1,448.69 | 2,225.24 | 1,112.62 | 2,894.88 | 1,429.67 | 6.73 | -1.79 | 0.534 |
| 40.00 | -16.48 | -19.65 | 0.00 | -1,361.29 | 0.00 | 1,361.29 | 2,194.35 | 1,097.17 | 2,791.07 | 1,378.40 | 8.46 | -2.00 | 0.513 |
| 45.00 | -15.46 | -19.06 | 0.00 | -1,263.06 | 0.00 | 1,263.06 | 2,157.69 | 1,078.84 | 2,672.25 | 1,319.72 | 10.69 | -2.26 | 0.488 |
| 50.00 | -14.47 | -18.46 | 0.00 | -1,167.77 | 0.00 | 1,167.77 | 2,119.93 | 1,059.96 | 2,554.56 | 1,261.60 | 13.19 | -2.51 | 0.464 |
| 55.00 | -13.49 | -17.84 | 0.00 | -1,075.50 | 0.00 | 1,075.50 | 2,081.07 | 1,040.54 | 2,438.12 | 1,204.10 | 15.94 | -2.75 | 0.439 |
| 60.00 | -12.53 | -17.22 | 0.00 | -986.30 | 0.00 | 986.30 | 2,041.12 | 1,020.56 | 2,323.03 | 1,147.26 | 18.95 | -2.99 | 0.413 |
| 65.00 | -11.60 | -16.58 | 0.00 | -900.22 | 0.00 | 900.22 | 1,992.10 | 996.05 | 2,200.59 | 1,086.79 | 22.21 | -3.23 | 0.389 |
| 70.00 | -10.69 | -16.00 | 0.00 | -817.31 | 0.00 | 817.31 | 1,932.46 | 966.23 | 2,070.05 | 1,022.32 | 25.71 | -3.46 | 0.367 |
| 73.50 | -9.84 | -15.62 | 0.00 | -761.30 | 0.00 | 761.30 | 1,451.36 | 725.68 | 1,558.37 | 769.62 | 28.31 | -3.61 | 0.401 |
| 75.00 | -9.59 | -15.46 | 0.00 | -737.86 | 0.00 | 737.86 | 1,443.19 | 721.60 | 1,535.11 | 758.14 | 29.45 | -3.68 | 0.391 |
| 75.75 | -9.46 | -15.21 | 0.00 | -726.27 | 0.00 | 726.27 | 1,439.07 | 719.54 | 1,523.51 | 752.40 | 30.03 | -3.71 | 0.387 |
| 75.75 | -9.46 | -15.21 | 0.00 | -726.27 | 0.00 | 726.27 | 1,439.07 | 719.54 | 1,523.51 | 752.40 | 30.03 | -3.71 | 0.972 |
| 80.00 | -8.98 | -14.66 | 0.00 | -661.64 | 0.00 | 661.64 | 1,415.26 | 707.63 | 1,458.06 | 720.08 | 33.43 | -3.91 | 0.926 |
| 85.00 | -8.40 | -14.10 | 0.00 | -588.32 | 0.00 | 588.32 | 1,386.24 | 693.12 | 1,381.78 | 682.41 | 37.81 | -4.46 | 0.869 |
| 90.00 | -7.85 | -13.54 | 0.00 | -517.84 | 0.00 | 517.84 | 1,356.12 | 678.06 | 1,306.38 | 645.17 | 42.76 | -5.00 | 0.809 |
| 95.00 | -7.32 | -12.98 | 0.00 | -450.14 | 0.00 | 450.14 | 1,324.90 | 662.45 | 1,231.99 | 608.43 | 48.28 | -5.52 | 0.746 |
| 100.00 | -6.82 | -12.42 | 0.00 | -385.24 | 0.00 | 385.24 | 1,293.04 | 646.52 | 1,159.10 | 572.44 | 54.32 | -6.02 | 0.679 |
| 105.00 | -5.90 | -10.82 | 0.00 | -321.34 | 0.00 | 321.34 | 1,245.33 | 622.66 | 1,074.67 | 530.74 | 60.87 | -6.50 | 0.610 |
| 110.00 | -5.46 | -10.26 | 0.00 | -267.22 | 0.00 | 267.22 | 1,197.61 | 598.80 | 993.42 | 490.61 | 67.90 | -6.94 | 0.550 |
| 110.00 | -5.46 | -10.26 | 0.00 | -267.22 | 0.00 | 267.22 | 833.77 | 416.88 | 695.90 | 343.68 | 67.90 | -6.94 | 0.785 |
| 115.00 | -5.10 | -9.71 | 0.00 | -215.93 | 0.00 | 215.93 | 813.89 | 406.95 | 652.08 | 322.04 | 75.37 | -7.34 | 0.677 |
| 120.00 | -4.04 | -7.13 | 0.00 | -167.38 | 0.00 | 167.38 | 792.92 | 396.46 | 608.75 | 300.64 | 83.30 | -7.83 | 0.562 |
| 125.00 | -3.77 | -6.65 | 0.00 | -131.72 | 0.00 | 131.72 | 770.85 | 385.43 | 566.02 | 279.54 | 91.70 | -8.25 | 0.476 |
| 130.00 | -3.51 | -6.20 | 0.00 | -98.50 | 0.00 | 98.50 | 747.69 | 373.84 | 524.00 | 258.78 | 100.52 | -8.63 | 0.386 |
| 134.00 | -3.05 | -4.61 | 0.00 | -73.69 | 0.00 | 73.69 | 728.37 | 364.19 | 490.97 | 242.47 | 107.84 | -8.88 | 0.308 |
| 135.00 | -3.02 | -4.43 | 0.00 | -69.09 | 0.00 | 69.09 | 722.05 | 361.03 | 481.88 | 237.98 | 109.70 | -8.94 | 0.295 |
| 140.00 | -2.83 | -4.11 | 0.00 | -46.94 | 0.00 | 46.94 | 686.26 | 343.13 | 435.03 | 214.85 | 119.16 | -9.20 | 0.223 |
| 145.00 | -2.65 | -3.81 | 0.00 | -26.36 | 0.00 | 26.36 | 650.48 | 325.24 | 390.59 | 192.90 | 128.86 | -9.38 | 0.141 |
| 150.00 | 0.00 | -3.32 | 0.00 | -7.32 | 0.00 | 7.32 | 614.69 | 307.34 | 348.53 | 172.13 | 138.70 | -9.48 | 0.043 |

| | | |
|--|--------------------------------|------------------------------|
| Load Case: 1.2D + 1.0Di + 1.0Wi | 50 mph with 1.00 in Radial Ice | 27 Iterations |
| Gust Response Factor :1.10 | Ice Dead Load Factor :1.00 | Wind Importance Factor :1.00 |
| Dead Load Factor :1.20 | | Ice Importance Factor :1.00 |
| Wind Load Factor :1.00 | | |

Applied Segment Forces Summary

| Seg Elev (ft) | Description | Shaft Forces | | Discrete Forces | | | Linear Forces | | Sum of Forces | | | | |
|---------------|-----------------|--------------|----------------|-----------------|--------------------|-------------------|----------------|--------------|----------------|--------------|----------------|--------------------|----------------|
| | | Wind FX (lb) | Dead Load (lb) | Wind FX (lb) | Torsion MY (lb-ft) | Moment MZ (lb-ft) | Dead Load (lb) | Wind FX (lb) | Dead Load (lb) | Wind FX (lb) | Dead Load (lb) | Torsion MY (lb-ft) | Moment MZ (lb) |
| 0.00 | | 48.0 | 0.0 | | | | | 0.0 | 0.0 | 48.0 | 0.0 | 0.0 | 0.0 |
| 5.00 | | 95.4 | 1,270.5 | | | | | 40.5 | 1,109.1 | 135.9 | 2,379.6 | 0.0 | 0.0 |
| 10.00 | | 94.1 | 1,287.4 | | | | | 43.0 | 1,171.0 | 137.1 | 2,458.4 | 0.0 | 0.0 |
| 15.00 | | 92.5 | 1,280.9 | | | | | 44.3 | 1,203.2 | 136.8 | 2,484.1 | 0.0 | 0.0 |
| 20.00 | | 90.8 | 1,266.6 | | | | | 45.2 | 1,225.8 | 136.0 | 2,492.4 | 0.0 | 0.0 |
| 25.00 | | 89.0 | 1,248.4 | | | | | 45.9 | 1,243.3 | 134.9 | 2,491.7 | 0.0 | 0.0 |
| 30.00 | | 57.2 | 1,227.6 | | | | | 46.4 | 1,257.8 | 103.6 | 2,485.4 | 0.0 | 0.0 |
| 31.50 | Bot - Section 2 | 44.7 | 365.0 | | | | | 14.1 | 379.8 | 58.9 | 744.9 | 0.0 | 0.0 |
| 35.00 | | 37.7 | 1,307.6 | | | | | 33.9 | 890.3 | 71.5 | 2,197.9 | 0.0 | 0.0 |
| 35.67 | Top - Section 1 | 45.9 | 247.2 | | | | | 6.6 | 170.2 | 52.5 | 417.4 | 0.0 | 0.0 |
| 40.00 | | 86.4 | 933.6 | | | | | 43.8 | 1,110.8 | 130.2 | 2,044.4 | 0.0 | 0.0 |
| 45.00 | | 93.6 | 1,056.5 | | | | | 52.7 | 1,290.7 | 146.2 | 2,347.2 | 0.0 | 0.0 |
| 50.00 | | 94.3 | 1,034.3 | | | | | 54.7 | 1,299.5 | 149.0 | 2,333.8 | 0.0 | 0.0 |
| 55.00 | | 94.7 | 1,011.4 | | | | | 56.7 | 1,307.5 | 151.3 | 2,318.9 | 0.0 | 0.0 |
| 60.00 | | 94.8 | 987.9 | | | | | 58.5 | 1,314.9 | 153.3 | 2,302.8 | 0.0 | 0.0 |
| 65.00 | | 94.7 | 964.0 | | | | | 60.2 | 1,321.7 | 154.9 | 2,285.7 | 0.0 | 0.0 |
| 70.00 | Bot - Section 3 | 80.8 | 939.6 | | | | | 61.8 | 1,328.1 | 142.6 | 2,267.7 | 0.0 | 0.0 |
| 73.50 | Top - Section 2 | 47.8 | 952.1 | | | | | 44.2 | 933.2 | 92.0 | 1,885.3 | 0.0 | 0.0 |
| 75.00 | | 21.5 | 246.6 | | | | | 19.2 | 400.8 | 40.6 | 647.5 | 0.0 | 0.0 |
| 75.75 | Reinf. Top | 47.5 | 122.7 | | | | | 9.6 | 200.6 | 57.1 | 323.3 | 0.0 | 0.0 |
| 80.00 | | 87.5 | 682.7 | | | | | 55.2 | 798.5 | 142.7 | 1,481.2 | 0.0 | 0.0 |
| 85.00 | | 93.7 | 781.9 | | | | | 56.8 | 877.1 | 150.5 | 1,659.0 | 0.0 | 0.0 |
| 90.00 | | 92.7 | 759.6 | | | | | 48.2 | 814.1 | 140.9 | 1,573.7 | 0.0 | 0.0 |
| 95.00 | | 91.5 | 737.1 | | | | | 49.2 | 818.0 | 140.6 | 1,555.1 | 0.0 | 0.0 |
| 100.00 | | 90.2 | 714.3 | | | | | 50.1 | 821.9 | 140.2 | 1,536.2 | 0.0 | 0.0 |
| 105.00 | Appurtenance(s) | 88.7 | 691.3 | 305.5 | 0.0 | 449.0 | 1,807.5 | 50.9 | 825.5 | 445.1 | 3,324.3 | 0.0 | 0.0 |
| 110.00 | Top - Section 3 | 87.1 | 668.2 | | | | | 51.8 | 726.0 | 138.9 | 1,394.1 | 0.0 | 0.0 |
| 115.00 | | 85.5 | 564.3 | | | | | 52.6 | 728.8 | 138.0 | 1,293.1 | 0.0 | 0.0 |
| 120.00 | Appurtenance(s) | 83.7 | 544.1 | 426.4 | 0.0 | 0.0 | 4,798.3 | 53.4 | 731.5 | 563.5 | 6,073.9 | 0.0 | 0.0 |
| 125.00 | | 81.8 | 523.7 | | | | | 29.8 | 458.9 | 111.6 | 982.6 | 0.0 | 0.0 |
| 130.00 | | 72.0 | 503.2 | | | | | 30.2 | 460.2 | 102.3 | 963.4 | 0.0 | 0.0 |
| 134.00 | Appurtenance(s) | 39.4 | 388.6 | 316.0 | 0.0 | 0.0 | 1,267.0 | 24.5 | 369.1 | 379.9 | 2,024.8 | 0.0 | 0.0 |
| 135.00 | | 46.1 | 95.8 | | | | | 0.0 | 21.2 | 46.1 | 117.0 | 0.0 | 0.0 |
| 140.00 | | 75.6 | 461.7 | | | | | 0.0 | 106.0 | 75.6 | 567.7 | 0.0 | 0.0 |
| 145.00 | | 73.4 | 440.8 | | | | | 0.0 | 106.0 | 73.4 | 546.8 | 0.0 | 0.0 |
| 150.00 | Appurtenance(s) | 36.1 | 419.8 | 904.4 | 0.0 | 1,905.0 | 11,376.4 | 0.0 | 106.0 | 940.5 | 11,902.2 | 0.0 | 0.0 |
| Totals: | | | | | | | | | | 5,962.24 | 73,903.4 | 0.00 | 0.00 |

Site Number: 302475

Code: ANSI/TIA-222-G

© 2007 - 2019 by ATC IP LLC. All rights reserved.

Site Name: Sttn - Southington, CT

Engineering Number: OAA713367_C3_07

1/4/2019 4:03:21 PM

Customer: CLEARWIRE

Load Case: 1.2D + 1.0Di + 1.0Wi

50 mph with 1.00 in Radial Ice

27 Iterations

Gust Response Factor :1.10

Ice Dead Load Factor :1.00

Wind Importance Factor :1.00

Dead Load Factor :1.20

Ice Importance Factor :1.00

Wind Load Factor :1.00

Calculated Forces

| Seg Elev (ft) | Pu FY (-) (kips) | Vu FX (-) (kips) | Tu MY (ft-kips) | Mu MZ (ft-kips) | Mu MX (ft-kips) | Resultant Moment (ft-kips) | phi Pn (kips) | phi Vn (kips) | phi Tn (ft-kips) | phi Mn (ft-kips) | Total Deflect (in) | Rotation (deg) | Ratio |
|---------------|------------------|------------------|-----------------|-----------------|-----------------|----------------------------|---------------|---------------|------------------|------------------|--------------------|----------------|-------|
| 0.00 | -73.90 | -5.96 | 0.00 | -650.15 | 0.00 | 650.15 | 3,136.53 | 1,568.27 | 4,731.25 | 2,336.59 | 0.00 | 0.00 | 0.188 |
| 5.00 | -71.51 | -5.92 | 0.00 | -620.34 | 0.00 | 620.34 | 3,092.06 | 1,546.03 | 4,560.72 | 2,252.37 | 0.04 | -0.07 | 0.183 |
| 10.00 | -69.05 | -5.86 | 0.00 | -590.76 | 0.00 | 590.76 | 3,046.49 | 1,523.25 | 4,391.58 | 2,168.84 | 0.16 | -0.15 | 0.179 |
| 15.00 | -66.56 | -5.81 | 0.00 | -561.44 | 0.00 | 561.44 | 2,999.83 | 1,499.91 | 4,223.96 | 2,086.05 | 0.35 | -0.22 | 0.175 |
| 20.00 | -64.06 | -5.74 | 0.00 | -532.41 | 0.00 | 532.41 | 2,952.07 | 1,476.04 | 4,057.95 | 2,004.07 | 0.62 | -0.30 | 0.170 |
| 25.00 | -61.56 | -5.67 | 0.00 | -503.70 | 0.00 | 503.70 | 2,901.93 | 1,450.96 | 3,891.94 | 1,922.08 | 0.97 | -0.37 | 0.166 |
| 30.00 | -59.07 | -5.60 | 0.00 | -475.33 | 0.00 | 475.33 | 2,830.35 | 1,415.18 | 3,701.25 | 1,827.91 | 1.40 | -0.45 | 0.162 |
| 31.50 | -58.32 | -5.58 | 0.00 | -466.92 | 0.00 | 466.92 | 2,808.88 | 1,404.44 | 3,644.98 | 1,800.12 | 1.55 | -0.47 | 0.161 |
| 35.00 | -56.12 | -5.52 | 0.00 | -447.40 | 0.00 | 447.40 | 2,758.78 | 1,379.39 | 3,515.36 | 1,736.10 | 1.91 | -0.52 | 0.156 |
| 35.67 | -55.70 | -5.50 | 0.00 | -443.73 | 0.00 | 443.73 | 2,225.24 | 1,112.62 | 2,894.88 | 1,429.67 | 1.99 | -0.53 | 0.178 |
| 40.00 | -53.65 | -5.41 | 0.00 | -419.90 | 0.00 | 419.90 | 2,194.35 | 1,097.17 | 2,791.07 | 1,378.40 | 2.50 | -0.60 | 0.172 |
| 45.00 | -51.30 | -5.31 | 0.00 | -392.83 | 0.00 | 392.83 | 2,157.69 | 1,078.84 | 2,672.25 | 1,319.72 | 3.17 | -0.68 | 0.165 |
| 50.00 | -48.96 | -5.20 | 0.00 | -366.27 | 0.00 | 366.27 | 2,119.93 | 1,059.96 | 2,554.56 | 1,261.60 | 3.92 | -0.75 | 0.158 |
| 55.00 | -46.64 | -5.08 | 0.00 | -340.26 | 0.00 | 340.26 | 2,081.07 | 1,040.54 | 2,438.12 | 1,204.10 | 4.75 | -0.83 | 0.151 |
| 60.00 | -44.33 | -4.95 | 0.00 | -314.86 | 0.00 | 314.86 | 2,041.12 | 1,020.56 | 2,323.03 | 1,147.26 | 5.66 | -0.91 | 0.143 |
| 65.00 | -42.04 | -4.81 | 0.00 | -290.11 | 0.00 | 290.11 | 1,992.10 | 996.05 | 2,200.59 | 1,086.79 | 6.66 | -0.98 | 0.137 |
| 70.00 | -39.77 | -4.67 | 0.00 | -266.05 | 0.00 | 266.05 | 1,932.46 | 966.23 | 2,070.05 | 1,022.32 | 7.73 | -1.06 | 0.130 |
| 73.50 | -37.88 | -4.57 | 0.00 | -249.70 | 0.00 | 249.70 | 1,451.36 | 725.68 | 1,558.37 | 769.62 | 8.52 | -1.11 | 0.144 |
| 75.00 | -37.24 | -4.53 | 0.00 | -242.84 | 0.00 | 242.84 | 1,443.19 | 721.60 | 1,535.11 | 758.14 | 8.87 | -1.13 | 0.141 |
| 75.75 | -36.91 | -4.49 | 0.00 | -239.45 | 0.00 | 239.45 | 1,439.07 | 719.54 | 1,523.51 | 752.40 | 9.05 | -1.14 | 0.139 |
| 75.75 | -36.91 | -4.49 | 0.00 | -239.45 | 0.00 | 239.45 | 1,439.07 | 719.54 | 1,523.51 | 752.40 | 9.05 | -1.14 | 0.344 |
| 80.00 | -35.42 | -4.39 | 0.00 | -220.37 | 0.00 | 220.37 | 1,415.26 | 707.63 | 1,458.06 | 720.08 | 10.10 | -1.21 | 0.331 |
| 85.00 | -33.75 | -4.31 | 0.00 | -198.41 | 0.00 | 198.41 | 1,386.24 | 693.12 | 1,381.78 | 682.41 | 11.46 | -1.39 | 0.315 |
| 90.00 | -32.17 | -4.23 | 0.00 | -176.85 | 0.00 | 176.85 | 1,356.12 | 678.06 | 1,306.38 | 645.17 | 13.02 | -1.57 | 0.298 |
| 95.00 | -30.61 | -4.14 | 0.00 | -155.68 | 0.00 | 155.68 | 1,324.90 | 662.45 | 1,231.99 | 608.43 | 14.76 | -1.75 | 0.279 |
| 100.00 | -29.07 | -4.04 | 0.00 | -134.98 | 0.00 | 134.98 | 1,293.04 | 646.52 | 1,159.10 | 572.44 | 16.69 | -1.93 | 0.258 |
| 105.00 | -25.75 | -3.55 | 0.00 | -114.33 | 0.00 | 114.33 | 1,245.33 | 622.66 | 1,074.67 | 530.74 | 18.80 | -2.10 | 0.236 |
| 110.00 | -24.35 | -3.42 | 0.00 | -96.58 | 0.00 | 96.58 | 1,197.61 | 598.80 | 993.42 | 490.61 | 21.08 | -2.25 | 0.217 |
| 110.00 | -24.35 | -3.42 | 0.00 | -96.58 | 0.00 | 96.58 | 833.77 | 416.88 | 695.90 | 343.68 | 21.08 | -2.25 | 0.310 |
| 115.00 | -23.06 | -3.30 | 0.00 | -79.46 | 0.00 | 79.46 | 813.89 | 406.95 | 652.08 | 322.04 | 23.53 | -2.40 | 0.275 |
| 120.00 | -17.01 | -2.52 | 0.00 | -62.96 | 0.00 | 62.96 | 792.92 | 396.46 | 608.75 | 300.64 | 26.14 | -2.58 | 0.231 |
| 125.00 | -16.02 | -2.41 | 0.00 | -50.35 | 0.00 | 50.35 | 770.85 | 385.43 | 566.02 | 279.54 | 28.93 | -2.74 | 0.201 |
| 130.00 | -15.06 | -2.29 | 0.00 | -38.31 | 0.00 | 38.31 | 747.69 | 373.84 | 524.00 | 258.78 | 31.88 | -2.89 | 0.168 |
| 134.00 | -13.06 | -1.82 | 0.00 | -29.15 | 0.00 | 29.15 | 728.37 | 364.19 | 490.97 | 242.47 | 34.34 | -2.99 | 0.138 |
| 135.00 | -12.94 | -1.78 | 0.00 | -27.32 | 0.00 | 27.32 | 722.05 | 361.03 | 481.88 | 237.98 | 34.97 | -3.01 | 0.133 |
| 140.00 | -12.37 | -1.70 | 0.00 | -18.41 | 0.00 | 18.41 | 686.26 | 343.13 | 435.03 | 214.85 | 38.18 | -3.11 | 0.104 |
| 145.00 | -11.83 | -1.60 | 0.00 | -9.93 | 0.00 | 9.93 | 650.48 | 325.24 | 390.59 | 192.90 | 41.47 | -3.18 | 0.070 |
| 150.00 | 0.00 | -0.94 | 0.00 | -1.91 | 0.00 | 1.91 | 614.69 | 307.34 | 348.53 | 172.13 | 44.83 | -3.22 | 0.011 |

| | | |
|-------------------------------|-----------------------|------------------------------|
| Load Case: 1.0D + 1.0W | Serviceability 60 mph | 26 Iterations |
| Gust Response Factor :1.10 | | Wind Importance Factor :1.00 |
| Dead Load Factor :1.00 | | |
| Wind Load Factor :1.00 | | |

Applied Segment Forces Summary

| Seg Elev (ft) | Description | Shaft Forces | | Discrete Forces | | | Linear Forces | | Sum of Forces | | | | |
|----------------|-----------------|--------------|----------------|-----------------|--------------------|-------------------|----------------|--------------|----------------|--------------|----------------|--------------------|----------------|
| | | Wind FX (lb) | Dead Load (lb) | Wind FX (lb) | Torsion MY (lb-ft) | Moment MZ (lb-ft) | Dead Load (lb) | Wind FX (lb) | Dead Load (lb) | Wind FX (lb) | Dead Load (lb) | Torsion MY (lb-ft) | Moment MZ (lb) |
| 0.00 | | 63.9 | 0.0 | | | | | 0.0 | 0.0 | 63.9 | 0.0 | 0.0 | 0.0 |
| 5.00 | | 126.3 | 744.2 | | | | | 27.1 | 538.6 | 153.4 | 1,282.8 | 0.0 | 0.0 |
| 10.00 | | 123.5 | 727.7 | | | | | 27.1 | 538.6 | 150.6 | 1,266.3 | 0.0 | 0.0 |
| 15.00 | | 120.7 | 711.1 | | | | | 27.1 | 538.6 | 147.8 | 1,249.8 | 0.0 | 0.0 |
| 20.00 | | 117.9 | 694.6 | | | | | 27.1 | 538.6 | 145.0 | 1,233.3 | 0.0 | 0.0 |
| 25.00 | | 115.1 | 678.1 | | | | | 27.1 | 538.6 | 142.2 | 1,216.7 | 0.0 | 0.0 |
| 30.00 | | 73.8 | 661.6 | | | | | 27.1 | 538.6 | 100.9 | 1,200.2 | 0.0 | 0.0 |
| 31.50 | Bot - Section 2 | 57.5 | 195.2 | | | | | 8.2 | 161.6 | 65.7 | 356.8 | 0.0 | 0.0 |
| 35.00 | | 48.4 | 832.9 | | | | | 19.6 | 377.1 | 68.0 | 1,209.9 | 0.0 | 0.0 |
| 35.67 | Top - Section 1 | 58.8 | 157.0 | | | | | 3.8 | 71.8 | 62.6 | 228.8 | 0.0 | 0.0 |
| 40.00 | | 110.4 | 463.3 | | | | | 25.1 | 466.8 | 135.5 | 930.2 | 0.0 | 0.0 |
| 45.00 | | 119.1 | 521.8 | | | | | 30.0 | 538.6 | 149.1 | 1,060.4 | 0.0 | 0.0 |
| 50.00 | | 119.5 | 508.0 | | | | | 30.9 | 538.6 | 150.4 | 1,046.7 | 0.0 | 0.0 |
| 55.00 | | 119.5 | 494.2 | | | | | 31.8 | 538.6 | 151.3 | 1,032.9 | 0.0 | 0.0 |
| 60.00 | | 119.1 | 480.5 | | | | | 32.7 | 538.6 | 151.7 | 1,019.1 | 0.0 | 0.0 |
| 65.00 | | 118.3 | 466.7 | | | | | 33.5 | 538.6 | 151.8 | 1,005.4 | 0.0 | 0.0 |
| 70.00 | Bot - Section 3 | 100.6 | 452.9 | | | | | 34.2 | 538.6 | 134.8 | 991.6 | 0.0 | 0.0 |
| 73.50 | Top - Section 2 | 59.5 | 561.3 | | | | | 24.4 | 377.1 | 83.8 | 938.4 | 0.0 | 0.0 |
| 75.00 | | 26.6 | 106.6 | | | | | 10.5 | 161.6 | 37.2 | 268.1 | 0.0 | 0.0 |
| 75.75 | Reinf. Top | 58.8 | 52.9 | | | | | 5.3 | 80.8 | 64.1 | 133.7 | 0.0 | 0.0 |
| 80.00 | | 107.9 | 295.1 | | | | | 30.3 | 174.0 | 138.1 | 469.1 | 0.0 | 0.0 |
| 85.00 | | 115.0 | 337.0 | | | | | 32.4 | 204.7 | 147.4 | 541.7 | 0.0 | 0.0 |
| 90.00 | | 113.0 | 326.0 | | | | | 29.0 | 204.7 | 142.1 | 530.6 | 0.0 | 0.0 |
| 95.00 | | 110.9 | 315.0 | | | | | 29.5 | 204.7 | 140.4 | 519.6 | 0.0 | 0.0 |
| 100.00 | | 108.6 | 304.0 | | | | | 30.0 | 204.7 | 138.5 | 508.6 | 0.0 | 0.0 |
| 105.00 | Appurtenance(s) | 106.1 | 293.0 | 233.7 | 0.0 | 433.4 | 627.0 | 30.4 | 204.7 | 370.1 | 1,124.6 | 0.0 | 0.0 |
| 110.00 | Top - Section 3 | 103.4 | 281.9 | | | | | 30.8 | 194.8 | 134.2 | 476.7 | 0.0 | 0.0 |
| 115.00 | | 100.6 | 203.8 | | | | | 31.2 | 194.7 | 131.8 | 398.6 | 0.0 | 0.0 |
| 120.00 | Appurtenance(s) | 97.7 | 195.6 | 460.5 | 0.0 | 0.0 | 1,098.7 | 31.6 | 194.8 | 589.8 | 1,489.0 | 0.0 | 0.0 |
| 125.00 | | 94.6 | 187.3 | | | | | 20.0 | 137.5 | 114.6 | 324.8 | 0.0 | 0.0 |
| 130.00 | | 82.6 | 179.1 | | | | | 20.2 | 137.5 | 102.8 | 316.6 | 0.0 | 0.0 |
| 134.00 | Appurtenance(s) | 43.4 | 137.3 | 304.6 | 0.0 | 0.0 | 519.0 | 16.3 | 110.0 | 364.3 | 766.3 | 0.0 | 0.0 |
| 135.00 | | 43.4 | 33.5 | | | | | 0.0 | 17.7 | 43.4 | 51.2 | 0.0 | 0.0 |
| 140.00 | | 70.5 | 162.5 | | | | | 0.0 | 88.3 | 70.5 | 250.8 | 0.0 | 0.0 |
| 145.00 | | 67.6 | 154.3 | | | | | 0.0 | 88.3 | 67.6 | 242.6 | 0.0 | 0.0 |
| 150.00 | Appurtenance(s) | 33.0 | 146.0 | 764.3 | 0.0 | 1,757.9 | 3,364.0 | 0.0 | 88.3 | 797.4 | 3,598.3 | 0.0 | 0.0 |
| Totals: | | | | | | | | | | 5,802.67 | 29,280.2 | 0.00 | 0.00 |

Site Number: 302475

Code: ANSI/TIA-222-G

© 2007 - 2019 by ATC IP LLC. All rights reserved.

Site Name: Sttn - Southington, CT

Engineering Number: OAA713367_C3_07

1/4/2019 4:03:26 PM

Customer: CLEARWIRE

Load Case: 1.0D + 1.0W

Serviceability 60 mph

26 Iterations

Gust Response Factor :1.10

Wind Importance Factor :1.00

Dead Load Factor :1.00

Wind Load Factor :1.00

Calculated Forces

| Seg Elev (ft) | Pu FY (-) (kips) | Vu FX (-) (kips) | Tu MY (ft-kips) | Mu MZ (ft-kips) | Mu MX (ft-kips) | Resultant Moment (ft-kips) | phi Pn (kips) | phi Vn (kips) | phi Tn (ft-kips) | phi Mn (ft-kips) | Total Deflect (in) | Rotation (deg) | Ratio |
|---------------|------------------|------------------|-----------------|-----------------|-----------------|----------------------------|---------------|---------------|------------------|------------------|--------------------|----------------|-------|
| 0.00 | -29.28 | -5.75 | 0.00 | -543.16 | 0.00 | 543.16 | 3,136.53 | 1,568.27 | 4,731.25 | 2,336.59 | 0.00 | 0.00 | 0.150 |
| 5.00 | -27.99 | -5.63 | 0.00 | -514.39 | 0.00 | 514.39 | 3,092.06 | 1,546.03 | 4,560.72 | 2,252.37 | 0.03 | -0.06 | 0.145 |
| 10.00 | -26.72 | -5.51 | 0.00 | -486.24 | 0.00 | 486.24 | 3,046.49 | 1,523.25 | 4,391.58 | 2,168.84 | 0.13 | -0.12 | 0.141 |
| 15.00 | -25.46 | -5.38 | 0.00 | -458.71 | 0.00 | 458.71 | 2,999.83 | 1,499.91 | 4,223.96 | 2,086.05 | 0.29 | -0.18 | 0.136 |
| 20.00 | -24.22 | -5.26 | 0.00 | -431.80 | 0.00 | 431.80 | 2,952.07 | 1,476.04 | 4,057.95 | 2,004.07 | 0.52 | -0.24 | 0.132 |
| 25.00 | -23.00 | -5.13 | 0.00 | -405.51 | 0.00 | 405.51 | 2,901.93 | 1,450.96 | 3,891.94 | 1,922.08 | 0.80 | -0.30 | 0.127 |
| 30.00 | -21.80 | -5.04 | 0.00 | -379.84 | 0.00 | 379.84 | 2,830.35 | 1,415.18 | 3,701.25 | 1,827.91 | 1.16 | -0.37 | 0.123 |
| 31.50 | -21.44 | -4.98 | 0.00 | -372.27 | 0.00 | 372.27 | 2,808.88 | 1,404.44 | 3,644.98 | 1,800.12 | 1.27 | -0.38 | 0.122 |
| 35.00 | -20.23 | -4.92 | 0.00 | -354.83 | 0.00 | 354.83 | 2,758.78 | 1,379.39 | 3,515.36 | 1,736.10 | 1.57 | -0.43 | 0.118 |
| 35.67 | -20.00 | -4.86 | 0.00 | -351.55 | 0.00 | 351.55 | 2,225.24 | 1,112.62 | 2,894.88 | 1,429.67 | 1.63 | -0.43 | 0.134 |
| 40.00 | -19.06 | -4.74 | 0.00 | -330.48 | 0.00 | 330.48 | 2,194.35 | 1,097.17 | 2,791.07 | 1,378.40 | 2.05 | -0.49 | 0.129 |
| 45.00 | -18.00 | -4.60 | 0.00 | -306.78 | 0.00 | 306.78 | 2,157.69 | 1,078.84 | 2,672.25 | 1,319.72 | 2.59 | -0.55 | 0.123 |
| 50.00 | -16.95 | -4.46 | 0.00 | -283.79 | 0.00 | 283.79 | 2,119.93 | 1,059.96 | 2,554.56 | 1,261.60 | 3.19 | -0.61 | 0.116 |
| 55.00 | -15.91 | -4.31 | 0.00 | -261.50 | 0.00 | 261.50 | 2,081.07 | 1,040.54 | 2,438.12 | 1,204.10 | 3.86 | -0.67 | 0.110 |
| 60.00 | -14.89 | -4.16 | 0.00 | -239.95 | 0.00 | 239.95 | 2,041.12 | 1,020.56 | 2,323.03 | 1,147.26 | 4.59 | -0.73 | 0.104 |
| 65.00 | -13.89 | -4.01 | 0.00 | -219.15 | 0.00 | 219.15 | 1,992.10 | 996.05 | 2,200.59 | 1,086.79 | 5.38 | -0.78 | 0.098 |
| 70.00 | -12.89 | -3.87 | 0.00 | -199.10 | 0.00 | 199.10 | 1,932.46 | 966.23 | 2,070.05 | 1,022.32 | 6.24 | -0.84 | 0.092 |
| 73.50 | -11.95 | -3.78 | 0.00 | -185.55 | 0.00 | 185.55 | 1,451.36 | 725.68 | 1,558.37 | 769.62 | 6.86 | -0.88 | 0.101 |
| 75.00 | -11.69 | -3.74 | 0.00 | -179.88 | 0.00 | 179.88 | 1,443.19 | 721.60 | 1,535.11 | 758.14 | 7.14 | -0.89 | 0.099 |
| 75.75 | -11.55 | -3.68 | 0.00 | -177.08 | 0.00 | 177.08 | 1,439.07 | 719.54 | 1,523.51 | 752.40 | 7.28 | -0.90 | 0.097 |
| 75.75 | -11.55 | -3.68 | 0.00 | -177.08 | 0.00 | 177.08 | 1,439.07 | 719.54 | 1,523.51 | 752.40 | 7.28 | -0.90 | 0.243 |
| 80.00 | -11.08 | -3.55 | 0.00 | -161.44 | 0.00 | 161.44 | 1,415.26 | 707.63 | 1,458.06 | 720.08 | 8.11 | -0.95 | 0.232 |
| 85.00 | -10.53 | -3.42 | 0.00 | -143.68 | 0.00 | 143.68 | 1,386.24 | 693.12 | 1,381.78 | 682.41 | 9.17 | -1.08 | 0.218 |
| 90.00 | -10.00 | -3.29 | 0.00 | -126.58 | 0.00 | 126.58 | 1,356.12 | 678.06 | 1,306.38 | 645.17 | 10.38 | -1.22 | 0.204 |
| 95.00 | -9.47 | -3.16 | 0.00 | -110.14 | 0.00 | 110.14 | 1,324.90 | 662.45 | 1,231.99 | 608.43 | 11.72 | -1.34 | 0.188 |
| 100.00 | -8.96 | -3.03 | 0.00 | -94.35 | 0.00 | 94.35 | 1,293.04 | 646.52 | 1,159.10 | 572.44 | 13.19 | -1.47 | 0.172 |
| 105.00 | -7.84 | -2.64 | 0.00 | -78.78 | 0.00 | 78.78 | 1,245.33 | 622.66 | 1,074.67 | 530.74 | 14.79 | -1.58 | 0.155 |
| 110.00 | -7.37 | -2.51 | 0.00 | -65.58 | 0.00 | 65.58 | 1,197.61 | 598.80 | 993.42 | 490.61 | 16.51 | -1.69 | 0.140 |
| 110.00 | -7.37 | -2.51 | 0.00 | -65.58 | 0.00 | 65.58 | 833.77 | 416.88 | 695.90 | 343.68 | 16.51 | -1.69 | 0.200 |
| 115.00 | -6.97 | -2.38 | 0.00 | -53.04 | 0.00 | 53.04 | 813.89 | 406.95 | 652.08 | 322.04 | 18.33 | -1.79 | 0.173 |
| 120.00 | -5.49 | -1.75 | 0.00 | -41.16 | 0.00 | 41.16 | 792.92 | 396.46 | 608.75 | 300.64 | 20.27 | -1.91 | 0.144 |
| 125.00 | -5.17 | -1.63 | 0.00 | -32.41 | 0.00 | 32.41 | 770.85 | 385.43 | 566.02 | 279.54 | 22.33 | -2.01 | 0.123 |
| 130.00 | -4.86 | -1.53 | 0.00 | -24.25 | 0.00 | 24.25 | 747.69 | 373.84 | 524.00 | 258.78 | 24.49 | -2.11 | 0.100 |
| 134.00 | -4.10 | -1.14 | 0.00 | -18.15 | 0.00 | 18.15 | 728.37 | 364.19 | 490.97 | 242.47 | 26.28 | -2.17 | 0.080 |
| 135.00 | -4.05 | -1.09 | 0.00 | -17.01 | 0.00 | 17.01 | 722.05 | 361.03 | 481.88 | 237.98 | 26.73 | -2.18 | 0.077 |
| 140.00 | -3.80 | -1.02 | 0.00 | -11.55 | 0.00 | 11.55 | 686.26 | 343.13 | 435.03 | 214.85 | 29.05 | -2.25 | 0.059 |
| 145.00 | -3.56 | -0.94 | 0.00 | -6.47 | 0.00 | 6.47 | 650.48 | 325.24 | 390.59 | 192.90 | 31.43 | -2.29 | 0.039 |
| 150.00 | 0.00 | -0.80 | 0.00 | -1.76 | 0.00 | 1.76 | 614.69 | 307.34 | 348.53 | 172.13 | 33.84 | -2.31 | 0.010 |

Equivalent Lateral Forces Method Analysis

(Based on ASCE7-10 Chapters 11, 12, 15)

| | |
|--|---------|
| Spectral Response Acceleration for Short Period (S_s): | 0.18 |
| Spectral Response Acceleration at 1.0 Second Period (S_1): | 0.06 |
| Long-Period Transition Period (T_L): | 6 |
| Importance Factor (I_E): | 1.00 |
| Site Coefficient F_a : | 1.60 |
| Site Coefficient F_v : | 2.40 |
| Response Modification Coefficient (R): | 1.50 |
| Design Spectral Response Acceleration at Short Period (S_{ds}): | 0.20 |
| Design Spectral Response Acceleration at 1.0 Second Period (S_{d1}): | 0.10 |
| Seismic Response Coefficient (C_s): | 0.03 |
| Upper Limit C_s | 0.03 |
| Lower Limit C_s | 0.03 |
| Period based on Rayleigh Method (sec): | 2.80 |
| Redundancy Factor (ρ): | 1.00 |
| Seismic Force Distribution Exponent (k): | 2.00 |
| Total Unfactored Dead Load: | 29.28 k |
| Seismic Base Shear (E): | 0.88 k |

Load Case (1.2 + 0.2Sds) * DL + E ELFM

Seismic Equivalent Lateral Forces Method

| Segment | Height Above Base (ft) | Weight (lb) | W_z (lb-ft) | C_{vx} | Horizontal Force (lb) | Vertical Force (lb) |
|---------|------------------------|-------------|---------------|----------|-----------------------|---------------------|
| 35 | 147.50 | 234 | 5,098 | 0.024 | 21 | 290 |
| 34 | 142.50 | 243 | 4,926 | 0.023 | 21 | 301 |
| 33 | 137.50 | 251 | 4,742 | 0.023 | 20 | 311 |
| 32 | 134.50 | 51 | 925 | 0.004 | 4 | 63 |
| 31 | 132.00 | 247 | 4,309 | 0.020 | 18 | 306 |
| 30 | 127.50 | 317 | 5,146 | 0.024 | 21 | 392 |
| 29 | 122.50 | 325 | 4,874 | 0.023 | 20 | 403 |
| 28 | 117.50 | 390 | 5,389 | 0.026 | 23 | 484 |
| 27 | 112.50 | 399 | 5,045 | 0.024 | 21 | 494 |
| 26 | 107.50 | 477 | 5,509 | 0.026 | 23 | 591 |
| 25 | 102.50 | 498 | 5,228 | 0.025 | 22 | 617 |
| 24 | 97.50 | 509 | 4,835 | 0.023 | 20 | 630 |
| 23 | 92.50 | 520 | 4,446 | 0.021 | 19 | 644 |
| 22 | 87.50 | 531 | 4,063 | 0.019 | 17 | 658 |
| 21 | 82.50 | 542 | 3,687 | 0.018 | 15 | 671 |
| 20 | 77.88 | 469 | 2,845 | 0.014 | 12 | 581 |
| 19 | 75.38 | 134 | 760 | 0.004 | 3 | 166 |
| 18 | 74.25 | 268 | 1,478 | 0.007 | 6 | 332 |
| 17 | 71.75 | 938 | 4,831 | 0.023 | 20 | 1,163 |
| 16 | 67.50 | 992 | 4,518 | 0.021 | 19 | 1,229 |
| 15 | 62.50 | 1,005 | 3,927 | 0.019 | 16 | 1,246 |
| 14 | 57.50 | 1,019 | 3,369 | 0.016 | 14 | 1,263 |
| 13 | 52.50 | 1,033 | 2,847 | 0.014 | 12 | 1,280 |

| | | | | | | |
|----------------------|--------|--------|---------|-------|-----|--------|
| 12 | 47.50 | 1,047 | 2,362 | 0.011 | 10 | 1,297 |
| 11 | 42.50 | 1,060 | 1,915 | 0.009 | 8 | 1,314 |
| 10 | 37.83 | 930 | 1,331 | 0.006 | 6 | 1,153 |
| 9 | 35.33 | 229 | 286 | 0.001 | 1 | 284 |
| 8 | 33.25 | 1,210 | 1,338 | 0.006 | 6 | 1,499 |
| 7 | 30.75 | 357 | 337 | 0.002 | 1 | 442 |
| 6 | 27.50 | 1,200 | 908 | 0.004 | 4 | 1,487 |
| 5 | 22.50 | 1,217 | 616 | 0.003 | 3 | 1,508 |
| 4 | 17.50 | 1,233 | 378 | 0.002 | 2 | 1,528 |
| 3 | 12.50 | 1,250 | 195 | 0.001 | 1 | 1,549 |
| 2 | 7.50 | 1,266 | 71 | 0.000 | 0 | 1,569 |
| 1 | 2.50 | 1,283 | 8 | 0.000 | 0 | 1,590 |
| CCI TPX-070821 | 150.00 | 45 | 1,013 | 0.005 | 4 | 56 |
| Raycap DC6-48-60-18- | 150.00 | 40 | 900 | 0.004 | 4 | 50 |
| CCI DTMAPB7819VG12A | 150.00 | 115 | 2,592 | 0.012 | 11 | 143 |
| Ericsson RRUS-11 (50 | 150.00 | 150 | 3,375 | 0.016 | 14 | 186 |
| Ericsson RRUS 32 B2 | 150.00 | 159 | 3,577 | 0.017 | 15 | 197 |
| 10' Omni | 150.00 | 25 | 563 | 0.003 | 2 | 31 |
| Ericsson RRUS-32 (77 | 150.00 | 231 | 5,198 | 0.025 | 22 | 286 |
| Powerwave Allgon 777 | 150.00 | 105 | 2,363 | 0.011 | 10 | 130 |
| KMW AM-X-CD-16-65-00 | 150.00 | 97 | 2,183 | 0.010 | 9 | 120 |
| Quintel QS66512-3 (1 | 150.00 | 336 | 7,560 | 0.036 | 32 | 416 |
| Andrew SBNH-1D6565C | 150.00 | 61 | 1,368 | 0.007 | 6 | 75 |
| Round Platform w/ Ha | 150.00 | 2,000 | 45,000 | 0.214 | 188 | 2,479 |
| Kathrein Smart Bias | 134.00 | 10 | 178 | 0.001 | 1 | 12 |
| Site-Pro UWS6-NP | 134.00 | 276 | 4,956 | 0.024 | 21 | 342 |
| RFS APXV18-206517S-C | 134.00 | 79 | 1,422 | 0.007 | 6 | 98 |
| Andrew LNX-6515DS-VT | 134.00 | 154 | 2,763 | 0.013 | 12 | 191 |
| DragonWave Horizon C | 120.00 | 11 | 153 | 0.001 | 1 | 13 |
| 12" x 12" Junction B | 120.00 | 10 | 144 | 0.001 | 1 | 12 |
| Alcatel-Lucent RRH2x | 120.00 | 317 | 4,571 | 0.022 | 19 | 393 |
| Nokia FZHN Flexi RRH | 120.00 | 132 | 1,905 | 0.009 | 8 | 164 |
| Alcatel-Lucent 1900 | 120.00 | 180 | 2,592 | 0.012 | 11 | 223 |
| RFS APXVTM14-ALU-I20 | 120.00 | 169 | 2,428 | 0.012 | 10 | 209 |
| DragonWave A-ANT-11G | 120.00 | 48 | 685 | 0.003 | 3 | 59 |
| Commscope NNVV-65B-R | 120.00 | 232 | 3,344 | 0.016 | 14 | 288 |
| dB Systems 5100A | 105.00 | 21 | 232 | 0.001 | 1 | 26 |
| VertexRSI 101V VPD | 105.00 | 4 | 44 | 0.000 | 0 | 5 |
| dB Systems 5100A-D | 105.00 | 152 | 1,676 | 0.008 | 7 | 188 |
| Round Side Arm | 105.00 | 450 | 4,961 | 0.024 | 21 | 558 |
| | | 29,280 | 210,285 | 1.000 | 878 | 36,286 |

Load Case (0.9 - 0.2Sds) * DL + E ELMF

Seismic (Reduced DL) Equivalent Lateral Forces Method

| Segment | Height Above Base (ft) | Weight (lb) | W _z (lb-ft) | C _{vx} | Horizontal Force (lb) | Vertical Force (lb) |
|---------|------------------------|-------------|------------------------|-----------------|-----------------------|---------------------|
| 35 | 147.50 | 234 | 5,098 | 0.024 | 21 | 202 |
| 34 | 142.50 | 243 | 4,926 | 0.023 | 21 | 209 |
| 33 | 137.50 | 251 | 4,742 | 0.023 | 20 | 216 |
| 32 | 134.50 | 51 | 925 | 0.004 | 4 | 44 |
| 31 | 132.00 | 247 | 4,309 | 0.020 | 18 | 213 |
| 30 | 127.50 | 317 | 5,146 | 0.024 | 21 | 272 |
| 29 | 122.50 | 325 | 4,874 | 0.023 | 20 | 280 |
| 28 | 117.50 | 390 | 5,389 | 0.026 | 23 | 336 |
| 27 | 112.50 | 399 | 5,045 | 0.024 | 21 | 343 |
| 26 | 107.50 | 477 | 5,509 | 0.026 | 23 | 410 |
| 25 | 102.50 | 498 | 5,228 | 0.025 | 22 | 428 |
| 24 | 97.50 | 509 | 4,835 | 0.023 | 20 | 438 |
| 23 | 92.50 | 520 | 4,446 | 0.021 | 19 | 447 |
| 22 | 87.50 | 531 | 4,063 | 0.019 | 17 | 457 |

Site Number: 302475

Code: ANSI/TIA-222-G

© 2007 - 2019 by ATC IP LLC. All rights reserved.

Site Name: Sttn - Southington, CT

Engineering Number: OAA713367_C3_07

1/4/2019 4:03:27 PM

Customer: CLEARWIRE

| | | | | | | |
|----------------------|--------|--------|---------|-------|-----|--------|
| 21 | 82.50 | 542 | 3,687 | 0.018 | 15 | 466 |
| 20 | 77.88 | 469 | 2,845 | 0.014 | 12 | 404 |
| 19 | 75.38 | 134 | 760 | 0.004 | 3 | 115 |
| 18 | 74.25 | 268 | 1,478 | 0.007 | 6 | 231 |
| 17 | 71.75 | 938 | 4,831 | 0.023 | 20 | 808 |
| 16 | 67.50 | 992 | 4,518 | 0.021 | 19 | 854 |
| 15 | 62.50 | 1,005 | 3,927 | 0.019 | 16 | 865 |
| 14 | 57.50 | 1,019 | 3,369 | 0.016 | 14 | 877 |
| 13 | 52.50 | 1,033 | 2,847 | 0.014 | 12 | 889 |
| 12 | 47.50 | 1,047 | 2,362 | 0.011 | 10 | 901 |
| 11 | 42.50 | 1,060 | 1,915 | 0.009 | 8 | 913 |
| 10 | 37.83 | 930 | 1,331 | 0.006 | 6 | 801 |
| 9 | 35.33 | 229 | 286 | 0.001 | 1 | 197 |
| 8 | 33.25 | 1,210 | 1,338 | 0.006 | 6 | 1,041 |
| 7 | 30.75 | 357 | 337 | 0.002 | 1 | 307 |
| 6 | 27.50 | 1,200 | 908 | 0.004 | 4 | 1,033 |
| 5 | 22.50 | 1,217 | 616 | 0.003 | 3 | 1,047 |
| 4 | 17.50 | 1,233 | 378 | 0.002 | 2 | 1,062 |
| 3 | 12.50 | 1,250 | 195 | 0.001 | 1 | 1,076 |
| 2 | 7.50 | 1,266 | 71 | 0.000 | 0 | 1,090 |
| 1 | 2.50 | 1,283 | 8 | 0.000 | 0 | 1,104 |
| CCI TPX-070821 | 150.00 | 45 | 1,013 | 0.005 | 4 | 39 |
| Raycap DC6-48-60-18- | 150.00 | 40 | 900 | 0.004 | 4 | 34 |
| CCI DTMAPB7819VG12A | 150.00 | 115 | 2,592 | 0.012 | 11 | 99 |
| Ericsson RRUS-11 (50 | 150.00 | 150 | 3,375 | 0.016 | 14 | 129 |
| Ericsson RRUS 32 B2 | 150.00 | 159 | 3,577 | 0.017 | 15 | 137 |
| 10' Omni | 150.00 | 25 | 563 | 0.003 | 2 | 22 |
| Ericsson RRUS-32 (77 | 150.00 | 231 | 5,198 | 0.025 | 22 | 199 |
| Powerwave Allgon 777 | 150.00 | 105 | 2,363 | 0.011 | 10 | 90 |
| KMW AM-X-CD-16-65-00 | 150.00 | 97 | 2,183 | 0.010 | 9 | 83 |
| Quintel QS66512-3 (1 | 150.00 | 336 | 7,560 | 0.036 | 32 | 289 |
| Andrew SBNH-1D6565C | 150.00 | 61 | 1,368 | 0.007 | 6 | 52 |
| Round Platform w/ Ha | 150.00 | 2,000 | 45,000 | 0.214 | 188 | 1,721 |
| Kathrein Smart Bias | 134.00 | 10 | 178 | 0.001 | 1 | 9 |
| Site-Pro UWS6-NP | 134.00 | 276 | 4,956 | 0.024 | 21 | 238 |
| RFS APXV18-206517S-C | 134.00 | 79 | 1,422 | 0.007 | 6 | 68 |
| Andrew LNX-6515DS-VT | 134.00 | 154 | 2,763 | 0.013 | 12 | 132 |
| DragonWave Horizon C | 120.00 | 11 | 153 | 0.001 | 1 | 9 |
| 12" x 12" Junction B | 120.00 | 10 | 144 | 0.001 | 1 | 9 |
| Alcatel-Lucent RRH2x | 120.00 | 317 | 4,571 | 0.022 | 19 | 273 |
| Nokia FZHN Flexi RRH | 120.00 | 132 | 1,905 | 0.009 | 8 | 114 |
| Alcatel-Lucent 1900 | 120.00 | 180 | 2,592 | 0.012 | 11 | 155 |
| RFS APXVTM14-ALU-I20 | 120.00 | 169 | 2,428 | 0.012 | 10 | 145 |
| DragonWave A-ANT-11G | 120.00 | 48 | 685 | 0.003 | 3 | 41 |
| Commscope NNVV-65B-R | 120.00 | 232 | 3,344 | 0.016 | 14 | 200 |
| dB Systems 5100A | 105.00 | 21 | 232 | 0.001 | 1 | 18 |
| VertexRSI 101V VPD | 105.00 | 4 | 44 | 0.000 | 0 | 3 |
| dB Systems 5100A-D | 105.00 | 152 | 1,676 | 0.008 | 7 | 131 |
| Round Side Arm | 105.00 | 450 | 4,961 | 0.024 | 21 | 387 |
| | | 29,280 | 210,285 | 1.000 | 878 | 25,203 |

Load Case (1.2 + 0.2Sds) * DL + E ELFM Seismic Equivalent Lateral Forces Method

Calculated Forces

| Seg Elev (ft) | Pu FY (-) (kips) | Vu FX (-) (kips) | Tu MY (ft-kips) | Mu MZ (ft-kips) | Mu MX (ft-kips) | Resultant Moment (ft-kips) | phi Pn (kips) | phi Vn (kips) | phi Tn (ft-kips) | phi Mn (ft-kips) | Total Deflect (in) | Rotation (deg) | Ratio |
|---------------|------------------|------------------|-----------------|-----------------|-----------------|----------------------------|---------------|---------------|------------------|------------------|--------------------|----------------|-------|
| 0.00 | -34.70 | -0.88 | 0.00 | -110.91 | 0.00 | 110.91 | 3,136.53 | 1,568.27 | 4,731.25 | 2,336.59 | 0.00 | 0.00 | 0.037 |
| 5.00 | -33.13 | -0.89 | 0.00 | -106.50 | 0.00 | 106.50 | 3,092.06 | 1,546.03 | 4,560.72 | 2,252.37 | 0.01 | -0.01 | 0.036 |
| 10.00 | -31.58 | -0.89 | 0.00 | -102.06 | 0.00 | 102.06 | 3,046.49 | 1,523.25 | 4,391.58 | 2,168.84 | 0.03 | -0.03 | 0.035 |
| 15.00 | -30.05 | -0.90 | 0.00 | -97.59 | 0.00 | 97.59 | 2,999.83 | 1,499.91 | 4,223.96 | 2,086.05 | 0.06 | -0.04 | 0.035 |
| 20.00 | -28.54 | -0.90 | 0.00 | -93.10 | 0.00 | 93.10 | 2,952.07 | 1,476.04 | 4,057.95 | 2,004.07 | 0.11 | -0.05 | 0.034 |
| 25.00 | -27.05 | -0.90 | 0.00 | -88.59 | 0.00 | 88.59 | 2,901.93 | 1,450.96 | 3,891.94 | 1,922.08 | 0.17 | -0.06 | 0.033 |
| 30.00 | -26.61 | -0.90 | 0.00 | -84.08 | 0.00 | 84.08 | 2,830.35 | 1,415.18 | 3,701.25 | 1,827.91 | 0.24 | -0.08 | 0.032 |
| 31.50 | -25.11 | -0.90 | 0.00 | -82.73 | 0.00 | 82.73 | 2,808.88 | 1,404.44 | 3,644.98 | 1,800.12 | 0.27 | -0.08 | 0.032 |
| 35.00 | -24.83 | -0.90 | 0.00 | -79.58 | 0.00 | 79.58 | 2,758.78 | 1,379.39 | 3,515.36 | 1,736.10 | 0.33 | -0.09 | 0.031 |
| 35.67 | -23.67 | -0.90 | 0.00 | -78.98 | 0.00 | 78.98 | 2,225.24 | 1,112.62 | 2,894.88 | 1,429.67 | 0.34 | -0.09 | 0.035 |
| 40.00 | -22.36 | -0.89 | 0.00 | -75.10 | 0.00 | 75.10 | 2,194.35 | 1,097.17 | 2,791.07 | 1,378.40 | 0.43 | -0.10 | 0.034 |
| 45.00 | -21.06 | -0.88 | 0.00 | -70.65 | 0.00 | 70.65 | 2,157.69 | 1,078.84 | 2,672.25 | 1,319.72 | 0.55 | -0.12 | 0.033 |
| 50.00 | -19.78 | -0.87 | 0.00 | -66.23 | 0.00 | 66.23 | 2,119.93 | 1,059.96 | 2,554.56 | 1,261.60 | 0.68 | -0.13 | 0.032 |
| 55.00 | -18.52 | -0.86 | 0.00 | -61.86 | 0.00 | 61.86 | 2,081.07 | 1,040.54 | 2,438.12 | 1,204.10 | 0.83 | -0.15 | 0.030 |
| 60.00 | -17.27 | -0.85 | 0.00 | -57.56 | 0.00 | 57.56 | 2,041.12 | 1,020.56 | 2,323.03 | 1,147.26 | 0.99 | -0.16 | 0.029 |
| 65.00 | -16.05 | -0.83 | 0.00 | -53.33 | 0.00 | 53.33 | 1,992.10 | 996.05 | 2,200.59 | 1,086.79 | 1.17 | -0.17 | 0.028 |
| 70.00 | -14.88 | -0.81 | 0.00 | -49.20 | 0.00 | 49.20 | 1,932.46 | 966.23 | 2,070.05 | 1,022.32 | 1.36 | -0.19 | 0.026 |
| 73.50 | -14.55 | -0.80 | 0.00 | -46.38 | 0.00 | 46.38 | 1,451.36 | 725.68 | 1,558.37 | 769.62 | 1.50 | -0.20 | 0.029 |
| 75.00 | -14.38 | -0.80 | 0.00 | -45.18 | 0.00 | 45.18 | 1,443.19 | 721.60 | 1,535.11 | 758.14 | 1.56 | -0.20 | 0.029 |
| 75.75 | -13.80 | -0.78 | 0.00 | -44.58 | 0.00 | 44.58 | 1,439.07 | 719.54 | 1,523.51 | 752.40 | 1.59 | -0.20 | 0.028 |
| 75.75 | -13.80 | -0.78 | 0.00 | -44.58 | 0.00 | 44.58 | 1,439.07 | 719.54 | 1,523.51 | 752.40 | 1.59 | -0.20 | 0.069 |
| 80.00 | -13.13 | -0.77 | 0.00 | -41.25 | 0.00 | 41.25 | 1,415.26 | 707.63 | 1,458.06 | 720.08 | 1.78 | -0.22 | 0.067 |
| 85.00 | -12.47 | -0.76 | 0.00 | -37.38 | 0.00 | 37.38 | 1,386.24 | 693.12 | 1,381.78 | 682.41 | 2.02 | -0.25 | 0.064 |
| 90.00 | -11.83 | -0.75 | 0.00 | -33.58 | 0.00 | 33.58 | 1,356.12 | 678.06 | 1,306.38 | 645.17 | 2.30 | -0.29 | 0.061 |
| 95.00 | -11.20 | -0.73 | 0.00 | -29.85 | 0.00 | 29.85 | 1,324.90 | 662.45 | 1,231.99 | 608.43 | 2.62 | -0.32 | 0.058 |
| 100.00 | -10.58 | -0.71 | 0.00 | -26.21 | 0.00 | 26.21 | 1,293.04 | 646.52 | 1,159.10 | 572.44 | 2.97 | -0.35 | 0.054 |
| 105.00 | -9.21 | -0.65 | 0.00 | -22.66 | 0.00 | 22.66 | 1,245.33 | 622.66 | 1,074.67 | 530.74 | 3.36 | -0.39 | 0.050 |
| 110.00 | -8.72 | -0.63 | 0.00 | -19.39 | 0.00 | 19.39 | 1,197.61 | 598.80 | 993.42 | 490.61 | 3.78 | -0.42 | 0.047 |
| 110.00 | -8.72 | -0.63 | 0.00 | -19.39 | 0.00 | 19.39 | 833.77 | 416.88 | 695.90 | 343.68 | 3.78 | -0.42 | 0.067 |
| 115.00 | -8.24 | -0.61 | 0.00 | -16.21 | 0.00 | 16.21 | 813.89 | 406.95 | 652.08 | 322.04 | 4.24 | -0.45 | 0.060 |
| 120.00 | -6.47 | -0.52 | 0.00 | -13.15 | 0.00 | 13.15 | 792.92 | 396.46 | 608.75 | 300.64 | 4.72 | -0.48 | 0.052 |
| 125.00 | -6.08 | -0.49 | 0.00 | -10.57 | 0.00 | 10.57 | 770.85 | 385.43 | 566.02 | 279.54 | 5.25 | -0.52 | 0.046 |
| 130.00 | -5.77 | -0.48 | 0.00 | -8.09 | 0.00 | 8.09 | 747.69 | 373.84 | 524.00 | 258.78 | 5.81 | -0.55 | 0.039 |
| 134.00 | -5.07 | -0.43 | 0.00 | -6.18 | 0.00 | 6.18 | 728.37 | 364.19 | 490.97 | 242.47 | 6.28 | -0.57 | 0.032 |
| 135.00 | -4.76 | -0.41 | 0.00 | -5.76 | 0.00 | 5.76 | 722.05 | 361.03 | 481.88 | 237.98 | 6.40 | -0.57 | 0.031 |
| 140.00 | -4.46 | -0.38 | 0.00 | -3.72 | 0.00 | 3.72 | 686.26 | 343.13 | 435.03 | 214.85 | 7.01 | -0.60 | 0.024 |
| 145.00 | -4.17 | -0.36 | 0.00 | -1.80 | 0.00 | 1.80 | 650.48 | 325.24 | 390.59 | 192.90 | 7.64 | -0.61 | 0.016 |
| 150.00 | 0.00 | -0.32 | 0.00 | 0.00 | 0.00 | 0.00 | 614.69 | 307.34 | 348.53 | 172.13 | 8.28 | -0.61 | 0.000 |

Load Case (0.9 - 0.2Sds) * DL + E ELMF

Seismic (Reduced DL) Equivalent Lateral Forces Method

Calculated Forces

| Seg Elev (ft) | Pu FY (-) (kips) | Vu FX (-) (kips) | Tu MY (ft-kips) | Mu MZ (ft-kips) | Mu MX (ft-kips) | Resultant Moment (ft-kips) | phi Pn (kips) | phi Vn (kips) | phi Tn (ft-kips) | phi Mn (ft-kips) | Total Deflect (in) | Rotation (deg) | Ratio |
|---------------|------------------|------------------|-----------------|-----------------|-----------------|----------------------------|---------------|---------------|------------------|------------------|--------------------|----------------|-------|
| 0.00 | -24.10 | -0.88 | 0.00 | -108.65 | 0.00 | 108.65 | 3,136.53 | 1,568.27 | 4,731.25 | 2,336.59 | 0.00 | 0.00 | 0.034 |
| 5.00 | -23.01 | -0.88 | 0.00 | -104.24 | 0.00 | 104.24 | 3,092.06 | 1,546.03 | 4,560.72 | 2,252.37 | 0.01 | -0.01 | 0.033 |
| 10.00 | -21.93 | -0.89 | 0.00 | -99.82 | 0.00 | 99.82 | 3,046.49 | 1,523.25 | 4,391.58 | 2,168.84 | 0.03 | -0.02 | 0.033 |
| 15.00 | -20.87 | -0.89 | 0.00 | -95.38 | 0.00 | 95.38 | 2,999.83 | 1,499.91 | 4,223.96 | 2,086.05 | 0.06 | -0.04 | 0.032 |
| 20.00 | -19.82 | -0.89 | 0.00 | -90.92 | 0.00 | 90.92 | 2,952.07 | 1,476.04 | 4,057.95 | 2,004.07 | 0.10 | -0.05 | 0.031 |
| 25.00 | -18.79 | -0.89 | 0.00 | -86.46 | 0.00 | 86.46 | 2,901.93 | 1,450.96 | 3,891.94 | 1,922.08 | 0.16 | -0.06 | 0.030 |
| 30.00 | -18.48 | -0.89 | 0.00 | -82.01 | 0.00 | 82.01 | 2,830.35 | 1,415.18 | 3,701.25 | 1,827.91 | 0.24 | -0.08 | 0.030 |
| 31.50 | -17.44 | -0.89 | 0.00 | -80.67 | 0.00 | 80.67 | 2,808.88 | 1,404.44 | 3,644.98 | 1,800.12 | 0.26 | -0.08 | 0.029 |
| 35.00 | -17.24 | -0.89 | 0.00 | -77.56 | 0.00 | 77.56 | 2,758.78 | 1,379.39 | 3,515.36 | 1,736.10 | 0.32 | -0.09 | 0.029 |
| 35.67 | -16.44 | -0.88 | 0.00 | -76.97 | 0.00 | 76.97 | 2,225.24 | 1,112.62 | 2,894.88 | 1,429.67 | 0.34 | -0.09 | 0.033 |
| 40.00 | -15.53 | -0.88 | 0.00 | -73.15 | 0.00 | 73.15 | 2,194.35 | 1,097.17 | 2,791.07 | 1,378.40 | 0.42 | -0.10 | 0.032 |
| 45.00 | -14.63 | -0.87 | 0.00 | -68.76 | 0.00 | 68.76 | 2,157.69 | 1,078.84 | 2,672.25 | 1,319.72 | 0.54 | -0.12 | 0.030 |
| 50.00 | -13.74 | -0.86 | 0.00 | -64.42 | 0.00 | 64.42 | 2,119.93 | 1,059.96 | 2,554.56 | 1,261.60 | 0.67 | -0.13 | 0.029 |
| 55.00 | -12.86 | -0.84 | 0.00 | -60.13 | 0.00 | 60.13 | 2,081.07 | 1,040.54 | 2,438.12 | 1,204.10 | 0.81 | -0.14 | 0.028 |
| 60.00 | -12.00 | -0.83 | 0.00 | -55.91 | 0.00 | 55.91 | 2,041.12 | 1,020.56 | 2,323.03 | 1,147.26 | 0.97 | -0.16 | 0.027 |
| 65.00 | -11.14 | -0.81 | 0.00 | -51.76 | 0.00 | 51.76 | 1,992.10 | 996.05 | 2,200.59 | 1,086.79 | 1.14 | -0.17 | 0.025 |
| 70.00 | -10.34 | -0.79 | 0.00 | -47.71 | 0.00 | 47.71 | 1,932.46 | 966.23 | 2,070.05 | 1,022.32 | 1.32 | -0.18 | 0.024 |
| 73.50 | -10.10 | -0.78 | 0.00 | -44.95 | 0.00 | 44.95 | 1,451.36 | 725.68 | 1,558.37 | 769.62 | 1.46 | -0.19 | 0.027 |
| 75.00 | -9.99 | -0.78 | 0.00 | -43.77 | 0.00 | 43.77 | 1,443.19 | 721.60 | 1,535.11 | 758.14 | 1.52 | -0.20 | 0.027 |
| 75.75 | -9.59 | -0.77 | 0.00 | -43.19 | 0.00 | 43.19 | 1,439.07 | 719.54 | 1,523.51 | 752.40 | 1.55 | -0.20 | 0.026 |
| 75.75 | -9.59 | -0.77 | 0.00 | -43.19 | 0.00 | 43.19 | 1,439.07 | 719.54 | 1,523.51 | 752.40 | 1.55 | -0.20 | 0.064 |
| 80.00 | -9.12 | -0.76 | 0.00 | -39.92 | 0.00 | 39.92 | 1,415.26 | 707.63 | 1,458.06 | 720.08 | 1.74 | -0.21 | 0.062 |
| 85.00 | -8.66 | -0.74 | 0.00 | -36.14 | 0.00 | 36.14 | 1,386.24 | 693.12 | 1,381.78 | 682.41 | 1.97 | -0.24 | 0.059 |
| 90.00 | -8.21 | -0.73 | 0.00 | -32.44 | 0.00 | 32.44 | 1,356.12 | 678.06 | 1,306.38 | 645.17 | 2.25 | -0.28 | 0.056 |
| 95.00 | -7.78 | -0.71 | 0.00 | -28.81 | 0.00 | 28.81 | 1,324.90 | 662.45 | 1,231.99 | 608.43 | 2.56 | -0.31 | 0.053 |
| 100.00 | -7.35 | -0.69 | 0.00 | -25.27 | 0.00 | 25.27 | 1,293.04 | 646.52 | 1,159.10 | 572.44 | 2.90 | -0.34 | 0.050 |
| 105.00 | -6.40 | -0.63 | 0.00 | -21.83 | 0.00 | 21.83 | 1,245.33 | 622.66 | 1,074.67 | 530.74 | 3.27 | -0.37 | 0.046 |
| 110.00 | -6.05 | -0.61 | 0.00 | -18.66 | 0.00 | 18.66 | 1,197.61 | 598.80 | 993.42 | 490.61 | 3.68 | -0.40 | 0.043 |
| 110.00 | -6.05 | -0.61 | 0.00 | -18.66 | 0.00 | 18.66 | 833.77 | 416.88 | 695.90 | 343.68 | 3.68 | -0.40 | 0.062 |
| 115.00 | -5.72 | -0.59 | 0.00 | -15.60 | 0.00 | 15.60 | 813.89 | 406.95 | 652.08 | 322.04 | 4.12 | -0.43 | 0.055 |
| 120.00 | -4.49 | -0.50 | 0.00 | -12.64 | 0.00 | 12.64 | 792.92 | 396.46 | 608.75 | 300.64 | 4.60 | -0.47 | 0.048 |
| 125.00 | -4.22 | -0.48 | 0.00 | -10.15 | 0.00 | 10.15 | 770.85 | 385.43 | 566.02 | 279.54 | 5.10 | -0.50 | 0.042 |
| 130.00 | -4.01 | -0.46 | 0.00 | -7.77 | 0.00 | 7.77 | 747.69 | 373.84 | 524.00 | 258.78 | 5.65 | -0.53 | 0.035 |
| 134.00 | -3.52 | -0.41 | 0.00 | -5.94 | 0.00 | 5.94 | 728.37 | 364.19 | 490.97 | 242.47 | 6.10 | -0.55 | 0.029 |
| 135.00 | -3.30 | -0.39 | 0.00 | -5.53 | 0.00 | 5.53 | 722.05 | 361.03 | 481.88 | 237.98 | 6.21 | -0.56 | 0.028 |
| 140.00 | -3.09 | -0.37 | 0.00 | -3.57 | 0.00 | 3.57 | 686.26 | 343.13 | 435.03 | 214.85 | 6.81 | -0.58 | 0.021 |
| 145.00 | -2.89 | -0.35 | 0.00 | -1.73 | 0.00 | 1.73 | 650.48 | 325.24 | 390.59 | 192.90 | 7.42 | -0.59 | 0.013 |
| 150.00 | 0.00 | -0.32 | 0.00 | 0.00 | 0.00 | 0.00 | 614.69 | 307.34 | 348.53 | 172.13 | 8.04 | -0.59 | 0.000 |

Equivalent Modal Forces Analysis

(Based on ASCE7-10 Chapters 11, 12 & 15 and ANSI/TIA-G, section 2.7)

| | |
|--|------|
| Spectral Response Acceleration for Short Period (S_s): | 0.18 |
| Spectral Response Acceleration at 1.0 Second Period (S_1): | 0.06 |
| Importance Factor (I_E): | 1.00 |
| Site Coefficient F_a : | 1.60 |
| Site Coefficient F_v : | 2.40 |
| Response Modification Coefficient (R): | 1.50 |
| Design Spectral Response Acceleration at Short Period (S_{ds}): | 0.20 |
| Design Spectral Response Acceleration at 1.0 Second Period (S_{d1}): | 0.10 |
| Period Based on Rayleigh Method (sec): | 2.80 |
| Redundancy Factor (ρ): | 1.00 |

Load Case (1.2 + 0.2Sds) * DL + E EMAM Seismic Equivalent Modal Analysis Method

| Segment | Height Above Base (ft) | Weight (lb) | a | b | c | Saz | Horizontal Force (lb) | Vertical Force (lb) |
|---------|---------------------------------|----------------|-------|--------|-------|--------|-----------------------------|---------------------------|
| 35 | 147.50 | 234 | 1.828 | 1.667 | 1.025 | 0.330 | 52 | 290 |
| 34 | 142.50 | 243 | 1.706 | 1.144 | 0.823 | 0.255 | 41 | 301 |
| 33 | 137.50 | 251 | 1.588 | 0.742 | 0.654 | 0.189 | 32 | 311 |
| 32 | 134.50 | 51 | 1.520 | 0.550 | 0.566 | 0.153 | 5 | 63 |
| 31 | 132.00 | 247 | 1.464 | 0.415 | 0.501 | 0.125 | 21 | 306 |
| 30 | 127.50 | 317 | 1.366 | 0.222 | 0.397 | 0.080 | 17 | 392 |
| 29 | 122.50 | 325 | 1.261 | 0.069 | 0.302 | 0.038 | 8 | 403 |
| 28 | 117.50 | 390 | 1.160 | -0.030 | 0.226 | 0.004 | 1 | 484 |
| 27 | 112.50 | 399 | 1.063 | -0.088 | 0.165 | -0.023 | -6 | 494 |
| 26 | 107.50 | 477 | 0.971 | -0.116 | 0.117 | -0.041 | -13 | 591 |
| 25 | 102.50 | 498 | 0.883 | -0.121 | 0.081 | -0.052 | -17 | 617 |
| 24 | 97.50 | 509 | 0.799 | -0.112 | 0.053 | -0.056 | -19 | 630 |
| 23 | 92.50 | 520 | 0.719 | -0.092 | 0.034 | -0.051 | -18 | 644 |
| 22 | 87.50 | 531 | 0.643 | -0.068 | 0.020 | -0.039 | -14 | 658 |
| 21 | 82.50 | 542 | 0.572 | -0.043 | 0.012 | -0.021 | -7 | 671 |
| 20 | 77.88 | 469 | 0.509 | -0.020 | 0.007 | -0.002 | -1 | 581 |
| 19 | 75.38 | 134 | 0.477 | -0.008 | 0.006 | 0.008 | 1 | 166 |
| 18 | 74.25 | 268 | 0.463 | -0.003 | 0.006 | 0.013 | 2 | 332 |
| 17 | 71.75 | 938 | 0.432 | 0.008 | 0.006 | 0.022 | 14 | 1,163 |
| 16 | 67.50 | 992 | 0.383 | 0.023 | 0.007 | 0.035 | 23 | 1,229 |
| 15 | 62.50 | 1,005 | 0.328 | 0.039 | 0.010 | 0.046 | 31 | 1,246 |
| 14 | 57.50 | 1,019 | 0.278 | 0.050 | 0.014 | 0.053 | 36 | 1,263 |
| 13 | 52.50 | 1,033 | 0.232 | 0.058 | 0.019 | 0.056 | 39 | 1,280 |
| 12 | 47.50 | 1,047 | 0.190 | 0.064 | 0.025 | 0.057 | 40 | 1,297 |
| 11 | 42.50 | 1,060 | 0.152 | 0.068 | 0.030 | 0.056 | 40 | 1,314 |
| 10 | 37.83 | 930 | 0.120 | 0.070 | 0.034 | 0.055 | 34 | 1,153 |
| 9 | 35.33 | 229 | 0.105 | 0.071 | 0.037 | 0.055 | 8 | 284 |
| 8 | 33.25 | 1,210 | 0.093 | 0.071 | 0.038 | 0.054 | 44 | 1,499 |
| 7 | 30.75 | 357 | 0.079 | 0.072 | 0.040 | 0.054 | 13 | 442 |
| 6 | 27.50 | 1,200 | 0.064 | 0.072 | 0.041 | 0.053 | 42 | 1,487 |
| 5 | 22.50 | 1,217 | 0.043 | 0.070 | 0.042 | 0.051 | 41 | 1,508 |
| 4 | 17.50 | 1,233 | 0.026 | 0.067 | 0.040 | 0.049 | 40 | 1,528 |
| 3 | 12.50 | 1,250 | 0.013 | 0.059 | 0.034 | 0.044 | 37 | 1,549 |
| 2 | 7.50 | 1,266 | 0.005 | 0.044 | 0.025 | 0.035 | 30 | 1,569 |

| | | | | | | | | |
|----------------------|--------|--------|--------|--------|--------|--------|-------|--------|
| 1 | 2.50 | 1,283 | 0.001 | 0.018 | 0.010 | 0.017 | 14 | 1,590 |
| CCI TPX-070821 | 150.00 | 45 | 1.890 | 1.980 | 1.140 | 0.370 | 11 | 56 |
| Raycap DC6-48-60-18- | 150.00 | 40 | 1.890 | 1.980 | 1.140 | 0.370 | 10 | 50 |
| CCI DTMAP7819VG12A | 150.00 | 115 | 1.890 | 1.980 | 1.140 | 0.370 | 28 | 143 |
| Ericsson RRUS-11 (50 | 150.00 | 150 | 1.890 | 1.980 | 1.140 | 0.370 | 37 | 186 |
| Ericsson RRUS 32 B2 | 150.00 | 159 | 1.890 | 1.980 | 1.140 | 0.370 | 39 | 197 |
| 10' Omni | 150.00 | 25 | 1.890 | 1.980 | 1.140 | 0.370 | 6 | 31 |
| Ericsson RRUS-32 (77 | 150.00 | 231 | 1.890 | 1.980 | 1.140 | 0.370 | 57 | 286 |
| Powerwave Allgon 777 | 150.00 | 105 | 1.890 | 1.980 | 1.140 | 0.370 | 26 | 130 |
| KMW AM-X-CD-16-65-00 | 150.00 | 97 | 1.890 | 1.980 | 1.140 | 0.370 | 24 | 120 |
| Quintel QS66512-3 (1 | 150.00 | 336 | 1.890 | 1.980 | 1.140 | 0.370 | 83 | 416 |
| Andrew SBNH-1D6565C | 150.00 | 61 | 1.890 | 1.980 | 1.140 | 0.370 | 15 | 75 |
| Round Platform w/ Ha | 150.00 | 2,000 | 1.890 | 1.980 | 1.140 | 0.370 | 494 | 2,479 |
| Kathrein Smart Bias | 134.00 | 10 | 1.508 | 0.522 | 0.553 | 0.147 | 1 | 12 |
| Site-Pro UWS6-NP | 134.00 | 276 | 1.508 | 0.522 | 0.553 | 0.147 | 27 | 342 |
| RFS APXV18-206517S-C | 134.00 | 79 | 1.508 | 0.522 | 0.553 | 0.147 | 8 | 98 |
| Andrew LNX-6515DS-VT | 134.00 | 154 | 1.508 | 0.522 | 0.553 | 0.147 | 15 | 191 |
| DragonWave Horizon C | 120.00 | 11 | 1.210 | 0.014 | 0.262 | 0.020 | 0 | 13 |
| 12" x 12" Junction B | 120.00 | 10 | 1.210 | 0.014 | 0.262 | 0.020 | 0 | 12 |
| Alcatel-Lucent RRH2x | 120.00 | 317 | 1.210 | 0.014 | 0.262 | 0.020 | 4 | 393 |
| Nokia FZHN Flexi RRH | 120.00 | 132 | 1.210 | 0.014 | 0.262 | 0.020 | 2 | 164 |
| Alcatel-Lucent 1900 | 120.00 | 180 | 1.210 | 0.014 | 0.262 | 0.020 | 2 | 223 |
| RFS APXVTM14-ALU-I20 | 120.00 | 169 | 1.210 | 0.014 | 0.262 | 0.020 | 2 | 209 |
| DragonWave A-ANT-11G | 120.00 | 48 | 1.210 | 0.014 | 0.262 | 0.020 | 1 | 59 |
| Commscope NNVV- | 120.00 | 232 | 1.210 | 0.014 | 0.262 | 0.020 | 3 | 288 |
| dB Systems 5100A | 105.00 | 21 | 0.926 | -0.121 | 0.098 | -0.048 | -1 | 26 |
| VertexRSI 101V VPD | 105.00 | 4 | 0.926 | -0.121 | 0.098 | -0.048 | 0 | 5 |
| dB Systems 5100A-D | 105.00 | 152 | 0.926 | -0.121 | 0.098 | -0.048 | -5 | 188 |
| Round Side Arm | 105.00 | 450 | 0.926 | -0.121 | 0.098 | -0.048 | -14 | 558 |
| | | 29,280 | 63.624 | 30.506 | 23.825 | 6.706 | 1,487 | 36,286 |

Load Case (0.9 - 0.2Sds) * DL + E EMAM

Seismic (Reduced DL) Equivalent Modal Analysis Method

| Segment | Height Above Base (ft) | Weight (lb) | a | b | c | Saz | Horizontal Force (lb) | Vertical Force (lb) |
|---------|------------------------|-------------|-------|--------|-------|--------|-----------------------|---------------------|
| 35 | 147.50 | 234 | 1.828 | 1.667 | 1.025 | 0.330 | 52 | 202 |
| 34 | 142.50 | 243 | 1.706 | 1.144 | 0.823 | 0.255 | 41 | 209 |
| 33 | 137.50 | 251 | 1.588 | 0.742 | 0.654 | 0.189 | 32 | 216 |
| 32 | 134.50 | 51 | 1.520 | 0.550 | 0.566 | 0.153 | 5 | 44 |
| 31 | 132.00 | 247 | 1.464 | 0.415 | 0.501 | 0.125 | 21 | 213 |
| 30 | 127.50 | 317 | 1.366 | 0.222 | 0.397 | 0.080 | 17 | 272 |
| 29 | 122.50 | 325 | 1.261 | 0.069 | 0.302 | 0.038 | 8 | 280 |
| 28 | 117.50 | 390 | 1.160 | -0.030 | 0.226 | 0.004 | 1 | 336 |
| 27 | 112.50 | 399 | 1.063 | -0.088 | 0.165 | -0.023 | -6 | 343 |
| 26 | 107.50 | 477 | 0.971 | -0.116 | 0.117 | -0.041 | -13 | 410 |
| 25 | 102.50 | 498 | 0.883 | -0.121 | 0.081 | -0.052 | -17 | 428 |
| 24 | 97.50 | 509 | 0.799 | -0.112 | 0.053 | -0.056 | -19 | 438 |
| 23 | 92.50 | 520 | 0.719 | -0.092 | 0.034 | -0.051 | -18 | 447 |
| 22 | 87.50 | 531 | 0.643 | -0.068 | 0.020 | -0.039 | -14 | 457 |
| 21 | 82.50 | 542 | 0.572 | -0.043 | 0.012 | -0.021 | -7 | 466 |
| 20 | 77.88 | 469 | 0.509 | -0.020 | 0.007 | -0.002 | -1 | 404 |
| 19 | 75.38 | 134 | 0.477 | -0.008 | 0.006 | 0.008 | 1 | 115 |
| 18 | 74.25 | 268 | 0.463 | -0.003 | 0.006 | 0.013 | 2 | 231 |
| 17 | 71.75 | 938 | 0.432 | 0.008 | 0.006 | 0.022 | 14 | 808 |
| 16 | 67.50 | 992 | 0.383 | 0.023 | 0.007 | 0.035 | 23 | 854 |
| 15 | 62.50 | 1,005 | 0.328 | 0.039 | 0.010 | 0.046 | 31 | 865 |
| 14 | 57.50 | 1,019 | 0.278 | 0.050 | 0.014 | 0.053 | 36 | 877 |
| 13 | 52.50 | 1,033 | 0.232 | 0.058 | 0.019 | 0.056 | 39 | 889 |
| 12 | 47.50 | 1,047 | 0.190 | 0.064 | 0.025 | 0.057 | 40 | 901 |

Site Number: 302475

Code: ANSI/TIA-222-G

© 2007 - 2019 by ATC IP LLC. All rights reserved.

Site Name: Sttn - Southington, CT

Engineering Number: OAA713367_C3_07

1/4/2019 4:03:27 PM

Customer: CLEARWIRE

| | | | | | | | | |
|----------------------|--------|--------|--------|--------|--------|--------|-------|--------|
| 11 | 42.50 | 1,060 | 0.152 | 0.068 | 0.030 | 0.056 | 40 | 913 |
| 10 | 37.83 | 930 | 0.120 | 0.070 | 0.034 | 0.055 | 34 | 801 |
| 9 | 35.33 | 229 | 0.105 | 0.071 | 0.037 | 0.055 | 8 | 197 |
| 8 | 33.25 | 1,210 | 0.093 | 0.071 | 0.038 | 0.054 | 44 | 1,041 |
| 7 | 30.75 | 357 | 0.079 | 0.072 | 0.040 | 0.054 | 13 | 307 |
| 6 | 27.50 | 1,200 | 0.064 | 0.072 | 0.041 | 0.053 | 42 | 1,033 |
| 5 | 22.50 | 1,217 | 0.043 | 0.070 | 0.042 | 0.051 | 41 | 1,047 |
| 4 | 17.50 | 1,233 | 0.026 | 0.067 | 0.040 | 0.049 | 40 | 1,062 |
| 3 | 12.50 | 1,250 | 0.013 | 0.059 | 0.034 | 0.044 | 37 | 1,076 |
| 2 | 7.50 | 1,266 | 0.005 | 0.044 | 0.025 | 0.035 | 30 | 1,090 |
| 1 | 2.50 | 1,283 | 0.001 | 0.018 | 0.010 | 0.017 | 14 | 1,104 |
| CCI TPX-070821 | 150.00 | 45 | 1.890 | 1.980 | 1.140 | 0.370 | 11 | 39 |
| Raycap DC6-48-60-18- | 150.00 | 40 | 1.890 | 1.980 | 1.140 | 0.370 | 10 | 34 |
| CCI DTMAPB7819VG12A | 150.00 | 115 | 1.890 | 1.980 | 1.140 | 0.370 | 28 | 99 |
| Ericsson RRUS-11 (50 | 150.00 | 150 | 1.890 | 1.980 | 1.140 | 0.370 | 37 | 129 |
| Ericsson RRUS 32 B2 | 150.00 | 159 | 1.890 | 1.980 | 1.140 | 0.370 | 39 | 137 |
| 10' Omni | 150.00 | 25 | 1.890 | 1.980 | 1.140 | 0.370 | 6 | 22 |
| Ericsson RRUS-32 (77 | 150.00 | 231 | 1.890 | 1.980 | 1.140 | 0.370 | 57 | 199 |
| Powerwave Allgon 777 | 150.00 | 105 | 1.890 | 1.980 | 1.140 | 0.370 | 26 | 90 |
| KMW AM-X-CD-16-65-00 | 150.00 | 97 | 1.890 | 1.980 | 1.140 | 0.370 | 24 | 83 |
| Quintel QS66512-3 (1 | 150.00 | 336 | 1.890 | 1.980 | 1.140 | 0.370 | 83 | 289 |
| Andrew SBNH-1D6565C | 150.00 | 61 | 1.890 | 1.980 | 1.140 | 0.370 | 15 | 52 |
| Round Platform w/ Ha | 150.00 | 2,000 | 1.890 | 1.980 | 1.140 | 0.370 | 494 | 1,721 |
| Kathrein Smart Bias | 134.00 | 10 | 1.508 | 0.522 | 0.553 | 0.147 | 1 | 9 |
| Site-Pro UWS6-NP | 134.00 | 276 | 1.508 | 0.522 | 0.553 | 0.147 | 27 | 238 |
| RFS APXV18-206517S-C | 134.00 | 79 | 1.508 | 0.522 | 0.553 | 0.147 | 8 | 68 |
| Andrew LNX-6515DS-VT | 134.00 | 154 | 1.508 | 0.522 | 0.553 | 0.147 | 15 | 132 |
| DragonWave Horizon C | 120.00 | 11 | 1.210 | 0.014 | 0.262 | 0.020 | 0 | 9 |
| 12" x 12" Junction B | 120.00 | 10 | 1.210 | 0.014 | 0.262 | 0.020 | 0 | 9 |
| Alcatel-Lucent RRH2x | 120.00 | 317 | 1.210 | 0.014 | 0.262 | 0.020 | 4 | 273 |
| Nokia FZHN Flexi RRH | 120.00 | 132 | 1.210 | 0.014 | 0.262 | 0.020 | 2 | 114 |
| Alcatel-Lucent 1900 | 120.00 | 180 | 1.210 | 0.014 | 0.262 | 0.020 | 2 | 155 |
| RFS APXVTM14-ALU-I20 | 120.00 | 169 | 1.210 | 0.014 | 0.262 | 0.020 | 2 | 145 |
| DragonWave A-ANT-11G | 120.00 | 48 | 1.210 | 0.014 | 0.262 | 0.020 | 1 | 41 |
| Commscope NNVV- | 120.00 | 232 | 1.210 | 0.014 | 0.262 | 0.020 | 3 | 200 |
| dB Systems 5100A | 105.00 | 21 | 0.926 | -0.121 | 0.098 | -0.048 | -1 | 18 |
| VertexRSI 101V VPD | 105.00 | 4 | 0.926 | -0.121 | 0.098 | -0.048 | 0 | 3 |
| dB Systems 5100A-D | 105.00 | 152 | 0.926 | -0.121 | 0.098 | -0.048 | -5 | 131 |
| Round Side Arm | 105.00 | 450 | 0.926 | -0.121 | 0.098 | -0.048 | -14 | 387 |
| | | 29,280 | 63.624 | 30.506 | 23.825 | 6.706 | 1,487 | 25,203 |

Load Case (1.2 + 0.2Sds) * DL + E EMAM Seismic Equivalent Modal Analysis Method

Calculated Forces

| Seg Elev (ft) | Pu FY (-) (kips) | Vu FX (-) (kips) | Tu MY (ft-kips) | Mu MZ (ft-kips) | Mu MX (ft-kips) | Resultant Moment (ft-kips) | phi Pn (kips) | phi Vn (kips) | phi Tn (ft-kips) | phi Mn (ft-kips) | Total Deflect (in) | Rotation (deg) | Ratio |
|---------------|------------------|------------------|-----------------|-----------------|-----------------|----------------------------|---------------|---------------|------------------|------------------|--------------------|----------------|-------|
| 0.00 | -34.70 | -1.48 | 0.00 | -176.62 | 0.00 | 176.62 | 3,136.53 | 1,568.27 | 4,731.25 | 2,336.59 | 0.00 | 0.00 | 0.054 |
| 5.00 | -33.13 | -1.46 | 0.00 | -169.23 | 0.00 | 169.23 | 3,092.06 | 1,546.03 | 4,560.72 | 2,252.37 | 0.01 | -0.02 | 0.053 |
| 10.00 | -31.58 | -1.43 | 0.00 | -161.93 | 0.00 | 161.93 | 3,046.49 | 1,523.25 | 4,391.58 | 2,168.84 | 0.04 | -0.04 | 0.052 |
| 15.00 | -30.05 | -1.40 | 0.00 | -154.76 | 0.00 | 154.76 | 2,999.83 | 1,499.91 | 4,223.96 | 2,086.05 | 0.10 | -0.06 | 0.051 |
| 20.00 | -28.54 | -1.37 | 0.00 | -147.75 | 0.00 | 147.75 | 2,952.07 | 1,476.04 | 4,057.95 | 2,004.07 | 0.17 | -0.08 | 0.050 |
| 25.00 | -27.05 | -1.34 | 0.00 | -140.90 | 0.00 | 140.90 | 2,901.93 | 1,450.96 | 3,891.94 | 1,922.08 | 0.27 | -0.10 | 0.049 |
| 30.00 | -26.61 | -1.33 | 0.00 | -134.22 | 0.00 | 134.22 | 2,830.35 | 1,415.18 | 3,701.25 | 1,827.91 | 0.38 | -0.12 | 0.048 |
| 31.50 | -25.11 | -1.29 | 0.00 | -132.23 | 0.00 | 132.23 | 2,808.88 | 1,404.44 | 3,644.98 | 1,800.12 | 0.42 | -0.13 | 0.048 |
| 35.00 | -24.83 | -1.28 | 0.00 | -127.73 | 0.00 | 127.73 | 2,758.78 | 1,379.39 | 3,515.36 | 1,736.10 | 0.53 | -0.15 | 0.047 |
| 35.67 | -23.67 | -1.25 | 0.00 | -126.88 | 0.00 | 126.88 | 2,225.24 | 1,112.62 | 2,894.88 | 1,429.67 | 0.55 | -0.15 | 0.053 |
| 40.00 | -22.36 | -1.21 | 0.00 | -121.47 | 0.00 | 121.47 | 2,194.35 | 1,097.17 | 2,791.07 | 1,378.40 | 0.69 | -0.17 | 0.052 |
| 45.00 | -21.06 | -1.18 | 0.00 | -115.41 | 0.00 | 115.41 | 2,157.69 | 1,078.84 | 2,672.25 | 1,319.72 | 0.88 | -0.19 | 0.050 |
| 50.00 | -19.78 | -1.14 | 0.00 | -109.52 | 0.00 | 109.52 | 2,119.93 | 1,059.96 | 2,554.56 | 1,261.60 | 1.09 | -0.21 | 0.049 |
| 55.00 | -18.52 | -1.11 | 0.00 | -103.81 | 0.00 | 103.81 | 2,081.07 | 1,040.54 | 2,438.12 | 1,204.10 | 1.32 | -0.24 | 0.047 |
| 60.00 | -17.27 | -1.08 | 0.00 | -98.27 | 0.00 | 98.27 | 2,041.12 | 1,020.56 | 2,323.03 | 1,147.26 | 1.58 | -0.26 | 0.046 |
| 65.00 | -16.04 | -1.06 | 0.00 | -92.87 | 0.00 | 92.87 | 1,992.10 | 996.05 | 2,200.59 | 1,086.79 | 1.87 | -0.28 | 0.044 |
| 70.00 | -14.88 | -1.04 | 0.00 | -87.59 | 0.00 | 87.59 | 1,932.46 | 966.23 | 2,070.05 | 1,022.32 | 2.18 | -0.31 | 0.043 |
| 73.50 | -14.55 | -1.04 | 0.00 | -83.94 | 0.00 | 83.94 | 1,451.36 | 725.68 | 1,558.37 | 769.62 | 2.41 | -0.32 | 0.049 |
| 75.00 | -14.38 | -1.04 | 0.00 | -82.37 | 0.00 | 82.37 | 1,443.19 | 721.60 | 1,535.11 | 758.14 | 2.51 | -0.33 | 0.048 |
| 75.75 | -13.80 | -1.04 | 0.00 | -81.59 | 0.00 | 81.59 | 1,439.07 | 719.54 | 1,523.51 | 752.40 | 2.56 | -0.34 | 0.048 |
| 75.75 | -13.80 | -1.04 | 0.00 | -81.59 | 0.00 | 81.59 | 1,439.07 | 719.54 | 1,523.51 | 752.40 | 2.56 | -0.34 | 0.118 |
| 80.00 | -13.13 | -1.06 | 0.00 | -77.17 | 0.00 | 77.17 | 1,415.26 | 707.63 | 1,458.06 | 720.08 | 2.87 | -0.36 | 0.116 |
| 85.00 | -12.47 | -1.08 | 0.00 | -71.89 | 0.00 | 71.89 | 1,386.24 | 693.12 | 1,381.78 | 682.41 | 3.28 | -0.42 | 0.114 |
| 90.00 | -11.82 | -1.11 | 0.00 | -66.50 | 0.00 | 66.50 | 1,356.12 | 678.06 | 1,306.38 | 645.17 | 3.76 | -0.49 | 0.112 |
| 95.00 | -11.19 | -1.13 | 0.00 | -60.97 | 0.00 | 60.97 | 1,324.90 | 662.45 | 1,231.99 | 608.43 | 4.31 | -0.56 | 0.109 |
| 100.00 | -10.57 | -1.16 | 0.00 | -55.31 | 0.00 | 55.31 | 1,293.04 | 646.52 | 1,159.10 | 572.44 | 4.94 | -0.63 | 0.105 |
| 105.00 | -9.20 | -1.18 | 0.00 | -49.53 | 0.00 | 49.53 | 1,245.33 | 622.66 | 1,074.67 | 530.74 | 5.63 | -0.70 | 0.101 |
| 110.00 | -8.71 | -1.19 | 0.00 | -43.60 | 0.00 | 43.60 | 1,197.61 | 598.80 | 993.42 | 490.61 | 6.40 | -0.77 | 0.096 |
| 110.00 | -8.71 | -1.19 | 0.00 | -43.60 | 0.00 | 43.60 | 833.77 | 416.88 | 695.90 | 343.68 | 6.40 | -0.77 | 0.137 |
| 115.00 | -8.22 | -1.20 | 0.00 | -37.63 | 0.00 | 37.63 | 813.89 | 406.95 | 652.08 | 322.04 | 7.25 | -0.84 | 0.127 |
| 120.00 | -6.46 | -1.16 | 0.00 | -31.64 | 0.00 | 31.64 | 792.92 | 396.46 | 608.75 | 300.64 | 8.17 | -0.93 | 0.113 |
| 125.00 | -6.06 | -1.14 | 0.00 | -25.85 | 0.00 | 25.85 | 770.85 | 385.43 | 566.02 | 279.54 | 9.19 | -1.01 | 0.100 |
| 130.00 | -5.76 | -1.12 | 0.00 | -20.14 | 0.00 | 20.14 | 747.69 | 373.84 | 524.00 | 258.78 | 10.28 | -1.08 | 0.086 |
| 134.00 | -5.05 | -1.06 | 0.00 | -15.65 | 0.00 | 15.65 | 728.37 | 364.19 | 490.97 | 242.47 | 11.21 | -1.14 | 0.071 |
| 135.00 | -4.74 | -1.02 | 0.00 | -14.59 | 0.00 | 14.59 | 722.05 | 361.03 | 481.88 | 237.98 | 11.45 | -1.15 | 0.068 |
| 140.00 | -4.44 | -0.98 | 0.00 | -9.49 | 0.00 | 9.49 | 686.26 | 343.13 | 435.03 | 214.85 | 12.68 | -1.20 | 0.051 |
| 145.00 | -4.15 | -0.92 | 0.00 | -4.61 | 0.00 | 4.61 | 650.48 | 325.24 | 390.59 | 192.90 | 13.96 | -1.24 | 0.030 |
| 150.00 | 0.00 | -0.83 | 0.00 | 0.00 | 0.00 | 0.00 | 614.69 | 307.34 | 348.53 | 172.13 | 15.26 | -1.25 | 0.000 |

Load Case (0.9 - 0.2Sds) * DL + E EMAM Seismic (Reduced DL) Equivalent Modal Analysis Method

Calculated Forces

| Seg Elev (ft) | Pu FY (-) (kips) | Vu FX (-) (kips) | Tu MY (ft-kips) | Mu MZ (ft-kips) | Mu MX (ft-kips) | Resultant Moment (ft-kips) | phi Pn (kips) | phi Vn (kips) | phi Tn (ft-kips) | phi Mn (ft-kips) | Total Deflect (in) | Rotation (deg) | Ratio |
|---------------|------------------|------------------|-----------------|-----------------|-----------------|----------------------------|---------------|---------------|------------------|------------------|--------------------|----------------|-------|
| 0.00 | -24.10 | -1.48 | 0.00 | -172.62 | 0.00 | 172.62 | 3,136.53 | 1,568.27 | 4,731.25 | 2,336.59 | 0.00 | 0.00 | 0.051 |
| 5.00 | -23.01 | -1.45 | 0.00 | -165.24 | 0.00 | 165.24 | 3,092.06 | 1,546.03 | 4,560.72 | 2,252.37 | 0.01 | -0.02 | 0.050 |
| 10.00 | -21.93 | -1.42 | 0.00 | -157.97 | 0.00 | 157.97 | 3,046.49 | 1,523.25 | 4,391.58 | 2,168.84 | 0.04 | -0.04 | 0.049 |
| 15.00 | -20.87 | -1.39 | 0.00 | -150.84 | 0.00 | 150.84 | 2,999.83 | 1,499.91 | 4,223.96 | 2,086.05 | 0.09 | -0.06 | 0.048 |
| 20.00 | -19.82 | -1.36 | 0.00 | -143.89 | 0.00 | 143.89 | 2,952.07 | 1,476.04 | 4,057.95 | 2,004.07 | 0.17 | -0.08 | 0.047 |
| 25.00 | -18.79 | -1.32 | 0.00 | -137.11 | 0.00 | 137.11 | 2,901.93 | 1,450.96 | 3,891.94 | 1,922.08 | 0.26 | -0.10 | 0.046 |
| 30.00 | -18.48 | -1.31 | 0.00 | -130.52 | 0.00 | 130.52 | 2,830.35 | 1,415.18 | 3,701.25 | 1,827.91 | 0.38 | -0.12 | 0.045 |
| 31.50 | -17.44 | -1.27 | 0.00 | -128.56 | 0.00 | 128.56 | 2,808.88 | 1,404.44 | 3,644.98 | 1,800.12 | 0.41 | -0.13 | 0.045 |
| 35.00 | -17.24 | -1.26 | 0.00 | -124.13 | 0.00 | 124.13 | 2,758.78 | 1,379.39 | 3,515.36 | 1,736.10 | 0.51 | -0.14 | 0.044 |
| 35.67 | -16.44 | -1.23 | 0.00 | -123.29 | 0.00 | 123.29 | 2,225.24 | 1,112.62 | 2,894.88 | 1,429.67 | 0.53 | -0.14 | 0.050 |
| 40.00 | -15.53 | -1.19 | 0.00 | -117.97 | 0.00 | 117.97 | 2,194.35 | 1,097.17 | 2,791.07 | 1,378.40 | 0.67 | -0.16 | 0.048 |
| 45.00 | -14.63 | -1.15 | 0.00 | -112.02 | 0.00 | 112.02 | 2,157.69 | 1,078.84 | 2,672.25 | 1,319.72 | 0.85 | -0.18 | 0.047 |
| 50.00 | -13.74 | -1.12 | 0.00 | -106.25 | 0.00 | 106.25 | 2,119.93 | 1,059.96 | 2,554.56 | 1,261.60 | 1.06 | -0.21 | 0.046 |
| 55.00 | -12.86 | -1.08 | 0.00 | -100.67 | 0.00 | 100.67 | 2,081.07 | 1,040.54 | 2,438.12 | 1,204.10 | 1.29 | -0.23 | 0.044 |
| 60.00 | -11.99 | -1.05 | 0.00 | -95.26 | 0.00 | 95.26 | 2,041.12 | 1,020.56 | 2,323.03 | 1,147.26 | 1.54 | -0.25 | 0.043 |
| 65.00 | -11.14 | -1.03 | 0.00 | -89.99 | 0.00 | 89.99 | 1,992.10 | 996.05 | 2,200.59 | 1,086.79 | 1.82 | -0.28 | 0.042 |
| 70.00 | -10.33 | -1.02 | 0.00 | -84.84 | 0.00 | 84.84 | 1,932.46 | 966.23 | 2,070.05 | 1,022.32 | 2.12 | -0.30 | 0.041 |
| 73.50 | -10.10 | -1.01 | 0.00 | -81.28 | 0.00 | 81.28 | 1,451.36 | 725.68 | 1,558.37 | 769.62 | 2.34 | -0.32 | 0.046 |
| 75.00 | -9.99 | -1.01 | 0.00 | -79.76 | 0.00 | 79.76 | 1,443.19 | 721.60 | 1,535.11 | 758.14 | 2.44 | -0.32 | 0.045 |
| 75.75 | -9.58 | -1.01 | 0.00 | -79.00 | 0.00 | 79.00 | 1,439.07 | 719.54 | 1,523.51 | 752.40 | 2.49 | -0.33 | 0.045 |
| 75.75 | -9.58 | -1.01 | 0.00 | -79.00 | 0.00 | 79.00 | 1,439.07 | 719.54 | 1,523.51 | 752.40 | 2.49 | -0.33 | 0.112 |
| 80.00 | -9.12 | -1.03 | 0.00 | -74.69 | 0.00 | 74.69 | 1,415.26 | 707.63 | 1,458.06 | 720.08 | 2.80 | -0.35 | 0.110 |
| 85.00 | -8.66 | -1.05 | 0.00 | -69.56 | 0.00 | 69.56 | 1,386.24 | 693.12 | 1,381.78 | 682.41 | 3.19 | -0.41 | 0.108 |
| 90.00 | -8.21 | -1.07 | 0.00 | -64.33 | 0.00 | 64.33 | 1,356.12 | 678.06 | 1,306.38 | 645.17 | 3.66 | -0.48 | 0.106 |
| 95.00 | -7.77 | -1.09 | 0.00 | -58.98 | 0.00 | 58.98 | 1,324.90 | 662.45 | 1,231.99 | 608.43 | 4.19 | -0.54 | 0.103 |
| 100.00 | -7.34 | -1.12 | 0.00 | -53.51 | 0.00 | 53.51 | 1,293.04 | 646.52 | 1,159.10 | 572.44 | 4.80 | -0.61 | 0.099 |
| 105.00 | -6.39 | -1.15 | 0.00 | -47.93 | 0.00 | 47.93 | 1,245.33 | 622.66 | 1,074.67 | 530.74 | 5.47 | -0.68 | 0.095 |
| 110.00 | -6.04 | -1.15 | 0.00 | -42.20 | 0.00 | 42.20 | 1,197.61 | 598.80 | 993.42 | 490.61 | 6.22 | -0.75 | 0.091 |
| 110.00 | -6.04 | -1.15 | 0.00 | -42.20 | 0.00 | 42.20 | 833.77 | 416.88 | 695.90 | 343.68 | 6.22 | -0.75 | 0.130 |
| 115.00 | -5.71 | -1.16 | 0.00 | -36.42 | 0.00 | 36.42 | 813.89 | 406.95 | 652.08 | 322.04 | 7.04 | -0.81 | 0.120 |
| 120.00 | -4.48 | -1.12 | 0.00 | -30.64 | 0.00 | 30.64 | 792.92 | 396.46 | 608.75 | 300.64 | 7.93 | -0.90 | 0.108 |
| 125.00 | -4.21 | -1.11 | 0.00 | -25.03 | 0.00 | 25.03 | 770.85 | 385.43 | 566.02 | 279.54 | 8.92 | -0.98 | 0.095 |
| 130.00 | -3.99 | -1.09 | 0.00 | -19.50 | 0.00 | 19.50 | 747.69 | 373.84 | 524.00 | 258.78 | 9.98 | -1.05 | 0.081 |
| 134.00 | -3.50 | -1.02 | 0.00 | -15.15 | 0.00 | 15.15 | 728.37 | 364.19 | 490.97 | 242.47 | 10.88 | -1.10 | 0.067 |
| 135.00 | -3.29 | -0.99 | 0.00 | -14.13 | 0.00 | 14.13 | 722.05 | 361.03 | 481.88 | 237.98 | 11.11 | -1.11 | 0.064 |
| 140.00 | -3.08 | -0.95 | 0.00 | -9.19 | 0.00 | 9.19 | 686.26 | 343.13 | 435.03 | 214.85 | 12.31 | -1.16 | 0.047 |
| 145.00 | -2.88 | -0.89 | 0.00 | -4.46 | 0.00 | 4.46 | 650.48 | 325.24 | 390.59 | 192.90 | 13.54 | -1.20 | 0.028 |
| 150.00 | 0.00 | -0.83 | 0.00 | 0.00 | 0.00 | 0.00 | 614.69 | 307.34 | 348.53 | 172.13 | 14.81 | -1.21 | 0.000 |

Site Number: 302475

Code: ANSI/TIA-222-G

© 2007 - 2019 by ATC IP LLC. All rights reserved.

Site Name: Sttn - Southington, CT

Engineering Number: OAA713367_C3_07

1/4/2019 4:03:27 PM

Customer: CLEARWIRE

Analysis Summary


| Load Case | Reactions | | | | | | Max Usage | |
|------------------------------|-----------------|-----------------|-----------------|---------------------|---------------------|---------------------|-----------|-------------------|
| | Shear FX (kips) | Shear FZ (kips) | Axial FY (kips) | Moment MX (ft-kips) | Moment MY (ft-kips) | Moment MZ (ft-kips) | Elev (ft) | Interaction Ratio |
| 1.2D + 1.6W | 23.98 | 0.00 | 35.08 | 0.00 | 0.00 | 2279.16 | 75.75 | 1.00 |
| 0.9D + 1.6W | 23.96 | 0.00 | 26.30 | 0.00 | 0.00 | 2245.15 | 75.75 | 0.97 |
| 1.2D + 1.0Di + 1.0Wi | 5.96 | 0.00 | 73.90 | 0.00 | 0.00 | 650.15 | 75.75 | 0.34 |
| (1.2 + 0.2Sds) * DL + E ELFM | 0.88 | 0.00 | 34.70 | 0.00 | 0.00 | 110.91 | 75.75 | 0.07 |
| (1.2 + 0.2Sds) * DL + E EMAM | 1.48 | 0.00 | 34.70 | 0.00 | 0.00 | 176.62 | 110.00 | 0.14 |
| (0.9 - 0.2Sds) * DL + E ELFM | 0.88 | 0.00 | 24.10 | 0.00 | 0.00 | 108.65 | 75.75 | 0.06 |
| (0.9 - 0.2Sds) * DL + E EMAM | 1.48 | 0.00 | 24.10 | 0.00 | 0.00 | 172.62 | 110.00 | 0.13 |
| 1.0D + 1.0W | 5.75 | 0.00 | 29.28 | 0.00 | 0.00 | 543.16 | 75.75 | 0.24 |

Additional Steel Summary

| Elev From (ft) | Elev To (ft) | Member | Intermediate Connectors | | | Upper Termination Connectors | | | | Lower Termination Connectors | | | | Max Member | | |
|----------------|--------------|----------------------|-------------------------|----------------|--------------|------------------------------|--------------|----------|------------|------------------------------|--------------|----------|------------|------------|-------------|-------|
| | | | VQ/I (lb/in) | Applied (kips) | phiVn (kips) | MQ/I (kips) | phiVn (kips) | Num Reqd | Num Actual | MQ/I (kips) | phiVn (kips) | Num Reqd | Num Actual | Pu (kip) | phiPn (kip) | Ratio |
| 0.00 | 75.7 | (4) SOL-#20 All Thre | 286.2 | 8.6 | 16.8 | 164.2 | 12.0 | 14 | 14 | 0.0 | 12.0 | 0 | 0 | 242.1 | 330.5 | 0.733 |

Site Name: Sttn- Southington, CT
 Site Number: 302475
 Engineering Number: OAA713367
 Engineer: Zackaryah.Hughes
 Date: 01/04/19
 Tower Type: MP

Program Last Updated: 5/13/2014



Design Loads (Factored) - Analysis per TIA-222-G Standards

Design / Analysis / Mapping:

| | Analysis | | |
|--|---------------------|-------------------------------------|-----------------------|
| Compression/Leg: | 35.1 k | Concrete Strength (f'_c): | 3000 psi |
| Uplift/Leg: | 0.0 k | Pad Tension Steel Depth: | 32.00 in |
| Total Shear: | 24.0 k | ϕ_{Shear} : | 0.75 |
| Moment: | 2279.2 k-ft | $\phi_{\text{Flexure / Tension}}$: | 0.90 |
| Tower + Appurtenance Weight: | 35.1 k | $\phi_{\text{Compression}}$: | 0.65 |
| Depth to Base of Foundation (l + t - h): | 8.00 ft | β : | 0.85 |
| Diameter of Pier (d): | 4.33 ft | Bottom Pad Rebar Size #: | 10 |
| Height of Pier above Ground (h): | 0.50 | # of Bottom Pad Rebar: | 36 |
| Width of Pad (W): | 18.00 ft | Pad Bottom Steel Area: | 45.72 in ² |
| Length of Pad (L): | 18.00 ft | Pad Steel F_y : | 60000 psi |
| Thickness of Pad (t): | 3.00 ft | Top Pad Rebar Size #: | 5 |
| Tower Leg Center to Center: | 0.00 ft | # of Top Pad Rebar: | 36 |
| Number of Tower Legs: | 1.0 (1 if MP or GT) | Pad Top Steel Area: | 11.16 in ² |
| Tower Center from Mat Center: | 0.00 ft | Pier Rebar Size #: | 11 |
| Depth Below Ground Surface to Water Table: | 9.00 ft | Pier Steel Area (Single Bar): | 1.56 in ² |
| Unit Weight of Concrete: | 150.0 pcf | # of Pier Rebar: | 52 |
| Unit Weight of Soil Above Water Table: | 115.0 pcf | Pier Steel F_y : | 60000 psi |
| Unit Weight of Water: | 62.4 pcf | Pier Cage Diameter: | 44.0 in |
| Unit Weight of Soil Below Water Table: | 52.6 pcf | Rebar Strain Limit: | 0.008 |
| Friction Angle of Uplift: | 0.0 Degrees | Steel Elastic Modulus: | 29000 ksi |
| Ultimate Coefficient of Shear Friction: | 0.35 | Tie Rebar Size #: | 4 |
| Ultimate Compressive Bearing Pressure: | 12000.0 psf | Tie Steel Area (Single Bar): | 0.20 in ² |
| Ultimate Passive Pressure on Pad Face: | 0.0 psf | Tie Spacing: | 12 in |
| $\phi_{\text{Soil and Concrete Weight}}$: | 0.9 | Tie Steel F_y : | 60000 psi |
| ϕ_{Soil} : | 0.75 | | |

Overturning Moment Usage

Design OTM: 2483.2 k-ft
 OTM Resistance: 2956.8 k-ft
 Design OTM / OTM Resistance: 0.84 Result: OK

Soil Bearing Pressure Usage

Net Bearing Pressure: 4414 psf
 Factored Nominal Bearing Pressure: 9000 psf
 Net Bearing Pressure/Factored Nominal Bearing Pressure: 0.49 Result: OK
 Load Direction Controlling Design Bearing Pressure: Diagonal to Pad Edge


Sliding Factor of Safety

Total Factored Sliding Resistance: 95.8 k
 Sliding Design / Sliding Resistance: 0.25 Result: OK

One Way Shear, Flexural Capacity, and Punching Shear

| | |
|---|--|
| Factored One Way Shear (V_u): | 165.8 k |
| One Way Shear Capacity (ϕV_c): | 498.2 k - ACI11.3.1.1 |
| $V_u / \phi V_c$: | 0.33 Result: OK |
| Load Direction Controlling Shear Capacity: | Diagonal to Pad Edge |
| Lower Steel Pad Factored Moment (M_u): | 987.1 k-ft |
| Lower Steel Pad Moment Capacity (ϕM_n): | 6148.2 k-ft - ACI10.3 |
| $M_u / \phi M_n$: | 0.16 Result: OK |
| Load Direction Controlling Flexural Capacity: | Parallel to Pad Edge |
| Upper Steel Pad Factored Moment (M_u): | 660.7 k-ft |
| Upper Steel Pad Moment Capacity (ϕM_n): | 1581.1 k-ft |
| $M_u / \phi M_n$: | 0.42 Result: OK |
| Lower Pad Flexural Reinforcement Ratio: | 0.0066 OK - Minimum Reinforcement Ratio Met - ACI10.5.1 |
| Upper Pad Flexural Reinforcement Ratio: | 0.0016 OK - Minimum Reinforcement Ratio Met - ACI10.5.1 |
| Lower Pad Reinforcement Spacing: | 6 in - Pad Reinforcing Spacing OK - ACI7.12.2.2 & 10.5.4 |
| Upper Pad Reinforcement Spacing: | 6 in - Pad Reinforcing Spacing OK - ACI7.12.2.2 & 10.5.4 |
| Factored Punching Shear (V_u): | 0.0 k |
| Nominal Punching Shear Capacity ($\phi_c V_n$): | 1386.9 k - ACI11.12.2.1 |
| $V_u / \phi V_c$: | 0.00 Result: OK |
| Factored Moment in Pier (M_u): | 2411.2 k-ft |
| Pier Moment Capacity (ϕM_n): | 7846.3 k-ft |
| $M_u / \phi M_n$: | 0.31 Result: OK |
| Factored Shear in Pier (V_u): | 24.0 k |
| Pier Shear Capacity (ϕV_n): | 175.7 k |
| $V_u / \phi V_c$: | 0.14 Result: OK |
| Pier Shear Reinforcement Ratio: | 0.0009 No Ties Necessary for Shear - ACI11.5.6.1 |
| Factored Tension in Pier (T_u): | 0.0 k |
| Pier Tension Capacity (ϕT_n): | 4380.5 k |
| $T_u / \phi T_n$: | 0.00 Result: OK |
| Factored Compression in Pier (P_u): | 35.1 k |
| Pier Compression Capacity (ϕP_n): | 2704.2 k - ACI10.3.6.2 |
| $P_u / \phi P_n$: | 0.01 Result: OK |
| Pier Compression Reinforcement Ratio: | 0.038 OK - Reinforcement Ratio Met - ACI10.9.1 & 10.8.4 |
| $M_u / \phi_B M_n + T_u / \phi_T T_n$: | 0.31 Result: OK |

Nominal and Design Moment Capacity and Factored Design Loads




Base Plate & Anchor Rod Analysis

| Pole Dimensions | | |
|--------------------|-------|----|
| Number of Sides | 12 | - |
| Diameter | 37.38 | in |
| Thickness | 0.375 | in |
| Orientation Offset | 0 | ° |

| Base Reactions | | |
|----------------|--------|------|
| Moment, Mu | 2279.2 | k-ft |
| Axial, Pu | 35.1 | k |
| Shear, Vu | 24.0 | k |
| Neutral Axis | 50 | ° |

| Report Capacities | | |
|-------------------|----------|--------|
| Component | Capacity | Result |
| Base Plate | 53% | Pass |
| Anchor Rods | 73% | Pass |
| Dwyidag | 48% | Pass |

| Base Plate | | |
|---------------------------|---------|-------------|
| Shape | Square | - |
| Width | 44 | in |
| Thickness | 2 1/2 | in |
| Grade | A572-60 | - |
| Yield Strength, Fy | 60 | ksi |
| Tensile Strength, Fu | 75 | ksi |
| Clip | 0 | in |
| Orientation Offset | 0 | ° |
| Anchor Rod Detail | c | $\eta=0.55$ |
| Clear Distance | N/A | in |
| Applied Moment, Mu | 1092.0 | k |
| Bending Stress, ϕMn | 2075.7 | k |



| Dwyidag Reinforcement | | |
|------------------------|-------|----|
| Quantity | 4 | - |
| Bar Size | #20 | in |
| Diameter, ϕ | 2.5 | in |
| Bracket Type | Angle | - |
| Circle | 44.26 | in |
| Orientation Offset | 0 | ° |
| Applied Force, Pu | 190.1 | k |
| Dwyidag Bar, ϕPn | 392.7 | k |

| Original Anchor Rods | | |
|------------------------|---------|-----|
| Arrangement | Cluster | - |
| Quantity | 8 | - |
| Diameter, ϕ | 2 1/4 | in |
| Bolt Circle | 44 | in |
| Grade | A615-75 | - |
| Yield Strength, Fy | 75 | ksi |
| Tensile Strength, Fu | 100 | ksi |
| Spacing | 6.0 | in |
| Orientation Offset | 0 | ° |
| Applied Force, Pu | 190.3 | k |
| Anchor Rods, ϕPn | 259.8 | k |

Calculations for Monopole Base Plate & Anchor Rod Analysis

Reaction Distribution

| Reaction | Shear Vu | Moment Mu | Factor |
|-------------------------------|-------------|--------------|--------|
| - | k | k-ft | - |
| Base Forces | 24.0 | 1379.1 | 0.61 |
| Anchor Rod Forces | 24.0 | 1379.1 | 0.61 |
| Additional Bolt (Grp1) Forces | 0.0 | 0.0 | 0.00 |
| Additional Bolt (Grp2) Forces | 0.0 | 0.0 | 0.00 |
| Dywidag Forces | 0.0 | 900.1 | 0.39 |
| Stiffener Forces | 0.0 | 0.0 | 0.00 |

Geometric Properties

| Section | Gross Area | Net Area | Individual Inertia | Threads per Inch | Moment of Inertia |
|-----------|-----------------|-----------------|--------------------|------------------|-------------------|
| - | in ² | in ² | in ⁴ | # | in ⁴ |
| Pole | 43.0934 | 3.5911 | 0.1692 | | 7376.38 |
| Bolt | 3.9761 | 3.2477 | 0.8393 | 4.5 | 6294.24 |
| Bolt1 | 0.0000 | 0.0000 | 0.0000 | 0 | 0.00 |
| Bolt2 | 0.0000 | 0.0000 | 0.0000 | 0 | 0.00 |
| Dywidag | 4.9087 | 4.9087 | 1.9175 | | 4814.56 |
| Stiffener | 0.0000 | 0.0000 | 0.0000 | | 0.00 |

| Base Plate | | |
|----------------------|--------|-----|
| Shape | Square | - |
| Width, W | 44 | in |
| Thickness, t | 2.5 | in |
| Yield Strength, Fy | 60 | ksi |
| Tensile Strength, Fu | 75 | ksi |
| Base Plate Chord | 23.219 | in |
| Detail Type | c | - |
| Detail Factor | 0.55 | - |
| Clear Distance | N/A | - |

| Anchor Rods | | |
|---------------------------|-------|-----|
| Anchor Rod Quantity, N | 8 | - |
| Rod Diameter, d | 2.25 | in |
| Bolt Circle, BC | 44 | in |
| Yield Strength, Fy | 75 | ksi |
| Tensile Strength, Fu | 100 | ksi |
| Applied Axial, Pu | 190.3 | k |
| Applied Shear, Vu | 0.3 | k |
| Compressive Capacity, φPn | 259.8 | k |
| Tensile Capacity, φRnt | 0.732 | OK |
| Interaction Capacity | 0.734 | OK |

| Base Plate Stiffeners | | |
|------------------------------|------|---|
| Applied Axial Force, Pu | 0.0 | k |
| Applied Horizontal Force, Vu | 0.00 | k |

| Vertical Weld | | |
|---|---------|---|
| Vert.-to-Stiffener a=e _x /l | #DIV/0! | - |
| Spacing Ratio, k | #DIV/0! | - |
| Weld Coefficient, C | #DIV/0! | - |
| Compressive Capacity, φPn | #DIV/0! | k |
| Vert.-to-Plate a=e _x /l | #DIV/0! | - |
| Spacing Ratio, k | #DIV/0! | - |
| Weld Coefficient, C | #DIV/0! | - |
| Shear Capacity, φVn | #DIV/0! | k |
| P _u /φ _p P _n + V _u /φ _v V _n | | |

| External Base Plate | | |
|-----------------------|--------|-----------------|
| Chord Length AA | 24.600 | in |
| Additional AA | 0.000 | in |
| Section Modulus, Z | 38.438 | in ³ |
| Applied Moment, Mu | 1092.0 | k-ft |
| Bending Capacity, φMn | 2075.7 | k-ft |
| Capacity, Mu/φMn | 0.526 | OK |

| Additional Bolt Group 1 | | |
|---------------------------|-----|-----|
| Bolt Quantity, N | 0 | - |
| Bolt Diameter, d | 0 | in |
| Bolt Circle, BC | 0 | in |
| Yield Strength, Fy | 0 | ksi |
| Tensile Strength, Fu | 0 | ksi |
| Applied Axial, Pu | 0.0 | k |
| Applied Shear, Vu | 0.0 | k |
| Compressive Capacity, φPn | 0.0 | k |
| Compressive Capacity, φPn | | |
| Interaction Capacity | | |

| Horizontal Weld | | |
|---|---------|----|
| Horz.-to-Stiffener a=e _x /l | 0.000 | - |
| Spacing Ratio, k | #DIV/0! | - |
| Weld Coefficient, C | #DIV/0! | - |
| Effective Fillet | 0.000 | in |
| Compressive Capacity, φPn | #DIV/0! | k |
| Horz.-to-Pole a=e _x /l | #DIV/0! | - |
| Spacing Ratio, k | #DIV/0! | - |
| Weld Coefficient, C | #DIV/0! | - |
| Shear Capacity, φVn | #DIV/0! | k |
| P _u /φ _p P _n + V _u /φ _v V _n | | |

| | | |
|-----------------------|--------|-----------------|
| Chord Length AB | 23.273 | in |
| Additional AB | 0.000 | in |
| Section Modulus, Z | 36.364 | in ³ |
| Applied Moment, Mu | 842.4 | k-ft |
| Bending Capacity, φMn | 1963.7 | k-ft |
| Capacity, Mu/φMn | 0.429 | OK |

| Additional Bolt Group 2 | | |
|---------------------------|-----|-----|
| Bolt Quantity, N | 0 | - |
| Bolt Diameter, d | 0 | in |
| Bolt Circle, BC | 0 | in |
| Yield Strength, Fy | 0 | ksi |
| Tensile Strength, Fu | 0 | ksi |
| Applied Axial, Pu | 0.0 | k |
| Applied Shear, Vu | 0.0 | k |
| Compressive Capacity, φPn | 0.0 | k |
| Compressive Capacity, φPn | | |
| Interaction Capacity | | |

| Plate Tension | | |
|-----------------------|-------|-----------------|
| Gross Cross Section | 0.000 | in ² |
| Net Cross Section | 0.000 | in ² |
| Tensile Capacity, φTn | 0.0 | k |
| Capacity, Tu/φTn | | |

| | | |
|-----------------------|-------|-----------------|
| Bend Line Length | 0.000 | in |
| Additional Bend Line | 0.000 | in |
| Section Modulus, Z | 0.000 | in ³ |
| Applied Moment, Mu | 0.0 | k-ft |
| Bending Capacity, φMn | 0.0 | k-ft |
| Capacity, Mu/φMn | | |

| Internal Base Plate | | |
|-----------------------|-------|-----------------|
| Arc Length | 0.000 | in |
| Section Modulus, Z | 0.000 | in ³ |
| Moment Arm | 0.000 | in |
| Applied Moment, Mu | 0.0 | k-ft |
| Bending Capacity, φMn | 0.0 | k-ft |
| Capacity, Mu/φMn | | |

| Dywidag Reinforcement | | |
|---------------------------|--------|-----|
| Dywidag Quantity, N | 4 | - |
| Dywidag Diameter, d | 2.5 | in |
| Bolt Circle, BC | 44.255 | in |
| Yield Strength, Fy | 80 | ksi |
| Tensile Strength, Fu | 100 | ksi |
| Applied Axial, Pu | 190.1 | k |
| Compressive Capacity, φPn | 392.7 | k |
| Capacity, Pu/φPn | 0.484 | OK |

| Plate Compression | | |
|---|---------|-----------------|
| Radius of Gyration | #DIV/0! | in ³ |
| kl/r | #DIV/0! | - |
| 4.71 √(E/Fy) | 0.00 | - |
| Buckling Stress(F _e) | 0.0 | - |
| Crit. Buckling Stress(F _{cr}) | 0.0 | ksi |
| Compressive Capacity, φPn | 0.0 | k |
| Capacity, Pu/φPn | | |

| | | |
|--------------------------|---------------------|--------------------------|
| Base/Flange Plate | Plate Type | Flange @ 110.0 ft |
| | Pole Diameter | 20.43 in |
| | Pole Thickness | 0.1875 in |
| | Plate Diameter | 28 in |
| | Plate Thickness | 1 in |
| | Plate Fy | 36 ksi |
| | Weld Length | 0.125 in |
| | ϕ_s Resistance | 347.07 k-in |
| | Applied | 83.60 k-in |
| Stiffeners | # | 12 Show |
| | Thickness | 0.75 in |
| | Length | 3 in |
| | Height | 6 in |
| | Chamfer | 0.75 in |
| | Offset Angle | 0° |
| | Fy | 50 ksi |

Code Rev. **G**

Date **1/4/2019**
 Engineer **Zackaryah.Hughes**
 Site # **302475**
 Carrier **CLEARWIRE CORPORATION**

Moment **277.1 k-ft**
 Axial **7.6 k**

| | | |
|--------------------|---------------------------------|---------------|
| Bolts | # | 12 |
| | Bolt Circle (R)adial / (S)quare | 25.75 in R |
| | Diameter | 1 in |
| | Hole Diameter | 1.125 in |
| | Type | A325 |
| | Fy | 92 ksi |
| | Fu | 120 ksi |
| | ϕ_s Resistance | 54.52 k |
| | Applied | 42.38 k |
| | Reinforcement | # |
| | | |
| Extra Bolts | # | 0 |
| | | |




Plate Stress Ratio:
0.24 (Pass)


Bolt Stress Ratio:
0.78 (Pass)

Mount Analysis Report

January 8, 2019

| | |
|----------------------|---|
| Site ID | CT52XC108 |
| Site Name | STTN – Southington |
| Client | Airosmith |
| Carrier | Sprint |
| Infinigy Job Number | 526-104 |
| Site Location | 80 Shuttle Meadow Road Southington, CT 06489 41° 38' 18.90" N NAD83 72° 50' 28.00" W NAD83 |
| Mount Centerline EL. | 120.0 ft |
| Mount Classification | Platform |
| Mount Usage | 56.4% |
| Overall Result | Contingent Pass |
| Note | Mount must be replaced with new SitePro1 RMQP-396 prior to installation of proposed appurtenances. |

Upon reviewing the results of this analysis, it is our opinion that the mount meets the specified TIA code requirements. The mounts and connections for the proposed carrier are therefore deemed adequate to support the final loading configuration as listed in this report.



Kevin Berger Jr.

Contents

| | |
|----------------------------------|----------|
| Introduction..... | 3 |
| Supporting Documentation..... | 3 |
| Analysis Code Requirements..... | 3 |
| Conclusion..... | 3 |
| Final Configuration Loading..... | 4 |
| Structure Usages..... | 4 |
| Mount Connection Reactions..... | 4 |
| Assumptions and Limitations..... | 5 |
| Calculations..... | Appended |

Introduction

Infinigy Engineering has been requested to perform a mount analysis on the existing Sprint mounts. All supporting documents have been obtained from the client and are assumed to be accurate and applicable to this site. The mount was analyzed using RISA-3D Version 17.0.2 analysis software.

Supporting Documentation

| | |
|-----------------------------|--|
| Colo App | Sprint Site ID #CT52XC108, dated December 6, 2018 |
| Construction Drawing | Infinigy Engineering Job #526-104, dated December 20, 2018 |
| Previous Analysis | Infinigy Engineering Job #526-104, dated January 19, 2018 |

Analysis Code Requirements

| | |
|-------------------------|--|
| Wind Speed | 97 mph (3-Second Gust, V_{ASD}) / 125 mph (3-Second Gust, V_{ULT}) |
| Wind Speed w/ ice | 50 mph (3-Second Gust, V_{ASD}) w/ 0.75" ice |
| TIA Revision | ANSI/TIA-222-G |
| Adopted IBC | 2015 IBC/ 2018 Connecticut State Building Code |
| Structure Class | II |
| Exposure Category | C |
| Topographic Category | 1 |
| Calculated Crest Height | 0 ft |

Conclusion

Upon reviewing the results of this analysis, it is our opinion that the mount meets the specified TIA code requirements. The mounts and connections for the proposed carrier are therefore deemed adequate to support the final loading configuration as listed in this report.

If you have any questions, require additional information, or actual conditions differ from those as detailed in this report please contact me via the information below:

Kevin Berger Jr.
1033 Watervliet Shaker Road
Albany NY 12205
(O) 518-690-0790 | Structural@Infinigy.com

Mount Analysis Report

January 8, 2019

Final Configuration Loading

| Mount CL (ft) | Rad. HT(ft) | Vert. O/S(ft) | Horiz. O/S(ft) ⁽¹⁾ | Qty | Appurtenance ⁽²⁾ | Carrier |
|---------------|-------------|---------------|-------------------------------|-----|---------------------------------|---------|
| 120.0 | 120.0 | 0.0 | 6.3 | 3 | Commscope NNVV-65B-R4 | Sprint |
| | | | 11.3 | 3 | RFS APXVTM14-ALU-I20 | |
| | | | 11.3 | 6 | Alcatel-Lucent 800 MHz 2x50 RRH | |
| | | | 6.3 | 3 | Alcatel-Lucent 1900 MHz 4x45 | |
| | | | 1.3 | 3 | Nokia Flexi RRH 8TR 2600 9x20W | |
| | | | 1.3 | 1 | DragonWave A-ANT-11G-2.5-C | |
| | | | 1.3 | 1 | DragonWave Horizon Compact | |

(1)Horizontal Offset is defined as the distance from the left most edge of the mount when viewed facing the tower.

(2)Radios are mounted behind antennas at respective locations see appended documents for vertical locations.

Structure Usages

| | | |
|----------------|--------------|-------------|
| Standoff | 56.4% | Pass |
| Horizontal | 37.4% | Pass |
| Mount Pipe | 56.1% | Pass |
| Results | 56.4% | Pass |

Mount Connection Reactions

| Reaction Data | Design Reactions | Analysis Reactions | Result |
|-------------------|------------------|--------------------|--------|
| Max Tension (lbs) | 12340.0 | 1855.1 | 15.0% |
| Max Shear (lbs) | 7770.0 | 2444.7 | 31.5% |
| Unity Check | -- | -- | 46.5% |

*Assumed (2) 1/2" A307 Anchors. Contractor to field to verify anchor diameters prior to proper installation.



- Anchor reactions are acceptable when compared to manufacturer's listed capacities.

Assumptions and Limitations

Our structural calculations are completed assuming all information provided to Infinigy Engineering is accurate and applicable to this site. For the purposes of calculations, we assume an overall structure condition of “like new” and all members and connections to be free of corrosion and/or structural defects. The structure owner and/or contractor shall verify the structure’s condition prior to installation of any proposed equipment. If actual conditions differ from those described in this report Infinigy Engineering should be notified immediately to complete a revised evaluation.

Our evaluation is completed using standard TIA, AISC, ACI, and ASCE methods and procedures. Our structural results are proprietary and should not be used by others as their own. Infinigy Engineering is not responsible for decisions made by others that are or are not based on our supplied assumptions and conclusions.

This report is an evaluation of the proposed carriers mount structure only and does not reflect adequacy of the existing tower, other mounts, or coax mounting attachments. These elements are assumed to be adequate for the purposes of this analysis and are assumed to have been installed per their manufacturer requirements.



Envelope Only Solution

Infinigy Engineering, PLLC.

KLB

526-104

CT52XC108

Final Configuration

Jan 8, 2019 at 12:15 PM

CT52XC108.r3d

| | |
|------------|-----------|
| Site Name: | CT52XC108 |
| Client: | Airosmith |
| Carrier: | Sprint |
| Engineer: | KLB |
| Date: | 1/8/2019 |



INFINIGY WIND LOAD CALCULATOR 3.0.2

Site Information Inputs:

| | |
|--------------------------|------------------|
| Adopted Building Code: | 2015 IBC |
| Structure Load Standard: | TIA-222-G |
| Antenna Load Standard: | TIA-222-G |
| Structure Risk Category: | II |
| Structure Type: | Mount - Platform |
| Number of Sectors: | 3 |
| Structure Shape 1: | Round |

Rooftop Inputs:

| | |
|-------------------------|----|
| Rooftop Wind Speed-Up?: | No |
|-------------------------|----|

Wind Loading Inputs:

| | | |
|-------------------------------|-------|-----------------------------|
| Design Wind Velocity: | 97 | mph (nominal 3-second gust) |
| Wind Centerline 1 (z_1): | 120.0 | ft |
| Side Face Angle (θ): | 60 | degrees |
| Exposure Category: | C | |
| Topographic Category: | 1 | |

| Wind with No Ice | | |
|------------------|------|----------------|
| q_z (psf) | Gh | F_{ST} (psf) |
| 30.09 | 1.00 | 36.11 |

| Wind with Ice | | |
|---------------|------|----------------|
| q_z (psf) | Gh | F_{ST} (psf) |
| 8.00 | 1.00 | 22.37 |

Ice Loading Inputs:

| | | |
|-------------------------|------|-----------------------------|
| Is Ice Loading Needed?: | Yes | |
| Ice Wind Velocity: | 50 | mph (nominal 3-second gust) |
| Base Ice Thickness: | 0.75 | in |

Input Appurtenance Information and Load Placements:

| Appurtenance Name | Elevation (ft) | Total Quantity | K_a | Front Shape | Side Shape | q_z (psf) | EPA (ft ²) | Fz (lbs) | Fx (lbs) | Fz(60) (lbs) | Fx(30) (lbs) |
|----------------------------------|----------------|----------------|-------|-------------|------------|-------------|------------------------|----------|----------|--------------|--------------|
| Commscope NNVV-65B-R4 | 120.0 | 3 | 1.00 | Flat | Flat | 30.09 | 12.27 | 369.29 | 173.04 | 222.10 | 320.23 |
| RFS APXVTM14-ALU-I20 | 120.0 | 3 | 1.00 | Flat | Flat | 30.09 | 6.34 | 190.87 | 108.56 | 129.14 | 170.29 |
| Alcatel-Lucent 800 MHz 2x50 RRH | 120.0 | 6 | 1.00 | Flat | Flat | 30.09 | 2.06 | 61.94 | 40.98 | 46.22 | 56.70 |
| Alcatel-Lucent 1900 MHz 4x45 RRH | 120.0 | 3 | 1.00 | Flat | Flat | 30.09 | 2.31 | 69.59 | 71.47 | 71.00 | 70.06 |
| Nokia Flexi RRH 8TR 2600 9x20W | 120.0 | 3 | 1.00 | Flat | Flat | 30.09 | 3.70 | 111.47 | 38.94 | 57.07 | 93.34 |
| DragonWave A-ANT-11G-2.5-C | 120.0 | 1 | 1.00 | Round | Round | 30.09 | 0.04 | 1.28 | 1.30 | 1.29 | 1.29 |
| DragonWave Horizon Compact | 120.0 | 1 | 1.00 | Flat | Flat | 30.09 | 0.36 | 10.96 | 10.96 | 10.96 | 10.96 |

Member Primary Data

| | Label | I Joint | J Joint | K Joint | Rotate(deg) | Section/Shape | Type | Design List | Material | Design Rules |
|----|-------|---------|---------|---------|-------------|----------------|------|-------------|-----------|--------------|
| 1 | M1 | N1 | N2 | | | HSS 4"x4"x1/4" | Beam | None | A53 Gr.B | Typical |
| 2 | M2 | N3 | N4 | | | Corner Plate | Beam | None | A53 Gr.B | Typical |
| 3 | M3 | N5 | N8 | | | HSS 4"x4"x1/4" | Beam | None | A53 Gr.B | Typical |
| 4 | M4 | N9 | N10 | | | Corner Plate | Beam | None | A53 Gr.B | Typical |
| 5 | M5 | N6 | N11 | | | HSS 4"x4"x1/4" | Beam | None | A53 Gr.B | Typical |
| 6 | M6 | N12 | N13 | | | Corner Plate | Beam | None | A53 Gr.B | Typical |
| 7 | M7 | N16 | N15 | | | 3" STD Pipe | Beam | None | A53 Gr.B | Typical |
| 8 | M8 | N19 | N18 | | | 3" STD Pipe | Beam | None | A53 Gr.B | Typical |
| 9 | M9 | N22 | N21 | | | 3" STD Pipe | Beam | None | A53 Gr.B | Typical |
| 10 | M10 | N26 | N27 | | | HSS 4"x4"x1/4" | Beam | None | A53 Gr.B | Typical |
| 11 | M11 | N28 | N29 | | | HSS 4"x4"x1/4" | Beam | None | A53 Gr.B | Typical |
| 12 | M12 | N30 | N31 | | | HSS 4"x4"x1/4" | Beam | None | A53 Gr.B | Typical |
| 13 | M13 | N33 | N34 | | | L2"x2"x1/8" | Beam | None | A36 Gr.36 | Typical |
| 14 | M14 | N32 | N35 | | 270 | L2"x2"x1/8" | Beam | None | A36 Gr.36 | Typical |
| 15 | M15 | N37 | N38 | | | L2"x2"x1/8" | Beam | None | A36 Gr.36 | Typical |
| 16 | M16 | N36 | N39 | | 270 | L2"x2"x1/8" | Beam | None | A36 Gr.36 | Typical |
| 17 | M17 | N41 | N42 | | | L2"x2"x1/8" | Beam | None | A36 Gr.36 | Typical |
| 18 | M18 | N40 | N43 | | 270 | L2"x2"x1/8" | Beam | None | A36 Gr.36 | Typical |
| 19 | MP1 | N100 | N101 | | | 2" STD Pipe | Beam | None | A53 Gr.B | Typical |
| 20 | MP2 | N102 | N103 | | | 2" STD Pipe | Beam | None | A53 Gr.B | Typical |
| 21 | MP3 | N104 | N105 | | | 2" STD Pipe | Beam | None | A53 Gr.B | Typical |
| 22 | MP7 | N112 | N113 | | | 2" STD Pipe | Beam | None | A53 Gr.B | Typical |
| 23 | MP8 | N114 | N115 | | | 2" STD Pipe | Beam | None | A53 Gr.B | Typical |
| 24 | MP9 | N116 | N117 | | | 2" STD Pipe | Beam | None | A53 Gr.B | Typical |
| 25 | MP4 | N106 | N107 | | | 2" STD Pipe | Beam | None | A53 Gr.B | Typical |
| 26 | MP5 | N108 | N109 | | | 2" STD Pipe | Beam | None | A53 Gr.B | Typical |
| 27 | MP6 | N110 | N111 | | | 2" STD Pipe | Beam | None | A53 Gr.B | Typical |

Material Takeoff

| | Material | Size | Pieces | Length[in] | Weight[K] |
|---|------------------|----------------|--------|------------|-----------|
| 1 | Hot Rolled Steel | | | | |
| 2 | A36 Gr.36 | L2x2x2 | 6 | 303.1 | 0 |
| 3 | A53 Gr.B | 6"x0.37" Plate | 3 | 36 | 0 |
| 4 | A53 Gr.B | HSS4x4x4 | 6 | 374.3 | .4 |
| 5 | A53 Gr.B | PIPE 2.0 | 9 | 648 | .2 |
| 6 | A53 Gr.B | PIPE 3.0 | 3 | 450 | .3 |
| 7 | Total HR Steel | | 27 | 1811.4 | .9 |

Basic Load Cases

| | BLC Description | Category | X Gravity | Y Gravity | Z Gravity | Joint | Point | Distributed Area(Me... | Surface(P... |
|----|-------------------------|----------|-----------|-----------|-----------|-------|-------|------------------------|--------------|
| 1 | Self Weight | DL | | -1 | | | 23 | 3 | |
| 2 | Wind Load AZI 000 | WLZ | | | | | 23 | 1 | |
| 3 | Wind Load AZI 090 | WLX | | | | | 23 | 1 | |
| 4 | Ice Weight | OL1 | | | | | 23 | 27 | 3 |
| 5 | Wind + Ice Load AZI ... | OL2 | | | | | 23 | 1 | |
| 6 | Wind + Ice Load AZI ... | OL3 | | | | | 23 | 1 | |
| 7 | Service Live 1 | LL | | | | 6 | | | |
| 8 | BLC 1 Transient Area... | None | | | | | | 60 | |
| 9 | BLC 2 Transient Area... | None | | | | | | 26 | |
| 10 | BLC 3 Transient Area... | None | | | | | | 22 | |
| 11 | BLC 4 Transient Area... | None | | | | | | 60 | |
| 12 | BLC 5 Transient Area... | None | | | | | | 26 | |
| 13 | BLC 6 Transient Area... | None | | | | | | 22 | |



Company : Infinigy Engineering, PLLC.
 Designer : KLB
 Job Number : 526-104
 Model Name : CT52XC108

Jan 8, 2019
 12:15 PM
 Checked By: _____

Load Combinations

| | Description | Sol. | PD | SR | BLC Fact. | BLC Fact. | BLC Fact. | BLC Fact. | BLC Fact. | BLC Fact. | BLC Fact. | BLC Fact. | BLC Fact. | BLC Fact. |
|----|--------------|------|----|----|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|
| 1 | 1.4D | Yes | Y | | DL | 1.4 | | | | | | | | |
| 2 | 1.2D + 1.6.. | Yes | Y | | DL | 1.2 | WLZ | 1.6 | | | | | | |
| 3 | 1.2D + 1.6.. | Yes | Y | | DL | 1.2 | WLZ | 1.386 | W... | .8 | | | | |
| 4 | 1.2D + 1.6.. | Yes | Y | | DL | 1.2 | WLZ | .8 | W... | 1.386 | | | | |
| 5 | 1.2D + 1.6.. | Yes | Y | | DL | 1.2 | | | W... | 1.6 | | | | |
| 6 | 1.2D + 1.6.. | Yes | Y | | DL | 1.2 | WLZ | -.8 | W... | 1.386 | | | | |
| 7 | 1.2D + 1.6.. | Yes | Y | | DL | 1.2 | WLZ | -1.3... | W... | .8 | | | | |
| 8 | 1.2D + 1.6.. | Yes | Y | | DL | 1.2 | WLZ | -1.6 | | | | | | |
| 9 | 1.2D + 1.6.. | Yes | Y | | DL | 1.2 | WLZ | -1.3... | W... | -.8 | | | | |
| 10 | 1.2D + 1.6.. | Yes | Y | | DL | 1.2 | WLZ | -.8 | W... | -1.3... | | | | |
| 11 | 1.2D + 1.6.. | Yes | Y | | DL | 1.2 | | | W... | -1.6 | | | | |
| 12 | 1.2D + 1.6.. | Yes | Y | | DL | 1.2 | WLZ | .8 | W... | -1.3... | | | | |
| 13 | 1.2D + 1.6.. | Yes | Y | | DL | 1.2 | WLZ | 1.386 | W... | -.8 | | | | |
| 14 | 0.9D + 1.6.. | Yes | Y | | DL | .9 | WLZ | 1.6 | | | | | | |
| 15 | 0.9D + 1.6.. | Yes | Y | | DL | .9 | WLZ | 1.386 | W... | .8 | | | | |
| 16 | 0.9D + 1.6.. | Yes | Y | | DL | .9 | WLZ | .8 | W... | 1.386 | | | | |
| 17 | 0.9D + 1.6.. | Yes | Y | | DL | .9 | | | W... | 1.6 | | | | |
| 18 | 0.9D + 1.6.. | Yes | Y | | DL | .9 | WLZ | -.8 | W... | 1.386 | | | | |
| 19 | 0.9D + 1.6.. | Yes | Y | | DL | .9 | WLZ | -1.3... | W... | .8 | | | | |
| 20 | 0.9D + 1.6.. | Yes | Y | | DL | .9 | WLZ | -1.6 | | | | | | |
| 21 | 0.9D + 1.6.. | Yes | Y | | DL | .9 | WLZ | -1.3... | W... | -.8 | | | | |
| 22 | 0.9D + 1.6.. | Yes | Y | | DL | .9 | WLZ | -.8 | W... | -1.3... | | | | |
| 23 | 0.9D + 1.6.. | Yes | Y | | DL | .9 | | | W... | -1.6 | | | | |
| 24 | 0.9D + 1.6.. | Yes | Y | | DL | .9 | WLZ | .8 | W... | -1.3... | | | | |
| 25 | 0.9D + 1.6.. | Yes | Y | | DL | .9 | WLZ | 1.386 | W... | -.8 | | | | |
| 26 | 1.2D + 1.0.. | Yes | Y | | DL | 1.2 | OL1 | 1 | | | | | | |
| 27 | 1.2D + 1.0.. | Yes | Y | | DL | 1.2 | OL1 | 1 | OL2 | 1 | | | | |
| 28 | 1.2D + 1.0.. | Yes | Y | | DL | 1.2 | OL1 | 1 | OL2 | .866 | OL3 | .5 | | |
| 29 | 1.2D + 1.0.. | Yes | Y | | DL | 1.2 | OL1 | 1 | OL2 | .5 | OL3 | .866 | | |
| 30 | 1.2D + 1.0.. | Yes | Y | | DL | 1.2 | OL1 | 1 | | | OL3 | 1 | | |
| 31 | 1.2D + 1.0.. | Yes | Y | | DL | 1.2 | OL1 | 1 | OL2 | -.5 | OL3 | .866 | | |
| 32 | 1.2D + 1.0.. | Yes | Y | | DL | 1.2 | OL1 | 1 | OL2 | -.866 | OL3 | .5 | | |
| 33 | 1.2D + 1.0.. | Yes | Y | | DL | 1.2 | OL1 | 1 | OL2 | -.1 | | | | |
| 34 | 1.2D + 1.0.. | Yes | Y | | DL | 1.2 | OL1 | 1 | OL2 | -.866 | OL3 | -.5 | | |
| 35 | 1.2D + 1.0.. | Yes | Y | | DL | 1.2 | OL1 | 1 | OL2 | -.5 | OL3 | -.866 | | |
| 36 | 1.2D + 1.0.. | Yes | Y | | DL | 1.2 | OL1 | 1 | | | OL3 | -.1 | | |
| 37 | 1.2D + 1.0.. | Yes | Y | | DL | 1.2 | OL1 | 1 | OL2 | .5 | OL3 | -.866 | | |
| 38 | 1.2D + 1.0.. | Yes | Y | | DL | 1.2 | OL1 | 1 | OL2 | .866 | OL3 | -.5 | | |
| 39 | 1.2D + 1.5.. | Yes | Y | | DL | 1.2 | LL | 1.5 | WLZ | .111 | | | | |
| 40 | 1.2D + 1.5.. | Yes | Y | | DL | 1.2 | LL | 1.5 | WLZ | .096 | W... | .056 | | |
| 41 | 1.2D + 1.5.. | Yes | Y | | DL | 1.2 | LL | 1.5 | WLZ | .056 | W... | .096 | | |
| 42 | 1.2D + 1.5.. | Yes | Y | | DL | 1.2 | LL | 1.5 | | | W... | .111 | | |
| 43 | 1.2D + 1.5.. | Yes | Y | | DL | 1.2 | LL | 1.5 | WLZ | -.056 | W... | .096 | | |
| 44 | 1.2D + 1.5.. | Yes | Y | | DL | 1.2 | LL | 1.5 | WLZ | -.096 | W... | .056 | | |
| 45 | 1.2D + 1.5.. | Yes | Y | | DL | 1.2 | LL | 1.5 | WLZ | -.111 | | | | |
| 46 | 1.2D + 1.5.. | Yes | Y | | DL | 1.2 | LL | 1.5 | WLZ | -.096 | W... | -.056 | | |
| 47 | 1.2D + 1.5.. | Yes | Y | | DL | 1.2 | LL | 1.5 | WLZ | -.056 | W... | -.096 | | |
| 48 | 1.2D + 1.5.. | Yes | Y | | DL | 1.2 | LL | 1.5 | | | W... | -.111 | | |
| 49 | 1.2D + 1.5.. | Yes | Y | | DL | 1.2 | LL | 1.5 | WLZ | .056 | W... | -.096 | | |
| 50 | 1.2D + 1.5.. | Yes | Y | | DL | 1.2 | LL | 1.5 | WLZ | .096 | W... | -.056 | | |



Company : Infinigy Engineering, PLLC.
 Designer : KLB
 Job Number : 526-104
 Model Name : CT52XC108

Jan 8, 2019
 12:15 PM
 Checked By: _____

Envelope Joint Reactions

| Joint | | X [lb] | LC | Y [lb] | LC | Z [lb] | LC | MX [lb-ft] | LC | MY [lb-ft] | LC | MZ [lb-ft] | LC | |
|-------|---------|--------|-----------|--------|----------|--------|-----------|------------|-----------|------------|-----------|------------|-----------|----|
| 1 | N6 | max | 1786.516 | 5 | 2232.943 | 36 | 1396.146 | 14 | 6513.316 | 45 | 4251.319 | 11 | 330.048 | 17 |
| 2 | | min | -1786.516 | 23 | 671.29 | 17 | -1396.146 | 8 | 1451.168 | 14 | -4251.83 | 5 | -571.498 | 11 |
| 3 | N5 | max | 1727.58 | 4 | 2444.681 | 31 | 1855.097 | 14 | -95.72 | 20 | 1571.214 | 7 | 5214.404 | 30 |
| 4 | | min | -1727.341 | 22 | 689.415 | 24 | -1855.163 | 8 | -3419.291 | 39 | -1569.809 | 25 | 549.005 | 23 |
| 5 | N1 | max | 1679.049 | 18 | 2158.897 | 37 | 1615.82 | 2 | -739.164 | 16 | 1440.847 | 15 | -890.511 | 23 |
| 6 | | min | -1679.475 | 12 | 567.946 | 18 | -1615.752 | 20 | -3234.47 | 47 | -1442.517 | 9 | -4800.072 | 42 |
| 7 | Totals: | max | 4781.07 | 5 | 6803.915 | 38 | 4867.057 | 14 | | | | | | |
| 8 | | min | -4781.07 | 23 | 2066.248 | 19 | -4867.057 | 8 | | | | | | |

Envelope AISC 14th(360-10): LRFD Steel Code Checks

| Member | Shape | Code Check | Loc[in] | LC | Shear | Loc[in] | Dir | LC | phi*Pnc | phi*Pnt | phi*Mn | phi*Mn | Cb | Eqn | |
|--------|-------|----------------|---------|--------|-------|---------|---------|----|---------|------------|---------|----------|----------|------|-------|
| 1 | M5 | HSS4x4x4 | .564 | 0 | 30 | .116 | 0 | z | 11 | 101755... | 106155 | 12311.25 | 12311.25 | 1 | H1-1b |
| 2 | MP2 | PIPE 2.0 | .561 | 36 | 8 | .046 | 36 | | 20 | 20866.7... | 32130 | 1871.625 | 1871.625 | 1... | H1-1b |
| 3 | M3 | HSS4x4x4 | .521 | 0 | 31 | .130 | 0 | z | 13 | 101755... | 106155 | 12311.25 | 12311.25 | 1 | H1-1b |
| 4 | M16 | L2x2x2 | .512 | 50.52 | 4 | .020 | 50.52 | z | 5 | 6508.508 | 15908.4 | 402.563 | 797.904 | 2... | H2-1 |
| 5 | MP8 | PIPE 2.0 | .497 | 36 | 23 | .042 | 36 | | 23 | 20866.7... | 32130 | 1871.625 | 1871.625 | 1... | H1-1b |
| 6 | MP5 | PIPE 2.0 | .496 | 36 | 17 | .042 | 36 | | 17 | 20866.7... | 32130 | 1871.625 | 1871.625 | 1... | H1-1b |
| 7 | M1 | HSS4x4x4 | .477 | 0 | 29 | .097 | 0 | y | 48 | 101755... | 106155 | 12311.25 | 12311.25 | 1 | H1-1b |
| 8 | M14 | L2x2x2 | .442 | 50.52 | 12 | .017 | 50.52 | z | 12 | 6508.508 | 15908.4 | 402.563 | 798.667 | 2... | H2-1 |
| 9 | M7 | PIPE 3.0 | .374 | 53.125 | 11 | .191 | 54.6... | | 4 | 59302.8... | 65205 | 5748.75 | 5748.75 | 1 | H1-1b |
| 10 | M13 | L2x2x2 | .354 | 50.52 | 21 | .011 | 50.52 | y | 28 | 6508.508 | 15908.4 | 402.563 | 788.455 | 2... | H2-1 |
| 11 | M15 | L2x2x2 | .334 | 50.52 | 6 | .016 | 50.52 | y | 6 | 6508.508 | 15908.4 | 402.563 | 813.39 | 2... | H2-1 |
| 12 | MP1 | PIPE 2.0 | .325 | 36 | 8 | .040 | 36 | | 20 | 20866.7... | 32130 | 1871.625 | 1871.625 | 1... | H1-1b |
| 13 | M4 | 6"x0.37" Pl... | .325 | 6 | 9 | .488 | 8.125 | y | 12 | 32988.6... | 69930 | 539.044 | 8741.25 | 1... | H1-1b |
| 14 | M18 | L2x2x2 | .313 | 50.52 | 8 | .011 | 50.52 | z | 37 | 6508.508 | 15908.4 | 402.563 | 704.355 | 1... | H2-1 |
| 15 | M9 | PIPE 3.0 | .311 | 53.125 | 7 | .191 | 54.6... | | 12 | 59302.8... | 65205 | 5748.75 | 5748.75 | 1 | H1-1b |
| 16 | MP7 | PIPE 2.0 | .298 | 36 | 5 | .037 | 36 | | 5 | 20866.7... | 32130 | 1871.625 | 1871.625 | 1... | H1-1b |
| 17 | MP4 | PIPE 2.0 | .298 | 36 | 5 | .037 | 36 | | 5 | 20866.7... | 32130 | 1871.625 | 1871.625 | 1... | H1-1b |
| 18 | M17 | L2x2x2 | .279 | 50.52 | 10 | .015 | 50.52 | y | 10 | 6508.508 | 15908.4 | 402.563 | 816.298 | 2... | H2-1 |
| 19 | M2 | 6"x0.37" Pl... | .274 | 6 | 8 | .312 | 3.875 | y | 10 | 32988.6... | 69930 | 539.044 | 8741.25 | 1... | H1-1b |
| 20 | M10 | HSS4x4x4 | .210 | 31.26 | 11 | .195 | 3.907 | y | 10 | 103885... | 106155 | 12311.25 | 12311.25 | 1 | H1-1b |
| 21 | M6 | 6"x0.37" Pl... | .194 | 6 | 3 | .597 | 8.125 | y | 5 | 32988.6... | 69930 | 539.044 | 8741.25 | 1... | H1-1b |
| 22 | M12 | HSS4x4x4 | .191 | 31.26 | 28 | .193 | 3.907 | y | 6 | 103885... | 106155 | 12311.25 | 12311.25 | 1 | H1-1b |
| 23 | M8 | PIPE 3.0 | .187 | 95.313 | 44 | .053 | 96.8... | | 2 | 59302.8... | 65205 | 5748.75 | 5748.75 | 1 | H1-1b |
| 24 | M11 | HSS4x4x4 | .173 | 31.26 | 27 | .126 | 58.6... | z | 5 | 103885... | 106155 | 12311.25 | 12311.25 | 1 | H1-1b |
| 25 | MP3 | PIPE 2.0 | .124 | 36 | 8 | .022 | 36 | | 20 | 20866.7... | 32130 | 1871.625 | 1871.625 | 1... | H1-1b |
| 26 | MP9 | PIPE 2.0 | .108 | 36 | 11 | .019 | 36 | | 23 | 20866.7... | 32130 | 1871.625 | 1871.625 | 1... | H1-1b |
| 27 | MP6 | PIPE 2.0 | .107 | 36 | 17 | .019 | 36 | | 17 | 20866.7... | 32130 | 1871.625 | 1871.625 | 1... | H1-1b |



RADIO FREQUENCY EMISSIONS ANALYSIS REPORT EVALUATION OF HUMAN EXPOSURE POTENTIAL TO NON-IONIZING EMISSIONS

SPRINT Existing Facility

Site ID: CT52XC108

STTN - Southington
80 Shuttle Meadow Road
Southington, CT 06489

March 27, 2019

EBI Project Number: 6219000803

| Site Compliance Summary | |
|---|------------------|
| Compliance Status: | COMPLIANT |
| Site total MPE% of FCC general population allowable limit: | 8.48 % |



March 27, 2019

SPRINT

Attn: RF Engineering Manager
1 International Boulevard, Suite 800
Mahwah, NJ 07495

Emissions Analysis for Site: **CT52XC108 – STTN - Southington**

EBI Consulting was directed to analyze the proposed SPRINT facility located at **80 Shuttle Meadow Road, Southington, CT**, for the purpose of determining whether the emissions from the Proposed SPRINT Antenna Installation located on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter ($\mu\text{W}/\text{cm}^2$). The number of $\mu\text{W}/\text{cm}^2$ calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits, therefore it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) – (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general population may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general population would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

General population exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter ($\mu\text{W}/\text{cm}^2$). The general population exposure limits for the 850 MHz Band is approximately $567 \mu\text{W}/\text{cm}^2$. The general population exposure limit for the 1900 MHz (PCS), 2500 MHz (BRS) and 11 GHz bands is $1000 \mu\text{W}/\text{cm}^2$. Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.



Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure. Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

CALCULATIONS

Calculations were done for the proposed SPRINT Wireless antenna facility located at **80 Shuttle Meadow Road, Southington, CT**, using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. Since SPRINT is proposing highly focused directional panel antennas, which project most of the emitted energy out toward the horizon, all calculations were performed assuming a lobe representing the maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB for directional panel antennas and 20 dB for highly focused parabolic microwave dishes, was focused at the base of the tower. For this report the sample point is the top of a 6-foot person standing at the base of the tower.

For all calculations, all equipment was calculated using the following assumptions:

- 1) 2 LTE channels (850 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 50 Watts per Channel.
- 2) 4 LTE channels (1900 MHz (PCS)) were considered for each sector of the proposed installation. These Channels have a transmit power of 40 Watts per Channel.
- 3) 3 LTE channels (2500 MHz (BRS)) were considered for each sector of the proposed installation. These Channels have a transmit power of 40 Watts per Channel.
- 4) 1 microwave channel (11 GHz) was considered for Sector C of the proposed installation. This channel has a transmit power of 1 Watt.



- 5) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 - Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.
- 6) For the following calculations, the sample point was the top of a 6-foot person standing at the base of the tower. The maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB for directional panel antennas and 20 dB for highly focused parabolic microwave dishes, was used in this direction. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 7) The antennas used in this modeling are the **Commscope NNVV-65B-R4 and the RFS APXVTM14-ALU-I20** for transmission in the 850 MHz, 1900 MHz (PCS) and 2500 MHz (BRS) frequency bands as well as the **Dragonwave A-ANT-11G-2.5-C** microwave dish for transmissions in the 11 GHz band. This is based on feedback from the carrier with regards to anticipated antenna selection. Maximum gain values for all antennas are listed in the Inventory and Power Data table below. The maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB for directional panel antennas and 20 dB for highly focused parabolic microwave dishes, was used for all calculations. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 8) The antenna mounting height centerlines of the proposed panel antennas and microwave dish are **120 feet** above ground level (AGL) for **Sector A**, **120 feet** above ground level (AGL) for **Sector B** and **120 feet** above ground level (AGL) for Sector C.
- 9) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.

All calculations were done with respect to uncontrolled / general population threshold limits.



SPRINT Site Inventory and Power Data by Antenna

| Sector: | A | Sector: | B | Sector: | C |
|--------------------|-----------------------------|--------------------|-----------------------------|--------------------|-----------------------------|
| Antenna #: | 1 | Antenna #: | 1 | Antenna #: | 1 |
| Make / Model: | Commscope NNVV-65B-R4 | Make / Model: | Commscope NNVV-65B-R4 | Make / Model: | Commscope NNVV-65B-R4 |
| Gain: | 12.75 / 15.05 dBd | Gain: | 12.75 / 15.05 dBd | Gain: | 12.75 / 15.05 dBd |
| Height (AGL): | 120 feet | Height (AGL): | 120 feet | Height (AGL): | 120 feet |
| Frequency Bands | 850 MHz / 1900 MHz (PCS) | Frequency Bands | 850 MHz / 1900 MHz (PCS) | Frequency Bands | 850 MHz / 1900 MHz (PCS) |
| Channel Count | 6 | Channel Count | 6 | Channel Count | 6 |
| Total TX Power(W): | 260 Watts | Total TX Power(W): | 260 Watts | Total TX Power(W): | 260 Watts |
| ERP (W): | 7,001.88 | ERP (W): | 7,001.88 | ERP (W): | 7,001.88 |
| Antenna A1 MPE% | 2.34% | Antenna B1 MPE% | 2.34% | Antenna C1 MPE% | 2.34% |
| Antenna #: | 2 | Antenna #: | 2 | Antenna #: | 2 |
| Make / Model: | RFS APXVTM14-ALU- I20 | Make / Model: | RFS APXVTM14-ALU- I20 | Make / Model: | RFS APXVTM14-ALU- I20 |
| Gain: | 15.9 dBd | Gain: | 15.9 dBd | Gain: | 15.9 dBd |
| Height (AGL): | 120 feet | Height (AGL): | 120 feet | Height (AGL): | 120 feet |
| Frequency Bands | 2500 MHz (BRS) | Frequency Bands | 2500 MHz (BRS) | Frequency Bands | 2500 MHz (BRS) |
| Channel Count | 3 | Channel Count | 3 | Channel Count | 3 |
| Total TX Power(W): | 120 Watts | Total TX Power(W): | 120 Watts | Total TX Power(W): | 120 Watts |
| ERP (W): | 4,668.54 | ERP (W): | 4,668.54 | ERP (W): | 4,668.54 |
| Antenna A2 MPE% | 1.29 % | Antenna B2 MPE% | 1.29 % | Antenna C2 MPE% | 1.29 % |

Microwave Backhaul Data

| Antenna Type: | Gain (dBd) | Height (feet AGL): | Frequency Bands | Channel Count | Total TX Power(W) | ERP (W) | MPE % | Sector |
|-------------------------------|------------|--------------------|-----------------|---------------|-------------------|----------|-------|--------|
| Dragonwave A-ANT-11G-2.5-C | 32.35 dBd | 120 | 11 GHz | 1 | 1 | 1,717.91 | 0.05 | C |

| Site Composite MPE% | |
|--------------------------|---------------|
| Carrier | MPE% |
| SPRINT – Sector C | 3.68 % |
| AT&T | 2.79 % |
| T-Mobile | 2.01 % |
| Site Total MPE %: | 8.48 % |

| | |
|------------------------|---------------|
| SPRINT Sector A Total: | 3.63 % |
| SPRINT Sector B Total: | 3.63 % |
| SPRINT Sector C Total: | 3.68 % |
| Site Total: | 8.48 % |

| SPRINT _ Frequency Band / Technology (Sector C) | # Channels | Watts ERP (Per Channel) | Height (feet) | Total Power Density ($\mu\text{W}/\text{cm}^2$) | Frequency (MHz) | Allowable MPE ($\mu\text{W}/\text{cm}^2$) | Calculated % MPE |
|---|------------|-------------------------|---------------|---|-----------------|---|------------------|
| Sprint 850 MHz LTE | 2 | 941.82 | 120 | 5.21 | 850 MHz | 567 | 0.92% |
| Sprint 1900 MHz (PCS) LTE | 4 | 1,279.56 | 120 | 14.16 | 1900 MHz (PCS) | 1000 | 1.42% |
| Sprint 2500 MHz (BRS) LTE | 3 | 1,556.18 | 120 | 12.91 | 2500 MHz (BRS) | 1000 | 1.29% |
| Sprint 11 GHz Microwave | 1 | 1,717.91 | 120 | 0.48 | 11 GHz | 1000 | 0.05% |
| Total: | | | | | | | 3.68% |

Summary

All calculations performed for this analysis yielded results that were **within** the allowable limits for general population exposure to RF Emissions.

The anticipated maximum composite contributions from the SPRINT facility as well as the site composite emissions value with regards to compliance with FCC's allowable limits for general population exposure to RF Emissions are shown here:

| SPRINT Sector | Power Density Value (%) |
|----------------------------------|-------------------------|
| Sector A: | 3.63 % |
| Sector B: | 3.63 % |
| Sector C: | 3.68 % |
| SPRINT Maximum MPE % (Sector C): | 3.68 % |
| | |
| Site Total: | 8.48 % |
| | |
| Site Compliance Status: | COMPLIANT |

The anticipated composite MPE value for this site assuming all carriers present is **8.48 %** of the allowable FCC established general population limit sampled at the ground level. This is based upon values listed in the Connecticut Siting Council database for existing carrier emissions.


FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.

Town of Southington

Geographic Information System (GIS)




Date Printed: 3/13/2019



MAP DISCLAIMER - NOTICE OF LIABILITY

This map is for assessment purposes only. It is not for legal description or conveyances. All information is subject to verification by any user. The Town of Southington and its mapping contractors assume no legal responsibility for the information contained herein.

Approximate Scale: 1 inch = 60 feet





Property Information

| | |
|-------------------|--|
| Property Location | 80 SHUTTLE MEADOW RD |
| Owner | SOUTHERN NEW ENGLAND TELEPHONE CO |
| Co-Owner | SITE# 302475 - STTN SOUTHTON CT |
| Mailing Address | C/O AMERICAN TOWER LAND MNGMT WOBURN MA 01801 |
| Land Use | 433V Radio, Television Trans Ld |
| Land Class | I |
| Water Service | |

| | |
|------------------|----------|
| Sewer Service | |
| Census Tract | 4303 |
| Neighborhood | 090 |
| Zoning Code | R-80 |
| Acreage | 0.17 |
| Book / Page | 331/ 320 |
| Lot Setting/Desc | |
| Trash Day | |

Photo



184 019 05/24/2015

Sketch

Primary Construction Details

| | |
|--------------------|--|
| Year Built | |
| Stories | |
| Building Style | |
| Building Use | |
| Building Condition | |
| Floors | |
| Total Rooms | |

| | |
|----------------|---|
| Bedrooms | 0 |
| Full Bathrooms | |
| Half Bathrooms | |
| Bath Style | |
| Kitchen Style | |
| Roof Style | |
| Roof Cover | |

| | |
|-------------------|---|
| Exterior Walls | |
| Interior Walls | |
| Heating Type | |
| Heating Fuel | |
| AC Type | |
| Gross Bldg Area | 0 |
| Total Living Area | 0 |



Valuation Summary (Assessed value = 70% of Appraised Value)

| Item | Appraised | Assessed |
|--------------|---------------|---------------|
| Buildings | | 0 |
| Outbuildings | 18560 | 12990 |
| Improvements | 18560 | 12990 |
| Extras | 0 | 0 |
| Land | 227860 | 159500 |
| Total | 246420 | 172490 |

Outbuilding and Extra Items

| Type | Description |
|---------------|--------------|
| Fence - Chain | 2600.00 L.F. |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

Sub Areas

| Subarea Type | Gross Area (sq ft) | Living Area (sq ft) |
|-------------------|--------------------|---------------------|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| Total Area | 0 | 0 |

Sales History

| Owner of Record | Book/ Page | Sale Date | Sale Price |
|-----------------------------------|------------|------------|------------|
| SOUTHERN NEW ENGLAND TELEPHONE CO | 331/ 320 | 1983-02-14 | 0 |