

September 3, 2015

Members of the Siting Council Connecticut Siting Council Ten Franklin Square New Britain, CT 06051

RE: Notice of Exempt Modification

555 E. Main Street, Stamford CT 06901

Longitude: -73 32 8.08 Latitude: 41 3 12.73

T-Mobile Site#: CT11410A_L700

Members of the Siting Council:

On behalf of T-Mobile, Northeast Site Solutions (NSS) is submitting an exempt modification application to the Connecticut Siting Council for modification of existing equipment at a tower facility located at 555 E. Main Street, Stamford CT 06901.

The 555 E. Main Street, Stamford, CT facility consists of a 125' Self Support Tower on a 106'-5" Rooftop. Both are owned and operated by Frontier Communications Corporation. In order to accommodate technological changes and enhance system performance in the State of Connecticut, T-Mobile plans to modify the equipment configurations at many of its existing cell sites. Please accept this letter and attachments as notification, pursuant to R.C.S.A. Section 16-50j-73, of construction which constitutes an exempt modification pursuant to R.C.S.A. Section 16-50j-72(b)(2). In compliance with R.C.S.A. Section 16-50j-73, a copy of this letter and attachments is being sent to the chief elected official of the municipality in which the affected cell site is located.

As part of T-Mobile's L700 Project, T-Mobile desires to upgrade their equipment to meet the new standards of 4G technology. The new equipment will allow customers to download files and browse the internet at a high rate of speed while also allowing their phones to be compatible with the latest 4G technology.

Attached is a summary of the planned modifications, including power density calculations reflecting the change in T-Mobile's operations at the site along with the required fee of \$625.



The changes to the facility do not constitute modifications as defined in Connecticut General Statutes significantly changed or altered. Rather, the planned changes to the facility fall squarely within those activities explicitly provided for in R.C.S.A. Section 16-50j-72(b)(2).

- 1. The overall height of the structure will be unaffected.
- 2. The proposed changes will not extend the site boundaries. There will be no effect on the site compound.
- 3. The proposed changes will not increase the noise level at the existing facility by six decibels or more.
- 4. The changes in radio frequency power density will not increase the calculated "worst case" power density for the combined operations at the site to a level at or above the applicable standard for uncontrolled environments as calculated for a mixed frequency site.

For the foregoing reasons, Northeast Site Solutions (NSS) on behalf of T-Mobile, respectfully submits that the proposed changes at the referenced site constitute exempt modifications under R.C.S.A.Section 16-50j-72(b)(2).

Please feel free to call me at 860.209.4690 with any questions you may have concerning this matter.

Sincerely,

Denise Sabo

Mobile: 860-209-4690 Fax: 413-521-0558

Office: 199 Brickyard Rd, Farmington, CT 06032 Email: denise@northeastsitesolutions.com

CC. City of Stamford- Zoning Enforcement Attn. David Klein, Structure owner- Frontier Communications Corp



Invoice Number Inv. Date Description Deductions Voucher **Amount Paid**

CT11410A-1

2/19/2015 Exempt Mod Filing Fees

0.00

1100314080

625.00

DO NOT ACCEPT THIS CHECK UNLESS THE FACE FADES FROM BLACK TO RED WITH LOGO IN BACKGROUND. THE BACK OF THIS DOCUMENT HAS HEAT-SENSITIVE INK THAT CHANGES FROM ORANGE TO YELLOW.

T-MOBILE USA, INC. 12920 SE 38th Street Bellevue, WA 98006 (425) 378-4000

The Bank of New York Mellon Pittsburgh, PA 60-160/433

3050114 2/23/2015 VID 2000011160

PAY \$62500

Order Of

*\$625.00

To CONNECTICUT SITING COUNCIL The

10 FRANKLIN SQ

NEW BRITAIN, CT 06051

VOID AFTER 180 DAYS

THIS CHECK CLEARS THROUGH POSITIVE PAY

Exhibit A

T - Mobile -

T-MOBILE NORTHEAST LLC

SITE #: CT11410A

SITE NAME: STAMFORD / DWTN

SITE ADDRESS:

555 E MAIN STREET

STAMFORD, CT, 06901

WIRELESS BROADBAND FACILITY

CONSTRUCTION DRAWINGS

(702CU CONFIGURATION)

VICINITY MAP



DO NOT SCALE DRAWINGS

CONTRACTOR SHALL VERIFY PLANS AND EXISTING DIMENSIONS AND CONDITIONS ON THE JOB SITE AND SHALL IMMEDIATELY NOTIFY THE ARCHITECT IN WRITING OF ANY DISCREPANCIES BEFORE PROCEEDING WITH THE WORK OR BE RESPONSIBLE FOR SAME.

CALL BEFORE YOU DIG:

CALL 800 922 4455, OR 811

CALL THREE WORKING DAYS PRIOR TO DIGGING SAFETY PRECAUTIONS SHALL BE IMPLEMENTED BY CONTRACTOR(S) AT ALTRENCHING IN ACCORDANCE WITH CURRENT OSHA STANDARDS.

COLOR CODE FOR UTILITY LOCATIONS

ELECTRIC - RED SEWER - GREEI GAS/OIL - YELLOW SURVEY - PINK TEL/CATV - ORANGE PROPOSED EXCAVATION - WHITE

RECLAIMED WATER

GENERAL NOTES

- 1. THE CONTRACTOR SHALL GIVE ALL NOTICES AND COMPLY WITH ALL LAWS, ORDINANCES. RULES, REGULATIONS AND LAWFUL ORDERS OF ANY PUBLIC AUTHORITY, MUNICIPAL AND UTILITY COMPANY SPECIFICATIONS, AND LOCAL AND STATE JURISDICTIONAL CODES BEARING ON THE PERFORMANCE OF THE WORK. THE WORK PERFORMED ON THE PROJECT AND THE MATERIALS INSTALLED SHALL BE IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS AND ORDINANCES.
- 2. THE ARCHITECT/ENGINEER HAVE MADE EVERY EFFORT TO SET FORTH IN THE CONSTRUCTION AND CONSTRUCT DOCUMENTS THE COMPLETE SCOPE OF WORK. THE CONTRACTOR BIDDING THE JOB IS NEVERTHELESS CAUTIONED THAT MINOR OMISSIONS OR ERRORS IN THE DRAWINGS AND OR SPECIFICATIONS SHALL NOT EXCUSE SAID CONTRACTOR FROM COMPLETING THE PROJECT AND IMPROVEMENTS IN ACCORDANCE WITH THE INTENT OF THESE DOCUMENTS.
- 3. THE CONTRACTOR OR BIDDER SHALL BEAR THE RESPONSIBILITY OF NOTIFYING (IN WRITING) THE T-MOBILE REPRESENTATIVE OF ANY CONFLICTS, ERRORS, OR OMISSIONS PRIOR TO THE SUBMISSION OF THE CONTRACTOR'S PROPOSAL OR PERFORMANCE OF WORK, IN THE EVENT OF DISCREPANCIES, THE CONTRACTOR SHALL PRICE THE MORE COSTLY OR EXPENSIVE WORK, UNLESS DIRECTED IN WRITING OTHERWISE
- 4. THE SCOPE OF WORK SHALL INCLUDE FURNISHING OF ALL MATERIALS, EQUIPMENT, LABOR AND ALL OTHER MATERIALS AND LABOR DEEMED NECESSARY TO COMPLETE THE WORK/PROJECT AS DESCRIBED HEREIN.
- THE CONTRACTOR SHALL VISIT THE JOB SITE PRIOR TO THE SUBMISSION OF BIDS OR PERFORMING WORK TO FAMILIARIZE HIMSELF WITH THE FIELD CONDITIONS AND TO VERIFY THAT THE PROJECT CAN BE CONSTRUCTED IN ACCORDANCE WITH THE CONTRACT DOCUMENTS.
- THE CONTRACTOR SHALL OBTAIN AUTHORIZATION TO PROCEED WITH CONSTRUCTION PRIOR TO STARTING WORK ON ANY ITEM NOT CLEARLY DEFINED BY THE CONSTRUCTION DRAWINGS/CONTRACT DOCUMENTS.
- 7. THE CONTRACTOR SHALL INSTALL ALL EQUIPMENT AND MATERIALS ACCORDING TO THE MANUFACTURER'S/VENDOR'S SPECIFICATIONS UNLESS NOTED OTHERWISE OR WHERE LOCAL CODES OR ORDINANCES TAKE PRECEDENCE.
- 8. THE CONTRACTOR SHALL PROVIDE A FULL SET OF CONSTRUCTION DOCUMENTS AT THE SITE UPDATED WITH THE LATEST REVISIONS AND ADDENDUM OR CLARIFICATIONS AVAILABLE FOR THE USE BY ALL PERSONNEL INVOLVED WITH THE PROJECT.

- 9. THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE PROJECT DESCRIBED HEREIN. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR ALL CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES AND FOR COORDINATING ALL PORTIONS OF THE WORK UNDER CONTRACT.
- 10. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ANY PERMITS AND INSPECTIONS WHICH ARE REQUIRED FOR THE WORK BY THE ARCHITECT/ENGINEER, THE STATE, COUNTY, OR LOCAL GOVERNMENT AUTHORITY
- 11. THE CONTRACTOR SHALL MAKE NECESSARY PROVISIONS TO PROTECT EXISTING IMPROVEMENTS, EASEMENTS, PAYING, CURBING, ETC., DURING CONSTRUCTION. UPON COMPLETION OF WORK, THE CONTRACTOR SHALL REPAIR ANY DAMAGE THAT MAY HAVE OCCURRED DUE TO CONSTRUCTION ON OR ABOUT THE PROPERTY
- 12. THE CONTRACTOR SHALL KEEP THE GENERAL WORK AREA CLEAN AND HAZARD FREE DURING CONSTRUCTION AND DISPOSE OF ALL DIRT, DEBRIS, RUBBISH AND REMOVE EQUIPMENT NOT SPECIFIED AS REMAINING ON PROPERTY. PREMISES SHALL BE LEFT IN CLEAN CONDITION AND FREE FROM PAINT SPOTS, DUST, OR SMUDGES OF ANY NATURE.
- 13. THE CONTRACTOR SHALL COMPLY WITH ALL OSHA REQUIREMENTS, AS WELL AS THE LATEST EDITIONS OF ANY PERTINENT STATE SAFFTY REGULATIONS.
- 14. THE CONTRACTOR SHALL NOTIFY THE T-MOBILE REPRESENTATIVE WHERE A CONFLICT OCCURS ON ANY OF THE CONTRACT DOCUMENTS. THE CONTRACTOR IS NOT TO ORDER MATERIAL OR CONSTRUCT ANY PORTION OF THE WORK THAT IS IN CONFLICT UNTIL CONFLICT IS RESOLVED BY THE T-MOBILE REPRESENTATIVE.
- 15. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS, ELEVATIONS, PROPERTY LINES, ETC., ON THE JOB.
- 16. THE CONTRACTOR SHALL RETURN ALL DISTURBED AREAS TO THEIR ORIGINAL CONDITION AT THE COMPLETION OF WORK.
- 17. REFER TO STRUCTURAL ANALYSIS AND TOWER MODIFICATION DESIGN DOCUMENT ENTITLED, "STRUCTURAL ANALYSIS REPORT PREPARED BY MALOUF ENGINEERING INTL., INC. (MEI PROJECT ID:CT02768S-15V2)
- "T-MOBILE SITE ID CT11410A", DATED JUNE 24, 2015.

SITE INFORMATION

SITE NUMBER: CT11410A

SITE NAME: STAMFORD / DWTN
SITE ADDRESS: 555 E MAIN STREET
STAMFORD, CT. 06901

LAT./LONG.: N 41.053535 / W -73.535579

JURISDICTION: FAIRFIELD COUNTY

PROPERTY OWNER: FRONTIER COMMUNICATIONS

805 CENTRAL EXPRESSWAY SOUTH ALLEN, TX 75013 972-908-4165 (O) 214-437-8156 (C) KELLEY.STEWART@FTR.COM

PROJECT SUB-CONTRACTORS

APPLICANT: T-MOBILE NORTHEAST, LLC. 35 GRIFFIN ROAD SOUTH

BLOOMFIELD, CT 06002 (860) 692-7100

PROJECT MANAGER LISA LIN ALLEN

NORTHEAST SITE SOLUTIONS 54 MAIN STREET STURBRIDGE, MA 01566 (508) 434-5237

ARCHITECT/ENGINEER: ATLANTIS GROUP INC.

1340 CENTRE STREET SUITE 212 NEWTON CENTER, MA 02459

(617) 965-0789

CODE COMPLIANCE

CONNECTICUT STATE BUILDING CODE

2005 CONNECTICUT BUILDING CODE WITH 2013 AMENDMENT 2011 NATIONAL ELECTRICAL CODE

CONSTRUCTION TYPE: 2B

USE GROUP: N/A

	SHEET INDEX
SHEET	DESCRIPTION
T-1	TITLE SHEET
N-1	GENERAL AND ELECTRICAL NOTES
A-1	SITE PLAN AND EQUIPMENT PLAN
A-2	ELEVATION AND DETAILS
E-1	GROUNDING DIAGRAM
E-2	GROUNDING DETAILS

T - Mobile -

T-MOBILE NORTHEAST, LLC

35 GRIFFIN ROAD SOUTH BLOOMFIELD, CT 06002 OFFICE: (860) 692-7100 EAX: (960) 692-7150

TLANTIS G R O U P

1340 Centre Street, Suite 21 Newton Center, MA 02459 Office: 617-965-0789 Fax: 617-213-5056

	SUBMITTALS	
DATE	DESCRIPTION	REVISION
07/15/15	ISSUED FOR REVIEW	Α
	•	

DEPT.	DATE	APP'D	REVISIONS
RFE			
RF MAN.			
ZONING			
OPS			
CONSTR.			
SITE AC.			

PROJECT NO:	CT11410A
DRAWN BY:	MB
CHECKED BY:	SM

PROFESSIONAL SEAL

THIS DOCUMENT IS THE CREATION, DESIGN, PROPERTY AND COPYRIGHTED WORK OF T-MOBILE. ANY DUPLICATION OR USE WITHOUT EXPRESS WRITTEN CONSENT IS STRICTLY PROHIBITED.

> SITE NAME CT11410A

> > SITE NAME

STAMFORD / DWTN

SITE ADDRESS

555 E MAIN STREET

STAMFORD, CT, 06901

SHEET TITLE

TITLE SHEET

SHEET NUMBER

T-1

ELECTRICAL NOTES:

- 1. INCLUDE ALL LABOR, MATERIALS, EQUIPMENT, PLANT SERVICES AND ADMINISTRATIVE TASKS REQUIRED TO COMPLETE AND MAKE OPERABLE THE ELECTRICAL WORK SHOWN ON THE DRAWINGS AND SPECIFIED HEREIN, INCLUDING BUT NOT LIMITED TO THE
- FOLLOWING:

 A. PREPARE AND SUBMIT SHOP DRAWINGS, DIAGRAMS AND
- B. PROCURE ALL NECESSARY PERMITS AND APPROVALS AND PAY ALL REQUIRED FEES AND CHARGES IN CONNECTION WITH THE WORK OF THIS CONTRACT.
- C. SUBMIT AS-BUILT DRAWINGS. OPERATING AND MAINTENANCE INSTRUCTIONS AND MANUALS.
- D. EXECUTE ALL CUTTING, DRILLING, ROUGH AND FINISH
 PATCHING OF EXISTING OR NEWLY INSTALLED CONSTRUCTION REQUIRED FOR THE WORK OF THIS CONTRACT. FOR SLAB PENETRATIONS THROUGH POST TENSION SLABS, X-RAY EXACT AREA OF PENETRATION PRIOR TO PERFORMING WORK COORDINATE ALL X-RAY WORK WITH BUILDING ENGINEER.
- E. PROVIDE HANGERS, SUPPORTS, FOUNDATIONS, STRUCTURAL FRAMING SUPPORTS, AND BASES FOR CONDUIT AND FOLIPMENT PROVIDED OR INSTALLED LINDER THE WORK OF HIS CONTRACT. PROVIDE COUNTER FLASHING, SLEEVES AND SEALS FOR FLOOR AND WALL PENETRATIONS
- F. MAINTAIN ALL EXISTING ELECTRICAL SERVICES IN THE BUILDING AREAS NOT AFFECTED BY THE ALTERATION DURING THE PROGRESS OF THE WORK INCLUDING PROVIDING ALL TEMPORARY JUMPERS. CONDUITS, CAPS, PROTECTIVE DEVICES, CONNECTIONS AND EQUIPMENT REQUIRED. PROVIDE TEMPORARY LIGHT AND POWER FOR CONSTRUCTION
- 2. IT IS THE INTENT OF THESE DRAWINGS AND SPECIFICATIONS TO CALL FOR AN INSTALLATION THAT IS COMPLETE IN EVERY RESPECT. IT IS NOT THE INTENT TO GIVE EVERY DETAIL ON THE DRAWINGS AND IN THE SPECIFICATIONS. IF AN ITEM OF WORK IS INDICATED IN THE DRAWINGS, IT IS CONSIDERED SUFFICIENT FOR INCLUSION IN THE CONTRACT. FURNISH AND INSTALL ALL MATERIAL AND EQUIPMENT USUALLY FURNISHED OR NEEDED TO MAKE A COMPLETE INSTALLATION WHETHER OR NOT SPECIFICALLY MENTIONED IN THE CONTRACT DOCUMENTS.

GENERAL REQUIREMENTS

- 1. PROVIDE ALL WORK IN ACCORDANCE WITH THE NATIONAL ELECTRICAL CODE (NEC) AND LOCAL AND STATE ELECTRICAL
- 2. THE ELECTRICAL PLANS ARE DIAGRAMMATIC ONLY. REFER TO THE ARCHITECTURAL PLANS FOR THE EXACT DIMENSIONS OF THE BUILDING.
- 3. LOAD CALCULATIONS ARE BASED ON EXISTING BUILDING INFORMATION/DRAWINGS PROVIDED TO ENGINEERING. CONTRACTOR IS TO VERIFY ALL EXISTING RATINGS AND LOADS PRIOR TO PURCHASING OF SPECIFIED EQUIPMENT FOR COMPLIANCE TO NEC. CONTRACTOR TO NOTIFY ENGINEER OF ANY DISCREPANCIES AND REQUEST FURTHER DIRECTION BY
- . EXISTING BUILDING EQUIPMENT IS NOTED ON THE DRAWINGS. NEW OR RELOCATED EQUIPMENT IS SHOWN WITH SOLID LINES.
 FUTURE EQUIPMENT (NOT IN THIS CONTRACT) IS DEPICTED WITH
 SHADED LINES. REQUEST CLARIFICATION OF DRAWINGS OR OF SPECIFICATIONS PRIOR TO PRICING OR INSTALLATION.

GENERAL

- A. AFTER CAREFULLY STUDYING THE DRAWINGS AND SPECIFICATIONS, AND BEFORE SUBMITTING THE PROPOSAL, MAKE A MANDATORY SITE VISIT TO ASCERTAIN CONDITIONS OF THE SITE, AND THE NATURE AND EXACT QUANTITY OF WORK TO BE PERFORMED. NO EXTRA COMPENSATION WILL BE ALLOWED FOR FAILURE TO NOTIFY THE OWNER. IN WRITING. OF ANY DISCREPANCIES THAT MAY HAVE BEEN NOTED BETWEEN THE EXISTING CONDITIONS AND THE DRAWINGS AND
- B. VERIFY ALL MEASUREMENTS AT THE SITE AND BE RESPONSIBLE FOR CORRECTNESS OF SAME.
 6. QUALITY, WORKMANSHIP, MATERIALS AND SAFETY
- A. PROVIDE NEW MATERIALS AND EQUIPMENT OF A DOMESTIC MANUFACTURER BY THOSE REGULARLY ENGAGED IN THE PRODUCTION AND MANUFACTURE OF SPECIFIED MATERIALS AND EQUIPMENT, WHERE UL, OR OTHER AGENCY, HAS ESTABLISHED STANDARDS FOR MATERIALS, PROVIDE MATERIALS WHICH ARE LISTED AND LABELED ACCORDINGLY. THE COMMERCIALLY STANDARD ITEMS OF EQUIPMENT AND THE SPECIFIC NAMES MENTIONED HEREIN ARE INTENDED FOR THE PROPER FUNCTIONING OF THE WORK.

 B. WORK SHALL BE PERFORMED BY WORKMEN SKILLED IN THE
- TRADE REQUIRED FOR THE WORK. INSTALL MATERIALS AND EQUIPMENT TO PRESENT A NEAT APPEARANCE WHEN COMPLETED AND IN ACCORDANCE WITH THE APPROVED RECOMMENDATIONS OF THE MANUFACTURER AND IN ACCORDANCE WITH CONTRACT DOCUMENTS C. PROVIDE LABOR, MATERIALS, APPARATUS AND APPLIANCES
- ESSENTIAL TO THE FUNCTIONING OF THE SYSTEMS DESCRIBED OR INDICATED HEREIN, OR WHICH MAY BE REASONABLY IMPLIED AS ESSENTIAL WHENEVER MENTIONED IN THI CONTRACT DOCUMENT OR NOT.
- D. MAKE WRITTEN REQUESTS FOR SUPPLEMENTARY INSTRUCTIONS TO ARCHITECT/ENGINEER IN CASE OF DOUBT AS TO WORK INTENDED OR IN EVENT OF NEED FOR
- E. PERFORMANCE AND MATERIAL REQUIREMENTS SCHEDULED OR SPECIFIED ARE MINIMUM STANDARD ACCEPTABLE. THE RIGHT TO JUDGE THE QUALITY OF EQUIPMENT THAT DEVIATES FROM THE CONTRACT DOCUMENT REMAINS SOLELY ARCHITECT/ENGINEER. CONTRACT DOCUMENT OR NOT

1. GUARANTEE MATERIALS. PARTS AND LABOR FOR WORK FOR ONE YEAR FROM THE DATE OF ISSUANCE OF OCCUPANCY PERMIT. DURING THAT PERIOD. MAKE GOOD FAULTS OR IMPERFECTIONS THAT MAY ARISE DUE TO DEFECTS OR OMISSIONS IN MATERIALS OR WORKMANSHIP WITH NO ADDITIONAL COMPENSATION AND AS

CI FANING

- 1. REMOVE ALL CONSTRUCTION DEBRIS RESULTING FROM THE
- 2. CLEAN EQUIPMENT AND SYSTEMS FOLLOWING THE COMPLETION OF THE PROJECT TO THE SATISFACTION OF THE ENGINEER.

COORDINATION AND SUPERVISION

 CAREFULLY LAY OUT ALL WORK IN ADVANCE TO AVOID UNNECESSARY CUTTING, CHANNELING, CHASING OR DRILLING OF FLOORS, WALLS, PARTITIONS, CEILINGS OR OTHER SURFACES. WHERE SUCH WORK IS NECESSARY, HOWEVER, PATCH AND REPAIR THE WORK IN AN APPROVED MANNER BY SKILLED MECHANICS AT NO ADDITIONAL COST TO THE OWNER. RENDER FULL COOPERATION TO OTHER TRADES WHERE WORK WILL B INSTALLED IN CLOSE PROXIMITY TO WORK OF OTHER TRADES. ASSIST IN WORKING OUT SPACE CONDITIONS IF WORK IS INSTALLED BEFORE COORDINATION WITH OTHER TRADES, OR CAUSES INTERFERENCE, MAKE CHANGES NECESSARY TO CORRECT CONDITIONS WITHOUT EXTRA CHARGE.

- 1 AS-RIJIT DRAWINGS:
- A. UPON COMPLETION OF THE WORK, FURNISH TO THE OWNER "AS-BUILT" DRAWINGS.
- A LIPON COMPLETION OF THE WORK FULLY INSTRUCT T-MOBILE AS TO THE OPERATION AND MAINTENANCE OF ALL MATERIAL, FOUIPMENT AND SYSTEMS.
- B. PROVIDE 3 COMPLETE BOUND SETS OF INSTRUCTIONS FOR OPERATING AND MAINTAINING ALL SYSTEMS AND EQUIPMENT.

CUTTING AND PATCHING

- I. PROVIDE ALL CUTTING, DRILLING, ROUGH AND FINISH PATCHING REQUIRED TO COMPLETE THE WORK.
 2. OBTAIN OWNER APPROVAL PRIOR TO CUTTING THROUGH FLOORS
- OR WALLS FOR PIPING OR CONDUIT

TESTS, INSPECTION AND APPROVAL

- . BEFORE ENERGIZING ANY ELECTRICAL INSTALLATION, INSPECT EACH UNIT IN DETAIL. TIGHTEN ALL BOLTS AND CONNECTIONS (TORQUE-TIGHTEN WHERE REQUIRED) AND DETERMINE THAT ALL COMPONENTS ARE ALIGNED, AND THE EQUIPMENT IS IN SAFE. OPERATIONAL CONDITION.

 2. PROVIDE THE COMPLETE ELECTRICAL SYSTEM FREE OF GROUND
- FAULTS AND SHORT CIRCUITS SUCH THAT THE SYSTEM WILL OPERATE SATISFACTORILY UNDER FULL LOAD CONDITIONS, WITHOUT EXCESSIVE HEATING AT ANY POINT IN THE SYSTEM.

SPECIAL REQUIREMENTS

- 1. DO NOT LEAVE ANY WORK INCOMPLETE NOR ANY HAZARDOUS SITUATIONS CREATED WHICH WILL AFFECT THE LIFE OR SAFETY OF THE PUBLIC AND/OR BUILDING OCCUPANTS. DO NOT INTERFERE WITH OR CUTOFF ANY OF THE EXISTING SERVICES WITHOUT THE OWNER'S WRITTEN PERMISSION.
- 2. WHEN NECESSARY TO TEMPORARILY DISCONNECT ANY EXISTING BUILDING UTILITIES AND SERVICE SYSTEMS, INCLUDING FEEDER OR BRANCH CIRCUITING SUPPLYING EXISTING FACILITIES, CONFER WITH THE OWNER AND ARRANGE THE PERIOD OF INTERRUPTION FOR A TIME MUTUALLY AGREED UPON. SHUTDOWN NOTE: SCHEDULE AND NOTIFY OWNER 48 HOURS PRIOR TO SHUTDOWN. ALL SHUTDOWN WORK TO BE SCHEDULED AT A TIME CONVENIENT TO OWNER.

- 1. ROUTE ALL GROUNDING CONDUCTORS AS SHOWN ON CONDUIT/GROUNDING RISER.
- 2 ROLLTE 500 KCMIL CIL THEN CONDUCTOR FROM THE MGR LOCATION TO BUILDING STEEL. VERIFY BUILDING STEEL IS EFFECTIVELY GROUNDED PER NEC TO THE MAIN SERVICE
- GROUNDING ELECTRODE CONDUCTOR (GEC).

 3. MAKE ALL GROUND CONNECTIONS FROM MGB TO ELECTRICAL EQUIPMENT WITH 2 HOLE, CRIMP TYPE, BURNDY COMPRESSION TERMINATIONS SIZED AS REQUIRED
- 4. USE 1 HOLE, CRIMP TYPE, BURNDY COMPRESSIONS TERMINATIONS, SIZED AS REQUIRED, AT EQUIPMENT GROUND
- 5. HIRE AN INDEPENDENT LAB TO PERFORM THE SPECIFIED OHMS TESTING. PROVIDE 4 SETS OF THE CERTIFIED DOCUMENTS TO THE OWNER FOR VERIFICATION PRIOR TO THE PROJECT

RACEWAYS

- 1. ALL WIRING TO BE INSTALLED IN CONDUIT SYSTEMS IN ACCORDANCE WITH THE FOLLOWING:
- A. EXTERIOR FEEDERS AND CONTROL, WHERE UNDERGROUND, TO BE IN SCH 40 PVC.
- B. EXTERIOR, ABOVE GROUND POWER CONDUITS TO BE GALVANIZED RIGID STEEL (RGS).
- C. ALL TELECOMMUNICATION CONDUITS, INTERIOR/EXTERIOR, TO D. INSTALL PULL ROPES IN ALL NEW EMPTY CONDUITS INSTALLED
- ON THIS PROJECT. E. ALL TELECOM CONDUITS AND PULL BOXES INSTALLED ON THIS PROJECT TO BE LABELED "T-MOBILE". OWNER WILL
- PROVIDE LABELS FOR CONTRACTOR TO INSTALL F. INTERIOR FEEDERS TO BE INSTALLED IN E.M.T. WITH STEEL COMPRESSION FITTINGS
- G. MINIMUM SIZE CONDUIT TO BE 3/4" TRADE SIZE
- UNLESS OTHERWISE INDICATED ON THE DRAWINGS.
 H. FINAL CONNECTIONS TO MOTORS AND VIBRATING EQUIPMENT TO BE INSTALLED IN LIQUID-TIGHT FLEXIBLE METAL CONDUIT.
- I. CONDUIT TO BE RUN CONCEALED IN CEILINGS, FINISHED AREAS OR DRYWALL PARTITIONS, UNLESS OTHERWISE NOTED J. THE ROUTING OF CONDUITS INDICATED ON THE DRAWINGS IS DIAGRAMMATIC. BEFORE INSTALLING ANY WORK, EXAMINE THE WORKING LAYOUTS AND SHOP DRAWINGS OF THE OTHER
- TRADES TO DETERMINE THE EXACT LOCATIONS AND K. ALL EXTERIOR MOUNTING HARDWARE TO BE GALVANIZED STEEL. COORDINATE WITH BUILDING ENGINEER PRIOR TO ATTACHING TO BUILDING STRUCTURE.

RACEWAYS CONT'D

- L. PENETRATIONS OF WALLS, FLOORS AND ROOFS, FOR THE PASSAGE OF ELECTRICAL RACEWAYS, TO BE PROPERLY SEALED AFTER INSTALLATION OF RACEWAYS SO AS TO MAINTAIN THE STRUCTURAL OR WATERPROOF INTEGRITY OF THE WALL, FLOOR OR ROOF SYSTEM TO BE PENETRATED.
 SEAL ALL CONDUIT PENETRATIONS THROUGH FIRE OR SMOKE RATED WALLS, CEILINGS OR SMOKE TIGHT CORRIDOR PARTITIONS TO MAINTAIN PROPER RATING OF WALL OR
- M. PROVIDE ALL CONDUIT ENDS WITH INSULATED METALLIC
- GROUNDING BUSHINGS.
 N. CONDUIT TO BE SUPPORTED AT MAXIMUM DISTANCE OF 8'-0", OR AS REQUIRED BY NEC, IN HORIZONTAL AND VERTICAL DIRECTIONS.
- O. PROVIDE STAINLESS STEEL BLANK COVER PLATES FOR ALL JUNCTION BOXES AND/OR OUTLET BOXES NOT USED IN EXPOSED AREAS. PROVIDE ALL OTHER UNUSED BOXES WITH STANDARD STEEL COVER PLATES.
- P. WHERE APPLICABLE, PROVIDE ROOFTOP CONDUIT SUPPORT SYSTEM, CONFORMING TO ROOFTOP WARRANTY REQUIREMENTS,

WIRES AND CARLES

- 1. CONTRACTOR TO COORDINATE WITH EQUIPMENT SUPPLIER AND VENDOR FOR EXACT EQUIPMENT OVER—CURRENT PROTECTION VOLTAGE, WIRE SIZE AND PLUG CONFIGURATION, IF APPLICABLE,
- 2. ALL EQUIPMENT/DEVICES TO BE PROVIDED WITH INSULATED GROUND CONDUCTOR
- 3. ALL WIRE AND CABLE TO BE 600VOLT, COPPER, WITH THWN/ THHN INSULATION EXCEPT AS NOTED
- 4. WIRE FOR POWER AND LIGHTING WILL NOT BE LESS THAN NO. 12AWG. ALL WIRE NO. 8 AND LARGER TO BE STRANDED. 5. CONTROL WIRING IS NOT TO BE LESS THAN NO. 14AWG,
- FLEXIBLE IN SINGLE CONDUCTORS OR MULTI-CONDUCTOR CABLES. CONTROL WIRING WILL CONSIST OF MULTI-CONDUCTOR CABLES WHEREVER POSSIBLE, CABLES TO BE PROVIDED WITH AN OVERALL FLAME-RETARDANT, EXTRUDED JACKET AND RATED FOR PLENUM USE, ALL CONTROL WIRE TO BE 600VOLT RATED 6. WIRE PREVIOUSLY PULLED INTO CONDUIT IS CONSIDERED USED
- AND IS NOT TO BE RE-PULLED. 7. HOME RUNS AND BRANCH CIRCUIT WIRING FOR 20A, 120V
- CIRCUITS: LENGTH (FT.) HOME RUN WIRE SIZE NO. 12 NO. 10 51 TO 100 101 TO 150
- 8. VOLTAGE DROP IS NOT TO EXCEED 3%. 9. MAKE ALL CONNECTIONS WITH UL APPROVED, SOLDERLESS,
- PRESSURE TYPE INSULATED CONNECTORS: SCOTCHLOK OR AND APPROVED EQUAL.
- 1. ALL RECEPTACLES INSTALLED IN THIS PROJECT TO BE GROUNDING TYPE, WITH GROUNDING PIN SLOT CONNECTED TO DEVICE GROUND SCREW FOR GROUND WIRE CONNECTION. DISCONNECT SWITCHES AND FUSES
- 1. DISCONNECT SWITCHES TO BE VOLTAGE—RATED TO SUIT THE CHARACTERISTICS OF THE SYSTEM FROM WHICH THEY ARE
- 2. PROVIDE HEAVY-DUTY, METAL-ENCLOSED, EXTERNALLY-OPERATED DISCONNECT SWITCHES, FUSED OR UNFUSED, OF SUCH TYPE AND SIZE AS REQUIRED TO PROPERLY PROTECT OR DISCONNECT THE LOAD FOR WHICH THEY ARE INTENDED.
- 3 PROVIDE NEMA 1 DISCONNECT SWITCHES FOR INTERIOR INSTALLATION, NEMA 3R FOR EXTERIOR INSTALLATION.
- 4 DISCONNECT SWITCHES TO BE MANUFACTURED BY A. GENERAL ELECTRIC COMPANY
- B SQUARE-D PROVIDE RK-1 TYPE FUSES, UNLESS NOTED OTHERWISE. INSTALLATION
- 1. INSTALL DISCONNECT SWITCHES WHERE INDICATED ON DRAWINGS
- 2. INSTALL FUSES IN FUSIBLE DISCONNECT SWITCHES. FUSES MUST MATCH IN TYPE AND RATING.
 3. FUSES TO BE MOUNTED SO THAT THE LABELS SHOWING THEIR RATINGS CAN BE READ WITHOUT REQUIRING FUSE REMOVAL.
- 4. FURNISH AND DEPOSIT SPARE FUSES AT THE JOB SITE AS
- A. THREE SPARES FOR EACH TYPE AND SIZE, IN EXCESS OF 60A, USED FOR INITIAL FUSING.
- B. TEN PERCENT SPARES FOR EACH TYPE AND SIZE, UP TO AND INCLUDING 60A, USED FOR INITIAL FUSING, IN NO CASE WILL LESS THAN THREE FUSES OF ONE PARTICULAR TYPE AND SIZE BE FURNISHED.

GENERAL NOTES:

INTENT

- 1. THESE SPECIFICATIONS AND CONSTRUCTION DRAWINGS ACCOMPANYING THEM DESCRIBE THE WORK TO BE DONE AND THE MATERIALS TO BE FURNISHED FOR CONSTRUCTION.
- 2. THE DRAWINGS AND SPECIFICATIONS ARE INTENDED TO BE FULLY EXPLANATORY AND SUPPLEMENTARY. HOWEVER, SHOULD ANYTHING BE SHOWN, INDICATED, OR SPECIFIED ON ONE AND NOT THE OTHER, IT SHALL BE DONE THE SAME AS IF SHOWN INDICATED OR SPECIFIED IN BOTH
- 3. THE INTENTION OF THE DOCUMENTS IS TO INCLUDE ALL LABOR AND MATERIALS REASONABLY NECESSARY FOR THE PROPER EXECUTION AND COMPLETION OF THE WORK AS STIPULATED IN THE CONTRACT.
- 4. THE PURPOSE OF THE SPECIFICATIONS IS TO INTERPRET THE INTENT OF THE DRAWINGS AND TO DESIGNATE THE METHOD OF THE PROCEDURE, TYPE AND QUALITY OF MATERIALS REQUIRED TO COMPLETE THE WORK.
- 5. MINOR DEVIATIONS FROM THE DESIGN LAYOUT ARE ANTICIPATED AND SHALL BE CONSIDERED AS PART OF THE WORK. NO CHANGES THAT ALTER THE CHARACTER OF THE WORK WILL BE MADE OR PERMITTED BY THE OWNER WITHOUT ISSUING A

CONFLICTS

- 1. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFICATIONS
 OF ALL MEASUREMENTS AT THE SITE BEFORE ORDERING ANY MATERIALS OR DOING ANY WORK. NO EXTRA CHARGE OR COMPENSATION SHALL BE ALLOWED DUE TO DIFFERENCE BETWEEN ACTUAL DIMENSIONS AND DIMENSIONS INDICATED ON THE CONSTRUCTION DRAWINGS. ANY SUCH DISCREPANCY IN DIMENSION WHICH MAY BE FOUND SHALL BE SUBMITTED TO THE OWNER FOR CONSIDERATION BEFORE THE CONTRACTOR
- PROCEEDS WITH THE WORK IN THE AFFECTED AREAS.

 2. THE BIDDER, IF AWARDED THE CONTRACT, WILL NOT BE ALLOWED ANY EXTRA COMPENSATION BY REASON OF ANY MATTER OR THING CONCERNING SUCH BIDDER MIGHT HAVE FULLY INFORMED THEMSELVES PRIOR TO THE BIDDING
- 3. NO PLEA OF IGNORANCE OF CONDITIONS THAT EXIST, OR OF DIFFICULTIES OR CONDITIONS THAT MAY BE ENCOUNTERED, OR OF ANY OTHER RELEVANT MATTER CONCERNING THE WORK TO BE PERFORMED IN THE EXECUTION OF THE WORK WILL BE ACCEPTED AS AN EXCUSE FOR ANY FAILURE OR OMISSION ON THE PART OF THE CONTRACTOR TO FULFILL EVERY DETAIL OF ALL THE REQUIREMENTS OF THE CONTRACT DOCUMENTS

CONTRACTS AND WARRANTIES

- 1. CONTRACTOR IS RESPONSIBLE FOR APPLICATION AND PAYMENT OF CONTRACTOR LICENSES AND BONDS.
- 2. SEE MASTER CONTRACTION SERVICES AGREEMENT FOR ADDITIONAL DETAILS.

 ALL MATERIALS MUST BE STORED IN A LEVEL AND DRY FASHION
 AND IN A MANNER THAT DOES NOT NECESSARILY OBSTRUCT THE RECOMMENDATIONS OF THE ASSOCIATED MANUFACTURER.

- 1. THE CONTRACTORS SHALL, AT ALL TIMES, KEEP THE SITE FREE FROM ACCUMULATION OF WASTE MATERIALS OR RUBBISH CAUSED BY THEIR EMPLOYEES AT WORK AND AT THE COMPLETION OF THE WORK. THEY SHALL REMOVE ALL RUBBISH FROM AND ABOUT THE BUILDING AREA, INCLUDING ALL THEIR TOOLS, SCAFFOLDING AND SURPLUS MATERIALS AND SHALL LEAVE THEIR WORK CLEAN AND READY TO USE
- EXTERIOR A. VISUALLY INSPECT EXTERIOR SURFACES AND REMOVE ALL TRACES OF SOIL, WASTE MATERIALS, SMUDGES AND OTHER B. REMOVE ALL TRACES OF SPLASHED MATERIALS FROM
- ADJACENT SURFACES.
 C. IF NECESSARY, TO ACHIEVE A UNIFORM DEGREE OF
- CLEANLINESS, HOSE DOWN THE EXTERIOR OF THE STRUCTURE. A. VISUALLY INSPECT INTERIOR SURFACE AND REMOVE ALL TRACES OF SOIL, WASTE MATERIALS, SMUDGES AND OTHER FOREIGN MATTER FROM WALLS, FLOOR, AND CEILING.

B. REMOVE ALL TRACES OF SPLASHED MATERIALS FROM

ADJACENT SURFACES. C. REMOVE PAINT DROPPINGS, SPOTS, STAINS, AND DIRT FROM FINISHED SURFACES.

CHANGE ORDER PROCEDURE:
1. REFER TO SECTION 17 OF SIGNED MCSA: SEE PROFESSIONAL SERVICE AGREEMENT FOR MCSA

RELATED DOCUMENTS AND COORDINATION

1. GENERAL CARPENTRY, ELECTRICAL AND ANTENNA DRAWINGS ARE INTERRELATED. IN PERFORMANCE OF THE WORK, THE CONTRACTOR MUST REFER TO ALL DRAWINGS. ALL COORDINATION TO BE THE RESPONSIBILITY OF THE CONTRACTOR

- 1. CONTRACTOR SHALL SUBMIT SHOP DRAWINGS AS REQUIRED AND LISTED IN THESE SPECIFICATIONS TO THE OWNER FOR
- 2. ALL SHOP DRAWINGS SHALL BE REVIEWED, CHECKED AND CORRECTED BY CONTRACTOR PRIOR TO SUBMITTAL TO THE

PRODUCTS AND SUBSTITUTIONS

- 1. SUBMIT 3 COPIES OF EACH REQUEST FOR SUBSTITUTION. IN EACH REQUEST, IDENTIFY THE PRODUCT OR FABRICATION OR INSTALLATION METHOD TO BE REPLACED BY THE SUBSTITUTION. INCLUDE RELATED SPECIFICATION SECTION AND DRAWING NUMBERS AND COMPLETE DOCUMENTATION SHOWING COMPLIANCE WITH THE REQUIREMENTS FOR SUBSTITUTIONS
 2. SUBMIT ALL NECESSARY PRODUCT DATA AND CUT SHEETS
- WHICH PROPERLY INDICATE AND DESCRIBE THE ITEMS, PRODUCTS AND MATERIALS BEING INSTALLED. THE CONTRACTOR SHALL, IF DEEMED NECESSARY BY THE OWNER, SUBMIT ACTUAL SAMPLES TO THE OWNER FOR APPROVAL IN LIEU OF CUT

QUALITY ASSURANCE

1. ALL WORK SHALL BE IN ACCORDANCE WITH APPLICABLE LOCAL,
STATE AND FEDERAL REGULATIONS. THESE SHALL INCLUDE, BUT
NOT BE LIMITED TO THE APPLICABLE CODES SET FORTH BY THE LOCAL GOVERNING BODY, SEE "CODE COMPLIANCE" T-1.

ADMINISTRATION 1. BEFORE THE COMMENCEMENT OF ANY WORK, THE CONTRACTOR WILL ASSIGN A PROJECT MANAGER WHO WILL ACT AS A SINGLE POINT OF CONTACT FOR ALL PERSONNEL INVOLVED IN THIS PROJECT. THIS PROJECT MANAGER WILL DEVELOP A MASTER SCHEDULE FOR THE PROJECT WHICH WILL BE SUBMITTED TO

- THE OWNER PRIOR TO THE COMMENCEMENT OF ANY WORK.
 2. SUBMIT A BAR TYPE PROGRESS CHART, NOT MORE THAN 3 DAYS AFTER THE DATE ESTABLISHED FOR COMMENCEMENT OF THE WORK ON THE SCHEDULE, INDICATING A TIME BAR FOR EACH MAJOR CATEGORY OR UNIT OF WORK TO BE PERFORMED AT THE SITE, PROPERLY SEQUENCED AND COORDINATED WITH OTHER ELEMENTS OF WORK AND SHOWING COMPLETION OF THE WORK SUFFICIENTLY IN ADVANCE OF THE DATE ESTABLISHED FOR SUBSTANTIAL COMPLETION OF THE WORK.

 3. PRIOR TO COMMENCING CONSTRUCTION, THE OWNER SHALL
- SCHEDULE AN ON-SITE MEETING WITH ALL MAJOR PARTIES. THIS WOULD INCLUDE, BUT NOT LIMITED TO, THE OWNER, PROJECT MANAGER, CONTRACTOR, LAND OWNER REPRESENTATIVE, LOCAL TELEPHONE COMPANY, TOWER ERECTION FOREMAN (IF SUBCONTRACTED).
 4. CONTRACTOR SHALL BE EQUIPPED WITH SOME MEANS OF
- CONSTANT COMMUNICATIONS, SUCH AS A MOBILE PHONE OR A BEEPER. THIS EQUIPMENT WILL NOT BE SUPPLIED BY THE
- OWNER, NOR WILL WIRELESS SERVICE BE ARRANGED.
 5. DURING CONSTRUCTION, CONTRACTOR MUST ENSURE THAT EMPLOYEES AND SUBCONTRACTORS WEAR HARD HATS AT ALL TIMES. CONTRACTOR WILL COMPLY WITH ALL WPCS SAFETY REQUIREMENTS IN THEIR AGREEMENT.
- 6. PROVIDE WRITTEN DAILY UPDATES ON SITE PROGRESS TO THE
- 7. COMPLETE INVENTORY OF CONSTRUCTION MATERIALS AND FOUIPMENT IS REQUIRED PRIOR TO START OF CONSTRUCTION 8. NOTIFY THE OWNER/PROJECT MANAGER IN WRITING NO LESS
 THAN 48 HOURS IN ADVANCE OF CONCRETE POURS. TOWER ERECTIONS, AND EQUIPMENT CABINET PLACEMENTS.

INSURANCE AND BONDS
1. CONTRACTOR, AT THEIR OWN EXPENSE, SHALL CARRY AND MAINTAIN, FOR THE DURATION OF THE PROJECT, ALL INSURANCE, AS REQUIRED AND LISTED. AND SHALL NOT COMMENCE WITH THEIR WORK UNTIL THEY HAVE PRESENTED AN ORIGINAL CERTIFICATE OF INSURANCE STATING ALL COVERAGES TO THE OWNER. REFER TO THE MASTER AGREEMENT FOR REQUIRED INSURANCE LIMITS.

ADJ

AGL

CLG

DWG

ELEC

ELEV EQ

EQUIP EGB

(E) EXT

FF GA

GALV

GRND LG MAX

MECH

MW

MFR

MGB

MIN

MTL

(N) NIC

NTS OC

OPP

(P) PCS PPC

SHT SIM SS STL

TOC

TOM

TYP VIF

UON

WWF

CONC

DIA OR Ø

APPROX

THE OWNER SHALL BE NAMED AS AN ADDITIONAL INSURED ON ALL POLICIES. 3. CONTRACTOR MUST PROVIDE PROOF OF INSURANCE

ADJUSTABLE

APPROXIMATE

CFILING

CONCRETE

DIAMETER

DRAWING

ELECTRICAL

ELEVATION

EACH

EQUAL

EXISTING

FXTFRIOR

GAUGE

GROUND

MAXIMUM

MINIMUM

METAL

NEW

MECHANICAL MICROWAVE DISH

MANUFACTURER

MASTER GROUND BAR

NOT IN CONTRACT

PERSONAL COMMUNICATION SYSTEM

POWER PROTECTION CABINET

UNLESS OTHERWISE NOTED

WELDED WIRE FABRIC

NOT TO SCALE

SQUARE FOOT

STAINLESS STEEL

STEEL TOP OF CONCRETE

TOP OF MASONRY

VERIFY IN FIELD

ON CENTER

OPPOSITE

PROPOSED

SHEET

SIMII AR

TYPICAL

FINISHED FLOOR

GENERAL CONTRACTOR

GALVANIZED

CONTINUOUS

ABOVE GROUND LINE

BASE TRANSMISSION STATION CABINET

EQUIPMENT EQUIPMENT GROUND BAR

DRAWN BY CHECKED BY **ABBREVIATIONS**

DEPT. DATE APP'D

PROJECT NO:

ZONING

SITE AC.

REVISIONS

CT11410A

SM

THIS DOCUMENT IS THE CREATION, DESIGN, PROPERTY AND COPYRIGHTED WORK OF T-MOBILE. ANY DUPLICATION OR USE WITHOUT EXPRESS WRITTEN CONSENT IS STRICTLY PROHIBITED.

PROFESSIONAL SEAL

T - Mobile -

T-MOBILE NORTHEAST, LLC

BLOOMFIELD, CT 0600 OFFICE: (860) 692-7100 FAX:(860) 692-7159

→ \TLANTIS

GROUP

340 Centre Street, Suite 212

Newton Center, MA 02459 Office: 617-965-0789

Fax: 617-213-5056

SUBMITTALS

DESCRIPTION

35 GRIFFIN ROAD SOUT

SITE NAME CT11410A SITE NAME

STAMFORD / DWTN SITE ADDRESS 555 E MAIN STREET

STAMFORD, CT, 06901

SHEET TITLE **GENERAL** AND ELECTRICAL NOTES

SHEET NUMBER


ARCHITECTURAL SYMBOLS STORAGE 38


> - DRAWING DETAIL NUMBER-EXISTING N.I.C.

LSHEET NUMBER OF DETAIL-

DETAIL REFERENCE KEY - REFER TO

RE: 2/A-3





T - Mobile -

T-MOBILE NORTHEAST, LLC

35 GRIFFIN ROAD SOUTH BLOOMFIELD, CT 06002 OFFICE: (860) 692-7100 FAX:(860) 692-7159



1340 Centre Street, Suite 212 Newton Center, MA 02459 Office: 617-965-0789 Fax: 617-213-5056

SUBMITTALS					
DATE		DESCRI	PTION		REVISION
07/15/15	IS	SUED FO	R REVIEW		A
DEDT	DATE	l appro l		EVACIO	MC

DEPT.	DATE	APP'D	REVISIONS
RFE			
RF MAN.			
ZONING			
OPS			
CONSTR.			
SITE AC.			

ı	PROJECT NO:	CT11410A
ı	DRAWN BY:	MB
ı	CHECKED BY:	SM

PROFESSIONAL SEAL

THIS DOCUMENT IS THE CREATION, DESIGN, PROPERTY AND COPYRIGHTED WORK OF T-MOBILE. ANY DUPLICATION OR USE WITHOUT EXPRESS WRITTEN CONSENT IS STRICTLY PROHIBITED.

SITE NAME
CT11410A
SITE NAME

STAMFORD / DWTN

SITE ADDRESS

555 E MAIN STREET


STAMFORD, CT, 06901


SHEET TITLE
ELEVATION
AND

DETAILS

SHEET NUMBER

A-2





TRUNK FIBER NOTES:

- 1. IN GENERAL THIS CABLE WILL HANDLE SIMILARLY TO 1/8" COAXIAL CABLE, AND SIMILAR INSTALLATION TECHNIQUES APPLY. ALL CABLES ARE INDIVIDUALLY SERIALIZED, BE SURE TO WRITE DOWN THE CABLE SERIAL NUMBER FOR FUTURE REFERENCE.
- 2. THE TERMINATED FIBER ENDS (THE BROKEN OUT FIBERS PLUS CONNECTORS) HOWEVER ARE FRAGILE, AND THESE MUST BE PROTECTED DURING THE INSTALLATION PROCESS.
- 3. LEAVE THE PROTECTIVE TUBE AND SOCK AROUND THE FIBER TAILS AND CONNECTORS IN PLACE DURING HOISTING AND SECURING THE CABLE. REMOVE THIS ONLY JUST PRIOR TO MAKING THE FINAL CONNECTIONS TO THE OVP BOX.
- 4. DO NOT BEND THE FIBER ENDS (IN THE ORANGE FURCATION TUBES) TIGHTER THAN ¾" (19MM) BEND RADIUS, ELSE THERE IS A RISK OF BREAKING THE GLASS FIBERS.
- 5. BE SURE THAT THE LACE UP ENDS AND FIBER CONNECTORS ARE NOT DAMAGED BY ATTACHMENT OF A HOISTING GRIP OR DURING THE HOISTING PROCESS. ATTACH A HOISTING GRIP ON THE JACKETED CABLE NO LESS THAN 6 INCHES BELOW THE FIBER BREAKOUT POINT. IF A HOISTING GRIP IS NOT EASILY ATTACHED, USE A SIMPLE LINE ATTACHED BELOW THE FIBER BREAK—OUT POINT (I.E. AT THE CABLE OUTER JACKET). PREVENT THE FIBER TAILS (IN PROTECTIVE TUBE) AT THE CABLE END FROM UNDUE MOVEMENT DURING HOISTING BY SECURING THE PROTECTIVE TUBE (WITH OUTER SOCK) TO THE HOISTING LINE.
- 6. DURING HOISTING ENSURE THAT THERE IS A FREE PATH AND THAT THE CABLE, AND ESPECIALLY THE FIBER ENDS, WILL NOT BE SNAGGED ON TOWER MEMBERS OR OTHER ORSTACLES.
- 7. INSTALLATION TEMPERATURE RANGE IS -22F TO 158F (-30C TO +70C).
- 8. MINIMUM CABLE BEND RADII ARE 22.2" (565MM) LOADED (WITH TENSION ON THE CABLE) AND 11.1" (280MM) UNLOADED.
- 9. MAXIMUM CABLE TENSILE LOAD IS 3560 N (800 LB) SHORT TERM (DURING INSTALLATION) AND 1070 N (240 LB) LONG TERM.
- 10. COMMSCOPE NON LACE UP GRIP RECOMMENDED FOR MONOPOLE INSTALLATIONS.
- 11. MAXIMUM HANGER SPACING 3FT (0.9 M).

HYBRID FIBER/POWER JUMPER NOTES:

- 1. IN GENERAL THIS CABLE WILL HANDLE SIMILARLY TO A %" COAXIAL CABLE.
- 2. THE TERMINATED FIBER ENDS HOWEVER ARE FRAGILE AND MUST BE PROTECTED DURING INSTALLATION. LEAVE THE PACKAGING AROUND THE FIBER ENDS IN PLACE UNTIL READY TO CONNECT THE JUMPER BETWEEN OVP AND RRU, OR BRU.
- 3. DO NOT BEND THE FIBER BREAKOUT CABLE (BETWEEN THE MAIN CABLE AND THE FIBER CONNECTOR) TIGHTER THAN 34" (19MM) RADIUS, ELSE THERE IS A RISK OF BREAKING THE GLASS.
- 4. ATTACH THE MAIN CABLE SECURELY TO THE STRUCTURE OR EQUIPMENT USING HANGERS AND/OR CABLE TIES TO PREVENT STRAIN ON CONNECTIONS FROM MOVEMENT IN WIND OR SNOW/ICE CONDITIONS.
- 5. ENSURE THE LC FIBER CONNECTORS ARE SEATED FIRMLY IN PANEL IN OVP OR IN EQUIPMENT.
- 6. INSTALLATION TEMPERATURE RANGE IS -22F TO 158F (-30C TO 70C).
- 7. MINIMUM CABLE BEND RADII ARE 10.3 INCH (265MM) LOADED (WITH TENSION ON THE CABLE) AND 5.2 INCH (130MM) UNLOADED.
- 8. MAXIMUM CABLE TENSILE LOAD IS 350 LB (1560N) SHORT TERM (DURING INSTALLATION) AND 105 LB (470N) LONG TERM.
- 9. STANDARD LENGTHS AVAILABLE ARE 6 FEET, 15 FEET AND 20 FEET

SCALE: N.T.S

702CU CONFIGURATION COAX/FIBER PLUMBING DIAGRAM



35 GRIFFIN ROAD SOUTH BLOOMFIELD, CT 06002 OFFICE: (860) 692-7100 FAX:(860) 692-7159

TLANTIS G R O U P

1340 Centre Street, Suite 212 Newton Center, MA 02459 Office: 617-965-0789 Fax: 617-213-5056

	SL	JBMITT	ALS	
DATE		DESCRIPT	ION	REVISION
07/15/15	IS	SUED FOR I	REVIEW	A
	†			
	<u> </u>			
	-			
	-			
	<u> </u>			
DEPT.	DATE	APP'D	REVISIO	nns en

DUI 11	-	14101010
RFE		
RF MAN.		
ZONING		
OPS		
CONSTR.		
SITE AC.		
		 OT44440A

PROJECT NO:	CT11410A
DRAWN BY:	MB
CHECKED BY:	SM

PROFESSIONAL SEAL

THIS DOCUMENT IS THE CREATION, DESIGN, PROPERTY AND COPYRIGHTED WORK OF T-MOBILE. ANY DUPLICATION OR USE WITHOUT EXPRESS WRITTEN CONSENT IS STRICTLY PROHIBITED.

SITE NAME CT11410A

STAMFORD / DWTN

SITE NAME

SITE ADDRESS


555 E MAIN STREET

STAMFORD, CT, 06901

SHEET TITLE
GROUNDING DIAGRAM
AND
POWER ONE
LINE DIAGRAM

SHEET NUMBER


E-1



BURNDY GROUNDING DETAILS


SCALE: N.T.S






BURNDY GROUNDING PRODUCTS 2

SCALE: N.T.S



CADWELD GROUNDING CONNECTION PRODUCTS


SCALE: N.T.S



GROUNDING TERMINATION MATRIX 7


SCALE: N.T.S





NOTES:

1. OXIDE INHIBITING COMPOUND TO BE USED AT ALL LOCATIONS.




NOTES

- 1. ALL HARDWARE STAINLESS STEEL COAT ALL SURFACES WITH KOPR-SHIELD BEFORE MATING.
- 2. FOR GROUND BOND TO STEEL ONLY: INSERT A TOOTH WASHER BETWEEN LUG AND STEEL, COAT ALL SURFACES WITH KOPR-SHIELD.
- 3. ALL HOLES ARE COUNTERSUNK 1/6".


TYPICAL GROUND BAR CONNECTIONS DETAIL

CALE: N.T.S



GROUND BAR DETAIL (5)

SCALE: N.T.S



LUG NOTE

- 1. ALL HARDWARE IS 18-8 STAINLESS STEEL, INCLUDING LOCK WASHERS.
- 2. ALL HARDWARE SHALL BE S.S. ¾"ø OR LARGER.
- 3. FOR GROUND BOND TO STEEL ONLY: INSERT A DRAGON TOOTH WASHER BETWEEN LUG AND STEEL. COAT ALL SURFACES WITH ANTI-OXIDIZATION COMPOUND PRIOR TO MATING.

GROUND BAR DETAIL

SCALE: N.T.S

T - Mobile -

T-MOBILE NORTHEAST, LLC

35 GRIFFIN ROAD SOUTH BLOOMFIELD, CT 06002 OFFICE: (860) 692-7100 FAX:(860) 692-7159



1340 Centre Street, Suite 212 Newton Center, MA 02459 Office: 617—965—0789 Fax: 617—213—5056

-		-		
SUBMITTALS				
DATE	DESCRIPTION	REVISION		
07/15/15	ISSUED FOR REVIEW	Α		
		1		
		+		
		+		
		+		
		+		

DEPT.	DATE	APP'D	REVISIONS	
RFE				
RF MAN.				
ZONING				
OPS				
CONSTR.				
SITE AC.				

PROJECT NO:	CT11410A
DRAWN BY:	MB
CHECKED BY:	SM
_	

PROFESSIONAL SEAL

THIS DOCUMENT IS THE CREATION, DESIGN, PROPERTY AND COPYRIGHTED WORK OF T-MOBILE. ANY DUPLICATION OR USE WITHOUT EXPRESS WRITTEN CONSENT IS STRICTLY PROHIBITED.

SITE NAME
CT11410A
SITE NAME

STAMFORD / DWTN

SITE ADDRESS

555 E MAIN STREET

STAMFORD, CT, 06901

017 11111 0112, 011, 000

SHEET TITLE

GROUNDING DETAILS

SHEET NUMBER

E**-**2

Exhibit B

Structural Analysis Report



AT&T – Stamford Central SBC CO #CT2118 / FA #10034983 Owner: Frontier Communications - Stamford #1 Co Site Stamford, Connecticut

June 24, 2015

MEI PROJECT ID: CT02768S-15V2



17950 Preston Road, Suite 720 ■ Dallas, Texas 75252 ■ Tel. 972 -783-2578 Fax 972-783-2583 *www.maloufengineering.com*





June 24, 2015

Mr. Miguel Nobre Vertical Resources Auburn, MA 01501

STRUCTURAL ANALYSIS

Structure/Make/Model:		elf-Supporting Tower 06.5ft Rooftop)	Not Known / Not Known		
Client/Site Name/#:	Vertica	I Resources / AT&T	Stamford Central SBC CO #CT217 FA #10034983		
Owner/Site Name/#:	Frontier Communications		Stamford #1 Co		
MEI Project ID:	CT02768	S-15V2			
Location:	555 Maii Stamfor	n St d, CT 06901			
	LAT	41-03-12.47 N	LON 73-32-8.4 W		

EXECUTIVE SUMMARY:

Malouf Engineering Int'l (MEI), as requested, has performed a structural analysis and modification design of the above mentioned structure to assess the impact of the changed condition as noted in Table 1.

Based on the stress analysis performed, the existing structure is in conformance with the Int'l Building Code (IBC) / ANSI/TIA 222-F Standard for the loading considered under the criteria listed and referenced in the report sections after proper installation of the recommended structural strengthening modifications outlined – tower rated at 93.7% - Legs.

The addition of the proposed changed condition as noted in Table 1 is structurally acceptable after proper installation of the proposed strengthening modifications. Please refer to modification drawings for details.

MEI appreciates the opportunity of providing our continuing professional services to you. If you have any questions or need further assistance on this or other projects please contact us.

Respectfully submitted,

MALOUF ENGINEERING INT'L, INC.

Analysis performed by:

Reviewed & Approved by:

E. Mark Malouf, PE Connecticut #17715

972-783-2578 ext. 106

mmalouf@maloufengineering.com

Luan Nguyen, PE Sr. Project Engineer

TABLE OF CONTENTS

1.	INTRODUCTION & SCOPE	4
2.	SOURCE OF DATA	4
	Background Information:	4
<i>3.</i>	ANALYSIS CRITERIA	5
	Appurtenances Configuration	5
4.	ANALYSIS PROCEDURE	7
	Analysis Program	
	Assumptions	7
<i>5.</i>	ANALYSIS RESULTS	8
6.	FINDINGS & RECOMMENDATIONS	9
7.	REPORT DISCLAIMER	10
APP	PENDIX 1 - ANALYSIS PRINTOUT & GRAPHICS	11
APP	PENDIX 2 – SOURCE / CHANGED CONDITION	12

Separate Attachment:

Modification Design Drawings



1. INTRODUCTION & SCOPE

A structural analysis and modification design were performed by Malouf Engineering Int'l (MEI), as requested and authorized by Mr. Miguel Nobre, Vertical Resources, on behalf of AT&T, to determine the acceptance of the proposed changed conditions in conformance with the IBC / ANSI/TIA-222-F Standard, "Structural Standards for Steel Antenna Towers and Antenna Supporting Structures".

The scope of this independent analysis is to determine the overall stability and the adequacy of structural members, foundations, and member connections, as available and stated. This analysis considers the structure to have been properly installed and maintained with no structural defects. Installation procedures and related loading are not within the scope of this analysis and should be performed and evaluated by a competent person of the erection contractor.

The different report sections detail the applicable information used in this evaluation, relating to the tower data, the appurtenances configuration and the wind and ice loading considered.

2. SOURCE OF DATA

The following information has been used in this evaluation as source data that accurately represent the existing structure and the related appurtenances:

	Source	Information	Reference	
STRUCTURE				
Tower	MEI Records	Previous Structural Analysis	ID CT02768S-15V0 Dated 04/27/2015	
Base Support	Tower is on a building roo	ftop - building members to	be reviewed by others.	
Material Grade	Not available from supplied documents-Assumed based on typical towers of			
	this type-refer to Appendi	X		
CURRENT APPURTENANCES				
	MEI Records	Previous Structural	ID CT02768S-15V0	
		Analysis	Dated 04/27/2015	
CHANGED CONDITION				
	Vertical Resources /	E-mail Instructions	Dated 06/10/2015	
	Mr. Miguel Nobre	AT&T Collo Application	Dated 03/31/2015	

Background Information:

Based on available information, the following is known regarding this structure:

DESIGNER / FABRICATOR	Not Known / Not Known	
ORIGINAL DESIGN CRITERIA	TIA/EIA 222-Unknown	
PRIOR STRUCTURAL MODIFICATIONS	Mods as per MEI CT02768S-11V1	



3. ANALYSIS CRITERIA

The structural analysis performed used the following criteria:

CODE / STANDARD	2005 CT State B	uilding Code / 2003 Int'l Building Code / ANSI/TIA-222-F-96 Standard		
LOADING CASES	Full Wind: 85 Mph (fastest-mile) – with No Radial Ice			
	Iced Case:	73.61 Mph (fastest-mile) + 0.5" Radial Ice		
	Service:	50 Mph		

Appurtenances Configuration

The following appurtenances configuration is denoted by the *summation of Tables 1 & 2*:

Table 1: Proposed Changed Condition Appurtenances

Elev (ft)	Tenant	Ants Qty	Appurtenance Model / Description	Mount Description	Lines Qty	Line size & Location
235	AT&T	6	OPA-65R-LCUU-H4 Panel Antennas	[Existing Mounts]	2	0.75" DC Power
		3	RRUS-12 w/ A2 Backpacks			Trunk Cables
		3	RRUS-32 Boxes		1	0.625" Fiber
		1	Raycap DC6-48-60-18-8F DC Surge Box			Trunk Cable-(FZ)
203 T-Ma	T-Mobile	3	LNX-6515DS-VTM Panel Antennas	[Existing Mounts]		No New Lines
		3	RRUS-11 B12 Boxes			
			To Be Removed (Se	ee Below)		
235	AT&T	3	P65-15-XLH-RR Panel Antennas			
		3	AM-X-CD-14-65-00T-RET Panel Ants.			
		6	LGP21401 TMAs			
		3	RRUS-11 Boxes			
203	T-Mobile	3	APX16DWV-16DWVS Panel Antennas			
		3	10"T x 9.5"W x 3.5"D TMAs			

Table 2: Current and Reserved/Future Appurtenances

Elev (ft)	Tenant	Ants Qty	Appurtenance Model / Description	Mount Description	Lines Qty	Line size & Location
245.17		2	Top Small Beacons	13ft T-Beam Mount	1	1-1/4" R.C.
244.5		1	Top Lightning Rod			
235	AT&T	3	P65-15-XLH-RR Panel Antennas	Top Square Platform Mount	12	1-5/8"
		6	LGP21401 TMAs		2	0.75" DCPower
		3	RRUS-11 Boxes			Trunk Cables
233	AT&T	1	Raycap DC6-48-60-18-8F DC Surge Box		1	0.625" Fiber Trunk Cable RET Cable-(FZ)
231.5				Unused I-Beam Mount		1121 00010 (12)
229	AT&T	1	1.5ft (2-Elem) Yagi Antenna	[Onto Platform]	1	1/2"-(FZ)
223.5		1	10ft Dia. HP Dish (Az. 210°±)	Dish Pipe Mount-DA Face	2	EW90-(FZ)
221.5	[Unused]				2	3/8"-(FZ)
221		1	1ft Dia. HP Dish (Windstar 43029) (Az. 210°±)	Dish Pipe Mount-BC Face	1	3/8"-(FZ)
216.5				(2) 4'Lx6'W Rest Platforms		
209.5	T-Mobile	6	AIR21 B2A B4P Panel Antennas	(3) Sector Frame Mounts	12	1-5/8"
		6	KRY 112 71/2 TMAs		1	Huber-Suhner 1.25" TC-OF Cable-(FZ)
203	T-Mobile			(3) Sector Frame Mounts		
201.5	T-Mobile [Unused]				18	1-5/8"-(FZ)
132	AT&T	1	4ft (7-Elem) Yagi Antenna	2ft Sidearm Mount	1	1/2"-(FZ)



Notes:

- 1. Tower Base elevation is at 106.5ft Above Ground Level All above elevations are measured from AGL.
- 2. Please note appurtenances not listed above are to be removed/not present as per data supplied.
- 3. (I) = Internal; (E) = External; (FZ) = Within Face Zone; (OFZ) = Outside Face Zone as per TIA-222.
- 4. The above appurtenances represent MEI's understanding of the appurtenances configuration. If different than above, the analysis is invalid. Please contact MEI if any discrepancies are found.



4. ANALYSIS PROCEDURE

The subject structure is analyzed for feasibility of the installation of the proposed changed condition previously noted. The data records furnished were reviewed and a computer stress analysis was performed in accordance with the TIA-222 Standard provisions and with the agreed scope of work terms and the results of this analysis are reported.

Analysis Program

The computer program used to model the structure is a rigorous Finite Element Analysis program, tnxTower (ver. 6.1.3.1), a commercially available program by Tower Numerics Inc. The latticed structures members are modeled using beam/truss and cable members and the pole members using tubular beam elements. The structural parameters and geometry of the members are included in the model. The dead and temperature loads and the wind loads are internally calculated by the program for the different wind directions and then applied as external loads on the structure.

Assumptions

This engineering study is based on the theoretical capacity of the members and is not a condition assessment of the structure. This analysis is based on information supplied, and therefore, its results are based on and as accurate as that supplied data. MEI has made no independent determination, nor is it required to, of its accuracy. The following assumptions were made for this structural stress analysis:

- This existing tower is assumed, for the purpose of this analysis, to have been properly maintained and to be in good condition with no structural defects and with no deterioration to its member capacities ('asnew' condition).
- The tower member sizes and configuration are considered accurate as supplied. The material grade is as per data supplied and/or as assumed and as stated.
- The appurtenances configuration is as supplied and/or as stated in the report. It is assumed to be complete and accurate. All antennas, mounts, coax and waveguides are assumed to be properly installed and supported as per manufacturer requirements.
- Some assumptions are made regarding antennas and mounts sizes and their projected areas based on best interpretation of data supplied and of best knowledge of antenna type & industry practice.
- Mounts/Platforms are considered adequate to support the loading. No actual analysis of the platform/mount itself is performed, with the analysis being limited to analyzing the structure.
- The soil parameters are as per data supplied or as assumed and stated in the calculations. Refer to the Appendix. If no data is available, the foundation system is assumed to support the structure with its new reactions.
- All welds and connections are assumed to develop at least the member capacity, unless determined otherwise and explicitly stated in this report.
- All prior structural modifications, if any, are assumed to be as per data supplied/available, and to have been properly installed and to be fully effective.

If any of the above assumptions are not valid or have been made in error, this analysis results may be invalided, MEI should be contacted to review any contradictory information to determine its effect.



5. ANALYSIS RESULTS

The structure will require structural strengthening as follows: (Refer to the attached drawings for details.)

STRU	ICTURAL STRENGTHENING REQUIRED
1	Add new Internal Hip Bracing angle members bolted onto existing members from Elevations:
	6.25' - 12.5' and 30' - 35' (2 bays total). Lengths to be field determined.
2	Add new Sub-bracing angle members bolted onto existing members from Elevations: 0' -
	6.25' and 25' - 30' (2 bays total). Lengths to be field determined.
3	Perform Maintenance work as required & applicable to bring the structure into good
	operational condition.
4	Field determination/verification and/or field adaptation is recommended.

Prior to implementation of the changed conditions and modifications, the data designated on the design documents requiring field verification shall be validated. Rigging and temporary supports required for the erection/modification shall be determined, documented, furnished and installed by the erector/contractor accounting for the loads imposed on the structure due to the proposed construction method.

Table 3: Stress Analysis Results – <u>AFTER PROPER INSTALLATION OF MODS</u>

Component Type	Maximum Stress Ratio	Controlling Elev. (ft) / Component	Pass/Fail	Comment
LEGS	93.7%	131.5 - 119	Pass	
DIAGONALS	84.8%	161.5 - 151.5	Pass	
HORIZONTALS / GIRTS	52.2%	141.5 - 131.5	Pass	
SECONDARY HORIZONTALS	79.3%	151.5 - 141.5	Pass	
Bracings	67.7%	131.5 - 119	Pass	
BASE SUPPORT	N/A	-	-	Tower is on top of building. Scope is limited to tower. Building members to be reviewed by others.

Table 4: Serviceability Requirements

	Maximum Value	TIA Requirement (10dB)	Pass/Fail	Comment
Twist/Sway	0.1764 Deg.	4.425 Deg.	Pass	1ft HP Dish (Windstar 43029) Elev. 221.00ft
	0.1783 Deg.	0.2957 Deg.	Pass	10 FT HP DISH Elev. 223.50ft

Notes:

- 1. The Maximum Stress Ratio is the percentage that the maximum load in the member is relative to the allowable load as determined by Code requirements.
- 2. Refer to the Appendix 1 for more details on the member loads.
- 3. A maximum stress ratio between 100% and 105% may be considered as *Acceptable* according to industry standard practice.



6. FINDINGS & RECOMMENDATIONS

- Based on the stress analysis results, the subject structure is rated at 93.7% of its support capacity (controlling component: Leg) with the proposed changed condition considered after strengthening. Please refer to Table 3 and to Appendix 1 for more details of the analysis results.
- Based on the stress analysis performed, the existing structure is in conformance with the IBC / ANSI/TIA 222-F Standard for the loading considered under the criteria listed and referenced in the report sections after proper installation of the recommended structural strengthening modifications outlined.
- Please note that the tower is mounted on top of a building rooftop. Building rooftop is to be evaluated by others to determine its adequacy for the new base loads (not within scope). Refer to Appendix for tower base reactions.
- The addition of the proposed changed condition as noted in Table 1 is structurally acceptable after proper installation of the proposed strengthening modifications.
 Please refer to modification drawings for details.
- This structure would be near its maximum support capacity for the appurtenances and loading criteria considered, after its modification. Therefore, no changes to the configuration considered should be made without performing a new proper evaluation.

Rigging and temporary supports required for the erection/modification shall be determined, documented, furnished and installed by the erector/contractor accounting for the loads imposed on the structure due to the proposed construction method.



7. REPORT DISCLAIMER

The engineering services rendered by Malouf Engineering International, Inc. ('MEI') in connection with this Structural Analysis are limited to a computer analysis of the tower structure, size and capacity of its members. MEI does not analyze the fabrication, including welding and connection capacities, except as included in this Report.

The analysis performed and the conclusions contained herein are based on the assumption that the tower has been properly installed and maintained, including, but not limited to the following:

- 1. Proper alignment and plumbness.
- 2. Correct guy tensions, as applicable.
- 3. Correct bolt tightness or slip jacking of sleeved connections.
- 4. No significant deterioration or damage to any structural component.

Furthermore, the information and conclusions contained in this Report were determined by application of the current "state-of-the-art" engineering and analysis procedures and formulae. Malouf Engineering International, Inc. assumes no obligation to revise any of the information or conclusions contained in this Report in the event that such engineering and analysis procedures and formulae are hereafter modified or revised. In addition, under no circumstances will Malouf Engineering International, Inc. have any obligation or responsibility whatsoever for or on account of consequential or incidental damages sustained by any person, firm or organization as a result of any information or conclusions contained in the Report, and the maximum liability of Malouf Engineering International, Inc., if any, pursuant to this Report shall be limited to the total funds actually received by Malouf Engineering International, Inc., for preparation of this Report.

Customer has requested Malouf Engineering International, Inc. to prepare and submit to Customer an engineering analysis with respect to the Subject Tower and has further requested Malouf Engineering International, Inc. to make appropriate recommendations regarding suggested structural modifications and changes to the Subject Tower. In making such request of Malouf Engineering International, Inc., Customer has informed Malouf Engineering International, Inc. that Customer will make a determination as to whether or not to implement any of the changes or modifications which may be suggested by Malouf Engineering International, Inc. and that Customer will have any such changes or modifications made by riggers, erectors and other subcontractors of Customer's choice. Malouf Engineering International, Inc. shall have the right to rely upon the accuracy of the information supplied by the customer and shall not be held responsible for the Customer's misrepresentation or omission of relevant fact whether intentional or otherwise.

Customer hereby agrees and acknowledges that MALOUF ENGINEERING INTERNATIONAL, INC. shall have no liability whatsoever to Customer or to others for any work or services performed by any persons other than MALOUF ENGINEERING INTERNATIONAL, INC. in connection with the implementation of services including but not limited to any services rendered for Customer or for others by riggers, erectors or other subcontractors. Customer acknowledges and agrees that any riggers, erectors or subcontractors retained or employed by Customer shall be solely responsible to Customer and to others for the quality of work performed by them and that MALOUF ENGINEERING INTERNATIONAL, INC. shall have no liability or responsibility whatsoever as a result of any negligence or breach of contract by any such rigger, erector or subcontractor and that Customer and rigger, erector, or subcontractor will provide MALOUF ENGINEERING INTERNATIONAL, INC. with a Certificate of Insurance naming MALOUF ENGINEERING INTERNATIONAL, INC. as additional insured.



APPENDIX 1 - ANALYSIS PRINTOUT & GRAPHICS

AFTER NOTED MODIFICATIONS





231.5 ft

229.0 ft

224.8 ft

220.7 ft

216.5 ft

211.5 ft

206.5 ft

201.5 ft

196.5 ft

191.5 ft

181.5 ft

171.5 ft

161.5 ft

151.5 ft

141.5 ft

131.5 ft

119.0 ft

106.5 ft

1 @ 2.5

3 @ 4.1667

5 @ 5

6.69223

7.05492

7.41761

L2 1/2x2 1/2x3/16

10.3191

2 @ 2

1 @ 12.5

L3x3x3/16

L2 1/2x2x3/16 L2 1/2x2x3/16

Leg Grade
Diagonals
Diagonal Grade
Top Gins
Horizontals
Sec. Horizontals
Red. Horizontals
Red. Chigonols
Red. Sub-Horizs
Red. Sub-Horizs
Red. Sub-Horizs
Fed. Sub-Diags
Inner Bracing
Face Width (ft)
Panels @ (ft)

12.6766

1 @ 12.4999

5 @ 10

A. A.

L2 1/2x2x1/4

L2 1/2x2x3/16

L2 1/2x2 1/2x1/4

L2 1/2x2x1/4

É

2L2 1/2x2 1/2x1/4x3/8 N.A.

2L2 1/2x2 1/2x1/4x3/8

N.A. L2 1/2x2x3/16 L2 1/2x2x3/16

A36

2L2 1/2x2x1/4x3/8

A.

Ė

L2 1/2x2x1/4

L6x6x5/8

T14

T15

T16

L6x6x3/4

DESIGNED APPURTENANCE LOADING


TYPE	ELEVATION	TYPE	ELEVATION
2) TOP SMALL BEACONS (E)	245.17	PIPE DISH MOUNT (E)	223.5
FOP LIGHTNING ROD (E)	244.5	10 FT HP DISH (E)	223.5
P65-15-XLH-RR w/ Pipe Mount (ATI / E)	235	PIPE DISH MOUNT (E)	221
2) LGP21401 TMA'S (ATI / E)	235	1 FT HP DISH (WINDSTAR 43029) (E)	221
2) OPA-65R-LCUU-H4 w/ Pipe Mounts (ATI / P)	235	4'Lx6'W REST PLATFORM (E)	216.5
P65-15-XLH-RR w/ Pipe Mount (ATI / E)	235	4'Lx6'W REST PLATFORM (E)	216.5
2) OPA-65R-LCUU-H4 w/ Pipe Mounts (ATI / P)	235	(2) AIR21 B2A B4P w/ pipe Mount (T-MOBILE / E)	209.5
2) LGP21401 TMA'S (ATI / E)	235	(2) KRY 112 71/2 (T-MOBILE / E)	209.5
RRUS-11 (ATI/E)	235	(2) KRY 112 71/2 (T-MOBILE / E)	209.5
RRUS-11 (AT <u>I</u> / E)	235	(2) KRY 112 71/2 (T-MOBILE / E)	209.5
P65-15-XLH-RR w/ Pipe Mount (AT <u>T</u> / E)	235	SECTOR FRAME MOUNT (T-MOBILE / E)	209.5
OPA-65R-LCUU-H4 w/ Pipe Mounts (ATI / P)	235	SECTOR FRAME MOUNT (T-MOBILE / E)	209.5
OPA-65R-LCUU-H4 w/ Pipe Mounts (ATI / P)	235	SECTOR FRAME MOUNT (T-MOBILE / E)	209.5
_GP21401 TMA'S (ATI / E)	235	(2) AIR21 B2A B4P w/ pipe Mount (T-MOBILE / E)	209.5
_GP21401 TMA'S (ATI / E)	235	(2) AIR21 B2A B4P w/ pipe Mount (T-MOBILE / E)	209.5
RRUS-11 (AT <u>I</u> / E)	235	10"T x 9.5"W x 3.5"D TMA's (T-MOBILE / E)	203
RRUS-12 w/ A2 Backpack (ATI / P)	235	LNX-6515DS-VTM w/ Pipe Mnt. (T-MOBILE / P)	203
RRUS-12 w/ A2 Backpack (ATI / P)	235	LNX-6515DS-VTM w/ Pipe Mnt. (T-MOBILE / P)	203
RRUS-12 w/ A2 Backpack (ATI / P)	235	LNX-6515DS-VTM w/ Pipe Mnt. (T-MOBILE / P)	203
RRUS-32 (ATI / P)	235	RRUS-11 B12 (T-MOBILE / P)	203
RRUS-32 (ATI / P)	235	RRUS-11 B12 (T-MOBILE / P)	203
RRUS-32 (AT <u>I</u> / P)	235	RRUS-11 B12 (T-MOBILE / P)	203
RAYCAP DC6-48-60-18-8F DC SURGE BOX (ATI	233	SECTOR FRAME MOUNT (T-MOBILE / E)	203
(E)		SECTOR FRAME MOUNT (T-MOBILE / E)	203
RAYCAP DC6-48-60-18-8F DC SURGE BOX (ATI P)	233	SECTOR FRAME MOUNT (T-MOBILE / E)	203
·		10"T x 9.5"W x 3.5"D TMA's (T-MOBILE / E)	203
13' T BEAM MOUNT (E)	231.5	10"T x 9.5"W x 3.5"D TMA's (T-MOBILE / E)	203
JNUSED I-BEAM MOUNT (ATI / E)	231.5	4'x7-ELEMENT YAGI (ATT / E)	132
FOP SQUARE PLATFORM MOUNT (ATI / E)	231.5	2FT SIDEARM MOUNT (ATI / E)	132

SYMBOL LIST MARK L2 1/2x2 1/2x1/4

SIZE

MATERIAL STRENGTH GRADE Fy Fu

TOWER DESIGN NOTES



loufengineering.com


Malouf Engineering Int'l, Inc. 17950 Preston Road, Suite #720

Dallas, TX 75252 Phone: (972) 783-2578 FAX: (972) 783-2583

125 FT SST, STAMFORD CENTRAL SITE #CT2118 Project: CT02768S-15V2

Client: VERTICAL RESOURCES GROUP / AT&T Drawn by: LNguyen App'd:


Date: 06/25/15 Scale: NTS Date: 06/25/15 Dwg No. E-1





125 FT SST, STAMFORD CENTRAL SITE #CT2118				
Project: CT02768S-15V2				
Client: VERTICAL RESOURCES GROUP / AT&T	Drawn by: LNguyen	App'd:		
Code: TIA/EIA-222-F	Date: 06/25/15	Scale: N	TS	
Path: D:MEIProjects\15 DATA\SS\CT02768S-15V2\CT02768S-15V2-M3-UPDATED.eri	Dwg No. E	E-5		

TIA/EIA-222-F - 85 mph/74 mph 0.5000 in Ice Leg Compression (K)





125 FT SST, STAMFORD CENTRAL SITE #CT2118				
oject: CT02768S-15V2				
ent: VERTICAL RESOURCES GROUP / AT&T	Drawn by: LNguyen	App'd:		
ode: TIA/EIA-222-F	Date: 06/25/15	Scale: NTS		
hth: D:WEIProjects\15 DATA\SS\CT02768S-15V2\CT02768S-15V2-M3-UPDATED.eri		Dwg No. E-3		

Malouf Engineering Int'l, Inc.

17950 Preston Road, Suite #720 Dallas, TX 75252 Phone: (972) 783-2578 FAX: (972) 783-2583

T	Job		Page
	125 FT SST, STAMFORD	CENTRAL SITE #CT2118	1 of 6
ſ	Project		Date
	CT02768	8S-15V2	09:01:11 06/25/15
	Client VERTICAL RESOUR	CES GROUP / AT&T	Designed by LNguyen

Tower Input Data

The main tower is a 4x free standing tower with an overall height of 231.50 ft above the ground line.

The base of the tower is set at an elevation of 106.50 ft above the ground line.

The face width of the tower is 5.60 ft at the top and 13.58 ft at the base.

This tower is designed using the TIA/EIA-222-F standard.

The following design criteria apply:

Tower is located in Fairfield County, Connecticut.

Basic wind speed of 85 mph.

Nominal ice thickness of 0.5000 in.

Ice density of 56 pcf.

A wind speed of 74 mph is used in combination with ice.

Temperature drop of 50 °F.

Deflections calculated using a wind speed of 50 mph.

A non-linear (P-delta) analysis was used.

Pressures are calculated at each section.

Stress ratio used in tower member design is 1.333.

Local bending stresses due to climbing loads, feed line supports, and appurtenance mounts are not considered.

Feed Line/Linear Appurtenances - Entered As Round Or Flat

Description	Placement	Total Number	Description Placement	Total Number
	ft		ft	
Safety Line 3/8	231.50 - 106.50	1	EW90 223.50 - 106.50	2
(E)			(E)	
Climbing Ladder	231.50 - 106.50	1	3/8 221.50 - 106.50	2
(E)			(E (UNUSED))	
W/G LADDER "A"	212.50 - 106.50	1	3/8 221.00 - 106.50	1
(E)			(E)	
W/G LADDER "B"	206.50 - 106.50	1	1 5/8 209.50 - 106.50	12
(E)			(T-MOBILE / E)	
W/G LADDER "C"	200.50 - 106.50	1	Huber-Suhner 1.25" 209.50 - 106.50	1
(E)			TC-OF Cable	
1 1/4" Rigid Conduit	231.50 - 106.50	1	(T-MOBILE / E)	
(E)			1 5/8 201.50 - 106.50	6
0.625" Fiber Trunk Cable	231.50 - 106.50	2	(T-MOBILE / E	
(AT&T/E+P)			(UNUSED))	
0.75" DC Power Trunk	231.50 - 106.50	4	1 5/8 201.50 - 106.50	12
Cable			(T-MOBILE / E	
(AT&T/E+P)			(UNUSED))	
1 5/8	231.50 - 106.50	12	1/2 132.00 - 106.50	1
(AT&T/E)			(E)	
0.30	231.50 - 106.50	1		
(AT&T/E)				
1/2	229.00 - 106.50	1		

Feed Line/Linear Appurtenances - Entered As Area

Description	Placement	Total Number
	ft	
MISCELLANEOUS	231.50 - 106.50	2
(E)		
MISCELLANEOUS	231.50 - 106.50	1

(E)

Description	Placement	Total Number
	ft	
WEIGHT		
(E)		

Malouf Engineering Int'l, Inc. 17950 Preston Road, Suite #720

7950 Preston Road, Suite #720 Dallas, TX 75252 Phone: (972) 783-2578 FAX: (972) 783-2583

Job		Page
	125 FT SST, STAMFORD CENTRAL SITE #CT2118	2 of 6
Proje	ect	Date
	CT02768S-15V2	09:01:11 06/25/15
Clien	vertical resources group / AT&T	Designed by LNguyen

Discrete Tower Loads

Description	Placement	Weight	Description	Placement	Weight
Description	1 iacemeni	weight	Description	1 шсетені	weigni
	ft	K		ft	K
(2) TOP SMALL BEACONS	245.17	0.06	(AT&T / P)	Ji	0.10
(E)	243.17	0.00	RRUS-32	235.00	0.10
TOP LIGHTNING ROD	244.50	0.05	(AT&T / P)	233.00	0.10
(E)	20	0.07	UNUSED I-BEAM MOUNT	231.50	0.10
13' T BEAM MOUNT	231.50	0.10	(AT&T / E)		0.15
(E)		0.15	1.5'x2-ELEMENT YAGI	229.00	0.07
P65-15-XLH-RR w/ Pipe	235.00	0.07	AND MOUNT		0.13
Mount		0.12	(AT&T / E)		
(AT&T / E)			TOP SQUARE PLATFORM	231.50	5.50
(2) LGP21401 TMA'S	235.00	0.02	MOUNT		7.50
(AT&T/E)		0.03	(AT&T/E)		
(2) OPA-65R-LCUU-H4 w/	235.00	0.08	PIPE DISH MOUNT	223.50	0.15
Pipe Mounts		0.13	(E)		0.23
(AT&T / P)	227.00	0.0=	PIPE DISH MOUNT	221.00	0.07
P65-15-XLH-RR w/ Pipe	235.00	0.07	(E)	24 - 50	0.10
Mount		0.12	4'Lx6'W REST PLATFORM	216.50	0.75
(AT&T / E)	225.00	0.08	(E)	216.50	1.25
(2) OPA-65R-LCUU-H4 w/	235.00	0.08	4'Lx6'W REST PLATFORM	216.50	0.75
Pipe Mounts (AT&T / P)		0.13	(E) (2) AIR21 B2A B4P w/ pipe	209.50	1.25 0.13
(2) LGP21401 TMA'S	235.00	0.02	Mount	209.30	0.13
(AT&T / E)	233.00	0.02	(T-MOBILE / E)		0.16
RRUS-11	235.00	0.05	(2) AIR21 B2A B4P w/ pipe	209.50	0.13
(AT&T / E)	233.00	0.07	Mount	207.30	0.18
RRUS-11	235.00	0.05	(T-MOBILE / E)		
(AT&T / E)		0.07	(2) AIR21 B2A B4P w/ pipe	209.50	0.13
RAYCAP DC6-48-60-18-8F	233.00	0.03	Mount		0.18
DC SURGE BOX		0.06	(T-MOBILE / E)		
(AT&T / E)			(2) KRY 112 71/2	209.50	0.01
P65-15-XLH-RR w/ Pipe	235.00	0.07	(T-MOBILE / E)		0.02
Mount		0.12	(2) KRY 112 71/2	209.50	0.01
(AT&T/E)			(T-MOBILE / E)		0.02
OPA-65R-LCUU-H4 w/ Pipe	235.00	0.08	(2) KRY 112 71/2	209.50	0.01
Mounts		0.13	(T-MOBILE / E)		0.02
(AT&T / P)	227.00	0.00	SECTOR FRAME MOUNT	209.50	0.40
OPA-65R-LCUU-H4 w/ Pipe	235.00	0.08	(T-MOBILE / E)	200.50	0.60
Mounts		0.13	SECTOR FRAME MOUNT	209.50	0.40
(AT&T / P)	235.00	0.02	(T-MOBILE / E)	200.50	0.60
LGP21401 TMA'S (AT&T / E)	255.00	0.02	SECTOR FRAME MOUNT (T-MOBILE / E)	209.50	0.40 0.60
LGP21401 TMA'S	235.00	0.03	10"T x 9.5"W x 3.5"D TMA's	203.00	0.00
(AT&T / E)	233.00	0.02	(T-MOBILE / E)	203.00	0.02
RRUS-11	235.00	0.05	10"T x 9.5"W x 3.5"D TMA's	203.00	0.03
(AT&T / E)	233.00	0.07	(T-MOBILE / E)	203.00	0.03
RRUS-12 w/ A2 Backpack	235.00	0.08	10"T x 9.5"W x 3.5"D TMA's	203.00	0.02
(AT&T / P)	200.00	0.11	(T-MOBILE / E)	200.00	0.03
RRUS-12 w/ A2 Backpack	235.00	0.08	LNX-6515DS-VTM w/ Pipe	203.00	0.09
(AT&T / P)		0.11	Mnt.		0.18
RRUS-12 w/ A2 Backpack	235.00	0.08	(T-MOBILE / P)		
(AT&T / P)		0.11	LNX-6515DS-VTM w/ Pipe	203.00	0.09
RAYCAP DC6-48-60-18-8F	233.00	0.03	Mnt.		0.18
DC SURGE BOX		0.06	(T-MOBILE / P)		
(AT&T / P)			LNX-6515DS-VTM w/ Pipe	203.00	0.09
RRUS-32	235.00	0.08	Mnt.		0.18
(AT&T/P)		0.10	(T-MOBILE / P)		
RRUS-32	235.00	0.08	RRUS-11 B12	203.00	0.05

Malouf Engineering Int'l, Inc. 17950 Preston Road, Suite #720

7950 Preston Road, Suite #720 Dallas, TX 75252 Phone: (972) 783-2578 FAX: (972) 783-2583

Job		Page
1	25 FT SST, STAMFORD CENTRAL SITE #CT2118	3 of 6
Projec	t	Date
	CT02768S-15V2	09:01:11 06/25/15
Client	VERTICAL RESOLIROFS ORGUR / ATST	Designed by
	VERTICAL RESOURCES GROUP / AT&T	LNguyen

Description	Placement	Weight
	ft	K
(T-MOBILE / P)		0.07
RRUS-11 B12	203.00	0.05
(T-MOBILE / P)		0.07
RRUS-11 B12	203.00	0.05
(T-MOBILE / P)		0.07
SECTOR FRAME MOUNT	203.00	0.40
(T-MOBILE / E)		0.60
SECTOR FRAME MOUNT	203.00	0.40
(T-MOBILE / E)		0.60
SECTOR FRAME MOUNT	203.00	0.40

Description	Placement	Weight
	ft	K
(T-MOBILE / E)		0.60
4'x7-ELEMENT YAGI	132.00	0.03
(AT&T / E)		0.04
2FT SIDEARM MOUNT	132.00	0.10
(AT&T / E)		0.15

Dishes

Description	Dish Type	Elevation	Outside Diameter	Weight
		ft	ft	K
10 FT HP DISH	Paraboloid	223.50	10.00	0.40
(E)	w/Shroud (HP)			0.81
1 FT HP DISH	Paraboloid	221.00	1.00	0.03
(WINDSTAR 43029)	w/Shroud (HP)			0.04
(E)				

Maximum Reactions

Location	Condition	Gov.	Vertical	Horizontal, X	Horizontal, 2
		Load	K	K	K
		Comb.			
Leg D	Max. Vert	16	258.49	16.24	-16.93
-	Max. H _x	16	258.49	16.24	-16.93
	Max. H _z	3	-232.29	-14.84	15.81
	Min. Vert	3	-232.29	-14.84	15.81
	Min. H _x	12	-225.17	-14.98	15.79
	Min. Hz	16	258.49	16.24	-16.93
Leg C	Max. Vert	14	249.47	-16.30	-16.05
	Max. H _x	18	-214.31	14.89	14.74
	Max. H _z	18	-214.31	14.89	14.74
	Min. Vert	9	-217.13	14.66	14.45
	Min. H _x	14	249.47	-16.30	-16.05
	Min. Hz	14	249.47	-16.30	-16.05
Leg B	Max. Vert	12	261.71	-17.13	16.38
	Max. H _x	16	-221.93	15.49	-14.94
	Max. H _z	12	261.71	-17.13	16.38
	Min. Vert	7	-227.77	15.42	-14.78
	Min. H _x	12	261.71	-17.13	16.38
	Min. Hz	16	-221.93	15.49	-14.94
Leg A	Max. Vert	18	250.92	16.02	16.36
_	Max. H _x	18	250.92	16.02	16.36
	Max. H _z	18	250.92	16.02	16.36
	Min. Vert	5	-216.43	-14.29	-14.82
	Min. H _x	14	-212.84	-14.60	-14.99
	Min. H _z	14	-212.84	-14.60	-14.99

Malouf Engineering Int'l, Inc. 17950 Preston Road, Suite #720

7950 Preston Road, Suite #72 Dallas, TX 75252 Phone: (972) 783-2578 FAX: (972) 783-2583

Job		Page
	125 FT SST, STAMFORD CENTRAL SITE #CT2118	4 of 6
Proje	ect	Date
	CT02768S-15V2	09:01:11 06/25/15
Clien	t VERTICAL RESOURCES GROUP / AT&T	Designed by LNguyen

Maximum Tower Deflections - Service Wind

Section	Elevation	Horz.	Gov.	Tilt	Twist
No.		Deflection	Load		
	ft	in	Comb.	0	0
T1	231.5 - 229	2.821	20	0.1784	0.0306
T2	229 - 224.833	2.700	20	0.1780	0.0270
T3	224.833 - 220.667	2.545	20	0.1770	0.0268
T4	220.667 - 216.5	2.392	20	0.1742	0.0261
T5	216.5 - 211.5	2.240	20	0.1701	0.0251
T6	211.5 - 206.5	2.059	20	0.1661	0.0231
T7	206.5 - 201.5	1.882	20	0.1606	0.0210
T8	201.5 - 196.5	1.710	20	0.1542	0.0189
T9	196.5 - 191.5	1.545	20	0.1462	0.0167
T10	191.5 - 181.5	1.388	20	0.1372	0.0149
T11	181.5 - 171.5	1.094	20	0.1244	0.0117
T12	171.5 - 161.5	0.829	20	0.1093	0.0093
T13	161.5 - 151.5	0.598	20	0.0922	0.0073
T14	151.5 - 141.5	0.405	20	0.0736	0.0057
T15	141.5 - 131.5	0.249	20	0.0568	0.0043
T16	131.5 - 119	0.128	20	0.0393	0.0033
T17	119 - 106.5	0.037	20	0.0201	0.0015

Critical Deflections and Radius of Curvature - Service Wind

Elevation	Appurtenance	Gov.	Deflection	Tilt	Twist	Radius of
		Load				Curvature
ft		Comb.	in	0	0	ft
245.17	(2) TOP SMALL BEACONS	20	2.821	0.1784	0.0306	8111
244.50	TOP LIGHTNING ROD	20	2.821	0.1784	0.0306	8111
235.00	P65-15-XLH-RR w/ Pipe Mount	20	2.821	0.1784	0.0306	8111
233.00	RAYCAP DC6-48-60-18-8F DC	20	2.821	0.1784	0.0306	8111
	SURGE BOX					
231.50	13' T BEAM MOUNT	20	2.821	0.1784	0.0306	8111
229.00	1.5'x2-ELEMENT YAGI AND	20	2.700	0.1780	0.0270	8111
	MOUNT					
223.50	10 FT HP DISH	20	2.497	0.1763	0.0267	114717
				(3 dB)	(3 dB)	
				0.2957	0.2957	
221.00	1 FT HP DISH (WINDSTAR 43029)	20	2.404	0.1745	0.0261	284636
216.50	4'Lx6'W REST PLATFORM	20	2.240	0.1701	0.0251	174663
209.50	(2) AIR21 B2A B4P w/ pipe Mount	20	1.988	0.1701	0.0221	56628
203.00	10"T x 9.5"W x 3.5"D TMA's	20	1.761	0.1562	0.0222	48308
132.00	4'x7-ELEMENT YAGI	20	0.133	0.1302	0.0193	28077
132.00	4X/-ELEMENT YAGI	20	0.133	0.0402	0.0033	20077

Section Capacity Table

Section No.	Elevation ft	Component Type	Size	Critical Element	P K	$SF*P_{allow} \ K$	% Capacity	Pass Fail
	<u>v</u>		T 4 4 2/0					
T1	231.5 - 229	Leg	L4x4x3/8	4	-4.54	69.70	87.6	Pass
T2	229 - 224.833	Leg	L4x4x3/8	12	-7.58	65.17	11.6	Pass
Т3	224.833 -	Leg	L4x4x3/8	21	-14.95	65.17	22.9	Pass
	220.667							
T4	220.667 - 216.5	Leg	L4x4x3/8	37	-20.76	65.17	31.9	Pass
T5	216.5 - 211.5	Leg	L5x5x1/2	51	-27.66	109.68	25.2	Pass
Т6	211.5 - 206.5	Leg	L5x5x1/2	67	-38.91	109.68	35.5	Pass
T7	206.5 - 201.5	Leg	L5x5x1/2	83	-49.26	109.68	44.9	Pass

Malouf Engineering Int'l, Inc. 17950 Preston Road, Suite #720

17950 Preston Road, Suite #72 Dallas, TX 75252 Phone: (972) 783-2578 FAX: (972) 783-2583

	Job 125	FT SST, STAMFORD CENTRAL SITE #CT2118	Page 5 of 6
	123	FT 331, STAWFORD GENTRAL SITE #GTZ110	0 01 0
Γ	Project		Date
		CT02768S-15V2	09:01:11 06/25/15
	Client	VERTICAL RESOURCES GROUP / AT&T	Designed by LNguyen

	TI .	<i>C</i> .	g.	G :: 1	D.	GEV-D	0.4	D
Section	Elevation ft	Component Type	Size	Critical Element	P K	SF*P _{allow} K	% Canacity	Pass Fail
No.		**	T # # 4 /A				Capacity	
T8	201.5 - 196.5	Leg	L5x5x1/2	95	-60.49	109.68	55.2	Pass
T9	196.5 - 191.5	Leg	L5x5x1/2	111	-72.39	109.68	66.0	Pass
T10	191.5 - 181.5	Leg	L6x6x5/8	123	-83.06	171.13	48.5	Pass
T11	181.5 - 171.5	Leg	L6x6x5/8	148	-105.30	171.31	61.5	Pass
T12	171.5 - 161.5	Leg	L6x6x5/8	168	-126.92	171.45	74.0	Pass
T13	161.5 - 151.5	Leg	L6x6x5/8	193	-147.98	171.58	86.2	Pass
T14	151.5 - 141.5	Leg	L6x6x3/4	213	-171.56	203.35	84.4	Pass
T15	141.5 - 131.5	Leg	L6x6x3/4	238	-190.92	227.69	83.9	Pass
T16	131.5 - 119	Leg	L6x6x7/8	306	-206.87	220.76	93.7	Pass
T17	119 - 106.5	Leg	L6x6x7/8	347	-233.39	256.70	90.9	Pass
T2	229 - 224.833	Diagonal	2L2 1/2x2x1/4x3/8	20	-3.50	47.46	7.4	Pass
Т3	224.833 -	Diagonal	2L2 1/2x2x1/4x3/8	35	-4.18	47.46	8.8	Pass
TD 4	220.667	D: 1	21 2 1 /2 2 1 /4 2 /2	45	5 41	12.22	12.0	ъ.
T4	220.667 - 216.5		2L2 1/2x2x1/4x3/8	47	-5.41	42.32	12.8	Pass
T5	216.5 - 211.5	Diagonal	L2 1/2x2x1/4	63	-5.65	16.13	35.0	Pass
T6	211.5 - 206.5	Diagonal	L2 1/2x2x1/4	79	-5.90	15.52	38.0	Pass
T7	206.5 - 201.5	Diagonal	L2 1/2x2x1/4	91	-6.78	14.88	45.5	Pass
T8	201.5 - 196.5	Diagonal	L2 1/2x2x1/4	107	-7.34	14.20	51.7	Pass
T9	196.5 - 191.5	Diagonal	L2 1/2x2x1/4	119	-7.35	13.49	54.5	Pass
T10	191.5 - 181.5	Diagonal	L3x3x1/4	138	-12.23	18.16	67.3	Pass
T11	181.5 - 171.5	Diagonal	L3x3x1/4	158	-12.34	17.25	71.5	Pass
T12	171.5 - 161.5	Diagonal	L3x3x1/4	183	-12.73	16.34	77.9	Pass
T13	161.5 - 151.5	Diagonal	L3x3x1/4	203	-13.11	15.46	84.8	Pass
T14	151.5 - 141.5	Diagonal	L3x3x1/4	228	-12.33	14.61	84.4	Pass
T15	141.5 - 131.5	Diagonal	L3x3x1/4	260	-14.72	25.96	56.7	Pass
m	101 - 110	·	07.0.1/0.0.1/0.1/1.0/0	2.10	10.50	2-1-	59.5 (b)	
T16	131.5 - 119	Diagonal	2L2 1/2x2 1/2x1/4x3/8	340	-18.69	36.15	51.7	Pass
T17	119 - 106.5	Diagonal	2L2 1/2x2 1/2x1/4x3/8	407	-18.60	49.40	37.6	Pass
T15	141.5 - 131.5	Horizontal	L2 1/2x2x1/4	251	-2.87	6.80	42.1	Pass
T10	191.5 - 181.5	Secondary Horizontal	L2 1/2x2x1/4	143	-1.25	5.74	21.7	Pass
T11	181.5 - 171.5	Secondary Horizontal	L2 1/2x2x1/4	164	-1.58	4.88	32.4	Pass
T12	171.5 - 161.5	Secondary Horizontal	L2 1/2x2x3/16	188	-1.91	3.26	58.5	Pass
T13	161.5 - 151.5	Secondary Horizontal	L2 1/2x2 1/2x1/4	208	-2.22	5.51	40.3	Pass
T14	151.5 - 141.5	Secondary Horizontal	L2 1/2x2x1/4	233	-2.58	3.25	79.3	Pass
T1	231.5 - 229	Top Girt	C8x11.5	8	-0.55	45.47	18.0	Pass
Т3	224.833 -	Top Girt	L2 1/2x2 1/2x1/4	25	-0.94	16.58	5.7	Pass
m.r	220.667	T. C'.	G7 0 0		1.01	44.01	2.2	ъ.
T5	216.5 - 211.5	Top Girt	C7x9.8	53	-1.01	44.01	2.3 3.7 (b)	Pass
T6	211.5 - 206.5	Top Girt	L2 1/2x2x1/4	69	-0.84	11.61	7.2	Pass
T8	201.5 - 196.5	Top Girt	L2 1/2x2 1/2x1/4	97	-0.72	13.26	5.5	Pass
T10	191.5 - 181.5	Top Girt	L2 1/2x2 1/2x1/4	127	3.51	28.16	12.5	Pass
							14.2 (b)	
T11	181.5 - 171.5	Top Girt	L2 1/2x2 1/2x1/4	150	-5.12	17.20	29.8	Pass
T12	171.5 - 161.5	Top Girt	L2 1/2x2 1/2x1/4	172	7.22	28.16	25.6	Pass
							29.2 (b)	
T13	161.5 - 151.5	Top Girt	L2 1/2x2 1/2x1/4	195	-6.23	14.22	43.8	Pass
T14	151.5 - 141.5	Top Girt	L2 1/2x2 1/2x1/4	215	-5.73	21.28	26.9	Pass
							30.0 (b)	
T15	141.5 - 131.5	Top Girt	L2 1/2x2 1/2x1/4	240	-6.04	11.58	52.2	Pass
T16	131.5 - 119	Top Girt	2L2 1/2x2 1/2x1/4x3/8	311	-9.34	40.29	23.2	Pass
T17	119 - 106.5	Top Girt	2L2 1/2x2 1/2x1/4x3/8	352	-8.73	36.94	23.6	Pass
T15	141.5 - 131.5	Redund Horz 1 Bracing	L2 1/2x2x3/16	286	-2.87	14.46	19.8	Pass
T16	131.5 - 119	Redund Horz 1 Bracing	L2 1/2x2x3/16	327	-3.11	14.29	21.7	Pass
T17	119 - 106.5	Redund Horz 1 Bracing	L2 1/2x2x3/16	389	-3.50	13.76	25.5	Pass
T15	141.5 - 131.5	Redund Diag 1	L2 1/2x2x3/16	291	-1.94	12.65	15.3	Pass
T16	131.5 - 119	Bracing Redund Diag 1	L2 1/2x2x3/16	328	-3.60	5.32	67.7	Pass
		-						

Malouf Engineering Int'l, Inc. 17950 Preston Road, Suite #720

7950 Preston Road, Suite #720 Dallas, TX 75252 Phone: (972) 783-2578 FAX: (972) 783-2583

Job)	Page
	125 FT SST, STAMFORD CENTRAL SITE #CT2118	6 of 6
Pre	oject	Date
	CT02768S-15V2	09:01:11 06/25/15
Cli	ient VERTICAL RESOURCES GROUP / AT&T	Designed by LNguyen

Section No.	Elevation ft	Component Type	Size	Critical Element	P K	$SF*P_{allow} \ K$	% Capacity	Pass Fail
110.		Bracing					1 2	
T17	119 - 106.5	Redund Diag 1 Bracing	L2 1/2x2x3/16	360	5.23	23.29	22.4	Pass
T15	141.5 - 131.5	Redund Hip 1 Bracing	L2x2x1/4	303	-0.03	12.17	0.2	Pass
T16	131.5 - 119	Redund Hip 1 Bracing	L2x2x1/4	344	-0.14	11.45	1.2	Pass
T17	119 - 106.5	Redund Hip 1 Bracing	L2x2x1/4	402	-0.18	9.87	1.9	Pass
Т17	119 - 106.5	Redund Hip Diagonal Bracing	L2x2x1/4	419	-0.12	2.18	5.3	Pass
Т17	119 - 106.5	Redund Sub Horz Bracing	L2 1/2x2x3/16	365	-3.90	20.91	18.6	Pass
Γ17	119 - 106.5	Redund Sub Diagonal Bracing	L2 1/2x2x3/16	394	-4.64	15.91	29.2	Pas
Γ10	191.5 - 181.5	Inner Bracing	L2 1/2x2 1/2x3/16	133	-0.04	5.55	0.7	Pass
Γ12	171.5 - 161.5	Inner Bracing	L2 1/2x2 1/2x3/16	178	-0.08	3.88	2.2	Pas
14	151.5 - 141.5	Inner Bracing	L2x2 1/2x3/16	223	-0.09	1.91	4.5	Pas
116	131.5 - 119	Inner Bracing	L3x3x3/16	316	-0.14	3.86	3.5	Pas
17	119 - 106.5	Inner Bracing	L3x3x3/16	357	-0.13	3.33	3.9	Pas
. 1 /	117 100.5	miler Bracing	L3X3X3/10	337	0.13	3.33	Summary	1 43
						Lag (T16)		Dos
						Leg (T16) Diagonal (T13)	93.7 84.8	Pas Pas
						Horizontal (T15)	42.1	Pas
						Secondary Horizontal (T14)	79.3	Pas
						Top Girt (T15)	52.2	Pas
						Redund Horz 1 Bracing	25.5	Pas
						(T17)		
						Redund Diag 1 Bracing (T16)	67.7	Pas
						Redund Hip 1 Bracing (T17)	1.9	Pas
						Redund Hip Diagonal Bracing (T17)	5.3	Pas
						Redund Sub Horz Bracing	18.6	Pas
						(T17) Redund Sub Diagonal Bracing (T17)	29.2	Pas
						Inner Bracing (T14)	4.5	Pas
						Bolt Checks	64.5	Pas
						RATING =	93.7	Pas

APPENDIX 2 - SOURCE / CHANGED CONDITION



From: Vertical Resources Group [mailto:mnobre@verticalresourcesgrp.com]

Sent: Wednesday, June 10, 2015 1:00 PM

To: 'Mark Malouf'

Subject: New Analysis Request site CT2118

Mark Empire would want to pass the analysis of this tower through us.

Here is the scoop.

Previous MEI analysis: MEI Project CT02768S-15V1 dated May 12, 2015

Existing AT&T Loading:

- 60' (3) KMW AMXCD146500TRET panels
- 60' (6) Powerwave P6515XLHRR panels
- 60' (12) Powerwave LGP21401 TMA
- 60' (6) Ericsson RRUS-11 Remote Radio Heads
- 60' (1) Raycap DC6-48-60-18-8F

Proposed Final Loading Configuration:

- 60' (3) Powerwave P6515XLHRR panels
- 60' (6) CCI OPA-65R-LCUU-H4 panels
- 60' (6) Powerwave LGP21401 TMA
- 60' (3) Ericsson RRUS-11 Remote Radio Heads
- 60' (3) Ericsson RRUS-12 Remote Radio Heads
- 60' (3) Ericsson A2 modules attached to back of RRUS-12
- 60' (3) Ericsson RRUS-32 Remote Radio Heads
- 60' (1) Raycap DC6-48-60-18-8F existing
- 60' (1) Raycap DC6-48-60-18-8F proposed

...

Thanks Mark

Miguel Nobre

Vertical Resources Group

489 Washington Street Auburn, MA 01501

P: 508-981-9590 F: 508-519-8939

Tower / Radio Information - Call Sign information needs to be tied to a specific antenna(s). Adjust letters as needed.

Α	Call Sign	WPWV368
	Class of Station	LTE 700 Mhz
	Emission Type	
	Transmit Frequency	734-746
	Output Power (watts)	250
	Transmitter ERP (dBm)	53.98
	Receive Frequency	716-728
В	Call Sign	KNLG502
	Class of Station	LTE 1900 Mhz
	Emission Type	
	Transmit Frequency	1985-1990, 1905-1910
	Output Power (watts)	250
	Transmitter ERP (dBm)	53.98
	Receive Frequency	1930-1945, 1850-1865
_	0-11 0:	KNIKAOFO
C	Call Sign	KNKA259
	Class of Station	800Mhz UMTS
	Emission Type	200 004 045 040
	Transmit Frequency	890-891, 845-846
	Output Power (watts)	250
	Transmitter ERP (dBm)	53.98
	Receive Frequency	869-879, 824,834
	Please attach frequency coordin	ation data (PCN)

D Call Sign Class of Station Emission Type	KNLB297 LTE 2300
Transmit Frequency	2345-2360,
Output Power (watts)	250
Transmitter ERP (dBm)	53.98
Receive Frequency	2305-2320
E Call Sign	KNLB312
Class of Station	
Emission Type	
Transmit Frequency	2350-2355
Output Power (watts)	250
Transmitter ERP (dBm)	53.98
Receive Frequency	2305-2310
F Call Sign	KNLB204
Class of Station	
Emission Type	
Transmit Frequency	2310-2315
Output Power (watts)	250
Transmitter ERP (dBm)	53.98
Receive Frequency	2355-2360

Coax / Waveguide / Cable				
	Information			
Type:	andrew			
Size:	1 5/8"			
Length:	275			
# of runs:	12			
Type:	DC Trunk line			
Size:	3/4"			
Length:	275			
# of runs:	4			
Type:	Fiber trunk			
Size:	5/8"			
Length:	275			
# of runs:	2			
Type:				
Size:				
Length:				
# of runs:				
	_			

Antenna & Ancillary Equipment Information		Check one						Heights - Above Ground Level (feet)		Notes: (including removals, ice shields,	
# Make	Model	Existing	Proposed	Size / Dimensions	Weight	Azimuth	RAD Center	Attachment	Tip	etc.)	
A CCI Products	OPA-65R-LCUU-H4		х	48 x 14.4 x 7.3	57	60	235	235	238		
B CCI Products	OPA-65R-LCUU-H4		х	48 x 14.4 x 7.3	57	60	235	235	238		
CCI Products	OPA-65R-LCUU-H4		х	48 x 14.4 x 7.3	57	180	235	235	238		
CCI Products	OPA-65R-LCUU-H4		х	48 x 14.4 x 7.3	57	180	235	235	238		
CCI Products	OPA-65R-LCUU-H4		х	48 x 14.4 x 7.3	57	300	235	235	238		
CCI Products	OPA-65R-LCUU-H4		х	48 x 14.4 x 7.3	57	300	235	235	238		
Power wave	P65-15-XLH-RR	х		51 x 12 x6	51	110	235	235	238		
Power wave	P65-15-XLH-RR	х		52 x 12 x6	51	280	235	235	238		
Power wave	P65-15-XLH-RR	х		53 x 12 x6	51	0	235	235	238		
Power wave	P65-15-XLH-RR	х		54 x 12 x6	51	110	235	235	238	removing	
Power wave	P65-15-XLH-RR	х		55 x 12 x6	51	280	235	235	238	removing	
Power wave	P65-15-XLH-RR	х		56 x 12 x6	51	0	235	235	238	removing	
KMW	AM-X-CD-14-65-OOT-RET	х		48 x 11.8 x 5.9	36.4	60	235	235	238	removing	
KMW	AM-X-CD-14-65-OOT-RET	х		48 x 11.8 x 5.9	36.4	180	235	235	238	removing	
KMW	AM-X-CD-14-65-OOT-RET	х		48 x 11.8 x 5.9	36.4	300	235	235	238	removing	
Power wave	LGP 21401	х		6 x8 x2	7.7lbs					12 total 4 per sector (TMA)	
Ericsson	RRUS-11	х		17 x 17 x 6	50 lbs ea	60/180/300	235	235		3 radio heads 1 per sector	
Ericsson	RRUS-12	х		17 x 17 x 6	50 lbs ea	60/180/300	235	235		3 radio heads being removed	
Ericsson	RRUS-12		х	17 x 17 x 6	50 lbs ea	60/180/300	235	235		3 new radio heads	
Ericsson	A-2 module		х	12 x 12 x 4	20lbs ea	60/180/300	235	235		attached to back of RRUS-12	
Ericsson	RRUS-32		х	17 x 17 x 6	77 lbs ea	60/180/300	235	235		3 new radio heads	
RAYCAP	Squid	Х			25lbs		232	232		fiber and DC junction box	
RAYCAP	Squid		х		25lbs		232	232		new fiber and DC junction box	

Exhibit C



RADIO FREQUENCY EMISSIONS ANALYSIS REPORT EVALUATION OF HUMAN EXPOSURE POTENTIAL TO NON-IONIZING EMISSIONS

T-Mobile Existing Facility

Site ID: CT11410A

Stamford/ Dwtn 555 E. Main Street Stamford, CT 06901

August 31, 2015

EBI Project Number: 6215004565

Site Compliance Summary					
Compliance Status:	COMPLIANT				
Site total MPE% of FCC general public	12.18 %				
allowable limit:	12.10 %				



August 31, 2015

T-Mobile USA Attn: Jason Overbey, RF Manager 35 Griffin Road South Bloomfield, CT 06002

Emissions Analysis for Site: **CT11410A – Stamford/ Dwtn**

EBI Consulting was directed to analyze the proposed T-Mobile facility located at **555 E. Main Street, Stamford, CT**, for the purpose of determining whether the emissions from the Proposed T-Mobile Antenna Installation located on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter (μ W/cm²). The number of μ W/cm² calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits, therefore it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) - (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general public may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general public would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

Public exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter (μ W/cm²). The general population exposure limit for the 700 MHz Band is approximately 467 μ W/cm², and the general population exposure limit for the PCS and AWS bands is 1000 μ W/cm². Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.



Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure. Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

CALCULATIONS

Calculations were done for the proposed T-Mobile Wireless antenna facility located at **555 E. Main Street, Stamford, CT**, using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. Since T-Mobile is proposing highly focused directional panel antennas, which project most of the emitted energy out toward the horizon, all calculations were performed assuming a lobe representing the maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was focused at the base of the tower. For this report the sample point is the top of a 6 foot person standing at the base of the tower.

For all calculations, all equipment was calculated using the following assumptions:

- 1) 2 UMTS channels (PCS Band 1900 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 30 Watts per Channel
- 2) 2 UMTS channels (AWS Band 2100 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 30 Watts per Channel.
- 3) 2 LTE channels (AWS Band 2100 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 60 Watts per Channel.
- 4) 1 LTE channel (700 MHz Band) was considered for each sector of the proposed installation. This channel has a transmit power of 30 Watts.
- 5) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.



- 6) For the following calculations the sample point was the top of a six foot person standing at the base of the tower. The maximum gain of the antenna per the antenna manufactures supplied specifications minus 10 dB was used in this direction. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 7) The antennas used in this modeling are the Ericsson AIR21 (B4A/B2P & B2A/B4P) for 1900 MHz (PCS) and 2100 MHz (AWS) channels and the Commscope LNX-6515DS-VTM for 700 MHz channels. This is based on feedback from the carrier with regards to anticipated antenna selection. The Ericsson AIR21 B4A/B2P & B2A/B4P) have a maximum gain of 15.9 dBd at their main lobe. The Commscope LNX-6515DS-VTM has a maximum gain of 14.6 dBd at its main lobe. The maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was used for all calculations. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 8) The antenna mounting height centerlines of the proposed antennas are **203 & 209.5 feet** above ground level (AGL).
- 9) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.

All calculations were done with respect to uncontrolled / general public threshold limits.



T-Mobile Site Inventory and Power Data

Sector:	A	Sector:	В	Sector:	С
Antenna #:	1	Antenna #:	1	Antenna #:	1
Make / Model:	Ericsson AIR21 B4A/B2P	Make / Model:	Ericsson AIR21 B4A/B2P	Make / Model:	Ericsson AIR21 B4A/B2P
Gain:	15.9 dBd	Gain:	15.9 dBd	Gain:	15.9 dBd
Height (AGL):	209.5	Height (AGL):	209.5	Height (AGL):	209.5
Frequency Bands	2100 MHz (AWS)	Frequency Bands	2100 MHz (AWS)	Frequency Bands	2100 MHz (AWS)
Channel Count	2	Channel Count	2	# PCS Channels:	2
Total TX Power:	120	Total TX Power:	120	# AWS Channels:	120
ERP (W):	4,668.54	ERP (W):	4,668.54	ERP (W):	4,668.54
Antenna A1 MPE%	0.41	Antenna B1 MPE%	0.41	Antenna C1 MPE%	0.41
Antenna #:	2	Antenna #:	2	Antenna #:	2
Make / Model:	Ericsson AIR21 B4A/B2P	Make / Model:	Ericsson AIR21 B4A/B2P	Make / Model:	Ericsson AIR21 B4A/B2P
Gain:	15.9 dBd	Gain:	15.9 dBd	Gain:	15.9 dBd
Height (AGL):	209.5	Height (AGL):	209.5	Height (AGL):	209.5
Frequency Bands	1900 MHz(PCS) / 2100 MHz (AWS)	Frequency Bands	1900 MHz(PCS) / 2100 MHz (AWS)	Frequency Bands	1900 MHz(PCS) / 2100 MHz (AWS)
Channel Count	4	Channel Count	4	Channel Count	4
Total TX Power:	120	Total TX Power:	120	Total TX Power:	120
ERP (W):	4,668.54	ERP (W):	4,668.54	ERP (W):	4,668.54
Antenna A2 MPE%	0.41	Antenna B2 MPE%	0.41	Antenna C2 MPE%	0.41
Antenna #:	3	Antenna #:	3	Antenna #:	3
Make / Model:	Commscope LNX- 6515DS-VTM	Make / Model:	Commscope LNX- 6515DS-VTM	Make / Model:	Commscope LNX- 6515DS-VTM
Gain:	14.6 dBd	Gain:	14.6 dBd	Gain:	14.6 dBd
Height (AGL):	203	Height (AGL):	203	Height (AGL):	203
Frequency Bands	700 MHz	Frequency Bands	700 MHz	Frequency Bands	700 MHz
Channel Count	1	Channel Count	1	Channel Count	1
Total TX Power:	30	Total TX Power:	30	Total TX Power:	30
ERP (W):	865.21	ERP (W):	865.21	ERP (W):	865.21
Antenna A3 MPE%	0.17	Antenna B3 MPE%	0.17	Antenna C3 MPE%	0.17

Site Composite MPE%					
Carrier	MPE%				
T-Mobile (Per Sector Max)	0.98 %				
AT&T	4.75 %				
WinStar Wireless	0.71 %				
PageNet	1.44 %				
Broadcast Video	4.30 %				
Site Total MPE %:	12.18 %				

T-Mobile Sector 1 Total:	0.98 %
T-Mobile Sector 2 Total:	0.98 %
T-Mobile Sector 3 Total:	0.98 %
Site Total:	12.18 %

T-Mobile _per sector	# Channels	Watts ERP (Per Channel)	Height (feet)	Total Power Density (µW/cm²)	Frequency (MHz)	Allowable MPE (µW/cm²)	Calculated % MPE
T-Mobile 2100 MHz (AWS) LTE	2	2334.27	209.5	4.05	2100	1000	0.41%
T-Mobile 700 MHz LTE	1	865.21	203	0.80	700	467	0.17 %
T-Mobile 1900 MHz (PCS) UMTS	2	1167.14	209.5	2.03	1900	1000	0.20 %
T-Mobile 2100 MHz (AWS) UMTS	2	1167.14	209.5	2.03	2100	1000	0.20 %
						Total:	0.98%

21 B Street Burlington, MA 01803 Tel: (781) 273.2500 Fax: (781) 273.3311



Summary

All calculations performed for this analysis yielded results that were **within** the allowable limits for general public exposure to RF Emissions.

The anticipated maximum composite contributions from the T-Mobile facility as well as the site composite emissions value with regards to compliance with FCC's allowable limits for general public exposure to RF Emissions are shown here:

T-Mobile Sector	Power Density Value (%)
Sector 1:	0.98 %
Sector 2:	0.98 %
Sector 3:	0.98 %
T-Mobile Per Sector	0.98 %
Maximum:	
Site Total:	12.18 %
Site Compliance Status:	COMPLIANT

The anticipated composite MPE value for this site assuming all carriers present is **12.18%** of the allowable FCC established general public limit sampled at the ground level. This is based upon values listed in the Connecticut Siting Council database for existing carrier emissions.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.

Scott Heffernan

RF Engineering Director

EBI Consulting

21 B Street

Burlington, MA 01803