

**JULIE D. KOHLER**

PLEASE REPLY TO: Bridgeport  
WRITER'S DIRECT DIAL: (203) 337-4157  
E-Mail Address: jkohler@cohenandwolf.com

March 11, 2015

Attorney Melanie Bachman  
Acting Executive Director  
Connecticut Siting Council  
Ten Franklin Square  
New Britain, CT 06051

**Re: Notice of Exempt Modification  
Glenbrook Industrial Park Associates LLC /T-Mobile equipment upgrade  
Site ID CT11334A  
652 Glenbrook Road, Stamford Connecticut**

Dear Attorney Bachman:

This office represents T-Mobile Northeast LLC ("T-Mobile") and has been retained to file exempt modification filings with the Connecticut Siting Council on its behalf.

In this case, Glenbrook Industrial Park Associates LLC owns the existing water tank and related facility located at 652 Glenbrook Road, Stamford, Connecticut (Latitude: 41.075484; Longitude: -73.519141). T-Mobile intends to replace three (3) antennas and add related equipment at this existing telecommunications facility in Stamford ("Stamford Facility"). Please accept this letter as notification, pursuant to R.C.S.A. § 16-50j-73, of construction which constitutes an exempt modification pursuant to R.C.S.A. § 16-50j-72(b)(2). In accordance with R.C.S.A. § 16-50j-73, a copy of this letter is being sent to the Mayor, David R. Martin. Glenbrook Industrial Park Associates LLC is also the property owner.

The existing Stamford Facility consists of a 108' 10" foot tall water tank.<sup>1</sup> T-Mobile plans to replace three (3) antennas, and add three (3) RRU's (remote radio units) at a centerline of 85 feet. (See the plans revised to February 28, 2015 attached hereto as Exhibit A). The existing Stamford Facility is structurally capable of supporting T-Mobile's proposed modifications, as indicated in the structural analysis dated February 25, 2015 and attached hereto as Exhibit B.

The planned modifications to the Stamford Facility fall squarely within those activities explicitly provided for in R.C.S.A. § 16-50j-72(b)(2).

1. The proposed modification will not increase the height of the water tank. T-Mobile's proposed modifications will be installed at a centerline of 85 feet, merely modifying

<sup>1</sup> The CSC online database does not contain a Docket or Petition relevant to the approval of this facility, however there are notices of intent captioned EM-CING-135-130703, EM-T-MOBILE-135-120620, and EM-CING-135-110630.

March 11, 2015  
Site ID CT11334A  
Page 2

existing antennas located at the same 85 foot elevation. The enclosed tower drawing confirms that the proposed modification will not increase the height of the water tank.

2. The proposed modifications will not require an extension of the site boundaries. T-Mobile is not proposing any modifications within the existing compound area (as shown on Sheet A-1).

3. The proposed modification to the Stamford Facility will not increase the noise levels at the existing facility by six decibels or more.

4. The operation of the replacement antennas will not increase the total radio frequency (RF) power density, measured at the base of the water tank, to a level at or above the applicable standard. According to a Radio Frequency Emissions Analysis Report prepared by EBI dated March 10, 2015, T-Mobile's operations would add 19.34% of the FCC Standard. Therefore, the calculated "worst case" power density for the planned combined operation at the site including all of the proposed antennas would be 87.62% of the FCC Standard as calculated for a mixed frequency site as evidenced by the engineering exhibit attached hereto as Exhibit C.

For the foregoing reasons, T-Mobile respectfully submits that the proposed replacement/additional antennas and equipment at the Stamford Facility constitutes an exempt modification under R.C.S.A. § 16-50j-72(b)(2). Upon acknowledgement by the Council of this proposed exempt modification, T-Mobile shall commence construction approximately sixty days from the date of the Council's notice of acknowledgement.

Sincerely,

  
Julie D. Kohler, Esq.

cc: City of Stamford, Mayor David R. Martin  
Glenbrook Industrial Park Associates LLC c/o Spinnaker Real Estate Partners LLC  
Sheldon Freinle, NSS

# **EXHIBIT A**



# T-MOBILE NORTHEAST LLC

SITE #: CT11334A

SITE NAME: STAMFORD-3/HOPE ST

SITE ADDRESS:

652 GLENBROOK ROAD

STAMFORD, CT 06907

WIRELESS BROADBAND FACILITY

CONSTRUCTION DRAWINGS

(702CU CONFIGURATION)


**T-Mobile**  
**T-MOBILE NORTHEAST, LLC**  
 35 GRIFFIN ROAD SOUTH  
 BLOOMFIELD, CT 06002  
 OFFICE: (860) 692-7100  
 FAX: (860) 692-7139

**ATLANTIS**  
**G R O U P**  
 1340 Centre Street, Suite 212  
 Newton Center, MA 02459  
 Office: 617-965-0789  
 Fax: 617-213-5056

SUBMITTALS			
DATE	DESCRIPTION	REVISION	
02/19/15	ISSUED FOR BIDDING	A	0
02/26/15	FINAL CD	B	0

DEPT.	DATE	APPRO	REVISIONS
RTE			
FR MAN			
ZONING			
OPS			
CONSTR			
SITE AC			

PROJECT NO: CT11334A  
 DRAWN BY: FG  
 CHECKED BY: SM



THIS DOCUMENT IS THE CREATION, DESIGN, PROPERTY AND COPYRIGHTED WORK OF T-MOBILE. ANY DUPLICATION OR USE WITHOUT EXPRESS WRITTEN CONSENT IS STRICTLY PROHIBITED.

SITE NUMBER  
 CT11334A  
 SITE NAME  
 STAMFORD-3/HOPE ST  
 SITE ADDRESS  
 652 GLENBROOK ROAD  
 STAMFORD, CT 06907

SHEET TITLE  
 TITLE SHEET

SHEET NUMBER  
 T-1

### SITE INFORMATION

SITE NUMBER: CT11334A  
 SITE NAME: STAMFORD-3/HOPE ST  
 SITE ADDRESS: 652 GLENBROOK ROAD STAMFORD, CT 06907  
 LAT./LONG.: N 41.075484 / W -73.519141  
 JURISDICTION: FAIRFIELD COUNTY  
 PROPERTY OWNER: GLENBROOK INDUSTRIAL PARK, LLC  
 C/O SPRINKLER REAL ESTATE PARTNERS, LLC  
 1 NORTH WATER STREET, SUITE 100  
 NORWALK, CT 06854  
 SHELLY  
 SHELLY@SPRINKER.COM  
 203-354-1542

### PROJECT SUB-CONTRACTORS

APPLICANT: T-MOBILE NORTHEAST, LLC.  
 35 GRIFFIN ROAD SOUTH  
 BLOOMFIELD, CT 06002  
 (860) 692-7100

PROJECT MANAGER: USA LIN ALLEN  
 NORTHEAST SITE SOLUTIONS  
 54 MAIN STREET  
 STURBRIDGE, MA 01566  
 (508) 434-5237

ARCHITECT/ENGINEER: ATLANTIS GROUP INC.  
 1340 CENTRE STREET SUITE 212  
 NEWTON CENTER, MA 02459  
 (617) 965-0789

### CODE COMPLIANCE

CONNECTICUT STATE BUILDING CODE  
 2006 CONNECTICUT BUILDING CODE WITH 2013 AMENDMENT  
 2011 NATIONAL ELECTRICAL CODE  
 CONSTRUCTION TYPE: 2B USE GROUP: N/A

### SHEET INDEX

SHEET	DESCRIPTION
T-1	TITLE SHEET
N-1	GENERAL AND ELECTRICAL NOTES
A-1	COMPOUND PLAN AND ELEVATION
A-2	ANTENNA PLAN AND DETAILS
E-1	GROUNDING AND POWER ONE LINE DIAGRAM
E-2	GROUNDING DETAILS

### GENERAL NOTES

1. THE CONTRACTOR SHALL GIVE ALL NOTICES AND COMPLY WITH ALL LAWS, ORDINANCES, RULES, REGULATIONS AND LAWFUL ORDERS OF ANY PUBLIC AUTHORITY, MUNICIPAL AND UTILITY COMPANY SPECIFICATIONS, AND LOCAL AND STATE JURISDICTIONAL CODES BEARING ON THE PERFORMANCE OF THE WORK. THE WORK SHALL BE IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS AND ORDINANCES.
2. THE ARCHITECT/ENGINEER HAVE MADE EVERY EFFORT TO SET FORTH IN THE CONSTRUCTION AND CONSTRUCT DOCUMENTS THE COMPLETE SCOPE OF WORK. THE CONTRACTOR BIDDING THE JOB IS NEVERTHESS CAUTIONED THAT MINOR OMISSIONS OR ERRORS IN THE DRAWINGS AND OR SPECIFICATIONS SHALL NOT EXCLUDE SAID CONTRACTOR FROM COMPLETING THE PROJECT AND IMPROVEMENTS IN ACCORDANCE WITH THE INTENT OF THESE DOCUMENTS.
3. THE CONTRACTOR OR BIDDER SHALL BEAR THE RESPONSIBILITY OF NOTIFYING (IN WRITING) THE T-MOBILE REPRESENTATIVE OF ANY CONFLICTS, ERRORS, OR OMISSIONS PRIOR TO THE SUBMISSION OF THE CONTRACTOR'S PROPOSAL OR PERFORMANCE OF WORK. IN THE EVENT OF DISCREPANCIES, THE CONTRACTOR SHALL PRICE THE MORE COSTLY OR EXPENSIVE WORK, UNLESS DIRECTED IN WRITING OTHERWISE.
4. THE SCOPE OF WORK SHALL INCLUDE FURNISHING OF ALL MATERIALS, EQUIPMENT, LABOR AND ALL OTHER MATERIALS AND LABOR DEEMED NECESSARY TO COMPLETE THE WORK/PROJECT AS DESCRIBED HEREIN.
5. THE CONTRACTOR SHALL VISIT THE JOB SITE PRIOR TO THE SUBMISSION OF BIDS OR PERFORMING WORK TO FAMILIARIZE HIMSELF WITH THE FIELD CONDITIONS AND TO VERIFY THAT THE PROJECT CAN BE CONSTRUCTED IN ACCORDANCE WITH THE CONTRACT DOCUMENTS.
6. THE CONTRACTOR SHALL OBTAIN AUTHORIZATION TO PROCEED WITH CONSTRUCTION PRIOR TO STARTING WORK ON ANY ITEM NOT CLEARLY DENIED BY THE CONSTRUCTION DRAWINGS/CONTRACT DOCUMENTS.
7. THE CONTRACTOR SHALL INSTALL ALL EQUIPMENT AND MATERIALS ACCORDING TO THE MANUFACTURER'S/VENDOR'S SPECIFICATIONS UNLESS NOTED OTHERWISE OR WHERE LOCAL CODES OR ORDINANCES TAKE PRECEDENCE.
8. THE CONTRACTOR SHALL PROVIDE A FULL SET OF CONSTRUCTION DOCUMENTS AT THE SITE UPDATED WITH THE LATEST REVISIONS AND ADDENDUM OR CLARIFICATIONS AVAILABLE FOR THE USE BY ALL PERSONNEL INVOLVED WITH THE PROJECT.
9. THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE PROJECT DESCRIBED HEREIN. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR ALL CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES AND FOR COORDINATING ALL PORTIONS OF THE WORK UNDER CONTRACT.
10. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ANY PERMITS AND INSPECTIONS WHICH ARE REQUIRED FOR THE WORK BY THE ARCHITECT/ENGINEER, THE STATE, COUNTY, OR LOCAL GOVERNMENT AUTHORITY.
11. THE CONTRACTOR SHALL MAKE NECESSARY PROVISIONS TO PROTECT EXISTING IMPROVEMENTS, EASEMENTS, PAVING, CURBING, ETC., DURING CONSTRUCTION. UPON COMPLETION OF WORK, THE CONTRACTOR SHALL REPAIR ANY DAMAGE THAT MAY HAVE OCCURRED DUE TO CONSTRUCTION ON OR ABOUT THE PROPERTY.
12. THE CONTRACTOR SHALL KEEP THE GENERAL WORK AREA CLEAN AND HAZARD FREE DURING CONSTRUCTION AND DISPOSE OF ALL DIRT, DEBRIS, RUBBISH AND REMOVE EQUIPMENT NOT SPECIFIED AS REMAINING ON PROPERTY. PREMISES SHALL BE LEFT IN CLEAN CONDITION AND FREE FROM PAINT SPOTS, DUST, OR SLAGGERS OF ANY NATURE.
13. THE CONTRACTOR SHALL COMPLY WITH ALL OSHA REQUIREMENTS, AS WELL AS THE LATEST EDITIONS OF ANY PERTINENT STATE SAFETY REGULATIONS.
14. THE CONTRACTOR SHALL NOTIFY THE T-MOBILE REPRESENTATIVE WHERE A CONFLICT OCCURS ON ANY OF THE CONTRACT DOCUMENTS. THE CONTRACTOR IS NOT TO ORDER MATERIAL OR CONSTRUCT ANY PORTION OF THE WORK THAT IS IN CONFLICT UNTIL CONFLICT IS RESOLVED BY THE T-MOBILE REPRESENTATIVE.
15. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS, ELEVATIONS, PROPERTY LINES, ETC., ON THE JOB.
16. THE CONTRACTOR SHALL RETURN ALL DISTURBED AREAS TO THEIR ORIGINAL CONDITION AT THE COMPLETION OF WORK.
17. REFER TO STRUCTURAL ANALYSIS REPORT DOCUMENT ENTITLED, "STRUCTURAL ANALYSIS REPORT WATERMANK- PREPARED BY ATLANTIS GROUP, INC., "T-MOBILE SITE ID CT11334A", DATED FEBRUARY 23, 2015

### VICINITY MAP



### DO NOT SCALE DRAWINGS

CONTRACTOR SHALL VERIFY PLANS AND EXISTING DIMENSIONS AND CONDITIONS ON THE JOB SITE AND SHALL IMMEDIATELY NOTIFY THE ARCHITECT IN WRITING OF ANY DISCREPANCIES BEFORE PROCEEDING WITH THE WORK OR BE RESPONSIBLE FOR SAME.

CALL BEFORE YOU DIG:  
 WWW.CBYD.COM



CALL THREE WORKING DAYS PRIOR TO DIGGING  
 SAFETY PRECAUTIONS SHALL BE IMPLEMENTED BY CONTRACTOR(S) AT ALL TRENCHING IN ACCORDANCE WITH CURRENT OSHA STANDARDS.

COLOR CODE FOR UTILITY LOCATIONS


ELECTRIC - RED	SEWER
GAS/OIL - YELLOW	SURVEY
TEL/CANV - ORANGE	PROPOSED EXCAVATION - WHITE
WATER - BLUE	RECLAIMED WATER - PURPLE






ACCESS  
DRIVEMWAY  
PROJECT  
LOCATION

**KEY PLAN**  
SCALE: N.T.S.  
1  
A-1



**ELEVATION VIEW**  
SCALE: 1" = 20'-0" (11x17)  
1" = 10'-0" (24x36)




**SITE LEGEND**


- SITE PROPERTY LINE
- STREET OR ROAD
- CHAIN LINK FENCE
- OPAQUE WOODEN FENCE
- BOARD ON BOARD FENCE
- DECIDUOUS TREES/SHRUBS
- EVERGREEN TREES/SHRUBS
- TREE LINE
- UTILITY POLE
- (E) EXISTING
- (N) NEW
- (P) PROPOSED
- (F) FUTURE
- PROP. LTE ANTENNA
- PROP. UMTS/GSM ANTENNA
- EX. GSM ANTENNA
- EX. UMTS ANTENNA

**GENERAL SITE NOTES:**

1. SITE INFORMATION WAS OBTAINED FROM A FIELD INVESTIGATION PERFORMED BY ATLANTIS GROUP, INC. CONTRACTOR TO FIELD VERIFY DIMENSIONS AS NECESSARY BEFORE CONSTRUCTION.
2. THE PROPOSED DEVELOPMENT DOES NOT INCLUDE SIGNS OF ADVERTISING.
3. THE PROPOSED DEVELOPMENT IS UNMANNED AND THEREFORE DOES NOT REQUIRE A MEANS OF WATER SUPPLY OR SEWAGE DISPOSAL.
4. NO LANDSCAPING WORK IS PROPOSED IN CONJUNCTION WITH THIS DEVELOPMENT OTHER THAN THAT WHICH IS SHOWN.
5. THE PROPOSED DEVELOPMENT DOES NOT INCLUDE OUTDOOR STORAGE OR ANY SOLID WASTE RECEPTACLES.
6. UTILITIES SHOWN ON PLAN ARE TAKEN FROM OWNERS RECORDS AND FIELD LOCATION OF VISIBLE SURFACE FEATURES. THE EXISTENCE, EXTENT AND EXACT HORIZONTAL AND VERTICAL LOCATIONS OF UTILITIES HAS NOT BEEN VERIFIED. ANY CONTRACTORS PERFORMING WORK ON THIS SITE MUST CONTACT GAIL BEFORE YOU DIG THREE WORKING DAYS PRIOR TO COMMENCING WORK.
7. ALL OBSOLETE OR UNUSED FACILITIES SHALL BE REMOVED WITHIN 12 MONTHS OF CESSATION OF OPERATIONS.



**ELEVATION VIEW**  
SCALE: 1" = 20'-0" (11x17)  
1" = 10'-0" (24x36)



**Mobile**

**ATLANTIS GROUP**

1340 Centre Street, Suite 212  
Newton Center, MA 02459  
Office: 617-965-0789  
Fax: 617-213-5056

**SUBMITTALS**

DATE	DESCRIPTION	REVISION
02/17/18	Revised for permit	1
02/24/18	Final CD	0

DEPT.	DATE	APPRO.	REVISIONS
RF			
ZONING			
PERM.			
CONSTR.			
SITE AC.			

PROJECT NO: CT11334A  
DRAWN BY: FG  
CHECKED BY: SM

STATE OF CONNECTICUT  
HOSSEAN VAN ELD  
LICENSED ARCHITECT  
NO. ARJ. 11182

PROFESSIONAL SEAL

THIS DOCUMENT IS THE CREATION, DESIGN, PROPERTY AND COPYRIGHTED WORK OF T-MOBILE. ANY DUPLICATION OR USE WITHOUT EXPRESS WRITTEN CONSENT IS STRICTLY PROHIBITED.

SITE NUMBER  
CT11334A

SITE NAME  
STAMFORD-3/HOPE ST

SITE ADDRESS  
652 GLENBROOK ROAD  
STAMFORD, CT 06907


SHEET TITLE  
COMPOUND PLAN  
AND  
ELEVATION

SHEET NUMBER  
A-1


REFER TO STRUCTURAL ANALYSIS REPORT DOCUMENT ENTITLED, "STRUCTURAL ANALYSIS REPORT WATERBANK" PREPARED BY ATLANTIS GROUP, INC., "T-MOBILE SITE ID CT11334A", DATED FEBRUARY 23, 2015

**T-Mobile**  
**ATLANTIS GROUP**  
 1340 Centre Street, Suite 212  
 Newton Center, MA 02459  
 Office: 617-965-0789  
 Fax: 617-213-5056


**ATLANTIS GROUP**  
 35 GREEN ROAD SOUTH  
 BLOOMFIELD, CT 06002  
 OFFICE: (860) 692-7100  
 FAX: (860) 692-7139



EXISTING ANTENNA



COMMSCOPE ANTENNA DETAIL



RRUS 11 B12 DETAILS


DATE	DESCRIPTION	REVISION
02/11/15	ISSUED FOR REVIEW	A
02/24/15	FINAL CD	0

DEPT.	DATE	APP'D	REVISIONS
RF MGR			
ZONING			
GIS			
CONSTR			
SITE AC			


PROJECT NO: CT11334A  
 DRAWN BY: FG  
 CHECKED BY: SM

PROPOSED ANTENNA



ANTENNA PLAN  
 SCALE: N.T.S.

ANTENNA MOUNT DETAIL  
 SCALE: N.T.S.



THIS DOCUMENT IS THE CREATION, DESIGN, PROPERTY AND COPYRIGHTED WORK OF T-MOBILE. ANY DUPLICATION OR USE WITHOUT EXPRESS WRITTEN CONSENT IS STRICTLY PROHIBITED.

SITE NUMBER  
 CT11334A  
 SITE NAME  
 STAMFORD-3/HOPE ST  
 SITE ADDRESS  
 652 GLENBROOK ROAD  
 STAMFORD, CT 06907


SHEET TITLE  
 ANTENNA  
 PLAN AND  
 DETAILS

SHEET NUMBER  
 A-2

DATE	DESCRIPTION	REVISION
02/19/15	ISSUED FOR REVIEW	A
02/24/15	FINAL CD	0

DEPT.	DATE	APPROV.	REVISIONS
RF MGR. <td></td> <td></td> <td></td>			
ZONING			
OPS			
CONSR.			
SITE AC.			

PROJECT NO.: CT11334A  
 DRAWN BY: FG  
 CHECKED BY: SM




THIS DOCUMENT IS THE CREATION, DESIGN, PROPERTY AND COPYRIGHTED WORK OF T-MOBILE. ANY DUPLICATION OR USE WITHOUT EXPRESS WRITTEN CONSENT IS STRICTLY PROHIBITED.

SITE NUMBER  
 CT11334A  
 SITE NAME  
 STAMFORD-3/HOPE ST  
 SITE ADDRESS  
 652 GLENBROOK ROAD  
 STAMFORD, CT 06907

SHEET TITLE  
 GROUNDING AND  
 POWER ONE LINE  
 DIAGRAM

SHEET NUMBER  
**E-1**



- TRUNK FIBER NOTES:**
1. IN GENERAL THIS CABLE WILL HANDLE SIMILARLY TO 3/4" COAXIAL CABLE, AND SIMILAR INSTALLATION TECHNIQUES APPLY. ALL CABLES ARE INDIVIDUALLY SERIALIZED, BE SURE TO WRITE DOWN THE CABLE SERIAL NUMBER FOR FUTURE REFERENCE.
  2. THE TERMINATED FIBER ENDS (THE BROKEN OUT FIBERS PLUS CONNECTORS) HOWEVER ARE FRAGILE, AND THESE MUST BE PROTECTED DURING THE INSTALLATION PROCESS.
  3. LEAVE THE PROTECTIVE TUBE AND SOCK AROUND THE FIBER TAILS AND CONNECTORS IN PLACE DURING HOISTING AND SECURING THE CABLE. REMOVE THIS ONLY JUST PRIOR TO MAKING THE FINAL CONNECTIONS TO THE OVP BOX.
  4. DO NOT BEND THE FIBER ENDS (IN THE ORANGE FURCATION TUBES) TIGHTER THAN 3" (19MM) BEND RADIUS, ELSE THERE IS A RISK OF BREAKING THE GLASS FIBERS.
  5. BE SURE THAT THE LACE UP ENDS AND FIBER CONNECTORS ARE NOT DAMAGED BY ATTACHMENT OF A HOISTING GRIP OR DURING THE HOISTING PROCESS. ATTACH A HOISTING GRIP ON THE JACKETS CABLE NO LESS THAN 6 INCHES BELOW THE FIBER BREAKOUT POINT. IF A HOISTING GRIP IS NOT EASILY ATTACHED, USE A SIMPLE LINE ATTACHED BELOW THE FIBER BREAK-OUT POINT (I.E. AT THE CABLE OUTER JACKET). PREVENT THE FIBER TAILS (IN PROTECTIVE TUBE) AT THE CABLE END FROM UNDE MOVEMENT DURING HOISTING BY SECURING THE PROTECTIVE TUBE (WITH OUTER SOCK) TO THE HOISTING LINE.
  6. DURING HOISTING ENSURE THAT THERE IS A FREE PATH AND THAT THE CABLE, AND ESPECIALLY THE FIBER ENDS, WILL NOT BE SMASHED ON TOWER MEMBERS OR OTHER OBSTACLES.
  7. INSTALLATION TEMPERATURE RANGE IS -22°F TO 158°F (-30°C TO +70°C).
  8. MINIMUM CABLE BEND RADI ARE 22.2" (569MM) LOADED (WITH TENSION ON THE CABLE) AND 11.1" (280MM) UNLOADED.
  9. MAXIMUM CABLE TENSILE LOAD IS 3560 N (800 LB) SHORT TERM (DURING INSTALLATION) AND 1070 N (240 LB) LONG TERM.
  10. COMMSCOPE NON LACE UP GRIP RECOMMENDED FOR MONOPOLE INSTALLATIONS.
  11. MAXIMUM HANGER SPACING 3FT (0.9 M).

- HYBRID FIBER/POWER JUMPER NOTES:**
1. IN GENERAL THIS CABLE WILL HANDLE SIMILARLY TO A 3/4" COAXIAL CABLE.
  2. THE TERMINATED FIBER ENDS HOWEVER ARE FRAGILE AND MUST BE PROTECTED DURING INSTALLATION. LEAVE THE PACKAGING AROUND THE FIBER ENDS IN PLACE UNTIL READY TO CONNECT THE JUMPER BETWEEN OVP AND RRU OR BBU.
  3. DO NOT BEND THE FIBER BREAKOUT CABLE (BETWEEN THE MAIN CABLE AND THE FIBER CONNECTOR) TIGHTER THAN 3/4" (19MM) RADIUS, ELSE THERE IS A RISK OF BREAKING THE GLASS.
  4. ATTACH THE MAIN CABLE SECURELY TO THE STRUCTURE OR EQUIPMENT USING HANGERS AND/OR CABLE TIES TO PREVENT STRAIN ON CONNECTIONS FROM MOVEMENT IN WIND OR SNOW/ICE CONDITIONS.
  5. ENSURE THE LC FIBER CONNECTORS ARE SEALED FIRMLY IN PANEL IN OVP OR IN EQUIPMENT.
  6. INSTALLATION TEMPERATURE RANGE IS -22°F TO 158°F (-30°C TO 70°C).
  7. MINIMUM CABLE BEND RADI ARE 10.3 INCH (263MM) LOADED (WITH TENSION ON THE CABLE) AND 5.2 INCH (130MM) UNLOADED.
  8. MAXIMUM CABLE TENSILE LOAD IS 350 LB (1560N) SHORT TERM (DURING INSTALLATION) AND 105 LB (470N) LONG TERM.
  9. STANDARD LENGTHS AVAILABLE ARE 6 FEET, 15 FEET AND 20 FEET


**GROUNDING SCHEDULE**

- 1 (E) MGB (BUSBAR #1)
- 2 (E) #2AWG BARE TINNED SOLID COPPER CONDUCTOR BONDED TO GROUND RING (GROUND CABINETS PER MANU. SPECS)
- 3 (E) SECTOR GROUND BAR

**CONDUIT SCHEDULE**

- (E) POWER CONDUIT
- (E) 3#6+1#8G IN (P) 2" CONDUIT


- NOTES:**
- PROVIDE #2AWG GROUNDING CONDUCTOR, U.O.N.
  - DO NOT INSTALL GROUND KIT AT BEND, DIRECT GROUND WIRE DOWN TO ANTENNA BUSBAR.
  - PROVIDE GROUNDING ELECTRODES IN QUANTITY, TYPE AND SIZE AS INDICATED ON SITE GROUNDING PLAN.
  - ADD COAX GROUND KIT CONNECTION TO BUSBAR WHEN LENGTH OF COAX RUN (FROM EQUIPMENT TO ANTENNA) IS GREATER THAN 20'-0"
  - GROUND HCS BOX W/ #2AWG GROUNDING CONDUCTOR ATTACHED TO GOOD GROUND AS DIRECT AND SHORT AS POSSIBLE. USE GREEN STRANDED INSULATED CONDUCTOR TO CONNECT TO BUSBAR/GROUND HALO OR BARE TINNED SOLID COPPER CONDUCTOR TO CONNECT TO GROUND RING.



**GROUNDING DIAGRAM**  
 SCALE: N.T.S  
**E-1**

**702CU CONFIGURATION  
 COAX/FIBER PLUMBING DIAGRAM**  
 SCALE: N.T.S  
**E-1**






**BURNDY GROUNDING DETAILS**

SCALE: N.T.S.


1  
E-2



**BURNDY GROUNDING PRODUCTS**

SCALE: N.T.S.

2  
E-2



**CADWELD GROUNDING CONNECTION PRODUCTS**

SCALE: N.T.S.


3  
E-2

TERMINATION TYPES:  
A. MECHANICAL COMPRESSION LUG  
B. DOUBLE BARRELL COMPRESSION CONNECTOR  
C. EXOTHERMIC TERMINATION  
D. BEAM CLAMP


SOLID #2 TINNED COPPER	B OR C	B OR C	#6 GROUND LEAD	A, C, OR D	A, C, OR D	STRUCTURAL OR TOWER STEEL	C	BLDG SERVICE ENTR OR GRND RING	C
#6 GROUND LEAD	B OR C	B OR C	#2/0 STRANDED MAIN DOWN CONDUCTOR	A, C, OR D	A, C, OR D	MASTER GRND BAR	A, C, OR D	GROUND ROD	C
#2/0 STRANDED ELECTR. CONDUCTOR	A	A	MASTER GRND BAR	A, C, OR D	A, C, OR D	STRUCTURAL OR TOWER STEEL	A	GROUND RING	C
STRUCTURAL OR TOWER STEEL	A, C, OR D	A, C, OR D	GROUND RING	C	C				

**GROUNDING TERMINATION MARTIX**

7  
E-2



NOTES:  
1. OXIDE INHIBITING COMPOUND TO BE USED AT ALL LOCATIONS.




NOTES:  
1. ALL HARDWARE STAINLESS STEEL COAT ALL SURFACES WITH KOPR-SHIELD BEFORE MATING.  
2. FOR GROUND BOND TO STEEL ONLY; INSERT A TOOTH WASHER BETWEEN LUG AND STEEL, COAT ALL SURFACES WITH KOPR-SHIELD.  
3. ALL HOLES ARE COUNTERSUNK 1/8".

**TYPICAL GROUND BAR CONNECTIONS DETAIL**

SCALE: N.T.S.


4  
E-2



**GROUND BAR DETAIL**

SCALE: N.T.S.

5  
E-2



**GROUND BAR DETAIL**

SCALE: N.T.S.

6  
E-2

LUG NOTES:  
1. ALL HARDWARE IS 18-8 STAINLESS STEEL, INCLUDING LOCK WASHERS.  
2. ALL HARDWARE SHALL BE S.S. 3/8" Ø OR LARGER.  
3. FOR GROUND BOND TO STEEL ONLY; INSERT A DRAGON TOOTH WASHER BETWEEN LUG AND STEEL. COAT ALL SURFACES WITH ANTI-OXIDIZATION COMPOUND PRIOR TO MATING.

**T-Mobile**  
**T-MOBILE NORTHEAST, LLC**  
315 GLENVIEW ROAD SOUTH  
NEWTON CENTER, MA 02459  
OFFICE: (860) 693-2100  
FAX: (860) 693-2159

**ATLANTIS**  
**G R O U P**  
1340 Centre Street, Suite 212  
Newton Center, MA 02459  
Office: 617-965-0789  
Fax: 617-213-5056

SUBMITTALS

DATE	DESCRIPTION	REVISION
02/19/15	ISSUED FOR REVIEW	A
02/24/15	FINAL CD	0

DEPT.	DATE	APPROV	REVISIONS
BY: [ ]			
DATE:			
CHKD:			
DATE:			
BY: [ ]			

PROJECT NO.: CT11334A  
DRAWN BY: FG  
CHECKED BY: SM

STATE OF CONNECTICUT  
HOSEAN WARD  
NO. APR. 11, 1992  
LICENSED ARCHITECT  
PROFESSIONAL SEAL

THIS DOCUMENT IS THE CREATION, DESIGN, PROPERTY AND COPYRIGHTED WORK OF T-MOBILE. ANY DUPLICATION OR USE WITHOUT EXPRESS WRITTEN CONSENT IS STRICTLY PROHIBITED.

SITE NUMBER  
CT11334A  
SITE NAME  
STAMFORD-3/HOPE ST  
SITE ADDRESS  
652 GLENBROOK ROAD  
STAMFORD, CT 06907

SHEET TITLE  
GROUNDING DETAILS

SHEET NUMBER  
E-2

# **EXHIBIT B**

**STRUCTURAL ANALYSIS REPORT  
WATERTANK**



Prepared For:



**35 Griffin Road South  
Bloomfield, CT 06002**



**Site ID: CT11334A**

**Site Name: Stamford-3/Hope St  
652 Glenbrook Road  
Stamford, CT 06907**

February, 2015

Prepared By:

Atlantis Group, Inc.

1340 Centre Street, Suite 212

Newton, Massachusetts 02459

Phone: 617-965-0789, Fax: 617-213-5056



A handwritten signature in blue ink, appearing to read 'D. Alebu'.

02/25/2015

**CONTENTS**

1.0 – SUBJECT AND REFERENCES

2.0 – EXISTING AND PROPOSED CONFIGURATION

3.0 – CODES AND LOADING

4.0 – STANDARD CONDITIONS FOR ENGINEERING SERVICES ON EXISTING STRUCTURES

5.0 – ANALYSIS AND ASSUMPTIONS

6.0 – RESULTS AND CONCLUSION

APPENDIX

A – PHOTOS AND CALCULATIONS

## **1.0 SUBJECT AND REFERENCES**

The purpose of this analysis is to evaluate the structural capacity of the existing watertank located at the 652 Glenbrook Road, Stamford, CT 06907 for modifications to an existing wireless telecommunications equipment installation proposed by T-Mobile Northeast, L.L.C. (T-Mobile).

This report is based on the following:

- Construction Drawing for Site CT11334A prepared by TECTONIC Engineering & Surveying Consultants P.C., dated June 27, 2012.
- “Network Modernization RFDS v3.0” for Site ID CT11334A prepared by T-Mobile.
- “Structural Certification-(Modernization Project)” for Site ID CT11334A prepared by TECTONIC Engineering & Surveying Consultants P.C., dated May 10, 2012.
- “Structural Analysis report” for Site ID CT2141 (LTE) prepared by Hudson Design Group, LLC. , dated June 24, 2011.

## **1.1 STRUCTURE**

The existing watertank structure is at the top of a three-story a building. Currently, T-Mobile operates a wireless telecommunications facility at the site, located at the roof level of the building. Three sectors of typical wireless telecommunications panel-style antennas have been installed onto sector frame mounts in Alpha, Beta, and Gamma sectors attached to the watertank’s catwalk. A structural steel equipment platform, also located at roof level, supports typical wireless telecommunications equipment cabinets.

## **2.0 EXISTING AND PROPOSED CONFIGURATION**

### **Equipment Cabinets:**

T-Mobile is not proposing any changes to the existing cabinet configuration.

**Antennas:**

**Existing Configuration of T-MOBILE Appurtenances:**

Sector	Rad. Center (ft)	Antenna	TMA/RRU	Mount Type
Alpha	85	(1) Ericsson AIR21 B4A/B2P (1) Ericsson AIR21 B2A/B4P (1) EMS DR65-18-02DP(Dummy)	(1) dd B4 TMA	(1) Sector Frame
Beta	85	(1) Ericsson AIR21 B4A/B2P (1) Ericsson AIR21 B2A/B4P (1) EMS DR65-18-02DP(Dummy)	(1) dd B4 TMA	(1) Sector Frame
Gamma	85	(1) Ericsson AIR21 B4A/B2P (1) Ericsson AIR21 B2A/B4P (1) EMS DR65-18-02DP(Dummy)	(1) dd B4 TMA	(1) Sector Frame

**Proposed and Final Configuration of T-MOBILE Appurtenances:**

Sector	Rad. Center (ft)	Antenna	TMA/RRU	Mount Type
Alpha	85	(1) Ericsson AIR21 B4A/B2P (1) Ericsson AIR21 B2A/B4P (1) Commscope LNX-6515DS-VTM	(1) dd B4 TMA (1) S11 B12 RRU	(1) Sector Frame
Beta	85	(1) Ericsson AIR21 B4A/B2P (1) Ericsson AIR21 B2A/B4P (1) Commscope LNX-6515DS-VTM	(1) dd B4 TMA (1) S11 B12 RRU	(1) Sector Frame
Gamma	85	(1) Ericsson AIR21 B4A/B2P (1) Ericsson AIR21 B2A/B4P (1) Commscope LNX-6515DS-VTM	(1) dd B4 TMA (1) S11 B12 RRU	(1) Sector Frame

### **3.0 CODES AND LOADING**

The analysis is in accordance with the following codes and loading as adopted in Connecticut for Fairfield County:

- *2005 State Building Code with 2005 Addendum and 2013 Supplement*, International Code Council
- *Minimum Design Loads for Building and Other Structures ASCE/SEI 7-02*, American Society of Civil Engineers
- *Specifications for Structural Steel Buildings – Allowable Stress ANSI/AISC 335-89s1*, American National Standards Institute/American Institute for Steel Construction
- *Structural Standards for Steel Antenna Towers and Antenna Supporting Structures – TIA/EIA-222-F*
- Basic Wind Speed: 85 mph
- Flat Ground Snow Load: 30 psf

### **4.0 STANDARD CONDITIONS FOR ENGINEERING SERVICES ON EXISTING STRUCTURES**

The analysis is based on the information provided to Atlantis Group and is assumed to be current and correct. Unless otherwise noted, the structure and the foundation system are assumed to be in good condition, free of defects, and can achieve theoretical strength.

It is assumed that the structure has been maintained and shall be maintained during its service. The superstructure and the foundation system are assumed to be designed with proper engineering practice and fabricated, constructed, and erected in accordance with the design documents. Atlantis Group will accept no liability which may arise due to any existing deficiency in design, material, fabrication, erection, construction, etc., or lack of maintenance. Contractor should inspect the condition of the existing structure, mounts and connections and notify Atlantis Group for any discrepancies and deficiencies before proceeding with the construction.

The evaluation results presented in this report are only applicable for the previously mentioned existing and proposed additions and alterations. Any deviation of the proposed equipment and placement, etc., will require Atlantis Group to generate an additional structural evaluation.

### **5.0 ANALYSIS and ASSUMPTIONS**

The structure is considered to have adequate strength for the proposed loading if the existing structural members that will be used to support the proposed equipment are structurally adequate per the applicable Code criteria or that the additions or alterations to the existing structure do not increase the force in any structural element by more than 5%.

## 6.0 RESULTS and CONCLUSION

**Cabinets:** T-Mobile is not proposing any changes to the existing equipment cabinet configuration. Therefore, the original analysis is still valid and no further evaluation is required.

**Antenna Mounts** The proposed T-Mobile antenna upgrade includes addition of (3) Commscope LNX 6515DS-VTM antennas and (3) S 11 B12 RRUs. The additional antennas and RRUs will be installed on mount pipes attached to existing mount frame in a similar manner as the existing. The proposed equipment will replace three (3) EMS DR65-18-02DP dummy antennas.

Based on an analysis of the existing and proposed installation pursuant to the above-referenced Codes and standards, we have determined that the proposed changes will not adversely affect the existing facility. The overall increase in horizontal forces due to the installation of antennas is significantly less than 10% allowed by the code. Thus, no further analysis of the structure is necessary and it should be capable of supporting the proposed antennas.

Should you have any questions or need any clarifications about this report, please contact Atlantis Group at (617) 965-0789.

Sincerely,

**Atlantis Group**



02/25/2015

Dmitriy V. Albul, P.E.  
Connecticut Professional Engineer  
License Num. 26725



**APPENDIX A  
PHOTOS AND CALCULATIONS**



**Existing sector mount – Alpha sector**




**Existing sector mount – Beta sector**




**Existing sector mount – Gamma sector**



**Existing equipment on the Rooftop**




MOUNT FRONT VIEW



MOUNT SIDE VIEW

SITE ID: CT11334A  
(All dimensions scaled from photos)

**Horizontal Frame Member Capacity Calculations**



Proposed Antenna (#1)	LNx6515DS
Length	96.4 in
Width	11.9 in
Weight (ant1)	50.3 lbs
Flat or Round	flat
Ca=	1.4
CaAa=	11.4 ft <sup>2</sup>
F(ant1)=	277 lbs
F(ant1)/2=	139 lbs

Existing Antenna (#2)	Air 21B4A/B2P
Length	56.2 in
Width	12.1 in
Weight (ant2)	91.5 lbs
Flat or Round	flat
Ca=	1.4
CaAa=	6.6 ft <sup>2</sup>
F(ant2)=	160 lbs
F(ant2)/2=	80 lbs

Existing Antenna (#3)	Air 21B2A/B4P
Length	56.2 in
Width	12.1 in
Weight (ant3)	91.5 lbs
Flat or Round	flat
Ca=	1.4
CaAa=	6.6 ft <sup>2</sup>
F(ant3) =	160 lbs
F(ant3)/2=	80 lbs

Proposed RRU	S11 B12
Length	20 in
Width	17 in
Weigh(rru)	50.7 lbs
Flat or Round	flat
Ca=	1.4
CaAa=	3.3 ft <sup>2</sup>
F(rru)=	80 lbs
F(rru)/2=	40 lbs

Existing Frame	2" STD. PIPE
Length	14 ft
Width	2.375 in
Flat or Round	round
S=	0.53 in <sup>3</sup>
Fy=	35 ksi
Ca=	1.2
CaAa=	3.3 ft <sup>2</sup>
F(Frame)=	81 lbs

Height above ground Z=	85 ft
Wind speed V=	85 mph
qz=	24.24 PSF
Gh=	1.0

L1=	2 ft
L2=	2.5 ft
L3=	2.5 ft
L4=	2 ft
L5=	2 ft

Reactions	
Ra=	91 lbs
Rb=	228 lbs
Moments	
M max=	307.2 lbs*ft
M resist=	924 lbs*ft
Percent capacity	33.2 %
<b>Member is adequate</b>	

$$q_z = 0.00256 \times K_z \times V^2 \text{ (psf)}$$

TIA/EIA 222-F Sec 2.3.3

Where:

$$K_z = \left(\frac{z}{33}\right)^{\frac{2}{7}}$$

$z$  – Height above average ground level to midpoint of the section (ft)

$V$  – Basic wind speed for the structure location (mph)

$$F_a = q_z \times G_h \times C_a \times A_a \quad \text{(lbs)}$$

TIA/EIA 222-F Sec. 2.3.2

Where:

$$G_h = 1.0$$

$A_a$  – Projected area

$C_a$  – Force coefficient

$$M_{\text{resist}} = 0.6 \times F_y \times S \quad \text{(lbs*ft)}$$

Where:

$F_y$  – Yield strength (psi)

$S$  – Section modulus (in.<sup>3</sup>)

$$M_{\text{max}} = \sum F_a * L_i \text{ (lbs*ft)}$$

Where:

$L_i$  – Moment arm (ft)

All calculations are in accordance with TIA-EIA-222-F, based on the information provided by client.

# Product Specifications

COMMSCOPE®



## LNX-6515DS-VTM

Andrew® Antenna, 698–896 MHz, 65° horizontal beamwidth, RET compatible

- Excellent choice to maximize both coverage and capacity in suburban and rural applications
- Fully compatible with Andrew remote electrical tilt system for greater OpEx savings
- Exceptional horizontal pattern roll-off and strong front-to-back ratio
- Extended bandwidth allows one antenna to serve multiple frequency allocations
- Great solution to maximize network coverage and capacity
- The RF connectors are designed for IP67 rating and the radome for IP56 rating

### Electrical Specifications

Frequency Band, MHz	698–806	806–896
Gain, dBi	16.7	17.6
Beamwidth, Horizontal, degrees	65	65
Beamwidth, Horizontal Tolerance, degrees	±2	±2
Beamwidth, Vertical, degrees	9.6	8.6
Beam Tilt, degrees	0–8	0–8
USLS, typical, dB	17	17
Front-to-Back Ratio at 180°, dB	32	27
CPR at Boresight, dB	24	24
CPR at Sector, dB	10	10
Isolation, dB	30	30
VSWR   Return Loss, dB	1.4   15.6	1.4   15.6
PIM, 3rd Order, 2 x 20 W, dBc	-150	-150
Input Power per Port, maximum, watts	400	400
Polarization	±45°	±45°
Impedance	50 ohm	50 ohm

### General Specifications

Antenna Brand	Andrew®
Antenna Type	DualPol®
Band	Single band
Brand	DualPol®   Teletilt®
Operating Frequency Band	698 – 896 MHz


### Mechanical Specifications

Color	Light gray
Connector Interface	7-16 DIN Female
Connector Location	Bottom
Connector Quantity, total	2
Lightning Protection	dc Ground
Radiator Material	Aluminum
Radome Material	Fiberglass, UV resistant
Wind Loading, maximum	878.0 N @ 150 km/h 197.4 lbf @ 150 km/h
Wind Speed, maximum	241.0 km/h   149.8 mph


LNX-6515DS-VTM

### Dimensions


Depth	181.0 mm   7.1 in
Length	2449.0 mm   96.4 in
Width	301.0 mm   11.9 in
Net Weight	22.8 kg   50.3 lb



# Remote Radio Unit – RRUS11 B12



\* RRUS 11 B12 is exactly the same size as RRUS 11 B2 or B4 that T-Mobile is currently using.



Dimensions with Solar Shield and Handle	
Height	500 mm
Width	431 mm
Depth	182 mm
<b>Weight</b>	
RRUS 11	23 kg
<b>Color</b>	
Gray	NCS S2502-R

Unit	Output Power
RRUS 11 B1, B4	2x30 W
	2x40 W
RRUS 11 B2	2x30 W
	2x40 W
RRUS 11 B12	2x30 W

# **EXHIBIT C**



RADIO FREQUENCY EMISSIONS ANALYSIS REPORT  
EVALUATION OF HUMAN EXPOSURE POTENTIAL  
TO NON-IONIZING EMISSIONS

T-Mobile Existing Facility

Site ID: CT11334A

Stamford 3 / Hope St.  
652 Glenbrook Road  
Stamford, CT 06907

**March 10, 2015**

**EBI Project Number: 6215001359**

Site Compliance Summary	
Compliance Status:	<b>COMPLIANT</b>
Site total MPE% of FCC general public allowable limit:	<b>87.62 %</b>

March 10, 2015

T-Mobile USA  
Attn: Jason Overbey, RF Manager  
35 Griffin Road South  
Bloomfield, CT 06002

Emissions Analysis for Site: **CT11334A – Stamford 3 / Hope St.**

EBI Consulting was directed to analyze the proposed T-Mobile facility located at **652 Glenbrook Road, Stamford, CT**, for the purpose of determining whether the emissions from the Proposed T-Mobile Antenna Installation located on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter ( $\mu\text{W}/\text{cm}^2$ ). The number of  $\mu\text{W}/\text{cm}^2$  calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits, therefore it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) – (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general public may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general public would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

Public exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter ( $\mu\text{W}/\text{cm}^2$ ). The general population exposure limit for the 700 MHz Band is  $467 \mu\text{W}/\text{cm}^2$ , and the general population exposure limit for the PCS and AWS bands is  $1000 \mu\text{W}/\text{cm}^2$ . Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.

Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure. Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

## **CALCULATIONS**

Calculations were done for the proposed T-Mobile Wireless antenna facility located at **652 Glenbrook Road, Stamford, CT**, using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. Since T-Mobile is proposing highly focused directional panel antennas, which project most of the emitted energy out toward the horizon, all calculations were performed assuming a lobe representing the maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was focused at the base of the tower. For this report the sample point is the top of a 6 foot person standing at the base of the tower.

For all calculations, all equipment was calculated using the following assumptions:

- 1) 2 GSM channels (PCS Band - 1900 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 30 Watts per Channel
- 2) 2 UMTS channels (AWS Band – 2100 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 30 Watts per Channel.
- 3) 2 LTE channels (AWS Band – 2100 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 60 Watts per Channel.
- 4) 1 LTE channel (700 MHz Band) was considered for each sector of the proposed installation. This channel has a transmit power of 30 Watts.
- 5) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 - Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.

- 6) For the following calculations the sample point was the top of a six foot person standing at the base of the tower. The maximum gain of the antenna per the antenna manufactures supplied specifications minus 10 dB was used in this direction. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 7) The antennas used in this modeling are the **Ericsson AIR21 (B4A/B2P & B2A/B4P)** for 1900 MHz (PCS) and 2100 MHz (AWS) channels and the **Commscope LNX-6515DS-VTM** for 700 MHz channels. This is based on feedback from the carrier with regards to anticipated antenna selection. The **Ericsson AIR21 (B4A/B2P & B2A/B4P)** have a maximum gain of **15.9 dBd** at its main lobe. The **Commscope LNX-6515DS-VTM** has a maximum gain of **14.6 dBd** at its main lobe. The maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was used for all calculations. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 8) The antenna mounting height centerline of the proposed antennas is **85 feet** above ground level (AGL).
- 9) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.

All calculations were done with respect to uncontrolled / general public threshold limits.

**T-Mobile Site Inventory and Power Data**

Sector:	A	Sector:	B	Sector:	C
Antenna #:	1	Antenna #:	1	Antenna #:	1
Make / Model:	Ericsson AIR21 B4A/B2P	Make / Model:	Ericsson AIR21 B4A/B2P	Make / Model:	Ericsson AIR21 B4A/B2P
Gain:	15.9 dBd	Gain:	15.9 dBd	Gain:	15.9 dBd
Height (AGL):	85	Height (AGL):	85	Height (AGL):	85
Frequency Bands	1900 MHz(PCS) / 2100 MHz (AWS)	Frequency Bands	1900 MHz(PCS) / 2100 MHz (AWS)	Frequency Bands	1900 MHz(PCS) / 2100 MHz (AWS)
Channel Count	2	Channel Count	2	# PCS Channels:	2
Total TX Power:	120	Total TX Power:	120	# AWS Channels:	120
ERP (W):	4,668.54	ERP (W):	4,668.54	ERP (W):	4,668.54
Antenna A1 MPE%	2.69	Antenna B1 MPE%	2.69	Antenna C1 MPE%	2.69
Antenna #:	2	Antenna #:	2	Antenna #:	2
Make / Model:	Ericsson AIR21 B2A/B4P	Make / Model:	Ericsson AIR21 B2A/B4P	Make / Model:	Ericsson AIR21 B2A/B4P
Gain:	15.9 dBd	Gain:	15.9 dBd	Gain:	15.9 dBd
Height (AGL):	85	Height (AGL):	85	Height (AGL):	85
Frequency Bands	1900 MHz(PCS) / 2100 MHz (AWS)	Frequency Bands	1900 MHz(PCS) / 2100 MHz (AWS)	Frequency Bands	1900 MHz(PCS) / 2100 MHz (AWS)
Channel Count	4	Channel Count	4	Channel Count	4
Total TX Power:	120	Total TX Power:	120	Total TX Power:	120
ERP (W):	4,668.54	ERP (W):	4,668.54	ERP (W):	4,668.54
Antenna A2 MPE%	2.69	Antenna B2 MPE%	2.69	Antenna C2 MPE%	2.69
Antenna #:	3	Antenna #:	3	Antenna #:	3
Make / Model:	Commscope LNX-6515DS-VTM	Make / Model:	Commscope LNX-6515DS-VTM	Make / Model:	Commscope LNX-6515DS-VTM
Gain:	14.6 dBd	Gain:	14.6 dBd	Gain:	14.6 dBd
Height (AGL):	85	Height (AGL):	85	Height (AGL):	85
Frequency Bands	700 Mhz	Frequency Bands	700 Mhz	Frequency Bands	700 Mhz
Channel Count	1	Channel Count	1	Channel Count	1
Total TX Power:	30	Total TX Power:	30	Total TX Power:	30
ERP (W):	865.21	ERP (W):	865.21	ERP (W):	865.21
Antenna A3 MPE%	1.07	Antenna B3 MPE%	1.07	Antenna C3 MPE%	1.07

Site Composite MPE%	
Carrier	MPE%
T-Mobile	19.34
MetroPCS	21.34 %
Clearwire	2.13 %
Nextel	6.63 %
AT&T	38.18 %
<b>Site Total MPE %:</b>	<b>87.62 %</b>

T-Mobile Sector 1 Total:	6.45 %
T-Mobile Sector 2 Total:	6.45 %
T-Mobile Sector 3 Total:	6.45 %
<b>Site Total:</b>	<b>87.62 %</b>

## Summary

All calculations performed for this analysis yielded results that were **within** the allowable limits for general public exposure to RF Emissions.

The anticipated maximum composite contributions from the T-Mobile facility as well as the site composite emissions value with regards to compliance with FCC's allowable limits for general public exposure to RF Emissions are shown here:

T-Mobile Sector	Power Density Value (%)
Sector 1:	6.45 %
Sector 2:	6.45 %
Sector 3 :	6.45 %
T-Mobile Total:	19.34 %
Site Total:	87.62 %
Site Compliance Status:	<b>COMPLIANT</b>

The anticipated composite MPE value for this site assuming all carriers present is **87.62%** of the allowable FCC established general public limit sampled at the ground level. This is based upon values listed in the Connecticut Siting Council database for existing carrier emissions.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.



Scott Heffernan  
RF Engineering Director

### EBI Consulting

21 B Street  
Burlington, MA 01803