



Crown Castle
3530 Toringdon Way, Suite 300
Charlotte, NC 28277

August 4, 2014

Melanie A. Bachman
Connecticut Siting Council
10 Franklin Square
New Britain, CT 06051

RE: Sprint PCS-Exempt Modification - Crown Site BU: 806953
Sprint PCS Site ID: CT03XC344
Located at: 69 Guinea Road, Stamford, CT 06903

Dear Ms. Bachman:

This letter and exhibits are submitted on behalf of Sprint PCS (Sprint). Sprint is making modifications to certain existing sites in its Connecticut system in order to implement their 2.5GHz LTE technology. Please accept this letter and exhibits as notification, pursuant to § 16-50j-73 of the Regulations of Connecticut State Agencies (“R.C.S.A.”), of construction that constitutes an exempt modification pursuant to R.C.S.A. § 16-50j-72(b)(2). In compliance with R.C.S.A. § 16-50j-73, a copy of this letter is being sent to The Honorable David Martin, Mayor for City of Stamford, and Girl Scouts of Connecticut, Inc., Property Owner.

Sprint plans to modify the existing wireless communications facility owned by Crown Castle and located at **69 Guinea Road, Stamford, CT 06903**. Attached are a compound plan and elevation depicting the planned changes (Exhibit-1), and documentation of the structural sufficiency of the structure to accommodate the revised antenna configuration (Exhibit-2). Also included is a power density table report reflecting the modification to Sprint’s operations at the site (Exhibit-3).

The changes to the facility do not constitute a modification as defined in Connecticut General Statutes (“C.G.S.”) § 16-50i(d) because the general physical characteristics of the facility will not be significantly changed. Rather, the planned changes to the facility fall squarely within those activities explicitly provided for in the R.C.S.A. § 16-50j-72(b)(2).

1. The proposed modifications will not result in an increase in the height of the existing tower. Sprint’s additional antennas will be located at the same elevation on the existing tower.
2. There will be no proposed modifications to the ground and no extension of boundaries.
3. The proposed modifications will not increase noise levels at the facility by six decibels or more.

Melanie A. Bachman

August 4, 2014

Page 2

4. A Structural Modification Report confirming that the tower and foundation can support Sprint's proposed modifications is included as Exhibit-2.
5. The operation of the additional antennas will not increase radio frequency (RF) emissions at the facility to a level at or above the Federal Communications Commission (FCC) adopted safety standard. A cumulative General Power Density table report for Sprint's modified facility is included as Exhibit-3.

For the foregoing reasons, Sprint respectfully submits the proposed modifications to the above-reference telecommunications facility constitutes an exempt modification under R.C.S.A. § 16-50j-72(b)(2). Please send approval/rejection letter to Attn: Donna Neal.

Sincerely,



Jeff Barbadora
Real Estate Specialist

Enclosures

Tab 1: Exhibit-1: Compound plan and elevation depicting the planned changes


Tab 2: Exhibit-2: Structural Modification Report

Tab 3: Exhibit-3: General Power Density Table Report (RF Emissions Analysis Report)

cc: Mayor David Martin
City of Stamford
888 Washington Boulevard
Stamford, CT 06901

Girl Scouts of Connecticut, Inc.
Attn: Mr. George Steiner
340 Washington Street
Hartford, CT 06106

Sprint



CROWN CASTLE

PROJECT: 2.5 EQUIPMENT DEPLOYMENT
 SITE NAME: MERRIT 4 - ROXBURY (CROWN)
 SITE CASCADE: CT03XC344
 SITE NUMBER: 806953
 SITE ADDRESS: 69 GUINEA ROAD
 STAMFORD, CT 06903
 SITE TYPE: MONOPOLE TOWER
 MARKET: SOUTHERN CONNECTICUT

PLANS PREPARED FOR:

Sprint
 6580 Sprint Parkway
 Overland Park, Kansas 66251

PLANS PREPARED BY:

INFINIGY Design. Build. Deliver.
 1033 Watervliet Shaker Rd
 Albany, NY 12205
 Office # (518) 690-0790
 Fax # (518) 690-0793
 JOB NUMBER 353-000

MLA PARTNER:

CROWN CASTLE

ENGINEERING LICENSE:

DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR CONSTRUCTION	02/10/14	MAP	0

SITE NAME:

MERRIT 4 - ROXBURY (CROWN)

SITE CASCADE:

CT03XC344

SITE ADDRESS:

69 GUINEA ROAD
 STAMFORD, CT 06903

SHEET DESCRIPTION:

TITLE SHEET & PROJECT DATA

SHEET NUMBER:

T-1

SITE INFORMATION

TOWER OWNER:
 CROWN ATLANTIC COMPANY LLC
 2000 CORPORATE DRIVE
 CANNONSBURG, PA 15317
 (704) 405-6555

LATITUDE (NAD83):
 41° 6' 6.48" N
 41.101800°

LONGITUDE (NAD83):
 73° 35' 39.84" W
 -73.594400°

COUNTY:
 FAIRFIELD

ZONING JURISDICTION:
 CONNECTICUT SITING COUNCIL

ZONING DISTRICT:
 TBD


POWER COMPANY:
 CONNECTICUT LIGHT & POWER
 (800) 286-2000

AAV PROVIDER:
 AT&T
 (800) 246-8464


SPRINT CM:
 GARY WOOD
 GARY.WOOD@SPRINT.COM

CROWN CASTLE CM:
 HARRY ATHAN
 (518) 380-0041
 HTAMANAGEMENT@NYCAP.RR.COM

AREA MAP



LOCATION MAP



PROJECT DESCRIPTION

SPRINT PROPOSES TO MODIFY AN EXISTING UNMANNED TELECOMMUNICATIONS FACILITY.

- INSTALL 2.5 EQUIPMENT IN EXISTING N.V. MMBS
- INSTALL (3) PANEL ANTENNAS
- INSTALL (3) RRU'S TO TOWER
- INSTALL (27) JUMPER CABLES
- INSTALL (1) FIBER CABLE
- INSTALL (4) BATTERIES IN EXISTING BBU CABINET

THESE PLANS HAVE BEEN DEVELOPED FOR THE MODIFICATION OF AN EXISTING UNMANNED TELECOMMUNICATIONS FACILITY OWNED OR LEASED BY SPRINT IN ACCORDANCE WITH THE SCOPE OF WORK PROVIDED BY SPRINT. INFINIGY HAS INCORPORATED THIS SCOPE OF WORK IN THE PLANS. THESE PLANS ARE NOT FOR CONSTRUCTION UNLESS ACCOMPANIED BY A PASSING STRUCTURAL STABILITY ANALYSIS PREPARED BY A LICENSED STRUCTURAL ENGINEER. STRUCTURAL ANALYSIS MUST INCLUDE BOTH TOWER AND MOUNT.

APPLICABLE CODES

ALL WORK SHALL BE PERFORMED AND MATERIALS INSTALL IN ACCORDANCE WITH THE CURRENT EDITIONS OF THE FOLLOWING CODES AS ADOPTED BY THE LOCAL GOVERNING AUTHORITIES. NOTHING IN THESE PLANS IS TO BE CONSTRUED TO PERMIT WORK NOT CONFORMING TO THESE CODES.

- INTERNATIONAL BUILDING CODE (2012 IBC)
- TIA-EIA-222-F OR LATEST EDITION
- NFPA 780 - LIGHTNING PROTECTION CODE
- 2011 NATIONAL ELECTRIC CODE OR LATEST EDITION
- ANY OTHER NATIONAL OR LOCAL APPLICABLE CODES, MOST RECENT EDITIONS
- CT BUILDING CODE
- LOCAL BUILDING CODE
- CITY/COUNTY ORDINANCES

DRAWING INDEX

SHEET NO:	SHEET TITLE	REV
T-1	TITLE SHEET & PROJECT DATA	0
SP-1	SPRINT SPECIFICATIONS	0
SP-2	SPRINT SPECIFICATIONS	0
SP-3	SPRINT SPECIFICATIONS	0
A-1	SITE PLAN	0
A-2	TOWER ELEVATION & CABLE PLAN	0
A-3	ANTENNA LAYOUT & MOUNTING DETAILS	0
A-4	COLOR CODING & NOTES	0
A-5	EQUIPMENT & MOUNTING DETAILS	0
A-6	CIVIL DETAILS	0
A-7	PLUMBING DIAGRAM	0
E-1	ELECTRICAL & GROUNDING PLAN	0
E-2	ELECTRICAL & GROUNDING DETAILS	0



APPROVED
 By Jeff Barbadora at 2:10 pm, Feb 27, 2014

THESE OUTLINE SPECIFICATIONS IN CONJUNCTION WITH THE SPRINT STANDARD CONSTRUCTION SPECIFICATIONS, INCLUDING CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

SECTION 01 100 – SCOPE OF WORK

PART 1 – GENERAL

- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE SPRINT CONSTRUCTION STANDARDS FOR WIRELESS SITES, CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
 - A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
 - B. SPRINT 'STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES' ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HERewith.
- 1.3 PRECEDENCE: SHOULD CONFLICTS OCCUR BETWEEN THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES INCLUDING THE STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES AND THE CONSTRUCTION DRAWINGS, INFORMATION ON THE CONSTRUCTION DRAWINGS SHALL TAKE PRECEDENCE. NOTIFY SPRINT CONSTRUCTION MANAGER IF THIS OCCURS.
- 1.4 NATIONALLY RECOGNIZED CODES AND STANDARDS:
 - A. THE WORK SHALL COMPLY WITH APPLICABLE NATIONAL AND LOCAL CODES AND STANDARDS, LATEST EDITION, AND PORTIONS THEREOF, INCLUDED BUT NOT LIMITED TO THE FOLLOWING:
 - 1. GR-63-CORE NEBS REQUIREMENTS: PHYSICAL PROTECTION
 - 5. GR-78-CORE GENERIC REQUIREMENTS FOR THE PHYSICAL DESIGN AND MANUFACTURE OF TELECOMMUNICATIONS EQUIPMENT.
 - 3. GR-1089 CORE, ELECTROMAGNETIC COMPATIBILITY AND ELECTRICAL SAFETY -GENERIC CRITERIA FOR NETWORK TELECOMMUNICATIONS EQUIPMENT.
 - 4. NATIONAL FIRE PROTECTION ASSOCIATION CODES AND STANDARDS (NFPA) INCLUDING NFPA 70 (NATIONAL ELECTRICAL CODE - "NEC") AND NFPA 101 (LIFE SAFETY CODE).
 - 5. AMERICAN SOCIETY FOR TESTING OF MATERIALS (ASTM)
 - 6. INSTITUTE OF ELECTRONIC AND ELECTRICAL ENGINEERS (IEEE)
 - 7. AMERICAN CONCRETE INSTITUTE (ACI)
 - 8. AMERICAN WIRE PRODUCERS ASSOCIATION (AWPA)
 - 9. CONCRETE REINFORCING STEEL INSTITUTE (CRSI)
 - 10. AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)
 - 11. PORTLAND CEMENT ASSOCIATION (PCA)
 - 12. NATIONAL CONCRETE MASONRY ASSOCIATION (NCMA)
 - 13. BRICK INDUSTRY ASSOCIATION (BIA)
 - 14. AMERICAN WELDING SOCIETY (AWS)
 - 15. NATIONAL ROOFING CONTRACTORS ASSOCIATION (NRCA)
 - 16. SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)
 - 17. DOOR AND HARDWARE INSTITUTE (DHI)
 - 18. OCCUPATIONAL SAFETY AND HEALTH ACT (OSHA)
 - 19. APPLICABLE BUILDING CODES INCLUDING UNIFORM BUILDING CODE, SOUTHERN BUILDING CODE, BOCA, AND THE INTERNATIONAL BUILDING CODE.
- 1.5 DEFINITIONS:
 - A. WORK: THE SUM OF TASKS AND RESPONSIBILITIES IDENTIFIED IN THE CONTRACT DOCUMENTS.
 - B. COMPANY: SPRINT CORPORATION
 - C. ENGINEER: SYNONYMOUS WITH ARCHITECT & ENGINEER AND "A&E". THE DESIGN PROFESSIONAL HAVING PROFESSIONAL RESPONSIBILITY FOR DESIGN OF THE PROJECT.
 - D. CONTRACTOR: CONSTRUCTION CONTRACTOR; CONSTRUCTION VENDOR; INDIVIDUAL OR ENTITY WHO AFTER EXECUTION OF A CONTRACT IS BOUND TO ACCOMPLISH THE WORK.
 - E. THIRD PARTY VENDOR OR AGENCY: A VENDOR OR AGENCY ENGAGED SEPARATELY BY THE COMPANY, A&E, OR CONTRACTOR TO PROVIDE MATERIALS OR TO ACCOMPLISH SPECIFIC TASKS RELATED TO BUT NOT INCLUDED IN THE WORK.
 - F. OFCI: OWNER FURNISHED, CONTRACTOR INSTALLED EQUIPMENT.
 - G. CONSTRUCTION MANAGER – ALL PROJECTS RELATED COMMUNICATION TO FLOW THROUGH SPRINT REPRESENTATIVE IN CHARGE OF PROJECT...

- 1.6 SITE FAMILIARITY: CONTRACTOR SHALL BE RESPONSIBLE FOR FAMILIARIZING HIMSELF WITH ALL CONTRACT DOCUMENTS, FIELD CONDITIONS AND DIMENSIONS PRIOR TO PROCEEDING WITH CONSTRUCTION. ANY DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE SPRINT CONSTRUCTION MANAGER PRIOR TO THE COMMENCEMENT OF WORK. NO COMPENSATION WILL BE AWARDED BASED ON CLAIM OF LACK OF KNOWLEDGE OR FIELD CONDITIONS.
 - 1.7 POINT OF CONTACT: COMMUNICATION BETWEEN SPRINT AND THE CONTRACTOR SHALL FLOW THROUGH THE SINGLE SPRINT CONSTRUCTION MANAGER APPOINTED TO MANAGE THE PROJECT FOR SPRINT.
 - 1.8 ON-SITE SUPERVISION: THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK AND SHALL BE RESPONSIBLE FOR CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES IN ACCORDANCE WITH THE CONTRACT DOCUMENTS. THE CONTRACTOR SHALL EMPLOY A COMPETENT SUPERINTENDENT WHO SHALL BE IN ATTENDANCE AT THE SITE AT ALL TIMES DURING PERFORMANCE OF THE WORK.
 - 1.9 DRAWINGS, SPECIFICATIONS AND DETAILS REQUIRED AT JOBSITE: THE CONSTRUCTION CONTRACTOR SHALL MAINTAIN A FULL SET OF THE CONSTRUCTION DRAWINGS, STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES AND THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES AT THE JOBSITE FROM MOBILIZATION THROUGH CONSTRUCTION COMPLETION.
 - A. THE JOBSITE DRAWINGS, SPECIFICATIONS AND DETAILS SHALL BE CLEARLY MARKED DAILY IN RED PENCIL WITH ANY CHANGES IN CONSTRUCTION OVER WHAT IS DEPICTED IN THE DOCUMENTS. AT CONSTRUCTION COMPLETION, THIS JOBSITE MARKUP SET SHALL BE DELIVERED TO THE COMPANY OR COMPANY'S DESIGNATED REPRESENTATIVE TO BE FORWARDED TO THE COMPANY'S A&E VENDOR FOR PRODUCTION OF "AS-BUILT" DRAWINGS.
 - B. DETAILS ARE INTENDED TO SHOW DESIGN INTENT. MODIFICATIONS MAY BE REQUIRED TO SUIT JOB DIMENSIONS OR CONDITIONS, AND SUCH MODIFICATIONS SHALL BE INCLUDED AS PART OF THE WORK. CONTRACTOR SHALL NOTIFY SPRINT CONSTRUCTION MANAGER OF ANY VARIATIONS PRIOR TO PROCEEDING WITH THE WORK.
 - C. DIMENSIONS SHOWN ARE TO FINISH SURFACES UNLESS NOTED OTHERWISE. SPACING BETWEEN EQUIPMENT IS THE REQUIRED CLEARANCE. SHOULD THERE BE ANY QUESTIONS REGARDING THE CONTRACT DOCUMENTS, EXISTING CONDITIONS AND/OR DESIGN INTENT, THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING A CLARIFICATION FROM THE SPRINT CONSTRUCTION MANAGER PRIOR TO PROCEEDING WITH THE WORK.
 - 1.10 USE OF JOB SITE: THE CONTRACTOR SHALL CONFINE ALL CONSTRUCTION AND RELATED OPERATIONS INCLUDING STAGING AND STORAGE OF MATERIALS AND EQUIPMENT, PARKING, TEMPORARY FACILITIES, AND WASTE STORAGE TO THE LEASE PARCEL UNLESS OTHERWISE PERMITTED BY THE CONTRACT DOCUMENTS.
 - 1.11 UTILITIES SERVICES: WHERE NECESSARY TO CUT EXISTING PIPES, ELECTRICAL WIRES, CONDUITS, CABLES, ETC., OF UTILITY SERVICES, OR OF FIRE PROTECTION OR COMMUNICATIONS SYSTEMS, THEY SHALL BE CUT AND CAPPED AT SUITABLE PLACES OR WHERE SHOWN. ALL SUCH ACTIONS SHALL BE COORDINATED WITH THE UTILITY COMPANY INVOLVED:
 - 1.12 PERMITS / FEES: WHEN REQUIRED THAT A PERMIT OR CONNECTION FEE BE PAID TO A PUBLIC UTILITY PROVIDER FOR NEW SERVICE TO THE CONSTRUCTION PROJECT, PAYMENT OF SUCH FEE SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.
 - 1.13 CONTRACTOR SHALL TAKE ALL MEASURES AND PROVIDE ALL MATERIAL NECESSARY FOR PROTECTING EXISTING EQUIPMENT AND PROPERTY.
 - 1.14 METHODS OF PROCEDURE (MOPS) FOR CONSTRUCTION: CONTRACTOR SHALL PERFORM WORK AS DESCRIBED IN THE FOLLOWING INSTALLATION AND COMMISSIONING MOPS.
- NOTE: IN SHORT-FORM SPECIFICATIONS ON THE DRAWINGS, A/E TO INSERT LIST OF APPLICABLE MOPS INCLUDING EN-2012-001, EN-2013-002, EL-0568, AND TS-0193
- 1.15 USE OF ELECTRONIC PROJECT MANAGEMENT SYSTEMS:

PART 2 – PRODUCTS (NOT USED)

PART 3 – EXECUTION

- 3.1 TEMPORARY UTILITIES AND FACILITIES: THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL TEMPORARY UTILITIES AND FACILITIES NECESSARY EXCEPT AS OTHERWISE INDICATED IN THE CONSTRUCTION DOCUMENTS. TEMPORARY UTILITIES AND FACILITIES INCLUDE POTABLE WATER, HEAT, HVAC, ELECTRICITY, SANITARY FACILITIES, WASTE DISPOSAL FACILITIES, AND TELEPHONE/COMMUNICATION SERVICES. PROVIDE TEMPORARY UTILITIES AND FACILITIES IN ACCORDANCE WITH OSHA AND THE AUTHORITY HAVING JURISDICTION. CONTRACTOR MAY UTILIZE THE COMPANY ELECTRICAL SERVICE IN THE COMPLETION OF THE WORK WHEN IT BECOMES AVAILABLE. USE OF THE LESSORS OR SITE OWNER'S UTILITIES OR FACILITIES IS EXPRESSLY FORBIDDEN EXCEPT AS OTHERWISE ALLOWED IN THE CONTRACT DOCUMENTS.
- 3.2 ACCESS TO WORK: THE CONTRACTOR SHALL PROVIDE ACCESS TO THE JOB SITE FOR AUTHORIZED COMPANY PERSONNEL AND AUTHORIZED REPRESENTATIVES OF THE ARCHITECT/ENGINEER DURING ALL PHASES OF THE WORK.
- 3.3 TESTING: REQUIREMENTS FOR TESTING BY THIS CONTRACTOR SHALL BE AS INDICATED HERewith, ON THE CONSTRUCTION DRAWINGS, AND IN THE INDIVIDUAL SECTIONS OF THESE SPECIFICATIONS. SHOULD COMPANY CHOOSE TO ENGAGE ANY THIRD-PARTY TO CONDUCT ADDITIONAL TESTING, THE CONTRACTOR SHALL COOPERATE WITH AND PROVIDE A WORK AREA FOR COMPANY'S TEST AGENCY.
- 3.4 DIMENSIONS: VERIFY DIMENSIONS INDICATED ON DRAWINGS WITH FIELD DIMENSIONS BEFORE FABRICATION OR ORDERING OF MATERIALS. DO NOT SCALE DRAWINGS.

3.5 EXISTING CONDITIONS: NOTIFY THE SPRINT CONSTRUCTION MANAGER OF EXISTING CONDITIONS DIFFERING FROM THOSE INDICATED ON THE DRAWINGS. DO NOT REMOVE OR ALTER STRUCTURAL COMPONENTS WITHOUT PRIOR WRITTEN APPROVAL FROM THE ARCHITECT AND ENGINEER.

SECTION 01 200 – COMPANY FURNISHED MATERIAL AND EQUIPMENT

PART 1 – GENERAL

- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
 - A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
 - B. SPRINT 'STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES' ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HERewith.

PART 2 – PRODUCTS (NOT USED)

PART 3 – EXECUTION

- 3.1 RECEIPT OF MATERIAL AND EQUIPMENT:
 - A. A COMPANY FURNISHED MATERIAL AND EQUIPMENT IS IDENTIFIED ON THE RF DATA SHEET IN THE CONSTRUCTION DOCUMENTS.
 - B. THE CONTRACTOR IS RESPONSIBLE FOR SPRINT PROVIDED MATERIAL AND EQUIPMENT AND UPON RECEIPT SHALL:
 - 1. ACCEPT DELIVERIES AS SHIPPED AND TAKE RECEIPT.
 - 2. VERIFY COMPLETENESS AND CONDITION OF ALL DELIVERIES.
 - 3. TAKE RESPONSIBILITY FOR EQUIPMENT AND PROVIDE INSURANCE PROTECTION AS REQUIRED IN AGREEMENT.
 - 4. RECORD ANY DEFECTS OR DAMAGES AND WITHIN TWENTY-FOUR HOURS AFTER RECEIPT, REPORT TO SPRINT OR ITS DESIGNATED PROJECT REPRESENTATIVE OF SUCH.
 - 5. PROVIDE SECURE AND NECESSARY WEATHER PROTECTED WAREHOUSING.
 - 6. COORDINATE SAFE AND SECURE TRANSPORTATION OF MATERIAL AND EQUIPMENT, DELIVERING AND OFF-LOADING FROM CONTRACTOR'S WAREHOUSE TO SITE.
- 3.2 DELIVERABLES:
 - A. COMPLETE SHIPPING AND RECEIPT DOCUMENTATION IN ACCORDANCE WITH COMPANY PRACTICE.
 - B. IF APPLICABLE, COMPLETE LOST/STOLEN/DAMAGED DOCUMENTATION REPORT AS NECESSARY IN ACCORDANCE WITH COMPANY PRACTICE, AND AS DIRECTED BY COMPANY.
 - C. UPLOAD DOCUMENTATION INTO SPRINT SITE MANAGEMENT SYSTEM (SMS) AND/OR PROVIDE HARD COPY DOCUMENTATION AS REQUESTED.

SECTION 01 300 – CELL SITE CONSTRUCTION CO.

PART 1 – GENERAL

- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
 - A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
 - B. SPRINT 'STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES' ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HERewith.
- 1.3 NOTICE TO PROCEED
 - A. NO WORK SHALL COMMENCE PRIOR TO COMPANY'S WRITTEN NOTICE TO PROCEED AND THE ISSUANCE OF THE WORK ORDER.
 - B. UPON RECEIVING NOTICE TO PROCEED, CONTRACTOR SHALL FULLY PERFORM ALL WORK NECESSARY TO PROVIDE SPRINT WITH AN OPERATIONAL WIRELESS FACILITY.

PART 2 – PRODUCTS (NOT USED)

PART 3 – EXECUTION

- 3.1 FUNCTIONAL REQUIREMENTS:
 - A. THE ACTIVITIES DESCRIBED IN THIS PARAGRAPH REPRESENT MINIMUM ACTIONS AND PROCESSES REQUIRED TO SUCCESSFULLY COMPLETE THE WORK. THE ACTIVITIES DESCRIBED ARE NOT EXHAUSTIVE, AND CONTRACTOR SHALL TAKE ANY AND ALL ACTIONS AS NECESSARY TO SUCCESSFULLY COMPLETE THE CONSTRUCTION OF A FULLY FUNCTIONING WIRELESS FACILITY AT THE SITE IN ACCORDANCE WITH COMPANY PROCESSES.
 - B. SUBMIT SPECIFIC DOCUMENTATION AS INDICATED HEREIN, AND OBTAIN REQUIRED APPROVALS WHILE THE WORK IS BEING PERFORMED.
 - C. MANAGE AND CONDUCT ALL FIELD CONSTRUCTION SERVICE RELATED ACTIVITIES
 - D. PROVIDE CONSTRUCTION ACTIVITIES TO THE EXTENT REQUIRED BY THE CONTRACT DOCUMENTS, INCLUDING BUT NOT LIMITED TO THE FOLLOWING:

PLANS PREPARED FOR:




PLANS PREPARED BY:



MLA PARTNER:



ENGINEERING LICENSE:



DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR CONSTRUCTION	02/10/14	MAP	0

SITE NAME:

MERRIT 4 - ROXBURY (CROWN)

SITE CASCADE:

CT03XC344

SITE ADDRESS:

**69 GUINEA ROAD
STAMFORD, CT 06903**

SHEET DESCRIPTION:

SPRINT SPECIFICATIONS

SHEET NUMBER:

SP-1

CONTINUE FROM SP-1

1. PERFORM ANY REQUIRED SITE ENVIRONMENTAL MITIGATION.
2. PREPARE GROUND SITES; PROVIDE DE-GRUBBING; AND ROUGH AND FINAL GRADING, AND COMPOUND SURFACE TREATMENTS.
3. MANAGE AND CONDUCT ALL ACTIVITIES FOR INSTALLATION OF UTILITIES INCLUDING ELECTRICAL AND TELCO BACKHAUL.
4. INSTALL UNDERGROUND FACILITIES INCLUDING UNDERGROUND POWER AND COMMUNICATIONS CONDUITS, AND UNDERGROUND GROUNDING SYSTEM.
5. INSTALL ABOVE GROUND GROUNDING SYSTEMS.
6. PROVIDE NEW HVAC INSTALLATIONS AND MODIFICATIONS.
7. INSTALL "H-FRAMES", CABINETS AND SHELTERS AS INDICATED.
8. INSTALL ROADS, ACCESS WAYS, CURBS AND DRAINS AS INDICATED.
9. ACCOMPLISH REQUIRED MODIFICATION OF EXISTING FACILITIES.
10. PROVIDE ANTENNA SUPPORT STRUCTURE FOUNDATIONS.
11. PROVIDE SLABS AND EQUIPMENT PLATFORMS.
12. INSTALL COMPOUND FENCING, SIGHT SHIELDING, LANDSCAPING AND ACCESS BARRIERS.
13. PERFORM INSPECTION AND MATERIAL TESTING AS REQUIRED HEREINAFTER.
14. CONDUCT SITE RESISTANCE TO EARTH TESTING AS REQUIRED HEREINAFTER.
15. INSTALL FIXED GENERATOR SETS AND OTHER STANDBY POWER SOLUTIONS.
16. INSTALL TOWERS, ANTENNA SUPPORT STRUCTURES AND PLATFORMS ON EXISTING TOWERS AS REQUIRED.
17. INSTALL CELL SITE RADIOS, MICROWAVE, GPS, COAXIAL MAINLINE, ANTENNAS, CROSS BAND COUPLERS, TOWER TOP AMPLIFIERS, LOW NOISE AMPLIFIERS AND RELATED EQUIPMENT.
18. PERFORM, DOCUMENT, AND CLOSE OUT ANY CONSTRUCTION CONTROL DOCUMENTS THAT MAY BE REQUIRED BY GOVERNMENT AGENCIES AND LANDLORDS.
19. PERFORM ANTENNA AND COAX SWEEP TESTING AND MAKE ANY AND ALL NECESSARY CORRECTIONS.
20. REMAIN ON SITE MOBILIZED THROUGHOUT HAND-OFF AND INTEGRATION TO ASSIST AS NEEDED UNTIL SITE IS DEEMED SUBSTANTIALLY COMPLETE AND PLACED "ON AIR."

3.2 GENERAL REQUIREMENTS FOR CIVL CONSTRUCTION:

- A. CONTRACTOR SHALL KEEP THE SITE FREE FROM ACCUMULATING WASTE MATERIAL, DEBRIS, AND TRASH. AT THE COMPLETION OF THE WORK, CONTRACTOR SHALL REMOVE FROM THE SITE ALL REMAINING RUBBISH, IMPLEMENTS, TEMPORARY FACILITIES, AND SURPLUS MATERIALS.
- B. EQUIPMENT ROOMS SHALL AT ALL TIMES BE MAINTAINED "BROOM CLEAN" AND CLEAR OF DEBRIS.
- C. CONTRACTOR SHALL TAKE ALL REASONABLE PRECAUTIONS TO DISCOVER AND LOCATE ANY HAZARDOUS CONDITION.
 1. IN THE EVENT CONTRACTOR ENCOUNTERS ANY HAZARDOUS CONDITION WHICH HAS NOT BEEN ABATED OR OTHERWISE MITIGATED, CONTRACTOR AND ALL OTHER PERSONS SHALL IMMEDIATELY STOP WORK IN THE AFFECTED AREA AND NOTIFY COMPANY IN WRITING. THE WORK IN THE AFFECTED AREA SHALL NOT BE RESUMED EXCEPT BY WRITTEN NOTIFICATION BY COMPANY.
 2. CONTRACTOR AGREES TO USE CARE WHILE ON THE SITE AND SHALL NOT TAKE ANY ACTION THAT WILL OR MAY RESULT IN OR CAUSE THE HAZARDOUS CONDITION TO BE FURTHER RELEASED IN THE ENVIRONMENT, OR TO FURTHER EXPOSE INDIVIDUALS TO THE HAZARD.
- D. CONTRACTOR'S ACTIVITIES SHALL BE RESTRICTED TO THE PROJECT LIMITS. SHOULD AREAS OUTSIDE THE PROJECT LIMITS BE AFFECTED BY CONTRACTOR'S ACTIVITIES, CONTRACTOR SHALL IMMEDIATELY RETURN THEM TO ORIGINAL CONDITION
- E. CONDUCT TESTING AS REQUIRED HEREIN.

3.3 DELIVERABLES:

- A. CONTRACTOR SHALL REVIEW, APPROVE, AND SUBMIT TO SPRINT SHOP DRAWINGS, PRODUCT DATA, SAMPLES, AND SIMILAR SUBMITTALS AS REQUIRED HEREINAFTER
- B. PROVIDE DOCUMENTATION INCLUDING, BUT NOT LIMITED TO, THE FOLLOWING. DOCUMENTATION SHALL BE FORWARDED IN ORIGINAL FORMAT AND/OR UPLOADED INTO SMS.
 1. ALL CORRESPONDENCE AND PRELIMINARY CONSTRUCTION REPORTS.
 2. PROJECT PROGRESS REPORTS.
 3. CIVL CONSTRUCTION START DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
 4. ELECTRICAL SERVICE COMPLETION DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).

5. LINES AND ANTENNA INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
6. POWER INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
7. TELCO READY DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
8. PPC (OR SHELTER) INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
9. TOWER CONSTRUCTION START DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
10. TOWER CONSTRUCTION COMPLETE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
11. BTS AND RADIO EQUIPMENT DELIVERED AT SITE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
12. NETWORK OPERATIONS HANDOFF CHECKLIST (HOC WALK) COMPLETE (UPLOAD FORM IN SMS)
13. CIVL CONSTRUCTION COMPLETE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
14. SITE CONSTRUCTION PROGRESS PHOTOS UNLOADED INTO SMS.

SECTION 01 400 - SUBMITTALS & TESTS

PART 1 - GENERAL

- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
 - A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
 - B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HERewith.
- 1.3 SUBMITTALS:
 - A. THE WORK IN ALL ASPECTS SHALL COMPLY WITH THE CONSTRUCTION DRAWINGS AND THESE SPECIFICATIONS.
 - B. SUBMIT THE FOLLOWING TO COMPANY REPRESENTATIVE FOR APPROVAL
 1. CONCRETE MIX-DESIGNS FOR TOWER FOUNDATIONS, ANCHORS PIERS, AND CONCRETE PAVING.
 2. CONCRETE BREAK TESTS AS SPECIFIED HEREIN.
 3. SPECIAL FINISHES FOR INTERIOR SPACES, IF ANY.
 4. ALL EQUIPMENT AND MATERIALS SO IDENTIFIED ON THE CONSTRUCTION DRAWINGS.
 5. CHEMICAL GROUNDING DESIGN
 - D. ALTERNATES: AT THE COMPANY'S REQUEST, ANY ALTERNATIVES TO THE MATERIALS OR METHODS SPECIFIED SHALL BE SUBMITTED TO SPRINT'S CONSTRUCTION MANAGER FOR APPROVAL PRIOR TO BEING SHIPPED TO SITE. SPRINT WILL REVIEW AND APPROVE ONLY THOSE REQUESTS MADE IN WRITING. NO VERBAL APPROVALS WILL BE CONSIDERED. SUBMITTAL FOR APPROVAL SHALL INCLUDE A STATEMENT OF COST REDUCTION PROPOSED FOR USE OF ALTERNATE PRODUCT.

1.4 TESTS AND INSPECTIONS:

- A. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CONSTRUCTION TESTS, INSPECTIONS AND PROJECT DOCUMENTATION.
- B. CONTRACTOR SHALL ACCOMPLISH TESTING INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
 1. COAX SWEEPS AND FIBER TESTS PER TS-0200 REV 4 ANTENNA LINE ACCEPTANCE STANDARDS.
 2. AGL, AZIMUTH AND DOWNTILT USING ELECTRONIC COMMERCIAL MADE-FOR-THE-PURPOSE ANTENNA ALIGNMENT TOOL.
 3. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN SITE INSPECTION ACTIVITIES AND/OR AS A RESULT OF TESTING.
- C. REQUIRED CLOSEOUT DOCUMENTATION INCLUDES, BUT IS NOT LIMITED TO THE FOLLOWING:
 1. AZIMUTH, DOWNTILT, AGL - UPLOAD REPORT FROM ANTENNA ALIGNMENT TOOL TO SITERRA TASK 465. INSTALLED AZIMUTH, DOWNTILT, AND AGL MUST CONFORM TO THE RF DATA SHEETS. SWEEP AND FIBER TESTS
 2. SCANABLE BARCODE PHOTOGRAPHS OF TOWER TOP AND INACCESSIBLE SERIALIZED EQUIPMENT
 3. ALL AVAILABLE JURISDICTIONAL INFORMATION
 4. PDF SCAN OF REDLINES PRODUCED IN FIELD

5. ELECTRONIC AS-BUILT DRAWINGS IN AUTOCAD AND PDF FORMATS. ANY FIELD CHANGE MUST BE REFLECTED BY MODIFYING THE PLANS, ELEVATIONS, AND DETAILS IN THE DRAWING SETS. GENERAL NOTES INDICATING MODIFICATIONS WILL NOT BE ACCEPTED. CHANGES SHALL BE HIGHLIGHTED AS "CLOUDS" IDENTIFIED AS THE "AS-BUILT" CONDITION.
6. LIEN WAIVERS
7. FINAL PAYMENT APPLICATION
8. REQUIRED FINAL CONSTRUCTION PHOTOS
9. CONSTRUCTION AND COMMISSIONING CHECKLIST COMPLETE WITH NO DEFICIENT ITEMS
10. ALL POST NTP TASKS INCLUDING DOCUMENT UPLOADS COMPLETED IN SITERRA (SPRINTS DOCUMENT REPOSITORY OF RECORD).

1.5 COMMISSIONING: PERFORM ALL COMMISSIONING AS REQUIRED BY APPLICABLE MOPs

1.6 INTEGRATION: PERFORM ALL INTEGRATION ACTIVITIES AS REQUIRED BY APPLICABLE MOPs

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION

3.1 REQUIREMENTS FOR TESTING:

A. THIRD PARTY TESTING AGENCY:

1. WHEN THE USE OF A THIRD PARTY INDEPENDENT TESTING AGENCY IS REQUIRED, THE AGENCY THAT IS SELECTED MUST PERFORM SUCH WORK ON A REGULAR BASIS IN THE STATE WHERE THE PROJECT IS LOCATED AND HAVE A THOROUGH UNDERSTANDING OF LOCAL AVAILABLE MATERIALS, INCLUDING THE SOIL, ROCK, AND GROUNDWATER CONDITIONS.
2. THE THIRD PARTY TESTING AGENCY IS TO BE FAMILIAR WITH THE APPLICABLE REQUIREMENTS FOR THE TESTS TO BE DONE, EQUIPMENT TO BE USED, AND ASSOCIATED HEALTH AND SAFETY ISSUES.
3. EXPERIENCE IN SOILS, CONCRETE, MASONRY, AGGREGATE, AND ASPHALT TESTING USING ASTM, AASJTO, AND OTHER METHODS IS NEEDED.
4. EXPERIENCE IN SOILS, CONCRETE, MASONRY, AGGREGATE, AND ASPHALT TESTING USING ASTM, AASJTO, AND OTHER METHODS IS NEEDED.

3.2 REQUIRED TESTS:

A. CONTRACTOR SHALL ACCOMPLISH TESTING INCLUDING BUT NOT LIMITED TO THE FOLLOWING:

1. CONCRETE CYLINDER BREAK TESTS FOR THE TOWER AND ANCHOR FOUNDATIONS AS SPECIFIED IN SECTION: PORTLAND CEMENT CONCRETE PAVING.
2. ASPHALT ROADWAY COMPACTED THICKNESS, SURFACE SMOOTHNESS, AND COMPACTED DENSITY TESTING AS SPECIFIED IN SECTION: HOT MIX ASPHALT PAVING.
3. FIELD QUALITY CONTROL TESTING AS SPECIFIED IN SECTION: PORTLAND CEMENT CONCRETE PAVING.
4. TESTING REQUIRED UNDER SECTION: AGGREGATE BASE FOR ACCESS ROADS, PADS AND ANCHOR LOCATIONS
5. STRUCTURAL BACKFILL COMPACTION TESTS FOR THE TOWER FOUNDATION.
6. SITE RESISTANCE TO EARTH TESTING PER EXHIBIT: CELL SITE GROUNDING SYSTEM DESIGN.
7. ANTENNA AND COAX SWEEP TESTS PER EXHIBIT: ANTENNA TRANSMISSION LINE ACCEPTANCE STANDARDS.
8. GROUNDING AT ANTENNA MASTS FOR GPS AND ANTENNAS
9. ALL OTHER TESTS REQUIRED BY COMPANY OR JURISDICTION.

3.3 REQUIRED INSPECTIONS

A. SCHEDULE INSPECTIONS WITH COMPANY REPRESENTATIVE.

B. CONDUCT INSPECTIONS INCLUDING BUT NOT LIMITED TO THE FOLLOWING:

1. GROUNDING SYSTEM INSTALLATION PRIOR TO EARTH CONCEALMENT DOCUMENTED WITH DIGITAL PHOTOGRAPHS BY CONTRACTOR, APPROVED BY A&E OR SPRINT REPRESENTATIVE.
2. FORMING FOR CONCRETE AND REBAR PLACEMENT PRIOR TO POUR DOCUMENTED WITH DIGITAL PHOTOGRAPHS BY CONTRACTOR, APPROVED BY A&E OR SPRINT REPRESENTATIVE.
3. COMPACTION OF BACKFILL MATERIALS; AGGREGATE BASE FOR ROADS, PADS, AND ANCHORS; ASPHALT PAVING; AND SHAFT BACKFILL FOR CONCRETE AND WOOD POLES, BY INDEPENDENT THIRD PARTY AGENCY.
4. PRE- AND POST-CONSTRUCTION ROOFTOP AND STRUCTURAL INSPECTIONS ON EXISTING FACILITIES.
5. TOWER ERECTION SECTION STACKING AND PLATFORM ATTACHMENT DOCUMENTED BY DIGITAL PHOTOGRAPHS BY THIRD PARTY AGENCY.
6. ANTENNA AZIMUTH , DOWN TILT AND PER SUNLIGHT TOOL SUNSIGHT INSTRUMENTS - ANTENNALIGN ALIGNMENT TOOL (AAT)

PLANS PREPARED FOR:



PLANS PREPARED BY:



MLA PARTNER:



ENGINEERING LICENSE:



DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR CONSTRUCTION	02/10/14	MAP	0

SITE NAME:

MERRIT 4 - ROXBURY (CROWN)

SITE CASCADE:

CT03XC344

SITE ADDRESS:

**69 GUINEA ROAD
STAMFORD, CT 06903**

SHEET DESCRIPTION:

SPRINT SPECIFICATIONS

SHEET NUMBER:

SP-2

CONTINUE FROM SP-2

7. VERIFICATION DOCUMENTED WITH THE ANTENNA CHECKLIST REPORT, BY A&E, SITE DEVELOPMENT REP, OR RF REP.
 8. FINAL INSPECTION CHECKLIST AND HANDOFF WALK (HOC). SIGNED FORM SHOWING ACCEPTANCE BY FIELD OPS IS TO BE UPLOADED INTO SMS.
 9. COAX SWEEP AND FIBER TESTING DOCUMENTS SUBMITTED VIA SMS FOR RF APPROVAL.
 10. SCAN-ABLE BARCODE PHOTOGRAPHS OF TOWER TOP AND INACCESSIBLE SERIALIZED EQUIPMENT
 11. ALL AVAILABLE JURISDICTIONAL INFORMATION
 12. PDF SCAN OF REDLINES PRODUCED IN FIELD
- C. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN SITE INSPECTION ACTIVITIES AND/OR AS A RESULT OF TESTING.
- D. CONSTRUCTION INSPECTIONS AND CORRECTIVE MEASURES SHALL BE DOCUMENTED BY THE CONTRACTOR WITH WRITTEN REPORTS AND PHOTOGRAPHS. PHOTOGRAPHS MUST BE DIGITAL AND OF SUFFICIENT QUALITY TO CLEARLY SHOW THE SITE CONSTRUCTION. PHOTOGRAPHS MUST CLEARLY IDENTIFY THE PHOTOGRAPHED ITEM AND BE LABELED WITH THE SITE CASCADE NUMBER, SITE NAME, DESCRIPTION, AND DATE.
- 3.4 DELIVERABLES: TEST AND INSPECTION REPORTS AND CLOSEOUT DOCUMENTATION SHALL BE UPLOADED TO THE SMS AND/OR FORWARDED TO SPRINT FOR INCLUSION INTO THE PERMANENT SITE FILES.
- A. THE FOLLOWING TEST AND INSPECTION REPORTS SHALL BE PROVIDED AS APPLICABLE.
1. CONCRETE MIX AND CYLINDER BREAK REPORTS.
 2. STRUCTURAL BACKFILL COMPACTION REPORTS.
 3. SITE RESISTANCE TO EARTH TEST.
 4. ANTENNA AZIMUTH AND DOWN TILT VERIFICATION
 5. TOWER ERECTION INSPECTIONS AND MEASUREMENTS DOCUMENTING TOWER INSTALLED PER SUPPLIER'S REQUIREMENTS AND THE APPLICABLE SECTIONS HEREIN.
 6. COAX CABLE SWEEP TESTS PER COMPANY'S "ANTENNA LINE ACCEPTANCE STANDARDS".
- B. REQUIRED CLOSEOUT DOCUMENTATION INCLUDES THE FOLLOWING;
1. TEST WELLS AND TRENCHES: PHOTOGRAPHS OF ALL TEST WELLS; PHOTOGRAPHS SHOWING ALL OPEN EXCAVATIONS AND TRENCHING PRIOR TO BACKFILLING SHOWING A TAPE MEASURE VISIBLE IN THE EXCAVATIONS INDICATING DEPTH.
 2. CONDUITS, CONDUCTORS AND GROUNDING: PHOTOGRAPHS SHOWING TYPICAL INSTALLATION OF CONDUCTORS AND CONNECTORS; PHOTOGRAPHS SHOWING TYPICAL BEND RADIUS OF INSTALLED GROUND WIRES AND GROUND ROD SPACING;
 3. CONCRETE FORMS AND REINFORCING: CONCRETE FORMING AT TOWER AND EQUIPMENT/SHELTER PAD/FOUNDATIONS - PHOTOGRAPHS SHOWING ALL REINFORCING STEEL, UTILITY AND CONDUIT STUB OUTS; PHOTOGRAPHS SHOWING CONCRETE POUR OF SHELTER SLAB/FOUNDATION, TOWER FOUNDATION AND GUY ANCHORS WITH VIBRATOR IN USE; PHOTOGRAPHS SHOWING EACH ANCHOR ON GUYED TOWERS, BEFORE CONCRETE POUR.
 4. TOWER, ANTENNAS AND MAINLINE: INSPECTION AND PHOTOGRAPHS OF SECTION STACKING; INSPECTION AND PHOTOGRAPHS OF PLATFORM COMPONENT ATTACHMENT POINTS; PHOTOGRAPHS OF TOWER TOP GROUNDING; PHOTOS OF TOWER COAX LINE COLOR CODING AT THE TOP AND AT GROUND LEVEL; INSPECTION AND PHOTOGRAPHS OF OPERATIONAL OF TOWER LIGHTING, AND PLACEMENT OF FAA REGISTRATION SIGN; PHOTOGRAPHS SHOWING ADDITIONAL GROUNDING POINTS FOR TOWERS GREATER THAN 200 FEET.; PHOTOS OF ANTENNA GROUND BAR, EQUIPMENT GROUND BAR, AND MASTER GROUND BAR; PHOTOS OF GPS ANTENNA(S); PHOTOS OF EACH SECTOR OF ANTENNAS; ONE PHOTOGRAPH LOOKING AT THE SECTOR AND ONE FROM BEHIND SHOWING THE PROJECTED COVERAGE AREA; PHOTOS OF COAX WEATHERPROOFING - TOP AND BOTTOM; PHOTOS OF COAX GROUNDING--TOP AND BOTTOM; PHOTOS OF ANTENNA AND MAST GROUNDING; PHOTOS OF COAX CABLE ENTRY INTO SHELTER; PHOTOS OF PLATFORM MECHANICAL CONNECTIONS TO TOWER/MONOPOLE.
 5. ROOF TOPS: PRE--CONSTRUCTION AND POST--CONSTRUCTION VISUAL INSPECTION AND PHOTOGRAPHS OF THE ROOF AND INTERIOR TO DETERMINE AND DOCUMENT CONDITIONS; ROOF TOP CONSTRUCTION INSPECTIONS AS REQUIRED BY THE JURISDICTION; PHOTOGRAPHS OF CABLE TRAY AND/OR ICE BRIDGE; PHOTOGRAPHS OF DOGHOUSE/CABLE EXIT FROM ROOF;
 6. SITE LAYOUT - PHOTOGRAPHS OF THE OVERALL COMPOUND, INCLUDING EQUIPMENT PLATFORM FROM ALL FOUR CORNERS.
 7. FINISHED UTILITIES: CLOSE-UP PHOTOGRAPHS OF THE PPC BREAKER PANEL; CLOSE-UP PHOTOGRAPH OF THE INSIDE OF THE TELCO PANEL AND NIU; CLOSE-UP PHOTOGRAPH OF THE POWER METER AND DISCONNECT; PHOTOS OF POWER AND TELCO ENTRANCE TO COMPANY ENCLOSURE; PHOTOGRAPHS AT METER BOX AND/OR FACILITY DISTRIBUTION PANEL.
 8. REQUIRED MATERIALS CERTIFICATIONS: CONCRETE MIX DESIGNS; MILL CERTIFICATION FOR ALL REINFORCING AND STRUCTURAL STEEL; AND ASPHALT PAVING MIX DESIGN.
 9. ANY AND ALL SUBMITTALS BY THE JURISDICTION OR COMPANY.

SECTION 01 400 - SUBMITTALS & TESTS

PART 1 - GENERAL

- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
 - A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
 - B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION

- 3.1 WEEKLY REPORTS:
 - A. CONTRACTOR SHALL PROVIDE SPRINT WITH WEEKLY REPORTS SHOWING PROJECT STATUS. THIS STATUS REPORT FORMAT WILL BE PROVIDED TO THE CONTRACTOR BY SPRINT. THE REPORT WILL CONTAIN SITE ID NUMBER, THE MILESTONES FOR EACH SITE, INCLUDING THE BASELINE DATE, ESTIMATED COMPLETION DATE AND ACTUAL COMPLETION DATE.
 - B. REPORT INFORMATION WILL BE TRANSMITTED TO SPRINT VIA ELECTRONIC MEANS AS REQUIRED. THIS INFORMATION WILL PROVIDE A BASIS FOR PROGRESS MONITORING AND PAYMENT.
- 3.2 PROJECT CONFERENCE CALLS:
 - A. SPRINT MAY HOLD WEEKLY PROJECT CONFERENCE CALLS. CONTRACTOR WILL BE REQUIRED TO COMMUNICATE SITE STATUS, MILESTONE COMPLETIONS AND UPCOMING MILESTONE PROJECTIONS, AND ANSWER ANY OTHER SITE STATUS QUESTIONS AS NECESSARY.
- 3.3 PROJECT TRACKING IN SMS:
 - A. CONTRACTOR SHALL PROVIDE SCHEDULE UPDATES AND PROJECTIONS IN THE SMS SYSTEM ON A WEEKLY BASIS.
- 3.4 ADDITIONAL REPORTING:
 - A. ADDITIONAL OR ALTERNATE REPORTING REQUIREMENTS MAY BE ADDED TO THE REPORT AS DETERMINED TO BE REASONABLY NECESSARY BY COMPANY.
- 3.5 PROJECT PHOTOGRAPHS:
 - A. FILE DIGITAL PHOTOGRAPHS OF COMPLETED SITE IN JPEG FORMAT IN THE SMS PHOTO LIBRARY FOR THE RESPECTIVE SITE. PHOTOGRAPHS SHALL BE CLEARLY LABELED WITH SITE NUMBER, NAME AND DESCRIPTION, AND SHALL INCLUDE AT A MINIMUM THE FOLLOWING AS APPLICABLE:
 1. SHELTER AND TOWER OVERVIEW.
 2. TOWER FOUNDATION(S) - FORMS AND STEEL BEFORE POUR (EACH ANCHOR ON GUYED TOWERS).
 3. TOWER FOUNDATION(S) POUR WITH VIBRATOR IN USE (EACH ANCHOR ON GUYED TOWERS).
 4. TOWER STEEL AS BEING INSTALLED INTO HOLE (SHOW ANCHOR STEEL ON GUYED TOWERS).
 5. PHOTOS OF TOWER SECTION STACKING.
 6. CONCRETE TESTING / SAMPLES.
 7. PLACING OF ANCHOR BOLTS IN TOWER FOUNDATION.
 8. BUILDING/WATER TANK FROM ROAD FOR TENANT IMPROVEMENTS OR COMMENTS.
 9. SHELTER FOUNDATION--FORMS AND STEEL BEFORE POURING.
 10. SHELTER FOUNDATION POUR WITH VIBRATOR IN USE.
 11. COAX CABLE ENTRY INTO SHELTER.
 12. PLATFORM MECHANICAL CONNECTIONS TO TOWER/MONOPOLE.
 13. ROOFTOP PRE AND POST CONSTRUCTION PHOTOS TO INCLUDE PENETRATIONS AND INTERIOR CEILING.
 14. PHOTOS OF TOWER TOP COAX LINE COLOR CODING AND COLOR CODING AT GROUND LEVEL.
 15. PHOTOS OF ALL APPROPRIATE COMPANY OR REGULATORY SIGNAGE.
 16. PHOTOS OF EQUIPMENT BOLT DOWN INSIDE SHELTER.
 17. POWER AND TELCO ENTRANCE TO COMPANY ENCLOSURE AND POWER AND TELCO SUPPLY LOCATIONS INCLUDING METER/DISCONNECT.
 18. ELECTRICAL TRENCH(S) WITH ELECTRICAL / CONDUIT BEFORE BACKFILL.
 19. ELECTRICAL TRENCH(S) WITH FOIL-BACKED TAPE BEFORE FURTHER BACKFILL.
 20. TELCO TRENCH WITH TELEPHONE / CONDUIT BEFORE BACKFILL.
 21. TELCO TRENCH WITH FOIL-BACKED TAPE BEFORE FURTHER BACKFILL.
 22. SHELTER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADII).
 23. TOWER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADII).

24. FENCE GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADII).
 25. ALL BTS GROUND CONNECTIONS.
 26. ALL GROUND TEST WELLS.
 27. ANTENNA GROUND BAR AND EQUIPMENT GROUND BAR.
 28. ADDITIONAL GROUNDING POINTS ON TOWERS ABOVE 200'.
 29. HVAC UNITS INCLUDING CONDENSERS ON SPLIT SYSTEMS.
 30. GPS ANTENNAS.
 31. CABLE TRAY AND/OR WAVEGUIDE BRIDGE.
 32. DOGHOUSE/CABLE EXIT FROM ROOF.
 33. EACH SECTOR OF ANTENNAS; ONE PHOTOGRAPH LOOKING AT THE SECTOR AND ONE FROM BEHIND SHOWING THE PROJECTED COVERAGE AREA.
 34. MASTER BUS BAR.
 35. TELCO BOARD AND NIU.
 36. ELECTRICAL DISTRIBUTION WALL.
 37. CABLE ENTRY WITH SURGE SUPPRESSION.
 38. ENTRANCE TO EQUIPMENT ROOM.
 39. COAX WEATHERPROOFING--TOP AND BOTTOM OF TOWER.
 40. COAX GROUNDING --TOP AND BOTTOM OF TOWER.
 41. ANTENNA AND MAST GROUNDING.
 42. LANDSCAPING - WHERE APPLICABLE.
- 3.6 FINAL PROJECT ACCEPTANCE: COMPLETE ALL REQUIRED REPORTING TASKS PER CONTRACT, CONTRACT DOCUMENTS OR THE SPRINT INTEGRATED CONSTRUCTION STANDARDS FOR WIRELESS SITES AND UPLOAD INTO SITERRA.

PLANS PREPARED FOR:



PLANS PREPARED BY:



MLA PARTNER:



ENGINEERING LICENSE:



DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR CONSTRUCTION	02/10/14	MAP	0

SITE NAME:

MERRIT 4 - ROXBURY (CROWN)

SITE CASCADE:

CT03XC344

SITE ADDRESS:

**69 GUINEA ROAD
STAMFORD, CT 06903**

SHEET DESCRIPTION:

SPRINT SPECIFICATIONS

SHEET NUMBER:

SP-3

INFORMATION CONTAINED WITHIN DRAWINGS ARE BASED ON PROVIDED INFORMATION AND ARE NOT THE RESULT OF A FIELD SURVEY.

PLANS PREPARED FOR:



6580 Sprint Parkway
Overland Park, Kansas 66251


PLANS PREPARED BY:




1033 Watervliet Shaker Rd
Albany, NY 12205
Office # (518) 690-0790
Fax # (518) 690-0783

JOB NUMBER 353-000

MLA PARTNER:



ENGINEERING LICENSE:



DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR CONSTRUCTION	02/10/14	MAP	0

SITE NAME:

MERRIT 4 - ROXBURY (CROWN)

SITE CASCADE:

CT03XC344

SITE ADDRESS:



**69 GUINEA ROAD
STAMFORD, CT 06903**

SHEET DESCRIPTION:

SITE PLAN



SHEET NUMBER:

A-1



OVERALL SITE PLAN

SCALE: AS NOTED 1



SPRINT EQUIPMENT PLAN

SCALE: AS NOTED 2

PLANS PREPARED FOR:




PLANS PREPARED BY:



MLA PARTNER:



ENGINEERING LICENSE:



DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR CONSTRUCTION	02/10/14	MAP	0

SITE NAME:

MERRIT 4 - ROXBURY (CROWN)

SITE CASCADE:

CT03XC344

SITE ADDRESS:


69 GUINEA ROAD
STAMFORD, CT 06903

SHEET DESCRIPTION:

TOWER ELEVATION & CABLE PLAN

SHEET NUMBER:

A-2



NOTE:
SPRINT TOWER TOP WORK CONTINGENT ON FOLLOWING: COMPLETION OF STRUCTURAL ANALYSIS PROVIDED BY CROWN CASTLE, COMPLETION OF ANTENNA/RRH MOUNTING ASSESSMENT (PROVIDED BY AE)

NOTE:
INFINIGY ENGINEERING HAS NOT EVALUATED THE EXISTING TOWER OR MOUNT FOR THIS SITE, AND ASSUMES NO RESPONSIBILITY FOR ITS STRUCTURAL INTEGRITY. REFER TO STRUCTURAL ANALYSIS BY OTHERS PRIOR TO ANY CONSTRUCTION.

NOTE:
CONTRACTOR SHALL NOT INSTALL THE 2.5 RRU'S SUCH THAT THEY IMPEDE CLIMBING ACCESS ON THE TOWER.


NOTE:
SEE DETAIL 2 ON A-3 FOR ANTENNA LAYOUT

DETAIL NOT USED NO SCALE 2

DETAIL NOT USED NO SCALE 3


DETAIL NOT USED NO SCALE 4

TOWER ELEVATION NO SCALE 1




EXISTING ANTENNA & RRU LAYOUT

NO SCALE 1




FINAL ANTENNA LAYOUT

NO SCALE 2



DETAIL NOT USED

NO SCALE 3



TYPICAL ANTENNA & RRU MOUNTING DETAILS

NO SCALE 4

PLANS PREPARED FOR:

6580 Sprint Parkway
Overland Park, Kansas 66251

PLANS PREPARED BY:

Design. Build. Deliver.
1033 Watervliet Shaker Rd
Albany, NY 12205
Office # (518) 690-0790
Fax # (518) 690-0793
JOB NUMBER 353-000

MLA PARTNER:

ENGINEERING LICENSE:

DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV

ISSUED FOR CONSTRUCTION 02/10/14 MAP 0

SITE NAME:
MERRIT 4 - ROXBURY (CROWN)

SITE CASCADE:
CT03XC344

SITE ADDRESS:
69 GUINEA ROAD
STAMFORD, CT 06903

SHEET DESCRIPTION:
ANTENNA LAYOUT & MOUNTING DETAILS

SHEET NUMBER:
A-3

NOTE: CONTRACTOR SHALL NOT INSTALL THE 2.5 RRU'S SUCH THAT THEY IMPEDE CLIMBING ACCESS ON THE TOWER.

THE CONFIGURATION PLANS ARE BASED ON PROVIDED INFORMATION AND ARE FOR CONCEPTUAL PURPOSES ONLY. CONTRACTOR TO VERIFY FIELD CONDITIONS PRIOR TO CONSTRUCTION.

NOTE: JUMPERS FROM 2.5 RRU TO THE 2.5 ANTENNA CANNOT EXCEED 15 FEET

NOTE: CONTRACTOR TO POSITION RRU ON MOUNT BEHIND ANTENNA SUCH THAT THE RRU DOES NOT INTERFERE WITH THE EXISTING PLATFORM/T-ARM MOUNTING HARDWARE.

NOTE: SPARE DC CABLES ARE COILED UP ON NV RRHS AT SPRINT ARRAY. THESE ARE TO BE USED TO POWER UP THE 2.5 RRHS AND TIED INTO EXISTING DC BREAKERS INSIDE THE FIBER JUNCTION BOX LOCATED AT EQUIPMENT.


NOTE: THE DIAGRAM IS FOR CONCEPTUAL PURPOSES ONLY. CONTRACTOR IS TO REFER TO PASSING STRUCTURAL ANALYSIS FOR ANTENNA AND RRU MOUNTING DETAILS

NV CABLES				
BAND	INDICATOR		PORT	COLOR
800-1	YEL	GRN	NV-1	GRN
1900-1	YEL	RED	NV-2	BLU
1900-2	YEL	BRN	NV-3	BRN
1900-3	YEL	BLU	NV-4	WHT
1900-4	YEL	SLT	NV-5	RED
800-2	YEL	ORG	NV-6	SLT
SPARE	YEL	WHT	NV-7	PPL
2500	YEL	PPL	NV-8	ORG

HYBRID	
HYBRID	COLOR
1	GRN
2	BLU
3	BRN
4	WHT
5	RED
6	SLT
7	PPL
8	ORG

2.5 Band		
2500 Radio 1	COLOR	
YEL	WHT	GRN
YEL	WHT	BLU
YEL	WHT	BRN
YEL	WHT	WHT
YEL	WHT	RED
YEL	WHT	SLT
YEL	WHT	PPL
YEL	WHT	ORG

Figure 1: Antenna Orientation






NOTES:

- ALL CABLES SHALL BE MARKED WITH 2" WIDE, UV STABILIZED, UL APPROVED TAPE.
- THE FIRST RING SHALL BE CLOSEST TO THE END OF THE CABLE AND SPACED APPROXIMATELY 2" FROM THE END CONNECTOR, WEATHERPROOFING, OR BREAK-OUT CYLINDER. THERE SHALL BE A 1" SPACE BETWEEN EACH RING FOR THE CABLE IDENTIFIER, AND NO SPACES BETWEEN THE FREQUENCY BANDS.
- A 2" GAP SHALL SEPARATE THE CABLE COLOR CODE FROM THE FREQUENCY COLOR CODE. THE 2" COLOR RINGS FOR THE FREQUENCY CODE SHALL BE PLACED NEXT TO EACH OTHER WITH NO SPACES.
- THE 2" COLORED TAPE(S) SHALL EACH BE WRAPPED A MINIMUM OF 3 TIMES AROUND THE INDIVIDUAL CABLES, AND THE TAPE SHALL BE KEPT IN THE SAME LOCATION AS MUCH AS POSSIBLE.
- SITES WITH MORE THAN FOUR (4) SECTORS WILL REQUIRE ADDITIONAL RINGS FOR EACH SECTOR, FOLLOWING THE PATTERN. HIGH CAPACITY SITES WILL USE THE NEXT COLOR IN THE SEQUENCE FOR ADDITIONAL CABLES IN EACH SECTOR.
- HYBRID FIBER CABLE SHALL BE SECTOR IDENTIFIED INSIDE THE CABINET ON FREQUENCY BUNDLES, ON THE SEALTITE, ON THE MAIN LINE UPON EXIT OF SEALTITE, AND BEFORE AND AFTER THE BREAKOUT UNIT (MEDUSA), AS WELL AS BEFORE AND AFTER ANY ENTRANCE OR EXIT.
- HFC "MAIN TRUNK" WILL NOT BE MARKED WITH THE FREQUENCY CODES, AS IT CONTAINS ALL FREQUENCIES.
- INDIVIDUAL POWER PAIRS AND FIBER BUNDLES SHALL BE LABELED WITH BOTH THE CABLE AND FREQUENCY.

Sector	Cable	First Ring	Second Ring	Third Ring
1 Alpha	1	Green	No Tape	No Tape
1	2	Blue	No Tape	No Tape
1	3	No Tape	No Tape	No Tape
1	4	White	No Tape	No Tape
1	5	Red	No Tape	No Tape
1	6	Grey	No Tape	No Tape
1	7	Purple	No Tape	No Tape
1	8	Orange	No Tape	No Tape
2 Beta	1	Green	Green	No Tape
2	2	Blue	Blue	No Tape
2	3	No Tape	No Tape	No Tape
2	4	White	White	No Tape
2	5	Red	Red	No Tape
2	6	Grey	Grey	No Tape
2	7	Purple	Purple	No Tape
2	8	Orange	Orange	No Tape
3 Gamma	1	Green	Green	Green
3	2	Blue	Blue	Blue
3	3	No Tape	No Tape	No Tape
3	4	White	White	White
3	5	Red	Red	Red
3	6	Grey	Grey	Grey
3	7	Purple	Purple	Purple
3	8	Orange	Orange	Orange

NV FREQUENCY	INDICATOR	ID
800-1	YEL	GRN
1900-1	YEL	RED
1900-2	YEL	BRN
1900-3	YEL	BLU
1900-4	YEL	SLT
800-1	YEL	ORG
RESERVED	YEL	WHT
RESERVED	YEL	PPL

2.5 FREQUENCY	INDICATOR	ID
2500 -1	YEL	WHT
2500 -2	YEL	WHT
2500 -3	YEL	WHT
2500 -4	YEL	WHT
2500 -5	YEL	WHT
2500 -6	YEL	WHT
2500 -7	YEL	WHT
2500 -8	YEL	WHT



COLOR CODING AND NOTES

NO SCALE

A

PLANS PREPARED FOR:



PLANS PREPARED BY:



MLA PARTNER:



ENGINEERING LICENSE:



DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:	DESCRIPTION	DATE	BY	REV
ISSUED FOR CONSTRUCTION		02/10/14	MAP	0

SITE NAME:
MERRIT 4 - ROXBURY (CROWN)


SITE CASCADE:
CT03XC344

SITE ADDRESS:
69 GUINEA ROAD
STAMFORD, CT 06903

SHEET DESCRIPTION:
COLOR CODING AND NOTES


SHEET NUMBER:
A-4

RRU: ALCATEL LUCENT TD-RRH8X20



NOTES

COMPLY WITH MANUFACTURERS INSTRUCTIONS TO ENSURE THAT ALL RRU'S RECEIVE ELECTRICAL POWER WITHIN 24 HOURS OF BEING REMOVED FROM THE MANUFACTURER'S PACKAGING. DO NOT OPEN RRU PACKAGES IN THE RAIN



2.5 RRU

NO SCALE

1



NEW EQUIPMENT IN EXISTING CABINET

NO SCALE

2

ANTENNA: RFS APXVTM14-C-I20

- RADOME MATERIAL: ASA
- RADOME COLOR: LIGHT GRAY
- DIMENSIONS, HxWxD.In(mlm): 56.3"x12.6"x6.3" (1430x320x160mm)
- WEIGHT: 52.9 lbs
- CONNECTORS: (8) 4.1/9.5 DIN FEMALE
(1) NF - CALIBRATION CONNECTOR



2.5 ANTENNA

NO SCALE

3

DETAIL NOT USED

NO SCALE

4

PLANS PREPARED FOR:

6580 Sprint Parkway
Overland Park, Kansas 66251

PLANS PREPARED BY:

Design. Build. Deliver.
 1033 Watervliet Shaker Rd
Albany, NY 12205
Office # (518) 680-0790
Fax # (518) 680-0793
 JOB NUMBER 353-000

MLA PARTNER:

ENGINEERING LICENSE:

DRAWING NOTICE:
 THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR CONSTRUCTION	02/10/14	MAP	0

SITE NAME:
MERRIT 4 - ROXBURY (CROWN)

SITE CASCADE:
CT03XC344

SITE ADDRESS:
 69 GUINEA ROAD
 STAMFORD, CT 06903

SHEET DESCRIPTION:
EQUIPMENT & MOUNTING DETAILS

SHEET NUMBER:
A-5





RFS HYBRIFLEX RISER CABLE SCHEDULE

Fiber Only (Existing DC Power)	Hybrid cable MN: HB058-M12-050F 12x multi-mode fiber pairs, Top: Outdoor protected connectors, Bottom: LC Connectors, 5/8 cable, 50 ft	50 ft
	MN: HB058-M12-075F	75 ft
	MN: HB058-M12-100F	100 ft
	MN: HB058-M12-125F	125 ft
	MN: HB058-M12-150F	150 ft
8 AWG Power	Hybrid cable MN: HB114-08U3M12-050F 3x 8 AWG power pairs, 12x multi-mode fiber pairs, Outdoor rated connectors & LC Connectors, 1 1/4 cable, 50 ft	50 ft
	MN: HB114-08U3M12-075F	75 ft
	MN: HB114-08U3M12-100F	100 ft
	MN: HB114-08U3M12-125F	125 ft
	MN: HB114-08U3M12-150F	150 ft
6 AWG Power	Hybrid cable MN: HB114-13U3M12-225F 3x 6 AWG power pair, 12x multi-mode fiber pairs, Outdoor rated connectors & LC Connectors, 1 1/4 cable, 225 ft	225 ft
	MN: HB114-13U3M12-250F	250 ft
	MN: HB114-13U3M12-275F	275 ft
	MN: HB114-13U3M12-300F	300 ft
	4 AWG Power	Hybrid cable MN: HB114-21U3M12-325F 3x 4 AWG power pair, 12x multi-mode fiber pairs, Outdoor rated connectors & LC Connectors, 1 1/4 cable, 325 ft
MN: HB114-21U3M12-350F		350 ft
MN: HB114-21U3M12-375F		375 ft

RFS HYBRIFLEX JUMPER CABLE SCHEDULE

Fiber Only	Hybrid Jumper cable MN: HBF012-M3-5F1 5 ft, 3x multi-mode fiber pairs, Outdoor & LC connectors, 1/2 cable	5 ft
	MN: HBF012-M3-10F1	10 ft
	MN: HBF012-M3-15F1	15 ft
	MN: HBF012-M3-20F1	20 ft
	MN: HBF012-M3-25F1	25 ft
8 AWG Power	Hybrid Jumper cable MN: HBF058-08U1M3-5F1 5 ft, 1x 8 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 5/8 cable	5 ft
	MN: HBF058-08U1M3-10F1	10 ft
	MN: HBF058-08U1M3-15F1	15 ft
	MN: HBF058-08U1M3-20F1	20 ft
	MN: HBF058-08U1M3-25F1	25 ft
6 AWG Power	Hybrid Jumper cable MN: HBF058-13U1M3-5F1 5 ft, 1x 6 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 5/8 cable	5 ft
	MN: HBF058-13U1M3-10F1	10 ft
	MN: HBF058-13U1M3-15F1	15 ft
	MN: HBF058-13U1M3-20F1	20 ft
	MN: HBF058-13U1M3-25F1	25 ft
4 AWG Power	Hybrid Jumper cable MN: HBF078-21U1M3-5F1 5 ft, 1x 4 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 7/8 cable	5 ft
	MN: HBF078-21U1M3-10F1	10 ft
	MN: HBF078-21U1M3-15F1	15 ft
	MN: HBF078-21U1M3-20F1	20 ft
	MN: HBF078-21U1M3-25F1	25 ft

NOTE:
SPRINT CM TO CONFIRM HYBRID RISER CABLE AND HYBRID JUMPER CABLE MODEL NUMBERS BEFORE PREPARING BOM.



FIBER JUNCTION BOX PENETRATION

NO SCALE 2

2.5 CABLE CROSS SECTION DATA

NO SCALE 1

DETAIL NOT USED

NO SCALE 4

PLANS PREPARED FOR:

6580 Sprint Parkway
Overland Park, Kansas 66251

PLANS PREPARED BY:

Design. Build. Deliver.
1033 Watervliet Shaker Rd
Albany, NY 12205
Office # (518) 690-0790
Fax # (518) 690-0793
JOB NUMBER 353-000

MLA PARTNER:

ENGINEERING LICENSE:

DRAWING NOTICE:
THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV

ISSUED FOR CONSTRUCTION 02/10/14 MAP 0


SITE NAME:
MERRIT 4 - ROXBURY (CROWN)

SITE CASCADE:
CT03XC344


SITE ADDRESS:
**69 GUINEA ROAD
STAMFORD, CT 06903**

SHEET DESCRIPTION:
CIVIL DETAILS


SHEET NUMBER:
A-6



ALU 2.5 ALU SCENARIO 1



RAN WIRING DIAGRAM



RF 2.5 ALU SCENARIO 1

PLUMBING DIAGRAM

NO SCALE

1

PLANS PREPARED FOR:



6580 Sprint Parkway
Overland Park, Kansas 66251

PLANS PREPARED BY:



1033 Watervliet Shaker Rd
Albany, NY 12205
Office # (518) 680-0790
Fax # (518) 680-0793

JOB NUMBER 353-000

MLA PARTNER:



ENGINEERING LICENSE:



DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR CONSTRUCTION	02/10/14	MAP	0

SITE NAME:

MERRIT 4 - ROXBURY (CROWN)

SITE CASCADE:

CT03XC344

SITE ADDRESS:

69 GUINEA ROAD
STAMFORD, CT 06903

SHEET DESCRIPTION:

PLUMBING DIAGRAM

SHEET NUMBER:


A-7

PLAN NOT USED

NO SCALE

1


- LEGEND:**
- G — EXISTING GROUND RING
 - CADWELD CONNECTION (EXOTHERMIC WELD)
 - ▲ MECHANICAL CONNECTION
 - ⊗ GROUND ROD
 - CABLE GROUND KIT



TYPICAL ANTENNA GROUNDING PLAN

NO SCALE

2



NOTE:
DEPICTION IS FOR CONCEPTUAL PURPOSES ONLY. CONTRACTOR IS TO FIELD VERIFY PRIOR TO CONSTRUCTION

TYPICAL EQUIPMENT GROUNDING PLAN (ELEVATION)

NO SCALE

3

DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR CONSTRUCTION	02/10/14	MAP	0

SITE NAME:

MERRIT 4 - ROXBURY (CROWN)

SITE CASCADE:

CT03XC344

SITE ADDRESS:

**69 GUINEA ROAD
STAMFORD, CT 06903**


SHEET DESCRIPTION:

ELECTRICAL & GROUNDING PLAN

SHEET NUMBER:

E-1



NOTES
 CG SHALL REFERENCE ALL SPECS FOR "CONNECTING THE POWER SUPPLY" OF THE NEW INSTALLATION DOCUMENTS, FOR ALL CONNECTION SPECIFICATIONS.



CIRCUIT SCHEDULE			
NO	FROM	TO	CONFIGURATION
①	UTILITY SOURCE	METER/DISCONNECT	EXISTING
②	METER/DISCONNECT	TRANSFER & LOAD CENTER	EXISTING
③	TRANSFER & LOAD CENTER	GENERATOR RECEPTACLE	EXISTING
④	TRANSFER & LOAD CENTER	EXISTING SPRINT BBU CABINET	EXISTING
⑤	TRANSFER & LOAD CENTER	EXISTING SPRINT MMBS CABINET	EXISTING

ELECTRICAL ONE-LINE DIAGRAM

NO SCALE 1



NOTES

1. APPLY NO-OX TO LUG AND BAR CONTACT SURFACE. DO NOT COAT INLINE LUG.
2. IF STOLEN GROUND BARS ARE ENCOUNTERED, CONTACT SPRINT CM FOR REPLACEMENT THREADED ROD KIT.

INSTALLATION OF GROUNDING CONDUCTOR TO GROUNDING BAR


NO SCALE

2

TWO HOLE LUG

NO SCALE

3



GROUNDING RISER DIAGRAM

NO SCALE

4

PLANS PREPARED FOR:



PLANS PREPARED BY:



MLA PARTNER:



ENGINEERING LICENSE:



DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR CONSTRUCTION	02/10/14	MAP	0

SITE NAME:

MERRIT 4 - ROXBURY (CROWN)

SITE CASCADE:

CT03XC344

SITE ADDRESS:

69 GUINEA ROAD
 STAMFORD, CT 06903

SHEET DESCRIPTION:

ELECTRICAL & GROUNDING DETAILS

SHEET NUMBER:

E-2



PAUL J. FORD AND COMPANY
STRUCTURAL ENGINEERS
 250 East Broad Street • Suite 600 • Columbus, Ohio 43215-3708

Date: April 07, 2014

Andrew Bazinet
 Crown Castle
 46 Broadway
 Albany, NY 12204

Paul J Ford and Company
 250 E. Broad Street Suite 600
 Columbus, OH 43215
 614.221.6679

Subject: Structural Modification Report

Carrier Designation: *Sprint PCS Co-Locate* **Scenario 2.5A**
Carrier Site Number: CT03XC344
Carrier Site Name: MERRIT 4- ROXBURY (CROWN)

Crown Castle Designation: **Crown Castle BU Number:** 806953
Crown Castle Site Name: BRG 2044 (A) 943097
Crown Castle JDE Job Number: 251890
Crown Castle Work Order Number: 736046
Crown Castle Application Number: 205537 Rev. 1

Engineering Firm Designation: **Paul J Ford and Company Project Number:** 37513-2318 BP A

Site Data: **69 Guinea RD(Camp Rocky Craig), Stamford, Fairfield County, CT**
Latitude 41° 6' 6.35", Longitude -73° 35' 41.45"
160 Foot - Monopole Tower

Dear Andrew Bazinet,

Paul J Ford and Company is pleased to submit this "**Structural Modification Report**" to determine the structural integrity of the above mentioned tower. This analysis has been performed in accordance with the Crown Castle Structural 'Statement of Work' and the terms of Crown Castle Purchase Order Number 633135, in accordance with application 205537, revision 1.

The purpose of the analysis is to determine acceptability of the tower stress level. Based on our analysis we have determined the tower stress level for the structure and foundation, under the following load case, to be:

LC4.7: Modified Structure w/ Existing + Reserved + Proposed Equipment **Sufficient Capacity**
 Note: See Table I and Table II for the proposed and existing/reserved loading, respectively.


The analysis has been performed in accordance with the TIA/EIA-222-F standard and the 2005 CT State Building Code based upon a fastest mile wind speed of 85 mph with no ice, 37.6 mph with 0.75 inch ice thickness and 50 mph under service loads.

All modifications and equipment proposed in this report shall be installed in accordance with the attached drawings for the determined available structural capacity to be effective.

We at Paul J Ford and Company appreciate the opportunity of providing our continuing professional services to you and Crown Castle. If you have any questions or need further assistance on this or any other projects please give us a call.

Respectfully submitted by:


 Joshua Frybarger, E.I.T.
 Structural Designer





PAUL J. FORD AND COMPANY
STRUCTURAL ENGINEERS
250 East Broad Street • Suite 600 • Columbus, Ohio 43215-3708

Date: **April 07, 2014**

Andrew Bazinet
Crown Castle
46 Broadway
Albany, NY 12204

Paul J Ford and Company
250 E. Broad Street Suite 600
Columbus, OH 43215
614.221.6679

Subject: Structural Modification Report

Carrier Designation:	Sprint PCS Co-Locate	Scenario 2.5A
	Carrier Site Number:	CT03XC344
	Carrier Site Name:	MERRIT 4- ROXBURY (CROWN)
Crown Castle Designation:	Crown Castle BU Number:	806953
	Crown Castle Site Name:	BRG 2044 (A) 943097
	Crown Castle JDE Job Number:	251890
	Crown Castle Work Order Number:	736046
	Crown Castle Application Number:	205537 Rev. 1
Engineering Firm Designation:	Paul J Ford and Company Project Number:	37513-2318 BP A
Site Data:	69 Guinea RD(Camp Rocky Craig), Stamford, Fairfield County, CT	
	Latitude 41° 6' 6.35", Longitude -73° 35' 41.45"	
	160 Foot - Monopole Tower	

Dear Andrew Bazinet,

Paul J Ford and Company is pleased to submit this "**Structural Modification Report**" to determine the structural integrity of the above mentioned tower. This analysis has been performed in accordance with the Crown Castle Structural 'Statement of Work' and the terms of Crown Castle Purchase Order Number 633135, in accordance with application 205537, revision 1.

The purpose of the analysis is to determine acceptability of the tower stress level. Based on our analysis we have determined the tower stress level for the structure and foundation, under the following load case, to be:

LC4.7: Modified Structure w/ Existing + Reserved + Proposed Equipment
Note: See Table I and Table II for the proposed and existing/reserved loading, respectively.

Sufficient Capacity

The analysis has been performed in accordance with the TIA/EIA-222-F standard and the 2005 CT State Building Code based upon a fastest mile wind speed of 85 mph with no ice, 37.6 mph with 0.75 inch ice thickness and 50 mph under service loads.

All modifications and equipment proposed in this report shall be installed in accordance with the attached drawings for the determined available structural capacity to be effective.

We at *Paul J Ford and Company* appreciate the opportunity of providing our continuing professional services to you and Crown Castle. If you have any questions or need further assistance on this or any other projects please give us a call.

Respectfully submitted by:

Joshua Frybarger, E.I.T.
Structural Designer

TABLE OF CONTENTS

1) INTRODUCTION

2) ANALYSIS CRITERIA

Table 1 - Proposed Antenna and Cable Information

Table 2 - Existing and Reserved Antenna and Cable Information

3) ANALYSIS PROCEDURE

Table 3 - Documents Provided

3.1) Analysis Method

3.2) Assumptions

4) ANALYSIS RESULTS

Table 4 - Section Capacity (Summary)

Table 5 – Tower Components vs. Capacity

4.1) Recommendations

5) APPENDIX A

tnxTower Output

6) APPENDIX B

Base Level Drawing

7) APPENDIX C

Additional Calculations

1) INTRODUCTION

This tower is a 160 ft Monopole tower designed by VALMONT in August of 1999. The tower was originally designed for a wind speed of 85 mph per TIA/EIA-222-F.

2) ANALYSIS CRITERIA

The structural analysis was performed for this tower in accordance with the requirements of TIA/EIA-222-F Structural Standards for Steel Antenna Towers and Antenna Supporting Structures using a fastest mile wind speed of 85 mph with no ice, 37.6 mph with 0.75 inch ice thickness and 50 mph under service loads.

Table 1 - Proposed Antenna and Cable Information

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)	Note
158.0	158.0	3	alcatel lucent	TME-1900MHz RRH (65MHz) w/ Mount Pipe	-	-	
		3	alcatel lucent	TME-800MHz RRH w/ mount pipe			
		2	tower mounts	Pipe Mount [PM 601-3]			
157.0	158.0	3	alcatel lucent	800 EXTERNAL NOTCH FILTER	3 1	1 1/4 5/8	-
		3	alcatel lucent	TD-RRH8x20-25			
		3	rfs celwave	APXVSP18-C-A20 w/ Mount Pipe			
		3	rfs celwave	APXVTM14-C-120 w/ Mount Pipe			
	157.0	9	rfs celwave	ACU-A20-N			

Table 2 - Existing and Reserved Antenna and Cable Information

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)	Note
157.0	160.0	6	decibel	DB980H90E-M w/Mount Pipe	6	1 5/8	3
	157.0	1	tower mounts	Platform Mount [LP 713-1]	-	-	1
149.0	151.0	6	alcatel lucent	LGP21401	12 2 1	1 5/8 3/8 5/8	1
		6	alcatel lucent	LGP21901			
		6	powerwave technologies	7770.00 w/ Mount Pipe			
	149.0	3	ericsson	RRUS-11			
		3	powerwave technologies	P65-16-XLH-RR w/ Mount Pipe			
		1	raycap	DC6-48-60-18-8F			
	1	tower mounts	Platform Mount [LP 713-1]				

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)	Note
139.0	142.0	1	gps	GPS_A	1	1/2	3
		3	alcatel lucent	RRH2X40-AWS	1	1 5/8	2
		3	rymsa	RYMSA MG D3-800TX w/ Mount Pipe			
		1	rfs celwave	DB-T1-6Z-8AB-0Z			
		6	andrew	DB846F65ZAXY w/ Mount Pipe	12	1 5/8	1
		3	powerwave technologies	P65.16.XL.2 w/ Mount Pipe			
	3	rymsa	RYMSA MG D3-800TV w/ Mount Pipe				
	139.0	6	rfs celwave	FD9R6004/2C-3L	9	1 1/4	3
1	tower mounts	Platform Mount [LP 713-1]					
126.0	128.0	9	decibel	DB844H90E-XY w/Mount Pipe	9	1 1/4	3
	126.0	1	tower mounts	Platform Mount [LP 712-1]			
116.0	118.0	3	comm. components.	DTMA-1819-DD-12	-	-	3
		3	ems wireless	RR90-17-02DP w/ Mount Pipe			
		3	rfs celwave	APX16DWV-16DWV-S-E-ACU w/ Mount Pipe			
		3	rfs celwave	ATMAA1412D-1A20	1	1 5/8	2
		3	ericsson	ERICSSON AIR 21 B2A B4P w/ Mount Pipe			
		3	ericsson	ERICSSON AIR 21 B4A B2P w/ Mount Pipe			
	116.0	3	ericsson	KRY 112 144/1	12	1 5/8	1
1	tower mounts	Platform Mount [LP 712-1]					
84.0	84.0	1	gps	GPS_A	1	1/2	1
		1	tower mounts	Side Arm Mount [SO 701-1]			

- Notes:
 1) Existing Equipment
 2) Reserved Equipment
 3) Equipment To Be Removed

3) ANALYSIS PROCEDURE

Table 3 - Documents Provided

Document	Remarks	Reference	Source
4-GEOTECHNICAL REPORTS	Dr. Clarence Welty, 7/20/98	1104116	CCISITES
4-TOWER FOUNDATION DRAWINGS/DESIGN/SPECS	Towerkraft, 2622, 7/30/98	1104113	CCISITES
4-TOWER MANUFACTURER DRAWINGS	Valmont, 18917-69, 8/5/99	823122	CCISITES
4-TOWER REINFORCEMENT DESIGN/DRAWINGS/DATA	PJF, 41705-162, 8/30/09	1251715	CCISITES
4-TOWER REINFORCEMENT DESIGN/DRAWINGS/DATA	PJF, 37512-1595, 10/1/12	3332716	CCISITES

3.1) Analysis Method

tnxTower (version 6.1.4.1), a commercially available analysis software package, was used to create a three-dimensional model of the tower and calculate member stresses for various loading cases. Selected output from the analysis is included in Appendix A.

3.2) Assumptions

- 1) Tower and structures were built in accordance with the manufacturer's specifications.
- 2) The tower and structures have been maintained in accordance with the manufacturer's specification.
- 3) The configuration of antennas, transmission cables, mounts and other appurtenances are as specified in Tables 1 and 2 and the referenced drawings.
- 4) Monopole was reinforced in conformance with the referenced modification drawings.
- 5) Based on pictures, (3) Powerwave LGP21401 and (3) Powerwave LGP21901 at the 149' level have been considered to be shielded by the existing antennas.
- 6) Any extraneous mount pipes at 116' are to be removed when the reserved loading is installed.
- 7) Monopole will be reinforced in conformance with the proposed modification drawings.

This analysis may be affected if any assumptions are not valid or have been made in error. Paul J Ford and Company should be notified to determine the effect on the structural integrity of the tower.

4) ANALYSIS RESULTS

Table 4 - Section Capacity (Summary)

Section No.	Elevation (ft)	Component Type	Size	Critical Element	P (K)	SF*P_allow (K)	% Capacity	Pass / Fail
L1	160 - 111.33	Pole	TP31.29x19.6x0.25	1	-9.41	1252.07	90.0	Pass
L2	111.33 - 86.25	Pole	TP36.797x29.6683x0.3438	2	-16.63	2097.93	97.2	Pass
L3	86.25 - 80.75	Pole	TP38.1149x36.797x0.5054	3	-18.08	2587.75	85.1	Pass
L4	80.75 - 79	Pole	TP38.5342x38.1149x0.4221	4	-18.47	2619.68	85.4	Pass
L5	79 - 50.0833	Pole	TP44.787x38.5342x0.4063	5	-25.43	3018.50	98.4	Pass
L6	50.0833 - 36.33	Pole	TP48.088x44.787x0.5368	6	-27.69	3374.40	93.2	Pass
L7	36.33 - 32.25	Pole	TP48.2559x45.4135x0.5632	7	-33.10	3676.67	93.6	Pass
L8	32.25 - 15.5	Pole	TP52.278x48.2559x0.5525	8	-39.08	3918.65	96.7	Pass
L9	15.5 - 14.5	Pole	TP52.5182x52.278x0.6092	9	-39.48	4338.39	88.0	Pass
L10	14.5 - 0	Pole	TP56x52.5182x0.4902	10	-44.54	4432.50	92.3	Pass
							Summary	
						Pole (L5)	98.4	Pass
						Rating =	98.4	Pass

Table 5 - Tower Component Stresses vs. Capacity

Notes	Component	Elevation (ft)	% Capacity	Pass / Fail
1	Anchor Rods	0	86.1	Pass
1	Base Plate	0	69.3	Pass
1	Base Foundation	0	74.4	Pass
1	Base Foundation Soil Interaction	0	99.9	Pass

Structure Rating (max from all components) =	99.9%
---	--------------

Notes:

- 1) See additional documentation in "Appendix C – Additional Calculations" for calculations supporting the % capacity consumed.

4.1) Recommendations

See attached modification drawings.

APPENDIX A

TNXTOWER OUTPUT

Tower Input Data

There is a pole section.

This tower is designed using the TIA/EIA-222-F standard.

The following design criteria apply:

- 1) Tower is located in Fairfield County, Connecticut.
- 2) Basic wind speed of 85 mph.
- 3) Nominal ice thickness of 0.7500 in.
- 4) Ice thickness is considered to increase with height.
- 5) Ice density of 56.00 pcf.
- 6) A wind speed of 38 mph is used in combination with ice.
- 7) Temperature drop of 50 °F.
- 8) Deflections calculated using a wind speed of 50 mph.
- 9) A non-linear (P-delta) analysis was used.
- 10) Pressures are calculated at each section.
- 11) Stress ratio used in pole design is 1.333.
- 12) Local bending stresses due to climbing loads, feed line supports, and appurtenance mounts are not considered.

Options

Consider Moments - Legs Consider Moments - Horizontals Consider Moments - Diagonals Use Moment Magnification ✓ Use Code Stress Ratios ✓ Use Code Safety Factors - Guys ✓ Escalate Ice Always Use Max Kz Use Special Wind Profile Include Bolts In Member Capacity Leg Bolts Are At Top Of Section Secondary Horizontal Braces Leg Use Diamond Inner Bracing (4 Sided) Add IBC .6D+W Combination	Distribute Leg Loads As Uniform Assume Legs Pinned ✓ Assume Rigid Index Plate ✓ Use Clear Spans For Wind Area Use Clear Spans For KL/r Retension Guys To Initial Tension ✓ Bypass Mast Stability Checks ✓ Use Azimuth Dish Coefficients ✓ Project Wind Area of Appurt. Autocalc Torque Arm Areas SR Members Have Cut Ends Sort Capacity Reports By Component Triangulate Diamond Inner Bracing Use TIA-222-G Tension Splice Capacity Exemption	Treat Feedline Bundles As Cylinder Use ASCE 10 X-Brace Ly Rules Calculate Redundant Bracing Forces Ignore Redundant Members in FEA SR Leg Bolts Resist Compression All Leg Panels Have Same Allowable Offset Girt At Foundation ✓ Consider Feedline Torque Include Angle Block Shear Check <div style="background-color: #e0e0e0; text-align: center; padding: 2px;">Poles</div> ✓ Include Shear-Torsion Interaction Always Use Sub-Critical Flow Use Top Mounted Sockets
--	--	--

Tapered Pole Section Geometry

Section	Elevation	Section Length	Splice Length	Number of Sides	Top Diameter	Bottom Diameter	Wall Thickness	Bend Radius	Pole Grade
	ft	ft	ft		in	in	in	in	
L1	160.0000-111.3300	48.6700	4.67	12	19.6000	31.2900	0.2500	1.0000	A572-65 (65 ksi)
L2	111.3300-86.2500	29.7500	0.00	12	29.6683	36.7970	0.3438	1.3752	A572-65 (65 ksi)
L3	86.2500-80.7500	5.5000	0.00	12	36.7970	38.1149	0.5054	2.0217	Reinf 52.86 ksi (53 ksi)
L4	80.7500-79.0000	1.7500	0.00	12	38.1149	38.5342	0.4221	1.6884	Reinf 63.23 ksi (63 ksi)
L5	79.0000-50.0833	28.9167	0.00	12	38.5342	44.7870	0.4063	1.6252	A572-65 (65 ksi)
L6	50.0833-36.3300	13.7533	6.67	12	44.7870	48.0880	0.5368	2.1472	Reinf 53.12 ksi (53 ksi)
L7	36.3300-32.2500	10.7500	0.00	12	45.4135	48.2559	0.5632	2.2528	Reinf 53.15 ksi (53 ksi)
L8	32.2500-15.5000	16.7500	0.00	12	48.2559	52.2780	0.5525	2.2101	Reinf 53.24 ksi (53 ksi)
L9	15.5000-14.5000	1.0000	0.00	12	52.2780	52.5181	0.6092	2.4368	Reinf 53.27 ksi (53 ksi)
L10	14.5000-0.0000	14.5000		12	52.5181	56.0000	0.4902	1.9608	Reinf 63.25 ksi (63 ksi)

Tapered Pole Properties

Section	Tip Dia. in	Area in ²	I in ⁴	r in	C in	I/C in ³	J in ⁴	It/Q in ²	w in	w/t
L1	20.2914	15.5768	744.4315	6.9273	10.1528	73.3228	1508.4200	7.6664	4.5828	18.331
	32.3938	24.9872	3072.8897	11.1123	16.2082	189.5883	6226.5076	12.2979	7.7157	30.863
L2	31.8734	32.4633	3563.2008	10.4982	15.3682	231.8556	7220.0109	15.9774	7.0297	20.447
	38.0950	40.3550	6844.6814	13.0502	19.0608	359.0968	13869.1803	19.8615	8.9402	26.004
L3	38.0950	59.0639	9929.3009	12.9924	19.0608	520.9271	20119.4556	29.0695	8.5070	16.831
	39.4594	61.2088	11050.7840	13.4642	19.7435	559.7177	22391.8845	30.1251	8.8602	17.53
L4	39.4594	51.2318	9290.5395	13.4940	19.7435	470.5620	18825.1518	25.2147	9.0835	21.519
	39.8935	51.8017	9604.0722	13.6441	19.9607	481.1488	19460.4541	25.4952	9.1959	21.786
L5	39.8935	49.8822	9255.8639	13.6498	19.9607	463.7041	18754.8897	24.5505	9.2383	22.738
	46.3669	58.0627	14597.2613	15.8883	23.1997	629.2012	29578.0089	28.5767	10.9140	26.862
L6	46.3669	76.4863	19116.1459	15.8416	23.1997	823.9835	38734.4943	37.6442	10.5643	19.68
	49.7844	82.1921	23721.3157	17.0233	24.9096	952.2967	48065.8167	40.4524	11.4490	21.328
L7	48.8413	81.3362	20883.3728	16.0564	23.5242	887.7402	42315.3750	40.0312	10.6614	18.93
	49.9582	86.4909	25110.7480	17.0740	24.9965	1004.5687	50881.1834	42.5682	11.4232	20.283
L8	49.9582	84.8713	24651.5551	17.0778	24.9965	986.1985	49950.7340	41.7710	11.4518	20.726
	54.1222	92.0272	31427.6223	18.5177	27.0800	1160.5467	63680.8833	45.2930	12.5297	22.677
L9	54.1222	101.3564	34537.7645	18.4974	27.0800	1275.3968	69982.8744	49.8846	12.3778	20.318
	54.3708	101.8275	35021.5471	18.5834	27.2044	1287.3485	70963.1492	50.1164	12.4422	20.423
L10	54.3708	82.1249	28374.8700	18.6260	27.2044	1043.0250	57495.1794	40.4194	12.7611	26.032
	57.9755	87.6209	34461.3861	19.8725	29.0080	1187.9959	69828.1111	43.1243	13.6942	27.935

Feed Line/Linear Appurtenances - Entered As Area

Description	Face or Leg	Allow Shield	Component Type	Placement ft	Total Number		C _A A _A ft ² /ft	Weight klf
HB058-M12- XXXF(5/8")	A	No	CaAa (Out Of Face)	157.0000 - 0.0000	1	No Ice	0.0000	0.00
						1/2" Ice	0.0000	0.00
						1" Ice	0.0000	0.00
						2" Ice	0.0000	0.01
						4" Ice	0.0000	0.02
HB114-1-0813U4-M5J(1 1/4")	A	No	CaAa (Out Of Face)	157.0000 - 116.0000	1	No Ice	0.1540	0.00
						1/2" Ice	0.2540	0.00
						1" Ice	0.3540	0.00
						2" Ice	0.5540	0.01
						4" Ice	0.9540	0.03
HB114-1-0813U4-M5J(1 1/4")	A	No	CaAa (Out Of Face)	157.0000 - 116.0000	2	No Ice	0.0000	0.00
						1/2" Ice	0.0000	0.00
						1" Ice	0.0000	0.00
						2" Ice	0.0000	0.01
						4" Ice	0.0000	0.03
HB114-1-0813U4-M5J(1 1/4")	A	No	CaAa (Out Of Face)	116.0000 - 0.0000	3	No Ice	0.0000	0.00
						1/2" Ice	0.0000	0.00
						1" Ice	0.0000	0.00
						2" Ice	0.0000	0.01
						4" Ice	0.0000	0.03

LCF158-50JA-A0(1 5/8")	C	No	Inside Pole	149.0000 - 0.0000	12	No Ice	0.0000	0.00
						1/2" Ice	0.0000	0.00
						1" Ice	0.0000	0.00
						2" Ice	0.0000	0.00
						4" Ice	0.0000	0.00
FB-L98B-002-75000(3/8")	C	No	Inside Pole	149.0000 - 0.0000	2	No Ice	0.0000	0.00
						1/2" Ice	0.0000	0.00
						1" Ice	0.0000	0.00
						2" Ice	0.0000	0.00
						4" Ice	0.0000	0.00
WR-VG82ST-BRDA(5/8")	C	No	Inside Pole	149.0000 - 0.0000	1	No Ice	0.0000	0.00
						1/2" Ice	0.0000	0.00
						1" Ice	0.0000	0.00
						2" Ice	0.0000	0.00
						4" Ice	0.0000	0.00

HB158-1-08U8-S8J18(1-5/8)	B	No	CaAa (Out Of Face)	139.0000 - 0.0000	1	No Ice	0.1980	0.00
						1/2" Ice	0.2980	0.00

Description	Face or Leg	Allow Shield	Component Type	Placement ft	Total Number		C _A A _A ft ² /ft	Weight klf
561(1-5/8")	B	No	Inside Pole	139.0000 - 0.0000	12	1" Ice	0.3980	0.00
						2" Ice	0.5980	0.01
						4" Ice	0.9980	0.03
						No Ice	0.0000	0.00
						1/2" Ice	0.0000	0.00
						1" Ice	0.0000	0.00
						2" Ice	0.0000	0.00
4" Ice	0.0000	0.00						

MLE Hybrid 9Power/18Fiber RL 2(1 5/8)	A	No	CaAa (Out Of Face)	116.0000 - 0.0000	1	No Ice	0.1625	0.00
						1/2" Ice	0.2625	0.00
						1" Ice	0.3625	0.00
						2" Ice	0.5625	0.01
						4" Ice	0.9625	0.03
LDF7-50A(1-5/8")	A	No	Inside Pole	116.0000 - 0.0000	12	No Ice	0.0000	0.00
						1/2" Ice	0.0000	0.00
						1" Ice	0.0000	0.00
						2" Ice	0.0000	0.00
						4" Ice	0.0000	0.00

LDF4-50A(1/2")	A	No	Inside Pole	84.0000 - 0.0000	1	No Ice	0.0000	0.00
						1/2" Ice	0.0000	0.00
						1" Ice	0.0000	0.00
						2" Ice	0.0000	0.00
						4" Ice	0.0000	0.00

3/4" Flat Reinforcement	C	No	CaAa (Out Of Face)	12.2500 - 1.7500	1	No Ice	0.1250	0.00
						1/2" Ice	0.2361	0.00
						1" Ice	0.3472	0.00
						2" Ice	0.5694	0.00
						4" Ice	1.0139	0.00
3/4" Flat Reinforcement	C	No	CaAa (Out Of Face)	78.5000 - 77.0000	1	No Ice	0.1250	0.00
						1/2" Ice	0.2361	0.00
						1" Ice	0.3472	0.00
						2" Ice	0.5694	0.00
						4" Ice	1.0139	0.00
1" Flat Reinforcement	C	No	CaAa (Out Of Face)	52.2500 - 12.2500	1	No Ice	0.1667	0.00
						1/2" Ice	0.2778	0.00
						1" Ice	0.3889	0.00
						2" Ice	0.6111	0.00
						4" Ice	1.0556	0.00
1" Flat Reinforcement	C	No	CaAa (Out Of Face)	88.5000 - 78.5000	1	No Ice	0.1667	0.00
						1/2" Ice	0.2778	0.00
						1" Ice	0.3889	0.00
						2" Ice	0.6111	0.00
						4" Ice	1.0556	0.00

Feed Line/Linear Appurtenances Section Areas

Tower Sectio n	Tower Elevation ft	Face	A _R ft ²	A _F ft ²	C _A A _A In Face ft ²	C _A A _A Out Face ft ²	Weight K
L1	160.0000- 111.3300	A	0.000	0.000	0.000	7.073	0.23
		B	0.000	0.000	0.000	5.479	0.48
		C	0.000	0.000	0.000	0.000	0.05
L2	111.3300- 86.2500	A	0.000	0.000	0.000	4.076	0.37
		B	0.000	0.000	0.000	4.966	0.44
		C	0.000	0.000	0.000	0.375	0.03
L3	86.2500-80.7500	A	0.000	0.000	0.000	0.894	0.08
		B	0.000	0.000	0.000	1.089	0.10
		C	0.000	0.000	0.000	0.917	0.01
L4	80.7500-79.0000	A	0.000	0.000	0.000	0.284	0.03
		B	0.000	0.000	0.000	0.346	0.03
		C	0.000	0.000	0.000	0.292	0.00
L5	79.0000-50.0833	A	0.000	0.000	0.000	4.699	0.43
		B	0.000	0.000	0.000	5.726	0.51

Tower Section n	Tower Elevation ft	Face	A _R ft ²	A _F ft ²	C _A A _A In Face ft ²	C _A A _A Out Face ft ²	Weight K
L6	50.0833-36.3300	C	0.000	0.000	0.000	0.632	0.04
		A	0.000	0.000	0.000	2.235	0.20
		B	0.000	0.000	0.000	2.723	0.24
L7	36.3300-32.2500	C	0.000	0.000	0.000	2.292	0.02
		A	0.000	0.000	0.000	0.663	0.06
		B	0.000	0.000	0.000	0.808	0.07
L8	32.2500-15.5000	C	0.000	0.000	0.000	0.680	0.01
		A	0.000	0.000	0.000	2.722	0.25
		B	0.000	0.000	0.000	3.317	0.29
L9	15.5000-14.5000	C	0.000	0.000	0.000	2.792	0.02
		A	0.000	0.000	0.000	0.163	0.01
		B	0.000	0.000	0.000	0.198	0.02
L10	14.5000-0.0000	C	0.000	0.000	0.000	0.167	0.00
		A	0.000	0.000	0.000	2.356	0.22
		B	0.000	0.000	0.000	2.871	0.25
		C	0.000	0.000	0.000	1.688	0.02

Feed Line/Linear Appurtenances Section Areas - With Ice

Tower Section n	Tower Elevation ft	Face or Leg	Ice Thickness in	A _R ft ²	A _F ft ²	C _A A _A In Face ft ²	C _A A _A Out Face ft ²	Weight K
L1	160.0000-111.3300	A	0.887	0.000	0.000	0.000	15.179	0.70
		B		0.000	0.000	0.000	10.390	0.57
		C		0.000	0.000	0.000	0.000	0.05
L2	111.3300-86.2500	A	0.855	0.000	0.000	0.000	8.527	0.69
		B		0.000	0.000	0.000	9.417	0.52
		C		0.000	0.000	0.000	0.819	0.03
L3	86.2500-80.7500	A	0.838	0.000	0.000	0.000	1.816	0.15
		B		0.000	0.000	0.000	2.011	0.11
		C		0.000	0.000	0.000	1.941	0.01
L4	80.7500-79.0000	A	0.834	0.000	0.000	0.000	0.576	0.05
		B		0.000	0.000	0.000	0.638	0.04
		C		0.000	0.000	0.000	0.616	0.00
L5	79.0000-50.0833	A	0.812	0.000	0.000	0.000	9.397	0.76
		B		0.000	0.000	0.000	10.423	0.59
		C		0.000	0.000	0.000	1.384	0.04
L6	50.0833-36.3300	A	0.774	0.000	0.000	0.000	4.365	0.35
		B		0.000	0.000	0.000	4.853	0.28
		C		0.000	0.000	0.000	4.659	0.02
L7	36.3300-32.2500	A	0.753	0.000	0.000	0.000	1.295	0.10
		B		0.000	0.000	0.000	1.440	0.08
		C		0.000	0.000	0.000	1.382	0.01
L8	32.2500-15.5000	A	0.750	0.000	0.000	0.000	5.234	0.42
		B		0.000	0.000	0.000	5.829	0.34
		C		0.000	0.000	0.000	5.583	0.02
L9	15.5000-14.5000	A	0.750	0.000	0.000	0.000	0.313	0.03
		B		0.000	0.000	0.000	0.348	0.02
		C		0.000	0.000	0.000	0.333	0.00
L10	14.5000-0.0000	A	0.750	0.000	0.000	0.000	4.531	0.37
		B		0.000	0.000	0.000	5.046	0.29
		C		0.000	0.000	0.000	3.812	0.02

Feed Line Center of Pressure

Section	Elevation ft	CP _x in	CP _z in	CP _x Ice in	CP _z Ice in
L1	160.0000-111.3300	0.1433	-0.1146	0.2313	-0.2267
L2	111.3300-86.2500	0.2084	-0.0733	0.3353	-0.1532
L3	86.2500-80.7500	0.0348	0.0255	0.0120	0.0317
L4	80.7500-79.0000	0.0349	0.0255	0.0121	0.0318
L5	79.0000-50.0833	0.2059	-0.0709	0.3245	-0.1448
L6	50.0833-36.3300	0.0358	0.0262	0.0142	0.0330
L7	36.3300-32.2500	0.0359	0.0263	0.0143	0.0332

Section	Elevation	CP _x	CP _z	CP _x Ice	CP _z Ice
	ft	in	in	in	in
L8	32.2500-15.5000	0.0362	0.0264	0.0150	0.0333
L9	15.5000-14.5000	0.0363	0.0265	0.0152	0.0336
L10	14.5000-0.0000	0.0966	-0.0076	0.0909	-0.0093

Discrete Tower Loads

Description	Face or Leg	Offset Type	Offsets:			Azimuth Adjustment	Placement	C _{AA} Front	C _{AA} Side	Weight
			Horz	Lateral	Vert					
			ft	ft	ft	°	ft	ft ²	ft ²	K
TME-800MHz RRH w/ mount pipe	A	From Face	2.0000	0.00	0.00	158.0000	No Ice	3.5250	3.4935	0.07
			0.00				1/2" Ice	4.1044	4.1955	0.11
			0.00				1" Ice	4.5973	4.7751	0.15
							2" Ice	5.6293	5.9880	0.25
							4" Ice	7.8776	8.6287	0.56
TME-800MHz RRH w/ mount pipe	B	From Face	2.0000	0.00	0.00	158.0000	No Ice	3.5250	3.4935	0.07
			0.00				1/2" Ice	4.1044	4.1955	0.11
			0.00				1" Ice	4.5973	4.7751	0.15
							2" Ice	5.6293	5.9880	0.25
							4" Ice	7.8776	8.6287	0.56
TME-800MHz RRH w/ mount pipe	C	From Face	2.0000	0.00	0.00	158.0000	No Ice	3.5250	3.4935	0.07
			0.00				1/2" Ice	4.1044	4.1955	0.11
			0.00				1" Ice	4.5973	4.7751	0.15
							2" Ice	5.6293	5.9880	0.25
							4" Ice	7.8776	8.6287	0.56
TME-1900MHz RRH (65MHz) w/ Mount Pipe	A	From Face	2.0000	0.00	0.00	158.0000	No Ice	2.6979	2.7708	0.06
			0.00				1/2" Ice	2.9362	3.0111	0.08
			0.00				1" Ice	3.1832	3.2600	0.11
							2" Ice	3.7030	3.7837	0.18
							4" Ice	4.8463	4.9348	0.35
TME-1900MHz RRH (65MHz) w/ Mount Pipe	B	From Face	2.0000	0.00	0.00	158.0000	No Ice	2.6979	2.7708	0.06
			0.00				1/2" Ice	2.9362	3.0111	0.08
			0.00				1" Ice	3.1832	3.2600	0.11
							2" Ice	3.7030	3.7837	0.18
							4" Ice	4.8463	4.9348	0.35
TME-1900MHz RRH (65MHz) w/ Mount Pipe	C	From Face	2.0000	0.00	0.00	158.0000	No Ice	2.6979	2.7708	0.06
			0.00				1/2" Ice	2.9362	3.0111	0.08
			0.00				1" Ice	3.1832	3.2600	0.11
							2" Ice	3.7030	3.7837	0.18
							4" Ice	4.8463	4.9348	0.35
(2) Pipe Mount [PM 601-3]	C	None		0.00	0.00	158.0000	No Ice	4.3900	4.3900	0.20
							1/2" Ice	5.4800	5.4800	0.24
							1" Ice	6.5700	6.5700	0.28
							2" Ice	8.7500	8.7500	0.36
							4" Ice	13.1100	13.1100	0.53

APXVTM14-C-120 w/ Mount Pipe	A	From Face	4.0000	0.00	0.00	157.0000	No Ice	7.1342	4.9591	0.08
			0.00				1/2" Ice	7.6618	5.7544	0.13
			1.00				1" Ice	8.1830	6.4723	0.19
							2" Ice	9.2563	8.0099	0.34
							4" Ice	11.5262	11.4120	0.75
APXVTM14-C-120 w/ Mount Pipe	B	From Face	4.0000	0.00	0.00	157.0000	No Ice	7.1342	4.9591	0.08
			0.00				1/2" Ice	7.6618	5.7544	0.13
			1.00				1" Ice	8.1830	6.4723	0.19
							2" Ice	9.2563	8.0099	0.34
							4" Ice	11.5262	11.4120	0.75
APXVTM14-C-120 w/ Mount Pipe	C	From Face	4.0000	0.00	0.00	157.0000	No Ice	7.1342	4.9591	0.08
			0.00				1/2" Ice	7.6618	5.7544	0.13
			1.00				1" Ice	8.1830	6.4723	0.19
							2" Ice	9.2563	8.0099	0.34
							4" Ice	11.5262	11.4120	0.75
TD-RRH8x20-25	A	From Face	4.0000	0.00	0.00	157.0000	No Ice	4.7198	1.7027	0.07
			0.00				1/2" Ice	5.0138	1.9196	0.10
			1.00				1" Ice	5.3165	2.1453	0.13

Description	Face or Leg	Offset Type	Offsets:			Azimuth Adjustment	Placement	C _{AA} _{Front}	C _{AA} _{Side}	Weight
			Horz	Lateral	Vert					
			ft	ft	ft	°	ft	ft ²	ft ²	K
TD-RRH8x20-25	B	From Face	4.0000	0.00	157.0000	0.00	2" Ice	5.9478	2.6224	0.20
							4" Ice	7.3141	3.6805	0.40
							No Ice	4.7198	1.7027	0.07
							1/2" Ice	5.0138	1.9196	0.10
							1" Ice	5.3165	2.1453	0.13
							2" Ice	5.9478	2.6224	0.20
TD-RRH8x20-25	C	From Face	4.0000	0.00	157.0000	0.00	4" Ice	7.3141	3.6805	0.40
							No Ice	4.7198	1.7027	0.07
							1/2" Ice	5.0138	1.9196	0.10
							1" Ice	5.3165	2.1453	0.13
							2" Ice	5.9478	2.6224	0.20
							4" Ice	7.3141	3.6805	0.40
APXVSP18-C-A20 w/ Mount Pipe	A	From Face	4.0000	0.00	157.0000	0.00	No Ice	8.4975	6.9458	0.08
							1/2" Ice	9.1490	8.1266	0.15
							1" Ice	9.7672	9.0212	0.23
							2" Ice	11.0311	10.8440	0.41
							4" Ice	13.6786	14.8507	0.91
							No Ice	8.4975	6.9458	0.08
APXVSP18-C-A20 w/ Mount Pipe	B	From Face	4.0000	0.00	157.0000	0.00	1/2" Ice	9.1490	8.1266	0.15
							1" Ice	9.7672	9.0212	0.23
							2" Ice	11.0311	10.8440	0.41
							4" Ice	13.6786	14.8507	0.91
							No Ice	8.4975	6.9458	0.08
							1/2" Ice	9.1490	8.1266	0.15
APXVSP18-C-A20 w/ Mount Pipe	C	From Face	4.0000	0.00	157.0000	0.00	1" Ice	9.7672	9.0212	0.23
							2" Ice	11.0311	10.8440	0.41
							4" Ice	13.6786	14.8507	0.91
							No Ice	8.4975	6.9458	0.08
							1/2" Ice	9.1490	8.1266	0.15
							1" Ice	9.7672	9.0212	0.23
800 EXTERNAL NOTCH FILTER	A	From Face	4.0000	0.00	157.0000	0.00	2" Ice	11.0311	10.8440	0.41
							4" Ice	13.6786	14.8507	0.91
							No Ice	0.7701	0.3747	0.01
							1/2" Ice	0.8898	0.4647	0.02
							1" Ice	1.0181	0.5634	0.02
							2" Ice	1.3007	0.7868	0.04
800 EXTERNAL NOTCH FILTER	B	From Face	4.0000	0.00	157.0000	0.00	4" Ice	1.9696	1.3372	0.11
							No Ice	0.7701	0.3747	0.01
							1/2" Ice	0.8898	0.4647	0.02
							1" Ice	1.0181	0.5634	0.02
							2" Ice	1.3007	0.7868	0.04
							4" Ice	1.9696	1.3372	0.11
800 EXTERNAL NOTCH FILTER	C	From Face	4.0000	0.00	157.0000	0.00	No Ice	0.7701	0.3747	0.01
							1/2" Ice	0.8898	0.4647	0.02
							1" Ice	1.0181	0.5634	0.02
							2" Ice	1.3007	0.7868	0.04
							4" Ice	1.9696	1.3372	0.11
							No Ice	0.7701	0.3747	0.01
(3) ACU-A20-N	A	From Face	4.0000	0.00	157.0000	0.00	1/2" Ice	0.1210	0.1890	0.00
							1" Ice	0.1728	0.2506	0.00
							2" Ice	0.3025	0.3997	0.01
							4" Ice	0.6654	0.8015	0.04
							No Ice	0.0778	0.1361	0.00
							1/2" Ice	0.1210	0.1890	0.00
(3) ACU-A20-N	B	From Face	4.0000	0.00	157.0000	0.00	1" Ice	0.1728	0.2506	0.00
							2" Ice	0.3025	0.3997	0.01
							4" Ice	0.6654	0.8015	0.04
							No Ice	0.0778	0.1361	0.00
							1/2" Ice	0.1210	0.1890	0.00
							1" Ice	0.1728	0.2506	0.00
(3) ACU-A20-N	C	From Face	4.0000	0.00	157.0000	0.00	2" Ice	0.3025	0.3997	0.01
							4" Ice	0.6654	0.8015	0.04
							No Ice	0.0778	0.1361	0.00
							1/2" Ice	0.1210	0.1890	0.00
							1" Ice	0.1728	0.2506	0.00
							2" Ice	0.3025	0.3997	0.01
Platform Mount [LP 713-1]	A	None			157.0000	0.00	4" Ice	0.6654	0.8015	0.04
							No Ice	31.2700	31.2700	1.51
							1/2" Ice	39.6800	39.6800	1.93
							1" Ice	48.0900	48.0900	2.35
							2" Ice	64.9100	64.9100	3.19
							4" Ice	98.5500	98.5500	4.86

(2) 7770.00 w/ Mount Pipe	A	From Face	4.0000	0.00	149.0000	0.00	No Ice	6.1194	4.2543	0.06
							1/2" Ice	6.6258	5.0137	0.10

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C _{AA} _{Front}	C _{AA} _{Side}	Weight
			Horz	Lateral Vert					
				2.00					
(2) 7770.00 w/ Mount Pipe	B	From Face	4.0000	0.00	149.0000	1" Ice	7.1283	5.7109	0.16
						2" Ice	8.1643	7.1553	0.29
						4" Ice	10.3599	10.4117	0.66
						No Ice	6.1194	4.2543	0.06
						1/2" Ice	6.6258	5.0137	0.10
(2) 7770.00 w/ Mount Pipe	C	From Face	4.0000	0.00	149.0000	1" Ice	7.1283	5.7109	0.16
						2" Ice	8.1643	7.1553	0.29
						4" Ice	10.3599	10.4117	0.66
						No Ice	6.1194	4.2543	0.06
						1/2" Ice	6.6258	5.0137	0.10
P65-16-XLH-RR w/ Mount Pipe	A	From Face	4.0000	0.00	149.0000	1" Ice	7.1283	5.7109	0.16
						2" Ice	8.1643	7.1553	0.29
						4" Ice	10.3599	10.4117	0.66
						No Ice	8.6375	6.3625	0.08
						1/2" Ice	9.2903	7.5378	0.14
P65-16-XLH-RR w/ Mount Pipe	B	From Face	4.0000	0.00	149.0000	1" Ice	9.9098	8.4270	0.22
						2" Ice	11.1763	10.2390	0.39
						4" Ice	13.8289	14.0988	0.89
						No Ice	8.6375	6.3625	0.08
						1/2" Ice	9.2903	7.5378	0.14
P65-16-XLH-RR w/ Mount Pipe	C	From Face	4.0000	0.00	149.0000	1" Ice	9.9098	8.4270	0.22
						2" Ice	11.1763	10.2390	0.39
						4" Ice	13.8289	14.0988	0.89
						No Ice	8.6375	6.3625	0.08
						1/2" Ice	9.2903	7.5378	0.14
LGP21401	A	From Face	4.0000	0.00	149.0000	1" Ice	9.9098	8.4270	0.22
						2" Ice	11.1763	10.2390	0.39
						4" Ice	13.8289	14.0988	0.89
						No Ice	1.2880	0.2326	0.01
						1/2" Ice	1.4453	0.3134	0.02
LGP21401	B	From Face	4.0000	0.00	149.0000	1" Ice	1.6112	0.4028	0.03
						2" Ice	1.9690	0.6076	0.05
						4" Ice	2.7882	1.1210	0.14
						No Ice	1.2880	0.2326	0.01
						1/2" Ice	1.4453	0.3134	0.02
LGP21401	C	From Face	4.0000	0.00	149.0000	1" Ice	1.6112	0.4028	0.03
						2" Ice	1.9690	0.6076	0.05
						4" Ice	2.7882	1.1210	0.14
						No Ice	1.2880	0.2326	0.01
						1/2" Ice	1.4453	0.3134	0.02
LGP21401	A	From Face	4.0000	0.00	149.0000	1" Ice	1.6112	0.4028	0.03
						2" Ice	1.9690	0.6076	0.05
						4" Ice	2.7882	1.1210	0.14
						No Ice	0.0000	0.0000	0.01
						1/2" Ice	0.0000	0.0000	0.02
LGP21401	B	From Face	4.0000	0.00	149.0000	1" Ice	0.0000	0.0000	0.03
						2" Ice	0.0000	0.0000	0.05
						4" Ice	0.0000	0.0000	0.14
						No Ice	0.0000	0.0000	0.01
						1/2" Ice	0.0000	0.0000	0.02
LGP21401	C	From Face	4.0000	0.00	149.0000	1" Ice	0.0000	0.0000	0.03
						2" Ice	0.0000	0.0000	0.05
						4" Ice	0.0000	0.0000	0.14
						No Ice	0.0000	0.0000	0.01
						1/2" Ice	0.0000	0.0000	0.02
LGP21901	A	From Face	4.0000	0.00	149.0000	1" Ice	0.0000	0.0000	0.03
						2" Ice	0.0000	0.0000	0.05
						4" Ice	0.0000	0.0000	0.14
						No Ice	0.2695	0.1838	0.01
						1/2" Ice	0.3432	0.2483	0.01
LGP21901	B	From Face	4.0000	0.00	149.0000	1" Ice	0.4255	0.3216	0.01
						2" Ice	0.6160	0.4940	0.02
						4" Ice	1.1009	0.9425	0.07
						No Ice	0.2695	0.1838	0.01
						1/2" Ice	0.3432	0.2483	0.01

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C _{AA} _{Front}	C _{AA} _{Side}	Weight
			Horz	Lateral Vert					
				2.00					
LGP21901	C	From Face	4.0000	0.00	0.00	149.0000	1" Ice 0.4255	0.3216	0.01
			0.00				2" Ice 0.6160	0.4940	0.02
			2.00				4" Ice 1.1009	0.9425	0.07
							No Ice 0.2695	0.1838	0.01
							1/2" Ice 0.3432	0.2483	0.01
							1" Ice 0.4255	0.3216	0.01
							2" Ice 0.6160	0.4940	0.02
							4" Ice 1.1009	0.9425	0.07
LGP21901	A	From Face	4.0000	0.00	0.00	149.0000	No Ice 0.0000	0.0000	0.01
			0.00				1/2" Ice 0.0000	0.0000	0.01
			2.00				1" Ice 0.0000	0.0000	0.01
							2" Ice 0.0000	0.0000	0.02
							4" Ice 0.0000	0.0000	0.07
LGP21901	B	From Face	4.0000	0.00	0.00	149.0000	No Ice 0.0000	0.0000	0.01
			0.00				1/2" Ice 0.0000	0.0000	0.01
			2.00				1" Ice 0.0000	0.0000	0.01
							2" Ice 0.0000	0.0000	0.02
							4" Ice 0.0000	0.0000	0.07
LGP21901	C	From Face	4.0000	0.00	0.00	149.0000	No Ice 0.0000	0.0000	0.01
			0.00				1/2" Ice 0.0000	0.0000	0.01
			2.00				1" Ice 0.0000	0.0000	0.01
							2" Ice 0.0000	0.0000	0.02
							4" Ice 0.0000	0.0000	0.07
RRUS-11	A	From Face	4.0000	0.00	0.00	149.0000	No Ice 3.2486	1.3726	0.05
			0.00				1/2" Ice 3.4905	1.5510	0.07
			0.00				1" Ice 3.7411	1.7380	0.09
							2" Ice 4.2682	2.1381	0.15
							4" Ice 5.4260	3.0418	0.31
RRUS-11	B	From Face	4.0000	0.00	0.00	149.0000	No Ice 3.2486	1.3726	0.05
			0.00				1/2" Ice 3.4905	1.5510	0.07
			0.00				1" Ice 3.7411	1.7380	0.09
							2" Ice 4.2682	2.1381	0.15
							4" Ice 5.4260	3.0418	0.31
RRUS-11	C	From Face	4.0000	0.00	0.00	149.0000	No Ice 3.2486	1.3726	0.05
			0.00				1/2" Ice 3.4905	1.5510	0.07
			0.00				1" Ice 3.7411	1.7380	0.09
							2" Ice 4.2682	2.1381	0.15
							4" Ice 5.4260	3.0418	0.31
DC6-48-60-18-8F	C	From Face	4.0000	0.00	0.00	149.0000	No Ice 2.5667	2.5667	0.02
			0.00				1/2" Ice 2.7978	2.7978	0.04
			0.00				1" Ice 3.0377	3.0377	0.07
							2" Ice 3.5432	3.5432	0.13
							4" Ice 4.6580	4.6580	0.30
Platform Mount [LP 713-1]	A	None			0.00	149.0000	No Ice 31.2700	31.2700	1.51
							1/2" Ice 39.6800	39.6800	1.93
							1" Ice 48.0900	48.0900	2.35
							2" Ice 64.9100	64.9100	3.19
							4" Ice 98.5500	98.5500	4.86

RYMSA MG D3-800TX w/ Mount Pipe	A	From Face	4.0000	0.00	0.00	139.0000	No Ice 3.5960	3.4435	0.04
			0.00				1/2" Ice 4.0150	4.1655	0.07
			3.00				1" Ice 4.4296	4.8367	0.11
							2" Ice 5.3815	6.2291	0.21
							4" Ice 7.4264	9.2649	0.52
RYMSA MG D3-800TX w/ Mount Pipe	B	From Face	4.0000	0.00	0.00	139.0000	No Ice 3.5960	3.4435	0.04
			0.00				1/2" Ice 4.0150	4.1655	0.07
			3.00				1" Ice 4.4296	4.8367	0.11
							2" Ice 5.3815	6.2291	0.21
							4" Ice 7.4264	9.2649	0.52
RYMSA MG D3-800TX w/ Mount Pipe	C	From Face	4.0000	0.00	0.00	139.0000	No Ice 3.5960	3.4435	0.04
			0.00				1/2" Ice 4.0150	4.1655	0.07
			3.00				1" Ice 4.4296	4.8367	0.11
							2" Ice 5.3815	6.2291	0.21
							4" Ice 7.4264	9.2649	0.52
RRH2X40-AWS	A	From Face	4.0000	0.00	0.00	139.0000	No Ice 2.9764	1.5960	0.04

Description	Face or Leg	Offset Type	Offsets:			Azimuth Adjustment	Placement	C _{AA} _{Front}	C _{AA} _{Side}	Weight
			Horz	Lateral	Vert					
			ft	ft	ft	ft	ft ²	ft ²	K	
RRH2X40-AWS	B	From Face	0.00			1/2" Ice	3.2363	1.8239	0.06	
			3.00			1" Ice	3.5048	2.0605	0.08	
						2" Ice	4.0678	2.5596	0.14	
						4" Ice	5.2975	3.6614	0.29	
			4.0000	0.00	139.0000	No Ice	2.9764	1.5960	0.04	
RRH2X40-AWS	C	From Face	0.00			1/2" Ice	3.2363	1.8239	0.06	
			3.00			1" Ice	3.5048	2.0605	0.08	
						2" Ice	4.0678	2.5596	0.14	
						4" Ice	5.2975	3.6614	0.29	
			4.0000	0.00	139.0000	No Ice	2.9764	1.5960	0.04	
DB-T1-6Z-8AB-OZ	C	From Face	0.00			1/2" Ice	3.2363	1.8239	0.06	
			3.00			1" Ice	3.5048	2.0605	0.08	
						2" Ice	4.0678	2.5596	0.14	
						4" Ice	5.2975	3.6614	0.29	
			4.0000	0.00	139.0000	No Ice	5.6000	2.3333	0.04	
(2) DB846F65ZAXY w/ Mount Pipe	A	From Face	0.00			1/2" Ice	5.9154	2.5580	0.08	
			3.00			1" Ice	6.2395	2.7914	0.12	
						2" Ice	6.9136	3.2840	0.21	
						4" Ice	8.3654	4.3728	0.45	
			4.0000	0.00	139.0000	No Ice	7.2708	7.8208	0.05	
(2) DB846F65ZAXY w/ Mount Pipe	B	From Face	0.00			1/2" Ice	7.8773	9.0097	0.11	
			3.00			1" Ice	8.4838	9.9124	0.19	
						2" Ice	9.7244	11.8119	0.37	
						4" Ice	12.3252	15.9785	0.87	
			4.0000	0.00	139.0000	No Ice	7.2708	7.8208	0.05	
(2) DB846F65ZAXY w/ Mount Pipe	C	From Face	0.00			1/2" Ice	7.8773	9.0097	0.11	
			3.00			1" Ice	8.4838	9.9124	0.19	
						2" Ice	9.7244	11.8119	0.37	
						4" Ice	12.3252	15.9785	0.87	
			4.0000	0.00	139.0000	No Ice	7.2708	7.8208	0.05	
P65.16.XL.2 w/ Mount Pipe	A	From Face	0.00			1/2" Ice	7.8773	9.0097	0.11	
			3.00			1" Ice	8.4838	9.9124	0.19	
						2" Ice	9.7244	11.8119	0.37	
						4" Ice	12.3252	15.9785	0.87	
			4.0000	0.00	139.0000	No Ice	8.6375	5.7792	0.06	
P65.16.XL.2 w/ Mount Pipe	B	From Face	0.00			1/2" Ice	9.2903	6.9491	0.12	
			3.00			1" Ice	9.9098	7.8329	0.19	
						2" Ice	11.1763	9.6341	0.36	
						4" Ice	13.8289	13.4365	0.84	
			4.0000	0.00	139.0000	No Ice	8.6375	5.7792	0.06	
P65.16.XL.2 w/ Mount Pipe	C	From Face	0.00			1/2" Ice	9.2903	6.9491	0.12	
			3.00			1" Ice	9.9098	7.8329	0.19	
						2" Ice	11.1763	9.6341	0.36	
						4" Ice	13.8289	13.4365	0.84	
			4.0000	0.00	139.0000	No Ice	8.6375	5.7792	0.06	
RYMSA MG D3-800TV w/ Mount Pipe	A	From Face	0.00			1/2" Ice	9.2903	6.9491	0.12	
			3.00			1" Ice	9.9098	7.8329	0.19	
						2" Ice	11.1763	9.6341	0.36	
						4" Ice	13.8289	13.4365	0.84	
			4.0000	0.00	139.0000	No Ice	3.4773	3.3248	0.04	
RYMSA MG D3-800TV w/ Mount Pipe	B	From Face	0.00			1/2" Ice	3.8534	3.9564	0.07	
			3.00			1" Ice	4.2373	4.5989	0.11	
						2" Ice	5.1257	5.9338	0.20	
						4" Ice	7.0405	8.9033	0.51	
			4.0000	0.00	139.0000	No Ice	3.4773	3.3248	0.04	
RYMSA MG D3-800TV w/ Mount Pipe	C	From Face	0.00			1/2" Ice	3.8534	3.9564	0.07	
			3.00			1" Ice	4.2373	4.5989	0.11	
						2" Ice	5.1257	5.9338	0.20	
						4" Ice	7.0405	8.9033	0.51	
			4.0000	0.00	139.0000	No Ice	3.4773	3.3248	0.04	
(2) FD9R6004/2C-3L	A	From Face	0.00			1/2" Ice	3.8534	3.9564	0.07	
			3.00			1" Ice	4.2373	4.5989	0.11	
						2" Ice	5.1257	5.9338	0.20	
						4" Ice	7.0405	8.9033	0.51	
			4.0000	0.00	139.0000	No Ice	0.3665	0.0846	0.00	

Description	Face or Leg	Offset Type	Offsets:			Azimuth Adjustment	Placement	C _{AA} _{Front}	C _{AA} _{Side}	Weight
			Horz	Lateral	Vert					
			ft	ft	ft	°	ft	ft ²	ft ²	K
			0.00				1/2" Ice	0.4506	0.1362	0.01
			0.00				1" Ice	0.5433	0.1965	0.01
							2" Ice	0.7546	0.3430	0.02
							4" Ice	1.2808	0.7396	0.06
(2) FD9R6004/2C-3L	B	From Face	4.0000	0.00	139.0000		No Ice	0.3665	0.0846	0.00
			0.00				1/2" Ice	0.4506	0.1362	0.01
			0.00				1" Ice	0.5433	0.1965	0.01
							2" Ice	0.7546	0.3430	0.02
							4" Ice	1.2808	0.7396	0.06
(2) FD9R6004/2C-3L	C	From Face	4.0000	0.00	139.0000		No Ice	0.3665	0.0846	0.00
			0.00				1/2" Ice	0.4506	0.1362	0.01
			0.00				1" Ice	0.5433	0.1965	0.01
							2" Ice	0.7546	0.3430	0.02
							4" Ice	1.2808	0.7396	0.06
Platform Mount [LP 713-1]	A	None		0.00	139.0000		No Ice	31.2700	31.2700	1.51
							1/2" Ice	39.6800	39.6800	1.93
							1" Ice	48.0900	48.0900	2.35
							2" Ice	64.9100	64.9100	3.19
							4" Ice	98.5500	98.5500	4.86

ERICSSON AIR 21 B2A B4P w/ Mount Pipe	A	From Face	4.0000	0.00	116.0000		No Ice	6.8253	5.6424	0.11
			0.00				1/2" Ice	7.3471	6.4800	0.17
			2.00				1" Ice	7.8631	7.2567	0.23
							2" Ice	8.9261	8.8640	0.38
							4" Ice	11.1755	12.2932	0.81
ERICSSON AIR 21 B2A B4P w/ Mount Pipe	B	From Face	4.0000	0.00	116.0000		No Ice	6.8253	5.6424	0.11
			0.00				1/2" Ice	7.3471	6.4800	0.17
			2.00				1" Ice	7.8631	7.2567	0.23
							2" Ice	8.9261	8.8640	0.38
							4" Ice	11.1755	12.2932	0.81
ERICSSON AIR 21 B2A B4P w/ Mount Pipe	C	From Face	4.0000	0.00	116.0000		No Ice	6.8253	5.6424	0.11
			0.00				1/2" Ice	7.3471	6.4800	0.17
			2.00				1" Ice	7.8631	7.2567	0.23
							2" Ice	8.9261	8.8640	0.38
							4" Ice	11.1755	12.2932	0.81
ERICSSON AIR 21 B4A B2P w/ Mount Pipe	A	From Face	4.0000	0.00	116.0000		No Ice	6.8155	5.6334	0.11
			0.00				1/2" Ice	7.3373	6.4717	0.17
			2.00				1" Ice	7.8532	7.2478	0.23
							2" Ice	8.9160	8.8537	0.38
							4" Ice	11.1650	12.2804	0.81
ERICSSON AIR 21 B4A B2P w/ Mount Pipe	B	From Face	4.0000	0.00	116.0000		No Ice	6.8155	5.6334	0.11
			0.00				1/2" Ice	7.3373	6.4717	0.17
			2.00				1" Ice	7.8532	7.2478	0.23
							2" Ice	8.9160	8.8537	0.38
							4" Ice	11.1650	12.2804	0.81
ERICSSON AIR 21 B4A B2P w/ Mount Pipe	C	From Face	4.0000	0.00	116.0000		No Ice	6.8155	5.6334	0.11
			0.00				1/2" Ice	7.3373	6.4717	0.17
			2.00				1" Ice	7.8532	7.2478	0.23
							2" Ice	8.9160	8.8537	0.38
							4" Ice	11.1650	12.2804	0.81
KRY 112 144/1	A	From Face	4.0000	0.00	116.0000		No Ice	0.4083	0.2042	0.01
			0.00				1/2" Ice	0.4969	0.2733	0.01
			2.00				1" Ice	0.5941	0.3511	0.02
							2" Ice	0.8145	0.5326	0.03
							4" Ice	1.3590	0.9992	0.08
KRY 112 144/1	B	From Face	4.0000	0.00	116.0000		No Ice	0.4083	0.2042	0.01
			0.00				1/2" Ice	0.4969	0.2733	0.01
			2.00				1" Ice	0.5941	0.3511	0.02
							2" Ice	0.8145	0.5326	0.03
							4" Ice	1.3590	0.9992	0.08
KRY 112 144/1	C	From Face	4.0000	0.00	116.0000		No Ice	0.4083	0.2042	0.01
			0.00				1/2" Ice	0.4969	0.2733	0.01
			2.00				1" Ice	0.5941	0.3511	0.02
							2" Ice	0.8145	0.5326	0.03

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment °	Placement ft	C _{AA} Front ft ²	C _{AA} Side ft ²	Weight K	
			Horz Lateral ft	Vert ft						
Platform Mount [LP 712-1]	A	None			0.00	116.0000	4" Ice	1.3590	0.9992	0.08
							No Ice	24.5300	24.5300	1.34
							1/2" Ice	29.9400	29.9400	1.65
							1" Ice	35.3500	35.3500	1.96
							2" Ice	46.1700	46.1700	2.58
							4" Ice	67.8100	67.8100	3.82
*** GPS_A	C	From Face	4.0000 0.00 0.00	0.00	84.0000	No Ice	0.2975	0.2975	0.00	
Side Arm Mount [SO 701-1]	C	From Face	2.0000 0.00 0.00	0.00	84.0000	No Ice	0.8500	1.6700	0.07	
						1/2" Ice	1.1400	2.3400	0.08	
						1" Ice	1.4300	3.0100	0.09	
						2" Ice	2.0100	4.3500	0.12	
						4" Ice	3.1700	7.0300	0.18	

Tower Pressures - No Ice

$G_H = 1.690$

Section Elevation ft	z ft	K _Z	q _z ksf	A _G ft ²	F a c e	A _F ft ²	A _R ft ²	A _{leg} ft ²	Leg %	C _{AA} In Face ft ²	C _{AA} Out Face ft ²
L1 160.0000-111.3300	134.1093	1.493	0.03	103.201	A	0.000	103.201	103.201	100.00	0.000	7.073
					B	0.000	103.201	100.00	0.000	5.479	
					C	0.000	103.201	100.00	0.000	0.000	
L2 111.3300-86.2500	98.4183	1.366	0.03	70.626	A	0.000	70.626	70.626	100.00	0.000	4.076
					B	0.000	70.626	100.00	0.000	4.966	
					C	0.000	70.626	100.00	0.000	0.375	
L3 86.2500-80.7500	83.4839	1.304	0.02	17.167	A	0.000	17.167	17.167	100.00	0.000	0.894
					B	0.000	17.167	100.00	0.000	1.089	
					C	0.000	17.167	100.00	0.000	0.917	
L4 80.7500-79.0000	79.8734	1.287	0.02	5.589	A	0.000	5.589	5.589	100.00	0.000	0.284
					B	0.000	5.589	100.00	0.000	0.346	
					C	0.000	5.589	100.00	0.000	0.292	
L5 79.0000-50.0833	64.1800	1.209	0.02	100.391	A	0.000	100.391	100.391	100.00	0.000	4.699
					B	0.000	100.391	100.00	0.000	5.726	
					C	0.000	100.391	100.00	0.000	0.632	
L6 50.0833-36.3300	43.1252	1.079	0.02	53.222	A	0.000	53.222	53.222	100.00	0.000	2.235
					B	0.000	53.222	100.00	0.000	2.723	
					C	0.000	53.222	100.00	0.000	2.292	
L7 36.3300-32.2500	34.2823	1.011	0.02	16.224	A	0.000	16.224	16.224	100.00	0.000	0.663
					B	0.000	16.224	100.00	0.000	0.808	
					C	0.000	16.224	100.00	0.000	0.680	
L8 32.2500-15.5000	23.7633	1	0.02	70.164	A	0.000	70.164	70.164	100.00	0.000	2.722
					B	0.000	70.164	100.00	0.000	3.317	
					C	0.000	70.164	100.00	0.000	2.792	
L9 15.5000-14.5000	14.9996	1	0.02	4.367	A	0.000	4.367	4.367	100.00	0.000	0.163
					B	0.000	4.367	100.00	0.000	0.198	
					C	0.000	4.367	100.00	0.000	0.167	
L10 14.5000-0.0000	7.1725	1	0.02	65.563	A	0.000	65.563	65.563	100.00	0.000	2.356
					B	0.000	65.563	100.00	0.000	2.871	
					C	0.000	65.563	100.00	0.000	1.688	

Tower Pressure - With Ice

$G_H = 1.690$

Section Elevation ft	z ft	K_z	q_z ksf	t_z in	A_G ft ²	F a c e	A_F ft ²	A_R ft ²	A_{leg} ft ²	Leg %	C_{AA} In Face ft ²	C_{AA} Out Face ft ²
L1 160.0000- 111.3300	134.1093	1.493	0.01	0.8874	110.399	A	0.000	110.399	110.399	100.00	0.000	15.179
						B	0.000	110.399	110.399	100.00	0.000	10.390
						C	0.000	110.399	110.399	100.00	0.000	0.000
L2 111.3300- 86.2500	98.4183	1.366	0.00	0.8551	74.335	A	0.000	74.335	74.335	100.00	0.000	8.527
						B	0.000	74.335	74.335	100.00	0.000	9.417
						C	0.000	74.335	74.335	100.00	0.000	0.819
L3 86.2500- 80.7500	83.4839	1.304	0.00	0.8384	17.936	A	0.000	17.936	17.936	100.00	0.000	1.816
						B	0.000	17.936	17.936	100.00	0.000	2.011
						C	0.000	17.936	17.936	100.00	0.000	1.941
L4 80.7500- 79.0000	79.8734	1.287	0.00	0.8339	5.832	A	0.000	5.832	5.832	100.00	0.000	0.576
						B	0.000	5.832	5.832	100.00	0.000	0.638
						C	0.000	5.832	5.832	100.00	0.000	0.616
L5 79.0000- 50.0833	64.1800	1.209	0.00	0.8123	104.306	A	0.000	104.306	104.306	100.00	0.000	9.397
						B	0.000	104.306	104.306	100.00	0.000	10.423
						C	0.000	104.306	104.306	100.00	0.000	1.384
L6 50.0833- 36.3300	43.1252	1.079	0.00	0.7745	54.998	A	0.000	54.998	54.998	100.00	0.000	4.365
						B	0.000	54.998	54.998	100.00	0.000	4.853
						C	0.000	54.998	54.998	100.00	0.000	4.659
L7 36.3300- 32.2500	34.2823	1.011	0.00	0.7534	16.750	A	0.000	16.750	16.750	100.00	0.000	1.295
						B	0.000	16.750	16.750	100.00	0.000	1.440
						C	0.000	16.750	16.750	100.00	0.000	1.382
L8 32.2500- 15.5000	23.7633	1	0.00	0.7500	72.258	A	0.000	72.258	72.258	100.00	0.000	5.234
						B	0.000	72.258	72.258	100.00	0.000	5.829
						C	0.000	72.258	72.258	100.00	0.000	5.583
L9 15.5000- 14.5000	14.9996	1	0.00	0.7500	4.492	A	0.000	4.492	4.492	100.00	0.000	0.313
						B	0.000	4.492	4.492	100.00	0.000	0.348
						C	0.000	4.492	4.492	100.00	0.000	0.333
L10 14.5000- 0.0000	7.1725	1	0.00	0.7500	67.376	A	0.000	67.376	67.376	100.00	0.000	4.531
						B	0.000	67.376	67.376	100.00	0.000	5.046
						C	0.000	67.376	67.376	100.00	0.000	3.812

Tower Pressure - Service

$G_H = 1.690$

Section Elevation ft	z ft	K_z	q_z ksf	A_G ft ²	F a c e	A_F ft ²	A_R ft ²	A_{leg} ft ²	Leg %	C_{AA} In Face ft ²	C_{AA} Out Face ft ²
L1 160.0000- 111.3300	134.1093	1.493	0.01	103.20	A	0.000	103.201	103.201	100.00	0.000	7.073
					B	0.000	103.201	103.201	100.00	0.000	5.479
					C	0.000	103.201	103.201	100.00	0.000	0.000
L2 111.3300- 86.2500	98.4183	1.366	0.01	70.626	A	0.000	70.626	70.626	100.00	0.000	4.076
					B	0.000	70.626	70.626	100.00	0.000	4.966
					C	0.000	70.626	70.626	100.00	0.000	0.375
L3 86.2500- 80.7500	83.4839	1.304	0.01	17.167	A	0.000	17.167	17.167	100.00	0.000	0.894
					B	0.000	17.167	17.167	100.00	0.000	1.089
					C	0.000	17.167	17.167	100.00	0.000	0.917
L4 80.7500- 79.0000	79.8734	1.287	0.01	5.589	A	0.000	5.589	5.589	100.00	0.000	0.284
					B	0.000	5.589	5.589	100.00	0.000	0.346
					C	0.000	5.589	5.589	100.00	0.000	0.292
L5 79.0000- 50.0833	64.1800	1.209	0.01	100.39	A	0.000	100.391	100.391	100.00	0.000	4.699
					B	0.000	100.391	100.391	100.00	0.000	5.726
					C	0.000	100.391	100.391	100.00	0.000	0.632
L6 50.0833- 36.3300	43.1252	1.079	0.01	53.222	A	0.000	53.222	53.222	100.00	0.000	2.235
					B	0.000	53.222	53.222	100.00	0.000	2.723
					C	0.000	53.222	53.222	100.00	0.000	2.292
L7 36.3300- 32.2500	34.2823	1.011	0.01	16.224	A	0.000	16.224	16.224	100.00	0.000	0.663
					B	0.000	16.224	16.224	100.00	0.000	0.808
					C	0.000	16.224	16.224	100.00	0.000	0.680
L8 32.2500- 15.5000	23.7633	1	0.01	70.164	A	0.000	70.164	70.164	100.00	0.000	2.722
					B	0.000	70.164	70.164	100.00	0.000	3.317
					C	0.000	70.164	70.164	100.00	0.000	2.792
L9 15.5000- 0.0000	14.9996	1	0.01	4.367	A	0.000	4.367	4.367	100.00	0.000	0.163

Section Elevation ft	z ft	K _z	q _z ksf	A _G ft ²	F a c e	A _F ft ²	A _R ft ²	A _{leg} ft ²	Leg %	C _A A _A In Face ft ²	C _A A _A Out Face ft ²
14.5000					B	0.000	4.367		100.00	0.000	0.198
L10 14.5000- 0.0000	7.1725	1	0.01	65.563	C	0.000	4.367	65.563	100.00	0.000	0.167
					A	0.000	65.563		100.00	0.000	2.356
					B	0.000	65.563		100.00	0.000	2.871
					C	0.000	65.563		100.00	0.000	1.688

Load Combinations

Comb. No.	Description
1	Dead Only
2	Dead+Wind 0 deg - No Ice
3	Dead+Wind 30 deg - No Ice
4	Dead+Wind 60 deg - No Ice
5	Dead+Wind 90 deg - No Ice
6	Dead+Wind 120 deg - No Ice
7	Dead+Wind 150 deg - No Ice
8	Dead+Wind 180 deg - No Ice
9	Dead+Wind 210 deg - No Ice
10	Dead+Wind 240 deg - No Ice
11	Dead+Wind 270 deg - No Ice
12	Dead+Wind 300 deg - No Ice
13	Dead+Wind 330 deg - No Ice
14	Dead+Ice+Temp
15	Dead+Wind 0 deg+Ice+Temp
16	Dead+Wind 30 deg+Ice+Temp
17	Dead+Wind 60 deg+Ice+Temp
18	Dead+Wind 90 deg+Ice+Temp
19	Dead+Wind 120 deg+Ice+Temp
20	Dead+Wind 150 deg+Ice+Temp
21	Dead+Wind 180 deg+Ice+Temp
22	Dead+Wind 210 deg+Ice+Temp
23	Dead+Wind 240 deg+Ice+Temp
24	Dead+Wind 270 deg+Ice+Temp
25	Dead+Wind 300 deg+Ice+Temp
26	Dead+Wind 330 deg+Ice+Temp
27	Dead+Wind 0 deg - Service
28	Dead+Wind 30 deg - Service
29	Dead+Wind 60 deg - Service
30	Dead+Wind 90 deg - Service
31	Dead+Wind 120 deg - Service
32	Dead+Wind 150 deg - Service
33	Dead+Wind 180 deg - Service
34	Dead+Wind 210 deg - Service
35	Dead+Wind 240 deg - Service
36	Dead+Wind 270 deg - Service
37	Dead+Wind 300 deg - Service
38	Dead+Wind 330 deg - Service

Maximum Member Forces

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Force K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
L1	160 - 111.33	Pole	Max Tension	8	0.00	0.00	0.00
			Max. Compression	14	-19.79	-0.11	-0.30
			Max. Mx	5	-9.43	-676.00	-0.09
			Max. My	8	-9.41	-0.03	-680.27
			Max. Vy	5	22.20	-676.00	-0.09
			Max. Vx	8	22.36	-0.03	-680.27
L2	111.33 - 86.25	Pole	Max. Torque	11			1.15
			Max Tension	1	0.00	0.00	0.00
			Max. Compression	14	-29.71	-0.26	0.31
			Max. Mx	5	-16.65	-1489.31	0.04

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Force K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
L3	86.25 - 80.75	Pole	Max. My	2	-16.63	-0.08	1498.18
			Max. Vy	5	29.30	-1489.31	0.04
			Max. Vx	2	-29.46	-0.08	1498.18
			Max. Torque	11			1.11
			Max Tension	1	0.00	0.00	0.00
			Max. Compression	14	-31.42	-0.29	0.08
L4	80.75 - 79	Pole	Max. Mx	5	-18.10	-1652.97	-0.15
			Max. My	8	-18.08	-0.09	-1662.76
			Max. Vy	5	30.22	-1652.97	-0.15
			Max. Vx	2	-30.35	-0.09	1662.40
			Max. Torque	11			1.41
			Max Tension	1	0.00	0.00	0.00
L5	79 - 50.0833	Pole	Max. Compression	14	-31.88	-0.30	0.12
			Max. Mx	5	-18.49	-1706.08	-0.14
			Max. My	8	-18.47	-0.09	-1716.07
			Max. Vy	5	30.49	-1706.08	-0.14
			Max. Vx	2	-30.62	-0.09	1715.74
			Max. Torque	11			1.41
L6	50.0833 - 36.33	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	14	-39.83	-0.48	0.83
			Max. Mx	5	-25.44	-2644.62	0.06
			Max. My	2	-25.43	-0.15	2658.09
			Max. Vy	5	34.51	-2644.62	0.06
			Max. Vx	2	-34.64	-0.15	2658.09
L7	36.33 - 32.25	Pole	Max. Torque	11			1.41
			Max Tension	1	0.00	0.00	0.00
			Max. Compression	14	-42.37	-0.53	1.02
			Max. Mx	5	-27.70	-2892.47	0.12
			Max. My	2	-27.69	-0.17	2906.86
			Max. Vy	5	35.50	-2892.47	0.12
L8	32.25 - 15.5	Pole	Max. Vx	2	-35.62	-0.17	2906.86
			Max. Torque	11			1.38
			Max Tension	1	0.00	0.00	0.00
			Max. Compression	14	-48.57	-0.60	1.31
			Max. Mx	5	-33.11	-3282.96	0.21
			Max. My	2	-33.10	-0.19	3298.75
L9	15.5 - 14.5	Pole	Max. Vy	5	37.10	-3282.96	0.21
			Max. Vx	2	-37.23	-0.19	3298.75
			Max. Torque	11			1.39
			Max Tension	1	0.00	0.00	0.00
			Max. Compression	14	-55.64	-0.73	1.80
			Max. Mx	5	-39.48	-3962.22	0.37
L10	14.5 - 0	Pole	Max. My	2	-39.48	-0.23	3980.34
			Max. Vy	5	39.48	-3962.22	0.37
			Max. Vx	2	-39.60	-0.23	3980.34
			Max. Torque	11			1.39
			Max Tension	1	0.00	0.00	0.00
			Max. Compression	14	-61.26	-0.84	2.24
			Max. Mx	5	-44.54	-4548.46	0.51
			Max. My	2	-44.54	-0.27	4568.45
			Max. Vy	5	41.42	-4548.46	0.51
			Max. Vx	2	-41.54	-0.27	4568.45
			Max. Torque	11			1.39

Maximum Reactions

Location	Condition	Gov. Load Comb.	Vertical K	Horizontal, X K	Horizontal, Z K
Pole	Max. Vert	14	61.26	0.00	0.00
	Max. H _x	11	44.56	41.40	-0.00
	Max. H _z	2	44.56	-0.00	41.52
	Max. M _x	2	4568.45	-0.00	41.52
	Max. M _z	5	4548.46	-41.40	-0.00
	Max. Torsion	11	1.39	41.40	-0.00
	Min. Vert	1	44.56	0.00	0.00
	Min. H _x	5	44.56	-41.40	-0.00
	Min. H _z	8	44.56	-0.00	-41.52
	Min. M _x	8	-4567.45	-0.00	-41.52
	Min. M _z	11	-4547.92	41.40	-0.00
	Min. Torsion	5	-1.39	-41.40	-0.00

Tower Mast Reaction Summary

Load Combination	Vertical K	Shear _x K	Shear _z K	Overturning Moment, M _x kip-ft	Overturning Moment, M _z kip-ft	Torque kip-ft
Dead Only	44.56	0.00	0.00	-0.50	-0.26	0.00
Dead+Wind 0 deg - No Ice	44.56	0.00	-41.52	-4568.45	-0.27	0.24
Dead+Wind 30 deg - No Ice	44.56	20.70	-35.96	-3956.49	-2274.33	0.89
Dead+Wind 60 deg - No Ice	44.56	35.86	-20.76	-2284.52	-3939.10	1.31
Dead+Wind 90 deg - No Ice	44.56	41.40	0.00	-0.51	-4548.46	1.39
Dead+Wind 120 deg - No Ice	44.56	35.86	20.76	2283.50	-3939.11	1.09
Dead+Wind 150 deg - No Ice	44.56	20.70	35.96	3955.48	-2274.34	0.50
Dead+Wind 180 deg - No Ice	44.56	0.00	41.52	4567.45	-0.27	-0.24
Dead+Wind 210 deg - No Ice	44.56	-20.70	35.96	3955.48	2273.80	-0.91
Dead+Wind 240 deg - No Ice	44.56	-35.86	20.76	2283.50	3938.57	-1.33
Dead+Wind 270 deg - No Ice	44.56	-41.40	0.00	-0.51	4547.92	-1.39
Dead+Wind 300 deg - No Ice	44.56	-35.86	-20.76	-2284.52	3938.56	-1.07
Dead+Wind 330 deg - No Ice	44.56	-20.70	-35.96	-3956.48	2273.79	-0.48
Dead+Ice+Temp	61.26	0.00	0.00	-2.24	-0.84	0.00
Dead+Wind 0 deg+Ice+Temp	61.26	0.00	-9.85	-1135.84	-0.88	0.08
Dead+Wind 30 deg+Ice+Temp	61.26	4.91	-8.53	-983.97	-565.77	0.23
Dead+Wind 60 deg+Ice+Temp	61.26	8.51	-4.92	-569.07	-979.30	0.33
Dead+Wind 90 deg+Ice+Temp	61.26	9.83	-0.00	-2.30	-1130.66	0.34
Dead+Wind 120 deg+Ice+Temp	61.26	8.51	4.92	564.48	-979.30	0.25
Dead+Wind 150 deg+Ice+Temp	61.26	4.91	8.53	979.38	-565.77	0.10
Dead+Wind 180 deg+Ice+Temp	61.26	0.00	9.85	1131.25	-0.88	-0.08
Dead+Wind 210 deg+Ice+Temp	61.26	-4.91	8.53	979.38	564.01	-0.24
Dead+Wind 240 deg+Ice+Temp	61.26	-8.51	4.92	564.48	977.54	-0.33
Dead+Wind 270 deg+Ice+Temp	61.26	-9.83	-0.00	-2.30	1128.90	-0.34
Dead+Wind 300 deg+Ice+Temp	61.26	-8.51	-4.92	-569.07	977.53	-0.25
Dead+Wind 330 deg+Ice+Temp	61.26	-4.91	-8.53	-983.97	564.01	-0.10
Dead+Wind 0 deg - Service	44.56	0.00	-14.37	-1583.65	-0.27	0.08
Dead+Wind 30 deg - Service	44.56	7.16	-12.44	-1371.56	-788.41	0.31
Dead+Wind 60 deg - Service	44.56	12.41	-7.18	-792.08	-1365.37	0.46
Dead+Wind 90 deg - Service	44.56	14.33	0.00	-0.50	-1576.55	0.49
Dead+Wind 120 deg - Service	44.56	12.41	7.18	791.08	-1365.37	0.38
Dead+Wind 150 deg - Service	44.56	7.16	12.44	1370.56	-788.41	0.17
Dead+Wind 180 deg - Service	44.56	0.00	14.37	1582.65	-0.27	-0.08
Dead+Wind 210 deg - Service	44.56	-7.16	12.44	1370.56	787.87	-0.32
Dead+Wind 240 deg - Service	44.56	-12.41	7.18	791.08	1364.83	-0.46
Dead+Wind 270 deg - Service	44.56	-14.33	0.00	-0.50	1576.01	-0.49
Dead+Wind 300 deg - Service	44.56	-12.41	-7.18	-792.08	1364.83	-0.38
Dead+Wind 330 deg - Service	44.56	-7.16	-12.44	-1371.56	787.87	-0.17

Solution Summary

Load Comb.	Sum of Applied Forces			Sum of Reactions			% Error
	PX K	PY K	PZ K	PX K	PY K	PZ K	
1	0.00	-44.56	0.00	0.00	44.56	0.00	0.000%
2	0.00	-44.56	-41.52	-0.00	44.56	41.52	0.000%
3	20.70	-44.56	-35.96	-20.70	44.56	35.96	0.000%
4	35.86	-44.56	-20.76	-35.86	44.56	20.76	0.000%
5	41.40	-44.56	0.00	-41.40	44.56	-0.00	0.000%
6	35.86	-44.56	20.76	-35.86	44.56	-20.76	0.000%
7	20.70	-44.56	35.96	-20.70	44.56	-35.96	0.000%
8	0.00	-44.56	41.52	-0.00	44.56	-41.52	0.000%
9	-20.70	-44.56	35.96	20.70	44.56	-35.96	0.000%
10	-35.86	-44.56	20.76	35.86	44.56	-20.76	0.000%
11	-41.40	-44.56	0.00	41.40	44.56	-0.00	0.000%
12	-35.86	-44.56	-20.76	35.86	44.56	20.76	0.000%
13	-20.70	-44.56	-35.96	20.70	44.56	35.96	0.000%
14	0.00	-61.26	0.00	0.00	61.26	0.00	0.000%
15	0.00	-61.26	-9.85	-0.00	61.26	9.85	0.000%
16	4.91	-61.26	-8.53	-4.91	61.26	8.53	0.000%
17	8.51	-61.26	-4.92	-8.51	61.26	4.92	0.000%
18	9.83	-61.26	0.00	-9.83	61.26	0.00	0.000%
19	8.51	-61.26	4.92	-8.51	61.26	-4.92	0.000%
20	4.91	-61.26	8.53	-4.91	61.26	-8.53	0.000%
21	0.00	-61.26	9.85	-0.00	61.26	-9.85	0.000%
22	-4.91	-61.26	8.53	4.91	61.26	-8.53	0.000%
23	-8.51	-61.26	4.92	8.51	61.26	-4.92	0.000%
24	-9.83	-61.26	0.00	9.83	61.26	0.00	0.000%
25	-8.51	-61.26	-4.92	8.51	61.26	4.92	0.000%
26	-4.91	-61.26	-8.53	4.91	61.26	8.53	0.000%
27	0.00	-44.56	-14.37	0.00	44.56	14.37	0.000%
28	7.16	-44.56	-12.44	-7.16	44.56	12.44	0.000%
29	12.41	-44.56	-7.18	-12.41	44.56	7.18	0.000%
30	14.33	-44.56	0.00	-14.33	44.56	-0.00	0.000%
31	12.41	-44.56	7.18	-12.41	44.56	-7.18	0.000%
32	7.16	-44.56	12.44	-7.16	44.56	-12.44	0.000%
33	0.00	-44.56	14.37	0.00	44.56	-14.37	0.000%
34	-7.16	-44.56	12.44	7.16	44.56	-12.44	0.000%
35	-12.41	-44.56	7.18	12.41	44.56	-7.18	0.000%
36	-14.33	-44.56	0.00	14.33	44.56	-0.00	0.000%
37	-12.41	-44.56	-7.18	12.41	44.56	7.18	0.000%
38	-7.16	-44.56	-12.44	7.16	44.56	12.44	0.000%

Non-Linear Convergence Results

Load Combination	Converged?	Number of Cycles	Displacement Tolerance	Force Tolerance
1	Yes	4	0.00000001	0.00000001
2	Yes	4	0.00000001	0.00027806
3	Yes	5	0.00000001	0.00087395
4	Yes	5	0.00000001	0.00085192
5	Yes	4	0.00000001	0.00072537
6	Yes	5	0.00000001	0.00087636
7	Yes	5	0.00000001	0.00085947
8	Yes	4	0.00000001	0.00027808
9	Yes	5	0.00000001	0.00085636
10	Yes	5	0.00000001	0.00087803
11	Yes	4	0.00000001	0.00072532
12	Yes	5	0.00000001	0.00085344
13	Yes	5	0.00000001	0.00087068
14	Yes	4	0.00000001	0.00000001
15	Yes	5	0.00000001	0.00040826
16	Yes	5	0.00000001	0.00047593
17	Yes	5	0.00000001	0.00047375
18	Yes	5	0.00000001	0.00040675
19	Yes	5	0.00000001	0.00047459
20	Yes	5	0.00000001	0.00047423

21	Yes	5	0.00000001	0.00040771
22	Yes	5	0.00000001	0.00047331
23	Yes	5	0.00000001	0.00047409
24	Yes	5	0.00000001	0.00040614
25	Yes	5	0.00000001	0.00047320
26	Yes	5	0.00000001	0.00047494
27	Yes	4	0.00000001	0.00015172
28	Yes	5	0.00000001	0.00008391
29	Yes	5	0.00000001	0.00007960
30	Yes	4	0.00000001	0.00020235
31	Yes	5	0.00000001	0.00008429
32	Yes	5	0.00000001	0.00008109
33	Yes	4	0.00000001	0.00015174
34	Yes	5	0.00000001	0.00008048
35	Yes	5	0.00000001	0.00008461
36	Yes	4	0.00000001	0.00020229
37	Yes	5	0.00000001	0.00007985
38	Yes	5	0.00000001	0.00008323

Maximum Tower Deflections - Service Wind

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
L1	160 - 111.33	40.78	33	2.42	0.00
L2	116 - 86.25	20.25	27	1.84	0.00
L3	86.25 - 80.75	10.48	27	1.25	0.00
L4	80.75 - 79	9.08	27	1.17	0.00
L5	79 - 50.0833	8.66	27	1.14	0.00
L6	50.0833 - 36.33	3.35	27	0.61	0.00
L7	43 - 32.25	2.51	27	0.52	0.00
L8	32.25 - 15.5	1.43	27	0.42	0.00
L9	15.5 - 14.5	0.34	27	0.21	0.00
L10	14.5 - 0	0.29	27	0.20	0.00

Critical Deflections and Radius of Curvature - Service Wind

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
158.0000	TME-800MHz RRH w/ mount pipe	33	39.77	2.40	0.00	22044
157.0000	APXVTM14-C-120 w/ Mount Pipe	33	39.27	2.38	0.00	22044
149.0000	(2) 7770.00 w/ Mount Pipe	33	35.28	2.30	0.00	10020
139.0000	RYMSA MG D3-800TX w/ Mount Pipe	27	30.41	2.19	0.00	5247
116.0000	ERICSSON AIR 21 B2A B4P w/ Mount Pipe	27	20.25	1.84	0.00	2562
84.0000	GPS_A	27	9.90	1.22	0.00	3361

Maximum Tower Deflections - Design Wind

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
L1	160 - 111.33	117.33	8	6.95	0.01
L2	116 - 86.25	58.33	2	5.29	0.00
L3	86.25 - 80.75	30.21	2	3.62	0.00
L4	80.75 - 79	26.18	2	3.38	0.00
L5	79 - 50.0833	24.96	2	3.29	0.00
L6	50.0833 - 36.33	9.65	2	1.77	0.00
L7	43 - 32.25	7.23	2	1.49	0.00
L8	32.25 - 15.5	4.13	2	1.21	0.00
L9	15.5 - 14.5	0.97	2	0.59	0.00
L10	14.5 - 0	0.85	2	0.56	0.00

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
-------------	-----------------	------------------------	-----------------	-----------	------------

Critical Deflections and Radius of Curvature - Design Wind

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
158.0000	TME-800MHz RRR w/ mount pipe	8	114.44	6.89	0.01	7856
157.0000	APXVTM14-C-120 w/ Mount Pipe	8	113.00	6.86	0.01	7856
149.0000	(2) 7770.00 w/ Mount Pipe	8	101.54	6.62	0.01	3569
139.0000	RYMSA MG D3-800TX w/ Mount Pipe	2	87.54	6.29	0.01	1867
116.0000	ERICSSON AIR 21 B2A B4P w/ Mount Pipe	2	58.33	5.29	0.00	907
84.0000	GPS_A	2	28.53	3.52	0.00	1175

Compression Checks

Pole Design Data

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	F _a ksi	A in ²	Actual P K	Allow. P _a K	Ratio P P _a
L1	160 - 111.33 (1)	TP31.29x19.6x0.25	48.6700	0.0000	0.0	39.00	24.0842	-9.41	939.29	0.010
L2	111.33 - 86.25 (2)	TP36.797x29.6683x0.3438	29.7500	0.0000	0.0	39.00	40.3550	-16.63	1573.84	0.011
L3	86.25 - 80.75 (3)	TP38.1149x36.797x0.5054	5.5000	0.0000	0.0	31.72	61.2088	-18.08	1941.30	0.009
L4	80.75 - 79 (4)	TP38.5342x38.1149x0.4221	1.7500	0.0000	0.0	37.94	51.8017	-18.47	1965.25	0.009
L5	79 - 50.0833 (5)	TP44.787x38.5342x0.4063	28.9167	0.0000	0.0	39.00	58.0627	-25.43	2264.44	0.011
L6	50.0833 - 36.33 (6)	TP48.088x44.787x0.5368	13.7533	0.0000	0.0	31.87	79.4249	-27.69	2531.43	0.011
L7	36.33 - 32.25 (7)	TP48.2559x45.4135x0.5632	10.7500	0.0000	0.0	31.89	86.4909	-33.10	2758.19	0.012
L8	32.25 - 15.5 (8)	TP52.278x48.2559x0.5525	16.7500	0.0000	0.0	31.94	92.0272	-39.08	2939.72	0.013
L9	15.5 - 14.5 (9)	TP52.5182x52.278x0.6092	1.0000	0.0000	0.0	31.96	101.827	-39.48	3254.61	0.012
L10	14.5 - 0 (10)	TP56x52.5182x0.4902	14.5000	0.0000	0.0	37.95	87.6209	-44.54	3325.21	0.013

Pole Bending Design Data

Section No.	Elevation ft	Size	Actual M _x kip-ft	Actual f _{bx} ksi	Allow. F _{bx} ksi	Ratio f _{bx} F _{bx}	Actual M _y kip-ft	Actual f _{by} ksi	Allow. F _{by} ksi	Ratio f _{by} F _{by}
L1	160 - 111.33 (1)	TP31.29x19.6x0.25	680.27	46.36	39.00	1.189	0.00	0.00	39.00	0.000
L2	111.33 - 86.25 (2)	TP36.797x29.6683x0.3438	1498.18	50.07	39.00	1.284	0.00	0.00	39.00	0.000
L3	86.25 - 80.75 (3)	TP38.1149x36.797x0.5054	1662.76	35.65	31.72	1.124	0.00	0.00	31.72	0.000
L4	80.75 - 79 (4)	TP38.5342x38.1149x0.4221	1716.07	42.80	37.94	1.128	0.00	0.00	37.94	0.000
L5	79 - 50.0833 (5)	TP44.787x38.5342x0.4063	2658.08	50.69	39.00	1.300	0.00	0.00	39.00	0.000
L6	50.0833 - 36.33 (6)	TP48.088x44.787x0.5368	2906.86	39.24	31.87	1.231	0.00	0.00	31.87	0.000
L7	36.33 - 32.25 (7)	TP48.2559x45.4135x0.5632	3298.76	39.41	31.89	1.236	0.00	0.00	31.89	0.000
L8	32.25 - 15.5 (8)	TP52.278x48.2559x0.5525	3940.81	40.75	31.94	1.276	0.00	0.00	31.94	0.000
L9	15.5 - 14.5 (9)	TP52.5182x52.278x0.6092	3980.33	37.10	31.96	1.161	0.00	0.00	31.96	0.000
L10	14.5 - 0 (10)	TP56x52.5182x0.4902	4568.45	46.15	37.95	1.216	0.00	0.00	37.95	0.000

Pole Shear Design Data

Section No.	Elevation ft	Size	Actual V K	Actual f_v ksi	Allow. F_v ksi	Ratio $\frac{f_v}{F_v}$	Actual T kip-ft	Actual f_{vt} ksi	Allow. F_{vt} ksi	Ratio $\frac{f_{vt}}{F_{vt}}$
L1	160 - 111.33 (1)	TP31.29x19.6x0.25	22.36	0.93	26.00	0.073	0.06	0.00	26.00	0.000
L2	111.33 - 86.25 (2)	TP36.797x29.6683x0.3438	29.46	0.73	26.00	0.057	0.13	0.00	26.00	0.000
L3	86.25 - 80.75 (3)	TP38.1149x36.797x0.5054	30.35	0.50	21.14	0.048	0.13	0.00	21.14	0.000
L4	80.75 - 79 (4)	TP38.5342x38.1149x0.4221	30.62	0.59	25.29	0.047	0.13	0.00	25.29	0.000
L5	79 - 50.0833 (5)	TP44.787x38.5342x0.4063	34.64	0.60	26.00	0.047	0.20	0.00	26.00	0.000
L6	50.0833 - 36.33 (6)	TP48.088x44.787x0.5368	35.62	0.45	21.25	0.043	0.21	0.00	21.25	0.000
L7	36.33 - 32.25 (7)	TP48.2559x45.4135x0.5632	37.23	0.43	21.26	0.041	0.21	0.00	21.26	0.000
L8	32.25 - 15.5 (8)	TP52.278x48.2559x0.5525	39.46	0.43	21.30	0.041	0.22	0.00	21.30	0.000
L9	15.5 - 14.5 (9)	TP52.5182x52.278x0.6092	39.60	0.39	21.31	0.037	0.22	0.00	21.31	0.000
L10	14.5 - 0 (10)	TP56x52.5182x0.4902	41.54	0.47	25.30	0.038	0.24	0.00	25.30	0.000


Pole Interaction Design Data

Section No.	Elevation ft	Ratio P $\frac{P}{P_a}$	Ratio f_{bx} $\frac{f_{bx}}{F_{bx}}$	Ratio f_{by} $\frac{f_{by}}{F_{by}}$	Ratio f_v $\frac{f_v}{F_v}$	Ratio f_{vt} $\frac{f_{vt}}{F_{vt}}$	Comb. Stress Ratio	Allow. Stress Ratio	Criteria
L1	160 - 111.33 (1)	0.010	1.189	0.000	0.073	0.000	1.200 ✓	1.333	H1-3+VT ✓
L2	111.33 - 86.25 (2)	0.011	1.284	0.000	0.057	0.000	1.295 ✓	1.333	H1-3+VT ✓
L3	86.25 - 80.75 (3)	0.009	1.124	0.000	0.048	0.000	1.134 ✓	1.333	H1-3+VT ✓
L4	80.75 - 79 (4)	0.009	1.128	0.000	0.047	0.000	1.138 ✓	1.333	H1-3+VT ✓
L5	79 - 50.0833 (5)	0.011	1.300	0.000	0.047	0.000	1.312 ✓	1.333	H1-3+VT ✓
L6	50.0833 - 36.33 (6)	0.011	1.231	0.000	0.043	0.000	1.243 ✓	1.333	H1-3+VT ✓
L7	36.33 - 32.25 (7)	0.012	1.236	0.000	0.041	0.000	1.248 ✓	1.333	H1-3+VT ✓
L8	32.25 - 15.5 (8)	0.013	1.276	0.000	0.041	0.000	1.289 ✓	1.333	H1-3+VT ✓
L9	15.5 - 14.5 (9)	0.012	1.161	0.000	0.037	0.000	1.173 ✓	1.333	H1-3+VT ✓
L10	14.5 - 0 (10)	0.013	1.216	0.000	0.038	0.000	1.230 ✓	1.333	H1-3+VT ✓

Section Capacity Table



Section No.	Elevation ft	Component Type	Size	Critical Element	P K	SF* P_{allow} K	% Capacity	Pass Fail	
L1	160 - 111.33	Pole	TP31.29x19.6x0.25	1	-9.41	1252.07	90.0	Pass	
L2	111.33 - 86.25	Pole	TP36.797x29.6683x0.3438	2	-16.63	2097.93	97.2	Pass	
L3	86.25 - 80.75	Pole	TP38.1149x36.797x0.5054	3	-18.08	2587.75	85.1	Pass	
L4	80.75 - 79	Pole	TP38.5342x38.1149x0.4221	4	-18.47	2619.68	85.4	Pass	
L5	79 - 50.0833	Pole	TP44.787x38.5342x0.4063	5	-25.43	3018.50	98.4	Pass	
L6	50.0833 - 36.33	Pole	TP48.088x44.787x0.5368	6	-27.69	3374.40	93.2	Pass	
L7	36.33 - 32.25	Pole	TP48.2559x45.4135x0.5632	7	-33.10	3676.67	93.6	Pass	
L8	32.25 - 15.5	Pole	TP52.278x48.2559x0.5525	8	-39.08	3918.65	96.7	Pass	
L9	15.5 - 14.5	Pole	TP52.5182x52.278x0.6092	9	-39.48	4338.39	88.0	Pass	
L10	14.5 - 0	Pole	TP56x52.5182x0.4902	10	-44.54	4432.50	92.3	Pass	
							Summary		
							Pole (L5)	98.4	Pass
							RATING =	98.4	Pass

APPENDIX B
BASE LEVEL DRAWING



APPENDIX C
ADDITIONAL CALCULATIONS

Section	1	2	3	4	5	6	7	8	9	10
Length (ft)	48.6700	29.7500	1.7500	1.7500	28.9167	10.7500	16.7500	1.0000	14.5000	
Number of Sides	12	12	12	12	12	12	12	12	12	12
Thickness (in)	0.2500	0.3438	0.4220	0.5054	0.4063	0.5368	0.5632	0.6092	0.4902	0.4902
Socket Length (ft)	4.6700									
Top Dia (in)	19.6000	29.6683	38.1149	46.7970	38.5342	44.7870	48.2559	52.2780	52.2780	52.2780
Bot Dia (in)	31.2900	36.7970	38.5342	44.7870	44.7870	48.0880	48.2559	52.2780	52.2780	52.2780
Grade	A572-65	A572-65	Reinf 52.86 ksi	Reinf 63.23 ksi	A572-65	Reinf 53.12 ksi	Reinf 53.15 ksi	Reinf 53.24 ksi	Reinf 53.27 ksi	Reinf 53.27 ksi
Weight (K)	3.4	3.7	1.1	0.3	5.3	3.7	3.1	5.0	0.3	4.2



DESIGNED APPURTENANCE LOADING

TYPE	ELEVATION	TYPE	ELEVATION
TME-800MHz RRH w/ mount pipe	158	RRUS-11	149
TME-800MHz RRH w/ mount pipe	158	RRUS-11	149
TME-800MHz RRH w/ mount pipe	158	RRUS-11	149
TME-1900MHz RRH (65MHz) w/ Mount Pipe	158	DC6-48-60-18-8F	149
TME-1900MHz RRH (65MHz) w/ Mount Pipe	158	Platform Mount [LP 713-1]	149
TME-1900MHz RRH (65MHz) w/ Mount Pipe	158	RYMSA MG D3-800TX w/ Mount Pipe	139
TME-1900MHz RRH (65MHz) w/ Mount Pipe	158	RYMSA MG D3-800TX w/ Mount Pipe	139
TME-1900MHz RRH (65MHz) w/ Mount Pipe	158	RYMSA MG D3-800TX w/ Mount Pipe	139
(2) Pipe Mount [PM 601-3]	158	RRH2X40-AWS	139
APXVTM14-C-120 w/ Mount Pipe	157	RRH2X40-AWS	139
APXVTM14-C-120 w/ Mount Pipe	157	RRH2X40-AWS	139
APXVTM14-C-120 w/ Mount Pipe	157	DB-T1-6Z-8AB-0Z	139
TD-RRH8x20-25	157	(2) DB846F65ZAXY w/ Mount Pipe	139
TD-RRH8x20-25	157	(2) DB846F65ZAXY w/ Mount Pipe	139
TD-RRH8x20-25	157	(2) DB846F65ZAXY w/ Mount Pipe	139
APXVSP18-C-A20 w/ Mount Pipe	157	P65.16.XL.2 w/ Mount Pipe	139
APXVSP18-C-A20 w/ Mount Pipe	157	P65.16.XL.2 w/ Mount Pipe	139
APXVSP18-C-A20 w/ Mount Pipe	157	P65.16.XL.2 w/ Mount Pipe	139
800 EXTERNAL NOTCH FILTER	157	RYMSA MG D3-800TV w/ Mount Pipe	139
800 EXTERNAL NOTCH FILTER	157	RYMSA MG D3-800TV w/ Mount Pipe	139
800 EXTERNAL NOTCH FILTER	157	RYMSA MG D3-800TV w/ Mount Pipe	139
(3) ACU-A20-N	157	(2) FD9R6004/2C-3L	139
(3) ACU-A20-N	157	(2) FD9R6004/2C-3L	139
(3) ACU-A20-N	157	(2) FD9R6004/2C-3L	139
Platform Mount [LP 713-1]	157	Platform Mount [LP 713-1]	139
(2) 7770.00 w/ Mount Pipe	149	ERICSSON AIR 21 B2A B4P w/ Mount Pipe	116
(2) 7770.00 w/ Mount Pipe	149	ERICSSON AIR 21 B2A B4P w/ Mount Pipe	116
(2) 7770.00 w/ Mount Pipe	149	ERICSSON AIR 21 B2A B4P w/ Mount Pipe	116
P65-16-XLH-RR w/ Mount Pipe	149	ERICSSON AIR 21 B4A B2P w/ Mount Pipe	116
P65-16-XLH-RR w/ Mount Pipe	149	ERICSSON AIR 21 B4A B2P w/ Mount Pipe	116
P65-16-XLH-RR w/ Mount Pipe	149	ERICSSON AIR 21 B4A B2P w/ Mount Pipe	116
LGP21401	149	ERICSSON AIR 21 B4A B2P w/ Mount Pipe	116
LGP21401	149	ERICSSON AIR 21 B4A B2P w/ Mount Pipe	116
LGP21401	149	ERICSSON AIR 21 B4A B2P w/ Mount Pipe	116
LGP21401	149	KRY 112 144/1	116
LGP21901	149	KRY 112 144/1	116
LGP21901	149	KRY 112 144/1	116
LGP21901	149	Platform Mount [LP 712-1]	116
LGP21901	149	GPS_A	84
LGP21901	149	Side Arm Mount [SO 701-1]	84
LGP21901	149		
LGP21901	149		

MATERIAL STRENGTH

GRADE	Fy	Fu	GRADE	Fy	Fu
A572-65	65 ksi	80 ksi	Reinf 53.15 ksi	53 ksi	65 ksi
Reinf 52.86 ksi	53 ksi	65 ksi	Reinf 53.24 ksi	53 ksi	67 ksi
Reinf 63.23 ksi	63 ksi	80 ksi	Reinf 53.27 ksi	53 ksi	65 ksi
Reinf 53.12 ksi	53 ksi	67 ksi	Reinf 63.25 ksi	63 ksi	80 ksi

TOWER DESIGN NOTES

1. Tower is located in Fairfield County, Connecticut.
2. Tower designed for a 85 mph basic wind in accordance with the TIA/EIA-222-F Standard.
3. Tower is also designed for a 38 mph basic wind with 0.75 in ice. Ice is considered to increase in thickness with height.
4. Deflections are based upon a 50 mph wind.
5. TOWER RATING: 98.4%

Paul J Ford and Company
 250 E. Broad Street Suite 600
 Columbus, OH 43215
 Phone: 614.221.6679
 FAX: 614.448.4105

Job: **160' MP; Stamford, CT; BRG 2044 (A) 943097**
 Project: **PJF 37513-2318 (BU 806953)**
 Client: **Crown Castle** Drawn by: **Joshua Frybarger** App'd:
 Code: **TIA/EIA-222-F** Date: **04/09/14** Scale: **NTS**
 Path: T:\375 Crown Castle\2013\37513-2318 BU 806953\WO 726046 BU 806953 (7701)\37513-2318 BP A.en Dwg No. **E-1**

Stiffened or Unstiffened, UngROUTED, Circular Base Plate - Any Rod Material

TIA Rev F

Site Data

BU#: 806953
Site Name:
App #:
Pole Manufacturer: <i>Other</i>

Reactions

Moment:	4568	ft-kips
Axial:	45	kips
Shear:	42	kips

Anchor Rod Data

Qty:	20	
Diam:	2.25	in
Rod Material:	A615-J	
Strength (Fu):	100	ksi
Yield (Fy):	75	ksi
Bolt Circle:	64.48	in

If No stiffeners, Criteria: **AISC ASD** <-Only Applicable to Unstiffened Cases

Anchor Rod Results

Maximum Rod Tension:	167.8 Kips
Allowable Tension:	195.0 Kips
Anchor Rod Stress Ratio:	86.1% Pass

Stiffened

Service, ASD
Fty*ASIF

Plate Data

Diam:	70.48	in
Thick:	2.5	in
Grade:	60	ksi
Single-Rod B-eff:	9.00	in

Base Plate Results

Base Plate Stress:	33.8 ksi	Flexural Check
Allowable Plate Stress:	60.0 ksi	
Base Plate Stress Ratio:	56.4% Pass	

Stiffened

Service, ASD
0.75*Fy*ASIF
Y.L. Length:
N/A, Roark

Stiffener Data (Welding at both sides)

Config:	1	*
Weld Type:	Both	
Groove Depth:	0.375	in **
Groove Angle:	45	degrees
Fillet H. Weld:	0.375	in
Fillet V. Weld:	0.3125	in
Width:	6	in
Height:	18	in
Thick:	0.75	in
Notch:	0.75	in
Grade:	50	ksi
Weld str.:	70	ksi

Stiffener Results


Horizontal Weld :	68.6% Pass
Vertical Weld:	52.3% Pass
Plate Flex+Shear, fb/Fb+(fv/Fv)^2:	18.3% Pass
Plate Tension+Shear, ft/Ft+(fv/Fv)^2:	69.3% Pass
Plate Comp. (AISC Bracket):	69.2% Pass

Pole Results

Pole Punching Shear Check:	10.1% Pass
----------------------------	-------------------

Pole Data

Diam:	56	in
Thick:	0.4375	in
Grade:	65	ksi
# of Sides:	12	"0" IF Round
Fu	80	ksi
Reinf. Fillet Weld	0	"0" if None



Stress Increase Factor

ASIF:	1.333
-------	-------

* 0 = none, 1 = every bolt, 2 = every 2 bolts, 3 = 2 per bolt

** Note: for complete joint penetration groove welds the groove depth must be exactly 1/2 the stiffener thickness for calculation purposes

foundation loads


Tower or Pole Weight = **45** kips
 Total Horizontal Force = **42** kips
 Overturning Moment = **4568** ft-kips

soil properties

Safety factor against overturning = **1.5**
 Soil density = **125** pcf
 Allowable soil bearing = **20** ksf
 Depth to water table = **99** ft

mat dimensions

depth to bottom of footing = **3.5** ft
 Footing thickness = **5** ft
 Footing Width = **26** ft
 Footing Length = **26** ft
 Tower/Pole Center Offset = **0** ft



Summary of analysis results

Overturning Moment: (Stress Ratio = 0.999) **< CONTROLLING CRITERIA**

Calculated Overturning Moment = 4778 ft-kips
 Resisting Moment = 7176 ft-kips
 Factor of Safety against overturning = 1.502 > 1.5 okay

Rebar strength = $F_y = 60$ (ksi)
 minimum cover over rebar = **3** inches

Soil Bearing

(Stress Ratio = 0.143)
 Net Soil Bearing Resistance = 20 ksf
 Calculated Soil Bearing Pressure = 2.861 ksf < 20 ksf okay

Bending Moment

(Stress Ratio = 0.744)
 Ultimate Bending Moment Resistance = 3526 ft-kips
 Calculated Ultimate Bending Moment = 2624 ft-kips < 3526 ft-kips okay

Bending Shear

(Stress Ratio = 0.245)
 Ultimate Bending Shear Resistance = 1643 kips
 Calculated Ultimate Bending Shear = 403 kips < 1643 kips okay

MONOPOLE REINFORCEMENT AND RETROFIT PROJECT

BU NUMBER; SITE NAME

BU #806953; BRG 2044 (A) 943097

APP: 205537 REV. 1; WO: 736046

SITE ADDRESS

**69 GUINEA RD. (CAMP ROCKY CRAIG
STAMFORD, CONNECTICUT 06903
FAIRFIELD COUNTY**

PROJECT NOTES

1. DETAILED FIELD INFORMATION REGARDING INTERFERENCES AND/OR EXISTING FIELD CONDITIONS MAY BE AVAILABLE ON CROWN'S CCISITES AND FROM CONTRACTOR'S PRE-MOD MAPPING. IT IS THE CONTRACTOR'S RESPONSIBILITY TO FIELD VERIFY ALL EXISTING CONDITIONS AND DIMENSIONS AND COORDINATE WITH THE AVAILABLE SOURCES OF INFORMATION ABOVE AND WITH THE PROJECT PLANS BEFORE PROCEEDING WITH THE WORK. CONTRACTOR SHALL IMMEDIATELY REPORT ANY AND ALL DISCREPANCIES TO PAUL J. FORD AND COMPANY AND CROWN CASTLE FIELD PERSONNEL BEFORE PROCEEDING WITH THE WORK.
2. ALL STRUCTURAL BOLTS SHALL BE INSTALLED AND TIGHTENED TO THE PRETENSIONED CONDITION ACCORDING TO THE REQUIREMENTS OF THE AISC 'SPECIFICATION FOR STRUCTURAL JOINTS USING HIGH-STRENGTH BOLTS', DEC. 31, 2009.
3. ALL STRUCTURAL BOLTS SHALL BE FIELD INSPECTED ACCORDING TO THE REQUIREMENTS OF THE AISC 'SPECIFICATION FOR STRUCTURAL JOINTS USING HIGH-STRENGTH BOLTS', DEC. 31, 2009.
4. (A.) DTI'S REQUIRED: ALL AJAX BOLTS SHALL BE INSTALLED USING DIRECT TENSION INDICATORS (DTI'S) AND HARDENED WASHERS. ALL AJAX M20 BOLTS WITH SHEAR SLEEVES SHALL BE PRETENSIONED AND TIGHTENED UNTIL THE DIRECT TENSION INDICATOR (DTI) WASHERS SHOW THAT THE PROPER BOLT TENSION HAS BEEN REACHED. SEE NOTES AND DETAILS ON SHEET S-3 FOR REQUIREMENTS ON THE USE OF DIRECT TENSION INDICATOR (DTI) WASHERS WITH THE AJAX M20 BOLTS.

(B.) EFFECTIVE 5/30/2012: UNTIL FURTHER NOTICE, CROWN CASTLE WILL ACCEPT AJAX BOLTS TIGHTENED USING AISC "TURN-OF-NUT" METHOD. INSTALLERS SHALL FOLLOW CROWN GUIDELINES FOR AISC "TURN-OF-NUT" METHOD AND ALSO PROVIDE COMPLETE INSPECTION DOCUMENTATION IN THE PMI. PRIOR TO STARTING WORK, CONTRACTOR SHALL CONSULT WITH CROWN ENGINEERING TO DETERMINE WHETHER THIS POLICY IS STILL IN PLACE.

(C.) REQUIREMENT EFFECTIVE 04/20/2013, PER CROWN CASTLE DIRECTIVE: ANY AND ALL STRUCTURAL BOLTS THAT ARE TIGHTENED TO THE PRETENSIONED CONDITION USING THE AISC "TURN-OF-NUT" TENSIONING PROCEDURE (NON-TENSION CONTROLLED [NON-TC] BOLTS AND/OR BOLTS WITHOUT DTI'S INSTALLED) SHALL BE INSPECTED ONSITE BY AN INDEPENDENT THIRD-PARTY BOLT INSPECTOR, AS APPROVED BY CROWN. **THIS INSPECTION IS REQUIRED TO BE AN ONSITE FIELD INSPECTION.** THE THIRD-PARTY BOLT INSPECTOR SHALL FOLLOW THE PUBLISHED CROWN CASTLE INSPECTION PROCEDURE "MI NON-TC BOLT INSPECTION", DATED APRIL 2013. THE THIRD-PARTY BOLT INSPECTOR SHALL PREPARE A FULLY DOCUMENTED BOLT INSPECTION REPORT, AS SPECIFIED BY CROWN, AND SHALL SUBMIT A COPY OF THE BOLT INSPECTION REPORT TO THE MI INSPECTOR, THE EOR, AND TO CROWN CASTLE.

PROJECT CONTACTS:

MONOPOLE OWNER:

CROWN CASTLE
46 BROADWAY ALBANY, NY 12204
TSA: ANDREW BAZINET AT ANDREW.BAZINET@CROWNCastle.COM
PH: (585) 899-3442
MOD PM: EVA MORALES AT EVA.MORALES@CROWNCastle.COM
PH: (704) 405-6612

STRUCTURAL ENGINEER OF RECORD (EOR):

PAUL J. FORD AND COMPANY
250 EAST BROAD STREET, SUITE 600
COLUMBUS, OHIO 43215-3708
CONTACT: JOSH FRYBARGER AT JFRYBARGER@PJFWEB.COM
PHONE: 614-221-6679

DESIGN STANDARD

THIS REINFORCEMENT DESIGN IS BASED UPON THE REQUIREMENTS OF THE TIA/EIA-222-F-1996 STRUCTURAL STANDARD FOR ANTENNA SUPPORTING STRUCTURES AND ANTENNAS, USING A DESIGN BASIC WIND SPEED OF 85 MPH (FASTEST MILE) WITH NO ICE, 38 MPH WITH 3/4 INCH ICE AND 50 MPH SERVICE LOADS.

REFER TO THE POLE DESIGN AND ANTENNA LOADING DOCUMENTED IN THE PJF STRUCTURAL ANALYSIS FOR THIS SITE (PJF#37513-2318A), DATED 4-7-2014.

THIS PROJECT INCLUDES THE FOLLOWING REINFORCING ELEMENTS:

SHAFT REINFORCING

SHEET INDEX

SHEET NUMBER	DESCRIPTION
T-1	TITLE SHEET
S-1	GENERAL NOTES
S-2	GENERAL NOTES
S-3	AJAX BOLT DETAIL
S-4	MONOPOLE PROFILE
S-5	SHAFT REINF. CHART AND DETAIL
S-6	MI CHECKLIST



PAUL J. FORD AND COMPANY
STRUCTURAL ENGINEERS
250 East Broad Street · Suite 600 · Columbus, Ohio 43215
(614) 221-6679 www.pjfweb.com

CROWN CASTLE

46 BROADWAY ALBANY, NY 12204
PH: (585) 899-3442 FAX: (585) 899-3448

BU #806953; BRG 2044 (A) 943097
STAMFORD, CONNECTICUT
MONOPOLE REINFORCEMENT AND RETROFIT PROJECT

PROJECT No:

37513-2318A

DRAWN BY:
T.A.N.

CHECKED BY:
J.J.F.

APPROVED BY:

DATE:
4-7-2014

ISSUE DATE OF
PERMIT A: 4-7-2014

T-1

CROWN CASTLE PROJECT: BU #806953; BRG 2044 (A) 943097; STAMFORD, CONNECTICUT
MONOPOLE RETROFIT PROJECT MASTER NOTES DOCUMENT (REV. 2, 1/22/2009)

A. GENERAL NOTES

- IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO FIELD VERIFY ALL EXISTING CONDITIONS AND DIMENSIONS PRIOR TO FABRICATION AND CONSTRUCTION. THESE DRAWINGS WERE PREPARED FROM INFORMATION AND DOCUMENTS PROVIDED TO PAUL J. FORD & COMPANY BY CROWN CASTLE. THIS INFORMATION PROVIDED HAS NOT BEEN FIELD VERIFIED BY PAUL J. FORD & COMPANY FOR ACCURACY AND THEREFORE DISCREPANCIES BETWEEN THESE DRAWINGS AND ACTUAL SITE CONDITIONS SHOULD BE ANTICIPATED. ANY DISCREPANCIES AND/OR CHANGES BETWEEN THE INFORMATION CONTAINED IN THESE DRAWINGS AND THE ACTUAL VERIFIED SITE CONDITIONS SHALL BE IMMEDIATELY BROUGHT TO THE ATTENTION OF CROWN CASTLE AND PAUL J. FORD & COMPANY SO THAT ANY CHANGES AND/OR ADJUSTMENTS, IF NECESSARY, CAN BE MADE TO THE DESIGN AND DRAWINGS.
- THE EXISTING UNREINFORCED MONOPOLE STRUCTURE DOES NOT HAVE THE STRUCTURAL CAPACITY TO CARRY ALL OF THE ANTENNA AND PLATFORM LOADS SHOWN ON THESE DRAWINGS AT THE REQUIRED MINIMUM TIA/EIA-222-F BASIC WIND SPEEDS. DO NOT INSTALL ANY ADDITIONAL OR NEW ANTENNA AND PLATFORM LOADS UNTIL THE MONOPOLE REINFORCING SYSTEM IS COMPLETELY AND SUCCESSFULLY INSTALLED.
- IF MATERIALS, QUANTITIES, STRENGTHS OR SIZES INDICATED BY THE DRAWINGS OR SPECIFICATIONS ARE NOT IN AGREEMENT WITH THESE NOTES, THE BETTER QUALITY AND/OR GREATER QUANTITY, STRENGTH OR SIZE INDICATED, SPECIFIED OR NOTED SHALL BE PROVIDED.
- THIS STRUCTURE IS DESIGNED TO BE SELF-SUPPORTING AND STABLE AFTER THE INSTALLATION OF THE REINFORCING REPAIR SYSTEM HAS BEEN PROPERLY AND ADEQUATELY COMPLETED. IT IS THE CONTRACTOR'S SOLE RESPONSIBILITY TO INSURE THE SAFETY AND STABILITY OF THE MONOPOLE AND ITS COMPONENT PARTS DURING FIELD MODIFICATIONS. THIS INCLUDES, BUT IS NOT LIMITED TO, THE ADDITION OF WHATEVER TEMPORARY BRACING, GUYS OR TIE DOWNS THAT MAY BE NECESSARY. SUCH MATERIAL SHALL BE REMOVED AND SHALL REMAIN THE PROPERTY OF THE CONTRACTOR AFTER THE COMPLETION OF THE PROJECT. **IMPORTANT CUTTING, WELDING AND SAFETY GUIDELINES:** THE CONTRACTOR SHALL FOLLOW ALL CROWN CASTLE CUTTING, WELDING, FIRE PREVENTION AND SAFETY GUIDELINES. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL OBTAIN A COPY OF THE CURRENT CROWN CASTLE GUIDELINES FROM CROWN CASTLE. PER THE 12-01-2005 CROWN CASTLE DIRECTIVE: "ALL CUTTING AND WELDING ACTIVITIES SHALL BE CONDUCTED IN ACCORDANCE WITH CROWN CASTLE POLICY 'CUTTING AND WELDING PLAN' (DOC # ENG-PLN-10015) ON AN ONGOING BASIS THROUGHOUT THE ENTIRE LIFE OF THE PROJECT".
- THE STRUCTURAL CONTRACT DOCUMENTS DO NOT INDICATE THE METHOD OR MEANS OF CONSTRUCTION. THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK AND SHALL BE SOLELY RESPONSIBLE FOR ALL CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES. OBSERVATION VISITS TO THE SITE BY THE OWNER AND/OR THE ENGINEER SHALL NOT INCLUDE INSPECTIONS OF THE PROTECTIVE MEASURES OR THE CONSTRUCTION PROCEDURES.
- ANY SUPPORT SERVICES PERFORMED BY THE ENGINEER DURING CONSTRUCTION SHALL BE DISTINGUISHED FROM CONTINUOUS AND DETAILED INSPECTION SERVICES WHICH ARE FURNISHED BY THE INSPECTION/TESTING AGENCY. THESE SUPPORT SERVICES PERFORMED BY THE ENGINEER ARE SOLELY FOR THE PURPOSE OF ASSISTING IN QUALITY CONTROL AND IN ACHIEVING CONFORMANCE WITH CONTRACT DOCUMENTS. THEY DO NOT GUARANTEE CONTRACTOR'S PERFORMANCE AND SHALL NOT BE CONSTRUED AS SUPERVISION OF CONSTRUCTION.
- ALL MATERIALS AND EQUIPMENT FURNISHED WILL BE NEW AND OF GOOD QUALITY, FREE FROM FAULTS AND DEFECTS AND IN CONFORMANCE WITH THE CONTRACT DOCUMENTS. ANY AND ALL SUBSTITUTIONS MUST BE PROPERLY APPROVED AND AUTHORIZED IN WRITING BY THE OWNER AND ENGINEER PRIOR TO INSTALLATION. THE CONTRACTOR SHALL FURNISH SATISFACTORY EVIDENCE AS TO THE KIND AND QUALITY OF MATERIALS AND EQUIPMENT BEING SUBSTITUTED.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR INITIATING, MAINTAINING, AND SUPERVISING ALL SAFETY PRECAUTIONS AND PROGRAMS IN CONNECTION WITH THE WORK. THE CONTRACTOR IS RESPONSIBLE TO INSURE THAT THIS PROJECT AND RELATED WORK COMPLIES WITH ALL APPLICABLE LOCAL, STATE, AND FEDERAL SAFETY CODES AND REGULATIONS GOVERNING THIS WORK AS WELL AS CROWN CASTLE SAFETY GUIDELINES.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING ALL EXISTING AND NEW COAXIAL CABLES AND OTHER EQUIPMENT DURING CONSTRUCTION.
- ANY EXISTING ATTACHMENTS AND/OR PROJECTIONS ON THE POLE THAT MAY INTERFERE WITH THE INSTALLATION OF THE REINFORCING SYSTEM WILL HAVE TO BE REMOVED, AND/OR RELOCATED, AND/OR REPLACED AND RE-INSTALLED AFTER THE REINFORCING IS SUCCESSFULLY COMPLETED. THE CONTRACTOR SHALL IDENTIFY AND COORDINATE THESE ITEMS PRIOR TO CONSTRUCTION WITH THE OWNER, TESTING AGENCY, AND ENGINEER.
- ANY AND ALL EXISTING PLATFORMS THAT ARE LOCATED IN AREAS OF THE POLE SHAFT WHERE SHAFT REINFORCING MUST BE APPLIED SHALL BE TEMPORARILY REMOVED OR OTHERWISE SUPPORTED TO PERMIT NEW CONTINUOUS REINFORCEMENT TO BE ATTACHED. AFTER THE CONTRACTOR HAS SUCCESSFULLY INSTALLED THE MONOPOLE REINFORCEMENT SYSTEM, THE CONTRACTOR SHALL RE-INSTALL THE PLATFORMS. IN NO CASE SHALL ANY NEW AND/OR ADDITIONAL PLATFORMS AND/OR ANTENNAS AND/OR COAX CABLES AND/OR OTHER EQUIPMENT BE INSTALLED ON THE MONOPOLE UNTIL THE CONTRACTOR HAS SUCCESSFULLY COMPLETED THE INSTALLATION OF ALL OF THE REQUIRED STRUCTURAL REINFORCING SYSTEM COMPONENTS.

B. (SECTION NOT USED)

C. SPECIAL INSPECTION AND TESTING

- ALL WORK SHALL BE SUBJECT TO REVIEW AND OBSERVATION BY THE OWNER'S REPRESENTATIVE AND THE OWNER'S AUTHORIZED INDEPENDENT INSPECTION AND TESTING AGENCY. REFER TO CROWN CASTLE DOCUMENT ENG-SOW-10066 FOR SPECIFICATION.
- ANY SUPPORT SERVICES PERFORMED BY THE ENGINEER DURING CONSTRUCTION SHALL BE DISTINGUISHED FROM CONTINUOUS AND DETAILED INSPECTION SERVICES WHICH ARE FURNISHED BY OTHERS. THESE SUPPORT SERVICES PERFORMED BY THE ENGINEER ARE PERFORMED SOLELY FOR THE PURPOSE OF ASSISTING IN QUALITY CONTROL AND IN ACHIEVING CONFORMANCE WITH CONTRACT DOCUMENTS. THEY DO NOT GUARANTEE CONTRACTOR'S PERFORMANCE AND SHALL NOT BE CONSTRUED AS SUPERVISION OF CONSTRUCTION.
- OBSERVED DISCREPANCIES BETWEEN THE WORK AND THE CONTRACT DOCUMENTS SHALL BE CORRECTED BY THE CONTRACTOR AT NO ADDITIONAL COST.
- AN INDEPENDENT QUALIFIED INSPECTION/TESTING AGENCY SHALL BE SELECTED, RETAINED AND PAID FOR BY THE OWNER FOR THE SOLE PURPOSE OF INSPECTING, TESTING, DOCUMENTING, AND APPROVING ALL WELDING AND FIELD WORK PERFORMED BY THE CONTRACTOR.
 - ACCESS TO ANY PLACE WHERE WORK IS BEING DONE SHALL BE PERMITTED AT ALL TIMES.
 - THE INSPECTION AGENCY SHALL SO SCHEDULE THIS WORK AS TO CAUSE A MINIMUM OF INTERRUPTION TO, AND COORDINATE WITH, THE WORK IN PROGRESS. IT IS THE CONTRACTOR'S RESPONSIBILITY TO COORDINATE THE WORK SCHEDULE WITH THE TESTING AGENCY. THE CONTRACTOR SHALL ALLOW FOR ADEQUATE TIME AND ACCESS FOR THE TESTING AGENCY TO PERFORM THEIR DUTIES.
- THE INSPECTION AND TESTING AGENCY SHALL BE RESPONSIBLE TO PERFORM THE FOLLOWING SERVICES FOR THE OWNER. THE TESTING AGENCY SHALL INSPECT THE FOLLOWING ITEMS IN ACCORDANCE WITH THE CONSTRUCTION DRAWINGS. THE TESTING AGENCY SHALL INSPECT ITEMS ON THIS LIST AND OTHER ITEMS AS NECESSARY TO FULFILL THEIR RESPONSIBILITY. THE TESTING AGENCY SHALL UTILIZE EXPERIENCED, TRAINED INSPECTORS INCLUDING AWS CERTIFIED WELDING INSPECTORS (CWI). INSPECTORS SHALL HAVE THE TRAINING, CREDENTIALS, AND EXPERIENCE APPROPRIATE FOR AND COMMENSURATE WITH THE SCOPE AND TYPE OF INSPECTION WORK TO BE PERFORMED.
 - GENERAL:**
 - PERFORM CONTINUOUS ON-SITE OBSERVATION, INSPECTION, VERIFICATION, AND TESTING DURING THE TIME THE CONTRACTOR IS WORKING ON-SITE. AGENCY SHALL NOTIFY OWNER IMMEDIATELY WHEN FIELD PROBLEMS OR DISCREPANCIES OCCUR.
 - FOUNDATIONS, CONCRETE, AND SOIL PREPARATION - (NOT REQUIRED)**
 - CONCRETE TESTING PER ACI - (NOT REQUIRED)**
 - STRUCTURAL STEEL**
 - CHECK THE STEEL ON THE JOB WITH THE PLANS.
 - CHECK MILL CERTIFICATIONS.
 - CHECK GRADE OF STEEL MEMBERS, AND BOLTS FOR CONFORMANCE WITH DRAWINGS.
 - INSPECT STEEL MEMBERS FOR DISTORTION, EXCESSIVE RUST, FLAWS AND BURNED HOLES.
 - CALL FOR LABORATORY TEST REPORTS WHEN IN DOUBT.
 - CHECK STEEL MEMBERS FOR SIZES, SWEEP AND DIMENSIONAL TOLERANCES.
 - CHECK FOR SURFACE FINISH SPECIFIED, GALVANIZED.
 - CHECK BOLT TIGHTENING ACCORDING TO AISC "TURN OF THE NUT" METHOD.
 - WELDING: - (NOT REQUIRED)**
 - SPECIAL INSPECTION OF EXISTING SHAFT-TO-FLANGE WELD CONNECTIONS: - (NOT REQUIRED)**
- REPORTS:**
 - COMPILE AND PERIODICALLY SUBMIT DAILY INSPECTION REPORTS TO THE OWNER.

- THE INSPECTION PLAN OUTLINED HEREIN IS INTENDED AS A DESCRIPTION OF GENERAL AND SPECIFIC ITEMS OF CONCERN. IT IS NOT INTENDED TO BE ALL-INCLUSIVE. IT DOES NOT LIMIT THE TESTING AND INSPECTION AGENCY TO THE ITEMS LISTED. ADDITIONAL TESTING, INSPECTION, AND CHECKING MAY BE REQUIRED AND SHOULD BE ANTICIPATED. THE TESTING AGENCY SHALL USE THEIR PROFESSIONAL JUDGMENT AND KNOWLEDGE OF THE JOB SITE CONDITIONS AND THE CONTRACTOR'S PERFORMANCE TO DECIDE WHAT OTHER ITEMS REQUIRE ADDITIONAL ATTENTION. THE TESTING AGENCY'S JUDGMENT MUST PREVAIL ON ITEMS NOT SPECIFICALLY COVERED. ANY DISCREPANCIES AND PROBLEMS SHALL BE BROUGHT IMMEDIATELY TO THE OWNER'S ATTENTION. RESOLUTIONS ARE NOT TO BE MADE WITHOUT THE OWNER'S REVIEW AND SPECIFIC WRITTEN CONSENT. THE OWNER RESERVES THE RIGHT TO DETERMINE WHAT IS AN ACCEPTABLE RESOLUTION OF DISCREPANCIES AND PROBLEMS.
- AFTER EACH INSPECTION, THE TESTING AGENCY WILL PREPARE A WRITTEN ACCEPTANCE OR REJECTION WHICH WILL BE GIVEN TO THE CONTRACTOR AND FILED AS DAILY REPORTS TO THE OWNER. THIS WRITTEN ACTION WILL GIVE THE CONTRACTOR A LIST OF ITEMS TO BE CORRECTED, PRIOR TO CONTINUING CONSTRUCTION, AND/OR LOADING OF STRUCTURAL ITEMS.
- RESPONSIBILITY: THE TESTING AGENCY DOES NOT RELIEVE THE CONTRACTOR'S CONTRACTUAL OR STATUTORY OBLIGATIONS. THE CONTRACTOR HAS THE SOLE RESPONSIBILITY FOR ANY DEVIATIONS FROM THE OFFICIAL CONTRACT DOCUMENTS. THE TESTING AGENCY WILL NOT REPLACE THE CONTRACTOR'S QUALITY CONTROL PERSONNEL.



PAUL J. FORD AND COMPANY
STRUCTURAL ENGINEERS
250 East Broad Street · Suite 600 · Columbus, Ohio 43215
(614) 221-6679 www.pjfweb.com

CROWN CASTLE

46 BROADWAY ALBANY, NY 12204
PH: (585) 899-3442 FAX: (585) 899-3448

BU #806953; BRG 2044 (A) 943097
STAMFORD, CONNECTICUT
MONOPOLE REINFORCEMENT AND RETROFIT PROJECT

PROJECT No:
37513-2318A

DRAWN BY:
T.A.N.

CHECKED BY:
J.J.F.

APPROVED BY:

DATE:
4-7-2014

ISSUE DATE OF
PERMIT A: 4-7-2014

S-1

D. STRUCTURAL STEEL

1. STRUCTURAL STEEL MATERIALS, FABRICATION, DETAILING, AND WORKMANSHIP SHALL CONFORM TO THE LATEST EDITION OF THE FOLLOWING REFERENCE STANDARDS:
- A. BY THE AMERICAN INSTITUTE OF STEEL CONSTRUCTION (AISC):
- "SPECIFICATION FOR THE DESIGN, FABRICATION AND ERECTION OF STRUCTURAL STEEL FOR BUILDINGS."
 - "SPECIFICATION FOR STRUCTURAL JOINTS USING ASTM A325 OR A490 BOLTS," AS APPROVED BY THE RESEARCH COUNCIL ON STRUCTURAL CONNECTIONS OF THE ENGINEERING FOUNDATION.
 - "CODE OF STANDARD PRACTICE FOR STEEL BUILDINGS AND BRIDGES" (PARAGRAPH 4.2.1 SPECIFICALLY EXCLUDED).
- B. BY THE AMERICAN WELDING SOCIETY (AWS):
- "STRUCTURAL WELDING CODE - STEEL D1.1."
 - "SYMBOLS FOR WELDING AND NON-DESTRUCTIVE TESTING"
2. ANY MATERIAL OR WORKMANSHIP WHICH IS OBSERVED TO BE DEFECTIVE OR INCONSISTENT WITH THE CONTRACT DOCUMENTS SHALL BE CORRECTED, MODIFIED, OR REPLACED AT THE CONTRACTOR'S EXPENSE.
3. TIGHTEN ALL STRUCTURAL BOLTS, INCLUDING THE AJAX M20 BOLTS WITH SHEAR SLEEVES, ACCORDING TO THE REQUIREMENTS OF THE AISC "TURN OF THE NUT" METHOD. TIGHTEN BOLTS 1/3 TURN PAST THE SNUG TIGHT CONDITION AS DEFINED BY AISC.
4. WELDED CONNECTIONS SHALL CONFORM TO THE LATEST REVISED CODE OF THE AMERICAN WELDING SOCIETY, AWS D1.1. ALL WELD ELECTRODES SHALL BE E80XX UNLESS NOTED OTHERWISE ON THE DRAWINGS.
5. ALL WELDED CONNECTIONS SHALL BE MADE BY WELDERS CERTIFIED BY AWS. CONTRACTOR SHALL SUBMIT WELDERS' CERTIFICATION AND QUALIFICATION DOCUMENTATION TO THE OWNER'S TESTING AGENCY FOR REVIEW AND APPROVAL PRIOR TO CONSTRUCTION.
6. STRUCTURAL STEEL PLATES SHALL CONFORM TO ASTM A572 GRADE 65 (FY = 65 KSI MIN.) UNLESS NOTED OTHERWISE ON THE DRAWINGS.
7. SURFACES OF EXISTING STEEL SHALL BE PREPARED AS REQUIRED FOR FIELD WELDING PER AWS. SEE SECTION I NOTES REGARDING TOUCH-UP OF GALVANIZED SURFACES DAMAGED DURING TRANSPORTATION OR ERECTION AND ASSEMBLY AS WELL AS FIELD WELDING.
8. UNLESS OTHERWISE NOTED, ALL STEEL MEMBERS SHALL BE HOT-DIP GALVANIZED, AFTER FABRICATION, IN ACCORDANCE WITH ASTM A123. SEE SECTION J FOR FURTHER NOTES AND FOR EXCEPTIONS (IF ANY).
9. ALL WELDS SHALL BE VISUALLY INSPECTED BY THE OWNER'S APPROVED TESTING AGENCY. OTHER TESTS MAY ALSO BE PERFORMED ON THE WELDS BY THE TESTING AGENCY IN ORDER FOR THEM TO PERFORM THEIR DUTIES FOR THIS PROJECT. THE CONTRACTOR SHALL COOPERATE WITH THE TESTING AGENCY IN THEIR TESTING EFFORTS.
10. NO WELDING SHALL BE DONE TO THE EXISTING STRUCTURE WITHOUT THE PRIOR APPROVAL AND SUPERVISION OF THE TESTING AGENCY.
11. FIELD CUTTING OF STEEL:
- PRIOR TO ANY FIELD CUTTING, THE CONTRACTOR SHALL MARK THE CUT OUTLINES ON THE STEEL AND THE INSPECTION/TESTING AGENCY SHALL VERIFY PROPOSED LAYOUT, LOCATION, AND DIMENSIONS.
 - ANY REQUIRED CUTS IN THE STEEL SHALL BE CAREFULLY CUT BY MECHANICAL METHODS SUCH AS DRILLING, SAW CUTTING, AND GRINDING. THE CONTRACTOR IS RESPONSIBLE TO PREVENT ANY DAMAGE TO THE COAX CABLES, AND/OR OTHER EQUIPMENT AND/OR THE STRUCTURE, DURING THE CUTTING WORK. ANY DAMAGE TO THE COAX CABLES, AND/OR OTHER EQUIPMENT AND/OR THE STRUCTURE, RESULTING FROM THE CONTRACTOR'S ACTIVITIES SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE. THE INSPECTION/TESTING AGENCY SHALL CLOSELY AND CONTINUOUSLY MONITOR THIS ACTIVITY.
 - ALL REQUIRED CUTS SHALL BE CUT WITHIN THE DIMENSIONS SHOWN ON THE DRAWINGS. NO CUTS SHALL EXTEND BEYOND THE OUTLINE OF THE DIMENSIONS SHOWN ON THE DRAWINGS. ALL CUT EDGES SHALL BE GROUND SMOOTH AND DE-BURRED. CUT EDGES THAT ARE TO BE FIELD WELDED SHALL BE PREPARED FOR FIELD WELDING PER AWS D1.1 AND AS SHOWN ON THE DRAWINGS. IT MAY BE NECESSARY TO DRILL STARTER HOLES AS REQUIRED TO MAKE THE CUTS. THE INSPECTION/TESTING AGENCY SHALL CLOSELY AND CONTINUOUSLY MONITOR THIS ACTIVITY.

E. BASE PLATE GROUT - (NOT REQUIRED)**F. FOUNDATION WORK - (NOT REQUIRED)****G. CAST-IN-PLACE CONCRETE - (NOT REQUIRED)****H. EPOXY GROUTED REINFORCING ANCHOR RODS - (NOT REQUIRED)****I. TOUCH UP OF GALVANIZING**

- THE CONTRACTOR SHALL TOUCH UP ANY AND/OR ALL AREAS OF GALVANIZING ON THE EXISTING STRUCTURE OR NEW COMPONENTS THAT ARE DAMAGED OR ABRADED DURING CONSTRUCTION. GALVANIZED SURFACES DAMAGED DURING TRANSPORTATION OR ERECTION AND ASSEMBLY AS WELL AS ANY AND ALL ABRASIONS, CUTS, FIELD DRILLING, AND ALL FIELD WELDING SHALL BE TOUCHED UP WITH TWO (2) COATS OF ZRC-BRAND ZINC-RICH COLD GALVANIZING COMPOUND. FILM THICKNESS PER COAT SHALL BE: WET 3.0 MILS; DRY 1.5 MILS. APPLY PER ZRC (MANUFACTURER) RECOMMENDED PROCEDURES. CONTACT ZRC AT 1-800-831-3275 FOR PRODUCT INFORMATION.
- CONTRACTOR SHALL CLEAN AND PREPARE ALL FIELD WELDS ON GALVANIZED AND PRIME PAINTED SURFACES FOR TOUCH-UP COATING IN ACCORDANCE WITH AWS D1.1. THE OWNER'S TESTING AGENCY SHALL VERIFY THE PREPARED SURFACE PRIOR TO APPLICATION OF THE TOUCH-UP COATING.
- THE OWNER'S TESTING AGENCY SHALL TEST AND VERIFY THE COATING THICKNESS AFTER THE CONTRACTOR HAS APPLIED THE ZRC COLD GALVANIZING COMPOUND AND IT HAS SUFFICIENTLY DRIED. AREAS FOUND TO BE INADEQUATELY COATED, SHALL BE RE-COATED BY THE CONTRACTOR AND RE-TESTED BY THE TESTING AGENCY.

J. HOT DIP GALVANIZING

- HOT-DIP GALVANIZE ALL STRUCTURAL STEEL MEMBERS AND ALL STEEL ACCESSORIES, BOLTS, WASHERS, ETC. PER ASTM A123 OR PER ASTM A153, AS APPROPRIATE.
- PROPERLY PREPARE STEEL ITEMS FOR GALVANIZING.
- DRILL OR PUNCH WEEP AND/OR DRAINAGE HOLES AS REQUIRED.
- ALL GALVANIZING SHALL BE DONE AFTER FABRICATION IS COMPLETED AND PRIOR TO FIELD INSTALLATION.

K. PERPETUAL INSPECTION AND MAINTENANCE BY THE OWNER

- AFTER THE CONTRACTOR HAS SUCCESSFULLY COMPLETED THE INSTALLATION OF THE MONOPOLE REINFORCING SYSTEM AND THE WORK HAS BEEN ACCEPTED BY THE OWNER, THE OWNER WILL BE RESPONSIBLE FOR THE LONG TERM AND PERPETUAL INSPECTION AND MAINTENANCE OF THE POLE AND REINFORCING SYSTEM.
- THE MONOPOLE REINFORCING SYSTEM INDICATED IN THESE DOCUMENTS USES REINFORCING COMPONENTS THAT INVOLVE FIELD WELDING STEEL MEMBERS TO THE EXISTING GALVANIZED STEEL POLE STRUCTURE. THESE FIELD WELDED CONNECTIONS ARE SUBJECT TO CORROSION DAMAGE AND DETERIORATION IF THEY ARE NOT PROPERLY MAINTAINED AND COVERED WITH CORROSION PREVENTIVE COATING SUCH AS THE ZRC GALVANIZING COMPOUND SPECIFIED PREVIOUSLY. THE STRUCTURAL LOAD CARRYING CAPACITY OF THE REINFORCED POLE SYSTEM IS DEPENDENT UPON THE INSTALLED SIZE AND QUALITY, MAINTAINED SOUND CONDITION AND STRENGTH OF THESE FIELD WELDED CONNECTIONS. **ANY CORROSION OF, DAMAGE TO, FATIGUE, FRACTURE, AND/OR DETERIORATION OF THESE WELDS AND/OR THE CONNECTED COMPONENTS WILL RESULT IN THE LOSS OF STRUCTURAL LOAD CARRYING CAPACITY AND MAY LEAD TO FAILURE OF THE STRUCTURAL SYSTEM. THEREFORE, IT IS IMPERATIVE THAT THE OWNER REGULARLY INSPECTS, MAINTAINS, AND REPAIRS AS NECESSARY, ALL OF THESE WELDS, CONNECTIONS, AND COMPONENTS FOR THE LIFE OF THE STRUCTURE.**
- THE OWNER SHALL REFER TO TIA/EIA-222-F-1996, SECTION 14 AND ANNEX E FOR RECOMMENDATIONS FOR MAINTENANCE AND INSPECTION. THE FREQUENCY OF THE INSPECTION AND MAINTENANCE INTERVALS IS TO BE DETERMINED BY THE OWNER BASED UPON ACTUAL SITE AND ENVIRONMENTAL CONDITIONS. **PAUL J. FORD & COMPANY RECOMMENDS THAT A COMPLETE AND THOROUGH INSPECTION OF THE ENTIRE REINFORCED MONOPOLE STRUCTURAL SYSTEM BE PERFORMED YEARLY AND/OR AS FREQUENTLY AS CONDITIONS WARRANT.** ACCORDING TO TIA/EIA-222-F-1996 SECTION 14.1, NOTE 1: "IT IS RECOMMENDED THAT THE STRUCTURE BE INSPECTED AFTER SEVERE WIND AND/OR ICE STORMS OR OTHER EXTREME LOADING CONDITIONS".



PAUL J. FORD AND COMPANY
STRUCTURAL ENGINEERS
250 East Broad Street · Suite 600 · Columbus, Ohio 43215
(614) 221-6679 www.pjfweb.com

CROWN CASTLE

46 BROADWAY ALBANY, NY 12204
PH: (585) 899-3442 FAX: (585) 899-3448

BU #806953; BRG 2044 (A) 943097
STAMFORD, CONNECTICUT
MONOPOLE REINFORCEMENT AND RETROFIT PROJECT

PROJECT No:
37513-2318A

DRAWN BY:
T.A.N.

CHECKED BY:
J.J.F.

APPROVED BY:

DATE:
4-7-2014

ISSUE DATE OF
PERMIT A: 4-7-2014

S-2

AJAX BOLT NOTE SHEET: REV. 1.4, 5-20-2013

- NOTES:**
1. ALL STRUCTURAL BOLTS SHALL BE INSTALLED AND TIGHTENED TO THE PRETENSIONED CONDITION ACCORDING TO THE REQUIREMENTS OF THE AISC 'SPECIFICATION FOR STRUCTURAL JOINTS USING HIGH-STRENGTH BOLTS', DEC. 31, 2009.
 2. ALL STRUCTURAL BOLTS SHALL BE INSPECTED ACCORDING TO THE REQUIREMENTS OF THE AISC 'SPECIFICATION FOR STRUCTURAL JOINTS USING HIGH-STRENGTH BOLTS', DEC. 31, 2009.
 3. ALL AJAX M20 BOLTS WITH SHEAR SLEEVES SHALL BE PRETENSIONED AND TIGHTENED UNTIL THE DIRECT TENSION INDICATOR (DTI) WASHERS SHOW THAT THE PROPER BOLT TENSION HAS BEEN REACHED. SEE NOTES AND DETAIL BELOW FOR THE USE OF DIRECT TENSION INDICATOR (DTI) WASHERS WITH THE AJAX M20 BOLTS.
 4. ALL AJAX BOLTS SHALL BE INSTALLED USING DIRECT TENSION INDICATORS (DTI'S) AND HARDENED WASHERS. DTI'S SHALL BE THE SQUIRTER® STYLE, MADE TO ASTM F959 LATEST REVISION; AND HARDENED WASHERS SHALL CONFORM TO ASTM F436 AND HAVE A HARDNESS OF RC 38 OR HIGHER.

NOTES FOR AJAX M20 'ONE-SIDE' BOLTS WITH DIRECT TENSION INDICATORS (DTI'S):

DTI'S REQUIRED: DTI'S SHALL BE "SELF-INDICATING" SQUIRTER® STYLE DTI'S MADE WITH SILICONE EMBEDDED IN THEM, INSPECTED BY MEANS OF THE VISUAL EJECTION OF SILICONE AS THE DTI PROTRUSIONS COMPRESS. SQUIRTER® DTI'S SHALL BE CALIBRATED PER MANUFACTURER'S INSTRUCTIONS PRIOR TO USE.

THE DIRECT TENSION INDICATOR (DTI) WASHERS SHALL BE THE "SQUIRTER® STYLE" AS MANUFACTURED BY:

APPLIED BOLTING TECHNOLOGY PRODUCTS, INC.
1413 ROCKINGHAM ROAD BELLOWS FALLS, VERMONT, USA 05101
PHONE 1-800-552-1999
WEBSITE: WWW.APPLIEDBOLTING.COM

DISTRIBUTORS OF SQUIRTER® DTI'S:
[HTTP://WWW.APPLIEDBOLTING.COM/APPLIED-BOLTING-DISTRIBUTORS.HTML](http://WWW.APPLIEDBOLTING.COM/APPLIED-BOLTING-DISTRIBUTORS.HTML)

DTI: USE DIRECT TENSION INDICATOR (DTI) WASHERS COMPATIBLE WITH 20 MM (M20) NOMINAL A325 BOLTS FOR THE AJAX M20 BOLTS. DTI'S SHALL NOT BE HOT-DIP GALVANIZED. DTI'S SHALL BE MECHANICALLY GALVANIZED (MG) BY THE COLD MECHANICAL PROCESS ONLY AS PROVIDED BY THE DTI MANUFACTURER.


HARDENED WASHERS REQUIRED: USE A HARDENED WASHER FOR A 20 MM (M20) NOMINAL BOLT BETWEEN THE TOP OF THE DIRECT TENSION INDICATOR (DTI) WASHER AND THE NUT OF THE AJAX M20 BOLTS. HARDENED WASHERS SHALL CONFORM TO ASTM F436 AND HAVE A MINIMUM HARDNESS OF RC 38 OR HIGHER. THE HARDENED WASHERS SHALL BE MECHANICALLY GALVANIZED BY THE COLD MECHANICAL PROCESS. ALTERNATIVELY, CORRECTLY MADE HOT DIP GALVANIZED HARDENED FLAT WASHERS HAVING A MINIMUM HARDNESS OF RC 38 CAN BE USED; CONTRACTOR SHALL PROVIDE DOCUMENTATION OF WASHER SPECIFICATION AND HARDNESS.

NUT LUBRICATION REQUIRED: PROPERLY LUBRICATE THE THREADS OF THE NUT OF THE AJAX BOLT SO THAT IT CAN BE PROPERLY TIGHTENED WITHOUT GALLING AND/OR LOCKING UP ON THE BOLT THREADS. CONTRACTOR SHALL FOLLOW DTI MANUFACTURER INSTRUCTIONS FOR PROPER LUBRICATION AND TIGHTENING.

NOTE: COMPLETELY COMPRESSED DTI'S SHOWING NO VISIBLE REMAINING GAP ARE ACCEPTABLE. DTI WASHERS SHALL BE PLACED DIRECTLY AGAINST THE OUTER AJAX WASHER WITH THE DTI BUMPS FACING AWAY FROM THE AJAX WASHER. PLACE A HARDENED WASHER BETWEEN THE DTI AND THE AJAX NUT. THE DTI BUMPS SHALL BEAR AGAINST THE UNDERSIDE OF A HARDENED FLAT WASHER, NEVER DIRECTLY AGAINST THE NUT.

CONTRACTOR SHALL FOLLOW DTI MANUFACTURER'S INSTRUCTIONS FOR INSTALLATION, LUBRICATION, TIGHTENING AND INSPECTION.

INSPECTION REQUIRED: ALL AJAX BOLTS SHALL BE INSPECTED ACCORDING TO THE REQUIREMENTS OF THE AISC 'SPECIFICATION FOR STRUCTURAL JOINTS USING HIGH-STRENGTH BOLTS', DEC. 31, 2009, BY A QUALIFIED BOLT INSPECTOR. DURING INSTALLATION, THE BOLT INSPECTOR SHALL VERIFY AND DOCUMENT: THE SHOP-DRILLED AND FIELD-DRILLED HOLE SIZES; THE INSTALLATION OF THE AJAX BOLT ASSEMBLY, INCLUDING THE SHEAR SLEEVE PLACEMENT AND NUT LUBRICATION; AND THE CONTRACTOR'S TENSIONING PROCEDURE. IN ADDITION, ALL AJAX BOLTS AND DTI'S SHALL BE VISUALLY INSPECTED ACCORDING TO THE DTI MANUFACTURER'S INSTRUCTIONS. THE BOLT INSPECTOR SHALL PROVIDE COMPLETE PHOTO DOCUMENTATION OF ALL BOLTS AFTER TIGHTENING CLEARLY SHOWING THE CONDITION OF THE DTI'S.



NOTE: ALL SHOP AND FIELD DRILLED HOLES SHALL BE NOMINAL 30MM DIAMETER. THE MAXIMUM HOLE DIAMETER PERMITTED IS 1-3/16".

NOTE: ALL AJAX BOLTS, AJAX SPLIT WASHERS, AJAX WASHERS, AJAX NUTS, AND SHEAR SLEEVES SHALL BE HOT DIP GALVANIZED PER ASTM A123 OR A153 AS APPROPRIATE. SHEAR SLEEVES MAY BE COLD GALVANIZED OR ZINC PLATED.

TYPICAL AJAX BOLT DETAIL 1
S-3



PAUL J. FORD AND COMPANY
STRUCTURAL ENGINEERS
250 East Broad Street · Suite 600 · Columbus, Ohio 43215
(614) 221-6679 www.pjfweb.com

CROWN CASTLE

46 BROADWAY ALBANY, NY 12204
PH: (585) 899-3442 FAX: (585) 899-3448

BU #806953; BRG 2044 (A) 943097
STAMFORD, CONNECTICUT
MONOPOLE REINFORCEMENT AND RETROFIT PROJECT

PROJECT No:
37513-2318A

DRAWN BY:
T.A.N.

CHECKED BY:
J.J.F.

APPROVED BY:

DATE:
4-7-2014

ISSUE DATE OF
PERMIT A: 4-7-2014

S-3

POLE SPECIFICATIONS	
POLE SHAPE TYPE:	12-SIDED POLYGON
TAPER:	0.2401 IN/FT
SHAFT STEEL:	ASTM A572 GRADE 65
BASE PL STEEL:	ASTM A633 GR. E (60 KSI)
ANCHOR RODS:	2 1/4"Ø #18J ASTM A615 GRADE 75


SHAFT SECTION DATA					
SHAFT SECTION	SECTION LENGTH (FT)	PLATE THICKNESS (IN)	LAP SPLICE (IN)	DIAMETER ACROSS FLATS (IN)	
				@ TOP	@ BOTTOM
1	48.67	0.2500		19.6000	31.2900
2	42.75	0.3438	54.00	29.6683	39.9120
3	42.67	0.4063	69.00	37.8466	48.0880
4	43.00	0.4375	80.00	45.6745	56.0000

NOTE: DIMENSIONS SHOWN DO NOT INCLUDE GALVANIZING TOLERANCES

CONTRACTOR SHALL PROVIDE ASTM A36 SHIM PLATES BELOW SLIP JOINTS. THE SHIM PLATES SHALL BE PLACED BETWEEN THE NEW SHAFT REINFORCEMENT AND THE EXISTING POLE SHAFT FROM THE SLIP JOINT TO THE NEW SHAFT REINFORCEMENT SPLICE PLATE LOCATION AND A EXTRA LONG "SPLICE SHIM" SHALL BE PLACED BETWEEN THE NEW UPPER AND LOWER SHAFT REINFORCEMENT PLATES AT THE SHAFT REINFORCEMENT SPLICE PLATE LOCATION AND ALL TERMINATION POINTS, AS REQUIRED.

- MODIFICATIONS:
- (A) INSTALL NEW SHAFT REINFORCING. SEE CHART.
 - (B) REMOVE EXISTING MOUNT AND EQUIPMENT AT EL. 126'±

(B) EXISTING MOUNTS AND EQUIPMENT AT 126'± TO BE REMOVED AS PART OF THE MODIFICATION.



POLE ELEVATION 1 S-4

CROWN CASTLE US PATENT NOS 8,046,972; 8,156,712; 7,849,659; 8,424,269 AND PATENT PENDING

PAUL J. FORD AND COMPANY
STRUCTURAL ENGINEERS
250 East Broad Street · Suite 600 · Columbus, Ohio 43215
(614) 221-6679 www.pjfweb.com

CROWN CASTLE
46 BROADWAY ALBANY, NY 12204
PH: (585) 899-3442 FAX: (585) 899-3448

BU #806953; BRG 2044 (A) 943097
STAMFORD, CONNECTICUT
MONOPOLE REINFORCEMENT AND RETROFIT PROJECT

PROJECT No:
37513-2318A
DRAWN BY:
T.A.N.
CHECKED BY:
J.J.F.
APPROVED BY:
DATE:
4-7-2014

ISSUE DATE OF
PERMIT A: 4-7-2014

S-4

© Copyright 2014, by Paul J. Ford and Company. All Rights Reserved. This document and the data contained herein, is proprietary to Paul J. Ford and Company, issued in strict confidence and shall not, without the prior written permission of Paul J. Ford and Company, be reproduced, copied or used for any purpose other than the intended use for this specific project.

NEW CCI FLAT PLATE (65 KSI) REINFORCING SCHEDULE												
CROWN CASTLE CATALOG PART NUMBER	BOTTOM ELEVATION	TOP ELEVATION	FLAT # / DEGREE SEPARATION	ELEMENT	ELEMENT LENGTH	ELEMENT QUANTITY	MINIMUM AJAX BOLTS PER ELEMENT	MINIMUM TOTAL AJAX BOLT QUANTITY	TERMINATION BOLTS (BOTTOM)	TERMINATION BOLTS (TOP)	MAXIMUM INTERMEDIATE BOLT SPACING	ESTIMATED TOTAL STEEL WEIGHT
CCI-AFP-06010020	12' - 3"	32' - 3"	3, 7 & 11	1" x 6"	20' - 0"	3	31	93	10	10	16"	1225 LBS.
CCI-AFP-06010020	32' - 4"	52' - 4"	3, 7 & 11	1" x 6"	20' - 0"	3	31	93	10	10	16"	1225 LBS.
CCI-AFP-06010010	78' - 6"	88' - 6"	3, 7 & 11	1" x 6"	10' - 0"	3	23	69	10	10	16"	612 LBS.
											255	3062 LBS.

NOTES:


- 1.) AJAX BOLTS ARE TO BE 20mm DIAMETER WITH CORRESPONDING 29mm DIAMETER SLEEVE WITH MATCHING STEEL GRADE.
- 2.) ALL STEEL SHALL BE HOT-DIP GALVANIZED AFTER FABRICATION IN ACCORDANCE WITH ASTM A123. ALTERNATIVELY, ALL NEW STIFFENER PLATE STEEL REINFORCING MAY BE COLD GALVANIZED AS FOLLOWS: APPLY A MINIMUM OF TWO COATS OF ZRC-BRAND ZINC-RICH COLD GALVANIZING COMPOUND. FILM THICKNESS PER COAT SHALL BE: WET 3.0 MILS; DRY 1.5 MILS. APPLY PER ZRC (MANUFACTURER) RECOMMENDED PROCEDURES. CONTACT ZRC AT 1-800-831-3275 FOR PRODUCT INFORMATION.
- 3.) ALL REINFORCING SHALL BE ASTM A572 GR. 65.
- 4.) WELDS ARE ASSUMED E80XX OR GREATER. TERMINATION WELDS SHALL BE 3/8" FILLET WELDS.
- 5.) HOLES FOR AJAX BOLTS AND SHEAR SLEEVES ARE 30mm UNLESS NOTED OTHERWISE.
- 6.) ALL SHIMS SHALL BE ASTM A-36.

SPlice PLATE INSTALLATION CHART								
ELEVATION	FLAT PLATE THICKNESS	FLAT PLATE WIDTH	FLAT PLATE LENGTH	FLAT PLATE QUANTITY	WELD LENGTH PER SIDE	TOTAL WELD LENGTH	AJAX BOLTS PER SPLICE*	TOTAL STEEL WEIGHT
32' - 3"	1"	8"	5' - 7"	3	-	-	20	457 LBS.
							0"	457 LBS.

* BOLTS INCLUDED IN THE TOTAL QUANTITY LISTED IN THE FLAT PLATE INSTALLATION CHART.

NEW SHIM CHART				
SHIM QUANTITY	SHIM WIDTH	SHIM LENGTH	SHIM THICKNESS	HOLE DIAMETER
21	4"	4"	1/4"	1-1/4"
39	4"	4"	1/16"	1-1/4"

SHIM QUANTITIES ARE APPROXIMATE AND ARE FOR BIDDING PURPOSES



© Copyright 2014, by Paul J. Ford and Company. All Rights Reserved. This document and the data contained herein, is proprietary to Paul J. Ford and Company, issued in strict confidence and shall not, without the prior written permission of Paul J. Ford and Company, be reproduced, copied or used for any purpose other than the intended use for this specific project.

PAUL J. FORD AND COMPANY
 STRUCTURAL ENGINEERS
 250 East Broad Street · Suite 600 · Columbus, Ohio 43215
 (614) 221-6679 www.pjfweb.com

CROWN CASTLE
 46 BROADWAY ALBANY, NY 12204
 PH: (585) 899-3442 FAX: (585) 899-3448

BU #806953; BRG 2044 (A) 943097
 STAMFORD, CONNECTICUT
 MONOPOLE REINFORCEMENT AND RETROFIT PROJECT

PROJECT No:
 37513-2318A
 DRAWN BY:
 T.A.N.
 CHECKED BY:
 J.J.F.
 APPROVED BY:
 DATE:
 4-7-2014

ISSUE DATE OF
 PERMIT A: 4-7-2014

S-5

MODIFICATION INSPECTION NOTES:**GENERAL**

THE MODIFICATION INSPECTION (MI) IS A VISUAL INSPECTION OF TOWER MODIFICATIONS AND A REVIEW OF CONSTRUCTION INSPECTIONS AND OTHER REPORTS TO ENSURE THE INSTALLATION WAS CONSTRUCTED IN ACCORDANCE WITH THE CONTRACT DOCUMENTS, NAMELY THE MODIFICATION DRAWINGS, AS DESIGNED BY THE ENGINEER OF RECORD (EOR).

THE MI IS TO CONFIRM INSTALLATION CONFIGURATION AND WORKMANSHIP ONLY AND IS NOT A REVIEW OF THE MODIFICATION DESIGN ITSELF, NOR DOES THE MI INSPECTOR TAKE OWNERSHIP OF THE MODIFICATION DESIGN. OWNERSHIP OF THE STRUCTURAL MODIFICATION DESIGN EFFECTIVENESS AND INTEGRITY RESIDES WITH THE EOR AT ALL TIMES.

ALL MI'S SHALL BE CONDUCTED BY A CROWN ENGINEERING VENDOR (AEV) OR ENGINEERING SERVICE VENDOR (AESV) THAT IS APPROVED TO PERFORM ELEVATED WORK FOR CROWN. SEE ENG-BUL-10173 LIST OF APPROVED MI VENDORS..

TO ENSURE THAT THE REQUIREMENTS OF THE MI ARE MET, IT IS VITAL THAT THE GENERAL CONTRACTOR (GC) AND THE MI INSPECTOR BEGIN COMMUNICATING AND COORDINATING AS SOON AS A PO IS RECEIVED. IT IS EXPECTED THAT EACH PARTY WILL BE PROACTIVE IN REACHING OUT TO THE OTHER PARTY. IF CONTACT INFORMATION IS NOT KNOWN, CONTACT YOUR CROWN POINT OF CONTACT (POC).

REFER TO ENG-SOW-10007 : MODIFICATION INSPECTION SOW FOR FURTHER DETAILS AND REQUIREMENTS.

MI INSPECTOR

THE MI INSPECTOR IS REQUIRED TO CONTACT THE GC AS SOON AS RECEIVING A PO FOR THE MI TO, AT A MINIMUM:

- REVIEW THE REQUIREMENTS OF THE MI CHECKLIST
- WORK WITH THE GC TO DEVELOP A SCHEDULE TO CONDUCT ON-SITE INSPECTIONS, INCLUDING FOUNDATION INSPECTIONS

THE MI INSPECTOR IS RESPONSIBLE FOR COLLECTING ALL GENERAL CONTRACTOR (GC) INSPECTION AND TEST REPORTS, REVIEWING THE DOCUMENTS FOR ADHERENCE TO THE CONTRACT DOCUMENTS, CONDUCTING THE IN-FIELD INSPECTIONS, AND SUBMITTING THE MI REPORT TO CROWN.

GENERAL CONTRACTOR

THE GC IS REQUIRED TO CONTACT THE MI INSPECTOR AS SOON AS RECEIVING A PO FOR THE MODIFICATION INSTALLATION OR TURNKEY PROJECT TO, AT A MINIMUM:

- REVIEW THE REQUIREMENTS OF THE MI CHECKLIST
- WORK WITH THE MI INSPECTOR TO DEVELOP A SCHEDULE TO CONDUCT ON-SITE INSPECTIONS, INCLUDING FOUNDATION INSPECTIONS
- BETTER UNDERSTAND ALL INSPECTION AND TESTING REQUIREMENTS

THE GC SHALL PERFORM AND RECORD THE TEST AND INSPECTION RESULTS IN ACCORDANCE WITH THE REQUIREMENTS OF THE MI CHECKLIST AN DENG-SOW-10007.

RECOMMENDATIONS

THE FOLLOWING RECOMMENDATIONS AND SUGGESTIONS ARE OFFERED TO ENHANCE THE EFFICIENCY AND EFFECTIVENESS OF DELIVERING A MI REPORT:

- IT IS SUGGESTED THAT THE GC PROVIDE A MINIMUM OF 5 BUSINESS DAYS NOTICE, PREFERABLE 10, TO THE MI INSPECTOR AS TO WHEN THE SITE WILL BE READY FOR THE MI TO BE CONDUCTED.
- THE GC AND MI INSPECTOR COORDINATE CLOSELY THROUGHOUT THE ENTIRE PROJECT.
- WHEN POSSIBLE, IT IS PREFERRED TO HAVE THE GC AND MI INSPECTOR ON-SITE SIMULTANEOUSLY FOR ANY GUY WIRE TENSIONING OR RE-TENSIONING OPERATIONS
- IT MAY BE BENEFICIAL TO INSTALL ALL TOWER MODIFICATIONS PRIOR TO CONDUCTING THE FOUNDATION INSPECTIONS TO ALLOW FOUNDATION AND MI INSPECTION(S) TO COMMENCE WITH ONE SITE VISIT.
- WHEN POSSIBLE, IT IS PREFERRED TO HAVE THE GC AND MI INSPECTOR ON-SITE DURING THE MI TO HAVE ANY DEFICIENCIES CORRECTED DURING THE INITIAL MI. THEREFORE, THE GC MAY CHOOSE TO COORDINATE THE MI CAREFULLY TO ENSURE ALL CONSTRUCTION FACILITIES ARE AT THEIR DISPOSAL WHEN THE MI INSPECTOR IS ON SITE.

CANCELLATION OR DELAYS IN SCHEDULED MI

IF THE GC AND MI INSPECTOR AGREE TO A DATE ON WHICH THE MI WILL BE CONDUCTED, AND EITHER PARTY CANCELS OR DELAYS, CROWN SHALL NOT BE RESPONSIBLE FOR ANY COSTS, FEES, LOSS OF DEPOSITS AND/OR OTHER PENALTIES RELATED TO THE CANCELLATION OR DELAY INCURRED BY EITHER PARTY FOR ANY TIME (E.G. TRAVEL AND LODGING, COSTS OF KEEPING EQUIPMENT ON-SITE, ETC.). IF CROWN CONTRACTS DIRECTLY FOR A THIRD PARTY MI, EXCEPTIONS MAY BE MADE IN THE EVENT THAT THE DELAY/CANCELLATION IS CAUSED BY WEATHER OR OTHER CONDITIONS THAT MAY COMPROMISE THE SAFETY OF THE PARTIES INVOLVED.

CORRECTION OF FAILING MIs

IF THE MODIFICATION INSTALLATION WOULD FAIL THE MI ("FAILED MI"), THE GC SHALL WORK WITH CROWN TO COORDINATE A REMEDIATION PLAN IN ONE OF TWO WAYS:

- CORRECT FAILING ISSUES TO COMPLY WITH THE SPECIFICATIONS CONTAINED IN THE ORIGINAL CONTRACT DOCUMENTS AND COORDINATE A SUPPLEMENT MI.
- OR, WITH CROWN'S APPROVAL, THE GC MAY WORK WITH THE EOR TO RE-ANALYZE THE MODIFICATION/REINFORCEMENT USING THE AS-BUILT CONDITION

MI VERIFICATION INSPECTIONS

CROWN RESERVES THE RIGHT TO CONDUCT A MI VERIFICATION INSPECTION TO VERIFY THE ACCURACY AND COMPLETENESS OF PREVIOUSLY COMPLETED MI INSPECTION(S) ON TOWER MODIFICATION PROJECTS.

ALL VERIFICATION INSPECTIONS SHALL BE HELD TO THE SAME SPECIFICATIONS AND REQUIREMENTS IN THE CONTRACT DOCUMENTS AND IN ACCORDANCE WITH ENG-SOW-10007.

VERIFICATION INSPECTION MAY BE CONDUCTED BY AN INDEPENDENT AEV/AESV FIRM AFTER A MODIFICATION PROJECT IS COMPLETED, AS MARKED BY THE DATE OF AN ACCEPTED "PASSING MI" OR "PASS AS NOTED MI" REPORT FOR THE ORIGINAL PROJECT.

PHOTOGRAPHS

BETWEEN THE GC AND THE MI INSPECTOR THE FOLLOWING PHOTOGRAPHS, AT A MINIMUM, ARE TO BE TAKEN AND INCLUDED IN THE MI REPORT:

- PRE-CONSTRUCTION GENERAL SITE CONDITION
- PHOTOGRAPHS DURING THE REINFORCEMENT MODIFICATION CONSTRUCTION/ERECTION AND INSPECTION
 - RAW MATERIALS
 - PHOTOS OF ALL CRITICAL DETAILS
 - FOUNDATION MODIFICATIONS
 - WELD PREPARATION
 - BOLT INSTALLATION AND TORQUE
 - FINAL INSTALLED CONDITION
 - SURFACE COATING REPAIR
- POST CONSTRUCTION PHOTOGRAPHS
 - FINAL INFIELD CONDITION

PHOTOS OF ELEVATED MODIFICATIONS TAKEN FROM THE GROUND SHALL BE CONSIDERED INADEQUATE.

THIS IS NOT A COMPLETE LIST OF REQUIRED PHOTOS, PLEASE REFER TO ENG-SOW-10007.

MI CHECKLIST

CONSTRUCTION/INSTALLATION INSPECTIONS AND TESTING REQUIRED (COMPLETED BY EOR)	REPORT ITEM
PRE-CONSTRUCTION	
X	MI CHECKLIST DRAWINGS
X	EOR APPROVED SHOP DRAWINGS
X	FABRICATION INSPECTION
NA	FABRICATOR CERTIFIED WELD INSPECTION
X	MATERIAL TEST REPORT (MTR)
NA	FABRICATOR NDE INSPECTION
NA	NDE REPORT OF MONOPOLE BASE PLATE (AS REQUIRED)
X	PACKING SLIPS
ADDITIONAL TESTING AND INSPECTIONS: -----	
CONSTRUCTION	
X	CONSTRUCTION INSPECTIONS
NA	FOUNDATION INSPECTIONS
NA	CONCRETE COMP. STRENGTH AND SLUMP TESTS
NA	POST INSTALLED ANCHOR ROD VERIFICATION
NA	BASE PLATE GROUT VERIFICATION
NA	CONTRACTOR'S CERTIFIED WELD INSPECTION
NA	EARTHWORK: LIFT AND DENSITY
X	ON SITE COLD GALVANIZING VERIFICATION
NA	GUY WIRE TENSION REPORT
X	GC AS-BUILT DOCUMENTS
X	THIRD PARTY ONSITE INSPECTION OF BOLT PRETENSION PER CROWN REQUIREMENTS
X	INSPECTION OF AJAX BOLTS AND DT'S PER REQUIREMENTS ON SHEET S-3
ADDITIONAL TESTING AND INSPECTIONS: -----	
POST-CONSTRUCTION	
X	MI INSPECTOR REDLINE OR RECORD DRAWING(S)
X	THIRD PARTY ONSITE BOLT INSPECTION REPORT
NA	POST INSTALLED ANCHOR ROD PULL-OUT TESTING
X	PHOTOGRAPHS
ADDITIONAL TESTING AND INSPECTIONS: -----	

NOTE: X DENOTES A DOCUMENT NEEDED FOR THE PMI REPORT

NA DENOTES A DOCUMENT THAT IS NOT REQUIRED FOR THE PMI REPORT

© Copyright 2014, by Paul J. Ford and Company. All Rights Reserved. This document and the data contained herein, is proprietary to Paul J. Ford and Company, issued in strict confidence and shall not, without the prior written permission of Paul J. Ford and Company, be reproduced, copied or used for any purpose other than the intended use for this specific project.

PAUL J. FORD AND COMPANY
STRUCTURAL ENGINEERS
250 East Broad Street · Suite 600 · Columbus, Ohio 43215
(614) 221-6679 www.pjfweb.com

CROWN CASTLE
46 BROADWAY ALBANY, NY 12204
PH: (585) 899-3442 FAX: (585) 899-3448

BU #806953; BRG 2044 (A) 943097
STAMFORD, CONNECTICUT
MONOPOLE REINFORCEMENT AND RETROFIT PROJECT

PROJECT No:
37513-2318A

DRAWN BY:
T.A.N.

CHECKED BY:
J.J.F.

APPROVED BY:

DATE:
4-7-2014

ISSUE DATE OF
PERMIT A: 4-7-2014

S-6

MONOPOLE REINFORCEMENT AND RETROFIT PROJECT

BU NUMBER; SITE NAME
BU #806953; BRG 2044 (A) 943097
 APP: 205537 REV. 1; WO: 736046

SITE ADDRESS
**69 GUINEA RD. (CAMP ROCKY CRAIG
 STAMFORD, CONNECTICUT 06903
 FAIRFIELD COUNTY**

PROJECT NOTES

- DETAILED FIELD INFORMATION REGARDING INTERFERENCES AND/OR EXISTING FIELD CONDITIONS MAY BE AVAILABLE ON CROWN'S CC/SITES AND FROM CONTRACTOR'S PRE-MOD MAPPING. IT IS THE CONTRACTOR'S RESPONSIBILITY TO FIELD VERIFY ALL EXISTING CONDITIONS AND DIMENSIONS AND COORDINATE WITH THE AVAILABLE SOURCES OF INFORMATION ABOVE AND WITH THE PROJECT PLANS BEFORE PROCEEDING WITH THE WORK. CONTRACTOR SHALL IMMEDIATELY REPORT ANY AND ALL DISCREPANCIES TO PAUL J. FORD AND COMPANY AND CROWN CASTLE FIELD PERSONNEL BEFORE PROCEEDING WITH THE WORK.
- ALL STRUCTURAL BOLTS SHALL BE INSTALLED AND TIGHTENED TO THE PRETENSIONED CONDITION ACCORDING TO THE REQUIREMENTS OF THE AISC 'SPECIFICATION FOR STRUCTURAL JOINTS USING HIGH-STRENGTH BOLTS', DEC. 31, 2009.
- ALL STRUCTURAL BOLTS SHALL BE FIELD INSPECTED ACCORDING TO THE REQUIREMENTS OF THE AISC 'SPECIFICATION FOR STRUCTURAL JOINTS USING HIGH-STRENGTH BOLTS', DEC. 31, 2009.
- (A.) DTIS REQUIRED: ALL AJAX BOLTS SHALL BE INSTALLED USING DIRECT TENSION INDICATORS (DTIS) AND HARDENED WASHERS. ALL AJAX M20 BOLTS WITH SHEAR SLEEVES SHALL BE PRETENSIONED AND TIGHTENED UNTIL THE DIRECT TENSION INDICATOR (DTI) WASHERS SHOW THAT THE PROPER BOLT TENSION HAS BEEN REACHED. SEE NOTES AND DETAILS ON SHEET S-3 FOR REQUIREMENTS ON THE USE OF DIRECT TENSION INDICATOR (DTI) WASHERS WITH THE AJAX M20 BOLTS.
 (B.) EFFECTIVE 5/30/2012: UNTIL FURTHER NOTICE, CROWN CASTLE WILL ACCEPT AJAX BOLTS TIGHTENED USING AISC "TURN-OF-NUT" METHOD. INSTALLERS SHALL FOLLOW CROWN GUIDELINES FOR AISC "TURN-OF-NUT" METHOD AND ALSO PROVIDE COMPLETE INSPECTION DOCUMENTATION IN THE PMI. PRIOR TO STARTING WORK, CONTRACTOR SHALL CONSULT WITH CROWN ENGINEERING TO DETERMINE WHETHER THIS POLICY IS STILL IN PLACE.
 (C.) REQUIREMENT EFFECTIVE 04/20/2013, PER CROWN CASTLE DIRECTIVE: ANY AND ALL STRUCTURAL BOLTS THAT ARE TIGHTENED TO THE PRETENSIONED CONDITION USING THE AISC "TURN-OF-NUT" TENSIONING PROCEDURE (NON-TENSION CONTROLLED [NON-TC] BOLTS AND/OR BOLTS WITHOUT DTIS INSTALLED) SHALL BE INSPECTED ON-SITE BY AN INDEPENDENT THIRD-PARTY BOLT INSPECTOR, AS APPROVED BY CROWN. THIS INSPECTION IS REQUIRED TO BE AN ON-SITE FIELD INSPECTION. THE THIRD-PARTY BOLT INSPECTOR SHALL FOLLOW THE PUBLISHED CROWN CASTLE INSPECTION PROCEDURE "MI NON-TC BOLT INSPECTION", DATED APRIL 2013. THE THIRD-PARTY BOLT INSPECTOR SHALL PREPARE A FULLY DOCUMENTED BOLT INSPECTION REPORT, AS SPECIFIED BY CROWN, AND SHALL SUBMIT A COPY OF THE BOLT INSPECTION REPORT TO THE MI INSPECTOR, THE EOR, AND TO CROWN CASTLE.

PROJECT CONTACTS:

MONOPOLE OWNER:

CROWN CASTLE
 46 BROADWAY ALBANY, NY 12204
 TSA: ANDREW BAZINET AT ANDREW.BAZINET@CROWNCASTLE.COM
 PH: (585) 899-3442
 MOD PM: EVA MORALES AT EVA.MORALES@CROWNCASTLE.COM
 PH: (704) 405-6612

STRUCTURAL ENGINEER OF RECORD (EOR):

PAUL J. FORD AND COMPANY
 250 EAST BROAD STREET, SUITE 600
 COLUMBUS, OHIO 43215-3708
 CONTACT: JOSH FRYBARGER AT JFRYBARGER@PJFWEB.COM
 PHONE: 614-221-6679

DESIGN STANDARD


THIS REINFORCEMENT DESIGN IS BASED UPON THE REQUIREMENTS OF THE TIA/EIA-222-F-1996 STRUCTURAL STANDARD FOR ANTENNA SUPPORTING STRUCTURES AND ANTENNAS, USING A DESIGN BASIC WIND SPEED OF 85 MPH (FASTEST MILE) WITH NO ICE, 38 MPH WITH 3/4 INCH ICE AND 50 MPH SERVICE LOADS.

REFER TO THE POLE DESIGN AND ANTENNA LOADING DOCUMENTED IN THE PJF STRUCTURAL ANALYSIS FOR THIS SITE (PJF#37513-2318A), DATED 4-7-2014.


THIS PROJECT INCLUDES THE FOLLOWING REINFORCING ELEMENTS:

SHAFT REINFORCING

SHEET INDEX	
SHEET NUMBER	DESCRIPTION
T-1	TITLE SHEET
S-1	GENERAL NOTES
S-2	GENERAL NOTES
S-3	AJAX BOLT DETAIL
S-4	MONOPOLE PROFILE
S-5	SHAFT REINF. CHART AND DETAIL
S-6	MI CHECKLIST



APR 10 2014



PAUL J. FORD AND COMPANY
 STRUCTURAL ENGINEERS
 250 East Broad Street - Suite 600 - Columbus, Ohio 43215
 (614) 221-6679 www.pjfweb.com

CROWN CASTLE

46 BROADWAY ALBANY, NY 12204
 PH: (585) 899-3442 FAX: (585) 899-3448

© Copyright 2014, by Paul J. Ford and Company, All Rights Reserved. This document and the data contained herein, is proprietary to Paul J. Ford and Company, issued in strict confidence and shall not, without the prior written permission of Paul J. Ford and Company, be reproduced, copied or used for any purpose other than the intended use for this specific project.

PROJECT No:
37513-2318A
 DRAWN BY:
T.A.N.
 CHECKED BY:
J.J.F.
 APPROVED BY:
DATE:
4-7-2014

BU #806953; BRG 2044 (A) 943097
 STAMFORD, CONNECTICUT
 MONOPOLE REINFORCEMENT AND RETROFIT PROJECT

ISSUE DATE OF
 PERMIT A: 4-7-2014

T-1

CROWN CASTLE PROJECT: BU #806953; BRG 2044 (A) 943097; STAMFORD, CONNECTICUT
MONOPOLE RETROFIT PROJECT MASTER NOTES DOCUMENT (REV. 2, 1/22/2009)

A. GENERAL NOTES

- IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO FIELD VERIFY ALL EXISTING CONDITIONS AND DIMENSIONS PRIOR TO FABRICATION AND CONSTRUCTION. THESE DRAWINGS WERE PREPARED FROM INFORMATION AND DOCUMENTS PROVIDED TO PAUL J. FORD & COMPANY BY CROWN CASTLE. THIS INFORMATION PROVIDED HAS NOT BEEN FIELD VERIFIED BY PAUL J. FORD & COMPANY FOR ACCURACY AND THEREFORE DISCREPANCIES BETWEEN THESE DRAWINGS AND ACTUAL SITE CONDITIONS SHOULD BE ANTICIPATED. ANY DISCREPANCIES AND/OR CHANGES BETWEEN THE INFORMATION CONTAINED IN THESE DRAWINGS AND THE ACTUAL VERIFIED SITE CONDITIONS SHALL BE IMMEDIATELY BROUGHT TO THE ATTENTION OF CROWN CASTLE AND PAUL J. FORD & COMPANY SO THAT ANY CHANGES AND/OR ADJUSTMENTS, IF NECESSARY, CAN BE MADE TO THE DESIGN AND DRAWINGS.
- THE EXISTING UNREINFORCED MONOPOLE STRUCTURE DOES NOT HAVE THE STRUCTURAL CAPACITY TO CARRY ALL OF THE ANTENNA AND PLATFORM LOADS SHOWN ON THESE DRAWINGS AT THE REQUIRED MINIMUM TIA/EIA-222-F BASIC WIND SPEEDS. DO NOT INSTALL ANY ADDITIONAL OR NEW ANTENNA AND PLATFORM LOADS UNTIL THE MONOPOLE REINFORCING SYSTEM IS COMPLETELY AND SUCCESSFULLY INSTALLED.
- IF MATERIALS, QUANTITIES, STRENGTHS OR SIZES INDICATED BY THE DRAWINGS OR SPECIFICATIONS ARE NOT IN AGREEMENT WITH THESE NOTES, THE BETTER QUALITY AND/OR GREATER QUANTITY, STRENGTH OR SIZE INDICATED, SPECIFIED OR NOTED SHALL BE PROVIDED.
- THIS STRUCTURE IS DESIGNED TO BE SELF-SUPPORTING AND STABLE AFTER THE INSTALLATION OF THE REINFORCING REPAIR SYSTEM HAS BEEN PROPERLY AND ADEQUATELY COMPLETED. IT IS THE CONTRACTOR'S SOLE RESPONSIBILITY TO INSURE THE SAFETY AND STABILITY OF THE MONOPOLE AND ITS COMPONENT PARTS DURING FIELD MODIFICATIONS. THIS INCLUDES, BUT IS NOT LIMITED TO, THE ADDITION OF WHATEVER TEMPORARY BRACING, GUYS OR TIE DOWNS THAT MAY BE NECESSARY. SUCH MATERIAL SHALL BE REMOVED AND SHALL REMAIN THE PROPERTY OF THE CONTRACTOR AFTER THE COMPLETION OF THE PROJECT. IMPORTANT CUTTING, WELDING AND SAFETY GUIDELINES: THE CONTRACTOR SHALL FOLLOW ALL CROWN CASTLE CUTTING, WELDING, FIRE PREVENTION AND SAFETY GUIDELINES. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL OBTAIN A COPY OF THE CURRENT CROWN CASTLE GUIDELINES FROM CROWN CASTLE. PER THE 12-01-2008 CROWN CASTLE DIRECTIVE: "ALL CUTTING AND WELDING ACTIVITIES SHALL BE CONDUCTED IN ACCORDANCE WITH CROWN CASTLE POLICY "CUTTING AND WELDING PLAN" (DOC # ENG-PLN-10015) ON AN ONGOING BASIS THROUGHOUT THE ENTIRE LIFE OF THE PROJECT"
- THE STRUCTURAL CONTRACT DOCUMENTS DO NOT INDICATE THE METHOD OR MEANS OF CONSTRUCTION. THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK AND SHALL BE SOLELY RESPONSIBLE FOR ALL CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES. OBSERVATION VISITS TO THE SITE BY THE OWNER AND/OR THE ENGINEER SHALL NOT INCLUDE INSPECTIONS OF THE PROTECTIVE MEASURES OR THE CONSTRUCTION PROCEDURES.
- ANY SUPPORT SERVICES PERFORMED BY THE ENGINEER DURING CONSTRUCTION SHALL BE DISTINGUISHED FROM CONTINUOUS AND DETAILED INSPECTION SERVICES WHICH ARE FURNISHED BY THE INSPECTION/TESTING AGENCY. THESE SUPPORT SERVICES PERFORMED BY THE ENGINEER ARE SOLELY FOR THE PURPOSE OF ASSISTING IN QUALITY CONTROL AND IN ACHIEVING CONFORMANCE WITH CONTRACT DOCUMENTS. THEY DO NOT GUARANTEE CONTRACTOR'S PERFORMANCE AND SHALL NOT BE CONSTRUED AS SUPERVISION OF CONSTRUCTION.
- ALL MATERIALS AND EQUIPMENT FURNISHED WILL BE NEW AND OF GOOD QUALITY, FREE FROM FAULTS AND DEFECTS AND IN CONFORMANCE WITH THE CONTRACT DOCUMENTS. ANY AND ALL SUBSTITUTIONS MUST BE PROPERLY APPROVED AND AUTHORIZED IN WRITING BY THE OWNER AND ENGINEER PRIOR TO INSTALLATION. THE CONTRACTOR SHALL FURNISH SATISFACTORY EVIDENCE AS TO THE KIND AND QUALITY OF MATERIALS AND EQUIPMENT BEING SUBSTITUTED.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR INITIATING, MAINTAINING, AND SUPERVISING ALL SAFETY PRECAUTIONS AND PROGRAMS IN CONNECTION WITH THE WORK. THE CONTRACTOR IS RESPONSIBLE TO INSURE THAT THIS PROJECT AND RELATED WORK COMPLIES WITH ALL APPLICABLE LOCAL, STATE, AND FEDERAL SAFETY CODES AND REGULATIONS GOVERNING THIS WORK AS WELL AS CROWN CASTLE SAFETY GUIDELINES.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING ALL EXISTING AND NEW COAXIAL CABLES AND OTHER EQUIPMENT DURING CONSTRUCTION.
- ANY EXISTING ATTACHMENTS AND/OR PROJECTIONS ON THE POLE THAT MAY INTERFERE WITH THE INSTALLATION OF THE REINFORCING SYSTEM WILL HAVE TO BE REMOVED, AND/OR RELOCATED, AND/OR REPLACED AND RE-INSTALLED AFTER THE REINFORCING IS SUCCESSFULLY COMPLETED. THE CONTRACTOR SHALL IDENTIFY AND COORDINATE THESE ITEMS PRIOR TO CONSTRUCTION WITH THE OWNER, TESTING AGENCY, AND ENGINEER.
- ANY AND ALL EXISTING PLATFORMS THAT ARE LOCATED IN AREAS OF THE POLE SHAFT WHERE SHAFT REINFORCING MUST BE APPLIED SHALL BE TEMPORARILY REMOVED OR OTHERWISE SUPPORTED TO PERMIT NEW CONTINUOUS REINFORCEMENT TO BE ATTACHED. AFTER THE CONTRACTOR HAS SUCCESSFULLY INSTALLED THE MONOPOLE REINFORCEMENT SYSTEM, THE CONTRACTOR SHALL RE-INSTALL THE PLATFORMS. IN NO CASE SHALL ANY NEW AND/OR ADDITIONAL PLATFORMS AND/OR ANTENNAS AND/OR COAX CABLES AND/OR OTHER EQUIPMENT BE INSTALLED ON THE MONOPOLE UNTIL THE CONTRACTOR HAS SUCCESSFULLY COMPLETED THE INSTALLATION OF ALL OF THE REQUIRED STRUCTURAL REINFORCING SYSTEM COMPONENTS.

B. (SECTION NOT USED)

- GENERAL:
 - PERFORM CONTINUOUS ON-SITE OBSERVATION, INSPECTION, VERIFICATION, AND TESTING DURING THE TIME THE CONTRACTOR IS WORKING ON-SITE. AGENCY SHALL NOTIFY OWNER IMMEDIATELY WHEN FIELD PROBLEMS OR DISCREPANCIES OCCUR.
 - FOUNDATIONS, CONCRETE, AND SOIL PREPARATION - (NOT REQUIRED)
 - CONCRETE TESTING PER ACI - (NOT REQUIRED)
 - STRUCTURAL STEEL
 - CHECK THE STEEL ON THE JOB WITH THE PLANS.
 - CHECK MILL CERTIFICATIONS.
 - CHECK GRADE OF STEEL MEMBERS AND BOLTS FOR CONFORMANCE WITH DRAWINGS.
 - INSPECT STEEL MEMBERS FOR DISTORTION, EXCESSIVE RUST, FLAWS AND BURNED HOLES.
 - CALL FOR LABORATORY TEST REPORTS WHEN IN DOUBT.
 - CHECK STEEL MEMBERS FOR SIZES, SWEEP AND DIMENSIONAL TOLERANCES.
 - CHECK FOR SURFACE FINISH SPECIFIED, GALVANIZED.
 - CHECK BOLT TIGHTENING ACCORDING TO AISC "TURN OF THE NUT" METHOD.
 - WELDING: - (NOT REQUIRED)
 - SPECIAL INSPECTION AND TESTING


ALL WORK SHALL BE SUBJECT TO REVIEW AND OBSERVATION BY THE OWNER'S REPRESENTATIVE AND THE OWNER'S AUTHORIZED INDEPENDENT INSPECTION AND TESTING AGENCY. REFER TO CROWN CASTLE DOCUMENT ENG-SOW-10066 FOR SPECIFICATION.

ANY SUPPORT SERVICES PERFORMED BY THE ENGINEER DURING CONSTRUCTION SHALL BE DISTINGUISHED FROM CONTINUOUS AND DETAILED INSPECTION SERVICES WHICH ARE FURNISHED BY OTHERS. THESE SUPPORT SERVICES PERFORMED BY THE ENGINEER ARE PERFORMED SOLELY FOR THE PURPOSE OF ASSISTING IN QUALITY CONTROL AND IN ACHIEVING CONFORMANCE WITH CONTRACT DOCUMENTS. THEY DO NOT GUARANTEE CONTRACTOR'S PERFORMANCE AND SHALL NOT BE CONSTRUED AS SUPERVISION OF CONSTRUCTION.

OBSERVED DISCREPANCIES BETWEEN THE WORK AND THE CONTRACT DOCUMENTS SHALL BE CORRECTED BY THE CONTRACTOR AT NO ADDITIONAL COST.

AN INDEPENDENT QUALIFIED INSPECTION/TESTING AGENCY SHALL BE SELECTED, RETAINED AND PAID FOR BY THE OWNER FOR THE SOLE PURPOSE OF INSPECTING, TESTING, DOCUMENTING, AND APPROVING ALL WELDING AND FIELD WORK PERFORMED BY THE CONTRACTOR.

 - ACCESS TO ANY PLACE WHERE WORK IS BEING DONE SHALL BE PERMITTED AT ALL TIMES. THE INSPECTION AGENCY SHALL SO SCHEDULE THIS WORK AS TO CAUSE A MINIMUM OF INTERRUPTION TO, AND COORDINATE WITH, THE WORK IN PROGRESS. IT IS THE CONTRACTOR'S RESPONSIBILITY TO COORDINATE THE WORK SCHEDULE WITH THE TESTING AGENCY. THE CONTRACTOR SHALL ALLOW FOR ADEQUATE TIME AND ACCESS FOR THE TESTING AGENCY TO PERFORM THEIR DUTIES.
 - THE INSPECTION AND TESTING AGENCY SHALL BE RESPONSIBLE TO PERFORM THE FOLLOWING SERVICES FOR THE OWNER. THE TESTING AGENCY SHALL INSPECT THE FOLLOWING ITEMS IN ACCORDANCE WITH THE CONSTRUCTION DRAWINGS. THE TESTING AGENCY SHALL INSPECT ITEMS ON THIS LIST AND OTHER ITEMS AS NECESSARY TO FULFILL THEIR RESPONSIBILITY. THE TESTING AGENCY SHALL UTILIZE EXPERIENCED, TRAINED INSPECTORS INCLUDING AWS CERTIFIED WELDING INSPECTORS (CWI). INSPECTORS SHALL HAVE THE TRAINING, CREDENTIALS, AND EXPERIENCE APPROPRIATE FOR AND COMMENSURATE WITH THE SCOPE AND TYPE OF INSPECTION WORK TO BE PERFORMED.
 - GENERAL:
 - PERFORM CONTINUOUS ON-SITE OBSERVATION, INSPECTION, VERIFICATION, AND TESTING DURING THE TIME THE CONTRACTOR IS WORKING ON-SITE. AGENCY SHALL NOTIFY OWNER IMMEDIATELY WHEN FIELD PROBLEMS OR DISCREPANCIES OCCUR.
 - FOUNDATIONS, CONCRETE, AND SOIL PREPARATION - (NOT REQUIRED)
 - CONCRETE TESTING PER ACI - (NOT REQUIRED)
 - STRUCTURAL STEEL
 - CHECK THE STEEL ON THE JOB WITH THE PLANS.
 - CHECK MILL CERTIFICATIONS.
 - CHECK GRADE OF STEEL MEMBERS AND BOLTS FOR CONFORMANCE WITH DRAWINGS.
 - INSPECT STEEL MEMBERS FOR DISTORTION, EXCESSIVE RUST, FLAWS AND BURNED HOLES.
 - CALL FOR LABORATORY TEST REPORTS WHEN IN DOUBT.
 - CHECK STEEL MEMBERS FOR SIZES, SWEEP AND DIMENSIONAL TOLERANCES.
 - CHECK FOR SURFACE FINISH SPECIFIED, GALVANIZED.
 - CHECK BOLT TIGHTENING ACCORDING TO AISC "TURN OF THE NUT" METHOD.
 - WELDING: - (NOT REQUIRED)
- SPECIAL INSPECTION OF EXISTING SHAFT-TO-FLANGE WELD CONNECTIONS: - (NOT REQUIRED)
- REPORTS:
 - COMPILE AND PERIODICALLY SUBMIT DAILY INSPECTION REPORTS TO THE OWNER.
- THE INSPECTION PLAN OUTLINED HEREIN IS INTENDED AS A DESCRIPTION OF GENERAL AND SPECIFIC ITEMS OF CONCERN. IT IS NOT INTENDED TO BE ALL-INCLUSIVE. IT DOES NOT LIMIT THE TESTING AND INSPECTION AGENCY TO THE ITEMS LISTED. ADDITIONAL TESTING, INSPECTION, AND CHECKING MAY BE REQUIRED AND SHOULD BE ANTICIPATED. THE TESTING AGENCY SHALL USE THEIR PROFESSIONAL JUDGMENT AND KNOWLEDGE OF THE JOB SITE CONDITIONS AND THE CONTRACTOR'S PERFORMANCE TO DECIDE WHAT OTHER ITEMS REQUIRE ADDITIONAL ATTENTION. THE TESTING AGENCY'S JUDGMENT MUST PREVAIL ON ITEMS NOT SPECIFICALLY COVERED. ANY DISCREPANCIES AND PROBLEMS SHALL BE BROUGHT IMMEDIATELY TO THE OWNER'S ATTENTION. RESOLUTIONS ARE NOT TO BE MADE WITHOUT THE OWNER'S REVIEW AND SPECIFIC WRITTEN CONSENT. THE OWNER RESERVES THE RIGHT TO DETERMINE WHAT IS AN ACCEPTABLE RESOLUTION OF DISCREPANCIES AND PROBLEMS.
- AFTER EACH INSPECTION, THE TESTING AGENCY WILL PREPARE A WRITTEN ACCEPTANCE OR REJECTION WHICH WILL BE GIVEN TO THE CONTRACTOR AND FILED AS DAILY REPORTS TO THE OWNER. THIS WRITTEN ACTION WILL GIVE THE CONTRACTOR A LIST OF ITEMS TO BE CORRECTED, PRIOR TO CONTINUING CONSTRUCTION, AND/OR LOADING OF STRUCTURAL ITEMS.
- RESPONSIBILITY: THE TESTING AGENCY DOES NOT RELIEVE THE CONTRACTOR'S CONTRACTUAL OR STATUTORY OBLIGATIONS. THE CONTRACTOR HAS THE SOLE RESPONSIBILITY FOR ANY DEVIATIONS FROM THE OFFICIAL CONTRACT DOCUMENTS. THE TESTING AGENCY WILL NOT REPLACE THE CONTRACTOR'S QUALITY CONTROL PERSONNEL.



APR 10 2014

CROWN CASTLE
PAUL J. FORD AND COMPANY
STRUCTURAL ENGINEERS
250 East Broad Street - Suite 600 - Columbus, Ohio 43215
(614) 221-6879 www.pjfweb.com

CROWN CASTLE
46 BROADWAY ALBANY, NY 12204
PH: (565) 899-3442 FAX: (565) 899-3448

© Copyright 2014, by Paul J. Ford and Company, All Rights Reserved. This document and the data contained herein, is proprietary to Paul J. Ford and Company, issued in strict confidence and shall not, without the prior written permission of Paul J. Ford and Company, be reproduced, copied or used for any purpose other than the intended use for this specific project.

PROJECT No:
37513-2318A
DRAWN BY:
T.A.N.
CHECKED BY:
J.J.F.
APPROVED BY:

BU #806953; BRG 2044 (A) 943097
STAMFORD, CONNECTICUT
MONOPOLE REINFORCEMENT AND RETROFIT PROJECT

ISSUE DATE OF
PERMIT A: 4-7-2014

DATE:
4-7-2014

S-1

- D. STRUCTURAL STEEL**
STRUCTURAL STEEL MATERIALS, FABRICATION, DETAILING, AND WORKMANSHIP SHALL CONFORM TO THE LATEST EDITION OF THE FOLLOWING REFERENCE STANDARDS:
BY THE AMERICAN INSTITUTE OF STEEL CONSTRUCTION (AISC):
- A. (A.) "SPECIFICATION FOR THE DESIGN, FABRICATION AND ERECTION OF STRUCTURAL STEEL FOR BUILDINGS."
(B.) "SPECIFICATION FOR STRUCTURAL JOINTS USING ASTM A325 OR A490 BOLTS," AS APPROVED BY THE RESEARCH COUNCIL ON STRUCTURAL CONNECTIONS OF THE ENGINEERING FOUNDATION.
(C.) "CODE OF STANDARD PRACTICE FOR STEEL BUILDINGS AND BRIDGES" (PARAGRAPH 4.2.1 SPECIFICALLY EXCLUDED).
 - B. BY THE AMERICAN WELDING SOCIETY (AWS):
(A.) "STRUCTURAL WELDING CODE - STEEL D1.1."
(B.) "SYMBOLS FOR WELDING AND NON-DESTRUCTIVE TESTING"
 2. ANY MATERIAL OR WORKMANSHIP WHICH IS OBSERVED TO BE DEFECTIVE OR INCONSISTENT WITH THE CONTRACT DOCUMENTS SHALL BE CORRECTED, MODIFIED, OR REPLACED AT THE CONTRACTOR'S EXPENSE.
 3. TIGHTEN ALL STRUCTURAL BOLTS, INCLUDING THE A/AX M20 BOLTS WITH SHEAR SLEEVES, ACCORDING TO THE REQUIREMENTS OF THE AISC "TURN OF THE NUT" METHOD. TIGHTEN BOLTS 1/3 TURN PAST THE SNUG TIGHT CONDITION AS DEFINED BY AISC.
 4. WELDED CONNECTIONS SHALL CONFORM TO THE LATEST REVISED CODE OF THE AMERICAN WELDING SOCIETY, AWS D1.1. ALL WELD ELECTRODES SHALL BE E80XX UNLESS NOTED OTHERWISE ON THE DRAWINGS.
 5. ALL WELDED CONNECTIONS SHALL BE MADE BY WELDERS CERTIFIED BY AWS. CONTRACTOR SHALL SUBMIT WELDERS' CERTIFICATION AND QUALIFICATION DOCUMENTATION TO THE OWNER'S TESTING AGENCY FOR REVIEW AND APPROVAL PRIOR TO CONSTRUCTION.
 6. STRUCTURAL STEEL PLATES SHALL CONFORM TO ASTM A572 GRADE 65 (FY = 65 KSI MIN.) UNLESS NOTED OTHERWISE ON THE DRAWINGS.
 7. SURFACES OF EXISTING STEEL SHALL BE PREPARED AS REQUIRED FOR FIELD WELDING PER AWS. SEE SECTION I NOTES REGARDING TOUCH-UP OF GALVANIZED SURFACES DAMAGED DURING TRANSPORTATION OR ERECTION AND ASSEMBLY AS WELL AS FIELD WELDING UNLESS OTHERWISE NOTED. ALL STEEL MEMBERS SHALL BE HOT-DIP GALVANIZED, AFTER FABRICATION, IN ACCORDANCE WITH ASTM A123. SEE SECTION J FOR FURTHER NOTES AND FOR EXCEPTIONS (IF ANY).
 9. ALL WELDS SHALL BE VISUALLY INSPECTED BY THE OWNER'S APPROVED TESTING AGENCY. OTHER TESTS MAY ALSO BE PERFORMED ON THE WELDS BY THE TESTING AGENCY IN ORDER FOR THEM TO PERFORM THEIR DUTIES FOR THIS PROJECT. THE CONTRACTOR SHALL COOPERATE WITH THE TESTING AGENCY IN THEIR TESTING EFFORTS.
 10. NO WELDING SHALL BE DONE TO THE EXISTING STRUCTURE WITHOUT THE PRIOR APPROVAL AND SUPERVISION OF THE TESTING AGENCY.
 11. FIELD CUTTING OF STEEL:
(A.) PRIOR TO ANY FIELD CUTTING, THE CONTRACTOR SHALL MARK THE CUT OUTLINES ON THE STEEL AND THE INSPECTION/TESTING AGENCY SHALL VERIFY PROPOSED LAYOUT, LOCATION, AND DIMENSIONS.
(B.) ANY REQUIRED CUTS IN THE STEEL SHALL BE CAREFULLY CUT BY MECHANICAL METHODS SUCH AS DRILLING, SAW CUTTING, AND GRINDING. THE CONTRACTOR IS RESPONSIBLE TO PREVENT ANY DAMAGE TO THE COAX CABLES, AND/OR OTHER EQUIPMENT AND/OR THE STRUCTURE DURING THE CUTTING WORK. ANY DAMAGE TO THE COAX CABLES, AND/OR OTHER EQUIPMENT AND/OR THE STRUCTURE, RESULTING FROM THE CONTRACTOR'S ACTIVITIES SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE. THE INSPECTION/TESTING AGENCY SHALL CLOSELY AND CONTINUOUSLY MONITOR THIS ACTIVITY.
(C.) ALL REQUIRED CUTS SHALL BE CUT WITHIN THE DIMENSIONS SHOWN ON THE DRAWINGS. NO CUTS SHALL EXTEND BEYOND THE OUTLINE OF THE DIMENSIONS SHOWN ON THE DRAWINGS. ALL CUT EDGES SHALL BE GROUND SMOOTH AND DE-BURRED. CUT EDGES THAT ARE TO BE FIELD WELDED SHALL BE PREPARED FOR FIELD WELDING PER AWS D1.1 AND AS SHOWN ON THE DRAWINGS. IT MAY BE NECESSARY TO DRILL STARTER HOLES AS REQUIRED TO MAKE THE CUTS. THE INSPECTION/TESTING AGENCY SHALL CLOSELY AND CONTINUOUSLY MONITOR THIS ACTIVITY.

E. BASE PLATE GROUT - (NOT REQUIRED)

F. FOUNDATION WORK - (NOT REQUIRED)

G. CAST-IN-PLACE CONCRETE - (NOT REQUIRED)

H. EPOXY GROUTED REINFORCING ANCHOR RODS - (NOT REQUIRED)

I. TOUCH UP OF GALVANIZING

THE CONTRACTOR SHALL TOUCH UP ANY AND/OR ALL AREAS OF GALVANIZING ON THE EXISTING STRUCTURE OR NEW COMPONENTS THAT ARE DAMAGED OR ABRADED DURING CONSTRUCTION. GALVANIZED SURFACES DAMAGED DURING TRANSPORTATION OR ERECTION AND ASSEMBLY AS WELL AS ANY AND ALL ABRASIONS, CUTS, FIELD DRILLING, AND ALL FIELD WELDING SHALL BE TOUCHED UP WITH TWO (2) COATS OF ZRC-BRAND ZINC-RICH COLD GALVANIZING COMPOUND. FILM THICKNESS PER COAT SHALL BE: WET 3.0 MILS; DRY 1.5 MILS. APPLY PER ZRC (MANUFACTURER) RECOMMENDED PROCEDURES. CONTACT ZRC AT 1-800-831-3275 FOR PRODUCT INFORMATION.

CONTRACTOR SHALL CLEAN AND PREPARE ALL FIELD WELDS ON GALVANIZED AND PRIME PAINTED SURFACES FOR TOUCH-UP COATING IN ACCORDANCE WITH AWS D1.1. THE OWNER'S TESTING AGENCY SHALL VERIFY THE PREPARED SURFACE PRIOR TO APPLICATION OF THE TOUCH-UP COATING.

THE OWNER'S TESTING AGENCY SHALL TEST AND VERIFY THE COATING THICKNESS AFTER THE CONTRACTOR HAS APPLIED THE ZRC COLD GALVANIZING COMPOUND AND IT HAS SUFFICIENTLY DRIED. AREAS FOUND TO BE INADEQUATELY COATED, SHALL BE RE-COATED BY THE CONTRACTOR AND RE-TESTED BY THE TESTING AGENCY.

HOT DIP GALVANIZING

HOT-DIP GALVANIZE ALL STRUCTURAL STEEL MEMBERS AND ALL STEEL ACCESSORIES, BOLTS, WASHERS, ETC., PER ASTM A123 OR PER ASTM A153, AS APPROPRIATE.

PROPERLY PREPARE STEEL ITEMS FOR GALVANIZING.

DRILL OR PUNCH WEEP AND/OR DRAINAGE HOLES AS REQUIRED.

ALL GALVANIZING SHALL BE DONE AFTER FABRICATION IS COMPLETED AND PRIOR TO FIELD INSTALLATION.


PERPETUAL INSPECTION AND MAINTENANCE BY THE OWNER

AFTER THE CONTRACTOR HAS SUCCESSFULLY COMPLETED THE INSTALLATION OF THE MONOPOLE REINFORCING SYSTEM AND THE WORK HAS BEEN ACCEPTED BY THE OWNER, THE OWNER WILL BE RESPONSIBLE FOR THE LONG TERM AND PERPETUAL INSPECTION AND MAINTENANCE OF THE POLE AND REINFORCING SYSTEM.

THE MONOPOLE REINFORCING SYSTEM INDICATED IN THESE DOCUMENTS USES REINFORCING COMPONENTS THAT INVOLVE FIELD WELDING STEEL MEMBERS TO THE EXISTING GALVANIZED STEEL POLE STRUCTURE. THESE FIELD WELDED CONNECTIONS ARE SUBJECT TO CORROSION DAMAGE AND DETERIORATION IF THEY ARE NOT PROPERLY MAINTAINED AND COVERED WITH CORROSION PREVENTIVE COATING SUCH AS THE ZRC GALVANIZING COMPOUND SPECIFIED PREVIOUSLY. THE STRUCTURAL LOAD CARRYING CAPACITY OF THE REINFORCED POLE SYSTEM IS DEPENDENT UPON THE INSTALLED SIZE AND QUALITY, MAINTAINED SOUND CONDITION AND STRENGTH OF THESE FIELD WELDED CONNECTIONS. ANY CORROSION OF, DAMAGE TO, FATIGUE, FRACTURE, AND/OR DETERIORATION OF THESE WELDS AND/OR THE CONNECTED COMPONENTS WILL RESULT IN THE LOSS OF STRUCTURAL LOAD CARRYING CAPACITY AND MAY LEAD TO FAILURE OF THE STRUCTURAL SYSTEM. THEREFORE, IT IS IMPERATIVE THAT THE OWNER REGULARLY INSPECTS, MAINTAINS, AND REPAIRS AS NECESSARY, ALL OF THESE WELDS, CONNECTIONS, AND COMPONENTS FOR THE LIFE OF THE STRUCTURE.

THE OWNER SHALL REFER TO TIA/EIA-222-F-1996, SECTION 14 AND ANNEX E FOR RECOMMENDATIONS FOR MAINTENANCE AND INSPECTION. THE FREQUENCY OF THE INSPECTION AND MAINTENANCE INTERVALS IS TO BE DETERMINED BY THE OWNER BASED UPON ACTUAL SITE AND ENVIRONMENTAL CONDITIONS. PAUL J. FORD & COMPANY RECOMMENDS THAT A COMPLETE AND THOROUGH INSPECTION OF THE ENTIRE REINFORCED MONOPOLE STRUCTURAL SYSTEM BE PERFORMED YEARLY AND/OR AS FREQUENTLY AS CONDITIONS WARRANT. ACCORDING TO TIA/EIA-222-F-1996 SECTION 14.1, NOTE 1: "IT IS RECOMMENDED THAT THE STRUCTURE BE INSPECTED AFTER SEVERE WIND AND/OR ICE STORMS OR OTHER EXTREME LOADING CONDITIONS".

APR 10 2014



PAUL J. FORD AND COMPANY
STRUCTURAL ENGINEERS
250 East Broad Street • Suite 600 • Columbus, Ohio 43215
(614) 221-6679 www.pjfweb.com

CROWN CASTLE

46 BROADWAY ALBANY, NY 12204
PH: (565) 899-3442 FAX: (565) 899-3448

© Copyright 2014, by Paul J. Ford and Company, All Rights Reserved. This document and the data contained herein, is proprietary to Paul J. Ford and Company, issued in strict confidence and shall not, without the prior written permission of Paul J. Ford and Company, be reproduced, copied or used for any purpose other than the intended use for this specific project.

BU #806953; BRG 2044 (A) 943097

STAMFORD, CONNECTICUT
MONOPOLE REINFORCEMENT AND RETROFIT PROJECT

PROJECT No:
37513-2318A

DRAWN BY:
T.A.N.

CHECKED BY:
J.J.F.

APPROVED BY:

DATE:
4-7-2014

ISSUE DATE OF
PERMIT A: 4-7-2014

S-2

AJAX BOLT NOTE SHEET: REV. 1.4, 5-20-2013

NOTES: 1. ALL STRUCTURAL BOLTS SHALL BE INSTALLED AND TIGHTENED TO THE PRETENSIONED CONDITION ACCORDING TO THE REQUIREMENTS OF THE AISC 'SPECIFICATION FOR STRUCTURAL JOINTS USING HIGH-STRENGTH BOLTS', DEC. 31, 2009.

2. ALL STRUCTURAL BOLTS SHALL BE INSPECTED ACCORDING TO THE REQUIREMENTS OF THE AISC 'SPECIFICATION FOR STRUCTURAL JOINTS USING HIGH-STRENGTH BOLTS', DEC. 31, 2009.

3. ALL AJAX M20 BOLTS WITH SHEAR SLEEVES SHALL BE PRETENSIONED AND TIGHTENED UNTIL THE DIRECT TENSION INDICATOR (DTI) WASHERS SHOW THAT THE PROPER BOLT TENSION HAS BEEN REACHED. SEE NOTES AND DETAIL BELOW FOR THE USE OF DIRECT TENSION INDICATOR (DTI) WASHERS WITH THE AJAX M20 BOLTS.

4. ALL AJAX BOLTS SHALL BE INSTALLED USING DIRECT TENSION INDICATORS (DTI'S) AND HARDENED WASHERS. DTI'S SHALL BE THE SQUIRTER® STYLE, MADE TO ASTM F959 LATEST REVISION; AND HARDENED WASHERS SHALL CONFORM TO ASTM F436 AND HAVE A HARDNESS OF RC 38 OR HIGHER.

NOTES FOR AJAX M20 'ONE-SIDE' BOLTS WITH DIRECT TENSION INDICATORS (DTI'S):

DTI'S REQUIRED: DTI'S SHALL BE "SELF-INDICATING" SQUIRTER® STYLE DTI'S MADE WITH SILICONE EMBEDDED IN THEM, INSPECTED BY MEANS OF THE VISUAL EJECTION OF SILICONE AS THE DTI PROTRUSIONS COMPRESS. SQUIRTER® DTI'S SHALL BE CALIBRATED PER MANUFACTURER'S INSTRUCTIONS PRIOR TO USE.

THE DIRECT TENSION INDICATOR (DTI) WASHERS SHALL BE THE "SQUIRTER® STYLE" AS MANUFACTURED BY:

APPLIED BOLTING TECHNOLOGY PRODUCTS, INC.
1413 ROCKINGHAM ROAD BELLOW FALLS, VERMONT, USA 05101
PHONE 1-800-552-1999
WEBSITE: WWW.APPLIEDBOLTING.COM

DISTRIBUTORS OF SQUIRTER® DTI'S:
[HTTP://WWW.APPLIEDBOLTING.COM/APPLIED-BOLTING-DISTRIBUTORS.HTML](http://WWW.APPLIEDBOLTING.COM/APPLIED-BOLTING-DISTRIBUTORS.HTML)

DTI: USE DIRECT TENSION INDICATOR (DTI) WASHERS COMPATIBLE WITH 20 MM (M20) NOMINAL A325 BOLTS FOR THE AJAX M20 BOLTS. DTI'S SHALL NOT BE HOT-DIP GALVANIZED. DTI'S SHALL BE MECHANICALLY GALVANIZED (MG) BY THE COLD MECHANICAL PROCESS ONLY AS PROVIDED BY THE DTI MANUFACTURER.


HARDENED WASHERS REQUIRED: USE A HARDENED WASHER FOR A 20 MM (M20) NOMINAL BOLT BETWEEN THE TOP OF THE DIRECT TENSION INDICATOR (DTI) WASHER AND THE NUT OF THE AJAX M20 BOLTS. HARDENED WASHERS SHALL CONFORM TO ASTM F436 AND HAVE A MINIMUM HARDNESS OF RC 38 OR HIGHER. THE HARDENED WASHERS SHALL BE MECHANICALLY GALVANIZED BY THE COLD MECHANICAL PROCESS. ALTERNATIVELY, CORRECTLY MADE HOT DIP GALVANIZED HARDENED FLAT WASHERS HAVING A MINIMUM HARDNESS OF RC 38 CAN BE USED; CONTRACTOR SHALL PROVIDE DOCUMENTATION OF WASHER SPECIFICATION AND HARDNESS.

NUT LUBRICATION REQUIRED: PROPERLY LUBRICATE THE THREADS OF THE NUT OF THE AJAX BOLT SO THAT IT CAN BE PROPERLY TIGHTENED WITHOUT GALLING AND/OR LOCKING UP ON THE BOLT THREADS. CONTRACTOR SHALL FOLLOW DTI MANUFACTURER INSTRUCTIONS FOR PROPER LUBRICATION AND TIGHTENING.

NOTE: COMPLETELY COMPRESSED DTI'S SHOWING NO VISIBLE REMAINING GAP ARE ACCEPTABLE. DTI WASHERS SHALL BE PLACED DIRECTLY AGAINST THE OUTER AJAX WASHER WITH THE DTI BUMPS FACING AWAY FROM THE AJAX WASHER. PLACE A HARDENED WASHER BETWEEN THE DTI AND THE AJAX NUT. THE DTI BUMPS SHALL BEAR AGAINST THE UNDERSIDE OF A HARDENED FLAT WASHER, NEVER DIRECTLY AGAINST THE NUT.

CONTRACTOR SHALL FOLLOW DTI MANUFACTURER'S INSTRUCTIONS FOR INSTALLATION, LUBRICATION, TIGHTENING AND INSPECTION.

INSPECTION REQUIRED: ALL AJAX BOLTS SHALL BE INSPECTED ACCORDING TO THE REQUIREMENTS OF THE AISC 'SPECIFICATION FOR STRUCTURAL JOINTS USING HIGH-STRENGTH BOLTS', DEC. 31, 2009, BY A QUALIFIED BOLT INSPECTOR. DURING INSTALLATION, THE BOLT INSPECTOR SHALL VERIFY AND DOCUMENT: THE SHOP-DRILLED AND FIELD-DRILLED HOLE SIZES; THE INSTALLATION OF THE AJAX BOLT ASSEMBLY, INCLUDING THE SHEAR SLEEVE PLACEMENT AND NUT LUBRICATION; AND THE CONTRACTOR'S TENSIONING PROCEDURE. IN ADDITION, ALL AJAX BOLTS AND DTI'S SHALL BE VISUALLY INSPECTED ACCORDING TO THE DTI MANUFACTURER'S INSTRUCTIONS. THE BOLT INSPECTOR SHALL PROVIDE COMPLETE PHOTO DOCUMENTATION OF ALL BOLTS AFTER TIGHTENING CLEARLY SHOWING THE CONDITION OF THE DTI'S.



APR 10 2014

PAUL J. FORD AND COMPANY
STRUCTURAL ENGINEERS
250 East Broad Street - Suite 600 - Columbus, Ohio 43215
(614) 221-6675
www.pjfweb.com

CROWN CASTLE
46 BROADWAY ALBANY, NY 12204
PH: (565) 899-3442
FAX: (565) 899-3448

© Copyright 2014, by Paul J. Ford and Company, All Rights Reserved. This document and the data contained herein, is proprietary to Paul J. Ford and Company, issued in strict confidence and shall not, without the prior written permission of Paul J. Ford and Company, be reproduced, copied or used for any purpose other than the intended use for this specific project.

PROJECT No: 37513-2318A
DRAWN BY: T.A.N.
CHECKED BY: J.J.F.
APPROVED BY:

BU #806953; BRG 2044 (A) 943097
STAMFORD, CONNECTICUT
MONOPOLE REINFORCEMENT AND RETROFIT PROJECT

ISSUE DATE OF PERMIT A: 4-7-2014

DATE: 4-7-2014

S-3

POLE SPECIFICATIONS	
POLE SHAPE TYPE:	12-SIDED POLYGON
TAPER:	0.2401 IN/FT
SHAFT STEEL:	ASTM A572 GRADE 65
BASE PL STEEL:	ASTM A633 GR. E (60 KSI)
ANCHOR RODS:	2 1/4" #16J ASTM A615 GRADE 75


SHAFT SECTION DATA					
SHAFT SECTION	SECTION LENGTH (FT)	PLATE THICKNESS (IN)	LAP SPLICE (IN)	DIAMETER ACROSS FLATS (IN)	
				@ TOP	@ BOTTOM
1	48.67	0.2500	54.00	19.6000	31.2900
2	42.75	0.3438	69.00	29.6883	39.9120
3	42.67	0.4063	80.00	37.8466	48.0880
4	43.00	0.4375		45.6745	56.0000

NOTE: DIMENSIONS SHOWN DO NOT INCLUDE GALVANIZING TOLERANCES

CONTRACTOR SHALL PROVIDE ASTM A38 SHIM PLATES BELOW SLIP JOINTS. THE SHIM PLATES SHALL BE PLACED BETWEEN THE NEW SHAFT REINFORCEMENT AND THE EXISTING POLE SHAFT FROM THE SLIP JOINT TO THE NEW SHAFT REINFORCEMENT SPLICE PLATE LOCATION AND A EXTRA LONG "SPLICE SHIM" SHALL BE PLACED BETWEEN THE NEW UPPER AND LOWER SHAFT REINFORCEMENT PLATES AT THE SHAFT REINFORCEMENT SPLICE PLATE LOCATION AND ALL TERMINATION POINTS, AS REQUIRED.


MODIFICATIONS:

- (A) INSTALL NEW SHAFT REINFORCING. SEE CHART.
- (B) REMOVE EXISTING MOUNT AND EQUIPMENT AT EL. 126±



* (B) EXISTING MOUNTS AND EQUIPMENT AT 126± TO BE REMOVED AS PART OF THE MODIFICATION.

POLE ELEVATION 1
S-4



APR 10 2014

CROWN CASTLE US PATENT NOS 8,046,972; 8,156,712; 7,849,659; 8,424,269 AND PATENT PENDING

PAUL J. FORD AND COMPANY
STRUCTURAL ENGINEERS
230 East Broad Street · Suite 600 · Columbus, Ohio 43215
(614) 221-0675 www.pjfweb.com

CROWN CASTLE
46 BROADWAY ALBANY, NY 12204
PH: (565) 899-3442 FAX: (565) 899-3448

BU #806953; BRG 2044 (A) 943097
STAMFORD, CONNECTICUT
MONOPOLE REINFORCEMENT AND RETROFIT PROJECT

PROJECT No: 37513-2318A
DRAWN BY: T.A.N.
CHECKED BY: J.J.F.
APPROVED BY:
DATE: 4-7-2014

ISSUE DATE OF PERMIT A: 4-7-2014

S-4

NEW CCI FLAT PLATE (65 KSI) REINFORCING SCHEDULE											
CROWN CASTLE CATALOG PART NUMBER	BOTTOM ELEVATION	TOP ELEVATION	FLAT #/ DEGREE SEPARATION	ELEMENT LENGTH	ELEMENT QUANTITY	MINIMUM AJAX BOLTS PER ELEMENT	MINIMUM TOTAL AJAX BOLT QUANTITY	TERMINATION BOLTS (BOTTOM)	TERMINATION BOLTS (TOP)	MAXIMUM INTERMEDIATE BOLT SPACING	ESTIMATED TOTAL STEEL WEIGHT
CCI-AFP-08010020	12'-3"	32'-3"	3, 7 & 11	1"x6"	3	31	93	10	10	16"	1225 LBS.
CCI-AFP-08010020	32'-4"	52'-4"	3, 7 & 11	1"x6"	3	31	93	10	10	16"	1225 LBS.
CCI-AFP-08010010	78'-6"	88'-6"	3, 7 & 11	1"x6"	3	23	69	10	10	16"	612 LBS.
255											
3062 LBS.											



- NOTES:**
- 1.) AJAX BOLTS ARE TO BE 20mm DIAMETER WITH CORRESPONDING 28mm DIAMETER SLEEVE WITH MAT CHING STEEL GRADE.
 - 2.) ALL STEEL SHALL BE HOT-DIP GALVANIZED AFTER FABRICATION IN ACCORDANCE WITH ASTM A123. ALTERNATIVELY, ALL NEW STIFFENER PLATE STEEL REINFORCING MAY BE COLD GALVANIZED AS FOLLOWS. APPLY A MINIMUM OF TWO COATS OF ZRC-BRAND ZINC-RICH COLD GALVANIZING COMPOUND. FILM THICKNESS PER COAT SHALL BE: WET 3.0 MILS; DRY 1.5 MILS. APPLY PER ZRC (MANUFACTURER) RECOMMENDED PROCEDURES. CONTACT ZRC AT 1-800-831-3275 FOR PRODUCT INFORMATION.
 - 3.) ALL REINFORCING SHALL BE ASTM A572 GR. 65.
 - 4.) WELDS ARE ASSUMED E80XX OR GREATER. TERMINATION WELDS SHALL BE 3/8" FILLET WELDS.
 - 5.) HOLES FOR AJAX BOLTS AND SHEAR SLEEVES ARE 30mm UNLESS NOTED OTHERWISE.
 - 6.) ALL SHIMS SHALL BE ASTM A-36.

SPLICE PLATE INSTALLATION CHART								
ELEVATION	FLAT PLATE THICKNESS	FLAT PLATE WIDTH	FLAT PLATE LENGTH	FLAT PLATE QUANTITY	WELD LENGTH PER SIDE	TOTAL WELD LENGTH	AJAX BOLTS PER SPLICE*	TOTAL STEEL WEIGHT
32'-3"	1"	8"	5'-7"	3	1"	0"	20	457 LBS.

* BOLTS INCLUDED IN THE TOTAL QUANTITY LISTED IN THE FLAT PLATE INSTALLATION CHART.

NEW SHIM CHART				
SHIM QUANTITY	SHIM WIDTH	SHIM LENGTH	SHIM THICKNESS	HOLE DIAMETER
21	4"	4"	1/4"	1-1/4"
39	4"	4"	1/16"	1-1/4"

SHIM QUANTITIES ARE APPROXIMATE AND ARE FOR BIDDING PURPOSES



APR 10 2014

CROWN CASTLE
 46 BROADWAY ALBANY, NY 12204
 PH: (518) 899-3442

BU #806953; BRG 2044 (A) 943097
STAMFORD, CONNECTICUT
 MONOPOLE REINFORCEMENT AND RETROFIT PROJECT

PROJECT No: 37513-2318A
 DRAWN BY: T.A.N.
 CHECKED BY: J.J.F.
 APPROVED BY: [Signature]
 DATE: 4-7-2014

ISSUE DATE OF PERMIT A: 4-7-2014

S-5

© Copyright 2014, by Paul J. Ford and Company, All Rights Reserved. This document and the data contained herein, is proprietary to Paul J. Ford and Company, issued in strict confidence and shall not, without the prior written permission of Paul J. Ford and Company, be reproduced, copied or used for any purpose other than the intended use for this specific project.

MODIFICATION INSPECTION NOTES:**GENERAL**

THE MODIFICATION INSPECTION (MI) IS A VISUAL INSPECTION OF TOWER MODIFICATIONS AND A REVIEW OF CONSTRUCTION INSPECTIONS AND OTHER REPORTS TO ENSURE THE INSTALLATION WAS CONSTRUCTED IN ACCORDANCE WITH THE CONTRACT DOCUMENTS, NAMELY THE MODIFICATION DRAWINGS, AS DESIGNED BY THE ENGINEER OF RECORD (EOR).

THE MI IS TO CONFIRM INSTALLATION CONFIGURATION AND WORKMANSHIP ONLY AND IS NOT A REVIEW OF THE MODIFICATION DESIGN ITSELF. NOR DOES THE MI INSPECTOR TAKE OWNERSHIP OF THE MODIFICATION DESIGN. OWNERSHIP OF THE STRUCTURAL MODIFICATION DESIGN EFFECTIVENESS AND INTEGRITY RESIDES WITH THE EOR AT ALL TIMES.

ALL MTS SHALL BE CONDUCTED BY A CROWN ENGINEERING VENDOR (AEV) OR ENGINEERING SERVICE VENDOR (AESV) THAT IS APPROVED TO PERFORM ELEVATED WORK FOR CROWN. SEE ENG-BUL-10773 LIST OF APPROVED MI VENDORS.

TO ENSURE THAT THE REQUIREMENTS OF THE MI ARE MET, IT IS VITAL THAT THE GENERAL CONTRACTOR (GC) AND THE MI INSPECTOR BEGIN COMMUNICATING AND COORDINATING AS SOON AS A PO IS RECEIVED. IT IS EXPECTED THAT EACH PARTY WILL BE PROACTIVE IN REACHING OUT TO THE OTHER PARTY. IF CONTACT INFORMATION IS NOT KNOWN, CONTACT YOUR CROWN POINT OF CONTACT (POC).

REFER TO ENG-SOW-10007 - MODIFICATION INSPECTION SOW FOR FURTHER DETAILS AND REQUIREMENTS.

MI INSPECTOR

THE MI INSPECTOR IS REQUIRED TO CONTACT THE GC AS SOON AS RECEIVING A PO FOR THE MI TO, AT A MINIMUM:

- REVIEW THE REQUIREMENTS OF THE MI CHECKLIST
- WORK WITH THE GC TO DEVELOP A SCHEDULE TO CONDUCT ON-SITE INSPECTIONS, INCLUDING FOUNDATION INSPECTIONS

THE MI INSPECTOR IS RESPONSIBLE FOR COLLECTING ALL GENERAL CONTRACTOR (GC) INSPECTION AND TEST REPORTS, REVIEWING THE DOCUMENTS FOR ADHERENCE TO THE CONTRACT DOCUMENTS, CONDUCTING THE IN-FIELD INSPECTIONS, AND SUBMITTING THE MI REPORT TO CROWN.

GENERAL CONTRACTOR

THE GC IS REQUIRED TO CONTACT THE MI INSPECTOR AS SOON AS RECEIVING A PO FOR THE MODIFICATION INSTALLATION OR TURNKEY PROJECT TO, AT A MINIMUM:

- REVIEW THE REQUIREMENTS OF THE MI CHECKLIST
- WORK WITH THE MI INSPECTOR TO DEVELOP A SCHEDULE TO CONDUCT ON-SITE INSPECTIONS, INCLUDING FOUNDATION INSPECTIONS
- BETTER UNDERSTAND ALL INSPECTION AND TESTING REQUIREMENTS

THE GC SHALL PERFORM AND RECORD THE TEST AND INSPECTION RESULTS IN ACCORDANCE WITH THE REQUIREMENTS OF THE MI CHECKLIST AN ENG-SOW-10007.

RECOMMENDATIONS

THE FOLLOWING RECOMMENDATIONS AND SUGGESTIONS ARE OFFERED TO ENHANCE THE EFFICIENCY AND EFFECTIVENESS OF DELIVERING A MI REPORT:

- IT IS SUGGESTED THAT THE GC PROVIDE A MINIMUM OF 5 BUSINESS DAYS NOTICE, PREFERABLE 10, TO THE MI INSPECTOR AS TO WHEN THE SITE WILL BE READY FOR THE MI TO BE CONDUCTED.
- THE GC AND MI INSPECTOR COORDINATE CLOSELY THROUGHOUT THE ENTIRE PROJECT.
- WHEN POSSIBLE, IT IS PREFERRED TO HAVE THE GC AND MI INSPECTOR ON-SITE SIMULTANEOUSLY FOR ANY GUY WIRE TENSIONING OR RE-TENSIONING OPERATIONS
- IT MAY BE BENEFICIAL TO INSTALL ALL TOWER MODIFICATIONS PRIOR TO CONDUCTING THE FOUNDATION INSPECTIONS TO ALLOW FOUNDATION AND MI INSPECTIONS TO COMMENCE WITH ONE SITE VISIT.
- WHEN POSSIBLE, IT IS PREFERRED TO HAVE THE GC AND MI INSPECTOR ON-SITE DURING THE MI TO HAVE ANY DEFICIENCIES CORRECTED DURING THE INITIAL MI. THEREFORE, THE GC MAY CHOOSE TO COORDINATE THE MI CAREFULLY TO ENSURE ALL CONSTRUCTION FACILITIES ARE AT THEIR DISPOSAL WHEN THE MI INSPECTOR IS ON-SITE.

CANCELLATION OR DELAYS IN SCHEDULED MI

IF THE GC AND MI INSPECTOR AGREE TO A DATE ON WHICH THE MI WILL BE CONDUCTED, AND EITHER PARTY CANCELS OR DELAYS, CROWN SHALL NOT BE RESPONSIBLE FOR ANY COSTS, FEES, LOSS OF DEPOSITS AND/OR OTHER PENALTIES RELATED TO THE CANCELLATION OR DELAY INCURRED BY EITHER PARTY FOR ANY TIME (E.G. TRAVEL AND LODGING, COSTS OF KEEPING EQUIPMENT ON-SITE, ETC.). IF CROWN CONTRACTS DIRECTLY FOR A THIRD PARTY MI, EXCEPTIONS MAY BE MADE IN THE EVENT THAT THE DELAY/CANCELLATION IS CAUSED BY WEATHER OR OTHER CONDITIONS THAT MAY COMPROMISE THE SAFETY OF THE PARTIES INVOLVED.

CORRECTION OF FAILING MTS

IF THE MODIFICATION INSTALLATION WOULD FAIL THE MI ("FAILED MI"), THE GC SHALL WORK WITH CROWN TO COORDINATE A REMEDIATION PLAN IN ONE OF TWO WAYS:

- CORRECT FAILING ISSUES TO COMPLY WITH THE SPECIFICATIONS CONTAINED IN THE ORIGINAL CONTRACT DOCUMENTS AND COORDINATE A SUPPLEMENT MI
- OR, WITH CROWN'S APPROVAL, THE GC MAY WORK WITH THE EOR TO RE-ANALYZE THE MODIFICATION/REINFORCEMENT USING THE AS-BUILT CONDITION

MI VERIFICATION INSPECTIONS

CROWN RESERVES THE RIGHT TO CONDUCT A MI VERIFICATION INSPECTION TO VERIFY THE ACCURACY AND COMPLETENESS OF PREVIOUSLY COMPLETED MI INSPECTIONS(S) ON TOWER MODIFICATION PROJECTS.

ALL VERIFICATION INSPECTIONS SHALL BE HELD TO THE SAME SPECIFICATIONS AND REQUIREMENTS IN THE CONTRACT DOCUMENTS AND IN ACCORDANCE WITH ENG-SOW-10007.

VERIFICATION INSPECTION MAY BE CONDUCTED BY AN INDEPENDENT AEV/AESV FIRM AFTER A MODIFICATION PROJECT IS COMPLETED, AS MARKED BY THE DATE OF AN ACCEPTED "PASSING MI" OR "PASS AS NOTED MI" REPORT FOR THE ORIGINAL PROJECT.

PHOTOGRAPHS

BETWEEN THE GC AND THE MI INSPECTOR THE FOLLOWING PHOTOGRAPHS, AT A MINIMUM, ARE TO BE TAKEN AND INCLUDED IN THE MI REPORT:

- PRE-CONSTRUCTION GENERAL SITE CONDITION
- PHOTOGRAPHS DURING THE REINFORCEMENT MODIFICATION CONSTRUCTION/RESECTION AND INSPECTION
- RAW MATERIALS
- PHOTOS OF ALL CRITICAL DETAILS
- FOUNDATION MODIFICATIONS
- WELD PREPARATION
- BOLT INSTALLATION AND TORQUE
- FINAL INSTALLED CONDITION
- SURFACE COATING REPAIR
- POST CONSTRUCTION PHOTOGRAPHS
- FINAL INFIELD CONDITION


PHOTOS OF ELEVATED MODIFICATIONS TAKEN FROM THE GROUND SHALL BE CONSIDERED INADEQUATE.

THIS IS NOT A COMPLETE LIST OF REQUIRED PHOTOS. PLEASE REFER TO ENG-SOW-10007.

CONSTRUCTION/INSTALLATION INSPECTIONS AND TESTING REQUIRED (COMPLETED BY EOR)	MI CHECKLIST	REPORT ITEM
	PRE-CONSTRUCTION	
	MI CHECKLIST DRAWINGS	
	EOR APPROVED SHOP DRAWINGS	
	FABRICATION INSPECTION	
	FABRICATOR CERTIFIED WELD INSPECTION	
	MATERIAL TEST REPORT (MTR)	
	FABRICATOR NDE INSPECTION	
	NDE REPORT OF MONOPOLE BASE PLATE (AS REQUIRED)	
	PACKING SLIPS	
	ADDITIONAL TESTING AND INSPECTIONS:	
	CONSTRUCTION	
	CONSTRUCTION INSPECTIONS	
	FOUNDATION INSPECTIONS	
	CONCRETE COMP. STRENGTH AND SLUMP TESTS	
	POST INSTALLED ANCHOR ROD VERIFICATION	
	BASE PLATE GROUT VERIFICATION	
	CONTRACTOR'S CERTIFIED WELD INSPECTION	
	EARTHWORK: LIFT AND DENSITY	
	ON SITE COLD GALVANIZING VERIFICATION	
	GUY WIRE TENSION REPORT	
	GC AS-BUILT DOCUMENTS	
	THIRD PARTY ONSITE INSPECTION OF BOLT PRETENSION PER CROWN REQUIREMENTS	
	INSPECTION OF AJAX BOLTS AND DTTS PER REQUIREMENTS ON SHEET S-3	
	ADDITIONAL TESTING AND INSPECTIONS:	
	POST-CONSTRUCTION	
	MI INSPECTOR REDLINE OR RECORD DRAWING(S)	
	THIRD PARTY ONSITE BOLT INSPECTION REPORT	
	POST INSTALLED ANCHOR ROD PULL-OUT TESTING	
	PHOTOGRAPHS	
	ADDITIONAL TESTING AND INSPECTIONS:	

NOTE: X DENOTES A DOCUMENT NEEDED FOR THE PMI REPORT

NA DENOTES A DOCUMENT THAT IS NOT REQUIRED FOR THE PMI REPORT



APR 10 2014

PAUL J. FORD AND COMPANY
STRUCTURAL ENGINEERS
250 East Broad Street - Suite 600 - Columbus, Ohio 43215
(614) 221-6679
www.pjweb.com

CROWN CASTLE
46 BROADWAY ALBANY, NY 12204
PH: (518) 899-3442

© Copyright 2014, by Paul J. Ford and Company, All Rights Reserved. This document and the data contained herein, is proprietary to Paul J. Ford and Company, issued in strict confidence and shall not, without the prior written permission of Paul J. Ford and Company, be reproduced, copied or used for any purpose other than the intended use for this specific project.

BU #806953; BRG 2044 (A) 943097

STAMFORD, CONNECTICUT
MONOPOLE REINFORCEMENT AND RETROFIT PROJECT

PROJECT No:
37513-2318A

DRAWN BY:
T.A.N.

CHECKED BY:
J.J.F.

APPROVED BY:

DATE:
4-7-2014

ISSUE DATE OF
PERMIT A: 4-7-2014

S-6

RADIO FREQUENCY FCC REGULATORY COMPLIANCE
MAXIMUM PERMISSIBLE EXPOSURE (MPE) ASSESSMENT

Sprint Existing Facility

Site ID: CT03XC344

Merritt 4 - Roxbury (Crown)

69 Guinea Road
Stamford, CT 06903

March 10, 2014

EBI Project Number: 62140952

March 10, 2014

Sprint
Attn: RF Engineering Manager
1 International Boulevard, Suite 800
Mahwah, NJ 07495

Re: Radio Frequency Maximum Permissible Exposure (MPE) Assessment for Site:
CT03XC344 - Merritt 4 - Roxbury (Crown)

Site Total: 43.172% - MPE % in full compliance

EBI Consulting was directed to analyze the proposed upgrades to the existing Sprint facility located at 69 Guinea Road, Stamford, CT, for the purpose of determining whether the radio frequency (RF) exposure levels from the proposed Sprint equipment upgrades on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter ($\mu\text{W}/\text{cm}^2$). The number of $\mu\text{W}/\text{cm}^2$ calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits, therefore it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) – (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general public may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general public would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

Public exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter ($\mu\text{W}/\text{cm}^2$). The general population exposure limit for the cellular band (850 MHz Band) is approximately $567 \mu\text{W}/\text{cm}^2$, and the general population exposure limit for the 1900 MHz and 2500 MHz bands is $1000 \mu\text{W}/\text{cm}^2$. Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.

Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure. Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

CALCULATIONS

Calculations were done for the proposed upgrades to the existing Sprint Wireless antenna facility located at 69 Guinea Road, Stamford, CT, using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. All calculations were performed assuming the main lobe of the antenna was focused at the base of the tower to present a worst case scenario. Actual values seen from this site will be dramatically less than those shown in this report. For this report the sample point is the top of a 6 foot person standing at the base of the tower.

For all calculations, all emissions were calculated using the following assumptions:

- 1) 2 channels in the 1900 MHz Band were considered for each sector of the proposed installation.
- 2) 1 channel in the 800 MHz Band was considered for each sector of the proposed installation
- 3) 2 channels in the 2500 MHz Band were considered for each sector of the proposed installation.
- 4) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 - Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.
- 5) For the following calculations the sample point was the top of a six foot person standing at the base of the tower. The maximum gain of the antenna per the antenna manufactures supplied specifications was used in this direction.

- 6) The antennas used in this modeling are the RFS APXVSPP18-C-A20 and the RFS APXVTMM-C-120. This is based on feedback from the carrier with regards to anticipated antenna selection. The RFS APXVSPP18-C-A20 has a 15.9 dBd gain value at its main lobe at 1900 MHz and 13.4 dBd at its main lobe for 850 MHz. The RFS APXVTMM-C-120 has a 15.9 dBd gain value at its main lobe at 2500 MHz. All calculations were performed assuming the main lobe of the antenna was focused at the base of the tower to present a worst case scenario.
- 7) The antenna mounting height centerline for the proposed antennas is **158 feet** above ground level (AGL).
- 8) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.

All calculation were done with respect to uncontrolled / general public threshold limits

Site ID	CT03XC344 - Merritt 4 - Roxbury (Crown)
Site Address	69 Guinea Road, Stamford, CT 06903
Site Type	Monopole

Sector 1

Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain in direction of sample point (dBd)	Antenna Height (ft)	analysis height	Antenna Height Meters	Cable Size	Cable Loss (dB)	Additional Loss (dB)	Gain Factor	ERP	Power Density Value	Power Density Percentage
1a	RFS	APXVSPP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	2	40	15.9	158	152	46.33016	1/2 "	0.5	3	17.378008	695.12033	10.8163	1.08163%
1a	RFS	APXVSPP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	13.4	158	152	46.33016	1/2 "	0.5	3	9.7723722	195.44744	3.041227	0.53637%
1B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	13.4	158	152	46.33016	1/2 "	0.5	3	9.7723722	390.89489	6.082453	1.07274%
Sector total Power Density Value:																		2.691%	

Sector 2

Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain in direction of sample point (dBd)	Antenna Height (ft)	analysis height	Antenna Height Meters	Cable Size	Cable Loss (dB)	Additional Loss (dB)	Gain Factor	ERP	Power Density Value	Power Density Percentage
2a	RFS	APXVSPP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	2	40	15.9	158	152	46.33016	1/2 "	0.5	3	17.378008	695.12033	10.8163	1.08163%
2a	RFS	APXVSPP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	13.4	158	152	46.33016	1/2 "	0.5	3	9.7723722	195.44744	3.041227	0.53637%
2B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	13.4	158	152	46.33016	1/2 "	0.5	3	9.7723722	390.89489	6.082453	1.07274%
Sector total Power Density Value:																		2.691%	

Sector 3

Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain in direction of sample point (dBd)	Antenna Height (ft)	analysis height	Antenna Height Meters	Cable Size	Cable Loss (dB)	Additional Loss (dB)	Gain Factor	ERP	Power Density Value	Power Density Percentage
3a	RFS	APXVSPP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	2	40	15.9	158	152	46.33016	1/2 "	0.5	3	17.378008	695.12033	10.8163	1.08163%
3a	RFS	APXVSPP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	13.4	158	152	46.33016	1/2 "	0.5	3	9.7723722	195.44744	3.041227	0.53637%
3B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	13.4	158	152	46.33016	1/2 "	0.5	3	9.7723722	390.89489	6.082453	1.07274%
Sector total Power Density Value:																		2.691%	

Site Composite MPE %	
Carrier	MPE %
Sprint	8.072%
T-Mobile	0.250%
Metricom	0.030%
Nextel	1.850%
AT&T	13.060%
Verizon Wireless	16.520%
XM Satellite Radio	3.390%
Total Site MPE %	43.172%

Summary

All calculations performed for this analysis yielded results that were well within the allowable limits for general public Maximum Permissible Exposure (MPE) to radio frequency energy.

The anticipated Maximum Composite contributions from the Sprint facility are **8.072% (2.691% from each sector)** of the allowable FCC established general public limit considering all three sectors simultaneously sampled at the ground level.

The anticipated composite MPE value for this site assuming all carriers present is **43.172%** of the allowable FCC established general public limit sampled at 6 feet above ground level. This total composite site value is based upon MPE values listed in the Connecticut Siting Council database for existing carrier emissions.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.



Scott Heffernan
RF Engineering Director

EBI Consulting
21 B Street
Burlington, MA 01803