



Northeast Site Solutions
Denise Sabo
199 Brickyard Rd Farmington, CT 06032
860-209-4690
denise@northeastsitesolutions.com

March 22, 2016

Members of the Siting Council
Connecticut Siting Council
Ten Franklin Square
New Britain, CT 06051

RE: Notice of Exempt Modification
555 Main St., Stamford, CT 06901
Latitude: 41.053535
Longitude: -73.535579
T-Mobile Site#: CT11410A_AIR32

Dear Ms. Bachman,

On behalf of T-Mobile, Northeast Site Solutions (NSS) is submitting an exempt modification application to the Connecticut Siting Council for modification of existing equipment at a tower facility located at 555 E. Main Street, Stamford CT 06901.

The 555 E. Main Street, Stamford, CT facility consists of a 125' Self Support Tower on a 106'-5" Rooftop. T-Mobile currently maintains six (6) antennas at the 210-foot AGL level and (3) antennas at the 203-foot AGL level. The tower and building are owned and operated by Frontier Communication Corporation. T-Mobile now intends to replace three (3) of its existing antennas with three (3) new 700 MHz antenna. The antennas will be installed at the 210-foot AGL level of the tower.

This facility was approved by the Council in Approvals dated April 13, 1998 and April 14, 1998 to a Notice of Intent to Modify an Existing Telecommunications Facility. These approvals included the following site-specific conditions: 1) Removal of the unused horn antenna, 2) matching the color of the proposed panel antennas with the tower, 3) removal of aviation beacons as soon as possible, consistent with FAA approval, 4) and repainting the tower to a solid neutral color, consistent with FAA approval, when such scheduled repainting is necessary, but no later than 10 years from the time of such FAA approval (see attached exhibit). The removal of horn antenna has been completed. The tower must be painted and lighted in accordance with the FAA Advisory Circular 70/7460-1L as per the Painting and Lighting Specifications on the ASR (see attached exhibit).

Please accept this letter as notification pursuant to Regulations of Connecticut State Agencies § 16-50j-73, for construction that constitutes an exempt modification pursuant to R.C.S.A. § 16-50j-72(b)(2). In accordance with R.C.S.A. § 16-50j-73, a copy of this letter is being sent to Brandon Robertson, Town Manager for the Town of Avon, as well as the property owner and the tower owner.



The planned modifications to the facility fall squarely within those activities explicitly provided for in R.C.S.A. § 16-50j-72(b)(2).

1. The proposed modifications will not result in an increase in the height of the existing structure.
2. The proposed modifications will not require the extension of the site boundary.
3. The proposed modifications will not increase noise levels at the facility by six decibels or more, or to levels that exceed state and local criteria.
4. The operation of the replacement antennas will not increase radio frequency emissions at the facility to a level at or above the Federal Communications Commission safety standard.
5. The proposed modifications will not cause a change or alteration in the physical or environmental characteristics of the site.
6. The existing structure and its foundation can support the proposed loading.

For the foregoing reasons, T-Mobile respectfully submits that the proposed modifications to the above referenced telecommunications facility constitute an exempt modification under R.C.S.A. § 16-50j-72(b)(2).

Sincerely,

Denise Sabo

Mobile: 860-209-4690

Fax: 413-521-0558

Office: 199 Brickyard Rd, Farmington, CT 06032

Email: denise@northeastsitesolutions.com

Attachments

cc: The Honorable David R. Martin, Mayor, City of Stamford – as Senior Elected Official
The Southern New England Telephone Company – as Property Owner and Tower Owner

Exhibit A



STATE OF CONNECTICUT
CONNECTICUT SITING COUNCIL

10 Franklin Square
New Britain, Connecticut 06051
Phone: (860) 827-2935
Fax: (860) 827-2950

April 13, 1998

Sharon Burrows
Omnipoint Communications
25 Van Zant Street, Suite 18E
Norwalk, CT 06855

Re: Omnipoint Communications notice of intent to modify an existing telecommunications facility located at 555 Main Street in Stamford, Connecticut.

Dear Ms. Burrows:

At a public meeting held on April 9, 1998, the Connecticut Siting Council (Council) acknowledged Omnipoint Communications (Omnipoint) notice to modify this existing telecommunications facility in Stamford, Connecticut, pursuant to Section 16-50j-73 of the Regulations of Connecticut State Agencies with conditions for removal of the unused horn antenna; matching the color of the proposed panel antennas with the tower; removal of aviation beacons as soon as possible, consistent with Federal Aviation Administration (FAA) approval; and repainting the tower to a solid neutral color, consistent with FAA approval, when such scheduled repainting is necessary, but no later than 10 years from the time of such FAA approval.

The proposed modifications as conditioned are to be implemented as specified here and in your notice dated March 12, 1998, and additional information submitted April 8, 1998. The modifications as conditioned are in compliance with the exception criteria in Section 16-50j-72 (b) of the Regulations of Connecticut State Agencies as changes to an existing facility site that would not increase tower height, extend the boundaries of the tower site, increase noise levels at the tower site boundary by six decibels, and increase the total radio frequency electromagnetic radiation power density measured at the tower site boundary to or above the standard adopted by the State Department of Environmental Protection pursuant to General Statutes § 22a-162. This facility has been carefully modeled to ensure that radio frequency emissions are conservatively below State and federal standards applicable to the frequency now used on this tower. Any additional change to this facility will require explicit notice to this agency pursuant to Regulations of Connecticut State Agencies Section 16-50j-73. Such notice shall include all relevant information regarding the proposed change with cumulative worst-case modeling of radio frequency exposure at the closest point of uncontrolled access to the tower base, consistent with Federal Communications Commission, Office of Engineering and Technology, Bulletin No. 65. Any deviation from this format may result in the Council implementing enforcement proceedings pursuant to General Statutes § 16-50u including, without limitation, imposition of expenses resulting from such failure and of civil penalties in an amount not less than one thousand dollars per day for each day of construction or operation in material violation.

Thank you for your attention and cooperation.

Very truly yours,

Mortimer A. Gelston
Chairman

MAG/RKE/sg

- c/ Honorable Dannel P. Malloy, Mayor, City of Stamford
Norman F. Cole, Principal Planner, City of Stamford
Peter J. Tyrrell, Senior Counsel, Springwich Cellular Ltd. Partnership



STATE OF CONNECTICUT
CONNECTICUT SITING COUNCIL

10 Franklin Square
New Britain, Connecticut 06051
Phone: (860) 827-2935
Fax: (860) 827-2950

April 14, 1998

Peter J. Tyrrell
Senior Counsel
Springwich Cellular Limited Partnership
500 Enterprise Drive
Rocky Hill, CT 06067-3900

Re: Omnipoint Communications notice of intent to modify an existing telecommunications facility located at 555 Main Street in Stamford, Connecticut.

Dear Attorney Tyrrell:

At a public meeting held on April 9, 1998, the Connecticut Siting Council (Council) acknowledged Omnipoint Communications (Omnipoint) notice to modify this existing telecommunications facility in Stamford, Connecticut, pursuant to Section 16-50j-73 of the Regulations of Connecticut State Agencies with conditions for removal of the unused horn antenna; matching the color of the proposed panel antennas with the tower; removal of aviation beacons as soon as possible, consistent with Federal Aviation Administration (FAA) approval; and repainting the tower to a solid neutral color, consistent with FAA approval, when such scheduled repainting is necessary, but no later than 10 years from the time of such FAA approval.

The proposed modifications as conditioned are to be implemented as specified here and in Omnipoint's notice dated March 12, 1998, and additional information submitted April 8, 1998. The modifications as conditioned are in compliance with the exception criteria in Section 16-50j-72 (b) of the Regulations of Connecticut State Agencies as changes to an existing facility site that would not increase tower height, extend the boundaries of the tower site, increase noise levels at the tower site boundary by six decibels, and increase the total radio frequency electromagnetic radiation power density measured at the tower site boundary to or above the standard adopted by the State Department of Environmental Protection pursuant to General Statutes § 22a-162. This facility has been carefully modeled to ensure that radio frequency emissions are conservatively below State and federal standards applicable to the frequency now used on this tower. Any additional change to this facility will require explicit notice to this agency pursuant to Regulations of Connecticut State Agencies Section 16-50j-73. Such notice shall include all relevant information regarding the proposed change with cumulative worst-case modeling of radio frequency exposure at the closest point of uncontrolled access to the tower base, consistent with Federal Communications Commission, Office of Engineering and Technology, Bulletin No. 65. Any deviation from this format may result in the Council implementing enforcement proceedings pursuant to General Statutes § 16-50u including, without limitation, imposition of expenses resulting from such failure and of civil penalties in an amount not less than one thousand dollars per day for each day of construction or operation in material violation.

Thank you for your attention and cooperation.

Very truly yours,

Mortimer A. Gelston
Chairman

MAG/RKE/sg

c: Honorable Dannel P. Malloy, Mayor, City of Stamford
Norman F. Cole, Principal Planner, City of Stamford
Sharon Burrows, Omnipoint Communications

Exhibit B



[FCC Home](#) | [Search](#) | [Updates](#) | [E-Filing](#) | [Initiatives](#) | [For Consumers](#) | [Find People](#)



Antenna Structure Registration

[FCC](#) > [WTB](#) > [ASR](#) > [Online Systems](#) > ASR Search

[FCC Site Map](#)

ASR Registration Search

Registration 1046319

[? HELP](#)

[New Search](#) [Return to Results](#) [Printable Page](#) [Reference Copy](#) [Map Registration](#)

Registration Detail

Reg Number	1046319	Status	Constructed
File Number	A0926190	Constructed	10/18/1999
EMI	Yes	Dismantled	
NEPA	No		

Antenna Structure

Structure Type BTWR - Building with Tower

Location (in NAD83 Coordinates - [Convert to NAD27](#))

Lat/Long	41-03-12.4 N 073-32-08.3 W	Address	555 MAIN STREET
City, State	STAMFORD , CT		
Zip	06901	County	FAIRFIELD
Center of AM Array		Position of Tower in Array	

Heights (meters)

Elevation of Site Above Mean Sea Level	Overall Height Above Ground (AGL)
3.7	76.5
Overall Height Above Mean Sea Level	Overall Height Above Ground w/o Appurtenances
80.2	76.3

Painting and Lighting Specifications

FAA Chapters 3, 4, 5, 13

Paint and Light in Accordance with FAA Circular Number [70/7460-1J](#)

FAA Notification

FAA Study	99-ANE-0338-OE	FAA Issue Date	10/18/1999
-----------	----------------	----------------	------------

Owner & Contact Information

FRN	0003576931	Owner Entity	Corporation
		Type	

Owner

The Southern New England Telephone Company	P: (931)528-1584
Attention To: Elissa E. McOmer	F:
250 South Franklin	E: elissa.mcomber@ftr.com
Cookeville , TN 38501	

Contact

Attention To: Elissa E. McOmber
250 South Franklin
Cookeville , TN 38501

P: (931)528-1584
F:
E: elissa.mcomber@ftr.com

Last Action Status

Status	Constructed	Received	11/07/2014
Purpose	Admin Update	Entered	11/07/2014
Mode	Interactive		

Related Applications

11/07/2014 [A0926190](#) - Admin Update (AU)
04/02/2014 [A0896535](#) - Admin Update (AU)
08/21/2001 [A0209321](#) - Notification (NT)

[All related applications \(6\)](#)

Comments

Comments

None

History

Date	Event
11/08/2014	Registration Printed
11/07/2014	ASR Application receipt email sent: Tower email
11/07/2014	Administrative Update Received

[All History \(10\)](#)

Automated Letters

11/08/2014 [Authorization](#), Reference
04/03/2014 [Authorization](#), Reference
04/09/2001 [Construction Reminder](#), Reference 124747

[All letters \(4\)](#)

ASR Help [ASR License Glossary](#) - [FAQ](#) - [Online Help](#) - [Documentation](#) - [Technical Support](#)

ASR Online Systems [TOWAIR](#)- [CORES](#) - [ASR Online Filing](#) - [Application Search](#) - [Registration Search](#)

About ASR [Privacy Statement](#) - [About ASR](#) - [ASR Home](#)

Registration Search

By Registration Number

SUBMIT

[FCC](#) | [Wireless](#) | [ULS](#) | [CORES](#)

[Help](#) | [Tech Support](#)

Federal Communications Commission
445 12th Street SW
Washington, DC 20554

Phone: 1-877-480-3201
TTY: 1-717-338-2824
[Submit Help Request](#)

Exhibit C

T-Mobile
T-MOBILE NORTHEAST LLC

SITE #: CT11410A

SITE NAME: STAMFORD / DWTN

SITE ADDRESS:

555 E MAIN STREET

STAMFORD, CT, 06901

WIRELESS BROADBAND FACILITY

CONSTRUCTION DRAWINGS

(702D CONFIGURATION)



T-MOBILE NORTHEAST, LLC
35 GRIFFIN ROAD SOUTH
BLOOMFIELD, CT 06002
OFFICE: (860) 692-7100
FAX: (860) 692-7159



286 Old Connecticut Path,
Wayland, MA 01778
Phone number: 617-852-3611
Fax Number: 781-742-2247

SUBMITTALS		
DATE	DESCRIPTION	REVISION
10/20/15	ISSUED FOR REVIEW	A
11/02/15	FINAL CD	0

DEPT.	DATE	APP'D	REVISIONS
RFE			
RF MAN.			
ZONING			
OPS			
CONSTR.			
SITE AC.			

PROJECT NO: CT11410A
DRAWN BY: PS
CHECKED BY: KM



THIS DOCUMENT IS THE CREATION, DESIGN, PROPERTY AND COPYRIGHTED WORK OF T-MOBILE. ANY DUPLICATION OR USE WITHOUT EXPRESS WRITTEN CONSENT IS STRICTLY PROHIBITED.

VICINITY MAP



DO NOT SCALE DRAWINGS

CONTRACTOR SHALL VERIFY PLANS AND EXISTING DIMENSIONS AND CONDITIONS ON THE JOB SITE AND SHALL IMMEDIATELY NOTIFY THE ARCHITECT IN WRITING OF ANY DISCREPANCIES BEFORE PROCEEDING WITH THE WORK OR BE RESPONSIBLE FOR SAME.

CALL BEFORE YOU DIG:
WWW.CBYD.COM
CALL 800 922 4455, OR 811
CALL THREE WORKING DAYS PRIOR TO DIGGING
SAFETY PRECAUTIONS SHALL BE IMPLEMENTED BY CONTRACTOR(S) AT ALL TRENCHING IN ACCORDANCE WITH CURRENT OSHA STANDARDS.

COLOR CODE FOR UTILITY LOCATIONS

ELECTRIC	- RED	SEWER	- GREEN
GAS/OIL	- YELLOW	SURVEY	- PINK
TEL/CATV	- ORANGE	PROPOSED EXCAVATION	- WHITE
WATER	- BLUE	RECLAIMED WATER	- PURPLE

GENERAL NOTES

- THE CONTRACTOR SHALL GIVE ALL NOTICES AND COMPLY WITH ALL LAWS, ORDINANCES, RULES, REGULATIONS AND LAWFUL ORDERS OF ANY PUBLIC AUTHORITY, MUNICIPAL AND UTILITY COMPANY SPECIFICATIONS, AND LOCAL AND STATE JURISDICTIONAL CODES BEARING ON THE PERFORMANCE OF THE WORK. THE WORK PERFORMED ON THE PROJECT AND THE MATERIALS INSTALLED SHALL BE IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS AND ORDINANCES.
- THE ARCHITECT/ENGINEER HAVE MADE EVERY EFFORT TO SET FORTH IN THE CONSTRUCTION AND CONSTRUCT DOCUMENTS THE COMPLETE SCOPE OF WORK. THE CONTRACTOR BIDDING THE JOB IS NEVERTHELESS CAUTIONED THAT MINOR OMISSIONS OR ERRORS IN THE DRAWINGS AND OR SPECIFICATIONS SHALL NOT EXCUSE SAID CONTRACTOR FROM COMPLETING THE PROJECT AND IMPROVEMENTS IN ACCORDANCE WITH THE INTENT OF THESE DOCUMENTS.
- THE CONTRACTOR OR BIDDER SHALL BEAR THE RESPONSIBILITY OF NOTIFYING (IN WRITING) THE T-MOBILE REPRESENTATIVE OF ANY CONFLICTS, ERRORS, OR OMISSIONS PRIOR TO THE SUBMISSION OF THE CONTRACTOR'S PROPOSAL OR PERFORMANCE OF WORK. IN THE EVENT OF DISCREPANCIES, THE CONTRACTOR SHALL PRICE THE MORE COSTLY OR EXPENSIVE WORK, UNLESS DIRECTED IN WRITING OTHERWISE.
- THE SCOPE OF WORK SHALL INCLUDE FURNISHING OF ALL MATERIALS, EQUIPMENT, LABOR AND ALL OTHER MATERIALS AND LABOR DEEMED NECESSARY TO COMPLETE THE WORK/PROJECT AS DESCRIBED HEREIN.
- THE CONTRACTOR SHALL VISIT THE JOB SITE PRIOR TO THE SUBMISSION OF BIDS OR PERFORMING WORK TO FAMILIARIZE HIMSELF WITH THE FIELD CONDITIONS AND TO VERIFY THAT THE PROJECT CAN BE CONSTRUCTED IN ACCORDANCE WITH THE CONTRACT DOCUMENTS.
- THE CONTRACTOR SHALL OBTAIN AUTHORIZATION TO PROCEED WITH CONSTRUCTION PRIOR TO STARTING WORK ON ANY ITEM NOT CLEARLY DEFINED BY THE CONSTRUCTION DRAWINGS/CONTRACT DOCUMENTS.
- THE CONTRACTOR SHALL INSTALL ALL EQUIPMENT AND MATERIALS ACCORDING TO THE MANUFACTURER'S/VENDOR'S SPECIFICATIONS UNLESS NOTED OTHERWISE OR WHERE LOCAL CODES OR ORDINANCES TAKE PRECEDENCE.
- THE CONTRACTOR SHALL PROVIDE A FULL SET OF CONSTRUCTION DOCUMENTS AT THE SITE UPDATED WITH THE LATEST REVISIONS AND ADDENDUM OR CLARIFICATIONS AVAILABLE FOR THE USE BY ALL PERSONNEL INVOLVED WITH THE PROJECT.
- THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE PROJECT DESCRIBED HEREIN. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR ALL CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES AND FOR COORDINATING ALL PORTIONS OF THE WORK UNDER CONTRACT.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ANY PERMITS AND INSPECTIONS WHICH ARE REQUIRED FOR THE WORK BY THE ARCHITECT/ENGINEER, THE STATE, COUNTY, OR LOCAL GOVERNMENT AUTHORITY.
- THE CONTRACTOR SHALL MAKE NECESSARY PROVISIONS TO PROTECT EXISTING IMPROVEMENTS, EASEMENTS, PAVING, CURBING, ETC., DURING CONSTRUCTION. UPON COMPLETION OF WORK, THE CONTRACTOR SHALL REPAIR ANY DAMAGE THAT MAY HAVE OCCURRED DUE TO CONSTRUCTION ON OR ABOUT THE PROPERTY.
- THE CONTRACTOR SHALL KEEP THE GENERAL WORK AREA CLEAN AND HAZARD FREE DURING CONSTRUCTION AND DISPOSE OF ALL DIRT, DEBRIS, RUBBISH AND REMOVE EQUIPMENT NOT SPECIFIED AS REMAINING ON PROPERTY. PREMISES SHALL BE LEFT IN CLEAN CONDITION AND FREE FROM PAINT SPOTS, DUST, OR SMUDGES OF ANY NATURE.
- THE CONTRACTOR SHALL COMPLY WITH ALL OSHA REQUIREMENTS, AS WELL AS THE LATEST EDITIONS OF ANY PERTINENT STATE SAFETY REGULATIONS.
- THE CONTRACTOR SHALL NOTIFY THE T-MOBILE REPRESENTATIVE WHERE A CONFLICT OCCURS ON ANY OF THE CONTRACT DOCUMENTS. THE CONTRACTOR IS NOT TO ORDER MATERIAL OR CONSTRUCT ANY PORTION OF THE WORK THAT IS IN CONFLICT UNTIL CONFLICT IS RESOLVED BY THE T-MOBILE REPRESENTATIVE.
- THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS, ELEVATIONS, PROPERTY LINES, ETC., ON THE JOB.
- THE CONTRACTOR SHALL RETURN ALL DISTURBED AREAS TO THEIR ORIGINAL CONDITION AT THE COMPLETION OF WORK.
- FINAL DESIGN PENDING STRUCTURAL EVALUATION.

SITE INFORMATION

SITE NUMBER: CT11410A
SITE NAME: STAMFORD / DWTN
SITE ADDRESS: 555 E MAIN STREET STAMFORD, CT, 06901
LAT./LONG.: N 41.053535 / W -73.535579
JURISDICTION: FAIRFIELD COUNTY
PROPERTY OWNER: FRONTIER COMMUNICATIONS
805 CENTRAL EXPRESSWAY SOUTH ALLEN, TX 75013
972-908-4165 (O)
214-437-8156 (C)
KELLEY.STEWART@FTR.COM

CODE COMPLIANCE

CONNECTICUT STATE BUILDING CODE
2005 CONNECTICUT BUILDING CODE WITH 2013 AMENDMENT
2011 NATIONAL ELECTRICAL CODE
CONSTRUCTION TYPE: 2B USE GROUP: N/A

PROJECT SUB-CONTRACTORS

APPLICANT: T-MOBILE NORTHEAST, LLC.
35 GRIFFIN ROAD SOUTH
BLOOMFIELD, CT 06002
(860) 692-7100
PROJECT MANAGER: LISA LIN ALLEN
NORTHEAST SITE SOLUTIONS
54 MAIN STREET
STURBRIDGE, MA 01566
(508) 434-5237
ARCHITECT/ENGINEER: ATLANTIS DESIGN GROUP INC.
286 OLD CONNECTICUT PATH,
WAYLAND, MA 01778
(617)-852-3611

SHEET INDEX

SHEET	DESCRIPTION
T-1	TITLE SHEET
N-1	GENERAL AND ELECTRICAL NOTES
A-1	SITE PLAN
A-2	ELEVATION
A-3	ANTENNA PLAN AND DETAILS
E-1	GROUNDING AND POWER ONE LINE DIAGRAM
E-2	GROUNDING DETAILS

SITE NAME
CT11410A

SITE NAME
STAMFORD / DWTN

SITE ADDRESS
555 E MAIN STREET
STAMFORD, CT, 06901

SHEET TITLE
TITLE SHEET

SHEET NUMBER
T-1

ELECTRICAL NOTES:

- WORK INCLUDED
1. INCLUDE ALL LABOR, MATERIALS, EQUIPMENT, PLANT SERVICES AND ADMINISTRATIVE TASKS REQUIRED TO COMPLETE AND MAKE OPERABLE THE ELECTRICAL WORK SHOWN ON THE DRAWINGS AND SPECIFIED HEREIN, INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
A. PREPARE AND SUBMIT SHOP DRAWINGS, DIAGRAMS AND ILLUSTRATIONS.
B. PROCURE ALL NECESSARY PERMITS AND APPROVALS AND PAY ALL REQUIRED FEES AND CHARGES IN CONNECTION WITH THE WORK OF THIS CONTRACT.
C. SUBMIT AS-BUILT DRAWINGS, OPERATING AND MAINTENANCE INSTRUCTIONS AND MANUALS.
D. EXECUTE ALL CUTTING, DRILLING, ROUGH AND FINISH PATCHING OF EXISTING OR NEWLY INSTALLED CONSTRUCTION REQUIRED FOR THE WORK OF THIS CONTRACT.
E. PROVIDE HANGERS, SUPPORTS, FOUNDATIONS, STRUCTURAL FRAMING SUPPORTS, AND BASES FOR CONDUIT AND EQUIPMENT PROVIDED OR INSTALLED UNDER THE WORK OF HIS CONTRACT.
F. MAINTAIN ALL EXISTING ELECTRICAL SERVICES IN THE BUILDING AREAS NOT AFFECTED BY THE ALTERATION DURING THE PROGRESS OF THE WORK INCLUDING PROVIDING ALL TEMPORARY JUMPERS, CONDUITS, CAPS, PROTECTIVE DEVICES, CONNECTIONS AND EQUIPMENT REQUIRED.
2. IT IS THE INTENT OF THESE DRAWINGS AND SPECIFICATIONS TO CALL FOR AN INSTALLATION THAT IS COMPLETE IN EVERY RESPECT. IT IS NOT THE INTENT TO GIVE EVERY DETAIL ON THE DRAWINGS AND IN THE SPECIFICATIONS.
GENERAL REQUIREMENTS
1. PROVIDE ALL WORK IN ACCORDANCE WITH THE NATIONAL ELECTRICAL CODE (NEC) AND LOCAL AND STATE ELECTRICAL CODES.
2. THE ELECTRICAL PLANS ARE DIAGRAMMATIC ONLY. REFER TO THE ARCHITECTURAL PLANS FOR THE EXACT DIMENSIONS OF THE BUILDING.
3. LOAD CALCULATIONS ARE BASED ON EXISTING BUILDING INFORMATION/DRAWINGS PROVIDED TO ENGINEERING.
4. EXISTING BUILDING EQUIPMENT IS NOTED ON THE DRAWINGS. NEW OR RELOCATED EQUIPMENT IS SHOWN WITH SOLID LINES.
5. GENERAL
A. AFTER CAREFULLY STUDYING THE DRAWINGS AND SPECIFICATIONS, AND BEFORE SUBMITTING THE PROPOSAL, MAKE A MANDATORY SITE VISIT TO ASCERTAIN CONDITIONS OF THE SITE, AND THE NATURE AND EXACT QUANTITY OF WORK TO BE PERFORMED.
B. VERIFY ALL MEASUREMENTS AT THE SITE AND BE RESPONSIBLE FOR CORRECTNESS OF SAME.
6. QUALITY, WORKMANSHIP, MATERIALS AND SAFETY
A. PROVIDE NEW MATERIALS AND EQUIPMENT OF A DOMESTIC MANUFACTURER BY THOSE REGULARLY ENGAGED IN THE PRODUCTION AND MANUFACTURE OF SPECIFIED MATERIALS AND EQUIPMENT.
B. WORK SHALL BE PERFORMED BY WORKMEN SKILLED IN THE TRADE REQUIRED FOR THE WORK.
C. PROVIDE LABOR, MATERIALS, APPARATUS AND APPLIANCES ESSENTIAL TO THE FUNCTIONING OF THE SYSTEMS DESCRIBED OR INDICATED HEREIN, OR WHICH MAY BE REASONABLY IMPLIED AS ESSENTIAL WHENEVER MENTIONED IN THE CONTRACT DOCUMENT OR NOT.
D. MAKE WRITTEN REQUESTS FOR SUPPLEMENTARY INSTRUCTIONS TO ARCHITECT/ENGINEER IN CASE OF DOUBT AS TO WORK INTENDED OR IN EVENT OF NEED FOR EXPLANATION THEREOF.
E. PERFORMANCE AND MATERIAL REQUIREMENTS SCHEDULED OR SPECIFIED ARE MINIMUM STANDARD ACCEPTABLE.
GUARANTEE
1. GUARANTEE MATERIALS, PARTS AND LABOR FOR WORK FOR ONE YEAR FROM THE DATE OF ISSUANCE OF OCCUPANCY PERMIT.

- CLEANING
1. REMOVE ALL CONSTRUCTION DEBRIS RESULTING FROM THE WORK.
2. CLEAN EQUIPMENT AND SYSTEMS FOLLOWING THE COMPLETION OF THE PROJECT TO THE SATISFACTION OF THE ENGINEER.
COORDINATION AND SUPERVISION
1. CAREFULLY LAY OUT ALL WORK IN ADVANCE TO AVOID UNNECESSARY CUTTING, CHANNELING, CHASING OR DRILLING OF FLOORS, WALLS, PARTITIONS, CEILINGS OR OTHER SURFACES.
SUBMITTALS
1. AS-BUILT DRAWINGS:
A. UPON COMPLETION OF THE WORK, FURNISH TO THE OWNER "AS-BUILT" DRAWINGS.
2. SERVICE MANUALS:
A. UPON COMPLETION OF THE WORK, FULLY INSTRUCT T-MOBILE AS TO THE OPERATION AND MAINTENANCE OF ALL MATERIAL, EQUIPMENT AND SYSTEMS.
CUTTING AND PATCHING
1. PROVIDE ALL CUTTING, DRILLING, ROUGH AND FINISH PATCHING REQUIRED TO COMPLETE THE WORK.
TESTS, INSPECTION AND APPROVAL
1. BEFORE ENERGIZING ANY ELECTRICAL INSTALLATION, INSPECT EACH UNIT IN DETAIL.
RACEWAYS
1. ALL WIRING TO BE INSTALLED IN CONDUIT SYSTEMS IN ACCORDANCE WITH THE FOLLOWING:
A. EXTERIOR FEEDERS AND CONTROL, WHERE UNDERGROUND, TO BE IN SCH 40 PVC.
B. EXTERIOR, ABOVE GROUND POWER CONDUITS TO BE GALVANIZED RIGID STEEL (RGS).
C. ALL TELECOMMUNICATION CONDUITS, INTERIOR/EXTERIOR, TO BE EMT.
D. INSTALL PULL ROPE IN ALL NEW EMPTY CONDUITS INSTALLED ON THIS PROJECT.
E. ALL TELECOM CONDUITS AND PULL BOXES INSTALLED ON THIS PROJECT TO BE LABELED "T-MOBILE".
GENERAL NOTES:
1. THESE SPECIFICATIONS AND CONSTRUCTION DRAWINGS ACCOMPANYING THEM DESCRIBE THE WORK TO BE DONE AND THE MATERIALS TO BE FURNISHED FOR CONSTRUCTION.
2. THE DRAWINGS AND SPECIFICATIONS ARE INTENDED TO BE FULLY EXPLANATORY AND SUPPLEMENTARY.
3. THE INTENTION OF THE DOCUMENTS IS TO INCLUDE ALL LABOR AND MATERIALS REASONABLY NECESSARY FOR THE PROPER EXECUTION AND COMPLETION OF THE WORK AS STIPULATED IN THE CONTRACT.
4. THE PURPOSE OF THE SPECIFICATIONS IS TO INTERPRET THE INTENT OF THE DRAWINGS AND TO DESIGNATE THE METHOD OF THE PROCEDURE, TYPE AND QUALITY OF MATERIALS REQUIRED TO COMPLETE THE WORK.
5. MINOR DEVIATIONS FROM THE DESIGN LAYOUT ARE ANTICIPATED AND SHALL BE CONSIDERED AS PART OF THE WORK. NO CHANGES THAT ALTER THE CHARACTER OF THE WORK WILL BE MADE OR PERMITTED BY THE OWNER WITHOUT ISSUING A CHANGE ORDER.

- RACEWAYS CONT'D
L. PENETRATIONS OF WALLS, FLOORS AND ROOFS, FOR THE PASSAGE OF ELECTRICAL RACEWAYS, TO BE PROPERLY SEALED AFTER INSTALLATION OF RACEWAYS SO AS TO MAINTAIN THE STRUCTURAL OR WATERPROOF INTEGRITY OF THE WALL, FLOOR OR ROOF SYSTEM TO BE PENETRATED.
M. PROVIDE ALL CONDUIT ENDS WITH INSULATED METALLIC GROUNDING BUSHINGS.
N. CONDUIT TO BE SUPPORTED AT MAXIMUM DISTANCE OF 8'-0", OR AS REQUIRED BY NEC, IN HORIZONTAL AND VERTICAL DIRECTIONS.
O. PROVIDE STAINLESS STEEL BLANK COVER PLATES FOR ALL JUNCTION BOXES AND/OR OUTLET BOXES NOT USED IN EXPOSED AREAS.
P. WHERE APPLICABLE, PROVIDE ROOFTOP CONDUIT SUPPORT SYSTEM, CONFORMING TO ROOFTOP WARRANTY REQUIREMENTS, PER BUILDING.
WIRES AND CABLES
1. CONTRACTOR TO COORDINATE WITH EQUIPMENT SUPPLIER AND VENDOR FOR EXACT EQUIPMENT OVER-CURRENT PROTECTION VOLTAGE, WIRE SIZE AND PLUG CONFIGURATION, IF APPLICABLE, PRIOR TO BID.
2. ALL EQUIPMENT/DEVICES TO BE PROVIDED WITH INSULATED GROUND CONDUCTOR.
3. ALL WIRE AND CABLE TO BE 600VOLT, COPPER, WITH THWN/THHN INSULATION, EXCEPT AS NOTED.
4. WIRE FOR POWER AND LIGHTING WILL NOT BE LESS THAN NO. 12AWG. ALL WIRE NO. 8 AND LARGER TO BE STRANDED.
5. CONTROL WIRING IS NOT TO BE LESS THAN NO. 14AWG, FLEXIBLE IN SINGLE CONDUCTORS OR MULTI-CONDUCTOR CABLES.
6. WIRE PREVIOUSLY PULLED INTO CONDUIT IS CONSIDERED USED AND IS NOT TO BE RE-PULLED.
7. HOME RUNS AND BRANCH CIRCUIT WIRING FOR 20A, 120V CIRCUITS:
LENGTH (FT.) HOME RUN WIRE SIZE
0 TO 50 NO. 12
51 TO 100 NO. 10
101 TO 150 NO. 8
8. VOLTAGE DROP IS NOT TO EXCEED 3%.
9. MAKE ALL CONNECTIONS WITH UL APPROVED, SOLDERLESS, PRESSURE TYPE INSULATED CONNECTORS: SCOTCHLOK OR AND APPROVED EQUAL.
WIRING DEVICES
1. ALL RECEPTACLES INSTALLED IN THIS PROJECT TO BE GROUNDING TYPE, WITH GROUNDING PIN SLOT CONNECTED TO DEVICE GROUND SCREW FOR GROUND WIRE CONNECTION.
DISCONNECT SWITCHES AND FUSES
1. DISCONNECT SWITCHES TO BE VOLTAGE-RATED TO SUIT THE CHARACTERISTICS OF THE SYSTEM FROM WHICH THEY ARE SUPPLIED.
2. PROVIDE HEAVY-DUTY, METAL-ENCLOSED, EXTERNALLY-OPERATED DISCONNECT SWITCHES, FUSED OR UNFUSED, OF SUCH TYPE AND SIZE AS REQUIRED TO PROPERLY PROTECT OR DISCONNECT THE LOAD FOR WHICH THEY ARE INTENDED.
3. PROVIDE NEMA 1 DISCONNECT SWITCHES FOR INTERIOR INSTALLATION, NEMA 3R FOR EXTERIOR INSTALLATION.
4. DISCONNECT SWITCHES TO BE MANUFACTURED BY:
A. GENERAL ELECTRIC COMPANY
B. SQUARE-D
5. PROVIDE RK-1 TYPE FUSES, UNLESS NOTED OTHERWISE.
INSTALLATION
1. INSTALL DISCONNECT SWITCHES WHERE INDICATED ON DRAWINGS.
2. INSTALL FUSES IN FUSIBLE DISCONNECT SWITCHES. FUSES MUST MATCH IN TYPE AND RATING.
3. FUSES TO BE MOUNTED SO THAT THE LABELS SHOWING THEIR RATINGS CAN BE READ WITHOUT REQUIRING FUSE REMOVAL.
4. FURNISH AND DEPOSIT SPARE FUSES AT THE JOB SITE AS FOLLOWS:
A. THREE SPARES FOR EACH TYPE AND SIZE, IN EXCESS OF 60A, USED FOR INITIAL FUSING.
B. TEN PERCENT SPARES FOR EACH TYPE AND SIZE, UP TO AND INCLUDING 60A, USED FOR INITIAL FUSING. IN NO CASE WILL LESS THAN THREE FUSES OF ONE PARTICULAR TYPE AND SIZE BE FURNISHED.
CONFLICTS
1. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFICATIONS OF ALL MEASUREMENTS AT THE SITE BEFORE ORDERING ANY MATERIALS OR DOING ANY WORK.
2. THE BIDDER, IF AWARDED THE CONTRACT, WILL NOT BE ALLOWED ANY EXTRA COMPENSATION BY REASON OF ANY MATTER OR THING CONCERNING SUCH BIDDER MIGHT HAVE FULLY INFORMED THEMSELVES PRIOR TO THE BIDDING.
3. NO PLEA OF IGNORANCE OF CONDITIONS THAT EXIST, OR OF DIFFICULTIES OR CONDITIONS THAT MAY BE ENCOUNTERED, OR OF ANY OTHER RELEVANT MATTER CONCERNING THE WORK TO BE PERFORMED IN THE EXECUTION OF THE WORK WILL BE ACCEPTED AS AN EXCUSE FOR ANY FAILURE OR OMISSION ON THE PART OF THE CONTRACTOR TO FULFILL EVERY DETAIL OF ALL THE REQUIREMENTS OF THE CONTRACT DOCUMENTS GOVERNING THE WORK.
CONTRACTS AND WARRANTIES
1. CONTRACTOR IS RESPONSIBLE FOR APPLICATION AND PAYMENT OF CONTRACTOR LICENSES AND BONDS.
2. SEE MASTER CONTRACTOR SERVICES AGREEMENT FOR ADDITIONAL DETAILS.
STORAGE
1. ALL MATERIALS MUST BE STORED IN A LEVEL AND DRY FASHION AND IN A MANNER THAT DOES NOT NECESSARILY OBSTRUCT THE FLOW OF OTHER WORK.
CLEANUP
1. THE CONTRACTORS SHALL, AT ALL TIMES, KEEP THE SITE FREE FROM ACCUMULATION OF WASTE MATERIALS OR RUBBISH CAUSED BY THEIR EMPLOYEES AT WORK AND AT THE COMPLETION OF THE WORK.
2. EXTERIOR
A. VISUALLY INSPECT EXTERIOR SURFACES AND REMOVE ALL TRACES OF SOIL, WASTE MATERIALS, SMUDGES AND OTHER FOREIGN MATTER.
B. REMOVE ALL TRACES OF SPLASHED MATERIALS FROM ADJACENT SURFACES.
C. IF NECESSARY, TO ACHIEVE A UNIFORM DEGREE OF CLEANLINESS, HOSE DOWN THE EXTERIOR OF THE STRUCTURE.
3. INTERIOR
A. VISUALLY INSPECT INTERIOR SURFACE AND REMOVE ALL TRACES OF SOIL, WASTE MATERIALS, SMUDGES AND OTHER FOREIGN MATTER FROM WALLS, FLOOR, AND CEILING.
B. REMOVE ALL TRACES OF SPLASHED MATERIALS FROM ADJACENT SURFACES.
C. REMOVE PAINT DROPPINGS, SPOTS, STAINS, AND DIRT FROM FINISHED SURFACES.
CHANGE ORDER PROCEDURE:
1. REFER TO SECTION 17 OF SIGNED MCSA: SEE PROFESSIONAL SERVICE AGREEMENT FOR MCSA.
RELATED DOCUMENTS AND COORDINATION
1. GENERAL CARPENTRY, ELECTRICAL AND ANTENNA DRAWINGS ARE INTERRELATED. IN PERFORMANCE OF THE WORK, THE CONTRACTOR MUST REFER TO ALL DRAWINGS.
SHOP DRAWINGS
1. CONTRACTOR SHALL SUBMIT SHOP DRAWINGS AS REQUIRED AND LISTED IN THESE SPECIFICATIONS TO THE OWNER FOR APPROVAL.
2. ALL SHOP DRAWINGS SHALL BE REVIEWED, CHECKED AND CORRECTED BY CONTRACTOR PRIOR TO SUBMITTAL TO THE OWNER.
PRODUCTS AND SUBSTITUTIONS
1. SUBMIT 3 COPIES OF EACH REQUEST FOR SUBSTITUTION. IN EACH REQUEST, IDENTIFY THE PRODUCT OR FABRICATION OR INSTALLATION METHOD TO BE REPLACED BY THE SUBSTITUTION. INCLUDE RELATED SPECIFICATION SECTION AND DRAWING NUMBERS AND COMPLETE DOCUMENTATION SHOWING COMPLIANCE WITH THE REQUIREMENTS FOR SUBSTITUTIONS.
2. SUBMIT ALL NECESSARY PRODUCT DATA AND CUT SHEETS WHICH PROPERLY INDICATE AND DESCRIBE THE ITEMS, PRODUCTS AND MATERIALS BEING INSTALLED.
QUALITY ASSURANCE
1. ALL WORK SHALL BE IN ACCORDANCE WITH APPLICABLE LOCAL, STATE AND FEDERAL REGULATIONS.
ADMINISTRATION
1. BEFORE THE COMMENCEMENT OF ANY WORK, THE CONTRACTOR WILL ASSIGN A PROJECT MANAGER WHO WILL ACT AS A SINGLE POINT OF CONTACT FOR ALL PERSONNEL INVOLVED IN THIS PROJECT.
2. SUBMIT A BAR TYPE PROGRESS CHART, NOT MORE THAN 3 DAYS AFTER THE DATE ESTABLISHED FOR COMMENCEMENT OF THE WORK ON THE SCHEDULE, INDICATING A TIME BAR FOR EACH MAJOR CATEGORY OR UNIT OF WORK TO BE PERFORMED AT THE SITE.
3. PRIOR TO COMMENCING CONSTRUCTION, THE OWNER SHALL SCHEDULE AN ON-SITE MEETING WITH ALL MAJOR PARTIES.
4. CONTRACTOR SHALL BE EQUIPPED WITH SOME MEANS OF CONSTANT COMMUNICATIONS, SUCH AS A MOBILE PHONE OR A BEEPER.
5. DURING CONSTRUCTION, CONTRACTOR MUST ENSURE THAT EMPLOYEES AND SUBCONTRACTORS WEAR HARD HATS AT ALL TIMES.
6. PROVIDE WRITTEN DAILY UPDATES ON SITE PROGRESS TO THE OWNER.
7. COMPLETE INVENTORY OF CONSTRUCTION MATERIALS AND EQUIPMENT IS REQUIRED PRIOR TO START OF CONSTRUCTION.
8. NOTIFY THE OWNER/PROJECT MANAGER IN WRITING NO LESS THAN 48 HOURS IN ADVANCE OF CONCRETE POURS, TOWER ERECTIONS, AND EQUIPMENT CABINET PLACEMENTS.
INSURANCE AND BONDS
1. CONTRACTOR, AT THEIR OWN EXPENSE, SHALL CARRY AND MAINTAIN, FOR THE DURATION OF THE PROJECT, ALL INSURANCE, AS REQUIRED AND LISTED, AND SHALL NOT COMMENCE WITH THEIR WORK UNTIL THEY HAVE PRESENTED AN ORIGINAL CERTIFICATE OF INSURANCE STATING ALL COVERAGES TO THE OWNER.
2. THE OWNER SHALL BE NAMED AS AN ADDITIONAL INSURED ON ALL POLICIES.
3. CONTRACTOR MUST PROVIDE PROOF OF INSURANCE.

- CONFLICTS (continued)
3. NO PLEA OF IGNORANCE OF CONDITIONS THAT EXIST, OR OF DIFFICULTIES OR CONDITIONS THAT MAY BE ENCOUNTERED, OR OF ANY OTHER RELEVANT MATTER CONCERNING THE WORK TO BE PERFORMED IN THE EXECUTION OF THE WORK WILL BE ACCEPTED AS AN EXCUSE FOR ANY FAILURE OR OMISSION ON THE PART OF THE CONTRACTOR TO FULFILL EVERY DETAIL OF ALL THE REQUIREMENTS OF THE CONTRACT DOCUMENTS GOVERNING THE WORK.
CONTRACTS AND WARRANTIES (continued)
2. SEE MASTER CONTRACTOR SERVICES AGREEMENT FOR ADDITIONAL DETAILS.
STORAGE (continued)
6. PROVIDE WRITTEN DAILY UPDATES ON SITE PROGRESS TO THE OWNER.
INSURANCE AND BONDS (continued)
3. CONTRACTOR MUST PROVIDE PROOF OF INSURANCE.

- QUALITY ASSURANCE (continued)
2. THE OWNER SHALL BE NAMED AS AN ADDITIONAL INSURED ON ALL POLICIES.
ADMINISTRATION (continued)
8. NOTIFY THE OWNER/PROJECT MANAGER IN WRITING NO LESS THAN 48 HOURS IN ADVANCE OF CONCRETE POURS, TOWER ERECTIONS, AND EQUIPMENT CABINET PLACEMENTS.
INSURANCE AND BONDS (continued)
3. CONTRACTOR MUST PROVIDE PROOF OF INSURANCE.


T-Mobile logo and contact information for T-Mobile Northeast, LLC, including address at 35 Griffin Road South, Bloomfield, CT 06002, and phone/fax numbers.

Atlantis Design Group, Inc. logo and contact information, including address at 286 Old Connecticut Path, Wayland, MA 01778, and phone/fax numbers.

Table with 3 columns: DATE, DESCRIPTION, REVISION. Includes entries for 10/20/15 and 11/02/15 with descriptions like 'ISSUED FOR REVIEW' and 'FINAL CD'.

Table with 4 columns: DEPT., DATE, APP'D, REVISIONS. Includes rows for RFE, RF MAN., ZONING, OPS, CONSTR., and SITE AC.

PROJECT NO: CT11410A
DRAWN BY: PS
CHECKED BY: KM



THIS DOCUMENT IS THE CREATION, DESIGN, PROPERTY AND COPYRIGHTED WORK OF T-MOBILE. ANY DUPLICATION OR USE WITHOUT EXPRESS WRITTEN CONSENT IS STRICTLY PROHIBITED.

SITE NAME: CT11410A
SITE NAME: STAMFORD / DWTN
SITE ADDRESS: 555 E MAIN STREET, STAMFORD, CT, 06901


SHEET TITLE: GENERAL AND ELECTRICAL NOTES

SHEET NUMBER: N-1


ABBREVIATIONS

Table listing abbreviations and their meanings, such as ADJ (ADJUSTABLE), AG (ABOVE GROUND LINE), and W (WITH).

ARCHITECTURAL SYMBOLS



DETAIL REFERENCE KEY



FINAL DESIGN PENDING STRUCTURAL EVALUATION.

GENERAL SITE NOTES

1. SITE INFORMATION WAS OBTAINED FROM A FIELD INVESTIGATION PERFORMED BY ATLANTIS DESIGN GROUP, INC. CONTRACTOR TO FIELD VERIFY DIMENSIONS AS NECESSARY BEFORE CONSTRUCTION.
2. THE PROPOSED DEVELOPMENT DOES NOT INCLUDE SIGNS OF ADVERTISING.
3. THE PROPOSED DEVELOPMENT IS UNMANNED AND THEREFORE DOES NOT REQUIRE A MEANS OF WATER SUPPLY OR SEWAGE DISPOSAL.
4. NO LANDSCAPING WORK IS PROPOSED IN CONJUNCTION WITH THIS DEVELOPMENT OTHER THAN THAT WHICH IS SHOWN.
5. THE PROPOSED DEVELOPMENT DOES NOT INCLUDE OUTDOOR STORAGE OR ANY SOLID WASTE RECEPTACLES.
6. UTILITIES SHOWN ON PLAN ARE TAKEN FROM OWNERS RECORDS AND FIELD LOCATION OF VISIBLE SURFACE FEATURES. THE EXISTENCE, EXTENT AND EXACT HORIZONTAL AND VERTICAL LOCATIONS OF UTILITIES HAS NOT BEEN VERIFIED. ANY CONTRACTOR PERFORMING WORK ON THIS SITE MUST CONTACT CALL BEFORE YOU DIG THREE WORKING DAYS PRIOR TO COMMENCING WORK.
7. ALL OBSOLETE OR UNUSED FACILITIES SHALL BE REMOVED WITHIN 12 MONTHS OF CESSATION OF OPERATIONS.



T-MOBILE NORTHEAST, LLC
 35 GRIFFIN ROAD SOUTH
 BLOOMFIELD, CT 06002
 OFFICE: (860) 692-7100
 FAX: (860) 692-7159



ATLANTIS DESIGN GROUP, INC.
 286 Old Connecticut Path,
 Wayland, MA 01778
 Phone number: 617-852-3611
 Fax Number: 781-742-2247

SUBMITTALS

DATE	DESCRIPTION	REVISION
10/20/15	ISSUED FOR REVIEW	A
11/02/15	FINAL CD	0

DEPT.	DATE	APP'D	REVISIONS
RFE			
RF MAN.			
ZONING			
OPS			
CONSTR.			
SITE AC.			

PROJECT NO: CT11410A
 DRAWN BY: PS
 CHECKED BY: KM

SITE LEGEND

- SITE PROPERTY LINE
- STREET OR ROAD
- CHAIN LINK FENCE
- OPAQUE WOODEN FENCE
- BOARD ON BOARD FENCE
- DECIDUOUS TREES/SHRUBS
- EVERGREEN TREES/SHRUBS
- TREE LINE
- UTILITY POLE
- (E) EXISTING
- (N) NEW
- (P) PROPOSED
- (F) FUTURE
- PROP. LTE ANTENNA
- PROP. UMS/GSM ANTENNA
- EX. GSM ANTENNA
- EX. UMS ANTENNA



THIS DOCUMENT IS THE CREATION, DESIGN, PROPERTY AND COPYRIGHTED WORK OF T-MOBILE. ANY DUPLICATION OR USE WITHOUT EXPRESS WRITTEN CONSENT IS STRICTLY PROHIBITED.

SITE NAME
CT11410A




SITE NAME
STAMFORD / DWTN

SITE ADDRESS
555 E MAIN STREET
STAMFORD, CT, 06901

SHEET TITLE
SITE PLAN
AND
EQUIPMENT PLAN

SHEET NUMBER

A-1



SITE PLAN 1
A-1

SCALE: 1" = 30'-0" (11x17)
 1" = 15'-0" (24x36)


SCALE 1"=30' (11x17)
 1"=15' (24x36)

EQUIPMENT PLAN AT THE 5th FLOOR 2
A-1

SCALE: 1/8" = 1'-0" (11x17)
 1/4" = 1'-0" (24x36)

SCALE 1/8"=1' (11x17)
 1/4"=1' (24x36)

FINAL DESIGN PENDING STRUCTURAL EVALUATION.



ELEVATION VIEW
 SCALE: 1" = 30'-0" (11x17)
 1" = 15'-0" (24x36)



T-Mobile
T-MOBILE NORTHEAST, LLC
 35 GRIFFIN ROAD SOUTH
 BLOOMFIELD, CT 06002
 OFFICE: (860) 692-7100
 FAX: (860) 692-7159

ATLANTIS DESIGN GROUP, INC.
 286 Old Connecticut Path,
 Wayland, MA 01778
 Phone number: 617-852-3611
 Fax Number : 781-742-2247

SUBMITTALS		
DATE	DESCRIPTION	REVISION
10/20/15	ISSUED FOR REVIEW	A
11/02/15	FINAL CD	0

DEPT.	DATE	APP'D	REVISIONS
RFE			
RF MAN.			
ZONING			
OPS			
CONSTR.			
SITE AC.			

PROJECT NO: CT11410A
 DRAWN BY: PS
 CHECKED BY: KM





THIS DOCUMENT IS THE CREATION, DESIGN, PROPERTY AND COPYRIGHTED WORK OF T-MOBILE. ANY DUPLICATION OR USE WITHOUT EXPRESS WRITTEN CONSENT IS STRICTLY PROHIBITED.

SITE NAME
CT11410A
 SITE NAME
 STAMFORD / DWTN
 SITE ADDRESS
 555 E MAIN STREET
 STAMFORD, CT, 06901

SHEET TITLE
 ELEVATION

SHEET NUMBER
A-2




FINAL DESIGN PENDING STRUCTURAL EVALUATION.



EXISTING ANTENNA CONFIGURATION

RAD CENTER OF (E) T-MOBILE ANTENNAS ELEV.= 203'-0"± (AGL)

RAD CENTER OF (E) T-MOBILE ANTENNAS ELEV.= 210'-0"± (AGL)



MANUFACTURER: ERICSSON
MODEL NO.: ERICSSON AIR32 B4A/B2P
DIMENSIONS - HxWxD, (IN) 56.6"x12.9"x8.7"

ERICSSON AIR32 B4A/B2P ANTENNA DETAILS




SCALE: N.T.S.

2
A-3

PROPOSED ANTENNA CONFIGURATION

RAD CENTER OF (P) T-MOBILE ANTENNAS ELEV.= 210'-0"± (AGL)

RAD CENTER OF (E) & (P) T-MOBILE ANTENNAS ELEV.= 210'-0"± (AGL)



ANTENNA PLAN CONFIGURATION

SCALE: N.T.S.

1
A-3

ANTENNA MOUNT DETAILS

SCALE: N.T.S.

3
A-3



T-MOBILE NORTHEAST, LLC
35 GRIFFIN ROAD SOUTH
BLOOMFIELD, CT 06002
OFFICE: (860) 692-7100
FAX: (860) 692-7159



286 Old Connecticut Path,
Wayland, MA 01778
Phone number: 617-852-3611
Fax Number: 781-742-2247

SUBMITTALS

DATE	DESCRIPTION	REVISION
10/20/15	ISSUED FOR REVIEW	A
11/02/15	FINAL CD	0

DEPT.	DATE	APP'D	REVISIONS
RFE			
RF MAN.			
ZONING			
OPS			
CONSTR.			
SITE AC.			

PROJECT NO: CT11410A
DRAWN BY: PS
CHECKED BY: KM



THIS DOCUMENT IS THE CREATION, DESIGN, PROPERTY AND COPYRIGHTED WORK OF T-MOBILE. ANY DUPLICATION OR USE WITHOUT EXPRESS WRITTEN CONSENT IS STRICTLY PROHIBITED.

SITE NAME
CT11410A
SITE NAME
STAMFORD / DWTN
SITE ADDRESS
555 E MAIN STREET
STAMFORD, CT, 06901

SHEET TITLE
ANTENNA PLAN AND DETAILS

SHEET NUMBER


A-3

SUBMITTALS

DATE	DESCRIPTION	REVISION
10/20/15	ISSUED FOR REVIEW	A
11/02/15	FINAL CD	0

DEPT.	DATE	APP'D	REVISIONS
RFE			
RF MAN.			
ZONING			
OPS			
CONSTR.			
SITE AC.			

PROJECT NO: CT11410A
 DRAWN BY: PS
 CHECKED BY: KM



THIS DOCUMENT IS THE CREATION, DESIGN, PROPERTY AND COPYRIGHTED WORK OF T-MOBILE. ANY DUPLICATION OR USE WITHOUT EXPRESS WRITTEN CONSENT IS STRICTLY PROHIBITED.

SITE NAME
CT11410A


SITE NAME
STAMFORD / DWTN

SITE ADDRESS
555 E MAIN STREET
STAMFORD, CT, 06901

SHEET TITLE
**GROUNDING DIAGRAM
AND
POWER ONE
LINE DIAGRAM**

SHEET NUMBER

E-1



TRUNK FIBER NOTES:

- IN GENERAL THIS CABLE WILL HANDLE SIMILARLY TO 3/8" COAXIAL CABLE, AND SIMILAR INSTALLATION TECHNIQUES APPLY. ALL CABLES ARE INDIVIDUALLY SERIALIZED, BE SURE TO WRITE DOWN THE CABLE SERIAL NUMBER FOR FUTURE REFERENCE.
- THE TERMINATED FIBER ENDS (THE BROKEN OUT FIBERS PLUS CONNECTORS) HOWEVER ARE FRAGILE, AND THESE MUST BE PROTECTED DURING THE INSTALLATION PROCESS.
- LEAVE THE PROTECTIVE TUBE AND SOCK AROUND THE FIBER TAILS AND CONNECTORS IN PLACE DURING HOISTING AND SECURING THE CABLE. REMOVE THIS ONLY JUST PRIOR TO MAKING THE FINAL CONNECTIONS TO THE OVP BOX.
- DO NOT BEND THE FIBER ENDS (IN THE ORANGE FURCATION TUBES) TIGHTER THAN 3/4" (19MM) BEND RADIUS, ELSE THERE IS A RISK OF BREAKING THE GLASS FIBERS.
- BE SURE THAT THE LACE UP ENDS AND FIBER CONNECTORS ARE NOT DAMAGED BY ATTACHMENT OF A HOISTING GRIP OR DURING THE HOISTING PROCESS. ATTACH A HOISTING GRIP ON THE JACKETED CABLE NO LESS THAN 6 INCHES BELOW THE FIBER BREAKOUT POINT. IF A HOISTING GRIP IS NOT EASILY ATTACHED, USE A SIMPLE LINE ATTACHED BELOW THE FIBER BREAK-OUT POINT (I.E. AT THE CABLE OUTER JACKET). PREVENT THE FIBER TAILS (IN PROTECTIVE TUBE) AT THE CABLE END FROM UNDUE MOVEMENT DURING HOISTING BY SECURING THE PROTECTIVE TUBE (WITH OUTER SOCK) TO THE HOISTING LINE.
- DURING HOISTING ENSURE THAT THERE IS A FREE PATH AND THAT THE CABLE, AND ESPECIALLY THE FIBER ENDS, WILL NOT BE SNAGGED ON TOWER MEMBERS OR OTHER OBSTACLES.
- INSTALLATION TEMPERATURE RANGE IS -22F TO 158F (-30C TO +70C).
- MINIMUM CABLE BEND RADII ARE 22.2" (565MM) LOADED (WITH TENSION ON THE CABLE) AND 11.1" (280MM) UNLOADED.
- MAXIMUM CABLE TENSILE LOAD IS 3560 N (800 LB) SHORT TERM (DURING INSTALLATION) AND 1070 N (240 LB) LONG TERM.
- COMMSCOPE NON LACE UP GRIP RECOMMENDED FOR MONOPOLE INSTALLATIONS.
- MAXIMUM HANGER SPACING 3FT (0.9 M).


HYBRID FIBER/POWER JUMPER NOTES:

- IN GENERAL THIS CABLE WILL HANDLE SIMILARLY TO A 3/8" COAXIAL CABLE.
- THE TERMINATED FIBER ENDS HOWEVER ARE FRAGILE AND MUST BE PROTECTED DURING INSTALLATION. LEAVE THE PACKAGING AROUND THE FIBER ENDS IN PLACE UNTIL READY TO CONNECT THE JUMPER BETWEEN OVP AND RRU OR BBU.
- DO NOT BEND THE FIBER BREAKOUT CABLE (BETWEEN THE MAIN CABLE AND THE FIBER CONNECTOR) TIGHTER THAN 3/4" (19MM) RADIUS, ELSE THERE IS A RISK OF BREAKING THE GLASS.
- ATTACH THE MAIN CABLE SECURELY TO THE STRUCTURE OR EQUIPMENT USING HANGERS AND/OR CABLE TIES TO PREVENT STRAIN ON CONNECTIONS FROM MOVEMENT IN WIND OR SNOW/ICE CONDITIONS.
- ENSURE THE LC FIBER CONNECTORS ARE SEATED FIRMLY IN PANEL IN OVP OR IN EQUIPMENT.
- INSTALLATION TEMPERATURE RANGE IS -22F TO 158F (-30C TO 70C).
- MINIMUM CABLE BEND RADII ARE 10.3 INCH (265MM) LOADED (WITH TENSION ON THE CABLE) AND 5.2 INCH (130MM) UNLOADED.
- MAXIMUM CABLE TENSILE LOAD IS 350 LB (1560N) SHORT TERM (DURING INSTALLATION) AND 105 LB (470N) LONG TERM.
- STANDARD LENGTHS AVAILABLE ARE 6 FEET, 15 FEET AND 20 FEET

**702D CONFIGURATION
COAX/FIBER PLUMBING DIAGRAM**


SCALE: N.T.S.

**(E) SECTOR
(VIEW FROM BEHIND)**



NOTES:


- PROVIDE #2AWG GROUNDING CONDUCTOR, U.O.N.
- DO NOT INSTALL GROUND KIT AT BEND. DIRECT GROUND WIRE DOWN TO ANTENNA BUSSBAR.
- PROVIDE GROUNDING ELECTRODES IN QUANTITY, TYPE AND SIZE AS INDICATED ON SITE GROUNDING PLAN.
- ADD COAX GROUND KIT CONNECTION TO BUSSBAR WHEN LENGTH OF COAX RUN (FROM EQUIPMENT TO ANTENNA) IS GREATER THAN 20'-0".
- GROUND HCS BOX W/ #2AWG GROUNDING CONDUCTOR ATTACHED TO GOOD GROUND AS DIRECT AND SHORT AS POSSIBLE. USE GREEN STRANDED INSULATED CONDUCTOR TO CONNECT TO BUSSBAR/GROUND HALO OR BARE TINNED SOLID COPPER CONDUCTOR TO CONNECT TO GROUND RING.



BURNDY GROUNDING DETAILS

SCALE: N.T.S


1
E-2



BURNDY GROUNDING PRODUCTS

SCALE: N.T.S

2
E-2



CADWELD GROUNDING CONNECTION PRODUCTS

SCALE: N.T.S

3
E-2

TERMINATION TYPES:


- A. MECHANICAL COMPRESSION LUG
- B. DOUBLE BARRELL COMPRESSION CONNECTOR
- C. EXOTHERMIC TERMINATION
- D. BEAM CLAMP

	SOLID #2 TINNED COPPER	#6 GROUND LEAD	#2/O STRANDED MAIN DOWN CONDUCTOR	MASTER GRND BAR	STRUCTURAL OR TOWER STEEL	BLDG SERVICE ENTR OR GROUND RING	GROUND ROD
SOLID #2 TINNED COPPER	B OR C	B OR C	/	/	/	/	/
#6 GROUND LEAD	B OR C	/	/	/	/	/	/
#2/O STRANDED GRNDG ELECTRODE CONDUCTOR	/	/	/	A	A, C, OR D	A	/
MASTER GROUND BAR	C	A	A	/	/	/	/
STRUCTURAL OR TOWER STEEL	A, C, OR D	A, C, OR D	A, C, OR D	/	/	/	/
GROUND RING	C	/	C	/	/	/	C

GROUNDING TERMINATION MATRIX


SCALE: N.T.S

7
E-2



NOTES:

- OXIDE INHIBITING COMPOUND TO BE USED AT ALL LOCATIONS.




NOTES:

- ALL HARDWARE STAINLESS STEEL COAT ALL SURFACES WITH KOPR-SHIELD BEFORE MATING.
- FOR GROUND BOND TO STEEL ONLY: INSERT A TOOTH WASHER BETWEEN LUG AND STEEL, COAT ALL SURFACES WITH KOPR-SHIELD.
- ALL HOLES ARE COUNTERSUNK 1/16".

TYPICAL GROUND BAR CONNECTIONS DETAIL

SCALE: N.T.S


4
E-2



GROUND BAR DETAIL

SCALE: N.T.S

5
E-2



LUG NOTES:

- ALL HARDWARE IS 18-8 STAINLESS STEEL, INCLUDING LOCK WASHERS.
- ALL HARDWARE SHALL BE S.S. 3/8" OR LARGER.
- FOR GROUND BOND TO STEEL ONLY: INSERT A DRAGON TOOTH WASHER BETWEEN LUG AND STEEL. COAT ALL SURFACES WITH ANTI-OXIDIZATION COMPOUND PRIOR TO MATING.

GROUND BAR DETAIL

SCALE: N.T.S

6
E-2



T-MOBILE NORTHEAST, LLC
35 GRIFFIN ROAD SOUTH
BLOOMFIELD, CT 06002
OFFICE: (860) 692-7100
FAX: (860) 692-7159



286 Old Connecticut Path,
Wayland, MA 01778
Phone number: 617-852-3611
Fax Number: 781-742-2247

SUBMITTALS

DATE	DESCRIPTION	REVISION
10/20/15	ISSUED FOR REVIEW	A
11/02/15	FINAL CD	0

DEPT.	DATE	APP'D	REVISIONS
RFE			
RF MAN.			
ZONING			
OPS			
CONSTR.			
SITE AC.			

PROJECT NO: CT11410A

DRAWN BY: PS

CHECKED BY: KM



THIS DOCUMENT IS THE CREATION, DESIGN, PROPERTY AND COPYRIGHTED WORK OF T-MOBILE. ANY DUPLICATION OR USE WITHOUT EXPRESS WRITTEN CONSENT IS STRICTLY PROHIBITED.

SITE NAME
CT11410A

SITE NAME
STAMFORD / DWTN

SITE ADDRESS
555 E MAIN STREET
STAMFORD, CT, 06901

SHEET TITLE
GROUNDING DETAILS

SHEET NUMBER

E-2

Exhibit D


Structural Analysis Report



T-Mobile - Stamford / Dwtm Site #CT11410A
Owner: Frontier Communications - Stamford #1 Co Site
Stamford, Connecticut

March 17, 2016

MEI PROJECT ID: CT02768S-16V0



17950 PRESTON ROAD, SUITE 720 ■ DALLAS, TEXAS 75252 ■ TEL. 972-783-2578 FAX 972-783-2583
www.maloufengineering.com



**RADIO FREQUENCY EMISSIONS ANALYSIS REPORT
EVALUATION OF HUMAN EXPOSURE POTENTIAL
TO NON-IONIZING EMISSIONS**

T-Mobile Existing Facility

Site ID: CT11410A

**Stamford/ Dwtm
555 E. Main Street
Stamford, CT 06901**

March 21, 2016

EBI Project Number: 6216001683

Site Compliance Summary	
Compliance Status:	COMPLIANT
Site total MPE% of FCC general public allowable limit:	2.25 %

March 21, 2016

T-Mobile USA
Attn: Jason Overbey, RF Manager
35 Griffin Road South
Bloomfield, CT 06002

Emissions Analysis for Site: **CT11410A – Stamford/ Dwtm**

EBI Consulting was directed to analyze the proposed T-Mobile facility located at **555 E. Main Street, Stamford, CT**, for the purpose of determining whether the emissions from the Proposed T-Mobile Antenna Installation located on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter ($\mu\text{W}/\text{cm}^2$). The number of $\mu\text{W}/\text{cm}^2$ calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits, therefore it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) – (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general public may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general public would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

Public exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter ($\mu\text{W}/\text{cm}^2$). The general population exposure limit for the 700 MHz Band is approximately 467 $\mu\text{W}/\text{cm}^2$, and the general population exposure limit for the PCS and AWS bands is 1000 $\mu\text{W}/\text{cm}^2$. Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.

Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure. Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

CALCULATIONS

Calculations were done for the proposed T-Mobile Wireless antenna facility located at **555 E. Main Street, Stamford, CT**, using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. Since T-Mobile is proposing highly focused directional panel antennas, which project most of the emitted energy out toward the horizon, all calculations were performed assuming a lobe representing the maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was focused at the base of the tower. For this report the sample point is the top of a 6 foot person standing at the base of the tower.

For all calculations, all equipment was calculated using the following assumptions:

- 1) 2 GSM / UMTS channels (PCS Band - 1900 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 30 Watts per Channel
- 2) 2 UMTS channels (AWS Band – 2100 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 30 Watts per Channel.
- 3) 2 LTE channels (AWS Band – 2100 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 60 Watts per Channel.
- 4) 1 LTE channel (700 MHz Band) was considered for each sector of the proposed installation. This channel has a transmit power of 30 Watts.
- 5) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 - Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.

- 6) For the following calculations the sample point was the top of a six foot person standing at the base of the tower. The maximum gain of the antenna per the antenna manufactures supplied specifications minus 10 dB was used in this direction. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 7) The antennas used in this modeling are the **Ericsson AIR32 B4A/B2P & AIR 21B2A/B4P** for 1900 MHz (PCS) and 2100 MHz (AWS) channels and the **Commscope LNX-6515DS-VTM** for 700 MHz channels. This is based on feedback from the carrier with regards to anticipated antenna selection. The **Ericsson AIR32 B4A/B2P & AIR 21B2A/B4P** have a maximum gain of **15.9 dBd** at their main lobe. The **Commscope LNX-6515DS-VTM** has a maximum gain of **14.6 dBd** at its main lobe. The maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was used for all calculations. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 8) The antenna mounting height centerlines of the proposed antennas are **203 & 210 feet** above ground level (AGL).
- 9) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.

All calculations were done with respect to uncontrolled / general public threshold limits.

T-Mobile Site Inventory and Power Data

Sector:	A	Sector:	B	Sector:	C
Antenna #:	1	Antenna #:	1	Antenna #:	1
Make / Model:	Ericsson AIR32 B4A/B2P	Make / Model:	Ericsson AIR32 B4A/B2P	Make / Model:	Ericsson AIR32 B4A/B2P
Gain:	15.9 dBd	Gain:	15.9 dBd	Gain:	15.9 dBd
Height (AGL):	210	Height (AGL):	210	Height (AGL):	210
Frequency Bands	2100 MHz (AWS)	Frequency Bands	2100 MHz (AWS)	Frequency Bands	2100 MHz (AWS)
Channel Count	2	Channel Count	2	Channel Count	2
Total TX Power(W):	120	Total TX Power(W):	120	Total TX Power(W):	120
ERP (W):	4,668.54	ERP (W):	4,668.54	ERP (W):	4,668.54
Antenna A1 MPE%	0.40	Antenna B1 MPE%	0.40	Antenna C1 MPE%	0.40
Antenna #:	2	Antenna #:	2	Antenna #:	2
Make / Model:	Ericsson AIR21 B2A/B4P	Make / Model:	Ericsson AIR21 B2A/B4P	Make / Model:	Ericsson AIR21 B2A/B4P
Gain:	15.9 dBd	Gain:	15.9 dBd	Gain:	15.9 dBd
Height (AGL):	210	Height (AGL):	210	Height (AGL):	210
Frequency Bands	1900 MHz(PCS) / 2100 MHz (AWS)	Frequency Bands	1900 MHz(PCS) / 2100 MHz (AWS)	Frequency Bands	1900 MHz(PCS) / 2100 MHz (AWS)
Channel Count	4	Channel Count	4	Channel Count	4
Total TX Power(W):	120	Total TX Power(W):	120	Total TX Power(W):	120
ERP (W):	4,668.54	ERP (W):	4,668.54	ERP (W):	4,668.54
Antenna A2 MPE%	0.40	Antenna B2 MPE%	0.40	Antenna C2 MPE%	0.40
Antenna #:	3	Antenna #:	3	Antenna #:	3
Make / Model:	Commscope LNX-6515DS-VTM	Make / Model:	Commscope LNX-6515DS-VTM	Make / Model:	Commscope LNX-6515DS-VTM
Gain:	14.6 dBd	Gain:	14.6 dBd	Gain:	14.6 dBd
Height (AGL):	210	Height (AGL):	210	Height (AGL):	210
Frequency Bands	700 MHz	Frequency Bands	700 MHz	Frequency Bands	700 MHz
Channel Count	1	Channel Count	1	Channel Count	1
Total TX Power(W):	30	Total TX Power(W):	30	Total TX Power(W):	30
ERP (W):	865.21	ERP (W):	865.21	ERP (W):	865.21
Antenna A3 MPE%	0.17	Antenna B3 MPE%	0.17	Antenna C3 MPE%	0.17

Site Composite MPE%	
Carrier	MPE%
T-Mobile (Per Sector Max)	0.98 %
AT&T	0.63 %
Winstar Wireless	0.07 %
PageNet	0.14 %
Broadcast Video	0.43 %
Site Total MPE %:	2.25 %

T-Mobile Sector 1 Total:	0.98 %
T-Mobile Sector 2 Total:	0.98 %
T-Mobile Sector 3 Total:	0.98 %
Site Total:	2.25 %

T-Mobile _per sector	# Channels	Watts ERP (Per Channel)	Height (feet)	Total Power Density ($\mu\text{W}/\text{cm}^2$)	Frequency (MHz)	Allowable MPE ($\mu\text{W}/\text{cm}^2$)	Calculated % MPE
T-Mobile 2100 MHz (AWS) LTE	2	2334.27	210	4.03	2100	1000	0.40 %
T-Mobile 1900 MHz (PCS) GSM/UMTS	2	1167.14	210	2.02	1900	1000	0.20 %
T-Mobile 2100 MHz (AWS) UMTS	2	1167.14	210	2.02	2100	1000	0.20 %
T-Mobile 700 MHz LTE	1	865.21	203	0.80	700	467	0.17 %
						Total:	0.98%

Summary

All calculations performed for this analysis yielded results that were **within** the allowable limits for general public exposure to RF Emissions.

The anticipated maximum composite contributions from the T-Mobile facility as well as the site composite emissions value with regards to compliance with FCC's allowable limits for general public exposure to RF Emissions are shown here:

T-Mobile Sector	Power Density Value (%)
Sector 1:	0.98 %
Sector 2:	0.98 %
Sector 3 :	0.98 %
T-Mobile Per Sector Maximum:	0.98 %
Site Total:	2.25 %
Site Compliance Status:	COMPLIANT

The anticipated composite MPE value for this site assuming all carriers present is **2.25%** of the allowable FCC established general public limit sampled at the ground level. This is based upon values listed in the Connecticut Siting Council database for existing carrier emissions.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.



Scott Heffernan
RF Engineering Director

EBI Consulting
21 B Street
Burlington, MA 01803



March 17, 2016

Mr. Sheldon Freinckle
Northeast Site Solutions
 Farmington, CT 06032

STRUCTURAL ANALYSIS

Structure/Make/Model:	125 ft Self-Supporting Tower (onto 106.5ft Rooftop)	Not Known / Not Known	
Client/Site Name/#:	Northeast Site Solutions / T-Mobile	Stamford / Dwtn #CT11410A	
Owner/Site Name/#:	Frontier Communications	Stamford #1 Co	
MEI Project ID:	CT02768S-16V0		
Location:	555 Main St Stamford, CT 06901	Fairfield County FCC #1046319	
	LAT	41-03-12.74 N	LON 73-32-8.09 W

EXECUTIVE SUMMARY:

Malouf Engineering Int'l (MEI), as requested, has performed a structural analysis of the above mentioned structure to assess the impact of the changed condition as noted in Table 1.

Based on the stress analysis performed, the existing structure **is in conformance** with the Int'l Building Code (IBC) / ANSI/TIA **222-F** Standard for the loading considered under the criteria listed and referenced in the report sections – tower rated at 98.8% - Legs.

The installation of the proposed changed condition as noted in Table 1 is structurally acceptable. Please refer to Appendix 1 for Schematic Lines Layout.

MEI appreciates the opportunity of providing our continuing professional services to you. If you have any questions or need further assistance on this or other projects please contact us.

Respectfully submitted,

MALOUF ENGINEERING INT'L, INC.

Analysis performed by:

Reviewed & Approved by:

Luan Nguyen, PE
 Sr. Project Engineer

E. Mark Malouf, PE
 Connecticut #17715
 972-783-2578 ext. 106
 mmalouf@maloufengineering.com



TABLE OF CONTENTS

1. **INTRODUCTION & SCOPE** _____ 4

2. **SOURCE OF DATA** _____ 4

Background Information: ----- 4

3. **ANALYSIS CRITERIA** _____ 5

Appurtenances Configuration ----- 5

4. **ANALYSIS PROCEDURE** _____ 6

Analysis Program ----- 6

Assumptions ----- 6

5. **ANALYSIS RESULTS** _____ 7

6. **FINDINGS & RECOMMENDATIONS** _____ 8

7. **REPORT DISCLAIMER** _____ 9

APPENDIX 1 - ANALYSIS PRINTOUT & GRAPHICS _____ 10

APPENDIX 2 – SOURCE / CHANGED CONDITION _____ 11



1. INTRODUCTION & SCOPE

A structural analysis was performed by Malouf Engineering Int'l (MEI), as requested and authorized by Mr. Sheldon Freinle, Northeast Site Solutions, on behalf of T-Mobile, to determine the acceptance of the proposed changed conditions in conformance with the IBC / ANSI/TIA-222-F Standard, "*Structural Standards for Steel Antenna Towers and Antenna Supporting Structures*".

The scope of this independent analysis is to determine the overall stability and the adequacy of structural members, foundations, and member connections, as available and stated. This analysis considers the structure to have been properly installed and maintained with no structural defects. Installation procedures and related loading are not within the scope of this analysis and should be performed and evaluated by a competent person of the erection contractor.

The different report sections detail the applicable information used in this evaluation, relating to the tower data, the appurtenances configuration and the wind and ice loading considered.

2. SOURCE OF DATA

The following information has been used in this evaluation as source data that accurately represent the existing structure and the related appurtenances:

	Source	Information	Reference
STRUCTURE			
Tower	MEI Records	Previous Structural Analysis	ID CT02768S-15V4-R1 Dated 10/15/2015
Base Support	Tower is on a building rooftop – building members to be reviewed by others.		
Material Grade	Not available from supplied documents-Assumed based on typical towers of this type-refer to Appendix		
CURRENT APPURTENANCES			
	MEI Records	Previous Structural Analysis	ID CT02768S-15V4-R1 Dated 10/15/2015
CHANGED CONDITION			
	Northeast Site Solutions/ Mr. Sheldon Freinle	T-Mobile CDs	Dated 11/02/2015
		Preliminary Data Questionnaire	Dated 03/08/2016

Background Information:

Based on available information, the following is known regarding this structure:

DESIGNER / FABRICATOR	Not Known / Not Known
ORIGINAL DESIGN CRITERIA	TIA/EIA 222-Unknown
PRIOR STRUCTURAL MODIFICATIONS	Mods as per MEI CT02768S-11V1; CT02768S-15V2 dated 06/24/2015 – considered properly installed.

3. ANALYSIS CRITERIA

The structural analysis performed used the following criteria:

CODE / STANDARD	2003 Int'l Building Code / ANSI/TIA-222-F-96 Standard	
LOADING CASES	<i>Full Wind:</i>	85 Mph (fastest-mile) – with No Radial Ice
	<i>Iced Case:</i>	73.61 Mph (fastest-mile) + 0.5" Radial Ice
	<i>Service:</i>	50 Mph

Appurtenances Configuration

The following appurtenances configuration is denoted by the *summation of Tables 1 & 2*:

Table 1: Proposed Changed Condition Appurtenances

Elev (ft)	Tenant	Ants Qty	Appurtenance Model / Description	Mount Description	Lines Qty	Line size & Location
210	T-Mobile	3	AIR-32 Panel Antennas	[Existing Mounts]		No New Lines
To Be Removed (See Below)						
210	T-Mobile	3	AIR21 Panel Antennas			

Table 2: Remaining Current and Reserved/Future Appurtenances

Elev (ft)	Tenant	Ants Qty	Appurtenance Model / Description	Mount Description	Lines Qty	Line size & Location
245.17		2	Top Small Beacons	13ft T-Beam Mount	1	1-1/4" R.C.
244.5		1	Top Lightning Rod			
235	AT&T	1	P65-15-XLH-RR Panel Antennas	Top Square Platform Mount	12	1-5/8" DC Power Trunk Cables 0.625" Fiber Trunk Cable RET Cable-(FZ)
		2	OPA-65R-LCUU-H4 Panel Antenna		4	
		6	LGP21401 TMAs			
		3	RRUS-11 Boxes		2	
		3	RRUS-32 Boxes			
	3	RRUS-12 w/ A2 Backpacks	1			
	AT&T [New]	6	HPA-45R-BUU-H6 Panel Antennas			
233	AT&T	2	Raycap DC6-48-60-18-8F DC Surge Box			
231.5				Unused I-Beam Mount		
229	AT&T	1	1.5ft (2-Elem) Yagi Antenna	[Onto Platform]	1	1/2" -(FZ)
223.5		1	10ft Dia. HP Dish (Az. 210°±)	Dish Pipe Mount-DA Face	2	EW90-(FZ)
221.5	[Unused]				2	3/8" -(FZ)
221		1	1ft Dia. HP Dish (Windstar 43029) (Az. 210°±)	Dish Pipe Mount-BC Face	1	3/8" -(FZ)
216.5				(2) 4'Lx6'W Rest Platforms		
210	T-Mobile	3	AIR21 Panel Antennas	(3) Sector Frame Mounts	30	1-5/8" Huber-Suhner 1.25" TC-OF Cable-(FZ)*
		3	KRY 112 71/2 TMAs		1	
203	T-Mobile [New]	3	LNX-6515DS-VTM Panel Antennas	(3) Sector Frame Mounts		
		3	RRUS-11 B12 Boxes			
132	AT&T	1	4ft (7-Elem) Yagi Antenna	2ft Sidearm Mount	1	1/2" -(FZ)

Notes:

1. Tower Base elevation is at 106.5ft Above Ground Level - All above elevations are measured from AGL.
2. *Line size adjusted as per previous MEI Mapping.
3. Please note appurtenances not listed above are to be removed/not present as per data supplied.
4. (I) = Internal; (E) = External; (FZ) = Within Face Zone; (OFZ) = Outside Face Zone - as per TIA-222.
5. The above appurtenances represent MEI's understanding of the appurtenances configuration. If different than above, the analysis is invalid. Please contact MEI if any discrepancies are found.

4. ANALYSIS PROCEDURE

The subject structure is analyzed for feasibility of the installation of the proposed changed condition previously noted. The data records furnished were reviewed and a computer stress analysis was performed in accordance with the TIA-222 Standard provisions and with the agreed scope of work terms and the results of this analysis are reported.

Analysis Program

The computer program used to model the structure is a rigorous Finite Element Analysis program, tnxTower (ver. 7.0.5), a commercially available program by Tower Numerics Inc. The latticed structures members are modeled using beam/truss and cable members and the pole members using tubular beam elements. The structural parameters and geometry of the members are included in the model. The dead and temperature loads and the wind loads are internally calculated by the program for the different wind directions and then applied as external loads on the structure.

Assumptions

This engineering study is based on the theoretical capacity of the members and is not a condition assessment of the structure. This analysis is based on information supplied, and therefore, its results are based on and as accurate as that supplied data. MEI has made no independent determination, nor is it required to, of its accuracy. The following assumptions were made for this structural stress analysis:

- This existing tower is assumed, for the purpose of this analysis, to have been properly maintained and to be in good condition with no structural defects and with no deterioration to its member capacities ('as-new' condition).
- The tower member sizes and configuration are considered accurate as supplied. The material grade is as per data supplied and/or as assumed and as stated.
- The appurtenances configuration is as supplied and/or as stated in the report. It is assumed to be complete and accurate. All antennas, mounts, coax and waveguides are assumed to be properly installed and supported as per manufacturer requirements.
- Some assumptions are made regarding antennas and mounts sizes and their projected areas based on best interpretation of data supplied and of best knowledge of antenna type & industry practice.
- Mounts/Platforms are considered adequate to support the loading. No actual analysis of the platform/mount itself is performed, with the analysis being limited to analyzing the structure.
- The soil parameters are as per data supplied or as assumed and stated in the calculations. Refer to the Appendix. If no data is available, the foundation system is assumed to support the structure with its new reactions.
- All welds and connections are assumed to develop at least the member capacity, unless determined otherwise and explicitly stated in this report.
- All prior structural modifications, if any, are assumed to be as per data supplied/available, and to have been properly installed and to be fully effective.

If any of the above assumptions are not valid or have been made in error, this analysis results may be invalidated, MEI should be contacted to review any contradictory information to determine its effect.

5. ANALYSIS RESULTS

The results of the structural stress analysis based on data available and with the previous listed criteria, indicated the following:

Table 3: Stress Analysis Results

Component Type	Maximum Stress Ratio	Controlling Elev. (ft) / Component	Pass/Fail	Comment
LEGS	98.8%	231.5 - 229	Pass	
DIAGONALS	85.9%	161.5 - 151.5	Pass	
HORIZONTALS / GIRTS	53.4%	141.5 - 131.5	Pass	
SECONDARY HORIZONTALS	18.5%	151.5 - 141.5	Pass	
BRACINGS	68.3%	131.5 - 119	Pass	
BASE SUPPORT	N/A	-	-	Tower is on top of building. Scope is limited to tower. Building members to be reviewed by others. Refer to Appendix 1 for reactions

Table 4: Serviceability Requirements

	Maximum Value	TIA Requirement (10dB)	Pass/Fail	Comment
TWIST/SWAY	0.1796 Deg.	4.425 Deg.	Pass	1ft HP Dish (Windstar 43029) Elev. 221.00ft
	0.1817 Deg.	0.2957 Deg.	Pass	10 FT HP DISH Elev. 223.50ft

Notes:

1. The Maximum Stress Ratio is the percentage that the maximum load in the member is relative to the allowable load as determined by Code requirements.
2. Refer to the Appendix 1 for more details on the member loads.
3. A maximum stress ratio between 100% and 105% may be considered as *Acceptable* according to industry standard practice.



6. FINDINGS & RECOMMENDATIONS

- Based on the stress analysis results, the subject structure is **rated at 98.8%** of its support capacity (controlling component: Leg) with the proposed changed condition considered. Please refer to Table 3 and to Appendix 1 for more details of the analysis results.
- Based on the stress analysis performed, the existing structure **is in conformance** with the IBC / ANSI/TIA **222-F** Standard for the loading considered under the criteria listed and referenced in the report sections.
- Please note that the tower is mounted on top of a building rooftop. Building rooftop is to be evaluated by others to determine its adequacy for the new base loads (not within scope). Refer to Appendix for tower base reactions.
- ***The installation of the proposed changed condition as noted in Table 1 is structurally acceptable.*** Please refer to Appendix 1 for Schematic Lines Layout.
- This structure is at its support capacity for the appurtenances and loading criteria considered. Therefore, no changes to the configuration considered should be made without performing a new proper evaluation.

Rigging and temporary supports required for the erection/modification shall be determined, documented, furnished and installed by the erector/contractor accounting for the loads imposed on the structure due to the proposed construction method.

7. REPORT DISCLAIMER

The engineering services rendered by Malouf Engineering International, Inc. ('MEI') in connection with this Structural Analysis are limited to a computer analysis of the tower structure, size and capacity of its members. MEI does not analyze the fabrication, including welding and connection capacities, except as included in this Report.

The analysis performed and the conclusions contained herein are based on the assumption that the tower has been properly installed and maintained, including, but not limited to the following:

1. Proper alignment and plumbness.
2. Correct guy tensions, as applicable.
3. Correct bolt tightness or slip jacking of sleeved connections.
4. No significant deterioration or damage to any structural component.

Furthermore, the information and conclusions contained in this Report were determined by application of the current "state-of-the-art" engineering and analysis procedures and formulae. MALOUF ENGINEERING INTERNATIONAL, INC. assumes no obligation to revise any of the information or conclusions contained in this Report in the event that such engineering and analysis procedures and formulae are hereafter modified or revised. In addition, under no circumstances will MALOUF ENGINEERING INTERNATIONAL, INC. have any obligation or responsibility whatsoever for or on account of consequential or incidental damages sustained by any person, firm or organization as a result of any information or conclusions contained in the Report, and the maximum liability of MALOUF ENGINEERING INTERNATIONAL, INC., if any, pursuant to this Report shall be limited to the total funds actually received by MALOUF ENGINEERING INTERNATIONAL, INC. for preparation of this Report.

Customer has requested MALOUF ENGINEERING INTERNATIONAL, INC. to prepare and submit to Customer an engineering analysis with respect to the Subject Tower and has further requested MALOUF ENGINEERING INTERNATIONAL, INC. to make appropriate recommendations regarding suggested structural modifications and changes to the Subject Tower. In making such request of MALOUF ENGINEERING INTERNATIONAL, INC., Customer has informed MALOUF ENGINEERING INTERNATIONAL, INC. that Customer will make a determination as to whether or not to implement any of the changes or modifications which may be suggested by MALOUF ENGINEERING INTERNATIONAL, INC. and that Customer will have any such changes or modifications made by riggers, erectors and other subcontractors of Customer's choice. MALOUF ENGINEERING INTERNATIONAL, INC. shall have the right to rely upon the accuracy of the information supplied by the customer and shall not be held responsible for the Customer's misrepresentation or omission of relevant fact whether intentional or otherwise.

Customer hereby agrees and acknowledges that MALOUF ENGINEERING INTERNATIONAL, INC. shall have no liability whatsoever to Customer or to others for any work or services performed by any persons other than MALOUF ENGINEERING INTERNATIONAL, INC. in connection with the implementation of services including but not limited to any services rendered for Customer or for others by riggers, erectors or other subcontractors. Customer acknowledges and agrees that any riggers, erectors or subcontractors retained or employed by Customer shall be solely responsible to Customer and to others for the quality of work performed by them and that MALOUF ENGINEERING INTERNATIONAL, INC. shall have no liability or responsibility whatsoever as a result of any negligence or breach of contract by any such rigger, erector or subcontractor and that Customer and rigger, erector, or subcontractor will provide MALOUF ENGINEERING INTERNATIONAL, INC. with a Certificate of Insurance naming MALOUF ENGINEERING INTERNATIONAL, INC. as additional insured.

APPENDIX 1 - ANALYSIS PRINTOUT & GRAPHICS

DESIGNED APPURTENANCE LOADING

TYPE	ELEVATION	TYPE	ELEVATION
(2) TOP SMALL BEACONS (E)	245.17	PIPE DISH MOUNT (E)	223.5
TOP LIGHTNING ROD (E)	244.5	10 FT HP DISH (E)	223.5
(3) HPA-45R-BUU-H6 w/ Pipe Mounts (ATI / N)	235	PIPE DISH MOUNT (E)	221
(2) LGP21401 TMA'S (ATI / E)	235	1 FT HP DISH (WINDSTAR 43029) (E)	221
(2) HPA-45R-BUU-H6 w/ Pipe Mounts (ATI / N)	235	4'Lx6'W REST PLATFORM (E)	216.5
HPA-45R-BUU-H6 w/ Pipe Mounts (ATI / N)	235	4'Lx6'W REST PLATFORM (E)	216.5
(2) LGP21401 TMA'S (ATI / E)	235	AIR21 B2A B4P w/ pipe Mount (T-MOBILE / E)	210
RRUS-11 (ATI / E)	235	AIR-32 Panel w/ Pipe Mount (T-MOBILE / P)	210
RRUS-11 (ATI / E)	235	AIR-32 Panel w/ Pipe Mount (T-MOBILE / P)	210
P65-15-XLH-RR w/ Pipe Mount (ATI / E)	235	AIR-32 Panel w/ Pipe Mount (T-MOBILE / P)	210
OPA-65R-LCUU-H4 w/ Pipe Mounts (ATI / E)	235	KRY 112 71/2 (T-MOBILE / E)	210
OPA-65R-LCUU-H4 w/ Pipe Mounts (ATI / E)	235	KRY 112 71/2 (T-MOBILE / E)	210
LGP21401 TMA'S (ATI / E)	235	KRY 112 71/2 (T-MOBILE / E)	210
LGP21401 TMA'S (ATI / E)	235	SECTOR FRAME MOUNT (T-MOBILE / E)	210
RRUS-11 (ATI / E)	235	SECTOR FRAME MOUNT (T-MOBILE / E)	210
RRUS-12 w/ A2 Backpack (ATI / E)	235	AIR21 B2A B4P w/ pipe Mount (T-MOBILE / E)	210
RRUS-12 w/ A2 Backpack (ATI / E)	235	AIR21 B2A B4P w/ pipe Mount (T-MOBILE / E)	210
RRUS-32 (ATI / E)	235	LNx-6515DS-VTM w/ Pipe Mnt. (T-MOBILE / N)	203
RRUS-32 (ATI / E)	235	RRUS-11 B12 (T-MOBILE / N)	203
RRUS-32 (ATI / E)	235	RRUS-11 B12 (T-MOBILE / N)	203
RAYCAP DC6-48-60-18-8F DC SURGE BOX (ATI / E)	233	RRUS-11 B12 (T-MOBILE / N)	203
RAYCAP DC6-48-60-18-8F DC SURGE BOX (ATI / E)	233	SECTOR FRAME MOUNT (T-MOBILE / E)	203
RAYCAP DC6-48-60-18-8F DC SURGE BOX (ATI / E)	233	SECTOR FRAME MOUNT (T-MOBILE / E)	203
13' T BEAM MOUNT (E)	231.5	SECTOR FRAME MOUNT (T-MOBILE / E)	203
UNUSED I-BEAM MOUNT (ATI / E)	231.5	LNx-6515DS-VTM w/ Pipe Mnt. (T-MOBILE / N)	203
TOP SQUARE PLATFORM MOUNT (ATI / E)	231.5	LNx-6515DS-VTM w/ Pipe Mnt. (T-MOBILE / N)	203
1.5x2-ELEMENT YAGI AND MOUNT (ATI / E)	229	4x7-ELEMENT YAGI (ATI / E)	132
		2FT SIDEARM MOUNT (ATI / E)	132

SYMBOL LIST

MARK	SIZE	MARK	SIZE
A	C8x11.5	B	L2 1/2x2 1/2x1/4


MATERIAL STRENGTH

GRADE	Fy	Fu	GRADE	Fy	Fu
A36	36 ksi	58 ksi			

TOWER DESIGN NOTES


1. Tower is located in Fairfield County, Connecticut.
2. Tower designed for a 85 mph basic wind in accordance with the TIA/EIA-222-F Standard.
3. Tower is also designed for a 74 mph basic wind with 0.50 in ice.
4. Deflections are based upon a 50 mph wind.
5. TOWER RATING: 98.8%

231.5 ft
229.0 ft
224.8 ft
220.7 ft
216.5 ft
211.5 ft
206.5 ft
201.5 ft
196.5 ft
191.5 ft
181.5 ft
171.5 ft
161.5 ft
151.5 ft
141.5 ft
131.5 ft
119.0 ft
106.5 ft




MAX. CORNER REACTIONS AT BASE:
DOWN: 263 K
SHEAR: 24 K

UPLIFT: -229 K
SHEAR: 21 K



TORQUE 21 kip-ft
74 mph WIND - 0.5000 in ICE



TORQUE 24 kip-ft
REACTIONS - 85 mph WIND

Section	T17	T16	T15	T14	T13	T12	T11	T10	T9	T8	T7	T6	T5	T4	T3	T2	T1
Legs	L6x6x7/8	L6x6x3/4	L6x6x5/8	A36	L5x5x1/2	L4x4x3/8											
Leg Grade																	
Diagonals	2L2 1/2x2 1/2x1/4x3/8	L3x3x1/4	A36														
Diagonal Grade																	
Top Girts	2L2 1/2x2 1/2x1/4x3/8	L2 1/2x2 1/2x1/4	L2 1/2x2 1/2x1/4	L2 1/2x2 1/2x1/4	L2 1/2x2 1/2x1/4	L2 1/2x2 1/2x1/4	L2 1/2x2 1/2x1/4	L2 1/2x2 1/2x1/4	L2 1/2x2 1/2x1/4	L2 1/2x2 1/2x1/4	L2 1/2x2 1/2x1/4	L2 1/2x2 1/2x1/4	L2 1/2x2 1/2x1/4	L2 1/2x2 1/2x1/4	L2 1/2x2 1/2x1/4	L2 1/2x2 1/2x1/4	L2 1/2x2 1/2x1/4
Horizontals	N.A.	L2 1/2x2 1/2x1/4	L2 1/2x2 1/2x1/4	L2 1/2x2 1/2x1/4	L2 1/2x2 1/2x1/4	L2 1/2x2 1/2x1/4	L2 1/2x2 1/2x1/4	L2 1/2x2 1/2x1/4	L2 1/2x2 1/2x1/4	L2 1/2x2 1/2x1/4	L2 1/2x2 1/2x1/4	L2 1/2x2 1/2x1/4	L2 1/2x2 1/2x1/4	L2 1/2x2 1/2x1/4	L2 1/2x2 1/2x1/4	L2 1/2x2 1/2x1/4	L2 1/2x2 1/2x1/4
Sec. Horizontals	N.A.	L2 1/2x2 3/16	L2 1/2x2 3/16	L2 1/2x2 3/16	L2 1/2x2 3/16	L2 1/2x2 3/16	L2 1/2x2 3/16	L2 1/2x2 3/16	L2 1/2x2 3/16	L2 1/2x2 3/16	L2 1/2x2 3/16	L2 1/2x2 3/16	L2 1/2x2 3/16	L2 1/2x2 3/16	L2 1/2x2 3/16	L2 1/2x2 3/16	L2 1/2x2 3/16
Red. Horizontals	L2 1/2x2 3/16	L2 1/2x2 3/16	L2 1/2x2 3/16	L2 1/2x2 3/16	L2 1/2x2 3/16	L2 1/2x2 3/16	L2 1/2x2 3/16	L2 1/2x2 3/16	L2 1/2x2 3/16	L2 1/2x2 3/16	L2 1/2x2 3/16	L2 1/2x2 3/16	L2 1/2x2 3/16	L2 1/2x2 3/16	L2 1/2x2 3/16	L2 1/2x2 3/16	L2 1/2x2 3/16
Red. Diagonals	L2 1/2x2 3/16	L2 1/2x2 3/16	L2 1/2x2 3/16	L2 1/2x2 3/16	L2 1/2x2 3/16	L2 1/2x2 3/16	L2 1/2x2 3/16	L2 1/2x2 3/16	L2 1/2x2 3/16	L2 1/2x2 3/16	L2 1/2x2 3/16	L2 1/2x2 3/16	L2 1/2x2 3/16	L2 1/2x2 3/16	L2 1/2x2 3/16	L2 1/2x2 3/16	L2 1/2x2 3/16
Red. Sub-Diags	L2 1/2x2 3/16	L2 1/2x2 3/16	L2 1/2x2 3/16	L2 1/2x2 3/16	L2 1/2x2 3/16	L2 1/2x2 3/16	L2 1/2x2 3/16	L2 1/2x2 3/16	L2 1/2x2 3/16	L2 1/2x2 3/16	L2 1/2x2 3/16	L2 1/2x2 3/16	L2 1/2x2 3/16	L2 1/2x2 3/16	L2 1/2x2 3/16	L2 1/2x2 3/16	L2 1/2x2 3/16
Inner Bracing	L3x3x3/16	L3x3x3/16	L3x3x3/16	L3x3x3/16	L3x3x3/16	L3x3x3/16	L3x3x3/16	L3x3x3/16	L3x3x3/16	L3x3x3/16	L3x3x3/16	L3x3x3/16	L3x3x3/16	L3x3x3/16	L3x3x3/16	L3x3x3/16	L3x3x3/16
Face Width (ft)	13.5833	12.6766	11.0445	10.3191	9.58373	8.86836	8.14298	7.41761	6.69223	5.96685	5.24144	4.51607	3.79070	3.06533	2.34000	1.61467	0.88930
# Panels @ (ft)	1 @ 12.4999	1 @ 12.5	2 @ 5	2 @ 5	2 @ 5	2 @ 5	2 @ 5	2 @ 5	2 @ 5	2 @ 5	2 @ 5	2 @ 5	2 @ 5	2 @ 5	2 @ 5	2 @ 5	2 @ 5
Weight (K)	25.4	4.0	3.5	2.6	2.6	2.6	2.6	2.6	2.6	2.6	2.6	2.6	2.6	2.6	2.6	2.6	2.6

<p>Malouf Engineering Int'l, Inc. 17950 Preston Road, Suite #720 Dallas, TX 75252 Phone: (972) 783-2578 FAX: (972) 783-2583</p>		Job: 125 FT SST, STAMFORD / DWTN SITE #CT11410A	Project: CT02768S-16V0
		Client: NORTHEAST SITE SOLUTIONS / T-MOBILE	Drawn by: LNguyen
maloufengineering.com	Code: TIA/EIA-222-F	Date: 03/17/16	Scale: NTS
	Path: D:\MEIP\Projects\16 DATA\SS\CT02768S-16V0\CT02768S-16V0.dwg	Dwg No. E-1	


ALL RIGHTS RESERVED. THIS DRAWING SHALL REMAIN THE PROPERTY OF MALOUF ENGINEERING INTERNATIONAL, INC. NO PART THEREOF SHALL BE REPRODUCED, COPIED, ADAPTED, DISCLOSED, OR DISTRIBUTED TO OTHERS WITHOUT WRITTEN PERMISSION OF MEI, INC.

No.	QTY.	DESCRIPTION	ELEV.	TENANT
1	1	Safety Climb & Climbing Ladder	125'	E
2	1	1 1/4" Rigid Conduit	125'	E
3	12	1 5/8	125'	AT&T / E
4	1	0.30	125'	AT&T / E
5	4	0.75" DC POWER TRUNK CABLES	125'	AT&T / E
6	2	0.625" FIBER TRUNK CABLE	125'	AT&T / E
7	2	3/8 (UNUSED)	115'	E
8	1	3/8	114.5'	E
9	1	1/2	122.5'	E
10	2	EW90	117'	E
11	1	1/2	25.5'	E
12	30	1 5/8	103.5'	T-MOBILE / E
13	1	HUBER-SUHNER 1.25" TC-OF CABLE	103.5'	T-MOBILE / E

LEGEND:

- E = EXISTING ○ — #X
- P = PROPOSED ○ — #X
- F = FUTURE ○ — #X
- R = REMOVE ○ — #X
- TO RELOCATE ○ — #X

NO NEW LINES ADDED.



101 PLAN: SCHEMATIC Tx-LINE LAYOUT
SCALE: NOT TO SCALE

- NOTE:**
1. Tx LINE LAYOUT IS SCHEMATIC ONLY, BASED UPON MEI RECORDS. NO NEW SITE PHOTOS PROVIDED.
 2. NO NEW LINES ARE ADDED.
 3. ELEVATIONS SHOWN ARE ABOVE ROOF LINE.

Mar 17, 2016



17950 PRESTON ROAD SUITE 720
DALLAS, TEXAS 75252-5635
972-783-2578 (fax: 2583)
www.maloufengineering.com




© MEI, INC. 2015



STAMFORD / DWTN SITE #CT11410A

TOWER TxLINE LAYOUT

MEI PROJECT ID	SHEET NUMBER	REV.
CT02768S-16V0	L01	0




<p>Malouf Engineering Int'l, Inc. 17950 Preston Road, Suite #720 Dallas, TX 75252 Phone: (972) 783-2578 FAX: (972) 783-2583</p>		<p>Job: 125 FT SST, STAMFORD / DWTN SITE #CT11410A</p>	
		<p>Project: CT02768S-16V0</p>	<p>Client: NORTHEAST SITE SOLUTIONS / T-MOBILE</p>
<p>maloufengineering.com</p>	<p>Date: 03/17/16</p>	<p>Drawn by: LNguyen</p>	<p>App'd:</p>
<p>Code: TIA/EIA-222-F</p>	<p>Scale: NTS</p>	<p>Path: D:\MEI\Projects\16 DATA\SST\CT02768S-16V0\CT02768S-16V0.eri</p>	<p>Dwg No. E-5</p>

TIA/EIA-222-F - 85 mph/74 mph 0.5000 in Ice

Leg Capacity ———

Leg Compression (K)



<p>Malouf Engineering Int'l, Inc. 17950 Preston Road, Suite #720 Dallas, TX 75252 Phone: (972) 783-2578 FAX: (972) 783-2583</p>		<p>Job: 125 FT SST, STAMFORD / DWTN SITE #CT11410A</p>		
		<p>Project: CT02768S-16V0</p>	<p>Client: NORTHEAST SITE SOLUTIONS / T-MOBILE</p>	<p>Drawn by: LNguyen</p>
<p>maloufengineering.com</p>		<p>Code: TIA/EIA-222-F</p>	<p>Date: 03/17/16</p>	<p>Scale: NTS</p>
		<p>Path: D:\MEI\Projects\16 DATA\SS\CT02768S-16V0\CT02768S-16V0.eri</p>		<p>Dwg No. E-3</p>

tnxTower Malouf Engineering Int'l, Inc. 17950 Preston Road, Suite #720 Dallas, TX 75252 Phone: (972) 783-2578 FAX: (972) 783-2583	Job 125 FT SST, STAMFORD / DWTN SITE #CT11410A	Page 1 of 7
	Project CT02768S-16V0	Date 16:04:22 03/17/16
	Client NORTHEAST SITE SOLUTIONS / T-MOBILE	Designed by LNguyen

Tower Input Data

The main tower is a 4x free standing tower with an overall height of 231.50 ft above the ground line.

The base of the tower is set at an elevation of 106.50 ft above the ground line.

The face width of the tower is 5.60 ft at the top and 13.58 ft at the base.

This tower is designed using the TIA/EIA-222-F standard.

The following design criteria apply:

Tower is located in Fairfield County, Connecticut.

Basic wind speed of 85 mph.

Nominal ice thickness of 0.5000 in.

Ice density of 56 pcf.

A wind speed of 74 mph is used in combination with ice.

Temperature drop of 50 °F.

Deflections calculated using a wind speed of 50 mph.

A non-linear (P-delta) analysis was used.

Pressures are calculated at each section.

Stress ratio used in tower member design is 1.333.

Local bending stresses due to climbing loads, feed line supports, and appurtenance mounts are not considered.

Feed Line/Linear Appurtenances - Entered As Round Or Flat

Description	Placement <i>ft</i>	Total Number	Description	Placement <i>ft</i>	Total Number
Safety Line 3/8 (E)	231.50 - 106.50	1	(E) EW90	223.50 - 106.50	2
Climbing Ladder (E)	231.50 - 106.50	1	(E) 3/8	221.50 - 106.50	2
W/G LADDER "A" (E)	212.50 - 106.50	1	(E (UNUSED)) 3/8	221.00 - 106.50	1
W/G LADDER "B" (E)	206.50 - 106.50	1	(E) 1 5/8	210.00 - 106.50	12
W/G LADDER "C" (E)	200.50 - 106.50	1	(T-MOBILE / E) Huber-Suhner 1.25"	210.00 - 106.50	1
1 1/4" Rigid Conduit (E)	231.50 - 106.50	1	TC-OF Cable (T-MOBILE / E)		
0.625" Fiber Trunk Cable (AT&T / E)	231.50 - 106.50	2	1 5/8	210.00 - 106.50	6
0.75" DC Power Trunk Cable (AT&T / E)	231.50 - 106.50	4	(T-MOBILE / E) 1 5/8	210.00 - 106.50	12
1 5/8 (AT&T / E)	231.50 - 106.50	12	(T-MOBILE / E) 1/2	132.00 - 106.50	1
0.30 (AT&T / E)	231.50 - 106.50	1	(E)		
1/2 (AT&T / E)	229.00 - 106.50	1			

Feed Line/Linear Appurtenances - Entered As Area

Description	Placement <i>ft</i>	Total Number	Description	Placement <i>ft</i>	Total Number
MISCELLANEOUS (E)	231.50 - 106.50	2	(E)		
MISCELLANEOUS WEIGHT	231.50 - 106.50	1			

tnxTower Malouf Engineering Int'l, Inc. 17950 Preston Road, Suite #720 Dallas, TX 75252 Phone: (972) 783-2578 FAX: (972) 783-2583	Job 125 FT SST, STAMFORD / DWTN SITE #CT11410A	Page 2 of 7
	Project CT02768S-16V0	Date 16:04:22 03/17/16
	Client NORTHEAST SITE SOLUTIONS / T-MOBILE	Designed by LNguyen

Discrete Tower Loads

Description	Placement	Weight	Description	Placement	Weight
	ft	K		ft	K
(2) TOP SMALL BEACONS (E)	245.17	0.06 0.09	UNUSED I-BEAM MOUNT (AT&T / E)	231.50	0.10 0.15
TOP LIGHTNING ROD (E)	244.50	0.05 0.07	1.5'x2-ELEMENT YAGI AND MOUNT (AT&T / E)	229.00	0.07 0.13
13' T BEAM MOUNT (E)	231.50	0.10 0.15	TOP SQUARE PLATFORM MOUNT (AT&T / E)	231.50	5.50 7.50
(3) HPA-45R-BUU-H6 w/ Pipe Mounts (AT&T / N)	235.00	0.08 0.17	PIPE DISH MOUNT (E)	223.50	0.15 0.23
(2) LGP21401 TMA'S (AT&T / E)	235.00	0.02 0.03	PIPE DISH MOUNT (E)	221.00	0.07 0.10
(2) HPA-45R-BUU-H6 w/ Pipe Mounts (AT&T / N)	235.00	0.08 0.17	4'Lx6'W REST PLATFORM (E)	216.50	0.75 1.25
HPA-45R-BUU-H6 w/ Pipe Mounts (AT&T / N)	235.00	0.08 0.17	4'Lx6'W REST PLATFORM (E)	216.50	0.75 1.25
(2) LGP21401 TMA'S (AT&T / E)	235.00	0.02 0.03	AIR21 B2A B4P w/ pipe Mount (T-MOBILE / E)	210.00	0.13 0.18
RRUS-11 (AT&T / E)	235.00	0.05 0.07	AIR21 B2A B4P w/ pipe Mount (T-MOBILE / E)	210.00	0.13 0.18
RRUS-11 (AT&T / E)	235.00	0.05 0.07	AIR-32 Panel w/ Pipe Mount (T-MOBILE / P)	210.00	0.15 0.22
RAYCAP DC6-48-60-18-8F DC SURGE BOX (AT&T / E)	233.00	0.03 0.06	AIR-32 Panel w/ Pipe Mount (T-MOBILE / P)	210.00	0.15 0.22
P65-15-XLH-RR w/ Pipe Mount (AT&T / E)	235.00	0.07 0.12	AIR-32 Panel w/ Pipe Mount (T-MOBILE / P)	210.00	0.15 0.22
OPA-65R-LCUU-H4 w/ Pipe Mounts (AT&T / E)	235.00	0.08 0.13	KRY 112 71/2 (T-MOBILE / E)	210.00	0.01 0.02
OPA-65R-LCUU-H4 w/ Pipe Mounts (AT&T / E)	235.00	0.08 0.13	KRY 112 71/2 (T-MOBILE / E)	210.00	0.01 0.02
LGP21401 TMA'S (AT&T / E)	235.00	0.02 0.03	KRY 112 71/2 (T-MOBILE / E)	210.00	0.01 0.02
LGP21401 TMA'S (AT&T / E)	235.00	0.02 0.03	SECTOR FRAME MOUNT (T-MOBILE / E)	210.00	0.40 0.60
RRUS-11 (AT&T / E)	235.00	0.05 0.07	SECTOR FRAME MOUNT (T-MOBILE / E)	210.00	0.40 0.60
RRUS-12 w/ A2 Backpack (AT&T / E)	235.00	0.08 0.11	SECTOR FRAME MOUNT (T-MOBILE / E)	210.00	0.40 0.60
RRUS-12 w/ A2 Backpack (AT&T / E)	235.00	0.08 0.11	LNx-6515DS-VTM w/ Pipe Mnt. (T-MOBILE / N)	203.00	0.08 0.17
RRUS-12 w/ A2 Backpack (AT&T / E)	235.00	0.08 0.11	LNx-6515DS-VTM w/ Pipe Mnt. (T-MOBILE / N)	203.00	0.08 0.17
RAYCAP DC6-48-60-18-8F DC SURGE BOX (AT&T / E)	233.00	0.03 0.06	LNx-6515DS-VTM w/ Pipe Mnt. (T-MOBILE / N)	203.00	0.08 0.17
RRUS-32 (AT&T / E)	235.00	0.08 0.10	LNx-6515DS-VTM w/ Pipe Mnt. (T-MOBILE / N)	203.00	0.08 0.17
RRUS-32 (AT&T / E)	235.00	0.08 0.10	RRUS-11 B12 (T-MOBILE / N)	203.00	0.05 0.07
RRUS-32 (AT&T / E)	235.00	0.08 0.10	RRUS-11 B12 (T-MOBILE / N)	203.00	0.05 0.07
RRUS-32 (AT&T / E)	235.00	0.08 0.10			

tnxTower Malouf Engineering Int'l, Inc. 17950 Preston Road, Suite #720 Dallas, TX 75252 Phone: (972) 783-2578 FAX: (972) 783-2583	Job	125 FT SST, STAMFORD / DWTN SITE #CT11410A	Page	3 of 7
	Project	CT02768S-16V0	Date	16:04:22 03/17/16
	Client	NORTHEAST SITE SOLUTIONS / T-MOBILE	Designed by	LNguyen

Description	Placement	Weight	Description	Placement	Weight
	ft	K		ft	K
RRUS-11 B12	203.00	0.05	(T-MOBILE / E)		0.60
(T-MOBILE / N)		0.07	4x7-ELEMENT YAGI	132.00	0.03
SECTOR FRAME MOUNT	203.00	0.40	(AT&T / E)		0.04
(T-MOBILE / E)		0.60	2FT SIDEARMS MOUNT	132.00	0.10
SECTOR FRAME MOUNT	203.00	0.40	(AT&T / E)		0.15
(T-MOBILE / E)		0.60			
SECTOR FRAME MOUNT	203.00	0.40			

Dishes

Description	Dish Type	Elevation	Outside Diameter	Weight
		ft	ft	K
10 FT HP DISH (E)	Paraboloid w/Shroud (HP)	223.50	10.00	0.40
1 FT HP DISH (WINDSTAR 43029) (E)	Paraboloid w/Shroud (HP)	221.00	1.00	0.03

Maximum Reactions

Location	Condition	Gov. Load Comb.	Vertical K	Horizontal, X K	Horizontal, Z K
Leg D	Max. Vert	16	259.56	16.15	-16.84
	Max. H _x	16	259.56	16.15	-16.84
	Max. H _z	12	-226.24	-14.88	15.69
	Min. Vert	3	-229.21	-14.49	15.47
	Min. H _x	12	-226.24	-14.88	15.69
	Min. H _z	16	259.56	16.15	-16.84
Leg C	Max. Vert	14	250.83	-16.22	-15.97
	Max. H _x	18	-215.64	14.80	14.66
	Max. H _z	18	-215.64	14.80	14.66
	Min. Vert	18	-215.64	14.80	14.66
	Min. H _x	14	250.83	-16.22	-15.97
	Min. H _z	14	250.83	-16.22	-15.97
Leg B	Max. Vert	12	262.78	-17.03	16.29
	Max. H _x	16	-223.00	15.39	-14.85
	Max. H _z	12	262.78	-17.03	16.29
	Min. Vert	7	-224.69	15.07	-14.45
	Min. H _x	12	262.78	-17.03	16.29
	Min. H _z	16	-223.00	15.39	-14.85
Leg A	Max. Vert	18	252.26	15.94	16.29
	Max. H _x	18	252.26	15.94	16.29
	Max. H _z	18	252.26	15.94	16.29
	Min. Vert	14	-214.19	-14.51	-14.91
	Min. H _x	14	-214.19	-14.51	-14.91
	Min. H _z	14	-214.19	-14.51	-14.91

tnxTower Malouf Engineering Int'l, Inc. 17950 Preston Road, Suite #720 Dallas, TX 75252 Phone: (972) 783-2578 FAX: (972) 783-2583	Job 125 FT SST, STAMFORD / DWTN SITE #CT11410A	Page 4 of 7
	Project CT02768S-16V0	Date 16:04:22 03/17/16
	Client NORTHEAST SITE SOLUTIONS / T-MOBILE	Designed by LNguyen

Maximum Tower Deflections - Service Wind

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
T1	231.5 - 229	2.838	20	0.1821	0.0304
T2	229 - 224.833	2.712	20	0.1816	0.0269
T3	224.833 - 220.667	2.554	20	0.1805	0.0266
T4	220.667 - 216.5	2.398	20	0.1774	0.0259
T5	216.5 - 211.5	2.244	20	0.1729	0.0250
T6	211.5 - 206.5	2.059	20	0.1686	0.0229
T7	206.5 - 201.5	1.880	20	0.1627	0.0208
T8	201.5 - 196.5	1.705	20	0.1559	0.0187
T9	196.5 - 191.5	1.539	20	0.1474	0.0166
T10	191.5 - 181.5	1.381	20	0.1381	0.0148
T11	181.5 - 171.5	1.085	20	0.1248	0.0116
T12	171.5 - 161.5	0.820	20	0.1093	0.0092
T13	161.5 - 151.5	0.591	20	0.0920	0.0073
T14	151.5 - 141.5	0.399	20	0.0733	0.0057
T15	141.5 - 131.5	0.244	20	0.0565	0.0043
T16	131.5 - 119	0.125	20	0.0391	0.0032
T17	119 - 106.5	0.035	20	0.0199	0.0015

Critical Deflections and Radius of Curvature - Service Wind

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
245.17	(2) TOP SMALL BEACONS	20	2.838	0.1821	0.0304	7200
244.50	TOP LIGHTNING ROD	20	2.838	0.1821	0.0304	7200
235.00	(3) HPA-45R-BUU-H6 w/ Pipe Mounts	20	2.838	0.1821	0.0304	7200
233.00	RAYCAP DC6-48-60-18-8F DC SURGE BOX	20	2.838	0.1821	0.0304	7200
231.50	13' T BEAM MOUNT	20	2.838	0.1821	0.0304	7200
229.00	1.5'x2-ELEMENT YAGI AND MOUNT	20	2.712	0.1816	0.0269	7200
223.50	10 FT HP DISH	20	2.505	0.1797 (3 dB)	0.0266 (3 dB)	108136
221.00	1 FT HP DISH (WINDSTAR 43029)	20	2.410	0.1777	0.0260	262667
216.50	4'Lx6'W REST PLATFORM	20	2.244	0.1729	0.0250	149764
210.00	AIR21 B2A B4P w/ pipe Mount	20	2.005	0.1670	0.0223	53100
203.00	LNx-6515DS-VTM w/ Pipe Mnt.	20	1.757	0.1580	0.0194	43770
132.00	4'x7-ELEMENT YAGI	20	0.130	0.0399	0.0033	28189

Section Capacity Table

Section No.	Elevation ft	Component Type	Size	Critical Element	P K	SF*P _{allow} K	% Capacity	Pass Fail
T1	231.5 - 229	Leg	L4x4x3/8	4	-4.96	60.16	98.8	Pass
T2	229 - 224.833	Leg	L4x4x3/8	12	-8.16	65.17	12.5	Pass
T3	224.833 - 220.667	Leg	L4x4x3/8	21	-16.00	65.17	24.6	Pass
T4	220.667 - 216.5	Leg	L4x4x3/8	37	-22.05	65.17	33.8	Pass
T5	216.5 - 211.5	Leg	L5x5x1/2	51	-29.50	109.68	26.9	Pass
T6	211.5 - 206.5	Leg	L5x5x1/2	67	-41.25	109.68	37.6	Pass

Job	125 FT SST, STAMFORD / DWTN SITE #CT11410A	Page	5 of 7
Project	CT02768S-16V0	Date	16:04:22 03/17/16
Client	NORTHEAST SITE SOLUTIONS / T-MOBILE	Designed by	LNguyen

Section No.	Elevation ft	Component Type	Size	Critical Element	P K	SF*P _{allow} K	% Capacity	Pass Fail
T7	206.5 - 201.5	Leg	L5x5x1/2	83	-51.94	109.68	47.4	Pass
T8	201.5 - 196.5	Leg	L5x5x1/2	95	-63.31	109.68	57.7	Pass
T9	196.5 - 191.5	Leg	L5x5x1/2	111	-75.34	109.68	68.7	Pass
T10	191.5 - 181.5	Leg	L6x6x5/8	123	-85.50	171.13	50.0	Pass
T11	181.5 - 171.5	Leg	L6x6x5/8	148	-107.39	171.31	62.7	Pass
T12	171.5 - 161.5	Leg	L6x6x5/8	168	-128.68	171.45	75.1	Pass
T13	161.5 - 151.5	Leg	L6x6x5/8	193	-150.48	171.58	87.7	Pass
T14	151.5 - 141.5	Leg	L6x6x3/4	213	-173.89	203.35	85.5	Pass
T15	141.5 - 131.5	Leg	L6x6x3/4	238	-193.04	227.69	84.8	Pass
T16	131.5 - 119	Leg	L6x6x7/8	306	-208.85	220.76	94.6	Pass
T17	119 - 106.5	Leg	L6x6x7/8	347	-234.93	256.70	91.5	Pass
T2	229 - 224.833	Diagonal	2L2 1/2x2x1/4x3/8	20	-3.83	47.46	8.1	Pass
							9.9 (b)	
T3	224.833 - 220.667	Diagonal	2L2 1/2x2x1/4x3/8	35	-4.44	47.46	9.4	Pass
							11.7 (b)	
T4	220.667 - 216.5	Diagonal	2L2 1/2x2x1/4x3/8	47	-5.70	42.32	13.5	Pass
							15.2 (b)	
T5	216.5 - 211.5	Diagonal	L2 1/2x2x1/4	63	-5.81	16.13	36.0	Pass
T6	211.5 - 206.5	Diagonal	L2 1/2x2x1/4	79	-6.21	15.52	40.0	Pass
T7	206.5 - 201.5	Diagonal	L2 1/2x2x1/4	91	-6.94	14.88	46.6	Pass
T8	201.5 - 196.5	Diagonal	L2 1/2x2x1/4	107	-7.42	14.20	52.3	Pass
T9	196.5 - 191.5	Diagonal	L2 1/2x2x1/4	119	-7.48	13.49	55.5	Pass
T10	191.5 - 181.5	Diagonal	L3x3x1/4	138	-12.55	18.16	69.1	Pass
T11	181.5 - 171.5	Diagonal	L3x3x1/4	158	-12.61	17.25	73.1	Pass
T12	171.5 - 161.5	Diagonal	L3x3x1/4	183	-12.94	16.34	79.2	Pass
T13	161.5 - 151.5	Diagonal	L3x3x1/4	203	-13.27	15.46	85.9	Pass
T14	151.5 - 141.5	Diagonal	L3x3x1/4	228	-12.47	14.61	85.3	Pass
T15	141.5 - 131.5	Diagonal	L3x3x1/4	260	-14.64	23.59	62.1	Pass
							64.0 (b)	
T16	131.5 - 119	Diagonal	2L2 1/2x2 1/2x1/4x3/8	340	-18.32	23.51	77.9	Pass
T17	119 - 106.5	Diagonal	2L2 1/2x2 1/2x1/4x3/8	407	-17.67	49.40	35.8	Pass
							48.8 (b)	
T15	141.5 - 131.5	Horizontal	L2 1/2x2x1/4	251	-2.90	6.80	42.6	Pass
T10	191.5 - 181.5	Secondary Horizontal	L2 1/2x2x1/4	144	-1.28	17.59	7.3	Pass
T11	181.5 - 171.5	Secondary Horizontal	L2 1/2x2x1/4	163	-1.61	16.77	9.6	Pass
T12	171.5 - 161.5	Secondary Horizontal	L2 1/2x2x3/16	188	-1.93	12.25	15.8	Pass
T13	161.5 - 151.5	Secondary Horizontal	L2 1/2x2 1/2x1/4	208	-2.26	19.73	11.4	Pass
							11.7 (b)	
T14	151.5 - 141.5	Secondary Horizontal	L2 1/2x2x1/4	233	-2.61	14.08	18.5	Pass
T1	231.5 - 229	Top Girt	C8x11.5	8	-0.59	45.47	19.8	Pass
T3	224.833 - 220.667	Top Girt	L2 1/2x2 1/2x1/4	25	-1.07	16.58	6.5	Pass
T5	216.5 - 211.5	Top Girt	C7x9.8	53	-1.11	44.01	2.5	Pass
							3.9 (b)	
T6	211.5 - 206.5	Top Girt	L2 1/2x2x1/4	69	-0.93	11.61	8.0	Pass
T8	201.5 - 196.5	Top Girt	L2 1/2x2 1/2x1/4	97	-0.81	13.26	6.1	Pass
T10	191.5 - 181.5	Top Girt	L2 1/2x2 1/2x1/4	127	3.70	28.16	13.1	Pass
							19.9 (b)	
T11	181.5 - 171.5	Top Girt	L2 1/2x2 1/2x1/4	150	-5.47	17.20	31.8	Pass
							37.5 (b)	
T12	171.5 - 161.5	Top Girt	L2 1/2x2 1/2x1/4	172	7.50	28.16	26.6	Pass
							40.3 (b)	
T13	161.5 - 151.5	Top Girt	L2 1/2x2 1/2x1/4	195	-6.46	14.22	45.5	Pass
T14	151.5 - 141.5	Top Girt	L2 1/2x2 1/2x1/4	215	-5.97	21.28	28.1	Pass
							41.2 (b)	
T15	141.5 - 131.5	Top Girt	L2 1/2x2 1/2x1/4	240	-6.19	11.58	53.4	Pass
T16	131.5 - 119	Top Girt	2L2 1/2x2 1/2x1/4x3/8	311	-9.09	47.16	19.3	Pass
							26.9 (b)	
T17	119 - 106.5	Top Girt	2L2 1/2x2 1/2x1/4x3/8	352	-8.53	36.94	23.1	Pass
T15	141.5 - 131.5	Redund Horz 1 Bracing	L2 1/2x2x3/16	286	-2.90	14.46	20.0	Pass

tnxTower Malouf Engineering Int'l, Inc. 17950 Preston Road, Suite #720 Dallas, TX 75252 Phone: (972) 783-2578 FAX: (972) 783-2583	Job 125 FT SST, STAMFORD / DWTN SITE #CT11410A	Page 6 of 7
	Project CT02768S-16V0	Date 16:04:22 03/17/16
	Client NORTHEAST SITE SOLUTIONS / T-MOBILE	Designed by LNguyen


Section No.	Elevation ft	Component Type	Size	Critical Element	P K	SF*P _{allow} K	% Capacity	Pass Fail	
T16	131.5 - 119	Redund Horz 1 Bracing	L2 1/2x2x3/16	327	-3.13	14.29	21.9	Pass	
T17	119 - 106.5	Redund Horz 1 Bracing	L2 1/2x2x3/16	376	-3.53	13.76	25.6	Pass	
T15	141.5 - 131.5	Redund Diag 1 Bracing	L2 1/2x2x3/16	287	-1.96	12.65	15.5	Pass	
T16	131.5 - 119	Redund Diag 1 Bracing	L2 1/2x2x3/16	328	-3.63	5.32	68.3	Pass	
T17	119 - 106.5	Redund Diag 1 Bracing	L2 1/2x2x3/16	360	5.18	23.29	22.2	Pass	
T15	141.5 - 131.5	Redund Hip 1 Bracing	L2x2x1/4	303	-0.03	12.17	0.2	Pass	
T16	131.5 - 119	Redund Hip 1 Bracing	L2x2x1/4	344	-0.14	11.45	1.2	Pass	
T17	119 - 106.5	Redund Hip 1 Bracing	L2x2x1/4	402	-0.18	9.87	1.8	Pass	
T17	119 - 106.5	Redund Hip Diagonal 1 Bracing	L2x2x1/4	419	-0.11	2.18	5.2	Pass	
T17	119 - 106.5	Redund Sub Horz Bracing	L2 1/2x2x3/16	365	-3.86	20.91	18.5	Pass	
T17	119 - 106.5	Redund Sub Diagonal Bracing	L2 1/2x2x3/16	394	-4.67	15.91	29.4	Pass	
T10	191.5 - 181.5	Inner Bracing	L2 1/2x2 1/2x3/16	133	-0.04	5.55	0.8	Pass	
T12	171.5 - 161.5	Inner Bracing	L2 1/2x2 1/2x3/16	178	-0.09	3.88	2.3	Pass	
T14	151.5 - 141.5	Inner Bracing	L2x2 1/2x3/16	223	-0.09	1.91	4.7	Pass	
T16	131.5 - 119	Inner Bracing	L3x3x3/16	316	-0.13	3.86	3.4	Pass	
T17	119 - 106.5	Inner Bracing	L3x3x3/16	357	-0.13	3.33	3.8	Pass	
							Summary		
							Leg (T1)	98.8	Pass
							Diagonal (T13)	85.9	Pass
							Horizontal (T15)	42.6	Pass
							Secondary Horizontal (T14)	18.5	Pass
							Top Girt (T15)	53.4	Pass
							Redund Horz 1 Bracing (T17)	25.6	Pass
							Redund Diag 1 Bracing (T16)	68.3	Pass
							Redund Hip 1 Bracing (T17)	1.8	Pass
							Redund Hip Diagonal 1 Bracing (T17)	5.2	Pass
							Redund Sub Horz Bracing (T17)	18.5	Pass
							Redund Sub Diagonal Bracing (T17)	29.4	Pass

<i>tnxTower</i> Malouf Engineering Int'l, Inc. 17950 Preston Road, Suite #720 Dallas, TX 75252 Phone: (972) 783-2578 FAX: (972) 783-2583	Job 125 FT SST, STAMFORD / DWTN SITE #CT11410A	Page 7 of 7
	Project CT02768S-16V0	Date 16:04:22 03/17/16
	Client NORTHEAST SITE SOLUTIONS / T-MOBILE	Designed by LNguyen

Section No.	Elevation ft	Component Type	Size	Critical Element	P K	SF*P _{allow} K	% Capacity	Pass Fail
						Inner Bracing (T14)	4.7	Pass
						Bolt Checks	65.2	Pass
						RATING =	98.8	Pass


APPENDIX 2 – SOURCE / CHANGED CONDITION

FINAL DESIGN PENDING STRUCTURAL EVALUATION.



ELEVATION VIEW
 SCALE: 1" = 30'-0" (11x17)
 1" = 15'-0" (24x36)

1
A-2




T-Mobile
T-MOBILE NORTHEAST, LLC
 35 GRIFFIN ROAD SOUTH
 BLOOMFIELD, CT 06002
 OFFICE: (860) 692-7100
 FAX: (860) 692-7159

ATLANTIS DESIGN GROUP, INC.
 286 Old Connecticut Path,
 Wayland, MA 01778
 Phone number: 617-852-3611
 Fax Number : 781-742-2247

SUBMITTALS		
DATE	DESCRIPTION	REVISION
10/20/15	ISSUED FOR REVIEW	A
11/02/15	FINAL CD	0

DEPT.	DATE	APP'D	REVISIONS
RFE			
RF MAN.			
ZONING			
OPS			
CONSTR.			
SITE AC.			

PROJECT NO: CT11410A
 DRAWN BY: PS
 CHECKED BY: KM





THIS DOCUMENT IS THE CREATION, DESIGN, PROPERTY AND COPYRIGHTED WORK OF T-MOBILE. ANY DUPLICATION OR USE WITHOUT EXPRESS WRITTEN CONSENT IS STRICTLY PROHIBITED.

SITE NAME
CT11410A
 SITE NAME
 STAMFORD / DWTN
 SITE ADDRESS
 555 E MAIN STREET
 STAMFORD, CT, 06901

SHEET TITLE
 ELEVATION

SHEET NUMBER
A-2




FINAL DESIGN PENDING STRUCTURAL EVALUATION.



EXISTING ANTENNA CONFIGURATION

RAD CENTER OF (E) T-MOBILE ANTENNAS ELEV.= 203'-0"± (AGL)

RAD CENTER OF (E) T-MOBILE ANTENNAS ELEV.= 210'-0"± (AGL)



MANUFACTURER: ERICSSON
MODEL NO.: ERICSSON AIR32 B4A/B2P
DIMENSIONS - HxWxD, (IN) 56.6"x12.9"x8.7"

ERICSSON AIR32 B4A/B2P ANTENNA DETAILS




SCALE: N.T.S.

2
A-3

PROPOSED ANTENNA CONFIGURATION

RAD CENTER OF (P) T-MOBILE ANTENNAS ELEV.= 210'-0"± (AGL)

RAD CENTER OF (E) & (P) T-MOBILE ANTENNAS ELEV.= 210'-0"± (AGL)



ANTENNA MOUNT DETAILS

SCALE: N.T.S.

3
A-3

ANTENNA PLAN CONFIGURATION

SCALE: N.T.S.

1
A-3

T-Mobile
T-MOBILE NORTHEAST, LLC
 35 GRIFFIN ROAD SOUTH
 BLOOMFIELD, CT 06002
 OFFICE: (860) 692-7100
 FAX: (860) 692-7159

ATLANTIS DESIGN GROUP, INC.
 286 Old Connecticut Path,
 Wayland, MA 01778
 Phone number: 617-852-3811
 Fax Number: 781-742-2247

SUBMITTALS		
DATE	DESCRIPTION	REVISION
10/20/15	ISSUED FOR REVIEW	A
11/02/15	FINAL CD	0

DEPT.	DATE	APP'D	REVISIONS
RFE			
RF MAN.			
ZONING			
OPS			
CONSTR.			
SITE AC.			

PROJECT NO:	CT11410A
DRAWN BY:	PS
CHECKED BY:	KM

PROFESSIONAL SEAL

THIS DOCUMENT IS THE CREATION, DESIGN, PROPERTY AND COPYRIGHTED WORK OF T-MOBILE. ANY DUPLICATION OR USE WITHOUT EXPRESS WRITTEN CONSENT IS STRICTLY PROHIBITED.

SITE NAME
CT11410A

SITE NAME
STAMFORD / DWTN

SITE ADDRESS
555 E MAIN STREET
STAMFORD, CT, 06901

SHEET TITLE
ANTENNA PLAN AND DETAILS


SHEET NUMBER
A-3

SUBMITTALS

DATE	DESCRIPTION	REVISION
10/20/15	ISSUED FOR REVIEW	A
11/02/15	FINAL CD	0

DEPT.	DATE	APP'D	REVISIONS
RFE			
RF MAN.			
ZONING			
OPS			
CONSTR.			
SITE AC.			

PROJECT NO: CT11410A
 DRAWN BY: PS
 CHECKED BY: KM




THIS DOCUMENT IS THE CREATION, DESIGN, PROPERTY AND COPYRIGHTED WORK OF T-MOBILE. ANY DUPLICATION OR USE WITHOUT EXPRESS WRITTEN CONSENT IS STRICTLY PROHIBITED.

SITE NAME
CT11410A
 SITE NAME
 STAMFORD / DWTN
 SITE ADDRESS
 555 E MAIN STREET
 STAMFORD, CT, 06901

SHEET TITLE
GROUNDING DIAGRAM AND POWER ONE LINE DIAGRAM

SHEET NUMBER
E-1




TRUNK FIBER NOTES:

1. IN GENERAL THIS CABLE WILL HANDLE SIMILARLY TO 3/8" COAXIAL CABLE, AND SIMILAR INSTALLATION TECHNIQUES APPLY. ALL CABLES ARE INDIVIDUALLY SERIALIZED, BE SURE TO WRITE DOWN THE CABLE SERIAL NUMBER FOR FUTURE REFERENCE.
2. THE TERMINATED FIBER ENDS (THE BROKEN OUT FIBERS PLUS CONNECTORS) HOWEVER ARE FRAGILE, AND THESE MUST BE PROTECTED DURING THE INSTALLATION PROCESS.
3. LEAVE THE PROTECTIVE TUBE AND SOCK AROUND THE FIBER TAILS AND CONNECTORS IN PLACE DURING HOISTING AND SECURING THE CABLE. REMOVE THIS ONLY JUST PRIOR TO MAKING THE FINAL CONNECTIONS TO THE OVP BOX.
4. DO NOT BEND THE FIBER ENDS (IN THE ORANGE FURCATION TUBES) TIGHTER THAN 3/4" (19MM) BEND RADIUS, ELSE THERE IS A RISK OF BREAKING THE GLASS FIBERS.
5. BE SURE THAT THE LACE UP ENDS AND FIBER CONNECTORS ARE NOT DAMAGED BY ATTACHMENT OF A HOISTING GRIP OR DURING THE HOISTING PROCESS. ATTACH A HOISTING GRIP ON THE JACKETED CABLE NO LESS THAN 6 INCHES BELOW THE FIBER BREAKOUT POINT. IF A HOISTING GRIP IS NOT EASILY ATTACHED, USE A SIMPLE LINE ATTACHED BELOW THE FIBER BREAK-OUT POINT (I.E. AT THE CABLE OUTER JACKET). PREVENT THE FIBER TAILS (IN PROTECTIVE TUBE) AT THE CABLE END FROM UNDUE MOVEMENT DURING HOISTING BY SECURING THE PROTECTIVE TUBE (WITH OUTER SOCK) TO THE HOISTING LINE.
6. DURING HOISTING ENSURE THAT THERE IS A FREE PATH AND THAT THE CABLE, AND ESPECIALLY THE FIBER ENDS, WILL NOT BE SNAGGED ON TOWER MEMBERS OR OTHER OBSTACLES.
7. INSTALLATION TEMPERATURE RANGE IS -22F TO 158F (-30C TO +70C).
8. MINIMUM CABLE BEND RADII ARE 22.2" (565MM) LOADED (WITH TENSION ON THE CABLE) AND 11.1" (280MM) UNLOADED.
9. MAXIMUM CABLE TENSILE LOAD IS 3560 N (800 LB) SHORT TERM (DURING INSTALLATION) AND 1070 N (240 LB) LONG TERM.
10. COMMSCOPE NON LACE UP GRIP RECOMMENDED FOR MONOPOLE INSTALLATIONS.
11. MAXIMUM HANGER SPACING 3FT (0.9 M).

HYBRID FIBER/POWER JUMPER NOTES:

1. IN GENERAL THIS CABLE WILL HANDLE SIMILARLY TO A 3/8" COAXIAL CABLE.
2. THE TERMINATED FIBER ENDS HOWEVER ARE FRAGILE AND MUST BE PROTECTED DURING INSTALLATION. LEAVE THE PACKAGING AROUND THE FIBER ENDS IN PLACE UNTIL READY TO CONNECT THE JUMPER BETWEEN OVP AND RRU OR BBU.
3. DO NOT BEND THE FIBER BREAKOUT CABLE (BETWEEN THE MAIN CABLE AND THE FIBER CONNECTOR) TIGHTER THAN 3/4" (19MM) RADIUS, ELSE THERE IS A RISK OF BREAKING THE GLASS.
4. ATTACH THE MAIN CABLE SECURELY TO THE STRUCTURE OR EQUIPMENT USING HANGERS AND/OR CABLE TIES TO PREVENT STRAIN ON CONNECTIONS FROM MOVEMENT IN WIND OR SNOW/ICE CONDITIONS.
5. ENSURE THE LC FIBER CONNECTORS ARE SEATED FIRMLY IN PANEL IN OVP OR IN EQUIPMENT.
6. INSTALLATION TEMPERATURE RANGE IS -22F TO 158F (-30C TO 70C).
7. MINIMUM CABLE BEND RADII ARE 10.3 INCH (265MM) LOADED (WITH TENSION ON THE CABLE) AND 5.2 INCH (130MM) UNLOADED.
8. MAXIMUM CABLE TENSILE LOAD IS 350 LB (1560N) SHORT TERM (DURING INSTALLATION) AND 105 LB (470N) LONG TERM.
9. STANDARD LENGTHS AVAILABLE ARE 6 FEET, 15 FEET AND 20 FEET

- NOTES:**
1. PROVIDE #2AWG GROUNDING CONDUCTOR, U.O.N.
 2. DO NOT INSTALL GROUND KIT AT BEND. DIRECT GROUND WIRE DOWN TO ANTENNA BUSSBAR.
 3. PROVIDE GROUNDING ELECTRODES IN QUANTITY, TYPE AND SIZE AS INDICATED ON SITE GROUNDING PLAN.
 4. ADD COAX GROUND KIT CONNECTION TO BUSSBAR WHEN LENGTH OF COAX RUN (FROM EQUIPMENT TO ANTENNA) IS GREATER THAN 20'-0".
 5. GROUND HCS BOX W/ #2AWG GROUNDING CONDUCTOR ATTACHED TO GOOD GROUND AS DIRECT AND SHORT AS POSSIBLE. USE GREEN STRANDED INSULATED CONDUCTOR TO CONNECT TO BUSSBAR/GROUND HALO OR BARE TINNED SOLID COPPER CONDUCTOR TO CONNECT TO GROUND RING.



702D CONFIGURATION COAX/FIBER PLUMBING DIAGRAM

SCALE: N.T.S

Exhibit E