



Together with Nextel

10 Industrial Ave, Suite 3  
Mahwah, NJ 07430  
Phone: (845)499-4712  
Jennifer Notaro  
Real Estate Consultant

October 14, 2014

**Hand Delivered**

Ms. Melanie A. Bachman  
Acting Executive Director  
Connecticut Siting Council  
10 Franklin Square  
New Britain, CT 06051

CC to Property Owner  
Long Ridge Fire Department  
366 Old Long Ridge Road  
Stamford, CT 06901

RE: Sprint Spectrum L.P. notice of intent to modify an existing telecommunications facility located at 366 Old Long Ridge Road Stamford, CT 06901 . Known to Sprint Spectrum L.P. as site CT03XC328.

Dear Ms. Bachman:

In order to accommodate technological changes, implement Code Division Multiple Access (“CDMA”) and/or Long Term Evolution (“LTE”) capabilities, and enhance system performance in the state of Connecticut, Sprint Spectrum L.P. plans to modify the equipment configurations at many of its existing cell sites. Please accept this letter and attachments as notification, pursuant to R.C.S.A. Section 16-50j-73, of construction which constitutes an exempt modification pursuant to R.C.S.A. Section 16-50j-72(b)(2). In compliance with R.C.S.A. Section 16-50j-73, a copy of this letter and its attachments is being sent to the chief elected official of the municipality in which affected cell site is located.

CDMA employs Spread-Spectrum technology and special coding scheme to allow multiple users to be multiplexed over the same physical channel.

LTE is a new high-performance air interface for cellular mobile communications. It is designed to increase the capacity and speed of mobile telephone networks.

Attached is a summary of the planned modifications, including power density calculations reflecting the change in Sprint's operations at the site. Also included is documentation of the structural sufficiency of the tower to accommodate the revised antenna configuration.

The changes to the facility do not constitute modification as defined Connecticut General Statutes ("C.G.S.") Section 16-50i(d) because the general physical characteristics of the facility will not be significantly changed or altered. Rather, the planned changes to the facility fall squarely within those activities explicitly provided for the R.C.S.A. Section 16-50j-72(b)(2).

1. The height of the overall structure will not be affected.
2. The proposed changes will not extend the site boundaries. There will be no effect on the site compound.
3. The proposed changes will not increase the noise level at the existing facility by 6 decibels or more.
4. Radio Frequency power density may increase due to the use of one or more CDMA transmissions. Moreover, LTE will utilize additional radio frequencies newly licensed by the FCC for cellular mobile communications. However, the changes will not increase the calculated "worst case" power density for the combined operations at the site to a level at or above the applicable standard for uncontrolled environments as calculated for a mixed frequency site.

For the foregoing reasons Sprint Spectrum L.P. respectfully submits that the proposed changes at the referenced site constitute exempt modifications under R.C.S.A. Section 16-50j-72(b)(2).

Please feel free to call me at (201)-704-8157 or email [JArdis@transcendwireless.com](mailto:JArdis@transcendwireless.com) with questions concerning this matter.  
Thank you for your consideration.

Sincerely,

Jennifer Ardis  
Real Estate Consultant

RADIO FREQUENCY FCC REGULATORY COMPLIANCE  
MAXIMUM PERMISSIBLE EXPOSURE (MPE) ASSESSMENT

Sprint Existing Facility

Site ID: CT03XC328

Stamford Fire Department

366 Old Long Ridge Road  
Stamford, CT 06903

**October 14, 2014**

**EBI Project Number: 62145487**

October 14, 2014

Sprint  
Attn: RF Engineering Manager  
1 International Boulevard, Suite 800  
Mahwah, NJ 07495

Re: Radio Frequency Maximum Permissible Exposure (MPE) Assessment for Site:  
**CT03XC328 - Stamford Fire Department**

**Site Total: 40.09% - MPE% in full compliance**

EBI Consulting was directed to analyze the proposed upgrades to the existing Sprint facility located at **366 Old Long Ridge Road, Stamford, CT**, for the purpose of determining whether the radio frequency (RF) exposure levels from the proposed Sprint equipment upgrades on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter ( $\mu\text{W}/\text{cm}^2$ ). The number of  $\mu\text{W}/\text{cm}^2$  calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits, therefore it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) – (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general public may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general public would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

Public exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter ( $\mu\text{W}/\text{cm}^2$ ). The general population exposure limit for the cellular band (850 MHz Band) is approximately  $567 \mu\text{W}/\text{cm}^2$ , and the general population exposure limit for the 1900 MHz and 2500 MHz bands is  $1000 \mu\text{W}/\text{cm}^2$ . Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.

Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure. Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

## **CALCULATIONS**

Calculations were done for the proposed upgrades to the existing Sprint Wireless antenna facility located at **366 Old Long Ridge Road, Stamford, CT**, using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. All calculations were performed assuming a lobe representing the maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was focused at the base of the tower. For this report the sample point is the top of a 6 foot person standing at the base of the tower.

For all calculations, all emissions were calculated using the following assumptions:

- 1) 4 channels in the 1900 MHz Band were considered for each sector of the proposed installation.
- 2) 1 channel in the 800 MHz Band was considered for each sector of the proposed installation.
- 3) 2 channels in the 2500 MHz Band were considered for each sector of the proposed installation.
- 4) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 - Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.
- 5) For the following calculations the sample point was the top of a six foot person standing at the base of the tower. The maximum gain of the antenna per the antenna manufactures supplied specifications minus 10 dB was used in this direction. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.

- 6) The antennas used in this modeling are the RFS APXVSPP18-C-A20 and the RFS APXVTM14-C-I20. This is based on feedback from the carrier with regards to anticipated antenna selection. The RFS APXVSPP18-C-A20 has a 15.9 dBd gain value at its main lobe at 1900 MHz and 13.4 dBd at its main lobe for 850 MHz. The RFS APXVTM14-C-I20 has a 15.9 dBd gain value at its main lobe at 2500 MHz. The maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was used for all calculations. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 7) The antenna mounting height centerline for the proposed antennas is **128 feet** above ground level (AGL).
- 8) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.

All calculation were done with respect to uncontrolled / general public threshold limits

Site ID	CT03XC328 - Stamford Fire Department
Site Address	366 Old Long Ridge Road, Stamford, CT, 06903
Site Type	Self Support Tower

**Sector 1**

Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain (10 db reduction)	Antenna Height (ft)	analysis height	Cable Size	Cable Loss (dB)	Additional Loss (dB)	ERP	Power Density Percentage
1a	RFS	APXVSP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	4	80	5.9	128	122	1/2 "	0.5	0	277.39	0.67%
1a	RFS	APXVSP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	3.4	128	122	1/2 "	0.5	0	39.00	0.17%
1B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	5.9	128	122	1/2 "	0.5	0	138.69	0.59%
Sector total Power Density Value:																1.43%

**Sector 2**

Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain (10 db reduction)	Antenna Height (ft)	analysis height	Cable Size	Cable Loss (dB)	Additional Loss (dB)	ERP	Power Density Percentage
2a	RFS	APXVSP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	4	80	5.9	128	122	1/2 "	0.5	0	277.39	0.67%
2a	RFS	APXVSP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	3.4	128	122	1/2 "	0.5	0	39.00	0.17%
2B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	5.9	128	122	1/2 "	0.5	0	138.69	0.59%
Sector total Power Density Value:																1.43%

**Sector 3**

Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain (10 db reduction)	Antenna Height (ft)	analysis height	Cable Size	Cable Loss (dB)	Additional Loss (dB)	ERP	Power Density Percentage
3a	RFS	APXVSP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	4	80	5.9	128	122	1/2 "	0.5	0	277.39	0.67%
3a	RFS	APXVSP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	3.4	128	122	1/2 "	0.5	0	39.00	0.17%
3B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	5.9	128	122	1/2 "	0.5	0	138.69	0.59%
Sector total Power Density Value:																1.43%

Site Composite MPE %	
Carrier	MPE %
Sprint	4.28%
Nextel	4.03%
AT&T	14.91%
T-Mobile	7.32%
EMCC	Per field measurement baseline for these antennas listed in CSC database
City of Stamford	
AirTouch	
SkyTel	
Fire Dept.	
Gardella Trans.	
Hoffman Fuel	
Pronet	
<b>Total Site MPE %</b>	<b>40.09%</b>

## Summary

All calculations performed for this analysis yielded results that were well within the allowable limits for general public Maximum Permissible Exposure (MPE) to radio frequency energy.

The anticipated Maximum Composite contributions from the Sprint facility are **4.28%** (**1.43% from sector 1, 1.43% from sector 2 and 1.43% from sector 3**) of the allowable FCC established general public limit considering all three sectors simultaneously sampled at the ground level.

The anticipated composite MPE value for this site assuming all carriers present is **40.09%** of the allowable FCC established general public limit sampled at 6 feet above ground level. This total composite site value is based upon MPE values listed in the Connecticut Siting Council database for existing carrier emissions.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.



**Scott Heffernan**  
RF Engineering Director

**EBI Consulting**  
21 B Street  
Burlington, MA 01803



---

# DETAILED STRUCTURAL ANALYSIS AND EVALUATION OF AN EXISTING 152' SELF SUPPORTING LATTICE TOWER FOR PROPOSED ANTENNA ARRANGEMENTS

Site I.D:     (Verizon)     Stamford NW  
              (AT&T)        CT5047  
              (Sprint)      CT03XC328

Address:     366 Old Long Ridge Road  
              Stamford, CT

---

*prepared for*



Verizon Wireless  
99 East River Drive  
East Hartford, Connecticut 06108



500 ENTERPRISE DRIVE, SUITE 3A  
ROCKY HILL, CT. 06067



1 International Blvd.  
Suite 800  
Mahwah, NJ. 07495

*prepared by*



URS CORPORATION  
500 ENTERPRISE DRIVE, SUITE 3B  
ROCKY HILL, CT 06067  
TEL. 860-529-8882  
(Sprint) 36928702.00000  
(Verizon) 36922268.00000  
(AT&T) 36922483.00000

July 15, 2014

## TABLE OF CONTENTS

1. EXECUTIVE SUMMARY
2. INTRODUCTION
3. ANALYSIS METHODOLOGY AND LOADING CONDITIONS
4. FINDINGS AND EVALUATION
5. CONCLUSIONS
6. DRAWINGS AND DATA
  - TOWER AND FOUNDATION REINFORCED DRAWINGS
    - (FROM URS CORPORATION MODIFICATION DESIGN/PASSING ANALYSIS DATED 6/13/2013)
  - TNX TOWER INPUT / OUTPUT SUMMARY
  - TNX TOWER FEEDLINE DISTRIBUTION CHART
  - TNX TOWER FEEDLINE PLAN
  - TNX TOWER DETAILED OUTPUT
  - ANCHOR BOLT EVALUATION
  - FOUNDATION EVALUATION

## 1. EXECUTIVE SUMMARY

This report summarizes the structural re-analysis of the modified existing 152' self-supporting lattice tower located at 366 Old Long Ridge Road, in Stamford, CT. The analysis was conducted in accordance with the 2005 Connecticut State Building Code and the TIA/EIA-222-F standard for a basic wind velocity of 85 mph (fastest mile) and 74 mph (fastest mile) concurrent with 0.50" ice. The antenna loading considered in the analysis consists of all existing and proposed antennas, transmission lines, and ancillary items as outlined in the Introduction Section of this report.

The proposed antenna modifications are as follows:

Proposed Antenna and Mount	Carrier	Antenna Center Elevation
<b>Remove:</b> (12) Decibel DB844H90E-XY Panel Antennas (3) T-Frame Mounts (12) 1 1/4 Coaxial Cable  (6) Amphenol LPA-80063-4CF Panel Antennas (3) Amphenol BXA-171063-8BF-EDIN-2 Panel Antennas (3) Amphenol BXA 171063-12CF-EDIN-2 Panel Antennas (3) Amphenol BXA-70063-6CF-2 Panel Antennas (18) 1 5/8" Coaxial Cables	Nextel (Existing)	118'
<b>Install</b> (3) RFS APXVSP18-C-A20 Panel Antennas (3) 800 MHz RRH Units (3) 1900 MHz RRH Units (3) Hybriflex Cables  (3) RFS APXV9TM14 Panel Antennas (3) RRH Units (1) Fiber Optic Cable (27) 8' Jumper Cables	Sprint (Previously Proposed)	128'
(2) Decibel LNX-8513DS-A1M Panel Antennas (Alpha Sector) (4) Decibel LNX-6514DS-A1M Panel Antennas (Beta and Gamma Sector) (6) RRH Units (6) HBXX-6517DS-A2M Panel Antennas (1) Raycap DB-T1-6Z-8AB-0Z Distribution Box	Sprint (Proposed)	128'
	Verizon (Proposed)	98'

The results of the analysis indicate that the proposed modified tower structure and the proposed modified foundation components are in compliance with the proposed loadings. The proposed modified tower structure and proposed modified foundation components are considered structurally adequate with the wind classification specified above and all the existing and proposed antenna loading.

## 1. EXECUTIVE SUMMARY - *continued*

The analysis results presented herewith are based upon the previous tower modification proposed by URS Corporations' tower modification analysis report, project 36922268, signed and sealed on June 13, 2013. No installation of proposed antennas, mounts, cables or accessories shall occur prior to the completion of the tower and foundation modifications specified in the June 13, 2013 report. A copy of the reinforced drawings are included with this report.

This analysis is based on:

- 1) The tower structure's theoretical capacity, not including any assessment of the condition of the tower.
- 2) Original tower geometry, structural member sizes and foundation information obtained from manufacturer's design documents prepared by ROHN Industries, Engineering File No. 24269DB, dated May 16, 1989.
- 3) Subsurface Investigation Report from Goldberg-Zoino & Associates Inc., dated December 14, 1988.
- 4) Completion of subsequent tower reinforcements:
  - Drawings SS-1 'Tower Foundation Reinforcement, Elevation, Sections and Details' and drawing SS-2 'Foundation Plan, Section and Notes' prepared by Tectonic Engineering Consultants P.C; on behalf of AT&T Wireless, PCS, LLC; dated April 23, 2002.
  - Drawing S-1 'Structural Details' prepared by Diversified Technology Consultants (dte), on behalf of Nextel Communications, dated June 11, 2002.
  - Tower reinforcement drawings sheets 1 thru 5, entitled '2007 Modifications Tower Rework For a 153' ROHN SSV Tower' Long Ridge, CT., prepared by Vertical Structures on behalf of Motorola, dated May 24, 2007.
  - Tower inventory and mapping report prepared by CSB Communications, Inc., on behalf of Verizon Wireless/URS Corporation, dated July 20, 2008.
- 5) Geotechnical report from Dr. Clarence Welti, P.E., Geotechnical Engineering, dated December 12, 2012.
- 6) Modification design/passing analysis performed by URS for Sprint, Verizon, and AT&T, dated June 13, 2013.
- 7) Verizon RFDS, dated May 5, 2014
- 8) Sprint flat file for proposed antenna inventory, obtained via e-mail dated July 11, 2014.
- 9) Antenna and mount configuration as specified within Section 2 and 6 of this report.
- 10) Coax cable orientation as specified in section 6 of this report.


1. EXECUTIVE SUMMARY - *continued*

This report is only valid as per the assumptions and data utilized in this report for antenna inventory, mounts and associated cables. The user of this report shall field verify the assumption of the antenna and mount configuration as well as the physical condition of the tower. Notify the engineer in writing immediately if any of the information in this report is found to be other than specified.

If you should have any questions, please call.

Sincerely,

**URS Corporation**



Richard A. Sambor, P.E.  
Senior Structural Engineer

RAS/mcd

cc: ICA – URS  
CF/Book



## 2. INTRODUCTION

The subject tower is located at 366 Old Long Ridge Road, in Stamford, CT. The structure is an existing 152' self supporting three-legged steel tapered lattice tower designed and manufactured by ROHN.

The inventory is summarized in the table below:

<b>Antenna Type</b>	<b>Carrier</b>	<b>Mount</b>	<b>Antenna Centerline Elevation</b>	<b>Cable</b>
(1) 20' 4-Bay Dipole	(existing)	12' Pipe Mount	162'	(1) 7/8"
(1) Decibel DB563K Directional Omni with 22"x22"x6" Filter Box	(existing)	3' Stand-off	156.70'	(2) 1-5/8"
(1) 4' HP Dish with Radome	(existing)	4" Dish Mount	152'	(1) 7/8" Elliptical
(1) 30"x3" Omni Whip with 20"x6"x8" Filter Box	(existing)	3' Stand-off	151.25'	(2) 1-1/4"
(1) 12'x3" Decibel Omni Whip	(existing)	4' Stand-off	144'	(1) 7/8"
(3) Powerwave 7770 panel antennas and (6) Powerwave LGP21401 TMA's	AT&T (existing)	Pipe Leg Mount	143'	(6) 1 5/8"
<b>(3) Powerwave P65-16-XLH-RR Antennas (6) Ericsson RRUS-11 RRU's (1) Raycap DC6-48-60-0-1B Surge Arrestor</b>	<b>AT&amp;T (Proposed)</b>	<b>(3) Valmont CWT01 Mounts</b>	<b>145'</b>	<b>3" Flex Conduit (3) 1 5/8"</b>
(1) Decibel DB563K Directional Omni	(existing)	3' Stand-off	141.70'	(1) 1-1/4"
(1) 4' HP Dish with Radome	(existing)	4" Dish Mount	140'	(1) 7/8" Elliptical
(1) 6'x3" Decibel Omni Whip	(existing)	3' Stand-off	138'	(2) 1-5/8"
(1) 2' HP Dish with Radome	(existing)	4" Dish Mount	136.5'	(1) 7/8" Elliptical
(1) Decibel DB495 Corner Reflector	(existing)	Leg Mount	135'	(1) 1/2"
(1) 8'x2" Decibel Omni Whip	(existing)	off Boom Gate listed above	133'	(1) 7/8"
<b>(3) RFS APXV9TM14 Pane Antennas (3) RRH Units</b>	<b>Sprint (Proposed)</b>	<i>See Below Mount</i>	<b>128'</b>	<b>(1) Fiber Optic Cable (27) 8' Jumper Cables</b>
<b>(3) RFS APXVSP18-C-A20 (3) 800 MHz RRH's (3) 1900 MHz RRH's</b>	<b>Sprint (Previously Proposed)</b>	(3) 11' Boom Gates	<b>128'</b>	<b>(3) Hybriflex Cables</b>
(1) Decibel DB254 Corner Reflector	(existing)	Leg Mount	122'	(1) 1/2"
(3) RFS APX16DWV-S-E-ACU Panel Antennas (3) TMAs	T-Mobile (existing)	Leg Mount	108'	(12) 1-5/8" (2 rows of 6)
(1) 10'x2" Decibel Omni Whip	(existing)	3' Stand-off	101'	(1) 7/8"
(1) 8' 4-Bay Dipole	(existing)	3' Stand-off	101'	(1) 7/8"
(1) 8' 4-Bay Dipole	(existing)	3' Stand-off	101'	(1) 7/8"
(1) 20'x3" Omni Whip	(existing)	3' Stand-off	101'	(1) 7/8"

<b>Antenna Type</b>	<b>Carrier</b>	<b>Mount</b>	<b>Antenna Centerline Elevation</b>	<b>Cable</b>
(2) Decibel LNX-8513DS-A1M Panel Antennas (Alpha Sector) (4) Decibel LNX-6514DS-A1M Panel Antennas (Beta and Gamma Sector) (6) RRH Units (6) HBXX-6517DS-A2M Panel Antennas (1) Raycap DB-T1-6Z-8AB-0Z Distribution Box	Verizon (Proposed)	See Below Mount	98'	(1) 1 1/4" Hybrid Cable
(3) ALU RRH's (1) Raycap DB-T1-6Z-8AB-0Z Distribution Box	Verizon (Previously Proposed)	(3) 13' T-frames	98'	(1) 1 1/4" Hybrid Cable
(1) 4'x3" Omni Whip	(existing)	3' Stand-off	79'	(1) 1-1/4"
(1) 8' 2-Bay Dipole	(existing)	3' Stand-off	78'	(1) 7/8"
(1) 3' Kathrein Yagi with Radome	(existing)	same as listed above	72'	(1) 1/2"
(1) GPS antenna	Sprint (existing)	2' Stand-off	58'	(1) 1/2"
(1) 1.2M Dish	(existing)	4' Stand-off	45'	(1) 1/4"

Notes:

- 1) Omni-whip antenna centerline elevations based on antenna size and respective mount height.
- 2) Refer to Section 6 Tower Feed Line Plan for coaxial cable locations.

This structural re-analysis of the communications tower modification design was performed by URS Corporation (URS) for Verizon and Sprint. The purpose of this analysis was to investigate the structural integrity of the modified tower and reinforced foundation with its existing and proposed antenna loads. The analysis was conducted to evaluate stress on the modified tower and the effect of forces to the modified foundation of the tower resulting from existing and proposed antenna arrangements.

The analysis results presented herewith are based upon previous tower modification proposed by URS Corporations' tower modification analysis report, project 36922268, signed and sealed on June 13, 2013.

### 3. ANALYSIS METHODOLOGY AND LOADING CONDITIONS

The structural analysis was done in accordance with the 2005 Connecticut State Building Code, TIA/EIA-222-F - Structural Standard for Steel Antenna Towers and Antenna Supporting Structures, and the American Institute of Steel Construction (AISC) Manual of Steel Construction – Allowable Stress Design (ASD).

The analysis was conducted using TNX Tower 6.1.3.1. Two load conditions were evaluated as shown below which were compared to allowable stresses according to AISC and TIA/EIA.

#### Basic Wind Speed:

- Fairfield County;  $v = 85$ mph (fastest mile) [Section 16 of TIA/EIA-222-F-1996]
- Stamford;  $v = 105$ mph (3 second gust) [Appendix K, 2005 Connecticut State Building Code Supplement]  
equivalent to 85mph (fastest mile)

#### Loading Cases:

Load Condition 1 = 85 mph (fastest mile) Wind Load (without ice) + Tower Dead Load

Load Condition 2 = 74 mph (fastest mile) Wind Load (with ice) + Ice Load + Tower Dead Load

Please note that wind pressure is a function of velocity squared. Under Load Condition 2, a 25 percent reduction in wind pressure is allowed by code to account for the unlikelihood of the full wind pressure and ice load occurring at the same time. The same results may be achieved by utilizing a lower wind pressure without taking the 25 percent reduction, as shown above.

The TIA/EIA standard permits a one-third increase in allowable stresses for towers and monopoles less than 700 feet tall. For the purposes of this analysis, in computing the load capacity the allowable stresses of the tower members were increased by one-third.



#### 4. FINDINGS AND EVALUATION

Stresses on the modified tower structure were evaluated to compare with the allowable stress in accordance with AISC. The results of the analysis indicate that the calculated stresses under the proposed loading are **BELOW** the allowable stresses (see tables below). The modified tower foundation has sufficient capacity to resist the proposed uplift forces. The tower anchor bolts were found to be within the allowable limits.

**TABLE 1: Tower Base Reactions:**

For detailed proposed tower reactions, see drawing no. E-1 in section 6 of this report.

Base Reactions	Proposed Reactions
Axial Load (kips)	31
Shear per Leg (kips)	23
Total Shear (kips)	43
Uplift per Leg (kips)	189
Comp. per Leg (kips)	220
O.T. Moment (ft-kips)	3784

**TABLE 2: Tower Component Stress vs. Capacity Summary:**

Component/ (Section No.)	Existing Component Size	Controlling Component/Elevation	Stress (% capacity)	Pass/Fail
Tower Leg (T15)	ROHN 5 X-STR w/ (3) 1.5"x0.5" Bars	Compression / 15'-20'	92.4 %	Pass
Diagonal (T15)	L3 1/2x3 1/2x1/4	Compression / 15'-20'	97.7 %	Pass
Horizontal (T16)	L2 7/8x2 7/8x1/4	Compression/10'-15'	77.4 %	Pass
Secondary Horizontal (T13)	L3x3x3/16	Compression/30'-40'	88.4 %	Pass
Top Girt (T1)	L2x2x1/8	Compression/140'-152'	10.0 %	Pass
Red. Horiz. Bracing (T15)	L2x2x1/4	Compression/15'-20'	34.9 %	Pass
Red. Diag. Bracing (T15)	L2x2x1/4	Compression/15'-20'	26.8 %	Pass
<b>Bolt Checks</b>				
Diagonal (T10)	0.500" dia A325X	Bolt Shear / 60'-67'	97.7 %	Pass
Anchor Bolts	(4) 1" dia A193 GR-7, A320 GR L7	Min Area per ASCE 10-97	96 %	Pass

**TABLE 3: Foundation Summary**

Foundation	Component	(% capacity/FOS)	Pass/Fail	Comments:
Drilled Concrete Caisson with Concrete Block Reinforcement & Grouted Rock Anchor	Uplift	92.3 % / 2.17	Pass	Min. F.O.S of 2.0 req'd per IBC 2003 Section 3108.4.2

## 5. CONCLUSIONS AND RECOMMENDATIONS

The results of the analysis indicate that the proposed modified tower structure and the proposed modified foundation components are in compliance with the proposed loadings. The proposed modified tower structure and proposed modified foundation components are considered structurally adequate with the wind classification specified above and all the existing and proposed antenna loading.

The analysis results presented herewith are based upon the previous tower modification proposed by URS Corporations' tower modification analysis report, project 36922268, signed and sealed on June 13, 2013. No installation of proposed antennas, mounts, cables of accessories shall occur prior to the completion of the tower and foundation modifications specified in the June 13, 2013 report. A copy of the reinforced drawings are included with this report.

### **Limitations/Assumptions:**

This report is based on the following:

- 1) Tower inventory as listed in this report.
- 2) Tower is properly installed and maintained.
- 3) All members are as specified in the original design documents and are in good condition.
- 4) All required members are in place.
- 5) All bolts are in place and are properly tightened.
- 6) Tower is in plumb condition.
- 7) All member protective coatings are in good condition.
- 8) All tower members were properly designed, detailed, fabricated, and installed and have been properly maintained since erection.
- 9) Foundations were properly constructed to support original design loads as specified in the original design documents.
- 10) All coaxial cable is installed as specified in Section 6 of this report

URS is not responsible for any modifications completed prior to or hereafter in which URS is not or was not directly involved. Modifications include but are not limited to:

- A. Adding antennas
- B. Removing/replacing antennas
- C. Adding coaxial cables

URS hereby states that this document represents the entire report and that it assumes no liability for any factual changes that may occur after the date of this report. All representations, recommendations, and conclusions are based upon information contained and set forth herein. If you are aware of any information which conflicts with that which is contained herein, or you are aware of any defects arising from original design, material, fabrication, or erection deficiencies, you should disregard this report and immediately contact URS. URS disclaims all liability for any representation, recommendation, or conclusion not expressly stated herein.

### **Ongoing and Periodic Inspection and Maintenance:**

The owner shall refer to TIA/EIA-222-F for recommendations for maintenance and inspection. The frequency of the inspection and maintenance intervals is to be determined by the owner based upon actual site and environmental conditions. It is recommended that a complete and thorough inspection of the entire tower structural system be performed at least yearly and more frequently as conditions warrant. According to TIA/EIA-222-F section 14.1, Note 1; it is recommended that the structure be inspected after severe wind and/or ice storms or other extreme loading conditions.

## 6. DRAWINGS AND DATA

(Sprint) 36928702.00000  
(Verizon) 36922268.00000  
(AT&T) 36922483.00000

152' SSV Lattice Tower  
Stamford, CT


7/15/2014

# TOWER AND FOUNDATION REINFORCEMENT DRAWINGS

(Sprint) 36928702.00000  
(Verizon) 36922268.00000  
(AT&T) 36922483.00000

152' SSV Lattice Tower  
Stamford, CT

7/15/2014



1 **SITE PLAN**  
 SK-1 SCALE: 1"=50'-0"

PROJECT NO.  
 36922268  
 Designed by:  
 MCD  
 Drawn by:  
 MCD  
 Checked by:  
 KB  
 Approved by:  
 ICA

**URS CORPORATION AES**  
 500 ENTERPRISE DRIVE  
 ROCKY HILL, CONNECTICUT  
 860-529-8882

**SITE PLAN**  
**STAMFORD FIRE DEPARTMENT TOWER**  
 SITE ADDRESS: 366 OLD LONG RIDGE ROAD  
 STAMFORD, CT

1	7/16/14	RE-ISSUE/NO CHANGE
REV.	DATE:	DESCRIPTION
Scale: AS NOTED		Date: 06/13/13
Job No. VZ5-110	File No.	

Dwg. No.  
**SK-1**  
 Dwg. 1 of 6

**STRUCTURAL NOTES**

**SOIL**

1. SOIL BEARING CAPACITY OF 5,000 PSF USED FOR FOUNDATION DESIGN. GENERAL CONTRACTOR RESPONSIBLE FOR VERIFYING BEARING CAPACITIES.
2. ALL SURFACES MUST BE FREE OF STANDING WATER PRIOR TO PLACING
3. COMPACTED GRAVEL FILL PER CONNECTICUT DOT STANDARD SPEC. SECTION M.02.01 AND ASTM D1557.
4. CONTACT THE ENGINEER IF GROUND WATER IS IN ENCOUNTERED AND DEWATERING IS REQUIRED.

**CONCRETE**

1. ALL CONCRETE WORK SHALL BE IN ACCORDANCE WITH THE ACI 301, ACI 318 AND THE SPECIFICATION CAST-IN-PLACE CONCRETE.
2. ALL CONCRETE SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH OF 3000 PSI AT 28 DAYS, UNLESS NOTED OTHERWISE. CONCRETE SHALL BE AIR ENTRAINED TO (4% TO 6%) AND SLUMP OF 3" TO 5".
3. REINFORCING STEEL SHALL CONFORM TO ASTM A 615, GRADE 60, DEFORMED UNLESS NOTED OTHERWISE. WELDED WIRE FABRIC SHALL CONFORM TO ASTM A 185 WELDED STEEL WIRE FABRIC UNLESS NOTED OTHERWISE. SPLICES SHALL BE CLASS "B" AND ALL HOOKS SHALL BE STANDARD, UNO.
4. THE FOLLOWING MINIMUM CONCRETE COVER SHALL BE PROVIDED FOR REINFORCING STEEL UNLESS SHOWN OTHERWISE ON DRAWINGS:
  - CONCRETE CAST AGAINST EARTH.....3 IN.
  - CONCRETE EXPOSED TO EARTH OR WEATHER:
    - #6 AND LARGER .....2 IN.
    - #5 AND SMALLER & WWF .....1 1/2 IN.
  - CONCRETE NOT EXPOSED TO EARTH OR WEATHER OR NOT CAST AGAINST THE GROUND:
    - SLAB AND WALL .....3/4 IN.
    - BEAMS AND COLUMNS .....1 1/2 IN.
5. A CHAMFER 3/4" SHALL BE PROVIDED AT ALL EXPOSED EDGES OF CONCRETE, UNO, IN ACCORDANCE WITH ACI 301 SECTION 4.2.4.
6. INSTALLATION OF CONCRETE EXPANSION/WEDGE ANCHOR, SHALL BE PER MANUFACTURER'S WRITTEN RECOMMENDED PROCEDURE. THE ANCHOR BOLT, DOWEL OR ROD SHALL CONFORM TO MANUFACTURER'S RECOMMENDATION FOR EMBEDMENT DEPTH OR AS SHOWN ON THE DRAWINGS. NO REBAR SHALL BE CUT WITHOUT PRIOR ENGINEERING APPROVAL WHEN DRILLING
7. COLD WEATHER CONCRETE PLACING SHALL BE IN ACCORDANCE WITH ACI-306.
8. NO FOOTING SHALL BE PLACED ON FROZEN GROUND. UNCURED CONCRETE SHALL BE PROTECTED AGAINST FROST.
9. APPLY NON-SLIP BROOM FINISH IMMEDIATELY AFTER TROWEL FINISHING.

**FOUNDATION NOTES**

1. A SOIL BEARING CAPACITY OF 5000 PSF WAS USED FOR THE FOUNDATION DESIGN. THE GENERAL CONTRACTOR IS TO CONFIRM THE EXISTING SOIL BEARING PRESSURE.
2. ALL FOOTINGS SHALL BEAR ON EXISTING UNDISTURBED ORGANIC FREE SOIL. ALL UNSUITABLE SOIL SHALL BE REMOVED AS DIRECTED BY THE ENGINEER AND REPLACED WITH COMPACTED GRAVEL PLACED IN 8" LAYERS AND COMPACTED TO 95% OF MODIFIED OPTIMUM DENSITY.
3. ALL FOOTINGS TO BE A MINIMUM OF 3'-6" BELOW FINISH GRADE UNLESS OTHERWISE NOTED. EXCEPT WHERE ROCK OR LEDGE OCCURS, PIN FOUNDATION TO ROCK.
4. INSTALLATION OF CONCRETE EXPANSION/WEDGE ANCHOR, SHALL BE PER MANUFACTURER'S WRITTEN RECOMMENDED PROCEDURE. THE ANCHOR BOLT, DOWEL OR ROD SHALL CONFORM TO MANUFACTURER'S RECOMMENDATION FOR EMBEDMENT DEPTH OR AS SHOWN ON THE DRAWINGS. NO REBAR SHALL BE CUT WITHOUT PRIOR ENGINEERING APPROVAL WHEN DRILLING HOLES IN CONCRETE.

**STRUCTURAL STEEL MATERIAL:**

STRUCTURAL STEEL BEAMS, CHANNELS, PLATES & ANGLES..... ASTM A572 GRADE 50  
 PIPE COLUMN..... ASTM A53 GRADE B  
 STUB COLUMNS..... FY=46 KSI..... ASTM A500  
 BOLTS..... ASTM A325-N  
 STRUCTURAL STEEL SHALL CONFORM TO ALL REQUIREMENTS OF THE 1999 AISC-LRFD SPECIFICATION, AS REFERENCED IN THE CODE.

UNLESS OTHERWISE NOTED, ALL STEEL WILL BE GALVANIZED IN ACCORDANCE WITH ASTM 123 AFTER FABRICATION. TOUCH UP ALL DAMAGED GALVANIZED STEEL WITH APPROVED COLD ZINC, "GALVANOX", "DRY GALV", "ZINC-IT", OR APPROVED EQUIVALENT, IN ACCORDANCE WITH MANUFACTURERS GUIDELINES. TOUCH-UP DAMAGED NON GALVANIZED STEEL WITH SAME PAINT APPLIED IN SHOP OR FIELD.

SHOP AND ERECTION DRAWINGS SHALL BE SUBMITTED FOR ALL STRUCTURAL STEEL WORK IN ACCORDANCE WITH THE CONTRACT DOCUMENTS. SUBMIT 2 SETS OF PRINTS FOR THE ENGINEER REVIEW.

EXISTING DIMENSIONS OF STRUCTURE SHOWN ON THESE DOCUMENTS ARE NOT GUARANTEED. CONTRACTOR SHALL TAKE FIELD DIMENSIONS AS NECESSARY TO ASSURE PROPER FIT OF ALL FINISHED WORK AND SHALL ASSUME FULL RESPONSIBILITY FOR THEIR ACCURACY. WHEN SHOP DRAWINGS BASED ON FIELD MEASUREMENT ARE SUBMITTED FOR REVIEW, DIMENSIONS ARE PROVIDED FOR THE ENGINEER'S REFERENCE ONLY.

CONNECTION ANGLES SHALL HAVE A MINIMUM THICKNESS OF 5/16" AND MINIMUM OF (2) 3/4" BOLTS.

ALL BOLT HOLES WILL BE DRILLED OR PUNCHED, WITH BURRS REMOVED PRIOR TO COATING.

MILL BEARING ENDS OF COLUMNS, STIFFENERS, AND OTHER BEARING SURFACES TO TRANSFER LOAD OVER ENTIRE CROSS SECTION.

THE OMISSION OF ANY MATERIAL THAT WAS SHOWN ON THE CONTRACT DRAWINGS SHALL NOT RELIEVE THE CONTRACTOR OF PROVIDING THE SAME.

ALL WELDING SHALL BE DONE BY A CERTIFIED WELDER IN ACCORDANCE WITH AWS STANDARDS, USING E70XX ELECTRODES UNLESS OTHERWISE NOTED. WHERE WELD SIZES ARE NOT SHOWN, PROVIDE THE MINIMUM SIZES PER "PREQUALIFIED WELDED JOINTS" TABLES IN AISC "MANUAL OF STEEL CONSTRUCTION", NINTH EDITION.

**CONNECTIONS / FIELD ASSEMBLY:**

BOLTED CONNECTIONS: UNLESS OTHERWISE NOTED, ALL JOINTS ARE BEARING TYPE, REQUIRING 3/4" DIA. A325-N BOLTS, A563 NUTS AND F436 WASHERS, ALL GALVANIZED. BEVELED WASHERS SHALL BE USED ON BEAM FLANGES HAVING A SLOPE GREATER THAN 1:20.

NON-STRUCTURAL CONNECTIONS, SUCH AS FOR STEEL GRATING, MAY USE 5/8" DIA. GALVANIZED ASTM A307 BOLTS, UNLESS OTHERWISE NOTED.

STRUCTURE IS DESIGNED TO BE LEVEL AND PLUMB, SELF-SUPPORTING AND STABLE AFTER WORK IS COMPLETED.

COMMENCEMENT OF STRUCTURAL STEEL WORK WITHOUT NOTIFYING THE ENGINEER OF ANY DISCREPANCIES WILL BE CONSIDERED ACCEPTANCE OF PRECEDING WORK.

IF WELDING GALVANIZED MATERIALS, USE PRECAUTIONS & PROCEDURES PER AWS D1.1.

**INSPECTIONS:**

SPECIAL INSPECTIONS REQUIRED PER THE 2005 CONNECTICUT STATE BUILDING CODE FOR STRUCTURAL STEEL WORK.

OWNER WILL SUPPLY THE SERVICES OF A SPECIAL INSPECTOR AND TESTING AGENTS AS REQUIRED. CONTRACTOR SHALL COORDINATE INSPECTIONS OF FABRICATOR'S AND ERECTOR'S WORK AND MATERIALS TO MEET THE REQUIREMENTS OF THE STATEMENT OF SPECIAL INSPECTIONS FOR THIS PROJECT.

COPIES OF TESTING AND INSPECTION REPORTS WILL BE PROVIDED TO THE OWNER, BUILDING OFFICIAL, ENGINEER OF RECORD AND CONTRACTOR.

**FOUNDATION WORK / REPLACEMENT OF TOWER MEMBERS AND BOLTS**

THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE STRUCTURAL INTEGRITY OF THE TOWER WHILE MEMBERS ARE REPLACED.

ONLY ONE MEMBER PER TOWER FACE SHALL BE REPLACED AT A TIME.

THE CONTRACTOR SHALL PREPARE AND MINIMIZE THE TIME THAT MEMBERS ARE NOT CONNECTED TO THE TOWER.

ALL MEMBERS SHALL BE LEFT FULLY CONNECTED AT THE END OF THE WORK DAY.

THE CONTRACTOR SHALL BE AWARE OF WEATHER AND WIND CONDITIONS AND NOT PERFORM REPLACEMENT IN A WIND.

PROJECT NO.  
36922268  
Designed by:  
MCD  
Drawn by:  
MCD  
Checked by:  
KB  
Approved by:  
ICA

**URS CORPORATION AES**  
500 ENTERPRISE DRIVE  
ROCKY HILL, CONNECTICUT  
860-529-8882

**GENERAL NOTES**


**STAMFORD FIRE DEPARTMENT TOWER**  
SITE ADDRESS: 366 OLD LONG RIDGE ROAD  
STAMFORD, CT

1	7/16/14	RE-ISSUE/NO CHANGE
REV.	DATE:	DESCRIPTION
Scale: AS NOTED		Date: 06/13/13
Job No. V25-110		File No.

Dwg. No.  
**SK-2**  
Dwg. 2 of 6

**NOTES**

1. PRIOR TO EXCAVATION, CONFIRM THAT NO CONDUITS, PIPES, LINES OR ANY OTHER OBJECTS ARE LOCATED WITHIN AREA TO BE EXCAVATED.
2. GROUND WATER AT 8' BELOW GRADE PER GEOTECHNICAL INFORMATION.
3. CONTRACTOR SHALL INSTALL WILLIAMS GROUT BONDED MCP ANCHORS (MCP 2) AT A DEPTH OF 52 FEET BELOW GRADE.
4. ROCK ANCHORS SHALL USE QUICK-SET CONCRETE GROUT FROM THE BOTTOM OF THE ANCHOR TO A DEPTH OF 39 FEET BELOW GRADE.
5. PROTECT EXISTING BUILDING ROOF FROM CONSTRUCTION RELATED DAMAGE.



1 **TOWER PLAN**  
SK-3 SCALE: 1"=5'-0"

PROJECT NO.  
36922268  
 Designed by:  
MCD  
 Drawn by:  
MCD  
 Checked by:  
KB  
 Approved by:  
ICA


**URS CORPORATION AES**  
 500 ENTERPRISE DRIVE  
 ROCKY HILL, CONNECTICUT  
 860-529-8882

**TOWER PLAN**

**STAMFORD FIRE DEPARTMENT TOWER**  
 SITE ADDRESS: 366 OLD LONG RIDGE ROAD  
 STAMFORD, CT


1	7/16/14	RE-ISSUE/NO CHANGE	<b>SK-3</b>
REV.	DATE:	DESCRIPTION	
Scale: AS NOTED		Date: 06/13/13	
Job No. VZ5-110		File No.	Dwg. 3 of 6

Dwg. No.  
**SK-3**  
 Dwg. 3 of 6



**1 TOWER LEG FOUNDATION**  
SK-4 N.T.S.

**NOTE:**  
INSTALL ANCHOR ASSEMBLY ON THE SOUTH WEST CAISSON ROTATED 4° CLOCKWISE FROM THE CENTERLINE BETWEEN TOWER FACES. OTHER CAISSON ANCHOR ASSEMBLIES WILL NOT NEED THIS ADJUSTMENT.



**2 ANCHOR ASSEMBLY**  
SK-4 N.T.S.

**3 REINFORCED TOWER FOUNDATION**  
SK-4 N.T.S.

**ANCHOR NOTES:**

CONTRACTOR SHALL USE QUIKCRETE QUICK-SETTING CEMENT (PRODUCT # 1240) FOR DEPTHS OF 39 FEET BELOW GRADE TO A MINIMUM DEPTH OF 52 FEET BELOW GRADE.

GROUT/BOND STRESS SHALL BE VERIFIED FOR TYPE OF ROCK ENCOUNTERED BEFORE INSTALLATION OF ANCHOR AND INJECTION OF GROUT CEMENT MATERIAL.

PROJECT NO.  
36922268  
Designed by:  
MCD  
Drawn by:  
MCD  
Checked by:  
KB  
Approved by:  
ICA

**URS CORPORATION AES**  
500 ENTERPRISE DRIVE  
ROCKY HILL, CONNECTICUT  
860-529-8882



**TOWER FOUNDATION DETAILS**

**STAMFORD FIRE DEPARTMENT TOWER**  
SITE ADDRESS: 366 OLD LONG RIDGE ROAD  
STAMFORD, CT

1	7/16/14	RE-ISSUE/NO CHANGE
REV.	DATE:	DESCRIPTION
Scale: AS NOTED		Date: 06/13/13
Job No. VZ5-110	File No.	

Dwg. No.  
**SK-4**  
Dwg. 4 of 6







NOTES:  
 1. WELD 4" EACH SIDE AT TOP AND BOTTOM OF SECTION AND 2" PER 12" EACH SIDE ALONG LENGTH. TYPICAL FOR ALL REINFORCING BARS.  
 2. ALLOW A MINIMUM 1/4" WELD FOR BARS 1/4" THICK AND A WELD OF 3/16" FOR 1/2" BARS

2 LEG SECTION SK-5 N.T.S.

REPLACE EXISTING DIAGONAL BOLTS A325N W/ A325X (66.7' TO 100')

REPLACE EXISTING DIAGONAL BOLTS A325N W/ A325X (0' TO 60')

1 TOWER ELEVATION SK-5 SCALE: 1"=20'-0"



NOTES:  
 1. WELD 4" EACH SIDE AT TOP AND BOTTOM OF SECTION AND 2" PER 12" EACH SIDE ALONG LENGTH. TYPICAL FOR ALL REINFORCING BARS.  
 2. ALLOW A MINIMUM 1/4" WELD FOR BARS 1/4" THICK AND A WELD OF 3/16" FOR 1/2" BARS

3 LEG SECTION (0' - 10') SK-5 N.T.S.

PROJECT NO. 36922268

Designed by: MCD

Drawn by: MCD

Checked by: KB

Approved by: ICA


**URS CORPORATION AES**  
 500 ENTERPRISE DRIVE  
 ROCKY HILL, CONNECTICUT  
 860-529-8882

**TOWER ELEVATION**


**STAMFORD FIRE DEPARTMENT TOWER**  
 SITE ADDRESS: 366 OLD LONG RIDGE ROAD  
 STAMFORD, CT

1	7/16/14	RE-ISSUE/NO CHANGE
REV.	DATE:	DESCRIPTION
Scale: AS NOTED		Date: 06/13/13
Job No. V25-110	File No.	Dwg. No. SK-5

Dwg. No. SK-5



**2 TOWER LEG SECTION**  
 SK-6 SCALE: 3"=1'-0"



**1 TOWER LEG DETAIL**  
 SK-6 SCALE: 3"=1'-0"



PROJECT NO.  
36922268  
 Designed by:  
MCD  
 Drawn by:  
MCD  
 Checked by:  
KB  
 Approved by:  
ICA

**URS CORPORATION AES**  
 500 ENTERPRISE DRIVE  
 ROCKY HILL, CONNECTICUT  
 860-529-8882

**ATTACHMENT DETAILS**  
**STAMFORD FIRE DEPARTMENT TOWER**  
 SITE ADDRESS: 366 OLD LONG RIDGE ROAD  
 STAMFORD, CT

1	7/16/14	RE-ISSUE/NO CHANGE
REV.	DATE:	DESCRIPTION
Scale: AS NOTED		Date: 06/13/13
Job No. VZ5-110	File No.	

Dwg. No.  
**SK-6**  
 Dwg. 6 of 6

## TNX TOWER INPUT / OUTPUT SUMMARY

(Sprint) 36928702.00000  
(Verizon) 36922268.00000  
(AT&T) 36922483.00000

152' SSV Lattice Tower  
Stamford, CT

7/15/2014

DESIGNED APPURTENANCE LOADING

TYPE	ELEVATION	TYPE	ELEVATION
(2) DB860HBE-M (Sprint)	162	(2) DB860HBE-M (Sprint)	128
DB553K-CR (Unknown)	156,701	DB254-A (Unknown)	128
4x4" Pipe Mount (Unknown)	152	APX16DWW-16DWW-S-E-ACU w/ Mount (T-Mobile)	108
4" w/Radome (Unknown)	152	TMA (T-Mobile)	108
DB803KHE-XP (Unknown)	151,25	APX16DWW-16DWW-S-E-ACU w/ Mount (T-Mobile)	108
Filter Box 22"x22"x6" (Unknown)	149	TMA (T-Mobile)	108
3' Sidearm (Unknown)	149	APX16DWW-16DWW-S-E-ACU w/ Mount (T-Mobile)	108
Filter Box 20"x6"x6" (Unknown)	146.5	TMA (T-Mobile)	108
3' Sidearm (Unknown)	146.5	APX16DWW-16DWW-S-E-ACU w/ Mount (T-Mobile)	108
12"x2 1/2" STD Pipe Mount (Unknown)	146	TMA (T-Mobile)	108
12" x 3" Dia Omni (Unknown)	144	20' x 3" Dia Omni (Unknown)	101
4x3" Pipe Mount (ATT)	143	2" Dia 18" Omni (Unknown)	101
4x3" Pipe Mount (ATT)	143	8' 4-Bay Dipole (Unknown)	101
7770 (ATT)	143	8' 4-Bay Dipole (Unknown)	101
7770 (ATT)	143	DB-T1-e2-9AB-02 (Verizon)	98
7770 (ATT)	143	Valmont 13' Lightweight T-Frame (Verizon)	98
(2) LPG 21401 TMA (ATT)	143	Valmont 13' Lightweight T-Frame (Verizon)	98
(2) LPG 21401 TMA (ATT)	143	Valmont 13' Lightweight T-Frame (Verizon)	98
(2) LPG 21401 TMA (ATT)	143	RRH (Verizon)	98
P65-16-XLH-RR (ATT)	143	RRH (Verizon)	98
P65-16-XLH-RR (ATT)	143	RRH (Verizon)	98
(2) RRUUS-11 (ATT)	143	LNX-8513DS-VTM (Verizon - LTE)	98
(2) RRUUS-11 (ATT)	143	LNX-8514DS-14M (Verizon - LTE)	98
4x3" Pipe Mount (ATT)	143	LNX-6514DS-14M (Verizon - LTE)	98
4x3" Pipe Mount (ATT)	143	LNX-6514DS-14M (Verizon - LTE)	98
4x3" Pipe Mount (ATT)	143	RH_2x40-700 (Verizon - LTE)	98
4x3" Pipe Mount (ATT)	143	RH_2x40-700 (Verizon - LTE)	98
4x3" Pipe Mount (ATT)	143	RH_2x40-700 (Verizon - LTE)	98
4x4" Pipe Mount (Unknown)	142	LNX-8513DS-VTM (Verizon - 850MHz)	98
DB553K-CR (Unknown)	141,701	LNX-8514DS-14M (Verizon - 850MHz)	98
4" w/Radome (Unknown)	140	HBXX-6517DS-VTM (Verizon - PCS)	98
6' x 3" Dia Omni (Unknown)	138	HBXX-6517DS-VTM (Verizon - PCS)	98
4' Side Mount Standoff (1) (Unknown)	137	Panasonic RRH 1900MHz (Verizon - PCS)	98
4x4" Pipe Mount (Unknown)	136.5	Panasonic RRH 1900MHz (Verizon - PCS)	98
DB495-A (Unknown)	135	Panasonic RRH 1900MHz (Verizon - PCS)	98
3' Sidearm (Unknown)	133.5	HBXX-6517DS-VTM (Verizon - PCS)	98
4' Side Mount Standoff (1) (Unknown)	133	HBXX-6517DS-VTM (Verizon - PCS)	98
2" Dia 8" Omni (Unknown)	133	HBXX-6517DS-VTM (Verizon - PCS)	98
APXV9TM14-120 (Sprint)	128	RH_2X40-AVIS (Verizon - AWS)	98
APXV9TM14-120 (Sprint)	128	RH_2X40-AVIS (Verizon - AWS)	98
APXV9TM14-120 (Sprint)	128	RH_2X40-AVIS (Verizon - AWS)	98
800 Mhz Filter (Sprint)	128	DB-T1-e2-9AB-02 (Verizon)	98
800 Mhz Filter (Sprint)	128	3' Sidearm (Vacant)	95.5
800 Mhz Filter (Sprint)	128	3' Sidearm (Unknown)	95.5
RRH (Sprint)	128	3' Sidearm (Unknown)	95.5
RRH (Sprint)	128	3' Sidearm (Unknown)	94.5
RRH (Sprint)	128	3' Sidearm (Unknown)	88.5
APXSPP18-C-A20 w/ Mounting Pipe (Sprint)	128	4' x 3" Dia Omni (Unknown)	79
APXSPP18-C-A20 w/ Mounting Pipe (Sprint)	128	8' 2-Bay Dipole (Unknown)	78
APXSPP18-C-A20 w/ Mounting Pipe (Sprint)	128	3' Sidearm (Unknown)	72.5
(3) 11" Boom Gate w/B - 2 3/8" Pipe (Tapered) (Sprint)	128	3' Sidearm (Unknown)	72.5
RRH (Sprint)	128	Scala Yagi w/ Radome (Unknown)	72
RRH (Sprint)	128	GPS (Sprint)	58
RRH (Sprint)	128	2' Sidearm (Sprint)	57
RRH (Sprint)	128	1.2M (Unknown)	45
(2) DB860HBE-M (Sprint)	128	4x4" Stand-off (Unknown)	44
(2) DB860HBE-M (Sprint)	128		

SYMBOL LIST

MARK	SIZE	MARK	SIZE
A	Rohn 5 STD w/ (3) 1.5"x0.5" Bars	D	L1 3/4x1 3/4x3/16
B	Rohn 5 STD w/ (6) 1.5"x0.5" Bars	E	L2 8/75x2 8/75x0.25
C	L1 1/2x1 1/2x1/4		

MATERIAL STRENGTH

GRADE	FU	FY	FU	FY	FU
A572-50	50 ksi	A36	36 ksi	58 ksi	

TOWER DESIGN NOTES

1. Tower is located in Fairfield County, Connecticut.
2. Tower designed for a 85 mph basic wind in accordance with the TIA/EIA-222-F Standard.
3. Tower is also designed for a 74 mph basic wind with 0.50 in ice.
4. Deflections are based upon a 50 mph wind.
5. TOWER RATING: 97.7%

MAX. CORNER REACTIONS AT BASE:

DOWN: 220 K  
SHEAR: 26 K

UPLIFT: -189 K  
SHEAR: 23 K

AXIAL  
51 K

SHEAR  
40 K

MOMENT  
3572 kip-ft


TORQUE 21 kip-ft  
74 mph WIND - 0.500 in ICE

AXIAL  
31 K

SHEAR  
43 K

MOMENT  
3784 kip-ft

TORQUE 21 kip-ft  
REACTIONS - 85 mph WIND



Section	Legs	Diagonals	Top Girts	Horizontal	Sec. Horizontals	Red. Horizontals	Red. Diagonals	Face Width (ft)	# Panels @ (ft)	Weight (k)
T17	B	L3 1/2x3 1/2x5/16	L3 1/2x3 1/2x3/16	N.A.	N.A.	N.A.	N.A.	20.7813	1 @ 10	17.9
T16	A	L3 1/2x3 1/2x1/4	L3 1/2x3 1/2x1/4	N.A.	N.A.	N.A.	N.A.	19.7813	1 @ 5	18.52083
T15		L3 1/2x3 1/2x1/4	L3 1/2x3 1/2x1/4	N.A.	N.A.	N.A.	N.A.	18.7708	4 @ 5	8.52083
T14		L3 1/2x3 1/2x1/4	L3 1/2x3 1/2x1/4	N.A.	N.A.	N.A.	N.A.	17.6979	3 @ 10	
T13		L3 1/2x2 1/2x5/16	L3 1/2x2 1/2x5/16	N.A.	N.A.	N.A.	N.A.	16.6979	9 @ 6.66667	
T12		L2 1/2x2 1/2x1/4	L2 1/2x2 1/2x1/4	N.A.	N.A.	N.A.	N.A.	13.3021		
T11		L2 1/2x2 1/2x1/4	L2 1/2x2 1/2x1/4	N.A.	N.A.	N.A.	N.A.	12.6042		
T10		A36	A36	N.A.	N.A.	N.A.	N.A.	10.5625		
T9								8.5625		
T8								8.0625		
T7								7.5625		
T6								7.0625		
T5								6.5625		
T4								6.0625		
T3								5.5625		
T2								5.0625		
T1								4.5625		

**URS Corporation**  
 500 Enterprise Drive, Suite 3B  
 Rocky Hill, CT 06067  
 Phone: 860-529-8882  
 FAX: 860-529-3991

**152' ROHN SSV Tower**  
 Project: 366 Old Long Ridge Road, Stamford, CT  
 Client: Verizon, Sprint and AT&T / S.A. Evaluation  
 Code: TIA/EIA-222-F  
 Drawn by: MCD  
 Date: 07/15/14  
 Scale:  
 Dwg No: E-1

## TNX TOWER FEEDLINE DISTRIBUTION CHART

(Sprint) 36928702.00000  
(Verizon) 36922268.00000  
(AT&T) 36922483.00000


152' SSV Lattice Tower  
Stamford, CT

7/15/2014

# Feed Line Distribution Chart

## 0' - 152'

Round      Flat      App In Face      App Out Face      Truss Leg



<b>URS Corporation</b> 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	<b>Job: 152' ROHN SSV Tower</b>		
	<b>Project: 366 Old Long Ridge Road, Stamford, CT</b>		
	Client: Verizon, Sprint and AT&T / S.A. Evaluation	Drawn by: MCD	App'd:
	Code: TIA/EIA-222-F	Date: 07/15/14	Scale: NTS
Path:	Dwg No: E-7		

# TNX TOWER FEEDLINE PLAN


(Sprint) 36928702.00000  
(Verizon) 36922268.00000  
(AT&T) 36922483.00000

152' SSV Lattice Tower  
Stamford, CT

7/15/2014

# Feed Line Plan

Round \_\_\_\_\_ Flat \_\_\_\_\_ App In Face \_\_\_\_\_ App Out Face \_\_\_\_\_



<b>URS Corporation</b>		<b>Job: 152' ROHN SSV Tower</b>	
500 Enterprise Drive, Suite 3B		Project: 366 Old Long Ridge Road, Stamford, CT	
Rocky Hill, CT 06067		Client: Verizon, Sprint and AT&T / S.A. Evaluation	Drawn by: MCD
Phone: 860-529-8882		Code: TIA/EIA-222-F	Date: 07/15/14
FAX: 860-529-3991		Scale: NTS	Dwg No: E-7



## TNX TOWER DETAILED OUTPUT

(Sprint) 36928702.00000  
(Verizon) 36922268.00000  
(AT&T) 36922483.00000

152' SSV Lattice Tower  
Stamford, CT

7/15/2014

<b>tnxTower</b>  <b>URS Corporation</b> 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	<b>Job</b> 152' ROHN SSV Tower	<b>Page</b> 1 of 55
	<b>Project</b> 366 Old Long Ridge Road, Stamford, CT	<b>Date</b> 11:46:06 07/15/14
	<b>Client</b> Verizon, Sprint and AT&T / S.A. Evaluation	<b>Designed by</b> MCD

## Tower Input Data

The main tower is a 3x free standing tower with an overall height of 152.00 ft above the ground line.

The base of the tower is set at an elevation of 0.00 ft above the ground line.

The face width of the tower is 6.52 ft at the top and 20.78 ft at the base.

This tower is designed using the TIA/EIA-222-F standard.

The following design criteria apply:

Tower is located in Fairfield County, Connecticut.

Basic wind speed of 85 mph.

Nominal ice thickness of 0.500 in.

Ice density of 56 pcf.

A wind speed of 74 mph is used in combination with ice.

Temperature drop of 50 °F.

Deflections calculated using a wind speed of 50 mph.

A non-linear (P-delta) analysis was used.

Pressures are calculated at each section.


Stress ratio used in tower member design is 1.333.

Local bending stresses due to climbing loads, feed line supports, and appurtenance mounts are not considered.

## Options

<ul style="list-style-type: none"> <li>Consider Moments - Legs</li> <li>Consider Moments - Horizontals</li> <li>Consider Moments - Diagonals</li> <li>Use Moment Magnification</li> <li>√ Use Code Stress Ratios</li> <li>Use Code Safety Factors - Guys</li> <li>Escalate Ice</li> <li>Always Use Max Kz</li> <li>Use Special Wind Profile</li> <li>√ Include Bolts In Member Capacity</li> <li>√ Leg Bolts Are At Top Of Section</li> <li>√ Secondary Horizontal Braces Leg</li> <li>Use Diamond Inner Bracing (4 Sided)</li> <li>Add IBC .6D+W Combination</li> </ul>	<ul style="list-style-type: none"> <li>Distribute Leg Loads As Uniform</li> <li>Assume Legs Pinned</li> <li>√ Assume Rigid Index Plate</li> <li>√ Use Clear Spans For Wind Area</li> <li>√ Use Clear Spans For KL/r</li> <li>Retension Guys To Initial Tension</li> <li>Bypass Mast Stability Checks</li> <li>Use Azimuth Dish Coefficients</li> <li>√ Project Wind Area of Appurt.</li> <li>Autocalc Torque Arm Areas</li> <li>SR Members Have Cut Ends</li> <li>√ Sort Capacity Reports By Component</li> <li>Triangulate Diamond Inner Bracing</li> <li>Use TIA-222-G Tension Splice Capacity</li> <li>Exemption</li> </ul>	<ul style="list-style-type: none"> <li>Treat Feedline Bundles As Cylinder</li> <li>Use ASCE 10 X-Brace Ly Rules</li> <li>√ Calculate Redundant Bracing Forces</li> <li>Ignore Redundant Members in FEA</li> <li>SR Leg Bolts Resist Compression</li> <li>√ All Leg Panels Have Same Allowable</li> <li>Offset Girt At Foundation</li> <li>√ Consider Feedline Torque</li> <li>Include Angle Block Shear Check</li> </ul> <p style="text-align: center;"><b>Poles</b></p> <ul style="list-style-type: none"> <li>Include Shear-Torsion Interaction</li> <li>Always Use Sub-Critical Flow</li> <li>Use Top Mounted Sockets</li> </ul>
--	--	---

<b>tnxTower</b>  <b>URS Corporation</b> 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	<b>Job</b> 152' ROHN SSV Tower	<b>Page</b> 2 of 55
	<b>Project</b> 366 Old Long Ridge Road, Stamford, CT	<b>Date</b> 11:46:06 07/15/14
	<b>Client</b> Verizon, Sprint and AT&T / S.A. Evaluation	<b>Designed by</b> MCD



**Triangular Tower**

## Tower Section Geometry

<i>Tower Section</i>	<i>Tower Elevation</i>	<i>Assembly Database</i>	<i>Description</i>	<i>Section Width</i>	<i>Number of Sections</i>	<i>Section Length</i>
	<i>ft</i>			<i>ft</i>		<i>ft</i>
T1	152.00-140.00			6.52	1	12.00
T2	140.00-135.00			6.56	1	5.00
T3	135.00-130.00			7.06	1	5.00
T4	130.00-125.00			7.56	1	5.00
T5	125.00-120.00			8.06	1	5.00
T6	120.00-100.00			8.56	1	20.00
T7	100.00-80.00			10.56	1	20.00
T8	80.00-73.33			12.60	1	6.67
T9	73.33-66.67			13.30	1	6.67
T10	66.67-60.00			14.00	1	6.67
T11	60.00-50.00			14.70	1	10.00
T12	50.00-40.00			15.70	1	10.00
T13	40.00-30.00			16.70	1	10.00
T14	30.00-20.00			17.70	1	10.00
T15	20.00-15.00			18.77	1	5.00
T16	15.00-10.00			19.26	1	5.00
T17	10.00-0.00			19.78	1	10.00

## Tower Section Geometry (cont'd)

<b>Job</b>	152' ROHN SSV Tower	<b>Page</b>	3 of 55
<b>Project</b>	366 Old Long Ridge Road, Stamford, CT	<b>Date</b>	11:46:06 07/15/14
<b>Client</b>	Verizon, Sprint and AT&T / S.A. Evaluation	<b>Designed by</b>	MCD

Tower Section	Tower Elevation	Diagonal Spacing	Bracing Type	Has K Brace End Panels	Has Horizontals	Top Girt Offset	Bottom Girt Offset
	ft	ft				in	in
T1	152.00-140.00	3.94	X Brace	No	Yes	1,000	1,000
T2	140.00-135.00	4.83	X Brace	No	Yes	1,000	1,000
T3	135.00-130.00	5.00	X Brace	No	No	0,000	0,000
T4	130.00-125.00	5.00	X Brace	No	No	0,000	0,000
T5	125.00-120.00	5.00	X Brace	No	No	0,000	0,000
T6	120.00-100.00	6.67	X Brace	No	No	0,000	0,000
T7	100.00-80.00	6.67	X Brace	No	Yes	0,000	0,000
T8	80.00-73.33	6.67	X Brace	No	No	0,000	0,000
T9	73.33-66.67	6.67	X Brace	No	Yes	0,000	0,000
T10	66.67-60.00	6.67	X Brace	No	Yes	0,000	0,000
T11	60.00-50.00	10.00	X Brace	No	No	0,000	0,000
T12	50.00-40.00	10.00	X Brace	No	Yes	0,000	0,000
T13	40.00-30.00	10.00	X Brace	No	Yes	0,000	0,000
T14	30.00-20.00	5.00	Double K1	No	Yes	0,000	0,000
T15	20.00-15.00	5.00	K1 Up	No	Yes	0,000	0,000
T16	15.00-10.00	5.00	K Brace Down	No	Yes	0,000	0,000
T17	10.00-0.00	10.00	X Brace	No	No	0,000	0,000

**Tower Section Geometry (cont'd)**

Tower Elevation	Leg Type	Leg Size	Leg Grade	Diagonal Type	Diagonal Size	Diagonal Grade
ft						
T1 152.00-140.00	Pipe	ROHN 2 STD	A572-50 (50 ksi)	Single Angle	L1 1/2x1 1/2x1/8	A36 (36 ksi)
T2 140.00-135.00	Pipe	ROHN 2.5 STD	A572-50 (50 ksi)	Single Angle	L1 1/2x1 1/2x3/16	A36 (36 ksi)
T3 135.00-130.00	Pipe	ROHN 2.5 STD	A572-50 (50 ksi)	Single Angle	L1 1/2x1 1/2x3/16	A36 (36 ksi)
T4 130.00-125.00	Pipe	ROHN 2.5 STD	A572-50 (50 ksi)	Single Angle	L1 1/2x1 1/2x1/4	A36 (36 ksi)
T5 125.00-120.00	Pipe	ROHN 2.5 STD	A572-50 (50 ksi)	Single Angle	L1 3/4x1 3/4x3/16	A36 (36 ksi)
T6 120.00-100.00	Arbitrary Shape	Rohn 2.5 X-Str w/ (3) 1.5"x0.25" Bars	A572-50 (50 ksi)	Single Angle	L2x2x1/4	A36 (36 ksi)
T7 100.00-80.00	Arbitrary Shape	Rohn 2.5 X-Str w/ (3) 1.5"x0.25" Bars	A572-50 (50 ksi)	Single Angle	L2 1/2x2 1/2x1/4	A36 (36 ksi)
T8 80.00-73.33	Arbitrary Shape	Rohn 3 X-Str w/ (3) 1.5"x0.5" Bars	A572-50 (50 ksi)	Single Angle	L2 1/2x2 1/2x1/4	A36 (36 ksi)
T9 73.33-66.67	Arbitrary Shape	Rohn 3 X-Str w/ (3) 1.5"x0.5" Bars	A572-50 (50 ksi)	Single Angle	L2 1/2x2 1/2x5/16	A36 (36 ksi)
T10 66.67-60.00	Arbitrary Shape	Rohn 3 X-Str w/ (3) 1.5"x0.5" Bars	A572-50 (50 ksi)	Single Angle	L2 1/2x2 1/2x5/16	A36 (36 ksi)
T11 60.00-50.00	Arbitrary Shape	Rohn 4 X-Str w/ (3) 1.5"x0.5" Bars	A572-50 (50 ksi)	Single Angle	L3x3x5/16	A36 (36 ksi)
T12 50.00-40.00	Arbitrary Shape	Rohn 4 X-Str w/ (3) 1.5"x0.5" Bars	A572-50 (50 ksi)	Single Angle	L3x3x5/16	A36 (36 ksi)
T13 40.00-30.00	Arbitrary Shape	Rohn 4 X-Str w/ (3) 1.5"x0.5" Bars	A572-50 (50 ksi)	Single Angle	L3x3x3/8	A36 (36 ksi)
T14 30.00-20.00	Arbitrary Shape	Rohn 4 X-Str w/ (3) 1.5"x0.5" Bars	A572-50 (50 ksi)	Single Angle	L3x3x5/16	A36 (36 ksi)
T15 20.00-15.00	Arbitrary Shape	Rohn 5 STD w/ (3) 1.5"x0.5" Bars	A572-50 (50 ksi)	Single Angle	L3 1/2x3 1/2x1/4	A36 (36 ksi)
T16 15.00-10.00	Arbitrary Shape	Rohn 5 STD w/ (3) 1.5"x0.5" Bars	A572-50 (50 ksi)	Single Angle	L3 1/2x3 1/2x1/4	A36 (36 ksi)
T17 10.00-0.00	Arbitrary Shape	Rohn 5 STD w/ (6) 1.5"x0.5" Bars	A572-50 (50 ksi)	Single Angle	L3 1/2x3 1/2x5/16	A36 (36 ksi)

<b>tnxTower</b>  <b>URS Corporation</b> 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	<b>Job</b> 152' ROHN SSV Tower	<b>Page</b> 4 of 55
	<b>Project</b> 366 Old Long Ridge Road, Stamford, CT	<b>Date</b> 11:46:06 07/15/14
	<b>Client</b> Verizon, Sprint and AT&T / S.A. Evaluation	<b>Designed by</b> MCD

Tower Elevation ft	Leg Type	Leg Size	Leg Grade	Diagonal Type	Diagonal Size	Diagonal Grade
		Bars	(50 ksi)			(36 ksi)

**Tower Section Geometry (cont'd)**

Tower Elevation ft	Top Girt Type	Top Girt Size	Top Girt Grade	Bottom Girt Type	Bottom Girt Size	Bottom Girt Grade
T1 152.00-140.00	Single Angle	L2x2x1/8	A36 (36 ksi)	Single Angle		A36 (36 ksi)
T2 140.00-135.00	Single Angle	L2x2x1/8	A36 (36 ksi)	Single Angle		A36 (36 ksi)

**Tower Section Geometry (cont'd)**

Tower Elevation ft	No. of Mid Girts	Mid Girt Type	Mid Girt Size	Mid Girt Grade	Horizontal Type	Horizontal Size	Horizontal Grade
T14 30.00-20.00	None	Flat Bar		A36 (36 ksi)	Single Angle	L3x3x3/16	A36 (36 ksi)
T15 20.00-15.00	None	Flat Bar		A36 (36 ksi)	Single Angle	L2.875x2.875x0.25	A36 (36 ksi)
T16 15.00-10.00	None	Flat Bar		A36 (36 ksi)	Single Angle	L2.875x2.875x0.25	A36 (36 ksi)

**Tower Section Geometry (cont'd)**

Tower Elevation ft	Secondary Horizontal Type	Secondary Horizontal Size	Secondary Horizontal Grade	Inner Bracing Type	Inner Bracing Size	Inner Bracing Grade
T7 100.00-80.00	Single Angle	L3x3x3/16	A36 (36 ksi)	Solid Round		A572-50 (50 ksi)
T9 73.33-66.67	Single Angle	L3x3x3/16	A36 (36 ksi)	Solid Round		A572-50 (50 ksi)
T10 66.67-60.00	Single Angle	L3x3x3/16	A36 (36 ksi)	Solid Round		A572-50 (50 ksi)
T12 50.00-40.00	Single Angle	L3x3x3/16	A36 (36 ksi)	Solid Round		A572-50 (50 ksi)
T13 40.00-30.00	Single Angle	L3x3x3/16	A36 (36 ksi)	Solid Round		A572-50 (50 ksi)

**Tower Section Geometry (cont'd)**

<b>tnxTower</b>  <b>URS Corporation</b> 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	<b>Job</b> 152' ROHN SSV Tower	<b>Page</b> 5 of 55
	<b>Project</b> 366 Old Long Ridge Road, Stamford, CT	<b>Date</b> 11:46:06 07/15/14
	<b>Client</b> Verizon, Sprint and AT&T / S.A. Evaluation	<b>Designed by</b> MCD

Tower Elevation	Redundant Bracing Grade	Redundant Type	Redundant Size	K Factor	
ft					
T14 30.00-20.00	A36 (36 ksi)	Horizontal (1) Diagonal (1)	Equal Angle Equal Angle	L2x2x1/4 L2x2x1/4	1 1
T15 20.00-15.00	A36 (36 ksi)	Horizontal (1) Diagonal (1)	Equal Angle Equal Angle	L2x2x1/4 L2x2x1/4	1 1

### Tower Section Geometry (cont'd)

Tower Elevation	Gusset Area (per face)	Gusset Thickness	Gusset Grade	Adjust. Factor $A_f$	Adjust. Factor $A_r$	Weight Mult.	Double Angle Stitch Bolt Spacing Diagonals	Double Angle Stitch Bolt Spacing Horizontals
ft	ft <sup>2</sup>	in					in	in
T1 152.00-140.00	0.00	0.000	A36 (36 ksi)	1	1	1	36.000	36.000
T2 140.00-135.00	0.00	0.000	A36 (36 ksi)	1	1	1	36.000	36.000
T3 135.00-130.00	0.00	0.000	A36 (36 ksi)	1	1	1	36.000	36.000
T4 130.00-125.00	0.00	0.000	A36 (36 ksi)	1	1	1	36.000	36.000
T5 125.00-120.00	0.00	0.000	A36 (36 ksi)	1	1	1	36.000	36.000
T6 120.00-100.00	0.00	0.000	A36 (36 ksi)	1	1	1	36.000	36.000
T7 100.00-80.00	0.00	0.000	A36 (36 ksi)	1	1	1	36.000	36.000
T8 80.00-73.33	0.00	0.000	A36 (36 ksi)	1	1	1	36.000	36.000
T9 73.33-66.67	0.00	0.000	A36 (36 ksi)	1	1	1	36.000	36.000
T10 66.67-60.00	0.00	0.000	A36 (36 ksi)	1	1	1	36.000	36.000
T11 60.00-50.00	0.00	0.000	A36 (36 ksi)	1	1	1	36.000	36.000
T12 50.00-40.00	0.00	0.000	A36 (36 ksi)	1	1	1	36.000	36.000
T13 40.00-30.00	0.00	0.000	A36 (36 ksi)	1	1	1	36.000	36.000
T14 30.00-20.00	0.00	0.000	A36 (36 ksi)	1	1	1	36.000	36.000
T15 20.00-15.00	0.00	0.000	A36 (36 ksi)	1	1	1	36.000	36.000
T16 15.00-10.00	0.00	0.000	A36 (36 ksi)	1	1	1	36.000	36.000
T17 10.00-0.00	0.00	0.000	A36 (36 ksi)	1	1	1	36.000	36.000

### Tower Section Geometry (cont'd)

*K Factors<sup>1</sup>*



<b>Job</b>	152' ROHN SSV Tower	<b>Page</b>	7 of 55
<b>Project</b>	366 Old Long Ridge Road, Stamford, CT	<b>Date</b>	11:46:06 07/15/14
<b>Client</b>	Verizon, Sprint and AT&T / S.A. Evaluation	<b>Designed by</b>	MCD

Tower Elevation ft	Leg		Diagonal		Top Girt		Bottom Girt		Mid Girt		Long Horizontal		Short Horizontal	
	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U
T5 125.00-120.00	0.000	1	0.000	0.75	0.000	0.75	0.000	0.75	0.000	0.75	0.000	0.75	0.000	0.75
T6 120.00-100.00	0.000	1	0.000	0.75	0.000	0.75	0.000	0.75	0.000	0.75	0.000	0.75	0.000	0.75
T7 100.00-80.00	0.000	1	0.000	0.75	0.000	0.75	0.000	0.75	0.000	0.75	0.000	0.75	0.000	0.75
T8 80.00-73.33	0.000	1	0.000	0.75	0.000	0.75	0.000	0.75	0.000	0.75	0.000	0.75	0.000	0.75
T9 73.33-66.67	0.000	1	0.000	0.75	0.000	0.75	0.000	0.75	0.000	0.75	0.000	0.75	0.000	0.75
T10 66.67-60.00	0.000	1	0.000	0.75	0.000	0.75	0.000	0.75	0.000	0.75	0.000	0.75	0.000	0.75
T11 60.00-50.00	0.000	1	0.000	0.75	0.000	0.75	0.000	0.75	0.000	0.75	0.000	0.75	0.000	0.75
T12 50.00-40.00	0.000	1	0.000	0.75	0.000	0.75	0.000	0.75	0.000	0.75	0.000	0.75	0.000	0.75
T13 40.00-30.00	0.000	1	0.000	0.75	0.000	0.75	0.000	0.75	0.000	0.75	0.000	0.75	0.000	0.75
T14 30.00-20.00	0.000	1	0.000	0.75	0.000	0.75	0.000	0.75	0.000	0.75	0.000	0.75	0.000	0.75
T15 20.00-15.00	0.000	1	0.000	0.75	0.000	0.75	0.000	0.75	0.000	0.75	0.000	0.75	0.000	0.75
T16 15.00-10.00	0.000	1	0.000	0.75	0.000	0.75	0.000	0.75	0.000	0.75	0.000	0.75	0.000	0.75
T17 10.00-0.00	0.000	1	0.000	0.75	0.000	0.75	0.000	0.75	0.000	0.75	0.000	0.75	0.000	0.75

**Tower Section Geometry (cont'd)**

Tower Elevation ft	Leg Connection Type	Leg		Diagonal		Top Girt		Bottom Girt		Mid Girt		Long Horizontal		Short Horizontal	
		Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.
T1 152.00-140.00	Flange	0.000	0	A325N	1	0.500	1	A325N	0	0.625	0	A325N	0	A325N	0
T2 140.00-135.00	Flange	0.625	4	A325N	1	0.500	1	A325N	0	0.000	0	0.625	0	0.625	0
T3 135.00-130.00	Flange	0.625	0	A325N	1	0.500	1	A325N	0	0.000	0	0.625	0	0.625	0
T4 130.00-125.00	Flange	0.625	0	A325N	1	0.500	1	A325N	0	0.000	0	0.625	0	0.625	0
T5 125.00-120.00	Flange	0.625	0	A325N	1	0.500	1	A325N	0	0.625	0	0.625	0	0.625	0
T6 120.00-100.00	Flange	0.625	4	A325N	1	0.500	1	A325N	0	0.625	0	0.625	0	0.625	0
T7 100.00-80.00	Flange	0.750	4	A325N	1	0.500	1	A325N	0	0.625	0	0.625	0	0.500	2
T8 80.00-73.33	Flange	0.875	4	A325N	1	0.500	1	A325N	0	0.000	0	0.625	0	0.625	0
T9 73.33-66.67	Flange	0.875	0	A325N	1	0.500	1	A325N	0	0.000	0	0.625	0	0.500	2
T10 66.67-60.00	Flange	0.875	0	A325N	1	0.500	1	A325N	0	0.625	0	0.625	0	0.500	2



<b>tnxTower</b>  <b>URS Corporation</b> 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	<b>Job</b> 152' ROHN SSV Tower	<b>Page</b> 8 of 55
	<b>Project</b> 366 Old Long Ridge Road, Stamford, CT	<b>Date</b> 11:46:06 07/15/14
	<b>Client</b> Verizon, Sprint and AT&T / S.A. Evaluation	<b>Designed by</b> MCD

Tower Elevation ft	Leg Connection Type	Leg Bolt Size in	Leg No.	Diagonal		Top Girt		Bottom Girt		Mid Girt		Long Horizontal		Short Horizontal	
				Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.
T11 60.00-50.00	Flange	0.875	4	0.625	1	0.625	0	0.000	0	0.625	0	0.625	0	0.625	0
T12 50.00-40.00	Flange	0.875	0	0.625	1	0.625	0	0.625	0	0.625	0	0.625	0	0.500	2
T13 40.00-30.00	Flange	1.000	4	0.625	1	0.625	0	0.000	0	0.625	0	0.625	0	0.500	2
T14 30.00-20.00	Flange	1.000	0	0.625	1	0.625	0	0.625	0	0.625	0	0.500	2	0.625	0
T15 20.00-15.00	Flange	1.000	4	0.625	1	0.625	0	0.000	0	0.625	0	0.625	0	0.625	0
T16 15.00-10.00	Flange	1.000	0	0.625	1	0.625	0	0.625	0	0.625	0	0.625	1	0.625	0
T17 10.00-0.00	Flange	1.000	0	0.625	1	0.625	0	0.625	0	0.625	0	0.625	0	0.625	0
		A325N		A325X		A325N		A325N		A325N		A325N		A325N	

**Feed Line/Linear Appurtenances - Entered As Round Or Flat**

Description	Face or Leg	Allow Shield	Component Type	Placement ft	Face Offset in	Lateral Offset (Frac FW)	# Per Row	# Row	Clear Spacing in	Width or Diameter in	Perimeter in	Weight klf
1 1/4	B	Yes	Ar (CfAe)	150.00 - 6.00	2.000	-0.44	2	2	1.550	1.550		0.001
1 5/8	A	Yes	Ar (CfAe)	150.00 - 6.00	-2.000	0.47	2	2	1.980	1.980		0.001
1/2	A	Yes	Ar (CfAe)	135.00 - 6.00	-2.000	0.45	2	2	0.580	0.580		0.000
EW180	C	Yes	Af (CfAe)	152.00 - 6.00	2.000	-0.04	1	1	0.590	0.590	2.006	0.000
EW180	C	Yes	Af (CfAe)	140.00 - 6.00	2.000	-0.05	1	1	0.590	0.590	2.006	0.000
1 5/8 (AT&T)	A	Yes	Ar (CfAe)	143.00 - 6.00	-2.000	0.1	9	9	1.980	1.980		0.001
7/8 EW180	C	Yes	Ar (CfAe)	152.00 - 6.00	2.000	-0.03	1	1	1.110	1.110		0.001
EW180	C	Yes	Af (CfAe)	136.50 - 6.00	-2.000	-0.46	1	1	0.590	0.590	2.006	0.000
1 5/8	C	Yes	Ar (CfAe)	135.00 - 6.00	2.000	0.02	2	2	1.980	1.980		0.001
7/8	B	Yes	Ar (CfAe)	138.00 - 6.00	2.000	0.41	1	1	1.110	1.110		0.001
1/2	A	Yes	Ar (CfAe)	122.00 - 6.00	2.000	-0.48	1	1	0.580	0.580		0.000
7/8	B	Yes	Ar (CfAe)	129.00 - 6.00	2.000	0.42	1	1	1.110	1.110		0.001
7/8	B	Yes	Ar (CfAe)	96.00 - 6.00	2.000	0.43	1	1	1.110	1.110		0.001
7/8	A	Yes	Ar (CfAe)	97.00 - 6.00	2.000	-0.49	1	1	1.110	1.110		0.001
7/8	B	Yes	Ar (CfAe)	97.00 - 6.00	2.000	0.44	1	1	1.110	1.110		0.001
7/8	B	Yes	Ar (CfAe)	91.00 - 6.00	2.000	0.45	1	1	1.110	1.110		0.001
1 1/4	B	Yes	Ar (CfAe)	75.00 - 6.00	2.000	0.47	1	1	1.550	1.550		0.001
7/8	B	Yes	Ar (CfAe)	72.00 - 6.00	2.000	-0.47	1	1	1.110	1.110		0.001
7/8	C	Yes	Ar (CfAe)	74.00 - 6.00	2.000	0.49	1	1	1.110	1.110		0.001
1/2	A	Yes	Ar (CfAe)	58.00 - 6.00	2.000	0.28	1	1	0.580	0.580		0.000
(Sprint - GPS) LDF1-50A (1/4 FOAM)	C	Yes	Ar (CfAe)	45.00 - 6.00	2.000	0.45	1	1	0.350	0.350		0.000
1 5/8 (T-Mobile)	B	Yes	Ar (CfAe)	108.00 - 6.00	0.000	-0.3	12	6	1.980	1.980		0.001
7/8 (Sprint - Hybriflex)	A	Yes	Ar (CfAe)	143.00 - 6.00	2.000	0.36	3	3	1.110	1.110		0.001
1 5/8" Hybriflex (Verizon)	C	Yes	Ar (CfAe)	98.00 - 6.00	2.000	-0.35	2	2	1.625	1.625		0.000
3 (AT&T)	A	Yes	Ar (CfAe)	143.00 - 6.00	-2.000	0	1	1	3.010	3.010		0.002

<b>tnxTower</b>  <b>URS Corporation</b> 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	<b>Job</b>	152' ROHN SSV Tower	<b>Page</b>	9 of 55
	<b>Project</b>	366 Old Long Ridge Road, Stamford, CT	<b>Date</b>	11:46:06 07/15/14
	<b>Client</b>	Verizon, Sprint and AT&T / S.A. Evaluation	<b>Designed by</b>	MCD

Description	Face or Leg	Allow Shield	Component Type	Placement ft	Face Offset in	Lateral Offset (Frac FW)	#	# Per Row	Clear Spacing in	Width or Diameter in	Perimeter in	Weight klf
1 5/8" Hybriflex (Verizon)	A	Yes	Ar (CfAe)	143.00 - 6.00	2.000	0.32	1	1	1,625	1,625		0,000

### Feed Line/Linear Appurtenances Section Areas

Tower Section	Tower Elevation ft	Face	A <sub>R</sub> ft <sup>2</sup>	A <sub>F</sub> ft <sup>2</sup>	C <sub>AA</sub> In Face ft <sup>2</sup>	C <sub>AA</sub> Out Face ft <sup>2</sup>	Weight K
T1	152.00-140.00	A	9.746	0.000	0.000	0.000	0.060
		B	2.583	0.000	0.000	0.000	0.013
		C	1.110	0.590	0.000	0.000	0.008
T2	140.00-135.00	A	12.394	0.000	0.000	0.000	0.075
		B	1.569	0.000	0.000	0.000	0.008
		C	0.463	0.565	0.000	0.000	0.004
T3	135.00-130.00	A	12.877	0.000	0.000	0.000	0.078
		B	1.754	0.000	0.000	0.000	0.009
		C	2.112	0.737	0.000	0.000	0.015
T4	130.00-125.00	A	12.877	0.000	0.000	0.000	0.078
		B	2.124	0.000	0.000	0.000	0.011
		C	2.112	0.737	0.000	0.000	0.015
T5	125.00-120.00	A	12.974	0.000	0.000	0.000	0.078
		B	2.217	0.000	0.000	0.000	0.012
		C	2.112	0.737	0.000	0.000	0.015
T6	120.00-100.00	A	52.475	0.000	0.000	0.000	0.316
		B	16.787	0.000	0.000	0.000	0.148
		C	8.450	2.949	0.000	0.000	0.061
T7	100.00-80.00	A	54.047	0.000	0.000	0.000	0.325
		B	32.737	0.000	0.000	0.000	0.321
		C	13.325	2.949	0.000	0.000	0.069
T8	80.00-73.33	A	18.108	0.000	0.000	0.000	0.109
		B	11.621	0.000	0.000	0.000	0.111
		C	4.684	0.983	0.000	0.000	0.024
T9	73.33-66.67	A	18.108	0.000	0.000	0.000	0.109
		B	12.760	0.000	0.000	0.000	0.117
		C	5.239	0.983	0.000	0.000	0.027
T10	66.67-60.00	A	18.108	0.000	0.000	0.000	0.109
		B	12.883	0.000	0.000	0.000	0.118
		C	5.239	0.983	0.000	0.000	0.027
T11	60.00-50.00	A	27.549	0.000	0.000	0.000	0.165
		B	19.325	0.000	0.000	0.000	0.177
		C	7.858	1.475	0.000	0.000	0.040
T12	50.00-40.00	A	27.646	0.000	0.000	0.000	0.166
		B	19.325	0.000	0.000	0.000	0.177
		C	8.004	1.475	0.000	0.000	0.041
T13	40.00-30.00	A	27.646	0.000	0.000	0.000	0.166
		B	19.325	0.000	0.000	0.000	0.177
		C	8.150	1.475	0.000	0.000	0.041
T14	30.00-20.00	A	27.646	0.000	0.000	0.000	0.166
		B	19.325	0.000	0.000	0.000	0.177
		C	8.150	1.475	0.000	0.000	0.041
T15	20.00-15.00	A	13.823	0.000	0.000	0.000	0.083
		B	9.662	0.000	0.000	0.000	0.088
		C	4.075	0.737	0.000	0.000	0.020
T16	15.00-10.00	A	13.823	0.000	0.000	0.000	0.083
		B	9.662	0.000	0.000	0.000	0.088
		C	4.075	0.737	0.000	0.000	0.020

<b>tnxTower</b>  <b>URS Corporation</b> 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	<b>Job</b>	152' ROHN SSV Tower	<b>Page</b>	10 of 55
	<b>Project</b>	366 Old Long Ridge Road, Stamford, CT	<b>Date</b>	11:46:06 07/15/14
	<b>Client</b>	Verizon, Sprint and AT&T / S.A. Evaluation	<b>Designed by</b>	MCD

Tower Section	Tower Elevation ft	Face	A <sub>R</sub> ft <sup>2</sup>	A <sub>F</sub> ft <sup>2</sup>	C <sub>AA</sub> In Face ft <sup>2</sup>	C <sub>AA</sub> Out Face ft <sup>2</sup>	Weight K
T17	10.00-0.00	A	11.058	0.000	0.000	0.000	0.066
		B	7.730	0.000	0.000	0.000	0.071
		C	3.260	0.590	0.000	0.000	0.016

**Feed Line/Linear Appurtenances Section Areas - With Ice**

Tower Section	Tower Elevation ft	Face or Leg	Ice Thickness in	A <sub>R</sub> ft <sup>2</sup>	A <sub>F</sub> ft <sup>2</sup>	C <sub>AA</sub> In Face ft <sup>2</sup>	C <sub>AA</sub> Out Face ft <sup>2</sup>	Weight K
T1	152.00-140.00	A	0.500	14.913	0.000	0.000	0.000	0.150
		B		4.250	0.000	0.000	0.000	0.038
		C		2.110	1.257	0.000	0.000	0.029
T2	140.00-135.00	A	0.500	19.060	0.000	0.000	0.000	0.191
		B		2.652	0.000	0.000	0.000	0.024
		C		0.879	1.204	0.000	0.000	0.018
T3	135.00-130.00	A	0.500	19.719	0.483	0.000	0.000	0.199
		B		3.004	0.000	0.000	0.000	0.027
		C		3.363	1.571	0.000	0.000	0.047
T4	130.00-125.00	A	0.500	19.719	0.483	0.000	0.000	0.199
		B		3.708	0.000	0.000	0.000	0.033
		C		3.363	1.571	0.000	0.000	0.047
T5	125.00-120.00	A	0.500	19.982	0.483	0.000	0.000	0.201
		B		3.883	0.000	0.000	0.000	0.034
		C		3.363	1.571	0.000	0.000	0.047
T6	120.00-100.00	A	0.500	81.508	1.933	0.000	0.000	0.816
		B		27.453	0.000	0.000	0.000	0.383
		C		13.450	6.283	0.000	0.000	0.187
T7	100.00-80.00	A	0.500	84.498	1.933	0.000	0.000	0.842
		B		53.070	0.000	0.000	0.000	0.818
		C		21.325	6.283	0.000	0.000	0.242
T8	80.00-73.33	A	0.500	28.342	0.644	0.000	0.000	0.282
		B		18.982	0.000	0.000	0.000	0.284
		C		7.517	2.094	0.000	0.000	0.084
T9	73.33-66.67	A	0.500	28.342	0.644	0.000	0.000	0.282
		B		20.982	0.000	0.000	0.000	0.302
		C		8.572	2.094	0.000	0.000	0.093
T10	66.67-60.00	A	0.500	28.342	0.644	0.000	0.000	0.282
		B		21.217	0.000	0.000	0.000	0.304
		C		8.572	2.094	0.000	0.000	0.093
T11	60.00-50.00	A	0.500	43.566	0.967	0.000	0.000	0.430
		B		31.825	0.000	0.000	0.000	0.455
		C		12.858	3.141	0.000	0.000	0.139
T12	50.00-40.00	A	0.500	43.829	0.967	0.000	0.000	0.432
		B		31.825	0.000	0.000	0.000	0.455
		C		13.421	3.141	0.000	0.000	0.142
T13	40.00-30.00	A	0.500	43.829	0.967	0.000	0.000	0.432
		B		31.825	0.000	0.000	0.000	0.455
		C		13.983	3.141	0.000	0.000	0.145
T14	30.00-20.00	A	0.500	43.829	0.967	0.000	0.000	0.432
		B		31.825	0.000	0.000	0.000	0.455
		C		13.983	3.141	0.000	0.000	0.145
T15	20.00-15.00	A	0.500	21.915	0.483	0.000	0.000	0.216
		B		15.913	0.000	0.000	0.000	0.228
		C		6.992	1.571	0.000	0.000	0.072
T16	15.00-10.00	A	0.500	21.915	0.483	0.000	0.000	0.216
		B		15.913	0.000	0.000	0.000	0.228
		C		6.992	1.571	0.000	0.000	0.072
T17	10.00-0.00	A	0.500	17.532	0.387	0.000	0.000	0.173

<b>tnxTower</b>  <b>URS Corporation</b> 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	<b>Job</b> 152' ROHN SSV Tower	<b>Page</b> 11 of 55
	<b>Project</b> 366 Old Long Ridge Road, Stamford, CT	<b>Date</b> 11:46:06 07/15/14
	<b>Client</b> Verizon, Sprint and AT&T / S.A. Evaluation	<b>Designed by</b> MCD

Tower Section	Tower Elevation ft	Face or Leg	Ice Thickness in	$A_R$ ft <sup>2</sup>	$A_F$ ft <sup>2</sup>	$C_{AA}$ In Face ft <sup>2</sup>	$C_{AA}$ Out Face ft <sup>2</sup>	Weight K
		B		12.730	0.000	0.000	0.000	0.182
		C		5.593	1.257	0.000	0.000	0.058

### Feed Line Shielding

Section	Elevation ft	Face	$A_R$ ft <sup>2</sup>	$A_R$ Ice ft <sup>2</sup>	$A_F$ ft <sup>2</sup>	$A_F$ Ice ft <sup>2</sup>
T1	152.00-140.00	A	0.000	0.829	0.847	1.296
		B	0.000	0.236	0.224	0.369
		C	0.000	0.206	0.148	0.321
T2	140.00-135.00	A	0.000	1.097	1.173	1.804
		B	0.000	0.153	0.148	0.251
		C	0.000	0.138	0.097	0.227
T3	135.00-130.00	A	0.000	0.816	0.780	1.224
		B	0.000	0.121	0.106	0.182
		C	0.000	0.216	0.173	0.324
T4	130.00-125.00	A	0.000	0.799	0.764	1.199
		B	0.000	0.147	0.126	0.220
		C	0.000	0.212	0.169	0.318
T5	125.00-120.00	A	0.000	0.796	0.883	1.393
		B	0.000	0.151	0.151	0.264
		C	0.000	0.208	0.194	0.364
T6	120.00-100.00	A	0.000	2.546	3.203	5.093
		B	0.000	0.838	1.025	1.676
		C	0.000	0.653	0.696	1.306
T7	100.00-80.00	A	0.000	3.575	5.927	9.479
		B	0.000	2.195	3.590	5.820
		C	0.000	1.211	1.785	3.210
T8	80.00-73.33	A	0.000	0.815	1.273	2.037
		B	0.000	0.534	0.817	1.334
		C	0.000	0.286	0.398	0.715
T9	73.33-66.67	A	0.000	1.169	1.939	3.103
		B	0.000	0.846	1.366	2.246
		C	0.000	0.452	0.666	1.201
T10	66.67-60.00	A	0.000	1.161	1.927	3.085
		B	0.000	0.850	1.371	2.258
		C	0.000	0.450	0.662	1.194
T11	60.00-50.00	A	0.000	0.888	1.649	2.665
		B	0.000	0.635	1.157	1.905
		C	0.000	0.336	0.559	1.007
T12	50.00-40.00	A	0.000	1.251	2.316	3.752
		B	0.000	0.889	1.619	2.666
		C	0.000	0.486	0.794	1.457
T13	40.00-30.00	A	0.000	1.237	2.290	3.711
		B	0.000	0.879	1.601	2.636
		C	0.000	0.496	0.797	1.488
T14	30.00-20.00	A	0.000	2.823	4.241	6.872
		B	0.000	2.006	2.964	4.882
		C	0.000	1.132	1.476	2.755
T15	20.00-15.00	A	0.000	1.215	1.891	3.064
		B	0.000	0.863	1.322	2.177
		C	0.000	0.487	0.658	1.228
T16	15.00-10.00	A	0.000	0.792	1.566	2.537
		B	0.000	0.562	1.095	1.803
		C	0.000	0.317	0.545	1.017

<b>tnxTower</b>  <b>URS Corporation</b> 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	<b>Job</b> 152' ROHN SSV Tower	<b>Page</b> 12 of 55
	<b>Project</b> 366 Old Long Ridge Road, Stamford, CT	<b>Date</b> 11:46:06 07/15/14
	<b>Client</b> Verizon, Sprint and AT&T / S.A. Evaluation	<b>Designed by</b> MCD

Section	Elevation	Face	$A_R$	$A_R$	$A_F$	$A_F$
	ft		ft <sup>2</sup>	Ice ft <sup>2</sup>	ft <sup>2</sup>	Ice ft <sup>2</sup>
T17	10.00-0.00	A	0.000	0.333	0.719	1.165
		B	0.000	0.237	0.503	0.828
		C	0.000	0.133	0.250	0.467

### Feed Line Center of Pressure

Section	Elevation	$CP_X$	$CP_Z$	$CP_X$	$CP_Z$
	ft	in	in	Ice in	Ice in
T1	152.00-140.00	-1.168	-6.466	-1.039	-6.056
T2	140.00-135.00	-3.510	-9.595	-3.192	-9.377
T3	135.00-130.00	-3.602	-9.703	-3.126	-9.159
T4	130.00-125.00	-3.308	-9.965	-2.696	-9.324
T5	125.00-120.00	-3.395	-9.914	-2.882	-9.288
T6	120.00-100.00	-2.757	-11.477	-2.645	-11.603
T7	100.00-80.00	-0.030	-10.890	0.398	-10.741
T8	80.00-73.33	0.533	-12.636	1.204	-12.438
T9	73.33-66.67	0.548	-10.990	1.057	-10.763
T10	66.67-60.00	0.539	-11.491	1.066	-11.293
T11	60.00-50.00	0.541	-14.249	1.157	-14.566
T12	50.00-40.00	0.354	-13.399	0.747	-13.601
T13	40.00-30.00	0.233	-13.935	0.477	-14.021
T14	30.00-20.00	0.170	-12.079	0.350	-11.682
T15	20.00-15.00	0.158	-12.925	0.360	-12.689
T16	15.00-10.00	0.142	-12.724	0.358	-12.884
T17	10.00-0.00	0.084	-8.205	0.251	-9.099

### Discrete Tower Loads

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert	Azimuth Adjustment	Placement ft	$C_{AA}$ Front ft <sup>2</sup>	$C_{AA}$ Side ft <sup>2</sup>	Weight K	
20' 4-Bay Dipole (Unknown)	C	From Face	0.50	0.0000	162.00	No Ice	3.15	3.15	0.032
			0.000			1/2" Ice	5.67	5.67	0.042
DB563K-CR (Unknown)	B	From Leg	3.00	0.0000	156.70	No Ice	19.01	19.01	0.050
			0.000			1/2" Ice	19.99	19.99	0.163
4'x4" Pipe Mount (Unknown)	C	From Leg	0.50	0.0000	152.00	No Ice	1.32	1.32	0.044
			0.000			1/2" Ice	1.58	1.58	0.057
DB803KHE-YP (Unknown)	A	From Leg	3.00	0.0000	151.25	No Ice	0.55	0.55	0.006
			0.000			1/2" Ice	0.76	0.76	0.011
3' Sidearm (Unknown)	B	From Leg	1.50	0.0000	149.00	No Ice	3.43	3.43	0.089
			0.000			1/2" Ice	4.34	4.34	0.122
Filter Box 22"x22"x6"	B	From Leg	1.50	0.0000	149.00	No Ice	4.71	1.28	0.025

<b>tnxTower</b>  <b>URS Corporation</b> 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	<b>Job</b>	152' ROHN SSV Tower	<b>Page</b>	13 of 55
	<b>Project</b>	366 Old Long Ridge Road, Stamford, CT	<b>Date</b>	11:46:06 07/15/14
	<b>Client</b>	Verizon, Sprint and AT&T / S.A. Evaluation	<b>Designed by</b>	MCD

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment °	Placement ft	C <sub>AA</sub> Front ft <sup>2</sup>	C <sub>AA</sub> Side ft <sup>2</sup>	Weight K
(Unknown)			0.000 0.000			1/2" Ice 5.00	1.47	0.051
3' Sidearm (Unknown)	A	From Leg	1.50 0.000 0.000	0.0000	148.50	No Ice 1/2" Ice 6.60	5.90 6.60	0.130 0.146
Filter Box 20"x6"x8" (Unknown)	A	From Leg	1.50 0.000 0.000	0.0000	148.50	No Ice 1/2" Ice 1.34	1.56 1.74	0.020 0.032
12'x2 1/2" STD Pipe Mount (Unknown)	C	From Face	0.00 0.000 0.000	0.0000	146.00	No Ice 1/2" Ice 4.68	3.45 4.68	0.069 0.095
12' x 3" Dia Omni (Unknown)	C	From Leg	4.00 0.000 0.000	0.0000	144.00	No Ice 1/2" Ice 4.83	3.60 4.83	0.035 0.061
4'x3" Pipe Mount (AT&T)	A	From Leg	0.50 0.000 0.000	0.0000	143.00	No Ice 1/2" Ice 1.36	1.11 1.36	0.030 0.041
4'x3" Pipe Mount (AT&T)	B	From Leg	0.50 0.000 0.000	0.0000	143.00	No Ice 1/2" Ice 1.36	1.11 1.36	0.030 0.041
4'x3" Pipe Mount (AT&T)	C	From Leg	0.50 0.000 0.000	0.0000	143.00	No Ice 1/2" Ice 1.36	1.11 1.36	0.030 0.041
7770 (AT&T)	A	From Leg	1.00 0.000 0.000	0.0000	143.00	No Ice 1/2" Ice 6.31	2.93 3.27	0.035 0.068
7770 (AT&T)	B	From Leg	1.00 0.000 0.000	0.0000	143.00	No Ice 1/2" Ice 6.31	2.93 3.27	0.035 0.068
7770 (AT&T)	C	From Leg	1.00 0.000 0.000	0.0000	143.00	No Ice 1/2" Ice 6.31	2.93 3.27	0.035 0.068
(2) LPG 21401 TMA (AT&T)	A	From Leg	0.50 0.000 0.000	0.0000	143.00	No Ice 1/2" Ice 1.09	0.37 0.48	0.018 0.023
(2) LPG 21401 TMA (AT&T)	B	From Leg	0.50 0.000 0.000	0.0000	143.00	No Ice 1/2" Ice 1.09	0.37 0.48	0.018 0.023
(2) LPG 21401 TMA (AT&T)	C	From Leg	0.50 0.000 0.000	0.0000	143.00	No Ice 1/2" Ice 1.09	0.37 0.48	0.018 0.023
P65-16-XLH-RR (ATT)	A	From Face	1.00 -1.000 0.000	0.0000	143.00	No Ice 1/2" Ice 8.95	4.70 5.15	0.050 0.097
P65-16-XLH-RR (ATT)	B	From Face	1.00 -1.000 0.000	0.0000	143.00	No Ice 1/2" Ice 8.95	4.70 5.15	0.050 0.097
P65-16-XLH-RR (ATT)	C	From Face	1.00 -1.000 0.000	0.0000	143.00	No Ice 1/2" Ice 8.95	4.70 5.15	0.050 0.097
(2) RRUS-11 (ATT)	A	From Leg	1.00 1.000 0.000	0.0000	143.00	No Ice 1/2" Ice 3.17	1.25 1.41	0.055 0.074
(2) RRUS-11 (ATT)	A	From Leg	1.00 1.000 0.000	0.0000	143.00	No Ice 1/2" Ice 3.17	1.25 1.41	0.055 0.074
(2) RRUS-11	A	From Leg	1.00	0.0000	143.00	No Ice	1.25	0.055

<b>tnxTower</b>  <b>URS Corporation</b> 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	<b>Job</b>	152' ROHN SSV Tower	<b>Page</b>	14 of 55
	<b>Project</b>	366 Old Long Ridge Road, Stamford, CT	<b>Date</b>	11:46:06 07/15/14
	<b>Client</b>	Verizon, Sprint and AT&T / S.A. Evaluation	<b>Designed by</b>	MCD

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment °	Placement ft	C <sub>AA</sub> Front ft <sup>2</sup>	C <sub>AA</sub> Side ft <sup>2</sup>	Weight K	
(ATT)			1.000 0.000			1/2" Ice 3.17	1.41	0.074	
4'x3" Pipe Mount (AT&T)	A	From Leg	0.08 1.000 0.000	0.0000	143.00	No Ice 1/2" Ice 1.36	1.11 1.36	0.030 0.041	
4'x3" Pipe Mount (AT&T)	B	From Leg	1.00 1.000 0.000	0.0000	143.00	No Ice 1/2" Ice 1.36	1.11 1.36	0.030 0.041	
4'x3" Pipe Mount (AT&T)	C	From Leg	1.00 1.000 0.000	0.0000	143.00	No Ice 1/2" Ice 1.36	1.11 1.36	0.030 0.041	
4'x4" Pipe Mount (Unknown)	B	From Leg	0.50 0.000 0.000	0.0000	142.00	No Ice 1/2" Ice 1.58	1.32 1.58	0.044 0.057	
DB563K-CR (Unknown)	C	From Leg	4.00 0.000 0.000	0.0000	141.70	No Ice 1/2" Ice 19.99	19.01 19.99	0.050 0.163	
6' x 3" Dia Omni (Unknown)	A	From Leg	3.00 0.000 0.000	0.0000	138.00	No Ice 1/2" Ice 2.13	1.77 2.13	0.020 0.033	
4' Side Mount Standoff (1) (Unknown)	C	From Leg	2.00 0.000 0.000	0.0000	137.00	No Ice 1/2" Ice 4.91	2.72 4.91	0.050 0.089	
4'x4" Pipe Mount (Unknown)	B	From Leg	0.50 0.000 0.000	0.0000	135.00	No Ice 1/2" Ice 1.58	1.32 1.58	0.044 0.057	
DB495-A (Unknown)	C	From Leg	0.00 0.000 0.000	0.0000	135.00	No Ice 1/2" Ice 4.23	2.35 4.23	0.010 0.013	
3' Sidearm (Unknown)	A	From Leg	1.50 0.000 0.000	0.0000	133.50	No Ice 1/2" Ice 6.60	5.90 6.60	0.130 0.146	
4' Side Mount Standoff (1) (Unknown)	C	From Leg	2.00 0.000 0.000	0.0000	133.00	No Ice 1/2" Ice 4.91	2.72 4.91	0.050 0.089	
2" Dia 8' Omni (Unknown)	A	From Leg	4.50 0.000 0.000	0.0000	133.00	No Ice 1/2" Ice 3.03	2.00 3.03	0.005 0.018	
(2) DB980H90E-M (Sprint)	A	From Leg	3.00 0.000 0.000	0.0000	128.00	No Ice 1/2" Ice 4.18	2.19 2.56	0.009 0.029	
(2) DB980H90E-M (Sprint)	B	From Leg	3.00 0.000 0.000	0.0000	128.00	No Ice 1/2" Ice 4.18	2.19 2.56	0.009 0.029	
(2) DB980H90E-M (Sprint)	C	From Leg	3.00 0.000 0.000	0.0000	128.00	No Ice 1/2" Ice 4.18	2.19 2.56	0.009 0.029	
APXV9TM14-120 (Sprint)	A	From Leg	3.00 0.000 0.000	0.0000	128.00	No Ice 1/2" Ice 7.35	3.61 3.97	0.067 0.106	
APXV9TM14-120 (Sprint)	B	From Leg	3.00 0.000 0.000	0.0000	128.00	No Ice 1/2" Ice 7.35	3.61 3.97	0.067 0.106	
APXV9TM14-120 (Sprint)	C	From Leg	3.00 0.000 0.000	0.0000	128.00	No Ice 1/2" Ice 7.35	3.61 3.97	0.067 0.106	
800 MHz Filter	A	From Leg	3.00	0.0000	128.00	No Ice	0.52	0.38	0.005

<b>tnxTower</b>  <b>URS Corporation</b> 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	<b>Job</b>	152' ROHN SSV Tower	<b>Page</b>	15 of 55
	<b>Project</b>	366 Old Long Ridge Road, Stamford, CT	<b>Date</b>	11:46:06 07/15/14
	<b>Client</b>	Verizon, Sprint and AT&T / S.A. Evaluation	<b>Designed by</b>	MCD

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment °	Placement ft	C <sub>AA</sub> Front ft <sup>2</sup>	C <sub>AA</sub> Side ft <sup>2</sup>	Weight K
(Sprint)			0.000 0.000			1/2" Ice 0.65	0.50	0.009
800 MHz Filter (Sprint)	B	From Leg	3.00 0.000 0.000	0.0000	128.00	No Ice 1/2" Ice 0.65	0.38 0.50	0.005 0.009
800 MHz Filter (Sprint)	C	From Leg	3.00 0.000 0.000	0.0000	128.00	No Ice 1/2" Ice 0.65	0.38 0.50	0.005 0.009
RRH (Sprint)	A	From Leg	3.00 0.000 0.000	0.0000	128.00	No Ice 1/2" Ice 2.45	1.23 1.39	0.050 0.067
RRH (Sprint)	B	From Leg	3.00 0.000 0.000	0.0000	128.00	No Ice 1/2" Ice 2.45	1.23 1.39	0.050 0.067
RRH (Sprint)	C	From Leg	3.00 0.000 0.000	0.0000	128.00	No Ice 1/2" Ice 2.45	1.23 1.39	0.050 0.067
DB254-A (Unknown)	C	From Leg	0.00 0.000 0.000	0.0000	122.00	No Ice 1/2" Ice 1.98	1.10 1.98	0.010 0.013
APX16DWV-16DWV-S-E-A CU w/ Mount (T-Mobile)	A	From Leg	0.50 0.000 0.000	0.0000	108.00	No Ice 1/2" Ice 7.13	3.27 3.86	0.073 0.122
TMA (T-Mobile)	A	From Leg	0.25 0.000 0.000	0.0000	108.00	No Ice 1/2" Ice 1.21	0.45 0.57	0.020 0.027
APX16DWV-16DWV-S-E-A CU w/ Mount (T-Mobile)	B	From Leg	0.50 0.000 0.000	0.0000	108.00	No Ice 1/2" Ice 7.13	3.27 3.86	0.073 0.122
TMA (T-Mobile)	B	From Leg	0.25 0.000 0.000	0.0000	108.00	No Ice 1/2" Ice 1.21	0.45 0.57	0.020 0.027
APX16DWV-16DWV-S-E-A CU w/ Mount (T-Mobile)	C	From Leg	0.50 0.000 0.000	0.0000	108.00	No Ice 1/2" Ice 7.13	3.27 3.86	0.073 0.122
TMA (T-Mobile)	C	From Leg	0.25 0.000 0.000	0.0000	108.00	No Ice 1/2" Ice 1.21	0.45 0.57	0.020 0.027
2" Dia 10' Omni (Unknown)	A	From Leg	3.00 0.000 0.000	0.0000	101.00	No Ice 1/2" Ice 3.02	2.00 3.02	0.025 0.041
8' 4-Bay Dipole (Unknown)	B	From Leg	3.00 0.000 0.000	0.0000	101.00	No Ice 1/2" Ice 2.70	1.50 2.70	0.025 0.033
8' 4-Bay Dipole (Unknown)	C	From Leg	3.00 0.000 0.000	0.0000	101.00	No Ice 1/2" Ice 2.70	1.50 2.70	0.025 0.033
20' x 3" Dia Omni (Unknown)	B	From Leg	3.00 0.000 0.000	0.0000	101.00	No Ice 1/2" Ice 8.03	6.00 8.03	0.050 0.093
Valmont 13' Lightweight T-Frame (Verizon)	A	From Leg	1.25 0.000 0.000	0.0000	98.00	No Ice 1/2" Ice 16.80	10.60 16.80	0.255 0.359
Valmont 13' Lightweight T-Frame (Verizon)	B	From Leg	1.25 0.000 0.000	0.0000	98.00	No Ice 1/2" Ice 16.80	10.60 16.80	0.255 0.359
Valmont 13' Lightweight	C	From Leg	1.25 0.000	0.0000	98.00	No Ice	10.60	0.255



<b>tnxTower</b>  <b>URS Corporation</b> 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	<b>Job</b>	152' ROHN SSV Tower	<b>Page</b>	16 of 55
	<b>Project</b>	366 Old Long Ridge Road, Stamford, CT	<b>Date</b>	11:46:06 07/15/14
	<b>Client</b>	Verizon, Sprint and AT&T / S.A. Evaluation	<b>Designed by</b>	MCD

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment °	Placement ft	C <sub>AA</sub> <sub>Front</sub> ft <sup>2</sup>	C <sub>AA</sub> <sub>Side</sub> ft <sup>2</sup>	Weight K
T-Frame (Verizon)			0.000 0.000			1/2" Ice 16,80	16.80	0.359
RRH (Verizon)	A	From Leg	1.25 6.000 0.000	0.0000	98.00	No Ice 1/2" Ice 2.25 2.45	1.23 1.39	0.050 0.067
RRH (Verizon)	B	From Leg	1.25 6.000 0.000	0.0000	98.00	No Ice 1/2" Ice 2.25 2.45	1.23 1.39	0.050 0.067
RRH (Verizon)	C	From Leg	1.25 6.000 0.000	0.0000	98.00	No Ice 1/2" Ice 2.25 2.45	1.23 1.39	0.050 0.067
DB-T1-6Z-8AB-0Z (Verizon)	A	None		0.0000	98.00	No Ice 1/2" Ice 5.35 5.75	2.40 2.72	0.044 0.073
3' Sidearm (Vacant)	A	From Leg	1.50 0.000 0.000	0.0000	95.50	No Ice 1/2" Ice 3.58 5.01	3.58 5.01	0.124 0.167
3' Sidearm (Unknown)	B	From Leg	1.50 0.000 0.000	0.0000	95.50	No Ice 1/2" Ice 3.58 5.01	3.58 5.01	0.124 0.167
3' Sidearm (Unknown)	C	From Leg	1.50 0.000 0.000	0.0000	95.50	No Ice 1/2" Ice 3.58 5.01	3.58 5.01	0.124 0.167
3' Sidearm (Unknown)	A	From Leg	1.50 0.000 0.000	0.0000	94.50	No Ice 1/2" Ice 3.58 5.01	3.58 5.01	0.124 0.167
3' Sidearm (Unknown)	B	From Leg	1.50 0.000 0.000	0.0000	89.50	No Ice 1/2" Ice 3.58 5.01	3.58 5.01	0.124 0.167
4' x 3" DIA Omni (Unknown)	A	From Leg	3.00 0.000 0.000	0.0000	79.00	No Ice 1/2" Ice 1.00 1.25	1.00 1.25	0.015 0.024
8' 2-Bay Dipole (Unknown)	C	From Leg	3.00 0.000 0.000	0.0000	78.00	No Ice 1/2" Ice 1.60 2.88	1.60 2.88	0.018 0.023
3' Sidearm (Unknown)	A	From Leg	1.50 0.000 0.000	0.0000	72.50	No Ice 1/2" Ice 3.58 5.01	3.58 5.01	0.124 0.167
3' Sidearm (Unknown)	C	From Leg	1.50 0.000 0.000	0.0000	72.50	No Ice 1/2" Ice 3.58 5.01	3.58 5.01	0.124 0.167
Scala Yagi w/ Radome (Unknown)	A	From Leg	3.00 0.000 0.000	0.0000	72.00	No Ice 1/2" Ice 2.78 5.00	2.78 5.00	0.016 0.021
GPS (Sprint)	C	From Leg	2.00 0.000 0.000	0.0000	58.00	No Ice 1/2" Ice 1.00 1.50	1.00 1.50	0.010 0.015
2' Sidearm (Sprint)	C	From Leg	1.00 0.000 0.000	0.0000	57.00	No Ice 1/2" Ice 2.09 3.20	2.09 3.20	0.069 0.092
4'x4" Stand-off (Unknown)	C	From Leg	0.50 0.000 0.000	0.0000	44.00	No Ice 1/2" Ice 0.47 0.93	0.47 0.93	0.061 0.066
APXVSPP18-C-A20 w/ Mounting Pipe (Sprint)	A	From Leg	3.00 0.000 0.000	0.0000	128.00	No Ice 1/2" Ice 5.93 6.39	4.61 4.99	0.026 0.066
APXVSPP18-C-A20 w/ Mounting Pipe	B	From Leg	3.00 0.000	0.0000	128.00	No Ice 1/2" Ice 5.93 6.39	4.61 4.99	0.026 0.066

<b>tnxTower</b>  <b>URS Corporation</b> 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	<b>Job</b>	152' ROHN SSV Tower	<b>Page</b>	17 of 55
	<b>Project</b>	366 Old Long Ridge Road, Stamford, CT	<b>Date</b>	11:46:06 07/15/14
	<b>Client</b>	Verizon, Sprint and AT&T / S.A. Evaluation	<b>Designed by</b>	MCD

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment °	Placement ft	C <sub>AA</sub> Front ft <sup>2</sup>	C <sub>AA</sub> Side ft <sup>2</sup>	Weight K	
(Sprint)			0.000						
APXVSP18-C-A20 w/ Mounting Pipe	C	From Leg	3.00 0.000	0.0000	128.00	No Ice 1/2" Ice	5.93 6.39	4.61 4.99	0.026 0.066
(Sprint)			0.000						
(3) 11' Boom Gate w/3 - 2 3/8" Pipe (Tapered)	A	None		0.0000	128.00	No Ice 1/2" Ice	35.30 46.40	35.30 46.40	1.750 2.400
(Sprint)									
RRH	A	From Leg	3.00 0.000	0.0000	128.00	No Ice 1/2" Ice	2.25 2.45	1.23 1.39	0.050 0.067
(Sprint)			0.000						
RRH	B	From Leg	3.00 0.000	0.0000	128.00	No Ice 1/2" Ice	2.25 2.45	1.23 1.39	0.050 0.067
(Sprint)			0.000						
RRH	C	From Leg	3.00 0.000	0.0000	128.00	No Ice 1/2" Ice	2.25 2.45	1.23 1.39	0.050 0.067
(Sprint)			0.000						
LNx-8513DS-VTM (Verizon - LTE)	A	From Leg	3.00 6.000 0.000	0.0000	98.00	No Ice 1/2" Ice	8.38 8.93	5.41 5.86	0.039 0.090
LNx-6514DS-T4M (Verizon - LTE)	B	From Leg	3.00 6.000 0.000	0.0000	98.00	No Ice 1/2" Ice	8.38 8.93	5.41 5.86	0.038 0.089
LNx-6514DS-T4M (Verizon - LTE)	C	From Leg	3.00 6.000 0.000	0.0000	98.00	No Ice 1/2" Ice	8.38 8.93	5.41 5.86	0.038 0.089
RH_2x40-700 (Verizon - LTE)	A	From Leg	3.00 6.000 0.000	0.0000	98.00	No Ice 1/2" Ice	2.12 2.32	1.77 1.97	0.060 0.077
RH_2x40-700 (Verizon - LTE)	B	From Leg	3.00 6.000 0.000	0.0000	98.00	No Ice 1/2" Ice	2.12 2.32	1.77 1.97	0.060 0.077
RH_2x40-700 (Verizon - LTE)	C	From Leg	3.00 6.000 0.000	0.0000	98.00	No Ice 1/2" Ice	2.12 2.32	1.77 1.97	0.060 0.077
LNx-8513DS-VTM (Verizon - 850MHz)	A	From Leg	3.00 3.000 0.000	0.0000	98.00	No Ice 1/2" Ice	8.38 8.93	5.41 5.86	0.039 0.090
LNx-6514DS-T4M (Verizon - 850MHz)	B	From Leg	3.00 3.000 0.000	0.0000	98.00	No Ice 1/2" Ice	8.38 8.93	5.41 5.86	0.038 0.089
LNx-6514DS-T4M (Verizon - 850MHz)	C	From Leg	3.00 3.000 0.000	0.0000	98.00	No Ice 1/2" Ice	8.38 8.93	5.41 5.86	0.038 0.089
HBXX-6517DS-VTM (Verizon - PCS)	A	From Leg	3.00 -3.000 0.000	0.0000	98.00	No Ice 1/2" Ice	8.74 9.31	6.11 6.82	0.058 0.119
HBXX-6517DS-VTM (Verizon - PCS)	B	From Leg	3.00 -3.000 0.000	0.0000	98.00	No Ice 1/2" Ice	8.74 9.31	6.11 6.82	0.058 0.119
HBXX-6517DS-VTM (Verizon - PCS)	C	From Leg	3.00 -3.000 0.000	0.0000	98.00	No Ice 1/2" Ice	8.74 9.31	6.11 6.82	0.058 0.119
Panasonic RRH 1900MHZ (Verizon - PCS)	A	From Leg	3.00 -3.000 0.000	0.0000	98.00	No Ice 1/2" Ice	2.49 2.71	3.06 3.30	0.090 0.117
Panasonic RRH 1900MHZ (Verizon - PCS)	B	From Leg	3.00 -3.000	0.0000	98.00	No Ice 1/2" Ice	2.49 2.71	3.06 3.30	0.090 0.117

<b>tnxTower</b>  <b>URS Corporation</b> 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	<b>Job</b> 152' ROHN SSV Tower	<b>Page</b> 18 of 55
	<b>Project</b> 366 Old Long Ridge Road, Stamford, CT	<b>Date</b> 11:46:06 07/15/14
	<b>Client</b> Verizon, Sprint and AT&T / S.A. Evaluation	<b>Designed by</b> MCD

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C <sub>AA</sub> Front	C <sub>AA</sub> Side	Weight	
			Horz	Vert						
			ft	ft	°	ft	ft <sup>2</sup>	ft <sup>2</sup>	K	
Panasonic RRH 1900MHZ (Verizon - PCS)	C	From Leg	0.000		0.0000	98.00	No Ice	2.49	3.06	0.090
			3.00				1/2" Ice	2.71	3.30	0.117
			-3.000							
HBXX-6517DS-VTM (Verizon - AWS)	A	From Leg	0.000		0.0000	98.00	No Ice	8.74	6.11	0.058
			3.00				1/2" Ice	9.31	6.82	0.119
			-6.000							
HBXX-6517DS-VTM (Verizon - AWS)	B	From Leg	0.000		0.0000	98.00	No Ice	8.74	6.11	0.058
			3.00				1/2" Ice	9.31	6.82	0.119
			-6.000							
HBXX-6517DS-VTM (Verizon - AWS)	C	From Leg	0.000		0.0000	98.00	No Ice	8.74	6.11	0.058
			3.00				1/2" Ice	9.31	6.82	0.119
			-6.000							
RH_2X40-AWS (Verizon - AWS)	A	From Leg	0.000		0.0000	98.00	No Ice	2.52	1.59	0.044
			3.00				1/2" Ice	2.75	1.80	0.061
			-6.000							
RH_2X40-AWS (Verizon - AWS)	B	From Leg	0.000		0.0000	98.00	No Ice	2.52	1.59	0.044
			3.00				1/2" Ice	2.75	1.80	0.061
			-6.000							
RH_2X40-AWS (Verizon - AWS)	C	From Leg	0.000		0.0000	98.00	No Ice	2.52	1.59	0.044
			3.00				1/2" Ice	2.75	1.80	0.061
			-6.000							
DB-T1-6Z-8AB-0Z (Verizon)	A	None	0.000		0.0000	98.00	No Ice	5.35	2.40	0.044
							1/2" Ice	5.75	2.72	0.073

### Dishes

Description	Face or Leg	Dish Type	Offset Type	Offsets:		Azimuth Adjustment	3 dB Beam Width	Elevation	Outside Diameter	Aperture Area	Weight	
				Horz	Vert							
			ft	ft	°	°	ft	ft	ft <sup>2</sup>	K		
4' w/Radome (Unknown)	C	Paraboloid w/Radome	From Leg	0.50		Worst		152.00	4.00	No Ice	12.57	0.140
				0.000						1/2" Ice	13.10	0.282
				0.000								
4' w/Radome (Unknown)	B	Paraboloid w/Radome	From Leg	0.50		Worst		140.00	4.00	No Ice	12.57	0.140
				0.000						1/2" Ice	13.10	0.282
				0.000								
2' w/Radome (Unknown)	B	Paraboloid w/Radome	From Leg	0.50		Worst		136.50	2.00	No Ice	3.14	0.070
				0.000						1/2" Ice	3.41	0.282
				0.000								
1.2M (Unknown)	C	Paraboloid w/o Radome	From Leg	4.00		Worst		45.00	4.00	No Ice	12.17	0.165
				0.000						1/2" Ice	13.09	0.232
				0.000								

### Tower Pressures - No Ice

$$G_H = 1.132$$

<b>tnxTower</b>  <b>URS Corporation</b> 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	<b>Job</b> 152' ROHN SSV Tower	<b>Page</b> 19 of 55
	<b>Project</b> 366 Old Long Ridge Road, Stamford, CT	<b>Date</b> 11:46:06 07/15/14
	<b>Client</b> Verizon, Sprint and AT&T / S.A. Evaluation	<b>Designed by</b> MCD

Section Elevation ft	z ft	$K_z$	$q_z$ ksf	$A_G$ ft <sup>2</sup>	F a c e	$A_F$ ft <sup>2</sup>	$A_R$ ft <sup>2</sup>	$A_{avg}$ ft <sup>2</sup>	Leg %	$C_{AA}$ In Face ft <sup>2</sup>	$C_{AA}$ Out Face ft <sup>2</sup>
T1 152.00-140.00	146.00	1.529	0.028	80.875	A	5.763	14.496	4.750	23.45	0.000	0.000
					B	6.385	7.333		34.62	0.000	0.000
					C	7.052	5.860		36.79	0.000	0.000
T2 140.00-135.00	137.50	1.503	0.028	35.262	A	1.897	14.794	2.400	14.38	0.000	0.000
					B	2.922	3.969		34.83	0.000	0.000
					C	3.538	2.862		37.49	0.000	0.000
T3 135.00-130.00	132.50	1.488	0.028	37.762	A	1.362	15.277	2.400	14.42	0.000	0.000
					B	2.036	4.154		38.77	0.000	0.000
					C	2.707	4.512		33.24	0.000	0.000
T4 130.00-125.00	127.50	1.471	0.027	40.262	A	1.484	15.277	2.400	14.32	0.000	0.000
					B	2.122	4.524		36.11	0.000	0.000
					C	2.816	4.512		32.75	0.000	0.000
T5 125.00-120.00	122.50	1.455	0.027	42.762	A	1.865	15.374	2.400	13.92	0.000	0.000
					B	2.597	4.616		33.27	0.000	0.000
					C	3.291	4.512		30.75	0.000	0.000
T6 120.00-100.00	110.00	1.411	0.026	199.956	A	25.390	52.475	17.420	22.37	0.000	0.000
					B	27.568	16.787		39.27	0.000	0.000
					C	30.846	8.450		44.33	0.000	0.000
T7 100.00-80.00	90.00	1.332	0.025	240.373	A	35.931	54.047	17.421	19.36	0.000	0.000
					B	38.269	32.737		24.53	0.000	0.000
					C	43.023	13.325		30.92	0.000	0.000
T8 80.00-73.33	76.67	1.272	0.024	89.625	A	11.125	18.108	6.544	22.39	0.000	0.000
					B	11.581	11.621		28.21	0.000	0.000
					C	12.983	4.684		37.04	0.000	0.000
T9 73.33-66.67	70.00	1.24	0.023	94.278	A	13.997	18.108	6.544	20.38	0.000	0.000
					B	14.570	12.760		23.95	0.000	0.000
					C	16.253	5.239		30.45	0.000	0.000
T10 66.67-60.00	63.33	1.205	0.022	98.930	A	14.448	18.108	6.544	20.10	0.000	0.000
					B	15.004	12.883		23.47	0.000	0.000
					C	16.696	5.239		29.84	0.000	0.000
T11 60.00-50.00	55.00	1.157	0.021	157.607	A	18.395	27.549	11.261	24.51	0.000	0.000
					B	18.887	19.325		29.47	0.000	0.000
					C	20.960	7.858		39.08	0.000	0.000
T12 50.00-40.00	45.00	1.093	0.020	167.607	A	22.039	27.646	11.261	22.66	0.000	0.000
					B	22.736	19.325		26.77	0.000	0.000
					C	25.035	8.004		34.08	0.000	0.000
T13 40.00-30.00	35.00	1.017	0.019	177.607	A	22.749	27.646	11.261	22.35	0.000	0.000
					B	23.438	19.325		26.33	0.000	0.000
					C	25.716	8.150		33.25	0.000	0.000
T14 30.00-20.00	25.00	1	0.018	187.973	A	27.625	27.646	11.264	20.38	0.000	0.000
					B	28.901	19.325		23.36	0.000	0.000
					C	31.864	8.150		28.15	0.000	0.000
T15 20.00-15.00	17.50	1	0.018	98.650	A	7.352	20.216	6.394	23.19	0.000	0.000
					B	7.921	16.056		26.67	0.000	0.000
					C	9.321	10.469		32.31	0.000	0.000
T16 15.00-10.00	12.50	1	0.018	101.177	A	9.153	20.218	6.395	21.77	0.000	0.000
					B	9.624	16.057		24.90	0.000	0.000
					C	10.911	10.470		29.91	0.000	0.000
T17 10.00-0.00	5.00	1	0.018	209.955	A	26.348	11.058	14.290	38.20	0.000	0.000
					B	26.564	7.730		41.67	0.000	0.000
					C	27.406	3.260		46.60	0.000	0.000

**Tower Pressure - With Ice**

$G_H = 1.132$

<b>tnxTower</b>  <b>URS Corporation</b> 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	<b>Job</b>	152' ROHN SSV Tower	<b>Page</b>	20 of 55
	<b>Project</b>	366 Old Long Ridge Road, Stamford, CT	<b>Date</b>	11:46:06 07/15/14
	<b>Client</b>	Verizon, Sprint and AT&T / S.A. Evaluation	<b>Designed by</b>	MCD

Section Elevation	z	K <sub>Z</sub>	q <sub>z</sub>	t <sub>z</sub>	A <sub>G</sub>	F a e	A <sub>F</sub>	A <sub>R</sub>	A <sub>leg</sub>	Leg %	C <sub>A A A</sub> In Face ft <sup>2</sup>	C <sub>A A A</sub> Out Face ft <sup>2</sup>
ft	ft		ksf	in	ft <sup>2</sup>		ft <sup>2</sup>	ft <sup>2</sup>	ft <sup>2</sup>			
T1 152.00-140.00	146.00	1.529	0.021	0.500	81.875	A	5.314	25.065	6.750	22.22	0.000	0.000
						B	6.240	14.995		31.79	0.000	0.000
						C	7.545	12.885		33.04	0.000	0.000
T2 140.00-135.00	137.50	1.503	0.021	0.500	35.679	A	1.267	23.069	3.235	13.29	0.000	0.000
						B	2.819	7.605		31.03	0.000	0.000
						C	4.047	5.846		32.69	0.000	0.000
T3 135.00-130.00	132.50	1.488	0.021	0.500	38.179	A	1.402	23.566	3.235	12.95	0.000	0.000
						B	1.960	7.546		34.03	0.000	0.000
						C	3.389	7.809		28.88	0.000	0.000
T4 130.00-125.00	127.50	1.471	0.020	0.500	40.679	A	1.532	23.653	3.235	12.84	0.000	0.000
						B	2.028	8.294		31.34	0.000	0.000
						C	3.501	7.884		28.41	0.000	0.000
T5 125.00-120.00	122.50	1.455	0.020	0.500	43.179	A	1.838	23.991	3.235	12.52	0.000	0.000
						B	2.484	8.537		29.35	0.000	0.000
						C	3.955	7.959		27.15	0.000	0.000
T6 120.00-100.00	110.00	1.411	0.020	0.500	201.625	A	27.659	84.548	19.646	17.51	0.000	0.000
						B	29.143	32.202		32.02	0.000	0.000
						C	35.795	18.383		36.26	0.000	0.000
T7 100.00-80.00	90.00	1.332	0.018	0.500	242.042	A	36.539	90.140	19.647	15.51	0.000	0.000
						B	38.265	60.093		19.97	0.000	0.000
						C	47.157	29.332		25.69	0.000	0.000
T8 80.00-73.33	76.67	1.272	0.018	0.500	90.181	A	11.747	29.868	7.286	17.51	0.000	0.000
						B	11.806	20.790		22.35	0.000	0.000
						C	14.520	9.573		30.24	0.000	0.000
T9 73.33-66.67	70.00	1.24	0.017	0.500	94.834	A	14.219	30.710	7.286	16.22	0.000	0.000
						B	14.432	23.674		19.12	0.000	0.000
						C	17.571	11.657		24.93	0.000	0.000
T10 66.67-60.00	63.33	1.205	0.017	0.500	99.487	A	14.677	30.882	7.286	15.99	0.000	0.000
						B	14.859	24.068		18.72	0.000	0.000
						C	18.017	11.824		24.42	0.000	0.000
T11 60.00-50.00	55.00	1.157	0.016	0.500	158.442	A	19.458	45.605	12.374	19.02	0.000	0.000
						B	19.252	34.118		23.19	0.000	0.000
						C	23.290	15.450		31.94	0.000	0.000
T12 50.00-40.00	45.00	1.093	0.015	0.500	168.442	A	22.682	46.943	12.374	17.77	0.000	0.000
						B	22.802	35.301		21.30	0.000	0.000
						C	27.152	17.300		27.84	0.000	0.000
T13 40.00-30.00	35.00	1.017	0.014	0.500	178.442	A	23.408	47.185	12.374	17.53	0.000	0.000
						B	23.516	35.539		20.95	0.000	0.000
						C	27.806	18.080		26.97	0.000	0.000
T14 30.00-20.00	25.00	1	0.014	0.500	188.807	A	27.074	48.891	12.377	16.29	0.000	0.000
						B	28.097	37.704		18.81	0.000	0.000
						C	33.366	20.736		22.88	0.000	0.000
T15 20.00-15.00	17.50	1	0.014	0.500	99.068	A	6.662	31.260	7.228	19.06	0.000	0.000
						B	7.066	25.609		22.12	0.000	0.000
						C	9.585	17.065		27.12	0.000	0.000
T16 15.00-10.00	12.50	1	0.014	0.500	101.594	A	8.665	31.692	7.230	17.91	0.000	0.000
						B	8.916	25.919		20.75	0.000	0.000
						C	11.272	17.244		25.35	0.000	0.000
T17 10.00-0.00	5.00	1	0.014	0.500	210.789	A	27.401	20.849	15.403	31.92	0.000	0.000
						B	27.352	16.144		35.41	0.000	0.000
						C	28.969	9.110		40.45	0.000	0.000

**Tower Pressure - Service**

<b>tnxTower</b>  <b>URS Corporation</b> 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	<b>Job</b>	152' ROHN SSV Tower	<b>Page</b>	21 of 55
	<b>Project</b>	366 Old Long Ridge Road, Stamford, CT	<b>Date</b>	11:46:06 07/15/14
	<b>Client</b>	Verizon, Sprint and AT&T / S.A. Evaluation	<b>Designed by</b>	MCD

$$G_H = 1.132$$

Section Elevation	z	K <sub>Z</sub>	q <sub>z</sub>	A <sub>G</sub>	F a c e	A <sub>F</sub>	A <sub>R</sub>	A <sub>leg</sub>	Leg %	C <sub>A</sub> A <sub>A</sub> In Face ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> Out Face ft <sup>2</sup>
ft	ft		ksf	ft <sup>2</sup>		ft <sup>2</sup>	ft <sup>2</sup>	ft <sup>2</sup>			
T1 152.00-140.00	146.00	1.529	0.010	80.875	A	5.763	14.496	4.750	23.45	0.000	0.000
					B	6.385	7.333		34.62	0.000	0.000
					C	7.052	5.860		36.79	0.000	0.000
T2 140.00-135.00	137.50	1.503	0.010	35.262	A	1.897	14.794	2.400	14.38	0.000	0.000
					B	2.922	3.969		34.83	0.000	0.000
					C	3.538	2.862		37.49	0.000	0.000
T3 135.00-130.00	132.50	1.488	0.010	37.762	A	1.362	15.277	2.400	14.42	0.000	0.000
					B	2.036	4.154		38.77	0.000	0.000
					C	2.707	4.512		33.24	0.000	0.000
T4 130.00-125.00	127.50	1.471	0.009	40.262	A	1.484	15.277	2.400	14.32	0.000	0.000
					B	2.122	4.524		36.11	0.000	0.000
					C	2.816	4.512		32.75	0.000	0.000
T5 125.00-120.00	122.50	1.455	0.009	42.762	A	1.865	15.374	2.400	13.92	0.000	0.000
					B	2.597	4.616		33.27	0.000	0.000
					C	3.291	4.512		30.75	0.000	0.000
T6 120.00-100.00	110.00	1.411	0.009	199.956	A	25.390	52.475	17.420	22.37	0.000	0.000
					B	27.568	16.787		39.27	0.000	0.000
					C	30.846	8.450		44.33	0.000	0.000
T7 100.00-80.00	90.00	1.332	0.009	240.373	A	35.931	54.047	17.421	19.36	0.000	0.000
					B	38.269	32.737		24.53	0.000	0.000
					C	43.023	13.325		30.92	0.000	0.000
T8 80.00-73.33	76.67	1.272	0.008	89.625	A	11.125	18.108	6.544	22.39	0.000	0.000
					B	11.581	11.621		28.21	0.000	0.000
					C	12.983	4.684		37.04	0.000	0.000
T9 73.33-66.67	70.00	1.24	0.008	94.278	A	13.997	18.108	6.544	20.38	0.000	0.000
					B	14.570	12.760		23.95	0.000	0.000
					C	16.253	5.239		30.45	0.000	0.000
T10 66.67-60.00	63.33	1.205	0.008	98.930	A	14.448	18.108	6.544	20.10	0.000	0.000
					B	15.004	12.883		23.47	0.000	0.000
					C	16.696	5.239		29.84	0.000	0.000
T11 60.00-50.00	55.00	1.157	0.007	157.607	A	18.395	27.549	11.261	24.51	0.000	0.000
					B	18.887	19.325		29.47	0.000	0.000
					C	20.960	7.858		39.08	0.000	0.000
T12 50.00-40.00	45.00	1.093	0.007	167.607	A	22.039	27.646	11.261	22.66	0.000	0.000
					B	22.736	19.325		26.77	0.000	0.000
					C	25.035	8.004		34.08	0.000	0.000
T13 40.00-30.00	35.00	1.017	0.007	177.607	A	22.749	27.646	11.261	22.35	0.000	0.000
					B	23.438	19.325		26.33	0.000	0.000
					C	25.716	8.150		33.25	0.000	0.000
T14 30.00-20.00	25.00	1	0.006	187.973	A	27.625	27.646	11.264	20.38	0.000	0.000
					B	28.901	19.325		23.36	0.000	0.000
					C	31.864	8.150		28.15	0.000	0.000
T15 20.00-15.00	17.50	1	0.006	98.650	A	7.352	20.216	6.394	23.19	0.000	0.000
					B	7.921	16.056		26.67	0.000	0.000
					C	9.321	10.469		32.31	0.000	0.000
T16 15.00-10.00	12.50	1	0.006	101.177	A	9.153	20.218	6.395	21.77	0.000	0.000
					B	9.624	16.057		24.90	0.000	0.000
					C	10.911	10.470		29.91	0.000	0.000
T17 10.00-0.00	5.00	1	0.006	209.955	A	26.348	11.058	14.290	38.20	0.000	0.000
					B	26.564	7.730		41.67	0.000	0.000
					C	27.406	3.260		46.60	0.000	0.000

**Tower Forces - No Ice - Wind Normal To Face**

<b>tnxTower</b>  <b>URS Corporation</b> 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	<b>Job</b> 152' ROHN SSV Tower	<b>Page</b> 22 of 55
	<b>Project</b> 366 Old Long Ridge Road, Stamford, CT	<b>Date</b> 11:46:06 07/15/14
	<b>Client</b> Verizon, Sprint and AT&T / S.A. Evaluation	<b>Designed by</b> MCD

Section Elevation	Add Weight	Self Weight	F a c e	e	C <sub>F</sub>	R <sub>R</sub>	D <sub>F</sub>	D <sub>R</sub>	A <sub>E</sub>	F	w	Ctrl, Face
ft	K	K							ft <sup>2</sup>	K	klf	
T1 152.00-140.00	0.081	0.335	A	0.251	2.436	0.602	1	1	14.490	1.131	0.094	A
			B	0.17	2.701	0.585	1	1	10.673			
			C	0.16	2.736	0.583	1	1	10.468			
T2 140.00-135.00	0.088	0.211	A	0.473	1.937	0.684	1	1	12.020	0.733	0.147	A
			B	0.195	2.611	0.589	1	1	5.261			
			C	0.182	2.659	0.587	1	1	5.218			
T3 135.00-130.00	0.102	0.184	A	0.441	1.989	0.669	1	1	11.583	0.718	0.144	A
			B	0.164	2.721	0.584	1	1	4.461			
			C	0.191	2.626	0.589	1	1	5.363			
T4 130.00-125.00	0.105	0.219	A	0.416	2.033	0.658	1	1	11.542	0.723	0.145	A
			B	0.165	2.717	0.584	1	1	4.763			
			C	0.182	2.657	0.587	1	1	5.464			
T5 125.00-120.00	0.106	0.212	A	0.403	2.058	0.653	1	1	11.902	0.746	0.149	A
			B	0.169	2.704	0.585	1	1	5.296			
			C	0.182	2.656	0.587	1	1	5.940			
T6 120.00-100.00	0.525	1.382	A	0.389	2.085	0.647	1	1	59.358	3.657	0.183	A
			B	0.222	2.525	0.595	1	1	37.557			
			C	0.197	2.608	0.59	1	1	35.829			
T7 100.00-80.00	0.716	2.073	A	0.374	2.117	0.641	1	1	70.601	4.170	0.208	A
			B	0.295	2.308	0.615	1	1	58.385			
			C	0.234	2.485	0.598	1	1	50.992			
T8 80.00-73.33	0.244	0.721	A	0.326	2.229	0.624	1	1	22.430	1.332	0.200	A
			B	0.259	2.411	0.604	1	1	18.603			
			C	0.197	2.606	0.59	1	1	15.746			
T9 73.33-66.67	0.253	0.972	A	0.341	2.194	0.629	1	1	25.390	1.446	0.217	A
			B	0.29	2.323	0.613	1	1	22.390			
			C	0.228	2.505	0.597	1	1	19.378			
T10 66.67-60.00	0.254	0.998	A	0.329	2.222	0.625	1	1	25.770	1.445	0.217	A
			B	0.282	2.345	0.611	1	1	22.870			
			C	0.222	2.525	0.595	1	1	19.813			
T11 60.00-50.00	0.383	1.354	A	0.292	2.319	0.613	1	1	35.292	1.983	0.198	A
			B	0.242	2.46	0.6	1	1	30.481			
			C	0.183	2.654	0.587	1	1	25.573			
T12 50.00-40.00	0.384	1.565	A	0.296	2.306	0.615	1	1	39.036	2.060	0.206	A
			B	0.251	2.435	0.602	1	1	34.372			
			C	0.197	2.606	0.59	1	1	29.756			
T13 40.00-30.00	0.384	1.741	A	0.284	2.34	0.611	1	1	39.642	1.976	0.198	A
			B	0.241	2.465	0.6	1	1	35.025			
			C	0.191	2.627	0.589	1	1	30.513			
T14 30.00-20.00	0.384	2.026	A	0.294	2.312	0.614	1	1	44.602	2.160	0.216	A
			B	0.257	2.418	0.604	1	1	40.565			
			C	0.213	2.554	0.593	1	1	36.698			
T15 20.00-15.00	0.192	0.907	A	0.279	2.352	0.61	1	1	19.680	0.970	0.194	A
			B	0.243	2.459	0.6	1	1	17.556			
			C	0.201	2.594	0.591	1	1	15.503			
T16 15.00-10.00	0.192	0.995	A	0.29	2.322	0.613	1	1	21.546	1.048	0.210	A
			B	0.254	2.426	0.603	1	1	19.304			
			C	0.211	2.559	0.593	1	1	17.117			
T17 10.00-0.00	0.154	1.983	A	0.178	2.671	0.586	1	1	32.830	1.836	0.184	A
			B	0.163	2.723	0.584	1	1	31.075			
			C	0.146	2.786	0.581	1	1	29.300			
Sum Weight:	4.545	17.879						OTM	1981.158 kip-ft	28.133		

**Tower Forces - No Ice - Wind 45 To Face**

<b>tnxTower</b>  <b>URS Corporation</b> 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	<b>Job</b> 152' ROHN SSV Tower	<b>Page</b> 23 of 55
	<b>Project</b> 366 Old Long Ridge Road, Stamford, CT	<b>Date</b> 11:46:06 07/15/14
	<b>Client</b> Verizon, Sprint and AT&T / S.A. Evaluation	<b>Designed by</b> MCD

Section Elevation	Add Weight	Self Weight	F a c e	e	C <sub>F</sub>	R <sub>R</sub>	D <sub>F</sub>	D <sub>R</sub>	A <sub>E</sub>	F	w	Ctrl. Face
ft	K	K							ft <sup>2</sup>	K	klf	
T1 152.00-140.00	0.081	0.335	A	0.251	2.436	0.602	0.825	1	13.481	1.052	0.088	A
			B	0.17	2.701	0.585	0.825	1	9.555			
			C	0.16	2.736	0.583	0.825	1	9.234			
T2 140.00-135.00	0.088	0.211	A	0.473	1.937	0.684	0.825	1	11.688	0.713	0.143	A
			B	0.195	2.611	0.589	0.825	1	4.750			
			C	0.182	2.659	0.587	0.825	1	4.599			
T3 135.00-130.00	0.102	0.184	A	0.441	1.989	0.669	0.825	1	11.345	0.703	0.141	A
			B	0.164	2.721	0.584	0.825	1	4.104			
			C	0.191	2.626	0.589	0.825	1	4.889			
T4 130.00-125.00	0.105	0.219	A	0.416	2.033	0.658	0.825	1	11.282	0.707	0.141	A
			B	0.165	2.717	0.584	0.825	1	4.392			
			C	0.182	2.657	0.587	0.825	1	4.972			
T5 125.00-120.00	0.106	0.212	A	0.403	2.058	0.653	0.825	1	11.576	0.726	0.145	A
			B	0.169	2.704	0.585	0.825	1	4.841			
			C	0.182	2.656	0.587	0.825	1	5.364			
T6 120.00-100.00	0.525	1.382	A	0.389	2.085	0.647	0.825	1	54.915	3.383	0.169	A
			B	0.222	2.525	0.595	0.825	1	32.733			
			C	0.197	2.608	0.59	0.825	1	30.431			
T7 100.00-80.00	0.716	2.073	A	0.374	2.117	0.641	0.825	1	64.313	3.798	0.190	A
			B	0.295	2.308	0.615	0.825	1	51.688			
			C	0.234	2.485	0.598	0.825	1	43.463			
T8 80.00-73.33	0.244	0.721	A	0.326	2.229	0.624	0.825	1	20.483	1.216	0.182	A
			B	0.259	2.411	0.604	0.825	1	16.576			
			C	0.197	2.606	0.59	0.825	1	13.474			
T9 73.33-66.67	0.253	0.972	A	0.341	2.194	0.629	0.825	1	22.940	1.307	0.196	A
			B	0.29	2.323	0.613	0.825	1	19.840			
			C	0.228	2.505	0.597	0.825	1	16.534			
T10 66.67-60.00	0.254	0.998	A	0.329	2.222	0.625	0.825	1	23.241	1.303	0.195	A
			B	0.282	2.345	0.611	0.825	1	20.244			
			C	0.222	2.525	0.595	0.825	1	16.892			
T11 60.00-50.00	0.383	1.354	A	0.292	2.319	0.613	0.825	1	32.073	1.802	0.180	A
			B	0.242	2.46	0.6	0.825	1	27.176			
			C	0.183	2.654	0.587	0.825	1	21.905			
T12 50.00-40.00	0.384	1.565	A	0.296	2.306	0.615	0.825	1	35.179	1.856	0.186	A
			B	0.251	2.435	0.602	0.825	1	30.393			
			C	0.197	2.606	0.59	0.825	1	25.375			
T13 40.00-30.00	0.384	1.741	A	0.284	2.34	0.611	0.825	1	35.661	1.777	0.178	A
			B	0.241	2.465	0.6	0.825	1	30.923			
			C	0.191	2.627	0.589	0.825	1	26.013			
T14 30.00-20.00	0.384	2.026	A	0.294	2.312	0.614	0.825	1	39.768	1.926	0.193	A
			B	0.257	2.418	0.604	0.825	1	35.508			
			C	0.213	2.554	0.593	0.825	1	31.122			
T15 20.00-15.00	0.192	0.907	A	0.279	2.352	0.61	0.825	1	18.394	0.906	0.181	A
			B	0.243	2.459	0.6	0.825	1	16.170			
			C	0.201	2.594	0.591	0.825	1	13.872			
T16 15.00-10.00	0.192	0.995	A	0.29	2.322	0.613	0.825	1	19.944	0.970	0.194	A
			B	0.254	2.426	0.603	0.825	1	17.620			
			C	0.211	2.559	0.593	0.825	1	15.208			
T17 10.00-0.00	0.154	1.983	A	0.178	2.671	0.586	0.825	1	28.219	1.578	0.158	A
			B	0.163	2.723	0.584	0.825	1	26.427			
			C	0.146	2.786	0.581	0.825	1	24.504			
Sum Weight:	4.545	17.879						OTM	1833.925 kip-ft	25,724		

**Tower Forces - No Ice - Wind 60 To Face**



<b>tnxTower</b>  <b>URS Corporation</b> 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	<b>Job</b> 152' ROHN SSV Tower	<b>Page</b> 24 of 55
	<b>Project</b> 366 Old Long Ridge Road, Stamford, CT	<b>Date</b> 11:46:06 07/15/14
	<b>Client</b> Verizon, Sprint and AT&T / S.A. Evaluation	<b>Designed by</b> MCD

Section Elevation	Add Weight	Self Weight	F a c e	e	C <sub>F</sub>	R <sub>R</sub>	D <sub>F</sub>	D <sub>R</sub>	A <sub>E</sub>	F	w	Ctrl. Face
ft	K	K							ft <sup>2</sup>	K	klf	
T1 152.00-140.00	0.081	0.335	A	0.251	2.436	0.602	0.8	1	13.337	1,041	0.087	A
			B	0.17	2.701	0.585	0.8	1	9.396			
			C	0.16	2.736	0.583	0.8	1	9.058			
T2 140.00-135.00	0.088	0.211	A	0.473	1.937	0.684	0.8	1	11.641	0.710	0.142	A
			B	0.195	2.611	0.589	0.8	1	4.677			
			C	0.182	2.659	0.587	0.8	1	4.510			
T3 135.00-130.00	0.102	0.184	A	0.441	1.989	0.669	0.8	1	11.311	0.701	0.140	A
			B	0.164	2.721	0.584	0.8	1	4.054			
			C	0.191	2.626	0.589	0.8	1	4.822			
T4 130.00-125.00	0.105	0.219	A	0.416	2.033	0.658	0.8	1	11.245	0.704	0.141	A
			B	0.165	2.717	0.584	0.8	1	4.339			
			C	0.182	2.657	0.587	0.8	1	4.901			
T5 125.00-120.00	0.106	0.212	A	0.403	2.058	0.653	0.8	1	11.529	0.723	0.145	A
			B	0.169	2.704	0.585	0.8	1	4.776			
			C	0.182	2.656	0.587	0.8	1	5.282			
T6 120.00-100.00	0.525	1.382	A	0.389	2.085	0.647	0.8	1	54.281	3,344	0.167	A
			B	0.222	2.525	0.595	0.8	1	32.044			
			C	0.197	2.608	0.59	0.8	1	29.660			
T7 100.00-80.00	0.716	2.073	A	0.374	2.117	0.641	0.8	1	63.415	3,745	0.187	A
			B	0.295	2.308	0.615	0.8	1	50.732			
			C	0.234	2.485	0.598	0.8	1	42.387			
T8 80.00-73.33	0.244	0.721	A	0.326	2.229	0.624	0.8	1	20.205	1,200	0.180	A
			B	0.259	2.411	0.604	0.8	1	16.286			
			C	0.197	2.606	0.59	0.8	1	13.149			
T9 73.33-66.67	0.253	0.972	A	0.341	2.194	0.629	0.8	1	22.591	1,287	0.193	A
			B	0.29	2.323	0.613	0.8	1	19.476			
			C	0.228	2.505	0.597	0.8	1	16.127			
T10 66.67-60.00	0.254	0.998	A	0.329	2.222	0.625	0.8	1	22.880	1,283	0.192	A
			B	0.282	2.345	0.611	0.8	1	19.869			
			C	0.222	2.525	0.595	0.8	1	16.474			
T11 60.00-50.00	0.383	1.354	A	0.292	2.319	0.613	0.8	1	31.613	1,777	0.178	A
			B	0.242	2.46	0.6	0.8	1	26.704			
			C	0.183	2.654	0.587	0.8	1	21.381			
T12 50.00-40.00	0.384	1.565	A	0.296	2.306	0.615	0.8	1	34.628	1,827	0.183	A
			B	0.251	2.435	0.602	0.8	1	29.825			
			C	0.197	2.606	0.59	0.8	1	24.749			
T13 40.00-30.00	0.384	1.741	A	0.284	2.34	0.611	0.8	1	35.092	1,749	0.175	A
			B	0.241	2.465	0.6	0.8	1	30.337			
			C	0.191	2.627	0.589	0.8	1	25.370			
T14 30.00-20.00	0.384	2.026	A	0.294	2.312	0.614	0.8	1	39.077	1,892	0.189	A
			B	0.257	2.418	0.604	0.8	1	34.785			
			C	0.213	2.554	0.593	0.8	1	30.325			
T15 20.00-15.00	0.192	0.907	A	0.279	2.352	0.61	0.8	1	18.210	0.897	0.179	A
			B	0.243	2.459	0.6	0.8	1	15.972			
			C	0.201	2.594	0.591	0.8	1	13.639			
T16 15.00-10.00	0.192	0.995	A	0.29	2.322	0.613	0.8	1	19.715	0.959	0.192	A
			B	0.254	2.426	0.603	0.8	1	17.379			
			C	0.211	2.559	0.593	0.8	1	14.935			
T17 10.00-0.00	0.154	1.983	A	0.178	2.671	0.586	0.8	1	27.560	1,542	0.154	A
			B	0.163	2.723	0.584	0.8	1	25.763			
			C	0.146	2.786	0.581	0.8	1	23.819			
Sum Weight:	4.545	17.879						OTM	1812.892 kip-ft	25.380		

**Tower Forces - No Ice - Wind 90 To Face**

<b>tnxTower</b>  <b>URS Corporation</b> 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	<b>Job</b> 152' ROHN SSV Tower	<b>Page</b> 25 of 55
	<b>Project</b> 366 Old Long Ridge Road, Stamford, CT	<b>Date</b> 11:46:06 07/15/14
	<b>Client</b> Verizon, Sprint and AT&T / S.A. Evaluation	<b>Designed by</b> MCD

Section Elevation	Add Weight	Self Weight	F a c e	e	C <sub>F</sub>	R <sub>R</sub>	D <sub>F</sub>	D <sub>R</sub>	A <sub>E</sub>	F	w	Ctrl. Face
ft	K	K							ft <sup>2</sup>	K	klf	
T1 152.00-140.00	0.081	0.335	A	0.251	2.436	0.602	0.85	1	13.625	1.063	0.089	A
			B	0.17	2.701	0.585	0.85	1	9.715			
			C	0.16	2.736	0.583	0.85	1	9.410			
T2 140.00-135.00	0.088	0.211	A	0.473	1.937	0.684	0.85	1	11.736	0.716	0.143	A
			B	0.195	2.611	0.589	0.85	1	4.823			
			C	0.182	2.659	0.587	0.85	1	4.687			
T3 135.00-130.00	0.102	0.184	A	0.441	1.989	0.669	0.85	1	11.379	0.705	0.141	A
			B	0.164	2.721	0.584	0.85	1	4.155			
			C	0.191	2.626	0.589	0.85	1	4.957			
T4 130.00-125.00	0.105	0.219	A	0.416	2.033	0.658	0.85	1	11.319	0.709	0.142	A
			B	0.165	2.717	0.584	0.85	1	4.445			
			C	0.182	2.657	0.587	0.85	1	5.042			
T5 125.00-120.00	0.106	0.212	A	0.403	2.058	0.653	0.85	1	11.622	0.729	0.146	A
			B	0.169	2.704	0.585	0.85	1	4.906			
			C	0.182	2.656	0.587	0.85	1	5.446			
T6 120.00-100.00	0.525	1.382	A	0.389	2.085	0.647	0.85	1	55.550	3.422	0.171	A
			B	0.222	2.525	0.595	0.85	1	33.422			
			C	0.197	2.608	0.59	0.85	1	31.202			
T7 100.00-80.00	0.716	2.073	A	0.374	2.117	0.641	0.85	1	65.211	3.851	0.193	A
			B	0.295	2.308	0.615	0.85	1	52.645			
			C	0.234	2.485	0.598	0.85	1	44.538			
T8 80.00-73.33	0.244	0.721	A	0.326	2.229	0.624	0.85	1	20.761	1.233	0.185	A
			B	0.259	2.411	0.604	0.85	1	16.865			
			C	0.197	2.606	0.59	0.85	1	13.798			
T9 73.33-66.67	0.253	0.972	A	0.341	2.194	0.629	0.85	1	23.290	1.327	0.199	A
			B	0.29	2.323	0.613	0.85	1	20.204			
			C	0.228	2.505	0.597	0.85	1	16.940			
T10 66.67-60.00	0.254	0.998	A	0.329	2.222	0.625	0.85	1	23.603	1.323	0.198	A
			B	0.282	2.345	0.611	0.85	1	20.619			
			C	0.222	2.525	0.595	0.85	1	17.309			
T11 60.00-50.00	0.383	1.354	A	0.292	2.319	0.613	0.85	1	32.532	1.828	0.183	A
			B	0.242	2.46	0.6	0.85	1	27.648			
			C	0.183	2.654	0.587	0.85	1	22.429			
T12 50.00-40.00	0.384	1.565	A	0.296	2.306	0.615	0.85	1	35.730	1.885	0.189	A
			B	0.251	2.435	0.602	0.85	1	30.962			
			C	0.197	2.606	0.59	0.85	1	26.001			
T13 40.00-30.00	0.384	1.741	A	0.284	2.34	0.611	0.85	1	36.230	1.806	0.181	A
			B	0.241	2.465	0.6	0.85	1	31.509			
			C	0.191	2.627	0.589	0.85	1	26.656			
T14 30.00-20.00	0.384	2.026	A	0.294	2.312	0.614	0.85	1	40.458	1.959	0.196	A
			B	0.257	2.418	0.604	0.85	1	36.230			
			C	0.213	2.554	0.593	0.85	1	31.918			
T15 20.00-15.00	0.192	0.907	A	0.279	2.352	0.61	0.85	1	18.577	0.915	0.183	A
			B	0.243	2.459	0.6	0.85	1	16.368			
			C	0.201	2.594	0.591	0.85	1	14.105			
T16 15.00-10.00	0.192	0.995	A	0.29	2.322	0.613	0.85	1	20.173	0.981	0.196	A
			B	0.254	2.426	0.603	0.85	1	17.861			
			C	0.211	2.559	0.593	0.85	1	15.480			
T17 10.00-0.00	0.154	1.983	A	0.178	2.671	0.586	0.85	1	28.878	1.615	0.162	A
			B	0.163	2.723	0.584	0.85	1	27.091			
			C	0.146	2.786	0.581	0.85	1	25.189			
Sum Weight:	4.545	17.879						OTM	1854.958 kip-ft	26.068		

**Tower Forces - With Ice - Wind Normal To Face**

<b>tnxTower</b>  <b>URS Corporation</b> 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	<b>Job</b> 152' ROHN SSV Tower	<b>Page</b> 26 of 55
	<b>Project</b> 366 Old Long Ridge Road, Stamford, CT	<b>Date</b> 11:46:06 07/15/14
	<b>Client</b> Verizon, Sprint and AT&T / S.A. Evaluation	<b>Designed by</b> MCD

Section Elevation	Add Weight	Self Weight	F a c e	e	C <sub>F</sub>	R <sub>R</sub>	D <sub>F</sub>	D <sub>R</sub>	A <sub>E</sub>	F	w	Ctrl. Face
ft	K	K							ft <sup>2</sup>	K	klf	
T1 152.00-140.00	0.218	0.649	A	0.371	2.124	0.64	1	1	21,361	1.090	0.091	A
			B	0.259	2.41	0.604	1	1	15,302			
			C	0.25	2.439	0.602	1	1	15,298			
T2 140.00-135.00	0.232	0.358	A	0.682	1.776	0.807	1	1	19,890	0.834	0.167	A
			B	0.292	2.317	0.614	1	1	7,485			
			C	0.277	2.358	0.609	1	1	7,609			
T3 135.00-130.00	0.273	0.298	A	0.654	1.78	0.788	1	1	19,975	0.831	0.166	A
			B	0.249	2.441	0.602	1	1	6,500			
			C	0.293	2.314	0.614	1	1	8,183			
T4 130.00-125.00	0.279	0.336	A	0.619	1.793	0.765	1	1	19,638	0.814	0.163	A
			B	0.254	2.426	0.603	1	1	7,028			
			C	0.28	2.351	0.61	1	1	8,310			
T5 125.00-120.00	0.282	0.344	A	0.598	1.805	0.752	1	1	19,891	0.820	0.164	A
			B	0.255	2.422	0.603	1	1	7,634			
			C	0.276	2.362	0.609	1	1	8,800			
T6 120.00-100.00	1.386	2.086	A	0.557	1.837	0.728	1	1	89,206	3,632	0.182	A
			B	0.304	2.285	0.617	1	1	49,018			
			C	0.269	2.383	0.607	1	1	46,950			
T7 100.00-80.00	1.901	3.212	A	0.523	1.871	0.71	1	1	100,512	3,936	0.197	A
			B	0.406	2.052	0.654	1	1	77,579			
			C	0.316	2.254	0.621	1	1	65,370			
T8 80.00-73.33	0.649	1.038	A	0.461	1.955	0.679	1	1	32,016	1.251	0.188	A
			B	0.361	2.145	0.637	1	1	25,042			
			C	0.267	2.387	0.606	1	1	20,325			
T9 73.33-66.67	0.676	1.409	A	0.474	1.936	0.684	1	1	35,240	1.329	0.199	A
			B	0.402	2.06	0.652	1	1	29,875			
			C	0.308	2.274	0.618	1	1	24,780			
T10 66.67-60.00	0.678	1.450	A	0.458	1.961	0.677	1	1	35,582	1.320	0.198	A
			B	0.391	2.082	0.648	1	1	30,457			
			C	0.3	2.296	0.616	1	1	25,299			
T11 60.00-50.00	1.025	1.856	A	0.411	2.043	0.656	1	1	49,375	1.834	0.183	A
			B	0.337	2.203	0.628	1	1	40,673			
			C	0.245	2.454	0.6	1	1	32,568			
T12 50.00-40.00	1.030	2.213	A	0.413	2.038	0.657	1	1	53,530	1.873	0.187	A
			B	0.345	2.183	0.631	1	1	45,066			
			C	0.264	2.396	0.606	1	1	37,627			
T13 40.00-30.00	1.032	2.411	A	0.396	2.073	0.65	1	1	54,070	1.790	0.179	A
			B	0.331	2.217	0.626	1	1	45,758			
			C	0.257	2.416	0.604	1	1	38,721			
T14 30.00-20.00	1.032	2.946	A	0.402	2.059	0.653	1	1	58,978	1.908	0.191	A
			B	0.349	2.175	0.632	1	1	51,924			
			C	0.287	2.332	0.612	1	1	46,054			
T15 20.00-15.00	0.516	1.349	A	0.383	2.099	0.645	1	1	26,816	0.884	0.177	A
			B	0.33	2.22	0.625	1	1	23,084			
			C	0.269	2.382	0.607	1	1	19,941			
T16 15.00-10.00	0.516	1.476	A	0.397	2.07	0.65	1	1	29,280	0.952	0.190	A
			B	0.343	2.188	0.63	1	1	25,244			
			C	0.281	2.349	0.61	1	1	21,794			
T17 10.00-0.00	0.413	2.705	A	0.229	2.502	0.597	1	1	39,842	1.566	0.157	A
			B	0.206	2.575	0.592	1	1	36,905			
			C	0.181	2.662	0.587	1	1	34,314			
Sum Weight:	12.139	26.137						OTM	1945.221 kip-ft	26.664		

**Tower Forces - With Ice - Wind 45 To Face**

<b>tnxTower</b>  <b>URS Corporation</b> 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	<b>Job</b> 152' ROHN SSV Tower	<b>Page</b> 27 of 55
	<b>Project</b> 366 Old Long Ridge Road, Stamford, CT	<b>Date</b> 11:46:06 07/15/14
	<b>Client</b> Verizon, Sprint and AT&T / S.A. Evaluation	<b>Designed by</b> MCD

Section Elevation	Add Weight	Self Weight	F a c e	e	C <sub>F</sub>	R <sub>R</sub>	D <sub>F</sub>	D <sub>R</sub>	A <sub>E</sub>	F	w	Ctrl. Face
ft	K	K							ft <sup>2</sup>	K	klf	
152.00-140.00	0.218	0.649	A	0.371	2.124	0.64	0.825	1	20,431	1.043	0.087	A
			B	0.259	2.41	0.604	0.825	1	14.210			
			C	0.25	2.439	0.602	0.825	1	13.978			
140.00-135.00	0.232	0.358	A	0.682	1.776	0.807	0.825	1	19,668	0.825	0.165	A
			B	0.292	2.317	0.614	0.825	1	6.992			
			C	0.277	2.358	0.609	0.825	1	6.901			
135.00-130.00	0.273	0.298	A	0.654	1.78	0.788	0.825	1	19,729	0.821	0.164	A
			B	0.249	2.441	0.602	0.825	1	6.157			
			C	0.293	2.314	0.614	0.825	1	7.590			
130.00-125.00	0.279	0.336	A	0.619	1.793	0.765	0.825	1	19,370	0.803	0.161	A
			B	0.254	2.426	0.603	0.825	1	6.673			
			C	0.28	2.351	0.61	0.825	1	7.697			
125.00-120.00	0.282	0.344	A	0.598	1.805	0.752	0.825	1	19,570	0.807	0.161	A
			B	0.255	2.422	0.603	0.825	1	7.199			
			C	0.276	2.362	0.609	0.825	1	8.108			
120.00-100.00	1.386	2.086	A	0.557	1.837	0.728	0.825	1	84,365	3,435	0.172	A
			B	0.304	2.285	0.617	0.825	1	43,918			
			C	0.269	2.383	0.607	0.825	1	40,686			
100.00-80.00	1.901	3.212	A	0.523	1.871	0.71	0.825	1	94,118	3,685	0.184	A
			B	0.406	2.052	0.654	0.825	1	70,882			
			C	0.316	2.254	0.621	0.825	1	57,118			
80.00-73.33	0.649	1.038	A	0.461	1.955	0.679	0.825	1	29,960	1,171	0.176	A
			B	0.361	2.145	0.637	0.825	1	22,975			
			C	0.267	2.387	0.606	0.825	1	17,784			
73.33-66.67	0.676	1.409	A	0.474	1.936	0.684	0.825	1	32,751	1,235	0.185	A
			B	0.402	2.06	0.652	0.825	1	27,349			
			C	0.308	2.274	0.618	0.825	1	21,705			
66.67-60.00	0.678	1.450	A	0.458	1.961	0.677	0.825	1	33,014	1,225	0.184	A
			B	0.391	2.082	0.648	0.825	1	27,857			
			C	0.3	2.296	0.616	0.825	1	22,146			
60.00-50.00	1.025	1.856	A	0.411	2.043	0.656	0.825	1	45,970	1,707	0.171	A
			B	0.337	2.203	0.628	0.825	1	37,304			
			C	0.245	2.454	0.6	0.825	1	28,492			
50.00-40.00	1.030	2.213	A	0.413	2.038	0.657	0.825	1	49,561	1,734	0.173	A
			B	0.345	2.183	0.631	0.825	1	41,076			
			C	0.264	2.396	0.606	0.825	1	32,876			
40.00-30.00	1.032	2.411	A	0.396	2.073	0.65	0.825	1	49,973	1,655	0.165	A
			B	0.331	2.217	0.626	0.825	1	41,643			
			C	0.257	2.416	0.604	0.825	1	33,855			
30.00-20.00	1.032	2.946	A	0.402	2.059	0.653	0.825	1	54,240	1,755	0.175	A
			B	0.349	2.175	0.632	0.825	1	47,007			
			C	0.287	2.332	0.612	0.825	1	40,215			
20.00-15.00	0.516	1.349	A	0.383	2.099	0.645	0.825	1	25,650	0.846	0.169	A
			B	0.33	2.22	0.625	0.825	1	21,847			
			C	0.269	2.382	0.607	0.825	1	18,264			
15.00-10.00	0.516	1.476	A	0.397	2.07	0.65	0.825	1	27,763	0.903	0.181	A
			B	0.343	2.188	0.63	0.825	1	23,684			
			C	0.281	2.349	0.61	0.825	1	19,821			
10.00-0.00	0.413	2.705	A	0.229	2.502	0.597	0.825	1	35,047	1,378	0.138	A
			B	0.206	2.575	0.592	0.825	1	32,118			
			C	0.181	2.662	0.587	0.825	1	29,244			
Sum Weight:	12,139	26,137						OTM	1845.630 kip-ft	25.026		

**Tower Forces - With Ice - Wind 60 To Face**

<b>tnxTower</b>  <b>URS Corporation</b> 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	<b>Job</b>	152' ROHN SSV Tower	<b>Page</b>	28 of 55
	<b>Project</b>	366 Old Long Ridge Road, Stamford, CT	<b>Date</b>	11:46:06 07/15/14
	<b>Client</b>	Verizon, Sprint and AT&T / S.A. Evaluation	<b>Designed by</b>	MCD

Section Elevation	Add Weight	Self Weight	F a c e	e	C <sub>F</sub>	R <sub>R</sub>	D <sub>F</sub>	D <sub>R</sub>	A <sub>E</sub>	F	w	Ctrl. Face
ft	K	K							ft <sup>2</sup>	K	klf	
T1 152.00-140.00	0.218	0.649	A	0.371	2.124	0.64	0.8	1	20,298	1,036	0.086	A
			B	0.259	2.41	0.604	0.8	1	14,054			
			C	0.25	2.439	0.602	0.8	1	13,790			
T2 140.00-135.00	0.232	0.358	A	0.682	1.776	0.807	0.8	1	19,636	0.824	0.165	A
			B	0.292	2.317	0.614	0.8	1	6,922			
			C	0.277	2.358	0.609	0.8	1	6,799			
T3 135.00-130.00	0.273	0.298	A	0.654	1.78	0.788	0.8	1	19,694	0.819	0.164	A
			B	0.249	2.441	0.602	0.8	1	6,108			
			C	0.293	2.314	0.614	0.8	1	7,505			
T4 130.00-125.00	0.279	0.336	A	0.619	1.793	0.765	0.8	1	19,331	0.801	0.160	A
			B	0.254	2.426	0.603	0.8	1	6,622			
			C	0.28	2.351	0.61	0.8	1	7,610			
T5 125.00-120.00	0.282	0.344	A	0.598	1.805	0.752	0.8	1	19,524	0.805	0.161	A
			B	0.255	2.422	0.603	0.8	1	7,137			
			C	0.276	2.362	0.609	0.8	1	8,009			
T6 120.00-100.00	1.386	2.086	A	0.557	1.837	0.728	0.8	1	83,674	3.407	0.170	A
			B	0.304	2.285	0.617	0.8	1	43,189			
			C	0.269	2.383	0.607	0.8	1	39,791			
T7 100.00-80.00	1.901	3.212	A	0.523	1.871	0.71	0.8	1	93,204	3,650	0.182	A
			B	0.406	2.052	0.654	0.8	1	69,926			
			C	0.316	2.254	0.621	0.8	1	55,939			
T8 80.00-73.33	0.649	1.038	A	0.461	1.955	0.679	0.8	1	29,667	1,159	0.174	A
			B	0.361	2.145	0.637	0.8	1	22,680			
			C	0.267	2.387	0.606	0.8	1	17,421			
T9 73.33-66.67	0.676	1.409	A	0.474	1.936	0.684	0.8	1	32,396	1,222	0.183	A
			B	0.402	2.06	0.652	0.8	1	26,989			
			C	0.308	2.274	0.618	0.8	1	21,266			
T10 66.67-60.00	0.678	1.450	A	0.458	1.961	0.677	0.8	1	32,647	1,211	0.182	A
			B	0.391	2.082	0.648	0.8	1	27,485			
			C	0.3	2.296	0.616	0.8	1	21,696			
T11 60.00-50.00	1.025	1.856	A	0.411	2.043	0.656	0.8	1	45,483	1,689	0.169	A
			B	0.337	2.203	0.628	0.8	1	36,823			
			C	0.245	2.454	0.6	0.8	1	27,910			
T12 50.00-40.00	1.030	2.213	A	0.413	2.038	0.657	0.8	1	48,994	1,714	0.171	A
			B	0.345	2.183	0.631	0.8	1	40,505			
			C	0.264	2.396	0.606	0.8	1	32,197			
T13 40.00-30.00	1.032	2.411	A	0.396	2.073	0.65	0.8	1	49,388	1,635	0.164	A
			B	0.331	2.217	0.626	0.8	1	41,055			
			C	0.257	2.416	0.604	0.8	1	33,160			
T14 30.00-20.00	1.032	2.946	A	0.402	2.059	0.653	0.8	1	53,563	1,733	0.173	A
			B	0.349	2.175	0.632	0.8	1	46,305			
			C	0.287	2.332	0.612	0.8	1	39,381			
T15 20.00-15.00	0.516	1.349	A	0.383	2.099	0.645	0.8	1	25,484	0.840	0.168	A
			B	0.33	2.22	0.625	0.8	1	21,671			
			C	0.269	2.382	0.607	0.8	1	18,024			
T16 15.00-10.00	0.516	1.476	A	0.397	2.07	0.65	0.8	1	27,547	0.896	0.179	A
			B	0.343	2.188	0.63	0.8	1	23,461			
			C	0.281	2.349	0.61	0.8	1	19,539			
T17 10.00-0.00	0.413	2.705	A	0.229	2.502	0.597	0.8	1	34,362	1,351	0.135	A
			B	0.206	2.575	0.592	0.8	1	31,434			
			C	0.181	2.662	0.587	0.8	1	28,520			
Sum Weight:	12.139	26.137						OTM	1831.402 kip-ft	24.792		

**Tower Forces - With Ice - Wind 90 To Face**

<b>tnxTower</b>  <b>URS Corporation</b> 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	<b>Job</b>	152' ROHN SSV Tower	<b>Page</b>	29 of 55
	<b>Project</b>	366 Old Long Ridge Road, Stamford, CT	<b>Date</b>	11:46:06 07/15/14
	<b>Client</b>	Verizon, Sprint and AT&T / S.A. Evaluation	<b>Designed by</b>	MCD

Section Elevation	Add Weight	Self Weight	F a c e	e	C <sub>F</sub>	R <sub>R</sub>	D <sub>F</sub>	D <sub>R</sub>	A <sub>E</sub>	F	w	Ctrl. Face
ft	K	K							ft <sup>2</sup>	K	klf	
T1 152.00-140.00	0.218	0.649	A	0.371	2.124	0.64	0.85	1	20.564	1.049	0.087	A
			B	0.259	2.41	0.604	0.85	1	14.366			
			C	0.25	2.439	0.602	0.85	1	14.167			
T2 140.00-135.00	0.232	0.358	A	0.682	1.776	0.807	0.85	1	19.700	0.826	0.165	A
			B	0.292	2.317	0.614	0.85	1	7.063			
			C	0.277	2.358	0.609	0.85	1	7.002			
T3 135.00-130.00	0.273	0.298	A	0.654	1.78	0.788	0.85	1	19.764	0.822	0.164	A
			B	0.249	2.441	0.602	0.85	1	6.206			
			C	0.293	2.314	0.614	0.85	1	7.675			
T4 130.00-125.00	0.279	0.336	A	0.619	1.793	0.765	0.85	1	19.408	0.804	0.161	A
			B	0.254	2.426	0.603	0.85	1	6.724			
			C	0.28	2.351	0.61	0.85	1	7.785			
T5 125.00-120.00	0.282	0.344	A	0.598	1.805	0.752	0.85	1	19.616	0.809	0.162	A
			B	0.255	2.422	0.603	0.85	1	7.261			
			C	0.276	2.362	0.609	0.85	1	8.207			
T6 120.00-100.00	1.386	2.086	A	0.557	1.837	0.728	0.85	1	85.057	3.463	0.173	A
			B	0.304	2.285	0.617	0.85	1	44.647			
			C	0.269	2.383	0.607	0.85	1	41.581			
T7 100.00-80.00	1.901	3.212	A	0.523	1.871	0.71	0.85	1	95.031	3.721	0.186	A
			B	0.406	2.052	0.654	0.85	1	71.839			
			C	0.316	2.254	0.621	0.85	1	58.297			
T8 80.00-73.33	0.649	1.038	A	0.461	1.955	0.679	0.85	1	30.254	1.182	0.177	A
			B	0.361	2.145	0.637	0.85	1	23.271			
			C	0.267	2.387	0.606	0.85	1	18.147			
T9 73.33-66.67	0.676	1.409	A	0.474	1.936	0.684	0.85	1	33.107	1.248	0.187	A
			B	0.402	2.06	0.652	0.85	1	27.710			
			C	0.308	2.274	0.618	0.85	1	22.144			
T10 66.67-60.00	0.678	1.450	A	0.458	1.961	0.677	0.85	1	33.381	1.239	0.186	A
			B	0.391	2.082	0.648	0.85	1	28.228			
			C	0.3	2.296	0.616	0.85	1	22.597			
T11 60.00-50.00	1.025	1.856	A	0.411	2.043	0.656	0.85	1	46.456	1.725	0.173	A
			B	0.337	2.203	0.628	0.85	1	37.785			
			C	0.245	2.454	0.6	0.85	1	29.074			
T12 50.00-40.00	1.030	2.213	A	0.413	2.038	0.657	0.85	1	50.128	1.754	0.175	A
			B	0.345	2.183	0.631	0.85	1	41.646			
			C	0.264	2.396	0.606	0.85	1	33.555			
T13 40.00-30.00	1.032	2.411	A	0.396	2.073	0.65	0.85	1	50.558	1.674	0.167	A
			B	0.331	2.217	0.626	0.85	1	42.231			
			C	0.257	2.416	0.604	0.85	1	34.550			
T14 30.00-20.00	1.032	2.946	A	0.402	2.059	0.653	0.85	1	54.917	1.777	0.178	A
			B	0.349	2.175	0.632	0.85	1	47.709			
			C	0.287	2.332	0.612	0.85	1	41.049			
T15 20.00-15.00	0.516	1.349	A	0.383	2.099	0.645	0.85	1	25.817	0.851	0.170	A
			B	0.33	2.22	0.625	0.85	1	22.024			
			C	0.269	2.382	0.607	0.85	1	18.504			
T16 15.00-10.00	0.516	1.476	A	0.397	2.07	0.65	0.85	1	27.980	0.910	0.182	A
			B	0.343	2.188	0.63	0.85	1	23.907			
			C	0.281	2.349	0.61	0.85	1	20.103			
T17 10.00-0.00	0.413	2.705	A	0.229	2.502	0.597	0.85	1	35.732	1.405	0.140	A
			B	0.206	2.575	0.592	0.85	1	32.802			
			C	0.181	2.662	0.587	0.85	1	29.968			
Sum Weight:	12.139	26.137						OTM	1859.857 kip-ft	25.260		

**Tower Forces - Service - Wind Normal To Face**

<b>tnxTower</b>  <b>URS Corporation</b> 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	<b>Job</b>	152' ROHN SSV Tower	<b>Page</b>	30 of 55
	<b>Project</b>	366 Old Long Ridge Road, Stamford, CT	<b>Date</b>	11:46:06 07/15/14
	<b>Client</b>	Verizon, Sprint and AT&T / S.A. Evaluation	<b>Designed by</b>	MCD

Section Elevation	Add Weight	Self Weight	F a c e	e	C <sub>F</sub>	R <sub>R</sub>	D <sub>F</sub>	D <sub>R</sub>	A <sub>E</sub>	F	w	Ctrl. Face
ft	K	K							ft <sup>2</sup>	K	klf	
T1 152.00-140.00	0.081	0.335	A	0.251	2.436	0.602	1	1	14.490	0.391	0.033	A
			B	0.17	2.701	0.585	1	1	10.673			
			C	0.16	2.736	0.583	1	1	10.468			
T2 140.00-135.00	0.088	0.211	A	0.473	1.937	0.684	1	1	12.020	0.254	0.051	A
			B	0.195	2.611	0.589	1	1	5.261			
			C	0.182	2.659	0.587	1	1	5.218			
T3 135.00-130.00	0.102	0.184	A	0.441	1.989	0.669	1	1	11.583	0.248	0.050	A
			B	0.164	2.721	0.584	1	1	4.461			
			C	0.191	2.626	0.589	1	1	5.363			
T4 130.00-125.00	0.105	0.219	A	0.416	2.033	0.658	1	1	11.542	0.250	0.050	A
			B	0.165	2.717	0.584	1	1	4.763			
			C	0.182	2.657	0.587	1	1	5.464			
T5 125.00-120.00	0.106	0.212	A	0.403	2.058	0.653	1	1	11.902	0.258	0.052	A
			B	0.169	2.704	0.585	1	1	5.296			
			C	0.182	2.656	0.587	1	1	5.940			
T6 120.00-100.00	0.525	1.382	A	0.389	2.085	0.647	1	1	59.358	1.265	0.063	A
			B	0.222	2.525	0.595	1	1	37.557			
			C	0.197	2.608	0.59	1	1	35.829			
T7 100.00-80.00	0.716	2.073	A	0.374	2.117	0.641	1	1	70.601	1.443	0.072	A
			B	0.295	2.308	0.615	1	1	58.385			
			C	0.234	2.485	0.598	1	1	50.992			
T8 80.00-73.33	0.244	0.721	A	0.326	2.229	0.624	1	1	22.430	0.461	0.069	A
			B	0.259	2.411	0.604	1	1	18.603			
			C	0.197	2.606	0.59	1	1	15.746			
T9 73.33-66.67	0.253	0.972	A	0.341	2.194	0.629	1	1	25.390	0.500	0.075	A
			B	0.29	2.323	0.613	1	1	22.390			
			C	0.228	2.505	0.597	1	1	19.378			
T10 66.67-60.00	0.254	0.998	A	0.329	2.222	0.625	1	1	25.770	0.500	0.075	A
			B	0.282	2.345	0.611	1	1	22.870			
			C	0.222	2.525	0.595	1	1	19.813			
T11 60.00-50.00	0.383	1.354	A	0.292	2.319	0.613	1	1	35.292	0.686	0.069	A
			B	0.242	2.46	0.6	1	1	30.481			
			C	0.183	2.654	0.587	1	1	25.573			
T12 50.00-40.00	0.384	1.565	A	0.296	2.306	0.615	1	1	39.036	0.713	0.071	A
			B	0.251	2.435	0.602	1	1	34.372			
			C	0.197	2.606	0.59	1	1	29.756			
T13 40.00-30.00	0.384	1.741	A	0.284	2.34	0.611	1	1	39.642	0.684	0.068	A
			B	0.241	2.465	0.6	1	1	35.025			
			C	0.191	2.627	0.589	1	1	30.513			
T14 30.00-20.00	0.384	2.026	A	0.294	2.312	0.614	1	1	44.602	0.747	0.075	A
			B	0.257	2.418	0.604	1	1	40.565			
			C	0.213	2.554	0.593	1	1	36.698			
T15 20.00-15.00	0.192	0.907	A	0.279	2.352	0.61	1	1	19.680	0.335	0.067	A
			B	0.243	2.459	0.6	1	1	17.556			
			C	0.201	2.594	0.591	1	1	15.503			
T16 15.00-10.00	0.192	0.995	A	0.29	2.322	0.613	1	1	21.546	0.363	0.073	A
			B	0.254	2.426	0.603	1	1	19.304			
			C	0.211	2.559	0.593	1	1	17.117			
T17 10.00-0.00	0.154	1.983	A	0.178	2.671	0.586	1	1	32.830	0.635	0.064	A
			B	0.163	2.723	0.584	1	1	31.075			
			C	0.146	2.786	0.581	1	1	29.300			
Sum Weight:	4.545	17.879						OTM	685.522 kip-ft	9.735		

**Tower Forces - Service - Wind 45 To Face**

<b>tnxTower</b>  <b>URS Corporation</b> 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	<b>Job</b>	152' ROHN SSV Tower	<b>Page</b>	31 of 55
	<b>Project</b>	366 Old Long Ridge Road, Stamford, CT	<b>Date</b>	11:46:06 07/15/14
	<b>Client</b>	Verizon, Sprint and AT&T / S.A. Evaluation	<b>Designed by</b>	MCD

Section Elevation	Add Weight	Self Weight	F a c e	e	C <sub>F</sub>	R <sub>R</sub>	D <sub>F</sub>	D <sub>R</sub>	A <sub>E</sub>	F	w	Ctrl. Face
ft	K	K							ft <sup>2</sup>	K	klf	
T1 152.00-140.00	0.081	0.335	A	0.251	2.436	0.602	0.825	1	13.481	0.364	0.030	A
			B	0.17	2.701	0.585	0.825	1	9.555			
			C	0.16	2.736	0.583	0.825	1	9.234			
T2 140.00-135.00	0.088	0.211	A	0.473	1.937	0.684	0.825	1	11.688	0.247	0.049	A
			B	0.195	2.611	0.589	0.825	1	4.750			
			C	0.182	2.659	0.587	0.825	1	4.599			
T3 135.00-130.00	0.102	0.184	A	0.441	1.989	0.669	0.825	1	11.345	0.243	0.049	A
			B	0.164	2.721	0.584	0.825	1	4.104			
			C	0.191	2.626	0.589	0.825	1	4.889			
T4 130.00-125.00	0.105	0.219	A	0.416	2.033	0.658	0.825	1	11.282	0.245	0.049	A
			B	0.165	2.717	0.584	0.825	1	4.392			
			C	0.182	2.657	0.587	0.825	1	4.972			
T5 125.00-120.00	0.106	0.212	A	0.403	2.058	0.653	0.825	1	11.576	0.251	0.050	A
			B	0.169	2.704	0.585	0.825	1	4.841			
			C	0.182	2.656	0.587	0.825	1	5.364			
T6 120.00-100.00	0.525	1.382	A	0.389	2.085	0.647	0.825	1	54.915	1.171	0.059	A
			B	0.222	2.525	0.595	0.825	1	32.733			
			C	0.197	2.608	0.59	0.825	1	30.431			
T7 100.00-80.00	0.716	2.073	A	0.374	2.117	0.641	0.825	1	64.313	1.314	0.066	A
			B	0.295	2.308	0.615	0.825	1	51.688			
			C	0.234	2.485	0.598	0.825	1	43.463			
T8 80.00-73.33	0.244	0.721	A	0.326	2.229	0.624	0.825	1	20.483	0.421	0.063	A
			B	0.259	2.411	0.604	0.825	1	16.576			
			C	0.197	2.606	0.59	0.825	1	13.474			
T9 73.33-66.67	0.253	0.972	A	0.341	2.194	0.629	0.825	1	22.940	0.452	0.068	A
			B	0.29	2.323	0.613	0.825	1	19.840			
			C	0.228	2.505	0.597	0.825	1	16.534			
T10 66.67-60.00	0.254	0.998	A	0.329	2.222	0.625	0.825	1	23.241	0.451	0.068	A
			B	0.282	2.345	0.611	0.825	1	20.244			
			C	0.222	2.525	0.595	0.825	1	16.892			
T11 60.00-50.00	0.383	1.354	A	0.292	2.319	0.613	0.825	1	32.073	0.624	0.062	A
			B	0.242	2.46	0.6	0.825	1	27.176			
			C	0.183	2.654	0.587	0.825	1	21.905			
T12 50.00-40.00	0.384	1.565	A	0.296	2.306	0.615	0.825	1	35.179	0.642	0.064	A
			B	0.251	2.435	0.602	0.825	1	30.393			
			C	0.197	2.606	0.59	0.825	1	25.375			
T13 40.00-30.00	0.384	1.741	A	0.284	2.34	0.611	0.825	1	35.661	0.615	0.062	A
			B	0.241	2.465	0.6	0.825	1	30.923			
			C	0.191	2.627	0.589	0.825	1	26.013			
T14 30.00-20.00	0.384	2.026	A	0.294	2.312	0.614	0.825	1	39.768	0.666	0.067	A
			B	0.257	2.418	0.604	0.825	1	35.508			
			C	0.213	2.554	0.593	0.825	1	31.122			
T15 20.00-15.00	0.192	0.907	A	0.279	2.352	0.61	0.825	1	18.394	0.314	0.063	A
			B	0.243	2.459	0.6	0.825	1	16.170			
			C	0.201	2.594	0.591	0.825	1	13.872			
T16 15.00-10.00	0.192	0.995	A	0.29	2.322	0.613	0.825	1	19.944	0.336	0.067	A
			B	0.254	2.426	0.603	0.825	1	17.620			
			C	0.211	2.559	0.593	0.825	1	15.208			
T17 10.00-0.00	0.154	1.983	A	0.178	2.671	0.586	0.825	1	28.219	0.546	0.055	A
			B	0.163	2.723	0.584	0.825	1	26.427			
			C	0.146	2.786	0.581	0.825	1	24.504			
Sum Weight:	4.545	17.879						OTM	634.576 kip-ft	8.901		

**Tower Forces - Service - Wind 60 To Face**



<b>tnxTower</b>  <b>URS Corporation</b> 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	<b>Job</b> 152' ROHN SSV Tower	<b>Page</b> 32 of 55
	<b>Project</b> 366 Old Long Ridge Road, Stamford, CT	<b>Date</b> 11:46:06 07/15/14
	<b>Client</b> Verizon, Sprint and AT&T / S.A. Evaluation	<b>Designed by</b> MCD

Section Elevation	Add Weight	Self Weight	F a c e	e	C <sub>F</sub>	R <sub>R</sub>	D <sub>F</sub>	D <sub>R</sub>	A <sub>E</sub>	F	w	Ctrl. Face
ft	K	K							ft <sup>2</sup>	K	klf	
T1 152.00-140.00	0.081	0.335	A	0.251	2.436	0.602	0.8	1	13.337	0.360	0.030	A
			B	0.17	2.701	0.585	0.8	1	9.396			
			C	0.16	2.736	0.583	0.8	1	9.058			
T2 140.00-135.00	0.088	0.211	A	0.473	1.937	0.684	0.8	1	11.641	0.246	0.049	A
			B	0.195	2.611	0.589	0.8	1	4.677			
			C	0.182	2.659	0.587	0.8	1	4.510			
T3 135.00-130.00	0.102	0.184	A	0.441	1.989	0.669	0.8	1	11.311	0.243	0.049	A
			B	0.164	2.721	0.584	0.8	1	4.054			
			C	0.191	2.626	0.589	0.8	1	4.822			
T4 130.00-125.00	0.105	0.219	A	0.416	2.033	0.658	0.8	1	11.245	0.244	0.049	A
			B	0.165	2.717	0.584	0.8	1	4.339			
			C	0.182	2.657	0.587	0.8	1	4.901			
T5 125.00-120.00	0.106	0.212	A	0.403	2.058	0.653	0.8	1	11.529	0.250	0.050	A
			B	0.169	2.704	0.585	0.8	1	4.776			
			C	0.182	2.656	0.587	0.8	1	5.282			
T6 120.00-100.00	0.525	1.382	A	0.389	2.085	0.647	0.8	1	54.281	1.157	0.058	A
			B	0.222	2.525	0.595	0.8	1	32.044			
			C	0.197	2.608	0.59	0.8	1	29.660			
T7 100.00-80.00	0.716	2.073	A	0.374	2.117	0.641	0.8	1	63.415	1.296	0.065	A
			B	0.295	2.308	0.615	0.8	1	50.732			
			C	0.234	2.485	0.598	0.8	1	42.387			
T8 80.00-73.33	0.244	0.721	A	0.326	2.229	0.624	0.8	1	20.205	0.415	0.062	A
			B	0.259	2.411	0.604	0.8	1	16.286			
			C	0.197	2.606	0.59	0.8	1	13.149			
T9 73.33-66.67	0.253	0.972	A	0.341	2.194	0.629	0.8	1	22.591	0.445	0.067	A
			B	0.29	2.323	0.613	0.8	1	19.476			
			C	0.228	2.505	0.597	0.8	1	16.127			
T10 66.67-60.00	0.254	0.998	A	0.329	2.222	0.625	0.8	1	22.880	0.444	0.067	A
			B	0.282	2.345	0.611	0.8	1	19.869			
			C	0.222	2.525	0.595	0.8	1	16.474			
T11 60.00-50.00	0.383	1.354	A	0.292	2.319	0.613	0.8	1	31.613	0.615	0.061	A
			B	0.242	2.46	0.6	0.8	1	26.704			
			C	0.183	2.654	0.587	0.8	1	21.381			
T12 50.00-40.00	0.384	1.565	A	0.296	2.306	0.615	0.8	1	34.628	0.632	0.063	A
			B	0.251	2.435	0.602	0.8	1	29.825			
			C	0.197	2.606	0.59	0.8	1	24.749			
T13 40.00-30.00	0.384	1.741	A	0.284	2.34	0.611	0.8	1	35.092	0.605	0.061	A
			B	0.241	2.465	0.6	0.8	1	30.337			
			C	0.191	2.627	0.589	0.8	1	25.370			
T14 30.00-20.00	0.384	2.026	A	0.294	2.312	0.614	0.8	1	39.077	0.655	0.065	A
			B	0.257	2.418	0.604	0.8	1	34.785			
			C	0.213	2.554	0.593	0.8	1	30.325			
T15 20.00-15.00	0.192	0.907	A	0.279	2.352	0.61	0.8	1	18.210	0.310	0.062	A
			B	0.243	2.459	0.6	0.8	1	15.972			
			C	0.201	2.594	0.591	0.8	1	13.639			
T16 15.00-10.00	0.192	0.995	A	0.29	2.322	0.613	0.8	1	19.715	0.332	0.066	A
			B	0.254	2.426	0.603	0.8	1	17.379			
			C	0.211	2.559	0.593	0.8	1	14.935			
T17 10.00-0.00	0.154	1.983	A	0.178	2.671	0.586	0.8	1	27.560	0.533	0.053	A
			B	0.163	2.723	0.584	0.8	1	25.763			
			C	0.146	2.786	0.581	0.8	1	23.819			
Sum Weight:	4.545	17.879						OTM	627.298 kip-ft	8.782		

**Tower Forces - Service - Wind 90 To Face**

<b>tnxTower</b>  <b>URS Corporation</b> 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	<b>Job</b> 152' ROHN SSV Tower	<b>Page</b> 33 of 55
	<b>Project</b> 366 Old Long Ridge Road, Stamford, CT	<b>Date</b> 11:46:06 07/15/14
	<b>Client</b> Verizon, Sprint and AT&T / S.A. Evaluation	<b>Designed by</b> MCD

Section Elevation	Add Weight	Self Weight	F a c e	e	C <sub>F</sub>	R <sub>R</sub>	D <sub>F</sub>	D <sub>R</sub>	A <sub>E</sub>	F	w	Ctrl. Face
ft	K	K							ft <sup>2</sup>	K	klf	
T1 152.00-140.00	0.081	0.335	A	0.251	2.436	0.602	0.85	1	13.625	0.368	0.031	A
			B	0.17	2.701	0.585	0.85	1	9.715			
			C	0.16	2.736	0.583	0.85	1	9.410			
T2 140.00-135.00	0.088	0.211	A	0.473	1.937	0.684	0.85	1	11.736	0.248	0.050	A
			B	0.195	2.611	0.589	0.85	1	4.823			
			C	0.182	2.659	0.587	0.85	1	4.687			
T3 135.00-130.00	0.102	0.184	A	0.441	1.989	0.669	0.85	1	11.379	0.244	0.049	A
			B	0.164	2.721	0.584	0.85	1	4.155			
			C	0.191	2.626	0.589	0.85	1	4.957			
T4 130.00-125.00	0.105	0.219	A	0.416	2.033	0.658	0.85	1	11.319	0.245	0.049	A
			B	0.165	2.717	0.584	0.85	1	4.445			
			C	0.182	2.657	0.587	0.85	1	5.042			
T5 125.00-120.00	0.106	0.212	A	0.403	2.058	0.653	0.85	1	11.622	0.252	0.050	A
			B	0.169	2.704	0.585	0.85	1	4.906			
			C	0.182	2.656	0.587	0.85	1	5.446			
T6 120.00-100.00	0.525	1.382	A	0.389	2.085	0.647	0.85	1	55.550	1.184	0.059	A
			B	0.222	2.525	0.595	0.85	1	33.422			
			C	0.197	2.608	0.59	0.85	1	31.202			
T7 100.00-80.00	0.716	2.073	A	0.374	2.117	0.641	0.85	1	65.211	1.333	0.067	A
			B	0.295	2.308	0.615	0.85	1	52.645			
			C	0.234	2.485	0.598	0.85	1	44.538			
T8 80.00-73.33	0.244	0.721	A	0.326	2.229	0.624	0.85	1	20.761	0.427	0.064	A
			B	0.259	2.411	0.604	0.85	1	16.865			
			C	0.197	2.606	0.59	0.85	1	13.798			
T9 73.33-66.67	0.253	0.972	A	0.341	2.194	0.629	0.85	1	23.290	0.459	0.069	A
			B	0.29	2.323	0.613	0.85	1	20.204			
			C	0.228	2.505	0.597	0.85	1	16.940			
T10 66.67-60.00	0.254	0.998	A	0.329	2.222	0.625	0.85	1	23.603	0.458	0.069	A
			B	0.282	2.345	0.611	0.85	1	20.619			
			C	0.222	2.525	0.595	0.85	1	17.309			
T11 60.00-50.00	0.383	1.354	A	0.292	2.319	0.613	0.85	1	32.532	0.633	0.063	A
			B	0.242	2.46	0.6	0.85	1	27.648			
			C	0.183	2.654	0.587	0.85	1	22.429			
T12 50.00-40.00	0.384	1.565	A	0.296	2.306	0.615	0.85	1	35.730	0.652	0.065	A
			B	0.251	2.435	0.602	0.85	1	30.962			
			C	0.197	2.606	0.59	0.85	1	26.001			
T13 40.00-30.00	0.384	1.741	A	0.284	2.34	0.611	0.85	1	36.230	0.625	0.062	A
			B	0.241	2.465	0.6	0.85	1	31.509			
			C	0.191	2.627	0.589	0.85	1	26.656			
T14 30.00-20.00	0.384	2.026	A	0.294	2.312	0.614	0.85	1	40.458	0.678	0.068	A
			B	0.257	2.418	0.604	0.85	1	36.230			
			C	0.213	2.554	0.593	0.85	1	31.918			
T15 20.00-15.00	0.192	0.907	A	0.279	2.352	0.61	0.85	1	18.577	0.317	0.063	A
			B	0.243	2.459	0.6	0.85	1	16.368			
			C	0.201	2.594	0.591	0.85	1	14.105			
T16 15.00-10.00	0.192	0.995	A	0.29	2.322	0.613	0.85	1	20.173	0.339	0.068	A
			B	0.254	2.426	0.603	0.85	1	17.861			
			C	0.211	2.559	0.593	0.85	1	15.480			
T17 10.00-0.00	0.154	1.983	A	0.178	2.671	0.586	0.85	1	28.878	0.559	0.056	A
			B	0.163	2.723	0.584	0.85	1	27.091			
			C	0.146	2.786	0.581	0.85	1	25.189			
Sum Weight:	4.545	17.879						OTM	641.854 kip-ft	9.020		

**Force Totals**

<b>tnxTower</b>  <b>URS Corporation</b> 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	<b>Job</b> 152' ROHN SSV Tower	<b>Page</b> 34 of 55
	<b>Project</b> 366 Old Long Ridge Road, Stamford, CT	<b>Date</b> 11:46:06 07/15/14
	<b>Client</b> Verizon, Sprint and AT&T / S.A. Evaluation	<b>Designed by</b> MCD

Load Case	Vertical Forces K	Sum of Forces X K	Sum of Forces Z K	Sum of Overturning Moments, $M_x$ kip-ft	Sum of Overturning Moments, $M_z$ kip-ft	Sum of Torques kip-ft
Leg Weight	7.490					
Bracing Weight	10.389					
Total Member Self-Weight	17.879			-14.558	2.671	
Total Weight	30.749			-14.558	2.671	
Wind 0 deg - No Ice		-0.048	-43.134	-3775.457	9.785	-7.307
Wind 30 deg - No Ice		20.365	-35.543	-3158.744	-1790.387	-15.502
Wind 45 deg - No Ice		28.582	-28.763	-2564.776	-2521.905	-17.923
Wind 60 deg - No Ice		34.725	-20.149	-1804.714	-3073.679	-19.004
Wind 90 deg - No Ice		40.813	0.048	-7.444	-3595.766	-18.421
Wind 120 deg - No Ice		37.157	21.608	1872.052	-3226.516	-14.022
Wind 135 deg - No Ice		28.650	28.831	2545.720	-2531.966	-7.659
Wind 150 deg - No Ice		20.448	35.591	3136.741	-1802.709	-2.919
Wind 180 deg - No Ice		0.048	40.381	3578.075	-4.443	7.251
Wind 210 deg - No Ice		-20.365	35.543	3129.627	1795.729	15.502
Wind 225 deg - No Ice		-28.582	28.763	2535.659	2527.247	17.923
Wind 240 deg - No Ice		-37.109	21.526	1859.730	3224.744	21.329
Wind 270 deg - No Ice		-40.813	-0.048	-21.672	3601.108	18.421
Wind 300 deg - No Ice		-34.773	-20.232	-1817.036	3086.135	11.753
Wind 315 deg - No Ice		-28.650	-28.831	-2574.837	2537.308	7.659
Wind 330 deg - No Ice		-20.448	-35.591	-3165.858	1808.050	2.919
Member Ice	8.258					
Total Weight Ice	51.144			-33.540	1.392	
Wind 0 deg - Ice		-0.037	-40.072	-3559.413	6.889	-6.505
Wind 30 deg - Ice		19.202	-33.469	-3010.359	-1699.969	-14.952
Wind 45 deg - Ice		27.009	-27.151	-2452.399	-2397.481	-17.613
Wind 60 deg - Ice		32.890	-19.068	-1734.806	-2926.306	-18.992
Wind 90 deg - Ice		38.468	0.037	-28.043	-3410.851	-18.619
Wind 120 deg - Ice		34.549	20.068	1734.157	-3030.374	-14.048
Wind 135 deg - Ice		27.061	27.203	2393.093	-2405.255	-8.397
Wind 150 deg - Ice		19.266	33.506	2948.776	-1709.491	-3.667
Wind 180 deg - Ice		0.037	38.200	3378.513	-4.106	6.519
Wind 210 deg - Ice		-19.202	33.469	2943.279	1702.752	14.952
Wind 225 deg - Ice		-27.009	27.151	2385.319	2400.264	17.613
Wind 240 deg - Ice		-34.512	20.004	1724.635	3027.660	20.553
Wind 270 deg - Ice		-38.468	-0.037	-39.037	3413.634	18.619
Wind 300 deg - Ice		-32.927	-19.132	-1744.328	2934.586	12.473
Wind 315 deg - Ice		-27.061	-27.203	-2460.174	2408.038	8.397
Wind 330 deg - Ice		-19.266	-33.506	-3015.856	1712.274	3.667
Total Weight	30.749			-14.558	2.671	
Wind 0 deg - Service		-0.017	-14.925	-1301.532	5.017	-2.528
Wind 30 deg - Service		7.047	-12.299	-1088.136	-617.880	-5.364
Wind 45 deg - Service		9.890	-9.953	-882.611	-871.001	-6.202
Wind 60 deg - Service		12.016	-6.972	-619.614	-1061.926	-6.576
Wind 90 deg - Service		14.122	0.017	2.279	-1242.579	-6.374
Wind 120 deg - Service		12.857	7.477	652.623	-1114.811	-4.852
Wind 135 deg - Service		9.913	9.976	885.726	-874.482	-2.650
Wind 150 deg - Service		7.075	12.315	1090.232	-622.144	-1.010
Wind 180 deg - Service		0.017	13.973	1242.943	0.094	2.509
Wind 210 deg - Service		-7.047	12.299	1087.770	622.990	5.364
Wind 225 deg - Service		-9.890	9.953	882.245	876.111	6.202
Wind 240 deg - Service		-12.841	7.448	648.360	1117.459	7.380
Wind 270 deg - Service		-14.122	-0.017	-2.645	1247.689	6.374
Wind 300 deg - Service		-12.032	-7.001	-623.878	1069.498	4.067
Wind 315 deg - Service		-9.913	-9.976	-886.093	879.592	2.650
Wind 330 deg - Service		-7.075	-12.315	-1090.598	627.254	1.010

<b>tnxTower</b>  <b>URS Corporation</b> 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	<b>Job</b>	152' ROHN SSV Tower	<b>Page</b>	35 of 55
	<b>Project</b>	366 Old Long Ridge Road, Stamford, CT	<b>Date</b>	11:46:06 07/15/14
	<b>Client</b>	Verizon, Sprint and AT&T / S.A. Evaluation	<b>Designed by</b>	MCD

## Load Combinations

Comb. No.	Description
1	Dead Only
2	Dead+Wind 0 deg - No Ice
3	Dead+Wind 30 deg - No Ice
4	Dead+Wind 45 deg - No Ice
5	Dead+Wind 60 deg - No Ice
6	Dead+Wind 90 deg - No Ice
7	Dead+Wind 120 deg - No Ice
8	Dead+Wind 135 deg - No Ice
9	Dead+Wind 150 deg - No Ice
10	Dead+Wind 180 deg - No Ice
11	Dead+Wind 210 deg - No Ice
12	Dead+Wind 225 deg - No Ice
13	Dead+Wind 240 deg - No Ice
14	Dead+Wind 270 deg - No Ice
15	Dead+Wind 300 deg - No Ice
16	Dead+Wind 315 deg - No Ice
17	Dead+Wind 330 deg - No Ice
18	Dead+Ice+Temp
19	Dead+Wind 0 deg+Ice+Temp
20	Dead+Wind 30 deg+Ice+Temp
21	Dead+Wind 45 deg+Ice+Temp
22	Dead+Wind 60 deg+Ice+Temp
23	Dead+Wind 90 deg+Ice+Temp
24	Dead+Wind 120 deg+Ice+Temp
25	Dead+Wind 135 deg+Ice+Temp
26	Dead+Wind 150 deg+Ice+Temp
27	Dead+Wind 180 deg+Ice+Temp
28	Dead+Wind 210 deg+Ice+Temp
29	Dead+Wind 225 deg+Ice+Temp
30	Dead+Wind 240 deg+Ice+Temp
31	Dead+Wind 270 deg+Ice+Temp
32	Dead+Wind 300 deg+Ice+Temp
33	Dead+Wind 315 deg+Ice+Temp
34	Dead+Wind 330 deg+Ice+Temp
35	Dead+Wind 0 deg - Service
36	Dead+Wind 30 deg - Service
37	Dead+Wind 45 deg - Service
38	Dead+Wind 60 deg - Service
39	Dead+Wind 90 deg - Service
40	Dead+Wind 120 deg - Service
41	Dead+Wind 135 deg - Service
42	Dead+Wind 150 deg - Service
43	Dead+Wind 180 deg - Service
44	Dead+Wind 210 deg - Service
45	Dead+Wind 225 deg - Service
46	Dead+Wind 240 deg - Service
47	Dead+Wind 270 deg - Service
48	Dead+Wind 300 deg - Service
49	Dead+Wind 315 deg - Service
50	Dead+Wind 330 deg - Service

## Maximum Member Forces

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Force K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
-------------	--------------	----------------	-----------	-----------------	---------	--------------------------	--------------------------

<b>tnxTower</b>  <b>URS Corporation</b> 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	<b>Job</b> 152' ROHN SSV Tower	<b>Page</b> 36 of 55
	<b>Project</b> 366 Old Long Ridge Road, Stamford, CT	<b>Date</b> 11:46:06 07/15/14
	<b>Client</b> Verizon, Sprint and AT&T / S.A. Evaluation	<b>Designed by</b> MCD

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Force K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
T1	152 - 140	Leg	Max Tension	15	5.558	-0.129	0.081
			Max. Compression	2	-7.018	0.380	0.130
			Max. Mx	2	-7.018	0.380	0.130
			Max. My	17	-0.575	-0.005	-0.502
			Max. Vy	2	-2.890	0.380	0.130
			Max. Vx	8	1.088	-0.077	-0.403
		Diagonal	Max Tension	6	1.915	0.000	0.000
			Max. Compression	14	-1.935	0.000	0.000
			Max. Mx	26	1.468	0.006	0.000
			Max. My	11	-0.355	0.001	0.002
			Max. Vy	26	-0.006	0.006	0.000
			Max. Vx	11	-0.000	0.001	0.002
		Top Girt	Max Tension	2	0.287	0.000	0.000
			Max. Compression	10	-0.284	0.000	0.000
			Max. Mx	18	0.005	-0.019	0.000
			Max. My	27	0.131	0.000	0.000
			Max. Vy	18	0.012	0.000	0.000
Max. Vx	27		0.000	0.000	0.000		
T2	140 - 135	Leg	Max Tension	10	10.129	0.260	0.008
			Max. Compression	2	-12.229	-0.030	-0.005
			Max. Mx	2	-7.168	0.598	0.130
			Max. My	9	-0.615	0.019	-0.516
			Max. Vy	2	-2.909	-0.030	-0.005
		Diagonal	Max. Vx	8	1.202	0.003	0.065
			Max Tension	14	2.776	0.000	0.000
			Max. Compression	14	-2.788	0.000	0.000
			Max. Mx	23	0.688	0.008	-0.001
			Max. My	6	-2.778	0.002	-0.003
		Top Girt	Max. Vy	23	0.008	0.008	-0.001
			Max. Vx	23	0.001	0.000	0.000
			Max Tension	7	0.144	0.000	0.000
			Max. Compression	15	-0.157	0.000	0.000
T3	135 - 130	Leg	Max. Mx	18	-0.024	-0.019	0.000
			Max. My	21	0.056	0.000	0.001
			Max. Vy	18	0.012	0.000	0.000
			Max. Vx	21	0.000	0.000	0.000
			Max Tension	10	12.213	0.024	0.005
		Diagonal	Max. Compression	2	-14.620	0.472	0.024
			Max. Mx	10	12.009	-0.508	-0.026
			Max. My	14	-1.337	-0.017	-0.510
			Max. Vy	10	0.166	-0.508	-0.026
			Max. Vx	14	0.203	-0.017	-0.510
T4	130 - 125	Leg	Max Tension	14	2.604	0.000	0.000
			Max. Compression	14	-2.612	0.000	0.000
			Max. Mx	24	1.618	0.010	-0.001
			Max. My	24	-0.148	0.008	-0.002
			Max. Vy	33	0.008	0.009	0.001
		Diagonal	Max. Vx	24	0.001	0.000	0.000
			Max Tension	15	17.210	-0.503	-0.025
			Max. Compression	2	-20.859	0.346	0.002
			Max. Mx	15	17.210	0.821	-0.025
			Max. My	11	-1.256	-0.013	-0.810
			Max. Vy	10	-0.671	-0.508	-0.026
T5	125 - 120	Leg	Max. Vx	14	-0.669	-0.017	-0.510
			Max Tension	14	3.424	0.000	0.000
			Max. Compression	14	-3.479	0.000	0.000
		Diagonal	Max. Mx	33	2.686	0.012	-0.001
			Max. My	32	-2.654	0.007	0.002
			Max. Vy	33	0.010	0.012	-0.001
			Max. Vx	32	-0.001	0.000	0.000
Max Tension	10	23.212	-0.385	-0.003			

<b>tnxTower</b>  <b>URS Corporation</b> 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	<b>Job</b>	152' ROHN SSV Tower	<b>Page</b>	37 of 55
	<b>Project</b>	366 Old Long Ridge Road, Stamford, CT	<b>Date</b>	11:46:06 07/15/14
	<b>Client</b>	Verizon, Sprint and AT&T / S.A. Evaluation	<b>Designed by</b>	MCD

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Force K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
T6	120 - 100	Leg	Max. Compression	2	-27.981	-0.043	0.015
			Max. Mx	5	22.904	-0.385	0.009
			Max. My	6	-2.015	-0.019	0.364
			Max. Vy	10	-0.111	-0.385	-0.003
			Max. Vx	6	0.109	-0.019	0.364
			Max Tension	14	3.945	0.000	0.000
			Max. Compression	14	-3.948	0.000	0.000
			Max. Mx	33	2.689	0.017	-0.001
			Max. My	27	-3.392	0.008	-0.003
			Max. Vy	33	0.012	0.017	-0.001
			Max. Vx	27	0.001	0.000	0.000
			Max Tension	10	47.129	0.040	0.003
			Max. Compression	2	-53.902	0.958	-0.016
			Max. Mx	10	46.998	-0.987	0.018
			Max. My	6	-2.798	-0.020	0.989
			Max. Vy	32	0.295	-0.940	-0.037
			Max. Vx	11	-0.313	-0.014	0.955
			T7	100 - 80	Leg	Max Tension	11
Max. Compression	11	-4.607				0.000	0.000
Max. Mx	19	3.474				0.031	0.003
Max. My	28	-4.386				0.010	-0.007
Max. Vy	33	0.018				0.028	0.003
Max. Vx	28	0.002				0.000	0.000
Max Tension	10	76.836				0.263	0.022
Max. Compression	2	-88.559				0.063	0.012
Max. Mx	5	55.183				1.240	0.019
Max. My	6	-3.662				0.017	-1.447
Max. Vy	10	-1.124				-0.987	0.018
Max. Vx	6	1.237				-0.020	0.989
Max Tension	11	6.897				0.000	0.000
Max. Compression	11	-6.923				0.000	0.000
Max. Mx	19	5.149				0.066	0.004
Max. My	21	-5.607				0.015	0.008
Max. Vy	19	-0.029				0.066	0.004
Max. Vx	21	-0.002				0.000	0.000
T8	80 - 73.3333	Leg	Max Tension	2	1.536	0.000	0.000
			Max. Compression	2	-1.536	0.000	0.000
			Max. Mx	18	0.148	-0.121	0.000
			Max. My	30	1.465	0.000	0.004
			Max. Vy	18	0.039	0.000	0.000
			Max. Vx	30	-0.001	0.000	0.000
			Max Tension	10	87.346	-0.116	-0.009
			Max. Compression	2	-100.326	0.188	0.010
			Max. Mx	27	78.260	-0.411	-0.011
			Max. My	6	-5.146	-0.023	0.544
			Max. Vy	27	0.115	-0.411	-0.011
			Max. Vx	6	-0.112	-0.023	0.544
			Max Tension	11	6.790	0.000	0.000
			Max. Compression	11	-6.848	0.000	0.000
			Max. Mx	32	5.175	0.050	-0.006
			Max. My	22	-5.623	0.025	0.008
			Max. Vy	32	0.028	0.050	-0.006
			Max. Vx	22	-0.002	0.000	0.000
T9	73.3333 - 66.6667	Leg	Max Tension	10	96.963	-0.225	-0.009
			Max. Compression	2	-111.296	-0.246	0.006
			Max. Mx	2	-111.169	0.558	-0.004
			Max. My	6	-5.277	-0.023	0.544
			Max. Vy	2	0.257	0.558	-0.004
			Max. Vx	23	0.378	-0.225	0.532

<b>Job</b>	152' ROHN SSV Tower	<b>Page</b>	38 of 55
<b>Project</b>	366 Old Long Ridge Road, Stamford, CT	<b>Date</b>	11:46:06 07/15/14
<b>Client</b>	Verizon, Sprint and AT&T / S.A. Evaluation	<b>Designed by</b>	MCD

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Force K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
T10	66.6667 - 60	Diagonal	Max Tension	11	7.057	0.000	0.000
			Max. Compression	28	-7.190	0.000	0.000
			Max. Mx	19	5.166	0.077	0.007
			Max. My	30	-0.097	0.062	-0.009
			Max. Vy	33	0.035	0.074	0.007
			Max. Vx	30	-0.002	0.000	0.000
		Secondary Horizontal	Max Tension	2	1.930	0.000	0.000
			Max. Compression	2	-1.930	0.000	0.000
			Max. Mx	18	0.176	-0.149	0.000
			Max. My	30	1.843	0.000	0.005
			Max. Vy	18	0.044	0.000	0.000
			Max. Vx	30	-0.001	0.000	0.000
		Leg	Max Tension	10	106.572	0.091	-0.005
			Max. Compression	2	-122.542	0.251	-0.025
			Max. Mx	19	-120.507	0.802	-0.001
			Max. My	14	-6.801	-0.020	-0.604
			Max. Vy	2	-0.317	0.720	-0.005
			Max. Vx	14	0.275	-0.020	-0.604
		Diagonal	Max Tension	28	7.191	0.000	0.000
			Max. Compression	11	-7.178	0.000	0.000
			Max. Mx	33	4.605	0.066	-0.007
Max. My	21		-6.367	0.029	0.014		
Max. Vy	33		0.035	0.066	-0.007		
Max. Vx	21		-0.003	0.000	0.000		
Secondary Horizontal	Max Tension	2	2.125	0.000	0.000		
	Max. Compression	2	-2.125	0.000	0.000		
	Max. Mx	18	0.198	-0.165	0.000		
	Max. My	30	2.038	0.000	0.005		
	Max. Vy	18	0.046	0.000	0.000		
	Max. Vx	30	-0.001	0.000	0.000		
T11	60 - 50	Leg	Max Tension	10	118.266	-0.291	0.016
			Max. Compression	2	-135.919	0.162	0.172
			Max. Mx	27	107.705	-0.669	0.010
			Max. My	17	-5.452	-0.048	0.994
			Max. Vy	27	-0.171	-0.669	0.010
			Max. Vx	13	0.140	-0.157	-0.784
		Diagonal	Max Tension	11	8.153	0.000	0.000
			Max. Compression	28	-8.503	0.000	0.000
			Max. Mx	32	5.594	0.131	-0.012
			Max. My	22	-7.288	0.071	0.018
			Max. Vy	32	0.048	0.131	-0.012
			Max. Vx	22	-0.003	0.000	0.000
T12	50 - 40	Leg	Max Tension	10	132.090	-0.285	-0.138
			Max. Compression	2	-151.941	-0.230	0.164
			Max. Mx	19	-149.459	1.174	-0.293
			Max. My	17	-6.287	-0.056	1.608
			Max. Vy	19	0.561	1.174	-0.293
			Max. Vx	17	-0.556	-0.056	1.608
		Diagonal	Max Tension	28	8.601	0.000	0.000
			Max. Compression	11	-8.569	0.000	0.000
			Max. Mx	19	6.857	0.109	0.011
			Max. My	30	0.314	0.085	-0.014
			Max. Vy	32	0.048	0.107	0.011
			Max. Vx	30	-0.003	0.000	0.000
Secondary Horizontal	Max Tension	2	2.635	0.000	0.000		
	Max. Compression	2	-2.635	0.000	0.000		
	Max. Mx	18	0.240	-0.210	0.000		
	Max. My	30	2.540	0.000	0.006		

<b>tnxTower</b>  <b>URS Corporation</b> 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	<b>Job</b>	152' ROHN SSV Tower	<b>Page</b>	39 of 55
	<b>Project</b>	366 Old Long Ridge Road, Stamford, CT	<b>Date</b>	11:46:06 07/15/14
	<b>Client</b>	Verizon, Sprint and AT&T / S.A. Evaluation	<b>Designed by</b>	MCD

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Force K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
T13	40 - 30	Leg	Max. Vy	18	-0.052	0.000	0.000
			Max. Vx	30	-0.001	0.000	0.000
			Max Tension	15	145.569	-0.041	0.076
			Max. Compression	2	-167.671	-1.860	-0.084
			Max. Mx	32	133.936	2.168	-0.072
			Max. My	17	-6.650	-0.056	1.608
		Diagonal	Max. Vy	2	0.640	1.269	0.069
			Max. Vx	14	-0.534	-0.053	-1.429
			Max Tension	11	8.824	0.000	0.000
			Max. Compression	28	-9.333	0.000	0.000
			Max. Mx	32	6.074	0.181	-0.015
			Max. My	21	-8.725	0.101	0.022
		Secondary Horizontal	Max. Vy	32	0.061	0.181	-0.015
			Max. Vx	21	-0.004	0.000	0.000
			Max Tension	2	2.908	0.000	0.000
			Max. Compression	2	-2.908	0.000	0.000
			Max. Mx	18	0.242	-0.237	0.000
			Max. My	31	2.387	0.000	0.007
T14	30 - 20	Leg	Max. Vy	18	0.055	0.000	0.000
			Max. Vx	31	-0.002	0.000	0.000
			Max Tension	15	157.929	1.363	-0.080
			Max. Compression	2	-182.598	1.873	-0.035
			Max. Mx	19	-179.462	-5.753	0.006
			Max. My	14	-9.140	-0.173	-1.318
		Diagonal	Max. Vy	19	3.165	2.153	-0.031
			Max. Vx	14	0.607	-0.238	-1.007
			Max Tension	4	9.038	0.048	-0.003
			Max. Compression	13	-9.591	0.000	0.000
			Max. Mx	19	7.427	0.129	-0.005
			Max. My	28	-8.589	-0.005	-0.008
		Horizontal	Max. Vy	19	-0.045	0.129	-0.005
			Max. Vx	28	-0.002	0.000	0.000
			Max Tension	2	3.167	0.000	0.000
			Max. Compression	2	-3.167	0.040	0.027
			Max. Mx	32	1.663	0.048	0.034
			Max. My	22	1.655	0.046	0.036
Redund Horz 1 Bracing	Max. Vy	32	0.035	0.048	0.034		
	Max. Vx	22	-0.005	0.000	0.000		
	Max Tension	2	3.167	0.000	0.000		
	Max. Compression	2	-3.167	0.000	0.000		
	Max. Mx	33	2.364	-0.013	0.000		
	Max. My	31	2.617	0.000	0.000		
Redund Diag 1 Bracing	Max. Vy	33	0.012	0.000	0.000		
	Max. Vx	31	-0.000	0.000	0.000		
	Max Tension	2	1.847	0.000	0.000		
	Max. Compression	2	-1.847	0.000	0.000		
	Max. Mx	34	0.919	-0.016	0.000		
	Max. My	30	0.511	0.000	0.001		
T15	20 - 15	Leg	Max. Vy	34	0.012	0.000	0.000
			Max. Vx	30	-0.000	0.000	0.000
			Max Tension	15	170.161	2.994	-0.023
			Max. Compression	2	-197.172	4.273	0.037
			Max. Mx	19	-191.572	-5.753	0.006
			Max. My	14	-10.050	-0.238	-1.007
		Diagonal	Max. Vy	19	-3.908	4.006	0.033
			Max. Vx	6	0.587	0.147	0.796
			Max Tension	11	8.854	0.153	0.003
			Max. Compression	28	-9.619	0.000	0.000



<b>tnxTower</b>  <b>URS Corporation</b> 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	<b>Job</b>	152' ROHN SSV Tower	<b>Page</b>	40 of 55
	<b>Project</b>	366 Old Long Ridge Road, Stamford, CT	<b>Date</b>	11:46:06 07/15/14
	<b>Client</b>	Verizon, Sprint and AT&T / S.A. Evaluation	<b>Designed by</b>	MCD

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Force K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft		
T16	15 - 10	Redund Horz 1 Bracing	Max. Mx	13	6.756	0.162	0.003		
			Max. My	21	-8.187	-0.105	0.007		
			Max. Vy	30	-0.050	0.156	0.005		
			Max. Vx	27	0.002	0.000	0.000		
			Max Tension	2	3.419	0.000	0.000		
			Max. Compression	2	-3.419	0.000	0.000		
			Max. Mx	33	0.980	-0.015	0.000		
			Max. My	20	2.982	0.000	0.000		
			Max. Vy	33	0.012	0.000	0.000		
			Max. Vx	20	-0.000	0.000	0.000		
			Max Tension	2	1.985	0.000	0.000		
			Max. Compression	2	-1.985	0.000	0.000		
			Max. Mx	20	0.854	-0.018	0.000		
			Max. My	30	0.029	0.000	0.001		
		Max. Vy	20	0.013	0.000	0.000			
		Max. Vx	30	-0.000	0.000	0.000			
		Leg		Diagonal	Max Tension	15	171.068	-0.662	0.030
					Max. Compression	2	-198.809	0.038	0.005
					Max. Mx	30	-189.630	1.983	-0.045
					Max. My	14	-10.547	-0.113	-1.878
					Max. Vy	32	-0.645	-1.318	0.032
					Max. Vx	14	0.548	-0.113	-1.878
					Max Tension	11	8.416	0.000	0.000
				Horizontal	Max. Compression	28	-9.671	0.000	0.000
					Max. Mx	19	5.399	-0.121	0.000
					Max. My	30	-0.510	0.000	0.004
					Max. Vy	19	0.044	0.000	0.000
					Max. Vx	30	-0.002	0.000	0.000
Max Tension	2				3.448	0.000	0.000		
Max. Compression	2				-3.448	0.051	0.032		
T17	10 - 0	Leg	Max. Mx	19	-0.782	0.116	0.071		
			Max. My	29	-3.110	0.112	0.088		
			Max. Vy	19	-0.047	0.116	0.071		
			Max. Vx	29	0.010	0.000	0.000		
			Max Tension	15	183.278	-0.230	-0.050		
			Max. Compression	2	-213.234	0.000	-0.000		
			Max. Mx	30	-205.599	1.983	-0.045		
		Diagonal	Max. My	14	-10.929	-0.113	-1.878		
			Max. Vy	30	0.270	1.983	-0.045		
			Max. Vx	14	-0.306	-0.113	-1.878		
			Max Tension	28	10.450	0.000	0.000		
			Max. Compression	11	-9.509	0.000	0.000		
			Max. Mx	17	3.965	0.157	-0.016		
			Max. My	29	6.567	0.122	-0.021		
Max. Vy	34	0.063	0.112	0.019					
Max. Vx	29	-0.004	0.000	0.000					

### Maximum Reactions

Location	Condition	Gov. Load Comb.	Vertical K	Horizontal, X K	Horizontal, Z K
Leg C	Max. Vert	13	217.548	21.846	-13.310
	Max. H <sub>x</sub>	13	217.548	21.846	-13.310
	Max. H <sub>z</sub>	21	-167.086	-19.369	12.681

<b>tnxTower</b>  <b>URS Corporation</b> 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	<b>Job</b>	152' ROHN SSV Tower	<b>Page</b>	41 of 55
	<b>Project</b>	366 Old Long Ridge Road, Stamford, CT	<b>Date</b>	11:46:06 07/15/14
	<b>Client</b>	Verizon, Sprint and AT&T / S.A. Evaluation	<b>Designed by</b>	MCD

Location	Condition	Gov. Load Comb.	Vertical K	Horizontal, X K	Horizontal, Z K
Leg B	Min. Vert	5	-188.230	-19.265	11.731
	Min. H <sub>x</sub>	22	-172.616	-20.296	12.307
	Min. H <sub>z</sub>	13	217.548	21.846	-13.310
	Max. Vert	7	217.978	-21.988	-13.159
	Max. H <sub>x</sub>	32	-173.282	20.424	12.173
	Max. H <sub>z</sub>	33	-167.812	19.537	12.483
	Min. Vert	15	-189.174	19.414	11.587
Leg A	Min. H <sub>x</sub>	7	217.978	-21.988	-13.159
	Min. H <sub>z</sub>	7	217.978	-21.988	-13.159
	Max. Vert	2	220.495	-0.201	25.737
	Max. H <sub>x</sub>	14	11.455	4.046	0.791
	Max. H <sub>z</sub>	2	220.495	-0.201	25.737
	Min. Vert	10	-189.001	0.199	-22.679
	Min. H <sub>x</sub>	6	10.662	-4.051	0.731
Min. H <sub>z</sub>	27	-171.327	0.180	-23.800	

### Tower Mast Reaction Summary

Load Combination	Vertical K	Shear <sub>x</sub> K	Shear <sub>z</sub> K	Overtuning Moment, M <sub>x</sub> kip-ft	Overtuning Moment, M <sub>z</sub> kip-ft	Torque kip-ft
Dead Only	30.749	0.000	-0.000	-14.559	2.671	0.000
Dead+Wind 0 deg - No Ice	30.749	-0.048	-43.126	-3783.801	9.823	-7.312
Dead+Wind 30 deg - No Ice	30.749	20.360	-35.536	-3165.771	-1794.247	-15.544
Dead+Wind 45 deg - No Ice	30.749	28.576	-28.757	-2570.475	-2527.377	-17.976
Dead+Wind 60 deg - No Ice	30.749	34.718	-20.145	-1808.709	-3080.397	-19.068
Dead+Wind 90 deg - No Ice	30.749	40.805	0.048	-7.426	-3603.695	-18.485
Dead+Wind 120 deg - No Ice	30.749	37.150	21.604	1876.168	-3233.642	-14.087
Dead+Wind 135 deg - No Ice	30.749	28.644	28.825	2551.347	-2537.637	-7.717
Dead+Wind 150 deg - No Ice	30.749	20.444	35.583	3143.636	-1806.745	-2.955
Dead+Wind 180 deg - No Ice	30.749	0.048	40.372	3585.932	-4.445	7.255
Dead+Wind 210 deg - No Ice	30.749	-20.362	35.536	3136.489	1799.761	15.546
Dead+Wind 225 deg - No Ice	30.749	-28.577	28.757	2541.243	2532.913	17.988
Dead+Wind 240 deg - No Ice	30.749	-37.102	21.522	1863.798	3231.865	21.401
Dead+Wind 270 deg - No Ice	30.749	-40.805	-0.047	-21.694	3609.044	18.485
Dead+Wind 300 deg - No Ice	30.749	-34.765	-20.227	-1821.054	3092.885	11.814
Dead+Wind 315 deg - No Ice	30.749	-28.643	-28.825	-2580.550	2542.827	7.707
Dead+Wind 330 deg - No Ice	30.749	-20.443	-35.584	-3172.890	1811.967	2.962
Dead+Ice+Temp	51.144	0.000	0.000	-33.639	1.393	-0.000
Dead+Wind 0 deg+Ice+Temp	51.144	-0.037	-40.059	-3571.711	6.960	-6.502
Dead+Wind 30 deg+Ice+Temp	51.144	19.195	-33.457	-3020.844	-1705.774	-15.012
Dead+Wind 45 deg+Ice+Temp	51.144	26.999	-27.141	-2460.936	-2405.703	-17.701
Dead+Wind 60 deg+Ice+Temp	51.144	32.878	-19.061	-1740.833	-2936.390	-19.106
Dead+Wind 90 deg+Ice+Temp	51.144	38.454	0.038	-28.105	-3422.664	-18.759
Dead+Wind 120 deg+Ice+Temp	51.144	34.538	20.062	1740.071	-3040.889	-14.176
Dead+Wind 135 deg+Ice+Temp	51.144	27.052	27.193	2401.402	-2413.671	-8.495
Dead+Wind 150 deg+Ice+Temp	51.144	19.260	33.494	2958.977	-1715.475	-3.736
Dead+Wind 180 deg+Ice+Temp	51.144	0.037	38.185	3390.200	-4.115	6.515
Dead+Wind 210 deg+Ice+Temp	51.144	-19.196	33.457	2953.443	1708.720	15.014
Dead+Wind 225 deg+Ice+Temp	51.144	-27.000	27.141	2393.578	2408.662	17.705
Dead+Wind 240 deg+Ice+Temp	51.144	-34.501	19.998	1730.465	3038.178	20.678
Dead+Wind 270 deg+Ice+Temp	51.144	-38.454	-0.036	-39.150	3425.447	18.759
Dead+Wind 300 deg+Ice+Temp	51.144	-32.915	-19.124	-1750.387	2944.699	12.593
Dead+Wind 315 deg+Ice+Temp	51.144	-27.051	-27.193	-2468.733	2416.305	8.489
Dead+Wind 330 deg+Ice+Temp	51.144	-19.259	-33.494	-3026.357	1718.138	3.736
Dead+Wind 0 deg - Service	30.749	-0.017	-14.922	-1318.817	5.144	-2.530
Dead+Wind 30 deg - Service	30.749	7.045	-12.296	-1104.969	-619.123	-5.377

<b>tnxTower</b>  <b>URS Corporation</b> 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	<b>Job</b>	152' ROHN SSV Tower	<b>Page</b>	42 of 55	
	<b>Project</b>	366 Old Long Ridge Road, Stamford, CT		<b>Date</b>	11:46:06 07/15/14
	<b>Client</b>	Verizon, Sprint and AT&T / S.A. Evaluation		<b>Designed by</b>	MCD

Load Combination	Vertical K	Shear <sub>y</sub> K	Shear <sub>z</sub> K	Overturing Moment, M <sub>x</sub> kip-ft	Overturing Moment, M <sub>z</sub> kip-ft	Torque kip-ft
Dead+Wind 45 deg - Service	30.749	9.888	-9.951	-898.987	-872.807	-6.220
Dead+Wind 60 deg - Service	30.749	12.013	-6.971	-635.403	-1064.162	-6.599
Dead+Wind 90 deg - Service	30.749	14.119	0.017	-12.122	-1245.217	-6.400
Dead+Wind 120 deg - Service	30.749	12.855	7.475	639.653	-1117.154	-4.873
Dead+Wind 135 deg - Service	30.749	9.911	9.974	873.285	-876.319	-2.668
Dead+Wind 150 deg - Service	30.749	7.074	12.313	1078.239	-623.417	-1.019
Dead+Wind 180 deg - Service	30.749	0.017	13.970	1231.293	0.208	2.512
Dead+Wind 210 deg - Service	30.749	-7.045	12.296	1075.769	624.494	5.377
Dead+Wind 225 deg - Service	30.749	-9.888	9.951	869.792	878.179	6.222
Dead+Wind 240 deg - Service	30.749	-12.838	7.447	635.376	1120.036	7.404
Dead+Wind 270 deg - Service	30.749	-14.119	-0.016	-17.059	1250.567	6.400
Dead+Wind 300 deg - Service	30.749	-12.030	-6.999	-639.678	1071.980	4.088
Dead+Wind 315 deg - Service	30.749	-9.911	-9.974	-902.476	881.648	2.666
Dead+Wind 330 deg - Service	30.749	-7.074	-12.313	-1107.436	628.750	1.019

## Solution Summary

Load Comb.	Sum of Applied Forces			Sum of Reactions			% Error
	PX K	PY K	PZ K	PX K	PY K	PZ K	
1	0.000	-30.749	0.000	-0.000	30.749	0.000	0.000%
2	-0.048	-30.749	-43.134	0.048	30.749	43.126	0.016%
3	20.365	-30.749	-35.543	-20.360	30.749	35.536	0.017%
4	28.582	-30.749	-28.763	-28.576	30.749	28.757	0.018%
5	34.725	-30.749	-20.149	-34.718	30.749	20.145	0.018%
6	40.813	-30.749	0.048	-40.805	30.749	-0.048	0.017%
7	37.157	-30.749	21.608	-37.150	30.749	-21.604	0.015%
8	28.650	-30.749	28.831	-28.644	30.749	-28.825	0.016%
9	20.448	-30.749	35.591	-20.444	30.749	-35.583	0.017%
10	0.048	-30.749	40.381	-0.048	30.749	-40.372	0.018%
11	-20.365	-30.749	35.543	20.362	30.749	-35.536	0.017%
12	-28.582	-30.749	28.763	28.577	30.749	-28.757	0.016%
13	-37.109	-30.749	21.526	37.102	30.749	-21.522	0.015%
14	-40.813	-30.749	-0.048	40.805	30.749	0.047	0.017%
15	-34.773	-30.749	-20.232	34.765	30.749	20.227	0.018%
16	-28.650	-30.749	-28.831	28.643	30.749	28.825	0.018%
17	-20.448	-30.749	-35.591	20.443	30.749	35.584	0.017%
18	0.000	-51.144	0.000	-0.000	51.144	-0.000	0.000%
19	-0.037	-51.144	-40.072	0.037	51.144	40.059	0.021%
20	19.202	-51.144	-33.469	-19.195	51.144	33.457	0.022%
21	27.009	-51.144	-27.151	-26.999	51.144	27.141	0.022%
22	32.890	-51.144	-19.068	-32.878	51.144	19.061	0.022%
23	38.468	-51.144	0.037	-38.454	51.144	-0.038	0.021%
24	34.549	-51.144	20.068	-34.538	51.144	-20.062	0.020%
25	27.061	-51.144	27.203	-27.052	51.144	-27.193	0.021%
26	19.266	-51.144	33.506	-19.260	51.144	-33.494	0.021%
27	0.037	-51.144	38.200	-0.037	51.144	-38.185	0.022%
28	-19.202	-51.144	33.469	19.196	51.144	-33.457	0.021%
29	-27.009	-51.144	27.151	27.000	51.144	-27.141	0.021%
30	-34.512	-51.144	20.004	34.501	51.144	-19.998	0.020%
31	-38.468	-51.144	-0.037	38.454	51.144	0.036	0.021%
32	-32.927	-51.144	-19.132	32.915	51.144	19.124	0.022%
33	-27.061	-51.144	-27.203	27.051	51.144	27.193	0.022%
34	-19.266	-51.144	-33.506	19.259	51.144	33.494	0.022%
35	-0.017	-30.749	-14.925	0.017	30.749	14.922	0.009%
36	7.047	-30.749	-12.299	-7.045	30.749	12.296	0.009%
37	9.890	-30.749	-9.953	-9.888	30.749	9.951	0.009%
38	12.016	-30.749	-6.972	-12.013	30.749	6.971	0.009%

<b>tnxTower</b>  <b>URS Corporation</b> 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	<b>Job</b> 152' ROHN SSV Tower	<b>Page</b> 43 of 55
	<b>Project</b> 366 Old Long Ridge Road, Stamford, CT	<b>Date</b> 11:46:06 07/15/14
	<b>Client</b> Verizon, Sprint and AT&T / S.A. Evaluation	<b>Designed by</b> MCD

Load Comb.	Sum of Applied Forces			Sum of Reactions			% Error
	PX K	PY K	PZ K	PX K	PY K	PZ K	
39	14.122	-30.749	0.017	-14.119	30.749	-0.017	0.009%
40	12.857	-30.749	7.477	-12.855	30.749	-7.475	0.009%
41	9.913	-30.749	9.976	-9.911	30.749	-9.974	0.009%
42	7.075	-30.749	12.315	-7.074	30.749	-12.313	0.009%
43	0.017	-30.749	13.973	-0.017	30.749	-13.970	0.009%
44	-7.047	-30.749	12.299	7.045	30.749	-12.296	0.009%
45	-9.890	-30.749	9.953	9.888	30.749	-9.951	0.009%
46	-12.841	-30.749	7.448	12.838	30.749	-7.447	0.009%
47	-14.122	-30.749	-0.017	14.119	30.749	0.016	0.009%
48	-12.032	-30.749	-7.001	12.030	30.749	6.999	0.009%
49	-9.913	-30.749	-9.976	9.911	30.749	9.974	0.009%
50	-7.075	-30.749	-12.315	7.074	30.749	12.313	0.009%

### Non-Linear Convergence Results

Load Combination	Converged?	Number of Cycles	Displacement Tolerance	Force Tolerance
1	Yes	4	0.00000001	0.00000001
2	Yes	4	0.00017843	0.00035923
3	Yes	4	0.00019246	0.00038685
4	Yes	4	0.00020170	0.00040479
5	Yes	4	0.00020558	0.00041232
6	Yes	4	0.00019300	0.00038744
7	Yes	4	0.00017861	0.00035913
8	Yes	4	0.00018327	0.00036928
9	Yes	4	0.00019279	0.00038798
10	Yes	4	0.00020562	0.00041337
11	Yes	4	0.00019301	0.00038779
12	Yes	4	0.00018342	0.00036882
13	Yes	4	0.00017873	0.00035865
14	Yes	4	0.00019321	0.00038766
15	Yes	4	0.00020558	0.00041281
16	Yes	4	0.00020164	0.00040527
17	Yes	4	0.00019246	0.00038730
18	Yes	4	0.00000001	0.00006344
19	Yes	4	0.00032503	0.00062535
20	Yes	4	0.00033933	0.00065077
21	Yes	4	0.00034836	0.00066761
22	Yes	4	0.00035211	0.00067486
23	Yes	4	0.00033921	0.00065151
24	Yes	4	0.00032558	0.00062535
25	Yes	4	0.00032998	0.00063464
26	Yes	4	0.00033920	0.00065181
27	Yes	4	0.00035151	0.00067604
28	Yes	4	0.00033980	0.00065144
29	Yes	4	0.00033078	0.00063390
30	Yes	4	0.00032608	0.00062450
31	Yes	4	0.00033935	0.00065135
32	Yes	4	0.00035164	0.00067518
33	Yes	4	0.00034763	0.00066794
34	Yes	4	0.00033840	0.00065103
35	Yes	4	0.00000001	0.00037143
36	Yes	4	0.00000001	0.00038077
37	Yes	4	0.00000001	0.00038692
38	Yes	4	0.00000001	0.00038957
39	Yes	4	0.00000001	0.00038073

<b>tnxTower</b>  <b>URS Corporation</b> 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	<b>Job</b>	152' ROHN SSV Tower	<b>Page</b>	44 of 55
	<b>Project</b>	366 Old Long Ridge Road, Stamford, CT	<b>Date</b>	11:46:06 07/15/14
	<b>Client</b>	Verizon, Sprint and AT&T / S.A. Evaluation	<b>Designed by</b>	MCD

40	Yes	4	0.00000001	0.00037079
41	Yes	4	0.00000001	0.00037438
42	Yes	4	0.00000001	0.00038052
43	Yes	4	0.00000001	0.00038928
44	Yes	4	0.00000001	0.00038004
45	Yes	4	0.00000001	0.00037372
46	Yes	4	0.00000001	0.00037012
47	Yes	4	0.00000001	0.00038031
48	Yes	4	0.00000001	0.00038936
49	Yes	4	0.00000001	0.00038684
50	Yes	4	0.00000001	0.00038081

### Maximum Tower Deflections - Service Wind

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
T1	152 - 140	4.165	35	0.2337	0.0047
T2	140 - 135	3.571	35	0.2283	0.0074
T3	135 - 130	3.325	35	0.2242	0.0099
T4	130 - 125	3.088	35	0.2180	0.0112
T5	125 - 120	2.855	35	0.2098	0.0115
T6	120 - 100	2.630	35	0.1993	0.0117
T7	100 - 80	1.827	35	0.1696	0.0104
T8	80 - 73.3333	1.165	35	0.1272	0.0086
T9	73.3333 - 66.6667	0.981	35	0.1165	0.0078
T10	66.6667 - 60	0.816	35	0.1052	0.0070
T11	60 - 50	0.664	35	0.0932	0.0061
T12	50 - 40	0.470	35	0.0782	0.0051
T13	40 - 30	0.308	35	0.0625	0.0041
T14	30 - 20	0.181	35	0.0461	0.0031
T15	20 - 15	0.087	35	0.0294	0.0021
T16	15 - 10	0.049	35	0.0207	0.0015
T17	10 - 0	0.024	35	0.0118	0.0009

### Critical Deflections and Radius of Curvature - Service Wind

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
162.00	20' 4-Bay Dipole	35	4.165	0.2337	0.0047	Inf
156.70	DB563K-CR	35	4.165	0.2337	0.0047	Inf
152.00	4' w/Radome	35	4.165	0.2337	0.0047	Inf
151.25	DB803KHE-YP	35	4.128	0.2334	0.0043	Inf
149.00	3' Sidearm	35	4.017	0.2326	0.0043	Inf
148.50	3' Sidearm	35	3.992	0.2325	0.0044	Inf
146.00	12'x2 1/2" STD Pipe Mount	35	3.868	0.2315	0.0050	949526
144.00	12' x 3" Dia Omni	35	3.769	0.2306	0.0060	692894
143.00	4'x3" Pipe Mount	35	3.719	0.2301	0.0063	528557
142.00	4'x4" Pipe Mount	35	3.670	0.2295	0.0066	355999
141.70	DB563K-CR	35	3.655	0.2294	0.0067	311557
140.00	4' w/Radome	35	3.571	0.2283	0.0074	142572
138.00	6' x 3" Dia Omni	35	3.472	0.2269	0.0083	65647
137.00	4' Side Mount Standoff (1)	35	3.423	0.2260	0.0089	51056
136.50	2' w/Radome	35	3.398	0.2256	0.0092	46474
135.00	4'x4" Pipe Mount	35	3.325	0.2242	0.0099	39509

<b>tnxTower</b>  <b>URS Corporation</b> 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	<b>Job</b>	152' ROHN SSV Tower	<b>Page</b>	45 of 55
	<b>Project</b>	366 Old Long Ridge Road, Stamford, CT	<b>Date</b>	11:46:06 07/15/14
	<b>Client</b>	Verizon, Sprint and AT&T / S.A. Evaluation	<b>Designed by</b>	MCD

Elevation	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
133.50	3' Sidearm	35	3.253	0.2225	0.0104	39873
133.00	4' Side Mount Standoff (1)	35	3.229	0.2220	0.0106	41094
128.00	(2) DB980H90E-M	35	2.994	0.2151	0.0114	52555
122.00	DB254-A	35	2.719	0.2035	0.0116	32778
108.00	APX16DWV-16DWV-S-E-ACU w/ Mount	35	2.131	0.1812	0.0111	33828
101.00	2" Dia 10' Omni	35	1.864	0.1713	0.0105	37510
98.00	Valmont 13' Lightweight T-Frame	35	1.754	0.1659	0.0102	36831
95.50	3' Sidearm	35	1.665	0.1608	0.0100	35076
94.50	3' Sidearm	35	1.630	0.1586	0.0099	34327
89.50	3' Sidearm	35	1.460	0.1473	0.0095	31013
79.00	4' x 3" DIA Omni	35	1.136	0.1255	0.0085	26646
78.00	8' 2-Bay Dipole	35	1.108	0.1238	0.0084	26674
72.50	3' Sidearm	35	0.960	0.1152	0.0077	30090
72.00	Scala Yagi w/ Radome	35	0.947	0.1144	0.0077	30946
58.00	GPS	35	0.622	0.0900	0.0059	28352
57.00	2' Sidearm	35	0.601	0.0884	0.0058	29057
45.00	1.2M	35	0.385	0.0706	0.0046	38242
44.00	4'x4" Stand-off	35	0.369	0.0690	0.0045	37862

### Maximum Tower Deflections - Design Wind

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
T1	152 - 140	11.926	2	0.6674	0.0135
T2	140 - 135	10.228	2	0.6520	0.0292
T3	135 - 130	9.527	2	0.6404	0.0351
T4	130 - 125	8.847	2	0.6231	0.0373
T5	125 - 120	8.183	2	0.5999	0.0374
T6	120 - 100	7.539	2	0.5700	0.0369
T7	100 - 80	5.239	2	0.4852	0.0312
T8	80 - 73.3333	3.342	2	0.3643	0.0252
T9	73.3333 - 66.6667	2.816	2	0.3337	0.0227
T10	66.6667 - 60	2.342	2	0.3013	0.0202
T11	60 - 50	1.906	2	0.2671	0.0177
T12	50 - 40	1.349	2	0.2242	0.0148
T13	40 - 30	0.887	2	0.1792	0.0118
T14	30 - 20	0.520	2	0.1321	0.0091
T15	20 - 15	0.249	2	0.0841	0.0060
T16	15 - 10	0.141	2	0.0593	0.0044
T17	10 - 0	0.071	2	0.0339	0.0027

### Critical Deflections and Radius of Curvature - Design Wind

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
162.00	20' 4-Bay Dipole	2	11.926	0.6674	0.0135	333631
156.70	DB563K-CR	2	11.926	0.6674	0.0135	333631
152.00	4' w/Radome	2	11.926	0.6674	0.0135	333631
151.25	DB803KHE-YP	2	11.820	0.6667	0.0124	333631

<b>Job</b>	152' ROHN SSV Tower	<b>Page</b>	46 of 55
<b>Project</b>	366 Old Long Ridge Road, Stamford, CT	<b>Date</b>	11:46:06 07/15/14
<b>Client</b>	Verizon, Sprint and AT&T / S.A. Evaluation	<b>Designed by</b>	MCD

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
149.00	3' Sidearm	2	11,501	0.6643	0.0157	333631
148.50	3' Sidearm	2	11,430	0.6638	0.0164	333631
146.00	12'x2 1/2" STD Pipe Mount	2	11,077	0.6610	0.0208	278026
144.00	12' x 3" Dia Omni	2	10,794	0.6584	0.0241	204933
143.00	4'x3" Pipe Mount	2	10,652	0.6569	0.0256	164838
142.00	4'x4" Pipe Mount	2	10,511	0.6554	0.0270	121057
141.70	DB563K-CR	2	10,469	0.6549	0.0274	108830
140.00	4' w/Radome	2	10,228	0.6520	0.0292	50849
138.00	6' x 3" Dia Omni	2	9,946	0.6479	0.0318	23599
137.00	4' Side Mount Standoff (1)	2	9,805	0.6457	0.0330	18231
136.50	2' w/Radome	2	9,735	0.6444	0.0336	16558
135.00	4'x4" Pipe Mount	2	9,527	0.6404	0.0351	14027
133.50	3' Sidearm	2	9,321	0.6358	0.0361	14151
133.00	4' Side Mount Standoff (1)	2	9,252	0.6342	0.0364	14590
128.00	(2) DB980H90E-M	2	8,579	0.6148	0.0375	18803
122.00	DB254-A	2	7,793	0.5820	0.0371	11542
108.00	APX16DWV-16DWV-S-E-ACU w/ Mount	2	6,110	0.5185	0.0338	11859
101.00	2" Dia 10' Omni	2	5,345	0.4901	0.0315	13182
98.00	Valmont 13' Lightweight T-Frame	2	5,031	0.4747	0.0306	12939
95.50	3' Sidearm	2	4,776	0.4601	0.0298	12310
94.50	3' Sidearm	2	4,675	0.4540	0.0296	12042
89.50	3' Sidearm	2	4,189	0.4217	0.0281	10858
79.00	4' x 3" DIA Omni	2	3,260	0.3593	0.0248	9319
78.00	8' 2-Bay Dipole	2	3,178	0.3546	0.0244	9336
72.50	3' Sidearm	2	2,754	0.3299	0.0224	10556
72.00	Scala Yagi w/ Radome	2	2,718	0.3276	0.0222	10851
58.00	GPS	2	1,786	0.2578	0.0171	9923
57.00	2' Sidearm	2	1,727	0.2534	0.0167	10172
45.00	1.2M	2	1,107	0.2023	0.0133	13326
44.00	4'x4" Stand-off	2	1,061	0.1977	0.0130	13180

**Bolt Design Data**

Section No.	Elevation ft	Component Type	Bolt Grade	Bolt Size in	Number Of Bolts	Maximum Load per Bolt K	Allowable Load K	Ratio Load Allowable	Allowable Ratio	Criteria
T1	152	Diagonal	A325N	0.500	1	1,915	2,719	0.704	1.333	Member Bearing
		Top Girt	A325N	0.500	1	0,287	2,719	0.106	1.333	Member Bearing
T2	140	Leg	A325N	0.625	4	1,424	13,435	0.106	1.333	Bolt Tension
		Diagonal	A325N	0.500	1	2,776	4,078	0.681	1.333	Member Bearing
		Top Girt	A325N	0.500	1	0,144	2,719	0,053	1.333	Member Bearing
T3	135	Diagonal	A325N	0.500	1	2,604	4,078	0.639	1.333	Member Bearing
T4	130	Diagonal	A325N	0.500	1	3,479	4,123	0.844	1.333	Bolt Shear
T5	125	Diagonal	A325N	0.500	1	3,945	4,078	0.967	1.333	Member Bearing
T6	120	Leg	A325N	0.625	4	7,682	13,499	0.569	1.333	Bolt Tension
		Diagonal	A325N	0.500	1	4,607	4,123	1,117	1.333	Bolt Shear
T7	100	Leg	A325N	0.750	4	13,969	19,430	0.719	1.333	Bolt Tension
		Diagonal	A325X	0.500	1	6,897	5,438	1,268	1.333	Member Bearing

<b>tnxTower</b>  <b>URS Corporation</b> 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	<b>Job</b> 152' ROHN SSV Tower	<b>Page</b> 47 of 55
	<b>Project</b> 366 Old Long Ridge Road, Stamford, CT	<b>Date</b> 11:46:06 07/15/14
	<b>Client</b> Verizon, Sprint and AT&T / S.A. Evaluation	<b>Designed by</b> MCD

Section No.	Elevation ft	Component Type	Bolt Grade	Bolt Size in	Number Of Bolts	Maximum Load per Bolt K	Allowable Load K	Ratio Load Allowable	Allowable Ratio	Criteria	
T8	80	Secondary Horizontal	A325N	0.500	2	0.768	4.123	0.186	✓	1.333	Bolt Shear
		Leg	A325N	0.875	4	21.837	26.458	0.825	✓	1.333	Bolt Tension
T9	73.3333	Diagonal	A325X	0.500	1	6.790	5.438	1.249	✓	1.333	Member Bearing
		Diagonal	A325X	0.500	1	7.190	5.890	1.221	✓	1.333	Bolt Shear
T10	66.6667	Secondary Horizontal	A325N	0.500	2	0.965	4.123	0.234	✓	1.333	Bolt Shear
		Diagonal	A325X	0.500	1	7.191	5.890	1.221	✓	1.333	Bolt Shear
T11	60	Secondary Horizontal	A325N	0.500	2	1.063	4.123	0.258	✓	1.333	Bolt Shear
		Leg	A325N	0.875	4	29.567	26.458	1.117	✓	1.333	Bolt Tension
T12	50	Diagonal	A325X	0.625	1	8.153	8.496	0.960	✓	1.333	Member Bearing
		Diagonal	A325X	0.625	1	8.601	8.496	1.012	✓	1.333	Member Bearing
T13	40	Secondary Horizontal	A325N	0.500	2	1.317	4.123	0.320	✓	1.333	Bolt Shear
		Leg	A325N	1.000	4	36.392	34.557	1.053	✓	1.333	Bolt Tension
T14	30	Diagonal	A325X	0.625	1	9.333	9.204	1.014	✓	1.333	Bolt Shear
		Secondary Horizontal	A325N	0.500	2	1.454	4.123	0.353	✓	1.333	Bolt Shear
T15	20	Diagonal	A325X	0.625	1	9.038	8.496	1.064	✓	1.333	Member Bearing
		Horizontal	A325N	0.500	2	1.584	4.123	0.384	✓	1.333	Bolt Shear
T16	15	Leg	A325N	1.000	4	42.540	34.529	1.232	✓	1.333	Bolt Tension
		Diagonal	A325X	0.625	1	8.854	6.797	1.303	✓	1.333	Member Bearing
T17	10	Diagonal	A325X	0.625	1	8.416	6.797	1.238	✓	1.333	Member Bearing
		Horizontal	A325N	0.625	1	3.448	6.443	0.535	✓	1.333	Bolt Shear
		Diagonal	A325X	0.625	1	10.451	8.496	1.230	✓	1.333	Member Bearing

### Compression Checks

### Leg Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L <sub>u</sub> ft	Kl/r	F <sub>a</sub> ksi	A in <sup>2</sup>	Actual P K	Allow. P <sub>a</sub> K	Ratio P P <sub>a</sub>
T1	152 - 140	ROHN 2 STD	12.00	3.94	60.1 K=1.00	22.695	1.075	-7.018	24.386	0.288
T2	140 - 135	ROHN 2.5 STD	5.01	4.84	61.3 K=1.00	22.491	1.704	-12.229	38.325	0.319
T3	135 - 130	ROHN 2.5 STD	5.01	5.01	63.4 K=1.00	22.122	1.704	-14.620	37.698	0.388
T4	130 - 125	ROHN 2.5 STD	5.01	5.01	63.4 K=1.00	22.122	1.704	-20.859	37.698	0.553
T5	125 - 120	ROHN 2.5 STD	5.01	5.01	63.4	22.122	1.704	-27.981	37.698	0.742



<b>tnxTower</b>  <b>URS Corporation</b> 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	<b>Job</b>	152' ROHN SSV Tower	<b>Page</b>	48 of 55
	<b>Project</b>	366 Old Long Ridge Road, Stamford, CT	<b>Date</b>	11:46:06 07/15/14
	<b>Client</b>	Verizon, Sprint and AT&T / S.A. Evaluation	<b>Designed by</b>	MCD

Section No.	Elevation ft	Size	L ft	L <sub>u</sub> ft	Kl/r	F <sub>a</sub> ksi	A in <sup>2</sup>	Actual P K	Allow. P <sub>a</sub> K	Ratio P P <sub>a</sub>
T6	120 - 100	Rohn 2.5 X-Str w/ (3) 1.5"x0.25" Bars	20.03	6.68	K=1.00 67.8	21.334	3.413	-53.902	72.823	0.740
T7	100 - 80	Rohn 2.5 X-Str w/ (3) 1.5"x0.25" Bars	20.03	3.44	K=1.00 35.0	26.516	3.413	-88.559	90.509	0.978
T8	80 - 73.3333	Rohn 3 X-Str w/ (3) 1.5"x0.5" Bars	6.68	6.68	K=1.00 55.1	23.542	5.275	-100.326	124.180	0.808
T9	73.3333 - 66.6667	Rohn 3 X-Str w/ (3) 1.5"x0.5" Bars	6.68	3.42	K=1.00 28.2	27.368	5.275	-111.296	144.363	0.771
T10	66.6667 - 60	Rohn 3 X-Str w/ (3) 1.5"x0.5" Bars	6.68	3.42	K=1.00 28.2	27.372	5.275	-122.542	144.385	0.849
T11	60 - 50	Rohn 4 X-Str w/ (3) 1.5"x0.5" Bars	10.02	10.02	K=1.00 69.4	21.056	6.640	-135.919	139.821	0.972
T12	50 - 40	Rohn 4 X-Str w/ (3) 1.5"x0.5" Bars	10.02	5.16	K=1.00 35.7	26.414	6.640	-151.941	175.395	0.866
T13	40 - 30	Rohn 4 X-Str w/ (3) 1.5"x0.5" Bars	10.02	5.15	K=1.00 35.7	26.422	6.640	-167.671	175.450	0.956
T14	30 - 20	Rohn 4 X-Str w/ (3) 1.5"x0.5" Bars	10.02	2.50	K=1.00 17.3	28.573	6.640	-182.598	189.733	0.962
T15	20 - 15	Rohn 5 STD w/ (3) 1.5"x0.5" Bars	5.01	2.50	K=1.00 14.2	28.881	6.555	-197.172	189.312	1.042
T16	15 - 10	Rohn 5 STD w/ (3) 1.5"x0.5" Bars	5.01	5.01	K=1.00 28.4	27.353	6.555	-198.809	179.298	1.109
T17	10 - 0	Rohn 5 STD w/ (6) 1.5"x0.5" Bars	10.02	10.02	K=1.00 56.9	23.237	9.761	-213.234	226.818	0.940

### Diagonal Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L <sub>u</sub> ft	Kl/r	F <sub>a</sub> ksi	A in <sup>2</sup>	Actual P K	Allow. P <sub>a</sub> K	Ratio P P <sub>a</sub>
T1	152 - 140	L1 1/2x1 1/2x1/8	7.65	3.61	K=1.00 146.2	6.982	0.359	-1.935	2.509	0.771
T2	140 - 135	L1 1/2x1 1/2x3/16	8.35	4.07	K=1.00 166.7	5.376	0.527	-2.788	2.835	0.983
T3	135 - 130	L1 1/2x1 1/2x3/16	8.86	4.33	K=1.00 177.2	4.755	0.527	-2.612	2.508	1.041
T4	130 - 125	L1 1/2x1 1/2x1/4	9.28	4.54	K=1.00 186.6	4.289	0.688	-3.479	2.949	1.180
T5	125 - 120	L1 3/4x1 3/4x3/16	9.70	4.75	K=1.00 166.1	5.415	0.621	-3.948	3.364	1.174
T6	120 - 100	L2x2x1/4	12.21	5.94	K=1.00 182.3	4.492	0.938	-4.607	4.213	1.093
T7	100 - 80	L2 1/2x2 1/2x1/4	13.96	6.82	K=1.00 166.7	5.372	1.190	-6.830	6.392	1.069
T8	80 - 73.3333	L2 1/2x2 1/2x1/4	14.57	7.10	K=1.00 173.6	4.958	1.190	-6.848	5.900	1.161
T9	73.3333 - 66.6667	L2 1/2x2 1/2x5/16	15.19	7.41	K=1.00 181.9	4.511	1.460	-7.190	6.586	1.092
T10	66.6667 - 60	L2 1/2x2 1/2x5/16	15.82	7.73	189.7	4.150	1.460	-7.178	6.059	1.185

<b>tnxTower</b>  <b>URS Corporation</b> 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	<b>Job</b>	152' ROHN SSV Tower	<b>Page</b>	49 of 55
	<b>Project</b>	366 Old Long Ridge Road, Stamford, CT	<b>Date</b>	11:46:06 07/15/14
	<b>Client</b>	Verizon, Sprint and AT&T / S.A. Evaluation	<b>Designed by</b>	MCD

Section No.	Elevation ft	Size	L ft	L <sub>u</sub> ft	KL/r	F <sub>a</sub> ksi	A in <sup>2</sup>	Actual P K	Allow. P <sub>a</sub> K	Ratio $\frac{P}{P_a}$
T11	60 - 50	L3x3x5/16	18.20	8.94	K=1.00 182.2	4.501	1,780	-8.503	8.011	1.061
T12	50 - 40	L3x3x5/16	19.04	9.36	K=1.00 190.8	4.104	1,780	-8.569	7.305	1.173
T13	40 - 30	L3x3x3/8	19.90	9.79	K=1.00 200.2	3.726	2.110	-9.333	7.863	1.187
T14	30 - 20	KL/R > 200 (C) - 177 L3x3x5/16	10.64	10.08	K=1.00 131.2	8.681	1.780	-9.591	15.452	0.621
T15	20 - 15	L3 1/2x3 1/2x1/4	10.64	10.08	K=1.04 115.5	10.922	1.690	-9.619	18.459	0.521
T16	15 - 10	L3 1/2x3 1/2x1/4	11.08	10.49	K=1.00 181.3	4.542	1.690	-9.671	7.676	1.260
T17	10 - 0	L3 1/2x3 1/2x5/16	22.61	11.11	K=1.00 193.2	4.000	2.090	-9.509	8.360	1.137

### Horizontal Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L <sub>u</sub> ft	KL/r	F <sub>a</sub> ksi	A in <sup>2</sup>	Actual P K	Allow. P <sub>a</sub> K	Ratio $\frac{P}{P_a}$
T14	30 - 20	L3x3x3/16	18.23	17.34	K=0.82 182.5	4.485	1.090	-3.167	4.888	0.648
T16	15 - 10	L2.875x2.875x0.25	19.26	18.38	K=1.00 247.8	2.432	1.375	-3.448	3.343	1.031
KL/R > 200 (C) - 233										

### Secondary Horizontal Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L <sub>u</sub> ft	KL/r	F <sub>a</sub> ksi	A in <sup>2</sup>	Actual P K	Allow. P <sub>a</sub> K	Ratio $\frac{P}{P_a}$
T7	100 - 80	L3x3x3/16	12.25	11.49	K=0.83 191.9	4.054	1.090	-1.536	4.419	0.348
T9	73.3333 - 66.6667	L3x3x3/16	13.64	12.82	K=0.81 210.2	3.379	1.090	-1.930	3.683	0.524
T10	66.6667 - 60	L3x3x3/16	14.34	13.52	K=0.81 219.7	3.093	1.090	-2.125	3.371	0.630
T12	50 - 40	L3x3x3/16	16.18	15.29	K=0.79 243.6	2.518	1.090	-2.635	2.744	0.960
T13	40 - 30	L3x3x3/16	17.18	16.29	K=0.78 256.9	2.263	1.090	-2.908	2.467	1.179
KL/R > 250 (C) - 179										

<b>tnxTower</b>  <b>URS Corporation</b> 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	<b>Job</b> 152' ROHN SSV Tower	<b>Page</b> 50 of 55
	<b>Project</b> 366 Old Long Ridge Road, Stamford, CT	<b>Date</b> 11:46:06 07/15/14
	<b>Client</b> Verizon, Sprint and AT&T / S.A. Evaluation	<b>Designed by</b> MCD

**Top Girt Design Data (Compression)**

Section No.	Elevation ft	Size	L ft	L <sub>u</sub> ft	Kl/r	F <sub>a</sub> ksi	A in <sup>2</sup>	Actual P K	Allow. P <sub>a</sub> K	Ratio $\frac{P}{P_u}$
T1	152 - 140	L2x2x1/8	6.52	6.11	184.6 K=1.00	4.383	0.484	-0.284	2.123	0.134
T2	140 - 135	L2x2x1/8	6.57	6.12	184.8 K=1.00	4.372	0.484	-0.157	2.117	0.074

**Redundant Horizontal (1) Design Data (Compression)**

Section No.	Elevation ft	Size	L ft	L <sub>u</sub> ft	Kl/r	F <sub>a</sub> ksi	A in <sup>2</sup>	Actual P K	Allow. P <sub>a</sub> K	Ratio $\frac{P}{P_u}$
T14	30 - 20	L2x2x1/4	4.56	4.28	131.3 K=1.00	8.665	0.938	-3.167	8.127	0.390
T15	20 - 15	L2x2x1/4	4.82	4.50	138.0 K=1.00	7.843	0.938	-3.419	7.357	0.465

**Redundant Diagonal (1) Design Data (Compression)**

Section No.	Elevation ft	Size	L ft	L <sub>u</sub> ft	Kl/r	F <sub>a</sub> ksi	A in <sup>2</sup>	Actual P K	Allow. P <sub>a</sub> K	Ratio $\frac{P}{P_u}$
T14	30 - 20	L2x2x1/4	5.32	4.99	153.3 K=1.00	6.355	0.938	-1.847	5.961	0.310
T15	20 - 15	L2x2x1/4	5.53	5.18	158.9 K=1.00	5.915	0.938	-1.985	5.549	0.358

**Tension Checks**

**Leg Design Data (Tension)**

Section No.	Elevation ft	Size	L ft	L <sub>u</sub> ft	Kl/r	F <sub>a</sub> ksi	A in <sup>2</sup>	Actual P K	Allow. P <sub>a</sub> K	Ratio $\frac{P}{P_u}$
T1	152 - 140	ROHN 2 STD	12.00	3.94	60.1	30.000	1.075	5.558	32.236	0.172
T2	140 - 135	ROHN 2.5 STD	5.01	4.84	61.3	30.000	1.704	10.129	51.121	0.198
T3	135 - 130	ROHN 2.5 STD	5.01	5.01	63.4	30.000	1.704	12.214	51.121	0.239
T4	130 - 125	ROHN 2.5 STD	5.01	5.01	63.4	30.000	1.704	17.210	51.121	0.337

<b>tnxTower</b>  <b>URS Corporation</b> 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	<b>Job</b> 152' ROHN SSV Tower	<b>Page</b> 51 of 55
	<b>Project</b> 366 Old Long Ridge Road, Stamford, CT	<b>Date</b> 11:46:06 07/15/14
	<b>Client</b> Verizon, Sprint and AT&T / S.A. Evaluation	<b>Designed by</b> MCD

Section No.	Elevation ft	Size	L ft	L <sub>u</sub> ft	Kl/r	F <sub>a</sub> ksi	A in <sup>2</sup>	Actual P K	Allow. P <sub>a</sub> K	Ratio P/P <sub>a</sub>
T5	125 - 120	ROHN 2.5 STD	5.01	5.01	63.4	30.000	1.704	23.212	51.121	0.454
T6	120 - 100	Rohn 2.5 X-Str w/ (3) 1.5"x0.25" Bars	20.03	6.68	67.8	30.000	3.413	47.129	102.402	0.460
T7	100 - 80	Rohn 2.5 X-Str w/ (3) 1.5"x0.25" Bars	20.03	3.44	35.0	30.000	3.413	76.836	102.402	0.750
T8	80 - 73.3333	Rohn 3 X-Str w/ (3) 1.5"x0.5" Bars	6.68	6.68	55.1	30.000	5.275	87.346	158.247	0.552
T9	73.3333 - 66.6667	Rohn 3 X-Str w/ (3) 1.5"x0.5" Bars	6.68	3.42	28.2	30.000	5.275	96.963	158.247	0.613
T10	66.6667 - 60	Rohn 3 X-Str w/ (3) 1.5"x0.5" Bars	6.68	3.42	28.2	30.000	5.275	106.572	158.247	0.673
T11	60 - 50	Rohn 4 X-Str w/ (3) 1.5"x0.5" Bars	10.02	10.02	69.4	30.000	6.640	118.266	199.209	0.594
T12	50 - 40	Rohn 4 X-Str w/ (3) 1.5"x0.5" Bars	10.02	5.16	35.7	30.000	6.640	132.090	199.209	0.663
T13	40 - 30	Rohn 4 X-Str w/ (3) 1.5"x0.5" Bars	10.02	5.15	35.7	30.000	6.640	145.569	199.209	0.731
T14	30 - 20	Rohn 4 X-Str w/ (3) 1.5"x0.5" Bars	10.02	2.50	17.3	30.000	6.640	157.929	199.209	0.793
T15	20 - 15	Rohn 5 STD w/ (3) 1.5"x0.5" Bars	5.01	2.50	14.2	30.000	6.555	170.161	196.650	0.865
T16	15 - 10	Rohn 5 STD w/ (3) 1.5"x0.5" Bars	5.01	5.01	28.4	30.000	6.555	171.068	196.650	0.870
T17	10 - 0	Rohn 5 STD w/ (6) 1.5"x0.5" Bars	10.02	10.02	56.9	30.000	9.761	183.278	292.833	0.626

### Diagonal Design Data (Tension)

Section No.	Elevation ft	Size	L ft	L <sub>u</sub> ft	Kl/r	F <sub>a</sub> ksi	A in <sup>2</sup>	Actual P K	Allow. P <sub>a</sub> K	Ratio P/P <sub>a</sub>
T1	152 - 140	L1 1/2x1 1/2x1/8	7.65	3.61	95.8	29.000	0.211	1.915	6.117	0.313
T2	140 - 135	L1 1/2x1 1/2x3/16	8.35	4.07	109.8	29.000	0.308	2.776	8.921	0.311
T3	135 - 130	L1 1/2x1 1/2x3/16	8.86	4.33	116.6	29.000	0.308	2.604	8.921	0.292
T4	130 - 125	L1 1/2x1 1/2x1/4	9.28	4.54	124.2	29.000	0.398	3.424	11.555	0.296
T5	125 - 120	L1 3/4x1 3/4x3/16	9.70	4.75	108.5	29.000	0.378	3.945	10.960	0.360
T6	120 - 100	L2x2x1/4	12.21	5.94	119.1	29.000	0.586	4.531	17.003	0.266
T7	100 - 80	L2 1/2x2 1/2x1/4	13.37	6.53	103.5	29.000	0.775	6.897	22.484	0.307
T8	80 - 73.3333	L2 1/2x2 1/2x1/4	14.57	7.10	112.4	29.000	0.775	6.790	22.484	0.302
T9	73.3333 - 66.6667	L2 1/2x2 1/2x5/16	15.19	7.41	118.6	29.000	0.949	7.057	27.507	0.257

<b>tnxTower</b>  <b>URS Corporation</b> 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	<b>Job</b> 152' ROHN SSV Tower	<b>Page</b> 52 of 55
	<b>Project</b> 366 Old Long Ridge Road, Stamford, CT	<b>Date</b> 11:46:06 07/15/14
	<b>Client</b> Verizon, Sprint and AT&T / S.A. Evaluation	<b>Designed by</b> MCD

Section No.	Elevation ft	Size	L ft	L <sub>u</sub> ft	Kl/r	F <sub>a</sub> ksi	A in <sup>2</sup>	Actual P K	Allow. P <sub>a</sub> K	Ratio P P <sub>a</sub>
T10	66.6667 - 60	L2 1/2x2 1/2x5/16	15.82	7.73	123.5	29,000	0.949	7,191	27,507	0.261
T11	60 - 50	L3x3x5/16	18.20	8.94	117.9	29,000	1.159	8,153	33,617	0.243
T12	50 - 40	L3x3x5/16	19.04	9.36	123.4	29,000	1.159	8,601	33,617	0.256
T13	40 - 30	L3x3x3/8	19.90	9.79	130.3	29,000	1.372	8,824	39,775	0.222
T14	30 - 20	L3x3x5/16	10.64	10.08	134.3	29,000	1.159	9,038	33,617	0.269
T15	20 - 15	L3 1/2x3 1/2x1/4	10.64	10.08	113.6	29,000	1.127	8,854	32,679	0.271
T16	15 - 10	L3 1/2x3 1/2x1/4	11.08	10.49	118.1	29,000	1.127	8,416	32,679	0.258
T17	10 - 0	L3 1/2x3 1/2x5/16	22.61	11.11	124.8	29,000	1.392	10,451	40,360	0.259

**Horizontal Design Data (Tension)**

Section No.	Elevation ft	Size	L ft	L <sub>u</sub> ft	Kl/r	F <sub>a</sub> ksi	A in <sup>2</sup>	Actual P K	Allow. P <sub>a</sub> K	Ratio P P <sub>a</sub>
T14	30 - 20	L3x3x3/16	18.23	17.34	225.8	29,000	0.730	3,167	21,159	0.150
T16	15 - 10	L2.875x2.875x0.25	19.26	18.38	251.1	29,000	0.891	3,448	25,828	0.134

**Secondary Horizontal Design Data (Tension)**

Section No.	Elevation ft	Size	L ft	L <sub>u</sub> ft	Kl/r	F <sub>a</sub> ksi	A in <sup>2</sup>	Actual P K	Allow. P <sub>a</sub> K	Ratio P P <sub>a</sub>
T7	100 - 80	L3x3x3/16	12.25	11.49	151.1	29,000	0.730	1,536	21,159	0.073
T9	73.3333 - 66.6667	L3x3x3/16	13.64	12.82	168.1	29,000	0.730	1,930	21,159	0.091
T10	66.6667 - 60	L3x3x3/16	14.34	13.52	177.0	29,000	0.730	2,125	21,159	0.100
T12	50 - 40	L3x3x3/16	16.18	15.29	199.6	29,000	0.730	2,635	21,159	0.125
T13	40 - 30	L3x3x3/16	17.18	16.29	212.4	29,000	0.730	2,908	21,159	0.137

**Top Girt Design Data (Tension)**

<b>tnxTower</b>  <b>URS Corporation</b> 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	<b>Job</b>	152' ROHN SSV Tower	<b>Page</b>	53 of 55
	<b>Project</b>	366 Old Long Ridge Road, Stamford, CT	<b>Date</b>	11:46:06 07/15/14
	<b>Client</b>	Verizon, Sprint and AT&T / S.A. Evaluation	<b>Designed by</b>	MCD

Section No.	Elevation ft	Size	L ft	L <sub>u</sub> ft	Kl/r	F <sub>a</sub> ksi	A in <sup>2</sup>	Actual P K	Allow. P <sub>a</sub> K	Ratio $\frac{P}{P_a}$
T1	152 - 140	L2x2x1/8	6.52	6.11	121.2	29.000	0.305	0.287	8.836	0.033
T2	140 - 135	L2x2x1/8	6.57	6.12	121.3	29.000	0.305	0.144	8.836	0.016

### Redundant Horizontal (1) Design Data (Tension)

Section No.	Elevation ft	Size	L ft	L <sub>u</sub> ft	Kl/r	F <sub>a</sub> ksi	A in <sup>2</sup>	Actual P K	Allow. P <sub>a</sub> K	Ratio $\frac{P}{P_a}$
T14	30 - 20	L2x2x1/4	4.56	4.28	84.3	21.600	0.938	3.167	20.261	0.156
T15	20 - 15	L2x2x1/4	4.82	4.50	88.6	21,600	0.938	3.419	20.261	0.169

### Redundant Diagonal (1) Design Data (Tension)

Section No.	Elevation ft	Size	L ft	L <sub>u</sub> ft	Kl/r	F <sub>a</sub> ksi	A in <sup>2</sup>	Actual P K	Allow. P <sub>a</sub> K	Ratio $\frac{P}{P_a}$
T14	30 - 20	L2x2x1/4	5.32	4.99	98.4	21,600	0.938	1.847	20.261	0.091
T15	20 - 15	L2x2x1/4	5.53	5.18	102.0	21,600	0.938	1.985	20.261	0.098

### Section Capacity Table

Section No.	Elevation ft	Component Type	Size	Critical Element	P K	SF*P <sub>allow</sub> K	% Capacity	Pass Fail
T1	152 - 140	Leg	ROHN 2 STD	3	-7.018	32,507	21.6	Pass
T2	140 - 135	Leg	ROHN 2.5 STD	27	-12.229	51,088	23.9	Pass
T3	135 - 130	Leg	ROHN 2.5 STD	39	-14.620	50.251	29.1	Pass
T4	130 - 125	Leg	ROHN 2.5 STD	48	-20.859	50.251	41.5	Pass
T5	125 - 120	Leg	ROHN 2.5 STD	57	-27.981	50.251	55.7	Pass
T6	120 - 100	Leg	Rohn 2.5 X-Str w/ (3) 1.5"x0.25" Bars	66	-53.902	97.073	55.5	Pass
T7	100 - 80	Leg	Rohn 2.5 X-Str w/ (3) 1.5"x0.25" Bars	87	-88.559	120.648	73.4	Pass
T8	80 - 73.3333	Leg	Rohn 3 X-Str w/ (3) 1.5"x0.5" Bars	117	-100.326	165.532	60.6	Pass
T9	73.3333 - 66.6667	Leg	Rohn 3 X-Str w/ (3) 1.5"x0.5" Bars	126	-111.296	192.436	61.9 (b) 57.8	Pass
T10	66.6667 - 60	Leg	Rohn 3 X-Str w/ (3) 1.5"x0.5" Bars	138	-122.542	192.465	63.7	Pass
T11	60 - 50	Leg	Rohn 4 X-Str w/ (3) 1.5"x0.5"	150	-135.919	186.381	72.9	Pass

<b>tnxTower</b>  <b>URS Corporation</b> 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	<b>Job</b>	152' ROHN SSV Tower	<b>Page</b>	54 of 55
	<b>Project</b>	366 Old Long Ridge Road, Stamford, CT	<b>Date</b>	11:46:06 07/15/14
	<b>Client</b>	Verizon, Sprint and AT&T / S.A. Evaluation	<b>Designed by</b>	MCD

Section No.	Elevation ft	Component Type	Size	Critical Element	P K	SF*P <sub>allow</sub> K	% Capacity	Pass Fail
			Bars				83.8 (b)	
T12	50 - 40	Leg	Rohn 4 X-Str w/ (3) 1.5"x0.5"	159	-151.941	233.802	65.0	Pass
			Bars				71.7	
T13	40 - 30	Leg	Rohn 4 X-Str w/ (3) 1.5"x0.5"	171	-167.671	233.875	71.7	Pass
			Bars				79.0 (b)	
T14	30 - 20	Leg	Rohn 4 X-Str w/ (3) 1.5"x0.5"	183	-182.598	252.914	72.2	Pass
			Bars				78.1	
T15	20 - 15	Leg	Rohn 5 STD w/ (3) 1.5"x0.5"	225	-197.172	252.353	78.1	Pass
			Bars				92.4 (b)	
T16	15 - 10	Leg	Rohn 5 STD w/ (3) 1.5"x0.5"	249	-198.809	239.004	83.2	Pass
			Bars				70.5	
T17	10 - 0	Leg	Rohn 5 STD w/ (6) 1.5"x0.5"	258	-213.234	302,348	70.5	Pass
			Bars				57.8	
T1	152 - 140	Diagonal	L1 1/2x1 1/2x1/8	7	-1.935	3.345	57.8	Pass
T2	140 - 135	Diagonal	L1 1/2x1 1/2x3/16	31	-2.788	3.779	73.8	Pass
T3	135 - 130	Diagonal	L1 1/2x1 1/2x3/16	40	-2.612	3.343	78.1	Pass
T4	130 - 125	Diagonal	L1 1/2x1 1/2x1/4	49	-3.479	3.931	88.5	Pass
T5	125 - 120	Diagonal	L1 3/4x1 3/4x3/16	58	-3.948	4.484	88.1	Pass
T6	120 - 100	Diagonal	L2x2x1/4	72	-4.607	5.616	82.0	Pass
							83.8 (b)	
T7	100 - 80	Diagonal	L2 1/2x2 1/2x1/4	93	-6.830	8.521	80.2	Pass
							95.2 (b)	
T8	80 - 73.3333	Diagonal	L2 1/2x2 1/2x1/4	123	-6.848	7.864	87.1	Pass
							93.7 (b)	
T9	73.3333 - 66.6667	Diagonal	L2 1/2x2 1/2x5/16	132	-7.190	8.780	81.9	Pass
							91.6 (b)	
T10	66.6667 - 60	Diagonal	L2 1/2x2 1/2x5/16	144	-7.178	8.077	88.9	Pass
							91.6 (b)	
T11	60 - 50	Diagonal	L3x3x5/16	156	-8.503	10.679	79.6	Pass
T12	50 - 40	Diagonal	L3x3x5/16	165	-8.569	9.738	88.0	Pass
T13	40 - 30	Diagonal	L3x3x3/8	177	-9.333	10.481	89.0	Pass
T14	30 - 20	Diagonal	L3x3x5/16	202	-9.591	20.597	46.6	Pass
							79.8 (b)	
T15	20 - 15	Diagonal	L3 1/2x3 1/2x1/4	241	-9.619	24.606	39.1	Pass
							97.7 (b)	
T16	15 - 10	Diagonal	L3 1/2x3 1/2x1/4	255	-9.671	10.232	94.5	Pass
T17	10 - 0	Diagonal	L3 1/2x3 1/2x5/16	264	-9.509	11.143	85.3	Pass
							92.3 (b)	
T14	30 - 20	Horizontal	L3x3x3/16	191	-3.167	6.516	48.6	Pass
T16	15 - 10	Horizontal	L2.875x2.875x0.25	240	-3.448	4.457	77.4	Pass
T7	100 - 80	Secondary Horizontal	L3x3x3/16	95	-1.536	5.891	26.1	Pass
T9	73.3333 - 66.6667	Secondary Horizontal	L3x3x3/16	135	-1.930	4.909	39.3	Pass
							47.3	
T10	66.6667 - 60	Secondary Horizontal	L3x3x3/16	146	-2.125	4.494	47.3	Pass
T12	50 - 40	Secondary Horizontal	L3x3x3/16	167	-2.635	3.658	72.0	Pass
T13	40 - 30	Secondary Horizontal	L3x3x3/16	179	-2.908	3.288	88.4	Pass
T1	152 - 140	Top Girt	L2x2x1/8	4	-0.284	2.830	10.0	Pass
T2	140 - 135	Top Girt	L2x2x1/8	30	-0.157	2.823	5.6	Pass
T14	30 - 20	Redund Horiz 1 Bracing	L2x2x1/4	200	-3.167	10.834	29.2	Pass
							34.9	
T15	20 - 15	Redund Horiz 1 Bracing	L2x2x1/4	238	-3.419	9.807	34.9	Pass
							23.2	
T14	30 - 20	Redund Diag 1 Bracing	L2x2x1/4	216	-1.847	7.946	23.2	Pass
							26.8	
T15	20 - 15	Redund Diag 1 Bracing	L2x2x1/4	239	-1.985	7.396	26.8	Pass
							Summary	
						Leg (T15)	92.4	Pass
						Diagonal (T15)	97.7	Pass
						Horizontal	77.4	Pass

<b>tnxTower</b>  <b>URS Corporation</b> 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	<b>Job</b> 152' ROHN SSV Tower	<b>Page</b> 55 of 55
	<b>Project</b> 366 Old Long Ridge Road, Stamford, CT	<b>Date</b> 11:46:06 07/15/14
	<b>Client</b> Verizon, Sprint and AT&T / S.A. Evaluation	<b>Designed by</b> MCD

Section No.	Elevation ft	Component Type	Size	Critical Element	P K	SF*P <sub>allow</sub> K	% Capacity	Pass Fail
						(T16)		
						Secondary Horizontal	88.4	Pass
						(T13)		
						Top Girt (T1)	10.0	Pass
						Redund Horz 1 Bracing (T15)	34.9	Pass
						Redund Diag 1 Bracing (T15)	26.8	Pass
						Bolt Checks	97.7	Pass
						<b>RATING =</b>	<b>97.7</b>	<b>Pass</b>

Program Version 6.1.3.1 - 3/21/2014 File:C:/Users/Michael\_Dalickas/Desktop/VZW-### and TWS-###\_Stamford\_CT/ERI/150'\_ROHN\_SSV\_Lattice\_Stamford\_CT\_w\_Mods.eri



# ANCHOR BOLT EVALUATION

(Sprint) 36928702.00000  
(Verizon) 36922268.00000  
(AT&T) 36922483.00000

152' SSV Lattice Tower  
Stamford, CT

7/15/2014

Job	<u>152' ROHN SSV LatticeTower, Stamford, CT</u>	Project No.	<u>VZW,AT&amp;T &amp; Sprint</u>	Sheet	<u>1</u>	of	<u>3</u>
Description	<u>Anchor Bolt Analysis</u>	Computed by	<u>MCD</u>	Date	<u>07/15/14</u>		
		Checked by	<u>                    </u>	Date	<u>                    </u>		

## ANCHOR BOLT ANALYSIS

### Input Data

#### Max Corner Reactions:

Uplift:	<u>Uplift := 189 kips</u>	<i>user input</i>
Shear:	<u>Shear := 26 kips</u>	<i>user input</i>
Compression:	<u>Compression := 220 kips</u>	<i>user input</i>

#### Anchor Bolt Data:

**Use ASTM A-193 GR B7/ASTM A-320 GR L7**

Number of Anchor Bolts = N	<u>N := 4</u>	<i>user input</i>
Bolt Ultimate Strength:	<u>F<sub>u</sub> := 125 ksi</u>	<i>user input</i>
Bolt Yield Strength:	<u>F<sub>y</sub> := 105 ksi</u>	<i>user input</i>
Bolt Modulus:	<u>E := 29000 ksi</u>	<i>user input</i>
Thickness of Anchor Bolts	<u>D := 1.0 in</u>	<i>user input</i>
Threads per Inch:	<u>n := 8.0</u>	<i>user input</i>
Coefficient of Friction:	<u>μ := 0.55</u>	<i>user input</i> (for baseplate with grout ASCE 10-97)

Job	152' ROHN SSV Lattice Tower, Stamford, CT	Project No.	VZW, AT&T & Sprint	Sheet	<u>2</u>	of	<u>3</u>
Description	Anchor Bolt Analysis	Computed by	MCD	Date	07/15/14		
		Checked by		Date			

## Anchor Bolt Area:

Gross Area of Bolt:

$$A_g := \frac{\pi \cdot D^2}{4} \qquad A_g = 0.785 \cdot \text{in}^2$$

Net Area of Bolt:

$$A_n := \frac{\pi}{4} \cdot \left( D - \frac{0.9743 \cdot \text{in}}{n} \right)^2 \qquad A_n = 0.606 \cdot \text{in}^2$$

## Check Tensile Forces:

Maximum Tensile Force (Gross Area):

$$\text{AllowableTension} := 1.333 \cdot (0.33 \cdot A_g \cdot F_u) \qquad \text{AllowableTension} = 43.2 \cdot \text{kips}$$

Note: 1.333 increase allowed per TIA/EIA

Maximum Tensile Force (Net Area):

$$F_{\text{net.area}} := 1.333 \cdot (0.60 \cdot A_n \cdot F_y) \qquad F_{\text{net.area}} = 50.9 \cdot \text{kips}$$

Note: 1.333 increase allowed per TIA/EIA

Applied Tension:

$$\text{MaxTension} := \frac{\text{Uplift}}{N} \qquad \text{MaxTension} = 47.3 \cdot \text{kips}$$

Check Stresses:

$$\frac{\text{MaxTension}}{F_{\text{net.area}}} = 0.93$$

$$\text{Condition1} := \text{if} \left( \frac{\text{MaxTension}}{F_{\text{net.area}}} \leq 1.00, \text{"OK"}, \text{"Overstressed"} \right)$$

$$\boxed{\text{Condition1} = \text{"OK"}}$$

Job	152' ROHN SSV Lattice Tower, Stamford, CT	Project No.	VZW, AT&T & Sprint	Sheet	3 of 3
Description	Anchor Bolt Analysis	Computed by	MCD	Date	07/15/14
		Checked by		Date	

## Check Anchor Bolt Area:

Based on the ASCE 10-97 Design of Latticed Steel Transmission Structures

Required Area:

$$A_{s1} := \frac{\text{Uplift}}{F_y} + \frac{\text{Shear}}{\mu \cdot 0.85 \cdot F_y} \quad A_{s1} = 2.3 \cdot \text{in}^2$$

$$A_{s2} := \left| \frac{\text{Shear} - (0.3 \cdot \text{Compression})}{\mu \cdot 0.85 \cdot F_y} \right| \quad A_{s2} = 0.8 \cdot \text{in}^2$$

Provided Area:

$$A_{\text{provided}} := A_n \cdot N \quad A_{\text{provided}} = 2.4 \cdot \text{in}^2$$

$$\text{Condition2} := \text{if} \left( \frac{A_{s1}}{A_{\text{provided}}} \leq 1.00, \text{"OK"}, \text{"Overstressed"} \right) \quad \frac{A_{s1}}{A_{\text{provided}}} = 0.96$$

Condition2 = "OK"

$$\text{Condition3} := \text{if} \left( \frac{A_{s2}}{A_{\text{provided}}} \leq 1.00, \text{"OK"}, \text{"Overstressed"} \right) \quad \frac{A_{s2}}{A_{\text{provided}}} = 0.34$$

Condition3 = "OK"

# FOUNDATION EVALUATION

(Sprint) 36928702.00000  
(Verizon) 36922268.00000  
(AT&T) 36922483.00000

152' SSV Lattice Tower  
Stamford, CT

7/15/2014

Job	152' ROHN SSV Lattice Tower - Stamford, CT	Project No.	VZW, AT&T & Sprint	Sheet	1 of 2
Description	Drilled Pier Caisson Evaluation	Computed by	MCD	Date	07/15/14
		Checked by		Date	

## FOUNDATION ANALYSIS

### Input Data

#### Maximum Pier Reactions:

Compression:  $C_t := 220 \cdot \text{kips}$  *user input*  
 Uplift:  $U_t := 189 \cdot \text{kips}$  *user input*

#### Material Properties:

Unit Weight of Concrete:  $\gamma_c := 150 \text{pcf}$  *user input*  
 Unit Weight of Water:  $\gamma_w := 62.4 \text{pcf}$  *user input*  
 Unit Weight of Soil:  $\gamma_s := 120 \text{pcf}$  *user input*

#### Foundation Dimensions:

Drilled Caisson Length:  $C_{\text{Length}} := 21.0 \cdot \text{ft}$  *user input*  
 Diameter of Pier:  $d_p := 4.5 \text{ft}$  *user input*  
 Extension of Pier Above Grade:  $L_{\text{pag}} := 0.5 \text{ft}$  *user input*  
 Conc Pad Length:  $\text{PadLength} := 5.0 \text{ft}$  *user input*  
 Conc Pad Width:  $\text{PadWidth} := 6 \text{ft}$  *user input*  
 Conc Pad Depth:  $\text{PadDepth} := 5.0 \text{ft}$  *user input*

Allowable Soil Bearing Capacity (Allowable Bearing Pressure at Depth 21'):  $q_s := 10 \cdot \text{ksf}$  *user input*  
 Water Table Below Grade:  $Wd := 8 \cdot \text{ft}$  *user input*  
 Average Allowable Shear:  $fl := 410 \cdot \text{psf}$  *user input*  
 Depth Neglected for Skin Friction at Top:  $\text{Depthunbond} := 0.5 \text{ft}$  *user input*  
 Assumed Allowable Soil Bearing Capacity For Conc Pad:  $q_u := 5 \text{ksf}$  *user input*

Note: Above concrete pad dimensions based on foundation reinforcement design by Tectonic Engineering P.C; for AT&T Wireless, dated 04/23/02.

#### Loading:

$$\text{TotalDownLoad} := C_t + \pi \cdot \frac{d_p^2}{4} \cdot [L_{\text{pag}} \cdot \gamma_c + [\gamma_c \cdot (C_{\text{Length}} - L_{\text{pag}})]]$$

$$\text{TotalDownLoad} = 270.1 \cdot \text{kips}$$

$$\text{PadWeight} := \text{PadLength} \cdot \text{PadWidth} \cdot \text{PadDepth} \cdot \gamma_c \quad \text{PadWeight} = 22.5 \cdot \text{kips}$$

$$\text{PierWeight} := \pi \cdot \frac{d_p^2}{4} \cdot [(Wd + L_{\text{pag}}) \cdot \gamma_c + (C_{\text{Length}} - Wd - L_{\text{pag}}) \cdot (\gamma_c - \gamma_w)] \quad \text{PierWeight} = 37.7 \cdot \text{kips}$$

$$\text{SoilShear} := \pi \cdot d_p \cdot [fl \cdot (Wd - \text{Depthunbond}) + fl \cdot (C_{\text{Length}} - Wd - L_{\text{pag}})]$$

$$\text{SoilShear} = 115.9 \cdot \text{kips}$$

Job	152' ROHN SSV Lattice Tower - Stamford, CT	Project No.	VZW, AT&T & Sprint	Sheet	2	of	2
Description	Drilled Pier Caisson Evaluation	Computed by	MCD	Date	07/15/14		
		Checked by		Date			

## Compression Capacity:

$$\text{TotalDownLoadCapacity} := \text{SoilShear} + q_s \left( \pi \cdot \frac{d_p^2}{4} \right) + q_u (\text{PadLength} \cdot \text{PadWidth})$$

$$\text{TotalDownLoadCapacity} = 425.0 \text{ kips}$$

$$\text{CheckDownLoadCapacity} := \text{if}(\text{TotalDownLoad} < \text{TotalDownLoadCapacity}, \text{"Okay"}, \text{"No Good"})$$

$$\text{CheckDownLoadCapacity} = \text{"Okay"}$$

## Tension Capacity:

$$\text{TotalUpLiftCapacity} := \text{SoilShear} + \text{PierWeight} + \text{PadWeight}$$

$$\text{TotalUpLiftCapacity} = 176.1 \text{ kips}$$

$$\text{Required Safety Factor: } F_{s_{\text{reqd}}} := 2.0$$

$$\text{CheckUpLiftCapacity} := \text{if} \left[ \left( \frac{\text{TotalUpLiftCapacity}}{U_t} \right) \geq 2.0, \text{"Okay"}, \text{"No Good"} \right] \quad \text{CheckUpLiftCapacity} = \text{"No Good"}$$

$$\text{SafetyFactor}_{\text{provided}} := \frac{\text{TotalUpLiftCapacity}}{U_t} \quad \text{SafetyFactor}_{\text{provided}} = 0.93$$

$$\text{AdditionalUplift} := 2 \cdot U_t - \text{TotalUpLiftCapacity}$$

$$\text{AdditionalUplift} = 201.9 \text{ kip}$$

Include the use of (1) Rock Anchor (Williams Form Engineering Corp.) with 150ksi All-Threaded Anchor Bar (2 1/4" diameter) and Concrete Grouting at each caisson anchor. (See following support calculations)

## Check Cone Failure:

$$\text{ConeFailureCapacity} := \frac{[(C_{\text{Length}} - L_{\text{pag}}) \cdot \tan(30\text{deg}) \cdot 2 + d_p]^2 \cdot \pi \cdot C_{\text{Length}} - L_{\text{pag}}}{4 \cdot 3} \cdot \gamma_s$$

$$\text{ConeFailureCapacity} = 511.12 \text{ kips}$$

$$\text{CheckConeFailureCapacity} := \text{if}(U_t < \text{ConeFailureCapacity}, \text{"Okay"}, \text{"No Good"})$$

$$\text{CheckConeFailureCapacity} = \text{"Okay"}$$

$$\text{ConeSafetyFactor}_{\text{provided}} := \frac{\text{ConeFailureCapacity}}{U_t}$$

$$\text{ConeSafetyFactor}_{\text{provided}} = 2.70$$

Reference

- Consider factored uplift for applications not involving allowable stress design;

$$202 \text{ kIP} \times 1.4 = 283 \text{ kIP}$$

- Determine Anchor rod:
  - Page 18 (Williams Form Engineering Corp.)

Use  $\geq 1/4''$

(Yield)  $P_n = F_y \times A_g = 128 \text{ ksi} \times 4.08 \text{ in}^2 \times 0.9 = 470 \text{ kIP (OK)}$

(Rupture)  $P_n = F_u \times A_e = 150 \text{ ksi} \times (4.08 \text{ in}^2 - (0.2 \times 4.08 \text{ in}^2)) \times 0.75 = 367.2 \text{ kIP (OK)}$

Check  $1/4''$

(Yield)  $P_n = F_y \times A_g = 128 \times 2.60 \text{ in}^2 \times 0.9 = 299.52 \text{ kIP (OK)}$

(Rupture)  $P_n = F_u \times A_e = 150 \text{ ksi} \times (2.60 \text{ in}^2 - (0.2 \times 2.60 \text{ in}^2)) \times 0.75 = 234 \text{ kIP (NG)}$

- Determine Anchor Length:
  - Page 10 § 11 (Williams Form Engineering Corp.) "Free Stress Length"

$$U = 613 \text{ kIP} \rightarrow 613 \text{ kIP} \times 0.5 = 306.5 \text{ kIP} > 283 \text{ kIP (OK)}$$

$$F.S. = 0.5$$

$V \times Y$  (See attached spread sheet)

Note: "S" will be ignored for conservative design

$$297 \text{ kIP} > 283 \text{ kIP (OK)} \therefore \text{"Free-Stress Length"} = 39 \text{ ft below grade}$$

"Rock Anchor Length"

$$L_b = \frac{P}{\pi(D)(T_w)}$$

$T_w = 3000 \text{ psi}$  (assumed soil/rock conditions of Shist & Gneiss are similar to Dolomitic Limestone (Ps 11 - Williams))

$$L_b = \frac{283 \text{ kIP} \times 1000 \text{ lb/kIP}}{\pi(8.5 \text{ in})(75 \text{ psi})} = 12.5 \text{ ft (min) bond Length}$$

$$39 \text{ ft} + 12.5 \text{ ft} = 51.5 \text{ ft below grade (Min.)}$$



1/3 Pi	Area	Ht	U. WT	H2O Wt.	lb/kip	Kips
0.333333	3.141593	161.6581	8	120	0	1000 162.5164
0.333333	3.141593	89.7058	5.5	120	62.4	1000 29.7601
0.333333	3.141593	94.1803	7.5	130	62.4	1000 50.00307
0.333333	3.141593	28.5788	3	140	62.4	1000 6.967157
0.333333	3.141593	36.0844	5	160	62.4	1000 18.4403
0.333333	3.141593	28.8675	10	160	62.4	1000 29.50446 (rock embedment)
			39			297.1915

288.26 CAPACITY NEEDED

Reference


- Consider Anchor bolts attached to caisson:  
See Attached calculations Spreadsheet using Hilti 1 1/4" Diameter HAS-E Super Rod (Reference Pages 154-162; Section 4.2.1)

\* Use 12 bolts spaced 12" apart

Design Capacity  $\approx 77\%$


- Consider Anchor Plate thickness:  
Steel = 50 ksi

$$S = \frac{M}{S} \rightarrow S = \frac{M}{S} = \frac{b \cdot d^2}{3} \Rightarrow d_{min} = \sqrt{\frac{3 \times \frac{M}{S}}{f \cdot b}}$$




$$= \sqrt{\frac{3 \times \frac{(283 \text{ kIP}) (9 \frac{7}{16})}{4}}{50 \text{ ksi} \times 9 \frac{7}{16} \text{ in}}} = 2.06 \text{ in} \approx \underline{2 \frac{1}{16} \text{ (t)}}$$

- Consider min material for gusset Plate supports:



$$d_{min} = \sqrt{\frac{3 \times F \times d}{f \cdot b}} = \sqrt{\frac{3 \times (283 \text{ kIP}) (9 \frac{7}{16} / 2)}{50 \text{ ksi} \times 5/8}} = 8.006 \text{ in} \therefore$$



- Consider connection plate thickness

$F = 283 \text{ kIP}$   
 $e = 10 \text{ in}$   
 $M = 2830 \text{ kIP} \cdot \text{in}$

$$f_{steel} = \frac{M}{S}$$

$$f_{steel} = \frac{M}{\frac{b \cdot d^2}{3}} \rightarrow b = \frac{3 \times M}{d^2 \times f_{steel}} = \frac{(3)(2830 \text{ kIP} \cdot \text{in})}{(10 \text{ in})^2 \times 50 \text{ ksi}}$$

$$b = \frac{0.139 \text{ in}}{0.75} = 0.185 \text{ in} < 5/8 \text{ (OK)}$$

Vert Force 202 kip  
Eccentricity 10 in  
Moment 2020 in\*kip

Number of Rows 6  
Number of Columns 2  
Number of Bolts 12  
Bolt Spacing 12 in

Row Number	1	2	3	4	5	6
Number of Bolts	2	2	2	2	2	2
Dist from Center	30	18	6	-6	-18	-30
A * d^2	1800	648	72	72	648	1800

I 5040 in^2  
S 168 in

Shear per Bolt	16.83333	kip
Tension per Bolt	12.0	kip

Use Hilti HVA Capsule Achesive Anchoring System  
Hilti HAS Rod

Diameter 1.25 in  
Embedment 18 in  
Spacing 12 in

**For 3000 ksi concrete (4.2.1, p. 154)**

Allow Tension 33728 lb  
Allow Shear 85627.5 lb

**Reduction Factors (4.2.1, p. 162)**

Spacing for Tension 0.75  
Spacing for Shear 0.75  
Edge Distance Shear 1

**Concrete Capacity**

Tension 25.3 kip  
Shear 64.2 kip

**For 1.25" Diameter HAS-E Super Rod**

Allow Tension 50.62 kip  
Allow Shear 26.08 kip

**Governing Capacities**

Tension 25.3 kip  
Shear 26.1 kip

**Applied Forces**

Tension 12.0 kip  
Shear 16.8 kip


**Percent Capacity**

Tension 48%  
Shear 65%

**Interaction**

per Hilti 4.1.8.3 77.2%

# Sprint®



PROJECT: 2.5 EQUIPMENT DEPLOYMENT

SITE NAME: STAMFORD FIRE DEPARTMENT

SITE CASCADE: CT03XC328-A

SITE ADDRESS: 366 OLD LONG RIDGE ROAD  
STAMFORD, CT 06903

SITE TYPE: 152'-0' SELF SUPPORT  
TOWER



6580 SPRINT PARKWAY  
OVERLAND PARK, KANSAS 66251



1120 Dallas Street, Sauk City, WI 53583  
 Phone: 608-643-4100 Fax: 608-643-7999  
 www.Ramaker.com



48 SPRUCE STREET  
OAKLAND, NJ 07346

Certification & Seal:  
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 8/29/2014

MARK	DATE	DESCRIPTION
ISSUE	FINAL	DATE ISSUED 08/29/2014

PROJECT TITLE:  
**STAMFORD FIRE DEPT.  
 CT03XC328-A**

PROJECT INFORMATION:  
 366 OLD LONG RIDGE ROAD  
 STAMFORD, CT 06903  
 FAIRFIELD COUNTY

SHEET TITLE:  
**TITLE SHEET**

SCALE: NONE

PROJECT NUMBER	29012
SHEET NUMBER	T-1

**SITE INFORMATION**

**PROPERTY OWNER:**  
 LONG RIDGE FIRE CO. INC.  
 366 OLD LONG RIDGE ROAD  
 STAMFORD, CT 06903-1133

**SITE ADDRESS:**  
 366 OLD LONG RIDGE ROAD  
 STAMFORD, CT 06903-1133  
 FAIRFIELD COUNTY

**GEOGRAPHIC COORDINATES:**  
 LATITUDE: 41.15311° (41° 09' 11.1954" N)  
 LONGITUDE: -73.5929° (73° 35' 34.44" W)

**ZONING JURISDICTION:**

CITY OF STAMFORD  
**ZONING DISTRICT:**  
 RA-2 ONE FAMILY RESIDENCE

**POWER COMPANY:**  
 CONNECTICUT LIGHT & POWER  
 PH.: (800) 286-2000


**AAV PROVIDER:**  
 VERIZON  
 PH.: (203) 968-6116

**SPRINT CONSTRUCTION MANAGER:**  
 NAME: GARY WOOD  
 PHONE: (860) 940-9168  
 E-MAIL: gary.wood@sprint.com

**EQUIPMENT SUPPLIER:**  
 ALCATEL-LUCENT  
 600-700 MOUNTAIN AVENUE  
 MURRAY HILL, NJ 07974  
 PH.: (908) 508-8080

**PLANS PREPARED BY:**  
 RAMAKER & ASSOCIATES, INC.  
 CONTACT: KEITH BOHNSACK, PROJECT MANAGER  
 PH.: (608) 643-4100  
 EMAIL: kbohnsack@ramaker.com

**AREA MAP**



**LOCATION MAP**



**PROJECT DESCRIPTION**

- INSTALL NEW 2.5 EQUIPMENT IN EXISTING BTS CABINET  
 \*(1) RECTIFIER SHELF AND (3) RECTIFIERS  
 \*(1) BASE BAND UNIT
- INSTALL (2) NEW BATTERY STRINGS IN EXISTING BATTERY CABINET
- INSTALL (3) PANEL ANTENNAS
- INSTALL (3) RRH'S ON TOWER
- INSTALL (1) FIBER CABLE AND (3) SECTOR JUMPERS
- INSTALL (27) ANTENNA / RRH JUMPERS

**APPLICABLE CODES**

- \* ALL WORK SHALL BE PERFORMED AND MATERIALS INSTALLED IN ACCORDANCE WITH THE FOLLOWING CODES AS ADOPTED BY THE LOCAL GOVERNING AUTHORITIES. NOTHING IN THESE PLANS IS TO BE CONSTRUED TO PERMIT WORK NOT CONFORMING TO THESE CODES.
1. INTERNATIONAL BUILDING CODE
  2. ANSI/TIA-222 STRUCTURAL STANDARD FOR ANTENNA STRUCTURES
  3. NFPA 780 - LIGHTNING PROTECTION CODE
  4. NATIONAL ELECTRIC CODE



**SECTION 01 100 - SCOPE OF WORK**

**THE WORK:**  
 THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE CONSTRUCTION DRAWINGS AND ASSOCIATED OUTLINE SPECIFICATIONS AND THE SITE SPECIFIC WORK ORDER, DESCRIBE THE WORK TO BE PERFORMED BY THIS CONSTRUCTION CONTRACTOR (SUPPLIER).

**RELATED DOCUMENTS:**  
 A. THE REQUIREMENTS OF EACH SECTION OF THIS SPECIFICATION APPLY TO ALL SECTIONS, INDIVIDUALLY AND COLLECTIVELY.  
 B. RELATED DOCUMENTS: THE CONTRACTOR SHALL COMPLY WITH THE MOST CURRENT VERSION OF THE FOLLOWING SUPPLEMENTAL REQUIREMENTS FOR INSTALLATION AND TESTING.  
 1. EN-201 2-001 : (FIBER OPTIC, DC CABLE, AND DC CIRCUIT BREAKER TAGGING STANDARDS)  
 2. TS-0200 - (TRANSMISSION ANTENNA LINE ACCEPTANCE STANDARDS)  
 3. EL-0568: (FIBER TESTING POLICY)  
 4. NP-312-201 : (EXTERIOR GROUNDING SYSTEM TESTING)  
 5. NP-760-500: ETHERNET, MICROWAVE, TESTING AND ACCEPTANCE

**PRECEDENCE:**  
 SHOULD CONFLICTS OCCUR BETWEEN THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES AND THE CONSTRUCTION DRAWINGS, INFORMATION ON THE CONSTRUCTION DRAWINGS SHALL TAKE PRECEDENCE. NOTIFY SPRINT CONSTRUCTION MANAGER IF THIS OCCURS.

**NATIONALLY RECOGNIZED CODES AND STANDARDS:**  
 THE WORK SHALL COMPLY WITH APPLICABLE NATIONAL AND LOCAL CODES AND STANDARDS, LATEST EDITION, AND PORTIONS THEREOF, INCLUDED BUT NOT LIMITED TO THE FOLLOWING:  
 A. GR-63-CORE NEBS REQUIREMENTS: PHYSICAL PROTECTION  
 B. GR-78-CORE GENERIC REQUIREMENTS FOR THE PHYSICAL DESIGN AND MANUFACTURE OF TELECOMMUNICATIONS EQUIPMENT.  
 C. GR-1089 CORE, ELECTROMAGNETIC COMPATIBILITY AND ELECTRICAL SAFETY -GENERIC CRITERIA FOR NETWORK TELECOMMUNICATIONS EQUIPMENT.  
 D. NATIONAL FIRE PROTECTION ASSOCIATION CODES AND STANDARDS (NFPA) INCLUDING NFPA 70 (NATIONAL ELECTRICAL CODE - "NEC") AND NFPA 101 (LIFE SAFETY CODE).  
 E. AMERICAN SOCIETY FOR TESTING OF MATERIALS (ASTM)  
 F. INSTITUTE OF ELECTRONIC AND ELECTRICAL ENGINEERS (IEEE)  
 G. AMERICAN CONCRETE INSTITUTE (ACI)  
 H. AMERICAN WIRE PRODUCERS ASSOCIATION (AWPA)  
 I. CONCRETE REINFORCING STEEL INSTITUTE (CRSI)  
 J. AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)  
 K. PORTLAND CEMENT ASSOCIATION (PCA)  
 L. NATIONAL CONCRETE MASONRY ASSOCIATION (NCMA)  
 M. BRICK INDUSTRY ASSOCIATION (BIA)  
 N. AMERICAN WELDING SOCIETY (AWS)  
 O. NATIONAL ROOFING CONTRACTORS ASSOCIATION (NRCA)  
 P. SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)  
 Q. DOOR AND HARDWARE INSTITUTE (DHI)  
 R. OCCUPATIONAL SAFETY AND HEALTH ACT (OSHA)  
 S. APPLICABLE BUILDING CODES INCLUDING UNIFORM BUILDING CODE, SOUTHERN BUILDING CODE, BOCA, AND THE INTERNATIONAL BUILDING CODE.

**DEFINITIONS:**  
 A. WORK: THE SUM OF TASKS AND RESPONSIBILITIES IDENTIFIED IN THE CONTRACT DOCUMENTS.  
 B. COMPANY: "SPRINT"; SPRINT NEXTEL CORPORATION AND ITS OPERATING ENTITIES.  
 C. ENGINEER: SYNONYMOUS WITH ARCHITECT & ENGINEER AND "A&E". THE DESIGN PROFESSIONAL HAVING PROFESSIONAL RESPONSIBILITY FOR DESIGN OF THE PROJECT.  
 D. CONTRACTOR: CONSTRUCTION CONTRACTOR, SUPPLIER, CONSTRUCTION VENDOR, INDIVIDUAL OR ENTITY WHO AFTER EXECUTION OF A CONTRACT IS BOUND TO ACCOMPLISH THE WORK.  
 E. THIRD PARTY VENDOR OR AGENCY: A VENDOR OR AGENCY ENGAGED SEPARATELY BY THE COMPANY, A&E, OR CONTRACTOR TO PROVIDE MATERIALS OR TO ACCOMPLISH SPECIFIC TASKS RELATED TO BUT NOT INCLUDED IN THE WORK.  
 F. CONSTRUCTION MANAGER - ALL PROJECTS RELATED COMMUNICATION TO FLOW THROUGH SPRINT REPRESENTATIVE IN CHARGE OF PROJECT.

**SITE FAMILIARITY:**  
 CONTRACTOR SHALL BE RESPONSIBLE FOR FAMILIARIZING HIMSELF WITH ALL CONTRACT DOCUMENTS, FIELD CONDITIONS AND DIMENSIONS PRIOR TO PROCEEDING WITH CONSTRUCTION. ANY DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE SPRINT CONSTRUCTION MANAGER PRIOR TO THE COMMENCEMENT OF WORK. NO COMPENSATION WILL BE AWARDED BASED ON CLAIM OF LACK OF KNOWLEDGE OR FIELD CONDITIONS.

**POINT OF CONTACT:**  
 COMMUNICATION BETWEEN SPRINT AND THE CONTRACTOR SHALL FLOW THROUGH THE SINGLE SPRINT CONSTRUCTION MANAGER APPOINTED TO MANAGE THE PROJECT FOR SPRINT.

**ON-SITE SUPERVISION:**  
 THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK AND SHALL BE RESPONSIBLE FOR CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES IN ACCORDANCE WITH THE CONTRACT DOCUMENTS. THE CONTRACTOR SHALL EMPLOY A COMPETENT SUPERINTENDENT WHO SHALL BE IN ATTENDANCE AT THE SITE AT ALL TIMES DURING PERFORMANCE OF THE WORK.

**DRAWINGS REQUIRED AT JOBSITE:**  
 THE CONSTRUCTION CONTRACTOR SHALL MAINTAIN A FULL SET OF THE CONSTRUCTION DRAWINGS FOR WIRELESS SITES AND THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES AT THE JOBSITE FROM MOBILIZATION THROUGH CONSTRUCTION COMPLETION.  
 A. THE JOBSITE DRAWINGS SHALL BE CLEARLY MARKED DAILY IN RED PENCIL WITH ANY CHANGES IN CONSTRUCTION OVER WHAT IS DEPICTED IN THE DOCUMENTS. AT CONSTRUCTION COMPLETION, THIS JOBSITE MARKUP SET SHALL BE DELIVERED TO THE COMPANY OR COMPANY'S DESIGNATED REPRESENTATIVE TO BE FORWARDED TO THE COMPANY'S A&E VENDOR FOR PRODUCTION OF "AS-BUILT" DRAWINGS.  
 B. DIMENSIONS SHOWN ARE TO FINISH SURFACES UNLESS NOTED OTHERWISE. SPACING BETWEEN EQUIPMENT IS THE REQUIRED CLEARANCE. SHOULD THERE BE ANY QUESTIONS REGARDING THE CONTRACT DOCUMENTS, EXISTING CONDITIONS AND/OR DESIGN INTENT, THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING A CLARIFICATION FROM THE SPRINT CONSTRUCTION MANAGER PRIOR TO PROCEEDING WITH THE WORK.

**USE OF JOB SITE:**  
 THE CONTRACTOR SHALL CONFINE ALL CONSTRUCTION AND RELATED OPERATIONS INCLUDING STAGING AND STORAGE OF MATERIALS AND EQUIPMENT, PARKING, TEMPORARY FACILITIES, AND WASTE STORAGE TO THE LEASE PARCEL UNLESS OTHERWISE PERMITTED BY THE CONTRACT DOCUMENTS.

**UTILITY SERVICES:**  
 WHERE NECESSARY TO CUT EXISTING PIPES, ELECTRICAL WIRES, CONDUITS, CABLES, ETC., OF UTILITY SERVICES, OR OF FIRE PROTECTION OR COMMUNICATIONS SYSTEMS, THEY SHALL BE CUT AND CAPPED AT SUITABLE PLACES OR WHERE SHOWN. ALL SUCH ACTIONS SHALL BE COORDINATED WITH THE UTILITY COMPANY INVOLVED:

**PERMITS/FEES:**  
 WHEN REQUIRED THAT A PERMIT OR CONNECTION FEE BE PAID TO A PUBLIC UTILITY PROVIDER FOR NEW SERVICE TO THE CONSTRUCTION PROJECT, PAYMENT OF SUCH FEE SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.

**CONTRACTOR:**  
 CONTRACTOR SHALL TAKE ALL MEASURES AND PROVIDE ALL MATERIAL NECESSARY FOR PROTECTING EXISTING EQUIPMENT AND PROPERTY.

**USE OF ELECTRONIC PROJECT MANAGEMENT SYSTEMS:**  
 CONTRACTOR WILL UTILIZE ITS BEST EFFORTS TO WORK WITH SPRINT ELECTRONIC PROJECT MANAGEMENT SYSTEMS. CONTRACTOR UNDERSTANDS THAT SUFFICIENT INTERNET ACCESS, EQUIVALENT TO "BROADBAND" OR BETTER, IS REQUIRED TO TIMELY AND EFFECTIVELY UTILIZE SPRINT DATA AND DOCUMENT MANAGEMENT SYSTEMS AND AGREES TO MAINTAIN APPROPRIATE CONNECTIONS FOR CONTRACTOR'S STAFF AND OFFICES THAT ARE COMPATIBLE WITH SPRINT DATA AND DOCUMENT MANAGEMENT SYSTEMS

**TEMPORARY UTILITIES AND FACILITIES:**  
 THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL TEMPORARY UTILITIES AND FACILITIES NECESSARY EXCEPT AS OTHERWISE INDICATED IN THE CONSTRUCTION DOCUMENTS. TEMPORARY UTILITIES AND FACILITIES INCLUDE POTABLE WATER, HEAT, HVAC, ELECTRICITY, SANITARY FACILITIES, WASTE DISPOSAL FACILITIES, AND TELEPHONE/COMMUNICATION SERVICES. PROVIDE TEMPORARY UTILITIES AND FACILITIES IN ACCORDANCE WITH OSHA AND THE AUTHORITY HAVING JURISDICTION. CONTRACTOR MAY UTILIZE THE COMPANY ELECTRICAL SERVICE IN THE COMPLETION OF THE WORK WHEN IT BECOMES AVAILABLE. USE OF THE LESSOR'S OR SITE OWNER'S UTILITIES OR FACILITIES IS EXPRESSLY FORBIDDEN EXCEPT AS OTHERWISE ALLOWED IN THE CONTRACT DOCUMENTS.

**ACCESS TO WORK:**  
 THE CONTRACTOR SHALL PROVIDE ACCESS TO THE JOB SITE FOR AUTHORIZED COMPANY PERSONNEL AND AUTHORIZED REPRESENTATIVES OF THE ARCHITECT/ENGINEER DURING ALL PHASES OF THE WORK.

**DIMENSIONS:**  
 VERIFY DIMENSIONS INDICATED ON DRAWINGS WITH FIELD DIMENSIONS BEFORE FABRICATION OR ORDERING OF MATERIALS. DO NOT SCALE DRAWINGS.

**EXISTING CONDITIONS:**  
 NOTIFY THE SPRINT CONSTRUCTION MANAGER OF EXISTING CONDITIONS DIFFERING FROM THOSE INDICATED ON THE DRAWINGS. DO NOT REMOVE OR ALTER STRUCTURAL COMPONENTS WITHOUT PRIOR WRITTEN APPROVAL FROM THE ARCHITECT AND ENGINEER.

**SECTION 01 200 - COMPANY FURNISHED MATERIAL AND EQUIPMENT**

**FURNISHED MATERIALS:**  
 COMPANY FURNISHED MATERIALS AND EQUIPMENT TO BE INSTALLED BY THE CONTRACTOR (OFC) IS IDENTIFIED ON THE RF DATA SHEET IN THE CONSTRUCTION DOCUMENTS.

**RECEIPT OF MATERIAL AND EQUIPMENT:**  
 A. THE CONTRACTOR IS RESPONSIBLE FOR SPRINT PROVIDED MATERIAL AND EQUIPMENT AND UPON RECEIPT SHALL:  
 1. ACCEPT DELIVERIES AS SHIPPED AND TAKE RECEIPT.  
 2. VERIFY COMPLETENESS AND CONDITION OF ALL DELIVERIES.  
 3. TAKE RESPONSIBILITY FOR EQUIPMENT AND PROVIDE INSURANCE PROTECTION AS REQUIRED IN AGREEMENT.  
 B. RECORD ANY DEFECTS OR DAMAGES AND WITHIN TWENTY-FOUR HOURS AFTER RECEIPT, REPORT TO SPRINT OR ITS DESIGNATED PROJECT REPRESENTATIVE OF SUCH.  
 C. PROVIDE SECURE AND NECESSARY WEATHER PROTECTED WAREHOUSING.  
 D. COORDINATE SAFE AND SECURE TRANSPORTATION OF MATERIAL AND EQUIPMENT, DELIVERING AND OFF-LOADING FROM CONTRACTOR'S WAREHOUSE TO SITE.

**DELIVERABLES:**  
 A. COMPLETE SHIPPING AND RECEIPT DOCUMENTATION IN ACCORDANCE WITH COMPANY PRACTICE.  
 B. IF APPLICABLE, COMPLETE LOST/STOLEN/DAMAGED DOCUMENTATION REPORT AS NECESSARY IN ACCORDANCE WITH COMPANY PRACTICE, AND AS DIRECTED BY COMPANY.

**SECTION 01 300 - CELL SITE CONSTRUCTION**

**NOTICE TO PROCEED:**  
 A. NO WORK SHALL COMMENCE PRIOR TO COMPANY'S ISSUANCE OF THE WORK ORDER.  
 B. UPON RECEIVING NOTICE TO PROCEED, CONTRACTOR SHALL FULLY PERFORM ALL WORK NECESSARY TO PROVIDE SPRINT WITH AN OPERATIONAL WIRELESS FACILITY.

**GENERAL REQUIREMENTS FOR CONSTRUCTION:**  
 A. CONTRACTOR SHALL KEEP THE SITE FREE FROM ACCUMULATING WASTE MATERIAL, DEBRIS, AND TRASH. AT THE COMPLETION OF THE WORK, CONTRACTOR SHALL REMOVE FROM THE SITE ALL REMAINING RUBBISH, IMPLEMENTS, TEMPORARY FACILITIES, AND SURPLUS MATERIALS.  
 B. EQUIPMENT ROOMS SHALL AT ALL TIMES BE MAINTAINED "BROOM CLEAN" AND CLEAR OF DEBRIS.  
 C. CONTRACTOR SHALL TAKE ALL REASONABLE PRECAUTIONS TO DISCOVER AND LOCATE ANY HAZARDOUS CONDITION.  
 1. IN THE EVENT CONTRACTOR ENCOUNTERS ANY HAZARDOUS CONDITION WHICH HAS NOT BEEN ABATED OR OTHERWISE MITIGATED, CONTRACTOR AND ALL OTHER PERSONS SHALL IMMEDIATELY STOP WORK IN THE AFFECTED AREA AND NOTIFY COMPANY IN WRITING. THE WORK IN THE AFFECTED AREA SHALL NOT BE RESUMED EXCEPT BY WRITTEN NOTIFICATION BY COMPANY.  
 2. CONTRACTOR AGREES TO USE CARE WHILE ON THE SITE AND SHALL NOT TAKE ANY ACTION THAT WILL OR MAY RESULT IN OR CAUSE THE HAZARDOUS CONDITION TO BE FURTHER RELEASED IN THE ENVIRONMENT, OR TO FURTHER EXPOSE INDIVIDUALS TO THE HAZARD.  
 D. CONTRACTOR'S ACTIVITIES SHALL BE RESTRICTED TO THE PROJECT LIMITS. SHOULD AREAS OUTSIDE THE PROJECT LIMITS BE AFFECTED BY CONTRACTOR'S ACTIVITIES, CONTRACTOR SHALL IMMEDIATELY RETURN THEM TO ORIGINAL CONDITION

**FUNCTIONAL REQUIREMENTS:**  
 A. THE ACTIVITIES DESCRIBED IN THIS PARAGRAPH REPRESENT MINIMUM ACTIONS AND PROCESSES REQUIRED TO SUCCESSFULLY COMPLETE THE WORK. CONTRACTOR SHALL TAKE ALL ACTIONS AS NECESSARY TO SUCCESSFULLY COMPLETE THE CONSTRUCTION OF A FULLY FUNCTIONING WIRELESS FACILITY AT THE SITE IN ACCORDANCE WITH COMPANY PROCESSES.  
 B. SUBMIT SPECIFIC DOCUMENTATION AS INDICATED HEREIN, AND OBTAIN REQUIRED APPROVALS WHILE THE WORK IS BEING PERFORMED.  
 C. MANAGE AND CONDUCT ALL FIELD CONSTRUCTION SERVICE RELATED ACTIVITIES  
 D. PROVIDE CONSTRUCTION ACTIVITIES TO THE EXTENT REQUIRED BY THE CONTRACT DOCUMENTS, INCLUDING BUT NOT LIMITED TO THE FOLLOWING:  
 1. PERFORM ANY REQUIRED SITE ENVIRONMENTAL MITIGATION.  
 2. PREPARE GROUND SITES; PROVIDE DE-GRUBBING; AND ROUGH AND FINAL GRADING, AND COMPOUND SURFACE TREATMENTS.  
 3. MANAGE AND CONDUCT ALL ACTIVITIES FOR INSTALLATION OF UTILITIES INCLUDING ELECTRICAL AND BACKHAUL (FIBER, COPPER, OR MICROWAVE).  
 4. INSTALL UNDERGROUND FACILITIES INCLUDING UNDERGROUND POWER AND COMMUNICATIONS CONDUITS, AND UNDERGROUND GROUNDING SYSTEM.  
 5. INSTALL ABOVE GROUND GROUNDING SYSTEMS, CONDUIT AND BOXES.  
 6. PROVIDE NEW HVAC INSTALLATIONS AND MODIFICATIONS.  
 7. INSTALL "H-FRAMES", CABINETS AND PADS AND PLATFORMS AS INDICATED.  
 8. INSTALL ROADS, ACCESS WAYS, CURBS AND DRAINS AS INDICATED.  
 9. ACCOMPLISH REQUIRED MODIFICATION OF EXISTING FACILITIES.

10. PROVIDE ANTENNA SUPPORT STRUCTURE FOUNDATIONS.
11. PROVIDE SLABS AND EQUIPMENT PLATFORMS.
12. INSTALL COMPOUND FENCING, SIGHT SHIELDING, LANDSCAPING AND ACCESS BARRIERS.
13. PERFORM INSPECTION AND MATERIAL TESTING AS REQUIRED HEREINAFTER.
14. CONDUCT SITE RESISTANCE TO EARTH TESTING AS REQUIRED HEREINAFTER
15. INSTALL FIXED GENERATOR SETS AND OTHER STANDBY POWER SOLUTIONS.
16. INSTALL TOWERS, ANTENNA SUPPORT STRUCTURES AND PLATFORMS ON EXISTING TOWERS AS REQUIRED.
17. INSTALL CELL SITE RADIOS, MICROWAVE, GPS, COAXIAL MAINLINE, ANTENNAS, CROSS BAND COUPLERS, TOWER TOP AMPLIFIERS, LOW NOISE AMPLIFIERS AND RELATED EQUIPMENT.
18. CONDUCT ALL REQUIRED TESTS AND INSPECTIONS
19. PERFORM, DOCUMENT, AND CLOSE OUT ALL JURISDICTIONAL PERMITTING REQUIREMENTS AND ANY CONSTRUCTION CONTROL DOCUMENTS THAT MAY BE REQUIRED BY GOVERNMENT AGENCIES AND LANDLORDS.
20. PERFORM ALL ADDITIONAL WORK AS IDENTIFIED IN SCOPE OF SERVICES ATTACHED TO THE SUPPLIER AGREEMENT FOR THIS PROJECT. THIS WORK MAY INCLUDE COMMISSIONING, INTEGRATION, SPECIAL WAREHOUSING, REVERSE LOGISTICS ACTIVITIES, ETC. PERFORM COMMISSIONING AND INTEGRATION ACTIVITIES PER APPLICABLE MOPS.

**DELIVERABLES:**  
 A. THE CONTRACTOR SHALL PROVIDE ALL REQUIRED TEST REPORTS AND DOCUMENTATION INCLUDED BUT NOT LIMITED TO THE FOLLOWING:  
 1. PRODUCT SPECIFICATIONS FOR MATERIALS OR SPECIAL CONSTRUCTION IF REQUESTED BY SPRINT  
 2. ACTUALIZE ALL CONSTRUCTION RELATED MILESTONES IN SITERRA AND COMPLETE ALL ON-LINE FORMS AND COMPLETE DOCUMENT UP-LOADS. UPLOAD ALL REQUIRED CLOSEOUT DOCUMENTS AND FINAL SITE PHOTOS  
 3. SCANABLE BARCODE PHOTOGRAPHS OF TOWER TOP AND INACCESSIBLE SERIALIZED EQUIPMENT LEFT ON SITE INSIDE BASE OF MAIN RF CABINET IN A PROTECTIVE POUCH.  
 4. ALL REQUIRED TEST REPORTS.  
 5. REQUIRED CLOSEOUT DOCUMENTATION INCLUDING BUT NOT LIMITED TO:  
 a. ALL JURISDICTIONAL PERMITTING AND OCCUPANCY INFORMATION  
 b. PDF SCAN OF REDLINES PRODUCED IN THE FIELD  
 c. ELECTRONIC AS-BUILT DRAWINGS IN AUTOCAD AND PDF FORMATS  
 d. LIEN WAIVERS  
 e. FINAL PAYMENT APPLICATION  
 f. REQUIRED FINAL CONSTRUCTION PHOTOS  
 g. CONSTRUCTION AND COMMISSIONING CHECKLIST COMPLETE WITH NO DEFICIENT ITEMS  
 h. LISTS OF SUBCONTRACTORS  
 B. PROVIDE ADDITIONAL DOCUMENTATION INCLUDING, BUT NOT LIMITED TO, THE FOLLOWING. DOCUMENTATION SHALL BE FORWARDED IN ORIGINAL FORMAT AND/OR UPLOADED INTO SMS.  
 1. ALL CORRESPONDENCE AND PRELIMINARY CONSTRUCTION REPORTS.  
 2. PROJECT PROGRESS REPORTS.  
 3. PRE-CONSTRUCTION MEETING NOTES.

**SECTION 01 400 - TESTS, INSPECTIONS, SUBMITTALS, AND PROJECT CLOSEOUT**

**TESTS AND INSPECTIONS:**  
 A. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CONSTRUCTION TESTS, INSPECTIONS AND PROJECT DOCUMENTATION.  
 B. CONTRACTOR SHALL ACCOMPLISH TESTING INCLUDING BUT NOT LIMITED TO THE FOLLOWING:  
 1. COAX SWEEPS AND FIBER TESTS PER TS-0200 (CURRENT VERSION) ANTENNA LINE ACCEPTANCE STANDARDS  
 2. POST CONSTRUCTION HEIGHT VERIFICATION, AZIMUTH AND DOWNTILT USING ELECTRONIC COMMERCIAL MADE-FOR-THE-PURPOSE ANTENNA ALIGNMENT TOOL.  
 3. CONCRETE BREAK TESTS  
 4. SITE RESISTANCE TO EARTH TEST  
 5. STRUCTURAL BACKFILL COMPACTION TESTS  
 6. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN SITE INSPECTION ACTIVITIES AND/OR AS A RESULT OF TESTING.  
 7. ADDITIONAL TESTING AS REQUIRED ELSEWHERE IN THIS SPECIFICATION.

**SUBMITTALS:**  
 A. THE WORK IN ALL ASPECTS SHALL COMPLY WITH THE CONSTRUCTION DRAWINGS AND THESE SPECIFICATIONS.  
 B. UPLOAD THE FOLLOWING TO SITERRA AS APPLICABLE INCLUDING BUT NOT LIMITED TO THE FOLLOWING:  
 1. CONCRETE MIX-DESIGNS FOR TOWER FOUNDATIONS, ANCHORS PIERS, AND CONCRETE PAVING.  
 2. CONCRETE BREAK TESTS AS SPECIFIED HEREIN.  
 3. CHEMICAL GROUNDING SYSTEM .  
 4. REINFORCEMENT CERTIFICATIONS  
 5. STRUCTURAL BACKFILL TEST RESULTS  
 6. SWEEP AND FIBER TESTS  
 7. ANTENNA AZIMUTH AND DOWN-TILT VERIFICATION  
 8. POST CONSTRUCTION HEIGHT VERIFICATION  
 9. ADDITIONAL SUBMITTALS MAY BE REQUIRED FOR SPECIAL CONSTRUCTION OR MINOR MATERIALS  
 C. ALTERNATES: AT THE COMPANY'S REQUEST, ANY ALTERNATIVES TO THE MATERIALS OR METHODS SPECIFIED SHALL BE SUBMITTED TO SPRINT'S CONSTRUCTION MANAGER FOR APPROVAL PRIOR TO BEING SHIPPED TO SITE. SPRINT WILL REVIEW AND APPROVE ONLY THOSE REQUESTS MADE IN WRITING. NO VERBAL APPROVALS WILL BE CONSIDERED. SUBMITTAL FOR APPROVAL SHALL INCLUDE A STATEMENT OF COST REDUCTION PROPOSED FOR USE OF ALTERNATE PRODUCT.

**TESTING BY THIRD PARTY AGENCY:**  
 A. EMPLOY AN AGENCY OF ENGINEERS AND SCIENTISTS WHO IS REGULARLY ENGAGED IN FIELD AND LABORATORY TESTING AND ANALYSIS. AGENCY SHALL HAVE BEEN IN BUSINESS A MINIMUM OF FIVE YEARS, AND BE LICENSED AS PROFESSIONAL ENGINEERS IN THE STATE WHERE THE PROJECT IS LOCATED. AGENCY IS SUBJECT TO APPROVAL BY COMPANY.  
 1. AGENCY MUST HAVE A THOROUGH UNDERSTANDING OF LOCAL AVAILABLE MATERIALS, INCLUDING THE SOIL, ROCK, AND GROUNDWATER CONDITIONS.  
 2. AGENCY IS TO BE FAMILIAR WITH THE APPLICABLE REQUIREMENTS FOR THE TESTS TO BE DONE, EQUIPMENT TO BE USED, AND ASSOCIATED HEALTH AND SAFETY ISSUES.  
 3. EXPERIENCE IN SOILS, CONCRETE, MASONRY, AGGREGATE, AND ASPHALT TESTING USING ASTM, AASHTO, AND OTHER METHODS IS NEEDED.  
 B. REQUIRED THIRD PARTY TESTS:  
 1. SITE RESISTANCE TO EARTH TEST PER NP-312-201  
 2. CONCRETE CYLINDER BREAK TESTS FOR TOWER PIER AND ANCHORS PER NATIONALLY RECOGNIZED STANDARDS  
 3. STRUCTURAL SOILS COMPACTION TESTS PER NATIONALLY RECOGNIZED STANDARDS  
 4. REBAR PLACEMENT VERIFICATION WITH REPORT  
 5. TESTING TENSION STUDY FOR ROCK ANCHORS  
 6. ALL THIRD PARTY TESTS AS REQUIRED BY LOCAL JURISDICTION  
 C. REQUIRED TESTS BY CONTRACTOR  
 1. COAX SWEEP TESTS PER SPRINT STANDARD TS-0200  
 2. FIBER TESTS PER SPRINT STANDARD EL-0568  
 3. MICROWAVE LINK TESTS PER NP-760-500  
 4. ANTENNA AZIMUTHS AND DOWN TILT USING ELECTRONIC ALIGNMENT TOOL PER ANTENNA INSTALLATION SPECIFICATION HEREIN.



**6580 SPRINT PARKWAY  
 OVERLAND PARK, KANSAS 66251**



**1120 Dallas Street, Sauk City, WI 53585  
 Phone: 608-643-4100 Fax: 608-643-7999  
 www.Ramaker.com**



**48 SPRUCE STREET  
 OAKLAND, NJ 07346**

**Certification & Seal:**  
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



*James R. Skowronski* 8/29/2014  
 Signature: \_\_\_\_\_ Date: \_\_\_\_\_


MARK	DATE	DESCRIPTION
ISSUE PHASE	FINAL	DATE ISSUED 08/29/2014
PROJECT TITLE:		
<b>STAMFORD FIRE DEPT. CTO3XC328-A</b>		

**PROJECT INFORMATION:**  
 366 OLD LONG RIDGE ROAD  
 STAMFORD, CT 06903  
 FAIRFIELD COUNTY

**SHEET TITLE:**  
 SPRINT SPECIFICATIONS

**SCALE:** NONE

PROJECT NUMBER	29012
SHEET NUMBER	SP-1

5. POST CONSTRUCTION HEIGHT VERIFICATION AS REQUIRED HEREWITH IN THE TOWER INSTALLATION SPECIFICATIONS.
6. ASPHALT ROADWAY COMPACTED THICKNESS, SURFACE SMOOTHNESS, AND COMPACTED DENSITY TESTING AS SPECIFIED HEREWITH IN THE ASPHALT PAVING SPECIFICATIONS.
7. FIELD QUALITY CONTROL TESTING AS SPECIFIED HEREWITH IN THE CONCRETE PAVING SPECIFICATIONS.
8. TESTING REQUIRED HEREWITH UNDER SPECIFICATIONS FOR AGGREGATE BASE FOR ROADWAYS
9. ALL OTHER TESTS REQUIRED BY LOCAL JURISDICTION
- D. INSPECTIONS BY COMPANY: THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN INSPECTION ACTIVITIES, FINAL ACCEPTANCE / PUNCH WALK REVIEW, AND/OR AS A RESULT OF TESTING
- E. SPRINT RESERVES THE RIGHT TO INSPECT THE CONSTRUCTION SITE AT ANY TIME VIA SITE WALKS AND/OR PHOTO REVIEWS. CONTRACTOR SHALL GIVE SPRINT 24 HOURS NOTICE PRIOR TO THE COMMENCEMENT OF THE FOLLOWING CONSTRUCTION ACTIVITIES AND PHOTOGRAPHS OF THE IN-PROGRESS WORK.
  1. GROUNDING SYSTEM AND BURIED UTILITIES INSTALLATION PRIOR TO EARTH CONCEALMENT DOCUMENTED WITH DIGITAL PHOTOGRAPHS BY CONTRACTOR, APPROVED BY A&E OR SPRINT REPRESENTATIVE.
  2. FORMING FOR CONCRETE AND REBAR PLACEMENT PRIOR TO POUR DOCUMENTED WITH DIGITAL PHOTOGRAPHS BY CONTRACTOR, APPROVED BY A&E OR SPRINT REPRESENTATIVE.
  3. COMPACTION OF BACKFILL MATERIALS, AGGREGATE BASE FOR ROADS, PADS, AND ANCHORS, ASPHALT PAVING, AND SHAFT BACKFILL FOR CONCRETE AND WOOD POLES, BY INDEPENDENT THIRD PARTY AGENCY.
  4. PRE AND POST CONSTRUCTION ROOFTOP AND STRUCTURAL INSPECTIONS ON EXISTING FACILITIES. PRIOR TO CONSTRUCTION ACTIVITIES AND AFTER CONSTRUCTION IS COMPLETE, PROVIDE PHOTOGRAPHIC DOCUMENTATION OF ROOF, FLASHINGS, AND PARAPETS, BOTH BEFORE AND AFTER CONSTRUCTION IS COMPLETE.
  5. TOWER ERECTION SECTION STACKING AND PLATFORM ATTACHMENT DOCUMENTED BY DIGITAL PHOTOGRAPHS BY THIRD PARTY AGENCY.
  6. TOWER TOP AND INACCESSIBLE EQUIPMENT (RRUS, ANTENNAS, AND CABLING): PROVIDE PHOTOS OF THE BACKS OF ALL ANTENNAS, RRUS, COMBINERS, FILTERS, FIBER AND DC CABLING, CABLE COLOR CODING, EQUIPMENT GROUNDING AND CONNECTOR WATER PROOFING INCLUDING NAME PLATE AND SERIAL NUMBER FOR ALL SERIALIZED EQUIPMENT.

**PROJECT CLOSEOUT:**  
A. FINAL ACCEPTANCE PUNCH WALK AND INSPECTION: AS IDENTIFIED IN THE SCOPE OF SERVICES, SPRINT WILL CONDUCT A FINAL PUNCH WALK OR FINAL DESK TOP PHOTO REVIEW (SITE MODIFICATIONS). PUNCH WALKS MUST BE SCHEDULED IN ADVANCE AS REQUIRED. AT THE PUNCH WALK / REVIEW, SPRINT MAY IDENTIFY CRITICAL DEFICIENCIES WHICH MUST BE CORRECTED PRIOR TO PUTTING SITE ON AIR. MINOR DEFICIENCIES MUST BE CORRECTED WITHIN 30 DAYS EXCEPT AS OTHERWISE REQUIRED. VERIFICATIONS OF CORRECTIONS MAY BE MADE BY COMPANY DURING A REPEAT SITE WALK OR DESK TOP PHOTO REVIEW AT COMPANY'S SOLE DISCRETION.  
B. CLOSEOUT DOCUMENTATION: ALL CLOSEOUT DOCUMENTATION AND PHOTOGRAPHS SHALL BE UPLOADED PRIOR TO FINAL ACCEPTANCE. SPRINT WILL REVIEW CLOSEOUT DOCUMENTATION FOR PRESENCE AND CONTENT. CLOSEOUT DOCUMENTATION SHALL INCLUDE BUT IS NOT LIMITED TO THE FOLLOWING AS APPLICABLE:

1. COAX SWEEP TESTS:
2. FIBER TESTS:
3. JURISDICTION FINAL INSPECTION DOCUMENTATION
4. REINFORCEMENT CERTIFICATION (MILL CERTIFICATION)
5. CONCRETE MIX DESIGN AND PRODUCT DATA (TOWER FOUNDATION)
6. LIEN WAIVERS AND RELEASES.
7. POST -CONSTRUCTION HEIGHT VERIFICATION
8. JURISDICTION CERTIFICATE OF OCCUPANCY
9. ELECTRONIC ANTENNA AZIMUTH AND DOWN TILT VERIFICATION
10. STRUCTURAL BACKFILL TEST RESULTS (IF APPLICABLE)
  11. CELL SITE UTILITY SETUP
  12. AS-BUILT REDLINE CONSTRUCTION DRAWINGS (PDF SCAN OF FIELD MARKS)
  13. AS-BUILT CONSTRUCTION DRAWINGS IN DWG AND PDF FORMATS
  14. LIST OF SUB CONTRACTORS
  15. APPROVED PERMITTING DOCUMENTS
16. FINAL SITE PHOTOS UP-LOADED TO SITERRA. INCLUDE THE FOLLOWING AS APPLICABLE:
  - a. TOWER, ANTENNAS, RRUS, AND MAINLINE: INSPECTION AND PHOTOGRAPHS OF SECTION STACKING; INSPECTION AND PHOTOGRAPHS OF PLATFORM COMPONENT ATTACHMENT POINTS; PHOTOGRAPHS OF TOWER TOP GROUNDING; PHOTOS OF TOWER COAX/CABLE LINE COLOR CODING AT THE TOP AND AT GROUND LEVEL; INSPECTION AND PHOTOGRAPHS OF OPERATIONAL OF TOWER LIGHTING, AND PLACEMENT OF FAA REGISTRATION SIGN; PHOTOGRAPHS SHOWING ADDITIONAL GROUNDING POINTS FOR TOWERS GREATER THAN 200 FEET.; PHOTOS OF ANTENNA GROUND BAR, EQUIPMENT GROUND BAR, AND MASTER GROUND BAR; PHOTOS OF GPS ANTENNA(S); PHOTOS OF EACH SECTOR OF ANTENNAS; ONE PHOTOGRAPH LOOKING AT THE SECTOR AND ONE FROM BEHIND SHOWING THE PROJECTED COVERAGE AREA; PHOTOS OF COAX WEATHERPROOFING - TOP AND BOTTOM; PHOTOS OF COAX GROUNDING--TOP AND BOTTOM; PHOTOS OF ANTENNA AND MAST GROUNDING; PHOTOS OF COAX CABLE ENTRY INTO SHELTER; PHOTOS OF PLATFORM MECHANICAL CONNECTIONS TO TOWER/MONOPOLE.
  - b. ROOF TOPS: PRE-CONSTRUCTION AND POST-CONSTRUCTION VISUAL INSPECTION AND PHOTOGRAPHS OF THE ROOF AND INTERIOR TO DETERMINE AND DOCUMENT CONDITIONS; ROOF TOP CONSTRUCTION INSPECTIONS AS REQUIRED BY THE JURISDICTION; PHOTOGRAPHS OF CABLE TRAY AND/OR ICE BRIDGE; PHOTOGRAPHS OF DOGHOUSE/CABLE EXIT FROM ROOF;
  - c. SITE LAYOUT - PHOTOGRAPHS OF THE OVERALL COMPOUND, INCLUDING EQUIPMENT PLATFORM FROM ALL FOUR CORNERS.
  - d. FINISHED UTILITIES: CLOSE-UP PHOTOGRAPHS OF THE PPC BREAKER PANEL; CLOSE-UP PHOTOGRAPH OF THE INSIDE OF THE TELCO PANEL AND NIU; CLOSE-UP PHOTOGRAPH OF THE POWER METER AND DISCONNECT; PHOTOS OF POWER AND TELCO ENTRANCE TO COMPANY ENCLOSURE; PHOTOGRAPHS AT METER BOX AND/OR FACILITY DISTRIBUTION PANEL.

**PROJECT PHOTOGRAPHS:**  
A. PROVIDE PROJECT CLOSEOUT GENERAL ARRANGEMENT PHOTOS OF ALL NEW WORK. THE FOLLOWING LIST REPRESENTS MINIMUM REQUIREMENTS AND MINIMUM QUANTITY. ADDITIONAL PHOTOS MAY BE REQUIRED TO ADEQUATELY DOCUMENT THE WORK.

1. ASR AND RF MPE SIGNAGE (IF NOT IN PLACE, SUPPLIER NOTIFIES EMS FIELD REPRESENTATIVE)
2. BACK OF ANTENNAS AND RRUS (1 EACH SECTOR)
3. BACK OF ANTENNAS AND RRUS (1 EACH SECTOR) CLOSE UP SHOWING WEATHERPROOFING AND GROUNDING (AS REQUIRED). CLOSE-UP OF BACK SIDE OF EACH PERMANENT RRU SHOWING SERIAL NUMBER/BAR CODE.
4. VIEW (1 EACH SECTOR) ALONG THE AZIMUTH AND TILT OF THE ANTENNAS
5. TOP OF TOWER FROM GROUND, 1 EACH SECTOR
6. MAINLINE HYBRID CABLE ROUTE DOWN TOWER SHOWING FASTENERS AND SUPPORT
7. MAINLINE/HYBRID CABLE ROUTE ALONG ICE BRIDGE OR IN CABLE TRAY SHOWING FASTENERS AND SUPPORT
8. GROUND MOUNTED RRU RACKS (FRONT AND BACK)
9. FRONT, SIDE AND BACK ELEVATIONS OF ALL GROUND CABINETS
10. VIEW OF COMPOUND FROM A DISTANCE
11. VIEW OF EACH GROUND CABINET (POWER, RF, FIBER SPOOL, PPC POWER, PPC TELCO WITH DOOR OPEN)
12. BACKHAUL FIBER MEET-ME-POINT AND CONDUIT ROUTE (MICROWAVE INSTALLATION IF NOT FIBER)
13. AAV NETWORK INTERFACE DEVICE OR MICROWAVE RADIO INSTALLATION

**DEFICIENCY CORRECTIONS:**  
CONTRACTOR IS RESPONSIBLE FOR ALL CORRECTIONS TO DEFICIENCIES IDENTIFIED THROUGH TESTING, REVIEW OF SUBMITTALS, INSPECTIONS AND CLOSEOUT REVIEWS.

**SECTION 01 500 - PROJECT REPORTING**

**WEEKLY REPORTS:**  
A. CONTRACTOR SHALL REPORT TO SPRINT AT MINIMUM ON A WEEKLY BASIS VIA SITERRA BY UPDATING ALL APPLICABLE POST END KEEPING MILESTONES WITH ACTUAL AND FORECASTED COMPLETION DATES.  
B. ADDITIONAL REQUIREMENTS FOR REPORTING MAY BE IDENTIFIED ELSEWHERE OR REQUIRED BY THE SCOPE OF SERVICES OR SPRINTS LOCAL MARKET CONSTRUCTION MANAGER. THIS INFORMATION WILL PROVIDE A BASIS FOR PROGRESS MONITORING AND PAYMENT.

**PROJECT CONFERENCE CALLS:**  
SPRINT MAY HOLD PERIODIC PROJECT CONFERENCE CALLS. CONTRACTOR WILL BE REQUIRED TO COMMUNICATE SITE STATUS, MILESTONE COMPLETIONS AND UPCOMING MILESTONE PROJECTIONS, AND ANSWER ANY OTHER SITE STATUS QUESTIONS AS NECESSARY.

**FINAL PROJECT ACCEPTANCE:** PRIOR TO SPRINTS FINAL PROJECT ACCEPTANCE. ALL REQUIRED MILESTONE ACTUALS MUST BE UPDATED IN SITERRA AND ALL REQUIRED REPORTING TASKS MUST BE COMPLETE.

**SECTION 11 700 - ANTENNA ASSEMBLY, REMOTE RADIO UNITS AND CABLE INSTALLATION**

**SUMMARY:**  
THIS SECTION SPECIFIES INSTALLATION OF ANTENNAS, RRUS, AND CABLE EQUIPMENT, INSTALLATION, AND TESTING OF COAXIAL FIBER CABLE.

**ANTENNAS AND RRUS:**  
THE NUMBER AND TYPE OF ANTENNAS AND RRUS TO BE INSTALLED IS DETAILED ON THE CONSTRUCTION DRAWINGS.

**HYBRID CABLE:**  
HYBRID CABLE WILL BE DC/FIBER AND FURNISHED FOR INSTALLATION AT EACH SITE. CABLE SHALL BE INSTALLED PER THE CONSTRUCTION DRAWINGS AND THE APPLICABLE MANUFACTURER'S REQUIREMENTS.

**JUMPERS AND CONNECTORS:**  
FURNISH AND INSTALL 1/2" COAX JUMPER CABLES BETWEEN THE RRUS AND ANTENNAS. JUMPERS SHALL BE TYPE LDF 4, FLC 12-50, CR 540, OR FXL 540. SUPER-FLEX CABLES ARE NOT ACCEPTABLE. JUMPERS BETWEEN THE RRUS AND ANTENNAS OR TOWER TOP AMPLIFIERS SHALL CONSIST OF 1/2 INCH FOAM DIELECTRIC, OUTDOOR RATED COAXIAL CABLE, MIN. LENGTH FOR JUMPER SHALL BE 10'-0".

**REMOTE ELECTRICAL TILT (RET) CABLES:**

**MISCELLANEOUS:**  
INSTALL SPLITTERS, COMBINERS, FILTERS PER RF DATA SHEET, FURNISHED BY SPRINT.

**ANTENNA INSTALLATION:**  
THE CONTRACTOR SHALL ASSEMBLE ALL ANTENNAS ONSITE IN ACCORDANCE WITH THE INSTRUCTIONS SUPPLIED BY THE MANUFACTURER. ANTENNA HEIGHT, AZIMUTH, AND FEED ORIENTATION INFORMATION SHALL BE A DESIGNATED ON THE CONSTRUCTION DRAWINGS.

A. THE CONTRACTOR SHALL POSITION THE ANTENNA ON TOWER PIPE MOUNTS SO THAT THE BOTTOM STRUT IS LEVEL. THE PIPE MOUNTS SHALL BE PLUMB TO WITHIN 1 DEGREE.

B. ANTENNA MOUNTING REQUIREMENTS: PROVIDE ANTENNA MOUNTING HARDWARE AS INDICATED ON THE DRAWINGS.

**HYBRID CABLE INSTALLATION:**

A. THE CONTRACTOR SHALL ROUTE, TEST, AND INSTALL ALL CABLES AS INDICATED ON THE CONSTRUCTION DRAWINGS AND IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS.

B. THE INSTALLED RADIUS OF THE CABLES SHALL NOT BE LESS THAN THE MANUFACTURER'S SPECIFICATIONS FOR BENDING RADII.

C. EXTREME CARE SHALL BE TAKEN TO AVOID DAMAGE TO THE CABLES DURING HANDLING AND INSTALLATION.

1. FASTENING MAIN HYBRID CABLES: ALL CABLES SHALL BE INSTALLED INSIDE MONOPOLE WITH CABLE SUPPORT GRIPS AS REQUIRED BY THE MANUFACTURER.

2. FASTENING INDIVIDUAL FIBER AND DC CABLES ABOVE BREAKOUT ENCLOSURE (MEDUSA), WITHIN THE MMBS CABINET AND ANY INTERMEDIATE DISTRIBUTION BOXES:

a. FIBER: SUPPORT FIBER BUNDLES USING 1/2" VELCRO STRAPS OF THE REQUIRED LENGTH AT 18" O.C. STRAPS SHALL BE UV, OIL AND WATER RESISTANT AND SUITABLE FOR INDUSTRIAL INSTALLATIONS AS MANUFACTURED BY TEXTOL OR APPROVED EQUAL.

b. DC: SUPPORT DC BUNDLES WITH ZIP TIES OF THE ADEQUATE LENGTH. ZIP TIES TO BE UV STABILIZED, BLACK NYLON, WITH TENSILE STRENGTH AT 12,000 PSI AS MANUFACTURED BY NELCO PRODUCTS OR EQUAL.

3. FASTENING JUMPERS: SECURE JUMPERS TO THE SIDE ARMS OR HEAD FRAMES USING STAINLESS STEEL TIE WRAPS OR STAINLESS STEEL BUTTERFLY CLIPS.

4. CABLE INSTALLATION:

a. INSPECT CABLE PRIOR TO USE FOR SHIPPING DAMAGE, NOTIFY THE CONSTRUCTION MANAGER.

b. CABLE ROUTING: CABLE INSTALLATION SHALL BE PLANNED TO ENSURE THAT THE LINES WILL BE PROPERLY ROUTED IN THE CABLE ENVELOP AS INDICATED ON THE DRAWINGS. AVOID TWISTING AND CROSSEOVERS.

c. HOIST CABLE USING PROPER HOISTING GRIPS. DO NOT EXCEED MANUFACTURER'S RECOMMENDED MAXIMUM BEND RADIUS.

5. GROUNDING OF TRANSMISSION LINES: ALL TRANSMISSION LINES SHALL BE GROUNDED AS INDICATED ON DRAWINGS.

6. HYBRID CABLE COLOR CODING: ALL COLOR CODING SHALL BE AS REQUIRED IN TS 0200 (CURRENT VERSION).

7. HYBRID CABLE LABELING: INDIVIDUAL HYBRID AND DC BUNDLES SHALL BE LABELED ALPHA-NUMERICALLY ACCORDING TO SPRINT CELL SITE ENGINEERING NOTICE - EN 2012-001, REV 1

**WEATHERPROOFING EXTERIOR CONNECTORS AND HYBRID CABLE GROUND KITS:**

A. ALL FIBER & COAX CONNECTORS AND GROUND KITS SHALL BE WEATHERPROOFED.

B. WEATHERPROOFED USING ONE OF THE FOLLOWING METHODS. ALL INSTALLATIONS MUST BE DONE IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS AND INDUSTRY BEST PRACTICES.

1. COLD SHRINK: ENCOMPASS CONNECTOR IN COLD SHRINK TUBING AND PROVIDE A DOUBLE WRAP OF 2" ELECTRICAL TAPE EXTENDING 2" BEYOND TUBING. PROVIDE 3M COLD SHRINK CX5 SERIES OR EQUAL.

2. SELF-AMALGAMATING TAPE: CLEAN SURFACES. APPLY A DOUBLE WRAP OF SELF-AMALGAMATING TAPE 2" BEYOND CONNECTOR. APPLY A SECOND WRAP OF SELF-AMALGAMATING TAPE IN OPPOSITE DIRECTION. APPLY DOUBLE WRAP OF 2" WIDE ELECTRICAL TAPE EXTENDING 2" BEYOND THE SELF-AMALGAMATING TAPE.

3. 3M SLIM LOCK CLOSURE 716: SUBSTITUTIONS WILL NOT BE ALLOWED.

4. OPEN FLAME ON JOB SITE IS NOT ACCEPTABLE

**SECTION 11 800 - INSTALLATION OF MULTIMODAL BASE STATIONS (MMBS) AND RELATED EQUIPMENT**

**SUMMARY:**

A. THIS SECTION SPECIFIES MMBS CABINETS, POWER CABINETS, AND INTERNAL EQUIPMENT INCLUDING BY NOT LIMITED TO RECTIFIERS, POWER DISTRIBUTION UNITS, BASE BAND UNITS, SURGE ARRESTORS, BATTERIES, AND SIMILAR EQUIPMENT FURNISHED BY THE COMPANY FOR INSTALLATION BY THE CONTRACTOR (OFCI).

B. CONTRACTOR SHALL PROVIDE AND INSTALL ALL MISCELLANEOUS MATERIALS AND PROVIDE ALL LABOR REQUIRED FOR INSTALLATION EQUIPMENT IN EXISTING CABINET OR NEW CABINET AS SHOWN ON DRAWINGS AND AS REQUIRED BY THE APPLICABLE INSTALLATION MOPS.

C. COMPLY WITH MANUFACTURER'S INSTALLATION AND START-UP REQUIREMENTS.

**DC CIRCUIT BREAKER LABELING**

A. NEW DC CIRCUIT IS REQUIRED IN MMBS CABINET SHALL BE CLEARLY IDENTIFIED AS TO RRU BEING SERVICED.

**SECTION 26 100 - BASIC ELECTRICAL REQUIREMENTS**

**SUMMARY:**

THIS SECTION SPECIFIES BASIC ELECTRICAL REQUIREMENTS FOR SYSTEMS AND COMPONENTS

**QUALITY ASSURANCE:**

A. ALL EQUIPMENT FURNISHED UNDER DIVISION 26 SHALL CARRY UL LABELS AND LISTINGS WHERE SUCH LABELS AND LISTINGS ARE AVAILABLE IN THE INDUSTRY.

B. MANUFACTURERS OF EQUIPMENT SHALL HAVE A MINIMUM OF THREE YEARS EXPERIENCE WITH THEIR EQUIPMENT INSTALLED AND OPERATING IN THE FIELD IN A USE SIMILAR TO THE PROPOSED USE FOR THIS PROJECT.

C. MATERIALS AND EQUIPMENT: ALL MATERIALS AND EQUIPMENT SPECIFIED IN DIVISION 26 OF THE SAME TYPE SHALL BE OF THE SAME MANUFACTURER AND SHALL BE NEW, OF THE BEST QUALITY AND DESIGN, AND FREE FROM DEFECTS.

**SUPPORTING DEVICES:**

A. MANUFACTURED STRUCTURAL SUPPORT MATERIALS: SUBJECT TO COMPLIANCE WITH REQUIREMENTS, PROVIDE PRODUCTS BY THE FOLLOWING:

1. ALLIED TUBE AND CONDUIT.
2. B-LINE SYSTEM.
3. UNISTRUT DIVERSIFIED PRODUCTS.
4. THOMAS & BETTS.

B. FASTENERS: TYPES, MATERIALS, AND CONSTRUCTION FEATURES AS FOLLOWS:

1. EXPANSION ANCHORS: CARBON STEEL WEDGE OR SLEEVE TYPE.
2. POWER-DRIVEN THREADED STUDS: HEAT-TREATED STEEL, DESIGNED SPECIFICALLY FOR THE INTENDED SERVICE.
3. FASTEN BY MEANS OF WOOD SCREWS ON WOOD.
4. TOGGLE BOLTS ON HOLLOW MASONRY UNITS.
5. CONCRETE INSERTS OR EXPANSION BOLTS ON CONCRETE OR SOLID MASONRY.
6. MACHINE SCREWS, WELDED THREADED STUDS, OR SPRING-TENSION CLAMPS ON STEEL.
7. EXPLOSIVE DEVICES FOR ATTACHING HANGERS TO STRUCTURE SHALL NOT BE PERMITTED.
8. DO NOT WELD CONDUIT, PIPE STRAPS, OR ITEMS OTHER THAN THREADED STUDS TO STEEL STRUCTURES.
9. IN PARTITIONS OF LIGHT STEEL CONSTRUCTION, USE SHEET METAL SCREWS.



**6580 SPRINT PARKWAY  
OVERLAND PARK, KANSAS 66251**



**1120 Dallas Street, Sauk City, WI 53583  
Phone: 608-643-4100 Fax: 608-643-7999  
www.Ramaker.com**



**48 SPRUCE STREET  
OAKLAND, NJ 07346**

**Certification & Seal:**  
I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



*James R. Skowronski* 8/29/2014  
Signature: \_\_\_\_\_ Date: \_\_\_\_\_

MARK	DATE	DESCRIPTION

ISSUE PHASE	FINAL	DATE ISSUED	08/29/2014
PROJECT TITLE:	STAMFORD FIRE DEPT. CTO3XC328-A		

**PROJECT INFORMATION:**  
366 OLD LONG RIDGE ROAD  
STAMFORD, CT 06903  
FAIRFIELD COUNTY

**SHEET TITLE:**  
SPRINT SPECIFICATIONS

**SCALE:** NONE

PROJECT NUMBER	29012
SHEET NUMBER	SP-2

SUPPORTING DEVICES:

- A. INSTALL SUPPORTING DEVICES TO FASTEN ELECTRICAL COMPONENTS SECURELY AND PERMANENTLY IN ACCORDANCE WITH NEC.
- B. COORDINATE WITH THE BUILDING STRUCTURAL SYSTEM AND WITH OTHER TRADES.
- C. UNLESS OTHERWISE INDICATED ON THE DRAWINGS, FASTEN ELECTRICAL ITEMS AND THEIR SUPPORTING HARDWARE SECURELY TO THE STRUCTURE IN ACCORDANCE WITH THE FOLLOWING:
  - 1. ENSURE THAT THE LOAD APPLIED BY ANY FASTENER DOES NOT EXCEED 25 PERCENT OF THE PROOF TEST LOAD.
  - 2. USE VIBRATION AND SHOCK-RESISTANT FASTENERS FOR ATTACHMENTS TO CONCRETE SLABS.

ELECTRICAL IDENTIFICATION:

- A. UPDATE AND PROVIDE TYPED CIRCUIT BREAKER SCHEDULES IN THE MOUNTING BRACKET, INSIDE DOORS OF AC PANEL BOARDS WITH ANY CHANGES MADE TO THE AC SYSTEM.
- B. BRANCH CIRCUITS FEEDING AVIATION OBSTRUCTION LIGHTING EQUIPMENT SHALL BE CLEARLY IDENTIFIED AS SUCH AT THE BRANCH CIRCUIT PANELBOARD.

SECTION 26 200 - ELECTRICAL MATERIALS AND EQUIPMENT

- A. RIGID GALVANIZED STEEL (RGS) CONDUIT SHALL BE USED FOR EXTERIOR LOCATIONS ABOVE GROUND AND IN UNFINISHED INTERIOR LOCATIONS AND FOR UNDERGROUND RUNS. RIGID CONDUIT AND FITTINGS SHALL BE STEEL, COATED WITH ZINC EXTERIOR AND INTERIOR BY THE HOT DIP GALVANIZING PROCESS. CONDUIT SHALL BE PRODUCED TO ANSI SPECIFICATIONS C80.1, FEDERAL SPECIFICATION WW-C-581 AND SHALL BE LISTED WITH THE UNDERWRITERS' LABORATORIES. FITTINGS SHALL BE THREADED - SET SCREW OR COMPRESSION FITTINGS WILL NOT BE ACCEPTABLE. RGS CONDUITS SHALL BE MANUFACTURED BY ALLIED, REPUBLIC OR WHEATLAND.
- B. UNDERGROUND CONDUIT IN CONCRETE SHALL BE POLYVINYLCHLORIDE (PVC) SUITABLE FOR DIRECT BURIAL AS APPLICABLE. JOINTS SHALL BE BELLED, AND FLUSH SOLVENT WELDED IN ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS. CONDUIT SHALL BE CARLON ELECTRICAL PRODUCTS OR APPROVED EQUAL.
- C. TRANSITIONS BETWEEN PVC AND RIGID (RGS) SHALL BE MADE WITH PVC COATED METALLIC LONG SWEEP RADIUS ELBOWS.
- D. EMT OR RIGID GALVANIZED STEEL CONDUIT MAY BE USED IN FINISHED SPACES CONCEALED IN WALLS AND CEILINGS. EMT SHALL BE MILD STEEL, ELECTRICALLY WELDED, ELECTRO-GALVANIZED OR HOT-DIPPED GALVANIZED AND PRODUCED TO ANSI SPECIFICATION C80.3, FEDERAL SPECIFICATION WW-C-563, AND SHALL BE UL LISTED. EMT SHALL BE MANUFACTURED BY ALLIED, REPUBLIC OR WHEATLAND, OR APPROVED EQUAL. FITTINGS SHALL BE METALLIC COMPRESSION. SET SCREW CONNECTIONS SHALL NOT BE ACCEPTABLE.
- E. LIQUID TIGHT FLEXIBLE METALLIC CONDUIT SHALL BE USED FOR FINAL CONNECTION TO EQUIPMENT. FITTINGS SHALL BE METALLIC GLAND TYPE COMPRESSION FITTINGS, MAINTAINING THE INTEGRITY OF CONDUIT SYSTEM. SET SCREW CONNECTIONS SHALL NOT BE ACCEPTABLE. MAXIMUM LENGTH OF FLEXIBLE CONDUIT SHALL NOT EXCEED 6-FEET. LFMC SHALL BE PROTECTED AND SUPPORTED AS REQUIRED BY NEC. MANUFACTURERS OF FLEXIBLE CONDUITS SHALL BE CAROL, ANACONDA METAL HOSE OR UNIVERSAL METAL HOSE, OR APPROVED EQUAL.
- F. MINIMUM SIZE CONDUIT SHALL BE 3/4 INCH (21 MM).

HUBS AND BOXES:

- A. AT ENTRANCES TO CABINETS OR OTHER EQUIPMENT NOT HAVING INTEGRAL THREADED HUBS PROVIDE METALLIC THREADED HUBS OF THE SIZE AND CONFIGURATION REQUIRED. HUB SHALL INCLUDE LOCKNUT AND NEOPRENE O-RING SEAL. PROVIDE IMPACT RESISTANT 105 DEGREE C PLASTIC BUSHINGS TO PROTECT CABLE INSULATION.
- B. CABLE TERMINATION FITTINGS FOR CONDUIT
  - 1. CABLE TERMINATORS FOR RGS CONDUITS SHALL BE TYPE CRC BY O-Z/GEDNEY OR EQUAL BY ROXTEC.
  - 2. CABLE TERMINATORS FOR LFMC SHALL BE ETCO - CL2075; OR MADE FOR THE PURPOSE PRODUCTS BY ROXTEC.
- C. EXTERIOR PULL BOXES AND PULL BOXES IN INTERIOR INDUSTRIAL AREAS SHALL BE PLATED CAST ALLOY, HEAVY DUTY, WEATHERPROOF, DUST PROOF, WITH GASKET, PLATED IRON ALLOY COVER AND STAINLESS STEEL COVER SCREWS, CROUSE-HINDS WAB SERIES OR EQUAL.
- D. CONDUIT OUTLET BODIES SHALL BE PLATED CAST ALLOY WITH SIMILAR GASKET COVERS. OUTLET BODIES SHALL BE OF THE CONFIGURATION AND SIZE SUITABLE FOR THE APPLICATION. PROVIDE CROUSE-HINDS FORM 8 OR EQUAL.
- E. MANUFACTURER FOR BOXES AND COVERS SHALL BE HOFFMAN, SQUARE "D", CROUSE-HINDS, COOPER, ADALET, APPLETON, O-Z GEDNEY, RACO, OR APPROVED EQUAL.

SUPPLEMENTAL GROUNDING SYSTEM:

- A. FURNISH AND INSTALL A SUPPLEMENTAL GROUNDING SYSTEM TO THE EXTENT INDICATED ON THE DRAWINGS. SUPPORT SYSTEM WITH NON-MAGNETIC STAINLESS STEEL CLIPS WITH RUBBER GROMMETS. GROUNDING CONNECTORS SHALL BE TINNED COPPER WIRE, SIZES AS INDICATED ON THE DRAWINGS. PROVIDE STRANDED OR SOLID BARE OR INSULATED CONDUCTORS EXCEPT AS OTHERWISE NOTED.
- B. SUPPLEMENTAL GROUNDING SYSTEM: ALL CONNECTIONS TO BE MADE WITH CAD WELDS, EXCEPT AT EQUIPMENT USE LUGS OR OTHER AVAILABLE GROUNDING MEANS AS REQUIRED BY MANUFACTURER; AT GROUND BARS USE TWO HOLE SPADES WITH NO-OX.
- C. STOLEN GROUND-BARS: IN THE EVENT OF STOLEN GROUND BARS, CONTACT SPRINT CM FOR REPLACEMENT INSTRUCTION USING THREADED ROD KITS.

EXISTING STRUCTURE:

- A. EXISTING EXPOSED WIRING AND ALL EXPOSED OUTLETS, RECEPTACLES, SWITCHES, DEVICES, BOXES, AND OTHER EQUIPMENT THAT ARE NOT TO BE UTILIZED IN THE COMPLETED PROJECT SHALL BE REMOVED OR DE-ENERGIZED AND CAPPED IN THE WALL, CEILING, OR FLOOR SO THAT THEY ARE CONCEALED AND SAFE. WALL, CEILING, OR FLOOR SHALL BE PATCHED TO MATCH THE ADJACENT CONSTRUCTION.

CONDUIT AND CONDUCTOR INSTALLATION:

- A. CONDUITS SHALL BE FASTENED SECURELY IN PLACE WITH APPROVED NON-PERFORATED STRAPS AND HANGERS. EXPLOSIVE DEVICES FOR ATTACHING HANGERS TO STRUCTURE WILL NOT BE PERMITTED. CLOSELY FOLLOW THE LINES OF THE STRUCTURE, MAINTAIN CLOSE PROXIMITY TO THE STRUCTURE AND KEEP CONDUITS IN TIGHT ENVELOPES. CHANGES IN DIRECTION TO ROUTE AROUND OBSTACLES SHALL BE MADE WITH CONDUIT OUTLET BODIES. CONDUIT SHALL BE INSTALLED IN A NEAT AND WORKMANLIKE MANNER, PARALLEL AND PERPENDICULAR TO STRUCTURE WALL AND CEILING LINES. ALL CONDUIT SHALL BE FISHED TO CLEAR OBSTRUCTIONS. ENDS OF CONDUITS SHALL BE TEMPORARILY CAPPED TO PREVENT CONCRETE, PLASTER OR DIRT FROM ENTERING. CONDUITS SHALL BE RIGIDLY CLAMPED TO BOXES BY GALVANIZED MALLEABLE IRON BUSHING ON INSIDE AND GALVANIZED MALLEABLE IRON LOCKNUT ON OUTSIDE AND INSIDE.
- B. CONDUCTORS SHALL BE PULLED IN ACCORDANCE WITH ACCEPTED GOOD PRACTICE.



6580 SPRINT PARKWAY  
 OVERLAND PARK, KANSAS 66251



1120 Dallas Street, Sauk City, WI 53583  
 Phone: 608-643-4100 Fax: 608-643-7999  
 www.Ramaker.com



48 SPRUCE STREET  
 OAKLAND, NJ 07346

Certification & Seal:  
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 8/29/2014

MARK	DATE	DESCRIPTION

ISSUE PHASE: FINAL DATE ISSUED: 08/29/2014

PROJECT TITLE:  
 STAMFORD FIRE DEPT.  
 CTO3XC328-A


PROJECT INFORMATION:  
 366 OLD LONG RIDGE ROAD  
 STAMFORD, CT 06903  
 FAIRFIELD COUNTY

SHEET TITLE:  
 SPRINT SPECIFICATIONS

SCALE: NONE

PROJECT NUMBER	29012
SHEET NUMBER	SP-3





6580 SPRINT PARKWAY  
 OVERLAND PARK, KANSAS 66251




1120 Dallas Street, Sauk City, WI 53583  
 Phone: 608-643-4100 Fax: 608-643-7999  
 www.Ramaker.com



48 SPRUCE STREET  
 OAKLAND, NJ 07346

Certification & Seal:  
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.




*James R. Skowronski*  
 Signature: \_\_\_\_\_ Date: 8/29/2014

MARK	DATE	DESCRIPTION
ISSUE	FINAL	DATE ISSUED 08/29/2014


PROJECT TITLE:  
**STAMFORD FIRE DEPT.  
 CT03XC328-A**

PROJECT INFORMATION:  
 366 OLD LONG RIDGE ROAD  
 STAMFORD, CT 06903  
 FAIRFIELD COUNTY

SHEET TITLE:  
**SITE PLAN**



**SITE PLAN**  
 SCALE: 1" = 5'



6580 SPRINT PARKWAY  
 OVERLAND PARK, KANSAS 66251



1120 Dallas Street, Sauk City, WI 53583  
 Phone: 608-643-4100 Fax: 608-643-7999  
 www.Ramaker.com



48 SPRUCE STREET  
 OAKLAND, NJ 07346

Certification & Seal:  
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.




Signature: *James R. Skowronski* Date: 8/29/2014

MARK	DATE	DESCRIPTION
ISSUE	FINAL	DATE ISSUED 08/29/2014

PROJECT TITLE:  
**STAMFORD FIRE DEPT.  
 CTO3XC328-A**


PROJECT INFORMATION:  
 366 OLD LONG RIDGE ROAD  
 STAMFORD, CT 06903  
 FAIRFIELD COUNTY

SHEET TITLE:  
**EQUIPMENT PLAN**




**EQUIPMENT PLAN**  
 SCALE: 1" = 2.5'

PROJECT NUMBER: 29012  
 SHEET NUMBER: A-2




ANTENNA & RRH MOUNTING DETAILS  
 SCALE: NTS

1





EXISTING ANTENNA ARRAY  
 SCALE: NTS

3



BUILDING ELEVATION  
 SCALE: 1" = 40'

2



PROPOSED ANTENNA ARRAY  
 SCALE: NTS

4



6580 SPRINT PARKWAY  
 OVERLAND PARK, KANSAS 66251



1120 Dallas Street, Sauk City, WI 53583  
 Phone: 608-643-4100 Fax: 608-643-7999  
 www.Ramaker.com



48 SPRUCE STREET  
 OAKLAND, NJ 07346

Certification & Seal:  
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 8/29/2014

MARK	DATE	DESCRIPTION
ISSUE	FINAL	DATE ISSUED 08/29/2014

PROJECT TITLE:  
**STAMFORD FIRE DEPT.  
 CTO3XC328-A**

PROJECT INFORMATION:  
 366 OLD LONG RIDGE ROAD  
 STAMFORD, CT 06903  
 FAIRFIELD COUNTY

SHEET TITLE:  
**BUILDING ELEVATIONS &  
 ANTENNA DETAILS**

SCALE:  
 AS NOTED

PROJECT NUMBER	29012
SHEET NUMBER	A-3

### RFDS Sheet

#### General Site Information

Site ID	CT03XC328	Equipment Vendor	Alcatel-Lucent
Market	Southern Connecticut	Latitude	41.15311
Region	Northeast	Longitude	-73.5929397
MLA	N/A	LL SITE ID	N/A
Structure Type	SELF SUPPORT		
BTS Type			

Solution ID		Siterra SR Equipment type		Incremental Power Draw needed by added Equipment	
		Equipment Vendor	Alcatel-Lucent		0

#### Base Equipment

BBU Kit	ALU BBU Kit	Top Hat	None
BBU Kit Qty	1	Top Hat Qty	N/A
Growth Cabinet	N/A	Top Hat Dimenstions	N/A
Growth Cabinet Qty	N/A	Top Hat Weight (lbs)	N/A
Growth Cabinet Dimensions	N/A		
Growth Cabinet Weight	N/A		

#### RF Path Information

RRH	TD-RRH8x20-25
RRH Qty	3
RRH Dimensions	26.1"x18.6"x6.7"
RRH Weight. lbs.	70
RRH Mount Weight. Lbs.	10
Power and Fiber Cable	ALU Fiber Only
Cable Qty	1
Weight per foot. Lbs.	0.242
Diameter. Inches.	0.73
Length Ft.	150 (calculated as antenna height plus 20%)
Coax Jumper	TBD
Coax Jumper Qty	27
Coax Jumper Length. Feet.	25
Coax Jumper Weight	1.7
Coax Jumper Diameter. Inches	0.5
AISG Cable	Commscope ATCB-B01-006
AISG Cable Qty	3
AISG Diameter. Inches.	0.315
AISG Cable Length.	8
Weight of entire AISG cable. Lbs.	1.3

#### Antenna Sector Information

	Sector 1	Sector 2	Sector 3
Antenna make/model	RFS APXV9TM14-ALU-I20	RFS APXV9TM14-ALU-I20	RFS APXV9TM14-ALU-I20
Antenna qty	1	1	1
Antenna Dimensions. Inches	56.3"x12.6"x6.3"	56.3"x12.6"x6.3"	56.3"x12.6"x6.3"
Antenna Weight. Lbs	55.12	55.12	55.12
Antenna Mounting Kit Weight. Lbs.	11.5	11.5	11.5
CL Height	128	128	128
Antenna Azimuth	330	90	190
Antenna Mechanical Downtilt	0	0	0
Antenna etilt	-2	-2	-2

\*RFDS SHEET WAS GENERATED BY RAMAKER & ASSOCIATES FROM PLAN OF RECORD (FOR) PROVIDED BY SPRINT. CONTRACTOR SHALL VERIFY AND OBTAIN FINAL RFDS FROM SPRINT CONSTRUCTION MANAGER PRIOR TO CONSTRUCTION.



6580 SPRINT PARKWAY  
 OVERLAND PARK, KANSAS 66251




1120 Dallas Street, Sauk City, WI 53583  
 Phone: 608-643-4100 Fax: 608-643-7999  
 www.Ramaker.com



48 SPRUCE STREET  
 OAKLAND, NJ 07346

Certification & Seal:  
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 8/29/2014

#### NOTES:

- GENERAL CONTRACTOR TO FIELD VERIFY AZIMUTH AND C/L HEIGHT AND MECHANICAL DOWNTILT. IF DIFFERENT THAN CALLED OUT BELOW, HALT ANTENNA WORK FOR ONE HOUR, CALL SPRINT RF ENGINEER (OR MANAGER IF RF ENGINEER DOES NOT ANSWER, BUT STILL LEAVE A MESSAGE TO RF ENGINEER) USING CONTACT INFORMATION ABOVE FOR FURTHER INSTRUCTIONS. IF SPRINT DOES NOT RESPOND WITHIN ONE HOUR, PLACE 2.5GHZ ANTENNA AT SAME C/L HEIGHT AS 1.9GHZ ANTENNA AND EMAIL CORRECT C/L HEIGHT AND AZIMUTH TO SPRINT RF ENGINEER. UPDATE AS-BUILT DRAWING WITH CORRECT C/L HEIGHT. ALSO EMAIL CORRECT 1.9GHZ AND 800MHZ ANTENNA C/L HEIGHT, AZIMUTH AND MECHANICAL DOWNTILT TO RF ENGINEER.
- AISG TESTS TO VERIFY OPERATION IS TO BE PERFORMED AFTER FINAL INSTALLATION OF ANTENNAS AND AISG CABLES HAVE BEEN CONNECTED. VERIFY OPERATION OF ALL EXISTING SPRINT AISG EQUIPMENT INCLUDING 800MHZ, 1.9GHZ AND 2.5GHZ. TEST TO INCLUDE COMPLETE DOWNTILT, AZIMUTH (IF APPLICABLE) AND BEAMWIDTH SWINGS (IF APPLICABLE). DOCUMENT AISG TEST RESULTS IN COAX SWEEP TEST SPREADSHEET.
- GENERAL CONTRACTOR MUST ENSURE THAT NO OBJECT IS LOCATED WITHIN 45 DEGREES OF LEFT AND RIGHT OF FRONT OF ANTENNA OR 7 DEGREES UP AND DOWN FROM CENTER OF ANTENNA. IF THIS IS NOT POSSIBLE, CONTACT RF ENGINEER FOR FURTHER INSTRUCTION. IN ADDITION, 2.5GHZ ANTENNA IS NOT TO BE PLACED IN FRONT OF ANY OTHER ANTENNA USING THE SAME 45 DEGREE RULE. THIS INCLUDES SPRINT AND NON-SPRINT ANTENNAS.
- 2.5GHZ ANTENNA MUST BE AT LEAST 6" FROM 1.9GHZ ANTENNA, 30" FROM 800MHZ ANTENNA AND 30" FROM DUAL BAND 1.9GHZ AND 800MHZ ANTENNA.
- GENERAL CONTRACTOR IS REQUIRED TO USE A DIGITAL ALIGNMENT TOOL TO SET AZIMUTH, ROLL AND DOWNTILT. AZIMUTH ACCURACY IS TO BE WITHIN 1 DEGREE. DOWNTILT AND ROLL (LEFT TO RIGHT TILT) IS TO BE WITHIN 0.1 DEGREES. IF FOR SOME REASON THIS ACCURACY CANNOT BE ACHIEVED, UPDATE AS-BUILT DRAWINGS AND EMAIL SPRINT RF ENGINEER WITH AS-BUILT SETTINGS. USE 3Z RF ALIGNMENT TOOL OR EQUIVALENT TOOL.

MARK	DATE	DESCRIPTION
ISSUE	FINAL	DATE ISSUED 08/29/2014


PROJECT TITLE:  
**STAMFORD FIRE DEPT.  
 CT03XC328-A**

PROJECT INFORMATION:  
 366 OLD LONG RIDGE ROAD  
 STAMFORD, CT 06903  
 FAIRFIELD COUNTY


SHEET TITLE:  
**RF DATA SHEET**

SCALE:  
 AS NOTED


PROJECT NUMBER: 29012  
 SHEET NUMBER: A-4




TYPICAL FIBER DISTRIBUTION BOX DETAIL  
 SCALE: NTS




RRH TO DISTRIBUTION BOX POWER CONNECTIVITY DETAIL  
 SCALE: NTS



8T8R DETAIL  
 SCALE: NTS



BTS TO DISTRIBUTION BOX FIBER CONNECTIVITY DETAIL  
 SCALE: NTS



RRH TO DISTRIBUTION BOX FIBER CONNECTIVITY DETAIL  
 SCALE: NTS



6580 SPRINT PARKWAY  
 OVERLAND PARK, KANSAS 66251




1120 Dallas Street, Sauk City, WI 53583  
 Phone: 608-643-4100 Fax: 608-643-7999  
 www.Ramaker.com



48 SPRUCE STREET  
 OAKLAND, NJ 07346

Certification & Seal:  
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 8/29/2014

MARK	DATE	DESCRIPTION
ISSUE PHASE	FINAL	DATE ISSUED 08/29/2014

PROJECT TITLE:  
**STAMFORD FIRE DEPT.  
 CTO3XC328-A**

PROJECT INFORMATION:  
 366 OLD LONG RIDGE ROAD  
 STAMFORD, CT 06903  
 FAIRFIELD COUNTY

SHEET TITLE:  
**FIBER PLUMBING DIAGRAM**





SCALE:  
 AS NOTED

PROJECT NUMBER	29012
SHEET NUMBER	A-5

2.5 FREQUENCY	INDICATOR		ID
2500 -1	YEL	WHT	GRN
2500 -2	YEL	WHT	RED
2500 -3	YEL	WHT	BRN
2500 -4	YEL	WHT	BLU
2500 -5	YEL	WHT	SLT
2500 -6	YEL	WHT	ORG
2500 -7	YEL	WHT	WHT
2500 -8	YEL	WHT	PPL

NV FREQUENCY	INDICATOR	ID
800-1	YEL	GRN
1900-1	YEL	RED
1900-2	YEL	BRN
1900-3	YEL	BLU
1900-4	YEL	SLT
800-1	YEL	ORG
RESERVED	YEL	WHT
RESERVED	YEL	PPL

Sector	Cable	First Ring	Second Ring	Third Ring
<b>1 Alpha</b>	<b>1</b>	Green	No Tape	No Tape
<b>1</b>	<b>2</b>	Blue	No Tape	No Tape
<b>1</b>	<b>3</b>	Brown	No Tape	No Tape
<b>1</b>	<b>4</b>	White	No Tape	No Tape
<b>1</b>	<b>5</b>	Red	No Tape	No Tape
<b>1</b>	<b>6</b>	Grey	No Tape	No Tape
<b>1</b>	<b>7</b>	Purple	No Tape	No Tape
<b>1</b>	<b>8</b>	Orange	No Tape	No Tape
<b>2 Beta</b>	<b>1</b>	Green	Green	No Tape
<b>2</b>	<b>2</b>	Blue	Blue	No Tape
<b>2</b>	<b>3</b>	Brown	Brown	No Tape
<b>2</b>	<b>4</b>	White	White	No Tape
<b>2</b>	<b>5</b>	Red	Red	No Tape
<b>2</b>	<b>6</b>	Grey	Grey	No Tape
<b>2</b>	<b>7</b>	Purple	Purple	No Tape
<b>2</b>	<b>8</b>	Orange	Orange	No Tape
<b>3 Gamma</b>	<b>1</b>	Green	Green	Green
<b>3</b>	<b>2</b>	Blue	Blue	Blue
<b>3</b>	<b>3</b>	Brown	Brown	Brown
<b>3</b>	<b>4</b>	White	White	White
<b>3</b>	<b>5</b>	Red	Red	Red
<b>3</b>	<b>6</b>	Grey	Grey	Grey
<b>3</b>	<b>7</b>	Purple	Purple	Purple
<b>3</b>	<b>8</b>	Orange	Orange	Orange



COLOR CODING CHARTS  
 SCALE: NTS

CABLE MARKING NOTES

- ALL CABLES SHALL BE MARKED WITH 2" WIDE, UV STABILIZED, UL APPROVED TAPE.
- THE FIRST RING SHALL BE CLOSEST TO THE END OF THE CABLE AND SPACED APPROXIMATELY 2" FROM THE END CONNECTOR, WEATHERPROOFING, OR BREAKOUT UNIT. THERE SHALL BE 1" SPACE BETWEEN EACH RING.
- A 2" GAP SHALL SEPARATE THE CABLE COLOR CODE FROM THE FREQUENCY COLOR CODE. THE 2" COLOR RINGS FOR THE FREQUENCY CODE SHALL BE PLACED NEXT TO EACH OTHER WITH NO SPACES.
- THE 2" COLORED TAPE(S) SHALL BE WRAPPED A MINIMUM OF 3 TIMES AROUND THE INDIVIDUAL CABLES, AND THE TAPE SHALL BE KEPT IN THE SAME LOCATION AS MUCH AS POSSIBLE.
- SITES WITH MORE THAN FOUR (4) SECTORS WILL REQUIRE ADDITIONAL RINGS FOR EACH SECTOR, FOLLOWING THE PATTERN. HIGH CAPACITY SITES WILL USE THE SECOND CABLE IDENTIFIED BY BLUE BANDS OF TAPE.
- HYBRID FIBER CABLE SHALL BE SECTOR IDENTIFIED INSIDE THE CABINET ON FREQUENCY BUNDLES, ON THE SEALTITE, ON THE MAIN LINE UPON EXIT OF SEALTITE, AND BEFORE AND AFTER THE BREAKOUT UNIT (MEDUSA), AS WELL AS BEFORE AND AFTER ANY ENTRANCE OR EXIT.
- HFC "MAIN TRUNK" WILL NOT BE MARKED WITH THE FREQUENCY CODES, AS IT CONTAINS ALL FREQUENCIES.
- INDIVIDUAL POWER PAIRS AND FIBER BUNDLES SHALL BE LABELED WITH BOTH THE CABLE AND FREQUENCY.



6580 SPRINT PARKWAY  
 OVERLAND PARK, KANSAS 66251




1120 Dallas Street, Sauk City, WI 53583  
 Phone: 608-643-4100 Fax: 608-643-7999  
 www.Ramaker.com



48 SPRUCE STREET  
 OAKLAND, NJ 07346

Certification & Seal:  
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 8/29/2014

MARK	DATE	DESCRIPTION
ISSUE	FINAL	DATE ISSUED 08/29/2014

PROJECT TITLE:  
**STAMFORD FIRE DEPT.  
 CTO3XC328-A**

PROJECT INFORMATION:  
 366 OLD LONG RIDGE ROAD  
 STAMFORD, CT 06903  
 FAIRFIELD COUNTY

SHEET TITLE:  
**CABLE COLOR CODING**

SCALE:  
 AS NOTED

PROJECT NUMBER: 29012  
 SHEET NUMBER: A-6

HYBRID CABLE DC CONDUCTOR SIZE GUIDELINE  
 MANUF:RFS




CABLE	LENGTH	DC CONDUCTOR	CABLE DIAMETER
Fiber Only	Varies	Use NV Hybriflex	5/8"
Hybriflex	<200'	8 AWG	1-1/4"
Hybriflex	225-300'	6 AWG	1-1/4"
Hybriflex	325-375'	4 AWG	1-1/4"

RFS HYBRIFLEX RISER CABLE SCHEDULE

FIBER ONLY (EXISTING DC POWER)	Hybrid cable	
MN-HB058-M12-050F	12x multi-mode fiber pairs, Top:Outdoor protected connectors, Bottom:LC	50 ft
MN-HB058-M12-075F	Connectors, 5/8 cable, 50 ft	75 ft
MN-HB058-M12-100F		100 ft
MN-HB058-M12-125F		125 ft
MN-HB058-M12-150F		150 ft
MN-HB058-M12-175F		175 ft
MN-HB058-M12-200F		200 ft
8 AWG Power	Hybrid cable	
MN-HB114-08U3M12-050F	3x 8 AWG power pairs, 12x multi-mode fiber pairs, Outdoor rated connectors & LC connectors. 1 1/4 cable, 50 ft	50 ft
MN-HB114-08U3M12-075F		75 ft
MN-HB114-08U3M12-100F		100 ft
MN-HB114-08U3M12-125F		125 ft
MN-HB114-08U3M12-150F		150 ft
MN-HB114-08U3M12-175F		175 ft
MN-HB114-08U3M12-200F		200 ft
6 AWG Power	Hybrid cable	
MN-HB114-13U3M12-225F	3x 6 AWG power pairs, 12x multi-mode fiber pairs, Outdoor rated connectors & LC connectors. 1 1/4 cable, 225 ft	225 ft
MN-HB114-13U3M12-250F		250 ft
MN-HB114-13U3M12-275F		275 ft
MN-HB114-13U3M12-300F		300 ft
4 AWG Power	Hybrid cable	
MN-HB114-21U3M12-325F	3x 4 AWG power pairs, 12x multi-mode fiber pairs, Outdoor rated connectors & LC connectors. 1 1/4 cable, 325 ft	325 ft
MN-HB114-21U3M12-350F		350 ft
MN-HB114-21U3M12-375F		375 ft

RFS HYBRIFLEX JUMPER CABLE SCHEDULE

FIBER ONLY	Hybrid Jumper cable	
MN-HBF012-M3-5F1	5 ft, 3x multi-mode fiber pairs, Outdoor & LC connectors, 1/2 cable	5 ft
MN-HBF012-M3-10F1		10 ft
MN-HBF012-M3-15F1		15 ft
SPECIAL INSTALLATION NOTE: JUMPERS FROM 2.5 RRH TO 2.5 ANTENNA SHALL NOT EXCEED 15'		
NOTIFY SPRINT CM OF ANY DISCREPANCY		
8 AWG POWER	Hybrid Jumper cable	
MN-HBF058-08U1M3-5F1	5 ft, 1x 8 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC connectors, 5/8 cable	5 ft
MN-HBF058-08U1M3-10F1		10 ft
MN-HBF058-08U1M3-15F1		15 ft
SPECIAL INSTALLATION NOTE: JUMPERS FROM 2.5 RRH TO 2.5 ANTENNA SHALL NOT EXCEED 15'		
NOTIFY SPRINT CM OF ANY DISCREPANCY		
6 AWG POWER	Hybrid Jumper cable	
MN-HBF058-13U1M3-5F1	5 ft, 1x 6 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC connectors, 7/8 cable	5 ft
MN-HBF058-13U1M3-10F1		10 ft
MN-HBF058-13U1M3-15F1		15 ft
SPECIAL INSTALLATION NOTE: JUMPERS FROM 2.5 RRH TO 2.5 ANTENNA SHALL NOT EXCEED 15'		
NOTIFY SPRINT CM OF ANY DISCREPANCY		
4 AWG POWER	Hybrid Jumper cable	
MN-HBF078-21U1M3-5F1	5 ft, 1x 4 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC connectors, 7/8 cable	5 ft
MN-HBF078-21U1M3-10F1		10 ft
MN-HBF078-21U1M3-15F1		15 ft
SPECIAL INSTALLATION NOTE: JUMPERS FROM 2.5 RRH TO 2.5 ANTENNA SHALL NOT EXCEED 15'		
NOTIFY SPRINT CM OF ANY DISCREPANCY		




\*NOTE: SPRINT CM TO CONFIRM HYBRID/FIBER RISER CABLE & HYBRID/FIBER JUMPER CABLE MODEL NUMBERS BEFORE PREPARING BOM.

HYBRID CABLE CROSS SECTION & DATA  
 SCALE: NTS

1


RFS: APXV9TM14-ALU-120

DIMENSIONS, HxWxD: 56.3" x 12.6" x 6.3"  
 WEIGHT, WITHOUT PRE-MOUNTED BRACKETS: 55.12 lbs  
 CONNECTOR: (9) MINI-DIN FEMALE/BOTTOM



2.5 ANTENNA DETAIL  
 SCALE: NTS

2



ALCATEL-LUCENT: TD-RRH8x20  
 HxWxD = (26.1" x 18.6" x 6.7")  
 WEIGHT = 70 lbs.

2.5 RRH DETAIL  
 SCALE: NTS

3



6580 SPRINT PARKWAY  
 OVERLAND PARK, KANSAS 66251




1120 Dallas Street, Sauk City, WI 53585  
 Phone: 608-643-4100 Fax: 608-643-7999  
 www.Ramaker.com



48 SPRUCE STREET  
 OAKLAND, NJ 07346

Certification & Seal:  
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 8/29/2014

MARK	DATE	DESCRIPTION
ISSUE PHASE	FINAL	DATE ISSUED 08/29/2014


PROJECT TITLE:  
**STAMFORD FIRE DEPT.  
 CTO3XC328-A**

PROJECT INFORMATION:  
 366 OLD LONG RIDGE ROAD  
 STAMFORD, CT 06903  
 FAIRFIELD COUNTY

SHEET TITLE:  
**ANTENNA & HYBRID CABLE  
 DETAILS**

SCALE:  
 AS NOTED


PROJECT NUMBER	29012
SHEET NUMBER	A-7



NOTES:

1. LINE UP WHITE MARKINGS ON JUMPER AND RISER IP-MPO CONNECTORS AND SLIDE THE RISER CONNECTOR TO THE JUMPER CONNECTOR. PUSH THE WHITE MARK ON THE JUMPER CONNECTOR FLUSH AGAIN THE RED SEAL ON THE RISER CONNECTOR.
2. ROTATE THE BAYONET HOUSING CLOCKWISE UNTIL YOU HEAR A CLICK SOUND.


HYBRID BREAKOUT DETAIL ①  
 SCALE: NTS



CABLE ROUTE FROM CABINET ②  
 SCALE: NTS



EXISTING BBU CABINET ③  
 SCALE: NTS



EXISTING MMBS CABINET ④  
 SCALE: NTS



6580 SPRINT PARKWAY  
 OVERLAND PARK, KANSAS 66251




1120 Dallas Street, Sauk City, WI 53583  
 Phone: 608-643-4100 Fax: 608-643-7999  
 www.Ramaker.com



48 SPRUCE STREET  
 OAKLAND, NJ 07346

Certification & Seal:  
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 8/29/2014

MARK	DATE	DESCRIPTION
ISSUE	FINAL	DATE ISSUED 08/29/2014

PROJECT TITLE:  
**STAMFORD FIRE DEPT.  
 CTO3XC328-A**



PROJECT INFORMATION:  
 366 OLD LONG RIDGE ROAD  
 STAMFORD, CT 06903  
 FAIRFIELD COUNTY

SHEET TITLE:  
**EQUIPMENT DETAILS**

SCALE:  
 AS NOTED


PROJECT NUMBER	29012
SHEET NUMBER	A-8





**EQUIPMENT UTILITY & GROUNDING PLAN**  
 SCALE: NTS

EXISTING FIBER DISTRIBUTION BOX ON H...



**ANTENNA GROUNDING DETAIL**  
 SCALE: NTS

(1) PROPOSED 5/8" FIBER CABLE TO BE ROUTED ALONG EXISTING CABLES FROM FIBER DISTRIBUTION BOX & UP TOWER TO SECTOR ANTENNAS. USE SNAP-IN HANGERS, SPACED MAX. 4'-0" O.C. AS NEEDED.

**GROUNDING NOTES:**

1. CONTRACTOR TO ENSURE PROPER SEQUENCING OF GROUNDING AND UNDERGROUND CONDUIT INSTALLATION TO PREVENT ANY LOSS OF CONTINUITY IN THE GROUNDING SYSTEM AND/OR DAMAGE TO THE CONDUIT.
2. ALL EXTERIOR GROUND CONDUCTORS SHALL BE #2 AWG SOLID TINNED COPPER UNLESS NOTED OTHERWISE.
3. ALL GROUND CONNECTIONS BELOW GRADE SHALL BE EXOTHERMIC (GADWELD).
4. ALL GROUND CONNECTIONS ABOVE GRADE AND/OR INTERIOR SHALL BE COMPRESSION TYPE, TWO-HOLE LUGS OR DOUBLE-CRIMP "C" TAPS.
5. CONTACT AREAS WHERE CONNECTIONS ARE MADE SHALL BE PREPARED TO A BARE BRIGHT FINISH AND COATED WITH AN ANTI-OXIDATION MATERIAL BEFORE CONNECTIONS ARE MADE.
6. MAXIMUM RESISTANCE OF THE COMPLETED GROUND SYSTEM SHALL NOT EXCEED 5 OHMS.
7. WHERE GROUNDING CONNECTIONS ARE MADE TO PAINTED METAL SURFACES, PAINT SHALL BE REMOVED TO BEAR METAL TO ENSURE PROPER CONTACT AND RESTORED/PAINTED TO ORIGINAL FINISH.
8. GROUND DEPTH SHALL BE 30" MINIMUM BELOW FINISHED GRADE, OR 6" BELOW FROST LINE, WHICHEVER IS GREATER.

LEGEND:	
---	EXISTING GROUND CABLE
----	PROPOSED GROUND CABLE
▲	MECHANICAL CONNECTION
■	EXOTHERMIC CONNECTION
—E—E—E—E—E—	PROPOSED ELECTRIC



6580 SPRINT PARKWAY  
 OVERLAND PARK, KANSAS 66251



1120 Dallas Street, Sauk City, WI 53583  
 Phone: 608-643-4100 Fax: 608-643-7999  
 www.Ramaker.com



48 SPRUCE STREET  
 OAKLAND, NJ 07346

Certification & Seal:  
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 8/29/2014

MARK	DATE	DESCRIPTION
ISSUE	FINAL	DATE ISSUED 08/29/2014



PROJECT TITLE:  
**STAMFORD FIRE DEPT.  
 CTO3XC328-A**

PROJECT INFORMATION:  
 366 OLD LONG RIDGE ROAD  
 STAMFORD, CT 06903  
 FAIRFIELD COUNTY


SHEET TITLE:  
**EQUIPMENT UTILITY &  
 GROUNDING PLAN**

SCALE:  
 AS NOTED

PROJECT NUMBER	29012
SHEET NUMBER	E-1




**GROUNDING RISER DIAGRAM**  
 SCALE: NTS



- NOTES:
1. APPLY NO-OX TO LUG AND GROUND BAR CONTACT SURFACE. DO NOT COAT INLINE LUG.
  2. IF STOLEN GROUND BARS ARE ENCOUNTERED, CONTACT SPRINT CM FOR REPLACEMENT THREADED ROD KIT.

**GROUNDING CONDUCTOR INSTALLATION**  
 SCALE: NTS



**TWO-HOLE LUG**  
 SCALE: NTS



6580 SPRINT PARKWAY  
 OVERLAND PARK, KANSAS 66251




1120 Dallas Street, Sauk City, WI 53583  
 Phone: 608-643-4100 Fax: 608-643-7999  
 www.Ramaker.com



48 SPRUCE STREET  
 OAKLAND, NJ 07346

Certification & Seal:  
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 8/29/2014

MARK	DATE	DESCRIPTION
ISSUE	FINAL	DATE ISSUED 08/29/2014


PROJECT TITLE:  
**STAMFORD FIRE DEPT.  
 CTO3XC328-A**

PROJECT INFORMATION:  
 366 OLD LONG RIDGE ROAD  
 STAMFORD, CT 06903  
 FAIRFIELD COUNTY

SHEET TITLE:  
**GROUNDING DETAILS**

SCALE:  
 AS NOTED

PROJECT NUMBER	29012
SHEET NUMBER	E-2



### A/C PANEL SCHEDULE

VOLTAGE:	240V/120	PANEL STATUS:	EXISTING	N TO GROUND BOND:	YES
MAIN BREAKER:	200 AMP	MODEL NUMBER:	TBD	INTERNAL TVSS:	YES
MOUNT:	GROUND	PHASE:	1	WIRE:	3
ENCLOSURE TYPE:	NEMA 3R	BUSS RATING:	200 AMP	GROUND BAR:	YES
		NEUTRAL BAR:	YES		

CKT	DESCRIPTION	BREAKER AMPS	BREAKER POLES	BREAKER STATUS	PHASE A VA	PHASE B VA	BREAKER STATUS	BREAKER POLES	BREAKER AMPS	DESCRIPTION	CKT
1	MMBTS	100	2	ON			ON	2	60	SURGE PROTECTION	7
2											8
3	BLANK (UNUSED)	-	-	-			OFF	2	40	CCI	9
4	BLANK (UNUSED)	-	-	-			ON	1	15	NOT LABELED	10
5	BLANK (UNUSED)	-	-	-						BLANK (UNUSED)	11
6	TELCO FAN	10	1	ON							12

AC PANEL SCHEDULE  
 SCALE: NTS



6580 SPRINT PARKWAY  
 OVERLAND PARK, KANSAS 66251

1120 Dallas Street, Sauk City, WI 53583  
 Phone: 608-643-4100 Fax: 608-643-7999  
 www.Ramaker.com

**Transcend Wireless**

48 SPRUCE STREET  
 OAKLAND, NJ 07346

Certification & Seal:  
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: James R. Skowronski  
 Date: 8/29/2014

MARK	DATE	DESCRIPTION
ISSUE	FINAL	DATE ISSUED 08/29/2014

PROJECT TITLE:  
 STAMFORD FIRE DEPT.  
 CTO3XC328-A

PROJECT INFORMATION:  
 366 OLD LONG RIDGE ROAD  
 STAMFORD, CT 06903  
 FAIRFIELD COUNTY

SHEET TITLE:  
 DC POWER DETAILS  
 & PANEL SCHEDULES

SCALE:  
 AS NOTED

PROJECT NUMBER: 29012  
 SHEET NUMBER: E-3