

January 5, 2024

Melanie A. Bachman, Esq.
Executive Director/Staff Attorney
Connecticut Siting Council
10 Franklin Square
New Britain, CT 06051

Re: **Notice of Exempt Modification – Facility Modification**
366 Old Long Ridge Road, Stamford, Connecticut

Dear Attorney Bachman:

Cellco Partnership d/b/a Verizon Wireless (“Cellco”) currently maintains a wireless telecommunications facility at the above-referenced address (the “Property”). Cellco’s facility consists of antennas and remote radio heads attached to a tower. Equipment associated with the facility is located on the ground adjacent to the tower. The tower was approved by the City of Stamford (“City”) in November of 1988. Cellco’s shared use of the tower was approved by the Siting Council (“Council”) in February of 2015 (TS-VER-135-150112). A copy of the City’s tower approval and Council’s TS-VER-135-150112 are included in Attachment 1.

Cellco’s proposed modification involves the installation of four (4) interference mitigation filters (“Filters”) on its existing antenna mounting assembly. The specification sheet for the new Filters is included in Attachment 2.

Please accept this letter as notification pursuant to R.C.S.A. § 16-50j-73, for construction that constitutes an exempt modification pursuant to R.C.S.A. § 16-50j-72(b)(2). In accordance with R.C.S.A. § 16-50j-73, a copy of this letter is being sent to Stamford’s Chief Elected Official and Land Use Officer.

The planned modifications to the facility fall squarely within those activities explicitly provided for in R.C.S.A. § 16-50j-72(b)(2).

1. The proposed modifications will not result in an increase in the height of the existing tower. The Filters will be installed on Cellco’s existing antenna mounting assembly.

28589270-v1

Melanie A. Bachman, Esq.

January 5, 2024

Page 2

2. The proposed modifications will not involve any change to ground-mounted equipment and, therefore, will not require the extension of the site boundary.

3. The proposed modifications will not increase noise levels at the facility by six decibels or more, or to levels that exceed state and local criteria.

4. The installation of Cellco's new Filters will not result in a change to radio frequency (RF) emissions from the facility. Therefore, no new RF emissions information is included in this filing.

5. The proposed modifications will not cause a change or alteration in the physical or environmental characteristics of the site.

6. According to the attached Structural Analysis Report ("SA") and Antenna Mount Analysis Report ("MA"), the existing tower, foundation and antenna mounting assembly can support Cellco's proposed modifications. A copy of the SA and MA are included in Attachment 3.

A copy of the parcel map and Property owner information is included in Attachment 4. A Certificate of Mailing verifying that this filing was sent to municipal officials and the property owner is included in Attachment 5.

For the foregoing reasons, Cellco respectfully submits that the proposed modifications to the above-referenced telecommunications facility constitutes an exempt modification under R.C.S.A. § 16-50j-72(b)(2).

Sincerely,



Kenneth C. Baldwin

Enclosures

Copy to:

Caroline Simmons, Mayor
Ralph Blessing, Land Use Bureau Chief
Long Ridge Fire Company Inc., Property Owner
Aleksy Tyurin, Verizon Wireless

ATTACHMENT 1

400

ZONING APPEALS BOARD CERTIFICATE

VOL 3356 REG 1

20110

I, LEONARD DIPRETA, zoning enforcement officer for the City of Stamford, in compliance with Special Act No. 379 of the 1951 General Assembly, hereby certify that on November 9, 1988 a hearing was held by the Zoning Appeals Board on the application of:

LONG RIDGE FIRE CO., INC.

Appl. #119-88

for a Special Exception as authorized by Section 19-3.2.a. for a replacement radio antenna tower, 150 feet in height, to be constructed on the Long Ridge Fire Company property located on the west side of Old Long Ridge Road, in an RA-2 zone, and is known as 366 Old Long Ridge Road.

and that the land affected is owned by and located on the following streets:

NAME

LOCATION

Long Ridge Fire Co., Inc.

366 Old Long Ridge Road

and that the following is a statement of its findings and approval or rejection.

November 16, 1988

The Board approves this Special Exception as authorized by Section 19-3.2.a. for a replacement radio antenna tower, 150 feet in height, to be constructed on the Long Ridge Fire Company property, subject to the following restriction:

The applicant must adhere to the approved plan which has been signed by Raymond D. Sanborne, Chairman of the Zoning Board of Appeals, and Michael D. Macri, Deputy Zoning Enforcement Officer. Said plan is on file in the office of the Zoning Board of Appeals and is referred to as Proposed Replacement of Radio Antenna Tower, dated 9/12/88.

In rendering the above decision, the Board finds that the proposed use or structure or the proposed extension or alteration of an existing use or structure is in accord with the public convenience and welfare after taking into account, where appropriate:

- (1) the location and nature of the proposed site including its size and configuration, the proposed size, scale and arrangement of structures, drives and parking areas and the proximity of existing dwellings and other structures.
- (2) the nature and intensity of the proposed use in relation to its site and the surrounding area. Operations in connection with special exception uses shall not be injurious to the neighborhood, shall be in harmony with the general purpose and intent of the Zoning Regulations, and shall not be more objectionable to nearby properties by reason of noise, fumes, vibration, artificial lighting or other potential disturbances to the health, safety or peaceful enjoyment of property than the public necessity demands.
- (3) the resulting traffic patterns, the adequacy of existing streets to accommodate the traffic associated with the proposed use, the adequacy of proposed off-street parking and loading, and the extent to which proposed driveways may cause a safety hazard or traffic nuisance.
- (4) the nature of the surrounding area and the extent to which the proposed use or feature might impair its present and future development.
- (5) the Master Plan of the City of Stamford and all statements of the purpose and intent of these regulations.

The applicant(s) is/are allowed one year from the effective date of this decision in which to obtain a building permit.

Given at Stamford, Connecticut, this 1st day of December, 1988.

Raymond D. Sanborne
Raymond D. Sanborne
Chairman, Zoning Board of Appeals

Leonard DiPreta
Leonard DiPreta
Zoning Enforcing Officer of the City of Stamford

The land hereby affected lies in block 400

THE LAND AFFECTED HEREBY LIES IN BLOCK 400
OF THE STAMFORD BLOCK MAP, REOPENED FOR RECORD
AT STAMFORD ON 12-7-88 AT 9:53 A.M.
ATTEST: LOIS PORTER, Town and City Clerk

This decision is under the exclusive jurisdiction of the Council and applies only to this request for tower sharing dated January 12, 2015. This facility has been carefully modeled to ensure that radio frequency emissions are conservatively below State and federal standards applicable to the frequencies now used on this tower. Any deviation from the approved tower sharing request is enforceable under the provisions of Connecticut General Statutes § 16-50u.

The proposed shared use is to be implemented as specified in your letter dated January 12, 2015, including the placement of all necessary equipment and shelters within the tower compound.

Please be advised that the validity of this action shall expire one year from the date of this letter.

Thank you for your attention and cooperation.

Very truly yours,

A handwritten signature in dark ink, appearing to read "Robert Stein" followed by the letters "UAB" in a larger, stylized font.

Robert Stein
Chairman

RS/MP/lm

- c: The Honorable David Martin, Mayor, City of Stamford
Norman Cole, AICP, Land Use Bureau Chief, City of Stamford
Stuart Teitelbaum, Chief, Long Ridge Fire Company

ATTACHMENT 2

KA-6030

TWIN BANDSTOP 900MHZ INTERFERENCE MITIGATION FILTER

The KA-6030 is ideal for co-located 700, 850 and 900 networks. Utilising a 2.6MHz guardband the KA-6030 provides rejection of the 900 UL band while passing 700/850 UL and DL bands. Capable of being used in an outdoor environment the KA-6030 contains two identical bandstop filters, suitable for 2x2 MIMO configuration, offering excellent insertion loss, group delay and rejection.

FEATURES

- Passes full 700 and 850 bands
- Low insertion loss
- Rejection of 900MHz uplink
- DC/AISG pass
- Twin unit
- Dual twin mounting available



TECHNICAL SPECIFICATIONS


BAND NAME	700 PATH / 850 UPLINK PATH	850 DOWNLINK PATH
Passband	698 - 849MHz	869 - 891.5MHz
Insertion loss	0.1dB typical / 0.3dB maximum	0.5dB typical, 1.45dB maximum
Return loss	24dB typical, 18dB minimum	
Maximum input power (Per Port)	100W average	200W average and 66W per 5MHz
Rejection	53dB minimum @ 894.1 - 896.5MHz	
ELECTRICAL		
Impedance	50Ohms	
Intermodulation products	-160dBc maximum in UL Band (assuming 20MHz Signal), with 2 x 43dBm carriers -153dBc maximum with 2 x 43dBm	
DC / AISG		
Passband	0 - 13MHz	
Insertion loss	0.3dB maximum	
Return loss	15dB minimum	
Input voltage range	± 33V	
DC current rating	2A continuous, 4A peak	
Compliance	3GPP TS 25.461	
ENVIRONMENTAL		
For further details of environmental compliance, please contact Kaelus.		
Temperature range	-20°C to +60°C -4°F to +140°F	
Ingress protection	IP67	
Altitude	2600m 8530ft	
Lightning protection	RF port: ±5kA maximum (8/20us), IEC 61000-4-5 – Unit must be terminated with some lightning protection circuits.	
MTBF	>1,000,000 hours	
Compliance	ETSI EN 300 019 class 4.1H, RoHS, NEBS GR-487-CORE	

MECHANICAL	
Dimensions H x D x W	269 x 277 x 80mm 10,60 x 10,90 x 3,15in (Excluding brackets and connectors)
Weight	8,0 kg 17,6 lbs (no bracket)
Finish	Powder coated, light grey (RAL7035)
Connectors	RF: 4,3-10 (F) x 4
Mounting	Optional pole/wall bracket supplied with two metal clamps 45-178mm diameter poles or custom bracket. See ordering information.


ORDERING INFORMATION

PART NUMBER	CONFIGURATION	OPTIONAL FEATURES	CONNECTORS
KA-6030-2032	TWIN, 2 in / 2 out	DC/AISG PASS	4,3-10 (F)

ELECTRICAL BLOCK DIAGRAM



MECHANICAL BLOCK DIAGRAM



ATTACHMENT 3



Structural Analysis Report

Location Code: 468119
Site Name: Stamford NW CT
FUZE Project ID: 17123711
Project Name: RF Filter Add
Address: 366 Old Long Ridge Road
Stamford, CT 06903

Client:

verizon✓

**20 ALEXANDER DRIVE
WALLINGFORD, CT 06492**

Date: 09/21/2023



Centerline Engineering Services, PA
750 W Center St, Suite 301
West Bridgewater, MA 02379
781-713-4725



Scope of Work:

Centerline Communications was authorized by Verizon Wireless to perform an analysis of the existing 152 ft. self support tower to determine its capacity to support the existing and proposed equipment listed in this report.

Existing & Proposed Equipment:

Carrier	Mounting Level (ft)	Center Line Elevation (ft)	Number of Appurtenances	Antenna Manufacturer	Appurtenance Model	Feed Lines (in)
-	152.0	162.0	1	Antennae	20' 4-Bay Dipole	(1) 7/8 (1) EW180
		152.0	1	-	TMA	
		152.0	1	-	6'x4" Sch 40 Pipe Mount	
		152.0	1	-	4' HP MW	
		152.0	1	-	4' x 4.5" Pipe Mount	
	150.0	156.7	1	Decibel	DB563K	(1) 1/2
		150.0	1	-	2' x 3' Side Arm	
-	145.0	145.0	3	Quintel	QS66512-2	(12) 1-5/8
		145.0	6	Kaelus	TMA2117F00V1-1	
		145.0	3	-	Side Arm Mount	
-	140.0	140.0	1	-	4' HP MW	(1) EW180
		140.0	1	-	4' x 4.5" Pipe Mount	
-	135.0	138.0	1	-	6' x 3" Omni	(2) 1-5/8
		135.0	1	Decibel	DB254	
		135.0	2	-	2' x 3' Side Arm	
-	131.0	131.0	3	RFS Celwave	APXVSP18-C-A20	(3) 1-1/4 (1) 7/8
		131.0	3	Alcatel Lucent	RRH2x50	
		131.0	3	Alcatel Lucent	RRH4X45	
		131.0	3	RFS Celwave	APXVTM14-ALU-I20	
		131.0	3	Alcatel Lucent	TD-RRH8x20	
		131.0	3	-	Sector Mount	

Centerline Engineering Services, PA
750 W Center St, Suite 301
West Bridgewater, MA 02379
781-713-4725



-	115.0	118.0	3	Ericsson	AIR32 KRD901146-1 B66 B2A	(4) 6x12 Hybrid
		118.0	3	Ericsson	AIR6449 B41	
		118.0	3	Ericsson	RADIO 4415 B25	
		118.0	3	Ericsson	RRUS 11 B4	
		118.0	3	Ericsson	RADIO 4449 B71+B85	
		118.0	3	RFS Celwave	APXVAALL24_43-UNA20	
		115.0	3	-	Sector Frames	
		115.0	3	Site Pro 1	SFR-K Kit	
		115.0	3	-	Horizontal 10.5'x2.5' std	
Verizon Wireless	96.75	98.0	3	Samsung	MT6407-77A	(3) 1-5/8 Hybrid
		98.0	6	Commscope	JAHH-65B-R3B	
		98.0	3	Samsung	XXDWMM-12.5-65-8T-CBRS	
		98.0	3	Samsung	B2/B66A RRH-BR049 (RFV01UD1A)	
		98.0	3	Samsung	B5/B13 RRH-BR04C (RFV01UD2A)	
		98.0	3	Commscope	CBC78T-DS-43-2X	
		98.0	3	RFS Celwave	DB-T1-6Z-8AB-OZ	
		98.0	4	Kaelus	KA-6030	
		98.0	2	Site Pro 1	RRUDSM	
		98.0	3	Site Pro 1	VFA12-HD	
-	74.0	78.0	1	Antennae	8' 4-Bay Dipole	(1) 7/8
		74.0	1	-	2' x 3' sidearm	
-	58.0	58.0	1	-	GPS	(1) 1/2
			1	-	2' x 3' sidearm	

Note: Proposed equipment shown in **bold**.

Centerline Engineering Services, PA
750 W Center St, Suite 301
West Bridgewater, MA 02379
781-713-4725



Design Criteria:

Design Codes:

2022 Connecticut State Building Code
 2021 International Building Code
 ASCE 7-16
 TIA-222-H Standards

Basic Design Wind Speed (V)	116 mph
Wind Speed with Ice	50 mph
Ice Thickness	1.00 in.
Exposure Category	B
Topographic Category	1
Risk Category	II
Site Soil Class (Assumed)	D – Stiff Soil
Seismic Design Category	B
Spectral Response Acceleration Parameter at a Short Periods, S_s	0.267 g
Spectral Response Acceleration Parameter at a Period of 1 Second, S_1	0.059 g
Short Period Site Coefficient, F_a	1.586
Long Period Site Coefficient, F_v	2.40

*Refer to calculations for additional design criteria.

Conclusion:

Tower Section Capacity (Summary)

Section No.	Elevation ft	Component Type	Size	Critical Element	P lb	ϕP_{allow} lb	% Capacity	Pass/Fail
T1	152 - 140	Leg	P2.375X0.154 (2" STD)	3	-4.58	36.84	12.4	Pass
T2	140 - 135	Leg	P2.875"x0.203" (2.5 STD)	27	-6.87	57.13	12.0	Pass
T3	135 - 130	Leg	P2.875"x0.203" (2.5 STD)	39	-10.73	57.13	18.8	Pass
T4	130 - 125	Leg	P2.875"x0.203" (2.5 STD)	48	-14.44	57.13	25.3	Pass
T5	125 - 120	Leg	P2.875"x0.203" (2.5 STD)	57	-19.29	57.14	33.8	Pass
T6	120 - 100	Leg	Pipe 2.5 XStr (2.875"ODx0.276")	64	-42.69	58.51	73.0	Pass
T7	100 - 80	Leg	2.875"x0.276" w/ 3.5"x.3" Sleeve (STAMFORD NW CT)	85	-70.80	126.18	56.1	Pass
T8	80 - 73.3333	Leg	3.5"x0.3" w/ 4"x.25" Sleeve (STAMFORD NW CT)	115	-80.30	162.69	49.4	Pass

Centerline Engineering Services, PA
 750 W Center St, Suite 301
 West Bridgewater, MA 02379
 781-713-4725



T9	73.3333 - 66.6667	Leg	3.5"x0.3" w/ 4"x.25" Sleeve (STAMFORD NW CT)	127	-88.95	162.72	54.7	Pass
T10	66.6667 - 60	Leg	3.5"x0.3" w/ 4"x.25" Sleeve (STAMFORD NW CT)	139	-97.87	162.76	60.1	Pass
T11	60 - 50	Leg	Pipe 4 XStr (4.5"ODx0.337")	151	-108.55	174.28	62.3	Pass
T12	50 - 40	Leg	Pipe 4 XStr (4.5"ODx0.337")	163	-121.11	174.35	69.5	Pass
T13	40 - 30	Leg	4.5"x0.337" w/ 5"x.25" Sleeve (STAMFORD NW CT 30'-40')	175	-133.70	216.57	61.7	Pass
T14	30 - 20	Leg	4.5"x0.337" w/ 5"x.25" Sleeve (STAMFORD NW CT 20'-30')	187	-145.45	245.84	59.2	Pass
T15	20 - 15	Leg	5.5"x0.259" w/ 6"x.25" Sleeve (STAMFORD NW CT 15'-20')	229	-157.37	186.20	84.5	Pass
T16	15 - 9.99999	Leg	5.5"x0.259" w/ (3) 1.5"x.5" Bars (STAMFORD NW CT 0'-15')	253	-158.54	232.29	68.3	Pass
T17	9.99999 - 0	Leg	5.5"x0.259" w/ (3) 1.5"x.5" Bars (STAMFORD NW CT 0'-15')	262	-170.03	232.30	73.2	Pass
T1	152 - 140	Diagonal	L1 1/2x1 1/2x1/8	11	-1.15	4.77	24.1 36.2 (b)	Pass
T2	140 - 135	Diagonal	L1 1/2x1 1/2x3/16	31	-1.11	5.28	21.0 22.8 (b)	Pass
T3	135 - 130	Diagonal	L1 1/2x1 1/2x3/16	40	-1.56	4.79	32.6	Pass
T4	130 - 125	Diagonal	L1 1/2x1 1/2x1/4	49	-2.45	5.62	43.6	Pass
T5	125 - 120	Diagonal	L1 1/2x1 1/2x1/4	59	-2.20	5.13	42.8	Pass
T6	120 - 100	Diagonal	L2x2x1/4	68	-3.90	7.69	50.7	Pass
T7	100 - 80	Diagonal	L2 1/2x2 1/2x1/4	88	-5.07	11.46	44.3 58.4 (b)	Pass
T8	80 - 73.3333	Diagonal	L2 1/2x2 1/2x1/4	119	-5.09	10.61	48.0 60.0 (b)	Pass
T9	73.3333 - 66.6667	Diagonal	L2 1/2x2 1/2x5/16	130	-5.41	11.91	45.5 60.7 (b)	Pass
T10	66.6667 - 60	Diagonal	L2 1/2x2 1/2x5/16	142	-5.33	11.01	48.4 62.6 (b)	Pass
T11	60 - 50	Diagonal	L3x3x1/4	154	-6.21	11.92	52.1 55.5 (b)	Pass
T12	50 - 40	Diagonal	L3x3x5/16	166	-6.42	13.31	48.3 55.9 (b)	Pass
T13	40 - 30	Diagonal	L3x3x3/8	178	-6.49	14.34	45.2 57.9 (b)	Pass
T14	30 - 20	Diagonal	L3x3x5/16	191	-7.51	27.69	27.1 63.6 (b)	Pass
T15	20 - 15	Diagonal	L3 1/2x3 1/2x1/4	236	-6.15	35.18	17.5 58.6 (b)	Pass
T16	15 - 9.99999	Diagonal	L3 1/2x3 1/2x1/4	256	-6.34	14.46	43.9 57.1 (b)	Pass
T17	9.99999 - 0	Diagonal	L3 1/2x3 1/2x5/16	265	-7.23	15.74	45.9	Pass

Centerline Engineering Services, PA
750 W Center St, Suite 301
West Bridgewater, MA 02379
781-713-4725



							63.7 (b)	
T14	30 - 20	Horizontal	L3x3x1/4	204	-2.52	12.55	20.1	Pass
T16	15 - 9.99999	Horizontal	L3x3x1/4	246	-2.75	7.19	38.2	Pass
T7	100 - 80	Secondary Horizontal	L2 1/2x2 1/2x1/4	96	-1.23	15.68	7.8	Pass
T8	80 - 73.3333	Secondary Horizontal	L2 1/2x2 1/2x1/4	126	-1.39	14.15	9.8	Pass
T9	73.3333 - 66.6667	Secondary Horizontal	L2 1/2x2 1/2x1/4	138	-1.54	12.75	12.1	Pass
T10	66.6667 - 60	Secondary Horizontal	L2 1/2x2 1/2x1/4	150	-1.70	11.55	14.7	Pass
T11	60 - 50	Secondary Horizontal	L2 1/2x2 1/2x1/4	162	-1.88	10.41	18.1	Pass
T12	50 - 40	Secondary Horizontal	L3x3x1/4	174	-2.10	16.03	13.1	Pass
T13	40 - 30	Secondary Horizontal	L3x3x1/4	186	-2.32	14.14	16.4	Pass
T1	152 - 140	Top Girt	L2x2x1/8	5	-0.10	4.07	2.5	Pass
T2	140 - 135	Top Girt	L2x2x1/8	29	-0.12	4.07	2.9	Pass
T14	30 - 20	Redund Horz 1 Bracing	L2x2x1/4	209	-2.52	14.85	17.0	Pass
T15	20 - 15	Redund Horz 1 Bracing	L2x2x1/4	251	-2.95	13.48	21.9	Pass
T14	30 - 20	Redund Diag 1 Bracing	L2x2x1/4	228	-1.47	10.93	13.4	Pass
T15	20 - 15	Redund Diag 1 Bracing	L2x2x1/4	235	-1.58	10.16	15.6	Pass
							Summary	
							Leg (T15)	84.5
							Diagonal (T17)	63.7
							Horizontal (T16)	38.2
							Secondary Horizontal (T11)	18.1
							Top Girt (T2)	2.9
							Redund Horz 1 Bracing (T15)	21.9
							Redund Diag 1 Bracing (T15)	15.6
							Bolt Checks	63.7
							RATING =	84.5

Structure Rating (Max From All Components) =	84.5%
---	--------------

Centerline Engineering Services, PA
750 W Center St, Suite 301
West Bridgewater, MA 02379
781-713-4725



Foundation Capacity (Summary)

Component	% Capacity	Pass Fail
Anchor Rods	76.7	Pass
Foundation – Soil Rating	81.8	Pass
Foundation – Structural Rating	62.2	Pass
Foundation Rating (Max From All Components) =		81.8%

Recommendations:

The existing tower and its foundation have sufficient capacity to support the existing and proposed loading for the final loading configuration.

Reference Documents:

- Structural Analysis Report by Paul J. Ford & Company, dated June 8, 2021
- Lease Exhibit by Centerline Engineering Services, PA, dated August 18, 2023
- Mount Analysis Report by Colliers Engineering and Design, dated 8/1/2023

Assumptions and Limitations:

- The tower and structures were built and maintained with the manufacturer's specifications.
- The configuration of antennas, transmission cables, mounts and other appurtenances are as specified in this report and the referenced drawings.
- Existing appurtenance information obtained from the Structural Analysis Report by Paul J. Ford & Company, dated June 8, 2021 and the Lease Exhibit by Centerline Engineering Services, PA, dated August 18, 2023.

Centerline Engineering Services, PA
750 W Center St, Suite 301
West Bridgewater, MA 02379
781-713-4725



Design Calculations

Centerline Engineering Services, PA
750 W Center St, Suite 301
West Bridgewater, MA 02379
781-713-4725

Section	117	116	115	114	113	112	111	110	109	108	107	106	105	104	103	102	101
Legs	H	G	F	E		Pipe 4 XSR (4.5"ODx0.337")	D	A500-50	C	B	P2.875x0.203* (2.5 STD)	A					
Leg Grade																	
Diagonals	L	K	L3x3x5/16	L3x3x3/8	L3x3x5/16	L3x3x1/4	L2 1/2x2 1/2x5/16	L2 1/2x2 1/2x1/4	L2 1/2x2 1/2x1/4	L2x2x1/4	L1 1/2x1 1/2x1/8						
Diagonal Grade																	
Top Chords																	
Horizontals	N.A.	M	N.A.	L3x3x1/4													L2x2x1/8
Sec. Horizontals																	
Red Horizontals	N.A.	N.A.															
Red Diagonals	N.A.																
Face Width (ft)	20.78	19.77	19.26	18.75	17.73	16.72	15.7	14.69	14.01	13.33	12.66	10.63	8.59	8.09	7.58	7.07	6.56
# Panels @ (ft)	1 @ 9.99999	4 @ 5	4 @ 5	3 @ 10	3 @ 10	15.7	14.69	14.01	13.33	12.66	9 @ 6.66667	12	4 @ 5	4 @ 5	4 @ 5	4 @ 5	3 @ 4
Weight (K)	17.5	1.7	1.1	6.9	2.1	1.8	1.5	1.3	1.0	0.9	0.8	2.2	0.2	0.2	0.2	0.2	0.3

TYPE	ELEVATION	TYPE	ELEVATION
20' 4-Bay Dipole	152	RRUS 4415 B25	115
TMA	152	RRUS 4415 B25	115
6"x4" Sch 40 Pipe	152	Sector Frame Mount	115
4' x 4.5" Pipe Mount	152	Sector Frame Mount	115
4' HP MW	152	Sector Frame Mount	115
DB583K-TT w/ Mount Pipe	150	(3) Site Pro 1 SFR-K	115
2' x 3' sidearm	150	10' x 2-1/4" Pipe Mount	115
QS66512-2 w/ Mount Pipe	145	10' x 2-1/4" Pipe Mount	115
QS66512-2 w/ Mount Pipe	145	10' x 2-1/4" Pipe Mount	115
(2) TMA2117F00V1-1	145	RADIO 4449 B71+B85	115
(2) TMA2117F00V1-1	145	RADIO 4449 B71+B85	115
(2) TMA2117F00V1-1	145	RADIO 4449 B71+B85	115
2' x 3' Side Arm Mount	145	AIR32 KRD901146- 1_B66_B2A w/ Mount Pipe	115
2' x 3' Side Arm Mount	145	AIR32 KRD901146- 1_B66_B2A w/ Mount Pipe	115
2' x 3' Side Arm Mount	145	AIR32 KRD901146- 1_B66_B2A w/ Mount Pipe	115
QS66512-2 w/ Mount Pipe	145		
4' x 4.5" Pipe Mount	140	DB-T1-6Z-8AB-0Z (OVP)	98
4' HP MW	140	DB-T1-6Z-8AB-0Z (OVP)	98
DB254-A	135	DB-T1-6Z-8AB-0Z (OVP)	98
2' x 3' Side Arm Mount	135	B2/B66A RRR-BR049 (RFV01U-D1A)	98
6' x 3" Omni	135	B2/B66A RRR-BR049 (RFV01U-D1A)	98
2' x 3' Side Arm Mount	135	B2/B66A RRR-BR049 (RFV01U-D1A)	98
APXVSP18-C-A20 w/ Mount Pipe	131	B5/B13 RRR-BR04C (RFV01U-D2A)	98
RRH2x50-WCS	131	B5/B13 RRR-BR04C (RFV01U-D2A)	98
RRH2x50-WCS	131	CBC78T-DS-43-2X	98
RRH4X45-19	131	CBC78T-DS-43-2X	98
RRH4X45-19	131	CBC78T-DS-43-2X	98
RRH4X45-19	131	Site Pro 1 VFA12-HD	98
RRH4X45-19	131	Site Pro 1 VFA12-HD	98
APXVTM14-ALU-120 w/ Mount Pipe	131	Site Pro 1 VFA12-HD	98
APXVTM14-ALU-120 w/ Mount Pipe	131	MT6407-77A w/ Pipe Mount	98
APXVTM14-ALU-120 w/ Mount Pipe	131	MT6407-77A w/ Pipe Mount	98
TD-RRH6x20	131	MT6407-77A w/ Pipe Mount	98
TD-RRH6x20	131	(2) KA-8030	98
TD-RRH6x20	131	(2) KA-8030	98
Sector Frame Mount	131	Site Pro 1 RRUDSM	98
Sector Frame Mount	131	Site Pro 1 RRUDSM	98
Sector Frame Mount	131	XDXWMM-12.5-65-8T-CBRS w/ Mount Pipe	98
APXVSP18-C-A20 w/ Mount Pipe	131	XDXWMM-12.5-65-8T-CBRS w/ Mount Pipe	98
APXVSP18-C-A20 w/ Mount Pipe	131	XDXWMM-12.5-65-8T-CBRS w/ Mount Pipe	98
AIR32 KRD901146- 1_B66_B2A w/ Mount Pipe	115	XDXWMM-12.5-65-8T-CBRS w/ Mount Pipe	98
AIR6449 B41 w/ Mount Pipe	115	(2) JAHH-65B-R3B w/ Mount Pipe	98
AIR6449 B41 w/ Mount Pipe	115	(2) JAHH-65B-R3B w/ Mount Pipe	98
AIR6449 B41 w/ Mount Pipe	115	(2) JAHH-65B-R3B w/ Mount Pipe	98
APXVAARR24_43-U-NA20 w/ Mount Pipe	115	BSAMNT-SBS-2-2	98
APXVAARR24_43-U-NA20 w/ Mount Pipe	115	BSAMNT-SBS-2-2	98
APXVAARR24_43-U-NA20 w/ Mount Pipe	115	BSAMNT-SBS-2-2	98
RRUS 11 B4	115	2' x 3' sidearm	74
RRUS 11 B4	115	6' 4-Bay Dipole	74
RRUS 11 B4	115	2' x 3' sidearm	58
RRUS 4415 B25	115	GPS	58

MARK		SIZE	MARK		SIZE
SHEAR 10 K	A	P2.375X0.154 (2" STD)	H	5.5"x0.259" w/ (3) 1.5"x.5" Bars (STAMFORD NW CT 0'-15')	
	B	Pipe 2.5 XStr (2.875"ODx0.276")	I	L1 1/2x1 1/2x3/16	
	C	2.875"x0.276" w/ 3.5"x.3" Sleeve (STAMFORD NW CT)	J	L1 1/2x1 1/2x1/4	
TORQ 50 mph WIN	D	3.5"x0.3" w/ 4"x.25" Sleeve (STAMFORD NW CT)	K	L3 1/2x3 1/2x1/4	
	E	4.5"x0.337" w/ 5"x.25" Sleeve (STAMFORD NW CT 30'-40')	L	L3 1/2x3 1/2x5/16	
	F	4.5"x0.337" w/ 5"x.25" Sleeve (STAMFORD NW CT 20'-30')	M	L3x3x1/4	
AXIAL					

GRADE	Fy	Fu	GRADE	Fy	Fu
A500-80	50 ksi	62 ksi	A36	36 ksi	58 ksi

TOWER DESIGN NOTES

TORQUE 18 kip-ft

REACTIONS

1. Tower designed for Exposure B to the TIA-222-H Standard.
2. Tower designed for a 116 mph basic wind in accordance with the TIA-222-H Standard.
3. Tower is also designed for a 50 mph basic wind with 1.00 in ice. Ice is considered to increase in thickness with height.
4. Deflections are based upon a 60 mph wind.
5. Tower Risk Category II.
6. Topographic Category 1 with Crest Height of 0.00 ft



750 W Center St, Suite 301
West Bridgewater, MA 02379
Phone: (781) 713-4725
FAX:

Project: 23CLVZ-0009

Client: Verizon W

Code: TIA-222-W

Path:

Drawn by: jboegel


Date: 09/21/23

05/21/20

TIA-222-H - 116 mph/50 mph 1.0000 in Ice Exposure B

Leg Capacity ———

Leg Compression (K)



 Centerline Engineering Services, PA 750 W Center St, Suite 301 West Bridgewater, MA 02379 Phone: (781) 713-4725 FAX:	Stamford NW CT Project: 23CLVZ-0009		
	Client: Verizon Wireless	Drawn by: jboegel	App'd:
	Code: TIA-222-H	Date: 09/21/23	Scale: NTS
	Path:		Dwg No. E-3

TIA-222-H - 116 mph/50 mph 1.0000 in Ice Exposure B

Maximum Values


Vx

Vz


Mx

Mz

Global Mast Shear (K)



Global Mast Moment (kip-ft)



Centerline Engineering Services, PA

750 W Center St, Suite 301
West Bridgewater, MA 02379

Phone: (781) 713-4725

FAX:

Job: Stamford NW CT

Project: 23CLVZ-0009

Client: Verizon Wireless

Drawn by: jboegel

App'd:

Code: TIA-222-H

Date: 09/21/23


Scale: NTS

Path:

Dwg No. E-4

TIA-222-H - Service - 60 mph


Maximum Values



	Centerline Engineering Services, PA 750 W Center St, Suite 301 West Bridgewater, MA 02379 Phone: (781) 713-4725 FAX:			Job: Stamford NW CT		
	Project: 23CLVZ-0009					
	Client: Verizon Wireless			Drawn by: jboegel		App'd:
	Code: TIA-222-H			Date: 09/21/23		Scale: NTS
	Path:					Dwg No. E-5

Feed Line Distribution Chart 0' - 152'


Round Flat App In Face App Out Face Truss Leg



Feed Line Plan 15'

Round Flat App In Face App Out Face


Section @ 15'




	Centerline Engineering Services, PA		Job: Stamford NW CT	
	750 W Center St, Suite 301 West Bridgewater, MA 02379		Project: 23CLVZ-0009	
	Phone: (781) 713-4725 FAX:		Client: Verizon Wireless	Drawn by: jboegel
			Code: TIA-222-H	Date: 09/21/23
			Path:	Scale: NTS Dwg No. E-7


Stress Distribution Chart 0' - 152'

■ > 100%
 ■ 90%-100%
 ■ 75%-90%
 ■ 50%-75%
 ■ < 50% Overstress



Wind Pressures and Ice Thickness
TIA-222-H - 116 mph/50 mph 1.0000 in Ice Exposure B



	Centerline Engineering Services, PA 750 W Center St, Suite 301 West Bridgewater, MA 02379 Phone: (781) 713-4725 FAX:			Job: Stamford NW CT
	Project: 23CLVZ-0009			Client: Verizon Wireless
	Code: TIA-222-H			Drawn by: jboegel
	Path:			Date: 09/21/23
				App'd: NTS Scale: NTS Dwg No: E-9

tnxTower Centerline Engineering Services, PA 750 W Center St, Suite 301 West Bridgewater, MA 02379 Phone: (781) 713-4725 FAX:	Job	Stamford NW CT	Page	1 of 52
	Project	23CLVZ-0009	Date	15:14:50 09/21/23
	Client	Verizon Wireless	Designed by	jboegel

Tower Input Data

The main tower is a 3x free standing tower with an overall height of 152.00 ft above the ground line.

The base of the tower is set at an elevation of 0.00 ft above the ground line.

The face width of the tower is 6.52 ft at the top and 20.78 ft at the base.

This tower is designed using the TIA-222-H standard.

The following design criteria apply:

Tower base elevation above sea level: 438.20 ft.

Basic wind speed of 116 mph.

Risk Category II.

Exposure Category B.

Simplified Topographic Factor Procedure for wind speed-up calculations is used.

Topographic Category: 1.

Crest Height: 0.00 ft.

Nominal ice thickness of 1.0000 in.

Ice thickness is considered to increase with height.

Ice density of 56 pcf.

A wind speed of 50 mph is used in combination with ice.

Temperature drop of 50 °F.

Deflections calculated using a wind speed of 60 mph.

Pressures are calculated at each section.

Stress ratio used in tower member design is 1.

Tower analysis based on target reliabilities in accordance with Annex S.

Load Modification Factors used: $K_{es}(F_w) = 0.95$, $K_{es}(t_i) = 0.85$.


Maximum demand-capacity ratio is: 1.

Local bending stresses due to climbing loads, feed line supports, and appurtenance mounts are not considered.

Options

- | | | |
|--|---|--|
| <ul style="list-style-type: none"> Consider Moments - Legs Consider Moments - Horizontals Consider Moments - Diagonals Use Moment Magnification ✓ Use Code Stress Ratios ✓ Use Code Safety Factors - Guys Escalate Ice Always Use Max Kz Use Special Wind Profile ✓ Include Bolts In Member Capacity Leg Bolts Are At Top Of Section ✓ Secondary Horizontal Braces Leg Use Diamond Inner Bracing (4 Sided) ✓ SR Members Have Cut Ends SR Members Are Concentric | <ul style="list-style-type: none"> Distribute Leg Loads As Uniform Assume Legs Pinned ✓ Assume Rigid Index Plate ✓ Use Clear Spans For Wind Area ✓ Use Clear Spans For KL/r Retension Guys To Initial Tension ✓ Bypass Mast Stability Checks ✓ Use Azimuth Dish Coefficients ✓ Project Wind Area of Appurt. Autocalc Torque Arm Areas Add IBC .6D+W Combination ✓ Sort Capacity Reports By Component Triangulate Diamond Inner Bracing Treat Feed Line Bundles As Cylinder Ignore KL/ry For 60 Deg. Angle Legs | <ul style="list-style-type: none"> Use ASCE 10 X-Brace Ly Rules ✓ Calculate Redundant Bracing Forces Ignore Redundant Members in FEA ✓ SR Leg Bolts Resist Compression All Leg Panels Have Same Allowable Offset Girt At Foundation ✓ Consider Feed Line Torque ✓ Include Angle Block Shear Check Use TIA-222-H Bracing Resist. Exemption Use TIA-222-H Tension Splice Exemption Poles Include Shear-Torsion Interaction Always Use Sub-Critical Flow Use Top Mounted Sockets Pole Without Linear Attachments Pole With Shroud Or No Appurtenances Outside and Inside Corner Radii Are Known |
|--|---|--|

tnxTower Centerline Engineering Services, PA 750 W Center St, Suite 301 West Bridgewater, MA 02379 Phone: (781) 713-4725 FAX:	Job	Stamford NW CT	Page 2 of 52
	Project	23CLVZ-0009	Date 15:14:50 09/21/23
	Client	Verizon Wireless	Designed by jboegel



Triangular Tower

Tower Section Geometry

Tower Section	Tower Elevation	Assembly Database	Description	Section Width	Number of Sections	Section Length
	ft			ft		ft
T1	152.00-140.00			6.52	1	12.00
T2	140.00-135.00			6.56	1	5.00
T3	135.00-130.00			7.07	1	5.00
T4	130.00-125.00			7.58	1	5.00
T5	125.00-120.00			8.09	1	5.00
T6	120.00-100.00			8.59	1	20.00
T7	100.00-80.00			10.63	1	20.00
T8	80.00-73.33			12.66	1	6.67
T9	73.33-66.67			13.33	1	6.67
T10	66.67-60.00			14.01	1	6.67
T11	60.00-50.00			14.69	1	10.00
T12	50.00-40.00			15.70	1	10.00
T13	40.00-30.00			16.72	1	10.00
T14	30.00-20.00			17.73	1	10.00
T15	20.00-15.00			18.75	1	5.00
T16	15.00-10.00			19.26	1	5.00
T17	10.00-0.00			19.77	1	10.00

Tower Section Geometry (cont'd)

tnxTower Centerline Engineering Services, PA 750 W Center St, Suite 301 West Bridgewater, MA 02379 Phone: (781) 713-4725 FAX:	Job	Stamford NW CT	Page	3 of 52
	Project	23CLVZ-0009	Date	15:14:50 09/21/23
	Client	Verizon Wireless	Designed by	jboegel

Tower Section	Tower Elevation	Diagonal Spacing	Bracing Type	Has K Brace End Panels	Has Horizontals	Top Girt Offset	Bottom Girt Offset
	ft	ft				in	in
T1	152.00-140.00	4.00	X Brace	No	No	0.0000	0.0000
T2	140.00-135.00	5.00	X Brace	No	No	0.0000	0.0000
T3	135.00-130.00	5.00	X Brace	No	No	0.0000	0.0000
T4	130.00-125.00	5.00	X Brace	No	No	0.0000	0.0000
T5	125.00-120.00	5.00	X Brace	No	No	0.0000	0.0000
T6	120.00-100.00	6.67	X Brace	No	No	0.0000	0.0000
T7	100.00-80.00	6.67	X Brace	No	Yes	0.0000	0.0000
T8	80.00-73.33	6.67	X Brace	No	Yes	0.0000	0.0000
T9	73.33-66.67	6.67	X Brace	No	Yes	0.0000	0.0000
T10	66.67-60.00	6.67	X Brace	No	Yes	0.0000	0.0000
T11	60.00-50.00	10.00	X Brace	No	Yes	0.0000	0.0000
T12	50.00-40.00	10.00	X Brace	No	Yes	0.0000	0.0000
T13	40.00-30.00	10.00	X Brace	No	Yes	0.0000	0.0000
T14	30.00-20.00	5.00	Double K1	No	Yes	0.0000	0.0000
T15	20.00-15.00	5.00	K1 Up	No	Yes	0.0000	0.0000
T16	15.00-10.00	5.00	K Brace Down	No	Yes	0.0000	0.0000
T17	10.00-0.00	10.00	X Brace	No	No	0.0000	0.0000

Tower Section Geometry (cont'd)

Tower Elevation	Leg Type	Leg Size	Leg Grade	Diagonal Type	Diagonal Size	Diagonal Grade
ft						
T1 152.00-140.00	Pipe	P2.375X0.154 (2" STD)	A500-50 (50 ksi)	Equal Angle	L1 1/2x1 1/2x1/8	A36 (36 ksi)
T2 140.00-135.00	Pipe	P2.875"x0.203" (2.5 STD)	A500-50 (50 ksi)	Equal Angle	L1 1/2x1 1/2x3/16	A36 (36 ksi)
T3 135.00-130.00	Pipe	P2.875"x0.203" (2.5 STD)	A500-50 (50 ksi)	Equal Angle	L1 1/2x1 1/2x3/16	A36 (36 ksi)
T4 130.00-125.00	Pipe	P2.875"x0.203" (2.5 STD)	A500-50 (50 ksi)	Equal Angle	L1 1/2x1 1/2x1/4	A36 (36 ksi)
T5 125.00-120.00	Pipe	P2.875"x0.203" (2.5 STD)	A500-50 (50 ksi)	Equal Angle	L1 1/2x1 1/2x1/4	A36 (36 ksi)
T6 120.00-100.00	Pipe	Pipe 2.5 XStr (2.875"ODx0.276")	A500-50 (50 ksi)	Equal Angle	L2x2x1/4	A36 (36 ksi)
T7 100.00-80.00	Arbitrary Shape	2.875"x0.276" w/ 3.5"x.3" Sleeve (STAMFORD NW CT)	A500-50 (50 ksi)	Equal Angle	L2 1/2x2 1/2x1/4	A36 (36 ksi)
T8 80.00-73.33	Arbitrary Shape	3.5"x0.3" w/ 4"x.25" Sleeve (STAMFORD NW CT)	A500-50 (50 ksi)	Equal Angle	L2 1/2x2 1/2x1/4	A36 (36 ksi)
T9 73.33-66.67	Arbitrary Shape	3.5"x0.3" w/ 4"x.25" Sleeve (STAMFORD NW CT)	A500-50 (50 ksi)	Equal Angle	L2 1/2x2 1/2x5/16	A36 (36 ksi)
T10 66.67-60.00	Arbitrary Shape	3.5"x0.3" w/ 4"x.25" Sleeve (STAMFORD NW CT)	A500-50 (50 ksi)	Equal Angle	L2 1/2x2 1/2x5/16	A36 (36 ksi)
T11 60.00-50.00	Pipe	Pipe 4 XStr (4.5"ODx0.337")	A500-50 (50 ksi)	Equal Angle	L3x3x1/4	A36 (36 ksi)
T12 50.00-40.00	Pipe	Pipe 4 XStr (4.5"ODx0.337")	A500-50 (50 ksi)	Equal Angle	L3x3x5/16	A36 (36 ksi)
T13 40.00-30.00	Arbitrary Shape	4.5"x0.337" w/ 5"x.25" Sleeve (STAMFORD NW CT 30'-40')	A500-50 (50 ksi)	Equal Angle	L3x3x3/8	A36 (36 ksi)
T14 30.00-20.00	Arbitrary Shape	4.5"x0.337" w/ 5"x.25" Sleeve (STAMFORD NW CT 20'-30')	A500-50 (50 ksi)	Equal Angle	L3x3x5/16	A36 (36 ksi)
T15 20.00-15.00	Arbitrary Shape	5.5"x0.259" w/ 6"x.25" Sleeve (STAMFORD NW CT 15'-20')	A500-50 (50 ksi)	Equal Angle	L3 1/2x3 1/2x1/4	A36 (36 ksi)
T16 15.00-10.00	Arbitrary Shape	5.5"x0.259" w/ (3) 1.5"x.5" Bars (STAMFORD NW CT 0'-15')	A500-50 (50 ksi)	Equal Angle	L3 1/2x3 1/2x1/4	A36 (36 ksi)

tnxTower Centerline Engineering Services, PA 750 W Center St, Suite 301 West Bridgewater, MA 02379 Phone: (781) 713-4725 FAX:	Job	Stamford NW CT	Page	4 of 52
	Project	23CLVZ-0009	Date	15:14:50 09/21/23
	Client	Verizon Wireless	Designed by	jboegel

Tower Elevation ft	Leg Type	Leg Size	Leg Grade	Diagonal Type	Diagonal Size	Diagonal Grade
T17 10.00-0.00	Arbitrary Shape	5.5"x0.259" w/ (3) 1.5"x.5" Bars (STAMFORD NW CT 0'-15')	A500-50 (50 ksi)	Equal Angle	L3 1/2x3 1/2x5/16	A36 (36 ksi)

Tower Section Geometry (cont'd)

Tower Elevation ft	Top Girt Type	Top Girt Size	Top Girt Grade	Bottom Girt Type	Bottom Girt Size	Bottom Girt Grade
T1 152.00-140.00	Equal Angle	L2x2x1/8	A36 (36 ksi)	Solid Round		A36 (36 ksi)
T2 140.00-135.00	Equal Angle	L2x2x1/8	A36 (36 ksi)	Solid Round		A36 (36 ksi)

Tower Section Geometry (cont'd)

Tower Elevation ft	No. of Mid Girts	Mid Girt Type	Mid Girt Size	Mid Girt Grade	Horizontal Type	Horizontal Size	Horizontal Grade
T14 30.00-20.00	None	Flat Bar		A36 (36 ksi)	Equal Angle	L3x3x1/4	A36 (36 ksi)
T15 20.00-15.00	None	Flat Bar		A36 (36 ksi)	Equal Angle	L3x3x1/4	A36 (36 ksi)
T16 15.00-10.00	None	Flat Bar		A36 (36 ksi)	Equal Angle	L3x3x1/4	A36 (36 ksi)

Tower Section Geometry (cont'd)

Tower Elevation ft	Secondary Horizontal Type	Secondary Horizontal Size	Secondary Horizontal Grade	Inner Bracing Type	Inner Bracing Size	Inner Bracing Grade
T7 100.00-80.00	Equal Angle	L2 1/2x2 1/2x1/4	A36 (36 ksi)	Solid Round		A572-50 (50 ksi)
T8 80.00-73.33	Equal Angle	L2 1/2x2 1/2x1/4	A36 (36 ksi)	Solid Round		A572-50 (50 ksi)
T9 73.33-66.67	Equal Angle	L2 1/2x2 1/2x1/4	A36 (36 ksi)	Solid Round		A572-50 (50 ksi)
T10 66.67-60.00	Equal Angle	L2 1/2x2 1/2x1/4	A36 (36 ksi)	Solid Round		A572-50 (50 ksi)
T11 60.00-50.00	Equal Angle	L2 1/2x2 1/2x1/4	A36 (36 ksi)	Solid Round		A572-50 (50 ksi)
T12 50.00-40.00	Equal Angle	L3x3x1/4	A36 (36 ksi)	Solid Round		A572-50 (50 ksi)
T13 40.00-30.00	Equal Angle	L3x3x1/4	A36 (36 ksi)	Solid Round		A572-50 (50 ksi)

tnxTower Centerline Engineering Services, PA 750 W Center St, Suite 301 West Bridgewater, MA 02379 Phone: (781) 713-4725 FAX:	Job	Stamford NW CT	Page	5 of 52
	Project	23CLVZ-0009	Date	15:14:50 09/21/23
	Client	Verizon Wireless	Designed by	jboegel

Tower Section Geometry (cont'd)

Tower Elevation ft	Redundant Bracing Grade	Redundant Type	Redundant Size	K Factor
T14 30.00-20.00	A36 (36 ksi)	Horizontal (1) Diagonal (1)	Equal Angle L2x2x1/4	1
T15 20.00-15.00	A36 (36 ksi)	Horizontal (1) Diagonal (1)	Equal Angle L2x2x1/4	1

Tower Section Geometry (cont'd)

Tower Elevation ft	Gusset Area (per face) ft ²	Gusset Thickness in	Gusset Grade	Adjust. Factor A_f	Adjust. Factor A_r	Weight Mult.	Double Angle Stitch Bolt Spacing Diagonals in	Double Angle Stitch Bolt Spacing Horizontals in	Double Angle Stitch Bolt Spacing Redundants in
T1 152.00-140.00	0.00	0.1875	A36 (36 ksi)	1	1	1.05	36.0000	36.0000	36.0000
T2 140.00-135.00	0.00	0.1875	A36 (36 ksi)	1	1	1.05	36.0000	36.0000	36.0000
T3 135.00-130.00	0.00	0.2500	A36 (36 ksi)	1	1	1.05	36.0000	36.0000	36.0000
T4 130.00-125.00	0.00	0.2500	A36 (36 ksi)	1	1	1.05	36.0000	36.0000	36.0000
T5 125.00-120.00	0.00	0.2500	A36 (36 ksi)	1	1	1.05	36.0000	36.0000	36.0000
T6 120.00-100.00	0.00	0.2500	A36 (36 ksi)	1	1	1.05	36.0000	36.0000	36.0000
T7 100.00-80.00	0.00	0.2500	A36 (36 ksi)	1	1	1.05	36.0000	36.0000	36.0000
T8 80.00-73.33	0.00	0.2500	A36 (36 ksi)	1	1	1.05	36.0000	36.0000	36.0000
T9 73.33-66.67	0.00	0.2500	A36 (36 ksi)	1	1	1.05	36.0000	36.0000	36.0000
T10 66.67-60.00	0.00	0.2500	A36 (36 ksi)	1	1	1.05	36.0000	36.0000	36.0000
T11 60.00-50.00	0.00	0.2500	A36 (36 ksi)	1	1	1.05	36.0000	36.0000	36.0000
T12 50.00-40.00	0.00	0.2500	A36 (36 ksi)	1	1	1.05	36.0000	36.0000	36.0000
T13 40.00-30.00	0.00	0.2500	A36 (36 ksi)	1	1	1.05	36.0000	36.0000	36.0000
T14 30.00-20.00	0.00	0.2500	A36 (36 ksi)	1	1	1.05	36.0000	36.0000	36.0000
T15 20.00-15.00	0.00	0.2500	A36 (36 ksi)	1	1	1.05	36.0000	36.0000	36.0000
T16 15.00-10.00	0.00	0.2500	A36 (36 ksi)	1	1	1.05	36.0000	36.0000	36.0000
T17 10.00-0.00	0.00	0.2500	A36 (36 ksi)	1	1	1.05	36.0000	36.0000	36.0000

Page 6 of 52
Date 15:14:50 09/21/23
Designed by jboegel

egs	<i>K Factors</i> ¹						
	<i>X</i> <i>Brace</i> <i>Diags</i>	<i>K</i> <i>Brace</i> <i>Diags</i>	<i>Single</i> <i>Diags</i>	<i>Girts</i>	<i>Horiz.</i>	<i>Sec.</i> <i>Horiz.</i>	<i>Inner</i> <i>Brace</i>
	<i>X</i> <i>Y</i>	<i>X</i> <i>Y</i>	<i>X</i> <i>Y</i>	<i>X</i> <i>Y</i>	<i>X</i> <i>Y</i>	<i>X</i> <i>Y</i>	<i>X</i> <i>Y</i>
1	1	1	1	1	1	1	1
	1	1	1	1	1	1	1
1	1	1	1	1	1	1	1
	1	1	1	1	1	1	1
1	1	1	1	1	1	1	1
	1	1	1	1	1	1	1
1	1	1	1	1	1	1	1
	1	1	1	1	1	1	1
1	1	1	1	1	1	1	1
	1	1	1	1	1	1	1
1	1	1	1	1	1	1	1
	1	1	1	1	1	1	1
1	1	1	1	1	1	0.5	1
	1	1	1	1	1	1	1
1	1	1	1	1	1	0.5	1
	1	1	1	1	1	1	1
1	1	1	1	1	1	0.5	1
	1	1	1	1	1	1	1
1	1	1	1	1	1	0.5	1
	1	1	1	1	1	1	1
1	1	1	1	1	1	1	1
	1	1	1	1	1	0.5	1
1	1	1	1	1	1	1	1
	1	1	1	1	0.5	1	1
4	1	1	1	1	1	1	1
	1	1	1	1	1	1	1
2	1	1	1	1	1	1	1
	1	1	1	1	1	1	1
1	1	1	1	1	1	1	1
	1	1	1	1	1	1	1

[illegible]

tnxTower Centerline Engineering Services, PA 750 W Center St, Suite 301 West Bridgewater, MA 02379 Phone: (781) 713-4725 FAX:	Job	Stamford NW CT	Page 8 of 52
	Project	23CLVZ-0009	Date 15:14:50 09/21/23
	Client	Verizon Wireless	Designed by jboegel

Tower Elevation ft	Redundant Horizontal		Redundant Diagonal		Redundant Sub-Diagonal		Redundant Sub-Horizontal		Redundant Vertical		Redundant Hip		Redundant Hip Diagonal	
	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U
T12 50.00-40.00	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75
T13 40.00-30.00	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75
T14 30.00-20.00	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75
T15 20.00-15.00	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75
T16 15.00-10.00	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75
T17 10.00-0.00	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75

Tower Section Geometry (cont'd)

Tower Elevation ft	Leg Connection Type	Leg		Diagonal		Top Girt		Bottom Girt		Mid Girt		Long Horizontal		Short Horizontal	
		Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.
T1 152.00-140.00	Flange	0.6250	4	0.5000	1	0.5000	1	0.6250	0	0.6250	0	0.6250	0	0.6250	0
T2 140.00-135.00	Flange	0.7500	0	0.5000	1	0.5000	1	0.6250	0	0.6250	0	0.6250	0	0.6250	0
T3 135.00-130.00	Flange	0.7500	0	0.5000	1	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
T4 130.00-125.00	Flange	0.7500	0	0.5000	1	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
T5 125.00-120.00	Flange	0.6250	4	0.5000	1	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
T6 120.00-100.00	Flange	0.7500	4	0.5000	1	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
T7 100.00-80.00	Flange	0.8750	4	0.5000	1	0.6250	0	0.6250	0	0.6250	0	0.5000	0	0.5000	2
T8 80.00-73.33	Flange	0.7500	0	0.5000	1	0.6250	0	0.6250	0	0.6250	0	0.5000	0	0.5000	2
T9 73.33-66.67	Flange	0.7500	0	0.5000	1	0.6250	0	0.6250	0	0.6250	0	0.5000	0	0.5000	2
T10 66.67-60.00	Flange	0.8750	4	0.5000	1	0.6250	0	0.6250	0	0.6250	0	0.5000	0	0.5000	2
T11 60.00-50.00	Flange	0.7500	0	0.6250	1	0.6250	0	0.6250	0	0.6250	0	0.5000	0	0.5000	2
T12 50.00-40.00	Flange	1.0000	4	0.6250	1	0.6250	0	0.6250	0	0.6250	0	0.5000	0	0.5000	2
T13 40.00-30.00	Flange	0.7500	0	0.6250	1	0.6250	0	0.6250	0	0.6250	0	0.5000	0	0.5000	2
T14 30.00-20.00	Flange	1.0000	4	0.6250	1	0.6250	0	0.6250	0	0.6250	0	0.5000	2	0.6250	0
T15 20.00-15.00	Flange	0.7500	0	0.6250	1	0.6250	0	0.6250	0	0.6250	0	0.6250	1	0.6250	0
T16 15.00-10.00	Flange	0.7500	0	0.6250	1	0.6250	0	0.6250	0	0.6250	0	0.6250	1	0.6250	0

inxTower Centerline Engineering Services, PA 750 W Center St, Suite 301 West Bridgewater, MA 02379 Phone: (781) 713-4725 FAX:	Job	Stamford NW CT	Page	9 of 52
	Project	23CLVZ-0009	Date	15:14:50 09/21/23
	Client	Verizon Wireless	Designed by	jboegel

Tower Elevation ft	Leg Connection Type	Leg		Diagonal		Top Girt		Bottom Girt		Mid Girt		Long Horizontal		Short Horizontal	
		Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.
T17 10.00-0.00	Flange	0.7500 A325N	0	0.6250 A325X	1	0.6250 A325N	0	0.6250 A325N	0	0.6250 A325N	0	0.5000 A325N	0	0.6250 A325N	0

Feed Line/Linear Appurtenances - Entered As Round Or Flat

Description	Face or Leg	Allow Shield	Exclude From Torque Calculation	Component Type	Placement ft	Face Offset in	Lateral Offset (Frac FW)	#	# Per Row	Clear Spacing in	Width or Diameter in	Perimeter in	Weight plf
LDF5-50A(7/8")	A	No	No	Ar (CaAa)	152.00 - 0.00	0.0000	-0.05	1	1	1.0900	1.0900		0.33
LDF4-50A(1/2")	A	No	No	Ar (CaAa)	150.00 - 0.00	0.0000	-0.03	1	1	0.6300	0.6300		0.15
Feedline Ladder (Af) ***	A	No	No	Af (CaAa)	150.00 - 0.00	0.0000	0	2	2	24.5000 0.5000	1.5000		1.80
LDF7-50A(1 5/8")	B	No	No	Ar (CaAa)	145.00 - 0.00	0.0000	0	12	12	0.5000	1.9800		0.82
Feedline Ladder (Af) ***	B	No	No	Af (CaAa)	145.00 - 0.00	0.0000	0	2	2	24.5000 0.5000	1.5000		1.80
EW180(ELLIPTICAL)	B	No	No	Ar (CaAa)	152.00 - 0.00	0.0000	0.25	1	1	0.7800	0.7800		0.15
EW180(ELLIPTICAL)	B	No	No	Ar (CaAa)	140.00 - 0.00	0.0000	0.22	1	1	0.7800	0.7800		0.15
LDF7-50A(1 5/8")	B	No	No	Ar (CaAa)	135.00 - 0.00	0.0000	0.2	2	2	0.5000	1.9800		0.82
LDF7-50A(1 5/8")	B	No	No	Ar (CaAa)	98.00 - 0.00	0.0000	0.18	3	3	0.5000	1.9800		0.82
LDF5-50A(7/8")	B	No	No	Ar (CaAa)	78.00 - 0.00	0.0000	0.15	1	1	0.5000	1.0900		0.33
Feedline Ladder (Af) ***	B	No	No	Af (CaAa)	152.00 - 0.00	0.0000	0.2	2	2	24.5000 0.5000	1.5000		1.80
LDF6-50A(1 1/4")	C	No	No	Ar (CaAa)	131.00 - 0.00	0.0000	0.25	3	3	1.5500	1.5500		0.66
LDF5-50A(7/8")	C	No	No	Ar (CaAa)	131.00 - 0.00	0.0000	0.23	1	1	1.0900	1.0900		0.33
LDF4P-50A(1/2")	C	No	No	Ar (CaAa)	58.00 - 0.00	0.0000	0.27	1	1	0.6300	0.6300		0.15
LDF7-50A(1 1/2")	C	No	No	Ar (CaAa)	115.00 - 0.00	0.0000	0.17	4	4	0.5000	1.5000		0.82
Feedline Ladder (Af) ***	C	No	No	Af (CaAa)	152.00 - 0.00	0.0000	0.2	2	2	24.5000 0.5000	1.5000		1.80

Feed Line/Linear Appurtenances - Entered As Area

tnxTower Centerline Engineering Services, PA 750 W Center St, Suite 301 West Bridgewater, MA 02379 Phone: (781) 713-4725 FAX:	Job	Stamford NW CT	Page	10 of 52
	Project	23CLVZ-0009	Date	15:14:50 09/21/23
	Client	Verizon Wireless	Designed by	jboegel

Description	Face or Leg	Allow Shield	Exclude From Torque Calculation	Component Type	Placement ft	Total Number	C _A A _A ft ² /ft	Weight plf

Feed Line/Linear Appurtenances Section Areas

Tower Section	Tower Elevation ft	Face	A _R ft ²	A _F ft ²	C _A A _A In Face ft ²	C _A A _A Out Face ft ²	Weight K
T1	152.00-140.00	A	0.000	0.000	6.938	0.000	0.04
		B	0.000	0.000	21.316	0.000	0.11
		C	0.000	0.000	6.000	0.000	0.04
T2	140.00-135.00	A	0.000	0.000	3.360	0.000	0.02
		B	0.000	0.000	17.660	0.000	0.09
		C	0.000	0.000	2.500	0.000	0.02
T3	135.00-130.00	A	0.000	0.000	3.360	0.000	0.02
		B	0.000	0.000	19.640	0.000	0.09
		C	0.000	0.000	3.074	0.000	0.02
T4	130.00-125.00	A	0.000	0.000	3.360	0.000	0.02
		B	0.000	0.000	19.640	0.000	0.09
		C	0.000	0.000	5.370	0.000	0.03
T5	125.00-120.00	A	0.000	0.000	3.360	0.000	0.02
		B	0.000	0.000	19.640	0.000	0.09
		C	0.000	0.000	5.370	0.000	0.03
T6	120.00-100.00	A	0.000	0.000	13.440	0.000	0.08
		B	0.000	0.000	78.560	0.000	0.38
		C	0.000	0.000	30.480	0.000	0.17
T7	100.00-80.00	A	0.000	0.000	13.440	0.000	0.08
		B	0.000	0.000	89.252	0.000	0.42
		C	0.000	0.000	33.480	0.000	0.18
T8	80.00-73.33	A	0.000	0.000	4.480	0.000	0.03
		B	0.000	0.000	30.655	0.000	0.14
		C	0.000	0.000	11.160	0.000	0.06
T9	73.33-66.67	A	0.000	0.000	4.480	0.000	0.03
		B	0.000	0.000	30.873	0.000	0.15
		C	0.000	0.000	11.160	0.000	0.06
T10	66.67-60.00	A	0.000	0.000	4.480	0.000	0.03
		B	0.000	0.000	30.873	0.000	0.15
		C	0.000	0.000	11.160	0.000	0.06
T11	60.00-50.00	A	0.000	0.000	6.720	0.000	0.04
		B	0.000	0.000	46.310	0.000	0.22
		C	0.000	0.000	17.244	0.000	0.09
T12	50.00-40.00	A	0.000	0.000	6.720	0.000	0.04
		B	0.000	0.000	46.310	0.000	0.22
		C	0.000	0.000	17.370	0.000	0.09
T13	40.00-30.00	A	0.000	0.000	6.720	0.000	0.04
		B	0.000	0.000	46.310	0.000	0.22
		C	0.000	0.000	17.370	0.000	0.09
T14	30.00-20.00	A	0.000	0.000	6.720	0.000	0.04
		B	0.000	0.000	46.310	0.000	0.22
		C	0.000	0.000	17.370	0.000	0.09
T15	20.00-15.00	A	0.000	0.000	3.360	0.000	0.02
		B	0.000	0.000	23.155	0.000	0.11
		C	0.000	0.000	8.685	0.000	0.05
T16	15.00-10.00	A	0.000	0.000	3.360	0.000	0.02
		B	0.000	0.000	23.155	0.000	0.11

tnxTower Centerline Engineering Services, PA 750 W Center St, Suite 301 West Bridgewater, MA 02379 Phone: (781) 713-4725 FAX:	Job	Stamford NW CT	Page	11 of 52
	Project	23CLVZ-0009	Date	15:14:50 09/21/23
	Client	Verizon Wireless	Designed by	jboegel

Tower Section	Tower Elevation ft	Face	A _R ft ²	A _F ft ²	C _A A _A In Face ft ²	C _A A _A Out Face ft ²	Weight K
T17	10.00-0.00	C	0.000	0.000	8.685	0.000	0.05
		A	0.000	0.000	6.720	0.000	0.04
		B	0.000	0.000	46.310	0.000	0.22
		C	0.000	0.000	17.370	0.000	0.09

Feed Line/Linear Appurtenances Section Areas - With Ice

Tower Section	Tower Elevation ft	Face or Leg	Ice Thickness in	A _R ft ²	A _F ft ²	C _A A _A In Face ft ²	C _A A _A Out Face ft ²	Weight K
T1	152.00-140.00	A	0.986	0.000	0.000	15.223	0.000	0.15
		B		0.000	0.000	38.186	0.000	0.39
		C		0.000	0.000	10.734	0.000	0.11
T2	140.00-135.00	A	0.980	0.000	0.000	7.282	0.000	0.07
		B		0.000	0.000	31.330	0.000	0.32
		C		0.000	0.000	4.461	0.000	0.05
T3	135.00-130.00	A	0.977	0.000	0.000	7.267	0.000	0.07
		B		0.000	0.000	36.006	0.000	0.36
		C		0.000	0.000	6.047	0.000	0.06
T4	130.00-125.00	A	0.973	0.000	0.000	7.252	0.000	0.07
		B		0.000	0.000	35.971	0.000	0.36
		C		0.000	0.000	12.406	0.000	0.12
T5	125.00-120.00	A	0.969	0.000	0.000	7.237	0.000	0.07
		B		0.000	0.000	35.936	0.000	0.36
		C		0.000	0.000	12.388	0.000	0.12
T6	120.00-100.00	A	0.959	0.000	0.000	28.780	0.000	0.27
		B		0.000	0.000	143.366	0.000	1.43
		C		0.000	0.000	68.146	0.000	0.65
T7	100.00-80.00	A	0.940	0.000	0.000	28.475	0.000	0.27
		B		0.000	0.000	164.332	0.000	1.60
		C		0.000	0.000	73.935	0.000	0.70
T8	80.00-73.33	A	0.925	0.000	0.000	9.412	0.000	0.09
		B		0.000	0.000	56.737	0.000	0.55
		C		0.000	0.000	24.522	0.000	0.23
T9	73.33-66.67	A	0.916	0.000	0.000	9.367	0.000	0.09
		B		0.000	0.000	57.194	0.000	0.55
		C		0.000	0.000	24.452	0.000	0.23
T10	66.67-60.00	A	0.907	0.000	0.000	9.319	0.000	0.09
		B		0.000	0.000	57.051	0.000	0.54
		C		0.000	0.000	24.377	0.000	0.23
T11	60.00-50.00	A	0.895	0.000	0.000	13.876	0.000	0.13
		B		0.000	0.000	85.277	0.000	0.81
		C		0.000	0.000	38.344	0.000	0.35
T12	50.00-40.00	A	0.877	0.000	0.000	13.734	0.000	0.12
		B		0.000	0.000	84.860	0.000	0.80
		C		0.000	0.000	38.572	0.000	0.35
T13	40.00-30.00	A	0.855	0.000	0.000	13.560	0.000	0.12
		B		0.000	0.000	84.348	0.000	0.78
		C		0.000	0.000	38.259	0.000	0.34
T14	30.00-20.00	A	0.827	0.000	0.000	13.334	0.000	0.12
		B		0.000	0.000	83.684	0.000	0.76
		C		0.000	0.000	37.853	0.000	0.33
T15	20.00-15.00	A	0.798	0.000	0.000	6.551	0.000	0.06
		B		0.000	0.000	41.502	0.000	0.37
		C		0.000	0.000	18.719	0.000	0.16
T16	15.00-10.00	A	0.771	0.000	0.000	6.445	0.000	0.06
		B		0.000	0.000	41.192	0.000	0.36
		C		0.000	0.000	17.048	0.000	0.15

tnxTower Centerline Engineering Services, PA 750 W Center St, Suite 301 West Bridgewater, MA 02379 Phone: (781) 713-4725 FAX:	Job	Stamford NW CT	Page 12 of 52
	Project	23CLVZ-0009	Date 15:14:50 09/21/23
	Client	Verizon Wireless	Designed by jboegel

Tower Section	Tower Elevation ft	Face or Leg	Ice Thickness in	A _R ft ²	A _F ft ²	C _A A _A In Face ft ²	C _A A _A Out Face ft ²	Weight K
T17	10.00-0.00	A	0.704	0.000	0.000	12.351	0.000	0.10
		B		0.000	0.000	80.801	0.000	0.69
		C		0.000	0.000	32.936	0.000	0.28

Feed Line Center of Pressure

Section	Elevation ft	CP _X in	CP _Z in	CP _X Ice in	CP _Z Ice in
T1	152.00-140.00	1.6869	-3.1968	1.2010	-2.3809
T2	140.00-135.00	4.0561	-5.0691	3.6574	-4.1573
T3	135.00-130.00	5.5855	-5.2251	4.8515	-3.9890
T4	130.00-125.00	4.1661	-4.5075	2.5474	-2.8061
T5	125.00-120.00	4.3545	-4.7247	2.6631	-2.9443
T6	120.00-100.00	3.4413	-4.5091	1.5783	-2.4507
T7	100.00-80.00	4.2111	-3.8694	2.6345	-2.0910
T8	80.00-73.33	4.8289	-4.0356	3.4439	-2.2328
T9	73.33-66.67	5.0746	-4.1490	3.7534	-2.3168
T10	66.67-60.00	5.2014	-4.2625	3.8501	-2.4000
T11	60.00-50.00	5.4990	-4.4093	3.6944	-2.0863
T12	50.00-40.00	5.5417	-4.4513	3.6592	-2.0544
T13	40.00-30.00	5.6964	-4.5853	3.7662	-2.1799
T14	30.00-20.00	5.0251	-4.1237	3.3825	-2.0530
T15	20.00-15.00	5.4110	-4.4111	3.5948	-2.2621
T16	15.00-10.00	4.4284	-3.7550	3.6748	-2.1154
T17	10.00-0.00	5.4789	-4.5889	4.4414	-2.7233

Shielding Factor Ka

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K _a No Ice	K _a Ice
T1	1	LDF5-50A(7/8")	140.00 -	0.6000	0.6000
			152.00		
T1	2	LDF4-50A(1/2")	140.00 -	0.6000	0.6000
			150.00		
T1	3	Feedline Ladder (Af)	140.00 -	0.6000	0.6000
			150.00		
T1	5	LDF7-50A(1 5/8")	140.00 -	0.6000	0.6000
			145.00		
T1	6	Feedline Ladder (Af)	140.00 -	0.6000	0.6000
			145.00		
T1	8	EW180(ELLIPTICAL)	140.00 -	0.6000	0.6000
			152.00		
T1	13	Feedline Ladder (Af)	140.00 -	0.6000	0.6000
			152.00		
T1	19	Feedline Ladder (Af)	140.00 -	0.6000	0.6000
			152.00		
T2	1	LDF5-50A(7/8")	135.00 -	0.6000	0.6000
			140.00		
T2	2	LDF4-50A(1/2")	135.00 -	0.6000	0.6000
			140.00		

tnxTower Centerline Engineering Services, PA 750 W Center St, Suite 301 West Bridgewater, MA 02379 Phone: (781) 713-4725 FAX:	Job	Stamford NW CT	Page	13 of 52
	Project	23CLVZ-0009	Date	15:14:50 09/21/23
	Client	Verizon Wireless	Designed by	jboegel

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K _a No Ice	K _a Ice
T2	3	Feedline Ladder (Af)	135.00 - 140.00	0.6000	0.6000
T2	5	LDF7-50A(1 5/8")	135.00 - 140.00	0.6000	0.6000
T2	6	Feedline Ladder (Af)	135.00 - 140.00	0.6000	0.6000
T2	8	EW180(ELLIPTICAL)	135.00 - 140.00	0.6000	0.6000
T2	9	EW180(ELLIPTICAL)	135.00 - 140.00	0.6000	0.6000
T2	13	Feedline Ladder (Af)	135.00 - 140.00	0.6000	0.6000
T2	19	Feedline Ladder (Af)	135.00 - 140.00	0.6000	0.6000
T3	1	LDF5-50A(7/8")	130.00 - 135.00	0.6000	0.6000
T3	2	LDF4-50A(1/2")	130.00 - 135.00	0.6000	0.6000
T3	3	Feedline Ladder (Af)	130.00 - 135.00	0.6000	0.6000
T3	5	LDF7-50A(1 5/8")	130.00 - 135.00	0.6000	0.6000
T3	6	Feedline Ladder (Af)	130.00 - 135.00	0.6000	0.6000
T3	8	EW180(ELLIPTICAL)	130.00 - 135.00	0.6000	0.6000
T3	9	EW180(ELLIPTICAL)	130.00 - 135.00	0.6000	0.6000
T3	10	LDF7-50A(1 5/8")	130.00 - 135.00	0.6000	0.6000
T3	13	Feedline Ladder (Af)	130.00 - 135.00	0.6000	0.6000
T3	15	LDF6-50A(1 1/4")	130.00 - 131.00	0.6000	0.6000
T3	16	LDF5-50A(7/8")	130.00 - 131.00	0.6000	0.6000
T3	19	Feedline Ladder (Af)	130.00 - 135.00	0.6000	0.6000
T4	1	LDF5-50A(7/8")	125.00 - 130.00	0.6000	0.6000
T4	2	LDF4-50A(1/2")	125.00 - 130.00	0.6000	0.6000
T4	3	Feedline Ladder (Af)	125.00 - 130.00	0.6000	0.6000
T4	5	LDF7-50A(1 5/8")	125.00 - 130.00	0.6000	0.6000
T4	6	Feedline Ladder (Af)	125.00 - 130.00	0.6000	0.6000
T4	8	EW180(ELLIPTICAL)	125.00 - 130.00	0.6000	0.6000
T4	9	EW180(ELLIPTICAL)	125.00 - 130.00	0.6000	0.6000
T4	10	LDF7-50A(1 5/8")	125.00 - 130.00	0.6000	0.6000
T4	13	Feedline Ladder (Af)	125.00 - 130.00	0.6000	0.6000
T4	15	LDF6-50A(1 1/4")	125.00 - 130.00	0.6000	0.6000
T4	16	LDF5-50A(7/8")	125.00 - 130.00	0.6000	0.6000
T4	19	Feedline Ladder (Af)	125.00 - 130.00	0.6000	0.6000

tnxTower Centerline Engineering Services, PA 750 W Center St, Suite 301 West Bridgewater, MA 02379 Phone: (781) 713-4725 FAX:	Job	Stamford NW CT	Page 14 of 52
	Project	23CLVZ-0009	Date 15:14:50 09/21/23
	Client	Verizon Wireless	Designed by jboegel

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K _a No Ice	K _a Ice
T5	1	LDF5-50A(7/8")	120.00 - 125.00	0.6000	0.6000
T5	2	LDF4-50A(1/2")	120.00 - 125.00	0.6000	0.6000
T5	3	Feedline Ladder (Af)	120.00 - 125.00	0.6000	0.6000
T5	5	LDF7-50A(1 5/8")	120.00 - 125.00	0.6000	0.6000
T5	6	Feedline Ladder (Af)	120.00 - 125.00	0.6000	0.6000
T5	8	EW180(ELLIPTICAL)	120.00 - 125.00	0.6000	0.6000
T5	9	EW180(ELLIPTICAL)	120.00 - 125.00	0.6000	0.6000
T5	10	LDF7-50A(1 5/8")	120.00 - 125.00	0.6000	0.6000
T5	13	Feedline Ladder (Af)	120.00 - 125.00	0.6000	0.6000
T5	15	LDF6-50A(1 1/4")	120.00 - 125.00	0.6000	0.6000
T5	16	LDF5-50A(7/8")	120.00 - 125.00	0.6000	0.6000
T5	19	Feedline Ladder (Af)	120.00 - 125.00	0.6000	0.6000
T6	1	LDF5-50A(7/8")	100.00 - 120.00	0.6000	0.6000
T6	2	LDF4-50A(1/2")	100.00 - 120.00	0.6000	0.6000
T6	3	Feedline Ladder (Af)	100.00 - 120.00	0.6000	0.6000
T6	5	LDF7-50A(1 5/8")	100.00 - 120.00	0.6000	0.6000
T6	6	Feedline Ladder (Af)	100.00 - 120.00	0.6000	0.6000
T6	8	EW180(ELLIPTICAL)	100.00 - 120.00	0.6000	0.6000
T6	9	EW180(ELLIPTICAL)	100.00 - 120.00	0.6000	0.6000
T6	10	LDF7-50A(1 5/8")	100.00 - 120.00	0.6000	0.6000
T6	13	Feedline Ladder (Af)	100.00 - 120.00	0.6000	0.6000
T6	15	LDF6-50A(1 1/4")	100.00 - 120.00	0.6000	0.6000
T6	16	LDF5-50A(7/8")	100.00 - 120.00	0.6000	0.6000
T6	18	LDF7-50A(1 1/2")	100.00 - 115.00	0.6000	0.6000
T6	19	Feedline Ladder (Af)	100.00 - 120.00	0.6000	0.6000
T7	1	LDF5-50A(7/8")	80.00 - 100.00	0.6000	0.6000
T7	2	LDF4-50A(1/2")	80.00 - 100.00	0.6000	0.6000
T7	3	Feedline Ladder (Af)	80.00 - 100.00	0.6000	0.6000
T7	5	LDF7-50A(1 5/8")	80.00 - 100.00	0.6000	0.6000
T7	6	Feedline Ladder (Af)	80.00 - 100.00	0.6000	0.6000
T7	8	EW180(ELLIPTICAL)	80.00 - 100.00	0.6000	0.6000
T7	9	EW180(ELLIPTICAL)	80.00 - 100.00	0.6000	0.6000
T7	10	LDF7-50A(1 5/8")	80.00 - 100.00	0.6000	0.6000
T7	11	LDF7-50A(1 5/8")	80.00 - 98.00	0.6000	0.6000
T7	13	Feedline Ladder (Af)	80.00 - 100.00	0.6000	0.6000
T7	15	LDF6-50A(1 1/4")	80.00 - 100.00	0.6000	0.6000
T7	16	LDF5-50A(7/8")	80.00 - 100.00	0.6000	0.6000

tnxTower Centerline Engineering Services, PA 750 W Center St, Suite 301 West Bridgewater, MA 02379 Phone: (781) 713-4725 FAX:	Job	Stamford NW CT	Page	15 of 52
	Project	23CLVZ-0009	Date	15:14:50 09/21/23
	Client	Verizon Wireless	Designed by	jboegel

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K _a No Ice	K _a Ice
T7	18	LDF7-50A(1 1/2")	80.00 - 100.00	0.6000	0.6000
T7	19	Feedline Ladder (Af)	80.00 - 100.00	0.6000	0.6000
T8	1	LDF5-50A(7/8")	73.33 - 80.00	0.6000	0.6000
T8	2	LDF4-50A(1/2")	73.33 - 80.00	0.6000	0.6000
T8	3	Feedline Ladder (Af)	73.33 - 80.00	0.6000	0.6000
T8	5	LDF7-50A(1 5/8")	73.33 - 80.00	0.6000	0.6000
T8	6	Feedline Ladder (Af)	73.33 - 80.00	0.6000	0.6000
T8	8	EW180(ELLIPTICAL)	73.33 - 80.00	0.6000	0.6000
T8	9	EW180(ELLIPTICAL)	73.33 - 80.00	0.6000	0.6000
T8	10	LDF7-50A(1 5/8")	73.33 - 80.00	0.6000	0.6000
T8	11	LDF7-50A(1 5/8")	73.33 - 80.00	0.6000	0.6000
T8	12	LDF5-50A(7/8")	73.33 - 78.00	0.6000	0.6000
T8	13	Feedline Ladder (Af)	73.33 - 80.00	0.6000	0.6000
T8	15	LDF6-50A(1 1/4")	73.33 - 80.00	0.6000	0.6000
T8	16	LDF5-50A(7/8")	73.33 - 80.00	0.6000	0.6000
T8	18	LDF7-50A(1 1/2")	73.33 - 80.00	0.6000	0.6000
T8	19	Feedline Ladder (Af)	73.33 - 80.00	0.6000	0.6000
T9	1	LDF5-50A(7/8")	66.67 - 73.33	0.6000	0.6000
T9	2	LDF4-50A(1/2")	66.67 - 73.33	0.6000	0.6000
T9	3	Feedline Ladder (Af)	66.67 - 73.33	0.6000	0.6000
T9	5	LDF7-50A(1 5/8")	66.67 - 73.33	0.6000	0.6000
T9	6	Feedline Ladder (Af)	66.67 - 73.33	0.6000	0.6000
T9	8	EW180(ELLIPTICAL)	66.67 - 73.33	0.6000	0.6000
T9	9	EW180(ELLIPTICAL)	66.67 - 73.33	0.6000	0.6000
T9	10	LDF7-50A(1 5/8")	66.67 - 73.33	0.6000	0.6000
T9	11	LDF7-50A(1 5/8")	66.67 - 73.33	0.6000	0.6000
T9	12	LDF5-50A(7/8")	66.67 - 73.33	0.6000	0.6000
T9	13	Feedline Ladder (Af)	66.67 - 73.33	0.6000	0.6000
T9	15	LDF6-50A(1 1/4")	66.67 - 73.33	0.6000	0.6000
T9	16	LDF5-50A(7/8")	66.67 - 73.33	0.6000	0.6000
T9	18	LDF7-50A(1 1/2")	66.67 - 73.33	0.6000	0.6000
T9	19	Feedline Ladder (Af)	66.67 - 73.33	0.6000	0.6000
T10	1	LDF5-50A(7/8")	60.00 - 66.67	0.6000	0.6000
T10	2	LDF4-50A(1/2")	60.00 - 66.67	0.6000	0.6000
T10	3	Feedline Ladder (Af)	60.00 - 66.67	0.6000	0.6000
T10	5	LDF7-50A(1 5/8")	60.00 - 66.67	0.6000	0.6000
T10	6	Feedline Ladder (Af)	60.00 - 66.67	0.6000	0.6000
T10	8	EW180(ELLIPTICAL)	60.00 - 66.67	0.6000	0.6000
T10	9	EW180(ELLIPTICAL)	60.00 - 66.67	0.6000	0.6000
T10	10	LDF7-50A(1 5/8")	60.00 - 66.67	0.6000	0.6000
T10	11	LDF7-50A(1 5/8")	60.00 - 66.67	0.6000	0.6000
T10	12	LDF5-50A(7/8")	60.00 - 66.67	0.6000	0.6000
T10	13	Feedline Ladder (Af)	60.00 - 66.67	0.6000	0.6000
T10	15	LDF6-50A(1 1/4")	60.00 - 66.67	0.6000	0.6000
T10	16	LDF5-50A(7/8")	60.00 - 66.67	0.6000	0.6000
T10	18	LDF7-50A(1 1/2")	60.00 - 66.67	0.6000	0.6000
T10	19	Feedline Ladder (Af)	60.00 - 66.67	0.6000	0.6000
T11	1	LDF5-50A(7/8")	50.00 - 60.00	0.6000	0.6000
T11	2	LDF4-50A(1/2")	50.00 - 60.00	0.6000	0.6000
T11	3	Feedline Ladder (Af)	50.00 - 60.00	0.6000	0.6000
T11	5	LDF7-50A(1 5/8")	50.00 - 60.00	0.6000	0.6000
T11	6	Feedline Ladder (Af)	50.00 - 60.00	0.6000	0.6000
T11	8	EW180(ELLIPTICAL)	50.00 - 60.00	0.6000	0.6000
T11	9	EW180(ELLIPTICAL)	50.00 - 60.00	0.6000	0.6000
T11	10	LDF7-50A(1 5/8")	50.00 - 60.00	0.6000	0.6000
T11	11	LDF7-50A(1 5/8")	50.00 - 60.00	0.6000	0.6000
T11	12	LDF5-50A(7/8")	50.00 - 60.00	0.6000	0.6000
T11	13	Feedline Ladder (Af)	50.00 - 60.00	0.6000	0.6000
T11	15	LDF6-50A(1 1/4")	50.00 - 60.00	0.6000	0.6000
T11	16	LDF5-50A(7/8")	50.00 - 60.00	0.6000	0.6000
T11	17	LDF4P-50A(1/2")	50.00 - 58.00	0.6000	0.6000
T11	18	LDF7-50A(1 1/2")	50.00 - 60.00	0.6000	0.6000

tnxTower Centerline Engineering Services, PA 750 W Center St, Suite 301 West Bridgewater, MA 02379 Phone: (781) 713-4725 FAX:	Job	Stamford NW CT	Page 16 of 52
	Project	23CLVZ-0009	Date 15:14:50 09/21/23
	Client	Verizon Wireless	Designed by jboegel

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K _a No Ice	K _a Ice
T11	19	Feedline Ladder (Af)	50.00 - 60.00	0.6000	0.6000
T12	1	LDF5-50A(7/8")	40.00 - 50.00	0.6000	0.6000
T12	2	LDF4-50A(1/2")	40.00 - 50.00	0.6000	0.6000
T12	3	Feedline Ladder (Af)	40.00 - 50.00	0.6000	0.6000
T12	5	LDF7-50A(1 5/8")	40.00 - 50.00	0.6000	0.6000
T12	6	Feedline Ladder (Af)	40.00 - 50.00	0.6000	0.6000
T12	8	EW180(ELLIPTICAL)	40.00 - 50.00	0.6000	0.6000
T12	9	EW180(ELLIPTICAL)	40.00 - 50.00	0.6000	0.6000
T12	10	LDF7-50A(1 5/8")	40.00 - 50.00	0.6000	0.6000
T12	11	LDF7-50A(1 5/8")	40.00 - 50.00	0.6000	0.6000
T12	12	LDF5-50A(7/8")	40.00 - 50.00	0.6000	0.6000
T12	13	Feedline Ladder (Af)	40.00 - 50.00	0.6000	0.6000
T12	15	LDF6-50A(1 1/4")	40.00 - 50.00	0.6000	0.6000
T12	16	LDF5-50A(7/8")	40.00 - 50.00	0.6000	0.6000
T12	17	LDF4P-50A(1/2")	40.00 - 50.00	0.6000	0.6000
T12	18	LDF7-50A(1 1/2")	40.00 - 50.00	0.6000	0.6000
T12	19	Feedline Ladder (Af)	40.00 - 50.00	0.6000	0.6000
T13	1	LDF5-50A(7/8")	30.00 - 40.00	0.6000	0.6000
T13	2	LDF4-50A(1/2")	30.00 - 40.00	0.6000	0.6000
T13	3	Feedline Ladder (Af)	30.00 - 40.00	0.6000	0.6000
T13	5	LDF7-50A(1 5/8")	30.00 - 40.00	0.6000	0.6000
T13	6	Feedline Ladder (Af)	30.00 - 40.00	0.6000	0.6000
T13	8	EW180(ELLIPTICAL)	30.00 - 40.00	0.6000	0.6000
T13	9	EW180(ELLIPTICAL)	30.00 - 40.00	0.6000	0.6000
T13	10	LDF7-50A(1 5/8")	30.00 - 40.00	0.6000	0.6000
T13	11	LDF7-50A(1 5/8")	30.00 - 40.00	0.6000	0.6000
T13	12	LDF5-50A(7/8")	30.00 - 40.00	0.6000	0.6000
T13	13	Feedline Ladder (Af)	30.00 - 40.00	0.6000	0.6000
T13	15	LDF6-50A(1 1/4")	30.00 - 40.00	0.6000	0.6000
T13	16	LDF5-50A(7/8")	30.00 - 40.00	0.6000	0.6000
T13	17	LDF4P-50A(1/2")	30.00 - 40.00	0.6000	0.6000
T13	18	LDF7-50A(1 1/2")	30.00 - 40.00	0.6000	0.6000
T13	19	Feedline Ladder (Af)	30.00 - 40.00	0.6000	0.6000
T14	1	LDF5-50A(7/8")	20.00 - 30.00	0.6000	0.6000
T14	2	LDF4-50A(1/2")	20.00 - 30.00	0.6000	0.6000
T14	3	Feedline Ladder (Af)	20.00 - 30.00	0.6000	0.6000
T14	5	LDF7-50A(1 5/8")	20.00 - 30.00	0.6000	0.6000
T14	6	Feedline Ladder (Af)	20.00 - 30.00	0.6000	0.6000
T14	8	EW180(ELLIPTICAL)	20.00 - 30.00	0.6000	0.6000
T14	9	EW180(ELLIPTICAL)	20.00 - 30.00	0.6000	0.6000
T14	10	LDF7-50A(1 5/8")	20.00 - 30.00	0.6000	0.6000
T14	11	LDF7-50A(1 5/8")	20.00 - 30.00	0.6000	0.6000
T14	12	LDF5-50A(7/8")	20.00 - 30.00	0.6000	0.6000
T14	13	Feedline Ladder (Af)	20.00 - 30.00	0.6000	0.6000
T14	15	LDF6-50A(1 1/4")	20.00 - 30.00	0.6000	0.6000
T14	16	LDF5-50A(7/8")	20.00 - 30.00	0.6000	0.6000
T14	17	LDF4P-50A(1/2")	20.00 - 30.00	0.6000	0.6000
T14	18	LDF7-50A(1 1/2")	20.00 - 30.00	0.6000	0.6000
T14	19	Feedline Ladder (Af)	20.00 - 30.00	0.6000	0.6000
T15	1	LDF5-50A(7/8")	15.00 - 20.00	0.6000	0.6000
T15	2	LDF4-50A(1/2")	15.00 - 20.00	0.6000	0.6000
T15	3	Feedline Ladder (Af)	15.00 - 20.00	0.6000	0.6000
T15	5	LDF7-50A(1 5/8")	15.00 - 20.00	0.6000	0.6000
T15	6	Feedline Ladder (Af)	15.00 - 20.00	0.6000	0.6000
T15	8	EW180(ELLIPTICAL)	15.00 - 20.00	0.6000	0.6000
T15	9	EW180(ELLIPTICAL)	15.00 - 20.00	0.6000	0.6000
T15	10	LDF7-50A(1 5/8")	15.00 - 20.00	0.6000	0.6000
T15	11	LDF7-50A(1 5/8")	15.00 - 20.00	0.6000	0.6000
T15	12	LDF5-50A(7/8")	15.00 - 20.00	0.6000	0.6000
T15	13	Feedline Ladder (Af)	15.00 - 20.00	0.6000	0.6000
T15	15	LDF6-50A(1 1/4")	15.00 - 20.00	0.6000	0.6000
T15	16	LDF5-50A(7/8")	15.00 - 20.00	0.6000	0.6000

tnxTower Centerline Engineering Services, PA 750 W Center St, Suite 301 West Bridgewater, MA 02379 Phone: (781) 713-4725 FAX:	Job	Stamford NW CT	Page	19 of 52
	Project	23CLVZ-0009	Date	15:14:50 09/21/23
	Client	Verizon Wireless	Designed by	jboegel

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment °	Placement ft		C _A A _A Front ft ²	C _A A _A Side ft ²	Weight K
APXVSPP18-C-A20 w/ Mount Pipe	A	From Leg	4.00 0.00 0.00	0.0000	131.00	No Ice 1/2" Ice 1" Ice	8.26 8.82 9.35	6.95 8.13 9.02	0.08 0.15 0.23
APXVSPP18-C-A20 w/ Mount Pipe	B	From Leg	4.00 0.00 0.00	0.0000	131.00	No Ice 1/2" Ice 1" Ice	8.26 8.82 9.35	6.95 8.13 9.02	0.08 0.15 0.23
APXVSPP18-C-A20 w/ Mount Pipe	C	From Leg	4.00 0.00 0.00	0.0000	131.00	No Ice 1/2" Ice 1" Ice	8.26 8.82 9.35	6.95 8.13 9.02	0.08 0.15 0.23
RRH2x50-WCS	A	From Leg	4.00 0.00 0.00	0.0000	131.00	No Ice 1/2" Ice 1" Ice	4.91 5.23 5.55	2.70 3.00 3.30	0.08 0.11 0.14
RRH2x50-WCS	B	From Leg	4.00 0.00 0.00	0.0000	131.00	No Ice 1/2" Ice 1" Ice	4.91 5.23 5.55	2.70 3.00 3.30	0.08 0.11 0.14
RRH2x50-WCS	C	From Leg	4.00 0.00 0.00	0.0000	131.00	No Ice 1/2" Ice 1" Ice	4.91 5.23 5.55	2.70 3.00 3.30	0.08 0.11 0.14
RRH4X45-19	A	From Leg	4.00 0.00 0.00	0.0000	131.00	No Ice 1/2" Ice 1" Ice	2.31 2.52 2.73	2.38 2.58 2.79	0.06 0.08 0.11
RRH4X45-19	B	From Leg	4.00 0.00 0.00	0.0000	131.00	No Ice 1/2" Ice 1" Ice	2.31 2.52 2.73	2.38 2.58 2.79	0.06 0.08 0.11
RRH4X45-19	C	From Leg	4.00 0.00 0.00	0.0000	131.00	No Ice 1/2" Ice 1" Ice	2.31 2.52 2.73	2.38 2.58 2.79	0.06 0.08 0.11
APXVTM14-ALU-I20 w/ Mount Pipe	A	From Leg	4.00 0.00 0.00	0.0000	131.00	No Ice 1/2" Ice 1" Ice	6.58 7.03 7.47	4.96 5.75 6.47	0.08 0.13 0.19
APXVTM14-ALU-I20 w/ Mount Pipe	B	From Leg	4.00 0.00 0.00	0.0000	131.00	No Ice 1/2" Ice 1" Ice	6.58 7.03 7.47	4.96 5.75 6.47	0.08 0.13 0.19
APXVTM14-ALU-I20 w/ Mount Pipe	C	From Leg	4.00 0.00 0.00	0.0000	131.00	No Ice 1/2" Ice 1" Ice	6.58 7.03 7.47	4.96 5.75 6.47	0.08 0.13 0.19
TD-RRH8x20	A	From Leg	4.00 0.00 0.00	0.0000	131.00	No Ice 1/2" Ice 1" Ice	3.70 3.95 4.20	1.29 1.46 1.64	0.07 0.09 0.12
TD-RRH8x20	B	From Leg	4.00 0.00 0.00	0.0000	131.00	No Ice 1/2" Ice 1" Ice	3.70 3.95 4.20	1.29 1.46 1.64	0.07 0.09 0.12
TD-RRH8x20	C	From Leg	4.00 0.00 0.00	0.0000	131.00	No Ice 1/2" Ice 1" Ice	3.70 3.95 4.20	1.29 1.46 1.64	0.07 0.09 0.12
Sector Frame Mount	A	From Leg	2.00 0.00 0.00	0.0000	131.00	No Ice 1/2" Ice 1" Ice	15.35 21.29 27.23	14.00 20.81 27.62	0.56 0.74 0.92
Sector Frame Mount	B	From Leg	2.00 0.00 0.00	0.0000	131.00	No Ice 1/2" Ice 1" Ice	15.35 21.29 27.23	14.00 20.81 27.62	0.56 0.74 0.92
Sector Frame Mount	C	From Leg	2.00 0.00 0.00	0.0000	131.00	No Ice 1/2" Ice 1" Ice	15.35 21.29 27.23	14.00 20.81 27.62	0.56 0.74 0.92
*** AIR32 KRD901146-1_B66_B2A w/ Mount Pipe	A	From Leg	4.00 0.00	0.0000	115.00	No Ice 1/2" Ice	11.39 11.88	5.90 6.56	0.11 0.19

tnxTower Centerline Engineering Services, PA 750 W Center St, Suite 301 West Bridgewater, MA 02379 Phone: (781) 713-4725 FAX:	Job	Stamford NW CT	Page	20 of 52
	Project	23CLVZ-0009	Date	15:14:50 09/21/23
	Client	Verizon Wireless	Designed by	jboegel

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment °	Placement ft	C _{AA} Front ft ²	C _{AA} Side ft ²	Weight K
AIR32 KRD901146-1_B66_B2A w/ Mount Pipe	B	From Leg	3.00 4.00 0.00 3.00	0.0000	115.00	1" Ice 12.33 No Ice 11.39 1/2" Ice 11.88 1" Ice 12.33	7.24 5.90 6.56 7.24	0.28 0.11 0.19 0.28
AIR32 KRD901146-1_B66_B2A w/ Mount Pipe	C	From Leg	3.00 4.00 0.00 3.00	0.0000	115.00	No Ice 11.39 1/2" Ice 11.88 1" Ice 12.33	5.90 6.56 7.24	0.11 0.19 0.28
AIR6449 B41 w/ Mount Pipe	A	From Leg	3.00 4.00 0.00 3.00	0.0000	115.00	No Ice 6.93 1/2" Ice 7.77 1" Ice 8.52	4.39 5.45 6.35	0.13 0.19 0.26
AIR6449 B41 w/ Mount Pipe	B	From Leg	3.00 4.00 0.00 3.00	0.0000	115.00	No Ice 6.93 1/2" Ice 7.77 1" Ice 8.52	4.39 5.45 6.35	0.13 0.19 0.26
AIR6449 B41 w/ Mount Pipe	C	From Leg	3.00 4.00 0.00 3.00	0.0000	115.00	No Ice 6.93 1/2" Ice 7.77 1" Ice 8.52	4.39 5.45 6.35	0.13 0.19 0.26
APXVAARR24_43-U-NA20 w/ Mount Pipe	A	From Leg	3.00 4.00 0.00 3.00	0.0000	115.00	No Ice 20.24 1/2" Ice 20.89 1" Ice 21.55	10.79 12.21 13.49	0.16 0.29 0.44
APXVAARR24_43-U-NA20 w/ Mount Pipe	B	From Leg	3.00 4.00 0.00 3.00	0.0000	115.00	No Ice 20.24 1/2" Ice 20.89 1" Ice 21.55	10.79 12.21 13.49	0.16 0.29 0.44
APXVAARR24_43-U-NA20 w/ Mount Pipe	C	From Leg	3.00 4.00 0.00 3.00	0.0000	115.00	No Ice 20.24 1/2" Ice 20.89 1" Ice 21.55	10.79 12.21 13.49	0.16 0.29 0.44
RRUS 11 B4	A	From Leg	3.00 4.00 0.00 3.00	0.0000	115.00	No Ice 2.83 1/2" Ice 3.04 1" Ice 3.26	1.18 1.33 1.48	0.05 0.07 0.10
RRUS 11 B4	B	From Leg	3.00 4.00 0.00 3.00	0.0000	115.00	No Ice 2.83 1/2" Ice 3.04 1" Ice 3.26	1.18 1.33 1.48	0.05 0.07 0.10
RRUS 11 B4	C	From Leg	3.00 4.00 0.00 3.00	0.0000	115.00	No Ice 2.83 1/2" Ice 3.04 1" Ice 3.26	1.18 1.33 1.48	0.05 0.07 0.10
RRUS 4415 B25	A	From Leg	3.00 4.00 0.00 3.00	0.0000	115.00	No Ice 1.64 1/2" Ice 1.80 1" Ice 1.97	0.68 0.79 0.91	0.04 0.06 0.07
RRUS 4415 B25	B	From Leg	3.00 4.00 0.00 3.00	0.0000	115.00	No Ice 1.64 1/2" Ice 1.80 1" Ice 1.97	0.68 0.79 0.91	0.04 0.06 0.07
RRUS 4415 B25	C	From Leg	3.00 4.00 0.00 3.00	0.0000	115.00	No Ice 1.64 1/2" Ice 1.80 1" Ice 1.97	0.68 0.79 0.91	0.04 0.06 0.07
Sector Frame Mount	A	From Leg	0.00 2.00 0.00 0.00	0.0000	115.00	No Ice 15.35 1/2" Ice 21.29 1" Ice 27.23	14.00 20.81 27.62	0.56 0.74 0.92
Sector Frame Mount	B	From Leg	0.00 2.00 0.00 0.00	0.0000	115.00	No Ice 15.35 1/2" Ice 21.29 1" Ice 27.23	14.00 20.81 27.62	0.56 0.74 0.92
Sector Frame Mount	C	From Leg	0.00 2.00 0.00 0.00	0.0000	115.00	No Ice 15.35 1/2" Ice 21.29 1" Ice 27.23	14.00 20.81 27.62	0.56 0.74 0.92

XXDWMM-12.5-65-8T-CBR S w/ Mount Pipe	A	From Leg	0.00 4.00 0.00 0.00	0.0000	98.00	No Ice 3.12 1/2" Ice 3.96 1" Ice 4.69	2.65 3.60 4.40	0.05 0.08 0.12
XXDWMM-12.5-65-8T-CBR	B	From Leg	0.00 4.00	0.0000	98.00	No Ice 3.12	2.65	0.05

tnxTower Centerline Engineering Services, PA 750 W Center St, Suite 301 West Bridgewater, MA 02379 Phone: (781) 713-4725 FAX:	Job	Stamford NW CT	Page	21 of 52
	Project	23CLVZ-0009	Date	15:14:50 09/21/23
	Client	Verizon Wireless	Designed by	jboegel

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment °	Placement ft	C _A A _A Front ft ²	C _A A _A Side ft ²	Weight K
S w/ Mount Pipe			0.00		1/2" Ice	3.96	3.60	0.08
XXDWMM-12.5-65-8T-CBR	C	From Leg	0.00		1" Ice	4.69	4.40	0.12
S w/ Mount Pipe			4.00	0.0000	No Ice	3.12	2.65	0.05
			0.00		1/2" Ice	3.96	3.60	0.08
			0.00		1" Ice	4.69	4.40	0.12
(2) JAHH-65B-R3B w/ Mount Pipe	A	From Leg	4.00	0.0000	No Ice	9.35	7.65	0.09
			0.00		1/2" Ice	9.92	8.83	0.16
			0.00		1" Ice	10.46	9.73	0.25
(2) JAHH-65B-R3B w/ Mount Pipe	B	From Leg	4.00	0.0000	No Ice	9.35	7.65	0.09
			0.00		1/2" Ice	9.92	8.83	0.16
			0.00		1" Ice	10.46	9.73	0.25
(2) JAHH-65B-R3B w/ Mount Pipe	C	From Leg	4.00	0.0000	No Ice	9.35	7.65	0.09
			0.00		1/2" Ice	9.92	8.83	0.16
			0.00		1" Ice	10.46	9.73	0.25
BSAMNT-SBS-2-2	A	From Leg	4.00	0.0000	No Ice	0.11	0.34	0.07
			0.00		1/2" Ice	0.16	0.42	0.07
			0.00		1" Ice	0.21	0.50	0.08
BSAMNT-SBS-2-2	B	From Leg	4.00	0.0000	No Ice	0.11	0.34	0.07
			0.00		1/2" Ice	0.16	0.42	0.07
			0.00		1" Ice	0.21	0.50	0.08
BSAMNT-SBS-2-2	C	From Leg	4.00	0.0000	No Ice	0.11	0.34	0.07
			0.00		1/2" Ice	0.16	0.42	0.07
			0.00		1" Ice	0.21	0.50	0.08
DB-T1-6Z-8AB-0Z (OVP)	A	From Leg	4.00	0.0000	No Ice	0.34	0.27	0.01
			0.00		1/2" Ice	0.42	0.34	0.01
			0.00		1" Ice	0.50	0.41	0.01
DB-T1-6Z-8AB-0Z (OVP)	B	From Leg	4.00	0.0000	No Ice	0.34	0.27	0.01
			0.00		1/2" Ice	0.42	0.34	0.01
			0.00		1" Ice	0.50	0.41	0.01
DB-T1-6Z-8AB-0Z (OVP)	C	From Leg	4.00	0.0000	No Ice	0.34	0.27	0.01
			0.00		1/2" Ice	0.42	0.34	0.01
			0.00		1" Ice	0.50	0.41	0.01
B2/B66A RRH-BR049 (RFV01U-D1A)	A	From Leg	4.00	0.0000	No Ice	1.88	1.25	0.08
			0.00		1/2" Ice	2.05	1.39	0.10
			0.00		1" Ice	2.22	1.54	0.12
B2/B66A RRH-BR049 (RFV01U-D1A)	B	From Leg	4.00	0.0000	No Ice	1.88	1.25	0.08
			0.00		1/2" Ice	2.05	1.39	0.10
			0.00		1" Ice	2.22	1.54	0.12
B2/B66A RRH-BR049 (RFV01U-D1A)	C	From Leg	4.00	0.0000	No Ice	1.88	1.25	0.08
			0.00		1/2" Ice	2.05	1.39	0.10
			0.00		1" Ice	2.22	1.54	0.12
B5/B13 RRH-BR04C (RFV01U-D2A)	A	From Leg	4.00	0.0000	No Ice	1.88	1.01	0.07
			0.00		1/2" Ice	2.05	1.14	0.09
			0.00		1" Ice	2.22	1.28	0.11
B5/B13 RRH-BR04C (RFV01U-D2A)	B	From Leg	4.00	0.0000	No Ice	1.88	1.01	0.07
			0.00		1/2" Ice	2.05	1.14	0.09
			0.00		1" Ice	2.22	1.28	0.11
B5/B13 RRH-BR04C (RFV01U-D2A)	C	From Leg	4.00	0.0000	No Ice	1.88	1.01	0.07
			0.00		1/2" Ice	2.05	1.14	0.09
			0.00		1" Ice	2.22	1.28	0.11
CBC78T-DS-43-2X	A	From Leg	4.00	0.0000	No Ice	0.37	0.51	0.02
			0.00		1/2" Ice	0.45	0.60	0.03
			0.00		1" Ice	0.53	0.70	0.04
CBC78T-DS-43-2X	B	From Leg	4.00	0.0000	No Ice	0.37	0.51	0.02
			0.00		1/2" Ice	0.45	0.60	0.03
			0.00		1" Ice	0.53	0.70	0.04
CBC78T-DS-43-2X	C	From Leg	4.00	0.0000	No Ice	0.37	0.51	0.02

tnxTower Centerline Engineering Services, PA 750 W Center St, Suite 301 West Bridgewater, MA 02379 Phone: (781) 713-4725 FAX:	Job	Stamford NW CT	Page 22 of 52
	Project	23CLVZ-0009	Date 15:14:50 09/21/23
	Client	Verizon Wireless	Designed by jboegel

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment °	Placement ft	C _A A _A Front ft ²	C _A A _A Side ft ²	Weight K	
Site Pro 1 VFA12-HD	A	From Leg	0.00	0.0000	98.00	1/2" Ice	0.45	0.03	
			0.00			1" Ice	0.53	0.70	0.04
			2.00			No Ice	13.20	9.20	0.66
			0.00			1/2" Ice	19.50	14.60	0.80
Site Pro 1 VFA12-HD	B	From Leg	0.00	0.0000	98.00	1" Ice	25.80	20.00	1.01
			2.00			No Ice	13.20	9.20	0.66
			0.00			1/2" Ice	19.50	14.60	0.80
			0.00			1" Ice	25.80	20.00	1.01
Site Pro 1 VFA12-HD	C	From Leg	2.00	0.0000	98.00	No Ice	13.20	9.20	0.66
			0.00			1/2" Ice	19.50	14.60	0.80
			0.00			1" Ice	25.80	20.00	1.01
			0.00			1" Ice	25.80	20.00	1.01
MT6407-77A w/ Pipe Mount	A	From Leg	4.00	0.0000	98.00	No Ice	4.71	2.43	0.10
			0.00			1/2" Ice	5.01	2.84	0.14
			0.00			1" Ice	5.31	3.26	0.18
			0.00			1" Ice	5.31	3.26	0.18
MT6407-77A w/ Pipe Mount	B	From Leg	4.00	0.0000	98.00	No Ice	4.71	2.43	0.10
			0.00			1/2" Ice	5.01	2.84	0.14
			0.00			1" Ice	5.31	3.26	0.18
			0.00			1" Ice	5.31	3.26	0.18
MT6407-77A w/ Pipe Mount	C	From Leg	4.00	0.0000	98.00	No Ice	4.71	2.43	0.10
			0.00			1/2" Ice	5.01	2.84	0.14
			0.00			1" Ice	5.31	3.26	0.18
			0.00			1" Ice	5.31	3.26	0.18
(2) KA-6030	B	From Leg	2.00	0.0000	98.00	No Ice	0.77	0.28	0.03
			0.00			1/2" Ice	0.88	0.35	0.03
			0.00			1" Ice	1.00	0.43	0.04
			0.00			1" Ice	1.00	0.43	0.04
(2) KA-6030	C	From Leg	2.00	0.0000	98.00	No Ice	0.77	0.28	0.03
			0.00			1/2" Ice	0.88	0.35	0.03
			0.00			1" Ice	1.00	0.43	0.04
			0.00			1" Ice	1.00	0.43	0.04
Site Pro 1 RRUDSM	B	From Leg	1.00	0.0000	98.00	No Ice	1.13	1.13	0.04
			0.00			1/2" Ice	1.69	1.69	0.09
			0.00			1" Ice	2.25	2.25	0.13
			0.00			1" Ice	2.25	2.25	0.13
Site Pro 1 RRUDSM	C	From Leg	1.00	0.0000	98.00	No Ice	1.13	1.13	0.04
			0.00			1/2" Ice	1.69	1.69	0.09
			0.00			1" Ice	2.25	2.25	0.13
			0.00			1" Ice	2.25	2.25	0.13

8' 4-Bay Dipole	C	From Leg	3.00	0.0000	74.00	No Ice	4.00	4.00	0.06
			0.00			1/2" Ice	6.00	6.00	0.10
			4.00			1" Ice	8.00	8.00	0.14
			0.00			No Ice	1.50	3.00	0.19
2' x 3' sidearm	C	From Leg	1.50	0.0000	74.00	1/2" Ice	2.50	4.00	0.28
			0.00			1" Ice	3.50	5.00	0.36
			0.00			1" Ice	3.50	5.00	0.36
			0.00			1" Ice	3.50	5.00	0.36

GPS	C	From Leg	3.00	0.0000	58.00	No Ice	0.15	0.15	0.01
			0.00			1/2" Ice	0.24	0.24	0.02
			0.00			1" Ice	0.31	0.31	0.02
			0.00			1" Ice	0.31	0.31	0.02
2' x 3' sidearm	C	From Leg	1.50	0.0000	58.00	No Ice	1.50	3.00	0.19
			0.00			1/2" Ice	2.50	4.00	0.28
			0.00			1" Ice	3.50	5.00	0.36
			0.00			1" Ice	3.50	5.00	0.36

(3) Site Pro 1 SFR-K	C	None		0.0000	115.00	No Ice	6.83	3.11	0.07
						1/2" Ice	8.01	3.65	0.11
						1" Ice	9.19	4.19	0.16
						No Ice	2.25	2.25	0.08
10' x 2-1/4" Pipe Mount	C	From Leg	4.00	0.0000	115.00	1/2" Ice	3.28	3.28	0.10
			0.00			1" Ice	4.32	4.32	0.12
			0.00			No Ice	2.25	2.25	0.08
			0.00			1/2" Ice	3.28	3.28	0.10
10' x 2-1/4" Pipe Mount	C	From Leg	0.00	0.0000	115.00	1" Ice	4.32	4.32	0.12
			4.00			No Ice	2.25	2.25	0.08
			0.00			1/2" Ice	3.28	3.28	0.10
			0.00			1" Ice	4.32	4.32	0.12
10' x 2-1/4" Pipe Mount	C	From Leg	4.00	0.0000	115.00	No Ice	2.25	2.25	0.08

tnxTower Centerline Engineering Services, PA 750 W Center St, Suite 301 West Bridgewater, MA 02379 Phone: (781) 713-4725 FAX:	Job	Stamford NW CT	Page	23 of 52
	Project	23CLVZ-0009	Date	15:14:50 09/21/23
	Client	Verizon Wireless	Designed by	jboegel

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment °	Placement ft	C _A A _A Front ft ²	C _A A _A Side ft ²	Weight K
RADIO 4449 B71+B85	A	From Leg	0.00	0.0000	115.00	1/2" Ice	3.28	0.10
			0.00			1" Ice	4.32	0.12
			4.00			No Ice	1.64	0.07
			0.00			1/2" Ice	1.80	0.09
RADIO 4449 B71+B85	B	From Leg	3.00	0.0000	115.00	1" Ice	1.97	0.11
			4.00			No Ice	1.64	0.07
			0.00			1/2" Ice	1.80	0.09
			3.00			1" Ice	1.97	0.11
RADIO 4449 B71+B85	C	From Leg	4.00	0.0000	115.00	No Ice	1.64	0.07
			0.00			1/2" Ice	1.80	0.09
			3.00			1" Ice	1.97	0.11
			0.00			1/2" Ice	1.80	0.09
***			3.00			1" Ice	1.97	0.11

Dishes

Description	Face or Leg	Dish Type	Offset Type	Offsets: Horz Lateral Vert ft	Azimuth Adjustment °	3 dB Beam Width °	Elevation ft	Outside Diameter ft	Aperture Area ft²	Weight K	
4' HP MW	C	Paraboloid w/Shroud (HP)	From Leg	1.00	0.0000		152.00	4.00	No Ice	12.57	0.12
				0.00					1/2" Ice	13.10	0.19
				0.00					1" Ice	13.63	0.26

4' HP MW	B	Paraboloid w/Shroud (HP)	From Leg	1.00	0.0000		140.00	4.00	No Ice	12.57	0.12
				0.00					1/2" Ice	13.10	0.19
				0.00					1" Ice	13.63	0.26

Discrete Appurtenance Pressures - No Ice G_H = 0.850

Description	Aiming Azimuth °	Weight K	Offset ₁ ft	Offset ₂ ft	z ft	K _z	q _z psf	C _A A _C Front ft ²	C _A A _C Side ft ²
20' 4-Bay Dipole	180.0000	0.06	0.00	2.88	162.00	1.134	31	4.00	4.00
TMA	240.0000	0.05	-3.69	2.13	152.00	1.114	30	1.50	1.50
6"x4" Sch 40 Pipe	240.0000	0.06	-3.69	2.13	152.00	1.114	30	1.96	1.96
DB563K-TT w/Mount Pipe	0.0000	0.13	0.00	-6.77	157.00	1.124	31	19.19	4.03
2' x 3' sidearm	0.0000	0.19	0.00	-5.27	150.00	1.110	30	1.50	3.00
4' x 4.5" Pipe Mount	240.0000	0.04	-3.69	2.13	152.00	1.114	30	1.19	1.19
QS66512-2 w/ Mount Pipe	0.0000	0.14	0.00	-6.78	145.00	1.099	30	8.37	8.46
QS66512-2 w/ Mount Pipe	120.0000	0.14	5.87	3.39	145.00	1.099	30	8.37	8.46
QS66512-2 w/ Mount Pipe	240.0000	0.14	-5.87	3.39	145.00	1.099	30	8.37	8.46
TMA2117F00V1-1	0.0000	0.04	0.00	-6.78	145.00	1.099	30	0.59	1.67
TMA2117F00V1-1	120.0000	0.04	5.87	3.39	145.00	1.099	30	0.59	1.67

tnxTower Centerline Engineering Services, PA 750 W Center St, Suite 301 West Bridgewater, MA 02379 Phone: (781) 713-4725 FAX:	Job	Stamford NW CT	Page 24 of 52
	Project	23CLVZ-0009	Date 15:14:50 09/21/23
	Client	Verizon Wireless	Designed by jboegel

Description	Aiming Azimuth °	Weight K	Offset _x ft	Offset _y ft	z ft	K _z	q _z psf	C _A Ac Front ft ²	C _A Ac Side ft ²
TMA2117F00V1-1	240.0000	0.04	-5.87	3.39	145.00	1.099	30	0.59	1.67
2' x 3' Side Arm Mount	0.0000	0.11	0.00	-5.28	145.00	1.099	30	1.78	2.97
2' x 3' Side Arm Mount	120.0000	0.11	4.57	2.64	145.00	1.099	30	1.78	2.97
2' x 3' Side Arm Mount	240.0000	0.11	-4.57	2.64	145.00	1.099	30	1.78	2.97
4' x 4.5" Pipe Mount	120.0000	0.04	3.71	2.14	140.00	1.088	30	1.19	1.19
6' x 3" Omni	120.0000	0.02	6.13	3.54	138.00	1.083	30	1.77	1.77
2' x 3' Side Arm Mount	120.0000	0.19	4.83	2.79	135.00	1.077	29	1.50	3.00
DB254-A	240.0000	0.01	-6.13	3.54	135.00	1.077	29	1.10	1.10
2' x 3' Side Arm Mount	240.0000	0.19	-4.83	2.79	135.00	1.077	29	1.50	3.00
APXVSPP18-C-A20 w/ Mount Pipe	0.0000	0.08	0.00	-8.32	131.00	1.067	29	8.26	6.95
APXVSPP18-C-A20 w/ Mount Pipe	120.0000	0.08	7.20	4.16	131.00	1.067	29	8.26	6.95
APXVSPP18-C-A20 w/ Mount Pipe	240.0000	0.08	-7.20	4.16	131.00	1.067	29	8.26	6.95
RRH2x50-WCS	0.0000	0.08	0.00	-8.32	131.00	1.067	29	4.91	2.70
RRH2x50-WCS	120.0000	0.08	7.20	4.16	131.00	1.067	29	4.91	2.70
RRH2x50-WCS	240.0000	0.08	-7.20	4.16	131.00	1.067	29	4.91	2.70
RRH4X45-19	0.0000	0.06	0.00	-8.32	131.00	1.067	29	2.31	2.38
RRH4X45-19	120.0000	0.06	7.20	4.16	131.00	1.067	29	2.31	2.38
RRH4X45-19	240.0000	0.06	-7.20	4.16	131.00	1.067	29	2.31	2.38
APXVTM14-ALU-I20 w/ Mount Pipe	0.0000	0.08	0.00	-8.32	131.00	1.067	29	6.58	4.96
APXVTM14-ALU-I20 w/ Mount Pipe	120.0000	0.08	7.20	4.16	131.00	1.067	29	6.58	4.96
APXVTM14-ALU-I20 w/ Mount Pipe	240.0000	0.08	-7.20	4.16	131.00	1.067	29	6.58	4.96
TD-RRH8x20	0.0000	0.07	0.00	-8.32	131.00	1.067	29	3.70	1.29
TD-RRH8x20	120.0000	0.07	7.20	4.16	131.00	1.067	29	3.70	1.29
TD-RRH8x20	240.0000	0.07	-7.20	4.16	131.00	1.067	29	3.70	1.29
Sector Frame Mount	0.0000	0.56	0.00	-6.32	131.00	1.067	29	15.35	14.00
Sector Frame Mount	120.0000	0.56	5.47	3.16	131.00	1.067	29	15.35	14.00
Sector Frame Mount	240.0000	0.56	-5.47	3.16	131.00	1.067	29	15.35	14.00
AIR32 KRD901146- 1_B66_B2A w/ Mount Pipe	0.0000	0.11	0.00	-9.25	118.00	1.036	28	11.39	5.90
AIR32 KRD901146- 1_B66_B2A w/ Mount Pipe	120.0000	0.11	8.01	4.63	118.00	1.036	28	11.39	5.90
AIR32 KRD901146- 1_B66_B2A w/ Mount Pipe	240.0000	0.11	-8.01	4.63	118.00	1.036	28	11.39	5.90
AIR6449 B41 w/ Mount Pipe	0.0000	0.13	0.00	-9.25	118.00	1.036	28	6.93	4.39
AIR6449 B41 w/ Mount Pipe	120.0000	0.13	8.01	4.63	118.00	1.036	28	6.93	4.39
AIR6449 B41 w/ Mount Pipe	240.0000	0.13	-8.01	4.63	118.00	1.036	28	6.93	4.39
APXVAARR24_43-U-N A20 w/ Mount Pipe	0.0000	0.16	0.00	-9.25	118.00	1.036	28	20.24	10.79
APXVAARR24_43-U-N A20 w/ Mount Pipe	120.0000	0.16	8.01	4.63	118.00	1.036	28	20.24	10.79
APXVAARR24_43-U-N A20 w/ Mount Pipe	240.0000	0.16	-8.01	4.63	118.00	1.036	28	20.24	10.79
RRUS 11 B4	0.0000	0.05	0.00	-9.25	118.00	1.036	28	2.83	1.18
RRUS 11 B4	120.0000	0.05	8.01	4.63	118.00	1.036	28	2.83	1.18
RRUS 11 B4	240.0000	0.05	-8.01	4.63	118.00	1.036	28	2.83	1.18
RRUS 4415 B25	0.0000	0.04	0.00	-9.25	118.00	1.036	28	1.64	0.68
RRUS 4415 B25	120.0000	0.04	8.01	4.63	118.00	1.036	28	1.64	0.68
RRUS 4415 B25	240.0000	0.04	-8.01	4.63	118.00	1.036	28	1.64	0.68
Sector Frame Mount	0.0000	0.56	0.00	-7.25	115.00	1.028	28	15.35	14.00

tnxTower Centerline Engineering Services, PA 750 W Center St, Suite 301 West Bridgewater, MA 02379 Phone: (781) 713-4725 FAX:	Job	Stamford NW CT	Page	25 of 52
	Project	23CLVZ-0009	Date	15:14:50 09/21/23
	Client	Verizon Wireless	Designed by	jboegel

Description	Aiming Azimuth °	Weight K	Offset _x ft	Offset _y ft	z ft	K _z	q _z psf	C _{AC} Front ft ²	C _{AC} Side ft ²
Sector Frame Mount	120.0000	0.56	6.28	3.63	115.00	1.028	28	15.35	14.00
Sector Frame Mount	240.0000	0.56	-6.28	3.63	115.00	1.028	28	15.35	14.00
XXDWMM-12.5-65-8T- CBRS w/ Mount Pipe	0.0000	0.05	0.00	-10.25	98.00	0.983	27	3.12	2.65
XXDWMM-12.5-65-8T- CBRS w/ Mount Pipe	120.0000	0.05	8.88	5.13	98.00	0.983	27	3.12	2.65
XXDWMM-12.5-65-8T- CBRS w/ Mount Pipe	240.0000	0.05	-8.88	5.13	98.00	0.983	27	3.12	2.65
JAHH-65B-R3B w/ Mount Pipe	0.0000	0.18	0.00	-10.25	98.00	0.983	27	18.70	15.29
JAHH-65B-R3B w/ Mount Pipe	120.0000	0.18	8.88	5.13	98.00	0.983	27	18.70	15.29
JAHH-65B-R3B w/ Mount Pipe	240.0000	0.18	-8.88	5.13	98.00	0.983	27	18.70	15.29
BSAMNT-SBS-2-2	0.0000	0.07	0.00	-10.25	98.00	0.983	27	0.11	0.34
BSAMNT-SBS-2-2	120.0000	0.07	8.88	5.13	98.00	0.983	27	0.11	0.34
BSAMNT-SBS-2-2	240.0000	0.07	-8.88	5.13	98.00	0.983	27	0.11	0.34
DB-T1-6Z-8AB-0Z (OVP)	0.0000	0.01	0.00	-10.25	98.00	0.983	27	0.34	0.27
DB-T1-6Z-8AB-0Z (OVP)	120.0000	0.01	8.88	5.13	98.00	0.983	27	0.34	0.27
DB-T1-6Z-8AB-0Z (OVP)	240.0000	0.01	-8.88	5.13	98.00	0.983	27	0.34	0.27
B2/B66A RRH-BR049 (RFV01U-D1A)	0.0000	0.08	0.00	-10.25	98.00	0.983	27	1.88	1.25
B2/B66A RRH-BR049 (RFV01U-D1A)	120.0000	0.08	8.88	5.13	98.00	0.983	27	1.88	1.25
B2/B66A RRH-BR049 (RFV01U-D1A)	240.0000	0.08	-8.88	5.13	98.00	0.983	27	1.88	1.25
B5/B13 RRH-BR04C (RFV01U-D2A)	0.0000	0.07	0.00	-10.25	98.00	0.983	27	1.88	1.01
B5/B13 RRH-BR04C (RFV01U-D2A)	120.0000	0.07	8.88	5.13	98.00	0.983	27	1.88	1.01
B5/B13 RRH-BR04C (RFV01U-D2A)	240.0000	0.07	-8.88	5.13	98.00	0.983	27	1.88	1.01
CBC78T-DS-43-2X	0.0000	0.02	0.00	-10.25	98.00	0.983	27	0.37	0.51
CBC78T-DS-43-2X	120.0000	0.02	8.88	5.13	98.00	0.983	27	0.37	0.51
CBC78T-DS-43-2X	240.0000	0.02	-8.88	5.13	98.00	0.983	27	0.37	0.51
Site Pro 1 VFA12-HD	0.0000	0.66	0.00	-8.25	98.00	0.983	27	13.20	9.20
Site Pro 1 VFA12-HD	120.0000	0.66	7.15	4.13	98.00	0.983	27	13.20	9.20
Site Pro 1 VFA12-HD	240.0000	0.66	-7.15	4.13	98.00	0.983	27	13.20	9.20
MT6407-77A w/ Pipe Mount	0.0000	0.10	0.00	-10.25	98.00	0.983	27	4.71	2.43
MT6407-77A w/ Pipe Mount	120.0000	0.10	8.88	5.13	98.00	0.983	27	4.71	2.43
MT6407-77A w/ Pipe Mount	240.0000	0.10	-8.88	5.13	98.00	0.983	27	4.71	2.43
KA-6030	120.0000	0.06	7.15	4.13	98.00	0.983	27	1.54	0.56
KA-6030	240.0000	0.06	-7.15	4.13	98.00	0.983	27	1.54	0.56
Site Pro 1 RRUDSM	120.0000	0.04	6.28	3.63	98.00	0.983	27	1.13	1.13
Site Pro 1 RRUDSM	240.0000	0.04	-6.28	3.63	98.00	0.983	27	1.13	1.13
8' 4-Bay Dipole	240.0000	0.06	-9.23	5.33	78.00	0.921	25	4.00	4.00
2' x 3' sidearm	240.0000	0.19	-7.93	4.58	74.00	0.907	25	1.50	3.00
GPS	240.0000	0.01	-10.04	5.80	58.00	0.846	23	0.15	0.15
2' x 3' sidearm	240.0000	0.19	-8.75	5.05	58.00	0.846	23	1.50	3.00
Site Pro 1 SFR-K	0.0000	0.20	0.00	0.00	115.00	1.028	28	20.49	9.33
10' x 2-1/4" Pipe Mount	240.0000	0.08	-8.01	4.63	115.00	1.028	28	2.25	2.25
10' x 2-1/4" Pipe Mount	240.0000	0.08	-8.01	4.63	115.00	1.028	28	2.25	2.25
10' x 2-1/4" Pipe Mount	240.0000	0.08	-8.01	4.63	115.00	1.028	28	2.25	2.25
RADIO 4449 B71+B85	0.0000	0.07	0.00	-9.25	118.00	1.036	28	1.64	1.31
RADIO 4449 B71+B85	120.0000	0.07	8.01	4.63	118.00	1.036	28	1.64	1.31

tnxTower Centerline Engineering Services, PA 750 W Center St, Suite 301 West Bridgewater, MA 02379 Phone: (781) 713-4725 FAX:	Job	Stamford NW CT	Page 26 of 52
	Project	23CLVZ-0009	Date 15:14:50 09/21/23
	Client	Verizon Wireless	Designed by jboegel

Description	Aiming Azimuth °	Weight K	Offset _x ft	Offset _z ft	z ft	K _z	q _z psf	C _d A _c Front ft ²	C _d A _c Side ft ²
RADIO 4449 B71+B85	240.0000	0.07	-8.01	4.63	118.00	1.036	28	1.64	1.31
	Sum	12.77							
	Weight:								

Discrete Appurtenance Pressures - With Ice G_H = 0.850

Description	Aiming Azimuth °	Weight K	Offset _x ft	Offset _z ft	z ft	K _z	q _z psf	C _d A _c Front ft ²	C _d A _c Side ft ²	l _z in
20' 4-Bay Dipole	180.0000	0.14	0.00	2.88	162.00	1.134	6	7.99	7.99	0.9966
TMA	240.0000	0.07	-3.69	2.13	152.00	1.114	6	2.98	2.98	0.9903
6'x4" Sch 40 Pipe	240.0000	0.10	-3.69	2.13	152.00	1.114	6	2.99	2.99	0.9903
DB563K-TT w/Mount	0.0000	0.35	0.00	-6.77	157.00	1.124	6	21.26	9.87	0.9935
Pipe										
2' x 3' sidearm	0.0000	0.36	0.00	-5.27	150.00	1.110	6	3.48	4.98	0.9890
4' x 4.5" Pipe Mount	240.0000	0.07	-3.69	2.13	152.00	1.114	6	1.83	1.83	0.9903
QS66512-2 w/ Mount	0.0000	0.29	0.00	-6.78	145.00	1.099	6	9.44	10.52	0.9856
Pipe										
QS66512-2 w/ Mount	120.0000	0.29	5.87	3.39	145.00	1.099	6	9.44	10.52	0.9856
Pipe										
QS66512-2 w/ Mount	240.0000	0.29	-5.87	3.39	145.00	1.099	6	9.44	10.52	0.9856
Pipe										
TMA2117F00V1-1	0.0000	0.07	0.00	-6.78	145.00	1.099	6	0.90	2.14	0.9856
TMA2117F00V1-1	120.0000	0.07	5.87	3.39	145.00	1.099	6	0.90	2.14	0.9856
TMA2117F00V1-1	240.0000	0.07	-5.87	3.39	145.00	1.099	6	0.90	2.14	0.9856
2' x 3' Side Arm Mount	0.0000	0.16	0.00	-5.28	145.00	1.099	6	2.74	4.17	0.9856
2' x 3' Side Arm Mount	120.0000	0.16	4.57	2.64	145.00	1.099	6	2.74	4.17	0.9856
2' x 3' Side Arm Mount	240.0000	0.16	-4.57	2.64	145.00	1.099	6	2.74	4.17	0.9856
4' x 4.5" Pipe Mount	120.0000	0.07	3.71	2.14	140.00	1.088	6	1.83	1.83	0.9822
6' x 3" Omni	120.0000	0.05	6.13	3.54	138.00	1.083	6	2.48	2.48	0.9807
2' x 3' Side Arm Mount	120.0000	0.36	4.83	2.79	135.00	1.077	5	3.46	4.96	0.9786
DB254-A	240.0000	0.02	-6.13	3.54	135.00	1.077	5	2.82	2.82	0.9786
2' x 3' Side Arm Mount	240.0000	0.36	-4.83	2.79	135.00	1.077	5	3.46	4.96	0.9786
APXVSP18-C-A20 w/	0.0000	0.22	0.00	-8.32	131.00	1.067	5	9.32	8.98	0.9757
Mount Pipe										
APXVSP18-C-A20 w/	120.0000	0.22	7.20	4.16	131.00	1.067	5	9.32	8.98	0.9757
Mount Pipe										
APXVSP18-C-A20 w/	240.0000	0.22	-7.20	4.16	131.00	1.067	5	9.32	8.98	0.9757
Mount Pipe										
RRH2x50-WCS	0.0000	0.14	0.00	-8.32	131.00	1.067	5	5.54	3.29	0.9757
RRH2x50-WCS	120.0000	0.14	7.20	4.16	131.00	1.067	5	5.54	3.29	0.9757
RRH2x50-WCS	240.0000	0.14	-7.20	4.16	131.00	1.067	5	5.54	3.29	0.9757
RRH4X45-19	0.0000	0.11	0.00	-8.32	131.00	1.067	5	2.72	2.78	0.9757
RRH4X45-19	120.0000	0.11	7.20	4.16	131.00	1.067	5	2.72	2.78	0.9757
RRH4X45-19	240.0000	0.11	-7.20	4.16	131.00	1.067	5	2.72	2.78	0.9757
APXVTM14-ALU-I20	0.0000	0.19	0.00	-8.32	131.00	1.067	5	7.45	6.44	0.9757
w/ Mount Pipe										
APXVTM14-ALU-I20	120.0000	0.19	7.20	4.16	131.00	1.067	5	7.45	6.44	0.9757
w/ Mount Pipe										
APXVTM14-ALU-I20	240.0000	0.19	-7.20	4.16	131.00	1.067	5	7.45	6.44	0.9757
w/ Mount Pipe										
TD-RRH8x20	0.0000	0.12	0.00	-8.32	131.00	1.067	5	4.18	1.63	0.9757
TD-RRH8x20	120.0000	0.12	7.20	4.16	131.00	1.067	5	4.18	1.63	0.9757
TD-RRH8x20	240.0000	0.12	-7.20	4.16	131.00	1.067	5	4.18	1.63	0.9757
Sector Frame Mount	0.0000	0.92	0.00	-6.32	131.00	1.067	5	26.94	27.29	0.9757
Sector Frame Mount	120.0000	0.92	5.47	3.16	131.00	1.067	5	26.94	27.29	0.9757
Sector Frame Mount	240.0000	0.92	-5.47	3.16	131.00	1.067	5	26.94	27.29	0.9757
AIR32 KRD901146-	0.0000	0.28	0.00	-9.25	118.00	1.036	5	12.30	7.19	0.9655

tnxTower Centerline Engineering Services, PA 750 W Center St, Suite 301 West Bridgewater, MA 02379 Phone: (781) 713-4725 FAX:	Job	Stamford NW CT	Page	27 of 52
	Project	23CLVZ-0009	Date	15:14:50 09/21/23
	Client	Verizon Wireless	Designed by	jboegel

Description	Aiming Azimuth °	Weight K	Offset _x ft	Offset _y ft	z ft	K _z	q _z psf	C _{AAC} Front ft ²	C _{AAC} Side ft ²	t _z in
1_B66_B2A w/ Mount Pipe										
AIR32 KRD901146-1_B66_B2A w/ Mount Pipe	120.0000	0.28	8.01	4.63	118.00	1.036	5	12.30	7.19	0.9655
AIR32 KRD901146-1_B66_B2A w/ Mount Pipe	240.0000	0.28	-8.01	4.63	118.00	1.036	5	12.30	7.19	0.9655
AIR6449 B41 w/ Mount Pipe	0.0000	0.26	0.00	-9.25	118.00	1.036	5	8.47	6.29	0.9655
AIR6449 B41 w/ Mount Pipe	120.0000	0.26	8.01	4.63	118.00	1.036	5	8.47	6.29	0.9655
AIR6449 B41 w/ Mount Pipe	240.0000	0.26	-8.01	4.63	118.00	1.036	5	8.47	6.29	0.9655
APXVAARR24 43-U-N A20 w/ Mount Pipe	0.0000	0.43	0.00	-9.25	118.00	1.036	5	21.50	13.41	0.9655
APXVAARR24 43-U-N A20 w/ Mount Pipe	120.0000	0.43	8.01	4.63	118.00	1.036	5	21.50	13.41	0.9655
APXVAARR24 43-U-N A20 w/ Mount Pipe	240.0000	0.43	-8.01	4.63	118.00	1.036	5	21.50	13.41	0.9655
RRUS 11 B4	0.0000	0.09	0.00	-9.25	118.00	1.036	5	3.24	1.47	0.9655
RRUS 11 B4	120.0000	0.09	8.01	4.63	118.00	1.036	5	3.24	1.47	0.9655
RRUS 11 B4	240.0000	0.09	-8.01	4.63	118.00	1.036	5	3.24	1.47	0.9655
RRUS 4415 B25	0.0000	0.07	0.00	-9.25	118.00	1.036	5	1.96	0.90	0.9655
RRUS 4415 B25	120.0000	0.07	8.01	4.63	118.00	1.036	5	1.96	0.90	0.9655
RRUS 4415 B25	240.0000	0.07	-8.01	4.63	118.00	1.036	5	1.96	0.90	0.9655
Sector Frame Mount	0.0000	0.91	0.00	-7.25	115.00	1.028	5	26.79	27.12	0.9630
Sector Frame Mount	120.0000	0.91	6.28	3.63	115.00	1.028	5	26.79	27.12	0.9630
Sector Frame Mount	240.0000	0.91	-6.28	3.63	115.00	1.028	5	26.79	27.12	0.9630
XXDWMM-12.5-65-8T-CBRS w/ Mount Pipe	0.0000	0.12	0.00	-10.25	98.00	0.983	5	4.61	4.32	0.9477
XXDWMM-12.5-65-8T-CBRS w/ Mount Pipe	120.0000	0.12	8.88	5.13	98.00	0.983	5	4.61	4.32	0.9477
XXDWMM-12.5-65-8T-CBRS w/ Mount Pipe	240.0000	0.12	-8.88	5.13	98.00	0.983	5	4.61	4.32	0.9477
JAHH-65B-R3B w/ Mount Pipe	0.0000	0.48	0.00	-10.25	98.00	0.983	5	20.80	19.28	0.9477
JAHH-65B-R3B w/ Mount Pipe	120.0000	0.48	8.88	5.13	98.00	0.983	5	20.80	19.28	0.9477
JAHH-65B-R3B w/ Mount Pipe	240.0000	0.48	-8.88	5.13	98.00	0.983	5	20.80	19.28	0.9477
BSAMNT-SBS-2-2	0.0000	0.07	0.00	-10.25	98.00	0.983	5	0.21	0.49	0.9477
BSAMNT-SBS-2-2	120.0000	0.07	8.88	5.13	98.00	0.983	5	0.21	0.49	0.9477
BSAMNT-SBS-2-2	240.0000	0.07	-8.88	5.13	98.00	0.983	5	0.21	0.49	0.9477
DB-T1-6Z-8AB-0Z (OVP)	0.0000	0.01	0.00	-10.25	98.00	0.983	5	0.49	0.40	0.9477
DB-T1-6Z-8AB-0Z (OVP)	120.0000	0.01	8.88	5.13	98.00	0.983	5	0.49	0.40	0.9477
DB-T1-6Z-8AB-0Z (OVP)	240.0000	0.01	-8.88	5.13	98.00	0.983	5	0.49	0.40	0.9477
B2/B66A RRH-BR049 (RFV01U-D1A)	0.0000	0.12	0.00	-10.25	98.00	0.983	5	2.20	1.53	0.9477
B2/B66A RRH-BR049 (RFV01U-D1A)	120.0000	0.12	8.88	5.13	98.00	0.983	5	2.20	1.53	0.9477
B2/B66A RRH-BR049 (RFV01U-D1A)	240.0000	0.12	-8.88	5.13	98.00	0.983	5	2.20	1.53	0.9477
B5/B13 RRH-BR04C (RFV01U-D2A)	0.0000	0.10	0.00	-10.25	98.00	0.983	5	2.20	1.27	0.9477
B5/B13 RRH-BR04C (RFV01U-D2A)	120.0000	0.10	8.88	5.13	98.00	0.983	5	2.20	1.27	0.9477
B5/B13 RRH-BR04C	240.0000	0.10	-8.88	5.13	98.00	0.983	5	2.20	1.27	0.9477

tnxTower Centerline Engineering Services, PA 750 W Center St, Suite 301 West Bridgewater, MA 02379 Phone: (781) 713-4725 FAX:	Job	Stamford NW CT	Page 28 of 52
	Project	23CLVZ-0009	Date 15:14:50 09/21/23
	Client	Verizon Wireless	Designed by jboegel

Description	Aiming Azimuth °	Weight K	Offset _x ft	Offset _y ft	z ft	K _z	q _z psf	C _A C _z Front ft ²	C _A C _z Side ft ²	t _z in
(RFV01U-D2A)										
CBC78T-DS-43-2X	0.0000	0.03	0.00	-10.25	98.00	0.983	5	0.52	0.69	0.9477
CBC78T-DS-43-2X	120.0000	0.03	8.88	5.13	98.00	0.983	5	0.52	0.69	0.9477
CBC78T-DS-43-2X	240.0000	0.03	-8.88	5.13	98.00	0.983	5	0.52	0.69	0.9477
Site Pro 1 VFA12-HD	0.0000	0.99	0.00	-8.25	98.00	0.983	5	25.14	19.44	0.9477
Site Pro 1 VFA12-HD	120.0000	0.99	7.15	4.13	98.00	0.983	5	25.14	19.44	0.9477
Site Pro 1 VFA12-HD	240.0000	0.99	-7.15	4.13	98.00	0.983	5	25.14	19.44	0.9477
MT6407-77A w/ Pipe Mount	0.0000	0.17	0.00	-10.25	98.00	0.983	5	5.28	3.22	0.9477
MT6407-77A w/ Pipe Mount	120.0000	0.17	8.88	5.13	98.00	0.983	5	5.28	3.22	0.9477
MT6407-77A w/ Pipe Mount	240.0000	0.17	-8.88	5.13	98.00	0.983	5	5.28	3.22	0.9477
KA-6030	120.0000	0.08	7.15	4.13	98.00	0.983	5	1.98	0.84	0.9477
KA-6030	240.0000	0.08	-7.15	4.13	98.00	0.983	5	1.98	0.84	0.9477
Site Pro 1 RRUDSM	120.0000	0.13	6.28	3.63	98.00	0.983	5	2.19	2.19	0.9477
Site Pro 1 RRUDSM	240.0000	0.13	-6.28	3.63	98.00	0.983	5	2.19	2.19	0.9477
8' 4-Bay Dipole	240.0000	0.14	-9.23	5.33	78.00	0.921	5	7.71	7.71	0.9264
2' x 3' sidearm	240.0000	0.35	-7.93	4.58	74.00	0.907	5	3.34	4.84	0.9215
GPS	240.0000	0.02	-10.04	5.80	58.00	0.846	4	0.30	0.30	0.8993
2' x 3' sidearm	240.0000	0.34	-8.75	5.05	58.00	0.846	4	3.30	4.80	0.8993
Site Pro 1 SFR-K	0.0000	0.47	0.00	0.00	115.00	1.028	5	27.31	12.45	0.9630
10' x 2-1/4" Pipe Mount	240.0000	0.12	-8.01	4.63	115.00	1.028	5	4.24	4.24	0.9630
10' x 2-1/4" Pipe Mount	240.0000	0.12	-8.01	4.63	115.00	1.028	5	4.24	4.24	0.9630
10' x 2-1/4" Pipe Mount	240.0000	0.12	-8.01	4.63	115.00	1.028	5	4.24	4.24	0.9630
RADIO 4449 B71+B85	0.0000	0.11	0.00	-9.25	118.00	1.036	5	1.96	1.60	0.9655
RADIO 4449 B71+B85	120.0000	0.11	8.01	4.63	118.00	1.036	5	1.96	1.60	0.9655
RADIO 4449 B71+B85	240.0000	0.11	-8.01	4.63	118.00	1.036	5	1.96	1.60	0.9655
Sum Weight:		23.45								

Discrete Appurtenance Pressures - Service $G_H = 0.850$

Description	Aiming Azimuth °	Weight K	Offset _x ft	Offset _y ft	z ft	K _z	q _z psf	C _A C _z Front ft ²	C _A C _z Side ft ²
20' 4-Bay Dipole	180.0000	0.06	0.00	2.88	162.00	1.134	9	4.00	4.00
TMA	240.0000	0.05	-3.69	2.13	152.00	1.114	9	1.50	1.50
6'x4" Sch 40 Pipe	240.0000	0.06	-3.69	2.13	152.00	1.114	9	1.96	1.96
DB563K-TT w/Mount	0.0000	0.13	0.00	-6.77	157.00	1.124	9	19.19	4.03
Pipe									
2' x 3' sidearm	0.0000	0.19	0.00	-5.27	150.00	1.110	9	1.50	3.00
4' x 4.5" Pipe Mount	240.0000	0.04	-3.69	2.13	152.00	1.114	9	1.19	1.19
QS66512-2 w/ Mount	0.0000	0.14	0.00	-6.78	145.00	1.099	8	8.37	8.46
Pipe									
QS66512-2 w/ Mount	120.0000	0.14	5.87	3.39	145.00	1.099	8	8.37	8.46
Pipe									
QS66512-2 w/ Mount	240.0000	0.14	-5.87	3.39	145.00	1.099	8	8.37	8.46
Pipe									
TMA2117F00V1-1	0.0000	0.04	0.00	-6.78	145.00	1.099	8	0.59	1.67
TMA2117F00V1-1	120.0000	0.04	5.87	3.39	145.00	1.099	8	0.59	1.67
TMA2117F00V1-1	240.0000	0.04	-5.87	3.39	145.00	1.099	8	0.59	1.67
2' x 3' Side Arm Mount	0.0000	0.11	0.00	-5.28	145.00	1.099	8	1.78	2.97
2' x 3' Side Arm Mount	120.0000	0.11	4.57	2.64	145.00	1.099	8	1.78	2.97
2' x 3' Side Arm Mount	240.0000	0.11	-4.57	2.64	145.00	1.099	8	1.78	2.97
4' x 4.5" Pipe Mount	120.0000	0.04	3.71	2.14	140.00	1.088	8	1.19	1.19
6' x 3" Omni	120.0000	0.02	6.13	3.54	138.00	1.083	8	1.77	1.77
2' x 3' Side Arm Mount	120.0000	0.19	4.83	2.79	135.00	1.077	8	1.50	3.00

tnxTower Centerline Engineering Services, PA 750 W Center St, Suite 301 West Bridgewater, MA 02379 Phone: (781) 713-4725 FAX:	Job	Stamford NW CT	Page	29 of 52
	Project	23CLVZ-0009	Date	15:14:50 09/21/23
	Client	Verizon Wireless	Designed by	jboegel

Description	Aiming Azimuth °	Weight K	Offset _x ft	Offset _z ft	z ft	K _z	q _z psf	C _A A _C Front ft ²	C _A A _C Side ft ²
DB254-A	240.0000	0.01	-6.13	3.54	135.00	1.077	8	1.10	1.10
2' x 3' Side Arm Mount	240.0000	0.19	-4.83	2.79	135.00	1.077	8	1.50	3.00
APXVSPP18-C-A20 w/ Mount Pipe	0.0000	0.08	0.00	-8.32	131.00	1.067	8	8.26	6.95
APXVSPP18-C-A20 w/ Mount Pipe	120.0000	0.08	7.20	4.16	131.00	1.067	8	8.26	6.95
APXVSPP18-C-A20 w/ Mount Pipe	240.0000	0.08	-7.20	4.16	131.00	1.067	8	8.26	6.95
RRH2x50-WCS	0.0000	0.08	0.00	-8.32	131.00	1.067	8	4.91	2.70
RRH2x50-WCS	120.0000	0.08	7.20	4.16	131.00	1.067	8	4.91	2.70
RRH2x50-WCS	240.0000	0.08	-7.20	4.16	131.00	1.067	8	4.91	2.70
RRH4X45-19	0.0000	0.06	0.00	-8.32	131.00	1.067	8	2.31	2.38
RRH4X45-19	120.0000	0.06	7.20	4.16	131.00	1.067	8	2.31	2.38
RRH4X45-19	240.0000	0.06	-7.20	4.16	131.00	1.067	8	2.31	2.38
APXVTM14-ALU-I20 w/ Mount Pipe	0.0000	0.08	0.00	-8.32	131.00	1.067	8	6.58	4.96
APXVTM14-ALU-I20 w/ Mount Pipe	120.0000	0.08	7.20	4.16	131.00	1.067	8	6.58	4.96
APXVTM14-ALU-I20 w/ Mount Pipe	240.0000	0.08	-7.20	4.16	131.00	1.067	8	6.58	4.96
TD-RRH8x20	0.0000	0.07	0.00	-8.32	131.00	1.067	8	3.70	1.29
TD-RRH8x20	120.0000	0.07	7.20	4.16	131.00	1.067	8	3.70	1.29
TD-RRH8x20	240.0000	0.07	-7.20	4.16	131.00	1.067	8	3.70	1.29
Sector Frame Mount	0.0000	0.56	0.00	-6.32	131.00	1.067	8	15.35	14.00
Sector Frame Mount	120.0000	0.56	5.47	3.16	131.00	1.067	8	15.35	14.00
Sector Frame Mount	240.0000	0.56	-5.47	3.16	131.00	1.067	8	15.35	14.00
AIR32 KRD901146- 1_B66_B2A w/ Mount Pipe	0.0000	0.11	0.00	-9.25	118.00	1.036	8	11.39	5.90
AIR32 KRD901146- 1_B66_B2A w/ Mount Pipe	120.0000	0.11	8.01	4.63	118.00	1.036	8	11.39	5.90
AIR32 KRD901146- 1_B66_B2A w/ Mount Pipe	240.0000	0.11	-8.01	4.63	118.00	1.036	8	11.39	5.90
AIR6449 B41 w/ Mount Pipe	0.0000	0.13	0.00	-9.25	118.00	1.036	8	6.93	4.39
AIR6449 B41 w/ Mount Pipe	120.0000	0.13	8.01	4.63	118.00	1.036	8	6.93	4.39
AIR6449 B41 w/ Mount Pipe	240.0000	0.13	-8.01	4.63	118.00	1.036	8	6.93	4.39
APXVAARR24_43-U-N A20 w/ Mount Pipe	0.0000	0.16	0.00	-9.25	118.00	1.036	8	20.24	10.79
APXVAARR24_43-U-N A20 w/ Mount Pipe	120.0000	0.16	8.01	4.63	118.00	1.036	8	20.24	10.79
APXVAARR24_43-U-N A20 w/ Mount Pipe	240.0000	0.16	-8.01	4.63	118.00	1.036	8	20.24	10.79
RRUS 11 B4	0.0000	0.05	0.00	-9.25	118.00	1.036	8	2.83	1.18
RRUS 11 B4	120.0000	0.05	8.01	4.63	118.00	1.036	8	2.83	1.18
RRUS 11 B4	240.0000	0.05	-8.01	4.63	118.00	1.036	8	2.83	1.18
RRUS 4415 B25	0.0000	0.04	0.00	-9.25	118.00	1.036	8	1.64	0.68
RRUS 4415 B25	120.0000	0.04	8.01	4.63	118.00	1.036	8	1.64	0.68
RRUS 4415 B25	240.0000	0.04	-8.01	4.63	118.00	1.036	8	1.64	0.68
Sector Frame Mount	0.0000	0.56	0.00	-7.25	115.00	1.028	8	15.35	14.00
Sector Frame Mount	120.0000	0.56	6.28	3.63	115.00	1.028	8	15.35	14.00
Sector Frame Mount	240.0000	0.56	-6.28	3.63	115.00	1.028	8	15.35	14.00
XXDWMM-12.5-65-8T- CBRS w/ Mount Pipe	0.0000	0.05	0.00	-10.25	98.00	0.983	8	3.12	2.65
XXDWMM-12.5-65-8T- CBRS w/ Mount Pipe	120.0000	0.05	8.88	5.13	98.00	0.983	8	3.12	2.65
XXDWMM-12.5-65-8T- CBRS w/ Mount Pipe	240.0000	0.05	-8.88	5.13	98.00	0.983	8	3.12	2.65

tnxTower Centerline Engineering Services, PA 750 W Center St, Suite 301 West Bridgewater, MA 02379 Phone: (781) 713-4725 FAX:	Job	Stamford NW CT	Page	31 of 52
	Project	23CLVZ-0009	Date	15:14:50 09/21/23
	Client	Verizon Wireless	Designed by	jboegel

Dish Pressures - No Ice

Elevation ft	Dish Description	Aiming Azimuth °	Weight K	Offset _x ft	Offset _z ft	K _z	A _A ft ²	q _z psf
152.00	4' HP MW	240.0000	0.12	-4.13	2.38	1.114	12.57	30
140.00	4' HP MW	120.0000	0.12	4.15	2.39	1.088	12.57	30
	Sum Weight:		0.24					

Dish Pressures - With Ice

Elevation ft	Dish Description	Aiming Azimuth °	Weight K	Offset _x ft	Offset _z ft	K _z	A _A ft ²	q _z psf	t _z in
152.00	4' HP MW	240.0000	0.26	-4.13	2.38	1.114	13.62	6	0.9903
140.00	4' HP MW	120.0000	0.26	4.15	2.39	1.088	13.61	6	0.9822
	Sum Weight:		0.52						

Dish Pressures - Service

Elevation ft	Dish Description	Aiming Azimuth °	Weight K	Offset _x ft	Offset _z ft	K _z	A _A ft ²	q _z psf
152.00	4' HP MW	240.0000	0.12	-4.13	2.38	1.114	12.57	9
140.00	4' HP MW	120.0000	0.12	4.15	2.39	1.088	12.57	8
	Sum Weight:		0.24					

Force Totals

Load Case	Vertical Forces K	Sum of Forces X K	Sum of Forces Z K	Sum of Overturning Moments, M _x kip-ft	Sum of Overturning Moments, M _z kip-ft	Sum of Torques kip-ft
Leg Weight	6.06					
Bracing Weight	11.44					
Total Member Self-Weight	17.50			4.93	-0.35	
Total Weight	35.38			4.93	-0.35	
Wind 0 deg - No Ice		-0.02	-32.33	-2769.46	-1.75	5.48
Wind 30 deg - No Ice		16.22	-28.14	-2424.58	-1399.75	17.54
Wind 60 deg - No Ice		27.93	-16.17	-1399.79	-2417.00	8.68
Wind 90 deg - No Ice		31.28	-0.00	1.29	-2704.86	-4.91
Wind 120 deg - No Ice		27.46	15.83	1357.58	-2350.83	0.88
Wind 150 deg - No Ice		13.48	23.54	2077.89	-1177.81	12.38
Wind 180 deg - No Ice		0.02	30.23	2648.70	-0.13	-5.48
Wind 210 deg - No Ice		-16.09	28.11	2430.52	1381.18	-17.48
Wind 240 deg - No Ice		-29.70	17.10	1458.29	2521.77	-8.43
Wind 270 deg - No Ice		-31.28	-0.05	1.40	2702.93	4.91
Wind 300 deg - No Ice		-25.68	-14.90	-1299.36	2242.78	-1.13
Wind 330 deg - No Ice		-13.60	-23.56	-2070.53	1194.99	-12.43
Member Ice	14.24					
Total Weight Ice	73.12			10.22	-13.27	

tnxTower Centerline Engineering Services, PA 750 W Center St, Suite 301 West Bridgewater, MA 02379 Phone: (781) 713-4725 FAX:	Job	Stamford NW CT	Page	32 of 52
	Project	23CLVZ-0009	Date	15:14:50 09/21/23
	Client	Verizon Wireless	Designed by	jboegel

Load Case	Vertical Forces K	Sum of Forces X K	Sum of Forces Z K	Sum of Overturning Moments, M_x kip-ft	Sum of Overturning Moments, M_z kip-ft	Sum of Torques kip-ft
Wind 0 deg - Ice		-0.00	-8.85	-758.41	-13.58	0.54
Wind 30 deg - Ice		4.48	-7.75	-665.15	-404.50	4.46
Wind 60 deg - Ice		7.97	-4.60	-390.94	-708.14	2.76
Wind 90 deg - Ice		8.62	-0.00	9.46	-768.81	-0.46
Wind 120 deg - Ice		7.39	4.25	379.90	-658.49	0.82
Wind 150 deg - Ice		3.85	6.69	603.40	-353.78	3.50
Wind 180 deg - Ice		0.00	8.50	757.20	-13.20	-0.54
Wind 210 deg - Ice		-4.46	7.75	684.81	374.36	-4.44
Wind 240 deg - Ice		-8.27	4.75	418.86	698.81	-2.71
Wind 270 deg - Ice		-8.62	-0.01	9.54	742.01	0.46
Wind 300 deg - Ice		-7.09	-4.09	-352.03	614.36	-0.87
Wind 330 deg - Ice		-3.88	-6.70	-583.46	330.83	-3.51
Total Weight	35.38			4.93	-0.35	
Wind 0 deg - Service		-0.01	-9.11	-776.83	5.65	1.54
Wind 30 deg - Service		4.57	-7.93	-679.70	-388.08	4.94
Wind 60 deg - Service		7.87	-4.55	-391.08	-674.57	2.44
Wind 90 deg - Service		8.81	-0.00	3.51	-755.64	-1.38
Wind 120 deg - Service		7.73	4.46	385.49	-655.93	0.25
Wind 150 deg - Service		3.80	6.63	588.35	-325.57	3.49
Wind 180 deg - Service		0.01	8.52	749.11	6.10	-1.54
Wind 210 deg - Service		-4.53	7.92	687.66	395.13	-4.92
Wind 240 deg - Service		-8.37	4.82	413.85	716.35	-2.37
Wind 270 deg - Service		-8.81	-0.01	3.54	767.38	1.38
Wind 300 deg - Service		-7.23	-4.20	-362.80	637.79	-0.32
Wind 330 deg - Service		-3.83	-6.64	-579.99	342.69	-3.50

Load Combinations

Comb. No.	Description
1	Dead Only
2	1.2 Dead+1.0 Wind 0 deg - No Ice
3	0.9 Dead+1.0 Wind 0 deg - No Ice
4	1.2 Dead+1.0 Wind 30 deg - No Ice
5	0.9 Dead+1.0 Wind 30 deg - No Ice
6	1.2 Dead+1.0 Wind 60 deg - No Ice
7	0.9 Dead+1.0 Wind 60 deg - No Ice
8	1.2 Dead+1.0 Wind 90 deg - No Ice
9	0.9 Dead+1.0 Wind 90 deg - No Ice
10	1.2 Dead+1.0 Wind 120 deg - No Ice
11	0.9 Dead+1.0 Wind 120 deg - No Ice
12	1.2 Dead+1.0 Wind 150 deg - No Ice
13	0.9 Dead+1.0 Wind 150 deg - No Ice
14	1.2 Dead+1.0 Wind 180 deg - No Ice
15	0.9 Dead+1.0 Wind 180 deg - No Ice
16	1.2 Dead+1.0 Wind 210 deg - No Ice
17	0.9 Dead+1.0 Wind 210 deg - No Ice
18	1.2 Dead+1.0 Wind 240 deg - No Ice
19	0.9 Dead+1.0 Wind 240 deg - No Ice
20	1.2 Dead+1.0 Wind 270 deg - No Ice
21	0.9 Dead+1.0 Wind 270 deg - No Ice
22	1.2 Dead+1.0 Wind 300 deg - No Ice
23	0.9 Dead+1.0 Wind 300 deg - No Ice
24	1.2 Dead+1.0 Wind 330 deg - No Ice
25	0.9 Dead+1.0 Wind 330 deg - No Ice
26	1.2 Dead+1.0 Ice+1.0 Temp

tnxTower Centerline Engineering Services, PA 750 W Center St, Suite 301 West Bridgewater, MA 02379 Phone: (781) 713-4725 FAX:	Job	Stamford NW CT	Page	33 of 52
	Project	23CLVZ-0009	Date	15:14:50 09/21/23
	Client	Verizon Wireless	Designed by	jboegel

Comb. No.	Description
27	1.2 Dead+1.0 Wind 0 deg+1.0 Ice+1.0 Temp
28	1.2 Dead+1.0 Wind 30 deg+1.0 Ice+1.0 Temp
29	1.2 Dead+1.0 Wind 60 deg+1.0 Ice+1.0 Temp
30	1.2 Dead+1.0 Wind 90 deg+1.0 Ice+1.0 Temp
31	1.2 Dead+1.0 Wind 120 deg+1.0 Ice+1.0 Temp
32	1.2 Dead+1.0 Wind 150 deg+1.0 Ice+1.0 Temp
33	1.2 Dead+1.0 Wind 180 deg+1.0 Ice+1.0 Temp
34	1.2 Dead+1.0 Wind 210 deg+1.0 Ice+1.0 Temp
35	1.2 Dead+1.0 Wind 240 deg+1.0 Ice+1.0 Temp
36	1.2 Dead+1.0 Wind 270 deg+1.0 Ice+1.0 Temp
37	1.2 Dead+1.0 Wind 300 deg+1.0 Ice+1.0 Temp
38	1.2 Dead+1.0 Wind 330 deg+1.0 Ice+1.0 Temp
39	Dead+Wind 0 deg - Service
40	Dead+Wind 30 deg - Service
41	Dead+Wind 60 deg - Service
42	Dead+Wind 90 deg - Service
43	Dead+Wind 120 deg - Service
44	Dead+Wind 150 deg - Service
45	Dead+Wind 180 deg - Service
46	Dead+Wind 210 deg - Service
47	Dead+Wind 240 deg - Service
48	Dead+Wind 270 deg - Service
49	Dead+Wind 300 deg - Service
50	Dead+Wind 330 deg - Service

Maximum Member Forces

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Axial K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
T1	152 - 140	Leg	Max Tension	15	2.72	-0.07	0.00
			Max. Compression	2	-4.58	-0.00	0.00
			Max. Mx	14	0.51	0.13	0.00
			Max. My	24	0.67	-0.08	0.13
			Max. Vy	6	-0.25	0.00	0.00
		Diagonal	Max. Vx	12	-0.34	0.00	0.00
			Max Tension	5	1.13	0.00	0.00
			Max. Compression	4	-1.15	0.00	0.00
			Max. Mx	27	0.23	0.01	-0.00
			Max. My	12	0.13	0.00	-0.00
			Max. Vy	27	-0.01	0.01	-0.00
		Top Girt	Max. Vx	12	0.00	0.00	0.00
			Max Tension	18	0.09	0.00	0.00
			Max. Compression	7	-0.10	0.00	0.00
			Max. Mx	26	0.00	-0.04	0.00
			Max. My	26	0.00	0.00	0.00
T2	140 - 135	Leg	Max. Vy	26	-0.02	0.00	0.00
			Max. Vx	26	-0.00	0.00	0.00
			Max Tension	15	4.74	0.02	-0.00
			Max. Compression	2	-6.87	0.12	-0.01
			Max. Mx	22	3.88	-0.14	-0.01
		Diagonal	Max. My	4	-0.65	-0.01	-0.17
			Max. Vy	22	-0.14	0.02	-0.00
			Max. Vx	16	0.18	0.01	-0.02
			Max Tension	21	1.07	0.00	0.00
			Max. Compression	20	-1.11	0.00	0.00
			Max. Mx	28	0.15	0.01	0.00
			Max. My	29	-0.29	0.01	0.00
			Max. Vy	28	0.01	0.01	0.00

tnxTower Centerline Engineering Services, PA 750 W Center St, Suite 301 West Bridgewater, MA 02379 Phone: (781) 713-4725 FAX:	Job	Stamford NW CT	Page	34 of 52
	Project	23CLVZ-0009	Date	15:14:50 09/21/23
	Client	Verizon Wireless	Designed by	jboegel

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Axial K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
T3	135 - 130	Top Girt	Max. Vx	29	-0.00	0.00	0.00
			Max. Tension	14	0.03	0.00	0.00
			Max. Compression	3	-0.04	0.00	0.00
			Max. Mx	26	-0.02	-0.04	0.00
			Max. My	26	-0.01	0.00	0.00
			Max. Vy	26	0.02	0.00	0.00
			Max. Vx	26	0.00	0.00	0.00
			Max. Tension	15	7.10	-0.14	0.01
			Max. Compression	2	-10.73	0.28	-0.01
			Max. Mx	22	4.79	0.35	-0.00
			Max. My	20	-2.15	-0.02	0.34
			Max. Vy	22	0.68	-0.32	-0.00
		Diagonal	Max. Vx	16	-0.63	-0.02	0.28
			Max. Tension	6	1.52	0.00	0.00
			Max. Compression	18	-1.56	0.00	0.00
			Max. Mx	28	0.34	0.01	-0.00
			Max. My	38	0.34	0.01	0.00
			Max. Vy	28	0.01	0.01	-0.00
T4	130 - 125	Leg	Max. Vx	38	-0.00	0.00	0.00
			Max. Tension	15	9.78	-0.31	0.01
			Max. Compression	2	-14.44	-0.10	-0.01
			Max. Mx	14	9.18	-0.32	0.01
			Max. My	16	-2.87	-0.02	0.28
			Max. Vy	22	-0.11	-0.32	-0.00
		Diagonal	Max. Vx	16	0.11	-0.02	0.28
			Max. Tension	7	2.34	0.00	0.00
			Max. Compression	18	-2.45	0.00	0.00
			Max. Mx	29	0.58	0.02	0.00
			Max. My	27	-0.65	0.01	-0.00
			Max. Vy	29	0.02	0.02	0.00
		Leg	Max. Vx	27	0.00	0.00	0.00
			Max. Tension	7	14.05	0.13	-0.00
			Max. Compression	2	-19.29	0.35	0.01
			Max. Mx	6	13.36	-0.40	-0.01
			Max. My	12	-3.40	-0.03	-0.46
			Max. Vy	6	0.13	-0.40	-0.01
T5	125 - 120	Diagonal	Max. Vx	16	-0.14	-0.03	0.44
			Max. Tension	18	2.32	0.00	0.00
			Max. Compression	7	-2.20	0.00	0.00
			Max. Mx	27	0.64	0.02	-0.00
			Max. My	34	-0.41	0.02	0.00
			Max. Vy	29	0.02	0.02	-0.00
		Leg	Max. Vx	34	-0.00	0.00	0.00
			Max. Tension	7	33.13	0.13	-0.01
			Max. Compression	18	-42.69	0.17	0.01
			Max. Mx	6	16.75	0.93	-0.01
			Max. My	12	-5.32	-0.05	0.99
			Max. Vy	6	0.97	-0.67	-0.01
		Diagonal	Max. Vx	24	-0.97	-0.05	0.61
			Max. Tension	8	4.11	0.00	0.00
			Max. Compression	8	-4.10	0.00	0.00
			Max. Mx	35	1.11	0.04	-0.01
			Max. My	20	-4.07	0.00	0.01
			Max. Vy	34	0.03	0.03	0.01
T6	120 - 100	Leg	Max. Vx	32	0.00	0.00	0.00
			Max. Tension	7	56.11	0.12	-0.00
			Max. Compression	18	-70.80	-0.27	0.00
			Max. Mx	18	-52.24	0.37	0.00
			Max. My	16	-5.63	-0.02	-0.42
			Max. Vy	6	0.56	-0.35	-0.00
		Diagonal	Max. Vx	16	-0.46	0.01	0.13

tnxTower Centerline Engineering Services, PA 750 W Center St, Suite 301 West Bridgewater, MA 02379 Phone: (781) 713-4725 FAX:	Job	Stamford NW CT	Page	35 of 52
	Project	23CLVZ-0009	Date	15:14:50 09/21/23
	Client	Verizon Wireless	Designed by	jboegel

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Axial K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
T8	80 - 73.3333	Diagonal	Max Tension	8	4.83	0.00	0.00
			Max. Compression	18	-5.07	0.00	0.00
			Max. Mx	35	1.17	0.07	-0.01
			Max. My	18	-4.93	0.00	0.01
			Max. Vy	29	0.04	0.07	-0.01
			Max. Vx	35	0.00	0.00	0.00
		Secondary Horizontal	Max Tension	7	0.59	0.00	0.00
			Max. Compression	18	-0.63	0.02	0.01
			Max. Mx	33	-0.00	0.06	0.01
			Max. My	29	-0.00	0.06	0.01
			Max. Vy	33	-0.04	0.06	0.01
			Max. Vx	29	0.00	0.00	0.00
		Leg	Max Tension	7	64.21	0.17	-0.00
			Max. Compression	18	-80.30	-0.26	0.01
			Max. Mx	18	-79.89	0.48	0.00
			Max. My	4	-7.95	-0.05	-0.25
			Max. Vy	18	-0.25	0.48	0.00
			Max. Vx	25	-0.20	-0.04	0.23
		Diagonal	Max Tension	21	4.96	0.04	-0.00
			Max. Compression	8	-5.09	0.00	0.00
			Max. Mx	35	1.59	0.06	-0.01
			Max. My	34	1.60	0.06	0.01
			Max. Vy	29	0.04	0.06	-0.01
			Max. Vx	34	-0.00	0.00	0.00
		Secondary Horizontal	Max Tension	4	0.33	0.00	0.00
			Max. Compression	5	-0.26	0.00	0.00
			Max. Mx	35	0.10	0.05	0.01
			Max. My	29	0.02	0.04	0.01
			Max. Vy	35	-0.04	0.05	0.01
			Max. Vx	29	0.00	0.00	0.00
T9	73.3333 - 66.6667	Leg	Max Tension	7	71.71	0.16	-0.00
			Max. Compression	18	-88.95	-0.37	0.00
			Max. Mx	18	-88.90	0.51	0.00
			Max. My	16	-9.17	-0.07	0.31
			Max. Vy	18	0.27	0.51	0.00
			Max. Vx	16	-0.14	-0.07	0.31
		Diagonal	Max Tension	8	5.02	0.00	0.00
			Max. Compression	18	-5.41	0.00	0.00
			Max. Mx	35	1.12	0.09	-0.01
			Max. My	35	-2.00	0.08	0.01
			Max. Vy	33	0.05	0.09	-0.01
			Max. Vx	35	0.00	0.00	0.00
		Secondary Horizontal	Max Tension	16	0.36	0.03	0.00
			Max. Compression	5	-0.29	0.00	0.00
			Max. Mx	33	-0.01	0.07	0.01
			Max. My	34	-0.03	0.07	0.01
			Max. Vy	33	-0.04	0.07	0.01
			Max. Vx	34	-0.00	0.00	0.00
T10	66.6667 - 60	Leg	Max Tension	7	79.41	0.24	-0.00
			Max. Compression	18	-97.87	-0.44	0.01
			Max. Mx	18	-97.83	0.58	-0.00
			Max. My	5	-6.67	-0.06	-0.33
			Max. Vy	18	0.31	0.58	-0.00
			Max. Vx	5	0.15	-0.06	-0.33
		Diagonal	Max Tension	8	5.17	0.00	0.00
			Max. Compression	18	-5.33	0.00	0.00
			Max. Mx	35	1.83	0.07	-0.01

tnxTower Centerline Engineering Services, PA 750 W Center St, Suite 301 West Bridgewater, MA 02379 Phone: (781) 713-4725 FAX:	Job	Stamford NW CT	Page	36 of 52
	Project	23CLVZ-0009	Date	15:14:50 09/21/23
	Client	Verizon Wireless	Designed by	jboegel

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Axial K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
T11	60 - 50	Secondary Horizontal	Max. My	32	-0.66	0.06	-0.01
			Max. Vy	29	0.05	0.07	-0.01
			Max. Vx	32	-0.00	0.00	0.00
			Max Tension	16	0.43	0.03	0.00
		Leg	Max. Compression	5	-0.35	0.00	0.00
			Max. Mx	35	0.11	0.05	0.01
			Max. My	29	0.02	0.05	0.01
			Max. Vy	35	-0.04	0.05	0.01
			Max. Vx	29	0.00	0.00	0.00
			Max Tension	7	88.55	0.29	-0.01
			Max. Compression	18	-108.55	-0.77	0.01
			Max. Mx	18	-108.47	1.02	0.00
			Max. My	16	-10.36	-0.16	0.86
			Max. Vy	18	0.37	1.02	0.00
			Max. Vx	16	-0.25	-0.16	0.86
		Diagonal	Max Tension	9	5.80	0.07	-0.00
			Max. Compression	18	-6.21	0.00	0.00
			Max. Mx	35	1.03	0.13	0.01
			Max. My	18	-6.18	0.01	0.02
		Secondary Horizontal	Max. Vy	29	0.06	0.13	-0.01
			Max. Vx	35	0.00	0.00	0.00
			Max Tension	4	0.49	0.00	0.00
			Max. Compression	17	-0.41	0.03	0.01
T12	50 - 40	Leg	Max. Mx	34	-0.04	0.08	0.01
			Max. My	29	-0.02	0.08	0.01
			Max. Vy	34	-0.05	0.08	0.01
			Max. Vx	29	0.00	0.00	0.00
			Max Tension	7	99.31	0.49	-0.01
		Diagonal	Max. Compression	18	-121.11	-0.63	0.01
			Max. Mx	18	-121.03	1.11	0.00
			Max. My	16	-10.82	-0.16	0.86
			Max. Vy	18	-0.41	1.11	0.00
			Max. Vx	16	0.26	-0.16	0.86
			Max Tension	9	5.83	0.10	0.01
			Max. Compression	18	-6.42	0.00	0.00
			Max. Mx	18	5.48	0.14	-0.02
			Max. My	18	5.03	0.14	0.02
			Max. Vy	29	0.07	0.12	0.01
			Max. Vx	35	-0.00	0.00	0.00
		Secondary Horizontal	Max Tension	16	0.55	0.06	0.00
			Max. Compression	5	-0.46	0.00	0.00
			Max. Mx	34	0.20	0.08	0.02
			Max. My	6	-0.34	0.05	0.02
T13	40 - 30	Leg	Max. Vy	34	-0.06	0.08	0.02
			Max. Vx	29	0.00	0.00	0.00
			Max Tension	7	109.92	0.46	-0.01
			Max. Compression	18	-133.70	-1.62	-0.01
		Diagonal	Max. Mx	18	-133.70	-1.62	-0.01
			Max. My	16	-12.03	-0.23	0.73
			Max. Vy	18	0.59	1.29	0.00
			Max. Vx	16	-0.22	-0.23	0.73
			Max Tension	9	6.04	0.11	0.00
			Max. Compression	18	-6.49	0.00	0.00
			Max. Mx	29	0.82	0.20	-0.02
			Max. My	35	-2.57	0.17	0.02
			Max. Vy	29	0.08	0.20	-0.02
			Max. Vx	35	0.00	0.00	0.00
		Secondary	Max Tension	16	0.65	0.05	0.00

tnxTower Centerline Engineering Services, PA 750 W Center St, Suite 301 West Bridgewater, MA 02379 Phone: (781) 713-4725 FAX:	Job	Stamford NW CT	Page	37 of 52
	Project	23CLVZ-0009	Date	15:14:50 09/21/23
	Client	Verizon Wireless	Designed by	jboegel

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Axial K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
T14	30 - 20	Horizontal	Max. Compression	5	-0.55	0.00	0.00
			Max. Mx	34	-0.11	0.13	0.02
			Max. My	29	-0.09	0.13	0.02
		Leg	Max. Vy	34	-0.06	0.13	0.02
			Max. Vx	29	0.00	0.00	0.00
			Max Tension	7	119.66	1.19	0.01
		Diagonal	Max. Compression	18	-145.45	1.35	-0.02
			Max. Mx	35	-60.88	-2.45	0.00
			Max. My	16	-12.48	-0.23	0.73
		Horizontal	Max. Vy	18	-1.46	2.01	0.02
			Max. Vx	4	0.26	-0.19	-0.32
			Max Tension	7	6.64	0.05	0.00
		Redund Horiz 1 Bracing	Max. Compression	18	-7.51	0.00	0.00
			Max. Mx	18	5.73	0.12	-0.00
			Max. My	35	0.68	0.04	-0.01
		Redund Diag 1 Bracing	Max. Vy	35	0.04	0.08	-0.01
			Max. Vx	29	-0.00	0.00	0.00
			Max Tension	16	0.43	0.07	0.03
		Leg	Max. Compression	5	-0.38	0.00	0.00
			Max. Mx	29	0.24	0.09	0.06
			Max. My	29	0.25	0.09	0.06
		Diagonal	Max. Vy	29	-0.06	0.09	0.06
			Max. Vx	29	-0.01	0.00	0.00
			Max Tension	18	1.46	0.00	0.00
		Redund Horiz 1 Bracing	Max. Compression	7	-1.19	0.00	0.00
			Max. Mx	26	0.04	-0.02	0.00
			Max. My	26	0.70	0.00	0.00
		Redund Diag 1 Bracing	Max. Vy	26	0.02	0.00	0.00
			Max. Vx	26	-0.00	0.00	0.00
			Max Tension	7	0.68	0.00	0.00
T15	20 - 15	Horizontal	Max. Compression	18	-0.97	0.00	0.00
			Max. Mx	26	-0.14	-0.02	0.00
			Max. My	26	-0.15	0.00	0.00
		Leg	Max. Vy	26	0.02	0.00	0.00
			Max. Vx	26	-0.00	0.00	0.00
			Max Tension	7	129.58	1.81	-0.01
		Diagonal	Max. Compression	18	-157.37	2.72	0.03
			Max. Mx	18	-157.37	2.72	0.03
			Max. My	5	-9.50	0.05	0.47
		Redund Horiz 1 Bracing	Max. Vy	18	-1.99	2.72	0.03
			Max. Vx	4	-0.38	0.17	-0.42
			Max Tension	18	6.11	0.15	-0.00
		Redund Diag 1 Bracing	Max. Compression	19	-6.15	0.00	0.00
			Max. Mx	18	6.11	0.15	-0.00
			Max. My	35	-0.81	0.03	-0.01
		Leg	Max. Vy	18	0.05	0.15	-0.00
			Max. Vx	35	0.00	0.00	0.00
			Max Tension	18	1.77	0.00	0.00
		Diagonal	Max. Compression	7	-1.51	0.00	0.00
			Max. Mx	26	0.69	-0.02	0.00
			Max. My	26	0.69	0.00	0.00
		Redund Horiz 1 Bracing	Max. Vy	26	0.02	0.00	0.00
			Max. Vx	26	0.00	0.00	0.00
			Max Tension	7	0.87	0.00	0.00
		Redund Diag 1 Bracing	Max. Compression	18	-1.16	0.00	0.00
			Max. Mx	26	-0.52	-0.03	0.00

tnxTower Centerline Engineering Services, PA 750 W Center St, Suite 301 West Bridgewater, MA 02379 Phone: (781) 713-4725 FAX:	Job	Stamford NW CT	Page	38 of 52
	Project	23CLVZ-0009	Date	15:14:50 09/21/23
	Client	Verizon Wireless	Designed by	jboegel

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Axial K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
T16	15 - 9.99999	Leg	Max. My	26	-0.52	0.00	-0.00
			Max. Vy	26	0.02	0.00	0.00
			Max. Vx	26	0.00	0.00	0.00
			Max Tension	7	130.11	-0.11	0.02
			Max. Compression	18	-158.54	0.13	0.02
			Max. Mx	35	-64.72	0.95	0.00
		Diagonal	Max. My	5	-9.77	-0.08	-1.21
			Max. Vy	33	-0.25	-0.35	-0.00
			Max. Vx	5	0.39	-0.08	-1.21
			Max Tension	19	5.96	0.00	0.00
			Max. Compression	18	-6.34	0.00	0.00
			Max. Mx	26	-1.26	-0.17	0.00
		Horizontal	Max. My	26	-1.27	0.00	-0.01
			Max. Vy	26	-0.06	0.00	0.00
			Max. Vx	26	0.00	0.00	0.00
			Max Tension	6	0.61	0.06	0.03
			Max. Compression	19	-0.44	0.00	0.00
			Max. Mx	35	-0.00	0.16	0.06
T17	9.99999 - 0	Leg	Max. My	38	0.05	0.16	0.06
			Max. Vy	35	0.07	0.16	0.06
			Max. Vx	35	-0.01	0.00	0.00
			Max Tension	7	139.68	-0.28	-0.02
			Max. Compression	18	-170.03	0.00	0.00
			Max. Mx	35	-70.82	0.95	0.00
		Diagonal	Max. My	5	-10.13	-0.08	-1.21
			Max. Vy	22	-0.11	-0.30	-0.01
			Max. Vx	5	-0.22	-0.08	-1.21
			Max Tension	20	6.65	0.00	0.00
			Max. Compression	18	-7.23	0.00	0.00
			Max. Mx	18	5.87	0.19	0.03
			Max. My	34	3.16	0.14	0.03
			Max. Vy	34	0.08	0.14	0.03
			Max. Vx	34	-0.00	0.00	0.00

Maximum Reactions

Location	Condition	Gov. Load Comb.	Vertical K	Horizontal, X K	Horizontal, Z K
Leg C	Max. Vert	18	176.03	18.35	-10.31
	Max. H _x	18	176.03	18.35	-10.31
	Max. H _z	7	-144.59	-15.68	8.78
	Min. Vert	7	-144.59	-15.68	8.78
	Min. H _x	7	-144.59	-15.68	8.78
	Min. H _z	18	176.03	18.35	-10.31
Leg B	Max. Vert	10	165.01	-16.97	-9.76
	Max. H _x	23	-133.42	14.29	8.22
	Max. H _z	23	-133.42	14.29	8.22
	Min. Vert	23	-133.42	14.29	8.22
	Min. H _x	10	165.01	-16.97	-9.76
	Min. H _z	10	165.01	-16.97	-9.76
Leg A	Max. Vert	2	167.97	0.16	19.94
	Max. H _x	20	14.02	2.76	1.14
	Max. H _z	2	167.97	0.16	19.94
	Min. Vert	15	-136.53	-0.16	-16.81
	Min. H _x	9	10.57	-2.76	0.84
	Min. H _z	15	-136.53	-0.16	-16.81

tnxTower Centerline Engineering Services, PA 750 W Center St, Suite 301 West Bridgewater, MA 02379 Phone: (781) 713-4725 FAX:	Job	Stamford NW CT	Page	39 of 52
	Project	23CLVZ-0009	Date	15:14:50 09/21/23
	Client	Verizon Wireless	Designed by	jboegel

Location	Condition	Gov. Load Comb.	Vertical K	Horizontal, X K	Horizontal, Z K
----------	-----------	-----------------------	---------------	--------------------	--------------------

Tower Mast Reaction Summary

Load Combination	Vertical K	Shear _x K	Shear _y K	Overturning Moment, M _x kip-ft	Overturning Moment, M _y kip-ft	Torque kip-ft
Dead Only	35.38	0.00	0.00	4.93	-0.35	0.00
1.2 Dead+1.0 Wind 0 deg - No Ice	42.46	-0.02	-32.33	-2768.16	-1.82	5.48
0.9 Dead+1.0 Wind 0 deg - No Ice	31.84	-0.02	-32.33	-2769.64	-1.71	5.48
1.2 Dead+1.0 Wind 30 deg - No Ice	42.46	16.22	-28.14	-2423.39	-1399.70	17.54
0.9 Dead+1.0 Wind 30 deg - No Ice	31.84	16.22	-28.14	-2424.87	-1399.60	17.54
1.2 Dead+1.0 Wind 60 deg - No Ice	42.46	27.93	-16.17	-1398.70	-2416.88	8.68
0.9 Dead+1.0 Wind 60 deg - No Ice	31.84	27.93	-16.17	-1400.18	-2416.78	8.68
1.2 Dead+1.0 Wind 90 deg - No Ice	42.46	31.28	-0.00	2.28	-2704.69	-4.91
0.9 Dead+1.0 Wind 90 deg - No Ice	31.84	31.28	-0.00	0.80	-2704.59	-4.91
1.2 Dead+1.0 Wind 120 deg - No Ice	42.46	27.46	15.83	1358.41	-2350.62	0.88
0.9 Dead+1.0 Wind 120 deg - No Ice	31.84	27.46	15.83	1356.93	-2350.52	0.88
1.2 Dead+1.0 Wind 150 deg - No Ice	42.46	13.48	23.54	2078.66	-1177.76	12.38
0.9 Dead+1.0 Wind 150 deg - No Ice	31.84	13.48	23.54	2077.19	-1177.66	12.38
1.2 Dead+1.0 Wind 180 deg - No Ice	42.46	0.02	30.23	2649.47	-0.20	-5.48
0.9 Dead+1.0 Wind 180 deg - No Ice	31.84	0.02	30.23	2647.99	-0.10	-5.48
1.2 Dead+1.0 Wind 210 deg - No Ice	42.46	-16.09	28.11	2431.30	1380.99	-17.48
0.9 Dead+1.0 Wind 210 deg - No Ice	31.84	-16.09	28.11	2429.82	1381.09	-17.48
1.2 Dead+1.0 Wind 240 deg - No Ice	42.46	-29.70	17.10	1459.12	2521.42	-8.43
0.9 Dead+1.0 Wind 240 deg - No Ice	31.84	-29.70	17.10	1457.64	2521.53	-8.43
1.2 Dead+1.0 Wind 270 deg - No Ice	42.46	-31.28	-0.05	2.39	2702.62	4.91
0.9 Dead+1.0 Wind 270 deg - No Ice	31.84	-31.28	-0.05	0.91	2702.72	4.91
1.2 Dead+1.0 Wind 300 deg - No Ice	42.46	-25.68	-14.90	-1298.26	2242.52	-1.13
0.9 Dead+1.0 Wind 300 deg - No Ice	31.84	-25.68	-14.90	-1299.74	2242.63	-1.13
1.2 Dead+1.0 Wind 330 deg - No Ice	42.46	-13.60	-23.56	-2069.33	1194.80	-12.43
0.9 Dead+1.0 Wind 330 deg - No Ice	31.84	-13.60	-23.56	-2070.81	1194.90	-12.43
1.2 Dead+1.0 Ice+1.0 Temp	80.19	0.00	0.00	11.21	-13.34	0.00
1.2 Dead+1.0 Wind 0 deg+1.0	80.19	-0.00	-8.85	-757.37	-13.66	0.54

tnxTower Centerline Engineering Services, PA 750 W Center St, Suite 301 West Bridgewater, MA 02379 Phone: (781) 713-4725 FAX:	Job	Stamford NW CT	Page	40 of 52
	Project	23CLVZ-0009	Date	15:14:50 09/21/23
	Client	Verizon Wireless	Designed by	jboegel

Load Combination	Vertical K	Shear _x K	Shear _z K	Overturning Moment, M _x kip-ft	Overturning Moment, M _z kip-ft	Torque kip-ft
Ice+1.0 Temp						
1.2 Dead+1.0 Wind 30 deg+1.0	80.19	4.48	-7.75	-664.13	-404.55	4.46
Ice+1.0 Temp						
1.2 Dead+1.0 Wind 60 deg+1.0	80.19	7.97	-4.60	-389.93	-708.18	2.76
Ice+1.0 Temp						
1.2 Dead+1.0 Wind 90 deg+1.0	80.19	8.62	-0.00	10.45	-768.83	-0.46
Ice+1.0 Temp						
1.2 Dead+1.0 Wind 120	80.19	7.39	4.25	380.85	-658.52	0.82
deg+1.0 Ice+1.0 Temp						
1.2 Dead+1.0 Wind 150	80.19	3.85	6.69	604.35	-353.83	3.50
deg+1.0 Ice+1.0 Temp						
1.2 Dead+1.0 Wind 180	80.19	0.00	8.50	758.15	-13.27	-0.54
deg+1.0 Ice+1.0 Temp						
1.2 Dead+1.0 Wind 210	80.19	-4.46	7.75	685.75	374.27	-4.44
deg+1.0 Ice+1.0 Temp						
1.2 Dead+1.0 Wind 240	80.19	-8.27	4.75	419.81	698.68	-2.71
deg+1.0 Ice+1.0 Temp						
1.2 Dead+1.0 Wind 270	80.19	-8.62	-0.01	10.53	741.90	0.46
deg+1.0 Ice+1.0 Temp						
1.2 Dead+1.0 Wind 300	80.19	-7.09	-4.09	-351.03	614.25	-0.87
deg+1.0 Ice+1.0 Temp						
1.2 Dead+1.0 Wind 330	80.19	-3.88	-6.70	-582.44	330.74	-3.51
deg+1.0 Ice+1.0 Temp						
Dead+Wind 0 deg - Service	35.38	-0.01	-9.11	-776.35	-0.74	1.54
Dead+Wind 30 deg - Service	35.38	4.57	-7.93	-679.25	-394.44	4.94
Dead+Wind 60 deg - Service	35.38	7.87	-4.55	-390.66	-680.91	2.44
Dead+Wind 90 deg - Service	35.38	8.81	-0.00	3.91	-761.97	-1.38
Dead+Wind 120 deg - Service	35.38	7.73	4.46	385.84	-662.25	0.25
Dead+Wind 150 deg - Service	35.38	3.80	6.63	588.69	-331.93	3.49
Dead+Wind 180 deg - Service	35.38	0.01	8.52	749.45	-0.29	-1.54
Dead+Wind 210 deg - Service	35.38	-4.53	7.92	688.00	388.70	-4.92
Dead+Wind 240 deg - Service	35.38	-8.37	4.82	414.20	709.89	-2.37
Dead+Wind 270 deg - Service	35.38	-8.81	-0.01	3.94	760.92	1.38
Dead+Wind 300 deg - Service	35.38	-7.23	-4.20	-362.37	631.35	-0.32
Dead+Wind 330 deg - Service	35.38	-3.83	-6.64	-579.54	336.27	-3.50

Solution Summary

Load Comb.	Sum of Applied Forces			Sum of Reactions			% Error
	PX K	PY K	PZ K	PX K	PY K	PZ K	
1	0.00	-35.38	0.00	0.00	35.38	0.00	0.000%
2	-0.02	-42.46	-32.33	0.02	42.46	32.33	0.000%
3	-0.02	-31.84	-32.33	0.02	31.84	32.33	0.000%
4	16.22	-42.46	-28.14	-16.22	42.46	28.14	0.000%
5	16.22	-31.84	-28.14	-16.22	31.84	28.14	0.000%
6	27.93	-42.46	-16.17	-27.93	42.46	16.17	0.000%
7	27.93	-31.84	-16.17	-27.93	31.84	16.17	0.000%
8	31.28	-42.46	-0.00	-31.28	42.46	0.00	0.000%
9	31.28	-31.84	-0.00	-31.28	31.84	0.00	0.000%
10	27.46	-42.46	15.83	-27.46	42.46	-15.83	0.000%
11	27.46	-31.84	15.83	-27.46	31.84	-15.83	0.000%
12	13.48	-42.46	23.54	-13.48	42.46	-23.54	0.000%
13	13.48	-31.84	23.54	-13.48	31.84	-23.54	0.000%
14	0.02	-42.46	30.23	-0.02	42.46	-30.23	0.000%
15	0.02	-31.84	30.23	-0.02	31.84	-30.23	0.000%
16	-16.09	-42.46	28.11	16.09	42.46	-28.11	0.000%
17	-16.09	-31.84	28.11	16.09	31.84	-28.11	0.000%

tnxTower Centerline Engineering Services, PA 750 W Center St, Suite 301 West Bridgewater, MA 02379 Phone: (781) 713-4725 FAX:	Job	Stamford NW CT	Page	41 of 52
	Project	23CLVZ-0009	Date	15:14:50 09/21/23
	Client	Verizon Wireless	Designed by	jboegel

Load Comb.	Sum of Applied Forces			Sum of Reactions			% Error
	PX K	PY K	PZ K	PX K	PY K	PZ K	
18	-29.70	-42.46	17.10	29.70	42.46	-17.10	0.000%
19	-29.70	-31.84	17.10	29.70	31.84	-17.10	0.000%
20	-31.28	-42.46	-0.05	31.28	42.46	0.05	0.000%
21	-31.28	-31.84	-0.05	31.28	31.84	0.05	0.000%
22	-25.68	-42.46	-14.90	25.68	42.46	14.90	0.000%
23	-25.68	-31.84	-14.90	25.68	31.84	14.90	0.000%
24	-13.60	-42.46	-23.56	13.60	42.46	23.56	0.000%
25	-13.60	-31.84	-23.56	13.60	31.84	23.56	0.000%
26	0.00	-80.19	0.00	0.00	80.19	0.00	0.000%
27	-0.00	-80.19	-8.85	0.00	80.19	8.85	0.000%
28	4.48	-80.19	-7.75	-4.48	80.19	7.75	0.000%
29	7.97	-80.19	-4.60	-7.97	80.19	4.60	0.000%
30	8.62	-80.19	-0.00	-8.62	80.19	0.00	0.000%
31	7.39	-80.19	4.25	-7.39	80.19	-4.25	0.000%
32	3.85	-80.19	6.69	-3.85	80.19	-6.69	0.000%
33	0.00	-80.19	8.50	-0.00	80.19	-8.50	0.000%
34	-4.46	-80.19	7.75	4.46	80.19	-7.75	0.000%
35	-8.27	-80.19	4.75	8.27	80.19	-4.75	0.000%
36	-8.62	-80.19	-0.01	8.62	80.19	0.01	0.000%
37	-7.09	-80.19	-4.09	7.09	80.19	4.09	0.000%
38	-3.88	-80.19	-6.70	3.88	80.19	6.70	0.000%
39	-0.01	-35.38	-9.11	0.01	35.38	9.11	0.000%
40	4.57	-35.38	-7.93	-4.57	35.38	7.93	0.000%
41	7.87	-35.38	-4.55	-7.87	35.38	4.55	0.000%
42	8.81	-35.38	-0.00	-8.81	35.38	0.00	0.000%
43	7.73	-35.38	4.46	-7.73	35.38	-4.46	0.000%
44	3.80	-35.38	6.63	-3.80	35.38	-6.63	0.000%
45	0.01	-35.38	8.52	-0.01	35.38	-8.52	0.000%
46	-4.53	-35.38	7.92	4.53	35.38	-7.92	0.000%
47	-8.37	-35.38	4.82	8.37	35.38	-4.82	0.000%
48	-8.81	-35.38	-0.01	8.81	35.38	0.01	0.000%
49	-7.23	-35.38	-4.20	7.23	35.38	4.20	0.000%
50	-3.83	-35.38	-6.64	3.83	35.38	6.64	0.000%

Maximum Tower Deflections - Service Wind

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
T1	152 - 140	3.205	47	0.1737	0.0144
T2	140 - 135	2.765	47	0.1704	0.0121
T3	135 - 130	2.585	47	0.1685	0.0117
T4	130 - 125	2.407	47	0.1657	0.0109
T5	125 - 120	2.230	47	0.1617	0.0103
T6	120 - 100	2.059	47	0.1564	0.0096
T7	100 - 80	1.433	47	0.1310	0.0076
T8	80 - 73.3333	0.914	47	0.1040	0.0058
T9	73.3333 - 66.6667	0.767	47	0.0953	0.0051
T10	66.6667 - 60	0.633	47	0.0860	0.0046
T11	60 - 50	0.512	47	0.0762	0.0040
T12	50 - 40	0.354	47	0.0621	0.0032
T13	40 - 30	0.232	47	0.0473	0.0026
T14	30 - 20	0.136	47	0.0350	0.0020
T15	20 - 15	0.068	47	0.0227	0.0013
T16	15 - 9.99999	0.039	47	0.0166	0.0010
T17	9.99999 - 0	0.018	47	0.0111	0.0006

tnxTower Centerline Engineering Services, PA 750 W Center St, Suite 301 West Bridgewater, MA 02379 Phone: (781) 713-4725 FAX:	Job	Stamford NW CT	Page	42 of 52
	Project	23CLVZ-0009	Date	15:14:50 09/21/23
	Client	Verizon Wireless	Designed by	jboegel

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
-------------	-----------------	---------------------------	-----------------------	-----------	------------

Critical Deflections and Radius of Curvature - Service Wind

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
152.00	4' HP MW	47	3.205	0.1737	0.0144	263327
150.00	DB563K-TT w/Mount Pipe	47	3.131	0.1732	0.0138	263327
145.00	QS66512-2 w/ Mount Pipe	47	2.948	0.1720	0.0123	188091
140.00	4' HP MW	47	2.765	0.1704	0.0121	112655
135.00	6' x 3" Omni	47	2.585	0.1685	0.0117	109736
131.00	APXVSPP18-C-A20 w/ Mount Pipe	47	2.442	0.1663	0.0111	177651
115.00	AIR32 KRD901146- 1_B66_B2A w/ Mount Pipe	47	1.893	0.1505	0.0090	51164
98.00	XXDWMM-12.5-65-8T-CBRS w/ Mount Pipe	47	1.376	0.1283	0.0075	43282
74.00	8' 4-Bay Dipole	47	0.781	0.0962	0.0052	42177
58.00	GPS	47	0.478	0.0734	0.0038	44487

Maximum Tower Deflections - Design Wind

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
T1	152 - 140	11.313	18	0.6115	0.0513
T2	140 - 135	9.765	18	0.6010	0.0431
T3	135 - 130	9.128	18	0.5940	0.0416
T4	130 - 125	8.500	18	0.5841	0.0388
T5	125 - 120	7.878	18	0.5701	0.0365
T6	120 - 100	7.273	18	0.5512	0.0340
T7	100 - 80	5.064	18	0.4622	0.0272
T8	80 - 73.3333	3.234	18	0.3671	0.0206
T9	73.3333 - 66.6667	2.714	18	0.3366	0.0182
T10	66.6667 - 60	2.239	18	0.3037	0.0163
T11	60 - 50	1.812	18	0.2692	0.0142
T12	50 - 40	1.253	18	0.2194	0.0114
T13	40 - 30	0.824	18	0.1674	0.0091
T14	30 - 20	0.483	18	0.1238	0.0071
T15	20 - 15	0.240	18	0.0805	0.0047
T16	15 - 9.99999	0.139	18	0.0587	0.0035
T17	9.99999 - 0	0.065	18	0.0392	0.0022

Critical Deflections and Radius of Curvature - Design Wind

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
152.00	4' HP MW	18	11.313	0.6115	0.0513	85581
150.00	DB563K-TT w/Mount Pipe	18	11.054	0.6101	0.0490	85581

tnxTower Centerline Engineering Services, PA 750 W Center St, Suite 301 West Bridgewater, MA 02379 Phone: (781) 713-4725 FAX:	Job	Stamford NW CT	Page	43 of 52
	Project	23CLVZ-0009	Date	15:14:50 09/21/23
	Client	Verizon Wireless	Designed by	jboegel

Elevation	Appurtenance	Gov. Load Comb.	Deflection	Tilt	Twist	Radius of Curvature
ft			in	°	°	ft
145.00	QS66512-2 w/ Mount Pipe	18	10.408	0.6061	0.0438	61130
140.00	4' HP MW	18	9.765	0.6010	0.0431	35596
135.00	6' x 3" Omni	18	9.128	0.5940	0.0416	31664
131.00	APXVSP18-C-A20 w/ Mount Pipe	18	8.625	0.5864	0.0394	52152
115.00	AIR32 KRD901146-1_B66_B2A w/ Mount Pipe	18	6.689	0.5304	0.0318	14630
98.00	XXDWMM-12.5-65-8T-CBRS w/ Mount Pipe	18	4.863	0.4527	0.0266	12337
74.00	8' 4-Bay Dipole	18	2.764	0.3397	0.0184	11908
58.00	GPS	18	1.692	0.2592	0.0136	12581

Bolt Design Data

Section No.	Elevation	Component Type	Bolt Grade	Bolt Size	Number Of Bolts	Maximum Load per Bolt	Allowable Load per Bolt	Ratio Load Allowable	Allowable Ratio	Criteria
	ft			in		K	K			
T1	152	Leg	A325N	0.6250	4	0.68	20.34	0.033 ✓	1	Bolt Tension
		Diagonal	A325N	0.5000	1	1.13	3.13	0.362 ✓	1	Member Block Shear
		Top Girt	A325N	0.5000	1	0.09	4.13	0.023 ✓	1	Member Bearing
T2	140	Diagonal	A325N	0.5000	1	1.07	4.69	0.228 ✓	1	Member Block Shear
		Top Girt	A325N	0.5000	1	0.12	4.13	0.029 ✓	1	Member Bearing
T3	135	Diagonal	A325N	0.5000	1	1.52	4.69	0.325 ✓	1	Member Block Shear
T4	130	Diagonal	A325N	0.5000	1	2.34	6.25	0.374 ✓	1	Member Block Shear
T5	125	Leg	A325N	0.6250	4	3.51	20.34	0.173 ✓	1	Bolt Tension
		Diagonal	A325N	0.5000	1	2.32	6.25	0.371 ✓	1	Member Block Shear
T6	120	Leg	A325N	0.7500	4	8.28	30.10	0.275 ✓	1	Bolt Tension
		Diagonal	A325N	0.5000	1	4.11	8.27	0.497 ✓	1	Gusset Bearing
T7	100	Leg	A325N	0.8750	4	14.01	41.56	0.337 ✓	1	Bolt Tension
		Diagonal	A325X	0.5000	1	4.83	8.27	0.584 ✓	1	Member Bearing
		Secondary Horizontal	A325N	0.5000	2	0.61	8.70	0.071 ✓	1	Member Block Shear
T8	80	Diagonal	A325X	0.5000	1	4.96	8.27	0.600 ✓	1	Member Bearing
		Secondary Horizontal	A325N	0.5000	2	0.70	8.70	0.080 ✓	1	Member Block Shear
T9	73.3333	Diagonal	A325X	0.5000	1	5.02	8.27	0.607 ✓	1	Gusset Bearing
		Secondary Horizontal	A325N	0.5000	2	0.77	8.70	0.089 ✓	1	Member Block Shear
T10	66.6667	Leg	A325N	0.8750	4	19.83	41.56	0.477 ✓	1	Bolt Tension
		Diagonal	A325N	0.5000	1	5.17	8.27	0.626 ✓	1	Gusset Bearing
		Secondary Horizontal	A325N	0.5000	2	0.85	8.70	0.098 ✓	1	Member Block Shear
T11	60	Diagonal	A325N	0.6250	1	5.80	10.44	0.555 ✓	1	Gusset Bearing
		Secondary Horizontal	A325N	0.5000	2	0.94	8.70	0.108 ✓	1	Member Block Shear

tnxTower Centerline Engineering Services, PA 750 W Center St, Suite 301 West Bridgewater, MA 02379 Phone: (781) 713-4725 FAX:	Job	Stamford NW CT	Page 44 of 52
	Project	23CLVZ-0009	Date 15:14:50 09/21/23
	Client	Verizon Wireless	Designed by jboegel

Section No.	Elevation ft	Component Type	Bolt Grade	Bolt Size in	Number Of Bolts	Maximum Load per Bolt K	Allowable Load per Bolt K	Ratio Load Allowable	Allowable Ratio	Criteria
T12	50	Leg	A325N	1.0000	4	24.80	54.52	0.455 ✓	1	Bolt Tension
		Diagonal	A325N	0.6250	1	5.83	10.44	0.559 ✓	1	Gusset Bearing
		Secondary Horizontal	A325N	0.5000	2	1.05	8.84	0.119 ✓	1	Bolt Shear
T13	40	Diagonal	A325N	0.6250	1	6.04	10.44	0.579 ✓	1	Gusset Bearing
		Secondary Horizontal	A325N	0.5000	2	1.16	8.84	0.131 ✓	1	Bolt Shear
T14	30	Leg	A325N	1.0000	4	29.83	54.52	0.547 ✓	1	Bolt Tension
		Diagonal	A325N	0.6250	1	6.64	10.44	0.636 ✓	1	Gusset Bearing
		Horizontal	A325N	0.5000	2	1.26	8.84	0.143 ✓	1	Bolt Shear
T15	20	Diagonal	A325X	0.6250	1	6.11	10.44	0.586 ✓	1	Member Bearing
T16	15	Diagonal	A325X	0.6250	1	5.96	10.44	0.571 ✓	1	Gusset Bearing
		Horizontal	A325N	0.6250	1	2.75	10.44	0.263 ✓	1	Member Bearing
T17	9.99999	Diagonal	A325X	0.6250	1	6.65	10.44	0.637 ✓	1	Gusset Bearing

Compression Checks

Leg Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u K	φP _u K	Ratio P _u φP _u
T1	152 - 140	P2.375X0.154 (2" STD)	12.00	4.00	61.0 K=1.00	1.0745	-4.58	36.84	0.124 ¹ ✓
T2	140 - 135	P2.875"x0.203" (2.5 STD)	5.01	5.01	63.4 K=1.00	1.7040	-6.87	57.13	0.120 ¹ ✓
T3	135 - 130	P2.875"x0.203" (2.5 STD)	5.01	5.01	63.4 K=1.00	1.7040	-10.73	57.13	0.188 ¹ ✓
T4	130 - 125	P2.875"x0.203" (2.5 STD)	5.01	5.01	63.4 K=1.00	1.7040	-14.44	57.13	0.253 ¹ ✓
T5	125 - 120	P2.875"x0.203" (2.5 STD)	5.01	5.01	63.4 K=1.00	1.7040	-19.29	57.14	0.338 ¹ ✓
T6	120 - 100	Pipe 2.5 XStr (2.875"ODx0.276")	20.03	6.68	86.7 K=1.00	2.2535	-42.69	58.51	0.730 ¹ ✓
T7	100 - 80	2.875"x0.276" w/ 3.5"x.3" Sleeve (STAMFORD NW CT)	20.03	3.43	45.3 K=1.00	3.2590	-70.80	126.18	0.561 ¹ ✓
T8	80 - 73.3333	3.5"x0.3" w/ 4"x.25" Sleeve (STAMFORD NW CT)	6.68	3.43	37.1 K=1.00	3.9980	-80.30	162.69	0.494 ¹ ✓
T9	73.3333 - 66.6667	3.5"x0.3" w/ 4"x.25" Sleeve (STAMFORD NW CT)	6.68	3.42	37.1 K=1.00	3.9980	-88.95	162.72	0.547 ¹ ✓
T10	66.6667 - 60	3.5"x0.3" w/ 4"x.25" Sleeve (STAMFORD NW CT)	6.68	3.42	37.0 K=1.00	3.9980	-97.87	162.76	0.601 ¹ ✓
T11	60 - 50	Pipe 4 XStr	10.02	5.17	42.1	4.4074	-108.55	174.28	0.623 ¹ ✓

tnxTower Centerline Engineering Services, PA 750 W Center St, Suite 301 West Bridgewater, MA 02379 Phone: (781) 713-4725 FAX:	Job	Stamford NW CT	Page	45 of 52
	Project	23CLVZ-0009	Date	15:14:50 09/21/23
	Client	Verizon Wireless	Designed by	jboegel

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u K	φP _n K	Ratio $\frac{P_u}{\phi P_n}$
T12	50 - 40	(4.5"ODx0.337") Pipe 4 XStr	10.02	5.17	K=1.00 42.0	4.4074	-121.11	174.35	0.695 ¹
T13	40 - 30	(4.5"ODx0.337") 4.5"x0.337" w/ 5"x.25" Sleeve (STAMFORD NW CT 30'-40')	10.02	5.16	K=1.00 43.5	5.5270	-133.70	216.57	0.617 ¹
T14	30 - 20	4.5"x0.337" w/ 5"x.25" Sleeve (STAMFORD NW CT 20'-30')	10.02	2.50	K=1.00 20.9	5.6410	-145.45	245.84	0.592 ¹
T15	20 - 15	5.5"x0.259" w/ 6"x.25" Sleeve (STAMFORD NW CT 15'-20')	5.01	2.50	K=4.00 67.4	5.7700	-157.37	186.20	0.845 ¹
T16	15 - 9.99999	5.5"x0.259" w/ (3) 1.5"x.5" Bars (STAMFORD NW CT 0'-15')	5.01	5.01	K=2.00 57.3	6.5614	-158.54	232.29	0.683 ¹
T17	9.99999 - 0	5.5"x0.259" w/ (3) 1.5"x.5" Bars (STAMFORD NW CT 0'-15')	10.02	10.02	K=1.00 57.3	6.5614	-170.03	232.30	0.732 ¹

¹ P_u / φP_n controls

Diagonal Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u K	φP _n K	Ratio $\frac{P_u}{\phi P_n}$
T1	152 - 140	L1 1/2x1 1/2x1/8	7.68	3.62	146.8 K=1.00	0.3594	-1.15	4.77	0.241 ¹
T2	140 - 135	L1 1/2x1 1/2x3/16	8.45	4.13	169.0 K=1.00	0.5273	-1.11	5.28	0.210 ¹
T3	135 - 130	L1 1/2x1 1/2x3/16	8.87	4.34	177.5 K=1.00	0.5273	-1.56	4.79	0.326 ¹
T4	130 - 125	L1 1/2x1 1/2x1/4	9.30	4.55	187.1 K=1.00	0.6875	-2.45	5.62	0.436 ¹
T5	125 - 120	L1 1/2x1 1/2x1/4	9.73	4.76	195.8 K=1.00	0.6875	-2.20	5.13	0.428 ¹
T6	120 - 100	L2x2x1/4	12.26	6.09	186.8 K=1.00	0.9380	-3.90	7.69	0.507 ¹
T7	100 - 80	L2 1/2x2 1/2x1/4	14.01	7.05	172.4 K=1.00	1.1900	-5.07	11.46	0.443 ¹
T8	80 - 73.3333	L2 1/2x2 1/2x1/4	14.61	7.33	179.1 K=1.00	1.1900	-5.09	10.61	0.480 ¹
T9	73.3333 - 66.6667	L2 1/2x2 1/2x5/16	15.21	7.63	187.3 K=1.00	1.4600	-5.41	11.91	0.455 ¹
T10	66.6667 - 60	L2 1/2x2 1/2x5/16	15.82	7.94	194.9 K=1.00	1.4600	-5.33	11.01	0.484 ¹
T11	60 - 50	L3x3x1/4	18.19	9.17	186.0 K=1.00	1.4400	-6.21	11.92	0.521 ¹
T12	50 - 40	L3x3x5/16	19.05	9.60	195.7 K=1.00	1.7800	-6.42	13.31	0.483 ¹
T13	40 - 30	L3x3x3/8	19.92	10.04	205.2 K=1.00	2.1100	-6.49	14.34	0.452 ¹

tnxTower Centerline Engineering Services, PA 750 W Center St, Suite 301 West Bridgewater, MA 02379 Phone: (781) 713-4725 FAX:	Job	Stamford NW CT	Page	46 of 52
	Project	23CLVZ-0009	Date	15:14:50 09/21/23
	Client	Verizon Wireless	Designed by	jboegel

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u K	φP _n K	Ratio $\frac{P_u}{\phi P_n}$
T14	30 - 20	KL/R > 200 (C) - 178 L3x3x5/16	10.63	10.42	135.7 K=1.00	1.7800	-7.51	27.69	0.271 ¹ ✓
T15	20 - 15	L3 1/2x3 1/2x1/4	10.63	10.14	115.8 K=1.04	1.6900	-6.15	35.18	0.175 ¹ ✓
T16	15 - 9.99999	L3 1/2x3 1/2x1/4	11.08	10.58	182.9 K=1.00	1.6900	-6.34	14.46	0.439 ¹ ✓
T17	9.99999 - 0	L3 1/2x3 1/2x5/16	22.61	11.21	194.9 K=1.00	2.0900	-7.23	15.74	0.459 ¹ ✓

¹ P_u / φP_n controls

Horizontal Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u K	φP _n K	Ratio $\frac{P_u}{\phi P_n}$
T14	30 - 20	L3x3x1/4	18.24	13.41	181.2 K=0.50	1.4400	-2.52	12.55	0.201 ¹ ✓
T16	15 - 9.99999	L3x3x1/4	19.26	9.28	239.4 K=1.00	1.4400	-2.75	7.19	0.382 ¹ ✓
KL/R > 200 (C) - 246									

¹ P_u / φP_n controls

Secondary Horizontal Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u K	φP _n K	Ratio $\frac{P_u}{\phi P_n}$
T7	100 - 80	L2 1/2x2 1/2x1/4	12.31	6.03	147.4 K=1.00	1.1900	-1.23	15.68	0.078 ¹ ✓
T8	80 - 73.3333	L2 1/2x2 1/2x1/4	12.99	6.35	155.2 K=1.00	1.1900	-1.39	14.15	0.098 ¹ ✓
T9	73.3333 - 66.6667	L2 1/2x2 1/2x1/4	13.66	6.69	163.4 K=1.00	1.1900	-1.54	12.75	0.121 ¹ ✓
T10	66.6667 - 60	L2 1/2x2 1/2x1/4	14.34	7.03	171.7 K=1.00	1.1900	-1.70	11.55	0.147 ¹ ✓
T11	60 - 50	L2 1/2x2 1/2x1/4	15.18	7.40	180.9 K=1.00	1.1900	-1.88	10.41	0.181 ¹ ✓
T12	50 - 40	L3x3x1/4	16.19	7.91	160.3 K=1.00	1.4400	-2.10	16.03	0.131 ¹ ✓
T13	40 - 30	L3x3x1/4	17.21	8.42	170.7 K=1.00	1.4400	-2.32	14.14	0.164 ¹ ✓

tnxTower Centerline Engineering Services, PA 750 W Center St, Suite 301 West Bridgewater, MA 02379 Phone: (781) 713-4725 FAX:	Job	Stamford NW CT	Page	47 of 52
	Project	23CLVZ-0009	Date	15:14:50 09/21/23
	Client	Verizon Wireless	Designed by	jboegel

¹ $P_u / \phi P_n$ controls

Top Girt Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u K	ϕP_n K	Ratio $\frac{P_u}{\phi P_n}$
T1	152 - 140	L2x2x1/8	6.52	6.11	184.5 K=1.00	0.4844	-0.10	4.07	0.025 ¹
T2	140 - 135	L2x2x1/8	6.56	6.11	184.5 K=1.00	0.4844	-0.12	4.07	0.029 ¹

¹ $P_u / \phi P_n$ controls

Redundant Horizontal (1) Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u K	ϕP_n K	Ratio $\frac{P_u}{\phi P_n}$
T14	30 - 20	L2x2x1/4	4.56	4.38	134.4 K=1.00	0.9380	-2.52	14.85	0.170 ¹
T15	20 - 15	L2x2x1/4	4.81	4.60	141.1 K=1.00	0.9380	-2.95	13.48	0.219 ¹

¹ $P_u / \phi P_n$ controls

Redundant Diagonal (1) Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u K	ϕP_n K	Ratio $\frac{P_u}{\phi P_n}$
T14	30 - 20	L2x2x1/4	5.31	5.11	156.7 K=1.00	0.9380	-1.47	10.93	0.134 ¹
T15	20 - 15	L2x2x1/4	5.54	5.30	162.6 K=1.00	0.9380	-1.58	10.16	0.156 ¹

¹ $P_u / \phi P_n$ controls

Tension Checks

Leg Design Data (Tension)

tnxTower Centerline Engineering Services, PA 750 W Center St, Suite 301 West Bridgewater, MA 02379 Phone: (781) 713-4725 FAX:	Job	Stamford NW CT	Page	48 of 52
	Project	23CLVZ-0009	Date	15:14:50 09/21/23
	Client	Verizon Wireless	Designed by	jboegel

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u K	φP _n K	Ratio P _u / φP _n
T1	152 - 140	P2.375X0.154 (2" STD)	12.00	4.00	61.0	1.0745	2.72	48.35	0.056 ¹ ✓
T2	140 - 135	P2.875"x0.203" (2.5 STD)	5.01	5.01	63.4	1.7040	4.74	76.68	0.062 ¹ ✓
T3	135 - 130	P2.875"x0.203" (2.5 STD)	5.01	5.01	63.4	1.7040	7.10	76.68	0.093 ¹ ✓
T4	130 - 125	P2.875"x0.203" (2.5 STD)	5.01	5.01	63.4	1.7040	9.78	76.68	0.128 ¹ ✓
T5	125 - 120	P2.875"x0.203" (2.5 STD)	5.01	5.01	63.4	1.7040	14.05	76.68	0.183 ¹ ✓
T6	120 - 100	Pipe 2.5 XStr (2.875"ODx0.276")	20.03	6.68	86.7	2.2535	33.13	101.41	0.327 ¹ ✓
T7	100 - 80	2.875"x0.276" w/ 3.5"x.3" Sleeve (STAMFORD NW CT)	20.03	3.25	42.9	3.2590	56.11	146.66	0.383 ¹ ✓
T8	80 - 73.3333	3.5"x0.3" w/ 4"x.25" Sleeve (STAMFORD NW CT)	6.68	3.25	35.2	3.9980	64.21	179.91	0.357 ¹ ✓
T9	73.3333 - 66.6667	3.5"x0.3" w/ 4"x.25" Sleeve (STAMFORD NW CT)	6.68	3.26	35.3	3.9980	71.71	179.91	0.399 ¹ ✓
T10	66.6667 - 60	3.5"x0.3" w/ 4"x.25" Sleeve (STAMFORD NW CT)	6.68	3.26	35.3	3.9980	79.41	179.91	0.441 ¹ ✓
T11	60 - 50	Pipe 4 XStr (4.5"ODx0.337")	10.02	4.84	39.3	4.4074	88.55	198.34	0.446 ¹ ✓
T12	50 - 40	Pipe 4 XStr (4.5"ODx0.337")	10.02	4.85	39.4	4.4074	99.31	198.34	0.501 ¹ ✓
T13	40 - 30	4.5"x0.337" w/ 5"x.25" Sleeve (STAMFORD NW CT 30'-40')	10.02	4.86	41.0	5.5270	109.92	248.72	0.442 ¹ ✓
T14	30 - 20	4.5"x0.337" w/ 5"x.25" Sleeve (STAMFORD NW CT 20'-30')	10.02	2.50	20.9	5.6410	119.66	253.85	0.471 ¹ ✓
T15	20 - 15	5.5"x0.259" w/ 6"x.25" Sleeve (STAMFORD NW CT 15'-20')	5.01	2.50	16.9	5.7700	129.58	259.65	0.499 ¹ ✓
T16	15 - 9.99999	5.5"x0.259" w/ (3) 1.5"x.5" Bars (STAMFORD NW CT 0'-15')	5.01	5.01	28.6	6.5614	130.11	295.26	0.441 ¹ ✓
T17	9.99999 - 0	5.5"x0.259" w/ (3) 1.5"x.5" Bars (STAMFORD NW CT 0'-15')	10.02	10.02	57.3	6.5614	139.68	295.26	0.473 ¹ ✓

¹ P_u / φP_n controls

Diagonal Design Data (Tension)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u K	φP _n K	Ratio P _u / φP _n
T1	152 - 140	L1 1/2x1 1/2x1/8	7.68	3.62	96.1	0.2109	1.13	9.18	0.123 ¹ ✓
T2	140 - 135	L1 1/2x1 1/2x3/16	8.45	4.13	111.3	0.3076	1.07	13.38	0.080 ¹ ✓

tnxTower Centerline Engineering Services, PA 750 W Center St, Suite 301 West Bridgewater, MA 02379 Phone: (781) 713-4725 FAX:	Job	Stamford NW CT	Page	49 of 52
	Project	23CLVZ-0009	Date	15:14:50 09/21/23
	Client	Verizon Wireless	Designed by	jboegel

Section No.	Elevation	Size	L	L _u	Kl/r	A	P _u	φP _n	Ratio
	ft		ft	ft		in ²	K	K	$\frac{P_u}{\phi P_n}$
T3	135 - 130	L1 1/2x1 1/2x3/16	8.87	4.34	116.8	0.3076	1.52	13.38	0.114 ¹
T4	130 - 125	L1 1/2x1 1/2x1/4	9.30	4.55	124.5	0.3984	2.34	17.33	0.135 ¹
T5	125 - 120	L1 1/2x1 1/2x1/4	9.73	4.76	130.2	0.3984	2.32	17.33	0.134 ¹
T6	120 - 100	L2x2x1/4	11.70	5.81	116.5	0.5863	4.11	25.50	0.161 ¹
T7	100 - 80	L2 1/2x2 1/2x1/4	13.42	6.76	105.5	0.7753	4.83	33.73	0.143 ¹
T8	80 - 73.3333	L2 1/2x2 1/2x1/4	14.61	7.33	114.4	0.7753	4.96	33.73	0.147 ¹
T9	73.3333 - 66.6667	L2 1/2x2 1/2x5/16	15.21	7.63	120.4	0.9485	5.02	41.26	0.122 ¹
T10	66.6667 - 60	L2 1/2x2 1/2x5/16	15.82	7.94	125.2	0.9485	5.17	41.26	0.125 ¹
T11	60 - 50	L3x3x1/4	18.19	9.17	118.4	0.9394	5.80	40.86	0.142 ¹
T12	50 - 40	L3x3x5/16	19.05	9.60	125.0	1.1592	5.83	50.43	0.116 ¹
T13	40 - 30	L3x3x3/8	19.92	10.04	132.0	1.3716	6.04	59.66	0.101 ¹
T14	30 - 20	L3x3x5/16	10.63	10.42	135.7	1.1592	6.64	50.43	0.132 ¹
T15	20 - 15	L3 1/2x3 1/2x1/4	10.63	10.14	114.3	1.1269	6.11	49.02	0.125 ¹
T16	15 - 9.99999	L3 1/2x3 1/2x1/4	11.08	10.58	119.1	1.1269	5.96	49.02	0.122 ¹
T17	9.99999 - 0	L3 1/2x3 1/2x5/16	22.61	11.21	125.9	1.3917	6.65	60.54	0.110 ¹

¹ P_u / φP_n controls

Horizontal Design Data (Tension)

Section No.	Elevation	Size	L	L _u	Kl/r	A	P _u	φP _n	Ratio
	ft		ft	ft		in ²	K	K	$\frac{P_u}{\phi P_n}$
T14	30 - 20	L3x3x1/4	18.24	13.41	173.0	0.9628	2.52	41.88	0.060 ¹
T16	15 - 9.99999	L3x3x1/4	19.26	9.28	181.9	0.9394	2.75	40.86	0.067 ¹

¹ P_u / φP_n controls

Secondary Horizontal Design Data (Tension)

tnxTower Centerline Engineering Services, PA 750 W Center St, Suite 301 West Bridgewater, MA 02379 Phone: (781) 713-4725 FAX:	Job	Stamford NW CT	Page	50 of 52
	Project	23CLVZ-0009	Date	15:14:50 09/21/23
	Client	Verizon Wireless	Designed by	jboegel

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u K	φP _n K	Ratio $\frac{P_u}{\phi P_n}$
T7	100 - 80	L2 1/2x2 1/2x1/4	11.64	5.69	177.6	0.7753	1.23	33.73	0.036 ¹ ✓
T8	80 - 73.3333	L2 1/2x2 1/2x1/4	12.99	6.35	198.1	0.7753	1.39	33.73	0.041 ¹ ✓
T9	73.3333 - 66.6667	L2 1/2x2 1/2x1/4	13.66	6.69	208.7	0.7753	1.54	33.73	0.046 ¹ ✓
T10	66.6667 - 60	L2 1/2x2 1/2x1/4	14.34	7.03	219.3	0.7753	1.70	33.73	0.050 ¹ ✓
T11	60 - 50	L2 1/2x2 1/2x1/4	15.18	7.40	231.0	0.7753	1.88	33.73	0.056 ¹ ✓
T12	50 - 40	L3x3x1/4	16.19	7.91	204.1	0.9628	2.10	41.88	0.050 ¹ ✓
T13	40 - 30	L3x3x1/4	17.21	8.42	217.3	0.9628	2.32	41.88	0.055 ¹ ✓

¹ P_u / φP_n controls

Top Girt Design Data (Tension)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u K	φP _n K	Ratio $\frac{P_u}{\phi P_n}$
T1	152 - 140	L2x2x1/8	6.52	6.11	121.1	0.3047	0.09	13.25	0.007 ¹ ✓
T2	140 - 135	L2x2x1/8	6.56	6.11	121.1	0.3047	0.12	13.25	0.009 ¹ ✓

¹ P_u / φP_n controls

Redundant Horizontal (1) Design Data (Tension)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u K	φP _n K	Ratio $\frac{P_u}{\phi P_n}$
T14	30 - 20	L2x2x1/4	4.56	4.38	86.3	0.9380	2.52	30.39	0.083 ¹ ✓
T15	20 - 15	L2x2x1/4	4.81	4.60	90.6	0.9380	2.95	30.39	0.097 ¹ ✓

¹ P_u / φP_n controls

Redundant Diagonal (1) Design Data (Tension)

tnxTower Centerline Engineering Services, PA 750 W Center St, Suite 301 West Bridgewater, MA 02379 Phone: (781) 713-4725 FAX:	Job	Stamford NW CT	Page	51 of 52
	Project	23CLVZ-0009	Date	15:14:50 09/21/23
	Client	Verizon Wireless	Designed by	jboegel

Section No.	Elevation	Size	L	L _u	Kl/r	A	P _u	φP _n	Ratio P _u / φP _n
	ft		ft	ft		in ²	K	K	
T14	30 - 20	L2x2x1/4	5.31	5.11	100.6	0.9380	1.47	30.39	0.048 ¹
T15	20 - 15	L2x2x1/4	5.54	5.30	104.4	0.9380	1.58	30.39	0.052 ¹

¹ P_u / φP_n controls

Section Capacity Table

Section No.	Elevation	Component Type	Size	Critical Element	P K	φP _{allow} K	% Capacity	Pass Fail
T1	152 - 140	Leg	P2.375X0.154 (2" STD)	3	-4.58	36.84	12.4	Pass
T2	140 - 135	Leg	P2.875"x0.203" (2.5 STD)	27	-6.87	57.13	12.0	Pass
T3	135 - 130	Leg	P2.875"x0.203" (2.5 STD)	39	-10.73	57.13	18.8	Pass
T4	130 - 125	Leg	P2.875"x0.203" (2.5 STD)	48	-14.44	57.13	25.3	Pass
T5	125 - 120	Leg	P2.875"x0.203" (2.5 STD)	57	-19.29	57.14	33.8	Pass
T6	120 - 100	Leg	Pipe 2.5 XStr (2.875"ODx0.276")	64	-42.69	58.51	73.0	Pass
T7	100 - 80	Leg	2.875"x0.276" w/ 3.5"x.3" Sleeve (STAMFORD NW CT)	85	-70.80	126.18	56.1	Pass
T8	80 - 73.3333	Leg	3.5"x0.3" w/ 4"x.25" Sleeve (STAMFORD NW CT)	115	-80.30	162.69	49.4	Pass
T9	73.3333 - 66.6667	Leg	3.5"x0.3" w/ 4"x.25" Sleeve (STAMFORD NW CT)	127	-88.95	162.72	54.7	Pass
T10	66.6667 - 60	Leg	3.5"x0.3" w/ 4"x.25" Sleeve (STAMFORD NW CT)	139	-97.87	162.76	60.1	Pass
T11	60 - 50	Leg	Pipe 4 XStr (4.5"ODx0.337")	151	-108.55	174.28	62.3	Pass
T12	50 - 40	Leg	Pipe 4 XStr (4.5"ODx0.337")	163	-121.11	174.35	69.5	Pass
T13	40 - 30	Leg	4.5"x0.337" w/ 5"x.25" Sleeve (STAMFORD NW CT 30'-40')	175	-133.70	216.57	61.7	Pass
T14	30 - 20	Leg	4.5"x0.337" w/ 5"x.25" Sleeve (STAMFORD NW CT 20'-30')	187	-145.45	245.84	59.2	Pass
T15	20 - 15	Leg	5.5"x0.259" w/ 6"x.25" Sleeve (STAMFORD NW CT 15'-20')	229	-157.37	186.20	84.5	Pass
T16	15 - 9.99999	Leg	5.5"x0.259" w/ (3) 1.5"x.5" Bars (STAMFORD NW CT 0'-15')	253	-158.54	232.29	68.3	Pass
T17	9.99999 - 0	Leg	5.5"x0.259" w/ (3) 1.5"x.5" Bars (STAMFORD NW CT 0'-15')	262	-170.03	232.30	73.2	Pass
T1	152 - 140	Diagonal	L1 1/2x1 1/2x1/8	11	-1.15	4.77	24.1	Pass
T2	140 - 135	Diagonal	L1 1/2x1 1/2x3/16	31	-1.11	5.28	36.2 (b) 21.0	Pass
T3	135 - 130	Diagonal	L1 1/2x1 1/2x3/16	40	-1.56	4.79	22.8 (b) 32.6	Pass
T4	130 - 125	Diagonal	L1 1/2x1 1/2x1/4	49	-2.45	5.62	43.6	Pass
T5	125 - 120	Diagonal	L1 1/2x1 1/2x1/4	59	-2.20	5.13	42.8	Pass
T6	120 - 100	Diagonal	L2x2x1/4	68	-3.90	7.69	50.7	Pass
T7	100 - 80	Diagonal	L2 1/2x2 1/2x1/4	88	-5.07	11.46	44.3	Pass
T8	80 - 73.3333	Diagonal	L2 1/2x2 1/2x1/4	119	-5.09	10.61	58.4 (b) 48.0	Pass
T9	73.3333 - 66.6667	Diagonal	L2 1/2x2 1/2x5/16	130	-5.41	11.91	60.0 (b) 45.5	Pass
T10	66.6667 - 60	Diagonal	L2 1/2x2 1/2x5/16	142	-5.33	11.01	60.7 (b) 48.4	Pass
T11	60 - 50	Diagonal	L3x3x1/4	154	-6.21	11.92	62.6 (b) 52.1	Pass

tnxTower Centerline Engineering Services, PA 750 W Center St, Suite 301 West Bridgewater, MA 02379 Phone: (781) 713-4725 FAX:	Job	Stamford NW CT	Page 52 of 52
	Project	23CLVZ-0009	Date 15:14:50 09/21/23
	Client	Verizon Wireless	Designed by jboegel

Section No.	Elevation ft	Component Type	Size	Critical Element	P K	ϕP_{allow} K	% Capacity	Pass Fail
							55.5 (b)	
T12	50 - 40	Diagonal	L3x3x5/16	166	-6.42	13.31	48.3	Pass
							55.9 (b)	
T13	40 - 30	Diagonal	L3x3x3/8	178	-6.49	14.34	45.2	Pass
							57.9 (b)	
T14	30 - 20	Diagonal	L3x3x5/16	191	-7.51	27.69	27.1	Pass
							63.6 (b)	
T15	20 - 15	Diagonal	L3 1/2x3 1/2x1/4	236	-6.15	35.18	17.5	Pass
							58.6 (b)	
T16	15 - 9.99999	Diagonal	L3 1/2x3 1/2x1/4	256	-6.34	14.46	43.9	Pass
							57.1 (b)	
T17	9.99999 - 0	Diagonal	L3 1/2x3 1/2x5/16	265	-7.23	15.74	45.9	Pass
							63.7 (b)	
T14	30 - 20	Horizontal	L3x3x1/4	204	-2.52	12.55	20.1	Pass
T16	15 - 9.99999	Horizontal	L3x3x1/4	246	-2.75	7.19	38.2	Pass
T7	100 - 80	Secondary Horizontal	L2 1/2x2 1/2x1/4	96	-1.23	15.68	7.8	Pass
T8	80 - 73.3333	Secondary Horizontal	L2 1/2x2 1/2x1/4	126	-1.39	14.15	9.8	Pass
T9	73.3333 - 66.6667	Secondary Horizontal	L2 1/2x2 1/2x1/4	138	-1.54	12.75	12.1	Pass
T10	66.6667 - 60	Secondary Horizontal	L2 1/2x2 1/2x1/4	150	-1.70	11.55	14.7	Pass
T11	60 - 50	Secondary Horizontal	L2 1/2x2 1/2x1/4	162	-1.88	10.41	18.1	Pass
T12	50 - 40	Secondary Horizontal	L3x3x1/4	174	-2.10	16.03	13.1	Pass
T13	40 - 30	Secondary Horizontal	L3x3x1/4	186	-2.32	14.14	16.4	Pass
T1	152 - 140	Top Girt	L2x2x1/8	5	-0.10	4.07	2.5	Pass
T2	140 - 135	Top Girt	L2x2x1/8	29	-0.12	4.07	2.9	Pass
T14	30 - 20	Redund Horz 1 Bracing	L2x2x1/4	209	-2.52	14.85	17.0	Pass
T15	20 - 15	Redund Horz 1 Bracing	L2x2x1/4	251	-2.95	13.48	21.9	Pass
T14	30 - 20	Redund Diag 1 Bracing	L2x2x1/4	228	-1.47	10.93	13.4	Pass
T15	20 - 15	Redund Diag 1 Bracing	L2x2x1/4	235	-1.58	10.16	15.6	Pass
							Summary	
							Leg (T15)	84.5 Pass
							Diagonal (T17)	63.7 Pass
							Horizontal (T16)	38.2 Pass
							Secondary Horizontal (T11)	18.1 Pass
							Top Girt (T2)	2.9 Pass
							Redund Horz 1 Bracing (T15)	21.9 Pass
							Redund Diag 1 Bracing (T15)	15.6 Pass
							Bolt Checks	63.7 Pass
							RATING =	84.5 Pass



Centerline Engineering Services, PA
750 W Center St, Suite 301
West Bridgewater, MA 02379
Tel: (781)-713-4725

Job: Stamford NW CT
Project: 23CLVZ-0009
Client: Verizon Wireless

Engineer: JB
Date: 9/21/2023
Sheet: 1 of 1

SST Anchor Rod Check (TIA-H)

Anchor Rod Information

Grout Considered?: No
Clear Distance, l_{ar} : 1 in
Quantity Per Leg: 4
Diameter: 1 in
Rod Material: F1554 Gr. 105
Strength (F_u): 125 ksi
Yield (F_y): 105 ksi

Reactions

Compression, P_{uc} : 176.0 kips
Comp Shear, V_{uc} : 21.0 kips
Tension, P_{ut} : 145.0 kips
Tension Shear, V_{ut} : 18.0 kips

Capacity Results

Anchor Rod Results

Interaction Equations for $l_{ar} \leq 1(d)$

$$(P_{uc}/\phi_c R_{nc}) + [V_{uc}/\phi_c R_{nvc}]^2 \leq 1.0$$

$R_{nt} = F_u A_n = 75.75$ kips
 $R_{nc} = F_y A_n = 63.63$ kips
 $R_{nv} = 0.5 F_u A_g = 49.09$ kips

$R_{nvc} = 0.6 F_y A_n / 2 = 19.09$ kips
 $R_{nb} = F_{cr} A_n = 63.34$ kips
 $M_n = F_y Z = 11.86$ ksi

$\phi_t = 0.75$
 $\phi_v = 0.75$
 $\phi_c = 1.0$
 $\phi_r = 0.9$

$P_{uc} = 44.00$ kips
 $P_{ut} = 36.25$ kips

$V_{uc} = 5.25$ kips
 $V_{ut} = 4.50$ kips

$M_{uc} = 3.41$ ksi
 $M_{ut} = 2.93$ ksi

Anchor Rod Stress Ratio= 76.7% **Good**



Centerline Engineering Services, PA
750 W Center St, Suite 301
West Bridgewater, MA 02379
Tel: (781)-713-4725

Job: Stamford NW CT
Project: 23CLVZ-0009
Client: Verizon Wireless

Engineer: JB
Date: 9/21/2023
Sheet: 1 of 1

Self Support Drilled Pier Analysis Summary (TIA-H)

Analysis Reactions

	Comp.	Uplift.	
Moment, M:	1.0	1.0	kip-ft
Axial, P:	176.0	145.0	kips
Shear, V:	21.0	18.0	kips

Material Properties

Rebar Strength, F _y :	60	ksi
Concrete Strength, f _c :	4.0	ksi
Dry Concrete Density, δ _c :	150	pcf

Pier Properties

Depth, D:	21.0	ft
Ext. Above Grade, E:	0.5	ft
Diameter, d:	4.5	ft
Rebar Quantity, R _q :	15	
Rebar Size, R _s :	8	
Clear Cover, cc:	3.00	in
Tie Size, T _s :	4	
Groundwater Depth, D _{gw} :	8.0	ft
Ultimate Gross End Bearing	10.0	ksf

Soil Properties

Layer	Top (ft)	Bottom (ft)	Thickness (ft)	Soil Unit Weight (pcf)	Cohesion (ksf)	Friction Angle (deg)	Ult. Skin Friction - Comp (ksf)	Ult. Skin Friction - Uplift (ksf)	SPT Blow Count (N)
1	0.0	5.0	5.0	120	0.00	0	0.000	0.000	0
2	5.0	8.0	3.0	120	0.00	30	0.820	0.820	0
3	8.0	13.5	5.5	120	0.00	30	0.820	0.820	0
4	13.5	21.0	7.5	130	0.00	36	0.820	0.820	0

Foundation Analysis Results

Soil Lateral Capacity

	Comp.	Uplift
D _v =0 (ft):	11.71	11.7
Soil Safety Factor:	3.11	3.1
Max Moment (kip-ft):	708.42	708.4
Rating:	40.7%	40.7%

Soil Vertical Capacity

	Comp.	Uplift
Skin Friction (kips):	139.1	139.1
End Bearing (kips):	119.3	-
Wt. of Conc. (kips):	46.1	34.5
Total Cap. (kips):	258.4	173.7
Axial (kips):	222.1	145.0
Rating:	81.8%	79.5%

Reinforced Concrete Flexure Capacity

	Comp.	Uplift
Critical Depth (ft):	11.96	11.2
Critical Mom. (k-ft):	707.85	706.2
Critical Mom. Cap.:	1431.09	1,080.5
Rating:	47.1%	62.2%

Reinforced Concrete Shear Capacity

	Comp.	Uplift
Critical Depth (ft):	17.55	17.6
Critical Shear:	41.16	35.3
Critical Shear Cap.:	272.57	246.6
Rating:	14.4%	13.6%

Soil Rating:	81.8%	GOOD
Structural Rating:	62.2%	GOOD



Colliers Engineering & Design CT, PC
1055 Washington Boulevard
Stamford, CT 06901
203.324.0800
peter.albano@collierseng.com

Antenna Mount Analysis Report and PMI Requirements

Mount ReAnalysis

SMART Tool Project #: 10208065
Colliers Engineering & Design CT, PC Project #: 23777220

August 1, 2023

Site Information

Site ID: 5000386730-VZW / STAMFORD NW CT
Site Name: STAMFORD NW CT
Carrier Name: Verizon Wireless
Address: 366 Old Long Ridge Rd
Stamford, Connecticut 06903
Fairfield County
Latitude: 41.153111°
Longitude: -73.592703°

Structure Information

Tower Type: 152-Ft Self Support
Mount Type: 12.50-Ft Sector Frame

FUZE ID # 17123711

Analysis Results

Sector Frame: 42.7% Pass*

***Antennas and equipment to be installed in compliance with PMI Requirements of this mount analysis.**

***Contractor PMI Requirements:

Included at the end of this MA report
Available & Submitted via portal at <https://pmi.vzwsmart.com>

For additional questions and support, please reach out to:
pmisupport@colliersengineering.com

Report Prepared By: Lauren Luzier



Executive Summary:

The objective of this report is to determine the capacity of the antenna support mount at the subject facility for the final wireless telecommunications configuration, per the applicable codes and standards. Any modification listed under Sources of Information was assumed completed and was included in this analysis.

This analysis is inclusive of the mount structure only and does not address the structural capacity of the supporting structure. This mounting frame was not analyzed as an anchor attachment point for fall protection. All climbing activities are required to have a fall protection plan completed by a competent person.

Sources of Information:

Document Type	Remarks
Radio Frequency Data Sheet (RFDS)	Verizon RFDS, Site ID: 1477020, dated March 16, 2021
Construction Drawings	On Air Engineering LLC, Site ID: STAMFORD NW CT, dated February 17, 2020
Previous Antenna Mount Analysis	Maser Consulting Connecticut Project #: 21777625A, dated May 11, 2021
Post Modification Inspection Report	Colliers Engineering & Design Project #: 21777625, dated July 7, 2023
Filter Add Scope	Provided by Verizon Wireless

Analysis Criteria:

Codes and Standards:	ANSI/TIA-222-H 2022 Connecticut State Building Code (CSBC), Effective October 1, 2022
Wind Parameters:	Basic Wind Speed (Ultimate 3-sec. Gust), V_{ULT} : 120 mph Ice Wind Speed (3-sec. Gust): 50 mph Design Ice Thickness: 1.00 in Risk Category: II Exposure Category: B Topographic Category: 1 Topographic Feature Considered: N/A Topographic Method: N/A Ground Elevation Factor, K_e : 0.984
Seismic Parameters:	S_s : 0.261 g S_1 : 0.058 g
Maintenance Parameters:	Wind Speed (3-sec. Gust): 30 mph Maintenance Live Load, L_v : 250 lbs. Maintenance Live Load, L_m : 500 lbs.
Analysis Software:	RISA-3D (V17)

Final Loading Configuration:

The following equipment has been considered for the analysis of the mounts:

Mount Elevation (ft)	Equipment Elevation (ft)	Quantity	Manufacturer	Model	Status
96.75	98.00	4	KAelus	KA-6030	Added
		3	Samsung	MT6407-77A	Retained
		6	Commscope	JAHH-65B-R3B	
		3	Samsung	XXDWMM-12.5-65-8T-CBRS	
		3	Samsung	B5/B13 RRH-BR04C	
		3	Samsung	B2/B66A RRH-BR049	
		3	Commscope	CBC78T-DS-43-2X	
		3	RFS Celwave	DB-T1-6Z-8AB-0Z *	

* Equipment to be flush mounted directly to the Self Support. They are not mounted on mounts and are not included in this mount analysis.

The recent PMI reported existing OVP units. It is acceptable to install up to any three (3) of the OVP model numbers listed below as required at any location other than the mount face without affecting the structural capacity of the mount. If OVP units are installed on the mount face, a mount re-analysis may be required unless replacing an existing OVP.

Model Number	Ports	AKA
DB-B1-6C-12AB-0Z	6	OVP-6
RVZDC-6627-PF-48	12	OVP-12

Standard Conditions:

1. All engineering services are performed on the basis that the information provided to Colliers Engineering & Design and used in this analysis is current and correct. The existing equipment loading has been applied at locations determined from the supplied documentation. Any deviation from the loading locations specified in this report shall be communicated to Colliers Engineering & Design to verify deviation will not adversely impact the analysis.
2. Mounts are assumed to have been properly fabricated, installed and maintained in good condition, twist free and plumb in accordance with its original design and manufacturer's specifications.

Obvious safety and structural issues/deficiencies noticed at the time of the mount mapping and reported in the Mount Mapping Report are assumed to be corrected and documented as part of the PMI process and are not considered in the mount analysis.

The mount analysis and the mount mapping are not a condition assessment of the mount. Proper maintenance and condition assessments are still required post analysis.

3. For mount analyses completed from other data sources (including new replacement mounts) and not specifically mapped in accordance with the NSTD-446 Standard, the mounts are assumed to have been properly fabricated, installed and maintained in good condition, twist free and plumb in accordance with its original design and manufacturer's specifications.
4. All member connections are assumed to have been designed to meet or exceed the load carrying capacity of the connected member unless otherwise specified in this report.

5. The mount was checked up to, and including, the bolts that fasten it to the mount collar/attachment and threaded rod connections in collar members if applicable. Local deformation and interaction between the mount collar/attachment and the supporting tower structure are outside the scope of this analysis.
6. All services are performed, results obtained, and recommendations made in accordance with generally accepted engineering principles and practices. Colliers Engineering & Design is not responsible for the conclusion, opinions, and recommendations made by others based on the information supplied.
7. Structural Steel Grades have been assumed as follows, if applicable, unless otherwise noted in this analysis:
 - o Channel, Solid Round, Angle, Plate ASTM A36 (Gr. 36)
 - o HSS (Rectangular) ASTM 500 (Gr. B-46)
 - o Pipe ASTM A53 (Gr. B-35)
 - o Threaded Rod F1554 (Gr. 36)
 - o Bolts ASTM A325

Discrepancies between in-field conditions and the assumptions listed above may render this analysis invalid unless explicitly approved by Colliers Engineering & Design.

Analysis Results:

Component	Utilization %	Pass/Fail
Face Horizontal	27.0 %	Pass
Standoff Horizontal	13.1 %	Pass
Standoff Diagonal	8.7 %	Pass
Standoff Vertical	11.3 %	Pass
Standoff Plate	42.7 %	Pass
Tieback	17.4 %	Pass
Antenna Pipe	41.5 %	Pass
Mount Connection	13.9 %	Pass

Structure Rating – (Controlling Utilization of all Components)	42.7%
--	-------

Mount Steel (EPA)a per ANSI/TIA-222-H Section 2.6.11.2:

Ice Thickness (In)	Mount Pipes Excluded		Mount Pipes Included	
	Front (EPA)a (Sq. Ft.)	Side (EPA)a (Sq. Ft.)	Front (EPA)a (Sq. Ft.)	Side (EPA)a (Sq. Ft.)
0	14.2	10.7	23.3	19.8
0.5	22.3	17.9	35.3	30.9
1	29.8	24.6	46.6	41.4

Notes:

- (EPA)a values listed above may be used in the absence of more precise information
- (EPA)a values in the table above include 1 sector(s).
- Ka factors included in (EPA)a calculations

Requirements:

The existing mounts are **SUFFICIENT** for the final loading configuration shown in attachment 2 and do not require modifications. Additional requirements are noted below.

Contractor shall install the proposed filter units on new Site Pro 1 Dual Swivel Mount Kit (Part #: RRUDSM or EOR approved equivalent) in the location shown in the placement diagrams.

Contractor shall record all dimensions and member sizes requested in the Mount Geometry Verification Requirements section of the Mount Analysis report. Contractor shall provide the requested information to Colliers Engineering & Design for structural verification while on site. Contact EOR if these documents are not available to the general contractor.

Contractor shall inspect climbing facilities and safety climb, if present, and ensure they are in good condition. Contractor shall install safety climb wire rope guides in locations where wire rope is rubbing against the mount or mount-to-tower connection steel. Wire brush clean any observed corrosion and protect with two (2) coats of cold galvanization (Zinga or Zinc Kote). Contractor shall provide photos of wire rope guide installation as part of PMI documents. Contact EOR if additional guidance is required.

If required, ANSI/ASSP rigging plan review services compliant with the requirements of ANSI/TIA 322 are available for a Construction Class IV site or other. Separate review fees will apply.

Attachments:

1. **Contractor Required Post Installation Inspection (PMI) Report Deliverables**
2. Antenna Placement Diagrams
3. Mount Photos
4. Analysis Calculations

Mount Desktop – Post Modification Inspection (PMI) Report Requirements

Documents & Photos Required from Contractor – **Passing Mount Analysis**

Passing Mount Analysis requires a PMI due to a modification in loading.

Electronic pdf version of this can be downloaded at <https://pmi.vzwsmart.com>.

For additional questions and support, please reach out to pmisupport@colliersengineering.com

MDG #: 5000386730

SMART Project #: 10208065

Fuze Project ID: 17123711

Purpose – to provide SMART Tool structural vendor the proper documentation in order to complete the required Mount Desktop review of the Post Modification Inspection Report.

- Contractor is responsible for making certain the photos provided as noted below provide confirmation that the installation was completed in accordance with this Passing Mount Analysis.
- Contractor shall relay any data that can impact the performance of the mount, this includes safety issues.

Base Requirements:

- If installation will cause damage to the structure, the climbing facility, or safety climb if present or any installed system, SMART Tool vendor to be notified prior to install. Any special photos outside of the standard requirements will be indicated on the drawings.
- Provide “as built mount drawings” showing contractor’s name, contact information, preparer’s signature, and date. Any deviations from the drawings (Proposed modification) shall be shown. NOTE: If loading is different than what is conveyed in the passing mount analysis (MA) contact the SMART Tool vendor immediately.
- Each photo should be time and date stamped
- Photos should be high resolution.
- Contractor shall ensure that the safety climb wire rope is supported and not adversely impacted by the install of the modification components. This may involve the install of wire rope guides, or other items to protect the wire rope. If there is conflict, contact the SMART Tool engineer for recommendations.
- The PMI can be accessed at the following portal: <https://pmi.vzwsmart.com>

Photo Requirements:

- *Photos taken at ground level*
 - Photo of Gate Signs showing the tower owner, site name, and number.
 - Overall tower structure after installation.
 - Photos of the mount after installation; if the mounts are at different rad elevations, pictures must be provided for all elevations that equipment was installed.
- *Photos taken at Mount Elevation*
 - Photos showing the safety climb wire rope above and below the mount prior to installation.
 - Photos showing the climbing facility and safety climb if present.
 - Photos showing each individual sector after installation. Each entire sector shall be in one photo to show the interconnection of members.

- These photos shall also certify that the placement and geometry of the equipment on the mount is as depicted in the antenna placement diagram in this form.
- Photos that show the model number of each antenna and piece of equipment installed per sector.

Antenna & equipment placement and Geometry Confirmation:

- The contractor shall certify that the antenna & equipment placement and geometry is in accordance with the sketch and table as included in the mount analysis and noted below.
- ☐ The contractor certifies that the photos support and the equipment on the mount is as depicted on the sketch and table included in this form and with the mount analysis provided.

OR

- ☐ The contractor notes that the equipment on the mount is not in accordance with the sketch and has noted the differences below and provided photo documentation of any alterations.

Special Instructions / Validation as required from the MA or any other information the contractor deems necessary to share that was identified:

Issue:

Contractor shall record all dimensions and member sizes requested in the Mount Geometry Verification Requirements section of the Mount Analysis report. Contractor shall provide the requested information to Colliers Engineering & Design for structural verification while on site. Contact EOR if these documents are not available to the general contractor.

Contractor shall inspect climbing facilities and safety climb, if present, and ensure they are in good condition. Contractor shall install safety climb wire rope guides in locations where wire rope is rubbing against the mount or mount-to-tower connection steel. Wire brush clean any observed corrosion and protect with two (2) coats of cold galvanization (Zinga or Zinc Kote). Contractor shall provide photos of wire rope guide installation as part of PMI documents. Contact EOR if additional guidance is required.

Response:

Special Instruction Confirmation:

- ☐ The contractor has read and acknowledges the above special instructions.
- ☐ All hardware listed in the Special Instructions above (if applicable) has been properly installed, and the existing hardware was inspected.
- ☐ The material utilized was as specified in the SMART Tool engineering vendor Special Instructions above (if applicable) and included in the material certification folder is a packing list or invoice for these materials.

OR

☐ The material utilized was approved by a SMART Tool engineering vendor as an “equivalent” and this approval is included as part of the contractor submission.

Comments:

--

Contractor certifies that the climbing facility / safety climb was not damaged prior to starting work:

☐ Yes ☐ No

Contractor certifies no new damage created during the current installation:

☐ Yes ☐ No

Contractor to certify the condition of the safety climb and verify no damage when leaving the site:


☐ Safety Climb in Good Condition ☐ Safety Climb Damaged

Certifying Individual:

Company:	
Employee Name:	
Contact Phone:	
Email:	
Date:	



MOUNT FRONT VIEW



MOUNT GEOMETRY VERIFICATION

CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND MEMBER SIZES SHOWN IN THIS SKETCH. DOCUMENT ALL VARIATIONS OR DEVIATIONS VIA PHOTOS AND SKETCHS AND PROVIDE TO THE EOR FOR EVALUATION.

Sector: A

8/1/2023


Structure Type: Self Support

10208065



Mount Elev: 96.75

Page: 1



Ref#	Model	Height (in)	Width (in)	H Dist Frm L.	Pipe #	Pipe Pos V	Ant Pos	C. Ant Frm T.	Ant H Off	Status	Validation
A2	HBXX-6517DS-A2M	74.9	12	147	1	a	Front	36	0	Retained	12/16/2021
R6	B5/B13 RRH-BR04C	15	15	147	1	a	Behind	39	0	Retained	12/16/2021
A4	JAHH-65B-R3B	72	13.8	99	2	a	Front	39	7.5	Retained	12/16/2021
A4	JAHH-65B-R3B	72	13.8	99	2	b	Front	39	-7.5	Retained	12/16/2021
A3	MT6407-77A	35.1	16.1	51	3	a	Front	39	0	Retained	12/16/2021
R7	B2/B66A RRH-BR049	15	15	51	3	a	Behind	39	0	Retained	12/16/2021
A5	XXDWMM-12.5-65	12.3	8.7	3	4	a	Front	39	0	Retained	12/16/2021
M1	CBC78T-DS-43-2X	6.4	6.9		Member					Retained	12/16/2021


Sector: B

Structure Type: Self Support


10208065

Mount Elev: 96.75

Plan View



Front View - Looking at Structure



Ref#	Model	Height (in)	Width (in)	H Dist Frm L.	Pipe #	Pipe Pos V	Ant Pos	C. Ant Frm T.	Ant H Off	Status	Validation
A2	HBXX-6517DS-A2M	74.9	12	147	1	a	Front	36	0	Retained	12/16/2021
R6	B5/B13 RRH-BR04C	15	15	147	1	a	Behind	39	0	Retained	12/16/2021
A4	JAHH-65B-R3B	72	13.8	99	2	a	Front	39	7.5	Retained	12/16/2021
A4	JAHH-65B-R3B	72	13.8	99	2	b	Front	39	-7.5	Retained	12/16/2021
A1	KA-6030	10.6	3.2	99	2	a	Behind	36	5	Added	
A1	KA-6030	10.6	3.2	99	2	b	Behind	36	-5	Added	
A3	MT6407-77A	35.1	16.1	51	3	a	Front	39	0	Retained	12/16/2021
R7	B2/B66A RRH-BR049	15	15	51	3	a	Behind	39	0	Retained	12/16/2021
A5	XXDWMM-12.5-65	12.3	8.7	3	4	a	Front	39	0	Retained	12/16/2021

Sector: C

8/1/2023


Structure Type: Self Support

10208065





Mount Elev: 96.75

Page: 3




Ref#	Model	Height (in)	Width (in)	H Dist Frm L.	Pipe #	Pipe Pos V	Ant Pos	C. Ant Frm T.	Ant H Off	Status	Validation
A2	HBXX-6517DS-A2M	74.9	12	147	1	a	Front	36	0	Retained	12/16/2021
R6	B5/B13 RRH-BR04C	15	15	147	1	a	Behind	39	0	Retained	12/16/2021
A4	JAHH-65B-R3B	72	13.8	99	2	a	Front	39	7.5	Retained	12/16/2021
A4	JAHH-65B-R3B	72	13.8	99	2	b	Front	39	-7.5	Retained	12/16/2021
A1	KA-6030	10.6	3.2	99	2	b	Behind	36	5	Added	
A1	KA-6030	10.6	3.2	99	2	c	Behind	36	-5	Added	
A3	MT6407-77A	35.1	16.1	51	3	a	Front	39	0	Retained	12/16/2021
R7	B2/B66A RRH-BR049	15	15	51	3	a	Behind	39	0	Retained	12/16/2021
A5	XXDWMM-12.5-65	12.3	8.7	3	4	a	Front	39	0	Retained	12/16/2021






Envelope Only Solution

		SK - 1
		July 28, 2023 at 1:36 PM
		5000386730-VZW_MT_LOT_B_H.r3d






Code Check
(Env)

No Calc
> 1.0
.90-.1.0
.75-.90
.50-.75
0.-.50



Member Code Checks Displayed (Enveloped)
Envelope Only Solution

	SK - 2
	July 28, 2023 at 1:37 PM
	5000386730-VZW_MT_LOT_B_H.r3d



Member Shear Checks Displayed (Enveloped)
Envelope Only Solution

		SK - 3
		July 28, 2023 at 1:37 PM
		5000386730-VZW_MT_LOT_B_H.r3d

Basic Load Cases

	BLC Description	Category	X Gravity	Y Gravity	Z Gravity	Joint	Point	Distribut...	Area(Me...	Surface(...
1	Antenna D	None					42			
2	Antenna Di	None					42			
3	Antenna Wo (0 Deg)	None					42			
4	Antenna Wo (30 Deg)	None					42			
5	Antenna Wo (60 Deg)	None					42			
6	Antenna Wo (90 Deg)	None					42			
7	Antenna Wo (120 Deg)	None					42			
8	Antenna Wo (150 Deg)	None					42			
9	Antenna Wo (180 Deg)	None					42			
10	Antenna Wo (210 Deg)	None					42			
11	Antenna Wo (240 Deg)	None					42			
12	Antenna Wo (270 Deg)	None					42			
13	Antenna Wo (300 Deg)	None					42			
14	Antenna Wo (330 Deg)	None					42			
15	Antenna Wi (0 Deg)	None					42			
16	Antenna Wi (30 Deg)	None					42			
17	Antenna Wi (60 Deg)	None					42			
18	Antenna Wi (90 Deg)	None					42			
19	Antenna Wi (120 Deg)	None					42			
20	Antenna Wi (150 Deg)	None					42			
21	Antenna Wi (180 Deg)	None					42			
22	Antenna Wi (210 Deg)	None					42			
23	Antenna Wi (240 Deg)	None					42			
24	Antenna Wi (270 Deg)	None					42			
25	Antenna Wi (300 Deg)	None					42			
26	Antenna Wi (330 Deg)	None					42			
27	Antenna Wm (0 Deg)	None					42			
28	Antenna Wm (30 Deg)	None					42			
29	Antenna Wm (60 Deg)	None					42			
30	Antenna Wm (90 Deg)	None					42			
31	Antenna Wm (120 Deg)	None					42			
32	Antenna Wm (150 Deg)	None					42			
33	Antenna Wm (180 Deg)	None					42			
34	Antenna Wm (210 Deg)	None					42			
35	Antenna Wm (240 Deg)	None					42			
36	Antenna Wm (270 Deg)	None					42			
37	Antenna Wm (300 Deg)	None					42			
38	Antenna Wm (330 Deg)	None					42			
39	Structure D	None		-1						
40	Structure Di	None						28		
41	Structure Wo (0 Deg)	None						56		
42	Structure Wo (30 Deg)	None						56		
43	Structure Wo (60 Deg)	None						56		
44	Structure Wo (90 Deg)	None						56		
45	Structure Wo (120 Deg)	None						56		
46	Structure Wo (150 Deg)	None						56		
47	Structure Wo (180 Deg)	None						56		
48	Structure Wo (210 Deg)	None						56		
49	Structure Wo (240 Deg)	None						56		
50	Structure Wo (270 Deg)	None						56		
51	Structure Wo (300 Deg)	None						56		
52	Structure Wo (330 Deg)	None						56		
53	Structure Wi (0 Deg)	None						56		
54	Structure Wi (30 Deg)	None						56		
55	Structure Wi (60 Deg)	None						56		
56	Structure Wi (90 Deg)	None						56		
57	Structure Wi (120 Deg)	None						56		
58	Structure Wi (150 Deg)	None						56		
59	Structure Wi (180 Deg)	None						56		
60	Structure Wi (210 Deg)	None						56		

Basic Load Cases (Continued)

	BLC Description	Category	X Gravity	Y Gravity	Z Gravity	Joint	Point	Distribut...	Area(Me...	Surface(...
61	Structure Wi (240 Deg)	None						56		
62	Structure Wi (270 Deg)	None						56		
63	Structure Wi (300 Deg)	None						56		
64	Structure Wi (330 Deg)	None						56		
65	Structure Wm (0 Deg)	None						56		
66	Structure Wm (30 Deg)	None						56		
67	Structure Wm (60 Deg)	None						56		
68	Structure Wm (90 Deg)	None						56		
69	Structure Wm (120 Deg)	None						56		
70	Structure Wm (150 Deg)	None						56		
71	Structure Wm (180 Deg)	None						56		
72	Structure Wm (210 Deg)	None						56		
73	Structure Wm (240 Deg)	None						56		
74	Structure Wm (270 Deg)	None						56		
75	Structure Wm (300 Deg)	None						56		
76	Structure Wm (330 Deg)	None						56		
77	Lm1	None					1			
78	Lm2	None					1			
79	Lv1	None					1			
80	Lv2	None					1			
81	Antenna Ev	None					42			
82	Antenna Eh (0 Deg)	None					28			
83	Antenna Eh (90 Deg)	None					28			
84	Structure Ev	ELY								
85	Structure Eh (0 Deg)	ELZ			-0.03					
86	Structure Eh (90 Deg)	ELX	.03							

Load Combinations

	Description	S...	PDelta	S...B...Fa...	BLC	Fa...	BLC	Fa...	BLC	Fa...	BLC	Fa...	B...Fa...	B...Fa...	B...Fa...	B...Fa...	B...Fa...	B...Fa...
1	1.2D+1.0Wo (0 D...Y...	Y	Y	1	1.2	39	1.2	3	1	41	1							
2	1.2D+1.0Wo (30 ...Y...	Y	Y	1	1.2	39	1.2	4	1	42	1							
3	1.2D+1.0Wo (60 ...Y...	Y	Y	1	1.2	39	1.2	5	1	43	1							
4	1.2D+1.0Wo (90 ...Y...	Y	Y	1	1.2	39	1.2	6	1	44	1							
5	1.2D+1.0Wo (120...Y...	Y	Y	1	1.2	39	1.2	7	1	45	1							
6	1.2D+1.0Wo (150...Y...	Y	Y	1	1.2	39	1.2	8	1	46	1							
7	1.2D+1.0Wo (180...Y...	Y	Y	1	1.2	39	1.2	9	1	47	1							
8	1.2D+1.0Wo (210...Y...	Y	Y	1	1.2	39	1.2	10	1	48	1							
9	1.2D+1.0Wo (240...Y...	Y	Y	1	1.2	39	1.2	11	1	49	1							
10	1.2D+1.0Wo (270...Y...	Y	Y	1	1.2	39	1.2	12	1	50	1							
11	1.2D+1.0Wo (300...Y...	Y	Y	1	1.2	39	1.2	13	1	51	1							
12	1.2D+1.0Wo (330...Y...	Y	Y	1	1.2	39	1.2	14	1	52	1							
13	1.2D + 1.0Di + 1.0...Y...	Y	Y	1	1.2	39	1.2	2	1	40	1	15	1	53	1			
14	1.2D + 1.0Di + 1.0...Y...	Y	Y	1	1.2	39	1.2	2	1	40	1	16	1	54	1			
15	1.2D + 1.0Di + 1.0...Y...	Y	Y	1	1.2	39	1.2	2	1	40	1	17	1	55	1			
16	1.2D + 1.0Di + 1.0...Y...	Y	Y	1	1.2	39	1.2	2	1	40	1	18	1	56	1			
17	1.2D + 1.0Di + 1.0...Y...	Y	Y	1	1.2	39	1.2	2	1	40	1	19	1	57	1			
18	1.2D + 1.0Di + 1.0...Y...	Y	Y	1	1.2	39	1.2	2	1	40	1	20	1	58	1			
19	1.2D + 1.0Di + 1.0...Y...	Y	Y	1	1.2	39	1.2	2	1	40	1	21	1	59	1			
20	1.2D + 1.0Di + 1.0...Y...	Y	Y	1	1.2	39	1.2	2	1	40	1	22	1	60	1			
21	1.2D + 1.0Di + 1.0...Y...	Y	Y	1	1.2	39	1.2	2	1	40	1	23	1	61	1			
22	1.2D + 1.0Di + 1.0...Y...	Y	Y	1	1.2	39	1.2	2	1	40	1	24	1	62	1			
23	1.2D + 1.0Di + 1.0...Y...	Y	Y	1	1.2	39	1.2	2	1	40	1	25	1	63	1			
24	1.2D + 1.0Di + 1.0...Y...	Y	Y	1	1.2	39	1.2	2	1	40	1	26	1	64	1			
25	1.2D + 1.5Lm1 + ... Y...	Y	Y	1	1.2	39	1.2	77	1.5	27	1	65	1					
26	1.2D + 1.5Lm1 + ... Y...	Y	Y	1	1.2	39	1.2	77	1.5	28	1	66	1					
27	1.2D + 1.5Lm1 + ... Y...	Y	Y	1	1.2	39	1.2	77	1.5	29	1	67	1					
28	1.2D + 1.5Lm1 + ... Y...	Y	Y	1	1.2	39	1.2	77	1.5	30	1	68	1					
29	1.2D + 1.5Lm1 + ... Y...	Y	Y	1	1.2	39	1.2	77	1.5	31	1	69	1					
30	1.2D + 1.5Lm1 + ... Y...	Y	Y	1	1.2	39	1.2	77	1.5	32	1	70	1					
31	1.2D + 1.5Lm1 + ... Y...	Y	Y	1	1.2	39	1.2	77	1.5	33	1	71	1					
32	1.2D + 1.5Lm1 + ... Y...	Y	Y	1	1.2	39	1.2	77	1.5	34	1	72	1					

[illegible]

[illegible]

Joint Coordinates and Temperatures (Continued)

	Label	X [ft]	Y [ft]	Z [ft]	Temp [F]	Detach From Diap...
16	N16	-6	3.479167	2.630208	0	
17	N17	-2	0.145833	2.630208	0	
18	N18	-2	3.479167	2.630208	0	
19	N19	2	0.145833	2.630208	0	
20	N20	2	3.479167	2.630208	0	
21	N21	6	0.145833	2.630208	0	
22	N22	6	3.479167	2.630208	0	
23	N23	-2.5	0	2.380208	0	
24	N24	-2.5	3.333333	2.380208	0	
25	N25	2.5	0	2.380208	0	
26	N26	2.5	3.333333	2.380208	0	
27	N27	-2.5	0	1.958333	0	
28	N28	-2.5	3.333333	1.958333	0	
29	N29	2.5	0	1.958333	0	
30	N30	2.5	3.333333	1.958333	0	
31	N31	0	0	0.416667	0	
32	N32	0	3.333333	0.416667	0	
33	N33	-0.53125	0	0.416667	0	
34	N34	-0.53125	3.333333	0.416667	0	
35	N35	0.53125	0	0.416667	0	
36	N36	0.53125	3.333333	0.416667	0	
37	N37	-6	5.8125	2.630208	0	
38	N38	-2	5.8125	2.630208	0	
39	N39	2	5.8125	2.630208	0	
40	N40	6	5.8125	2.630208	0	
41	N41	-6	-2.1875	2.630208	0	
42	N42	-2	-2.1875	2.630208	0	
43	N43	2	-2.1875	2.630208	0	
44	N44	6	-2.1875	2.630208	0	
45	N45	-2.5	3.333333	2.005208	0	
46	N46	-2.5	0.145833	2.380208	0	
47	N47	-2.5	3.479167	2.380208	0	
48	N48	2.5	0.145833	2.380208	0	
49	N49	2.5	3.479167	2.380208	0	
50	N50	-3	3.479167	2.380208	0	
51	N51	3	3.479167	2.380208	0	
52	N54	4	0.145833	2.380208	0	
53	N56	-5.333333	3.479167	-9.237604	0	
54	N57	5.333333	3.479167	-9.237604	0	

Hot Rolled Steel Section Sets

	Label	Shape	Type	Design L...	Material	Design ...	A [in2]	Iyy [in4]	Izz [in4]	J [in4]
1	Face Horizontal	PIPE 2.5	None	None	Q235	Typical	1.61	1.45	1.45	2.89
2	Standoff Horizontal	PIPE 2.0	None	None	Q235	Typical	1.02	.627	.627	1.25
3	Standoff Diagonal	SR 0.75	None	None	Q235	Typical	.442	.016	.016	.031
4	Standoff Vertical	SR 0.625	None	None	Q235	Typical	.307	.007	.007	.015
5	Standoff Plate	PL5/8X3.5	None	None	Q235	Typical	2.188	.071	2.233	.253
6	Tieback	PIPE 2.0	None	None	Q235	Typical	1.02	.627	.627	1.25
7	Antenna Pipe	PIPE 2.0	None	None	Q235	Typical	1.02	.627	.627	1.25

Hot Rolled Steel Properties

	Label	E [ksi]	G [ksi]	Nu	Therm (/1E...	Density[k/ft...	Yield[ksi]	Ry	Fu[ksi]	Rt
1	A36 Gr.36	29000	11154	.3	.65	.49	36	1.5	58	1.2
2	A53 Gr. B	29000	11154	.3	.65	.49	35	1.5	60	1.2
3	A572 Gr.50	29000	11154	.3	.65	.49	50	1.1	65	1.1
4	A992	29000	11154	.3	.65	.49	50	1.1	65	1.1
5	A500 Gr. B 42	29000	11154	.3	.65	.49	42	1.4	58	1.3
6	A500 Gr. B 46	29000	11154	.3	.65	.49	46	1.4	58	1.3
7	Q235	29000	11154	.3	.65	.49	35	1.5	58	1.2

Member Primary Data

	Label	I Joint	J Joint	K Joint	Rotate(deg)	Section/Shape	Type	Design List	Material	Design Rules
1	M1	N4	N3			Face Horizont...	None	None	Q235	Typical
2	M2	N6	N5			Face Horizont...	None	None	Q235	Typical
3	M3	N28	N34			Standoff Hori...	None	None	Q235	Typical
4	M4	N27	N33			Standoff Hori...	None	None	Q235	Typical
5	M5	N29	N35			Standoff Hori...	None	None	Q235	Typical
6	M6	N30	N36			Standoff Hori...	None	None	Q235	Typical
7	M7	N33	N28			Standoff Diag...	None	None	Q235	Typical
8	M8	N34	N27			Standoff Diag...	None	None	Q235	Typical
9	M9	N35	N30			Standoff Diag...	None	None	Q235	Typical
10	M10	N29	N36			Standoff Diag...	None	None	Q235	Typical
11	M11	N27	N28			Standoff Verti...	None	None	Q235	Typical
12	M12	N33	N34			Standoff Verti...	None	None	Q235	Typical
13	M13	N35	N36			Standoff Verti...	None	None	Q235	Typical
14	M14	N29	N30			Standoff Verti...	None	None	Q235	Typical
15	M15	N24	N28		90	Standoff Plate	None	None	Q235	Typical
16	M16	N23	N27		90	Standoff Plate	None	None	Q235	Typical
17	M17	N25	N29		90	Standoff Plate	None	None	Q235	Typical
18	M18	N26	N30		90	Standoff Plate	None	None	Q235	Typical
19	M19	N34	N32		90	Standoff Plate	None	None	Q235	Typical
20	M20	N36	N32		90	Standoff Plate	None	None	Q235	Typical
21	M21	N33	N31		90	Standoff Plate	None	None	Q235	Typical
22	M22	N35	N31		90	Standoff Plate	None	None	Q235	Typical
23	M23	N50	N56			Tieback	None	None	Q235	Typical
24	M24	N51	N57			Tieback	None	None	Q235	Typical
25	MP1A	N40	N44			Antenna Pipe	None	None	Q235	Typical
26	MP2A	N39	N43			Antenna Pipe	None	None	Q235	Typical
27	MP3A	N38	N42			Antenna Pipe	None	None	Q235	Typical
28	MP4A	N37	N41			Antenna Pipe	None	None	Q235	Typical
29	M29	N7	N15			RIGID	None	None	RIGID	Typical
30	M30	N8	N16			RIGID	None	None	RIGID	Typical
31	M31	N10	N18			RIGID	None	None	RIGID	Typical
32	M32	N9	N17			RIGID	None	None	RIGID	Typical
33	M33	N12	N20			RIGID	None	None	RIGID	Typical
34	M34	N11	N19			RIGID	None	None	RIGID	Typical
35	M35	N14	N22			RIGID	None	None	RIGID	Typical
36	M36	N13	N21			RIGID	None	None	RIGID	Typical
37	M37	N31	N1			RIGID	None	None	RIGID	Typical
38	M38	N32	N2			RIGID	None	None	RIGID	Typical
39	M39	N24	N47			RIGID	None	None	RIGID	Typical
40	M40	N23	N46			RIGID	None	None	RIGID	Typical
41	M41	N26	N49			RIGID	None	None	RIGID	Typical
42	M42	N25	N48			RIGID	None	None	RIGID	Typical
43	M43	N32	N2			RIGID	None	None	RIGID	Typical
44	M44	N31	N1			RIGID	None	None	RIGID	Typical

Member Advanced Data

	Label	I Release	J Release	I Offset[in]	J Offset[in]	T/C Only	Physical	Defl Ratio	Options	Analysis ...	Inactive	Seismi...
1	M1						Yes	** NA **				None
2	M2						Yes	** NA **				None
3	M3						Yes	** NA **				None
4	M4						Yes	** NA **				None
5	M5						Yes	** NA **				None
6	M6						Yes	** NA **				None
7	M7	BenPIN	BenPIN			Euler Bu...	Yes	** NA **				None
8	M8	BenPIN	BenPIN			Euler Bu...	Yes	** NA **				None
9	M9	BenPIN	BenPIN			Euler Bu...	Yes	** NA **				None
10	M10	BenPIN	BenPIN			Euler Bu...	Yes	** NA **				None
11	M11	BenPIN	BenPIN				Yes	** NA **				None
12	M12	BenPIN	BenPIN				Yes	** NA **				None
13	M13	BenPIN	BenPIN				Yes	** NA **				None

Member Advanced Data (Continued)

	Label	I Release	J Release	I Offset(in)	J Offset(in)	T/C Only	Physical	Defl Ratio	Options	Analysis ...	Inactive	Seismi...
14	M14	BenPIN	BenPIN				Yes	** NA **				None
15	M15						Yes	** NA **				None
16	M16						Yes	** NA **				None
17	M17						Yes	** NA **				None
18	M18						Yes	** NA **				None
19	M19						Yes	** NA **				None
20	M20						Yes	** NA **				None
21	M21						Yes	** NA **				None
22	M22						Yes	** NA **				None
23	M23	BenPIN					Yes	** NA **				None
24	M24	BenPIN					Yes	** NA **				None
25	MP1A						Yes	** NA **				None
26	MP2A						Yes	** NA **				None
27	MP3A						Yes	** NA **				None
28	MP4A						Yes	** NA **				None
29	M29						Yes	** NA **				None
30	M30						Yes	** NA **				None
31	M31						Yes	** NA **				None
32	M32						Yes	** NA **				None
33	M33						Yes	** NA **				None
34	M34						Yes	** NA **				None
35	M35						Yes	** NA **				None
36	M36						Yes	** NA **				None
37	M37						Yes	** NA **			Inactive	None
38	M38						Yes	** NA **			Inactive	None
39	M39		OOOXOO				Yes	** NA **				None
40	M40		OOOXOO				Yes	** NA **				None
41	M41		OOOXOO				Yes	** NA **				None
42	M42		OOOXOO				Yes	** NA **				None
43	M43						Yes	** NA **				None
44	M44						Yes	** NA **				None

Member Distributed Loads (BLC 40 : Structure Di)

	Member Label	Direction	Start Magnitude[lb/ft.F,ksf]	End Magnitude[lb/ft...	Start Location[ft.%]	End Location[ft.%]
1	M1	Y	-5.426	-5.426	0	%100
2	M2	Y	-5.426	-5.426	0	%100
3	M3	Y	-4.746	-4.746	0	%100
4	M4	Y	-4.746	-4.746	0	%100
5	M5	Y	-4.746	-4.746	0	%100
6	M6	Y	-4.746	-4.746	0	%100
7	M7	Y	-2.535	-2.535	0	%100
8	M8	Y	-2.535	-2.535	0	%100
9	M9	Y	-2.535	-2.535	0	%100
10	M10	Y	-2.535	-2.535	0	%100
11	M11	Y	-2.365	-2.365	0	%100
12	M12	Y	-2.365	-2.365	0	%100
13	M13	Y	-2.365	-2.365	0	%100
14	M14	Y	-2.365	-2.365	0	%100
15	M15	Y	-6.352	-6.352	0	%100
16	M16	Y	-6.352	-6.352	0	%100
17	M17	Y	-6.352	-6.352	0	%100
18	M18	Y	-6.352	-6.352	0	%100
19	M19	Y	-6.352	-6.352	0	%100
20	M20	Y	-6.352	-6.352	0	%100
21	M21	Y	-6.352	-6.352	0	%100
22	M22	Y	-6.352	-6.352	0	%100
23	M23	Y	-4.746	-4.746	0	%100
24	M24	Y	-4.746	-4.746	0	%100
25	MP1A	Y	-4.746	-4.746	0	%100
26	MP2A	Y	-4.746	-4.746	0	%100
27	MP3A	Y	-4.746	-4.746	0	%100

Member Distributed Loads (BLC 40 : Structure Di) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft.F,ksf]	End Magnitude[lb/ft...	Start Location[ft.%]	End Location[ft.%]
28	MP4A	Y	-4.746	-4.746	0	%100

Member Distributed Loads (BLC 41 : Structure Wo (0 Deg))

	Member Label	Direction	Start Magnitude[lb/ft.F,ksf]	End Magnitude[lb/ft...	Start Location[ft.%]	End Location[ft.%]
1	M1	X	0	0	0	%100
2	M1	Z	-8.731	-8.731	0	%100
3	M2	X	0	0	0	%100
4	M2	Z	-8.731	-8.731	0	%100
5	M3	X	0	0	0	%100
6	M3	Z	-3.447	-3.447	0	%100
7	M4	X	0	0	0	%100
8	M4	Z	-3.447	-3.447	0	%100
9	M5	X	0	0	0	%100
10	M5	Z	-3.447	-3.447	0	%100
11	M6	X	0	0	0	%100
12	M6	Z	-3.447	-3.447	0	%100
13	M7	X	0	0	0	%100
14	M7	Z	-1.966	-1.966	0	%100
15	M8	X	0	0	0	%100
16	M8	Z	-1.966	-1.966	0	%100
17	M9	X	0	0	0	%100
18	M9	Z	-1.966	-1.966	0	%100
19	M10	X	0	0	0	%100
20	M10	Z	-1.966	-1.966	0	%100
21	M11	X	0	0	0	%100
22	M11	Z	-1.898	-1.898	0	%100
23	M12	X	0	0	0	%100
24	M12	Z	-1.898	-1.898	0	%100
25	M13	X	0	0	0	%100
26	M13	Z	-1.898	-1.898	0	%100
27	M14	X	0	0	0	%100
28	M14	Z	-1.898	-1.898	0	%100
29	M15	X	0	0	0	%100
30	M15	Z	0	0	0	%100
31	M16	X	0	0	0	%100
32	M16	Z	0	0	0	%100
33	M17	X	0	0	0	%100
34	M17	Z	0	0	0	%100
35	M18	X	0	0	0	%100
36	M18	Z	0	0	0	%100
37	M19	X	0	0	0	%100
38	M19	Z	-1.898	-1.898	0	%100
39	M20	X	0	0	0	%100
40	M20	Z	-1.898	-1.898	0	%100
41	M21	X	0	0	0	%100
42	M21	Z	-1.898	-1.898	0	%100
43	M22	X	0	0	0	%100
44	M22	Z	-1.898	-1.898	0	%100
45	M23	X	0	0	0	%100
46	M23	Z	-.28	-.28	0	%100
47	M24	X	0	0	0	%100
48	M24	Z	-.28	-.28	0	%100
49	MP1A	X	0	0	0	%100
50	MP1A	Z	-7.213	-7.213	0	%100
51	MP2A	X	0	0	0	%100
52	MP2A	Z	-7.213	-7.213	0	%100
53	MP3A	X	0	0	0	%100
54	MP3A	Z	-7.213	-7.213	0	%100
55	MP4A	X	0	0	0	%100
56	MP4A	Z	-7.213	-7.213	0	%100

Member Distributed Loads (BLC 42 : Structure Wo (30 Deg))

	Member Label	Direction	Start Magnitude[lb/ft.F,ksf]	End Magnitude[lb/ft...	Start Location[ft.%]	End Location[ft.%]
1	M1	X	3.274	3.274	0	%100
2	M1	Z	-5.671	-5.671	0	%100
3	M2	X	3.274	3.274	0	%100
4	M2	Z	-5.671	-5.671	0	%100
5	M3	X	.388	.388	0	%100
6	M3	Z	-.672	-.672	0	%100
7	M4	X	.388	.388	0	%100
8	M4	Z	-.672	-.672	0	%100
9	M5	X	2.726	2.726	0	%100
10	M5	Z	-4.721	-4.721	0	%100
11	M6	X	2.726	2.726	0	%100
12	M6	Z	-4.721	-4.721	0	%100
13	M7	X	.786	.786	0	%100
14	M7	Z	-1.361	-1.361	0	%100
15	M8	X	.786	.786	0	%100
16	M8	Z	-1.361	-1.361	0	%100
17	M9	X	1.131	1.131	0	%100
18	M9	Z	-1.959	-1.959	0	%100
19	M10	X	1.131	1.131	0	%100
20	M10	Z	-1.959	-1.959	0	%100
21	M11	X	.949	.949	0	%100
22	M11	Z	-1.644	-1.644	0	%100
23	M12	X	.949	.949	0	%100
24	M12	Z	-1.644	-1.644	0	%100
25	M13	X	.949	.949	0	%100
26	M13	Z	-1.644	-1.644	0	%100
27	M14	X	.949	.949	0	%100
28	M14	Z	-1.644	-1.644	0	%100
29	M15	X	.237	.237	0	%100
30	M15	Z	-.411	-.411	0	%100
31	M16	X	.237	.237	0	%100
32	M16	Z	-.411	-.411	0	%100
33	M17	X	.237	.237	0	%100
34	M17	Z	-.411	-.411	0	%100
35	M18	X	.237	.237	0	%100
36	M18	Z	-.411	-.411	0	%100
37	M19	X	.712	.712	0	%100
38	M19	Z	-1.233	-1.233	0	%100
39	M20	X	.712	.712	0	%100
40	M20	Z	-1.233	-1.233	0	%100
41	M21	X	.712	.712	0	%100
42	M21	Z	-1.233	-1.233	0	%100
43	M22	X	.712	.712	0	%100
44	M22	Z	-1.233	-1.233	0	%100
45	M23	X	1.574	1.574	0	%100
46	M23	Z	-2.727	-2.727	0	%100
47	M24	X	.369	.369	0	%100
48	M24	Z	-.638	-.638	0	%100
49	MP1A	X	3.606	3.606	0	%100
50	MP1A	Z	-6.247	-6.247	0	%100
51	MP2A	X	3.606	3.606	0	%100
52	MP2A	Z	-6.247	-6.247	0	%100
53	MP3A	X	3.606	3.606	0	%100
54	MP3A	Z	-6.247	-6.247	0	%100
55	MP4A	X	3.606	3.606	0	%100
56	MP4A	Z	-6.247	-6.247	0	%100

Member Distributed Loads (BLC 43 : Structure Wo (60 Deg))

	Member Label	Direction	Start Magnitude[lb/ft.F,ksf]	End Magnitude[lb/ft...	Start Location[ft.%]	End Location[ft.%]
1	M1	X	1.89	1.89	0	%100
2	M1	Z	-1.091	-1.091	0	%100
3	M2	X	1.89	1.89	0	%100

Member Distributed Loads (BLC 43 : Structure Wo (60 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft.F,ksf]	End Magnitude[lb/ft...	Start Location[ft.%]	End Location[ft.%]
4	M2	Z	-1.091	-1.091	0	%100
5	M3	X	.095	.095	0	%100
6	M3	Z	-.055	-.055	0	%100
7	M4	X	.095	.095	0	%100
8	M4	Z	-.055	-.055	0	%100
9	M5	X	4.144	4.144	0	%100
10	M5	Z	-2.393	-2.393	0	%100
11	M6	X	4.144	4.144	0	%100
12	M6	Z	-2.393	-2.393	0	%100
13	M7	X	1.276	1.276	0	%100
14	M7	Z	-.737	-.737	0	%100
15	M8	X	1.276	1.276	0	%100
16	M8	Z	-.737	-.737	0	%100
17	M9	X	1.873	1.873	0	%100
18	M9	Z	-1.082	-1.082	0	%100
19	M10	X	1.873	1.873	0	%100
20	M10	Z	-1.082	-1.082	0	%100
21	M11	X	1.644	1.644	0	%100
22	M11	Z	-.949	-.949	0	%100
23	M12	X	1.644	1.644	0	%100
24	M12	Z	-.949	-.949	0	%100
25	M13	X	1.644	1.644	0	%100
26	M13	Z	-.949	-.949	0	%100
27	M14	X	1.644	1.644	0	%100
28	M14	Z	-.949	-.949	0	%100
29	M15	X	1.233	1.233	0	%100
30	M15	Z	-.712	-.712	0	%100
31	M16	X	1.233	1.233	0	%100
32	M16	Z	-.712	-.712	0	%100
33	M17	X	1.233	1.233	0	%100
34	M17	Z	-.712	-.712	0	%100
35	M18	X	1.233	1.233	0	%100
36	M18	Z	-.712	-.712	0	%100
37	M19	X	.411	.411	0	%100
38	M19	Z	-.237	-.237	0	%100
39	M20	X	.411	.411	0	%100
40	M20	Z	-.237	-.237	0	%100
41	M21	X	.411	.411	0	%100
42	M21	Z	-.237	-.237	0	%100
43	M22	X	.411	.411	0	%100
44	M22	Z	-.237	-.237	0	%100
45	M23	X	5.608	5.608	0	%100
46	M23	Z	-3.238	-3.238	0	%100
47	M24	X	3.519	3.519	0	%100
48	M24	Z	-2.032	-2.032	0	%100
49	MP1A	X	6.247	6.247	0	%100
50	MP1A	Z	-3.606	-3.606	0	%100
51	MP2A	X	6.247	6.247	0	%100
52	MP2A	Z	-3.606	-3.606	0	%100
53	MP3A	X	6.247	6.247	0	%100
54	MP3A	Z	-3.606	-3.606	0	%100
55	MP4A	X	6.247	6.247	0	%100
56	MP4A	Z	-3.606	-3.606	0	%100

Member Distributed Loads (BLC 44 : Structure Wo (90 Deg))

	Member Label	Direction	Start Magnitude[lb/ft.F,ksf]	End Magnitude[lb/ft...	Start Location[ft.%]	End Location[ft.%]
1	M1	X	0	0	0	%100
2	M1	Z	0	0	0	%100
3	M2	X	0	0	0	%100
4	M2	Z	0	0	0	%100
5	M3	X	2.114	2.114	0	%100
6	M3	Z	0	0	0	%100

Member Distributed Loads (BLC 44 : Structure Wo (90 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft.F,ksf]	End Magnitude[lb/ft...	Start Location(ft,%)	End Location(ft,%)
7	M4	X	2.114	2.114	0	%100
8	M4	Z	0	0	0	%100
9	M5	X	2.114	2.114	0	%100
10	M5	Z	0	0	0	%100
11	M6	X	2.114	2.114	0	%100
12	M6	Z	0	0	0	%100
13	M7	X	1.769	1.769	0	%100
14	M7	Z	0	0	0	%100
15	M8	X	1.769	1.769	0	%100
16	M8	Z	0	0	0	%100
17	M9	X	1.769	1.769	0	%100
18	M9	Z	0	0	0	%100
19	M10	X	1.769	1.769	0	%100
20	M10	Z	0	0	0	%100
21	M11	X	1.898	1.898	0	%100
22	M11	Z	0	0	0	%100
23	M12	X	1.898	1.898	0	%100
24	M12	Z	0	0	0	%100
25	M13	X	1.898	1.898	0	%100
26	M13	Z	0	0	0	%100
27	M14	X	1.898	1.898	0	%100
28	M14	Z	0	0	0	%100
29	M15	X	1.898	1.898	0	%100
30	M15	Z	0	0	0	%100
31	M16	X	1.898	1.898	0	%100
32	M16	Z	0	0	0	%100
33	M17	X	1.898	1.898	0	%100
34	M17	Z	0	0	0	%100
35	M18	X	1.898	1.898	0	%100
36	M18	Z	0	0	0	%100
37	M19	X	0	0	0	%100
38	M19	Z	0	0	0	%100
39	M20	X	0	0	0	%100
40	M20	Z	0	0	0	%100
41	M21	X	0	0	0	%100
42	M21	Z	0	0	0	%100
43	M22	X	0	0	0	%100
44	M22	Z	0	0	0	%100
45	M23	X	6.933	6.933	0	%100
46	M23	Z	0	0	0	%100
47	M24	X	6.933	6.933	0	%100
48	M24	Z	0	0	0	%100
49	MP1A	X	7.213	7.213	0	%100
50	MP1A	Z	0	0	0	%100
51	MP2A	X	7.213	7.213	0	%100
52	MP2A	Z	0	0	0	%100
53	MP3A	X	7.213	7.213	0	%100
54	MP3A	Z	0	0	0	%100
55	MP4A	X	7.213	7.213	0	%100
56	MP4A	Z	0	0	0	%100

Member Distributed Loads (BLC 45 : Structure Wo (120 Deg))

	Member Label	Direction	Start Magnitude[lb/ft.F,ksf]	End Magnitude[lb/ft...	Start Location(ft,%)	End Location(ft,%)
1	M1	X	1.89	1.89	0	%100
2	M1	Z	1.091	1.091	0	%100
3	M2	X	1.89	1.89	0	%100
4	M2	Z	1.091	1.091	0	%100
5	M3	X	4.144	4.144	0	%100
6	M3	Z	2.393	2.393	0	%100
7	M4	X	4.144	4.144	0	%100
8	M4	Z	2.393	2.393	0	%100
9	M5	X	.095	.095	0	%100

Member Distributed Loads (BLC 45 : Structure Wo (120 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft.F.ksf]	End Magnitude[lb/ft...	Start Location[ft.%]	End Location[ft.%]
10	M5	Z	.055	.055	0	%100
11	M6	X	.095	.095	0	%100
12	M6	Z	.055	.055	0	%100
13	M7	X	1.873	1.873	0	%100
14	M7	Z	1.082	1.082	0	%100
15	M8	X	1.873	1.873	0	%100
16	M8	Z	1.082	1.082	0	%100
17	M9	X	1.276	1.276	0	%100
18	M9	Z	.737	.737	0	%100
19	M10	X	1.276	1.276	0	%100
20	M10	Z	.737	.737	0	%100
21	M11	X	1.644	1.644	0	%100
22	M11	Z	.949	.949	0	%100
23	M12	X	1.644	1.644	0	%100
24	M12	Z	.949	.949	0	%100
25	M13	X	1.644	1.644	0	%100
26	M13	Z	.949	.949	0	%100
27	M14	X	1.644	1.644	0	%100
28	M14	Z	.949	.949	0	%100
29	M15	X	1.233	1.233	0	%100
30	M15	Z	.712	.712	0	%100
31	M16	X	1.233	1.233	0	%100
32	M16	Z	.712	.712	0	%100
33	M17	X	1.233	1.233	0	%100
34	M17	Z	.712	.712	0	%100
35	M18	X	1.233	1.233	0	%100
36	M18	Z	.712	.712	0	%100
37	M19	X	.411	.411	0	%100
38	M19	Z	.237	.237	0	%100
39	M20	X	.411	.411	0	%100
40	M20	Z	.237	.237	0	%100
41	M21	X	.411	.411	0	%100
42	M21	Z	.237	.237	0	%100
43	M22	X	.411	.411	0	%100
44	M22	Z	.237	.237	0	%100
45	M23	X	3.519	3.519	0	%100
46	M23	Z	2.032	2.032	0	%100
47	M24	X	5.608	5.608	0	%100
48	M24	Z	3.238	3.238	0	%100
49	MP1A	X	6.247	6.247	0	%100
50	MP1A	Z	3.606	3.606	0	%100
51	MP2A	X	6.247	6.247	0	%100
52	MP2A	Z	3.606	3.606	0	%100
53	MP3A	X	6.247	6.247	0	%100
54	MP3A	Z	3.606	3.606	0	%100
55	MP4A	X	6.247	6.247	0	%100
56	MP4A	Z	3.606	3.606	0	%100

Member Distributed Loads (BLC 46 : Structure Wo (150 Deg))

	Member Label	Direction	Start Magnitude[lb/ft.F.ksf]	End Magnitude[lb/ft...	Start Location[ft.%]	End Location[ft.%]
1	M1	X	3.274	3.274	0	%100
2	M1	Z	5.671	5.671	0	%100
3	M2	X	3.274	3.274	0	%100
4	M2	Z	5.671	5.671	0	%100
5	M3	X	2.726	2.726	0	%100
6	M3	Z	4.721	4.721	0	%100
7	M4	X	2.726	2.726	0	%100
8	M4	Z	4.721	4.721	0	%100
9	M5	X	.388	.388	0	%100
10	M5	Z	.672	.672	0	%100
11	M6	X	.388	.388	0	%100
12	M6	Z	.672	.672	0	%100

Member Distributed Loads (BLC 46 : Structure Wo (150 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft,F,ksf]	End Magnitude[lb/ft...	Start Location[ft, %]	End Location[ft, %]
13	M7	X	1.131	1.131	0	%100
14	M7	Z	1.959	1.959	0	%100
15	M8	X	1.131	1.131	0	%100
16	M8	Z	1.959	1.959	0	%100
17	M9	X	.786	.786	0	%100
18	M9	Z	1.361	1.361	0	%100
19	M10	X	.786	.786	0	%100
20	M10	Z	1.361	1.361	0	%100
21	M11	X	.949	.949	0	%100
22	M11	Z	1.644	1.644	0	%100
23	M12	X	.949	.949	0	%100
24	M12	Z	1.644	1.644	0	%100
25	M13	X	.949	.949	0	%100
26	M13	Z	1.644	1.644	0	%100
27	M14	X	.949	.949	0	%100
28	M14	Z	1.644	1.644	0	%100
29	M15	X	.237	.237	0	%100
30	M15	Z	.411	.411	0	%100
31	M16	X	.237	.237	0	%100
32	M16	Z	.411	.411	0	%100
33	M17	X	.237	.237	0	%100
34	M17	Z	.411	.411	0	%100
35	M18	X	.237	.237	0	%100
36	M18	Z	.411	.411	0	%100
37	M19	X	.712	.712	0	%100
38	M19	Z	1.233	1.233	0	%100
39	M20	X	.712	.712	0	%100
40	M20	Z	1.233	1.233	0	%100
41	M21	X	.712	.712	0	%100
42	M21	Z	1.233	1.233	0	%100
43	M22	X	.712	.712	0	%100
44	M22	Z	1.233	1.233	0	%100
45	M23	X	.369	.369	0	%100
46	M23	Z	.638	.638	0	%100
47	M24	X	1.574	1.574	0	%100
48	M24	Z	2.727	2.727	0	%100
49	MP1A	X	3.606	3.606	0	%100
50	MP1A	Z	6.247	6.247	0	%100
51	MP2A	X	3.606	3.606	0	%100
52	MP2A	Z	6.247	6.247	0	%100
53	MP3A	X	3.606	3.606	0	%100
54	MP3A	Z	6.247	6.247	0	%100
55	MP4A	X	3.606	3.606	0	%100
56	MP4A	Z	6.247	6.247	0	%100

Member Distributed Loads (BLC 47 : Structure Wo (180 Deg))

	Member Label	Direction	Start Magnitude[lb/ft,F,ksf]	End Magnitude[lb/ft...	Start Location[ft, %]	End Location[ft, %]
1	M1	X	0	0	0	%100
2	M1	Z	8.731	8.731	0	%100
3	M2	X	0	0	0	%100
4	M2	Z	8.731	8.731	0	%100
5	M3	X	0	0	0	%100
6	M3	Z	3.447	3.447	0	%100
7	M4	X	0	0	0	%100
8	M4	Z	3.447	3.447	0	%100
9	M5	X	0	0	0	%100
10	M5	Z	3.447	3.447	0	%100
11	M6	X	0	0	0	%100
12	M6	Z	3.447	3.447	0	%100
13	M7	X	0	0	0	%100
14	M7	Z	1.966	1.966	0	%100
15	M8	X	0	0	0	%100

Member Distributed Loads (BLC 47 : Structure Wo (180 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft.F,ksf]	End Magnitude[lb/ft...	Start Location[ft, %]	End Location[ft, %]
16	M8	Z	1.966	1.966	0	%100
17	M9	X	0	0	0	%100
18	M9	Z	1.966	1.966	0	%100
19	M10	X	0	0	0	%100
20	M10	Z	1.966	1.966	0	%100
21	M11	X	0	0	0	%100
22	M11	Z	1.898	1.898	0	%100
23	M12	X	0	0	0	%100
24	M12	Z	1.898	1.898	0	%100
25	M13	X	0	0	0	%100
26	M13	Z	1.898	1.898	0	%100
27	M14	X	0	0	0	%100
28	M14	Z	1.898	1.898	0	%100
29	M15	X	0	0	0	%100
30	M15	Z	0	0	0	%100
31	M16	X	0	0	0	%100
32	M16	Z	0	0	0	%100
33	M17	X	0	0	0	%100
34	M17	Z	0	0	0	%100
35	M18	X	0	0	0	%100
36	M18	Z	0	0	0	%100
37	M19	X	0	0	0	%100
38	M19	Z	1.898	1.898	0	%100
39	M20	X	0	0	0	%100
40	M20	Z	1.898	1.898	0	%100
41	M21	X	0	0	0	%100
42	M21	Z	1.898	1.898	0	%100
43	M22	X	0	0	0	%100
44	M22	Z	1.898	1.898	0	%100
45	M23	X	0	0	0	%100
46	M23	Z	.28	.28	0	%100
47	M24	X	0	0	0	%100
48	M24	Z	.28	.28	0	%100
49	MP1A	X	0	0	0	%100
50	MP1A	Z	7.213	7.213	0	%100
51	MP2A	X	0	0	0	%100
52	MP2A	Z	7.213	7.213	0	%100
53	MP3A	X	0	0	0	%100
54	MP3A	Z	7.213	7.213	0	%100
55	MP4A	X	0	0	0	%100
56	MP4A	Z	7.213	7.213	0	%100

Member Distributed Loads (BLC 48 : Structure Wo (210 Deg))

	Member Label	Direction	Start Magnitude[lb/ft.F,ksf]	End Magnitude[lb/ft...	Start Location[ft, %]	End Location[ft, %]
1	M1	X	-3.274	-3.274	0	%100
2	M1	Z	5.671	5.671	0	%100
3	M2	X	-3.274	-3.274	0	%100
4	M2	Z	5.671	5.671	0	%100
5	M3	X	-.388	-.388	0	%100
6	M3	Z	.672	.672	0	%100
7	M4	X	-.388	-.388	0	%100
8	M4	Z	.672	.672	0	%100
9	M5	X	-2.726	-2.726	0	%100
10	M5	Z	4.721	4.721	0	%100
11	M6	X	-2.726	-2.726	0	%100
12	M6	Z	4.721	4.721	0	%100
13	M7	X	-.786	-.786	0	%100
14	M7	Z	1.361	1.361	0	%100
15	M8	X	-.786	-.786	0	%100
16	M8	Z	1.361	1.361	0	%100
17	M9	X	-1.131	-1.131	0	%100
18	M9	Z	1.959	1.959	0	%100

Member Distributed Loads (BLC 48 : Structure Wo (210 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft.F,ksf]	End Magnitude[lb/ft...	Start Location[ft, %]	End Location[ft, %]
19	M10	X	-1.131	-1.131	0	%100
20	M10	Z	1.959	1.959	0	%100
21	M11	X	-.949	-.949	0	%100
22	M11	Z	1.644	1.644	0	%100
23	M12	X	-.949	-.949	0	%100
24	M12	Z	1.644	1.644	0	%100
25	M13	X	-.949	-.949	0	%100
26	M13	Z	1.644	1.644	0	%100
27	M14	X	-.949	-.949	0	%100
28	M14	Z	1.644	1.644	0	%100
29	M15	X	-.237	-.237	0	%100
30	M15	Z	.411	.411	0	%100
31	M16	X	-.237	-.237	0	%100
32	M16	Z	.411	.411	0	%100
33	M17	X	-.237	-.237	0	%100
34	M17	Z	.411	.411	0	%100
35	M18	X	-.237	-.237	0	%100
36	M18	Z	.411	.411	0	%100
37	M19	X	-.712	-.712	0	%100
38	M19	Z	1.233	1.233	0	%100
39	M20	X	-.712	-.712	0	%100
40	M20	Z	1.233	1.233	0	%100
41	M21	X	-.712	-.712	0	%100
42	M21	Z	1.233	1.233	0	%100
43	M22	X	-.712	-.712	0	%100
44	M22	Z	1.233	1.233	0	%100
45	M23	X	-1.574	-1.574	0	%100
46	M23	Z	2.727	2.727	0	%100
47	M24	X	-.369	-.369	0	%100
48	M24	Z	.638	.638	0	%100
49	MP1A	X	-3.606	-3.606	0	%100
50	MP1A	Z	6.247	6.247	0	%100
51	MP2A	X	-3.606	-3.606	0	%100
52	MP2A	Z	6.247	6.247	0	%100
53	MP3A	X	-3.606	-3.606	0	%100
54	MP3A	Z	6.247	6.247	0	%100
55	MP4A	X	-3.606	-3.606	0	%100
56	MP4A	Z	6.247	6.247	0	%100

Member Distributed Loads (BLC 49 : Structure Wo (240 Deg))

	Member Label	Direction	Start Magnitude[lb/ft.F,ksf]	End Magnitude[lb/ft...	Start Location[ft, %]	End Location[ft, %]
1	M1	X	-1.89	-1.89	0	%100
2	M1	Z	1.091	1.091	0	%100
3	M2	X	-1.89	-1.89	0	%100
4	M2	Z	1.091	1.091	0	%100
5	M3	X	-.095	-.095	0	%100
6	M3	Z	.055	.055	0	%100
7	M4	X	-.095	-.095	0	%100
8	M4	Z	.055	.055	0	%100
9	M5	X	-4.144	-4.144	0	%100
10	M5	Z	2.393	2.393	0	%100
11	M6	X	-4.144	-4.144	0	%100
12	M6	Z	2.393	2.393	0	%100
13	M7	X	-1.276	-1.276	0	%100
14	M7	Z	.737	.737	0	%100
15	M8	X	-1.276	-1.276	0	%100
16	M8	Z	.737	.737	0	%100
17	M9	X	-1.873	-1.873	0	%100
18	M9	Z	1.082	1.082	0	%100
19	M10	X	-1.873	-1.873	0	%100
20	M10	Z	1.082	1.082	0	%100
21	M11	X	-1.644	-1.644	0	%100

Member Distributed Loads (BLC 49 : Structure Wo (240 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft,F,ksf]	End Magnitude[lb/ft...	Start Location[ft.%]	End Location[ft.%]
22	M11	Z	.949	.949	0	%100
23	M12	X	-1.644	-1.644	0	%100
24	M12	Z	.949	.949	0	%100
25	M13	X	-1.644	-1.644	0	%100
26	M13	Z	.949	.949	0	%100
27	M14	X	-1.644	-1.644	0	%100
28	M14	Z	.949	.949	0	%100
29	M15	X	-1.233	-1.233	0	%100
30	M15	Z	.712	.712	0	%100
31	M16	X	-1.233	-1.233	0	%100
32	M16	Z	.712	.712	0	%100
33	M17	X	-1.233	-1.233	0	%100
34	M17	Z	.712	.712	0	%100
35	M18	X	-1.233	-1.233	0	%100
36	M18	Z	.712	.712	0	%100
37	M19	X	-.411	-.411	0	%100
38	M19	Z	.237	.237	0	%100
39	M20	X	-.411	-.411	0	%100
40	M20	Z	.237	.237	0	%100
41	M21	X	-.411	-.411	0	%100
42	M21	Z	.237	.237	0	%100
43	M22	X	-.411	-.411	0	%100
44	M22	Z	.237	.237	0	%100
45	M23	X	-5.608	-5.608	0	%100
46	M23	Z	3.238	3.238	0	%100
47	M24	X	-3.519	-3.519	0	%100
48	M24	Z	2.032	2.032	0	%100
49	MP1A	X	-6.247	-6.247	0	%100
50	MP1A	Z	3.606	3.606	0	%100
51	MP2A	X	-6.247	-6.247	0	%100
52	MP2A	Z	3.606	3.606	0	%100
53	MP3A	X	-6.247	-6.247	0	%100
54	MP3A	Z	3.606	3.606	0	%100
55	MP4A	X	-6.247	-6.247	0	%100
56	MP4A	Z	3.606	3.606	0	%100

Member Distributed Loads (BLC 50 : Structure Wo (270 Deg))

	Member Label	Direction	Start Magnitude[lb/ft,F,ksf]	End Magnitude[lb/ft...	Start Location[ft.%]	End Location[ft.%]
1	M1	X	0	0	0	%100
2	M1	Z	0	0	0	%100
3	M2	X	0	0	0	%100
4	M2	Z	0	0	0	%100
5	M3	X	-2.114	-2.114	0	%100
6	M3	Z	0	0	0	%100
7	M4	X	-2.114	-2.114	0	%100
8	M4	Z	0	0	0	%100
9	M5	X	-2.114	-2.114	0	%100
10	M5	Z	0	0	0	%100
11	M6	X	-2.114	-2.114	0	%100
12	M6	Z	0	0	0	%100
13	M7	X	-1.769	-1.769	0	%100
14	M7	Z	0	0	0	%100
15	M8	X	-1.769	-1.769	0	%100
16	M8	Z	0	0	0	%100
17	M9	X	-1.769	-1.769	0	%100
18	M9	Z	0	0	0	%100
19	M10	X	-1.769	-1.769	0	%100
20	M10	Z	0	0	0	%100
21	M11	X	-1.898	-1.898	0	%100
22	M11	Z	0	0	0	%100
23	M12	X	-1.898	-1.898	0	%100
24	M12	Z	0	0	0	%100

Member Distributed Loads (BLC 50 : Structure Wo (270 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft.F,ksf]	End Magnitude[lb/ft...	Start Location[ft.%]	End Location[ft.%]
25	M13	X	-1.898	-1.898	0	%100
26	M13	Z	0	0	0	%100
27	M14	X	-1.898	-1.898	0	%100
28	M14	Z	0	0	0	%100
29	M15	X	-1.898	-1.898	0	%100
30	M15	Z	0	0	0	%100
31	M16	X	-1.898	-1.898	0	%100
32	M16	Z	0	0	0	%100
33	M17	X	-1.898	-1.898	0	%100
34	M17	Z	0	0	0	%100
35	M18	X	-1.898	-1.898	0	%100
36	M18	Z	0	0	0	%100
37	M19	X	0	0	0	%100
38	M19	Z	0	0	0	%100
39	M20	X	0	0	0	%100
40	M20	Z	0	0	0	%100
41	M21	X	0	0	0	%100
42	M21	Z	0	0	0	%100
43	M22	X	0	0	0	%100
44	M22	Z	0	0	0	%100
45	M23	X	-6.933	-6.933	0	%100
46	M23	Z	0	0	0	%100
47	M24	X	-6.933	-6.933	0	%100
48	M24	Z	0	0	0	%100
49	MP1A	X	-7.213	-7.213	0	%100
50	MP1A	Z	0	0	0	%100
51	MP2A	X	-7.213	-7.213	0	%100
52	MP2A	Z	0	0	0	%100
53	MP3A	X	-7.213	-7.213	0	%100
54	MP3A	Z	0	0	0	%100
55	MP4A	X	-7.213	-7.213	0	%100
56	MP4A	Z	0	0	0	%100

Member Distributed Loads (BLC 51 : Structure Wo (300 Deg))

	Member Label	Direction	Start Magnitude[lb/ft.F,ksf]	End Magnitude[lb/ft...	Start Location[ft.%]	End Location[ft.%]
1	M1	X	-1.89	-1.89	0	%100
2	M1	Z	-1.091	-1.091	0	%100
3	M2	X	-1.89	-1.89	0	%100
4	M2	Z	-1.091	-1.091	0	%100
5	M3	X	-4.144	-4.144	0	%100
6	M3	Z	-2.393	-2.393	0	%100
7	M4	X	-4.144	-4.144	0	%100
8	M4	Z	-2.393	-2.393	0	%100
9	M5	X	-.095	-.095	0	%100
10	M5	Z	-.055	-.055	0	%100
11	M6	X	-.095	-.095	0	%100
12	M6	Z	-.055	-.055	0	%100
13	M7	X	-1.873	-1.873	0	%100
14	M7	Z	-1.082	-1.082	0	%100
15	M8	X	-1.873	-1.873	0	%100
16	M8	Z	-1.082	-1.082	0	%100
17	M9	X	-1.276	-1.276	0	%100
18	M9	Z	-.737	-.737	0	%100
19	M10	X	-1.276	-1.276	0	%100
20	M10	Z	-.737	-.737	0	%100
21	M11	X	-1.644	-1.644	0	%100
22	M11	Z	-.949	-.949	0	%100
23	M12	X	-1.644	-1.644	0	%100
24	M12	Z	-.949	-.949	0	%100
25	M13	X	-1.644	-1.644	0	%100
26	M13	Z	-.949	-.949	0	%100
27	M14	X	-1.644	-1.644	0	%100

Member Distributed Loads (BLC 51 : Structure Wo (300 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft,F,ksf]	End Magnitude[lb/ft...	Start Location(ft,%)	End Location(ft,%)
28	M14	Z	-949	-949	0	%100
29	M15	X	-1.233	-1.233	0	%100
30	M15	Z	-712	-712	0	%100
31	M16	X	-1.233	-1.233	0	%100
32	M16	Z	-712	-712	0	%100
33	M17	X	-1.233	-1.233	0	%100
34	M17	Z	-712	-712	0	%100
35	M18	X	-1.233	-1.233	0	%100
36	M18	Z	-712	-712	0	%100
37	M19	X	-411	-411	0	%100
38	M19	Z	-237	-237	0	%100
39	M20	X	-411	-411	0	%100
40	M20	Z	-237	-237	0	%100
41	M21	X	-411	-411	0	%100
42	M21	Z	-237	-237	0	%100
43	M22	X	-411	-411	0	%100
44	M22	Z	-237	-237	0	%100
45	M23	X	-3.519	-3.519	0	%100
46	M23	Z	-2.032	-2.032	0	%100
47	M24	X	-5.608	-5.608	0	%100
48	M24	Z	-3.238	-3.238	0	%100
49	MP1A	X	-6.247	-6.247	0	%100
50	MP1A	Z	-3.606	-3.606	0	%100
51	MP2A	X	-6.247	-6.247	0	%100
52	MP2A	Z	-3.606	-3.606	0	%100
53	MP3A	X	-6.247	-6.247	0	%100
54	MP3A	Z	-3.606	-3.606	0	%100
55	MP4A	X	-6.247	-6.247	0	%100
56	MP4A	Z	-3.606	-3.606	0	%100

Member Distributed Loads (BLC 52 : Structure Wo (330 Deg))

	Member Label	Direction	Start Magnitude[lb/ft,F,ksf]	End Magnitude[lb/ft...	Start Location(ft,%)	End Location(ft,%)
1	M1	X	-3.274	-3.274	0	%100
2	M1	Z	-5.671	-5.671	0	%100
3	M2	X	-3.274	-3.274	0	%100
4	M2	Z	-5.671	-5.671	0	%100
5	M3	X	-2.726	-2.726	0	%100
6	M3	Z	-4.721	-4.721	0	%100
7	M4	X	-2.726	-2.726	0	%100
8	M4	Z	-4.721	-4.721	0	%100
9	M5	X	-388	-388	0	%100
10	M5	Z	-672	-672	0	%100
11	M6	X	-388	-388	0	%100
12	M6	Z	-672	-672	0	%100
13	M7	X	-1.131	-1.131	0	%100
14	M7	Z	-1.959	-1.959	0	%100
15	M8	X	-1.131	-1.131	0	%100
16	M8	Z	-1.959	-1.959	0	%100
17	M9	X	-786	-786	0	%100
18	M9	Z	-1.361	-1.361	0	%100
19	M10	X	-786	-786	0	%100
20	M10	Z	-1.361	-1.361	0	%100
21	M11	X	-949	-949	0	%100
22	M11	Z	-1.644	-1.644	0	%100
23	M12	X	-949	-949	0	%100
24	M12	Z	-1.644	-1.644	0	%100
25	M13	X	-949	-949	0	%100
26	M13	Z	-1.644	-1.644	0	%100
27	M14	X	-949	-949	0	%100
28	M14	Z	-1.644	-1.644	0	%100
29	M15	X	-237	-237	0	%100
30	M15	Z	-411	-411	0	%100

Member Distributed Loads (BLC 52 : Structure Wo (330 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft,F,ksf]	End Magnitude[lb/ft...	Start Location[ft, %]	End Location[ft, %]
31	M16	X	-237	-237	0	%100
32	M16	Z	-411	-411	0	%100
33	M17	X	-237	-237	0	%100
34	M17	Z	-411	-411	0	%100
35	M18	X	-237	-237	0	%100
36	M18	Z	-411	-411	0	%100
37	M19	X	-712	-712	0	%100
38	M19	Z	-1.233	-1.233	0	%100
39	M20	X	-712	-712	0	%100
40	M20	Z	-1.233	-1.233	0	%100
41	M21	X	-712	-712	0	%100
42	M21	Z	-1.233	-1.233	0	%100
43	M22	X	-712	-712	0	%100
44	M22	Z	-1.233	-1.233	0	%100
45	M23	X	-369	-369	0	%100
46	M23	Z	-638	-638	0	%100
47	M24	X	-1.574	-1.574	0	%100
48	M24	Z	-2.727	-2.727	0	%100
49	MP1A	X	-3.606	-3.606	0	%100
50	MP1A	Z	-6.247	-6.247	0	%100
51	MP2A	X	-3.606	-3.606	0	%100
52	MP2A	Z	-6.247	-6.247	0	%100
53	MP3A	X	-3.606	-3.606	0	%100
54	MP3A	Z	-6.247	-6.247	0	%100
55	MP4A	X	-3.606	-3.606	0	%100
56	MP4A	Z	-6.247	-6.247	0	%100

Member Distributed Loads (BLC 53 : Structure Wi (0 Deg))

	Member Label	Direction	Start Magnitude[lb/ft,F,ksf]	End Magnitude[lb/ft...	Start Location[ft, %]	End Location[ft, %]
1	M1	X	0	0	0	%100
2	M1	Z	-2.69	-2.69	0	%100
3	M2	X	0	0	0	%100
4	M2	Z	-2.69	-2.69	0	%100
5	M3	X	0	0	0	%100
6	M3	Z	-1.171	-1.171	0	%100
7	M4	X	0	0	0	%100
8	M4	Z	-1.171	-1.171	0	%100
9	M5	X	0	0	0	%100
10	M5	Z	-1.171	-1.171	0	%100
11	M6	X	0	0	0	%100
12	M6	Z	-1.171	-1.171	0	%100
13	M7	X	0	0	0	%100
14	M7	Z	-1.307	-1.307	0	%100
15	M8	X	0	0	0	%100
16	M8	Z	-1.307	-1.307	0	%100
17	M9	X	0	0	0	%100
18	M9	Z	-1.307	-1.307	0	%100
19	M10	X	0	0	0	%100
20	M10	Z	-1.307	-1.307	0	%100
21	M11	X	0	0	0	%100
22	M11	Z	-1.351	-1.351	0	%100
23	M12	X	0	0	0	%100
24	M12	Z	-1.351	-1.351	0	%100
25	M13	X	0	0	0	%100
26	M13	Z	-1.351	-1.351	0	%100
27	M14	X	0	0	0	%100
28	M14	Z	-1.351	-1.351	0	%100
29	M15	X	0	0	0	%100
30	M15	Z	0	0	0	%100
31	M16	X	0	0	0	%100
32	M16	Z	0	0	0	%100
33	M17	X	0	0	0	%100

Member Distributed Loads (BLC 53 : Structure Wi (0 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft,F,ksf]	End Magnitude[lb/ft...	Start Location[ft.%]	End Location[ft.%]
34	M17	Z	0	0	0	%100
35	M18	X	0	0	0	%100
36	M18	Z	0	0	0	%100
37	M19	X	0	0	0	%100
38	M19	Z	-1.022	-1.022	0	%100
39	M20	X	0	0	0	%100
40	M20	Z	-1.022	-1.022	0	%100
41	M21	X	0	0	0	%100
42	M21	Z	-1.022	-1.022	0	%100
43	M22	X	0	0	0	%100
44	M22	Z	-1.022	-1.022	0	%100
45	M23	X	0	0	0	%100
46	M23	Z	-.094	-.094	0	%100
47	M24	X	0	0	0	%100
48	M24	Z	-.094	-.094	0	%100
49	MP1A	X	0	0	0	%100
50	MP1A	Z	-2.427	-2.427	0	%100
51	MP2A	X	0	0	0	%100
52	MP2A	Z	-2.427	-2.427	0	%100
53	MP3A	X	0	0	0	%100
54	MP3A	Z	-2.427	-2.427	0	%100
55	MP4A	X	0	0	0	%100
56	MP4A	Z	-2.427	-2.427	0	%100

Member Distributed Loads (BLC 54 : Structure Wi (30 Deg))

	Member Label	Direction	Start Magnitude[lb/ft,F,ksf]	End Magnitude[lb/ft...	Start Location[ft.%]	End Location[ft.%]
1	M1	X	1.009	1.009	0	%100
2	M1	Z	-1.747	-1.747	0	%100
3	M2	X	1.009	1.009	0	%100
4	M2	Z	-1.747	-1.747	0	%100
5	M3	X	.132	.132	0	%100
6	M3	Z	-.228	-.228	0	%100
7	M4	X	.132	.132	0	%100
8	M4	Z	-.228	-.228	0	%100
9	M5	X	.926	.926	0	%100
10	M5	Z	-1.604	-1.604	0	%100
11	M6	X	.926	.926	0	%100
12	M6	Z	-1.604	-1.604	0	%100
13	M7	X	.523	.523	0	%100
14	M7	Z	-.905	-.905	0	%100
15	M8	X	.523	.523	0	%100
16	M8	Z	-.905	-.905	0	%100
17	M9	X	.752	.752	0	%100
18	M9	Z	-1.302	-1.302	0	%100
19	M10	X	.752	.752	0	%100
20	M10	Z	-1.302	-1.302	0	%100
21	M11	X	.675	.675	0	%100
22	M11	Z	-1.17	-1.17	0	%100
23	M12	X	.675	.675	0	%100
24	M12	Z	-1.17	-1.17	0	%100
25	M13	X	.675	.675	0	%100
26	M13	Z	-1.17	-1.17	0	%100
27	M14	X	.675	.675	0	%100
28	M14	Z	-1.17	-1.17	0	%100
29	M15	X	.127	.127	0	%100
30	M15	Z	-.22	-.22	0	%100
31	M16	X	.127	.127	0	%100
32	M16	Z	-.22	-.22	0	%100
33	M17	X	.127	.127	0	%100
34	M17	Z	-.22	-.22	0	%100
35	M18	X	.127	.127	0	%100
36	M18	Z	-.22	-.22	0	%100

Member Distributed Loads (BLC 54 : Structure Wi (30 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft.F,ksf]	End Magnitude[lb/ft...	Start Location[ft.%]	End Location[ft.%]
37	M19	X	.383	.383	0	%100
38	M19	Z	-.664	-.664	0	%100
39	M20	X	.383	.383	0	%100
40	M20	Z	-.664	-.664	0	%100
41	M21	X	.383	.383	0	%100
42	M21	Z	-.664	-.664	0	%100
43	M22	X	.383	.383	0	%100
44	M22	Z	-.664	-.664	0	%100
45	M23	X	.53	.53	0	%100
46	M23	Z	-.917	-.917	0	%100
47	M24	X	.124	.124	0	%100
48	M24	Z	-.215	-.215	0	%100
49	MP1A	X	1.213	1.213	0	%100
50	MP1A	Z	-2.101	-2.101	0	%100
51	MP2A	X	1.213	1.213	0	%100
52	MP2A	Z	-2.101	-2.101	0	%100
53	MP3A	X	1.213	1.213	0	%100
54	MP3A	Z	-2.101	-2.101	0	%100
55	MP4A	X	1.213	1.213	0	%100
56	MP4A	Z	-2.101	-2.101	0	%100

Member Distributed Loads (BLC 55 : Structure Wi (60 Deg))

	Member Label	Direction	Start Magnitude[lb/ft.F,ksf]	End Magnitude[lb/ft...	Start Location[ft.%]	End Location[ft.%]
1	M1	X	.582	.582	0	%100
2	M1	Z	-.336	-.336	0	%100
3	M2	X	.582	.582	0	%100
4	M2	Z	-.336	-.336	0	%100
5	M3	X	.032	.032	0	%100
6	M3	Z	-.019	-.019	0	%100
7	M4	X	.032	.032	0	%100
8	M4	Z	-.019	-.019	0	%100
9	M5	X	1.408	1.408	0	%100
10	M5	Z	-.813	-.813	0	%100
11	M6	X	1.408	1.408	0	%100
12	M6	Z	-.813	-.813	0	%100
13	M7	X	.848	.848	0	%100
14	M7	Z	-.49	-.49	0	%100
15	M8	X	.848	.848	0	%100
16	M8	Z	-.49	-.49	0	%100
17	M9	X	1.246	1.246	0	%100
18	M9	Z	-.719	-.719	0	%100
19	M10	X	1.246	1.246	0	%100
20	M10	Z	-.719	-.719	0	%100
21	M11	X	1.17	1.17	0	%100
22	M11	Z	-.675	-.675	0	%100
23	M12	X	1.17	1.17	0	%100
24	M12	Z	-.675	-.675	0	%100
25	M13	X	1.17	1.17	0	%100
26	M13	Z	-.675	-.675	0	%100
27	M14	X	1.17	1.17	0	%100
28	M14	Z	-.675	-.675	0	%100
29	M15	X	.659	.659	0	%100
30	M15	Z	-.38	-.38	0	%100
31	M16	X	.659	.659	0	%100
32	M16	Z	-.38	-.38	0	%100
33	M17	X	.659	.659	0	%100
34	M17	Z	-.38	-.38	0	%100
35	M18	X	.659	.659	0	%100
36	M18	Z	-.38	-.38	0	%100
37	M19	X	.221	.221	0	%100
38	M19	Z	-.128	-.128	0	%100
39	M20	X	.221	.221	0	%100

Member Distributed Loads (BLC 55 : Structure Wi (60 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft,F,ksf]	End Magnitude[lb/ft...	Start Location[ft, %]	End Location[ft, %]
40	M20	Z	-.128	-.128	0	%100
41	M21	X	.221	.221	0	%100
42	M21	Z	-.128	-.128	0	%100
43	M22	X	.221	.221	0	%100
44	M22	Z	-.128	-.128	0	%100
45	M23	X	1.887	1.887	0	%100
46	M23	Z	-1.089	-1.089	0	%100
47	M24	X	1.184	1.184	0	%100
48	M24	Z	-.684	-.684	0	%100
49	MP1A	X	2.101	2.101	0	%100
50	MP1A	Z	-1.213	-1.213	0	%100
51	MP2A	X	2.101	2.101	0	%100
52	MP2A	Z	-1.213	-1.213	0	%100
53	MP3A	X	2.101	2.101	0	%100
54	MP3A	Z	-1.213	-1.213	0	%100
55	MP4A	X	2.101	2.101	0	%100
56	MP4A	Z	-1.213	-1.213	0	%100

Member Distributed Loads (BLC 56 : Structure Wi (90 Deg))

	Member Label	Direction	Start Magnitude[lb/ft,F,ksf]	End Magnitude[lb/ft...	Start Location[ft, %]	End Location[ft, %]
1	M1	X	0	0	0	%100
2	M1	Z	0	0	0	%100
3	M2	X	0	0	0	%100
4	M2	Z	0	0	0	%100
5	M3	X	.718	.718	0	%100
6	M3	Z	0	0	0	%100
7	M4	X	.718	.718	0	%100
8	M4	Z	0	0	0	%100
9	M5	X	.718	.718	0	%100
10	M5	Z	0	0	0	%100
11	M6	X	.718	.718	0	%100
12	M6	Z	0	0	0	%100
13	M7	X	1.176	1.176	0	%100
14	M7	Z	0	0	0	%100
15	M8	X	1.176	1.176	0	%100
16	M8	Z	0	0	0	%100
17	M9	X	1.176	1.176	0	%100
18	M9	Z	0	0	0	%100
19	M10	X	1.176	1.176	0	%100
20	M10	Z	0	0	0	%100
21	M11	X	1.351	1.351	0	%100
22	M11	Z	0	0	0	%100
23	M12	X	1.351	1.351	0	%100
24	M12	Z	0	0	0	%100
25	M13	X	1.351	1.351	0	%100
26	M13	Z	0	0	0	%100
27	M14	X	1.351	1.351	0	%100
28	M14	Z	0	0	0	%100
29	M15	X	1.015	1.015	0	%100
30	M15	Z	0	0	0	%100
31	M16	X	1.015	1.015	0	%100
32	M16	Z	0	0	0	%100
33	M17	X	1.015	1.015	0	%100
34	M17	Z	0	0	0	%100
35	M18	X	1.015	1.015	0	%100
36	M18	Z	0	0	0	%100
37	M19	X	0	0	0	%100
38	M19	Z	0	0	0	%100
39	M20	X	0	0	0	%100
40	M20	Z	0	0	0	%100
41	M21	X	0	0	0	%100
42	M21	Z	0	0	0	%100

Member Distributed Loads (BLC 56 : Structure Wi (90 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft.F.ksf]	End Magnitude[lb/ft...	Start Location[ft.%]	End Location[ft.%]
43	M22	X	0	0	0	%100
44	M22	Z	0	0	0	%100
45	M23	X	2.332	2.332	0	%100
46	M23	Z	0	0	0	%100
47	M24	X	2.332	2.332	0	%100
48	M24	Z	0	0	0	%100
49	MP1A	X	2.427	2.427	0	%100
50	MP1A	Z	0	0	0	%100
51	MP2A	X	2.427	2.427	0	%100
52	MP2A	Z	0	0	0	%100
53	MP3A	X	2.427	2.427	0	%100
54	MP3A	Z	0	0	0	%100
55	MP4A	X	2.427	2.427	0	%100
56	MP4A	Z	0	0	0	%100

Member Distributed Loads (BLC 57 : Structure Wi (120 Deg))

	Member Label	Direction	Start Magnitude[lb/ft.F.ksf]	End Magnitude[lb/ft...	Start Location[ft.%]	End Location[ft.%]
1	M1	X	.582	.582	0	%100
2	M1	Z	.336	.336	0	%100
3	M2	X	.582	.582	0	%100
4	M2	Z	.336	.336	0	%100
5	M3	X	1.408	1.408	0	%100
6	M3	Z	.813	.813	0	%100
7	M4	X	1.408	1.408	0	%100
8	M4	Z	.813	.813	0	%100
9	M5	X	.032	.032	0	%100
10	M5	Z	.019	.019	0	%100
11	M6	X	.032	.032	0	%100
12	M6	Z	.019	.019	0	%100
13	M7	X	1.246	1.246	0	%100
14	M7	Z	.719	.719	0	%100
15	M8	X	1.246	1.246	0	%100
16	M8	Z	.719	.719	0	%100
17	M9	X	.848	.848	0	%100
18	M9	Z	.49	.49	0	%100
19	M10	X	.848	.848	0	%100
20	M10	Z	.49	.49	0	%100
21	M11	X	1.17	1.17	0	%100
22	M11	Z	.675	.675	0	%100
23	M12	X	1.17	1.17	0	%100
24	M12	Z	.675	.675	0	%100
25	M13	X	1.17	1.17	0	%100
26	M13	Z	.675	.675	0	%100
27	M14	X	1.17	1.17	0	%100
28	M14	Z	.675	.675	0	%100
29	M15	X	.659	.659	0	%100
30	M15	Z	.38	.38	0	%100
31	M16	X	.659	.659	0	%100
32	M16	Z	.38	.38	0	%100
33	M17	X	.659	.659	0	%100
34	M17	Z	.38	.38	0	%100
35	M18	X	.659	.659	0	%100
36	M18	Z	.38	.38	0	%100
37	M19	X	.221	.221	0	%100
38	M19	Z	.128	.128	0	%100
39	M20	X	.221	.221	0	%100
40	M20	Z	.128	.128	0	%100
41	M21	X	.221	.221	0	%100
42	M21	Z	.128	.128	0	%100
43	M22	X	.221	.221	0	%100
44	M22	Z	.128	.128	0	%100
45	M23	X	1.184	1.184	0	%100

Member Distributed Loads (BLC 57 : Structure Wi (120 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft.F.ksf]	End Magnitude[lb/ft...	Start Location[ft.%]	End Location[ft.%]
46	M23	Z	.684	.684	0	%100
47	M24	X	1.887	1.887	0	%100
48	M24	Z	1.089	1.089	0	%100
49	MP1A	X	2.101	2.101	0	%100
50	MP1A	Z	1.213	1.213	0	%100
51	MP2A	X	2.101	2.101	0	%100
52	MP2A	Z	1.213	1.213	0	%100
53	MP3A	X	2.101	2.101	0	%100
54	MP3A	Z	1.213	1.213	0	%100
55	MP4A	X	2.101	2.101	0	%100
56	MP4A	Z	1.213	1.213	0	%100

Member Distributed Loads (BLC 58 : Structure Wi (150 Deg))

	Member Label	Direction	Start Magnitude[lb/ft.F.ksf]	End Magnitude[lb/ft...	Start Location[ft.%]	End Location[ft.%]
1	M1	X	1.009	1.009	0	%100
2	M1	Z	1.747	1.747	0	%100
3	M2	X	1.009	1.009	0	%100
4	M2	Z	1.747	1.747	0	%100
5	M3	X	.926	.926	0	%100
6	M3	Z	1.604	1.604	0	%100
7	M4	X	.926	.926	0	%100
8	M4	Z	1.604	1.604	0	%100
9	M5	X	.132	.132	0	%100
10	M5	Z	.228	.228	0	%100
11	M6	X	.132	.132	0	%100
12	M6	Z	.228	.228	0	%100
13	M7	X	.752	.752	0	%100
14	M7	Z	1.302	1.302	0	%100
15	M8	X	.752	.752	0	%100
16	M8	Z	1.302	1.302	0	%100
17	M9	X	.523	.523	0	%100
18	M9	Z	.905	.905	0	%100
19	M10	X	.523	.523	0	%100
20	M10	Z	.905	.905	0	%100
21	M11	X	.675	.675	0	%100
22	M11	Z	1.17	1.17	0	%100
23	M12	X	.675	.675	0	%100
24	M12	Z	1.17	1.17	0	%100
25	M13	X	.675	.675	0	%100
26	M13	Z	1.17	1.17	0	%100
27	M14	X	.675	.675	0	%100
28	M14	Z	1.17	1.17	0	%100
29	M15	X	.127	.127	0	%100
30	M15	Z	.22	.22	0	%100
31	M16	X	.127	.127	0	%100
32	M16	Z	.22	.22	0	%100
33	M17	X	.127	.127	0	%100
34	M17	Z	.22	.22	0	%100
35	M18	X	.127	.127	0	%100
36	M18	Z	.22	.22	0	%100
37	M19	X	.383	.383	0	%100
38	M19	Z	.664	.664	0	%100
39	M20	X	.383	.383	0	%100
40	M20	Z	.664	.664	0	%100
41	M21	X	.383	.383	0	%100
42	M21	Z	.664	.664	0	%100
43	M22	X	.383	.383	0	%100
44	M22	Z	.664	.664	0	%100
45	M23	X	.124	.124	0	%100
46	M23	Z	.215	.215	0	%100
47	M24	X	.53	.53	0	%100
48	M24	Z	.917	.917	0	%100

Member Distributed Loads (BLC 58 : Structure Wi (150 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft,F,ksf]	End Magnitude[lb/ft...	Start Location[ft, %]	End Location[ft, %]
49	MP1A	X	1.213	1.213	0	%100
50	MP1A	Z	2.101	2.101	0	%100
51	MP2A	X	1.213	1.213	0	%100
52	MP2A	Z	2.101	2.101	0	%100
53	MP3A	X	1.213	1.213	0	%100
54	MP3A	Z	2.101	2.101	0	%100
55	MP4A	X	1.213	1.213	0	%100
56	MP4A	Z	2.101	2.101	0	%100

Member Distributed Loads (BLC 59 : Structure Wi (180 Deg))

	Member Label	Direction	Start Magnitude[lb/ft,F,ksf]	End Magnitude[lb/ft...	Start Location[ft, %]	End Location[ft, %]
1	M1	X	0	0	0	%100
2	M1	Z	2.69	2.69	0	%100
3	M2	X	0	0	0	%100
4	M2	Z	2.69	2.69	0	%100
5	M3	X	0	0	0	%100
6	M3	Z	1.171	1.171	0	%100
7	M4	X	0	0	0	%100
8	M4	Z	1.171	1.171	0	%100
9	M5	X	0	0	0	%100
10	M5	Z	1.171	1.171	0	%100
11	M6	X	0	0	0	%100
12	M6	Z	1.171	1.171	0	%100
13	M7	X	0	0	0	%100
14	M7	Z	1.307	1.307	0	%100
15	M8	X	0	0	0	%100
16	M8	Z	1.307	1.307	0	%100
17	M9	X	0	0	0	%100
18	M9	Z	1.307	1.307	0	%100
19	M10	X	0	0	0	%100
20	M10	Z	1.307	1.307	0	%100
21	M11	X	0	0	0	%100
22	M11	Z	1.351	1.351	0	%100
23	M12	X	0	0	0	%100
24	M12	Z	1.351	1.351	0	%100
25	M13	X	0	0	0	%100
26	M13	Z	1.351	1.351	0	%100
27	M14	X	0	0	0	%100
28	M14	Z	1.351	1.351	0	%100
29	M15	X	0	0	0	%100
30	M15	Z	0	0	0	%100
31	M16	X	0	0	0	%100
32	M16	Z	0	0	0	%100
33	M17	X	0	0	0	%100
34	M17	Z	0	0	0	%100
35	M18	X	0	0	0	%100
36	M18	Z	0	0	0	%100
37	M19	X	0	0	0	%100
38	M19	Z	1.022	1.022	0	%100
39	M20	X	0	0	0	%100
40	M20	Z	1.022	1.022	0	%100
41	M21	X	0	0	0	%100
42	M21	Z	1.022	1.022	0	%100
43	M22	X	0	0	0	%100
44	M22	Z	1.022	1.022	0	%100
45	M23	X	0	0	0	%100
46	M23	Z	.094	.094	0	%100
47	M24	X	0	0	0	%100
48	M24	Z	.094	.094	0	%100
49	MP1A	X	0	0	0	%100
50	MP1A	Z	2.427	2.427	0	%100
51	MP2A	X	0	0	0	%100

Member Distributed Loads (BLC 59 : Structure Wi (180 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft.F,ksf]	End Magnitude[lb/ft...	Start Location[ft.%]	End Location[ft.%]
52	MP2A	Z	2.427	2.427	0	%100
53	MP3A	X	0	0	0	%100
54	MP3A	Z	2.427	2.427	0	%100
55	MP4A	X	0	0	0	%100
56	MP4A	Z	2.427	2.427	0	%100

Member Distributed Loads (BLC 60 : Structure Wi (210 Deg))

	Member Label	Direction	Start Magnitude[lb/ft.F,ksf]	End Magnitude[lb/ft...	Start Location[ft.%]	End Location[ft.%]
1	M1	X	-1.009	-1.009	0	%100
2	M1	Z	1.747	1.747	0	%100
3	M2	X	-1.009	-1.009	0	%100
4	M2	Z	1.747	1.747	0	%100
5	M3	X	-.132	-.132	0	%100
6	M3	Z	.228	.228	0	%100
7	M4	X	-.132	-.132	0	%100
8	M4	Z	.228	.228	0	%100
9	M5	X	-.926	-.926	0	%100
10	M5	Z	1.604	1.604	0	%100
11	M6	X	-.926	-.926	0	%100
12	M6	Z	1.604	1.604	0	%100
13	M7	X	-.523	-.523	0	%100
14	M7	Z	.905	.905	0	%100
15	M8	X	-.523	-.523	0	%100
16	M8	Z	.905	.905	0	%100
17	M9	X	-.752	-.752	0	%100
18	M9	Z	1.302	1.302	0	%100
19	M10	X	-.752	-.752	0	%100
20	M10	Z	1.302	1.302	0	%100
21	M11	X	-.675	-.675	0	%100
22	M11	Z	1.17	1.17	0	%100
23	M12	X	-.675	-.675	0	%100
24	M12	Z	1.17	1.17	0	%100
25	M13	X	-.675	-.675	0	%100
26	M13	Z	1.17	1.17	0	%100
27	M14	X	-.675	-.675	0	%100
28	M14	Z	1.17	1.17	0	%100
29	M15	X	-.127	-.127	0	%100
30	M15	Z	.22	.22	0	%100
31	M16	X	-.127	-.127	0	%100
32	M16	Z	.22	.22	0	%100
33	M17	X	-.127	-.127	0	%100
34	M17	Z	.22	.22	0	%100
35	M18	X	-.127	-.127	0	%100
36	M18	Z	.22	.22	0	%100
37	M19	X	-.383	-.383	0	%100
38	M19	Z	.664	.664	0	%100
39	M20	X	-.383	-.383	0	%100
40	M20	Z	.664	.664	0	%100
41	M21	X	-.383	-.383	0	%100
42	M21	Z	.664	.664	0	%100
43	M22	X	-.383	-.383	0	%100
44	M22	Z	.664	.664	0	%100
45	M23	X	-.53	-.53	0	%100
46	M23	Z	.917	.917	0	%100
47	M24	X	-.124	-.124	0	%100
48	M24	Z	.215	.215	0	%100
49	MP1A	X	-1.213	-1.213	0	%100
50	MP1A	Z	2.101	2.101	0	%100
51	MP2A	X	-1.213	-1.213	0	%100
52	MP2A	Z	2.101	2.101	0	%100
53	MP3A	X	-1.213	-1.213	0	%100
54	MP3A	Z	2.101	2.101	0	%100

Member Distributed Loads (BLC 60 : Structure Wi (210 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft.F,ksf]	End Magnitude[lb/ft...	Start Location[ft, %]	End Location[ft, %]
55	MP4A	X	-1.213	-1.213	0	%100
56	MP4A	Z	2.101	2.101	0	%100

Member Distributed Loads (BLC 61 : Structure Wi (240 Deg))

	Member Label	Direction	Start Magnitude[lb/ft.F,ksf]	End Magnitude[lb/ft...	Start Location[ft, %]	End Location[ft, %]
1	M1	X	-.582	-.582	0	%100
2	M1	Z	.336	.336	0	%100
3	M2	X	-.582	-.582	0	%100
4	M2	Z	.336	.336	0	%100
5	M3	X	-.032	-.032	0	%100
6	M3	Z	.019	.019	0	%100
7	M4	X	-.032	-.032	0	%100
8	M4	Z	.019	.019	0	%100
9	M5	X	-1.408	-1.408	0	%100
10	M5	Z	.813	.813	0	%100
11	M6	X	-1.408	-1.408	0	%100
12	M6	Z	.813	.813	0	%100
13	M7	X	-.848	-.848	0	%100
14	M7	Z	.49	.49	0	%100
15	M8	X	-.848	-.848	0	%100
16	M8	Z	.49	.49	0	%100
17	M9	X	-1.246	-1.246	0	%100
18	M9	Z	.719	.719	0	%100
19	M10	X	-1.246	-1.246	0	%100
20	M10	Z	.719	.719	0	%100
21	M11	X	-1.17	-1.17	0	%100
22	M11	Z	.675	.675	0	%100
23	M12	X	-1.17	-1.17	0	%100
24	M12	Z	.675	.675	0	%100
25	M13	X	-1.17	-1.17	0	%100
26	M13	Z	.675	.675	0	%100
27	M14	X	-1.17	-1.17	0	%100
28	M14	Z	.675	.675	0	%100
29	M15	X	-.659	-.659	0	%100
30	M15	Z	.38	.38	0	%100
31	M16	X	-.659	-.659	0	%100
32	M16	Z	.38	.38	0	%100
33	M17	X	-.659	-.659	0	%100
34	M17	Z	.38	.38	0	%100
35	M18	X	-.659	-.659	0	%100
36	M18	Z	.38	.38	0	%100
37	M19	X	-.221	-.221	0	%100
38	M19	Z	.128	.128	0	%100
39	M20	X	-.221	-.221	0	%100
40	M20	Z	.128	.128	0	%100
41	M21	X	-.221	-.221	0	%100
42	M21	Z	.128	.128	0	%100
43	M22	X	-.221	-.221	0	%100
44	M22	Z	.128	.128	0	%100
45	M23	X	-1.887	-1.887	0	%100
46	M23	Z	1.089	1.089	0	%100
47	M24	X	-1.184	-1.184	0	%100
48	M24	Z	.684	.684	0	%100
49	MP1A	X	-2.101	-2.101	0	%100
50	MP1A	Z	1.213	1.213	0	%100
51	MP2A	X	-2.101	-2.101	0	%100
52	MP2A	Z	1.213	1.213	0	%100
53	MP3A	X	-2.101	-2.101	0	%100
54	MP3A	Z	1.213	1.213	0	%100
55	MP4A	X	-2.101	-2.101	0	%100
56	MP4A	Z	1.213	1.213	0	%100

Member Distributed Loads (BLC 62 : Structure Wi (270 Deg))

	Member Label	Direction	Start Magnitude[lb/ft.F,ksf]	End Magnitude[lb/ft...	Start Location[ft, %]	End Location[ft, %]
1	M1	X	0	0	0	%100
2	M1	Z	0	0	0	%100
3	M2	X	0	0	0	%100
4	M2	Z	0	0	0	%100
5	M3	X	-.718	-.718	0	%100
6	M3	Z	0	0	0	%100
7	M4	X	-.718	-.718	0	%100
8	M4	Z	0	0	0	%100
9	M5	X	-.718	-.718	0	%100
10	M5	Z	0	0	0	%100
11	M6	X	-.718	-.718	0	%100
12	M6	Z	0	0	0	%100
13	M7	X	-1.176	-1.176	0	%100
14	M7	Z	0	0	0	%100
15	M8	X	-1.176	-1.176	0	%100
16	M8	Z	0	0	0	%100
17	M9	X	-1.176	-1.176	0	%100
18	M9	Z	0	0	0	%100
19	M10	X	-1.176	-1.176	0	%100
20	M10	Z	0	0	0	%100
21	M11	X	-1.351	-1.351	0	%100
22	M11	Z	0	0	0	%100
23	M12	X	-1.351	-1.351	0	%100
24	M12	Z	0	0	0	%100
25	M13	X	-1.351	-1.351	0	%100
26	M13	Z	0	0	0	%100
27	M14	X	-1.351	-1.351	0	%100
28	M14	Z	0	0	0	%100
29	M15	X	-1.015	-1.015	0	%100
30	M15	Z	0	0	0	%100
31	M16	X	-1.015	-1.015	0	%100
32	M16	Z	0	0	0	%100
33	M17	X	-1.015	-1.015	0	%100
34	M17	Z	0	0	0	%100
35	M18	X	-1.015	-1.015	0	%100
36	M18	Z	0	0	0	%100
37	M19	X	0	0	0	%100
38	M19	Z	0	0	0	%100
39	M20	X	0	0	0	%100
40	M20	Z	0	0	0	%100
41	M21	X	0	0	0	%100
42	M21	Z	0	0	0	%100
43	M22	X	0	0	0	%100
44	M22	Z	0	0	0	%100
45	M23	X	-2.332	-2.332	0	%100
46	M23	Z	0	0	0	%100
47	M24	X	-2.332	-2.332	0	%100
48	M24	Z	0	0	0	%100
49	MP1A	X	-2.427	-2.427	0	%100
50	MP1A	Z	0	0	0	%100
51	MP2A	X	-2.427	-2.427	0	%100
52	MP2A	Z	0	0	0	%100
53	MP3A	X	-2.427	-2.427	0	%100
54	MP3A	Z	0	0	0	%100
55	MP4A	X	-2.427	-2.427	0	%100
56	MP4A	Z	0	0	0	%100

Member Distributed Loads (BLC 63 : Structure Wi (300 Deg))

	Member Label	Direction	Start Magnitude[lb/ft.F,ksf]	End Magnitude[lb/ft...	Start Location[ft, %]	End Location[ft, %]
1	M1	X	-.582	-.582	0	%100
2	M1	Z	-.336	-.336	0	%100
3	M2	X	-.582	-.582	0	%100

Member Distributed Loads (BLC 63 : Structure Wi (300 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft.F,ksf]	End Magnitude[lb/ft...	Start Location[ft.%]	End Location[ft.%]
4	M2	Z	-.336	-.336	0	%100
5	M3	X	-1.408	-1.408	0	%100
6	M3	Z	-.813	-.813	0	%100
7	M4	X	-1.408	-1.408	0	%100
8	M4	Z	-.813	-.813	0	%100
9	M5	X	-.032	-.032	0	%100
10	M5	Z	-.019	-.019	0	%100
11	M6	X	-.032	-.032	0	%100
12	M6	Z	-.019	-.019	0	%100
13	M7	X	-1.246	-1.246	0	%100
14	M7	Z	-.719	-.719	0	%100
15	M8	X	-1.246	-1.246	0	%100
16	M8	Z	-.719	-.719	0	%100
17	M9	X	-.848	-.848	0	%100
18	M9	Z	-.49	-.49	0	%100
19	M10	X	-.848	-.848	0	%100
20	M10	Z	-.49	-.49	0	%100
21	M11	X	-1.17	-1.17	0	%100
22	M11	Z	-.675	-.675	0	%100
23	M12	X	-1.17	-1.17	0	%100
24	M12	Z	-.675	-.675	0	%100
25	M13	X	-1.17	-1.17	0	%100
26	M13	Z	-.675	-.675	0	%100
27	M14	X	-1.17	-1.17	0	%100
28	M14	Z	-.675	-.675	0	%100
29	M15	X	-.659	-.659	0	%100
30	M15	Z	-.38	-.38	0	%100
31	M16	X	-.659	-.659	0	%100
32	M16	Z	-.38	-.38	0	%100
33	M17	X	-.659	-.659	0	%100
34	M17	Z	-.38	-.38	0	%100
35	M18	X	-.659	-.659	0	%100
36	M18	Z	-.38	-.38	0	%100
37	M19	X	-.221	-.221	0	%100
38	M19	Z	-.128	-.128	0	%100
39	M20	X	-.221	-.221	0	%100
40	M20	Z	-.128	-.128	0	%100
41	M21	X	-.221	-.221	0	%100
42	M21	Z	-.128	-.128	0	%100
43	M22	X	-.221	-.221	0	%100
44	M22	Z	-.128	-.128	0	%100
45	M23	X	-1.184	-1.184	0	%100
46	M23	Z	-.684	-.684	0	%100
47	M24	X	-1.887	-1.887	0	%100
48	M24	Z	-1.089	-1.089	0	%100
49	MP1A	X	-2.101	-2.101	0	%100
50	MP1A	Z	-1.213	-1.213	0	%100
51	MP2A	X	-2.101	-2.101	0	%100
52	MP2A	Z	-1.213	-1.213	0	%100
53	MP3A	X	-2.101	-2.101	0	%100
54	MP3A	Z	-1.213	-1.213	0	%100
55	MP4A	X	-2.101	-2.101	0	%100
56	MP4A	Z	-1.213	-1.213	0	%100

Member Distributed Loads (BLC 64 : Structure Wi (330 Deg))

	Member Label	Direction	Start Magnitude[lb/ft.F,ksf]	End Magnitude[lb/ft...	Start Location[ft.%]	End Location[ft.%]
1	M1	X	-1.009	-1.009	0	%100
2	M1	Z	-1.747	-1.747	0	%100
3	M2	X	-1.009	-1.009	0	%100
4	M2	Z	-1.747	-1.747	0	%100
5	M3	X	-.926	-.926	0	%100
6	M3	Z	-1.604	-1.604	0	%100

Member Distributed Loads (BLC 64 : Structure Wi (330 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft.F.ksf]	End Magnitude[lb/ft...	Start Location[ft.%]	End Location[ft.%]
7	M4	X	-.926	-.926	0	%100
8	M4	Z	-1.604	-1.604	0	%100
9	M5	X	-.132	-.132	0	%100
10	M5	Z	-.228	-.228	0	%100
11	M6	X	-.132	-.132	0	%100
12	M6	Z	-.228	-.228	0	%100
13	M7	X	-.752	-.752	0	%100
14	M7	Z	-1.302	-1.302	0	%100
15	M8	X	-.752	-.752	0	%100
16	M8	Z	-1.302	-1.302	0	%100
17	M9	X	-.523	-.523	0	%100
18	M9	Z	-.905	-.905	0	%100
19	M10	X	-.523	-.523	0	%100
20	M10	Z	-.905	-.905	0	%100
21	M11	X	-.675	-.675	0	%100
22	M11	Z	-1.17	-1.17	0	%100
23	M12	X	-.675	-.675	0	%100
24	M12	Z	-1.17	-1.17	0	%100
25	M13	X	-.675	-.675	0	%100
26	M13	Z	-1.17	-1.17	0	%100
27	M14	X	-.675	-.675	0	%100
28	M14	Z	-1.17	-1.17	0	%100
29	M15	X	-.127	-.127	0	%100
30	M15	Z	-.22	-.22	0	%100
31	M16	X	-.127	-.127	0	%100
32	M16	Z	-.22	-.22	0	%100
33	M17	X	-.127	-.127	0	%100
34	M17	Z	-.22	-.22	0	%100
35	M18	X	-.127	-.127	0	%100
36	M18	Z	-.22	-.22	0	%100
37	M19	X	-.383	-.383	0	%100
38	M19	Z	-.664	-.664	0	%100
39	M20	X	-.383	-.383	0	%100
40	M20	Z	-.664	-.664	0	%100
41	M21	X	-.383	-.383	0	%100
42	M21	Z	-.664	-.664	0	%100
43	M22	X	-.383	-.383	0	%100
44	M22	Z	-.664	-.664	0	%100
45	M23	X	-.124	-.124	0	%100
46	M23	Z	-.215	-.215	0	%100
47	M24	X	-.53	-.53	0	%100
48	M24	Z	-.917	-.917	0	%100
49	MP1A	X	-1.213	-1.213	0	%100
50	MP1A	Z	-2.101	-2.101	0	%100
51	MP2A	X	-1.213	-1.213	0	%100
52	MP2A	Z	-2.101	-2.101	0	%100
53	MP3A	X	-1.213	-1.213	0	%100
54	MP3A	Z	-2.101	-2.101	0	%100
55	MP4A	X	-1.213	-1.213	0	%100
56	MP4A	Z	-2.101	-2.101	0	%100

Member Distributed Loads (BLC 65 : Structure Wm (0 Deg))

	Member Label	Direction	Start Magnitude[lb/ft.F.ksf]	End Magnitude[lb/ft...	Start Location[ft.%]	End Location[ft.%]
1	M1	X	0	0	0	%100
2	M1	Z	-.546	-.546	0	%100
3	M2	X	0	0	0	%100
4	M2	Z	-.546	-.546	0	%100
5	M3	X	0	0	0	%100
6	M3	Z	-.215	-.215	0	%100
7	M4	X	0	0	0	%100
8	M4	Z	-.215	-.215	0	%100
9	M5	X	0	0	0	%100

Member Distributed Loads (BLC 65 : Structure Wm (0 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft.F,ksf]	End Magnitude[lb/ft...	Start Location[ft.%]	End Location[ft.%]
10	M5	Z	-.215	-.215	0	%100
11	M6	X	0	0	0	%100
12	M6	Z	-.215	-.215	0	%100
13	M7	X	0	0	0	%100
14	M7	Z	-.123	-.123	0	%100
15	M8	X	0	0	0	%100
16	M8	Z	-.123	-.123	0	%100
17	M9	X	0	0	0	%100
18	M9	Z	-.123	-.123	0	%100
19	M10	X	0	0	0	%100
20	M10	Z	-.123	-.123	0	%100
21	M11	X	0	0	0	%100
22	M11	Z	-.119	-.119	0	%100
23	M12	X	0	0	0	%100
24	M12	Z	-.119	-.119	0	%100
25	M13	X	0	0	0	%100
26	M13	Z	-.119	-.119	0	%100
27	M14	X	0	0	0	%100
28	M14	Z	-.119	-.119	0	%100
29	M15	X	0	0	0	%100
30	M15	Z	0	0	0	%100
31	M16	X	0	0	0	%100
32	M16	Z	0	0	0	%100
33	M17	X	0	0	0	%100
34	M17	Z	0	0	0	%100
35	M18	X	0	0	0	%100
36	M18	Z	0	0	0	%100
37	M19	X	0	0	0	%100
38	M19	Z	-.119	-.119	0	%100
39	M20	X	0	0	0	%100
40	M20	Z	-.119	-.119	0	%100
41	M21	X	0	0	0	%100
42	M21	Z	-.119	-.119	0	%100
43	M22	X	0	0	0	%100
44	M22	Z	-.119	-.119	0	%100
45	M23	X	0	0	0	%100
46	M23	Z	-.017	-.017	0	%100
47	M24	X	0	0	0	%100
48	M24	Z	-.017	-.017	0	%100
49	MP1A	X	0	0	0	%100
50	MP1A	Z	-.451	-.451	0	%100
51	MP2A	X	0	0	0	%100
52	MP2A	Z	-.451	-.451	0	%100
53	MP3A	X	0	0	0	%100
54	MP3A	Z	-.451	-.451	0	%100
55	MP4A	X	0	0	0	%100
56	MP4A	Z	-.451	-.451	0	%100

Member Distributed Loads (BLC 66 : Structure Wm (30 Deg))

	Member Label	Direction	Start Magnitude[lb/ft.F,ksf]	End Magnitude[lb/ft...	Start Location[ft.%]	End Location[ft.%]
1	M1	X	.205	.205	0	%100
2	M1	Z	-.354	-.354	0	%100
3	M2	X	.205	.205	0	%100
4	M2	Z	-.354	-.354	0	%100
5	M3	X	.024	.024	0	%100
6	M3	Z	-.042	-.042	0	%100
7	M4	X	.024	.024	0	%100
8	M4	Z	-.042	-.042	0	%100
9	M5	X	.17	.17	0	%100
10	M5	Z	-.295	-.295	0	%100
11	M6	X	.17	.17	0	%100
12	M6	Z	-.295	-.295	0	%100

Member Distributed Loads (BLC 66 : Structure Wm (30 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft.F,ksf]	End Magnitude[lb/ft...	Start Location[ft.%]	End Location[ft.%]
13	M7	X	.049	.049	0	%100
14	M7	Z	-.085	-.085	0	%100
15	M8	X	.049	.049	0	%100
16	M8	Z	-.085	-.085	0	%100
17	M9	X	.071	.071	0	%100
18	M9	Z	-.122	-.122	0	%100
19	M10	X	.071	.071	0	%100
20	M10	Z	-.122	-.122	0	%100
21	M11	X	.059	.059	0	%100
22	M11	Z	-.103	-.103	0	%100
23	M12	X	.059	.059	0	%100
24	M12	Z	-.103	-.103	0	%100
25	M13	X	.059	.059	0	%100
26	M13	Z	-.103	-.103	0	%100
27	M14	X	.059	.059	0	%100
28	M14	Z	-.103	-.103	0	%100
29	M15	X	.015	.015	0	%100
30	M15	Z	-.026	-.026	0	%100
31	M16	X	.015	.015	0	%100
32	M16	Z	-.026	-.026	0	%100
33	M17	X	.015	.015	0	%100
34	M17	Z	-.026	-.026	0	%100
35	M18	X	.015	.015	0	%100
36	M18	Z	-.026	-.026	0	%100
37	M19	X	.044	.044	0	%100
38	M19	Z	-.077	-.077	0	%100
39	M20	X	.044	.044	0	%100
40	M20	Z	-.077	-.077	0	%100
41	M21	X	.044	.044	0	%100
42	M21	Z	-.077	-.077	0	%100
43	M22	X	.044	.044	0	%100
44	M22	Z	-.077	-.077	0	%100
45	M23	X	.098	.098	0	%100
46	M23	Z	-.17	-.17	0	%100
47	M24	X	.023	.023	0	%100
48	M24	Z	-.04	-.04	0	%100
49	MP1A	X	.225	.225	0	%100
50	MP1A	Z	-.39	-.39	0	%100
51	MP2A	X	.225	.225	0	%100
52	MP2A	Z	-.39	-.39	0	%100
53	MP3A	X	.225	.225	0	%100
54	MP3A	Z	-.39	-.39	0	%100
55	MP4A	X	.225	.225	0	%100
56	MP4A	Z	-.39	-.39	0	%100

Member Distributed Loads (BLC 67 : Structure Wm (60 Deg))

	Member Label	Direction	Start Magnitude[lb/ft.F,ksf]	End Magnitude[lb/ft...	Start Location[ft.%]	End Location[ft.%]
1	M1	X	.118	.118	0	%100
2	M1	Z	-.068	-.068	0	%100
3	M2	X	.118	.118	0	%100
4	M2	Z	-.068	-.068	0	%100
5	M3	X	.006	.006	0	%100
6	M3	Z	-.003	-.003	0	%100
7	M4	X	.006	.006	0	%100
8	M4	Z	-.003	-.003	0	%100
9	M5	X	.259	.259	0	%100
10	M5	Z	-.15	-.15	0	%100
11	M6	X	.259	.259	0	%100
12	M6	Z	-.15	-.15	0	%100
13	M7	X	.08	.08	0	%100
14	M7	Z	-.046	-.046	0	%100
15	M8	X	.08	.08	0	%100

Member Distributed Loads (BLC 67 : Structure Wm (60 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft.F,ksf]	End Magnitude[lb/ft...	Start Location[ft, %]	End Location[ft, %]
16	M8	Z	-.046	-.046	0	%100
17	M9	X	.117	.117	0	%100
18	M9	Z	-.068	-.068	0	%100
19	M10	X	.117	.117	0	%100
20	M10	Z	-.068	-.068	0	%100
21	M11	X	.103	.103	0	%100
22	M11	Z	-.059	-.059	0	%100
23	M12	X	.103	.103	0	%100
24	M12	Z	-.059	-.059	0	%100
25	M13	X	.103	.103	0	%100
26	M13	Z	-.059	-.059	0	%100
27	M14	X	.103	.103	0	%100
28	M14	Z	-.059	-.059	0	%100
29	M15	X	.077	.077	0	%100
30	M15	Z	-.044	-.044	0	%100
31	M16	X	.077	.077	0	%100
32	M16	Z	-.044	-.044	0	%100
33	M17	X	.077	.077	0	%100
34	M17	Z	-.044	-.044	0	%100
35	M18	X	.077	.077	0	%100
36	M18	Z	-.044	-.044	0	%100
37	M19	X	.026	.026	0	%100
38	M19	Z	-.015	-.015	0	%100
39	M20	X	.026	.026	0	%100
40	M20	Z	-.015	-.015	0	%100
41	M21	X	.026	.026	0	%100
42	M21	Z	-.015	-.015	0	%100
43	M22	X	.026	.026	0	%100
44	M22	Z	-.015	-.015	0	%100
45	M23	X	.351	.351	0	%100
46	M23	Z	-.202	-.202	0	%100
47	M24	X	.22	.22	0	%100
48	M24	Z	-.127	-.127	0	%100
49	MP1A	X	.39	.39	0	%100
50	MP1A	Z	-.225	-.225	0	%100
51	MP2A	X	.39	.39	0	%100
52	MP2A	Z	-.225	-.225	0	%100
53	MP3A	X	.39	.39	0	%100
54	MP3A	Z	-.225	-.225	0	%100
55	MP4A	X	.39	.39	0	%100
56	MP4A	Z	-.225	-.225	0	%100

Member Distributed Loads (BLC 68 : Structure Wm (90 Deg))

	Member Label	Direction	Start Magnitude[lb/ft.F,ksf]	End Magnitude[lb/ft...	Start Location[ft, %]	End Location[ft, %]
1	M1	X	0	0	0	%100
2	M1	Z	0	0	0	%100
3	M2	X	0	0	0	%100
4	M2	Z	0	0	0	%100
5	M3	X	.132	.132	0	%100
6	M3	Z	0	0	0	%100
7	M4	X	.132	.132	0	%100
8	M4	Z	0	0	0	%100
9	M5	X	.132	.132	0	%100
10	M5	Z	0	0	0	%100
11	M6	X	.132	.132	0	%100
12	M6	Z	0	0	0	%100
13	M7	X	.111	.111	0	%100
14	M7	Z	0	0	0	%100
15	M8	X	.111	.111	0	%100
16	M8	Z	0	0	0	%100
17	M9	X	.111	.111	0	%100
18	M9	Z	0	0	0	%100

Member Distributed Loads (BLC 68 : Structure Wm (90 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft.F,ksf]	End Magnitude[lb/ft...	Start Location[ft.%]	End Location[ft.%]
19	M10	X	.111	.111	0	%100
20	M10	Z	0	0	0	%100
21	M11	X	.119	.119	0	%100
22	M11	Z	0	0	0	%100
23	M12	X	.119	.119	0	%100
24	M12	Z	0	0	0	%100
25	M13	X	.119	.119	0	%100
26	M13	Z	0	0	0	%100
27	M14	X	.119	.119	0	%100
28	M14	Z	0	0	0	%100
29	M15	X	.119	.119	0	%100
30	M15	Z	0	0	0	%100
31	M16	X	.119	.119	0	%100
32	M16	Z	0	0	0	%100
33	M17	X	.119	.119	0	%100
34	M17	Z	0	0	0	%100
35	M18	X	.119	.119	0	%100
36	M18	Z	0	0	0	%100
37	M19	X	0	0	0	%100
38	M19	Z	0	0	0	%100
39	M20	X	0	0	0	%100
40	M20	Z	0	0	0	%100
41	M21	X	0	0	0	%100
42	M21	Z	0	0	0	%100
43	M22	X	0	0	0	%100
44	M22	Z	0	0	0	%100
45	M23	X	.433	.433	0	%100
46	M23	Z	0	0	0	%100
47	M24	X	.433	.433	0	%100
48	M24	Z	0	0	0	%100
49	MP1A	X	.451	.451	0	%100
50	MP1A	Z	0	0	0	%100
51	MP2A	X	.451	.451	0	%100
52	MP2A	Z	0	0	0	%100
53	MP3A	X	.451	.451	0	%100
54	MP3A	Z	0	0	0	%100
55	MP4A	X	.451	.451	0	%100
56	MP4A	Z	0	0	0	%100

Member Distributed Loads (BLC 69 : Structure Wm (120 Deg))

	Member Label	Direction	Start Magnitude[lb/ft.F,ksf]	End Magnitude[lb/ft...	Start Location[ft.%]	End Location[ft.%]
1	M1	X	.118	.118	0	%100
2	M1	Z	.068	.068	0	%100
3	M2	X	.118	.118	0	%100
4	M2	Z	.068	.068	0	%100
5	M3	X	.259	.259	0	%100
6	M3	Z	.15	.15	0	%100
7	M4	X	.259	.259	0	%100
8	M4	Z	.15	.15	0	%100
9	M5	X	.006	.006	0	%100
10	M5	Z	.003	.003	0	%100
11	M6	X	.006	.006	0	%100
12	M6	Z	.003	.003	0	%100
13	M7	X	.117	.117	0	%100
14	M7	Z	.068	.068	0	%100
15	M8	X	.117	.117	0	%100
16	M8	Z	.068	.068	0	%100
17	M9	X	.08	.08	0	%100
18	M9	Z	.046	.046	0	%100
19	M10	X	.08	.08	0	%100
20	M10	Z	.046	.046	0	%100
21	M11	X	.103	.103	0	%100

Member Distributed Loads (BLC 69 : Structure Wm (120 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft,F,ksf]	End Magnitude[lb/ft...	Start Location[ft.%]	End Location[ft.%]
22	M11	Z	.059	.059	0	%100
23	M12	X	.103	.103	0	%100
24	M12	Z	.059	.059	0	%100
25	M13	X	.103	.103	0	%100
26	M13	Z	.059	.059	0	%100
27	M14	X	.103	.103	0	%100
28	M14	Z	.059	.059	0	%100
29	M15	X	.077	.077	0	%100
30	M15	Z	.044	.044	0	%100
31	M16	X	.077	.077	0	%100
32	M16	Z	.044	.044	0	%100
33	M17	X	.077	.077	0	%100
34	M17	Z	.044	.044	0	%100
35	M18	X	.077	.077	0	%100
36	M18	Z	.044	.044	0	%100
37	M19	X	.026	.026	0	%100
38	M19	Z	.015	.015	0	%100
39	M20	X	.026	.026	0	%100
40	M20	Z	.015	.015	0	%100
41	M21	X	.026	.026	0	%100
42	M21	Z	.015	.015	0	%100
43	M22	X	.026	.026	0	%100
44	M22	Z	.015	.015	0	%100
45	M23	X	.22	.22	0	%100
46	M23	Z	.127	.127	0	%100
47	M24	X	.351	.351	0	%100
48	M24	Z	.202	.202	0	%100
49	MP1A	X	.39	.39	0	%100
50	MP1A	Z	.225	.225	0	%100
51	MP2A	X	.39	.39	0	%100
52	MP2A	Z	.225	.225	0	%100
53	MP3A	X	.39	.39	0	%100
54	MP3A	Z	.225	.225	0	%100
55	MP4A	X	.39	.39	0	%100
56	MP4A	Z	.225	.225	0	%100

Member Distributed Loads (BLC 70 : Structure Wm (150 Deg))

	Member Label	Direction	Start Magnitude[lb/ft,F,ksf]	End Magnitude[lb/ft...	Start Location[ft.%]	End Location[ft.%]
1	M1	X	.205	.205	0	%100
2	M1	Z	.354	.354	0	%100
3	M2	X	.205	.205	0	%100
4	M2	Z	.354	.354	0	%100
5	M3	X	.17	.17	0	%100
6	M3	Z	.295	.295	0	%100
7	M4	X	.17	.17	0	%100
8	M4	Z	.295	.295	0	%100
9	M5	X	.024	.024	0	%100
10	M5	Z	.042	.042	0	%100
11	M6	X	.024	.024	0	%100
12	M6	Z	.042	.042	0	%100
13	M7	X	.071	.071	0	%100
14	M7	Z	.122	.122	0	%100
15	M8	X	.071	.071	0	%100
16	M8	Z	.122	.122	0	%100
17	M9	X	.049	.049	0	%100
18	M9	Z	.085	.085	0	%100
19	M10	X	.049	.049	0	%100
20	M10	Z	.085	.085	0	%100
21	M11	X	.059	.059	0	%100
22	M11	Z	.103	.103	0	%100
23	M12	X	.059	.059	0	%100
24	M12	Z	.103	.103	0	%100

Member Distributed Loads (BLC 70 : Structure Wm (150 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft,F,ksf]	End Magnitude[lb/ft...	Start Location[ft, %]	End Location[ft, %]
25	M13	X	.059	.059	0	%100
26	M13	Z	.103	.103	0	%100
27	M14	X	.059	.059	0	%100
28	M14	Z	.103	.103	0	%100
29	M15	X	.015	.015	0	%100
30	M15	Z	.026	.026	0	%100
31	M16	X	.015	.015	0	%100
32	M16	Z	.026	.026	0	%100
33	M17	X	.015	.015	0	%100
34	M17	Z	.026	.026	0	%100
35	M18	X	.015	.015	0	%100
36	M18	Z	.026	.026	0	%100
37	M19	X	.044	.044	0	%100
38	M19	Z	.077	.077	0	%100
39	M20	X	.044	.044	0	%100
40	M20	Z	.077	.077	0	%100
41	M21	X	.044	.044	0	%100
42	M21	Z	.077	.077	0	%100
43	M22	X	.044	.044	0	%100
44	M22	Z	.077	.077	0	%100
45	M23	X	.023	.023	0	%100
46	M23	Z	.04	.04	0	%100
47	M24	X	.098	.098	0	%100
48	M24	Z	.17	.17	0	%100
49	MP1A	X	.225	.225	0	%100
50	MP1A	Z	.39	.39	0	%100
51	MP2A	X	.225	.225	0	%100
52	MP2A	Z	.39	.39	0	%100
53	MP3A	X	.225	.225	0	%100
54	MP3A	Z	.39	.39	0	%100
55	MP4A	X	.225	.225	0	%100
56	MP4A	Z	.39	.39	0	%100

Member Distributed Loads (BLC 71 : Structure Wm (180 Deg))

	Member Label	Direction	Start Magnitude[lb/ft,F,ksf]	End Magnitude[lb/ft...	Start Location[ft, %]	End Location[ft, %]
1	M1	X	0	0	0	%100
2	M1	Z	.546	.546	0	%100
3	M2	X	0	0	0	%100
4	M2	Z	.546	.546	0	%100
5	M3	X	0	0	0	%100
6	M3	Z	.215	.215	0	%100
7	M4	X	0	0	0	%100
8	M4	Z	.215	.215	0	%100
9	M5	X	0	0	0	%100
10	M5	Z	.215	.215	0	%100
11	M6	X	0	0	0	%100
12	M6	Z	.215	.215	0	%100
13	M7	X	0	0	0	%100
14	M7	Z	.123	.123	0	%100
15	M8	X	0	0	0	%100
16	M8	Z	.123	.123	0	%100
17	M9	X	0	0	0	%100
18	M9	Z	.123	.123	0	%100
19	M10	X	0	0	0	%100
20	M10	Z	.123	.123	0	%100
21	M11	X	0	0	0	%100
22	M11	Z	.119	.119	0	%100
23	M12	X	0	0	0	%100
24	M12	Z	.119	.119	0	%100
25	M13	X	0	0	0	%100
26	M13	Z	.119	.119	0	%100
27	M14	X	0	0	0	%100

Member Distributed Loads (BLC 71 : Structure Wm (180 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft.F,ksf]	End Magnitude[lb/ft...	Start Location[ft.%]	End Location[ft.%]
28	M14	Z	.119	.119	0	%100
29	M15	X	0	0	0	%100
30	M15	Z	0	0	0	%100
31	M16	X	0	0	0	%100
32	M16	Z	0	0	0	%100
33	M17	X	0	0	0	%100
34	M17	Z	0	0	0	%100
35	M18	X	0	0	0	%100
36	M18	Z	0	0	0	%100
37	M19	X	0	0	0	%100
38	M19	Z	.119	.119	0	%100
39	M20	X	0	0	0	%100
40	M20	Z	.119	.119	0	%100
41	M21	X	0	0	0	%100
42	M21	Z	.119	.119	0	%100
43	M22	X	0	0	0	%100
44	M22	Z	.119	.119	0	%100
45	M23	X	0	0	0	%100
46	M23	Z	.017	.017	0	%100
47	M24	X	0	0	0	%100
48	M24	Z	.017	.017	0	%100
49	MP1A	X	0	0	0	%100
50	MP1A	Z	.451	.451	0	%100
51	MP2A	X	0	0	0	%100
52	MP2A	Z	.451	.451	0	%100
53	MP3A	X	0	0	0	%100
54	MP3A	Z	.451	.451	0	%100
55	MP4A	X	0	0	0	%100
56	MP4A	Z	.451	.451	0	%100

Member Distributed Loads (BLC 72 : Structure Wm (210 Deg))

	Member Label	Direction	Start Magnitude[lb/ft.F,ksf]	End Magnitude[lb/ft...	Start Location[ft.%]	End Location[ft.%]
1	M1	X	-.205	-.205	0	%100
2	M1	Z	.354	.354	0	%100
3	M2	X	-.205	-.205	0	%100
4	M2	Z	.354	.354	0	%100
5	M3	X	-.024	-.024	0	%100
6	M3	Z	.042	.042	0	%100
7	M4	X	-.024	-.024	0	%100
8	M4	Z	.042	.042	0	%100
9	M5	X	-.17	-.17	0	%100
10	M5	Z	.295	.295	0	%100
11	M6	X	-.17	-.17	0	%100
12	M6	Z	.295	.295	0	%100
13	M7	X	-.049	-.049	0	%100
14	M7	Z	.085	.085	0	%100
15	M8	X	-.049	-.049	0	%100
16	M8	Z	.085	.085	0	%100
17	M9	X	-.071	-.071	0	%100
18	M9	Z	.122	.122	0	%100
19	M10	X	-.071	-.071	0	%100
20	M10	Z	.122	.122	0	%100
21	M11	X	-.059	-.059	0	%100
22	M11	Z	.103	.103	0	%100
23	M12	X	-.059	-.059	0	%100
24	M12	Z	.103	.103	0	%100
25	M13	X	-.059	-.059	0	%100
26	M13	Z	.103	.103	0	%100
27	M14	X	-.059	-.059	0	%100
28	M14	Z	.103	.103	0	%100
29	M15	X	-.015	-.015	0	%100
30	M15	Z	.026	.026	0	%100

Member Distributed Loads (BLC 72 : Structure Wm (210 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft.F,ksf]	End Magnitude[lb/ft...	Start Location[ft.%]	End Location[ft.%]
31	M16	X	-.015	-.015	0	%100
32	M16	Z	.026	.026	0	%100
33	M17	X	-.015	-.015	0	%100
34	M17	Z	.026	.026	0	%100
35	M18	X	-.015	-.015	0	%100
36	M18	Z	.026	.026	0	%100
37	M19	X	-.044	-.044	0	%100
38	M19	Z	.077	.077	0	%100
39	M20	X	-.044	-.044	0	%100
40	M20	Z	.077	.077	0	%100
41	M21	X	-.044	-.044	0	%100
42	M21	Z	.077	.077	0	%100
43	M22	X	-.044	-.044	0	%100
44	M22	Z	.077	.077	0	%100
45	M23	X	-.098	-.098	0	%100
46	M23	Z	.17	.17	0	%100
47	M24	X	-.023	-.023	0	%100
48	M24	Z	.04	.04	0	%100
49	MP1A	X	-.225	-.225	0	%100
50	MP1A	Z	.39	.39	0	%100
51	MP2A	X	-.225	-.225	0	%100
52	MP2A	Z	.39	.39	0	%100
53	MP3A	X	-.225	-.225	0	%100
54	MP3A	Z	.39	.39	0	%100
55	MP4A	X	-.225	-.225	0	%100
56	MP4A	Z	.39	.39	0	%100

Member Distributed Loads (BLC 73 : Structure Wm (240 Deg))

	Member Label	Direction	Start Magnitude[lb/ft.F,ksf]	End Magnitude[lb/ft...	Start Location[ft.%]	End Location[ft.%]
1	M1	X	-.118	-.118	0	%100
2	M1	Z	.068	.068	0	%100
3	M2	X	-.118	-.118	0	%100
4	M2	Z	.068	.068	0	%100
5	M3	X	-.006	-.006	0	%100
6	M3	Z	.003	.003	0	%100
7	M4	X	-.006	-.006	0	%100
8	M4	Z	.003	.003	0	%100
9	M5	X	-.259	-.259	0	%100
10	M5	Z	.15	.15	0	%100
11	M6	X	-.259	-.259	0	%100
12	M6	Z	.15	.15	0	%100
13	M7	X	-.08	-.08	0	%100
14	M7	Z	.046	.046	0	%100
15	M8	X	-.08	-.08	0	%100
16	M8	Z	.046	.046	0	%100
17	M9	X	-.117	-.117	0	%100
18	M9	Z	.068	.068	0	%100
19	M10	X	-.117	-.117	0	%100
20	M10	Z	.068	.068	0	%100
21	M11	X	-.103	-.103	0	%100
22	M11	Z	.059	.059	0	%100
23	M12	X	-.103	-.103	0	%100
24	M12	Z	.059	.059	0	%100
25	M13	X	-.103	-.103	0	%100
26	M13	Z	.059	.059	0	%100
27	M14	X	-.103	-.103	0	%100
28	M14	Z	.059	.059	0	%100
29	M15	X	-.077	-.077	0	%100
30	M15	Z	.044	.044	0	%100
31	M16	X	-.077	-.077	0	%100
32	M16	Z	.044	.044	0	%100
33	M17	X	-.077	-.077	0	%100

Member Distributed Loads (BLC 73 : Structure Wm (240 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft.F,ksf]	End Magnitude[lb/ft...	Start Location[ft.%]	End Location[ft.%]
34	M17	Z	.044	.044	0	%100
35	M18	X	-.077	-.077	0	%100
36	M18	Z	.044	.044	0	%100
37	M19	X	-.026	-.026	0	%100
38	M19	Z	.015	.015	0	%100
39	M20	X	-.026	-.026	0	%100
40	M20	Z	.015	.015	0	%100
41	M21	X	-.026	-.026	0	%100
42	M21	Z	.015	.015	0	%100
43	M22	X	-.026	-.026	0	%100
44	M22	Z	.015	.015	0	%100
45	M23	X	-.351	-.351	0	%100
46	M23	Z	.202	.202	0	%100
47	M24	X	-.22	-.22	0	%100
48	M24	Z	.127	.127	0	%100
49	MP1A	X	-.39	-.39	0	%100
50	MP1A	Z	.225	.225	0	%100
51	MP2A	X	-.39	-.39	0	%100
52	MP2A	Z	.225	.225	0	%100
53	MP3A	X	-.39	-.39	0	%100
54	MP3A	Z	.225	.225	0	%100
55	MP4A	X	-.39	-.39	0	%100
56	MP4A	Z	.225	.225	0	%100

Member Distributed Loads (BLC 74 : Structure Wm (270 Deg))

	Member Label	Direction	Start Magnitude[lb/ft.F,ksf]	End Magnitude[lb/ft...	Start Location[ft.%]	End Location[ft.%]
1	M1	X	0	0	0	%100
2	M1	Z	0	0	0	%100
3	M2	X	0	0	0	%100
4	M2	Z	0	0	0	%100
5	M3	X	-.132	-.132	0	%100
6	M3	Z	0	0	0	%100
7	M4	X	-.132	-.132	0	%100
8	M4	Z	0	0	0	%100
9	M5	X	-.132	-.132	0	%100
10	M5	Z	0	0	0	%100
11	M6	X	-.132	-.132	0	%100
12	M6	Z	0	0	0	%100
13	M7	X	-.111	-.111	0	%100
14	M7	Z	0	0	0	%100
15	M8	X	-.111	-.111	0	%100
16	M8	Z	0	0	0	%100
17	M9	X	-.111	-.111	0	%100
18	M9	Z	0	0	0	%100
19	M10	X	-.111	-.111	0	%100
20	M10	Z	0	0	0	%100
21	M11	X	-.119	-.119	0	%100
22	M11	Z	0	0	0	%100
23	M12	X	-.119	-.119	0	%100
24	M12	Z	0	0	0	%100
25	M13	X	-.119	-.119	0	%100
26	M13	Z	0	0	0	%100
27	M14	X	-.119	-.119	0	%100
28	M14	Z	0	0	0	%100
29	M15	X	-.119	-.119	0	%100
30	M15	Z	0	0	0	%100
31	M16	X	-.119	-.119	0	%100
32	M16	Z	0	0	0	%100
33	M17	X	-.119	-.119	0	%100
34	M17	Z	0	0	0	%100
35	M18	X	-.119	-.119	0	%100
36	M18	Z	0	0	0	%100

Member Distributed Loads (BLC 74 : Structure Wm (270 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft.F.ksf]	End Magnitude[lb/ft...	Start Location[ft.%]	End Location[ft.%]
37	M19	X	0	0	0	%100
38	M19	Z	0	0	0	%100
39	M20	X	0	0	0	%100
40	M20	Z	0	0	0	%100
41	M21	X	0	0	0	%100
42	M21	Z	0	0	0	%100
43	M22	X	0	0	0	%100
44	M22	Z	0	0	0	%100
45	M23	X	-.433	-.433	0	%100
46	M23	Z	0	0	0	%100
47	M24	X	-.433	-.433	0	%100
48	M24	Z	0	0	0	%100
49	MP1A	X	-.451	-.451	0	%100
50	MP1A	Z	0	0	0	%100
51	MP2A	X	-.451	-.451	0	%100
52	MP2A	Z	0	0	0	%100
53	MP3A	X	-.451	-.451	0	%100
54	MP3A	Z	0	0	0	%100
55	MP4A	X	-.451	-.451	0	%100
56	MP4A	Z	0	0	0	%100

Member Distributed Loads (BLC 75 : Structure Wm (300 Deg))

	Member Label	Direction	Start Magnitude[lb/ft.F.ksf]	End Magnitude[lb/ft...	Start Location[ft.%]	End Location[ft.%]
1	M1	X	-.118	-.118	0	%100
2	M1	Z	-.068	-.068	0	%100
3	M2	X	-.118	-.118	0	%100
4	M2	Z	-.068	-.068	0	%100
5	M3	X	-.259	-.259	0	%100
6	M3	Z	-.15	-.15	0	%100
7	M4	X	-.259	-.259	0	%100
8	M4	Z	-.15	-.15	0	%100
9	M5	X	-.006	-.006	0	%100
10	M5	Z	-.003	-.003	0	%100
11	M6	X	-.006	-.006	0	%100
12	M6	Z	-.003	-.003	0	%100
13	M7	X	-.117	-.117	0	%100
14	M7	Z	-.068	-.068	0	%100
15	M8	X	-.117	-.117	0	%100
16	M8	Z	-.068	-.068	0	%100
17	M9	X	-.08	-.08	0	%100
18	M9	Z	-.046	-.046	0	%100
19	M10	X	-.08	-.08	0	%100
20	M10	Z	-.046	-.046	0	%100
21	M11	X	-.103	-.103	0	%100
22	M11	Z	-.059	-.059	0	%100
23	M12	X	-.103	-.103	0	%100
24	M12	Z	-.059	-.059	0	%100
25	M13	X	-.103	-.103	0	%100
26	M13	Z	-.059	-.059	0	%100
27	M14	X	-.103	-.103	0	%100
28	M14	Z	-.059	-.059	0	%100
29	M15	X	-.077	-.077	0	%100
30	M15	Z	-.044	-.044	0	%100
31	M16	X	-.077	-.077	0	%100
32	M16	Z	-.044	-.044	0	%100
33	M17	X	-.077	-.077	0	%100
34	M17	Z	-.044	-.044	0	%100
35	M18	X	-.077	-.077	0	%100
36	M18	Z	-.044	-.044	0	%100
37	M19	X	-.026	-.026	0	%100
38	M19	Z	-.015	-.015	0	%100
39	M20	X	-.026	-.026	0	%100

Member Distributed Loads (BLC 75 : Structure Wm (300 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft,F,ksf]	End Magnitude[lb/ft...	Start Location[ft, %]	End Location[ft, %]
40	M20	Z	-.015	-.015	0	%100
41	M21	X	-.026	-.026	0	%100
42	M21	Z	-.015	-.015	0	%100
43	M22	X	-.026	-.026	0	%100
44	M22	Z	-.015	-.015	0	%100
45	M23	X	-.22	-.22	0	%100
46	M23	Z	-.127	-.127	0	%100
47	M24	X	-.351	-.351	0	%100
48	M24	Z	-.202	-.202	0	%100
49	MP1A	X	-.39	-.39	0	%100
50	MP1A	Z	-.225	-.225	0	%100
51	MP2A	X	-.39	-.39	0	%100
52	MP2A	Z	-.225	-.225	0	%100
53	MP3A	X	-.39	-.39	0	%100
54	MP3A	Z	-.225	-.225	0	%100
55	MP4A	X	-.39	-.39	0	%100
56	MP4A	Z	-.225	-.225	0	%100

Member Distributed Loads (BLC 76 : Structure Wm (330 Deg))

	Member Label	Direction	Start Magnitude[lb/ft,F,ksf]	End Magnitude[lb/ft...	Start Location[ft, %]	End Location[ft, %]
1	M1	X	-.205	-.205	0	%100
2	M1	Z	-.354	-.354	0	%100
3	M2	X	-.205	-.205	0	%100
4	M2	Z	-.354	-.354	0	%100
5	M3	X	-.17	-.17	0	%100
6	M3	Z	-.295	-.295	0	%100
7	M4	X	-.17	-.17	0	%100
8	M4	Z	-.295	-.295	0	%100
9	M5	X	-.024	-.024	0	%100
10	M5	Z	-.042	-.042	0	%100
11	M6	X	-.024	-.024	0	%100
12	M6	Z	-.042	-.042	0	%100
13	M7	X	-.071	-.071	0	%100
14	M7	Z	-.122	-.122	0	%100
15	M8	X	-.071	-.071	0	%100
16	M8	Z	-.122	-.122	0	%100
17	M9	X	-.049	-.049	0	%100
18	M9	Z	-.085	-.085	0	%100
19	M10	X	-.049	-.049	0	%100
20	M10	Z	-.085	-.085	0	%100
21	M11	X	-.059	-.059	0	%100
22	M11	Z	-.103	-.103	0	%100
23	M12	X	-.059	-.059	0	%100
24	M12	Z	-.103	-.103	0	%100
25	M13	X	-.059	-.059	0	%100
26	M13	Z	-.103	-.103	0	%100
27	M14	X	-.059	-.059	0	%100
28	M14	Z	-.103	-.103	0	%100
29	M15	X	-.015	-.015	0	%100
30	M15	Z	-.026	-.026	0	%100
31	M16	X	-.015	-.015	0	%100
32	M16	Z	-.026	-.026	0	%100
33	M17	X	-.015	-.015	0	%100
34	M17	Z	-.026	-.026	0	%100
35	M18	X	-.015	-.015	0	%100
36	M18	Z	-.026	-.026	0	%100
37	M19	X	-.044	-.044	0	%100
38	M19	Z	-.077	-.077	0	%100
39	M20	X	-.044	-.044	0	%100
40	M20	Z	-.077	-.077	0	%100
41	M21	X	-.044	-.044	0	%100
42	M21	Z	-.077	-.077	0	%100

Member Distributed Loads (BLC 76 : Structure Wm (330 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft,F,ksf]	End Magnitude[lb/ft...	Start Location[ft.%]	End Location[ft.%]
43	M22	X	-.044	-.044	0	%100
44	M22	Z	-.077	-.077	0	%100
45	M23	X	-.023	-.023	0	%100
46	M23	Z	-.04	-.04	0	%100
47	M24	X	-.098	-.098	0	%100
48	M24	Z	-.17	-.17	0	%100
49	MP1A	X	-.225	-.225	0	%100
50	MP1A	Z	-.39	-.39	0	%100
51	MP2A	X	-.225	-.225	0	%100
52	MP2A	Z	-.39	-.39	0	%100
53	MP3A	X	-.225	-.225	0	%100
54	MP3A	Z	-.39	-.39	0	%100
55	MP4A	X	-.225	-.225	0	%100
56	MP4A	Z	-.39	-.39	0	%100

Envelope Joint Reactions

	Joint		X [lb]	LC	Y [lb]	LC	Z [lb]	LC	MX [k-ft]	LC	MY [k-ft]	LC	MZ [k-ft]	LC
1	N1	max	1456.788	33	1026.747	24	1224.065	13	-.159	69	0	75	.279	32
2		min	-76.304	3	380.919	69	-11.756	7	-.431	13	0	1	-.011	2
3	N2	max	439.401	10	1038.829	18	-73.844	7	-.161	75	0	75	.27	32
4		min	-1479.688	28	383.641	75	-1049.424	13	-.436	18	0	1	-.012	2
5	N56	max	109.004	10	52.823	18	467.452	12	0	75	0	75	0	75
6		min	-121.532	4	18.509	74	-528.34	6	0	1	0	1	0	1
7	N57	max	254.642	8	52.902	20	1196.535	2	0	75	0	75	0	75
8		min	-241.665	2	18.509	65	-1260.51	8	0	1	0	1	0	1
9	Totals:	max	1219.733	9	2162.366	21	1624.737	1						
10		min	-1219.734	3	802.401	67	-1624.738	7						

Envelope AISC 15th(360-16): LRFD Steel Code Checks

	Member	Shape	Code Check	Lo...	LC	Shear Check	Lo...	phi*P	phi*P	phi*M	phi*M	Eqn
1	M1	PIPE 2.5	.270	8.7...	30	.088	8.7...	431455...	50715	3.596	3.596	H1-1b
2	M2	PIPE 2.5	.258	8.7...	33	.096	8.7...	2 1455...	50715	3.596	3.596	H1-1b
3	M3	PIPE 2.0	.099	0	5	.041	0	173112...	32130	1.872	1.872	H1-1b
4	M4	PIPE 2.0	.054	0	8	.035	0	133112...	32130	1.872	1.872	H1-1b
5	M5	PIPE 2.0	.099	2.5...	32	.085	0	333112...	32130	1.872	1.872	H1-1b
6	M6	PIPE 2.0	.131	0	3	.072	0	323112...	32130	1.872	1.872	H1-1b
7	M7	SR 0.75	.000	4.1...	32	.006	4.1...	322863...	1391...	.174	.174	H1-...
8	M8	SR 0.75	.031	0	14	.012	0	2 2863...	1391...	.174	.174	H1-...
9	M9	SR 0.75	.000	0	75	.014	0	312863...	1391...	.174	.174	H1-1a
10	M10	SR 0.75	.087	4.1...	31	.018	0	332863...	1391...	.174	.174	H1-...
11	M11	SR 0.625	.039	1.6...	11	.014	0	322158...	9664...	.101	.101	H1-1b
12	M12	SR 0.625	.030	1.6...	9	.014	0	8 2158...	9664...	.101	.101	H1-1b
13	M13	SR 0.625	.044	1.6...	7	.015	0	2 2158...	9664...	.101	.101	1 H1-1b
14	M14	SR 0.625	.113	0	2	.016	0	322158...	9664...	.101	.101	H1-...
15	M15	PL5/8X3.5	.102	0	3	.106	.422 y	5 6618...	6890...	.897	5.024	H1-1b
16	M16	PL5/8X3.5	.075	.422	20	.053	.422 y	8 6618...	6890...	.897	5.024	H1-1b
17	M17	PL5/8X3.5	.274	0	32	.100	0 y	1 6618...	6890...	.897	5.024	H1-1b
18	M18	PL5/8X3.5	.216	0	25	.121	.422 y	3 6618...	6890...	.897	5.024	H1-1b
19	M19	PL5/8X3.5	.152	.531	13	.040	0 y	6 6759...	6890...	.897	5.024	H1-1b
20	M20	PL5/8X3.5	.410	.531	27	.063	0 y	276759...	6890...	.897	5.024	H1-1b
21	M21	PL5/8X3.5	.167	.531	14	.021	.531 y	1 6759...	6890...	.897	5.024	H1-1b
22	M22	PL5/8X3.5	.427	.531	36	.046	.531 y	256759...	6890...	.897	5.024	H1-1b
23	M23	PIPE 2.0	.099	5.9...	10	.006	0	227005...	32130	1.872	1.872	H1-1b
24	M24	PIPE 2.0	.174	11...	2	.006	0	227005...	32130	1.872	1.872	H1-...
25	MP1A	PIPE 2.0	.415	2.3...	27	.068	5.6...	361491...	32130	1.872	1.872	H1-1b
26	MP2A	PIPE 2.0	.312	2.3...	2	.083	2.3...	8 1491...	32130	1.872	1.872	H1-1b
27	MP3A	PIPE 2.0	.167	2.3...	32	.048	4.0...	9 1491...	32130	1.872	1.872	H1-1b
28	MP4A	PIPE 2.0	.071	2.3...	21	.011	2.3...	331491...	32130	1.872	1.872	H1-1b

Version 1.01


Yes

A diagram of a triangular truss structure. The truss has three main vertices and three internal nodes. The top vertex is connected to two internal nodes, which are connected to each other and to the bottom vertex. The left and right sides are vertical. The top and bottom members are horizontal. The internal members are diagonal. The truss is subjected to four external forces: a 50 deg force at the top vertex pointing up, a 180 deg force at the left vertex pointing left, a 0 deg force at the right vertex pointing right, and a 270 deg force at the bottom vertex pointing down. A small square symbol is located at the bottom-left internal node, indicating a right angle.

Yes

Parallel

4
12
5
A307
0.5
0.7
0.6
6.6
4,0
13.9%



No

ATTACHMENT 4

© 2014 Google

Search result

366 Old Long Ridge Rd, Stamford, Connecticut,
06903

© Zoom to



OLD LONG RIDGE RD

OLD LONG RIDGE RD

CURRENT OWNER		TOPO	UTILITIES		STRT / ROAD		LOCATION		CURRENT ASSESSMENT						
LONG RIDGE FIRE CO INC			6 Septic	3 Unpaved					Description	Code	Appraised	Assessed			
			5 Well	1 Paved					EX COM LN	21	365,320	255,720			
			7						EX COM BL	22	1,534,420	1,074,100			
366 OLD LONG RIDGE RD			SUPPLEMENTAL DATA						EX CM OTB	25	734,040	513,840			
STAMFORD CT 06903-1133		Alt Prcl ID 14 400 B	DSSD												
		Survey1 11116	Agent Nam												
		Survey2 203	Roll												
		Census Tr 3005	Common												
		Census Bl	Neighborn												
		Sewer Acct	N STAM:												
GIS ID W 016 6320		Assoc Pid#													
RECORD OF OWNERSHIP			BK-VOL/PAGE	SALE DATE	Q/U	V/I	SALE PRICE	VC	PREVIOUS ASSESSMENTS (HISTORY)						
LONG RIDGE FIRE CO INC			0686 0581	01-14-1953	U	I	0	25	Year	Code	Assessed	Year	Code	Assessed	
									2022	21	255,720	2022	21	255,720	
										22	1,074,100		22	1,074,100	
										25	513,840		25	513,840	
			Total	1,843,660.00					Total	1,843,660			Total	1,843,660	
EXEMPTIONS			OTHER ASSESSMENTS				APPRAISED VALUE SUMMARY								
Year	Code	Description	Amount	Code	Description	Number	Amount	Comm Int							
2012	CAAX	Volunteer Fire Company	1843660.00												
			Total	1,843,660.00											
ASSESSING NEIGHBORHOOD			NOTES												
Nbhd			B Tracing												
0100															
1 STRY FIREHOUSE															
LONG RIDGE FIRE CO															
ATT															
SPRINT															
NEXTEL															
2 FC1 OWNED BY CITY															
BUILDING PERMIT RECORD			VISIT / CHANGE HISTORY												
Permit Id	Issue Date	Type	Description	Amount	Insp Date	% Comp	Date Comp	Comments	Date	Id	Type	Is	Cd	Purpost/Result	
B-21-1245	07-06-2021	NV	No Value	0	0	100	04-19-2022	VERIZON WILL SWAP 3 ANT	08-15-2022	MVS			01	Measur+1Visit	
B-21-442	03-04-2021	NV	No Value	0	10-01-1996			REPLACEMENT OF 6 CELLU	10-15-2012	SM			80	Walk Around, No one hom	
76376	01-26-1996	RE		0	10-06-1994			C/O 25198 10-6-97 INTERAL	07-31-2012	SM			00	Measur+Listed	
73737	12-09-1993	AD		221,070				C/O 22755 6-23-94. SECOND							
			Total Appraised Parcel Value												
			2,633,780												
LAND LINE VALUATION SECTION															
B Use Code	Description	Zone	Distri	District Desc.	Land Units	Unit Price	I. Factor	Site Index	Cond.	Nbhd.	Nbhd Adj	Notes	Location Adjustment	Adj Unit Price	Land Value
1 902C	Exmpt Comm M	RA2	3		0.490	AC 407,029.70	1.83169	C	1.00	0100	1.000		0	745,556.3	365,320
Total Card Land Units			0.49 AC			Parcel Total Land Area: 0.49			Total Land Value			365,320			

CONSTRUCTION DETAIL			CONSTRUCTION DETAIL (CONTINUED)		
Element	Cd	Description	Element	Cd	Description
Style:	89	Fire Station			
Model	96	Ind/Comm			
Grade	07	B			
Stories:	1				
Occupancy	1.00				
Exterior Wall 1	23	Brick/Masonry			
Exterior Wall 2	03	Gable/Hip			
Roof Structure	03	Asph/F Glis/Cmp			
Roof Cover	01	Minimum			
Interior Wall 1	05	Drywall/Plaste			
Interior Wall 2	03	Concrete Slab			
Interior Floor 1	05	Vinyl/Asphalt			
Interior Floor 2	03	Oil			
Heating Fuel	03	Forced Air-Duc			
Heating Type	07	Partial A/C			
AC Type	902C	Exmpt Comm MDL-94			
Bldg Use					
Total Rooms	00				
Total Bedrms	0				
Total Baths	01				
Heat/AC	06	Heat/AC Pkgs			
Frame Type	02	FireProofSteel			
Baths/Plumbing	04	Average			
Ceiling/Wall	02	Ceil & Mn Wall			
Rooms/Ptns	11.00	Average			
Wall Height					
% Conn Wall	902C				
1st Floor Use:					
			</		

ATTACHMENT 5



Certificate of Mailing — Firm

Name and Address of Sender Kenneth C. Baldwin, Esq. Robinson & Cole LLP 280 Trumbull Street Hartford, CT 06103		TOTAL NO. of Pieces Listed by Sender 3	TOTAL NO. of Pieces Received at Post Office™ 3	Affix Stamp Here Postmark with Date of Receipt. neopost 01/05/2024 US POSTAGE \$003.19 04111203937 ZIP 06903 04111203937 42, 5 - NAF OLD STAMFORD			
USPS® Tracking Number Firm-specific Identifier		Postmaster, per (name of receiving employee) [Signature]		Postage	Fee	Special Handling	Parcel/Airift
1.		Address (Name, Street, City, State, and ZIP Code™) Caroline Simmons, Mayor City of Stamford - Stamford Government Center 888 Washington Boulevard Stamford, CT 06901					
2.		Ralph Blessing, Land Use Bureau Chief City of Stamford - Stamford Government Center 888 Washington Boulevard Stamford, CT 06901					
3.		Long Ridge Fire Company Inc. 366 Old Long Ridge Road Stamford, CT 06903					
4.							
5.							
6.							