

Filed by:

Kri Pelletier, Property Specialist - SBA Communications
134 Flanders Rd., Suite 125, Westborough, MA 01581
508.251.0720 x 3804 - kpelletier@sbasite.com

June 19, 2018

Melanie A. Bachman
Acting Executive Director
Connecticut Siting Council
Ten Franklin Square
New Britain, CT 06051

Notice of Exempt Modification

**Taugwonk Spur Road No. 2
Stonington, CT 06378
Sprint Site #: CT03XC107_DO Macro Upgrade
N 41 22 56.1
W -71 54 12.4**

Dear Ms. Bachman:

Sprint currently maintains antennas at the 145-foot level of the existing 190-foot Monopole Tower at 2 Taugwonk Spur, Stonington, CT. The tower is owned by SBA Properties, LLC. The property is owned by Louis J. D'Amato & John C. D'Amato. Sprint now intends to replace (6) existing antennas with (6) newer technology cell antennas at the 145-foot level of the tower. The proposed full scope of work is as follows:

Remove:

- (9) 1-5/8" lines

Remove and Replace:

- Remove:
 - (6) Decibel/db908h90e-m panel antennas (actual); and
 - (3) Decibel/db908h90e-m panel antennas (entitlements only)
- Replace with:
 - (3) RFS APXVTM14-C-I20 – Panel Antennas
 - (3) Commscope NNVV-65B-R4 – Panel Antennas

Install:

- (3) ALU 1900 MHz – RRUs
- (6) ALU 800 MHz – RRUs
- (3) ALU TD-RRH8x20-25 – RRUs
- (1) SitePro HRK14-U Handrail Kit
- (1) SitePro PRK-SFS-H-L Vbrace Kit
- (1) SitePro PRK-1245L reinforcement kit
- (6) SitePro SCX1-K Brackets
- (3) Pipe2.0STD x 4' long corner braces
- (3) Pipe2.0STD x 14' horizontal rails
- (4) 1-1/4" fiber

Existing Equipment to Remain (Including entitlements):

- (1) Low Profile Platform
- At 46.5':
 - (1) GPS
 - (1) 4' standoff
 - (1) $\frac{1}{2}$ " line

This facility was approved prior to the Council's jurisdiction, on 5/19/98, by the Town of Stonington's Planning & Zoning Commission. Application #PZ9820SPA was approved for a multi-tenant monopole telecom facilities and placement of associated equipment. The only stipulation for construction was to screen with Colorado or White Spruce. There were no post-constructions conditions placed on the tower. This modification complies with all conditions.

Please accept this letter as notification pursuant to Regulations of Connecticut State Agencies §16-50j-73, for construction that constitutes an exempt modification pursuant to R.C.S.A. §16.50j-72(b)(2). In accordance with R.C.S.A. § 16.50j-73, a copy of this letter is being sent to the Town of Stonington's First Selectman, Robert Simmons, Director of Planning, Jason Vincent, as well as to the property owners, Louis J. D'Amato & John C. D'Amato/D'Amato Investments, LLC. (Separate notice is not being sent to tower owner, as it belongs to SBA.)

The planned modifications to the facility fall squarely within those activities explicitly provided for in R.C.S.A. §16.50j-72(b)(2).

1. The proposed modifications will not result in an increase in the height of the existing structure.
2. The proposed modification will not require the extension of the site boundary.
3. The proposed modifications will not increase noise levels at the facility by six decibels or more, or to levels that exceed state and local criteria.
4. The operation of the replacement antennas will not increase radio frequency emissions at the facility to a level at or above the Federal Communications Commission safety standard.
5. The proposed modification will not cause a change or alteration in the physical or environmental characteristics of the site.
6. The existing structure and its foundation can support the proposed loading.

For the foregoing reasons, Sprint respectfully submits that the proposed modifications to the above-referenced telecommunication facility constitute an exempt modifications under R.C.S.A. § 16-50j-72(b)(2).

Sincerely,



Kri Pelletier

Property Specialist

SBA COMMUNICATIONS CORPORATION

134 Flanders Rd., Suite 125

Westborough, MA 01581

508.251.0720 x3804 + T

508.366.2610 + F

203.446.7700 + C

kpelletier@sbsite.com

Attachments



cc: Robert Simmons, First Selectman / with attachments
Town of Stonington, 152 Elm Street, Stonington, CT 06378
Jason Vincent, Director of Planning / with attachments
Town of Stonington, 152 Elm Street, Stonington, CT 06378
Louis J. D'Amato & John C. D'Amato / D'Amato Investments, LLC / with attachments
183 Quarry Road Milford CT 06460



POWER DENSITY

SPRINT Site Inventory and Power Data by Antenna

Sector:	A	Sector:	B	Sector:	C
Antenna #:	1	Antenna #:	1	Antenna #:	1
Make / Model:	Commscope NNVV-65B-R4	Make / Model:	Commscope NNVV-65B-R4	Make / Model:	Commscope NNVV-65B-R4
Gain:	12.75 / 15.05 dBd	Gain:	12.75 / 15.05 dBd	Gain:	12.75 / 15.05 dBd
Height (AGL):	145 feet	Height (AGL):	145 feet	Height (AGL):	145 feet
Frequency Bands	850 MHz / 1900 MHz (PCS)	Frequency Bands	850 MHz / 1900 MHz (PCS)	Frequency Bands	850 MHz / 1900 MHz (PCS)
Channel Count	10	Channel Count	10	Channel Count	10
Total TX Power(W):	280 Watts	Total TX Power(W):	280 Watts	Total TX Power(W):	280 Watts
ERP (W):	7,378.61	ERP (W):	7,378.61	ERP (W):	7,378.61
Antenna A1 MPE%	1.69 %	Antenna B1 MPE%	1.69 %	Antenna C1 MPE%	1.69 %
Antenna #:	2	Antenna #:	2	Antenna #:	2
Make / Model:	RFS APXVTM14-ALU- I20	Make / Model:	RFS APXVTM14-ALU- I20	Make / Model:	RFS APXVTM14-ALU- I20
Gain:	15.9 dBd	Gain:	15.9 dBd	Gain:	15.9 dBd
Height (AGL):	145 feet	Height (AGL):	145 feet	Height (AGL):	145 feet
Frequency Bands	2500 MHz (BRS)	Frequency Bands	2500 MHz (BRS)	Frequency Bands	2500 MHz (BRS)
Channel Count	8	Channel Count	8	Channel Count	8
Total TX Power(W):	160 Watts	Total TX Power(W):	160 Watts	Total TX Power(W):	160 Watts
ERP (W):	6,224.72	ERP (W):	6,224.72	ERP (W):	6,224.72
Antenna A2 MPE%	1.16 %	Antenna B2 MPE%	1.16 %	Antenna C2 MPE%	1.16 %

Site Composite MPE%	
Carrier	MPE %
SPRINT – Max per sector	2.85 %
Nextel	0.17 %
Public Safety	0.04 %
T-Mobile	1.71 %
CL&P	2.44 %
MetroPCS	0.25 %
Site Total MPE %:	7.46 %

SPRINT Sector A Total:	2.85 %
SPRINT Sector B Total:	2.85 %
SPRINT Sector C Total:	2.85 %
Site Total:	7.46 %

Site Total MPE %	7.46 %	SPRINT Frequency Band / Technology (Per Sector)	# Channels	Watts ERP (Per Channel)	Height (feet)	Total Power Density ($\mu\text{W}/\text{cm}^2$)	Frequency (MHz)	Allowable MPE ($\mu\text{W}/\text{cm}^2$)	Calculated % MPE
Sprint 850 MHz CDMA	1	376.73	145	0.70	850 MHz	567	0.11%		
Sprint 850 MHz LTE	2	941.82	145	3.50	850 MHz	567	0.62%		
Sprint 1900 MHz (PCS) CDMA	5	511.82	145	4.76	1900 MHz (PCS)	1000	0.48%		
Sprint 1900 MHz (PCS) LTE	2	1,279.56	145	4.76	1900 MHz (PCS)	1000	0.48%		
Sprint 2500 MHz (BRS) LTE	8	778.09	145	11.58	2500 MHz (BRS)	1000	1.16%		
								Total:	2.85%

ORIGIN ID: BBFA
RICK WOODS
SBA NETWORK SERVICES INC
134 FLANDERS ROAD
SUITE 125
WESTBOROUGH, MA 01581
UNITED STATES US

(508) 614-0389

SHIP DATE: 19 JUN 18
ACT. WT.: 1.00 LB
CAD: 105843304/NET 3980

BILL SENDER


TO ROBERT SIMMONS, FIRST SELECTMAN
TOWN OF STONINGTON
152 ELM STREET

STONINGTON CT 06378
(508) 251-0720 X 3804

REF: 105843309/6089

PO:

DEPT:



J181118012601uv

552.2/93DF/DCA5

WED - 20 JUN 12:00P
PRIORITY OVERNIGHT

TRK#
0201
7725 1341 6263

EB GONA

06378
CT-US
BDL

**After printing this label:**

1. Use the 'Print' button on this page to print your label to your laser or inkjet printer.
2. Fold the printed page along the horizontal line.
3. Place label in shipping pouch and affix it to your shipment so that the barcode portion of the label can be read and scanned.

Warning: Use only the printed original label for shipping. Using a photocopy of this label for shipping purposes is fraudulent and could result in additional billing charges, along with the cancellation of your FedEx account number.

Use of this system constitutes your agreement to the service conditions in the current FedEx Service Guide, available on fedex.com. FedEx will not be responsible for any claim in excess of \$100 per package, whether the result of loss, damage, delay, non-delivery, misdelivery, or misinformation, unless you declare a higher value, pay an additional charge, document your actual loss and file a timely claim. Limitations found in the current FedEx Service Guide apply. Your right to recover from FedEx for any loss, including intrinsic value of the package, loss of sales, income interest, profit, attorney's fees, costs, and other forms of damage whether direct, incidental, consequential, or special is limited to the greater of \$100 or the authorized declared value. Recovery cannot exceed actual documented loss. Maximum for items of extraordinary value is \$1,000, e.g. jewelry, precious metals, negotiable instruments and other items listed in our ServiceGuide. Written claims must be filed within strict time limits, see current FedEx Service Guide.

ORIGIN ID:BBFA (508) 614-0389
 RICK WOODS
 SBG NETWORK SERVICES INC
 134 FLANDERS ROAD
 SUITE 125
 WESTBOROUGH, MA 01581
 UNITED STATES US

SHIP DATE: 19 JUN 18
 ACT WT: 1.00 LB
 CID: 105843304/NET3980
 BILL SENDER


TO JASON VINCENT, DIRECTOR OF PLANNING
 TOWN OF STONINGTON
 152 ELM STREET

STONINGTON CT 06378

(508) 251-0720 X 3804

REF: 105843304/NET3980
 PO: _____
 DEPT: _____

552J293DFDC0A5



WED - 20 JUN 12:00P
 PRIORITY OVERNIGHT

TRK#
 0201 7725 1344 3852

06378
 CT-US
 BDL

EB GONA



After printing this label:

1. Use the 'Print' button on this page to print your label to your laser or inkjet printer.
2. Fold the printed page along the horizontal line.
3. Place label in shipping pouch and affix it to your shipment so that the barcode portion of the label can be read and scanned.

Warning: Use only the printed original label for shipping. Using a photocopy of this label for shipping purposes is fraudulent and could result in additional billing charges, along with the cancellation of your FedEx account number.

Use of this system constitutes your agreement to the service conditions in the current FedEx Service Guide, available on fedex.com. FedEx will not be responsible for any claim in excess of \$100 per package, whether the result of loss, damage, delay, non-delivery, misdelivery, or misinformation, unless you declare a higher value, pay an additional charge, document your actual loss and file a timely claim. Limitations found in the current FedEx Service Guide apply. Your right to recover from FedEx for any loss, including intrinsic value of the package, loss of sales, income interest, profit, attorney's fees, costs, and other forms of damage whether direct, incidental, consequential, or special is limited to the greater of \$100 or the authorized declared value. Recovery cannot exceed actual documented loss. Maximum for items of extraordinary value is \$1,000, e.g. jewelry, precious metals, negotiable instruments and other items listed in our ServiceGuide. Written claims must be filed within strict time limits, see current FedEx Service Guide.

ORIGIN ID: BBFA
RICK WOODS
SBA NETWORK SERVICES INC
134 FLANDERS ROAD
SUITE 125
WESTBOROUGH, MA 01581
UNITED STATES US

(508) 614-0389

SHIP DATE: 19 JUN 18
ACT. WT.: 1.00 LB
CAD: 105843304/NET3980

BILL SENDER

TO LOUIS AND JOHN D'AMATO
D'AMATO INVESTMENTS LLC
183 QUARRY RD.


MILFORD CT 06460

(508) 251-0720 X 3804

REF: 1056920096089

PO:

DEPT:




552J293DF/DCA5

WED - 20 JUN 10:30A
PRIORITY OVERNIGHT

TRK#
0201 7725 1346 6327

06460
CT-US
BDL

EB OXCA



After printing this label:

1. Use the 'Print' button on this page to print your label to your laser or inkjet printer.
2. Fold the printed page along the horizontal line.
3. Place label in shipping pouch and affix it to your shipment so that the barcode portion of the label can be read and scanned.

Warning: Use only the printed original label for shipping. Using a photocopy of this label for shipping purposes is fraudulent and could result in additional billing charges, along with the cancellation of your FedEx account number.

Use of this system constitutes your agreement to the service conditions in the current FedEx Service Guide, available on fedex.com. FedEx will not be responsible for any claim in excess of \$100 per package, whether the result of loss, damage, delay, non-delivery, misdelivery, or misinformation, unless you declare a higher value, pay an additional charge, document your actual loss and file a timely claim. Limitations found in the current FedEx Service Guide apply. Your right to recover from FedEx for any loss, including intrinsic value of the package, loss of sales, income interest, profit, attorney's fees, costs, and other forms of damage whether direct, incidental, consequential, or special is limited to the greater of \$100 or the authorized declared value. Recovery cannot exceed actual documented loss. Maximum for items of extraordinary value is \$1,000, e.g. jewelry, precious metals, negotiable instruments and other items listed in our ServiceGuide. Written claims must be filed within strict time limits, see current FedEx Service Guide.



Town of Stonington, CT
Property Listing Report

Map Block Lot 84-1-3

Account 00194500

Property Information


Property Location	TAUGWONK SPUR RD		
Owner	DAMATO INVESTMENTS LLC		
Co-Owner			
Mailing Address	183 QUARRY RD	MILFORD	CT 06460
Land Use	3324 COM JOB SHOP(S)		
Land Class	C		
Survey Map #	NA		
School District			

Fire District	Wequetequock	
Census Tract	7054	
Neighborhood	2500	
Zoning Code	LI-130	
Acreage	8.5	
Utilities		
Lot Setting/Desc	Suburban	Above Street
Trash Day	TH	
Polling Place (District)	Deans Mill Sch	3

Photo



Sketch



Primary Construction Details

Year Built	1984
Stories	1
Building Style	Job Shop(s)
Building Use	Gar/Svc Statn
Building Condition	Average
Floors	Concr-Finished
Total Rooms	0

Bedrooms	0
Full Bathrooms	0
Half Bathrooms	0
Bath Style	NA
Kitchen Style	NA
Roof Style	Gable/Hip
Roof Cover	Asph/F Gls/Cmp

Exterior Walls	Concr/Cinder
Interior Walls	Drywall/Sheet
Heating Type	Hot Air-no Duc
Heating Fuel	Gas
AC Type	None
Gross Bldg Area	5000
Total Living Area	5000



Town of Stonington, CT
Property Listing Report

Map Block Lot 84-1-3

Account 00194500

Valuation Summary (Assessed value = 70% of Appraised Value)

Item	Appraised	Assessed
Buildings	2290700	1603500
Extras	0	0
Outbuildings	146400	102600
Land	540100	378100
Total	2977200	2084200

Sub Areas

Subarea Type	Gross Area (sq ft)	Living Area (sq ft)
First Floor	5000	5000
Total Area	5000	5000

Sales History

Owner of Record	Book/ Page	Sale Date	Sale Price
DAMATO INVESTMENTS LLC	740/ 277	5/22/2015	2000
DAMATO INVESTMENTS LLC	421/ 81	7/7/1998	0

Outbuilding and Extra Items

Type	Description
FENCE-8' CHAIN	108.00 L.F.
PAVING-ASPHALT	60000.00 S.F.
CELL TOWER	
LIGHTS-IN W/PL	5.00 UNITS
PAVING-CONC	484.00 S.F.



**Town of Stonington, CT
Property Listing Report**

Map Block Lot 84-1-3

Account 00194500

Photo



Sketch



Primary Construction Details

Year Built	1984
Stories	1
Building Style	Job Shop(s)
Building Use	Gar/Svc Statn
Building Condition	Average
Floors	Concr-Finished
Total Rooms	0
Bedrooms	0
Bathrooms	0
Bath Style	NA

Kitchen Style	NA
Roof Style	Gable/Hip
Roof Cover	Asph/F Gls/Cmp
Exterior Walls	Concr/Cinder
Interior Walls	Minim/Masonry
Heating Type	Hot Air-no Duc
Heating Fuel	Gas
AC Type	None
Gross Bldg Area	16000
Total Living Area	16000

Sub Areas

Subarea Type	Gross Area (sq ft)	Living Area (sq ft)
First Floor	16000	16000
Total Area	16000	16000

Photo



Sketch



Primary Construction Details

Year Built	1984
Stories	1
Building Style	Job Shop(s)
Building Use	Gar/Svc Statn
Building Condition	Average
Floors	Concr-Finished
Total Rooms	0
Bedrooms	0
Bathrooms	0
Bath Style	NA

Kitchen Style	NA
Roof Style	Gable/Hip
Roof Cover	Asph/F Gls/Cmp
Exterior Walls	Brick/Masonry
Interior Walls	Minim/Masonry
Heating Type	Hot Air-no Duc
Heating Fuel	Gas
AC Type	None
Gross Bldg Area	9600
Total Living Area	9600

Subarea Type	Gross Area (sq ft)	Living Area (sq ft)
First Floor	9600	9600
Total Area	9600	9600



Town of Stonington, CT
Property Listing Report

Map Block Lot 84-1-3

Account 00194500

Photo



Sketch



Primary Construction Details

Year Built	1984	Kitchen Style	NA
Stories	1	Roof Style	Gable/Hip
Building Style	Job Shop(s)	Roof Cover	Asph/F Gls/Cmp
Building Use	Gar/Svc Statn	Exterior Walls	Brick/Masonry
Building Condition	Average	Interior Walls	Drywall/Sheet
Floors	Concr-Finished	Heating Type	Hot Air-no Duc
Total Rooms	0	Heating Fuel	Gas
Bedrooms	0	AC Type	None
Bathrooms	0	Gross Bldg Area	8000
Bath Style	NA	Total Living Area	8000

Sub Areas

Subarea Type	Gross Area (sq ft)	Living Area (sq ft)
First Floor	7200	7200
Office,	800	800

Total Area 8000 8000

Photo



Sketch



Primary Construction Details

Year Built	1995	Kitchen Style	NA
Stories	1	Roof Style	Gable/Hip
Building Style	Job Shop(s)	Roof Cover	Asph/F Gls/Cmp
Building Use	Gar/Svc Statn	Exterior Walls	Brick/Masonry
Building Condition	Average	Interior Walls	Drywall/Sheet
Floors	Concr-Finished	Heating Type	Hot Air-no Duc
Total Rooms	0	Heating Fuel	Gas
Bedrooms	0	AC Type	None
Bathrooms	0	Gross Bldg Area	9600
Bath Style	NA	Total Living Area	9600

Subarea Type	Gross Area (sq ft)	Living Area (sq ft)
First Floor	9600	9600

Total Area 9600 9600



RADIO FREQUENCY EMISSIONS ANALYSIS REPORT EVALUATION OF HUMAN EXPOSURE POTENTIAL TO NON-IONIZING EMISSIONS

SPRINT Existing Facility

Site ID: CT03XC107

Stont Brook
2 Taugwonk Spur
Stonington, CT 06378

June 15, 2018

EBI Project Number: 6218004398

Site Compliance Summary	
Compliance Status:	COMPLIANT
Site total MPE% of FCC general population allowable limit:	7.46 %



June 15, 2018

SPRINT
Attn: RF Engineering Manager
1 International Boulevard, Suite 800
Mahwah, NJ 07495

Emissions Analysis for Site: **CT03XC107 – Stont Brook**

EBI Consulting was directed to analyze the proposed SPRINT facility located at **2 Taugwonk Spur, Stonington, CT**, for the purpose of determining whether the emissions from the Proposed SPRINT Antenna Installation located on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter ($\mu\text{W}/\text{cm}^2$). The number of $\mu\text{W}/\text{cm}^2$ calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits, therefore it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) – (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general population may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general population would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

General population exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter ($\mu\text{W}/\text{cm}^2$). The general population exposure limits for the 850 MHz Band is approximately $567 \mu\text{W}/\text{cm}^2$. The general population exposure limit for the 1900 MHz (PCS) and 2500 MHz (BRS) bands is $1000 \mu\text{W}/\text{cm}^2$. Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.



Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure. Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

CALCULATIONS

Calculations were done for the proposed SPRINT Wireless antenna facility located at **2 Taugwonk Spur, Stonington, CT**, using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. Since SPRINT is proposing highly focused directional panel antennas, which project most of the emitted energy out toward the horizon, all calculations were performed assuming a lobe representing the maximum gain of the antenna per the antenna manufacturer's supplied specifications, minus 10 dB, was focused at the base of the tower. For this report the sample point is the top of a 6-foot person standing at the base of the tower.

For all calculations, all equipment was calculated using the following assumptions:

- 1) 1 CDMA channels (850 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 20 Watts per Channel.
- 2) 2 LTE channels (850 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 50 Watts per Channel.
- 3) 5 CDMA channels (1900 MHz (PCS)) were considered for each sector of the proposed installation. These Channels have a transmit power of 16 Watts per Channel.
- 4) 2 LTE channels (1900 MHz (PCS)) were considered for each sector of the proposed installation. These Channels have a transmit power of 40 Watts per Channel.
- 5) 8 LTE channels (2500 MHz (BRS)) were considered for each sector of the proposed installation. These Channels have a transmit power of 20 Watts per Channel.



- 6) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 - Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.
- 7) For the following calculations, the sample point was the top of a 6-foot person standing at the base of the tower. The maximum gain of the antenna per the antenna manufacturer's supplied specifications minus 10 dB was used in this direction. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 8) The antennas used in this modeling are the **Commscope NNVV-65B-R4** and the **RFS APXVTM14-ALU-I20** for transmission in the 850 MHz, 1900 MHz (PCS) and 2500 MHz (BRS) frequency bands. This is based on feedback from the carrier with regards to anticipated antenna selection. Maximum gain values for all antennas are listed in the Inventory and Power Data table below. The maximum gain of the antenna per the antenna manufacturer's supplied specifications, minus 10 dB, was used for all calculations. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 9) The antenna mounting height centerlines of the proposed antennas are **145 feet** above ground level (AGL) for **Sector A**, **145 feet** above ground level (AGL) for **Sector B** and **145 feet** above ground level (AGL) for Sector C.
- 10) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.

All calculations were done with respect to uncontrolled / general population threshold limits.



SPRINT Site Inventory and Power Data by Antenna

Sector:	A	Sector:	B	Sector:	C
Antenna #:	1	Antenna #:	1	Antenna #:	1
Make / Model:	Commscope NNVV-65B-R4	Make / Model:	Commscope NNVV-65B-R4	Make / Model:	Commscope NNVV-65B-R4
Gain:	12.75 / 15.05 dBd	Gain:	12.75 / 15.05 dBd	Gain:	12.75 / 15.05 dBd
Height (AGL):	145 feet	Height (AGL):	145 feet	Height (AGL):	145 feet
Frequency Bands	850 MHz / 1900 MHz (PCS)	Frequency Bands	850 MHz / 1900 MHz (PCS)	Frequency Bands	850 MHz / 1900 MHz (PCS)
Channel Count	10	Channel Count	10	Channel Count	10
Total TX Power(W):	280 Watts	Total TX Power(W):	280 Watts	Total TX Power(W):	280 Watts
ERP (W):	7,378.61	ERP (W):	7,378.61	ERP (W):	7,378.61
Antenna A1 MPE%	1.69 %	Antenna B1 MPE%	1.69 %	Antenna C1 MPE%	1.69 %
Antenna #:	2	Antenna #:	2	Antenna #:	2
Make / Model:	RFS APXVTM14-ALU-I20	Make / Model:	RFS APXVTM14-ALU-I20	Make / Model:	RFS APXVTM14-ALU-I20
Gain:	15.9 dBd	Gain:	15.9 dBd	Gain:	15.9 dBd
Height (AGL):	145 feet	Height (AGL):	145 feet	Height (AGL):	145 feet
Frequency Bands	2500 MHz (BRS)	Frequency Bands	2500 MHz (BRS)	Frequency Bands	2500 MHz (BRS)
Channel Count	8	Channel Count	8	Channel Count	8
Total TX Power(W):	160 Watts	Total TX Power(W):	160 Watts	Total TX Power(W):	160 Watts
ERP (W):	6,224.72	ERP (W):	6,224.72	ERP (W):	6,224.72
Antenna A2 MPE%	1.16 %	Antenna B2 MPE%	1.16 %	Antenna C2 MPE%	1.16 %

Site Composite MPE%	
Carrier	MPE%
SPRINT – Max per sector	2.85 %
Nextel	0.17 %
Public Safety	0.04 %
T-Mobile	1.71 %
CL&P	2.44 %
MetroPCS	0.25 %
Site Total MPE %:	7.46 %

SPRINT Sector A Total:	2.85 %
SPRINT Sector B Total:	2.85 %
SPRINT Sector C Total:	2.85 %
Site Total:	7.46 %

SPRINT – Frequency Band / Technology (Per Sector)	# Channels	Watts ERP (Per Channel)	Height (feet)	Total Power Density ($\mu\text{W}/\text{cm}^2$)	Frequency (MHz)	Allowable MPE ($\mu\text{W}/\text{cm}^2$)	Calculated % MPE
Sprint 850 MHz CDMA	1	376.73	145	0.70	850 MHz	567	0.11%
Sprint 850 MHz LTE	2	941.82	145	3.50	850 MHz	567	0.62%
Sprint 1900 MHz (PCS) CDMA	5	511.82	145	4.76	1900 MHz (PCS)	1000	0.48%
Sprint 1900 MHz (PCS) LTE	2	1,279.56	145	4.76	1900 MHz (PCS)	1000	0.48%
Sprint 2500 MHz (BRS) LTE	8	778.09	145	11.58	2500 MHz (BRS)	1000	1.16%
							Total: 2.85%



Summary

All calculations performed for this analysis yielded results that were **within** the allowable limits for general population exposure to RF Emissions.

The anticipated maximum composite contributions from the SPRINT facility as well as the site composite emissions value with regards to compliance with FCC's allowable limits for general population exposure to RF Emissions are shown here:

SPRINT Sector	Power Density Value (%)
Sector A:	2.85 %
Sector B:	2.85 %
Sector C:	2.85 %
SPRINT Maximum Total (per sector):	2.85 %
Site Total:	7.46 %
Site Compliance Status:	COMPLIANT

The anticipated composite MPE value for this site assuming all carriers present is **7.46 %** of the allowable FCC established general population limit sampled at the ground level. This is based upon values listed in the Connecticut Siting Council database for existing carrier emissions.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.



Tower Engineering Solutions

Phone (972) 483-0607, Fax (972) 975-9615
8445 Freeport Parkway, Suite 375, Irving, Texas 75063

Structural Analysis Report

Existing 190 ft SUMMIT Monopole

Customer Name: SBA Communications Corp

Customer Site Number: CT00235-B

Customer Site Name: Stony Brook

Carrier Name: Sprint Nextel

Carrier Site ID / Name: CT03XC107 / Stony Brook


Site Location: Taugwonk Spur Road No. 2

Stonington, Connecticut

New London County

Latitude: 41.382249

Longitude: -71.903444



Analysis Result:

Max Structural Usage: 75.0% [Pass]

Max Foundation Usage: 74.0% [Pass]

Additional Usage Caused by Mount Modification: 4.10%

Report Prepared By: Mariana Franco

Introduction

The purpose of this report is to summarize the analysis results on the 190 ft SUMMIT Monopole to support the proposed antennas and transmission lines in addition to those currently installed. Any modification listed under Sources of Information was assumed completed and was included in this analysis.

Sources of Information

Tower Drawings	Original Drawings from Summit Manufacturing Inc, Job#: 3535 Dated: 05/14/1998 Monopole Tower Report by FDH Job#: 08-10050T Dated: 12/29/2008 Structural Analysis by FDH, Project#:15BEFV1400(R1) Dated:02/23/2015, Revised:06/17/2017
Foundation Drawing	Foundation Design by Paul J Ford and Company Project#: 29298-318 Dated: 05/06/1998
Geotechnical Report	Geotechnical Report by SAGE Environmental Inc, Project#: S598 Dated:04/22/98
Modification Drawings	N/A

Analysis Criteria

The rigorous analysis was performed in accordance with the requirements and stipulations of the ANSI/TIA/EIA 222-G. In accordance with this standard, the structure was analyzed using **TESPoles**, a proprietary analysis software. The program considers the structure as an elastic 3-D model with second-order effects and temperature effects incorporated in the analysis. The analysis was performed using multiple wind directions.

Wind Speed Used in the Analysis:	Ultimate Design Wind Speed V_{ult} = 140.0 mph (3-Sec. Gust)/ Nominal Design Wind Speed V_{asd} = 108.0 mph (3-Sec. Gust)
Wind Speed with Ice:	50 mph (3-Sec. Gust) with 3/4" radial ice concurrent
Operational Wind Speed:	60 mph + 0" Radial ice
Standard/Codes:	ANSI/TIA/EIA 222-G / 2012 IBC / 2016 Connecticut State Building Code
Exposure Category:	C
Structure Class:	II
Topographic Category:	1
Crest Height:	0 ft
Seismic Parameters:	$S_s = 0.159g$, $S_1 = 0.058g$

This structural analysis is based upon the tower being classified as a Structure Class II; however, if a different classification is required subsequent to the date hereof, the tower classification will be changed to meet such requirement and a new structural analysis will be run.

Existing Antennas, Mounts and Transmission Lines

The table below summarizes the antennas, mounts and transmission lines that were considered in the analysis as existing on the tower.

Items	Elevation (ft)	Qty.	Antenna Descriptions	Mount Type & Qty.	Transmission Lines	Owner
1	194.0	1	Telwave ANT150D3 Dipole	Direct Mount	(1) 7/8"	SPD
2	190.0	-	-	Low Profile Platform	-	Nextel
3	184.0	6	Kathrein 742 351	Low Profile Platform	(12) 1 5/8"	Metro PCS
4	172.5	3	Ericsson Air B2A B4P	(1) 13' Low Profile Platform w/Site Pro PRK-1245 Support Kit	(12) 1 5/8" (1) 1 5/8" Fiber	T-Mobile
5		3	Ericsson Air B4A B2P			
6		3	Commscope LNX-6515DS			
7		3	Ericsson KRY 112 144/1			
8		3	Ericsson S11B12			
9	158.5	1	RFS PD458-2N Omni	(2) Standoffs at 150	(3) 7/8"	CL&P
10	156.0	1	RFS 114202C Omni			
11	153.0	1	Telewave ANT450D6 Omni	Low Profile Platform at 158.5'	-	
-	145.0	9	Decibel/db908h90e-m	Low Profile Platform	(9) 1 5/8"	Sprint
17	129.5	1	RFS 220-7N Omni	(3) Standoffs at 120.0'	(3) 7/8"	CL&P
18	124.7	1	RFS/220-3AN -Omni			
19	123.0	1	Telewave ANT450D6 Omni			
-	46.5	1	GPS	(1) 4' Standoff	(1) 1/2" ¹	Sprint

1. GPS 1/2" line installed outside pole

Proposed Carrier's Final Configuration of Antennas, Mounts and Transmission Lines

Information pertaining to the proposed carrier's final configuration of antennas and transmission lines was provided by SBA Communications Corp. The proposed antennas and lines are listed below.

Items	Elevation (ft)	Qty.	Antenna Descriptions	Mount Type & Qty.	Transmission Lines	Owner
12	145.0	3	ALU 1900 MHz - RRUs	Low Profile Platform with (1) SitePro HRK14-U Handrail Kit, (1) SitePro PRK-SFS-H-L V-brace Kit, (1) SitePro PRK-1245L reinforcement kit, (6) SitePro SCX1-K Brackets, (3) Pipe2.0STD x 4' long corner braces and (3) Pipe2.0STD x 14' horizontal rails	(4) 1-1/4" Fiber	Sprint Nextel
13		6	ALU 800 MHz - RRUs			
14		3	ALU TD-RRH8x20-25 - RRUs			
15		3	RFS APXVTM14-C-I20 - Panel			
16		3	Commscope NNVV-65B-R4 - Panel			
20	46.5	1	GPS	(1) 4' Standoff	(1) 1/2" ¹	

1. GPS 1/2" line installed outside pole

All transmission lines are considered running inside of the pole shafts.

Analysis Results

The results of the structural analysis, performed for the wind and ice loading and antenna equipment as defined above, are summarized as the following:

	Pole shafts	Anchor Bolts	Base Plate
Max. Usage:	75.0%	74.3%	61.0%
Pass/Fail	Pass	Pass	Pass

Foundations

	Moment (Kip-Ft)	Shear (Kips)
Original Design Reactions	5800.0	43.0
Analysis Reactions	6470.9	50.3
Factored Reactions*	7830.0	58.1
% of Design Reactions	82.6%	86.7%

* Per section 15.5.1 of the TIA-222-G standard, factored reactions were obtained by multiplying a 1.35 factor to the original design reactions.

Two foundation design options were included in the referenced foundation design document. Since it is not known which option was installed, both designs were analyzed using the supplied documents and soils report and both were found adequate. Therefore, no modification to the foundation will be required.

Operational Condition (Rigidity):

Operational characteristics of the tower are found to be within the limits prescribed by ANSI/TIA/EIA 222-G for the installed antennas. The maximum twist/sway at the elevation of the proposed equipment is 1.1248 degrees under the operational wind speed as specified in the Analysis Criteria.

Conclusions

Based on the analysis results, the existing structure and its foundation were found to be adequate to safely support the existing and proposed equipment and meet the minimum requirements per the ANSI/TIA/EIA 222-G Standard under the design basic wind speed as specified in the Analysis Criteria.

Standard Conditions

1. This analysis was performed based on the information supplied to **(TES) Tower Engineering Solutions, LLC**. Verification of the information provided was not included in the Scope of Work for **TES**. The accuracy of the analysis is dependent on the accuracy of the information provided.
2. The analysis is based on the presumption that the tower members and components along with any existing reinforcement items have been correctly and properly designed, manufactured, installed and maintained.
3. All the existing structural members were assumed to be in good condition with no physical damage or deterioration associated with corrosion.
4. An initial tension of 10% of the break strength on all the existing guy wires was assumed in all the structural analyses of guyed towers unless different values were provided by the client. **TES** cannot take responsibility for the deviations in the analysis results because of differences in the initial tension forces of the existing guy wires.
5. Secondary component or connection secondary components, welds and bolts are assumed to be able to carry their intended original design loads. **TES** cannot take responsibility for verification of the adequacy on the connections, bolts and welds present in the structure.
6. The analyses will be performed based on the codes as specified by the client or based on the best knowledge of the engineering staff of **TES**. In the absence of information to the contrary, all work will be performed in accordance with the latest relevant revision of ANSI/TIA-222. If wind speed and/or ice loads are different from the minimum values recommended by the EIA/TIA-222 standard or other codes, **TES** should be notified in writing and the applicable minimum values provided by the client.
7. The configuration of the existing mounts, antennas, coax and other appurtenances were supplied by the customer for the current structural analysis. **TES** has not visited the tower site to verify the adequacy of the information provided. If there is any discrepancy found in the report regarding the existing conditions, **TES** should be notified immediately to evaluate the effect of the discrepancy on the analysis results.
8. The client will assume responsibility for rework associated with the differences in initially provided information, including tower and foundation information, existing and/or proposed equipment and transmission lines.
9. If a feasibility analysis was performed, final acceptance of changed conditions shall be based upon a rigorous structural analysis.

Usage Diagram - Max Ratio 74.97% at 0.0ft

Structure: CT00235-B-SBA
Site Name: Stony Brook
Height: 190.00 (ft)
Base Elev: 0.000 (ft)

Code: EIA/TIA-222-G
Exposure: C
G_h: 1.1

5/23/2018



Page: 1


Dead Load Factor: 1.20
Wind Load Factor: 1.60

Load Case : 1.2D + 1.6W 108 mph Wind



Iterations: 26

Copyright © 2018 by Tower Engineering Solutions, LLC. All rights reserved.



Structure: CT00235-B-SBA

Type: Tapered
Site Name: Stony Brook
Height: 190.00 (ft)
Base Elev: 0.00 (ft)

Base Shape: 18 Sided
Taper: 0.22003

5/23/2018

Page: 2



Shaft Properties


Seq	Length (ft)	Top (in)	Bottom (in)	Thick (in)	Joint Type	Taper	Grade (ksi)
1	19.50	58.39	62.68	0.500		0.22003	65
2	45.00	51.19	61.09	0.500	Slip	0.22003	65
3	50.00	42.55	53.55	0.438	Slip	0.22003	65
4	50.00	33.51	44.51	0.375	Slip	0.22003	65
5	50.00	24.00	35.00	0.250	Slip	0.22003	60

Discrete Appurtenances

Attach Elev (ft)	Force Elev (ft)	Qty	Description	Carrier
190.00	190.00	1	Low Profile Platform-flat	Nextel
190.00	195.00	1	ANT150D3	SPD
184.00	184.00	1	Low Profile Platform-flat	Metro PCS
184.00	184.00	6	742 351	Metro PCS
172.50	172.50	3	AIR B2A B4P	T-Mobile
172.50	172.50	3	AIR 32 B4A B2P	T-Mobile
172.50	172.50	3	LNX-6515DS	T-Mobile
172.50	172.50	3	KRY 112 144/1	T-Mobile
172.50	172.50	3	S11B12	T-Mobile
172.50	172.50	1	PRK-1245	T-Mobile
172.50	172.50	1	Low Profile Platform-flat	T-Mobile
158.50	158.50	1	Low Profile Platform-flat	CL&P
158.50	165.15	1	PD458-2N	CL&P
156.00	162.30	1	114202C	CL&P
153.00	156.00	1	ANT450D6-9	CL&P
150.00	150.00	2	3 ft Standoff	CL&P
145.00	145.00	1	Low Profile Platform-flat	Sprint Nextel
145.00	145.00	3	1900 MHz RRUs	Sprint Nextel
145.00	145.00	6	800 MHz RRUs	Sprint Nextel
145.00	145.00	3	TD-RRH8x20-25	Sprint Nextel
145.00	145.00	3	APXVTM14-C-I20	Sprint Nextel
145.00	145.00	3	NNVV-65B-R4	Sprint Nextel
145.00	145.00	1	HRK14	Sprint Nextel
145.00	145.00	1	PRK-1245 (kicker kit)	Sprint Nextel
145.00	145.00	1	(3) SFS-H-L (V-Braces)	Sprint Nextel
145.00	145.00	1	Horizontal Rail & SCX1-K	Sprint Nextel
129.50	139.00	1	220-7N Omni	CL&P
124.70	135.05	1	220-3AN	CL&P
123.00	126.00	1	ANT450D6-9	CL&P
120.00	120.00	3	3 ft Standoff	CL&P
46.50	46.50	1	3 ft Standoff	Sprint Nextel
46.50	46.50	1	GPS	Sprint Nextel

Linear Appurtenances

Elev From (ft)	Elev To (ft)	Placement	Description	Carrier
0.00	190.00	Inside	7/8" Coax	SPD
0.00	184.00	Inside	1 5/8" Coax	Metro PCS
0.00	172.50	Inside	1 5/8" Coax	T-Mobile
0.00	172.50	Inside	1 5/8" Fiber	T-Mobile
0.00	158.50	Inside	7/8" Coax	CL&P
0.00	145.00	Inside	1-1/4" Fiber	Sprint Nextel
0.00	120.00	Inside	7/8" Coax	CL&P
0.00	46.50	Outside	1/2" GPS Line	Sprint Nextel



Structure: CT00235-B-SBA

Type: Tapered
Site Name: Stony Brook
Height: 190.00 (ft)
Base Elev: 0.00 (ft)

Base Shape: 18 Sided
Taper: 0.22003

5/23/2018

Page: 3



Anchor Bolts

Qty	Specifications	Grade (ksi)	Grade
			Arrangement
24	2.25" 18J	75.0	Cluster

Base Plate

Thickness (in)	Specifications (in)	Grade (ksi)	Geometry
3.5000	71.0	50.0	Clipped

Reactions


Load Case	Moment (FT-Kips)	Shear (Kips)	Axial (Kips)
1.2D + 1.6W 108 mph Wind	6470.9	50.3	70.6
0.9D + 1.6W 108 mph Wind	6400.5	50.3	52.9
1.2D + 1.0Di + 1.0Wi 50 mph Wind	1653.6	12.7	98.4
1.2D + 1.0E	242.9	1.9	70.7
0.9D + 1.0E	240.1	1.9	53.0
1.0D + 1.0W 60 mph Wind	1241.2	9.7	58.9

Structure: CT00235-B-SBA - Coax Line Placement

Type: Monopole
Site Name: Stony Brook
Height: 190.00 (ft)

5/23/2018

Page: 4



Shaft Properties

Structure: CT00235-B-SBA

Code: EIA/TIA-222-G

5/23/2018

Site Name: Stony Brook

Exposure: C

Height: 190.00 (ft)

Crest Height: 0.00

Base Elev: 0.000 (ft)

Site Class: D - Stiff Soil

Gh: 1.1

Topography: 1

Struct Class: II

Page: 5



Tower Engineering Solutions

Sec. No.	Shape	Length (ft)	Thick (in)	Fy (ksi)	Joint Type	Overlap (in)	Weight (lb)
1	18	19.500	0.5000	65		0.00	6,322
2	18	45.000	0.5000	65	Slip	93.00	13,522
3	18	50.000	0.4375	65	Slip	81.00	11,249
4	18	50.000	0.3750	65	Slip	66.00	7,824
5	18	50.000	0.2500	60	Slip	54.00	3,949
Total Shaft Weight:							42,865

Bottom

Sec. No.	Dia (in)	Elev (ft)	Area (sqin)	Ix (in^4)	W/t Ratio	D/t Ratio	Dia (in)	Elev (ft)	Area (sqin)	Ix (in^4)	W/t Ratio	D/t Ratio	Taper
1	62.68	0.00	98.68	48202.16	20.69	125.36	58.39	19.50	91.87	38896.7	19.18	116.7	0.220026
2	61.09	11.75	96.16	44608.55	20.13	122.19	51.19	56.75	80.45	26119.8	16.64	102.3	0.220026
3	53.55	50.00	73.76	26290.75	20.17	122.41	42.55	100.00	58.48	13104.7	15.74	97.26	0.220026
4	44.51	94.50	52.53	12930.02	19.52	118.70	33.51	144.50	39.44	5471.21	14.35	89.36	0.220026
5	35.00	140.0	27.57	4207.25	23.28	140.01	24.00	190.00	18.84	1343.00	15.52	96.00	0.220026

Top

Load Summary

Structure: CT00235-B-SBA
Site Name: Stony Brook
Height: 190.00 (ft)
Base Elev: 0.000 (ft)
Gh: 1.1

Topography: 1

Code: EIA/TIA-222-G
Exposure: C
Crest Height: 0.00
Site Class: D - Stiff Soil
Struct Class: II

5/23/2018



Page: 6

Discrete Appurtenances

No.	Elev (ft)	Description	Qty	No Ice			Ice			Hor. Ecc. (ft)	Vert Ecc (ft)
				Weight (lb)	CaAa (sf)	CaAa Factor	Weight (lb)	CaAa (sf)	CaAa Factor		
1	190.00	Low Profile Platform-flat	1	1200.00	25.00	1.00	2272.18	46.444	1.00	0.00	0.00
2	190.00	ANT150D3	1	18.00	2.18	1.00	92.89	10.878	1.00	0.00	5.00
3	184.00	Low Profile Platform-flat	1	1200.00	25.00	1.00	2268.74	46.375	1.00	0.00	0.00
4	184.00	742 351	6	29.80	5.38	0.61	127.07	7.408	0.61	0.00	0.00
5	172.50	AIR B2A B4P	3	91.50	6.09	0.86	263.23	7.204	0.86	0.00	0.00
6	172.50	AIR 32 B4A B2P	3	105.80	6.51	0.87	293.25	7.707	0.87	0.00	0.00
7	172.50	LNX-6515DS	3	49.80	11.47	0.80	282.58	14.783	0.80	0.00	0.00
8	172.50	KRY 112 144/1	3	11.00	0.41	0.70	21.93	0.892	0.75	0.00	0.00
9	172.50	S11B12	3	51.00	2.83	0.70	121.58	3.511	0.75	0.00	0.00
10	172.50	PRK-1245	1	464.91	9.50	1.00	794.02	19.588	1.00	0.00	0.00
11	172.50	Low Profile Platform-flat	1	1200.00	25.00	1.00	2261.87	46.237	1.00	0.00	0.00
12	158.50	Low Profile Platform-flat	1	1200.00	25.00	1.00	2252.92	46.058	1.00	0.00	0.00
13	158.50	PD458-2N	1	22.00	2.66	1.00	94.09	7.416	1.00	0.00	6.65
14	156.00	114202C	1	24.00	2.14	1.00	145.62	6.709	1.00	0.00	6.30
15	153.00	ANT450D6-9	1	18.00	2.77	1.00	100.69	5.806	1.00	0.00	3.00
16	150.00	3 ft Standoff	2	40.00	2.63	1.00	120.28	8.599	1.00	0.00	0.00
17	145.00	Low Profile Platform-flat	1	1200.00	25.00	1.00	2243.59	45.872	1.00	0.00	0.00
18	145.00	1900 MHz RRUs	3	44.00	3.80	0.88	152.79	5.185	0.88	0.00	0.00
19	145.00	800 MHz RRUs	6	53.00	2.49	0.92	126.71	3.630	0.92	0.00	0.00
20	145.00	TD-RRH8x20-25	3	70.00	4.05	0.69	180.01	4.860	0.69	0.00	0.00
21	145.00	APXVTM14-C-I20	3	56.20	6.34	0.77	215.96	7.449	0.77	0.00	0.00
22	145.00	NNVV-65B-R4	3	77.40	12.27	0.74	361.99	13.721	0.74	0.00	0.00
23	145.00	HRK14	1	302.36	8.13	1.00	659.97	16.049	1.00	0.00	0.00
24	145.00	PRK-1245 (kicker kit)	1	464.91	9.50	1.00	788.36	19.414	1.00	0.00	0.00
25	145.00	(3) SFS-H-L (V-Braces)	1	230.00	9.70	1.00	550.03	19.823	1.00	0.00	0.00
26	145.00	Horizontal Rail & SCX1-K	1	302.36	9.97	1.00	659.97	19.681	1.00	0.00	0.00
27	129.50	220-7N Omni	1	22.00	5.32	1.00	256.07	12.034	1.00	0.00	9.50
28	124.70	220-3AN	1	24.00	5.69	1.00	166.04	12.888	1.00	0.00	10.35
29	123.00	ANT450D6-9	1	18.00	2.77	1.00	98.91	5.741	1.00	0.00	3.00
30	120.00	3 ft Standoff	3	40.00	2.63	1.00	118.51	8.467	1.00	0.00	0.00
31	46.50	3 ft Standoff	1	40.00	2.63	1.00	111.41	7.939	1.00	0.00	0.00
32	46.50	GPS	1	10.00	1.00	1.00	36.08	1.633	1.00	0.00	0.00

Totals: 63 10,327.44 23,652.19

Linear Appurtenances

Bottom Elev. (ft)	Top Elev. (ft)	Description	Exposed Width	Exposed
0.00	190.00	(1) 7/8" Coax	0.00	Inside
0.00	184.00	(12) 1 5/8" Coax	0.00	Inside
0.00	172.50	(12) 1 5/8" Coax	0.00	Inside
0.00	172.50	(1) 1 5/8" Fiber	0.00	Inside
0.00	158.50	(3) 7/8" Coax	0.00	Inside
0.00	145.00	(4) 1-1/4" Fiber	0.00	Inside
0.00	120.00	(3) 7/8" Coax	0.00	Inside
0.00	46.50	(1) 1/2" GPS Line	0.50	Outside

Discrete Appurtenances

No.	Elev (ft)	Description	No Ice				Ice				Hor. Ecc. (ft)	Vert Ecc (ft)
			Qty	Weight (lb)	CaAa (sf)	CaAa Factor	Weight (lb)	CaAa (sf)	CaAa Factor			

Increment Length: 5 (ft)

Elev (ft)	Description	Thick (in)	Dia (in)	Area (in ²)	I _x (in ⁴)	W/t Ratio	D/t Ratio	F _{py} (ksi)	S (in ³)	Weight (lb)
184.00		0.2500	25.320	19.892	1579.6	16.45	101.28	76.2	122.9	275.5
185.00		0.2500	25.100	19.718	1538.4	16.29	100.40	76.2	120.7	67.4
190.00		0.2500	24.000	18.845	1343.0	15.52	96.00	76.2	110.2	328.1
										42865.3

Wind Loading - Shaft

Structure: CT00235-B-SBA

Code: EIA/TIA-222-G

5/23/2018

Site Name: Stony Brook

Exposure: C

Height: 190.00 (ft)

Crest Height: 0.00

Base Elev: 0.000 (ft)

Site Class: D - Stiff Soil

G_h: 1.1

Topography: 1

Struct Class: II

Page: 11



172.50 Appurtenance(s)	1.00	1.42	40.268	44.30	303.25	0.650	0.000	2.50	5.950	3.87	274.1	0.0	225.8
175.00	1.00	1.42	40.391	44.43	297.71	0.650	0.000	2.50	5.834	3.79	269.5	0.0	221.3
180.00	1.00	1.43	40.631	44.69	286.56	0.650	0.000	5.00	11.318	7.36	526.1	0.0	429.3
184.00 Appurtenance(s)	1.00	1.44	40.819	44.90	277.58	0.650	0.000	4.00	8.719	5.67	407.2	0.0	330.6
185.00	1.00	1.44	40.866	44.95	275.32	0.650	0.000	1.00	2.133	1.39	99.7	0.0	80.9
190.00 Appurtenance(s)	1.00	1.45	41.096	45.21	264.00	0.650	0.000	5.00	10.387	6.75	488.3	0.0	393.7
		Totals:		190.00					26,803.4				51,438.3

Total Applied Force Summary

Structure: CT00235-B-SBA
Site Name: Stony Brook
Height: 190.00 (ft)
Base Elev: 0.000 (ft)
Gh: 1.1

Code: EIA/TIA-222-G
Exposure: C
Crest Height: 0.00
Site Class: D - Stiff Soil
Struct Class: II

5/23/2018



Page: 13

Load Case: 1.2D + 1.6W 108 mph Wind

Dead Load Factor 1.20
Wind Load Factor 1.60



Elev (ft)	Description	Lateral FX (-) (lb)	Axial FY (-) (lb)	Torsion MY (lb-ft)	Moment MZ (lb-ft)
0.00		0.00	0.00	0.00	0.00
5.00		725.09	2198.87	0.00	0.00
10.00		712.25	2163.23	0.00	0.00
11.75		246.26	748.71	0.00	0.00
15.00		460.75	2647.47	0.00	0.00
19.50		663.85	3616.01	0.00	0.00
20.00		73.47	210.83	0.00	0.00
25.00		762.23	2088.69	0.00	0.00
30.00		777.21	2053.05	0.00	0.00
35.00		787.52	2017.40	0.00	0.00
40.00		794.21	1981.76	0.00	0.00
45.00		798.00	1946.12	0.00	0.00
46.50	(2) attachments	433.10	636.88	0.00	0.00
50.00		557.83	1332.92	0.00	0.00
55.00		812.12	3364.12	0.00	0.00
56.75		282.12	1161.65	0.00	0.00
60.00		524.53	1075.56	0.00	0.00
65.00		806.27	1628.97	0.00	0.00
70.00		801.22	1597.78	0.00	0.00
75.00		794.95	1566.59	0.00	0.00
80.00		787.58	1535.41	0.00	0.00
85.00		779.22	1504.22	0.00	0.00
90.00		769.96	1473.03	0.00	0.00
94.50		683.97	1299.06	0.00	0.00
95.00		76.42	249.90	0.00	0.00
100.00		762.03	2467.15	0.00	0.00
105.00		750.58	1230.87	0.00	0.00
110.00		738.46	1204.13	0.00	0.00
115.00		725.72	1177.40	0.00	0.00
120.00	(3) attachments	1230.44	1294.67	0.00	0.00
123.00	(1) attachments	603.83	693.55	0.00	551.26
124.70	(1) attachments	618.54	405.30	0.00	3964.17
125.00		41.34	66.12	0.00	0.00
129.50	(1) attachments	976.37	1006.66	0.00	3422.71
130.00		67.50	107.58	0.00	0.00
135.00		669.18	1061.11	0.00	0.00
140.00		653.80	1034.37	0.00	0.00
144.50		583.14	1407.54	0.00	0.00
145.00	(23) attachments	8115.16	4346.29	0.00	0.00
150.00	(2) attachments	993.17	801.08	0.00	0.00
153.00	(1) attachments	562.46	436.09	0.00	576.61
155.00		243.32	272.76	0.00	0.00
156.00	(1) attachments	270.30	164.11	0.00	943.32
158.50	(2) attachments	2188.70	1801.56	0.00	993.78
160.00		177.07	196.15	0.00	0.00
165.00		580.25	642.25	0.00	0.00
170.00		562.54	624.43	0.00	0.00

Total Applied Force Summary

Structure: CT00235-B-SBA

Code: EIA/TIA-222-G

5/23/2018

Site Name: Stony Brook

Exposure: C

Height: 190.00 (ft)

Crest Height: 0.00

Base Elev: 0.000 (ft)

Site Class: D - Stiff Soil

Gh: 1.1

Topography: 1

Struct Class: II

Page: 14



Tower Engineering Solutions

172.50	(17) attachments	6519.95	3416.18	0.00	0.00
175.00		269.55	260.34	0.00	0.00
180.00		526.08	507.31	0.00	0.00
184.00	(7) attachments	3334.91	2047.57	0.00	0.00
185.00		99.73	81.50	0.00	0.00
190.00	(2) attachments	2455.09	1858.38	0.00	792.71
Totals:		50,229.36	70,710.70	0.00	11,244.56

Linear Appurtenance Segment Forces (Factored)

Structure: CT00235-B-SBA

Code: EIA/TIA-222-G

5/23/2018

Site Name: Stony Brook

Exposure: C

Height: 190.00 (ft)

Crest Height: 0.00

Base Elev: 0.000 (ft)

Site Class: D - Stiff Soil

Gh: 1.1

Topography: 1

Struct Class: II

Page: 15



Load Case: 1.2D + 1.6W 108 mph Wind

Dead Load Factor 1.20

Wind Load Factor 1.60



Top Elev (ft)	Description	Wind Exposed	Length (ft)	Ca	Exposed Width (in)	Area (sqft)	CaAa (sqft)	Ra	Cf Adjust Factor	qz (psf)	F X (lb)	Dead Load (lb)
5.00	1/2" GPS Line	Yes	5.00	0.000	0.50	0.21	0.00	0.008	0.000	24.112	0.00	0.96
10.00	1/2" GPS Line	Yes	5.00	0.000	0.50	0.21	0.00	0.008	0.000	24.112	0.00	0.96
11.75	1/2" GPS Line	Yes	1.75	0.000	0.50	0.07	0.00	0.008	0.000	24.112	0.00	0.34
15.00	1/2" GPS Line	Yes	3.25	0.000	0.50	0.14	0.00	0.008	0.000	24.112	0.00	0.62
19.50	1/2" GPS Line	Yes	4.50	0.000	0.50	0.19	0.00	0.008	0.000	25.448	0.00	0.86
20.00	1/2" GPS Line	Yes	0.50	0.000	0.50	0.02	0.00	0.008	0.000	25.584	0.00	0.10
25.00	1/2" GPS Line	Yes	5.00	0.000	0.50	0.21	0.00	0.008	0.000	26.814	0.00	0.96
30.00	1/2" GPS Line	Yes	5.00	0.000	0.50	0.21	0.00	0.009	0.000	27.863	0.00	0.96
35.00	1/2" GPS Line	Yes	5.00	0.000	0.50	0.21	0.00	0.009	0.000	28.782	0.00	0.96
40.00	1/2" GPS Line	Yes	5.00	0.000	0.50	0.21	0.00	0.009	0.000	29.603	0.00	0.96
45.00	1/2" GPS Line	Yes	5.00	0.000	0.50	0.21	0.00	0.009	0.000	30.346	0.00	0.96
46.50	1/2" GPS Line	Yes	1.50	0.000	0.50	0.06	0.00	0.009	0.000	30.557	0.00	0.29
Totals:										0.0	0.0	8.9

Calculated Forces

Structure: CT00235-B-SBA

Code: EIA/TIA-222-G

5/23/2018

Site Name: Stony Brook

Exposure: C

Height: 190.00 (ft)

Crest Height: 0.00

Base Elev: 0.000 (ft)

Site Class: D - Stiff Soil

Gh: 1.1

Topography: 1

Struct Class: II

Page: 17



175.00	-3.72	-6.90	0.00	-76.58	0.00	76.58	1448.54	724.27	1607.86	805.12	128.47	-6.669	0.000	0.098
180.00	-3.27	-6.32	0.00	-42.10	0.00	42.10	1404.63	702.31	1495.13	748.67	135.46	-6.712	0.000	0.059
184.00	-1.63	-2.76	0.00	-16.84	0.00	16.84	1364.22	682.11	1402.40	702.24	141.08	-6.731	0.000	0.025
185.00	-1.56	-2.66	0.00	-14.07	0.00	14.07	1352.25	676.13	1377.77	689.91	142.49	-6.734	0.000	0.022
190.00	0.00	-2.46	0.00	-0.79	0.00	0.79	1292.39	646.19	1257.90	629.89	149.53	-6.741	0.000	0.001

Wind Loading - Shaft

Structure: CT00235-B-SBA

Code: EIA/TIA-222-G

5/23/2018

Site Name: Stony Brook

Exposure: C

Height: 190.00 (ft)

Crest Height: 0.00

Base Elev: 0.000 (ft)

Site Class: D - Stiff Soil

G_h: 1.1

Topography: 1

Struct Class: II

Page: 19



172.50 Appurtenance(s)	1.00	1.42	40.268	44.30	303.25	0.650	0.000	2.50	5.950	3.87	274.1	0.0	169.3
175.00	1.00	1.42	40.391	44.43	297.71	0.650	0.000	2.50	5.834	3.79	269.5	0.0	166.0
180.00	1.00	1.43	40.631	44.69	286.56	0.650	0.000	5.00	11.318	7.36	526.1	0.0	322.0
184.00 Appurtenance(s)	1.00	1.44	40.819	44.90	277.58	0.650	0.000	4.00	8.719	5.67	407.2	0.0	248.0
185.00	1.00	1.44	40.866	44.95	275.32	0.650	0.000	1.00	2.133	1.39	99.7	0.0	60.7
190.00 Appurtenance(s)	1.00	1.45	41.096	45.21	264.00	0.650	0.000	5.00	10.387	6.75	488.3	0.0	295.2
		Totals:		190.00					26,803.4				38,578.7

Total Applied Force Summary

Structure: CT00235-B-SBA
Site Name: Stony Brook
Height: 190.00 (ft)
Base Elev: 0.000 (ft)
Gh: 1.1

Code: EIA/TIA-222-G
Exposure: C
Crest Height: 0.00
Site Class: D - Stiff Soil
Struct Class: II

5/23/2018



Page: 21

Load Case: 0.9D + 1.6W 108 mph Wind

Dead Load Factor 0.90
Wind Load Factor 1.60



Elev (ft)	Description	Lateral FX (-) (lb)	Axial FY (-) (lb)	Torsion MY (lb-ft)	Moment MZ (lb-ft)
0.00		0.00	0.00	0.00	0.00
5.00		725.09	1649.15	0.00	0.00
10.00		712.25	1622.42	0.00	0.00
11.75		246.26	561.53	0.00	0.00
15.00		460.75	1985.60	0.00	0.00
19.50		663.85	2712.00	0.00	0.00
20.00		73.47	158.12	0.00	0.00
25.00		762.23	1566.52	0.00	0.00
30.00		777.21	1539.79	0.00	0.00
35.00		787.52	1513.05	0.00	0.00
40.00		794.21	1486.32	0.00	0.00
45.00		798.00	1459.59	0.00	0.00
46.50	(2) attachments	433.10	477.66	0.00	0.00
50.00		557.83	999.69	0.00	0.00
55.00		812.12	2523.09	0.00	0.00
56.75		282.12	871.24	0.00	0.00
60.00		524.53	806.67	0.00	0.00
65.00		806.27	1221.73	0.00	0.00
70.00		801.22	1198.34	0.00	0.00
75.00		794.95	1174.95	0.00	0.00
80.00		787.58	1151.55	0.00	0.00
85.00		779.22	1128.16	0.00	0.00
90.00		769.96	1104.77	0.00	0.00
94.50		683.97	974.29	0.00	0.00
95.00		76.42	187.43	0.00	0.00
100.00		762.03	1850.37	0.00	0.00
105.00		750.58	923.15	0.00	0.00
110.00		738.46	903.10	0.00	0.00
115.00		725.72	883.05	0.00	0.00
120.00	(3) attachments	1230.44	971.00	0.00	0.00
123.00	(1) attachments	603.83	520.16	0.00	551.26
124.70	(1) attachments	618.54	303.98	0.00	3964.17
125.00		41.34	49.59	0.00	0.00
129.50	(1) attachments	976.37	754.99	0.00	3422.71
130.00		67.50	80.69	0.00	0.00
135.00		669.18	795.83	0.00	0.00
140.00		653.80	775.78	0.00	0.00
144.50		583.14	1055.65	0.00	0.00
145.00	(23) attachments	8115.16	3259.72	0.00	0.00
150.00	(2) attachments	993.17	600.81	0.00	0.00
153.00	(1) attachments	562.46	327.07	0.00	576.61
155.00		243.32	204.57	0.00	0.00
156.00	(1) attachments	270.30	123.08	0.00	943.32
158.50	(2) attachments	2188.70	1351.17	0.00	993.78
160.00		177.07	147.11	0.00	0.00
165.00		580.25	481.69	0.00	0.00
170.00		562.54	468.32	0.00	0.00

Total Applied Force Summary

Structure: CT00235-B-SBA

Code: EIA/TIA-222-G

5/23/2018

Site Name: Stony Brook

Exposure: C

Height: 190.00 (ft)

Crest Height: 0.00

Base Elev: 0.000 (ft)

Site Class: D - Stiff Soil

Gh: 1.1

Topography: 1

Struct Class: II

Page: 22



Tower Engineering Solutions

172.50	(17) attachments	6519.95	2562.14	0.00	0.00
175.00		269.55	195.25	0.00	0.00
180.00		526.08	380.48	0.00	0.00
184.00	(7) attachments	3334.91	1535.68	0.00	0.00
185.00		99.73	61.12	0.00	0.00
190.00	(2) attachments	2455.09	1393.79	0.00	792.71
Totals:		50,229.36	53,033.03	0.00	11,244.56

Linear Appurtenance Segment Forces (Factored)

Structure: CT00235-B-SBA

Code: EIA/TIA-222-G

5/23/2018

Site Name: Stony Brook

Exposure: C

Height: 190.00 (ft)

Crest Height: 0.00

Base Elev: 0.000 (ft)

Site Class: D - Stiff Soil

Gh: 1.1

Topography: 1

Struct Class: II

Page: 23



Load Case: 0.9D + 1.6W 108 mph Wind

Dead Load Factor 0.90

Wind Load Factor 1.60



Top Elev (ft)	Description	Wind Exposed	Length (ft)	Ca	Exposed Width (in)	Area (sqft)	CaAa (sqft)	Ra	Cf Adjust Factor	qz (psf)	F X (lb)	Dead Load (lb)
5.00	1/2" GPS Line	Yes	5.00	0.000	0.50	0.21	0.00	0.008	0.000	24.112	0.00	0.72
10.00	1/2" GPS Line	Yes	5.00	0.000	0.50	0.21	0.00	0.008	0.000	24.112	0.00	0.72
11.75	1/2" GPS Line	Yes	1.75	0.000	0.50	0.07	0.00	0.008	0.000	24.112	0.00	0.25
15.00	1/2" GPS Line	Yes	3.25	0.000	0.50	0.14	0.00	0.008	0.000	24.112	0.00	0.47
19.50	1/2" GPS Line	Yes	4.50	0.000	0.50	0.19	0.00	0.008	0.000	25.448	0.00	0.65
20.00	1/2" GPS Line	Yes	0.50	0.000	0.50	0.02	0.00	0.008	0.000	25.584	0.00	0.07
25.00	1/2" GPS Line	Yes	5.00	0.000	0.50	0.21	0.00	0.008	0.000	26.814	0.00	0.72
30.00	1/2" GPS Line	Yes	5.00	0.000	0.50	0.21	0.00	0.009	0.000	27.863	0.00	0.72
35.00	1/2" GPS Line	Yes	5.00	0.000	0.50	0.21	0.00	0.009	0.000	28.782	0.00	0.72
40.00	1/2" GPS Line	Yes	5.00	0.000	0.50	0.21	0.00	0.009	0.000	29.603	0.00	0.72
45.00	1/2" GPS Line	Yes	5.00	0.000	0.50	0.21	0.00	0.009	0.000	30.346	0.00	0.72
46.50	1/2" GPS Line	Yes	1.50	0.000	0.50	0.06	0.00	0.009	0.000	30.557	0.00	0.22
Totals:										0.0	0.0	6.7

Calculated Forces

Structure: CT00235-B-SBA

Code: EIA/TIA-222-G

5/23/2018

Site Name: Stony Brook

Exposure: C

Height: 190.00 (ft)

Crest Height: 0.00

Base Elev: 0.000 (ft)

Site Class: D - Stiff Soil

Gh: 1.1

Topography: 1

Struct Class: II

Page: 25



175.00	-2.61	-6.76	0.00	-75.08	0.00	75.08	1448.54	724.27	1607.86	805.12	126.62	-6.566	0.000	0.095
180.00	-2.29	-6.20	0.00	-41.28	0.00	41.28	1404.63	702.31	1495.13	748.67	133.51	-6.608	0.000	0.057
184.00	-1.15	-2.71	0.00	-16.50	0.00	16.50	1364.22	682.11	1402.40	702.24	139.04	-6.626	0.000	0.024
185.00	-1.10	-2.60	0.00	-13.79	0.00	13.79	1352.25	676.13	1377.77	689.91	140.43	-6.629	0.000	0.021
190.00	0.00	-2.46	0.00	-0.79	0.00	0.79	1292.39	646.19	1257.90	629.89	147.36	-6.636	0.000	0.001

Wind Loading - Shaft

Structure: CT00235-B-SBA

Code: EIA/TIA-222-G

5/23/2018

Site Name: Stony Brook

Exposure: C

Height: 190.00 (ft)

Crest Height: 0.00

Base Elev: 0.000 (ft)

Site Class: D - Stiff Soil

G_h: 1.1

Topography: 1

Struct Class: II

Page: 27



172.50 Appurtenance(s)	1.00	1.42	8.631	9.49	0.00	1.200	1.770	2.50	6.687	8.02	76.2	164.1	389.9
175.00	1.00	1.42	8.657	9.52	0.00	1.200	1.772	2.50	6.572	7.89	75.1	161.3	382.6
180.00	1.00	1.43	8.709	9.58	0.00	1.200	1.777	5.00	12.799	15.36	147.1	311.3	740.6
184.00 Appurtenance(s)	1.00	1.44	8.749	9.62	0.00	1.200	1.781	4.00	9.907	11.89	114.4	241.8	572.4
185.00	1.00	1.44	8.759	9.63	0.00	1.200	1.782	1.00	2.430	2.92	28.1	60.0	140.9
190.00 Appurtenance(s)	1.00	1.45	8.808	9.69	0.00	1.200	1.787	5.00	11.876	14.25	138.1	288.5	682.1
		Totals:		190.00						7,139.4			68,616.2

Total Applied Force Summary

Structure: CT00235-B-SBA
Site Name: Stony Brook
Height: 190.00 (ft)
Base Elev: 0.000 (ft)
Gh: 1.1

Code: EIA/TIA-222-G
Exposure: C
Crest Height: 0.00
Site Class: D - Stiff Soil
Struct Class: II


5/23/2018



Page: 29

Load Case: 1.2D + 1.0Di + 1.0Wi 50 mph Wind

Dead Load Factor 1.20
Wind Load Factor 1.00



Elev (ft)	Description	Lateral FX (-) (lb)	Axial FY (-) (lb)	Torsion MY (lb-ft)	Moment MZ (lb-ft)
0.00		0.00	0.00	0.00	0.00
5.00		186.38	2700.43	0.00	0.00
10.00		183.71	2693.06	0.00	0.00
11.75		63.59	936.15	0.00	0.00
15.00		119.07	3006.15	0.00	0.00
19.50		171.86	4118.47	0.00	0.00
20.00		19.03	266.71	0.00	0.00
25.00		197.73	2650.61	0.00	0.00
30.00		201.97	2615.54	0.00	0.00
35.00		205.00	2578.66	0.00	0.00
40.00		207.09	2540.40	0.00	0.00
45.00		208.42	2501.05	0.00	0.00
46.50	(2) attachments	131.15	869.46	0.00	0.00
50.00		145.96	1704.81	0.00	0.00
55.00		212.63	3898.40	0.00	0.00
56.75		73.93	1347.92	0.00	0.00
60.00		137.59	1418.83	0.00	0.00
65.00		211.81	2150.39	0.00	0.00
70.00		210.85	2112.05	0.00	0.00
75.00		209.57	2073.30	0.00	0.00
80.00		208.01	2034.20	0.00	0.00
85.00		206.20	1994.78	0.00	0.00
90.00		204.15	1955.07	0.00	0.00
94.50		181.70	1725.79	0.00	0.00
95.00		20.30	298.01	0.00	0.00
100.00		202.64	2939.25	0.00	0.00
105.00		200.03	1693.75	0.00	0.00
110.00		197.24	1657.59	0.00	0.00
115.00		194.29	1621.24	0.00	0.00
120.00	(3) attachments	414.61	1895.24	0.00	0.00
123.00	(1) attachments	163.98	1007.71	0.00	153.04
124.70	(1) attachments	179.63	650.23	0.00	1202.84
125.00		11.14	91.57	0.00	0.00
129.50	(1) attachments	275.37	1614.21	0.00	1037.14
130.00		18.23	148.98	0.00	0.00
135.00		181.07	1464.79	0.00	0.00
140.00		177.44	1427.65	0.00	0.00
144.50		158.53	1757.85	0.00	0.00
145.00	(23) attachments	1751.26	8250.19	0.00	0.00
150.00	(2) attachments	330.72	1293.17	0.00	0.00
153.00	(1) attachments	155.25	717.84	0.00	161.91
155.00		66.68	419.47	0.00	0.00
156.00	(1) attachments	95.96	358.65	0.00	396.18
158.50	(2) attachments	567.43	2785.64	0.00	371.13
160.00		48.71	302.91	0.00	0.00
165.00		160.07	987.14	0.00	0.00
170.00		155.85	958.22	0.00	0.00

Total Applied Force Summary

Structure: CT00235-B-SBA

Code: EIA/TIA-222-G

5/23/2018

Site Name: Stony Brook

Exposure: C

Height: 190.00 (ft)

Crest Height: 0.00

Base Elev: 0.000 (ft)

Site Class: D - Stiff Soil

Gh: 1.1

Topography: 1

Struct Class: II

Page: 30



172.50	(17) attachments	1339.78	6341.62	0.00	0.00
175.00		75.10	421.64	0.00	0.00
180.00		147.13	818.62	0.00	0.00
184.00	(7) attachments	769.46	3477.88	0.00	0.00
185.00		28.10	141.48	0.00	0.00
190.00	(2) attachments	694.06	2973.02	0.00	529.88
Totals:		12,677.45	98,407.76	0.00	3,852.12

Linear Appurtenance Segment Forces (Factored)

Structure: CT00235-B-SBA

Code: EIA/TIA-222-G

5/23/2018

Site Name: Stony Brook

Exposure: C

Height: 190.00 (ft)

Crest Height: 0.00

Base Elev: 0.000 (ft)

Site Class: D - Stiff Soil

Gh: 1.1

Topography: 1

Struct Class: II

Page: 31



Load Case: 1.2D + 1.0Di + 1.0Wi 50 mph Wind

Dead Load Factor 1.20

Wind Load Factor 1.00



Iterations

25

Top Elev (ft)	Description	Wind Exposed	Length (ft)	Ca	Exposed Width (in)	Area (sqft)	CaAa (sqft)	Ra	Cf Adjust Factor	qz (psf)	F X (lb)	Dead Load (lb)
5.00	1/2" GPS Line	Yes	5.00	0.000	0.50	1.24	0.00	0.008	0.000	5.168	0.00	13.70
10.00	1/2" GPS Line	Yes	5.00	0.000	0.50	1.32	0.00	0.008	0.000	5.168	0.00	15.33
11.75	1/2" GPS Line	Yes	1.75	0.000	0.50	0.47	0.00	0.008	0.000	5.168	0.00	5.51
15.00	1/2" GPS Line	Yes	3.25	0.000	0.50	0.89	0.00	0.008	0.000	5.168	0.00	10.65
19.50	1/2" GPS Line	Yes	4.50	0.000	0.50	1.25	0.00	0.008	0.000	5.454	0.00	15.39
20.00	1/2" GPS Line	Yes	0.50	0.000	0.50	0.14	0.00	0.008	0.000	5.483	0.00	1.72
25.00	1/2" GPS Line	Yes	5.00	0.000	0.50	1.42	0.00	0.008	0.000	5.747	0.00	17.83
30.00	1/2" GPS Line	Yes	5.00	0.000	0.50	1.45	0.00	0.009	0.000	5.972	0.00	18.38
35.00	1/2" GPS Line	Yes	5.00	0.000	0.50	1.47	0.00	0.009	0.000	6.169	0.00	18.86
40.00	1/2" GPS Line	Yes	5.00	0.000	0.50	1.48	0.00	0.009	0.000	6.345	0.00	19.29
45.00	1/2" GPS Line	Yes	5.00	0.000	0.50	1.50	0.00	0.009	0.000	6.504	0.00	19.67
46.50	1/2" GPS Line	Yes	1.50	0.000	0.50	0.45	0.00	0.009	0.000	6.549	0.00	5.93
Totals:										0.0	162.2	

Calculated Forces

Structure: CT00235-B-SBA

Code: EIA/TIA-222-G

5/23/2018

Site Name: Stony Brook

Exposure: C

Height: 190.00 (ft)

Crest Height: 0.00

Base Elev: 0.000 (ft)

Site Class: D - Stiff Soil

Gh: 1.1

Topography: 1

Struct Class: II

Page: 33



175.00	-7.36	-1.86	0.00	-21.32	0.00	21.32	1448.54	724.27	1607.86	805.12	32.95	-1.711	0.000	0.032
180.00	-6.54	-1.69	0.00	-12.02	0.00	12.02	1404.63	702.31	1495.13	748.67	34.75	-1.723	0.000	0.021
184.00	-3.09	-0.82	0.00	-5.26	0.00	5.26	1364.22	682.11	1402.40	702.24	36.19	-1.729	0.000	0.010
185.00	-2.95	-0.78	0.00	-4.45	0.00	4.45	1352.25	676.13	1377.77	689.91	36.56	-1.730	0.000	0.009
190.00	0.00	-0.69	0.00	-0.53	0.00	0.53	1292.39	646.19	1257.90	629.89	38.37	-1.732	0.000	0.001

Seismic Segment Forces (Factored)

Structure: CT00235-B-SBA
Site Name: Stony Brook
Height: 190.00 (ft)
Base Elev: 0.000 (ft)
Gh: 1.1

Code: EIA/TIA-222-G
Exposure: C
Crest Height: 0.00
Site Class: D - Stiff Soil
Struct Class: II

5/23/2018



Topography: 1

Page: 34

Load Case: 1.2D + 1.0E



Gust Response Factor	1.10		Sds	0.17	Iterations	23	
Dead Load Factor	1.20	Seismic Load Factor	1.00	Sd1	0.09	Ss	0.16
Wind Load Factor	0.00	Structure Frequency	0.30	SA	0.03	S1	0.06

Top Elev (ft)	Description	Wz (lb)	Lateral Fs (lb)			R: 1.50
			a	b	c	
0.00		0.00	0.00	0.00	0.00	0.00
5.00		1664.0	0.00	0.03	0.01	25.12
10.00		1634.3	0.01	0.05	0.03	36.89
11.75	Bot - Section 2	564.99	0.01	0.05	0.03	13.72
15.00		2096.7	0.01	0.06	0.03	55.96
19.50	Top - Section 1	2861.8	0.02	0.06	0.04	82.58
20.00		158.85	0.02	0.06	0.04	4.61
25.00		1572.2	0.03	0.07	0.04	47.83
30.00		1542.4	0.05	0.07	0.04	48.30
35.00		1512.7	0.06	0.07	0.04	48.39
40.00		1483.0	0.08	0.07	0.04	48.36
45.00		1453.3	0.11	0.07	0.04	48.30
46.50	Appurtenance(s)	480.22	0.11	0.07	0.04	16.05
50.00	Bot - Section 3	993.46	0.13	0.07	0.03	33.63
55.00		2635.8	0.16	0.07	0.03	90.61
56.75	Top - Section 2	909.39	0.17	0.07	0.03	31.38
60.00		787.37	0.19	0.06	0.02	27.28
65.00		1189.9	0.22	0.06	0.02	40.94
70.00		1163.9	0.26	0.05	0.02	38.82
75.00		1137.9	0.29	0.05	0.01	35.40
80.00		1111.9	0.34	0.04	0.01	30.29
85.00		1085.9	0.38	0.02	0.01	23.26
90.00		1059.9	0.42	0.01	0.01	14.32
94.50	Bot - Section 4	931.73	0.47	0.00	0.01	4.52
95.00		191.49	0.47	-0.01	0.01	0.73
100.00	Top - Section 3	1888.3	0.52	-0.02	0.01	-12.79
105.00		858.14	0.58	-0.04	0.01	-14.64
110.00		835.86	0.63	-0.06	0.02	-21.59
115.00		813.59	0.69	-0.08	0.03	-26.19
120.00	Appurtenance(s)	911.31	0.75	-0.10	0.04	-32.54
123.00	Appurtenance(s)	482.09	0.79	-0.11	0.05	-17.55
124.70	Appurtenance(s)	283.43	0.81	-0.11	0.06	-10.29
125.00		45.51	0.82	-0.11	0.06	-1.65
129.50	Appurtenance(s)	695.08	0.88	-0.12	0.08	-23.82
130.00		73.67	0.88	-0.12	0.08	-2.50
135.00		724.48	0.95	-0.12	0.11	-20.78
140.00	Bot - Section 5	702.20	1.03	-0.10	0.14	-14.53
144.50	Top - Section 4	1029.1	1.09	-0.07	0.18	-11.50
145.00	Appurtenance(s)	3605.9	1.10	-0.07	0.19	-35.97
150.00	Appurtenance(s)	526.87	1.18	-0.02	0.24	1.82
153.00	Appurtenance(s)	278.99	1.23	0.03	0.27	3.58
155.00		171.02	1.26	0.07	0.30	3.35
156.00	Appurtenance(s)	108.62	1.27	0.09	0.31	2.52
158.50	Appurtenance(s)	1430.9	1.32	0.14	0.35	46.59
160.00		123.59	1.34	0.18	0.37	4.76
165.00		402.31	1.43	0.33	0.46	24.23

Seismic Segment Forces (Factored)

Structure: CT00235-B-SBA

Code: EIA/TIA-222-G

5/23/2018

Site Name: Stony Brook

Exposure: C

Height: 190.00 (ft)

Crest Height: 0.00

Base Elev: 0.000 (ft)

Site Class: D - Stiff Soil

G_h: 1.1

Topography: 1

Struct Class: II

Page: 35



170.00		387.46	1.51	0.53	0.56	32.85
172.50	Appurtenance(s)	2780.3	1.56	0.65	0.61	272.83
175.00		184.45	1.60	0.79	0.67	20.70
180.00		357.76	1.70	1.11	0.81	51.02
184.00	Appurtenance(s)	1654.3	1.77	1.42	0.93	279.72
185.00		67.39	1.79	1.50	0.96	11.86
190.00	Appurtenance(s)	1546.0	1.89	1.98	1.14	328.51
Totals:		53,192.7			1,685.3	
						Total Wind: 50,229.4

Seismic Base Shear is Less Than 50% of Wind Force - An Analysis is NOT Required

Calculated Forces

Structure: CT00235-B-SBA

Code: EIA/TIA-222-G

5/23/2018

Site Name: Stony Brook

Exposure: C

Height: 190.00 (ft)

Crest Height: 0.00

Base Elev: 0.000 (ft)

Site Class: D - Stiff Soil

Gh: 1.1

Topography: 1

Struct Class: II

Page: 37



172.50	-4.75	-0.72	0.00	-9.89	0.00	9.89	1470.02	735.01	1665.18	833.83	5.22	-0.32	0.015
175.00	-4.49	-0.70	0.00	-8.10	0.00	8.10	1448.54	724.27	1607.86	805.12	5.38	-0.32	0.013
180.00	-3.98	-0.64	0.00	-4.62	0.00	4.62	1404.63	702.31	1495.13	748.67	5.72	-0.33	0.009
184.00	-1.94	-0.35	0.00	-2.05	0.00	2.05	1364.22	682.11	1402.40	702.24	6.00	-0.33	0.004
185.00	-1.86	-0.34	0.00	-1.70	0.00	1.70	1352.25	676.13	1377.77	689.91	6.06	-0.33	0.004
190.00	0.00	-0.33	0.00	0.00	0.00	0.00	1292.39	646.19	1257.90	629.89	6.41	-0.33	0.000

Seismic Segment Forces (Factored)

Structure: CT00235-B-SBA
Site Name: Stony Brook
Height: 190.00 (ft)
Base Elev: 0.000 (ft)
Gh: 1.1

Code: EIA/TIA-222-G
Exposure: C
Crest Height: 0.00
Site Class: D - Stiff Soil
Struct Class: II

5/23/2018



Topography: 1

Page: 38

Load Case: 0.9D + 1.0E



Gust Response Factor	1.10	Sds	0.17	Iterations	23
Dead Load Factor	0.90	Seismic Load Factor	1.00	Sd1	0.09
Wind Load Factor	0.00	Structure Frequency	0.30	SA	0.03
				Seismic Importance Factor	1.00

Top Elev (ft)	Description	Wz (lb)	a	b	c	Lateral Fs (lb)	R: 1.50
0.00		0.00	0.00	0.00	0.00	0.00	
5.00		1664.0	0.00	0.03	0.01	25.12	
10.00		1634.3	0.01	0.05	0.03	36.89	
11.75	Bot - Section 2	564.99	0.01	0.05	0.03	13.72	
15.00		2096.7	0.01	0.06	0.03	55.96	
19.50	Top - Section 1	2861.8	0.02	0.06	0.04	82.58	
20.00		158.85	0.02	0.06	0.04	4.61	
25.00		1572.2	0.03	0.07	0.04	47.83	
30.00		1542.4	0.05	0.07	0.04	48.30	
35.00		1512.7	0.06	0.07	0.04	48.39	
40.00		1483.0	0.08	0.07	0.04	48.36	
45.00		1453.3	0.11	0.07	0.04	48.30	
46.50	Appurtenance(s)	480.22	0.11	0.07	0.04	16.05	
50.00	Bot - Section 3	993.46	0.13	0.07	0.03	33.63	
55.00		2635.8	0.16	0.07	0.03	90.61	
56.75	Top - Section 2	909.39	0.17	0.07	0.03	31.38	
60.00		787.37	0.19	0.06	0.02	27.28	
65.00		1189.9	0.22	0.06	0.02	40.94	
70.00		1163.9	0.26	0.05	0.02	38.82	
75.00		1137.9	0.29	0.05	0.01	35.40	
80.00		1111.9	0.34	0.04	0.01	30.29	
85.00		1085.9	0.38	0.02	0.01	23.26	
90.00		1059.9	0.42	0.01	0.01	14.32	
94.50	Bot - Section 4	931.73	0.47	0.00	0.01	4.52	
95.00		191.49	0.47	-0.01	0.01	0.73	
100.00	Top - Section 3	1888.3	0.52	-0.02	0.01	-12.79	
105.00		858.14	0.58	-0.04	0.01	-14.64	
110.00		835.86	0.63	-0.06	0.02	-21.59	
115.00		813.59	0.69	-0.08	0.03	-26.19	
120.00	Appurtenance(s)	911.31	0.75	-0.10	0.04	-32.54	
123.00	Appurtenance(s)	482.09	0.79	-0.11	0.05	-17.55	
124.70	Appurtenance(s)	283.43	0.81	-0.11	0.06	-10.29	
125.00		45.51	0.82	-0.11	0.06	-1.65	
129.50	Appurtenance(s)	695.08	0.88	-0.12	0.08	-23.82	
130.00		73.67	0.88	-0.12	0.08	-2.50	
135.00		724.48	0.95	-0.12	0.11	-20.78	
140.00	Bot - Section 5	702.20	1.03	-0.10	0.14	-14.53	
144.50	Top - Section 4	1029.1	1.09	-0.07	0.18	-11.50	
145.00	Appurtenance(s)	3605.9	1.10	-0.07	0.19	-35.97	
150.00	Appurtenance(s)	526.87	1.18	-0.02	0.24	1.82	
153.00	Appurtenance(s)	278.99	1.23	0.03	0.27	3.58	
155.00		171.02	1.26	0.07	0.30	3.35	
156.00	Appurtenance(s)	108.62	1.27	0.09	0.31	2.52	
158.50	Appurtenance(s)	1430.9	1.32	0.14	0.35	46.59	
160.00		123.59	1.34	0.18	0.37	4.76	
165.00		402.31	1.43	0.33	0.46	24.23	

Seismic Segment Forces (Factored)

Structure: CT00235-B-SBA

Code: EIA/TIA-222-G

5/23/2018

Site Name: Stony Brook

Exposure: C

Height: 190.00 (ft)

Crest Height: 0.00

Base Elev: 0.000 (ft)

Site Class: D - Stiff Soil

G_h: 1.1

Topography: 1

Struct Class: II

Page: 39



170.00		387.46	1.51	0.53	0.56	32.85
172.50	Appurtenance(s)	2780.3	1.56	0.65	0.61	272.83
175.00		184.45	1.60	0.79	0.67	20.70
180.00		357.76	1.70	1.11	0.81	51.02
184.00	Appurtenance(s)	1654.3	1.77	1.42	0.93	279.72
185.00		67.39	1.79	1.50	0.96	11.86
190.00	Appurtenance(s)	1546.0	1.89	1.98	1.14	328.51
Totals:		53,192.7			1,685.3	
						Total Wind: 50,229.4

Seismic Base Shear is Less Than 50% of Wind Force - An Analysis is NOT Required

Calculated Forces

Structure: CT00235-B-SBA

Code: EIA/TIA-222-G

5/23/2018

Site Name: Stony Brook

Exposure: C

Height: 190.00 (ft)

Crest Height: 0.00

Base Elev: 0.000 (ft)

Site Class: D - Stiff Soil

Gh: 1.1

Topography: 1

Struct Class: II

Page: 41



172.50	-3.56	-0.71	0.00	-9.80	0.00	9.80	1470.02	735.01	1665.18	833.83	5.14	-0.31	0.014
175.00	-3.37	-0.69	0.00	-8.03	0.00	8.03	1448.54	724.27	1607.86	805.12	5.31	-0.32	0.012
180.00	-2.99	-0.64	0.00	-4.58	0.00	4.58	1404.63	702.31	1495.13	748.67	5.64	-0.32	0.008
184.00	-1.45	-0.35	0.00	-2.03	0.00	2.03	1364.22	682.11	1402.40	702.24	5.91	-0.32	0.004
185.00	-1.39	-0.34	0.00	-1.68	0.00	1.68	1352.25	676.13	1377.77	689.91	5.98	-0.32	0.003
190.00	0.00	-0.33	0.00	0.00	0.00	0.00	1292.39	646.19	1257.90	629.89	6.32	-0.32	0.000

Wind Loading - Shaft

Structure: CT00235-B-SBA

Code: EIA/TIA-222-G

5/23/2018

Site Name: Stony Brook

Exposure: C

Height: 190.00 (ft)

Crest Height: 0.00

Base Elev: 0.000 (ft)

Site Class: D - Stiff Soil

G_h: 1.1

Topography: 1

Struct Class: II

Page: 43



172.50 Appurtenance(s)	1.00	1.42	12.429	13.67	168.47	0.650	0.000	2.50	5.950	3.87	52.9	0.0	188.2
175.00	1.00	1.42	12.466	13.71	165.39	0.650	0.000	2.50	5.834	3.79	52.0	0.0	184.4
180.00	1.00	1.43	12.540	13.79	159.20	0.650	0.000	5.00	11.318	7.36	101.5	0.0	357.8
184.00 Appurtenance(s)	1.00	1.44	12.599	13.86	154.21	0.650	0.000	4.00	8.719	5.67	78.5	0.0	275.5
185.00	1.00	1.44	12.613	13.87	152.96	0.650	0.000	1.00	2.133	1.39	19.2	0.0	67.4
190.00 Appurtenance(s)	1.00	1.45	12.684	13.95	146.66	0.650	0.000	5.00	10.387	6.75	94.2	0.0	328.1
Totals:								190.00		5,170.4			42,865.3

Discrete Appurtenance Forces

Structure: CT00235-B-SBA
Site Name: Stony Brook
Height: 190.00 (ft)
Base Elev: 0.000 (ft)
Gh: 1.1

Code: EIA/TIA-222-G
Exposure: C
Crest Height: 0.00
Site Class: D - Stiff Soil
Struct Class: II

5/23/2018



Page: 44

Load Case: 1.0D + 1.0W 60 mph Wind

Dead Load Factor 1.00
Wind Load Factor 1.00



No.	Elev (ft)	Description	Qty	qz (psf)	qzGh (psf)	CaAa x Ka	Ka	Total CaAa (sf)	Dead Load (lb)	Horiz Ecc (ft)	Vert Ecc (ft)	Wind FX (lb)	Mom Y (lb-ft)	Mom Z (lb-ft)
1	190.00	ANT150D3	1	12.753	14.029	1.00	1.00	2.18	18.00	0.000	5.000	30.58	0.00	152.91
2	190.00	Low Profile Platform-flat	1	12.684	13.952	1.00	1.00	25.00	1200.00	0.000	0.000	348.81	0.00	0.00
3	184.00	742 351	6	12.599	13.858	0.49	0.80	15.75	178.80	0.000	0.000	218.31	0.00	0.00
4	184.00	Low Profile Platform-flat	1	12.599	13.858	1.00	1.00	25.00	1200.00	0.000	0.000	346.46	0.00	0.00
5	172.50	AIR B2A B4P	3	12.429	13.671	0.69	0.80	12.57	274.50	0.000	0.000	171.85	0.00	0.00
6	172.50	AIR 32 B4A B2P	3	12.429	13.671	0.70	0.80	13.59	317.40	0.000	0.000	185.83	0.00	0.00
7	172.50	LNX-6515DS	3	12.429	13.671	0.64	0.80	22.02	149.40	0.000	0.000	301.08	0.00	0.00
8	172.50	KRY 112 144/1	3	12.429	13.671	0.56	0.80	0.69	33.00	0.000	0.000	9.42	0.00	0.00
9	172.50	S11B12	3	12.429	13.671	0.56	0.80	4.75	153.00	0.000	0.000	65.00	0.00	0.00
10	172.50	PRK-1245	1	12.429	13.671	1.00	1.00	9.50	464.91	0.000	0.000	129.88	0.00	0.00
11	172.50	Low Profile Platform-flat	1	12.429	13.671	1.00	1.00	25.00	1200.00	0.000	0.000	341.78	0.00	0.00
12	158.50	PD458-2N	1	12.315	13.547	0.80	0.80	2.13	22.00	0.000	6.650	28.83	0.00	191.70
13	158.50	Low Profile Platform-flat	1	12.209	13.430	1.00	1.00	25.00	1200.00	0.000	0.000	335.75	0.00	0.00
14	156.00	114202C	1	12.270	13.497	1.00	1.00	2.14	24.00	0.000	6.300	28.88	0.00	181.97
15	153.00	ANT450D6-9	1	12.168	13.385	1.00	1.00	2.77	18.00	0.000	3.000	37.08	0.00	111.23
16	150.00	3 ft Standoff	2	12.068	13.275	1.00	1.00	5.26	80.00	0.000	0.000	69.83	0.00	0.00
17	145.00	Horizontal Rail & SCX1-K	1	11.982	13.181	1.00	1.00	9.97	302.36	0.000	0.000	131.41	0.00	0.00
18	145.00	TD-RRH8x20-25	3	11.982	13.181	0.52	0.75	6.29	210.00	0.000	0.000	82.87	0.00	0.00
19	145.00	Low Profile Platform-flat	1	11.982	13.181	1.00	1.00	25.00	1200.00	0.000	0.000	329.51	0.00	0.00
20	145.00	1900 MHz RRUs	3	11.982	13.181	0.66	0.75	7.52	132.00	0.000	0.000	99.17	0.00	0.00
21	145.00	800 MHz RRUs	6	11.982	13.181	0.69	0.75	10.31	318.00	0.000	0.000	135.87	0.00	0.00
22	145.00	(3) SFS-H-L (V-Braces)	1	11.982	13.181	1.00	1.00	9.70	230.00	0.000	0.000	127.85	0.00	0.00
23	145.00	APXVTM14-C-I20	3	11.982	13.181	0.58	0.75	10.98	168.60	0.000	0.000	144.78	0.00	0.00
24	145.00	NNVV-65B-R4	3	11.982	13.181	0.55	0.75	20.43	232.20	0.000	0.000	269.27	0.00	0.00
25	145.00	HRK14	1	11.982	13.181	1.00	1.00	8.13	302.36	0.000	0.000	107.16	0.00	0.00
26	145.00	PRK-1245 (kicker kit)	1	11.982	13.181	1.00	1.00	9.50	464.91	0.000	0.000	125.22	0.00	0.00
27	129.50	220-7N Omni	1	11.876	13.064	1.00	1.00	5.32	22.00	0.000	9.500	69.50	0.00	660.25
28	124.70	220-3AN	1	11.804	12.985	1.00	1.00	5.69	24.00	0.000	10.350	73.88	0.00	764.69
29	123.00	ANT450D6-9	1	11.633	12.797	1.00	1.00	2.77	18.00	0.000	3.000	35.45	0.00	106.34
30	120.00	3 ft Standoff	3	11.514	12.666	1.00	1.00	7.89	120.00	0.000	0.000	99.93	0.00	0.00
31	46.50	GPS	1	9.431	10.374	1.00	1.00	1.00	10.00	0.000	0.000	10.37	0.00	0.00
32	46.50	3 ft Standoff	1	9.431	10.374	1.00	1.00	2.63	40.00	0.000	0.000	27.28	0.00	0.00

Totals: 10,327.44

4,518.89

Total Applied Force Summary

Structure: CT00235-B-SBA
Site Name: Stony Brook
Height: 190.00 (ft)
Base Elev: 0.000 (ft)
Gh: 1.1

Code: EIA/TIA-222-G
Exposure: C
Crest Height: 0.00
Site Class: D - Stiff Soil
Struct Class: II

5/23/2018



Page: 45

Load Case: 1.0D + 1.0W 60 mph Wind

Dead Load Factor 1.00
Wind Load Factor 1.00



Iterations

24

Elev (ft)	Description	Lateral FX (-) (lb)	Axial FY (-) (lb)	Torsion MY (lb-ft)	Moment MZ (lb-ft)
0.00		0.00	0.00	0.00	0.00
5.00		139.87	1832.39	0.00	0.00
10.00		137.39	1802.69	0.00	0.00
11.75		47.50	623.92	0.00	0.00
15.00		88.88	2206.23	0.00	0.00
19.50		128.06	3013.34	0.00	0.00
20.00		14.17	175.69	0.00	0.00
25.00		147.03	1740.58	0.00	0.00
30.00		149.93	1710.87	0.00	0.00
35.00		151.91	1681.17	0.00	0.00
40.00		153.20	1651.47	0.00	0.00
45.00		153.93	1621.76	0.00	0.00
46.50	(2) attachments	83.55	530.74	0.00	0.00
50.00		107.61	1110.76	0.00	0.00
55.00		156.66	2803.43	0.00	0.00
56.75		54.42	968.04	0.00	0.00
60.00		101.18	896.30	0.00	0.00
65.00		155.53	1357.48	0.00	0.00
70.00		154.56	1331.49	0.00	0.00
75.00		153.35	1305.50	0.00	0.00
80.00		151.93	1279.50	0.00	0.00
85.00		150.31	1253.51	0.00	0.00
90.00		148.53	1227.52	0.00	0.00
94.50		131.94	1082.55	0.00	0.00
95.00		14.74	208.25	0.00	0.00
100.00		147.00	2055.96	0.00	0.00
105.00		144.79	1025.72	0.00	0.00
110.00		142.45	1003.44	0.00	0.00
115.00		139.99	981.17	0.00	0.00
120.00	(3) attachments	237.35	1078.89	0.00	0.00
123.00	(1) attachments	116.48	577.96	0.00	106.34
124.70	(1) attachments	119.32	337.75	0.00	764.69
125.00		7.98	55.10	0.00	0.00
129.50	(1) attachments	188.34	838.88	0.00	660.25
130.00		13.02	89.65	0.00	0.00
135.00		129.09	884.26	0.00	0.00
140.00		126.12	861.98	0.00	0.00
144.50		112.49	1172.95	0.00	0.00
145.00	(23) attachments	1565.42	3621.91	0.00	0.00
150.00	(2) attachments	191.58	667.57	0.00	0.00
153.00	(1) attachments	108.50	363.41	0.00	111.23
155.00		46.94	227.30	0.00	0.00
156.00	(1) attachments	52.14	136.76	0.00	181.97
158.50	(2) attachments	422.20	1501.30	0.00	191.70
160.00		34.16	163.46	0.00	0.00
165.00		111.93	535.21	0.00	0.00
170.00		108.51	520.36	0.00	0.00

Total Applied Force Summary

Structure: CT00235-B-SBA

Code: EIA/TIA-222-G

5/23/2018

Site Name: Stony Brook

Exposure: C

Height: 190.00 (ft)

Crest Height: 0.00

Base Elev: 0.000 (ft)

Site Class: D - Stiff Soil

Gh: 1.1

Topography: 1

Struct Class: II

Page: 46



172.50	(17) attachments	1257.71	2846.82	0.00	0.00
175.00		52.00	216.95	0.00	0.00
180.00		101.48	422.76	0.00	0.00
184.00	(7) attachments	643.31	1706.31	0.00	0.00
185.00		19.24	67.91	0.00	0.00
190.00	(2) attachments	473.59	1548.65	0.00	152.91
Totals:		9,689.31	58,925.58	0.00	2,169.09

Linear Appurtenance Segment Forces (Factored)

Structure: CT00235-B-SBA

Code: EIA/TIA-222-G

5/23/2018

Site Name: Stony Brook

Exposure: C

Height: 190.00 (ft)

Crest Height: 0.00

Base Elev: 0.000 (ft)

Site Class: D - Stiff Soil

Gh: 1.1

Topography: 1

Struct Class: II

Page: 47



Load Case: 1.0D + 1.0W 60 mph Wind

Dead Load Factor 1.00

Wind Load Factor 1.00



Top Elev (ft)	Description	Wind Exposed	Length (ft)	Ca	Exposed Width (in)	Area (sqft)	CaAa (sqft)	Ra	Cf Adjust Factor	qz (psf)	F X (lb)	Dead Load (lb)
5.00	1/2" GPS Line	Yes	5.00	0.000	0.50	0.21	0.00	0.008	0.000	7.442	0.00	0.80
10.00	1/2" GPS Line	Yes	5.00	0.000	0.50	0.21	0.00	0.008	0.000	7.442	0.00	0.80
11.75	1/2" GPS Line	Yes	1.75	0.000	0.50	0.07	0.00	0.008	0.000	7.442	0.00	0.28
15.00	1/2" GPS Line	Yes	3.25	0.000	0.50	0.14	0.00	0.008	0.000	7.442	0.00	0.52
19.50	1/2" GPS Line	Yes	4.50	0.000	0.50	0.19	0.00	0.008	0.000	7.854	0.00	0.72
20.00	1/2" GPS Line	Yes	0.50	0.000	0.50	0.02	0.00	0.008	0.000	7.896	0.00	0.08
25.00	1/2" GPS Line	Yes	5.00	0.000	0.50	0.21	0.00	0.008	0.000	8.276	0.00	0.80
30.00	1/2" GPS Line	Yes	5.00	0.000	0.50	0.21	0.00	0.009	0.000	8.600	0.00	0.80
35.00	1/2" GPS Line	Yes	5.00	0.000	0.50	0.21	0.00	0.009	0.000	8.883	0.00	0.80
40.00	1/2" GPS Line	Yes	5.00	0.000	0.50	0.21	0.00	0.009	0.000	9.137	0.00	0.80
45.00	1/2" GPS Line	Yes	5.00	0.000	0.50	0.21	0.00	0.009	0.000	9.366	0.00	0.80
46.50	1/2" GPS Line	Yes	1.50	0.000	0.50	0.06	0.00	0.009	0.000	9.431	0.00	0.24
Totals:										0.0	0.0	7.4

Calculated Forces

Structure: CT00235-B-SBA

Code: EIA/TIA-222-G

5/23/2018

Site Name: Stony Brook

Exposure: C

Height: 190.00 (ft)

Crest Height: 0.00

Base Elev: 0.000 (ft)

Site Class: D - Stiff Soil

Gh: 1.1

Topography: 1

Struct Class: II

Page: 49



175.00	-3.72	-1.32	0.00	-14.67	0.00	14.67	1448.54	724.27	1607.86	805.12	24.65	-1.278	0.000	0.021
180.00	-3.30	-1.21	0.00	-8.06	0.00	8.06	1404.63	702.31	1495.13	748.67	25.99	-1.286	0.000	0.013
184.00	-1.61	-0.53	0.00	-3.22	0.00	3.22	1364.22	682.11	1402.40	702.24	27.07	-1.290	0.000	0.006
185.00	-1.54	-0.51	0.00	-2.69	0.00	2.69	1352.25	676.13	1377.77	689.91	27.34	-1.290	0.000	0.005
190.00	0.00	-0.47	0.00	-0.15	0.00	0.15	1292.39	646.19	1257.90	629.89	28.69	-1.291	0.000	0.000

Final Analysis Summary

Structure: CT00235-B-SBA
Site Name: Stony Brook
Height: 190.00 (ft)
Base Elev: 0.000 (ft)
Gh: 1.1

Code: EIA/TIA-222-G
Exposure: C
Crest Height: 0.00
Site Class: D - Stiff Soil
Struct Class: II

5/23/2018
 Page: 50



Reactions

Load Case	Shear FX (kips)	Shear FZ (kips)	Axial FY (kips)	Moment MX (ft-kips)	Moment MY (ft-kips)	Moment MZ (ft-kips)
1.2D + 1.6W 108 mph Wind	50.3	0.00	70.63	0.00	0.00	6470.89
0.9D + 1.6W 108 mph Wind	50.3	0.00	52.95	0.00	0.00	6400.52
1.2D + 1.0Di + 1.0Wi 50 mph Wind	12.7	0.00	98.40	0.00	0.00	1653.59
1.2D + 1.0E	1.9	0.00	70.71	0.00	0.00	242.91
0.9D + 1.0E	1.9	0.00	53.03	0.00	0.00	240.06
1.0D + 1.0W 60 mph Wind	9.7	0.00	58.92	0.00	0.00	1241.23

Max Stresses

Load Case	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (-) (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	phi Pn (kips)	phi Vn (kips)	phi Tn (ft-kips)	phi Mn (ft-kips)	Elev (ft)	Stress Ratio
1.2D + 1.6W 108 mph Wind	-70.63	-50.35	0.00	-6470.8	0.00	-6470.8	6843.68	3421.8	17482.3	8754.18	0.00	0.750
0.9D + 1.6W 108 mph Wind	-52.95	-50.32	0.00	-6400.5	0.00	-6400.5	6843.68	3421.8	17482.3	8754.18	0.00	0.739
1.2D + 1.0Di + 1.0Wi 50 mph Wind	-98.40	-12.72	0.00	-1653.5	0.00	-1653.5	6843.68	3421.8	17482.3	8754.18	0.00	0.203
1.2D + 1.0E	-17.45	-1.16	0.00	-40.56	0.00	-40.56	1688.87	844.44	2343.95	1173.72	144.50	0.045
0.9D + 1.0E	-13.09	-1.14	0.00	-40.08	0.00	-40.08	1688.87	844.44	2343.95	1173.72	144.50	0.042
1.0D + 1.0W 60 mph Wind	-58.92	-9.71	0.00	-1241.2	0.00	-1241.2	6843.68	3421.8	17482.3	8754.18	0.00	0.150

Base Plate Summary

Structure: CT00235-B-SB
Site Name: Stony Brook
Height: 190.00 (ft)
Base Elev: 0.000 (ft)
Gh: 1.1

Topography: 1

Code: EIA/TIA-222-G
Exposure: C
Crest Height: 0.00
Site Class: D - Stiff Soil
Struct Class: II

5/23/2018

Page: 51



Reactions		Base Plate		Anchor Bolts	
Original Design		Yield (ksi):	50.00	Bolt Circle:	70.00
Moment (kip-ft):	5800.00	Width (in):	71.00	Number Bolts:	24.00
Axial (kip):	60.00	Style:	Clipped	Bolt Type:	2.25" 18J
Shear (kip):	43.00	Polygon Sides:	4.00	Bolt Diameter (in):	2.25
Analysis		Clip Length (in):	13.00	Yield (ksi):	75.00
Moment (kip-ft):	6470.89	Effective Len (in):	8.22	Ultimate (ksi):	100.00
Axial (kip):	98.40	Moment (kip-in):	691.68	Arrangement:	Clustered
Shear (kip):	50.35	Allow Stress (ksi):	67.50	Cluster Dist (in):	6.00
		Applied Stress (ksi):	0.00	Start Angle (deg):	45.00
Moment Design %:	111.57	Stress Ratio:	0.61	Compression	
				Force (kip):	188.98
				Allowable (kip):	260.00
				Ratio:	0.74
				Tension	
				Force (kip):	180.78
				Allowable (kip):	260.00
				Ratio:	0.71



Monopole Mat Foundation Design

Date
5/23/2018

Customer Name:	Sprint Nextel	EIA/TIA Standard:	EIA-222-G
Site Name:		Structure Height (Ft.):	190
Site Number:	CT00235-B-SBA	Engineer Name:	M. Franco
Engr. Number:	53345	Engineer Login ID:	

Foundation Info Obtained from:

Drawings/Calculations

Structure Type:

Monopole

Analysis or Design?

Analysis

Base Reactions (Factored):

Axial Load (Kips):

70.6

Shear Force (Kips):

50.3

Uplift Force (Kips):

0.0

Moment (Kips-ft):

6470.9

Allowable overstress %: 5.0%

Foundation Geometries:

Mods required -Yes/No ?: No

Diameter of Pier (ft.):

8.0

Depth of Base BG (ft.):

11.0

Pier Height A. G. (ft.):

0.50

Thickness of Pad (ft.):

4.00

Length of Pad (ft.):

24.5

Width of Pad (ft.):

24.5

Final Length of pad (ft)

24.5

Final width of pad (ft):

24.5

Control Value for Cell D18:

0

Control Value for Cell F18:

0

Material Properties and Rebar Info:

Concrete Strength (psi):

3000

Steel Elastic Modulus:

29000 ksi

Vertical bar yield (ksi):

60

Tie steel yield (ksi):

60

Vertical Rebar Size #:

11

Tie / Stirrup Size #:

5

Qty. of Vertical Rebars:

48

Tie Spacing (in):

12.0

Pad Rebar Yield (Ksi):

60

Pad Steel Rebar Size (#):

11

Concrete Cover (in.):

3

Unit Weight of Concrete:

150.0 pcf

Rebar at the bottom of the concrete pad:

Qty. of Rebar in Pad (L):

29

Qty. of Rebar in Pad (W):

29

Rebar at the top of the concrete pad:

Qty. of Rebar in Pad (L):

29

Qty. of Rebar in Pad (W):

29

Apply 1.35 factor for e/w Per G:

1.35

Soil Design Parameters:

Soil Unit Weight (pcf):

130.0

Soil Buoyant Weight:

50.0 Pcf

Water Table B.G.S. (ft.):

21.0

Unit Weight of Water:

62.4 pcf

Ultimate Bearing Pressure (psf):

8000

Ultimate Skin Friction:

0 Psf

Consider Friction for O.T.M. (Y/N):

No

Consider Friction for bearing (Y/N):

No

Consider soil hor. resist. for OTM.:

Yes

Angle from Top of Pad:

30

Angle from Bottom of Pad:

25

Reduction factor on the maximum soil bearing pressure: 1.00

Foundation Analysis and Design:

Uplift Strength Reduction Factor:

0.75

Compression Strength Reduction Factor:

0.75

Total Dry Soil Volume (cu. Ft.):

3849.89 Total Dry Soil Weight (Kips):

500.49

Total Buoyant Soil Volume (cu. Ft.):

0.00 Total Buoyant Soil Weight (Kips):

0.00

Total Effective Soil Weight (Kips):

500.49 Weight from the Concrete Block at Top (K):

0.00

Total Dry Concrete Volume (cu. Ft.):

2777.99 Total Dry Concrete Weight (Kips):

416.70

Total Buoyant Concrete Volume (cu. Ft.):

0.00 Total Buoyant Concrete Weight (Kips):

0.00

Total Effective Concrete Weight (Kips):

416.70 Total Vertical Load on Base (Kips):

987.81

Load/
Capacity
RatioCheck Soil Capacities:

Calculated Maximum Net Soil Pressure under the base (psf):

4413

<

Allowable Factored Soil Bearing (psf):

6000

0.74

OK!

Allowable Foundation Overturning Resistance (kips-ft.):

10977.2

>

Design Factored Moment (kips-ft.):

6222


0.57

OK!

Factor of Safety Against Overturning (O. R. Moment/Design Moment):

1.76

OK!



Check the capacities of Reinforcing Concrete:

Strength reduction factor (Flexure and axial tension):	0.90	Strength reduction factor (Shear):	0.75	
Strength reduction factor (Axial compression):	0.65	Wind Load Factor on Concrete Design:	1.00	Load/ Capacity Ratio

(1) Concrete Pier:


Vertical Steel Rebar Area (sq. in./each):	1.56	Tie / Stirrup Area (sq. in./each):	0.31	
Calculated Moment Capacity (Mn,Kips-Ft):	13572.9	> Design Factored Moment (Mu, Kips-Ft)	6848.2	0.50 OK!
Calculated Shear Capacity (Kips):	832.8	> Design Factored Shear (Kips):	50.3	0.06 OK!
Calculated Tension Capacity (Tn, Kips):	4043.5	> Design Factored Tension (Tu Kips):	0.0	0.00 OK!
Calculated Compression Capacity (Pn, Kips):	9498.6	> Design Factored Axial Load (Pu Kips):	70.6	0.01 OK!
Moment & Axial Strength Combination:	0.50	OK! Check Tie Spacing (Design/Required):		1 OK!
Pier Reinforcement Ratio:	0.010	Reinforcement Ratio is satisfied per ACI		

(2) Concrete Pad:

One-Way Design Shear Capacity (L-Direction, Kips):	1070.3	> One-Way Factored Shear (L-D. Kips):	302.3	0.28 OK!
One-Way Design Shear Capacity (W-Direction, Kips):	1070.3	> One-Way Factored Shear (W-D., Kips)	302.3	0.28 OK!
One-Way Design Shear Capacity (Corner-Corner, Kips):	841.5	> One-Way Factored Shear (C-C, Kips):	283.2	0.34 OK!
Lower Steel Pad Reinforcement Ratio (L-Direct.):	0.0035	OK! Lower Steel Pad Reinf. Ratio (W-Direc	0.0035	
Lower Steel Pad Moment Capacity (L-Direction. Kips-ft):	8652.6	> Moment at Bottom (L-Dir. K-Ft):	1820.6	0.21 OK!
Lower Steel Pad Moment Capacity (W-Direction. Kips-ft):	8652.6	> Moment at Bottom (W-Dir. K-Ft):	1820.6	0.21 OK!
Lower Steel Pad Moment Capacity (Corner-Corner,K-ft):	12080.1	> Moment at Bottom (C-C Dir. K-Ft):	2574.6	0.21 OK!
Upper Steel Pad Reinforcement Ratio (L-Direct.):	0.0035	OK! Upper Steel Reinf. Ratio (W-Dir.):	0.0035	
Upper Steel Pad Moment Capacity (L-Direc. Kips-ft):	8652.6	> Moment at the top (L-Dir K-Ft):	1111.2	0.13 OK!
Upper Steel Pad Moment Capacity (W-Direc. Kips-ft):	8652.6	> Moment at the top (W-Dir K-Ft):	1111.2	0.13 OK!
Upper Steel Pad Moment Capacity (Corner-Corner. K-ft):	12080.1	> Moment at the top (C-C Dir. K-Ft):	1050.8	0.09 OK!

(3) Check Punching Shear Capacity due to Moment in the Pier:

Moment transferred by punching shear:	2588.4 k-ft.	Max. factored shear stress $v_{u,CD}$:	4.4 Psi
Max. factored shear stress $v_{u,AB}$:	9.8 Psi	Factored shear Strength ϕv_n :	164.3 Psi
Max. factored shear stress v_u :	9.8 Psi	Check Usage of Punching Shear Capacity:	0.06 OK!

 <p>Tower Engineering Solutions</p>	Pier Foundation Design For Monopole			Date 5/23/2018
	Customer Name:	Sprint Nextel	EIA/TIA Standard:	EIA-222-G
	Site Name:		Structure Height (Ft.):	190
	Site Number:	CT00235-B-SBA	Engineer Name:	M. Franco
	Engr. Number:	53345	Engineer Login ID:	

Foundation Info Obtained from:

Structure Type: Monopole

Analysis or Design? Analysis

Base Reactions (Factored):


Axial Load (Kips):	70.6	Shear Force (Kips):	50.3
Uplift Force (Kips):	0.0	Moment (Kips-ft.):	6470.9

Foundation Geometries:

Mods required -Yes/No ?:	No	ft.	
Diameter of Pier (ft.):	8.0	Depth of Base B. G. S. :	24.0 ft.
Pier Height A. G. (ft.):	0.50		

Material Properties and Rebar Info:

Concrete Strength (psi):	3000	Steel Elastic Modulus:	29000 ksi
Vertical bar yield (ksi)	60	Tie steel yield strength:	40 ksi
Vertical Rebar Size #:	11	Tie / Stirrup Size #:	5
Qty. of Vertical Rebars:	48	Tie Spacing:	18.0 in.
Concrete Cover (in.):	4	Concrete unit weight:	150.0 pcf



Monopole Pier Foundation

Soil Design Parameters:

Water Table B.G.S. (ft):	21.0	Unit weight of water:	62.4 psf
Ratio of Uplift/Axial Skin Friction:	1.0	Pullout failure Angle:	30 (°)
Skin Frictions are to be obtained from:		Soil Report	

Depth of Layers (ft)		γ_{soil} (pcf)	ϕ (°)	Cohesion (psf)	Ultimate Skin Friction (psf)	Ultimate Bearing (psf)	Soil Types				
Top	Bottom										
0.0	4.0	140	0								
4.0	21.0	140	36	0			Sand				
21.0	41.5	147	36	0			Sand				
41.5	46.5	147	36	0			Sand				

Soil weight Increase Factor for buoyant soils (1.0 to 1.15): 1.1

Foundation Analysis and Design:

Uplift Strength Reduction Factor:	0.75	Soil Bearing Strength Reduction Factor:	0.75
Total Dry Soil Volume from Conical Failure (cu. Ft.):	8905	Dry Soil Weight from Conical Failure:	1247 Kips
Total Buoyant Soil Volume from Conical Failure (cu. Ft.):	75	Buoyant Soil Weight from Conical Failure (Kg):	8 Kips
Total Dry Concrete Volume (cu. Ft.):	1081	Total Dry Concrete Weight:	162.1 Kips
Total Buoyant Concrete Volume (cu. Ft.):	150.8	Total Buoyant Concrete Weight:	13.21 Kips
Total Effective Concrete Weight (Kips):	175.3	Total Effective Soil Weight:	1254.6 Kips
Total Effective Vertical Load on Base (Kips):	82.1		

Check Soil Capacities:

			Usage
Allowable Foundation Overturning Resistance (kips-ft.):	10239.9	> Design Factored Moment (kips-ft):	7312
Factor of Safety of Passive Soil Resistance against Moment:	1.40	OK!	0.71 OK!

Check the capacities of Reinforcing Concrete:

Strength reduction factor (Flexure and axial tension):	0.90	Strength reduction factor (Shear):	0.75
Strength reduction factor (Axial compression):	0.65	Wind Load Factor on Concrete Design:	1.00
Reinforcing Concrete Pier:			
Vertical Steel Rebar Area (sq. in./each):	1.56	Tie / Stirrup Area (sq. in./each):	0.31
Calculated Moment Capacity (Mn,Kips-Ft):	13515.8	> Design Factored Moment (Mu, K-Ft):	6698.0
Calculated Shear Capacity (Kips):	1274.2	> Design Factored Shear (Kips):	675.1
Calculated Tension Capacity (Tn, Kips):	4043.5	> Design Factored Tension (Tu Kips):	0.0
Calculated Compression Capacity (Pn, Kips):	9499	> Design Factored Axial Load (Pu Kips):	70.6
Moment & Axial Strength Combination:	0.50	Max. Allowable Tie/Stirrup Spacing:	0.01
Pier Reinforcement Ratio:	0.010	OK! Reinforcement Ratio is satisfied per ACI	
in.			

Antenna Mount Structural Analysis



Source: SBA Date: 11.12.2017

SBA Site: CT00235-B Stony Brook

Sprint Site Number: CT03XC107

Project: Sprint DO Macro Upgrade

Prepared For: Sprint

Mount Description: (1) Platform

Site Location: 2 Taugwonk Spur, Stonington, CT
New London County
 41.38197° , -71.90358°

Design Codes: ANSI/TIA-222-G
IBC 2012 w/ 2016 CT Building Code

Analysis Load Case: Sprint Final Configuration

Analysis Result: Adequate @ 65% - Once Augmented
See Conclusion



Revision 0
April 12, 2018

CT03XC107-PASSING-MOUNT-STRUCTURAL-ANALYSIS-04-12-18



GeoStructural • P.O. Box 2621, Boise, ID 83701 • Office: (530) 539-4787
Professional Engineers | Tower Technicians | Climbers | sUAS Mapping

1.0 Introduction

An antenna mount structural analysis has been performed on Sprint's existing mount assembly located at the CT00235-B Stony Brook communications site in New London County, CT considering the final equipment loading configuration listed in Section 3.0.

2.0 Analysis Criteria

An elastic three-dimensional model of the mount structure has been analyzed pursuant to the following criteria:

- IBC 2012 – International Building Code.
- ANSI/TIA-222-G – Structural Standard for Antenna Supporting Structures and Antennas.
- AISC – Steel Construction Manual.
- ANSI/AWS D1.1 – Structural Welding Code.

Wind w/o ice = 140 mph (3-sec gust Ultimate Wind Speed)	
Wind w/o ice = 108 mph (3-sec gust Equivalent per TIA-222-G Tower Code)	
Wind with ice = 50 mph (3-sec gust, 3/4" Ice) Exposure Category C	Topographic Category 1 Structure Class II

The following documents were provided:

- Mount and Tower Record Documents
SBA
- Tower Structural Analysis
TES, 12/14/17.
- RF Design
Sprint DOMU Project

The results of the analysis are illustrated in Section 4.0. If any of the existing or proposed conditions reported in this analysis are not properly represented, please contact our office immediately to request an amended report.

3.0 Appurtenance Information

Table 3.1 – Sprint Final Configuration¹

COR	(Quantity) Appurtenance Make/Model	Mount Description
145.0'±	(3) RFS APXVTM14-ALU-I20	(1) Platform
	(3) COMMSCOPE NNVV-65B-R4	
	(6) ALU 800MHz RRH	
	(3) ALU 1900MHz RRH	
	(3) ALU 2500MHz RRH	

1. Refer to antenna installation Construction Drawings (by others, when applicable) for additional information regarding final antenna and equipment orientations.
2. Panel antennas to be installed in Positions 1 and 3 (as close to the center of face near existing standoff as possible. RRH units to be installed on dual swivel brackets behind panel antennas in Positions 1 and 3 (a maximum of 2 RRH per pipe).

4.0 Analysis Results

Table 4.1 – Existing Mount Capacity

Load Case	Governing Mount Component ¹	% Capacity ²	Result
Final Sprint Configuration	Angle Rail	>200%	Inadequate ³

1. Refer to the Calculations & Software Output portion of this report for mount component and structural information.
2. Listed results are expressed as a percentage of available mount member capacity based upon the assumed material strengths listed in Table 4.3. 105% is an acceptable allowable stress percentage for mount components.
3. Structural augments to the existing mount structure are required to obtain a mount structure capable of supporting the currently proposed final loading configuration in Table 3.1.

Table 4.2 – Augmented Mount Capacity

Load Case	Governing Mount Component ¹	% Capacity ²	Result
Final Sprint Configuration	New SFS-H Connection Capacity	65%	Adequate Once Augmented ³

1. Refer to the Calculations & Software Output portion of this report for mount component and structural information.
2. Listed results are expressed as a percentage of available mount member capacity based upon the assumed material strengths listed in Table 4.3. 105% is an acceptable allowable stress percentage for mount components.
3. Refer to [GeoStructural Mount Augmentation Drawings](#) and Section 5.0 for information regarding required mount augments.

Table 4.3 – Structural Component Material Strengths

Structural Component	Nominal Strength/Material ¹
Pipe	$F_y = 35$ ksi (A53, Gr. B)
Tube	$F_y = 46$ ksi (A500, Gr. B)
Structural Shapes (L, C, W, etc.), Plate / Bar	$F_y = 36$ ksi (A36)
Uni-Strut	$F_y = 33$ ksi (A570, Gr. 33)
Connection Bolts	A325
Stainless Steel Bolts	18-8 Stainless, Grade 316/304 $F_y = 74$ ksi (Yield) & $F_u = 29$ ksi (Tension)
U-Bolts / Threaded Rod	SAE J429 Grade 2 (Substitution: ASTM A449) $F_y = 57$ ksi (Yield) & $F_u = 74$ ksi (Tension)
Welds	E70XX Electrodes

1. Strengths listed were assumed for this analysis and are based upon ASTM, AISC, RCSC, AWS and ACI preferred specification values. Values and materials are consistent with industry standards. Material strengths were taken from original design documents when available.

5.0 Conclusion & Recommendations

Based on Sprint's final equipment loading configuration, the existing mount assembly does not have sufficient capacity to support the loading considered in this analysis pursuant to the listed standards. Structural augments (reinforcements) will be required and are briefly summarized below:

- Install Platform Reinforcement Kit; located 4' below the existing collar mount and attaching to the middle of the existing back-to-back angle platform member at the platform corners.
 - Sitepro1 PRK-1245L, (1) total.
- Install Handrail Kit; located 3.0' above the existing platform rail and attaching to the mount pipes.
 - Sitepro1 HRK14-U, (1) total. Attach all mount pipes to new handrail with kit-provided cross-over plates. (6) new Pipe2.0STD x 9' tall mount pipes will be required to span between the existing rail and new top and bottom rails.
- Install V-Brace Kit; located 2.5' below the existing platform rail and attaching to the new bottom handrail kit.
 - Sitepro1 PRK-SFS-H-L, (1) total. Attach kit ring mount in kit to monopole shaft.
 - If the PRK-SFS-H-L kit is not available, provide (6) total L2-1/2x2-1/2x3/16 x ~8' long replacement angles, field-cut and drill to suit.
 - Pipe2.0STD x 14.0' Horizontal Rail, (3) total. Attach SFS-H-L kit angles to new horizontal bottom rail.
 - Pipe2.0STD x ~4' long corner braces, (3) total. Attach to new horizontal bottom rail w/ Sitepro1 PUCK brackets, (6) total.
 - Sitepro1 SCX1-K, (6) total. Attach all mount pipes to new horizontal bottom rail.
- Panel antennas to be installed in Positions 1 and 3 (as close to the center of face near existing standoff as possible. RRH units to be installed on dual swivel brackets behind panel antennas in Positions 1 and 3 (a maximum of 2 RRH per pipe).

Once the recommended augments are successfully implemented, the **augmented** mount assembly has sufficient capacity to support the loading considered in this analysis pursuant to the listed standards.

Augmentation Requirements:

- In order to obtain a mount structure capable of supporting the currently proposed final loading configuration, upgrade augments must be installed in accordance with GeoStructural's Mount Augmentation Drawings.
- Antennas and equipment shall be installed centered vertically on the mount front face rails. If this assumption is incorrect, the results of this analysis will be affected.

This analysis only encompasses the antenna mount assembly. The tower, overall mount support structure, foundation, etc. are beyond the scope of this analysis. If any of the existing or proposed conditions (appurtenance loading, member sizes, etc.) reported in this analysis are not properly represented, please contact our office immediately to request an amended report.

Prepared by:



Jesse Drennen, PE, MLE
208.761.7986
jesse.drennen@geostructural.com

Reviewed and Approved by:





Don George, PE, SE, MLSE
208.602.6569
don.george@geostructural.com

6.0 Standard Conditions

- All data required to complete our structural analysis was furnished by our client and provided record data. GeoStructural has not conducted a site visit or independent study to verify existing conditions and the results of this analysis are based solely on the information provided. It has been assumed that the tower, antenna support structure and foundation have been constructed according to the provided existing drawings, previous structural analysis reports, mapping documents, etc.
- The default Structure Classification is Class II in accordance with ANSI/TIA-222-G §A.2.2 & §A.15.3 and has been assumed for this analysis. The owner shall verify this classification conforms with original or desired reliability criteria.
- This analysis assumes that the structure has been properly installed and maintained in accordance with ANSI/TIA-222-G §15.5 and that no physical deterioration has occurred in any of the components of the structure. Damaged, missing, or rusted members were not considered.
- This analysis verifies the adequacy of the main components of the structure. Not all connections, welds, bolts, plates, etc. were individually detailed and analyzed. Where not specifically analyzed, the existing connection plates, welds, bolts, etc. were assumed adequate to develop the full capacity of the main structural members.
- No consideration has been made for unusual or extreme wind events, rime/in-cloud ice loadings, harmonic or nodal vibration, vortex shedding or other similar conditions.
- It is the owner's responsibility to determine the appropriate design wind speed and amount of ice accumulation beyond code minimum values that should be considered in the analysis.
- This analysis report does not constitute a maintenance and condition assessment. No certifications regarding maintenance and condition are expressed or implied. If desired, GeoStructural can provide these services under a subsequent contract.
- This analysis only encompasses the antenna mount assembly. The tower, overall mount support structure, foundation, etc. are beyond the scope of this analysis. If desired, GeoStructural can provide these services under a subsequent contract.


7.0 Calculations & Software Output

This page intentionally left blank.




Envelope Only Solution

GeoStructural, LLC	CT03XC107	SK - 1
Jesse Drennen, PE		Apr 12, 2018 at 1:07 PM
		CT03XC107_Mount Analysis_R0 1...






Code Check (Env)	
No Calc	
> 1.0	
.90-1.0	
.75-.90	
.50-.75	
0.-.50	





Member Code Checks Displayed (Enveloped)
Envelope Only Solution

GeoStructural, LLC	CT03XC107	SK - 2
Jesse Drennen, PE		Apr 12, 2018 at 1:07 PM
		CT03XC107_Mount Analysis_R0 1...





Member Shear Checks Displayed (Enveloped)
Envelope Only Solution

GeoStructural, LLC	CT03XC107	SK - 3
Jesse Drennen, PE		Apr 12, 2018 at 1:07 PM
		CT03XC107_Mount Analysis_R0 1...




Envelope Only Solution

GeoStructural, LLC	CT03XC107	SK - 1
Jesse Drennen, PE		Apr 12, 2018 at 1:12 PM
		CT03XC107_Mount Analysis_R0 1...




Envelope Only Solution

GeoStructural, LLC	CT03XC107	SK - 7
Jesse Drennen, PE		Apr 12, 2018 at 1:14 PM
		CT03XC107_Mount Analysis_R0 1...



Code Check (Env)	
No Calc	
> 1.0	
.90-1.0	
.75-.90	
.50-.75	
0.-.50	



Member Code Checks Displayed (Enveloped)
Envelope Only Solution

GeoStructural, LLC




Jesse Drennen, PE

CT03XC107

SK - 2

Apr 12, 2018 at 1:12 PM

CT03XC107_Mount Analysis_R0 1...



Member Shear Checks Displayed (Enveloped)
Envelope Only Solution

GeoStructural, LLC

Jesse Drennen, PE

SK - 3

CT03XC107

Apr 12, 2018 at 1:12 PM

CT03XC107_Mount Analysis_R0 1...

Basic Load Cases

BLC Description		Category	X Gravity	Y Gravity	Z Gravity	Joint	Point	Distributed Area(Me...)	Surface(P...
1	D	DL		-1		25		6	
2	Di	SL				25		54	
3	Lm [500]	LL				1			
4	Lv [250]	LL				2			
5	Woz	WL				25		48	
6	Wox	WL				25		48	
7	Wiz	WL				25		48	
8	Wix	WL				25		48	
9	Ez	EL				25			
10	Ex	EL				25			

Load Combination Design

Description	ASIF	CD	Service	Hot Rol...	Cold Form...	Wood	Concrete	Masonry	Aluminum	Stainless	Connection
1 1) 1.4D				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
2 2) 1.2D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
3 2) 1.2D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
4 2) 1.2D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
5 2) 1.2D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
6 2) 1.2D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
7 2) 1.2D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
8 2) 1.2D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
9 2) 1.2D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
10 2) 1.2D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
11 2) 1.2D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
12 2) 1.2D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
13 2) 1.2D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
14 3) 0.9D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
15 3) 0.9D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
16 3) 0.9D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
17 3) 0.9D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
18 3) 0.9D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
19 3) 0.9D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
20 3) 0.9D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
21 3) 0.9D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
22 3) 0.9D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
23 3) 0.9D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
24 3) 0.9D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
25 3) 0.9D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
26 4) 1.2D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
27 4) 1.2D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
28 4) 1.2D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
29 4) 1.2D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
30 4) 1.2D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
31 4) 1.2D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
32 4) 1.2D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
33 4) 1.2D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
34 4) 1.2D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
35 4) 1.2D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
36 4) 1.2D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
37 4) 1.2D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
38 5) 1.2D+1.5L...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
39 5) 1.2D+1.5L...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
40 5) 1.2D+1.5L...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
41 5) 1.2D+1.5L...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes

Company : GeoStructural, LLC
Designer : Jesse Drennen, PE
Job Number :
Model Name : CT03XC107

Apr 12, 2018
1:13 PM
Checked By: DWG

Load Combination Design (Continued)

Description	ASIF	CD	Service	Hot Rol...	Cold Form...	Wood	Concrete	Masonry	Aluminum	Stainless	Connection
42	5) 1.2D+1.5L...				Yes	Yes	Yes	Yes	Yes	Yes	Yes
43	5) 1.2D+1.5L...				Yes	Yes	Yes	Yes	Yes	Yes	Yes
44	5) 1.2D+1.5L...				Yes	Yes	Yes	Yes	Yes	Yes	Yes
45	5) 1.2D+1.5L...				Yes	Yes	Yes	Yes	Yes	Yes	Yes
46	5) 1.2D+1.5L...				Yes	Yes	Yes	Yes	Yes	Yes	Yes
47	5) 1.2D+1.5L...				Yes	Yes	Yes	Yes	Yes	Yes	Yes
48	5) 1.2D+1.5L...				Yes	Yes	Yes	Yes	Yes	Yes	Yes
49	5) 1.2D+1.5L...				Yes	Yes	Yes	Yes	Yes	Yes	Yes
50	6) 1.2D+1.5Lv				Yes	Yes	Yes	Yes	Yes	Yes	Yes
51	7) (1.2+0.2Sd..				Yes	Yes	Yes	Yes	Yes	Yes	Yes
52	7) (1.2+0.2Sd..				Yes	Yes	Yes	Yes	Yes	Yes	Yes
53	7) (1.2+0.2Sd..				Yes	Yes	Yes	Yes	Yes	Yes	Yes
54	7) (1.2+0.2Sd..				Yes	Yes	Yes	Yes	Yes	Yes	Yes
55	7) (1.2+0.2Sd..				Yes	Yes	Yes	Yes	Yes	Yes	Yes
56	7) (1.2+0.2Sd..				Yes	Yes	Yes	Yes	Yes	Yes	Yes
57	7) (1.2+0.2Sd..				Yes	Yes	Yes	Yes	Yes	Yes	Yes
58	7) (1.2+0.2Sd..				Yes	Yes	Yes	Yes	Yes	Yes	Yes
59	7) (1.2+0.2Sd..				Yes	Yes	Yes	Yes	Yes	Yes	Yes
60	7) (1.2+0.2Sd..				Yes	Yes	Yes	Yes	Yes	Yes	Yes
61	7) (1.2+0.2Sd..				Yes	Yes	Yes	Yes	Yes	Yes	Yes
62	7) (1.2+0.2Sd..				Yes	Yes	Yes	Yes	Yes	Yes	Yes
63	8) (0.9-0.2Sd..				Yes	Yes	Yes	Yes	Yes	Yes	Yes
64	8) (0.9-0.2Sd..				Yes	Yes	Yes	Yes	Yes	Yes	Yes
65	8) (0.9-0.2Sd..				Yes	Yes	Yes	Yes	Yes	Yes	Yes
66	8) (0.9-0.2Sd..				Yes	Yes	Yes	Yes	Yes	Yes	Yes
67	8) (0.9-0.2Sd..				Yes	Yes	Yes	Yes	Yes	Yes	Yes
68	8) (0.9-0.2Sd..				Yes	Yes	Yes	Yes	Yes	Yes	Yes
69	8) (0.9-0.2Sd..				Yes	Yes	Yes	Yes	Yes	Yes	Yes
70	8) (0.9-0.2Sd..				Yes	Yes	Yes	Yes	Yes	Yes	Yes
71	8) (0.9-0.2Sd..				Yes	Yes	Yes	Yes	Yes	Yes	Yes
72	8) (0.9-0.2Sd..				Yes	Yes	Yes	Yes	Yes	Yes	Yes
73	8) (0.9-0.2Sd..				Yes	Yes	Yes	Yes	Yes	Yes	Yes
74	8) (0.9-0.2Sd..				Yes	Yes	Yes	Yes	Yes	Yes	Yes

Envelope Joint Reactions

Joint		X [k]	LC	Y [k]	LC	Z [k]	LC	MX [k-ft]	LC	MY [k-ft]	LC	MZ [k-ft]	LC
1	N25	max	.863	5	.095	32	1.608	2	.002	2	0	1	0
2		min	-.845	23	.007	14	-1.575	20	-.001	20	0	1	0
3	N30	max	1.33	5	.095	36	1.032	25	0	23	0	1	0
4		min	-1.308	23	.008	18	-1.047	7	0	5	0	1	-.001
5	N35	max	1.457	17	.095	28	.923	15	0	17	0	1	.001
6		min	-1.483	11	.008	22	-.937	9	-.001	11	0	1	0
7	N42	max	1.725	16	1.219	33	2.739	3	2.301	36	2.955	22	3.918
8		min	-2.029	10	.3	63	-2.555	21	.533	69	-2.967	4	.91
9	N40	max	1.945	6	1.243	35	2.562	13	2.274	27	2.777	24	-.929
10		min	-1.637	24	.306	68	-2.392	19	.518	69	-2.783	6	-3.974
11	N44	max	1.927	5	1.225	37	.646	14	-1.071	64	1.038	5	.095
12		min	-1.922	23	.302	66	-1.002	8	-4.564	33	-1.032	23	-.117
13	N116	max	.081	17	1.926	26	-.403	69	0	1	0	23	0
14		min	-.081	23	.321	20	-2.047	26	0	1	0	5	0
15	N118	max	-.346	73	1.914	30	1.022	28	0	5	0	23	0
16		min	-1.758	30	.298	24	.151	22	0	23	0	5	0
17	N120	max	1.792	33	1.947	34	1.039	35	0	23	0	23	0
18		min	.354	65	.311	16	.174	18	0	5	0	5	0
19	N135	max	.185	17	.066	32	.668	2	0	27	0	1	0

Company : GeoStructural, LLC
Designer : Jesse Drennen, PE
Job Number :
Model Name : CT03XC107

Apr 12, 2018
1:13 PM
Checked By: DWG

Envelope AISC 14th(360-10): LRFD Steel Code Checks (Continued)

Member	Shape	Code Check	Loc[ft]	LC	Shear...Loc[ft]	Dir	LC	phi*Pnc...	phi*Pnt ...	phi*Mn ...	phi*Mn ...Cb	Eqn			
41	M78 1	L2.5x2.5x3	.106	2.141	2	.011	0	v	8	15.939	29.192	.873	1.724	1...	H2-1
42	M57C	PIPE 2.0	.104	3.083	11	.088	3.083		6	14.916	32.13	1.872	1.872	1...	H1-1b
43	M74 1	L2.5x2.5x3	.090	2.141	3	.009	4.282	y	4	15.939	29.192	.873	1.724	1...	H2-1
44	M76 1	L2.5x2.5x3	.089	2.141	13	.008	4.282	z	12	15.939	29.192	.873	1.724	1...	H2-1
45	M104	LL2.5x2.5x...	.086	3.01	27	.006	6.021	z	5	36.392	58.32	3.954	2.55	1...	H1-1b
46	M71 1	PIPE 2.0	.074	0	39	.040	2.5		7	29.81	32.13	1.872	1.872	1...	H1-1b
47	M70 1	PIPE 2.0	.062	0	11	.039	2.5		3	29.81	32.13	1.872	1.872	1...	H1-1b
48	M72 1	PIPE 2.0	.046	0	10	.048	2.5		11	29.81	32.13	1.872	1.872	1...	H1-1b

SPECIAL CONSTRUCTION NOTE:
SPRINT WORK IS CONTINGENT ON THE FOLLOWING:
* COMPLETION OF A GLOBAL STRUCTURAL STABILITY ANALYSIS.
* COMPLETION OF AN ANTENNA/RRH MOUNT STRUCTURAL ASSESSMENT.
* GC SHALL FURNISH, INSTALL AND COMPLETE ALL REQUIRED STRUCTURAL MODIFICATIONS AS INDICATED IN BEFORE-MENTIONED ANALYSIS AND ASSESSMENT.

SPECIAL CONSTRUCTION NOTE:
GENERAL CONTRACTOR SHALL FURNISH AND INSTALL ALL ANTENNA MOUNT STRUCTURAL AUGMENTS (STRUCTURAL MODIFICATIONS) AT THE SPRINT'S RAD/VERTICAL EQUIPMENT SPACE PER RECOMMENDATIONS FROM SBA- PROVIDED ANTENNA MOUNT STRUCTURAL ANALYSIS AND ANY SUPPLEMENTAL CONSTRUCTION DRAWINGS (PROVIDED BY OTHERS).




PROGRAM:



DO MACRO UPGRADE EQUIPMENT DEPLOYMENT

SITE NUMBER: CT03XC107

SITE ADDRESS: 2 TAUGWONK SPUR
STONINGTON, CT 06378

SITE TYPE: EXISTING 190' MONOPOLE



PROJECT INFORMATION		AREA MAP	SCOPE OF WORK	DRAWING INDEX		
SITE INFORMATION:			<p>SPRINT PROPOSES TO MODIFY AN EXISTING UNMANNED TELECOMMUNICATIONS FACILITY.</p> <ul style="list-style-type: none"> • REMOVE (6) EXISTING PANEL ANTENNAS • REMOVED (9) EXISTING 1 5/8" COAX • INSTALL (6) PANEL ANTENNAS • INSTALL (3) 2.5 GHz RRH'S ON PROPOSED DUAL RRH MOUNT • INSTALL (6) 800 MHz RRH'S ON PROPOSED DUAL RRH MOUNT • RELOCATE (3) 1900 MHz RRH'S ON PROPOSED DUAL RRH MOUNT • INSTALL (4) HYBRID CABLES • INSTALL STRUCTURAL AUGMENTS • INSTALL RAN EQUIPMENT INSIDE EXISTING MMBTS CABINET <p>THESE PLANS HAVE BEEN DEVELOPED FOR THE MODIFICATION OF AN EXISTING UNMANNED TELECOMMUNICATIONS FACILITY OWNED OR LEASED BY SPRINT IN ACCORDANCE WITH THE SCOPE OF WORK PROVIDED BY SPRINT. INFINIGY HAS INCORPORATED THIS SCOPE OF WORK IN THE PLANS. THESE PLANS ARE NOT FOR CONSTRUCTION UNLESS ACCOMPANIED BY A PASSING STRUCTURAL STABILITY ANALYSIS PREPARED BY A LICENSED STRUCTURAL ENGINEER. STRUCTURAL STABILITY ANALYSIS MUST INCLUDE BOTH TOWER AND MOUNT.</p>	SHEET NO.	SHEET TITLE	REV.
APPLICANT:			APPLICABLE CODES	T-1	TITLE SHEET & PROJECT DATA	0
TOWER OWNER:			ALL WORK SHALL BE PERFORMED AND MATERIALS INSTALLED IN ACCORDANCE WITH THE CURRENT EDITIONS OF THE FOLLOWING CODES AS ADOPTED BY THE LOCAL GOVERNING AUTHORITIES. NOTHING IN THESE PLANS IS TO BE CONSTRUED TO PERMIT WORK NOT CONFORMING TO THESE CODES.	SP-1	OUTLINE SPECIFICATIONS	0
SBA PROPERTIES LLC, 8051 CONGRESS AVENUE BOCA RATON, FL 33487			1. INTERNATIONAL BUILDING CODE (2012 IBC) 2. TIA-222-G OR LATEST EDITION 3. NFPA 780 - LIGHTNING PROTECTION CODE 4. 2014 NATIONAL ELECTRIC CODE OR LATEST EDITION 5. ANY OTHER NATIONAL OR LOCAL APPLICABLE CODES, MOST RECENT EDITIONS 6. CT BUILDING CODE 7. LOCAL BUILDING CODE 8. CITY/COUNTY ORDINANCES	SP-2	OUTLINE SPECIFICATIONS	0
SBA SITE ID: CT00235-B				SP-3	OUTLINE SPECIFICATIONS	0
SBA SITE NAME: STONY BROOK				A-1	SITE PLAN	0
SBA CONTACT: STEPHEN ROTH (800) 539-4920 sroth@sbasite.com				A-2	TOWER ELEVATION	0
CALL CONNECTICUT ONE CALL (800) 922-4455				A-3	ANTENNA LAYOUT & MOUNTING DETAILS	0
CALL 3 WORKING DAYS BEFORE YOU DIG!				A-4	EQUIPMENT & MOUNTING DETAILS	0
GENERAL NOTES				A-5	DETAILS	0
				E-1	ELECTRICAL & GROUNDING DETAILS	0
				RF-1	RF DATA SHEET	0
				RF-2	PLUMBING DIAGRAM	0
APPROVALS						
PROJECT MANAGER:						
CONSTRUCTION:						
RF ENGINEER:						
ZONING/SITE ACQ:						
OPERATIONS:						
TOWER OWNER:						
THE FOLLOWING PARTIES HEREBY APPROVE AND ACCEPT THESE DOCUMENTS AND AUTHORIZE THE CONTRACTOR TO PROCEED WITH THE CONSTRUCTION DESCRIBED HEREIN. ALL DOCUMENTS ARE SUBJECT TO REVIEW BY THE LOCAL BUILDING DEPARTMENT AND MAY IMPOSE CHANGES OR MODIFICATIONS.						
CALL 811						
Know what's below. Call before you dig. www.call811.com						

T-1

THESE OUTLINE SPECIFICATIONS IN CONJUNCTION WITH THE SPRINT STANDARD CONSTRUCTION SPECIFICATIONS, INCLUDING CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

SECTION 01 100 – SCOPE OF WORK

PART 1 – GENERAL

1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE SPRINT CONSTRUCTION STANDARDS FOR WIRELESS SITES, CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

1.2 RELATED DOCUMENTS:

- A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
- B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.

1.3 PRECEDENCE: SHOULD CONFLICTS OCCUR BETWEEN THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES INCLUDING THE STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES AND THE CONSTRUCTION DRAWINGS, INFORMATION ON THE CONSTRUCTION DRAWINGS SHALL TAKE PRECEDENCE. NOTIFY SPRINT CONSTRUCTION MANAGER IF THIS OCCURS.

1.4 NATIONALLY RECOGNIZED CODES AND STANDARDS:

- A. THE WORK SHALL COMPLY WITH APPLICABLE NATIONAL AND LOCAL CODES AND STANDARDS, LATEST EDITION, AND PORTIONS THEREOF, INCLUDED BUT NOT LIMITED TO THE FOLLOWING:
 - 1. GR-63-CORE NEBS REQUIREMENTS: PHYSICAL PROTECTION
 - 5. GR-78-CORE GENERIC REQUIREMENTS FOR THE PHYSICAL DESIGN AND MANUFACTURE OF TELECOMMUNICATIONS EQUIPMENT.
 - 3. GR-1089 CORE, ELECTROMAGNETIC COMPATIBILITY AND ELECTRICAL SAFETY –GENERIC CRITERIA FOR NETWORK TELECOMMUNICATIONS EQUIPMENT.
 - 4. NATIONAL FIRE PROTECTION ASSOCIATION CODES AND STANDARDS (NFPA) INCLUDING NFPA 70 (NATIONAL ELECTRICAL CODE – "NEC") AND NFPA 101 (LIFE SAFETY CODE).
 - 5. AMERICAN SOCIETY FOR TESTING OF MATERIALS (ASTM)
 - 6. INSTITUTE OF ELECTRONIC AND ELECTRICAL ENGINEERS (IEEE)
 - 7. AMERICAN CONCRETE INSTITUTE (ACI)
 - 8. AMERICAN WIRE PRODUCERS ASSOCIATION (AWPA)
 - 9. CONCRETE REINFORCING STEEL INSTITUTE (CRSI)
 - 10. AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)
 - 11. PORTLAND CEMENT ASSOCIATION (PCA)
 - 12. NATIONAL CONCRETE MASONRY ASSOCIATION (NCMA)
 - 13. BRICK INDUSTRY ASSOCIATION (BIA)
 - 14. AMERICAN WELDING SOCIETY (AWS)
 - 15. NATIONAL ROOFING CONTRACTORS ASSOCIATION (NRCA)
 - 16. SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)
 - 17. DOOR AND HARDWARE INSTITUTE (DHI)
 - 18. OCCUPATIONAL SAFETY AND HEALTH ACT (OSHA)
 - 19. APPLICABLE BUILDING CODES INCLUDING UNIFORM BUILDING CODE, SOUTHERN BUILDING CODE, BOCA, AND THE INTERNATIONAL BUILDING CODE.

1.5 DEFINITIONS:

- A. WORK: THE SUM OF TASKS AND RESPONSIBILITIES IDENTIFIED IN THE CONTRACT DOCUMENTS.
- B. COMPANY: SPRINT CORPORATION
- C. ENGINEER: SYNONYMOUS WITH ARCHITECT & ENGINEER AND "A&E". THE DESIGN PROFESSIONAL HAVING PROFESSIONAL RESPONSIBILITY FOR DESIGN OF THE PROJECT.
- D. CONTRACTOR: CONSTRUCTION CONTRACTOR; CONSTRUCTION VENDOR; INDIVIDUAL OR ENTITY WHO AFTER EXECUTION OF A CONTRACT IS BOUND TO ACCOMPLISH THE WORK.
- E. THIRD PARTY VENDOR OR AGENCY: A VENDOR OR AGENCY ENGAGED SEPARATELY BY THE COMPANY, A&E, OR CONTRACTOR TO PROVIDE MATERIALS OR TO ACCOMPLISH SPECIFIC TASKS RELATED TO BUT NOT INCLUDED IN THE WORK.
- F. OFCI: OWNER FURNISHED, CONTRACTOR INSTALLED EQUIPMENT.
- G. CONSTRUCTION MANAGER – ALL PROJECTS RELATED COMMUNICATION TO FLOW THROUGH SPRINT REPRESENTATIVE IN CHARGE OF PROJECT...

1.6 SITE FAMILIARITY: CONTRACTOR SHALL BE RESPONSIBLE FOR FAMILIARIZING HIMSELF WITH ALL CONTRACT DOCUMENTS, FIELD CONDITIONS AND DIMENSIONS PRIOR TO PROCEEDING WITH CONSTRUCTION. ANY DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE SPRINT CONSTRUCTION MANAGER PRIOR TO THE COMMENCEMENT OF WORK. NO COMPENSATION WILL BE AWARDED BASED ON CLAIM OF LACK OF KNOWLEDGE OF FIELD CONDITIONS.

1.7 POINT OF CONTACT: COMMUNICATION BETWEEN SPRINT AND THE CONTRACTOR SHALL FLOW THROUGH THE SINGLE SPRINT CONSTRUCTION MANAGER APPOINTED TO MANAGE THE PROJECT FOR SPRINT.

1.8 ON-SITE SUPERVISION: THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK AND SHALL BE RESPONSIBLE FOR CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES IN ACCORDANCE WITH THE CONTRACT DOCUMENTS. THE CONTRACTOR SHALL EMPLOY A COMPETENT SUPERINTENDENT WHO SHALL BE IN ATTENDANCE AT THE SITE AT ALL TIMES DURING PERFORMANCE OF THE WORK.

1.9 DRAWINGS, SPECIFICATIONS AND DETAILS REQUIRED AT JOBSITE: THE CONSTRUCTION CONTRACTOR SHALL MAINTAIN A FULL SET OF THE CONSTRUCTION DRAWINGS, STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES AND THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES AT THE JOBSITE FROM MOBILIZATION THROUGH CONSTRUCTION COMPLETION.

A. THE JOBSITE DRAWINGS, SPECIFICATIONS AND DETAILS SHALL BE CLEARLY MARKED DAILY IN RED PENCIL WITH ANY CHANGES IN CONSTRUCTION OVER WHAT IS DEPICTED IN THE DOCUMENTS. AT CONSTRUCTION COMPLETION, THIS JOBSITE MARKUP SET SHALL BE DELIVERED TO THE COMPANY OR COMPANY'S DESIGNATED REPRESENTATIVE TO BE FORWARDED TO THE COMPANY'S A&E VENDOR FOR PRODUCTION OF "AS-BUILT" DRAWINGS.

B. DETAILS ARE INTENDED TO SHOW DESIGN INTENT. MODIFICATIONS MAY BE REQUIRED TO SUIT JOB DIMENSIONS OR CONDITIONS, AND SUCH MODIFICATIONS SHALL BE INCLUDED AS PART OF THE WORK. CONTRACTOR SHALL NOTIFY SPRINT CONSTRUCTION MANAGER OF ANY VARIATIONS PRIOR TO PROCEEDING WITH THE WORK.

C. DIMENSIONS SHOWN ARE TO FINISH SURFACES UNLESS NOTED OTHERWISE. SPACING BETWEEN EQUIPMENT IS THE REQUIRED CLEARANCE. SHOULD THERE BE ANY QUESTIONS REGARDING THE CONTRACT DOCUMENTS, EXISTING CONDITIONS AND/OR DESIGN INTENT, THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING A CLARIFICATION FROM THE SPRINT CONSTRUCTION MANAGER PRIOR TO PROCEEDING WITH THE WORK.

1.10 USE OF JOB SITE: THE CONTRACTOR SHALL CONFINE ALL CONSTRUCTION AND RELATED OPERATIONS INCLUDING STAGING AND STORAGE OF MATERIALS AND EQUIPMENT, PARKING, TEMPORARY FACILITIES, AND WASTE STORAGE TO THE LEASE PARCEL UNLESS OTHERWISE PERMITTED BY THE CONTRACT DOCUMENTS.

1.11 UTILITIES SERVICES: WHERE NECESSARY TO CUT EXISTING PIPES, ELECTRICAL WIRES, CONDUITS, CABLES, ETC., OF UTILITY SERVICES, OR OF FIRE PROTECTION OR COMMUNICATIONS SYSTEMS, THEY SHALL BE CUT AND CAPPED AT SUITABLE PLACES OR WHERE SHOWN. ALL SUCH ACTIONS SHALL BE COORDINATED WITH THE UTILITY COMPANY INVOLVED:

1.12 PERMITS / FEES: WHEN REQUIRED THAT A PERMIT OR CONNECTION FEE BE PAID TO A PUBLIC UTILITY PROVIDER FOR NEW SERVICE TO THE CONSTRUCTION PROJECT, PAYMENT OF SUCH FEE SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.

1.13 CONTRACTOR SHALL TAKE ALL MEASURES AND PROVIDE ALL MATERIAL NECESSARY FOR PROTECTING EXISTING EQUIPMENT AND PROPERTY.

1.14 METHODS OF PROCEDURE (MOPS) FOR CONSTRUCTION: CONTRACTOR SHALL PERFORM WORK AS DESCRIBED IN THE FOLLOWING INSTALLATION AND COMMISSIONING MOPS.

NOTE: IN SHORT-FORM SPECIFICATIONS ON THE DRAWINGS, A/E TO INSERT LIST OF APPLICABLE MOPS INCLUDING EN-2012-001, EN-2013-002, EL-0568, AND TS-0193

1.15 USE OF ELECTRONIC PROJECT MANAGEMENT SYSTEMS:

PART 2 – PRODUCTS (NOT USED)

PART 3 – EXECUTION

3.1 TEMPORARY UTILITIES AND FACILITIES: THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL TEMPORARY UTILITIES AND FACILITIES NECESSARY EXCEPT AS OTHERWISE INDICATED IN THE CONSTRUCTION DOCUMENTS. TEMPORARY UTILITIES AND FACILITIES INCLUDE POTABLE WATER, HEAT, HVAC, ELECTRICITY, SANITARY FACILITIES, WASTE DISPOSAL FACILITIES, AND TELEPHONE/COMMUNICATION SERVICES. PROVIDE TEMPORARY UTILITIES AND FACILITIES IN ACCORDANCE WITH OSHA AND THE AUTHORITY HAVING JURISDICTION. CONTRACTOR MAY UTILIZE THE COMPANY ELECTRICAL SERVICE IN THE COMPLETION OF THE WORK WHEN IT BECOMES AVAILABLE. USE OF THE LESSOR'S OR SITE OWNER'S UTILITIES OR FACILITIES IS EXPRESSLY FORBIDDEN EXCEPT AS OTHERWISE ALLOWED IN THE CONTRACT DOCUMENTS.

3.2 ACCESS TO WORK: THE CONTRACTOR SHALL PROVIDE ACCESS TO THE JOB SITE FOR AUTHORIZED COMPANY PERSONNEL AND AUTHORIZED REPRESENTATIVES OF THE ARCHITECT/ENGINEER DURING ALL PHASES OF THE WORK.

3.3 TESTING: REQUIREMENTS FOR TESTING BY THIS CONTRACTOR SHALL BE AS INDICATED HEREWITH, ON THE CONSTRUCTION DRAWINGS, AND IN THE INDIVIDUAL SECTIONS OF THESE SPECIFICATIONS. SHOULD COMPANY CHOOSE TO ENGAGE ANY THIRD-PARTY TO CONDUCT ADDITIONAL TESTING, THE CONTRACTOR SHALL COOPERATE WITH AND PROVIDE A WORK AREA FOR COMPANY'S TEST AGENCY.

3.4 DIMENSIONS: VERIFY DIMENSIONS INDICATED ON DRAWINGS WITH FIELD DIMENSIONS BEFORE FABRICATION OR ORDERING OF MATERIALS. DO NOT SCALE DRAWINGS.

3.5 EXISTING CONDITIONS: NOTIFY THE SPRINT CONSTRUCTION MANAGER OF EXISTING CONDITIONS DIFFERENT FROM THOSE INDICATED ON THE DRAWINGS. DO NOT REMOVE OR ALTER STRUCTURAL COMPONENTS WITHOUT PRIOR WRITTEN APPROVAL FROM THE ARCHITECT AND ENGINEER.

SECTION 01 200 – COMPANY FURNISHED MATERIAL AND EQUIPMENT

PART 1 – GENERAL

1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

1.2 RELATED DOCUMENTS:

- A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
- B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.

PART 2 – PRODUCTS (NOT USED)

PART 3 – EXECUTION

3.1 RECEIPT OF MATERIAL AND EQUIPMENT:

- A. A COMPANY FURNISHED MATERIAL AND EQUIPMENT IS IDENTIFIED ON THE RF DATA SHEET IN THE CONSTRUCTION DOCUMENTS.
- B. THE CONTRACTOR IS RESPONSIBLE FOR SPRINT PROVIDED MATERIAL AND EQUIPMENT AND UPON RECEIPT SHALL:
 - 1. ACCEPT DELIVERIES AS SHIPPED AND TAKE RECEIPT.
 - 2. VERIFY COMPLETENESS AND CONDITION OF ALL DELIVERIES.
 - 3. TAKE RESPONSIBILITY FOR EQUIPMENT AND PROVIDE INSURANCE PROTECTION AS REQUIRED IN AGREEMENT.
 - 4. RECORD ANY DEFECTS OR DAMAGES AND WITHIN TWENTY-FOUR HOURS AFTER RECEIPT, REPORT TO SPRINT OR ITS DESIGNATED PROJECT REPRESENTATIVE OF SUCH.
 - 5. PROVIDE SECURE AND NECESSARY WEATHER PROTECTED WAREHOUSING.
 - 6. COORDINATE SAFE AND SECURE TRANSPORTATION OF MATERIAL AND EQUIPMENT, DELIVERING AND OFF-LOADING FROM CONTRACTOR'S WAREHOUSE TO SITE.

3.2 DELIVERABLES:

- A. COMPLETE SHIPPING AND RECEIPT DOCUMENTATION IN ACCORDANCE WITH COMPANY PRACTICE.
- B. IF APPLICABLE, COMPLETE LOST/STOLEN/DAMAGED DOCUMENTATION REPORT AS NECESSARY IN ACCORDANCE WITH COMPANY PRACTICE, AND AS DIRECTED BY COMPANY.
- C. UPLOAD DOCUMENTATION INTO SPRINT SITE MANAGEMENT SYSTEM (SMS) AND/OR PROVIDE HARD COPY DOCUMENTATION AS REQUESTED.

SECTION 01 300 – CELL SITE CONSTRUCTION CO.

PART 1 – GENERAL

1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

1.2 RELATED DOCUMENTS:

- A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
- B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.

1.3 NOTICE TO PROCEED

- A. NO WORK SHALL COMMENCE PRIOR TO COMPANY'S WRITTEN NOTICE TO PROCEED AND THE ISSUANCE OF THE WORK ORDER.
- B. UPON RECEIVING NOTICE TO PROCEED, CONTRACTOR SHALL FULLY PERFORM ALL WORK NECESSARY TO PROVIDE SPRINT WITH AN OPERATIONAL WIRELESS FACILITY.

PART 2 – PRODUCTS (NOT USED)

PART 3 – EXECUTION

3.1 FUNCTIONAL REQUIREMENTS:

- A. THE ACTIVITIES DESCRIBED IN THIS PARAGRAPH REPRESENT MINIMUM ACTIONS AND PROCESSES REQUIRED TO SUCCESSFULLY COMPLETE THE WORK. THE ACTIVITIES DESCRIBED ARE NOT EXHAUSTIVE, AND CONTRACTOR SHALL TAKE ANY AND ALL ACTIONS AS NECESSARY TO SUCCESSFULLY COMPLETE THE CONSTRUCTION OF A FULLY FUNCTIONING WIRELESS FACILITY AT THE SITE IN ACCORDANCE WITH COMPANY PROCESSES.
- B. SUBMIT SPECIFIC DOCUMENTATION AS INDICATED HEREIN, AND OBTAIN REQUIRED APPROVALS WHILE THE WORK IS BEING PERFORMED.
- C. MANAGE AND CONDUCT ALL FIELD CONSTRUCTION SERVICE RELATED ACTIVITIES
- D. PROVIDE CONSTRUCTION ACTIVITIES TO THE EXTENT REQUIRED BY THE CONTRACT DOCUMENTS, INCLUDING BUT NOT LIMITED TO THE FOLLOWING:


PLANS PREPARED FOR:




PROJECT MANAGER:



PLANS PREPARED BY:



ENGINEERING LICENSE:



CHECKED BY:

APPROVED BY:

REVISIONS:	DESCRIPTION	DATE	BY REV.

ISSUED FOR CONSTRUCTION 04/10/18 SL 0

SITE NUMBER:

CT03XC107

SITE ADDRESS:


2 TAUGWONK SPUR
STONINGTON, CT 06389

SHEET DESCRIPTION:

OUTLINE SPECIFICATIONS

SHEET NUMBER:

SP-1



CHECKED BY: _____

APPROVED BY: _____

REVISIONS:	DESCRIPTION	DATE	BY REV.

ISSUED FOR CONSTRUCTION 04/10/18 SL 0

SITE NUMBER: CT03XC107

SITE ADDRESS: 2 TAUGWONK SPUR STONINGTON, CT 06389

SHEET DESCRIPTION: OUTLINE SPECIFICATIONS

SHEET NUMBER: SP-2

PLANS PREPARED FOR:

CONTINUE FROM SP-1

1. PERFORM ANY REQUIRED SITE ENVIRONMENTAL MITIGATION.
2. PREPARE GROUND SITES; PROVIDE DE-GRUBBING; AND ROUGH AND FINAL GRADING, AND COMPOUND SURFACE TREATMENTS.
3. MANAGE AND CONDUCT ALL ACTIVITIES FOR INSTALLATION OF UTILITIES INCLUDING ELECTRICAL AND TELCO BACKHAUL.
4. INSTALL UNDERGROUND FACILITIES INCLUDING UNDERGROUND POWER AND COMMUNICATIONS CONDUITS, AND UNDERGROUND GROUNDING SYSTEM.
5. INSTALL ABOVE GROUND GROUNDING SYSTEMS.
6. PROVIDE NEW HVAC INSTALLATIONS AND MODIFICATIONS.
7. INSTALL "H-FRAMES", CABINETS AND SHELTERS AS INDICATED.
8. INSTALL ROADS, ACCESS WAYS, CURBS AND DRAINS AS INDICATED.
9. ACCOMPLISH REQUIRED MODIFICATION OF EXISTING FACILITIES.
10. PROVIDE ANTENNA SUPPORT STRUCTURE FOUNDATIONS.
11. PROVIDE SLABS AND EQUIPMENT PLATFORMS.
12. INSTALL COMPOUND FENCING, SIGHT SHIELDING, LANDSCAPING AND ACCESS BARRIERS.
13. PERFORM INSPECTION AND MATERIAL TESTING AS REQUIRED HEREINAFTER.
14. CONDUCT SITE RESISTANCE TO EARTH TESTING AS REQUIRED HEREINAFTER.
15. INSTALL FIXED GENERATOR SETS AND OTHER STANDBY POWER SOLUTIONS.
16. INSTALL TOWERS, ANTENNA SUPPORT STRUCTURES AND PLATFORMS ON EXISTING TOWERS AS REQUIRED.
17. INSTALL CELL SITE RADIOS, MICROWAVE, GPS, COAXIAL MAINLINE, ANTENNAS, CROSS BAND COUPLERS, TOWER TOP AMPLIFIERS, LOW NOISE AMPLIFIERS AND RELATED EQUIPMENT.
18. PERFORM, DOCUMENT, AND CLOSE OUT ANY CONSTRUCTION CONTROL DOCUMENTS THAT MAY BE REQUIRED BY GOVERNMENT AGENCIES AND LANDLORDS.
19. PERFORM ANTENNA AND COAX SWEEP TESTING AND MAKE ANY AND ALL NECESSARY CORRECTIONS.
20. REMAIN ON SITE MOBILIZED THROUGHOUT HAND-OFF AND INTEGRATION TO ASSIST AS NEEDED UNTIL SITE IS DEEMED SUBSTANTIALLY COMPLETE AND PLACED "ON AIR."

3.2 GENERAL REQUIREMENTS FOR CIVIL CONSTRUCTION:

- A. CONTRACTOR SHALL KEEP THE SITE FREE FROM ACCUMULATING WASTE MATERIAL, DEBRIS, AND TRASH. AT THE COMPLETION OF THE WORK, CONTRACTOR SHALL REMOVE FROM THE SITE ALL REMAINING RUBBISH, IMPLEMENTS, TEMPORARY FACILITIES, AND SURPLUS MATERIALS.
- B. EQUIPMENT ROOMS SHALL AT ALL TIMES BE MAINTAINED "BROOM CLEAN" AND CLEAR OF DEBRIS.
- C. CONTRACTOR SHALL TAKE ALL REASONABLE PRECAUTIONS TO DISCOVER AND LOCATE ANY HAZARDOUS CONDITION.
 1. IN THE EVENT CONTRACTOR ENCOUNTERS ANY HAZARDOUS CONDITION WHICH HAS NOT BEEN ABATED OR OTHERWISE MITIGATED, CONTRACTOR AND ALL OTHER PERSONS SHALL IMMEDIATELY STOP WORK IN THE AFFECTED AREA AND NOTIFY COMPANY IN WRITING. THE WORK IN THE AFFECTED AREA SHALL NOT BE RESUMED EXCEPT BY WRITTEN NOTIFICATION BY COMPANY.
 2. CONTRACTOR AGREES TO USE CARE WHILE ON THE SITE AND SHALL NOT TAKE ANY ACTION THAT WILL OR MAY RESULT IN OR CAUSE THE HAZARDOUS CONDITION TO BE FURTHER RELEASED IN THE ENVIRONMENT, OR TO FURTHER EXPOSE INDIVIDUALS TO THE HAZARD.
- D. CONTRACTOR'S ACTIVITIES SHALL BE RESTRICTED TO THE PROJECT LIMITS. SHOULD AREAS OUTSIDE THE PROJECT LIMITS BE Affected BY CONTRACTOR'S ACTIVITIES, CONTRACTOR SHALL IMMEDIATELY RETURN THEM TO ORIGINAL CONDITION
- E. CONDUCT TESTING AS REQUIRED HEREIN.

3.3 DELIVERABLES:

- A. CONTRACTOR SHALL REVIEW, APPROVE, AND SUBMIT TO SPRINT SHOP DRAWINGS, PRODUCT DATA, SAMPLES, AND SIMILAR SUBMITTALS AS REQUIRED HEREINAFTER
- B. PROVIDE DOCUMENTATION INCLUDING, BUT NOT LIMITED TO, THE FOLLOWING. DOCUMENTATION SHALL BE FORWARDED IN ORIGINAL FORMAT AND/OR UPLOADED INTO SMS.
 1. ALL CORRESPONDENCE AND PRELIMINARY CONSTRUCTION REPORTS.
 2. PROJECT PROGRESS REPORTS.
 3. CIVIL CONSTRUCTION START DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
 4. ELECTRICAL SERVICE COMPLETION DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).

5. LINES AND ANTENNA INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
6. POWER INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
7. TELCO READY DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
8. PPC (OR SHELTER) INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
9. TOWER CONSTRUCTION START DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
10. TOWER CONSTRUCTION COMPLETE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
11. BTS AND RADIO EQUIPMENT DELIVERED AT SITE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
12. NETWORK OPERATIONS HANDOFF CHECKLIST (HOC WALK) COMPLETE (UPLOAD FORM IN SMS)
13. CIVIL CONSTRUCTION COMPLETE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
14. SITE CONSTRUCTION PROGRESS PHOTOS UNLOADED INTO SMS.

SECTION 01 400 – SUBMITTALS & TESTS

PART 1 – GENERAL

- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
 - A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
 - B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITHE.
- 1.3 SUBMITTALS:
 - A. THE WORK IN ALL ASPECTS SHALL COMPLY WITH THE CONSTRUCTION DRAWINGS AND THESE SPECIFICATIONS.
 - B. SUBMIT THE FOLLOWING TO COMPANY REPRESENTATIVE FOR APPROVAL.
 1. CONCRETE MIX-DESIGNS FOR TOWER FOUNDATIONS, ANCHORS PIERS, AND CONCRETE PAVING.
 2. CONCRETE BREAK TESTS AS SPECIFIED HEREIN.
 3. SPECIAL FINISHES FOR INTERIOR SPACES, IF ANY.
 4. ALL EQUIPMENT AND MATERIALS SO IDENTIFIED ON THE CONSTRUCTION DRAWINGS.
 5. CHEMICAL GROUNDING DESIGN
 - D. ALTERNATES: AT THE COMPANY'S REQUEST, ANY ALTERNATIVES TO THE MATERIALS OR METHODS SPECIFIED SHALL BE SUBMITTED TO SPRINT'S CONSTRUCTION MANAGER FOR APPROVAL PRIOR TO BEING SHIPPED TO SITE. SPRINT WILL REVIEW AND APPROVE ONLY THOSE REQUESTS MADE IN WRITING. NO VERBAL APPROVALS WILL BE CONSIDERED. SUBMITTAL FOR APPROVAL SHALL INCLUDE A STATEMENT OF COST REDUCTION PROPOSED FOR USE OF ALTERNATE PRODUCT.

1.4 TESTS AND INSPECTIONS:

- A. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CONSTRUCTION TESTS, INSPECTIONS AND PROJECT DOCUMENTATION.
- B. CONTRACTOR SHALL ACCOMPLISH TESTING INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
 1. COAX SWEEPS AND FIBER TESTS PER TS-0200 REV 4 ANTENNA LINE ACCEPTANCE STANDARDS.
 2. AGL, AZIMUTH AND DOWNTILT USING ELECTRONIC COMMERCIAL MADE-FOR-THE-PURPOSE ANTENNA ALIGNMENT TOOL.
 3. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN SITE INSPECTION ACTIVITIES AND/OR AS A RESULT OF TESTING.
- C. REQUIRED CLOSEOUT DOCUMENTATION INCLUDES, BUT IS NOT LIMITED TO THE FOLLOWING:
 1. AZIMUTH, DOWNTILT, AGL – UPLOAD REPORT FROM ANTENNA ALIGNMENT TOOL TO SITERRA TASK 465. INSTALLED AZIMUTH, DOWNTILT, AND AGL MUST CONFORM TO THE RF DATA SHEETS. SWEEP AND FIBER TESTS
 2. SCANABLE BARCODE PHOTOGRAPHS OF TOWER TOP AND INACCESSIBLE SERIALIZED EQUIPMENT
 3. ALL AVAILABLE JURISDICTIONAL INFORMATION
 4. PDF SCAN OF REDLINES PRODUCED IN FIELD

5. ELECTRONIC AS-BUILT DRAWINGS IN AUTOCAD AND PDF FORMATS. ANY FIELD CHANGE MUST BE REFLECTED BY MODIFYING THE PLANS, ELEVATIONS, AND DETAILS IN THE DRAWING SETS. GENERAL NOTES INDICATING MODIFICATIONS WILL NOT BE ACCEPTED. CHANGES SHALL BE HIGHLIGHTED AS "CLOUDS" IDENTIFIED AS THE "AS-BUILT" CONDITION.
6. LIEN WAIVERS
7. FINAL PAYMENT APPLICATION
8. REQUIRED FINAL CONSTRUCTION PHOTOS
9. CONSTRUCTION AND COMMISSIONING CHECKLIST COMPLETE WITH NO DEFICIENT ITEMS
10. ALL POST NTP TASKS INCLUDING DOCUMENT UPLOADS COMPLETED IN SITERRA (SPRINT'S DOCUMENT REPOSITORY OF RECORD).
- 1.5 COMMISSIONING: PERFORM ALL COMMISSIONING AS REQUIRED BY APPLICABLE MOPs
- 1.6 INTEGRATION: PERFORM ALL INTEGRATION ACTIVITIES AS REQUIRED BY APPLICABLE MOPs

PART 2 – PRODUCTS (NOT USED)

PART 3 – EXECUTION

3.1 REQUIREMENTS FOR TESTING:

- A. THIRD PARTY TESTING AGENCY:
 1. WHEN THE USE OF A THIRD PARTY INDEPENDENT TESTING AGENCY IS REQUIRED, THE AGENCY THAT IS SELECTED MUST PERFORM SUCH WORK ON A REGULAR BASIS IN THE STATE WHERE THE PROJECT IS LOCATED AND HAVE A THOROUGH UNDERSTANDING OF LOCAL AVAILABLE MATERIALS, INCLUDING THE SOIL, ROCK, AND GROUNDWATER CONDITIONS.
 2. THE THIRD PARTY TESTING AGENCY IS TO BE FAMILIAR WITH THE APPLICABLE REQUIREMENTS FOR THE TESTS TO BE DONE, EQUIPMENT TO BE USED, AND ASSOCIATED HEALTH AND SAFETY ISSUES.
 3. EXPERIENCE IN SOILS, CONCRETE, MASONRY, AGGREGATE, AND ASPHALT TESTING USING ASTM, AASHTO, AND OTHER METHODS IS NEEDED.
 4. EXPERIENCE IN SOILS, CONCRETE, MASONRY, AGGREGATE, AND ASPHALT TESTING USING ASTM, AASHTO, AND OTHER METHODS IS NEEDED.
- 3.2 REQUIRED TESTS:
 - A. CONTRACTOR SHALL ACCOMPLISH TESTING INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
 1. CONCRETE CYLINDER BREAK TESTS FOR THE TOWER AND ANCHOR FOUNDATIONS AS SPECIFIED IN SECTION: PORTLAND CEMENT CONCRETE PAVING.
 2. ASPHALT ROADWAY COMPACTED THICKNESS, SURFACE SMOOTHNESS, AND COMPACTED DENSITY TESTING AS SPECIFIED IN SECTION: HOT MIX ASPHALT PAVING.
 3. FIELD QUALITY CONTROL TESTING AS SPECIFIED IN SECTION: PORTLAND CEMENT CONCRETE PAVING.
 4. TESTING REQUIRED UNDER SECTION: AGGREGATE BASE FOR ACCESS ROADS, PADS AND ANCHOR LOCATIONS
 5. STRUCTURAL BACKFILL COMPACTION TESTS FOR THE TOWER FOUNDATION.
 6. SITE RESISTANCE TO EARTH TESTING PER EXHIBIT: CELL SITE GROUNDING SYSTEM DESIGN.
 7. ANTENNA AND COAX SWEEP TESTS PER EXHIBIT: ANTENNA TRANSMISSION LINE ACCEPTANCE STANDARDS.
 8. GROUNDING AT ANTENNA MASTS FOR GPS AND ANTENNAS
 9. ALL OTHER TESTS REQUIRED BY COMPANY OR JURISDICTION.

3.3 REQUIRED INSPECTIONS


- A. SCHEDULE INSPECTIONS WITH COMPANY REPRESENTATIVE.
- B. CONDUCT INSPECTIONS INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
 1. GROUNDING SYSTEM INSTALLATION PRIOR TO EARTH CONCEALMENT DOCUMENTED WITH DIGITAL PHOTOGRAPHS BY CONTRACTOR, APPROVED BY A&E OR SPRINT REPRESENTATIVE.
 2. FORMING FOR CONCRETE AND REBAR PLACEMENT PRIOR TO POUR DOCUMENTED WITH DIGITAL PHOTOGRAPHS BY CONTRACTOR, APPROVED BY A&E OR SPRINT REPRESENTATIVE.
 3. COMPACTION OF BACKFILL MATERIALS; AGGREGATE BASE FOR ROADS, PADS, AND ANCHORS; ASPHALT PAVING; AND SHAFT BACKFILL FOR CONCRETE AND WOOD POLES, BY INDEPENDENT THIRD PARTY AGENCY.
 4. PRE- AND POST-CONSTRUCTION ROOFTOP AND STRUCTURAL INSPECTIONS ON EXISTING FACILITIES.
 5. TOWER ERECTION SECTION STACKING AND PLATFORM ATTACHMENT DOCUMENTED BY DIGITAL PHOTOGRAPHS BY THIRD PARTY AGENCY.
 6. ANTENNA AZIMUTH, DOWN TILT AND PER SUNLIGHT TOOL SUNSIGHT INSTRUMENTS – ANTENNALIGN ALIGNMENT TOOL (AAT)




PLANS PREPARED FOR:
Sprint
INTERNATIONAL BLVD, SUITE 800
MAHWAH, NJ 07495
TEL: (800) 357-7641



PROJECT MANAGER:
SBA
SBA COMMUNICATIONS CORP.
134 FLANDERS ROAD, SUITE 125
WESTBOROUGH, MA 01581
TEL: (508) 251-0720



PLANS PREPARED BY:
INFINIGY
FROM ZERO TO INFINIGY
the solutions are endless
1033 Watervliet Shaker Rd | Albany, NY 12205
Phone: 518-690-0790 | Fax: 518-690-0793
www.infinigy.com
JOB NUMBER 526-104



ENGINEERING LICENSE:

CHECKED BY:
APPROVED BY:
REVISIONS: _____ DESCRIPTION: _____ DATE: _____ BY REV: _____

ISSUED FOR CONSTRUCTION 04/10/18 SL 0

SITE NUMBER:
CT03XC107

SITE ADDRESS:
2 TAUGWONK SPUR STONINGTON, CT 06389

SHEET DESCRIPTION:
OUTLINE SPECIFICATIONS

SHEET NUMBER:
SP-3

CONTINUE FROM SP-2

7. VERIFICATION DOCUMENTED WITH THE ANTENNA CHECKLIST REPORT, BY A&E, SITE DEVELOPMENT REP, OR RF REP.
8. FINAL INSPECTION CHECKLIST AND HANDOFF WALK (HOC). SIGNED FORM SHOWING ACCEPTANCE BY FIELD OPS IS TO BE UPLOADED INTO SMS.
9. COAX SWEEP AND FIBER TESTING DOCUMENTS SUBMITTED VIA SMS FOR RF APPROVAL.
10. SCAN-ABLE BARCODE PHOTOGRAPHS OF TOWER TOP AND INACCESSIBLE SERIALIZED EQUIPMENT
11. ALL AVAILABLE JURISDICTIONAL INFORMATION
12. PDF SCAN OF REDLINES PRODUCED IN FIELD
- C. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN SITE INSPECTION ACTIVITIES AND/OR AS A RESULT OF TESTING.
- D. CONSTRUCTION INSPECTIONS AND CORRECTIVE MEASURES SHALL BE DOCUMENTED BY THE CONTRACTOR WITH WRITTEN REPORTS AND PHOTOGRAPHS. PHOTOGRAPHS MUST BE DIGITAL AND OF SUFFICIENT QUALITY TO CLEARLY SHOW THE SITE CONSTRUCTION. PHOTOGRAPHS MUST CLEARLY IDENTIFY THE PHOTOGRAPHED ITEM AND BE LABELED WITH THE SITE CASCADE NUMBER, SITE NAME, DESCRIPTION, AND DATE.
- 3.4 DELIVERABLES: TEST AND INSPECTION REPORTS AND CLOSEOUT DOCUMENTATION SHALL BE UPLOADED TO THE SMS AND/OR FORWARDED TO SPRINT FOR INCLUSION INTO THE PERMANENT SITE FILES.
- A. THE FOLLOWING TEST AND INSPECTION REPORTS SHALL BE PROVIDED AS APPLICABLE.
 1. CONCRETE MIX AND CYLINDER BREAK REPORTS.
 2. STRUCTURAL BACKFILL COMPACTION REPORTS.
 3. SITE RESISTANCE TO EARTH TEST.
 4. ANTENNA AZIMUTH AND DOWN TILT VERIFICATION
 5. TOWER ERECTION INSPECTIONS AND MEASUREMENTS DOCUMENTING TOWER INSTALLED PER SUPPLIER'S REQUIREMENTS AND THE APPLICABLE SECTIONS HEREIN.
 6. COAX CABLE SWEEP TESTS PER COMPANY'S "ANTENNA LINE ACCEPTANCE STANDARDS".
- B. REQUIRED CLOSEOUT DOCUMENTATION INCLUDES THE FOLLOWING;
 1. TEST WELLS AND TRENCHES: PHOTOGRAPHS OF ALL TEST WELLS; PHOTOGRAPHS SHOWING ALL OPEN EXCAVATIONS AND TRENCHING PRIOR TO BACKFILLING SHOWING A TAPE MEASURE VISIBLE IN THE EXCAVATIONS INDICATING DEPTH.
 2. CONDUITS, CONDUCTORS AND GROUNDING: PHOTOGRAPHS SHOWING TYPICAL INSTALLATION OF CONDUCTORS AND CONNECTORS; PHOTOGRAPHS SHOWING TYPICAL BEND RADIUS OF INSTALLED GROUND WIRES AND GROUND ROD SPACING;
 3. CONCRETE FORMS AND REINFORCING: CONCRETE FORMING AT TOWER AND EQUIPMENT/SHELTER PAD/FOUNDATIONS – PHOTOGRAPHS SHOWING ALL REINFORCING STEEL, UTILITY AND CONDUIT STUB OUTS; PHOTOGRAPHS SHOWING CONCRETE POUR OF SHELTER SLAB/FOUNDATION, TOWER FOUNDATION AND GUY ANCHORS WITH VIBRATOR IN USE; PHOTOGRAPHS SHOWING EACH ANCHOR ON GUYED TOWERS, BEFORE CONCRETE POUR.
 4. TOWER, ANTENNAS AND MAINLINE: INSPECTION AND PHOTOGRAPHS OF SECTION STACKING; INSPECTION AND PHOTOGRAPHS OF PLATFORM COMPONENT ATTACHMENT POINTS; PHOTOGRAPHS OF TOWER TOP GROUNDING; PHOTOS OF TOWER COAX LINE COLOR CODING AT THE TOP AND AT GROUND LEVEL; INSPECTION AND PHOTOGRAPHS OF OPERATIONAL OF TOWER LIGHTING, AND PLACEMENT OF FAA REGISTRATION SIGN; PHOTOGRAPHS SHOWING ADDITIONAL GROUNDING POINTS FOR TOWERS GREATER THAN 200 FEET.; PHOTOS OF ANTENNA GROUND BAR, EQUIPMENT GROUND BAR, AND MASTER GROUND BAR; PHOTOS OF GPS ANTENNA(S); PHOTOS OF EACH SECTOR OF ANTENNAS; ONE PHOTOGRAPH LOOKING AT THE SECTOR AND ONE FROM BEHIND SHOWING THE PROJECTED COVERAGE AREA; PHOTOS OF COAX WEATHERPROOFING – TOP AND BOTTOM; PHOTOS OF COAX GROUNDING – TOP AND BOTTOM; PHOTOS OF ANTENNA AND MAST GROUNDING; PHOTOS OF COAX CABLE ENTRY INTO SHELTER; PHOTOS OF PLATFORM MECHANICAL CONNECTIONS TO TOWER/MONOPOLE.
 5. ROOF TOPS: PRE-CONSTRUCTION AND POST-CONSTRUCTION VISUAL INSPECTION AND PHOTOGRAPHS OF THE ROOF AND INTERIOR TO DETERMINE AND DOCUMENT CONDITIONS; ROOF TOP CONSTRUCTION INSPECTIONS AS REQUIRED BY THE JURISDICTION; PHOTOGRAPHS OF CABLE TRAY AND/OR ICE BRIDGE; PHOTOGRAPHS OF DOGHOUSE/CABLE EXIT FROM ROOF;
 6. SITE LAYOUT – PHOTOGRAPHS OF THE OVERALL COMPOUND, INCLUDING EQUIPMENT PLATFORM FROM ALL FOUR CORNERS.
 7. FINISHED UTILITIES: CLOSE-UP PHOTOGRAPHS OF THE PPC BREAKER PANEL; CLOSE-UP PHOTOGRAPH OF THE INSIDE OF THE TELCO PANEL AND NIU; CLOSE-UP PHOTOGRAPH OF THE POWER METER AND DISCONNECT; PHOTOS OF POWER AND TELCO ENTRANCE TO COMPANY ENCLOSURE; PHOTOGRAPHS AT METER BOX AND/OR FACILITY DISTRIBUTION PANEL.
 8. REQUIRED MATERIALS CERTIFICATIONS: CONCRETE MIX DESIGNS; MILL CERTIFICATION FOR ALL REINFORCING AND STRUCTURAL STEEL; AND ASPHALT PAVING MIX DESIGN.
 9. ANY AND ALL SUBMITTALS BY THE JURISDICTION OR COMPANY.

SECTION 01 400 – SUBMITTALS & TESTS

PART 1 – GENERAL

- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
 - A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
 - B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.

PART 2 – PRODUCTS (NOT USED)

PART 3 – EXECUTION

3.1 WEEKLY REPORTS:

- A. CONTRACTOR SHALL PROVIDE SPRINT WITH WEEKLY REPORTS SHOWING PROJECT STATUS. THIS STATUS REPORT FORMAT WILL BE PROVIDED TO THE CONTRACTOR BY SPRINT. THE REPORT WILL CONTAIN SITE ID NUMBER, THE MILESTONES FOR EACH SITE, INCLUDING THE BASELINE DATE, ESTIMATED COMPLETION DATE AND ACTUAL COMPLETION DATE.
- B. REPORT INFORMATION WILL BE TRANSMITTED TO SPRINT VIA ELECTRONIC MEANS AS REQUIRED. THIS INFORMATION WILL PROVIDE A BASIS FOR PROGRESS MONITORING AND PAYMENT.

3.2 PROJECT CONFERENCE CALLS:

- A. SPRINT MAY HOLD WEEKLY PROJECT CONFERENCE CALLS. CONTRACTOR WILL BE REQUIRED TO COMMUNICATE SITE STATUS, MILESTONE COMPLETIONS AND UPCOMING MILESTONE PROJECTIONS, AND ANSWER ANY OTHER SITE STATUS QUESTIONS AS NECESSARY.

3.3 PROJECT TRACKING IN SMS:

- A. CONTRACTOR SHALL PROVIDE SCHEDULE UPDATES AND PROJECTIONS IN THE SMS SYSTEM ON A WEEKLY BASIS.


3.4 ADDITIONAL REPORTING:

- A. ADDITIONAL OR ALTERNATE REPORTING REQUIREMENTS MAY BE ADDED TO THE REPORT AS DETERMINED TO BE REASONABLY NECESSARY BY COMPANY.

3.5 PROJECT PHOTOGRAPHS:

- A. FILE DIGITAL PHOTOGRAPHS OF COMPLETED SITE IN JPEG FORMAT IN THE SMS PHOTO LIBRARY FOR THE RESPECTIVE SITE. PHOTOGRAPHS SHALL BE CLEARLY LABELED WITH SITE NUMBER, NAME AND DESCRIPTION, AND SHALL INCLUDE AT A MINIMUM THE FOLLOWING AS APPLICABLE:

1. TOWER AND TOWER OVERVIEW.
2. TOWER FOUNDATION(S) – FORMS AND STEEL BEFORE POUR (EACH ANCHOR ON GUYED TOWERS).
3. TOWER FOUNDATION(S) POUR WITH VIBRATOR IN USE (EACH ANCHOR ON GUYED TOWERS).
4. TOWER STEEL AS BEING INSTALLED INTO HOLE (SHOW ANCHOR STEEL ON GUYED TOWERS).
5. PHOTOS OF TOWER SECTION STACKING.
6. CONCRETE TESTING / SAMPLES.
7. PLACING OF ANCHOR BOLTS IN TOWER FOUNDATION.
8. BUILDING/WATER TANK FROM ROAD FOR TENANT IMPROVEMENTS OR COMMENTS.
9. SHELTER FOUNDATION – FORMS AND STEEL BEFORE POURING.
10. SHELTER FOUNDATION POUR WITH VIBRATOR IN USE.
11. COAX CABLE ENTRY INTO SHELTER.
12. PLATFORM MECHANICAL CONNECTIONS TO TOWER/MONOPOLE.
13. ROOFTOP PRE AND POST CONSTRUCTION PHOTOS TO INCLUDE PENETRATIONS AND INTERIOR CEILING.
14. PHOTOS OF TOWER TOP COAX LINE COLOR CODING AND COLOR CODING AT GROUND LEVEL.
15. PHOTOS OF ALL APPROPRIATE COMPANY OR REGULATORY SIGNAGE.
16. PHOTOS OF EQUIPMENT BOLT DOWN INSIDE SHELTER.
17. POWER AND TELCO ENTRANCE TO COMPANY ENCLOSURE AND POWER AND TELCO SUPPLY LOCATIONS INCLUDING METER/DISCONNECT.
18. ELECTRICAL TRENCH(S) WITH ELECTRICAL / CONDUIT BEFORE BACKFILL.
19. ELECTRICAL TRENCH(S) WITH FOIL-BACKED TAPE BEFORE FURTHER BACKFILL.
20. TELCO TRENCH WITH TELEPHONE / CONDUIT BEFORE BACKFILL.
21. TELCO TRENCH WITH FOIL-BACKED TAPE BEFORE FURTHER BACKFILL.
22. SHELTER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADII).
23. TOWER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADII).



CHECKED BY:

APPROVED BY:

REVISIONS:	DESCRIPTION	DATE	BY REV.



ISSUED FOR CONSTRUCTION 04/10/18 SL 0


SITE NUMBER:
CT03XC107

SITE ADDRESS:
**2 TAUGWONK SPUR
STONINGTON, CT 06389**

SHEET DESCRIPTION:
SITE PLAN

SHEET NUMBER:
A-1





CHECKED BY: _____

APPROVED BY: _____

REVISIONS:	DESCRIPTION	DATE	BY REV.



ISSUED FOR CONSTRUCTION 04/10/18 SL 0






SITE NUMBER: CT03XC107

SITE ADDRESS: 2 TAUGWONK SPUR STONINGTON, CT 06389



SHEET DESCRIPTION: TOWER ELEVATION

SHEET NUMBER: A-2







CHECKED BY:	
APPROVED BY:	
REVISIONS:	DESCRIPTION DATE BY REV.
ISSUED FOR CONSTRUCTION	04/10/18 SL 0
SITE NUMBER:	CT03XC107
SITE ADDRESS:	2 TAUGWONK SPUR STONINGTON, CT 06389
SHEET DESCRIPTION:	ANTENNA LAYOUT & MOUNTING DETAILS
SHEET NUMBER:	A-3



ANTENNA SPECIFICATIONS	
MANUF.	COMMSCOPE
MODEL #	NNVV-65B-R4
HEIGHT	72"
WIDTH	19.6"
DEPTH	7.8"
WEIGHT	84.7± LBS.



ANTENNA SPECIFICATIONS	
MANUF.	RFS
MODEL #	APXVTM14-ALU-I20
HEIGHT	56.3"
WIDTH	12.6"
DEPTH	6.3"
WEIGHT	56.2± LBS.



2.5 GHZ RRH SPECIFICATIONS	
MANUF.	NOKIA (ALU)
MODEL #	TD-RRH8X20-25
HEIGHT	26.1"
WIDTH	18.6"
DEPTH	6.7"
WEIGHT	70± LBS.

ANTENNA DETAIL

NO SCALE

1

ANTENNA DETAIL





NO SCALE

2

2.5 RRH

NO SCALE

3



800 MHZ RRH SPECIFICATIONS	
MANUF.	NOKIA (ALU)
MODEL #	800MHZ 2X50W
HEIGHT	19.7"
WIDTH	13"
DEPTH	10.8"
WEIGHT	53± LBS

1900 MHZ RRH SPECIFICATIONS	
MANUF.	NOKIA (ALU)
MODEL #	1900 4X45 65MHz
HEIGHT	25"
WIDTH	11.1"
DEPTH	11.4"
WEIGHT	60± LBS

DUAL RRH MOUNT DETAIL

NO SCALE

4

800 MHZ RRH

NO SCALE



5

1900 MHz RRH (EXISTING TO BE RELOCATED)

NO SCALE

6

A-4



RFS HYBRIFLEX RISER CABLE SCHEDULE

Fiber Only (Existing DC Power)	Hybrid cable MN: HB058-M12-050F 12x multi-mode fiber pairs, Top: Outdoor protected connectors, Bottom: LC Connectors, 5/8 cable, 50 ft	50 ft
	MN: HB058-M12-075F	75 ft
	MN: HB058-M12-100F	100 ft
	MN: HB058-M12-125F	125 ft
	MN: HB058-M12-150F	150 ft
	MN: HB058-M12-175F	175 ft
	MN: HB058-M12-200F	200 ft

8 AWG Power	Hybrid cable MN: HB114-08U3M12-050F 3x 8 AWG power pairs, 12x multi-mode fiber pairs, Outdoor rated connectors & LC Connectors, 1 1/4 cable, 50 ft	50 ft
	MN: HB114-08U3M12-075F	75 ft
	MN: HB114-08U3M12-100F	100 ft
	MN: HB114-08U3M12-125F	125 ft
	MN: HB114-08U3M12-150F	150 ft
	MN: HB114-08U3M12-175F	175 ft
	MN: HB114-08U3M12-200F	200 ft

6 AWG Power	Hybrid cable MN: HB114-13U3M12-225F 3x 6 AWG power pair, 12x multi-mode fiber pairs, Outdoor rated connectors & LC Connectors, 1 1/4 cable, 225 ft	225 ft
	MN: HB114-13U3M12-250F	250 ft
	MN: HB114-13U3M12-275F	275 ft
	MN: HB114-13U3M12-300F	300 ft

4 AWG Power	Hybrid cable MN: HB114-21U3M12-325F 3x 4 AWG power pair, 12x multi-mode fiber pairs, Outdoor rated connectors & LC Connectors, 1 1/4 cable, 325 ft	325 ft
	MN: HB114-21U3M12-350F	350 ft
	MN: HB114-21U3M12-375F	375 ft

RFS HYBRIFLEX JUMPER CABLE SCHEDULE

Fiber Only	Hybrid Jumper cable MN: HBF012-M3-5F1 5 ft, 3x multi-mode fiber pairs, Outdoor & LC connectors, 1/2 cable	5 ft
	MN: HBF012-M3-10F1	10 ft
	MN: HBF012-M3-15F1	15 ft
	MN: HBF012-M3-20F1	20 ft
	MN: HBF012-M3-25F1	25 ft
	MN: HBF012-M3-30F1	30 ft



8 AWG Power	Hybrid Jumper cable MN: HBF058-08U1M3-5F1 5 ft, 1x 8 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 5/8 cable	5 ft
	MN: HBF058-08U1M3-10F1	10 ft
	MN: HBF058-08U1M3-15F1	15 ft
	MN: HBF058-08U1M3-20F1	20 ft
	MN: HBF058-08U1M3-25F1	25 ft
	MN: HBF058-08U1M3-30F1	30 ft

6 AWG Power	Hybrid Jumper cable MN: HBF058-13U1M3-5F1 5 ft, 1x 6 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 5/8 cable	5 ft
	MN: HBF058-13U1M3-10F1	10 ft
	MN: HBF058-13U1M3-15F1	15 ft
	MN: HBF058-13U1M3-20F1	20 ft
	MN: HBF058-13U1M3-25F1	25 ft
	MN: HBF058-13U1M3-30F1	30 ft


4 AWG Power	Hybrid Jumper cable MN: HBF078-21U1M3-5F1 5 ft, 1x 4 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 7/8 cable	5 ft
	MN: HBF078-21U1M3-10F1	10 ft
	MN: HBF078-21U1M3-15F1	15 ft
	MN: HBF078-21U1M3-20F1	20 ft
	MN: HBF078-21U1M3-25F1	25 ft
	MN: HBF078-21U1M3-30F1	30 ft

NOTE:
 SPRINT CM TO CONFIRM HYBRID OR FIBER RISER CABLE
 AND HYBRID OR FIBER JUMPER CABLE MODEL NUMBERS IF
 HYBRID CABLES ARE REQUIRED BEFORE PREPARING BOM.

- * PROPOSED CABLE LENGTH WAS DETERMINED USING THE SUM OF THE RAD CENTER OF ANTENNAS, AND DISTANCE FROM EXISTING EQUIPMENT AREA TO TOWER BASE WITH AN ADDITIONAL 20' BUFFER. LENGTH TO BE VERIFIED IN FIELD PRIOR TO ORDERING MATERIALS.
- * SPRINT CM TO CONFIRM HYBRID RISER CABLE AND HYBRID JUMPER CABLE MODEL NUMBERS BEFORE PREPARING BOM.






8 & 6 AWG



FIBER ONLY






1. APPLY NO-OX TO LUG AND BAR CONTACT SURFACE. DO NOT COAT INLINE LUG.
2. IF STOLEN GROUND BARS ARE ENCOUNTERED, CONTACT SPRINT CM FOR REPLACEMENT THREADED ROD KIT.

INSTALLATION OF GROUNDING CONDUCTOR TO GROUNDING BAR

SCALE: N.T.S.

2
E-1



SCALE: N.T.S.

3
E-1

ELECTRICAL & GROUNDING DETAILS

NO SCALE 1

ELECTRICAL NOTES

- 1) ALL ELECTRICAL WORK SHALL CONFORM TO THE REQUIREMENTS OF THE NATIONAL ELECTRICAL CODE (NEC) AS WELL AS APPLICABLE STATE AND LOCAL CODES.
- 2) THE ELECTRICAL CONTRACTOR SHALL COORDINATE ALL CONDUIT ROUTING WITH LOCAL UTILITY COMPANIES AND SPRINT CONSTRUCTION MANAGER.
- 3) ALL CONDUITS ROUTED BELOW GRADE SHALL TRANSITION TO RIGID GALVANIZED STEEL ELBOWS WITH RIGID GALVANIZED STEEL CONDUIT ABOVE GRADE.
- 4) ALL METAL CONDUITS SHALL BE PROVIDED WITH GROUNDING BUSHSINGS.
- 5) GENERAL CONTRACTOR SHALL PROVIDE ALL DIRECT BURIED CONDUITS WITH PLASTIC WARNING TAPE IDENTIFYING CONTENTS. TAPE COLORS SHALL BE ORANGE FOR TELEPHONE AND RED FOR ELECTRIC.
- 6) ALL ELECTRICAL ITEMS SHALL BE U.L. APPROVED OR LISTED AND PROCURED PER SPECIFICATION REQUIREMENTS.
- 7) THE ELECTRICAL WORK INCLUDES ALL LABOR AND MATERIALS DESCRIBED BY DRAWINGS AND SPECIFICATIONS INCLUDING INCIDENTAL WORK TO PROVIDE COMPLETE OPERATING AND APPROVED ELECTRICAL SYSTEM.
- 8) GENERAL CONTRACTOR SHALL PAY FEES FOR PERMITS, AND IS RESPONSIBLE FOR OBTAINING SAID PERMITS AND COORDINATION OF INSPECTIONS.
- 9) ELECTRICAL AND TELCO WIRING OUTSIDE A BUILDING AND EXPOSED TO WEATHER SHALL BE IN WATER TIGHT GALVANIZED RIGID STEEL CONDUITS OR SCHEDULE 80 PVC (AS PERMITTED BY CODE) AND WHERE REQUIRED IN LIQUID TIGHT FLEXIBLE METAL OR NONMETALLIC CONDUITS.
- 10) BURIED CONDUIT SHALL BE SCHEDULE 40 PVC.
- 11) ELECTRICAL WIRING SHALL BE COPPER WITH TYPE XHHW, THWN, OR THIN INSULATION.
- 12) RUN ELECTRICAL CONDUIT OR CABLE BETWEEN ELECTRICAL UTILITY DEMARCTION POINT AND PROJECT OWNER CELL SITE PPC AS INDICATED ON THIS DRAWING. PROVIDE FULL LENGTH PULL ROPE. COORDINATE INSTALLATION WITH UTILITY COMPANY.
- 13) RUN TELCO CONDUIT OR CABLE BETWEEN TELEPHONE UTILITY DEMARCTION POINT AND PROJECT OWNER CELL SITE TELCO CABINET AND BTS CABINET AS INDICATED ON THIS DRAWING. PROVIDE FULL LENGTH PULL ROPE IN INSTALLED TELCO CONDUIT. PROVIDE GREENLEE CONDUIT MEASURING TAPE AT EACH END.
- 14) FIBER OPTIC CIRCUITS SHALL BE IN ACCORDANCE WITH NEC ARTICLE 770—OPTICAL FIBER CABLES AND RACEWAYS.
- 15) COMMUNICATIONS CIRCUITS SHALL BE IN ACCORDANCE WITH NEC ARTICLE 800—COMMUNICATIONS SYSTEMS.

PROTECTIVE GROUNDING SYSTEMS GENERAL NOTES:

1. GROUNDING SHALL BE IN ACCORDANCE WITH NEC ARTICLE 250-GROUNDING AND BONDING.

1. GROUNDING SHALL BE IN ACCORDANCE WITH SPRINT SSO DOCUMENTS 3.018.02.004 "BONDING, GROUNDING AND TRANSIENT PROTECTION FOR CELL SITES" AND 3.018.10.002 "SITE RESISTANCE TO EARTH TESTING".
3. PROVIDE GROUND CONNECTIONS FOR ALL METALLIC STRUCTURES, ENCLOSURES, RACEWAYS AND OTHER CONDUCTIVE ITEMS ASSOCIATED WITH THE INSTALLATION OF CARRIER'S EQUIPMENT.
4. GROUND CONNECTIONS: CLEAN SURFACES THOROUGHLY BEFORE APPLYING GROUND LUGS OR CLAMPS. IF SURFACE IS COATED, REMOVE THE COATING. APPLY A NON-CORROSIVE APPROVED COMPOUND TO CLEAN SURFACE AND INSTALL LUGS OR CLAMPS. WHERE GALVANIZING IS REMOVED FROM METAL, IT SHALL BE PAINTED OR TOUCHED UP WITH "GALVAMOX" OR EQUAL.
5. ALL GROUND WIRES SHALL PROVIDE A STRAIGHT, DOWNWARD PATH TO GROUND WITH GRADUAL BENDS AS REQUIRED. GROUND WIRES SHALL NOT BE LOOPED OR SHARPLY BENT.
6. ALL CLAMPS AND SUPPORTS USED TO SUPPORT THE GROUNDING SYSTEM CONDUCTORS AND PVC CONDUITS SHALL BE PVC TYPE (NON CONDUCTIVE). DO NOT USE METAL BRACKETS OR SUPPORTS WHICH WOULD FORM A COMPLETE RING AROUND ANY GROUNDING CONDUCTOR.
7. ALL GROUND WIRES SHALL BE #2 SOLID TINNED BCW UNLESS NOTED OTHERWISE.
8. PROVIDE DEDICATED #2 AWG COPPER GROUND WIRE FROM EACH ANTENNA MOUNTING PIPE TO ASSOCIATED CIGBE.
9. GROUND ANTENNA BASES, FRAMES, CABLE RACKS, AND OTHER METALLIC COMPONENTS WITH #2 INSULATED TINNED STRANDED COPPER GROUNDING CONDUCTORS AND CONNECT TO INSULATED SURFACE MOUNTED GROUND BARS. CONNECTION DETAILS SHALL FOLLOW MANUFACTURER'S SPECIFICATIONS FOR GROUNDING.
10. EACH EQUIPMENT CABINET SHALL BE CONNECTED TO THE MASTER ISOLATION GROUND BAR (MGB) WITH #2 SOLID TINNED BCW EQUIPMENT CABINETS WILL HAVE (2) CONNECTIONS.
11. GROUND HYBRIFLEX SHIELD AT TOP, BOTTOM AND AT TRANSITION TO HYBRIFLEX JUMPER CABLES AT EQUIPMENT CABINET ENTRANCE USING MANUFACTURER'S GUIDELINES. WHEN HYBRIFLEX CABLE EXCEEDS 200', GROUND AT INTERVALS NOT EXCEDING 100'.
12. THE CONTRACTOR SHALL VERIFY THAT THE EXISTING GROUND BARS HAVE ENOUGH SPACE/HOLES FOR ADDITIONAL TWO HOLE LUGS.
13. EXOTHERMIC WELDING IS RECOMMENDED FOR GROUNDING CONNECTION WHERE PRACTICAL OTHERWISE. THE CONNECTION SHALL BE MADE USING COMPRESSION TYPE-2 HOLES, LONG BARREL LUGS OR DOUBLE CRIMP "C" CLAMP. THE COPPER CABLES SHALL BE COATED WITH AN ANTI-OXIDANT (THOMAS BETTS KOPR-SHIELD) BEFORE MAKING THE CRIMP CONNECTIONS. THE CONTRACTOR SHALL FOLLOW MANUFACTURER'S RECOMMENDED TORKES ON THE BOLT ASSEMBLY TO SECURE CONNECTIONS.
14. AT ALL TERMINATIONS AT EQUIPMENT ENCLOSURES, PANEL, AND FRAMES OF EQUIPMENT AND WHERE EXPOSED FOR GROUNDING, CONDUCTOR TERMINATION SHALL BE PERFORMED UTILIZING TWO HOLE BOLTED TONGUE COMPRESSION TYPE LUGS WITH STAINLESS STEEL SELF-TAPPING SCREWS.
15. THE MASTER GROUND BAR (MGB) SHALL BE MADE OF BARE 1/4"x2" COPPER (FOR OUTDOOR APPLICATIONS IT SHALL BE TINNED COPPER) AND LARGE ENOUGH TO ACCOMMODATE THE REQUIRED NUMBER OF GROUND CONNECTIONS. THE HARDWARE SECURING THE MGB SHALL ELECTRICAL INSULATE THE MGB FROM ANY STRUCTURE TO WHICH IT IS FASTENED.
16. ALL BOLTS, WASHERS, AND NUTS USED ON GROUNDING CONNECTIONS SHALL BE STAINLESS STEEL.
17. ALL GROUNDING CONNECTIONS SHALL BE COATED WITH A COPPER SHIELD ANTI-CORROSIVE AGENT SUCH AS TAB KOPR SHIELD. VERIFY PRODUCT WITH SPRINT CONSTRUCTION MANAGER.
18. FOR NEW OR REPAIRED GROUNDING EQUIPMENT. REFER TO SPRINT GROUNDING STANDARDS AND FOLLOWING (SUPPLEMENTS):
 - ANTI-THEFT UPDATE TO SPRINT GROUNDING DATED 08-24-12 (OR CURRENT VERSION)
 - SPRINT ENGINEERING LETTER EL-0504 DATED 04-20-12 (OR CURRENT VERSION)

CHECKED BY:

APPROVED BY:

REVISIONS:	DESCRIPTION	DATE	BY REV.
		04/10/18	SL 0

ISSUED FOR CONSTRUCTION 04/10/18 SL 0

SITE NUMBER:

CT03XC107

SITE ADDRESS:

2 TAUGWONK SPUR
STONINGTON, CT 06389

SHEET DESCRIPTION:

ELECTRICAL & GROUNDING DETAILS

SHEET NUMBER:

E-1



RF Design Sheet


PLANS PREPARED FOR:
Sprint
INTERNATIONAL BLVD, SUITE 800
MAHWAH, NJ 07495
TEL: (800) 357-7641

Site Identification	
Cascade	CT03XC107
SMS Schedule ID	12323080
SMS Schedule Name	DO Macro Upgrade
PID	
RRU OEM	ALU
Switch OEM	Alcatel Lucent
RFDS Issue Date	2017-08-15 00:00:00.00
RFDS Revision Date	2017-10-20 09:40:01.0
RFDS Revision	3
Filter Analysis Complete	YES
RFDS - Issue Date	08/15/2017
Design Status	Complete
Project Description	DO Macro Upgrade - Add 800MHz (30+40) and 2500 MHz
Contact Information	
Engineer Email	Bill.M.Hastings@sprint.com
Sprint Badged RF Engineer	Bill Hastings
RF Engineer Email	Bill.M.Hastings@sprint.com
RF Engineer Phone	978-590-9700
RF Manager	Jonathan Hull
RF Manager Email	Jonathan.B.Hull@sprint.com
RF Manager Phone	617-233-2920
Carrier Count	
2500 LTE	3
1900 LTE	1
1900 EVDO	
1900 Voice	1
800 LTE	1
800 Voice	1
Location Details	
Latitude	41.38197
Longitude	-71.90368
Market	Northern Connecticut
Region	Northeast
City	Stonington
State	CT
Zip Code	06378
County	New London
2500MHz	3
1900MHz	3
800MHz	3

Band: 2500	Alpha	Beta	Gamma	Delta	Epsilon	Zeta
Radio Model						
Model Number	TD-RRH8x20-25	TD-RRH8x20-25	TD-RRH8x20-25	N/A	N/A	N/A
Weight (lbs)	76.2	76.2	76.2	N/A	N/A	N/A
Dimensions	26 x 18.6 x 6.7	26 x 18.6 x 6.7	26 x 18.6 x 6.7	N/A	N/A	N/A
Manufacturer	ALU	ALU	ALU	N/A	N/A	N/A
Number of RRUs needed	1	1	1	0	0	0
Trunk Cable 1						
Model Number	Hybriflex	N/A	N/A	N/A	N/A	N/A
Weight (Lbs.)	1	N/A	N/A	N/A	N/A	N/A
Dimensions (In.)	1.54	N/A	N/A	N/A	N/A	N/A
Manufacturer	ALU	N/A	N/A	N/A	N/A	N/A
Band: 800	Alpha	Beta	Gamma	Delta	Epsilon	Zeta
Radio Model						
Model Number	RRH-2x50-800	RRH-2x50-800	RRH-2x50-800	N/A	N/A	N/A
Weight (lbs)	69.1	69.1	69.1	N/A	N/A	N/A
Dimensions	16 x 13 x 10	16 x 13 x 10	16 x 13 x 10	N/A	N/A	N/A
Manufacturer	ALU	ALU	ALU	N/A	N/A	N/A
Number of RRUs needed	2	2	2	0	0	0
Band: 2500	Alpha	Beta	Gamma	Delta	Epsilon	Zeta
Antenna1						
Model Number	APXVTM14-ALU-I20	APXVTM14-ALU-I20	APXVTM14-ALU-I20			
Weight (lbs)	56.2	56.2	56.2	N/A	N/A	N/A
Dimensions	56.3 x 12.6 x 6.3	56.3 x 12.6 x 6.3	56.3 x 12.6 x 6.3	N/A	N/A	N/A
Manufacturer	RFS	RFS	RFS	N/A	N/A	N/A
Ant1 Top Jumper Make/Mode/Qty	2.5 Jumper	8	2.5 Jumper	8	N/A	0
Ant 1 RF requested Diameter	1/2"		1/2"		N/A	
Ant 1 RF requested Top Jumper Length(ft)	8		8		N/A	
Antenna 1 Azimuth	60		160		270	
Antenna 1 Mechanical DT	N/A		N/A		N/A	
Antenna 1 Center Line (ft)	139.9606344		139.9606344		N/A	
Antenna 1 Electrical DT	2		2		N/A	
Antenna 1 Electrical DT 2	N/A		N/A		N/A	
Antenna 1 Electrical DT 3	N/A		N/A		N/A	
Antenna 1 Twist	N/A		N/A		N/A	
Band: 1900	Alpha	Beta	Gamma	Delta	Epsilon	Zeta
Antenna1						
Model Number	NNVV-65B-R4	NNVV-65B-R4	NNVV-65B-R4			
Weight (lbs)	84.7	84.7	84.7	N/A	N/A	N/A
Dimensions	72 x 19.6 x 7.8	72 x 19.6 x 7.8	72 x 19.6 x 7.8	N/A	N/A	N/A
Manufacturer	CommScope	CommScope	CommScope	N/A	N/A	N/A
Ant1 Top Jumper Make/Mode/Qty	800/1900 Jumper	4	800/1900 Jumper	4	N/A	0
Ant 1 RF requested Diameter	1/2"		1/2"		N/A	
Ant 1 RF requested Top Jumper Length(ft)	8		8		N/A	
Antenna 1 Azimuth	60		160		270	
Antenna 1 Mechanical DT	N/A		N/A		N/A	
Antenna 1 Center Line (ft)	139.9606344		139.9606344		N/A	
Antenna 1 Electrical DT	3		3		N/A	
Antenna 1 Electrical DT 2	N/A		N/A		N/A	
Antenna 1 Electrical DT 3	N/A		N/A		N/A	
Antenna 1 Twist	N/A		N/A		N/A	

PLANS PREPARED FOR:
SBA
SBA COMMUNICATIONS CORP.
134 FLANDERS ROAD, SUITE 125
WESTBOROUGH, MA 01581
TEL: (508) 251-0720




PLANS PREPARED BY:
INFINIGY
FROM ZERO TO INFINIGY
the solutions are endless
1033 Watervliet Shaker Rd | Albany, NY 12205
Phone: 518-690-0790 | Fax: 518-690-0793
www.infinigy.com
JOB NUMBER 526-104



CHECKED BY:
APPROVED BY:
REVISIONS: DESCRIPTION DATE BY REV.
ISSUED FOR CONSTRUCTION 04/10/18 SL 0

SITE NUMBER: CT03XC107
SITE ADDRESS: 2 TAUGWONK SPUR STONINGTON, CT 06389

SHEET DESCRIPTION: RF DATA SHEET
SHEET NUMBER: RF-1





1 INTERNATIONAL BLVD., SUITE 800
MAHWAH, NJ 07495
P: 800.357.7641



134 FLANDERS RD., SUITE 125
WESTBOROUGH, MA 01581
P: 508.251.0720



GEOSTRUCTURAL
PO BOX 2421, BOISE, ID 83701
P: 503.539.4787
E: CONTACT@GEOSTRUCTURAL.COM
WWW.GEOSTRUCTURAL.COM

REVISIONS:		
0	04/16/18	ISSUE FOR CONSTRUCTION
		JAD

CHECKED BY: DWG

THE INFORMATION CONTAINED IN THIS SET OF DOCUMENTS IS PROPRIETARY BY NATURE. ANY USE OR DISCLOSURE OTHER THAN THAT WHICH RELATES TO THE CLIENT NAMES IS STRICTLY PROHIBITED.



SITE INFORMATION:

MOUNT AUGMENTATION

CT03XC107

STONINGTON, CT

LATITUDE: 41.38197

LONGITUDE: -71.90358

SHEET TITLE:

TITLE SHEET

SHEET NUMBER:

S1

CT03XC107

DO MACRO EQUIPMENT DEPLOYMENT

MOUNT AUGMENTATION @ 145'

MONOPOLE TOWER

STONINGTON, CT
NEW LONDON COUNTY

SITE INFORMATION

STRUCTURE TYPE: MONOPOLE

MOUNT TYPE: PLATFORM

LATITUDE: 41.38197 (NAD 83)

LONGITUDE: -71.90358 (NAD 83)

CITY, STATE: STONINGTON, CT

COUNTY: NEW LONDON

SBA SITE: CT00235-B Stony Brook

COORDINATES ARE FOR NAVIGATIONAL PURPOSES ONLY, NOT TO 1A ACCURACY.

DO NOT SCALE DRAWINGS

CONTRACTOR SHALL VERIFY ALL PLANS, EXISTING DIMENSIONS, CONDITIONS ON THE JOB SITE & SHALL IMMEDIATELY NOTIFY THE ENGINEER IN WRITING OF ANY DISCREPANCIES BEFORE PROCEEDING WITH THE WORK OR BE RESPONSIBLE FOR THE LABOR & MATERIALS FOR THE DISCREPANCIES.

CODE COMPLIANCE

ALL WORK SHALL BE PERFORMED AND MATERIALS INSTALLED IN ACCORDANCE WITH THE CURRENT EDITIONS OF THE FOLLOWING CODES AS ADOPTED BY THE LOCAL GOVERNING AUTHORITIES.

BUILDING CODE AND DESIGN STANDARD: 2012 IBC / TIA-222-G / 2016 CT

RIGGING PLAN REQUIRED


THIS SET OF PLANS DOES "NOT" CONSTITUTE A RIGGING PLAN.

A PROPER RIGGING PLAN SHALL BE PERFORMED BY A LICENSED PROFESSIONAL ENGINEER PRIOR TO PROCEEDING ON ANY AUGMENTATIONS SHOWN HEREIN.

GENERAL DESIGN NOTES

1. THIS PLAN HAS BEEN DESIGNED UTILIZING THE CORRESPONDING MOUNT STRUCTURAL ANALYSIS.
2. THESE PLANS HAVE BEEN DESIGNED IN ACCORDANCE WITH THE GOVERNING PROVISIONS OF TIA/EIA-222, ASCE 7, AWS, ACI, AND AISC. MATERIALS AND SERVICES PROVIDED BY THE CONTRACTOR SHALL CONFORM TO THE ABOVE-MENTIONED CODES AND THE CONTRACT SPECIFICATIONS.
3. ALL STRUCTURE INFORMATION OBTAINED IN THE FORM OF INFORMATION PROVIDED BY THE CLIENT. CONTRACTOR SHALL OBTAIN AND BECOME FAMILIAR WITH THE REFERENCED DOCUMENTS. CONTRACTOR SHALL ISSUE A REQUEST FOR INFORMATION (RFI) IN THE EVENT ANY DISCREPANCIES ARE DISCOVERED BETWEEN THESE DOCUMENTS AND THE AS-BUILT CONDITIONS IN THE FIELD IN A SITE VISIT THAT SHALL BE PERFORMED PRIOR TO STARTING FABRICATION OR CONSTRUCTION.
4. ALL MATERIALS UTILIZED FOR THIS PROJECT MUST BE NEW AND FREE OF ANY DEFECTS.
5. ALL PRODUCT OR MATERIAL SUBSTITUTIONS PROPOSED BY THE CONTRACTOR SHALL BE APPROVED IN WRITING BY THE ENGINEER. CONTRACTOR SHALL PROVIDE DOCUMENTATION TO ENGINEER SUITABLE TO DETERMINE IF SUBSTITUTE IS ACCEPTABLE FOR USE AND MEETS THE ORIGINAL DESIGN CRITERIA. DIFFERENCES FROM THE ORIGINAL DESIGN, INCLUDING MAINTENANCE, REPAIR AND REPLACEMENT, SHALL BE NOTED. ESTIMATES OF COSTS/CREDITS ASSOCIATED WITH THE SUBSTITUTION (INCLUDING RE-DESIGN COSTS AND COSTS TO SUB-CONTRACTORS) SHALL BE PROVIDED TO THE ENGINEER. CONTRACTOR SHALL PROVIDE ADDITIONAL DOCUMENTATION AND/OR SPECIFICATIONS TO THE ENGINEER AS REQUESTED.
6. PROVIDE STRUCTURAL STEEL SHOP DRAWING(S) TO THE ENGINEER OF RECORD FOR APPROVAL PRIOR TO FABRICATION (ONLY IF SPECIFICALLY REQUESTED BY ENGINEER).
7. UNLESS NOTED OTHERWISE, ALL NEW MEMBERS AND REINFORCING SHALL MAINTAIN THE EXISTING MEMBER WORK LINES AND NOT INTRODUCE ECCENTRICITIES INTO THE STRUCTURE.
8. ANY CONTRACTOR-CAUSED DAMAGE TO PROPERTY OF THE LAND OWNER, PROPERTY OF THE STRUCTURE OWNER, PROPERTY OF THE CUSTOMER, SITE FENCING OR GATES, ANY AND ALL UTILITY AND/OR SERVICE LINES, SHOWN OR NOT SHOWN ON THE PLANS, SHALL BE REPAIRED OR REPLACED AT THE SOLE COST OF THE CONTRACTOR AND SHALL BE ACCOMPLISHED BY THE CONTRACTOR OR SUBCONTRACTOR AS APPROVED BY THE ENGINEER OF RECORD AND LAND OWNER. DAMAGE TO EQUIPMENT OR PROPERTY OF ANY KIND BELONGING TO OTHER COMPANIES (BESIDES THE INDICATED CUSTOMER) SHALL BE ADDRESSED BY THE CONTRACTOR WITH THE COMPANIES THAT OWN THE DAMAGED ITEMS.

MOUNT AUGMENTATION CONFIGURATION



AUGMENTATION SCOPE

AUGMENT ALL SECTORS OF CARRIER'S EXISTING MOUNT INSTALLATION AS REQUIRED (UNLESS NOTED OTHERWISE)

CONTRACTOR NOTES

- PRIOR TO BEGINNING CONSTRUCTION, ALL CONTRACTORS AND SUBCONTRACTORS MUST ACKNOWLEDGE IN WRITING TO TOWER OWNER THAT THEY HAVE OBTAINED, UNDERSTAND, AND WILL FOLLOW STRUCTURE OWNER STANDARDS OF PRACTICE, CONSTRUCTION GUIDELINES, ALL SITE AND STRUCTURE/TOWER SAFETY PROCEDURES, ALL PRODUCT LIMITATIONS AND INSTALLATION PROCEDURES USED ON SITE, AND PROPOSED AUGMENTATIONS DESCRIBED. RECEIPT OF ACKNOWLEDGEMENT MUST OCCUR PRIOR TO BEGINNING CONSTRUCTION OR CLIMBING. IT IS THE RESPONSIBILITY OF THE GENERAL CONTRACTOR TO PROVIDE THIS DOCUMENTATION FOR STRUCTURE OWNER ON COMPANY LETTERHEAD AND THE RESPONSIBILITY OF THE GENERAL CONTRACTOR TO OBTAIN THIS DOCUMENTATION FROM ANY SUBCONTRACTORS (ON SUBCONTRACTOR LETTERHEAD) AND DELIVER IT TO THE STRUCTURE OWNER.
- IF THE CONTRACTOR DISCOVERS ANY EXISTING CONDITIONS THAT ARE NOT REPRESENTED ON THESE DRAWINGS, OR ANY CONDITIONS THAT WOULD INTERFERE WITH THE INSTALLATION OF THE AUGMENTATIONS, THE ENGINEER OF RECORD SHALL BE CONTACTED IMMEDIATELY TO EVALUATE THE SIGNIFICANCE OF THE DEVIATION.
- THE CONTRACTOR SHALL SOLICIT AND HIRE THE SERVICES OF A QUALIFIED AUGMENTATION INSPECTOR PRIOR TO BEGINNING CONSTRUCTION. THE AUGMENTATION INSPECTOR MAY BE AN EMPLOYEE OF THE CONTRACTOR'S FIRM, HOWEVER THE INSPECTOR'S ONLY DUTIES SHALL BE INSPECTION, TESTING, AND REPORT CREATION AS REQUIRED ON THE "AUGMENTATION INSPECTION NOTES" SHEET.
- THE CONTRACTOR SHALL NOTIFY THE TOWER OWNER OF THE PLANNED CONSTRUCTION & INSPECTION SCHEDULE, AS WELL AS ANY CHANGES TO THE SCHEDULE, WITHIN TWO BUSINESS DAYS OF THE COMPLETION OF THE SCHEDULE OR SCHEDULE REVISION BOTH PRIOR TO BEGINNING CONSTRUCTION AND DURING CONSTRUCTION AS THE SCHEDULE CHANGES. THE STRUCTURE OWNER WHEN THE WORK HAS BEEN COMPLETED WITHIN 2 BUSINESS DAYS OF THE COMPLETION OF THE WORK AND ASSOCIATED AUGMENTATION INSPECTIONS & TESTING (WHEN APPLICABLE).
- IT IS ASSUMED THAT ANY STRUCTURAL AUGMENTATION WORK SPECIFIED ON THESE PLANS WILL BE ACCOMPLISHED BY KNOWLEDGEABLE WORKMEN WITH TOWER CONSTRUCTION EXPERIENCE. THIS INCLUDES PROVIDING THE NECESSARY CERTIFICATIONS TO THE STRUCTURE OWNER AND ENGINEER INCLUDING BUT NOT LIMITED TO TOWER CLIMBER AND RESCUE CLIMBER CERTIFICATIONS, ET CETERA.
- THESE DRAWINGS DO NOT INDICATE THE METHOD OF CONSTRUCTION. THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK AND SHALL BE SOLELY RESPONSIBLE FOR ALL CONSTRUCTION METHODS, MEANS, TECHNIQUES, SEQUENCES AND PROCEDURES.
- CONTRACTOR SHALL WORK WITHIN THE LIMITS OF THE STRUCTURE OWNER'S PROPERTY OR LEASE AREA AND APPROVED EASEMENTS. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO VERIFY WORK IS WITHIN THESE BOUNDARIES. CONTRACTOR SHALL EMPLOY A SURVEYOR AS REQUIRED. ANY WORK OUTSIDE THESE BOUNDARIES SHALL BE APPROVED IN WRITING BY THE LAND OWNER PRIOR TO MOBILIZATION. CONSTRUCTION STAKING AND BOUNDARY MARKING IS THE RESPONSIBILITY OF THE CONTRACTOR.

STRUCTURAL ERECTION AND BRACING REQUIREMENTS

- THE STRUCTURAL DRAWINGS ILLUSTRATE THE COMPLETED STRUCTURE WITH ALL ELEMENTS IN THEIR FINAL POSITIONS, PROPERLY SUPPORTED AND BRACED.
- THE CONTRACTOR SHALL PROVIDE SHORING AND BRACING AS REQUIRED DURING CONSTRUCTION TO ENSURE STABILITY. DESIGN AND SEQUENCING OF CONSTRUCTION SHORING AND BRACING IS OUTSIDE THE SCOPE OF THIS WORK.
- THE CONTRACTOR IS RESPONSIBLE FOR THE DESIGN AND EXECUTION OF ALL MISCELLANEOUS SHORING, BRACING, TEMPORARY SUPPORTS, GUYING, ETC. NECESSARY TO PROVIDE A COMPLETE AND STABLE STRUCTURE AS SHOWN ON THESE DRAWINGS.

BOLTS

- ALL CONNECTIONS OF STRUCTURAL STEEL MEMBERS SHALL BE MADE USING SPECIFIED GALVANIZED HIGH STRENGTH ASTM A325 OR A490 BOLTS WITH THREADS EXCLUDED FROM SHEAR PLANE.
- FASTENERS SHALL BE INSTALLED IN PROPERLY ALIGNED HOLES, WITH BOLT HEADS FACING DOWN WHERE APPLICABLE.
- ALL BOLTS AT EVERY CONNECTION SHALL BE INSTALLED SNUG-TIGHT UNTIL THE SECTION IS FULLY COMPACTED AND ALL PLIES ARE JOINED, AND THEN TIGHTENED FURTHER BY AISC - 'TURN OF THE NUT' METHOD. TIGHTENING SHALL PROGRESS SYSTEMATICALLY.
- BOLT LENGTHS UP TO AND INCLUDING 4 DIAMETERS SHALL BE TENSIONED 1/3 TURN BEYOND SNUG-TIGHT. BOLT LENGTHS OVER 4 DIAMETERS SHALL BE 1/2 TURNS BEYOND SNUG-TIGHT.
- ALL BOLTED CONNECTIONS SHALL USE LOCK WASHERS.

STRUCTURAL STEEL

- STRUCTURAL STEEL SHALL BE DETAILED, FABRICATED, AND ERECTED IN ACCORDANCE WITH THE CURRENT EDITION OF THE AISC STEEL CONSTRUCTION MANUAL AND SECTION 4 OF THE TIA CODE.
- PRE-QUALIFIED STRUCTURAL STEEL SHALL CONFORM TO THE FOLLOWING MINIMUM GRADES UNLESS OTHERWISE NOTED:
 - CHANNELS & ANGLES ASTM A36, (Fy = 36 KSI)
 - PLATES ASTM A36, (Fy = 36 KSI)
 - PIPES ASTM A53 GR.B, (Fy = 35 KSI)
 - HSS ROUND ASTM A500 GR.B, (Fy = 42 KSI)
 - HSS RECTANGULAR ASTM A500 GR.B, (Fy = 46 KSI)
 - STRUCTURAL BOLTS ASTM A325
 - U-BOLTS ASTM A307 GR.A
 - NUTS FOR BOLTS ASTM A563 (THREADING TO MATCH BOLT)
 - WASHERS FOR BOLTS ASTM F436
 - SEE TABLE 5-1 OF THE TIA CODE FOR ADDITIONAL SHAPES AND STANDARDS THAT ARE NOT LISTED ABOVE.
- NON PRE-QUALIFIED STRUCTURAL STEEL SHALL CONFORM TO THE FOLLOWING STANDARDS PER THE TIA CODE:
 - THE CARBON EQUIVALENT OF STEEL SHALL NOT EXCEED 0.65 PER SECTION 5.4.2 OF THE TIA CODE
 - ELONGATION OF STEEL SHALL NOT BE LESS THAN 18%
 - TEST REPORTS SHALL BE IN ACCORDANCE WITH ASTM A6 OR A568
 - TOLERANCES SHALL BE IN ACCORDANCE WITH ASTM A6
- FIELD CUT EDGES, EXCEPT DRILLED HOLES, SHALL BE GROUND SMOOTH AND COLD GALVANIZED.
- ALL WELDING WORK SHALL CONFORM TO THE AWS D1.1 STRUCTURAL WELDING CODE. ALL WELDING SHALL BE PERFORMED BY CERTIFIED WELDERS ONLY. WELDING ELECTRODES SHALL BE E70XX.
- ALL DETAILING, FABRICATION AND ERECTION OF STRUCTURAL STEEL SHALL CONFORM TO AISC SPECS AND CODES, LATEST EDITION.
- UPON REQUEST, THE CONTRACTOR SHALL SUBMIT DETAILED, ENGINEERED, COORDINATED AND CHECKED SHOP DRAWINGS FOR ALL STRUCTURAL STEEL TO THE ENGINEER OF RECORD TO REVIEW FOR COMPLIANCE WITH DESIGN INTENT PRIOR TO THE START OF FABRICATION AND/OR ERECTION.
- TORCH-CUTTING OF ANY KIND SHALL NOT BE PERMITTED.
- ALL BOLT HOLES SHALL BE STANDARD SIZE BOLT HOLES PER AISC 360, UNLESS OTHERWISE NOTED. ALL HOLES SHALL BE SHOP DRILLED OR SUB-PUNCHED AND REAMED. BURNING OF HOLES IS NOT PERMITTED. WHERE SLOTTED OR OVERSIZE HOLES ARE SPECIFIED ON THE DRAWINGS, EXTRA-THICK ASTM F436 PLATE WASHERS SHALL BE USED (3/16" MINIMUM THICKNESS) WITH A DIAMETER SUITABLE TO COVER THE EXTENTS OF THE SLOT OR HOLE. BOLTS SHALL BE HEAVY-HEX WHERE AVAILABLE IN THE SIZE AND GRADE SPECIFIED, OTHERWISE BOLTS SHALL BE HEX HEAD CAP SCREWS.
- ALL STEEL HARDWARE, INCLUDING ADHESIVE OR EMBEDDED ANCHOR BOLTS AND THEIR ACCESSORIES, SHALL BE HOT-DIP GALVANIZED IN ACCORDANCE WITH ASTM A153 (EXCEPT BOLTS SMALLER THAN 1/2" SHALL CONFORM TO FE/ZN 3 AT PER ASTM F1941 WHERE HOT-DIP GALVANIZED BOLTS ARE NOT AVAILABLE). ALL STEEL MEMBERS, INCLUDING WELDMENTS, SHALL BE HOT-DIP GALVANIZED IN ACCORDANCE WITH ASTM A123. REPAIR DAMAGE TO GALVANIZED COATINGS USING ASTM A780 PROCEDURES WITH A ZINC RICH PAINT (SUCH AS ZINC GALVILITE) FOR GALVANIZING DAMAGED BY HANDLING, TRANSPORTING, CUTTING, WELDING, OR BOLTING. DO NOT HEAT SURFACES TO WHICH REPAIR PAINT HAS BEEN APPLIED. CALL OUT HOLES REQUIRED FOR HOT-DIP GALVANIZING ON SHOP DRAWINGS.
- MEMBERS SHALL BE SHOP-FABRICATED AND WELDED TO THE EXTENT PRACTICABLE IN ORDER TO REDUCE FIELD INSTALLATION COSTS.

NOMINAL HOLE DIMENSIONS

BOLT Ø	STANDARD HOLE Ø
1/2"Ø	9/16"Ø
5/8"Ø	11/16"Ø
3/4"Ø	13/16"Ø
7/8"Ø	15/16"Ø
1"Ø	1 1/16"Ø



GEOSTRUCTURAL
PO BOX 2421, BOISE, ID 83701
P: 503.539.4787
E: CONTACT@GEOSTRUCTURAL.COM
WWW.GEOSTRUCTURAL.COM

REVISIONS:		
0	04/16/18	ISSUE FOR CONSTRUCTION
JAD		

CHECKED BY: DWG

THE INFORMATION CONTAINED IN THIS SET OF DOCUMENTS IS PROPRIETARY BY NATURE. ANY USE OR DISCLOSURE OTHER THAN THAT WHICH RELATES TO THE CLIENT NAMES IS STRICTLY PROHIBITED.



SITE INFORMATION:

MOUNT AUGMENTATION

CT03XC107

STONINGTON, CT

LATITUDE: 41.38197
LONGITUDE: -71.90358

SHEET TITLE:
NOTES AND SPECIFICATIONS


SHEET NUMBER:
S2



REVISIONS:		
0	04/16/18	ISSUE FOR CONSTRUCTION JAD

CHECKED BY: DWG

THE INFORMATION CONTAINED IN THIS SET OF DOCUMENTS IS PROPRIETARY BY NATURE. ANY USE OR DISCLOSURE OTHER THAN THAT WHICH RELATES TO THE CLIENT NAMES IS STRICTLY PROHIBITED.



SITE INFORMATION:
MOUNT AUGMENTATION
CT03XC107
STONINGTON, CT
LATITUDE: 41.38197
LONGITUDE: -71.90358

SHEET TITLE:
AUGMENTATIONS, SECTIONS & DETAILS


SHEET NUMBER:
S3

NEW MOUNT AUGMENTATIONS

- 1 PLATFORM REINFORCEMENT KIT
SITEPRO1 PART# PRK-1245L. ATTACH PRK COLLAR TO MONOPOLE SHAFT ~4.0' BELOW EXISTING STANOFF CENTERLINE AND DOUBLE ANGLE KICKER BRACKET TO BACK-TO-BACK ANGLES AT PLATFORM CORNERS AS SHOWN PER MANUF. SPECS. [(1) KIT TOTAL]
 - 2 HANDRAIL KIT COMPONENTS
SITEPRO1 PART# HRK12-U OR HRK14-U. ATTACH TO MOUNT PIPES ~3.0' ABOVE EXISTING STANOFF CENTERLINE. VERIFY MOUNT FACE WIDTH IN FIELD PRIOR TO ORDERING. [(1) KIT TOTAL]
 - 3 HANDRAIL KIT COMPONENTS - V-BRACE KIT
SITEPRO1 PART# PRK-SFS-H-L. ATTACH COLLAR MOUNT TO MONOPOLE SHAFT ~2.5' BELOW AND ~3.0' ABOVE EXISTING STANOFF CENTERLINE. NOTE: IF THE PRK-SFS-H-L KIT IS NOT AVAILABLE, PROVIDE (12) TOTAL L $\frac{1}{2}$ x2 $\frac{1}{2}$ x $\frac{3}{16}$ x ~8' LONG REPLACEMENT ANGLES, FIELD-CUT AND DRILL TO SUIT. [(2) KITS TOTAL]
 - 4 HANDRAIL KIT COMPONENTS - BOTTOM FACE RAIL
 - PIPE2.0STD X 14.0' HORIZ. RAIL, [(3) TOTAL]. ATTACH SFS-H-L KIT ANGLES TO NEW HORIZ. RAIL.
 - PIPE2.0STD X ~4' LONG CORNER BRACE, [(3) TOTAL]. ATTACH TO NEW HORIZ. RAIL W/ (6) SITEPRO1 PART# PUCK BRACKETS.
 - PIPE2.0STD X 8.0' MOUNT PIPES, [(9) TOTAL] W/ SITEPRO1 SCX x-K, [(9) TOTAL] CROSS-OVER PLATES. ATTACH ALL MOUNT PIPES TO EXISTING AND NEW HORIZ. RAILS.
 - 1/2"Ø OR 5/8"Ø U-BOLTS, (18) TOTAL. ATTACH ALL MOUNT PIPES TO EXISTING BOTTOM RAIL W/ (2) U-BOLTS.
 - 5 PANEL ANTENNAS TO BE INSTALLED IN POSITIONS 1 AND 3 (AS CLOSE TO THE CENTER OF FACE NEAR EXISTING STANOFF AS POSSIBLE. RRH UNITS TO BE INSTALLED ON DUAL SWIVEL BRACKETS BEHIND PANEL ANTENNAS IN POSITIONS 1 AND 3).
- AUGMENTATIONS SHALL BE COMPLETED PRIOR TO THE INSTALLATION OF ANY NEW EQUIPMENT.




PLATFORM @ 145' AUGMENTATION



MOUNT AUGMENTATION ISOMETRY
SCALE: N.T.S.

CONSTRUCTION NOTES


1. SCOPE OF WORK MUST BE COMPLETED AT WIND SPEEDS < 20 MPH.
2. ALL DIMENSIONS ARE APPROXIMATE. CONTRACTOR SHOULD FIELD-VERIFY ALL DIMENSIONS BEFORE FABRICATION OF STEEL AND COMMENCEMENT OF WORK. FIELD CUT MEMBERS AS REQUIRED.
3. CONTRACTOR TO COORDINATE THE TEMPORARY REMOVAL/RELLOCATION/REPLACEMENT OF ELEMENTS (E.G. COAX, CLIPS, TMAs, ETC.) CONNECTED TO, OR IN THE DIRECT PATH, OF NEW AUGMENTATION MEMBERS.




AUGMENTED MOUNT ISOMETRY
SCALE: N.T.S.

INSTALLATION NOTES

1. AUGMENT MEMBER(S) MAY NEED TO BE FIELD-CUT TO LENGTH TO ACCOMMODATE THIS INSTALLATION. CONTRACTOR TO CUT AND DRILL TO SUIT AS REQUIRED AND APPLY (2) COATS OF COLD-GALV. COMPOUND TO CUT MEMBER ENDS.
2. CONTRACTOR TO CHECK ALL EXISTING MEMBER CONNECTION BOLTS, PARTICULARLY STANOFF TO TOWER BOLTS, FOR PROPER INSTALLATION AND TIGHTNESS.
3. COORDINATE PLACEMENT OF NEW AUGMENT MEMBERS WITH EXISTING TOWER AND CLIMBING FACILITY ELEMENTS (E.G. STEP PEGS, COAX PORTS, ETC.)
4. REFER TO CONSTRUCTION DRAWINGS (BY OTHERS) AND MOUNT STRUCTURAL ANALYSIS FOR APPROVED INSTALLATION LOCATIONS AND QUANTITIES OF APPURTENANCES.



AUGMENTED MOUNT PLAN
SCALE: N.T.S.



AUGMENTED MOUNT FRONT ELEVATION
SCALE: N.T.S.