



Northeast Site Solutions
Denise Sabo
4 Angela's Way, Burlington CT 06013
203-435-3640
denise@northeastsitesolutions.com

August 11, 2021

Members of the Siting Council
Connecticut Siting Council
Ten Franklin Square
New Britain, CT 06051

RE: Tower Share Application
44 Fflyer Place, Suffield CT 06078
Latitude: 41.980472
Longitude: -72.657278
Site# 801486_Crown_Dish

Dear Ms. Bachman:

This letter and attachments are submitted on behalf of Dish Wireless LLC. Dish Wireless LLC plans to install antennas and related equipment to the tower site located at 44 Fflyer Place in Suffield, Connecticut.

Dish Wireless LLC proposes to install three (3) 600/1900/2100 MHz antenna and six (6) RRUs, at the 101-foot level of the existing 109-foot monopole tower, one (1) Fiber cables will also be installed. Dish Wireless LLC equipment cabinets will be placed within 7x5 lease area. Included are plans by Infinigy, dated July 1, 2021 Exhibit C. Also included is a structural analysis prepared by Crown Castle, dated May 22, 2021, confirming that the existing tower is structurally capable of supporting the proposed equipment. Attached as Exhibit D. This facility was approved by the Town of Suffield Planning and Zoning on March 30, 2000. Please see attached Exhibit A.

Please accept this letter as notification pursuant to Regulations of Connecticut State Agencies 16-50aa, of Dish Wireless LLC intent to share a telecommunications facility pursuant to R.C.S.A. 16-50j-88. In accordance with R.C.S.A., a copy of this letter is being sent to The Honorable Melissa M. Mack, First Selectman for the Town of Suffield, James Taylor, Zoning Enforcement Officer, as well as the tower owner (Crown Castle) and property owner (Town of Suffield).

The planned modifications of the facility fall squarely within those activities explicitly provided for in R.C.S.A. 16-50j-89.

1. The proposed modification will not result in an increase in the height of the existing structure. The top of the tower is 109-feet; Dish Wireless LLC proposed antennas will be located at a center line height of 101-feet.
2. The proposed modifications will not result in the increase of the site boundary as depicted on the attached site plan.
3. The proposed modifications will not increase noise levels at the facility by six decibels or more, or to levels that exceed local and state criteria. The incremental effect of the proposed changes will be negligible.



4. The operation of the proposed antennas will not increase radio frequency emissions at the facility to a level at or above the Federal Communications Commission safety standard. As indicated in the attached power density calculations, the combined site operations will result in a total power density of 57.34% as evidenced by Exhibit F.

Connecticut General Statutes 16-50aa indicates that the Council must approve the shared use of a telecommunications facility provided it finds the shared use is technically, legally, environmentally, and economically feasible and meets public safety concerns. As demonstrated in this letter, Dish Wireless LLC respectfully indicates that the shared use of this facility satisfies these criteria.

A. Technical Feasibility. The existing monopole has been deemed structurally capable of supporting Dish Wireless LLC proposed loading. The structural analysis is included as Exhibit D.

B. Legal Feasibility. As referenced above, C.G.S. 16-50aa has been authorized to issue orders approving the shared use of an existing tower such as this support tower in Suffield. Under the authority granted to the Council, an order of the Council approving the requested shared use would permit Dish Wireless LLC to obtain a building permit for the proposed installation. Further, a Letter of Authorization is included as Exhibit G, authorizing Dish Wireless LLC to file this application for shared use.

C. Environmental Feasibility. The proposed shared use of this facility would have a minimal environmental impact. The installation of Dish Wireless LLC equipment at the 101-foot level of the existing 109-foot tower would have an insignificant visual impact on the area around the tower. Dish Wireless LLC ground equipment would be installed within the existing facility compound. Dish Wireless LLC shared use would therefore not cause any significant alteration in the physical or environmental characteristics of the existing site. Additionally, as evidenced by Exhibit F, the proposed antennas would not increase radio frequency emissions to a level at or above the Federal Communications Commission safety standard.

D. Economic Feasibility. Dish Wireless LLC will be entering into an agreement with the owner of this facility to mutually agreeable terms. As previously mentioned, the Letter of Authorization has been provided by the owner to assist Dish Wireless LLC with this tower sharing application.

E. Public Safety Concerns. As discussed above, the tower is structurally capable of supporting Dish Wireless LLC proposed loading. Dish Wireless LLC is not aware of any public safety concerns relative to the proposed sharing of the existing guyed tower. Dish Wireless LLC intentions of providing new and improved wireless service through the shared use of this facility is expected to enhance the safety and welfare of local residents and individuals traveling through Suffield.

Sincerely,

Denise Sabo

Denise Sabo
Mobile: 203-435-3640
Fax: 413-521-0558
Office: 4 Angela's Way, Burlington CT 06013
Email: denise@northeastsitesolutions.com



NSS

NORTHEAST
SITE SOLUTIONS

Turnkey Wireless Development

Attachments cc:

The Honorable Melissa M. Mack, First Selectman (also as property owner)
Town of Suffield
83 Mountain Road Suffield, CT 06078

Town of Suffield
James Taylor – Zoning Enforcement Officer
83 Mountain Road Suffield, CT 06078

Crown Castle, Tower Owner

Exhibit A

Original Facility Approval




Suffield Conservation Commission

83 Mountain Road • Suffield, Connecticut 06078
(860) 668-3847

March 30, 2000

Elaine Sarsynski
Suffield Economic Development Commission
83 Mountain Road
Suffield, CT 06078



RE: PERMIT # 1264
Communications Towers
Phelps Road, Ff Tyler Place, & Ucar Street

Dear Elaine:

The Suffield Conservation Commission (SCC), at their March 28, 2000 meeting, approved the Town's application for the construction of three communications towers. The properties are located on Phelps Road, Ff Tyler Place, and Ucar Street, Assessor's Map Numbers 80, 34-H, and 9, Parcels 55, 70, 32, 4, and 9, in Suffield, Connecticut.

This permit is granted as a Declaratory Ruling, as there are no wetland impacts proposed.


The following items shall be addressed in the final submittal for construction:

- 9) The SCC must be notified in writing prior to any work commencing on site, of the date work will start, and the name, address, and telephone number of the contractor responsible for the work. Failure to do so will render this permit null and void.
- 10) The contractor is responsible for using proper soil and erosion controls. The contractor is also responsible for any fees associated with soil and erosion control inspections by the Town's Consultant.
- 11) All the poles and antennas shall be tinted a dull gray color.
- 12) If the FAA or any other regulatory agency ever requires lights on top of the town landfill tower, the applicant must come back to the Commission for review and approval.

13) The foundation design and geotechnical data must be supplied to the Commission for each pole.

The fee has been waived.

Respectfully,


Art Christian, Chairman

AC/klm

Cc: Suffield Building Department



Zoning and Planning Commission

Town of Suffield

May 4, 2000

Ms. Elaine Sarsynski, Director
Suffield Economic Development Commission
83 Mountain Road
Suffield, Connecticut 06078

Re: File #740 -- Request of the Suffield Economic Development Commission for a special use permit for the approval of sites for telecommunication towers located on Town properties: WPCA, Highway Department, and Transfer Station.

Dear Ms. Sarsynski:

At a duly called Special Meeting of the Suffield Zoning and Planning Commission held on Monday, May 1, 2000, the Commission voted to approve the Town of Suffield's special use permit request for the for three (3) proposed telecommunication sites located as designated:

1. Town of Suffield Transfer Station site on the west side of Mountain Road (Route 168), on undeveloped land west of the Transfer Station operations (Site A);
2. Town of Suffield Public Works garage/maintenance facility off of Mountain Road, on land immediately adjacent to the Maintenance Facility Building (Site B); and
3. Town of Suffield Sewage Treatment Plant on the east side of East Street (Route 159), on undeveloped land along the north side of the Treatment's Plant's access driveway (Site C).

with the following conditions:

1. The heights of the respective mono-pole towers, including antennae, shall not exceed 199-feet (Site A); 120-feet (Site B); and 174-feet (Site C);
2. Each tower shall be certified as "self-collapsing" by a Connecticut registered professional engineer;
3. Details drawings are to be submitted with each request for building permits for both the towers and related facilities;
4. FCC licenses shall be produced prior to the issuance of the permits for company leasing space on the towers;
5. The Zoning Enforcement Officer shall review each proposal for zoning conformance prior to the issuance of the building permits;
6. All utilities are to be underground;
7. Site plans are to be revised.

A mylar and four (4) copies of site plans for each of the three approved sites must be submitted to this office as soon as possible for signatures.

Please remit a check in the amount of \$10.00 (payable to the Town of Suffield), *along with this original letter*, to the Office of the Town Clerk, 83 Mountain Road. This fee is required to cover the cost of recording the Special Use Permit in the Office of the Town Clerk.

Ms. Elaine Sarsynski, Director
Suffield Economic Development Commission
May 4, 2000

2

A copy of the legal notice that will appear in the Journal Inquirer on Saturday, May 6, 2000 is enclosed.

Sincerely,

Douglas H. Viets, M.D. /bgk

Douglas H. Viets, M.D.
Chairman

:bgk
Enclosure

cc:	Building Official	Zoning Enforcement Officer
	Planning Consultant	File
	Town Engineer	

LEGAL NOTICE
SUFFIELD PLANNING AND ZONING COMMISSION

At a duly called Special Meeting of the Suffield Zoning and Planning Commission held on Monday, May 1, 2000, the Commission took the following actions:

APPROVED WITH CONDITIONS: Special use permit request of Suffield Economic Development Commission for the approval of sites for communication towers located on Town properties: WPCA, Highway Department and Landfill.

Douglas H. Viets, M.D., Chairman

Stephen J. Martin, Secretary

Journal Inquirer
May 6, 2000

Exhibit B

Property Card



Town of Suffield, CT

Property Listing Report

Map Block Lot

34H-32-4

Account


34522

Property Information

Property Location	44 FFYLER PL
Owner	SUFFIELD TOWN OF
Co-Owner	
Mailing Address	83 MOUNTAIN RD SUFFIELD CT 06078
Land Use	903I Municipal MDL-96
Land Class	E
Zoning Code	TCV
Census Tract	4771.01

Neighborhood	D
Acreage	3.5
Utilities	
Lot Setting/Desc	
Additional Info	

Photo



Sketch



Primary Construction Details

Year Built	2000
Stories	1
Building Style	Pre-Eng Garage
Building Use	Industrial
Building Condition	02
Floors	Concrete
Total Rooms	

Bedrooms	
Full Bathrooms	
Half Bathrooms	
Bath Style	
Kitchen Style	
Roof Style	Gable
Roof Cover	Asphalt

Exterior Walls	MASONRY
Interior Walls	Minimum
Heating Type	Hot Air-No Duc
Heating Fuel	Oil
AC Type	None
Gross Bldg Area	736
Total Living Area	736



Valuation Summary (Assessed value = 70% of Appraised Value)

Item	Appraised	Assessed
Buildings	531800	372260
Extras	34200	23940
Improvements	619500	433650
Outbuildings	53500	37450
Land	229000	160300
Total	848500	593950

Outbuilding and Extra Items

Type	Description
Shed	1920 S.F.
Kennel - Ave	640 S.F.
Fence - 6' Chain	142 L.F.
Paving - Asphalt	14000 S.F.
Garage - Ave	2408 S.F.
Shed	360 S.F.
Paving - Asphalt	880 S.F.
Mezzanine Unfinished	837 S.F.
Canopy Ave	1600 S.F.

Sub Areas

Subarea Type	Gross Area (sq ft)	Living Area (sq ft)
First Floor	736	736
Total Area	6000	6000

Sales History

Owner of Record	Book/ Page	Sale Date	Sale Price
SUFFIELD TOWN OF	134/ 430	6/8/1973	0
SUFFIELD TOWN OF	53/ 210	12/22/1920	0
SUFFIELD TOWN OF	53/ 151	4/15/1920	0
SUFFIELD TOWN OF	53/ 141	3/11/1920	0

Exhibit C

Construction Drawings



DISH Wireless L.L.C. SITE ID:

BOBDL00036A

DISH Wireless L.L.C. SITE ADDRESS:

**44 FFYLER PLACE
SUFFIELD, CT 06078**

SCOPE OF WORK	
THIS IS NOT AN ALL INCLUSIVE LIST. CONTRACTOR SHALL UTILIZE SPECIFIED EQUIPMENT PART OR ENGINEER APPROVED EQUIVALENT. CONTRACTOR SHALL VERIFY ALL NEEDED EQUIPMENT TO PROVIDE A FUNCTIONAL SITE. THE PROJECT GENERALLY CONSISTS OF THE FOLLOWING:	
TOWER SCOPE OF WORK:	
<ul style="list-style-type: none"> • INSTALL (3) PROPOSED PANEL ANTENNAS (1 PER SECTOR) • INSTALL (1) PROPOSED TOWER PLATFORM MOUNT • INSTALL PROPOSED JUMPERS • INSTALL (6) PROPOSED RRUs (2 PER SECTOR) • INSTALL (1) PROPOSED OVER VOLTAGE PROTECTION DEVICE (OVP) • INSTALL (1) PROPOSED HYBRID CABLE 	
GROUND SCOPE OF WORK:	
<ul style="list-style-type: none"> • INSTALL (1) PROPOSED METAL PLATFORM • INSTALL (1) PROPOSED ICE BRIDGE • INSTALL (1) PROPOSED PPC CABINET • INSTALL (1) PROPOSED EQUIPMENT CABINET • INSTALL (1) PROPOSED POWER CONDUIT • INSTALL (1) PROPOSED TELCO CONDUIT • INSTALL (1) PROPOSED TELCO-FIBER BOX • INSTALL (1) PROPOSED GPS UNIT • INSTALL (1) PROPOSED FIBER NID (IF REQUIRED) 	

SITE INFORMATION	PROJECT DIRECTORY
PROPERTY OWNER: TOWN OF SUFFIELD ADDRESS: 83 MOUNTAIN ROAD SUFFIELD, CT 06078-2041	APPLICANT: DISH Wireless L.L.C. 5701 SOUTH SANTA FE DRIVE LITTLETON, CO 80120
TOWER TYPE: MONOPOLE	TOWER OWNER: CROWN CASTLE 2000 CORPORATE DRIVE CANONSBURG, PA 15317 (877) 486-9377
TOWER CO SITE ID: 801486	SITE DESIGNER: B+T GROUP 1717 S. BOULDER AVE, SUITE 300 TULSA, OK 74119 (918) 587-4630
TOWER APP NUMBER: 556646	SITE ACQUISITION: NICHOLAS CURRY NICHOLAS.CURRY@CROWNCastle.COM
COUNTY: HARTFORD	CONSTRUCTION MANAGER: JAVIER SOTO JAVIER.SOTO@DISH.COM
LATITUDE (NAD 83): 41° 58' 49.70" N 41.980472 N	RF ENGINEER: BOSSENER CHARLES BOSSENER.CHARLES@DISH.COM
LONGITUDE (NAD 83): 72° 39' 26.20" W 72.657278 W	
ZONING JURISDICTION: CONNECTICUT SITING COUNCIL	
ZONING DISTRICT: TCV	
PARCEL NUMBER: SUFF-000034H-000032 -000004	
OCCUPANCY GROUP: U	
CONSTRUCTION TYPE: II-B	
POWER COMPANY: EVERSOURCE	
TELEPHONE COMPANY: T.B.D.	



5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



2000 CORPORATE DRIVE
CANONSBURG, PA 15317



1717 S. BOULDER
SUITE 300
TULSA, OK 74119
PH: (918) 587-4630
www.btgrp.com



B&T ENGINEERING, INC.
PEC.0001564
Expires 2/10/22

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY: JJR	CHECKED BY: RMC	APPROVED BY: MDW
---------------	-----------------	------------------

RFDS REV #: ---

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	5/28/21	ISSUED FOR REVIEW
0	7/1/21	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
151123.001.01

DISH Wireless L.L.C.
PROJECT INFORMATION

BOBDL00036A
44 FFYLER PLACE
SUFFIELD, CT 06078

SHEET TITLE
TITLE SHEET

SHEET NUMBER
T-1

CONNECTICUT CODE COMPLIANCE

ALL WORK SHALL BE PERFORMED AND MATERIALS INSTALLED IN ACCORDANCE WITH THE CURRENT EDITIONS OF THE FOLLOWING CODES AS ADOPTED BY THE LOCAL GOVERNING AUTHORITIES. NOTHING IN THESE PLANS IS TO BE CONSTRUED TO PERMIT WORK NOT CONFORMING TO THESE CODES:

CODE TYPE	CODE
BUILDING	2018 CT STATE BUILDING CODE/2015 IBC W/ CT AMENDMENTS
MECHANICAL	2018 CT STATE BUILDING CODE/2015 IMC W/ CT AMENDMENTS
ELECTRICAL	2018 CT STATE BUILDING CODE/2017 NEC W/ CT AMENDMENTS

SHEET INDEX

SHEET NO.	SHEET TITLE
T-1	TITLE SHEET
A-1	OVERALL AND ENLARGED SITE PLAN
A-2	ELEVATION, ANTENNA LAYOUT AND SCHEDULE
A-3	EQUIPMENT PLATFORM AND H-FRAME DETAILS
A-4	EQUIPMENT DETAILS
A-5	EQUIPMENT DETAILS
A-6	EQUIPMENT DETAILS
E-1	ELECTRICAL/FIBER ROUTE PLAN AND NOTES
E-2	ELECTRICAL DETAILS
E-3	ELECTRICAL ONE-LINE, FAULT CALCS & PANEL SCHEDULE
G-1	GROUNDING PLANS AND NOTES
G-2	GROUNDING DETAILS
G-3	GROUNDING DETAILS
RF-1	RF CABLE COLOR CODE
RF-2	RF PLUMBING DIAGRAM
GN-1	LEGEND AND ABBREVIATIONS
GN-2	GENERAL NOTES
GN-3	GENERAL NOTES
GN-4	GENERAL NOTES

SITE PHOTO



UNDERGROUND SERVICE ALERT CBYD 811
UTILITY NOTIFICATION CENTER OF CONNECTICUT
(800) 922-4455
WWW.CBYD.COM



CALL 2 WORKING DAYS UTILITY NOTIFICATION PRIOR TO CONSTRUCTION

GENERAL NOTES

THE FACILITY IS UNMANNED AND NOT FOR HUMAN HABITATION. A TECHNICIAN WILL VISIT THE SITE AS REQUIRED FOR ROUTINE MAINTENANCE. THE PROJECT WILL NOT RESULT IN ANY SIGNIFICANT DISTURBANCE OR EFFECT ON DRAINAGE, NO SANITARY SEWER SERVICE, POTABLE WATER, OR TRASH DISPOSAL IS REQUIRED AND NO COMMERCIAL SIGNAGE IS PROPOSED.

11"x17" PLOT WILL BE HALF SCALE UNLESS OTHERWISE NOTED


CONTRACTOR SHALL VERIFY ALL PLANS, EXISTING DIMENSIONS, AND CONDITIONS ON THE JOB SITE, AND SHALL IMMEDIATELY NOTIFY THE ENGINEER IN WRITING OF ANY DISCREPANCIES BEFORE PROCEEDING WITH THE WORK.

DIRECTIONS

DIRECTIONS FROM BRADLEY INTERNATIONAL AIRPORT:

HEAD NORTH TOWARD BRADLEY INTERNATIONAL AIRPORT. SLIGHT LEFT ONTO BRADLEY INTERNATIONAL AIRPORT. SLIGHT LEFT. CONTINUE ONTO BRADLEY INTERNATIONAL AIRPORT CON. TAKE THE CT-20 W EXIT TOWARD E GRANBY/GRANBY. CONTINUE ONTO CT-20 W. TURN RIGHT ONTO EAST ST. CONTINUE ONTO S GRAND ST. TURN RIGHT ONTO STATE HWY 526. TURN RIGHT ONTO CT-168 E/MOUNTAIN RD. TURN RIGHT ONTO FFYLER PL. DESTINATION WILL BE ON THE LEFT. ARRIVE AT BOBDL00036A.

VICINITY MAP



NOTES

1. CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS.
2. ANTENNAS AND MOUNTS OMITTED FOR CLARITY.

NOTES

1. CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS.
2. CONTRACTOR SHALL MAINTAIN A 10'-0" MINIMUM SEPARATION BETWEEN THE PROPOSED GPS UNIT, TRANSMITTING ANTENNAS AND EXISTING GPS UNITS.
3. ANTENNAS AND MOUNTS OMITTED FOR CLARITY.

dish
wireless.

5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120

CROWN CASTLE

2000 CORPORATE DRIVE
CANONSBURG, PA 15317

B+T GRP

1717 S. BOULDER
SUITE 300
TULSA, OK 74119
PH: (918) 587-4630
www.btgrp.com



B&T ENGINEERING, INC.
PEC.0001564
Expires 2/10/22

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY: CHECKED BY: APPROVED BY:
JJR RMC MDW

RFDS REV #: ---

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	5/28/21	ISSUED FOR REVIEW
0	7/1/21	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
151123.001.01


DISH Wireless L.L.C.
PROJECT INFORMATION

BOBDL0036A
44 FFYLER PLACE
SUFFIELD, CT 06078


SHEET TITLE
OVERALL AND ENLARGED
SITE PLAN

SHEET NUMBER


A-1



ENLARGED SITE PLAN



2




OVERALL UTILITY PLAN

NO SCALE

3


OVERALL SITE PLAN



1

NOTES

1. CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS.
2. ANTENNA AND MW DISH SPECIFICATIONS REFER TO ANTENNA SCHEDULE AND TO FINAL CONSTRUCTION RFDS FOR ALL RF DETAILS
3. EXISTING EQUIPMENT AND FENCE OMITTED FOR CLARITY.



(1) PROPOSED DISH Wireless L.L.C. HYBRID CABLE ROUTED OUTSIDE POLE

EXISTING MONOPOLE


PROPOSED DISH Wireless L.L.C. ICE BRIDGE

PROPOSED DISH Wireless L.L.C. EQUIPMENT ON PROPOSED STEEL PLATFORM


PROPOSED DISH Wireless L.L.C. GPS UNIT (BEHIND CABINET)

EXISTING MONOPOLE
BOTTOM EL. @ 6" AGL


PROPOSED SOUTH ELEVATION



1



ANTENNA LAYOUT



2

SECTOR	POSITION	ANTENNA					TRANSMISSION CABLE	
		EXISTING OR PROPOSED	MANUFACTURER - MODEL NUMBER	TECHNOLOGY	SIZE (HxW)	AZIMUTH	RAD CENTER	FEED LINE TYPE AND LENGTH
ALPHA	A1	PROPOSED	JMA WIRELESS-MX08FRO665-21	5G	72.00" x 20.0"	0°	101'-0"	(1) HIGH-CAPACITY HYBRID CABLE (140' LONG)
BETA	B1	PROPOSED	JMA WIRELESS-MX08FRO665-21	5G	72.00" x 20.0"	120°	101'-0"	
GAMMA	C1	PROPOSED	JMA WIRELESS-MX08FRO665-21	5G	72.00" x 20.0"	240°	101'-0"	

SECTOR	POSITION	RRH		NOTES
		MANUFACTURER - MODEL NUMBER	TECHNOLOGY	
ALPHA	A1	FUJITSU - TA08025-B605	5G	1. CONTRACTOR TO REFER TO FINAL CONSTRUCTION RFDS FOR ALL RF DETAILS. 2. ANTENNA AND RRH MODELS MAY CHANGE DUE TO EQUIPMENT AVAILABILITY. ALL EQUIPMENT CHANGES MUST BE APPROVED AND REMAIN IN COMPLIANCE WITH THE PROPOSED DESIGN AND STRUCTURAL ANALYSES.
	A1	FUJITSU - TA08025-B604	5G	
BETA	B1	FUJITSU - TA08025-B605	5G	
	B1	FUJITSU - TA08025-B604	5G	
GAMMA	C1	FUJITSU - TA08025-B605	5G	
	C1	FUJITSU - TA08025-B604	5G	

ANTENNA SCHEDULE

NO SCALE

3



5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



2000 CORPORATE DRIVE
CANONSBURG, PA 15317



B&T ENGINEERING, INC.
PEC.0001564
Expires 2/10/22

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY: CHECKED BY: APPROVED BY:
JJR RMC MDW

RFDS REV #:

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	5/28/21	ISSUED FOR REVIEW
0	7/1/21	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
151123.001.01


DISH Wireless L.L.C. PROJECT INFORMATION

BOBDL0036A
44 FFYLER PLACE
SUFFIELD, CT 06078


SHEET TITLE
ELEVATION, ANTENNA LAYOUT AND SCHEDULE

SHEET NUMBER

A-2




PLATFORM EQUIPMENT PLAN



1

COMMSCOPE MTC4045LP 5X7 PLATFORM	
DIMENSIONS (HxWxD)	16"x84"x60"
TOTAL WEIGHT	423 LBS

NOTE:
GC TO PROVIDE EXTENDED
THREAD FOR PLATFORM IF
REQUIRED HEIGHT EXCEEDS 17"




PLATFORM DETAIL

NO SCALE

2

KENWOOD T1701KT5-5S H-FRAME	
UNISTRUT/SUPPORT RAIL	5
WEIGHT/ VOLUME	173.6 LBS



H-FRAME DETAIL

NO SCALE

3


NOT USED

NO SCALE


4

NOTES


- CONTRACTOR TO BURY PLATFORM FEET WITH A MINIMUM OF 2" OF FILL PER EXISTING SITE SURFACE
- WEED BARRIER FABRIC TO BE ADDED AT DISCRETION OF DISH Wireless L.L.C. CONSTRUCTION MANAGER AT TIME OF CONSTRUCTION. ONE SHEET 8'x8' INSTALLED UNDER ALL FOUR FEET OF THE PLATFORM (4 MIL BLACK PLASTIC)
- EQUIPMENT CABINET OMITTED FOR CLARITY



FRONT ELEVATION



BACK ELEVATION



5



5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



2000 CORPORATE DRIVE
CANONSBURG, PA 15317



1717 S. BOULDER
SUITE 300
TULSA, OK 74119
PH: (918) 587-4630
www.btgrp.com



B&T ENGINEERING, INC.
PEC.0001564
Expires 2/10/22

IT IS A VIOLATION OF LAW FOR ANY PERSON,
UNLESS THEY ARE ACTING UNDER THE DIRECTION
OF A LICENSED PROFESSIONAL ENGINEER,
TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
JJR	RMC	MDW

RFDS REV #:

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	5/28/21	ISSUED FOR REVIEW
0	7/1/21	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
151123.001.01


DISH Wireless L.L.C.
PROJECT INFORMATION

BOBDL0036A
44 FFYLER PLACE
SUFFIELD, CT 06078

SHEET TITLE
EQUIPMENT PLATFORM AND
H-FRAME DETAILS

SHEET NUMBER


A-3



CABINET DETAIL

NO SCALE

1



POWER PROTECTION CABINET (PPC) DETAIL

NO SCALE


2



NOT USED

NO SCALE


3



NOT USED

NO SCALE


4



NETWORK INTERFACE UNIT DETAIL

NO SCALE


5



FIBER TELCO ENCLOSURE DETAIL

NO SCALE


6



ICE BRIDGE DETAIL

NO SCALE


7



TYPICAL ICE BRIDGE CONCRETE PIER DETAIL

NO SCALE

8



HYBRID CABLE RUN

NO SCALE

9



5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



2000 CORPORATE DRIVE
CANONSBURG, PA 15317



1717 S. BOULDER
SUITE 300
TULSA, OK 74119
PH: (918) 587-4630
www.blgrp.com



B&T ENGINEERING, INC.
PEC.0001564
Expires 2/10/22

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
JJR	RMC	MDW

RFDS REV #: ---

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	5/28/21	ISSUED FOR REVIEW
0	7/1/21	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
151123.001.01

DISH Wireless L.L.C.
PROJECT INFORMATION






BOBDL0036A
44 FFYLER PLACE
SUFFIELD, CT 06078

SHEET TITLE
EQUIPMENT DETAILS

SHEET NUMBER

A-4

ROSENBERGER GPSGLONASS-36-N-S	
DIMENSION (DIA x H)	69mm x 98.5mm
WEIGHT (WITH ACCESSORIES)	515.74g
CONNECTOR	N-FEMALE
FREQUENCY RANGE	1559 MHz ~ 1610.5MHz



GPS ANTENNA DETAIL NO SCALE 1

GPS MINIMUM SKY VIEW REQUIREMENTS NO SCALE 2

CABLES UNLIMITED HYBRID CABLE MINIMUM BEND RADIUS NO SCALE 3

NOT USED NO SCALE 4

NOT USED NO SCALE 5

NOT USED NO SCALE 6

NOT USED NO SCALE 7

NOT USED NO SCALE 8

NOT USED NO SCALE 9

dish
wireless.

5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120

CROWN CASTLE

2000 CORPORATE DRIVE
CANONSBURG, PA 15317

B+T GRP
1717 S. BOULDER
SUITE 300
TULSA, OK 74119
PH: (918) 587-4630
www.btgrp.com



B&T ENGINEERING, INC.
PEC.0001564
Expires 2/10/22

IT IS A VIOLATION OF LAW FOR ANY PERSON,
UNLESS THEY ARE ACTING UNDER THE DIRECTION
OF A LICENSED PROFESSIONAL ENGINEER,
TO ALTER THIS DOCUMENT.

DRAWN BY: CHECKED BY: APPROVED BY:
JJR RMC MDW

RFDS REV #: ---

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	5/28/21	ISSUED FOR REVIEW
0	7/1/21	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
151123.001.01


DISH Wireless L.L.C.
PROJECT INFORMATION

BOBDL0036A
44 FFYLER PLACE
SUFFIELD, CT 06078


SHEET TITLE
EQUIPMENT DETAILS

SHEET NUMBER
A-5


FUJITSU TA08025-B604 RRH	
DIMENSIONS (HxWxD) (KG/IN)	380x400x200/14.9"x15.7"x7.8"
WEIGHT(KG,LB)/ VOLUME	29kg,63.9lb/ 30L
POWER SUPPLY	DC-58~-36V



PLAN



SIDE




FRONT

REMOTE RADIO HEAD DETAIL


NO SCALE

1


FUJITSU TA08025-B605 RRH	
DIMENSIONS (HxWxD) (KG/IN)	380x400x230/14.9"x15.7"x9.0"
WEIGHT(KG,LB)/ VOLUME	34kg,74.9lb/ 35L
POWER SUPPLY	DC-58~-36V



PLAN



SIDE



FRONT


REMOTE RADIO HEAD DETAIL

NO SCALE

2


SABRE INDUSTRIES RRU BRACKET MOUNT C10123155	
DIMENSIONS (HxWxD) (1 BRACKET)	5"x20"x1-13/16"
WEIGHT (FULL ASSEMBLY)	35.79 lbs
PACKAGE QUANTITY	4

ITEM#	DESCRIPTION
1	PLATE, CHANNEL BRACKET
2	RRH Z BRACKET, 3/16"
3	THREADED ROD ASSEMBLY 1/2"x12"



11MM x 30MM SLOTS
40MM ON CENTER

11MM x 24MM SLOTS



REMOTE RADIO MOUNT DETAIL

NO SCALE

3

JMA WIRELESS MX08FRO665-21 ANTENNA	
DIMENSIONS (HxWxD)	72.0"x20.0"x8.0"
TOTAL WEIGHT	64.5 LB
RF PORTS, CONNECTOR TYPE	8 x 4.3-10 FEMALE



PLAN



BACK



SIDE





FRONT

ANTENNA DETAIL

NO SCALE

4

COMMSCOPE XP-2040 CROSSOVER PLATE	
DIMENSIONS (HxW)	10"x12"
WEIGHT	11.023 LBS





RRH/OVP MOUNT DETAIL

NO SCALE

8

COMMSCOPE MC-PK8-DSH	
FACE WIDTH	96"
WEIGHT	1373.08 lbs
NOTE: 15" TO 38" O.D.	



ANTENNA PLATFORM DETAIL

NO SCALE

9


RAYCAP RDIDC-9181-PF-48 DC SURGE PROTECTION (OVP)	
DIMENSIONS (HxWxD)	18.98"x14.39"x8.15"
WEIGHT	21.82 LBS




PLAN



SIDE



BACK



FRONT

SURGE SUPPRESSION DETAIL (OVP)

NO SCALE

7



5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



2000 CORPORATE DRIVE
CANONSBURG, PA 15317



1717 S. BOULDER
SUITE 300
TULSA, OK 74119
PH: (918) 587-4630
www.blgrp.com



B&T ENGINEERING, INC.
PEC.0001564
Expires 2/10/22

IT IS A VIOLATION OF LAW FOR ANY PERSON,
UNLESS THEY ARE ACTING UNDER THE DIRECTION
OF A LICENSED PROFESSIONAL ENGINEER,
TO ALTER THIS DOCUMENT.

DRAWN BY: CHECKED BY: APPROVED BY:

JJR RMC MDW

RFDS REV #: ---

**CONSTRUCTION
DOCUMENTS**

SUBMITTALS		
REV	DATE	DESCRIPTION
A	5/28/21	ISSUED FOR REVIEW
0	7/1/21	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
151123.001.01


DISH Wireless L.L.C.
PROJECT INFORMATION

BOBDL0036A
44 FFYLER PLACE
SUFFIELD, CT 06078

SHEET TITLE
EQUIPMENT DETAILS

SHEET NUMBER

A-6




NOTES

1. CONTRACTOR SHALL FIELD VERIFY ALL PROPOSED UNDERGROUND UTILITY CONDUIT ROUTE.
2. ANTENNAS AND MOUNTS OMITTED FOR CLARITY.

UTILITY ROUTE PLAN

DC POWER WIRING SHALL BE COLOR CODED AT EACH END FOR IDENTIFYING +24V AND -48V CONDUCTORS. RED MARKINGS SHALL IDENTIFY +24V AND BLUE MARKINGS SHALL IDENTIFY -48V.

1. CONTRACTOR SHALL INSPECT THE EXISTING CONDITIONS PRIOR TO SUBMITTING A BID. ANY QUESTIONS ARISING DURING THE BID PERIOD IN REGARDS TO THE CONTRACTOR'S FUNCTIONS, THE SCOPE OF WORK, OR ANY OTHER ISSUE RELATED TO THIS PROJECT SHALL BE BROUGHT UP DURING THE BID PERIOD WITH THE PROJECT MANAGER FOR CLARIFICATION, NOT AFTER THE CONTRACT HAS BEEN AWARDED.
2. ALL ELECTRICAL WORK SHALL BE DONE IN ACCORDANCE WITH CURRENT NATIONAL ELECTRICAL CODES AND ALL STATE AND LOCAL CODES, LAWS, AND ORDINANCES. PROVIDE ALL COMPONENTS AND WIRING SIZES AS REQUIRED TO MEET NEC STANDARDS.
3. LOCATION OF EQUIPMENT, CONDUIT AND DEVICES SHOWN ON THE DRAWINGS ARE APPROXIMATE AND SHALL BE COORDINATED WITH FIELD CONDITIONS PRIOR TO CONSTRUCTION.
4. CONDUIT ROUGH-IN SHALL BE COORDINATED WITH THE MECHANICAL EQUIPMENT TO AVOID LOCATION CONFLICTS. VERIFY WITH THE MECHANICAL EQUIPMENT CONTRACTOR AND COMPLY AS REQUIRED.
5. CONTRACTOR SHALL PROVIDE ALL BREAKERS, CONDUITS AND CIRCUITS AS REQUIRED FOR A COMPLETE SYSTEM.
6. CONTRACTOR SHALL PROVIDE PULL BOXES AND JUNCTION BOXES AS REQUIRED BY THE NEC ARTICLE 314.
7. CONTRACTOR SHALL PROVIDE ALL STRAIN RELIEF AND CABLE SUPPORTS FOR ALL CABLE ASSEMBLIES. INSTALLATION SHALL BE IN ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS AND RECOMMENDATIONS.
8. ALL DISCONNECTS AND CONTROLLING DEVICES SHALL BE PROVIDED WITH ENGRAVED PHENOLIC NAMEPLATES INDICATING EQUIPMENT CONTROLLED, BRANCH CIRCUITS INSTALLED ON, AND PANEL FIELD LOCATIONS FED FROM.
9. INSTALL AN EQUIPMENT GROUNDING CONDUCTOR IN ALL CONDUITS PER THE SPECIFICATIONS AND NEC 250. THE EQUIPMENT GROUNDING CONDUCTORS SHALL BE BONDED AT ALL JUNCTION BOXES, PULL BOXES, AND ALL DISCONNECT SWITCHES, AND EQUIPMENT CABINETS.
10. ALL NEW MATERIAL SHALL HAVE A U.L. LABEL.
11. PANEL SCHEDULE LOADING AND CIRCUIT ARRANGEMENTS REFLECT POST-CONSTRUCTION EQUIPMENT.
12. CONTRACTOR SHALL BE RESPONSIBLE FOR AS-BUILT PANEL SCHEDULE AND SITE DRAWINGS.
13. ALL TRENCHES IN COMPOUND TO BE HAND DUG



ELECTRICAL NOTES

NO SCALE 2



5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



2000 CORPORATE DRIVE
CANONSBURG, PA 15317



1717 S. BOULDER
SUITE 300
TULSA, OK 74119
PH: (918) 587-4630
www.btgrp.com



B&T ENGINEERING, INC.
PEC.0001564
Expires 2/10/22

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
JJR	RMC	MDW

RFDS REV #: ---

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	5/28/21	ISSUED FOR REVIEW
0	7/1/21	ISSUED FOR CONSTRUCTION


A&E PROJECT NUMBER
151123.001.01

DISH Wireless L.L.C.
PROJECT INFORMATION
BOBDL00036A
44 FFYLER PLACE
SUFFIELD, CT 06078

SHEET TITLE
ELECTRICAL/FIBER ROUTE PLAN AND NOTES

SHEET NUMBER
E-1



CARLON EXPANSION FITTINGS				
COUPLING END PART#	MALE TERMINAL ADAPTER END PART#	SIZE	STD CTN QTY.	TRAVEL LENGTH
E945D	E945DX	1/2"	20	4"
E945E	E945EX	3/4"	15	4"
E945F	E945FX	1"	10	4"
E945G	E945GX	1 1/4"	5	4"
E945H	E945HX	1 1/2"	5	4"
E945J	E945JX	2"	15	8"
E945K	E945KX	2 1/2"	10	8"
E945L	E945LX	3"	10	8"
E945M	E945MX	3 1/2"	5	8"
E945N	E945NX	4"	5	8"
E945P	E945PX	5"	1	8"
E945R	E945RX	6"	1	8"



NOTE: CONTRACTOR TO INSTALL EXPANSION FITTING SLIP JOINT AT METER CENTER CONDUIT TERMINATION, AS PER LOCAL UTILITY POLICY, ORDINANCE AND/OR SPECIFIED REQUIREMENT.

TRENCHING NOTES

- CONTRACTOR SHALL RESTORE THE TRENCH TO ITS ORIGINAL CONDITIONS BY EITHER SEEDING OR SODDING GRASS AREAS, OR REPLACING ASPHALT OR CONCRETE AREAS TO ITS ORIGINAL CROSS SECTION.
- TRENCHING SAFETY; INCLUDING, BUT NOT LIMITED TO SOIL CLASSIFICATION, SLOPING, AND SHORING, SHALL BE GOVERNED BY THE CURRENT OSHA TRENCHING AND EXCAVATION SAFETY STANDARDS.
- ALL CONDUITS SHALL BE INSTALLED IN COMPLIANCE WITH THE CURRENT NATIONAL ELECTRIC CODE (NEC) OR AS REQUIRED BY THE LOCAL JURISDICTION, WHICHEVER IS THE MOST STRINGENT.



5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



2000 CORPORATE DRIVE
CANONSBURG, PA 15317



1717 S. BOULDER
SUITE 300
TULSA, OK 74119
PH: (918) 587-4630
www.btgrp.com



B&T ENGINEERING, INC.
PEC.0001564
Expires 2/10/22

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY: CHECKED BY: APPROVED BY:
JJR RMC MDW

RFDS REV #: ---

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	5/28/21	ISSUED FOR REVIEW
0	7/1/21	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
151123.001.01

DISH Wireless L.L.C.
PROJECT INFORMATION
BOBDL0036A
44 FFYLER PLACE
SUFFIELD, CT 06078


SHEET TITLE
ELECTRICAL
DETAILS

SHEET NUMBER
E-2

EXPANSION JOINT DETAIL NO SCALE 1

TYPICAL UNDERGROUND TRENCH DETAIL NO SCALE 2

DARK TELCO BOX – INTERIOR WIRING LAYOUT NO SCALE 3



LIT TELCO BOX – INTERIOR WIRING LAYOUT (OPTIONAL) NO SCALE 4



NOT USED NO SCALE 5

NOT USED NO SCALE 6

NOT USED NO SCALE 7

NOT USED NO SCALE 8

NOT USED NO SCALE 9



NOTE:
BRANCH CIRCUIT WIRING SUPPLYING RECTIFIERS ARE TO BE RATED UL1015, 105°C, 600V, AND PVC INSULATED, IN THE SIZES SHOWN IN THE ONE-LINE DIAGRAM. CONTRACTOR MAY SUBSTITUTE UL1015 WIRE FOR THWN-2 FOR CONVENIENCE OUTLET BRANCH CIRCUIT.

BREAKERS REQUIRED:
(4) 30A, 2P BREAKER - SQUARE D P/N:Q0230
(1) 15A, 1P BREAKER - SQUARE D P/N:Q0115

PPC ONE-LINE DIAGRAM

NOTES

THE ENGINEER OF RECORD HAS PERFORMED ALL REQUIRED SHORT CIRCUIT CALCULATIONS AND THE AIC RATINGS FOR EACH DEVICE IS ADEQUATE TO PROTECT THE EQUIPMENT AND THE ELECTRICAL SYSTEM.

THE ENGINEER OF RECORD HAS PERFORMED ALL REQUIRED VOLTAGE DROP CALCULATIONS AND ALL BRANCH CIRCUIT AND FEEDERS COMPLY WITH THE NEC (LISTED ON T-1) ARTICLE 210.19(A)(1) FPN NO. 4.

THE (2) CONDUITS WITH (4) CURRENT CARRYING CONDUCTORS EACH, SHALL APPLY THE ADJUSTMENT FACTOR OF 80% PER 2014/17 NEC TABLE 310.15(B)(3)(a) OR 2020 NEC TABLE 310.15(C)(1) FOR UL1015 WIRE.

#12 FOR 15A-20A/1P BREAKER: 0.8 x 30A = 24.0A
#10 FOR 25A-30A/2P BREAKER: 0.8 x 40A = 32.0A
#8 FOR 35A-40A/2P BREAKER: 0.8 x 55A = 44.0A
#6 FOR 45A-60A/2P BREAKER: 0.8 x 75A = 60.0A

CONDUIT SIZING: AT 40% FILL PER NEC CHAPTER 9, TABLE 4, ARTICLE 358.
0.5" CONDUIT - 0.122 SQ. IN AREA
0.75" CONDUIT - 0.213 SQ. IN AREA
2.0" CONDUIT - 1.316 SQ. IN AREA
3.0" CONDUIT - 2.907 SQ. IN AREA

CABINET CONVENIENCE OUTLET CONDUCTORS (1 CONDUIT): USING THWN-2, CU.
#10 - 0.0211 SQ. IN X 2 = 0.0422 SQ. IN
#10 - 0.0211 SQ. IN X 1 = 0.0211 SQ. IN <GROUND
TOTAL = 0.0633 SQ. IN

0.5" EMT CONDUIT IS ADEQUATE TO HANDLE THE TOTAL OF (3) WIRES, INCLUDING GROUND WIRE, AS INDICATED ABOVE.

RECTIFIER CONDUCTORS (2 CONDUITS): USING UL1015, CU.
#10 - 0.0266 SQ. IN X 4 = 0.1064 SQ. IN
#10 - 0.0082 SQ. IN X 1 = 0.0082 SQ. IN <BARE GROUND
TOTAL = 0.1146 SQ. IN

0.75" EMT CONDUIT IS ADEQUATE TO HANDLE THE TOTAL OF (5) WIRES, INCLUDING GROUND WIRE, AS INDICATED ABOVE.

PPC FEED CONDUCTORS (1 CONDUIT): USING THWN, CU.
3/0 - 0.2679 SQ. IN X 3 = 0.8037 SQ. IN
#6 - 0.0507 SQ. IN X 1 = 0.0507 SQ. IN <GROUND
TOTAL = 0.8544 SQ. IN

3.0" SCH 40 PVC CONDUIT IS ADEQUATE TO HANDLE THE TOTAL OF (4) WIRES, INCLUDING GROUND WIRE, AS INDICATED ABOVE.



5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



2000 CORPORATE DRIVE
CANONSBURG, PA 15317



1717 S. BOULDER
SUITE 300
TULSA, OK 74119
PH: (918) 587-4630
www.blgrp.com



B&T ENGINEERING, INC.
PEC.0001564
Expires 2/10/22

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY: CHECKED BY: APPROVED BY:
JJR RMC MDW

RFDS REV #: ---

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	5/28/21	ISSUED FOR REVIEW
0	7/1/21	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
151123.001.01

DISH Wireless L.L.C.
PROJECT INFORMATION

BOBDL0036A
44 FFYLER PLACE
SUFFIELD, CT 06078

SHEET TITLE
ELECTRICAL ONE-LINE, FAULT
CALCS & PANEL SCHEDULE

SHEET NUMBER

E-3

PROPOSED CHARLES PANEL SCHEDULE										
LOAD SERVED	VOLT AMPS (WATTS)		TRIP	CKT #	PHASE	CKT #	TRIP	VOLT AMPS (WATTS)		LOAD SERVED
	L1	L2						L1	L2	
PPC GFCI OUTLET	180	180	15A	1	A	2	30A	2880	2880	ABB/GE INFINITY RECTIFIER 1
CHARLES GFCI OUTLET	180	180	15A	3	B	4	30A	2880	2880	ABB/GE INFINITY RECTIFIER 1
-SPACE-				5	A	6	30A	2880	2880	ABB/GE INFINITY RECTIFIER 2
-SPACE-				7	B	8	30A	2880	2880	ABB/GE INFINITY RECTIFIER 2
-SPACE-				9	A	10	30A	2880	2880	ABB/GE INFINITY RECTIFIER 3
-SPACE-				11	B	12	30A	2880	2880	ABB/GE INFINITY RECTIFIER 3
-SPACE-				13	A	14	30A	2880	2880	ABB/GE INFINITY RECTIFIER 4
-SPACE-				15	B	16	30A	2880	2880	ABB/GE INFINITY RECTIFIER 4
-SPACE-				17	A	18				-SPACE-
-SPACE-				19	B	20				-SPACE-
-SPACE-				21	A	22				-SPACE-
-SPACE-				23	B	24				-SPACE-
VOLTAGE AMPS		180	180					11520	11520	
200A MCB, 1φ, 24 SPACE, 120/240V				L1	L2					
MB RATING: 65,000 AIC				11700	11700					
				98	98					VOLTAGE AMPS
										AMPS
										MAX AMPS
										MAX 125%


PANEL SCHEDULE

NO SCALE 2

FAULT CURRENT VALUES BASED ON POINT-TO-POINT METHOD OF CALCULATION			
F1 (SINGLE PHASE)		F3 (SINGLE PHASE)	
LOCATION: TRANSFORMER		LOCATION: DISCONNECT	
TRANSFORMER SIZE =	50 kVA	TYPE OF CONDUIT:	RGS
SECONDARY VOLTAGE (L-L) =	240 V	CONDUCTOR SIZE AND TYPE:	3/0 COPPER
SECONDARY VOLTAGE (L-N) =	120 V	SETS OF CONDUCTORS =	1
ISC =	12327 A	LENGTH OF CONDUCTORS =	5 FEET
		"C" VALUE =	8925
		f(L-L) =	0.0157
		M(L-L) =	0.9845
		f(L-N) =	0.0182
		M(L-N) =	0.9822
		ISC (L-L) =	3,309 A
		ISC (L-N) =	1,911 A
F2 (SINGLE PHASE)		F4 (SINGLE PHASE)	
LOCATION: METER		LOCATION: 200A PPC	
TYPE OF CONDUIT:	RGS	TYPE OF CONDUIT:	PVC
CONDUCTOR SIZE AND TYPE:	1/0 AL	CONDUCTOR SIZE AND TYPE:	3/0 COPPER
SETS OF CONDUCTORS =	1	SETS OF CONDUCTORS =	1
LENGTH OF CONDUCTORS =	150 FEET	LENGTH OF CONDUCTORS =	55 FEET
"C" VALUE =	5777	"C" VALUE =	13923
f(L-L) =	2.6673	f(L-L) =	0.1089
M(L-L) =	0.2727	M(L-L) =	0.9018
f(L-N) =	5.3345	f(L-N) =	0.2179
M(L-N) =	0.1579	M(L-N) =	0.8211
ISC (L-L) =	3,361 A	ISC (L-L) =	2,984 A
ISC (L-N) =	1,946 A	ISC (L-N) =	1,569 A

FAULT CALCULATIONS

NO SCALE 3




TYPICAL EQUIPMENT GROUNDING PLAN

NO SCALE 1


NOTES

1. ANTENNAS AND OVP SHOWN ARE GENERIC AND NOT REFERENCING TO A SPECIFIC MANUFACTURER. THIS LAYOUT IS FOR REFERENCE ONLY



TYPICAL ANTENNA GROUNDING PLAN

NO SCALE 2



GROUNDING LEGEND

1. GROUNDING IS SHOWN DIAGRAMMATICALLY ONLY.
2. CONTRACTOR SHALL GROUND ALL EQUIPMENT AS A COMPLETE SYSTEM. GROUNDING SHALL BE IN COMPLIANCE WITH NEC SECTION 250 AND DISH Wireless L.L.C. GROUNDING AND BONDING REQUIREMENTS AND MANUFACTURER'S SPECIFICATIONS.
3. ALL GROUND CONDUCTORS SHALL BE COPPER; NO ALUMINUM CONDUCTORS SHALL BE USED.

GROUNDING KEY NOTES

- EXTERIOR GROUND RING:** #2 AWG SOLID COPPER, BURIED AT A DEPTH OF AT LEAST 30 INCHES BELOW GRADE, OR 6 INCHES BELOW THE FROST LINE AND APPROXIMATELY 24 INCHES FROM THE EXTERIOR WALL OR FOOTING.
- TOWER GROUND RING:** THE GROUND RING SYSTEM SHALL BE INSTALLED AROUND AN ANTENNA TOWER'S LEGS, AND/OR GUY ANCHORS. WHERE SEPARATE SYSTEMS HAVE BEEN PROVIDED FOR THE TOWER AND THE BUILDING, AT LEAST TWO BONDS SHALL BE MADE BETWEEN THE TOWER RING GROUND SYSTEM AND THE BUILDING RING GROUND SYSTEM USING MINIMUM #2 AWG SOLID COPPER CONDUCTORS.
- INTERIOR GROUND RING:** #2 AWG STRANDED GREEN INSULATED COPPER CONDUCTOR EXTENDED AROUND THE PERIMETER OF THE EQUIPMENT AREA. ALL NON-TELECOMMUNICATIONS RELATED METALLIC OBJECTS FOUND WITHIN A SITE SHALL BE GROUNDED TO THE INTERIOR GROUND RING WITH #6 AWG STRANDED GREEN INSULATED CONDUCTOR.
- BOND TO INTERIOR GROUND RING:** #2 AWG SOLID TINNED COPPER WIRE PRIMARY BONDS SHALL BE PROVIDED AT LEAST AT FOUR POINTS ON THE INTERIOR GROUND RING, LOCATED AT THE CORNERS OF THE BUILDING.
- GROUND ROD:** UL LISTED COPPER CLAD STEEL MINIMUM 1/2" DIAMETER BY EIGHT FEET LONG. GROUND RODS SHALL BE INSTALLED WITH INSPECTION SLEEVES. GROUND RODS SHALL BE DRIVEN TO THE DEPTH OF GROUND RING CONDUCTOR.
- CELL REFERENCE GROUND BAR:** POINT OF GROUND REFERENCE FOR ALL COMMUNICATIONS EQUIPMENT FRAMES. ALL BONDS ARE MADE WITH #2 AWG UNLESS NOTED OTHERWISE STRANDED GREEN INSULATED COPPER CONDUCTORS. BOND TO GROUND RING WITH (2) #2 SOLID TINNED COPPER CONDUCTORS.
- HATCH PLATE GROUND BAR:** BOND TO THE INTERIOR GROUND RING WITH TWO #2 AWG STRANDED GREEN INSULATED COPPER CONDUCTORS. WHEN A HATCH-PLATE AND A CELL REFERENCE GROUND BAR ARE BOTH PRESENT, THE CRGB MUST BE CONNECTED TO THE HATCH-PLATE AND TO THE INTERIOR GROUND RING USING (2) TWO #2 AWG STRANDED GREEN INSULATED COPPER CONDUCTORS EACH.
- EXTERIOR CABLE ENTRY PORT GROUND BARS:** LOCATED AT THE ENTRANCE TO THE CELL SITE BUILDING. BOND TO GROUND RING WITH A #2 AWG SOLID TINNED COPPER CONDUCTORS WITH AN EXOTHERMIC WELD AND INSPECTION SLEEVE.
- TELCO GROUND BAR:** BOND TO BOTH CELL REFERENCE GROUND BAR OR EXTERIOR GROUND RING.
- FRAME BONDING:** THE BONDING POINT FOR TELECOM EQUIPMENT FRAMES SHALL BE THE GROUND BUS THAT IS NOT ISOLATED FROM THE EQUIPMENTS METAL FRAMEWORK.
- INTERIOR UNIT BONDS:** METAL FRAMES, CABINETS AND INDIVIDUAL METALLIC UNITS LOCATED WITH THE AREA OF THE INTERIOR GROUND RING REQUIRE A #6 AWG STRANDED GREEN INSULATED COPPER BOND TO THE INTERIOR GROUND RING.
- FENCE AND GATE GROUNDING:** METAL FENCES WITHIN 7 FEET OF THE EXTERIOR GROUND RING OR OBJECTS BONDED TO THE EXTERIOR GROUND RING SHALL BE BONDED TO THE GROUND RING WITH A #2 AWG SOLID TINNED COPPER CONDUCTOR AT AN INTERVAL NOT EXCEEDING 25 FEET. BONDS SHALL BE MADE AT EACH GATE POST AND ACROSS GATE OPENINGS.
- EXTERIOR UNIT BONDS:** METALLIC OBJECTS, EXTERNAL TO OR MOUNTED TO THE BUILDING, SHALL BE BONDED TO THE EXTERIOR GROUND RING. USING #2 TINNED SOLID COPPER WIRE
- ICE BRIDGE SUPPORTS:** EACH ICE BRIDGE LEG SHALL BE BONDED TO THE GROUND RING WITH #2 AWG BARE TINNED COPPER CONDUCTOR. PROVIDE EXOTHERMIC WELDS AT BOTH THE ICE BRIDGE LEG AND BURIED GROUND RING.
- DURING ALL DC POWER SYSTEM CHANGES INCLUDING DC SYSTEM CHANGE OUTS, RECTIFIER REPLACEMENTS OR ADDITIONS, BREAKER DISTRIBUTION CHANGES, BATTERY ADDITIONS, BATTERY REPLACEMENTS AND INSTALLATIONS OR CHANGES TO DC CONVERTER SYSTEMS IT SHALL BE REQUIRED THAT SERVICE CONTRACTORS VERIFY ALL DC POWER SYSTEMS ARE EQUIPPED WITH A MASTER DC SYSTEM RETURN GROUND CONDUCTOR FROM THE DC POWER SYSTEM COMMON RETURN BUS DIRECTLY CONNECTED TO THE CELL SITE REFERENCE GROUND BAR**
- TOWER TOP COLLECTOR BUSS BAR IS TO BE MECHANICALLY BONDED TO PROPOSED ANTENNA MOUNT COLLAR. REFER TO DISH Wireless L.L.C. GROUNDING NOTES.**

GROUNDING KEY NOTES

NO SCALE 3



5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



2000 CORPORATE DRIVE
CANONSBURG, PA 15317



1717 S. BOULDER
SUITE 300
TULSA, OK 74119
PH: (918) 587-4630
www.btgrp.com



B&T ENGINEERING, INC.
PEC.0001564
Expires 2/10/22

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY: CHECKED BY: APPROVED BY:
JJR RMC MDW

RFDS REV #: ---

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	5/28/21	ISSUED FOR REVIEW
0	7/1/21	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
151123.001.01

DISH Wireless L.L.C.
PROJECT INFORMATION

BOBDL0036A
44 FFYLER PLACE
SUFFIELD, CT 06078


SHEET TITLE
GROUNDING PLANS
AND NOTES

SHEET NUMBER

G-1

NOTES

EQUIPMENT CABINET OMITTED FOR CLARITY




#2 TINNED SOLID IN 1/2" MIN. LIQUID TIGHT CONDUIT FROM 24" BELOW GRADE TO WITHIN 3" TO 6" OF CAD-WELD TERMINATION POINT. EXPOSED END OF THE LIQUID TIGHT CONDUIT MUST BE SEALED WITH SILICONE CAULK. (TYP)

H-FRAME GROUNDING DETAIL

NO SCALE 1


NOTES

CABLE GROUNDING **NOT** REQUIRED WHEN ANTENNA IS LESS THAN 10' FROM CABINET




TYPICAL GPS UNIT GROUNDING

NO SCALE 2




OUTDOOR CABINET GROUNDING

NO SCALE 3




TRANSITIONING GROUND DETAIL

NO SCALE 4



TYPICAL TEST GROUND ROD WITH INSPECTION SLEEVE

NO SCALE 5



TYPICAL GROUND RING TRENCH

NO SCALE 6

dish wireless.

5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120

CROWN CASTLE

2000 CORPORATE DRIVE
CANONSBURG, PA 15317

B+T GRP

1717 S. BOULDER
SUITE 300
TULSA, OK 74119
PH: (918) 587-4630
www.blgrp.com



B&T ENGINEERING, INC.
PEC.0001564
Expires 2/10/22

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY: CHECKED BY: APPROVED BY:

JJR RMC MDW

RFDS REV #: ---

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	5/28/21	ISSUED FOR REVIEW
0	7/1/21	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
151123.001.01

DISH Wireless L.L.C.
PROJECT INFORMATION



BOBDL0036A
44 FFYLER PLACE
SUFFIELD, CT 06078

SHEET TITLE
GROUNDING DETAILS

SHEET NUMBER

G-2

1. EXOTHERMIC WELD (2) TWO, #2 AWG BARE TINNED SOLID COPPER CONDUCTORS TO GROUND BAR. ROUTE CONDUCTORS TO BURIED GROUND RING AND PROVIDE PARALLEL EXOTHERMIC WELD.
2. ALL EXTERIOR GROUNDING HARDWARE SHALL BE STAINLESS STEEL 3/8" DIAMETER OR LARGER. ALL HARDWARE 18-8 STAINLESS STEEL INCLUDING LOCK WASHERS, COAT ALL SURFACES WITH AN ANTI-OXIDANT COMPOUND BEFORE MATING.
3. FOR GROUND BOND TO STEEL ONLY: COAT ALL SURFACES WITH AN ANTI-OXIDANT COMPOUND BEFORE MATING.
4. DO NOT INSTALL CABLE GROUNDING KIT AT A BEND AND ALWAYS DIRECT GROUND CONDUCTOR DOWN TO GROUNDING BUS.
5. NUT & WASHER SHALL BE PLACED ON THE FRONT SIDE OF THE GROUND BAR AND BOLTED ON THE BACK SIDE.
6. ALL GROUNDING PARTS AND EQUIPMENT TO BE SUPPLIED AND INSTALLED BY CONTRACTOR.
7. THE CONTRACTOR SHALL BE RESPONSIBLE FOR INSTALLING ADDITIONAL GROUND BAR AS REQUIRED.
8. ENSURE THE WIRE INSULATION TERMINATION IS WITHIN 1/8" OF THE BARREL (NO SHINERS).



TYPICAL GROUNDING NOTES


NO SCALE 1

TYPICAL EXTERIOR TWO HOLE LUG

NO SCALE 2

TYPICAL INTERIOR TWO HOLE LUG

NO SCALE 3



LUG DETAIL

NO SCALE 4

NOT USED

NO SCALE 5

NOT USED

NO SCALE 6

NOT USED

NO SCALE 7

NOT USED

NO SCALE 8

NOT USED

NO SCALE 9



5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



2000 CORPORATE DRIVE
CANONSBURG, PA 15317



B&T ENGINEERING, INC.
PEC.0001564
Expires 2/10/22

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY: CHECKED BY: APPROVED BY:
JJR RMC MDW

RFDS REV #: ---

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	5/28/21	ISSUED FOR REVIEW
0	7/1/21	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
151123.001.01

DISH Wireless L.L.C.
PROJECT INFORMATION
BOBDL0036A
44 FFYLER PLACE
SUFFIELD, CT 06078

SHEET TITLE
GROUNDING DETAILS

SHEET NUMBER
G-3

RF JUMPER COLOR CODING

3/4" TAPE WIDTHS WITH 3/4" SPACING

LOW-BAND RRH -
(600MHz N71 BASEBAND) +
(850MHz N26 BAND) +
(700MHz N29 BAND) - OPTIONAL PER MARKET

ADD FREQUENCY COLOR TO SECTOR BAND
(CBRS WILL USE YELLOW BANDS)

ALPHA RRH				BETA RRH				GAMMA RRH			
PORT 1 + SLANT	PORT 2 - SLANT	PORT 3 + SLANT	PORT 4 - SLANT	PORT 1 + SLANT	PORT 2 - SLANT	PORT 3 + SLANT	PORT 4 - SLANT	PORT 1 + SLANT	PORT 2 - SLANT	PORT 3 + SLANT	PORT 4 - SLANT
RED	RED	RED	RED	BLUE	BLUE	BLUE	BLUE	GREEN	GREEN	GREEN	GREEN
ORANGE	ORANGE	RED	RED	ORANGE	ORANGE	BLUE	BLUE	ORANGE	ORANGE	GREEN	GREEN
	WHITE (-) PORT	ORANGE	ORANGE		WHITE (-) PORT	ORANGE	ORANGE		WHITE (-) PORT	ORANGE	ORANGE
			WHITE (-) PORT				WHITE (-) PORT				WHITE (-) PORT

MID-BAND RRH -
(AWS BANDS N66+N70)

ADD FREQUENCY COLOR TO SECTOR BAND
(CBRS WILL USE YELLOW BANDS)

RED	RED	RED	RED	BLUE	BLUE	BLUE	BLUE	GREEN	GREEN	GREEN	GREEN
PURPLE	PURPLE	RED	RED	PURPLE	PURPLE	BLUE	BLUE	PURPLE	PURPLE	GREEN	GREEN
	WHITE (-) PORT	PURPLE	PURPLE		WHITE (-) PORT	PURPLE	PURPLE		WHITE (-) PORT	PURPLE	PURPLE
			WHITE (-) PORT				WHITE (-) PORT				WHITE (-) PORT

HYBRID/DISCREET CABLES

INCLUDE SECTOR BANDS BEING SUPPORTED
ALONG WITH FREQUENCY BANDS

EXAMPLE 1 - HYBRID, OR DISCREET, SUPPORTS
ALL SECTORS, BOTH LOW-BANDS AND MID-BANDS

EXAMPLE 2 - HYBRID, OR DISCREET, SUPPORTS
CBRS ONLY, ALL SECTORS

EXAMPLE 1	EXAMPLE 2	EXAMPLE 3
RED	RED	RED
BLUE	BLUE	
GREEN	GREEN	ORANGE
ORANGE	YELLOW	PURPLE
PURPLE		

FIBER JUMPERS TO RRHs

LOW-BAND RRH FIBER CABLES HAVE SECTOR
STRIPE ONLY

LOW BAND RRH	HIGH BAND RRH	LOW BAND RRH	HIGH BAND RRH	LOW BAND RRH	HIGH BAND RRH
RED	RED	BLUE	BLUE	GREEN	GREEN
	PURPLE		PURPLE		PURPLE

POWER CABLES TO RRHs

LOW-BAND RRH POWER CABLES HAVE SECTOR
STRIPE ONLY

LOW BAND RRH	HIGH BAND RRH	LOW BAND RRH	HIGH BAND RRH	LOW BAND RRH	HIGH BAND RRH
RED	RED	BLUE	BLUE	GREEN	GREEN
	PURPLE		PURPLE		PURPLE

RET MOTORS AT ANTENNAS

ANTENNA 1 LOW BAND/ "IN"	ANTENNA 1 HIGH BAND/ "IN"	ANTENNA 1 LOW BAND/ "IN"	ANTENNA 1 HIGH BAND/ "IN"	ANTENNA 1 LOW BAND/ "IN"	ANTENNA 1 HIGH BAND/ "IN"
RED	RED	BLUE	BLUE	GREEN	GREEN
	PURPLE		PURPLE		PURPLE

MICROWAVE RADIO LINKS

LINKS WILL HAVE A 1.5-2 INCH WHITE WRAP WITH
THE AZIMUTH COLOR OVERLAPPING IN THE MIDDLE.
ADD ADDITIONAL SECTOR COLOR BANDS FOR EACH
ADDITIONAL MW RADIO.

MICROWAVE CABLES WILL REQUIRE P-TOUCH
LABELS INSIDE THE CABINET TO IDENTIFY THE
LOCAL AND REMOTE SITE ID'S

FORWARD AZIMUTH OF 0-120 DEGREES		FORWARD AZIMUTH OF 120-240 DEGREES		FORWARD AZIMUTH OF 240-360 DEGREES	
PRIMARY	SECONDARY	PRIMARY	SECONDARY	PRIMARY	SECONDARY
WHITE	WHITE	WHITE	WHITE	WHITE	WHITE
RED	RED	BLUE	BLUE	GREEN	GREEN
WHITE	WHITE	WHITE	WHITE	WHITE	WHITE
	RED		BLUE		GREEN
	WHITE		WHITE		WHITE

RF CABLE COLOR CODES

NO SCALE

1

LOW BANDS (N71+N26)
OPTIONAL - (N29)



AWS
(N66+N70+H-BLOCK)



CBRS TECH
(3 GHz)



NEGATIVE SLANT PORT
ON ANT/RRH



ALPHA SECTOR



BETA SECTOR



GAMMA SECTOR



COLOR IDENTIFIER

NO SCALE

2

NOT USED

NO SCALE

3

NOT USED

NO SCALE

4



5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



2000 CORPORATE DRIVE
CANONSBURG, PA 15317



1717 S. BOULDER
SUITE 300
TULSA, OK 74119
PH: (918) 587-4630
www.btgrp.com



B&T ENGINEERING, INC.
PEC.0001564
Expires 2/10/22

IT IS A VIOLATION OF LAW FOR ANY PERSON,
UNLESS THEY ARE ACTING UNDER THE DIRECTION
OF A LICENSED PROFESSIONAL ENGINEER,
TO ALTER THIS DOCUMENT.

DRAWN BY: CHECKED BY: APPROVED BY:

JJR RMC MDW

RFDS REV #: ---

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	5/28/21	ISSUED FOR REVIEW
0	7/1/21	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
151123.001.01

DISH Wireless L.L.C.
PROJECT INFORMATION

BOBDL0036A
44 FFYLER PLACE
SUFFIELD, CT 06078

SHEET TITLE
RF
CABLE COLOR CODES

SHEET NUMBER

RF-1



5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



2000 CORPORATE DRIVE
CANONSBURG, PA 15317



1717 S. BOULDER
SUITE 300
TULSA, OK 74119
PH: (918) 587-4630
www.btgrp.com



B&T ENGINEERING, INC.
PEC.0001564
Expires 2/10/22

IT IS A VIOLATION OF LAW FOR ANY PERSON,
UNLESS THEY ARE ACTING UNDER THE DIRECTION
OF A LICENSED PROFESSIONAL ENGINEER,
TO ALTER THIS DOCUMENT.

DRAWN BY: CHECKED BY: APPROVED BY:
JRJ RMC MDW

RFDS REV #: ---

CONSTRUCTION DOCUMENTS

SUBMITTALS

REV	DATE	DESCRIPTION
A	5/28/21	ISSUED FOR REVIEW
0	7/1/21	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
151123.001.01


DISH Wireless L.L.C.
PROJECT INFORMATION

BOBDL0036A
44 FFYLER PLACE
SUFFIELD, CT 06078

SHEET TITLE
RF
PLUMBING DIAGRAM


SHEET NUMBER

RF-2



Fiber Patch Panel

Bottom Row	Pair 1	Pair 2	Pair 3	Pair 10	Open	Open
Middle Row	Pair 4	Pair 5	Pair 6	Pair 11	Open	Open
Top Row	Pair 7	Pair 8	Pair 9	Pair 12	Open	Open




CSR NCS540

Port	Interface	Description
0	Gi0/0/0	SiteBoss
1	Gi0/0/1	CBRS - Alpha
2	Gi0/0/2	CBRS - Beta
3	Gi0/0/3	CBRS - Gamma
4	Te0/0/4	Fujitsu Low-Band RU - Alpha
5	Te0/0/5	Fujitsu Mid-Band RU - Alpha
6	Te0/0/6	Fujitsu Low-Band RU - Beta
7	Te0/0/7	Fujitsu Mid-Band RU - Beta
8	Te0/0/8	Fujitsu Low-Band RU - Gamma
9	Te0/0/9	Fujitsu Mid-Band RU - Gamma
10	Te0/0/10	Fixed Wifi
11	Te0/0/11	Fixed Wifi
12	Te0/0/12	Fixed Wifi
13	Te0/0/13	Fixed Wifi
14	Te0/0/14	CBRS1
15	Te0/0/15	CBRS2
16	Te0/0/16	CBRS3
17	Gi0/0/17	SM1 - BMC
18	Gi0/0/18	SM2 - BMC
19	Te0/0/19	SM1 - Data 1
20	Te0/0/20	SM1 - Data 2
21	Te0/0/21	SM2 - Data 1
22	Te0/0/22	SM2 - Data 2
23	Te0/0/23	Reserved Uplink (EDC, LDC)
24	Te0/0/24	Blank/Future
25	Te0/0/25	Blank/Future
26	Te0/0/26	Fiber NIU
27	Te0/0/27	Fiber NIU
28	Te0/0/28	Blank/Future
29	Te0/0/29	Blank/Future

top
bottom

Bottom OVP Layout

Circuit 1	Alpha Low Band
Circuit 2	Beta Low Band
Circuit 3	Gamma Low Band
Circuit 4	Alpha Mid Band
Circuit 5	Beta Mid Band
Circuit 6	Gamma Mid Band
Circuit 7	Alpha CBRS
Circuit 8	Beta CBRS
Circuit 9	Gamma CBRS
Circuit 10	Open
Circuit 11	Open
Circuit 12	Open




5G plumbing diagram JMA MX08FRO665-20
2-2-2(LB+MB)

REV	DATE	DESCRIPTION
3	5-Jan-2021	

PLUMBING DIAGRAM

NO SCALE 1

EXOTHERMIC CONNECTION
 MECHANICAL CONNECTION
 BUSS BAR INSULATOR
 CHEMICAL ELECTROLYTIC GROUNDING SYSTEM
 TEST CHEMICAL ELECTROLYTIC GROUNDING SYSTEM
 EXOTHERMIC WITH INSPECTION SLEEVE
 GROUNDING BAR
 GROUND ROD
 TEST GROUND ROD WITH INSPECTION SLEEVE
 SINGLE POLE SWITCH
 DUPLEX RECEPTACLE
 DUPLEX GFCI RECEPTACLE
 FLUORESCENT LIGHTING FIXTURE
 (2) TWO LAMPS 48-T8
 SMOKE DETECTION (DC)
 EMERGENCY LIGHTING (DC)
 SECURITY LIGHT W/PHOTOCELL LITHONIA ALXW
 LED-1-25A400/51K-SR4-120-PE-DBTDX
 CHAIN LINK FENCE
 WOOD/WROUGHT IRON FENCE
 WALL STRUCTURE
 LEASE AREA
 PROPERTY LINE (PL)
 SETBACKS
 ICE BRIDGE
 CABLE TRAY
 WATER LINE
 UNDERGROUND POWER
 UNDERGROUND TELCO
 OVERHEAD POWER
 OVERHEAD TELCO
 UNDERGROUND TELCO/POWER
 ABOVE GROUND POWER
 ABOVE GROUND TELCO
 ABOVE GROUND TELCO/POWER
 WORKPOINT
 SECTION REFERENCE
 DETAIL REFERENCE



LEGEND

AB ANCHOR BOLT
 ABV ABOVE
 AC ALTERNATING CURRENT
 ADDL ADDITIONAL
 AFF ABOVE FINISHED FLOOR
 AFG ABOVE FINISHED GRADE
 AGL ABOVE GROUND LEVEL
 AIC AMPERAGE INTERRUPTION CAPACITY
 ALUM ALUMINUM
 ALT ALTERNATE
 ANT ANTENNA
 APPROX APPROXIMATE
 ARCH ARCHITECTURAL
 ATS AUTOMATIC TRANSFER SWITCH
 AWG AMERICAN WIRE GAUGE
 BATT BATTERY
 BLDG BUILDING
 BLK BLOCK
 BLKG BLOCKING
 BM BEAM
 BTC BARE TINNED COPPER CONDUCTOR
 BOF BOTTOM OF FOOTING
 CAB CABINET
 CANT CANTILEVERED
 CHG CHARGING
 CLG CEILING
 CLR CLEAR
 COL COLUMN
 COMM COMMON
 CONC CONCRETE
 CONSTR CONSTRUCTION
 DBL DOUBLE
 DC DIRECT CURRENT
 DEPT DEPARTMENT
 DF DOUGLAS FIR
 DIA DIAMETER
 DIAG DIAGONAL
 DIM DIMENSION
 DWG DRAWING
 DWL DOWEL
 EA EACH
 EC ELECTRICAL CONDUCTOR
 EL ELEVATION
 ELEC ELECTRICAL
 EMT ELECTRICAL METALLIC TUBING
 ENG ENGINEER
 EQ EQUAL
 EXP EXPANSION
 EXT EXTERIOR
 EW EACH WAY
 FAB FABRICATION
 FF FINISH FLOOR
 FG FINISH GRADE
 FIF FACILITY INTERFACE FRAME
 FIN FINISH(ED)
 FLR FLOOR
 FDN FOUNDATION
 FOC FACE OF CONCRETE
 FOM FACE OF MASONRY
 FOS FACE OF STUD
 FOW FACE OF WALL
 FS FINISH SURFACE
 FT FOOT
 FTG FOOTING
 GA GAUGE
 GEN GENERATOR
 GFCI GROUND FAULT CIRCUIT INTERRUPTER
 GLB GLUE LAMINATED BEAM
 GLV GALVANIZED
 GPS GLOBAL POSITIONING SYSTEM
 GND GROUND
 GSM GLOBAL SYSTEM FOR MOBILE
 HDG HOT DIPPED GALVANIZED
 HDR HEADER
 HGR HANGER
 HVAC HEAT/VENTILATION/AIR CONDITIONING
 HT HEIGHT
 IGR INTERIOR GROUND RING
 IN INCH
 INT INTERIOR
 LB(S) POUND(S)
 LF LINEAR FEET
 LTE LONG TERM EVOLUTION
 MAS MASONRY
 MAX MAXIMUM
 MB MACHINE BOLT
 MECH MECHANICAL
 MFR MANUFACTURER
 MGB MASTER GROUND BAR
 MIN MINIMUM
 MISC MISCELLANEOUS
 MTL METAL
 MTS MANUAL TRANSFER SWITCH
 MW MICROWAVE
 NEC NATIONAL ELECTRIC CODE
 NM NEWTON METERS
 NO. NUMBER
 # NUMBER
 NTS NOT TO SCALE
 OC ON-CENTER
 OSHA OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION
 OPNG OPENING
 P/C PRECAST CONCRETE
 PCS PERSONAL COMMUNICATION SERVICES
 PCU PRIMARY CONTROL UNIT
 PRC PRIMARY RADIO CABINET
 PP POLARIZING PRESERVING
 PSF POUNDS PER SQUARE FOOT
 PSI POUNDS PER SQUARE INCH
 PT PRESSURE TREATED
 PWR POWER CABINET
 QTY QUANTITY
 RAD RADIUS
 RECT RECTIFIER
 REF REFERENCE
 REINF REINFORCEMENT
 REQ'D REQUIRED
 RET REMOTE ELECTRIC TILT
 RF RADIO FREQUENCY
 RMC RIGID METALLIC CONDUIT
 RRH REMOTE RADIO HEAD
 RRU REMOTE RADIO UNIT
 RWY RACEWAY
 SCH SCHEDULE
 SHT SHEET
 SIAD SMART INTEGRATED ACCESS DEVICE
 SIM SIMILAR
 SPEC SPECIFICATION
 SQ SQUARE
 SS STAINLESS STEEL
 STD STANDARD
 STL STEEL
 TEMP TEMPORARY
 THK THICKNESS
 TMA TOWER MOUNTED AMPLIFIER
 TN TOE NAIL
 TOA TOP OF ANTENNA
 TOC TOP OF CURB
 TOF TOP OF FOUNDATION
 TOP TOP OF PLATE (PARAPET)
 TOS TOP OF STEEL
 TOW TOP OF WALL
 TVSS TRANSIENT VOLTAGE SURGE SUPPRESSION
 TYP TYPICAL
 UG UNDERGROUND
 UL UNDERWRITERS LABORATORY
 UNO UNLESS NOTED OTHERWISE
 UMTS UNIVERSAL MOBILE TELECOMMUNICATIONS SYSTEM
 UPS UNINTERRUPTIBLE POWER SYSTEM (DC POWER PLANT)
 VIF VERIFIED IN FIELD
 W WIDE
 W/ WITH
 WD WOOD
 WP WEATHERPROOF
 WT WEIGHT

ABBREVIATIONS



5701 SOUTH SANTA FE DRIVE
 LITTLETON, CO 80120



2000 CORPORATE DRIVE
 CANONSBURG, PA 15317



B&T ENGINEERING, INC.
 PEC.0001564
 Expires 2/10/22

IT IS A VIOLATION OF LAW FOR ANY PERSON,
 UNLESS THEY ARE ACTING UNDER THE DIRECTION
 OF A LICENSED PROFESSIONAL ENGINEER,
 TO ALTER THIS DOCUMENT.

DRAWN BY: CHECKED BY: APPROVED BY:

JJR RMC MDW

RFDS REV #: ---

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	5/28/21	ISSUED FOR REVIEW
0	7/1/21	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
 151123.001.01

DISH Wireless L.L.C.
 PROJECT INFORMATION
 BOBDL00036A
 44 FFYLER PLACE
 SUFFIELD, CT 06078

SHEET TITLE
 LEGEND AND ABBREVIATIONS

SHEET NUMBER
GN-1

SITE ACTIVITY REQUIREMENTS:

- NOTICE TO PROCEED – NO WORK SHALL COMMENCE PRIOR TO CONTRACTOR RECEIVING A WRITTEN NOTICE TO PROCEED (NTP) AND THE ISSUANCE OF A PURCHASE ORDER. PRIOR TO ACCESSING/ENTERING THE SITE YOU MUST CONTACT THE DISH Wireless L.L.C. AND TOWER OWNER NOC & THE DISH Wireless L.L.C. AND TOWER OWNER CONSTRUCTION MANAGER.
- "LOOK UP" – DISH Wireless L.L.C. AND TOWER OWNER SAFETY CLIMB REQUIREMENT:
THE INTEGRITY OF THE SAFETY CLIMB AND ALL COMPONENTS OF THE CLIMBING FACILITY SHALL BE CONSIDERED DURING ALL STAGES OF DESIGN, INSTALLATION, AND INSPECTION. TOWER MODIFICATION, MOUNT REINFORCEMENTS, AND/OR EQUIPMENT INSTALLATIONS SHALL NOT COMPROMISE THE INTEGRITY OR FUNCTIONAL USE OF THE SAFETY CLIMB OR ANY COMPONENTS OF THE CLIMBING FACILITY ON THE STRUCTURE. THIS SHALL INCLUDE, BUT NOT BE LIMITED TO: PINCHING OF THE WIRE ROPE, BENDING OF THE WIRE ROPE FROM ITS SUPPORTS, DIRECT CONTACT OR CLOSE PROXIMITY TO THE WIRE ROPE WHICH MAY CAUSE FRICTIONAL WEAR, IMPACT TO THE ANCHORAGE POINTS IN ANY WAY, OR TO IMPEDE/BLOCK ITS INTENDED USE. ANY COMPROMISED SAFETY CLIMB, INCLUDING EXISTING CONDITIONS MUST BE TAGGED OUT AND REPORTED TO YOUR DISH Wireless L.L.C. AND DISH Wireless L.L.C. AND TOWER OWNER POC OR CALL THE NOC TO GENERATE A SAFETY CLIMB MAINTENANCE AND CONTRACTOR NOTICE TICKET.
- PRIOR TO THE START OF CONSTRUCTION, ALL REQUIRED JURISDICTIONAL PERMITS SHALL BE OBTAINED. THIS INCLUDES, BUT IS NOT LIMITED TO, BUILDING, ELECTRICAL, MECHANICAL, FIRE, FLOOD ZONE, ENVIRONMENTAL, AND ZONING. AFTER ONSITE ACTIVITIES AND CONSTRUCTION ARE COMPLETED, ALL REQUIRED PERMITS SHALL BE SATISFIED AND CLOSED OUT ACCORDING TO LOCAL JURISDICTIONAL REQUIREMENTS.
- ALL CONSTRUCTION MEANS AND METHODS; INCLUDING BUT NOT LIMITED TO, ERECTION PLANS, RIGGING PLANS, CLIMBING PLANS, AND RESCUE PLANS SHALL BE THE RESPONSIBILITY OF THE GENERAL CONTRACTOR RESPONSIBLE FOR THE EXECUTION OF THE WORK CONTAINED HEREIN, AND SHALL MEET ANSI/ASSE A10.48 (LATEST EDITION); FEDERAL, STATE, AND LOCAL REGULATIONS; AND ANY APPLICABLE INDUSTRY CONSENSUS STANDARDS RELATED TO THE CONSTRUCTION ACTIVITIES BEING PERFORMED. ALL RIGGING PLANS SHALL ADHERE TO ANSI/ASSE A10.48 (LATEST EDITION) AND DISH Wireless L.L.C. AND TOWER OWNER STANDARDS, INCLUDING THE REQUIRED INVOLVEMENT OF A QUALIFIED ENGINEER FOR CLASS IV CONSTRUCTION, TO CERTIFY THE SUPPORTING STRUCTURE(S) IN ACCORDANCE WITH ANSI/TIA-322 (LATEST EDITION).
- ALL SITE WORK TO COMPLY WITH DISH Wireless L.L.C. AND TOWER OWNER INSTALLATION STANDARDS FOR CONSTRUCTION ACTIVITIES ON DISH Wireless L.L.C. AND TOWER OWNER TOWER SITE AND LATEST VERSION OF ANSI/TIA-1019-A-2012 "STANDARD FOR INSTALLATION, ALTERATION, AND MAINTENANCE OF ANTENNA SUPPORTING STRUCTURES AND ANTENNAS."
- IF THE SPECIFIED EQUIPMENT CAN NOT BE INSTALLED AS SHOWN ON THESE DRAWINGS, THE CONTRACTOR SHALL PROPOSE AN ALTERNATIVE INSTALLATION FOR APPROVAL BY DISH Wireless L.L.C. AND TOWER OWNER PRIOR TO PROCEEDING WITH ANY SUCH CHANGE OF INSTALLATION.
- ALL MATERIALS FURNISHED AND INSTALLED SHALL BE IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS AND ORDINANCES. CONTRACTOR SHALL ISSUE ALL APPROPRIATE NOTICES AND COMPLY WITH ALL LAWS, ORDINANCES, RULES, REGULATIONS AND LAWFUL ORDERS OF ANY PUBLIC AUTHORITY REGARDING THE PERFORMANCE OF THE WORK. ALL WORK CARRIED OUT SHALL COMPLY WITH ALL APPLICABLE MUNICIPAL AND UTILITY COMPANY SPECIFICATIONS AND LOCAL JURISDICTIONAL CODES, ORDINANCES AND APPLICABLE REGULATIONS.
- THE CONTRACTOR SHALL INSTALL ALL EQUIPMENT AND MATERIALS IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS UNLESS SPECIFICALLY STATED OTHERWISE.
- THE CONTRACTOR SHALL CONTACT UTILITY LOCATING SERVICES INCLUDING PRIVATE LOCATES SERVICES PRIOR TO THE START OF CONSTRUCTION.
- ALL EXISTING ACTIVE SEWER, WATER, GAS, ELECTRIC AND OTHER UTILITIES WHERE ENCOUNTERED IN THE WORK, SHALL BE PROTECTED AT ALL TIMES AND WHERE REQUIRED FOR THE PROPER EXECUTION OF THE WORK, SHALL BE RELOCATED AS DIRECTED BY CONTRACTOR. EXTREME CAUTION SHOULD BE USED BY THE CONTRACTOR WHEN EXCAVATING OR DRILLING PIERS AROUND OR NEAR UTILITIES. CONTRACTOR SHALL PROVIDE SAFETY TRAINING FOR THE WORKING CREW. THIS WILL INCLUDE BUT NOT BE LIMITED TO A) FALL PROTECTION B) CONFINED SPACE C) ELECTRICAL SAFETY D) TRENCHING AND EXCAVATION E) CONSTRUCTION SAFETY PROCEDURES.
- ALL SITE WORK SHALL BE AS INDICATED ON THE STAMPED CONSTRUCTION DRAWINGS AND DISH PROJECT SPECIFICATIONS, LATEST APPROVED REVISION.
- CONTRACTOR SHALL KEEP THE SITE FREE FROM ACCUMULATING WASTE MATERIAL, DEBRIS, AND TRASH AT THE COMPLETION OF THE WORK. IF NECESSARY, RUBBISH, STUMPS, DEBRIS, STICKS, STONES AND OTHER REFUSE SHALL BE REMOVED FROM THE SITE AND DISPOSED OF LEGALLY.
- ALL EXISTING INACTIVE SEWER, WATER, GAS, ELECTRIC AND OTHER UTILITIES, WHICH INTERFERE WITH THE EXECUTION OF THE WORK, SHALL BE REMOVED AND/OR CAPPED, PLUGGED OR OTHERWISE DISCONTINUED AT POINTS WHICH WILL NOT INTERFERE WITH THE EXECUTION OF THE WORK, SUBJECT TO THE APPROVAL OF DISH Wireless L.L.C. AND TOWER OWNER, AND/OR LOCAL UTILITIES.
- THE CONTRACTOR SHALL PROVIDE SITE SIGNAGE IN ACCORDANCE WITH THE TECHNICAL SPECIFICATION FOR SITE SIGNAGE REQUIRED BY LOCAL JURISDICTION AND SIGNAGE REQUIRED ON INDIVIDUAL PIECES OF EQUIPMENT, ROOMS, AND SHELTERS.
- THE SITE SHALL BE GRADED TO CAUSE SURFACE WATER TO FLOW AWAY FROM THE CARRIER'S EQUIPMENT AND TOWER AREAS.
- THE SUB GRADE SHALL BE COMPACTED AND BROUGHT TO A SMOOTH UNIFORM GRADE PRIOR TO FINISHED SURFACE APPLICATION.
- THE AREAS OF THE OWNERS PROPERTY DISTURBED BY THE WORK AND NOT COVERED BY THE TOWER, EQUIPMENT OR DRIVEWAY, SHALL BE GRADED TO A UNIFORM SLOPE, AND STABILIZED TO PREVENT EROSION AS SPECIFIED ON THE CONSTRUCTION DRAWINGS AND/OR PROJECT SPECIFICATIONS.
- CONTRACTOR SHALL MINIMIZE DISTURBANCE TO EXISTING SITE DURING CONSTRUCTION. EROSION CONTROL MEASURES, IF REQUIRED DURING CONSTRUCTION, SHALL BE IN CONFORMANCE WITH THE LOCAL GUIDELINES FOR EROSION AND SEDIMENT CONTROL.
- THE CONTRACTOR SHALL PROTECT EXISTING IMPROVEMENTS, PAVEMENTS, CURBS, LANDSCAPING AND STRUCTURES. ANY DAMAGED PART SHALL BE REPAIRED AT CONTRACTOR'S EXPENSE TO THE SATISFACTION OF OWNER.
- CONTRACTOR SHALL LEGALLY AND PROPERLY DISPOSE OF ALL SCRAP MATERIALS SUCH AS COAXIAL CABLES AND OTHER ITEMS REMOVED FROM THE EXISTING FACILITY. ANTENNAS AND RADIOS REMOVED SHALL BE RETURNED TO THE OWNER'S DESIGNATED LOCATION.
- CONTRACTOR SHALL LEAVE PREMISES IN CLEAN CONDITION. TRASH AND DEBRIS SHOULD BE REMOVED FROM SITE ON A DAILY BASIS.
- NO FILL OR EMBANKMENT MATERIAL SHALL BE PLACED ON FROZEN GROUND. FROZEN MATERIALS, SNOW OR ICE SHALL NOT BE PLACED IN ANY FILL OR EMBANKMENT.

GENERAL NOTES:

- FOR THE PURPOSE OF CONSTRUCTION DRAWING, THE FOLLOWING DEFINITIONS SHALL APPLY:
CONTRACTOR:GENERAL CONTRACTOR RESPONSIBLE FOR CONSTRUCTION
CARRIER:DISH Wireless L.L.C.
TOWER OWNER:TOWER OWNER
- THESE DRAWINGS HAVE BEEN PREPARED USING STANDARDS OF PROFESSIONAL CARE AND COMPLETENESS NORMALLY EXERCISED UNDER SIMILAR CIRCUMSTANCES BY REPUTABLE ENGINEERS IN THIS OR SIMILAR LOCALITIES. IT IS ASSUMED THAT THE WORK DEPICTED WILL BE PERFORMED BY AN EXPERIENCED CONTRACTOR AND/OR WORKPEOPLE WHO HAVE A WORKING KNOWLEDGE OF THE APPLICABLE CODE STANDARDS AND REQUIREMENTS AND OF INDUSTRY ACCEPTED STANDARD GOOD PRACTICE. AS NOT EVERY CONDITION OR ELEMENT IS (OR CAN BE) EXPLICITLY SHOWN ON THESE DRAWINGS, THE CONTRACTOR SHALL USE INDUSTRY ACCEPTED STANDARD GOOD PRACTICE FOR MISCELLANEOUS WORK NOT EXPLICITLY SHOWN.
- THESE DRAWINGS REPRESENT THE FINISHED STRUCTURE. THEY DO NOT INDICATE THE MEANS OR METHODS OF CONSTRUCTION. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR THE CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES. THE CONTRACTOR SHALL PROVIDE ALL MEASURES NECESSARY FOR PROTECTION OF LIFE AND PROPERTY DURING CONSTRUCTION. SUCH MEASURES SHALL INCLUDE, BUT NOT BE LIMITED TO, BRACING, FORMWORK, SHORING, ETC. SITE VISITS BY THE ENGINEER OR HIS REPRESENTATIVE WILL NOT INCLUDE INSPECTION OF THESE ITEMS AND IS FOR STRUCTURAL OBSERVATION OF THE FINISHED STRUCTURE ONLY.
- NOTES AND DETAILS IN THE CONSTRUCTION DRAWINGS SHALL TAKE PRECEDENCE OVER GENERAL NOTES AND TYPICAL DETAILS. WHERE NO DETAILS ARE SHOWN, CONSTRUCTION SHALL CONFORM TO SIMILAR WORK ON THE PROJECT, AND/OR AS PROVIDED FOR IN THE CONTRACT DOCUMENTS. WHERE DISCREPANCIES OCCUR BETWEEN PLANS, DETAILS, GENERAL NOTES, AND SPECIFICATIONS, THE GREATER, MORE STRICT REQUIREMENTS, SHALL GOVERN. IF FURTHER CLARIFICATION IS REQUIRED CONTACT THE ENGINEER OF RECORD.
- SUBSTANTIAL EFFORT HAS BEEN MADE TO PROVIDE ACCURATE DIMENSIONS AND MEASUREMENTS ON THE DRAWINGS TO ASSIST IN THE FABRICATION AND/OR PLACEMENT OF CONSTRUCTION ELEMENTS BUT IT IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR TO FIELD VERIFY THE DIMENSIONS, MEASUREMENTS, AND/OR CLEARANCES SHOWN IN THE CONSTRUCTION DRAWINGS PRIOR TO FABRICATION OR CUTTING OF ANY NEW OR EXISTING CONSTRUCTION ELEMENTS. IF IT IS DETERMINED THAT THERE ARE DISCREPANCIES AND/OR CONFLICTS WITH THE CONSTRUCTION DRAWINGS THE ENGINEER OF RECORD IS TO BE NOTIFIED AS SOON AS POSSIBLE.
- PRIOR TO THE SUBMISSION OF BIDS, THE BIDDING CONTRACTOR SHALL VISIT THE CELL SITE TO FAMILIARIZE WITH THE EXISTING CONDITIONS AND TO CONFIRM THAT THE WORK CAN BE ACCOMPLISHED AS SHOWN ON THE CONSTRUCTION DRAWINGS. ANY DISCREPANCY FOUND SHALL BE BROUGHT TO THE ATTENTION OF CARRIER POC AND TOWER OWNER.
- ALL MATERIALS FURNISHED AND INSTALLED SHALL BE IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS AND ORDINANCES. CONTRACTOR SHALL ISSUE ALL APPROPRIATE NOTICES AND COMPLY WITH ALL LAWS, ORDINANCES, RULES, REGULATIONS AND LAWFUL ORDERS OF ANY PUBLIC AUTHORITY REGARDING THE PERFORMANCE OF THE WORK. ALL WORK CARRIED OUT SHALL COMPLY WITH ALL APPLICABLE MUNICIPAL AND UTILITY COMPANY SPECIFICATIONS AND LOCAL JURISDICTIONAL CODES, ORDINANCES AND APPLICABLE REGULATIONS.
- UNLESS NOTED OTHERWISE, THE WORK SHALL INCLUDE FURNISHING MATERIALS, EQUIPMENT, APPURTENANCES AND LABOR NECESSARY TO COMPLETE ALL INSTALLATIONS AS INDICATED ON THE DRAWINGS.
- THE CONTRACTOR SHALL INSTALL ALL EQUIPMENT AND MATERIALS IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS UNLESS SPECIFICALLY STATED OTHERWISE.
- IF THE SPECIFIED EQUIPMENT CAN NOT BE INSTALLED AS SHOWN ON THESE DRAWINGS, THE CONTRACTOR SHALL PROPOSE AN ALTERNATIVE INSTALLATION FOR APPROVAL BY THE CARRIER AND TOWER OWNER PRIOR TO PROCEEDING WITH ANY SUCH CHANGE OF INSTALLATION.
- CONTRACTOR IS TO PERFORM A SITE INVESTIGATION, BEFORE SUBMITTING BIDS, TO DETERMINE THE BEST ROUTING OF ALL CONDUITS FOR POWER, AND TELCO AND FOR GROUNDING CABLES AS SHOWN IN THE POWER, TELCO, AND GROUNDING PLAN DRAWINGS.
- THE CONTRACTOR SHALL PROTECT EXISTING IMPROVEMENTS, PAVEMENTS, CURBS, LANDSCAPING AND STRUCTURES. ANY DAMAGED PART SHALL BE REPAIRED AT CONTRACTOR'S EXPENSE TO THE SATISFACTION OF DISH Wireless L.L.C. AND TOWER OWNER
- CONTRACTOR SHALL LEGALLY AND PROPERLY DISPOSE OF ALL SCRAP MATERIALS SUCH AS COAXIAL CABLES AND OTHER ITEMS REMOVED FROM THE EXISTING FACILITY. ANTENNAS REMOVED SHALL BE RETURNED TO THE OWNER'S DESIGNATED LOCATION.
- CONTRACTOR SHALL LEAVE PREMISES IN CLEAN CONDITION. TRASH AND DEBRIS SHOULD BE REMOVED FROM SITE ON A DAILY BASIS.



5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



2000 CORPORATE DRIVE
CANONSBURG, PA 15317



1717 S. BOULDER
SUITE 300
TULSA, OK 74119
PH: (918) 587-4630
www.btgrp.com



B&T ENGINEERING, INC.
PEC.0001564
Expires 2/10/22

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
JJR	RMC	MDW

RFDS REV #: ---

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	5/28/21	ISSUED FOR REVIEW
0	7/1/21	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
151123.001.01

DISH Wireless L.L.C.
PROJECT INFORMATION

BOBDL00036A
44 FFYLER PLACE
SUFFIELD, CT 06078

SHEET TITLE
GENERAL NOTES

SHEET NUMBER
GN-2

CONCRETE, FOUNDATIONS, AND REINFORCING STEEL:

1. ALL CONCRETE WORK SHALL BE IN ACCORDANCE WITH THE ACI 301, ACI 318, ACI 336, ASTM A184, ASTM A185 AND THE DESIGN AND CONSTRUCTION SPECIFICATION FOR CAST-IN-PLACE CONCRETE.
2. UNLESS NOTED OTHERWISE, SOIL BEARING PRESSURE USED FOR DESIGN OF SLABS AND FOUNDATIONS IS ASSUMED TO BE 1000 psf.
3. ALL CONCRETE SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH (f'c) OF 3000 psi AT 28 DAYS, UNLESS NOTED OTHERWISE. NO MORE THAN 90 MINUTES SHALL ELAPSE FROM BATCH TIME TO TIME OF PLACEMENT UNLESS APPROVED BY THE ENGINEER OF RECORD. TEMPERATURE OF CONCRETE SHALL NOT EXCEED 90°f AT TIME OF PLACEMENT.
4. CONCRETE EXPOSED TO FREEZE-THAW CYCLES SHALL CONTAIN AIR ENTRAINING ADMIXTURES. AMOUNT OF AIR ENTRAINMENT TO BE BASED ON SIZE OF AGGREGATE AND F3 CLASS EXPOSURE (VERY SEVERE). CEMENT USED TO BE TYPE II PORTLAND CEMENT WITH A MAXIMUM WATER-TO-CEMENT RATIO (W/C) OF 0.45.
5. ALL STEEL REINFORCING SHALL CONFORM TO ASTM A615. ALL WELDED WIRE FABRIC (WWF) SHALL CONFORM TO ASTM A185. ALL SPLICES SHALL BE CLASS "B" TENSION SPLICES, UNLESS NOTED OTHERWISE. ALL HOOKS SHALL BE STANDARD 90 DEGREE HOOKS, UNLESS NOTED OTHERWISE. YIELD STRENGTH (Fy) OF STANDARD DEFORMED BARS ARE AS FOLLOWS:
 - #4 BARS AND SMALLER 40 ksi
 - #5 BARS AND LARGER 60 ksi
6. THE FOLLOWING MINIMUM CONCRETE COVER SHALL BE PROVIDED FOR REINFORCING STEEL UNLESS SHOWN OTHERWISE ON DRAWINGS:
 - CONCRETE CAST AGAINST AND PERMANENTLY EXPOSED TO EARTH 3"
 - CONCRETE EXPOSED TO EARTH OR WEATHER:
 - #6 BARS AND LARGER 2"
 - #5 BARS AND SMALLER 1-1/2"
 - CONCRETE NOT EXPOSED TO EARTH OR WEATHER:
 - SLAB AND WALLS 3/4"
 - BEAMS AND COLUMNS 1-1/2"
7. A TOOLED EDGE OR A 3/4" CHAMFER SHALL BE PROVIDED AT ALL EXPOSED EDGES OF CONCRETE, UNLESS NOTED OTHERWISE, IN ACCORDANCE WITH ACI 301 SECTION 4.2.4.

ELECTRICAL INSTALLATION NOTES:

1. ALL ELECTRICAL WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS, NEC AND ALL APPLICABLE FEDERAL, STATE, AND LOCAL CODES/ORDINANCES.
2. CONDUIT ROUTINGS ARE SCHEMATIC. CONTRACTOR SHALL INSTALL CONDUITS SO THAT ACCESS TO EQUIPMENT IS NOT BLOCKED AND TRIP HAZARDS ARE ELIMINATED.
3. WIRING, RACEWAY AND SUPPORT METHODS AND MATERIALS SHALL COMPLY WITH THE REQUIREMENTS OF THE NEC.
4. ALL CIRCUITS SHALL BE SEGREGATED AND MAINTAIN MINIMUM CABLE SEPARATION AS REQUIRED BY THE NEC.
- 4.1. ALL EQUIPMENT SHALL BEAR THE UNDERWRITERS LABORATORIES LABEL OF APPROVAL, AND SHALL CONFORM TO REQUIREMENT OF THE NATIONAL ELECTRICAL CODE.
- 4.2. ALL OVERCURRENT DEVICES SHALL HAVE AN INTERRUPTING CURRENT RATING THAT SHALL BE GREATER THAN THE SHORT CIRCUIT CURRENT TO WHICH THEY ARE SUBJECTED, 22,000 AIC MINIMUM. VERIFY AVAILABLE SHORT CIRCUIT CURRENT DOES NOT EXCEED THE RATING OF ELECTRICAL EQUIPMENT IN ACCORDANCE WITH ARTICLE 110.24 NEC OR THE MOST CURRENT ADOPTED CODE PRE THE GOVERNING JURISDICTION.
5. EACH END OF EVERY POWER PHASE CONDUCTOR, GROUNDING CONDUCTOR, AND TELCO CONDUCTOR OR CABLE SHALL BE LABELED WITH COLOR-CODED INSULATION OR ELECTRICAL TAPE (3M BRAND, 1/2" PLASTIC ELECTRICAL TAPE WITH UV PROTECTION, OR EQUAL). THE IDENTIFICATION METHOD SHALL CONFORM WITH NEC AND OSHA.
6. ALL ELECTRICAL COMPONENTS SHALL BE CLEARLY LABELED WITH LAMICOID TAGS SHOWING THEIR RATED VOLTAGE, PHASE CONFIGURATION, WIRE CONFIGURATION, POWER OR AMPACITY RATING AND BRANCH CIRCUIT ID NUMBERS (i.e. PANEL BOARD AND CIRCUIT ID'S).
7. PANEL BOARDS (ID NUMBERS) SHALL BE CLEARLY LABELED WITH PLASTIC LABELS.
8. TIE WRAPS ARE NOT ALLOWED.
9. ALL POWER AND EQUIPMENT GROUND WIRING IN TUBING OR CONDUIT SHALL BE SINGLE COPPER CONDUCTOR (#14 OR LARGER) WITH TYPE THHW, THWN, THWN-2, XHHW, XHHW-2, THW, THW-2, RHW, OR RHW-2 INSULATION UNLESS OTHERWISE SPECIFIED.
10. SUPPLEMENTAL EQUIPMENT GROUND WIRING LOCATED INDOORS SHALL BE SINGLE COPPER CONDUCTOR (#6 OR LARGER) WITH TYPE THHW, THWN, THWN-2, XHHW, XHHW-2, THW, THW-2, RHW, OR RHW-2 INSULATION UNLESS OTHERWISE SPECIFIED.
11. POWER AND CONTROL WIRING IN FLEXIBLE CORD SHALL BE MULTI-CONDUCTOR, TYPE SOOW CORD (#14 OR LARGER) UNLESS OTHERWISE SPECIFIED.
12. POWER AND CONTROL WIRING FOR USE IN CABLE TRAY SHALL BE MULTI-CONDUCTOR, TYPE TC CABLE (#14 OR LARGER), WITH TYPE THHW, THWN, THWN-2, XHHW, XHHW-2, THW, THW-2, RHW, OR RHW-2 INSULATION UNLESS OTHERWISE SPECIFIED.
13. ALL POWER AND GROUNDING CONNECTIONS SHALL BE CRIMP-STYLE, COMPRESSION WIRE LUGS AND WIRE NUTS BY THOMAS AND BETTS (OR EQUAL). LUGS AND WIRE NUTS SHALL BE RATED FOR OPERATION NOT LESS THAN 75° C (90° C IF AVAILABLE).
14. RACEWAY AND CABLE TRAY SHALL BE LISTED OR LABELED FOR ELECTRICAL USE IN ACCORDANCE WITH NEMA, UL, ANSI/IEEE AND NEC.
15. ELECTRICAL METALLIC TUBING (EMT), INTERMEDIATE METAL CONDUIT (IMC), OR RIGID METAL CONDUIT (RMC) SHALL BE USED FOR EXPOSED INDOOR LOCATIONS.

16. ELECTRICAL METALLIC TUBING (EMT) OR METAL-CLAD CABLE (MC) SHALL BE USED FOR CONCEALED INDOOR LOCATIONS.
17. SCHEDULE 40 PVC UNDERGROUND ON STRAIGHTS AND SCHEDULE 80 PVC FOR ALL ELBOWS/90s AND ALL APPROVED ABOVE GRADE PVC CONDUIT.
18. LIQUID-TIGHT FLEXIBLE METALLIC CONDUIT (LIQUID-TITE FLEX) SHALL BE USED INDOORS AND OUTDOORS, WHERE VIBRATION OCCURS OR FLEXIBILITY IS NEEDED.
19. CONDUIT AND TUBING FITTINGS SHALL BE THREADED OR COMPRESSION-TYPE AND APPROVED FOR THE LOCATION USED. SET SCREW FITTINGS ARE NOT ACCEPTABLE.
20. CABINETS, BOXES AND WIRE WAYS SHALL BE LABELED FOR ELECTRICAL USE IN ACCORDANCE WITH NEMA, UL, ANSI/IEEE AND THE NEC.
21. WIREWAYS SHALL BE METAL WITH AN ENAMEL FINISH AND INCLUDE A HINGED COVER, DESIGNED TO SWING OPEN DOWNWARDS (WIREMOLD SPECIMATE WIREWAY).
22. SLOTTED WIRING DUCT SHALL BE PVC AND INCLUDE COVER (PANDUIT TYPE E OR EQUAL).
23. CONDUITS SHALL BE FASTENED SECURELY IN PLACE WITH APPROVED NON-PERFORATED STRAPS AND HANGERS. EXPLOSIVE DEVICES (i.e. POWDER-ACTUATED) FOR ATTACHING HANGERS TO STRUCTURE WILL NOT BE PERMITTED. CLOSELY FOLLOW THE LINES OF THE STRUCTURE, MAINTAIN CLOSE PROXIMITY TO THE STRUCTURE AND KEEP CONDUITS IN TIGHT ENVELOPES. CHANGES IN DIRECTION TO ROUTE AROUND OBSTACLES SHALL BE MADE WITH CONDUIT OUTLET BODIES. CONDUIT SHALL BE INSTALLED IN A NEAT AND WORKMANLIKE MANNER. PARALLEL AND PERPENDICULAR TO STRUCTURE WALL AND CEILING LINES. ALL CONDUIT SHALL BE FISHED TO CLEAR OBSTRUCTIONS. ENDS OF CONDUITS SHALL BE TEMPORARILY CAPPED FLUSH TO FINISH GRADE TO PREVENT CONCRETE, PLASTER OR DIRT FROM ENTERING. CONDUITS SHALL BE RIGIDLY CLAMPED TO BOXES BY GALVANIZED MALLEABLE IRON BUSHING ON INSIDE AND GALVANIZED MALLEABLE IRON LOCKNUT ON OUTSIDE AND INSIDE.
24. EQUIPMENT CABINETS, TERMINAL BOXES, JUNCTION BOXES AND PULL BOXES SHALL BE GALVANIZED OR EPOXY-COATED SHEET STEEL SHALL MEET OR EXCEED UL 50 AND BE RATED NEMA 1 (OR BETTER) FOR INTERIOR LOCATIONS AND NEMA 3 (OR BETTER) FOR EXTERIOR LOCATIONS.
25. METAL RECEPTACLE, SWITCH AND DEVICE BOXES SHALL BE GALVANIZED, EPOXY-COATED OR NON-CORRODING; SHALL MEET OR EXCEED UL 514A AND NEMA OS 1 AND BE RATED NEMA 1 (OR BETTER) FOR INTERIOR LOCATIONS AND WEATHER PROTECTED (WP OR BETTER) FOR EXTERIOR LOCATIONS.
26. NONMETALLIC RECEPTACLE, SWITCH AND DEVICE BOXES SHALL MEET OR EXCEED NEMA OS 2 (NEWEST REVISION) AND BE RATED NEMA 1 (OR BETTER) FOR INTERIOR LOCATIONS AND WEATHER PROTECTED (WP OR BETTER) FOR EXTERIOR LOCATIONS.
27. THE CONTRACTOR SHALL NOTIFY AND OBTAIN NECESSARY AUTHORIZATION FROM THE CARRIER AND/OR DISH Wireless L.L.C. AND TOWER OWNER BEFORE COMMENCING WORK ON THE AC POWER DISTRIBUTION PANELS.
28. THE CONTRACTOR SHALL PROVIDE NECESSARY TAGGING ON THE BREAKERS, CABLES AND DISTRIBUTION PANELS IN ACCORDANCE WITH THE APPLICABLE CODES AND STANDARDS TO SAFEGUARD LIFE AND PROPERTY.
29. INSTALL LAMICOID LABEL ON THE METER CENTER TO SHOW "DISH Wireless L.L.C.".
30. ALL EMPTY/SPARE CONDUITS THAT ARE INSTALLED ARE TO HAVE A METERED MULE TAPE PULL CORD INSTALLED.



5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



2000 CORPORATE DRIVE
CANONSBURG, PA 15317



1717 S. BOULDER
SUITE 300
TULSA, OK 74119
PH: (918) 587-4630
www.btgrp.com



B&T ENGINEERING, INC.
PEC.0001564
Expires 2/10/22

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY: CHECKED BY: APPROVED BY:

JJR RMC MDW

RFDS REV #: ---

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	5/28/21	ISSUED FOR REVIEW
0	7/1/21	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
151123.001.01

DISH Wireless L.L.C.
PROJECT INFORMATION

BOBDL00036A
44 FFYLER PLACE
SUFFIELD, CT 06078

SHEET TITLE
GENERAL NOTES

SHEET NUMBER
GN-3

GROUNDING NOTES:

1. ALL GROUND ELECTRODE SYSTEMS (INCLUDING TELECOMMUNICATION, RADIO, LIGHTNING PROTECTION AND AC POWER GES'S) SHALL BE BONDED TOGETHER AT OR BELOW GRADE, BY TWO OR MORE COPPER BONDING CONDUCTORS IN ACCORDANCE WITH THE NEC.
2. THE CONTRACTOR SHALL PERFORM IEEE FALL-OF-POTENTIAL RESISTANCE TO EARTH TESTING (PER IEEE 1100 AND 81) FOR GROUND ELECTRODE SYSTEMS, THE CONTRACTOR SHALL FURNISH AND INSTALL SUPPLEMENTAL GROUND ELECTRODES AS NEEDED TO ACHIEVE A TEST RESULT OF 5 OHMS OR LESS.
3. THE CONTRACTOR IS RESPONSIBLE FOR PROPERLY SEQUENCING GROUNDING AND UNDERGROUND CONDUIT INSTALLATION AS TO PREVENT ANY LOSS OF CONTINUITY IN THE GROUNDING SYSTEM OR DAMAGE TO THE CONDUIT AND PROVIDE TESTING RESULTS.
4. METAL CONDUIT AND TRAY SHALL BE GROUNDED AND MADE ELECTRICALLY CONTINUOUS WITH LISTED BONDING FITTINGS OR BY BONDING ACROSS THE DISCONTINUITY WITH #6 COPPER WIRE UL APPROVED GROUNDING TYPE CONDUIT CLAMPS.
5. METAL RACEWAY SHALL NOT BE USED AS THE NEC REQUIRED EQUIPMENT GROUND CONDUCTOR. STRANDED COPPER CONDUCTORS WITH GREEN INSULATION, SIZED IN ACCORDANCE WITH THE NEC, SHALL BE FURNISHED AND INSTALLED WITH THE POWER CIRCUITS TO BTS EQUIPMENT.
6. EACH CABINET FRAME SHALL BE DIRECTLY CONNECTED TO THE MASTER GROUND BAR WITH GREEN INSULATED SUPPLEMENTAL EQUIPMENT GROUND WIRES, #6 STRANDED COPPER OR LARGER FOR INDOOR BTS; #2 BARE SOLID TINNED COPPER FOR OUTDOOR BTS.
7. CONNECTIONS TO THE GROUND BUS SHALL NOT BE DOUBLED UP OR STACKED BACK TO BACK CONNECTIONS ON OPPOSITE SIDE OF THE GROUND BUS ARE PERMITTED.
8. ALL EXTERIOR GROUND CONDUCTORS BETWEEN EQUIPMENT/GROUND BARS AND THE GROUND RING SHALL BE #2 SOLID TINNED COPPER UNLESS OTHERWISE INDICATED.
9. ALUMINUM CONDUCTOR OR COPPER CLAD STEEL CONDUCTOR SHALL NOT BE USED FOR GROUNDING CONNECTIONS.
10. USE OF 90° BENDS IN THE PROTECTION GROUNDING CONDUCTORS SHALL BE AVOIDED WHEN 45° BENDS CAN BE ADEQUATELY SUPPORTED.
11. EXOTHERMIC WELDS SHALL BE USED FOR ALL GROUNDING CONNECTIONS BELOW GRADE.
12. ALL GROUND CONNECTIONS ABOVE GRADE (INTERIOR AND EXTERIOR) SHALL BE FORMED USING HIGH PRESS CRIMPS.
13. COMPRESSION GROUND CONNECTIONS MAY BE REPLACED BY EXOTHERMIC WELD CONNECTIONS.
14. ICE BRIDGE BONDING CONDUCTORS SHALL BE EXOTHERMICALLY BONDED OR BOLTED TO THE BRIDGE AND THE TOWER GROUND BAR.
15. APPROVED ANTIOXIDANT COATINGS (i.e. CONDUCTIVE GEL OR PASTE) SHALL BE USED ON ALL COMPRESSION AND BOLTED GROUND CONNECTIONS.
16. ALL EXTERIOR GROUND CONNECTIONS SHALL BE COATED WITH A CORROSION RESISTANT MATERIAL.
17. MISCELLANEOUS ELECTRICAL AND NON-ELECTRICAL METAL BOXES, FRAMES AND SUPPORTS SHALL BE BONDED TO THE GROUND RING, IN ACCORDANCE WITH THE NEC.
18. BOND ALL METALLIC OBJECTS WITHIN 6 ft OF MAIN GROUND RING WITH (1) #2 BARE SOLID TINNED COPPER GROUND CONDUCTOR.
19. GROUND CONDUCTORS USED FOR THE FACILITY GROUNDING AND LIGHTNING PROTECTION SYSTEMS SHALL NOT BE ROUTED THROUGH METALLIC OBJECTS THAT FORM A RING AROUND THE CONDUCTOR, SUCH AS METALLIC CONDUITS, METAL SUPPORT CLIPS OR SLEEVES THROUGH WALLS OR FLOORS. WHEN IT IS REQUIRED TO BE HOUSED IN CONDUIT TO MEET CODE REQUIREMENTS OR LOCAL CONDITIONS, NON-METALLIC MATERIAL SUCH AS PVC CONDUIT SHALL BE USED. WHERE USE OF METAL CONDUIT IS UNAVOIDABLE (i.e., NONMETALLIC CONDUIT PROHIBITED BY LOCAL CODE) THE GROUND CONDUCTOR SHALL BE BONDED TO EACH END OF THE METAL CONDUIT.
20. ALL GROUNDS THAT TRANSITION FROM BELOW GRADE TO ABOVE GRADE MUST BE #2 BARE SOLID TINNED COPPER IN 3/4" NON-METALLIC, FLEXIBLE CONDUIT FROM 24" BELOW GRADE TO WITHIN 3" TO 6" OF CAD-WELD TERMINATION POINT. THE EXPOSED END OF THE CONDUIT MUST BE SEALED WITH SILICONE CAULK. (ADD TRANSITIONING GROUND STANDARD DETAIL AS WELL).
21. BUILDINGS WHERE THE MAIN GROUNDING CONDUCTORS ARE REQUIRED TO BE ROUTED TO GRADE, THE CONTRACTOR SHALL ROUTE TWO GROUNDING CONDUCTORS FROM THE ROOFTOP, TOWERS, AND WATER TOWERS GROUNDING RING, TO THE EXISTING GROUNDING SYSTEM, THE GROUNDING CONDUCTORS SHALL NOT BE SMALLER THAN 2/0 COPPER. ROOFTOP GROUNDING RING SHALL BE BONDED TO THE EXISTING GROUNDING SYSTEM, THE BUILDING STEEL COLUMNS, LIGHTNING PROTECTION SYSTEM, AND BUILDING MAIN WATER LINE (FERROUS OR NONFERROUS METAL PIPING ONLY). DO NOT ATTACH GROUNDING TO FIRE SPRINKLER SYSTEM PIPES.



5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



2000 CORPORATE DRIVE
CANONSBURG, PA 15317



1717 S. BOULDER
SUITE 300
TULSA, OK 74119
PH: (918) 587-4630
www.btgrp.com



B&T ENGINEERING, INC.
PEC.0001564
Expires 2/10/22

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
JJR	RMC	MDW

RFDS REV #: ---

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	5/28/21	ISSUED FOR REVIEW
0	7/1/21	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
151123.001.01

DISH Wireless L.L.C.
PROJECT INFORMATION

BOBDL0036A
44 FFYLER PLACE
SUFFIELD, CT 06078

SHEET TITLE
GENERAL NOTES

SHEET NUMBER
GN-4

Exhibit D

Structural Analysis Report

Date: **May 22, 2021**



Crown Castle
2000 Corporate Dr.
Canonsburg, PA 15317
(724) 416-2000

Subject: **Structural Analysis Report**

Carrier Designation: **DISH Network Co-Locate**
Site Number: BOBDL00036A
Site Name: CT-CCI-T-801486

Crown Castle Designation: **BU Number:** 801486
Site Name: CT SUFFIELD 2 CAC 801486
JDE Job Number: 650034
Work Order Number: 1962728
Order Number: 556646 Rev. 0

Engineering Firm Designation: **Crown Castle Project Number:** 1962728

Site Data: **44 FFyler Place, Suffield, Hartford County, CT**
Latitude 41° 58' 49.7", Longitude -72° 39' 26.2"
109 Foot - Monopole Tower

Crown Castle is pleased to submit this “**Structural Analysis Report**” to determine the structural integrity of the above-mentioned tower.

The purpose of the analysis is to determine acceptability of the tower stress level. Based on our analysis we have determined the tower stress level for the structure and foundation, under the following load case, to be:

LC5: Proposed Equipment Configuration

Sufficient Capacity – 65%

This analysis utilizes an ultimate 3-second gust wind speed of 120 mph as required by the 2018 Connecticut State Building Code. Applicable Standard references and design criteria are listed in Section 2 - "Analysis Criteria".

Structural analysis prepared by: Derek L. Tordella

Respectfully submitted by:

Maham Barimani, P.E.
Senior Project Engineer




TABLE OF CONTENTS

1) INTRODUCTION

2) ANALYSIS CRITERIA

Table 1 - Proposed Equipment Configuration

Table 2 - Other Considered Equipment

3) ANALYSIS PROCEDURE

Table 3 - Documents Provided

3.1) Analysis Method

3.2) Assumptions

4) ANALYSIS RESULTS

Table 4 - Section Capacity (Summary)

Table 5 - Tower Component Stresses vs. Capacity - LC5

4.1) Recommendations

5) APPENDIX A

tnxTower Output

6) APPENDIX B

Base Level Drawing

7) APPENDIX C

Additional Calculations

1) INTRODUCTION

This tower is a 109 ft Monopole tower designed by FWT INC.

2) ANALYSIS CRITERIA

TIA-222 Revision:	TIA-222-H
Risk Category:	II
Wind Speed:	120 mph
Exposure Category:	C
Topographic Factor:	1
Ice Thickness:	2 in
Wind Speed with Ice:	50 mph
Service Wind Speed:	60 mph

Table 1 - Proposed Equipment Configuration

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)
101.0	101.0	3	fujitsu	TA08025-B604	1	1-1/2
		3	fujitsu	TA08025-B605		
		3	jma wireless	MX08FRO665-21 w/ Mount Pipe		
		1	raycap	RDIDC-9181-PF-48		
		1	tower mounts	Commscope MC-PK8-DSH		

Table 2 - Other Considered Equipment

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)
109.0	111.0	3	cci antennas	HPA-65R-BUU-H8 w/ Mount Pipe	2 6 12 2	3/8 3/4 1-5/8 Conduit
		3	cci antennas	HPA65R-BU8A w/ Mount Pipe		
		3	ericsson	RADIO 4415 B30		
		3	ericsson	RRUS 4449 B5/B12		
		3	ericsson	RRUS 8843 B2/B66A		
		3	kathrein	800 10121 w/ Mount Pipe		
		3	kathrein	80010966 w/ Mount Pipe		
		3	raycap	DC6-48-60-18-8F		
	6	powerwave technologies	TT19-08BP111-001			
	1	tower mounts	Platform Mount [LP 714-1]			
92.0	92.0	1	tower mounts	Platform Mount [LP 715-1]	12 2	1-1/4 1-1/2
	91.0	3	alcatel lucent	B13 RRH 4X30		
		3	alcatel lucent	PCS B25 RRH4X30		
		3	alcatel lucent	RRH2X60-AWS		
		2	antel	LPA-80080-4CF-EDIN-0 w/ Mount Pipe		
		2	commscope	RC2DC-3315-PF-48		
		6	commscope	SBNHH-1D65B w/ Mount Pipe		
		4	swedcom	SC 9012 REV2 w/ Mount Pipe		

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)
80.0	81.0	12	decibel	DB844H90-XY w/ Mount Pipe	12	7/8
	80.0	1	tower mounts	Platform Mount [LP 1201-1]		
74.0	75.0	3	alcatel lucent	PCS 1900MHZ 4X45W-65MHZ	-	-
	74.0	1	tower mounts	Side Arm Mount [SO 102-3]		
	72.0	3	alcatel lucent	800MHZ 2X50W RRH W/FILTER		
69.0	72.0	3	alcatel lucent	TD-RRH8X20-25	1 3	5/8 1-1/4
	71.0	2	rfs celwave	APXV9ERR18-C-A20 w/ Mount Pipe		
		1	rfs celwave	APXVSP18-C-A20 w/ Mount Pipe		
		3	rfs celwave	APXVTM14-C-120 w/ Mount Pipe		
69.0	1	tower mounts	Platform Mount [LP 1201-1]			
62.0	62.0	3	rfs celwave	APX18-206516L	6	1-5/8
		1	tower mounts	Pipe Mount [PM 602-3]		

3) ANALYSIS PROCEDURE

Table 3 - Documents Provided

Document	Reference	Source
4-GEOTECHNICAL REPORTS	2294830	CCISITES
4-TOWER FOUNDATION DRAWINGS/DESIGN/SPECS	821489	CCISITES
4-TOWER MANUFACTURER DRAWINGS	823124	CCISITES

3.1) Analysis Method

tnxTower (version 8.0.9.0), a commercially available analysis software package, was used to create a three-dimensional model of the tower and calculate member stresses for various loading cases. Selected output from the analysis is included in Appendix A. When applicable, Crown Castle has calculated and provided the effective area for panel antennas using approved methods following the intent of the TIA-222 standard.

3.2) Assumptions

- 1) Tower and structures were maintained in accordance with the TIA-222 Standard.
- 2) The configuration of antennas, transmission cables, mounts and other appurtenances are as specified in Tables 1 and 2 and the referenced drawings.

This analysis may be affected if any assumptions are not valid or have been made in error. Crown Castle should be notified to determine the effect on the structural integrity of the tower.

4) ANALYSIS RESULTS

Table 4 - Section Capacity (Summary)

Section No.	Elevation (ft)	Component Type	Size	Critical Element	P (K)	SF*P_allow (K)	% Capacity	Pass / Fail
L1	109 - 95	Pole	TP26.715x23.476x0.1875	1	-8.02	969.73	25.6	Pass
L2	95 - 48.08	Pole	TP37.573x26.715x0.3125	2	-26.36	2200.76	54.4	Pass
L3	48.08 - 0	Pole	TP48.075x35.8094x0.375	3	-41.69	3487.40	65.0	Pass

Section No.	Elevation (ft)	Component Type	Size	Critical Element	P (K)	SF*P_allow (K)	% Capacity	Pass / Fail
							Summary	
						Pole (L3)	65.0	Pass
						Rating =	65.0	Pass

Table 5 - Tower Component Stresses vs. Capacity - LC5

Notes	Component	Elevation (ft)	% Capacity	Pass / Fail
1	Flange Bolts	95	17.8	Pass
1	Flange Plates		6.5	Pass
1	Anchor Rods	0	53.2	Pass
1	Base Plate		29.6	Pass
1	Base Foundation (Structure)		61.1	Pass
1	Base Foundation (Soil Interaction)		43.8	Pass

Structure Rating (max from all components) =	65%
---	------------

Notes:


- 1) See additional documentation in "Appendix C – Additional Calculations" for calculations supporting the % capacity consumed.

4.1) Recommendations

The tower and its foundation have sufficient capacity to carry the proposed load configuration. No modifications are required at this time.

APPENDIX A
TNXTOWER OUTPUT

Section	1	2	3
Length (ft)	14.00	46.92	53.00
Number of Sides	18	18	18
Thickness (in)	0.1875	0.3125	0.3750
Socket Length (ft)		4.92	
Top Dia (in)	23.4760	26.7150	35.8094
Bot Dia (in)	26.7150	37.5730	48.0750
Grade		A572-65	
Weight (K)	0.7	5.0	8.9




MATERIAL STRENGTH

GRADE	Fy	Fu	GRADE	Fy	Fu
A572-65	65 ksi	80 ksi			

TOWER DESIGN NOTES

1. Tower is located in Hartford County, Connecticut.
2. Tower designed for Exposure C to the TIA-222-H Standard.
3. Tower designed for a 120 mph basic wind in accordance with the TIA-222-H Standard.
4. Tower is also designed for a 50 mph basic wind with 2.00 in ice. Ice is considered to increase in thickness with height.
5. Deflections are based upon a 60 mph wind.
6. Tower Risk Category II.
7. Topographic Category 1 with Crest Height of 0.00 ft
8. TOWER RATING: 65%



CROWN CASTLE
The Pathway to Possible

Crown Castle
2000 Corporate Dr.
Canonsburg, PA 15317
Phone: (724) 416-2000
FAX:

Job: BU# 801486		
Project:		
Client: Crown Castle	Drawn by: DTordella	App'd:
Code: TIA-222-H	Date: 05/22/21	Scale: NTS
Path:	Dwg No. E-1	

C:\Users\dtordella\Desktop\SA SDD Processing\801486\WO 1962728 - SA\Prod\801486_RPA.er

Tower Input Data

The tower is a monopole.

This tower is designed using the TIA-222-H standard.

The following design criteria apply:

- Tower is located in Hartford County, Connecticut.
- Tower base elevation above sea level: 132.00 ft.
- Basic wind speed of 120 mph.
- Risk Category II.
- Exposure Category C.
- Simplified Topographic Factor Procedure for wind speed-up calculations is used.
- Topographic Category: 1.
- Crest Height: 0.00 ft.
- Nominal ice thickness of 2.0000 in.
- Ice thickness is considered to increase with height.
- Ice density of 56 pcf.
- A wind speed of 50 mph is used in combination with ice.
- Temperature drop of 50 °F.
- Deflections calculated using a wind speed of 60 mph.
- A non-linear (P-delta) analysis was used.
- Pressures are calculated at each section.
- Stress ratio used in pole design is 1.
- Tower analysis based on target reliabilities in accordance with Annex S.
- Load Modification Factors used: $K_{es}(F_w) = 0.95$, $K_{es}(t_i) = 0.85$.
- Maximum demand-capacity ratio is: 1.05.
- Local bending stresses due to climbing loads, feed line supports, and appurtenance mounts are not considered.

Options

Consider Moments - Legs Consider Moments - Horizontals Consider Moments - Diagonals Use Moment Magnification ✓ Use Code Stress Ratios ✓ Use Code Safety Factors - Guys Escalate Ice Always Use Max Kz Use Special Wind Profile Include Bolts In Member Capacity Leg Bolts Are At Top Of Section Secondary Horizontal Braces Leg Use Diamond Inner Bracing (4 Sided) SR Members Have Cut Ends SR Members Are Concentric	Distribute Leg Loads As Uniform Assume Legs Pinned ✓ Assume Rigid Index Plate ✓ Use Clear Spans For Wind Area Use Clear Spans For KL/r Retension Guys To Initial Tension ✓ Bypass Mast Stability Checks ✓ Use Azimuth Dish Coefficients ✓ Project Wind Area of Appurt. Autocalc Torque Arm Areas Add IBC .6D+W Combination ✓ Sort Capacity Reports By Component Triangulate Diamond Inner Bracing Treat Feed Line Bundles As Cylinder Ignore KL/ry For 60 Deg. Angle Legs	Use ASCE 10 X-Brace Ly Rules Calculate Redundant Bracing Forces Ignore Redundant Members in FEA SR Leg Bolts Resist Compression All Leg Panels Have Same Allowable Offset Girt At Foundation ✓ Consider Feed Line Torque Include Angle Block Shear Check Use TIA-222-H Bracing Resist. Exemption Use TIA-222-H Tension Splice Exemption <div style="text-align: center; background-color: #e0e0e0; padding: 2px;">Poles</div> ✓ Include Shear-Torsion Interaction Always Use Sub-Critical Flow Use Top Mounted Sockets Pole Without Linear Attachments Pole With Shroud Or No Appurtenances Outside and Inside Corner Radii Are Known
--	---	--

Tapered Pole Section Geometry

Section	Elevation ft	Section Length ft	Splice Length ft	Number of Sides	Top Diameter in	Bottom Diameter in	Wall Thickness in	Bend Radius in	Pole Grade
L1	109.00-95.00	14.00	0.00	18	23.4760	26.7150	0.1875	0.7500	A572-65 (65 ksi)
L2	95.00-48.08	46.92	4.92	18	26.7150	37.5730	0.3125	1.2500	A572-65 (65 ksi)
L3	48.08-0.00	53.00		18	35.8094	48.0750	0.3750	1.5000	A572-65 (65 ksi)

Tapered Pole Properties

Section	Tip Dia. in	Area in ²	I in ⁴	r in	C in	I/C in ³	J in ⁴	It/Q in ²	w in	w/t
L1	23.8092	13.8596	949.6645	8.2674	11.9258	79.6310	1900.5786	6.9311	3.8018	20.276
	27.0982	15.7872	1403.5717	9.4173	13.5712	103.4227	2808.9903	7.8951	4.3718	23.316
L2	27.0789	26.1880	2306.3730	9.3729	13.5712	169.9459	4615.7808	13.0965	4.1518	13.286
	38.1044	36.9578	6482.4687	13.2275	19.0871	339.6259	12973.4672	18.4824	6.0628	19.401
L3	37.4602	42.1758	6690.4028	12.5792	18.1912	367.7825	13389.6089	21.0919	5.6425	15.047
	48.7588	56.7749	16320.3992	16.9335	24.4221	668.2635	32662.2732	28.3929	7.8012	20.803

Tower Elevation ft	Gusset Area (per face) ft ²	Gusset Thickness in	Gusset Grade	Adjust. Factor A _r	Adjust. Factor A _r	Weight Mult.	Double Angle Stitch Bolt Spacing Diagonals in	Double Angle Stitch Bolt Spacing Horizontal in	Double Angle Stitch Bolt Spacing Redundants in
L1 109.00-95.00				1	1	1			
L2 95.00-48.08				1	1	1			
L3 48.08-0.00				1	1	1			

Feed Line/Linear Appurtenances - Entered As Round Or Flat

Description	Sector	Exclude From Torque Calculation	Component Type	Placement ft	Total Number	Number Per Row	Start/End Position	Width or Diameter in	Perimeter in	Weight plf

CU12PSM9P6XXX(1-1/2)	C	No	Surface Ar (CaAa)	101.00 - 0.00	1	1	0.200 - 0.210	1.6000		2.35
LDf6-50A(1-1/4")	A	No	Surface Ar (CaAa)	92.00 - 0.00	6	6	0.350 - 0.500	1.5500		0.66

CR 50 1873(1-5/8)	C	No	Surface Ar (CaAa)	62.00 - 0.00	6	6	-0.100 - 0.100	1.9800		0.83

Feed Line/Linear Appurtenances - Entered As Area

Description	Face or Leg	Allow Shield	Exclude From Torque Calculation	Component Type	Placement ft	Total Number	C _A A _A ft ² /ft	Weight plf
-------------	-------------	--------------	---------------------------------	----------------	-----------------	--------------	--	---------------

Description	Face or Leg	Allow Shield	Exclude From Torque Calculation	Component Type	Placement ft	Total Number		C _{AA} ft ² /ft	Weight plf

LDF7-50A(1-5/8)	B	No	No	Inside Pole	109.00 - 0.00	12	No Ice	0.00	0.82
							1/2" Ice	0.00	0.82
							1" Ice	0.00	0.82
							2" Ice	0.00	0.82
FB-L98B-002-75000(3/8)	B	No	No	Inside Pole	109.00 - 0.00	2	No Ice	0.00	0.06
							1/2" Ice	0.00	0.06
							1" Ice	0.00	0.06
							2" Ice	0.00	0.06
WR-VG86ST-BRD(3/4)	B	No	No	Inside Pole	109.00 - 0.00	6	No Ice	0.00	0.58
							1/2" Ice	0.00	0.58
							1" Ice	0.00	0.58
							2" Ice	0.00	0.58
2" Rigid Conduit	B	No	No	Inside Pole	109.00 - 0.00	2	No Ice	0.00	2.80
							1/2" Ice	0.00	2.80
							1" Ice	0.00	2.80
							2" Ice	0.00	2.80

LDF6-50A(1-1/4")	A	No	No	Inside Pole	92.00 - 0.00	6	No Ice	0.00	0.66
							1/2" Ice	0.00	0.66
							1" Ice	0.00	0.66
							2" Ice	0.00	0.66
MLC HYBRID 6X12 LI(1-1/2)	A	No	No	Inside Pole	92.00 - 0.00	2	No Ice	0.00	1.85
							1/2" Ice	0.00	1.85
							1" Ice	0.00	1.85
							2" Ice	0.00	1.85

LDF5-50A(7/8)	A	No	No	Inside Pole	80.00 - 0.00	12	No Ice	0.00	0.33
							1/2" Ice	0.00	0.33
							1" Ice	0.00	0.33
							2" Ice	0.00	0.33

HB058-M12-XXXF(5/8)	C	No	No	Inside Pole	69.00 - 0.00	1	No Ice	0.00	0.24
							1/2" Ice	0.00	0.24
							1" Ice	0.00	0.24
							2" Ice	0.00	0.24
HB114-1-08U4-M5J(1-1/4)	C	No	No	Inside Pole	69.00 - 0.00	3	No Ice	0.00	1.08
							1/2" Ice	0.00	1.08
							1" Ice	0.00	1.08
							2" Ice	0.00	1.08

Feed Line/Linear Appurtenances Section Areas

Tower Section	Tower Elevation ft	Face	A _R ft ²	A _F ft ²	C _{AA} In Face ft ²	C _{AA} Out Face ft ²	Weight K
L1	109.00-95.00	A	0.000	0.000	0.000	0.000	0.00
		B	0.000	0.000	0.000	0.000	0.27
		C	0.000	0.000	0.960	0.000	0.01
L2	95.00-48.08	A	0.000	0.000	40.846	0.000	0.64
		B	0.000	0.000	0.000	0.000	0.89
		C	0.000	0.000	24.044	0.000	0.25
L3	48.08-0.00	A	0.000	0.000	44.714	0.000	0.75
		B	0.000	0.000	0.000	0.000	0.92
		C	0.000	0.000	64.812	0.000	0.52

Feed Line/Linear Appurtenances Section Areas - With Ice

Tower Sectio n	Tower Elevation ft	Face or Leg	Ice Thickness in	A_R ft ²	A_F ft ²	C_{AA} In Face ft ²	C_{AA} Out Face ft ²	Weight K
L1	109.00-95.00	A	1.903	0.000	0.000	0.000	0.000	0.00
		B		0.000	0.000	0.000	0.000	0.27
		C		0.000	0.000	3.243	0.000	0.06
L2	95.00-48.08	A	1.834	0.000	0.000	71.199	0.000	1.50
		B		0.000	0.000	0.000	0.000	0.89
		C		0.000	0.000	51.776	0.000	0.95
L3	48.08-0.00	A	1.647	0.000	0.000	77.942	0.000	1.69
		B		0.000	0.000	0.000	0.000	0.92
		C		0.000	0.000	118.781	0.000	2.06

Feed Line Center of Pressure

Section	Elevation ft	CP_x in	CP_z in	CP_x Ice in	CP_z Ice in
L1	109.00-95.00	-0.2438	0.5325	-0.4218	0.9213
L2	95.00-48.08	-1.0226	-1.6323	-1.0953	-0.9181
L3	48.08-0.00	-0.9538	1.9182	-1.0331	1.8362

Note: For pole sections, center of pressure calculations do not consider feed line shielding.

Shielding Factor Ka

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K_a No Ice	K_a Ice
L1	9	CU12PSM9P6XXX(1-1/2)	95.00 - 101.00	1.0000	1.0000
L2	9	CU12PSM9P6XXX(1-1/2)	48.08 - 95.00	1.0000	1.0000
L2	12	LDF6-50A(1-1/4")	48.08 - 92.00	1.0000	1.0000
L2	20	CR 50 1873(1-5/8)	48.08 - 62.00	1.0000	1.0000
L3	9	CU12PSM9P6XXX(1-1/2)	0.00 - 48.08	1.0000	1.0000
L3	12	LDF6-50A(1-1/4")	0.00 - 48.08	1.0000	1.0000
L3	20	CR 50 1873(1-5/8)	0.00 - 48.08	1.0000	1.0000

Discrete Tower Loads

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustmen t °	Placement ft	C_{AA} Front ft ²	C_{AA} Side ft ²	Weight K	
Lighting Rod 3/4" x 4'	C	None		0.0000	111.00	No Ice	0.30	0.30	0.03

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment t °	Placement ft	C _{AA} Front ft ²	C _{AA} Side ft ²	Weight K	
						1/2"	0.71	0.71	0.03
						Ice	1.00	1.00	0.04
						1" Ice	1.52	1.52	0.06
						2" Ice			
**									
800 10121 w/ Mount Pipe	A	From Leg	4.00 0.00 2.00	0.0000	109.00	No Ice 1/2" Ice 1" Ice 2" Ice	3.60 4.00 4.42 5.29	2.95 3.34 3.74 4.59	0.07 0.11 0.17 0.30
800 10121 w/ Mount Pipe	B	From Leg	4.00 0.00 2.00	0.0000	109.00	No Ice 1/2" Ice 1" Ice 2" Ice	3.60 4.00 4.42 5.29	2.95 3.34 3.74 4.59	0.07 0.11 0.17 0.30
800 10121 w/ Mount Pipe	C	From Leg	4.00 0.00 2.00	0.0000	109.00	No Ice 1/2" Ice 1" Ice 2" Ice	3.60 4.00 4.42 5.29	2.95 3.34 3.74 4.59	0.07 0.11 0.17 0.30
80010966 w/ Mount Pipe	A	From Leg	4.00 0.00 2.00	0.0000	109.00	No Ice 1/2" Ice 1" Ice 2" Ice	14.61 15.47 16.35 18.14	6.84 7.63 8.42 10.06	0.16 0.27 0.39 0.68
80010966 w/ Mount Pipe	B	From Leg	4.00 0.00 2.00	0.0000	109.00	No Ice 1/2" Ice 1" Ice 2" Ice	14.61 15.47 16.35 18.14	6.84 7.63 8.42 10.06	0.16 0.27 0.39 0.68
80010966 w/ Mount Pipe	C	From Leg	4.00 0.00 2.00	0.0000	109.00	No Ice 1/2" Ice 1" Ice 2" Ice	14.61 15.47 16.35 18.14	6.84 7.63 8.42 10.06	0.16 0.27 0.39 0.68
HPA-65R-BUU-H8 w/ Mount Pipe	A	From Leg	4.00 0.00 2.00	0.0000	109.00	No Ice 1/2" Ice 1" Ice 2" Ice	12.25 13.19 14.16 16.14	8.33 9.23 10.15 12.05	0.10 0.19 0.30 0.54
HPA-65R-BUU-H8 w/ Mount Pipe	B	From Leg	4.00 0.00 2.00	0.0000	109.00	No Ice 1/2" Ice 1" Ice 2" Ice	12.25 13.19 14.16 16.14	8.33 9.23 10.15 12.05	0.10 0.19 0.30 0.54
HPA-65R-BUU-H8 w/ Mount Pipe	C	From Leg	4.00 0.00 2.00	0.0000	109.00	No Ice 1/2" Ice 1" Ice 2" Ice	12.25 13.19 14.16 16.14	8.33 9.23 10.15 12.05	0.10 0.19 0.30 0.54
HPA65R-BU8A w/ Mount Pipe	A	From Leg	4.00 0.00 2.00	0.0000	109.00	No Ice 1/2" Ice 1" Ice 2" Ice	8.10 8.86 9.64 11.24	6.94 7.69 8.45 10.03	0.09 0.17 0.27 0.50
HPA65R-BU8A w/ Mount Pipe	B	From Leg	4.00 0.00 2.00	0.0000	109.00	No Ice 1/2" Ice 1" Ice 2" Ice	8.10 8.86 9.64 11.24	6.94 7.69 8.45 10.03	0.09 0.17 0.27 0.50
HPA65R-BU8A w/ Mount Pipe	C	From Leg	4.00 0.00 2.00	0.0000	109.00	No Ice 1/2" Ice 1" Ice 2" Ice	8.10 8.86 9.64 11.24	6.94 7.69 8.45 10.03	0.09 0.17 0.27 0.50

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C _{AA} _{Front}	C _{AA} _{Side}	Weight	
			Horz	Lateral						Vert
			ft	ft	°	ft	ft ²	ft ²	K	
(2) TT19-08BP111-001	A	From Leg	4.00		0.0000	109.00	No Ice	0.55	0.44	0.02
			0.00				1/2"	0.64	0.53	0.02
			0.00				Ice	0.74	0.63	0.03
							1" Ice	0.97	0.84	0.05
							2" Ice			
(2) TT19-08BP111-001	B	From Leg	4.00		0.0000	109.00	No Ice	0.55	0.44	0.02
			0.00				1/2"	0.64	0.53	0.02
			0.00				Ice	0.74	0.63	0.03
							1" Ice	0.97	0.84	0.05
							2" Ice			
(2) TT19-08BP111-001	C	From Leg	4.00		0.0000	109.00	No Ice	0.55	0.44	0.02
			0.00				1/2"	0.64	0.53	0.02
			0.00				Ice	0.74	0.63	0.03
							1" Ice	0.97	0.84	0.05
							2" Ice			
RADIO 4415 B30	A	From Leg	4.00		0.0000	109.00	No Ice	1.64	0.64	0.04
			0.00				1/2"	1.80	0.75	0.05
			2.00				Ice	1.97	0.87	0.07
							1" Ice	2.33	1.13	0.11
							2" Ice			
RADIO 4415 B30	B	From Leg	4.00		0.0000	109.00	No Ice	1.64	0.64	0.04
			0.00				1/2"	1.80	0.75	0.05
			2.00				Ice	1.97	0.87	0.07
							1" Ice	2.33	1.13	0.11
							2" Ice			
RADIO 4415 B30	C	From Leg	4.00		0.0000	109.00	No Ice	1.64	0.64	0.04
			0.00				1/2"	1.80	0.75	0.05
			2.00				Ice	1.97	0.87	0.07
							1" Ice	2.33	1.13	0.11
							2" Ice			
RRUS 8843 B2/B66A	A	From Leg	4.00		0.0000	109.00	No Ice	1.64	1.35	0.07
			0.00				1/2"	1.80	1.50	0.09
			2.00				Ice	1.97	1.65	0.11
							1" Ice	2.32	1.99	0.16
							2" Ice			
RRUS 8843 B2/B66A	B	From Leg	4.00		0.0000	109.00	No Ice	1.64	1.35	0.07
			0.00				1/2"	1.80	1.50	0.09
			2.00				Ice	1.97	1.65	0.11
							1" Ice	2.32	1.99	0.16
							2" Ice			
RRUS 8843 B2/B66A	C	From Leg	4.00		0.0000	109.00	No Ice	1.64	1.35	0.07
			0.00				1/2"	1.80	1.50	0.09
			2.00				Ice	1.97	1.65	0.11
							1" Ice	2.32	1.99	0.16
							2" Ice			
DC6-48-60-18-8F	A	From Leg	4.00		0.0000	109.00	No Ice	1.21	1.21	0.02
			0.00				1/2"	1.89	1.89	0.04
			2.00				Ice	2.11	2.11	0.07
							1" Ice	2.57	2.57	0.13
							2" Ice			
DC6-48-60-18-8F	B	From Leg	4.00		0.0000	109.00	No Ice	1.21	1.21	0.02
			0.00				1/2"	1.89	1.89	0.04
			2.00				Ice	2.11	2.11	0.07
							1" Ice	2.57	2.57	0.13
							2" Ice			
DC6-48-60-18-8F	C	From Leg	4.00		0.0000	109.00	No Ice	1.21	1.21	0.02
			0.00				1/2"	1.89	1.89	0.04
			2.00				Ice	2.11	2.11	0.07
							1" Ice	2.57	2.57	0.13
							2" Ice			
RRUS 4449 B5/B12	A	From Leg	4.00		0.0000	109.00	No Ice	1.97	1.41	0.07
			0.00				1/2"	2.14	1.56	0.09
			2.00				Ice	2.33	1.73	0.11
							1" Ice	2.72	2.07	0.16
							2" Ice			

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C _{AA} _{Front}	C _{AA} _{Side}	Weight	
			Horz	Lateral						Vert
			ft	ft	°	ft	ft ²	ft ²	K	
RRUS 4449 B5/B12	B	From Leg	4.00		0.0000	109.00	No Ice	1.97	1.41	0.07
			0.00				1/2"	2.14	1.56	0.09
			2.00				Ice	2.33	1.73	0.11
							1" Ice	2.72	2.07	0.16
							2" Ice			
RRUS 4449 B5/B12	C	From Leg	4.00		0.0000	109.00	No Ice	1.97	1.41	0.07
			0.00				1/2"	2.14	1.56	0.09
			2.00				Ice	2.33	1.73	0.11
							1" Ice	2.72	2.07	0.16
							2" Ice			
6' x 2" Mount Pipe	A	From Leg	1.00		0.0000	109.00	No Ice	1.43	1.43	0.02
			0.00				1/2"	1.92	1.92	0.03
			2.00				Ice	2.29	2.29	0.05
							1" Ice	3.06	3.06	0.09
							2" Ice			
6' x 2" Mount Pipe	B	From Leg	1.00		0.0000	109.00	No Ice	1.43	1.43	0.02
			0.00				1/2"	1.92	1.92	0.03
			2.00				Ice	2.29	2.29	0.05
							1" Ice	3.06	3.06	0.09
							2" Ice			
6' x 2" Mount Pipe	C	From Leg	1.00		0.0000	109.00	No Ice	1.43	1.43	0.02
			0.00				1/2"	1.92	1.92	0.03
			2.00				Ice	2.29	2.29	0.05
							1" Ice	3.06	3.06	0.09
							2" Ice			
Platform Mount [LP 714-1]	C	None			0.0000	109.00	No Ice	37.51	37.51	1.60
							1/2"	41.70	41.70	2.50
							Ice	45.89	45.89	3.46
							1" Ice	54.29	54.29	5.58
							2" Ice			
**										
MX08FRO665-21 w/ Mount Pipe	A	From Leg	4.00		0.0000	101.00	No Ice	8.01	4.23	0.11
			0.00				1/2"	8.52	4.69	0.19
			0.00				Ice	9.04	5.16	0.29
							1" Ice	10.11	6.12	0.52
							2" Ice			
MX08FRO665-21 w/ Mount Pipe	B	From Leg	4.00		0.0000	101.00	No Ice	8.01	4.23	0.11
			0.00				1/2"	8.52	4.69	0.19
			0.00				Ice	9.04	5.16	0.29
							1" Ice	10.11	6.12	0.52
							2" Ice			
MX08FRO665-21 w/ Mount Pipe	C	From Leg	4.00		0.0000	101.00	No Ice	8.01	4.23	0.11
			0.00				1/2"	8.52	4.69	0.19
			0.00				Ice	9.04	5.16	0.29
							1" Ice	10.11	6.12	0.52
							2" Ice			
TA08025-B605	A	From Leg	4.00		0.0000	101.00	No Ice	1.96	1.13	0.08
			0.00				1/2"	2.14	1.27	0.09
			0.00				Ice	2.32	1.41	0.11
							1" Ice	2.71	1.72	0.16
							2" Ice			
TA08025-B605	B	From Leg	4.00		0.0000	101.00	No Ice	1.96	1.13	0.08
			0.00				1/2"	2.14	1.27	0.09
			0.00				Ice	2.32	1.41	0.11
							1" Ice	2.71	1.72	0.16
							2" Ice			
TA08025-B605	C	From Leg	4.00		0.0000	101.00	No Ice	1.96	1.13	0.08
			0.00				1/2"	2.14	1.27	0.09
			0.00				Ice	2.32	1.41	0.11
							1" Ice	2.71	1.72	0.16
							2" Ice			
TA08025-B604	A	From Leg	4.00		0.0000	101.00	No Ice	1.96	0.98	0.06
			0.00				1/2"	2.14	1.11	0.08
			0.00				Ice	2.32	1.25	0.10
							1" Ice	2.71	1.55	0.15
							2" Ice			

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C _{AA} _{Front}	C _{AA} _{Side}	Weight	
			Horz	Lateral Vert						ft
TA08025-B604	B	From Leg	4.00	0.00	0.0000	101.00	2" Ice			
							No Ice	1.96	0.98	0.06
							1/2"	2.14	1.11	0.08
							Ice	2.32	1.25	0.10
							1" Ice	2.71	1.55	0.15
TA08025-B604	C	From Leg	4.00	0.00	0.0000	101.00	2" Ice			
							No Ice	1.96	0.98	0.06
							1/2"	2.14	1.11	0.08
							Ice	2.32	1.25	0.10
							1" Ice	2.71	1.55	0.15
RDIDC-9181-PF-48	A	From Leg	4.00	0.00	0.0000	101.00	2" Ice			
							No Ice	2.31	1.29	0.02
							1/2"	2.50	1.45	0.04
							Ice	2.70	1.61	0.06
							1" Ice	3.12	1.96	0.12
(2) 8' x 2" Mount Pipe	A	From Leg	4.00	0.00	0.0000	101.00	2" Ice			
							No Ice	1.90	1.90	0.03
							1/2"	2.73	2.73	0.04
							Ice	3.40	3.40	0.06
							1" Ice	4.40	4.40	0.12
(2) 8' x 2" Mount Pipe	B	From Leg	4.00	0.00	0.0000	101.00	2" Ice			
							No Ice	1.90	1.90	0.03
							1/2"	2.73	2.73	0.04
							Ice	3.40	3.40	0.06
							1" Ice	4.40	4.40	0.12
(2) 8' x 2" Mount Pipe	C	From Leg	4.00	0.00	0.0000	101.00	2" Ice			
							No Ice	1.90	1.90	0.03
							1/2"	2.73	2.73	0.04
							Ice	3.40	3.40	0.06
							1" Ice	4.40	4.40	0.12
Commscope MC-PK8-DSH	C	None			0.0000	101.00	2" Ice			
							No Ice	34.24	34.24	1.75
							1/2"	62.95	62.95	2.10
							Ice	91.66	91.66	2.45
							1" Ice	149.08	149.08	3.15
** (2) LPA-80080-4CF-EDIN-0 w/ Mount Pipe	A	From Leg	4.00	0.00	0.0000	92.00	2" Ice			
							No Ice	2.86	6.57	0.03
							1/2"	3.22	7.19	0.08
							Ice	3.59	7.84	0.13
							1" Ice	4.34	9.17	0.25
(2) SBNHH-1D65B w/ Mount Pipe	A	From Leg	4.00	0.00	0.0000	92.00	2" Ice			
							No Ice	4.09	3.30	0.07
							1/2"	4.49	3.68	0.13
							Ice	4.89	4.07	0.20
							1" Ice	5.72	4.87	0.39
(2) SBNHH-1D65B w/ Mount Pipe	B	From Leg	4.00	0.00	0.0000	92.00	2" Ice			
							No Ice	4.09	3.30	0.07
							1/2"	4.49	3.68	0.13
							Ice	4.89	4.07	0.20
							1" Ice	5.72	4.87	0.39
(2) SBNHH-1D65B w/ Mount Pipe	C	From Leg	4.00	0.00	0.0000	92.00	2" Ice			
							No Ice	4.09	3.30	0.07
							1/2"	4.49	3.68	0.13
							Ice	4.89	4.07	0.20
							1" Ice	5.72	4.87	0.39
(2) SC 9012 REV2 w/ Mount Pipe	B	From Leg	4.00	0.00	0.0000	92.00	2" Ice			
							No Ice	2.91	4.22	0.03
							1/2"	3.25	4.78	0.06
							Ice	3.59	5.35	0.10
							1" Ice	4.29	6.55	0.21
(2) SC 9012 REV2 w/ Mount Pipe	C	From Leg	4.00	0.00	0.0000	92.00	2" Ice			
							No Ice	2.91	4.22	0.03
							1/2"	3.25	4.78	0.06
							Ice	3.59	5.35	0.10
							1" Ice	4.29	6.55	0.21

Description	Face or Leg	Offset Type	Offsets:			Azimuth Adjustment	Placement	C _{AA} _{Front}	C _{AA} _{Side}	Weight	
			Horz	Lateral	Vert						ft
			ft	ft	ft	°	ft	ft ²	ft ²	K	
B13 RRH 4X30	A	From Leg	4.00	0.00	-1.00	0.0000	92.00	1" Ice	4.29	6.55	0.21
								2" Ice	2.06	1.32	0.06
								No Ice	2.24	1.48	0.07
								1/2" Ice	2.43	1.64	0.09
								1" Ice	2.84	2.00	0.14
B13 RRH 4X30	B	From Leg	4.00	0.00	-1.00	0.0000	92.00	1" Ice	2.06	1.32	0.06
								2" Ice	2.24	1.48	0.07
								No Ice	2.43	1.64	0.09
								1/2" Ice	2.84	2.00	0.14
								1" Ice	2.06	1.32	0.06
B13 RRH 4X30	C	From Leg	4.00	0.00	-1.00	0.0000	92.00	1" Ice	2.24	1.48	0.07
								2" Ice	2.43	1.64	0.09
								No Ice	2.84	2.00	0.14
								1/2" Ice	2.06	1.32	0.06
								1" Ice	2.24	1.48	0.07
RRH2X60-AWS	A	From Leg	4.00	0.00	-1.00	0.0000	92.00	1" Ice	4.03	2.29	0.11
								2" Ice	4.58	2.79	0.17
								No Ice	3.50	1.82	0.06
								1/2" Ice	3.76	2.05	0.08
								1" Ice	4.03	2.29	0.11
RRH2X60-AWS	B	From Leg	4.00	0.00	-1.00	0.0000	92.00	1" Ice	4.58	2.79	0.17
								2" Ice	3.50	1.82	0.06
								No Ice	3.76	2.05	0.08
								1/2" Ice	4.03	2.29	0.11
								1" Ice	4.58	2.79	0.17
RRH2X60-AWS	C	From Leg	4.00	0.00	-1.00	0.0000	92.00	1" Ice	3.50	1.82	0.06
								2" Ice	3.76	2.05	0.08
								No Ice	4.03	2.29	0.11
								1/2" Ice	4.58	2.79	0.17
								1" Ice	3.50	1.82	0.06
(2) RC2DC-3315-PF-48	A	From Leg	4.00	0.00	-1.00	0.0000	92.00	1" Ice	4.84	3.41	0.18
								2" Ice	3.79	2.51	0.03
								No Ice	4.04	2.72	0.06
								1/2" Ice	4.30	2.94	0.10
								1" Ice	4.84	3.41	0.18
PCS B25 RRH4X30	A	From Leg	4.00	0.00	-1.00	0.0000	92.00	1" Ice	3.01	2.50	0.16
								2" Ice	2.20	1.74	0.06
								No Ice	2.39	1.92	0.08
								1/2" Ice	2.59	2.11	0.10
								1" Ice	3.01	2.50	0.16
PCS B25 RRH4X30	B	From Leg	4.00	0.00	-1.00	0.0000	92.00	1" Ice	2.20	1.74	0.06
								2" Ice	2.39	1.92	0.08
								No Ice	2.59	2.11	0.10
								1/2" Ice	3.01	2.50	0.16
								1" Ice	2.20	1.74	0.06
PCS B25 RRH4X30	C	From Leg	4.00	0.00	-1.00	0.0000	92.00	1" Ice	2.39	1.92	0.08
								2" Ice	2.59	2.11	0.10
								No Ice	3.01	2.50	0.16
								1/2" Ice	2.20	1.74	0.06
								1" Ice	2.39	1.92	0.08
8' x 2" Mount Pipe	A	From Leg	4.00	0.00	-1.00	0.0000	92.00	1" Ice	4.40	4.40	0.12
								2" Ice	1.90	1.90	0.03
								No Ice	2.73	2.73	0.04
								1/2" Ice	3.40	3.40	0.06
								1" Ice	4.40	4.40	0.12
8' x 2" Mount Pipe	B	From Leg	4.00	0.00	-1.00	0.0000	92.00	1" Ice	1.90	1.90	0.03
								2" Ice	2.73	2.73	0.04
								No Ice	3.40	3.40	0.06
								1/2" Ice	4.40	4.40	0.12
								1" Ice	1.90	1.90	0.03
8' x 2" Mount Pipe	C	From Leg	4.00	0.00	-1.00	0.0000	92.00	1" Ice	2.73	2.73	0.04
								2" Ice	3.40	3.40	0.06
								No Ice	3.40	3.40	0.06

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment t °	Placement ft	C _{AA} Front ft ²	C _{AA} Side ft ²	Weight K	
						1" Ice 2" Ice No Ice	4.40 4.40	0.12	
Platform Mount [LP 715-1]	C	None		0.0000	92.00	46.77 50.25 53.97 62.22	46.77 50.25 53.97 62.22	1.77 2.88 4.09 6.81	
**									
(4) DB844H90-XY w/ Mount Pipe	A	From Face	4.00 0.00 1.00	0.0000	80.00	No Ice 1/2" Ice 1" Ice 2" Ice	2.24 2.61 2.99 3.78	3.34 3.73 4.13 4.97	0.04 0.07 0.12 0.23
(4) DB844H90-XY w/ Mount Pipe	B	From Face	4.00 0.00 1.00	0.0000	80.00	No Ice 1/2" Ice 1" Ice 2" Ice	2.24 2.61 2.99 3.78	3.34 3.73 4.13 4.97	0.04 0.07 0.12 0.23
(4) DB844H90-XY w/ Mount Pipe	C	From Face	4.00 0.00 1.00	0.0000	80.00	No Ice 1/2" Ice 1" Ice 2" Ice	2.24 2.61 2.99 3.78	3.34 3.73 4.13 4.97	0.04 0.07 0.12 0.23
Platform Mount [LP 1201-1]	C	None		0.0000	80.00	No Ice 1/2" Ice 1" Ice 2" Ice	18.38 22.11 25.87 33.47	18.38 22.11 25.87 33.47	2.10 2.65 3.26 4.66
level 74									
800MHZ 2X50W RRH W/FILTER	A	From Leg	2.00 0.00 -2.00	0.0000	74.00	No Ice 1/2" Ice 1" Ice 2" Ice	2.06 2.24 2.43 2.83	1.93 2.11 2.29 2.68	0.06 0.09 0.11 0.17
800MHZ 2X50W RRH W/FILTER	B	From Leg	2.00 0.00 -2.00	0.0000	74.00	No Ice 1/2" Ice 1" Ice 2" Ice	2.06 2.24 2.43 2.83	1.93 2.11 2.29 2.68	0.06 0.09 0.11 0.17
800MHZ 2X50W RRH W/FILTER	C	From Leg	2.00 0.00 -2.00	0.0000	74.00	No Ice 1/2" Ice 1" Ice 2" Ice	2.06 2.24 2.43 2.83	1.93 2.11 2.29 2.68	0.06 0.09 0.11 0.17
PCS 1900MHZ 4X45W- 65MHZ	A	From Leg	2.00 0.00 1.00	0.0000	74.00	No Ice 1/2" Ice 1" Ice 2" Ice	2.32 2.53 2.74 3.19	2.24 2.44 2.65 3.09	0.06 0.08 0.11 0.17
PCS 1900MHZ 4X45W- 65MHZ	B	From Leg	2.00 0.00 1.00	0.0000	74.00	No Ice 1/2" Ice 1" Ice 2" Ice	2.32 2.53 2.74 3.19	2.24 2.44 2.65 3.09	0.06 0.08 0.11 0.17
PCS 1900MHZ 4X45W- 65MHZ	C	From Leg	2.00 0.00 1.00	0.0000	74.00	No Ice 1/2" Ice 1" Ice 2" Ice	2.32 2.53 2.74 3.19	2.24 2.44 2.65 3.09	0.06 0.08 0.11 0.17
(2) 5'x2 1/2" Pipe Mount	A	From Leg	2.00 0.00 0.00	0.0000	74.00	No Ice 1/2" Ice 1" Ice 2" Ice	1.33 1.63 1.95 2.60	1.33 1.63 1.95 2.60	0.03 0.04 0.05 0.09
(2) 5'x2 1/2" Pipe Mount	B	From Leg	2.00	0.0000	74.00	No Ice	1.33	1.33	0.03

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C _{AA} _{Front}	C _{AA} _{Side}	Weight	
			Horz	Lateral						Vert
			ft	ft	°	ft	ft ²	ft ²	K	
			0.00			1/2"	1.63	1.63	0.04	
			0.00			Ice	1.95	1.95	0.05	
						1" Ice	2.60	2.60	0.09	
						2" Ice				
(2) 5'x2 1/2" Pipe Mount	C	From Leg	2.00		0.0000	74.00	No Ice	1.33	1.33	0.03
			0.00				1/2"	1.63	1.63	0.04
			0.00				Ice	1.95	1.95	0.05
							1" Ice	2.60	2.60	0.09
							2" Ice			
Side Arm Mount [SO 102-3]	C	None			0.0000	74.00	No Ice	3.60	3.60	0.07
							1/2"	4.18	4.18	0.11
							Ice	4.75	4.75	0.14
							1" Ice	5.90	5.90	0.20
							2" Ice			
**										
APXVMTM14-C-120 w/ Mount Pipe	A	From Face	4.00		0.0000	69.00	No Ice	4.09	2.86	0.08
			0.00				1/2"	4.48	3.23	0.13
			2.00				Ice	4.88	3.61	0.19
							1" Ice	5.71	4.40	0.33
							2" Ice			
APXVMTM14-C-120 w/ Mount Pipe	B	From Face	4.00		0.0000	69.00	No Ice	4.09	2.86	0.08
			0.00				1/2"	4.48	3.23	0.13
			2.00				Ice	4.88	3.61	0.19
							1" Ice	5.71	4.40	0.33
							2" Ice			
APXVMTM14-C-120 w/ Mount Pipe	C	From Face	4.00		0.0000	69.00	No Ice	4.09	2.86	0.08
			0.00				1/2"	4.48	3.23	0.13
			2.00				Ice	4.88	3.61	0.19
							1" Ice	5.71	4.40	0.33
							2" Ice			
APXV9ERR18-C-A20 w/ Mount Pipe	A	From Face	4.00		0.0000	69.00	No Ice	4.60	4.01	0.10
			0.00				1/2"	5.05	4.45	0.16
			2.00				Ice	5.50	4.89	0.23
							1" Ice	6.44	5.82	0.42
							2" Ice			
APXV9ERR18-C-A20 w/ Mount Pipe	C	From Face	4.00		0.0000	69.00	No Ice	4.60	4.01	0.10
			0.00				1/2"	5.05	4.45	0.16
			2.00				Ice	5.50	4.89	0.23
							1" Ice	6.44	5.82	0.42
							2" Ice			
APXVSP18-C-A20 w/ Mount Pipe	B	From Face	4.00		0.0000	69.00	No Ice	4.60	4.01	0.10
			0.00				1/2"	5.05	4.45	0.16
			2.00				Ice	5.50	4.89	0.23
							1" Ice	6.44	5.82	0.42
							2" Ice			
TD-RRH8X20-25	A	From Face	4.00		0.0000	69.00	No Ice	4.05	1.53	0.07
			0.00				1/2"	4.30	1.71	0.10
			3.00				Ice	4.56	1.90	0.13
							1" Ice	5.10	2.30	0.20
							2" Ice			
TD-RRH8X20-25	B	From Face	4.00		0.0000	69.00	No Ice	4.05	1.53	0.07
			0.00				1/2"	4.30	1.71	0.10
			3.00				Ice	4.56	1.90	0.13
							1" Ice	5.10	2.30	0.20
							2" Ice			
TD-RRH8X20-25	C	From Face	4.00		0.0000	69.00	No Ice	4.05	1.53	0.07
			0.00				1/2"	4.30	1.71	0.10
			3.00				Ice	4.56	1.90	0.13
							1" Ice	5.10	2.30	0.20
							2" Ice			
6' x 2" Mount Pipe	A	From Face	4.00		0.0000	69.00	No Ice	1.43	1.43	0.02
			0.00				1/2"	1.92	1.92	0.03
			2.00				Ice	2.29	2.29	0.05
							1" Ice	3.06	3.06	0.09
							2" Ice			

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C _{AA} _{Front}	C _{AA} _{Side}	Weight	
			Horz	Lateral						Vert
			ft	ft	°	ft	ft ²	ft ²	K	
6' x 2" Mount Pipe	B	From Face	4.00		0.0000	69.00	No Ice	1.43	1.43	0.02
			0.00				1/2"	1.92	1.92	0.03
			2.00				Ice	2.29	2.29	0.05
							1" Ice	3.06	3.06	0.09
							2" Ice			
6' x 2" Mount Pipe	C	From Face	4.00		0.0000	69.00	No Ice	1.43	1.43	0.02
			0.00				1/2"	1.92	1.92	0.03
			2.00				Ice	2.29	2.29	0.05
							1" Ice	3.06	3.06	0.09
							2" Ice			
Platform Mount [LP 1201-1]	C	None			0.0000	69.00	No Ice	18.38	18.38	2.10
							1/2"	22.11	22.11	2.65
							Ice	25.87	25.87	3.26
							1" Ice	33.47	33.47	4.66
							2" Ice			
**										
APX18-206516L	A	From Leg	1.00		0.0000	62.00	No Ice	2.56	1.21	0.03
			0.00				1/2"	3.00	1.63	0.05
			0.00				Ice	3.45	2.05	0.07
							1" Ice	4.41	2.95	0.13
							2" Ice			
APX18-206516L	B	From Leg	1.00		0.0000	62.00	No Ice	2.56	1.21	0.03
			0.00				1/2"	3.00	1.63	0.05
			0.00				Ice	3.45	2.05	0.07
							1" Ice	4.41	2.95	0.13
							2" Ice			
APX18-206516L	C	From Leg	1.00		0.0000	62.00	No Ice	2.56	1.21	0.03
			0.00				1/2"	3.00	1.63	0.05
			0.00				Ice	3.45	2.05	0.07
							1" Ice	4.41	2.95	0.13
							2" Ice			
Pipe Mount [PM 602-3]	C	None			0.0000	62.00	No Ice	6.67	6.67	0.28
							1/2"	7.70	7.70	0.34
							Ice	8.74	8.74	0.42
							1" Ice	10.90	10.90	0.63
							2" Ice			

Load Combinations

Comb. No.	Description
1	Dead Only
2	1.2 Dead+1.0 Wind 0 deg - No Ice
3	0.9 Dead+1.0 Wind 0 deg - No Ice
4	1.2 Dead+1.0 Wind 30 deg - No Ice
5	0.9 Dead+1.0 Wind 30 deg - No Ice
6	1.2 Dead+1.0 Wind 60 deg - No Ice
7	0.9 Dead+1.0 Wind 60 deg - No Ice
8	1.2 Dead+1.0 Wind 90 deg - No Ice
9	0.9 Dead+1.0 Wind 90 deg - No Ice
10	1.2 Dead+1.0 Wind 120 deg - No Ice
11	0.9 Dead+1.0 Wind 120 deg - No Ice
12	1.2 Dead+1.0 Wind 150 deg - No Ice
13	0.9 Dead+1.0 Wind 150 deg - No Ice
14	1.2 Dead+1.0 Wind 180 deg - No Ice
15	0.9 Dead+1.0 Wind 180 deg - No Ice
16	1.2 Dead+1.0 Wind 210 deg - No Ice
17	0.9 Dead+1.0 Wind 210 deg - No Ice

Comb. No.	Description
18	1.2 Dead+1.0 Wind 240 deg - No Ice
19	0.9 Dead+1.0 Wind 240 deg - No Ice
20	1.2 Dead+1.0 Wind 270 deg - No Ice
21	0.9 Dead+1.0 Wind 270 deg - No Ice
22	1.2 Dead+1.0 Wind 300 deg - No Ice
23	0.9 Dead+1.0 Wind 300 deg - No Ice
24	1.2 Dead+1.0 Wind 330 deg - No Ice
25	0.9 Dead+1.0 Wind 330 deg - No Ice
26	1.2 Dead+1.0 Ice+1.0 Temp
27	1.2 Dead+1.0 Wind 0 deg+1.0 Ice+1.0 Temp
28	1.2 Dead+1.0 Wind 30 deg+1.0 Ice+1.0 Temp
29	1.2 Dead+1.0 Wind 60 deg+1.0 Ice+1.0 Temp
30	1.2 Dead+1.0 Wind 90 deg+1.0 Ice+1.0 Temp
31	1.2 Dead+1.0 Wind 120 deg+1.0 Ice+1.0 Temp
32	1.2 Dead+1.0 Wind 150 deg+1.0 Ice+1.0 Temp
33	1.2 Dead+1.0 Wind 180 deg+1.0 Ice+1.0 Temp
34	1.2 Dead+1.0 Wind 210 deg+1.0 Ice+1.0 Temp
35	1.2 Dead+1.0 Wind 240 deg+1.0 Ice+1.0 Temp
36	1.2 Dead+1.0 Wind 270 deg+1.0 Ice+1.0 Temp
37	1.2 Dead+1.0 Wind 300 deg+1.0 Ice+1.0 Temp
38	1.2 Dead+1.0 Wind 330 deg+1.0 Ice+1.0 Temp
39	Dead+Wind 0 deg - Service
40	Dead+Wind 30 deg - Service
41	Dead+Wind 60 deg - Service
42	Dead+Wind 90 deg - Service
43	Dead+Wind 120 deg - Service
44	Dead+Wind 150 deg - Service
45	Dead+Wind 180 deg - Service
46	Dead+Wind 210 deg - Service
47	Dead+Wind 240 deg - Service
48	Dead+Wind 270 deg - Service
49	Dead+Wind 300 deg - Service
50	Dead+Wind 330 deg - Service

Maximum Member Forces

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Axial K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
L1	109 - 95	Pole	Max Tension	26	0.00	-0.00	-0.00
			Max. Compression	26	-23.13	0.02	0.56
			Max. Mx	20	-8.03	145.71	0.11
			Max. My	2	-8.02	0.00	146.03
			Max. Vy	20	-12.04	145.71	0.11
			Max. Vx	2	-12.07	0.00	146.03
			Max. Torque	20			-0.25
L2	95 - 48.08	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-65.82	1.28	2.44
			Max. Mx	20	-26.36	1043.33	0.30
			Max. My	2	-26.36	0.24	1042.08
			Max. Vy	20	-26.38	1043.33	0.30
			Max. Vx	2	-26.33	0.24	1042.08
			Max. Torque	9			2.04
L3	48.08 - 0	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-87.89	3.29	-0.18
			Max. Mx	20	-41.69	2544.21	-0.27
			Max. My	14	-41.69	0.64	-2540.13
			Max. Vy	20	-30.03	2544.21	-0.27
			Max. Vx	14	29.98	0.64	-2540.13
			Max. Torque	9			2.04

Maximum Reactions

Location	Condition	Gov. Load Comb.	Vertical K	Horizontal, X K	Horizontal, Z K
Pole	Max. Vert	36	87.89	8.99	0.00
	Max. H _x	21	31.29	29.99	0.00
	Max. H _z	2	41.72	0.00	29.94
	Max. M _x	2	2539.61	0.00	29.94
	Max. M _z	8	2542.93	-29.99	0.00
	Max. Torsion	9	2.03	-29.99	0.00
	Min. Vert	5	31.29	-14.99	25.93
	Min. H _x	9	31.29	-29.99	0.00
	Min. H _z	14	41.72	0.00	-29.94
	Min. M _x	14	-2540.13	0.00	-29.94
	Min. M _z	20	-2544.21	29.99	0.00
	Min. Torsion	21	-2.03	29.99	0.00

Tower Mast Reaction Summary

Load Combination	Vertical K	Shear _x K	Shear _z K	Overtuning Moment, M _x kip-ft	Overtuning Moment, M _z kip-ft	Torque kip-ft
Dead Only	34.76	0.00	0.00	0.22	0.52	0.00
1.2 Dead+1.0 Wind 0 deg - No Ice	41.72	0.00	-29.94	-2539.61	0.64	0.00
0.9 Dead+1.0 Wind 0 deg - No Ice	31.29	0.00	-29.94	-2517.42	0.48	0.00
1.2 Dead+1.0 Wind 30 deg - No Ice	41.72	14.99	-25.93	-2199.33	-1271.15	-1.02
0.9 Dead+1.0 Wind 30 deg - No Ice	31.29	14.99	-25.93	-2180.12	-1260.17	-1.02
1.2 Dead+1.0 Wind 60 deg - No Ice	41.72	25.97	-14.97	-1269.67	-2202.16	-1.76
0.9 Dead+1.0 Wind 60 deg - No Ice	31.29	25.97	-14.97	-1258.61	-2183.02	-1.76
1.2 Dead+1.0 Wind 90 deg - No Ice	41.72	29.99	-0.00	0.27	-2542.93	-2.03
0.9 Dead+1.0 Wind 90 deg - No Ice	31.29	29.99	-0.00	0.21	-2520.81	-2.03
1.2 Dead+1.0 Wind 120 deg - No Ice	41.72	25.97	14.97	1270.21	-2202.15	-1.76
0.9 Dead+1.0 Wind 120 deg - No Ice	31.29	25.97	14.97	1259.01	-2183.02	-1.76
1.2 Dead+1.0 Wind 150 deg - No Ice	41.72	14.99	25.93	2199.86	-1271.14	-1.02
0.9 Dead+1.0 Wind 150 deg - No Ice	31.29	14.99	25.93	2180.52	-1260.16	-1.02
1.2 Dead+1.0 Wind 180 deg - No Ice	41.72	0.00	29.94	2540.13	0.64	-0.00
0.9 Dead+1.0 Wind 180 deg - No Ice	31.29	0.00	29.94	2517.82	0.48	-0.00
1.2 Dead+1.0 Wind 210 deg - No Ice	41.72	-14.99	25.93	2199.86	1272.42	1.02
0.9 Dead+1.0 Wind 210 deg - No Ice	31.29	-14.99	25.93	2180.52	1261.12	1.02
1.2 Dead+1.0 Wind 240 deg - No Ice	41.72	-25.97	14.97	1270.21	2203.43	1.76
0.9 Dead+1.0 Wind 240 deg - No Ice	31.29	-25.97	14.97	1259.01	2183.97	1.76
1.2 Dead+1.0 Wind 270 deg - No Ice	41.72	-29.99	-0.00	0.27	2544.21	2.03
0.9 Dead+1.0 Wind 270 deg - No Ice	31.29	-29.99	-0.00	0.21	2521.76	2.03
1.2 Dead+1.0 Wind 300 deg - No Ice	41.72	-25.97	-14.97	-1269.67	2203.44	1.76
0.9 Dead+1.0 Wind 300 deg - No Ice	31.29	-25.97	-14.97	-1258.60	2183.97	1.76
1.2 Dead+1.0 Wind 330 deg - No Ice	41.72	-14.99	-25.93	-2199.33	1272.43	1.02

Load Combination	Vertical	Shear _x	Shear _z	Overturing Moment, M _x	Overturing Moment, M _z	Torque
	K	K	K	kip-ft	kip-ft	kip-ft
0.9 Dead+1.0 Wind 330 deg - No Ice	31.29	-14.99	-25.93	-2180.12	1261.12	1.02
1.2 Dead+1.0 Ice+1.0Temp	87.89	-0.00	-0.00	0.18	3.29	-0.00
1.2 Dead+1.0 Wind 0 deg+1.0 Ice+1.0Temp	87.89	-0.00	-8.98	-802.37	3.47	0.00
1.2 Dead+1.0 Wind 30 deg+1.0 Ice+1.0Temp	87.89	4.49	-7.78	-694.86	-398.07	-0.22
1.2 Dead+1.0 Wind 60 deg+1.0 Ice+1.0Temp	87.89	7.78	-4.49	-401.14	-692.01	-0.38
1.2 Dead+1.0 Wind 90 deg+1.0 Ice+1.0Temp	87.89	8.99	-0.00	0.09	-799.60	-0.44
1.2 Dead+1.0 Wind 120 deg+1.0 Ice+1.0Temp	87.89	7.78	4.49	401.32	-692.01	-0.38
1.2 Dead+1.0 Wind 150 deg+1.0 Ice+1.0Temp	87.89	4.49	7.78	695.03	-398.06	-0.22
1.2 Dead+1.0 Wind 180 deg+1.0 Ice+1.0Temp	87.89	-0.00	8.98	802.54	3.47	-0.00
1.2 Dead+1.0 Wind 210 deg+1.0 Ice+1.0Temp	87.89	-4.49	7.78	695.03	405.00	0.22
1.2 Dead+1.0 Wind 240 deg+1.0 Ice+1.0Temp	87.89	-7.78	4.49	401.31	698.94	0.38
1.2 Dead+1.0 Wind 270 deg+1.0 Ice+1.0Temp	87.89	-8.99	-0.00	0.09	806.53	0.44
1.2 Dead+1.0 Wind 300 deg+1.0 Ice+1.0Temp	87.89	-7.78	-4.49	-401.14	698.94	0.38
1.2 Dead+1.0 Wind 330 deg+1.0 Ice+1.0Temp	87.89	-4.49	-7.78	-694.86	405.00	0.22
Dead+Wind 0 deg - Service	34.76	0.00	-7.05	-595.31	0.53	0.00
Dead+Wind 30 deg - Service	34.76	3.53	-6.11	-515.52	-297.67	-0.24
Dead+Wind 60 deg - Service	34.76	6.12	-3.53	-297.54	-515.96	-0.42
Dead+Wind 90 deg - Service	34.76	7.07	-0.00	0.22	-595.86	-0.48
Dead+Wind 120 deg - Service	34.76	6.12	3.53	297.98	-515.96	-0.42
Dead+Wind 150 deg - Service	34.76	3.53	6.11	515.96	-297.67	-0.24
Dead+Wind 180 deg - Service	34.76	0.00	7.05	595.74	0.53	-0.00
Dead+Wind 210 deg - Service	34.76	-3.53	6.11	515.96	298.73	0.24
Dead+Wind 240 deg - Service	34.76	-6.12	3.53	297.98	517.02	0.42
Dead+Wind 270 deg - Service	34.76	-7.07	-0.00	0.22	596.92	0.48
Dead+Wind 300 deg - Service	34.76	-6.12	-3.53	-297.54	517.02	0.42
Dead+Wind 330 deg - Service	34.76	-3.53	-6.11	-515.52	298.73	0.24

Solution Summary

Load Comb.	Sum of Applied Forces			Sum of Reactions			% Error
	PX K	PY K	PZ K	PX K	PY K	PZ K	
1	0.00	-34.76	0.00	0.00	34.76	0.00	0.000%
2	0.00	-41.72	-29.94	0.00	41.72	29.94	0.000%
3	0.00	-31.29	-29.94	0.00	31.29	29.94	0.000%
4	14.99	-41.72	-25.93	-14.99	41.72	25.93	0.000%
5	14.99	-31.29	-25.93	-14.99	31.29	25.93	0.000%
6	25.97	-41.72	-14.97	-25.97	41.72	14.97	0.000%
7	25.97	-31.29	-14.97	-25.97	31.29	14.97	0.000%
8	29.99	-41.72	0.00	-29.99	41.72	0.00	0.000%
9	29.99	-31.29	0.00	-29.99	31.29	0.00	0.000%
10	25.97	-41.72	14.97	-25.97	41.72	-14.97	0.000%
11	25.97	-31.29	14.97	-25.97	31.29	-14.97	0.000%
12	14.99	-41.72	25.93	-14.99	41.72	-25.93	0.000%
13	14.99	-31.29	25.93	-14.99	31.29	-25.93	0.000%

Load Comb.	Sum of Applied Forces			Sum of Reactions			% Error
	PX K	PY K	PZ K	PX K	PY K	PZ K	
14	0.00	-41.72	29.94	0.00	41.72	-29.94	0.000%
15	0.00	-31.29	29.94	0.00	31.29	-29.94	0.000%
16	-14.99	-41.72	25.93	14.99	41.72	-25.93	0.000%
17	-14.99	-31.29	25.93	14.99	31.29	-25.93	0.000%
18	-25.97	-41.72	14.97	25.97	41.72	-14.97	0.000%
19	-25.97	-31.29	14.97	25.97	31.29	-14.97	0.000%
20	-29.99	-41.72	0.00	29.99	41.72	0.00	0.000%
21	-29.99	-31.29	0.00	29.99	31.29	0.00	0.000%
22	-25.97	-41.72	-14.97	25.97	41.72	14.97	0.000%
23	-25.97	-31.29	-14.97	25.97	31.29	14.97	0.000%
24	-14.99	-41.72	-25.93	14.99	41.72	25.93	0.000%
25	-14.99	-31.29	-25.93	14.99	31.29	25.93	0.000%
26	0.00	-87.89	0.00	0.00	87.89	0.00	0.000%
27	0.00	-87.89	-8.98	0.00	87.89	8.98	0.000%
28	4.49	-87.89	-7.78	-4.49	87.89	7.78	0.000%
29	7.78	-87.89	-4.49	-7.78	87.89	4.49	0.000%
30	8.99	-87.89	0.00	-8.99	87.89	0.00	0.000%
31	7.78	-87.89	4.49	-7.78	87.89	-4.49	0.000%
32	4.49	-87.89	7.78	-4.49	87.89	-7.78	0.000%
33	0.00	-87.89	8.98	0.00	87.89	-8.98	0.000%
34	-4.49	-87.89	7.78	4.49	87.89	-7.78	0.000%
35	-7.78	-87.89	4.49	7.78	87.89	-4.49	0.000%
36	-8.99	-87.89	0.00	8.99	87.89	0.00	0.000%
37	-7.78	-87.89	-4.49	7.78	87.89	4.49	0.000%
38	-4.49	-87.89	-7.78	4.49	87.89	7.78	0.000%
39	0.00	-34.76	-7.05	0.00	34.76	7.05	0.000%
40	3.53	-34.76	-6.11	-3.53	34.76	6.11	0.000%
41	6.12	-34.76	-3.53	-6.12	34.76	3.53	0.000%
42	7.07	-34.76	0.00	-7.07	34.76	0.00	0.000%
43	6.12	-34.76	3.53	-6.12	34.76	-3.53	0.000%
44	3.53	-34.76	6.11	-3.53	34.76	-6.11	0.000%
45	0.00	-34.76	7.05	0.00	34.76	-7.05	0.000%
46	-3.53	-34.76	6.11	3.53	34.76	-6.11	0.000%
47	-6.12	-34.76	3.53	6.12	34.76	-3.53	0.000%
48	-7.07	-34.76	0.00	7.07	34.76	0.00	0.000%
49	-6.12	-34.76	-3.53	6.12	34.76	3.53	0.000%
50	-3.53	-34.76	-6.11	3.53	34.76	6.11	0.000%

Non-Linear Convergence Results

Load Combination	Converged?	Number of Cycles	Displacement Tolerance	Force Tolerance
1	Yes	4	0.00000001	0.00000001
2	Yes	4	0.00000001	0.00009474
3	Yes	4	0.00000001	0.00003832
4	Yes	5	0.00000001	0.00043419
5	Yes	5	0.00000001	0.00019415
6	Yes	5	0.00000001	0.00046854
7	Yes	5	0.00000001	0.00021083
8	Yes	5	0.00000001	0.00004574
9	Yes	4	0.00000001	0.00072252
10	Yes	5	0.00000001	0.00042588
11	Yes	5	0.00000001	0.00019017
12	Yes	5	0.00000001	0.00045816
13	Yes	5	0.00000001	0.00020587
14	Yes	4	0.00000001	0.00009473
15	Yes	4	0.00000001	0.00003832
16	Yes	5	0.00000001	0.00045859
17	Yes	5	0.00000001	0.00020600
18	Yes	5	0.00000001	0.00042620
19	Yes	5	0.00000001	0.00019028
20	Yes	5	0.00000001	0.00004575
21	Yes	4	0.00000001	0.00072273
22	Yes	5	0.00000001	0.00046892
23	Yes	5	0.00000001	0.00021095

24	Yes	5	0.0000001	0.00043465
25	Yes	5	0.0000001	0.00019429
26	Yes	4	0.0000001	0.00001429
27	Yes	5	0.0000001	0.00028149
28	Yes	5	0.0000001	0.00041047
29	Yes	5	0.0000001	0.00041946
30	Yes	5	0.0000001	0.00028099
31	Yes	5	0.0000001	0.00040343
32	Yes	5	0.0000001	0.00041039
33	Yes	5	0.0000001	0.00027878
34	Yes	5	0.0000001	0.00041491
35	Yes	5	0.0000001	0.00040704
36	Yes	5	0.0000001	0.00028329
37	Yes	5	0.0000001	0.00042339
38	Yes	5	0.0000001	0.00041511
39	Yes	4	0.0000001	0.00001914
40	Yes	4	0.0000001	0.00017634
41	Yes	4	0.0000001	0.00022588
42	Yes	4	0.0000001	0.00007478
43	Yes	4	0.0000001	0.00016992
44	Yes	4	0.0000001	0.00020837
45	Yes	4	0.0000001	0.00001912
46	Yes	4	0.0000001	0.00020906
47	Yes	4	0.0000001	0.00017035
48	Yes	4	0.0000001	0.00007491
49	Yes	4	0.0000001	0.00022658
50	Yes	4	0.0000001	0.00017716

Maximum Tower Deflections - Service Wind

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
L1	109 - 95	12.567	48	0.9666	0.0028
L2	95 - 48.08	9.793	48	0.9120	0.0027
L3	53 - 0	3.146	48	0.5459	0.0008

Critical Deflections and Radius of Curvature - Service Wind

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
111.00	Lighting Rod 3/4" x 4'	48	12.567	0.9666	0.0028	31687
109.00	800 10121 w/ Mount Pipe	48	12.567	0.9666	0.0028	31687
101.00	MX08FRO665-21 w/ Mount Pipe	48	10.969	0.9387	0.0028	19804
92.00	(2) LPA-80080-4CF-EDIN-0 w/ Mount Pipe	48	9.218	0.8955	0.0026	10092
80.00	(4) DB844H90-XY w/ Mount Pipe	48	7.037	0.8094	0.0022	7008
74.00	800MHZ 2X50W RRH W/FILTER	48	6.035	0.7567	0.0019	6081
69.00	APXVTM14-C-120 w/ Mount Pipe	48	5.253	0.7094	0.0016	5476
62.00	APX18-206516L	48	4.251	0.6393	0.0013	4806

Maximum Tower Deflections - Design Wind

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
L1	109 - 95	53.589	20	4.1223	0.0118
L2	95 - 48.08	41.764	20	3.8900	0.0114

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
L3	53 - 0	13.417	20	2.3290	0.0036

Critical Deflections and Radius of Curvature - Design Wind

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
111.00	Lighting Rod 3/4" x 4'	20	53.589	4.1223	0.0118	7550
109.00	800 10121 w/ Mount Pipe	20	53.589	4.1223	0.0118	7550
101.00	MX08FRO665-21 w/ Mount Pipe	20	46.776	4.0036	0.0117	4718
92.00	(2) LPA-80080-4CF-EDIN-0 w/ Mount Pipe	20	39.313	3.8197	0.0111	2399
80.00	(4) DB844H90-XY w/ Mount Pipe	20	30.015	3.4531	0.0092	1658
74.00	800MHZ 2X50W RRH W/FILTER	20	25.738	3.2288	0.0080	1436
69.00	APXVTM14-C-120 w/ Mount Pipe	20	22.404	3.0267	0.0069	1291
62.00	APX18-206516L	20	18.132	2.7276	0.0054	1131

Compression Checks

Pole Design Data

Section No.	Elevation ft	Size	L ft	L _u ft	KI/r	A in ²	P _u K	φP _n K	Ratio $\frac{P_u}{\phi P_n}$
L1	109 - 95 (1)	TP26.715x23.476x0.1875	14.00	0.00	0.0	15.787	-8.02	923.55	0.009
L2	95 - 48.08 (2)	TP37.573x26.715x0.3125	46.92	0.00	0.0	35.828	-26.36	2095.96	0.013
L3	48.08 - 0 (3)	TP48.075x35.8094x0.375	53.00	0.00	0.0	56.774	-41.69	3321.33	0.013

Pole Bending Design Data

Section No.	Elevation ft	Size	M _{ux} kip-ft	φM _{rx} kip-ft	Ratio $\frac{M_{ux}}{\phi M_{rx}}$	M _{uy} kip-ft	φM _{ry} kip-ft	Ratio $\frac{M_{uy}}{\phi M_{ry}}$
L1	109 - 95 (1)	TP26.715x23.476x0.1875	146.03	565.78	0.258	0.00	565.78	0.000
L2	95 - 48.08 (2)	TP37.573x26.715x0.3125	1043.33	1873.95	0.557	0.00	1873.95	0.000
L3	48.08 - 0 (3)	TP48.075x35.8094x0.375	2544.21	3803.96	0.669	0.00	3803.96	0.000

Pole Shear Design Data

Section No.	Elevation ft	Size	Actual V _u K	φV _n K	Ratio $\frac{V_u}{\phi V_n}$	Actual T _u kip-ft	φT _n kip-ft	Ratio $\frac{T_u}{\phi T_n}$
L1	109 - 95 (1)	TP26.715x23.476x0.1875	12.07	277.07	0.044	0.00	643.66	0.000
L2	95 - 48.08 (2)	TP37.573x26.715x0.3125	26.38	628.79	0.042	2.04	1989.10	0.001
L3	48.08 - 0 (3)	TP48.075x35.8094x0.375	30.03	996.40	0.030	2.03	4162.29	0.000


Pole Interaction Design Data

Section No.	Elevation ft	Ratio	Ratio	Ratio	Ratio	Ratio	Comb. Stress Ratio	Allow. Stress Ratio	Criteria
		$\frac{P_u}{\phi P_n}$	$\frac{M_{ux}}{\phi M_{nx}}$	$\frac{M_{uy}}{\phi M_{ny}}$	$\frac{V_u}{\phi V_n}$	$\frac{T_u}{\phi T_n}$			
L1	109 - 95 (1)	0.009	0.258	0.000	0.044	0.000	0.269	1.050	4.8.2
L2	95 - 48.08 (2)	0.013	0.557	0.000	0.042	0.001	0.571	1.050	4.8.2
L3	48.08 - 0 (3)	0.013	0.669	0.000	0.030	0.000	0.682	1.050	4.8.2

Section Capacity Table

Section No.	Elevation ft	Component Type	Size	Critical Element	P K	ϕP_{allow} K	% Capacity	Pass Fail	
L1	109 - 95	Pole	TP26.715x23.476x0.1875	1	-8.02	969.73	25.6	Pass	
L2	95 - 48.08	Pole	TP37.573x26.715x0.3125	2	-26.36	2200.76	54.4	Pass	
L3	48.08 - 0	Pole	TP48.075x35.8094x0.375	3	-41.69	3487.40	65.0	Pass	
							Summary		
							Pole (L3)	65.0	Pass
							RATING =	65.0	Pass

APPENDIX B
BASE LEVEL DRAWING



APPENDIX C
ADDITIONAL CALCULATIONS

Monopole Flange Plate Connection

Elevation = 95 ft.




BU #	801486
Site Name	SUFFIELD 2 CAC 8014
Order #	556646 Rev. 0
TIA-222 Revision	H


Applied Loads	
Moment (kip-ft)	146.03
Axial Force (kips)	8.02
Shear Force (kips)	12.07

*TIA-222-H Section 15.5 Applied

Top Plate - External



Bottom Plate - External



Connection Properties

Bolt Data

(20) 1" \emptyset bolts (A325 N; Fy=92 ksi, Fu=120 ksi) on 33" BC

Top Plate Data

36" OD x 2.25" Plate (A633 Gr. E; Fy=60 ksi, Fu=70 ksi)

Top Stiffener Data

N/A

Top Pole Data

26.715" x 0.1875" 18-sided pole (A572-65; Fy=65 ksi, Fu=80 ksi)

Bottom Plate Data

36" OD x 2.25" Plate (A633 Gr. E; Fy=60 ksi, Fu=70 ksi)

Bottom Stiffener Data

N/A

Bottom Pole Data

26.715" x 0.3125" 18-sided pole (A572-65; Fy=65 ksi, Fu=80 ksi)

Analysis Results

Bolt Capacity

Max Load (kips)	10.22
Allowable (kips)	54.53
Stress Rating:	17.8% Pass

Top Plate Capacity

Max Stress (ksi):	3.69	(Flexural)
Allowable Stress (ksi):	54.00	
Stress Rating:	6.5%	Pass
Tension Side Stress Rating:	4.4%	Pass

Bottom Plate Capacity

Max Stress (ksi):	3.69	(Flexural)
Allowable Stress (ksi):	54.00	
Stress Rating:	6.5%	Pass
Tension Side Stress Rating:	4.4%	Pass

Monopole Base Plate Connection




Site Info	
BU #	801486
Site Name	SUFFIELD 2 CAC 80144
Order #	556646 Rev. 0

Analysis Considerations	
TIA-222 Revision	H
Grout Considered:	No
l_{ar} (in)	0.75

Applied Loads	
Moment (kip-ft)	2544.21
Axial Force (kips)	41.69
Shear Force (kips)	30.03

*TIA-222-H Section 15.5 Applied



Connection Properties	Analysis Results
-----------------------	------------------

Anchor Rod Data
(16) 2-1/4" ϕ bolts (A615-75 N; $F_y=75$ ksi, $F_u=100$ ksi) on 55" BC
Base Plate Data
61" OD x 2.75" Plate (A633 Gr. E; $F_y=60$ ksi, $F_u=70$ ksi)
Stiffener Data
N/A
Pole Data
48.075" x 0.375" 18-sided pole (A572-65; $F_y=65$ ksi, $F_u=80$ ksi)

Anchor Rod Summary		<i>(units of kips, kip-in)</i>	
$Pu_t = 136.07$	$\phi Pn_t = 243.75$	Stress Rating	
$Vu = 1.88$	$\phi Vn = 149.1$		53.2%
$Mu = n/a$	$\phi Mn = n/a$		Pass
Base Plate Summary			
Max Stress (ksi):	16.77		(Flexural)
Allowable Stress (ksi):	54		
Stress Rating:	29.6%		Pass

Pier and Pad Foundation



BU # : 801486
Site Name: CT SUFFIELD 2 C.
App. Number: 556646 Rev. 0

TIA-222 Revision: H
Tower Type: Monopole

Top & Bot. Pad Rein. Different?:
Block Foundation?:
Rectangular Pad?:

Superstructure Analysis Reactions		
Compression, P_{comp} :	41.72	kips
Base Shear, V_{u_comp} :	29.99	kips
Moment, M_u :	2544.21	ft-kips
Tower Height, H :	109	ft
BP Dist. Above Fdn, bp_{dist} :	3	in

Foundation Analysis Checks				
	Capacity	Demand	Rating*	Check
<i>Lateral (Sliding) (kips)</i>	733.50	29.99	3.9%	Pass
<i>Bearing Pressure (ksf)</i>	6.00	1.73	27.5%	Pass
<i>Overtuning (kip*ft)</i>	6302.20	2761.64	43.8%	Pass
<i>Pier Flexure (Comp.) (kip*ft)</i>	4653.47	2679.17	54.8%	Pass
<i>Pier Compression (kip)</i>	15840.27	68.60	0.4%	Pass
<i>Pad Flexure (kip*ft)</i>	2373.87	965.72	38.7%	Pass
<i>Pad Shear - 1-way (kips)</i>	635.91	147.53	22.1%	Pass
<i>Pad Shear - 2-way (Comp) (ksi)</i>	0.164	0.043	25.1%	Pass
<i>Flexural 2-way (Comp) (kip*ft)</i>	2507.27	1607.50	61.1%	Pass

Pier Properties		
Pier Shape:	Circular	
Pier Diameter, $dpier$:	6.5	ft
Ext. Above Grade, E :	0.5	ft
Pier Rebar Size, Sc :	9	
Pier Rebar Quantity, mc :	32	
Pier Tie/Spiral Size, St :	5	
Pier Tie/Spiral Quantity, mt :	9	
Pier Reinforcement Type:	Tie	
Pier Clear Cover, cc_{pier} :	3	in

*Rating per TIA-222-H Section 15.5

Soil Rating*:	43.8%
Structural Rating*:	61.1%

Pad Properties		
Depth, D :	6.5	ft
Pad Width, W_1 :	26	ft
Pad Thickness, T :	2.5	ft
Pad Rebar Size (Bottom dir. 2), Sp_2 :	9	
Pad Rebar Quantity (Bottom dir. 2), mp_2 :	22	
Pad Clear Cover, cc_{pad} :	3.5	in

Material Properties		
Rebar Grade, F_y :	60	ksi
Concrete Compressive Strength, F'_c :	3	ksi
Dry Concrete Density, δ_c :	150	pcf

Soil Properties		
Total Soil Unit Weight, γ :	115	pcf
Ultimate Gross Bearing, Q_{ult} :	8.000	ksf
Cohesion, C_u :	1.150	ksf
Friction Angle, ϕ :	0	degrees
SPT Blow Count, N_{blows} :		
Base Friction, μ :		
Neglected Depth, N :	3.33	ft
Foundation Bearing on Rock?	No	
Groundwater Depth, gw :	N/A	ft


<-- Toggle between Gross and Net

ASCE 7 Hazards Report

Address:
No Address at This
Location

Standard: ASCE/SEI 7-10
Risk Category: II
Soil Class: D - Stiff Soil

Elevation: 132.2 ft (NAVD 88)
Latitude: 41.980472
Longitude: -72.657278



Wind

Results:

Wind Speed:	120 Vmph
10-year MRI	76 Vmph
25-year MRI	86 Vmph
50-year MRI	91 Vmph
100-year MRI	98 Vmph

Data Source: ASCE/SEI 7-10, Fig. 26.5-1A and Figs. CC-1–CC-4, and Section 26.5.2, incorporating errata of March 12, 2014

Value provided is 3-second gust wind speeds at 33 ft above ground for Exposure C Category, based on linear interpolation between contours. Wind speeds are interpolated in accordance with the 7-10 Standard. Wind speeds correspond to approximately a 7% probability of exceedance in 50 years (annual exceedance probability = 0.00143, MRI = 700 years).



Site is in a hurricane-prone region as defined in ASCE/SEI 7-10 Section 26.2. Glazed openings need not be protected against wind-borne debris.

Site Soil Class: D - Stiff Soil

Results:

S_S :	0.176	S_{DS} :	0.187
S_1 :	0.065	S_{D1} :	0.103
F_a :	1.6	T_L :	6
F_v :	2.4	PGA :	0.086
S_{MS} :	0.281	PGA _M :	0.138
S_{M1} :	0.155	F _{PGA} :	1.6
		I_e :	1

Seismic Design Category B



Data Accessed:

Thu Apr 29 2021

Date Source:

USGS Seismic Design Maps based on ASCE/SEI 7-10, incorporating Supplement 1 and errata of March 31, 2013, and ASCE/SEI 7-10 Table 1.5-2. Additional data for site-specific ground motion procedures in accordance with ASCE/SEI 7-10 Ch. 21 are available from USGS.

Ice

Results:

Ice Thickness: 1.00 in.

Concurrent Temperature: 5 F

Gust Speed: 50 mph

Data Source: Standard ASCE/SEI 7-10, Figs. 10-2 through 10-8

Date Accessed: Thu Apr 29 2021

Ice thicknesses on structures in exposed locations at elevations higher than the surrounding terrain and in valleys and gorges may exceed the mapped values.

Values provided are equivalent radial ice thicknesses due to freezing rain with concurrent 3-second gust speeds, for a 50-year mean recurrence interval, and temperatures concurrent with ice thicknesses due to freezing rain. Thicknesses for ice accretions caused by other sources shall be obtained from local meteorological studies. Ice thicknesses in exposed locations at elevations higher than the surrounding terrain and in valleys and gorges may exceed the mapped values.

The ASCE 7 Hazard Tool is provided for your convenience, for informational purposes only, and is provided “as is” and without warranties of any kind. The location data included herein has been obtained from information developed, produced, and maintained by third party providers; or has been extrapolated from maps incorporated in the ASCE 7 standard. While ASCE has made every effort to use data obtained from reliable sources or methodologies, ASCE does not make any representations or warranties as to the accuracy, completeness, reliability, currency, or quality of any data provided herein. Any third-party links provided by this Tool should not be construed as an endorsement, affiliation, relationship, or sponsorship of such third-party content by or from ASCE.

ASCE does not intend, nor should anyone interpret, the results provided by this Tool to replace the sound judgment of a competent professional, having knowledge and experience in the appropriate field(s) of practice, nor to substitute for the standard of care required of such professionals in interpreting and applying the contents of this Tool or the ASCE 7 standard.

In using this Tool, you expressly assume all risks associated with your use. Under no circumstances shall ASCE or its officers, directors, employees, members, affiliates, or agents be liable to you or any other person for any direct, indirect, special, incidental, or consequential damages arising from or related to your use of, or reliance on, the Tool or any information obtained therein. To the fullest extent permitted by law, you agree to release and hold harmless ASCE from any and all liability of any nature arising out of or resulting from any use of data provided by the ASCE 7 Hazard Tool.

Exhibit E

Mount Analysis

Date: **August 3, 2021**

Darcy Tarr
Crown Castle
3530 Toringdon Way, Suite 300
Charlotte, NC 28277
(704) 405-6589



Trylon
1825 W. Walnut Hill Lane,
Suite 302
Irving, TX 75038
214-930-1730

Subject: **Mount Replacement Analysis Report**

Carrier Designation: **DISH Network Equipment Change-Out**
Carrier Site Number: BOBDL00036A
Carrier Site Name: CT-CCI-T-801486

Crown Castle Designation: **Crown Castle BU Number:** 801486
Crown Castle Site Name: CT Suffield 2 CAC 801486
Crown Castle JDE Job Number: 650034
Crown Castle Order Number: 556646 Rev. 0

Engineering Firm Designation: **Trylon Report Designation:** 189200

Site Data: **44 FFyler Place, Suffield, Hartford County, CT, 06078**
Latitude 41°58'49.70" Longitude -72°39'26.20"

Structure Information: **Tower Height & Type:** **109.0 ft Monopole**
Mount Elevation: **101.0 ft**
Mount Type: **8.0 ft Platform**

Dear Darcy Tarr,

Trylon is pleased to submit this "**Mount Replacement Analysis Report**" to determine the structural integrity of DISH Network's antenna mounting system with the proposed appurtenance and equipment addition on the abovementioned supporting tower structure. Analysis of the existing supporting tower structure is to be completed by others and therefore is not part of this analysis. Analysis of the antenna mounting system as a tie-off point for fall protection or rigging is not part of this document.

The purpose of the analysis is to determine acceptability of the mount stress level. Based on our analysis we have determined the mount stress level to be:

Platform **Sufficient**
***Sufficient upon completion of the changes listed in the 'Recommendations' section of this report.**

This analysis utilizes an ultimate 3-second gust wind speed of 120 mph as required by the 2018 Connecticut State Building Code. Applicable Standard references and design criteria are listed in Section 2 - Analysis Criteria.

Mount analysis prepared by: Trevor Leahy, E.I.T.

Respectfully Submitted by:
Jinshan Wang, P.E.




TABLE OF CONTENTS

1) INTRODUCTION

2) ANALYSIS CRITERIA

Table 1 - Proposed Equipment Configuration

3) ANALYSIS PROCEDURE

Table 2 - Documents Provided

3.1) Analysis Method

3.2) Assumptions

4) ANALYSIS RESULTS

Table 3 - Mount Component Stresses vs. Capacity

4.1) Recommendations

5) APPENDIX A

Wire Frame and Rendered Models

6) APPENDIX B

Software Input Calculations

7) APPENDIX C

Software Analysis Output

8) APPENDIX D

Additional Calculations

9) APPENDIX E

Supplemental Drawings

1) INTRODUCTION

This is a proposed 3 sector 8.0 ft Platform Mount, designed by Commscope.

2) ANALYSIS CRITERIA

Building Code:	2015 IBC / 2018 CTSCB
TIA-222 Revision:	TIA-222-H
Risk Category:	II
Ultimate Wind Speed:	120 mph
Exposure Category:	C
Topographic Factor at Base:	1.0
Topographic Factor at Mount:	1.0
Ice Thickness:	2.00 in
Wind Speed with Ice:	50 mph
Seismic S_s:	0.176
Seismic S₁:	0.065
Live Loading Wind Speed:	30 mph
Man Live Load at Mid/End-Points:	250 lb
Man Live Load at Mount Pipes:	500 lb

Table 1 - Proposed Equipment Configuration

Mount Centerline (ft)	Antenna Centerline (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Mount / Modification Details
101.0	101.0	3	JMA Wireless	MX08FRO665-21	8.0 ft Platform [Commscope MC- PK8-DSH]
		3	Fujitsu	TA08025-B604	
		3	Fujitsu	TA08025-B605	
		1	Raycap	RDIDC-9181-PF-48	

3) ANALYSIS PROCEDURE

Table 2 - Documents Provided

Document	Remarks	Reference	Source
Crown Application	DISH Network Application	556646 Rev. 0	CCI Sites
Mount Manufacturer Drawings	Commscope	MC-PK8-DSH	Trylon
Tower Analysis	Crown Castle	9785171	CCI Sites

3.1) Analysis Method

RISA-3D (Version 17.0.4), a commercially available analysis software package, was used to create a three-dimensional model of the antenna mounting system and calculate member stresses for various loading cases.

A tool internally developed, using Microsoft Excel, by Trylon was used to calculate wind loading on all appurtenances, dishes, and mount members for various load cases. Selected output from the analysis is included in Appendix B.

This analysis was performed in accordance with Crown Castle's ENG-SOW-10208 *Tower Mount Analysis* (Revision B).

3.2) Assumptions

- 1) The antenna mounting system was properly fabricated, installed and maintained in good condition in accordance with its original design and manufacturer's specifications.
- 2) The configuration of antennas, mounts, and other appurtenances are as specified in Table 1 and the referenced drawings.
- 3) All member connections are assumed to have been designed to meet or exceed the load carrying capacity of the connected member unless otherwise specified in this report.
- 4) The analysis will be required to be revised if the existing conditions in the field differ from those shown in the above-referenced documents or assumed in this analysis. No allowance was made for any damaged, missing, or rusted members.
- 5) Prior structural modifications to the tower mounting system are assumed to be installed as shown per available data.
- 6) Steel grades have been assumed as follows, unless noted otherwise:

Channel, Solid Round, Angle, Plate	ASTM A36 (GR 36)
HSS (Rectangular)	ASTM A500 (GR B-46)
Pipe	ASTM A53 (GR 35)
Connection Bolts	ASTM A325

This analysis may be affected if any assumptions are not valid or have been made in error. Tylon should be notified to determine the effect on the structural integrity of the antenna mounting system.

4) ANALYSIS RESULTS

Table 3 - Mount Component Stresses vs. Capacity (Platform, All Sectors)

Notes	Component	Critical Member	Centerline (ft)	% Capacity	Pass / Fail
1, 2	Mount Pipe(s)	MP4	101.0	41.4	Pass
	Horizontal(s)	H1		11.5	Pass
	Standoff(s)	M2		57.9	Pass
	Bracing(s)	M11		47.7	Pass
	Handrail(s)	M19		15.7	Pass
	Plate(s)	M10		28.0	Pass
	Mount Connection(s)	-		29.7	Pass

Structure Rating (max from all components) =	57.9%
---	--------------

Notes:

- 1) See additional documentation in "Appendix C - Software Analysis Output" for calculations supporting the % capacity consumed.
- 2) Rating per TIA-222-H, Section 15.5



4.1) Recommendations

The mount has sufficient capacity to carry the proposed loading configuration. In order for the results of the analysis to be considered valid, the proposed mount listed below must be installed.

1. Commscope MC-PK8-DSH.

No structural modifications are required at this time, provided that the above-listed changes are implemented.

APPENDIX A
WIRE FRAME AND RENDERED MODELS



Trylon

TL



189200

CT Suffield 2 CAC 801486 (BU 801486 Order 556646)

SK - 1

Aug 3, 2021 at 10:36 AM

MC-PK8-C_loaded.r3d



Trylon	CT Suffield 2 CAC 801486 (BU 801486 Order 556646)	SK - 2
TL		Aug 3, 2021 at 10:36 AM
189200		MC-PK8-C_loaded.r3d


APPENDIX B
SOFTWARE INPUT CALCULATIONS

ASCE 7 Hazards Report

Address:
No Address at This
Location

Standard: ASCE/SEI 7-10
Risk Category: II
Soil Class: D - Stiff Soil

Elevation: 132.2 ft (NAVD 88)
Latitude: 41.980472
Longitude: -72.657278



Ice

Results:

Ice Thickness: 1.00 in.
Concurrent Temperature: 5 F
Gust Speed: 50 mph

Data Source: Standard ASCE/SEI 7-10, Figs. 10-2 through 10-8

Date Accessed: Tue Aug 03 2021

Ice thicknesses on structures in exposed locations at elevations higher than the surrounding terrain and in valleys and gorges may exceed the mapped values.

Values provided are equivalent radial ice thicknesses due to freezing rain with concurrent 3-second gust speeds, for a 50-year mean recurrence interval, and temperatures concurrent with ice thicknesses due to freezing rain. Thicknesses for ice accretions caused by other sources shall be obtained from local meteorological studies. Ice thicknesses in exposed locations at elevations higher than the surrounding terrain and in valleys and gorges may exceed the mapped values.



Trylon

1825 W. Walnut Hill Lane Suite 120
Irving, TX 75038

TIA LOAD CALCULATOR 2.0

PROJECT DATA	
Job Code:	189200
Carrier Site ID:	BOBDL00036A
Carrier Site Name:	CT-CCI-T-801486

CODES AND STANDARDS	
Building Code:	2015 IBC
Local Building Code:	2018 CTSBC
Design Standard:	TIA-222-H

STRUCTURE DETAILS		
Mount Type:	Platform	--
Mount Elevation:	101.0	ft.
Number of Sectors:	3	--
Structure Type:	Monopole	--
Structure Height:	109.0	ft.

ANALYSIS CRITERIA		
Structure Risk Category:	II	--
Exposure Category:	C	--
Site Class:	D - Stiff Soil	--
Ground Elevation:	132.2	ft.

TOPOGRAPHIC DATA		
Topographic Category:	1.00	--
Topographic Feature:	N/A	--
Crest Point Elevation:	0.00	ft.
Base Point Elevation:	0.00	ft.
Crest to Mid-Height (L/2):	0.00	ft.
Distance from Crest (x):	0.00	ft.
Base Topo Factor (K_{zt}):	1.00	--
Mount Topo Factor (K_{zt}):	1.00	--

WIND PARAMETERS		
Design Wind Speed:	120	mph
Wind Escalation Factor (K_s):	1.00	--
Velocity Coefficient (K_z):	1.27	--
Directionality Factor (K_d):	0.95	--
Gust Effect Factor (G_h):	1.00	--
Shielding Factor (K_a):	0.90	--
Velocity Pressure (q_z):	44.20	psf

ICE PARAMETERS		
Design Ice Wind Speed:	50	mph
Design Ice Thickness (t_i):	2.00	in
Importance Factor (I_i):	1.00	--
Ice Velocity Pressure (q_{zi}):	44.20	psf
Mount Ice Thickness (t_{iz}):	2.24	in

WIND STRUCTURE CALCULATIONS		
Flat Member Pressure:	79.57	psf
Round Member Pressure:	47.74	psf
Ice Wind Pressure:	7.31	psf

SEISMIC PARAMETERS		
Importance Factor (I_e):	1.00	--
Short Period Accel. (S_s):	0.18	g
1 Second Accel. (S_1):	0.07	g
Short Period Des. (S_{DS}):	0.19	g
1 Second Des. (S_{D1}):	0.10	g
Short Period Coeff. (F_a):	1.60	--
1 Second Coeff. (F_v):	2.40	--
Response Coefficient (C_s):	0.09	--
Amplification Factor (A_S):	1.20	--

LOAD COMBINATIONS [LRFD]

#	Description
1	1.4DL
2	1.2DL + 1WL 0 AZI
3	1.2DL + 1WL 30 AZI
4	1.2DL + 1WL 45 AZI
5	1.2DL + 1WL 60 AZI
6	1.2DL + 1WL 90 AZI
7	1.2DL + 1WL 120 AZI
8	1.2DL + 1WL 135 AZI
9	1.2DL + 1WL 150 AZI
10	1.2DL + 1WL 180 AZI
11	1.2DL + 1WL 210 AZI
12	1.2DL + 1WL 225 AZI
13	1.2DL + 1WL 240 AZI
14	1.2DL + 1WL 270 AZI
15	1.2DL + 1WL 300 AZI
16	1.2DL + 1WL 315 AZI
17	1.2DL + 1WL 330 AZI
18	0.9DL + 1WL 0 AZI
19	0.9DL + 1WL 30 AZI
20	0.9DL + 1WL 45 AZI
21	0.9DL + 1WL 60 AZI
22	0.9DL + 1WL 90 AZI
23	0.9DL + 1WL 120 AZI
24	0.9DL + 1WL 135 AZI
25	0.9DL + 1WL 150 AZI
26	0.9DL + 1WL 180 AZI
27	0.9DL + 1WL 210 AZI
28	0.9DL + 1WL 225 AZI
29	0.9DL + 1WL 240 AZI
30	0.9DL + 1WL 270 AZI
31	0.9DL + 1WL 300 AZI
32	0.9DL + 1WL 315 AZI
33	0.9DL + 1WL 330 AZI
34	1.2DL + 1DLi + 1WLi 0 AZI
35	1.2DL + 1DLi + 1WLi 30 AZI
36	1.2DL + 1DLi + 1WLi 45 AZI
37	1.2DL + 1DLi + 1WLi 60 AZI
38	1.2DL + 1DLi + 1WLi 90 AZI
39	1.2DL + 1DLi + 1WLi 120 AZI
40	1.2DL + 1DLi + 1WLi 135 AZI
41	1.2DL + 1DLi + 1WLi 150 AZI

#	Description
42	1.2DL + 1DLi + 1WLi 180 AZI
43	1.2DL + 1DLi + 1WLi 210 AZI
44	1.2DL + 1DLi + 1WLi 225 AZI
45	1.2DL + 1DLi + 1WLi 240 AZI
46	1.2DL + 1DLi + 1WLi 270 AZI
47	1.2DL + 1DLi + 1WLi 300 AZI
48	1.2DL + 1DLi + 1WLi 315 AZI
49	1.2DL + 1DLi + 1WLi 330 AZI
50	(1.2+0.2Sds) + 1.0E 0 AZI
51	(1.2+0.2Sds) + 1.0E 30 AZI
52	(1.2+0.2Sds) + 1.0E 45 AZI
53	(1.2+0.2Sds) + 1.0E 60 AZI
54	(1.2+0.2Sds) + 1.0E 90 AZI
55	(1.2+0.2Sds) + 1.0E 120 AZI
56	(1.2+0.2Sds) + 1.0E 135 AZI
57	(1.2+0.2Sds) + 1.0E 150 AZI
58	(1.2+0.2Sds) + 1.0E 180 AZI
59	(1.2+0.2Sds) + 1.0E 210 AZI
60	(1.2+0.2Sds) + 1.0E 225 AZI
61	(1.2+0.2Sds) + 1.0E 240 AZI
62	(1.2+0.2Sds) + 1.0E 270 AZI
63	(1.2+0.2Sds) + 1.0E 300 AZI
64	(1.2+0.2Sds) + 1.0E 315 AZI
65	(1.2+0.2Sds) + 1.0E 330 AZI
66	(0.9-0.2Sds) + 1.0E 0 AZI
67	(0.9-0.2Sds) + 1.0E 30 AZI
68	(0.9-0.2Sds) + 1.0E 45 AZI
69	(0.9-0.2Sds) + 1.0E 60 AZI
70	(0.9-0.2Sds) + 1.0E 90 AZI
71	(0.9-0.2Sds) + 1.0E 120 AZI
72	(0.9-0.2Sds) + 1.0E 135 AZI
73	(0.9-0.2Sds) + 1.0E 150 AZI
74	(0.9-0.2Sds) + 1.0E 180 AZI
75	(0.9-0.2Sds) + 1.0E 210 AZI
76	(0.9-0.2Sds) + 1.0E 225 AZI
77	(0.9-0.2Sds) + 1.0E 240 AZI
78	(0.9-0.2Sds) + 1.0E 270 AZI
79	(0.9-0.2Sds) + 1.0E 300 AZI
80	(0.9-0.2Sds) + 1.0E 315 AZI
81	(0.9-0.2Sds) + 1.0E 330 AZI
82-88	1.2D + 1.5 Lv1

#	Description
89	1.2D + 1.5Lm + 1.0Wm 0 AZI - MP1
90	1.2D + 1.5Lm + 1.0Wm 30 AZI - MP1
91	1.2D + 1.5Lm + 1.0Wm 45 AZI - MP1
92	1.2D + 1.5Lm + 1.0Wm 60 AZI - MP1
93	1.2D + 1.5Lm + 1.0Wm 90 AZI - MP1
94	1.2D + 1.5Lm + 1.0Wm 120 AZI - MP1
95	1.2D + 1.5Lm + 1.0Wm 135 AZI - MP1
96	1.2D + 1.5Lm + 1.0Wm 150 AZI - MP1
97	1.2D + 1.5Lm + 1.0Wm 180 AZI - MP1
98	1.2D + 1.5Lm + 1.0Wm 210 AZI - MP1
99	1.2D + 1.5Lm + 1.0Wm 225 AZI - MP1
100	1.2D + 1.5Lm + 1.0Wm 240 AZI - MP1
101	1.2D + 1.5Lm + 1.0Wm 270 AZI - MP1
102	1.2D + 1.5Lm + 1.0Wm 300 AZI - MP1
103	1.2D + 1.5Lm + 1.0Wm 315 AZI - MP1
104	1.2D + 1.5Lm + 1.0Wm 330 AZI - MP1
105	1.2D + 1.5Lm + 1.0Wm 0 AZI - MP2
106	1.2D + 1.5Lm + 1.0Wm 30 AZI - MP2
107	1.2D + 1.5Lm + 1.0Wm 45 AZI - MP2
108	1.2D + 1.5Lm + 1.0Wm 60 AZI - MP2
109	1.2D + 1.5Lm + 1.0Wm 90 AZI - MP2
110	1.2D + 1.5Lm + 1.0Wm 120 AZI - MP2
111	1.2D + 1.5Lm + 1.0Wm 135 AZI - MP2
112	1.2D + 1.5Lm + 1.0Wm 150 AZI - MP2
113	1.2D + 1.5Lm + 1.0Wm 180 AZI - MP2
114	1.2D + 1.5Lm + 1.0Wm 210 AZI - MP2
115	1.2D + 1.5Lm + 1.0Wm 225 AZI - MP2
116	1.2D + 1.5Lm + 1.0Wm 240 AZI - MP2
117	1.2D + 1.5Lm + 1.0Wm 270 AZI - MP2
118	1.2D + 1.5Lm + 1.0Wm 300 AZI - MP2
119	1.2D + 1.5Lm + 1.0Wm 315 AZI - MP2
120	1.2D + 1.5Lm + 1.0Wm 330 AZI - MP2

#	Description
121	1.2D + 1.5Lm + 1.0Wm 0 AZI - MP3
122	1.2D + 1.5Lm + 1.0Wm 30 AZI - MP3
123	1.2D + 1.5Lm + 1.0Wm 45 AZI - MP3
124	1.2D + 1.5Lm + 1.0Wm 60 AZI - MP3
125	1.2D + 1.5Lm + 1.0Wm 90 AZI - MP3
126	1.2D + 1.5Lm + 1.0Wm 120 AZI - MP3
127	1.2D + 1.5Lm + 1.0Wm 135 AZI - MP3
128	1.2D + 1.5Lm + 1.0Wm 150 AZI - MP3
129	1.2D + 1.5Lm + 1.0Wm 180 AZI - MP3
130	1.2D + 1.5Lm + 1.0Wm 210 AZI - MP3
131	1.2D + 1.5Lm + 1.0Wm 225 AZI - MP3
132	1.2D + 1.5Lm + 1.0Wm 240 AZI - MP3
133	1.2D + 1.5Lm + 1.0Wm 270 AZI - MP3
134	1.2D + 1.5Lm + 1.0Wm 300 AZI - MP3
135	1.2D + 1.5Lm + 1.0Wm 315 AZI - MP3
136	1.2D + 1.5Lm + 1.0Wm 330 AZI - MP3
137	1.2D + 1.5Lm + 1.0Wm 0 AZI - MP4
138	1.2D + 1.5Lm + 1.0Wm 30 AZI - MP4
139	1.2D + 1.5Lm + 1.0Wm 45 AZI - MP4
140	1.2D + 1.5Lm + 1.0Wm 60 AZI - MP4
141	1.2D + 1.5Lm + 1.0Wm 90 AZI - MP4
142	1.2D + 1.5Lm + 1.0Wm 120 AZI - MP4
143	1.2D + 1.5Lm + 1.0Wm 135 AZI - MP4
144	1.2D + 1.5Lm + 1.0Wm 150 AZI - MP4
145	1.2D + 1.5Lm + 1.0Wm 180 AZI - MP4
146	1.2D + 1.5Lm + 1.0Wm 210 AZI - MP4
147	1.2D + 1.5Lm + 1.0Wm 225 AZI - MP4
148	1.2D + 1.5Lm + 1.0Wm 240 AZI - MP4
149	1.2D + 1.5Lm + 1.0Wm 270 AZI - MP4
150	1.2D + 1.5Lm + 1.0Wm 300 AZI - MP4
151	1.2D + 1.5Lm + 1.0Wm 315 AZI - MP4
152	1.2D + 1.5Lm + 1.0Wm 330 AZI - MP4

*This page shows an example of maintenance loads for (4) pipes, the number of mount pipe LCs may vary per site

EQUIPMENT LOADING

<i>Appurtenance Name/Location</i>	<i>Qty.</i>	<i>Elevation [ft]</i>	<i>--</i>	<i>EPA_N (ft²)</i>	<i>EPA_T (ft²)</i>	<i>Weight (lbs)</i>
MX08FRO665-21	3	101	No Ice	12.49	5.87	82.50
MP2/MP5/MP8, 0/140/240	--	--	w/ Ice	14.09	7.33	383.21
TA08025-B604	3	101	No Ice	1.96	0.98	63.90
MP2/MP5/MP8, 0/140/240	--	--	w/ Ice	2.53	1.42	97.12
TA08025-B605	3	101	No Ice	1.96	1.13	75.00
MP2/MP5/MP8, 0/140/240	--	--	w/ Ice	2.53	1.59	103.19
RDIDC-9181-PF-48	1	101	No Ice	2.01	1.17	21.85
MP2, 0	--	--	w/ Ice	2.58	1.65	101.77
			No Ice			
--	--	--	w/ Ice			
			No Ice			
--	--	--	w/ Ice			
			No Ice			
--	--	--	w/ Ice			
			No Ice			
--	--	--	w/ Ice			
			No Ice			
--	--	--	w/ Ice			
			No Ice			
--	--	--	w/ Ice			
			No Ice			
--	--	--	w/ Ice			
			No Ice			
--	--	--	w/ Ice			
			No Ice			
--	--	--	w/ Ice			
			No Ice			
--	--	--	w/ Ice			
			No Ice			
--	--	--	w/ Ice			
			No Ice			
--	--	--	w/ Ice			
			No Ice			
--	--	--	w/ Ice			
			No Ice			
--	--	--	w/ Ice			
			No Ice			
--	--	--	w/ Ice			
			No Ice			
--	--	--	w/ Ice			
			No Ice			
--	--	--	w/ Ice			
			No Ice			
--	--	--	w/ Ice			
			No Ice			
--	--	--	w/ Ice			
			No Ice			
--	--	--	w/ Ice			

EQUIPMENT LOADING [CONT.]

<i>Appurtenance Name/Location</i>	<i>Qty.</i>	<i>Elevation [ft]</i>	<i>--</i>	<i>EPA_N (ft²)</i>	<i>EPA_T (ft²)</i>	<i>Weight (lbs)</i>
			No Ice			
--	--	--	w/ Ice			
			No Ice			
--	--	--	w/ Ice			
			No Ice			
--	--	--	w/ Ice			
			No Ice			
--	--	--	w/ Ice			
			No Ice			
--	--	--	w/ Ice			
			No Ice			
--	--	--	w/ Ice			
			No Ice			
--	--	--	w/ Ice			
			No Ice			
--	--	--	w/ Ice			
			No Ice			
--	--	--	w/ Ice			
			No Ice			
--	--	--	w/ Ice			
			No Ice			
--	--	--	w/ Ice			
			No Ice			
--	--	--	w/ Ice			
			No Ice			
--	--	--	w/ Ice			
			No Ice			
--	--	--	w/ Ice			
			No Ice			
--	--	--	w/ Ice			
			No Ice			
--	--	--	w/ Ice			

EQUIPMENT WIND CALCULATIONS

<i>Appurtenance Name</i>	<i>Qty.</i>	<i>Elevation [ft]</i>	<i>K_{zt}</i>	<i>K_z</i>	<i>K_d</i>	<i>t_d</i>	<i>q_z [psf]</i>	<i>q_{zi} [psf]</i>
MX08FRO665-21	3	101	1.00	1.27	0.95	2.24	44.20	7.67
TA08025-B604	3	101	1.00	1.27	0.95	2.24	44.20	7.67
TA08025-B605	3	101	1.00	1.27	0.95	2.24	44.20	7.67
RDIDC-9181-PF-48	1	101	1.00	1.27	0.95	2.24	44.20	7.67

EQUIPMENT LATERAL WIND FORCE CALCULATIONS

<i>Appurtenance Name</i>	<i>Qty.</i>	<i>--</i>	<i>0° 180°</i>	<i>30° 210°</i>	<i>60° 240°</i>	<i>90° 270°</i>	<i>120° 300°</i>	<i>150° 330°</i>
MX08FRO665-21	3	No Ice	496.85	299.26	430.99	233.40	430.99	299.26
MP2/MP5/MP8, 0/140/240	--	w/ Ice	97.30	62.29	85.63	50.62	85.63	62.29
TA08025-B604	3	No Ice	78.11	48.80	68.34	39.03	68.34	48.80
MP2/MP5/MP8, 0/140/240	--	w/ Ice	17.46	11.74	15.55	9.83	15.55	11.74
TA08025-B605	3	No Ice	78.11	53.23	69.82	44.93	69.82	53.23
MP2/MP5/MP8, 0/140/240	--	w/ Ice	17.46	12.60	15.84	10.98	15.84	12.60
RDIDC-9181-PF-48	1	No Ice	80.04	54.87	71.65	46.47	71.65	54.87
MP2, 0	--	w/ Ice	17.85	12.99	16.23	11.37	16.23	12.99
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						

EQUIPMENT LATERAL WIND FORCE CALCULATIONS [CONT.]

Appurtenance Name	Qty.	--	0° 180°	30° 210°	60° 240°	90° 270°	120° 300°	150° 330°
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						

APPENDIX C
SOFTWARE ANALYSIS OUTPUT



Company : Trylon
 Designer : TL
 Job Number : 189200
 Model Name : CT Suffield 2 CAC 801486 (BU 801486 Order 556646)

Aug 3, 2021
 10:35 AM
 Checked By: _____

(Global) Model Settings

Display Sections for Member Calcs	5
Max Internal Sections for Member Calcs	97
Include Shear Deformation?	Yes
Increase Nailing Capacity for Wind?	Yes
Include Warping?	Yes
Trans Load Btwn Intersecting Wood Wall?	Yes
Area Load Mesh (in^2)	144
Merge Tolerance (in)	.12
P-Delta Analysis Tolerance	0.50%
Include P-Delta for Walls?	Yes
Automatically Iterate Stiffness for Walls?	Yes
Max Iterations for Wall Stiffness	3
Gravity Acceleration (in/sec^2)	386.4
Wall Mesh Size (in)	24
Eigensolution Convergence Tol. (1.E-)	4
Vertical Axis	Y
Global Member Orientation Plane	XZ
Static Solver	Sparse Accelerated
Dynamic Solver	Accelerated Solver

Hot Rolled Steel Code	AISC 15th(360-16): LRFD
Adjust Stiffness?	Yes(Iterative)
RISACONNECTION CODE	AISC 15th(360-16): LRFD
Cold Formed Steel Code	AISI S100-12: LRFD
Wood Code	AWC NDS-15: ASD
Wood Temperature	< 100F
Concrete Code	ACI 318-14
Masonry Code	ACI 530-13: Strength
Aluminum Code	AA ADM1-10: LRFD - Building
Stainless Steel Code	AISC 14th(360-10): LRFD
Adjust Stiffness?	Yes(Iterative)

Number of Shear Regions	4
Region Spacing Increment (in)	4
Biaxial Column Method	Exact Integration
Parame Beta Factor (PCA)	.65
Concrete Stress Block	Rectangular
Use Cracked Sections?	Yes
Use Cracked Sections Slab?	Yes
Bad Framing Warnings?	No
Unused Force Warnings?	Yes
Min 1 Bar Diam. Spacing?	No
Concrete Rebar Set	REBAR SET ASTMA615
Min % Steel for Column	1
Max % Steel for Column	8



(Global) Model Settings, Continued

Seismic Code	ASCE 7-10
Seismic Base Elevation (in)	Not Entered
Add Base Weight?	Yes
Ct X	.02
Ct Z	.02
T X (sec)	Not Entered
T Z (sec)	Not Entered
R X	3
R Z	3
Ct Exp. X	.75
Ct Exp. Z	.75
SD1	1
SDS	1
S1	1
TL (sec)	5
Risk Cat	I or II
Drift Cat	Other
Om Z	1
Om X	1
Cd Z	1
Cd X	1
Rho Z	1
Rho X	1

Hot Rolled Steel Properties

	Label	E [ksi]	G [ksi]	Nu	Therm (/1E...Density[k/ft...	Yield[psi]	Ry	Fu[psi]	Rt	
1	A992	29000	11154	.3	.65	.49	50000	1.1	65000	1.1
2	A36 Gr.36	29000	11154	.3	.65	.49	36000	1.5	58000	1.2
3	A572 Gr.50	29000	11154	.3	.65	.49	50000	1.1	65000	1.1
4	A500 Gr.B RND	29000	11154	.3	.65	.527	42000	1.4	58000	1.3
5	A500 Gr.B Rect	29000	11154	.3	.65	.527	46000	1.4	58000	1.3
6	A53 Gr.B	29000	11154	.3	.65	.49	35000	1.6	60000	1.2
7	A1085	29000	11154	.3	.65	.49	50000	1.4	65000	1.3

Cold Formed Steel Properties

	Label	E [ksi]	G [ksi]	Nu	Therm (/1E5 F)	Density[k/ft^3]	Yield[psi]	Fu[psi]
1	A653 SS Gr33	29500	11346	.3	.65	.49	33000	45000
2	A653 SS Gr50/1	29500	11346	.3	.65	.49	50000	65000

Hot Rolled Steel Section Sets

	Label	Shape	Type	Design List	Material	Design ...	A [in2]	Iyy [in4]	Izz [in4]	J [in4]
1	Plates	6.5"x0.37" Plate	Beam	RECT	A53 Gr.B	Typical	2.405	.027	8.468	.106
2	Grating Bracing	L2x2x3	Beam	Single Angle	A36 Gr.36	Typical	.722	.271	.271	.009
3	Standoffs	PIPE 3.5	Beam	Pipe	A53 Gr.B	Typical	2.5	4.52	4.52	9.04
4	Standoff Bracing	C3X5	Beam	Channel	A36 Gr.36	Typical	1.47	.241	1.85	.043
5	Handrails	PIPE 2.0	Beam	Pipe	A53 Gr.B	Typical	1.02	.627	.627	1.25
6	Handrail Corners	L6 5/8x4 7/16x...	Beam	Single Angle	A36 Gr.36	Typical	2.039	3.593	9.575	.023
7	Horizontals	PIPE 3.5	Beam	Pipe	A53 Gr.B	Typical	2.5	4.52	4.52	9.04
8	Mount Pipes	PIPE_2.0	Beam	Pipe	A53 Gr.B	Typical	1.02	.627	.627	1.25



Company : Trylon
 Designer : TL
 Job Number : 189200
 Model Name : CT Suffield 2 CAC 801486 (BU 801486 Order 556646)

Aug 3, 2021
 10:35 AM
 Checked By: _____

Cold Formed Steel Section Sets

	Label	Shape	Type	Design List	Material	Design Rul...	A [in ²]	I _{yy} [in ⁴]	I _{zz} [in ⁴]	J [in ⁴]
1	CF1A	8CU1.25X057	Beam	None	A653 SS Gr33	Typical	.581	.057	4.41	.00063

Joint Boundary Conditions

	Joint Label	X [k/in]	Y [k/in]	Z [k/in]	X Rot.[k-ft/rad]	Y Rot.[k-ft/rad]	Z Rot.[k-ft/rad]
1	N25	Reaction	Reaction	Reaction	Reaction	Reaction	Reaction
2	N1	Reaction	Reaction	Reaction	Reaction	Reaction	Reaction
3	N13	Reaction	Reaction	Reaction	Reaction	Reaction	Reaction

Basic Load Cases

	BLC Description	Category	X Gravity	Y Gravity	Z Gravity	Joint	Point	Distributed Area(Me... Surface(...
1	Self Weight	DL		-1			15	3
2	Structure Wind Z	WLZ					51	
3	Structure Wind X	WLX					51	
4	Wind Load 0 AZI	WLZ					30	
5	Wind Load 30 AZI	None					30	
6	Wind Load 45 AZI	None					30	
7	Wind Load 60 AZI	None					30	
8	Wind Load 90 AZI	WLX					30	
9	Wind Load 120 AZI	None					30	
10	Wind Load 135 AZI	None					30	
11	Wind Load 150 AZI	None					30	
12	Ice Weight	OL1					15	51 3
13	Ice Structure Wind Z	OL2					51	
14	Ice Structure Wind X	OL3					51	
15	Ice Wind Load 0 AZI	OL2					30	
16	Ice Wind Load 30 AZI	None					30	
17	Ice Wind Load 45 AZI	None					30	
18	Ice Wind Load 60 AZI	None					30	
19	Ice Wind Load 90 AZI	OL3					30	
20	Ice Wind Load 120 AZI	None					30	
21	Ice Wind Load 135 AZI	None					30	
22	Ice Wind Load 150 AZI	None					30	
23	Seismic Load Z	ELZ			-.113		15	
24	Seismic Load X	ELX	-.113				15	
25	Live Load 1 (Lv)	None					1	
26	Live Load 2 (Lv)	None					1	
27	Live Load 3 (Lv)	None					1	
28	Live Load 4 (Lv)	None					1	
29	Live Load 5 (Lv)	None					1	
30	Live Load 6 (Lv)	None					1	
31	Live Load 7 (Lv)	None					1	
32	Live Load 8 (Lv)	None					1	
33	Live Load 9 (Lv)	None					1	
34	Maintenance Load 1 (Lm)	None					1	
35	Maintenance Load 2 (Lm)	None					1	
36	Maintenance Load 3 (Lm)	None					1	
37	Maintenance Load 4 (Lm)	None					1	
38	Maintenance Load 5 (Lm)	None					1	
39	Maintenance Load 6 (Lm)	None					1	
40	Maintenance Load 7 (Lm)	None					1	
41	Maintenance Load 8 (Lm)	None					1	
42	Maintenance Load 9 (Lm)	None					1	
43	BLC 1 Transient Area Loads	None					9	



Basic Load Cases (Continued)

BLC Description	Category	X Gravity	Y Gravity	Z Gravity	Joint	Point	Distributed Area(Me... Surface(...
44 BLC 12 Transient Area Loads	None						9

Load Combinations

Description	S...	P...	S...	B...	Fa...	B...	Fa...	B...	Fa...	B...	Fa...	B...	Fa...	B...	Fa...	B...	Fa...	B...	Fa...	B...	Fa...	B...	Fa...	B...	Fa...	B...	Fa...			
1 1.4DL	Yes	Y		DL	1.4																									
2 1.2DL + 1WL 0 AZI	Yes	Y		DL	1.2	2	1	3		4	1																			
3 1.2DL + 1WL 30 AZI	Yes	Y		DL	1.2	2	.866	3	.5	5	1																			
4 1.2DL + 1WL 45 AZI	Yes	Y		DL	1.2	2	.707	3	.707	6	1																			
5 1.2DL + 1WL 60 AZI	Yes	Y		DL	1.2	2	.5	3	.866	7	1																			
6 1.2DL + 1WL 90 AZI	Yes	Y		DL	1.2	2		3	1	8	1																			
7 1.2DL + 1WL 120 AZI	Yes	Y		DL	1.2	2	-.5	3	.866	9	1																			
8 1.2DL + 1WL 135 AZI	Yes	Y		DL	1.2	2	-.7...	3	.707	10	1																			
9 1.2DL + 1WL 150 AZI	Yes	Y		DL	1.2	2	-.8...	3	.5	11	1																			
10 1.2DL + 1WL 180 AZI	Yes	Y		DL	1.2	2	-1	3		4	-1																			
11 1.2DL + 1WL 210 AZI	Yes	Y		DL	1.2	2	-.8...	3	-.5	5	-1																			
12 1.2DL + 1WL 225 AZI	Yes	Y		DL	1.2	2	-.7...	3	-.7...	6	-1																			
13 1.2DL + 1WL 240 AZI	Yes	Y		DL	1.2	2	-.5	3	-.8...	7	-1																			
14 1.2DL + 1WL 270 AZI	Yes	Y		DL	1.2	2		3	-1	8	-1																			
15 1.2DL + 1WL 300 AZI	Yes	Y		DL	1.2	2	.5	3	-.8...	9	-1																			
16 1.2DL + 1WL 315 AZI	Yes	Y		DL	1.2	2	.707	3	-.7...	10	-1																			
17 1.2DL + 1WL 330 AZI	Yes	Y		DL	1.2	2	.866	3	-.5	11	-1																			
18 0.9DL + 1WL 0 AZI	Yes	Y		DL	.9	2	1	3		4	1																			
19 0.9DL + 1WL 30 AZI	Yes	Y		DL	.9	2	.866	3	.5	5	1																			
20 0.9DL + 1WL 45 AZI	Yes	Y		DL	.9	2	.707	3	.707	6	1																			
21 0.9DL + 1WL 60 AZI	Yes	Y		DL	.9	2	.5	3	.866	7	1																			
22 0.9DL + 1WL 90 AZI	Yes	Y		DL	.9	2		3	1	8	1																			
23 0.9DL + 1WL 120 AZI	Yes	Y		DL	.9	2	-.5	3	.866	9	1																			
24 0.9DL + 1WL 135 AZI	Yes	Y		DL	.9	2	-.7...	3	.707	10	1																			
25 0.9DL + 1WL 150 AZI	Yes	Y		DL	.9	2	-.8...	3	.5	11	1																			
26 0.9DL + 1WL 180 AZI	Yes	Y		DL	.9	2	-1	3		4	-1																			
27 0.9DL + 1WL 210 AZI	Yes	Y		DL	.9	2	-.8...	3	-.5	5	-1																			
28 0.9DL + 1WL 225 AZI	Yes	Y		DL	.9	2	-.7...	3	-.7...	6	-1																			
29 0.9DL + 1WL 240 AZI	Yes	Y		DL	.9	2	-.5	3	-.8...	7	-1																			
30 0.9DL + 1WL 270 AZI	Yes	Y		DL	.9	2		3	-1	8	-1																			
31 0.9DL + 1WL 300 AZI	Yes	Y		DL	.9	2	.5	3	-.8...	9	-1																			
32 0.9DL + 1WL 315 AZI	Yes	Y		DL	.9	2	.707	3	-.7...	10	-1																			
33 0.9DL + 1WL 330 AZI	Yes	Y		DL	.9	2	.866	3	-.5	11	-1																			
34 1.2DL + 1DLi + 1WLi 0 AZI	Yes	Y		DL	1.2	O...	1	13	1	14		15	1																	
35 1.2DL + 1DLi + 1WLi 30 AZI	Yes	Y		DL	1.2	O...	1	13	.866	14	.5	16	1																	
36 1.2DL + 1DLi + 1WLi 45 AZI	Yes	Y		DL	1.2	O...	1	13	.707	14	.707	17	1																	
37 1.2DL + 1DLi + 1WLi 60 AZI	Yes	Y		DL	1.2	O...	1	13	.5	14	.866	18	1																	
38 1.2DL + 1DLi + 1WLi 90 AZI	Yes	Y		DL	1.2	O...	1	13		14	1	19	1																	
39 1.2DL + 1DLi + 1WLi 120 AZI	Yes	Y		DL	1.2	O...	1	13	-.5	14	.866	20	1																	
40 1.2DL + 1DLi + 1WLi 135 AZI	Yes	Y		DL	1.2	O...	1	13	-.7...	14	.707	21	1																	
41 1.2DL + 1DLi + 1WLi 150 AZI	Yes	Y		DL	1.2	O...	1	13	-.8...	14	.5	22	1																	
42 1.2DL + 1DLi + 1WLi 180 AZI	Yes	Y		DL	1.2	O...	1	13	-1	14		15	-1																	
43 1.2DL + 1DLi + 1WLi 210 AZI	Yes	Y		DL	1.2	O...	1	13	-.8...	14	-.5	16	-1																	
44 1.2DL + 1DLi + 1WLi 225 AZI	Yes	Y		DL	1.2	O...	1	13	-.7...	14	-.7...	17	-1																	
45 1.2DL + 1DLi + 1WLi 240 AZI	Yes	Y		DL	1.2	O...	1	13	-.5	14	-.8...	18	-1																	
46 1.2DL + 1DLi + 1WLi 270 AZI	Yes	Y		DL	1.2	O...	1	13		14	-1	19	-1																	
47 1.2DL + 1DLi + 1WLi 300 AZI	Yes	Y		DL	1.2	O...	1	13	.5	14	-.8...	20	-1																	
48 1.2DL + 1DLi + 1WLi 315 AZI	Yes	Y		DL	1.2	O...	1	13	.707	14	-.7...	21	-1																	
49 1.2DL + 1DLi + 1WLi 330 AZI	Yes	Y		DL	1.2	O...	1	13	.866	14	-.5	22	-1																	
50 (1.2+0.2Sds)DL + 1E 0 AZI	Yes	Y		DL	1.2...	23	1	24																						
51 (1.2+0.2Sds)DL + 1E 30 AZI	Yes	Y		DL	1.2...	23	.866	24	.5																					

Load Combinations (Continued)

Line	Description	S...	P...	S...	B...	Fa...	B...	Fa...	B...	Fa...	B...	Fa...	B...	Fa...	B...	Fa...	B...	Fa...	B...	Fa...	B...	Fa...	B...	Fa...	B...	Fa...	B...
166	1.2DL + 1.5Lm + 1Wm 240 A...	Yes	Y		DL	1.2	38	1.5	2	-0...	3	-0...	7	-0...													
167	1.2DL + 1.5Lm + 1Wm 270 A...	Yes	Y		DL	1.2	38	1.5	2		3	-0...	8	-0...													
168	1.2DL + 1.5Lm + 1Wm 300 A...	Yes	Y		DL	1.2	38	1.5	2	.031	3	-0...	9	-0...													
169	1.2DL + 1.5Lm + 1Wm 315 A...	Yes	Y		DL	1.2	38	1.5	2	.044	3	-0...	10	-0...													
170	1.2DL + 1.5Lm + 1Wm 330 A...	Yes	Y		DL	1.2	38	1.5	2	.054	3	-0...	11	-0...													
171	1.2DL + 1.5Lm + 1Wm 0 AZI -..	Yes	Y		DL	1.2	39	1.5	2	.063	3		4	.063													
172	1.2DL + 1.5Lm + 1Wm 30 AZI..	Yes	Y		DL	1.2	39	1.5	2	.054	3	.031	5	.063													
173	1.2DL + 1.5Lm + 1Wm 45 AZI..	Yes	Y		DL	1.2	39	1.5	2	.044	3	.044	6	.063													
174	1.2DL + 1.5Lm + 1Wm 60 AZI..	Yes	Y		DL	1.2	39	1.5	2	.031	3	.054	7	.063													
175	1.2DL + 1.5Lm + 1Wm 90 AZI..	Yes	Y		DL	1.2	39	1.5	2		3	.063	8	.063													
176	1.2DL + 1.5Lm + 1Wm 120 A...	Yes	Y		DL	1.2	39	1.5	2	-0...	3	.054	9	.063													
177	1.2DL + 1.5Lm + 1Wm 135 A...	Yes	Y		DL	1.2	39	1.5	2	-0...	3	.044	10	.063													
178	1.2DL + 1.5Lm + 1Wm 150 A...	Yes	Y		DL	1.2	39	1.5	2	-0...	3	.031	11	.063													
179	1.2DL + 1.5Lm + 1Wm 180 A...	Yes	Y		DL	1.2	39	1.5	2	-0...	3		4	-0...													
180	1.2DL + 1.5Lm + 1Wm 210 A...	Yes	Y		DL	1.2	39	1.5	2	-0...	3	-0...	5	-0...													
181	1.2DL + 1.5Lm + 1Wm 225 A...	Yes	Y		DL	1.2	39	1.5	2	-0...	3	-0...	6	-0...													
182	1.2DL + 1.5Lm + 1Wm 240 A...	Yes	Y		DL	1.2	39	1.5	2	-0...	3	-0...	7	-0...													
183	1.2DL + 1.5Lm + 1Wm 270 A...	Yes	Y		DL	1.2	39	1.5	2		3	-0...	8	-0...													
184	1.2DL + 1.5Lm + 1Wm 300 A...	Yes	Y		DL	1.2	39	1.5	2	.031	3	-0...	9	-0...													
185	1.2DL + 1.5Lm + 1Wm 315 A...	Yes	Y		DL	1.2	39	1.5	2	.044	3	-0...	10	-0...													
186	1.2DL + 1.5Lm + 1Wm 330 A...	Yes	Y		DL	1.2	39	1.5	2	.054	3	-0...	11	-0...													
187	1.2DL + 1.5Lm + 1Wm 0 AZI -..	Yes	Y		DL	1.2	40	1.5	2	.063	3		4	.063													
188	1.2DL + 1.5Lm + 1Wm 30 AZI..	Yes	Y		DL	1.2	40	1.5	2	.054	3	.031	5	.063													
189	1.2DL + 1.5Lm + 1Wm 45 AZI..	Yes	Y		DL	1.2	40	1.5	2	.044	3	.044	6	.063													
190	1.2DL + 1.5Lm + 1Wm 60 AZI..	Yes	Y		DL	1.2	40	1.5	2	.031	3	.054	7	.063													
191	1.2DL + 1.5Lm + 1Wm 90 AZI..	Yes	Y		DL	1.2	40	1.5	2		3	.063	8	.063													
192	1.2DL + 1.5Lm + 1Wm 120 A...	Yes	Y		DL	1.2	40	1.5	2	-0...	3	.054	9	.063													
193	1.2DL + 1.5Lm + 1Wm 135 A...	Yes	Y		DL	1.2	40	1.5	2	-0...	3	.044	10	.063													
194	1.2DL + 1.5Lm + 1Wm 150 A...	Yes	Y		DL	1.2	40	1.5	2	-0...	3	.031	11	.063													
195	1.2DL + 1.5Lm + 1Wm 180 A...	Yes	Y		DL	1.2	40	1.5	2	-0...	3		4	-0...													
196	1.2DL + 1.5Lm + 1Wm 210 A...	Yes	Y		DL	1.2	40	1.5	2	-0...	3	-0...	5	-0...													
197	1.2DL + 1.5Lm + 1Wm 225 A...	Yes	Y		DL	1.2	40	1.5	2	-0...	3	-0...	6	-0...													
198	1.2DL + 1.5Lm + 1Wm 240 A...	Yes	Y		DL	1.2	40	1.5	2	-0...	3	-0...	7	-0...													
199	1.2DL + 1.5Lm + 1Wm 270 A...	Yes	Y		DL	1.2	40	1.5	2		3	-0...	8	-0...													
200	1.2DL + 1.5Lm + 1Wm 300 A...	Yes	Y		DL	1.2	40	1.5	2	.031	3	-0...	9	-0...													
201	1.2DL + 1.5Lm + 1Wm 315 A...	Yes	Y		DL	1.2	40	1.5	2	.044	3	-0...	10	-0...													
202	1.2DL + 1.5Lm + 1Wm 330 A...	Yes	Y		DL	1.2	40	1.5	2	.054	3	-0...	11	-0...													
203	1.2DL + 1.5Lm + 1Wm 0 AZI -..	Yes	Y		DL	1.2	41	1.5	2	.063	3		4	.063													
204	1.2DL + 1.5Lm + 1Wm 30 AZI..	Yes	Y		DL	1.2	41	1.5	2	.054	3	.031	5	.063													
205	1.2DL + 1.5Lm + 1Wm 45 AZI..	Yes	Y		DL	1.2	41	1.5	2	.044	3	.044	6	.063													
206	1.2DL + 1.5Lm + 1Wm 60 AZI..	Yes	Y		DL	1.2	41	1.5	2	.031	3	.054	7	.063													
207	1.2DL + 1.5Lm + 1Wm 90 AZI..	Yes	Y		DL	1.2	41	1.5	2		3	.063	8	.063													
208	1.2DL + 1.5Lm + 1Wm 120 A...	Yes	Y		DL	1.2	41	1.5	2	-0...	3	.054	9	.063													
209	1.2DL + 1.5Lm + 1Wm 135 A...	Yes	Y		DL	1.2	41	1.5	2	-0...	3	.044	10	.063													
210	1.2DL + 1.5Lm + 1Wm 150 A...	Yes	Y		DL	1.2	41	1.5	2	-0...	3	.031	11	.063													
211	1.2DL + 1.5Lm + 1Wm 180 A...	Yes	Y		DL	1.2	41	1.5	2	-0...	3		4	-0...													
212	1.2DL + 1.5Lm + 1Wm 210 A...	Yes	Y		DL	1.2	41	1.5	2	-0...	3	-0...	5	-0...													
213	1.2DL + 1.5Lm + 1Wm 225 A...	Yes	Y		DL	1.2	41	1.5	2	-0...	3	-0...	6	-0...													
214	1.2DL + 1.5Lm + 1Wm 240 A...	Yes	Y		DL	1.2	41	1.5	2	-0...	3	-0...	7	-0...													
215	1.2DL + 1.5Lm + 1Wm 270 A...	Yes	Y		DL	1.2	41	1.5	2		3	-0...	8	-0...													
216	1.2DL + 1.5Lm + 1Wm 300 A...	Yes	Y		DL	1.2	41	1.5	2	.031	3	-0...	9	-0...													
217	1.2DL + 1.5Lm + 1Wm 315 A...	Yes	Y		DL	1.2	41	1.5	2	.044	3	-0...	10	-0...													
218	1.2DL + 1.5Lm + 1Wm 330 A...	Yes	Y		DL	1.2	41	1.5	2	.054	3	-0...	11	-0...													
219	1.2DL + 1.5Lm + 1Wm 0 AZI -..	Yes	Y		DL	1.2	42	1.5	2	.063	3		4	.063													
220	1.2DL + 1.5Lm + 1Wm 30 AZI..	Yes	Y		DL	1.2	42	1.5	2	.054	3	.031	5	.063													
221	1.2DL + 1.5Lm + 1Wm 45 AZI..	Yes	Y		DL	1.2	42	1.5	2	.044	3	.044	6	.063													
222	1.2DL + 1.5Lm + 1Wm 60 AZI..	Yes	Y		DL	1.2	42	1.5	2	.031	3	.054	7	.063													



Load Combinations (Continued)

Description	S...	P...	S...	B...	Fa...	B...	Fa...	B...	Fa...	B...	Fa...	B...	Fa...	B...	Fa...	B...	Fa...	B...	Fa...	B...	Fa...	B...	Fa...	B...	Fa...	B...	Fa...	B...
223	1.2DL + 1.5Lm + 1Wm 90 AZI...	Yes	Y		DL	1.2	42	1.5	2		3	.063	8	.063														
224	1.2DL + 1.5Lm + 1Wm 120 A...	Yes	Y		DL	1.2	42	1.5	2	-0...	3	.054	9	.063														
225	1.2DL + 1.5Lm + 1Wm 135 A...	Yes	Y		DL	1.2	42	1.5	2	-0...	3	.044	10	.063														
226	1.2DL + 1.5Lm + 1Wm 150 A...	Yes	Y		DL	1.2	42	1.5	2	-0...	3	.031	11	.063														
227	1.2DL + 1.5Lm + 1Wm 180 A...	Yes	Y		DL	1.2	42	1.5	2	-0...	3		4	-0...														
228	1.2DL + 1.5Lm + 1Wm 210 A...	Yes	Y		DL	1.2	42	1.5	2	-0...	3	-0...	5	-0...														
229	1.2DL + 1.5Lm + 1Wm 225 A...	Yes	Y		DL	1.2	42	1.5	2	-0...	3	-0...	6	-0...														
230	1.2DL + 1.5Lm + 1Wm 240 A...	Yes	Y		DL	1.2	42	1.5	2	-0...	3	-0...	7	-0...														
231	1.2DL + 1.5Lm + 1Wm 270 A...	Yes	Y		DL	1.2	42	1.5	2		3	-0...	8	-0...														
232	1.2DL + 1.5Lm + 1Wm 300 A...	Yes	Y		DL	1.2	42	1.5	2	.031	3	-0...	9	-0...														
233	1.2DL + 1.5Lm + 1Wm 315 A...	Yes	Y		DL	1.2	42	1.5	2	.044	3	-0...	10	-0...														
234	1.2DL + 1.5Lm + 1Wm 330 A...	Yes	Y		DL	1.2	42	1.5	2	.054	3	-0...	11	-0...														

Envelope Joint Reactions

Joint	X [lb]	LC	Y [lb]	LC	Z [lb]	LC	MX [lb-ft]	LC	MY [lb-ft]	LC	MZ [lb-ft]	LC		
1	N25	max	1083.26	20	2357.688	39	1829.519	3	569.859	18	2067.69	3	506.705	31
2		min	-1089.993	12	-104.089	31	-1825.295	27	-2573.589	42	-2067.145	27	-4126.869	39
3	N1	max	1082.676	8	2359.385	45	1774.263	17	571.118	19	2006.301	25	4132	45
4		min	-1075.963	32	-113.514	21	-1770.058	25	-2574.665	43	-2006.885	17	-534.904	21
5	N13	max	1704.981	22	2273.142	34	443.857	18	4652.958	34	1619.81	30	766.497	14
6		min	-1704.949	30	-180.893	26	-452.678	10	-783.528	26	-1619.822	22	-767.066	6
7	Totals:	max	3190.568	22	6514.097	42	3617.639	18						
8		min	-3190.568	30	1348.123	81	-3617.64	10						

Envelope AISC 15th(360-16): LRFD Steel Code Checks

Member	Shape	Code	Loc[in]	LC	Shear	Loc[in]	Dir	LC	phi*Pnc	phi*Pnt	phi*Mn	phi*Mn	Cb	Eqn
1	M2	PIPE 3.5	.608	40	45	.208	40	9	75262.68	78750	7953.75	7953.75	2.141	H1-1b
2	M12	PIPE 3.5	.607	40	39	.214	40	11	75262.68	78750	7953.75	7953.75	2.141	H1-1b
3	M7	PIPE 3.5	.586	40	34	.184	40	6	75262.68	78750	7953.75	7953.75	2.14	H1-1b
4	M11	C3X5	.501	34.8...	41	.171	63.1...	y 35	11202.9...	47628	981.263	4104	1.344	H1-1b
5	M1	C3X5	.501	34.8...	43	.171	6.536	y 49	11202.9...	47628	981.263	4104	1.344	H1-1b
6	M6	C3X5	.477	34.8...	34	.164	63.1...	y 45	37027.8...	47628	981.263	4020.228	1	H1-1b
7	MP4	PIPE 2.0	.435	60	10	.048	60	5	20866.7...	32130	1871.625	1871.625	1.564	H1-1b
8	MP9	PIPE 2.0	.405	60	10	.049	60	15	20866.7...	32130	1871.625	1871.625	1.558	H1-1b
9	MP3	PIPE 2.0	.404	60	4	.050	60	9	20866.7...	32130	1871.625	1871.625	1.857	H1-1b
10	MP1	PIPE 2.0	.401	60	16	.054	60	11	20866.7...	32130	1871.625	1871.625	1.857	H1-1b
11	MP6	PIPE 2.0	.378	60	2	.058	60	3	20866.7...	32130	1871.625	1871.625	1.595	H1-1b
12	MP7	PIPE 2.0	.377	60	5	.057	60	15	20866.7...	32130	1871.625	1871.625	1.929	H1-1b
13	MP5	PIPE 2.0	.375	60	10	.053	60	10	20866.7...	32130	1871.625	1871.625	1.423	H1-1b
14	MP8	PIPE 2.0	.353	60	10	.050	60	10	20866.7...	32130	1871.625	1871.625	1.497	H1-1b
15	MP2	PIPE 2.0	.343	60	15	.055	60	15	20866.7...	32130	1871.625	1871.625	1.491	H1-1b
16	M10	6.5"x0.37" Plate	.294	21	2	.107	21	y 37	3513.807	75757.5	583.963	6147.509	1.139	H1-1b
17	M5	6.5"x0.37" Plate	.287	21	12	.111	21	y 42	3513.807	75757.5	583.963	6331.63	1.173	H1-1b
18	M15	6.5"x0.37" Plate	.283	21	8	.111	21	y 42	3513.807	75757.5	583.963	6336.004	1.174	H1-1b
19	M4	L2x2x3	.166	0	13	.035	0	y 41	18051.7...	23392.8	557.717	1239.29	2.208	H2-1
20	M19	PIPE 2.0	.165	24	10	.156	24	2	14916.0...	32130	1871.625	1871.625	1.48	H1-1b
21	M9	L2x2x3	.164	0	2	.034	0	y 46	18051.7...	23392.8	557.717	1239.29	2.259	H2-1
22	M21	PIPE 2.0	.162	72	4	.156	24	12	14916.0...	32130	1871.625	1871.625	1.53	H1-1b
23	M20	PIPE 2.0	.159	24	16	.153	72	8	14916.0...	32130	1871.625	1871.625	1.536	H1-1b
24	M13	L2x2x3	.159	0	7	.035	0	z 43	18051.7...	23392.8	557.717	1239.29	2.204	H2-1
25	M22	L6 5/8x4 7/16x3/...	.156	42	27	.046	0	y 3	15453.0...	66065.6...	1040.591	3031.076	2.194	H2-1
26	M8	L2x2x3	.156	0	2	.034	0	z 38	18051.7...	23392.8	557.717	1239.29	2.255	H2-1
27	M3	L2x2x3	.151	0	12	.036	0	z 49	18051.7...	23392.8	557.717	1239.29	2.162	H2-1
28	M14	L2x2x3	.149	0	8	.036	0	y 35	18051.7...	23392.8	557.717	1239.29	2.161	H2-1



Company : Trylon
 Designer : TL
 Job Number : 189200
 Model Name : CT Suffield 2 CAC 801486 (BU 801486 Order 556646)

Aug 3, 2021
 10:35 AM
 Checked By: _____

Envelope AISC 15th(360-16): LRFD Steel Code Checks (Continued)

Member	Shape	Code	Loc[in]	LC	Shear	Loc[in]	Dir	LC	phi*Pnc	phi*Pnt	phi*Mn	phi*Mn	Cb	Eqn	
29	M23	L6 5/8x4 7/16x3/...	.140	0	25	.044	42	y	17	15453.0...	66065.6...	1040.591	3031.076	2.218	H2-1
30	H1	PIPE 3.5	.121	48	92	.111	24		10	60666.0...	78750	7953.75	7953.75	1.445	H1-1b
31	H2	PIPE 3.5	.118	48	196	.110	72		4	60666.0...	78750	7953.75	7953.75	1.446	H1-1b
32	H3	PIPE 3.5	.118	48	146	.109	24		16	60666.0...	78750	7953.75	7953.75	1.446	H1-1b
33	M24	L6 5/8x4 7/16x3/...	.118	37.6...	19	.040	42	y	6	15453.0...	66065.6...	1040.591	3031.076	1.413	H2-1

Envelope AISI S100-12: LRFD Cold Formed Steel Code Checks

Member	Shape	Code Check	Loc[in]	LC	Shea...	Loc[j]	Dir	LC	phi*Pn[...	phi*Tn[...	phi*Mn...	phi*Mn...	Cb	Cmyy	Cmzz	Eqn
No Data to Print ...																

APPENDIX D
ADDITIONAL CALCULATIONS

BOLT TOOL 1.5.2

Project Data	
Job Code:	189200
Carrier Site ID:	BOBDL00036A
Carrier Site Name:	CT-CCI-T-801486


Code	
Design Standard:	TIA-222-H
Slip Check:	No
Pretension Standard:	TIA-222-H

Bolt Properties		
Connection Type:	Bolt	
Diameter:	0.75	in
Grade:	A529	--
Yield Strength (Fy):	50	ksi
Ultimate Strength (Fu):	65	ksi
Number of Bolts:	4	--
Threads Included:	Yes	--
Double Shear:	No	--
Connection Pipe Size:	-	in

Connection Description
Mount Standoff to Collar

Bolt Check*		
Tensile Capacity (ϕT_n):	16304.9	lbs
Shear Capacity (ϕV_n):	10768.5	lbs
Tension Force (T_u):	5081.2	lbs
Shear Force (V_u):	763.5	lbs
Tension Usage:	29.7%	--
Shear Usage:	6.8%	--
Interaction:	29.7%	Pass
Controlling Member:	M12	--
Controlling LC:	42	--

*Rating per TIA-222-H Section 15.5




APPENDIX E
SUPPLEMENTAL DRAWINGS

ITEM	PART NO.	DESCRIPTION	QTY.	WEIGHT	NOTE NO.
1	MTC3006SB	STEEL BUNDLE FOR SNUB NOSE PLATFORM	1	402.64 LBS	
2	MCPK8CSB	PIPE STEEL BUNDLE FOR MC-PK8-C	1	464.27 LBS	
3	MCPK8CHWK	HARDWARE KIT FOR MC-PK8-C	1	543.22 LBS	







REVISIONS				
REV.	ECN	DESCRIPTION	BY	DATE
A		INITIAL RELEASE	DRR	12/27/11
B	8000005979	CHANGE NOSE CORNER BRKT, ADD GUB-4240	MSM	11/25/14
C	8000007579	NEW RINGMOUNT WELDMENT DESIGN	RJC	04/07/15

FOR BOM ENTRY ONLY



NOTES:
1. CUSTOMER ASSEMBLY SHEETS 2-3.

<small>These drawings and specifications are the proprietary property of ANDREW CORPORATION and may be used only for the specific purpose authorized in writing by Andrew Corporation.</small>			<small>DRAWN BY:</small> MSM	<small>SHEET:</small> 1 of 3	<small>PART NUMBER:</small> MC-PK8-C
<small>ALL DIMENSIONS ARE IN INCHES U.O.S. TOLERANCES UNLESS OTHERWISE SPECIFIED:</small>			<small>CHECKED BY:</small> TP	<small>SCALE:</small> NTS	<small>DESCRIPTION:</small> LOW PROFILE PLATFORM KIT 8' FACE
<small>.X = ± .12 ANGLES ±2° .XX = ± .06 FRACTIONS ±1/32 .XXX = ± .03</small>			<small>DATE:</small> 10/18/11	<small>MATERIAL:</small> A36, A500	<small>DRAWING TYPE:</small> ASSEMBLY DRAWING
<small>REMOVE BURRS AND BREAK EDGES .005</small>			<small>REVISION:</small> C	<small>FINISH:</small> GALV A123	 WESTCHESTER, IL. 60154 U.S.A.
<small>DO NOT SCALE THIS PRINT</small>				<small>WEIGHT:</small> 1410.14 LBS	




ITEM	PART NO.	DESCRIPTION	QTY.	WEIGHT
1	MC-RM1550-3	12" - 50" OD RINGMOUNT	1	230.42 LBS
2	MTC300601	Low Profile Co-Location Platform Snub Nose	3	134.21 LBS
3	MT195801	Corner Weldment Snub Nose Handrail	3	27.10 LBS
4	XA2020.01	CROSS OVER ANGLE	9	2.65 LBS
5	GUB-4356	1/2" X 3-5/8" X 6" GALV U-BOLT	18	0.82 LBS
6	GUB-4355	1/2" X 3-5/8" X 5" GALV U-BOLT	12	0.71 LBS
7	GUB-4240	1/2" X 2-1/2" X 4" GALV U-BOLT	48	0.56 LBS
8	GB-04145	1/2" X 1-1/2" GALV BOLT KIT	12	0.13 LBS
9	GWF-04	1/2" GALV FLAT WASHER	24	0.03 LBS
10	GB-0520A	5/8" X 2" GALV BOLT KIT (A325)	12	0.27 LBS
11	MT54796	3.50" OD X 96" GALV PIPE	3	60.28 LBS
12	MT-651-96	Ø2.375" OD X 96" PIPE	3	29.07 LBS
13	MT-651	2.375" OD x 72" PIPE	9	21.80 LBS
14	MT19617	MT196 Pipe Mount Plate	6	2.49 LBS
15	MT21701	PIPE MOUNT PLATE	9	7.93 LBS

<small>These drawings and specifications are the proprietary property of ANDREW CORPORATION and may be used only for the specific purpose authorized in writing by Andrew Corporation.</small>			
<small>DESIGNED BY:</small> MSM	<small>DRAWN BY:</small> TP	<small>SHEET:</small> 2 of 3	<small>PART NUMBER:</small> MC-PK8-C
<small>ALL DIMENSIONS ARE IN INCHES U.O.S. TOLERANCES UNLESS OTHERWISE SPECIFIED:</small> .X = ± .12 ANGLES ±2° .XX = ± .06 FRACTIONS ±1/32 .XXX = ± .03		<small>DATE:</small> 10/18/11	<small>DESCRIPTION:</small> 25" OD Snub Nose MT-196
<small>REVISIONS:</small> C		<small>MATERIAL:</small> A36, A53	<small>DRAWING TYPE:</small> ASSEMBLY DRAWING
<small>REMOVE BURRS AND BREAK EDGES .005</small> DO NOT SCALE THIS PRINT		<small>FINISH:</small> GALV A123	<small>WEIGHT:</small> 1361.27 LBS


- NOTES:
1. ALL METRIC DIMENSIONS ARE IN BRACKETS.
 2. WILL FIT MONOPOLES 15"-38" OD.




8 7 6 5 4 3 2 1




DETAIL A
SCALE 1 : 8



DETAIL B
SCALE 1 : 8




DETAIL C
SCALE 1 : 8



WITH ANTENNAS

NOTES:
1. ALL METRIC DIMENSIONS ARE IN BRACKETS.

<small>These drawings and specifications are the proprietary property of ANDREW CORPORATION and may be used only for the specific purpose authorized in writing by Andrew Corporation.</small>		<small>DRAWN BY:</small> MSM	<small>SHEET:</small> 3 of 3	<small>PART NUMBER:</small> MC-PK8-C
<small>ALL DIMENSIONS ARE IN INCHES U.O.S. TOLERANCES UNLESS OTHERWISE SPECIFIED:</small>		<small>CHECKED BY:</small> TP	<small>SCALE:</small> NTS	<small>DESCRIPTION:</small> 25" OD Snub Nose MT-196
<small>.X = ± .12 ANGLES ±2° .XX = ± .06 FRACTIONS ±1/32 .XXX = ± .03</small>		<small>DATE:</small> 10/18/11	<small>MATERIAL:</small> A36, A53	<small>DRAWING TYPE:</small> ASSEMBLY DRAWING
<small>REMOVE BURRS AND BREAK EDGES .005</small>		<small>REVISION:</small> C	<small>FINISH:</small> GALV A123	 WESTCHESTER, IL. 60154 U.S.A.
<small>DO NOT SCALE THIS PRINT</small>			<small>WEIGHT:</small> 1361.27 LBS	

8 7 6 5 4 3 2 1

Exhibit F

Power Density/RF Emissions Report

RADIO FREQUENCY EMISSIONS ANALYSIS REPORT
EVALUATION OF HUMAN EXPOSURE POTENTIAL
TO NON-IONIZING EMISSIONS

Dish Wireless Existing Facility

Site ID: 801486

BOBDL00036A

44 Ffyer Plac

Suffield, Connecticut 06078

June 24, 2021

EBI Project Number: 6221003219

Site Compliance Summary	
Compliance Status:	COMPLIANT
Site total MPE% of FCC general population allowable limit:	57.34%

June 24, 2021

Dish Wireless

Emissions Analysis for Site: 801486 - BOBDL00036A

EBI Consulting was directed to analyze the proposed Dish Wireless facility located at **44 Ffyer Plac** in **Suffield, Connecticut** for the purpose of determining whether the emissions from the Proposed Dish Wireless Antenna Installation located on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter ($\mu\text{W}/\text{cm}^2$). The number of $\mu\text{W}/\text{cm}^2$ calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits; therefore, it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) – (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general population may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general population would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

Public exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter ($\mu\text{W}/\text{cm}^2$). The general population exposure limits for the 600 MHz and 700 MHz frequency bands are approximately $400 \mu\text{W}/\text{cm}^2$ and $467 \mu\text{W}/\text{cm}^2$, respectively. The general population exposure limit for the 1900 MHz (PCS), 2100 MHz (AWS) and 11 GHz frequency bands is $1000 \mu\text{W}/\text{cm}^2$. Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.

Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure.

Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

CALCULATIONS

Calculations were done for the proposed Dish Wireless Wireless antenna facility located at 44 Ffyer Plac in Suffield, Connecticut using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. Since Dish Wireless is proposing highly focused directional panel antennas, which project most of the emitted energy out toward the horizon, all calculations were performed assuming a lobe representing the maximum gain of the antenna per the antenna manufacturer's supplied specifications, minus 10 dB for directional panel antennas and 20 dB for highly focused parabolic microwave dishes, was focused at the base of the tower. For this report, the sample point is the top of a 6-foot person standing at the base of the tower.

For all calculations, all equipment was calculated using the following assumptions:

- 1) 4 5G channels (600 MHz Band) were considered for each sector of the proposed installation. These Channels have a transmit power of 30 Watts per Channel.
- 2) 4 5G channels (PCS Band - 1900 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 40 Watts per Channel.
- 3) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 - Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.
- 4) For the following calculations, the sample point was the top of a 6-foot person standing at the base of the tower. The maximum gain of the antenna per the antenna manufacturer's supplied specifications, minus 10 dB for directional panel antennas and 20 dB for highly focused parabolic microwave dishes, was used in this direction. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.

- 5) The antennas used in this modeling are the JMA MX08FRO665-21 for the 600 MHz / 1900 MHz channel(s) in Sector A, the JMA MX08FRO665-21 for the 600 MHz / 1900 MHz channel(s) in Sector B, the JMA MX08FRO665-21 for the 600 MHz / 1900 MHz channel(s) in Sector C. This is based on feedback from the carrier with regard to anticipated antenna selection. All Antenna gain values and associated transmit power levels are shown in the Site Inventory and Power Data table below. The maximum gain of the antenna per the antenna manufacturer's supplied specifications, minus 10 dB for directional panel antennas and 20 dB for highly focused parabolic microwave dishes, was used for all calculations. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 6) The antenna mounting height centerline of the proposed antennas is 101 feet above ground level (AGL).
- 7) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.
- 8) All calculations were done with respect to uncontrolled / general population threshold limits.

Dish Wireless Site Inventory and Power Data

Sector:	A	Sector:	B	Sector:	C
Antenna #:	1	Antenna #:	1	Antenna #:	1
Make / Model:	JMA MX08FRO665-21	Make / Model:	JMA MX08FRO665-21	Make / Model:	JMA MX08FRO665-21
Frequency Bands:	600 MHz / 1900 MHz	Frequency Bands:	600 MHz / 1900 MHz	Frequency Bands:	600 MHz / 1900 MHz
Gain:	17.45 dBd / 22.65 dBd	Gain:	17.45 dBd / 22.65 dBd	Gain:	17.45 dBd / 22.65 dBd
Height (AGL):	101 feet	Height (AGL):	101 feet	Height (AGL):	101 feet
Channel Count:	8	Channel Count:	8	Channel Count:	8
Total TX Power (W):	280 Watts	Total TX Power (W):	280 Watts	Total TX Power (W):	280 Watts
ERP (W):	36,123.20	ERP (W):	36,123.20	ERP (W):	36,123.20
Antenna AI MPE %:	18.38%	Antenna BI MPE %:	18.38%	Antenna CI MPE %:	18.38%

Site Composite MPE %	
Carrier	MPE %
Dish Wireless (Max at Sector A):	18.38%
AT&T	24.55%
Verizon	9.06%
Metro PCS	2.17%
Nextel	0.96%
Sprint	2.22%
Site Total MPE % :	57.34%

Dish Wireless MPE % Per Sector	
Dish Wireless Sector A Total:	18.38%
Dish Wireless Sector B Total:	18.38%
Dish Wireless Sector C Total:	18.38%
Site Total MPE % :	
	57.34%

Dish Wireless Maximum MPE Power Values (Sector A)							
Dish Wireless Frequency Band / Technology (Sector A)	# Channels	Watts ERP (Per Channel)	Height (feet)	Total Power Density ($\mu\text{W}/\text{cm}^2$)	Frequency (MHz)	Allowable MPE ($\mu\text{W}/\text{cm}^2$)	Calculated % MPE
Dish Wireless 600 MHz 5G	4	1667.71	101.0	26.57	600 MHz 5G	400	6.64%
Dish Wireless 1900 MHz 5G	4	7363.09	101.0	117.32	1900 MHz 5G	1000	11.73%
						Total:	18.38%

• NOTE: Totals may vary by approximately 0.01% due to summation of remainders in calculations.

Summary

All calculations performed for this analysis yielded results that were **within** the allowable limits for general population exposure to RF Emissions.

The anticipated maximum composite contributions from the Dish Wireless facility as well as the site composite emissions value with regards to compliance with FCC's allowable limits for general population exposure to RF Emissions are shown here:

Dish Wireless Sector	Power Density Value (%)
Sector A:	18.38%
Sector B:	18.38%
Sector C:	18.38%
Dish Wireless Maximum MPE % (Sector A):	18.38%
Site Total:	57.34%
Site Compliance Status:	COMPLIANT

The anticipated composite MPE value for this site assuming all carriers present is **57.34%** of the allowable FCC established general population limit sampled at the ground level. This is based upon values listed in the Connecticut Siting Council database for existing carrier emissions.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.

Exhibit G

Letter of Authorization



4545 E River Rd, Suite 320
West Henrietta, NY 14586

Phone: (585) 445-5896
Fax: (724) 416-4461
www.crowncastle.com

Crown Castle Letter of Authorization

CT - CONNECTICUT SITING COUNCIL

Melanie A. Bachman
Executive Director
Connecticut Siting Council
10 Franklin Square
New Britain, CT 06051

Re: Tower Share Application
Crown Castle telecommunications site at:
44 FFYLER PLACE, SUFFIELD, CT 06078

CROWN ATLANTIC COMPANY LLC ("Crown Castle") hereby authorizes DISH WIRELESS, LLC, including their Agent, to act as our Agent in the processing of all zoning applications, building permits and approvals through the CT - CONNECTICUT SITING COUNCIL for the existing wireless communications site described below:

Crown Site ID/Name: 801486/CT SUFFIELD 2 CAC 801486
Customer Site ID: BOBDL00036A/CT-CCI-T-801486
Site Address: 44 Fyler Place, Suffield, CT 06078

Crown Castle



By:  Date: 7/29/2021
Richard Zajac
Site Acquisition Specialist

Exhibit H

Recipient Mailings



USPS TRACKING #

9405 5036 9930 0475 8594 61

Electronic Rate Approved #038555749

SHIP

TO: MELISSA M MACK
FIRST SELECTMAN
83 MOUNTAIN RD
SUFFIELD CT 06078-2041

Expected Delivery Date: 08/20/21

Re#: DS-801486

0006

C003

P

US POSTAGE
Flat Rate Env

usps.com 9405 5036 9930 0475 8594 61 0079 5000 0010 6078

\$7.95

08/17/2021

Click-N-Ship®

U.S. POSTAGE PAID
click-n-ship®

Mailed from 01566



Cut on dotted line.

Instructions

1. Each Click-N-Ship® label is unique. Labels are to be used as printed and used only once. DO NOT PHOTO COPY OR ALTER LABEL.
2. Place your label so it does not wrap around the edge of the package.
3. Adhere your label to the package. A self-adhesive label is recommended. If tape or glue is used, DO NOT TAPE OVER BARCODE. Be sure all edges are secure.
4. To mail your package with PC Postage®, you may schedule a Package Pickup online, hand to your letter carrier, take to a Post Office™, or drop in a USPS collection box.
5. Mail your package on the "Ship Date" you selected when creating this label.

Click-N-Ship® Label Record

USPS TRACKING # :
9405 5036 9930 0475 8594 61

Trans. #: 540963939	Priority Mail® Postage: \$7.95
Print Date: 08/17/2021	Total: \$7.95
Ship Date: 08/17/2021	
Expected Delivery Date: 08/20/2021	

From: DEBORAH CHASE
 NORTHEAST SITE SOLUTIONS
 420 MAIN ST
 STE 1
 STURBRIDGE MA 01566-1359


Re#: DS-801486

To: MELISSA M MACK
 FIRST SELECTMAN
 83 MOUNTAIN RD
 SUFFIELD CT 06078-2041

* Retail Pricing Priority Mail rates apply. There is no fee for USPS Tracking® service on Priority Mail service with use of this electronic rate shipping label. Refunds for unused postage paid labels can be requested online 30 days from the print date.



Thank you for shipping with the United States Postal Service!
 Check the status of your shipment on the USPS Tracking® page at usps.com



Cut on dotted line.

Instructions

- Each Click-N-Ship® label is unique. Labels are to be used as printed and used only once. DO NOT PHOTO COPY OR ALTER LABEL.
- Place your label so it does not wrap around the edge of the package.
- Adhere your label to the package. A self-adhesive label is recommended. If tape or glue is used, DO NOT TAPE OVER BARCODE. Be sure all edges are secure.
- To mail your package with PC Postage®, you may schedule a Package Pickup online, hand to your letter carrier, take to a Post Office™, or drop in a USPS collection box.
- Mail your package on the "Ship Date" you selected when creating this label.

Click-N-Ship® Label Record

USPS TRACKING # :
9405 5036 9930 0475 8594 78

Trans. #:	540963939	Priority Mail® Postage:	\$7.95
Print Date:	08/17/2021	Total:	\$7.95
Ship Date:	08/17/2021		
Expected			
Delivery Date:	08/20/2021		


From: DEBORAH CHASE
 NORTHEAST SITE SOLUTIONS
 420 MAIN ST
 STE 1
 STURBRIDGE MA 01566-1359
 Re#: DS-801486

To: JAMES TAYLOR
 ZONING ENFORCEMENT OFFICER
 83 MOUNTAIN RD
 SUFFIELD CT 06078-2041

* Retail Pricing Priority Mail rates apply. There is no fee for USPS Tracking® service on Priority Mail service with use of this electronic rate shipping label. Refunds for unused postage paid labels can be requested online 30 days from the print date.



Thank you for shipping with the United States Postal Service!
 Check the status of your shipment on the USPS Tracking® page at usps.com



**UNITED STATES
POSTAL SERVICE®**

Click-N-Ship®

P

usps.com
US POSTAGE
 Flat Rate Env
 \$7.95

9405 5036 9930 0475 8594 85 0079 5000 0031 4586

U.S. POSTAGE PAID
click-n-ship®

08/17/2021 Mailed from 01566


PRIORITY MAIL 2-DAY™

Expected Delivery Date: 08/20/21
 Re#: DS-801486
0006

R013

SHIP TO: RICH ZAJAC
 CROWN CASTLE
 4545 E RIVER RD
 STE 320
 W HENRIETTA NY 14586-9024

USPS TRACKING #



9405 5036 9930 0475 8594 85

Electronic Rate Approved #038555749



Cut on dotted line.

Instructions

1. Each Click-N-Ship® label is unique. Labels are to be used as printed and used only once. DO NOT PHOTO COPY OR ALTER LABEL.
2. Place your label so it does not wrap around the edge of the package.
3. Adhere your label to the package. A self-adhesive label is recommended. If tape or glue is used, DO NOT TAPE OVER BARCODE. Be sure all edges are secure.
4. To mail your package with PC Postage®, you may schedule a Package Pickup online, hand to your letter carrier, take to a Post Office™, or drop in a USPS collection box.
5. Mail your package on the "Ship Date" you selected when creating this label.

Click-N-Ship® Label Record

USPS TRACKING # :
9405 5036 9930 0475 8594 85

Trans. #: 540963939	Priority Mail® Postage: \$7.95
Print Date: 08/17/2021	Total: \$7.95
Ship Date: 08/17/2021	
Expected Delivery Date: 08/20/2021	

From: DEBORAH CHASE
 NORTHEAST SITE SOLUTIONS
 420 MAIN ST
 STE 1
 STURBRIDGE MA 01566-1359

Re#: DS-801486

To: RICH ZAJAC
 CROWN CASTLE
 4545 E RIVER RD
 STE 320
 W HENRIETTA NY 14586-9024

* Retail Pricing Priority Mail rates apply. There is no fee for USPS Tracking® service on Priority Mail service with use of this electronic rate shipping label. Refunds for unused postage paid labels can be requested online 30 days from the print date.



Thank you for shipping with the United States Postal Service!
 Check the status of your shipment on the USPS Tracking® page at usps.com

8014804



FISKDALE
458 MAIN ST
FISKDALE, MA 01518-9998
(800)275-8777

08/18/2021

12:49 PM

Product Qty Unit Price

Prepaid Mail 1 \$0.00

Suffield, CT 06078

Weight: 1 lb 7.80 oz

Acceptance Date:

Wed 08/18/2021

Tracking #:

9405 5036 9930 0475 8594 78

Prepaid Mail 1 \$0.00

Suffield, CT 06078

Weight: 1 lb 7.80 oz

Acceptance Date:

Wed 08/18/2021

Tracking #:

9405 5036 9930 0475 8594 61

Prepaid Mail 1 \$0.00

West Henrietta, NY 14586

Weight: 0 lb 2.00 oz

Acceptance Date:

Wed 08/18/2021

Tracking #:

9405 5036 9930 0475 8594 85

Grand Total: \$0.00
