



Crown Castle
3530 Toringdon Way
Suite 300
Charlotte, NC 28277

Tel: 704-405-6600

www.crowncastle.com

March 24, 2014

Melanie A. Bachman
Connecticut Siting Council
10 Franklin Square
New Britain, CT 06051

RE: Sprint PCS-Exempt Modification - Crown Site BU: 801486
Sprint PCS Site ID: CT43XC829
Located at: 44 Fyler Place, Suffield, CT 06078

Dear Ms. Bachman:

This letter and exhibits are submitted on behalf of Sprint PCS (Sprint). Sprint is making modifications to certain existing sites in its Connecticut system in order to implement their 2.5GHz LTE technology. Please accept this letter and exhibits as notification, pursuant to § 16-50j-73 of the Regulations of Connecticut State Agencies (“R.C.S.A.”), of construction that constitutes an exempt modification pursuant to R.C.S.A. § 16-50j-72(b)(2). In compliance with R.C.S.A. § 16-50j-73, a copy of this letter is being sent to Mr. Edward G. McAnaney, First Selectman for the Town of Suffield.

Sprint plans to modify the existing wireless communications facility owned by Crown Castle and located at **44 Fyler Place, Suffield, CT 06078**. Attached are a compound plan and elevation depicting the planned changes (Exhibit-1), and documentation of the structural sufficiency of the structure to accommodate the revised antenna configuration (Exhibit-2). Also included is a power density table report reflecting the modification to Sprint’s operations at the site (Exhibit-3).

The changes to the facility do not constitute a modification as defined in Connecticut General Statutes (“C.G.S.”) § 16-50i(d) because the general physical characteristics of the facility will not be significantly changed. Rather, the planned changes to the facility fall squarely within those activities explicitly provided for in the R.C.S.A. § 16-50j-72(b)(2).

1. The proposed modifications will not result in an increase in the height of the existing tower. Sprint’s additional antennas will be located at the same elevation on the existing tower.
2. There will be no proposed modifications to the ground and no extension of boundaries.
3. The proposed modifications will not increase noise levels at the facility by six decibels or more.

Melanie A. Bachman

March 24, 2014

Page 2

4. A Structural Modification Report confirming that the tower and foundation can support Sprint's proposed modifications is included as Exhibit-2.
5. The operation of the additional antennas will not increase radio frequency (RF) emissions at the facility to a level at or above the Federal Communications Commission (FCC) adopted safety standard. A cumulative General Power Density table report for Sprint's modified facility is included as Exhibit-3.

For the foregoing reasons, Sprint respectfully submits the proposed modifications to the above-reference telecommunications facility constitutes an exempt modification under R.C.S.A. § 16-50j-72(b)(2). Please send approval/rejection letter to Attn: Donna Neal.

Sincerely,



Jeff Barbadora
Real Estate Specialist

Enclosures


Tab 1: Exhibit-1: Compound plan and elevation depicting the planned changes

Tab 2: Exhibit-2: Structural Modification Report

Tab 3: Exhibit-3: General Power Density Table Report (RF Emissions Analysis Report)

cc: Mr. Edward G. McAnaney, First Selectman
Town of Suffield
83 Mountain Road
Suffield, CT 06078

Sprint



CROWN CASTLE

PROJECT: 2.5 EQUIPMENT DEPLOYMENT
 SITE NAME: WINDSOR LOCKS / CROWN
 SITE CASCADE: CT43XC829
 SITE NUMBER: 801486
 SITE ADDRESS: 44 FYLER PL.
 SUFFIELD, CT 06078
 SITE TYPE: MONOPOLE TOWER
 MARKET: NORTHERN CONNECTICUT

PLANS PREPARED FOR:
Sprint
 6580 Sprint Parkway
 Overland Park, Kansas 66251

PLANS PREPARED BY:
INFINIGY Design. Build. Deliver.
 1033 Watervliet Shaker Rd
 Albany, NY 12205
 Office # (518) 690-0790
 Fax # (518) 690-0793
 JOB NUMBER 333-000

MLA PARTNER:
CROWN CASTLE



DRAWING NOTICE:
 THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:	DESCRIPTION	DATE	BY	REV
ISSUED FOR CONSTRUCTION		3/3/14	MAP	0

SITE NAME:
WINDSOR LOCKS / CROWN

SITE CASCADE:
CT43XC829

SITE ADDRESS:
 44 FYLER PL.
 SUFFIELD, CT 06078

SHEET DESCRIPTION:
TITLE SHEET & PROJECT DATA

SHEET NUMBER:
T-1

SITE INFORMATION

TOWER OWNER:
 CROWN CASTLE
 2000 CORPORATE DRIVE
 CANONBURG, PA 15317

LATITUDE (NAD83):
 41° 58' 55.0164" N
 41.981949°

LONGITUDE (NAD83):
 72° 39' 24.984" W
 -72.65694°

COUNTY:
 HARTFORD

ZONING JURISDICTION:
 CONNECTICUT SITING COUNCIL

ZONING DISTRICT:
 TBD


POWER COMPANY:
 CONNECTICUT LIGHT & POWER
 (860) 947-2000

AAV PROVIDER:
 AT&T
 (800) 288-2020


SPRINT CM:
 PETER CULBERT
 (603) 203-6446
 (603) 969-0886
 peter.culbert@sprint.com

CROWN CASTLE CM:
 JASON D'AMICO
 (860) 209-0104
 JASON.D'AMICO@CROWNCastle.COM

AREA MAP



LOCATION MAP



PROJECT DESCRIPTION

SPRINT PROPOSES TO MODIFY AN EXISTING UNMANNED TELECOMMUNICATIONS FACILITY.

- INSTALL (3) PANEL ANTENNAS
- INSTALL (3) RRU'S TO TOWER
- INSTALL (27) JUMPER CABLES
- INSTALL (1) FIBER CABLE
- INSTALL (4) NEW BATTERIES IN EXISTING BBU CABINET
- INSTALL 2.5 EQUIPMENT IN EXISTING N.V. MMBS CABINET

THESE PLANS HAVE BEEN DEVELOPED FOR THE MODIFICATION OF AN EXISTING UNMANNED TELECOMMUNICATIONS FACILITY OWNED OR LEASED BY SPRINT IN ACCORDANCE WITH THE SCOPE OF WORK PROVIDED BY SPRINT. INFINIGY HAS INCORPORATED THIS SCOPE OF WORK IN THE PLANS. THESE PLANS ARE NOT FOR CONSTRUCTION UNLESS ACCOMPANIED BY A PASSING STRUCTURAL STABILITY ANALYSIS PREPARED BY A LICENSED STRUCTURAL ENGINEER. STRUCTURAL ANALYSIS MUST INCLUDE BOTH TOWER AND MOUNT.

APPLICABLE CODES

ALL WORK SHALL BE PERFORMED AND MATERIALS INSTALL IN ACCORDANCE WITH THE CURRENT EDITIONS OF THE FOLLOWING CODES AS ADOPTED BY THE LOCAL GOVERNING AUTHORITIES. NOTHING IN THESE PLANS IS TO BE CONSTRUED TO PERMIT WORK NOT CONFORMING TO THESE CODES.

- INTERNATIONAL BUILDING CODE (2012 IBC)
- TIA-EIA-222-F OR LATEST EDITION
- NFPA 780 - LIGHTNING PROTECTION CODE
- 2011 NATIONAL ELECTRIC CODE OR LATEST EDITION
- ANY OTHER NATIONAL OR LOCAL APPLICABLE CODES, MOST RECENT EDITIONS
- CT BUILDING CODE
- LOCAL BUILDING CODE
- CITY/COUNTY ORDINANCES

DRAWING INDEX

SHEET NO:	SHEET TITLE	REV
T-1	TITLE SHEET & PROJECT DATA	0
SP-1	SPRINT SPECIFICATIONS	0
SP-2	SPRINT SPECIFICATIONS	0
SP-3	SPRINT SPECIFICATIONS	0
A-1	SITE PLAN	0
A-2	TOWER ELEVATION & CABLE PLAN	0
A-3	ANTENNA LAYOUT & MOUNTING DETAILS	0
A-4	COLOR CODING AND NOTES	0
A-5	EQUIPMENT & MOUNTING DETAILS	0
A-6	CIVIL DETAILS	0
A-7	PLUMBING DIAGRAM	0
E-1	ELECTRICAL & GROUNDING PLAN	0
E-2	ELECTRICAL & GROUNDING DETAILS	0



THESE OUTLINE SPECIFICATIONS IN CONJUNCTION WITH THE SPRINT STANDARD CONSTRUCTION SPECIFICATIONS, INCLUDING CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

SECTION 01 100 – SCOPE OF WORK

PART 1 – GENERAL

- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE SPRINT CONSTRUCTION STANDARDS FOR WIRELESS SITES, CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
 - A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
 - B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.
- 1.3 PRECEDENCE: SHOULD CONFLICTS OCCUR BETWEEN THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES INCLUDING THE STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES AND THE CONSTRUCTION DRAWINGS, INFORMATION ON THE CONSTRUCTION DRAWINGS SHALL TAKE PRECEDENCE. NOTIFY SPRINT CONSTRUCTION MANAGER IF THIS OCCURS.
- 1.4 NATIONALLY RECOGNIZED CODES AND STANDARDS:
 - A. THE WORK SHALL COMPLY WITH APPLICABLE NATIONAL AND LOCAL CODES AND STANDARDS, LATEST EDITION, AND PORTIONS THEREOF, INCLUDED BUT NOT LIMITED TO THE FOLLOWING:
 1. GR-63-CORE NEBS REQUIREMENTS: PHYSICAL PROTECTION
 5. GR-78-CORE GENERIC REQUIREMENTS FOR THE PHYSICAL DESIGN AND MANUFACTURE OF TELECOMMUNICATIONS EQUIPMENT.
 3. GR-1089 CORE, ELECTROMAGNETIC COMPATIBILITY AND ELECTRICAL SAFETY -GENERIC CRITERIA FOR NETWORK TELECOMMUNICATIONS EQUIPMENT.
 4. NATIONAL FIRE PROTECTION ASSOCIATION CODES AND STANDARDS (NFPA) INCLUDING NFPA 70 (NATIONAL ELECTRICAL CODE - "NEC") AND NFPA 101 (LIFE SAFETY CODE).
 5. AMERICAN SOCIETY FOR TESTING OF MATERIALS (ASTM)
 6. INSTITUTE OF ELECTRONIC AND ELECTRICAL ENGINEERS (IEEE)
 7. AMERICAN CONCRETE INSTITUTE (ACI)
 8. AMERICAN WIRE PRODUCERS ASSOCIATION (AWPA)
 9. CONCRETE REINFORCING STEEL INSTITUTE (CRSI)
 10. AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)
 11. PORTLAND CEMENT ASSOCIATION (PCA)
 12. NATIONAL CONCRETE MASONRY ASSOCIATION (NCMA)
 13. BRICK INDUSTRY ASSOCIATION (BIA)
 14. AMERICAN WELDING SOCIETY (AWS)
 15. NATIONAL ROOFING CONTRACTORS ASSOCIATION (NRCA)
 16. SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)
 17. DOOR AND HARDWARE INSTITUTE (DHI)
 18. OCCUPATIONAL SAFETY AND HEALTH ACT (OSHA)
 19. APPLICABLE BUILDING CODES INCLUDING UNIFORM BUILDING CODE, SOUTHERN BUILDING CODE, BOCA, AND THE INTERNATIONAL BUILDING CODE.

1.5 DEFINITIONS:

- A. WORK: THE SUM OF TASKS AND RESPONSIBILITIES IDENTIFIED IN THE CONTRACT DOCUMENTS.
- B. COMPANY: SPRINT CORPORATION
- C. ENGINEER: SYNONYMOUS WITH ARCHITECT & ENGINEER AND "A&E". THE DESIGN PROFESSIONAL HAVING PROFESSIONAL RESPONSIBILITY FOR DESIGN OF THE PROJECT.
- D. CONTRACTOR: CONSTRUCTION CONTRACTOR; CONSTRUCTION VENDOR; INDIVIDUAL OR ENTITY WHO AFTER EXECUTION OF A CONTRACT IS BOUND TO ACCOMPLISH THE WORK.
- E. THIRD PARTY VENDOR OR AGENCY: A VENDOR OR AGENCY ENGAGED SEPARATELY BY THE COMPANY, A&E, OR CONTRACTOR TO PROVIDE MATERIALS OR TO ACCOMPLISH SPECIFIC TASKS RELATED TO BUT NOT INCLUDED IN THE WORK.
- F. OFCI: OWNER FURNISHED, CONTRACTOR INSTALLED EQUIPMENT.
- G. CONSTRUCTION MANAGER - ALL PROJECTS RELATED COMMUNICATION TO FLOW THROUGH SPRINT REPRESENTATIVE IN CHARGE OF PROJECT...

- 1.6 SITE FAMILIARITY: CONTRACTOR SHALL BE RESPONSIBLE FOR FAMILIARIZING HIMSELF WITH ALL CONTRACT DOCUMENTS, FIELD CONDITIONS AND DIMENSIONS PRIOR TO PROCEEDING WITH CONSTRUCTION. ANY DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE SPRINT CONSTRUCTION MANAGER PRIOR TO THE COMMENCEMENT OF WORK. NO COMPENSATION WILL BE AWARDED BASED ON CLAIM OF LACK OF KNOWLEDGE OR FIELD CONDITIONS.
- 1.7 POINT OF CONTACT: COMMUNICATION BETWEEN SPRINT AND THE CONTRACTOR SHALL FLOW THROUGH THE SINGLE SPRINT CONSTRUCTION MANAGER APPOINTED TO MANAGE THE PROJECT FOR SPRINT.
- 1.8 ON-SITE SUPERVISION: THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK AND SHALL BE RESPONSIBLE FOR CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES IN ACCORDANCE WITH THE CONTRACT DOCUMENTS. THE CONTRACTOR SHALL EMPLOY A COMPETENT SUPERINTENDENT WHO SHALL BE IN ATTENDANCE AT THE SITE AT ALL TIMES DURING PERFORMANCE OF THE WORK.
- 1.9 DRAWINGS, SPECIFICATIONS AND DETAILS REQUIRED AT JOBSITE: THE CONSTRUCTION CONTRACTOR SHALL MAINTAIN A FULL SET OF THE CONSTRUCTION DRAWINGS, STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES AND THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES AT THE JOBSITE FROM MOBILIZATION THROUGH CONSTRUCTION COMPLETION.
 - A. THE JOBSITE DRAWINGS, SPECIFICATIONS AND DETAILS SHALL BE CLEARLY MARKED DAILY IN RED PENCIL WITH ANY CHANGES IN CONSTRUCTION OVER WHAT IS DEPICTED IN THE DOCUMENTS. AT CONSTRUCTION COMPLETION, THIS JOBSITE MARKUP SET SHALL BE DELIVERED TO THE COMPANY OR COMPANY'S DESIGNATED REPRESENTATIVE TO BE FORWARDED TO THE COMPANY'S A&E VENDOR FOR PRODUCTION OF "AS-BUILT" DRAWINGS.
 - B. DETAILS ARE INTENDED TO SHOW DESIGN INTENT. MODIFICATIONS MAY BE REQUIRED TO SUIT JOB DIMENSIONS OR CONDITIONS, AND SUCH MODIFICATIONS SHALL BE INCLUDED AS PART OF THE WORK. CONTRACTOR SHALL NOTIFY SPRINT CONSTRUCTION MANAGER OF ANY VARIATIONS PRIOR TO PROCEEDING WITH THE WORK.
 - C. DIMENSIONS SHOWN ARE TO FINISH SURFACES UNLESS NOTED OTHERWISE. SPACING BETWEEN EQUIPMENT IS THE REQUIRED CLEARANCE. SHOULD THERE BE ANY QUESTIONS REGARDING THE CONTRACT DOCUMENTS, EXISTING CONDITIONS AND/OR DESIGN INTENT, THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING A CLARIFICATION FROM THE SPRINT CONSTRUCTION MANAGER PRIOR TO PROCEEDING WITH THE WORK.
- 1.10 USE OF JOB SITE: THE CONTRACTOR SHALL CONFINE ALL CONSTRUCTION AND RELATED OPERATIONS INCLUDING STAGING AND STORAGE OF MATERIALS AND EQUIPMENT, PARKING, TEMPORARY FACILITIES, AND WASTE STORAGE TO THE LEASE PARCEL UNLESS OTHERWISE PERMITTED BY THE CONTRACT DOCUMENTS.
- 1.11 UTILITIES SERVICES: WHERE NECESSARY TO CUT EXISTING PIPES, ELECTRICAL WIRES, CONDUITS, CABLES, ETC., OF UTILITY SERVICES, OR OF FIRE PROTECTION OR COMMUNICATIONS SYSTEMS, THEY SHALL BE CUT AND CAPPED AT SUITABLE PLACES OR WHERE SHOWN. ALL SUCH ACTIONS SHALL BE COORDINATED WITH THE UTILITY COMPANY INVOLVED.
- 1.12 PERMITS / FEES: WHEN REQUIRED THAT A PERMIT OR CONNECTION FEE BE PAID TO A PUBLIC UTILITY PROVIDER FOR NEW SERVICE TO THE CONSTRUCTION PROJECT, PAYMENT OF SUCH FEE SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.
- 1.13 CONTRACTOR SHALL TAKE ALL MEASURES AND PROVIDE ALL MATERIAL NECESSARY FOR PROTECTING EXISTING EQUIPMENT AND PROPERTY.
- 1.14 METHODS OF PROCEDURE (MOPS) FOR CONSTRUCTION: CONTRACTOR SHALL PERFORM WORK AS DESCRIBED IN THE FOLLOWING INSTALLATION AND COMMISSIONING MOPS.

NOTE: IN SHORT-FORM SPECIFICATIONS ON THE DRAWINGS, A/E TO INSERT LIST OF APPLICABLE MOPS INCLUDING EN-2012-001, EN-2013-002, EL-0568, AND TS-0193
- 1.15 USE OF ELECTRONIC PROJECT MANAGEMENT SYSTEMS:

PART 2 – PRODUCTS (NOT USED)

PART 3 – EXECUTION

- 3.1 TEMPORARY UTILITIES AND FACILITIES: THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL TEMPORARY UTILITIES AND FACILITIES NECESSARY EXCEPT AS OTHERWISE INDICATED IN THE CONSTRUCTION DOCUMENTS. TEMPORARY UTILITIES AND FACILITIES INCLUDE POTABLE WATER, HEAT, HVAC, ELECTRICITY, SANITARY FACILITIES, WASTE DISPOSAL FACILITIES, AND TELEPHONE/COMMUNICATION SERVICES. PROVIDE TEMPORARY UTILITIES AND FACILITIES IN ACCORDANCE WITH OSHA AND THE AUTHORITY HAVING JURISDICTION. CONTRACTOR MAY UTILIZE THE COMPANY ELECTRICAL SERVICE IN THE COMPLETION OF THE WORK WHEN IT BECOMES AVAILABLE. USE OF THE LESSORS OR SITE OWNER'S UTILITIES OR FACILITIES IS EXPRESSLY FORBIDDEN EXCEPT AS OTHERWISE ALLOWED IN THE CONTRACT DOCUMENTS.
- 3.2 ACCESS TO WORK: THE CONTRACTOR SHALL PROVIDE ACCESS TO THE JOB SITE FOR AUTHORIZED COMPANY PERSONNEL AND AUTHORIZED REPRESENTATIVES OF THE ARCHITECT/ENGINEER DURING ALL PHASES OF THE WORK.
- 3.3 TESTING: REQUIREMENTS FOR TESTING BY THIS CONTRACTOR SHALL BE AS INDICATED HEREWITH, ON THE CONSTRUCTION DRAWINGS, AND IN THE INDIVIDUAL SECTIONS OF THESE SPECIFICATIONS. SHOULD COMPANY CHOOSE TO ENGAGE ANY THIRD-PARTY TO CONDUCT ADDITIONAL TESTING, THE CONTRACTOR SHALL COOPERATE WITH AND PROVIDE A WORK AREA FOR COMPANY'S TEST AGENCY.
- 3.4 DIMENSIONS: VERIFY DIMENSIONS INDICATED ON DRAWINGS WITH FIELD DIMENSIONS BEFORE FABRICATION OR ORDERING OF MATERIALS. DO NOT SCALE DRAWINGS.

3.5 EXISTING CONDITIONS: NOTIFY THE SPRINT CONSTRUCTION MANAGER OF EXISTING CONDITIONS DIFFERING FROM THOSE INDICATED ON THE DRAWINGS. DO NOT REMOVE OR ALTER STRUCTURAL COMPONENTS WITHOUT PRIOR WRITTEN APPROVAL FROM THE ARCHITECT AND ENGINEER.

SECTION 01 200 – COMPANY FURNISHED MATERIAL AND EQUIPMENT

PART 1 – GENERAL

- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
 - A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
 - B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.

PART 2 – PRODUCTS (NOT USED)

PART 3 – EXECUTION

- 3.1 RECEIPT OF MATERIAL AND EQUIPMENT:
 - A. A COMPANY FURNISHED MATERIAL AND EQUIPMENT IS IDENTIFIED ON THE RF DATA SHEET IN THE CONSTRUCTION DOCUMENTS.
 - B. THE CONTRACTOR IS RESPONSIBLE FOR SPRINT PROVIDED MATERIAL AND EQUIPMENT AND UPON RECEIPT SHALL:
 1. ACCEPT DELIVERIES AS SHIPPED AND TAKE RECEIPT.
 2. VERIFY COMPLETENESS AND CONDITION OF ALL DELIVERIES.
 3. TAKE RESPONSIBILITY FOR EQUIPMENT AND PROVIDE INSURANCE PROTECTION AS REQUIRED IN AGREEMENT.
 4. RECORD ANY DEFECTS OR DAMAGES AND WITHIN TWENTY-FOUR HOURS AFTER RECEIPT, REPORT TO SPRINT OR ITS DESIGNATED PROJECT REPRESENTATIVE OF SUCH.
 5. PROVIDE SECURE AND NECESSARY WEATHER PROTECTED WAREHOUSING.
 6. COORDINATE SAFE AND SECURE TRANSPORTATION OF MATERIAL AND EQUIPMENT, DELIVERING AND OFF-LOADING FROM CONTRACTOR'S WAREHOUSE TO SITE.
- 3.2 DELIVERABLES:
 - A. COMPLETE SHIPPING AND RECEIPT DOCUMENTATION IN ACCORDANCE WITH COMPANY PRACTICE.
 - B. IF APPLICABLE, COMPLETE LOST/STOLEN/DAMAGED DOCUMENTATION REPORT AS NECESSARY IN ACCORDANCE WITH COMPANY PRACTICE, AND AS DIRECTED BY COMPANY.
 - C. UPLOAD DOCUMENTATION INTO SPRINT SITE MANAGEMENT SYSTEM (SMS) AND/OR PROVIDE HARD COPY DOCUMENTATION AS REQUESTED.

SECTION 01 300 – CELL SITE CONSTRUCTION CO.

PART 1 – GENERAL

- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
 - A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
 - B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.
- 1.3 NOTICE TO PROCEED
 - A. NO WORK SHALL COMMENCE PRIOR TO COMPANY'S WRITTEN NOTICE TO PROCEED AND THE ISSUANCE OF THE WORK ORDER.
 - B. UPON RECEIVING NOTICE TO PROCEED, CONTRACTOR SHALL FULLY PERFORM ALL WORK NECESSARY TO PROVIDE SPRINT WITH AN OPERATIONAL WIRELESS FACILITY.

TOWER OWNER NOTIFICATION
 ONCE THE CONTRACTOR HAS RECEIVED AND ACCEPTED THE NOTICE TO PROCEED, CONTRACTOR WILL CONTACT THE CROWN CASTLE CONSTRUCTION MANAGER OF RECORD (NOTED ON THE FIRST PAGE ON THIS CONSTRUCTION DRAWING) A MINIMUM OF 48 HOURS PRIOR TO WORK START. UPON ARRIVAL TO THE JOB SITE, CONTRACTOR CREW IS REQUIRED CALL 1-800-788-7011 TO NOTIFY THE CROWN CASTLE NOC WORK HAS BEGUN.

PART 2 – PRODUCTS (NOT USED)

PART 3 – EXECUTION

- 3.1 FUNCTIONAL REQUIREMENTS:
 - A. THE ACTIVITIES DESCRIBED IN THIS PARAGRAPH REPRESENT MINIMUM ACTIONS AND PROCESSES REQUIRED TO SUCCESSFULLY COMPLETE THE WORK. THE ACTIVITIES DESCRIBED ARE NOT EXHAUSTIVE, AND CONTRACTOR SHALL TAKE ANY AND ALL ACTIONS AS NECESSARY TO SUCCESSFULLY COMPLETE THE CONSTRUCTION OF A FULLY FUNCTIONING WIRELESS FACILITY AT THE SITE IN ACCORDANCE WITH COMPANY PROCESSES.
 - B. SUBMIT SPECIFIC DOCUMENTATION AS INDICATED HEREIN, AND OBTAIN REQUIRED APPROVALS WHILE THE WORK IS BEING PERFORMED.
 - C. MANAGE AND CONDUCT ALL FIELD CONSTRUCTION SERVICE RELATED ACTIVITIES
 - D. PROVIDE CONSTRUCTION ACTIVITIES TO THE EXTENT REQUIRED BY THE CONTRACT DOCUMENTS, INCLUDING BUT NOT LIMITED TO THE FOLLOWING:

PLANS PREPARED FOR:



PLANS PREPARED BY:



MLA PARTNER:



ENGINEERING LICENSE:



DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR CONSTRUCTION	3/3/14	MAP	0

SITE NAME:

WINDSOR LOCKS / CROWN

SITE CASCADE:

CT43XC829

SITE ADDRESS:

44 FYLER PL.
SUFFIELD, CT 06078

SHEET DESCRIPTION:

SPRINT SPECIFICATIONS

SHEET NUMBER:

SP-1

CONTINUE FROM SP-1

1. PERFORM ANY REQUIRED SITE ENVIRONMENTAL MITIGATION.
2. PREPARE GROUND SITES; PROVIDE DE-GRUBBING; AND ROUGH AND FINAL GRADING, AND COMPOUND SURFACE TREATMENTS.
3. MANAGE AND CONDUCT ALL ACTIVITIES FOR INSTALLATION OF UTILITIES INCLUDING ELECTRICAL AND TELCO BACKHAUL.
4. INSTALL UNDERGROUND FACILITIES INCLUDING UNDERGROUND POWER AND COMMUNICATIONS CONDUITS, AND UNDERGROUND GROUNDING SYSTEM.
5. INSTALL ABOVE GROUND GROUNDING SYSTEMS.
6. PROVIDE NEW HVAC INSTALLATIONS AND MODIFICATIONS.
7. INSTALL "H-FRAMES", CABINETS AND SHELTERS AS INDICATED.
8. INSTALL ROADS, ACCESS WAYS, CURBS AND DRAINS AS INDICATED.
9. ACCOMPLISH REQUIRED MODIFICATION OF EXISTING FACILITIES.
10. PROVIDE ANTENNA SUPPORT STRUCTURE FOUNDATIONS.
11. PROVIDE SLABS AND EQUIPMENT PLATFORMS.
12. INSTALL COMPOUND FENCING, SIGHT SHIELDING, LANDSCAPING AND ACCESS BARRIERS.
13. PERFORM INSPECTION AND MATERIAL TESTING AS REQUIRED HEREINAFTER.
14. CONDUCT SITE RESISTANCE TO EARTH TESTING AS REQUIRED HEREINAFTER.
15. INSTALL FIXED GENERATOR SETS AND OTHER STANDBY POWER SOLUTIONS.
16. INSTALL TOWERS, ANTENNA SUPPORT STRUCTURES AND PLATFORMS ON EXISTING TOWERS AS REQUIRED.
17. INSTALL CELL SITE RADIOS, MICROWAVE, GPS, COAXIAL MAINLINE, ANTENNAS, CROSS BAND COUPLERS, TOWER TOP AMPLIFIERS, LOW NOISE AMPLIFIERS AND RELATED EQUIPMENT.
18. PERFORM, DOCUMENT, AND CLOSE OUT ANY CONSTRUCTION CONTROL DOCUMENTS THAT MAY BE REQUIRED BY GOVERNMENT AGENCIES AND LANDLORDS.
19. PERFORM ANTENNA AND COAX SWEEP TESTING AND MAKE ANY AND ALL NECESSARY CORRECTIONS.
20. REMAIN ON SITE MOBILIZED THROUGHOUT HAND-OFF AND INTEGRATION TO ASSIST AS NEEDED UNTIL SITE IS DEEMED SUBSTANTIALLY COMPLETE AND PLACED "ON AIR."

3.2 GENERAL REQUIREMENTS FOR CIVIL CONSTRUCTION:

- A. CONTRACTOR SHALL KEEP THE SITE FREE FROM ACCUMULATING WASTE MATERIAL, DEBRIS, AND TRASH. AT THE COMPLETION OF THE WORK, CONTRACTOR SHALL REMOVE FROM THE SITE ALL REMAINING RUBBISH, IMPLEMENTS, TEMPORARY FACILITIES, AND SURPLUS MATERIALS.
- B. EQUIPMENT ROOMS SHALL AT ALL TIMES BE MAINTAINED "BROOM CLEAN" AND CLEAR OF DEBRIS.
- C. CONTRACTOR SHALL TAKE ALL REASONABLE PRECAUTIONS TO DISCOVER AND LOCATE ANY HAZARDOUS CONDITION.
 1. IN THE EVENT CONTRACTOR ENCOUNTERS ANY HAZARDOUS CONDITION WHICH HAS NOT BEEN ABATED OR OTHERWISE MITIGATED, CONTRACTOR AND ALL OTHER PERSONS SHALL IMMEDIATELY STOP WORK IN THE AFFECTED AREA AND NOTIFY COMPANY IN WRITING. THE WORK IN THE AFFECTED AREA SHALL NOT BE RESUMED EXCEPT BY WRITTEN NOTIFICATION BY COMPANY.
 2. CONTRACTOR AGREES TO USE CARE WHILE ON THE SITE AND SHALL NOT TAKE ANY ACTION THAT WILL OR MAY RESULT IN OR CAUSE THE HAZARDOUS CONDITION TO BE FURTHER RELEASED IN THE ENVIRONMENT, OR TO FURTHER EXPOSE INDIVIDUALS TO THE HAZARD.
- D. CONTRACTOR'S ACTIVITIES SHALL BE RESTRICTED TO THE PROJECT LIMITS. SHOULD AREAS OUTSIDE THE PROJECT LIMITS BE AFFECTED BY CONTRACTOR'S ACTIVITIES, CONTRACTOR SHALL IMMEDIATELY RETURN THEM TO ORIGINAL CONDITION
- E. CONDUCT TESTING AS REQUIRED HEREIN.

3.3 DELIVERABLES:

- A. CONTRACTOR SHALL REVIEW, APPROVE, AND SUBMIT TO SPRINT SHOP DRAWINGS, PRODUCT DATA, SAMPLES, AND SIMILAR SUBMITTALS AS REQUIRED HEREINAFTER
- B. PROVIDE DOCUMENTATION INCLUDING, BUT NOT LIMITED TO, THE FOLLOWING. DOCUMENTATION SHALL BE FORWARDED IN ORIGINAL FORMAT AND/OR UPLOADED INTO SMS.
 1. ALL CORRESPONDENCE AND PRELIMINARY CONSTRUCTION REPORTS.
 2. PROJECT PROGRESS REPORTS.
 3. CIVIL CONSTRUCTION START DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
 4. ELECTRICAL SERVICE COMPLETION DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).

5. LINES AND ANTENNA INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
6. POWER INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
7. TELCO READY DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
8. PPC (OR SHELTER) INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
9. TOWER CONSTRUCTION START DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
10. TOWER CONSTRUCTION COMPLETE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
11. BTS AND RADIO EQUIPMENT DELIVERED AT SITE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
12. NETWORK OPERATIONS HANDOFF CHECKLIST (HOC WALK) COMPLETE (UPLOAD FORM IN SMS)
13. CIVIL CONSTRUCTION COMPLETE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
14. SITE CONSTRUCTION PROGRESS PHOTOS UNLOADED INTO SMS.

SECTION 01 400 - SUBMITTALS & TESTS

PART 1 - GENERAL

- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
 - A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
 - B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HERewith.
- 1.3 SUBMITTALS:
 - A. THE WORK IN ALL ASPECTS SHALL COMPLY WITH THE CONSTRUCTION DRAWINGS AND THESE SPECIFICATIONS.
 - B. SUBMIT THE FOLLOWING TO COMPANY REPRESENTATIVE FOR APPROVAL
 1. CONCRETE MIX-DESIGNS FOR TOWER FOUNDATIONS, ANCHORS PIERS, AND CONCRETE PAVING.
 2. CONCRETE BREAK TESTS AS SPECIFIED HEREIN.
 3. SPECIAL FINISHES FOR INTERIOR SPACES, IF ANY.
 4. ALL EQUIPMENT AND MATERIALS SO IDENTIFIED ON THE CONSTRUCTION DRAWINGS.
 5. CHEMICAL GROUNDING DESIGN
 - D. ALTERNATES: AT THE COMPANY'S REQUEST, ANY ALTERNATIVES TO THE MATERIALS OR METHODS SPECIFIED SHALL BE SUBMITTED TO SPRINT'S CONSTRUCTION MANAGER FOR APPROVAL PRIOR TO BEING SHIPPED TO SITE. SPRINT WILL REVIEW AND APPROVE ONLY THOSE REQUESTS MADE IN WRITING. NO VERBAL APPROVALS WILL BE CONSIDERED. SUBMITTAL FOR APPROVAL SHALL INCLUDE A STATEMENT OF COST REDUCTION PROPOSED FOR USE OF ALTERNATE PRODUCT.

1.4 TESTS AND INSPECTIONS:

- A. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CONSTRUCTION TESTS, INSPECTIONS AND PROJECT DOCUMENTATION.
- B. CONTRACTOR SHALL ACCOMPLISH TESTING INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
 1. COAX SWEEPS AND FIBER TESTS PER TS-0200 REV 4 ANTENNA LINE ACCEPTANCE STANDARDS.
 2. AZIMUTH AND DOWNTILT USING ELECTRONIC COMMERCIAL MADE-FOR-THE-PURPOSE ANTENNA ALIGNMENT TOOL.
 3. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN SITE INSPECTION ACTIVITIES AND/OR AS A RESULT OF TESTING.
- C. REQUIRED CLOSEOUT DOCUMENTATION INCLUDES, BUT IS NOT LIMITED TO THE FOLLOWING:
 1. AZIMUTH, DOWNTILT, AZIMUTH, AGL - UPLOAD REPORT FROM ANTENNA ALIGNMENT TOOL TO SITERRA TASK 465. INSTALLED AZIMUTH, DOWNTILT, AND AZIMUTH MUST CONFORM TO THE RF DATA SHEETS. SWEEP AND FIBER TESTS
 2. SCANABLE BARCODE PHOTOGRAPHS OF TOWER TOP AND INACCESSIBLE SERIALIZED EQUIPMENT
 3. ALL AVAILABLE JURISDICTIONAL INFORMATION
 4. PDF SCAN OF REDLINES PRODUCED IN FIELD

5. ELECTRONIC AS-BUILT DRAWINGS IN AUTOCAD AND PDF FORMATS. ANY FIELD CHANGE MUST BE REFLECTED BY MODIFYING THE PLANS, ELEVATIONS, AND DETAILS IN THE DRAWING SETS. GENERAL NOTES INDICATING MODIFICATIONS WILL NOT BE ACCEPTED. CHANGES SHALL BE HIGHLIGHTED AS "CLOUDS" IDENTIFIED AS THE "AS-BUILT" CONDITION.
6. LIEN WAIVERS
7. FINAL PAYMENT APPLICATION
8. REQUIRED FINAL CONSTRUCTION PHOTOS
9. CONSTRUCTION AND COMMISSIONING CHECKLIST COMPLETE WITH NO DEFICIENT ITEMS
10. ALL POST NTP TASKS INCLUDING DOCUMENT UPLOADS COMPLETED IN SITERRA (SPRINTS DOCUMENT REPOSITORY OF RECORD).

1.5 COMMISSIONING: PERFORM ALL COMMISSIONING AS REQUIRED BY APPLICABLE MOPs

1.6 INTEGRATION: PERFORM ALL INTEGRATION ACTIVITIES AS REQUIRED BY APPLICABLE MOPs

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION

3.1 REQUIREMENTS FOR TESTING:

- A. THIRD PARTY TESTING AGENCY:
 1. WHEN THE USE OF A THIRD PARTY INDEPENDENT TESTING AGENCY IS REQUIRED, THE AGENCY THAT IS SELECTED MUST PERFORM SUCH WORK ON A REGULAR BASIS IN THE STATE WHERE THE PROJECT IS LOCATED AND HAVE A THOROUGH UNDERSTANDING OF LOCAL AVAILABLE MATERIALS, INCLUDING THE SOIL, ROCK, AND GROUNDWATER CONDITIONS.
 2. THE THIRD PARTY TESTING AGENCY IS TO BE FAMILIAR WITH THE APPLICABLE REQUIREMENTS FOR THE TESTS TO BE DONE, EQUIPMENT TO BE USED, AND ASSOCIATED HEALTH AND SAFETY ISSUES.
 3. EXPERIENCE IN SOILS, CONCRETE, MASONRY, AGGREGATE, AND ASPHALT TESTING USING ASTM, AASHTO, AND OTHER METHODS IS NEEDED.
 4. EXPERIENCE IN SOILS, CONCRETE, MASONRY, AGGREGATE, AND ASPHALT TESTING USING ASTM, AASHTO, AND OTHER METHODS IS NEEDED.

3.2 REQUIRED TESTS:

- A. CONTRACTOR SHALL ACCOMPLISH TESTING INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
 1. CONCRETE CYLINDER BREAK TESTS FOR THE TOWER AND ANCHOR FOUNDATIONS AS SPECIFIED IN SECTION: PORTLAND CEMENT CONCRETE PAVING.
 2. ASPHALT ROADWAY COMPACTED THICKNESS, SURFACE SMOOTHNESS, AND COMPACTED DENSITY TESTING AS SPECIFIED IN SECTION: HOT MIX ASPHALT PAVING.
 3. FIELD QUALITY CONTROL TESTING AS SPECIFIED IN SECTION: PORTLAND CEMENT CONCRETE PAVING.
 4. TESTING REQUIRED UNDER SECTION: AGGREGATE BASE FOR ACCESS ROADS, PADS AND ANCHOR LOCATIONS
 5. STRUCTURAL BACKFILL COMPACTION TESTS FOR THE TOWER FOUNDATION.
 6. SITE RESISTANCE TO EARTH TESTING PER EXHIBIT: CELL SITE GROUNDING SYSTEM DESIGN.
 7. ANTENNA AND COAX SWEEP TESTS PER EXHIBIT: ANTENNA TRANSMISSION LINE ACCEPTANCE STANDARDS.
 8. GROUNDING AT ANTENNA MASTS FOR GPS AND ANTENNAS
 9. ALL OTHER TESTS REQUIRED BY COMPANY OR JURISDICTION.

3.3 REQUIRED INSPECTIONS

- A. SCHEDULE INSPECTIONS WITH COMPANY REPRESENTATIVE.
- B. CONDUCT INSPECTIONS INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
 1. GROUNDING SYSTEM INSTALLATION PRIOR TO EARTH CONCEALMENT DOCUMENTED WITH DIGITAL PHOTOGRAPHS BY CONTRACTOR, APPROVED BY A&E OR SPRINT REPRESENTATIVE.
 2. FORMING FOR CONCRETE AND REBAR PLACEMENT PRIOR TO POUR DOCUMENTED WITH DIGITAL PHOTOGRAPHS BY CONTRACTOR, APPROVED BY A&E OR SPRINT REPRESENTATIVE.
 3. COMPACTION OF BACKFILL MATERIALS; AGGREGATE BASE FOR ROADS, PADS, AND ANCHORS; ASPHALT PAVING; AND SHAFT BACKFILL FOR CONCRETE AND WOOD POLES, BY INDEPENDENT THIRD PARTY AGENCY.
 4. PRE- AND POST-CONSTRUCTION ROOFTOP AND STRUCTURAL INSPECTIONS ON EXISTING FACILITIES.
 5. TOWER ERECTION SECTION STACKING AND PLATFORM ATTACHMENT DOCUMENTED BY DIGITAL PHOTOGRAPHS BY THIRD PARTY AGENCY.
 6. ANTENNA AZIMUTH, DOWN TILT AND PER SUNLIGHT TOOL SUNSIGHT INSTRUMENTS - ANTENNA ALIGNMENT TOOL (AAT)

PLANS PREPARED FOR:



PLANS PREPARED BY:



MLA PARTNER:



ENGINEERING LICENSE:



DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR CONSTRUCTION	3/3/14	MAP	0

SITE NAME:

WINDSOR LOCKS / CROWN

SITE CASCADE:

CT43XC829

SITE ADDRESS:

44 FYLER PL.
SUFFIELD, CT 06078

SHEET DESCRIPTION:

SPRINT SPECIFICATIONS

SHEET NUMBER:

SP-2

CONTINUE FROM SP-2

7. VERIFICATION DOCUMENTED WITH THE ANTENNA CHECKLIST REPORT, BY A&E, SITE DEVELOPMENT REP, OR RF REP.
 8. FINAL INSPECTION CHECKLIST AND HANDOFF WALK (HOC). SIGNED FORM SHOWING ACCEPTANCE BY FIELD OPS IS TO BE UPLOADED INTO SMS.
 9. COAX SWEEP AND FIBER TESTING DOCUMENTS SUBMITTED VIA SMS FOR RF APPROVAL.
 10. SCAN-ABLE BARCODE PHOTOGRAPHS OF TOWER TOP AND INACCESSIBLE SERIALIZED EQUIPMENT
 11. ALL AVAILABLE JURISDICTIONAL INFORMATION
 12. PDF SCAN OF REDLINES PRODUCED IN FIELD
- C. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN SITE INSPECTION ACTIVITIES AND/OR AS A RESULT OF TESTING.
- D. CONSTRUCTION INSPECTIONS AND CORRECTIVE MEASURES SHALL BE DOCUMENTED BY THE CONTRACTOR WITH WRITTEN REPORTS AND PHOTOGRAPHS. PHOTOGRAPHS MUST BE DIGITAL AND OF SUFFICIENT QUALITY TO CLEARLY SHOW THE SITE CONSTRUCTION. PHOTOGRAPHS MUST CLEARLY IDENTIFY THE PHOTOGRAPHED ITEM AND BE LABELED WITH THE SITE CASCADE NUMBER, SITE NAME, DESCRIPTION, AND DATE.
- 3.4 DELIVERABLES: TEST AND INSPECTION REPORTS AND CLOSEOUT DOCUMENTATION SHALL BE UPLOADED TO THE SMS AND/OR FORWARDED TO SPRINT FOR INCLUSION INTO THE PERMANENT SITE FILES.
- A. THE FOLLOWING TEST AND INSPECTION REPORTS SHALL BE PROVIDED AS APPLICABLE.
1. CONCRETE MIX AND CYLINDER BREAK REPORTS.
 2. STRUCTURAL BACKFILL COMPACTION REPORTS.
 3. SITE RESISTANCE TO EARTH TEST.
 4. ANTENNA AZIMUTH AND DOWN TILT VERIFICATION
 5. TOWER ERECTION INSPECTIONS AND MEASUREMENTS DOCUMENTING TOWER INSTALLED PER SUPPLIER'S REQUIREMENTS AND THE APPLICABLE SECTIONS HEREIN.
 6. COAX CABLE SWEEP TESTS PER COMPANY'S "ANTENNA LINE ACCEPTANCE STANDARDS".
- B. REQUIRED CLOSEOUT DOCUMENTATION INCLUDES THE FOLLOWING;
1. TEST WELLS AND TRENCHES: PHOTOGRAPHS OF ALL TEST WELLS; PHOTOGRAPHS SHOWING ALL OPEN EXCAVATIONS AND TRENCHING PRIOR TO BACKFILLING SHOWING A TAPE MEASURE VISIBLE IN THE EXCAVATIONS INDICATING DEPTH.
 2. CONDUITS, CONDUCTORS AND GROUNDING: PHOTOGRAPHS SHOWING TYPICAL INSTALLATION OF CONDUCTORS AND CONNECTORS; PHOTOGRAPHS SHOWING TYPICAL BEND RADIUS OF INSTALLED GROUND WIRES AND GROUND ROD SPACING;
 3. CONCRETE FORMS AND REINFORCING: CONCRETE FORMING AT TOWER AND EQUIPMENT/SHELTER PAD/FOUNDATIONS - PHOTOGRAPHS SHOWING ALL REINFORCING STEEL, UTILITY AND CONDUIT STUB OUTS; PHOTOGRAPHS SHOWING CONCRETE POUR OF SHELTER SLAB/FOUNDATION, TOWER FOUNDATION AND GUY ANCHORS WITH VIBRATOR IN USE; PHOTOGRAPHS SHOWING EACH ANCHOR ON GUYED TOWERS, BEFORE CONCRETE POUR.
 4. TOWER, ANTENNAS AND MAINLINE: INSPECTION AND PHOTOGRAPHS OF SECTION STACKING; INSPECTION AND PHOTOGRAPHS OF PLATFORM COMPONENT ATTACHMENT POINTS; PHOTOGRAPHS OF TOWER TOP GROUNDING; PHOTOS OF TOWER COAX LINE COLOR CODING AT THE TOP AND AT GROUND LEVEL; INSPECTION AND PHOTOGRAPHS OF OPERATIONAL OF TOWER LIGHTING, AND PLACEMENT OF FAA REGISTRATION SIGN; PHOTOGRAPHS SHOWING ADDITIONAL GROUNDING POINTS FOR TOWERS GREATER THAN 200 FEET.; PHOTOS OF ANTENNA GROUND BAR, EQUIPMENT GROUND BAR, AND MASTER GROUND BAR; PHOTOS OF GPS ANTENNA(S); PHOTOS OF EACH SECTOR OF ANTENNAS; ONE PHOTOGRAPH LOOKING AT THE SECTOR AND ONE FROM BEHIND SHOWING THE PROJECTED COVERAGE AREA; PHOTOS OF COAX WEATHERPROOFING - TOP AND BOTTOM; PHOTOS OF COAX GROUNDING--TOP AND BOTTOM; PHOTOS OF ANTENNA AND MAST GROUNDING; PHOTOS OF COAX CABLE ENTRY INTO SHELTER; PHOTOS OF PLATFORM MECHANICAL CONNECTIONS TO TOWER/MONOPOLE.
 5. ROOF TOPS: PRE-CONSTRUCTION AND POST-CONSTRUCTION VISUAL INSPECTION AND PHOTOGRAPHS OF THE ROOF AND INTERIOR TO DETERMINE AND DOCUMENT CONDITIONS; ROOF TOP CONSTRUCTION INSPECTIONS AS REQUIRED BY THE JURISDICTION; PHOTOGRAPHS OF CABLE TRAY AND/OR ICE BRIDGE; PHOTOGRAPHS OF DOGHOUSE/CABLE EXIT FROM ROOF;
 6. SITE LAYOUT - PHOTOGRAPHS OF THE OVERALL COMPOUND, INCLUDING EQUIPMENT PLATFORM FROM ALL FOUR CORNERS.
 7. FINISHED UTILITIES: CLOSE-UP PHOTOGRAPHS OF THE PPC BREAKER PANEL; CLOSE-UP PHOTOGRAPH OF THE INSIDE OF THE TELCO PANEL AND NIU; CLOSE-UP PHOTOGRAPH OF THE POWER METER AND DISCONNECT; PHOTOS OF POWER AND TELCO ENTRANCE TO COMPANY ENCLOSURE; PHOTOGRAPHS AT METER BOX AND/OR FACILITY DISTRIBUTION PANEL.
 8. REQUIRED MATERIALS CERTIFICATIONS: CONCRETE MIX DESIGNS; MILL CERTIFICATION FOR ALL REINFORCING AND STRUCTURAL STEEL; AND ASPHALT PAVING MIX DESIGN.
 9. ANY AND ALL SUBMITTALS BY THE JURISDICTION OR COMPANY.

SECTION 01 400 - SUBMITTALS & TESTS

PART 1 - GENERAL

- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
 - A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
 - B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION

- 3.1 WEEKLY REPORTS:
 - A. CONTRACTOR SHALL PROVIDE SPRINT WITH WEEKLY REPORTS SHOWING PROJECT STATUS. THIS STATUS REPORT FORMAT WILL BE PROVIDED TO THE CONTRACTOR BY SPRINT. THE REPORT WILL CONTAIN SITE ID NUMBER, THE MILESTONES FOR EACH SITE, INCLUDING THE BASELINE DATE, ESTIMATED COMPLETION DATE AND ACTUAL COMPLETION DATE.
 - B. REPORT INFORMATION WILL BE TRANSMITTED TO SPRINT VIA ELECTRONIC MEANS AS REQUIRED. THIS INFORMATION WILL PROVIDE A BASIS FOR PROGRESS MONITORING AND PAYMENT.
- 3.2 PROJECT CONFERENCE CALLS:
 - A. SPRINT MAY HOLD WEEKLY PROJECT CONFERENCE CALLS. CONTRACTOR WILL BE REQUIRED TO COMMUNICATE SITE STATUS, MILESTONE COMPLETIONS AND UPCOMING MILESTONE PROJECTIONS, AND ANSWER ANY OTHER SITE STATUS QUESTIONS AS NECESSARY.
- 3.3 PROJECT TRACKING IN SMS:
 - A. CONTRACTOR SHALL PROVIDE SCHEDULE UPDATES AND PROJECTIONS IN THE SMS SYSTEM ON A WEEKLY BASIS.
- 3.4 ADDITIONAL REPORTING:
 - A. ADDITIONAL OR ALTERNATE REPORTING REQUIREMENTS MAY BE ADDED TO THE REPORT AS DETERMINED TO BE REASONABLY NECESSARY BY COMPANY.
- 3.5 PROJECT PHOTOGRAPHS:
 - A. FILE DIGITAL PHOTOGRAPHS OF COMPLETED SITE IN JPEG FORMAT IN THE SMS PHOTO LIBRARY FOR THE RESPECTIVE SITE. PHOTOGRAPHS SHALL BE CLEARLY LABELED WITH SITE NUMBER, NAME AND DESCRIPTION, AND SHALL INCLUDE AT A MINIMUM THE FOLLOWING AS APPLICABLE:
 1. SHELTER AND TOWER OVERVIEW.
 2. TOWER FOUNDATION(S) - FORMS AND STEEL BEFORE POUR (EACH ANCHOR ON GUYED TOWERS).
 3. TOWER FOUNDATION(S) POUR WITH VIBRATOR IN USE (EACH ANCHOR ON GUYED TOWERS).
 4. TOWER STEEL AS BEING INSTALLED INTO HOLE (SHOW ANCHOR STEEL ON GUYED TOWERS).
 5. PHOTOS OF TOWER SECTION STACKING.
 6. CONCRETE TESTING / SAMPLES.
 7. PLACING OF ANCHOR BOLTS IN TOWER FOUNDATION.
 8. BUILDING/WATER TANK FROM ROAD FOR TENANT IMPROVEMENTS OR COMMENTS.
 9. SHELTER FOUNDATION--FORMS AND STEEL BEFORE POURING.
 10. SHELTER FOUNDATION POUR WITH VIBRATOR IN USE.
 11. COAX CABLE ENTRY INTO SHELTER.
 12. PLATFORM MECHANICAL CONNECTIONS TO TOWER/MONOPOLE.
 13. ROOFTOP PRE AND POST CONSTRUCTION PHOTOS TO INCLUDE PENETRATIONS AND INTERIOR CEILING.
 14. PHOTOS OF TOWER TOP COAX LINE COLOR CODING AND COLOR CODING AT GROUND LEVEL.
 15. PHOTOS OF ALL APPROPRIATE COMPANY OR REGULATORY SIGNAGE.
 16. PHOTOS OF EQUIPMENT BOLT DOWN INSIDE SHELTER.
 17. POWER AND TELCO ENTRANCE TO COMPANY ENCLOSURE AND POWER AND TELCO SUPPLY LOCATIONS INCLUDING METER/DISCONNECT.
 18. ELECTRICAL TRENCH(S) WITH ELECTRICAL / CONDUIT BEFORE BACKFILL
 19. ELECTRICAL TRENCH(S) WITH FOIL-BACKED TAPE BEFORE FURTHER BACKFILL
 20. TELCO TRENCH WITH TELEPHONE / CONDUIT BEFORE BACKFILL
 21. TELCO TRENCH WITH FOIL-BACKED TAPE BEFORE FURTHER BACKFILL
 22. SHELTER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADI).
 23. TOWER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADI).

24. FENCE GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADI).
 25. ALL BTS GROUND CONNECTIONS.
 26. ALL GROUND TEST WELLS.
 27. ANTENNA GROUND BAR AND EQUIPMENT GROUND BAR.
 28. ADDITIONAL GROUNDING POINTS ON TOWERS ABOVE 200'.
 29. HVAC UNITS INCLUDING CONDENSERS ON SPLIT SYSTEMS.
 30. GPS ANTENNAS.
 31. CABLE TRAY AND/OR WAVEGUIDE BRIDGE.
 32. DOGHOUSE/CABLE EXIT FROM ROOF.
 33. EACH SECTOR OF ANTENNAS; ONE PHOTOGRAPH LOOKING AT THE SECTOR AND ONE FROM BEHIND SHOWING THE PROJECTED COVERAGE AREA.
 34. MASTER BUS BAR.
 35. TELCO BOARD AND NIU.
 36. ELECTRICAL DISTRIBUTION WALL.
 37. CABLE ENTRY WITH SURGE SUPPRESSION.
 38. ENTRANCE TO EQUIPMENT ROOM.
 39. COAX WEATHERPROOFING--TOP AND BOTTOM OF TOWER.
 40. COAX GROUNDING -TOP AND BOTTOM OF TOWER.
 41. ANTENNA AND MAST GROUNDING.
 42. LANDSCAPING - WHERE APPLICABLE.
- 3.6 FINAL PROJECT ACCEPTANCE: COMPLETE ALL REQUIRED REPORTING TASKS PER CONTRACT, CONTRACT DOCUMENTS OR THE SPRINT INTEGRATED CONSTRUCTION STANDARDS FOR WIRELESS SITES AND UPLOAD INTO SITERRA.

PLANS PREPARED FOR:



PLANS PREPARED BY:

INFINIGY Design. Build. Deliver.
 1033 Watervliet Shaker Rd
 Albany, NY 12205
 Office # (518) 690-0790
 Fax # (518) 690-0793
 JOB NUMBER 333-000

MLA PARTNER:



ENGINEERING LICENSE:



DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:	DESCRIPTION	DATE	BY	REV
ISSUED FOR CONSTRUCTION		3/3/14	MAP	0

SITE NAME:

WINDSOR LOCKS / CROWN

SITE CASCADE:

CT43XC829

SITE ADDRESS:

44 FYLER PL.
SUFFIELD, CT 06078



SHEET DESCRIPTION:

SPRINT SPECIFICATIONS

SHEET NUMBER:



SP-3

INFORMATION CONTAINED WITHIN DRAWINGS ARE BASED ON PROVIDED INFORMATION AND ARE NOT THE RESULT OF A FIELD SURVEY.



OVERALL SITE PLAN

SCALE: AS NOTED 1



SPRINT EQUIPMENT PLAN

SCALE: AS NOTED 2

PLANS PREPARED FOR:

6580 Sprint Parkway
Overland Park, Kansas 66251

PLANS PREPARED BY:

Design. Build. Deliver.

1033 Watervliet Shaker Rd
Albany, NY 12205
Office # (518) 690-0790
Fax # (518) 690-0793

JOB NUMBER 333-000

MLA PARTNER:

ENGINEERING LICENSE:

DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR CONSTRUCTION	3/3/14	MAP	0

SITE NAME:

WINDSOR LOCKS / CROWN

SITE CASCADE:

CT43XC829

SITE ADDRESS:

44 FYLER PL.
SUFFIELD, CT 06078

SHEET DESCRIPTION:

SITE PLAN

SHEET NUMBER:


A-1

NOTE:
SPRINT TOWER TOP WORK CONTINGENT ON FOLLOWING:
COMPLETION OF STRUCTURAL ANALYSIS PROVIDED BY
CROWN CASTLE, COMPLETION OF ANTENNA/RRH
MOUNTING ASSESSMENT (PROVIDED BY AE)

NOTE:
CONTRACTOR SHALL NOT INSTALL THE
2.5 RRU'S SUCH THAT THEY IMPEDE
CLIMBING ACCESS ON THE TOWER.

NOTE:
SEE DETAIL 2 ON A-3
FOR ANTENNA LAYOUT

NOTE:
BASED ON THE ANALYSIS PROVIDED BY CROWN CASTLE,
DATED 1/4/14. THE EXISTING STRUCTURE IS CAPABLE
OF SUPPORTING THE PROPOSED EQUIPMENT
CONFIGURATION. THE ANALYSIS INDICATES THE TOWER
AND ITS FOUNDATION HAVE SUFFICIENT CAPACITY TO
CARRY THE EXISTING, RESERVED, AND PROPOSED LOADS.
NO MODIFICATIONS ARE REQUIRED AT THIS TIME.



DETAIL NOT USED NO SCALE 2

DETAIL NOT USED NO SCALE 3

DETAIL NOT USED NO SCALE 4

TOWER ELEVATION

NO SCALE 1

DETAIL NOT USED

NO SCALE 3

DETAIL NOT USED

NO SCALE 4

PLANS PREPARED FOR:

6580 Sprint Parkway
Overland Park, Kansas 66251

PLANS PREPARED BY:

Design. Build. Deliver.

1033 Watervliet Shaker Rd
Albany, NY 12205
Office # (518) 690-0790
Fax # (518) 690-0793

JOB NUMBER 333-000

MLA PARTNER:

ENGINEERING LICENSE:

DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR CONSTRUCTION	3/3/14	MAP	0


SITE NAME:
WINDSOR LOCKS / CROWN

SITE CASCADE:
CT43XC829

SITE ADDRESS:
44 FYLER PL.
SUFFIELD, CT 06078

SHEET DESCRIPTION:
TOWER ELEVATION & CABLE PLAN


SHEET NUMBER:
A-2



EXISTING ANTENNA & RRU LAYOUT

NO SCALE


1



FINAL ANTENNA LAYOUT

NO SCALE


2



DETAIL NOT USED

NO SCALE

3



TYPICAL ANTENNA & RRU MOUNTING DETAILS

NO SCALE

4

PLANS PREPARED FOR:

6580 Sprint Parkway
Overland Park, Kansas 66251

PLANS PREPARED BY:

Design. Build. Deliver.
1033 Watervliet Shaker Rd
Albany, NY 12205
Office # (518) 690-0790
Fax # (518) 690-0793
JOB NUMBER 333-000

MLA PARTNER:

ENGINEERING LICENSE:

DRAWING NOTICE:
THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR CONSTRUCTION	3/3/14	MAP	0

SITE NAME:
WINDSOR LOCKS / CROWN

SITE CASCADE:
CT43XC829

SITE ADDRESS:
44 FYLER PL.
SUFFIELD, CT 06078

SHEET DESCRIPTION:
ANTENNA LAYOUT & MOUNTING DETAILS

SHEET NUMBER:
A-3

THE CONFIGURATION PLANS ARE BASED ON PROVIDED INFORMATION AND ARE FOR CONCEPTUAL PURPOSES ONLY. CONTRACTOR TO VERIFY FIELD CONDITIONS PRIOR TO CONSTRUCTION.

NOTE:
JUMPERS FROM 2.5 RRH TO THE 2.5 ANTENNA CANNOT EXCEED 15 FEET

NOTE:
CONTRACTOR SHALL NOT INSTALL THE 2.5 RRU'S SUCH THAT THEY IMPEDE CLIMBING ACCESS ON THE TOWER.

- NOTES:
- CUT DC CONDUCTORS TO LENGTH.
 - COIL FIBER CABLE AND SECURE AT SIDE OF RRU.
 - DO NOT EXCEED BEND RADIUS.

NOTE:
CONTRACTOR TO POSITION RRU ON MOUNT BEHIND ANTENNA SUCH THAT THE RRU DOES NOT INTERFERE WITH THE EXISTING PLATFORM/T-ARM MOUNTING HARDWARE.

NOTE:
SPARE DC CABLES ARE COILED UP ON NV RRHS AT SPRINT ARRAY. THESE ARE TO BE USED TO POWER UP THE 2.5 RRHS AND TIED INTO EXISTING DC BREAKERS INSIDE THE FIBER JUNCTION BOX LOCATED AT EQUIPMENT.


NOTE:
THE DIAGRAM IS FOR CONCEPTUAL PURPOSES ONLY. CONTRACTOR IS TO REFER TO PASSING STRUCTURAL ANALYSIS FOR ANTENNA AND RRU MOUNTING DETAILS

NV CABLES			
BAND	INDICATOR	PORT	COLOR
800-1	YEL GRN	NV-1	GRN
1900-1	YEL RED	NV-2	BLU
1900-2	YEL BRN	NV-3	BRN
1900-3	YEL BLU	NV-4	WHT
1900-4	YEL SLT	NV-5	RED
800-2	YEL ORG	NV-6	SLT
SPARE	YEL WHT	NV-7	PPL
2500	YEL PPL	NV-8	ORG

HYBRID	
HYBRID	COLOR
1	GRN
2	BLU
3	BRN
4	WHT
5	RED
6	SLT
7	PPL
8	ORG

2.5 Band		
2500 Radio 1	COLOR	
YEL	WHT	GRN
YEL	WHT	BLU
YEL	WHT	BRN
YEL	WHT	WHT
YEL	WHT	RED
YEL	WHT	SLT
YEL	WHT	PPL
YEL	WHT	ORG

Figure 1: Antenna Orientation






NOTES:

- ALL CABLES SHALL BE MARKED WITH 2" WIDE, UV STABILIZED, UL APPROVED TAPE.
- THE FIRST RING SHALL BE CLOSEST TO THE END OF THE CABLE AND SPACED APPROXIMATELY 2" FROM THE END CONNECTOR, WEATHERPROOFING, OR BREAK-OUT CYLINDER. THERE SHALL BE A 1" SPACE BETWEEN EACH RING FOR THE CABLE IDENTIFIER, AND NO SPACES BETWEEN THE FREQUENCY BANDS.
- A 2" GAP SHALL SEPARATE THE CABLE COLOR CODE FROM THE FREQUENCY COLOR CODE. THE 2" COLOR RINGS FOR THE FREQUENCY CODE SHALL BE PLACED NEXT TO EACH OTHER WITH NO SPACES.
- THE 2" COLORED TAPE(S) SHALL EACH BE WRAPPED A MINIMUM OF 3 TIMES AROUND THE INDIVIDUAL CABLES, AND THE TAPE SHALL BE KEPT IN THE SAME LOCATION AS MUCH AS POSSIBLE.
- SITES WITH MORE THAN FOUR (4) SECTORS WILL REQUIRE ADDITIONAL RINGS FOR EACH SECTOR, FOLLOWING THE PATTERN. HIGH CAPACITY SITES WILL USE THE NEXT COLOR IN THE SEQUENCE FOR ADDITIONAL CABLES IN EACH SECTOR.
- HYBRID FIBER CABLE SHALL BE SECTOR IDENTIFIED INSIDE THE CABINET ON FREQUENCY BUNDLES, ON THE SEALTITE, ON THE MAIN LINE UPON EXIT OF SEALTITE, AND BEFORE AND AFTER THE BREAKOUT UNIT (MEDUSA), AS WELL AS BEFORE AND AFTER ANY ENTRANCE OR EXIT.
- HFC "MAIN TRUNK" WILL NOT BE MARKED WITH THE FREQUENCY CODES, AS IT CONTAINS ALL FREQUENCIES.
- INDIVIDUAL POWER PAIRS AND FIBER BUNDLES SHALL BE LABELED WITH BOTH THE CABLE AND FREQUENCY.

Sector	Cable	First Ring	Second Ring	Third Ring
1 Alpha	1	Green	No Tape	No Tape
	2	Green	No Tape	No Tape
	3	Brown	No Tape	No Tape
	4	White	No Tape	No Tape
	5	Red	No Tape	No Tape
	6	Grey	No Tape	No Tape
	7	Purple	No Tape	No Tape
	8	Orange	No Tape	No Tape
2 Beta	1	Green	Green	No Tape
	2	Green	Green	No Tape
	3	Brown	Brown	No Tape
	4	White	White	No Tape
	5	Red	Red	No Tape
	6	Grey	Grey	No Tape
	7	Purple	Purple	No Tape
	8	Orange	Orange	No Tape
3 Gamma	1	Green	Green	Green
	2	Green	Green	Green
	3	Brown	Brown	Brown
	4	White	White	White
	5	Red	Red	Red
	6	Grey	Grey	Grey
	7	Purple	Purple	Purple
	8	Orange	Orange	Orange

NV FREQUENCY	INDICATOR	ID
800-1	YEL	GRN
1900-1	YEL	RED
1900-2	YEL	BRN
1900-3	YEL	BLU
1900-4	YEL	SLT
800-1	YEL	ORG
RESERVED	YEL	WHT
RESERVED	YEL	PPL

2.5 FREQUENCY	INDICATOR		ID
2500 -1	YEL	WHT	GRN
2500 -2	YEL	WHT	RED
2500 -3	YEL	WHT	BRN
2500 -4	YEL	WHT	BLU
2500 -5	YEL	WHT	SLT
2500 -6	YEL	WHT	ORG
2500 -7	YEL	WHT	WHT
2500 -8	YEL	WHT	PPL



PLANS PREPARED FOR:

6580 Sprint Parkway
Overland Park, Kansas 66251

PLANS PREPARED BY:

Design. Build. Deliver.
1033 Watervliet Shaker Rd
Albany, NY 12205
Office # (518) 690-0790
Fax # (518) 690-0793
JOB NUMBER 333-000

MLA PARTNER:

ENGINEERING LICENSE:

DRAWING NOTICE:
THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR CONSTRUCTION	3/3/14	MAP	0

SITE NAME:
WINDSOR LOCKS / CROWN

SITE CASCADE:
CT43XC829


SITE ADDRESS:
44 FYLER PL.
SUFFIELD, CT 06078

SHEET DESCRIPTION:
COLOR CODING & NOTES


SHEET NUMBER:
A-4

RRU: ALCATEL LUCENT TD-RRH8X20


COLOR: LIGHT GREY
WEIGHT: 70 LBS.



SIDE VIEW



FRONT VIEW




PLAN VIEW

NOTES

COMPLY WITH MANUFACTURERS INSTRUCTIONS TO ENSURE THAT ALL RRU'S RECEIVE ELECTRICAL POWER WITHIN 24 HOURS OF BEING REMOVED FROM THE MANUFACTURER'S PACKAGING. DO NOT OPEN RRU PACKAGES IN THE RAIN.

- DS3 SURGE PROTECTOR
- POWER INJECTOR 5-8
- POWER INJECTOR 1-4
- 7210 SAS-M 2
- 7210 SAS-M 1
- 7205 SAR-B
- LTE-BBU 2.5GHz
- LTE-BBU FDD
- CDMA MT-BBU GROWTH
- CDMA MT-BBU PRIMARY
- PDP1
- PDP2
- 15MHz SPLITTER
- ETHERNET HUB SEC-B
- PRIMARY PROTECTION T1
- SEC-B #1, #1 & #3
- RECTIFIER SHELF PRIMARY
- RECTIFIER SHELF 2.5GHz



FRONT VIEW

2.5 RRU'S

NO SCALE

1


2.5 EQUIPMENT IN EXISTING CABINET

NO SCALE


2

ANTENNA RFS APXVTM14-C-120

- RADOME MATERIAL: ASA
- RADOME COLOR: LIGHT GRAY
- DIMENSIONS, HxWxD.in(mim): 56.3"x12.6"x6.3" (1430x320x160mm)
- WEIGHT: 52.9 lbs
- CONNECTORS: (8) 4.1/9.5 DIN FEMALE
(1) NF - CALIBRATION CONNECTOR



PLAN VIEW



PLAN VIEW

2.5 ANTENNA

NO SCALE

3

DETAIL NOT USED

NO SCALE

4

PLANS PREPARED FOR:



PLANS PREPARED BY:



MLA PARTNER:



ENGINEERING LICENSE:



DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR CONSTRUCTION	3/3/14	MAP	0

SITE NAME:

WINDSOR LOCKS / CROWN

SITE CASCADE:

CT43XC829

SITE ADDRESS:

44 FYLER PL.
SUFFIELD, CT 06078

SHEET DESCRIPTION:

EQUIPMENT & MOUNTING DETAILS

SHEET NUMBER:

A-5


RFS HYBRIFLEX RISER CABLE SCHEDULE

Fiber Only (Existing DC Power)	Hybrid cable MN: HB058-M12-050F 12x multi-mode fiber pairs, Top: Outdoor protected connectors, Bottom: LC Connectors, 5/8 cable, 50 ft	50 ft
	MN: HB058-M12-075F	75 ft
	MN: HB058-M12-100F	100 ft
	MN: HB058-M12-125F	125 ft
	MN: HB058-M12-150F	150 ft
	MN: HB058-M12-175F	175 ft
8 AWG Power	Hybrid cable MN: HB114-08U3M12-050F 3x 8 AWG power pairs, 12x multi-mode fiber pairs, Outdoor rated connectors & LC Connectors, 1 1/4 cable, 50 ft	50 ft
	MN: HB114-08U3M12-075F	75 ft
	MN: HB114-08U3M12-100F	100 ft
	MN: HB114-08U3M12-125F	125 ft
	MN: HB114-08U3M12-150F	150 ft
	MN: HB114-08U3M12-175F	175 ft
6 AWG Power	Hybrid cable MN: HB114-13U3M12-225F 3x 6 AWG power pair, 12x multi-mode fiber pairs, Outdoor rated connectors & LC Connectors, 1 1/4 cable, 225 ft	225 ft
	MN: HB114-13U3M12-250F	250 ft
	MN: HB114-13U3M12-275F	275 ft
	MN: HB114-13U3M12-300F	300 ft
4 AWG Power	Hybrid cable MN: HB114-21U3M12-325F 3x 4 AWG power pair, 12x multi-mode fiber pairs, Outdoor rated connectors & LC Connectors, 1 1/4 cable, 325 ft	325 ft
	MN: HB114-21U3M12-350F	350 ft
	MN: HB114-21U3M12-375F	375 ft


RFS HYBRIFLEX JUMPER CABLE SCHEDULE

Fiber Only	Hybrid Jumper cable MN: HBF012-M3-5F1 5 ft, 3x multi-mode fiber pairs, Outdoor & LC connectors, 1/2 cable	5 ft
	MN: HBF012-M3-10F1	10 ft
	MN: HBF012-M3-15F1	15 ft
	MN: HBF012-M3-20F1	20 ft
	MN: HBF012-M3-25F1	25 ft
	MN: HBF012-M3-30F1	30 ft
8 AWG Power	Hybrid Jumper cable MN: HBF058-08U1M3-5F1 5 ft, 1x 8 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 5/8 cable	5 ft
	MN: HBF058-08U1M3-10F1	10 ft
	MN: HBF058-08U1M3-15F1	15 ft
	MN: HBF058-08U1M3-20F1	20 ft
	MN: HBF058-08U1M3-25F1	25 ft
	MN: HBF058-08U1M3-30F1	30 ft
6 AWG Power	Hybrid Jumper cable MN: HBF058-13U1M3-5F1 5 ft, 1x 6 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 5/8 cable	5 ft
	MN: HBF058-13U1M3-10F1	10 ft
	MN: HBF058-13U1M3-15F1	15 ft
	MN: HBF058-13U1M3-20F1	20 ft
	MN: HBF058-13U1M3-25F1	25 ft
	MN: HBF058-13U1M3-30F1	30 ft
4 AWG Power	Hybrid Jumper cable MN: HBF078-21U1M3-5F1 5 ft, 1x 4 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 7/8 cable	5 ft
	MN: HBF078-21U1M3-10F1	10 ft
	MN: HBF078-21U1M3-15F1	15 ft
	MN: HBF078-21U1M3-20F1	20 ft
	MN: HBF078-21U1M3-25F1	25 ft
	MN: HBF078-21U1M3-30F1	30 ft


NOTE:
SPRINT CM TO CONFIRM HYBRID OR FIBER RISER CABLE AND HYBRID OR FIBER JUMPER CABLE MODEL NUMBERS IF HYBRID CABLES ARE REQUIRED BEFORE PREPARING BOM.




4 AWG



8 & 6 AWG



FIBER ONLY



FIBER JUNCTION BOX PENETRATION

NO SCALE

2

PLANS PREPARED FOR:



PLANS PREPARED BY:



1033 Watervliet Shaker Rd
Albany, NY 12205
Office # (518) 690-0790
Fax # (518) 690-0793

JOB NUMBER 333-000

MLA PARTNER:



ENGINEERING LICENSE:



DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR CONSTRUCTION	3/3/14	MAP	0

SITE NAME:

WINDSOR LOCKS / CROWN

SITE CASCADE:

CT43XC829

SITE ADDRESS:


44 FYLER PL.
SUFFIELD, CT 06078

SHEET DESCRIPTION:


CIVIL DETAILS

SHEET NUMBER:


A-6



ALU 2.5 ALU SCENARIO 1



RAN WIRING DIAGRAM



RF 2.5 ALU SCENARIO 1

PLUMBING DIAGRAM

NO SCALE

1

DRAWING NOTICE:
 THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR CONSTRUCTION	3/3/14	MAP	0

SITE NAME:
WINDSOR LOCKS / CROWN

SITE CASCADE:
CT43XC829

SITE ADDRESS:
 44 FYLER PL.
 SUFFIELD, CT 06078

SHEET DESCRIPTION:
PLUMBING DIAGRAM

SHEET NUMBER:
A-7

PLAN NOT USED

NO SCALE

1

DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR CONSTRUCTION	3/3/14	MAP	0

SITE NAME:
WINDSOR LOCKS / CROWN


SITE CASCADE:
CT43XC829

SITE ADDRESS:
44 FYLER PL.
SUFFIELD, CT 06078

SHEET DESCRIPTION:
ELECTRICAL & GROUNDING PLAN

SHEET NUMBER:
E-1


- LEGEND:**
- EXISTING GROUND RING
 - CADWELD CONNECTION (EXOTHERMIC WELD)
 - ▲ MECHANICAL CONNECTION
 - ⊗ GROUND ROD
 - CABLE GROUND KIT



TYPICAL ANTENNA GROUNDING PLAN

NO SCALE

2




NOTE:
DEPICTION IS FOR CONCEPTUAL PURPOSES ONLY. CONTRACTOR IS TO FIELD VERIFY PRIOR TO CONSTRUCTION

TYPICAL EQUIPMENT GROUNDING PLAN (ELEVATION)

NO SCALE

3


NOTES
 CG SHALL REFERENCE ALL SPECS FOR "CONNECTING THE POWER SUPPLY" OF THE NEW INSTALLATION DOCUMENTS, FOR ALL CONNECTION SPECIFICATIONS.




CIRCUIT SCHEDULE			
NO	FROM	TO	CONFIGURATION
①	UTILITY SOURCE	METER/DISCONNECT	EXISTING
②	METER/DISCONNECT	TRANSFER & LOAD CENTER	EXISTING
③	TRANSFER & LOAD CENTER	GENERATOR RECEPTACLE	EXISTING
④	TRANSFER & LOAD CENTER	EXISTING SPRINT BBU CABINET	EXISTING
⑤	TRANSFER & LOAD CENTER	EXISTING SPRINT MMBS CABINET	EXISTING

ELECTRICAL ONE-LINE DIAGRAM

NO SCALE 1




NOTES
 1. APPLY NO-OX TO LUG AND BAR CONTACT SURFACE. DO NOT COAT INLINE LUG.
 2. IF STOLEN GROUND BARS ARE ENCOUNTERED, CONTACT SPRINT CM FOR REPLACEMENT THREADED ROD KIT.



TWO HOLE LUG

NO SCALE 3



GROUNDING RISER DIAGRAM

NO SCALE 4

PLANS PREPARED FOR:
Sprint
 6580 Sprint Parkway
 Overland Park, Kansas 66251

PLANS PREPARED BY:
INFINIGY Design. Build. Deliver.
 1033 Watervliet Shaker Rd
 Albany, NY 12205
 Office # (518) 690-0790
 Fax # (518) 690-0793
JOB NUMBER 333-000

MLA PARTNER:
CROWN CASTLE

ENGINEERING LICENSE:

 JOHN S. STEVENS
 No. 24705
 LICENSED PROFESSIONAL ENGINEER

DRAWING NOTICE:
 THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:			
DESCRIPTION	DATE	BY	REV
ISSUED FOR CONSTRUCTION	3/3/14	MAP	0

SITE NAME:
WINDSOR LOCKS / CROWN

SITE CASCADE:
CT43XC829

SITE ADDRESS:
 44 FYLER PL.
 SUFFIELD, CT 06078

SHEET DESCRIPTION:
ELECTRICAL & GROUNDING DETAILS

SHEET NUMBER:
E-2

INSTALLATION OF GROUNDING CONDUCTOR TO GROUNDING BAR

NO SCALE 2

Date: January 04, 2014

Amanda Martin
Crown Castle
12725 Morris Road Extension, Suite 400
Alpharetta, GA 30004

Crown Castle
2000 Corporate Drive
Canonsburg PA
(724) 416-2000

Subject: Structural Analysis Report

Carrier Designation: *Sprint PCS Co-Locate* Scenario 2.5A
Carrier Site Number: CT43XC829

Crown Castle Designation: **Crown Castle BU Number:** 801486
Crown Castle Site Name: CT SUFFIELD 2 CAC 801486
Crown Castle JDE Job Number: 252988
Crown Castle Work Order Number: 693444
Crown Castle Application Number: 208200 Rev. 4

Engineering Firm Designation: **Crown Castle Project Number:** 693444

Site Data: **44 Fyler Place, Suffield, Hartford County, CT**
Latitude 41° 58' 49.7", Longitude -72° 39' 26.2"
109 Foot - Monopole Tower

Dear Amanda Martin,

Crown Castle is pleased to submit this "Structural Analysis Report" to determine the structural integrity of the above mentioned tower. This analysis has been performed in accordance with the Crown Castle Structural 'Statement of Work' and the terms of Crown Castle Purchase Order Number 693444, in accordance with application 208200, revision 3.

The purpose of the analysis is to determine acceptability of the tower stress level. Based on our analysis we have determined the tower stress level for the structure and foundation, under the following load case, to be:

LC7: Existing + Reserved + Proposed Equipment **Sufficient Capacity**
Note: See Table I and Table II for the proposed and existing/reserved loading, respectively.

The analysis has been performed in accordance with the TIA/EIA-222-F standard and 2005 Connecticut State Building Code based upon a wind speed of 80mph fastest mile.

All modifications and equipment proposed in this report shall be installed in accordance with the attached drawings for the determined available structural capacity to be effective.

We at Crown Castle appreciate the opportunity of providing our continuing professional services to you and Crown Castle. If you have any questions or need further assistance on this or any other projects please give us a call.

Structural analysis prepared by: Ming Chin / MBC

Respectfully submitted by:

Jamal A. Huwel, P.E.
Manager Engineering




TABLE OF CONTENTS

1) INTRODUCTION

2) ANALYSIS CRITERIA

Table 1 - Proposed Antenna and Cable Information

Table 2 - Existing and Reserved Antenna and Cable Information

Table 3 - Design Antenna and Cable Information

3) ANALYSIS PROCEDURE

Table 4 - Documents Provided

3.1) Analysis Method

3.2) Assumptions

4) ANALYSIS RESULTS

Table 5 - Section Capacity (Summary)

Table 6 – Tower Components vs. Capacity

4.1) Recommendations

5) APPENDIX A

tnxTower Output

6) APPENDIX B

Base Level Drawing

7) APPENDIX C

Additional Calculations

1) INTRODUCTION

This tower is a 109 ft Monopole tower designed by FWT INC. in February of 2002. The tower was originally designed for a wind speed of 80 mph per TIA/EIA-222-F.

2) ANALYSIS CRITERIA

The structural analysis was performed for this tower in accordance with the requirements of TIA/EIA-222-F Structural Standards for Steel Antenna Towers and Antenna Supporting Structures using a fastest mile wind speed of 80 mph with no ice, 37.6 mph with 1 inch ice thickness and 50 mph under service loads.

Table 1 - Proposed Antenna and Cable Information

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)	Note
72.0	74.0	3	alcatel lucent	TD-RRH8x20-25	1	5/8	-
		3	rfs celwave	APXVTM14-C-120 w/ Mount Pipe			

Table 2 - Existing and Reserved Antenna and Cable Information

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)	Note
107.0	109.0	4	andrew	SBNH-1D6565C w/ Mount Pipe	2 1 12	3/4 3/8 1-5/8	1
		3	communication components inc.	DTMABP7819VG12A			
		6	ericsson	RRUS-11			
		3	kathrein	800 10121 w/ Mount Pipe			
		6	kathrein	860 10025			
		3	powerwave technologies	7020.00			
		6	powerwave technologies	LGP13519			
		2	powerwave technologies	P65-15-XLH-RR w/ Mount Pipe			
		6	powerwave technologies	TT19-08BP111-001			
	1	raycap	DC6-48-60-18-8F				
	107.0	1	tower mounts	Platform Mount [LP 712-1]			
90.0	91.0	2	antel	BXA-70063-6CF-EDIN-0 w/ Mount Pipe	-	-	2
		1	antel	BXA-70063-4CF-EDIN-X w/ Mount Pipe	18	1-1/4	1
		6	antel	LPA-171080/8CFx2 w/ Mount Pipe			
		2	antel	LPA-80080-4CF-EDIN-0 w/ Mount Pipe			
		4	swedcom	SC 9012 REV2 w/ Mount Pipe			

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)	Note
	90.0	1	tower mounts	Platform Mount [LP 712-1]			
80.0	81.0	12	decibel	DB844H90-XY w/ Mount Pipe	12	7/8	1
	80.0	1	tower mounts	Platform Mount [LP 712-1]			
74.0	74.0	3	alcatel lucent	800MHz 2X50W RRH W/FILTER	-	-	1
		3	alcatel lucent	PCS 1900MHz 4x45W- 65MHz			
		1	tower mounts	Side Arm Mount [SO 102-3]			
72.0	74.0	2	rfs celwave	APXV9ERR18-C-A20 w/ Mount Pipe	3	1-1/4	1
		1	rfs celwave	APXVSPP18-C-A20 w/ Mount Pipe			
	72.0	1	tower mounts	Platform Mount [LP 712-1]			
62.0	62.0	3	rfs celwave	APX18-206516L w/ Mount Pipe	6	1-5/8	1
		1	tower mounts	Pipe Mount [PM 501-3]			
47.0	47.0	1	tower mounts	Side Arm Mount [SO 701-1]	1	1/2	1
		1	unknown	GPS			

Notes:

- 1) Existing equipment
- 2) Reserved Equipment

Table 3 - Design Antenna and Cable Information

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)
110	110	12	swedcom	ALP-9212-N	-	-
102	102	12	swedcom	ALP-9212-N	-	-
92	92	12	swedcom	ALP-9212-N	-	-
82	82	12	swedcom	ALP-9212-N	-	-
72	72	12	swedcom	ALP-9212-N	-	-

3) ANALYSIS PROCEDURE

Table 4 - Documents Provided

Document	Remarks	Reference	Source
4-GEOTECHNICAL REPORTS	Clough, Harbour & Associates LLP	2294830	CCISITES
4-TOWER FOUNDATION DRAWINGS/DESIGN/SPECS	FWT	821489	CCISITES
4-TOWER MANUFACTURER DRAWINGS	FWT	823124	CCISITES

3.1) Analysis Method

tnxTower (version 6.1.3.1), a commercially available analysis software package, was used to create a three-dimensional model of the tower and calculate member stresses for various loading cases. Selected output from the analysis is included in Appendix A.

3.2) Assumptions

- 1) Tower and structures were built in accordance with the manufacturer's specifications.
- 2) The tower and structures have been maintained in accordance with the manufacturer's specification.
- 3) The configuration of antennas, transmission cables, mounts and other appurtenances are as specified in Tables 1 and 2 and the referenced drawings.
- 4) When applicable, transmission cables are considered as structural components for calculating wind loads as allowed by TIA/EIA-222-F.

This analysis may be affected if any assumptions are not valid or have been made in error. Crown Castle should be notified to determine the effect on the structural integrity of the tower.

4) ANALYSIS RESULTS

Table 5 - Section Capacity (Summary)

Section No.	Elevation (ft)	Component Type	Size	Critical Element	P (K)	SF*P_allow (K)	% Capacity	Pass / Fail
L1	109 - 95	Pole	TP26.715x23.476x0.1875	1	-3.28	820.73	16.4	Pass
L2	95 - 48.0833	Pole	TP37.573x26.715x0.3125	2	-15.18	1862.65	47.8	Pass
L3	48.0833 - 0	Pole	TP48.075x35.8101x0.375	3	-27.12	2951.56	61.6	Pass
							Summary	
						Pole (L3)	61.6	Pass
						Rating =	61.6	Pass

Table 6 - Tower Component Stresses vs. Capacity – LC7

Notes	Component	Elevation (ft)	% Capacity	Pass / Fail
1	Anchor Rods	0	48.3	Pass
1	Base Plate	0	28.9	Pass
1	Base Foundation	0	51.6	Pass
1	Flange Plate & Bolts	95	4.5 & 10.9	Pass

Structure Rating (max from all components) =	61.6%
---	--------------

Notes:


- 1) See additional documentation in "Appendix C – Additional Calculations" for calculations supporting the % capacity consumed.

4.1) Recommendations

The tower and its foundation have sufficient capacity to carry the existing, reserved and proposed loads. No modifications are required at this time.

APPENDIX A
TNXTOWER OUTPUT

Section	1	2	3
Length (ft)	14'	46'11-1/32"	53'
Number of Sides	18	18	18
Thickness (in)	0.1875	0.3125	0.3750
Socket Length (ft)		4'11-1/32"	
Top Dia (in)	23.4760	26.7150	35.8101
Bot Dia (in)	26.7150	37.5730	48.0750
Grade		A572-65	
Weight (K)	0.7	5.0	8.9



DESIGNED APPURTENANCE LOADING


TYPE	ELEVATION	TYPE	ELEVATION
Lighting Rod 3/4" x 4'	111	BXA-70063-6CF-EDIN-0 w/ Mount Pipe	90
800 10121 w/ Mount Pipe	107	(2) LPA-171080/8CFx2 w/ Mount Pipe	90
(2) LGP13519	107	(2) SC 9012 REV2 w/ Mount Pipe	90
SBNH-1D6565C w/ Mount Pipe	107	Platform Mount [LP 712-1]	90
P65-15-XLH-RR w/ Mount Pipe	107	(4) DB844H90-XY w/ Mount Pipe	80
(4) RRUS-11	107	(4) DB844H90-XY w/ Mount Pipe	80
(2) 860 10025	107	(4) DB844H90-XY w/ Mount Pipe	80
7020.00	107	Platform Mount [LP 712-1]	80
(2) TT19-08BP111-001	107	800MHz 2X50W RRH W/FILTER	74
DC6-48-60-18-8F	107	PCS 1900MHz 4x45W-65MHz	74
(2) SBNH-1D6565C w/ Mount Pipe	107	800MHz 2X50W RRH W/FILTER	74
800 10121 w/ Mount Pipe	107	PCS 1900MHz 4x45W-65MHz	74
(2) LGP13519	107	800MHz 2X50W RRH W/FILTER	74
DTMABP7819VG12A	107	PCS 1900MHz 4x45W-65MHz	74
(2) RRUS-11	107	Side Arm Mount [SO 102-3]	74
(2) 860 10025	107	(2) 5x2 1/2" Pipe Mount	74
7020.00	107	(2) 5x2 1/2" Pipe Mount	74
(2) TT19-08BP111-001	107	(2) 5x2 1/2" Pipe Mount	74
P65-15-XLH-RR w/ Mount Pipe	107	(2) 5' x 2' Pipe Mount	72
800 10121 w/ Mount Pipe	107	(2) 5' x 2' Pipe Mount	72
(2) LGP13519	107	(2) 5' x 2' Pipe Mount	72
SBNH-1D6565C w/ Mount Pipe	107	TD-RRH8x20-25	72
(2) DTMABP7819VG12A	107	APXVTM14-C-120 w/ Mount Pipe	72
(2) 860 10025	107	TD-RRH8x20-25	72
7020.00	107	APXVTM14-C-120 w/ Mount Pipe	72
(2) TT19-08BP111-001	107	TD-RRH8x20-25	72
5' x 2' Pipe Mount	107	APXVTM14-C-120 w/ Mount Pipe	72
5' x 2' Pipe Mount	107	APXV9ERR18-C-A20 w/ Mount Pipe	72
5' x 2' Pipe Mount	107	APXVSP18-C-A20 w/ Mount Pipe	72
Platform Mount [LP 712-1]	107	APXV9ERR18-C-A20 w/ Mount Pipe	72
BXA-70063-4CF-EDIN-X w/ Mount Pipe	90	Platform Mount [LP 712-1]	72
(2) LPA-171080/8CFx2 w/ Mount Pipe	90	APX18-206516L w/ Mount Pipe	62
(2) LPA-80080-4CF-EDIN-0 w/ Mount Pipe	90	APX18-206516L w/ Mount Pipe	62
BXA-70063-6CF-EDIN-0 w/ Mount Pipe	90	APX18-206516L w/ Mount Pipe	62
(2) LPA-171080/8CFx2 w/ Mount Pipe	90	Pipe Mount [PM 501-3]	62
(2) SC 9012 REV2 w/ Mount Pipe	90	GPS	47
		Side Arm Mount [SO 701-1]	47

MATERIAL STRENGTH

GRADE	Fy	Fu	GRADE	Fy	Fu
A572-65	65 ksi	80 ksi			

TOWER DESIGN NOTES

1. Tower is located in Hartford County, Connecticut.
2. Tower designed for a 80 mph basic wind in accordance with the TIA/EIA-222-F Standard.
3. Tower is also designed for a 38 mph basic wind with 1.00 in ice. Ice is considered to increase in thickness with height.
4. Deflections are based upon a 50 mph wind.
5. TOWER RATING: 61.6%



Crown Castle
2000 Corporate Drive
Canonsburg, PA 15317
Phone: (724) 416-2000
FAX: (724) 416-2254

Job: **BU# 801486**

Project:	Client: Crown Castle	Drawn by: MCarll	App'd:
Code: TIA/EIA-222-F	Date: 01/03/14	Scale: NTS	Dwg No. E-1

Tower Input Data

There is a pole section.
 This tower is designed using the TIA/EIA-222-F standard.
 The following design criteria apply:

- 3) Tower is located in Hartford County, Connecticut.
- 4) Basic wind speed of 80 mph.
- 5) Nominal ice thickness of 1.0000 in.
- 6) Ice thickness is considered to increase with height.
- 7) Ice density of 56 pcf.
- 8) A wind speed of 38 mph is used in combination with ice.
- 9) Temperature drop of 50 °F.
- 10) Deflections calculated using a wind speed of 50 mph.
- 11) A non-linear (P-delta) analysis was used.
- 12) Pressures are calculated at each section.
- 13) Stress ratio used in pole design is 1.333.
- 14) Local bending stresses due to climbing loads, feed line supports, and appurtenance mounts are not considered.

Options

Consider Moments - Legs Consider Moments - Horizontals Consider Moments - Diagonals Use Moment Magnification ✓ Use Code Stress Ratios ✓ Use Code Safety Factors - Guys ✓ Escalate Ice Always Use Max Kz Use Special Wind Profile Include Bolts In Member Capacity Leg Bolts Are At Top Of Section Secondary Horizontal Braces Leg Use Diamond Inner Bracing (4 Sided) Add IBC .6D+W Combination	Distribute Leg Loads As Uniform Assume Legs Pinned ✓ Assume Rigid Index Plate ✓ Use Clear Spans For Wind Area Use Clear Spans For KL/r Retension Guys To Initial Tension ✓ Bypass Mast Stability Checks ✓ Use Azimuth Dish Coefficients ✓ Project Wind Area of Appurt. Autocalc Torque Arm Areas SR Members Have Cut Ends Sort Capacity Reports By Component Triangulate Diamond Inner Bracing Use TIA-222-G Tension Splice Capacity Exemption	Treat Feedline Bundles As Cylinder Use ASCE 10 X-Brace Ly Rules Calculate Redundant Bracing Forces Ignore Redundant Members in FEA SR Leg Bolts Resist Compression All Leg Panels Have Same Allowable Offset Girt At Foundation ✓ Consider Feedline Torque Include Angle Block Shear Check <div style="text-align: center; background-color: #e0e0e0; padding: 2px;">Poles</div> ✓ Include Shear-Torsion Interaction Always Use Sub-Critical Flow Use Top Mounted Sockets
--	--	---

Tapered Pole Section Geometry

Section	Elevation ft	Section Length ft	Splice Length ft	Number of Sides	Top Diameter in	Bottom Diameter in	Wall Thickness in	Bend Radius in	Pole Grade
L1	109'-95'	14'	0'	18	23.4760	26.7150	0.1875	0.7500	A572-65 (65 ksi)
L2	95'-48'31/32"	46'11-1/32"	4'11-1/32"	18	26.7150	37.5730	0.3125	1.2500	A572-65 (65 ksi)
L3	48'31/32"-0'	53'		18	35.8101	48.0750	0.3750	1.5000	A572-65 (65 ksi)

Tapered Pole Properties

Section	Tip Dia. in	Area in ²	I in ⁴	r in	C in	I/C in ³	J in ⁴	It/Q in ²	w in	w/t
L1	23.8382 27.1271	13.8596 15.7872	949.6645 1403.5717	8.2674 9.4173	11.9258 13.5712	79.6310 103.4227	1900.5786 2808.9903	6.9311 7.8951	3.8018 4.3718	20.276 23.316

Section	Tip Dia. in	Area in ²	I in ⁴	r in	C in	I/C in ³	J in ⁴	I/Q in ²	w in	w/t
L2	27.1271	26.1880	2306.3730	9.3729	13.5712	169.9459	4615.7808	13.0965	4.1518	13.286
	38.1526	36.9578	6482.4687	13.2275	19.0871	339.6259	12973.467	18.4824	6.0628	19.401
L3	37.5179	42.1767	6690.7939	12.5795	18.1915	367.7969	13390.391	21.0923	5.6426	15.047
	48.8166	56.7749	16320.399	16.9335	24.4221	668.2635	32662.273	28.3929	7.8012	20.803

Tower Elevation	Gusset Area (per face)	Gusset Thickness	Gusset Grade	Adjust. Factor A _r	Adjust. Factor A _r	Weight Mult.	Double Angle Stitch Bolt Spacing Diagonals	Double Angle Stitch Bolt Spacing Horizontals
ft	ft ²	in					in	in
L1 109'-95'				1	1	1		
L2 95'-48'31/32"				1	1	1		
L3 48'31/32"-0'				1	1	1		

Feed Line/Linear Appurtenances - Entered As Round Or Flat

Description	Face or Leg	Allow Shield	Component Type	Placement	Total Number	Number Per Row	Clear Spacing	Width or Diameter	Perimete r	Weight
				ft			in	r in	r in	plf
*										

Feed Line/Linear Appurtenances - Entered As Area

Description	Face or Leg	Allow Shield	Component Type	Placement	Total Number	C _A A _A	Weight	
				ft		ft ² /ft	plf	
LDF7-50A(1-5/8")	B	No	Inside Pole	107' - 0'	12	No Ice	0.00	0.82
						1/2" Ice	0.00	0.82
						1" Ice	0.00	0.82
						2" Ice	0.00	0.82
						4" Ice	0.00	0.82
FB-L98B-002-75000(3/8")	B	No	Inside Pole	107' - 0'	1	No Ice	0.00	0.06
						1/2" Ice	0.00	0.06
						1" Ice	0.00	0.06
						2" Ice	0.00	0.06
						4" Ice	0.00	0.06
WR-VG86ST-BRD(3/4)	B	No	Inside Pole	107' - 0'	2	No Ice	0.00	0.59
						1/2" Ice	0.00	0.59
						1" Ice	0.00	0.59
						2" Ice	0.00	0.59
						4" Ice	0.00	0.59
* LDF6-50A(1-1/4")	A	No	Inside Pole	90' - 0'	12	No Ice	0.00	0.66
						1/2" Ice	0.00	0.66
						1" Ice	0.00	0.66
						2" Ice	0.00	0.66
						4" Ice	0.00	0.66
LDF6-50A(1-1/4")	A	No	CaAa (Out Of Face)	90' - 0'	1	No Ice	0.16	0.66
						1/2" Ice	0.25	1.91
						1" Ice	0.35	3.78
						2" Ice	0.55	9.33
						4" Ice	0.95	27.78
LDF6-50A(1-1/4")	A	No	CaAa (Out Of Face)	90' - 0'	5	No Ice	0.00	0.66
						1/2" Ice	0.00	1.91
						1" Ice	0.00	3.78
						2" Ice	0.00	9.33
						4" Ice	0.00	27.78

Description	Face or Leg	Allow Shield	Component Type	Placement ft	Total Number		C _{AA} ft ² /ft	Weight plf
*								
LDF5-50A(7/8")	A	No	Inside Pole	80' - 0'	12	No Ice	0.00	0.33
						1/2" Ice	0.00	0.33
						1" Ice	0.00	0.33
						2" Ice	0.00	0.33
						4" Ice	0.00	0.33
*								
CR 50 1873(1-5/8")	C	No	CaAa (Out Of Face)	62' - 0'	2	No Ice	0.20	0.83
						1/2" Ice	0.30	2.34
						1" Ice	0.40	4.47
						2" Ice	0.60	10.55
						4" Ice	1.00	30.05
CR 50 1873(1-5/8")	C	No	CaAa (Out Of Face)	62' - 0'	4	No Ice	0.00	0.83
						1/2" Ice	0.00	2.34
						1" Ice	0.00	4.47
						2" Ice	0.00	10.55
						4" Ice	0.00	30.05
*								
LDF4-50A(1/2")	A	No	CaAa (Out Of Face)	47' - 0'	1	No Ice	0.06	0.15
						1/2" Ice	0.16	0.84
						1" Ice	0.26	2.14
						2" Ice	0.46	6.58
						4" Ice	0.86	22.78
*								
HB114-1-08U4-M5J(1 1/4")	A	No	Inside Pole	72' - 0'	2	No Ice	0.00	1.08
						1/2" Ice	0.00	1.08
						1" Ice	0.00	1.08
						2" Ice	0.00	1.08
						4" Ice	0.00	1.08
HB114-1-08U4-M5J(1 1/4")	A	No	Inside Pole	72' - 0'	1	No Ice	0.00	1.08
						1/2" Ice	0.00	1.08
						1" Ice	0.00	1.08
						2" Ice	0.00	1.08
						4" Ice	0.00	1.08
*								
HB058-M12-XXXF(5/8")	A	No	Inside Pole	72' - 0'	1	No Ice	0.00	0.24
						1/2" Ice	0.00	0.24
						1" Ice	0.00	0.24
						2" Ice	0.00	0.24
						4" Ice	0.00	0.24
*								

Feed Line/Linear Appurtenances Section Areas

Tower Section	Tower Elevation ft	Face	A _R ft ²	A _F ft ²	C _{AA} In Face ft ²	C _{AA} Out Face ft ²	Weight K
L1	109'-95'	A	0.000	0.000	0.000	0.000	0.00
		B	0.000	0.000	0.000	0.000	0.13
		C	0.000	0.000	0.000	0.000	0.00
L2	95'-48'31/32"	A	0.000	0.000	0.000	6.497	0.71
		B	0.000	0.000	0.000	0.000	0.52
		C	0.000	0.000	0.000	5.511	0.07
L3	48'31/32"-0'	A	0.000	0.000	0.000	10.414	0.94
		B	0.000	0.000	0.000	0.000	0.53
		C	0.000	0.000	0.000	19.041	0.24

Feed Line/Linear Appurtenances Section Areas - With Ice

Tower Section	Tower Elevation ft	Face or Leg	Ice Thickness in	A _R ft ²	A _F ft ²	C _{AA} In Face ft ²	C _{AA} Out Face ft ²	Weight K
L1	109'-95'	A	1.145	0.000	0.000	0.000	0.000	0.00

Tower Section	Tower Elevation ft	Face or Leg	Ice Thickness in	A _R ft ²	A _F ft ²	C _A A _A In Face ft ²	C _A A _A Out Face ft ²	Weight K
L2	95'-48'31/32"	B	1.096	0.000	0.000	0.000	0.000	0.13
		C		0.000	0.000	0.000	0.000	0.00
		A		0.000	0.000	0.000	15.684	1.63
L3	48'31/32"-0'	B	1.000	0.000	0.000	0.000	0.000	0.52
		C		0.000	0.000	0.000	11.611	0.42
		A		0.000	0.000	0.000	31.254	2.10
		B		0.000	0.000	0.000	0.000	0.53
		C		0.000	0.000	0.000	40.119	1.46

Feed Line Center of Pressure

Section	Elevation ft	CP _X in	CP _Z in	CP _X Ice in	CP _Z Ice in
L1	109'-95'	0.0000	0.0000	0.0000	0.0000
L2	95'-48'31/32"	-0.1558	-0.1031	-0.2798	-0.2356
L3	48'31/32"-0'	-0.4386	-0.0240	-0.7370	-0.2383

Discrete Tower Loads

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustmen t °	Placement ft	C _A A _A Front ft ²	C _A A _A Side ft ²	Weight K	
Lighting Rod 3/4" x 4'	C	None		0.0000	111'	No Ice	0.30	0.30	0.03
						1/2" Ice	0.71	0.71	0.03
						1" Ice	1.00	1.00	0.04
						2" Ice	1.52	1.52	0.06
						4" Ice	2.72	2.72	0.14
800 10121 w/ Mount Pipe	A	From Leg	4.00 0' 2'	0.0000	107'	No Ice	5.69	4.60	0.07
						1/2" Ice	6.18	5.35	0.11
						1" Ice	6.68	6.05	0.17
						2" Ice	7.70	7.53	0.30
						4" Ice	9.86	10.83	0.68
(2) LGP13519	A	From Leg	4.00 0' 2'	0.0000	107'	No Ice	0.34	0.21	0.01
						1/2" Ice	0.42	0.28	0.01
						1" Ice	0.51	0.36	0.01
						2" Ice	0.73	0.55	0.02
						4" Ice	1.25	1.03	0.07
SBNH-1D6565C w/ Mount Pipe	A	From Leg	4.00 0' 2'	0.0000	107'	No Ice	11.68	9.84	0.09
						1/2" Ice	12.40	11.37	0.18
						1" Ice	13.14	12.91	0.28
						2" Ice	14.60	15.27	0.52
						4" Ice	17.87	20.14	1.16
P65-15-XLH-RR w/ Mount Pipe	A	From Leg	4.00 0' 2'	0.0000	107'	No Ice	5.84	3.67	0.05
						1/2" Ice	6.29	4.28	0.09
						1" Ice	6.76	4.90	0.14
						2" Ice	7.72	6.23	0.26
						4" Ice	9.77	9.28	0.61
(4) RRUS-11	A	From Leg	4.00 0' 2'	0.0000	107'	No Ice	3.25	1.37	0.05
						1/2" Ice	3.49	1.55	0.07
						1" Ice	3.74	1.74	0.09
						2" Ice			

Description	Face or Leg	Offset Type	Offsets:			Azimuth Adjustment	Placement	C _{AA} _{Front}	C _{AA} _{Side}	Weight
			Horz	Lateral	Vert					
			ft	ft	ft	°	ft	ft ²	ft ²	K
							1" Ice	4.27	2.14	0.15
							2" Ice	5.43	3.04	0.31
							4" Ice			
(2) 860 10025	A	From Leg	4.00	0.0000	107'		No Ice	0.16	0.14	0.00
			0'				1/2"	0.23	0.20	0.00
			2'				Ice	0.30	0.27	0.01
							1" Ice	0.48	0.44	0.01
							2" Ice	0.93	0.88	0.05
							4" Ice			
7020.00	A	From Leg	4.00	0.0000	107'		No Ice	0.12	0.20	0.00
			0'				1/2"	0.17	0.28	0.01
			2'				Ice	0.23	0.36	0.01
							1" Ice	0.38	0.56	0.02
							2" Ice	0.78	1.05	0.07
							4" Ice			
(2) TT19-08BP111-001	A	From Leg	4.00	0.0000	107'		No Ice	0.64	0.52	0.02
			0'				1/2"	0.75	0.62	0.02
			2'				Ice	0.87	0.73	0.03
							1" Ice	1.13	0.98	0.05
							2" Ice	1.77	1.58	0.12
							4" Ice			
DC6-48-60-18-8F	A	From Leg	4.00	0.0000	107'		No Ice	1.27	1.27	0.02
			0'				1/2"	1.46	1.46	0.04
			2'				Ice	1.66	1.66	0.05
							1" Ice	2.09	2.09	0.10
							2" Ice	3.10	3.10	0.21
							4" Ice			
(2) SBNH-1D6565C w/ Mount Pipe	B	From Leg	4.00	0.0000	107'		No Ice	11.68	9.84	0.09
			0'				1/2"	12.40	11.37	0.18
			2'				Ice	13.14	12.91	0.28
							1" Ice	14.60	15.27	0.52
							2" Ice	17.87	20.14	1.16
							4" Ice			
800 10121 w/ Mount Pipe	B	From Leg	4.00	0.0000	107'		No Ice	5.69	4.60	0.07
			0'				1/2"	6.18	5.35	0.11
			2'				Ice	6.68	6.05	0.17
							1" Ice	7.70	7.53	0.30
							2" Ice	9.86	10.83	0.68
							4" Ice			
(2) LGP13519	B	From Leg	4.00	0.0000	107'		No Ice	0.34	0.21	0.01
			0'				1/2"	0.42	0.28	0.01
			2'				Ice	0.51	0.36	0.01
							1" Ice	0.73	0.55	0.02
							2" Ice	1.25	1.03	0.07
							4" Ice			
DTMABP7819VG12A	B	From Leg	4.00	0.0000	107'		No Ice	1.14	0.39	0.02
			0'				1/2"	1.28	0.49	0.03
			2'				Ice	1.44	0.59	0.04
							1" Ice	1.77	0.83	0.06
							2" Ice	2.54	1.41	0.14
							4" Ice			
(2) RRUS-11	B	From Leg	4.00	0.0000	107'		No Ice	3.25	1.37	0.05
			0'				1/2"	3.49	1.55	0.07
			2'				Ice	3.74	1.74	0.09
							1" Ice	4.27	2.14	0.15
							2" Ice	5.43	3.04	0.31
							4" Ice			
(2) 860 10025	B	From Leg	4.00	0.0000	107'		No Ice	0.16	0.14	0.00
			0'				1/2"	0.23	0.20	0.00
			2'				Ice	0.30	0.27	0.01
							1" Ice	0.48	0.44	0.01
							2" Ice	0.93	0.88	0.05
							4" Ice			
7020.00	B	From Leg	4.00	0.0000	107'		No Ice	0.12	0.20	0.00

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C _{AA} Front	C _{AA} Side	Weight	
			Horz	Lateral						ft
			Vert	ft	°	ft	ft ²	ft ²	K	
			ft	ft						
			0'			1/2"	0.17	0.28	0.01	
			2'			Ice	0.23	0.36	0.01	
						1" Ice	0.38	0.56	0.02	
						2" Ice	0.78	1.05	0.07	
						4" Ice				
(2) TT19-08BP111-001	B	From Leg	4.00		0.0000	107'	No Ice	0.64	0.52	0.02
			0'				1/2"	0.75	0.62	0.02
			2'				Ice	0.87	0.73	0.03
							1" Ice	1.13	0.98	0.05
							2" Ice	1.77	1.58	0.12
							4" Ice			
* P65-15-XLH-RR w/ Mount Pipe	C	From Leg	4.00		0.0000	107'	No Ice	5.84	3.67	0.05
			0'				1/2"	6.29	4.28	0.09
			2'				Ice	6.76	4.90	0.14
							1" Ice	7.72	6.23	0.26
							2" Ice	9.77	9.28	0.61
							4" Ice			
800 10121 w/ Mount Pipe	C	From Leg	4.00		0.0000	107'	No Ice	5.69	4.60	0.07
			0'				1/2"	6.18	5.35	0.11
			2'				Ice	6.68	6.05	0.17
							1" Ice	7.70	7.53	0.30
							2" Ice	9.86	10.83	0.68
							4" Ice			
(2) LGP13519	C	From Leg	4.00		0.0000	107'	No Ice	0.34	0.21	0.01
			0'				1/2"	0.42	0.28	0.01
			2'				Ice	0.51	0.36	0.01
							1" Ice	0.73	0.55	0.02
							2" Ice	1.25	1.03	0.07
							4" Ice			
SBNH-1D6565C w/ Mount Pipe	C	From Leg	4.00		0.0000	107'	No Ice	11.68	9.84	0.09
			0'				1/2"	12.40	11.37	0.18
			2'				Ice	13.14	12.91	0.28
							1" Ice	14.60	15.27	0.52
							2" Ice	17.87	20.14	1.16
							4" Ice			
(2) DTMABP7819VG12A	C	From Leg	4.00		0.0000	107'	No Ice	1.14	0.39	0.02
			0'				1/2"	1.28	0.49	0.03
			2'				Ice	1.44	0.59	0.04
							1" Ice	1.77	0.83	0.06
							2" Ice	2.54	1.41	0.14
							4" Ice			
(2) 860 10025	C	From Leg	4.00		0.0000	107'	No Ice	0.16	0.14	0.00
			0'				1/2"	0.23	0.20	0.00
			2'				Ice	0.30	0.27	0.01
							1" Ice	0.48	0.44	0.01
							2" Ice	0.93	0.88	0.05
							4" Ice			
7020.00	C	From Leg	4.00		0.0000	107'	No Ice	0.12	0.20	0.00
			0'				1/2"	0.17	0.28	0.01
			2'				Ice	0.23	0.36	0.01
							1" Ice	0.38	0.56	0.02
							2" Ice	0.78	1.05	0.07
							4" Ice			
(2) TT19-08BP111-001	C	From Leg	4.00		0.0000	107'	No Ice	0.64	0.52	0.02
			0'				1/2"	0.75	0.62	0.02
			2'				Ice	0.87	0.73	0.03
							1" Ice	1.13	0.98	0.05
							2" Ice	1.77	1.58	0.12
							4" Ice			
5' x 2' Pipe Mount	A	From Leg	4.00		0.0000	107'	No Ice	1.00	1.00	0.03
			0'				1/2"	1.39	1.39	0.04
			0'				Ice	1.70	1.70	0.05
							1" Ice	2.35	2.35	0.08
							2" Ice	3.78	3.78	0.20

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C _{AA} Front	C _{AA} Side	Weight
			Horz	Lateral					
							ft ²	ft ²	K
5' x 2' Pipe Mount	B	From Leg	4.00	0.0000	107'	4" Ice			
						No Ice	1.00	1.00	0.03
						1/2"	1.39	1.39	0.04
						Ice	1.70	1.70	0.05
						1" Ice	2.35	2.35	0.08
						2" Ice	3.78	3.78	0.20
5' x 2' Pipe Mount	C	From Leg	4.00	0.0000	107'	4" Ice			
						No Ice	1.00	1.00	0.03
						1/2"	1.39	1.39	0.04
						Ice	1.70	1.70	0.05
						1" Ice	2.35	2.35	0.08
						2" Ice	3.78	3.78	0.20
Platform Mount [LP 712-1]	C	None	0.0000	107'	4" Ice				
					No Ice	24.53	24.53	1.34	
					1/2"	29.94	29.94	1.65	
					Ice	35.35	35.35	1.96	
					1" Ice	46.17	46.17	2.58	
					2" Ice	67.81	67.81	3.82	
*** BXA-70063-4CF-EDIN-X w/ Mount Pipe	A	From Leg	4.00	0.0000	90'	4" Ice			
						No Ice	5.40	3.69	0.03
						1/2"	5.84	4.29	0.07
						Ice	6.30	4.91	0.12
						1" Ice	7.24	6.26	0.23
						2" Ice	9.26	9.29	0.58
(2) LPA-171080/8CFx2 w/ Mount Pipe	A	From Leg	4.00	0.0000	90'	4" Ice			
						No Ice	2.49	4.41	0.03
						1/2"	2.85	5.07	0.06
						Ice	3.22	5.74	0.10
						1" Ice	3.99	7.15	0.20
						2" Ice	5.84	10.23	0.50
(2) LPA-80080-4CF-EDIN-0 w/ Mount Pipe	A	From Leg	4.00	0.0000	90'	4" Ice			
						No Ice	2.86	7.23	0.03
						1/2"	3.22	7.92	0.08
						Ice	3.59	8.63	0.13
						1" Ice	4.45	10.11	0.25
						2" Ice	6.32	13.34	0.61
BXA-70063-6CF-EDIN-0 w/ Mount Pipe	B	From Leg	4.00	0.0000	90'	4" Ice			
						No Ice	7.97	5.80	0.04
						1/2"	8.61	6.95	0.10
						Ice	9.22	7.82	0.17
						1" Ice	10.46	9.60	0.34
						2" Ice	13.07	13.37	0.80
(2) LPA-171080/8CFx2 w/ Mount Pipe	B	From Leg	4.00	0.0000	90'	4" Ice			
						No Ice	2.49	4.41	0.03
						1/2"	2.85	5.07	0.06
						Ice	3.22	5.74	0.10
						1" Ice	3.99	7.15	0.20
						2" Ice	5.84	10.23	0.50
(2) SC 9012 REV2 w/Mount Pipe	B	From Leg	4.00	0.0000	90'	4" Ice			
						No Ice	2.95	4.40	0.03
						1/2"	3.33	5.01	0.06
						Ice	3.73	5.64	0.10
						1" Ice	4.55	6.96	0.21
						2" Ice	6.35	9.90	0.51
BXA-70063-6CF-EDIN-0 w/ Mount Pipe	C	From Leg	4.00	0.0000	90'	4" Ice			
						No Ice	7.97	5.80	0.04
						1/2"	8.61	6.95	0.10
						Ice	9.22	7.82	0.17
						1" Ice	10.46	9.60	0.34
						2" Ice	13.07	13.37	0.80
(2) LPA-171080/8CFx2 w/ Mount Pipe	C	From Leg	4.00	0.0000	90'	4" Ice			
						No Ice	2.49	4.41	0.03
						1/2"	2.85	5.07	0.06
						Ice	3.22	5.74	0.10

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C _{AA} _{Front}	C _{AA} _{Side}	Weight	
			Horz Lateral	Vert						
			ft	ft	°	ft	ft ²	ft ²	K	
(2) SC 9012 REV2 w/ Mount Pipe	C	From Leg	4.00	0'	0.0000	90'	1" Ice	3.99	7.15	0.20
							2" Ice	5.84	10.23	0.50
							4" Ice			
							No Ice	2.95	4.40	0.03
							1/2" Ice	3.33	5.01	0.06
							1" Ice	3.73	5.64	0.10
							2" Ice	4.55	6.96	0.21
Platform Mount [LP 712-1]	C	None	0'	0.0000	90'	4" Ice	6.35	9.90	0.51	
						No Ice	24.53	24.53	1.34	
						1/2" Ice	29.94	29.94	1.65	
						Ice	35.35	35.35	1.96	
						1" Ice	46.17	46.17	2.58	
						2" Ice	67.81	67.81	3.82	
						4" Ice				
*** (4) DB844H90-XY w/ Mount Pipe	A	From Leg	4.00	0'	0.0000	80'	No Ice	3.10	5.15	0.03
							1/2" Ice	3.48	5.83	0.07
							Ice	3.88	6.52	0.11
							1" Ice	4.76	7.96	0.22
							2" Ice	6.66	11.09	0.55
							4" Ice			
							No Ice	3.10	5.15	0.03
(4) DB844H90-XY w/ Mount Pipe	B	From Leg	4.00	0'	0.0000	80'	1/2" Ice	3.48	5.83	0.07
							Ice	3.88	6.52	0.11
							1" Ice	4.76	7.96	0.22
							2" Ice	6.66	11.09	0.55
							4" Ice			
							No Ice	3.10	5.15	0.03
							1/2" Ice	3.48	5.83	0.07
(4) DB844H90-XY w/ Mount Pipe	C	From Leg	4.00	0'	0.0000	80'	Ice	3.88	6.52	0.11
							1" Ice	4.76	7.96	0.22
							2" Ice	6.66	11.09	0.55
							4" Ice			
							No Ice	3.10	5.15	0.03
							1/2" Ice	3.48	5.83	0.07
							Ice	3.88	6.52	0.11
Platform Mount [LP 712-1]	C	None	0'	0.0000	80'	1" Ice	4.76	7.96	0.22	
						2" Ice	6.66	11.09	0.55	
						4" Ice				
						No Ice	24.53	24.53	1.34	
						1/2" Ice	29.94	29.94	1.65	
						Ice	35.35	35.35	1.96	
						1" Ice	46.17	46.17	2.58	
*** TD-RRH8x20-25	A	From Leg	4.00	0'	0.0000	72'	2" Ice	6.66	11.09	0.55
							4" Ice			
							No Ice	4.72	1.70	0.07
							1/2" Ice	5.01	1.92	0.10
							Ice	5.32	2.15	0.13
							1" Ice	5.95	2.62	0.20
							2" Ice	7.31	3.68	0.40
APXVTM14-C-120 w/ Mount Pipe	A	From Leg	4.00	0'	0.0000	72'	4" Ice	7.31	3.68	0.40
							No Ice	7.13	4.96	0.07
							1/2" Ice	7.66	5.75	0.13
							Ice	8.18	6.47	0.19
							1" Ice	9.26	8.01	0.34
							2" Ice	11.53	11.41	0.75
							4" Ice			
TD-RRH8x20-25	B	From Leg	4.00	0'	0.0000	72'	No Ice	4.72	1.70	0.07
							1/2" Ice	5.01	1.92	0.10
							Ice	5.32	2.15	0.13
							1" Ice	5.95	2.62	0.20
							2" Ice	7.31	3.68	0.40
							4" Ice			
							No Ice	4.72	1.70	0.07
APXVTM14-C-120 w/ Mount Pipe	B	From Leg	4.00	0'	0.0000	72'	1/2" Ice	7.66	5.75	0.13
							Ice	8.18	6.47	0.19
							1" Ice	9.26	8.01	0.34
							2" Ice	11.53	11.41	0.75
							4" Ice			
							No Ice	7.13	4.96	0.07
							1/2" Ice	7.66	5.75	0.13

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C _{AA} Front	C _{AA} Side	Weight	
			Horz	Lateral						ft
			ft	ft	°	ft	ft ²	ft ²	K	
TD-RRH8x20-25	C	From Leg	4.00	0'	0.0000	72'	No Ice	4.72	1.70	0.07
							1/2" Ice	5.01	1.92	0.10
							Ice	5.32	2.15	0.13
							1" Ice	5.95	2.62	0.20
							2" Ice	7.31	3.68	0.40
							4" Ice			
APXVTM14-C-120 w/ Mount Pipe	C	From Leg	4.00	0'	0.0000	72'	No Ice	7.13	4.96	0.07
							1/2" Ice	7.66	5.75	0.13
							Ice	8.18	6.47	0.19
							1" Ice	9.26	8.01	0.34
							2" Ice	11.53	11.41	0.75
							4" Ice			

APXV9ERR18-C-A20 w/ Mount Pipe	A	From Leg	4.00	0'	0.0000	72'	No Ice	8.50	7.47	0.09
							1/2" Ice	9.15	8.66	0.16
							Ice	9.77	9.56	0.24
							1" Ice	11.03	11.39	0.42
							2" Ice	13.68	15.53	0.94
							4" Ice			
APXVSP18-C-A20 w/ Mount Pipe	B	From Leg	4.00	0'	0.0000	72'	No Ice	8.50	6.95	0.08
							1/2" Ice	9.15	8.13	0.15
							Ice	9.77	9.02	0.23
							1" Ice	11.03	10.84	0.41
							2" Ice	13.68	14.85	0.91
							4" Ice			
APXV9ERR18-C-A20 w/ Mount Pipe	C	From Leg	4.00	0'	0.0000	72'	No Ice	8.50	7.47	0.09
							1/2" Ice	9.15	8.66	0.16
							Ice	9.77	9.56	0.24
							1" Ice	11.03	11.39	0.42
							2" Ice	13.68	15.53	0.94
							4" Ice			
Platform Mount [LP 712-1]	C	None			0.0000	72'	No Ice	24.53	24.53	1.34
							1/2" Ice	29.94	29.94	1.65
							Ice	35.35	35.35	1.96
							1" Ice	46.17	46.17	2.58
							2" Ice	67.81	67.81	3.82
							4" Ice			
(2) 5' x 2' Pipe Mount	A	From Leg	4.00	0'	0.0000	72'	No Ice	1.00	1.00	0.03
							1/2" Ice	1.39	1.39	0.04
							Ice	1.70	1.70	0.05
							1" Ice	2.35	2.35	0.08
							2" Ice	3.78	3.78	0.20
							4" Ice			
(2) 5' x 2' Pipe Mount	B	From Leg	4.00	0'	0.0000	72'	No Ice	1.00	1.00	0.03
							1/2" Ice	1.39	1.39	0.04
							Ice	1.70	1.70	0.05
							1" Ice	2.35	2.35	0.08
							2" Ice	3.78	3.78	0.20
							4" Ice			
(2) 5' x 2' Pipe Mount	C	From Leg	4.00	0'	0.0000	72'	No Ice	1.00	1.00	0.03
							1/2" Ice	1.39	1.39	0.04
							Ice	1.70	1.70	0.05
							1" Ice	2.35	2.35	0.08
							2" Ice	3.78	3.78	0.20
							4" Ice			

**										
800MHz 2X50W RRH W/FILTER	A	From Leg	2.00	0'	0.0000	74'	No Ice	2.40	2.25	0.06
							1/2" Ice	2.61	2.46	0.09
							Ice	2.83	2.68	0.11
							1" Ice	3.30	3.13	0.17
							2" Ice	4.34	4.15	0.34
							4" Ice			
PCS 1900MHz 4x45W-65MHz	A	From Leg	2.00	0'	0.0000	74'	No Ice	2.71	2.61	0.06
							1/2" Ice	2.95	2.85	0.08

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment t °	Placement ft	C _{AA} Front ft ²	C _{AA} Side ft ²	Weight K	
APX18-206516L w/ Mount Pipe	C	From Leg	1.00 0' 0'	0.0000	62'	No Ice	3.74	3.29	0.04
						1/2" Ice	4.16	4.00	0.07
						Ice	4.59	4.66	0.11
						1" Ice	5.54	6.04	0.21
						2" Ice	7.57	9.02	0.52
						4" Ice			
Pipe Mount [PM 501-3]	C	None		0.0000	62'	No Ice	5.78	5.78	0.16
						1/2" Ice	7.37	7.37	0.18
						Ice	8.96	8.96	0.20
						1" Ice	12.14	12.14	0.24
						2" Ice	18.50	18.50	0.32
						4" Ice			
*** GPS	A	From Leg	3.00 0' 0'	0.0000	47'	No Ice	0.17	0.17	0.00
						1/2" Ice	0.24	0.24	0.00
						Ice	0.31	0.31	0.00
						1" Ice	0.48	0.48	0.01
						2" Ice	0.92	0.92	0.05
						4" Ice			
Side Arm Mount [SO 701-1]	A	From Leg	2.00 0' 0'	0.0000	47'	No Ice	0.85	1.67	0.07
						1/2" Ice	1.14	2.34	0.08
						Ice	1.43	3.01	0.09
						1" Ice	2.01	4.35	0.12
						2" Ice	3.17	7.03	0.18
						4" Ice			
**									

Load Combinations

Comb. No.	Description
1	Dead Only
2	Dead+Wind 0 deg - No Ice
3	Dead+Wind 30 deg - No Ice
4	Dead+Wind 60 deg - No Ice
5	Dead+Wind 90 deg - No Ice
6	Dead+Wind 120 deg - No Ice
7	Dead+Wind 150 deg - No Ice
8	Dead+Wind 180 deg - No Ice
9	Dead+Wind 210 deg - No Ice
10	Dead+Wind 240 deg - No Ice
11	Dead+Wind 270 deg - No Ice
12	Dead+Wind 300 deg - No Ice
13	Dead+Wind 330 deg - No Ice
14	Dead+Ice+Temp
15	Dead+Wind 0 deg+Ice+Temp
16	Dead+Wind 30 deg+Ice+Temp
17	Dead+Wind 60 deg+Ice+Temp
18	Dead+Wind 90 deg+Ice+Temp
19	Dead+Wind 120 deg+Ice+Temp
20	Dead+Wind 150 deg+Ice+Temp
21	Dead+Wind 180 deg+Ice+Temp
22	Dead+Wind 210 deg+Ice+Temp
23	Dead+Wind 240 deg+Ice+Temp
24	Dead+Wind 270 deg+Ice+Temp
25	Dead+Wind 300 deg+Ice+Temp
26	Dead+Wind 330 deg+Ice+Temp
27	Dead+Wind 0 deg - Service
28	Dead+Wind 30 deg - Service

Comb. No.	Description
29	Dead+Wind 60 deg - Service
30	Dead+Wind 90 deg - Service
31	Dead+Wind 120 deg - Service
32	Dead+Wind 150 deg - Service
33	Dead+Wind 180 deg - Service
34	Dead+Wind 210 deg - Service
35	Dead+Wind 240 deg - Service
36	Dead+Wind 270 deg - Service
37	Dead+Wind 300 deg - Service
38	Dead+Wind 330 deg - Service

Maximum Member Forces

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Force K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
L1	109 - 95	Pole	Max Tension	15	0.00	0.00	-0.00
			Max. Compression	14	-6.90	-1.40	1.13
			Max. Mx	5	-3.28	-68.89	-0.04
			Max. My	2	-3.28	0.17	71.52
			Max. Vy	5	5.44	-68.89	-0.04
			Max. Vx	2	-5.62	0.17	71.52
			Max. Torque	8			1.46
L2	95 - 48.0833	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	14	-28.88	-0.87	2.23
			Max. Mx	5	-15.18	-645.99	-2.01
			Max. My	2	-15.18	2.37	647.48
			Max. Vy	5	18.89	-645.99	-2.01
			Max. Vx	2	-18.83	2.37	647.48
			Max. Torque	13			-1.79
L3	48.0833 - 0	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	14	-45.94	1.42	3.84
			Max. Mx	5	-27.12	-1750.98	-4.47
			Max. My	2	-27.12	5.59	1748.84
			Max. Vy	5	22.83	-1750.98	-4.47
			Max. Vx	2	-22.75	5.59	1748.84
			Max. Torque	13			-1.81

Maximum Reactions

Location	Condition	Gov. Load Comb.	Vertical K	Horizontal, X K	Horizontal, Z K
Pole	Max. Vert	26	45.94	3.34	5.76
	Max. H _x	11	27.13	22.81	0.05
	Max. H _z	2	27.13	0.05	22.73
	Max. M _x	2	1748.84	0.05	22.73
	Max. M _z	5	1750.98	-22.81	-0.05
	Max. Torsion	6	1.73	-19.78	-11.41
	Min. Vert	1	27.13	0.00	0.00
	Min. H _x	5	27.13	-22.81	-0.05
	Min. H _z	8	27.13	-0.05	-22.73
	Min. M _x	8	-1746.55	-0.05	-22.73
	Min. M _z	11	-1750.93	22.81	0.05
	Min. Torsion	12	-1.75	19.78	11.41

Tower Mast Reaction Summary

Load Combination	Vertical	Shear _x	Shear _z	Overturning Moment, M _x	Overturning Moment, M _z	Torque
	K	K	K	kip-ft	kip-ft	kip-ft
Dead Only	27.13	0.00	0.00	-1.12	-0.02	0.00
Dead+Wind 0 deg - No Ice	27.13	-0.05	-22.73	-1748.84	5.59	1.19
Dead+Wind 30 deg - No Ice	27.13	11.36	-19.66	-1511.89	-870.64	0.36
Dead+Wind 60 deg - No Ice	27.13	19.73	-11.32	-870.14	-1513.59	-0.56
Dead+Wind 90 deg - No Ice	27.13	22.81	0.05	4.47	-1750.98	-1.32
Dead+Wind 120 deg - No Ice	27.13	19.78	11.41	877.56	-1519.20	-1.73
Dead+Wind 150 deg - No Ice	27.13	11.45	19.71	1515.21	-880.36	-1.68
Dead+Wind 180 deg - No Ice	27.13	0.05	22.73	1746.55	-5.64	-1.19
Dead+Wind 210 deg - No Ice	27.13	-11.36	19.66	1509.60	870.59	-0.38
Dead+Wind 240 deg - No Ice	27.13	-19.73	11.32	867.84	1513.54	0.54
Dead+Wind 270 deg - No Ice	27.13	-22.81	-0.05	-6.76	1750.93	1.32
Dead+Wind 300 deg - No Ice	27.13	-19.78	-11.41	-879.85	1519.15	1.75
Dead+Wind 330 deg - No Ice	27.13	-11.45	-19.71	-1517.50	880.31	1.70
Dead+Ice+Temp	45.94	0.00	-0.00	-3.84	1.42	0.00
Dead+Wind 0 deg+Ice+Temp	45.94	-0.01	-6.64	-522.05	2.19	0.32
Dead+Wind 30 deg+Ice+Temp	45.94	3.32	-5.75	-452.26	-256.98	0.10
Dead+Wind 60 deg+Ice+Temp	45.94	5.76	-3.31	-262.34	-446.91	-0.16
Dead+Wind 90 deg+Ice+Temp	45.94	6.66	0.01	-3.18	-516.70	-0.37
Dead+Wind 120 deg+Ice+Temp	45.94	5.77	3.33	255.77	-447.67	-0.48
Dead+Wind 150 deg+Ice+Temp	45.94	3.34	5.76	445.14	-258.29	-0.46
Dead+Wind 180 deg+Ice+Temp	45.94	0.01	6.64	514.17	0.67	-0.32
Dead+Wind 210 deg+Ice+Temp	45.94	-3.32	5.75	444.38	259.84	-0.10
Dead+Wind 240 deg+Ice+Temp	45.94	-5.76	3.31	254.46	449.77	0.16
Dead+Wind 270 deg+Ice+Temp	45.94	-6.66	-0.01	-4.70	519.57	0.37
Dead+Wind 300 deg+Ice+Temp	45.94	-5.77	-3.33	-263.65	450.53	0.48
Dead+Wind 330 deg+Ice+Temp	45.94	-3.34	-5.76	-453.02	261.16	0.46
Dead+Wind 0 deg - Service	27.13	-0.02	-8.88	-684.02	2.17	0.46
Dead+Wind 30 deg - Service	27.13	4.44	-7.68	-591.44	-340.20	0.14
Dead+Wind 60 deg - Service	27.13	7.71	-4.42	-340.69	-591.42	-0.22
Dead+Wind 90 deg - Service	27.13	8.91	0.02	1.05	-684.17	-0.52
Dead+Wind 120 deg - Service	27.13	7.73	4.46	342.19	-593.61	-0.68
Dead+Wind 150 deg - Service	27.13	4.47	7.70	591.34	-344.00	-0.66
Dead+Wind 180 deg - Service	27.13	0.02	8.88	681.73	-2.22	-0.47
Dead+Wind 210 deg - Service	27.13	-4.44	7.68	589.14	340.15	-0.15
Dead+Wind 240 deg - Service	27.13	-7.71	4.42	338.39	591.37	0.21
Dead+Wind 270 deg - Service	27.13	-8.91	-0.02	-3.34	684.12	0.52
Dead+Wind 300 deg - Service	27.13	-7.73	-4.46	-344.49	593.56	0.68
Dead+Wind 330 deg - Service	27.13	-4.47	-7.70	-593.63	343.95	0.66

Solution Summary

Load Comb.	Sum of Applied Forces			Sum of Reactions			% Error
	PX K	PY K	PZ K	PX K	PY K	PZ K	
1	0.00	-27.13	0.00	0.00	27.13	0.00	0.000%
2	-0.05	-27.13	-22.73	0.05	27.13	22.73	0.000%

Load Comb.	Sum of Applied Forces			Sum of Reactions			% Error
	PX K	PY K	PZ K	PX K	PY K	PZ K	
3	11.36	-27.13	-19.66	-11.36	27.13	19.66	0.000%
4	19.73	-27.13	-11.32	-19.73	27.13	11.32	0.000%
5	22.81	-27.13	0.05	-22.81	27.13	-0.05	0.000%
6	19.78	-27.13	11.41	-19.78	27.13	-11.41	0.000%
7	11.45	-27.13	19.71	-11.45	27.13	-19.71	0.000%
8	0.05	-27.13	22.73	-0.05	27.13	-22.73	0.000%
9	-11.36	-27.13	19.66	11.36	27.13	-19.66	0.000%
10	-19.73	-27.13	11.32	19.73	27.13	-11.32	0.000%
11	-22.81	-27.13	-0.05	22.81	27.13	0.05	0.000%
12	-19.78	-27.13	-11.41	19.78	27.13	11.41	0.000%
13	-11.45	-27.13	-19.71	11.45	27.13	19.71	0.000%
14	0.00	-45.94	0.00	-0.00	45.94	0.00	0.000%
15	-0.01	-45.94	-6.64	0.01	45.94	6.64	0.000%
16	3.32	-45.94	-5.75	-3.32	45.94	5.75	0.000%
17	5.76	-45.94	-3.31	-5.76	45.94	3.31	0.000%
18	6.66	-45.94	0.01	-6.66	45.94	-0.01	0.000%
19	5.77	-45.94	3.33	-5.77	45.94	-3.33	0.000%
20	3.34	-45.94	5.76	-3.34	45.94	-5.76	0.000%
21	0.01	-45.94	6.64	-0.01	45.94	-6.64	0.000%
22	-3.32	-45.94	5.75	3.32	45.94	-5.75	0.000%
23	-5.76	-45.94	3.31	5.76	45.94	-3.31	0.000%
24	-6.66	-45.94	-0.01	6.66	45.94	0.01	0.000%
25	-5.77	-45.94	-3.33	5.77	45.94	3.33	0.000%
26	-3.34	-45.94	-5.76	3.34	45.94	5.76	0.000%
27	-0.02	-27.13	-8.88	0.02	27.13	8.88	0.000%
28	4.44	-27.13	-7.68	-4.44	27.13	7.68	0.000%
29	7.71	-27.13	-4.42	-7.71	27.13	4.42	0.000%
30	8.91	-27.13	0.02	-8.91	27.13	-0.02	0.000%
31	7.73	-27.13	4.46	-7.73	27.13	-4.46	0.000%
32	4.47	-27.13	7.70	-4.47	27.13	-7.70	0.000%
33	0.02	-27.13	8.88	-0.02	27.13	-8.88	0.000%
34	-4.44	-27.13	7.68	4.44	27.13	-7.68	0.000%
35	-7.71	-27.13	4.42	7.71	27.13	-4.42	0.000%
36	-8.91	-27.13	-0.02	8.91	27.13	0.02	0.000%
37	-7.73	-27.13	-4.46	7.73	27.13	4.46	0.000%
38	-4.47	-27.13	-7.70	4.47	27.13	7.70	0.000%

Non-Linear Convergence Results

Load Combination	Converged?	Number of Cycles	Displacement Tolerance	Force Tolerance
1	Yes	4	0.00000001	0.00000001
2	Yes	4	0.00000001	0.00027061
3	Yes	5	0.00000001	0.00002691
4	Yes	5	0.00000001	0.00002524
5	Yes	4	0.00000001	0.00017446
6	Yes	5	0.00000001	0.00002282
7	Yes	5	0.00000001	0.00002984
8	Yes	4	0.00000001	0.00029182
9	Yes	5	0.00000001	0.00002337
10	Yes	5	0.00000001	0.00002455
11	Yes	4	0.00000001	0.00019625
12	Yes	5	0.00000001	0.00002930
13	Yes	5	0.00000001	0.00002274
14	Yes	4	0.00000001	0.00000001
15	Yes	4	0.00000001	0.00051400
16	Yes	4	0.00000001	0.00059140
17	Yes	4	0.00000001	0.00058566
18	Yes	4	0.00000001	0.00050504
19	Yes	4	0.00000001	0.00057468
20	Yes	4	0.00000001	0.00058741
21	Yes	4	0.00000001	0.00050309
22	Yes	4	0.00000001	0.00056938
23	Yes	4	0.00000001	0.00057092
24	Yes	4	0.00000001	0.00050344

25	Yes	4	0.00000001	0.00059417
26	Yes	4	0.00000001	0.00058505
27	Yes	4	0.00000001	0.00005910
28	Yes	4	0.00000001	0.00012409
29	Yes	4	0.00000001	0.00010762
30	Yes	4	0.00000001	0.00003885
31	Yes	4	0.00000001	0.00009435
32	Yes	4	0.00000001	0.00015296
33	Yes	4	0.00000001	0.00006056
34	Yes	4	0.00000001	0.00009268
35	Yes	4	0.00000001	0.00010085
36	Yes	4	0.00000001	0.00004056
37	Yes	4	0.00000001	0.00014752
38	Yes	4	0.00000001	0.00009647

Maximum Tower Deflections - Service Wind

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
L1	109 - 95	13.470	38	0.9849	0.0060
L2	95 - 48.0833	10.623	38	0.9428	0.0040
L3	53 - 0	3.530	38	0.6044	0.0012

Critical Deflections and Radius of Curvature - Service Wind

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
111'	Lighting Rod 3/4" x 4'	38	13.470	0.9849	0.0061	47655
107'	800 10121 w/ Mount Pipe	38	13.060	0.9801	0.0058	47655
90'	BXA-70063-4CF-EDIN-X w/ Mount Pipe	38	9.633	0.9189	0.0034	12167
80'	(4) DB844H90-XY w/ Mount Pipe	38	7.731	0.8545	0.0025	7748
74'	800MHz 2X50W RRH W/FILTER	38	6.661	0.8069	0.0022	6362
72'	TD-RRH8x20-25	38	6.319	0.7898	0.0020	6004
62'	APX18-206516L w/ Mount Pipe	38	4.736	0.6965	0.0016	4678
47'	GPS	38	2.857	0.5404	0.0010	4398

Maximum Tower Deflections - Design Wind

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
L1	109 - 95	34.416	13	2.5157	0.0154
L2	95 - 48.0833	27.147	13	2.4092	0.0102
L3	53 - 0	9.026	12	1.5450	0.0031

Critical Deflections and Radius of Curvature - Design Wind

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
111'	Lighting Rod 3/4" x 4'	13	34.416	2.5157	0.0156	19053
107'	800 10121 w/ Mount Pipe	13	33.370	2.5034	0.0148	19053
90'	BXA-70063-4CF-EDIN-X w/	13	24.617	2.3482	0.0088	4829

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
	Mount Pipe					
80'	(4) DB844H90-XY w/ Mount Pipe	13	19.760	2.1840	0.0065	3055
74'	800MHz 2X50W RRH W/FILTER	13	17.025	2.0625	0.0055	2502
72'	TD-RRH8x20-25	12	16.151	2.0188	0.0052	2359
62'	APX18-206516L w/ Mount Pipe	12	12.109	1.7804	0.0040	1834
47'	GPS	12	7.307	1.3816	0.0026	1722

Compression Checks

Pole Design Data

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	F _a ksi	A in ²	Actual P K	Allow. P _a K	Ratio P P _a
L1	109 - 95 (1)	TP26.715x23.476x0.1875	14'	0'	0.0	39.000	15.7872	-3.28	615.70	0.005
L2	95 - 48.0833 (2)	TP37.573x26.715x0.3125	46'11- 1/32"	0'	0.0	39.000	35.8291	-15.18	1397.34	0.011
L3	48.0833 - 0 (3)	TP48.075x35.8101x0.375	53'	0'	0.0	39.000	56.7749	-27.12	2214.22	0.012

Pole Bending Design Data

Section No.	Elevation ft	Size	Actual M _x kip-ft	Actual f _{bx} ksi	Allow. F _{bx} ksi	Ratio $\frac{f_{bx}}{F_{bx}}$	Actual M _y kip-ft	Actual f _{by} ksi	Allow. F _{by} ksi	Ratio $\frac{f_{by}}{F_{by}}$
L1	109 - 95 (1)	TP26.715x23.476x0.1875	71.52	8.299	39.000	0.213	0.00	0.000	39.000	0.000
L2	95 - 48.0833 (2)	TP37.573x26.715x0.3125	649.27	24.415	39.000	0.626	0.00	0.000	39.000	0.000
L3	48.0833 - 0 (3)	TP48.075x35.8101x0.375	1755.5 5	31.524	39.000	0.808	0.00	0.000	39.000	0.000

Pole Shear Design Data

Section No.	Elevation ft	Size	Actual V K	Actual f _v ksi	Allow. F _v ksi	Ratio $\frac{f_v}{F_v}$	Actual T kip-ft	Actual f _{vt} ksi	Allow. F _{vt} ksi	Ratio $\frac{f_{vt}}{F_{vt}}$
L1	109 - 95 (1)	TP26.715x23.476x0.1875	5.62	0.356	26.000	0.027	1.46	0.083	26.000	0.003
L2	95 - 48.0833 (2)	TP37.573x26.715x0.3125	18.89	0.527	26.000	0.041	1.72	0.032	26.000	0.001
L3	48.0833 - 0 (3)	TP48.075x35.8101x0.375	22.86	0.403	26.000	0.031	1.75	0.015	26.000	0.001

Pole Interaction Design Data

Section No.	Elevation ft	Ratio P P _a	Ratio f _{bx} F _{bx}	Ratio f _{by} F _{by}	Ratio f _v F _v	Ratio f _{vt} F _{vt}	Comb. Stress Ratio	Allow. Stress Ratio	Criteria
L1	109 - 95 (1)	0.005	0.213	0.000	0.027	0.003	0.218	1.333	H1-3+VT ✓

Section No.	Elevation ft	Ratio P P_a	Ratio f_{bx} F_{bx}	Ratio f_{by} F_{by}	Ratio f_v F_v	Ratio f_{vt} F_{vt}	Comb. Stress Ratio	Allow. Stress Ratio	Criteria
L2	95 - 48.0833 (2)	0.011	0.626	0.000	0.041	0.001	0.637 ✓	1.333	H1-3+VT ✓
L3	48.0833 - 0 (3)	0.012	0.808	0.000	0.031	0.001	0.821 ✓	1.333	H1-3+VT ✓

Section Capacity Table

Section No.	Elevation ft	Component Type	Size	Critical Element	P K	SF* P_{allow} K	% Capacity	Pass Fail
L1	109 - 95	Pole	TP26.715x23.476x0.1875	1	-3.28	820.73	16.4	Pass
L2	95 - 48.0833	Pole	TP37.573x26.715x0.3125	2	-15.18	1862.65	47.8	Pass
L3	48.0833 - 0	Pole	TP48.075x35.8101x0.375	3	-27.12	2951.56	61.6	Pass
Summary								
Pole (L3)							61.6	Pass
RATING =							61.6	Pass

APPENDIX B
BASE LEVEL DRAWING




(INSTALLED)
(1) 3/8" TO 107 FT LEVEL
(2) 3/4" TO 107 FT LEVEL
(12) 1-5/8" TO 107 FT LEVEL

(INSTALLED)
(18) 1-1/4" TO 90 FT LEVEL

(INSTALLED)
(12) 7/8" TO 80 FT LEVEL

(PROPOSED)
(1) 5/8" TO 72 FT LEVEL
(INSTALLED)
(1) 1/2" TO 47 FT LEVEL
(3) 1-1/4" TO 72 FT LEVEL

(INSTALLED)
(6) 1-5/8" TO 62 FT LEVEL



APPENDIX C
ADDITIONAL CALCULATIONS

Stiffened or Unstiffened, Exterior Flange Plate - Any Bolt Material TIA Rev F

Site Data

BU#: 801486
 Site Name: CT SUFFIELD 2 CAC 801
 App #: 208200, Rev 4

Pole Manufacturer: Other

Bolt Data

Qty:	20	Bolt Fu:	120
Diameter (in.):	1	Bolt Fy:	92
Bolt Material:	A325	Bolt Fty:	44.00
N/A:		<-- Disregard	
N/A:		<-- Disregard	
Circle (in.):	33		

Plate Data

Diam:	36	in
Thick, t:	2.25	in
Grade (Fy):	60	ksi
Strength, Fu:	75	ksi
Single-Rod B-eff:	4.24	in

Stiffener Data (Welding at Both Sides)

Config:	0	*
Weld Type:		
Groove Depth:		in **
Groove Angle:		degrees
Fillet H. Weld:		<-- Disregard
Fillet V. Weld:		in
Width:		in
Height:		in
Thick:		in
Notch:		in
Grade:		ksi
Weld str.:		ksi

Pole Data

Diam:	26.715	in
Thick:	0.1875	in
Grade:	65	ksi
# of Sides:	18	"0" IF Round
Fu	80	ksi
Reinf. Fillet Weld	0	"0" if None

Stress Increase Factor

ASIF: 1.333

Reactions

Moment:	71.52	ft-kips
Axial:	3.28	kips
Shear:	5.62	kips
Elevation:	95	feet

If No stiffeners, Criteria: AISC ASD <-Only Applicable to Unstiffened Cases

Flange Bolt Results

Bolt Tension Capacity, B: 46.07 kips
 Max Bolt directly applied T: 5.04 Kips
 Min. PL "tc" for B cap. w/o Pry: 1.703 in
 Min PL "treq" for actual T w/ Pry: 0.426 in
 Min PL "t1" for actual T w/o Pry: 0.563 in
 T allowable w/o Prying: 46.07 kips
 Prying Force, Q: 0.00 kips
 Total Bolt Tension=T+Q: 5.04 kips
 Non-Prying Bolt Stress Ratio, T/B: 10.9% **Pass**

Rigid
Service, ASD
Fty*ASIF

Exterior Flange Plate Results

Flexural Check
 Compression Side Plate Stress: 2.7 ksi
 Allowable Plate Stress: 60.0 ksi
 Compression Plate Stress Ratio: 4.5% **Pass**
No Prying
 Tension Side Stress Ratio, (treq/t)^2: 3.6% **Pass**

Rigid
Service ASD
0.75*Fy*ASIF
Comp. Y.L. Length: 19.37



n/a

Stiffener Results

Horizontal Weld : n/a
 Vertical Weld: n/a
 Plate Flex+Shear, fb/Fb+(fv/Fv)^2: n/a
 Plate Tension+Shear, ft/Ft+(fv/Fv)^2: n/a
 Plate Comp. (AISC Bracket): n/a

Pole Results

Pole Punching Shear Check: n/a



* 0 = none, 1 = every bolt, 2 = every 2 bolts, 3 = 2 per bolt

** Note: for complete joint penetration groove welds the groove depth must be exactly 1/2 the stiffener thickness for calculation purposes

Stiffened or Unstiffened, Ungrouted, Circular Base Plate - Any Rod Material

TIA Rev F

Site Data

BU#: 801486
Site Name: CT SUFFIELD 2 CAC 801
App #: 208200, Rev 4
Pole Manufacturer: Other

Reactions		
Moment:	1756	ft-kips
Axial:	27	kips
Shear:	23	kips

Anchor Rod Data

Qty:	16	
Diam:	2.25	in
Rod Material:	A615-J	
Strength (Fu):	100	ksi
Yield (Fy):	75	ksi
Bolt Circle:	55	in

If No stiffeners, Criteria: **AISC ASD** <-Only Applicable to Unstiffened Cases

Anchor Rod Results

Maximum Rod Tension:	94.1 Kips
Allowable Tension:	195.0 Kips
Anchor Rod Stress Ratio:	48.3% Pass

Rigid
Service, ASD
Fty*ASIF

Plate Data

Diam:	61	in
Thick:	2.75	in
Grade:	60	ksi
Single-Rod B-eff:	9.54	in

Base Plate Results

Base Plate Stress:	17.4 ksi	Flexural Check
Allowable Plate Stress:	60.0 ksi	
Base Plate Stress Ratio:	28.9% Pass	

Rigid
Service ASD
0.75*Fy*ASIF
Y.L. Length:
26.72

Stiffener Data (Welding at both sides)

Config:	0	*
Weld Type:		
Groove Depth:		in **
Groove Angle:		degrees
Fillet H. Weld:		<-- Disregard
Fillet V. Weld:		in
Width:		in
Height:		in
Thick:		in
Notch:		in
Grade:		ksi
Weld str.:		ksi

n/a

Stiffener Results

Horizontal Weld :	n/a
Vertical Weld:	n/a
Plate Flex+Shear, fb/Fb+(fv/Fv)^2:	n/a
Plate Tension+Shear, ft/Ft+(fv/Fv)^2:	n/a
Plate Comp. (AISC Bracket):	n/a

Pole Results


Pole Punching Shear Check:	n/a
----------------------------	-----

Pole Data

Diam:	48.075	in
Thick:	0.375	in
Grade:	65	ksi
# of Sides:	18	"0" IF Round
Fu	80	ksi
Reinf. Fillet Weld	0	"0" if None

Stress Increase Factor

ASIF:	1.333
-------	-------



* 0 = none, 1 = every bolt, 2 = every 2 bolts, 3 = 2 per bolt

** Note: for complete joint penetration groove welds the groove depth must be exactly 1/2 the stiffener thickness for calculation purposes

Monopole Pier and Pad Foundation

BU #: 801486

Site Name: CT SUFFIELD 2 CAC 801486

App. Number: 208200, Rev 4

TIA-222 Revision: **F**



Design Reactions		
Shear, S:	23	kips
Moment, M:	1756	ft-kips
Tower Height, H:	109	ft
Tower Weight, Wt:	27	kips
Base Diameter, BD:	4.00	ft

Foundation Dimensions		
Depth, D:	6.5	ft
Pad Width, W:	26	ft
Neglected Depth, N:	4	ft
Thickness, T:	2.50	ft
Pier Diameter, Pd:	6.50	ft
Ext. Above Grade, E:	0.50	ft
BP Dist. Above Pier:	3	in.
Clear Cover, Cc:	3.0	in

Soil Properties		
Soil Unit Weight, γ :	0.120	kcf
Ult. Bearing Capacity, Bc:	8.0	ksf
Angle of Friction, Φ :	0	deg
Cohesion, Co:	1.150	ksf
Passive Pressure, Pp:	0.000	ksf
Base Friction, μ :	0.35	

Material Properties		
Rebar Yield Strength, Fy:	60000	psi
Concrete Strength, F'c:	3000	psi
Concrete Unit Weight, δ_c :	0.150	kcf
Seismic Zone, z:	1	

Rebar Properties		
Pier Rebar Size, Sp:	9	
Pier Rebar Quantity, mp:	32	24
Pad Rebar Size, Spad:	9	
Pad Rebar Quantity, mpad:	22	9
Pier Tie Size, St:	5	3
Tie Quantity, mt:	9	5

Design Checks			
	Capacity/Availability	Demand/Limits	Check
<i>Req'd Pier Diam.(ft)</i>	6.5	5.5	OK
<i>Overturning (ft-kips)</i>	4921.63	1756.00	35.7%
<i>Shear Capacity (kips)</i>	107.00	23.00	21.5%
<i>Bearing (ksf)</i>	6.00	1.67	27.8%
<i>Pad Shear - 1-way (kips)</i>	677.64	349.21	51.5%
<i>Pad Shear - 2-way (kips)</i>	1425.21	80.39	5.6%
<i>Pad Moment Capacity (k-ft)</i>	2535.04	852.68	33.6%
<i>Pier Moment Capacity (k-ft)</i>	3607.03	1859.50	51.6%

RADIO FREQUENCY FCC REGULATORY COMPLIANCE
MAXIMUM PERMISSIBLE EXPOSURE (MPE) ASSESSMENT

Sprint Existing Facility

Site ID: CT43XC829

Windsor Locks (Crown)

44 Flyer Place
Suffield, CT 06078

March 21, 2014

EBI Project Number: 62141425

March 21, 2014

Sprint
Attn: RF Engineering Manager
1 International Boulevard, Suite 800
Mahwah, NJ 07495

Re: Radio Frequency Maximum Permissible Exposure (MPE) Assessment for Site:
CT43XC829 - Windsor Locks (Crown)

Site Total: 118.223% - MPE% NOT IN compliance for General Public Thresholds

EBI Consulting was directed to analyze the proposed upgrades to the existing Sprint facility located at 44 Flyer Place, Suffield, CT, for the purpose of determining whether the radio frequency (RF) exposure levels from the proposed Sprint equipment upgrades on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter ($\mu\text{W}/\text{cm}^2$). The number of $\mu\text{W}/\text{cm}^2$ calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits, therefore it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) – (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general public may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general public would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

Public exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter ($\mu\text{W}/\text{cm}^2$). The general population exposure limit for the cellular band (850 MHz Band) is approximately $567 \mu\text{W}/\text{cm}^2$, and the general population exposure limit for the 1900 MHz and 2500 MHz bands is $1000 \mu\text{W}/\text{cm}^2$. Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.

Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure. Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

CALCULATIONS

Calculations were done for the proposed upgrades to the existing Sprint Wireless antenna facility located at 44 Flyer Place, Suffield, CT, using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. All calculations were performed assuming the main lobe of the antenna was focused at the base of the tower to present a worst case scenario. Actual values seen from this site will be dramatically less than those shown in this report. For this report the sample point is the top of a 6 foot person standing at the base of the tower.

For all calculations, all emissions were calculated using the following assumptions:

- 1) 2 channels in the 1900 MHz Band were considered for each sector of the proposed installation.
- 2) 1 channel in the 800 MHz Band was considered for each sector of the proposed installation
- 3) 2 channels in the 2500 MHz Band were considered for each sector of the proposed installation.
- 4) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 - Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.
- 5) For the following calculations the sample point was the top of a six foot person standing at the base of the tower. The maximum gain of the antenna per the antenna manufactures supplied specifications was used in this direction.

- 6) The antennas used in this modeling are the RFS APXVSPP18-C-A20 and the RFS APXVTMM-C-120. This is based on feedback from the carrier with regards to anticipated antenna selection. The RFS APXVSPP18-C-A20 has a 15.9 dBd gain value at its main lobe at 1900 MHz and 13.4 dBd at its main lobe for 850 MHz. The RFS APXVTMM-C-120 has a 15.9 dBd gain value at its main lobe at 2500 MHz. All calculations were performed assuming the main lobe of the antenna was focused at the base of the tower to present a worst case scenario.
- 7) The antenna mounting height centerline for the proposed antennas is **74 feet** above ground level (AGL).
- 8) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.

All calculation were done with respect to uncontrolled / general public threshold limits

Site ID	CT43XC829 - Windsor Locks (Crown)
Site Address	44 Flyer Place, Suffield, CT 06078
Site Type	Monopole

Sector 1

Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain in direction of sample point (dBd)	Antenna Height (ft)	analysis height	Cable Size	Cable Loss (dB)	Additional Loss (dB)	ERP	Power Density Percentage
1a	RFS	APXVSP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	2	40	15.9	74	68	1/2 "	0.5	3	695.12033	5.40441%
1a	RFS	APXVSP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	13.4	74	68	1/2 "	0.5	3	195.44744	2.68000%
1B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	13.4	74	68	1/2 "	0.5	3	390.89489	5.36000%
Sector total Power Density Value:																13.444%

Sector 2

Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain in direction of sample point (dBd)	Antenna Height (ft)	analysis height	Cable Size	Cable Loss (dB)	Additional Loss (dB)	ERP	Power Density Percentage
2a	RFS	APXVSP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	2	40	15.9	74	68	1/2 "	0.5	3	695.12033	5.40441%
2a	RFS	APXVSP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	13.4	74	68	1/2 "	0.5	3	195.44744	2.68000%
2B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	13.4	74	68	1/2 "	0.5	3	390.89489	5.36000%
Sector total Power Density Value:																13.444%

Sector 3

Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain in direction of sample point (dBd)	Antenna Height (ft)	analysis height	Cable Size	Cable Loss (dB)	Additional Loss (dB)	ERP	Power Density Percentage
3a	RFS	APXVSP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	2	40	15.9	74	68	1/2 "	0.5	3	695.12033	5.40441%
3a	RFS	APXVSP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	13.4	74	68	1/2 "	0.5	3	195.44744	2.68000%
3B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	13.4	74	68	1/2 "	0.5	3	390.89489	5.36000%
Sector total Power Density Value:																13.444%

Site Composite MPE %	
Carrier	MPE %
Sprint	40.333%
AT&T	3.570%
Verizon Wireless	48.330%
MetroPCS	17.710%
Nextel	8.280%
Total Site MPE %	118.223%

Summary

Calculations performed for this analysis yielded results that were above the allowable limits for general public Maximum Permissible Exposure (MPE) to radio frequency energy. However, the area surrounding the tower is a controlled fenced compound, occupational threshold limits would apply to this area.

The anticipated Maximum Composite contributions from the Sprint facility are **40.333%** (**13.444% from each sector**) of the allowable FCC established general public limit considering all three sectors simultaneously sampled at the ground level. This is equal to **8.067%** (**2.689% from each sector**) of the allowable FCC established occupational limit considering all three sectors simultaneously sampled at the ground level.

The anticipated composite MPE value for this site assuming all carriers present is **118.223%** of the allowable FCC established general public limit sampled at the 6 feet above ground level. This is equal to **23.645%** of the allowable FCC established occupational limit sampled at the ground level. This total composite site value is based upon MPE values listed in the Connecticut Siting Council database for existing carrier emissions.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. Although values could potentially exceed the FCC established general public limit at the base of the tower, this area is well within the FCC established occupational limit for this same area and should be considered in compliance since it is a controlled area.



Scott Heffernan
RF Engineering Director

EBI Consulting

21 B Street
Burlington, MA 01803