AIROSMITH DEVELOPMENT
We do it right the first time.

January 30th, 2018

Melanie Bachman, Executive Director
Connecticut Siting Council
10 Franklin Square
New Britain, CT 06051

RE: Notice of Exempt Modification – Antenna Swap for wireless facility located at 1 EAGLE HILL, TOLLAND CONNECTICUT – CT03XC207 (lat. 42° 52' 24.43" N, long. -72° 20' 18.66" W)

Dear Ms. Bachman:

Sprint Spectrum, LP ("Sprint") currently maintains wireless telecommunications antennas at the (133-foot level) on an existing (153-foot monopole tower) at the above-referenced address. The property is owned by the Town of Tolland, and the tower is owned by American Tower Corporation.

Sprint's proposed work involves antenna replacement and tower work. Sprint intends to replace three (3) antennas, relocate three (3) RRHs from ground level to the tower and add nine (9) new RRHs onto the tower. All the proposed work is contained within the existing fenced area. Please refer to the attached drawings for site plans prepared by Infinigy Engineering.

Please accept this letter as notification pursuant to R.C.S.A. § 16-50j-73, for construction that constitutes an exempt modification pursuant to R.C.S.A. § 16-50j-72(b). In accordance with R.C.S.A. § 16-50j-73, a copy of this letter is being sent to STEVEN R. WERBNER, TOWN MANGER, and HEIDI SAMOKAR, DIRECTOR of PLANNING AND DEVELOPMENT of the Town of TOLLAND. A copy of this letter is also being sent to JUSTINE PAUL the manager for AMERICAN TOWER CORPORATION who manages the site and owns the land.

The planned modifications to the facility fall squarely within those activities explicitly provided for in R.C.S.A. § 16-50j-72(b).

1. The proposed modifications will not result in an increase in the height of the existing tower.
2. The antennas work is a one-for-one replacement of facility components.
3. The proposed modifications will include the addition of ground base equipment as

32 Clinton Street, Saratoga Springs, NY 12866
Office 518-306-1733 – Fax 518-306-1711
www.airosmithdevelopment.com

AIROSMITH DEVELOPMENT
We do it right the first time.

depicted on the attached drawings; however, the proposed equipment will not require an extension of the site boundaries.

4. The proposed modifications will not increase noise levels at the facility by six decibels or more.

5. The additional ground based equipment will not increase radio frequency (RF) emissions at the facility to a level at or above the Federal Communications Commission (FCC) adopted safety standard.

For the foregoing reasons, Sprint respectfully submits that the proposed modifications to the above referenced telecommunications facility constitutes an exempt modification under R.C.S.A. § 16-50j-72(b).

If you have any questions or require any additional information regarding this request, please do not hesitate to give me a call at (518) 350-4222 or email me to aperkowski@airosmithdevelopment.com

Kind Regards,

Arthur Perkowski
Airosmith Development Inc.
32 Clinton Street
Saratoga Springs, NY 12866
518-306-1711 desk & fax
518-871-3707 cell
aperkowski@airosmithdevelopment.com

Attachment

CC: STEVEN R. WERBNER (Town Manager, TOLLAND, CT)
JUSTINE PAUL (Manager, AMERICAN TOWER CORPORATION)
HEIDI SAMOKAR (Director of Planning & Development / TOLLAND, CT)

U.S. Postal Service™
CERTIFIED MAIL® RECEIPT
Domestic Mail Only

For delivery information, visit our website at www.usps.com®.

TOLLAND, CT 06084

OFFICIAL USE

Certified Mail Fee $3.45

Extra Services & Fees (check box, add fee as appropriate)
- Return Receipt (hardcopy) $0.00
- Return Receipt (electronic) $0.00
- Certified Mail Restricted Delivery $0.00
- Adult Signature Required $0.00
- Adult Signature Restricted Delivery $

Postage $0.50

Total Postage and Fees $6.70

Postmark Here
SARATOGA FINANCE
SARATOGA SPRINGS, NY 12866
0867 06
JAN 25 2018
01/25/2018

Sent To Steven Werbner (CT03XC207)
Street and Apt. No., or PO Box No. 21 Tolland Green, 5th Floor
City, State, ZIP+4® Tolland CT 06084-2819

PS Form 3800, April 2015 PSN 7530-02-000-9047 See Reverse for Instructions

7017 1450 0002 2926 7786

U.S. Postal Service™
CERTIFIED MAIL® RECEIPT
Domestic Mail Only

For delivery information, visit our website at www.usps.com®.

TOLLAND, CT 06084

OFFICIAL USE

Certified Mail Fee $3.45

Extra Services & Fees (check box, add fee as appropriate)
- Return Receipt (hardcopy) $0.00
- Return Receipt (electronic) $0.00
- Certified Mail Restricted Delivery $0.00
- Adult Signature Required $0.00
- Adult Signature Restricted Delivery $

Postage $0.50

Total Postage and Fees $6.70

Postmark Here
SARATOGA FINANCE
SARATOGA SPRINGS, NY
0867 17
JAN 30 2018
01/30/2018

Sent To Heidi Symoker (CT03XC207)
Street and Apt. No., or PO Box No. 21 Tolland Green, 3rd Floor
City, State, ZIP+4® Tolland, CT 06084-2819

PS Form 3800, April 2015 PSN 7530-02-000-9047 See Reverse for Instructions

7017 3040 0000 5168 0235

U.S. Postal Service™
CERTIFIED MAIL® RECEIPT
Domestic Mail Only

For delivery information, visit our website at www.usps.com®.

WOBURN, MA 01801

OFFICIAL USE

Certified Mail Fee $3.45

Extra Services & Fees (check box, add fee as appropriate)
- Return Receipt (hardcopy) $0.00
- Return Receipt (electronic) $0.00
- Certified Mail Restricted Delivery $0.00
- Adult Signature Required $0.00
- Adult Signature Restricted Delivery $

Postage $0.50

Total Postage and Fees $6.70

Postmark Here
SARATOGA FINANCE
SARATOGA SPRINGS, NY 12866
0867 06
JAN 25 2018
01/25/2018

Sent To Jesse Paul (CT03XC207)
Street and Apt. No., or PO Box No. 10 Presidential Way
City, State, ZIP+4® Woburn MA 01801-2085

PS Form 3800, April 2015 PSN 7530-02-000-9047 See Reverse for Instructions

7017 1450 0002 2926 7519

1 EAGLE HILL

Location	1 EAGLE HILL	**Mblu**	23/ E/ 51/00 /
Acct#	6783	**Owner**	TOWN OF TOLLAND
Assessment	$47,896,000	**Appraisal**	$68,422,700
PID	3893	**Building Count**	1

Current Value

Appraisal			
Valuation Year	**Improvements**	**Land**	**Total**
2014	$65,645,700	$2,777,000	$68,422,700
Assessment			
Valuation Year	**Improvements**	**Land**	**Total**
2014	$45,952,100	$1,943,900	$47,896,000

Owner of Record

Owner	TOWN OF TOLLAND	**Sale Price**	$850,000
Co-Owner		**Certificate**	
Address	21 TOLLAND GREEN TOLLAND, CT 06084-0000	**Book & Page**	819/ 81
		Sale Date	04/24/2003
		Instrument	15

Ownership History

Ownership History					
Owner	**Sale Price**	**Certificate**	**Book & Page**	**Instrument**	**Sale Date**
TOWN OF TOLLAND	$850,000		819/ 81	15	04/24/2003
RUOPS ALBERT J TRUSTEE U TR	$0		396/ 288	29	06/16/1960

Building Information

Building 1 : Section 1

Year Built:	2005
Living Area:	258,330
Replacement Cost:	$69,099,782
Building Percent Good:	91
Replacement Cost Less Depreciation:	$62,880,800

Building Attributes

Field	Description
STYLE	Schools-Public
MODEL	Commercial
Grade	Excellent
Stories:	2
Occupancy	1
Ext Wall 1	Brick Veneer
Exterior Wall 2	Reinforc Concr
Roof Structure	Flat
Roof Cover	Tar & Gravel
Interior Wall 1	Minim/Masonry
Interior Wall 2	Drywall/Sheet
Interior Floor 1	Vinyl/Asphalt
Interior Floor 2	
Heating Fuel	Oil
Heating Type	Hot Water
AC Type	Vapor Cooler
Bldg Use	Municipal
Total Rooms	70
Total Bedrms	0
Total Baths	0
Solar	
1st Floor Use:	901C
Heat/AC	Heat/AC Split
Frame Type	Fireprf Steel
Baths/Plumbing	Average
Ceiling/Wall	Sus Ceil Min W
Rooms/Prtns	Above Average
Wall Height	16
% Comn Wall	

Building Photo

(http://images.vgsi.com/photos/TollandCTPhotos//\00\00\69/90.

Building Layout



Building Sub-Areas (sq ft)			Legend
Code	Description	Gross Area	Living Area
BAS	Main Floor	177,914	177,914
FUS	Finished Upper Story	80,416	80,416
CAN	Canopy	2,640	0
CLP	Covered Loading Platform	380	0
FOP	Open Porch	202	0
GRN	Green House	540	0
ULP	Loading Platform	728	0
		262,820	258,330

Extra Features

Extra Features				Legend
Code	Description	Size	Value	Bldg #
SPR1	SPRINKLERS-WET	248306 S.F.	$180,800	1
ELV	ELEVATOR	1 UNITS	$24,600	1

Land

Land Use

Use Code	901C
Description	Municipal
Zone	RDD
Neighborhood	350C
Alt Land Appr	No
Category	

Land Line Valuation

Size (Acres)	68.5
Frontage	1351
Depth	
Assessed Value	$1,943,900
Appraised Value	$2,777,000

Outbuildings

Outbuildings						Legend
Code	**Description**	**Sub Code**	**Sub Description**	**Size**	**Value**	**Bldg #**
PAV	PAVING	A	Asphalt	480000 S.F.	$645,100	1
FN	FENCE	CL4	4' Chain Link	7500 L.F.	$50,400	1
PLS	POLES	L1	Lighting	48 UNITS	$121,000	1
BALL	FIELD HARD			1 UNITS	$702,000	1
TRL1	TRAILER	A	Storage	640 S.F.	$9,600	1
FGR	GARAGE	1F	1Story Frame	720 S.F.	$16,800	1
FGR	GARAGE	1F	1Story Frame	720 S.F.	$16,800	1
SHD	SHED	1LT	1 Stry Lean To	1024 S.F.	$9,200	1
BALL	FIELD HARD			2 UNITS	$650,000	1
AF	ATHLETIC FLD	FB	Football	1 UNITS	$126,000	1
AF	ATHLETIC FLD	RT	Running Trck	1 UNITS	$210,000	1
SHD	SHED	1F	1 Stry Frame	160 S.F.	$2,600	1

Valuation History

Appraisal			
Valuation Year	**Improvements**	**Land**	**Total**
2015	$65,645,700	$2,777,000	$68,422,700
2014	$65,645,700	$2,777,000	$68,422,700
2013	$62,968,300	$3,111,000	$66,079,300

Assessment			
Valuation Year	**Improvements**	**Land**	**Total**
2015	$45,952,100	$1,943,900	$47,896,000
2014	$45,952,100	$1,943,900	$47,896,000
2013	$44,077,800	$2,177,700	$46,255,500

CT03XC207 - 1 Eagle Hill, Tolland, CT 06084



Property Information

Property ID	23/E/051
Location	1 EAGLE HILL
Owner	TOWN OF TOLLAND

MAP FOR REFERENCE ONLY
NOT A LEGAL DOCUMENT

Town of Tolland, CT makes no claims and no warranties, expressed or implied, concerning the validity or accuracy of the GIS data presented on this map.

Properties updated 12/06/2017

EBI Consulting
environmental | engineering | due diligence

RADIO FREQUENCY EMISSIONS ANALYSIS REPORT
EVALUATION OF HUMAN EXPOSURE POTENTIAL TO NON-IONIZING EMISSIONS

SPRINT Existing Facility

Site ID: CT03XC207

SNET - Tolland
1 Eagle Hill
Tolland, CT 06084

January 16, 2018

EBI Project Number: 6218000235

Site Compliance Summary	
Compliance Status:	COMPLIANT
Site total MPE% of FCC general population allowable limit:	10.85 %

EBI Consulting
environmental | engineering | due diligence

January 16, 2018

SPRINT
Attn: RF Engineering Manager
1 International Boulevard, Suite 800
Mahwah, NJ 07495

Emissions Analysis for Site: **CT03XC207 – SNET - Tolland**

EBI Consulting was directed to analyze the proposed SPRINT facility located at **1 Eagle Hill, Tolland, CT**, for the purpose of determining whether the emissions from the Proposed SPRINT Antenna Installation located on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter (μW/cm2). The number of $\mu W/cm^2$ calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits, therefore it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) – (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general population may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general population would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

General population exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter ($\mu W/cm^2$). The general population exposure limits for the 850 MHz Band is approximately 567 $\mu W/cm^2$. The general population exposure limit for the 1900 MHz (PCS) and 2500 MHz (BRS) bands is 1000 $\mu W/cm^2$. Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.

Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure. Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

CALCULATIONS

Calculations were done for the proposed SPRINT Wireless antenna facility located at **1 Eagle Hill, Tolland, CT**, using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. Since SPRINT is proposing highly focused directional panel antennas, which project most of the emitted energy out toward the horizon, all calculations were performed assuming a lobe representing the maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was focused at the base of the tower. For this report the sample point is the top of a 6-foot person standing at the base of the tower.

For all calculations, all equipment was calculated using the following assumptions:

1) 1 CDMA channels (850 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 20 Watts per Channel.

2) 2 LTE channels (850 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 20 Watts per Channel.

3) 5 CDMA channels (1900 MHz (PCS)) were considered for each sector of the proposed installation. These Channels have a transmit power of 16 Watts per Channel.

4) 2 LTE channels (1900 MHz (PCS)) were considered for each sector of the proposed installation. These Channels have a transmit power of 40 Watts per Channel.

5) 8 LTE channels (2500 MHz (BRS)) were considered for each sector of the proposed installation. These Channels have a transmit power of 20 Watts per Channel.

6) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 - Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.

7) For the following calculations, the sample point was the top of a 6-foot person standing at the base of the tower. The maximum gain of the antenna per the antenna manufactures supplied specifications minus 10 dB was used in this direction. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.

8) The antennas used in this modeling are the **KMW ETCR-654L12H6** for transmission in the 850 MHz, 1900 MHz (PCS) and 2500 MHz (BRS) frequency bands. This is based on feedback from the carrier with regards to anticipated antenna selection. Maximum gain values for all antennas are listed in the Inventory and Power Data table below. The maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was used for all calculations. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction. There is also one existing antenna per sector that will remain but appears dormant.

9) The antenna mounting height centerlines of the proposed antennas are **133 feet** above ground level (AGL) for **Sector A**, **133 feet** above ground level (AGL) for **Sector B** and **133 feet** above ground level (AGL) for Sector C.

10) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.

All calculations were done with respect to uncontrolled / general population threshold limits.

SPRINT Site Inventory and Power Data by Antenna

Sector:	A	Sector:	B	Sector:	C
Antenna #:	**1**	Antenna #:	**1**	Antenna #:	**1**
Make / Model:	KMW ETCR-654L12H6	Make / Model:	KMW ETCR-654L12H6	Make / Model:	KMW ETCR-654L12H6
Gain:	13.35 / 15.25 / 15.05 dBd	Gain:	13.35 / 15.25 / 15.05 dBd	Gain:	13.35 / 15.25 / 15.05 dBd
Height (AGL):	**133 feet**	Height (AGL):	**133 feet**	Height (AGL):	**133 feet**
Frequency Bands	850 MHz / 1900 MHz (PCS) / 2500 MHz (BRS)	Frequency Bands	850 MHz / 1900 MHz (PCS) / 2500 MHz (BRS)	Frequency Bands	850 MHz / 1900 MHz (PCS) / 2500 MHz (BRS)
Channel Count	18	Channel Count	18	Channel Count	18
Total TX Power(W):	380 Watts	Total TX Power(W):	380 Watts	Total TX Power(W):	380 Watts
ERP (W):	11,775.31	ERP (W):	11,775.31	ERP (W):	11,775.31
Antenna A1 MPE%	**2.85 %**	Antenna B1 MPE%	**2.85 %**	Antenna C1 MPE%	**2.85 %**

Site Composite MPE%	
Carrier	**MPE%**
SPRINT – Max per sector	**2.85 %**
T-Mobile	1.75 %
AT&T	2.98 %
Verizon Wireless	2.83 %
Nextel	0.44 %
Site Total MPE %:	**10.85 %**

SPRINT Sector A Total:	2.85 %
SPRINT Sector B Total:	2.85 %
SPRINT Sector C Total:	2.85 %
Site Total:	10.85 %

SPRINT _ Frequency Band / Technology (All Sectors)	# Channels	Watts ERP (Per Channel)	Height (feet)	Total Power Density ($\mu W/cm^2$)	Frequency (MHz)	Allowable MPE ($\mu W/cm^2$)	Calculated % MPE
Sprint 850 MHz CDMA	1	432.54	133	0.96	850 MHz	567	0.17%
Sprint 850 MHz LTE	2	432.54	133	1.93	850 MHz	567	0.34%
Sprint 1900 MHz (PCS) CDMA	5	535.94	133	5.97	1900 MHz (PCS)	1000	0.60%
Sprint 1900 MHz (PCS) LTE	2	1,339.86	133	5.97	1900 MHz (PCS)	1000	0.60%
Sprint 2500 MHz (BRS) LTE	8	639.78	133	11.41	2500 MHz (BRS)	1000	1.14%
						Total:	**2.85%**

Summary

All calculations performed for this analysis yielded results that were **within** the allowable limits for general population exposure to RF Emissions.

The anticipated maximum composite contributions from the SPRINT facility as well as the site composite emissions value with regards to compliance with FCC's allowable limits for general population exposure to RF Emissions are shown here:

SPRINT Sector	Power Density Value (%)
Sector A:	2.85 %
Sector B:	2.85 %
Sector C:	2.85 %
SPRINT Maximum Total (per sector):	2.85 %
Site Total:	10.85 %
Site Compliance Status:	**COMPLIANT**

The anticipated composite MPE value for this site assuming all carriers present is **10.85 %** of the allowable FCC established general population limit sampled at the ground level. This is based upon values listed in the Connecticut Siting Council database for existing carrier emissions.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.

AMERICAN TOWER®
CORPORATION

Structural Analysis Report

Structure	:	**155 ft Monopole**
ATC Site Name	:	**Tolland CT, CT**
ATC Site Number	:	**302495**
Engineering Number	:	**OAA714899_C3_01**
Proposed Carrier	:	**Sprint Nextel**
Carrier Site Name	:	**SNET - Tolland**
Carrier Site Number	:	**CT03XC207**
Site Location	:	**5 Barbara Road** **Tolland, CT 06084-3116** **41.873300,-72.338300**
County	:	**Tolland**
Date	:	**November 15, 2017**
Max Usage	:	**87%**
Result	:	**Pass**

Prepared By:
Robert D. Barrett, E.I.
Structural Engineer II

Robert D. Barrett

Reviewed By:

COA: PEC.0001553

AMERICAN TOWER®
CORPORATION

Table of Contents

Introduction

The purpose of this report is to summarize results of a structural analysis performed on the 155 ft monopole to reflect the change in loading by Sprint Nextel.

Supporting Documents

Tower Drawings	EEI Drawing #GS50842 Rev 1, dated June 24, 1998
Foundation Drawing	EEI Drawing #F3503-150.N, dated March 2, 1998
Geotechnical Report	ASR Project #12-06077, dated December 1, 2006
Modifications	Spectrasite Drawing #CT-0031-M1, dated November 15, 2004

Analysis

The tower was analyzed using American Tower Corporation's tower analysis software. This program considers an elastic three-dimensional model and second-order effects per ANSI/TIA-222.

Basic Wind Speed:	97 mph (3-Second Gust, V_{asd}) / 125 mph (3-Second Gust, V_{ult})
Basic Wind Speed w/ Ice:	50 mph (3-Second Gust) w/ 1" radial ice concurrent
Code:	ANSI/TIA-222-G / 2012 IBC / 2016 Connecticut State Building Code
Structure Class:	II
Exposure Category:	B
Topographic Category:	1
Crest Height:	0 ft
Spectral Response:	Ss = 0.17, S_1 = 0.06
Site Class:	D - Stiff Soil

Conclusion

Based on the analysis results, the structure meets the requirements per the applicable codes listed above. The tower and foundation can support the equipment as described in this report.

If you have any questions or require additional information, please contact American Tower via email at Engineering@americantower.com. Please include the American Tower site name, site number, and engineering number in the subject line for any questions.

Existing and Reserved Equipment

Elevation[1] (ft)		Qty	Antenna	Mount Type	Lines	Carrier
Mount	RAD					
155.0	164.0	3	EMS RR90-17-02DP	Flush	(6) 1 5/8" Coax	T-Mobile
	159.0	6	Ericsson KRY 112 71/x			
149.0	152.0	1	7' Omni	Platform w/ Handrails	(1) 1 1/4" Coax	Spok Holdings
	149.0	1	Andrew ABT-DMDF-ADBH		(12) 1 1/4" Coax (2) 0.78" 8 AWG 6 (1) 0.39" Fiber Trunk (1) 3" Conduit (1) 3/8" RET Control Cable	AT&T Mobility
		3	Powerwave 7020.00 Dual Band RET			
		6	Kathrein 782-10250			
		6	CCI DTMABP7819VG12A			
		1	Raycap DC6-48-60-18-8F			
		3	Ericsson RRUS 11 (Band 12)			
		3	Ericsson RRUS-12 800MHz			
		3	Powerwave 7770.00			
		6	KMW AM-X-CD-16-65-00T-RET			
143.0	143.0	3	Nokia B5 RRH4x40-850	Platform w/ Handrails	(14) 1 5/8" Coax (2) 1 5/8" Hybriflex	Verizon
		3	Alcatel-Lucent RRH2x60 700			
		3	Alcatel-Lucent RRH AWS			
		3	Alcatel-Lucent RRH2x60			
		6	Swedcom ALP 9212-N			
		2	RFS DB-T1-6Z-8AB-0Z			
		6	Commscope JAHH-65B-R3B			
123.0	123.0	12	Decibel DB844H90E-A	Platform w/ Handrails	(12) 1 1/4" Coax	Sprint Nextel
107.0	107.0	3	Commscope LNX-6515DS-VTM	Flush	(6) 1 1/4" Coax	Metro PCS
105.0	105.0	3	Kathrein Smart Bias Tee	Flush	-	
83.0	83.0	1	GPS	Stand-Off	(1) 1/2" Coax	T-Mobile
63.0	63.0	2	GPS	Stand-Offs	(2) 1/2" Coax	Sprint Nextel
50.0	50.0	1	2" x 4" GPS	Stand-Off	(1) 1/2" Coax	
17.0	17.0	1	4' Std. Dish	Flush	(1) 0.27" RG-6/U	Spok Holdings

Equipment to be Removed

Elevation[1] (ft)		Qty	Antenna	Mount Type	Lines	Carrier
Mount	RAD					
125.0	125.0	5	Decibel 980H65T2E-M	-	(9) 1 5/8" Coax	Sprint Nextel
		4	Decibel DB980H90A-KL			

Proposed Equipment

Elevation[1] (ft)		Qty	Antenna	Mount Type	Lines	Carrier
Mount	RAD					
133.0	133.0	6	Alcatel-Lucent 800 MHz 2X50W RRH w/ Filter	Platform w/ Handrails	(6) 1 5/8" Coax (4) 1 1/4" Hybriflex Cable	Sprint Nextel
		3	Alcatel-Lucent 1900 MHz 4x45 RRH			
		3	Decibel 980H65T2E-M			
		3	Alcatel-Lucent TD-RRH8x20-25 w/ Solar Shield			
		3	KMW ETCR-654L12H6			

[1]Mount elevation is defined as height above bottom of steel structure to the bottom of mount, RAD elevation is defined as center of antenna above ground level (AGL).

Install proposed coax inside the pole shaft.

Structure Usages

Structural Component	Controlling Usage	Pass/Fail
Anchor Bolts	78%	Pass
Shaft	87%	Pass
Base Plate	57%	Pass
Flanges	21%	Pass

Foundations

Reaction Component	Analysis Reactions	% of Usage
Moment (Kips-Ft)	3,903.8	84%
Axial (Kips)	52.7	5%
Shear (Kips)	35.0	60%

The structure base reactions resulting from this analysis were found to be acceptable through analysis based on geotechnical and foundation information, therefore no modification or reinforcement of the foundation will be required.

Deflection and Sway*

Antenna Elevation (ft)	Antenna	Carrier	Deflection (ft)	Sway (Rotation) (°)
133.0	Alcatel-Lucent 800 MHz 2X50W RRH w/ Filter	Sprint Nextel	2.137	1.878
	Alcatel-Lucent 1900 MHz 4x45 RRH			
	Decibel 980H65T2E-M			
	Alcatel-Lucent TD-RRH8x20-25 w/ Solar Shield			
	KMW ETCR-654L12H6			
17.0	4' Std. Dish	Spok Holdings	0.030	0.206

***Deflection and Sway was evaluated considering a design wind speed of 60 mph (3-Second Gust) per ANSI/TIA-222-G**

AMERICAN TOWER®
CORPORATION

Standard Conditions

All engineering services are performed on the basis that the information used is current and correct. This information may consist of, but is not necessary limited, to:

-- Information supplied by the client regarding the structure itself, antenna, mounts and feed line loading on the structure and its components, or other relevant information.

-- Information from drawings in the possession of American Tower Corporation, or generated by field inspections or measurements of the structure.

It is the responsibility of the client to ensure that the information provided to A.T. Engineering Service, PLLC and used in the performance of our engineering services is correct and complete. In the absence of information to the contrary, we assume that all structures were constructed in accordance with the drawings and specifications and that their capacity has not significantly changed from the "as new" condition.

Unless explicitly agreed by both the client and American Tower Corporation, all services will be performed in accordance with the current revision of ANSI/TIA -222. The design basic wind speed will be determined based on the minimum basic wind speed as prescribed in ANSI/TIA-222. Although every effort is taken to ensure that the loading considered is adequate to meet the requirements of all applicable regulatory entities, we can provide no assurance to meet any other local and state codes or requirements. If wind and ice loads or other relevant parameters are to be different from the minimum values recommended by the codes, the client shall specify the exact requirement.

All services are performed, results obtained, and recommendations made in accordance with generally accepted engineering principles and practices. A.T. Engineering Service, PLLC is not responsible for the conclusions, opinions and recommendations made by others based on the information we supply.



Job Information

Pole :	302495	Code:	ANSI/TIA-222-G
Description :	EEI 155' Monopole - Model verified 4/25/12		
Client :	Sprint Nextel	Struct Class :	II
Location :	Tolland CT, CT		
Shape :	12 Sides	Exposure :	B
Height :	155.00 (ft)	Topo :	1
Base Elev (ft):	0.00		
Taper:	0.210616 (in/ft)		

Sections Properties

Shaft Section	Length (ft)	Diameter (in) Accross Flats Top	Bottom	Thick (in)	Joint Type	Overlap Length (in)	Taper (in/ft)	Steel Grade (ksi)
1	45.898	40.33	50.00	0.438		0.000	0.210600	65
2	45.302	32.76	42.30	0.375	Slip Joint	69.531	0.210600	65
3	45.286	24.86	34.40	0.313	Slip Joint	57.688	0.210600	65
4	23.878	21.00	26.02	0.188	Slip Joint	45.156	0.210600	65
5	9.000	16.00	16.00	0.500	Butt Joint	0.000	0.000000	42

Discrete Appurtenance

Attach Elev (ft)	Force Elev (ft)	Qty	Description
155.000	155.000	1	Canister
155.000	159.000	6	Ericsson KRY 112 71/x
155.000	164.000	3	EMS RR90-17-02DP
149.000	149.000	3	Ericsson RRUS-12 800 MHz
149.000	149.000	1	Raycap DC6-48-60-18-8F
149.000	152.000	1	7' Omni
149.000	149.000	3	Powerwave Allgon 7770.00
149.000	149.000	1	Flat Platform w/ Handrails
149.000	149.000	3	Powerwave Allgon 7020.00
149.000	149.000	6	KMW AM-X-CD-16-65-00T-RET
149.000	149.000	3	Ericsson RRUS 11 (Band 12)
149.000	149.000	6	CCI DTMABP7819VG12A
149.000	149.000	6	Kathrein Scala 782-10250
149.000	149.000	1	Andrew ABT-DMDF-ADBH
143.000	143.000	1	Flat Platform w/ Handrails
143.000	143.000	6	Commscope JAHH-65B-R3B
143.000	143.000	1	RFS DB-T1-6Z-8AB-0Z
143.000	143.000	1	RFS DB-T1-6Z-8AB-0Z
143.000	143.000	6	Swedcom ALP 9212-N
143.000	143.000	3	Alcatel-Lucent RRH2x60
143.000	143.000	3	Alcatel-Lucent RRH AWS
143.000	143.000	3	Alcatel-Lucent RRH2x60 700
143.000	143.000	3	Nokia B5 RRH4x40-850
133.000	133.000	3	KMW ETCR-654L12H6
133.000	133.000	3	Alcatel-Lucent TD-RRH8x20-25
133.000	133.000	3	Decibel 980H65T2E-M
133.000	133.000	3	Alcatel-Lucent 1900 MHz 4x45
133.000	133.000	6	Alcatel-Lucent 800 MHz 2X50W
133.000	133.000	1	Flat Platform w/ Handrails
123.000	123.000	12	Decibel DB844H90E-A
123.000	123.000	1	Flat Platform w/ Handrails
107.000	107.000	3	Commscope LNX-6515DS-VTM
105.000	105.000	3	Kathrein Smart Bias Tee
83.000	83.000	1	Stand-Off
83.000	83.000	1	GPS
63.000	63.000	2	Stand-Off
63.000	63.000	2	GPS
50.000	50.000	1	Stand-Off
50.000	50.000	1	2" x 4" GPS
17.000	17.000	1	4' Std. Dish



Linear Appurtenance

Elev (ft) From	To	Description	Exposed To Wind
120.0	149.0	Climbing Ladder	Yes
0.000	155.0	1 5/8" Coax	No
0.000	17.000	0.27" RG-6/U	Yes
0.000	50.000	1/2" Coax	Yes
0.000	63.000	1/2" Coax	Yes
0.000	83.000	1/2" Coax	Yes
0.000	107.0	1 1/4" Coax	Yes
0.000	123.0	1 1/4" Coax	No
0.000	133.0	1 1/4" Hybriflex	No
0.000	133.0	1 5/8" Coax	No
0.000	143.0	1 5/8" Coax	Yes
0.000	143.0	1 5/8" Coax	No
0.000	143.0	1 5/8" Hybriflex	Yes
0.000	149.0	0.39" Fiber Trunk	No
0.000	149.0	0.78" 8 AWG 6	No
0.000	149.0	1 1/4" Coax	No
0.000	149.0	1 1/4" Coax	Yes
0.000	149.0	1 1/4" Coax	No
0.000	149.0	3" Conduit	No
0.000	149.0	3/8" RET Control	No

Load Cases

1.2D + 1.6W	97 mph with No Ice
0.9D + 1.6W	97 mph with No Ice (Reduced DL)
1.2D + 1.0Di + 1.0Wi	50 mph with 1.00 in Radial Ice
(1.2 + 0.2Sds) * DL + E	Seismic Equivalent Lateral Forces Method
(1.2 + 0.2Sds) * DL + E	Seismic Equivalent Modal Analysis Method
(0.9 - 0.2Sds) * DL + E	Seismic (Reduced DL) Equivalent Lateral
(0.9 - 0.2Sds) * DL + E	Seismic (Reduced DL) Equivalent Modal
1.0D + 1.0W	Serviceability 60 mph

Reactions

Load Case	Moment (kip-ft)	Shear (kip)	Axial (kip)
1.2D + 1.6W	3903.79	35.01	52.72
0.9D + 1.6W	3811.94	34.78	39.53
1.2D + 1.0Di + 1.0Wi	1082.46	8.54	99.85
(1.2 + 0.2Sds) * DL + E ELFM	229.27	1.72	53.32
(1.2 + 0.2Sds) * DL + E EMAM	329.82	2.63	53.32
(0.9 - 0.2Sds) * DL + E ELFM	224.02	1.72	37.18
(0.9 - 0.2Sds) * DL + E EMAM	322.11	2.63	37.18
1.0D + 1.0W	919.23	8.32	43.97

Dish Deflections

Load Case	Attach Elev (ft)	Deflection (in)	Rotation (deg)
1.0D + 1.0W	17.00	0.364	0.206


Load Case : 1.2D + 1.6W
Max Ratio 87.22% at 45.9 ft
0.00
0.01
0.11
0.25
0.61
0.61
0.41
0.49
0.58
0.65
0.71
0.82
0.68
0.79
0.84
0.87
0.83
0.84
1.00
1.00
153.000
147.000
143.000
138.000
132.000
125.885
122.122
117.000
111.000
105.000
99.000
93.000
87.000
83.000
78.000
72.000
66.000
60.000
54.000
50.000
45.000
39.000
33.000
27.000
21.000
17.000
12.000
6.000
0.000
Elevation (ft)
0.02
0.12
0.22
0.32
0.42
0.52
0.62
0.72
0.82
0.92
Interaction

Site Number:	302495	Code: ANSI/TIA-222-G	
Site Name:	Tolland CT, CT	Engineering Number:OAA714899_C3_01	11/15/2017 3:52:31 PM
Customer:	Sprint Nextel		

Analysis Parameters

Location:	Tolland County, CT	Height (ft):	155
Code:	ANSI/TIA-222-G	Base Diameter (in):	50.00
Shape:	12 Sides. Sect 5: Round	Top Diameter (in):	16.00
Pole Type:	Custom	Taper (in/ft) :	0.211
Pole Manfacturer:	EEI	Rotation (deg) :	0.00

Ice & Wind Parameters

Structure Class:	II	Design Wind Speed Without Ice:	97 mph
Exposure Category:	B	Design Wind Speed With Ice:	50 mph
Topographic Category:	1	Operational Wind Speed:	60 mph
Crest Height:	0.0 ft	Design Ice Thickness:	1.00 in

Seismic Parameters

Analysis Method:	Equivalent Modal Analysis & Equivalent Lateral Force Methods				
Site Class:	D - Stiff Soil				
Period Based on Rayleigh Method (sec):	2.93				
T_L (sec):	6	p:	1.3	C_s:	0.030
S_s:	0.175	S_1:	0.063	C_s Max:	0.030
F_a:	1.600	F_v:	2.400	C_s Min:	0.030
S_{ds}:	0.187	S_{d1}:	0.101		

Load Cases

1.2D + 1.6W	97 mph with No Ice
0.9D + 1.6W	97 mph with No Ice (Reduced DL)
1.2D + 1.0Di + 1.0Wi	50 mph with 1.00 in Radial Ice
(1.2 + 0.2Sds) * DL + E ELFM	Seismic Equivalent Lateral Forces Method
(1.2 + 0.2Sds) * DL + E EMAM	Seismic Equivalent Modal Analysis Method
(0.9 - 0.2Sds) * DL + E ELFM	Seismic (Reduced DL) Equivalent Lateral Forces Method
(0.9 - 0.2Sds) * DL + E EMAM	Seismic (Reduced DL) Equivalent Modal Analysis Method
1.0D + 1.0W	Serviceability 60 mph

Shaft Section Properties

Sect Info	Length (ft)	Thick (in)	Fy (ksi)	Slip Joint Type	Slip Joint Len (in)	Weight (lb)	Bottom Dia (in)	Bottom Elev (ft)	Bottom Area (in²)	Bottom Ix (in⁴)	Bottom W/t Ratio	Bottom D/t Ratio	Top Dia (in)	Top Elev (ft)	Top Area (in²)	Top Ix (in⁴)	Top W/t Ratio	Top D/t Ratio	Taper (in/ft)
1-12	45.898	0.4375	65		0.00	9,841	50.00	0.00	69.82	21891.7	27.94	114.29	40.33	45.90	56.20	11418.1	22.02	92.19	0.210616
2-12	45.302	0.3750	65	Slip	69.53	6,917	42.30	40.10	50.63	11360.5	27.55	112.81	32.76	85.41	39.11	5235.8	20.73	87.37	0.210616
3-12	45.286	0.3125	65	Slip	57.69	4,546	34.40	80.60	34.30	5087.0	26.82	110.08	24.86	125.89	24.70	1900.2	18.64	79.56	0.210616
4-12	23.878	0.1875	65	Slip	45.16	1,144	26.02	122.12	15.60	1329.8	34.52	138.82	21.00	146.00	12.57	694.7	27.33	112.00	0.210616
5-R	9.000	0.5000	42	Butt	0.00	746	16.00	146.00	24.35	731.7	0.00	32.00	16.00	155.00	24.35	731.7	0.00	32.00	0.000000
				Shaft Weight		23,194													

Discrete Appurtenance Properties

Attach Elev (ft)	Description	Qty	No Ice Weight (lb)	No Ice EPAa (sf)	No Ice Orientation Factor	Ice Weight (lb)	Ice EPAa (sf)	Ice Orientation Factor	Distance From Face (ft)	Vert Ecc (ft)
155.00	Canister	1	500.00	9.800	1.00	897.56	13.175	1.00	0.000	0.000
155.00	EMS RR90-17-02DP	3	13.50	4.360	0.01	158.35	5.725	0.01	0.000	9.000
155.00	Ericsson KRY 112 71/x	6	13.20	0.730	0.01	53.56	1.162	0.01	0.000	4.000
149.00	7' Omni	1	25.00	2.100	1.00	168.52	4.247	1.00	0.000	3.000
149.00	Andrew ABT-DMDF-ADBH	1	1.10	0.050	0.50	10.90	0.202	0.50	0.000	0.000
149.00	CCI DTMABP7819VG12A	6	19.20	0.970	0.50	70.27	1.569	0.50	0.000	0.000
149.00	Ericsson RRUS 11 (Band 12)	3	50.00	2.570	0.67	167.31	3.464	0.67	0.000	0.000
149.00	Ericsson RRUS-12 800 MHz	3	60.00	2.700	0.67	186.41	3.625	0.67	0.000	0.000
149.00	Flat Platform w/ Handrails	1	2000.00	42.400	1.00	3,896.23	70.382	1.00	0.000	0.000
149.00	Kathrein Scala 782-10250	6	6.40	0.520	0.50	36.64	0.913	0.50	0.000	0.000
149.00	KMW AM-X-CD-16-65-00T-	6	48.50	8.020	0.67	316.98	9.782	0.67	0.000	0.000
149.00	Powerwave Allgon 7020.00	3	2.20	0.400	0.50	27.26	0.742	0.50	0.000	0.000
149.00	Powerwave Allgon 7770.00	3	35.00	5.510	0.65	228.78	6.949	0.65	0.000	0.000
149.00	Raycap DC6-48-60-18-8F	1	31.80	1.280	1.00	165.01	3.096	1.00	0.000	0.000
143.00	Alcatel-Lucent RRH AWS	3	49.00	2.500	0.67	178.94	3.432	0.67	0.000	0.000
143.00	Alcatel-Lucent RRH2x60	3	60.00	3.500	0.67	165.14	5.450	0.67	0.000	0.000
143.00	Alcatel-Lucent RRH2x60 700	3	56.70	2.150	0.67	173.27	3.005	0.67	0.000	0.000
143.00	Commscope JAHH-65B-R3B	6	60.60	9.110	0.69	383.64	10.930	0.69	0.000	0.000
143.00	Flat Platform w/ Handrails	1	2000.00	42.400	1.00	3,888.40	70.267	1.00	0.000	0.000
143.00	Nokia B5 RRH4x40-850	3	48.50	1.320	0.50	123.73	1.988	0.50	0.000	0.000
143.00	RFS DB-T1-6Z-8AB-0Z	1	44.00	4.800	0.67	245.88	5.984	0.67	0.000	0.000
143.00	RFS DB-T1-6Z-8AB-0Z	1	44.00	4.800	0.67	245.88	5.984	0.67	0.000	0.000
143.00	Swedcom ALP 9212-N	6	26.70	4.520	0.90	235.40	12.625	0.90	0.000	0.000
133.00	Alcatel-Lucent 1900 MHz	3	60.00	2.320	0.67	194.38	3.231	0.67	0.000	0.000
133.00	Alcatel-Lucent 800 MHz	6	64.00	2.060	0.67	245.44	4.439	0.67	0.000	0.000
133.00	Alcatel-Lucent TD-RRH8x20-	3	70.00	4.050	0.67	194.71	5.804	0.67	0.000	0.000
133.00	Decibel 980H65T2E-M	3	8.50	3.800	0.67	140.91	5.207	0.67	0.000	0.000
133.00	Flat Platform w/ Handrails	1	2000.00	42.400	1.00	3,875.37	70.075	1.00	0.000	0.000
133.00	KMW ETCR-654L12H6	3	84.90	15.710	0.61	530.12	17.967	0.61	0.000	0.000
123.00	Decibel DB844H90E-A	12	10.00	3.800	0.72	165.62	5.011	0.72	0.000	0.000
123.00	Flat Platform w/ Handrails	1	2000.00	42.400	1.00	3,860.80	69.860	1.00	0.000	0.000
107.00	Commscope LNX-6515DS-	3	50.30	11.450	0.84	407.80	13.597	0.84	0.000	0.000
105.00	Kathrein Smart Bias Tee	3	3.31	0.090	0.50	14.35	0.314	0.50	0.000	0.000
83.00	GPS	1	10.00	1.000	1.00	62.74	1.066	1.00	0.000	0.000
83.00	Stand-Off	1	75.00	2.500	1.00	140.72	4.691	1.00	0.000	0.000
63.00	GPS	2	10.00	1.000	1.00	60.64	1.048	1.00	0.000	0.000
63.00	Stand-Off	2	75.00	2.500	0.90	138.85	4.628	0.90	0.000	0.000
50.00	2" x 4" GPS	1	5.00	0.040	1.00	14.52	0.244	1.00	0.000	0.000
50.00	Stand-Off	1	75.00	2.500	1.00	137.42	4.581	1.00	0.000	0.000
17.00	4' Std. Dish	1	188.00	20.910	1.00	523.75	24.022	1.00	0.000	0.000
	Totals	118	12676.23			37,246.10			Number of Loadings :	40

Linear Appurtenance Properties

Elev From (ft)	Elev To (ft)	Qty	Description	Coax Diameter (in)	Coax Weight (lb/ft)	Flat	Projected Width (in)	Exposed To Wind	Carrier
0.00	155.00	6	1 5/8" Coax	1.98	0.82	N	0.00	N	T-Mobile
0.00	149.00	1	0.39" Fiber Trunk	0.39	0.06	N	0.00	N	AT&T Mobility
0.00	149.00	2	0.78" 8 AWG 6	0.78	0.59	N	0.00	N	AT&T Mobility
0.00	149.00	9	1 1/4" Coax	1.55	0.63	N	0.00	N	AT&T Mobility
0.00	149.00	3	1 1/4" Coax	1.55	0.63	N	1.55	Y	AT&T Mobility
0.00	149.00	1	1 1/4" Coax	1.55	0.63	N	0.00	N	Spok Holdings
0.00	149.00	1	3" Conduit	3.50	7.58	N	0.00	N	AT&T Mobility
0.00	149.00	1	3/8" RET Control Cable	0.38	0.23	N	0.00	N	AT&T Mobility
120.00	149.00	1	Climbing Ladder	2.00	6.90	N	2.00	Y	--
0.00	143.00	3	1 5/8" Coax	1.98	0.82	N	1.98	Y	Verizon Wireless
0.00	143.00	11	1 5/8" Coax	1.98	0.82	N	0.00	N	Verizon Wireless
0.00	143.00	2	1 5/8" Hybriflex	1.98	1.30	N	0.00	Y	Verizon Wireless
0.00	133.00	4	1 1/4" Hybriflex Cable	1.54	1.00	N	0.00	N	Sprint Nextel
0.00	133.00	6	1 5/8" Coax	1.98	0.82	N	0.00	N	Sprint Nextel
0.00	123.00	12	1 1/4" Coax	1.55	0.63	N	0.00	N	Sprint Nextel
0.00	107.00	6	1 1/4" Coax	1.55	0.63	N	0.00	Y	Metro PCS
0.00	83.00	1	1/2" Coax	0.63	0.15	N	0.00	Y	T-Mobile
0.00	63.00	2	1/2" Coax	0.63	0.15	N	0.00	Y	Sprint Nextel
0.00	50.00	1	1/2" Coax	0.63	0.15	N	0.00	Y	Sprint Nextel
0.00	17.00	1	0.27" RG-6/U	0.27	0.04	N	0.00	Y	Spok Holdings

Segment Properties (Max Len : 3. ft)

Seg Top Elev (ft)	Description	Thick (in)	Flat Dia (in)	Area (in^2)	Ix (in^4)	W/t Ratio	D/t Ratio	F'y (ksi)	S (in^3)	Z (in^3)	Weight (lb)
0.00		0.4375	50.000	69.821	21,891.7	27.94	114.29	74.2	845.8	0.0	0.0
3.00		0.4375	49.368	68.931	21,065.1	27.56	112.84	74.7	824.3	0.0	708.2
6.00		0.4375	48.736	68.041	20,259.5	27.17	111.40	75.1	803.1	0.0	699.1
9.00		0.4375	48.104	67.151	19,474.8	26.78	109.95	75.5	782.1	0.0	690.0
12.00		0.4375	47.473	66.261	18,710.5	26.40	108.51	75.9	761.4	0.0	681.0
15.00		0.4375	46.841	65.371	17,966.6	26.01	107.06	76.3	741.0	0.0	671.9
17.00		0.4375	46.420	64.777	17,481.7	25.75	106.10	76.6	727.5	0.0	442.9
18.00		0.4375	46.209	64.480	17,242.6	25.62	105.62	76.8	720.9	0.0	219.9
21.00		0.4375	45.577	63.590	16,538.3	25.23	104.18	77.2	701.0	0.0	653.7
24.00		0.4375	44.945	62.700	15,853.5	24.85	102.73	77.6	681.4	0.0	644.6
27.00		0.4375	44.313	61.810	15,187.9	24.46	101.29	78.0	662.1	0.0	635.5
30.00		0.4375	43.682	60.920	14,541.1	24.07	99.84	78.5	643.1	0.0	626.4
33.00		0.4375	43.050	60.030	13,913.0	23.69	98.40	78.9	624.3	0.0	617.3
36.00		0.4375	42.418	59.140	13,303.2	23.30	96.95	79.3	605.9	0.0	608.3
39.00		0.4375	41.786	58.250	12,711.5	22.91	95.51	79.7	587.7	0.0	599.2
40.10	Bot - Section 2	0.4375	41.553	57.922	12,498.3	22.77	94.98	79.9	581.1	0.0	218.2
42.00		0.4375	41.154	57.360	12,137.7	22.53	94.07	80.1	569.8	0.0	696.9
45.00		0.4375	40.522	56.469	11,581.3	22.14	92.62	80.6	552.1	0.0	1,089.0
45.90	Top - Section 1	0.3750	41.083	49.155	10,397.1	26.68	109.55	75.6	488.9	0.0	322.9
48.00		0.3750	40.640	48.620	10,061.7	26.36	108.37	76.0	478.3	0.0	349.6
50.00		0.3750	40.219	48.112	9,749.2	26.06	107.25	76.3	468.3	0.0	329.2
51.00		0.3750	40.009	47.858	9,595.4	25.91	106.69	76.5	463.3	0.0	163.3
54.00		0.3750	39.377	47.095	9,143.7	25.46	105.00	77.0	448.6	0.0	484.7
57.00		0.3750	38.745	46.332	8,706.5	25.00	103.32	77.4	434.1	0.0	476.9
60.00		0.3750	38.113	45.569	8,283.4	24.55	101.63	77.9	419.9	0.0	469.1
63.00		0.3750	37.481	44.806	7,874.3	24.10	99.95	78.4	405.9	0.0	461.3
66.00		0.3750	36.849	44.043	7,478.8	23.65	98.26	78.9	392.1	0.0	453.5
69.00		0.3750	36.217	43.280	7,096.9	23.20	96.58	79.4	378.5	0.0	445.7
72.00		0.3750	35.586	42.517	6,728.1	22.75	94.89	79.9	365.3	0.0	437.9
75.00		0.3750	34.954	41.754	6,372.4	22.30	93.21	80.4	352.2	0.0	430.1
78.00		0.3750	34.322	40.991	6,029.4	21.84	91.53	80.9	339.4	0.0	422.3
80.60	Bot - Section 3	0.3750	33.775	40.330	5,742.4	21.45	90.07	81.3	328.5	0.0	359.6
81.00		0.3750	33.690	40.228	5,699.0	21.39	89.84	81.4	326.8	0.0	101.7
83.00		0.3750	33.269	39.719	5,485.5	21.09	88.72	81.7	318.5	0.0	503.5
84.00		0.3750	33.058	39.465	5,380.8	20.94	88.16	81.9	314.4	0.0	249.3
85.41	Top - Section 2	0.3125	33.387	33.281	4,647.0	25.95	106.84	76.4	268.9	0.0	348.0
87.00		0.3125	33.051	32.943	4,507.0	25.66	105.76	76.7	263.4	0.0	179.6
90.00		0.3125	32.420	32.308	4,251.0	25.12	103.74	77.3	253.3	0.0	333.1
93.00		0.3125	31.788	31.672	4,004.9	24.58	101.72	77.9	243.4	0.0	326.6
96.00		0.3125	31.156	31.036	3,768.6	24.03	99.70	78.5	233.7	0.0	320.1
99.00		0.3125	30.524	30.400	3,541.7	23.49	97.68	79.1	224.2	0.0	313.6
102.0		0.3125	29.892	29.765	3,324.1	22.95	95.65	79.7	214.8	0.0	307.1
105.0		0.3125	29.260	29.129	3,115.6	22.41	93.63	80.3	205.7	0.0	300.6
107.0		0.3125	28.839	28.705	2,981.5	22.05	92.28	80.7	199.7	0.0	196.8
108.0		0.3125	28.628	28.493	2,916.0	21.87	91.61	80.9	196.8	0.0	97.3
111.0		0.3125	27.997	27.857	2,725.1	21.33	89.59	81.5	188.0	0.0	287.6
114.0		0.3125	27.365	27.221	2,542.7	20.78	87.57	81.9	179.5	0.0	281.1
117.0		0.3125	26.733	26.586	2,368.7	20.24	85.55	81.9	171.2	0.0	274.6
120.0		0.3125	26.101	25.950	2,202.8	19.70	83.52	81.9	163.0	0.0	268.1
122.1	Bot - Section 4	0.3125	25.654	25.500	2,090.2	19.32	82.09	81.9	157.4	0.0	185.8
123.0		0.3125	25.469	25.314	2,044.8	19.16	81.50	81.9	155.1	0.0	122.3
125.8	Top - Section 3	0.1875	25.236	15.123	1,211.2	33.38	134.59	68.3	92.7	0.0	395.8
126.0		0.1875	25.212	15.109	1,207.7	33.35	134.47	68.3	92.5	0.0	5.9
129.0		0.1875	24.580	14.727	1,118.5	32.45	131.10	69.3	87.9	0.0	152.3
132.0		0.1875	23.949	14.346	1,033.8	31.54	127.73	70.3	83.4	0.0	148.4
133.0		0.1875	23.738	14.219	1,006.6	31.24	126.60	70.6	81.9	0.0	48.6
135.0		0.1875	23.317	13.964	953.5	30.64	124.36	71.3	79.0	0.0	95.9
138.0		0.1875	22.685	13.583	877.5	29.74	120.99	72.3	74.7	0.0	140.6

141.0		0.1875	22.053	13.201	805.6	28.84	117.62	73.3	70.6	0.0	136.7
143.0		0.1875	21.632	12.947	759.9	28.23	115.37	73.9	67.9	0.0	89.0
144.0		0.1875	21.421	12.820	737.8	27.93	114.25	74.2	66.5	0.0	43.8
146.0	Top - Section 4	0.1875	21.000	12.566	694.7	27.33	112.00	74.9	63.9	0.0	86.4
146.0	Bot - Section 5	0.5000	16.000	24.347	731.7	0.00	32.00	42.0	91.5	120.2	
147.0		0.5000	16.000	24.347	731.7	0.00	32.00	42.0	91.5	120.2	82.8
149.0		0.5000	16.000	24.347	731.7	0.00	32.00	42.0	91.5	120.2	165.7
150.0		0.5000	16.000	24.347	731.7	0.00	32.00	42.0	91.5	120.2	82.8
153.0		0.5000	16.000	24.347	731.7	0.00	32.00	42.0	91.5	120.2	248.5
155.0		0.5000	16.000	24.347	731.7	0.00	32.00	42.0	91.5	120.2	165.7
											23,194.0

Site Number: 302495 Code: ANSI/TIA-222-G

Site Name: Tolland CT, CT Engineering Number:OAA714899_C3_01 11/15/2017 3:52:31 PM

Customer: Sprint Nextel

Load Case: 1.2D + 1.6W 97 mph with No Ice 29 Iterations

Gust Response Factor :1.10 Wind Importance Factor 1.00

Dead Load Factor :1.20

Wind Load Factor :1.60

Applied Segment Forces Summary

		Shaft Forces		Discrete Forces				Linear Forces		Sum of Forces			
Seg Elev (ft)	Description	Wind FX (lb)	Dead Load (lb)	Wind FX (lb)	Torsion MY (lb-ft)	Moment MZ (lb-ft)	Dead Load (lb)	Wind FX (lb)	Dead Load (lb)	Wind FX (lb)	Dead Load (lb)	Torsion MY (lb-ft)	Moment MZ (lb)
0.00		181.3	0.0					0.0	0.0	181.3	0.0	0.0	0.0
3.00		360.2	849.9					0.0	205.7	360.2	1,055.6	0.0	0.0
6.00		355.6	839.0					0.0	205.7	355.6	1,044.7	0.0	0.0
9.00		351.0	828.0					0.0	205.7	351.0	1,033.8	0.0	0.0
12.00		346.4	817.1					0.0	205.7	346.4	1,022.8	0.0	0.0
15.00		285.5	806.2					0.0	205.7	285.5	1,011.9	0.0	0.0
17.00	Appertunance(s)	169.7	531.4	589.5	0.0	0.0	225.6	0.0	137.1	759.2	894.2	0.0	0.0
18.00		223.8	263.9					0.0	68.5	223.8	332.4	0.0	0.0
21.00		332.6	784.4					0.0	205.6	332.6	990.0	0.0	0.0
24.00		327.9	773.5					0.0	205.6	327.9	979.1	0.0	0.0
27.00		323.3	762.6					0.0	205.6	323.3	968.2	0.0	0.0
30.00		321.1	751.7					0.0	205.6	321.1	957.3	0.0	0.0
33.00		323.0	740.8					0.0	205.6	323.0	946.4	0.0	0.0
36.00		326.2	729.9					0.0	205.6	326.2	935.5	0.0	0.0
39.00		224.4	719.0					0.0	205.6	224.4	924.6	0.0	0.0
40.10	Bot - Section 2	166.9	261.9					0.0	75.7	166.9	337.5	0.0	0.0
42.00		275.1	836.3					0.0	129.9	275.1	966.2	0.0	0.0
45.00		219.6	1,306.8					0.0	205.6	219.6	1,512.4	0.0	0.0
45.90	Top - Section 1	169.5	387.4					0.0	61.6	169.5	449.0	0.0	0.0
48.00		232.0	419.5					0.0	144.0	232.0	563.5	0.0	0.0
50.00	Appertunance(s)	169.9	395.0	82.9	0.0	0.0	96.0	0.0	137.0	252.8	628.0	0.0	0.0
51.00		226.7	195.9					0.0	68.3	226.7	264.3	0.0	0.0
54.00		340.1	581.6					0.0	205.0	340.1	786.6	0.0	0.0
57.00		339.8	572.2					0.0	205.0	339.8	777.3	0.0	0.0
60.00		339.2	562.9					0.0	205.0	339.2	767.9	0.0	0.0
63.00	Appertunance(s)	338.3	553.5	211.0	0.0	0.0	204.0	0.0	205.0	549.3	962.6	0.0	0.0
66.00		337.1	544.2					0.0	203.9	337.1	748.1	0.0	0.0
69.00		335.5	534.9					0.0	203.9	335.5	738.8	0.0	0.0
72.00		333.7	525.5					0.0	203.9	333.7	729.4	0.0	0.0
75.00		331.6	516.2					0.0	203.9	331.6	720.1	0.0	0.0
78.00		307.4	506.8					0.0	203.9	307.4	710.8	0.0	0.0
80.60	Bot - Section 3	164.5	431.5					0.0	176.7	164.5	608.2	0.0	0.0
81.00		133.6	122.1					0.0	27.3	133.6	149.3	0.0	0.0
83.00	Appertunance(s)	166.8	604.1	132.1	0.0	0.0	102.0	0.0	136.0	298.9	842.1	0.0	0.0
84.00		133.6	299.2					0.0	67.8	133.6	367.0	0.0	0.0
85.41	Top - Section 2	165.9	417.6					0.0	95.3	165.9	512.9	0.0	0.0
87.00		252.7	215.5					0.0	108.1	252.7	323.5	0.0	0.0
90.00		329.1	399.7					0.0	203.4	329.1	603.1	0.0	0.0
93.00		327.7	391.9					0.0	203.4	327.7	595.3	0.0	0.0
96.00		326.2	384.1					0.0	203.4	326.2	587.5	0.0	0.0
99.00		324.5	376.3					0.0	203.4	324.5	579.7	0.0	0.0
102.00		322.7	368.5					0.0	203.4	322.7	571.9	0.0	0.0
105.00	Appertunance(s)	267.6	360.7	5.4	0.0	0.0	11.9	0.0	203.4	273.0	576.0	0.0	0.0
107.00	Appertunance(s)	159.9	236.2	1,170.8	0.0	0.0	181.1	0.0	135.6	1,330.7	552.8	0.0	0.0
108.00		212.0	116.8					0.0	63.3	212.0	180.0	0.0	0.0
111.00		316.5	345.1					0.0	189.8	316.5	534.9	0.0	0.0
114.00		314.2	337.4					0.0	189.8	314.2	527.1	0.0	0.0
117.00		311.8	329.6					0.0	189.8	311.8	519.4	0.0	0.0

Load Case: 1.2D + 1.6W 97 mph with No Ice 29 Iterations

Gust Response Factor :1.10
Dead Load Factor :1.20
Wind Load Factor :1.60

Wind Importance Factor 1.00

120.00		274.8	321.8					0.0	189.8	274.8	511.6	0.0	0.0
122.12	Bot - Section 4	169.2	222.9					61.2	151.8	230.4	374.8	0.0	0.0
123.00	Appertunance(s)	211.3	146.8	2,830.1	0.0	0.0	2,544.0	25.4	62.8	3,066.8	2,753.5	0.0	0.0
125.89	Top - Section 3	168.0	475.0					83.9	180.3	251.9	655.3	0.0	0.0
126.00		171.3	7.1					3.3	7.2	174.6	14.2	0.0	0.0
129.00		326.8	182.7					87.8	187.4	414.6	370.2	0.0	0.0
132.00		215.1	178.1					88.4	187.4	303.5	365.5	0.0	0.0
133.00	Appertunance(s)	158.6	58.3	3,691.9	0.0	0.0	3,665.0	29.6	62.5	3,880.1	3,785.8	0.0	0.0
135.00		260.8	115.1					59.4	103.5	320.2	218.6	0.0	0.0
138.00		307.4	168.7					89.6	155.3	397.0	324.0	0.0	0.0
141.00		251.5	164.1					90.1	155.3	341.7	319.4	0.0	0.0
143.00	Appertunance(s)	147.7	106.8	4,742.7	0.0	0.0	3,905.3	60.4	103.5	4,950.8	4,115.6	0.0	0.0
144.00		144.2	52.6					0.0	34.9	144.2	87.5	0.0	0.0
146.00	Top - Section 4	131.5	103.7					0.0	69.7	131.5	173.4	0.0	0.0
147.00		106.7	99.4					21.7	34.9	128.4	134.3	0.0	0.0
149.00	Appertunance(s)	89.1	198.8	3,990.9	0.0	282.6	3,532.9	43.5	69.7	4,123.4	3,801.5	0.0	0.0
150.00		71.6	99.4					0.0	5.9	71.6	105.3	0.0	0.0
153.00		89.8	298.3					0.0	17.7	89.8	316.0	0.0	0.0
155.00	Appertunance(s)	36.0	198.8	450.1	0.0	61.9	743.6	0.0	11.8	486.1	954.3	0.0	0.0
								Totals:		35,116.6	52,770.3	0.00	0.00

Site Number: 302495 Code: ANSI/TIA-222-G

Site Name: Tolland CT, CT Engineering Number:OAA714899_C3_01 11/15/2017 3:52:35 PM

Customer: Sprint Nextel

Load Case: 1.2D + 1.6W 97 mph with No Ice 29 Iterations

Gust Response Factor :1.10 Wind Importance Factor 1.00

Dead Load Factor :1.20

Wind Load Factor :1.60

Calculated Forces

Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	phi Pn (kips)	phi Vn (kips)	phi Tn (ft-kips)	phi Mn (ft-kips)	Total Deflect (in)	Rotation (deg)	Ratio
0.00	-52.72	-35.01	0.00	-3,903.79	0.00	3,903.79	4,665.07	2,332.54	9,536.02	4,709.48	0.00	0.00	0.840
3.00	-51.58	-34.78	0.00	-3,798.77	0.00	3,798.77	4,631.78	2,315.89	9,346.21	4,615.74	0.05	-0.15	0.834
6.00	-50.44	-34.56	0.00	-3,694.43	0.00	3,694.43	4,597.82	2,298.91	9,156.81	4,522.21	0.19	-0.30	0.828
9.00	-49.32	-34.33	0.00	-3,590.77	0.00	3,590.77	4,563.18	2,281.59	8,967.87	4,428.89	0.43	-0.46	0.822
12.00	-48.21	-34.11	0.00	-3,487.78	0.00	3,487.78	4,527.86	2,263.93	8,779.43	4,335.83	0.77	-0.61	0.815
15.00	-47.12	-33.92	0.00	-3,385.47	0.00	3,385.47	4,491.86	2,245.93	8,591.56	4,243.05	1.20	-0.77	0.809
17.00	-46.19	-33.21	0.00	-3,317.64	0.00	3,317.64	4,467.49	2,233.75	8,466.65	4,181.36	1.55	-0.87	0.804
18.00	-45.80	-33.07	0.00	-3,284.43	0.00	3,284.43	4,455.19	2,227.60	8,404.31	4,150.57	1.74	-0.93	0.802
21.00	-44.72	-32.84	0.00	-3,185.24	0.00	3,185.24	4,417.85	2,208.92	8,217.72	4,058.43	2.37	-1.09	0.795
24.00	-43.66	-32.62	0.00	-3,086.71	0.00	3,086.71	4,379.82	2,189.91	8,031.86	3,966.64	3.11	-1.25	0.788
27.00	-42.61	-32.39	0.00	-2,988.86	0.00	2,988.86	4,341.13	2,170.56	7,846.78	3,875.23	3.94	-1.41	0.781
30.00	-41.56	-32.17	0.00	-2,891.68	0.00	2,891.68	4,301.75	2,150.88	7,662.53	3,784.23	4.88	-1.58	0.774
33.00	-40.53	-31.94	0.00	-2,795.18	0.00	2,795.18	4,261.70	2,130.85	7,479.16	3,693.68	5.93	-1.74	0.766
36.00	-39.52	-31.70	0.00	-2,699.37	0.00	2,699.37	4,220.97	2,110.49	7,296.73	3,603.58	7.08	-1.91	0.759
39.00	-38.54	-31.52	0.00	-2,604.28	0.00	2,604.28	4,179.57	2,089.78	7,115.28	3,513.97	8.34	-2.08	0.751
40.10	-38.16	-31.40	0.00	-2,569.48	0.00	2,569.48	4,164.16	2,082.08	7,048.76	3,481.12	8.83	-2.15	0.748
42.00	-37.12	-31.18	0.00	-2,509.95	0.00	2,509.95	4,137.49	2,068.74	6,934.89	3,424.88	9.70	-2.26	0.742
45.00	-35.56	-30.97	0.00	-2,416.42	0.00	2,416.42	4,094.73	2,047.37	6,755.59	3,336.33	11.18	-2.43	0.733
45.90	-35.07	-30.83	0.00	-2,388.60	0.00	2,388.60	3,345.43	1,672.72	5,614.65	2,772.86	11.64	-2.48	0.872
48.00	-34.45	-30.65	0.00	-2,323.80	0.00	2,323.80	3,324.15	1,662.07	5,517.72	2,724.99	12.76	-2.61	0.863
50.00	-33.79	-30.43	0.00	-2,262.50	0.00	2,262.50	3,303.59	1,651.79	5,425.69	2,679.55	13.88	-2.74	0.855
51.00	-33.46	-30.27	0.00	-2,232.07	0.00	2,232.07	3,293.20	1,646.60	5,379.77	2,656.86	14.46	-2.80	0.851
54.00	-32.59	-30.00	0.00	-2,141.28	0.00	2,141.28	3,261.57	1,630.78	5,242.36	2,589.00	16.28	-3.00	0.837
57.00	-31.73	-29.72	0.00	-2,051.29	0.00	2,051.29	3,229.26	1,614.63	5,105.54	2,521.44	18.23	-3.19	0.824
60.00	-30.89	-29.45	0.00	-1,962.12	0.00	1,962.12	3,196.28	1,598.14	4,969.37	2,454.19	20.30	-3.39	0.809
63.00	-29.86	-28.94	0.00	-1,873.77	0.00	1,873.77	3,162.62	1,581.31	4,833.91	2,387.28	22.49	-3.59	0.795
66.00	-29.03	-28.66	0.00	-1,786.94	0.00	1,786.94	3,128.28	1,564.14	4,699.19	2,320.75	24.80	-3.78	0.780
69.00	-28.22	-28.37	0.00	-1,700.96	0.00	1,700.96	3,093.27	1,546.64	4,565.29	2,254.62	27.24	-3.98	0.764
72.00	-27.42	-28.09	0.00	-1,615.84	0.00	1,615.84	3,057.58	1,528.79	4,432.24	2,188.92	29.81	-4.18	0.747
75.00	-26.63	-27.79	0.00	-1,531.58	0.00	1,531.58	3,021.22	1,510.61	4,300.11	2,123.66	32.50	-4.38	0.730
78.00	-25.86	-27.52	0.00	-1,448.20	0.00	1,448.20	2,984.18	1,492.09	4,168.95	2,058.89	35.32	-4.58	0.712
80.60	-25.22	-27.35	0.00	-1,376.69	0.00	1,376.69	2,951.54	1,475.77	4,056.14	2,003.18	37.86	-4.76	0.696
81.00	-25.04	-27.24	0.00	-1,365.73	0.00	1,365.73	2,946.46	1,473.23	4,038.81	1,994.61	38.26	-4.78	0.694
83.00	-24.18	-26.91	0.00	-1,311.26	0.00	1,311.26	2,920.94	1,460.47	3,952.64	1,952.06	40.29	-4.92	0.680
84.00	-23.79	-26.78	0.00	-1,284.35	0.00	1,284.35	2,908.96	1,454.48	3,910.94	1,931.47	41.32	-4.98	0.673
85.41	-23.24	-26.61	0.00	-1,246.69	0.00	1,246.69	2,288.86	1,144.43	3,120.34	1,541.02	42.80	-5.08	0.820
87.00	-22.87	-26.39	0.00	-1,204.28	0.00	1,204.28	2,274.94	1,137.47	3,069.59	1,515.95	44.52	-5.18	0.805
90.00	-22.20	-26.10	0.00	-1,125.10	0.00	1,125.10	2,248.22	1,124.11	2,974.43	1,468.96	47.84	-5.40	0.776
93.00	-21.54	-25.79	0.00	-1,046.82	0.00	1,046.82	2,220.81	1,110.41	2,879.80	1,422.23	51.30	-5.62	0.746
96.00	-20.89	-25.49	0.00	-969.44	0.00	969.44	2,192.74	1,096.37	2,785.75	1,375.78	54.90	-5.84	0.715
99.00	-20.26	-25.18	0.00	-892.97	0.00	892.97	2,163.98	1,081.99	2,692.34	1,329.64	58.63	-6.05	0.681
102.00	-19.64	-24.87	0.00	-817.44	0.00	817.44	2,134.56	1,067.28	2,599.61	1,283.85	62.49	-6.25	0.646
105.00	-19.02	-24.59	0.00	-742.84	0.00	742.84	2,104.45	1,052.22	2,507.63	1,238.42	66.48	-6.45	0.609
107.00	-18.59	-23.23	0.00	-693.66	0.00	693.66	2,084.00	1,042.00	2,446.74	1,208.36	69.20	-6.59	0.583
108.00	-18.38	-23.04	0.00	-670.43	0.00	670.43	2,073.67	1,036.83	2,416.44	1,193.39	70.59	-6.65	0.571
111.00	-17.82	-22.72	0.00	-601.30	0.00	601.30	2,042.21	1,021.11	2,326.10	1,148.77	74.82	-6.84	0.533
114.00	-17.26	-22.40	0.00	-533.14	0.00	533.14	2,006.48	1,003.24	2,232.66	1,102.63	79.16	-7.01	0.493
117.00	-16.72	-22.07	0.00	-465.94	0.00	465.94	1,959.62	979.81	2,129.00	1,051.43	83.62	-7.18	0.452
120.00	-16.20	-21.77	0.00	-399.72	0.00	399.72	1,912.75	956.38	2,027.81	1,001.46	88.17	-7.34	0.408
122.12	-15.83	-21.52	0.00	-353.51	0.00	353.51	1,879.60	939.80	1,957.71	966.84	91.45	-7.44	0.375
123.00	-13.47	-18.14	0.00	-334.63	0.00	334.63	1,865.89	932.94	1,929.08	952.70	92.81	-7.48	0.359

Load Case: 1.2D + 1.6W 97 mph with No Ice 29 Iterations

Gust Response Factor :1.10 Wind Importance Factor 1.00
Dead Load Factor :1.20
Wind Load Factor :1.60

125.89	-12.84	-17.81	0.00	-282.30	0.00	282.30	929.68	464.84	961.73	474.96	97.36	-7.61	0.610
126.00	-12.82	-17.66	0.00	-280.26	0.00	280.26	929.29	464.65	960.40	474.31	97.55	-7.61	0.606
129.00	-12.46	-17.24	0.00	-227.27	0.00	227.27	918.88	459.44	925.49	457.06	102.37	-7.79	0.512
132.00	-12.11	-16.91	0.00	-175.56	0.00	175.56	907.79	453.90	890.46	439.76	107.31	-7.94	0.414
133.00	-8.88	-12.55	0.00	-158.66	0.00	158.66	903.95	451.97	878.77	433.99	108.97	-7.99	0.376
135.00	-8.69	-12.22	0.00	-133.56	0.00	133.56	896.03	448.02	855.37	422.43	112.33	-8.07	0.327
138.00	-8.41	-11.79	0.00	-96.91	0.00	96.91	883.59	441.80	820.26	405.10	117.42	-8.18	0.249
141.00	-8.13	-11.41	0.00	-61.54	0.00	61.54	870.48	435.24	785.20	387.78	122.57	-8.25	0.169
143.00	-4.77	-5.92	0.00	-38.71	0.00	38.71	861.36	430.68	761.88	376.27	126.02	-8.29	0.109
144.00	-4.70	-5.77	0.00	-32.79	0.00	32.79	856.69	428.34	750.24	370.52	127.75	-8.30	0.094
146.00	-4.55	-5.62	0.00	-21.24	0.00	21.24	847.12	423.56	727.02	359.05	131.22	-8.32	0.065
146.00	-4.55	-5.62	0.00	-21.24	0.00	21.24	920.33	460.16	575.46	378.52	131.22	-8.32	0.061
147.00	-4.43	-5.47	0.00	-15.63	0.00	15.63	920.33	460.16	575.46	378.52	132.96	-8.33	0.046
149.00	-1.27	-0.84	0.00	-4.40	0.00	4.40	920.33	460.16	575.46	378.52	136.44	-8.34	0.013
150.00	-1.17	-0.75	0.00	-3.56	0.00	3.56	920.33	460.16	575.46	378.52	138.18	-8.34	0.011
153.00	-0.87	-0.62	0.00	-1.30	0.00	1.30	920.33	460.16	575.46	378.52	143.40	-8.34	0.004
155.00	0.00	-0.49	0.00	-0.06	0.00	0.06	920.33	460.16	575.46	378.52	146.89	-8.34	0.000

Site Number: 302495 Code: ANSI/TIA-222-G

Site Name: Tolland CT, CT Engineering Number:OAA714899_C3_01 11/15/2017 3:52:36 PM

Customer: Sprint Nextel

Load Case: 0.9D + 1.6W — 97 mph with No Ice (Reduced DL) — 29 Iterations

Gust Response Factor :1.10 Wind Importance Factor 1.00

Dead Load Factor :0.90

Wind Load Factor :1.60

Applied Segment Forces Summary

		Shaft Forces		Discrete Forces				Linear Forces		Sum of Forces			
Seg Elev (ft)	Description	Wind FX (lb)	Dead Load (lb)	Wind FX (lb)	Torsion MY (lb-ft)	Moment MZ (lb-ft)	Dead Load (lb)	Wind FX (lb)	Dead Load (lb)	Wind FX (lb)	Dead Load (lb)	Torsion MY (lb-ft)	Moment MZ (lb)
0.00		181.3	0.0					0.0	0.0	181.3	0.0	0.0	0.0
3.00		360.2	637.4					0.0	154.3	360.2	791.7	0.0	0.0
6.00		355.6	629.2					0.0	154.3	355.6	783.5	0.0	0.0
9.00		351.0	621.0					0.0	154.3	351.0	775.3	0.0	0.0
12.00		346.4	612.9					0.0	154.3	346.4	767.1	0.0	0.0
15.00		285.5	604.7					0.0	154.3	285.5	759.0	0.0	0.0
17.00	Appertunance(s)	169.7	398.6	589.5	0.0	0.0	169.2	0.0	102.9	759.2	670.6	0.0	0.0
18.00		223.8	197.9					0.0	51.4	223.8	249.3	0.0	0.0
21.00		332.6	588.3					0.0	154.2	332.6	742.5	0.0	0.0
24.00		327.9	580.1					0.0	154.2	327.9	734.3	0.0	0.0
27.00		323.3	572.0					0.0	154.2	323.3	726.1	0.0	0.0
30.00		321.1	563.8					0.0	154.2	321.1	718.0	0.0	0.0
33.00		323.0	555.6					0.0	154.2	323.0	709.8	0.0	0.0
36.00		326.2	547.4					0.0	154.2	326.2	701.6	0.0	0.0
39.00		224.4	539.3					0.0	154.2	224.4	693.4	0.0	0.0
40.10	Bot - Section 2	166.9	196.4					0.0	56.7	166.9	253.2	0.0	0.0
42.00		275.1	627.2					0.0	97.4	275.1	724.6	0.0	0.0
45.00		219.6	980.1					0.0	154.2	219.6	1,134.3	0.0	0.0
45.90	Top - Section 1	169.5	290.6					0.0	46.2	169.5	336.7	0.0	0.0
48.00		232.0	314.6					0.0	108.0	232.0	422.6	0.0	0.0
50.00	Appertunance(s)	169.9	296.2	82.9	0.0	0.0	72.0	0.0	102.8	252.8	471.0	0.0	0.0
51.00		226.7	147.0					0.0	51.3	226.7	198.2	0.0	0.0
54.00		340.1	436.2					0.0	153.8	340.1	590.0	0.0	0.0
57.00		339.8	429.2					0.0	153.8	339.8	582.9	0.0	0.0
60.00		339.2	422.2					0.0	153.8	339.2	575.9	0.0	0.0
63.00	Appertunance(s)	338.3	415.2	211.0	0.0	0.0	153.0	0.0	153.8	549.3	721.9	0.0	0.0
66.00		337.1	408.1					0.0	153.0	337.1	561.1	0.0	0.0
69.00		335.5	401.1					0.0	153.0	335.5	554.1	0.0	0.0
72.00		333.7	394.1					0.0	153.0	333.7	547.1	0.0	0.0
75.00		331.6	387.1					0.0	153.0	331.6	540.1	0.0	0.0
78.00		307.4	380.1					0.0	153.0	307.4	533.1	0.0	0.0
80.60	Bot - Section 3	164.4	323.6					0.0	132.5	164.4	456.1	0.0	0.0
81.00		132.9	91.5					0.0	20.4	132.9	112.0	0.0	0.0
83.00	Appertunance(s)	165.7	453.1	132.1	0.0	0.0	76.5	0.0	102.0	297.8	631.6	0.0	0.0
84.00		132.3	224.4					0.0	50.8	132.3	275.3	0.0	0.0
85.41	Top - Section 2	164.3	313.2					0.0	71.5	164.3	384.7	0.0	0.0
87.00		249.9	161.6					0.0	81.0	249.9	242.7	0.0	0.0
90.00		324.0	299.7					0.0	152.5	324.0	452.3	0.0	0.0
93.00		320.7	293.9					0.0	152.5	320.7	446.5	0.0	0.0
96.00		317.2	288.1					0.0	152.5	317.2	440.6	0.0	0.0
99.00		313.5	282.2					0.0	152.5	313.5	434.8	0.0	0.0
102.00		309.6	276.4					0.0	152.5	309.6	428.9	0.0	0.0
105.00	Appertunance(s)	255.3	270.5	5.4	0.0	0.0	8.9	0.0	152.5	260.7	432.0	0.0	0.0
107.00	Appertunance(s)	151.8	177.1	1,170.8	0.0	0.0	135.8	0.0	101.7	1,322.6	414.6	0.0	0.0
108.00		200.0	87.6					0.0	47.4	200.0	135.0	0.0	0.0
111.00		297.1	258.9					0.0	142.3	297.1	401.2	0.0	0.0
114.00		292.6	253.0					0.0	142.3	292.6	395.4	0.0	0.0
117.00		288.0	247.2					0.0	142.3	288.0	389.5	0.0	0.0

Load Case: 0.9D + 1.6W — 97 mph with No Ice (Reduced DL) — 29 Iterations

Gust Response Factor :1.10
Dead Load Factor :0.90
Wind Load Factor :1.60

Wind Importance Factor 1.00

120.00		262.3	241.3					0.0	142.3	262.3	383.7	0.0	0.0
122.12	Bot - Section 4	169.2	167.2					61.2	113.9	230.4	281.1	0.0	0.0
123.00	Appertunance(s)	211.3	110.1	2,830.1	0.0	0.0	1,908.0	25.4	47.1	3,066.8	2,065.2	0.0	0.0
125.89	Top - Section 3	168.0	356.2					83.9	135.2	251.9	491.4	0.0	0.0
126.00		171.3	5.3					3.3	5.4	174.6	10.7	0.0	0.0
129.00		326.8	137.1					87.8	140.6	414.6	277.6	0.0	0.0
132.00		215.1	133.6					88.4	140.6	303.5	274.1	0.0	0.0
133.00	Appertunance(s)	158.6	43.7	3,691.9	0.0	0.0	2,748.8	29.6	46.9	3,880.1	2,839.4	0.0	0.0
135.00		260.8	86.3					59.4	77.7	320.2	164.0	0.0	0.0
138.00		307.4	126.5					89.6	116.5	397.0	243.0	0.0	0.0
141.00		251.5	123.0					90.1	116.5	341.7	239.5	0.0	0.0
143.00	Appertunance(s)	140.5	80.1	4,742.7	0.0	0.0	2,929.0	60.4	77.7	4,943.5	3,086.7	0.0	0.0
144.00		122.0	39.5					0.0	26.2	122.0	65.6	0.0	0.0
146.00	Top - Section 4	116.5	77.7					0.0	52.3	116.5	130.1	0.0	0.0
147.00		106.7	74.6					21.7	26.2	128.4	100.7	0.0	0.0
149.00	Appertunance(s)	89.1	149.1	3,990.9	0.0	282.6	2,649.7	43.5	52.3	4,123.4	2,851.1	0.0	0.0
150.00		71.6	74.6					0.0	4.4	71.6	79.0	0.0	0.0
153.00		89.8	223.7					0.0	13.3	89.8	237.0	0.0	0.0
155.00	Appertunance(s)	36.0	149.1	450.1	0.0	61.9	557.7	0.0	8.9	486.1	715.7	0.0	0.0
								Totals:		34,909.9	39,577.7	0.00	0.00

Site Number: 302495 Code: ANSI/TIA-222-G

Site Name: Tolland CT, CT Engineering Number:OAA714899_C3_01 11/15/2017 3:52:40 PM

Customer: Sprint Nextel

Load Case: 0.9D + 1.6W 97 mph with No Ice (Reduced DL) 29 Iterations

Gust Response Factor :1.10 Wind Importance Factor 1.00

Dead Load Factor :0.90

Wind Load Factor :1.60

Calculated Forces

Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	phi Pn (kips)	phi Vn (kips)	phi Tn (ft-kips)	phi Mn (ft-kips)	Total Deflect (in)	Rotation (deg)	Ratio
0.00	-39.53	-34.78	0.00	-3,811.94	0.00	3,811.94	4,665.07	2,332.54	9,536.02	4,709.48	0.00	0.00	0.818
3.00	-38.65	-34.52	0.00	-3,707.60	0.00	3,707.60	4,631.78	2,315.89	9,346.21	4,615.74	0.05	-0.15	0.812
6.00	-37.78	-34.26	0.00	-3,604.05	0.00	3,604.05	4,597.82	2,298.91	9,156.81	4,522.21	0.19	-0.29	0.805
9.00	-36.92	-34.00	0.00	-3,501.27	0.00	3,501.27	4,563.18	2,281.59	8,967.87	4,428.89	0.42	-0.44	0.799
12.00	-36.07	-33.74	0.00	-3,399.28	0.00	3,399.28	4,527.86	2,263.93	8,779.43	4,335.83	0.75	-0.60	0.792
15.00	-35.24	-33.53	0.00	-3,298.06	0.00	3,298.06	4,491.86	2,245.93	8,591.56	4,243.05	1.17	-0.75	0.785
17.00	-34.53	-32.80	0.00	-3,231.00	0.00	3,231.00	4,467.49	2,233.75	8,466.65	4,181.36	1.51	-0.85	0.781
18.00	-34.23	-32.64	0.00	-3,198.20	0.00	3,198.20	4,455.19	2,227.60	8,404.31	4,150.57	1.69	-0.90	0.778
21.00	-33.40	-32.39	0.00	-3,100.28	0.00	3,100.28	4,417.85	2,208.92	8,217.72	4,058.43	2.31	-1.06	0.772
24.00	-32.58	-32.13	0.00	-3,003.13	0.00	3,003.13	4,379.82	2,189.91	8,031.86	3,966.64	3.03	-1.22	0.765
27.00	-31.78	-31.88	0.00	-2,906.73	0.00	2,906.73	4,341.13	2,170.56	7,846.78	3,875.23	3.85	-1.38	0.758
30.00	-30.98	-31.63	0.00	-2,811.09	0.00	2,811.09	4,301.75	2,150.88	7,662.53	3,784.23	4.76	-1.54	0.750
33.00	-30.19	-31.37	0.00	-2,716.20	0.00	2,716.20	4,261.70	2,130.85	7,479.16	3,693.68	5.78	-1.70	0.743
36.00	-29.41	-31.11	0.00	-2,622.08	0.00	2,622.08	4,220.97	2,110.49	7,296.73	3,603.58	6.90	-1.86	0.735
39.00	-28.66	-30.92	0.00	-2,528.75	0.00	2,528.75	4,179.57	2,089.78	7,115.28	3,513.97	8.12	-2.03	0.727
40.10	-28.37	-30.78	0.00	-2,494.61	0.00	2,494.61	4,164.16	2,082.08	7,048.76	3,481.12	8.60	-2.09	0.724
42.00	-27.58	-30.55	0.00	-2,436.25	0.00	2,436.25	4,137.49	2,068.74	6,934.89	3,424.88	9.45	-2.20	0.718
45.00	-26.40	-30.34	0.00	-2,344.60	0.00	2,344.60	4,094.73	2,047.37	6,755.59	3,336.33	10.89	-2.36	0.709
45.90	-26.03	-30.19	0.00	-2,317.35	0.00	2,317.35	3,345.43	1,672.72	5,614.65	2,772.86	11.34	-2.42	0.844
48.00	-25.55	-30.00	0.00	-2,253.90	0.00	2,253.90	3,324.15	1,662.07	5,517.72	2,724.99	12.43	-2.54	0.835
50.00	-25.04	-29.76	0.00	-2,193.91	0.00	2,193.91	3,303.59	1,651.79	5,425.69	2,679.55	13.52	-2.66	0.827
51.00	-24.79	-29.58	0.00	-2,164.15	0.00	2,164.15	3,293.20	1,646.60	5,379.77	2,656.86	14.08	-2.73	0.822
54.00	-24.12	-29.29	0.00	-2,075.40	0.00	2,075.40	3,261.57	1,630.78	5,242.36	2,589.00	15.86	-2.91	0.809
57.00	-23.46	-29.00	0.00	-1,987.53	0.00	1,987.53	3,229.26	1,614.63	5,105.54	2,521.44	17.75	-3.10	0.796
60.00	-22.81	-28.71	0.00	-1,900.53	0.00	1,900.53	3,196.28	1,598.14	4,969.37	2,454.19	19.76	-3.29	0.782
63.00	-22.02	-28.19	0.00	-1,814.41	0.00	1,814.41	3,162.62	1,581.31	4,833.91	2,387.28	21.89	-3.49	0.767
66.00	-21.39	-27.89	0.00	-1,729.84	0.00	1,729.84	3,128.28	1,564.14	4,699.19	2,320.75	24.14	-3.68	0.753
69.00	-20.77	-27.59	0.00	-1,646.17	0.00	1,646.17	3,093.27	1,546.64	4,565.29	2,254.62	26.51	-3.87	0.737
72.00	-20.15	-27.29	0.00	-1,563.41	0.00	1,563.41	3,057.58	1,528.79	4,432.24	2,188.92	29.00	-4.06	0.721
75.00	-19.55	-26.98	0.00	-1,481.55	0.00	1,481.55	3,021.22	1,510.61	4,300.11	2,123.66	31.62	-4.26	0.704
78.00	-18.96	-26.69	0.00	-1,400.61	0.00	1,400.61	2,984.18	1,492.09	4,168.95	2,058.89	34.35	-4.45	0.687
80.60	-18.47	-26.53	0.00	-1,331.23	0.00	1,331.23	2,951.54	1,475.77	4,056.14	2,003.18	36.82	-4.62	0.671
81.00	-18.33	-26.41	0.00	-1,320.59	0.00	1,320.59	2,946.46	1,473.23	4,038.81	1,994.61	37.21	-4.64	0.669
83.00	-17.68	-26.09	0.00	-1,267.78	0.00	1,267.78	2,920.94	1,460.47	3,952.64	1,952.06	39.18	-4.77	0.656
84.00	-17.39	-25.96	0.00	-1,241.69	0.00	1,241.69	2,908.96	1,454.48	3,910.94	1,931.47	40.18	-4.84	0.649
85.41	-16.97	-25.79	0.00	-1,205.18	0.00	1,205.18	2,288.86	1,144.43	3,120.34	1,541.02	41.62	-4.93	0.790
87.00	-16.68	-25.57	0.00	-1,164.08	0.00	1,164.08	2,274.94	1,137.47	3,069.59	1,515.95	43.28	-5.03	0.776
90.00	-16.17	-25.26	0.00	-1,087.37	0.00	1,087.37	2,248.22	1,124.11	2,974.43	1,468.96	46.51	-5.24	0.748
93.00	-15.66	-24.96	0.00	-1,011.58	0.00	1,011.58	2,220.81	1,110.41	2,879.80	1,422.23	49.87	-5.46	0.719
96.00	-15.17	-24.66	0.00	-936.70	0.00	936.70	2,192.74	1,096.37	2,785.75	1,375.78	53.36	-5.66	0.688
99.00	-14.68	-24.35	0.00	-862.73	0.00	862.73	2,163.98	1,081.99	2,692.34	1,329.64	56.98	-5.87	0.656
102.00	-14.20	-24.05	0.00	-789.67	0.00	789.67	2,134.56	1,067.28	2,599.61	1,283.85	60.72	-6.07	0.622
105.00	-13.73	-23.78	0.00	-717.52	0.00	717.52	2,104.45	1,052.22	2,507.63	1,238.42	64.59	-6.26	0.586
107.00	-13.43	-22.44	0.00	-669.96	0.00	669.96	2,084.00	1,042.00	2,446.74	1,208.36	67.23	-6.39	0.561
108.00	-13.27	-22.26	0.00	-647.51	0.00	647.51	2,073.67	1,036.83	2,416.44	1,193.39	68.57	-6.45	0.549
111.00	-12.84	-21.96	0.00	-580.74	0.00	580.74	2,042.21	1,021.11	2,326.10	1,148.77	72.68	-6.63	0.512
114.00	-12.42	-21.66	0.00	-514.87	0.00	514.87	2,006.48	1,003.24	2,232.66	1,102.63	76.89	-6.80	0.474
117.00	-12.01	-21.36	0.00	-449.90	0.00	449.90	1,959.62	979.81	2,129.00	1,051.43	81.20	-6.96	0.434
120.00	-11.61	-21.08	0.00	-385.82	0.00	385.82	1,912.75	956.38	2,027.81	1,001.46	85.62	-7.11	0.392
122.12	-11.34	-20.83	0.00	-341.10	0.00	341.10	1,879.60	939.80	1,957.71	966.84	88.79	-7.21	0.359
123.00	-9.65	-17.54	0.00	-322.82	0.00	322.82	1,865.89	932.94	1,929.08	952.70	90.12	-7.25	0.344

Site Number: 302495 Code: ANSI/TIA-222-G

Site Name: Tolland CT, CT Engineering Number:OAA714899_C3_01 11/15/2017 3:52:40 PM

Customer: Sprint Nextel

Load Case: 0.9D + 1.6W 97 mph with No Ice (Reduced DL) 29 Iterations

Gust Response Factor :1.10 Wind Importance Factor 1.00

Dead Load Factor :0.90

Wind Load Factor :1.60

125.89	-9.18	-17.23	0.00	-272.22	0.00	272.22	929.68	464.84	961.73	474.96	94.53	-7.37	0.584
126.00	-9.16	-17.07	0.00	-270.25	0.00	270.25	929.29	464.65	960.40	474.31	94.71	-7.38	0.581
129.00	-8.89	-16.65	0.00	-219.02	0.00	219.02	918.88	459.44	925.49	457.06	99.39	-7.55	0.490
132.00	-8.64	-16.33	0.00	-169.07	0.00	169.07	907.79	453.90	890.46	439.76	104.17	-7.70	0.395
133.00	-6.33	-12.11	0.00	-152.74	0.00	152.74	903.95	451.97	878.77	433.99	105.78	-7.74	0.360
135.00	-6.19	-11.78	0.00	-128.52	0.00	128.52	896.03	448.02	855.37	422.43	109.03	-7.82	0.312
138.00	-5.99	-11.36	0.00	-93.19	0.00	93.19	883.59	441.80	820.26	405.10	113.96	-7.92	0.237
141.00	-5.79	-11.00	0.00	-59.10	0.00	59.10	870.48	435.24	785.20	387.78	118.95	-7.99	0.160
143.00	-3.42	-5.67	0.00	-37.11	0.00	37.11	861.36	430.68	761.88	376.27	122.30	-8.03	0.103
144.00	-3.37	-5.54	0.00	-31.44	0.00	31.44	856.69	428.34	750.24	370.52	123.97	-8.04	0.089
146.00	-3.26	-5.41	0.00	-20.35	0.00	20.35	847.12	423.56	727.02	359.05	127.34	-8.06	0.061
146.00	-3.26	-5.41	0.00	-20.35	0.00	20.35	920.33	460.16	575.46	378.52	127.34	-8.06	0.057
147.00	-3.17	-5.27	0.00	-14.94	0.00	14.94	920.33	460.16	575.46	378.52	129.02	-8.07	0.043
149.00	-0.93	-0.79	0.00	-4.12	0.00	4.12	920.33	460.16	575.46	378.52	132.39	-8.08	0.012
150.00	-0.86	-0.70	0.00	-3.34	0.00	3.34	920.33	460.16	575.46	378.52	134.08	-8.08	0.010
153.00	-0.64	-0.58	0.00	-1.23	0.00	1.23	920.33	460.16	575.46	378.52	139.14	-8.08	0.004
155.00	0.00	-0.49	0.00	-0.06	0.00	0.06	920.33	460.16	575.46	378.52	142.51	-8.08	0.000

Load Case: 1.2D + 1.0Di + 1.0Wi — 50 mph with 1.00 in Radial Ice — 29 Iterations

Gust Response Factor :1.10 | Ice Dead Load Factor :1.00 | Wind Importance Factor :1.00
Dead Load Factor :1.20 | Ice Importance Factor :1.00
Wind Load Factor :1.00

Applied Segment Forces Summary

		Shaft Forces		Discrete Forces				Linear Forces		Sum of Forces			
Seg Elev (ft)	Description	Wind FX (lb)	Dead Load (lb)	Wind FX (lb)	Torsion MY (lb-ft)	Moment MZ (lb-ft)	Dead Load (lb)	Wind FX (lb)	Dead Load (lb)	Wind FX (lb)	Dead Load (lb)	Torsion MY (lb-ft)	Moment MZ (lb)
0.00		38.2	0.0					0.0	0.0	38.2	0.0	0.0	0.0
3.00		76.1	1,139.9					0.0	370.9	76.1	1,510.8	0.0	0.0
6.00		75.6	1,159.6					0.0	397.0	75.6	1,556.7	0.0	0.0
9.00		74.9	1,161.9					0.0	410.8	74.9	1,572.7	0.0	0.0
12.00		74.1	1,158.4					0.0	420.6	74.1	1,579.0	0.0	0.0
15.00		61.2	1,152.0					0.0	428.2	61.2	1,580.2	0.0	0.0
17.00	Appertunance(s)	36.4	764.0	112.5	0.0	0.0	472.4	0.0	289.0	148.9	1,525.4	0.0	0.0
18.00		48.1	380.8					0.0	140.7	48.1	521.5	0.0	0.0
21.00		71.6	1,134.3					0.0	425.4	71.6	1,559.7	0.0	0.0
24.00		70.8	1,123.9					0.0	429.8	70.8	1,553.7	0.0	0.0
27.00		69.9	1,112.8					0.0	433.7	69.9	1,546.5	0.0	0.0
30.00		69.6	1,101.1					0.0	437.2	69.6	1,538.3	0.0	0.0
33.00		70.1	1,089.0					0.0	440.4	70.1	1,529.4	0.0	0.0
36.00		71.0	1,076.5					0.0	443.4	71.0	1,519.9	0.0	0.0
39.00		48.9	1,063.6					0.0	446.2	48.9	1,509.8	0.0	0.0
40.10	Bot - Section 2	36.4	388.8					0.0	164.9	36.4	553.7	0.0	0.0
42.00		60.0	1,056.7					0.0	283.9	60.0	1,340.6	0.0	0.0
45.00		47.9	1,652.7					0.0	451.2	47.9	2,104.0	0.0	0.0
45.90	Top - Section 1	37.1	491.0					0.0	135.6	37.1	626.6	0.0	0.0
48.00		50.8	660.2					0.0	317.9	50.8	978.2	0.0	0.0
50.00	Appertunance(s)	37.2	622.8	26.2	0.0	0.0	167.9	0.0	303.6	63.4	1,094.3	0.0	0.0
51.00		49.8	309.6					0.0	145.6	49.8	455.2	0.0	0.0
54.00		74.8	918.9					0.0	438.0	74.8	1,356.9	0.0	0.0
57.00		74.9	906.4					0.0	439.8	74.9	1,346.1	0.0	0.0
60.00		74.9	893.7					0.0	441.5	74.9	1,335.1	0.0	0.0
63.00	Appertunance(s)	74.8	880.8	55.6	0.0	0.0	433.0	0.0	443.1	130.4	1,756.9	0.0	0.0
66.00		74.7	867.9					0.0	420.3	74.7	1,288.2	0.0	0.0
69.00		74.5	854.8					0.0	421.7	74.5	1,276.5	0.0	0.0
72.00		74.3	841.6					0.0	422.9	74.3	1,264.6	0.0	0.0
75.00		74.0	828.3					0.0	424.2	74.0	1,252.5	0.0	0.0
78.00		68.8	815.0					0.0	425.3	68.8	1,240.3	0.0	0.0
80.60	Bot - Section 3	36.8	695.5					0.0	369.4	36.8	1,064.9	0.0	0.0
81.00		29.8	163.5					0.0	57.1	29.8	220.6	0.0	0.0
83.00	Appertunance(s)	37.1	808.7	36.1	0.0	0.0	220.5	0.0	284.9	73.2	1,314.1	0.0	0.0
84.00		29.7	401.1					0.0	135.5	29.7	536.6	0.0	0.0
85.41	Top - Section 2	36.9	559.8					0.0	190.7	36.9	750.5	0.0	0.0
87.00		56.3	375.5					0.0	216.4	56.3	591.9	0.0	0.0
90.00		73.1	696.3					0.0	408.0	73.1	1,104.3	0.0	0.0
93.00		72.5	684.1					0.0	408.9	72.5	1,093.0	0.0	0.0
96.00		71.9	671.9					0.0	409.7	71.9	1,081.6	0.0	0.0
99.00		71.3	659.6					0.0	410.6	71.3	1,070.1	0.0	0.0
102.00		70.6	647.2					0.0	411.4	70.6	1,058.6	0.0	0.0
105.00	Appertunance(s)	58.4	634.8	3.2	0.0	0.0	45.0	0.0	412.2	61.5	1,092.0	0.0	0.0
107.00	Appertunance(s)	34.8	416.9	230.9	0.0	0.0	1,253.6	0.0	275.2	265.7	1,945.7	0.0	0.0
108.00		46.0	206.7					0.0	109.5	46.0	316.2	0.0	0.0
111.00		68.4	609.8					0.0	329.0	68.4	938.7	0.0	0.0
114.00		67.6	597.2					0.0	329.5	67.6	926.7	0.0	0.0
117.00		66.8	584.6					0.0	330.0	66.8	914.5	0.0	0.0

Site Number: 302495 Code: ANSI/TIA-222-G

Site Name: Tolland CT, CT Engineering Number:OAA714899_C3_01 11/15/2017 3:52:45 PM

Customer: Sprint Nextel

Load Case: 1.2D + 1.0Di + 1.0Wi 50 mph with 1.00 in Radial Ice 29 Iterations

Gust Response Factor :1.10 Ice Dead Load Factor :1.00 Wind Importance Factor :1.00

Dead Load Factor :1.20 Ice Importance Factor :1.00

Wind Load Factor :1.00

120.00		56.4	571.9					0.0	330.5	56.4	902.3	0.0	0.0
122.12	Bot - Section 4	32.9	397.5					34.9	273.3	67.8	670.8	0.0	0.0
123.00	Appertunance(s)	41.1	219.5	717.6	0.0	0.0	5,822.2	14.5	113.1	773.2	6,154.8	0.0	0.0
125.89	Top - Section 3	32.7	709.4					47.9	346.1	80.6	1,055.5	0.0	0.0
126.00		33.5	16.4					1.9	13.8	35.4	30.1	0.0	0.0
129.00		64.0	421.3					50.3	360.4	114.3	781.7	0.0	0.0
132.00		42.3	411.6					50.7	360.9	93.0	772.5	0.0	0.0
133.00	Appertunance(s)	31.3	135.7	929.2	0.0	0.0	8,608.0	17.0	120.4	977.5	8,864.1	0.0	0.0
135.00		51.6	267.4					34.1	219.7	85.7	487.1	0.0	0.0
138.00		61.1	392.1					51.5	329.9	112.6	722.0	0.0	0.0
141.00		50.2	382.2					51.9	330.5	102.1	712.7	0.0	0.0
143.00	Appertunance(s)	29.8	250.0	1,328.7	0.0	0.0	9,879.8	34.8	220.6	1,393.3	10,350.4	0.0	0.0
144.00		29.4	123.7					0.0	60.9	29.4	184.6	0.0	0.0
146.00	Top - Section 4	27.2	243.4					0.0	121.9	27.2	365.3	0.0	0.0
147.00		22.9	151.4					12.7	61.0	35.6	212.3	0.0	0.0
149.00	Appertunance(s)	22.9	302.8	991.1	0.0	94.9	8,752.1	25.5	122.0	1,039.6	9,177.0	0.0	0.0
150.00		30.7	151.5					0.0	5.9	30.7	157.4	0.0	0.0
153.00		38.5	454.7					0.0	17.7	38.5	472.4	0.0	0.0
155.00	Appertunance(s)	15.5	303.3	100.5	0.0	13.9	1,567.9	0.0	11.8	116.0	1,883.0	0.0	0.0
								Totals:		8,542.73	99,849.2	0.00	0.00

Site Number: 302495 Code: ANSI/TIA-222-G

Site Name: Tolland CT, CT Engineering Number:OAA714899_C3_01 11/15/2017 3:52:45 PM

Customer: Sprint Nextel

Load Case: 1.2D + 1.0Di + 1.0Wi 50 mph with 1.00 in Radial Ice 29 Iterations

Gust Response Factor :1.10 Ice Dead Load Factor :1.00 Wind Importance Factor :1.00

Dead Load Factor :1.20 Ice Importance Factor :1.00

Wind Load Factor :1.00

Calculated Forces

Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	phi Pn (kips)	phi Vn (kips)	phi Tn (ft-kips)	phi Mn (ft-kips)	Total Deflect (in)	Rotation (deg)	Ratio
0.00	-99.85	-8.54	0.00	-1,082.46	0.00	1,082.46	4,665.07	2,332.54	9,536.02	4,709.48	0.00	0.00	0.251
3.00	-98.33	-8.54	0.00	-1,056.84	0.00	1,056.84	4,631.78	2,315.89	9,346.21	4,615.74	0.01	-0.04	0.250
6.00	-96.77	-8.53	0.00	-1,031.23	0.00	1,031.23	4,597.82	2,298.91	9,156.81	4,522.21	0.05	-0.08	0.249
9.00	-95.19	-8.53	0.00	-1,005.63	0.00	1,005.63	4,563.18	2,281.59	8,967.87	4,428.89	0.12	-0.13	0.248
12.00	-93.60	-8.52	0.00	-980.06	0.00	980.06	4,527.86	2,263.93	8,779.43	4,335.83	0.21	-0.17	0.247
15.00	-92.02	-8.51	0.00	-954.50	0.00	954.50	4,491.86	2,245.93	8,591.56	4,243.05	0.34	-0.21	0.245
17.00	-90.49	-8.39	0.00	-937.48	0.00	937.48	4,467.49	2,233.75	8,466.65	4,181.36	0.43	-0.24	0.244
18.00	-89.96	-8.39	0.00	-929.09	0.00	929.09	4,455.19	2,227.60	8,404.31	4,150.57	0.48	-0.26	0.244
21.00	-88.40	-8.38	0.00	-903.92	0.00	903.92	4,417.85	2,208.92	8,217.72	4,058.43	0.66	-0.31	0.243
24.00	-86.84	-8.37	0.00	-878.78	0.00	878.78	4,379.82	2,189.91	8,031.86	3,966.64	0.87	-0.35	0.241
27.00	-85.28	-8.36	0.00	-853.67	0.00	853.67	4,341.13	2,170.56	7,846.78	3,875.23	1.10	-0.40	0.240
30.00	-83.74	-8.35	0.00	-828.59	0.00	828.59	4,301.75	2,150.88	7,662.53	3,784.23	1.37	-0.44	0.238
33.00	-82.20	-8.34	0.00	-803.54	0.00	803.54	4,261.70	2,130.85	7,479.16	3,693.68	1.66	-0.49	0.237
36.00	-80.68	-8.32	0.00	-778.53	0.00	778.53	4,220.97	2,110.49	7,296.73	3,603.58	1.99	-0.54	0.235
39.00	-79.16	-8.30	0.00	-753.57	0.00	753.57	4,179.57	2,089.78	7,115.28	3,513.97	2.35	-0.59	0.233
40.10	-78.61	-8.30	0.00	-744.40	0.00	744.40	4,164.16	2,082.08	7,048.76	3,481.12	2.48	-0.61	0.233
42.00	-77.26	-8.28	0.00	-728.68	0.00	728.68	4,137.49	2,068.74	6,934.89	3,424.88	2.73	-0.64	0.231
45.00	-75.15	-8.25	0.00	-703.85	0.00	703.85	4,094.73	2,047.37	6,755.59	3,336.33	3.15	-0.69	0.229
45.90	-74.52	-8.24	0.00	-696.44	0.00	696.44	3,345.43	1,672.72	5,614.65	2,772.86	3.28	-0.71	0.273
48.00	-73.54	-8.22	0.00	-679.13	0.00	679.13	3,324.15	1,662.07	5,517.72	2,724.99	3.60	-0.74	0.271
50.00	-72.44	-8.18	0.00	-662.69	0.00	662.69	3,303.59	1,651.79	5,425.69	2,679.55	3.92	-0.78	0.269
51.00	-71.98	-8.17	0.00	-654.51	0.00	654.51	3,293.20	1,646.60	5,379.77	2,656.86	4.09	-0.80	0.268
54.00	-70.62	-8.15	0.00	-630.00	0.00	630.00	3,261.57	1,630.78	5,242.36	2,589.00	4.61	-0.86	0.265
57.00	-69.27	-8.12	0.00	-605.56	0.00	605.56	3,229.26	1,614.63	5,105.54	2,521.44	5.17	-0.91	0.262
60.00	-67.92	-8.09	0.00	-581.20	0.00	581.20	3,196.28	1,598.14	4,969.37	2,454.19	5.76	-0.97	0.258
63.00	-66.16	-8.00	0.00	-556.92	0.00	556.92	3,162.62	1,581.31	4,833.91	2,387.28	6.39	-1.03	0.254
66.00	-64.87	-7.97	0.00	-532.92	0.00	532.92	3,128.28	1,564.14	4,699.19	2,320.75	7.06	-1.09	0.250
69.00	-63.58	-7.94	0.00	-509.02	0.00	509.02	3,093.27	1,546.64	4,565.29	2,254.62	7.76	-1.15	0.246
72.00	-62.31	-7.90	0.00	-485.21	0.00	485.21	3,057.58	1,528.79	4,432.24	2,188.92	8.50	-1.21	0.242
75.00	-61.05	-7.86	0.00	-461.51	0.00	461.51	3,021.22	1,510.61	4,300.11	2,123.66	9.28	-1.27	0.238
78.00	-59.81	-7.83	0.00	-437.92	0.00	437.92	2,984.18	1,492.09	4,168.95	2,058.89	10.10	-1.33	0.233
80.60	-58.74	-7.79	0.00	-417.58	0.00	417.58	2,951.54	1,475.77	4,056.14	2,003.18	10.84	-1.38	0.228
81.00	-58.52	-7.78	0.00	-414.46	0.00	414.46	2,946.46	1,473.23	4,038.81	1,994.61	10.95	-1.39	0.228
83.00	-57.20	-7.71	0.00	-398.89	0.00	398.89	2,920.94	1,460.47	3,952.64	1,952.06	11.55	-1.43	0.224
84.00	-56.66	-7.69	0.00	-391.18	0.00	391.18	2,908.96	1,454.48	3,910.94	1,931.47	11.85	-1.45	0.222
85.41	-55.91	-7.66	0.00	-380.37	0.00	380.37	2,288.86	1,144.43	3,120.34	1,541.02	12.28	-1.48	0.271
87.00	-55.31	-7.64	0.00	-368.15	0.00	368.15	2,274.94	1,137.47	3,069.59	1,515.95	12.78	-1.51	0.267
90.00	-54.20	-7.60	0.00	-345.23	0.00	345.23	2,248.22	1,124.11	2,974.43	1,468.96	13.75	-1.58	0.259
93.00	-53.10	-7.56	0.00	-322.43	0.00	322.43	2,220.81	1,110.41	2,879.80	1,422.23	14.77	-1.65	0.251
96.00	-52.01	-7.52	0.00	-299.75	0.00	299.75	2,192.74	1,096.37	2,785.75	1,375.78	15.82	-1.71	0.242
99.00	-50.94	-7.47	0.00	-277.20	0.00	277.20	2,163.98	1,081.99	2,692.34	1,329.64	16.92	-1.78	0.232
102.00	-49.87	-7.42	0.00	-254.79	0.00	254.79	2,134.56	1,067.28	2,599.61	1,283.85	18.06	-1.84	0.222
105.00	-48.78	-7.37	0.00	-232.53	0.00	232.53	2,104.45	1,052.22	2,507.63	1,238.42	19.24	-1.91	0.211
107.00	-46.84	-7.06	0.00	-217.79	0.00	217.79	2,084.00	1,042.00	2,446.74	1,208.36	20.05	-1.95	0.203
108.00	-46.52	-7.04	0.00	-210.73	0.00	210.73	2,073.67	1,036.83	2,416.44	1,193.39	20.46	-1.97	0.199
111.00	-45.58	-6.98	0.00	-189.62	0.00	189.62	2,042.21	1,021.11	2,326.10	1,148.77	21.71	-2.03	0.187
114.00	-44.65	-6.92	0.00	-168.67	0.00	168.67	2,006.48	1,003.24	2,232.66	1,102.63	23.00	-2.08	0.175
117.00	-43.73	-6.86	0.00	-147.90	0.00	147.90	1,959.62	979.81	2,129.00	1,051.43	24.33	-2.14	0.163
120.00	-42.82	-6.80	0.00	-127.32	0.00	127.32	1,912.75	956.38	2,027.81	1,001.46	25.69	-2.18	0.150
122.12	-42.15	-6.73	0.00	-112.88	0.00	112.88	1,879.60	939.80	1,957.71	966.84	26.66	-2.22	0.139
123.00	-36.03	-5.73	0.00	-106.98	0.00	106.98	1,865.89	932.94	1,929.08	952.70	27.07	-2.23	0.132

Load Case: 1.2D + 1.0Di + 1.0Wi 50 mph with 1.00 in Radial Ice 29 Iterations

Gust Response Factor :1.10 Ice Dead Load Factor :1.00 Wind Importance Factor :1.00
Dead Load Factor :1.20 Ice Importance Factor :1.00
Wind Load Factor :1.00

125.89	-34.98	-5.62	0.00	-90.44	0.00	90.44	929.68	464.84	961.73	474.96	28.43	-2.27	0.228
126.00	-34.95	-5.60	0.00	-89.79	0.00	89.79	929.29	464.65	960.40	474.31	28.49	-2.27	0.227
129.00	-34.16	-5.49	0.00	-72.98	0.00	72.98	918.88	459.44	925.49	457.06	29.94	-2.33	0.197
132.00	-33.39	-5.38	0.00	-56.51	0.00	56.51	907.79	453.90	890.46	439.76	31.42	-2.38	0.165
133.00	-24.58	-4.05	0.00	-51.13	0.00	51.13	903.95	451.97	878.77	433.99	31.92	-2.39	0.145
135.00	-24.09	-3.95	0.00	-43.04	0.00	43.04	896.03	448.02	855.37	422.43	32.92	-2.42	0.129
138.00	-23.37	-3.82	0.00	-31.18	0.00	31.18	883.59	441.80	820.26	405.10	34.46	-2.45	0.103
141.00	-22.66	-3.70	0.00	-19.71	0.00	19.71	870.48	435.24	785.20	387.78	36.01	-2.48	0.077
143.00	-12.38	-1.86	0.00	-12.32	0.00	12.32	861.36	430.68	761.88	376.27	37.05	-2.49	0.047
144.00	-12.20	-1.82	0.00	-10.46	0.00	10.46	856.69	428.34	750.24	370.52	37.57	-2.49	0.042
146.00	-11.84	-1.78	0.00	-6.82	0.00	6.82	847.12	423.56	727.02	359.05	38.61	-2.50	0.033
146.00	-11.84	-1.78	0.00	-6.82	0.00	6.82	920.33	460.16	575.46	378.52	38.61	-2.50	0.031
147.00	-11.63	-1.73	0.00	-5.04	0.00	5.04	920.33	460.16	575.46	378.52	39.14	-2.50	0.026
149.00	-2.50	-0.29	0.00	-1.48	0.00	1.48	920.33	460.16	575.46	378.52	40.19	-2.51	0.007
150.00	-2.35	-0.26	0.00	-1.18	0.00	1.18	920.33	460.16	575.46	378.52	40.71	-2.51	0.006
153.00	-1.88	-0.20	0.00	-0.41	0.00	0.41	920.33	460.16	575.46	378.52	42.29	-2.51	0.003
155.00	0.00	-0.12	0.00	-0.01	0.00	0.01	920.33	460.16	575.46	378.52	43.34	-2.51	0.000

Load Case: 1.0D + 1.0W Serviceability 60 mph 27 Iterations

Gust Response Factor :1.10 Wind Importance Factor 1.00
Dead Load Factor :1.00
Wind Load Factor :1.00

Applied Segment Forces Summary

		Shaft Forces		Discrete Forces				Linear Forces		Sum of Forces			
Seg Elev (ft)	Description	Wind FX (lb)	Dead Load (lb)	Wind FX (lb)	Torsion MY (lb-ft)	Moment MZ (lb-ft)	Dead Load (lb)	Wind FX (lb)	Dead Load (lb)	Wind FX (lb)	Dead Load (lb)	Torsion MY (lb-ft)	Moment MZ (lb)
0.00		43.3	0.0					0.0	0.0	43.3	0.0	0.0	0.0
3.00		86.1	708.2					0.0	171.4	86.1	879.6	0.0	0.0
6.00		85.0	699.1					0.0	171.4	85.0	870.5	0.0	0.0
9.00		83.9	690.0					0.0	171.4	83.9	861.5	0.0	0.0
12.00		82.8	681.0					0.0	171.4	82.8	852.4	0.0	0.0
15.00		68.3	671.9					0.0	171.4	68.3	843.3	0.0	0.0
17.00	Appertunance(s)	40.6	442.9	141.0	0.0	0.0	188.0	0.0	114.3	181.6	745.1	0.0	0.0
18.00		53.5	219.9					0.0	57.1	53.5	277.0	0.0	0.0
21.00		79.5	653.7					0.0	171.3	79.5	825.0	0.0	0.0
24.00		78.4	644.6					0.0	171.3	78.4	815.9	0.0	0.0
27.00		77.3	635.5					0.0	171.3	77.3	806.8	0.0	0.0
30.00		76.8	626.4					0.0	171.3	76.8	797.7	0.0	0.0
33.00		77.2	617.3					0.0	171.3	77.2	788.6	0.0	0.0
36.00		78.0	608.3					0.0	171.3	78.0	779.6	0.0	0.0
39.00		53.7	599.2					0.0	171.3	53.7	770.5	0.0	0.0
40.10	Bot - Section 2	39.9	218.2					0.0	63.0	39.9	281.3	0.0	0.0
42.00		65.8	696.9					0.0	108.3	65.8	805.2	0.0	0.0
45.00		52.5	1,089.0					0.0	171.3	52.5	1,260.3	0.0	0.0
45.90	Top - Section 1	40.5	322.9					0.0	51.3	40.5	374.2	0.0	0.0
48.00		55.5	349.6					0.0	120.0	55.5	469.6	0.0	0.0
50.00	Appertunance(s)	40.6	329.2	19.8	0.0	0.0	80.0	0.0	114.2	60.5	523.4	0.0	0.0
51.00		54.2	163.3					0.0	56.9	54.2	220.2	0.0	0.0
54.00		81.3	484.7					0.0	170.8	81.3	655.5	0.0	0.0
57.00		81.3	476.9					0.0	170.8	81.3	647.7	0.0	0.0
60.00		81.1	469.1					0.0	170.8	81.1	639.9	0.0	0.0
63.00	Appertunance(s)	80.9	461.3	50.5	0.0	0.0	170.0	0.0	170.8	131.4	802.1	0.0	0.0
66.00		80.6	453.5					0.0	169.9	80.6	623.4	0.0	0.0
69.00		80.2	445.7					0.0	169.9	80.2	615.7	0.0	0.0
72.00		79.8	437.9					0.0	169.9	79.8	607.9	0.0	0.0
75.00		79.3	430.1					0.0	169.9	79.3	600.1	0.0	0.0
78.00		73.5	422.3					0.0	169.9	73.5	592.3	0.0	0.0
80.60	Bot - Section 3	39.3	359.6					0.0	147.2	39.3	506.8	0.0	0.0
81.00		31.8	101.7					0.0	22.7	31.8	124.4	0.0	0.0
83.00	Appertunance(s)	39.6	503.5	31.6	0.0	0.0	85.0	0.0	113.3	71.2	701.8	0.0	0.0
84.00		31.6	249.3					0.0	56.5	31.6	305.8	0.0	0.0
85.41	Top - Section 2	39.3	348.0					0.0	79.5	39.3	427.4	0.0	0.0
87.00		59.8	179.6					0.0	90.0	59.8	269.6	0.0	0.0
90.00		77.5	333.1					0.0	169.5	77.5	502.6	0.0	0.0
93.00		76.7	326.6					0.0	169.5	76.7	496.1	0.0	0.0
96.00		75.9	320.1					0.0	169.5	75.9	489.6	0.0	0.0
99.00		75.0	313.6					0.0	169.5	75.0	483.1	0.0	0.0
102.00		74.0	307.1					0.0	169.5	74.0	476.6	0.0	0.0
105.00	Appertunance(s)	61.0	300.6	1.3	0.0	0.0	9.9	0.0	169.5	62.3	480.0	0.0	0.0
107.00	Appertunance(s)	36.3	196.8	280.0	0.0	0.0	150.9	0.0	113.0	316.3	460.7	0.0	0.0
108.00		47.8	97.3					0.0	52.7	47.8	150.0	0.0	0.0
111.00		71.0	287.6					0.0	158.2	71.0	445.8	0.0	0.0
114.00		70.0	281.1					0.0	158.2	70.0	439.3	0.0	0.0
117.00		68.9	274.6					0.0	158.2	68.9	432.8	0.0	0.0

Load Case: 1.0D + 1.0W Serviceability 60 mph 27 Iterations

Gust Response Factor :1.10 Wind Importance Factor 1.00
Dead Load Factor :1.00
Wind Load Factor :1.00

120.00		62.7	268.1					0.0	158.2	62.7	426.3	0.0	0.0
122.12	Bot - Section 4	40.5	185.8					14.6	126.5	55.1	312.3	0.0	0.0
123.00	Appertunance(s)	50.5	122.3	676.8	0.0	0.0	2,120.0	6.1	52.3	733.4	2,294.6	0.0	0.0
125.89	Top - Section 3	40.2	395.8					20.1	150.2	60.2	546.0	0.0	0.0
126.00		41.0	5.9					0.8	6.0	41.8	11.9	0.0	0.0
129.00		78.1	152.3					21.0	156.2	99.1	308.5	0.0	0.0
132.00		51.4	148.4					21.1	156.2	72.6	304.6	0.0	0.0
133.00	Appertunance(s)	37.9	48.6	882.9	0.0	0.0	3,054.2	7.1	52.1	927.9	3,154.9	0.0	0.0
135.00		62.4	95.9					14.2	86.3	76.6	182.2	0.0	0.0
138.00		73.5	140.6					21.4	129.4	94.9	270.0	0.0	0.0
141.00		60.1	136.7					21.6	129.4	81.7	266.1	0.0	0.0
143.00	Appertunance(s)	33.6	89.0	1,134.1	0.0	0.0	3,254.4	14.4	86.3	1,182.2	3,429.7	0.0	0.0
144.00		29.2	43.8					0.0	29.1	29.2	72.9	0.0	0.0
146.00	Top - Section 4	27.9	86.4					0.0	58.1	27.9	144.5	0.0	0.0
147.00		25.5	82.8					5.2	29.1	30.7	111.9	0.0	0.0
149.00	Appertunance(s)	21.3	165.7	954.3	0.0	67.6	2,944.1	10.4	58.1	986.0	3,167.9	0.0	0.0
150.00		17.1	82.8					0.0	4.9	17.1	87.8	0.0	0.0
153.00		21.5	248.5					0.0	14.8	21.5	263.3	0.0	0.0
155.00	Appertunance(s)	8.6	165.7	107.6	0.0	14.8	619.7	0.0	9.8	116.2	795.2	0.0	0.0
								Totals:		8,348.11	43,975.2	0.00	0.00

Load Case: 1.0D + 1.0W Serviceability 60 mph 27 Iterations

Gust Response Factor :1.10 Wind Importance Factor 1.00
Dead Load Factor :1.00
Wind Load Factor :1.00

Calculated Forces

Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	phi Pn (kips)	phi Vn (kips)	phi Tn (ft-kips)	phi Mn (ft-kips)	Total Deflect (in)	Rotation (deg)	Ratio
0.00	-43.97	-8.32	0.00	-919.23	0.00	919.23	4,665.07	2,332.54	9,536.02	4,709.48	0.00	0.00	0.205
3.00	-43.09	-8.26	0.00	-894.28	0.00	894.28	4,631.78	2,315.89	9,346.21	4,615.74	0.01	-0.04	0.203
6.00	-42.21	-8.20	0.00	-869.51	0.00	869.51	4,597.82	2,298.91	9,156.81	4,522.21	0.05	-0.07	0.201
9.00	-41.35	-8.14	0.00	-844.91	0.00	844.91	4,563.18	2,281.59	8,967.87	4,428.89	0.10	-0.11	0.200
12.00	-40.49	-8.08	0.00	-820.49	0.00	820.49	4,527.86	2,263.93	8,779.43	4,335.83	0.18	-0.14	0.198
15.00	-39.64	-8.03	0.00	-796.25	0.00	796.25	4,491.86	2,245.93	8,591.56	4,243.05	0.28	-0.18	0.196
17.00	-38.89	-7.86	0.00	-780.19	0.00	780.19	4,467.49	2,233.75	8,466.65	4,181.36	0.36	-0.21	0.195
18.00	-38.61	-7.82	0.00	-772.33	0.00	772.33	4,455.19	2,227.60	8,404.31	4,150.57	0.41	-0.22	0.195
21.00	-37.78	-7.76	0.00	-748.86	0.00	748.86	4,417.85	2,208.92	8,217.72	4,058.43	0.56	-0.26	0.193
24.00	-36.96	-7.71	0.00	-725.57	0.00	725.57	4,379.82	2,189.91	8,031.86	3,966.64	0.73	-0.29	0.191
27.00	-36.15	-7.65	0.00	-702.45	0.00	702.45	4,341.13	2,170.56	7,846.78	3,875.23	0.93	-0.33	0.190
30.00	-35.35	-7.59	0.00	-679.50	0.00	679.50	4,301.75	2,150.88	7,662.53	3,784.23	1.15	-0.37	0.188
33.00	-34.56	-7.53	0.00	-656.73	0.00	656.73	4,261.70	2,130.85	7,479.16	3,693.68	1.40	-0.41	0.186
36.00	-33.77	-7.47	0.00	-634.13	0.00	634.13	4,220.97	2,110.49	7,296.73	3,603.58	1.67	-0.45	0.184
39.00	-33.00	-7.43	0.00	-611.71	0.00	611.71	4,179.57	2,089.78	7,115.28	3,513.97	1.96	-0.49	0.182
40.10	-32.71	-7.40	0.00	-603.51	0.00	603.51	4,164.16	2,082.08	7,048.76	3,481.12	2.08	-0.50	0.181
42.00	-31.91	-7.34	0.00	-589.49	0.00	589.49	4,137.49	2,068.74	6,934.89	3,424.88	2.28	-0.53	0.180
45.00	-30.64	-7.29	0.00	-567.46	0.00	567.46	4,094.73	2,047.37	6,755.59	3,336.33	2.63	-0.57	0.178
45.90	-30.27	-7.26	0.00	-560.91	0.00	560.91	3,345.43	1,672.72	5,614.65	2,772.86	2.74	-0.58	0.211
48.00	-29.79	-7.21	0.00	-545.65	0.00	545.65	3,324.15	1,662.07	5,517.72	2,724.99	3.00	-0.61	0.209
50.00	-29.27	-7.16	0.00	-531.22	0.00	531.22	3,303.59	1,651.79	5,425.69	2,679.55	3.26	-0.64	0.207
51.00	-29.04	-7.12	0.00	-524.06	0.00	524.06	3,293.20	1,646.60	5,379.77	2,656.86	3.40	-0.66	0.206
54.00	-28.38	-7.05	0.00	-502.71	0.00	502.71	3,261.57	1,630.78	5,242.36	2,589.00	3.83	-0.70	0.203
57.00	-27.73	-6.99	0.00	-481.55	0.00	481.55	3,229.26	1,614.63	5,105.54	2,521.44	4.29	-0.75	0.200
60.00	-27.09	-6.92	0.00	-460.60	0.00	460.60	3,196.28	1,598.14	4,969.37	2,454.19	4.77	-0.80	0.196
63.00	-26.28	-6.80	0.00	-439.84	0.00	439.84	3,162.62	1,581.31	4,833.91	2,387.28	5.29	-0.84	0.193
66.00	-25.65	-6.73	0.00	-419.46	0.00	419.46	3,128.28	1,564.14	4,699.19	2,320.75	5.83	-0.89	0.189
69.00	-25.04	-6.66	0.00	-399.28	0.00	399.28	3,093.27	1,546.64	4,565.29	2,254.62	6.41	-0.94	0.185
72.00	-24.42	-6.59	0.00	-379.31	0.00	379.31	3,057.58	1,528.79	4,432.24	2,188.92	7.01	-0.98	0.181
75.00	-23.82	-6.52	0.00	-359.55	0.00	359.55	3,021.22	1,510.61	4,300.11	2,123.66	7.64	-1.03	0.177
78.00	-23.22	-6.45	0.00	-340.00	0.00	340.00	2,984.18	1,492.09	4,168.95	2,058.89	8.31	-1.08	0.173
80.60	-22.72	-6.41	0.00	-323.23	0.00	323.23	2,951.54	1,475.77	4,056.14	2,003.18	8.90	-1.12	0.169
81.00	-22.59	-6.38	0.00	-320.66	0.00	320.66	2,946.46	1,473.23	4,038.81	1,994.61	9.00	-1.12	0.168
83.00	-21.89	-6.31	0.00	-307.89	0.00	307.89	2,920.94	1,460.47	3,952.64	1,952.06	9.47	-1.16	0.165
84.00	-21.58	-6.28	0.00	-301.59	0.00	301.59	2,908.96	1,454.48	3,910.94	1,931.47	9.72	-1.17	0.164
85.41	-21.15	-6.24	0.00	-292.76	0.00	292.76	2,288.86	1,144.43	3,120.34	1,541.02	10.07	-1.19	0.199
87.00	-20.88	-6.19	0.00	-282.82	0.00	282.82	2,274.94	1,137.47	3,069.59	1,515.95	10.47	-1.22	0.196
90.00	-20.37	-6.12	0.00	-264.26	0.00	264.26	2,248.22	1,124.11	2,974.43	1,468.96	11.25	-1.27	0.189
93.00	-19.87	-6.05	0.00	-245.91	0.00	245.91	2,220.81	1,110.41	2,879.80	1,422.23	12.07	-1.32	0.182
96.00	-19.38	-5.98	0.00	-227.78	0.00	227.78	2,192.74	1,096.37	2,785.75	1,375.78	12.91	-1.37	0.174
99.00	-18.89	-5.90	0.00	-209.85	0.00	209.85	2,163.98	1,081.99	2,692.34	1,329.64	13.79	-1.42	0.167
102.00	-18.41	-5.83	0.00	-192.14	0.00	192.14	2,134.56	1,067.28	2,599.61	1,283.85	14.70	-1.47	0.158
105.00	-17.93	-5.77	0.00	-174.64	0.00	174.64	2,104.45	1,052.22	2,507.63	1,238.42	15.64	-1.52	0.150
107.00	-17.48	-5.45	0.00	-163.09	0.00	163.09	2,084.00	1,042.00	2,446.74	1,208.36	16.28	-1.55	0.143
108.00	-17.33	-5.41	0.00	-157.64	0.00	157.64	2,073.67	1,036.83	2,416.44	1,193.39	16.61	-1.56	0.140
111.00	-16.88	-5.34	0.00	-141.42	0.00	141.42	2,042.21	1,021.11	2,326.10	1,148.77	17.60	-1.61	0.131
114.00	-16.44	-5.27	0.00	-125.41	0.00	125.41	2,006.48	1,003.24	2,232.66	1,102.63	18.62	-1.65	0.122
117.00	-16.00	-5.20	0.00	-109.62	0.00	109.62	1,959.62	979.81	2,129.00	1,051.43	19.67	-1.69	0.112
120.00	-15.58	-5.13	0.00	-94.03	0.00	94.03	1,912.75	956.38	2,027.81	1,001.46	20.75	-1.72	0.102
122.12	-15.26	-5.07	0.00	-83.15	0.00	83.15	1,879.60	939.80	1,957.71	966.84	21.52	-1.75	0.094
123.00	-12.99	-4.27	0.00	-78.70	0.00	78.70	1,865.89	932.94	1,929.08	952.70	21.84	-1.76	0.090

Load Case: 1.0D + 1.0W Serviceability 60 mph 27 Iterations

Gust Response Factor :1.10 Wind Importance Factor 1.00
Dead Load Factor :1.00
Wind Load Factor :1.00

125.89	-12.45	-4.20	0.00	-66.38	0.00	66.38	929.68	464.84	961.73	474.96	22.91	-1.79	0.153
126.00	-12.43	-4.16	0.00	-65.90	0.00	65.90	929.29	464.65	960.40	474.31	22.95	-1.79	0.152
129.00	-12.13	-4.06	0.00	-53.43	0.00	53.43	918.88	459.44	925.49	457.06	24.09	-1.83	0.130
132.00	-11.82	-3.98	0.00	-41.26	0.00	41.26	907.79	453.90	890.46	439.76	25.25	-1.87	0.107
133.00	-8.70	-2.95	0.00	-37.28	0.00	37.28	903.95	451.97	878.77	433.99	25.65	-1.88	0.096
135.00	-8.52	-2.87	0.00	-31.37	0.00	31.37	896.03	448.02	855.37	422.43	26.44	-1.90	0.084
138.00	-8.25	-2.77	0.00	-22.76	0.00	22.76	883.59	441.80	820.26	405.10	27.64	-1.92	0.066
141.00	-7.99	-2.68	0.00	-14.44	0.00	14.44	870.48	435.24	785.20	387.78	28.85	-1.94	0.046
143.00	-4.60	-1.39	0.00	-9.07	0.00	9.07	861.36	430.68	761.88	376.27	29.67	-1.95	0.029
144.00	-4.53	-1.35	0.00	-7.69	0.00	7.69	856.69	428.34	750.24	370.52	30.07	-1.95	0.026
146.00	-4.38	-1.32	0.00	-4.98	0.00	4.98	847.12	423.56	727.02	359.05	30.89	-1.96	0.019
146.00	-4.38	-1.32	0.00	-4.98	0.00	4.98	920.33	460.16	575.46	378.52	30.89	-1.96	0.018
147.00	-4.27	-1.29	0.00	-3.66	0.00	3.66	920.33	460.16	575.46	378.52	31.30	-1.96	0.014
149.00	-1.14	-0.19	0.00	-1.02	0.00	1.02	920.33	460.16	575.46	378.52	32.12	-1.96	0.004
150.00	-1.05	-0.17	0.00	-0.82	0.00	0.82	920.33	460.16	575.46	378.52	32.53	-1.96	0.003
153.00	-0.79	-0.14	0.00	-0.30	0.00	0.30	920.33	460.16	575.46	378.52	33.76	-1.96	0.002
155.00	0.00	-0.12	0.00	-0.01	0.00	0.01	920.33	460.16	575.46	378.52	34.59	-1.96	0.000

Equivalent Lateral Forces Method Analysis

(Based on ASCE7-10 Chapters 11, 12, 15)

Spectral Response Acceleration for Short Period (S_s):	0.17	
Spectral Response Acceleration at 1.0 Second Period (S_1):	0.06	
Long-Period Transition Period (T_L):	6	
Importance Factor (I_E):	1.00	
Site Coefficient F_a:	1.60	
Site Coeffiecient F_v:	2.40	
Response Modification Coefficient (R):	1.50	
Design Spectral Response Acceleration at Short Period (S_{ds}):	0.19	
Design Spectral Response Acceleration at 1.0 Second Period (S_{d1}):	0.10	
Seismic Response Coefficient (C_s):	0.03	
Upper Limit C_s	0.03	
Lower Limit C_s	0.03	
Period based on Rayleigh Method (sec):	2.93	
Redundancy Factor (p):	1.30	
Seismic Force Distribution Exponent (k):	2.00	
Total Unfactored Dead Load:	43.98	k
Seismic Base Shear (E):	1.72	k

Load Case (1.2 + 0.2Sds) * DL + E ELFM Seismic Equivalent Lateral Forces Method

Segment	Height Above Base (ft)	Weight (lb)	W_z (lb-ft)	C_{vx}	Horizontal Force (lb)	Vertical Force (lb)
66	154.00	176	4,163	0.010	17	217
65	151.50	263	6,043	0.015	25	326
64	149.50	88	1,962	0.005	8	109
63	148.00	224	4,902	0.012	20	277
62	146.50	112	2,402	0.006	10	138
61	145.00	145	3,038	0.007	13	179
60	143.50	73	1,501	0.004	6	90
59	142.00	175	3,534	0.009	15	217
58	139.50	266	5,179	0.013	22	329
57	136.50	270	5,031	0.012	21	334
56	134.00	182	3,271	0.008	14	225
55	132.50	101	1,767	0.004	7	125
54	130.50	305	5,187	0.013	22	377
53	127.50	308	5,015	0.012	21	382
52	125.94	12	188	0.000	1	15
51	124.44	546	8,456	0.021	35	676
50	122.56	175	2,623	0.006	11	216
49	121.06	312	4,577	0.011	19	386
48	118.50	426	5,986	0.015	25	527
47	115.50	433	5,774	0.014	24	536
46	112.50	439	5,560	0.014	23	544
45	109.50	446	5,345	0.013	22	552
44	107.50	150	1,734	0.004	7	186

43	106.00	310	3,481	0.008	15	383
42	103.50	470	5,036	0.012	21	582
41	100.50	477	4,814	0.012	20	590
40	97.50	483	4,592	0.011	19	598
39	94.50	490	4,372	0.011	18	606
38	91.50	496	4,153	0.010	17	614
37	88.50	503	3,936	0.010	16	622
36	86.20	270	2,004	0.005	8	334
35	84.70	427	3,067	0.007	13	529
34	83.50	306	2,132	0.005	9	378
33	82.00	617	4,147	0.010	17	763
32	80.80	124	812	0.002	3	154
31	79.30	507	3,187	0.008	13	627
30	76.50	592	3,466	0.008	14	733
29	73.50	600	3,242	0.008	14	742
28	70.50	608	3,021	0.007	13	752
27	67.50	616	2,805	0.007	12	762
26	64.50	623	2,594	0.006	11	771
25	61.50	632	2,391	0.006	10	782
24	58.50	640	2,190	0.005	9	792
23	55.50	648	1,995	0.005	8	801
22	52.50	656	1,807	0.004	8	811
21	50.50	220	562	0.001	2	272
20	49.00	443	1,065	0.003	4	549
19	46.95	470	1,035	0.003	4	581
18	45.45	374	773	0.002	3	463
17	43.50	1,260	2,385	0.006	10	1,559
16	41.05	805	1,357	0.003	6	996
15	39.55	281	440	0.001	2	348
14	37.50	770	1,083	0.003	5	953
13	34.50	780	928	0.002	4	965
12	31.50	789	783	0.002	3	976
11	28.50	798	648	0.002	3	987
10	25.50	807	525	0.001	2	998
9	22.50	816	413	0.001	2	1,010
8	19.50	825	314	0.001	1	1,021
7	17.50	277	85	0.000	0	343
6	16.00	557	143	0.000	1	689
5	13.50	843	154	0.000	1	1,043
4	10.50	852	94	0.000	0	1,055
3	7.50	861	48	0.000	0	1,066
2	4.50	871	18	0.000	0	1,077
1	1.50	880	2	0.000	0	1,088
Ericsson KRY 112 71/	155.00	79	1,903	0.005	8	98
EMS RR90-17-02DP	155.00	41	973	0.002	4	50
Canister	155.00	500	12,013	0.029	50	619
Andrew ABT-DMDF-ADBH	149.00	1	24	0.000	0	1
Powerwave Allgon 702	149.00	7	147	0.000	1	8
Kathrein Scala 782-1	149.00	38	853	0.002	4	48
CCI DTMABP7819VG12A	149.00	115	2,558	0.006	11	143
Raycap DC6-48-60-18-	149.00	32	706	0.002	3	39
7' Omni	149.00	25	555	0.001	2	31
Ericsson RRUS 11 (Ba	149.00	150	3,330	0.008	14	186
Ericsson RRUS-12 800	149.00	180	3,996	0.010	17	223
Powerwave Allgon 777	149.00	105	2,331	0.006	10	130
KMW AM-X-CD-16-65-00	149.00	291	6,460	0.016	27	360
Flat Platform w/ Han	149.00	2,000	44,402	0.108	185	2,475
Nokia B5 RRH4x40-850	143.00	146	2,975	0.007	12	180
Alcatel-Lucent RRH2x	143.00	170	3,478	0.008	14	210
Alcatel-Lucent RRH A	143.00	147	3,006	0.007	13	182
Alcatel-Lucent RRH2x	143.00	180	3,681	0.009	15	223
Swedcom ALP 9212-N	143.00	160	3,276	0.008	14	198
RFS DB-T1-6Z-8AB-0Z	143.00	44	900	0.002	4	54
RFS DB-T1-6Z-8AB-0Z	143.00	44	900	0.002	4	54

Commscope JAHH-65B-R	143.00	364	7,435	0.018	31	450
Flat Platform w/ Han	143.00	2,000	40,898	0.099	170	2,475
Alcatel-Lucent 800 M	133.00	384	6,793	0.017	28	475
Alcatel-Lucent 1900	133.00	180	3,184	0.008	13	223
Decibel 980H65T2E-M	133.00	25	451	0.001	2	32
Alcatel-Lucent TD-RR	133.00	210	3,715	0.009	15	260
KMW ETCR-654L12H6	133.00	255	4,505	0.011	19	315
Flat Platform w/ Han	133.00	2,000	35,378	0.086	147	2,475
Decibel DB844H90E-A	123.00	120	1,815	0.004	8	148
Flat Platform w/ Han	123.00	2,000	30,258	0.074	126	2,475
Commscope LNX-6515DS	107.00	151	1,728	0.004	7	187
Kathrein Smart Bias	105.00	10	109	0.000	0	12
GPS	83.00	10	69	0.000	0	12
Stand-Off	83.00	75	517	0.001	2	93
GPS	63.00	20	79	0.000	0	25
Stand-Off	63.00	150	595	0.001	2	186
2" x 4" GPS	50.00	5	13	0.000	0	6
Stand-Off	50.00	75	188	0.000	1	93
4' Std. Dish	17.00	188	54	0.000	0	233
		43,975	411,585	1.000	1,715	54,412

Load Case (0.9 - 0.2Sds) * DL + E ELFM Seismic (Reduced DL) Equivalent Lateral Forces Method

Segment	Height Above Base (ft)	Weight (lb)	W_z (lb-ft)	C_{vx}	Horizontal Force (lb)	Vertical Force (lb)
66	154.00	176	4,163	0.010	17	151
65	151.50	263	6,043	0.015	25	227
64	149.50	88	1,962	0.005	8	76
63	148.00	224	4,902	0.012	20	193
62	146.50	112	2,402	0.006	10	97
61	145.00	145	3,038	0.007	13	125
60	143.50	73	1,501	0.004	6	63
59	142.00	175	3,534	0.009	15	151
58	139.50	266	5,179	0.013	22	230
57	136.50	270	5,031	0.012	21	233
56	134.00	182	3,271	0.008	14	157
55	132.50	101	1,767	0.004	7	87
54	130.50	305	5,187	0.013	22	263
53	127.50	308	5,015	0.012	21	266
52	125.94	12	188	0.000	1	10
51	124.44	546	8,456	0.021	35	471
50	122.56	175	2,623	0.006	11	151
49	121.06	312	4,577	0.011	19	269
48	118.50	426	5,986	0.015	25	368
47	115.50	433	5,774	0.014	24	373
46	112.50	439	5,560	0.014	23	379
45	109.50	446	5,345	0.013	22	385
44	107.50	150	1,734	0.004	7	129
43	106.00	310	3,481	0.008	15	267
42	103.50	470	5,036	0.012	21	406
41	100.50	477	4,814	0.012	20	411
40	97.50	483	4,592	0.011	19	417
39	94.50	490	4,372	0.011	18	422
38	91.50	496	4,153	0.010	17	428
37	88.50	503	3,936	0.010	16	434
36	86.20	270	2,004	0.005	8	233
35	84.70	427	3,067	0.007	13	369
34	83.50	306	2,132	0.005	9	264
33	82.00	617	4,147	0.010	17	532
32	80.80	124	812	0.002	3	107

31	79.30	507	3,187	0.008	13	437
30	76.50	592	3,466	0.008	14	511
29	73.50	600	3,242	0.008	14	518
28	70.50	608	3,021	0.007	13	524
27	67.50	616	2,805	0.007	12	531
26	64.50	623	2,594	0.006	11	538
25	61.50	632	2,391	0.006	10	545
24	58.50	640	2,190	0.005	9	552
23	55.50	648	1,995	0.005	8	559
22	52.50	656	1,807	0.004	8	565
21	50.50	220	562	0.001	2	190
20	49.00	443	1,065	0.003	4	382
19	46.95	470	1,035	0.003	4	405
18	45.45	374	773	0.002	3	323
17	43.50	1,260	2,385	0.006	10	1,087
16	41.05	805	1,357	0.003	6	695
15	39.55	281	440	0.001	2	243
14	37.50	770	1,083	0.003	5	665
13	34.50	780	928	0.002	4	673
12	31.50	789	783	0.002	3	680
11	28.50	798	648	0.002	3	688
10	25.50	807	525	0.001	2	696
9	22.50	816	413	0.001	2	704
8	19.50	825	314	0.001	1	712
7	17.50	277	85	0.000	0	239
6	16.00	557	143	0.000	1	481
5	13.50	843	154	0.000	1	727
4	10.50	852	94	0.000	0	735
3	7.50	861	48	0.000	0	743
2	4.50	871	18	0.000	0	751
1	1.50	880	2	0.000	0	759
Ericsson KRY 112 71/	155.00	79	1,903	0.005	8	68
EMS RR90-17-02DP	155.00	41	973	0.002	4	35
Canister	155.00	500	12,013	0.029	50	431
Andrew ABT-DMDF-ADBH	149.00	1	24	0.000	0	1
Powerwave Allgon 702	149.00	7	147	0.000	1	6
Kathrein Scala 782-1	149.00	38	853	0.002	4	33
CCI DTMABP7819VG12A	149.00	115	2,558	0.006	11	99
Raycap DC6-48-60-18-	149.00	32	706	0.002	3	27
7' Omni	149.00	25	555	0.001	2	22
Ericsson RRUS 11 (Ba	149.00	150	3,330	0.008	14	129
Ericsson RRUS-12 800	149.00	180	3,996	0.010	17	155
Powerwave Allgon 777	149.00	105	2,331	0.006	10	91
KMW AM-X-CD-16-65-00	149.00	291	6,460	0.016	27	251
Flat Platform w/ Han	149.00	2,000	44,402	0.108	185	1,725
Nokia B5 RRH4x40-850	143.00	146	2,975	0.007	12	126
Alcatel-Lucent RRH2x	143.00	170	3,478	0.008	14	147
Alcatel-Lucent RRH A	143.00	147	3,006	0.007	13	127
Alcatel-Lucent RRH2x	143.00	180	3,681	0.009	15	155
Swedcom ALP 9212-N	143.00	160	3,276	0.008	14	138
RFS DB-T1-6Z-8AB-0Z	143.00	44	900	0.002	4	38
RFS DB-T1-6Z-8AB-0Z	143.00	44	900	0.002	4	38
Commscope JAHH-65B-R	143.00	364	7,435	0.018	31	314
Flat Platform w/ Han	143.00	2,000	40,898	0.099	170	1,725
Alcatel-Lucent 800 M	133.00	384	6,793	0.017	28	331
Alcatel-Lucent 1900	133.00	180	3,184	0.008	13	155
Decibel 980H65T2E-M	133.00	25	451	0.001	2	22
Alcatel-Lucent TD-RR	133.00	210	3,715	0.009	15	181
KMW ETCR-654L12H6	133.00	255	4,505	0.011	19	220
Flat Platform w/ Han	133.00	2,000	35,378	0.086	147	1,725
Decibel DB844H90E-A	123.00	120	1,815	0.004	8	104
Flat Platform w/ Han	123.00	2,000	30,258	0.074	126	1,725
Commscope LNX-6515DS	107.00	151	1,728	0.004	7	130
Kathrein Smart Bias	105.00	10	109	0.000	0	9

GPS	83.00	10	69	0.000	0	9
Stand-Off	83.00	75	517	0.001	2	65
GPS	63.00	20	79	0.000	0	17
Stand-Off	63.00	150	595	0.001	2	129
2" x 4" GPS	50.00	5	13	0.000	0	4
Stand-Off	50.00	75	188	0.000	1	65
4' Std. Dish	17.00	188	54	0.000	0	162
		43,975	411,585	1.000	1,715	37,936

Load Case (1.2 + 0.2Sds) * DL + E ELFM Seismic Equivalent Lateral Forces Method

Calculated Forces

Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	phi Pn (kips)	phi Vn (kips)	phi Tn (ft-kips)	phi Mn (ft-kips)	Total Deflect (in)	Rotation (deg)	Ratio
0.00	-53.32	-1.72	0.00	-229.27	0.00	229.27	4,665.07	2,332.54	9,536.02	4,709.48	0.00	0.00	0.060
3.00	-52.25	-1.73	0.00	-224.11	0.00	224.11	4,631.78	2,315.89	9,346.21	4,615.74	0.00	-0.01	0.060
6.00	-51.18	-1.73	0.00	-218.93	0.00	218.93	4,597.82	2,298.91	9,156.81	4,522.21	0.01	-0.02	0.060
9.00	-50.12	-1.74	0.00	-213.73	0.00	213.73	4,563.18	2,281.59	8,967.87	4,428.89	0.03	-0.03	0.059
12.00	-49.08	-1.75	0.00	-208.51	0.00	208.51	4,527.86	2,263.93	8,779.43	4,335.83	0.05	-0.04	0.059
15.00	-48.39	-1.75	0.00	-203.26	0.00	203.26	4,491.86	2,245.93	8,591.56	4,243.05	0.07	-0.05	0.059
17.00	-47.82	-1.76	0.00	-199.76	0.00	199.76	4,467.49	2,233.75	8,466.65	4,181.36	0.09	-0.05	0.058
18.00	-46.80	-1.76	0.00	-198.00	0.00	198.00	4,455.19	2,227.60	8,404.31	4,150.57	0.10	-0.06	0.058
21.00	-45.79	-1.76	0.00	-192.72	0.00	192.72	4,417.85	2,208.92	8,217.72	4,058.43	0.14	-0.06	0.058
24.00	-44.79	-1.77	0.00	-187.43	0.00	187.43	4,379.82	2,189.91	8,031.86	3,966.64	0.18	-0.07	0.057
27.00	-43.80	-1.77	0.00	-182.12	0.00	182.12	4,341.13	2,170.56	7,846.78	3,875.23	0.23	-0.08	0.057
30.00	-42.82	-1.78	0.00	-176.81	0.00	176.81	4,301.75	2,150.88	7,662.53	3,784.23	0.29	-0.09	0.057
33.00	-41.86	-1.78	0.00	-171.48	0.00	171.48	4,261.70	2,130.85	7,479.16	3,693.68	0.35	-0.10	0.056
36.00	-40.90	-1.78	0.00	-166.15	0.00	166.15	4,220.97	2,110.49	7,296.73	3,603.58	0.42	-0.12	0.056
39.00	-40.56	-1.78	0.00	-160.82	0.00	160.82	4,179.57	2,089.78	7,115.28	3,513.97	0.50	-0.13	0.055
40.10	-39.56	-1.78	0.00	-158.85	0.00	158.85	4,164.16	2,082.08	7,048.76	3,481.12	0.53	-0.13	0.055
42.00	-38.00	-1.77	0.00	-155.48	0.00	155.48	4,137.49	2,068.74	6,934.89	3,424.88	0.58	-0.14	0.055
45.00	-37.54	-1.77	0.00	-150.18	0.00	150.18	4,094.73	2,047.37	6,755.59	3,336.33	0.67	-0.15	0.054
45.90	-36.96	-1.77	0.00	-148.59	0.00	148.59	3,345.43	1,672.72	5,614.65	2,772.86	0.70	-0.15	0.065
48.00	-36.41	-1.77	0.00	-144.87	0.00	144.87	3,324.15	1,662.07	5,517.72	2,724.99	0.77	-0.16	0.064
50.00	-36.04	-1.77	0.00	-141.34	0.00	141.34	3,303.59	1,651.79	5,425.69	2,679.55	0.83	-0.17	0.064
51.00	-35.22	-1.76	0.00	-139.58	0.00	139.58	3,293.20	1,646.60	5,379.77	2,656.86	0.87	-0.17	0.063
54.00	-34.42	-1.76	0.00	-134.30	0.00	134.30	3,261.57	1,630.78	5,242.36	2,589.00	0.98	-0.18	0.062
57.00	-33.63	-1.75	0.00	-129.02	0.00	129.02	3,229.26	1,614.63	5,105.54	2,521.44	1.10	-0.19	0.062
60.00	-32.85	-1.75	0.00	-123.77	0.00	123.77	3,196.28	1,598.14	4,969.37	2,454.19	1.23	-0.21	0.061
63.00	-31.87	-1.74	0.00	-118.53	0.00	118.53	3,162.62	1,581.31	4,833.91	2,387.28	1.36	-0.22	0.060
66.00	-31.10	-1.73	0.00	-113.32	0.00	113.32	3,128.28	1,564.14	4,699.19	2,320.75	1.50	-0.23	0.059
69.00	-30.35	-1.72	0.00	-108.13	0.00	108.13	3,093.27	1,546.64	4,565.29	2,254.62	1.65	-0.24	0.058
72.00	-29.61	-1.71	0.00	-102.97	0.00	102.97	3,057.58	1,528.79	4,432.24	2,188.92	1.81	-0.26	0.057
75.00	-28.88	-1.70	0.00	-97.84	0.00	97.84	3,021.22	1,510.61	4,300.11	2,123.66	1.98	-0.27	0.056
78.00	-28.25	-1.69	0.00	-92.74	0.00	92.74	2,984.18	1,492.09	4,168.95	2,058.89	2.15	-0.28	0.055
80.60	-28.09	-1.69	0.00	-88.36	0.00	88.36	2,951.54	1,475.77	4,056.14	2,003.18	2.31	-0.29	0.054
81.00	-27.33	-1.67	0.00	-87.68	0.00	87.68	2,946.46	1,473.23	4,038.81	1,994.61	2.33	-0.30	0.053
83.00	-26.85	-1.66	0.00	-84.34	0.00	84.34	2,920.94	1,460.47	3,952.64	1,952.06	2.46	-0.30	0.052
84.00	-26.32	-1.64	0.00	-82.69	0.00	82.69	2,908.96	1,454.48	3,910.94	1,931.47	2.52	-0.31	0.052
85.41	-25.98	-1.64	0.00	-80.38	0.00	80.38	2,288.86	1,144.43	3,120.34	1,541.02	2.61	-0.31	0.064
87.00	-25.36	-1.62	0.00	-77.77	0.00	77.77	2,274.94	1,137.47	3,069.59	1,515.95	2.72	-0.32	0.062
90.00	-24.75	-1.61	0.00	-72.90	0.00	72.90	2,248.22	1,124.11	2,974.43	1,468.96	2.93	-0.34	0.061
93.00	-24.14	-1.59	0.00	-68.08	0.00	68.08	2,220.81	1,110.41	2,879.80	1,422.23	3.14	-0.35	0.059
96.00	-23.54	-1.57	0.00	-63.31	0.00	63.31	2,192.74	1,096.37	2,785.75	1,375.78	3.37	-0.36	0.057
99.00	-22.95	-1.56	0.00	-58.58	0.00	58.58	2,163.98	1,081.99	2,692.34	1,329.64	3.60	-0.38	0.055
102.00	-22.37	-1.54	0.00	-53.92	0.00	53.92	2,134.56	1,067.28	2,599.61	1,283.85	3.84	-0.39	0.052
105.00	-21.98	-1.52	0.00	-49.31	0.00	49.31	2,104.45	1,052.22	2,507.63	1,238.42	4.09	-0.40	0.050
107.00	-21.60	-1.51	0.00	-46.26	0.00	46.26	2,084.00	1,042.00	2,446.74	1,208.36	4.27	-0.41	0.049
108.00	-21.05	-1.48	0.00	-44.76	0.00	44.76	2,073.67	1,036.83	2,416.44	1,193.39	4.35	-0.42	0.048
111.00	-20.51	-1.46	0.00	-40.30	0.00	40.30	2,042.21	1,021.11	2,326.10	1,148.77	4.62	-0.43	0.045
114.00	-19.97	-1.44	0.00	-35.92	0.00	35.92	2,006.48	1,003.24	2,232.66	1,102.63	4.89	-0.44	0.043
117.00	-19.45	-1.41	0.00	-31.60	0.00	31.60	1,959.62	979.81	2,129.00	1,051.43	5.18	-0.45	0.040
120.00	-19.06	-1.39	0.00	-27.37	0.00	27.37	1,912.75	956.38	2,027.81	1,001.46	5.46	-0.46	0.037
122.12	-18.84	-1.38	0.00	-24.41	0.00	24.41	1,879.60	939.80	1,957.71	966.84	5.67	-0.47	0.035
123.00	-15.55	-1.19	0.00	-23.20	0.00	23.20	1,865.89	932.94	1,929.08	952.70	5.76	-0.47	0.033
125.89	-15.53	-1.19	0.00	-19.77	0.00	19.77	929.68	464.84	961.73	474.96	6.05	-0.48	0.058
126.00	-15.15	-1.17	0.00	-19.63	0.00	19.63	929.29	464.65	960.40	474.31	6.06	-0.48	0.058
129.00	-14.77	-1.14	0.00	-16.13	0.00	16.13	918.88	459.44	925.49	457.06	6.37	-0.50	0.051
132.00	-14.65	-1.14	0.00	-12.70	0.00	12.70	907.79	453.90	890.46	439.76	6.68	-0.51	0.045
133.00	-10.65	-0.86	0.00	-11.56	0.00	11.56	903.95	451.97	878.77	433.99	6.79	-0.51	0.038

135.00	-10.31	-0.84	0.00	-9.84	0.00	9.84	896.03	448.02	855.37	422.43	7.01	-0.52	0.035
138.00	-9.98	-0.82	0.00	-7.31	0.00	7.31	883.59	441.80	820.26	405.10	7.33	-0.52	0.029
141.00	-9.77	-0.80	0.00	-4.86	0.00	4.86	870.48	435.24	785.20	387.78	7.66	-0.53	0.024
143.00	-5.65	-0.48	0.00	-3.25	0.00	3.25	861.36	430.68	761.88	376.27	7.89	-0.53	0.015
144.00	-5.47	-0.47	0.00	-2.77	0.00	2.77	856.69	428.34	750.24	370.52	8.00	-0.53	0.014
146.00	-5.33	-0.46	0.00	-1.84	0.00	1.84	847.12	423.56	727.02	359.05	8.22	-0.54	0.011
146.00	-5.33	-0.46	0.00	-1.84	0.00	1.84	920.33	460.16	575.46	378.52	8.22	-0.54	0.011
147.00	-5.06	-0.43	0.00	-1.39	0.00	1.39	920.33	460.16	575.46	378.52	8.33	-0.54	0.009
149.00	-1.31	-0.12	0.00	-0.52	0.00	0.52	920.33	460.16	575.46	378.52	8.56	-0.54	0.003
150.00	-0.98	-0.09	0.00	-0.40	0.00	0.40	920.33	460.16	575.46	378.52	8.67	-0.54	0.002
153.00	-0.77	-0.07	0.00	-0.14	0.00	0.14	920.33	460.16	575.46	378.52	9.01	-0.54	0.001
155.00	0.00	-0.06	0.00	0.00	0.00	0.00	920.33	460.16	575.46	378.52	9.23	-0.54	0.000

Load Case (0.9 - 0.2Sds) * DL + E ELFM Seismic (Reduced DL) Equivalent Lateral Forces Method

Calculated Forces

Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	phi Pn (kips)	phi Vn (kips)	phi Tn (ft-kips)	phi Mn (ft-kips)	Total Deflect (in)	Rotation (deg)	Ratio
0.00	-37.18	-1.72	0.00	-224.02	0.00	224.02	4,665.07	2,332.54	9,536.02	4,709.48	0.00	0.00	0.056
3.00	-36.43	-1.72	0.00	-218.87	0.00	218.87	4,631.78	2,315.89	9,346.21	4,615.74	0.00	-0.01	0.055
6.00	-35.68	-1.73	0.00	-213.71	0.00	213.71	4,597.82	2,298.91	9,156.81	4,522.21	0.01	-0.02	0.055
9.00	-34.95	-1.73	0.00	-208.53	0.00	208.53	4,563.18	2,281.59	8,967.87	4,428.89	0.02	-0.03	0.055
12.00	-34.22	-1.74	0.00	-203.33	0.00	203.33	4,527.86	2,263.93	8,779.43	4,335.83	0.04	-0.04	0.054
15.00	-33.74	-1.74	0.00	-198.13	0.00	198.13	4,491.86	2,245.93	8,591.56	4,243.05	0.07	-0.04	0.054
17.00	-33.34	-1.74	0.00	-194.65	0.00	194.65	4,467.49	2,233.75	8,466.65	4,181.36	0.09	-0.05	0.054
18.00	-32.62	-1.74	0.00	-192.91	0.00	192.91	4,455.19	2,227.60	8,404.31	4,150.57	0.10	-0.05	0.054
21.00	-31.92	-1.75	0.00	-187.68	0.00	187.68	4,417.85	2,208.92	8,217.72	4,058.43	0.14	-0.06	0.053
24.00	-31.22	-1.75	0.00	-182.45	0.00	182.45	4,379.82	2,189.91	8,031.86	3,966.64	0.18	-0.07	0.053
27.00	-30.54	-1.75	0.00	-177.20	0.00	177.20	4,341.13	2,170.56	7,846.78	3,875.23	0.23	-0.08	0.053
30.00	-29.86	-1.75	0.00	-171.96	0.00	171.96	4,301.75	2,150.88	7,662.53	3,784.23	0.28	-0.09	0.052
33.00	-29.18	-1.75	0.00	-166.71	0.00	166.71	4,261.70	2,130.85	7,479.16	3,693.68	0.35	-0.10	0.052
36.00	-28.52	-1.75	0.00	-161.46	0.00	161.46	4,220.97	2,110.49	7,296.73	3,603.58	0.41	-0.11	0.052
39.00	-28.27	-1.75	0.00	-156.21	0.00	156.21	4,179.57	2,089.78	7,115.28	3,513.97	0.49	-0.12	0.051
40.10	-27.58	-1.75	0.00	-154.27	0.00	154.27	4,164.16	2,082.08	7,048.76	3,481.12	0.52	-0.13	0.051
42.00	-26.49	-1.74	0.00	-150.96	0.00	150.96	4,137.49	2,068.74	6,934.89	3,424.88	0.57	-0.13	0.050
45.00	-26.17	-1.74	0.00	-145.75	0.00	145.75	4,094.73	2,047.37	6,755.59	3,336.33	0.65	-0.14	0.050
45.90	-25.76	-1.73	0.00	-144.19	0.00	144.19	3,345.43	1,672.72	5,614.65	2,772.86	0.68	-0.15	0.060
48.00	-25.38	-1.73	0.00	-140.55	0.00	140.55	3,324.15	1,662.07	5,517.72	2,724.99	0.75	-0.15	0.059
50.00	-25.12	-1.73	0.00	-137.09	0.00	137.09	3,303.59	1,651.79	5,425.69	2,679.55	0.81	-0.16	0.059
51.00	-24.56	-1.72	0.00	-135.36	0.00	135.36	3,293.20	1,646.60	5,379.77	2,656.86	0.85	-0.17	0.058
54.00	-24.00	-1.72	0.00	-130.18	0.00	130.18	3,261.57	1,630.78	5,242.36	2,589.00	0.96	-0.18	0.058
57.00	-23.45	-1.71	0.00	-125.02	0.00	125.02	3,229.26	1,614.63	5,105.54	2,521.44	1.07	-0.19	0.057
60.00	-22.90	-1.71	0.00	-119.88	0.00	119.88	3,196.28	1,598.14	4,969.37	2,454.19	1.19	-0.20	0.056
63.00	-22.21	-1.70	0.00	-114.76	0.00	114.76	3,162.62	1,581.31	4,833.91	2,387.28	1.32	-0.21	0.055
66.00	-21.68	-1.69	0.00	-109.68	0.00	109.68	3,128.28	1,564.14	4,699.19	2,320.75	1.46	-0.23	0.054
69.00	-21.16	-1.68	0.00	-104.62	0.00	104.62	3,093.27	1,546.64	4,565.29	2,254.62	1.61	-0.24	0.053
72.00	-20.64	-1.66	0.00	-99.59	0.00	99.59	3,057.58	1,528.79	4,432.24	2,188.92	1.76	-0.25	0.052
75.00	-20.13	-1.65	0.00	-94.60	0.00	94.60	3,021.22	1,510.61	4,300.11	2,123.66	1.92	-0.26	0.051
78.00	-19.69	-1.64	0.00	-89.64	0.00	89.64	2,984.18	1,492.09	4,168.95	2,058.89	2.09	-0.27	0.050
80.60	-19.58	-1.64	0.00	-85.38	0.00	85.38	2,951.54	1,475.77	4,056.14	2,003.18	2.25	-0.29	0.049
81.00	-19.05	-1.62	0.00	-84.72	0.00	84.72	2,946.46	1,473.23	4,038.81	1,994.61	2.27	-0.29	0.049
83.00	-18.72	-1.61	0.00	-81.48	0.00	81.48	2,920.94	1,460.47	3,952.64	1,952.06	2.39	-0.30	0.048
84.00	-18.35	-1.60	0.00	-79.87	0.00	79.87	2,908.96	1,454.48	3,910.94	1,931.47	2.45	-0.30	0.048
85.41	-18.11	-1.59	0.00	-77.62	0.00	77.62	2,288.86	1,144.43	3,120.34	1,541.02	2.54	-0.31	0.058
87.00	-17.68	-1.57	0.00	-75.09	0.00	75.09	2,274.94	1,137.47	3,069.59	1,515.95	2.65	-0.31	0.057
90.00	-17.25	-1.56	0.00	-70.37	0.00	70.37	2,248.22	1,124.11	2,974.43	1,468.96	2.85	-0.33	0.056
93.00	-16.83	-1.54	0.00	-65.70	0.00	65.70	2,220.81	1,110.41	2,879.80	1,422.23	3.06	-0.34	0.054
96.00	-16.41	-1.52	0.00	-61.07	0.00	61.07	2,192.74	1,096.37	2,785.75	1,375.78	3.27	-0.35	0.052
99.00	-16.00	-1.50	0.00	-56.50	0.00	56.50	2,163.98	1,081.99	2,692.34	1,329.64	3.50	-0.37	0.050
102.00	-15.60	-1.48	0.00	-51.99	0.00	51.99	2,134.56	1,067.28	2,599.61	1,283.85	3.74	-0.38	0.048
105.00	-15.32	-1.47	0.00	-47.53	0.00	47.53	2,104.45	1,052.22	2,507.63	1,238.42	3.98	-0.39	0.046
107.00	-15.06	-1.46	0.00	-44.59	0.00	44.59	2,084.00	1,042.00	2,446.74	1,208.36	4.14	-0.40	0.044
108.00	-14.67	-1.43	0.00	-43.14	0.00	43.14	2,073.67	1,036.83	2,416.44	1,193.39	4.23	-0.41	0.043
111.00	-14.30	-1.41	0.00	-38.84	0.00	38.84	2,042.21	1,021.11	2,326.10	1,148.77	4.49	-0.42	0.041
114.00	-13.92	-1.39	0.00	-34.60	0.00	34.60	2,006.48	1,003.24	2,232.66	1,102.63	4.75	-0.43	0.038
117.00	-13.55	-1.36	0.00	-30.44	0.00	30.44	1,959.62	979.81	2,129.00	1,051.43	5.03	-0.44	0.036
120.00	-13.29	-1.34	0.00	-26.36	0.00	26.36	1,912.75	956.38	2,027.81	1,001.46	5.31	-0.45	0.033
122.12	-13.13	-1.33	0.00	-23.51	0.00	23.51	1,879.60	939.80	1,957.71	966.84	5.51	-0.46	0.031
123.00	-10.84	-1.15	0.00	-22.34	0.00	22.34	1,865.89	932.94	1,929.08	952.70	5.59	-0.46	0.029
125.89	-10.83	-1.15	0.00	-19.04	0.00	19.04	929.68	464.84	961.73	474.96	5.87	-0.47	0.052
126.00	-10.56	-1.12	0.00	-18.91	0.00	18.91	929.29	464.65	960.40	474.31	5.88	-0.47	0.051
129.00	-10.30	-1.10	0.00	-15.54	0.00	15.54	918.88	459.44	925.49	457.06	6.18	-0.48	0.045
132.00	-10.21	-1.09	0.00	-12.24	0.00	12.24	907.79	453.90	890.46	439.76	6.49	-0.49	0.039
133.00	-7.42	-0.83	0.00	-11.14	0.00	11.14	903.95	451.97	878.77	433.99	6.59	-0.49	0.034

135.00	-7.19	-0.81	0.00	-9.48	0.00	9.48	896.03	448.02	855.37	422.43	6.80	-0.50	0.030
138.00	-6.96	-0.79	0.00	-7.04	0.00	7.04	883.59	441.80	820.26	405.10	7.11	-0.51	0.025
141.00	-6.81	-0.77	0.00	-4.68	0.00	4.68	870.48	435.24	785.20	387.78	7.43	-0.51	0.020
143.00	-3.94	-0.46	0.00	-3.14	0.00	3.14	861.36	430.68	761.88	376.27	7.65	-0.52	0.013
144.00	-3.81	-0.45	0.00	-2.67	0.00	2.67	856.69	428.34	750.24	370.52	7.76	-0.52	0.012
146.00	-3.72	-0.44	0.00	-1.77	0.00	1.77	847.12	423.56	727.02	359.05	7.98	-0.52	0.009
146.00	-3.72	-0.44	0.00	-1.77	0.00	1.77	920.33	460.16	575.46	378.52	7.98	-0.52	0.009
147.00	-3.52	-0.42	0.00	-1.34	0.00	1.34	920.33	460.16	575.46	378.52	8.08	-0.52	0.007
149.00	-0.91	-0.11	0.00	-0.50	0.00	0.50	920.33	460.16	575.46	378.52	8.30	-0.52	0.002
150.00	-0.69	-0.09	0.00	-0.39	0.00	0.39	920.33	460.16	575.46	378.52	8.41	-0.52	0.002
153.00	-0.53	-0.07	0.00	-0.13	0.00	0.13	920.33	460.16	575.46	378.52	8.74	-0.52	0.001
155.00	0.00	-0.06	0.00	0.00	0.00	0.00	920.33	460.16	575.46	378.52	8.96	-0.52	0.000

Equivalent Modal Forces Analysis

(Based on ASCE7-10 Chapters 11, 12 & 15 and ANSI/TIA-G, section 2.7)

Spectral Response Acceleration for Short Period (S_s):	0.17
Spectral Response Acceleration at 1.0 Second Period (S_1):	0.06
Importance Factor (I_E):	1.00
Site Coefficient F_a:	1.60
Site Coefficient F_v	2.40
Response Modification Coefficient (R):	1.50
Design Spectral Response Acceleration at Short Period (S_{ds}):	0.19
Desing Spectral Response Acceleration at 1.0 Second Period (S_{d1}):	0.10
Period Based on Rayleigh Method (sec):	2.93
Redundancy Factor (p):	1.30

Load Case (1.2 + 0.2Sds) * DL + E EMAM Seismic Equivalent Modal Analysis Method

Segment	Height Above Base (ft)	Weight (lb)	a	b	c	Saz	Horizontal Force (lb)	Vertical Force (lb)
66	154.00	176	1.866	1.854	1.094	0.337	51	217
65	151.50	263	1.806	1.564	0.987	0.300	69	326
64	149.50	88	1.758	1.356	0.907	0.272	21	109
63	148.00	224	1.723	1.212	0.851	0.252	49	277
62	146.50	112	1.688	1.079	0.797	0.233	23	138
61	145.00	145	1.654	0.955	0.746	0.214	27	179
60	143.50	73	1.620	0.842	0.697	0.196	12	90
59	142.00	175	1.586	0.737	0.652	0.178	27	217
58	139.50	266	1.531	0.580	0.580	0.151	35	329
57	136.50	270	1.466	0.420	0.503	0.120	28	334
56	134.00	182	1.413	0.308	0.445	0.096	15	225
55	132.50	101	1.381	0.249	0.413	0.083	7	125
54	130.50	305	1.340	0.179	0.372	0.066	17	377
53	127.50	308	1.279	0.092	0.318	0.043	11	382
52	125.94	12	1.248	0.055	0.292	0.032	0	15
51	124.44	546	1.218	0.023	0.269	0.022	10	676
50	122.56	175	1.182	-0.012	0.241	0.010	2	216
49	121.06	312	1.153	-0.035	0.221	0.002	0	386
48	118.50	426	1.105	-0.067	0.190	-0.012	-4	527
47	115.50	433	1.049	-0.094	0.157	-0.025	-9	536
46	112.50	439	0.996	-0.111	0.129	-0.036	-14	544
45	109.50	446	0.943	-0.120	0.105	-0.044	-17	552
44	107.50	150	0.909	-0.122	0.091	-0.048	-6	186
43	106.00	310	0.884	-0.121	0.081	-0.050	-13	383
42	103.50	470	0.843	-0.118	0.067	-0.053	-21	582
41	100.50	477	0.795	-0.111	0.052	-0.053	-22	590
40	97.50	483	0.748	-0.100	0.040	-0.051	-21	598
39	94.50	490	0.703	-0.088	0.030	-0.047	-20	606
38	91.50	496	0.659	-0.074	0.023	-0.040	-17	614
37	88.50	503	0.616	-0.059	0.016	-0.031	-14	622
36	86.20	270	0.585	-0.047	0.013	-0.024	-6	334
35	84.70	427	0.564	-0.040	0.011	-0.018	-7	529
34	83.50	306	0.548	-0.034	0.010	-0.014	-4	378
33	82.00	617	0.529	-0.027	0.008	-0.008	-4	763

32	80.80	124	0.514	-0.021	0.008	-0.003	0	154
31	79.30	507	0.495	-0.014	0.007	0.002	1	627
30	76.50	592	0.460	-0.002	0.006	0.013	7	733
29	73.50	600	0.425	0.010	0.006	0.023	12	742
28	70.50	608	0.391	0.021	0.007	0.032	17	752
27	67.50	616	0.358	0.030	0.008	0.039	21	762
26	64.50	623	0.327	0.039	0.010	0.044	24	771
25	61.50	632	0.298	0.046	0.012	0.048	27	782
24	58.50	640	0.269	0.052	0.015	0.051	28	792
23	55.50	648	0.242	0.057	0.018	0.053	30	801
22	52.50	656	0.217	0.061	0.021	0.054	31	811
21	50.50	220	0.201	0.063	0.023	0.054	10	272
20	49.00	443	0.189	0.064	0.025	0.054	21	549
19	46.95	470	0.173	0.066	0.027	0.054	22	581
18	45.45	374	0.162	0.067	0.028	0.054	18	463
17	43.50	1,260	0.149	0.068	0.030	0.054	59	1,559
16	41.05	805	0.133	0.069	0.033	0.053	37	996
15	39.55	281	0.123	0.070	0.034	0.053	13	348
14	37.50	770	0.111	0.070	0.036	0.052	35	953
13	34.50	780	0.094	0.071	0.038	0.052	35	965
12	31.50	789	0.078	0.072	0.040	0.051	35	976
11	28.50	798	0.064	0.072	0.041	0.050	35	987
10	25.50	807	0.051	0.071	0.042	0.049	35	998
9	22.50	816	0.040	0.070	0.042	0.049	34	1,010
8	19.50	825	0.030	0.068	0.041	0.047	34	1,021
7	17.50	277	0.024	0.066	0.039	0.046	11	343
6	16.00	557	0.020	0.064	0.038	0.045	22	689
5	13.50	843	0.014	0.060	0.035	0.043	31	1,043
4	10.50	852	0.009	0.053	0.030	0.039	29	1,055
3	7.50	861	0.004	0.043	0.024	0.033	25	1,066
2	4.50	871	0.002	0.029	0.016	0.024	18	1,077
1	1.50	880	0.000	0.011	0.006	0.010	8	1,088
Ericsson KRY 112 71/	155.00	79	1.890	1.980	1.140	0.352	24	98
EMS RR90-17-02DP	155.00	41	1.890	1.980	1.140	0.352	12	50
Canister	155.00	500	1.890	1.980	1.140	0.352	153	619
Andrew ABT-DMDF-	149.00	1	1.747	1.306	0.888	0.266	0	1
Powerwave Allgon 702	149.00	7	1.747	1.306	0.888	0.266	2	8
Kathrein Scala 782-1	149.00	38	1.747	1.306	0.888	0.266	9	48
CCI DTMABP7819VG12A	149.00	115	1.747	1.306	0.888	0.266	27	143
Raycap DC6-48-60-18-	149.00	32	1.747	1.306	0.888	0.266	7	39
7' Omni	149.00	25	1.747	1.306	0.888	0.266	6	31
Ericsson RRUS 11 (Ba	149.00	150	1.747	1.306	0.888	0.266	35	186
Ericsson RRUS-12 800	149.00	180	1.747	1.306	0.888	0.266	41	223
Powerwave Allgon 777	149.00	105	1.747	1.306	0.888	0.266	24	130
KMW AM-X-CD-16-65-00	149.00	291	1.747	1.306	0.888	0.266	67	360
Flat Platform w/ Han	149.00	2,000	1.747	1.306	0.888	0.266	460	2,475
Nokia B5 RRH4x40-850	143.00	146	1.609	0.806	0.682	0.190	24	180
Alcatel-Lucent RRH2x	143.00	170	1.609	0.806	0.682	0.190	28	210
Alcatel-Lucent RRH A	143.00	147	1.609	0.806	0.682	0.190	24	182
Alcatel-Lucent RRH2x	143.00	180	1.609	0.806	0.682	0.190	30	223
Swedcom ALP 9212-N	143.00	160	1.609	0.806	0.682	0.190	26	198
RFS DB-T1-6Z-8AB-0Z	143.00	44	1.609	0.806	0.682	0.190	7	54
RFS DB-T1-6Z-8AB-0Z	143.00	44	1.609	0.806	0.682	0.190	7	54
Commscope JAHH-65B-	143.00	364	1.609	0.806	0.682	0.190	60	450
Flat Platform w/ Han	143.00	2,000	1.609	0.806	0.682	0.190	329	2,475
Alcatel-Lucent 800 M	133.00	384	1.392	0.268	0.423	0.087	29	475
Alcatel-Lucent 1900	133.00	180	1.392	0.268	0.423	0.087	14	223
Decibel 980H65T2E-M	133.00	25	1.392	0.268	0.423	0.087	2	32
Alcatel-Lucent TD-RR	133.00	210	1.392	0.268	0.423	0.087	16	260
KMW ETCR-654L12H6	133.00	255	1.392	0.268	0.423	0.087	19	315
Flat Platform w/ Han	133.00	2,000	1.392	0.268	0.423	0.087	151	2,475
Decibel DB844H90E-A	123.00	120	1.190	-0.004	0.248	0.013	1	148
Flat Platform w/ Han	123.00	2,000	1.190	-0.004	0.248	0.013	22	2,475
Commscope LNX-	107.00	151	0.901	-0.122	0.088	-0.049	-6	187

Kathrein Smart Bias	105.00	10	0.867	-0.121	0.075	-0.051	0	12
GPS	83.00	10	0.542	-0.032	0.009	-0.012	0	12
Stand-Off	83.00	75	0.542	-0.032	0.009	-0.012	-1	93
GPS	63.00	20	0.312	0.042	0.011	0.047	1	25
Stand-Off	63.00	150	0.312	0.042	0.011	0.047	6	186
2" x 4" GPS	50.00	5	0.197	0.063	0.024	0.054	0	6
Stand-Off	50.00	75	0.197	0.063	0.024	0.054	4	93
4' Std. Dish	17.00	188	0.023	0.065	0.039	0.046	7	233
		43,975	99.034	40.822	34.842	9.735	2,634	54,412

Load Case (0.9 - 0.2Sds) * DL + E EMAM Seismic (Reduced DL) Equivalent Modal Analysis Method

Segment	Height Above Base (ft)	Weight (lb)	a	b	c	Saz	Horizontal Force (lb)	Vertical Force (lb)
66	154.00	176	1.866	1.854	1.094	0.337	51	151
65	151.50	263	1.806	1.564	0.987	0.300	69	227
64	149.50	88	1.758	1.356	0.907	0.272	21	76
63	148.00	224	1.723	1.212	0.851	0.252	49	193
62	146.50	112	1.688	1.079	0.797	0.233	23	97
61	145.00	145	1.654	0.955	0.746	0.214	27	125
60	143.50	73	1.620	0.842	0.697	0.196	12	63
59	142.00	175	1.586	0.737	0.652	0.178	27	151
58	139.50	266	1.531	0.580	0.580	0.151	35	230
57	136.50	270	1.466	0.420	0.503	0.120	28	233
56	134.00	182	1.413	0.308	0.445	0.096	15	157
55	132.50	101	1.381	0.249	0.413	0.083	7	87
54	130.50	305	1.340	0.179	0.372	0.066	17	263
53	127.50	308	1.279	0.092	0.318	0.043	11	266
52	125.94	12	1.248	0.055	0.292	0.032	0	10
51	124.44	546	1.218	0.023	0.269	0.022	10	471
50	122.56	175	1.182	-0.012	0.241	0.010	2	151
49	121.06	312	1.153	-0.035	0.221	0.002	0	269
48	118.50	426	1.105	-0.067	0.190	-0.012	-4	368
47	115.50	433	1.049	-0.094	0.157	-0.025	-9	373
46	112.50	439	0.996	-0.111	0.129	-0.036	-14	379
45	109.50	446	0.943	-0.120	0.105	-0.044	-17	385
44	107.50	150	0.909	-0.122	0.091	-0.048	-6	129
43	106.00	310	0.884	-0.121	0.081	-0.050	-13	267
42	103.50	470	0.843	-0.118	0.067	-0.053	-21	406
41	100.50	477	0.795	-0.111	0.052	-0.053	-22	411
40	97.50	483	0.748	-0.100	0.040	-0.051	-21	417
39	94.50	490	0.703	-0.088	0.030	-0.047	-20	422
38	91.50	496	0.659	-0.074	0.023	-0.040	-17	428
37	88.50	503	0.616	-0.059	0.016	-0.031	-14	434
36	86.20	270	0.585	-0.047	0.013	-0.024	-6	233
35	84.70	427	0.564	-0.040	0.011	-0.018	-7	369
34	83.50	306	0.548	-0.034	0.010	-0.014	-4	264
33	82.00	617	0.529	-0.027	0.008	-0.008	-4	532
32	80.80	124	0.514	-0.021	0.008	-0.003	0	107
31	79.30	507	0.495	-0.014	0.007	0.002	1	437
30	76.50	592	0.460	-0.002	0.006	0.013	7	511
29	73.50	600	0.425	0.010	0.006	0.023	12	518
28	70.50	608	0.391	0.021	0.007	0.032	17	524
27	67.50	616	0.358	0.030	0.008	0.039	21	531
26	64.50	623	0.327	0.039	0.010	0.044	24	538
25	61.50	632	0.298	0.046	0.012	0.048	27	545
24	58.50	640	0.269	0.052	0.015	0.051	28	552
23	55.50	648	0.242	0.057	0.018	0.053	30	559
22	52.50	656	0.217	0.061	0.021	0.054	31	565

21	50.50	220	0.201	0.063	0.023	0.054	10	190
20	49.00	443	0.189	0.064	0.025	0.054	21	382
19	46.95	470	0.173	0.066	0.027	0.054	22	405
18	45.45	374	0.162	0.067	0.028	0.054	18	323
17	43.50	1,260	0.149	0.068	0.030	0.054	59	1,087
16	41.05	805	0.133	0.069	0.033	0.053	37	695
15	39.55	281	0.123	0.070	0.034	0.053	13	243
14	37.50	770	0.111	0.070	0.036	0.052	35	665
13	34.50	780	0.094	0.071	0.038	0.052	35	673
12	31.50	789	0.078	0.072	0.040	0.051	35	680
11	28.50	798	0.064	0.072	0.041	0.050	35	688
10	25.50	807	0.051	0.071	0.042	0.049	35	696
9	22.50	816	0.040	0.070	0.042	0.049	34	704
8	19.50	825	0.030	0.068	0.041	0.047	34	712
7	17.50	277	0.024	0.066	0.039	0.046	11	239
6	16.00	557	0.020	0.064	0.038	0.045	22	481
5	13.50	843	0.014	0.060	0.035	0.043	31	727
4	10.50	852	0.009	0.053	0.030	0.039	29	735
3	7.50	861	0.004	0.043	0.024	0.033	25	743
2	4.50	871	0.002	0.029	0.016	0.024	18	751
1	1.50	880	0.000	0.011	0.006	0.010	8	759
Ericsson KRY 112 71/	155.00	79	1.890	1.980	1.140	0.352	24	68
EMS RR90-17-02DP	155.00	41	1.890	1.980	1.140	0.352	12	35
Canister	155.00	500	1.890	1.980	1.140	0.352	153	431
Andrew ABT-DMDF-	149.00	1	1.747	1.306	0.888	0.266	0	1
Powerwave Allgon 702	149.00	7	1.747	1.306	0.888	0.266	2	6
Kathrein Scala 782-1	149.00	38	1.747	1.306	0.888	0.266	9	33
CCI DTMABP7819VG12A	149.00	115	1.747	1.306	0.888	0.266	27	99
Raycap DC6-48-60-18-	149.00	32	1.747	1.306	0.888	0.266	7	27
7' Omni	149.00	25	1.747	1.306	0.888	0.266	6	22
Ericsson RRUS 11 (Ba	149.00	150	1.747	1.306	0.888	0.266	35	129
Ericsson RRUS-12 800	149.00	180	1.747	1.306	0.888	0.266	41	155
Powerwave Allgon 777	149.00	105	1.747	1.306	0.888	0.266	24	91
KMW AM-X-CD-16-65-00	149.00	291	1.747	1.306	0.888	0.266	67	251
Flat Platform w/ Han	149.00	2,000	1.747	1.306	0.888	0.266	460	1,725
Nokia B5 RRH4x40-850	143.00	146	1.609	0.806	0.682	0.190	24	126
Alcatel-Lucent RRH2x	143.00	170	1.609	0.806	0.682	0.190	28	147
Alcatel-Lucent RRH A	143.00	147	1.609	0.806	0.682	0.190	24	127
Alcatel-Lucent RRH2x	143.00	180	1.609	0.806	0.682	0.190	30	155
Swedcom ALP 9212-N	143.00	160	1.609	0.806	0.682	0.190	26	138
RFS DB-T1-6Z-8AB-0Z	143.00	44	1.609	0.806	0.682	0.190	7	38
RFS DB-T1-6Z-8AB-0Z	143.00	44	1.609	0.806	0.682	0.190	7	38
Commscope JAHH-65B-	143.00	364	1.609	0.806	0.682	0.190	60	314
Flat Platform w/ Han	143.00	2,000	1.609	0.806	0.682	0.190	329	1,725
Alcatel-Lucent 800 M	133.00	384	1.392	0.268	0.423	0.087	29	331
Alcatel-Lucent 1900	133.00	180	1.392	0.268	0.423	0.087	14	155
Decibel 980H65T2E-M	133.00	25	1.392	0.268	0.423	0.087	2	22
Alcatel-Lucent TD-RR	133.00	210	1.392	0.268	0.423	0.087	16	181
KMW ETCR-654L12H6	133.00	255	1.392	0.268	0.423	0.087	19	220
Flat Platform w/ Han	133.00	2,000	1.392	0.268	0.423	0.087	151	1,725
Decibel DB844H90E-A	123.00	120	1.190	-0.004	0.248	0.013	1	104
Flat Platform w/ Han	123.00	2,000	1.190	-0.004	0.248	0.013	22	1,725
Commscope LNX-	107.00	151	0.901	-0.122	0.088	-0.049	-6	130
Kathrein Smart Bias	105.00	10	0.867	-0.121	0.075	-0.051	0	9
GPS	83.00	10	0.542	-0.032	0.009	-0.012	0	9
Stand-Off	83.00	75	0.542	-0.032	0.009	-0.012	-1	65
GPS	63.00	20	0.312	0.042	0.011	0.047	1	17
Stand-Off	63.00	150	0.312	0.042	0.011	0.047	6	129
2" x 4" GPS	50.00	5	0.197	0.063	0.024	0.054	0	4
Stand-Off	50.00	75	0.197	0.063	0.024	0.054	4	65
4' Std. Dish	17.00	188	0.023	0.065	0.039	0.046	7	162
		43,975	99.034	40.822	34.842	9.735	2,634	37,936

Load Case (1.2 + 0.2Sds) * DL + E EMAM Seismic Equivalent Modal Analysis Method

Calculated Forces

Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	phi Pn (kips)	phi Vn (kips)	phi Tn (ft-kips)	phi Mn (ft-kips)	Total Deflect (in)	Rotation (deg)	Ratio
0.00	-53.32	-2.63	0.00	-329.82	0.00	329.82	4,665.07	2,332.54	9,536.02	4,709.48	0.00	0.00	0.081
3.00	-52.25	-2.62	0.00	-321.93	0.00	321.93	4,631.78	2,315.89	9,346.21	4,615.74	0.00	-0.01	0.081
6.00	-51.18	-2.61	0.00	-314.06	0.00	314.06	4,597.82	2,298.91	9,156.81	4,522.21	0.02	-0.03	0.081
9.00	-50.12	-2.59	0.00	-306.23	0.00	306.23	4,563.18	2,281.59	8,967.87	4,428.89	0.04	-0.04	0.080
12.00	-49.08	-2.57	0.00	-298.45	0.00	298.45	4,527.86	2,263.93	8,779.43	4,335.83	0.07	-0.05	0.080
15.00	-48.39	-2.56	0.00	-290.74	0.00	290.74	4,491.86	2,245.93	8,591.56	4,243.05	0.10	-0.07	0.079
17.00	-47.81	-2.54	0.00	-285.62	0.00	285.62	4,467.49	2,233.75	8,466.65	4,181.36	0.13	-0.07	0.079
18.00	-46.79	-2.52	0.00	-283.08	0.00	283.08	4,455.19	2,227.60	8,404.31	4,150.57	0.15	-0.08	0.079
21.00	-45.78	-2.49	0.00	-275.53	0.00	275.53	4,417.85	2,208.92	8,217.72	4,058.43	0.20	-0.09	0.078
24.00	-44.78	-2.47	0.00	-268.05	0.00	268.05	4,379.82	2,189.91	8,031.86	3,966.64	0.26	-0.11	0.078
27.00	-43.80	-2.44	0.00	-260.65	0.00	260.65	4,341.13	2,170.56	7,846.78	3,875.23	0.34	-0.12	0.077
30.00	-42.82	-2.42	0.00	-253.32	0.00	253.32	4,301.75	2,150.88	7,662.53	3,784.23	0.42	-0.14	0.077
33.00	-41.86	-2.39	0.00	-246.08	0.00	246.08	4,261.70	2,130.85	7,479.16	3,693.68	0.51	-0.15	0.076
36.00	-40.90	-2.36	0.00	-238.91	0.00	238.91	4,220.97	2,110.49	7,296.73	3,603.58	0.61	-0.17	0.076
39.00	-40.55	-2.36	0.00	-231.83	0.00	231.83	4,179.57	2,089.78	7,115.28	3,513.97	0.71	-0.18	0.076
40.10	-39.56	-2.32	0.00	-229.23	0.00	229.23	4,164.16	2,082.08	7,048.76	3,481.12	0.76	-0.19	0.075
42.00	-38.00	-2.26	0.00	-224.83	0.00	224.83	4,137.49	2,068.74	6,934.89	3,424.88	0.83	-0.20	0.075
45.00	-37.53	-2.25	0.00	-218.04	0.00	218.04	4,094.73	2,047.37	6,755.59	3,336.33	0.96	-0.21	0.075
45.90	-36.95	-2.23	0.00	-216.01	0.00	216.01	3,345.43	1,672.72	5,614.65	2,772.86	1.00	-0.22	0.089
48.00	-36.40	-2.22	0.00	-211.32	0.00	211.32	3,324.15	1,662.07	5,517.72	2,724.99	1.10	-0.23	0.089
50.00	-36.03	-2.21	0.00	-206.89	0.00	206.89	3,303.59	1,651.79	5,425.69	2,679.55	1.20	-0.24	0.088
51.00	-35.22	-2.18	0.00	-204.68	0.00	204.68	3,293.20	1,646.60	5,379.77	2,656.86	1.25	-0.25	0.088
54.00	-34.42	-2.16	0.00	-198.14	0.00	198.14	3,261.57	1,630.78	5,242.36	2,589.00	1.41	-0.26	0.087
57.00	-33.63	-2.14	0.00	-191.66	0.00	191.66	3,229.26	1,614.63	5,105.54	2,521.44	1.58	-0.28	0.086
60.00	-32.84	-2.12	0.00	-185.25	0.00	185.25	3,196.28	1,598.14	4,969.37	2,454.19	1.76	-0.30	0.086
63.00	-31.86	-2.09	0.00	-178.90	0.00	178.90	3,162.62	1,581.31	4,833.91	2,387.28	1.96	-0.32	0.085
66.00	-31.10	-2.08	0.00	-172.63	0.00	172.63	3,128.28	1,564.14	4,699.19	2,320.75	2.16	-0.34	0.084
69.00	-30.35	-2.07	0.00	-166.40	0.00	166.40	3,093.27	1,546.64	4,565.29	2,254.62	2.38	-0.36	0.084
72.00	-29.60	-2.06	0.00	-160.20	0.00	160.20	3,057.58	1,528.79	4,432.24	2,188.92	2.61	-0.38	0.083
75.00	-28.87	-2.06	0.00	-154.03	0.00	154.03	3,021.22	1,510.61	4,300.11	2,123.66	2.85	-0.40	0.082
78.00	-28.24	-2.06	0.00	-147.85	0.00	147.85	2,984.18	1,492.09	4,168.95	2,058.89	3.11	-0.42	0.081
80.60	-28.09	-2.07	0.00	-142.49	0.00	142.49	2,951.54	1,475.77	4,056.14	2,003.18	3.34	-0.43	0.081
81.00	-27.32	-2.07	0.00	-141.67	0.00	141.67	2,946.46	1,473.23	4,038.81	1,994.61	3.38	-0.44	0.080
83.00	-26.84	-2.07	0.00	-137.53	0.00	137.53	2,920.94	1,460.47	3,952.64	1,952.06	3.56	-0.45	0.080
84.00	-26.31	-2.08	0.00	-135.45	0.00	135.45	2,908.96	1,454.48	3,910.94	1,931.47	3.66	-0.46	0.079
85.41	-25.98	-2.09	0.00	-132.53	0.00	132.53	2,288.86	1,144.43	3,120.34	1,541.02	3.80	-0.47	0.097
87.00	-25.35	-2.10	0.00	-129.20	0.00	129.20	2,274.94	1,137.47	3,069.59	1,515.95	3.95	-0.48	0.096
90.00	-24.74	-2.13	0.00	-122.89	0.00	122.89	2,248.22	1,124.11	2,974.43	1,468.96	4.26	-0.50	0.095
93.00	-24.13	-2.15	0.00	-116.51	0.00	116.51	2,220.81	1,110.41	2,879.80	1,422.23	4.59	-0.53	0.093
96.00	-23.53	-2.18	0.00	-110.05	0.00	110.05	2,192.74	1,096.37	2,785.75	1,375.78	4.93	-0.55	0.091
99.00	-22.94	-2.20	0.00	-103.52	0.00	103.52	2,163.98	1,081.99	2,692.34	1,329.64	5.28	-0.58	0.088
102.00	-22.36	-2.23	0.00	-96.91	0.00	96.91	2,134.56	1,067.28	2,599.61	1,283.85	5.65	-0.60	0.086
105.00	-21.96	-2.25	0.00	-90.23	0.00	90.23	2,104.45	1,052.22	2,507.63	1,238.42	6.04	-0.62	0.083
107.00	-21.59	-2.26	0.00	-85.73	0.00	85.73	2,084.00	1,042.00	2,446.74	1,208.36	6.30	-0.64	0.081
108.00	-21.04	-2.28	0.00	-83.48	0.00	83.48	2,073.67	1,036.83	2,416.44	1,193.39	6.43	-0.65	0.080
111.00	-20.49	-2.29	0.00	-76.65	0.00	76.65	2,042.21	1,021.11	2,326.10	1,148.77	6.85	-0.67	0.077
114.00	-19.96	-2.30	0.00	-69.78	0.00	69.78	2,006.48	1,003.24	2,232.66	1,102.63	7.28	-0.69	0.073
117.00	-19.43	-2.31	0.00	-62.87	0.00	62.87	1,959.62	979.81	2,129.00	1,051.43	7.72	-0.72	0.070
120.00	-19.04	-2.31	0.00	-55.95	0.00	55.95	1,912.75	956.38	2,027.81	1,001.46	8.18	-0.74	0.066
122.12	-18.82	-2.31	0.00	-51.06	0.00	51.06	1,879.60	939.80	1,957.71	966.84	8.51	-0.75	0.063
123.00	-15.53	-2.23	0.00	-49.03	0.00	49.03	1,865.89	932.94	1,929.08	952.70	8.65	-0.76	0.060
125.89	-15.51	-2.23	0.00	-42.59	0.00	42.59	929.68	464.84	961.73	474.96	9.12	-0.78	0.106
126.00	-15.13	-2.22	0.00	-42.33	0.00	42.33	929.29	464.65	960.40	474.31	9.13	-0.78	0.106
129.00	-14.75	-2.21	0.00	-35.67	0.00	35.67	918.88	459.44	925.49	457.06	9.63	-0.81	0.094
132.00	-14.63	-2.20	0.00	-29.05	0.00	29.05	907.79	453.90	890.46	439.76	10.15	-0.83	0.082
133.00	-10.63	-1.90	0.00	-26.85	0.00	26.85	903.95	451.97	878.77	433.99	10.32	-0.84	0.074

135.00	-10.29	-1.87	0.00	-23.05	0.00	23.05	896.03	448.02	855.37	422.43	10.68	-0.85	0.066
138.00	-9.96	-1.83	0.00	-17.44	0.00	17.44	883.59	441.80	820.26	405.10	11.22	-0.87	0.054
141.00	-9.75	-1.80	0.00	-11.94	0.00	11.94	870.48	435.24	785.20	387.78	11.77	-0.88	0.042
143.00	-5.64	-1.19	0.00	-8.33	0.00	8.33	861.36	430.68	761.88	376.27	12.14	-0.89	0.029
144.00	-5.46	-1.16	0.00	-7.14	0.00	7.14	856.69	428.34	750.24	370.52	12.33	-0.89	0.026
146.00	-5.32	-1.14	0.00	-4.81	0.00	4.81	847.12	423.56	727.02	359.05	12.70	-0.90	0.020
146.00	-5.32	-1.14	0.00	-4.81	0.00	4.81	920.33	460.16	575.46	378.52	12.70	-0.90	0.018
147.00	-5.04	-1.09	0.00	-3.67	0.00	3.67	920.33	460.16	575.46	378.52	12.89	-0.90	0.015
149.00	-1.30	-0.33	0.00	-1.50	0.00	1.50	920.33	460.16	575.46	378.52	13.27	-0.90	0.005
150.00	-0.98	-0.26	0.00	-1.17	0.00	1.17	920.33	460.16	575.46	378.52	13.46	-0.90	0.004
153.00	-0.76	-0.20	0.00	-0.40	0.00	0.40	920.33	460.16	575.46	378.52	14.03	-0.90	0.002
155.00	0.00	-0.19	0.00	0.00	0.00	0.00	920.33	460.16	575.46	378.52	14.41	-0.90	0.000

Load Case (0.9 - 0.2Sds) * DL + E EMAM Seismic (Reduced DL) Equivalent Modal Analysis Method

Calculated Forces

Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	phi Pn (kips)	phi Vn (kips)	phi Tn (ft-kips)	phi Mn (ft-kips)	Total Deflect (in)	Rotation (deg)	Ratio
0.00	-37.18	-2.63	0.00	-322.11	0.00	322.11	4,665.07	2,332.54	9,536.02	4,709.48	0.00	0.00	0.076
3.00	-36.43	-2.62	0.00	-314.23	0.00	314.23	4,631.78	2,315.89	9,346.21	4,615.74	0.00	-0.01	0.076
6.00	-35.68	-2.60	0.00	-306.37	0.00	306.37	4,597.82	2,298.91	9,156.81	4,522.21	0.02	-0.02	0.076
9.00	-34.95	-2.58	0.00	-298.57	0.00	298.57	4,563.18	2,281.59	8,967.87	4,428.89	0.04	-0.04	0.075
12.00	-34.22	-2.56	0.00	-290.83	0.00	290.83	4,527.86	2,263.93	8,779.43	4,335.83	0.06	-0.05	0.075
15.00	-33.74	-2.54	0.00	-283.17	0.00	283.17	4,491.86	2,245.93	8,591.56	4,243.05	0.10	-0.06	0.074
17.00	-33.34	-2.52	0.00	-278.09	0.00	278.09	4,467.49	2,233.75	8,466.65	4,181.36	0.13	-0.07	0.074
18.00	-32.62	-2.49	0.00	-275.56	0.00	275.56	4,455.19	2,227.60	8,404.31	4,150.57	0.14	-0.08	0.074
21.00	-31.92	-2.47	0.00	-268.08	0.00	268.08	4,417.85	2,208.92	8,217.72	4,058.43	0.20	-0.09	0.073
24.00	-31.22	-2.44	0.00	-260.68	0.00	260.68	4,379.82	2,189.91	8,031.86	3,966.64	0.26	-0.10	0.073
27.00	-30.53	-2.41	0.00	-253.36	0.00	253.36	4,341.13	2,170.56	7,846.78	3,875.23	0.33	-0.12	0.072
30.00	-29.85	-2.38	0.00	-246.13	0.00	246.13	4,301.75	2,150.88	7,662.53	3,784.23	0.41	-0.13	0.072
33.00	-29.18	-2.35	0.00	-238.99	0.00	238.99	4,261.70	2,130.85	7,479.16	3,693.68	0.49	-0.15	0.072
36.00	-28.51	-2.32	0.00	-231.93	0.00	231.93	4,220.97	2,110.49	7,296.73	3,603.58	0.59	-0.16	0.071
39.00	-28.27	-2.31	0.00	-224.97	0.00	224.97	4,179.57	2,089.78	7,115.28	3,513.97	0.70	-0.18	0.071
40.10	-27.58	-2.28	0.00	-222.41	0.00	222.41	4,164.16	2,082.08	7,048.76	3,481.12	0.74	-0.18	0.071
42.00	-26.49	-2.22	0.00	-218.10	0.00	218.10	4,137.49	2,068.74	6,934.89	3,424.88	0.81	-0.19	0.070
45.00	-26.17	-2.21	0.00	-211.43	0.00	211.43	4,094.73	2,047.37	6,755.59	3,336.33	0.94	-0.21	0.070
45.90	-25.76	-2.19	0.00	-209.45	0.00	209.45	3,345.43	1,672.72	5,614.65	2,772.86	0.98	-0.21	0.083
48.00	-25.38	-2.17	0.00	-204.85	0.00	204.85	3,324.15	1,662.07	5,517.72	2,724.99	1.07	-0.22	0.083
50.00	-25.12	-2.16	0.00	-200.51	0.00	200.51	3,303.59	1,651.79	5,425.69	2,679.55	1.17	-0.23	0.082
51.00	-24.55	-2.13	0.00	-198.35	0.00	198.35	3,293.20	1,646.60	5,379.77	2,656.86	1.21	-0.24	0.082
54.00	-23.99	-2.11	0.00	-191.96	0.00	191.96	3,261.57	1,630.78	5,242.36	2,589.00	1.37	-0.26	0.082
57.00	-23.44	-2.08	0.00	-185.65	0.00	185.65	3,229.26	1,614.63	5,105.54	2,521.44	1.54	-0.27	0.081
60.00	-22.90	-2.06	0.00	-179.40	0.00	179.40	3,196.28	1,598.14	4,969.37	2,454.19	1.71	-0.29	0.080
63.00	-22.21	-2.03	0.00	-173.22	0.00	173.22	3,162.62	1,581.31	4,833.91	2,387.28	1.90	-0.31	0.080
66.00	-21.68	-2.02	0.00	-167.13	0.00	167.13	3,128.28	1,564.14	4,699.19	2,320.75	2.10	-0.33	0.079
69.00	-21.15	-2.00	0.00	-161.08	0.00	161.08	3,093.27	1,546.64	4,565.29	2,254.62	2.32	-0.35	0.078
72.00	-20.64	-1.99	0.00	-155.07	0.00	155.07	3,057.58	1,528.79	4,432.24	2,188.92	2.54	-0.37	0.078
75.00	-20.12	-1.99	0.00	-149.08	0.00	149.08	3,021.22	1,510.61	4,300.11	2,123.66	2.77	-0.38	0.077
78.00	-19.69	-1.99	0.00	-143.11	0.00	143.11	2,984.18	1,492.09	4,168.95	2,058.89	3.02	-0.40	0.076
80.60	-19.58	-2.00	0.00	-137.93	0.00	137.93	2,951.54	1,475.77	4,056.14	2,003.18	3.25	-0.42	0.075
81.00	-19.05	-2.00	0.00	-137.13	0.00	137.13	2,946.46	1,473.23	4,038.81	1,994.61	3.28	-0.42	0.075
83.00	-18.71	-2.01	0.00	-133.13	0.00	133.13	2,920.94	1,460.47	3,952.64	1,952.06	3.46	-0.44	0.075
84.00	-18.34	-2.01	0.00	-131.12	0.00	131.12	2,908.96	1,454.48	3,910.94	1,931.47	3.56	-0.44	0.074
85.41	-18.11	-2.02	0.00	-128.29	0.00	128.29	2,288.86	1,144.43	3,120.34	1,541.02	3.69	-0.45	0.091
87.00	-17.67	-2.03	0.00	-125.07	0.00	125.07	2,274.94	1,137.47	3,069.59	1,515.95	3.84	-0.47	0.090
90.00	-17.24	-2.06	0.00	-118.97	0.00	118.97	2,248.22	1,124.11	2,974.43	1,468.96	4.14	-0.49	0.089
93.00	-16.82	-2.08	0.00	-112.81	0.00	112.81	2,220.81	1,110.41	2,879.80	1,422.23	4.46	-0.51	0.087
96.00	-16.40	-2.10	0.00	-106.57	0.00	106.57	2,192.74	1,096.37	2,785.75	1,375.78	4.79	-0.54	0.085
99.00	-15.99	-2.13	0.00	-100.26	0.00	100.26	2,163.98	1,081.99	2,692.34	1,329.64	5.13	-0.56	0.083
102.00	-15.58	-2.15	0.00	-93.88	0.00	93.88	2,134.56	1,067.28	2,599.61	1,283.85	5.49	-0.58	0.080
105.00	-15.31	-2.17	0.00	-87.43	0.00	87.43	2,104.45	1,052.22	2,507.63	1,238.42	5.86	-0.61	0.078
107.00	-15.05	-2.18	0.00	-83.10	0.00	83.10	2,084.00	1,042.00	2,446.74	1,208.36	6.12	-0.62	0.076
108.00	-14.66	-2.20	0.00	-80.92	0.00	80.92	2,073.67	1,036.83	2,416.44	1,193.39	6.25	-0.63	0.075
111.00	-14.28	-2.21	0.00	-74.33	0.00	74.33	2,042.21	1,021.11	2,326.10	1,148.77	6.65	-0.65	0.072
114.00	-13.91	-2.22	0.00	-67.69	0.00	67.69	2,006.48	1,003.24	2,232.66	1,102.63	7.07	-0.67	0.068
117.00	-13.54	-2.23	0.00	-61.02	0.00	61.02	1,959.62	979.81	2,129.00	1,051.43	7.50	-0.70	0.065
120.00	-13.27	-2.23	0.00	-54.34	0.00	54.34	1,912.75	956.38	2,027.81	1,001.46	7.94	-0.72	0.061
122.12	-13.12	-2.23	0.00	-49.62	0.00	49.62	1,879.60	939.80	1,957.71	966.84	8.26	-0.73	0.058
123.00	-10.82	-2.17	0.00	-47.66	0.00	47.66	1,865.89	932.94	1,929.08	952.70	8.40	-0.74	0.056
125.89	-10.81	-2.17	0.00	-41.41	0.00	41.41	929.68	464.84	961.73	474.96	8.85	-0.75	0.099
126.00	-10.54	-2.15	0.00	-41.17	0.00	41.17	929.29	464.65	960.40	474.31	8.87	-0.75	0.098
129.00	-10.28	-2.14	0.00	-34.70	0.00	34.70	918.88	459.44	925.49	457.06	9.35	-0.78	0.087
132.00	-10.19	-2.13	0.00	-28.29	0.00	28.29	907.79	453.90	890.46	439.76	9.85	-0.81	0.076
133.00	-7.40	-1.85	0.00	-26.16	0.00	26.16	903.95	451.97	878.77	433.99	10.02	-0.81	0.068

135.00	-7.17	-1.82	0.00	-22.46	0.00	22.46	896.03	448.02	855.37	422.43	10.36	-0.83	0.061
138.00	-6.94	-1.78	0.00	-17.00	0.00	17.00	883.59	441.80	820.26	405.10	10.89	-0.84	0.050
141.00	-6.79	-1.76	0.00	-11.65	0.00	11.65	870.48	435.24	785.20	387.78	11.42	-0.86	0.038
143.00	-3.93	-1.16	0.00	-8.14	0.00	8.14	861.36	430.68	761.88	376.27	11.78	-0.87	0.026
144.00	-3.80	-1.14	0.00	-6.98	0.00	6.98	856.69	428.34	750.24	370.52	11.97	-0.87	0.023
146.00	-3.71	-1.11	0.00	-4.70	0.00	4.70	847.12	423.56	727.02	359.05	12.33	-0.87	0.017
146.00	-3.71	-1.11	0.00	-4.70	0.00	4.70	920.33	460.16	575.46	378.52	12.33	-0.87	0.016
147.00	-3.51	-1.06	0.00	-3.59	0.00	3.59	920.33	460.16	575.46	378.52	12.51	-0.87	0.013
149.00	-0.91	-0.32	0.00	-1.47	0.00	1.47	920.33	460.16	575.46	378.52	12.88	-0.88	0.005
150.00	-0.68	-0.25	0.00	-1.15	0.00	1.15	920.33	460.16	575.46	378.52	13.06	-0.88	0.004
153.00	-0.53	-0.20	0.00	-0.39	0.00	0.39	920.33	460.16	575.46	378.52	13.62	-0.88	0.002
155.00	0.00	-0.19	0.00	0.00	0.00	0.00	920.33	460.16	575.46	378.52	13.98	-0.88	0.000

Analysis Summary

	Reactions						Max Usage	
Load Case	Shear FX (kips)	Shear FZ (kips)	Axial FY (kips)	Moment MX (ft-kips)	Moment MY (ft-kips)	Moment MZ (ft-kips)	Elev (ft)	Interaction Ratio
1.2D + 1.6W	35.01	0.00	52.72	0.00	0.00	3903.79	45.90	0.87
0.9D + 1.6W	34.78	0.00	39.53	0.00	0.00	3811.94	45.90	0.84
1.2D + 1.0Di + 1.0Wi	8.54	0.00	99.85	0.00	0.00	1082.46	45.90	0.27
(1.2 + 0.2Sds) * DL + E ELFM	1.72	0.00	53.32	0.00	0.00	229.27	45.90	0.06
(1.2 + 0.2Sds) * DL + E EMAM	2.63	0.00	53.32	0.00	0.00	329.82	125.89	0.11
(0.9 - 0.2Sds) * DL + E ELFM	1.72	0.00	37.18	0.00	0.00	224.02	45.90	0.06
(0.9 - 0.2Sds) * DL + E EMAM	2.63	0.00	37.18	0.00	0.00	322.11	125.89	0.10
1.0D + 1.0W	8.32	0.00	43.97	0.00	0.00	919.23	45.90	0.21

Code Rev.	***G***	**Date**	11/15/2017
		Engineer	RDB
		Site #	302495
Moment	3903.8 k-ft	**Carrier**	Sprint Nextel
Axial	52.7 k		

Base/Flange Plate	Plate Type	***Baseplate***	
	Pole Diameter	50	in
	Pole Thickness	0.4375	in
	Plate Diameter	65	in
	Plate Thickness	2	in
	Plate Fy	60	ksi
	Weld Length	0.3125	in
	ϕ_s Resistance	996.01	k-in
	Applied	567.21	k-in
Stiffeners	#	***8***	***Show***
	Thickness	0.75	in
	Length	5	in
	Height	12	in
	Chamfer	0.5	in
	Offset Angle	0	°
	Fy	36	ksi

Bolts	#	***16***	
	Bolt Circle	59	in
	(R)adial / (S)quare	R	
●	Diameter	2.25	in
	Hole Diameter	2.75	in
	Type	A615 Gr 75	
	Fy	75	ksi
	Fu	100	ksi
	ϕ_s Resistance	259.82	k
	Applied	201.67	k
Reinforcement ●	#	***0***	
Extra Bolts O	#	***0***	



Plate Stress Ratio:

0.57 (Pass)

Bolt Stress Ratio:

0.78 (Pass)

Base/Flange Plate	Plate Type	***Flange***	***@ 146.0 ft***
	Pole Diameter	16	in
	Pole Thickness	0.5	in
	Plate Diameter	28.5	in
	Plate Thickness	1	in
	Plate Fy	60	ksi
	Weld Length	0.3125	in
	ϕ_s Resistance	56.55	k-in
	Applied	11.67	k-in
Stiffeners	#	***0***	

Bolts	#	***12***	
	Bolt Circle	25.75	in
	(R)adial / (S)quare	R	
●	Diameter	1	in
	Hole Diameter	1.125	in
	Type	A325	
	Fy	92	ksi
	Fu	120	ksi
	ϕ_s Resistance	54.52	k
	Applied	2.92	k
Reinforcement ●	#	***0***	
Extra Bolts O	#	***0***	

Code Rev. ***G***

Moment 21.2 k-ft
Axial 4.6 k

Date	11/15/2017
Engineer	RDB
Site #	302495
Carrier	Sprint Nextel

Required Flange Thickness:
0.45 in OK



Plate Stress Ratio:
0.21 (Pass)

Bolt Stress Ratio:
0.05 (Pass)

Site Name:	Tolland, CT	*Program Last Updated:*	*5/13/2014*
Site Number:	302495	*American Tower Corporation*	
Engineer:	RDB		
Engineering Number:	OAA714899_C3_01		
Date:	11/15/17		



Design Base Loads (Factored) - Analysis per TIA-222-G Standards

Analyze or Design a Foundation?	Analyze	
Foundation Mapped:	N	
Moment (M):	3903.8	k-ft
Shear/Leg (V):	35.0	k
Axial Load (P):	52.7	k
Uplift/Leg (U):	0.0	k
Tower Type (GT / SST / MP):	MP	
Diameter of Caisson (d):	7.0	ft
Caisson Embedment (L-h):	30.0	ft
Caisson Height Above Ground (h):	0.5	ft
Depth Below Ground Surface to Water Table (w):	3.0	ft
Unit Weight of Concrete:	150.0	pcf
Unit Weight of Water:	62.4	pcf
Tension Skin Friction/Compression Skin Friction:	0.75	
Pullout Angle:	30.0	degrees

Engineer Notes

Soil Mechanical Properties

Depth (ft) Top	Depth (ft) Bottom	γ_{Soil} (pcf)	Cohesion (psf)	ϕ (degree)	Ultimate Skin Friction (psf)	Ultimate Bearing Pressure (psf)
0.0	3.0	105	0	0	0	0
3.0	5.0	127	0	37	0	0
5.0	10.0	133	0	40	832	0
10.0	31.0	137	0	40	1668	34021

Volume of Concrete:	1173.8	ft^3 =	43.5 yd^3
Weight of Concrete (Buoyancy Effect Considered):	111.2	k	
Average Soil Unit Weight:	76.3	pcf	
Skin Friction Resistance:	825.1	k	
Compressive Bearing Resistance:	1309.3	k	
Pullout Weight (Minus Concrete Weight):	1155.1	k	
Nominal Uplift Capacity per Leg ($\phi_s T_n$):	547.5	k	
Nominal Compressive Capacity per Leg ($\phi_s P_n$):	1600.8	k	
P_u:	77.0	k	
$T_u/\phi_s T_n$:	0.00	Result:	OK
$P_u/\phi_s P_n$:	0.05	Result:	OK
Total Lateral Resistance:	2862.3	k	
Inflection Point (Below Ground Surface):	21.1	ft	
Design Overturning Moment At Inflection Point (M_D):	4660.5	k-ft	
Nominal Moment Capacity ($\phi_s M_n$):	12424.5	k-ft	
$M_D/\phi_s M_n$:	0.38	Result:	OK
ϕ_s:	0.75		

Caisson Strength Capacity

Concrete Compressive Strength (f'_c):	4000	psi
Vertical Steel Rebar Size #:	11	
Vertical Steel Rebar Area:	1.56	in^2
# of Vertical Steel Rebars:	18	
Vertical Steel Rebar Yield Strength (F_y):	60	ksi
Horizontal Tie / Stirrup Size #:	5	
Horizontal Tie / Stirrup Area:	0.31	in^2
Design Horizontal Tie / Stirrup Spacing:	12.0	in
Horizontal Tie / Stirrup Steel Yield Strength (F_y):	60	ksi
Rebar Cage Diameter:	76.0	in
Strength Bending/Tension Reduction Factor (ϕ_B):	0.90	ACI318-05 - 9.3.2.1
Strength Shear Reduction Factor (ϕ_V):	0.75	ACI318-05 - 9.3.2.3
Strength Compression Reduction Factor (ϕ_V):	0.65	ACI318-05 - 9.3.2.2
Steel Elastic Modulus:	29000	ksi
Design Moment (M_u):	3930.3	k-ft
Nominal Moment Capacity ($\phi_B M_n$):	4700.7	k-ft - ACI318-005 - 10.2
$M_u/\phi_B M_n$:	0.84	Result: OK
Design Shear (V_u):	316.2	k
Nominal Shear Capacity ($\phi_V V_n$):	528.2	k - ACI318-05 - 11.3.1.1 or 11.5.7.2
$V_u/\phi_V V_n$:	0.60	Result: OK
Design Tension (T_u):	0.0	k
Nominal Tension Capacity ($\phi_T T_n$):	1516.3	k - ACI318-05 - 10.2
$T_u/\phi_T T_n$:	0.00	Result: OK
Design Compression (P_u):	77.0	k
Nominal Compression Capacity ($\phi_P P_n$):	9748.2	k - ACI318-05 - 10.3.6.2
$P_u/\phi_P P_n$:	0.01	Result: OK
Bending Reinforcement Ratio:	0.005	ACI318-05 - 10.8.4 & 10.9.1
$M_u/\phi_B M_n + T_u/\phi_T T_n$:	0.84	Result: OK


Design Factored Shear / Depth
-400
-300
-200
-100
0
100
0
-5
-10
-15
-20
-25
-30
-35
Depth (ft)
Shear (k)


Design Factored Moment / Depth
0
2000
4000
6000
0
-5
-10
-15
-20
-25
-30
-35
Depth (ft)
Moment (k-ft)


Nominal and Factored Moment Capacity and Factored Design Loads
0
2000
4000
6000
8000
10000
12000
14000
16000
18000
20000
25000
20000
15000
10000
5000
0
-5000
Axial (kip)
Moment (k-ft)
Pu & Mu
Tu & Mu
Factored Envelope
Nominal Envelope

Sprint

PROJECT:	DO MACRO UPGRADE
SITE NAME:	SNET - TOLLAND
SITE CASCADE:	CT03XC207
SITE ADDRESS:	1 EAGLE HILL TOLLAND, CT 06084
SITE TYPE:	MONOPOLE TOWER
MARKET:	NORTHERN CONNECTICUT

SITE INFORMATION

TOWER OWNER:
AMERICAN TOWER CORPORATION
10 PRESIDENTIAL WAY
WOBURN, MA 01801

LATITUDE (NAD83):
42° 52' 24.43" N
42.872619°

LONGITUDE (NAD83):
72° 20' 18.66" W
-72.338517°

COUNTY:
TOLLAND COUNTY

ZONING JURISDICTION:
CONNECTICUT SITING COUNCIL

ZONING DISTRICT:
TBD

POWER COMPANY:
CONNECTICUT LIGHT & POWER
PHONE: (800) 322-3223

AAV PROVIDER:
FRONTIER COMMUNICATIONS
PHONE: (866) 502-7167

PROJECT MANAGER:
AIROSMITH DEVELOPMENT
TERRI BURKHOLDER
(315) 719-2928
TBURKHOLDER@AIROSMITHDEVELOPMENT.COM

AREA MAP



LOCATION MAP



PROJECT DESCRIPTION

SPRINT PROPOSES TO MODIFY AN EXISTING UNMANNED TELECOMMUNICATIONS FACILITY.

- REMOVE (3) EXISTING PANEL ANTENNAS (3), PANEL ANTENNAS TO REMAIN
- INSTALL (3) PANEL ANTENNAS
- RELOCATE (3) 1900 MHz RRH'S BEHIND EXISTING PIPE MOUNT
- INSTALL (3) 2.5 GHz & (3) 800 MHz RRH'S BEHIND PROPOSED ANTENNAS
- INSTALL (3) 800 MHz RRH'S BEHIND EXISTING PIPE MOUNT
- INSTALL (48) JUMPER CABLES
- INSTALL (4) HYBRID CABLE
- INSTALL 2.5 EQUIPMENT INSIDE EXISTING N.V. MMBS CABINET

THESE PLANS HAVE BEEN DEVELOPED FOR THE MODIFICATION OF AN EXISTING UNMANNED TELECOMMUNICATIONS FACILITY OWNED OR LEASED BY SPRINT IN ACCORDANCE WITH THE SCOPE OF WORK PROVIDED BY SPRINT. INFINIGY HAS INCORPORATED THIS SCOPE OF WORK IN THE PLANS. THESE PLANS ARE NOT FOR CONSTRUCTION UNLESS ACCOMPANIED BY A PASSING STRUCTURAL STABILITY ANALYSIS PREPARED BY A LICENSED STRUCTURAL ENGINEER. STRUCTURAL ANALYSIS MUST INCLUDE BOTH TOWER AND MOUNT.

APPLICABLE CODES

ALL WORK SHALL BE PERFORMED AND MATERIALS INSTALL IN ACCORDANCE WITH THE CURRENT EDITIONS OF THE FOLLOWING CODES AS ADOPTED BY THE LOCAL GOVERNING AUTHORITIES. NOTHING IN THESE PLANS IS TO BE CONSTRUED TO PERMIT WORK NOT CONFORMING TO THESE CODES.

1. INTERNATIONAL BUILDING CODE (2015 IBC)
2. TIA-222-G OR LATEST EDITION
3. NFPA 780 – LIGHTNING PROTECTION CODE
4. 2011 NATIONAL ELECTRIC CODE OR LATEST EDITION
5. ANY OTHER NATIONAL OR LOCAL APPLICABLE CODES, MOST RECENT EDITIONS
6. CT BUILDING CODE
7. LOCAL BUILDING CODE
8. CITY/COUNTY ORDINANCES

811 Know what's below. Call before you dig. www.call811.com

DRAWING INDEX

SHEET NO.	SHEET TITLE	REV.
T-1	TITLE SHEET & PROJECT DATA	0
SP-1	SPRINT SPECIFICATIONS	0
SP-2	SPRINT SPECIFICATIONS	0
SP-3	SPRINT SPECIFICATIONS	0
A-1	SITE PLAN	0
A-2	TOWER ELEVATION	0
A-3	ANTENNA LAYOUT & MOUNTING DETAILS	0
A-4	EQUIPMENT & MOUNTING DETAILS	0
A-5	CIVIL DETAILS	0
A-6	PLUMBING DIAGRAM	0
E-1	ELECTRICAL & GROUNDING PLAN	0
E-2	ELECTRICAL & GROUNDING DETAILS	0

PLANS PREPARED FOR:
Sprint

PLANS PREPARED BY:

INFINIGY
FROM ZERO TO INFINIGY
the solutions are endless
1033 Watervliet Shaker Rd | Albany, NY 12205
Phone: 518-690-0790 | Fax: 518-690-0793
www.infinigy.com
JOB NUMBER 526-104

PROJECT MANAGER:

AIROSMITH DEVELOPMENT
32 CLINTON ST.
SARATOGA SPRINGS, NY 12866
OFFICE#. (518) 306-3740

ENGINEERING LICENSE:
STATE OF CONNECTICUT
JOHN S. STEVENS
JANUARY 2018
No. 24705
LICENSED PROFESSIONAL ENGINEER

DRAWING NOTICE:

REVISIONS:

DESCRIPTION	DATE	BY	REV.
ISSUED FOR PERMIT	12/27/17	JDL	0

SITE NAME:
SNET - TOLLAND

SITE NUMBER:
CT03XC207

SITE ADDRESS:
1 EAGLE HILL
TOLLAND, CT 06084

SHEET DESCRIPTION:
TITLE SHEET
& PROJECT DATA

SHEET NUMBER:
T-1

THESE OUTLINE SPECIFICATIONS IN CONJUNCTION WITH THE SPRINT STANDARD CONSTRUCTION SPECIFICATIONS, INCLUDING CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

SECTION 01 100 – SCOPE OF WORK

PART 1 – GENERAL

1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE SPRINT CONSTRUCTION STANDARDS FOR WIRELESS SITES, CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

1.2 RELATED DOCUMENTS:

A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.

B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.

1.3 PRECEDENCE: SHOULD CONFLICTS OCCUR BETWEEN THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES INCLUDING THE STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES AND THE CONSTRUCTION DRAWINGS, INFORMATION ON THE CONSTRUCTION DRAWINGS SHALL TAKE PRECEDENCE. NOTIFY SPRINT CONSTRUCTION MANAGER IF THIS OCCURS.

1.4 NATIONALLY RECOGNIZED CODES AND STANDARDS:

A. THE WORK SHALL COMPLY WITH APPLICABLE NATIONAL AND LOCAL CODES AND STANDARDS, LATEST EDITION, AND PORTIONS THEREOF, INCLUDED BUT NOT LIMITED TO THE FOLLOWING:

1. GR-63-CORE NEBS REQUIREMENTS: PHYSICAL PROTECTION
5. GR-78-CORE GENERIC REQUIREMENTS FOR THE PHYSICAL DESIGN AND MANUFACTURE OF TELECOMMUNICATIONS EQUIPMENT.
3. GR-1089 CORE, ELECTROMAGNETIC COMPATIBILITY AND ELECTRICAL SAFETY –GENERIC CRITERIA FOR NETWORK TELECOMMUNICATIONS EQUIPMENT.
4. NATIONAL FIRE PROTECTION ASSOCIATION CODES AND STANDARDS (NFPA) INCLUDING NFPA 70 (NATIONAL ELECTRICAL CODE – "NEC") AND NFPA 101 (LIFE SAFETY CODE).
5. AMERICAN SOCIETY FOR TESTING OF MATERIALS (ASTM)
6. INSTITUTE OF ELECTRONIC AND ELECTRICAL ENGINEERS (IEEE)
7. AMERICAN CONCRETE INSTITUTE (ACI)
8. AMERICAN WIRE PRODUCERS ASSOCIATION (AWPA)
9. CONCRETE REINFORCING STEEL INSTITUTE (CRSI)
10. AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)
11. PORTLAND CEMENT ASSOCIATION (PCA)
12. NATIONAL CONCRETE MASONRY ASSOCIATION (NCMA)
13. BRICK INDUSTRY ASSOCIATION (BIA)
14. AMERICAN WELDING SOCIETY (AWS)
15. NATIONAL ROOFING CONTRACTORS ASSOCIATION (NRCA)
16. SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)
17. DOOR AND HARDWARE INSTITUTE (DHI)
18. OCCUPATIONAL SAFETY AND HEALTH ACT (OSHA)
19. APPLICABLE BUILDING CODES INCLUDING UNIFORM BUILDING CODE, SOUTHERN BUILDING CODE, BOCA, AND THE INTERNATIONAL BUILDING CODE.

1.5 DEFINITIONS:

A. WORK: THE SUM OF TASKS AND RESPONSIBILITIES IDENTIFIED IN THE CONTRACT DOCUMENTS.

B. COMPANY: SPRINT CORPORATION

C. ENGINEER: SYNONYMOUS WITH ARCHITECT & ENGINEER AND "A&E". THE DESIGN PROFESSIONAL HAVING PROFESSIONAL RESPONSIBILITY FOR DESIGN OF THE PROJECT.

D. CONTRACTOR: CONSTRUCTION CONTRACTOR; CONSTRUCTION VENDOR; INDIVIDUAL OR ENTITY WHO AFTER EXECUTION OF A CONTRACT IS BOUND TO ACCOMPLISH THE WORK.

E. THIRD PARTY VENDOR OR AGENCY: A VENDOR OR AGENCY ENGAGED SEPARATELY BY THE COMPANY, A&E, OR CONTRACTOR TO PROVIDE MATERIALS OR TO ACCOMPLISH SPECIFIC TASKS RELATED TO BUT NOT INCLUDED IN THE WORK.

F. OFCI: OWNER FURNISHED, CONTRACTOR INSTALLED EQUIPMENT.

G. CONSTRUCTION MANAGER – ALL PROJECTS RELATED COMMUNICATION TO FLOW THROUGH SPRINT REPRESENTATIVE IN CHARGE OF PROJECT...

1.6 SITE FAMILIARITY: CONTRACTOR SHALL BE RESPONSIBLE FOR FAMILIARIZING HIMSELF WITH ALL CONTRACT DOCUMENTS, FIELD CONDITIONS AND DIMENSIONS PRIOR TO PROCEEDING WITH CONSTRUCTION. ANY DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE SPRINT CONSTRUCTION MANAGER PRIOR TO THE COMMENCEMENT OF WORK. NO COMPENSATION WILL BE AWARDED BASED ON CLAIM OF LACK OF KNOWLEDGE OR FIELD CONDITIONS.

1.7 POINT OF CONTACT: COMMUNICATION BETWEEN SPRINT AND THE CONTRACTOR SHALL FLOW THROUGH THE SINGLE SPRINT CONSTRUCTION MANAGER APPOINTED TO MANAGE THE PROJECT FOR SPRINT.

1.8 ON-SITE SUPERVISION: THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK AND SHALL BE RESPONSIBLE FOR CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES IN ACCORDANCE WITH THE CONTRACT DOCUMENTS. THE CONTRACTOR SHALL EMPLOY A COMPETENT SUPERINTENDENT WHO SHALL BE IN ATTENDANCE AT THE SITE AT ALL TIMES DURING PERFORMANCE OF THE WORK.

1.9 DRAWINGS, SPECIFICATIONS AND DETAILS REQUIRED AT JOBSITE: THE CONSTRUCTION CONTRACTOR SHALL MAINTAIN A FULL SET OF THE CONSTRUCTION DRAWINGS, STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES AND THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES AT THE JOBSITE FROM MOBILIZATION THROUGH CONSTRUCTION COMPLETION.

A. THE JOBSITE DRAWINGS, SPECIFICATIONS AND DETAILS SHALL BE CLEARLY MARKED DAILY IN RED PENCIL WITH ANY CHANGES IN CONSTRUCTION OVER WHAT IS DEPICTED IN THE DOCUMENTS. AT CONSTRUCTION COMPLETION, THIS JOBSITE MARKUP SET SHALL BE DELIVERED TO THE COMPANY OR COMPANY'S DESIGNATED REPRESENTATIVE TO BE FORWARDED TO THE COMPANY'S A&E VENDOR FOR PRODUCTION OF "AS-BUILT" DRAWINGS.

B. DETAILS ARE INTENDED TO SHOW DESIGN INTENT. MODIFICATIONS MAY BE REQUIRED TO SUIT JOB DIMENSIONS OR CONDITIONS, AND SUCH MODIFICATIONS SHALL BE INCLUDED AS PART OF THE WORK. CONTRACTOR SHALL NOTIFY SPRINT CONSTRUCTION MANAGER OF ANY VARIATIONS PRIOR TO PROCEEDING WITH THE WORK.

C. DIMENSIONS SHOWN ARE TO FINISH SURFACES UNLESS NOTED OTHERWISE. SPACING BETWEEN EQUIPMENT IS THE REQUIRED CLEARANCE. SHOULD THERE BE ANY QUESTIONS REGARDING THE CONTRACT DOCUMENTS, EXISTING CONDITIONS AND/OR DESIGN INTENT, THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING A CLARIFICATION FROM THE SPRINT CONSTRUCTION MANAGER PRIOR TO PROCEEDING WITH THE WORK.

1.10 USE OF JOB SITE: THE CONTRACTOR SHALL CONFINE ALL CONSTRUCTION AND RELATED OPERATIONS INCLUDING STAGING AND STORAGE OF MATERIALS AND EQUIPMENT, PARKING, TEMPORARY FACILITIES, AND WASTE STORAGE TO THE LEASE PARCEL UNLESS OTHERWISE PERMITTED BY THE CONTRACT DOCUMENTS.

1.11 UTILITIES SERVICES: WHERE NECESSARY TO CUT EXISTING PIPES, ELECTRICAL WIRES, CONDUITS, CABLES, ETC., OF UTILITY SERVICES, OR OF FIRE PROTECTION OR COMMUNICATIONS SYSTEMS, THEY SHALL BE CUT AND CAPPED AT SUITABLE PLACES OR WHERE SHOWN. ALL SUCH ACTIONS SHALL BE COORDINATED WITH THE UTILITY COMPANY INVOLVED:

1.12 PERMITS / FEES: WHEN REQUIRED THAT A PERMIT OR CONNECTION FEE BE PAID TO A PUBLIC UTILITY PROVIDER FOR NEW SERVICE TO THE CONSTRUCTION PROJECT, PAYMENT OF SUCH FEE SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.

1.13 CONTRACTOR SHALL TAKE ALL MEASURES AND PROVIDE ALL MATERIAL NECESSARY FOR PROTECTING EXISTING EQUIPMENT AND PROPERTY.

1.14 METHODS OF PROCEDURE (MOPS) FOR CONSTRUCTION: CONTRACTOR SHALL PERFORM WORK AS DESCRIBED IN THE FOLLOWING INSTALLATION AND COMMISSIONING MOPS.

NOTE: IN SHORT-FORM SPECIFICATIONS ON THE DRAWINGS, A/E TO INSERT LIST OF APPLICABLE MOPS INCLUDING EN-2012-001, EN-2013-002, EL-0568, AND TS-0193

1.15 USE OF ELECTRONIC PROJECT MANAGEMENT SYSTEMS:

PART 2 – PRODUCTS (NOT USED)

PART 3 – EXECUTION

3.1 TEMPORARY UTILITIES AND FACILITIES: THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL TEMPORARY UTILITIES AND FACILITIES NECESSARY EXCEPT AS OTHERWISE INDICATED IN THE CONSTRUCTION DOCUMENTS. TEMPORARY UTILITIES AND FACILITIES INCLUDE POTABLE WATER, HEAT, HVAC, ELECTRICITY, SANITARY FACILITIES, WASTE DISPOSAL FACILITIES, AND TELEPHONE/COMMUNICATION SERVICES. PROVIDE TEMPORARY UTILITIES AND FACILITIES IN ACCORDANCE WITH OSHA AND THE AUTHORITY HAVING JURISDICTION. CONTRACTOR MAY UTILIZE THE COMPANY ELECTRICAL SERVICE IN THE COMPLETION OF THE WORK WHEN IT BECOMES AVAILABLE. USE OF THE LESSORS OR SITE OWNER'S UTILITIES OR FACILITIES IS EXPRESSLY FORBIDDEN EXCEPT AS OTHERWISE ALLOWED IN THE CONTRACT DOCUMENTS.

3.2 ACCESS TO WORK: THE CONTRACTOR SHALL PROVIDE ACCESS TO THE JOB SITE FOR AUTHORIZED COMPANY PERSONNEL AND AUTHORIZED REPRESENTATIVES OF THE ARCHITECT/ENGINEER DURING ALL PHASES OF THE WORK.

3.3 TESTING: REQUIREMENTS FOR TESTING BY THIS CONTRACTOR SHALL BE AS INDICATED HEREWITH, ON THE CONSTRUCTION DRAWINGS, AND IN THE INDIVIDUAL SECTIONS OF THESE SPECIFICATIONS. SHOULD COMPANY CHOOSE TO ENGAGE ANY THIRD-PARTY TO CONDUCT ADDITIONAL TESTING, THE CONTRACTOR SHALL COOPERATE WITH AND PROVIDE A WORK AREA FOR COMPANY'S TEST AGENCY.

3.4 DIMENSIONS: VERIFY DIMENSIONS INDICATED ON DRAWINGS WITH FIELD DIMENSIONS BEFORE FABRICATION OR ORDERING OF MATERIALS. DO NOT SCALE DRAWINGS.

3.5 EXISTING CONDITIONS: NOTIFY THE SPRINT CONSTRUCTION MANAGER OF EXISTING CONDITIONS DIFFERING FROM THOSE INDICATED ON THE DRAWINGS. DO NOT REMOVE OR ALTER STRUCTURAL COMPONENTS WITHOUT PRIOR WRITTEN APPROVAL FROM THE ARCHITECT AND ENGINEER.

SECTION 01 200 – COMPANY FURNISHED MATERIAL AND EQUIPMENT

PART 1 – GENERAL

1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

1.2 RELATED DOCUMENTS:

A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.

B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.

PART 2 – PRODUCTS (NOT USED)

PART 3 – EXECUTION

3.1 RECEIPT OF MATERIAL AND EQUIPMENT:

A. A COMPANY FURNISHED MATERIAL AND EQUIPMENT IS IDENTIFIED ON THE RF DATA SHEET IN THE CONSTRUCTION DOCUMENTS.

B. THE CONTRACTOR IS RESPONSIBLE FOR SPRINT PROVIDED MATERIAL AND EQUIPMENT AND UPON RECEIPT SHALL:

1 ACCEPT DELIVERIES AS SHIPPED AND TAKE RECEIPT.

2. VERIFY COMPLETENESS AND CONDITION OF ALL DELIVERIES.

3. TAKE RESPONSIBILITY FOR EQUIPMENT AND PROVIDE INSURANCE PROTECTION AS REQUIRED IN AGREEMENT.

4. RECORD ANY DEFECTS OR DAMAGES AND WITHIN TWENTY-FOUR HOURS AFTER RECEIPT, REPORT TO SPRINT OR ITS DESIGNATED PROJECT REPRESENTATIVE OF SUCH.

5. PROVIDE SECURE AND NECESSARY WEATHER PROTECTED WAREHOUSING.

6. COORDINATE SAFE AND SECURE TRANSPORTATION OF MATERIAL AND EQUIPMENT, DELIVERING AND OFF-LOADING FROM CONTRACTOR'S WAREHOUSE TO SITE.

3.2 DELIVERABLES:

A. COMPLETE SHIPPING AND RECEIPT DOCUMENTATION IN ACCORDANCE WITH COMPANY PRACTICE.

B. IF APPLICABLE, COMPLETE LOST/STOLEN/DAMAGED DOCUMENTATION REPORT AS NECESSARY IN ACCORDANCE WITH COMPANY PRACTICE, AND AS DIRECTED BY COMPANY.

C. UPLOAD DOCUMENTATION INTO SPRINT SITE MANAGEMENT SYSTEM (SMS) AND/OR PROVIDE HARD COPY DOCUMENTATION AS REQUESTED.

SECTION 01 300 – CELL SITE CONSTRUCTION CO.

PART 1 – GENERAL

1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

1.2 RELATED DOCUMENTS:

A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.

B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.

1.3 NOTICE TO PROCEED

A. NO WORK SHALL COMMENCE PRIOR TO COMPANY'S WRITTEN NOTICE TO PROCEED AND THE ISSUANCE OF THE WORK ORDER.

B. UPON RECEIVING NOTICE TO PROCEED, CONTRACTOR SHALL FULLY PERFORM ALL WORK NECESSARY TO PROVIDE SPRINT WITH AN OPERATIONAL WIRELESS FACILITY.

PART 2 – PRODUCTS (NOT USED)

PART 3 – EXECUTION

3.1 FUNCTIONAL REQUIREMENTS:

A. THE ACTIVITIES DESCRIBED IN THIS PARAGRAPH REPRESENT MINIMUM ACTIONS AND PROCESSES REQUIRED TO SUCCESSFULLY COMPLETE THE WORK. THE ACTIVITIES DESCRIBED ARE NOT EXHAUSTIVE, AND CONTRACTOR SHALL TAKE ANY AND ALL ACTIONS AS NECESSARY TO SUCCESSFULLY COMPLETE THE CONSTRUCTION OF A FULLY FUNCTIONING WIRELESS FACILITY AT THE SITE IN ACCORDANCE WITH COMPANY PROCESSES.

B. SUBMIT SPECIFIC DOCUMENTATION AS INDICATED HEREIN, AND OBTAIN REQUIRED APPROVALS WHILE THE WORK IS BEING PERFORMED.

C. MANAGE AND CONDUCT ALL FIELD CONSTRUCTION SERVICE RELATED ACTIVITIES

D. PROVIDE CONSTRUCTION ACTIVITIES TO THE EXTENT REQUIRED BY THE CONTRACT DOCUMENTS, INCLUDING BUT NOT LIMITED TO THE FOLLOWING:

PLANS PREPARED FOR:

Sprint

PLANS PREPARED BY:

INFINIGY
FROM ZERO TO INFINIGY
the solutions are endless
1033 Watervliet Shaker Rd | Albany, NY 12205
Phone: 518-690-0790 | Fax: 518-690-0793
www.infinigy.com
JOB NUMBER 526-104

PROJECT MANAGER:

AIROSMITH DEVELOPMENT
32 CLINTON ST.
SARATOGA SPRINGS, NY 12866
OFFICE#. (518) 306-3740

ENGINEERING LICENSE:

DRAWING NOTICE:

REVISIONS:

DESCRIPTION	DATE	BY	REV.
ISSUED FOR PERMIT	12/27/17	JDL	0

SITE NAME:

SNET - TOLLAND

SITE NUMBER:

CT03XC207

SITE ADDRESS:

1 EAGLE HILL
TOLLAND, CT 06084

SHEET DESCRIPTION:

SPRINT SPECIFICATIONS

SHEET NUMBER:

SP-1

CONTINUE FROM SP-1

1. PERFORM ANY REQUIRED SITE ENVIRONMENTAL MITIGATION.
2. PREPARE GROUND SITES; PROVIDE DE-GRUBBING; AND ROUGH AND FINAL GRADING, AND COMPOUND SURFACE TREATMENTS.
3. MANAGE AND CONDUCT ALL ACTIVITIES FOR INSTALLATION OF UTILITIES INCLUDING ELECTRICAL AND TELCO BACKHAUL.
4. INSTALL UNDERGROUND FACILITIES INCLUDING UNDERGROUND POWER AND COMMUNICATIONS CONDUITS, AND UNDERGROUND GROUNDING SYSTEM.
5. INSTALL ABOVE GROUND GROUNDING SYSTEMS.
6. PROVIDE NEW HVAC INSTALLATIONS AND MODIFICATIONS.
7. INSTALL "H-FRAMES", CABINETS AND SHELTERS AS INDICATED.
8. INSTALL ROADS, ACCESS WAYS, CURBS AND DRAINS AS INDICATED.
9. ACCOMPLISH REQUIRED MODIFICATION OF EXISTING FACILITIES.
10. PROVIDE ANTENNA SUPPORT STRUCTURE FOUNDATIONS.
11. PROVIDE SLABS AND EQUIPMENT PLATFORMS.
12. INSTALL COMPOUND FENCING, SIGHT SHIELDING, LANDSCAPING AND ACCESS BARRIERS.
13. PERFORM INSPECTION AND MATERIAL TESTING AS REQUIRED HEREINAFTER.
14. CONDUCT SITE RESISTANCE TO EARTH TESTING AS REQUIRED HEREINAFTER
15. INSTALL FIXED GENERATOR SETS AND OTHER STANDBY POWER SOLUTIONS.
16. INSTALL TOWERS, ANTENNA SUPPORT STRUCTURES AND PLATFORMS ON EXISTING TOWERS AS REQUIRED.
17. INSTALL CELL SITE RADIOS, MICROWAVE, GPS, COAXIAL MAINLINE, ANTENNAS, CROSS BAND COUPLERS, TOWER TOP AMPLIFIERS, LOW NOISE AMPLIFIERS AND RELATED EQUIPMENT.
18. PERFORM, DOCUMENT, AND CLOSE OUT ANY CONSTRUCTION CONTROL DOCUMENTS THAT MAY BE REQUIRED BY GOVERNMENT AGENCIES AND LANDLORDS.
19. PERFORM ANTENNAL AND COAX SWEEP TESTING AND MAKE ANY AND ALL NECESSARY CORRECTIONS.
20. REMAIN ON SITE MOBILIZED THROUGHOUT HAND-OFF AND INTEGRATION TO ASSIST AS NEEDED UNTIL SITE IS DEEMED SUBSTANTIALLY COMPLETE AND PLACED "ON AIR."

3.2 GENERAL REQUIREMENTS FOR CIVIL CONSTRUCTION:

A. CONTRACTOR SHALL KEEP THE SITE FREE FROM ACCUMULATING WASTE MATERIAL, DEBRIS, AND TRASH. AT THE COMPLETION OF THE WORK, CONTRACTOR SHALL REMOVE FROM THE SITE ALL REMAINING RUBBISH, IMPLEMENTS, TEMPORARY FACILITIES, AND SURPLUS MATERIALS.

B. EQUIPMENT ROOMS SHALL AT ALL TIMES BE MAINTAINED "BROOM CLEAN" AND CLEAR OF DEBRIS.

C. CONTRACTOR SHALL TAKE ALL REASONABLE PRECAUTIONS TO DISCOVER AND LOCATE ANY HAZARDOUS CONDITION.

1. IN THE EVENT CONTRACTOR ENCOUNTERS ANY HAZARDOUS CONDITION WHICH HAS NOT BEEN ABATED OR OTHERWISE MITIGATED, CONTRACTOR AND ALL OTHER PERSONS SHALL IMMEDIATELY STOP WORK IN THE AFFECTED AREA AND NOTIFY COMPANY IN WRITING. THE WORK IN THE AFFECTED AREA SHALL NOT BE RESUMED EXCEPT BY WRITTEN NOTIFICATION BY COMPANY.
2. CONTRACTOR AGREES TO USE CARE WHILE ON THE SITE AND SHALL NOT TAKE ANY ACTION THAT WILL OR MAY RESULT IN OR CAUSE THE HAZARDOUS CONDITION TO BE FURTHER RELEASED IN THE ENVIRONMENT, OR TO FURTHER EXPOSE INDIVIDUALS TO THE HAZARD.

D. CONTRACTOR'S ACTIVITIES SHALL BE RESTRICTED TO THE PROJECT LIMITS. SHOULD AREAS OUTSIDE THE PROJECT LIMITS BE AFFECTED BY CONTRACTOR'S ACTIVITIES, CONTRACTOR SHALL IMMEDIATELY RETURN THEM TO ORIGINAL CONDITION

E. CONDUCT TESTING AS REQUIRED HEREIN.

3.3 DELIVERABLES:

A. CONTRACTOR SHALL REVIEW, APPROVE, AND SUBMIT TO SPRINT SHOP DRAWINGS, PRODUCT DATA, SAMPLES, AND SIMILAR SUBMITTALS AS REQUIRED HEREINAFTER

B. PROVIDE DOCUMENTATION INCLUDING, BUT NOT LIMITED TO, THE FOLLOWING. DOCUMENTATION SHALL BE FORWARDED IN ORIGINAL FORMAT AND/OR UPLOADED INTO SMS.

1. ALL CORRESPONDENCE AND PRELIMINARY CONSTRUCTION REPORTS.
2. PROJECT PROGRESS REPORTS.
3. CIVIL CONSTRUCTION START DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
4. ELECTRICAL SERVICE COMPLETION DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
5. LINES AND ANTENNA INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
6. POWER INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
7. TELCO READY DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
8. PPC (OR SHELTER) INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
9. TOWER CONSTRUCTION START DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
10. TOWER CONSTRUCTION COMPLETE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
11. BTS AND RADIO EQUIPMENT DELIVERED AT SITE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
12. NETWORK OPERATIONS HANDOFF CHECKLIST (HOC WALK) COMPLETE (UPLOAD FORM IN SMS)
13. CIVIL CONSTRUCTION COMPLETE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
14. SITE CONSTRUCTION PROGRESS PHOTOS UNLOADED INTO SMS.

SECTION 01 400 - SUBMITTALS & TESTS

PART 1 - GENERAL

1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

1.2 RELATED DOCUMENTS:

A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.

B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.

1.3 SUBMITTALS:

A. THE WORK IN ALL ASPECTS SHALL COMPLY WITH THE CONSTRUCTION DRAWINGS AND THESE SPECIFICATIONS.

B. SUBMIT THE FOLLOWING TO COMPANY REPRESENTATIVE FOR APPROVAL.

1. CONCRETE MIX-DESIGNS FOR TOWER FOUNDATIONS, ANCHORS PIERS, AND CONCRETE PAVING.
2. CONCRETE BREAK TESTS AS SPECIFIED HEREIN.
3. SPECIAL FINISHES FOR INTERIOR SPACES, IF ANY.
4. ALL EQUIPMENT AND MATERIALS SO IDENTIFIED ON THE CONSTRUCTION DRAWINGS.
5. CHEMICAL GROUNDING DESIGN

D. ALTERNATES: AT THE COMPANY'S REQUEST, ANY ALTERNATIVES TO THE MATERIALS OR METHODS SPECIFIED SHALL BE SUBMITTED TO SPRINT'S CONSTRUCTION MANAGER FOR APPROVAL PRIOR TO BEING SHIPPED TO SITE. SPRINT WILL REVIEW AND APPROVE ONLY THOSE REQUESTS MADE IN WRITING. NO VERBAL APPROVALS WILL BE CONSIDERED. SUBMITTAL FOR APPROVAL SHALL INCLUDE A STATEMENT OF COST REDUCTION PROPOSED FOR USE OF ALTERNATE PRODUCT.

1.4 TESTS AND INSPECTIONS:

A. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CONSTRUCTION TESTS, INSPECTIONS AND PROJECT DOCUMENTATION.

B. CONTRACTOR SHALL ACCOMPLISH TESTING INCLUDING BUT NOT LIMITED TO THE FOLLOWING:

1. COAX SWEEPS AND FIBER TESTS PER TS-0200 REV 4 ANTENNA LINE ACCEPTANCE STANDARDS.
2. AGL, AZIMUTH AND DOWNTILT USING ELECTRONIC COMMERCIAL MADE-FOR-THE-PURPOSE ANTENNA ALIGNMENT TOOL.
3. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN SITE INSPECTION ACTIVITIES AND/OR AS A RESULT OF TESTING.

C. REQUIRED CLOSEOUT DOCUMENTATION INCLUDES, BUT IS NOT LIMITED TO THE FOLLOWING;

1. AZIMUTH, DOWNTILT, AGL - UPLOAD REPORT FROM ANTENNA ALIGNMENT TOOL TO SITERRA TASK 465. INSTALLED AZIMUTH, DOWNTILT, AND AGL MUST CONFORM TO THE RF DATA SHEETS. SWEEP AND FIBER TESTS
2. SCANABLE BARCODE PHOTOGRAPHS OF TOWER TOP AND INACCESSIBLE SERIALIZED EQUIPMENT
3. ALL AVAILABLE JURISDICTIONAL INFORMATION
4. PDF SCAN OF REDLINES PRODUCED IN FIELD
5. ELECTRONIC AS-BUILT DRAWINGS IN AUTOCAD AND PDF FORMATS. ANY FIELD CHANGE MUST BE REFLECTED BY MODIFYING THE PLANS, ELEVATIONS, AND DETAILS IN THE DRAWING SETS. GENERAL NOTES INDICATING MODIFICATIONS WILL NOT BE ACCEPTED. CHANGES SHALL BE HIGHLIGHTED AS "CLOUDS" IDENTIFIED AS THE "AS-BUILT" CONDITION.
6. LIEN WAIVERS
7. FINAL PAYMENT APPLICATION
8. REQUIRED FINAL CONSTRUCTION PHOTOS
9. CONSTRUCTION AND COMMISSIONING CHECKLIST COMPLETE WITH NO DEFICIENT ITEMS
10. ALL POST NTP TASKS INCLUDING DOCUMENT UPLOADS COMPLETED IN SITERRA (SPRINTS DOCUMENT REPOSITORY OF RECORD).

1.5 COMMISSIONING: PERFORM ALL COMMISSIONING AS REQUIRED BY APPLICABLE MOPs

1.6 INTEGRATION: PERFORM ALL INTEGRATION ACTIVITIES AS REQUIRED BY APPLICABLE MOPs

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION

3.1 REQUIREMENTS FOR TESTING:

A. THIRD PARTY TESTING AGENCY:

1. WHEN THE USE OF A THIRD PARTY INDEPENDENT TESTING AGENCY IS REQUIRED, THE AGENCY THAT IS SELECTED MUST PERFORM SUCH WORK ON A REGULAR BASIS IN THE STATE WHERE THE PROJECT IS LOCATED AND HAVE A THOROUGH UNDERSTANDING OF LOCAL AVAILABLE MATERIALS, INCLUDING THE SOIL, ROCK, AND GROUNDWATER CONDITIONS.
2. THE THIRD PARTY TESTING AGENCY IS TO BE FAMILIAR WITH THE APPLICABLE REQUIREMENTS FOR THE TESTS TO BE DONE, EQUIPMENT TO BE USED, AND ASSOCIATED HEALTH AND SAFETY ISSUES.
3. EXPERIENCE IN SOILS, CONCRETE, MASONRY, AGGREGATE, AND ASPHALT TESTING USING ASTM, AASJTO, AND OTHER METHODS IS NEEDED.
4. EXPERIENCE IN SOILS, CONCRETE, MASONRY, AGGREGATE, AND ASPHALT TESTING USING ASTM, AASJTO, AND OTHER METHODS IS NEEDED.

3.2 REQUIRED TESTS:

A. CONTRACTOR SHALL ACCOMPLISH TESTING INCLUDING BUT NOT LIMITED TO THE FOLLOWING:

1. CONCRETE CYLINDER BREAK TESTS FOR THE TOWER AND ANCHOR FOUNDATIONS AS SPECIFIED IN SECTION: PORTLAND CEMENT CONCRETE PAVING.
2. ASPHALT ROADWAY COMPACTED THICKNESS, SURFACE SMOOTHNESS, AND COMPACTED DENSITY TESTING AS SPECIFIED IN SECTION: HOT MIX ASPHALT PAVING.
3. FIELD QUALITY CONTROL TESTING AS SPECIFIED IN SECTION: PORTLAND CEMENT CONCRETE PAVING.
4. TESTING REQUIRED UNDER SECTION: AGGREGATE BASE FOR ACCESS ROADS, PADS AND ANCHOR LOCATIONS
5. STRUCTURAL BACKFILL COMPACTION TESTS FOR THE TOWER FOUNDATION.
6. SITE RESISTANCE TO EARTH TESTING PER EXHIBIT: CELL SITE GROUNDING SYSTEM DESIGN.
7. ANTENNA AND COAX SWEEP TESTS PER EXHIBIT: ANTENNA TRANSMISSION LINE ACCEPTANCE STANDARDS.
8. GROUNDING AT ANTENNA MASTS FOR GPS AND ANTENNAS
9. ALL OTHER TESTS REQUIRED BY COMPANY OR JURISDICTION.

3.3 REQUIRED INSPECTIONS

A. SCHEDULE INSPECTIONS WITH COMPANY REPRESENTATIVE.

B. CONDUCT INSPECTIONS INCLUDING BUT NOT LIMITED TO THE FOLLOWING:

1. GROUNDING SYSTEM INSTALLATION PRIOR TO EARTH CONCEALMENT DOCUMENTED WITH DIGITAL PHOTOGRAPHS BY CONTRACTOR, APPROVED BY A&E OR SPRINT REPRESENTATIVE.
2. FORMING FOR CONCRETE AND REBAR PLACEMENT PRIOR TO POUR DOCUMENTED WITH DIGITAL PHOTOGRAPHS BY CONTRACTOR, APPROVED BY A&E OR SPRINT REPRESENTATIVE.
3. COMPACTION OF BACKFILL MATERIALS; AGGREGATE BASE FOR ROADS, PADS, AND ANCHORS; ASPHALT PAVING; AND SHAFT BACKFILL FOR CONCRETE AND WOOD POLES, BY INDEPENDENT THIRD PARTY AGENCY.
4. PRE- AND POST-CONSTRUCTION ROOFTOP AND STRUCTURAL INSPECTIONS ON EXISTING FACILITIES.
5. TOWER ERECTION SECTION STACKING AND PLATFORM ATTACHMENT DOCUMENTED BY DIGITAL PHOTOGRAPHS BY THIRD PARTY AGENCY.
6. ANTENNA AZIMUTH , DOWN TILT AND PER SUNLIGHT TOOL SUNSIGHT INSTRUMENTS - ANTENNALIGN ALIGNMENT TOOL (AAT)

PLANS PREPARED FOR:

Sprint

PLANS PREPARED BY:

INFINIGY
FROM ZERO TO INFINIGY
the solutions are endless
1033 Watervliet Shaker Rd | Albany, NY 12205
Phone: 518-690-0790 | Fax: 518-690-0793
www.infinigy.com
JOB NUMBER 526-104

PROJECT MANAGER:

AIROSMITH DEVELOPMENT
32 CLINTON ST.
SARATOGA SPRINGS, NY 12866
OFFICE#. (518) 306-3740

ENGINEERING LICENSE:

DRAWING NOTICE:

REVISIONS:

DESCRIPTION	DATE	BY	REV.
ISSUED FOR PERMIT	12/27/17	JDL	0

SITE NAME:

SNET - TOLLAND

SITE NUMBER:

CT03XC207

SITE ADDRESS:

1 EAGLE HILL
TOLLAND, CT 06084

SHEET DESCRIPTION:

SPRINT SPECIFICATIONS

SHEET NUMBER:

SP-2

CONTINUE FROM SP-2

7. VERIFICATION DOCUMENTED WITH THE ANTENNA CHECKLIST REPORT, BY A&E, SITE DEVELOPMENT REP, OR RF REP.
8. FINAL INSPECTION CHECKLIST AND HANDOFF WALK (HOC.). SIGNED FORM SHOWING ACCEPTANCE BY FIELD OPS IS TO BE UPLOADED INTO SMS.
9. COAX SWEEP AND FIBER TESTING DOCUMENTS SUBMITTED VIA SMS FOR RF APPROVAL.
10. SCAN–ABLE BARCODE PHOTOGRAPHS OF TOWER TOP AND INACCESSIBLE SERIALIZED EQUIPMENT
11. ALL AVAILABLE JURISDICTIONAL INFORMATION
12. PDF SCAN OF REDLINES PRODUCED IN FIELD

C. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN SITE INSPECTION ACTIVITIES AND/OR AS A RESULT OF TESTING.

D. CONSTRUCTION INSPECTIONS AND CORRECTIVE MEASURES SHALL BE DOCUMENTED BY THE CONTRACTOR WITH WRITTEN REPORTS AND PHOTOGRAPHS. PHOTOGRAPHS MUST BE DIGITAL AND OF SUFFICIENT QUALITY TO CLEARLY SHOW THE SITE CONSTRUCTION. PHOTOGRAPHS MUST CLEARLY IDENTIFY THE PHOTOGRAPHED ITEM AND BE LABELED WITH THE SITE CASCADE NUMBER, SITE NAME, DESCRIPTION, AND DATE.

3.4 DELIVERABLES: TEST AND INSPECTION REPORTS AND CLOSEOUT DOCUMENTATION SHALL BE UPLOADED TO THE SMS AND/OR FORWARDED TO SPRINT FOR INCLUSION INTO THE PERMANENT SITE FILES.

A. THE FOLLOWING TEST AND INSPECTION REPORTS SHALL BE PROVIDED AS APPLICABLE.

1. CONCRETE MIX AND CYLINDER BREAK REPORTS.
2. STRUCTURAL BACKFILL COMPACTION REPORTS.
3. SITE RESISTANCE TO EARTH TEST.
4. ANTENNA AZIMUTH AND DOWN TILT VERIFICATION
5. TOWER ERECTION INSPECTIONS AND MEASUREMENTS DOCUMENTING TOWER INSTALLED PER SUPPLIER'S REQUIREMENTS AND THE APPLICABLE SECTIONS HEREIN.
6. COAX CABLE SWEEP TESTS PER COMPANY'S "ANTENNA LINE ACCEPTANCE STANDARDS".

B. REQUIRED CLOSEOUT DOCUMENTATION INCLUDES THE FOLLOWING;

1. TEST WELLS AND TRENCHES: PHOTOGRAPHS OF ALL TEST WELLS; PHOTOGRAPHS SHOWING ALL OPEN EXCAVATIONS AND TRENCHING PRIOR TO BACKFILLING SHOWING A TAPE MEASURE VISIBLE IN THE EXCAVATIONS INDICATING DEPTH.
2. CONDUITS, CONDUCTORS AND GROUNDING: PHOTOGRAPHS SHOWING TYPICAL INSTALLATION OF CONDUCTORS AND CONNECTORS; PHOTOGRAPHS SHOWING TYPICAL BEND RADIUS OF INSTALLED GROUND WIRES AND GROUND ROD SPACING;
3. CONCRETE FORMS AND REINFORCING: CONCRETE FORMING AT TOWER AND EQUIPMENT/SHELTER PAD/FOUNDATIONS – PHOTOGRAPHS SHOWING ALL REINFORCING STEEL, UTILITY AND CONDUIT STUB OUTS; PHOTOGRAPHS SHOWING CONCRETE POUR OF SHELTER SLAB/FOUNDATION, TOWER FOUNDATION AND GUY ANCHORS WITH VIBRATOR IN USE; PHOTOGRAPHS SHOWING EACH ANCHOR ON GUYED TOWERS, BEFORE CONCRETE POUR.
4. TOWER, ANTENNAS AND MAINLINE: INSPECTION AND PHOTOGRAPHS OF SECTION STACKING; INSPECTION AND PHOTOGRAPHS OF PLATFORM COMPONENT ATTACHMENT POINTS; PHOTOGRAPHS OF TOWER TOP GROUNDING; PHOTOS OF TOWER COAX LINE COLOR CODING AT THE TOP AND AT GROUND LEVEL; INSPECTION AND PHOTOGRAPHS OF OPERATIONAL OF TOWER LIGHTING, AND PLACEMENT OF FAA REGISTRATION SIGN; PHOTOGRAPHS SHOWING ADDITIONAL GROUNDING POINTS FOR TOWERS GREATER THAN 200 FEET.; PHOTOS OF ANTENNA GROUND BAR, EQUIPMENT GROUND BAR, AND MASTER GROUND BAR; PHOTOS OF GPS ANTENNA(S); PHOTOS OF EACH SECTOR OF ANTENNAS; ONE PHOTOGRAPH LOOKING AT THE SECTOR AND ONE FROM BEHIND SHOWING THE PROJECTED COVERAGE AREA; PHOTOS OF COAX WEATHERPROOFING – TOP AND BOTTOM; PHOTOS OF COAX GROUNDING––TOP AND BOTTOM; PHOTOS OF ANTENNA AND MAST GROUNDING; PHOTOS OF COAX CABLE ENTRY INTO SHELTER; PHOTOS OF PLATFORM MECHANICAL CONNECTIONS TO TOWER/MONOPOLE.
5. ROOF TOPS: PRE–CONSTRUCTION AND POST–CONSTRUCTION VISUAL INSPECTION AND PHOTOGRAPHS OF THE ROOF AND INTERIOR TO DETERMINE AND DOCUMENT CONDITIONS; ROOF TOP CONSTRUCTION INSPECTIONS AS REQUIRED BY THE JURISDICTION; PHOTOGRAPHS OF CABLE TRAY AND/OR ICE BRIDGE; PHOTOGRAPHS OF DOGHOUSE/CABLE EXIT FROM ROOF;
6. SITE LAYOUT – PHOTOGRAPHS OF THE OVERALL COMPOUND, INCLUDING EQUIPMENT PLATFORM FROM ALL FOUR CORNERS.
7. FINISHED UTILITIES: CLOSE–UP PHOTOGRAPHS OF THE PPC BREAKER PANEL; CLOSE–UP PHOTOGRAPH OF THE INSIDE OF THE TELCO PANEL AND NIU; CLOSE–UP PHOTOGRAPH OF THE POWER METER AND DISCONNECT; PHOTOS OF POWER AND TELCO ENTRANCE TO COMPANY ENCLOSURE; PHOTOGRAPHS AT METER BOX AND/OR FACILITY DISTRIBUTION PANEL.
8. REQUIRED MATERIALS CERTIFICATIONS: CONCRETE MIX DESIGNS; MILL CERTIFICATION FOR ALL REINFORCING AND STRUCTURAL STEEL; AND ASPHALT PAVING MIX DESIGN.
9. ANY AND ALL SUBMITTALS BY THE JURISDICTION OR COMPANY.

SECTION 01 400 – SUBMITTALS & TESTS

PART 1 – GENERAL

1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

1.2 RELATED DOCUMENTS:

A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.

B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.

PART 2 – PRODUCTS (NOT USED)

PART 3 – EXECUTION

3.1 WEEKLY REPORTS:

A. CONTRACTOR SHALL PROVIDE SPRINT WITH WEEKLY REPORTS SHOWING PROJECT STATUS. THIS STATUS REPORT FORMAT WILL BE PROVIDED TO THE CONTRACTOR BY SPRINT. THE REPORT WILL CONTAIN SITE ID NUMBER, THE MILESTONES FOR EACH SITE, INCLUDING THE BASELINE DATE, ESTIMATED COMPLETION DATE AND ACTUAL COMPLETION DATE.

B. REPORT INFORMATION WILL BE TRANSMITTED TO SPRINT VIA ELECTRONIC MEANS AS REQUIRED. THIS INFORMATION WILL PROVIDE A BASIS FOR PROGRESS MONITORING AND PAYMENT.

3.2 PROJECT CONFERENCE CALLS:

A. SPRINT MAY HOLD WEEKLY PROJECT CONFERENCE CALLS. CONTRACTOR WILL BE REQUIRED TO COMMUNICATE SITE STATUS, MILESTONE COMPLETIONS AND UPCOMING MILESTONE PROJECTIONS, AND ANSWER ANY OTHER SITE STATUS QUESTIONS AS NECESSARY.

3.3 PROJECT TRACKING IN SMS:

A. CONTRACTOR SHALL PROVIDE SCHEDULE UPDATES AND PROJECTIONS IN THE SMS SYSTEM ON A WEEKLY BASIS.

3.4 ADDITIONAL REPORTING:

A. ADDITIONAL OR ALTERNATE REPORTING REQUIREMENTS MAY BE ADDED TO THE REPORT AS DETERMINED TO BE REASONABLY NECESSARY BY COMPANY.

3.5 PROJECT PHOTOGRAPHS:

A. FILE DIGITAL PHOTOGRAPHS OF COMPLETED SITE IN JPEG FORMAT IN THE SMS PHOTO LIBRARY FOR THE RESPECTIVE SITE. PHOTOGRAPHS SHALL BE CLEARLY LABELED WITH SITE NUMBER, NAME AND DESCRIPTION, AND SHALL INCLUDE AT A MINIMUM THE FOLLOWING AS APPLICABLE:

1. 1SHELTER AND TOWER OVERVIEW.
2. TOWER FOUNDATION(S) – FORMS AND STEEL BEFORE POUR (EACH ANCHOR ON GUYED TOWERS).
3. TOWER FOUNDATION(S) POUR WITH VIBRATOR IN USE (EACH ANCHOR ON GUYED TOWERS).
4. TOWER STEEL AS BEING INSTALLED INTO HOLE (SHOW ANCHOR STEEL ON GUYED TOWERS).
5. PHOTOS OF TOWER SECTION STACKING.
6. CONCRETE TESTING / SAMPLES.
7. PLACING OF ANCHOR BOLTS IN TOWER FOUNDATION.
8. BUILDING/WATER TANK FROM ROAD FOR TENANT IMPROVEMENTS OR COMMENTS.
9. SHELTER FOUNDATION––FORMS AND STEEL BEFORE POURING.
10. SHELTER FOUNDATION POUR WITH VIBRATOR IN USE.
11. COAX CABLE ENTRY INTO SHELTER.
12. PLATFORM MECHANICAL CONNECTIONS TO TOWER/MONOPOLE.
13. ROOFTOP PRE AND POST CONSTRUCTION PHOTOS TO INCLUDE PENETRATIONS AND INTERIOR CEILING.
14. PHOTOS OF TOWER TOP COAX LINE COLOR CODING AND COLOR CODING AT GROUND LEVEL.
15. PHOTOS OF ALL APPROPRIATE COMPANY OR REGULATORY SIGNAGE.
16. PHOTOS OF EQUIPMENT BOLT DOWN INSIDE SHELTER.
17. POWER AND TELCO ENTRANCE TO COMPANY ENCLOSURE AND POWER AND TELCO SUPPLY LOCATIONS INCLUDING METER/DISCONNECT.
18. ELECTRICAL TRENCH(S) WITH ELECTRICAL / CONDUIT BEFORE BACKFILL.
19. ELECTRICAL TRENCH(S) WITH FOIL–BACKED TAPE BEFORE FURTHER BACKFILL.
20. TELCO TRENCH WITH TELEPHONE / CONDUIT BEFORE BACKFILL.
21. TELCO TRENCH WITH FOIL–BACKED TAPE BEFORE FURTHER BACKFILL.
22. SHELTER GROUND–RING TRENCH WITH GROUND–WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADII).
23. TOWER GROUND–RING TRENCH WITH GROUND–WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADII).
24. FENCE GROUND–RING TRENCH WITH GROUND–WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADII).
25. ALL BTS GROUND CONNECTIONS.
26. ALL GROUND TEST WELLS.
27. ANTENNA GROUND BAR AND EQUIPMENT GROUND BAR.
28. ADDITIONAL GROUNDING POINTS ON TOWERS ABOVE 200'.
29. HVAC UNITS INCLUDING CONDENSERS ON SPLIT SYSTEMS.
30. GPS ANTENNAS.
31. CABLE TRAY AND/OR WAVEGUIDE BRIDGE.
32. DOGHOUSE/CABLE EXIT FROM ROOF.
33. EACH SECTOR OF ANTENNAS; ONE PHOTOGRAPH LOOKING AT THE SECTOR AND ONE FROM BEHIND SHOWING THE PROJECTED COVERAGE AREA.
34. MASTER BUS BAR.
35. TELCO BOARD AND NIU.
36. ELECTRICAL DISTRIBUTION WALL.
37. CABLE ENTRY WITH SURGE SUPPRESSION.
38. ENTRANCE TO EQUIPMENT ROOM.
39. COAX WEATHERPROOFING–TOP AND BOTTOM OF TOWER.
40. COAX GROUNDING –TOP AND BOTTOM OF TOWER.
41. ANTENNA AND MAST GROUNDING.
42. LANDSCAPING – WHERE APPLICABLE.

3.6 FINAL PROJECT ACCEPTANCE: COMPLETE ALL REQUIRED REPORTING TASKS PER CONTRACT, CONTRACT DOCUMENTS OR THE SPRINT INTEGRATED CONSTRUCTION STANDARDS FOR WIRELESS SITES AND UPLOAD INTO SITERRA.

PLANS PREPARED FOR:

Sprint

PLANS PREPARED BY:
INFINIGY
FROM ZERO TO INFINIGY
the solutions are endless
1033 Watervliet Shaker Rd | Albany, NY 12205
Phone: 518-690-0790 | Fax: 518-690-0793
www.infinigy.com
JOB NUMBER 526-104

PROJECT MANAGER:
AIROSMITH DEVELOPMENT
32 CLINTON ST.
SARATOGA SPRINGS, NY 12866
OFFICE#. (518) 306-3740

ENGINEERING LICENSE:

REVISIONS:

DESCRIPTION	DATE	BY	REV.
ISSUED FOR PERMIT	12/27/17	JDL	0

SITE NAME:
SNET - TOLLAND

SITE NUMBER:
CT03XC207

SITE ADDRESS:
1 EAGLE HILL
TOLLAND, CT 06084

SHEET DESCRIPTION:
SPRINT SPECIFICATIONS

SHEET NUMBER:
SP-3



INFORMATION CONTAINED WITHIN DRAWINGS ARE BASED ON PROVIDED INFORMATION AND ARE NOT THE RESULT OF A FIELD SURVEY.

N

GRAPHIC SCALE:
20' 10' 0 10' 20'
SCALE (11x17): 1" = 20'-0"
SCALE (22x34): 1" = 10'-0"

OVERALL SITE PLAN | SCALE: AS NOTED | 1



GRAPHIC SCALE:
4' 2' 0 2' 4'
SCALE (11x17): 1" = 4'-0"
SCALE (22x34): 1" = 2'-0"

SPRINT EQUIPMENT PLAN | SCALE: AS NOTED | 2

PLANS PREPARED FOR:
Sprint

PLANS PREPARED BY:
INFINIGY
FROM ZERO TO INFINIGY
the solutions are endless
1033 Watervliet Shaker Rd | Albany, NY 12205
Phone: 518-690-0790 | Fax: 518-690-0793
www.infinigy.com
JOB NUMBER 526-104

PROJECT MANAGER:
AIROSMITH DEVELOPMENT
32 CLINTON ST.
SARATOGA SPRINGS, NY 12866
OFFICE# (518) 306-3740

ENGINEERING LICENSE:
STATE OF CONNECTICUT
JOHN S. STEVENS
No. 24108
JAN. 04 2018
LICENSED PROFESSIONAL ENGINEER

DRAWING NOTICE:
THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV.
ISSUED FOR PERMIT	12/27/17	JDL	0

SITE NAME:
SNET - TOLLAND

SITE NUMBER:
CT03XC207

SITE ADDRESS:
1 EAGLE HILL
TOLLAND, CT 06084

SHEET DESCRIPTION:
SITE PLAN

SHEET NUMBER:
A-1

NOTE:
INFINIGY ENGINEERING HAS NOT EVALUATED THE EXISTING STRUCTURE FOR THIS SITE, AND ASSUMES NO RESPONSIBILITY FOR ITS STRUCTURAL INTEGRITY. REFER TO STRUCTURAL ANALYSIS BY OTHERS PRIOR TO ANY CONSTRUCTION.

NOTE:
SEE DETAIL 2 ON A-3 FOR ANTENNA LAYOUT



NOTE:
STRUCTURAL ANALYSIS COMPLETED BY AMERICAN TOWER CORPORATION. FOR ADDITIONAL INFORMATION SEE REPORT TITLED: "STRUCTURAL ANALYSIS REPORT, ATC SITE NUMBER: 302495", DATED: "NOVEMBER 15, 2017". ACCORDING TO RESULTS OF STRUCTURAL MODIFICATION REPORT, THE STRUCTURE DOES HAVE SUFFICIENT CAPACITY TO SUPPORT THE PROPOSED LOADING.

- ANTENNA AND RRH SUPPORT EVALUATION COMPLETED BY INFINIGY. FOR ADDITIONAL INFORMATION SEE REPORT TITLED: "SPRINT PROJECT DO MACRO MOUNT UPGRADE ANALYSIS REPORT", DATED: "DECEMBER 27, 2017". ACCORDING TO THE RESULTS OF REVIEW, THE ANTENNA AND RRH SUPPORTS ARE NOT ADEQUATE TO SUPPORT THE PROPOSED LOADING. CONTRACTOR TO INSTALL NEW L1¾ x 1¾ x ¼ ANGLES TO EXISTING L1¾ x 1¾ x ¼ ANGLES WITH (4) ½" ø A325X BOLTS TO CREATE DOUBLE ANGLES.

TOWER ELEVATION | NO SCALE | 1

SITE LOADING CHART

SECTOR	EXISTING/ PROPOSED	ANTENNA MODEL #	VENDOR	AZIMUTH	QTY.	REMAIN/ REMOVED	RRH (QTY/MODEL)	CABLE	CABLE LENGTH	RAD CENTER
ALPHA	PROPOSED	KMW ETCR-654L12H6	KMW	45°	1	–	(2) 800 MHZ 2X50W RRH W/ FILTER	SEE SHEET A-5 DETAIL 1	±168'*	±133' AGL
	EXISTING	980H65T2E-M	DECIBEL	30°	1	REMAIN	(1) TD-RRH8X20-25 W/ SOLAR SHIELD	EXISTING COAX		
	EXISTING	DB980H90A-KL	DECIBEL	30°	1	REMOVE	(1) 1900 MHz 4X45 RRH	EXISTING COAX		
BETA	PROPOSED	KMW ETCR-654L12H6	KMW	150°	1	–	(2) 800 MHZ 2X50W RRH W/ FILTER	SEE SHEET A-5 DETAIL 1		±133' AGL
	EXISTING	980H65T2E-M	DECIBEL	150°	1	REMAIN	(1) TD-RRH8X20-25 W/ SOLAR SHIELD	EXISTING COAX		
	EXISTING	DB980H90A-KL	DECIBEL	150°	1	REMOVE	(1) 1900 MHz 4X45 RRH	EXISTING COAX		
GAMMA	PROPOSED	KMW ETCR-654L12H6	KMW	260°	1	–	(2) 800 MHZ 2X50W RRH W/ FILTER	SEE SHEET A-5 DETAIL 1		±133' AGL
	EXISTING	980H65T2E-M	DECIBEL	270°	1	REMAIN	(1) TD-RRH8X20-25 W/ SOLAR SHIELD	EXISTING COAX		
	EXISTING	DB980H90A-KL	DECIBEL	270°	1	REMOVE	(1) 1900 MHz 4X45 RRH	EXISTING COAX		

PROJECT SCOPE:

REMOVE: (3) PANEL ANTENNAS INSTALL: (3) PANEL ANTENNAS AND (9) RRH'S RELOCATE: (3) EXISTING RRH'S

* PROPOSED CABLE LENGTH WAS DETERMINED USING THE SUM OF THE RAD CENTER OF ANTENNAS, AND DISTANCE FROM EXISTING EQUIPMENT AREA TO TOWER BASE WITH AN ADDITIONAL 20' BUFFER. LENGTH TO BE VERIFIED IN FIELD PRIOR TO ORDERING MATERIALS.

SITE LOADING CHART | NO SCALE | 2

DETAIL NOT USED | NO SCALE | 3

PLANS PREPARED FOR:
Sprint

PLANS PREPARED BY:
INFINIGY
FROM ZERO TO INFINIGY
the solutions are endless
1033 Watervliet Shaker Rd | Albany, NY 12205
Phone: 518-690-0790 | Fax: 518-690-0793
www.infinigy.com
JOB NUMBER 526-104

PROJECT MANAGER:
AIROSMITH DEVELOPMENT
32 CLINTON ST.
SARATOGA SPRINGS, NY 12866
OFFICE#. (518) 306-3740

ENGINEERING LICENSE:
STATE OF CONNECTICUT
JOHN S. STEVENS
JAN 09 2018
No. 24705
LICENSED PROFESSIONAL ENGINEER

REVISIONS:

DESCRIPTION	DATE	BY	REV.
ISSUED FOR PERMIT	12/27/17	JDL	0

SITE NAME:
SNET - TOLLAND

SITE NUMBER:
CT03XC207

SITE ADDRESS:
1 EAGLE HILL
TOLLAND, CT 06084

SHEET DESCRIPTION:
TOWER ELEVATION

SHEET NUMBER:
A-2



EXISTING ANTENNA & RRH LAYOUT | NO SCALE | 1

THE CONFIGURATION PLANS ARE BASED ON PROVIDED INFORMATION AND ARE FOR CONCEPTUAL PURPOSES ONLY. CONTRACTOR TO VERIFY FIELD CONDITIONS PRIOR TO CONSTRUCTION.



NOTE:
JUMPERS FROM 2.5 RRH TO THE 2.5 ANTENNA CANNOT EXCEED 15 FEET

FINAL ANTENNA & RRH LAYOUT | NO SCALE | 2



NOTE:
CONTRACTOR TO POSITION RRH ON MOUNT BEHIND ANTENNA SUCH THAT THE RRH DOES NOT INTERFERE WITH THE EXISTING PLATFORM/T-ARM MOUNTING HARDWARE.

NOTE:
THE DIAGRAM IS FOR CONCEPTUAL PURPOSES ONLY. CONTRACTOR IS TO REFER TO PASSING STRUCTURAL ANALYSIS FOR ANTENNA AND RRH MOUNTING DETAILS

NOTES:

1. CUT DC CONDUCTORS TO LENGTH.
2. COIL FIBER CABLE AND SECURE AT SIDE OF RRH.
3. DO NO EXCEED BEND RADIUS.

TYPICAL ANTENNA & RRH MOUNTING DETAILS | NO SCALE | 3



NOTE:
CONTRACTOR TO POSITION RRH ON MOUNT BEHIND ANTENNA SUCH THAT THE RRH DOES NOT INTERFERE WITH THE EXISTING PLATFORM/T-ARM MOUNTING HARDWARE.

NOTE:
THE DIAGRAM IS FOR CONCEPTUAL PURPOSES ONLY. CONTRACTOR IS TO REFER TO PASSING STRUCTURAL ANALYSIS FOR ANTENNA AND RRH MOUNTING DETAILS

NOTES:

1. CUT DC CONDUCTORS TO LENGTH.
2. COIL FIBER CABLE AND SECURE AT SIDE OF RRH.
3. DO NO EXCEED BEND RADIUS.

TYPICAL ANTENNA & RRH MOUNTING DETAILS | NO SCALE | 4

PLANS PREPARED FOR:
Sprint

PLANS PREPARED BY:
INFINIGY
FROM ZERO TO INFINIGY
the solutions are endless
1033 Watervliet Shaker Rd | Albany, NY 12205
Phone: 518-690-0790 | Fax: 518-690-0793
www.infinigy.com
JOB NUMBER 526-104

PROJECT MANAGER:
AIROSMITH DEVELOPMENT
32 CLINTON ST.
SARATOGA SPRINGS, NY 12866
OFFICE#. (518) 306-3740

ENGINEERING LICENSE:
STATE OF CONNECTICUT
JOHN S. STEVENS
No. 24705
LICENSED PROFESSIONAL ENGINEER
JAN 19 2018

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR PERMIT	12/27/17	JDL	0

SITE NAME:
SNET - TOLLAND

SITE NUMBER:
CT03XC207

SITE ADDRESS:
1 EAGLE HILL
TOLLAND, CT 06084

SHEET DESCRIPTION:
ANTENNA LAYOUT & MOUNTING DETAILS

SHEET NUMBER:
A-3

RRH: ALCATEL LUCENT TD-RRH8X20

COLOR: LIGHT GREY
WEIGHT: 70 LBS.



SIDE VIEW



FRONT VIEW



PLAN VIEW

NOTES

COMPLY WITH MANUFACTURERS INSTRUCTIONS TO ENSURE THAT ALL RRH'S RECEIVE ELECTRICAL POWER WITHIN 24 HOURS OF BEING REMOVED FROM THE MANUFACTURER'S PACKAGING. DO NOT OPEN RRH PACKAGES IN THE RAIN.

2.5 RRH'S | NO SCALE | 1

RRH: ALCATEL LUCENT 1900 MHz

COLOR: LIGHT GREY
WEIGHT: 70 LBS.
(INCLUDING OPTIONAL SOLAR SHIELD)



FRONT VIEW



SIDE VIEW



TOP VIEW

EXISTING 1900 MHz RRH | NO SCALE | 2

ANTENNA KMW ETCR-654L12H6

RADOME MATERIAL:	ASA
RADOME COLOR:	LIGHT GREY
DIMENSIONS, HxWxD.in(mim):	84.9"x21.0"x6.3" (2156x533x160mm)
WEIGHT:	84.9 lbs
CONNECTORS:	(8) 7/16" DIN FEMALE (8) MINI DIN FEMALE (1) N TYPE(CAL PORT, FEMALE)



PLAN VIEW

SIDE VIEW



FRONT VIEW

TRIBAND ANTENNA | NO SCALE | 3

RRH: ALCATEL LUCENT RRH 800 MHz 2x50W

COLOR: LIGHT GREY
WEIGHT: 53 LBS.

NOTES

COMPLY WITH MANUFACTURERS INSTRUCTIONS TO ENSURE THAT ALL RRH'S RECEIVE ELECTRICAL POWER WITHIN 24 HOURS OF BEING REMOVED FROM THE MANUFACTURER'S PACKAGING. DO NOT OPEN RRH PACKAGES IN THE RAIN.



SIDE VIEW



FRONT VIEW



PLAN VIEW

800 MHz RRH | NO SCALE | 4

PLANS PREPARED FOR:
Sprint

PLANS PREPARED BY:
INFINIGY
FROM ZERO TO INFINIGY
the solutions are endless
1033 Watervliet Shaker Rd | Albany, NY 12205
Phone: 518-690-0790 | Fax: 518-690-0793
www.infinigy.com
JOB NUMBER 526-104

PROJECT MANAGER:
AIROSMITH DEVELOPMENT
32 CLINTON ST.
SARATOGA SPRINGS, NY 12866
OFFICE#. (518) 306-3740

ENGINEERING LICENSE:
STATE OF CONNECTICUT
JOHN S. STEVENS
No. 24705
LICENSED PROFESSIONAL ENGINEER
DEC 08 2017

DRAWING NOTICE:

REVISIONS:

DESCRIPTION	DATE	BY	REV.
ISSUED FOR PERMIT	12/27/17	JDL	0

SITE NAME:
SNET - TOLLAND

SITE NUMBER:
CT03XC207

SITE ADDRESS:
1 EAGLE HILL
TOLLAND, CT 06084

SHEET DESCRIPTION:
EQUIPMENT & MOUNTING DETAILS

SHEET NUMBER:
A-4

RFS HYBRIFLEX RISER CABLE SCHEDULE

Fiber Only (Existing DC Power)	**Hybrid cable** MN: HB058-M12-050F 12x multi-mode fiber pairs, Top: Outdoor protected connectors, Bottom: LC Connectors, 5/8 cable, 50 ft	50 ft
	MN: HB058-M12-075F	75 ft
	MN: HB058-M12-100F	100 ft
	MN: HB058-M12-125F	125 ft
	MN: HB058-M12-150F	150 ft
	MN: HB058-M12-175F	175 ft
	MN: HB058-M12-200F	200 ft
8 AWG Power	**Hybrid cable** MN: HB114-08U3M12-050F 3x 8 AWG power pairs, 12x multi-mode fiber pairs, Outdoor rated connectors & LC Connectors, 1 1/4 cable, 50 ft	50 ft
	MN: HB114-08U3M12-075F	75 ft
	MN: HB114-08U3M12-100F	100 ft
	MN: HB114-08U3M12-125F	125 ft
	MN: HB114-08U3M12-150F	150 ft
	MN: HB114-08U3M12-175F	175 ft
	MN: HB114-08U3M12-200F	200 ft (4)*
6 AWG Power	**Hybrid cable** MN: HB114-13U3M12-225F 3x 6 AWG power pair, 12x multi-mode fiber pairs, Outdoor rated connectors & LC Connectors, 1 1/4 cable, 225 ft	225 ft
	MN: HB114-13U3M12-250F	250 ft
	MN: HB114-13U3M12-275F	275 ft
	MN: HB114-13U3M12-300F	300 ft
4 AWG Power	**Hybrid cable** MN: HB114-21U3M12-325F 3x 4 AWG power pair, 12x multi-mode fiber pairs, Outdoor rated connectors & LC Connectors, 1 1/4 cable, 325 ft	325 ft
	MN: HB114-21U3M12-350F	350 ft
	MN: HB114-21U3M12-375F	375 ft

RFS HYBRIFLEX JUMPER CABLE SCHEDULE

Fiber Only	**Hybrid Jumper cable** MN: HBF012-M3-5F1 5 ft, 3x multi-mode fiber pairs, Outdoor & LC connectors, 1/2 cable	5 ft
	MN: HBF012-M3-10F1	10 ft
	MN: HBF012-M3-15F1	15 ft
	MN: HBF012-M3-20F1	20 ft
	MN: HBF012-M3-25F1	25 ft
	MN: HBF012-M3-30F1	30 ft
8 AWG Power	**Hybrid Jumper cable** MN: HBF058-08U1M3-5F1 5 ft, 1x 8 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 5/8 cable	5 ft
	MN: HBF058-08U1M3-10F1	10 ft
	MN: HBF058-08U1M3-15F1	15 ft
	MN: HBF058-08U1M3-20F1	20 ft
	MN: HBF058-08U1M3-25F1	25 ft
	MN: HBF058-08U1M3-30F1	30 ft
6 AWG Power	**Hybrid Jumper cable** MN: HBF058-13U1M3-5F1 5 ft, 1x 6 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 5/8 cable	5 ft
	MN: HBF058-13U1M3-10F1	10 ft
	MN: HBF058-13U1M3-15F1	15 ft
	MN: HBF058-13U1M3-20F1	20 ft
	MN: HBF058-13U1M3-25F1	25 ft
	MN: HBF058-13U1M3-30F1	30 ft
4 AWG Power	**Hybrid Jumper cable** MN: HBF078-21U1M3-5F1 5 ft, 1x 4 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 7/8 cable	5 ft
	MN: HBF078-21U1M3-10F1	10 ft
	MN: HBF078-21U1M3-15F1	15 ft
	MN: HBF078-21U1M3-20F1	20 ft
	MN: HBF078-21U1M3-25F1	25 ft
	MN: HBF078-21U1M3-30F1	30 ft

* PROPOSED CABLE LENGTH WAS DETERMINED USING THE SUM OF THE RAD CENTER OF ANTENNAS, AND DISTANCE FROM EXISTING EQUIPMENT AREA TO TOWER BASE WITH AN ADDITIONAL 20' BUFFER. LENGTH TO BE VERIFIED IN FIELD PRIOR TO ORDERING MATERIALS.

NOTE:
SPRINT CM TO CONFIRM HYBRID OR FIBER RISER CABLE AND HYBRID OR FIBER JUMPER CABLE MODEL NUMBERS IF HYBRID CABLES ARE REQUIRED BEFORE PREPARING BOM.



4 AWG



8 & 6 AWG



FIBER ONLY

800/1900/2500 CROSS SECTION DATA — NO SCALE — 1



FIBER JUNCTION BOX & PENETRATION — NO SCALE — 2



FRONT VIEW

NEW EQUIPMENT IN EXISTING CABINET — NO SCALE — 3

PLANS PREPARED FOR:
Sprint

PLANS PREPARED BY:

INFINIGY
FROM ZERO TO INFINIGY
the solutions are endless
1033 Watervliet Shaker Rd | Albany, NY 12205
Phone: 518-690-0790 | Fax: 518-690-0793
www.infinigy.com

JOB NUMBER 526-104

PROJECT MANAGER:

AIROSMITH DEVELOPMENT
32 CLINTON ST.
SARATOGA SPRINGS, NY 12866
OFFICE#. (518) 306-3740

ENGINEERING LICENSE:
STATE OF CONNECTICUT
JOHN S. STEVENS
No. 24705
LICENSED PROFESSIONAL ENGINEER
JAN 4 2018

DRAWING NOTICE:

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR PERMIT	12/27/17	JDL	0

SITE NAME:
SNET - TOLLAND

SITE NUMBER:
CT03XC207

SITE ADDRESS:
1 EAGLE HILL
TOLLAND, CT 06084

SHEET DESCRIPTION:
CIVIL DETAILS

SHEET NUMBER:
A-5

KMW 16 Port Nokia-A RRH 800, 1900, and 2500 (Sprint Scenario 4)



Not to Scale

Each Sector is Equipped with:
Two 800 RRH
One 1900 RRHs
One 2500 RRH

CPRI Block Connections for Sprint Scenario 4



Not to Scale

PLUMBING DIAGRAM | NO SCALE | 1

PLANS PREPARED FOR:
Sprint

PLANS PREPARED BY:
INFINIGY
FROM ZERO TO INFINIGY
the solutions are endless
1033 Watervliet Shaker Rd | Albany, NY 12205
Phone: 518-690-0790 | Fax: 518-690-0793
www.infinigy.com
JOB NUMBER 526-104

PROJECT MANAGER:
AIROSMITH DEVELOPMENT
32 CLINTON ST.
SARATOGA SPRINGS, NY 12866
OFFICE#. (518) 306-3740

ENGINEERING LICENSE:
STATE OF CONNECTICUT
JOHN S. STEVENS
JAN 0 2 2018
No. 24705
LICENSED PROFESSIONAL ENGINEER

DRAWING NOTICE:

REVISIONS:

DESCRIPTION	DATE	BY	REV.
ISSUED FOR PERMIT	12/27/17	JDL	0

SITE NAME:
SNET - TOLLAND

SITE NUMBER:
CT03XC207

SITE ADDRESS:
1 EAGLE HILL
TOLLAND, CT 06084

SHEET DESCRIPTION:
PLUMBING DIAGRAM

SHEET NUMBER:
A-6



RRH TO DISTRIBUTION BOX POWER CONNECTIVITY

NO SCALE | 1

LEGEND:

- EXISTING GROUND RING
- ■ CADWELD CONNECTION (EXOTHERMIC WELD)
- ▲ MECHANICAL CONNECTION
- ⊗ GROUND ROD
- ● CABLE GROUND KIT



TYPICAL ANTENNA GROUNDING PLAN | NO SCALE | 2



NOTE:
DEPICTION IS FOR CONCEPTUAL PURPOSES ONLY. CONTRACTOR IS TO FIELD VERIFY PRIOR TO CONSTRUCTION

TYPICAL EQUIPMENT GROUNDING PLAN (ELEVATION) | NO SCALE | 3

PLANS PREPARED FOR:
Sprint

PLANS PREPARED BY:
INFINIGY
FROM ZERO TO INFINIGY
the solutions are endless
1033 Watervliet Shaker Rd | Albany, NY 12205
Phone: 518-690-0790 | Fax: 518-690-0793
www.infinigy.com
JOB NUMBER 526-104

PROJECT MANAGER:
AIROSMITH DEVELOPMENT
32 CLINTON ST.
SARATOGA SPRINGS, NY 12866
OFFICE#. (518) 306-3740

ENGINEERING LICENSE:
STATE OF CONNECTICUT
JOHN S. STEVENS
JAN 2018
NO. 24705
LICENSED PROFESSIONAL ENGINEER

REVISIONS:

DESCRIPTION	DATE	BY	REV.
ISSUED FOR PERMIT	12/27/17	JDL	0

SITE NAME:
SNET - TOLLAND

SITE NUMBER:
CT03XC207

SITE ADDRESS:
1 EAGLE HILL
TOLLAND, CT 06084

SHEET DESCRIPTION:
ELECTRICAL & GROUNDING PLAN

SHEET NUMBER:
E-1

NOTES

CG SHALL REFERENCE ALL SPECS FOR "CONNECTING THE POWER SUPPLY" OF THE NEW INSTALLATION DOCUMENTS, FOR ALL CONNECTION SPECIFICATIONS.



CIRCUIT SCHEDULE			
NO	FROM	TO	CONFIGURATION
1	UTILITY SOURCE	METER/DISCONNECT	EXISTING
2	METER/DISCONNECT	TRANSFER & LOAD CENTER	EXISTING
3	TRANSFER & LOAD CENTER	GENERATOR RECEPTACLE	EXISTING
4	TRANSFER & LOAD CENTER	EXISTING SPRINT BBU CABINET	EXISTING
5	TRANSFER & LOAD CENTER	EXISTING SPRINT MMBS CABINET	EXISTING

ELECTRICAL ONE–LINE DIAGRAM — NO SCALE — 1



NOTES

1. APPLY NO–OX TO LUG AND BAR CONTACT SURFACE. DO NOT COAT INLINE LUG.
2. IF STOLEN GROUND BARS ARE ENCOUNTERED, CONTACT SPRINT CM FOR REPLACEMENT THREADED ROD KIT.

INSTALLATION OF GROUNDING CONDUCTOR TO GROUNDING BAR — NO SCALE — 2



TWO HOLE LUG — NO SCALE — 3

LEGEND:

- EXISTING GROUND RING
- ■ CADWELD CONNECTION (EXOTHERMIC WELD)
- ▲ MECHANICAL CONNECTION
- ⊗ GROUND ROD
- ● CABLE GROUND KIT



GROUNDING RISER DIAGRAM — NO SCALE — 4

PLANS PREPARED FOR: Sprint

PLANS PREPARED BY:
INFINIGY
FROM ZERO TO INFINIGY
the solutions are endless
1033 Watervliet Shaker Rd | Albany, NY 12205
Phone: 518-690-0790 | Fax: 518-690-0793
www.infinigy.com
JOB NUMBER 526-104

PROJECT MANAGER:
AIROSMITH DEVELOPMENT
32 CLINTON ST.
SARATOGA SPRINGS, NY 12866
OFFICE#. (518) 306-3740

ENGINEERING LICENSE:
STATE OF CONNECTICUT
JOHN S. STEVENS
JAN 19 2018
No. 24705
LICENSED PROFESSIONAL ENGINEER

DRAWING NOTICE:

REVISIONS:

DESCRIPTION	DATE	BY	REV.
ISSUED FOR PERMIT	12/27/17	JDL	0

SITE NAME: SNET - TOLLAND

SITE NUMBER: CT03XC207

SITE ADDRESS: 1 EAGLE HILL TOLLAND, CT 06084

SHEET DESCRIPTION: ELECTRICAL & GROUNDING DETAILS

SHEET NUMBER: E-2