



**NSS** **NORTHEAST**  
SITE SOLUTIONS  
*Turnkey Wireless Development*

Northeast Site Solutions  
Denise Sabo  
4 Angela's Way, Burlington CT 06013  
203-435-3640  
denise@northeastsitesolutions.com

March 4, 2022

Members of the Siting Council  
Connecticut Siting Council  
Ten Franklin Square  
New Britain, CT 06051

RE: Tower Share Application  
425 Indian Ledge Park Road, Trumbull, CT 06611  
Latitude: 41.273302  
Longitude: -73.213094  
Site #: 881535\_Crown\_Dish

Dear Ms. Bachman:

This letter and attachments are submitted on behalf of Dish Wireless LLC. Dish Wireless LLC plans to install antennas and related equipment to the tower site located at 425 Indian Ledge Park Road, Trumbull, Connecticut.

Dish Wireless LLC proposes to install three (3) 600/1900 MHz 5G antennas and six (6) RRUs, at the 175-foot level of the existing 195-foot monopole tower, one (1) Fiber cable will also be installed. Dish Wireless LLC equipment cabinets will be placed within a 7' x 5' lease area on an existing concrete pad. Included are plans by B&T Group, dated January 26, 2022 Exhibit C. Also included is a structural analysis prepared by Crown Castle, dated May 29, 2021, confirming that the existing tower is structurally capable of supporting the proposed equipment. Attached as Exhibit D. The facility was approved by the Town of Trumbull, however the Town has been unable to locate a copy of the approval. Please see attached Exhibit A.

Please accept this letter as notification pursuant to Regulations of Connecticut State Agencies 16-50aa, of DISH WIRELESS LLC Wireless LLC intent to share a telecommunications facility pursuant to R.C.S.A. 16-50j-88. In accordance with R.C.S.A., a copy of this letter is being sent to Vicki Tesoro, First Selectman and Rob Librandi, Land Use Planner for the Town of Trumbull as well as the tower owner (Crown Castle) and property owner (Town of Trumbull).

The planned modifications of the facility fall squarely within those activities explicitly provided for in R.C.S.A. 16-50j-89.

1. The proposed modification will not result in an increase in the height of the existing structure. The top of the existing tower is 195-feet and the Dish Wireless LLC antennas will be located at a center line height of 175-feet.
2. The proposed modifications will not result in an increase of the site boundary as depicted on the attached site plan.



**NSS** **NORTHEAST**  
SITE SOLUTIONS

*Turnkey Wireless Development*

3. The proposed modifications will not increase noise levels at the facility by six decibels or more, or to levels that exceed local and state criteria. The incremental effect of the proposed changes will be negligent.

4. The operation of the proposed antennas will not increase radio frequency emissions at the facility to a level at or above the Federal Communications Commission safety standard. The combined site operations will result in a total power density of 18.77% as evidenced by Exhibit F.

Connecticut General Statutes 16-50aa indicates that the Council must approve the shared use of a telecommunications facility provided it finds the shared use is technically, legally, environmentally, and economically feasible and meets public safety concerns. As demonstrated in this letter, Dish Wireless LLC respectfully submits that the shared use of this facility satisfies these criteria.

A. Technical Feasibility. The existing monopole has been deemed structurally capable of supporting Dish Wireless LLC proposed loading. The structural analysis is included as Exhibit D.

B. Legal Feasibility. As referenced above, C.G.S. 16-50aa has been authorized to issue orders approving the shared use of an existing tower such as this support tower in Trumbull. Under the authority granted to the Council, an order of the Council approving the requested shared use would permit Dish Wireless LLC to obtain a building permit for the proposed installation. Further, a Letter of Authorization is included as Exhibit G, authorizing Dish Wireless LLC to file this application for shared use.

C. Environmental Feasibility. The proposed shared use of this facility would have a minimal environmental impact. The installation of Dish Wireless LLC equipment at the 175-foot level of the existing 195-foot tower would have an insignificant visual impact on the area around the tower. Dish Wireless LLC ground equipment would be installed within the existing facility compound. Dish Wireless LLC shared use would therefore not cause any significant alteration in the physical or environmental characteristics of the existing site. Additionally, as evidenced by Exhibit F, the proposed antennas would not increase radio frequency emissions to a level at or above the Federal Communications Commission safety standard.

D. Economic Feasibility. Dish Wireless LLC will be entering into an agreement with the owner of this facility to mutually agreeable terms. As previously mentioned, the Letter of Authorization has been provided by the owner to assist Dish Wireless LLC with this tower sharing application.

E. Public Safety Concerns. As discussed above, the tower is structurally capable of supporting Dish Wireless LLC proposed loading. Dish Wireless LLC is not aware of any public safety concerns relative to the proposed sharing of the existing tower. Dish Wireless LLC intentions of providing new and improved wireless service through the shared use of this facility is expected to enhance the safety and welfare of local residents and individuals traveling through Trumbull.

Sincerely,

*Denise Sabo*

Denise Sabo

Mobile: 203-435-3640

Fax: 413-521-0558

Office: 4 Angela's Way, Burlington CT 06013

Email: [denise@northeastsitesolutions.com](mailto:denise@northeastsitesolutions.com)



**NSS** **NORTHEAST**  
SITE SOLUTIONS  
*Turnkey Wireless Development*

Attachments

Cc: Vicki Tesoro, First Selectman & Property Owner  
Trumbull Town Hall  
5866 Main Street  
Second Floor  
Trumbull, CT 06611

Rob Librandi, Land Use Planner  
Trumbull Town Hall  
5866 Main Street  
Second Floor  
Trumbull, CT 06611

Crown Castle, Tower Owner

# Exhibit A

## **Original Facility Approval**

## Hanlon, Dashanna

---

**From:** Myl, Kimberly  
**Sent:** Friday, March 11, 2016 9:34 AM  
**To:** [siting.council@ct.gov](mailto:siting.council@ct.gov)  
**Subject:** Existing Telecommunications Tower - 425 Indian Ledge Park Road, Trumbull (Crown: 881535 / T-Mobile CT11961A)

Good Morning,  
Please be advised per the below email from the Town of Trumbull and on behalf of Crown Castle the Tower Owner, neither party have the original zoning approval on file. Please use this email notification to replace that requirement. Please let me know if you have any questions or need additional information. Thank you in advance.

**KIMBERLY MYL**  
Real Estate Specialist  
T: (201) 236-9069 | M: (201) 993-3697

**CROWN CASTLE**  
1200 MacArthur Blvd, Suite 200  
Mahwah, NJ 07430

---

**From:** Gail Andreyka [<mailto:gandreyka@trumbull-ct.gov>]  
**Sent:** Tuesday, March 08, 2016 9:48 AM  
**To:** Myl, Kimberly  
**Cc:** Douglas Wenz  
**Subject:** RE: Zoning Approval - Telecommunications Tower 425 Indian Ledge Park Road

Hi Kim,

We cannot locate the zoning approval. They never came to Planning & Zoning with an application as far as we know. If you have any further questions, please contact Doug Wenz 203-452-5052.

Thank you,

Gail Andreyka

---

**From:** Myl, Kimberly [<mailto:Kimberly.Myl@crowncastle.com>]  
**Sent:** Monday, February 29, 2016 12:45 PM  
**To:** Gail Andreyka  
**Subject:** Zoning Approval - Telecommunications Tower 425 Indian Ledge Park Road

Good Afternoon Gail,  
I have another existing telecommunications facility that I will need a copy of the original zoning resolution to submit into the CSC. Can you kindly forward this over to me so I can submit on behalf of T-Mobile, one of our tenants. If you do not have this document, kindly reply stating that the township does not have this on record and I can use your email in place of this requirement. Please call or email me if you have any questions or need additional information. Thank you in advance.

**KIMBERLY MYL**  
Real Estate Specialist  
T: (201) 236-9069 | M: (201) 993-3697

# Exhibit B

## **Property Card**

# 425 INDIAN LEDGE PARK ROAD

**Location** 425 INDIAN LEDGE PARK ROAD

**Mblu** F/05 / 00096/ 000/

**Acct#**

**Owner** TRUMBULL TOWN OF

**Assessment** \$1,320,620

**Appraisal** \$1,886,600

**PID** 12730

**Building Count** 1

**Fire District** T

## Current Value

Appraisal	
Valuation Year	Total
2015	\$1,886,600
Assessment	
Valuation Year	Total
2015	\$1,320,620

## Owner of Record

**Owner** TRUMBULL TOWN OF  
**Co-Owner**  
**Address** 5866 MAIN STREET  
 TRUMBULL, CT 06611

**Sale Price** \$0  
**Book & Page** 1/ 466  
**Sale Date** 06/15/1989  
**Instrument**

## Ownership History

Ownership History				
Owner	Sale Price	Book & Page	Instrument	Sale Date
TRUMBULL TOWN OF	\$0	1/ 466		06/15/1989

## Building Information

### Building 1 : Section 1


**Year Built:**

**Living Area:** 0

Building Attributes	
Field	Description

Style	Outbuildings
Stories:	
Occupancy	
Exterior Wall 1	
Exterior Wall 2	
Roof Structure:	
Roof Cover	
Interior Wall 1	
Interior Wall 2	
Floor Covering	
Alt. Floor Cover	
Heat Fuel	
Heat Type:	
AC Type:	
Total Bedrooms:	
Total Bthrms:	
Total Half Baths:	
Total Xtra Fixtrs:	
Total Rooms:	
Bath Style:	
Kitchen Style:	
Total Kitchens	
Total Elec Meters	

### Building Photo



F05-96 05/04/2015

(<http://images.vgsi.com/photos2/TrumbullCTPhotos/\00\02\19\51.JPG>)

### Building Layout

Building Layout

([http://images.vgsi.com/photos2/TrumbullCTPhotos/Sketches/12730\\_1273](http://images.vgsi.com/photos2/TrumbullCTPhotos/Sketches/12730_1273))

Building Sub-Areas (sq ft)	Legend
No Data for Building Sub-Areas	

### Extra Features

Extra Features	Legend
No Data for Extra Features	

### Land

#### Land Use

**Use Code** 921  
**Description** Mun Lnd Res  
**Zone** AA  
**Neighborhood** 320  
**Alt Land Appr Category** No

#### Land Line Valuation

**Size (Acres)** 46.5  
**Frontage**  
**Depth**

### Outbuildings

Outbuildings	Legend
No Data for Outbuildings	



Code	Description	Sub Code	Sub Description	Size	Bldg #
BHS1	Comm Bth Hse	CB	CindBk/Frame	200 S.F.	1

**Valuation History**

Appraisal	
Valuation Year	Total
2019	\$1,886,600
2018	\$1,886,600
2017	\$1,886,600

Assessment	
Valuation Year	Total
2019	\$1,320,620
2018	\$1,320,620
2017	\$1,320,620



# Exhibit C

## **Construction Drawings**



DISH Wireless L.L.C. SITE ID:

**NJJER01096A**

DISH Wireless L.L.C. SITE ADDRESS:

**425 INDIAN LEDGE PARK RD  
TRUMBULL, CT 06611**

SCOPE OF WORK
THIS IS NOT AN ALL INCLUSIVE LIST. CONTRACTOR SHALL UTILIZE SPECIFIED EQUIPMENT PART OR ENGINEER APPROVED EQUIVALENT. CONTRACTOR SHALL VERIFY ALL NEEDED EQUIPMENT TO PROVIDE A FUNCTIONAL SITE. THE PROJECT GENERALLY CONSISTS OF THE FOLLOWING:
TOWER SCOPE OF WORK: <ul style="list-style-type: none"> <li>• INSTALL (3) PROPOSED PANEL ANTENNAS (1 PER SECTOR) MX08FR0665-21</li> <li>• INSTALL (1) PROPOSED TOWER PLATFORM MOUNT</li> <li>• INSTALL PROPOSED JUMPERS</li> <li>• INSTALL (6) PROPOSED RRUs (2 PER SECTOR) TA08025-B604, TA08025-B605</li> <li>• INSTALL (1) PROPOSED OVER VOLTAGE PROTECTION DEVICE (OVP) RDIDC-9181-PF-48</li> <li>• INSTALL (1) PROPOSED HYBRID CABLE CU12PSM6P4XXX</li> </ul>
GROUND SCOPE OF WORK: <ul style="list-style-type: none"> <li>• INSTALL (1) PROPOSED METAL PLATFORM</li> <li>• INSTALL (1) PROPOSED PPC CABINET</li> <li>• INSTALL (1) PROPOSED EQUIPMENT CABINET</li> <li>• INSTALL (1) PROPOSED POWER CONDUIT</li> <li>• INSTALL (1) PROPOSED TELCO CONDUIT</li> <li>• INSTALL (1) PROPOSED TELCO-FIBER BOX</li> <li>• INSTALL (1) PROPOSED GPS UNIT</li> <li>• INSTALL (1) PROPOSED FIBER NID (IF REQUIRED)</li> <li>• INSTALL (1) PROPOSED METER IN EXISTING SOCKET</li> </ul>

SITE INFORMATION	PROJECT DIRECTORY
PROPERTY OWNER: TRUMBULL TOWN OF ADDRESS: 5866 MAIN STREET TRUMBULL, CT 06611	APPLICANT: DISH Wireless L.L.C. 5701 SOUTH SANTA FE DRIVE LITTLETON, CO 80120
TOWER TYPE: MONOPOLE	TOWER OWNER: CROWN CASTLE 2000 CORPORATE DRIVE CANONSBURG, PA 15317 (877) 486-9377
TOWER CO SITE ID: 881535	SITE DESIGNER: B+T GROUP 1717 S. BOULDER AVE, SUITE 300 TULSA, OK 74119 (918) 587-4630
TOWER APP NUMBER: 548692	SITE ACQUISITION: WILLIAM SNIDER WILLIAM.SNIDER@DISH.COM
COUNTY: FAIRFIELD	CONSTRUCTION MANAGER: JOSEPH DIPIAZZA JOSEPH.DIPIAZZA@DISH.COM
LATITUDE (NAD 83): 41° 16' 23.8" N 41.273281 N	RF ENGINEER: MURUGABIRAN JAYAPAL MURUGABIRAN.JAYAPAL@DISH.COM
LONGITUDE (NAD 83): 73° 12' 47.2" W 73.21310556 W	
ZONING JURISDICTION: CONNECTICUT SITING COUNCIL	
ZONING DISTRICT: AA - MUN LND RES	
PARCEL NUMBER: F05-96	
OCCUPANCY GROUP: U	
CONSTRUCTION TYPE: V-B	
POWER COMPANY: T.B.D.	
TELEPHONE COMPANY: T.B.D.	



5701 SOUTH SANTA FE DRIVE  
LITTLETON, CO 80120



2000 CORPORATE DRIVE  
CANONSBURG, PA 15317



1717 S. BOULDER  
SUITE 300  
TULSA, OK 74119  
PH: (918) 587-4630  
www.btgrp.com



B&T ENGINEERING, INC.  
PEC.0001564  
Expires 2/10/22

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY: JTS	CHECKED BY: JTS	APPROVED BY: MDW
---------------	-----------------	------------------

RFDS REV #: 3.0

**CONSTRUCTION DOCUMENTS**

SUBMITTALS		
REV	DATE	DESCRIPTION
A	6/17/21	ISSUED FOR REVIEW
0	7/30/21	ISSUED FOR CONSTRUCTION
1	10/22/21	ISSUED FOR CONSTRUCTION
2	1/26/22	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER  
**136595.002.01**

DISH Wireless L.L.C.  
PROJECT INFORMATION  
**NJJER01096A**  
**425 INDIAN LEDGE PARK RD**  
**TRUMBULL, CT 06611**

SHEET TITLE  
**TITLE SHEET**

SHEET NUMBER  
**T-1**

**CONNECTICUT CODE COMPLIANCE**

ALL WORK SHALL BE PERFORMED AND MATERIALS INSTALLED IN ACCORDANCE WITH THE CURRENT EDITIONS OF THE FOLLOWING CODES AS ADOPTED BY THE LOCAL GOVERNING AUTHORITIES. NOTHING IN THESE PLANS IS TO BE CONSTRUED TO PERMIT WORK NOT CONFORMING TO THESE CODES:

CODE TYPE	CODE
BUILDING	2018 CT STATE BUILDING CODE/2015 IBC W/ CT AMENDMENTS
MECHANICAL	2018 CT STATE BUILDING CODE/2015 IMC W/ CT AMENDMENTS
ELECTRICAL	2018 CT STATE BUILDING CODE/2017 NEC W/ CT AMENDMENTS

**SHEET INDEX**

SHEET NO.	SHEET TITLE
T-1	TITLE SHEET
A-1	OVERALL AND ENLARGED SITE PLAN
A-2	ELEVATION, ANTENNA LAYOUT AND SCHEDULE
A-3	EQUIPMENT PLATFORM AND H-FRAME DETAILS
A-4	EQUIPMENT DETAILS
A-5	EQUIPMENT DETAILS
A-6	EQUIPMENT DETAILS
E-1	ELECTRICAL/FIBER ROUTE PLAN AND NOTES
E-2	ELECTRICAL DETAILS
E-3	ELECTRICAL ONE-LINE, FAULT CALCS & PANEL SCHEDULE
G-1	GROUNDING PLANS AND NOTES
G-2	GROUNDING DETAILS
G-3	GROUNDING DETAILS
RF-1	RF CABLE COLOR CODE
GN-1	LEGEND AND ABBREVIATIONS
GN-2	GENERAL NOTES
GN-3	GENERAL NOTES
GN-4	GENERAL NOTES

**SITE PHOTO**



**UNDERGROUND SERVICE ALERT CBYD 811**  
**UTILITY NOTIFICATION CENTER OF CONNECTICUT**  
 (800) 922-4455  
 WWW.CBYD.COM  
 CALL 2 WORKING DAYS UTILITY NOTIFICATION PRIOR TO CONSTRUCTION

**GENERAL NOTES**

THE FACILITY IS UNMANNED AND NOT FOR HUMAN HABITATION. A TECHNICIAN WILL VISIT THE SITE AS REQUIRED FOR ROUTINE MAINTENANCE. THE PROJECT WILL NOT RESULT IN ANY SIGNIFICANT DISTURBANCE OR EFFECT ON DRAINAGE. NO SANITARY SEWER SERVICE, POTABLE WATER, OR TRASH DISPOSAL IS REQUIRED AND NO COMMERCIAL SIGNAGE IS PROPOSED.


**11"x17" PLOT WILL BE HALF SCALE UNLESS OTHERWISE NOTED**


CONTRACTOR SHALL VERIFY ALL PLANS, EXISTING DIMENSIONS, AND CONDITIONS ON THE JOB SITE, AND SHALL IMMEDIATELY NOTIFY THE ENGINEER IN WRITING OF ANY DISCREPANCIES BEFORE PROCEEDING WITH THE WORK.

**DIRECTIONS**


- DIRECTIONS FROM 3 ADP BOULEVARD, ROSELAND, NJ:**
1. GET ON I-280 E FROM LIVINGSTON AVE.
  2. CONTINUE ON I-280 E. TAKE GARDEN STATE PKWY, I-287 E AND CT-15 N TO CT-25 S IN TRUMBULL.
  3. TAKE EXIT 48 FOR CT-111.
  4. USE ANY LANE TO TURN LEFT ONTO CT-111 N/MAIN ST.
  5. TURN RIGHT ONTO WHITNEY AVE.
  6. TURN RIGHT ONTO INDIAN LEDGE PARK RD.
  7. SITE ACCESS WILL BE IN THE BACK OF THE PARK BEHIND THE SOCCER FIELD.

**VICINITY MAP**






OVERALL SITE PLAN



ENLARGED SITE PLAN



OVERALL UTILITY PLAN

**dish wireless.**

5701 SOUTH SANTA FE DRIVE  
LITTLETON, CO 80120

**CROWN CASTLE**

2000 CORPORATE DRIVE  
CANONSBURG, PA 15317

**B+T GRP**

1717 S. BOULDER  
SUITE 300  
TULSA, OK 74119  
PH: (918) 587-4630  
www.btgrp.com

**Professional Engineer**  
No. 23824  
1/26/22

B&T ENGINEERING, INC.  
PEC.0001564  
Expires 2/10/22

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY: JTS  
CHECKED BY: JTS  
APPROVED BY: MDW

RFDS REV #: 3.0

**CONSTRUCTION DOCUMENTS**

SUBMITTALS		
REV	DATE	DESCRIPTION
A	6/17/21	ISSUED FOR REVIEW
0	7/30/21	ISSUED FOR CONSTRUCTION
1	10/22/21	ISSUED FOR CONSTRUCTION
2	1/26/22	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER  
**136595.002.01**

DISH Wireless L.L.C.  
PROJECT INFORMATION

NJJER01096A  
425 INDIAN LEDGE PARK RD  
TRUMBULL, CT 06611


SHEET TITLE  
**OVERALL AND ENLARGED SITE PLAN**

SHEET NUMBER  
**A-1**


NO SCALE

**NOTES**


1. CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS.
2. ANTENNA AND MW DISH SPECIFICATIONS REFER TO ANTENNA SCHEDULE AND TO FINAL CONSTRUCTION RFDS FOR ALL RF DETAILS
3. EXISTING EQUIPMENT AND FENCE OMITTED FOR CLARITY.





(1) PROPOSED DISH Wireless L.L.C. HYBRID CABLE ROUTED OUTSIDE POLE



**PROPOSED EAST ELEVATION**




1



\*AZIMUTHS ARE TENTATIVE AND ARE TO BE CONFIRMED BEFORE START OF CONSTRUCTION.

**ANTENNA LAYOUT**



2

SECTOR	POSITION	ANTENNA						TRANSMISSION CABLE
		EXISTING OR PROPOSED	MANUFACTURER - MODEL NUMBER	TECHNOLOGY	SIZE (HxW)	AZIMUTH	RAD CENTER	
ALPHA	A1	PROPOSED	JMA - MX08FRO665-21	5G	72.0" x 20.0"	100'	175'-0"	(1) HIGH-CAPACITY HYBRID CABLE (220' LONG)
BETA	B1	PROPOSED	JMA - MX08FRO665-21	5G	72.0" x 20.0"	220'	175'-0"	
GAMMA	C1	PROPOSED	JMA - MX08FRO665-21	5G	72.0" x 20.0"	340'	175'-0"	

SECTOR	POSITION	RRH		NOTES
		MANUFACTURER - MODEL NUMBER	TECHNOLOGY	
ALPHA	A1	FUJITSU - TA08025-B605	5G	1. CONTRACTOR TO REFER TO FINAL CONSTRUCTION RFDS FOR ALL RF DETAILS. 2. ANTENNA AND RRH MODELS MAY CHANGE DUE TO EQUIPMENT AVAILABILITY. ALL EQUIPMENT CHANGES MUST BE APPROVED AND REMAIN IN COMPLIANCE WITH THE PROPOSED DESIGN AND STRUCTURAL ANALYSES.
	A1	FUJITSU - TA08025-B604	5G	
	A1	RAYCAP - RDIDC-9181-PF-48	5G	
BETA	B1	FUJITSU - TA08025-B605	5G	
	B1	FUJITSU - TA08025-B604	5G	
GAMMA	C1	FUJITSU - TA08025-B605	5G	
	C1	FUJITSU - TA08025-B604	5G	

**ANTENNA SCHEDULE**

NO SCALE

3



5701 SOUTH SANTA FE DRIVE  
LITTLETON, CO 80120



2000 CORPORATE DRIVE  
CANONSBURG, PA 15317



1717 S. BOULDER  
SUITE 300  
TULSA, OK 74119  
PH: (918) 587-4630  
www.btgrp.com



B&T ENGINEERING, INC.  
PEC.0001564  
Expires 2/10/22

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
JTS	JTS	MDW

RFDS REV #: 3.0

**CONSTRUCTION DOCUMENTS**


SUBMITTALS		
REV	DATE	DESCRIPTION
A	6/17/21	ISSUED FOR REVIEW
0	7/30/21	ISSUED FOR CONSTRUCTION
1	10/22/21	ISSUED FOR CONSTRUCTION
2	1/26/22	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER  
**136595.002.01**


DISH Wireless L.L.C. PROJECT INFORMATION  
**NJJER01096A**  
425 INDIAN LEDGE PARK RD  
TRUMBULL, CT 06611

SHEET TITLE  
**ELEVATION, ANTENNA LAYOUT AND SCHEDULE**

SHEET NUMBER  
**A-2**



PLATFORM EQUIPMENT PLAN




1

COMMSCOPE MTC4045LP  
5X7 PLATFORM

DIMENSIONS (HxWxD)	16"x84"x60"
TOTAL WEIGHT	423 LBS

NOTE:  
GC TO PROVIDE EXTENDED  
THREAD FOR PLATFORM IF  
REQUIRED HEIGHT EXCEEDS 17"




PLATFORM DETAIL

NO SCALE

2

KENWOOD T1701KT5-5S  
H-FRAME

UNISTRUT/SUPPORT RAIL	5
WEIGHT/ VOLUME	173.6 LBS



H-FRAME DETAIL

NO SCALE

3


NOT USED

NO SCALE


4

NOTES


- CONTRACTOR TO BURY PLATFORM FEET WITH A MINIMUM OF 2" OF FILL PER EXISTING SITE SURFACE
- WEED BARRIER FABRIC TO BE ADDED AT DISCRETION OF DISH Wireless L.L.C. CONSTRUCTION MANAGER AT TIME OF CONSTRUCTION. ONE SHEET 8'x8' INSTALLED UNDER ALL FOUR FEET OF THE PLATFORM (4 MIL BLACK PLASTIC)
- EQUIPMENT CABINET OMITTED FOR CLARITY



FRONT ELEVATION



BACK ELEVATION



5



5701 SOUTH SANTA FE DRIVE  
LITTLETON, CO 80120



2000 CORPORATE DRIVE  
CANONSBURG, PA 15317



1717 S. BOULDER  
SUITE 300  
TULSA, OK 74119  
PH: (918) 587-4630  
www.btgrp.com



B&T ENGINEERING, INC.  
PEC.0001564  
Expires 2/10/22

IT IS A VIOLATION OF LAW FOR ANY PERSON,  
UNLESS THEY ARE ACTING UNDER THE DIRECTION  
OF A LICENSED PROFESSIONAL ENGINEER,  
TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
JTS	JTS	MDW

RFDS REV #: 3.0

CONSTRUCTION  
DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	6/17/21	ISSUED FOR REVIEW
0	7/30/21	ISSUED FOR CONSTRUCTION
1	10/22/21	ISSUED FOR CONSTRUCTION
2	1/26/22	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER  
136595.002.01



DISH Wireless L.L.C.  
PROJECT INFORMATION  
NJJER01096A  
425 INDIAN LEDGE PARK RD  
TRUMBULL, CT 06611

SHEET TITLE  
EQUIPMENT PLATFORM AND  
H-FRAME DETAILS

SHEET NUMBER

A-3

ENERSYS HVAC CABINET 2000005995	
DIMENSIONS (HxWxD):	73"x30"x32"
WEIGHT EMPTY:	371 lbs
HVAC	600W
POWER SYSTEM	-48V ALPHA/600A





CABINET DETAIL

NO SCALE

1

RAYCAP PPC RDIAC-2465-P-240-MTS	
ENCLOSURE DIMENSIONS (HxWxD):	39"x22.855"x12.593
WEIGHT:	80 lbs
OPERATING AC VOLTAGE	240/120 1 PHASE 3W+G



POWER PROTECTION CABINET (PPC) DETAIL

NO SCALE



2

NOT USED

NO SCALE

3

ZAYO 5RU CABINET LEFT SWING DOOR ("LIT" SITES)	
DIMENSIONS (HxWxD)	36.115"x29"x12.9"
WEIGHT	85 LBS
POWER INPUT	20A, -48VDC



NOT USED

NO SCALE



4

NETWORK INTERFACE UNIT DETAIL

NO SCALE

5


CHARLES CFIT-PF2020DSH1 FIBER TELCO ENCLOSURE	
ENCLOSURE DIMS (HxWxD)	20"x20"x9"
ENCLOSURE WEIGHT	20 lbs
MOUNTING	WALL
COMPLIANCE	TYPE 4



FIBER TELCO ENCLOSURE DETAIL

NO SCALE

6



HYBRID CABLE RUN

NO SCALE

9

**dish**  
wireless.

5701 SOUTH SANTA FE DRIVE  
LITTLETON, CO 80120

**CROWN**  
**CASTLE**

2000 CORPORATE DRIVE  
CANONSBURG, PA 15317

**B+T GRP**

1717 S. BOULDER  
SUITE 300  
TULSA, OK 74119  
PH: (918) 587-4630  
www.btgrp.com



B&T ENGINEERING, INC.  
PEC.0001564  
Expires 2/10/22

IT IS A VIOLATION OF LAW FOR ANY PERSON,  
UNLESS THEY ARE ACTING UNDER THE DIRECTION  
OF A LICENSED PROFESSIONAL ENGINEER,  
TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
JTS	JTS	MDW

RFDS REV #: 3.0

**CONSTRUCTION  
DOCUMENTS**

SUBMITTALS		
REV	DATE	DESCRIPTION
A	6/17/21	ISSUED FOR REVIEW
0	7/30/21	ISSUED FOR CONSTRUCTION
1	10/22/21	ISSUED FOR CONSTRUCTION
2	1/26/22	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER  
**136595.002.01**

DISH Wireless L.L.C.  
PROJECT INFORMATION  
**NJJER01096A**  
425 INDIAN LEDGE PARK RD  
TRUMBULL, CT 06611

SHEET TITLE  
**EQUIPMENT DETAILS**

SHEET NUMBER  
**A-4**

NOT USED

NO SCALE

7






NOT USED

NO SCALE

8



ROSENBERGER GPSGLONASS-36-N-S	
DIMENSION (DIA x H)	69mm x 98.5mm
WEIGHT (WITH ACCESSORIES)	515.74g
CONNECTOR	N-FEMALE
FREQUENCY RANGE	1559 MHz ~ 1610.5MHz



GPS ANTENNA DETAIL

NO SCALE 1

GPS MINIMUM SKY VIEW REQUIREMENTS

NO SCALE 2

CABLES UNLIMITED HYBRID CABLE  
MINIMUM BEND RADIUS

NO SCALE 3

NOT USED

NO SCALE 4

NOT USED

NO SCALE 5

NOT USED

NO SCALE 6

NOT USED

NO SCALE 7

NOT USED

NO SCALE 8

NOT USED

NO SCALE 9

**dish**  
wireless.

5701 SOUTH SANTA FE DRIVE  
LITTLETON, CO 80120

**CROWN CASTLE**

2000 CORPORATE DRIVE  
CANONSBURG, PA 15317

**B+T GRP**  
1717 S. BOULDER  
SUITE 300  
TULSA, OK 74119  
PH: (918) 587-4630  
www.btgrp.com



B&T ENGINEERING, INC.  
PEC.0001564  
Expires 2/10/22

IT IS A VIOLATION OF LAW FOR ANY PERSON,  
UNLESS THEY ARE ACTING UNDER THE DIRECTION  
OF A LICENSED PROFESSIONAL ENGINEER,  
TO ALTER THIS DOCUMENT.

DRAWN BY: JTS    CHECKED BY: JTS    APPROVED BY: MDW

RFDS REV #: 3.0

**CONSTRUCTION DOCUMENTS**

SUBMITTALS		
REV	DATE	DESCRIPTION
A	6/17/21	ISSUED FOR REVIEW
0	7/30/21	ISSUED FOR CONSTRUCTION
1	10/22/21	ISSUED FOR CONSTRUCTION
2	1/26/22	ISSUED FOR CONSTRUCTION


A&E PROJECT NUMBER  
**136595.002.01**

DISH Wireless L.L.C.  
PROJECT INFORMATION  
**NJJER01096A**  
425 INDIAN LEDGE PARK RD  
TRUMBULL, CT 06611


SHEET TITLE  
**EQUIPMENT DETAILS**

SHEET NUMBER  
**A-5**


<b>FUJITSU TA08025-B604 RRH</b>	
DIMENSIONS (HxWxD) (KG/IN)	380x400x200/14.9"x15.7"x7.8"
WEIGHT(KG,LB)/ VOLUME	29kg,63.9lb/ 30L
POWER SUPPLY	DC-58~-36V



PLAN



SIDE




FRONT

REMOTE RADIO HEAD DETAIL


NO SCALE

1


<b>FUJITSU TA08025-B605 RRH</b>	
DIMENSIONS (HxWxD) (KG/IN)	380x400x230/14.9"x15.7"x9.0"
WEIGHT(KG,LB)/ VOLUME	34kg,74.9lb/ 35L
POWER SUPPLY	DC-58~-36V



PLAN



SIDE



FRONT


REMOTE RADIO HEAD DETAIL

NO SCALE

2


<b>SABRE INDUSTRIES RRU BRACKET MOUNT C10123155</b>	
DIMENSIONS (HxWxD) (1 BRACKET)	5"x20"x1-13/16"
WEIGHT (FULL ASSEMBLY)	35.79 lbs
PACKAGE QUANTITY	4

ITEM#	DESCRIPTION
1	PLATE, CHANNEL BRACKET
2	RRH Z BRACKET, 3/16"
3	THREADED ROD ASSEMBLY 1/2"x12"



11MM x 30MM SLOTS  
40MM ON CENTER

11MM x 24MM SLOTS




REMOTE RADIO MOUNT DETAIL


NO SCALE

3

<b>JMA WIRELESS MX08FRO665-21 ANTENNA</b>	
DIMENSIONS (HxWxD)	72.0"x20.0"x8.0"
TOTAL WEIGHT	64.5 LB
RF PORTS, CONNECTOR TYPE	8 x 4.3-10 FEMALE



PLAN



BACK

SIDE



FRONT

ANTENNA DETAIL


NO SCALE

4

<b>RAYCAP RDIC-9181-PF-48 DC SURGE PROTECTION (OVP)</b>	
DIMENSIONS (HxWxD)	18.98"x14.39"x8.15"
WEIGHT	21.82 LBS



PLAN



SIDE

BACK


FRONT

SURGE SUPPRESSION DETAIL (OVP)

NO SCALE


7

<b>COMMSCOPE XP-2040 CROSSOVER PLATE</b>	
DIMENSIONS (HxW)	10"x12"
WEIGHT	11.023 LBS




PLAN

SIDE



PLAN

SIDE



CROSSOVER PLATE


OPTION OF EITHER  
SQUARE OR CIRCULAR  
U-BOLT

RRH/OVP MOUNT DETAIL

NO SCALE

8

<b>COMMSCOPE MC-PK8-DSH</b>	
FACE WIDTH	96"
WEIGHT	1373.08 lbs
NOTE: 15" TO 38" O.D.	



FACE PIPE

HANDRAIL PIPE

ANTENNA PIPE

41.4"

PLATFORM

96"

ANTENNA PLATFORM DETAIL

NO SCALE

9

**dish**  
wireless.

5701 SOUTH SANTA FE DRIVE  
LITTLETON, CO 80120

**CROWN  
CASTLE**

2000 CORPORATE DRIVE  
CANONSBURG, PA 15317

**B+T GRP**

1717 S. BOULDER  
SUITE 300  
TULSA, OK 74119  
PH: (918) 587-4630  
www.btgrp.com



B&T ENGINEERING, INC.  
PEC.0001564  
Expires 2/10/22

IT IS A VIOLATION OF LAW FOR ANY PERSON,  
UNLESS THEY ARE ACTING UNDER THE DIRECTION  
OF A LICENSED PROFESSIONAL ENGINEER,  
TO ALTER THIS DOCUMENT.

DRAWN BY: CHECKED BY: APPROVED BY:

JTS JTS MDW

RFDS REV #: 3.0

**CONSTRUCTION  
DOCUMENTS**

SUBMITTALS		
REV	DATE	DESCRIPTION
A	6/17/21	ISSUED FOR REVIEW
0	7/30/21	ISSUED FOR CONSTRUCTION
1	10/22/21	ISSUED FOR CONSTRUCTION
2	1/26/22	ISSUED FOR CONSTRUCTION


A&E PROJECT NUMBER  
136595.002.01

DISH Wireless L.L.C.  
PROJECT INFORMATION  
NJJER01096A  
425 INDIAN LEDGE PARK RD  
TRUMBULL, CT 06611

SHEET TITLE  
EQUIPMENT DETAILS

SHEET NUMBER

**A-6**




**NOTES**

1. CONTRACTOR SHALL FIELD VERIFY ALL PROPOSED UNDERGROUND UTILITY CONDUIT ROUTE.
2. ANTENNAS AND MOUNTS OMITTED FOR CLARITY.

DC POWER WIRING SHALL BE COLOR CODED AT EACH END FOR IDENTIFYING +24V AND -48V CONDUCTORS. RED MARKINGS SHALL IDENTIFY +24V AND BLUE MARKINGS SHALL IDENTIFY -48V.

1. CONTRACTOR SHALL INSPECT THE EXISTING CONDITIONS PRIOR TO SUBMITTING A BID. ANY QUESTIONS ARISING DURING THE BID PERIOD IN REGARDS TO THE CONTRACTOR'S FUNCTIONS, THE SCOPE OF WORK, OR ANY OTHER ISSUE RELATED TO THIS PROJECT SHALL BE BROUGHT UP DURING THE BID PERIOD WITH THE PROJECT MANAGER FOR CLARIFICATION, NOT AFTER THE CONTRACT HAS BEEN AWARDED.
2. ALL ELECTRICAL WORK SHALL BE DONE IN ACCORDANCE WITH CURRENT NATIONAL ELECTRICAL CODES AND ALL STATE AND LOCAL CODES, LAWS, AND ORDINANCES. PROVIDE ALL COMPONENTS AND WIRING SIZES AS REQUIRED TO MEET NEC STANDARDS.
3. LOCATION OF EQUIPMENT, CONDUIT AND DEVICES SHOWN ON THE DRAWINGS ARE APPROXIMATE AND SHALL BE COORDINATED WITH FIELD CONDITIONS PRIOR TO CONSTRUCTION.
4. CONDUIT ROUGH-IN SHALL BE COORDINATED WITH THE MECHANICAL EQUIPMENT TO AVOID LOCATION CONFLICTS. VERIFY WITH THE MECHANICAL EQUIPMENT CONTRACTOR AND COMPLY AS REQUIRED.
5. CONTRACTOR SHALL PROVIDE ALL BREAKERS, CONDUITS AND CIRCUITS AS REQUIRED FOR A COMPLETE SYSTEM.
6. CONTRACTOR SHALL PROVIDE PULL BOXES AND JUNCTION BOXES AS REQUIRED BY THE NEC ARTICLE 314.
7. CONTRACTOR SHALL PROVIDE ALL STRAIN RELIEF AND CABLE SUPPORTS FOR ALL CABLE ASSEMBLIES. INSTALLATION SHALL BE IN ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS AND RECOMMENDATIONS.
8. ALL DISCONNECTS AND CONTROLLING DEVICES SHALL BE PROVIDED WITH ENGRAVED PHENOLIC NAMEPLATES INDICATING EQUIPMENT CONTROLLED, BRANCH CIRCUITS INSTALLED ON, AND PANEL FIELD LOCATIONS FED FROM.
9. INSTALL AN EQUIPMENT GROUNDING CONDUCTOR IN ALL CONDUITS PER THE SPECIFICATIONS AND NEC 250. THE EQUIPMENT GROUNDING CONDUCTORS SHALL BE BONDED AT ALL JUNCTION BOXES, PULL BOXES, AND ALL DISCONNECT SWITCHES, AND EQUIPMENT CABINETS.
10. ALL NEW MATERIAL SHALL HAVE A U.L. LABEL.
11. PANEL SCHEDULE LOADING AND CIRCUIT ARRANGEMENTS REFLECT POST-CONSTRUCTION EQUIPMENT.
12. CONTRACTOR SHALL BE RESPONSIBLE FOR AS-BUILT PANEL SCHEDULE AND SITE DRAWINGS.
13. ALL TRENCHES IN COMPOUND TO BE HAND DUG



**ELECTRICAL NOTES**



5701 SOUTH SANTA FE DRIVE  
LITTLETON, CO 80120



2000 CORPORATE DRIVE  
CANONSBURG, PA 15317



1717 S. BOULDER  
SUITE 300  
TULSA, OK 74119  
PH: (918) 587-4630  
www.btgrp.com



B&T ENGINEERING, INC.  
PEC.0001564  
Expires 2/10/22

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
JTS	JTS	MDW

RFDS REV #: 3.0

**CONSTRUCTION DOCUMENTS**

SUBMITTALS		
REV	DATE	DESCRIPTION
A	6/17/21	ISSUED FOR REVIEW
0	7/30/21	ISSUED FOR CONSTRUCTION
1	10/22/21	ISSUED FOR CONSTRUCTION
2	1/26/22	ISSUED FOR CONSTRUCTION


A&E PROJECT NUMBER  
**136595.002.01**

DISH Wireless L.L.C.  
PROJECT INFORMATION  
**NJJER01096A**  
425 INDIAN LEDGE PARK RD  
TRUMBULL, CT 06611

SHEET TITLE  
**ELECTRICAL/FIBER ROUTE  
PLAN AND NOTES**


SHEET NUMBER  
**E-1**

**UTILITY ROUTE PLAN**



**CARLON EXPANSION FITTINGS**



COUPLING END PART#	MALE TERMINAL ADAPTER END PART#	SIZE	STD CTN QTY.	TRAVEL LENGTH
E945D	E945DX	1/2"	20	4"
E945E	E945EX	3/4"	15	4"
E945F	E945FX	1"	10	4"
E945G	E945GX	1 1/4"	5	4"
E945H	E945HX	1 1/2"	5	4"
E945J	E945JX	2"	15	8"
E945K	E945KX	2 1/2"	10	8"
E945L	E945LX	3"	10	8"
E945M	E945MX	3 1/2"	5	8"
E945N	E945NX	4"	5	8"
E945P	E945PX	5"	1	8"
E945R	E945RX	6"	1	8"



NOTE: CONTRACTOR TO INSTALL EXPANSION FITTING SLIP JOINT AT METER CENTER CONDUIT TERMINATION, AS PER LOCAL UTILITY POLICY, ORDINANCE AND/OR SPECIFIED REQUIREMENT.

**TRENCHING NOTES**

- CONTRACTOR SHALL RESTORE THE TRENCH TO ITS ORIGINAL CONDITIONS BY EITHER SEEDING OR SODDING GRASS AREAS, OR REPLACING ASPHALT OR CONCRETE AREAS TO ITS ORIGINAL CROSS SECTION.
- TRENCHING SAFETY; INCLUDING, BUT NOT LIMITED TO SOIL CLASSIFICATION, SLOPING, AND SHORING, SHALL BE GOVERNED BY THE CURRENT OSHA TRENCHING AND EXCAVATION SAFETY STANDARDS.
- ALL CONDUITS SHALL BE INSTALLED IN COMPLIANCE WITH THE CURRENT NATIONAL ELECTRIC CODE (NEC) OR AS REQUIRED BY THE LOCAL JURISDICTION, WHICHEVER IS THE MOST STRINGENT.



EXPANSION JOINT DETAIL


NO SCALE 1

TYPICAL UNDERGROUND TRENCH DETAIL

NO SCALE 2

DARK TELCO BOX – INTERIOR WIRING LAYOUT

NO SCALE 3



LIT TELCO BOX – INTERIOR WIRING LAYOUT (OPTIONAL)

NO SCALE 4

NOT USED

NO SCALE 5

NOT USED

NO SCALE 6

NOT USED

NO SCALE 7

NOT USED

NO SCALE 8

NOT USED

NO SCALE 9



5701 SOUTH SANTA FE DRIVE  
LITTLETON, CO 80120



2000 CORPORATE DRIVE  
CANONSBURG, PA 15317



1717 S. BOULDER  
SUITE 300  
TULSA, OK 74119  
PH: (918) 587-4630  
www.btgrp.com



B&T ENGINEERING, INC.  
PEC.0001564  
Expires 2/10/22

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY: CHECKED BY: APPROVED BY:

JTS JTS MDW

RFDS REV #: 3.0

**CONSTRUCTION DOCUMENTS**


SUBMITTALS		
REV	DATE	DESCRIPTION
A	6/17/21	ISSUED FOR REVIEW
0	7/30/21	ISSUED FOR CONSTRUCTION
1	10/22/21	ISSUED FOR CONSTRUCTION
2	1/26/22	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER  
136595.002.01

DISH Wireless L.L.C.  
PROJECT INFORMATION  
NJJER01096A  
425 INDIAN LEDGE PARK RD  
TRUMBULL, CT 06611

SHEET TITLE  
ELECTRICAL  
DETAILS

SHEET NUMBER  
E-2



**NOTE:**  
BRANCH CIRCUIT WIRING SUPPLYING RECTIFIERS ARE TO BE RATED UL1015, 105°C, 600V, AND PVC INSULATED, IN THE SIZES SHOWN IN THE ONE-LINE DIAGRAM. CONTRACTOR MAY SUBSTITUTE UL1015 WIRE FOR THWN-2 FOR CONVENIENCE OUTLET BRANCH CIRCUIT.

**BREAKERS REQUIRED:**  
(2) 40A, 2P BREAKER – SQUARE D P/N:QO240  
(1) 20A, 2P BREAKER – SQUARE D P/N:QO220  
(1) 20A, 1P BREAKER – SQUARE D P/N:QO120

**NOTES**

CONDUIT SIZING: AT 40% FILL PER NEC CHAPTER 9, TABLE 4, ARTICLE 358.  
 0.5" CONDUIT – 0.122 SQ. IN AREA  
 0.75" CONDUIT – 0.213 SQ. IN AREA  
 2.0" CONDUIT – 1.316 SQ. IN AREA  
 3.0" CONDUIT – 2.907 SQ. IN AREA

CABINET CONVENIENCE OUTLET CONDUCTORS (1 CONDUIT): USING THWN-2, CU.  
 #10 – 0.0211 SQ. IN X 2 = 0.0422 SQ. IN  
 #10 – 0.0211 SQ. IN X 1 = 0.0211 SQ. IN <GROUND  
 TOTAL = 0.0633 SQ. IN

0.5" EMT CONDUIT IS ADEQUATE TO HANDLE THE TOTAL OF (3) WIRES, INCLUDING GROUND WIRE, AS INDICATED ABOVE.

RECTIFIER CONDUCTORS (3 CONDUITS): USING UL1015, CU.  
 #8 – 0.0552 SQ. IN X 2 = 0.1103 SQ. IN  
 #8 – 0.0131 SQ. IN X 1 = 0.0131 SQ. IN <BARE GROUND  
 TOTAL = 0.1234 SQ. IN

0.75" EMT CONDUIT IS ADEQUATE TO HANDLE THE TOTAL OF (3) WIRES, INCLUDING GROUND WIRE, AS INDICATED ABOVE.

PPC FEED CONDUCTORS (1 CONDUIT): USING THWN, CU.  
 3/0 – 0.2679 SQ. IN X 3 = 0.8037 SQ. IN  
 #6 – 0.0507 SQ. IN X 1 = 0.0507 SQ. IN <GROUND  
 TOTAL = 0.8544 SQ. IN

3.0" SCH 40 PVC CONDUIT IS ADEQUATE TO HANDLE THE TOTAL OF (4) WIRES, INCLUDING GROUND WIRE, AS INDICATED ABOVE.



5701 SOUTH SANTA FE DRIVE  
LITTLETON, CO 80120



2000 CORPORATE DRIVE  
CANONSBURG, PA 15317



1717 S. BOULDER  
SUITE 300  
TULSA, OK 74119  
PH: (918) 587-4630  
www.btrgp.com



B&T ENGINEERING, INC.  
PEC.0001564  
Expires 2/10/22

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
JTS	JTS	MDW

RFDS REV #: 3.0

**CONSTRUCTION DOCUMENTS**

SUBMITTALS

REV	DATE	DESCRIPTION
A	6/17/21	ISSUED FOR REVIEW
0	7/30/21	ISSUED FOR CONSTRUCTION
1	10/22/21	ISSUED FOR CONSTRUCTION
2	1/26/22	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER  
**136595.002.01**

DISH Wireless L.L.C.  
PROJECT INFORMATION  
**NJJER01096A**  
425 INDIAN LEDGE PARK RD  
TRUMBULL, CT 06611

SHEET TITLE  
**ELECTRICAL ONE-LINE, FAULT CALCS & PANEL SCHEDULE**

SHEET NUMBER  
**E-3**

PPC ONE-LINE DIAGRAM

NO SCALE 1


PROPOSED ENERSYS PANEL SCHEDULE											
LOAD SERVED	VOLT AMPS (WATTS)		TRIP	CKT #	PHASE	CKT #	TRIP	VOLT AMPS (WATTS)		LOAD SERVED	
	L1	L2						L1	L2		
PPC GFCI OUTLET	180	180	15A	1	A	2	40A	3840	3840	ENERSYS ALPHA CORDEX RECTIFIERS 1 & 2	
ENERSYS GFCI OUTLET			20A	3	B	4					
-SPACE-				5	A	6	40A	3840	3840	ENERSYS ALPHA CORDEX RECTIFIER 3 & 4	
-SPACE-				7	B	8					
-SPACE-				9	A	10	20A	1920	1920	ENERSYS ALPHA CORDEX RECTIFIER 5	
-SPACE-				11	B	12					
-SPACE-				13	A	14				-SPACE-	
-SPACE-				15	B	16				-SPACE-	
-SPACE-				17	A	18				-SPACE-	
-SPACE-				19	B	20				-SPACE-	
-SPACE-				21	A	22				-SPACE-	
-SPACE-				23	B	24				-SPACE-	
VOLTAGE AMPS	180	180						9500	9500		
200A MCB, 1φ, 24 SPACE, 120/240V				L1	L2						
MB RATING: 65,000 AIC				9680	9680						
				81	81						
				81							
				102							

PANEL SCHEDULE

NO SCALE 2

NOT USED

NO SCALE 3




TYPICAL EQUIPMENT GROUNDING PLAN

NO SCALE 1


NOTES

1. ANTENNAS AND OVP SHOWN ARE GENERIC AND NOT REFERENCING TO A SPECIFIC MANUFACTURER. THIS LAYOUT IS FOR REFERENCE ONLY



TYPICAL ANTENNA GROUNDING PLAN

NO SCALE 2



GROUNDING LEGEND

1. GROUNDING IS SHOWN DIAGRAMMATICALLY ONLY.
2. CONTRACTOR SHALL GROUND ALL EQUIPMENT AS A COMPLETE SYSTEM. GROUNDING SHALL BE IN COMPLIANCE WITH NEC SECTION 250 AND DISH Wireless L.L.C. GROUNDING AND BONDING REQUIREMENTS AND MANUFACTURER'S SPECIFICATIONS.
3. ALL GROUND CONDUCTORS SHALL BE COPPER; NO ALUMINUM CONDUCTORS SHALL BE USED.

GROUNDING KEY NOTES

- (A) **EXTERIOR GROUND RING:** #2 AWG SOLID COPPER, BURIED AT A DEPTH OF AT LEAST 30 INCHES BELOW GRADE, OR 6 INCHES BELOW THE FROST LINE AND APPROXIMATELY 24 INCHES FROM THE EXTERIOR WALL OR FOOTING.
- (B) **TOWER GROUND RING:** THE GROUND RING SYSTEM SHALL BE INSTALLED AROUND AN ANTENNA TOWER'S LEGS, AND/OR GUY ANCHORS. WHERE SEPARATE SYSTEMS HAVE BEEN PROVIDED FOR THE TOWER AND THE BUILDING, AT LEAST TWO BONDS SHALL BE MADE BETWEEN THE TOWER RING GROUND SYSTEM AND THE BUILDING RING GROUND SYSTEM USING MINIMUM #2 AWG SOLID COPPER CONDUCTORS.
- (C) **INTERIOR GROUND RING:** #2 AWG STRANDED GREEN INSULATED COPPER CONDUCTOR EXTENDED AROUND THE PERIMETER OF THE EQUIPMENT AREA. ALL NON-TELECOMMUNICATIONS RELATED METALLIC OBJECTS FOUND WITHIN A SITE SHALL BE GROUND TO THE INTERIOR GROUND RING WITH #6 AWG STRANDED GREEN INSULATED CONDUCTOR.
- (D) **BOND TO INTERIOR GROUND RING:** #2 AWG SOLID TINNED COPPER WIRE PRIMARY BONDS SHALL BE PROVIDED AT LEAST AT FOUR POINTS ON THE INTERIOR GROUND RING, LOCATED AT THE CORNERS OF THE BUILDING.
- (E) **GROUND ROD:** UL LISTED COPPER CLAD STEEL. MINIMUM 1/2" DIAMETER BY EIGHT FEET LONG. GROUND RODS SHALL BE INSTALLED WITH INSPECTION SLEEVES. GROUND RODS SHALL BE DRIVEN TO THE DEPTH OF GROUND RING CONDUCTOR.
- (F) **CELL REFERENCE GROUND BAR:** POINT OF GROUND REFERENCE FOR ALL COMMUNICATIONS EQUIPMENT FRAMES. ALL BONDS ARE MADE WITH #2 AWG UNLESS NOTED OTHERWISE STRANDED GREEN INSULATED COPPER CONDUCTORS. BOND TO GROUND RING WITH (2) #2 SOLID TINNED COPPER CONDUCTORS.
- (G) **HATCH PLATE GROUND BAR:** BOND TO THE INTERIOR GROUND RING WITH TWO #2 AWG STRANDED GREEN INSULATED COPPER CONDUCTORS. WHEN A HATCH-PLATE AND A CELL REFERENCE GROUND BAR ARE BOTH PRESENT, THE CRGB MUST BE CONNECTED TO THE HATCH-PLATE AND TO THE INTERIOR GROUND RING USING (2) TWO #2 AWG STRANDED GREEN INSULATED COPPER CONDUCTORS EACH.
- (H) **EXTERIOR CABLE ENTRY PORT GROUND BARS:** LOCATED AT THE ENTRANCE TO THE CELL SITE BUILDING. BOND TO GROUND RING WITH A #2 AWG SOLID TINNED COPPER CONDUCTORS WITH AN EXOTHERMIC WELD AND INSPECTION SLEEVE.
- (I) **TELCO GROUND BAR:** BOND TO BOTH CELL REFERENCE GROUND BAR OR EXTERIOR GROUND RING.
- (J) **FRAME BONDING:** THE BONDING POINT FOR TELECOM EQUIPMENT FRAMES SHALL BE THE GROUND BUS THAT IS NOT ISOLATED FROM THE EQUIPMENTS METAL FRAMEWORK.
- (K) **INTERIOR UNIT BONDS:** METAL FRAMES, CABINETS AND INDIVIDUAL METALLIC UNITS LOCATED WITH THE AREA OF THE INTERIOR GROUND RING REQUIRE A #6 AWG STRANDED GREEN INSULATED COPPER BOND TO THE INTERIOR GROUND RING.
- (L) **FENCE AND GATE GROUNDING:** METAL FENCES WITHIN 7 FEET OF THE EXTERIOR GROUND RING OR OBJECTS BONDED TO THE EXTERIOR GROUND RING SHALL BE BONDED TO THE GROUND RING WITH A #2 AWG SOLID TINNED COPPER CONDUCTOR AT AN INTERVAL NOT EXCEEDING 25 FEET. BONDS SHALL BE MADE AT EACH GATE POST AND ACROSS GATE OPENINGS.
- (M) **EXTERIOR UNIT BONDS:** METALLIC OBJECTS, EXTERNAL TO OR MOUNTED TO THE BUILDING, SHALL BE BONDED TO THE EXTERIOR GROUND RING. USING #2 TINNED SOLID COPPER WIRE
- (N) **ICE BRIDGE SUPPORTS:** EACH ICE BRIDGE LEG SHALL BE BONDED TO THE GROUND RING WITH #2 AWG BARE TINNED COPPER CONDUCTOR. PROVIDE EXOTHERMIC WELDS AT BOTH THE ICE BRIDGE LEG AND BURIED GROUND RING.
- (O) **DURING ALL DC POWER SYSTEM CHANGES INCLUDING DC SYSTEM CHANGE OUTS, RECTIFIER REPLACEMENTS OR ADDITIONS, BREAKER DISTRIBUTION CHANGES, BATTERY ADDITIONS, BATTERY REPLACEMENTS AND INSTALLATIONS OR CHANGES TO DC CONVERTER SYSTEMS IT SHALL BE REQUIRED THAT SERVICE CONTRACTORS VERIFY ALL DC POWER SYSTEMS ARE EQUIPPED WITH A MASTER DC SYSTEM RETURN GROUND CONDUCTOR FROM THE DC POWER SYSTEM COMMON RETURN BUS DIRECTLY CONNECTED TO THE CELL SITE REFERENCE GROUND BAR**
- (P) **TOWER TOP COLLECTOR BUSS BAR IS TO BE MECHANICALLY BONDED TO PROPOSED ANTENNA MOUNT COLLAR. REFER TO DISH Wireless L.L.C. GROUNDING NOTES.**

GROUNDING KEY NOTES

NO SCALE 3



5701 SOUTH SANTA FE DRIVE  
LITTLETON, CO 80120



2000 CORPORATE DRIVE  
CANONSBURG, PA 15317



1717 S. BOULDER  
SUITE 300  
TULSA, OK 74119  
PH: (918) 587-4630  
www.btgrp.com



B&T ENGINEERING, INC.  
PEC.0001564  
Expires 2/10/22

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
JTS	JTS	MDW

RFDS REV #: 3.0

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	6/17/21	ISSUED FOR REVIEW
0	7/30/21	ISSUED FOR CONSTRUCTION
1	10/22/21	ISSUED FOR CONSTRUCTION
2	1/26/22	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER  
136595.002.01

DISH Wireless L.L.C.  
PROJECT INFORMATION  
NJJER01096A  
425 INDIAN LEDGE PARK RD  
TRUMBULL, CT 06611


SHEET TITLE  
GROUNDING PLANS  
AND NOTES

SHEET NUMBER

G-1

NOTES

EQUIPMENT CABINET OMITTED FOR CLARITY




H-FRAME GROUNDING DETAIL

NO SCALE 1


NOTES

CABLE GROUNDING NOT REQUIRED WHEN ANTENNA IS LESS THAN 10' FROM CABINET




TYPICAL GPS UNIT GROUNDING

NO SCALE 2




OUTDOOR CABINET GROUNDING

NO SCALE 3




TRANSITIONING GROUND DETAIL

NO SCALE 4



TYPICAL TEST GROUND ROD WITH INSPECTION SLEEVE

NO SCALE 5



TYPICAL GROUND RING TRENCH

NO SCALE 6

**dish**  
wireless.

5701 SOUTH SANTA FE DRIVE  
LITTLETON, CO 80120

**CROWN**  
**CASTLE**

2000 CORPORATE DRIVE  
CANONSBURG, PA 15317

**B+T GRP**

1717 S. BOULDER  
SUITE 300  
TULSA, OK 74119  
PH: (918) 587-4630  
www.btgrp.com



B&T ENGINEERING, INC.  
PEC.0001564  
Expires 2/10/22

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY: CHECKED BY: APPROVED BY:

JTS JTS MDW

RFDS REV #: 3.0

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	6/17/21	ISSUED FOR REVIEW
0	7/30/21	ISSUED FOR CONSTRUCTION
1	10/22/21	ISSUED FOR CONSTRUCTION
2	1/26/22	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER

136595.002.01

DISH Wireless L.L.C.  
PROJECT INFORMATION



NJJER01096A  
425 INDIAN LEDGE PARK RD  
TRUMBULL, CT 06611

SHEET TITLE  
GROUNDING DETAILS

SHEET NUMBER

G-2

1. EXOTHERMIC WELD (2) TWO, #2 AWG BARE TINNED SOLID COPPER CONDUCTORS TO GROUND BAR. ROUTE CONDUCTORS TO BURIED GROUND RING AND PROVIDE PARALLEL EXOTHERMIC WELD.
2. ALL EXTERIOR GROUNDING HARDWARE SHALL BE STAINLESS STEEL 3/8" DIAMETER OR LARGER. ALL HARDWARE 18-8 STAINLESS STEEL INCLUDING LOCK WASHERS, COAT ALL SURFACES WITH AN ANTI-OXIDANT COMPOUND BEFORE MATING.
3. FOR GROUND BOND TO STEEL ONLY: COAT ALL SURFACES WITH AN ANTI-OXIDANT COMPOUND BEFORE MATING.
4. DO NOT INSTALL CABLE GROUNDING KIT AT A BEND AND ALWAYS DIRECT GROUND CONDUCTOR DOWN TO GROUNDING BUS.
5. NUT & WASHER SHALL BE PLACED ON THE FRONT SIDE OF THE GROUND BAR AND BOLTED ON THE BACK SIDE.
6. ALL GROUNDING PARTS AND EQUIPMENT TO BE SUPPLIED AND INSTALLED BY CONTRACTOR.
7. THE CONTRACTOR SHALL BE RESPONSIBLE FOR INSTALLING ADDITIONAL GROUND BAR AS REQUIRED.
8. ENSURE THE WIRE INSULATION TERMINATION IS WITHIN 1/8" OF THE BARREL (NO SHINERS).



TYPICAL GROUNDING NOTES

NO SCALE

1

TYPICAL EXTERIOR TWO HOLE LUG


NO SCALE

2

TYPICAL INTERIOR TWO HOLE LUG

NO SCALE

3



LUG DETAIL

NO SCALE

4

NOT USED

NO SCALE

5

NOT USED

NO SCALE

6

NOT USED

NO SCALE

7

NOT USED

NO SCALE

8

NOT USED

NO SCALE

9

**dish**  
wireless.

5701 SOUTH SANTA FE DRIVE  
LITTLETON, CO 80120

**CROWN**  
**CASTLE**

2000 CORPORATE DRIVE  
CANONSBURG, PA 15317

**B+T GRP**

1717 S. BOULDER  
SUITE 300  
TULSA, OK 74119  
PH: (918) 587-4630  
www.btgrp.com



B&T ENGINEERING, INC.  
PEC.0001564  
Expires 2/10/22

IT IS A VIOLATION OF LAW FOR ANY PERSON,  
UNLESS THEY ARE ACTING UNDER THE DIRECTION  
OF A LICENSED PROFESSIONAL ENGINEER,  
TO ALTER THIS DOCUMENT.

DRAWN BY: CHECKED BY: APPROVED BY:

JTS JTS MDW

RFDS REV #: 3.0

CONSTRUCTION  
DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	6/17/21	ISSUED FOR REVIEW
0	7/30/21	ISSUED FOR CONSTRUCTION
1	10/22/21	ISSUED FOR CONSTRUCTION
2	1/26/22	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER  
136595.002.01

DISH Wireless L.L.C.  
PROJECT INFORMATION  
NJJER01096A  
425 INDIAN LEDGE PARK RD  
TRUMBULL, CT 06611

SHEET TITLE  
GROUNDING DETAILS

SHEET NUMBER

**G-3**



**RF JUMPER COLOR CODING**

3/4" TAPE WIDTHS WITH 3/4" SPACING

LOW-BAND RRH -  
(600MHz N71 BASEBAND) +  
(850MHz N26 BAND) +  
(700MHz N29 BAND) - OPTIONAL PER MARKET

ADD FREQUENCY COLOR TO SECTOR BAND  
(CBRS WILL USE YELLOW BANDS)

ALPHA RRH				BETA RRH				GAMMA RRH			
PORT 1 + SLANT	PORT 2 - SLANT	PORT 3 + SLANT	PORT 4 - SLANT	PORT 1 + SLANT	PORT 2 - SLANT	PORT 3 + SLANT	PORT 4 - SLANT	PORT 1 + SLANT	PORT 2 - SLANT	PORT 3 + SLANT	PORT 4 - SLANT
RED	RED	RED	RED	BLUE	BLUE	BLUE	BLUE	GREEN	GREEN	GREEN	GREEN
ORANGE	ORANGE	RED	RED	ORANGE	ORANGE	BLUE	BLUE	ORANGE	ORANGE	GREEN	GREEN
	WHITE (-) PORT	ORANGE	ORANGE		WHITE (-) PORT	ORANGE	ORANGE		WHITE (-) PORT	ORANGE	ORANGE
			WHITE (-) PORT				WHITE (-) PORT				WHITE (-) PORT

MID-BAND RRH -  
(AWS BANDS N66+N70)

ADD FREQUENCY COLOR TO SECTOR BAND  
(CBRS WILL USE YELLOW BANDS)

RED	RED	RED	RED	BLUE	BLUE	BLUE	BLUE	GREEN	GREEN	GREEN	GREEN
PURPLE	PURPLE	RED	RED	PURPLE	PURPLE	BLUE	BLUE	PURPLE	PURPLE	GREEN	GREEN
	WHITE (-) PORT	PURPLE	PURPLE		WHITE (-) PORT	PURPLE	PURPLE		WHITE (-) PORT	PURPLE	PURPLE
			WHITE (-) PORT				WHITE (-) PORT				WHITE (-) PORT

**HYBRID/DISCREET CABLES**

INCLUDE SECTOR BANDS BEING SUPPORTED  
ALONG WITH FREQUENCY BANDS

EXAMPLE 1 - HYBRID, OR DISCREET, SUPPORTS  
ALL SECTORS, BOTH LOW-BANDS AND MID-BANDS

EXAMPLE 2 - HYBRID, OR DISCREET, SUPPORTS  
CBRS ONLY, ALL SECTORS

EXAMPLE 1	EXAMPLE 2	EXAMPLE 3
RED	RED	RED
BLUE	BLUE	
GREEN	GREEN	ORANGE
ORANGE	YELLOW	PURPLE
PURPLE		

**FIBER JUMPERS TO RRHs**

LOW-BAND RRH FIBER CABLES HAVE SECTOR  
STRIPE ONLY

LOW BAND RRH	HIGH BAND RRH	LOW BAND RRH	HIGH BAND RRH	LOW BAND RRH	HIGH BAND RRH
RED	RED	BLUE	BLUE	GREEN	GREEN
	PURPLE		PURPLE		PURPLE

**POWER CABLES TO RRHs**

LOW-BAND RRH POWER CABLES HAVE SECTOR  
STRIPE ONLY

LOW BAND RRH	HIGH BAND RRH	LOW BAND RRH	HIGH BAND RRH	LOW BAND RRH	HIGH BAND RRH
RED	RED	BLUE	BLUE	GREEN	GREEN
	PURPLE		PURPLE		PURPLE

**RET MOTORS AT ANTENNAS**

ANTENNA 1 LOW BAND/ "IN"	ANTENNA 1 HIGH BAND/ "IN"	ANTENNA 1 LOW BAND/ "IN"	ANTENNA 1 HIGH BAND/ "IN"	ANTENNA 1 LOW BAND/ "IN"	ANTENNA 1 HIGH BAND/ "IN"
RED	RED	BLUE	BLUE	GREEN	GREEN
	PURPLE		PURPLE		PURPLE

**MICROWAVE RADIO LINKS**

LINKS WILL HAVE A 1.5-2 INCH WHITE WRAP WITH  
THE AZIMUTH COLOR OVERLAPPING IN THE MIDDLE.  
ADD ADDITIONAL SECTOR COLOR BANDS FOR EACH  
ADDITIONAL MW RADIO.

MICROWAVE CABLES WILL REQUIRE P-TOUCH  
LABELS INSIDE THE CABINET TO IDENTIFY THE  
LOCAL AND REMOTE SITE ID'S

FORWARD AZIMUTH OF 0-120 DEGREES		FORWARD AZIMUTH OF 120-240 DEGREES		FORWARD AZIMUTH OF 240-360 DEGREES	
PRIMARY	SECONDARY	PRIMARY	SECONDARY	PRIMARY	SECONDARY
WHITE	WHITE	WHITE	WHITE	WHITE	WHITE
RED	RED	BLUE	BLUE	GREEN	GREEN
WHITE	WHITE	WHITE	WHITE	WHITE	WHITE
	RED		BLUE		GREEN
	WHITE		WHITE		WHITE

RF CABLE COLOR CODES

NO SCALE

1

LOW BANDS (N71+N26)  
OPTIONAL - (N29)

ORANGE

CBRS TECH  
(3 GHz)

YELLOW

AWS  
(N66+N70+H-BLOCK)

PURPLE

NEGATIVE SLANT PORT  
ON ANT/RRH

WHITE

ALPHA SECTOR

RED

BETA SECTOR

BLUE

GAMMA SECTOR

GREEN

COLOR IDENTIFIER

NO SCALE

2

NOT USED

NO SCALE

3

NOT USED

NO SCALE

4

**dish**  
wireless.

5701 SOUTH SANTA FE DRIVE  
LITTLETON, CO 80120

**CROWN**  
CASTLE

2000 CORPORATE DRIVE  
CANONSBURG, PA 15317

**B+T GRP**  
1717 S. BOULDER  
SUITE 300  
TULSA, OK 74119  
PH: (918) 587-4630  
www.btgrp.com



B&T ENGINEERING, INC.  
PEC.0001564  
Expires 2/10/22

IT IS A VIOLATION OF LAW FOR ANY PERSON,  
UNLESS THEY ARE ACTING UNDER THE DIRECTION  
OF A LICENSED PROFESSIONAL ENGINEER,  
TO ALTER THIS DOCUMENT.

DRAWN BY: CHECKED BY: APPROVED BY:

JTS JTS MDW

RFDS REV #: 3.0

**CONSTRUCTION**  
DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	6/17/21	ISSUED FOR REVIEW
0	7/30/21	ISSUED FOR CONSTRUCTION
1	10/22/21	ISSUED FOR CONSTRUCTION
2	1/26/22	ISSUED FOR CONSTRUCTION


A&E PROJECT NUMBER  
136595.002.01

DISH Wireless L.L.C.  
PROJECT INFORMATION  
NJJER01096A  
425 INDIAN LEDGE PARK RD  
TRUMBULL, CT 06611

SHEET TITLE  
RF  
CABLE COLOR CODES

SHEET NUMBER  
**RF-1**

EXOTHERMIC CONNECTION  
 MECHANICAL CONNECTION  
 BUSS BAR INSULATOR  
 CHEMICAL ELECTROLYTIC GROUNDING SYSTEM  
 TEST CHEMICAL ELECTROLYTIC GROUNDING SYSTEM  
 EXOTHERMIC WITH INSPECTION SLEEVE  
 GROUNDING BAR  
 GROUND ROD  
 TEST GROUND ROD WITH INSPECTION SLEEVE  
 SINGLE POLE SWITCH  
 DUPLEX RECEPTACLE  
 DUPLEX GFCI RECEPTACLE  
 FLUORESCENT LIGHTING FIXTURE  
 (2) TWO LAMPS 48-T8  
 SMOKE DETECTION (DC)  
 EMERGENCY LIGHTING (DC)  
 SECURITY LIGHT W/PHOTOCELL LITHONIA ALXW  
 LED-1-25A400/51K-SR4-120-PE-DBTDX  
 CHAIN LINK FENCE  
 WOOD/WROUGHT IRON FENCE  
 WALL STRUCTURE  
 LEASE AREA  
 PROPERTY LINE (PL)  
 SETBACKS  
 ICE BRIDGE  
 CABLE TRAY  
 WATER LINE  
 UNDERGROUND POWER  
 UNDERGROUND TELCO  
 OVERHEAD POWER  
 OVERHEAD TELCO  
 UNDERGROUND TELCO/POWER  
 ABOVE GROUND POWER  
 ABOVE GROUND TELCO  
 ABOVE GROUND TELCO/POWER  
 WORKPOINT  
 SECTION REFERENCE  
 DETAIL REFERENCE



LEGEND

AB ANCHOR BOLT  
 ABV ABOVE  
 AC ALTERNATING CURRENT  
 ADDL ADDITIONAL  
 AFF ABOVE FINISHED FLOOR  
 AFG ABOVE FINISHED GRADE  
 AGL ABOVE GROUND LEVEL  
 AIC AMPERAGE INTERRUPTION CAPACITY  
 ALUM ALUMINUM  
 ALT ALTERNATE  
 ANT ANTENNA  
 APPROX APPROXIMATE  
 ARCH ARCHITECTURAL  
 ATS AUTOMATIC TRANSFER SWITCH  
 AWG AMERICAN WIRE GAUGE  
 BATT BATTERY  
 BLDG BUILDING  
 BLK BLOCK  
 BLKG BLOCKING  
 BM BEAM  
 BTC BARE TINNED COPPER CONDUCTOR  
 BOF BOTTOM OF FOOTING  
 CAB CABINET  
 CANT CANTILEVERED  
 CHG CHARGING  
 CLG CEILING  
 CLR CLEAR  
 COL COLUMN  
 COMM COMMON  
 CONC CONCRETE  
 CONSTR CONSTRUCTION  
 DBL DOUBLE  
 DC DIRECT CURRENT  
 DEPT DEPARTMENT  
 DF DOUGLAS FIR  
 DIA DIAMETER  
 DIAG DIAGONAL  
 DIM DIMENSION  
 DWG DRAWING  
 DWL DOWEL  
 EA EACH  
 EC ELECTRICAL CONDUCTOR  
 EL ELEVATION  
 ELEC ELECTRICAL  
 EMT ELECTRICAL METALLIC TUBING  
 ENG ENGINEER  
 EQ EQUAL  
 EXP EXPANSION  
 EXT EXTERIOR  
 EW EACH WAY  
 FAB FABRICATION  
 FF FINISH FLOOR  
 FG FINISH GRADE  
 FIF FACILITY INTERFACE FRAME  
 FIN FINISH(ED)  
 FLR FLOOR  
 FDN FOUNDATION  
 FOC FACE OF CONCRETE  
 FOM FACE OF MASONRY  
 FOS FACE OF STUD  
 FOW FACE OF WALL  
 FS FINISH SURFACE  
 FT FOOT  
 FTG FOOTING  
 GA GAUGE  
 GEN GENERATOR  
 GFCI GROUND FAULT CIRCUIT INTERRUPTER  
 GLB GLUE LAMINATED BEAM  
 GLV GALVANIZED  
 GPS GLOBAL POSITIONING SYSTEM  
 GND GROUND  
 GSM GLOBAL SYSTEM FOR MOBILE  
 HDG HOT DIPPED GALVANIZED  
 HDR HEADER  
 HGR HANGER  
 HVAC HEAT/VENTILATION/AIR CONDITIONING  
 HT HEIGHT  
 IGR INTERIOR GROUND RING  
 IN INCH  
 INT INTERIOR  
 LB(S) POUND(S)  
 LF LINEAR FEET  
 LTE LONG TERM EVOLUTION  
 MAS MASONRY  
 MAX MAXIMUM  
 MB MACHINE BOLT  
 MECH MECHANICAL  
 MFR MANUFACTURER  
 MGB MASTER GROUND BAR  
 MIN MINIMUM  
 MISC MISCELLANEOUS  
 MTL METAL  
 MTS MANUAL TRANSFER SWITCH  
 MW MICROWAVE  
 NEC NATIONAL ELECTRIC CODE  
 NM NEWTON METERS  
 NO. NUMBER  
 # NUMBER  
 NTS NOT TO SCALE  
 OC ON-CENTER  
 OSHA OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION  
 OPNG OPENING  
 P/C PRECAST CONCRETE  
 PCS PERSONAL COMMUNICATION SERVICES  
 PCU PRIMARY CONTROL UNIT  
 PRC PRIMARY RADIO CABINET  
 PP POLARIZING PRESERVING  
 PSF POUNDS PER SQUARE FOOT  
 PSI POUNDS PER SQUARE INCH  
 PT PRESSURE TREATED  
 PWR POWER CABINET  
 QTY QUANTITY  
 RAD RADIUS  
 RECT RECTIFIER  
 REF REFERENCE  
 REINF REINFORCEMENT  
 REQ'D REQUIRED  
 RET REMOTE ELECTRIC TILT  
 RF RADIO FREQUENCY  
 RMC RIGID METALLIC CONDUIT  
 RRH REMOTE RADIO HEAD  
 RRU REMOTE RADIO UNIT  
 RWY RACEWAY  
 SCH SCHEDULE  
 SHT SHEET  
 SIAD SMART INTEGRATED ACCESS DEVICE  
 SIM SIMILAR  
 SPEC SPECIFICATION  
 SQ SQUARE  
 SS STAINLESS STEEL  
 STD STANDARD  
 STL STEEL  
 TEMP TEMPORARY  
 THK THICKNESS  
 TMA TOWER MOUNTED AMPLIFIER  
 TN TOE NAIL  
 TOA TOP OF ANTENNA  
 TOC TOP OF CURB  
 TOF TOP OF FOUNDATION  
 TOP TOP OF PLATE (PARAPET)  
 TOS TOP OF STEEL  
 TOW TOP OF WALL  
 TVSS TRANSIENT VOLTAGE SURGE SUPPRESSION  
 TYP TYPICAL  
 UG UNDERGROUND  
 UL UNDERWRITERS LABORATORY  
 UNO UNLESS NOTED OTHERWISE  
 UMTS UNIVERSAL MOBILE TELECOMMUNICATIONS SYSTEM  
 UPS UNINTERRUPTIBLE POWER SYSTEM (DC POWER PLANT)  
 VIF VERIFIED IN FIELD  
 W WIDE  
 W/ WITH  
 WD WOOD  
 WP WEATHERPROOF  
 WT WEIGHT

ABBREVIATIONS



5701 SOUTH SANTA FE DRIVE  
 LITTLETON, CO 80120



2000 CORPORATE DRIVE  
 CANONSBURG, PA 15317



1717 S. BOULDER  
 SUITE 300  
 TULSA, OK 74119  
 PH: (918) 587-4630  
 www.btgrp.com



B&T ENGINEERING, INC.  
 PEC.0001564  
 Expires 2/10/22

IT IS A VIOLATION OF LAW FOR ANY PERSON,  
 UNLESS THEY ARE ACTING UNDER THE DIRECTION  
 OF A LICENSED PROFESSIONAL ENGINEER,  
 TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
JTS	JTS	MDW

RFDS REV #: 3.0

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	6/17/21	ISSUED FOR REVIEW
0	7/30/21	ISSUED FOR CONSTRUCTION
1	10/22/21	ISSUED FOR CONSTRUCTION
2	1/26/22	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER  
 136595.002.01

DISH Wireless L.L.C.  
 PROJECT INFORMATION  
 NJJER01096A  
 425 INDIAN LEDGE PARK RD  
 TRUMBULL, CT 06611

SHEET TITLE  
 LEGEND AND ABBREVIATIONS

SHEET NUMBER  
 GN-1

SITE ACTIVITY REQUIREMENTS:

- NOTICE TO PROCEED – NO WORK SHALL COMMENCE PRIOR TO CONTRACTOR RECEIVING A WRITTEN NOTICE TO PROCEED (NTP) AND THE ISSUANCE OF A PURCHASE ORDER. PRIOR TO ACCESSING/ENTERING THE SITE YOU MUST CONTACT THE DISH Wireless L.L.C. AND TOWER OWNER NOC & THE DISH Wireless L.L.C. AND TOWER OWNER CONSTRUCTION MANAGER.
- "LOOK UP" – DISH Wireless L.L.C. AND TOWER OWNER SAFETY CLIMB REQUIREMENT:  
THE INTEGRITY OF THE SAFETY CLIMB AND ALL COMPONENTS OF THE CLIMBING FACILITY SHALL BE CONSIDERED DURING ALL STAGES OF DESIGN, INSTALLATION, AND INSPECTION. TOWER MODIFICATION, MOUNT REINFORCEMENTS, AND/OR EQUIPMENT INSTALLATIONS SHALL NOT COMPROMISE THE INTEGRITY OR FUNCTIONAL USE OF THE SAFETY CLIMB OR ANY COMPONENTS OF THE CLIMBING FACILITY ON THE STRUCTURE. THIS SHALL INCLUDE, BUT NOT BE LIMITED TO: PINCHING OF THE WIRE ROPE, BENDING OF THE WIRE ROPE FROM ITS SUPPORTS, DIRECT CONTACT OR CLOSE PROXIMITY TO THE WIRE ROPE WHICH MAY CAUSE FRICTIONAL WEAR, IMPACT TO THE ANCHORAGE POINTS IN ANY WAY, OR TO IMPEDE/BLOCK ITS INTENDED USE. ANY COMPROMISED SAFETY CLIMB, INCLUDING EXISTING CONDITIONS MUST BE TAGGED OUT AND REPORTED TO YOUR DISH Wireless L.L.C. AND DISH Wireless L.L.C. AND TOWER OWNER POC OR CALL THE NOC TO GENERATE A SAFETY CLIMB MAINTENANCE AND CONTRACTOR NOTICE TICKET.
- PRIOR TO THE START OF CONSTRUCTION, ALL REQUIRED JURISDICTIONAL PERMITS SHALL BE OBTAINED. THIS INCLUDES, BUT IS NOT LIMITED TO, BUILDING, ELECTRICAL, MECHANICAL, FIRE, FLOOD ZONE, ENVIRONMENTAL, AND ZONING. AFTER ONSITE ACTIVITIES AND CONSTRUCTION ARE COMPLETED, ALL REQUIRED PERMITS SHALL BE SATISFIED AND CLOSED OUT ACCORDING TO LOCAL JURISDICTIONAL REQUIREMENTS.
- ALL CONSTRUCTION MEANS AND METHODS; INCLUDING BUT NOT LIMITED TO, ERECTION PLANS, RIGGING PLANS, CLIMBING PLANS, AND RESCUE PLANS SHALL BE THE RESPONSIBILITY OF THE GENERAL CONTRACTOR RESPONSIBLE FOR THE EXECUTION OF THE WORK CONTAINED HEREIN, AND SHALL MEET ANSI/ASSE A10.48 (LATEST EDITION); FEDERAL, STATE, AND LOCAL REGULATIONS; AND ANY APPLICABLE INDUSTRY CONSENSUS STANDARDS RELATED TO THE CONSTRUCTION ACTIVITIES BEING PERFORMED. ALL RIGGING PLANS SHALL ADHERE TO ANSI/ASSE A10.48 (LATEST EDITION) AND DISH Wireless L.L.C. AND TOWER OWNER STANDARDS, INCLUDING THE REQUIRED INVOLVEMENT OF A QUALIFIED ENGINEER FOR CLASS IV CONSTRUCTION, TO CERTIFY THE SUPPORTING STRUCTURE(S) IN ACCORDANCE WITH ANSI/TIA-322 (LATEST EDITION).
- ALL SITE WORK TO COMPLY WITH DISH Wireless L.L.C. AND TOWER OWNER INSTALLATION STANDARDS FOR CONSTRUCTION ACTIVITIES ON DISH Wireless L.L.C. AND TOWER OWNER TOWER SITE AND LATEST VERSION OF ANSI/TIA-1019-A-2012 "STANDARD FOR INSTALLATION, ALTERATION, AND MAINTENANCE OF ANTENNA SUPPORTING STRUCTURES AND ANTENNAS."
- IF THE SPECIFIED EQUIPMENT CAN NOT BE INSTALLED AS SHOWN ON THESE DRAWINGS, THE CONTRACTOR SHALL PROPOSE AN ALTERNATIVE INSTALLATION FOR APPROVAL BY DISH Wireless L.L.C. AND TOWER OWNER PRIOR TO PROCEEDING WITH ANY SUCH CHANGE OF INSTALLATION.
- ALL MATERIALS FURNISHED AND INSTALLED SHALL BE IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS AND ORDINANCES. CONTRACTOR SHALL ISSUE ALL APPROPRIATE NOTICES AND COMPLY WITH ALL LAWS, ORDINANCES, RULES, REGULATIONS AND LAWFUL ORDERS OF ANY PUBLIC AUTHORITY REGARDING THE PERFORMANCE OF THE WORK. ALL WORK CARRIED OUT SHALL COMPLY WITH ALL APPLICABLE MUNICIPAL AND UTILITY COMPANY SPECIFICATIONS AND LOCAL JURISDICTIONAL CODES, ORDINANCES AND APPLICABLE REGULATIONS.
- THE CONTRACTOR SHALL INSTALL ALL EQUIPMENT AND MATERIALS IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS UNLESS SPECIFICALLY STATED OTHERWISE.
- THE CONTRACTOR SHALL CONTACT UTILITY LOCATING SERVICES INCLUDING PRIVATE LOCATES SERVICES PRIOR TO THE START OF CONSTRUCTION.
- ALL EXISTING ACTIVE SEWER, WATER, GAS, ELECTRIC AND OTHER UTILITIES WHERE ENCOUNTERED IN THE WORK, SHALL BE PROTECTED AT ALL TIMES AND WHERE REQUIRED FOR THE PROPER EXECUTION OF THE WORK, SHALL BE RELOCATED AS DIRECTED BY CONTRACTOR. EXTREME CAUTION SHOULD BE USED BY THE CONTRACTOR WHEN EXCAVATING OR DRILLING PIERS AROUND OR NEAR UTILITIES. CONTRACTOR SHALL PROVIDE SAFETY TRAINING FOR THE WORKING CREW. THIS WILL INCLUDE BUT NOT BE LIMITED TO A) FALL PROTECTION B) CONFINED SPACE C) ELECTRICAL SAFETY D) TRENCHING AND EXCAVATION E) CONSTRUCTION SAFETY PROCEDURES.
- ALL SITE WORK SHALL BE AS INDICATED ON THE STAMPED CONSTRUCTION DRAWINGS AND DISH PROJECT SPECIFICATIONS, LATEST APPROVED REVISION.
- CONTRACTOR SHALL KEEP THE SITE FREE FROM ACCUMULATING WASTE MATERIAL, DEBRIS, AND TRASH AT THE COMPLETION OF THE WORK. IF NECESSARY, RUBBISH, STUMPS, DEBRIS, STICKS, STONES AND OTHER REFUSE SHALL BE REMOVED FROM THE SITE AND DISPOSED OF LEGALLY.
- ALL EXISTING INACTIVE SEWER, WATER, GAS, ELECTRIC AND OTHER UTILITIES, WHICH INTERFERE WITH THE EXECUTION OF THE WORK, SHALL BE REMOVED AND/OR CAPPED, PLUGGED OR OTHERWISE DISCONTINUED AT POINTS WHICH WILL NOT INTERFERE WITH THE EXECUTION OF THE WORK, SUBJECT TO THE APPROVAL OF DISH Wireless L.L.C. AND TOWER OWNER, AND/OR LOCAL UTILITIES.
- THE CONTRACTOR SHALL PROVIDE SITE SIGNAGE IN ACCORDANCE WITH THE TECHNICAL SPECIFICATION FOR SITE SIGNAGE REQUIRED BY LOCAL JURISDICTION AND SIGNAGE REQUIRED ON INDIVIDUAL PIECES OF EQUIPMENT, ROOMS, AND SHELTERS.
- THE SITE SHALL BE GRADED TO CAUSE SURFACE WATER TO FLOW AWAY FROM THE CARRIER'S EQUIPMENT AND TOWER AREAS.
- THE SUB GRADE SHALL BE COMPACTED AND BROUGHT TO A SMOOTH UNIFORM GRADE PRIOR TO FINISHED SURFACE APPLICATION.
- THE AREAS OF THE OWNERS PROPERTY DISTURBED BY THE WORK AND NOT COVERED BY THE TOWER, EQUIPMENT OR DRIVEWAY, SHALL BE GRADED TO A UNIFORM SLOPE, AND STABILIZED TO PREVENT EROSION AS SPECIFIED ON THE CONSTRUCTION DRAWINGS AND/OR PROJECT SPECIFICATIONS.
- CONTRACTOR SHALL MINIMIZE DISTURBANCE TO EXISTING SITE DURING CONSTRUCTION. EROSION CONTROL MEASURES, IF REQUIRED DURING CONSTRUCTION, SHALL BE IN CONFORMANCE WITH THE LOCAL GUIDELINES FOR EROSION AND SEDIMENT CONTROL.
- THE CONTRACTOR SHALL PROTECT EXISTING IMPROVEMENTS, PAVEMENTS, CURBS, LANDSCAPING AND STRUCTURES. ANY DAMAGED PART SHALL BE REPAIRED AT CONTRACTOR'S EXPENSE TO THE SATISFACTION OF OWNER.
- CONTRACTOR SHALL LEGALLY AND PROPERLY DISPOSE OF ALL SCRAP MATERIALS SUCH AS COAXIAL CABLES AND OTHER ITEMS REMOVED FROM THE EXISTING FACILITY. ANTENNAS AND RADIOS REMOVED SHALL BE RETURNED TO THE OWNER'S DESIGNATED LOCATION.
- CONTRACTOR SHALL LEAVE PREMISES IN CLEAN CONDITION. TRASH AND DEBRIS SHOULD BE REMOVED FROM SITE ON A DAILY BASIS.
- NO FILL OR EMBANKMENT MATERIAL SHALL BE PLACED ON FROZEN GROUND. FROZEN MATERIALS, SNOW OR ICE SHALL NOT BE PLACED IN ANY FILL OR EMBANKMENT.

GENERAL NOTES:

- FOR THE PURPOSE OF CONSTRUCTION DRAWING, THE FOLLOWING DEFINITIONS SHALL APPLY:  
CONTRACTOR:GENERAL CONTRACTOR RESPONSIBLE FOR CONSTRUCTION  
CARRIER:DISH Wireless L.L.C.  
TOWER OWNER:TOWER OWNER
- THESE DRAWINGS HAVE BEEN PREPARED USING STANDARDS OF PROFESSIONAL CARE AND COMPLETENESS NORMALLY EXERCISED UNDER SIMILAR CIRCUMSTANCES BY REPUTABLE ENGINEERS IN THIS OR SIMILAR LOCALITIES. IT IS ASSUMED THAT THE WORK DEPICTED WILL BE PERFORMED BY AN EXPERIENCED CONTRACTOR AND/OR WORKPEOPLE WHO HAVE A WORKING KNOWLEDGE OF THE APPLICABLE CODE STANDARDS AND REQUIREMENTS AND OF INDUSTRY ACCEPTED STANDARD GOOD PRACTICE. AS NOT EVERY CONDITION OR ELEMENT IS (OR CAN BE) EXPLICITLY SHOWN ON THESE DRAWINGS, THE CONTRACTOR SHALL USE INDUSTRY ACCEPTED STANDARD GOOD PRACTICE FOR MISCELLANEOUS WORK NOT EXPLICITLY SHOWN.
- THESE DRAWINGS REPRESENT THE FINISHED STRUCTURE. THEY DO NOT INDICATE THE MEANS OR METHODS OF CONSTRUCTION. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR THE CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES. THE CONTRACTOR SHALL PROVIDE ALL MEASURES NECESSARY FOR PROTECTION OF LIFE AND PROPERTY DURING CONSTRUCTION. SUCH MEASURES SHALL INCLUDE, BUT NOT BE LIMITED TO, BRACING, FORMWORK, SHORING, ETC. SITE VISITS BY THE ENGINEER OR HIS REPRESENTATIVE WILL NOT INCLUDE INSPECTION OF THESE ITEMS AND IS FOR STRUCTURAL OBSERVATION OF THE FINISHED STRUCTURE ONLY.
- NOTES AND DETAILS IN THE CONSTRUCTION DRAWINGS SHALL TAKE PRECEDENCE OVER GENERAL NOTES AND TYPICAL DETAILS. WHERE NO DETAILS ARE SHOWN, CONSTRUCTION SHALL CONFORM TO SIMILAR WORK ON THE PROJECT, AND/OR AS PROVIDED FOR IN THE CONTRACT DOCUMENTS. WHERE DISCREPANCIES OCCUR BETWEEN PLANS, DETAILS, GENERAL NOTES, AND SPECIFICATIONS, THE GREATER, MORE STRICT REQUIREMENTS, SHALL GOVERN. IF FURTHER CLARIFICATION IS REQUIRED CONTACT THE ENGINEER OF RECORD.
- SUBSTANTIAL EFFORT HAS BEEN MADE TO PROVIDE ACCURATE DIMENSIONS AND MEASUREMENTS ON THE DRAWINGS TO ASSIST IN THE FABRICATION AND/OR PLACEMENT OF CONSTRUCTION ELEMENTS BUT IT IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR TO FIELD VERIFY THE DIMENSIONS, MEASUREMENTS, AND/OR CLEARANCES SHOWN IN THE CONSTRUCTION DRAWINGS PRIOR TO FABRICATION OR CUTTING OF ANY NEW OR EXISTING CONSTRUCTION ELEMENTS. IF IT IS DETERMINED THAT THERE ARE DISCREPANCIES AND/OR CONFLICTS WITH THE CONSTRUCTION DRAWINGS THE ENGINEER OF RECORD IS TO BE NOTIFIED AS SOON AS POSSIBLE.
- PRIOR TO THE SUBMISSION OF BIDS, THE BIDDING CONTRACTOR SHALL VISIT THE CELL SITE TO FAMILIARIZE WITH THE EXISTING CONDITIONS AND TO CONFIRM THAT THE WORK CAN BE ACCOMPLISHED AS SHOWN ON THE CONSTRUCTION DRAWINGS. ANY DISCREPANCY FOUND SHALL BE BROUGHT TO THE ATTENTION OF CARRIER POC AND TOWER OWNER.
- ALL MATERIALS FURNISHED AND INSTALLED SHALL BE IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS AND ORDINANCES. CONTRACTOR SHALL ISSUE ALL APPROPRIATE NOTICES AND COMPLY WITH ALL LAWS, ORDINANCES, RULES, REGULATIONS AND LAWFUL ORDERS OF ANY PUBLIC AUTHORITY REGARDING THE PERFORMANCE OF THE WORK. ALL WORK CARRIED OUT SHALL COMPLY WITH ALL APPLICABLE MUNICIPAL AND UTILITY COMPANY SPECIFICATIONS AND LOCAL JURISDICTIONAL CODES, ORDINANCES AND APPLICABLE REGULATIONS.
- UNLESS NOTED OTHERWISE, THE WORK SHALL INCLUDE FURNISHING MATERIALS, EQUIPMENT, APPURTENANCES AND LABOR NECESSARY TO COMPLETE ALL INSTALLATIONS AS INDICATED ON THE DRAWINGS.
- THE CONTRACTOR SHALL INSTALL ALL EQUIPMENT AND MATERIALS IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS UNLESS SPECIFICALLY STATED OTHERWISE.
- IF THE SPECIFIED EQUIPMENT CAN NOT BE INSTALLED AS SHOWN ON THESE DRAWINGS, THE CONTRACTOR SHALL PROPOSE AN ALTERNATIVE INSTALLATION FOR APPROVAL BY THE CARRIER AND TOWER OWNER PRIOR TO PROCEEDING WITH ANY SUCH CHANGE OF INSTALLATION.
- CONTRACTOR IS TO PERFORM A SITE INVESTIGATION, BEFORE SUBMITTING BIDS, TO DETERMINE THE BEST ROUTING OF ALL CONDUITS FOR POWER, AND TELCO AND FOR GROUNDING CABLES AS SHOWN IN THE POWER, TELCO, AND GROUNDING PLAN DRAWINGS.
- THE CONTRACTOR SHALL PROTECT EXISTING IMPROVEMENTS, PAVEMENTS, CURBS, LANDSCAPING AND STRUCTURES. ANY DAMAGED PART SHALL BE REPAIRED AT CONTRACTOR'S EXPENSE TO THE SATISFACTION OF DISH Wireless L.L.C. AND TOWER OWNER
- CONTRACTOR SHALL LEGALLY AND PROPERLY DISPOSE OF ALL SCRAP MATERIALS SUCH AS COAXIAL CABLES AND OTHER ITEMS REMOVED FROM THE EXISTING FACILITY. ANTENNAS REMOVED SHALL BE RETURNED TO THE OWNER'S DESIGNATED LOCATION.
- CONTRACTOR SHALL LEAVE PREMISES IN CLEAN CONDITION. TRASH AND DEBRIS SHOULD BE REMOVED FROM SITE ON A DAILY BASIS.



5701 SOUTH SANTA FE DRIVE  
LITTLETON, CO 80120



2000 CORPORATE DRIVE  
CANONSBURG, PA 15317



1717 S. BOULDER  
SUITE 300  
TULSA, OK 74119  
PH: (918) 587-4630  
www.btgrp.com



B&T ENGINEERING, INC.  
PEC.0001564  
Expires 2/10/22

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
JTS	JTS	MDW

RFDS REV #: 3.0

**CONSTRUCTION DOCUMENTS**

SUBMITTALS		
REV	DATE	DESCRIPTION
A	6/17/21	ISSUED FOR REVIEW
0	7/30/21	ISSUED FOR CONSTRUCTION
1	10/22/21	ISSUED FOR CONSTRUCTION
2	1/26/22	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER  
**136595.002.01**

DISH Wireless L.L.C.  
PROJECT INFORMATION  
**NJJER01096A**  
425 INDIAN LEDGE PARK RD  
TRUMBULL, CT 06611

SHEET TITLE  
**GENERAL NOTES**

SHEET NUMBER  
**GN-2**

CONCRETE, FOUNDATIONS, AND REINFORCING STEEL:

- ALL CONCRETE WORK SHALL BE IN ACCORDANCE WITH THE ACI 301, ACI 318, ACI 336, ASTM A184, ASTM A185 AND THE DESIGN AND CONSTRUCTION SPECIFICATION FOR CAST-IN-PLACE CONCRETE.
- UNLESS NOTED OTHERWISE, SOIL BEARING PRESSURE USED FOR DESIGN OF SLABS AND FOUNDATIONS IS ASSUMED TO BE 1000 psf.
- ALL CONCRETE SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH (f'c) OF 3000 psi AT 28 DAYS, UNLESS NOTED OTHERWISE. NO MORE THAN 90 MINUTES SHALL ELAPSE FROM BATCH TIME TO TIME OF PLACEMENT UNLESS APPROVED BY THE ENGINEER OF RECORD. TEMPERATURE OF CONCRETE SHALL NOT EXCEED 90°f AT TIME OF PLACEMENT.
- CONCRETE EXPOSED TO FREEZE-THAW CYCLES SHALL CONTAIN AIR ENTRAINING ADMIXTURES. AMOUNT OF AIR ENTRAINMENT TO BE BASED ON SIZE OF AGGREGATE AND F3 CLASS EXPOSURE (VERY SEVERE). CEMENT USED TO BE TYPE II PORTLAND CEMENT WITH A MAXIMUM WATER-TO-CEMENT RATIO (W/C) OF 0.45.
- ALL STEEL REINFORCING SHALL CONFORM TO ASTM A615. ALL WELDED WIRE FABRIC (WWF) SHALL CONFORM TO ASTM A185. ALL SPLICES SHALL BE CLASS "B" TENSION SPLICES, UNLESS NOTED OTHERWISE. ALL HOOKS SHALL BE STANDARD 90 DEGREE HOOKS, UNLESS NOTED OTHERWISE. YIELD STRENGTH (Fy) OF STANDARD DEFORMED BARS ARE AS FOLLOWS:  
#4 BARS AND SMALLER 40 ksi  
#5 BARS AND LARGER 60 ksi
- THE FOLLOWING MINIMUM CONCRETE COVER SHALL BE PROVIDED FOR REINFORCING STEEL UNLESS SHOWN OTHERWISE ON DRAWINGS:
  - CONCRETE CAST AGAINST AND PERMANENTLY EXPOSED TO EARTH 3"
  - CONCRETE EXPOSED TO EARTH OR WEATHER:
    - #6 BARS AND LARGER 2"
    - #5 BARS AND SMALLER 1-1/2"
  - CONCRETE NOT EXPOSED TO EARTH OR WEATHER:
    - SLAB AND WALLS 3/4"
    - BEAMS AND COLUMNS 1-1/2"
- A TOOLED EDGE OR A 3/4" CHAMFER SHALL BE PROVIDED AT ALL EXPOSED EDGES OF CONCRETE, UNLESS NOTED OTHERWISE, IN ACCORDANCE WITH ACI 301 SECTION 4.2.4.

ELECTRICAL INSTALLATION NOTES:

- ALL ELECTRICAL WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS, NEC AND ALL APPLICABLE FEDERAL, STATE, AND LOCAL CODES/ORDINANCES.
- CONDUIT ROUTINGS ARE SCHEMATIC. CONTRACTOR SHALL INSTALL CONDUITS SO THAT ACCESS TO EQUIPMENT IS NOT BLOCKED AND TRIP HAZARDS ARE ELIMINATED.
- WIRING, RACEWAY AND SUPPORT METHODS AND MATERIALS SHALL COMPLY WITH THE REQUIREMENTS OF THE NEC.
- ALL CIRCUITS SHALL BE SEGREGATED AND MAINTAIN MINIMUM CABLE SEPARATION AS REQUIRED BY THE NEC.
  - ALL EQUIPMENT SHALL BEAR THE UNDERWRITERS LABORATORIES LABEL OF APPROVAL, AND SHALL CONFORM TO REQUIREMENT OF THE NATIONAL ELECTRICAL CODE.
  - ALL OVERCURRENT DEVICES SHALL HAVE AN INTERRUPTING CURRENT RATING THAT SHALL BE GREATER THAN THE SHORT CIRCUIT CURRENT TO WHICH THEY ARE SUBJECTED, 22,000 AIC MINIMUM. VERIFY AVAILABLE SHORT CIRCUIT CURRENT DOES NOT EXCEED THE RATING OF ELECTRICAL EQUIPMENT IN ACCORDANCE WITH ARTICLE 110.24 NEC OR THE MOST CURRENT ADOPTED CODE PRE THE GOVERNING JURISDICTION.
- EACH END OF EVERY POWER PHASE CONDUCTOR, GROUNDING CONDUCTOR, AND TELCO CONDUCTOR OR CABLE SHALL BE LABELED WITH COLOR-CODED INSULATION OR ELECTRICAL TAPE (3M BRAND, 1/2" PLASTIC ELECTRICAL TAPE WITH UV PROTECTION, OR EQUAL). THE IDENTIFICATION METHOD SHALL CONFORM WITH NEC AND OSHA.
- ALL ELECTRICAL COMPONENTS SHALL BE CLEARLY LABELED WITH LAMICOID TAGS SHOWING THEIR RATED VOLTAGE, PHASE CONFIGURATION, WIRE CONFIGURATION, POWER OR AMPACITY RATING AND BRANCH CIRCUIT ID NUMBERS (i.e. PANEL BOARD AND CIRCUIT ID'S).
- PANEL BOARDS (ID NUMBERS) SHALL BE CLEARLY LABELED WITH PLASTIC LABELS.
- TIE WRAPS ARE NOT ALLOWED.
- ALL POWER AND EQUIPMENT GROUND WIRING IN TUBING OR CONDUIT SHALL BE SINGLE COPPER CONDUCTOR (#14 OR LARGER) WITH TYPE THHW, THWN, THWN-2, XHHW, XHHW-2, THW, THW-2, RHW, OR RHW-2 INSULATION UNLESS OTHERWISE SPECIFIED.
- SUPPLEMENTAL EQUIPMENT GROUND WIRING LOCATED INDOORS SHALL BE SINGLE COPPER CONDUCTOR (#6 OR LARGER) WITH TYPE THHW, THWN, THWN-2, XHHW, XHHW-2, THW, THW-2, RHW, OR RHW-2 INSULATION UNLESS OTHERWISE SPECIFIED.
- POWER AND CONTROL WIRING IN FLEXIBLE CORD SHALL BE MULTI-CONDUCTOR, TYPE SOOW CORD (#14 OR LARGER) UNLESS OTHERWISE SPECIFIED.
- POWER AND CONTROL WIRING FOR USE IN CABLE TRAY SHALL BE MULTI-CONDUCTOR, TYPE TC CABLE (#14 OR LARGER), WITH TYPE THHW, THWN, THWN-2, XHHW, XHHW-2, THW, THW-2, RHW, OR RHW-2 INSULATION UNLESS OTHERWISE SPECIFIED.
- ALL POWER AND GROUNDING CONNECTIONS SHALL BE CRIMP-STYLE, COMPRESSION WIRE LUGS AND WIRE NUTS BY THOMAS AND BETTS (OR EQUAL). LUGS AND WIRE NUTS SHALL BE RATED FOR OPERATION NOT LESS THAN 75° C (90° C IF AVAILABLE).
- RACEWAY AND CABLE TRAY SHALL BE LISTED OR LABELED FOR ELECTRICAL USE IN ACCORDANCE WITH NEMA, UL, ANSI/IEEE AND NEC.
- ELECTRICAL METALLIC TUBING (EMT), INTERMEDIATE METAL CONDUIT (IMC), OR RIGID METAL CONDUIT (RMC) SHALL BE USED FOR EXPOSED INDOOR LOCATIONS.

- ELECTRICAL METALLIC TUBING (EMT) OR METAL-CLAD CABLE (MC) SHALL BE USED FOR CONCEALED INDOOR LOCATIONS.
- SCHEDULE 40 PVC UNDERGROUND ON STRAIGHTS AND SCHEDULE 80 PVC FOR ALL ELBOWS/90s AND ALL APPROVED ABOVE GRADE PVC CONDUIT.
- LIQUID-TIGHT FLEXIBLE METALLIC CONDUIT (LIQUID-TITE FLEX) SHALL BE USED INDOORS AND OUTDOORS, WHERE VIBRATION OCCURS OR FLEXIBILITY IS NEEDED.
- CONDUIT AND TUBING FITTINGS SHALL BE THREADED OR COMPRESSION-TYPE AND APPROVED FOR THE LOCATION USED. SET SCREW FITTINGS ARE NOT ACCEPTABLE.
- CABINETS, BOXES AND WIRE WAYS SHALL BE LABELED FOR ELECTRICAL USE IN ACCORDANCE WITH NEMA, UL, ANSI/IEEE AND THE NEC.
- WIREWAYS SHALL BE METAL WITH AN ENAMEL FINISH AND INCLUDE A HINGED COVER, DESIGNED TO SWING OPEN DOWNWARDS (WIREMOLD SPECMATE WIREWAY).
- SLOTTED WIRING DUCT SHALL BE PVC AND INCLUDE COVER (PANDUIT TYPE E OR EQUAL).
- CONDUITS SHALL BE FASTENED SECURELY IN PLACE WITH APPROVED NON-PERFORATED STRAPS AND HANGERS. EXPLOSIVE DEVICES (i.e. POWDER-ACTUATED) FOR ATTACHING HANGERS TO STRUCTURE WILL NOT BE PERMITTED. CLOSELY FOLLOW THE LINES OF THE STRUCTURE, MAINTAIN CLOSE PROXIMITY TO THE STRUCTURE AND KEEP CONDUITS IN TIGHT ENVELOPES. CHANGES IN DIRECTION TO ROUTE AROUND OBSTACLES SHALL BE MADE WITH CONDUIT OUTLET BODIES. CONDUIT SHALL BE INSTALLED IN A NEAT AND WORKMANLIKE MANNER. PARALLEL AND PERPENDICULAR TO STRUCTURE WALL AND CEILING LINES. ALL CONDUIT SHALL BE FISHED TO CLEAR OBSTRUCTIONS. ENDS OF CONDUITS SHALL BE TEMPORARILY CAPPED FLUSH TO FINISH GRADE TO PREVENT CONCRETE, PLASTER OR DIRT FROM ENTERING. CONDUITS SHALL BE RIGIDLY CLAMPED TO BOXES BY GALVANIZED MALLEABLE IRON BUSHING ON INSIDE AND GALVANIZED MALLEABLE IRON LOCKNUT ON OUTSIDE AND INSIDE.
- EQUIPMENT CABINETS, TERMINAL BOXES, JUNCTION BOXES AND PULL BOXES SHALL BE GALVANIZED OR EPOXY-COATED SHEET STEEL. SHALL MEET OR EXCEED UL 50 AND BE RATED NEMA 1 (OR BETTER) FOR INTERIOR LOCATIONS AND NEMA 3 (OR BETTER) FOR EXTERIOR LOCATIONS.
- METAL RECEPTACLE, SWITCH AND DEVICE BOXES SHALL BE GALVANIZED, EPOXY-COATED OR NON-CORRODING; SHALL MEET OR EXCEED UL 514A AND NEMA OS 1 AND BE RATED NEMA 1 (OR BETTER) FOR INTERIOR LOCATIONS AND WEATHER PROTECTED (WP OR BETTER) FOR EXTERIOR LOCATIONS.
- NONMETALLIC RECEPTACLE, SWITCH AND DEVICE BOXES SHALL MEET OR EXCEED NEMA OS 2 (NEWEST REVISION) AND BE RATED NEMA 1 (OR BETTER) FOR INTERIOR LOCATIONS AND WEATHER PROTECTED (WP OR BETTER) FOR EXTERIOR LOCATIONS.
- THE CONTRACTOR SHALL NOTIFY AND OBTAIN NECESSARY AUTHORIZATION FROM THE CARRIER AND/OR DISH Wireless L.L.C. AND TOWER OWNER BEFORE COMMENCING WORK ON THE AC POWER DISTRIBUTION PANELS.
- THE CONTRACTOR SHALL PROVIDE NECESSARY TAGGING ON THE BREAKERS, CABLES AND DISTRIBUTION PANELS IN ACCORDANCE WITH THE APPLICABLE CODES AND STANDARDS TO SAFEGUARD LIFE AND PROPERTY.
- INSTALL LAMICOID LABEL ON THE METER CENTER TO SHOW "DISH Wireless L.L.C.".
- ALL EMPTY/SPARE CONDUITS THAT ARE INSTALLED ARE TO HAVE A METERED MULE TAPE PULL CORD INSTALLED.



5701 SOUTH SANTA FE DRIVE  
LITTLETON, CO 80120



2000 CORPORATE DRIVE  
CANONSBURG, PA 15317



1717 S. BOULDER  
SUITE 300  
TULSA, OK 74119  
PH: (918) 587-4630  
www.btgrp.com



B&T ENGINEERING, INC.  
PEC.0001564  
Expires 2/10/22

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
JTS	JTS	MDW

RFDS REV #: 3.0

**CONSTRUCTION DOCUMENTS**

SUBMITTALS		
REV	DATE	DESCRIPTION
A	6/17/21	ISSUED FOR REVIEW
0	7/30/21	ISSUED FOR CONSTRUCTION
1	10/22/21	ISSUED FOR CONSTRUCTION
2	1/26/22	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER  
**136595.002.01**

DISH Wireless L.L.C.  
PROJECT INFORMATION  
**NJJER01096A**  
425 INDIAN LEDGE PARK RD  
TRUMBULL, CT 06611

SHEET TITLE  
**GENERAL NOTES**

SHEET NUMBER  
**GN-3**

**GROUNDING NOTES:**

1. ALL GROUND ELECTRODE SYSTEMS (INCLUDING TELECOMMUNICATION, RADIO, LIGHTNING PROTECTION AND AC POWER GES'S) SHALL BE BONDED TOGETHER AT OR BELOW GRADE, BY TWO OR MORE COPPER BONDING CONDUCTORS IN ACCORDANCE WITH THE NEC.
2. THE CONTRACTOR SHALL PERFORM IEEE FALL-OF-POTENTIAL RESISTANCE TO EARTH TESTING (PER IEEE 1100 AND 81) FOR GROUND ELECTRODE SYSTEMS, THE CONTRACTOR SHALL FURNISH AND INSTALL SUPPLEMENTAL GROUND ELECTRODES AS NEEDED TO ACHIEVE A TEST RESULT OF 5 OHMS OR LESS.
3. THE CONTRACTOR IS RESPONSIBLE FOR PROPERLY SEQUENCING GROUNDING AND UNDERGROUND CONDUIT INSTALLATION AS TO PREVENT ANY LOSS OF CONTINUITY IN THE GROUNDING SYSTEM OR DAMAGE TO THE CONDUIT AND PROVIDE TESTING RESULTS.
4. METAL CONDUIT AND TRAY SHALL BE GROUNDED AND MADE ELECTRICALLY CONTINUOUS WITH LISTED BONDING FITTINGS OR BY BONDING ACROSS THE DISCONTINUITY WITH #6 COPPER WIRE UL APPROVED GROUNDING TYPE CONDUIT CLAMPS.
5. METAL RACEWAY SHALL NOT BE USED AS THE NEC REQUIRED EQUIPMENT GROUND CONDUCTOR. STRANDED COPPER CONDUCTORS WITH GREEN INSULATION, SIZED IN ACCORDANCE WITH THE NEC, SHALL BE FURNISHED AND INSTALLED WITH THE POWER CIRCUITS TO BTS EQUIPMENT.
6. EACH CABINET FRAME SHALL BE DIRECTLY CONNECTED TO THE MASTER GROUND BAR WITH GREEN INSULATED SUPPLEMENTAL EQUIPMENT GROUND WIRES, #6 STRANDED COPPER OR LARGER FOR INDOOR BTS; #2 BARE SOLID TINNED COPPER FOR OUTDOOR BTS.
7. CONNECTIONS TO THE GROUND BUS SHALL NOT BE DOUBLED UP OR STACKED BACK TO BACK CONNECTIONS ON OPPOSITE SIDE OF THE GROUND BUS ARE PERMITTED.
8. ALL EXTERIOR GROUND CONDUCTORS BETWEEN EQUIPMENT/GROUND BARS AND THE GROUND RING SHALL BE #2 SOLID TINNED COPPER UNLESS OTHERWISE INDICATED.
9. ALUMINUM CONDUCTOR OR COPPER CLAD STEEL CONDUCTOR SHALL NOT BE USED FOR GROUNDING CONNECTIONS.
10. USE OF 90° BENDS IN THE PROTECTION GROUNDING CONDUCTORS SHALL BE AVOIDED WHEN 45° BENDS CAN BE ADEQUATELY SUPPORTED.
11. EXOTHERMIC WELDS SHALL BE USED FOR ALL GROUNDING CONNECTIONS BELOW GRADE.
12. ALL GROUND CONNECTIONS ABOVE GRADE (INTERIOR AND EXTERIOR) SHALL BE FORMED USING HIGH PRESS CRIMPS.
13. COMPRESSION GROUND CONNECTIONS MAY BE REPLACED BY EXOTHERMIC WELD CONNECTIONS.
14. ICE BRIDGE BONDING CONDUCTORS SHALL BE EXOTHERMICALLY BONDED OR BOLTED TO THE BRIDGE AND THE TOWER GROUND BAR.
15. APPROVED ANTIOXIDANT COATINGS (i.e. CONDUCTIVE GEL OR PASTE) SHALL BE USED ON ALL COMPRESSION AND BOLTED GROUND CONNECTIONS.
16. ALL EXTERIOR GROUND CONNECTIONS SHALL BE COATED WITH A CORROSION RESISTANT MATERIAL.
17. MISCELLANEOUS ELECTRICAL AND NON-ELECTRICAL METAL BOXES, FRAMES AND SUPPORTS SHALL BE BONDED TO THE GROUND RING, IN ACCORDANCE WITH THE NEC.
18. BOND ALL METALLIC OBJECTS WITHIN 6 ft OF MAIN GROUND RING WITH (1) #2 BARE SOLID TINNED COPPER GROUND CONDUCTOR.
19. GROUND CONDUCTORS USED FOR THE FACILITY GROUNDING AND LIGHTNING PROTECTION SYSTEMS SHALL NOT BE ROUTED THROUGH METALLIC OBJECTS THAT FORM A RING AROUND THE CONDUCTOR, SUCH AS METALLIC CONDUITS, METAL SUPPORT CLIPS OR SLEEVES THROUGH WALLS OR FLOORS. WHEN IT IS REQUIRED TO BE HOUSED IN CONDUIT TO MEET CODE REQUIREMENTS OR LOCAL CONDITIONS, NON-METALLIC MATERIAL SUCH AS PVC CONDUIT SHALL BE USED. WHERE USE OF METAL CONDUIT IS UNAVOIDABLE (i.e., NONMETALLIC CONDUIT PROHIBITED BY LOCAL CODE) THE GROUND CONDUCTOR SHALL BE BONDED TO EACH END OF THE METAL CONDUIT.
20. ALL GROUNDS THAT TRANSITION FROM BELOW GRADE TO ABOVE GRADE MUST BE #2 BARE SOLID TINNED COPPER IN 3/4" NON-METALLIC, FLEXIBLE CONDUIT FROM 24" BELOW GRADE TO WITHIN 3" TO 6" OF CAD-WELD TERMINATION POINT. THE EXPOSED END OF THE CONDUIT MUST BE SEALED WITH SILICONE CAULK. (ADD TRANSITIONING GROUND STANDARD DETAIL AS WELL).
21. BUILDINGS WHERE THE MAIN GROUNDING CONDUCTORS ARE REQUIRED TO BE ROUTED TO GRADE, THE CONTRACTOR SHALL ROUTE TWO GROUNDING CONDUCTORS FROM THE ROOFTOP, TOWERS, AND WATER TOWERS GROUNDING RING, TO THE EXISTING GROUNDING SYSTEM, THE GROUNDING CONDUCTORS SHALL NOT BE SMALLER THAN 2/0 COPPER. ROOFTOP GROUNDING RING SHALL BE BONDED TO THE EXISTING GROUNDING SYSTEM, THE BUILDING STEEL COLUMNS, LIGHTNING PROTECTION SYSTEM, AND BUILDING MAIN WATER LINE (FERROUS OR NONFERROUS METAL PIPING ONLY). DO NOT ATTACH GROUNDING TO FIRE SPRINKLER SYSTEM PIPES.



5701 SOUTH SANTA FE DRIVE  
LITTLETON, CO 80120



2000 CORPORATE DRIVE  
CANONSBURG, PA 15317



1717 S. BOULDER  
SUITE 300  
TULSA, OK 74119  
PH: (918) 587-4630  
www.btgrp.com



B&T ENGINEERING, INC.  
PEC.0001564  
Expires 2/10/22

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
JTS	JTS	MDW

RFDS REV #: 3.0

**CONSTRUCTION DOCUMENTS**

SUBMITTALS		
REV	DATE	DESCRIPTION
A	6/17/21	ISSUED FOR REVIEW
0	7/30/21	ISSUED FOR CONSTRUCTION
1	10/22/21	ISSUED FOR CONSTRUCTION
2	1/26/22	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER  
**136595.002.01**

DISH Wireless L.L.C.  
PROJECT INFORMATION  
**NJJER01096A**  
425 INDIAN LEDGE PARK RD  
TRUMBULL, CT 06611

SHEET TITLE  
**GENERAL NOTES**

SHEET NUMBER  
**GN-4**

# Exhibit D

## **Structural Analysis Report**

Date: **May 29, 2021**



Crown Castle  
2000 Corporate Drive  
Canonsburg, PA 15317  
(724) 416-2000

**Subject:** **Structural Analysis Report**

**Carrier Designation:** **DISH Network Co-Locate**  
**Site Number:** NJJER01096A  
**Site Name:** CT-CCI-T-881535

**Crown Castle Designation:** **BU Number:** 881535  
**Site Name:** TRUMBULL TOWER  
**JDE Job Number:** 640206  
**Work Order Number:** 1964277  
**Order Number:** 548692 Rev. 1

**Engineering Firm Designation:** **Crown Castle Project Number:** 1964277

**Site Data:** **425 Indian Ledge Park Rd, Trumbull, FAIRFIELD County, CT**  
**Latitude 41° 16' 23.81", Longitude -73° 12' 47.18"**  
**195 Foot - Monopole Tower**

Crown Castle is pleased to submit this “**Structural Analysis Report**” to determine the structural integrity of the above-mentioned tower.

The purpose of the analysis is to determine acceptability of the tower stress level. Based on our analysis we have determined the tower stress level for the structure and foundation, under the following load case, to be:

LC7: Proposed Equipment Configuration

**Sufficient Capacity - 64.5%**

**\*The structure has sufficient capacity once the loading changes, described in the Recommendations section of this report, are completed.**

This analysis utilizes an ultimate 3-second gust wind speed of 125 mph as required by the 2018 Connecticut State Building Code and Appendix N. Applicable Standard references and design criteria are listed in Section 2 - Analysis Criteria.

Structural analysis prepared by: Hayes Lei

Respectfully submitted by:

Bradley E. Byrom, P.E., S.E.  
Senior Project Engineer



Digitally signed by Bradley E Byrom  
Date: 2021.05.31 08:50:23 -04'00'

## TABLE OF CONTENTS

### 1) INTRODUCTION

### 2) ANALYSIS CRITERIA

- Table 1 - Proposed Equipment Configuration
- Table 2 - Non-Carrier Equipment To Be Conditionally Removed
- Table 3 - Other Considered Equipment

### 3) ANALYSIS PROCEDURE

- Table 4 - Documents Provided
- 3.1) Analysis Method
- 3.2) Assumptions

### 4) ANALYSIS RESULTS

- Table 5 - Section Capacity (Summary)
- Table 6 - Tower Component Stresses vs. Capacity - LC7
- 4.1) Recommendations

### 5) APPENDIX A

- tnxTower Output

### 6) APPENDIX B

- Base Level Drawing

### 7) APPENDIX C

- Additional Calculations



## 1) INTRODUCTION

This tower is a 195 ft Monopole tower designed by ENGINEERED ENDEAVORS, INC.

## 2) ANALYSIS CRITERIA

<b>TIA-222 Revision:</b>	TIA-222-H
<b>Risk Category:</b>	II
<b>Wind Speed:</b>	125 mph
<b>Exposure Category:</b>	B
<b>Topographic Factor:</b>	1
<b>Ice Thickness:</b>	1.5 in
<b>Wind Speed with Ice:</b>	50 mph
<b>Service Wind Speed:</b>	60 mph

**Table 1 - Proposed Equipment Configuration**

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)
175.0	175.0	3	fujitsu	TA08025-B604	1	1-3/4
		3	fujitsu	TA08025-B605		
		3	jma wireless	MX08FRO665-21 w/ Mount Pipe		
		1	raycap	RDIDC-9181-PF-48		
		1	tower mounts	Commscope MC-PK8-DSH		

**Table 2 - Non-Carrier Equipment To Be Conditionally Removed**

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)
175.0	175.0	12	mounts	2.4" Dia x 6-ft Pipe	-	-
		1	tower mounts	Platform Mount [LP 601-1]		

**Table 3 - Other Considered Equipment**

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)	
185.0	187.0	3	cci antennas	HPA-65R-BUU-H6 w/ Mount Pipe	2 4 12 2	3/8 5/8 1-1/4 conduit	
		3	ericsson	RRUS 32			
		3	ericsson	RRUS 4449 B5/B12			
		3	ericsson	RRUS12/RRUS A2			
		3	kathrein	80010965 w/ Mount Pipe			
		3	powerwave technologies	7770.00 w/ Mount Pipe			
	185.0	185.0	6	powerwave technologies			LGP21401
			2	raycap			DC6-48-60-18-8F
			6	tower mounts			Miscellaneous [NA 509-1]
			1	tower mounts			Platform Mount [LP 602-

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)
				1_KCKR]		
164.0	166.0	3		A-ANT-23G-2-C	3 1 6 2 1	1-1/4 1-1/2 5/16 7983A conduit
		3	alcatel lucent	1900MHz RRH (65MHz)		
		3	alcatel lucent	800 EXTERNAL NOTCH FILTER		
		3	alcatel lucent	800MHZ RRH		
		3	alcatel lucent	TD-RRH8x20-25		
		3	argus technologies	LLPX310R w/ Mount Pipe		
		9	rfs celwave	ACU-A20-N		
		3	rfs celwave	APXVSPP18-C-A20 w/ Mount Pipe		
		3	rfs celwave	APXVTM14-ALU-I20 w/ Mount Pipe		
		3	samsung telecommunications	FDD_R6_RRH		
		164.0	6	mounts		
		1	tower mounts	Platform Mount [LP 602-1]		
154.0	155.0	2	antel	LPA-4016 w/ Mount Pipe	20	1-5/8
		3	commscope	CBC78T-DS-43-2X		
		6	commscope_cfd	JAHH-65B-R3B w/ Mount Pipe		
		4	decibel_cfd	DB844G65ZAXY w/ Mount Pipe		
		2	rfs celwave	DB-B1-6C-8AB-0Z		
		3	samsung telecommunications	RFV01U-D1A		
		3	samsung telecommunications	RFV01U-D2A		
	3	vzw	Sub6 Antenna - VZS01 w/ Mount Pipe			
	154.0	1	tower mounts	Platform Mount [LP 601-1]		
146.0	146.0	1	tower mounts	Platform Mount [LP 602-1]	14	1-5/8
	145.0	3	ericsson	KRY 112 144/1		
		3	ericsson	RADIO 4449 B12/B71		
		3	ericsson	RRUS 11 B2		
		3	ericsson_cfd	ERICSSON AIR 21 B4A B2P w/ Mount Pipe		
		3	rfs celwave_cfd	APXVAARR24_43-U-NA20 w/ Mount Pipe		
134.0	135.0	12	decibel_cfd	DB844H90E-XY w/ Mount Pipe	9	1-1/4
	134.0	1	tower mounts	Platform Mount [LP 303-1]	6	1-5/8

### 3) ANALYSIS PROCEDURE

**Table 4 - Documents Provided**

Document	Reference	Source
4-GEOTECHNICAL REPORTS	1406210	CCISITES
4-TOWER FOUNDATION DRAWINGS/DESIGN/SPECS	1405798	CCISITES
4-TOWER MANUFACTURER DRAWINGS	1405789	CCISITES

#### 3.1) Analysis Method

tnxTower (version 8.0.9.0), a commercially available analysis software package, was used to create a three-dimensional model of the tower and calculate member stresses for various loading cases. Selected output from the analysis is included in Appendix A. When applicable, Crown Castle has calculated and provided the effective area for panel antennas using approved methods following the intent of the TIA-222 standard.

#### 3.2) Assumptions

- 1) Tower and structures were maintained in accordance with the TIA-222 Standard.
- 2) The configuration of antennas, transmission cables, mounts and other appurtenances are as specified in Tables 1 and 3 and the referenced drawings.

This analysis may be affected if any assumptions are not valid or have been made in error. Crown Castle should be notified to determine the effect on the structural integrity of the tower.

### 4) ANALYSIS RESULTS

**Table 5 - Section Capacity (Summary)**

Section No.	Elevation (ft)	Component Type	Size	Critical Element	P (K)	SF*P_allow (K)	% Capacity	Pass / Fail
L1	195 - 157.65	Pole	TP33.875x25x0.25	1	-13.26	1584.12	22.9	Pass
L2	157.65 - 117.08	Pole	TP42.9063x32.2511x0.3125	2	-30.03	2511.09	55.4	Pass
L3	117.08 - 81.09	Pole	TP50.75x40.9029x0.375	3	-41.74	3565.31	62.3	Pass
L4	81.09 - 40.03	Pole	TP59.6563x48.3906x0.5	4	-60.63	5584.37	52.3	Pass
L5	40.03 - 0	Pole	TP68x56.7865x0.5	5	-87.39	6580.00	59.7	Pass
							Summary	
						Pole (L3)	62.3	Pass
						Rating =	62.3	Pass

**Table 6 - Tower Component Stresses vs. Capacity - LC7**

Notes	Component	Elevation (ft)	% Capacity	Pass / Fail
1	Anchor Rods	0	60.7	Pass
1	Base Plate	0	53.8	Pass
1	Base Foundation (Structure)	0	64.5	Pass
1	Base Foundation (Soil Interaction)	0	62.7	Pass

<b>Structure Rating (max from all components) =</b>	<b>64.5%</b>
---	--------------

Notes:

- 1) See additional documentation in "Appendix C – Additional Calculations" for calculations supporting the % capacity. Rating per TIA-222-H Section 15.5.

#### 4.1) Recommendations

The tower and its foundation have sufficient capacity to carry the proposed load configuration. In order for the results of this analysis to be considered valid, the loading modification, as follows, must be completed.


Loading Changes:

- a) Removal of the abandoned mounts at the 175 ft level

No structural modifications are required at this time provided that the above-listed changes are completed.

**APPENDIX A**  
**TNXTOWER OUTPUT**

195.0 ft



**MATERIAL STRENGTH**

GRADE	Fy	Fu	GRADE	Fy	Fu
A572-65	65 ksi	80 ksi			

**TOWER DESIGN NOTES**

1. Tower is located in Fairfield County, Connecticut.
2. Tower designed for Exposure B to the TIA-222-H Standard.
3. Tower designed for a 125 mph basic wind in accordance with the TIA-222-H Standard.
4. Tower is also designed for a 50 mph basic wind with 1.50 in ice. Ice is considered to increase in thickness with height.
5. Deflections are based upon a 60 mph wind.
6. Tower Risk Category II.
7. Topographic Category 1 with Crest Height of 0.00 ft
8. TOWER RATING: 62.3%

157.7 ft



117.1 ft

81.1 ft

40.0 ft

0.0 ft

ALL REACTIONS  
ARE FACTORED



Section	Length (ft)	Number of Sides	Thickness (in)	Socket Length (ft)	Top Dia (in)	Bot Dia (in)	Grade	Weight (K)
1	37.35	18	0.2500	4.73	25.0000	33.8750	A572-65	2.9
2	45.30	18	0.3125	5.86	32.2511	42.9063	A572-65	5.7
3	41.85	18	0.3750	6.84	40.9029	50.7500	A572-65	7.7
4	47.90	18	0.5000	7.95	48.3906	59.6563	A572-65	13.8
5	47.98	18	0.5000	56.7865	68.0000		A572-65	16.0

**CROWN CASTLE**  
The Pathway To Possible

**Crown Castle**  
2000 Corporate Drive  
Canonsburg, PA 15317  
Phone: (724) 416-2000  
FAX:

Job: <b>BU 881535</b>		
Project:	Client: Crown Castle	Drawn by: HLej
Code: TIA-222-H	Date: 05/29/21	App'd:
Path:	Scale: NTS	Dwg No. E-1

## Tower Input Data

The tower is a monopole.  
 This tower is designed using the TIA-222-H standard.  
 The following design criteria apply:

- Tower is located in Fairfield County, Connecticut.
- Tower base elevation above sea level: 323.00 ft.
- Basic wind speed of 125 mph.
- Risk Category II.
- Exposure Category B.
- Simplified Topographic Factor Procedure for wind speed-up calculations is used.
- Topographic Category: 1.
- Crest Height: 0.00 ft.
- Nominal ice thickness of 1.5000 in.
- Ice thickness is considered to increase with height.
- Ice density of 56 pcf.
- A wind speed of 50 mph is used in combination with ice.
- Temperature drop of 50 °F.
- Deflections calculated using a wind speed of 60 mph.
- A non-linear (P-delta) analysis was used.
- Pressures are calculated at each section.
- Stress ratio used in pole design is 1.
- Tower analysis based on target reliabilities in accordance with Annex S.
- Load Modification Factors used:  $K_{es}(F_w) = 0.95$ ,  $K_{es}(t_i) = 0.85$ .
- Maximum demand-capacity ratio is: 1.05.
- Local bending stresses due to climbing loads, feed line supports, and appurtenance mounts are not considered.

## Options

Consider Moments - Legs Consider Moments - Horizontals Consider Moments - Diagonals Use Moment Magnification ✓ Use Code Stress Ratios ✓ Use Code Safety Factors - Guys Escalate Ice Always Use Max Kz Use Special Wind Profile  Include Bolts In Member Capacity  Leg Bolts Are At Top Of Section Secondary Horizontal Braces Leg Use Diamond Inner Bracing (4 Sided) SR Members Have Cut Ends SR Members Are Concentric	Distribute Leg Loads As Uniform Assume Legs Pinned ✓ Assume Rigid Index Plate ✓ Use Clear Spans For Wind Area Use Clear Spans For KL/r Retension Guys To Initial Tension ✓ Bypass Mast Stability Checks ✓ Use Azimuth Dish Coefficients ✓ Project Wind Area of Appurt.  Autocalc Torque Arm Areas  Add IBC .6D+W Combination ✓ Sort Capacity Reports By Component Triangulate Diamond Inner Bracing Treat Feed Line Bundles As Cylinder Ignore KL/ry For 60 Deg. Angle Legs	Use ASCE 10 X-Brace Ly Rules Calculate Redundant Bracing Forces Ignore Redundant Members in FEA SR Leg Bolts Resist Compression All Leg Panels Have Same Allowable Offset Girt At Foundation ✓ Consider Feed Line Torque Include Angle Block Shear Check Use TIA-222-H Bracing Resist. Exemption Use TIA-222-H Tension Splice Exemption  <div style="text-align: center; background-color: #e0e0e0; padding: 2px;"><b>Poles</b></div> ✓ Include Shear-Torsion Interaction Always Use Sub-Critical Flow Use Top Mounted Sockets Pole Without Linear Attachments Pole With Shroud Or No Appurtenances Outside and Inside Corner Radii Are Known
--	---	---

## Tapered Pole Section Geometry

Section	Elevation ft	Section Length ft	Splice Length ft	Number of Sides	Top Diameter in	Bottom Diameter in	Wall Thickness in	Bend Radius in	Pole Grade
L1	195.00-157.65	37.35	4.73	18	25.0000	33.8750	0.2500	1.0000	A572-65 (65 ksi)
L2	157.65-117.08	45.30	5.86	18	32.2511	42.9063	0.3125	1.2500	A572-65 (65 ksi)
L3	117.08-81.09	41.85	6.84	18	40.9029	50.7500	0.3750	1.5000	A572-65 (65 ksi)
L4	81.09-40.03	47.90	7.95	18	48.3906	59.6563	0.5000	2.0000	A572-65 (65 ksi)
L5	40.03-0.00	47.98		18	56.7865	68.0000	0.5000	2.0000	A572-65 (65 ksi)

### Tapered Pole Properties

Section	Tip Dia. in	Area in <sup>2</sup>	I in <sup>4</sup>	r in	C in	I/C in <sup>3</sup>	J in <sup>4</sup>	I/Q in <sup>2</sup>	w in	w/t
L1	25.3471	19.6391	1519.8824	8.7863	12.7000	119.6758	3041.7647	9.8214	3.9600	15.84
	34.3590	26.6814	3811.2835	11.9369	17.2085	221.4768	7627.5821	13.3433	5.5220	22.088
L2	33.8301	31.6791	4082.6377	11.3382	16.3835	249.1914	8170.6474	15.8425	5.1262	16.404
	43.5199	42.2477	9683.4926	15.1208	21.7964	444.2708	19379.727	21.1279	7.0015	22.405
L3	42.8761	48.2383	10010.087	14.3874	20.7787	481.7482	20033.346	24.1237	6.5389	17.437
	51.4751	59.9588	19222.984	17.8831	25.7810	745.6260	38471.263	29.9851	8.2720	22.059
L4	50.6935	76.0024	22022.402	17.0012	24.5824	895.8600	44073.782	38.0084	7.6367	15.273
	60.4994	93.8810	41506.516	21.0005	30.3054	1369.6091	83067.647	46.9494	9.6195	19.239
L5	59.4720	89.3266	35754.161	19.9817	28.8475	1239.4184	71555.369	44.6718	9.1144	18.229
	68.9719	107.1225	61663.148	23.9625	34.5440	1785.0610	123407.43	53.5714	11.0880	22.176

Tower Elevation ft	Gusset Area (per face) ft <sup>2</sup>	Gusset Thickness in	Gusset Grade	Adjust. Factor A <sub>r</sub>	Adjust. Factor A <sub>r</sub>	Weight Mult.	Double Angle Stitch Bolt Spacing Diagonals in	Double Angle Stitch Bolt Spacing Horizontals in	Double Angle Stitch Bolt Spacing Redundants in
L1 195.00-157.65				1	1	1			
L2 157.65-117.08				1	1	1			
L3 117.08-81.09				1	1	1			
L4 81.09-40.03				1	1	1			
L5 40.03-0.00				1	1	1			

### Feed Line/Linear Appurtenances - Entered As Round Or Flat

Description	Sector	Exclude From Torque Calculation	Component Type	Placement ft	Total Number	Number Per Row	Start/End Position	Width or Diameter r in	Perimeter r in	Weight plf
*** **154** AL7-50(1-5/8)	B	No	Surface Ar (CaAa)	154.00 - 0.00	6	6	-0.166 -0.166	1.9600		0.52
**** CU12PSM6P4XXX(1-	B	No	Surface Ar	175.00 -	1	1	0.500	1.7500		2.72



Description	Sector	Exclude From Torque Calculation	Component Type	Placement ft	Total Number	Number Per Row	Start/End Position	Width or Diameter in	Perimeter in	Weight plf
3/4) *** ** *			(CaAa)	0.00			0.500			

### Feed Line/Linear Appurtenances - Entered As Area

Description	Face or Leg	Allow Shield	Exclude From Torque Calculation	Component Type	Placement ft	Total Number		CAAA ft <sup>2</sup> /ft	Weight plf
<b>**185**</b>									
LDF6-50A(1-1/4)	B	No	No	Inside Pole	185.00 - 0.00	12	No Ice	0.00	0.60
							1/2" Ice	0.00	0.60
							1" Ice	0.00	0.60
							2" Ice	0.00	0.60
FB-L98B-002-75000(3/8)	B	No	No	Inside Pole	185.00 - 0.00	2	No Ice	0.00	0.06
							1/2" Ice	0.00	0.06
							1" Ice	0.00	0.06
							2" Ice	0.00	0.06
WR-VG82ST-BRDA(5/8)	B	No	No	Inside Pole	185.00 - 0.00	4	No Ice	0.00	0.31
							1/2" Ice	0.00	0.31
							1" Ice	0.00	0.31
							2" Ice	0.00	0.31
2" Flexible Conduit	B	No	No	Inside Pole	185.00 - 0.00	2	No Ice	0.00	0.34
							1/2" Ice	0.00	0.34
							1" Ice	0.00	0.34
							2" Ice	0.00	0.34
<b>**164**</b>									
7983A(ELLIPTICAL)	B	No	No	Inside Pole	164.00 - 0.00	2	No Ice	0.00	0.08
							1/2" Ice	0.00	0.08
							1" Ice	0.00	0.08
							2" Ice	0.00	0.08
9207(5/16)	B	No	No	Inside Pole	164.00 - 0.00	6	No Ice	0.00	0.60
							1/2" Ice	0.00	0.60
							1" Ice	0.00	0.60
							2" Ice	0.00	0.60
HB114-1-0813U4-M5J(1-1/4)	B	No	No	Inside Pole	164.00 - 0.00	3	No Ice	0.00	1.20
							1/2" Ice	0.00	1.20
							1" Ice	0.00	1.20
							2" Ice	0.00	1.20
HB114-21U3M12-XXXF(1-1/4)	B	No	No	Inside Pole	164.00 - 0.00	1	No Ice	0.00	1.22
							1/2" Ice	0.00	1.22
							1" Ice	0.00	1.22
							2" Ice	0.00	1.22
2" Flexible Conduit	B	No	No	Inside Pole	164.00 - 0.00	1	No Ice	0.00	0.34
							1/2" Ice	0.00	0.34
							1" Ice	0.00	0.34
							2" Ice	0.00	0.34
HJ7-50A(1-5/8)	B	No	No	Inside Pole	154.00 - 0.00	12	No Ice	0.00	1.04
							1/2" Ice	0.00	1.04
							1" Ice	0.00	1.04
							2" Ice	0.00	1.04
HB158-1-08U8-S8J18(1-5/8)	B	No	No	Inside Pole	154.00 - 0.00	2	No Ice	0.00	1.30
							1/2" Ice	0.00	1.30
							1" Ice	0.00	1.30
							2" Ice	0.00	1.30
<b>**146**</b>									
LDF7-50A(1-5/8)	A	No	No	Inside Pole	146.00 - 0.00	12	No Ice	0.00	0.82
							1/2" Ice	0.00	0.82
							1" Ice	0.00	0.82
							2" Ice	0.00	0.82
HCS 6X12 4AWG(1-5/8)	A	No	No	Inside Pole	146.00 - 0.00	1	No Ice	0.00	2.40
							1/2" Ice	0.00	2.40
							1" Ice	0.00	2.40

Description	Face or Leg	Allow Shield	Exclude From Torque Calculation	Component Type	Placement ft	Total Number		C <sub>AA</sub> ft <sup>2</sup> /ft	Weight plf
MLE HYBRID 9POWER/18FIBER RL 2(1-5/8)	A	No	No	Inside Pole	146.00 - 0.00	1	2" Ice	0.00	2.40
							No Ice	0.00	1.07
							1/2" Ice	0.00	1.07
							1" Ice	0.00	1.07
							2" Ice	0.00	1.07
**134**									
LDF6-50A(1-1/4)	A	No	No	Inside Pole	135.00 - 0.00	9	No Ice	0.00	0.60
							1/2" Ice	0.00	0.60
							1" Ice	0.00	0.60
							2" Ice	0.00	0.60
LDF7-50A(1-5/8)	A	No	No	Inside Pole	135.00 - 0.00	6	No Ice	0.00	0.82
							1/2" Ice	0.00	0.82
							1" Ice	0.00	0.82
							2" Ice	0.00	0.82
***									
**									
*									

**Feed Line/Linear Appurtenances Section Areas**

Tower Section n	Tower Elevation ft	Face	A <sub>R</sub> ft <sup>2</sup>	A <sub>F</sub> ft <sup>2</sup>	C <sub>AA</sub> In Face ft <sup>2</sup>	C <sub>AA</sub> Out Face ft <sup>2</sup>	Weight K
L1	195.00-157.65	A	0.000	0.000	0.000	0.000	0.00
		B	0.000	0.000	3.036	0.000	0.36
		C	0.000	0.000	0.000	0.000	0.00
L2	157.65-117.08	A	0.000	0.000	0.000	0.000	0.57
		B	0.000	0.000	50.518	0.000	1.52
		C	0.000	0.000	0.000	0.000	0.00
L3	117.08-81.09	A	0.000	0.000	0.000	0.000	0.85
		B	0.000	0.000	48.622	0.000	1.41
		C	0.000	0.000	0.000	0.000	0.00
L4	81.09-40.03	A	0.000	0.000	0.000	0.000	0.97
		B	0.000	0.000	55.472	0.000	1.60
		C	0.000	0.000	0.000	0.000	0.00
L5	40.03-0.00	A	0.000	0.000	0.000	0.000	0.95
		B	0.000	0.000	54.081	0.000	1.56
		C	0.000	0.000	0.000	0.000	0.00

**Feed Line/Linear Appurtenances Section Areas - With Ice**

Tower Section n	Tower Elevation ft	Face or Leg	Ice Thickness in	A <sub>R</sub> ft <sup>2</sup>	A <sub>F</sub> ft <sup>2</sup>	C <sub>AA</sub> In Face ft <sup>2</sup>	C <sub>AA</sub> Out Face ft <sup>2</sup>	Weight K
L1	195.00-157.65	A	1.507	0.000	0.000	0.000	0.000	0.00
		B		0.000	0.000	8.265	0.000	0.46
		C		0.000	0.000	0.000	0.000	0.00
L2	157.65-117.08	A	1.470	0.000	0.000	0.000	0.000	0.57
		B		0.000	0.000	87.508	0.000	2.48
		C		0.000	0.000	0.000	0.000	0.00
L3	117.08-81.09	A	1.423	0.000	0.000	0.000	0.000	0.85
		B		0.000	0.000	83.007	0.000	2.30
		C		0.000	0.000	0.000	0.000	0.00
L4	81.09-40.03	A	1.355	0.000	0.000	0.000	0.000	0.97
		B		0.000	0.000	93.831	0.000	2.58
		C		0.000	0.000	0.000	0.000	0.00
L5	40.03-0.00	A	1.210	0.000	0.000	0.000	0.000	0.95
		B		0.000	0.000	90.250	0.000	2.47
		C		0.000	0.000	0.000	0.000	0.00

### Feed Line Center of Pressure

Section	Elevation	CP <sub>x</sub>	CP <sub>z</sub>	CP <sub>x</sub>	CP <sub>z</sub>
	ft	in	in	Ice in	Ice in
L1	195.00-157.65	0.6227	0.3595	0.9168	0.5293
L2	157.65-117.08	4.7205	-4.1265	4.3799	-3.0947
L3	117.08-81.09	5.2145	-4.6668	4.8575	-3.5877
L4	81.09-40.03	5.4481	-4.8750	5.1207	-3.8047
L5	40.03-0.00	5.6385	-5.0447	5.3224	-3.9903

Note: For pole sections, center of pressure calculations do not consider feed line shielding.

### Shielding Factor Ka

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K <sub>a</sub> No Ice	K <sub>a</sub> Ice
L1	26	CU12PSM6P4XXX(1-3/4)	157.65 - 175.00	1.0000	1.0000
L2	15	AL7-50(1-5/8)	117.08 - 154.00	1.0000	1.0000
L2	26	CU12PSM6P4XXX(1-3/4)	117.08 - 157.65	1.0000	1.0000
L3	15	AL7-50(1-5/8)	81.09 - 117.08	1.0000	1.0000
L3	26	CU12PSM6P4XXX(1-3/4)	81.09 - 117.08	1.0000	1.0000
L4	15	AL7-50(1-5/8)	40.03 - 81.09	1.0000	1.0000
L4	26	CU12PSM6P4XXX(1-3/4)	40.03 - 81.09	1.0000	1.0000
L5	15	AL7-50(1-5/8)	0.00 - 40.03	1.0000	1.0000
L5	26	CU12PSM6P4XXX(1-3/4)	0.00 - 40.03	1.0000	1.0000

### Discrete Tower Loads

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C <sub>A</sub> A <sub>A</sub> Front	C <sub>A</sub> A <sub>A</sub> Side	Weight	
			Horz	Lateral						ft
**185**										
7770.00 w/ Mount Pipe	A	From Centroid-Leg	4.00	0.00	0.0000	185.00	No Ice	5.75	4.25	0.06
							1/2" Ice	6.18	5.01	0.10
							1" Ice	6.61	5.71	0.16
							2" Ice	7.49	7.16	0.29
7770.00 w/ Mount Pipe	B	From Centroid-Leg	4.00	0.00	0.0000	185.00	No Ice	5.75	4.25	0.06
							1/2" Ice	6.18	5.01	0.10
							1" Ice	6.61	5.71	0.16
							2" Ice	7.49	7.16	0.29

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C <sub>AA</sub> <sub>Front</sub>	C <sub>AA</sub> <sub>Side</sub>	Weight	
			Horz	Lateral						Vert
			ft	ft	°	ft	ft <sup>2</sup>	ft <sup>2</sup>	K	
7770.00 w/ Mount Pipe	C	From Centroid-Leg	4.00	0.00	0.0000	185.00	2" Ice			
							No Ice	5.75	4.25	0.06
							1/2"	6.18	5.01	0.10
							Ice	6.61	5.71	0.16
							1" Ice	7.49	7.16	0.29
HPA-65R-BUU-H6 w/ Mount Pipe	A	From Centroid-Leg	4.00	0.00	0.0000	185.00	2" Ice			
							No Ice	9.22	6.25	0.07
							1/2"	9.98	6.96	0.14
							Ice	10.76	7.70	0.22
							1" Ice	12.36	9.22	0.42
HPA-65R-BUU-H6 w/ Mount Pipe	B	From Centroid-Leg	4.00	0.00	0.0000	185.00	2" Ice			
							No Ice	9.22	6.25	0.07
							1/2"	9.98	6.96	0.14
							Ice	10.76	7.70	0.22
							1" Ice	12.36	9.22	0.42
HPA-65R-BUU-H6 w/ Mount Pipe	C	From Centroid-Leg	4.00	0.00	0.0000	185.00	2" Ice			
							No Ice	9.22	6.25	0.07
							1/2"	9.98	6.96	0.14
							Ice	10.76	7.70	0.22
							1" Ice	12.36	9.22	0.42
80010965 w/ Mount Pipe	A	From Centroid-Leg	4.00	0.00	0.0000	185.00	2" Ice			
							No Ice	12.26	5.79	0.14
							1/2"	13.03	6.47	0.23
							Ice	13.80	7.17	0.33
							1" Ice	15.41	8.60	0.57
80010965 w/ Mount Pipe	B	From Centroid-Leg	4.00	0.00	0.0000	185.00	2" Ice			
							No Ice	12.26	5.79	0.14
							1/2"	13.03	6.47	0.23
							Ice	13.80	7.17	0.33
							1" Ice	15.41	8.60	0.57
80010965 w/ Mount Pipe	C	From Centroid-Leg	4.00	0.00	0.0000	185.00	2" Ice			
							No Ice	12.26	5.79	0.14
							1/2"	13.03	6.47	0.23
							Ice	13.80	7.17	0.33
							1" Ice	15.41	8.60	0.57
RRUS 32	A	From Centroid-Leg	4.00	0.00	0.0000	185.00	2" Ice			
							No Ice	2.86	1.78	0.06
							1/2"	3.08	1.97	0.08
							Ice	3.32	2.17	0.10
							1" Ice	3.81	2.58	0.16
RRUS 32	B	From Centroid-Leg	4.00	0.00	0.0000	185.00	2" Ice			
							No Ice	2.86	1.78	0.06
							1/2"	3.08	1.97	0.08
							Ice	3.32	2.17	0.10
							1" Ice	3.81	2.58	0.16
RRUS 32	C	From Centroid-Leg	4.00	0.00	0.0000	185.00	2" Ice			
							No Ice	2.86	1.78	0.06
							1/2"	3.08	1.97	0.08
							Ice	3.32	2.17	0.10
							1" Ice	3.81	2.58	0.16
RRUS 4449 B5/B12	A	From Centroid-Leg	4.00	0.00	0.0000	185.00	2" Ice			
							No Ice	1.97	1.41	0.07
							1/2"	2.14	1.56	0.09
							Ice	2.33	1.73	0.11
							1" Ice	2.72	2.07	0.16
RRUS 4449 B5/B12	B	From Centroid-Leg	4.00	0.00	0.0000	185.00	2" Ice			
							No Ice	1.97	1.41	0.07
							1/2"	2.14	1.56	0.09
							Ice	2.33	1.73	0.11
							1" Ice	2.72	2.07	0.16
RRUS 4449 B5/B12	C	From Centroid-Leg	4.00	0.00	0.0000	185.00	2" Ice			
							No Ice	1.97	1.41	0.07
							1/2"	2.14	1.56	0.09
							Ice	2.33	1.73	0.11
							1" Ice	2.72	2.07	0.16

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C <sub>AA</sub> <sub>Front</sub>	C <sub>AA</sub> <sub>Side</sub>	Weight	
			Horz	Lateral						Vert
			ft	ft	°	ft	ft <sup>2</sup>	ft <sup>2</sup>	K	
RRUS12/RRUS A2	A	From Centroid-Leg	4.00	0.00	0.0000	185.00	2" Ice			
							No Ice	3.14	1.84	0.07
							1/2"	3.36	2.01	0.10
							Ice	3.59	2.20	0.13
							1" Ice	4.07	2.59	0.20
RRUS12/RRUS A2	B	From Centroid-Leg	4.00	0.00	0.0000	185.00	2" Ice			
							No Ice	3.14	1.84	0.07
							1/2"	3.36	2.01	0.10
							Ice	3.59	2.20	0.13
							1" Ice	4.07	2.59	0.20
RRUS12/RRUS A2	C	From Centroid-Leg	4.00	0.00	0.0000	185.00	2" Ice			
							No Ice	3.14	1.84	0.07
							1/2"	3.36	2.01	0.10
							Ice	3.59	2.20	0.13
							1" Ice	4.07	2.59	0.20
(2) LGP21401	A	From Centroid-Leg	4.00	0.00	0.0000	185.00	2" Ice			
							No Ice	1.10	0.21	0.01
							1/2"	1.24	0.27	0.02
							Ice	1.38	0.35	0.03
							1" Ice	1.69	0.52	0.05
(2) LGP21401	B	From Centroid-Leg	4.00	0.00	0.0000	185.00	2" Ice			
							No Ice	1.10	0.21	0.01
							1/2"	1.24	0.27	0.02
							Ice	1.38	0.35	0.03
							1" Ice	1.69	0.52	0.05
(2) LGP21401	C	From Centroid-Leg	4.00	0.00	0.0000	185.00	2" Ice			
							No Ice	1.10	0.21	0.01
							1/2"	1.24	0.27	0.02
							Ice	1.38	0.35	0.03
							1" Ice	1.69	0.52	0.05
DC6-48-60-18-8F	A	From Centroid-Leg	4.00	0.00	0.0000	185.00	2" Ice			
							No Ice	1.21	1.21	0.02
							1/2"	1.89	1.89	0.04
							Ice	2.11	2.11	0.07
							1" Ice	2.57	2.57	0.13
DC6-48-60-18-8F	B	From Centroid-Leg	4.00	0.00	0.0000	185.00	2" Ice			
							No Ice	1.21	1.21	0.02
							1/2"	1.89	1.89	0.04
							Ice	2.11	2.11	0.07
							1" Ice	2.57	2.57	0.13
2.4" Dia x 6-ft Pipe	A	From Centroid-Leg	4.00	0.00	0.0000	185.00	2" Ice			
							No Ice	1.43	1.43	0.02
							1/2"	1.93	1.93	0.03
							Ice	2.30	2.30	0.05
							1" Ice	3.06	3.06	0.09
2.4" Dia x 6-ft Pipe	B	From Centroid-Leg	4.00	0.00	0.0000	185.00	2" Ice			
							No Ice	1.43	1.43	0.02
							1/2"	1.93	1.93	0.03
							Ice	2.30	2.30	0.05
							1" Ice	3.06	3.06	0.09
2.4" Dia x 6-ft Pipe	C	From Centroid-Leg	4.00	0.00	0.0000	185.00	2" Ice			
							No Ice	1.43	1.43	0.02
							1/2"	1.93	1.93	0.03
							Ice	2.30	2.30	0.05
							1" Ice	3.06	3.06	0.09
2.4" Dia. x 12' Pipe (Horizontal)	A	From Centroid-Leg	4.00	0.00	0.0000	185.00	2" Ice			
							No Ice	1.90	0.00	0.04
							1/2"	2.70	0.00	0.07
							Ice	3.50	0.00	0.10
							1" Ice	5.10	0.00	0.18
2.4" Dia. x 12' Pipe (Horizontal)	B	From Centroid-Leg	4.00	0.00	0.0000	185.00	2" Ice			
							No Ice	1.90	0.00	0.04
							1/2"	2.70	0.00	0.07
							Ice	3.50	0.00	0.10
							1" Ice	5.10	0.00	0.18

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C <sub>AA</sub> Front	C <sub>AA</sub> Side	Weight
			Horz	Lateral					
2.4" Dia. x 12' Pipe (Horizontal)	C	From Centroid-Leg	4.00	0.0000	185.00	2" Ice			
			0.00			No Ice	1.90	0.00	0.04
			0.00			1/2"	2.70	0.00	0.07
						Ice	3.50	0.00	0.10
						1" Ice	5.10	0.00	0.18
(2) Miscellaneous [NA 509-1]	A	From Centroid-Leg	2.00	0.0000	185.00	2" Ice			
			0.00			No Ice	6.32	4.85	0.09
			0.00			1/2"	7.79	6.36	0.14
						Ice	9.36	7.94	0.20
						1" Ice	12.81	11.32	0.36
(2) Miscellaneous [NA 509-1]	B	From Centroid-Leg	2.00	0.0000	185.00	2" Ice			
			0.00			No Ice	6.32	4.85	0.09
			0.00			1/2"	7.79	6.36	0.14
						Ice	9.36	7.94	0.20
						1" Ice	12.81	11.32	0.36
(2) Miscellaneous [NA 509-1]	C	From Centroid-Leg	2.00	0.0000	185.00	2" Ice			
			0.00			No Ice	6.32	4.85	0.09
			0.00			1/2"	7.79	6.36	0.14
						Ice	9.36	7.94	0.20
						1" Ice	12.81	11.32	0.36
Platform Mount [LP 602-1_KCKR]	C	None		0.0000	185.00	2" Ice			
						No Ice	42.30	42.30	1.62
						1/2"	49.04	49.04	2.38
						Ice	55.87	55.87	3.27
						1" Ice	69.85	69.85	5.40
** 175 **					2" Ice				
MX08FRO665-21 w/ Mount Pipe	A	From Leg	4.00	0.0000	175.00	No Ice	8.01	4.23	0.11
			0.00			1/2"	8.52	4.69	0.19
			0.00			Ice	9.04	5.16	0.29
						1" Ice	10.11	6.12	0.52
						2" Ice			
MX08FRO665-21 w/ Mount Pipe	B	From Leg	4.00	0.0000	175.00	No Ice	8.01	4.23	0.11
			0.00			1/2"	8.52	4.69	0.19
			0.00			Ice	9.04	5.16	0.29
						1" Ice	10.11	6.12	0.52
						2" Ice			
MX08FRO665-21 w/ Mount Pipe	C	From Leg	4.00	0.0000	175.00	No Ice	8.01	4.23	0.11
			0.00			1/2"	8.52	4.69	0.19
			0.00			Ice	9.04	5.16	0.29
						1" Ice	10.11	6.12	0.52
						2" Ice			
TA08025-B604	A	From Leg	4.00	0.0000	175.00	No Ice	1.96	0.98	0.06
			0.00			1/2"	2.14	1.11	0.08
			0.00			Ice	2.32	1.25	0.10
						1" Ice	2.71	1.55	0.15
						2" Ice			
TA08025-B604	B	From Leg	4.00	0.0000	175.00	No Ice	1.96	0.98	0.06
			0.00			1/2"	2.14	1.11	0.08
			0.00			Ice	2.32	1.25	0.10
						1" Ice	2.71	1.55	0.15
						2" Ice			
TA08025-B604	C	From Leg	4.00	0.0000	175.00	No Ice	1.96	0.98	0.06
			0.00			1/2"	2.14	1.11	0.08
			0.00			Ice	2.32	1.25	0.10
						1" Ice	2.71	1.55	0.15
						2" Ice			
TA08025-B605	A	From Leg	4.00	0.0000	175.00	No Ice	1.96	1.13	0.08
			0.00			1/2"	2.14	1.27	0.09
			0.00			Ice	2.32	1.41	0.11
						1" Ice	2.71	1.72	0.16
						2" Ice			
TA08025-B605	B	From Leg	4.00	0.0000	175.00	No Ice	1.96	1.13	0.08
			0.00			1/2"	2.14	1.27	0.09
			0.00			Ice	2.32	1.41	0.11
						1" Ice	2.71	1.72	0.16
						2" Ice			

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustmen t °	Placement ft		C <sub>AA</sub> Front ft <sup>2</sup>	C <sub>AA</sub> Side ft <sup>2</sup>	Weight K
TA08025-B605	C	From Leg	4.00 0.00 0.00	0.0000	175.00	1" Ice	2.71	1.72	0.16
						2" Ice			
						No Ice	1.96	1.13	0.08
						1/2" Ice	2.14	1.27	0.09
						Ice	2.32	1.41	0.11
RDIDC-9181-PF-48	A	From Leg	4.00 0.00 0.00	0.0000	175.00	1" Ice	2.71	1.72	0.16
						2" Ice			
						No Ice	2.31	1.29	0.02
						1/2" Ice	2.50	1.45	0.04
						Ice	2.70	1.61	0.06
(2) 8' x 2" Mount Pipe	A	From Leg	4.00 0.00 0.00	0.0000	175.00	1" Ice	3.12	1.96	0.12
						2" Ice			
						No Ice	1.90	1.90	0.03
						1/2" Ice	2.73	2.73	0.04
						Ice	3.40	3.40	0.06
(2) 8' x 2" Mount Pipe	B	From Leg	4.00 0.00 0.00	0.0000	175.00	1" Ice	4.40	4.40	0.12
						2" Ice			
						No Ice	1.90	1.90	0.03
						1/2" Ice	2.73	2.73	0.04
						Ice	3.40	3.40	0.06
(2) 8' x 2" Mount Pipe	C	From Leg	4.00 0.00 0.00	0.0000	175.00	1" Ice	4.40	4.40	0.12
						2" Ice			
						No Ice	1.90	1.90	0.03
						1/2" Ice	2.73	2.73	0.04
						Ice	3.40	3.40	0.06
Commscope MC-PK8-DSH	C	None		0.0000	175.00	1" Ice	4.40	4.40	0.12
						2" Ice			
						No Ice	34.24	34.24	1.75
						1/2" Ice	62.95	62.95	2.10
						Ice	91.66	91.66	2.45
**175** **164** APXVSPP18-C-A20 w/ Mount Pipe	A	From Centroid- Leg	4.00 0.00 2.00	0.0000	164.00	1" Ice	6.44	5.82	0.42
						2" Ice			
						No Ice	4.60	4.01	0.10
						1/2" Ice	5.05	4.45	0.16
						Ice	5.50	4.89	0.23
APXVSPP18-C-A20 w/ Mount Pipe	B	From Centroid- Leg	4.00 0.00 2.00	0.0000	164.00	1" Ice	6.44	5.82	0.42
						2" Ice			
						No Ice	4.60	4.01	0.10
						1/2" Ice	5.05	4.45	0.16
						Ice	5.50	4.89	0.23
APXVSPP18-C-A20 w/ Mount Pipe	C	From Centroid- Leg	4.00 0.00 2.00	0.0000	164.00	1" Ice	6.44	5.82	0.42
						2" Ice			
						No Ice	4.60	4.01	0.10
						1/2" Ice	5.05	4.45	0.16
						Ice	5.50	4.89	0.23
APXVTM14-ALU-I20 w/ Mount Pipe	A	From Centroid- Leg	4.00 0.00 2.00	0.0000	164.00	1" Ice	5.71	4.40	0.33
						2" Ice			
						No Ice	4.09	2.86	0.08
						1/2" Ice	4.48	3.23	0.13
						Ice	4.88	3.61	0.19
APXVTM14-ALU-I20 w/ Mount Pipe	B	From Centroid- Leg	4.00 0.00 2.00	0.0000	164.00	1" Ice	5.71	4.40	0.33
						2" Ice			
						No Ice	4.09	2.86	0.08
						1/2" Ice	4.48	3.23	0.13
						Ice	4.88	3.61	0.19
APXVTM14-ALU-I20 w/ Mount Pipe	C	From Centroid- Leg	4.00 0.00 2.00	0.0000	164.00	1" Ice	5.71	4.40	0.33
						2" Ice			
						No Ice	4.09	2.86	0.08
						1/2" Ice	4.48	3.23	0.13
						Ice	4.88	3.61	0.19
LLPX310R w/ Mount Pipe	A	From	4.00	0.0000	164.00	No Ice	3.88	2.36	0.06

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C <sub>AA</sub> Front	C <sub>AA</sub> Side	Weight
			Horz Lateral	Vert					
		Centroid-Leg	0.00				4.29	2.73	0.09
			2.00			1/2" Ice	4.72	3.12	0.13
						1" Ice	5.61	3.94	0.24
						2" Ice			
LLPX310R w/ Mount Pipe	B	From Centroid-Leg	4.00	0.0000	164.00	No Ice	3.88	2.36	0.06
			0.00			1/2" Ice	4.29	2.73	0.09
			2.00			1" Ice	4.72	3.12	0.13
						2" Ice	5.61	3.94	0.24
LLPX310R w/ Mount Pipe	C	From Centroid-Leg	4.00	0.0000	164.00	No Ice	3.88	2.36	0.06
			0.00			1/2" Ice	4.29	2.73	0.09
			2.00			1" Ice	4.72	3.12	0.13
						2" Ice	5.61	3.94	0.24
1900MHz RRH (65MHz)	A	From Centroid-Leg	4.00	0.0000	164.00	No Ice	2.31	2.38	0.06
			0.00			1/2" Ice	2.52	2.58	0.08
			2.00			1" Ice	2.73	2.79	0.11
						2" Ice	3.17	3.24	0.18
1900MHz RRH (65MHz)	B	From Centroid-Leg	4.00	0.0000	164.00	No Ice	2.31	2.38	0.06
			0.00			1/2" Ice	2.52	2.58	0.08
			2.00			1" Ice	2.73	2.79	0.11
						2" Ice	3.17	3.24	0.18
1900MHz RRH (65MHz)	C	From Centroid-Leg	4.00	0.0000	164.00	No Ice	2.31	2.38	0.06
			0.00			1/2" Ice	2.52	2.58	0.08
			2.00			1" Ice	2.73	2.79	0.11
						2" Ice	3.17	3.24	0.18
800MHZ RRH	A	From Centroid-Leg	4.00	0.0000	164.00	No Ice	2.13	1.77	0.05
			0.00			1/2" Ice	2.32	1.95	0.07
			2.00			1" Ice	2.51	2.13	0.10
						2" Ice	2.92	2.51	0.16
800MHZ RRH	B	From Centroid-Leg	4.00	0.0000	164.00	No Ice	2.13	1.77	0.05
			0.00			1/2" Ice	2.32	1.95	0.07
			2.00			1" Ice	2.51	2.13	0.10
						2" Ice	2.92	2.51	0.16
800MHZ RRH	C	From Centroid-Leg	4.00	0.0000	164.00	No Ice	2.13	1.77	0.05
			0.00			1/2" Ice	2.32	1.95	0.07
			2.00			1" Ice	2.51	2.13	0.10
						2" Ice	2.92	2.51	0.16
800 EXTERNAL NOTCH FILTER	A	From Centroid-Leg	4.00	0.0000	164.00	No Ice	0.66	0.32	0.01
			0.00			1/2" Ice	0.76	0.40	0.02
			2.00			1" Ice	0.87	0.48	0.02
						2" Ice	1.11	0.67	0.04
800 EXTERNAL NOTCH FILTER	B	From Centroid-Leg	4.00	0.0000	164.00	No Ice	0.66	0.32	0.01
			0.00			1/2" Ice	0.76	0.40	0.02
			2.00			1" Ice	0.87	0.48	0.02
						2" Ice	1.11	0.67	0.04
800 EXTERNAL NOTCH FILTER	C	From Centroid-Leg	4.00	0.0000	164.00	No Ice	0.66	0.32	0.01
			0.00			1/2" Ice	0.76	0.40	0.02
			2.00			1" Ice	0.87	0.48	0.02
						2" Ice	1.11	0.67	0.04
(3) ACU-A20-N	A	From Centroid-Leg	4.00	0.0000	164.00	No Ice	0.07	0.12	0.00
			0.00			1/2" Ice	0.10	0.16	0.00
			2.00			1" Ice	0.15	0.21	0.00
						2" Ice	0.26	0.34	0.01
(3) ACU-A20-N	B	From	4.00	0.0000	164.00	No Ice	0.07	0.12	0.00



Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C <sub>AA</sub> Front	C <sub>AA</sub> Side	Weight	
			Horz Lateral	Vert						ft
(3) ACU-A20-N	C	Centroid-Leg	0.00	2.00	0.0000	164.00	1/2"	0.10	0.16	0.00
							Ice	0.15	0.21	0.00
							1" Ice	0.26	0.34	0.01
							2" Ice			
TD-RRH8x20-25	B	From Centroid-Leg	4.00	0.00	0.0000	164.00	No Ice	0.07	0.12	0.00
							1/2"	0.10	0.16	0.00
							Ice	0.15	0.21	0.00
							1" Ice	0.26	0.34	0.01
TD-RRH8x20-25	B	From Centroid-Leg	4.00	0.00	0.0000	164.00	No Ice	4.05	1.53	0.07
							1/2"	4.30	1.71	0.10
							Ice	4.56	1.90	0.13
							1" Ice	5.10	2.30	0.20
TD-RRH8x20-25	B	From Centroid-Leg	4.00	0.00	0.0000	164.00	No Ice	4.05	1.53	0.07
							1/2"	4.30	1.71	0.10
							Ice	4.56	1.90	0.13
							1" Ice	5.10	2.30	0.20
TD-RRH8x20-25	C	From Centroid-Leg	4.00	0.00	0.0000	164.00	No Ice	4.05	1.53	0.07
							1/2"	4.30	1.71	0.10
							Ice	4.56	1.90	0.13
							1" Ice	5.10	2.30	0.20
FDD_R6_RRH	A	From Centroid-Leg	4.00	0.00	0.0000	164.00	No Ice	1.53	0.68	0.03
							1/2"	1.69	0.80	0.04
							Ice	1.85	0.92	0.06
							1" Ice	2.20	1.19	0.09
FDD_R6_RRH	B	From Centroid-Leg	4.00	0.00	0.0000	164.00	No Ice	1.53	0.68	0.03
							1/2"	1.69	0.80	0.04
							Ice	1.85	0.92	0.06
							1" Ice	2.20	1.19	0.09
FDD_R6_RRH	C	From Centroid-Leg	4.00	0.00	0.0000	164.00	No Ice	1.53	0.68	0.03
							1/2"	1.69	0.80	0.04
							Ice	1.85	0.92	0.06
							1" Ice	2.20	1.19	0.09
(2) 2.4" Dia x 6-ft Pipe	A	From Centroid-Leg	4.00	2.00	0.0000	164.00	No Ice	1.43	1.43	0.02
							1/2"	1.93	1.93	0.03
							Ice	2.30	2.30	0.05
							1" Ice	3.06	3.06	0.09
(2) 2.4" Dia x 6-ft Pipe	B	From Centroid-Leg	4.00	-2.00	0.0000	164.00	No Ice	1.43	1.43	0.02
							1/2"	1.93	1.93	0.03
							Ice	2.30	2.30	0.05
							1" Ice	3.06	3.06	0.09
(2) 2.4" Dia x 6-ft Pipe	C	From Centroid-Leg	4.00	2.00	0.0000	164.00	No Ice	1.43	1.43	0.02
							1/2"	1.93	1.93	0.03
							Ice	2.30	2.30	0.05
							1" Ice	3.06	3.06	0.09
8' Ladder	A	From Centroid-Leg	2.00	0.00	0.0000	164.00	No Ice	1.53	5.33	0.10
							1/2"	4.36	8.08	0.11
							Ice	7.19	10.83	0.13
							1" Ice	12.86	16.33	0.16
Platform Mount [LP 602-1]	C	None			0.0000	164.00	No Ice	32.03	32.03	1.34
							1/2"	38.71	38.71	1.80
							Ice	45.39	45.39	2.26
							1" Ice	58.75	58.75	3.17
							2" Ice			

\*\*154\*\*

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C <sub>AA</sub> Front	C <sub>AA</sub> Side	Weight
			Horz	Lateral					
(2) DB844G65ZAXY w/ Mount Pipe	A	From Centroid- Face	4.00	0.0000	154.00	No Ice	4.23	4.51	0.03
			0.00	0.00		1/2"	4.71	5.00	0.08
			1.00	1.00		Ice	5.21	5.50	0.13
						1" Ice	6.26	6.57	0.25
						2" Ice			
(2) DB844G65ZAXY w/ Mount Pipe	B	From Centroid- Face	4.00	0.0000	154.00	No Ice	4.23	4.51	0.03
			0.00	0.00		1/2"	4.71	5.00	0.08
			1.00	1.00		Ice	5.21	5.50	0.13
						1" Ice	6.26	6.57	0.25
						2" Ice			
(2) LPA-4016 w/ Mount Pipe	C	From Centroid- Face	4.00	0.0000	154.00	No Ice	5.06	6.03	0.04
			0.00	0.00		1/2"	8.44	6.06	0.08
			1.00	1.00		Ice	11.82	6.09	0.12
						1" Ice	18.58	6.15	0.19
						2" Ice			
(2) JAHH-65B-R3B w/ Mount Pipe	A	From Centroid- Face	4.00	0.0000	154.00	No Ice	5.50	4.38	0.10
			0.00	0.00		1/2"	5.97	4.84	0.17
			1.00	1.00		Ice	6.45	5.30	0.25
						1" Ice	7.44	6.26	0.46
						2" Ice			
(2) JAHH-65B-R3B w/ Mount Pipe	B	From Centroid- Face	4.00	0.0000	154.00	No Ice	5.50	4.38	0.10
			0.00	0.00		1/2"	5.97	4.84	0.17
			1.00	1.00		Ice	6.45	5.30	0.25
						1" Ice	7.44	6.26	0.46
						2" Ice			
(2) JAHH-65B-R3B w/ Mount Pipe	C	From Centroid- Face	4.00	0.0000	154.00	No Ice	5.50	4.38	0.10
			0.00	0.00		1/2"	5.97	4.84	0.17
			1.00	1.00		Ice	6.45	5.30	0.25
						1" Ice	7.44	6.26	0.46
						2" Ice			
Sub6 Antenna - VZS01 w/ Mount Pipe	A	From Centroid- Face	4.00	0.0000	154.00	No Ice	4.92	2.69	0.10
			0.00	0.00		1/2"	5.26	3.15	0.14
			1.00	1.00		Ice	5.62	3.63	0.19
						1" Ice	6.37	4.64	0.29
						2" Ice			
Sub6 Antenna - VZS01 w/ Mount Pipe	B	From Centroid- Face	4.00	0.0000	154.00	No Ice	4.92	2.69	0.10
			0.00	0.00		1/2"	5.26	3.15	0.14
			1.00	1.00		Ice	5.62	3.63	0.19
						1" Ice	6.37	4.64	0.29
						2" Ice			
Sub6 Antenna - VZS01 w/ Mount Pipe	C	From Centroid- Face	4.00	0.0000	154.00	No Ice	4.92	2.69	0.10
			0.00	0.00		1/2"	5.26	3.15	0.14
			1.00	1.00		Ice	5.62	3.63	0.19
						1" Ice	6.37	4.64	0.29
						2" Ice			
(2) DB-B1-6C-8AB-0Z	A	From Centroid- Face	4.00	0.0000	154.00	No Ice	4.80	2.00	0.04
			0.00	0.00		1/2"	5.07	2.19	0.08
			1.00	1.00		Ice	5.35	2.39	0.12
						1" Ice	5.93	2.81	0.21
						2" Ice			
CBC78T-DS-43-2X	A	From Centroid- Face	4.00	0.0000	154.00	No Ice	0.37	0.51	0.02
			0.00	0.00		1/2"	0.45	0.60	0.03
			1.00	1.00		Ice	0.53	0.70	0.04
						1" Ice	0.72	0.93	0.06
						2" Ice			
CBC78T-DS-43-2X	B	From Centroid- Face	4.00	0.0000	154.00	No Ice	0.37	0.51	0.02
			0.00	0.00		1/2"	0.45	0.60	0.03
			1.00	1.00		Ice	0.53	0.70	0.04
						1" Ice	0.72	0.93	0.06
						2" Ice			
CBC78T-DS-43-2X	C	From Centroid- Face	4.00	0.0000	154.00	No Ice	0.37	0.51	0.02
			0.00	0.00		1/2"	0.45	0.60	0.03
			1.00	1.00		Ice	0.53	0.70	0.04
						1" Ice	0.72	0.93	0.06
						2" Ice			

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C <sub>AA</sub> Front	C <sub>AA</sub> Side	Weight
			Horz	Lateral					
			ft	ft	°	ft	ft <sup>2</sup>	ft <sup>2</sup>	K
RFV01U-D1A	A	From Centroid-Face	4.00	0.0000	154.00	No Ice	1.88	1.25	0.08
			0.00	0.0000		1/2"	2.05	1.39	0.10
			1.00	0.0000		Ice	2.22	1.54	0.12
				0.0000		1" Ice	2.60	1.86	0.18
				0.0000		2" Ice			
RFV01U-D1A	B	From Centroid-Face	4.00	0.0000	154.00	No Ice	1.88	1.25	0.08
			0.00	0.0000		1/2"	2.05	1.39	0.10
			1.00	0.0000		Ice	2.22	1.54	0.12
				0.0000		1" Ice	2.60	1.86	0.18
				0.0000		2" Ice			
RFV01U-D1A	C	From Centroid-Face	4.00	0.0000	154.00	No Ice	1.88	1.25	0.08
			0.00	0.0000		1/2"	2.05	1.39	0.10
			1.00	0.0000		Ice	2.22	1.54	0.12
				0.0000		1" Ice	2.60	1.86	0.18
				0.0000		2" Ice			
RFV01U-D2A	A	From Centroid-Face	4.00	0.0000	154.00	No Ice	1.88	1.01	0.07
			0.00	0.0000		1/2"	2.05	1.14	0.09
			1.00	0.0000		Ice	2.22	1.28	0.11
				0.0000		1" Ice	2.60	1.59	0.15
				0.0000		2" Ice			
RFV01U-D2A	B	From Centroid-Face	4.00	0.0000	154.00	No Ice	1.88	1.01	0.07
			0.00	0.0000		1/2"	2.05	1.14	0.09
			1.00	0.0000		Ice	2.22	1.28	0.11
				0.0000		1" Ice	2.60	1.59	0.15
				0.0000		2" Ice			
RFV01U-D2A	C	From Centroid-Face	4.00	0.0000	154.00	No Ice	1.88	1.01	0.07
			0.00	0.0000		1/2"	2.05	1.14	0.09
			1.00	0.0000		Ice	2.22	1.28	0.11
				0.0000		1" Ice	2.60	1.59	0.15
				0.0000		2" Ice			
2.4" Dia x 6-ft Pipe	A	From Centroid-Face	4.00	0.0000	154.00	No Ice	1.43	1.43	0.02
			0.00	0.0000		1/2"	1.93	1.93	0.03
			0.00	0.0000		Ice	2.30	2.30	0.05
				0.0000		1" Ice	3.06	3.06	0.09
				0.0000		2" Ice			
2.4" Dia x 6-ft Pipe	B	From Centroid-Face	4.00	0.0000	154.00	No Ice	1.43	1.43	0.02
			0.00	0.0000		1/2"	1.93	1.93	0.03
			0.00	0.0000		Ice	2.30	2.30	0.05
				0.0000		1" Ice	3.06	3.06	0.09
				0.0000		2" Ice			
2.4" Dia x 6-ft Pipe	C	From Centroid-Face	4.00	0.0000	154.00	No Ice	1.43	1.43	0.02
			0.00	0.0000		1/2"	1.93	1.93	0.03
			0.00	0.0000		Ice	2.30	2.30	0.05
				0.0000		1" Ice	3.06	3.06	0.09
				0.0000		2" Ice			
Platform Mount [LP 601-1]	C	None		0.0000	154.00	No Ice	28.47	28.47	1.12
				0.0000		1/2"	33.59	33.59	1.51
				0.0000		Ice	38.71	38.71	1.91
				0.0000		1" Ice	48.95	48.95	2.69
				0.0000		2" Ice			
**144**									
ERICSSON AIR 21 B4A B2P w/ Mount Pipe	A	From Centroid-Face	4.00	0.0000	146.00	No Ice	3.14	2.59	0.11
			0.00	0.0000		1/2"	3.45	2.88	0.16
			-1.00	0.0000		Ice	3.77	3.19	0.22
				0.0000		1" Ice	4.43	3.84	0.37
				0.0000		2" Ice			
ERICSSON AIR 21 B4A B2P w/ Mount Pipe	B	From Centroid-Face	4.00	0.0000	146.00	No Ice	3.14	2.59	0.11
			0.00	0.0000		1/2"	3.45	2.88	0.16
			-1.00	0.0000		Ice	3.77	3.19	0.22
				0.0000		1" Ice	4.43	3.84	0.37
				0.0000		2" Ice			
ERICSSON AIR 21 B4A B2P w/ Mount Pipe	C	From Centroid-Face	4.00	0.0000	146.00	No Ice	3.14	2.59	0.11
			0.00	0.0000		1/2"	3.45	2.88	0.16
			-1.00	0.0000		Ice	3.77	3.19	0.22
				0.0000		1" Ice	4.43	3.84	0.37
				0.0000		2" Ice			

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C <sub>AA</sub> Front	C <sub>AA</sub> Side	Weight	
			Horz	Lateral						Vert
			ft	ft	°	ft	ft <sup>2</sup>	ft <sup>2</sup>	K	
APXVAARR24_43-U-NA20 w/ Mount Pipe	A	From Centroid- Face	4.00	0.0000	146.00	2" Ice				
			0.00			No Ice	14.69	6.87	0.19	
			-1.00			1/2"	15.46	7.55	0.31	
						Ice	16.23	8.25	0.46	
APXVAARR24_43-U-NA20 w/ Mount Pipe	B	From Centroid- Face	4.00	0.0000	146.00	2" Ice				
			0.00			No Ice	14.69	6.87	0.19	
			-1.00			1/2"	15.46	7.55	0.31	
						Ice	16.23	8.25	0.46	
APXVAARR24_43-U-NA20 w/ Mount Pipe	C	From Centroid- Face	4.00	0.0000	146.00	2" Ice				
			0.00			No Ice	14.69	6.87	0.19	
			-1.00			1/2"	15.46	7.55	0.31	
						Ice	16.23	8.25	0.46	
KRY 112 144/1	A	From Centroid- Face	4.00	0.0000	146.00	2" Ice				
			0.00			No Ice	0.35	0.17	0.01	
			-1.00			1/2"	0.43	0.23	0.01	
						Ice	0.51	0.30	0.02	
KRY 112 144/1	B	From Centroid- Face	4.00	0.0000	146.00	2" Ice				
			0.00			No Ice	0.35	0.17	0.01	
			-1.00			1/2"	0.43	0.23	0.01	
						Ice	0.51	0.30	0.02	
KRY 112 144/1	C	From Centroid- Face	4.00	0.0000	146.00	2" Ice				
			0.00			No Ice	0.35	0.17	0.01	
			-1.00			1/2"	0.43	0.23	0.01	
						Ice	0.51	0.30	0.02	
RADIO 4449 B12/B71	A	From Centroid- Face	4.00	0.0000	146.00	2" Ice				
			0.00			No Ice	1.65	1.16	0.07	
			-1.00			1/2"	1.81	1.30	0.09	
						Ice	1.98	1.45	0.11	
RADIO 4449 B12/B71	B	From Centroid- Face	4.00	0.0000	146.00	2" Ice				
			0.00			No Ice	1.65	1.16	0.07	
			-1.00			1/2"	1.81	1.30	0.09	
						Ice	1.98	1.45	0.11	
RADIO 4449 B12/B71	C	From Centroid- Face	4.00	0.0000	146.00	2" Ice				
			0.00			No Ice	1.65	1.16	0.07	
			-1.00			1/2"	1.81	1.30	0.09	
						Ice	1.98	1.45	0.11	
RRUS 11 B2	A	From Centroid- Face	4.00	0.0000	146.00	2" Ice				
			0.00			No Ice	2.83	1.18	0.05	
			-1.00			1/2"	3.04	1.33	0.07	
						Ice	3.26	1.48	0.10	
RRUS 11 B2	B	From Centroid- Face	4.00	0.0000	146.00	2" Ice				
			0.00			No Ice	2.83	1.18	0.05	
			-1.00			1/2"	3.04	1.33	0.07	
						Ice	3.26	1.48	0.10	
RRUS 11 B2	C	From Centroid- Face	4.00	0.0000	146.00	2" Ice				
			0.00			No Ice	2.83	1.18	0.05	
			-1.00			1/2"	3.04	1.33	0.07	
						Ice	3.26	1.48	0.10	
2.4" Dia x 6-ft Pipe	A	From Centroid- Face	4.00	0.0000	146.00	2" Ice				
			0.00			No Ice	1.43	1.43	0.02	
			0.00			1/2"	1.93	1.93	0.03	
						Ice	2.30	2.30	0.05	
							1" Ice	3.06	3.06	0.09

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C <sub>AA</sub> Front	C <sub>AA</sub> Side	Weight	
			Horz Lateral	Vert						
			ft	ft	°	ft	ft <sup>2</sup>	ft <sup>2</sup>	K	
2.4" Dia x 6-ft Pipe	B	From Centroid-Face	4.00	0.00	0.0000	146.00	2" Ice			
			0.00				No Ice	1.43	1.43	0.02
			0.00				1/2"	1.93	1.93	0.03
							Ice	2.30	2.30	0.05
							1" Ice	3.06	3.06	0.09
2.4" Dia x 6-ft Pipe	C	From Centroid-Face	4.00	0.00	0.0000	146.00	2" Ice			
			0.00				No Ice	1.43	1.43	0.02
			0.00				1/2"	1.93	1.93	0.03
							Ice	2.30	2.30	0.05
							1" Ice	3.06	3.06	0.09
Platform Mount [LP 602-1]	C	None			0.0000	146.00	2" Ice			
							No Ice	32.03	32.03	1.34
							1/2"	38.71	38.71	1.80
							Ice	45.39	45.39	2.26
							1" Ice	58.75	58.75	3.17
**134** (4) DB844H90E-XY w/ Mount Pipe	A	From Centroid-Leg	4.00	0.00	0.0000	134.00	2" Ice			
			0.00				No Ice	2.24	3.34	0.04
			1.00				1/2"	2.61	3.73	0.08
							Ice	2.99	4.13	0.12
							1" Ice	3.78	4.97	0.23
(4) DB844H90E-XY w/ Mount Pipe	B	From Centroid-Leg	4.00	0.00	0.0000	134.00	2" Ice			
			0.00				No Ice	2.24	3.34	0.04
			1.00				1/2"	2.61	3.73	0.08
							Ice	2.99	4.13	0.12
							1" Ice	3.78	4.97	0.23
(4) DB844H90E-XY w/ Mount Pipe	C	From Centroid-Leg	4.00	0.00	0.0000	134.00	2" Ice			
			0.00				No Ice	2.24	3.34	0.04
			1.00				1/2"	2.61	3.73	0.08
							Ice	2.99	4.13	0.12
							1" Ice	3.78	4.97	0.23
Platform Mount [LP 303-1]	C	None			0.0000	134.00	2" Ice			
							No Ice	14.66	14.66	1.25
							1/2"	18.87	18.87	1.48
							Ice	23.08	23.08	1.71
							1" Ice	31.50	31.50	2.18
		2" Ice								

\*\*\*  
 \*\*  
 \*

### Dishes

Description	Face or Leg	Dish Type	Offset Type	Offsets:		Azimuth Adjustment	3 dB Beam Width	Elevation	Outside Diameter	Aperture Area	Weight	
				Horz Lateral	Vert							
				ft	ft	°	°	ft	ft	ft <sup>2</sup>	K	
**164** A-ANT-23G-2-C	A	Paraboloid w/Shroud (HP)	From Centroid-Leg	4.00	0.00	0.0000		164.00	2.17	No Ice	3.72	0.01
				0.00						1/2" Ice	4.01	0.02
				2.00						1" Ice	4.30	0.03
										2" Ice	4.88	0.05
										No Ice	3.72	0.01
A-ANT-23G-2-C	B	Paraboloid w/Shroud (HP)	From Centroid-Leg	4.00	0.00	40.0000		164.00	2.17	No Ice	3.72	0.01
				0.00						1/2" Ice	4.01	0.02
				2.00						1" Ice	4.30	0.03
										2" Ice	4.88	0.05
										No Ice	3.72	0.01
A-ANT-23G-2-C	C	Paraboloid w/Shroud (HP)	From Centroid-Leg	4.00	0.00	20.0000		164.00	2.17	No Ice	3.72	0.01
										1/2" Ice	4.01	0.02
										1" Ice	4.30	0.03

Description	Face or Leg	Dish Type	Offset Type	Offsets: Horz Lateral Vert ft	Azimuth Adjustment °	3 dB Beam Width °	Elevation ft	Outside Diameter ft	Aperture Area ft <sup>2</sup>	Weight K
			d-Leg	2.00				1" Ice	4.30	0.03
								2" Ice	4.88	0.05
***										

## Load Combinations

Comb. No.	Description
1	Dead Only
2	1.2 Dead+1.0 Wind 0 deg - No Ice
3	0.9 Dead+1.0 Wind 0 deg - No Ice
4	1.2 Dead+1.0 Wind 30 deg - No Ice
5	0.9 Dead+1.0 Wind 30 deg - No Ice
6	1.2 Dead+1.0 Wind 60 deg - No Ice
7	0.9 Dead+1.0 Wind 60 deg - No Ice
8	1.2 Dead+1.0 Wind 90 deg - No Ice
9	0.9 Dead+1.0 Wind 90 deg - No Ice
10	1.2 Dead+1.0 Wind 120 deg - No Ice
11	0.9 Dead+1.0 Wind 120 deg - No Ice
12	1.2 Dead+1.0 Wind 150 deg - No Ice
13	0.9 Dead+1.0 Wind 150 deg - No Ice
14	1.2 Dead+1.0 Wind 180 deg - No Ice
15	0.9 Dead+1.0 Wind 180 deg - No Ice
16	1.2 Dead+1.0 Wind 210 deg - No Ice
17	0.9 Dead+1.0 Wind 210 deg - No Ice
18	1.2 Dead+1.0 Wind 240 deg - No Ice
19	0.9 Dead+1.0 Wind 240 deg - No Ice
20	1.2 Dead+1.0 Wind 270 deg - No Ice
21	0.9 Dead+1.0 Wind 270 deg - No Ice
22	1.2 Dead+1.0 Wind 300 deg - No Ice
23	0.9 Dead+1.0 Wind 300 deg - No Ice
24	1.2 Dead+1.0 Wind 330 deg - No Ice
25	0.9 Dead+1.0 Wind 330 deg - No Ice
26	1.2 Dead+1.0 Ice+1.0 Temp
27	1.2 Dead+1.0 Wind 0 deg+1.0 Ice+1.0 Temp
28	1.2 Dead+1.0 Wind 30 deg+1.0 Ice+1.0 Temp
29	1.2 Dead+1.0 Wind 60 deg+1.0 Ice+1.0 Temp
30	1.2 Dead+1.0 Wind 90 deg+1.0 Ice+1.0 Temp
31	1.2 Dead+1.0 Wind 120 deg+1.0 Ice+1.0 Temp
32	1.2 Dead+1.0 Wind 150 deg+1.0 Ice+1.0 Temp
33	1.2 Dead+1.0 Wind 180 deg+1.0 Ice+1.0 Temp
34	1.2 Dead+1.0 Wind 210 deg+1.0 Ice+1.0 Temp
35	1.2 Dead+1.0 Wind 240 deg+1.0 Ice+1.0 Temp
36	1.2 Dead+1.0 Wind 270 deg+1.0 Ice+1.0 Temp
37	1.2 Dead+1.0 Wind 300 deg+1.0 Ice+1.0 Temp
38	1.2 Dead+1.0 Wind 330 deg+1.0 Ice+1.0 Temp
39	Dead+Wind 0 deg - Service
40	Dead+Wind 30 deg - Service
41	Dead+Wind 60 deg - Service
42	Dead+Wind 90 deg - Service
43	Dead+Wind 120 deg - Service
44	Dead+Wind 150 deg - Service
45	Dead+Wind 180 deg - Service
46	Dead+Wind 210 deg - Service
47	Dead+Wind 240 deg - Service
48	Dead+Wind 270 deg - Service
49	Dead+Wind 300 deg - Service
50	Dead+Wind 330 deg - Service

## Maximum Member Forces

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Axial K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
L1	195 - 157.65	Pole	Max Tension	8	0.00	0.00	-0.00
			Max. Compression	26	-31.60	-1.50	0.64
			Max. Mx	8	-13.26	-269.11	-0.21
			Max. My	2	-13.29	-0.21	268.75
			Max. Vy	8	18.22	-269.11	-0.21
			Max. Vx	14	18.03	-0.65	-268.54
			Max. Torque	22			-1.23
L2	157.65 - 117.08	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-63.71	-2.11	2.74
			Max. Mx	8	-30.04	-1322.78	-4.99
			Max. My	2	-30.08	4.88	1310.21
			Max. Vy	8	32.52	-1322.78	-4.99
			Max. Vx	14	32.17	-4.98	-1309.34
			Max. Torque	22			-1.23
L3	117.08 - 81.09	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-79.09	-4.18	4.00
			Max. Mx	8	-41.74	-2526.50	-9.90
			Max. My	2	-41.77	9.62	2501.55
			Max. Vy	8	36.14	-2526.50	-9.90
			Max. Vx	14	35.79	-9.78	-2500.22
			Max. Torque	22			-0.86
L4	81.09 - 40.03	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-102.65	-6.65	5.42
			Max. Mx	8	-60.63	-4055.61	-15.41
			Max. My	2	-60.65	14.90	4016.60
			Max. Vy	8	40.22	-4055.61	-15.41
			Max. Vx	14	39.88	-15.29	-4014.63
			Max. Torque	22			-0.86
L5	40.03 - 0	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-134.96	-9.94	7.32
			Max. Mx	8	-87.39	-6082.56	-21.82
			Max. My	2	-87.39	20.99	6027.01
			Max. Vy	8	44.03	-6082.56	-21.82
			Max. Vx	14	43.70	-21.85	-6024.19
			Max. Torque	22			-0.86

### Maximum Reactions

Location	Condition	Gov. Load Comb.	Vertical K	Horizontal, X K	Horizontal, Z K
Pole	Max. Vert	27	134.96	0.02	11.78
	Max. H <sub>x</sub>	21	65.56	43.94	0.21
	Max. H <sub>z</sub>	2	87.41	0.14	43.66
	Max. M <sub>x</sub>	2	6027.01	0.14	43.66
	Max. M <sub>z</sub>	8	6082.56	-43.99	-0.14
	Max. Torsion	10	0.61	-38.14	-22.00
	Min. Vert	17	65.56	21.84	-37.76
	Min. H <sub>x</sub>	8	87.41	-43.99	-0.14
	Min. H <sub>z</sub>	14	87.41	-0.12	-43.66
	Min. M <sub>x</sub>	14	-6024.19	-0.12	-43.66
	Min. M <sub>z</sub>	20	-6070.06	43.94	0.21
	Min. Torsion	22	-0.85	38.13	21.99

### Tower Mast Reaction Summary

Load Combination	Vertical K	Shear <sub>x</sub> K	Shear <sub>z</sub> K	Overturning Moment, M <sub>x</sub> kip-ft	Overturning Moment, M <sub>z</sub> kip-ft	Torque kip-ft
Dead Only	72.85	0.00	0.00	-1.21	-1.91	0.00
1.2 Dead+1.0 Wind 0 deg - No Ice	87.41	-0.14	-43.66	-6027.01	20.99	0.35
0.9 Dead+1.0 Wind 0 deg - No Ice	65.56	-0.14	-43.66	-5954.98	21.32	0.34
1.2 Dead+1.0 Wind 30 deg - No Ice	87.41	21.86	-37.76	-5211.91	-3019.55	0.30
0.9 Dead+1.0 Wind 30 deg - No Ice	65.56	21.86	-37.76	-5149.55	-2983.05	0.30
1.2 Dead+1.0 Wind 60 deg - No Ice	87.41	38.01	-21.74	-2999.91	-5253.90	-0.16
0.9 Dead+1.0 Wind 60 deg - No Ice	65.56	38.01	-21.74	-2963.86	-5190.81	-0.17
1.2 Dead+1.0 Wind 90 deg - No Ice	87.41	43.99	0.14	21.82	-6082.56	-0.61
0.9 Dead+1.0 Wind 90 deg - No Ice	65.56	43.99	0.14	21.93	-6009.64	-0.61
1.2 Dead+1.0 Wind 120 deg - No Ice	87.41	38.14	22.00	3040.23	-5274.44	-0.61
0.9 Dead+1.0 Wind 120 deg - No Ice	65.56	38.14	22.00	3004.44	-5211.10	-0.61
1.2 Dead+1.0 Wind 150 deg - No Ice	87.41	22.12	37.87	5226.41	-3064.11	-0.40
0.9 Dead+1.0 Wind 150 deg - No Ice	65.56	22.12	37.87	5164.63	-3027.05	-0.40
1.2 Dead+1.0 Wind 180 deg - No Ice	87.41	0.12	43.66	6024.19	-21.85	-0.25
0.9 Dead+1.0 Wind 180 deg - No Ice	65.56	0.12	43.66	5952.95	-20.99	-0.25
1.2 Dead+1.0 Wind 210 deg - No Ice	87.41	-21.84	37.76	5209.23	3012.41	-0.16
0.9 Dead+1.0 Wind 210 deg - No Ice	65.56	-21.84	37.76	5147.65	2977.17	-0.16
1.2 Dead+1.0 Wind 240 deg - No Ice	87.41	-37.95	21.78	3003.63	5239.11	0.11
0.9 Dead+1.0 Wind 240 deg - No Ice	65.56	-37.95	21.78	2968.29	5177.39	0.11
1.2 Dead+1.0 Wind 270 deg - No Ice	87.41	-43.94	-0.21	-36.73	6070.06	0.78
0.9 Dead+1.0 Wind 270 deg - No Ice	65.56	-43.94	-0.21	-35.89	5998.43	0.78
1.2 Dead+1.0 Wind 300 deg - No Ice	87.41	-38.13	-21.99	-3041.70	5268.67	0.85
0.9 Dead+1.0 Wind 300 deg - No Ice	65.56	-38.13	-21.99	-3005.14	5206.58	0.85
1.2 Dead+1.0 Wind 330 deg - No Ice	87.41	-22.11	-37.88	-5231.56	3056.73	0.49
0.9 Dead+1.0 Wind 330 deg - No Ice	65.56	-22.11	-37.88	-5168.96	3020.95	0.49
1.2 Dead+1.0 Ice+1.0 Temp	134.96	0.00	-0.00	-7.32	-9.94	0.00
1.2 Dead+1.0 Wind 0 deg+1.0 Ice+1.0 Temp	134.96	-0.02	-11.78	-1704.66	-5.98	0.11
1.2 Dead+1.0 Wind 30 deg+1.0 Ice+1.0 Temp	134.96	5.84	-10.19	-1475.93	-849.47	-0.01
1.2 Dead+1.0 Wind 60 deg+1.0 Ice+1.0 Temp	134.96	10.14	-5.88	-853.61	-1468.59	-0.20
1.2 Dead+1.0 Wind 90 deg+1.0 Ice+1.0 Temp	134.96	11.72	0.02	-3.29	-1697.28	-0.33
1.2 Dead+1.0 Wind 120 deg+1.0 Ice+1.0 Temp	134.96	10.16	5.92	846.50	-1472.34	-0.32
1.2 Dead+1.0 Wind 150 deg+1.0 Ice+1.0 Temp	134.96	5.88	10.21	1463.85	-857.81	-0.22
1.2 Dead+1.0 Wind 180 deg+1.0 Ice+1.0 Temp	134.96	0.02	11.78	1689.50	-13.81	-0.09
1.2 Dead+1.0 Wind 210 deg+1.0 Ice+1.0 Temp	134.96	-5.83	10.19	1460.79	828.38	0.04
1.2 Dead+1.0 Wind 240 deg+1.0 Ice+1.0 Temp	134.96	-10.12	5.88	839.81	1445.92	0.18
1.2 Dead+1.0 Wind 270 deg+1.0 Ice+1.0 Temp	134.96	-11.71	-0.04	-14.38	1675.07	0.36



Load Combination	Vertical	Shear <sub>x</sub>	Shear <sub>z</sub>	Overturning Moment, M <sub>x</sub>	Overturning Moment, M <sub>z</sub>	Torque
	K	K	K	kip-ft	kip-ft	kip-ft
deg+1.0 Ice+1.0 Temp						
1.2 Dead+1.0 Wind 300	134.96	-10.16	-5.92	-861.38	1451.54	0.37
deg+1.0 Ice+1.0 Temp						
1.2 Dead+1.0 Wind 330	134.96	-5.88	-10.21	-1479.49	836.67	0.24
deg+1.0 Ice+1.0 Temp						
Dead+Wind 0 deg - Service	72.85	-0.03	-9.48	-1300.34	3.05	0.08
Dead+Wind 30 deg - Service	72.85	4.74	-8.20	-1124.60	-652.47	0.07
Dead+Wind 60 deg - Service	72.85	8.25	-4.72	-647.71	-1134.19	-0.04
Dead+Wind 90 deg - Service	72.85	9.55	0.03	3.77	-1312.87	-0.14
Dead+Wind 120 deg - Service	72.85	8.28	4.78	654.54	-1138.63	-0.14
Dead+Wind 150 deg - Service	72.85	4.80	8.22	1125.87	-662.08	-0.09
Dead+Wind 180 deg - Service	72.85	0.03	9.48	1297.87	-6.18	-0.06
Dead+Wind 210 deg - Service	72.85	-4.74	8.20	1122.15	647.99	-0.04
Dead+Wind 240 deg - Service	72.85	-8.24	4.73	646.64	1128.07	0.02
Dead+Wind 270 deg - Service	72.85	-9.54	-0.05	-8.85	1307.23	0.17
Dead+Wind 300 deg - Service	72.85	-8.28	-4.77	-656.72	1134.45	0.19
Dead+Wind 330 deg - Service	72.85	-4.80	-8.22	-1128.85	657.55	0.11

## Solution Summary

Load Comb.	Sum of Applied Forces			Sum of Reactions			% Error
	PX K	PY K	PZ K	PX K	PY K	PZ K	
1	0.00	-72.85	0.00	0.00	72.85	0.00	0.000%
2	-0.14	-87.41	-43.66	0.14	87.41	43.66	0.000%
3	-0.14	-65.56	-43.66	0.14	65.56	43.66	0.000%
4	21.86	-87.41	-37.76	-21.86	87.41	37.76	0.000%
5	21.86	-65.56	-37.76	-21.86	65.56	37.76	0.000%
6	38.01	-87.41	-21.74	-38.01	87.41	21.74	0.000%
7	38.01	-65.56	-21.74	-38.01	65.56	21.74	0.000%
8	43.99	-87.41	0.14	-43.99	87.41	-0.14	0.000%
9	43.99	-65.56	0.14	-43.99	65.56	-0.14	0.000%
10	38.14	-87.41	22.00	-38.14	87.41	-22.00	0.000%
11	38.14	-65.56	22.00	-38.14	65.56	-22.00	0.000%
12	22.12	-87.41	37.87	-22.12	87.41	-37.87	0.000%
13	22.12	-65.56	37.87	-22.12	65.56	-37.87	0.000%
14	0.12	-87.41	43.66	-0.12	87.41	-43.66	0.000%
15	0.12	-65.56	43.66	-0.12	65.56	-43.66	0.000%
16	-21.84	-87.41	37.76	21.84	87.41	-37.76	0.000%
17	-21.84	-65.56	37.76	21.84	65.56	-37.76	0.000%
18	-37.95	-87.41	21.78	37.95	87.41	-21.78	0.000%
19	-37.95	-65.56	21.78	37.95	65.56	-21.78	0.000%
20	-43.94	-87.41	-0.21	43.94	87.41	0.21	0.000%
21	-43.94	-65.56	-0.21	43.94	65.56	0.21	0.000%
22	-38.13	-87.41	-21.99	38.13	87.41	21.99	0.000%
23	-38.13	-65.56	-21.99	38.13	65.56	21.99	0.000%
24	-22.11	-87.41	-37.88	22.11	87.41	37.88	0.000%
25	-22.11	-65.56	-37.88	22.11	65.56	37.88	0.000%
26	0.00	-134.96	0.00	-0.00	134.96	0.00	0.000%
27	-0.02	-134.96	-11.78	0.02	134.96	11.78	0.000%
28	5.84	-134.96	-10.19	-5.84	134.96	10.19	0.000%
29	10.13	-134.96	-5.88	-10.14	134.96	5.88	0.000%
30	11.72	-134.96	0.02	-11.72	134.96	-0.02	0.000%
31	10.16	-134.96	5.92	-10.16	134.96	-5.92	0.000%
32	5.88	-134.96	10.21	-5.88	134.96	-10.21	0.000%
33	0.02	-134.96	11.78	-0.02	134.96	-11.78	0.000%
34	-5.83	-134.96	10.19	5.83	134.96	-10.19	0.000%
35	-10.12	-134.96	5.88	10.12	134.96	-5.88	0.000%

Load Comb.	Sum of Applied Forces			Sum of Reactions			% Error
	PX K	PY K	PZ K	PX K	PY K	PZ K	
36	-11.71	-134.96	-0.04	11.71	134.96	0.04	0.000%
37	-10.16	-134.96	-5.92	10.16	134.96	5.92	0.000%
38	-5.88	-134.96	-10.21	5.88	134.96	10.21	0.000%
39	-0.03	-72.85	-9.48	0.03	72.85	9.48	0.000%
40	4.74	-72.85	-8.20	-4.74	72.85	8.20	0.000%
41	8.25	-72.85	-4.72	-8.25	72.85	4.72	0.000%
42	9.55	-72.85	0.03	-9.55	72.85	-0.03	0.000%
43	8.28	-72.85	4.78	-8.28	72.85	-4.78	0.000%
44	4.80	-72.85	8.22	-4.80	72.85	-8.22	0.000%
45	0.03	-72.85	9.48	-0.03	72.85	-9.48	0.000%
46	-4.74	-72.85	8.20	4.74	72.85	-8.20	0.000%
47	-8.24	-72.85	4.73	8.24	72.85	-4.73	0.000%
48	-9.54	-72.85	-0.05	9.54	72.85	0.05	0.000%
49	-8.28	-72.85	-4.77	8.28	72.85	4.77	0.000%
50	-4.80	-72.85	-8.22	4.80	72.85	8.22	0.000%

### Non-Linear Convergence Results

Load Combination	Converged?	Number of Cycles	Displacement Tolerance	Force Tolerance
1	Yes	4	0.00000001	0.00000001
2	Yes	4	0.00000001	0.00057187
3	Yes	4	0.00000001	0.00025365
4	Yes	6	0.00000001	0.00009275
5	Yes	5	0.00000001	0.00079055
6	Yes	6	0.00000001	0.00009290
7	Yes	5	0.00000001	0.00079155
8	Yes	4	0.00000001	0.00058115
9	Yes	4	0.00000001	0.00026012
10	Yes	6	0.00000001	0.00009370
11	Yes	5	0.00000001	0.00079799
12	Yes	6	0.00000001	0.00009446
13	Yes	5	0.00000001	0.00080497
14	Yes	4	0.00000001	0.00072190
15	Yes	4	0.00000001	0.00037995
16	Yes	6	0.00000001	0.00009195
17	Yes	5	0.00000001	0.00078412
18	Yes	6	0.00000001	0.00009238
19	Yes	5	0.00000001	0.00078748
20	Yes	5	0.00000001	0.00005918
21	Yes	4	0.00000001	0.00067359
22	Yes	6	0.00000001	0.00009516
23	Yes	5	0.00000001	0.00081081
24	Yes	6	0.00000001	0.00009340
25	Yes	5	0.00000001	0.00079588
26	Yes	4	0.00000001	0.00005240
27	Yes	5	0.00000001	0.00071097
28	Yes	5	0.00000001	0.00088893
29	Yes	5	0.00000001	0.00088875
30	Yes	5	0.00000001	0.00070739
31	Yes	5	0.00000001	0.00088169
32	Yes	5	0.00000001	0.00088697
33	Yes	5	0.00000001	0.00070328
34	Yes	5	0.00000001	0.00086766
35	Yes	5	0.00000001	0.00086491
36	Yes	5	0.00000001	0.00069859
37	Yes	5	0.00000001	0.00088570
38	Yes	5	0.00000001	0.00088249
39	Yes	4	0.00000001	0.00009052
40	Yes	4	0.00000001	0.00041184
41	Yes	4	0.00000001	0.00041163
42	Yes	4	0.00000001	0.00009240
43	Yes	4	0.00000001	0.00040874
44	Yes	4	0.00000001	0.00042111
45	Yes	4	0.00000001	0.00009067

46	Yes	4	0.00000001	0.00040024
47	Yes	4	0.00000001	0.00040353
48	Yes	4	0.00000001	0.00009530
49	Yes	4	0.00000001	0.00042842
50	Yes	4	0.00000001	0.00040699

### Maximum Tower Deflections - Service Wind

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
L1	195 - 157.65	25.793	43	1.1421	0.0010
L2	162.38 - 117.08	18.092	43	1.0834	0.0008
L3	122.94 - 81.09	10.062	43	0.8177	0.0003
L4	87.93 - 40.03	5.010	43	0.5371	0.0002
L5	47.98 - 0	1.511	43	0.2844	0.0001

### Critical Deflections and Radius of Curvature - Service Wind

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
185.00	7770.00 w/ Mount Pipe	43	23.390	1.1340	0.0010	46018
175.00	MX08FRO665-21 w/ Mount Pipe	43	21.014	1.1198	0.0009	23009
166.00	A-ANT-23G-2-C	43	18.919	1.0966	0.0008	15868
164.00	APXVSP18-C-A20 w/ Mount Pipe	43	18.461	1.0896	0.0008	14850
154.00	(2) DB844G65ZAXY w/ Mount Pipe	43	16.224	1.0434	0.0007	11334
146.00	ERICSSON AIR 21 B4A B2P w/ Mount Pipe	43	14.509	0.9945	0.0006	9543
134.00	(4) DB844H90E-XY w/ Mount Pipe	43	12.092	0.9071	0.0004	7714

### Maximum Tower Deflections - Design Wind

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
L1	195 - 157.65	119.568	10	5.3023	0.0045
L2	162.38 - 117.08	83.900	10	5.0303	0.0035
L3	122.94 - 81.09	46.675	10	3.7971	0.0014
L4	87.93 - 40.03	23.240	10	2.4934	0.0007
L5	47.98 - 0	7.009	10	1.3195	0.0003

### Critical Deflections and Radius of Curvature - Design Wind

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
185.00	7770.00 w/ Mount Pipe	10	108.441	5.2650	0.0043	10111
175.00	MX08FRO665-21 w/ Mount Pipe	10	97.434	5.1990	0.0040	5054
166.00	A-ANT-23G-2-C	10	87.729	5.0914	0.0036	3483
164.00	APXVSP18-C-A20 w/ Mount Pipe	10	85.608	5.0591	0.0036	3259
154.00	(2) DB844G65ZAXY w/ Mount Pipe	10	75.242	4.8446	0.0031	2480

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
146.00	Pipe ERICSSON AIR 21 B4A B2P w/ Mount Pipe	10	67.295	4.6178	0.0026	2084
134.00	(4) DB844H90E-XY w/ Mount Pipe	10	56.090	4.2120	0.0020	1680

### Compression Checks

### Pole Design Data

Section No.	Elevation ft	Size	L ft	$L_u$ ft	$Kl/r$	A $in^2$	$P_u$ K	$\phi P_n$ K	Ratio $\frac{P_u}{\phi P_n}$
L1	195 - 157.65 (1)	TP33.875x25x0.25	37.35	0.00	0.0	25.789 6	-13.26	1508.69	0.009
L2	157.65 - 117.08 (2)	TP42.9063x32.2511x0.31 25	45.30	0.00	0.0	40.880 5	-30.03	2391.51	0.013
L3	117.08 - 81.09 (3)	TP50.75x40.9029x0.375	41.85	0.00	0.0	58.043 2	-41.74	3395.53	0.012
L4	81.09 - 40.03 (4)	TP59.6563x48.3906x0.5	47.90	0.00	0.0	90.913 6	-60.63	5318.45	0.011
L5	40.03 - 0 (5)	TP68x56.7865x0.5	47.98	0.00	0.0	107.12 20	-87.39	6266.67	0.014

### Pole Bending Design Data

Section No.	Elevation ft	Size	$M_{ux}$ kip-ft	$\phi M_{nx}$ kip-ft	Ratio $\frac{M_{ux}}{\phi M_{nx}}$	$M_{uy}$ kip-ft	$\phi M_{ny}$ kip-ft	Ratio $\frac{M_{uy}}{\phi M_{ny}}$
L1	195 - 157.65 (1)	TP33.875x25x0.25	269.23	1168.53	0.230	0.00	1168.53	0.000
L2	157.65 - 117.08 (2)	TP42.9063x32.2511x0.31 25	1324.03	2337.04	0.567	0.00	2337.04	0.000
L3	117.08 - 81.09 (3)	TP50.75x40.9029x0.375	2528.97	3945.68	0.641	0.00	3945.68	0.000
L4	81.09 - 40.03 (4)	TP59.6563x48.3906x0.5	4059.43	7560.90	0.537	0.00	7560.90	0.000
L5	40.03 - 0 (5)	TP68x56.7865x0.5	6087.92	9944.92	0.612	0.00	9944.92	0.000

### Pole Shear Design Data

Section No.	Elevation ft	Size	Actual $V_u$ K	$\phi V_n$ K	Ratio $\frac{V_u}{\phi V_n}$	Actual $T_u$ kip-ft	$\phi T_n$ kip-ft	Ratio $\frac{T_u}{\phi T_n}$
L1	195 - 157.65 (1)	TP33.875x25x0.25	18.23	452.61	0.040	0.98	1288.25	0.001
L2	157.65 - 117.08 (2)	TP42.9063x32.2511x0.31 25	32.56	717.45	0.045	0.61	2589.60	0.000
L3	117.08 - 81.09 (3)	TP50.75x40.9029x0.375	36.18	1018.66	0.036	0.61	4350.33	0.000
L4	81.09 - 40.03 (4)	TP59.6563x48.3906x0.5	40.26	1595.53	0.025	0.61	8004.57	0.000
L5	40.03 - 0 (5)	TP68x56.7865x0.5	44.07	1880.00	0.023	0.61	11113.25	0.000

### Pole Interaction Design Data

Section No.	Elevation ft	Ratio $P_u$ $\phi P_n$	Ratio $M_{ux}$ $\phi M_{nx}$	Ratio $M_{uy}$ $\phi M_{ny}$	Ratio $V_u$ $\phi V_n$	Ratio $T_u$ $\phi T_n$	Comb. Stress Ratio	Allow. Stress Ratio	Criteria
L1	195 - 157.65 (1)	0.009	0.230	0.000	0.040	0.001	0.241	1.050	4.8.2
L2	157.65 - 117.08 (2)	0.013	0.567	0.000	0.045	0.000	0.581	1.050	4.8.2
L3	117.08 - 81.09 (3)	0.012	0.641	0.000	0.036	0.000	0.655	1.050	4.8.2
L4	81.09 - 40.03 (4)	0.011	0.537	0.000	0.025	0.000	0.549	1.050	4.8.2
L5	40.03 - 0 (5)	0.014	0.612	0.000	0.023	0.000	0.627	1.050	4.8.2

### Section Capacity Table

Section No.	Elevation ft	Component Type	Size	Critical Element	P K	$\phi P_{allow}$ K	% Capacity	Pass Fail
L1	195 - 157.65	Pole	TP33.875x25x0.25	1	-13.26	1584.12	22.9	Pass
L2	157.65 - 117.08	Pole	TP42.9063x32.2511x0.3125	2	-30.03	2511.09	55.4	Pass
L3	117.08 - 81.09	Pole	TP50.75x40.9029x0.375	3	-41.74	3565.31	62.3	Pass
L4	81.09 - 40.03	Pole	TP59.6563x48.3906x0.5	4	-60.63	5584.37	52.3	Pass
L5	40.03 - 0	Pole	TP68x56.7865x0.5	5	-87.39	6580.00	59.7	Pass
Summary								
Pole (L3)							62.3	Pass
<b>RATING =</b>							<b>62.3</b>	<b>Pass</b>

**APPENDIX B**  
**BASE LEVEL DRAWING**



(OTHER CONSIDERED EQUIPMENT)  
(3) 1-1/4" TO 164 FT LEVEL  
(1) 1-1/2" TO 164 FT LEVEL

(OTHER CONSIDERED EQUIPMENT-IN 2" CONDUIT)  
(6) 5/16" TO 164 FT LEVEL  
(OTHER CONSIDERED EQUIPMENT)  
(2) 7983A TO 164 FT LEVEL

(OTHER CONSIDERED EQUIPMENT)  
(20) 1-5/8" TO 154 FT LEVEL


CLIMBING  
PEGS

(OTHER CONSIDERED EQUIPMENT)  
(9) 1-1/4" TO 134 FT LEVEL  
(6) 1-5/8" TO 134 FT LEVEL

(OTHER CONSIDERED EQUIPMENT)  
(14) 1-5/8" TO 146 FT LEVEL

(OTHER CONSIDERED EQUIPMENT-IN 2 CONDUITS)  
(2) 3/8" TO 185 FT LEVEL  
(4) 5/8" TO 185 FT LEVEL  
(OTHER CONSIDERED EQUIPMENT)  
(12) 1-1/4" TO 185 FT LEVEL

(PROPOSED EQUIPMENT CONFIGURATION)  
(1) 1-3/4" TO 175 FT LEVEL



**APPENDIX C**  
**ADDITIONAL CALCULATIONS**



# Monopole Base Plate Connection




Site Info	
BU #	881535
Site Name	TRUMBULL TOWER
Order #	548692, Rev 1

Analysis Considerations	
TIA-222 Revision	H
Grout Considered:	No
$I_{gr}$ (in)	2

Applied Loads	
Moment (kip-ft)	6087.91
Axial Force (kips)	87.39
Shear Force (kips)	44.07

\*TIA-222-H Section 15.5 Applied



Connection Properties	Analysis Results
-----------------------	------------------

Anchor Rod Data
(24) 2-1/4" $\phi$ bolts (A615-75 N; $F_y=75$ ksi, $F_u=100$ ksi) on 76.5" BC
Base Plate Data
82.5" OD x 2.5" Plate (A572-60; $F_y=60$ ksi, $F_u=75$ ksi)
Stiffener Data
N/A
Pole Data
68" x 0.5" 18-sided pole (A572-65; $F_y=65$ ksi, $F_u=80$ ksi)

Anchor Rod Summary	<i>(units of kips, kip-in)</i>	
$P_{u,t} = 155.46$	$\phi P_{n,t} = 243.75$	<b>Stress Rating</b>
$V_u = 1.84$	$\phi V_n = 149.1$	<b>60.7%</b>
$\mu = n/a$	$\phi M_n = n/a$	<b>Pass</b>
Base Plate Summary		
Max Stress (ksi):	30.49	(Flexural)
Allowable Stress (ksi):	54	
Stress Rating:	<b>53.8%</b>	<b>Pass</b>

# Pier and Pad Foundation



BU #: 881535  
 Site Name: TRUMBULL TOWER  
 App. Number: 548692, Rev 1

TIA-222 Revision: H  
 Tower Type: Monopole

Top & Bot. Pad Rein. Different?:   
 Block Foundation?:   
 Rectangular Pad?:

Superstructure Analysis Reactions		
Compression, $P_{comp}$ :	87.41	kips
Base Shear, $V_{u\_comp}$ :	44.03	kips
Moment, $M_u$ :	6087.92	ft-kips
Tower Height, $H$ :	195	ft
BP Dist. Above Fdn, $bp_{dist}$ :	4.25	in

Foundation Analysis Checks				
	Capacity	Demand	Rating*	Check
<i>Lateral (Sliding) (kips)</i>	488.87	44.03	8.6%	Pass
<i>Bearing Pressure (ksf)</i>	9.00	2.46	27.4%	Pass
<i>Overturning (kip*ft)</i>	10303.34	6455.75	62.7%	Pass
<i>Pier Flexure (Comp.) (kip*ft)</i>	9313.13	6308.07	64.5%	Pass
<i>Pier Compression (kip)</i>	51554.88	160.31	0.3%	Pass
<i>Pad Flexure (kip*ft)</i>	5943.63	2217.06	35.5%	Pass
<i>Pad Shear - 1-way (kips)</i>	1039.95	315.55	28.9%	Pass
<i>Pad Shear - 2-way (Comp) (ksi)</i>	0.190	0.045	22.4%	Pass
<i>Flexural 2-way (Comp) (kip*ft)</i>	5714.52	3784.84	63.1%	Pass

Pier Properties		
Pier Shape:	Square	
Pier Diameter, $dpier$ :	9	ft
Ext. Above Grade, $E$ :	1	ft
Pier Rebar Size, $Sc$ :	8	
Pier Rebar Quantity, $mc$ :	54	
Pier Tie/Spiral Size, $St$ :	4	
Pier Tie/Spiral Quantity, $mt$ :	10	
Pier Reinforcement Type:	Tie	
Pier Clear Cover, $cc_{pier}$ :	3	in

\*Rating per TIA-222-H Section 15.5

Structural Rating*:	64.5%
Soil Rating*:	62.7%

Pad Properties		
Depth, $D$ :	7	ft
Pad Width, $W_1$ :	29	ft
Pad Thickness, $T$ :	3	ft
Pad Rebar Size (Top dir.2), $Sp_{top2}$ :	8	
Pad Rebar Quantity (Top dir. 2), $mp_{top2}$ :	30	
Pad Rebar Size (Bottom dir. 2), $Sp_2$ :	8	
Pad Rebar Quantity (Bottom dir. 2), $mp_2$ :	55	
Pad Clear Cover, $cc_{pad}$ :	3	in

Material Properties		
Rebar Grade, $F_y$ :	60	ksi
Concrete Compressive Strength, $F'_c$ :	4	ksi
Dry Concrete Density, $\delta_c$ :	150	pcf

Soil Properties		
Total Soil Unit Weight, $\gamma$ :	120	pcf
Ultimate Gross Bearing, $Q_{ult}$ :	12,000	ksf
Cohesion, $C_u$ :	0.000	ksf
Friction Angle, $\phi$ :	30	degrees
SPT Blow Count, $N_{blows}$ :	60	
Base Friction, $\mu$ :	0.6	
Neglected Depth, $N$ :	3.50	ft
Foundation Bearing on Rock?	No	
Groundwater Depth, $gw$ :	15	ft

<--Toggle between Gross and Net

# ASCE 7 Hazards Report

**Address:**  
No Address at This  
Location

**Standard:** ASCE/SEI 7-10  
**Risk Category:** II  
**Soil Class:** D - Stiff Soil

**Elevation:** 322.51 ft (NAVD 88)  
**Latitude:** 41.273281  
**Longitude:** -73.213106



## Wind

### Results:

Wind Speed:	121 Vmph	<b>125 Vmph required by Jurisdiction</b>
10-year MRI	76 Vmph	
25-year MRI	86 Vmph	
50-year MRI	92 Vmph	
100-year MRI	99 Vmph	

**Data Source:** ASCE/SEI 7-10 Fig. 26.5-1A and Figs. CC-1–CC-4, and Section 26.5.2, incorporating errata of March 12, 2014

Value provided is 3-second gust wind speeds at 33 ft above ground for Exposure C Category, based on linear interpolation between contours. Wind speeds are interpolated in accordance with the 7-10 Standard. Wind speeds correspond to approximately a 7% probability of exceedance in 50 years (annual exceedance probability = 0.00143, MRI = 700 years).



Site is in a hurricane-prone region as defined in ASCE/SEI 7-10 Section 26.2. Glazed openings need not be protected against wind-borne debris.

**Site Soil Class:** D - Stiff Soil

**Results:**

$S_s$ :	0.207	$S_{DS}$ :	0.221
$S_1$ :	0.065	$S_{D1}$ :	0.104
$F_a$ :	1.6	$T_L$ :	6
$F_v$ :	2.4	PGA :	0.112
$S_{MS}$ :	0.331	PGA <sub>M</sub> :	0.176
$S_{M1}$ :	0.156	F <sub>PGA</sub> :	1.577
		$I_e$ :	1

**Seismic Design Category** B



**Data Accessed:**

Wed Apr 21 2021

**Date Source:**

USGS Seismic Design Maps based on ASCE/SEI 7-10, incorporating Supplement 1 and errata of March 31, 2013, and ASCE/SEI 7-10 Table 1.5-2. Additional data for site-specific ground motion procedures in accordance with ASCE/SEI 7-10 Ch. 21 are available from USGS.

## Ice

---

### Results:

Ice Thickness: 0.75 in.  
Concurrent Temperature: 15 F  
Gust Speed: 50 mph

**Data Source:** Standard ASCE/SEI 7-10, Figs. 10-2 through 10-8

**Date Accessed:** Wed Apr 21 2021

Ice thicknesses on structures in exposed locations at elevations higher than the surrounding terrain and in valleys and gorges may exceed the mapped values.

Values provided are equivalent radial ice thicknesses due to freezing rain with concurrent 3-second gust speeds, for a 50-year mean recurrence interval, and temperatures concurrent with ice thicknesses due to freezing rain. Thicknesses for ice accretions caused by other sources shall be obtained from local meteorological studies. Ice thicknesses in exposed locations at elevations higher than the surrounding terrain and in valleys and gorges may exceed the mapped values.

---

The ASCE 7 Hazard Tool is provided for your convenience, for informational purposes only, and is provided "as is" and without warranties of any kind. The location data included herein has been obtained from information developed, produced, and maintained by third party providers; or has been extrapolated from maps incorporated in the ASCE 7 standard. While ASCE has made every effort to use data obtained from reliable sources or methodologies, ASCE does not make any representations or warranties as to the accuracy, completeness, reliability, currency, or quality of any data provided herein. Any third-party links provided by this Tool should not be construed as an endorsement, affiliation, relationship, or sponsorship of such third-party content by or from ASCE.

ASCE does not intend, nor should anyone interpret, the results provided by this Tool to replace the sound judgment of a competent professional, having knowledge and experience in the appropriate field(s) of practice, nor to substitute for the standard of care required of such professionals in interpreting and applying the contents of this Tool or the ASCE 7 standard.

In using this Tool, you expressly assume all risks associated with your use. Under no circumstances shall ASCE or its officers, directors, employees, members, affiliates, or agents be liable to you or any other person for any direct, indirect, special, incidental, or consequential damages arising from or related to your use of, or reliance on, the Tool or any information obtained therein. To the fullest extent permitted by law, you agree to release and hold harmless ASCE from any and all liability of any nature arising out of or resulting from any use of data provided by the ASCE 7 Hazard Tool.

# Exhibit E

## **Mount Analysis**

Date: **July 28, 2021**

Darcy Tarr  
Crown Castle  
3530 Toringdon Way, Suite 300  
Charlotte, NC 28277  
(704) 405-6589



Trylon  
1825 W. Walnut Hill Lane,  
Suite 302  
Irving, TX 75038  
214-930-1730

**Subject:** **Mount Replacement Analysis Report**

**Carrier Designation:** **Dish Network Dish 5G**  
**Carrier Site Number:** NJJER01096A  
**Carrier Site Name:** CT-CCI-T-881535

**Crown Castle Designation:** **Crown Castle BU Number:** 881535  
**Crown Castle Site Name:** Trumbull Tower  
**Crown Castle JDE Job Number:** 640206  
**Crown Castle Order Number:** 548692 Rev. 1

**Engineering Firm Designation:** **Trylon Report Designation:** 188625

**Site Data:** **425 Indian Ledge Park Rd, Trumbull, Fairfield County, CT, 06611**  
**Latitude 41°16'23.81" Longitude -73°12'47.18"**

**Structure Information:** **Tower Height & Type:** **195.0 ft Monopole**  
**Mount Elevation:** **175.0 ft**  
**Mount Type:** **8.0 ft Platform**

Dear Darcy Tarr,

Trylon is pleased to submit this **"Mount Replacement Analysis Report"** to determine the structural integrity of Dish Network's antenna mounting system with the proposed appurtenance and equipment addition on the abovementioned supporting tower structure. Analysis of the existing supporting tower structure is to be completed by others and therefore is not part of this analysis. Analysis of the antenna mounting system as a tie-off point for fall protection or rigging is not part of this document.

The purpose of the analysis is to determine acceptability of the mount stress level. Based on our analysis we have determined the mount stress level to be:

**Platform**


**Sufficient\***

**\*Sufficient upon completion of the changes listed in the 'Recommendations' section of this report.**

This analysis utilizes an ultimate 3-second gust wind speed of 125 mph as required by the 2018 Connecticut State Building Code. Applicable Standard references and design criteria are listed in Section 2 - Analysis Criteria.

Mount analysis prepared by: Aura Baltoiu

Respectfully Submitted by:  
Cliff Abernathy, P.E.



Cliff Abernathy

Digitally signed by Cliff  
Abernathy  
Date: 2021.07.28 16:33:35  
-04'00'

## TABLE OF CONTENTS

### 1) INTRODUCTION

### 2) ANALYSIS CRITERIA

Table 1 - Proposed Equipment Configuration

### 3) ANALYSIS PROCEDURE

Table 2 - Documents Provided

3.1) Analysis Method

3.2) Assumptions

### 4) ANALYSIS RESULTS

Table 3 - Mount Component Stresses vs. Capacity

4.1) Recommendations

### 5) APPENDIX A

Wire Frame and Rendered Models

### 6) APPENDIX B

Software Input Calculations

### 7) APPENDIX C

Software Analysis Output

### 8) APPENDIX D

Additional Calculations

### 9) APPENDIX E

Supplemental Drawings



## 1) INTRODUCTION

This is a proposed 3 sector 8.0 ft Platform, designed by Commscope.

## 2) ANALYSIS CRITERIA

<b>Building Code:</b>	2015 IBC
<b>TIA-222 Revision:</b>	TIA-222-H
<b>Risk Category:</b>	II
<b>Ultimate Wind Speed:</b>	125 mph
<b>Exposure Category:</b>	B
<b>Topographic Factor at Base:</b>	1.00
<b>Topographic Factor at Mount:</b>	1.00
<b>Ice Thickness:</b>	1.5 in
<b>Wind Speed with Ice:</b>	50 mph
<b>Seismic S<sub>s</sub>:</b>	0.207
<b>Seismic S<sub>1</sub>:</b>	0.065
<b>Live Loading Wind Speed:</b>	30 mph
<b>Man Live Load at Mid/End-Points:</b>	250 lb
<b>Man Live Load at Mount Pipes:</b>	500 lb

**Table 1 - Proposed Equipment Configuration**

Mount Centerline (ft)	Antenna Centerline (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Mount / Modification Details
175.0	175.0	3	JMA WIRELESS	MX08FRO665-21	8.0 ft Platform [Commscope, MC-PK8-C]
		3	FUJITSU	TA08025-B604	
		3	FUJITSU	TA08025-B605	
		1	RAYCAP	RDIDC-9181-PF-48	

## 3) ANALYSIS PROCEDURE

**Table 2 - Documents Provided**

Document	Remarks	Reference	Source
Crown Application	Dish Network Application	548692, Rev.1	CCI Sites
Mount Manufacturer Drawings	Commscope	MC-PK8-C	Trylon

### 3.1) Analysis Method

RISA-3D (Version 17.0.4), a commercially available analysis software package, was used to create a three-dimensional model of the antenna mounting system and calculate member stresses for various loading cases.

A tool internally developed, using Microsoft Excel, by Trylon was used to calculate wind loading on all appurtenances, dishes, and mount members for various load cases. Selected output from the analysis is included in Appendix B.

This analysis was performed in accordance with Crown Castle's ENG-SOW-10208 *Tower Mount Analysis* (Revision B).

**3.2) Assumptions**

- 1) The antenna mounting system was properly fabricated, installed and maintained in good condition in accordance with its original design and manufacturer's specifications.
- 2) The configuration of antennas, mounts, and other appurtenances are as specified in Table 1 and the referenced drawings.
- 3) All member connections are assumed to have been designed to meet or exceed the load carrying capacity of the connected member unless otherwise specified in this report.
- 4) The analysis will be required to be revised if the existing conditions in the field differ from those shown in the above-referenced documents or assumed in this analysis. No allowance was made for any damaged, missing, or rusted members.
- 5) Prior structural modifications to the tower mounting system are assumed to be installed as shown per available data.
- 6) Steel grades have been assumed as follows, unless noted otherwise:
 

Channel, Solid Round, Angle, Plate	ASTM A36 (GR 36)
HSS (Rectangular)	ASTM A500 (GR B-46)
Pipe	ASTM A53 (GR 35)
Connection Bolts	ASTM A325

This analysis may be affected if any assumptions are not valid or have been made in error. Tylon should be notified to determine the effect on the structural integrity of the antenna mounting system.

**4) ANALYSIS RESULTS**

**Table 3 - Mount Component Stresses vs. Capacity (Platform, All Sectors)**

Notes	Component	Critical Member	Centerline (ft)	% Capacity	Pass / Fail
1,2	Mount Pipe(s)	MP1	175.0	32.9	Pass
	Horizontal(s)	H1		10.1	Pass
	Standoff(s)	SA2		48.3	Pass
	Bracing(s)	PB2		36.7	Pass
	Handrail(s)	M19		14.0	Pass
	Corner Angle(s)	CP2		5.33	Pass
	Plate(s)	CP5		22.6	Pass
	Mount Connection(s)	-		19.4	Pass

<b>Structure Rating (max from all components) =</b>	<b>48.3%</b>
---	--------------

Notes:

- 1) See additional documentation in "Appendix C - Software Analysis Output" for calculations supporting the % capacity consumed.
- 2) Rating per TIA-222-H, Section 15.5



#### 4.1) Recommendations

The mount has sufficient capacity to carry the proposed loading configuration. In order for the results of the analysis to be considered valid, the proposed mount listed below must be installed.

1. Commscope, MC-PK8-C.



No structural modifications are required at this time, provided that the above-listed changes are implemented.

**APPENDIX A**  
**WIRE FRAME AND RENDERED MODELS**



Envelope Only Solution

Trylon	881535	SK - 1
AB		July 27, 2021 at 10:34 AM
188625		881535.r3d



Envelope Only Solution

Trylon

AB

188625

881535

SK - 2

July 27, 2021 at 10:34 AM

881535.r3d



**APPENDIX B**  
**SOFTWARE INPUT CALCULATIONS**

# ASCE 7 Hazards Report

**Address:**  
No Address at This  
Location

**Standard:** ASCE/SEI 7-10  
**Risk Category:** II  
**Soil Class:** D - Stiff Soil

**Elevation:** 322.51 ft (NAVD 88)  
**Latitude:** 41.273281  
**Longitude:** -73.213106



## Ice

### Results:

Ice Thickness: 0.75 in.  
Concurrent Temperature: 15 F  
Gust Speed: 50 mph

**Data Source:** Standard ASCE/SEI 7-10, Figs. 10-2 through 10-8

**Date Accessed:** Tue Jul 27 2021

Ice thicknesses on structures in exposed locations at elevations higher than the surrounding terrain and in valleys and gorges may exceed the mapped values.

Values provided are equivalent radial ice thicknesses due to freezing rain with concurrent 3-second gust speeds, for a 50-year mean recurrence interval, and temperatures concurrent with ice thicknesses due to freezing rain. Thicknesses for ice accretions caused by other sources shall be obtained from local meteorological studies. Ice thicknesses in exposed locations at elevations higher than the surrounding terrain and in valleys and gorges may exceed the mapped values.



The ASCE 7 Hazard Tool is provided for your convenience, for informational purposes only, and is provided “as is” and without warranties of any kind. The location data included herein has been obtained from information developed, produced, and maintained by third party providers; or has been extrapolated from maps incorporated in the ASCE 7 standard. While ASCE has made every effort to use data obtained from reliable sources or methodologies, ASCE does not make any representations or warranties as to the accuracy, completeness, reliability, currency, or quality of any data provided herein. Any third-party links provided by this Tool should not be construed as an endorsement, affiliation, relationship, or sponsorship of such third-party content by or from ASCE.

ASCE does not intend, nor should anyone interpret, the results provided by this Tool to replace the sound judgment of a competent professional, having knowledge and experience in the appropriate field(s) of practice, nor to substitute for the standard of care required of such professionals in interpreting and applying the contents of this Tool or the ASCE 7 standard.

In using this Tool, you expressly assume all risks associated with your use. Under no circumstances shall ASCE or its officers, directors, employees, members, affiliates, or agents be liable to you or any other person for any direct, indirect, special, incidental, or consequential damages arising from or related to your use of, or reliance on, the Tool or any information obtained therein. To the fullest extent permitted by law, you agree to release and hold harmless ASCE from any and all liability of any nature arising out of or resulting from any use of data provided by the ASCE 7 Hazard Tool.



# Trylon

1825 W. Walnut Hill Lane Suite 120  
Irving, TX 75038

## TIA LOAD CALCULATOR 2.0

PROJECT DATA	
Job Code:	188625
Carrier Site ID:	NJJER01096A
Carrier Site Name:	CT-CCI-T-881535

CODES AND STANDARDS	
Building Code:	2015 IBC
Local Building Code:	2018 CSBC
Design Standard:	TIA-222-H

STRUCTURE DETAILS		
Mount Type:	Platform	--
Mount Elevation:	175.0	ft.
Number of Sectors:	3	--
Structure Type:	Monopole	--
Structure Height:	195.0	ft.

ANALYSIS CRITERIA		
Structure Risk Category:	II	--
Exposure Category:	B	--
Site Class:	D - Stiff Soil	--
Ground Elevation:	322.51	ft.

TOPOGRAPHIC DATA		
Topographic Category:	1.00	--
Topographic Feature:	N/A	--
Crest Point Elevation:	0.00	ft.
Base Point Elevation:	0.00	ft.
Crest to Mid-Height (L/2):	0.00	ft.
Distance from Crest (x):	0.00	ft.
Base Topo Factor ( $K_{zt}$ ):	1.00	--
Mount Topo Factor ( $K_{zt}$ ):	1.00	--

WIND PARAMETERS		
Design Wind Speed:	125	mph
Wind Escalation Factor ( $K_s$ ):	1.00	--
Velocity Coefficient ( $K_z$ ):	1.16	--
Directionality Factor ( $K_d$ ):	0.95	--
Gust Effect Factor ( $G_h$ ):	1.00	--
Shielding Factor ( $K_a$ ):	0.90	--
Velocity Pressure ( $q_z$ ):	43.55	psf

ICE PARAMETERS		
Design Ice Wind Speed:	50	mph
Design Ice Thickness ( $t_i$ ):	1.50	in
Importance Factor ( $I_i$ ):	1.00	--
Ice Velocity Pressure ( $q_{zi}$ ):	43.55	psf
Mount Ice Thickness ( $t_{iz}$ ):	1.77	in

WIND STRUCTURE CALCULATIONS		
Flat Member Pressure:	78.39	psf
Round Member Pressure:	47.04	psf
Ice Wind Pressure:	7.67	psf

SEISMIC PARAMETERS		
Importance Factor ( $I_e$ ):	1.00	--
Short Period Accel. ( $S_s$ ):	0.207	g
1 Second Accel. ( $S_1$ ):	0.065	g
Short Period Des. ( $S_{DS}$ ):	0.22	g
1 Second Des. ( $S_{D1}$ ):	0.10	g
Short Period Coeff. ( $F_a$ ):	1.60	--
1 Second Coeff. ( $F_v$ ):	2.40	--
Response Coefficient ( $C_s$ ):	0.11	--
Amplification Factor ( $A_S$ ):	1.20	--

## LOAD COMBINATIONS [LRFD]

#	Description
1	1.4DL
2	1.2DL + 1WL 0 AZI
3	1.2DL + 1WL 30 AZI
4	1.2DL + 1WL 45 AZI
5	1.2DL + 1WL 60 AZI
6	1.2DL + 1WL 90 AZI
7	1.2DL + 1WL 120 AZI
8	1.2DL + 1WL 135 AZI
9	1.2DL + 1WL 150 AZI
10	1.2DL + 1WL 180 AZI
11	1.2DL + 1WL 210 AZI
12	1.2DL + 1WL 225 AZI
13	1.2DL + 1WL 240 AZI
14	1.2DL + 1WL 270 AZI
15	1.2DL + 1WL 300 AZI
16	1.2DL + 1WL 315 AZI
17	1.2DL + 1WL 330 AZI
18	0.9DL + 1WL 0 AZI
19	0.9DL + 1WL 30 AZI
20	0.9DL + 1WL 45 AZI
21	0.9DL + 1WL 60 AZI
22	0.9DL + 1WL 90 AZI
23	0.9DL + 1WL 120 AZI
24	0.9DL + 1WL 135 AZI
25	0.9DL + 1WL 150 AZI
26	0.9DL + 1WL 180 AZI
27	0.9DL + 1WL 210 AZI
28	0.9DL + 1WL 225 AZI
29	0.9DL + 1WL 240 AZI
30	0.9DL + 1WL 270 AZI
31	0.9DL + 1WL 300 AZI
32	0.9DL + 1WL 315 AZI
33	0.9DL + 1WL 330 AZI
34	1.2DL + 1DLi + 1WLi 0 AZI
35	1.2DL + 1DLi + 1WLi 30 AZI
36	1.2DL + 1DLi + 1WLi 45 AZI
37	1.2DL + 1DLi + 1WLi 60 AZI
38	1.2DL + 1DLi + 1WLi 90 AZI
39	1.2DL + 1DLi + 1WLi 120 AZI
40	1.2DL + 1DLi + 1WLi 135 AZI
41	1.2DL + 1DLi + 1WLi 150 AZI

#	Description
42	1.2DL + 1DLi + 1WLi 180 AZI
43	1.2DL + 1DLi + 1WLi 210 AZI
44	1.2DL + 1DLi + 1WLi 225 AZI
45	1.2DL + 1DLi + 1WLi 240 AZI
46	1.2DL + 1DLi + 1WLi 270 AZI
47	1.2DL + 1DLi + 1WLi 300 AZI
48	1.2DL + 1DLi + 1WLi 315 AZI
49	1.2DL + 1DLi + 1WLi 330 AZI
50	(1.2+0.2Sds) + 1.0E 0 AZI
51	(1.2+0.2Sds) + 1.0E 30 AZI
52	(1.2+0.2Sds) + 1.0E 45 AZI
53	(1.2+0.2Sds) + 1.0E 60 AZI
54	(1.2+0.2Sds) + 1.0E 90 AZI
55	(1.2+0.2Sds) + 1.0E 120 AZI
56	(1.2+0.2Sds) + 1.0E 135 AZI
57	(1.2+0.2Sds) + 1.0E 150 AZI
58	(1.2+0.2Sds) + 1.0E 180 AZI
59	(1.2+0.2Sds) + 1.0E 210 AZI
60	(1.2+0.2Sds) + 1.0E 225 AZI
61	(1.2+0.2Sds) + 1.0E 240 AZI
62	(1.2+0.2Sds) + 1.0E 270 AZI
63	(1.2+0.2Sds) + 1.0E 300 AZI
64	(1.2+0.2Sds) + 1.0E 315 AZI
65	(1.2+0.2Sds) + 1.0E 330 AZI
66	(0.9-0.2Sds) + 1.0E 0 AZI
67	(0.9-0.2Sds) + 1.0E 30 AZI
68	(0.9-0.2Sds) + 1.0E 45 AZI
69	(0.9-0.2Sds) + 1.0E 60 AZI
70	(0.9-0.2Sds) + 1.0E 90 AZI
71	(0.9-0.2Sds) + 1.0E 120 AZI
72	(0.9-0.2Sds) + 1.0E 135 AZI
73	(0.9-0.2Sds) + 1.0E 150 AZI
74	(0.9-0.2Sds) + 1.0E 180 AZI
75	(0.9-0.2Sds) + 1.0E 210 AZI
76	(0.9-0.2Sds) + 1.0E 225 AZI
77	(0.9-0.2Sds) + 1.0E 240 AZI
78	(0.9-0.2Sds) + 1.0E 270 AZI
79	(0.9-0.2Sds) + 1.0E 300 AZI
80	(0.9-0.2Sds) + 1.0E 315 AZI
81	(0.9-0.2Sds) + 1.0E 330 AZI
82-88	1.2D + 1.5 Lv1

#	Description
89	1.2D + 1.5Lm + 1.0Wm 0 AZI - MP1
90	1.2D + 1.5Lm + 1.0Wm 30 AZI - MP1
91	1.2D + 1.5Lm + 1.0Wm 45 AZI - MP1
92	1.2D + 1.5Lm + 1.0Wm 60 AZI - MP1
93	1.2D + 1.5Lm + 1.0Wm 90 AZI - MP1
94	1.2D + 1.5Lm + 1.0Wm 120 AZI - MP1
95	1.2D + 1.5Lm + 1.0Wm 135 AZI - MP1
96	1.2D + 1.5Lm + 1.0Wm 150 AZI - MP1
97	1.2D + 1.5Lm + 1.0Wm 180 AZI - MP1
98	1.2D + 1.5Lm + 1.0Wm 210 AZI - MP1
99	1.2D + 1.5Lm + 1.0Wm 225 AZI - MP1
100	1.2D + 1.5Lm + 1.0Wm 240 AZI - MP1
101	1.2D + 1.5Lm + 1.0Wm 270 AZI - MP1
102	1.2D + 1.5Lm + 1.0Wm 300 AZI - MP1
103	1.2D + 1.5Lm + 1.0Wm 315 AZI - MP1
104	1.2D + 1.5Lm + 1.0Wm 330 AZI - MP1
105	1.2D + 1.5Lm + 1.0Wm 0 AZI - MP2
106	1.2D + 1.5Lm + 1.0Wm 30 AZI - MP2
107	1.2D + 1.5Lm + 1.0Wm 45 AZI - MP2
108	1.2D + 1.5Lm + 1.0Wm 60 AZI - MP2
109	1.2D + 1.5Lm + 1.0Wm 90 AZI - MP2
110	1.2D + 1.5Lm + 1.0Wm 120 AZI - MP2
111	1.2D + 1.5Lm + 1.0Wm 135 AZI - MP2
112	1.2D + 1.5Lm + 1.0Wm 150 AZI - MP2
113	1.2D + 1.5Lm + 1.0Wm 180 AZI - MP2
114	1.2D + 1.5Lm + 1.0Wm 210 AZI - MP2
115	1.2D + 1.5Lm + 1.0Wm 225 AZI - MP2
116	1.2D + 1.5Lm + 1.0Wm 240 AZI - MP2
117	1.2D + 1.5Lm + 1.0Wm 270 AZI - MP2
118	1.2D + 1.5Lm + 1.0Wm 300 AZI - MP2
119	1.2D + 1.5Lm + 1.0Wm 315 AZI - MP2
120	1.2D + 1.5Lm + 1.0Wm 330 AZI - MP2

#	Description
121	1.2D + 1.5Lm + 1.0Wm 0 AZI - MP3
122	1.2D + 1.5Lm + 1.0Wm 30 AZI - MP3
123	1.2D + 1.5Lm + 1.0Wm 45 AZI - MP3
124	1.2D + 1.5Lm + 1.0Wm 60 AZI - MP3
125	1.2D + 1.5Lm + 1.0Wm 90 AZI - MP3
126	1.2D + 1.5Lm + 1.0Wm 120 AZI - MP3
127	1.2D + 1.5Lm + 1.0Wm 135 AZI - MP3
128	1.2D + 1.5Lm + 1.0Wm 150 AZI - MP3
129	1.2D + 1.5Lm + 1.0Wm 180 AZI - MP3
130	1.2D + 1.5Lm + 1.0Wm 210 AZI - MP3
131	1.2D + 1.5Lm + 1.0Wm 225 AZI - MP3
132	1.2D + 1.5Lm + 1.0Wm 240 AZI - MP3
133	1.2D + 1.5Lm + 1.0Wm 270 AZI - MP3
134	1.2D + 1.5Lm + 1.0Wm 300 AZI - MP3
135	1.2D + 1.5Lm + 1.0Wm 315 AZI - MP3
136	1.2D + 1.5Lm + 1.0Wm 330 AZI - MP3
137	1.2D + 1.5Lm + 1.0Wm 0 AZI - MP4
138	1.2D + 1.5Lm + 1.0Wm 30 AZI - MP4
139	1.2D + 1.5Lm + 1.0Wm 45 AZI - MP4
140	1.2D + 1.5Lm + 1.0Wm 60 AZI - MP4
141	1.2D + 1.5Lm + 1.0Wm 90 AZI - MP4
142	1.2D + 1.5Lm + 1.0Wm 120 AZI - MP4
143	1.2D + 1.5Lm + 1.0Wm 135 AZI - MP4
144	1.2D + 1.5Lm + 1.0Wm 150 AZI - MP4
145	1.2D + 1.5Lm + 1.0Wm 180 AZI - MP4
146	1.2D + 1.5Lm + 1.0Wm 210 AZI - MP4
147	1.2D + 1.5Lm + 1.0Wm 225 AZI - MP4
148	1.2D + 1.5Lm + 1.0Wm 240 AZI - MP4
149	1.2D + 1.5Lm + 1.0Wm 270 AZI - MP4
150	1.2D + 1.5Lm + 1.0Wm 300 AZI - MP4
151	1.2D + 1.5Lm + 1.0Wm 315 AZI - MP4
152	1.2D + 1.5Lm + 1.0Wm 330 AZI - MP4

\*This page shows an example of maintenance loads for (4) pipes, the number of mount pipe LCs may vary per site











## EQUIPMENT LATERAL WIND FORCE CALCULATIONS [CONT.]

<i>Appurtenance Name</i>	<i>Qty.</i>	<i>--</i>	<i>0° 180°</i>	<i>30° 210°</i>	<i>60° 240°</i>	<i>90° 270°</i>	<i>120° 300°</i>	<i>150° 330°</i>
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						
		No Ice						
--	--	w/ Ice						



**APPENDIX C**  
**SOFTWARE ANALYSIS OUTPUT**

**(Global) Model Settings**

Display Sections for Member Calcs	5
Max Internal Sections for Member Calcs	97
Include Shear Deformation?	Yes
Increase Nailing Capacity for Wind?	Yes
Include Warping?	Yes
Trans Load Btwn Intersecting Wood Wall?	Yes
Area Load Mesh (in^2)	144
Merge Tolerance (in)	.12
P-Delta Analysis Tolerance	0.50%
Include P-Delta for Walls?	Yes
Automatically Iterate Stiffness for Walls?	Yes
Max Iterations for Wall Stiffness	3
Gravity Acceleration (in/sec^2)	386.4
Wall Mesh Size (in)	24
Eigensolution Convergence Tol. (1.E-)	4
Vertical Axis	Z
Global Member Orientation Plane	XY
Static Solver	Sparse Accelerated
Dynamic Solver	Accelerated Solver

Hot Rolled Steel Code	AISC 15th(360-16): LRFD
Adjust Stiffness?	Yes(Iterative)
RISAC Connection Code	AISC 15th(360-16): LRFD
Cold Formed Steel Code	AISI S100-12: LRFD
Wood Code	AWC NDS-15: ASD
Wood Temperature	< 100F
Concrete Code	ACI 318-14
Masonry Code	ACI 530-13: Strength
Aluminum Code	AA ADM 1-10: LRFD - Building
Stainless Steel Code	AISC 14th(360-10): LRFD
Adjust Stiffness?	Yes(Iterative)

Number of Shear Regions	4
Region Spacing Increment (in)	4
Biaxial Column Method	Exact Integration
Parame Beta Factor (PCA)	.65
Concrete Stress Block	Rectangular
Use Cracked Sections?	Yes
Use Cracked Sections Slab?	Yes
Bad Framing Warnings?	No
Unused Force Warnings?	Yes
Min 1 Bar Diam. Spacing?	No
Concrete Rebar Set	REBAR_SET_ASTMA615
Min % Steel for Column	1
Max % Steel for Column	8

**(Global) Model Settings, Continued**

Seismic Code	ASCE 7-10
Seismic Base Elevation (in)	Not Entered
Add Base Weight?	Yes
Ct X	.02
Ct Z	.02
T X (sec)	Not Entered
T Z (sec)	Not Entered
R X	3
R Z	3
Ct Exp. X	.75
Ct Exp. Z	.75
SD1	1
SDS	1
S1	1
TL (sec)	5
Risk Cat	I or II
Drift Cat	Other
Om Z	1
Om X	1
Cd Z	1
Cd X	1
Rho Z	1
Rho X	1

**Hot Rolled Steel Properties**

	Label	E [ksi]	G [ksi]	Nu	Therm (/1E5 F)	Density[k/ft^3]	Yield[psi]	Ry	Fu[psi]	Rt
1	A992	29000	11154	.3	.65	.49	50000	1.1	65000	1.1
2	A36 Gr.36	29000	11154	.3	.65	.49	36000	1.5	58000	1.2
3	A572 Gr.50	29000	11154	.3	.65	.49	50000	1.1	65000	1.1
4	A500 Gr.B RND	29000	11154	.3	.65	.527	42000	1.4	58000	1.3
5	A500 Gr.B Rect	29000	11154	.3	.65	.527	46000	1.4	58000	1.3
6	A53 Gr.B	29000	11154	.3	.65	.49	35000	1.6	60000	1.2
7	A1085	29000	11154	.3	.65	.49	50000	1.4	65000	1.3

**Cold Formed Steel Properties**

	Label	E [ksi]	G [ksi]	Nu	Therm (/1E5 F)	Density[k/ft^3]	Yield[psi]	Fu[psi]
1	A653 S S Gr33	29500	11346	.3	.65	.49	33000	45000
2	A653 S S Gr50/1	29500	11346	.3	.65	.49	50000	65000

**Hot Rolled Steel Section Sets**

	Label	Shape	Type	Design List	Material	Design ...	A [in2]	Iyy [in4]	Izz [in4]	J [in4]
1	Plates	6.5"x0.37" Plate	Beam	RECT	A53 Gr.B	Typical	2.405	.027	8.468	.106
2	Grating Bracing	L2x2x3	Beam	Single Angle	A36 Gr.36	Typical	.722	.271	.271	.009
3	Standoffs	PIPE 3.5	Beam	Pipe	A53 Gr.B	Typical	2.5	4.52	4.52	9.04
4	Standoff Bracing	C3X5	Beam	Channel	A36 Gr.36	Typical	1.47	.241	1.85	.043
5	Handrails	PIPE 2.0	Beam	Pipe	A53 Gr.B	Typical	1.02	.627	.627	1.25
6	Handrail Corners	6.6x4.46x0.25	Beam	Single Angle	A36 Gr.36	Typical	2.702	4.759	12.473	.055
7	Horizontals	PIPE 3.5	Beam	Pipe	A53 Gr.B	Typical	2.5	4.52	4.52	9.04



Company : Trylon  
 Designer : AB  
 Job Number : 188625  
 Model Name : 881535

July 27, 2021  
 3:35 PM  
 Checked By: CA

### Hot Rolled Steel Section Sets (Continued)

	Label	Shape	Type	Design List	Material	Design ...	A [in2]	Iyy [in4]	Izz [in4]	J [in4]
8	Mount Pipes	PIPE 2.0	Beam	Pipe	A53 Gr.B	Typical	1.02	.627	.627	1.25

### Cold Formed Steel Section Sets

	Label	Shape	Type	Design List	Material	Design R...	A [in2]	Iyy [in4]	Izz [in4]	J [in4]
1	CF1A	8CU1.25X057	Beam	None	A653 SS Gr33	Typical	.581	.057	4.41	.00063

### Joint Boundary Conditions

	Joint Label	X [k/in]	Y [k/in]	Z [k/in]	X Rot.[k-ft/rad]	Y Rot.[k-ft/rad]	Z Rot.[k-ft/rad]
1	N25	Reaction	Reaction	Reaction	Reaction	Reaction	Reaction
2	N1	Reaction	Reaction	Reaction	Reaction	Reaction	Reaction
3	N13	Reaction	Reaction	Reaction	Reaction	Reaction	Reaction

### Basic Load Cases

	BLC Description	Category	X Gravity	Y Gravity	Z Gravity	Joint	Point	Distribu...	Area(M...	Surface...
1	Self Weight	DL			-1		13		3	
2	Structure Wind X	WLX						33		
3	Structure Wind Y	WLY						33		
4	Wind Load 0 AZI	WLX					13			
5	Wind Load 30 AZI	None					26			
6	Wind Load 45 AZI	None					26			
7	Wind Load 60 AZI	None					26			
8	Wind Load 90 AZI	WLY					13			
9	Wind Load 120 AZI	None					26			
10	Wind Load 135 AZI	None					26			
11	Wind Load 150 AZI	None					26			
12	Ice Weight	OL1					13	33	3	
13	Structure Ice Wind X	OL2						33		
14	Structure Ice Wind Y	OL3						33		
15	Ice Wind Load 0 AZI	OL2					13			
16	Ice Wind Load 30 AZI	None					26			
17	Ice Wind Load 45 AZI	None					26			
18	Ice Wind Load 60 AZI	None					26			
19	Ice Wind Load 90 AZI	OL3					13			
20	Ice Wind Load 120 AZI	None					26			
21	Ice Wind Load 135 AZI	None					26			
22	Ice Wind Load 150 AZI	None					26			
23	Seismic Load X	ELX	-.132				13			
24	Seismic Load Y	ELY		-.132			13			
25	Live Load 1 (Lv)	LL					1			
26	Live Load 2 (Lv)	LL					1			
27	Live Load 3 (Lv)	LL					1			
28	Live Load 4 (Lv)	LL					1			
29	Live Load 5 (Lv)	LL					1			
30	Live Load 6 (Lv)	LL					1			
31	Maintenance Load 1 (Lm)	None					1			
32	Maintenance Load 2 (Lm)	None					1			
33	Maintenance Load 3 (Lm)	None					1			



Company : Trylon  
 Designer : AB  
 Job Number : 188625  
 Model Name : 881535

July 27, 2021  
 3:35 PM  
 Checked By: CA

**Basic Load Cases (Continued)**

	BLC Description	Category	X Gravity	Y Gravity	Z Gravity	Joint	Point	Distribu...	Area(M...	Surface...
34	Maintenance Load 4 (Lm)	None					1			
35	Maintenance Load 5 (Lm)	None					1			
36	Maintenance Load 6 (Lm)	None					1			
37	Maintenance Load 7 (Lm)	None					1			
38	Maintenance Load 8 (Lm)	None					1			
39	Maintenance Load 9 (Lm)	None					1			
40	Maintenance Load 7 (Lm)	None								
41	Maintenance Load 8 (Lm)	None								
42	Maintenance Load 9 (Lm)	None								
43	BLC 1 Transient Area Loads	None						9		
44	BLC 12 Transient Area Loads	None						9		

**Load Combinations**

	Description	Solve	PD...	SR...	B...	Factor	BLC	Factor	B...	Fa...	B...	Fa...	BLC	Fa...	B...	Fa...	B...	Fa...	B...	Fa...	
1	1.4DL	Yes	Y	DL	1.4																
2	1.2DL + 1WL 0 AZI	Yes	Y	DL	1.2	2	1	3		4	1										
3	1.2DL + 1WL 30 AZI	Yes	Y	DL	1.2	2	.866	3	.5	5	1										
4	1.2DL + 1WL 45 AZI	Yes	Y	DL	1.2	2	.707	3	.707	6	1										
5	1.2DL + 1WL 60 AZI	Yes	Y	DL	1.2	2	.5	3	.866	7	1										
6	1.2DL + 1WL 90 AZI	Yes	Y	DL	1.2	2		3	1	8	1										
7	1.2DL + 1WL 120 AZI	Yes	Y	DL	1.2	2	-.5	3	.866	9	1										
8	1.2DL + 1WL 135 AZI	Yes	Y	DL	1.2	2	-.707	3	.707	10	1										
9	1.2DL + 1WL 150 AZI	Yes	Y	DL	1.2	2	-.866	3	.5	11	1										
10	1.2DL + 1WL 180 AZI	Yes	Y	DL	1.2	2	-1	3		4	-1										
11	1.2DL + 1WL 210 AZI	Yes	Y	DL	1.2	2	-.866	3	-.5	5	-1										
12	1.2DL + 1WL 225 AZI	Yes	Y	DL	1.2	2	-.707	3	-.7	6	-1										
13	1.2DL + 1WL 240 AZI	Yes	Y	DL	1.2	2	-.5	3	-.8	7	-1										
14	1.2DL + 1WL 270 AZI	Yes	Y	DL	1.2	2		3	-1	8	-1										
15	1.2DL + 1WL 300 AZI	Yes	Y	DL	1.2	2	.5	3	-.8	9	-1										
16	1.2DL + 1WL 315 AZI	Yes	Y	DL	1.2	2	.707	3	-.7	10	-1										
17	1.2DL + 1WL 330 AZI	Yes	Y	DL	1.2	2	.866	3	-.5	11	-1										
18	0.9DL + 1WL 0 AZI	Yes	Y	DL	.9	2	1	3		4	1										
19	0.9DL + 1WL 30 AZI	Yes	Y	DL	.9	2	.866	3	.5	5	1										
20	0.9DL + 1WL 45 AZI	Yes	Y	DL	.9	2	.707	3	.707	6	1										
21	0.9DL + 1WL 60 AZI	Yes	Y	DL	.9	2	.5	3	.866	7	1										
22	0.9DL + 1WL 90 AZI	Yes	Y	DL	.9	2		3	1	8	1										
23	0.9DL + 1WL 120 AZI	Yes	Y	DL	.9	2	-.5	3	.866	9	1										
24	0.9DL + 1WL 135 AZI	Yes	Y	DL	.9	2	-.707	3	.707	10	1										
25	0.9DL + 1WL 150 AZI	Yes	Y	DL	.9	2	-.866	3	.5	11	1										
26	0.9DL + 1WL 180 AZI	Yes	Y	DL	.9	2	-1	3		4	-1										
27	0.9DL + 1WL 210 AZI	Yes	Y	DL	.9	2	-.866	3	-.5	5	-1										
28	0.9DL + 1WL 225 AZI	Yes	Y	DL	.9	2	-.707	3	-.7	6	-1										
29	0.9DL + 1WL 240 AZI	Yes	Y	DL	.9	2	-.5	3	-.8	7	-1										
30	0.9DL + 1WL 270 AZI	Yes	Y	DL	.9	2		3	-1	8	-1										
31	0.9DL + 1WL 300 AZI	Yes	Y	DL	.9	2	.5	3	-.8	9	-1										
32	0.9DL + 1WL 315 AZI	Yes	Y	DL	.9	2	.707	3	-.7	10	-1										
33	0.9DL + 1WL 330 AZI	Yes	Y	DL	.9	2	.866	3	-.5	11	-1										
34	1.2DL + 1DLi + 1WL...	Yes	Y	DL	1.2	OL1	1	13	1	14		15	1								
35	1.2DL + 1DLi + 1WL...	Yes	Y	DL	1.2	OL1	1	13.866	14	.5	16	1									
36	1.2DL + 1DLi + 1WL...	Yes	Y	DL	1.2	OL1	1	13.707	14.707	17	1										



Company : Trylon  
 Designer : AB  
 Job Number : 188625  
 Model Name : 881535

July 27, 2021  
 3:35 PM  
 Checked By: CA

**Load Combinations (Continued)**

	Description	Solve	PD...	SR...	B...	Factor	BLC	Factor	B...	Fa...	B...	Fa...	BLC	Fa...	B...	Fa...	B...	Fa...	B...	Fa...	
37	1.2DL + 1DLi + 1WL...	Yes	Y		DL	1.2	OL1	1	13	.5	14	.866	18	1							
38	1.2DL + 1DLi + 1WL...	Yes	Y		DL	1.2	OL1	1	13		14	1	19	1							
39	1.2DL + 1DLi + 1WL...	Yes	Y		DL	1.2	OL1	1	13	-.5	14	.866	20	1							
40	1.2DL + 1DLi + 1WL...	Yes	Y		DL	1.2	OL1	1	13	-.7	14	.707	21	1							
41	1.2DL + 1DLi + 1WL...	Yes	Y		DL	1.2	OL1	1	13	-.8	14	.5	22	1							
42	1.2DL + 1DLi + 1WL...	Yes	Y		DL	1.2	OL1	1	13	-1	14		15	-1							
43	1.2DL + 1DLi + 1WL...	Yes	Y		DL	1.2	OL1	1	13	-.8	14	-.5	16	-1							
44	1.2DL + 1DLi + 1WL...	Yes	Y		DL	1.2	OL1	1	13	-.7	14	-.7	17	-1							
45	1.2DL + 1DLi + 1WL...	Yes	Y		DL	1.2	OL1	1	13	-.5	14	-.8	18	-1							
46	1.2DL + 1DLi + 1WL...	Yes	Y		DL	1.2	OL1	1	13		14	-1	19	-1							
47	1.2DL + 1DLi + 1WL...	Yes	Y		DL	1.2	OL1	1	13	.5	14	-.8	20	-1							
48	1.2DL + 1DLi + 1WL...	Yes	Y		DL	1.2	OL1	1	13	.707	14	-.7	21	-1							
49	1.2DL + 1DLi + 1WL...	Yes	Y		DL	1.2	OL1	1	13	.866	14	-.5	22	-1							
50	(1.2+0.2Sds) + 1.0E...	Yes	Y		DL	1.244	ELX	1	E...												
51	(1.2+0.2Sds) + 1.0E...	Yes	Y		DL	1.244	ELX	.866	E...	.5											
52	(1.2+0.2Sds) + 1.0E...	Yes	Y		DL	1.244	ELX	.707	E...	.707											
53	(1.2+0.2Sds) + 1.0E...	Yes	Y		DL	1.244	ELX	.5	E...	.866											
54	(1.2+0.2Sds) + 1.0E...	Yes	Y		DL	1.244	ELX		E...	1											
55	(1.2+0.2Sds) + 1.0E...	Yes	Y		DL	1.244	ELX	-.5	E...	.866											
56	(1.2+0.2Sds) + 1.0E...	Yes	Y		DL	1.244	ELX	-.707	E...	.707											
57	(1.2+0.2Sds) + 1.0E...	Yes	Y		DL	1.244	ELX	-.866	E...	.5											
58	(1.2+0.2Sds) + 1.0E...	Yes	Y		DL	1.244	ELX	-1	E...												
59	(1.2+0.2Sds) + 1.0E...	Yes	Y		DL	1.244	ELX	-.866	E...	-.5											
60	(1.2+0.2Sds) + 1.0E...	Yes	Y		DL	1.244	ELX	-.707	E...	-.7...											
61	(1.2+0.2Sds) + 1.0E...	Yes	Y		DL	1.244	ELX	-.5	E...	-.8...											
62	(1.2+0.2Sds) + 1.0E...	Yes	Y		DL	1.244	ELX		E...	-1											
63	(1.2+0.2Sds) + 1.0E...	Yes	Y		DL	1.244	ELX	.5	E...	-.8...											
64	(1.2+0.2Sds) + 1.0E...	Yes	Y		DL	1.244	ELX	.707	E...	-.7...											
65	(1.2+0.2Sds) + 1.0E...	Yes	Y		DL	1.244	ELX	.866	E...	-.5											
66	(0.9-0.2Sds) + 1.0E...	Yes	Y		DL	.856	ELX	1	E...												
67	(0.9-0.2Sds) + 1.0E...	Yes	Y		DL	.856	ELX	.866	E...	.5											
68	(0.9-0.2Sds) + 1.0E...	Yes	Y		DL	.856	ELX	.707	E...	.707											
69	(0.9-0.2Sds) + 1.0E...	Yes	Y		DL	.856	ELX	.5	E...	.866											
70	(0.9-0.2Sds) + 1.0E...	Yes	Y		DL	.856	ELX		E...	1											
71	(0.9-0.2Sds) + 1.0E...	Yes	Y		DL	.856	ELX	-.5	E...	.866											
72	(0.9-0.2Sds) + 1.0E...	Yes	Y		DL	.856	ELX	-.707	E...	.707											
73	(0.9-0.2Sds) + 1.0E...	Yes	Y		DL	.856	ELX	-.866	E...	.5											
74	(0.9-0.2Sds) + 1.0E...	Yes	Y		DL	.856	ELX	-1	E...												
75	(0.9-0.2Sds) + 1.0E...	Yes	Y		DL	.856	ELX	-.866	E...	-.5											
76	(0.9-0.2Sds) + 1.0E...	Yes	Y		DL	.856	ELX	-.707	E...	-.7...											
77	(0.9-0.2Sds) + 1.0E...	Yes	Y		DL	.856	ELX	-.5	E...	-.8...											
78	(0.9-0.2Sds) + 1.0E...	Yes	Y		DL	.856	ELX		E...	-1											
79	(0.9-0.2Sds) + 1.0E...	Yes	Y		DL	.856	ELX	.5	E...	-.8...											
80	(0.9-0.2Sds) + 1.0E...	Yes	Y		DL	.856	ELX	.707	E...	-.7...											
81	(0.9-0.2Sds) + 1.0E...	Yes	Y		DL	.856	ELX	.866	E...	-.5											
82	1.2D + 1.5 Lv1	Yes	Y		DL	1.2	25	1.5													
83	1.2D + 1.5 Lv2	Yes	Y		DL	1.2	26	1.5													
84	1.2D + 1.5 Lv3	Yes	Y		DL	1.2	27	1.5													
85	1.2D + 1.5 Lv4	Yes	Y		DL	1.2	28	1.5													
86	1.2D + 1.5 Lv5	Yes	Y		DL	1.2	29	1.5													
87	1.2D + 1.5 Lv6	Yes	Y		DL	1.2	30	1.5													
88	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	31	1.5	4	.058	2	.058	3								





**Load Combinations (Continued)**

	Description	Solve	PD...	SR...	B...	Factor	BLC	Factor	B...	Fa...	B...	Fa...	BLC	Fa...	B...	Fa...	B...	Fa...	B...	Fa...
89	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	31	1.5	5	.058	2	.05	3	.029						
90	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	31	1.5	6	.058	2	.041	3	.041						
91	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	31	1.5	7	.058	2	.029	3	.05						
92	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	31	1.5	8	.058	2	3....	3	.058						
93	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	31	1.5	9	.058	2	-0...	3	.05						
94	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	31	1.5	10	.058	2	-0...	3	.041						
95	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	31	1.5	11	.058	2	-05	3	.029						
96	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	31	1.5	4	.058	2	-0...	3	7....						
97	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	31	1.5	5	.058	2	-05	3	-0...						
98	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	31	1.5	6	.058	2	-0...	3	-0...						
99	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	31	1.5	7	.058	2	-0...	3	-05						
100	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	31	1.5	8	.058	2	-1...	3	-0...						
101	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	31	1.5	9	.058	2	.029	3	-05						
102	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	31	1.5	10	.058	2	.041	3	-0...						
103	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	31	1.5	11	.058	2	.05	3	-0...						
104	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	32	1.5	4	.058	2	.058	3							
105	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	32	1.5	5	.058	2	.05	3	.029						
106	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	32	1.5	6	.058	2	.041	3	.041						
107	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	32	1.5	7	.058	2	.029	3	.05						
108	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	32	1.5	8	.058	2	3....	3	.058						
109	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	32	1.5	9	.058	2	-0...	3	.05						
110	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	32	1.5	10	.058	2	-0...	3	.041						
111	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	32	1.5	11	.058	2	-05	3	.029						
112	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	32	1.5	4	.058	2	-0...	3	7....						
113	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	32	1.5	5	.058	2	-05	3	-0...						
114	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	32	1.5	6	.058	2	-0...	3	-0...						
115	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	32	1.5	7	.058	2	-0...	3	-05						
116	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	32	1.5	8	.058	2	-1...	3	-0...						
117	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	32	1.5	9	.058	2	.029	3	-05						
118	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	32	1.5	10	.058	2	.041	3	-0...						
119	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	32	1.5	11	.058	2	.05	3	-0...						
120	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	33	1.5	4	.058	2	.058	3							
121	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	33	1.5	5	.058	2	.05	3	.029						
122	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	33	1.5	6	.058	2	.041	3	.041						
123	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	33	1.5	7	.058	2	.029	3	.05						
124	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	33	1.5	8	.058	2	3....	3	.058						
125	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	33	1.5	9	.058	2	-0...	3	.05						
126	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	33	1.5	10	.058	2	-0...	3	.041						
127	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	33	1.5	11	.058	2	-05	3	.029						
128	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	33	1.5	4	.058	2	-0...	3	7....						
129	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	33	1.5	5	.058	2	-05	3	-0...						
130	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	33	1.5	6	.058	2	-0...	3	-0...						
131	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	33	1.5	7	.058	2	-0...	3	-05						
132	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	33	1.5	8	.058	2	-1...	3	-0...						
133	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	33	1.5	9	.058	2	.029	3	-05						
134	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	33	1.5	10	.058	2	.041	3	-0...						
135	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	33	1.5	11	.058	2	.05	3	-0...						
136	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	34	1.5	4	.058	2	.058	3							
137	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	34	1.5	5	.058	2	.05	3	.029						
138	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	34	1.5	6	.058	2	.041	3	.041						
139	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	34	1.5	7	.058	2	.029	3	.05						
140	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	34	1.5	8	.058	2	3....	3	.058						

**Load Combinations (Continued)**

	Description	Solve	PD...	SR...	B...	Factor	BLC	Factor	B...	Fa...	B...	Fa...	BLC	Fa...	B...	Fa...	B...	Fa...	B...	Fa...
141	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	34	1.5	9	.058	2	-0...	3	.05						
142	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	34	1.5	10	.058	2	-0...	3	.041						
143	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	34	1.5	11	.058	2	-05	3	.029						
144	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	34	1.5	4	.058	2	-0...	3	7...						
145	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	34	1.5	5	.058	2	-05	3	-0...						
146	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	34	1.5	6	.058	2	-0...	3	-0...						
147	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	34	1.5	7	.058	2	-0...	3	-05						
148	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	34	1.5	8	.058	2	-1...	3	-0...						
149	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	34	1.5	9	.058	2	.029	3	-05						
150	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	34	1.5	10	.058	2	.041	3	-0...						
151	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	34	1.5	11	.058	2	.05	3	-0...						
152	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	35	1.5	4	.058	2	.058	3							
153	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	35	1.5	5	.058	2	.05	3	.029						
154	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	35	1.5	6	.058	2	.041	3	.041						
155	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	35	1.5	7	.058	2	.029	3	.05						
156	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	35	1.5	8	.058	2	3...	3	.058						
157	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	35	1.5	9	.058	2	-0...	3	.05						
158	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	35	1.5	10	.058	2	-0...	3	.041						
159	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	35	1.5	11	.058	2	-05	3	.029						
160	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	35	1.5	4	.058	2	-0...	3	7...						
161	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	35	1.5	5	.058	2	-05	3	-0...						
162	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	35	1.5	6	.058	2	-0...	3	-0...						
163	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	35	1.5	7	.058	2	-0...	3	-05						
164	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	35	1.5	8	.058	2	-1...	3	-0...						
165	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	35	1.5	9	.058	2	.029	3	-05						
166	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	35	1.5	10	.058	2	.041	3	-0...						
167	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	35	1.5	11	.058	2	.05	3	-0...						
168	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	36	1.5	4	.058	2	.058	3							
169	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	36	1.5	5	.058	2	.05	3	.029						
170	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	36	1.5	6	.058	2	.041	3	.041						
171	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	36	1.5	7	.058	2	.029	3	.05						
172	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	36	1.5	8	.058	2	3...	3	.058						
173	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	36	1.5	9	.058	2	-0...	3	.05						
174	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	36	1.5	10	.058	2	-0...	3	.041						
175	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	36	1.5	11	.058	2	-05	3	.029						
176	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	36	1.5	4	.058	2	-0...	3	7...						
177	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	36	1.5	5	.058	2	-05	3	-0...						
178	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	36	1.5	6	.058	2	-0...	3	-0...						
179	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	36	1.5	7	.058	2	-0...	3	-05						
180	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	36	1.5	8	.058	2	-1...	3	-0...						
181	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	36	1.5	9	.058	2	.029	3	-05						
182	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	36	1.5	10	.058	2	.041	3	-0...						
183	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	36	1.5	11	.058	2	.05	3	-0...						
184	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	37	1.5	4	.058	2	.058	3							
185	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	37	1.5	5	.058	2	.05	3	.029						
186	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	37	1.5	6	.058	2	.041	3	.041						
187	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	37	1.5	7	.058	2	.029	3	.05						
188	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	37	1.5	8	.058	2	3...	3	.058						
189	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	37	1.5	9	.058	2	-0...	3	.05						
190	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	37	1.5	10	.058	2	-0...	3	.041						
191	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	37	1.5	11	.058	2	-05	3	.029						
192	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	37	1.5	4	.058	2	-0...	3	7...						

**Load Combinations (Continued)**

	Description	Solve	PD...	SR...	B...	Factor	BLC	Factor	B...	Fa...	B...	Fa...	BLC	Fa...	B...	Fa...	B...	Fa...	B...	Fa...	
193	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	37	1.5	5	.058	2	-0.05	3	-0.05							
194	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	37	1.5	6	.058	2	-0.05	3	-0.05							
195	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	37	1.5	7	.058	2	-0.05	3	-0.05							
196	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	37	1.5	8	.058	2	-1.05	3	-0.05							
197	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	37	1.5	9	.058	2	.029	3	-0.05							
198	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	37	1.5	10	.058	2	.041	3	-0.05							
199	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	37	1.5	11	.058	2	.05	3	-0.05							
200	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	38	1.5	4	.058	2	.058	3								
201	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	38	1.5	5	.058	2	.05	3	.029							
202	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	38	1.5	6	.058	2	.041	3	.041							
203	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	38	1.5	7	.058	2	.029	3	.05							
204	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	38	1.5	8	.058	2	3.05	3	.058							
205	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	38	1.5	9	.058	2	-0.05	3	.05							
206	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	38	1.5	10	.058	2	-0.05	3	.041							
207	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	38	1.5	11	.058	2	-0.05	3	.029							
208	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	38	1.5	4	.058	2	-0.05	3	7.05							
209	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	38	1.5	5	.058	2	-0.05	3	-0.05							
210	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	38	1.5	6	.058	2	-0.05	3	-0.05							
211	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	38	1.5	7	.058	2	-0.05	3	-0.05							
212	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	38	1.5	8	.058	2	-1.05	3	-0.05							
213	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	38	1.5	9	.058	2	.029	3	-0.05							
214	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	38	1.5	10	.058	2	.041	3	-0.05							
215	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	38	1.5	11	.058	2	.05	3	-0.05							
216	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	39	1.5	4	.058	2	.058	3								
217	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	39	1.5	5	.058	2	.05	3	.029							
218	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	39	1.5	6	.058	2	.041	3	.041							
219	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	39	1.5	7	.058	2	.029	3	.05							
220	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	39	1.5	8	.058	2	3.05	3	.058							
221	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	39	1.5	9	.058	2	-0.05	3	.05							
222	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	39	1.5	10	.058	2	-0.05	3	.041							
223	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	39	1.5	11	.058	2	-0.05	3	.029							
224	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	39	1.5	4	.058	2	-0.05	3	7.05							
225	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	39	1.5	5	.058	2	-0.05	3	-0.05							
226	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	39	1.5	6	.058	2	-0.05	3	-0.05							
227	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	39	1.5	7	.058	2	-0.05	3	-0.05							
228	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	39	1.5	8	.058	2	-1.05	3	-0.05							
229	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	39	1.5	9	.058	2	.029	3	-0.05							
230	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	39	1.5	10	.058	2	.041	3	-0.05							
231	1.2D + 1.5Lm + 1.0...	Yes	Y		DL	1.2	39	1.5	11	.058	2	.05	3	-0.05							

**Envelope Joint Reactions**

	Joint		X [lb]	LC	Y [lb]	LC	Z [lb]	LC	MX [lb-ft]	LC	MY [lb-ft]	LC	MZ [lb-ft]	LC
1	N25	max	1563.59	3	938.6	20	1956.53	39	402.95	31	471.33	33	1805.69	3
2		min	-1559.84	27	-944.77	12	-61	31	-3455.77	38	-2127.95	41	-1805.25	27
3	N1	max	1563.59	17	944.76	8	1956.54	45	3455.8	46	471.34	19	1805.25	25
4		min	-1559.83	25	-938.59	32	-61.01	21	-402.95	21	-2127.96	43	-1805.69	17
5	N13	max	335.54	18	1564.2	22	1882.13	34	686.34	14	3872.38	34	1503.43	14
6		min	-343.29	10	-1564.2	30	-97.48	26	-686.33	6	-555.3	26	-1503.43	6
7	Totals:	max	3033.14	18	2832.83	22	5517.97	44						
8		min	-3033.14	10	-2832.83	30	1358.14	69						



Company : Trylon  
 Designer : AB  
 Job Number : 188625  
 Model Name : 881535

July 27, 2021  
 3:35 PM  
 Checked By: CA

**Envelope AISC 15th(360-16): LRFD Steel Code Checks**

Member	Shape	Code Check	Loc[in]	LC	Shea...	Lo...	...	phi*P...	phi*P...	phi*M...	phi*M.....	Eqn		
1	SA2	PIPE 3.5	.508	40	45	.186	40	9	64491...	78750	7953...	7953....	H1-1b	
2	SA3	PIPE 3.5	.508	40	39	.186	40	11	64491...	78750	7953...	7953....	H1-1b	
3	SA1	PIPE 3.5	.487	40	34	.168	40	14	64491...	78750	7953...	7953....	H1-1b	
4	PB2	C3X5	.386	34.86	45	.142	6.54	y	49	32858...	47628	981.26	4104	H1-1b
5	PB3	C3X5	.386	34.86	39	.142	63...	y	35	32858...	47628	981.26	4104	H1-1b
6	PB1	C3X5	.366	34.86	49	.133	63...	y	46	32858...	47628	981.26	4104	H1-1b
7	MP3	PIPE 2.0	.346	57	5	.049	57	10	20866...	32130	1871....	1871....	1 H1-1b	
8	MP1	PIPE 2.0	.346	57	15	.049	57	10	20866...	32130	1871....	1871....	H1-1b	
9	MP9	PIPE 2.0	.340	57	10	.039	57	15	20866...	32130	1871....	1871....	H1-1b	
10	MP4	PIPE 2.0	.340	57	10	.039	57	5	20866...	32130	1871....	1871....	1 H1-1b	
11	MP2	PIPE 2.0	.320	57	14	.046	57	5	20866...	32130	1871....	1871....	H1-1b	
12	MP7	PIPE 2.0	.312	57	5	.046	57	16	20866...	32130	1871....	1871....	1 H1-1b	
13	MP6	PIPE 2.0	.312	57	15	.046	57	4	20866...	32130	1871....	1871....	H1-1b	
14	MP8	PIPE 2.0	.307	57	10	.043	57	10	20866...	32130	1871....	1871....	H1-1b	
15	MP5	PIPE 2.0	.307	57	10	.043	57	10	20866...	32130	1871....	1871....	1 H1-1b	
16	CP5	6.5"x0.37" Plate	.238	21	13	.091	21	y	47	27548...	75757...	583.96	6228.5	H1-1b
17	CP6	6.5"x0.37" Plate	.238	21	7	.091	21	y	37	27548...	75757...	583.96	6228....	H1-1b
18	CP4	6.5"x0.37" Plate	.236	21	2	.085	21	y	47	27548...	75757...	583.96	6182....	H1-1b
19	M19	PIPE 2.0	.138	24	10	.147	72	2	14916...	32130	1871....	1871....	H1-1b	
20	M20	PIPE 2.0	.134	24	15	.139	72	8	14916...	32130	1871....	1871....	H1-1b	
21	M21	PIPE 2.0	.134	72	5	.139	24	12	14916...	32130	1871....	1871....	H1-1b	
22	IFH32	L2x2x3	.118	0	14	.029	0	y	41	18084...	23392...	557.72	1182....	1 H2-1
23	IFH21	L2x2x3	.117	0	30	.029	0	z	43	18084...	23392...	557.72	1182....	1 H2-1
24	IFH11	L2x2x3	.107	0	3	.029	0	z	49	18084...	23392...	557.72	1179....	1 H2-1
25	IFH12	L2x2x3	.107	0	25	.029	0	y	35	18084...	23392...	557.72	1179....	1 H2-1
26	H1	PIPE 3.5	.107	48	105	.096	24	10	60666...	78750	7953...	7953....	1 H1-1b	
27	H3	PIPE 3.5	.104	48	207	.091	24	15	60666...	78750	7953...	7953....	1 H1-1b	
28	H2	PIPE 3.5	.102	48	159	.091	72	5	60666...	78750	7953...	7953....	1 H1-1b	
29	IFH22	L2x2x3	.098	0	2	.028	0	y	46	18084...	23392...	557.72	1182....	1 H2-1
30	IFH 31	L2x2x3	.097	0	26	.028	0	z	38	18084...	23392...	557.72	1182....	1 H2-1
31	CP3	6.6x4.46x0.25	.056	0	21	.041	0	y	3	51170...	87561	2464...	7125....	1 H2-1
32	CP2	6.6x4.46x0.25	.056	42	31	.041	42	y	17	51170...	87561	2464...	7125....	1 H2-1
33	CP1	6.6x4.46x0.25	.049	21	18	.038	0	y	14	51170...	87561	2464...	7125....	1 H2-1

**Envelope AISI 100-12: LRFD Cold Formed Steel Code Checks**

Member	Shape	Code Check	Loc[in]	LC	Shea...	Loc[...Dir	LC	phi*Pn[...phi*Tn[...phi*Mn...phi*Mn...	Cb	Cmyy	Cmzz	Eqn
No Data to Print ...												

**APPENDIX D**  
**ADDITIONAL CALCUATIONS**

**BOLT TOOL 1.5.2**

Project Data	
Job Code:	188625
Carrier Site ID:	NJJER01096A
Carrier Site Name:	CT-CCI-T-881535


Code	
Design Standard:	TIA-222-H
Slip Check:	No
Pretension Standard:	TIA-222-H

Bolt Properties		
Connection Type:	Bolt	
Diameter:	0.625	in
Grade:	A325	--
Yield Strength (Fy):	92	ksi
Ultimate Strength (Fu):	120	ksi
Number of Bolts:	4	--
Threads Included:	No	--
Double Shear:	No	--
Connection Pipe Size:	-	in

Connection Description
Standoff to Monopole

Bolt Check*		
Tensile Capacity ( $\phi T_n$ ):	20340.1	lbs
Shear Capacity ( $\phi V_n$ ):	17257.3	lbs
Tension Force ( $T_u$ ):	4148.5	lbs
Shear Force ( $V_u$ ):	593.4	lbs
Tension Usage:	19.4%	--
Shear Usage:	3.3%	--
Interaction:	19.4%	Pass
Controlling Member:	SA2	--
Controlling LC:	42	--

\*Rating per TIA-222-H Section 15.5




**APPENDIX E**  
**SUPPLEMENTAL DRAWINGS**

ITEM	PART NO.	DESCRIPTION	QTY.	WEIGHT	NOTE NO.
1	MTC3006SB	STEEL BUNDLE FOR SNUB NOSE PLATFORM	1	402.64 LBS	
2	MCPK8CSB	PIPE STEEL BUNDLE FOR MC-PK8-C	1	464.27 LBS	
3	MCPK8CHWK	HARDWARE KIT FOR MC-PK8-C	1	543.22 LBS	



FOR BOM ENTRY ONLY



REV.	ECN	DESCRIPTION	BY	DATE
A		INITIAL RELEASE	DRR	12/27/11
B	8000005979	CHANGE NOSE CORNER BRKT. ADD GUB-4240	MSM	11/25/14
C	8000007579	NEW RINGMOUNT WELDMENT DESIGN	RJC	04/07/15




<p>These drawings and specifications are the property of Andrew Corporation and may be used only for the specific purpose intended in writing by Andrew Corporation.</p> <p>ALL DIMENSIONS ARE IN INCHES UNLESS OTHERWISE SPECIFIED:</p> <p>X = ± .12 ANGLES ±7</p> <p>XX = ± .06 FRACTIONS ±1/32</p> <p>XXX = ± .03</p> <p>REMOVE BURRS AND BREAK EDGES .005</p> <p>DO NOT SCALE THIS PRINT</p>		<p>DATE: 10/18/11</p> <p>BY: TP</p> <p>REVISED: C</p>	<p>QTY: 1 of 3</p> <p>UNIT: NTS</p> <p>ITEM: A36, A500</p> <p>REVISION: GALV A123</p> <p>WEIGHT: 1410.14 LBS</p>	<p>ITEM: MC-PK8-C</p> <p>DESCRIPTION: LOW PROFILE PLATFORM KIT 8' FACE ASSEMBLY DRAWING</p>
--	--	---	--	---

NOTES:  
1. CUSTOMER ASSEMBLY SHEETS 2-3.





38 [965.2]  
15 [381.0]



ITEM	PART NO.	DESCRIPTION	QTY.	WEIGHT
1	MC-RM1550-3	12" - 50" OD RINGMOUNT	1	230.42 LBS
2	MTC300601	Low Profile Co-Location Platform Snub Nose	3	134.21 LBS
3	MT1195801	Corner Weldment Snub Nose Handrail	3	27.10 LBS
4	XA2020.01	CROSS OVER ANGLE	9	2.65 LBS
5	GUB-4356	1/2" X 3-5/8" X 6" GALV U-BOLT	18	0.82 LBS
6	GUB-4355	1/2" X 3-5/8" X 5" GALV U-BOLT	12	0.71 LBS
7	GUB-4240	1/2" X 2-1/2" X 4" GALV U-BOLT	48	0.56 LBS
8	GB-04145	1/2" X 1-1/2" GALV BOLT KIT	12	0.13 LBS
9	GW-04	1/2" GALV FLAT WASHER	24	0.03 LBS
10	GB-0520A	5/8" X 2" GALV BOLT KIT (A325)	12	0.27 LBS
11	MT154796	3.50" OD X 96" GALV PIPE	3	60.28 LBS
12	MT-651-96	Ø2.375" OD X 96" PIPE	3	29.07 LBS
13	MT-651	2.375" OD x 72" PIPE	9	21.80 LBS
14	MT119617	MT1196 Pipe Mount Plate	6	2.49 LBS
15	MT21701	PIPE MOUNT PLATE	9	7.93 LBS

These drawings and specifications are the property of Andrew Corporation and may be used only for the specific application indicated in writing by Andrew Corporation.

ALL DIMENSIONS ARE IN INCHES UNLESS OTHERWISE SPECIFIED.

TOLERANCES UNLESS OTHERWISE SPECIFIED:  
X = ± .12  
XX = ± .06  
XXX = ± .03

ANGLES ±7  
FRACTIONS ±1/32

REVISION C

DO NOT SCALE THIS PRINT


Part No. MSM 2 of 3  
Title NTS  
Drawing No. A36, A53  
Revision GALV A123  
Quantity 136127 LBS

Part No. MC-PK8-C  
Title 25" OD Snub Nose MT-196  
Drawing No. ASSEMBLY DRAWING


Part No. WESTCHESTER, IL. 60154  
U.S.A.

**ANDREW**®  
U.S.A.


NOTES:  
1. ALL METRIC DIMENSIONS ARE IN BRACKETS.  
2. WILL FIT MONOPOLES 15"-38" OD.




# WITH ANTENNAS



DETAIL A  
SCALE 1 : 8



DETAIL C  
SCALE 1 : 8



DETAIL B  
SCALE 1 : 8

These drawings and specifications are the property of Andrew Corporation and may be used only for the specific purpose intended in writing by Andrew Corporation.

ALL DIMENSIONS ARE IN INCHES U.S.S.  
TOLERANCES UNLESS OTHERWISE SPECIFIED:  
X = ± .12 ANGLES ±7  
XX = ± .06 FRACTIONS ±1/32  
XXX = ± .03 REVISION  
REMOVE BURRS AND BREAK EDGES .005

DO NOT SCALE THIS PRINT

FORM NO.	MSM	REV.	3 of 3	REV. DATE	MC-PK8-C
DATE	TP	NTS		REV. DATE	25" OD Stub Nose, WT-196
REV.	10/18/11	A36, A53		REV. DATE	ASSEMBLY DRAWING
REVISION	C	CALL A123		REV. DATE	
WEIGHT			1361.27 LBS	WESTCHESTER, ILL. 60154	
PART NO.				U.S.A.	
DRAWN BY				ANDREW®	

NOTES:  
1. ALL METRIC DIMENSIONS ARE IN BRACKETS.

# Exhibit F

## **Power Density/RF Emissions Report**

RADIO FREQUENCY EMISSIONS ANALYSIS REPORT  
EVALUATION OF HUMAN EXPOSURE POTENTIAL  
TO NON-IONIZING EMISSIONS

Dish Wireless Existing Facility

Site ID: NJJER01096A

881535

425 Indian Ledge Park Road  
Trumbull, Connecticut 06611

**September 9, 2021**

**EBI Project Number: 6221004863**

Site Compliance Summary	
Compliance Status:	<b>COMPLIANT</b>
Site total MPE% of FCC general population allowable limit:	<b>18.77%</b>

September 9, 2021

Dish Wireless

Emissions Analysis for Site: NJJER01096A - 881535

EBI Consulting was directed to analyze the proposed Dish Wireless facility located at **425 Indian Ledge Park Road in Trumbull, Connecticut** for the purpose of determining whether the emissions from the Proposed Dish Wireless Antenna Installation located on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter ( $\mu\text{W}/\text{cm}^2$ ). The number of  $\mu\text{W}/\text{cm}^2$  calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits; therefore, it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) – (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general population may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general population would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

Public exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter ( $\mu\text{W}/\text{cm}^2$ ). The general population exposure limits for the 600 MHz and 700 MHz frequency bands are approximately  $400 \mu\text{W}/\text{cm}^2$  and  $467 \mu\text{W}/\text{cm}^2$ , respectively. The general population exposure limit for the 1900 MHz (PCS), 2100 MHz (AWS) and 11 GHz frequency bands is  $1000 \mu\text{W}/\text{cm}^2$ . Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.

Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure.

Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

## **CALCULATIONS**

Calculations were done for the proposed Dish Wireless antenna facility located at 425 Indian Ledge Park Road in Trumbull, Connecticut using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. Since Dish Wireless is proposing highly focused directional panel antennas, which project most of the emitted energy out toward the horizon, all calculations were performed assuming a lobe representing the maximum gain of the antenna per the antenna manufacturer's supplied specifications, minus 20 dB for directional panel antennas and 20 dB for highly focused parabolic microwave dishes, was focused at the base of the tower. For this report, the sample point is the top of a 6-foot person standing at the base of the tower.

For all calculations, all equipment was calculated using the following assumptions:

- 1) 4 n71 channels (600 MHz Band) were considered for each sector of the proposed installation. These Channels have a transmit power of 30 Watts per Channel.
- 2) 4 n70 channels (PCS Band - 1900 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 40 Watts per Channel.
- 3) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 - Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.
- 4) For the following calculations, the sample point was the top of a 6-foot person standing at the base of the tower. The maximum gain of the antenna per the antenna manufacturer's supplied specifications, minus 20 dB for directional panel antennas and 20 dB for highly focused parabolic microwave dishes, was used in this direction. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.

- 5) The antennas used in this modeling are the JMA MX08FRO665-20 for the 600 MHz / 1900 MHz channel(s) in Sector A, the JMA MX08FRO665-20 for the 600 MHz / 1900 MHz channel(s) in Sector B, the JMA MX08FRO665-20 for the 600 MHz / 1900 MHz channel(s) in Sector C. This is based on feedback from the carrier with regard to anticipated antenna selection. All Antenna gain values and associated transmit power levels are shown in the Site Inventory and Power Data table below. The maximum gain of the antenna per the antenna manufacturer's supplied specifications, minus 20 dB for directional panel antennas and 20 dB for highly focused parabolic microwave dishes, was used for all calculations. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 6) The antenna mounting height centerline of the proposed antennas is 175 feet above ground level (AGL).
- 7) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.
- 8) All calculations were done with respect to uncontrolled / general population threshold limits.

## Dish Wireless Site Inventory and Power Data

Sector:	A	Sector:	B	Sector:	C
Antenna #:	I	Antenna #:	I	Antenna #:	I
Make / Model:	JMA MX08FRO665-20	Make / Model:	JMA MX08FRO665-20	Make / Model:	JMA MX08FRO665-20
Frequency Bands:	600 MHz / 1900 MHz	Frequency Bands:	600 MHz / 1900 MHz	Frequency Bands:	600 MHz / 1900 MHz
Gain:	17.45 dBd / 22.65 dBd	Gain:	17.45 dBd / 22.65 dBd	Gain:	17.45 dBd / 22.65 dBd
Height (AGL):	175 feet	Height (AGL):	175 feet	Height (AGL):	175 feet
Channel Count:	8	Channel Count:	8	Channel Count:	8
Total TX Power (W):	280 Watts	Total TX Power (W):	280 Watts	Total TX Power (W):	280 Watts
ERP (W):	3,065.51	ERP (W):	3,065.51	ERP (W):	3,065.51
Antenna AI MPE %:	<b>0.55%</b>	Antenna BI MPE %:	<b>0.55%</b>	Antenna CI MPE %:	<b>0.55%</b>



Site Composite MPE %	
Carrier	MPE %
Dish Wireless (Max at Sector A):	0.55%
Town	4.8%
AT&T	5.01%
Sprint	2.07%
Clearwire	0.07%
Verizon	2.95%
T-Mobile	3.32%
<b>Site Total MPE % :</b>	<b>18.77%</b>

Dish Wireless MPE % Per Sector	
Dish Wireless Sector A Total:	0.55%
Dish Wireless Sector B Total:	0.55%
Dish Wireless Sector C Total:	0.55%
<b>Site Total MPE % :</b>	<b>18.77%</b>

Dish Wireless Maximum MPE Power Values (Sector A)							
Dish Wireless Frequency Band / Technology (Sector A)	# Channels	Watts ERP (Per Channel)	Height (feet)	Total Power Density ( $\mu\text{W}/\text{cm}^2$ )	Frequency (MHz)	Allowable MPE ( $\mu\text{W}/\text{cm}^2$ )	Calculated % MPE
Dish Wireless 600 MHz n71	4	223.68	175.0	1.13	600 MHz n71	400	0.28%
Dish Wireless 1900 MHz n70	4	542.70	175.0	2.73	1900 MHz n70	1000	0.27%
						<b>Total:</b>	<b>0.55%</b>

• NOTE: Totals may vary by approximately 0.01% due to summation of remainders in calculations.

## Summary

All calculations performed for this analysis yielded results that were **within** the allowable limits for general population exposure to RF Emissions.

The anticipated maximum composite contributions from the Dish Wireless facility as well as the site composite emissions value with regards to compliance with FCC's allowable limits for general population exposure to RF Emissions are shown here:

Dish Wireless Sector	Power Density Value (%)
Sector A:	0.55%
Sector B:	0.55%
Sector C:	0.55%
Dish Wireless Maximum MPE % (Sector A):	0.55%
Site Total:	18.77%
Site Compliance Status:	<b>COMPLIANT</b>

The anticipated composite MPE value for this site assuming all carriers present is **18.77%** of the allowable FCC established general population limit sampled at the ground level. This is based upon values listed in the Connecticut Siting Council database for existing carrier emissions.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.

# Exhibit G

## **Letter of Authorization**



4545 E River Rd, Suite 320  
West Henrietta, NY 14586

Phone: (585) 445-5896  
Fax: (724) 416-4461  
www.crowncastle.com

**Crown Castle Letter of Authorization**

**CT - CONNECTICUT SITING COUNCIL**

Melanie A. Bachman  
Executive Director  
Connecticut Siting Council  
10 Franklin Square  
New Britain, CT 06051

**Re: Tower Share Application  
Crown Castle telecommunications site at:  
425 INDIAN LEDGE PARK RD, TRUMBULL, CT 06611**

GLOBAL SIGNAL ACQUISITIONS IV LLC (“Crown Castle”) hereby authorizes DISH Wireless LLC, including their Agent, to act as our Agent in the processing of all zoning applications, building permits and approvals through the CT - CONNECTICUT SITING COUNCIL for the existing wireless communications site described below:


**Crown Site ID/Name: 881535/TRUMBULL TOWER  
Customer Site ID: NJJER01096A/CT-CCI-T-881535  
Site Address: 425 Indian Ledge Park Rd, Trumbull, CT 06611**

Crown Castle

By:  \_\_\_\_\_ Date: 8/30/2021  
Richard Zajac  
Site Acquisition Specialist

# Exhibit H

## Recipient Mailings



Cut on dotted line.

### Instructions

1. Each Click-N-Ship® label is unique. Labels are to be used as printed and used only once. DO NOT PHOTO COPY OR ALTER LABEL.
2. Place your label so it does not wrap around the edge of the package.
3. Adhere your label to the package. A self-adhesive label is recommended. If tape or glue is used, DO NOT TAPE OVER BARCODE. Be sure all edges are secure.
4. To mail your package with PC Postage®, you may schedule a Package Pickup online, hand to your letter carrier, take to a Post Office™, or drop in a USPS collection box.
5. Mail your package on the "Ship Date" you selected when creating this label.


### Click-N-Ship® Label Record

<b>USPS TRACKING # :</b>	
<b>9405 5036 9930 0185 2343 29</b>	
Trans. #:	558182931
Print Date:	03/07/2022
Ship Date:	03/07/2022
Expected Delivery Date:	03/10/2022
Priority Mail® Postage:	<b>\$8.95</b>
Total:	<b>\$8.95</b>
<b>From:</b>	DEBORAH CHASE NORTHEAST SITE SOLUTIONS 420 MAIN ST STE 1 STURBRIDGE MA 01566-1359
<b>To:</b>	RICH ZAJAC CROWN CASTLE 4545 E RIVER RD STE 320 W HENRIETTA NY 14586-9024
	Reff#: DS-881535
<small>* Retail Pricing Priority Mail rates apply. There is no fee for USPS Tracking® service on Priority Mail service with use of this electronic rate shipping label. Refunds for unused postage paid labels can be requested online 30 days from the print date.</small>	



Thank you for shipping with the United States Postal Service!

Check the status of your shipment on the USPS Tracking® page at usps.com



**UNITED STATES  
POSTAL SERVICE®**

**Click-N-Ship®**

**P**

usps.com 9405 5036 9930 0185 2343 36 0089 5000 0020 6611  
**US POSTAGE**  
 Flat Rate Env  
 03/07/2022

**U.S. POSTAGE PAID**  
Click-N-Ship®

Mailed from 01566


**PRIORITY MAIL 2-DAY™**

Expected Delivery Date: 03/10/22  
 Re#: DS-881535  
**0006**

**C002**

SHIP TO: VICKI TESORO  
 FIRST SELECTMAN & PROPERTY OWNER  
 5866 MAIN ST  
 # 2  
 TRUMBULL CT 06611-3113

**USPS TRACKING #**



**9405 5036 9930 0185 2343 36**

Electronic Rate Approved #038555749



Cut on dotted line.

### Instructions

1. Each Click-N-Ship® label is unique. Labels are to be used as printed and used only once. DO NOT PHOTO COPY OR ALTER LABEL.
2. Place your label so it does not wrap around the edge of the package.
3. Adhere your label to the package. A self-adhesive label is recommended. If tape or glue is used, DO NOT TAPE OVER BARCODE. Be sure all edges are secure.
4. To mail your package with PC Postage®, you may schedule a Package Pickup online, hand to your letter carrier, take to a Post Office™, or drop in a USPS collection box.
5. Mail your package on the "Ship Date" you selected when creating this label.

### Click-N-Ship® Label Record

**USPS TRACKING # :**  
**9405 5036 9930 0185 2343 36**

Trans. #: 558182931	Priority Mail® Postage: <b>\$8.95</b>
Print Date: 03/07/2022	Total: <b>\$8.95</b>
Ship Date: 03/07/2022	
Expected Delivery Date: 03/10/2022	

**From:** DEBORAH CHASE  
 NORTHEAST SITE SOLUTIONS  
 420 MAIN ST  
 STE 1  
 STURBRIDGE MA 01566-1359


Re#: DS-881535

**To:** VICKI TESORO  
 FIRST SELECTMAN & PROPERTY OWNER  
 5866 MAIN ST  
 # 2  
 TRUMBULL CT 06611-3113

\* Retail Pricing Priority Mail rates apply. There is no fee for USPS Tracking® service on Priority Mail service with use of this electronic rate shipping label. Refunds for unused postage paid labels can be requested online 30 days from the print date.



Thank you for shipping with the United States Postal Service!  
 Check the status of your shipment on the USPS Tracking® page at usps.com



**UNITED STATES  
POSTAL SERVICE®**

**Click-N-Ship®**

**P**

usps.com 9405 5036 9930 0185 2343 81 0089 5000 0020 6611  
**US POSTAGE**  
 Flat Rate Envoy

U.S. POSTAGE PAID  
Click-N-Ship®

03/07/2022 Mailed from 01566


**PRIORITY MAIL 2-DAY™**

Expected Delivery Date: 03/10/22  
 Ref#: CR-881535  
**0006**

**C002**

SHIP TO: ROB LIBRANDI  
 LAND USE PLANNER  
 5866 MAIN ST  
 # 2  
 TRUMBULL CT 06611-3113

**USPS TRACKING #**



**9405 5036 9930 0185 2343 81**

Electronic Rate Approved #038555749



Cut on dotted line.

### Instructions

1. Each Click-N-Ship® label is unique. Labels are to be used as printed and used only once. DO NOT PHOTO COPY OR ALTER LABEL.
2. Place your label so it does not wrap around the edge of the package.
3. Adhere your label to the package. A self-adhesive label is recommended. If tape or glue is used, DO NOT TAPE OVER BARCODE. Be sure all edges are secure.
4. To mail your package with PC Postage®, you may schedule a Package Pickup online, hand to your letter carrier, take to a Post Office™, or drop in a USPS collection box.
5. Mail your package on the "Ship Date" you selected when creating this label.

### Click-N-Ship® Label Record

**USPS TRACKING # :**  
**9405 5036 9930 0185 2343 81**

Trans. #: 558182931	Priority Mail® Postage: <b>\$8.95</b>
Print Date: 03/07/2022	Total: <b>\$8.95</b>
Ship Date: 03/07/2022	
Expected Delivery Date: 03/10/2022	

**From:** DEBORAH CHASE  
 NORTHEAST SITE SOLUTIONS  
 420 MAIN ST  
 STE 1  
 STURBRIDGE MA 01566-1359  
 Ref#: CR-881535

**To:** ROB LIBRANDI  
 LAND USE PLANNER  
 5866 MAIN ST  
 # 2  
 TRUMBULL CT 06611-3113

\* Retail Pricing Priority Mail rates apply. There is no fee for USPS Tracking® service on Priority Mail service with use of this electronic rate shipping label. Refunds for unused postage paid labels can be requested online 30 days from the print date.



Thank you for shipping with the United States Postal Service!  
 Check the status of your shipment on the USPS Tracking® page at usps.com



881535 Crown Dish



FARMINGTON  
210 MAIN ST  
FARMINGTON, CT 06032-9998  
(800)275-8777

03/07/2022 04:38 PM

Product	Qty	Unit Price	Price
Prepaid Mail West Henrietta, NY 14586 Weight: 0 lb 1.90 oz Acceptance Date: Mon 03/07/2022 Tracking #: 9405 5036 9930 0185 2343 29	1		\$0.00
Prepaid Mail Trumbull, CT 06611 Weight: 0 lb 11.10 oz Acceptance Date: Mon 03/07/2022 Tracking #: 9405 5036 9930 0185 2343 81	1		\$0.00
Prepaid Mail Trumbull, CT 06611 Weight: 0 lb 11.10 oz Acceptance Date: Mon 03/07/2022 Tracking #: 9405 5036 9930 0185 2343 36	1		\$0.00
Grand Total:			\$0.00