

January 9, 2015

Melanie A. Bachman
Connecticut Siting Council
10 Franklin Square
New Britain, CT 06051

**RE: Sprint PCS-Exempt Modification - Crown Site BU: 881535
Sprint PCS Site ID: CT03XC373
Located at: 425 Indian Ledge Park Road, Trumbull, CT 06611**

Dear Ms. Bachman:

This letter and exhibits are submitted on behalf of Sprint PCS (Sprint). Sprint is making modifications to certain existing sites in its Connecticut system in order to implement their 2.5GHz LTE technology. Please accept this letter and exhibits as notification, pursuant to § 16-50j-73 of the Regulations of Connecticut State Agencies (“R.C.S.A.”), of construction that constitutes an exempt modification pursuant to R.C.S.A. § 16-50j-72(b)(2). In compliance with R.C.S.A. § 16-50j-73, a copy of this letter is being sent to The Honorable Timothy M. Herbst, First Selectman for Town of Trumbull. The Town of Trumbull is also the Property Owner.

Sprint plans to modify the existing wireless communications facility owned by Crown Castle and located at **425 Indian Ledge Park Road, Trumbull, CT 06611**. Attached are a compound plan and elevation depicting the planned changes (Exhibit-1), and documentation of the structural sufficiency of the structure to accommodate the revised antenna configuration (Exhibit-2). Also included is a power density table report reflecting the modification to Sprint’s operations at the site (Exhibit-3).

The changes to the facility do not constitute a modification as defined in Connecticut General Statutes (“C.G.S.”) § 16-50i(d) because the general physical characteristics of the facility will not be significantly changed. Rather, the planned changes to the facility fall squarely within those activities explicitly provided for in the R.C.S.A. § 16-50j-72(b)(2).

1. The proposed modifications will not result in an increase in the height of the existing tower. Sprint’s additional antennas will be located at the same elevation on the existing tower.
2. There will be no proposed modifications to the ground and no extension of boundaries.
3. The proposed modifications will not increase noise levels at the facility by six decibels or more.

Melanie A. Bachman

January 9, 2015

Page 2

4. A Structural Modification Report confirming that the tower and foundation can support Sprint's proposed modifications is included as Exhibit-2.
5. The operation of the additional antennas will not increase radio frequency (RF) emissions at the facility to a level at or above the Federal Communications Commission (FCC) adopted safety standard. A cumulative General Power Density table report for Sprint's modified facility is included as Exhibit-3.

For the foregoing reasons, Sprint respectfully submits the proposed modifications to the above-reference telecommunications facility constitutes an exempt modification under R.C.S.A. § 16-50j-72(b)(2). Please send approval/rejection letter to Attn: Donna Neal.

Sincerely,



Susan Vale
Real Estate Specialist

Enclosures

Tab 1: Exhibit-1: Compound plan and elevation depicting the planned changes

Tab 2: Exhibit-2: Structural Modification Report

Tab 3: Exhibit-3: General Power Density Table Report (RF Emissions Analysis Report)

cc: The Honorable Timothy M. Herbst, First Selectman
Town of Trumbull
Town Hall, 2nd Floor
5866 Main Street
Trumbull, CT 06611

Jamie Bratt, Director of Planning
Town of Trumbull
5866 Main Street
Second Floor
Trumbull, CT 06611



2.5 EQUIPMENT DEPLOYMENT

SITE NUMBER:
CT03XC373

SITE NAME:
CANDID COMMUNICATIONS

SITE ADDRESS:
425 INDIAN LEDGE PARK
TRUMBULL, CT 06611

CROWN ID#: 881535

CROWN SITE NAME: TRUMBULL TOWER

Sprint
2.5 EQUIPMENT DEPLOYMENT
6580 SPRINT PARKWAY
OVERLAND PARK, KANSAS 66251




TECTONIC
• PLANNING
• ENGINEERING
• SURVEYING
• CONSTRUCTION MANAGEMENT
TECTONIC Engineering & Surveying
Consultants P.C.
1279 Route 300
Newburgh, NY 12550
Phone: (845) 567-6656
Fax: (845) 567-8703
www.tectonicengineering.com

SHEET INFORMATION

SITE NUMBER:	CT03XC373	LANDLORD:	CROWN CASTLE USA 2000 CORPORATE DRIVE CANONSBURG, PA
SITE NAME:	CANDID COMMUNICATIONS	LOCAL POWER COMPANY:	CONNECTICUT LIGHT AND POWER CONTACT CUSTOMER SERVICE (800) 286-2000
SITE ADDRESS:	425 INDIAN LEDGE PARK TRUMBULL, CT 06611	APPLICANT:	SPRINT 6580 SPRINT PARKWAY OVERLAND PARK, KANSAS 66251
COUNTY:	FAIRFIELD	ENGINEER:	JAMES QUICKSELL (845) 567-8656 EXT. 2835 jquicksell@tectonicengineering.com
COORDINATES: (NAD 83)	41° 16' 23.81" N 73° 12' 47.18" W	SPRINT CM:	PETER CULBERT (603) 203-8446 Peter.Culbert@sprint.com
GROUND ELEV:	323'± AMSL	CROWN CM:	JASON D'AMICO (860) 209-0104 jason.d'amico@crowncastle.com
STRUCTURE TYPE:	MONOPOLE	AAV:	AT&T
STRUCTURE HEIGHT:	195'-0"± AGL		
STRUCTURE RAD CENTER:	166'-0"± AGL		
ZONING CLASSIFICATION:	AA		
MAP-BLOCK-LOT:	F/04/00101/000		

VICINITY MAP (NOT TO SCALE)



SHEET INDEX

SHT. NO.	SHEET DESCRIPTION
T-1	TITLE SHEET
SP-1	GENERAL NOTES
SP-2	GENERAL NOTES
A-1	SITE PLAN
A-2	ELEVATION
A-3	ENLARGED EQUIPMENT LAYOUT PLANS
A-4	ANTENNA LAYOUT PLANS
A-5	RAN WIRING DIAGRAM
A-6	CABLE DETAILS
S-1	EQUIPMENT DETAILS
S-2	EQUIPMENT SCHEMATIC DETAILS
E-1	ELECTRICAL & GROUNDING PLANS
E-2	GROUNDING DETAILS & NOTES

THIS DOCUMENT IS THE CREATION, DESIGN, PROPERTY AND COPYRIGHTED WORK OF SPRINT COMMUNICATIONS, INC. ANY DUPLICATION OR USE WITHOUT EXPRESS WRITTEN CONSENT IS STRICTLY PROHIBITED. DUPLICATION AND USE BY GOVERNMENT AGENCIES FOR THE PURPOSES OF CONDUCTING THEIR LAWFULLY AUTHORIZED REGULATORY AND ADMINISTRATIVE FUNCTIONS IS SPECIFICALLY ALLOWED.

SUBMITTALS


PROJECT NO: 7225.CT03XC373

NO	DATE	DESCRIPTION	BY
0	06/16/14	FOR COMMENT	JT
1	12/10/14	FOR CONSTRUCTION	MP
2	01/08/15	REVISED ADDRESS	RD

GENERAL NOTES

- THIS IS AN UNMANNED TELECOMMUNICATION FACILITY AND NOT FOR HUMAN HABITATION. HANDICAP ACCESS REQUIREMENTS ARE NOT REQUIRED. FACILITY HAS NO PLUMBING OR REFRIGERANTS. THIS FACILITY SHALL MEET OR EXCEED ALL FAA AND FCC REGULATOR REQUIREMENTS.
- CONTRACTOR SHALL VERIFY ALL PLANS AND EXISTING DIMENSIONS AND CONDITIONS ON THE JOB SITE AND SHALL IMMEDIATELY NOTIFY THE PROJECT OWNER'S REPRESENTATIVE IN WRITING OF DISCREPANCIES BEFORE PROCEEDING WITH THE WORK OR BE RESPONSIBLE FOR SAME.
- DEVELOPMENT AND USE OF THIS SITE WILL CONFORM TO ALL APPLICABLE CODES AND ORDINANCES.
 - 2005 STATE OF CONNECTICUT BUILDING CODE.
 - ANSI/TIA/EIA-222-F-1996.
 - NATIONAL ELECTRICAL CODE, LATEST EDITION.

AERIAL VIEW (NOT TO SCALE)



APPROVALS

THE FOLLOWING PARTIES HEREBY APPROVE AND ACCEPT THESE DOCUMENTS AND AUTHORIZE THE CONTRACTOR TO PROCEED WITH THE CONSTRUCTION DESCRIBED HEREIN. ALL DOCUMENTS ARE SUBJECT TO REVIEW BY THE LOCAL BUILDING DEPARTMENT AND MAY IMPOSE CHANGES OR MODIFICATIONS.


CONSTRUCTION: _____ DATE: _____

LEASING/
SITE ACQUISITION: _____ DATE: _____

LANDLORD/
PROPERTY OWNER: _____ DATE: _____

R.F. ENGINEER: _____ DATE: _____

DATE: 1/8/15
REVIEWED BY: TMO



PROJECT DESCRIPTION

- (1) NEW 2.5 EQUIPMENT RACK INSIDE EXIST MMBS CABINET.
- (3) NEW RFS APXVTM14-C-120 ANTENNAS.
- (3) NEW TD-RRH0x20-25 RRH.
- (1) NEW 5/8" FIBER CABLE.
- (3) NEW HANDRAIL SITE PRO1 P/N HRK-12.

SITE NUMBER:
CT03XC373
SITE NAME:
CANDID COMMUNICATIONS
SITE ADDRESS:
425 INDIAN LEDGE PARK
TRUMBULL, CT 06611

SHEET TITLE:
TITLE SHEET

SHEET NO:
T-1



DIVISION 01000—GENERAL NOTES

1. THE CONTRACTOR SHALL GIVE ALL NOTICES AND COMPLY WITH ALL LAWS, ORDINANCES, RULES, REGULATIONS AND LAWFUL ORDERS OF ANY PUBLIC AUTHORITY, MUNICIPAL AND UTILITY COMPANY SPECIFICATIONS, AND LOCAL AND STATE JURISDICTIONAL CODES BEARING ON THE PERFORMANCE OF THE WORK. THE WORK PERFORMED ON THE PROJECT AND THE MATERIALS INSTALLED SHALL BE IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS, AND ORDINANCES.
2. THE ARCHITECT/ENGINEER HAVE MADE EVERY EFFORT TO SET FORTH IN THE CONSTRUCTION AND CONTRACT DOCUMENTS THE COMPLETE SCOPE OF WORK. THE CONTRACTOR BIDDING THE JOB IS NEVERTHELESS CAUTIONED THAT MINOR OMISSIONS OR ERRORS IN THE DRAWINGS AND OR SPECIFICATIONS SHALL NOT EXCUSE SAID CONTRACTOR FROM COMPLETING THE PROJECT AND IMPROVEMENTS IN ACCORDANCE WITH THE INTENT OF THESE DOCUMENTS.
3. THE CONTRACTOR OR BIDDER SHALL BEAR THE RESPONSIBILITY OF NOTIFYING (IN WRITING) THE PROJECT OWNER'S REPRESENTATIVE OF ANY CONFLICTS, ERRORS, OR OMISSIONS PRIOR TO THE SUBMISSION OF CONTRACTOR'S PROPOSAL OR PERFORMANCE OF WORK.
4. THE SCOPE OF WORK SHALL INCLUDE FURNISHING ALL MATERIALS, EQUIPMENT, LABOR AND ALL OTHER MATERIALS AND LABOR DEEMED NECESSARY TO COMPLETE THE WORK/PROJECT AS DESCRIBED HEREIN.
5. THE CONTRACTOR SHALL VISIT THE JOB SITE PRIOR TO THE SUBMISSION OF BIDS OR PERFORMING WORK TO FAMILIARIZE HIMSELF WITH THE FIELD CONDITIONS AND TO VERIFY THAT THE PROJECT CAN BE CONSTRUCTED IN ACCORDANCE WITH THE CONTRACT DOCUMENTS.
6. ONCE THE CONTRACTOR HAS RECEIVED AND ACCEPTED THE NOTICE TO PROCEED, CONTRACTOR WILL CONTACT THE CROWN CASTLE CONSTRUCTION MANAGER OF RECORD (NOTED ON THE FIRST PAGE ON THIS CONSTRUCTION DRAWING) A MINIMUM OF 48 HOURS PRIOR TO WORK START. UPON ARRIVAL TO THE JOB SITE, CONTRACTOR CREW IS REQUIRED CALL 1-800-788-7011 TO NOTIFY THE CROWN CASTLE NOC WORK HAS BEGUN.
7. THE CONTRACTOR SHALL INSTALL ALL EQUIPMENT AND MATERIALS ACCORDING TO THE MANUFACTURER'S/VENDOR'S SPECIFICATIONS UNLESS NOTED OTHERWISE OR WHERE LOCAL CODES OR ORDINANCES TAKE PRECEDENCE.
8. THE CONTRACTOR SHALL PROVIDE A FULL SET OF CONSTRUCTION DOCUMENTS AT THE SITE UPDATED WITH THE LATEST REVISIONS AND ADDENDUMS OR CLARIFICATIONS AVAILABLE FOR THE USE BY ALL PERSONNEL INVOLVED WITH THE PROJECT.
9. THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE PROJECT DESCRIBED HEREIN. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR ALL CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES AND PROCEDURES AND FOR COORDINATING ALL PORTIONS OF THE WORK UNDER THE CONTRACT.
10. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL PERMITS AND INSPECTIONS WHICH MAY BE REQUIRED FOR THE WORK BY THE ARCHITECT/ENGINEER, THE STATE, COUNTY OR LOCAL GOVERNMENT AUTHORITY.
11. THE CONTRACTOR SHALL MAKE NECESSARY PROVISIONS TO PROTECT EXISTING IMPROVEMENTS, EASEMENTS, PAVING, CURBING, ETC. DURING CONSTRUCTION. UPON COMPLETION OF WORK, THE CONTRACTOR SHALL REPAIR ANY DAMAGE THAT MAY HAVE OCCURRED DUE TO CONSTRUCTION ON OR ABOUT THE PROPERTY.
12. THE CONTRACTOR SHALL KEEP THE GENERAL WORK AREA CLEAN AND HAZARD FREE DURING CONSTRUCTION AND DISPOSE OF ALL DIRT, DEBRIS, RUBBISH AND REMOVE EQUIPMENT NOT SPECIFIED AS REMAINING ON THE PROPERTY. PREMISES SHALL BE LEFT IN CLEAN CONDITION AND FREE FROM PAINT SPOTS, DUST, OR SMUDGES OF ANY NATURE.
13. THE CONTRACTOR SHALL COMPLY WITH ALL PERTINENT SECTIONS OF THE BASIC STATE BUILDING CODE, LATEST EDITION, AND ALL OSHA REQUIREMENTS AS THEY APPLY TO THIS PROJECT. ALL EXISTING ACTIVE SEWER, WATER, GAS, ELECTRIC, AND OTHER UTILITIES WHERE ENCOUNTERED IN THE WORK SHALL BE PROTECTED AT ALL TIMES, AND WHERE REQUIRED FOR THE PROPER EXECUTION OF THE WORK SHALL BE RELOCATED AS DIRECTED BY THE ARCHITECT/ENGINEER. EXTREME CAUTION SHOULD BE USED BY THE CONTRACTOR WHEN EXCAVATING OR PIER DRILLING AROUND OR NEAR UTILITIES. THE CONTRACTOR SHALL PROVIDE SAFETY TRAINING FOR THE WORKING CREW. THIS WILL INCLUDE BUT NOT LIMITED TO A) FALL PROTECTION, B) CONFINED SPACE, C) ELECTRICAL SAFETY, D) TRENCHING AND EXCAVATION OF ALL EXISTING INACTIVE SEWER, WATER, GAS, ELECTRIC AND OTHER UTILITIES WHICH INTERFERE WITH THE EXECUTION OF THE WORK SHALL BE REMOVED AND OR CAPPED, PLUGGED OR OTHERWISE DISCONTINUED AT THE POINTS WHICH WILL NOT INTERFERE WITH THE EXECUTION OF THE WORK SUBJECT TO THE APPROVAL OF THE ARCHITECT/ENGINEER.
14. THE CONTRACTOR SHALL NOTIFY THE PROJECT OWNER'S REPRESENTATIVE IN WRITING WHERE A CONFLICT OCCURS ON ANY OF THE CONTRACT DOCUMENTS. THE CONTRACTOR IS NOT TO ORDER MATERIAL OR CONSTRUCT ANY PORTION OF THE WORK THAT IS IN CONFLICT UNTIL CONFLICT IS RESOLVED BY THE LESSEE/LICENSEE REPRESENTATIVE.
15. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS, ELEVATIONS, PROPERTY LINES, ETC. ON THE JOB.
16. THE CONTRACTOR SHALL NOTIFY THE THE RF ENGINEER FOR ANTENNA AZIMUTH VERIFICATION (DURING ANTENNA INSTALLATION) PRIOR TO CONDUCTING SWEEP TESTS.
17. THE CONTRACTOR SHALL SUBMIT AT THE END OF THE PROJECT A COMPLETE SET OF AS-BUILT DRAWINGS TO THE CLIENT REPRESENTATIVE.

18. REFER TO: CONSTRUCTION STANDARDS—SPRINT DOCUMENT EXHIBIT A—STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES REV. 4.0— 02.15.2011.DOCM.
19. REFER TO: WEATHER PROOFING SPECS: EXCERPT EXH A—WIHRPRF—STD CONSTR SPECS...157201110421855492.DOCM.
20. REFER TO: COLOR CODING—SPRINT NEXTEL ANT AND LINE COLOR CODING (DRAFT) V3 09-08-11.PDF
21. REFER TO LATEST DOCUMENTATION REVISION.

DIVISION 03000—CONCRETE

- 1.03 APPLICABLE STANDARDS (USE LATEST EDITIONS)
 - A. AC1-301 — SPECIFICATIONS FOR STRUCTURAL CONCRETE FOR BUILDINGS.
 - B. AC1-347 GUIDE TO FORM WORK FOR CONCRETE.
 - C. ASTM C33— CONCRETE AGGREGATE
 - D. ASTM C94 — READY MIXED CONCRETE e. ASTM C150 — PORTLAND CEMENT.
 - E. ASTM C260 — AIR-ENTRAINING ADMIXTURES FOR CONCRETE
 - F. ASTM C309— LIQUID MEMBRANE FORMING COMPOUNDS FOR CURING CONCRETE.
 - H. ASTM C494 — CHEMICAL ADMIXTURES FOR CONCRETE
 - I. ASTM A615— DEFORMED AND PLAIN BILLET—STEEL BARS FOR CONCRETE REINFORCEMENT
 - J. ASTM A185— STEEL WELDED WIRE FABRIC (PLAIN) FOR CONCRETE REINFORCEMENT
- 1.04 QUALITY ASSURANCE

CONCRETE MATERIALS AND OPERATIONS SHALL BE TESTED AND INSPECTED BY THE ARCHITECT/ENGINEER AS DIRECTED BY THE CLIENT'S REPRESENTATIVE.

 - 3.04 SURFACE FINISHES
 - A. SURFACES AGAINST WHICH BACKFILL OR CONCRETE SHALL BE PLACED REQUIRE NO TREATMENT EXCEPT REPAIR OF DEFECTIVE AREAS.
 - B. SURFACES THAT WILL BE PERMANENTLY EXPOSED SHALL PRESENT A UNIFORM FINISH PROVIDED BY THE REMOVAL OF FINIS AND THE FILLING HOLES AND OTHER IRREGULARITIES WITH DRY PACK GROUT, OR BY SACKING WITH UTILITY OR ORDINARY GROUT.
 - C. SURFACES THAT WOULD NORMALLY BE LEVEL AND WHICH WILL BE PERMANENTLY EXPOSED TO THE WEATHER SHALL BE SLOPED FOR DRAINAGE. UNLESS ENGINEER'S DESIGN DRAWING SPECIFIES A HORIZONTAL SURFACE OR SURFACES SUCH AS STAIR TREADS, WALLS, CURBS, AND PARAPETS SHALL BE SLOPED APPROXIMATELY 1/4" PER FOOT.
 - D. SURFACES THAT WILL BE COVERED BY BACKFILL OR CONCRETE SHALL BE SMOOTH SCREENED.
 - E. EXPOSED SLAB SURFACES SHALL BE CONSOLIDATED, SCREENED, FLOATED, AND STEEL TROWELED. HAND OR POWER-DRIVEN EQUIPMENT MAY BE USED FOR FLOATING. FLOATING SHALL BE STARTED AS SOON AS THE SCREENED SURFACE HAS ATTAINED A STIFFNESS TO PERMIT FINISHING OPERATIONS. OPERATIONS. ALL EDGES MUST HAVE A 3/4" CHAMFER.

1.04 QUALITY ASSURANCE CONCRETE MATERIALS AND OPERATIONS SHALL BE TESTED AND INSPECTED BY THE ENGINEER.
- 3.05 PATCHING

THE CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY UPON REMOVAL OF THE FORMS TO OBSERVE CONCRETE SURFACE CONDITIONS. IMPERFECTIONS SHALL BE PATCHED ACCORDING TO THE ENGINEER'S DIRECTION.
- 3.06 DEFECTIVE CONCRETE

THE CONTRACTOR SHALL NOTIFY OR REPLACE CONCRETE NOT CONFORMING TO REQUIRED LEVELS AND LINES, DETAILS, AND ELEVATIONS AS SPECIFIED IN ACI 301.
- 3.07 PROTECTION
 - A. IMMEDIATELY AFTER PLACEMENT. THE CONTRACTOR SHALL PROTECT THE CONCRETE FROM PREMATURE DRYING, EXCESSIVELY HOT OR COLD TEMPERATURES, AND MECHANICAL INJURY. FINISHED WORK SHALL BE PROTECTED.
 - B. CONCRETE SHALL BE MAINTAINED WITH MINIMAL MOISTURE LOSS AT RELATIVELY CONSTANT TEMPERATURE FOR PERIOD NECESSARY FOR HYDRATION OF CEMENT AND HARDENING OF CONCRETE.
 - C. ALL CONCRETE SHALL BE WATER CURED PER ACCEPTABLE PRACTICES SPECIFIED BY ACI CODE (LATEST EDITION)

DIVISION 05000 — METALS

- PART 1 — GENERAL
 - 1.01 WORK INCLUDED
 - A. THE WORK CONSISTS OF THE FABRICATION AND INSTALLATION OF ALL MATERIALS TO BE FURNISHED. AND WITHOUT LIMITING THE GENERALITY THEREOF, INCLUDING ALL EQUIPMENT, LABOR AND SERVICES REQUIRED FOR ALL STRUCTURAL STEEL WORK AND ALL ITEMS INCIDENTAL AS SPECIFIED AND AS SHOWN ON THE DRAWINGS:
 1. STEEL FRAMING INCLUDING BEAMS, ANGLES, CHANNELS AND PLATES.
 2. WELDING AND BOLTING OF ATTACHMENTS.
 - 1.02 REFERENCE STANDARDS
 - A. THE WORK SHALL CONFORM TO THE CODES AND STANDARDS OF THE FOLLOWING AGENCIES AS FURTHER CITED HEREIN:
 1. ASTM: AMERICAN SOCIETY FOR TESTING AND MATERIALS AS PUBLISHED IN "COMPILATION OF ASTM STANDARDS IN BUILDING CODES" OR LATEST EDITION.
 2. AWS: AMERICAN WELDING SOCIETY CODE OR LATEST EDITION.
 3. AISC: AMERICAN INSTITUTE OF STEEL CONSTRUCTION, "SPECIFICATION FOR THE DESIGN, FABRICATION AND ERECTION OF STRUCTURAL STEEL FOR BUILDINGS" (LATEST EDITION).
 - PART 2 — PRODUCTS
 - 2.01 MATERIALS
 - A. STRUCTURAL STEEL: SHALL COMPLY WITH THE REQUIREMENTS OF ASTM A36 AND A992 FOR STRUCTURAL STEEL.

ALL PROPOSED STRUCTURAL STEEL SHALL BE FABRICATED AND ERECTED IN ACCORDANCE WITH AISC CODE AND ASTM SPECIFICATIONS (LATEST EDITION) ALL NEW STEEL SHALL CONFORM TO THE FOLLOWING.

 1. STRUCTURAL WIDE FLANGE: ASTM A992 Fy=50KSI.
 2. MISCELLANEOUS STEEL (PLATES, CHANNELS, ANGLES, ETC): ASTM A36 (Fy=36KSI).
 3. STRUCTURAL TUBING: ASTM A500 Gr. B (Fy=46KSI).
 4. STEEL PIPE: ASTM A53 Gr B (Fy=35KSI).
 - 2.02 WELDING
 - A. ALL WELDING SHALL BE DONE BY CERTIFIED WELDERS. CERTIFICATION DOCUMENTS SHALL BE MADE AVAILABLE FOR ENGINEER'S AND/OR OWNER'S REVIEW IF REQUESTED.
 - B. WELDING ELECTRODES FOR MANUAL SHIELDED METAL ARC WELDING SHALL CONFORM TO ASTM 1-233, E70 SERIES. BARE ELECTRODES AND GRANULAR FLUX USED IN THE SUBMERGED ARC PROCESS SHALL CONFORM TO AISC SPECIFICATIONS.
 - C. FIELD WELDING SHALL BE DONE AS PER AWS D1.1 REQUIREMENTS VISUAL INSPECTION IS ACCEPTABLE.
 - D. STUD WELDING SHALL BE ACCOMPLISHED BY CAPACITOR DISCHARGE (CD) WELDING TECHNIQUE USING CAPACITOR DISCHARGE STUD WELDER.
 - E. PROVIDE STUD FASTENERS OF MATERIALS AND SIZES SHOWN ON DRAWINGS OR AS RECOMMENDED BY THE MANUFACTURER FOR STRUCTURAL LOADINGS REQUIRED.
 - F. FOLLOW MANUFACTURERS SPECIFICATIONS AND INSTRUCTIONS TO PROPERLY SELECT AND INSTALL STUD WELDS.
 - 2.03 BOLTING
 - A. BOLTS SHALL BE CONFORMING TO ASTM A35 HIGH STRENGTH HOT DIP GALVANIZED WITH ASTM A153 HEAVY HEX TYPE NUTS.
 - B. BOLTS SHALL BE 3/4" (MINIMUM) CONFORMING TO ASTM A325, HOT DIP GALVANIZED, ASTM A153 NUTS SHALL BE HEAVY HEX TYPE.
 - C. ALL CONNECTIONS SHALL BE 2 BOLTS MINIMUM.
 - D. EXCEPT WHERE SHOWN, ALL BEAM TO BEAM AND BEAM TO COLUMN CONNECTIONS TO BE DOUBLE ANGLED CONNECTIONS WITH HIGH STRENGTH BOLTS (THREADS EXCLUDED FROM SHEAR PLANE) AND HARDENED WASHERS.
 - E. STANDARD, OVERSIZED OR HORIZONTAL SHORT SLOTTED HOLES.
 - F. SNUG-TIGHT STRENGTH BEARING BOLTS MAY BE USED IN STANDARD HOLES CONFORMING TO ACIS, USING THE TURN OF THE NUT METHOD.
 - H. FULLY-TENSIONED HIGH STRENGTH (SLIP CRITICAL) SHALL BE USED IN OVERSIZED SLOT HOLES (RESPECTIVE OF SLOT ORIENTATION).
 - I. ALL BRACED CONNECTION, MOMENT CONNECTION AND CONNECTIONS NOTED AS "SLIP CRITICAL" SHALL BE BE SLIP CRITICAL JOINTS WITH CLASS A SURFACE CONDITIONS, UNLESS OTHERWISE NOTED.
 - J. EPOXY ANCHOR ASSEMBLIES SHALL BE AS MANUFACTURED BY HILTI OR ENGINEER APPROVED EQUAL, AS FOLLOWS:

BASE MATERIAL	ANCHOR SYSTEM
CONCRETE	HILTI HIT-HY 200
HOLLOW & GROUTED CMU OR BRICK	HILTI HIT-HY 70
- 2.04 FABRICATION
 - A. FABRICATION OF STEEL SHALL CONFORM TO THE AISC AND AWS

- 2.05 FINISH
 - A. STRUCTURAL STEEL EXPOSED TO WEATHER SHALL BE HOT-DIP GALVANIZED AFTER FABRICATION IN ACCORDANCE WITH ASTM A123. (LATEST EDITION) UNLESS OTHERWISE NOTED.
- 2.06 PROTECTION
 - A. UPON COMPLETION OF ERECTION, INSPECT ALL GALVANIZED STEEL AND PAINT ANY FIELD CUTS, WELDS OR GALVANIZED BREAKS WITH (2) COATS OF ZINC-RICH COLD GALVANIZING PAINT.
- PART 3 — ERECTION
 - A. PROVIDE ALL ERECTION, EQUIPMENT, BRACING, PLANKING, FIELD BOLTS, NUTS, WASHERS, DRIFT PINS, AND SIMILAR MATERIALS WHICH DO NOT FORM A PART OF THE COMPLETED CONSTRUCTION, BUT ARE NECESSARY FOR ITS PROPER ERECTION.
 - B. ERECT AND ANCHOR ALL STRUCTURAL STEEL IN ACCORDANCE WITH AISC REFERENCE STANDARDS. ALL WORK SHALL BE ACCURATELY SET TO ESTABLISHED SUITABLE ATTACHMENTS TO THE CONSTRUCTION OF THE BUILDING
 - C. TEMPORARY BRACING, GUYING, AND SUPPORT SHALL BE PROVIDED TO KEEP THE STRUCTURE SET AND ALIGNED AT ALL TIMES DURING CONSTRUCTION, AND TO PREVENT DANGER TO PERSONS AND PROPERTY. CHECK ALL TEMPORARY LOADS AND STAY WITHIN SAFE CAPACITY OF ALL BUILDING COMPONENTS.



2.5 EQUIPMENT DEPLOYMENT
6580 SPRINT PARKWAY
OVERLAND PARK, KANSAS 66251




PLANNING
ENGINEERING
SURVEYING
CONSTRUCTION MANAGEMENT

Tectonic Engineering & Surveying Consultants P.C.

1279 Route 300
Newburgh, NY 12550
Phone: (845) 567-6656
Fax: (845) 567-8703
www.tectonicengineering.com

THIS DOCUMENT IS THE CREATION, DESIGN, PROPERTY AND COPYRIGHTED WORK OF SPRINT COMMUNICATIONS, INC. ANY DUPLICATION OR USE WITHOUT EXPRESS WRITTEN CONSENT IS STRICTLY PROHIBITED. DUPLICATION AND USE BY GOVERNMENT AGENCIES FOR THE PURPOSES OF CONDUCTING THEIR LAWFULLY AUTHORIZED REGULATORY AND ADMINISTRATIVE FUNCTIONS IS SPECIFICALLY ALLOWED.

SUBMITTALS			
PROJECT NO: 7225.CT03XC373			
NO	DATE	DESCRIPTION	BY
0	06/16/14	FOR COMMENT	JT
1	12/10/14	FOR CONSTRUCTION	MP
2	01/08/15	REVISED ADDRESS	RD

DATE	REVIEWED BY
1/8/15	JMQ



SITE NUMBER:
CT03XC373

SITE NAME:
CANDID COMMUNICATIONS

SITE ADDRESS:
425 INDIAN LEDGE PARK
TRUMBULL, CT 06611

SHEET TITLE:
GENERAL NOTES

SHEET NO:
SP-1

Sprint
 2.5 EQUIPMENT DEPLOYMENT
 6580 SPRINT PARKWAY
 OVERLAND PARK, KANSAS 66251

CROWN CASTLE

TECTONIC • PLANNING
 • ENGINEERING
 • SURVEYING
 • CONSTRUCTION
 • MANAGEMENT
TECTONIC Engineering & Surveying
 Consultants P.C.
 1279 Route 300
 Newburgh, NY 12550
 Phone: (845) 567-6656
 Fax: (845) 567-8703
 www.tectonicengineering.com


THIS DOCUMENT IS THE CREATION, DESIGN, PROPERTY AND COPYRIGHTED WORK OF SPRINT COMMUNICATIONS, INC. ANY DUPLICATION OR USE WITHOUT EXPRESS WRITTEN CONSENT IS STRICTLY PROHIBITED. DUPLICATION AND USE BY GOVERNMENT AGENCIES FOR THE PURPOSES OF CONDUCTING THEIR LAWFULLY AUTHORIZED REGULATORY AND ADMINISTRATIVE FUNCTIONS IS SPECIFICALLY ALLOWED.

SUBMITTALS

PROJECT NO: 7225.CT03XC373

NO	DATE	DESCRIPTION	BY
0	06/16/14	FOR COMMENT	JT
1	12/10/14	FOR CONSTRUCTION	MP
2	01/08/15	REVISED ADDRESS	RD

DATE	REVIEWED BY
1/8/15	JMQ




SITE NUMBER:
 CT03XC373
 SITE NAME:
 CANDID COMMUNICATIONS
 SITE ADDRESS:
 425 INDIAN LEDGE PARK
 TRUMBULL, CT 06611

SHEET TITLE:
 SITE PLAN

SHEET NO:
 A-1

NORTH NOTE:
 NORTH SHOWN HAS BEEN ESTABLISHED USING THE USGS QUADRANGLE 7.5 MINUTE MAPS AND IS APPROXIMATE. VERIFY TRUE NORTH PRIOR TO INSTALLATION OF ANTENNAS.





SITE PLAN
 SCALE: 1/4" = 1'-0"



THE EXISTING MONOPOLE SHALL BE ANALYZED BY A PROFESSIONAL ENGINEER LICENSED IN THE STATE OF CONNECTICUT (TO BE COORDINATED BY OTHERS).

THE EXISTING MOUNT HAS BEEN ANALYZED BY TECTONIC ENGINEERING AND FOUND TO BE ADEQUATE TO SUPPORT THE PROPOSED SPRINT UPGRADE ONCE THE PROPOSED MODIFICATIONS HAVE BEEN COMPLETED AS DETAILED IN THE STRUCTURAL ANALYSIS EVALUATION LETTER DATED 12/10/14.



NOTE:
SPRINT MUST REMOVE ALL NEXTEL EQUIPMENT AND ASSOCIATED CABLES FROM THE TOWER PRIOR TO INSTALLATION.

1
A-2
ELEVATION
SCALE: 3/32" = 1'-0"

Sprint
2.5 EQUIPMENT DEPLOYMENT
6580 SPRINT PARKWAY
OVERLAND PARK, KANSAS 66251

CROWN CASTLE

TECTONIC
PLANNING
ENGINEERING
SURVEYING
CONSTRUCTION MANAGEMENT
TECTONIC Engineering & Surveying Consultants P.C.
1279 Route 300
Newburgh, NY 12550
Phone: (845) 567-6656
Fax: (845) 567-8703
www.tectonicengineering.com


THIS DOCUMENT IS THE CREATION, DESIGN, PROPERTY AND COPYRIGHTED WORK OF SPRINT COMMUNICATIONS, INC. ANY DUPLICATION OR USE WITHOUT EXPRESS WRITTEN CONSENT IS STRICTLY PROHIBITED. DUPLICATION AND USE BY GOVERNMENT AGENCIES FOR THE PURPOSES OF CONDUCTING THEIR LAWFULLY AUTHORIZED REGULATORY AND ADMINISTRATIVE FUNCTIONS IS SPECIFICALLY ALLOWED.

SUBMITTALS

PROJECT NO: 7225.CT03XC373

NO	DATE	DESCRIPTION	BY
0	06/16/14	FOR COMMENT	JT
1	12/10/14	FOR CONSTRUCTION	MP
2	01/08/15	REVISED ADDRESS	RD

DATE: 1/8/15
REVIEWED BY: JMQ




SITE NUMBER:
CT03XC373
SITE NAME:
CANDID COMMUNICATIONS
SITE ADDRESS:
425 INDIAN LEDGE PARK
TRUMBULL, CT 06611

SHEET TITLE:
ELEVATION

SHEET NO:
A-2


NORTH NOTE:
 NORTH SHOWN HAS BEEN ESTABLISHED USING THE USGS QUADRANGLE 7.5 MINUTE MAPS AND IS APPROXIMATE. VERIFY TRUE NORTH PRIOR TO INSTALLATION OF ANTENNAS.



1 ENLARGED EQUIP. LAYOUT PLAN (EXIST)
 SCALE: 3/4" = 1'-0"



3 EXIST EQUIPMENT PAD
 SCALE: NTS



2 ENLARGED EQUIP. LAYOUT PLAN (FINAL)
 SCALE: 3/4" = 1'-0"



4 EXIST FIBER DISTRIBUTION BOX
 SCALE: NTS

Sprint
 2.5 EQUIPMENT DEPLOYMENT
 6580 SPRINT PARKWAY
 OVERLAND PARK, KANSAS 66251


CROWN CASTLE

TECTONIC ENGINEERING & SURVEYING CONSULTANTS P.C.
 1279 Route 300
 Newburgh, NY 12550
 Phone: (845) 567-6656
 Fax: (845) 567-8703
 www.tectonicengineering.com

THIS DOCUMENT IS THE CREATION, DESIGN, PROPERTY AND COPYRIGHTED WORK OF SPRINT COMMUNICATIONS, INC. ANY DUPLICATION OR USE WITHOUT EXPRESS WRITTEN CONSENT IS STRICTLY PROHIBITED. DUPLICATION AND USE BY GOVERNMENT AGENCIES FOR THE PURPOSES OF CONDUCTING THEIR LAWFULLY AUTHORIZED REGULATORY AND ADMINISTRATIVE FUNCTIONS IS SPECIFICALLY ALLOWED.

SUBMITTALS			
PROJECT NO: 7225.CT03XC373			
NO	DATE	DESCRIPTION	BY
0	06/16/14	FOR COMMENT	JT
1	12/10/14	FOR CONSTRUCTION	MP
2	01/08/15	REVISED ADDRESS	RD

DATE: 1/8/15
 REVIEWED BY: JMA




SITE NUMBER:
CT03XC373

SITE NAME:
CANDID COMMUNICATIONS


SITE ADDRESS:
**425 INDIAN LEDGE PARK
 TRUMBULL, CT 06611**

SHEET TITLE:
**ENLARGED EQUIPMENT
 LAYOUT PLANS**

SHEET NO:
A-3




1 ANTENNA LAYOUT PLAN (EXIST)
A-4 SCALE: 3/8" = 1'-0"




THE EXISTING MONOPOLE SHALL BE ANALYZED BY A PROFESSIONAL ENGINEER LICENSED IN THE STATE OF CONNECTICUT (TO BE COORDINATED BY OTHERS).

THE EXISTING MOUNT HAS BEEN ANALYZED BY TECTONIC ENGINEERING AND FOUND TO BE ADEQUATE TO SUPPORT THE PROPOSED SPRINT UPGRADE ONCE THE PROPOSED MODIFICATIONS HAVE BEEN COMPLETED AS DETAILED IN THE STRUCTURAL ANALYSIS EVALUATION LETTER DATED 12/10/14.



3 RRH MOUNTING DETAIL
A-4 SCALE: 1 1/2" = 1'-0"



2 ANTENNA LAYOUT PLAN (FINAL)
A-4 SCALE: 3/8" = 1'-0"

ANTENNA DATA

Status	Exist	Proposed
Antenna Manufacturer	RFS-CEL WAVE	RFS-CEL WAVE
Antenna Model Number	APXVSP18C-A20	APXVTM14-C-120
Number of Antennas	3	3
Antenna RAD Center	166'	166'
Antenna Azimuth	20/180/260	20/180/260
Antenna RRH Model Number	1900MHz/800MHz RRHS	TD-RRHx20-25
Number of RRH	6	3

Sprint
2.5 EQUIPMENT DEPLOYMENT
6580 SPRINT PARKWAY
OVERLAND PARK, KANSAS 66251

CROWN CASTLE

TECTONIC ENGINEERING & SURVEYING CONSULTANTS P.C.
1279 Route 300
Newburgh, NY 12550
Phone: (845) 567-6656
Fax: (845) 567-8703
www.tectonicengineering.com

THIS DOCUMENT IS THE CREATION, DESIGN, PROPERTY AND COPYRIGHTED WORK OF SPRINT COMMUNICATIONS, INC. ANY DUPLICATION OR USE WITHOUT EXPRESS WRITTEN CONSENT IS STRICTLY PROHIBITED. DUPLICATION AND USE BY GOVERNMENT AGENCIES FOR THE PURPOSES OF CONDUCTING THEIR LAWFULLY AUTHORIZED REGULATORY AND ADMINISTRATIVE FUNCTIONS IS SPECIFICALLY ALLOWED.

SUBMITTALS


PROJECT NO: 7225.CT03XC373

NO	DATE	DESCRIPTION	BY
0	06/16/14	FOR COMMENT	JT
1	12/10/14	FOR CONSTRUCTION	MP
2	01/08/15	REVISED ADDRESS	RD


DATE	REVIEWED BY
1/8/15	JMQ




SITE NUMBER: CT03XC373
SITE NAME: CANDID COMMUNICATIONS
SITE ADDRESS: 425 INDIAN LEDGE PARK TRUMBULL, CT 06611
SHEET TITLE: ANTENNA LAYOUT PLANS
SHEET NO: A-4



1 2.5 CABLE COLOR CODING
A-5 SCALE: N.T.S.



2 RRH CONNECTIVITY
A-5 SCALE: N.T.S.



3 RAN WIRING
A-5 SCALE: N.T.S.



4 CABLE SCENARIO
A-5 SCALE: N.T.S.

Sprint
2.5 EQUIPMENT DEPLOYMENT
6580 SPRINT PARKWAY
OVERLAND PARK, KANSAS 66251

CROWN CASTLE


TECTONIC ENGINEERING & SURVEYING CONSULTANTS P.C.
1279 Route 300
Newburgh, NY 12550
Phone: (845) 567-6656
Fax: (845) 567-8703
www.tectonicengineering.com

THIS DOCUMENT IS THE CREATION, DESIGN, PROPERTY AND COPYRIGHTED WORK OF SPRINT COMMUNICATIONS, INC. ANY DUPLICATION OR USE WITHOUT EXPRESS WRITTEN CONSENT IS STRICTLY PROHIBITED. DUPLICATION AND USE BY GOVERNMENT AGENCIES FOR THE PURPOSES OF CONDUCTING THEIR LAWFULLY AUTHORIZED REGULATORY AND ADMINISTRATIVE FUNCTIONS IS SPECIFICALLY ALLOWED.

SUBMITTALS

NO.	DATE	DESCRIPTION	BY
0	06/16/14	FOR COMMENT	JT
1	12/10/14	FOR CONSTRUCTION	MP
2	01/08/15	REVISED ADDRESS	RD

DATE	REVIEWED BY
1/8/15	JMG



SITE NUMBER:
CT03XC373
SITE NAME:
CANDID COMMUNICATIONS
SITE ADDRESS:
425 INDIAN LEDGE PARK
TRUMBULL, CT 06611

SHEET TITLE:
RAN WIRING DIAGRAM

SHEET NO:
A-5


THIS DOCUMENT IS THE CREATION, DESIGN, PROPERTY AND COPYRIGHTED WORK OF SPRINT COMMUNICATIONS, INC. ANY DUPLICATION OR USE WITHOUT EXPRESS WRITTEN CONSENT IS STRICTLY PROHIBITED. DUPLICATION AND USE BY GOVERNMENT AGENCIES FOR THE PURPOSES OF CONDUCTING THEIR LAWFULLY AUTHORIZED REGULATORY AND ADMINISTRATIVE FUNCTIONS IS SPECIFICALLY ALLOWED.

SUBMITTALS

PROJECT NO: 7225.CT03XC373

NO	DATE	DESCRIPTION	BY
0	06/16/14	FOR COMMENT	JT
1	12/10/14	FOR CONSTRUCTION	MP
2	01/08/15	REVISED ADDRESS	RD

DATE	REVIEWED BY
1/8/15	JMG



SITE NUMBER:
CT03XC373

SITE NAME:
CANDID COMMUNICATIONS

SITE ADDRESS:
425 INDIAN LEDGE PARK
TRUMBULL, CT 06611


SHEET TITLE:
CABLE DETAILS

SHEET NO:
A-6

IMPORTANT! LINE UP WHITE MARKINGS ON JUMPER AND RISER IP-MPO CONNECTOR. PUSH THE WHITE MARK ON THE JUMPER CONNECTOR FLUSH AGAINST THE RED SEAL ON THE RISER CONNECTION




IMPORTANT! ROTATE THE BAYONET HOUSING CLOCKWISE UNTIL A CLICK SOUND IS HEARD TO ENSURE A GOOD CONNECTION




1 HYBRIFLEX RISER/JUMPER CONNECTION DETAILS
 A-6 SCALE: N.T.S.

TRUNK-LINE TO JUMPER CONNECTION (MPO) TO BE INSTALLED PER MANUFACTURER REQUIREMENTS. SEE DETAIL.




2 2.5 HYBRID CABLE W/FIBER & DC FEEDERS
 A-6 SCALE: N.T.S.



3 FIBER ONLY TRUNK LINES
 A-6 SCALE: N.T.S.

SPECIAL NOTES: CABLE MARKINGS AT RAD CENTER AND ALL WALL/BLDG. PENETRATIONS

- ALL COLOR CODE TAPE SHALL BE 3M-35 AND SHALL BE INSTALLED USING A MINIMUM OF (3) WRAPS OF TAPE.
- ALL COLOR BANDS INSTALLED AT THE TOWER TOP SHALL BE A MINIMUM OF 3" WIDE AND SHALL HAVE A MINIMUM OF 3/4" OF SPACING BETWEEN EACH COLOR.
- ALL COLOR BANDS INSTALLED AT OR NEAR THE GROUND MAY BE ONLY 3/4" WIDE. EACH TOP-JUMPER SHALL BE COLOR CODED WITH (1) SET OF 3" WIDE BANDS.
- EACH MAIN COAX SHALL BE COLOR CODED WITH (1) SET OF 3" BANDS NEAR THE TOP-JUMPER CONNECTION AND WITH 3/4" COLOR BANDS JUST PRIOR TO ENTERING THE BTS OR TRANSMITTER BUILDING.
- ALL BOTTOM JUMPERS SHALL BE COLOR CODED WITH (1) SET OF 3/4" BANDS ON EACH END OF THE BOTTOM JUMPER.
- ALL COLOR CODES SHALL BE INSTALLED SO AS TO ALIGN NEATLY WITH ONE ANOTHER FROM SIDE-TO-SIDE.
- EACH COLOR BAND SHALL HAVE A MINIMUM OF (3) WRAPS AND SHALL BE NEATLY TRIMMED AND SMOOTHED OUT AS TO AVOID UNRAVELING.
- X-POLE ANTENNAS SHOULD USE "XX-1" FOR THE "+45" PORT, "XX-2" FOR THE "-45" PORT.
- COLOR BAND #4 REFERS TO THE FREQUENCY BAND: ORANGE=850, VIOLET=1900. USED ON JUMPERS ONLY.
- RF FEEDLINE SHALL BE IDENTIFIED WITH A METAL TAG (STAINLESS OR BRASS) AND STAMPED WITH THE SECTOR, ANTENNA POSITION, AND CABLE NUMBER.
- ANTENNAS MUST BE IDENTIFIED, USING THE SECTOR LETTER AND ANTENNA NUMBER, WITH A BLACK MARKER PRIOR TO INSTALLATION.




CABINET FRONT
9928 MMBTS MODULAR CELL

SPECIFICATIONS:

HEIGHT: 70"
WIDTH: 35"
DEPTH: 37.8"
WEIGHT: 1090 LBS.

1 (EXIST) MMBTS CABINET
S-1 SCALE: 1" = 1'-0"




ANDREW 60ECv2


SPECIFICATIONS:

HEIGHT: 60"
WIDTH: 31"
DEPTH: 30"
WEIGHT: 2430 LBS.



2 (EXIST) BATTERY CABINET
S-1 SCALE: 1" = 1'-0"



3 (EXIST) ANTENNA DETAILS
S-1 SCALE: 3/4"=1'-0"




4 (PROPOSED) ANTENNA DETAIL
S-1 SCALE: 3/4"=1'-0"




TYPE: 1900 MHz 4x45W
MODEL #: RRH 1900 4X45 65MHz
HEIGHT: 25.0"
WIDTH: 11.1"
DEPTH: 11.4"
WEIGHT: ±60 LBS.

5 (EXIST) RRH DETAILS
S-1 SCALE: 1 1/2"=1'-0"



TYPE: 800 MHz 2x50W
MODEL #: FD-RRH-2x50-800
HEIGHT: 19.7"
WIDTH: 13"
DEPTH: 10.8"
WEIGHT: ±53 LBS



TYPE: 2.5 RRH
MODEL #: TD-RRH8x20-25
HEIGHT: 26.1"
WIDTH: 18.6"
DEPTH: 6.7"
WEIGHT: ±70 LBS

6 (PROPOSED) RRH DETAIL
S-1 SCALE: N.T.S.

Sprint

2.5 EQUIPMENT DEPLOYMENT
6580 SPRINT PARKWAY
OVERLAND PARK, KANSAS 66251

CROWN CASTLE

TECTONIC ENGINEERING & SURVEYING CONSULTANTS P.C.

1279 Route 300
Newburgh, NY 12550
Phone: (845) 567-6656
Fax: (845) 567-8703
www.tectonicengineering.com

THIS DOCUMENT IS THE CREATION, DESIGN, PROPERTY AND COPYRIGHTED WORK OF SPRINT COMMUNICATIONS, INC. ANY DUPLICATION OR USE WITHOUT EXPRESS WRITTEN CONSENT IS STRICTLY PROHIBITED. DUPLICATION AND USE BY GOVERNMENT AGENCIES FOR THE PURPOSES OF CONDUCTING THEIR LAWFULLY AUTHORIZED REGULATORY AND ADMINISTRATIVE FUNCTIONS IS SPECIFICALLY ALLOWED.

SUBMITTALS

PROJECT NO: 7225.CT03XC373

NO	DATE	DESCRIPTION	BY
0	06/16/14	FOR COMMENT	JT
1	12/10/14	FOR CONSTRUCTION	MP
2	01/08/15	REVISED ADDRESS	RD

DATE	REVIEWED BY
1/8/15	JMQ



SITE NUMBER:
CT03XC373


SITE NAME:
CANDID COMMUNICATIONS

SITE ADDRESS:
425 INDIAN LEDGE PARK
TRUMBULL, CT 06611

SHEET TITLE:
EQUIPMENT DETAILS

SHEET NO:
S-1

NOTE:
LOCATIONS SHOWN FOR
INSTALLATION OF NEW
EQUIPMENT IN EXISTING
CABINET ARE APPROXIMATE.
ACTUAL SPACE AVAILABLE
TO BE VERIFIED IN FIELD
ON A SITE BY SITE BASIS.




EXIST GROUND
BAR TO BE UTILIZED

INSTALL NEW 2.5
EQUIPMENT IN EXIST MMBTS
CABINET INCLUDING BUT
NOT LIMITED TO BASE BAND
UNIT, CELL SITE ROUTER
AND SURGE ARRESTORS.
GROUND EQUIPMENT TO
EXIST INTERIOR CABINET
GROUND BAR

FRONT ELEVATION
(CABINET INTERIOR)

1 MMBTS INTERIOR DETAIL
SCALE: N.T.S.

- LEGEND:
1. P1000T-HG UNISTRUT, 12" LONG.
 2. 6" PIPE HANGER.
 3. EXISTING SUPPORT PIPE.
 4. NEW STANDOFF BRACKET, ANDREW PART# 30848-4.
 5. NEW ROUND MEMBER ADAPTER SIZED FOR EXISTING PIPE SUPPORT.
 6. BREAKOUT UNIT.
 7. CABLE.



2 MEDUSA HEAD DETAIL
SCALE: NTS

RFS HYBRIFLEX RISER CABLES SCHEDULE




Power	Hybrid cable	Length
Fiber Only (Existing DC Power)	MN: HB058-M12-050F 12x multi-mode fiber pairs, Top: Outdoor protected connectors, Bottom: LC Connectors, 5/8 cable, 50ft	50ft
	MN: HB058-M12-075F	75ft
	MN: HB058-M12-100F	100ft
	MN: HB058-M12-125F	125ft
	MN: HB058-M12-150F	150ft
	MN: HB058-M12-175F	175ft
8 AWG Power	MN: HB114-08U3M12-050F 3x 8 AWG power pairs, 12x multi-mode fiber pairs, Outdoor rated connectors & LC Connectors, 1 1/4 cable, 50ft	50ft
	MN: HB114-08U3M12-075F	75ft
	MN: HB114-08U3M12-100F	100ft
	MN: HB114-08U3M12-125F	125ft
	MN: HB114-08U3M12-150F	150ft
	MN: HB114-08U3M12-175F	175ft
6 AWG Power	MN: HB114-13U3M12-225F 3x 6 AWG power pairs, 12x multi-mode fiber pairs, Outdoor rated connectors & LC Connectors, 1 1/4 cable, 225ft	225ft
	MN: HB114-13U3M12-250F	250ft
	MN: HB114-13U3M12-275F	275ft
	MN: HB114-13U3M12-300F	300ft
4 AWG Power	MN: HB114-21U3M12-225F 3x 4 AWG power pairs, 12x multi-mode fiber pairs, Outdoor rated connectors & LC Connectors, 1 1/4 cable, 225ft	225ft
	MN: HB114-21U3M12-350F	350ft
	MN: HB114-21U3M12-375F	375ft

RFS HYBRIFLEX JUMPER CABLE SCHEDULE

Power	Hybrid Jumper cable	Length
Fiber Only	MN: HBF012-M3-5F1 5 ft, 3x multi-mode fiber pairs, Outdoor & LC connectors, 1/2 cable	5 ft
	MN: HBF012-M3-10F1	10 ft
	MN: HBF012-M3-15F1	15 ft
	MN: HBF012-M3-20F1	20 ft
	MN: HBF012-M3-25F1	25 ft
8 AWG Power	MN: HBF058-08U1M3-5F1 5 ft, 1x 8 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 5/8 cable	5 ft
	MN: HBF058-08U1M3-10F1	10 ft
	MN: HBF058-08U1M3-15F1	15 ft
	MN: HBF058-08U1M3-20F1	20 ft
	MN: HBF058-08U1M3-25F1	25 ft
6 AWG Power	MN: HBF058-13U1M3-5F1 5 ft, 1x 6 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 5/8 cable	5 ft
	MN: HBF058-13U1M3-10F1	10 ft
	MN: HBF058-13U1M3-15F1	15 ft
	MN: HBF058-13U1M3-20F1	20 ft
	MN: HBF058-13U1M3-25F1	25 ft
4 AWG Power	MN: HBF078-21U1M3-5F1 5 ft, 1x 4 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 7/8 cable	5 ft
	MN: HBF078-21U1M3-10F1	10 ft
	MN: HBF078-21U1M3-15F1	15 ft
	MN: HBF078-21U1M3-20F1	20 ft
	MN: HBF078-21U1M3-25F1	25 ft

HYBRID CABLE DC CONDUCTOR SIZE GUIDELINE

MANUF:	RFS	DC CONDUCTOR	CABLE DIAMETER
CABLE	LENGTH	USE NV HYBRIFLEX	7/8"
FIBER ONLY	VARIES		
HYBRIFLEX	<200'	8 AWG	1-1/4"
HYBRIFLEX	225-300'	6 AWG	1-1/4"
HYBRIFLEX	325-375'	4 AWG	1-1/4"



3 2.5 HYBRID CABLE X-SECTION AND DATA
SCALE: NTS

Sprint
2.5 EQUIPMENT DEPLOYMENT
6580 SPRINT PARKWAY
OVERLAND PARK, KANSAS 66251

CROWN CASTLE


TECTONIC ENGINEERING & SURVEYING
TECTONIC Engineering & Surveying
Consultants P.C.
1279 Route 300
Newburgh, NY 12550
Phone: (845) 567-6656
Fax: (845) 567-8703
www.tectonicengineering.com

THIS DOCUMENT IS THE CREATION,
DESIGN, PROPERTY AND COPYRIGHTED
WORK OF SPRINT COMMUNICATIONS, INC.
ANY DUPLICATION OR USE WITHOUT
EXPRESS WRITTEN CONSENT IS STRICTLY
PROHIBITED. DUPLICATION AND USE BY
GOVERNMENT AGENCIES FOR THE
PURPOSES OF CONDUCTING THEIR
LAWFULLY AUTHORIZED REGULATORY AND
ADMINISTRATIVE FUNCTIONS IS
SPECIFICALLY ALLOWED.

SUBMITTALS

NO	DATE	DESCRIPTION	BY
0	06/16/14	FOR COMMENT	JT
1	12/10/14	FOR CONSTRUCTION	MP
2	01/08/15	REVISED ADDRESS	RD



DATE	REVIEWED BY
1/8/15	JMG



SITE NUMBER:
CT03XC373
SITE NAME:
CANDID COMMUNICATIONS
SITE ADDRESS:
425 INDIAN LEDGE PARK
TRUMBULL, CT 06611

SHEET TITLE:
EQUIPMENT
SCHEMATIC DETAILS


SHEET NO:
S-2




LEGEND

- CADWELDED CONNECTION
- MECHANICAL CONNECTION
- COMPRESSION CONNECTION

1 TYPICAL GROUNDING ONE LINE DIAGRAM
E-1 SCALE: NTS



2 TYPICAL ANTENNA GROUNDING PLAN
E-1 SCALE: NTS



3 TYPICAL ELECTRICAL & TELCO PLAN
E-1 SCALE: NTS

Sprint

2.5 EQUIPMENT DEPLOYMENT
6580 SPRINT PARKWAY
OVERLAND PARK, KANSAS 66251

CROWN CASTLE

TECTONIC ENGINEERING & SURVEYING CONSULTANTS P.C.

1279 Route 300
Newburgh, NY 12550
Phone: (845) 567-6656
Fax: (845) 567-8703
www.tectonicengineering.com

THIS DOCUMENT IS THE CREATION, DESIGN, PROPERTY AND COPYRIGHTED WORK OF SPRINT COMMUNICATIONS, INC. ANY DUPLICATION OR USE WITHOUT EXPRESS WRITTEN CONSENT IS STRICTLY PROHIBITED. DUPLICATION AND USE BY GOVERNMENT AGENCIES FOR THE PURPOSES OF CONDUCTING THEIR LAWFULLY AUTHORIZED REGULATORY AND ADMINISTRATIVE FUNCTIONS IS SPECIFICALLY ALLOWED.

SUBMITTALS

PROJECT NO: 7225.CT03XC373

NO	DATE	DESCRIPTION	BY
0	06/16/14	FOR COMMENT	JT
1	12/10/14	FOR CONSTRUCTION	MP
2	01/08/15	REVISED ADDRESS	RD

DATE: 1/8/15 REVIEWED BY: JMO




SITE NUMBER: CT03XC373

SITE NAME: CANDID COMMUNICATIONS

SITE ADDRESS: 425 INDIAN LEDGE PARK TRUMBULL, CT 06611


SHEET TITLE: ELECTRICAL & GROUNDING PLANS

SHEET NO: E-1



6 AWG STRANDED Cu WIRE WITH GREEN, 600V, THWN INSULATION OR BLACK, MARKED AS REQUIRED BY THE NEC (GROUNDED TO GROUND BAR) (SEE NOTES 1 & 2)

CONNECTION OF CABLE GROUND KIT TO ANTENNA CABLE



*TWO HOLE LUG, OR EXOTHERMIC WELD TO BE USED WITH #2 AWG BCW TO BUILDING, GROUND OR GROUND RING

* - GROUND BARS AT THE BOTTOM OF TOWERS/MONOPOLES SHALL ONLY USE EXOTHERMIC WELDS.

- ATTACH "DO NOT DISCONNECT" LABELS TO GROUND BARS. CAN USE BRASS TAG "DO NOT DISCONNECT" AT EACH HYBRID GROUND POINT OR BACK-A-LITE PLATE LABEL ON GROUND BAR.

- CONNECT SEQUENCE- BOLT/WASHER/NO-OX/GROUND BAR/NO-OX/WASHER/LOCK-WASHER/NUT. THIS IS REPEATED FOR EACH LUG CONNECTION POINT.

4 ANTENNA GROUND BAR DETAIL SCALE: NTS


NOTES:

DO NOT INSTALL CABLE GROUND KIT AT A BEND AND ALWAYS DIRECT GROUND WIRE DOWN TO GROUND BAR.


GROUNTING KIT SHALL BE TYPE AND PART NUMBER AS SUPPLIED OR RECOMMENDED BY CABLE MANUFACTURER.

WEATHER PROOFING SHALL BE (TYPE AND PART NUMBER) AS SUPPLIED OR RECOMMENDED BY CABLE MANUFACTURER AND APPROVED BY CONTRACTOR.

1 CABLE GROUNDING KIT DETAIL SCALE: N.T.S.




NOTE:
1. "DOUBLING UP" OR "STACKING" OF CONNECTION IS NOT PERMITTED.
2. OXIDE INHIBITING COMPOUND TO BE USED AT ALL LOCATIONS.
3. CADWELD DOWNLEADS FROM UPPER EGB, LOWER EGB AND MGB.



SECTION "A-A"

2 GROUNDING BAR CONN. DETAIL SCALE: NTS



LEGEND

- 1- COPPER TINNED GROUND BAR, 1/4" X 4" X 20", OR OTHER LENGTH AS REQUIRED, HOLE CENTERS TO MATCH NEMA DOUBLE LUG CONFIGURATION
- 2- INSULATORS, NEWTON INSTRUMENT CAT. NO. 3061-4 OR EQUAL
- 3- 5/8" LOCKWASHERS OR EQUAL
- 4- WALL MOUNTING BRACKET, NEWTON INSTRUMENT CO. CAT NO. A-6056 OR EQUAL
- 5- 5/8-11 X 1" H.H.C.S. BOLTS

NOTE:
ALL BOLTS, NUTS, WASHERS AND LOCK WASHERS SHALL BE 18-8 STAINLESS STEEL.

3 GROUNDING BAR DETAIL SCALE: NTS

GROUNDING NOTES:

1. GROUNDING SHALL BE IN ACCORDANCE WITH NEC ARTICLE 250-GROUNDING AND BONDING.
2. ALL GROUND WIRES SHALL BE #2 AWG UNLESS NOTED OTHERWISE.
3. ALL GROUNDING WIRES SHALL PROVIDE A STRAIGHT, DOWNWARD PATH TO GROUND WITH GRADUAL BENDS AS REQUIRED. GROUND WIRES SHALL NOT BE LOOPED OR SHARPLY BENT.
4. EACH EQUIPMENT CABINET SHALL BE CONNECTED TO THE MASTER ISOLATION GROUND BAR (MGB) WITH #2 AWG INSULATED STRANDED COPPER WIRE. EQUIPMENT CABINETS WALL HAVE (2) CONNECTIONS.
5. PROVIDE DEDICATED #2 AWG COPPER GROUND WIRE FROM EACH ANTENNA MOUNTING PIPE TO ASSOCIATED CIGBE.
6. THE CONTRACTOR SHALL VERIFY THAT THE EXISTING GROUND BARS HAVE ENOUGH SPACE/HOLES FOR ADDITIONAL TWO HOLE LUGS.
7. ALL CONDUITS SHALL BE RIGID GALVANIZED STEEL AND SHALL BE PROVIDED WITH GROUNDING BUSHINGS.
8. PROVIDE GROUND CONNECTIONS FOR ALL METALLIC STRUCTURES, ENCLOSURES, RACEWAYS AND OTHER CONDUCTIVE ITEMS ASSOCIATED WITH THE INSTALLATION OF CARRIER'S EQUIPMENT.
9. WHEN CABLE LENGTH IS OVER 20' THE MANUFACTURERS GROUND KIT MUST BE INSTALLED PER THE MANUFACTURERS SPECIFICATIONS.
10. REFER TO "ANTI-THEFT UPDATE TO SPRINT GROUNDING 082412.PDF" FOR GUIDELINE TO SUSPECTED OR ACTUAL THEFT OF GROUNDING.
11. HOME RUN GROUNDS ARE NOT APPROVED BY CROWN CASTLE CONSTRUCTION STANDARDS AND THAT ANTENNA BUSS BARS SHOULD BE INSTALLED DIRECTLY TO TOWER STEEL WITHOUT INSULATORS OR DOWN CONDUCTORS.

PROTECTIVE GROUNDING SYSTEM GENERAL NOTES:

1. AT ALL TERMINATIONS AT EQUIPMENT ENCLOSURES, PANEL, AND FRAMES OF EQUIPMENT AND WHERE EXPOSED FOR GROUNDING. CONDUCTOR TERMINATION SHALL BE PERFORMED UTILIZING TWO HOLE BOLTED TONGUE COMPRESSION TYPE LUGS WITH STAINLESS STEEL SELF-TAPPING SCREWS.
2. ALL CLAMPS AND SUPPORTS USED TO SUPPORT THE GROUNDING SYSTEM CONDUCTORS AND PVC CONDUITS SHALL BE PVC TYPE (NON CONDUCTIVE). DO NOT USE METAL BRACKETS OR SUPPORTS WHICH WOULD FORM A COMPLETE RING AROUND ANY GROUNDING CONDUCTOR.
3. ALL GROUNDING CONNECTIONS SHALL BE COATED WITH A COPPER SHIELD ANTI-CORROSIVE AGENT SUCH AS T&B KOPR SHIELD. VERIFY PRODUCT WITH PROJECT MANAGER.
4. ALL BOLTS, WASHERS, AND NUTS USED ON GROUNDING CONNECTIONS SHALL BE STAINLESS STEEL.
5. INSTALL GROUND BUSHING ON ALL METALLIC CONDUITS AND BOND TO THE EQUIPMENT GROUND BUS IN THE PANEL BOARD.
6. GROUND ANTENNA BASES, FRAMES, CABLE RACKS, AND OTHER METALLIC COMPONENTS WITH #2 INSULATED TINNED STRANDED COPPER GROUNDING CONDUCTORS AND CONNECT TO INSULATED SURFACE MOUNTED GROUND BARS. CONNECTION DETAILS SHALL FOLLOW MANUFACTURER'S SPECIFICATIONS FOR GROUNDING.
7. GROUND HYBRID CABLE SHIELD AT BOTH ENDS USING MANUFACTURER'S GUIDELINES.

ELECTRICAL AND GROUNDING NOTES

1. ALL ELECTRICAL WORK SHALL CONFORM TO THE REQUIREMENTS OF THE NATIONAL ELECTRICAL CODE (NEC) AS WELL AS APPLICABLE STATE AND LOCAL CODES.
2. ALL ELECTRICAL ITEMS SHALL BE U.L. APPROVED OR LISTED AND PROCURED PER SPECIFICATION REQUIREMENTS.
3. ELECTRICAL AND TELCO WIRING OUTSIDE A BUILDING AND EXPOSED TO WEATHER SHALL BE IN WATER TIGHT GALVANIZED RIGID STEEL CONDUITS OR SCHEDULE 80 PVC (AS PERMITTED BY CODE) AND WHERE REQUIRED IN LIQUID TIGHT FLEXIBLE METAL OR NONMETALLIC CONDUITS.
4. BURIED CONDUIT SHALL BE SCHEDULE 40 PVC.
5. ELECTRICAL WIRING SHALL BE COPPER WITH TYPE XHHW, THWN, OR THHN INSULATION.
6. RUN TELCO CONDUIT OR CABLE BETWEEN TELEPHONE UTILITY DEMARCATION POINT AND PROJECT OWNER CELL SITE TELCO CABINET AND BTS CABINET AS INDICATED ON THIS DRAWING PROVIDE FULL LENGTH PULL ROPE IN INSTALLED TELCO CONDUIT. PROVIDE GREENLEE CONDUIT MEASURING TAPE AT EACH END.
7. WHERE CONDUIT BETWEEN BTS AND PROJECT OWNER CELL SITE PPC AND BETWEEN BTS AND PROJECT OWNER CELL SITE TELCO SERVICE CABINET ARE UNDERGROUND USE PVC, SCHEDULE 40 CONDUIT. ABOVE THE GROUND PORTION OF THESE CONDUITS SHALL BE PVC CONDUIT.
8. ALL EQUIPMENT LOCATED OUTSIDE SHALL HAVE NEMA 3R ENCLOSURE.
9. GROUNDING SHALL COMPLY WITH NEC ART. 250.
10. GROUND HYBRID CABLE SHIELDS AT 3 LOCATIONS USING MANUFACTURER'S HYBRID CABLE GROUNDING KITS SUPPLIED BY PROJECT OWNER.
11. USE #2 COPPER STRANDED WIRE WITH GREEN COLOR INSULATION FOR ABOVE GRADE GROUNDING (UNLESS OTHERWISE SPECIFIED) AND #2 SOLID TINNED BARE COPPER WIRE FOR BELOW GRADE GROUNDING AS INDICATED ON THE DRAWING.
12. ALL GROUND CONNECTIONS TO BE BURNDY HYGROUND COMPRESSION TYPE CONNECTORS OR CADWELD EXOTHERMIC WELD. DO NOT ALLOW BARE COPPER WIRE TO BE IN CONTACT WITH GALVANIZED STEEL.
13. ROUTE GROUNDING CONDUCTORS ALONG THE SHORTEST AND STRAIGHTEST PATH POSSIBLE, EXCEPT AS OTHERWISE INDICATED. GROUNDING LEADS SHOULD NEVER BE BENT AT RIGHT ANGLE. ALWAYS MAKE AT LEAST 12" RADIUS BENDS. #2 WIRE CAN BE BENT AT 6" RADIUS WHEN NECESSARY. BOND ANY METAL OBJECTS WITHIN 6 FEET OF PROJECT OWNER EQUIPMENT OR CABINET TO MASTER GROUND BAR OR GROUNDING RING.
14. CONNECTIONS TO GROUND BARS SHALL BE MADE WITH TWO HOLE COMPRESSION TYPE COPPER LUGS. APPLY OXIDE INHIBITING COMPOUND TO ALL LOCATIONS.
15. APPLY OXIDE INHIBITING COMPOUND TO ALL COMPRESSION TYPE GROUND CONNECTIONS.
16. BOND ANTENNA MOUNTING BRACKETS, HYBRID CABLE GROUND KITS, AND RRRs TO EGB PLACED NEAR THE ANTENNA LOCATION.
17. BOND ANTENNA EGB'S AND MGB TO GROUND RING.
18. CONTRACTOR SHALL TEST COMPLETED GROUND SYSTEM AND RECORD RESULT FOR PROJECT CLOSE-OUT DOCUMENTATION. 5 OHMS MINIMUM RESISTANCE REQUIRED.
19. CONTRACTOR SHALL CONDUCT ANTENNA, HYBRID CABLES, GPS COAX AND RRR RETURN-LOSS AND DISTANCE- TO-FAULT MEASUREMENTS (SWEEP TESTS) AND RECORD RESULTS FOR PROJECT CLOSE OUT.
20. CONTRACTOR SHALL CHECK CAPACITY OF EXISTING SERVICE & PANEL ON SITE TO DETERMINE IF CAPACITY EXISTS TO ACCOMMODATE THE ADDED LOAD OF THIS PROJECT. ADVISE ENGINEER OF ANY DISCREPANCY.
21. LOCATION OF ALL OUTLET, BOXES, ETC, AND THE TYPE OF CONNECTION (PLUG OR DIRECT) SHALL BE CONFIRMED WITH THE OWNER'S REPRESENTATIVE PRIOR TO ROUGH-IN.
22. ELECTRICAL CHARACTERISTICS OF ALL EQUIPMENT (NEW AND EXISTING) SHALL BE FIELD VERIFIED WITH THE OWNERS REPRESENTATIVE AND EQUIPMENT SUPPLIER PRIOR TO ROUGH-IN OF CONDUIT AND WIRE. ALL EQUIPMENT SHALL BE PROPERLY CONNECTED ACCORDING TO THE NAMEPLATE DATA FURNISHED ON THE EQUIPMENT.

Sprint
2.5 EQUIPMENT DEPLOYMENT
6580 SPRINT PARKWAY
OVERLAND PARK, KANSAS 66251

CROWN CASTLE

TECTONIC PLANNING
ENGINEERING
SURVEYING
CONSTRUCTION
MANAGEMENT
TECTONIC Engineering & Surveying
Consultants P.C.
1279 Route 300
Newburgh, NY 12550
Phone: (845) 567-6656
Fax: (845) 567-8703
www.tectonicengineering.com

THIS DOCUMENT IS THE CREATION, DESIGN, PROPERTY AND COPYRIGHTED WORK OF SPRINT COMMUNICATIONS, INC. ANY DUPLICATION OR USE WITHOUT EXPRESS WRITTEN CONSENT IS STRICTLY PROHIBITED. DUPLICATION AND USE BY GOVERNMENT AGENCIES FOR THE PURPOSES OF CONDUCTING THEIR LAWFULLY AUTHORIZED REGULATORY AND ADMINISTRATIVE FUNCTIONS IS SPECIFICALLY ALLOWED.

SUBMITTALS

PROJECT NO: 7225.CT03XC373			
NO	DATE	DESCRIPTION	BY
0	06/16/14	FOR COMMENT	JT
1	12/10/14	FOR CONSTRUCTION	MP
2	01/08/15	REVISED ADDRESS	RD

DATE	REVIEWED BY
1/8/15	JMA

STATE OF CONNECTICUT
MANUQUIN J. PATEL
No. 22038
PROFESSIONAL ENGINEER

SITE NUMBER:
CT03XC373
SITE NAME:
CANDID COMMUNICATIONS
SITE ADDRESS:
425 INDIAN LEDGE PARK
TRUMBULL, CT 06611

SHEET TITLE:
GROUNDING DETAILS & NOTES

SHEET NO:
E-2

Date: June 12, 2014

Darcy Tarr
Crown Castle
3530 Toringdon Way Suite 300
Charlotte, NC 28277

JACOBS

Jacobs Engineering Group, Inc.

5449 Bells Ferry Rd
Acworth, GA 30102
770-701-2500

Subject: Structural Analysis Report

Carrier Designation:	Sprint PCS Co-Locate Scenario A1	
	Carrier Site Number:	CT03XC373
Crown Castle Designation:	Crown Castle BU Number:	881535
	Crown Castle Site Name:	TRUMBULL TOWER
	Crown Castle JDE Job Number:	288083
	Crown Castle Work Order Number:	773620
	Crown Castle Application Number:	245867 Rev. 1
Engineering Firm Designation:	Jacobs Engineering Group, Inc. Project Number:	773620
Site Data:	Indian Ledge Park - Whitney Ave, Trumbull, Fairfield County, CT	
	Latitude 41° 16' 23.81", Longitude -73° 12' 47.18"	
	195 Foot - Monopole Tower	

Dear Darcy Tarr,

Jacobs Engineering Group, Inc. is pleased to submit this "Structural Analysis Report" to determine the structural integrity of the above mentioned tower. This analysis has been performed in accordance with the Crown Castle Structural 'Statement of Work' and the terms of Crown Castle Purchase Order Number 656468, in accordance with application 245867, revision 1.

The purpose of the analysis is to determine acceptability of the tower stress level. Based on our analysis we have determined the tower stress level for the structure and foundation, under the following load case, to be:

LC7: Existing + Reserved + Proposed Equipment	Sufficient Capacity
Note: See Table I and Table II for the proposed and existing/reserved loading, respectively.	

The analysis has been performed in accordance with the TIA/EIA-222-F standard and the 2005 CT State Building Code, and all local code requirements based upon a wind speed of 85 mph fastest mile.

All modifications and equipment proposed in this report shall be installed in accordance with the attached drawings for the determined available structural capacity to be effective.

We at Jacobs Engineering Group, Inc. appreciate the opportunity of providing our continuing professional services to you and Crown Castle. If you have any questions or need further assistance on this or any other projects please give us a call.

Structural analysis prepared by:

Reviewed By:



Jeremy Earnest, EIT
Structural Engineer

Matthew E. Watkins, PE
Project Engineer



TABLE OF CONTENTS

1) INTRODUCTION

2) ANALYSIS CRITERIA

Table 1 - Proposed Antenna and Cable Information

Table 2 - Existing and Reserved Antenna and Cable Information

Table 3 - Design Antenna and Cable Information

3) ANALYSIS PROCEDURE

Table 4 - Documents Provided

3.1) Analysis Method

3.2) Assumptions

4) ANALYSIS RESULTS

Table 5 - Section Capacity (Summary)

Table 6 – Tower Components vs. Capacity

4.1) Recommendations

5) APPENDIX A

tnxTower Output

6) APPENDIX B

Base Level Drawing

7) APPENDIX C

Additional Calculations

1) INTRODUCTION

This tower is a 195 ft Monopole tower designed by ENGINEERED ENDEAVORS, INC. in July of 2001. The tower was originally designed for a wind speed of 85 mph per TIA/EIA-222-F.

2) ANALYSIS CRITERIA

The structural analysis was performed for this tower in accordance with the requirements of TIA/EIA-222-F Structural Standards for Steel Antenna Towers and Antenna Supporting Structures using a fastest mile wind speed of 85 mph with no ice, 37.6 mph with 0.75 inch ice thickness and 50 mph under service loads.

Table 1 - Proposed Antenna and Cable Information

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)	Note
164.0	166.0	3	alcatel lucent	TD-RRH8x20-25	1	1-1/4	-
		3	rfs celwave	APXVTM14-C-120 w/ Mount Pipe			

Table 2 - Existing and Reserved Antenna and Cable Information

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)	Note	
185.0	187.0	6	ericsson	RRUS-11	12 2 1	1-1/4 5/8 3/8	1	
		6	powerwave technologies	7770.00 w/ Mount Pipe				
		12	powerwave technologies	LGP21401				
		3	powerwave technologies	P65-16-XLH-RR w/ Mount Pipe				
		1	raycap	DC6-48-60-18-8F				
	185.0	1	tower mounts	Platform Mount [LP 601-1]				
174.0	174.0	1	tower mounts	Platform Mount [LP 601-1]	-	-	3	
164.0	166.0	1	dragonwave	A-ANT-23G-2-C	6 1	5/16 1/2	4	
		3	argus technologies	LLPX310R w/ Mount Pipe				
		3	samsung telecommunications	FDD_R6_RRH				
		164.0	3	rfs celwave	APXVSPP18-C-A20 w/ Mount Pipe	3	1-1/4	1
	3		alcatel lucent	1900 MHz RRH (65 MHz)				
	3		alcatel lucent	800 EXTERNAL NOTCH FILTER				
	3		alcatel lucent	800MHZ RRH				
		9	rfs celwave	ACU-A20-N				
		1	tower mounts	Platform Mount [LP 601-1]				

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)	Note
154.0	155.0	3	alcatel lucent	RRH2x40-AWS	1	1-5/8	2
		3	kathrein	742 213 w/ Mount Pipe			
		1	rfs celwave	DB-B1-6C-8AB-0Z			
		3	antel	BXA-70063/6CF w/ Mount Pipe	18	1-5/8	1
		2	antel	LPA-4016 w/ Mount Pipe			
		4	decibel	DB844G65ZAXY w/ Mount Pipe			
	3	rymsa wireless	MG D3-800TV w/ Mount Pipe				
154.0	1	tower mounts	Platform Mount [LP 601-1]				
144.0	146.0	3	ericsson	KRY 112 144/1	12	1-5/8	1
		3	ericsson	KRY 112 89/5			
		3	ems wireless	DR65-18-00DPL2Q w/ Mount Pipe			
	144.0	1	tower mounts	Platform Mount [LP 601-1]			
134.0	135.0	12	decibel	DB844H90E-XY w/ Mount Pipe	3	1-5/8	1
	134.0	1	tower mounts	Platform Mount [LP 303-1]	9	1-1/4	

Notes:

- 1) Existing Equipment
- 2) Reserved Equipment
- 3) Empty Mount
- 4) Second Carrier

Table 3 - Design Antenna and Cable Information

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)
195	195	2	-	Omni Whip Antenna	-	-
185	185	12	Allgon	7120.16	-	-
175	175	12	Allgon	7120.16	-	-
165	165	12	Allgon	7120.16	-	-
155	155	12	Allgon	7120.16	-	-
145	145	12	Allgon	7120.16	-	-
135	135	12	Allgon	7120.16	-	-
125	125	12	Allgon	7120.16	-	-

3) ANALYSIS PROCEDURE

Table 4 - Documents Provided

Document	Remarks	Reference	Source
TOWER MANUFACTURER DRAWINGS	EEI	1405789	CCISITES
TOWER FOUNDATION DRAWINGS/DESIGN/SPECS	EEI	1405798	CCISITES
GEOTECHNICAL REPORTS	Dr. Clarence Welti, P.E., P.C.,	1406210	CCISITES
ORIGINAL TOWER STRUCTURAL ANALYSIS REPORT	EEI	1405808	CCISITES

3.1) Analysis Method

tnxTower (version 6.1.4.1), a commercially available analysis software package, was used to create a three-dimensional model of the tower and calculate member stresses for various loading cases. Selected output from the analysis is included in Appendix A.

3.2) Assumptions

- 1) Tower and structures were built in accordance with the manufacturer's specifications.
- 2) The tower and structures have been maintained in accordance with the manufacturer's specifications.
- 3) The configuration of antennas, transmission cables, mounts, and other appurtenances are as specified in Tables 1 and 2 and the referenced drawings.
- 4) When applicable, transmission cables are considered as structural components for calculating wind loads as allowed by EIA/TIA-222-F.

This analysis may be affected if any assumptions are not valid or have been made in error. Jacobs Engineering Group, Inc. should be notified to determine the effect on the structural integrity of the tower.

4) ANALYSIS RESULTS

Table 5 - Section Capacity (Summary)

Section No.	Elevation (ft)	Component Type	Size	Critical Element	P (K)	SF*P_allow (K)	% Capacity	Pass / Fail
L1	195 - 157.62	Pole	TP33.86x25x0.25	1	-7.73	1340.02	27.0	Pass
L2	157.62 - 117.04	Pole	TP42.87x32.2341x0.3125	2	-18.95	2122.84	74.0	Pass
L3	117.04 - 81.58	Pole	TP50.53x40.856x0.375	3	-28.66	3004.66	86.2	Pass
L4	81.58 - 39.99	Pole	TP59.51x48.1832x0.5	4	-44.66	4714.13	76.8	Pass
L5	39.99 - 0	Pole	TP68x56.6386x0.5	5	-67.17	5568.98	83.4	Pass
							Summary	
						Pole (L3)	86.2	Pass
						Rating =	86.2	Pass

Table 6 - Tower Component Stresses vs. Capacity – LC7

Notes	Component	Elevation (ft)	% Capacity	Pass / Fail
1	Anchor Rods	0	83.8	Pass
1	Base Plate	0	79.2	Pass
1	Base Foundation	0	79.0	Pass
Structure Rating (max from all components) =				86.2%

Notes:

- 1) See additional documentation in "Appendix C - Additional Calculations" for calculations supporting the % capacity consumed.

4.1) Recommendations


The tower and its foundation have sufficient capacity to carry the existing, reserved, and proposed loads. No modifications are required at this time.

APPENDIX A
TNXTOWER OUTPUT

APPENDIX B
BASE LEVEL DRAWING

APPENDIX C
ADDITIONAL CALCULATIONS

Section	1	2	3	4	5
Length (ft)	37.38	45.33	41.38	48.42	47.99
Number of Sides	18	18	18	18	18
Thickness (in)	0.2500	0.3125	0.3750	0.5000	0.5000
Socket Length (ft)	4.75	5.92	6.83	8.00	8.00
Top Dia (in)	25.0000	32.2341	40.8560	48.1832	56.6386
Bot Dia (in)	33.8600	42.8700	50.5300	59.5100	68.0000
Grade			A572-65		
Weight (K)	2.9	5.7	7.6	13.9	16.0



DESIGNED APPURTENANCE LOADING


TYPE	ELEVATION	TYPE	ELEVATION
Lightning Rod	195	(2) 8' x 2" Mount Pipe	164
(2) 7770.00 w/ Mount Pipe	185	APXVTM14-C-120 w/ Mount Pipe	164
(2) 7770.00 w/ Mount Pipe	185	APXVTM14-C-120 w/ Mount Pipe	164
P65-16-XLH-RR w/ Mount Pipe	185	APXVTM14-C-120 w/ Mount Pipe	164
P65-16-XLH-RR w/ Mount Pipe	185	TD-RRH8x20-25	164
P65-16-XLH-RR w/ Mount Pipe	185	TD-RRH8x20-25	164
(4) LGP21401	185	TD-RRH8x20-25	164
(4) LGP21401	185	Platform Mount [LP 601-1]	164
(4) LGP21401	185	LLPX310R w/ Mount Pipe	164
DC6-48-60-18-8F	185	A-ANT-23G-2-C	164
(2) RRUS-11	185	(2) DB844G65ZAXY w/ Mount Pipe	154
(2) RRUS-11	185	MG D3-800TV w/ Mount Pipe	154
(2) RRUS-11	185	MG D3-800TV w/ Mount Pipe	154
Platform Mount [LP 601-1]	185	MG D3-800TV w/ Mount Pipe	154
(2) 7770.00 w/ Mount Pipe	185	BXA-70063/6CF w/ Mount Pipe	154
(4) 8' x 2" Mount Pipe	174	BXA-70063/6CF w/ Mount Pipe	154
(4) 8' x 2" Mount Pipe	174	BXA-70063/6CF w/ Mount Pipe	154
Platform Mount [LP 601-1]	174	742 213 w/ Mount Pipe	154
(4) 8' x 2" Mount Pipe	174	742 213 w/ Mount Pipe	154
LLPX310R w/ Mount Pipe	164	742 213 w/ Mount Pipe	154
LLPX310R w/ Mount Pipe	164	RRH2x40-AWS	154
FDD_R6_RRH	164	RRH2x40-AWS	154
FDD_R6_RRH	164	RRH2x40-AWS	154
FDD_R6_RRH	164	DB-B1-6C-8AB-0Z	154
APXVSP18-C-A20 w/ Mount Pipe	164	Platform Mount [LP 601-1]	154
APXVSP18-C-A20 w/ Mount Pipe	164	(2) DB844G65ZAXY w/ Mount Pipe	154
APXVSP18-C-A20 w/ Mount Pipe	164	(2) LPA-4016 w/ Mount Pipe	154
1900 MHz RRH (65 MHz)	164	DR65-18-00DPL2Q w/ Mount Pipe	144
1900 MHz RRH (65 MHz)	164	KRY 112 144/1	144
1900 MHz RRH (65 MHz)	164	KRY 112 144/1	144
800MHZ RRH	164	KRY 112 144/1	144
800MHZ RRH	164	KRY 112 89/5	144
800MHZ RRH	164	KRY 112 89/5	144
800 EXTERNAL NOTCH FILTER	164	KRY 112 89/5	144
800 EXTERNAL NOTCH FILTER	164	Platform Mount [LP 601-1]	144
800 EXTERNAL NOTCH FILTER	164	DR65-18-00DPL2Q w/ Mount Pipe	144
(3) ACU-A20-N	164	DR65-18-00DPL2Q w/ Mount Pipe	144
(3) ACU-A20-N	164	(4) DB844H90E-XY w/ Mount Pipe	134
(3) ACU-A20-N	164	Platform Mount [LP 303-1]	134
(2) 8' x 2" Mount Pipe	164	(4) DB844H90E-XY w/ Mount Pipe	134
(2) 8' x 2" Mount Pipe	164	(4) DB844H90E-XY w/ Mount Pipe	134

MATERIAL STRENGTH

GRADE	Fy	Fu	GRADE	Fy	Fu
A572-65	65 ksi	80 ksi			

TOWER DESIGN NOTES

1. Tower is located in Fairfield County, Connecticut.
2. Tower designed for a 85 mph basic wind in accordance with the TIA/EIA-222-F Standard.
3. Tower is also designed for a 38 mph basic wind with 0.75 in ice. Ice is considered to increase in thickness with height.
4. Deflections are based upon a 50 mph wind.
5. TOWER RATING: 86.2%



Jacobs Engineering Group, Inc. 5449 Bells Ferry Road Acworth, GA 30102 Phone: 770-701-2500 FAX: 770-701-2501	Job: TRUMBULL TOWER - MP -195		
	Project: BU# 881535 WO# 773620		
Client: Crown Castle	Drawn by: Stephen Richards	App'd:	
Code: TIA/EIA-222-F	Date: 06/12/14	Scale: NTS	
Path:	Dwg No. E-1		

Tower Input Data

There is a pole section.
 This tower is designed using the TIA/EIA-222-F standard.
 The following design criteria apply:

- 4) Tower is located in Fairfield County, Connecticut.
- 5) Basic wind speed of 85 mph.
- 6) Nominal ice thickness of 0.7500 in.
- 7) Ice thickness is considered to increase with height.
- 8) Ice density of 56 pcf.
- 9) A wind speed of 38 mph is used in combination with ice.
- 10) Temperature drop of 50 °F.
- 11) Deflections calculated using a wind speed of 50 mph.
- 12) A non-linear (P-delta) analysis was used.
- 13) Pressures are calculated at each section.
- 14) Stress ratio used in pole design is 1.333.
- 15) Local bending stresses due to climbing loads, feed line supports, and appurtenance mounts are not considered.

Options

- | | | |
|--|--|--|
| Consider Moments - Legs
Consider Moments - Horizontals
Consider Moments - Diagonals
Use Moment Magnification
✓ Use Code Stress Ratios
✓ Use Code Safety Factors - Guys
✓ Escalate Ice
Always Use Max Kz
Use Special Wind Profile
Include Bolts In Member Capacity
Leg Bolts Are At Top Of Section
Secondary Horizontal Braces Leg
Use Diamond Inner Bracing (4 Sided)
Add IBC .6D+W Combination | Distribute Leg Loads As Uniform
Assume Legs Pinned
✓ Assume Rigid Index Plate
✓ Use Clear Spans For Wind Area
Use Clear Spans For KL/r
Retension Guys To Initial Tension
✓ Bypass Mast Stability Checks
✓ Use Azimuth Dish Coefficients
✓ Project Wind Area of Appurt.
Autocalc Torque Arm Areas
SR Members Have Cut Ends
Sort Capacity Reports By Component
Triangulate Diamond Inner Bracing
Use TIA-222-G Tension Splice
Capacity Exemption | Treat Feedline Bundles As Cylinder
Use ASCE 10 X-Brace Ly Rules
Calculate Redundant Bracing Forces
Ignore Redundant Members in FEA
SR Leg Bolts Resist Compression
All Leg Panels Have Same Allowable
Offset Girt At Foundation
✓ Consider Feedline Torque
Include Angle Block Shear Check
<div style="text-align: center; background-color: #e0e0e0; padding: 2px;">Poles</div> ✓ Include Shear-Torsion Interaction
Always Use Sub-Critical Flow
Use Top Mounted Sockets |
|--|--|--|

Tapered Pole Section Geometry

Section	Elevation ft	Section Length ft	Splice Length ft	Number of Sides	Top Diameter in	Bottom Diameter in	Wall Thickness in	Bend Radius in	Pole Grade
L1	195.00-157.62	37.38	4.75	18	25.0000	33.8600	0.2500	1.0000	A572-65 (65 ksi)
L2	157.62-117.04	45.33	5.92	18	32.2341	42.8700	0.3125	1.2500	A572-65 (65 ksi)
L3	117.04-81.58	41.38	6.83	18	40.8560	50.5300	0.3750	1.5000	A572-65 (65 ksi)
L4	81.58-39.99	48.42	8.00	18	48.1832	59.5100	0.5000	2.0000	A572-65 (65 ksi)
L5	39.99-0.00	47.99		18	56.6386	68.0000	0.5000	2.0000	A572-65 (65 ksi)

Tapered Pole Properties

Section	Tip Dia. in	Area in ²	I in ⁴	r in	C in	I/C in ³	J in ⁴	It/Q in ²	w in	w/t
L1	25.3857	19.6391	1519.8824	8.7863	12.7000	119.6758	3041.7647	9.8214	3.9600	15.84
	34.3823	26.6695	3806.1852	11.9316	17.2009	221.2785	7617.3787	13.3373	5.5194	22.077
L2	33.8631	31.6623	4076.1447	11.3322	16.3749	248.9258	8157.6529	15.8341	5.1232	16.394
	43.5313	42.2117	9658.7899	15.1079	21.7780	443.5122	19330.289	21.1099	6.9951	22.384
L3	42.8916	48.1825	9975.3615	14.3707	20.7548	480.6283	19963.848	24.0958	6.5307	17.415
	51.3095	59.6970	18972.228	17.8050	25.6692	739.1036	37969.421	29.8542	8.2333	21.955
L4	50.5489	75.6733	21737.614	16.9276	24.4771	888.0800	43503.832	37.8438	7.6003	15.201
	60.4280	93.6489	41199.431	20.9486	30.2311	1362.8171	82453.073	46.8333	9.5938	19.188
L5	59.4355	89.0919	35473.065	19.9292	28.7724	1232.8852	70992.806	44.5544	9.0884	18.177
	69.0490	107.1225	61663.148	23.9625	34.5440	1785.0610	123407.43	53.5714	11.0880	22.176

Tower Elevation	Gusset Area (per face)	Gusset Thickness	Gusset Grade	Adjust. Factor A _r	Adjust. Factor A _r	Weight Mult.	Double Angle Stitch Bolt Spacing Diagonals	Double Angle Stitch Bolt Spacing Horizontals
ft	ft ²	in					in	in
L1 195.00-157.62				1	1	1		
L2 157.62-117.04				1	1	1		
L3 117.04-81.58				1	1	1		
L4 81.58-39.99				1	1	1		
L5 39.99-0.00				1	1	1		

Feed Line/Linear Appurtenances - Entered As Round Or Flat

Description	Face or Leg	Allow Shield	Component Type	Placement	Total Number	Number Per Row	Clear Spacing	Width or Diameter	Perimeter	Weight
				ft			in	r in	r in	plf
**										

Feed Line/Linear Appurtenances - Entered As Area

Description	Face or Leg	Allow Shield	Component Type	Placement	Total Number		C _A A _A	Weight		
				ft			ft ² /ft	plf		
Step Pegs	A	No	CaAa (Out Of Face)	195.00 - 0.00	1	No Ice	0.08	2.72		
						1/2" Ice	0.18	3.51		
						1" Ice	0.28	4.92		
						2" Ice	0.48	9.56		
						4" Ice	0.88	26.18		
Safety Line 3/8	A	No	CaAa (Out Of Face)	195.00 - 0.00	1	No Ice	0.04	0.22		
						1/2" Ice	0.14	0.75		
						1" Ice	0.24	1.28		
						2" Ice	0.44	2.34		
						4" Ice	0.84	4.46		

LDF6-50A (1-1/4")	C	No	Inside Pole	185.00 - 0.00	12	No Ice	0.00	0.66		
						1/2" Ice	0.00	0.66		
						1" Ice	0.00	0.66		
						2" Ice	0.00	0.66		
						4" Ice	0.00	0.66		
FB-L98B-002-75000	C	No	Inside Pole	185.00 - 0.00	1	No Ice	0.00	0.06		

Description	Face or Leg	Allow Shield	Component Type	Placement ft	Total Number	CA _A A ft ² /ft	Weight plf
(3/8")						1/2" Ice 0.00	0.06
						1" Ice 0.00	0.06
						2" Ice 0.00	0.06
						4" Ice 0.00	0.06
WR-VG82ST-BRDA (5/8")	C	No	Inside Pole	185.00 - 0.00	2	No Ice 0.00	0.31
						1/2" Ice 0.00	0.31
						1" Ice 0.00	0.31
						2" Ice 0.00	0.31
						4" Ice 0.00	0.31
2" Rigid Conduit	C	No	Inside Pole	185.00 - 0.00	1	No Ice 0.00	2.80
						1/2" Ice 0.00	2.80
						1" Ice 0.00	2.80
						2" Ice 0.00	2.80
						4" Ice 0.00	2.80

2" Rigid Conduit	B	No	Inside Pole	164.00 - 0.00	1	No Ice 0.00	2.80
						1/2" Ice 0.00	2.80
						1" Ice 0.00	2.80
						2" Ice 0.00	2.80
						4" Ice 0.00	2.80
7983A (1/2")	B	No	Inside Pole	164.00 - 0.00	1	No Ice 0.00	0.15
						1/2" Ice 0.00	0.15
						1" Ice 0.00	0.15
						2" Ice 0.00	0.15
						4" Ice 0.00	0.15
9207 (5/16")	B	No	Inside Pole	164.00 - 0.00	6	No Ice 0.00	0.06
						1/2" Ice 0.00	0.06
						1" Ice 0.00	0.06
						2" Ice 0.00	0.06
						4" Ice 0.00	0.06
HB114-1-0813U4-M5J(1 1/4")	C	No	Inside Pole	164.00 - 0.00	3	No Ice 0.00	1.20
						1/2" Ice 0.00	1.20
						1" Ice 0.00	1.20
						2" Ice 0.00	1.20
						4" Ice 0.00	1.20
HB114-21U3M12-XXXF(1-1/4")	C	No	Inside Pole	164.00 - 0.00	1	No Ice 0.00	1.22
						1/2" Ice 0.00	1.22
						1" Ice 0.00	1.22
						2" Ice 0.00	1.22
						4" Ice 0.00	1.22

HJ7-50A (1-5/8")	B	No	Inside Pole	154.00 - 0.00	12	No Ice 0.00	1.04
						1/2" Ice 0.00	1.04
						1" Ice 0.00	1.04
						2" Ice 0.00	1.04
						4" Ice 0.00	1.04
HB158-1-08U8-S8J18(1-5/8)	B	No	CaAa (Out Of Face)	154.00 - 0.00	1	No Ice 0.20	1.30
						1/2" Ice 0.30	2.81
						1" Ice 0.40	4.94
						2" Ice 0.60	11.02
						4" Ice 1.00	30.52
HJ7-50A (1-5/8")	B	No	CaAa (Out Of Face)	154.00 - 0.00	6	No Ice 0.00	1.04
						1/2" Ice 0.00	2.55
						1" Ice 0.00	4.68
						2" Ice 0.00	10.76
						4" Ice 0.00	30.26

FLC 158-50J (1-5/8")	A	No	Inside Pole	144.00 - 0.00	12	No Ice 0.00	0.92
						1/2" Ice 0.00	0.92
						1" Ice 0.00	0.92
						2" Ice 0.00	0.92
						4" Ice 0.00	0.92

LDF6-50A (1-1/4")	A	No	Inside Pole	134.00 - 0.00	9	No Ice 0.00	0.66
						1/2" Ice 0.00	0.66
						1" Ice 0.00	0.66
						2" Ice 0.00	0.66
						4" Ice 0.00	0.66
LDF7-50A (1-5/8")	A	No	Inside Pole	134.00 - 0.00	3	No Ice 0.00	0.82

Description	Face or Leg	Allow Shield	Component Type	Placement ft	Total Number	C _A A _A ft ² /ft	Weight plf
					1/2" Ice	0.00	0.82
					1" Ice	0.00	0.82
					2" Ice	0.00	0.82
					4" Ice	0.00	0.82
**							

Feed Line/Linear Appurtenances Section Areas

Tower Section n	Tower Elevation ft	Face	A _R ft ²	A _F ft ²	C _A A _A In Face ft ²	C _A A _A Out Face ft ²	Weight K
L1	195.00-157.62	A	0.000	0.000	0.000	4.392	0.11
		B	0.000	0.000	0.000	0.000	0.02
		C	0.000	0.000	0.000	0.000	0.34
L2	157.62-117.04	A	0.000	0.000	0.000	4.768	0.56
		B	0.000	0.000	0.000	7.318	0.87
		C	0.000	0.000	0.000	0.000	0.66
L3	117.04-81.58	A	0.000	0.000	0.000	4.167	0.79
		B	0.000	0.000	0.000	7.021	0.83
		C	0.000	0.000	0.000	0.000	0.57
L4	81.58-39.99	A	0.000	0.000	0.000	4.887	0.93
		B	0.000	0.000	0.000	8.235	0.97
		C	0.000	0.000	0.000	0.000	0.67
L5	39.99-0.00	A	0.000	0.000	0.000	4.699	0.89
		B	0.000	0.000	0.000	7.918	0.93
		C	0.000	0.000	0.000	0.000	0.65

Feed Line/Linear Appurtenances Section Areas - With Ice

Tower Section n	Tower Elevation ft	Face or Leg	Ice Thickness in	A _R ft ²	A _F ft ²	C _A A _A In Face ft ²	C _A A _A Out Face ft ²	Weight K
L1	195.00-157.62	A	0.917	0.000	0.000	0.000	18.096	0.22
		B		0.000	0.000	0.000	0.000	0.02
		C		0.000	0.000	0.000	0.000	0.34
L2	157.62-117.04	A	0.889	0.000	0.000	0.000	19.646	0.68
		B		0.000	0.000	0.000	14.093	1.72
		C		0.000	0.000	0.000	0.000	0.66
L3	117.04-81.58	A	0.856	0.000	0.000	0.000	16.783	0.89
		B		0.000	0.000	0.000	13.329	1.61
		C		0.000	0.000	0.000	0.000	0.57
L4	81.58-39.99	A	0.807	0.000	0.000	0.000	19.122	1.04
		B		0.000	0.000	0.000	15.353	1.85
		C		0.000	0.000	0.000	0.000	0.67
L5	39.99-0.00	A	0.750	0.000	0.000	0.000	17.606	1.00
		B		0.000	0.000	0.000	14.371	1.72
		C		0.000	0.000	0.000	0.000	0.65

Feed Line Center of Pressure

Section	Elevation ft	CP _x in	CP _z in	CP _x Ice in	CP _z Ice in
L1	195.00-157.62	0.0000	-0.1682	0.0000	-0.5765
L2	157.62-117.04	0.2166	-0.0361	0.3483	-0.3533
L3	117.04-81.58	0.2378	-0.0257	0.3881	-0.3402
L4	81.58-39.99	0.2405	-0.0260	0.3952	-0.3402
L5	39.99-0.00	0.2427	-0.0262	0.3966	-0.3320

Discrete Tower Loads

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustmen t °	Placement ft	C _{AA} Front ft ²	C _{AA} Side ft ²	Weight K	
(2) 7770.00 w/ Mount Pipe	A	From Leg	4.00	0.0000	185.00	No Ice	6.12	4.25	0.06
			0.00			1/2"	6.63	5.01	0.10
			2.00			Ice	7.13	5.71	0.16
						1" Ice	8.16	7.16	0.29
						2" Ice	10.36	10.41	0.66
(2) 7770.00 w/ Mount Pipe	B	From Leg	4.00	0.0000	185.00	No Ice	6.12	4.25	0.06
			0.00			1/2"	6.63	5.01	0.10
			2.00			Ice	7.13	5.71	0.16
						1" Ice	8.16	7.16	0.29
						2" Ice	10.36	10.41	0.66
(2) 7770.00 w/ Mount Pipe	C	From Leg	4.00	0.0000	185.00	No Ice	6.12	4.25	0.06
			0.00			1/2"	6.63	5.01	0.10
			2.00			Ice	7.13	5.71	0.16
						1" Ice	8.16	7.16	0.29
						2" Ice	10.36	10.41	0.66
P65-16-XLH-RR w/ Mount Pipe	A	From Leg	4.00	0.0000	185.00	No Ice	8.64	6.36	0.08
			0.00			1/2"	9.29	7.54	0.14
			2.00			Ice	9.91	8.43	0.22
						1" Ice	11.18	10.24	0.39
						2" Ice	13.83	14.10	0.89
P65-16-XLH-RR w/ Mount Pipe	B	From Leg	4.00	0.0000	185.00	No Ice	8.64	6.36	0.08
			0.00			1/2"	9.29	7.54	0.14
			2.00			Ice	9.91	8.43	0.22
						1" Ice	11.18	10.24	0.39
						2" Ice	13.83	14.10	0.89
P65-16-XLH-RR w/ Mount Pipe	C	From Leg	4.00	0.0000	185.00	No Ice	8.64	6.36	0.08
			0.00			1/2"	9.29	7.54	0.14
			2.00			Ice	9.91	8.43	0.22
						1" Ice	11.18	10.24	0.39
						2" Ice	13.83	14.10	0.89
(4) LGP21401	A	From Leg	4.00	0.0000	185.00	No Ice	1.29	0.23	0.01
			0.00			1/2"	1.45	0.31	0.02
			2.00			Ice	1.61	0.40	0.03
						1" Ice	1.97	0.61	0.05
						2" Ice	2.79	1.12	0.14
(4) LGP21401	B	From Leg	4.00	0.0000	185.00	No Ice	1.29	0.23	0.01
			0.00			1/2"	1.45	0.31	0.02
			2.00			Ice	1.61	0.40	0.03
						1" Ice	1.97	0.61	0.05
						2" Ice	2.79	1.12	0.14
(4) LGP21401	C	From Leg	4.00	0.0000	185.00	No Ice	1.29	0.23	0.01
			0.00			1/2"	1.45	0.31	0.02
			2.00			Ice	1.61	0.40	0.03
						1" Ice	1.97	0.61	0.05
						2" Ice	2.79	1.12	0.14
DC6-48-60-18-8F	A	From Leg	4.00	0.0000	185.00	No Ice	2.57	4.32	0.03
			0.00			1/2"	2.80	4.60	0.06
			2.00			Ice	3.04	4.88	0.10
						1" Ice	3.54	5.49	0.18
						2" Ice	4.66	6.80	0.40

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment t °	Placement ft	C _{AA} Front ft ²	C _{AA} Side ft ²	Weight K	
(2) RRUS-11	A	From Leg	4.00 0.00 2.00	0.0000	185.00	4" Ice No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	2.94 1.25 3.17 1.41 3.41 1.59 3.91 1.96 5.02 2.82	0.06 0.07 0.10 0.15 0.30	
(2) RRUS-11	B	From Leg	4.00 0.00 2.00	0.0000	185.00	4" Ice No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	2.94 1.25 3.17 1.41 3.41 1.59 3.91 1.96 5.02 2.82	0.06 0.07 0.10 0.15 0.30	
(2) RRUS-11	C	From Leg	4.00 0.00 2.00	0.0000	185.00	4" Ice No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	2.94 1.25 3.17 1.41 3.41 1.59 3.91 1.96 5.02 2.82	0.06 0.07 0.10 0.15 0.30	
Platform Mount [LP 601-1]	C	None		0.0000	185.00	4" Ice No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	28.47 28.47 33.59 33.59 38.71 38.71 48.95 48.95 69.43 69.43	1.12 1.51 1.91 2.69 4.26	
*** (4) 8' x 2" Mount Pipe	A	From Leg	4.00 0.00 0.00	0.0000	174.00	4" Ice No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	1.90 1.90 2.73 2.73 3.40 3.40 4.40 4.40 6.50 6.50	0.03 0.04 0.06 0.12 0.30	
(4) 8' x 2" Mount Pipe	B	From Leg	4.00 0.00 0.00	0.0000	174.00	4" Ice No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	1.90 1.90 2.73 2.73 3.40 3.40 4.40 4.40 6.50 6.50	0.03 0.04 0.06 0.12 0.30	
(4) 8' x 2" Mount Pipe	C	From Leg	4.00 0.00 0.00	0.0000	174.00	4" Ice No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	1.90 1.90 2.73 2.73 3.40 3.40 4.40 4.40 6.50 6.50	0.03 0.04 0.06 0.12 0.30	
Platform Mount [LP 601-1]	C	None		0.0000	174.00	4" Ice No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	28.47 28.47 33.59 33.59 38.71 38.71 48.95 48.95 69.43 69.43	1.12 1.51 1.91 2.69 4.26	
*** *** LLPX310R w/ Mount Pipe	A	From Leg	4.00 0.00 2.00	0.0000	164.00	4" Ice No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	5.07 2.98 5.48 3.53 5.91 4.09 6.79 5.31 8.70 8.13	0.05 0.08 0.13 0.23 0.54	
LLPX310R w/ Mount Pipe	B	From Leg	4.00 0.00 2.00	0.0000	164.00	4" Ice No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	5.07 2.98 5.48 3.53 5.91 4.09 6.79 5.31 8.70 8.13	0.05 0.08 0.13 0.23 0.54	
LLPX310R w/ Mount Pipe	C	From Leg	4.00	0.0000	164.00	No Ice	5.07	2.98	0.05

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment t °	Placement ft	C _{AA} Front ft ²	C _{AA} Side ft ²	Weight K	
			0.00			1/2"	5.48	3.53	0.08
			2.00			Ice	5.91	4.09	0.13
						1" Ice	6.79	5.31	0.23
						2" Ice	8.70	8.13	0.54
						4" Ice			
FDD_R6_RRH	A	From Leg	4.00	0.0000	164.00	No Ice	1.79	0.78	0.03
			0.00			1/2"	1.97	0.92	0.04
			2.00			Ice	2.16	1.07	0.06
						1" Ice	2.57	1.39	0.09
						2" Ice	3.49	2.14	0.20
						4" Ice			
FDD_R6_RRH	B	From Leg	4.00	0.0000	164.00	No Ice	1.79	0.78	0.03
			0.00			1/2"	1.97	0.92	0.04
			2.00			Ice	2.16	1.07	0.06
						1" Ice	2.57	1.39	0.09
						2" Ice	3.49	2.14	0.20
						4" Ice			
FDD_R6_RRH	C	From Leg	4.00	0.0000	164.00	No Ice	1.79	0.78	0.03
			0.00			1/2"	1.97	0.92	0.04
			2.00			Ice	2.16	1.07	0.06
						1" Ice	2.57	1.39	0.09
						2" Ice	3.49	2.14	0.20
						4" Ice			
APXVSPP18-C-A20 w/ Mount Pipe	A	From Leg	4.00	0.0000	164.00	No Ice	8.50	6.95	0.08
			0.00			1/2"	9.15	8.13	0.15
			2.00			Ice	9.77	9.02	0.23
						1" Ice	11.03	10.84	0.41
						2" Ice	13.68	14.85	0.91
						4" Ice			
APXVSPP18-C-A20 w/ Mount Pipe	B	From Leg	4.00	0.0000	164.00	No Ice	8.50	6.95	0.08
			0.00			1/2"	9.15	8.13	0.15
			2.00			Ice	9.77	9.02	0.23
						1" Ice	11.03	10.84	0.41
						2" Ice	13.68	14.85	0.91
						4" Ice			
APXVSPP18-C-A20 w/ Mount Pipe	C	From Leg	4.00	0.0000	164.00	No Ice	8.50	6.95	0.08
			0.00			1/2"	9.15	8.13	0.15
			2.00			Ice	9.77	9.02	0.23
						1" Ice	11.03	10.84	0.41
						2" Ice	13.68	14.85	0.91
						4" Ice			
1900 MHz RRH (65 MHz)	A	From Leg	4.00	0.0000	164.00	No Ice	2.70	2.77	0.06
			0.00			1/2"	2.94	3.01	0.08
			0.00			Ice	3.18	3.26	0.11
						1" Ice	3.70	3.78	0.18
						2" Ice	4.85	4.93	0.35
						4" Ice			
1900 MHz RRH (65 MHz)	B	From Leg	4.00	0.0000	164.00	No Ice	2.70	2.77	0.06
			0.00			1/2"	2.94	3.01	0.08
			0.00			Ice	3.18	3.26	0.11
						1" Ice	3.70	3.78	0.18
						2" Ice	4.85	4.93	0.35
						4" Ice			
1900 MHz RRH (65 MHz)	C	From Leg	4.00	0.0000	164.00	No Ice	2.70	2.77	0.06
			0.00			1/2"	2.94	3.01	0.08
			0.00			Ice	3.18	3.26	0.11
						1" Ice	3.70	3.78	0.18
						2" Ice	4.85	4.93	0.35
						4" Ice			
800MHZ RRH	A	From Leg	4.00	0.0000	164.00	No Ice	2.49	2.07	0.05
			0.00			1/2"	2.71	2.27	0.07
			0.00			Ice	2.93	2.48	0.10
						1" Ice	3.41	2.93	0.16
						2" Ice	4.46	3.93	0.32
						4" Ice			

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment t °	Placement ft		C _{AA} Front ft ²	C _{AA} Side ft ²	Weight K
800MHZ RRH	B	From Leg	4.00 0.00 0.00	0.0000	164.00	No Ice	2.49	2.07	0.05
						1/2" Ice	2.71	2.27	0.07
						Ice	2.93	2.48	0.10
						1" Ice	3.41	2.93	0.16
						2" Ice	4.46	3.93	0.32
						4" Ice			
800MHZ RRH	C	From Leg	4.00 0.00 0.00	0.0000	164.00	No Ice	2.49	2.07	0.05
						1/2" Ice	2.71	2.27	0.07
						Ice	2.93	2.48	0.10
						1" Ice	3.41	2.93	0.16
						2" Ice	4.46	3.93	0.32
						4" Ice			
800 EXTERNAL NOTCH FILTER	A	From Leg	4.00 0.00 0.00	0.0000	164.00	No Ice	0.77	0.37	0.01
						1/2" Ice	0.89	0.46	0.02
						Ice	1.02	0.56	0.02
						1" Ice	1.30	0.79	0.04
						2" Ice	1.97	1.34	0.11
						4" Ice			
800 EXTERNAL NOTCH FILTER	B	From Leg	4.00 0.00 0.00	0.0000	164.00	No Ice	0.77	0.37	0.01
						1/2" Ice	0.89	0.46	0.02
						Ice	1.02	0.56	0.02
						1" Ice	1.30	0.79	0.04
						2" Ice	1.97	1.34	0.11
						4" Ice			
800 EXTERNAL NOTCH FILTER	C	From Leg	4.00 0.00 0.00	0.0000	164.00	No Ice	0.77	0.37	0.01
						1/2" Ice	0.89	0.46	0.02
						Ice	1.02	0.56	0.02
						1" Ice	1.30	0.79	0.04
						2" Ice	1.97	1.34	0.11
						4" Ice			
(3) ACU-A20-N	A	From Leg	4.00 0.00 0.00	0.0000	164.00	No Ice	0.08	0.14	0.00
						1/2" Ice	0.12	0.19	0.00
						Ice	0.17	0.25	0.00
						1" Ice	0.30	0.40	0.01
						2" Ice	0.67	0.80	0.04
						4" Ice			
(3) ACU-A20-N	B	From Leg	4.00 0.00 0.00	0.0000	164.00	No Ice	0.08	0.14	0.00
						1/2" Ice	0.12	0.19	0.00
						Ice	0.17	0.25	0.00
						1" Ice	0.30	0.40	0.01
						2" Ice	0.67	0.80	0.04
						4" Ice			
(3) ACU-A20-N	C	From Leg	4.00 0.00 0.00	0.0000	164.00	No Ice	0.08	0.14	0.00
						1/2" Ice	0.12	0.19	0.00
						Ice	0.17	0.25	0.00
						1" Ice	0.30	0.40	0.01
						2" Ice	0.67	0.80	0.04
						4" Ice			
(2) 8' x 2" Mount Pipe	A	From Leg	4.00 0.00 2.00	0.0000	164.00	No Ice	1.90	1.90	0.03
						1/2" Ice	2.73	2.73	0.04
						Ice	3.40	3.40	0.06
						1" Ice	4.40	4.40	0.12
						2" Ice	6.50	6.50	0.30
						4" Ice			
(2) 8' x 2" Mount Pipe	B	From Leg	4.00 0.00 2.00	0.0000	164.00	No Ice	1.90	1.90	0.03
						1/2" Ice	2.73	2.73	0.04
						Ice	3.40	3.40	0.06
						1" Ice	4.40	4.40	0.12
						2" Ice	6.50	6.50	0.30
						4" Ice			
(2) 8' x 2" Mount Pipe	C	From Leg	4.00 0.00 2.00	0.0000	164.00	No Ice	1.90	1.90	0.03
						1/2" Ice	2.73	2.73	0.04
						Ice	3.40	3.40	0.06
						1" Ice	4.40	4.40	0.12
						2" Ice	6.50	6.50	0.30
						4" Ice			

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C _{AA} Front	C _{AA} Side	Weight	
			Horz	Lateral						ft
APXVTM14-C-120 w/ Mount Pipe	A	From Leg	4.00	0.00	0.0000	164.00	4" Ice			
							No Ice	7.13	4.96	0.08
							1/2"	7.66	5.75	0.13
							Ice	8.18	6.47	0.19
							1" Ice	9.26	8.01	0.34
APXVTM14-C-120 w/ Mount Pipe	B	From Leg	4.00	0.00	0.0000	164.00	2" Ice	11.53	11.41	0.75
							4" Ice			
							No Ice	7.13	4.96	0.08
							1/2"	7.66	5.75	0.13
							Ice	8.18	6.47	0.19
APXVTM14-C-120 w/ Mount Pipe	C	From Leg	4.00	0.00	0.0000	164.00	1" Ice	9.26	8.01	0.34
							2" Ice	11.53	11.41	0.75
							4" Ice			
							No Ice	7.13	4.96	0.08
							1/2"	7.66	5.75	0.13
TD-RRH8x20-25	A	From Leg	4.00	0.00	0.0000	164.00	Ice	8.18	6.47	0.19
							1" Ice	9.26	8.01	0.34
							2" Ice	11.53	11.41	0.75
							4" Ice			
							No Ice	4.72	1.70	0.07
TD-RRH8x20-25	B	From Leg	4.00	0.00	0.0000	164.00	1/2"	5.01	1.92	0.10
							Ice	5.32	2.14	0.13
							1" Ice	5.95	2.62	0.20
							2" Ice	7.31	3.68	0.40
							4" Ice			
TD-RRH8x20-25	C	From Leg	4.00	0.00	0.0000	164.00	No Ice	4.72	1.70	0.07
							1/2"	5.01	1.92	0.10
							Ice	5.32	2.14	0.13
							1" Ice	5.95	2.62	0.20
							2" Ice	7.31	3.68	0.40
Platform Mount [LP 601-1]	C	None	0.0000	164.00	0.0000	164.00	4" Ice			
							No Ice	28.47	28.47	1.12
							1/2"	33.59	33.59	1.51
							Ice	38.71	38.71	1.91
							1" Ice	48.95	48.95	2.69
(2) DB844G65ZAXY w/ Mount Pipe	A	From Leg	4.00	0.00	0.0000	154.00	2" Ice	69.43	69.43	4.26
							4" Ice			
							No Ice	4.90	4.92	0.03
							1/2"	5.35	5.60	0.08
							Ice	5.80	6.28	0.13
(2) LPA-4016 w/ Mount Pipe	B	From Leg	4.00	0.00	0.0000	154.00	1" Ice	6.73	7.71	0.26
							2" Ice	8.73	10.83	0.62
							4" Ice			
							No Ice	10.01	7.46	0.04
							1/2"	10.52	8.15	0.12
(2) DB844G65ZAXY w/ Mount Pipe	C	From Leg	4.00	0.00	0.0000	154.00	Ice	11.04	8.87	0.21
							1" Ice	12.11	10.35	0.40
							2" Ice	14.39	13.59	0.91
							4" Ice			
							No Ice	4.90	4.92	0.03
MG D3-800TV w/ Mount Pipe	A	From Leg	4.00	0.00	0.0000	154.00	1/2"	3.98	4.12	0.07
							Ice	4.39	4.78	0.11
							1" Ice	6.73	7.71	0.26
							2" Ice	8.73	10.83	0.62

Description	Face or Leg	Offset Type	Offsets:			Azimuth Adjustment	Placement	C _{AA} _{Front}	C _{AA} _{Side}	Weight	
			Horz	Lateral	Vert						ft
			ft	ft	ft	°	ft	ft ²	ft ²	K	
MG D3-800TV w/ Mount Pipe	B	From Leg	4.00	0.00	1.00	0.0000	154.00	1" Ice	5.33	6.16	0.21
								2" Ice	7.34	9.18	0.52
								4" Ice			
								No Ice	3.57	3.42	0.04
								1/2" Ice	3.98	4.12	0.07
								1" Ice	4.39	4.78	0.11
								2" Ice	5.33	6.16	0.21
MG D3-800TV w/ Mount Pipe	C	From Leg	4.00	0.00	1.00	0.0000	154.00	2" Ice	7.34	9.18	0.52
								4" Ice			
								No Ice	3.57	3.42	0.04
								1/2" Ice	3.98	4.12	0.07
								1" Ice	4.39	4.78	0.11
								1" Ice	5.33	6.16	0.21
								2" Ice	7.34	9.18	0.52
BXA-70063/6CF w/ Mount Pipe	A	From Leg	4.00	0.00	1.00	0.0000	154.00	4" Ice			
								No Ice	7.98	5.41	0.04
								1/2" Ice	8.62	6.56	0.10
								1" Ice	9.23	7.42	0.17
								1" Ice	10.47	9.20	0.33
								2" Ice	13.08	12.95	0.79
								4" Ice			
BXA-70063/6CF w/ Mount Pipe	B	From Leg	4.00	0.00	1.00	0.0000	154.00	No Ice	7.98	5.41	0.04
								1/2" Ice	8.62	6.56	0.10
								1" Ice	9.23	7.42	0.17
								1" Ice	10.47	9.20	0.33
								2" Ice	13.08	12.95	0.79
								4" Ice			
								No Ice	7.98	5.41	0.04
BXA-70063/6CF w/ Mount Pipe	C	From Leg	4.00	0.00	1.00	0.0000	154.00	1/2" Ice	8.62	6.56	0.10
								1" Ice	9.23	7.42	0.17
								1" Ice	10.47	9.20	0.33
								2" Ice	13.08	12.95	0.79
								4" Ice			
								No Ice	7.98	5.41	0.04
								1/2" Ice	8.62	6.56	0.10
742 213 w/ Mount Pipe	A	From Leg	4.00	0.00	1.00	0.0000	154.00	1" Ice	5.37	4.62	0.05
								1/2" Ice	5.95	6.00	0.09
								1" Ice	6.50	6.98	0.15
								1" Ice	7.61	8.85	0.28
								2" Ice	9.93	12.79	0.68
								4" Ice			
								No Ice	5.37	4.62	0.05
742 213 w/ Mount Pipe	B	From Leg	4.00	0.00	1.00	0.0000	154.00	1/2" Ice	5.95	6.00	0.09
								1" Ice	6.50	6.98	0.15
								1" Ice	7.61	8.85	0.28
								2" Ice	9.93	12.79	0.68
								4" Ice			
								No Ice	5.37	4.62	0.05
								1/2" Ice	5.95	6.00	0.09
742 213 w/ Mount Pipe	C	From Leg	4.00	0.00	1.00	0.0000	154.00	1" Ice	5.37	4.62	0.05
								1/2" Ice	5.95	6.00	0.09
								1" Ice	6.50	6.98	0.15
								1" Ice	7.61	8.85	0.28
								2" Ice	9.93	12.79	0.68
								4" Ice			
								No Ice	5.37	4.62	0.05
RRH2x40-AWS	A	From Leg	4.00	0.00	1.00	0.0000	154.00	1/2" Ice	2.52	1.59	0.04
								1" Ice	2.75	1.80	0.06
								1" Ice	2.99	2.01	0.08
								1" Ice	3.50	2.46	0.13
								2" Ice	4.61	3.48	0.28
								4" Ice			
								No Ice	2.52	1.59	0.04
RRH2x40-AWS	B	From Leg	4.00	0.00	1.00	0.0000	154.00	1/2" Ice	2.75	1.80	0.06
								1" Ice	2.99	2.01	0.08
								1" Ice	3.50	2.46	0.13
								2" Ice	4.61	3.48	0.28
								4" Ice			
								No Ice	2.52	1.59	0.04
								1/2" Ice	2.75	1.80	0.06
RRH2x40-AWS	C	From Leg	4.00	0.00		0.0000	154.00	No Ice	2.52	1.59	0.04
								1/2" Ice	2.75	1.80	0.06

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C _{AA} Front	C _{AA} Side	Weight
			Horz	Lateral					
			ft	ft	°	ft	ft ²	ft ²	K
			1.00			Ice	2.99	2.01	0.08
						1" Ice	3.50	2.46	0.13
						2" Ice	4.61	3.48	0.28
						4" Ice			
DB-B1-6C-8AB-0Z	C	From Leg	4.00	0.0000	154.00	No Ice	5.60	2.33	0.04
			0.00			1/2"	5.92	2.56	0.08
			1.00			Ice	6.24	2.79	0.12
						1" Ice	6.91	3.28	0.21
						2" Ice	8.37	4.37	0.45
						4" Ice			
Platform Mount [LP 601-1]	C	None		0.0000	154.00	No Ice	28.47	28.47	1.12
						1/2"	33.59	33.59	1.51
						Ice	38.71	38.71	1.91
						1" Ice	48.95	48.95	2.69
						2" Ice	69.43	69.43	4.26
						4" Ice			

DR65-18-00DPL2Q w/ Mount Pipe	A	From Leg	4.00	0.0000	144.00	No Ice	6.54	3.73	0.04
			0.00			1/2"	7.04	4.46	0.09
			2.00			Ice	7.54	5.14	0.14
						1" Ice	8.58	6.56	0.27
						2" Ice	10.78	9.66	0.64
						4" Ice			
DR65-18-00DPL2Q w/ Mount Pipe	B	From Leg	4.00	0.0000	144.00	No Ice	6.54	3.73	0.04
			0.00			1/2"	7.04	4.46	0.09
			2.00			Ice	7.54	5.14	0.14
						1" Ice	8.58	6.56	0.27
						2" Ice	10.78	9.66	0.64
						4" Ice			
DR65-18-00DPL2Q w/ Mount Pipe	C	From Leg	4.00	0.0000	144.00	No Ice	6.54	3.73	0.04
			0.00			1/2"	7.04	4.46	0.09
			2.00			Ice	7.54	5.14	0.14
						1" Ice	8.58	6.56	0.27
						2" Ice	10.78	9.66	0.64
						4" Ice			
KRY 112 144/1	A	From Leg	4.00	0.0000	144.00	No Ice	0.00	0.19	0.01
			0.00			1/2"	0.00	0.26	0.01
			2.00			Ice	0.00	0.33	0.02
						1" Ice	0.00	0.51	0.03
						2" Ice	0.00	0.97	0.08
						4" Ice			
KRY 112 144/1	B	From Leg	4.00	0.0000	144.00	No Ice	0.00	0.19	0.01
			0.00			1/2"	0.00	0.26	0.01
			2.00			Ice	0.00	0.33	0.02
						1" Ice	0.00	0.51	0.03
						2" Ice	0.00	0.97	0.08
						4" Ice			
KRY 112 144/1	C	From Leg	4.00	0.0000	144.00	No Ice	0.00	0.19	0.01
			0.00			1/2"	0.00	0.26	0.01
			2.00			Ice	0.00	0.33	0.02
						1" Ice	0.00	0.51	0.03
						2" Ice	0.00	0.97	0.08
						4" Ice			
KRY 112 89/5	A	From Leg	4.00	0.0000	144.00	No Ice	0.00	0.43	0.02
			0.00			1/2"	0.00	0.53	0.02
			2.00			Ice	0.00	0.64	0.03
						1" Ice	0.00	0.89	0.05
						2" Ice	0.00	1.48	0.11
						4" Ice			
KRY 112 89/5	B	From Leg	4.00	0.0000	144.00	No Ice	0.00	0.43	0.02
			0.00			1/2"	0.00	0.53	0.02
			2.00			Ice	0.00	0.64	0.03
						1" Ice	0.00	0.89	0.05
						2" Ice	0.00	1.48	0.11
						4" Ice			

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C _A A _{Front}	C _A A _{Side}	Weight
			Horz Lateral	Vert					
KRY 112 89/5	C	From Leg	4.00	0.0000	144.00	No Ice	0.00	0.43	0.02
						1/2" Ice	0.00	0.53	0.02
						1" Ice	0.00	0.64	0.03
						2" Ice	0.00	0.89	0.05
						4" Ice	0.00	1.48	0.11
						Platform Mount [LP 601-1]	C	None	
						1/2" Ice	33.59	33.59	1.51
						1" Ice	38.71	38.71	1.91
						2" Ice	48.95	48.95	2.69
						4" Ice	69.43	69.43	4.26

(4) DB844H90E-XY w/ Mount Pipe	A	From Leg	4.00	0.0000	134.00	No Ice	3.30	4.92	0.03
						1/2" Ice	3.69	5.60	0.07
						1" Ice	4.12	6.28	0.12
						2" Ice	5.01	7.71	0.23
						4" Ice	6.92	10.83	0.56
						(4) DB844H90E-XY w/ Mount Pipe	B	From Leg	4.00
			0.00			1/2" Ice	3.69	5.60	0.07
			1.00			1" Ice	4.12	6.28	0.12
						2" Ice	5.01	7.71	0.23
						4" Ice	6.92	10.83	0.56
(4) DB844H90E-XY w/ Mount Pipe	C	From Leg	4.00	0.0000	134.00	No Ice	3.30	4.92	0.03
			0.00			1/2" Ice	3.69	5.60	0.07
			1.00			1" Ice	4.12	6.28	0.12
						2" Ice	5.01	7.71	0.23
						4" Ice	6.92	10.83	0.56
Platform Mount [LP 303-1]	C	None		0.0000	134.00	No Ice	14.66	14.66	1.25
						1/2" Ice	18.87	18.87	1.48
						1" Ice	23.08	23.08	1.71
						2" Ice	31.50	31.50	2.18
						4" Ice	48.34	48.34	3.10
*									
Lightning Rod	C	From Leg	0.00	0.0000	195.00	No Ice	0.25	0.25	0.03
						1/2" Ice	0.66	0.66	0.03
						1" Ice	0.97	0.97	0.04
						2" Ice	1.49	1.49	0.06
						4" Ice	2.68	2.68	0.14
									0.00

Dishes

Description	Face or Leg	Dish Type	Offset Type	Offsets:		Azimuth Adjustment	3 dB Beam Width	Elevation	Outside Diameter	Aperture Area	Weight
				Horz Lateral	Vert						
A-ANT-23G-2-C	B	Paraboloid w/Shroud (HP)	From Leg	4.00	40.0000	164.00	2.17	3.72	No Ice	3.72	0.01
									1/2" Ice	4.01	0.02
									1" Ice	4.30	0.03
									2" Ice	4.88	0.05
									4" Ice	6.04	0.08

Load Combinations

Comb. No.	Description
1	Dead Only
2	Dead+Wind 0 deg - No Ice
3	Dead+Wind 30 deg - No Ice
4	Dead+Wind 60 deg - No Ice
5	Dead+Wind 90 deg - No Ice
6	Dead+Wind 120 deg - No Ice
7	Dead+Wind 150 deg - No Ice
8	Dead+Wind 180 deg - No Ice
9	Dead+Wind 210 deg - No Ice
10	Dead+Wind 240 deg - No Ice
11	Dead+Wind 270 deg - No Ice
12	Dead+Wind 300 deg - No Ice
13	Dead+Wind 330 deg - No Ice
14	Dead+Ice+Temp
15	Dead+Wind 0 deg+Ice+Temp
16	Dead+Wind 30 deg+Ice+Temp
17	Dead+Wind 60 deg+Ice+Temp
18	Dead+Wind 90 deg+Ice+Temp
19	Dead+Wind 120 deg+Ice+Temp
20	Dead+Wind 150 deg+Ice+Temp
21	Dead+Wind 180 deg+Ice+Temp
22	Dead+Wind 210 deg+Ice+Temp
23	Dead+Wind 240 deg+Ice+Temp
24	Dead+Wind 270 deg+Ice+Temp
25	Dead+Wind 300 deg+Ice+Temp
26	Dead+Wind 330 deg+Ice+Temp
27	Dead+Wind 0 deg - Service
28	Dead+Wind 30 deg - Service
29	Dead+Wind 60 deg - Service
30	Dead+Wind 90 deg - Service
31	Dead+Wind 120 deg - Service
32	Dead+Wind 150 deg - Service
33	Dead+Wind 180 deg - Service
34	Dead+Wind 210 deg - Service
35	Dead+Wind 240 deg - Service
36	Dead+Wind 270 deg - Service
37	Dead+Wind 300 deg - Service
38	Dead+Wind 330 deg - Service

Maximum Member Forces

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Force K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
L1	195 - 157.62	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	14	-16.09	-0.11	0.62
			Max. Mx	5	-7.73	-235.66	-0.11
			Max. My	2	-7.73	0.22	233.96
			Max. Vy	5	17.95	-235.66	-0.11
			Max. Vx	2	-17.96	0.22	233.96
			Max. Torque	12			-1.54
			Max Tension	1	0.00	0.00	0.00
L2	157.62 - 117.04	Pole	Max. Compression	14	-35.42	-1.64	-0.49
			Max. Mx	5	-18.95	-1311.46	-3.96
			Max. My	2	-18.98	3.25	1303.04
			Max. Vy	5	33.94	-1311.46	-3.96
			Max. Vx	2	-33.74	3.25	1303.04
			Max. Torque	2			-1.57
			Max Tension	1	0.00	0.00	0.00
			Max. Compression	14	-47.40	-3.29	-1.07
L3	117.04 - 81.58	Pole	Max. Mx	5	-28.66	-2556.62	-7.58

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Force K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
L4	81.58 - 39.99	Pole	Max. My	2	-28.68	5.95	2540.80
			Max. Vy	5	38.05	-2556.62	-7.58
			Max. Vx	2	-37.84	5.95	2540.80
			Max. Torque	2			-1.65
			Max Tension	1	0.00	0.00	0.00
			Max. Compression	14	-66.25	-5.53	-1.86
			Max. Mx	5	-44.66	-4192.51	-11.82
			Max. My	2	-44.67	9.02	4167.96
			Max. Vy	5	42.71	-4192.51	-11.82
			Max. Vx	2	-42.51	9.02	4167.96
L5	39.99 - 0	Pole	Max. Torque	2			-1.75
			Max Tension	1	0.00	0.00	0.00
			Max. Compression	14	-92.12	-8.48	-2.88
			Max. Mx	5	-67.17	-6356.84	-16.78
			Max. My	2	-67.17	12.50	6321.96
			Max. Vy	5	47.30	-6356.84	-16.78
			Max. Vx	2	-47.11	12.50	6321.96
			Max. Torque	2			-1.86

Maximum Reactions

Location	Condition	Gov. Load Comb.	Vertical K	Horizontal, X K	Horizontal, Z K
Pole	Max. Vert	18	92.12	-11.61	-0.02
	Max. H _x	11	67.19	47.26	0.13
	Max. H _z	2	67.19	0.09	47.07
	Max. M _x	2	6321.96	0.09	47.07
	Max. M _z	5	6356.84	-47.26	-0.10
	Max. Torsion	8	1.70	-0.08	-47.02
	Min. Vert	1	67.19	0.00	0.00
	Min. H _x	5	67.19	-47.26	-0.10
	Min. H _z	8	67.19	-0.08	-47.02
	Min. M _x	8	-6313.80	-0.08	-47.02
	Min. M _z	11	-6352.39	47.26	0.13
	Min. Torsion	2	-1.86	0.09	47.07

Tower Mast Reaction Summary

Load Combination	Vertical K	Shear _x K	Shear _z K	Overturning Moment, M _x kip-ft	Overturning Moment, M _z kip-ft	Torque kip-ft
Dead Only	67.19	0.00	0.00	0.18	-2.08	0.00
Dead+Wind 0 deg - No Ice	67.19	-0.09	-47.07	-6321.96	12.50	1.86
Dead+Wind 30 deg - No Ice	67.19	23.52	-40.75	-5473.56	-3160.55	1.61
Dead+Wind 60 deg - No Ice	67.19	40.88	-23.47	-3150.30	-5497.98	0.91
Dead+Wind 90 deg - No Ice	67.19	47.26	0.10	16.78	-6356.84	-0.13
Dead+Wind 120 deg - No Ice	67.19	40.94	23.60	3172.42	-5506.86	-1.07
Dead+Wind 150 deg - No Ice	67.19	23.68	40.75	5473.18	-3187.86	-1.50
Dead+Wind 180 deg - No Ice	67.19	0.08	47.02	6313.80	-14.56	-1.70
Dead+Wind 210 deg - No Ice	67.19	-23.53	40.72	5467.27	3158.99	-1.52
Dead+Wind 240 deg - No Ice	67.19	-40.88	23.48	3152.96	5493.54	-0.98
Dead+Wind 270 deg - No Ice	67.19	-47.26	-0.13	-20.96	6352.39	0.29
Dead+Wind 300 deg - No Ice	67.19	-40.96	-23.64	-3178.11	5506.51	1.21
Dead+Wind 330 deg - No Ice	67.19	-23.70	-40.80	-5480.69	3186.47	1.68
Dead+Ice+Temp	92.12	0.00	0.00	2.88	-8.48	0.00
Dead+Wind 0 deg+Ice+Temp	92.12	-0.02	-11.57	-1606.73	-5.64	0.44
Dead+Wind 30 deg+Ice+Temp	92.12	5.78	-10.02	-1390.84	-812.71	0.31

Load Combination	Vertical	Shear _x	Shear _z	Overturning Moment, M _x	Overturning Moment, M _z	Torque
	K	K	K	kip-ft	kip-ft	kip-ft
Dead+Wind 60 deg+Ice+Temp	92.12	10.04	-5.77	-799.62	-1406.81	0.09
Dead+Wind 90 deg+Ice+Temp	92.12	11.61	0.02	6.59	-1624.97	-0.17
Dead+Wind 120 deg+Ice+Temp	92.12	10.05	5.80	810.24	-1408.66	-0.38
Dead+Wind 150 deg+Ice+Temp	92.12	5.81	10.02	1396.46	-818.62	-0.43
Dead+Wind 180 deg+Ice+Temp	92.12	0.02	11.56	1610.75	-11.44	-0.41
Dead+Wind 210 deg+Ice+Temp	92.12	-5.78	10.01	1395.29	795.74	-0.29
Dead+Wind 240 deg+Ice+Temp	92.12	-10.04	5.77	806.11	1389.19	-0.11
Dead+Wind 270 deg+Ice+Temp	92.12	-11.61	-0.03	-1.66	1607.34	0.21
Dead+Wind 300 deg+Ice+Temp	92.12	-10.06	-5.81	-805.66	1391.98	0.41
Dead+Wind 330 deg+Ice+Temp	92.12	-5.82	-10.03	-1392.30	801.70	0.47
Dead+Wind 0 deg - Service	67.19	-0.03	-16.29	-2189.77	2.93	0.65
Dead+Wind 30 deg - Service	67.19	8.14	-14.10	-1895.88	-1096.19	0.56
Dead+Wind 60 deg - Service	67.19	14.15	-8.12	-1091.13	-1905.87	0.32
Dead+Wind 90 deg - Service	67.19	16.35	0.03	5.93	-2203.39	-0.05
Dead+Wind 120 deg - Service	67.19	14.17	8.17	1099.04	-1908.96	-0.37
Dead+Wind 150 deg - Service	67.19	8.19	14.10	1896.00	-1105.66	-0.52
Dead+Wind 180 deg - Service	67.19	0.03	16.27	2187.17	-6.44	-0.59
Dead+Wind 210 deg - Service	67.19	-8.14	14.09	1893.94	1092.85	-0.53
Dead+Wind 240 deg - Service	67.19	-14.15	8.13	1092.29	1901.54	-0.34
Dead+Wind 270 deg - Service	67.19	-16.35	-0.04	-7.14	2199.06	0.10
Dead+Wind 300 deg - Service	67.19	-14.17	-8.18	-1100.78	1906.05	0.42
Dead+Wind 330 deg - Service	67.19	-8.20	-14.12	-1898.37	1102.38	0.59

Solution Summary

Load Comb.	Sum of Applied Forces			Sum of Reactions			% Error
	PX K	PY K	PZ K	PX K	PY K	PZ K	
1	0.00	-67.19	0.00	0.00	67.19	0.00	0.000%
2	-0.09	-67.19	-47.07	0.09	67.19	47.07	0.000%
3	23.52	-67.19	-40.75	-23.52	67.19	40.75	0.000%
4	40.88	-67.19	-23.47	-40.88	67.19	23.47	0.000%
5	47.26	-67.19	0.10	-47.26	67.19	-0.10	0.000%
6	40.94	-67.19	23.60	-40.94	67.19	-23.60	0.000%
7	23.68	-67.19	40.75	-23.68	67.19	-40.75	0.000%
8	0.08	-67.19	47.02	-0.08	67.19	-47.02	0.000%
9	-23.53	-67.19	40.72	23.53	67.19	-40.72	0.000%
10	-40.88	-67.19	23.48	40.88	67.19	-23.48	0.000%
11	-47.26	-67.19	-0.13	47.26	67.19	0.13	0.000%
12	-40.96	-67.19	-23.64	40.96	67.19	23.64	0.000%
13	-23.70	-67.19	-40.80	23.70	67.19	40.80	0.000%
14	0.00	-92.12	0.00	-0.00	92.12	-0.00	0.000%
15	-0.02	-92.12	-11.57	0.02	92.12	11.57	0.000%
16	5.78	-92.12	-10.02	-5.78	92.12	10.02	0.000%
17	10.04	-92.12	-5.77	-10.04	92.12	5.77	0.000%
18	11.61	-92.12	0.02	-11.61	92.12	-0.02	0.000%
19	10.05	-92.12	5.80	-10.05	92.12	-5.80	0.000%
20	5.81	-92.12	10.02	-5.81	92.12	-10.02	0.000%

Load Comb.	Sum of Applied Forces			Sum of Reactions			% Error
	PX K	PY K	PZ K	PX K	PY K	PZ K	
21	0.02	-92.12	11.56	-0.02	92.12	-11.56	0.000%
22	-5.78	-92.12	10.01	5.78	92.12	-10.01	0.000%
23	-10.04	-92.12	5.77	10.04	92.12	-5.77	0.000%
24	-11.61	-92.12	-0.03	11.61	92.12	0.03	0.000%
25	-10.06	-92.12	-5.81	10.06	92.12	5.81	0.000%
26	-5.82	-92.12	-10.03	5.82	92.12	10.03	0.000%
27	-0.03	-67.19	-16.29	0.03	67.19	16.29	0.000%
28	8.14	-67.19	-14.10	-8.14	67.19	14.10	0.000%
29	14.15	-67.19	-8.12	-14.15	67.19	8.12	0.000%
30	16.35	-67.19	0.03	-16.35	67.19	-0.03	0.000%
31	14.17	-67.19	8.17	-14.17	67.19	-8.17	0.000%
32	8.19	-67.19	14.10	-8.19	67.19	-14.10	0.000%
33	0.03	-67.19	16.27	-0.03	67.19	-16.27	0.000%
34	-8.14	-67.19	14.09	8.14	67.19	-14.09	0.000%
35	-14.15	-67.19	8.13	14.15	67.19	-8.13	0.000%
36	-16.35	-67.19	-0.04	16.35	67.19	0.04	0.000%
37	-14.17	-67.19	-8.18	14.17	67.19	8.18	0.000%
38	-8.20	-67.19	-14.12	8.20	67.19	14.12	0.000%

Non-Linear Convergence Results

Load Combination	Converged?	Number of Cycles	Displacement Tolerance	Force Tolerance
1	Yes	4	0.00000001	0.00000001
2	Yes	4	0.00000001	0.00044879
3	Yes	5	0.00000001	0.00058956
4	Yes	5	0.00000001	0.00057803
5	Yes	4	0.00000001	0.00020782
6	Yes	5	0.00000001	0.00058060
7	Yes	5	0.00000001	0.00059371
8	Yes	4	0.00000001	0.00057937
9	Yes	5	0.00000001	0.00057255
10	Yes	5	0.00000001	0.00058704
11	Yes	4	0.00000001	0.00034254
12	Yes	5	0.00000001	0.00059529
13	Yes	5	0.00000001	0.00057718
14	Yes	4	0.00000001	0.00001351
15	Yes	5	0.00000001	0.00018488
16	Yes	5	0.00000001	0.00022627
17	Yes	5	0.00000001	0.00022612
18	Yes	5	0.00000001	0.00018685
19	Yes	5	0.00000001	0.00022751
20	Yes	5	0.00000001	0.00022797
21	Yes	5	0.00000001	0.00018525
22	Yes	5	0.00000001	0.00022373
23	Yes	5	0.00000001	0.00022488
24	Yes	5	0.00000001	0.00018495
25	Yes	5	0.00000001	0.00022577
26	Yes	5	0.00000001	0.00022413
27	Yes	4	0.00000001	0.00012325
28	Yes	5	0.00000001	0.00004632
29	Yes	5	0.00000001	0.00004432
30	Yes	4	0.00000001	0.00009226
31	Yes	5	0.00000001	0.00004450
32	Yes	5	0.00000001	0.00004676
33	Yes	4	0.00000001	0.00012503
34	Yes	5	0.00000001	0.00004342
35	Yes	5	0.00000001	0.00004574
36	Yes	4	0.00000001	0.00009721
37	Yes	5	0.00000001	0.00004684
38	Yes	5	0.00000001	0.00004388

Maximum Tower Deflections - Service Wind

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
L1	195 - 157.62	42.459	30	1.8482	0.0027
L2	162.37 - 117.04	29.975	30	1.7663	0.0021
L3	122.96 - 81.58	16.796	30	1.3543	0.0010
L4	88.41 - 39.99	8.484	30	0.9033	0.0005
L5	47.99 - 0	2.535	30	0.4768	0.0002

Critical Deflections and Radius of Curvature - Service Wind

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
195.00	Lightning Rod	30	42.459	1.8482	0.0027	65248
185.00	(2) 7770.00 w/ Mount Pipe	30	38.574	1.8388	0.0025	32624
174.00	(4) 8' x 2" Mount Pipe	30	34.344	1.8168	0.0023	15534
166.00	A-ANT-23G-2-C	30	31.324	1.7860	0.0021	11247
164.00	LLPX310R w/ Mount Pipe	30	30.579	1.7756	0.0021	10505
154.00	(2) DB844G65ZAXY w/ Mount Pipe	30	26.929	1.7059	0.0019	7648
144.00	DR65-18-00DPL2Q w/ Mount Pipe	30	23.435	1.6101	0.0016	5971
134.00	(4) DB844H90E-XY w/ Mount Pipe	30	20.143	1.4952	0.0013	4896

Maximum Tower Deflections - Design Wind

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
L1	195 - 157.62	122.308	5	5.3282	0.0079
L2	162.37 - 117.04	86.372	5	5.0925	0.0060
L3	122.96 - 81.58	48.418	5	3.9054	0.0028
L4	88.41 - 39.99	24.468	12	2.6054	0.0014
L5	47.99 - 0	7.314	12	1.3756	0.0006

Critical Deflections and Radius of Curvature - Design Wind

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
195.00	Lightning Rod	5	122.308	5.3282	0.0079	23013
185.00	(2) 7770.00 w/ Mount Pipe	5	111.125	5.3011	0.0072	11506
174.00	(4) 8' x 2" Mount Pipe	5	98.949	5.2378	0.0065	5477
166.00	A-ANT-23G-2-C	5	90.255	5.1491	0.0061	3963
164.00	LLPX310R w/ Mount Pipe	5	88.110	5.1193	0.0061	3702
154.00	(2) DB844G65ZAXY w/ Mount Pipe	5	77.600	4.9185	0.0055	2690
144.00	DR65-18-00DPL2Q w/ Mount Pipe	5	67.542	4.6426	0.0047	2097
134.00	(4) DB844H90E-XY w/ Mount Pipe	5	58.061	4.3114	0.0038	1717

Compression Checks

Pole Design Data

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	F _a ksi	A in ²	Actual P K	Allow. P _a K	Ratio P P _a
L1	195 - 157.62 (1)	TP33.86x25x0.25	37.38	0.00	0.0	39.000	25.7762	-7.73	1005.27	0.008
L2	157.62 - 117.04 (2)	TP42.87x32.2341x0.3125	45.33	0.00	0.0	39.000	40.8340	-18.95	1592.53	0.012
L3	117.04 - 81.58 (3)	TP50.53x40.856x0.375	41.38	0.00	0.0	39.000	57.7965	-28.66	2254.06	0.013
L4	81.58 - 39.99 (4)	TP59.51x48.1832x0.5	48.42	0.00	0.0	39.000	90.6789	-44.66	3536.48	0.013
L5	39.99 - 0 (5)	TP68x56.6386x0.5	47.99	0.00	0.0	39.000	107.122 0	-67.17	4177.78	0.016

Pole Bending Design Data

Section No.	Elevation ft	Size	Actual M _x kip-ft	Actual f _{bx} ksi	Allow. F _{bx} ksi	Ratio f _{bx} F _{bx}	Actual M _y kip-ft	Actual f _{by} ksi	Allow. F _{by} ksi	Ratio f _{by} F _{by}
L1	195 - 157.62 (1)	TP33.86x25x0.25	235.66	13.685	39.000	0.351	0.00	0.000	39.000	0.000
L2	157.62 - 117.04 (2)	TP42.87x32.2341x0.3125	1312.0 7	37.946	39.000	0.973	0.00	0.000	39.000	0.000
L3	117.04 - 81.58 (3)	TP50.53x40.856x0.375	2557.5 1	44.310	39.000	1.136	0.00	0.000	39.000	0.000
L4	81.58 - 39.99 (4)	TP59.51x48.1832x0.5	4193.5 5	39.395	39.000	1.010	0.00	0.000	39.000	0.000
L5	39.99 - 0 (5)	TP68x56.6386x0.5	6357.8 3	42.740	39.000	1.096	0.00	0.000	39.000	0.000

Pole Shear Design Data

Section No.	Elevation ft	Size	Actual V K	Actual f _v ksi	Allow. F _v ksi	Ratio f _v F _v	Actual T kip-ft	Actual f _{vt} ksi	Allow. F _{vt} ksi	Ratio f _{vt} F _{vt}
L1	195 - 157.62 (1)	TP33.86x25x0.25	17.95	0.696	26.000	0.054	1.06	0.030	26.000	0.001
L2	157.62 - 117.04 (2)	TP42.87x32.2341x0.3125	33.97	0.832	26.000	0.064	1.05	0.015	26.000	0.001
L3	117.04 - 81.58 (3)	TP50.53x40.856x0.375	38.08	0.659	26.000	0.051	1.09	0.009	26.000	0.000
L4	81.58 - 39.99 (4)	TP59.51x48.1832x0.5	42.74	0.471	26.000	0.036	1.15	0.005	26.000	0.000
L5	39.99 - 0 (5)	TP68x56.6386x0.5	47.33	0.442	26.000	0.034	1.21	0.004	26.000	0.000

Pole Interaction Design Data


Section No.	Elevation ft	Ratio P P _a	Ratio f _{bx} F _{bx}	Ratio f _{by} F _{by}	Ratio f _v F _v	Ratio f _{vt} F _{vt}	Comb. Stress Ratio	Allow. Stress Ratio	Criteria

Section No.	Elevation ft	Ratio P P_a	Ratio f_{bx} F_{bx}	Ratio f_{by} F_{by}	Ratio f_v F_v	Ratio f_{vt} F_{vt}	Comb. Stress Ratio	Allow. Stress Ratio	Criteria
L1	195 - 157.62 (1)	0.008	0.351	0.000	0.054	0.001	0.359 ✓	1.333	H1-3+VT ✓
L2	157.62 - 117.04 (2)	0.012	0.973	0.000	0.064	0.001	0.986 ✓	1.333	H1-3+VT ✓
L3	117.04 - 81.58 (3)	0.013	1.136	0.000	0.051	0.000	1.150 ✓	1.333	H1-3+VT ✓
L4	81.58 - 39.99 (4)	0.013	1.010	0.000	0.036	0.000	1.023 ✓	1.333	H1-3+VT ✓
L5	39.99 - 0 (5)	0.016	1.096	0.000	0.034	0.000	1.112 ✓	1.333	H1-3+VT ✓

Section Capacity Table

Section No.	Elevation ft	Component Type	Size	Critical Element	P K	SF* P_{allow} K	% Capacity	Pass Fail	
L1	195 - 157.62	Pole	TP33.86x25x0.25	1	-7.73	1340.02	27.0	Pass	
L2	157.62 - 117.04	Pole	TP42.87x32.2341x0.3125	2	-18.95	2122.84	74.0	Pass	
L3	117.04 - 81.58	Pole	TP50.53x40.856x0.375	3	-28.66	3004.66	86.2	Pass	
L4	81.58 - 39.99	Pole	TP59.51x48.1832x0.5	4	-44.66	4714.13	76.8	Pass	
L5	39.99 - 0	Pole	TP68x56.6386x0.5	5	-67.17	5568.98	83.4	Pass	
							Summary		
							Pole (L3)	86.2	Pass
							RATING =	86.2	Pass

APPENDIX B
BASE LEVEL DRAWING



BUSINESS UNIT: 881535 TOWER ID: C_BASELEVEL

BASE LEVEL DRAWING

SCALE: 1" = 1'-0"

1

- 02/07/10 AS-BUILT INFORMATION ADDED PER WORK ORDER # 364833 JN
- 17/11/10 AS-BUILT INFORMATION ADDED PER WORK ORDER # 304831 SM
- 18/04/11 APPLICATION ADDED PER WORK ORDER # 402782 WAM
- 01/08/11 AS-BUILT INFORMATION ADDED PER WORK ORDER # 400704 VP
- 18/04/12 AS-BUILT INFORMATION ADDED PER WORK ORDER # 481317 CAH
- 31/08/12 APPLICATION ADDED PER WORK ORDER # 489178 RJK
- 08/01/14 APPLICATION ADDED PER WORK ORDER # 687712 KT
- 08/01/14 AS-BUILT INFORMATION ADDED PER WORK ORDER # 688063 KT
- 28/05/14 UPDATED PER WORK ORDER # 773818 APR

DRAWN BY: JEP
 CHECKED BY: DMK
 DRAWING DATE: 28/08/07

SITE NUMBER:
 SITE NAME:
 SITE NAME:
 TRUMBELL TOWER
 BUSINESS UNIT NUMBER:
 881535
 SITE ADDRESS:

CT
 FAIRFIELD COUNTY
 USA
 SHEET TITLE:
 BASE LEVEL
 SHEET NUMBER:

A1-0

APPENDIX C
ADDITIONAL CALCULATIONS

Stiffened or Unstiffened, UngROUTED, Circular Base Plate - Any Rod Material

TIA Rev F

Site Data

BU#: 881535
Site Name: TRUMBULL TOWER
App #: 245867
Pole Manufacturer: Other

Reactions		
Moment:	6358	ft-kips
Axial:	67	kips
Shear:	47	kips

Anchor Rod Data		
Qty:	24	
Diam:	2.25	in
Rod Material:	A615-J	
Strength (Fu):	100	ksi
Yield (Fy):	75	ksi
Bolt Circle:	76.5	in

If No stiffeners, Criteria: **AISC ASD** <-Only Applicable to Unstiffened Cases

Anchor Rod Results
 Maximum Rod Tension: 163.4 Kips
 Allowable Tension: 195.0 Kips
 Anchor Rod Stress Ratio: 83.8% **Pass**

Rigid
Service, ASD
Fty*ASIF

Plate Data		
Diam:	82.5	in
Thick:	2.5	in
Grade:	60	ksi
Single-Rod B-eff:	8.99	in

Base Plate Results
 Base Plate Stress: 47.5 ksi
 Allowable Plate Stress: 60.0 ksi
 Base Plate Stress Ratio: 79.2% **Pass**

Flexural Check

Rigid
Service ASD
0.75*Fy*ASIF
Y.L. Length:
35.05

Stiffener Data (Welding at both sides)		
Config:	0	*
Weld Type:	Both	
Groove Depth:	0.25	in **
Groove Angle:	45	degrees
Fillet H. Weld:	0.3125	in
Fillet V. Weld:	0.3125	in
Width:	5	in
Height:	18	in
Thick:	0.75	in
Notch:	0.5	in
Grade:	50	ksi
Weld str.:	70	ksi

n/a


Stiffener Results
 Horizontal Weld : n/a
 Vertical Weld: n/a
 Plate Flex+Shear, fb/Fb+(fv/Fv)^2: n/a
 Plate Tension+Shear, ft/Ft+(fv/Fv)^2: n/a
 Plate Comp. (AISC Bracket): n/a

Pole Results

Pole Punching Shear Check: n/a

Pole Data		
Diam:	68	in
Thick:	0.5	in
Grade:	65	ksi
# of Sides:	18	"0" IF Round
Fu	80	ksi
Reinf. Fillet Weld	0	"0" if None

Stress Increase Factor		
ASIF:	1.333	



* 0 = none, 1 = every bolt, 2 = every 2 bolts, 3 = 2 per bolt

** Note: for complete joint penetration groove welds the groove depth must be exactly 1/2 the stiffener thickness for calculation purposes

(Bearing and Stability Checks) Tool for TIA Rev F or G - Application (MP, SST with unitbase)

Site Data

BU#: 881535
Site Name: TRUMBULL TOWER
App #: 245867

Monopole Base Reaction Forces		
TIA Revision:	F	<--Pull Down
Unfactored DL Axial, PD:	67	kips
Unfactored WL Axial, PW:	0	kips
Unfactored WL Shear, V:	47	kips
Unfactored WL Moment, M:	6358	ft-kips

Enter Load Factors Below:		
For P (DL)	1.2	<---- Enter Factor
For P,V, and M (WL)	1.35	<---- Enter Factor

Load Factor	Shaft Factored Loads		
1.20	1.2D+1.6W, Pu:	80.4	kips
0.90	0.9D+1.6W, Pu:	60.3	kips
1.35	Vu:	63.45	kips
	Mu:	8583.3	ft-kips

Pad & Pier Data		
Base PL Dist. Above Pier:	0	in
Pier Dist. Above Grade:	12	in
Pad Bearing Depth, D:	7	ft
Pad Thickness, T:	3	ft
Pad Width=Length, L:	29	ft
Pier Cross Section Shape:	Square	<--Pull Down
Enter Pier Side Width:	9	ft
Concrete Density:	150.0	pcf
Pier Cross Section Area:	81.00	ft^2
Pier Height:	5.00	ft
Soil (above pad) Height:	4.00	ft

1.2D+1.6W Load Combination, Bearing Results:

(No Soil Wedges) [Reaction+Conc+Soil]	1063.44	P1="1.2D+1.6W" (Kips)
Factored "1.6W" Overturning Moment (MW-Msoil), M1	9004.38	ft-kips

Orthogonal Direction:

ecc1 = M1/P1 = 8.47 ft
 Orthogonal qu= 3.04 ksf
 qu/φ*qn Ratio= **33.77% Pass**

Diagonal Direction:

ecc2 = (0.707M1)/P1 = 5.99 ft
 Diagonal qu= 3.67 ksf
 qu/φ*qn Ratio= **40.75% Pass**

<-- Press Upon Completing All Input

Soil Parameters		
Unit Weight, γ:	125.0	pcf
Ultimate Bearing Capacity, qn:	12.00	ksf
Strength Reduct. factor, φ:	0.75	
Angle of Friction, Φ:	34.0	degrees
Undrained Shear Strength, Cu:	0.00	ksf
Allowable Bearing: φ*qn:	9.00	ksf
Passive Pres. Coeff., Kp	3.54	

Overturning Stability Check

0.9D+1.6W Load Combination, Bearing Results:

Forces/Moments due to Wind and Lateral Soil		
Minimum of (φ*Ultimate Pad Passive Force, Vu):	63.5	kips
Pad Force Location Above D:	1.36	ft
φ(Passive Pressure Moment):	86.52	ft-kips
Factored O.T. M(WL), "1.6W":	9090.9	ft-kips
Factored OT (MW-Msoil), M1	9004.38	ft-kips

(w/ Soil Wedges) [Reaction+Conc+Soil]	842.15	P2="0.9D+1.6W" (Kips)
Factored "1.6W" Overturning Moment (MW-Msoil) - 0.9(M of Wedge + M of Cohesion), M2	8592.95	ft-kips

Resistance due to Foundation Gravity		
Soil Wedge Projection grade, a:	2.70	ft
Sum of Soil Wedges Wt:	49.52	kips
Soil Wedges ecc, K1:	9.23	ft
Ftg+Soil above Pad wt:	819.2	kips
Unfactored (Total ftg-soil Wt):	868.72	kips
1.2D. No Soil Wedges.	1063.44	kips
0.9D. With Soil Wedges	842.15	kips

Orthogonal ecc3 = M2/P2 = 10.20 ft
 Ortho Non Bearing Length,NBL= **20.41 ft**
 Orthogonal qu= 3.38 ksf
 Diagonal qu= 3.97 ksf

Resistance due to Cohesion (Vertical)		
φ*(1/2*Cu)(Total Vert. Planes)	0.00	kips
Cohesion Force Eccentricity, K2	0.00	ft

Max Reaction Moment (ft-kips) so that qu=φ*qn = 100% Capacity Rating			
Actual M:	6358.00		
M Orthogonal:	8044.60	79.03%	Pass
M Diagonal:	8044.60	79.03%	Pass

RADIO FREQUENCY FCC REGULATORY COMPLIANCE
MAXIMUM PERMISSIBLE EXPOSURE (MPE) ASSESSMENT

Sprint Existing Facility

Site ID: CT03XC373

Candid Communications

425 Indian Ledge Park Road
Trumbull, CT 06611

December 22, 2014

EBI Project Number: 62143784

December 22, 2014

Sprint
Attn: RF Engineering Manager
1 International Boulevard, Suite 800
Mahwah, NJ 07495

Re: Radio Frequency Maximum Permissible Exposure (MPE) Assessment for Site:
CT03XC373 - Candid Communications

Site Total: 49.16% - MPE% in full compliance

EBI Consulting was directed to analyze the proposed upgrades to the existing Sprint facility located at 425 Indian Ledge Park Road, Trumbull, CT, for the purpose of determining whether the radio frequency (RF) exposure levels from the proposed Sprint equipment upgrades on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter ($\mu\text{W}/\text{cm}^2$). The number of $\mu\text{W}/\text{cm}^2$ calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits, therefore it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) – (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general public may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general public would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

Public exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter ($\mu\text{W}/\text{cm}^2$). The general population exposure limit for the cellular band (850 MHz Band) is approximately $567 \mu\text{W}/\text{cm}^2$, and the general population exposure limit for the 1900 MHz and 2500 MHz bands is $1000 \mu\text{W}/\text{cm}^2$. Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.

Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure. Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

CALCULATIONS

Calculations were done for the proposed upgrades to the existing Sprint Wireless antenna facility located at 425 Indian Ledge Park Road, Trumbull, CT, using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. All calculations were performed assuming a lobe representing the maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was focused at the base of the tower. For this report the sample point is the top of a 6 foot person standing at the base of the tower.

For all calculations, all emissions were calculated using the following assumptions:

- 1) 2 channels in the 1900 MHz Band were considered for each sector of the proposed installation.
- 2) 1 channel in the 800 MHz Band was considered for each sector of the proposed installation
- 3) 2 channels in the 2500 MHz Band were considered for each sector of the proposed installation.
- 4) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 - Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.
- 5) For the following calculations the sample point was the top of a six foot person standing at the base of the tower. The maximum gain of the antenna per the antenna manufactures supplied specifications minus 10 dB was used in this direction. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.

- 6) The antennas used in this modeling are the RFS APXVSPP18-C-A20 and the RFS APXVTM14-C-I20. This is based on feedback from the carrier with regards to anticipated antenna selection. The RFS APXVSPP18-C-A20 has a 15.9 dBd gain value at its main lobe at 1900 MHz and 13.4 dBd at its main lobe for 850 MHz. The RFS APXVTM14-C-I20 has a 15.9 dBd gain value at its main lobe at 2500 MHz. The maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was used for all calculations. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 7) The antenna mounting height centerline for the proposed antennas is **166 feet** above ground level (AGL).
- 8) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.

All calculation were done with respect to uncontrolled / general public threshold limits

Site ID		CT03XC373 - Candid Communications														
Site Address		425 Indian Ledge Park Road, Trumbull, CT, 06611														
Site Type		Monopole														
Sector 1																
Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain (10 db reduction)	Antenna Height (ft)	analysis height	Cable Size	Cable Loss (dB)	Additional Loss (dB)	ERP	Power Density Percentage
1a	RFS	APXVSP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	2	40	5.9	166	160	1/2 "	0.5	0	138.69	0.19%
1a	RFS	APXVSP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	3.4	166	160	1/2 "	0.5	0	39.00	0.10%
1B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	5.9	166	160	1/2 "	0.5	0	138.69	0.34%
Sector total Power Density Value:															0.63%	
Sector 2																
Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain (10 db reduction)	Antenna Height (ft)	analysis height	Cable Size	Cable Loss (dB)	Additional Loss (dB)	ERP	Power Density Percentage
2a	RFS	APXVSP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	2	40	5.9	166	160	1/2 "	0.5	0	138.69	0.19%
2a	RFS	APXVSP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	3.4	166	160	1/2 "	0.5	0	39.00	0.10%
2B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	5.9	166	160	1/2 "	0.5	0	138.69	0.34%
Sector total Power Density Value:															0.63%	
Sector 3																
Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain (10 db reduction)	Antenna Height (ft)	analysis height	Cable Size	Cable Loss (dB)	Additional Loss (dB)	ERP	Power Density Percentage
3a	RFS	APXVSP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	2	40	5.9	166	160	1/2 "	0.5	0	138.69	0.19%
3a	RFS	APXVSP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	3.4	166	160	1/2 "	0.5	0	39.00	0.10%
3B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	5.9	166	160	1/2 "	0.5	0	138.69	0.34%
Sector total Power Density Value:															0.63%	

Site Composite MPE %	
Carrier	MPE %
Sprint	1.90%
Town	4.80%
AT&T	8.18%
Sprint MW	0.08%
Clearwire	0.69%
Verizon Wireless	24.61%
T-Mobile	4.73%
Nextel	4.17%
Total Site MPE %	49.16%

Summary

All calculations performed for this analysis yielded results that were well within the allowable limits for general public Maximum Permissible Exposure (MPE) to radio frequency energy.

The anticipated Maximum Composite contributions from the Sprint facility are **1.90% (0.63% from sector 1, 0.63% from sector 2 and 0.63% from sector 3)** of the allowable FCC established general public limit considering all three sectors simultaneously sampled at the ground level.

The anticipated composite MPE value for this site assuming all carriers present is **49.16%** of the allowable FCC established general public limit sampled at 6 feet above ground level. This total composite site value is based upon MPE values listed in the Connecticut Siting Council database for existing carrier emissions.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.



Scott Heffernan
RF Engineering Director

EBI Consulting
21 B Street
Burlington, MA 01803



Practical Solutions, Exceptional Service

CORPORATE OFFICE
Mountainville, NY (800) 829-6531

1279 Route 300
Newburgh, NY 12550

(845) 567-6656 FAX: (845) 567-8703
www.tectonicengineering.com

December 10, 2014

STRUCTURAL ANALYSIS EVALUATION LETTER

Michelle Hisert
Real Estate Manager III
Upstate NY and Southern Connecticut
Sprint, Regional Site Development
michelle.hisert@sprint.com

Site Number: CT03XC373
Site Name: CANDID COMMUNICATIONS
Site Address: 307 Indian Ledge Park, Trumbull, CT 06611
Crown ID#: 881535

Project Number: 7225-Crown-Sprint 2.5
Project Name: Sprint 2.5 Equipment Deployment
Work Order: 7225.CT03XC373

Dear Ms. Hisert,

This letter is to confirm Tectonic Engineering and Surveying Consultants P.C.'s (TECTONIC) structural assessment of the existing Sprint antenna mounting system on the site noted above. The intent of the review is to determine if the load from the proposed modification of antennas and equipment will exceed the structural capacity of the existing antenna mounting system.

The existing antenna mounting system has been categorized as a low-profile platform. Currently Sprint has three (3) antennas mounted to the frame at a RAD elevation of approximately one hundred sixty six feet (166'-0") above ground level. Sprint is proposing to install three (3) new antennas and associated appurtenances as part of this upgrade. The final configuration upon this installation will be as follows:

- 3 (E) RFS APXVSP18-C-A20 (72.0"Hx11.8"Wx7.0"D, 57 lbs.) panel antennas, one (1) per sector, mounted to steel pipes.
- 3 (E) Alcatel Lucent 1900 MHZ 4x45W (25.0"Hx11.1"Wx11.4"D, 60 lbs.), one (1) per sector, mounted to steel pipes.
- 3 (E) Alcatel Lucent 800 MHz 2x50w (19.7"Hx13.0"Wx10.8"D, 53 lbs.), one (1) per sector, mounted to steel pipes.
- 3 (E) Clearwire Argus LLPX310R (42.1"Hx11.8"Wx4.5"D, 28.7 lbs.) panel antennas, one (1) per sector, mounted to steel pipes.
- 3 (E) Clearwire Samsung FDD R6 RRH (16.0"Hx11.5"Wx5.0"D, 33 lbs.), one (1) per sector, mounted to steel pipes.
- 1 (E) Clearwire Dragonwave A-ANT-23G-2-C (26.1"Hx26.1"Wx13.2"D, 27.1 lbs.) microwave dish, mounted to a steel pipe.
- 3 (P) RFS APXVTM14-C-120 (56.3"Hx12.6"Wx6.3"D, 56 lbs.) panel antennas, one (1) per sector, mounted to steel pipes.
- 3 (P) Alcatel Lucent TD-RRH8x20-25 (26.1"Hx18.6"Wx6.7"D, 70 lbs.), one (1) per sector, mounted to steel pipes.
- 3 (E) 1-1/4" diameter Hybrid Power/Fiber cables routed along the interior of the pole up to the antennas.
- 1 (P) 5/8" diameter Fiber cable routed along the interior of the pole up to the antennas.

Proposed antennas are to be installed at the same RAD elevation as the existing antennas.

WO. No.: 7225.CT03XC373
CANDID COMMUNICATIONS

December 10, 2014 | Page 2

This generic low-profile platform **is believed** to have the following characteristics:

- Triangular low-profile platform with a nominal face width of about twelve feet (12'-0").
- Antenna mounting pipes are made from 2 inch standard pipe stock (2.375" OD).
- Main horizontal members are made from steel angles L4x4x1/4.

The review and the analysis is based on ANSI/TIA/EIA-222-F-1996 "Structural Standards for Steel Antenna Towers and Antenna Supporting Structures", using a basic wind speed of eighty five (85) mph with no ice and seventy four (74) mph with half inch (0.5") of radial ice at one hundred and sixty six feet (166'-0") above ground level.

By engineering analysis and comparison, the existing antenna mounting system will be capable of supporting the proposed Sprint upgrade **once a new handrail kit is installed on the platform as specifically shown on the construction drawings prepared by TECTONIC.**

This certification is based on the information provided by the client and a limited visual inspection from the ground. This certification also assumes that all structural members are in good condition.

A detailed mapping of the mount was not performed. Therefore the contractor shall field verify mount member sizes and field conditions, and notify the design engineer of any discrepancies prior to installation of the proposed upgrade. Any further changes to the antenna or other appurtenances configuration and location should be reviewed with respect to their effect on structural loads prior to implementation.

The existing structure analysis is completed by others and therefore not part of this assessment.

Should you have any questions, please do not hesitate to contact us.

Sincerely,

TECTONIC



Manojkumar Patel, P.E.
Sr. Project Manager