

STATE OF CONNECTICUT

CONNECTICUT SITING COUNCIL

Ten Franklin Square, New Britain, CT 06051

Phone: (860) 827-2935 Fax: (860) 827-2950

E-Mail: siting.council@ct.gov

www.ct.gov/csc

May 29, 2012

Jennifer Young Gaudet
HPC Wireless Services
46 Mill Plain Road, Floor 2
Danbury, CT 06811

RE: **EM-CING-151-120511** - New Cingular Wireless PCS, LLC (AT&T) notice of intent to modify an existing telecommunications facility located at 670 Captain Neville Road, Waterbury, Connecticut.

Dear Ms. Gaudet:

The Connecticut Siting Council (Council) hereby acknowledges your notice to modify this existing telecommunications facility, pursuant to Section 16-50j-73 of the Regulations of Connecticut State Agencies with the following conditions:

- Any deviation from the proposed modification as specified in this notice and supporting materials with Council shall render this acknowledgement invalid;
- Any material changes to this modification as proposed shall require the filing of a new notice with the Council;
- Not less than 45 days after completion of construction, the Council shall be notified in writing that construction has been completed;
- The validity of this action shall expire one year from the date of this letter; and
- The applicant may file a request for an extension of time beyond the one year deadline provided that such request is submitted to the Council not less than 60 days prior to the expiration;

The proposed modifications including the placement of all necessary equipment and shelters within the tower compound are to be implemented as specified here and in your notice dated May 9, 2012. The modifications are in compliance with the exception criteria in Section 16-50j-72 (b) of the Regulations of Connecticut State Agencies as changes to an existing facility site that would not increase tower height, extend the boundaries of the tower site, increase noise levels at the tower site boundary by six decibels, and increase the total radio frequencies electromagnetic radiation power density measured at the tower site boundary to or above the standard adopted by the State Department of Environmental Protection pursuant to General Statutes § 22a-162. This facility has also been carefully modeled to ensure that radio frequency emissions are conservatively below State and federal standards applicable to the frequencies now used on this tower.

This decision is under the exclusive jurisdiction of the Council. Please be advised that the validity of this action shall expire one year from the date of this letter. Any additional change to this facility will require explicit notice to this agency pursuant to Regulations of Connecticut State Agencies



Section 16-50j-73. Such notice shall include all relevant information regarding the proposed change with cumulative worst-case modeling of radio frequency exposure at the closest point of uncontrolled access to the tower base, consistent with Federal Communications Commission, Office of Engineering and Technology, Bulletin 65. Thank you for your attention and cooperation.

Very truly yours,

A handwritten signature in black ink that reads "Linda Roberts". The signature is written in a cursive, flowing style.

Linda Roberts
Executive Director

LR/cm

c: The Honorable Neil M. O'Leary, Mayor, City of Waterbury
Gil Grabeline, Zoning Enforcement Officer, City of Waterbury

EM-CING-151-120511

HPC Wireless Services

46 Mill Plain Rd.

Floor 2

Danbury, CT, 06811

P.: 203.797.1112



ORIGINAL

May 9, 2012

VIA OVERNIGHT COURIER

RECEIVED
MAY 11 2012

CONNECTICUT
SITING COUNCIL

Connecticut Siting Council
10 Franklin Square
New Britain, Connecticut 06051
Attn: Ms. Linda Roberts, Executive Director

Re: New Cingular Wireless PCS, LLC – exempt modification
670 Captain Neville Road, Waterbury, Connecticut

Dear Ms. Roberts:

This letter and attachments are submitted on behalf of New Cingular Wireless PCS, LLC (“AT&T”). AT&T is making modifications to certain existing sites in its Connecticut system in order to implement LTE technology. Please accept this letter and attachments as notification, pursuant to R.C.S.A. Section 16-50j-73, of construction that constitutes an exempt modification pursuant to R.C.S.A. Section 16-50j-72(b)(2). In compliance with R.C.S.A. Section 16-50j-73, a copy of this letter and attachments is being sent to the Mayor of the City of Waterbury.

AT&T plans to modify the existing wireless communications facility owned by Crown Castle and located at 670 Captain Neville Road in the City of Waterbury (coordinates 41°-32’-03” N, 72°-58’-08” W). Attached are a compound plan and elevation depicting the planned changes, and documentation of the structural sufficiency of the structure to accommodate the revised antenna configuration. Also included is a power density report reflecting the modification to AT&T’s operations at the site.

The changes to the facility do not constitute a modification as defined in Connecticut General Statutes (“C.G.S.”) Section 16-50i(d) because the general physical characteristics of the facility will not be significantly changed. Rather, the planned changes to the facility fall squarely within those activities explicitly provided for in R.C.S.A. Section 16-50j-72(b)(2).

1. AT&T will add three (3) LTE antennas to the six (6) antennas on the existing platform; all will have a center line of approximately 150’. Six (6) RRUs (remote radio

Boston

Albany

Buffalo

Danbury

Philadelphia

Raleigh

Atlanta

units) will be mounted, two (2) each, behind the LTE antennas and a surge arrestor will be mounted to an unused pipe mount on the platform. AT&T will also place a DC power and fiber run from the equipment to the antennas within the tower along the existing coaxial cable run. The proposed modifications will not extend the height of the approximately 150' structure.

2. The proposed changes will not extend the site boundaries. AT&T will install related equipment within its existing shelter and will mount a GPS antenna to the shelter. These changes will be within the existing compound and will have no effect on the site boundaries.

3. The proposed changes will not increase the noise level at the existing facility by six decibels or more. The incremental effect of the proposed changes will be negligible.

4. The changes to the facility will not increase the calculated "worst case" power density for the combined operations at the site to a level at or above the applicable standard for uncontrolled environments as calculated for a mixed frequency site. As indicated on the attached report prepared by C Squared Systems, LLC, AT&T's operations at the site will result in a power density of approximately 1.59%; the combined site operations will result in a total power density of approximately 4.21%.

Please feel free to contact me by phone at (860) 798-7454 or by e-mail at jgaudet@hpcwireless.com with questions concerning this matter. Thank you for your consideration.


Respectfully yours,



Jennifer Young Gaudet

Attachments

cc: Honorable Neil M. O'Leary, Mayor, City of Waterbury
MW Cell REIT 1, LLC (underlying property owner)




NOTES:
1. AZIMUTHS BASED ON TRUE NORTH.

PLATFORM ANTENNA ORIENTATION
SCALE: N.T.S.

3

ISOMETRIC ANTENNA DETAILS
SCALE: N.T.S.


2



NOTES:
1. PRIOR TO START OF ANY WORK, A PASSING STRUCTURAL ANALYSIS SHALL BE OBTAINED FROM THE STRUCTURAL CONTRACTOR TO OBTAIN COPY BEFORE STARTING ANY WORK.
2. ALL ANTENNAS AND COAX TO BE INSTALLED SHALL BE INSTALLED BY STRUCTURAL CONTRACTOR. STRUCTURAL ANALYSIS PROVIDED BY CROWN CASTLE AND FINAL ART BY DATA SHEET.

ELEVATION LOOKING NORTHWEST
SCALE: 1/4\"/>

1



NOTES:
1. ALL ANTENNAS, COAX AND ANTENNA SUPPORT SHALL BE INSTALLED BY STRUCTURAL CONTRACTOR WITH STRUCTURAL ANALYSIS AND FINAL RF DATA SHEET.

RRUS-11 AND SURGE PROTECTOR MOUNTING DETAIL
SCALE: N.T.S.

5

NO.		DATE	REVISIONS	DESIGNED BY: CHM	DRAWN BY: JRF
1	04/26/12		ISSUED FOR SUBMITTAL	JME JMS DRK	JRF JMS DRK
0	02/07/12		PRELIMINARY SUBMISSION	JRF JMS DRK	JRF JMS DRK

Dewberry
Engineers Inc.
600 FINESTREET ROAD
WATERBURY, CT 06705
PHONE: 978.752.9400
FAX: 978.752.6750

at&t
WATERBURY EAST
SITE NO. 011127
670 CAPTAIN NESHLE DRIVE
WATERBURY, CT 06705
CROWN SITE #881534

ELEVATION & CONSTRUCTION DETAILS
DEWBERRY NO. 50048347/50048371
DRAWING NUMBER A02
REV 1



Date: April 19, 2012

Veronica Harris
Crown Castle
1200 McArthur Blvd
Mahwah, NJ 07430

FDH Engineering, Inc.
2730 Rowland Rd.
Raleigh NC 27615
(919) 755-1012

Subject: Structural Analysis Report

Carrier Designation:	AT&T Mobility Co-Locate	
	Carrier Site Number:	CT1127
	Carrier Site Name:	WATERBURY-NH63
Crown Castle Designation:	Crown Castle BU Number:	881534
TOWER	Crown Castle Site Name:	WATERBURY
	Crown Castle JDE Job Number:	183466
	Crown Castle Work Order Number:	482683
	Crown Castle Application Number:	144446 Rev. 2
Engineering Firm Designation:	FDH Engineering, Inc. Project Number:	12-04404ES1
Site Data:	670 Captain Neville Drive, Waterbury, New Haven County, CT	
	Latitude 41° 32' 3.55", Longitude -72° 58' 10"	
	150.0 Foot - Monopole Tower	

Dear Veronica Harris,

FDH Engineering, Inc. is pleased to submit this "Structural Analysis Report" to determine the structural integrity of the above mentioned tower. This analysis has been performed in accordance with the Crown Castle Structural 'Statement of Work' and the terms of Crown Castle Purchase Order Number 458613, in accordance with application 144446, revision 2.

The purpose of the analysis is to determine acceptability of the tower stress level. Based on our analysis we have determined the tower stress level for the structure and foundation, under the following load case, to be:

LC5: Existing + Proposed Equipment

Sufficient Capacity

Note: See Table I and Table II for the proposed and existing/reserved loading, respectively.


The analysis has been performed in accordance with the TIA/EIA-222-F standard and 2005 Connecticut Building Code based upon a wind speed of 85 mph fastest mile.

All modifications and equipment proposed in this report shall be installed in accordance with the attached drawings for the determined available structural capacity to be effective.

We at FDH Engineering, Inc. appreciate the opportunity of providing our continuing professional services to you and Crown Castle. If you have any questions or need further assistance on this or any other projects please give us a call.

Structural analysis prepared by:

Respectfully submitted by:


Chad Barham
Project Engineer

Christopher M Murphy, PE
President
Connecticut PE No. 25842



TABLE OF CONTENTS

1) INTRODUCTION

2) ANALYSIS CRITERIA

Table 1 - Proposed Antenna and Cable Information

Table 2 - Existing and Reserved Antenna and Cable Information

Table 3 - Design Antenna and Cable Information

3) ANALYSIS PROCEDURE

Table 4 - Documents Provided

3.1) Analysis Method

3.2) Assumptions

4) ANALYSIS RESULTS

Table 5 - Section Capacity (Summary)

Table 6 – Tower Components vs. Capacity

4.1) Recommendations

5) APPENDIX A

tnxTower Output

6) APPENDIX B

Base Level Drawing

7) APPENDIX C

Additional Calculations

1) INTRODUCTION

This tower is a 150.0 ft Monopole tower designed by ENGINEERED ENDEAVORS, INC. in February of 2000. The tower was originally designed for a wind speed of 85 mph per TIA/EIA-222-F.

2) ANALYSIS CRITERIA

The structural analysis was performed for this tower in accordance with the requirements of TIA/EIA-222-F Structural Standards for Steel Antenna Towers and Antenna Supporting Structures using a fastest mile wind speed of 85 mph with no ice, 38 mph with .75 inch ice thickness and 50 mph under service loads.

Table 1 - Proposed Antenna and Cable Information

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)	Note
150.0	150.0	2	andrew	SBNH-1D6565C w/ Mount Pipe	2 1	3/4" 3/8"	1
		6	ericsson	RRUS-11			
		1	kmw communications	AM-X-CD-16-65-00T-RET w/ Mount Pipe			
		1	raycap	DC6-48-60-18-8F			
148.0	148.0	1	crown mounts	Side Arm Mount [SO 102-3]			

Notes:

- 1) Proposed Equipment

Table 2 - Existing and Reserved Antenna and Cable Information

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)	Note
150.0	150.0	1	crown mounts	Platform Mount [LP 601-1]	12	1-5/8"	1
		6	powerwave technologies	7770.00 w/ Mount Pipe			
		6	powerwave technologies	LGP13519			
		6	powerwave technologies	LGP21401			
140.0	142.0	2	andrew	VHLP2-11	3 3 3	5/16" 1/4" 1/2"	1
		1	andrew	VHLP2-18			
		1	andrew	VHLP2-23			
		1	motorola	TIMING 2000			
	140.0	3	argus technologies	LLPX310R w/ Mount Pipe			
		1	crown mounts	Platform Mount [LP 601-1]			
		4	dragonwave	Horizon Compact			
		3	samsung telecommunications	WIMAX DAP HEAD			

Notes:

- 1) Existing Equipment

Table 3 - Design Antenna and Cable Information

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)
150	150	12	Allgon	A-800-110	---	---
140	140	12	Allgon	A-800-110	---	1-5/8"
130	130	12	Allgon	A-800-110	---	1-5/8"
120	120	12	Allgon	A-800-110	---	1-5/8"

3) ANALYSIS PROCEDURE

Table 4 - Documents Provided

Document	Remarks	Reference	Source
4-GEOTECHNICAL REPORTS	Dr. Clarence Welti, PE, P.C. (November 30, 1999)	1405752	CCISITES
4-TOWER FOUNDATION DRAWINGS/DESIGN/SPECS	AES (March 2, 2000)	1406237	CCISITES
4-TOWER MANUFACTURER DRAWINGS	EEI (February 17, 2000)	1405785	CCISITES

3.1) Analysis Method

tnxTower (version 6.0.4.0), a commercially available analysis software package, was used to create a three-dimensional model of the tower and calculate member stresses for various loading cases. Selected output from the analysis is included in Appendix A.

3.2) Assumptions

- 1) Tower and structures were built in accordance with the manufacturer's specifications.
- 2) The tower and structures have been maintained in accordance with the manufacturer's specification.
- 3) The configuration of antennas, transmission cables, mounts and other appurtenances are as specified in Tables 1 and 2 and the referenced drawings.
- 4) When applicable, transmission cables are considered as structural components for calculating wind loads as allowed by TIA/EIA-222-F.

This analysis may be affected if any assumptions are not valid or have been made in error. FDH Engineering, Inc. should be notified to determine the effect on the structural integrity of the tower.

4) ANALYSIS RESULTS

Table 5 - Section Capacity (Summary)

Section No.	Elevation (ft)	Component Type	Size	Critical Element	P (K)	SF*P_allow (K)	% Capacity	Pass / Fail
L1	150.004 - 123.294	Pole	TP23.17x17x0.1875	1	-4.41	686.63	67.4	Pass
L2	123.294 - 87.7903	Pole	TP30.86x22.0057x0.3125	2	-8.17	1523.35	68.0	Pass
L3	87.7903 - 43.207	Pole	TP40.4x29.2302x0.375	3	-15.42	2397.89	66.6	Pass
L4	43.207 - 0	Pole	TP49.5x38.3773x0.4375	4	-23.47	3279.87	60.3	Pass
							Summary	

Section No.	Elevation (ft)	Component Type	Size	Critical Element	P (K)	SF*P_allow (K)	% Capacity	Pass / Fail
						Pole (L2)	68.0	Pass
						Rating =	68.0	Pass

Table 6 - Tower Component Stresses vs. Capacity – LC5

Notes	Component	Elevation (ft)	% Capacity	Pass / Fail
1	Anchor Rods	0	55.5	Pass
1	Base Plate	0	74.1	Pass
1	Base Foundation	0	46.1	Pass

Structure Rating (max from all components) =	74.1%
---	--------------

Notes:

- 1) See additional documentation in "Appendix C – Additional Calculations" for calculations supporting the % capacity consumed.

4.1) Recommendations

1. Proposed coax must be installed as shown in Appendix B.



C Squared Systems, LLC
65 Dartmouth Drive, Unit A3
Auburn, NH 03032
(603) 644-2800
support@csquaredsystems.com

Calculated Radio Frequency Emissions



CT1127

(Waterbury-NH63)

670 Captain Neville Drive, Waterbury, CT 06705

(a.k.a. Captain Neville Drive)

April 25, 2012

Table of Contents

1. Introduction.....	1
2. FCC Guidelines for Evaluating RF Radiation Exposure Limits.....	1
3. RF Exposure Prediction Methods.....	2
4. Calculation Results	3
5. Conclusion	4
6. Statement of Certification.....	4
Attachment A: References.....	5
Attachment B: FCC Limits for Maximum Permissible Exposure (MPE).....	6
Attachment C: AT&T Antenna Data Sheets and Electrical Patterns.....	8

List of Tables

Table 1: Carrier Information.....	3
Table 2: FCC Limits for Maximum Permissible Exposure (MPE).....	6

List of Figures

Figure 1: Graph of FCC Limits for Maximum Permissible Exposure (MPE).....	7
---	---

1. Introduction

The purpose of this report is to investigate compliance with applicable FCC regulations for the proposed modifications to the existing AT&T antenna arrays mounted on the monopole tower located at 670 Captain Neville Drive in Waterbury, CT. The coordinates of the tower are 41-32-3.6 N, 72-58-8.5 W.

AT&T is proposing the following modifications:

- 1) Install three multi-band (700/850/1900/2100 MHz) antennas (one per sector).

2. FCC Guidelines for Evaluating RF Radiation Exposure Limits

In 1985, the FCC established rules to regulate radio frequency (RF) exposure from FCC licensed antenna facilities. In 1996, the FCC updated these rules, which were further amended in August 1997 by OET Bulletin 65 Edition 97-01. These new rules include Maximum Permissible Exposure (MPE) limits for transmitters operating between 300 kHz and 100 GHz. The FCC MPE limits are based upon those recommended by the National Council on Radiation Protection and Measurements (NCRP), developed by the Institute of Electrical and Electronics Engineers, Inc., (IEEE) and adopted by the American National Standards Institute (ANSI).

The FCC general population/uncontrolled limits set the maximum exposure to which most people may be subjected. General population/uncontrolled exposures apply in situations in which the general public may be exposed, or in which persons that are exposed as a consequence of their employment may not be fully aware of the potential for exposure or cannot exercise control over their exposure.

Public exposure to radio frequencies is regulated and enforced in units of milliwatts per square centimeter (mW/cm^2). The general population exposure limits for the various frequency ranges are defined in the attached "FCC Limits for Maximum Permissible Exposure (MPE)" in Attachment B of this report.

Higher exposure limits are permitted under the occupational/controlled exposure category, but only for persons who are exposed as a consequence of their employment and who have been made fully aware of the potential for exposure, and they must be able to exercise control over their exposure. General population/uncontrolled limits are five times more stringent than the levels that are acceptable for occupational, or radio frequency trained individuals. Attachment B contains excerpts from OET Bulletin 65 and defines the Maximum Exposure Limit.

Finally, it should be noted that the MPE limits adopted by the FCC for both general population/uncontrolled exposure and for occupational/controlled exposure incorporate a substantial margin of safety and have been established to be well below levels generally accepted as having the potential to cause adverse health effects.

3. RF Exposure Prediction Methods

The emission field calculation results displayed in the following figures were generated using the following formula as outlined in FCC bulletin OET 65:

$$\text{Power Density} = \left(\frac{1.6^2 \times EIRP}{4\pi \times R^2} \right) \times \text{Off Beam Loss}$$

Where:

EIRP = Effective Isotropic Radiated Power

R = Radial Distance = $\sqrt{(H^2 + V^2)}$

H = Horizontal Distance from antenna in meters

V = Vertical Distance from radiation center of antenna in meters

Ground reflection factor of 1.6

Off Beam Loss is determined by the selected antenna pattern

These calculations assume that the antennas are operating at 100 percent capacity and power, and that all channels are transmitting simultaneously. Obstructions (trees, buildings, etc.) that would normally attenuate the signal are not taken into account. The calculations assume even terrain in the area of study and do not take into account actual terrain elevations which could attenuate the signal. As a result, the predicted signal levels reported below are much higher than the actual signal levels will be from the finished modifications.

4. Calculation Results

Table 1 below outlines the power density information for the site. Because the proposed AT&T antennas are directional in nature, the majority of the RF power is focused out towards the horizon. As a result, there will be less RF power directed below the antennas relative to the horizon, and consequently lower power density levels around the base of the tower. Please refer to Attachment C for the vertical pattern of the proposed AT&T antennas. The calculated results for AT&T in Table 1 include a nominal 10 dB off-beam pattern loss to account for the lower relative gain below the antennas.

Carrier	Antenna Height (Feet)	Operating Frequency (MHz)	Number of Trans.	ERP Per Transmitter (Watts)	Power Density (mw/cm ²)	Limit	%MPE
<i>Cingular UMTS</i>	150	880	1	500	0.0080	0.5867	1.36%
<i>Cingular GSM</i>	150	880	3	296	0.0142	0.5867	2.42%
<i>Cingular GSM</i>	150	1900	2	427	0.0136	1.0000	1.36%
Clearwire antennas	140	2496	2	153	0.0056	1.0000	0.56%
Clearwire microwave dishes	140	11 GHz	1	211	0.0039	1.0000	0.39%
Clearwire microwave dishes	140	11 GHz	1	211	0.0039	1.0000	0.39%
Clearwire microwave dishes	140	11 GHz	1	211	0.0039	1.0000	0.39%
XM Sat Radio	158.5	2337.49	2	312	0.0089	1.0000	0.89%
AT&T UMTS	150	880	2	565	0.0018	0.5867	0.31%
AT&T UMTS	150	1900	2	1077	0.0034	1.0000	0.34%
AT&T LTE	150	734	1	1375	0.0022	0.4893	0.45%
AT&T GSM	150	880	1	283	0.0005	0.5867	0.08%
AT&T GSM	150	1900	4	646	0.0041	1.0000	0.41%
						Total	4.21%

Table 1: Carrier Information^{1 2}

¹ The existing CSC filing for Cingular should be removed and replaced with the updated AT&T technologies and values provided in Table 1. The power density information for carriers other than AT&T was taken directly from the CSC database dated 3/29/2012. Please note that %MPE values listed are rounded to two decimal points. The total %MPE listed is a summation of each unrounded contribution. Therefore, summing each rounded value may not reflect the total value listed in the table.

² In the case where antenna models are not uniform across all 3 sectors for the same frequency band, the antenna model with the highest gain was used for the calculations to present a worse-case scenario.

5. Conclusion

The above analysis verifies that emissions from the existing site will be below the maximum power density levels as outlined by the FCC in the OET Bulletin 65 Ed. 97-01. Even when using conservative methods, the cumulative power density from the proposed transmit antennas at the existing facility is well below the limits for the general public. The highest expected percent of Maximum Permissible Exposure at ground level is **4.21% of the FCC limit**.

As noted previously, obstructions (trees, buildings, etc.) that would normally attenuate the signal are not taken into account. As a result, the predicted signal levels are more conservative (higher) than the actual signal levels will be from the finished modifications.

6. Statement of Certification

I certify to the best of my knowledge that the statements in this report are true and accurate. The calculations follow guidelines set forth in ANSI/IEEE Std. C95.3, ANSI/IEEE Std. C95.1 and FCC OET Bulletin 65 Edition 97-01.



Daniel L. Goulet
C Squared Systems, LLC

April 25, 2012

Date

Attachment A: References

OET Bulletin 65 - Edition 97-01 - August 1997 Federal Communications Commission Office of Engineering & Technology

ANSI C95.1-1982, American National Standard Safety Levels With Respect to Human Exposure to Radio Frequency Electromagnetic Fields, 300 kHz to 100 GHz. IEEE-SA Standards Board

IEEE Std C95.3-1991 (Reaff 1997), IEEE Recommended Practice for the Measurement of Potentially Hazardous Electromagnetic Fields - RF and Microwave. IEEE-SA Standards Board

Attachment B: FCC Limits for Maximum Permissible Exposure (MPE)

(A) Limits for Occupational/Controlled Exposure³

Frequency Range (MHz)	Electric Field Strength (E) (V/m)	Magnetic Field Strength (E) (A/m)	Power Density (S) (mW/cm ²)	Averaging Time E ² , H ² or S (minutes)
0.3-3.0	614	1.63	(100)*	6
3.0-30	1842/f	4.89/f	(900/f ²)*	6
30-300	61.4	0.163	1.0	6
300-1500	-	-	f/300	6
1500-100,000	-	-	5	6

(B) Limits for General Population/Uncontrolled Exposure⁴

Frequency Range (MHz)	Electric Field Strength (E) (V/m)	Magnetic Field Strength (E) (A/m)	Power Density (S) (mW/cm ²)	Averaging Time E ² , H ² or S (minutes)
0.3-1.34	614	1.63	(100)*	30
1.34-30	824/f	2.19/f	(180/f ²)*	30
30-300	27.5	0.073	0.2	30
300-1500	-	-	f/1500	30
1500-100,000	-	-	1.0	30

f = frequency in MHz * Plane-wave equivalent power density

Table 2: FCC Limits for Maximum Permissible Exposure (MPE)

³ Occupational/controlled limits apply in situations in which persons are exposed as a consequence of their employment provided those persons are fully aware of the potential for exposure and can exercise control over their exposure. Limits for occupational/controlled exposure also apply in situations when an individual is transient through a location where occupational/controlled limits apply provided he or she is made aware of the potential for exposure

⁴ General population/uncontrolled exposures apply in situations in which the general public may be exposed, or in which persons that are exposed as a consequence of their employment may not be fully aware of the potential for exposure or cannot exercise control over their exposure






Figure 1: Graph of FCC Limits for Maximum Permissible Exposure (MPE)

Attachment C: AT&T Antenna Data Sheets and Electrical Patterns

<p>700 MHz</p> <p>Manufacturer: Commscope Model #: SBNH-1D6565C Frequency Band: 698-806 MHz Gain: 13.6 dBd Vertical Beamwidth: 8.6° Horizontal Beamwidth: 71° Polarization: Dual Linear ± 45° Size L x W x D: 96.42" x 11.85" x 7.1"</p>	
<p>850 MHz</p> <p>Manufacturer: Kathrein-Scala Model #: 800-10121 Frequency Band: 806-894 MHz Gain: 11.5 dBd Vertical Beamwidth: 14.5° Horizontal Beamwidth: 86° Polarization: Dual Linear ± 45° Size L x W x D: 54.5" x 10.3" x 5.9"</p>	
<p>1900 MHz</p> <p>Manufacturer: Kathrein-Scala Model #: 800-10121 Frequency Band: 1850-1990 MHz Gain: 14.3 dBd Vertical Beamwidth: 6.6° Horizontal Beamwidth: 85° Polarization: Dual Linear ± 45° Size L x W x D: 54.5" x 10.3" x 5.9"</p>	