



Crown Castle  
3 Corporate Park Drive, Suite 101  
Clifton Park, NY 12065

June 29, 2018

Melanie A. Bachman  
Acting Executive Director  
Connecticut Siting Council  
10 Franklin Square  
New Britain, CT 06051

**RE: Notice of Exempt Modification for Sprint Crown Site BU: 881534**  
**Sprint Site ID: CT52XC061**  
**670 Captain Neville Drive, Waterbury, New Haven County, CT 06705**  
**Latitude: 41° 32' 3.60"/ Longitude: -72° 58' 8.40"**

Dear Ms. Bachman:

Sprint currently maintains (3) antennas at the 140-foot level of the existing 150-foot monopole at 670 Captain Neville Drive, Waterbury, Connecticut 06705. The tower is owned by Global Signal Acquisitions (Crown Castle) and the property is owned by MW Cell REIT 1, LLC (Crown Castle). Sprint intends to replace (3) antennas, install (3) antennas, add (12) RRHs, and add (4) lines.

The Connecticut Siting Council's Telecommunications Database provides the Council approved SCLP's use of the telecommunications facility located at 670 Captain Neville Drive, Waterbury, Connecticut on April 12, 2000. A diligent search of available records was not fruitful for obtaining a copy of the original tower approval.

Please accept this letter as notification pursuant to Regulations of Connecticut State Agencies § 16-50j-73, for construction that constitutes an exempt modification pursuant to R.C.S.A. § 16-50j-72(b)(2). In accordance with R.S.C.A. § 16-50j-73, a copy of this letter is being sent to The Honorable Robert Congdon, First Selectman for the Town of Preston, as well as the property owner.

1. The proposed modifications will not result in an increase in the height of the existing tower.
2. The proposed modifications will not require the extension of the site boundary.
3. The proposed modification will not increase noise levels at the facility by six decibels or more, or to levels that exceed state and local criteria.
4. The operation of the replacement antennas will not increase radio frequency emissions at the facility to a level at or above the Federal Communication Commission safety standard.

Melanie A. Bachman

June 29, 2018

Page 2

5. The proposed modifications will not cause a change or alteration in the physical or environmental characteristics of the site.
6. The existing structure and its foundation can support the proposed loading.

For the foregoing reasons, Sprint respectfully submits that the proposed modifications to the above-reference telecommunications facility constitutes an exempt modification under R.C.S.A. § 16-50j-72(b)(2). Please send approval/rejection letter to Attn: Anne Marie Zsamba.

Sincerely,



Anne Marie Zsamba, Esq.

Real Estate Specialist

3 Corporate Park Drive, Suite 101, Clifton Park, NY 12065

(518) 350-3639

annemarie.zsamba.contractor@crowncastle.com

Attachments:


Tab A: Exhibit-1: Compound Plan and Elevation Depicting the Planned Changes

Tab B: Exhibit-2: Structural Modification Report

Tab C: Exhibit-3: General Power Density Table Report (RF Emissions Analysis Report)

cc: The Honorable Neil M. O'Leary, Mayor  
City of Waterbury – City Hall  
235 Grand Street  
Waterbury, CT 06702  
(203) 597-3444

Mr. James A. Sequin, AICP, City Planner  
185 South Main St., 5<sup>th</sup> Floor  
(1 Jefferson Square)  
Waterbury, CT 06706  
(203) 346-3949




**City of Waterbury**  
Public Works Department


MBL: **0450-0490-0070**

ADDRESS: **670 CAPT NEVILLE DR**

*This map is for informational purposes only and has not been prepared for, or suitable for legal, engineering, or surveying purposes. Users of this information should review or consult the primary data and information sources to verify the usability of the information. The City of Waterbury makes no warranties, express or implied, as to the use of the information obtained herein.*



Location: 670 CAPT NEVILLE DR Owner: M B REALTY LLC



### Property Information:

Map Block Lot:	0450-0490-0070	Acres:	8.88
Primary Use:	Light Industrial	Zone:	IP
Neighborhood:	85000-Industrial Park	Vol/Page:	3298
Mailing Address:	M B REALTY LLC 670 CAPTAIN NEVILLE DR WATERBURY CT 067050000		

### Property Values:

	Appraised Value	Assessed Value (70%)
Building	2298424	1608900
Land	477464	334220
OutBuilding	48610	34030
Total	2824498	1977150

### Sales Information:

Sale Date	Sale Price	Sale Type	Valid sale
1/17/1996	475000		No

### Building Information:

Bldg Style:		Living Area:	69700sq.ft
Construction:	Average	Year Built:	1990
Exterior Wall:	Concrete Precast Panel	Stories:	2
Roof Cover:		Heating:	Space Heater
Condition:	Good	Heat Fuel:	Gas
Rooms:	0	Bedrooms:	0
Full Baths:	0	Half Baths:	0

### Outbuilding Information:

Type	Area (sq.ft)	Year Built	Condition
Canopy Canopy	400sq.ft	2001	Average
Concrete Paving	340sq.ft	1996	Average

Alex Padilla  
California Secretary of State

## Business Search - Entity Detail

The California Business Search is updated daily and reflects work processed through Tuesday, June 26, 2018. Please refer to document [Processing Times](#) for the received dates of filings currently being processed. The data provided is not a complete or certified record of an entity. Not all images are available online.

201227810202 MW CELL REIT 1 LLC

<b>Registration Date:</b>	10/04/2012
<b>Jurisdiction:</b>	DELAWARE
<b>Entity Type:</b>	FOREIGN
<b>Status:</b>	ACTIVE
<b>Agent for Service of Process:</b>	<b><u>CT CORPORATION SYSTEM (C0168406)</u></b> To find the most current California registered Corporate Agent for Service of Process address and authorized employee(s) information, click the link above and then select the most current 1505 Certificate.
<b>Entity Address:</b>	1220 AUGUSTA DR STE 600 HOUSTON TX 77057
<b>Entity Mailing Address:</b>	1220 AUGUSTA DR STE 600 HOUSTON TX 77057
<b>LLC Management</b>	*

A Statement of Information is due EVERY EVEN-NUMBERED year beginning five months before and through the end of October.

Document Type	↕ File Date	↕ PDF
SI-NO CHANGE	10/06/2017	
SI-COMPLETE	11/17/2014	
REGISTRATION	10/04/2012	

\* Indicates the information is not contained in the California Secretary of State's database.


**Note:** If the agent for service of process is a corporation, the address of the agent may be requested by ordering a status report.

- For information on checking or reserving a name, refer to [Name Availability](#).
- If the image is not available online, for information on ordering a copy refer to [Information Requests](#).
- For information on ordering certificates, status reports, certified copies of documents and copies of documents not currently available in the Business Search or to request a more extensive search for records, refer to [Information Requests](#).
- For help with searching an entity name, refer to [Search Tips](#).
- For descriptions of the various fields and status types, refer to [Frequently Asked Questions](#).


[Modify Search](#)

[New Search](#)

[Back to Search Results](#)



**INFINIGY**  
FROM ZERO TO INFINIGY  
The solutions are endless  
1000 Westchester Road, Suite 100  
Westchester, PA 19380  
Tel: 610-336-0099  
www.infinigy.com



**DRAWING NOTE:**  
THIS DOCUMENT IS CONFIDENTIAL AND IS THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR RE-DISTRIBUTED WITHOUT THE EXPRESS CONSENT OF SPRINT.

REVISION	DESCRIPTION	DATE	BY	REV
1	ISSUED FOR CONSTRUCTION	06/27/18	SA	1
2	CLIENT COMMENTS	06/27/18	SA	1
3	ISSUED FOR PERMIT	06/27/18	SA	1

**SITE NAME:**  
WATERBURY TOWER

**SITE CASCADE:**  
CTS2XC061

**SITE ADDRESS:**  
670 CAPTAIN NEVILLE DRIVE  
WATERBURY, CT 06705

**SHEET DESCRIPTION:**  
TITLE SHEET & PROJECT DATA

**SHEET NUMBER:**  
T-1

**PROJECT:** 2.5 EQUIPMENT DEPLOYMENT

**SITE NAME:** WATERBURY TOWER

**SITE CASCADE:** CTS2XC061

**SITE NUMBER:** 881534

**SITE ADDRESS:** 670 CAPTAIN NEVILLE DRIVE  
WATERBURY, CT 06705

**SITE TYPE:** MONOPOLE

**MARKET:** NORTHERN CONNECTICUT

**DRAINING INDEX**

SHEET NO.	SHEET TITLE	REV.
T-1	TITLE SHEET & PROJECT DATA	0
SP-1	SPRINT SPECIFICATIONS	0
SP-2	SPRINT SPECIFICATIONS	0
SP-3	SPRINT SPECIFICATIONS	0
A-1	SEE PLAN	0
A-2	ANTENNA LOCATION & CABLE RUN	0
A-3	ANTENNA LAYOUT & MOUNTING DETAILS	0
A-4	EQUIPMENT & MOUNTING DETAILS	0
A-5	CMA DETAILS	0
A-6	PLUMBING DIAGRAM	0
A-7	ELECTRICAL & GROUNDING DETAILS	0
E-1	ELECTRICAL & GROUNDING DETAILS	0
E-2	ELECTRICAL & GROUNDING DETAILS	0

**PROJECT DESCRIPTION:**


PERMIT PROPOSED TO MOUNT AN EXISTING UNMANNED TELECOMMUNICATIONS FACILITY.

- INSTALL 2.5 EQUIPMENT MOUNT EXISTING N.E. MANS CROWN
- REMOVE (R) EXISTING LEAD-ACID BATTERY ANTENNAS FROM TOWER
- INSTALL (I) 180W-180W-180W PANEL ANTENNAS ON TOWER
- INSTALL (I) APPROXIMATE 400-400 PANE ANTENNAS ON TOWER
- INSTALL (I) 100W/100W-180W-180W RIBB ON TOWER
- INSTALL (I) 10-100W/100-25 RIBB ON TOWER
- INSTALL (I) HYBRID CABLES
- REMOVE (R) COAX

THESE PLANS HAVE BEEN DEVELOPED FOR THE IMPLEMENTATION OF AN EXISTING UNMANNED TELECOMMUNICATIONS FACILITY ORIGINALLY DESIGNED BY SPRINT AND ACCORDANCE WITH THE SCOPE OF WORK PREPARED BY SPRINT. ANY OTHER WORK NOT SHOWN ON THESE PLANS IS TO BE CONSIDERED AS EXISTING. THE DESIGNER HAS NOT PERFORMED A VISUAL SURVEY OF THE SITE AND HAS NOT CONDUCTED A VISUAL ANALYSIS. VISUAL ANALYSIS MUST BE CONDUCTED BY A LICENSED STRUCTURAL ENGINEER. STRUCTURAL ANALYSIS MUST INCLUDE BOTH STRUCTURE AND MOUNTING.

**APPLICABLE CODES:**

- INTERNATIONAL BUILDING CODE (IBC) (2015 EDITION)
- NFPA 700 - FIRE PROTECTION CODE
- 2011 NATIONAL ELECTRICAL CODE OR LATEST EDITION
- 2011 INTERNATIONAL MECHANICAL CODE OR LATEST EDITION
- 2011 INTERNATIONAL PLUMBING CODE OR LATEST EDITION
- LOCAL BUILDING CODE
- CITY/COUNTY ORDINANCES



**SITE INFORMATION:**

**TOWER OWNER:**  
CROWN ATLANTIC COMPANY LLC  
2000 CORPORATE DRIVE  
CONOWINGTOWN, PA 15317  
(717) 465-6555

**LATITUDE (NAD83):**  
41.82433° N

**LONGITUDE (NAD83):**  
-72° 56' 8.40" W

**COUNTY:**  
NEW HAVEN

**ZONING JURISDICTION:**  
CITY OF WATERBURY

**ZONING DISTRICT:**  
R

**POWER COMPANY:**  
CONNECTICUT LIGHT & POWER  
(860) 847-5000



**SPRINT CONSTRUCTION:**  
TRD

**GROUND PILE:**  
SCOTT WATROUSE  
(861) 649-6628



ALL WORK SHALL BE PERFORMED AND MATERIALS INSTALLED IN ACCORDANCE WITH THE APPLICABLE CODES AS ADOPTED BY THE LOCAL GOVERNING AUTHORITIES. NOTINGS IN THESE PLANS IS TO BE CONSIDERED TO PERMIT WORK NOT CONFORMING TO THESE CODES.





NOTICE: THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

Table with columns: REVISION, DATE BY, DESCRIPTION. Includes entries for CONSTRUCTION, COMMENTS, and SUBMITTALS.

WATERBURY TOWER

CT152XC061

670 CAPTAIN NEVILLER DRIVE WATERBURY, CT 06705

SPRINT SPECIFICATIONS

SP-1

1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE SPRINT CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

1.2 RELATED DOCUMENTS: A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.

1.3 REFERENCES: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE SPRINT CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

1.4 NATIONAL RECOGNIZED CODES AND STANDARDS: A. THE WORK SHALL COMPLY WITH APPLICABLE NATIONAL AND LOCAL CODES AND STANDARDS LISTED HEREIN, INCLUDING BUT NOT LIMITED TO THE FOLLOWING:

- 1. 01-05-CORE NEBS REQUIREMENTS: PHYSICAL PROTECTION MANUFACTURE OF TELECOMMUNICATIONS EQUIPMENT.
2. 01-1088 CORE: ELECTROMAGNETIC COMPATIBILITY AND ELECTRICAL SAFETY -SIGNALING CRITERIA FOR NETWORK TELECOMMUNICATIONS EQUIPMENT.
3. NATIONAL FIRE PROTECTION ASSOCIATION CODES AND STANDARDS (NFPA) INCLUDING NFPA 70 (NATIONAL ELECTRICAL CODE - NEC) AND NFPA 101 (LIFE SAFETY CODE).
4. AMERICAN SOCIETY FOR TESTING OF MATERIALS (ASTM)
5. INSTITUTE OF ELECTRIC AND ELECTRICAL ENGINEERS (IEEE)
6. AMERICAN CONCRETE INSTITUTE (ACI)
7. AMERICAN WIRE PRODUCERS ASSOCIATION (AWPA)
8. AMERICAN REINFORCING STEEL INSTITUTE (ARSI)
9. AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (ASHTO)
10. PORTLAND CEMENT ASSOCIATION (PCA)
11. NATIONAL CONCRETE MASONRY ASSOCIATION (NCMA)
12. BRICK INDUSTRY ASSOCIATION (BIA)
13. AMERICAN WELDING SOCIETY (AWS)
14. NATIONAL ROOFING CONTRACTORS ASSOCIATION (NRCA)
15. SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)
16. DOOR AND HARDWARE INSTITUTE (DHI)
17. OCCUPATIONAL SAFETY AND HEALTH ACT (OSHA)
18. APPLICABLE BUILDING CODES INCLUDING UNIFORM BUILDING CODE, SOUTHERN BUILDING CODE, BOCA, AND THE INTERNATIONAL BUILDING CODE.

1.5 DEFINITIONS: A. WORK: THE SUM OF TASKS AND RESPONSIBILITIES IDENTIFIED IN THE CONTRACT DOCUMENTS.

1.6 CONTRACTOR: CONSTRUCTION CONTRACTOR. CONSTRUCTION VENDOR, INDIVIDUAL, OR ENTITY WHO AFTER EXECUTION OF A CONTRACT IS BOUND TO ACCOMPLISH THE WORK.

1.7 THIRD PARTY VENDOR OR AGENT: A VENDOR OR AGENT ENGAGED SEPARATELY BY THE COMPANY, A/E/C, OR CONTRACTOR TO PROVIDE MATERIALS OR TO ACCOMPLISH SPECIFIC TASKS RELATED TO BUT NOT INCLUDED IN THE WORK.

1.8 OTHER: OTHER FURNISHED, CONTRACTOR INSTALLED EQUIPMENT.

1.9 THROUGH: THROUGH MANAGER - ALL PROJECTS RELATED EQUIPMENT TO FLOW THROUGH SPRINT REPRESENTATIVE IN CHARGE OF PROJECT...

1.10 SITE: THE CONTRACTOR SHALL BE RESPONSIBLE FOR FURNISHING ALL NECESSARY ACCESS TO ALL CONTRACT DOCUMENTS, FIELD CONDITIONS AND INSTRUMENTS PRIOR TO PROCEEDING WITH CONSTRUCTION. ANY INSTRUMENTS SHALL BE BROUGHT TO THE WORK AREA PRIOR TO CONSTRUCTION. ANY INSTRUMENTS SHALL BE BROUGHT TO THE WORK AREA PRIOR TO CONSTRUCTION. ANY INSTRUMENTS SHALL BE BROUGHT TO THE WORK AREA PRIOR TO CONSTRUCTION.

1.11 THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM ALL APPLICABLE AGENCIES AND AGENCIES PRIOR TO THE START OF CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM ALL APPLICABLE AGENCIES AND AGENCIES PRIOR TO THE START OF CONSTRUCTION.

1.12 THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM ALL APPLICABLE AGENCIES AND AGENCIES PRIOR TO THE START OF CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM ALL APPLICABLE AGENCIES AND AGENCIES PRIOR TO THE START OF CONSTRUCTION.

1.13 THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM ALL APPLICABLE AGENCIES AND AGENCIES PRIOR TO THE START OF CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM ALL APPLICABLE AGENCIES AND AGENCIES PRIOR TO THE START OF CONSTRUCTION.

1.14 THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM ALL APPLICABLE AGENCIES AND AGENCIES PRIOR TO THE START OF CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM ALL APPLICABLE AGENCIES AND AGENCIES PRIOR TO THE START OF CONSTRUCTION.

1.15 THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM ALL APPLICABLE AGENCIES AND AGENCIES PRIOR TO THE START OF CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM ALL APPLICABLE AGENCIES AND AGENCIES PRIOR TO THE START OF CONSTRUCTION.

1.16 THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM ALL APPLICABLE AGENCIES AND AGENCIES PRIOR TO THE START OF CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM ALL APPLICABLE AGENCIES AND AGENCIES PRIOR TO THE START OF CONSTRUCTION.

1.17 THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM ALL APPLICABLE AGENCIES AND AGENCIES PRIOR TO THE START OF CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM ALL APPLICABLE AGENCIES AND AGENCIES PRIOR TO THE START OF CONSTRUCTION.

1.18 THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM ALL APPLICABLE AGENCIES AND AGENCIES PRIOR TO THE START OF CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM ALL APPLICABLE AGENCIES AND AGENCIES PRIOR TO THE START OF CONSTRUCTION.

1.19 THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM ALL APPLICABLE AGENCIES AND AGENCIES PRIOR TO THE START OF CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM ALL APPLICABLE AGENCIES AND AGENCIES PRIOR TO THE START OF CONSTRUCTION.

1.20 THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM ALL APPLICABLE AGENCIES AND AGENCIES PRIOR TO THE START OF CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM ALL APPLICABLE AGENCIES AND AGENCIES PRIOR TO THE START OF CONSTRUCTION.



1.21 THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM ALL APPLICABLE AGENCIES AND AGENCIES PRIOR TO THE START OF CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM ALL APPLICABLE AGENCIES AND AGENCIES PRIOR TO THE START OF CONSTRUCTION.

1.22 THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM ALL APPLICABLE AGENCIES AND AGENCIES PRIOR TO THE START OF CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM ALL APPLICABLE AGENCIES AND AGENCIES PRIOR TO THE START OF CONSTRUCTION.

1.23 THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM ALL APPLICABLE AGENCIES AND AGENCIES PRIOR TO THE START OF CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM ALL APPLICABLE AGENCIES AND AGENCIES PRIOR TO THE START OF CONSTRUCTION.

1.24 THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM ALL APPLICABLE AGENCIES AND AGENCIES PRIOR TO THE START OF CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM ALL APPLICABLE AGENCIES AND AGENCIES PRIOR TO THE START OF CONSTRUCTION.

1.25 THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM ALL APPLICABLE AGENCIES AND AGENCIES PRIOR TO THE START OF CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM ALL APPLICABLE AGENCIES AND AGENCIES PRIOR TO THE START OF CONSTRUCTION.



DRAWING NOTICE: THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

Table with columns: REVISION, DESCRIPTION, DATE, BY, CHECKED BY. Includes rows for 'ISSUED FOR CONSTRUCTION' and 'ISSUED FOR PERMITS'.

WATERBURY TOWER

CTS2X0061

670 CAPTAIN NEVILLE DRIVE, WATERBURY, CT 06705

SPRINT SPECIFICATIONS

SP-2

5. ELECTRICIAN TO FIELD DRAWINGS IN AUTODRAW AND PDF FORMATS. ANY FIELD CHANGES TO THE DRAWINGS MUST BE APPROVED BY THE ARCHITECT AND NOTED IN THE DRAWING SETS. ALL CHANGES MUST BE DOCUMENTED AS 'CLOUDS' AS SHOWN IN THE '70-SHEET' CONDITION.

6. USER WASTES

7. REMOVED FINAL CONSTRUCTION PHOTOS

8. CONSTRUCTION AND COMMISSIONING CHECKLIST COMPLETE WITH NO DETECTED ISSUES

9. ALL PAST AND FUTURE DOCUMENT UPLOADED COMPLETED IN SIERRA (SPRINT'S DOCUMENT REPOSITORY OF RECORD)

10. COMMISSIONING: PERFORM ALL COMMISSIONING AS REQUIRED BY APPLICABLE IFC'S

11. INSPECTIONS: PERFORM ALL INSPECTION ACTIVITIES AS REQUIRED BY APPLICABLE IFC'S

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION

3.1 REQUIREMENTS FOR TESTING

A. THIRD PARTY TESTING AGENCY

1. WHEN THE USE OF A THIRD PARTY INDEPENDENT TESTING AGENCY IS REQUIRED, THE AGENCY THAT IS SELECTED MUST PERFORM SUCH WORK ON A REGULAR BASIS IN THE SAME MANNER AS THE PROJECT IS LOCATED AND HAVE A PROVEN RECORD OF SUCCESSFUL TESTING OF SIMILAR MATERIALS, INCLUDING THE SOIL, ROCK, AND GROUNDWATER CONDITIONS.

2. THE THIRD PARTY TESTING AGENCY IS TO BE FAMILIAR WITH THE APPLICABLE REQUIREMENTS FOR THE TESTS TO BE DONE, EQUIPMENT TO BE USED, AND ASSOCIATED HEALTH AND SAFETY ISSUES.

3. EXPERIENCE IN SOILS, CONCRETE, MASONRY, AGGREGATE, AND ASPHALT TESTING USING ASTM, AASHTO, AND OTHER METHODS IS NEEDED.

4. EXPERIENCE IN SOILS, CONCRETE, MASONRY, AGGREGATE, AND ASPHALT TESTING USING ASTM, AASHTO, AND OTHER METHODS IS NEEDED.

3.2 REQUIRED TESTS

A. FOUNDATIONS

1. FOUNDATION CRACK TESTS FOR THE TOWER AND ANTENNA FOUNDATIONS AS SPECIFIED IN SECTION 05100 AND CEILING CONCRETE FINISH.

2. ASPHALT BONDING COMPACTED THROUGHNESS, SURFACE SMOOTHNESS, AND AIR VOID TESTS SHALL BE PERFORMED IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS FOR ROAD AND PAVEMENT CONSTRUCTION.

3. FIELD QUALITY CONTROL TESTING AS SPECIFIED IN SECTION 05100 AND CEILING CONCRETE FINISH.

4. TESTING REQUIRED UNDER SECTION 05100 AND CEILING CONCRETE FINISH SHALL BE PERFORMED UNDER SECTION 05100 AND CEILING CONCRETE FINISH.

5. SITE RESISTANCE TO EARTH TESTING PER EXHIBIT: CELL SITE GROUNDING SYSTEM DESIGN.

6. ANTENNA AND COAX SNEEP TESTS PER EXHIBIT: ANTENNA TRANSMISSION LINE ACCEPTANCE STANDARDS.

7. GROUNDING AT ANTENNA WASTES FOR OPS AND ANTENNAS

8. ALL OTHER TESTS REQUIRED BY COMPANY OR JURISDICTION.

5. LINES AND ANTENNA INSTALL DATE (POPULATE FIELD IN SIS AND/OR FORWARD FORMED NOTIFICATION)

6. POWER INSTALL DATE (POPULATE FIELD IN SIS AND/OR FORWARD FORMED NOTIFICATION)

7. TOWER CONSTRUCTION START DATE (POPULATE FIELD IN SIS AND/OR FORWARD FORMED NOTIFICATION)

8. TOWER CONSTRUCTION COMPLETE DATE (POPULATE FIELD IN SIS AND/OR FORWARD FORMED NOTIFICATION)

9. RIS AND WIND ENGINEERING DELIVERABLES AT SITE DATE (POPULATE FIELD IN SIS AND/OR FORWARD FORMED NOTIFICATION)

10. RISK ASSESSMENT WINDOFF CHECKLIST (NIC ONLY) COMPLETE (UPLOAD FORM IN SIS)

11. CIVIL CONSTRUCTION COMPLETE DATE (POPULATE FIELD IN SIS AND/OR FORWARD FORMED NOTIFICATION)

12. SITE CONSTRUCTION PROGRESS PHOTOS UNLOADED INTO SIS.

SECTION 01 4100 - SUBMITTALS & TESTS

PART 1 - GENERAL

1. THE WORK UNDER THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONFORMANCE WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DOCUMENTS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

1.2 RELATED DOCUMENTS

A. SPECIFICATIONS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.

B. VERIFY CONTRACTOR CONSTRUCTION DETAILS FOR WHETHER SEES ARE INCLUDED IN AND MAKE A PART OF THESE SPECIFICATIONS HEREIN.

1.3 SUBMITTALS

A. THE WORK IN ALL ASPECTS SHALL COMPLY WITH THE CONSTRUCTION DOCUMENTS AND THESE SPECIFICATIONS.

B. SUBMIT THE FOLLOWING TO COMPANY REPRESENTATIVE FOR APPROVAL:

1. CONCRETE MIX-DESIGNS FOR TOWER FOUNDATIONS, ANTENNA FEEDS, AND CONCRETE FINISH.

2. CONCRETE CRACK TESTS AS SPECIFIED HEREIN.

3. SPECIAL FINISHES FOR INTERIOR SPACES, IF ANY.

4. ALL EQUIPMENT AND MATERIALS TO BE ORDERED ON THE CONSTRUCTION DOCUMENTS.

5. CHEMICAL CORROSION DESIGN

D. ALTERNATES: AT THE COMPANY'S REQUEST, ANY ALTERNATES TO THE MATERIALS OR METHODS SPECIFIED SHALL BE SUBMITTED TO SPRINT'S CONSTRUCTION DESIGN AND APPROVAL ONLY. THOSE ALTERNATES MUST BE MADE IN WRITING. NO VERBAL AGREEMENTS WILL BE CONSIDERED. SUBMITTALS FOR APPROVAL SHALL INCLUDE A STATEMENT OF COST DIFFERENCE PROPOSED FOR USE OF ALTERNATE PRODUCT.

1.4 TESTS AND INSPECTIONS

A. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CONSTRUCTION TESTS, INSPECTIONS AND PROJECT DOCUMENTATION.

1. PERFORM ANY REQUIRED SITE ENVIRONMENTAL MITIGATION.

2. REMEDIATE GROUND STATES, PROVIDE DE-CORROSION, AND ROUGH AND FINISH FLOORING, AND COMPOUND SURFACE TREATMENTS.

3. UNLARGE AND CONDUCT ALL ACTIVITIES FOR INSTALLATION OF UTILITIES INCLUDING ELECTRICAL AND TELLER BACKWALL.

4. INSTALL UNDERGROUND FACILITIES INCLUDING UNDERGROUND POWER, AND COMMUNICATIONS CONDUITS, AND UNDERGROUND GROUNDING SYSTEMS.

5. INSTALL ABOVE GROUND GROUNDING SYSTEMS.

6. PROVIDE NEW HVAC INSTALLATIONS AND MODIFICATIONS.

7. INSTALL "H-FRAMES", CHIMNEYS AND SHELTERS AS NOTICED.

8. INSTALL RAILS, ADDRESS WAYS, CURBS AND DRAINS AS NOTICED.

9. ACCOMPLISH REQUIRED MODIFICATION OF EXISTING FACILITIES.

10. PROVIDE ANTENNA SUPPORT STRUCTURES AND PLATFORMS ON EXISTING TOWERS AS REQUIRED.

11. PROVIDE SLABS AND EQUIPMENT PLATFORMS.

12. INSTALL COMPOUND FENCING, SIGHT SHIELDING, LANDSCAPING AND ACCESS BARRIERS.

13. PERFORM INSPECTION AND MATERIAL TESTING AS REQUIRED HEREIN/OTHER.

14. CONDUCT SITE RESISTANCE TO EARTH TESTING AS REQUIRED HEREIN/OTHER.

15. INSTALL FIXED GENERATOR SETS AND OTHER STANDBY POWER SOLUTIONS.

16. INSTALL TOWERS, ANTENNA SUPPORT STRUCTURES AND PLATFORMS ON EXISTING TOWERS AS REQUIRED.

17. INSTALL CELL SITE RAILS, WINDOFFS, GPS, COAXIAL WINDING, ANTENNAS, RELATED EQUIPMENT, TOWER TOP AMPIFIERS, LOW NOISE AMPLIFIERS AND RELATED EQUIPMENT.

18. PERFORM DOCUMENT AND ASSESS ALL CONSTRUCTION CRITICAL DOCUMENTS THAT MAY BE REQUIRED BY GOVERNMENT AGENCIES AND LANDLORDS.

19. PERFORM ANTENNA AND COAX SNEEP TESTING AND MAKE ANY AND ALL NECESSARY CORRECTIONS.

20. REMAIN ON SITE THROUGHOUT HAND-OFF AND INTERFERE TO ASSIST AS NEEDED UNTIL SITE IS DEEMED SUBSTANTIALLY COMPLETE AND PLACED "ON AIR."

3.2 GENERAL REQUIREMENTS FOR CIVIL CONSTRUCTION

A. CONTRACTOR SHALL KEEP THE SITE FREE FROM ACCUMULATING WASTE MATERIAL, EXCESS MATERIAL, EXCESS EQUIPMENT, EXCESS MATERIALS, EXCESS EQUIPMENT, EXCESS FACILITIES, AND SURPLUS MATERIALS.

B. EQUIPMENT ROOMS SHALL AT ALL TIMES BE MAINTAINED "ROOM CLEAN AND CLEAR OF DEBRIS."

C. CONTRACTOR SHALL TAKE ALL REASONABLE PRECAUTIONS TO DISCOVER AND LOCATE ANY HAZARDOUS CONDITION.

D. IN THE EVENT CONTRACTOR ENCOUNTERS ANY HAZARDOUS CONDITION WHICH MAY BE AFFECTED BY THE WORK, THE CONTRACTOR SHALL IMMEDIATELY STOP WORK IN THE AFFECTED AREA AND NOTIFY COMPANY IN WRITING. THE WORK IN THE AFFECTED AREA SHALL NOT BE RESUMED EXCEPT BY WRITTEN NOTIFICATION BY COMPANY.

CONTINUE FROM SP-1

D. CONTRACTOR'S ACTIVITIES SHALL BE RESTRICTED TO THE PROJECT LIMITS. SHOULD AREAS OUTSIDE THE PROJECT LIMITS BE AFFECTED BY CONTRACTOR'S ACTIVITIES, CONTRACTOR SHALL IMMEDIATELY RETURN THEM TO ORIGINAL CONDITION.

E. CONDUCT TESTING AS REQUIRED HEREIN.

3.3 DELIVERABLES

A. CONTRACTOR SHALL REVIEW, APPROVE, AND SUBMIT TO SPRINT SHOP DRAWINGS, PRODUCT DATA, SAMPLES, AND SIMILAR SUBMITTALS AS REQUIRED HEREIN/OTHER.

B. PROVIDE DOCUMENTATION INCLUDING, BUT NOT LIMITED TO THE FOLLOWING: DOCUMENTATION SHALL BE FORWARDED IN ORIGINAL FORMAT AND/OR UPLOADED INTO SIS.

1. ALL CORRESPONDENCE AND PRELIMINARY CONSTRUCTION REPORTS.



2. PROJECT PROGRESS REPORTS.

3. CIVIL CONSTRUCTION START DATE (POPULATE FIELD IN SIS AND/OR FORWARD NOTIFICATION).

4. ELECTRICAL SERVICE COMPLETION DATE (POPULATE FIELD IN SIS AND/OR FORWARD NOTIFICATION).



PLANS PREPARED FOR:



CONTRACT NUMBER: THESE DOCUMENTS ARE CONFIDENTIAL AND ARE NOT TO BE REPRODUCED OR COPIED IN ANY MANNER WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

Table with columns: REVISIONS, DESCRIPTION, DATE, BY, FOR. Includes rows for issues like 'USED FOR CONSTRUCTION' and 'ISSUED FOR PERMITS'.

PROJECT NAME: WATERBURY TOWER

SITE ADDRESS: 670 CAPTAIN NEVILLE DRIVE, WATERBURY, CT 06705

PROJECT NUMBER: SP-3

SECTION 03.400 - SUBMITTALS, A. TESTS

PART 1 - GENERAL
1.1 THE WORK THESE SUBMITTALS CONSTITUTE SHALL BE COMPLETED IN CONFORMANCE WITH THE SCHEDULED SUBMITTALS AND THE CONSTRUCTION PROGRAMS DESCRIBED IN THE WORK TO BE PERFORMED BY THE CONTRACTOR.
1.2 RELATED DOCUMENTS:
A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SUBSECTION.

PART 2 - PRODUCTS (NOT USED)
3.1 MEASUREMENTS
A. CONTRACTOR SHALL PROVIDE SCHEDULE DOWNS AND PROJECTIONS IN THE S/S SYSTEM ON A METAL BRASS.
3.4 ADDITIONAL REQUIREMENTS:
A. REPORT AS DETERMINED TO BE NECESSARY BY COMPANY.

3.5 PROJECT TESTS:
A. CONCRETE FORS AND REINFORCING: CONCRETE TESTING AND PHOTOGRAPHS OF SECTION AND PHOTOGRAPHS OF PLATFORM COMPONENTS.
B. TOWER FOUNDATIONS: PHOTOGRAPHS OF ALL TEST WELLS AND TRENCHES SHOWING ALL OPEN EXCAVATIONS AND TRENCHING PRIOR TO BACKFILLING THEREOF.

3.6 PRELIMINARY TEST AND INSPECTION REPORTS SHALL BE PROVIDED AS APPLICABLE.
A. CONCRETE MIX AND CILINDER BREAK REPORTS.
B. STRUCTURAL BACKFILL COMPACTION REPORTS.
C. SITE RESISTANCE TO EARTH TEST.
D. ANTENNA ALIGNMENT AND DOWN TILT VERIFICATION.
E. TOWER ERECTION INSPECTIONS AND MEASUREMENTS DOCUMENTING TOWER INSTALLATION PER SUPPLIER'S REQUIREMENTS AND THE APPLICABLE STANDARDS.

3.7 FOUNDATION TESTS:
A. FOUNDATION TESTS SHALL BE PROVIDED AS APPLICABLE.
B. FOUNDATION TESTS SHALL BE PROVIDED AS APPLICABLE.
C. FOUNDATION TESTS SHALL BE PROVIDED AS APPLICABLE.

3.8 FOUNDATION TESTS:
A. FOUNDATION TESTS SHALL BE PROVIDED AS APPLICABLE.
B. FOUNDATION TESTS SHALL BE PROVIDED AS APPLICABLE.
C. FOUNDATION TESTS SHALL BE PROVIDED AS APPLICABLE.

3.9 FOUNDATION TESTS:
A. FOUNDATION TESTS SHALL BE PROVIDED AS APPLICABLE.
B. FOUNDATION TESTS SHALL BE PROVIDED AS APPLICABLE.
C. FOUNDATION TESTS SHALL BE PROVIDED AS APPLICABLE.

3.10 FOUNDATION TESTS:
A. FOUNDATION TESTS SHALL BE PROVIDED AS APPLICABLE.
B. FOUNDATION TESTS SHALL BE PROVIDED AS APPLICABLE.
C. FOUNDATION TESTS SHALL BE PROVIDED AS APPLICABLE.

CONTINUE FROM SP-2

7. VERIFICATION DOCUMENTED WITH THE ANTENNA CHECKOUT REPORT, BY A/E, SITE DEVELOPMENT REP, OR RF REP.
8. FINAL INSPECTION CHECKLIST AND HANDOUT WALK (HOC), SIGNED FROM SHOWING ACCEPTANCE BY FIELD OPS IS TO BE UPLOADED INTO S/S.
9. COAX SWEEP AND FIBER TESTING DOCUMENTS SUBMITTED VIA S/S FOR RF APPROVAL.
10. AVAILABLE BARCODE PHOTOGRAPHS OF TOWER TOP AND UNACCESSIBLE SEPARATED EQUIPMENT.

11. ALL AVAILABLE JUNCTIONAL INFORMATION
12. P/F SCAN OF REIMAGES PRODUCED IN FIELD
C. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN SITE INSPECTION ACTIVITIES AND/OR AS A RESULT OF TESTING.
D. CONSTRUCTION INSPECTIONS AND CORRECTIVE MEASURES SHALL BE DOCUMENTED BY THE CONTRACTOR WITH WRITTEN REPORTS AND PHOTOGRAPHS. PHOTOGRAPHS MUST BE DATED AND OF SUFFICIENT QUALITY TO CLEARLY SHOW THE S/S ITEM AND BE LABELED WITH THE SITE CASUALTY NUMBER, SITE NAME, DESCRIPTION, AND DATE.

3.4 DELIVERABLES: TEST AND INSPECTION REPORTS AND CLOSEOUT DOCUMENTATION SHALL BE UPLOADED TO THE S/S AND/OR FORWARDED TO SPRINT FOR INCLUSION INTO THE FOLLOWING TEST AND INSPECTION REPORTS SHALL BE PROVIDED AS APPLICABLE.
A. CONCRETE MIX AND CILINDER BREAK REPORTS.
B. STRUCTURAL BACKFILL COMPACTION REPORTS.
C. SITE RESISTANCE TO EARTH TEST.
D. ANTENNA ALIGNMENT AND DOWN TILT VERIFICATION.
E. TOWER ERECTION INSPECTIONS AND MEASUREMENTS DOCUMENTING TOWER INSTALLATION PER SUPPLIER'S REQUIREMENTS AND THE APPLICABLE STANDARDS.

3.5 FOUNDATION TESTS:
A. FOUNDATION TESTS SHALL BE PROVIDED AS APPLICABLE.
B. FOUNDATION TESTS SHALL BE PROVIDED AS APPLICABLE.
C. FOUNDATION TESTS SHALL BE PROVIDED AS APPLICABLE.

3.6 FOUNDATION TESTS:
A. FOUNDATION TESTS SHALL BE PROVIDED AS APPLICABLE.
B. FOUNDATION TESTS SHALL BE PROVIDED AS APPLICABLE.
C. FOUNDATION TESTS SHALL BE PROVIDED AS APPLICABLE.

3.7 FOUNDATION TESTS:
A. FOUNDATION TESTS SHALL BE PROVIDED AS APPLICABLE.
B. FOUNDATION TESTS SHALL BE PROVIDED AS APPLICABLE.
C. FOUNDATION TESTS SHALL BE PROVIDED AS APPLICABLE.

3.8 FOUNDATION TESTS:
A. FOUNDATION TESTS SHALL BE PROVIDED AS APPLICABLE.
B. FOUNDATION TESTS SHALL BE PROVIDED AS APPLICABLE.
C. FOUNDATION TESTS SHALL BE PROVIDED AS APPLICABLE.

3.9 FOUNDATION TESTS:
A. FOUNDATION TESTS SHALL BE PROVIDED AS APPLICABLE.
B. FOUNDATION TESTS SHALL BE PROVIDED AS APPLICABLE.
C. FOUNDATION TESTS SHALL BE PROVIDED AS APPLICABLE.

24. FENCE GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELLS AND BEND RADIUS).

25. ALL ITS GROUND CONNECTIONS.

26. ALL GROUND TEST WELLS.

27. ANTENNA GROUND BAR AND EQUIPMENT GROUND BAR.

28. ADDITIONAL GROUNDING POINTS ON TOWERS ABOVE 200'.

29. HMC UNITS INCLUDING COMPENSERS ON SPLIT SYSTEMS.

30. GPS ANTENNAS.

31. CABLE TIE AND/OR WIRELESS BRIDGE.

32. DOWNROPS/CABLE CUT FROM ROOF.

33. EACH SECTION OF ANTENNAS ONE PHOTOGRAPH LOOKING AT THE SECTOR AND ONE FROM BEHIND SHOWING THE PROJECTED COVERAGE AREA.

34. MASTER BUS BAR.

35. TOWER BOND AND WEL.

36. ELECTRICAL RESTRICTION WALL.

37. CABLE ENTRY WITH SLIDE SUPPRESSION.

38. ENTRANCE TO EQUIPMENT ROOM.

39. COAX WIRE/PROTECTING-TOP AND BOTTOM OF TOWER.

40. COAX STRAPPING -TOP AND BOTTOM OF TOWER.

41. ANTENNA AND WAST GROUNDING.

42. UNDOCKING - WHERE APPLICABLE.

3.6 FINAL PROJECT ACCEPTANCE: COMPLETE ALL REQUIRED REPORTING TASKS PER SPRINT'S REQUIREMENTS AND SUBMIT TO SPRINT FOR APPROVAL AND CONSTRUCTION STANDARDS FOR WIRELESS SITES AND UPLINK INTO SPRINT.

14. ELECTRICAL TRENCHES WITH ELECTRICAL / CONDUIT BEFORE BACKFILL.

15. ELECTRICAL TRENCHES) WITH FOL-STACKED TYPE BEFORE FURTHER BACKFILL.

16. TOWER TRENCH WITH FOL-STACKED TYPE BEFORE FURTHER BACKFILL.

17. TOWER TRENCH WITH FOL-STACKED TYPE BEFORE FURTHER BACKFILL.

18. TOWER TRENCH WITH FOL-STACKED TYPE BEFORE FURTHER BACKFILL.

19. TOWER TRENCH WITH FOL-STACKED TYPE BEFORE FURTHER BACKFILL.

20. TOWER TRENCH WITH FOL-STACKED TYPE BEFORE FURTHER BACKFILL.

21. TOWER TRENCH WITH FOL-STACKED TYPE BEFORE FURTHER BACKFILL.

22. TOWER TRENCH WITH FOL-STACKED TYPE BEFORE FURTHER BACKFILL.

23. TOWER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELLS AND BEND RADIUS).

24. TOWER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELLS AND BEND RADIUS).

25. TOWER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELLS AND BEND RADIUS).

26. TOWER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELLS AND BEND RADIUS).

27. TOWER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELLS AND BEND RADIUS).

28. TOWER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELLS AND BEND RADIUS).

29. TOWER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELLS AND BEND RADIUS).

30. TOWER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELLS AND BEND RADIUS).

31. TOWER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELLS AND BEND RADIUS).

32. TOWER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELLS AND BEND RADIUS).

33. TOWER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELLS AND BEND RADIUS).

34. TOWER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELLS AND BEND RADIUS).

35. TOWER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELLS AND BEND RADIUS).

36. TOWER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELLS AND BEND RADIUS).

37. TOWER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELLS AND BEND RADIUS).

38. TOWER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELLS AND BEND RADIUS).

39. TOWER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELLS AND BEND RADIUS).

40. TOWER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELLS AND BEND RADIUS).

41. TOWER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELLS AND BEND RADIUS).

42. TOWER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELLS AND BEND RADIUS).

43. TOWER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELLS AND BEND RADIUS).

44. TOWER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELLS AND BEND RADIUS).

45. TOWER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELLS AND BEND RADIUS).

46. TOWER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELLS AND BEND RADIUS).

47. TOWER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELLS AND BEND RADIUS).

48. TOWER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELLS AND BEND RADIUS).

49. TOWER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELLS AND BEND RADIUS).

50. TOWER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELLS AND BEND RADIUS).

51. TOWER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELLS AND BEND RADIUS).

52. TOWER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELLS AND BEND RADIUS).

53. TOWER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELLS AND BEND RADIUS).

54. TOWER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELLS AND BEND RADIUS).

55. TOWER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELLS AND BEND RADIUS).


56. TOWER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELLS AND BEND RADIUS).

PLANS PREPARED FOR:



6800 Sprint Parkway  
Overland Park, Kansas 66201

PLANS PREPARED BY:  
**INFINIGY**  
FROM ZERO TO INFINIGY  
the solutions are endless  
1032 Waterville Shaker Rd., J. Albany, NY 12205  
Phone: 518-486-1100 Fax: 518-486-1193  
www.infinigy.com  
JOB NUMBER: 002-100



UNLESS NOTED OTHERWISE:  
THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, COPIED, OR DISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISION	DESCRIPTION	DATE	BY	CHKD
1	ISSUED FOR CONSTRUCTION	03/20/10	J	D
2	ISSUED FOR PERMITS	03/22/10	J	B
3	ISSUED FOR BIDDING	03/22/10	J	A



WATERBURY TOWER

CTS2XC061

670 CAPTAIN NEVILLE DRIVE  
WATERBURY, CT 06705

SHEET DESCRIPTION:  
SITE PLAN

SHEET NUMBER:  
A-1



SCALE: AS NOTED

SERIAL EQUIPMENT PLAN


SCALE: AS NOTED

OVERALL SITE PLAN

P.L. UNLESS NOTED OTHERWISE



**INFINIGY**  
FROM ZERO TO INFINITY  
The solutions are endless  
1022 Waterbury Tower, Mt. Lebanon, PA 15145  
Phone: 412-261-8700 Fax: 412-261-8705  
WWW.INFINIGY.COM



**DRAWING NOTICE:**  
THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, COPIED, OR TRANSMITTED IN ANY MANNER WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

NO.	REVISIONS:	DESCRIPTION	DATE	BY	REV
1	ISSUED FOR CONSTRUCTION		05/29/08	JS	1
2	ISSUED FOR CONSTRUCTION		05/29/08	JS	2
3	ISSUED FOR CONSTRUCTION		05/29/08	JS	3
4	ISSUED FOR CONSTRUCTION		05/29/08	JS	4





**WATERBURY TOWER**

PROJECT NO: CT52XC061

670 CAPTAIN NEVILLE DRIVE  
WATERBURY, CT 06705

TOWER ELEVATION  
& CABLE PLAN

SHEET NUMBER: A-2



NO. SCALE	NO. SCALE	NO. SCALE
1	2	3

PLANS PREPARED FOR:



**INFINIGY**  
FROM ZERO TO INFINITY  
The solutions are endless  
1033 Waterbury Tower Rd | Albany, NY 12209  
Phone: 518-882-8888 | Fax: 518-882-8889  
www.infinigy.com | Email: info@infinigy.com



REVISIONS:

NO.	DESCRIPTION	DATE	BY	REV
1	ISSUED FOR CONSTRUCTION	06/20/11	JL	0
2	CLIENT COMMENTS	07/27/11	JL	1
3	ISSUED FOR PERMIT	08/24/11	JL	2





PROJECT NAME:  
**WATERBURY TOWER**

SITE ADDRESS:  
**670 CAPTAIN NEVILLE DRIVE  
WATERBURY, CT 06705**

PROJECT NUMBER:  
**CT52XC061**

PROJECT TITLE:  
**ANTENNA LAYOUT  
& MOUNTING DETAILS**

SHEET NUMBER:  
**A-3**



**GENERAL NOTES:**

- ALL ANTENNA HEIGHTS ARE TO CENTER OF HORIZONTAL ANTENNA.
- VERIFY AZIMUTH AND CL HEIGHT WITH AS-BUILT DRAWINGS IF AVAILABLE.
- NO OBJECT IS TO BE WITHIN 45 DEGREES OF SPREAD OF ANY OTHER TOWER ANTENNA.
- 2.5G ANTENNA MUST BE AT LEAST 6' FROM TOWER AND BOUNDED ANTENNA.
- IF ANTENNAS ARE MOUNTED ON A FACE SURFACE SUCH AS A BUILDING WALL, PROTECT WALL OR SURFACE FROM CORROSION BY APPLYING AN ANTI-CORROSION TREATMENT TO THE SURFACE.
- SPRINT OF ENGINEER CALLING OUT THE EXACT LOCATION OF THESE ANTENNAS IS TO BE LOCATED, CONTACT SPRINT OF ENGINEER IF THE LOCATION IS MISSING.
- GENERAL CONTRACTOR TO FIELD VERIFY AZIMUTH AND CL HEIGHT AND MECHANICAL DOWNWELL. IF DIFFERENT THAN CALLED OUT BELOW, CALL SPRINT OF ENGINEER FOR ANSWER, BUT STILL LEAVE A MESSAGE TO BE RESPONDED TO WITHIN ONE HOUR. PLACE 2.5G ANTENNA AT SAME CL HEIGHT AS 1.9G ANTENNA AND EQUAL CORRECT CL HEIGHT AND AZIMUTH TO SPRINT OF ENGINEER. UPDATE AS-BUILT DRAWINGS WITH CORRECT CL HEIGHT AND AZIMUTH TO BE CORRECTED. 1900 MHz AND 900 MHz ANTENNA CL HEIGHT, AZIMUTH AND MECHANICAL DOWNWELL TO BE CORRECTED.
- AS-BUILT DRAWINGS TO BE PROVIDED AFTER FINAL INSTALLATION OF ANTENNAS.
- GENERAL CONTRACTOR TO PROVIDE ALL NECESSARY SPREADSHEET INFORMATION INCLUDING BIDDING, LABOR AND 2.5G TEST INCLUDE COMPLETE DOWNWELL, AZIMUTH OF EMPLOYMENT AND BEARINGS SWINGS (IF APPLICABLE), DOCUMENT ALSO TEST RESULTS IN CONK SHEET TEST SPREADSHEET.
- GENERAL CONTRACTOR MUST INSURE THAT NO OBJECT IS LOCATED IN FRONT OF ANTENNA. THIS MEANS NO OBJECT IS TO BE LOCATED 45 DEGREES UP AND 45 DEGREES DOWN FROM THE CENTER OF ANTENNA. IN ADDITION, 2.5G ANTENNA IS NOT TO BE PLACED IN FRONT OF ANY OTHER ANTENNA USING THE SAME 45 DEGREE RULE. THIS INCLUDES SPRINT AND NON-SPRINT ANTENNAS.
- GENERAL CONTRACTOR IS REQUIRED TO USE A DIGITAL ALIGNMENT TOOL TO SET AZIMUTH, ROLL AND DOWNWELL. THE ALIGNMENT TOOL IS TO BE USED TO SET THE ALIGNMENT OF THE ANTENNA. THE ALIGNMENT TOOL IS TO BE USED TO SET THE ALIGNMENT OF THE ANTENNA. THE ALIGNMENT TOOL IS TO BE USED TO SET THE ALIGNMENT OF THE ANTENNA.

**GENERAL NOTES:**

- CUT DC CONDUCTORS TO LENGTH.
- CUT FREE CABLE AND SECURE AT SIDE OF RAIL.
- DO NOT EXCEED BEND RADIUS.

**NOTE:** SPINE OF CABLES ARE COILED UP ON THE RAILS AT REAR AND ANTENNA SUCH THAT THE RAILS ARE 2.5 FEET AND 2.5 FEET FROM EACH OTHER. MAKE THE FREE JUNCTION BEND LOCATED AT EQUIPMENT PLATFORM/ANTENNA MOUNTING DETAIL.

**NOTE:** THE DRAWING IS FOR CONCEPTUAL PURPOSES ONLY. CONTRACTOR IS TO VERIFY ALL DIMENSIONS AND MOUNTING DETAILS FOR ANTENNA AND RAIL MOUNTING DETAILS.

**GENERAL NOTES:**

- CUT DC CONDUCTORS TO LENGTH.
- CUT FREE CABLE AND SECURE AT SIDE OF RAIL.
- DO NOT EXCEED BEND RADIUS.


**NOTE:** SPINE OF CABLES ARE COILED UP ON THE RAILS AT REAR AND ANTENNA SUCH THAT THE RAILS ARE 2.5 FEET AND 2.5 FEET FROM EACH OTHER. MAKE THE FREE JUNCTION BEND LOCATED AT EQUIPMENT PLATFORM/ANTENNA MOUNTING DETAIL.

**NOTE:** THE DRAWING IS FOR CONCEPTUAL PURPOSES ONLY. CONTRACTOR IS TO VERIFY ALL DIMENSIONS AND MOUNTING DETAILS FOR ANTENNA AND RAIL MOUNTING DETAILS.

PLANS PROVIDED FOR:



PLANS PROVIDED BY:  
**INFINIGY**  
 FROM ZERO TO INFINIGY  
 The solutions are endless  
 1033 Waterhill Shaker Rd., Albany, NY 12240  
 Phone: 518-751-1100  
 Fax: 518-751-1100  
 Web: info@infigy.com



OWNING NOTICE:  
 THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, COPIED, OR DISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISION	DESCRIPTION	DATE	BY	CHK
1	ISSUED FOR CONSTRUCTION	02/20/15	S	J
2	ISSUED FOR AS-BUILT	02/20/15	S	J

SITE NAME:  
**WATERBURY TOWER**

RFE NUMBER:  
**CT152XC061**


SITE ADDRESS:  
**670 CAPTAIN NEVILLE DRIVE  
 WATERBURY, CT 06705**

SHEET DESCRIPTION:  
**EQUIPMENT &  
 MOUNTING DETAILS**

SHEET NUMBER:  
**A-4**


RRR: ALCATEL LUCENT RRR 800 MHz 2-50W  
 COLOR: LIGHT GREY  
 WEIGHT: 53 LBS.

NOTES  
 COMPLY WITH MANUFACTURER'S INSTRUCTIONS TO ENSURE PROPER INSTALLATION. THE WEIGHTS LISTED WITHIN THESE PLANS ARE BASED ON THE MANUFACTURER'S PACKAGING. DO NOT OPEN RRR PACKAGES IN THE RAN.



RRR 800 MHz RRR NO SCALE 2

RRR: ALCATEL LUCENT TD-RRR1020  
 COLOR: LIGHT GREY  
 WEIGHT: 70 LBS.





NOTES  
 COMPLY WITH MANUFACTURER'S INSTRUCTIONS TO ENSURE PROPER INSTALLATION. THE WEIGHTS LISTED WITHIN THESE PLANS ARE BASED ON THE MANUFACTURER'S PACKAGING. DO NOT OPEN RRR PACKAGES IN THE RAN.


2.5. RRR'S NO SCALE 1

ANTENNA RFS APYTM14-ALU-120

RADIOME MATERIAL: ASA  
 RADIOME COLOR: LIGHT GREY  
 DIMENSIONS: 14.0x12.5x4.5" (14.0x12.5x4.5mm)  
 WEIGHT: 56.2 Lbs  
 CONNECTORS: (9) 4.5/16.5 OH FEMALE  
 (1) N - CALIBRATION CONNECTOR



RRR: ALCATEL LUCENT 1900 MHz  
 COLOR: LIGHT GREY  
 WEIGHT: 70 LBS.  
 (INCLUDING OPTIONAL SOLAR SHIELD)




RRR 1900 MHz RRR NO SCALE 4

TRIBAND ANTENNA



**INFINIGY**  
FROM ZERO TO INFINITY  
The solutions are endless  
1832 Waterbury Tower Rd J Albany, NY 12241  
Phone: 518-882-3700 Fax: 518-660-0750  
WWW.INFINIGY.COM



**DRAWING NOTICE**  
THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.


REVISION	DESCRIPTION	DATE	BY	REV
1	ISSUED FOR CONSTRUCTION	06/29/18	JG	0
2	CLIENT COMMENTS	07/27/18	JG	0
3	ISSUED FOR PERMIT	08/20/18	JG	1

**WATERBURY TOWER**

SITE ADDRESS:  
670 CAPTAIN NEVILL DRIVE  
WATERBURY, CT 06705


SHEET DESCRIPTION:  
**CIVIL DETAILS**

SHEET NUMBER:  
**A-5**



**FIBER JUNCTION BOX PENETRATION**

NO	SCALE	NO	SCALE
2		3	



**2.5\_CABLE CROSS SECTION DATA**

NO	SCALE	NO	SCALE
1		1	

**FIBER ONLY**

NO	SCALE	NO	SCALE
1		1	

**REFS. HYBRIDEX RISER CABLE SCHEDULE**

NO	SCALE	NO	SCALE
1		1	

**REFS. HYBRIDEX JUMPER CABLE SCHEDULE**


NO	SCALE	NO	SCALE
1		1	

**NOTE:** CALL TO CROWN CASTLE OR FIBER RISER CABLE AND HYBRID ON FIBER JUMPER CABLE MODEL NUMBERS IF HYBRID CABLES ARE REQUIRED BEFORE PREPARING BOM.

PLANS PREPARED FOR:



INFINIGY  
FROM ZERO TO INFINIGY  
BIG SOLUTIONS are endless  
1033 Massachusetts  
Boston, MA 02118  
Tel: 617-452-9744  
Fax: 617-452-9755  
www.infinigy.com  
M.A. PARTNER:  
100 JAMES ST. 4TH FL.  
CAMBRIDGE, MA 02142




DRAWING NOTES:  
THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REINSTATED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:	DESCRIPTION:	DATE:	BY:	REV:
1	ISSUED FOR CONSTRUCTION	05/25/08	SS	0
2	CLIENT COMMENTS	05/27/08	SS	1
3	ISSUED FOR PERMITS	01/25/09	SS	1

WATERBURY TOWER  
SITE NAME:  
SITE ADDRESS:  
CT52XC061

760 CAPTAIN NEVILLE DRIVE  
WATERBURY, CT 06705  
SHEET DESCRIPTION:  
PLUMBING DIAGRAM  
SHEET NUMBER:  
A-6



ALU 211 APXVTM14-ALU-120 & NNVV-65B-R4 wo Filters

PLUMBING DIAGRAM

NO SCALE

1

PLANS PREPARED FOR:



6500 Sprint Parkway  
Overland Park, Kansas 66201

PLANS PREPARED BY:




FROM ZERO TO INFINIGY  
The solutions are endless.  
1933 Waterhill Street, 4th Floor, Albany, NY 12203  
Phone: 518-896-8756 | Fax: 518-896-0939  
WWW.INFINIGY.COM

PLANNING:



ENGINEERING LICENSE:



DRAWING NOTES:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISION:	DESCRIPTION	DATE	BY	REV
1	ISSUED FOR CONSTRUCTION	06/27/09	S.A.	1
2	CLIENT COMMENTS	06/27/09	S.A.	2
3	ISSUED FOR WORK	06/29/09	S.A.	3

WATERBURY TOWER

CT152XC061

670 CAPTAIN NEVILLE DRIVE  
WATERBURY, CT 06705

ELECTRICAL &  
GROUNDING DETAILS

E-1

### FINAL EQUIPMENT CONFIGURATION

SECTOR	ANTENNA MANUFACTURER	ANTENNA MODEL	ROD CENTER	HEIGHT	WINDLAGE AND ANGLE
1	RFS	AP1711H-AU-100	140"	30'	0°/141°/250°/250°/0°
	COMMERCIAL	MMV-600-RN	140"	30'	0°/141°/250°/250°/0°
2	RFS	AP1711H-AU-100	140"	30'	0°/141°/250°/250°/0°
	COMMERCIAL	MMV-600-RN	140"	30'	0°/141°/250°/250°/0°
3	RFS	AP1711H-AU-100	140"	30'	0°/141°/250°/250°/0°
	COMMERCIAL	MMV-600-RN	140"	30'	0°/141°/250°/250°/0°


  

FEEDER CABLES		
MANUFACTURER	MODEL	LENGTH
RFS	R114-3000Z-T25	253'
RFS	R114-2000Z-T25	253'


NOTES:  
1. CONTRACTOR TO VERIFY PROPOSED ANTENNA INFORMATION IS THE MOST CURRENT DATA AT TIME OF CONSTRUCTION.  
2. CONTRACTOR TO OBTAIN CABLE LENGTHS PRIOR TO CONSTRUCTION.

ANTENNA/CABLE SCHEDULE

NO SCALE



NO SCALE



NO SCALE



PLANS PREPARED FOR:


**Sprint**  
1580 Sprint Parkway  
Overland Park, Kansas 66261

PLAN PREPARED BY:

**INFINIGY**  
FROM ZERO TO INFINIGY  
The solutions are endless  
1833 Watermill Street #3, Albany, NY 12243  
Phone: 518-869-4100 | Fax: 518-869-1953  
www.infigny.com | Email: info@infigny.com

M.A. PARTNER:

**CROWN  
CASTLE**



DRAWING NOTES:  
THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, COPIED, OR TRANSMITTED IN ANY MANNER WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.











REVISION	DESCRIPTION	DATE	BY	CHECKED
1	ISSUED FOR PERMITS	05/09/18	J	
2	ISSUED FOR BIDDING	05/09/18	J	
3	ISSUED FOR FIELD	05/22/18	J	

WATERBURY TOWER

SITE ADDRESS:  
670 CAPTAIN NEVILLE DRIVE  
WATERBURY, CT 06705

SHEET DESCRIPTION:  
**ELECTRICAL & GROUNDING DETAILS**

SHEET NUMBER:  
**E-2**



NO SCALE	NO SCALE	NO SCALE	NO SCALE
1	2	3	4

NOTES  
1. APPLY NO-OX TO LUG AND BAR CONTACT SURFACE. DO NOT OAT IN-LINE LUG.  
2. IF STOLEN GROUND BARS ARE ENCOUNTERED, CONTACT SPRINT CM FOR REPLACEMENT THREADED ROD KIT.

Date: April 25, 2018

Chanhdara Ratsavong  
Crown Castle  
3530 Toringdon Way, Suite 300  
Charlotte, NC 28277



Crown Castle  
2000 Corporate Drive  
Canonsburg, PA 15317  
(724) 416-2000

**Subject: Structural Analysis Report**

**Carrier Designation:**

**Clearwire Corp Co-Locate**  
**Carrier Site Number:** CT52XC061  
**Carrier Site Name:** CT52XC061

**Crown Castle Designation:**

**Crown Castle BU Number:** 881534  
**Crown Castle Site Name:** WATERBURY TOWER  
**Crown Castle JDE Job Number:** 499050  
**Crown Castle Work Order Number:** 1560796  
**Crown Castle Order Number:** 436930 Rev. 0

**Engineering Firm Designation:**

**Crown Castle Project Number:** 1560796

**Site Data:**

**670 Captain Neville Drive, Waterbury, New Haven County, CT**  
**Latitude 41° 32' 3.6", Longitude -72° 58' 8.4"**  
**150 Foot - Monopole Tower**

Dear Chanhdara Ratsavong,

Crown Castle is pleased to submit this "Structural Analysis Report" to determine the structural integrity of the above mentioned tower. This analysis has been performed in accordance with the Crown Castle Structural 'Statement of Work' and the terms of Crown Castle Purchase Order Number 1560796, in accordance with order 436930, revision 0.

The purpose of the analysis is to determine acceptability of the tower stress level. Based on our analysis we have determined the tower stress level for the structure and foundation, under the following load case, to be:

LC7: Existing + Reserved + Proposed Equipment

**Sufficient Capacity**

Note: See Table I and Table II for the proposed and existing/reserved loading, respectively.

This analysis has been performed in accordance with the 2016 Connecticut State Building Code based upon an ultimate 3-second gust wind speed of 125 mph converted to a nominal 3-second gust wind speed of 97 mph per Section 1609.3 and Appendix N as required for use in the TIA-222-G Standard per Exception #5 of Section 1609.1.1. Exposure Category C and Risk Category II were used in this analysis.

All modifications and equipment proposed in this report shall be installed in accordance with the attached drawings for the determined available structural capacity to be effective.


We at Crown Castle appreciate the opportunity of providing our continuing professional services to you and Crown Castle. If you have any questions or need further assistance on this or any other projects please give us a call.

Structural analysis prepared by: Steven Hu / SCK

Respectfully submitted by:

Terry P. Styran, P.E.  
Senior Project Engineer

tnxTower Report - version 7.0.5.1



## TABLE OF CONTENTS

### 1) INTRODUCTION

### 2) ANALYSIS CRITERIA

Table 1 - Proposed Antenna and Cable Information

Table 2 - Existing and Reserved Antenna and Cable Information

Table 3 - Design Antenna and Cable Information

### 3) ANALYSIS PROCEDURE

Table 4 - Documents Provided

3.1) Analysis Method

3.2) Assumptions

### 4) ANALYSIS RESULTS

Table 5 - Section Capacity (Summary)

Table 6 - Tower Component Stresses vs. Capacity - LC7

4.1) Recommendations

### 5) APPENDIX A

tnxTower Output

### 6) APPENDIX B

Base Level Drawing

### 7) APPENDIX C

Additional Calculations

## 1) INTRODUCTION

This tower is a 150 ft Monopole tower designed by ENGINEERED ENDEAVORS, INC. in February of 2000. The tower was originally designed for a wind speed of 85 mph per TIA/EIA-222-F.

## 2) ANALYSIS CRITERIA

The structural analysis was performed for this tower in accordance with the requirements of TIA-222-G Structural Standards for Steel Antenna Towers and Antenna Supporting Structures using a 3-second gust wind speed of 97 mph with no ice, 50 mph with 0.75 inch ice thickness and 60 mph under service loads, exposure category C.

**Table 1 - Proposed Antenna and Cable Information**

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)	Note
140.0	140.0	3	alcatel lucent	PCS 1900MHZ 4X45W-65MHZ	4	1-1/4	-
		6	alcatel lucent	RRH2X50-800			
		3	alcatel lucent	TD-RRH8X20-25			
		3	commscope	NNVV-65B-R4 w/ Mount Pipe			
		3	rfs celwave	APXVTM14-ALU-I20 w/ Mount Pipe			

**Table 2 - Existing and Reserved Antenna and Cable Information**

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)	Note
150.0	151.0	2	cci antennas	TPA-65R-LCUUUU-H8	1 2	3/8 3/4	2
		1	quintel technology	QS66512-2			
		6	cci antennas	TPX-070821			
		3	ericsson	RRUS 32			
		1	raycap	DC6-48-60-18-8F			
		3	cci antennas	DTMABP7819VG12A	1 1 2 12	conduit 3/8 3/4 1-5/8	1
		3	cci antennas	OPA-65R-LCUU-H6			
		3	ericsson	RRUS 11			
		3	ericsson	RRUS 12 W/O SOLAR SHIELD			
		3	ericsson	RRUS A2 MODULE			
		3	kathrein	800 10121			
		3	powerwave technologies	LGP21401			
		1	raycap	DC6-48-60-18-8F			
	150.0	1	tower mounts	Platform Mount [LP 1301-1]			
140.0	142.0	4	andrew	VHLP2-11	-	-	1
		1	motorola	TIMING 2000			
	140.0	3	argus technologies	LLPX310R w/ Mount Pipe			

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)	Note
		3	samsung telecommunications	WIMAX DAP HEAD	3	5/16 conduit	
		4	dragonwave	HORIZON COMPACT	3	1/2 conduit	1
		1	tower mounts	Platform Mount [LP 712-1]	1		

**Table 3 - Design Antenna and Cable Information**

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)
150.0	150.0	12	allgon	A-800-110 Panel Antennas	-	-
140.0	140.0	12	allgon	A-800-110 Panel Antennas	-	-
130.0	130.0	12	allgon	A-800-110 Panel Antennas	-	-
120.0	120.0	9	allgon	A-800-110 Panel Antennas	-	-

### 3) ANALYSIS PROCEDURE

**Table 4 - Documents Provided**

Document	Remarks	Reference	Source
4-GEOTECHNICAL REPORTS	Clarence Welti Assoc., Inc.	1405752	CCSITES
4-TOWER FOUNDATION DRAWINGS/DESIGN/SPECS	Candid Communications	1406237	CCSITES
4-TOWER MANUFACTURER DRAWINGS	Engineered Endeavros Incorporated	1405785	CCSITES

#### 3.1) Analysis Method

tnxTower (version 7.0.5.1), a commercially available analysis software package, was used to create a three-dimensional model of the tower and calculate member stresses for various loading cases. Selected output from the analysis is included in Appendix A.

#### 3.2) Assumptions

- 1) Tower and structures were built in accordance with the manufacturer's specifications.
- 2) The tower and structures have been maintained in accordance with the manufacturer's specification.
- 3) The configuration of antennas, transmission cables, mounts and other appurtenances are as specified in Tables 1 and 2 and the referenced drawings.

This analysis may be affected if any assumptions are not valid or have been made in error. Crown Castle should be notified to determine the effect on the structural integrity of the tower.

**4) ANALYSIS RESULTS**

**Table 5 - Section Capacity (Summary)**

Section No.	Elevation (ft)	Component Type	Size	Critical Element	P (K)	SF*P_allow (K)	% Capacity	Pass / Fail
L1	150 - 123.29	Pole	TP23.17x17x0.1875	1	-7.48	936.21	73.6	Pass
L2	123.29 - 87.79	Pole	TP30.86x22.005x0.3125	2	-12.71	2176.98	70.5	Pass
L3	87.79 - 43.21	Pole	TP40.4x29.2294x0.375	3	-22.33	3398.73	68.2	Pass
L4	43.21 - 0	Pole	TP49.5x38.3779x0.4375	4	-37.64	4908.34	61.8	Pass
							Summary	
						Pole (L1)	73.6	Pass
						Rating =	73.6	Pass

**Table 6 - Tower Component Stresses vs. Capacity – LC7**

Notes	Component	Elevation (ft)	% Capacity	Pass / Fail
1	Anchor Rods	0	62.2	Pass
1	Base Plate	0	78.0	Pass
1	Base Foundation Structure	0	75.9	Pass
1	Base Foundation Soil Interaction	0	45.1	Pass

<b>Structure Rating (max from all components) =</b>	<b>78%</b>
---	------------

**4.1) Recommendations**

The tower and its foundation have sufficient capacity to carry the proposed load configuration. No modifications are required at this time.

As requested, the results of the tilt and twist values for a 60 mph 3-second gust service wind speed per the TIA-222-G standard are given below:

**Critical Deflections and Radius of Curvature - Service Wind**

Elevation	Appurtenance	Gov. Load Comb.	Deflection	Tilt	Twist	Radius of Curvature
ft			in	°	°	ft
142.00	VHLP2-11	45	24.613	1.8141	0.0028	8433

**APPENDIX A**  
**TNXTOWER OUTPUT**

Section	1	2	3	4	
Length (ft)	26.71	38.92	48.00	46.79	
Number of Sides	18	18	18	18	
Thickness (in)	0.1875	0.3125	0.3750	0.4375	
Socket Length (ft)	3.42	4.42	5.58	38.3779	
Top Dia (in)	17.0000	22.0050	29.2294	49.5000	
Bot Dia (in)	23.1700	30.8600	40.4000		
Grade			A572-65		
Weight (K)	1.1	3.4	6.8	10.0	21.4


150.0 ft

123.3 ft

87.8 ft

43.2 ft

0.0 ft



## DESIGNED APPURTENANCE LOADING


TYPE	ELEVATION	TYPE	ELEVATION
800 10121	150	(2) TPX-070821	150
800 10121	150	DC6-48-60-18-8F	150
800 10121	150	Platform Mount [LP 1301-1]	150
OPA-65R-LCUU-H6	160	HORIZON COMPACT	140
OPA-65R-LCUU-H6	160	HORIZON COMPACT	140
OPA-65R-LCUU-H6	160	(2) HORIZON COMPACT	140
DTMABP7819VG12A	150	TIMING 2000	140
DTMABP7819VG12A	150	APXVTM14-ALU-I20 w/ Mount Pipe	140
DTMABP7819VG12A	150	APXVTM14-ALU-I20 w/ Mount Pipe	140
LGP21401	150	APXVTM14-ALU-I20 w/ Mount Pipe	140
LGP21401	150	NNV-65B-R4 w/ Mount Pipe	140
LGP21401	150	NNV-65B-R4 w/ Mount Pipe	140
RRUS A2 MODULE	160	NNV-65B-R4 w/ Mount Pipe	140
RRUS A2 MODULE	150	(2) RRH2X50-300	140
RRUS A2 MODULE	150	(2) RRH2X50-600	140
RRUS 11	150	(2) RRH2X50-800	140
RRUS 11	150	PCS 1900MHZ 4X45W-65MHZ	140
RRUS 11	150	PCS 1900MHZ 4X45W-65MHZ	140
RRUS 12 W/O SOLAR SHIELD	150	PCS 1900MHZ 4X45W-65MHZ	140
RRUS 12 W/O SOLAR SHIELD	150	TD-RRH8X20-25	140
RRUS 12 W/O SOLAR SHIELD	150	TD-RRH8X20-25	140
DC6-48-60-18-8F	150	TD-RRH8X20-25	140
TPA-65R-LCUUUU-H6	150	Platform Mount [LP 712-1]	140
TPA-65R-LCUUUU-H6	150	(2) 6' x 2' Mount Pipe	140
QS66512-2	150	(2) 6' x 2' Mount Pipe	140
RRUS 32	150	(2) 6' x 2' Mount Pipe	140
RRUS 32	150	VHLP2-11	140
RRUS 32	150	VHLP2-11	140
(2) TPX-070821	150	VHLP2-11	140
(2) TPX-070821	150	VHLP2-11	140

## MATERIAL STRENGTH

GRADE	Fy	Fu	GRADE	Fy	Fu
A572-65	65 ksi	80 ksi			

## TOWER DESIGN NOTES

1. Tower is located in New Haven County, Connecticut.
2. Tower designed for Exposure C to the TIA-222-G Standard.
3. Tower designed for a 97 mph basic wind in accordance with the TIA-222-G Standard.
4. Tower is also designed for a 50 mph basic wind with 0.75 in ice. Ice is considered to increase in thickness with height.
5. Deflections are based upon a 60 mph wind.
6. Tower Structure Class II.
7. Topographic Category 1 with Crest Height of 0.00 ft
8. TOWER RATING: 73.6%

ALL REACTIONS  
ARE FACTOREDCROWN  
CASTLE

The Foundation for a Wireless World

Crown Castle

2000 Corporate Drive  
Canonsburg, PA 15317

Phone: (724) 416-2000

FAX: (724) 416-4623

Job: 881534

Project:

Client: Crown Castle

Drawn by: Steven Hu

App'd:

Code: TIA-222-G

Date: 04/23/18

Scale: NT:

Path:

Dwg No. E-

R:\SA Models - Letters\Work Area\Shul1.WP\881534.WD 1560796881534.dwg



## Tower Input Data

There is a pole section.

This tower is designed using the TIA-222-G standard.

The following design criteria apply:

- 4) Tower is located in New Haven County, Connecticut.
- 5) Basic wind speed of 97 mph.
- 6) Structure Class II.
- 7) Exposure Category C.
- 8) Topographic Category 1.
- 9) Crest Height 0.00 ft.
- 10) Nominal ice thickness of 0.7500 in.
- 11) Ice thickness is considered to increase with height.
- 12) Ice density of 56 pcf.
- 13) A wind speed of 50 mph is used in combination with ice.
- 14) Temperature drop of 50 °F.
- 15) Deflections calculated using a wind speed of 60 mph.
- 16) A non-linear (P-delta) analysis was used.
- 17) Pressures are calculated at each section.
- 18) Stress ratio used in pole design is 1.
- 19) Local bending stresses due to climbing loads, feed line supports, and appurtenance mounts are not considered.

## Options

Consider Moments - Legs Consider Moments - Horizontals Consider Moments - Diagonals Use Moment Magnification ✓ Use Code Stress Ratios ✓ Use Code Safety Factors - Guys Escalate Ice Always Use Max Kz Use Special Wind Profile  Include Bolts In Member Capacity  Leg Bolts Are At Top Of Section Secondary Horizontal Braces Leg Use Diamond Inner Bracing (4 Sided) SR Members Have Cut Ends SR Members Are Concentric	Distribute Leg Loads As Uniform Assume Legs Pinned ✓ Assume Rigid Index Plate ✓ Use Clear Spans For Wind Area Use Clear Spans For KL/r Retension Guys To Initial Tension ✓ Bypass Mast Stability Checks ✓ Use Azimuth Dish Coefficients ✓ Project Wind Area of Appurt.  Autocalc Torque Arm Areas  Add IBC .6D+W Combination ✓ Sort Capacity Reports By Component Triangulate Diamond Inner Bracing Treat Feed Line Bundles As Cylinder	Use ASCE 10 X-Brace Ly Rules Calculate Redundant Bracing Forces Ignore Redundant Members in FEA SR Leg Bolts Resist Compression All Leg Panels Have Same Allowable Offset Girt At Foundation ✓ Consider Feed Line Torque Include Angle Block Shear Check Use TIA-222-G Bracing Resist. Exemption Use TIA-222-G Tension Splice Exemption  Poles ✓ Include Shear-Torsion Interaction Always Use Sub-Critical Flow Use Top Mounted Sockets
--	--	---

## Tapered Pole Section Geometry

Section	Elevation ft	Section Length ft	Splice Length ft	Number of Sides	Top Diameter in	Bottom Diameter in	Wall Thickness in	Bend Radius in	Pole Grade
L1	150.00-123.29	26.71	3.42	18	17.0000	23.1700	0.1875	0.7500	A572-65 (65 ksi)
L2	123.29-87.79	38.92	4.42	18	22.0050	30.8600	0.3125	1.2500	A572-65 (65 ksi)
L3	87.79-43.21	49.00	5.58	18	29.2294	40.4000	0.3750	1.5000	A572-65 (65 ksi)
L4	43.21-0.00	48.79		18	38.3779	49.5000	0.4375	1.7500	A572-65 (65 ksi)

### Tapered Pole Properties

Section	Tip Dia. in	Area in <sup>2</sup>	I in <sup>4</sup>	r in	C in	I/C in <sup>3</sup>	J in <sup>4</sup>	It/Q in <sup>2</sup>	w in	w/t
L1	17.2623	10.0055	357.3078	5.9684	8.6360	41.3742	715.0858	5.0037	2.6620	14.197
	23.5274	13.6775	912.7198	8.1588	11.7704	77.5439	1826.6405	6.8400	3.7479	19.989
L2	23.1346	21.5162	1279.1518	7.7008	11.1785	114.4293	2559.9868	10.7602	3.3229	10.633
	31.3361	30.2993	3572.0820	10.8444	15.6769	227.8567	7148.8642	15.1525	4.8814	15.62
L3	30.7035	34.3439	3612.5208	10.2433	14.8485	243.2917	7229.7951	17.1752	4.4844	11.958
	41.0232	47.6398	9642.0563	14.2089	20.5232	469.8125	19296.799	23.8244	6.4504	17.201
L4	40.2616	52.6850	9581.3938	13.4688	19.4960	491.4548	19175.395	26.3475	5.9845	13.679
	50.2636	68.1294	20719.127	17.4172	25.1460	823.9532	41465.516	34.0712	7.9420	18.153

Tower Elevation	Gusset Area (per face)	Gusset Thickness	Gusset Grade	Adjust. Factor A <sub>r</sub>	Adjust. Factor A <sub>r</sub>	Weight Mult.	Double Angle Stitch Bolt Spacing Diagonals	Double Angle Stitch Bolt Spacing Horizontals	Double Angle Stitch Bolt Spacing Redundants
ft	ft <sup>2</sup>	in					in	in	in
L1 150.00-123.29				1	1	1			
L2 123.29-87.79				1	1	1			
L3 87.79-43.21				1	1	1			
L4 43.21-0.00				1	1	1			

### Feed Line/Linear Appurtenances - Entered As Round Or Flat

Description	Sector	Component Type	Placement	Total Number	Number Per Row	Start/End Position	Width or Diameter	Perimeter	Weight
			ft				in	in	plf
HB114-1-0813U4-M5J(1-1/4)	C	Surface Ar (CaAa)	140.00 - 0.00	4	4	0.300 0.400	1.5400		1.20

### Feed Line/Linear Appurtenances - Entered As Area

Description	Face or Leg	Allow Shield	Component Type	Placement	Total Number	CAAA	Weight
				ft		ft <sup>2</sup> /ft	plf
CR 50 1873(1-5/8)	C	No	Inside Pole	150.00 - 0.00	12	No Ice	0.83
						1/2" Ice	0.83
						1" Ice	0.83
FB-L98B-002-75000(3/8)	C	No	Inside Pole	150.00 - 0.00	1	No Ice	0.06
						1/2" Ice	0.06
						1" Ice	0.06
WR-VG86ST-BRD(3/4)	C	No	Inside Pole	150.00 - 0.00	2	No Ice	0.58
						1/2" Ice	0.58
						1" Ice	0.58
FB-L98B-034-XXX(3/8)	C	No	Inside Pole	150.00 - 0.00	1	No Ice	0.06
						1/2" Ice	0.06
						1" Ice	0.06
WR-VG86ST-BRD(3/4)	C	No	Inside Pole	150.00 - 0.00	2	No Ice	0.58
						1/2" Ice	0.58
						1" Ice	0.58
2" Rigid Conduit	C	No	Inside Pole	150.00 - 0.00	1	No Ice	2.80
						1/2" Ice	2.80
						1" Ice	2.80

\*\*

Description	Face or Leg	Allow Shield	Component Type	Placement ft	Total Number	C <sub>A</sub> A <sub>A</sub>		Weight plf
						ft <sup>2</sup> /ft		
EC4-50(1/2)	C	No	Inside Pole	140.00 - 0.00	3	No Ice	0.00	0.16
						1/2" Ice	0.00	0.16
						1" Ice	0.00	0.16
2" Rigid Conduit	C	No	Inside Pole	140.00 - 0.00	1	No Ice	0.00	2.80
						1/2" Ice	0.00	2.80
						1" Ice	0.00	2.80

### Feed Line/Linear Appurtenances Section Areas

Tower Section n	Tower Elevation ft	Face	A <sub>R</sub> ft <sup>2</sup>	A <sub>F</sub> ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> In Face ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> Out Face ft <sup>2</sup>	Weight K
L1	150.00-123.29	A	0.000	0.000	0.000	0.000	0.00
		B	0.000	0.000	0.000	0.000	0.00
		C	0.000	0.000	10.293	0.000	0.54
L2	123.29-87.79	A	0.000	0.000	0.000	0.000	0.00
		B	0.000	0.000	0.000	0.000	0.00
		C	0.000	0.000	21.868	0.000	0.83
L3	87.79-43.21	A	0.000	0.000	0.000	0.000	0.00
		B	0.000	0.000	0.000	0.000	0.00
		C	0.000	0.000	27.461	0.000	1.04
L4	43.21-0.00	A	0.000	0.000	0.000	0.000	0.00
		B	0.000	0.000	0.000	0.000	0.00
		C	0.000	0.000	26.617	0.000	1.01

### Feed Line/Linear Appurtenances Section Areas - With Ice

Tower Section n	Tower Elevation ft	Face or Leg	Ice Thickness in	A <sub>R</sub> ft <sup>2</sup>	A <sub>F</sub> ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> In Face ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> Out Face ft <sup>2</sup>	Weight K
L1	150.00-123.29	A	1.728	0.000	0.000	0.000	0.000	0.00
		B		0.000	0.000	0.000	0.000	0.00
		C		0.000	0.000	20.086	0.000	0.77
L2	123.29-87.79	A	1.684	0.000	0.000	0.000	0.000	0.00
		B		0.000	0.000	0.000	0.000	0.00
		C		0.000	0.000	42.672	0.000	1.31
L3	87.79-43.21	A	1.605	0.000	0.000	0.000	0.000	0.00
		B		0.000	0.000	0.000	0.000	0.00
		C		0.000	0.000	53.092	0.000	1.63
L4	43.21-0.00	A	1.438	0.000	0.000	0.000	0.000	0.00
		B		0.000	0.000	0.000	0.000	0.00
		C		0.000	0.000	50.608	0.000	1.55

### Feed Line Center of Pressure

Section	Elevation ft	CP <sub>x</sub> in	CP <sub>z</sub> in	CP <sub>x</sub> Ice in	CP <sub>z</sub> Ice in
L1	150.00-123.29	-0.3522	0.3911	-0.4577	0.5084
L2	123.29-87.79	-0.5064	0.5624	-0.6504	0.7223
L3	87.79-43.21	-0.5268	0.5851	-0.7237	0.8037
L4	43.21-0.00	-0.5415	0.6014	-0.7783	0.8644

### Shielding Factor Ka

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K <sub>o</sub> No Ice	K <sub>o</sub> Ice
L1	11	HB114-1-0813U4-M5J(1-1/4)	123.29 - 140.00	1.0000	1.0000
L2	11	HB114-1-0813U4-M5J(1-1/4)	87.79 - 123.29	1.0000	1.0000
L3	11	HB114-1-0813U4-M5J(1-1/4)	43.21 - 87.79	1.0000	1.0000

### Discrete Tower Loads

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment t	Placement ft	C <sub>A</sub> A <sub>A</sub> Front	C <sub>A</sub> A <sub>A</sub> Side	Weight K
			Horz Lateral ft	Vert ft					
800 10121	A	From Leg	4.00	0.0000	150.00	No Ice	5.15	3.29	0.05
						1/2"	5.50	3.63	0.08
						Ice	5.86	3.99	0.12
						1" Ice			
800 10121	B	From Leg	4.00	0.0000	150.00	No Ice	5.15	3.29	0.05
						1/2"	5.50	3.63	0.08
						Ice	5.86	3.99	0.12
						1" Ice			
800 10121	C	From Leg	4.00	0.0000	150.00	No Ice	5.15	3.29	0.05
						1/2"	5.50	3.63	0.08
						Ice	5.86	3.99	0.12
						1" Ice			
OPA-65R-LCUU-H6	A	From Leg	4.00	0.0000	150.00	No Ice	9.66	5.52	0.07
						1/2"	10.13	5.97	0.13
						Ice	10.61	6.43	0.20
						1" Ice			
OPA-65R-LCUU-H6	B	From Leg	4.00	0.0000	150.00	No Ice	9.66	5.52	0.07
						1/2"	10.13	5.97	0.13
						Ice	10.61	6.43	0.20
						1" Ice			
OPA-65R-LCUU-H6	C	From Leg	4.00	0.0000	150.00	No Ice	9.66	5.52	0.07
						1/2"	10.13	5.97	0.13
						Ice	10.61	6.43	0.20
						1" Ice			
DTMABP7819VG12A	A	From Leg	4.00	0.0000	150.00	No Ice	0.98	0.34	0.02
						1/2"	1.10	0.42	0.03
						Ice	1.23	0.51	0.04
						1" Ice			
DTMABP7819VG12A	B	From Leg	4.00	0.0000	150.00	No Ice	0.98	0.34	0.02
						1/2"	1.10	0.42	0.03
						Ice	1.23	0.51	0.04
						1" Ice			
DTMABP7819VG12A	C	From Leg	4.00	0.0000	150.00	No Ice	0.98	0.34	0.02
						1/2"	1.10	0.42	0.03
						Ice	1.23	0.51	0.04
						1" Ice			
LGP21401	A	From Leg	4.00	0.0000	150.00	No Ice	1.10	0.21	0.01
						1/2"	1.24	0.27	0.02
						Ice	1.38	0.35	0.03
						1" Ice			
LGP21401	B	From Leg	4.00	0.0000	150.00	No Ice	1.10	0.21	0.01
						1/2"	1.24	0.27	0.02
						Ice	1.38	0.35	0.03
						1" Ice			
LGP21401	C	From Leg	4.00	0.0000	150.00	No Ice	1.10	0.21	0.01

Description	Face or Leg	Offset Type	Offsets:			Azimuth Adjustment	Placement	C <sub>A</sub> A <sub>A</sub> Front	C <sub>A</sub> A <sub>A</sub> Side	Weight
			Horz	Lateral	Vert					
			ft	ft	ft	ft	ft <sup>2</sup>	ft <sup>2</sup>	K	
			0.00				1/2"	1.24	0.27	0.02
			1.00				Ice	1.38	0.35	0.03
							1" Ice			
RRUS A2 MODULE	A	From Leg	4.00	0.0000	150.00		No Ice	1.84	1.06	0.06
			0.00				1/2"	2.01	1.20	0.08
			1.00				Ice	2.19	1.34	0.09
							1" Ice			
RRUS A2 MODULE	B	From Leg	4.00	0.0000	150.00		No Ice	1.84	1.06	0.06
			0.00				1/2"	2.01	1.20	0.08
			1.00				Ice	2.19	1.34	0.09
							1" Ice			
RRUS A2 MODULE	C	From Leg	4.00	0.0000	150.00		No Ice	1.84	1.06	0.06
			0.00				1/2"	2.01	1.20	0.08
			1.00				Ice	2.19	1.34	0.09
							1" Ice			
RRUS 11	A	From Leg	4.00	0.0000	150.00		No Ice	2.78	1.19	0.05
			0.00				1/2"	2.99	1.33	0.07
			1.00				Ice	3.21	1.49	0.09
							1" Ice			
RRUS 11	B	From Leg	4.00	0.0000	150.00		No Ice	2.78	1.19	0.05
			0.00				1/2"	2.99	1.33	0.07
			1.00				Ice	3.21	1.49	0.09
							1" Ice			
RRUS 11	C	From Leg	4.00	0.0000	150.00		No Ice	2.78	1.19	0.05
			0.00				1/2"	2.99	1.33	0.07
			1.00				Ice	3.21	1.49	0.09
							1" Ice			
RRUS 12 W/O SOLAR SHIELD	A	From Leg	4.00	0.0000	150.00		No Ice	2.47	0.86	0.06
			0.00				1/2"	2.67	0.99	0.08
			1.00				Ice	2.87	1.13	0.10
							1" Ice			
RRUS 12 W/O SOLAR SHIELD	B	From Leg	4.00	0.0000	150.00		No Ice	2.47	0.86	0.06
			0.00				1/2"	2.67	0.99	0.08
			1.00				Ice	2.87	1.13	0.10
							1" Ice			
RRUS 12 W/O SOLAR SHIELD	C	From Leg	4.00	0.0000	150.00		No Ice	2.47	0.86	0.06
			0.00				1/2"	2.67	0.99	0.08
			1.00				Ice	2.87	1.13	0.10
							1" Ice			
DC6-48-60-18-8F	C	From Leg	4.00	0.0000	150.00		No Ice	0.79	0.79	0.02
			0.00				1/2"	1.27	1.27	0.04
			1.00				Ice	1.45	1.45	0.05
							1" Ice			
TPA-65R-LCUUUU-H8	A	From Leg	4.00	0.0000	150.00		No Ice	13.30	8.82	0.08
			0.00				1/2"	13.90	9.42	0.16
			1.00				Ice	14.50	10.03	0.25
							1" Ice			
TPA-65R-LCUUUU-H8	B	From Leg	4.00	0.0000	150.00		No Ice	13.30	8.82	0.08
			0.00				1/2"	13.90	9.42	0.16
			1.00				Ice	14.50	10.03	0.25
							1" Ice			
QS66512-2	C	From Leg	4.00	0.0000	150.00		No Ice	8.13	6.80	0.11
			0.00				1/2"	8.59	7.27	0.17
			1.00				Ice	9.05	7.72	0.23
							1" Ice			
RRUS 32	A	From Leg	4.00	0.0000	150.00		No Ice	2.86	1.78	0.06
			0.00				1/2"	3.08	1.97	0.08
			1.00				Ice	3.32	2.17	0.10
							1" Ice			
RRUS 32	B	From Leg	4.00	0.0000	150.00		No Ice	2.86	1.78	0.06
			0.00				1/2"	3.08	1.97	0.08
			1.00				Ice	3.32	2.17	0.10
							1" Ice			
RRUS 32	C	From Leg	4.00	0.0000	150.00		No Ice	2.86	1.78	0.06
			0.00				1/2"	3.08	1.97	0.08

Description	Face or Leg	Offset Type	Offsets:			Azimuth Adjustment	Placement	C <sub>A</sub> A <sub>A</sub> Front	C <sub>A</sub> A <sub>A</sub> Side	Weight
			Horz	Lateral	Vert					
					1.00					
(2) TPX-070821	A	From Leg	4.00	0.0000	150.00	Ice	3.32	2.17	0.10	
			0.00			1" Ice				
			1.00			No Ice	0.47	0.10	0.01	
						1/2"	0.56	0.15	0.01	
						Ice	0.66	0.20	0.02	
(2) TPX-070821	B	From Leg	4.00	0.0000	150.00	1" Ice				
			0.00			No Ice	0.47	0.10	0.01	
			1.00			1/2"	0.56	0.15	0.01	
						Ice	0.66	0.20	0.02	
(2) TPX-070821	C	From Leg	4.00	0.0000	150.00	1" Ice				
			0.00			No Ice	0.47	0.10	0.01	
			1.00			1/2"	0.56	0.15	0.01	
						Ice	0.66	0.20	0.02	
DC6-48-60-18-8F	A	From Leg	4.00	0.0000	150.00	1" Ice				
			0.00			No Ice	0.79	0.79	0.02	
			1.00			1/2"	1.27	1.27	0.04	
						Ice	1.45	1.45	0.05	
Platform Mount [LP 1301-1]	C	None		0.0000	150.00	1" Ice				
						No Ice	51.70	51.70	2.26	
						1/2"	62.70	62.70	2.94	
						Ice	73.70	73.70	3.61	
						1" Ice				
**										
HORIZON COMPACT	A	From Leg	4.00	0.0000	140.00	No Ice	0.72	0.37	0.01	
			0.00			1/2"	0.83	0.45	0.02	
			0.00			Ice	0.94	0.54	0.03	
						1" Ice				
HORIZON COMPACT	B	From Leg	4.00	0.0000	140.00	No Ice	0.72	0.37	0.01	
			0.00			1/2"	0.83	0.45	0.02	
			0.00			Ice	0.94	0.54	0.03	
						1" Ice				
(2) HORIZON COMPACT	C	From Leg	4.00	0.0000	140.00	No Ice	0.72	0.37	0.01	
			0.00			1/2"	0.83	0.45	0.02	
			0.00			Ice	0.94	0.54	0.03	
						1" Ice				
TIMING 2000	C	From Leg	4.00	0.0000	140.00	No Ice	0.11	0.11	0.00	
			0.00			1/2"	0.15	0.15	0.00	
			2.00			Ice	0.20	0.20	0.01	
						1" Ice				
APXVTM14-ALU-I20 w/ Mount Pipe	A	From Leg	4.00	0.0000	140.00	No Ice	6.58	4.96	0.08	
			0.00			1/2"	7.03	5.75	0.13	
			0.00			Ice	7.47	6.47	0.19	
						1" Ice				
APXVTM14-ALU-I20 w/ Mount Pipe	B	From Leg	4.00	0.0000	140.00	No Ice	6.58	4.96	0.08	
			0.00			1/2"	7.03	5.75	0.13	
			0.00			Ice	7.47	6.47	0.19	
						1" Ice				
APXVTM14-ALU-I20 w/ Mount Pipe	C	From Leg	4.00	0.0000	140.00	No Ice	6.58	4.96	0.08	
			0.00			1/2"	7.03	5.75	0.13	
			0.00			Ice	7.47	6.47	0.19	
						1" Ice				
NNVV-65B-R4 w/ Mount Pipe	A	From Leg	4.00	0.0000	140.00	No Ice	12.51	7.41	0.10	
			0.00			1/2"	13.11	8.60	0.19	
			0.00			Ice	13.67	9.50	0.29	
						1" Ice				
NNVV-65B-R4 w/ Mount Pipe	B	From Leg	4.00	0.0000	140.00	No Ice	12.51	7.41	0.10	
			0.00			1/2"	13.11	8.60	0.19	
			0.00			Ice	13.67	9.50	0.29	
						1" Ice				
NNVV-65B-R4 w/ Mount Pipe	C	From Leg	4.00	0.0000	140.00	No Ice	12.51	7.41	0.10	
			0.00			1/2"	13.11	8.60	0.19	
			0.00			Ice	13.67	9.50	0.29	
						1" Ice				
(2) RRH2X50-800	A	From Leg	4.00	0.0000	140.00	No Ice	1.70	1.28	0.05	
			0.00			1/2"	1.86	1.43	0.07	

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C <sub>A</sub> A <sub>A</sub> Front	C <sub>A</sub> A <sub>A</sub> Side	Weight
			Horz	Lateral					
			0.00						
(2) RRH2X50-800	B	From Leg	4.00	0.0000	140.00	Ice 1" Ice No Ice	2.03 1.70	1.58	0.09
			0.00			1/2"	1.86	1.43	0.07
			0.00			Ice 1" Ice	2.03	1.58	0.09
(2) RRH2X50-800	C	From Leg	4.00	0.0000	140.00	No Ice 1/2"	1.70	1.28	0.05
			0.00			Ice	1.86	1.43	0.07
			0.00			1" Ice	2.03	1.58	0.09
PCS 1900MHZ 4X45W-65MHZ	A	From Leg	4.00	0.0000	140.00	No Ice 1/2"	2.32	2.24	0.06
			0.00			Ice	2.53	2.44	0.08
			0.00			1" Ice	2.74	2.65	0.11
PCS 1900MHZ 4X45W-65MHZ	B	From Leg	4.00	0.0000	140.00	No Ice 1/2"	2.32	2.24	0.06
			0.00			Ice	2.53	2.44	0.08
			0.00			1" Ice	2.74	2.65	0.11
PCS 1900MHZ 4X45W-65MHZ	C	From Leg	4.00	0.0000	140.00	No Ice 1/2"	2.32	2.24	0.06
			0.00			Ice	2.53	2.44	0.08
			0.00			1" Ice	2.74	2.65	0.11
TD-RRH8X20-25	A	From Leg	4.00	0.0000	140.00	No Ice 1/2"	4.05	1.53	0.07
			0.00			Ice	4.30	1.71	0.10
			0.00			1" Ice	4.56	1.90	0.13
TD-RRH8X20-25	B	From Leg	4.00	0.0000	140.00	No Ice 1/2"	4.05	1.53	0.07
			0.00			Ice	4.30	1.71	0.10
			0.00			1" Ice	4.56	1.90	0.13
TD-RRH8X20-25	C	From Leg	4.00	0.0000	140.00	No Ice 1/2"	4.05	1.53	0.07
			0.00			Ice	4.30	1.71	0.10
			0.00			1" Ice	4.56	1.90	0.13
Platform Mount [LP 712-1]	C	None		0.0000	140.00	No Ice 1/2"	24.53	24.53	1.34
						Ice	29.94	29.94	1.65
						1" Ice	35.35	35.35	1.96
(2) 6' x 2" Mount Pipe	A	From Leg	4.00	0.0000	140.00	No Ice 1/2"	1.43	1.43	0.02
			0.00			Ice	1.92	1.92	0.03
			0.00			1" Ice	2.29	2.29	0.05
(2) 6' x 2" Mount Pipe	B	From Leg	4.00	0.0000	140.00	No Ice 1/2"	1.43	1.43	0.02
			0.00			Ice	1.92	1.92	0.03
			0.00			1" Ice	2.29	2.29	0.05
(2) 6' x 2" Mount Pipe	C	From Leg	4.00	0.0000	140.00	No Ice 1/2"	1.43	1.43	0.02
			0.00			Ice	1.92	1.92	0.03
			0.00			1" Ice	2.29	2.29	0.05

\*\*

### Dishes

Description	Face or Leg	Dish Type	Offset Type	Offsets: Horz Lateral	Azimuth Adjustment	3 dB Beam Width	Elevation	Outside Diameter	Aperture Area	Weight
				ft	°	°	ft	ft	ft <sup>2</sup>	K

Description	Face or Leg	Dish Type	Offset Type	Offsets:		Azimuth Adjustment	3 dB Beam Width	Elevation	Outside Diameter	Aperture Area	Weight
				Horz Lateral	Vert						
				ft	ft	°	°	ft	ft	ft <sup>2</sup>	K
VHLP2-11	A	Paraboloid w/Shroud (HP)	From Leg	1.00	0.0000	140.00	2.17	No Ice	3.72	0.03	
				0.00				1/2" Ice	4.01	0.05	
				2.00				1" Ice	4.30	0.07	
VHLP2-11	A	Paraboloid w/Shroud (HP)	From Leg	1.00	0.0000	140.00	2.17	No Ice	3.72	0.03	
				0.00				1/2" Ice	4.01	0.05	
				2.00				1" Ice	4.30	0.07	
VHLP2-11	C	Paraboloid w/Shroud (HP)	From Leg	1.00	0.0000	140.00	2.17	No Ice	3.72	0.03	
				0.00				1/2" Ice	4.01	0.05	
				2.00				1" Ice	4.30	0.07	
VHLP2-11	C	Paraboloid w/Shroud (HP)	From Leg	1.00	0.0000	140.00	2.17	No Ice	3.72	0.03	
				0.00				1/2" Ice	4.01	0.05	
				2.00				1" Ice	4.30	0.07	

### Load Combinations

Comb. No.	Description
1	Dead Only
2	1.2 Dead+1.6 Wind 0 deg - No Ice
3	0.9 Dead+1.6 Wind 0 deg - No Ice
4	1.2 Dead+1.6 Wind 30 deg - No Ice
5	0.9 Dead+1.6 Wind 30 deg - No Ice
6	1.2 Dead+1.6 Wind 60 deg - No Ice
7	0.9 Dead+1.6 Wind 60 deg - No Ice
8	1.2 Dead+1.6 Wind 90 deg - No Ice
9	0.9 Dead+1.6 Wind 90 deg - No Ice
10	1.2 Dead+1.6 Wind 120 deg - No Ice
11	0.9 Dead+1.6 Wind 120 deg - No Ice
12	1.2 Dead+1.6 Wind 150 deg - No Ice
13	0.9 Dead+1.6 Wind 150 deg - No Ice
14	1.2 Dead+1.6 Wind 180 deg - No Ice
15	0.9 Dead+1.6 Wind 180 deg - No Ice
16	1.2 Dead+1.6 Wind 210 deg - No Ice
17	0.9 Dead+1.6 Wind 210 deg - No Ice
18	1.2 Dead+1.6 Wind 240 deg - No Ice
19	0.9 Dead+1.6 Wind 240 deg - No Ice
20	1.2 Dead+1.6 Wind 270 deg - No Ice
21	0.9 Dead+1.6 Wind 270 deg - No Ice
22	1.2 Dead+1.6 Wind 300 deg - No Ice
23	0.9 Dead+1.6 Wind 300 deg - No Ice
24	1.2 Dead+1.6 Wind 330 deg - No Ice
25	0.9 Dead+1.6 Wind 330 deg - No Ice
26	1.2 Dead+1.0 Ice+1.0 Temp
27	1.2 Dead+1.0 Wind 0 deg+1.0 Ice+1.0 Temp
28	1.2 Dead+1.0 Wind 30 deg+1.0 Ice+1.0 Temp
29	1.2 Dead+1.0 Wind 60 deg+1.0 Ice+1.0 Temp
30	1.2 Dead+1.0 Wind 90 deg+1.0 Ice+1.0 Temp
31	1.2 Dead+1.0 Wind 120 deg+1.0 Ice+1.0 Temp
32	1.2 Dead+1.0 Wind 150 deg+1.0 Ice+1.0 Temp
33	1.2 Dead+1.0 Wind 180 deg+1.0 Ice+1.0 Temp
34	1.2 Dead+1.0 Wind 210 deg+1.0 Ice+1.0 Temp
35	1.2 Dead+1.0 Wind 240 deg+1.0 Ice+1.0 Temp
36	1.2 Dead+1.0 Wind 270 deg+1.0 Ice+1.0 Temp
37	1.2 Dead+1.0 Wind 300 deg+1.0 Ice+1.0 Temp
38	1.2 Dead+1.0 Wind 330 deg+1.0 Ice+1.0 Temp
39	Dead+Wind 0 deg - Service
40	Dead+Wind 30 deg - Service
41	Dead+Wind 60 deg - Service
42	Dead+Wind 90 deg - Service
43	Dead+Wind 120 deg - Service
44	Dead+Wind 150 deg - Service
45	Dead+Wind 180 deg - Service
46	Dead+Wind 210 deg - Service
47	Dead+Wind 240 deg - Service



Comb. No.	Description
48	Dead+Wind 270 deg - Service
49	Dead+Wind 300 deg - Service
50	Dead+Wind 330 deg - Service

### Maximum Member Forces

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Axial K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
L1	150 - 123.29	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-21.27	1.01	0.16
			Max. Mx	8	-7.53	-306.50	1.47
			Max. My	14	-7.48	1.28	-310.49
			Max. Vy	8	16.25	-306.50	1.47
			Max. Vx	14	16.43	1.28	-310.49
			Max. Torque	9			0.76
L2	123.29 - 87.79	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-28.65	1.66	-0.46
			Max. Mx	8	-12.74	-911.31	6.45
			Max. My	14	-12.71	4.86	-921.60
			Max. Vy	8	18.84	-911.31	6.45
			Max. Vx	14	19.02	4.86	-921.60
			Max. Torque	9			0.70
L3	87.79 - 43.21	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-41.55	2.56	-1.42
			Max. Mx	8	-22.35	-1807.00	12.58
			Max. My	14	-22.33	9.40	-1825.35
			Max. Vy	8	22.41	-1807.00	12.58
			Max. Vx	14	22.58	9.40	-1825.35
			Max. Torque	9			0.70
L4	43.21 - 0	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-61.03	3.68	-2.67
			Max. Mx	8	-37.64	-2992.68	19.20
			Max. My	14	-37.64	14.43	-3019.99
			Max. Vy	8	26.02	-2992.68	19.20
			Max. Vx	14	26.18	14.43	-3019.99
			Max. Torque	9			0.69

### Maximum Reactions

Location	Condition	Gov. Load Comb.	Vertical K	Horizontal, X K	Horizontal, Z K
Pole	Max. Vert	33	61.03	0.02	-7.51
	Max. H <sub>x</sub>	21	28.25	25.89	-0.02
	Max. H <sub>z</sub>	2	37.66	-0.19	26.07
	Max. M <sub>x</sub>	2	3006.65	-0.19	26.07
	Max. M <sub>z</sub>	8	2992.68	-25.99	0.14
	Max. Torsion	9	0.69	-25.99	0.14
	Min. Vert	19	28.25	22.35	-13.20
	Min. H <sub>x</sub>	8	37.66	-25.99	0.14
	Min. H <sub>z</sub>	14	37.66	0.09	-26.15
	Min. M <sub>x</sub>	14	-3019.99	0.09	-26.15
	Min. M <sub>z</sub>	20	-2980.16	25.89	-0.02
	Min. Torsion	21	-0.66	25.89	-0.02

### Tower Mast Reaction Summary

Load Combination	Vertical	Shear <sub>x</sub>	Shear <sub>z</sub>	Overturing Moment, M <sub>x</sub>	Overturing Moment, M <sub>z</sub>	Torque
	K	K	K	kip-ft	kip-ft	kip-ft
Dead Only	31.39	0.00	0.00	0.74	1.02	-0.00
1.2 Dead+1.6 Wind 0 deg - No Ice	37.66	0.19	-26.07	-3006.65	-26.36	-0.11
0.9 Dead+1.6 Wind 0 deg - No Ice	28.25	0.19	-26.07	-2969.34	-26.33	-0.11
1.2 Dead+1.6 Wind 30 deg - No Ice	37.66	13.02	-22.63	-2610.43	-1498.97	-0.32
0.9 Dead+1.6 Wind 30 deg - No Ice	28.25	13.02	-22.63	-2578.07	-1480.60	-0.32
1.2 Dead+1.6 Wind 60 deg - No Ice	37.66	22.46	-13.16	-1520.05	-2584.75	-0.57
0.9 Dead+1.6 Wind 60 deg - No Ice	28.25	22.46	-13.16	-1501.29	-2552.83	-0.57
1.2 Dead+1.6 Wind 90 deg - No Ice	37.66	25.99	-0.14	-19.20	-2992.68	-0.69
0.9 Dead+1.6 Wind 90 deg - No Ice	28.25	25.99	-0.14	-19.18	-2955.67	-0.69
1.2 Dead+1.6 Wind 120 deg - No Ice	37.66	22.47	13.05	1507.50	-2586.02	-0.33
0.9 Dead+1.6 Wind 120 deg - No Ice	28.25	22.47	13.05	1488.43	-2554.08	-0.34
1.2 Dead+1.6 Wind 150 deg - No Ice	37.66	12.87	22.71	2625.85	-1478.18	0.11
0.9 Dead+1.6 Wind 150 deg - No Ice	28.25	12.87	22.71	2592.82	-1460.07	0.11
1.2 Dead+1.6 Wind 180 deg - No Ice	37.66	-0.09	26.15	3019.99	14.43	0.23
0.9 Dead+1.6 Wind 180 deg - No Ice	28.25	-0.09	26.15	2982.06	13.92	0.22
1.2 Dead+1.6 Wind 210 deg - No Ice	37.66	-12.97	22.66	2616.92	1493.50	0.31
0.9 Dead+1.6 Wind 210 deg - No Ice	28.25	-12.97	22.66	2584.02	1474.56	0.30
1.2 Dead+1.6 Wind 240 deg - No Ice	37.66	-22.35	13.20	1528.74	2570.09	0.44
0.9 Dead+1.6 Wind 240 deg - No Ice	28.25	-22.35	13.20	1509.40	2537.74	0.44
1.2 Dead+1.6 Wind 270 deg - No Ice	37.66	-25.89	0.02	3.11	2980.16	0.66
0.9 Dead+1.6 Wind 270 deg - No Ice	28.25	-25.89	0.02	2.84	2942.67	0.66
1.2 Dead+1.6 Wind 300 deg - No Ice	37.66	-22.43	-13.03	-1502.21	2582.70	0.35
0.9 Dead+1.6 Wind 300 deg - No Ice	28.25	-22.43	-13.03	-1483.67	2550.16	0.35
1.2 Dead+1.6 Wind 330 deg - No Ice	37.66	-12.93	-22.57	-2601.93	1488.79	-0.07
0.9 Dead+1.6 Wind 330 deg - No Ice	28.25	-12.93	-22.57	-2569.68	1469.90	-0.06
1.2 Dead+1.0 Ice+1.0 Temp	61.03	-0.00	0.00	2.67	3.68	0.00
1.2 Dead+1.0 Wind 0 deg+1.0 Ice+1.0 Temp	61.03	0.04	-7.49	-860.39	-2.97	-0.06
1.2 Dead+1.0 Wind 30 deg+1.0 Ice+1.0 Temp	61.03	3.75	-6.50	-746.57	-427.81	-0.11
1.2 Dead+1.0 Wind 60 deg+1.0 Ice+1.0 Temp	61.03	6.47	-3.77	-433.17	-740.39	-0.16
1.2 Dead+1.0 Wind 90 deg+1.0 Ice+1.0 Temp	61.03	7.48	-0.03	-2.33	-856.93	-0.17
1.2 Dead+1.0 Wind 120 deg+1.0 Ice+1.0 Temp	61.03	6.47	3.75	434.46	-740.10	-0.07
1.2 Dead+1.0 Wind 150 deg+1.0 Ice+1.0 Temp	61.03	3.71	6.52	754.56	-422.16	0.05
1.2 Dead+1.0 Wind 180 deg+1.0 Ice+1.0 Temp	61.03	-0.02	7.51	868.49	7.32	0.09
1.2 Dead+1.0 Wind 210 deg+1.0 Ice+1.0 Temp	61.03	-3.74	6.51	753.12	433.62	0.11
1.2 Dead+1.0 Wind 240 deg+1.0 Ice+1.0 Temp	61.03	-6.44	3.78	440.21	744.13	0.13
1.2 Dead+1.0 Wind 270 deg+1.0 Ice+1.0 Temp	61.03	-7.46	0.01	3.81	861.13	0.16

Load Combination	Vertical	Shear <sub>x</sub>	Shear <sub>z</sub>	Overturing Moment, M <sub>x</sub>	Overturing Moment, M <sub>z</sub>	Torque
	K	K	K	kip-ft	kip-ft	kip-ft
deg+1.0 Ice+1.0 Temp						
1.2 Dead+1.0 Wind 300	61.03	-6.46	-3.74	-428.18	746.38	0.07
deg+1.0 Ice+1.0 Temp						
1.2 Dead+1.0 Wind 330	61.03	-3.72	-6.48	-744.08	431.57	-0.03
deg+1.0 Ice+1.0 Temp						
Dead+Wind 0 deg - Service	31.39	0.04	-5.58	-639.17	-4.81	-0.02
Dead+Wind 30 deg - Service	31.39	2.79	-4.84	-554.87	-318.15	-0.07
Dead+Wind 60 deg - Service	31.39	4.81	-2.82	-322.85	-549.17	-0.13
Dead+Wind 90 deg - Service	31.39	5.56	-0.03	-3.51	-635.95	-0.15
Dead+Wind 120 deg - Service	31.39	4.81	2.79	321.32	-549.43	-0.07
Dead+Wind 150 deg - Service	31.39	2.75	4.86	559.30	-313.73	0.03
Dead+Wind 180 deg - Service	31.39	-0.02	5.60	643.17	3.87	0.05
Dead+Wind 210 deg - Service	31.39	-2.77	4.85	557.40	318.58	0.07
Dead+Wind 240 deg - Service	31.39	-4.78	2.82	325.84	547.63	0.10
Dead+Wind 270 deg - Service	31.39	-5.54	0.00	1.23	634.87	0.14
Dead+Wind 300 deg - Service	31.39	-4.80	-2.79	-319.05	550.31	0.08
Dead+Wind 330 deg - Service	31.39	-2.77	-4.83	-553.05	317.57	-0.01

### Solution Summary

Load Comb.	Sum of Applied Forces			Sum of Reactions			% Error
	PX K	PY K	PZ K	PX K	PY K	PZ K	
1	0.00	-31.39	0.00	0.00	31.39	0.00	0.000%
2	0.19	-37.66	-26.07	-0.19	37.66	26.07	0.000%
3	0.19	-28.25	-26.07	-0.19	28.25	26.07	0.000%
4	13.02	-37.66	-22.63	-13.02	37.66	22.63	0.000%
5	13.02	-28.25	-22.63	-13.02	28.25	22.63	0.000%
6	22.46	-37.66	-13.16	-22.46	37.66	13.16	0.000%
7	22.46	-28.25	-13.16	-22.46	28.25	13.16	0.000%
8	25.99	-37.66	-0.14	-25.99	37.66	0.14	0.000%
9	25.99	-28.25	-0.14	-25.99	28.25	0.14	0.000%
10	22.47	-37.66	13.05	-22.47	37.66	-13.05	0.000%
11	22.47	-28.25	13.05	-22.47	28.25	-13.05	0.000%
12	12.87	-37.66	22.71	-12.87	37.66	-22.71	0.000%
13	12.87	-28.25	22.71	-12.87	28.25	-22.71	0.000%
14	-0.09	-37.66	26.15	0.09	37.66	-26.15	0.000%
15	-0.09	-28.25	26.15	0.09	28.25	-26.15	0.000%
16	-12.97	-37.66	22.66	12.97	37.66	-22.66	0.000%
17	-12.97	-28.25	22.66	12.97	28.25	-22.66	0.000%
18	-22.35	-37.66	13.20	22.35	37.66	-13.20	0.000%
19	-22.35	-28.25	13.20	22.35	28.25	-13.20	0.000%
20	-25.89	-37.66	0.02	25.89	37.66	-0.02	0.000%
21	-25.89	-28.25	0.02	25.89	28.25	-0.02	0.000%
22	-22.43	-37.66	-13.03	22.43	37.66	13.03	0.000%
23	-22.43	-28.25	-13.03	22.43	28.25	13.03	0.000%
24	-12.93	-37.66	-22.57	12.93	37.66	22.57	0.000%
25	-12.93	-28.25	-22.57	12.93	28.25	22.57	0.000%
26	0.00	-61.03	0.00	0.00	61.03	-0.00	0.000%
27	0.04	-61.03	-7.49	-0.04	61.03	7.49	0.000%
28	3.75	-61.03	-6.50	-3.75	61.03	6.50	0.000%
29	6.47	-61.03	-3.77	-6.47	61.03	3.77	0.000%
30	7.48	-61.03	-0.03	-7.48	61.03	0.03	0.000%
31	6.47	-61.03	3.75	-6.47	61.03	-3.75	0.000%
32	3.71	-61.03	6.52	-3.71	61.03	-6.52	0.000%
33	-0.02	-61.03	7.51	0.02	61.03	-7.51	0.000%
34	-3.74	-61.03	6.51	3.74	61.03	-6.51	0.000%
35	-6.44	-61.03	3.78	6.44	61.03	-3.78	0.000%

Load Comb.	Sum of Applied Forces			Sum of Reactions			% Error
	PX K	PY K	PZ K	PX K	PY K	PZ K	
36	-7.46	-61.03	0.01	7.46	61.03	-0.01	0.000%
37	-6.46	-61.03	-3.74	6.46	61.03	3.74	0.000%
38	-3.72	-61.03	-6.48	3.72	61.03	6.48	0.000%
39	0.04	-31.39	-5.58	-0.04	31.39	5.58	0.000%
40	2.79	-31.39	-4.84	-2.79	31.39	4.84	0.000%
41	4.81	-31.39	-2.82	-4.81	31.39	2.82	0.000%
42	5.56	-31.39	-0.03	-5.56	31.39	0.03	0.000%
43	4.81	-31.39	2.79	-4.81	31.39	-2.79	0.000%
44	2.75	-31.39	4.86	-2.75	31.39	-4.86	0.000%
45	-0.02	-31.39	5.60	0.02	31.39	-5.60	0.000%
46	-2.77	-31.39	4.85	2.77	31.39	-4.85	0.000%
47	-4.78	-31.39	2.82	4.78	31.39	-2.82	0.000%
48	-5.54	-31.39	0.00	5.54	31.39	-0.00	0.000%
49	-4.80	-31.39	-2.79	4.80	31.39	2.79	0.000%
50	-2.77	-31.39	-4.83	2.77	31.39	4.83	0.000%

### Non-Linear Convergence Results

Load Combination	Converged?	Number of Cycles	Displacement Tolerance	Force Tolerance
1	Yes	4	0.00000001	0.00000001
2	Yes	5	0.00000001	0.00009773
3	Yes	5	0.00000001	0.00004116
4	Yes	6	0.00000001	0.00022024
5	Yes	6	0.00000001	0.00005941
6	Yes	6	0.00000001	0.00022476
7	Yes	6	0.00000001	0.00006088
8	Yes	5	0.00000001	0.00017729
9	Yes	5	0.00000001	0.00007501
10	Yes	6	0.00000001	0.00021938
11	Yes	6	0.00000001	0.00005917
12	Yes	6	0.00000001	0.00022099
13	Yes	6	0.00000001	0.00005982
14	Yes	5	0.00000001	0.00009182
15	Yes	5	0.00000001	0.00003694
16	Yes	6	0.00000001	0.00022367
17	Yes	6	0.00000001	0.00006057
18	Yes	6	0.00000001	0.00021954
19	Yes	6	0.00000001	0.00005905
20	Yes	5	0.00000001	0.00008401
21	Yes	4	0.00000001	0.00099689
22	Yes	6	0.00000001	0.00022286
23	Yes	6	0.00000001	0.00006050
24	Yes	6	0.00000001	0.00022134
25	Yes	6	0.00000001	0.00005998
26	Yes	4	0.00000001	0.00003693
27	Yes	5	0.00000001	0.00080156
28	Yes	6	0.00000001	0.00023545
29	Yes	6	0.00000001	0.00023982
30	Yes	5	0.00000001	0.00079890
31	Yes	6	0.00000001	0.00023601
32	Yes	6	0.00000001	0.00023568
33	Yes	5	0.00000001	0.00080969
34	Yes	6	0.00000001	0.00024457
35	Yes	6	0.00000001	0.00024091
36	Yes	5	0.00000001	0.00080319
37	Yes	6	0.00000001	0.00023957
38	Yes	6	0.00000001	0.00023978
39	Yes	4	0.00000001	0.00007705
40	Yes	5	0.00000001	0.00006842
41	Yes	5	0.00000001	0.00007226
42	Yes	4	0.00000001	0.00015143
43	Yes	5	0.00000001	0.00006804
44	Yes	5	0.00000001	0.00006916
45	Yes	4	0.00000001	0.00009521

46	Yes	5	0.00000001	0.00007200
47	Yes	5	0.00000001	0.00006876
48	Yes	4	0.00000001	0.00012682
49	Yes	5	0.00000001	0.00007100
50	Yes	5	0.00000001	0.00006980

### Maximum Tower Deflections - Service Wind

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
L1	150 - 123.29	27.749	45	1.9140	0.0032
L2	126.71 - 87.79	18.951	45	1.6069	0.0014
L3	92.21 - 43.21	9.270	45	1.0424	0.0006
L4	48.79 - 0	2.390	45	0.4627	0.0002

### Critical Deflections and Radius of Curvature - Service Wind

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
150.00	800 10121	45	27.749	1.9140	0.0035	13493
142.00	VHLP2-11	45	24.613	1.8141	0.0028	8433
140.00	HORIZON COMPACT	45	23.840	1.7886	0.0026	6746

### Maximum Tower Deflections - Design Wind

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
L1	150 - 123.29	130.126	14	8.9887	0.0142
L2	126.71 - 87.79	88.946	14	7.5498	0.0063
L3	92.21 - 43.21	43.540	14	4.8994	0.0025
L4	48.79 - 0	11.227	14	2.1742	0.0008

### Critical Deflections and Radius of Curvature - Design Wind

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
150.00	800 10121	14	130.126	8.9887	0.0170	3000
142.00	VHLP2-11	14	115.452	8.5211	0.0131	1874
140.00	HORIZON COMPACT	14	111.834	8.4016	0.0121	1498

### Compression Checks

### Pole Design Data

Section No.	Elevation ft	Size	L ft	L <sub>v</sub> ft	Kl/r	A in <sup>2</sup>	P <sub>v</sub> K	φP <sub>n</sub> K	Ratio P <sub>v</sub> φP <sub>n</sub>
L1	150 - 123.29 (1)	TP23.17x17x0.1875	26.71	0.00	0.0	13.207 3	-7.48	936.21	0.008
L2	123.29 - 87.79 (2)	TP30.86x22.005x0.3125	38.92	0.00	0.0	29.301 8	-12.71	2176.98	0.006
L3	87.79 - 43.21 (3)	TP40.4x29.2294x0.375	49.00	0.00	0.0	46.125 7	-22.33	3398.73	0.007
L4	43.21 - 0 (4)	TP49.5x38.3779x0.4375	48.79	0.00	0.0	68.129 4	-37.64	4908.34	0.008

### Pole Bending Design Data

Section No.	Elevation ft	Size	M <sub>ux</sub> kip-ft	φM <sub>nx</sub> kip-ft	Ratio M <sub>ux</sub> φM <sub>nx</sub>	M <sub>uy</sub> kip-ft	φM <sub>ny</sub> kip-ft	Ratio M <sub>uy</sub> φM <sub>ny</sub>
L1	150 - 123.29 (1)	TP23.17x17x0.1875	310.49	426.99	0.727	0.00	426.99	0.000
L2	123.29 - 87.79 (2)	TP30.86x22.005x0.3125	921.62	1318.91	0.699	0.00	1318.91	0.000
L3	87.79 - 43.21 (3)	TP40.4x29.2294x0.375	1825.38	2703.53	0.675	0.00	2703.53	0.000
L4	43.21 - 0 (4)	TP49.5x38.3779x0.4375	3020.03	4946.76	0.611	0.00	4946.76	0.000

### Pole Shear Design Data

Section No.	Elevation ft	Size	Actual V <sub>v</sub> K	φV <sub>n</sub> K	Ratio V <sub>v</sub> φV <sub>n</sub>	Actual T <sub>v</sub> kip-ft	φT <sub>n</sub> kip-ft	Ratio T <sub>v</sub> φT <sub>n</sub>
L1	150 - 123.29 (1)	TP23.17x17x0.1875	16.43	468.11	0.035	0.23	855.02	0.000
L2	123.29 - 87.79 (2)	TP30.86x22.005x0.3125	19.02	1088.49	0.017	0.23	2641.04	0.000
L3	87.79 - 43.21 (3)	TP40.4x29.2294x0.375	22.58	1699.36	0.013	0.23	5413.67	0.000
L4	43.21 - 0 (4)	TP49.5x38.3779x0.4375	26.18	2454.17	0.011	0.23	9905.58	0.000

### Pole Interaction Design Data


Section No.	Elevation ft	Ratio P <sub>v</sub> φP <sub>n</sub>	Ratio M <sub>ux</sub> φM <sub>nx</sub>	Ratio M <sub>uy</sub> φM <sub>ny</sub>	Ratio V <sub>v</sub> φV <sub>n</sub>	Ratio T <sub>v</sub> φT <sub>n</sub>	Comb. Stress Ratio	Allow. Stress Ratio	Criteria
L1	150 - 123.29 (1)	0.008	0.727	0.000	0.035	0.000	0.736	1.000	4.8.2
L2	123.29 - 87.79 (2)	0.006	0.699	0.000	0.017	0.000	0.705	1.000	4.8.2
L3	87.79 - 43.21 (3)	0.007	0.675	0.000	0.013	0.000	0.682	1.000	4.8.2
L4	43.21 - 0 (4)	0.008	0.611	0.000	0.011	0.000	0.618	1.000	4.8.2

### Section Capacity Table

Section No.	Elevation ft	Component Type	Size	Critical Element	P K	$\phi P_{allow}$ K	% Capacity	Pass Fail
L1	150 - 123.29	Pole	TP23.17x17x0.1875	1	-7.48	936.21	73.6	Pass
L2	123.29 - 87.79	Pole	TP30.86x22.005x0.3125	2	-12.71	2176.98	70.5	Pass
L3	87.79 - 43.21	Pole	TP40.4x29.2294x0.375	3	-22.33	3398.73	68.2	Pass
L4	43.21 - 0	Pole	TP49.5x38.3779x0.4375	4	-37.64	4908.34	61.8	Pass
Summary								
Pole (L1)							73.6	Pass
<b>RATING =</b>							<b>73.6</b>	<b>Pass</b>

**APPENDIX B**  
**BASE LEVEL DRAWING**





(PROPOSED)  
(4) 1-1/4" TO 140 FT LEVEL  
(INSTALLED-IN CONDUIT--TO BE REMOVED)  
(3) 1/4" TO 140 FT LEVEL  
(3) 5/16" TO 140 FT LEVEL  
(INSTALLED)  
(3) 1/2" TO 140 FT LEVEL

(RESERVED)  
(1) 3/8" TO 150 FT LEVEL  
(2) 3/4" TO 150 FT LEVEL  
(INSTALLED-IN CONDUIT)  
(1) 3/8" TO 150 FT LEVEL  
(2) 3/4" TO 150 FT LEVEL  
(INSTALLED)  
(12) 1-5/8" TO 150 FT LEVEL

BUSINESS UNIT: 881534 TOWER ID: C\_BASELEVEL

**APPENDIX C**  
**ADDITIONAL CALCULATIONS**

## Stiffened or Unstiffened, UngROUTed, Circular Base Plate - Any Rod Material

**TIA Rev G**

Assumption: Clear space between bottom of leveling nut and top of concrete not exceeding (1)\*(Rod Diameter)

**Site Data**

BU#: 881534
Site Name: WATERBURY TOWER
App #: 436930 Rev. 0
Pole Manufacturer: <i>Other</i>

**Anchor Rod Data**

Qty:	16	
Diam:	2.25	in
Rod Material:	A815-J	
Strength (Fu):	100	ksi
Yield (Fy):	75	ksi
Bolt Circle:	58	in

**Plate Data**

Diam:	64	in
Thick:	2	in
Grade:	60	ksi
Single-Rod B-eff:	9.82	in

**Stiffener Data (Welding at both sides)**

Config:	0	*
Weld Type:		
Groove Depth:		<-- Disregard
Groove Angle:		<-- Disregard
Fillet H. Weld:		in
Fillet V. Weld:		in
Width:		in
Height:		in
Thick:		in
Notch:		in
Grade:		ksi
Weld str.:		ksi

**Pole Data**

Diam:	49.5	in
Thick:	0.4375	in
Grade:	65	ksi
# of Sides:	18	"0" IF Round
Fu	80	ksi
Reinf. Fillet Weld	0	"0" if None

Reactions		
Mu:	3020	ft-kips
Axial, Pu:	38	kips
Shear, Vu:	26	kips
Eta Factor, η	0.5	TIA G (Fig. 4-4)

If No stiffeners, Criteria: **AISC LRFD** <-Only Applicable to Unstiffened Cases

**Anchor Rod Results**

Max Rod (Cu+ Vu/r):	161.8 Kips
Allowable Axial, $\Phi * Fu * Anet$ :	260.0 Kips
Anchor Rod Stress Ratio:	62.2% Pass

Rigid
AISC LRFD
$\phi * Tn$

**Base Plate Results**

Base Plate Stress:	42.1 ksi	Flexural Check
Allowable Plate Stress:	54.0 ksi	
Base Plate Stress Ratio:	78.0% Pass	

Rigid	
AISC LRFD	
$\phi * Fy$	
Y.L. Length:	30.23


n/a

**Stiffener Results**

Horizontal Weld :	n/a
Vertical Weld:	n/a
Plate Flex+Shear, $fb/Fb+(fv/Fv)^2$ :	n/a
Plate Tension+Shear, $ft/Ft+(fv/Fv)^2$ :	n/a
Plate Comp. (AISC Bracket):	n/a

**Pole Results**

Pole Punching Shear Check:	n/a
----------------------------	-----



\* 0 = none, 1 = every bolt, 2 = every 2 bolts, 3 = 2 per bolt

\*\* Note: for complete joint penetration groove welds the groove depth must be exactly 1/2 the stiffener thickness for calculation purposes

# Anchor Rods - Shear, Axial and Bending Interaction Check



## Description:

TIA-222-G Section 4.9.9

Applies to detail type (d) anchors when the clear distance from the top of the concrete to the bottom leveling nut exceeds 1.0 times the diameter of the anchor rod.

## Assumptions:

1. The tower is a monopole.
2. The anchor rods are evenly spaced in a circular pattern.

## 1. INPUTS

### Tower Reactions (from tnxTower)

Base Moment:  $M := 3020 \text{kip}\cdot\text{ft}$

Axial Force:  $P := 37 \text{kip}$

Base Shear:  $V_{\text{WW}} := 26 \text{kip}$

### Anchor Rods Properties

Number of Anchors:  $N_{\text{AW}} := 16$

Bolt Circle Diameter:  $BC := 58 \text{in}$

Yield Strength of Rods:  $F_y := 75 \text{ksi}$

Ultimate Strength of Rods:  $F_{\text{ub}} := 100 \text{ksi}$

Distance from Bottom Nut to Concrete:  $l_{\text{ar}} := 3 \cdot \text{in}$

Rod Diameter:  $2\text{-}1/4\text{"}$

Per photos, are the bolts threaded at the top of the concrete?:

Not Threaded  
 Threaded

[Section 4.9.6.3(a) applies]

[Section 4.9.6.3(b) applies]

Gross Area:  $A_b := \frac{1}{4} \cdot \pi \cdot d^2 = 3.98 \cdot \text{in}^2$

Net Area:  $A_n = 3.25 \cdot \text{in}^2$

Moment of Inertia of Group:  $I := \frac{1}{8} \cdot N \cdot A_n \cdot BC^2 = 21866 \cdot \text{in}^4$

## 2. CALCULATIONS

### Shear Force per Anchor

$$V_u := \frac{V}{N} = 1.63 \cdot \text{kip}$$

### Maximum Axial Force per Anchor

$$P_u := \frac{M \cdot (0.5 \cdot BC)}{I} \cdot A_n + \frac{P}{N} = 158.52 \cdot \text{kip}$$

### Bending Moment (due to Shear)

[TIA-222-G Section 4.9.9]

$$M_u := 0.65 \cdot l_{ar} \cdot V_u = 3.17 \cdot \text{kip} \cdot \text{in}$$

### Shear Strength

[TIA-222-G Section 4.9.6.3]

Thread Factor:  $t_h = 0.45$

Strength:  $\phi R_{nv} := 0.75 \cdot (t_h) \cdot F_{ub} \cdot A_b = 134.19 \cdot \text{kip}$

### Tensile Strength

[TIA-222-G Section 4.9.6.1]

$$\phi R_{nt} := 0.8 \cdot F_{ub} \cdot A_n = 260 \cdot \text{kip}$$

### Flexural Strength

[TIA-222-G Section 4.7.1]

Per Section 4.9.9, calculate "Z" based on the tensile root diameter of the rod:

Tensile Root Diameter:  
(back-calculated)  $d_{tr} := \sqrt{\frac{4 \cdot A_n}{\pi}} = 2.03 \cdot \text{in}$

Plastic Modulus:  $Z := \frac{1}{6} \cdot d_{tr}^3 = 1.4 \cdot \text{in}^3$

Strength:  $\phi R_{nm} := 0.9 \cdot F_y \cdot Z = 94.7 \cdot \text{kip} \cdot \text{in}$

### Capacity Check

[TIA-222-G Section 4.9.9]

Interaction Equation: 
$$\text{Capacity} := \left( \frac{V_u}{\phi R_{nv}} \right)^2 + \left[ \left( \frac{P_u}{\phi R_{nt}} \right) + \left( \frac{M_u}{\phi R_{nm}} \right) \right]^2$$

$$\text{Capacity} = 1.149$$

Check = "Okay"

## SUMMARY

### 1. Inputs

#### 1.1 Tower Reactions

Base Moment:  $M = 3020 \cdot \text{kip} \cdot \text{ft}$

Axial Shear:  $P = 37 \cdot \text{kip}$

Base Shear:  $V = 26 \cdot \text{kip}$

#### 1.2 Anchor Rods Properties

Number of Anchors:  $N = 16$

Rod Diameter:  $d = 2.25 \cdot \text{in}$

Yield Strength:  $F_y = 75 \cdot \text{ksi}$

### 2. Calculations

Shear Force per Anchor:  $V_u = 1.63 \cdot \text{kip}$

Axial Force per Anchor:  $P_u = 158.52 \cdot \text{kip}$

Bending Moment per Anchor:  $M_u = 3.17 \cdot \text{kip} \cdot \text{in}$

Shear Strength:  $\phi R_{nv} = 134.19 \cdot \text{kip}$

Tensile Strength:  $\phi R_{nt} = 260 \cdot \text{kip}$

Flexural Strength:  $\phi R_{nm} = 94.7 \cdot \text{kip} \cdot \text{in}$

Capacity: **Capacity = 41.33%**

Capacity Check: Check = "Okay"

# Pier and Pad Foundation



BU #: 881534  
 Site Name: WATERBURY TOWER  
 App. Number: 436930 Rev. 0

TIA-222 Revision: G  
 Tower Type: Monopole

Block Foundation?:

Superstructure Analysis Reactions		
Compression, $P_{comp}$ :	38	kips
Base Shear, $V_u_{comp}$ :	26	kips
Moment, $M_u$ :	3020	ft-kips
Tower Height, H:	150	ft
BP Dist. Above Fdn, $bp_{dist}$ :	5.25	in

Foundation Analysis Checks				
	Capacity	Demand	Rating	Check
Lateral (Sliding) (kips)	513.00	26.00	5.1%	Pass
Bearing Pressure (ksf)	6.00	2.29	38.2%	Pass
Overtuning (kip*ft)	7235.50	3265.38	45.1%	Pass
Pier Flexure (Comp.) (kip*ft)	4133.00	3137.00	75.9%	Pass
Pier Compression (kip)	20168.46	72.22	0.4%	Pass
Pad Flexure (kip*ft)	6548.99	1095.92	16.7%	Pass
Pad Shear - 1-way (kips)	1224.67	137.66	11.2%	Pass
Pad Shear - 2-way (ksi)	0.16	0.02	9.8%	Pass

Soil Rating: 45.1%  
 Structural Rating: 75.9%

Pier Properties		
Pier Shape:	Square	
Pier Diameter, $d_{pier}$ :	6.5	ft
Ext. Above Grade, E:	1.00	ft
Pier Rebar Size, $S_c$ :	8	
Pier Rebar Quantity, $m_c$ :	36	
Pier Tie/Spiral Size, $S_t$ :	5	
Pier Tie/Spiral Quantity, $m_t$ :	4	
Pier Reinforcement Type:	Tie	
Pier Clear Cover, $cc_{pier}$ :	4	in

Pad Properties		
Depth, D:	8.0	ft
Pad Width, W:	25.0	ft
Pad Thickness, T:	4.5	ft
Pad Rebar Size, $S_p$ :	7	
Pad Rebar Quantity, $m_p$ :	50	
Pad Clear Cover, $cc_{pad}$ :	3	in

Material Properties		
Rebar Grade, $F_y$ :	60000	psi
Concrete Compressive Strength, $F'_c$ :	3000	psi
Dry Concrete Density, $\delta_c$ :	150	pcf

Soil Properties		
Total Soil Unit Weight, $\gamma$ :	125	pcf
Ultimate Gross Bearing, $Q_{ult}$ :	8.000	ksf
Cohesion, $C_u$ :	0.000	ksf
Friction Angle, $\phi$ :	34	degrees
SPT Blow Count, $N_{blows}$ :	63	
Base Friction, $\mu$ :	0.6	
Neglected Depth, N:	3.50	ft
Foundation Bearing on Rock?	No	
Groundwater Depth, gw:	N/A	ft

<--Toggle between Gross and Net

# USGS Design Maps Summary Report

## User-Specified Input


**Report Title** 881534  
Wed April 25, 2018 13:15:53 UTC

**Building Code Reference Document** 2012/2015 International Building Code  
(which utilizes USGS hazard data available in 2008)

**Site Coordinates** 41.53433°N, 72.969°W

**Site Soil Classification** Site Class D - "Stiff Soil"


**Risk Category** I/II/III



## USGS-Provided Output

$S_s = 0.187 \text{ g}$	$S_{MS} = 0.300 \text{ g}$	$S_{DS} = 0.200 \text{ g}$
$S_1 = 0.064 \text{ g}$	$S_{M1} = 0.153 \text{ g}$	$S_{D1} = 0.102 \text{ g}$

For information on how the  $S_s$  and  $S_1$  values above have been calculated from probabilistic (risk-targeted) and deterministic ground motions in the direction of maximum horizontal response, please return to the application and select the "2009 NEHRP" building code reference document.





# CCISeismic - Design Category

Per 2012/2015 IBC

Site BU: 881534  
 Work Order: 1560796  
 Application: 436930 Rev. 0



	Degrees	Minutes	Seconds		
Site Latitude =	41	32	3.59	41.5343	degrees
Site Longitude =	-72	58	8.39	-72.9690	degrees
Ground Supported Structure =	Yes				
Structure Class =	II				(Table 2-1)
Site Class =	D - Stiff Soil				(Table 2-11)
Spectral response acceleration short periods, $S_s$ =	0.189				<a href="#">USGS Seismic Tool</a>
Spectral response acceleration 1 s period, $S_1$ =	0.064				
Importance Factor, $I$ =	1.0				(Table 2-3)
Acceleration-based site coefficient, $F_a$ =	1.6				(Table 2-12)
Velocity-based site coefficient, $F_v$ =	2.4				(Table 2-13)
Design spectral response acceleration short period, $S_{DS}$ =	0.202				(2.7.6)
Design spectral response acceleration 1 s period, $S_{D1}$ =	0.102				(2.7.6)
Seismic Design Category - Short Period Response =	B				ASCE 7-05 Table 11.6-1
Seismic Design Category - 1s Period Response =	B				ASCE 7-05 Table 11.6-2
Worst Case Seismic Design Category =	B				ASCE 7-05 Tables 11.6-1 and 6-2



# EBI Consulting

environmental | engineering | due diligence

---

## RADIO FREQUENCY EMISSIONS ANALYSIS REPORT EVALUATION OF HUMAN EXPOSURE POTENTIAL TO NON-IONIZING EMISSIONS

SPRINT Existing Facility

Site ID: CT52XC061

Waterbury Tower  
670 Captain Neville Drive  
Waterbury, CT 06705

June 21, 2018

**EBI Project Number: 6218004577**

Site Compliance Summary	
Compliance Status:	<b>COMPLIANT</b>
Site total MPE% of FCC general population allowable limit:	<b>4.70 %</b>



# EBI Consulting

environmental | engineering | due diligence

June 21, 2018

SPRINT

Attn: RF Engineering Manager  
1 International Boulevard, Suite 800  
Mahwah, NJ 07495

## Emissions Analysis for Site: **CT52XC061 – Waterbury Tower**

EBI Consulting was directed to analyze the proposed SPRINT facility located at **670 Captain Neville Drive, Waterbury, CT**, for the purpose of determining whether the emissions from the Proposed SPRINT Antenna Installation located on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter ( $\mu\text{W}/\text{cm}^2$ ). The number of  $\mu\text{W}/\text{cm}^2$  calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits, therefore it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) – (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general population may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general population would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

General population exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter ( $\mu\text{W}/\text{cm}^2$ ). The general population exposure limits for the 850 MHz Band is approximately  $567 \mu\text{W}/\text{cm}^2$ . The general population exposure limit for the 1900 MHz (PCS) and 2500 MHz (BRS) bands is  $1000 \mu\text{W}/\text{cm}^2$ . Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.



# EBI Consulting

environmental | engineering | due diligence

Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure. Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

## CALCULATIONS

Calculations were done for the proposed SPRINT Wireless antenna facility located at **670 Captain Neville Drive, Waterbury, CT**, using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. Since SPRINT is proposing highly focused directional panel antennas, which project most of the emitted energy out toward the horizon, all calculations were performed assuming a lobe representing the maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB for directional panel antennas and 20 dB for parabolic microwave dishes, was focused at the base of the tower. For this report the sample point is the top of a 6-foot person standing at the base of the tower.

For all calculations, all equipment was calculated using the following assumptions:

- 1) 1 CDMA channels (850 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 20 Watts per Channel.
- 2) 2 LTE channels (850 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 50 Watts per Channel.
- 3) 5 CDMA channels (1900 MHz (PCS)) were considered for each sector of the proposed installation. These Channels have a transmit power of 16 Watts per Channel.
- 4) 2 LTE channels (1900 MHz (PCS)) were considered for each sector of the proposed installation. These Channels have a transmit power of 40 Watts per Channel.
- 5) 8 LTE channels (2500 MHz (BRS)) were considered for each sector of the proposed installation. These Channels have a transmit power of 20 Watts per Channel.



# EBI Consulting

environmental | engineering | due diligence

---

- 6) 1 microwave backhaul (11 GHz) channel was considered for Sectors A & B and 2 microwave backhaul (11 GHz) channels were considered for Sector C. These channels have a transmit power of 1 Watt per Channel.
  
- 7) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 - Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.
  
- 8) For the following calculations, the sample point was the top of a 6-foot person standing at the base of the tower. The maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB for directional panel antennas and 20 dB for parabolic microwave dishes, was used in this direction. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
  
- 9) The antennas used in this modeling are the **Commscope NNVV-65B-R4** and the **RFS APXVTM14-ALU-I20** for transmission in the 850 MHz, 1900 MHz (PCS) and 2500 MHz (BRS) frequency bands and the **Commscope VHLP2-11** microwave dish for the proposed 11 GHz microwave backhaul. This is based on feedback from the carrier with regards to anticipated antenna selection. Maximum gain values for all antennas are listed in the Inventory and Power Data table below. The maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB for directional panel antennas and 20 dB for parabolic microwave dishes, was used for all calculations. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
  
- 10) The antenna mounting height centerlines of the proposed panel antennas and microwave dishes are **140 feet** above ground level (AGL) for **Sector A**, **140 feet** above ground level (AGL) for **Sector B** and **140 feet** above ground level (AGL) for Sector C.
  
- 11) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.

All calculations were done with respect to uncontrolled / general population threshold limits.



# EBI Consulting

environmental | engineering | due diligence

## SPRINT Site Inventory and Power Data by Antenna

Sector	A	Sector	B	Sector	C
Antenna #	1	Antenna #	1	Antenna #	1
Make / Model	Commscope NNVV-65B-R4	Make / Model	Commscope NNVV-65B-R4	Make / Model	Commscope NNVV-65B-R4
Gain	12.75 / 15.05 dBd	Gain	12.75 / 15.05 dBd	Gain	12.75 / 15.05 dBd
Height (AGL)	140 feet	Height (AGL)	140 feet	Height (AGL)	140 feet
Frequency Bands	850 MHz / 1900 MHz (PCS)	Frequency Bands	850 MHz / 1900 MHz (PCS)	Frequency Bands	850 MHz / 1900 MHz (PCS)
Channel Count	10	Channel Count	10	Channel Count	10
Total TX Power(W)	280 Watts	Total TX Power(W)	280 Watts	Total TX Power(W)	280 Watts
ERP (W)	7,378.61	ERP (W)	7,378.61	ERP (W)	7,378.61
Antenna A1 MPE%	1.83 %	Antenna B1 MPE%	1.83 %	Antenna C1 MPE%	1.83 %
Antenna #	2	Antenna #	2	Antenna #	2
Make / Model	RFS APXVTM14-ALU- I20	Make / Model	RFS APXVTM14-ALU- I20	Make / Model	RFS APXVTM14-ALU- I20
Gain	15.9 dBd	Gain	15.9 dBd	Gain	15.9 dBd
Height (AGL)	140 feet	Height (AGL)	140 feet	Height (AGL)	140 feet
Frequency Bands	2500 MHz (BRS)	Frequency Bands	2500 MHz (BRS)	Frequency Bands	2500 MHz (BRS)
Channel Count	8	Channel Count	8	Channel Count	8
Total TX Power(W)	160 Watts	Total TX Power(W)	160 Watts	Total TX Power(W)	160 Watts
ERP (W)	6,224.72	ERP (W)	6,224.72	ERP (W)	6,224.72
Antenna A2 MPE%	1.25 %	Antenna B2 MPE%	1.25 %	Antenna C2 MPE%	1.25 %

## Microwave Backhaul Data

Antenna Type:	Gain (dBd)	Height (feet AGL):	Frequency Bands	Channel Count	Total TX Power(W)	ERP (W)	MPE %	Sector
Commscope VHLP2-11	32.35 dBd	140	11 GHz	1	1	1,717.91	0.03	A
Commscope VHLP2-11	32.35 dBd	140	11 GHz	1	1	1,717.91	0.03	B
Commscope VHLP2-11	32.35 dBd	140	11 GHz	1	1	1,717.91	0.03	C
Commscope VHLP2-11	32.35 dBd	140	11 GHz	1	1	1,717.91	0.03	C

Site Composite MPE%	
Carrier	MPE%
SPRINT - Sector C	3.14 %
AT&T	1.27 %
Clearwire	0.06 %
Clearwire MW	0.13 %
XM Satellite Radio	0.10 %
<b>Site Total MPE %:</b>	<b>4.70 %</b>

SPRINT Sector A Total	3.10 %
SPRINT Sector B Total	3.10 %
SPRINT Sector C Total	3.14 %
<b>Site Total:</b>	<b>4.70 %</b>



# EBI Consulting

environmental | engineering | due diligence

SPRINT Frequency Band/ Technology Max Power Values (Sector C)	# Channels	Watts ERP (Per Channel)	Height (feet)	Total Power Density ( $\mu\text{W}/\text{cm}^2$ )	Frequency (MHz)	Allowable MPE ( $\mu\text{W}/\text{cm}^2$ )	Calculated % MPE
Sprint 850 MHz CDMA	1	376.73	140	0.75	850 MHz	567	0.14%
Sprint 850 MHz LTE	2	941.82	140	3.77	850 MHz	567	0.67%
Sprint 1900 MHz (PCS) CDMA	5	511.82	140	5.12	1900 MHz (PCS)	1000	0.51%
Sprint 1900 MHz (PCS) LTE	2	1,279.56	140	5.12	1900 MHz (PCS)	1000	0.51%
Sprint 2500 MHz (BRS) LTE	8	778.09	140	12.46	2500 MHz (BRS)	1000	1.25%
Sprint 11 GHz Microwave	1	1,717.91	140	0.34	11 GHz	1000	0.03%
Sprint 11 GHz Microwave	1	1,717.91	140	0.34	11 GHz	1000	0.03%
						<b>Total:</b>	<b>3.14%</b>



# EBI Consulting

environmental | engineering | due diligence

## Summary

All calculations performed for this analysis yielded results that were **within** the allowable limits for general population exposure to RF Emissions.

The anticipated maximum composite contributions from the SPRINT facility as well as the site composite emissions value with regards to compliance with FCC's allowable limits for general population exposure to RF Emissions are shown here:

SPRINT Sector	Power Density Value (%)
Sector A:	3.10 %
Sector B:	3.10 %
Sector C:	3.14 %
SPRINT Maximum Total (per sector):	3.14 %
Site Total:	4.70 %
Site Compliance Status:	<b>COMPLIANT</b>

The anticipated composite MPE value for this site assuming all carriers present is **4.70 %** of the allowable FCC established general population limit sampled at the ground level. This is based upon values listed in the Connecticut Siting Council database for existing carrier emissions.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.



## Zsamba, Anne Marie (Contractor)

**From:** TrackingUpdates@fedex.com  
**Sent:** Friday, June 29, 2018 10:24 AM  
**To:** Zsamba, Anne Marie (Contractor)  
**Subject:** FedEx Shipment 772588620432 Delivered

# Your package has been delivered

Tracking # 772588620432

Ship date:  
**Thu, 6/28/2018**

Rebecca Alescio  
Crown Castle  
Clifton Park, NY 12065  
US

Delivery date:  
**Fri, 6/29/2018 10:14 am**

Mr. James A. Sequin, City  
Planner  
Crown Castle  
185 South Main Street, 5th  
Floor  
WATERBURY, CT 06706  
US



## Shipment Facts

Our records indicate that the following package has been delivered.

**Tracking number:** 772588620432

**Status:** Delivered: 06/29/2018 10:14 AM  
Signed for By: D.FARRELL

**Reference:** 1734.7680

**Signed for by:** D.FARRELL

**Delivery location:** WATERBURY, CT

**Delivered to:** Receptionist/Front Desk

**Service type:** FedEx Priority Overnight

**Packaging type:** FedEx Pak

**Number of pieces:** 1

**Weight:** 2.00 lb.

**Special handling/Services:** Adult Signature Required  
Deliver Weekday

**Standard transit:** 6/29/2018 by 10:30 am

Please do not respond to this message. This email was sent from an unattended mailbox. This report was generated at approximately 9:24 AM CDT on 06/29/2018.

**Zsamba, Anne Marie (Contractor)**

**From:** TrackingUpdates@fedex.com  
**Sent:** Friday, June 29, 2018 10:49 AM  
**To:** Zsamba, Anne Marie (Contractor)  
**Subject:** FedEx Shipment 772588601047 Delivered

## Your package has been delivered

Tracking # 772588601047

Ship date:  
**Thu, 6/28/2018**  
Rebecca Alescio  
Crown Castle  
Clifton Park, NY 12065  
US



Delivery date:  
**Fri, 6/29/2018 10:47 am**  
The Honorable Neil. M.  
O'Leary  
Crown Castle  
235 Grand Street, 2nd Floor  
City Of Waterbury - City Hall  
WATERBURY, CT 06702  
US



### Shipment Facts

Our records indicate that the following package has been delivered.

**Tracking number:** [772588601047](#)  
**Status:** Delivered: 06/29/2018 10:47 AM Signed for By: M.ACETO  
**Reference:** 1734.7680  
**Signed for by:** M.ACETO  
**Delivery location:** WATERBURY, CT  
**Delivered to:** Receptionist/Front Desk  
**Service type:** FedEx Priority Overnight  
**Packaging type:** FedEx Pak  
**Number of pieces:** 1  
**Weight:** 2.00 lb.  
**Special handling/Services:** Adult Signature Required  
Deliver Weekday  
**Standard transit:** 6/29/2018 by 10:30 am

Please do not respond to this message. This email was sent from an unattended mailbox. This report was generated at approximately 9:49 AM CDT on 06/29/2018.

All weights are estimated.