



Crown Castle  
3530 Toringdon Way  
Suite 300  
Charlotte, NC 28277

Tel: 704-405-6600

[www.crowncastle.com](http://www.crowncastle.com)

April 7, 2014

Melanie A. Bachman  
Connecticut Siting Council  
10 Franklin Square  
New Britain, CT 06051

**RE: Sprint PCS-Exempt Modification - Crown Site BU: 876328**  
**Sprint PCS Site ID: CT03XC075**  
**Located at: 27-31 South Main Street, West Hartford, CT 06110**

Dear Ms. Bachman:

This letter and exhibits are submitted on behalf of Sprint PCS (Sprint). Sprint is making modifications to certain existing sites in its Connecticut system in order to implement their 2.5GHz LTE technology. Please accept this letter and exhibits as notification, pursuant to § 16-50j-73 of the Regulations of Connecticut State Agencies (“R.C.S.A.”), of construction that constitutes an exempt modification pursuant to R.C.S.A. § 16-50j-72(b)(2). In compliance with R.C.S.A. § 16-50j-73, a copy of this letter is being sent to The Honorable Scott Slifka, Mayor for the Town of West Hartford.

Sprint plans to modify the existing wireless communications facility owned by Crown Castle and located at **27-31 South Main Street, West Hartford, CT 06110**. Attached are a compound plan and elevation depicting the planned changes (Exhibit-1), and documentation of the structural sufficiency of the structure to accommodate the revised antenna configuration (Exhibit-2). Also included is a power density table report reflecting the modification to Sprint’s operations at the site (Exhibit-3).

The changes to the facility do not constitute a modification as defined in Connecticut General Statutes (“C.G.S.”) § 16-50i(d) because the general physical characteristics of the facility will not be significantly changed. Rather, the planned changes to the facility fall squarely within those activities explicitly provided for in the R.C.S.A. § 16-50j-72(b)(2).

1. The proposed modifications will not result in an increase in the height of the existing tower. Sprint’s additional antennas will be located at the same elevation on the existing tower.
2. There will be no proposed modifications to the ground and no extension of boundaries.
3. The proposed modifications will not increase noise levels at the facility by six decibels or more.

Melanie A. Bachman

April 7, 2014

Page 2

4. A Structural Modification Report confirming that the tower and foundation can support Sprint's proposed modifications is included as Exhibit-2.
5. The operation of the additional antennas will not increase radio frequency (RF) emissions at the facility to a level at or above the Federal Communications Commission (FCC) adopted safety standard. A cumulative General Power Density table report for Sprint's modified facility is included as Exhibit-3.

For the foregoing reasons, Sprint respectfully submits the proposed modifications to the above-reference telecommunications facility constitutes an exempt modification under R.C.S.A. § 16-50j-72(b)(2). Please send approval/rejection letter to Attn: Donna Neal.

Sincerely,



Jeff Barbadora  
Real Estate Specialist

Enclosures

Tab 1: Exhibit-1: Compound plan and elevation depicting the planned changes

Tab 2: Exhibit-2: Structural Modification Report

Tab 3: Exhibit-3: General Power Density Table Report (RF Emissions Analysis Report)

cc: The Honorable Scott Slifka, Mayor  
Town of West Hartford  
50 South Main Street  
West Hartford, CT 06107



THESE OUTLINE SPECIFICATIONS IN CONJUNCTION WITH THE SPRINT STANDARD CONSTRUCTION SPECIFICATIONS, INCLUDING CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

**SECTION 01 100 - SCOPE OF WORK**

**PART 1 - GENERAL**

- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE SPRINT CONSTRUCTION STANDARDS FOR WIRELESS SITES, CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
  - A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
  - B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.
- 1.3 PRECEDENCE: SHOULD CONFLICTS OCCUR BETWEEN THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES INCLUDING THE STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES AND THE CONSTRUCTION DRAWINGS, INFORMATION ON THE CONSTRUCTION DRAWINGS SHALL TAKE PRECEDENCE. NOTIFY SPRINT CONSTRUCTION MANAGER IF THIS OCCURS.
- 1.4 NATIONALLY RECOGNIZED CODES AND STANDARDS:
  - A. THE WORK SHALL COMPLY WITH APPLICABLE NATIONAL AND LOCAL CODES AND STANDARDS, LATEST EDITION, AND PORTIONS THEREOF, INCLUDED BUT NOT LIMITED TO THE FOLLOWING:
    - 1. GR-63-CORE NEBS REQUIREMENTS: PHYSICAL PROTECTION
    - 5. GR-78-CORE GENERIC REQUIREMENTS FOR THE PHYSICAL DESIGN AND MANUFACTURE OF TELECOMMUNICATIONS EQUIPMENT.
    - 3. GR-1089 CORE, ELECTROMAGNETIC COMPATIBILITY AND ELECTRICAL SAFETY -GENERIC CRITERIA FOR NETWORK TELECOMMUNICATIONS EQUIPMENT.
    - 4. NATIONAL FIRE PROTECTION ASSOCIATION CODES AND STANDARDS (NFPA) INCLUDING NFPA 70 (NATIONAL ELECTRICAL CODE - "NEC") AND NFPA 101 (LIFE SAFETY CODE).
    - 5. AMERICAN SOCIETY FOR TESTING OF MATERIALS (ASTM)
    - 6. INSTITUTE OF ELECTRONIC AND ELECTRICAL ENGINEERS (IEEE)
    - 7. AMERICAN CONCRETE INSTITUTE (ACI)
    - 8. AMERICAN WIRE PRODUCERS ASSOCIATION (AWPA)
    - 9. CONCRETE REINFORCING STEEL INSTITUTE (CRSI)
    - 10. AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)
    - 11. PORTLAND CEMENT ASSOCIATION (PCA)
    - 12. NATIONAL CONCRETE MASONRY ASSOCIATION (NCMA)
    - 13. BRICK INDUSTRY ASSOCIATION (BIA)
    - 14. AMERICAN WELDING SOCIETY (AWS)
    - 15. NATIONAL ROOFING CONTRACTORS ASSOCIATION (NRCA)
    - 16. SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)
    - 17. DOOR AND HARDWARE INSTITUTE (DHI)
    - 18. OCCUPATIONAL SAFETY AND HEALTH ACT (OSHA)
    - 19. APPLICABLE BUILDING CODES INCLUDING UNIFORM BUILDING CODE, SOUTHERN BUILDING CODE, BOCA, AND THE INTERNATIONAL BUILDING CODE.

**1.5 DEFINITIONS:**

- A. WORK: THE SUM OF TASKS AND RESPONSIBILITIES IDENTIFIED IN THE CONTRACT DOCUMENTS.
- B. COMPANY: SPRINT CORPORATION
- C. ENGINEER: SYNONYMOUS WITH ARCHITECT & ENGINEER AND "A&E". THE DESIGN PROFESSIONAL HAVING PROFESSIONAL RESPONSIBILITY FOR DESIGN OF THE PROJECT.
- D. CONTRACTOR: CONSTRUCTION CONTRACTOR; CONSTRUCTION VENDOR; INDIVIDUAL OR ENTITY WHO AFTER EXECUTION OF A CONTRACT IS BOUND TO ACCOMPLISH THE WORK.
- E. THIRD PARTY VENDOR OR AGENCY: A VENDOR OR AGENCY ENGAGED SEPARATELY BY THE COMPANY, A&E, OR CONTRACTOR TO PROVIDE MATERIALS OR TO ACCOMPLISH SPECIFIC TASKS RELATED TO BUT NOT INCLUDED IN THE WORK.
- F. OFCI: OWNER FURNISHED, CONTRACTOR INSTALLED EQUIPMENT.
- G. CONSTRUCTION MANAGER - ALL PROJECTS RELATED COMMUNICATION TO FLOW THROUGH SPRINT REPRESENTATIVE IN CHARGE OF PROJECT...

- 1.6 SITE FAMILIARITY: CONTRACTOR SHALL BE RESPONSIBLE FOR FAMILIARIZING HIMSELF WITH ALL CONTRACT DOCUMENTS, FIELD CONDITIONS AND DIMENSIONS PRIOR TO PROCEEDING WITH CONSTRUCTION. ANY DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE SPRINT CONSTRUCTION MANAGER PRIOR TO THE COMMENCEMENT OF WORK. NO COMPENSATION WILL BE AWARDED BASED ON CLAIM OF LACK OF KNOWLEDGE OR FIELD CONDITIONS.
- 1.7 POINT OF CONTACT: COMMUNICATION BETWEEN SPRINT AND THE CONTRACTOR SHALL FLOW THROUGH THE SINGLE SPRINT CONSTRUCTION MANAGER APPOINTED TO MANAGE THE PROJECT FOR SPRINT.
- 1.8 ON-SITE SUPERVISION: THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK AND SHALL BE RESPONSIBLE FOR CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES IN ACCORDANCE WITH THE CONTRACT DOCUMENTS. THE CONTRACTOR SHALL EMPLOY A COMPETENT SUPERINTENDENT WHO SHALL BE IN ATTENDANCE AT THE SITE AT ALL TIMES DURING PERFORMANCE OF THE WORK.
- 1.9 DRAWINGS, SPECIFICATIONS AND DETAILS REQUIRED AT JOBSITE: THE CONSTRUCTION CONTRACTOR SHALL MAINTAIN A FULL SET OF THE CONSTRUCTION DRAWINGS, STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES AND THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES AT THE JOBSITE FROM MOBILIZATION THROUGH CONSTRUCTION COMPLETION.
  - A. THE JOBSITE DRAWINGS, SPECIFICATIONS AND DETAILS SHALL BE CLEARLY MARKED DAILY IN RED PENCIL WITH ANY CHANGES IN CONSTRUCTION OVER WHAT IS DEPICTED IN THE DOCUMENTS. AT CONSTRUCTION COMPLETION, THIS JOBSITE MARKUP SET SHALL BE DELIVERED TO THE COMPANY OR COMPANY'S DESIGNATED REPRESENTATIVE TO BE FORWARDED TO THE COMPANY'S A&E VENDOR FOR PRODUCTION OF "AS-BUILT" DRAWINGS.
  - B. DETAILS ARE INTENDED TO SHOW DESIGN INTENT. MODIFICATIONS MAY BE REQUIRED TO SUIT JOB DIMENSIONS OR CONDITIONS, AND SUCH MODIFICATIONS SHALL BE INCLUDED AS PART OF THE WORK. CONTRACTOR SHALL NOTIFY SPRINT CONSTRUCTION MANAGER OF ANY VARIATIONS PRIOR TO PROCEEDING WITH THE WORK.
  - C. DIMENSIONS SHOWN ARE TO FINISH SURFACES UNLESS NOTED OTHERWISE. SPACING BETWEEN EQUIPMENT IS THE REQUIRED CLEARANCE. SHOULD THERE BE ANY QUESTIONS REGARDING THE CONTRACT DOCUMENTS, EXISTING CONDITIONS AND/OR DESIGN INTENT, THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING A CLARIFICATION FROM THE SPRINT CONSTRUCTION MANAGER PRIOR TO PROCEEDING WITH THE WORK.
- 1.10 USE OF JOB SITE: THE CONTRACTOR SHALL CONFINE ALL CONSTRUCTION AND RELATED OPERATIONS INCLUDING STAGING AND STORAGE OF MATERIALS AND EQUIPMENT, PARKING, TEMPORARY FACILITIES, AND WASTE STORAGE TO THE LEASE PARCEL UNLESS OTHERWISE PERMITTED BY THE CONTRACT DOCUMENTS.
- 1.11 UTILITIES SERVICES: WHERE NECESSARY TO CUT EXISTING PIPES, ELECTRICAL WIRES, CONDUITS, CABLES, ETC., OF UTILITY SERVICES, OR OF FIRE PROTECTION OR COMMUNICATIONS SYSTEMS, THEY SHALL BE CUT AND CAPPED AT SUITABLE PLACES OR WHERE SHOWN. ALL SUCH ACTIONS SHALL BE COORDINATED WITH THE UTILITY COMPANY INVOLVED.
- 1.12 PERMITS / FEES: WHEN REQUIRED THAT A PERMIT OR CONNECTION FEE BE PAID TO A PUBLIC UTILITY PROVIDER FOR NEW SERVICE TO THE CONSTRUCTION PROJECT, PAYMENT OF SUCH FEE SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.
- 1.13 CONTRACTOR SHALL TAKE ALL MEASURES AND PROVIDE ALL MATERIAL NECESSARY FOR PROTECTING EXISTING EQUIPMENT AND PROPERTY.
- 1.14 METHODS OF PROCEDURE (MOPS) FOR CONSTRUCTION: CONTRACTOR SHALL PERFORM WORK AS DESCRIBED IN THE FOLLOWING INSTALLATION AND COMMISSIONING MOPS.
 

NOTE: IN SHORT-FORM SPECIFICATIONS ON THE DRAWINGS, A/E TO INSERT LIST OF APPLICABLE MOPS INCLUDING EN-2012-001, EN-2013-002, EL-0568, AND TS-0193
- 1.15 USE OF ELECTRONIC PROJECT MANAGEMENT SYSTEMS:

**PART 2 - PRODUCTS (NOT USED)**

**PART 3 - EXECUTION**

- 3.1 TEMPORARY UTILITIES AND FACILITIES: THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL TEMPORARY UTILITIES AND FACILITIES NECESSARY EXCEPT AS OTHERWISE INDICATED IN THE CONSTRUCTION DOCUMENTS. TEMPORARY UTILITIES AND FACILITIES INCLUDE POTABLE WATER, HEAT, HVAC, ELECTRICITY, SANITARY FACILITIES, WASTE DISPOSAL FACILITIES, AND TELEPHONE/COMMUNICATION SERVICES. PROVIDE TEMPORARY UTILITIES AND FACILITIES IN ACCORDANCE WITH OSHA AND THE AUTHORITY HAVING JURISDICTION. CONTRACTOR MAY UTILIZE THE COMPANY ELECTRICAL SERVICE IN THE COMPLETION OF THE WORK WHEN IT BECOMES AVAILABLE. USE OF THE LESSORS OR SITE OWNER'S UTILITIES OR FACILITIES IS EXPRESSLY FORBIDDEN EXCEPT AS OTHERWISE ALLOWED IN THE CONTRACT DOCUMENTS.
- 3.2 ACCESS TO WORK: THE CONTRACTOR SHALL PROVIDE ACCESS TO THE JOB SITE FOR AUTHORIZED COMPANY PERSONNEL AND AUTHORIZED REPRESENTATIVES OF THE ARCHITECT/ENGINEER DURING ALL PHASES OF THE WORK.
- 3.3 TESTING: REQUIREMENTS FOR TESTING BY THIS CONTRACTOR SHALL BE AS INDICATED HEREWITH, ON THE CONSTRUCTION DRAWINGS, AND IN THE INDIVIDUAL SECTIONS OF THESE SPECIFICATIONS. SHOULD COMPANY CHOOSE TO ENGAGE ANY THIRD-PARTY TO CONDUCT ADDITIONAL TESTING, THE CONTRACTOR SHALL COOPERATE WITH AND PROVIDE A WORK AREA FOR COMPANY'S TEST AGENCY.
- 3.4 DIMENSIONS: VERIFY DIMENSIONS INDICATED ON DRAWINGS WITH FIELD DIMENSIONS BEFORE FABRICATION OR ORDERING OF MATERIALS. DO NOT SCALE DRAWINGS.

3.5 EXISTING CONDITIONS: NOTIFY THE SPRINT CONSTRUCTION MANAGER OF EXISTING CONDITIONS DIFFERING FROM THOSE INDICATED ON THE DRAWINGS. DO NOT REMOVE OR ALTER STRUCTURAL COMPONENTS WITHOUT PRIOR WRITTEN APPROVAL FROM THE ARCHITECT AND ENGINEER.

**SECTION 01 200 - COMPANY FURNISHED MATERIAL AND EQUIPMENT**

**PART 1 - GENERAL**

- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
  - A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
  - B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.

**PART 2 - PRODUCTS (NOT USED)**

**PART 3 - EXECUTION**

- 3.1 RECEIPT OF MATERIAL AND EQUIPMENT:
  - A. A COMPANY FURNISHED MATERIAL AND EQUIPMENT IS IDENTIFIED ON THE RF DATA SHEET IN THE CONSTRUCTION DOCUMENTS.
  - B. THE CONTRACTOR IS RESPONSIBLE FOR SPRINT PROVIDED MATERIAL AND EQUIPMENT AND UPON RECEIPT SHALL:
    - 1. ACCEPT DELIVERIES AS SHIPPED AND TAKE RECEIPT.
    - 2. VERIFY COMPLETENESS AND CONDITION OF ALL DELIVERIES.
    - 3. TAKE RESPONSIBILITY FOR EQUIPMENT AND PROVIDE INSURANCE PROTECTION AS REQUIRED IN AGREEMENT.
    - 4. RECORD ANY DEFECTS OR DAMAGES AND WITHIN TWENTY-FOUR HOURS AFTER RECEIPT, REPORT TO SPRINT OR ITS DESIGNATED PROJECT REPRESENTATIVE OF SUCH.
    - 5. PROVIDE SECURE AND NECESSARY WEATHER PROTECTED WAREHOUSING.
    - 6. COORDINATE SAFE AND SECURE TRANSPORTATION OF MATERIAL AND EQUIPMENT, DELIVERING AND OFF-LOADING FROM CONTRACTOR'S WAREHOUSE TO SITE.
- 3.2 DELIVERABLES:
  - A. COMPLETE SHIPPING AND RECEIPT DOCUMENTATION IN ACCORDANCE WITH COMPANY PRACTICE.
  - B. IF APPLICABLE, COMPLETE LOST/STOLEN/DAMAGED DOCUMENTATION REPORT AS NECESSARY IN ACCORDANCE WITH COMPANY PRACTICE, AND AS DIRECTED BY COMPANY.
  - C. UPLOAD DOCUMENTATION INTO SPRINT SITE MANAGEMENT SYSTEM (SMS) AND/OR PROVIDE HARD COPY DOCUMENTATION AS REQUESTED.

**SECTION 01 300 - CELL SITE CONSTRUCTION CO.**

**PART 1 - GENERAL**

- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
  - A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
  - B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.
- 1.3 NOTICE TO PROCEED
  - A. NO WORK SHALL COMMENCE PRIOR TO COMPANY'S WRITTEN NOTICE TO PROCEED AND THE ISSUANCE OF THE WORK ORDER.
  - B. UPON RECEIVING NOTICE TO PROCEED, CONTRACTOR SHALL FULLY PERFORM ALL WORK NECESSARY TO PROVIDE SPRINT WITH AN OPERATIONAL WIRELESS FACILITY.

**TOWER OWNER NOTIFICATION**  
 ONCE THE CONTRACTOR HAS RECEIVED AND ACCEPTED THE NOTICE TO PROCEED, CONTRACTOR WILL CONTACT THE CROWN CASTLE CONSTRUCTION MANAGER OF RECORD (NOTED ON THE FIRST PAGE ON THIS CONSTRUCTION DRAWING) A MINIMUM OF 48 HOURS PRIOR TO WORK START. UPON ARRIVAL TO THE JOB SITE, CONTRACTOR CREW IS REQUIRED CALL 1-800-788-7011 TO NOTIFY THE CROWN CASTLE NOC WORK HAS BEGUN.

**PART 2 - PRODUCTS (NOT USED)**

**PART 3 - EXECUTION**

- 3.1 FUNCTIONAL REQUIREMENTS:
  - A. THE ACTIVITIES DESCRIBED IN THIS PARAGRAPH REPRESENT MINIMUM ACTIONS AND PROCESSES REQUIRED TO SUCCESSFULLY COMPLETE THE WORK. THE ACTIVITIES DESCRIBED ARE NOT EXHAUSTIVE, AND CONTRACTOR SHALL TAKE ANY AND ALL ACTIONS AS NECESSARY TO SUCCESSFULLY COMPLETE THE CONSTRUCTION OF A FULLY FUNCTIONING WIRELESS FACILITY AT THE SITE IN ACCORDANCE WITH COMPANY PROCESSES.
  - B. SUBMIT SPECIFIC DOCUMENTATION AS INDICATED HEREIN, AND OBTAIN REQUIRED APPROVALS WHILE THE WORK IS BEING PERFORMED.
  - C. MANAGE AND CONDUCT ALL FIELD CONSTRUCTION SERVICE RELATED ACTIVITIES
  - D. PROVIDE CONSTRUCTION ACTIVITIES TO THE EXTENT REQUIRED BY THE CONTRACT DOCUMENTS, INCLUDING BUT NOT LIMITED TO THE FOLLOWING:

PLANS PREPARED FOR:



PLANS PREPARED BY:



MLA PARTNER:



ENGINEERING LICENSE:



DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

NO.	DESCRIPTION	DATE	BY

ISSUED FOR CONSTRUCTION

3/17/14	MAP	0
---------	-----	---

SITE NAME:

**WEST HARTFORD PARKING GARAGE**

SITE CASCADE:

**CT03XC075**

SITE ADDRESS:

27-31 SOUTH MAIN ST  
WEST HARTFORD, CT 06110

SHEET DESCRIPTION:

**SPRINT SPECIFICATIONS**

SHEET NUMBER:

**SP-1**

**CONTINUE FROM SP-1**

1. PERFORM ANY REQUIRED SITE ENVIRONMENTAL MITIGATION.
2. PREPARE GROUND SITES; PROVIDE DE-GRUBBING; AND ROUGH AND FINAL GRADING, AND COMPOUND SURFACE TREATMENTS.
3. MANAGE AND CONDUCT ALL ACTIVITIES FOR INSTALLATION OF UTILITIES INCLUDING ELECTRICAL AND TELCO BACKHAUL.
4. INSTALL UNDERGROUND FACILITIES INCLUDING UNDERGROUND POWER AND COMMUNICATIONS CONDUITS, AND UNDERGROUND GROUNDING SYSTEM.
5. INSTALL ABOVE GROUND GROUNDING SYSTEMS.
6. PROVIDE NEW HVAC INSTALLATIONS AND MODIFICATIONS.
7. INSTALL "H-FRAMES", CABINETS AND SHELTERS AS INDICATED.
8. INSTALL ROADS, ACCESS WAYS, CURBS AND DRAINS AS INDICATED.
9. ACCOMPLISH REQUIRED MODIFICATION OF EXISTING FACILITIES.
10. PROVIDE ANTENNA SUPPORT STRUCTURE FOUNDATIONS.
11. PROVIDE SLABS AND EQUIPMENT PLATFORMS.
12. INSTALL COMPOUND FENCING, SIGHT SHIELDING, LANDSCAPING AND ACCESS BARRIERS.
13. PERFORM INSPECTION AND MATERIAL TESTING AS REQUIRED HEREINAFTER.
14. CONDUCT SITE RESISTANCE TO EARTH TESTING AS REQUIRED HEREINAFTER
15. INSTALL FIXED GENERATOR SETS AND OTHER STANDBY POWER SOLUTIONS.
16. INSTALL TOWERS, ANTENNA SUPPORT STRUCTURES AND PLATFORMS ON EXISTING TOWERS AS REQUIRED.
17. INSTALL CELL SITE RADIOS, MICROWAVE, GPS, COAXIAL MAINLINE, ANTENNAS, CROSS BAND COUPLERS, TOWER TOP AMPLIFIERS, LOW NOISE AMPLIFIERS AND RELATED EQUIPMENT.
18. PERFORM, DOCUMENT, AND CLOSE OUT ANY CONSTRUCTION CONTROL DOCUMENTS THAT MAY BE REQUIRED BY GOVERNMENT AGENCIES AND LANDLORDS.
19. PERFORM ANTENNA AND COAX SWEEP TESTING AND MAKE ANY AND ALL NECESSARY CORRECTIONS.
20. REMAIN ON SITE MOBILIZED THROUGHOUT HAND-OFF AND INTEGRATION TO ASSIST AS NEEDED UNTIL SITE IS DEEMED SUBSTANTIALLY COMPLETE AND PLACED "ON AIR."

**3.2 GENERAL REQUIREMENTS FOR CIVIL CONSTRUCTION:**

- A. CONTRACTOR SHALL KEEP THE SITE FREE FROM ACCUMULATING WASTE MATERIAL, DEBRIS, AND TRASH. AT THE COMPLETION OF THE WORK, CONTRACTOR SHALL REMOVE FROM THE SITE ALL REMAINING RUBBISH, IMPLEMENTS, TEMPORARY FACILITIES, AND SURPLUS MATERIALS.
- B. EQUIPMENT ROOMS SHALL AT ALL TIMES BE MAINTAINED "BROOM CLEAN" AND CLEAR OF DEBRIS.
- C. CONTRACTOR SHALL TAKE ALL REASONABLE PRECAUTIONS TO DISCOVER AND LOCATE ANY HAZARDOUS CONDITION.
  1. IN THE EVENT CONTRACTOR ENCOUNTERS ANY HAZARDOUS CONDITION WHICH HAS NOT BEEN ABATED OR OTHERWISE MITIGATED, CONTRACTOR AND ALL OTHER PERSONS SHALL IMMEDIATELY STOP WORK IN THE AFFECTED AREA AND NOTIFY COMPANY IN WRITING. THE WORK IN THE AFFECTED AREA SHALL NOT BE RESUMED EXCEPT BY WRITTEN NOTIFICATION BY COMPANY.
  2. CONTRACTOR AGREES TO USE CARE WHILE ON THE SITE AND SHALL NOT TAKE ANY ACTION THAT WILL OR MAY RESULT IN OR CAUSE THE HAZARDOUS CONDITION TO BE FURTHER RELEASED IN THE ENVIRONMENT, OR TO FURTHER EXPOSE INDIVIDUALS TO THE HAZARD.
- D. CONTRACTOR'S ACTIVITIES SHALL BE RESTRICTED TO THE PROJECT LIMITS. SHOULD AREAS OUTSIDE THE PROJECT LIMITS BE AFFECTED BY CONTRACTOR'S ACTIVITIES, CONTRACTOR SHALL IMMEDIATELY RETURN THEM TO ORIGINAL CONDITION
- E. CONDUCT TESTING AS REQUIRED HEREIN.

**3.3 DELIVERABLES:**

- A. CONTRACTOR SHALL REVIEW, APPROVE, AND SUBMIT TO SPRINT SHOP DRAWINGS, PRODUCT DATA, SAMPLES, AND SIMILAR SUBMITTALS AS REQUIRED HEREINAFTER
- B. PROVIDE DOCUMENTATION INCLUDING, BUT NOT LIMITED TO, THE FOLLOWING. DOCUMENTATION SHALL BE FORWARDED IN ORIGINAL FORMAT AND/OR UPLOADED INTO SMS.
  1. ALL CORRESPONDENCE AND PRELIMINARY CONSTRUCTION REPORTS.
  2. PROJECT PROGRESS REPORTS.
  3. CIVIL CONSTRUCTION START DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
  4. ELECTRICAL SERVICE COMPLETION DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).

5. LINES AND ANTENNA INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
6. POWER INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
7. TELCO READY DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
8. PPC (OR SHELTER) INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
9. TOWER CONSTRUCTION START DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
10. TOWER CONSTRUCTION COMPLETE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
11. BTS AND RADIO EQUIPMENT DELIVERED AT SITE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
12. NETWORK OPERATIONS HANDOFF CHECKLIST (HOC WALK) COMPLETE (UPLOAD FORM IN SMS)
13. CIVIL CONSTRUCTION COMPLETE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
14. SITE CONSTRUCTION PROGRESS PHOTOS UNLOADED INTO SMS.

**SECTION 01 400 - SUBMITTALS & TESTS**

**PART 1 - GENERAL**

- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
  - A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
  - B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.
- 1.3 SUBMITTALS:
  - A. THE WORK IN ALL ASPECTS SHALL COMPLY WITH THE CONSTRUCTION DRAWINGS AND THESE SPECIFICATIONS.
  - B. SUBMIT THE FOLLOWING TO COMPANY REPRESENTATIVE FOR APPROVAL.
    1. CONCRETE MIX-DESIGNS FOR TOWER FOUNDATIONS, ANCHORS PIERS, AND CONCRETE PAVING.
    2. CONCRETE BREAK TESTS AS SPECIFIED HEREIN.
    3. SPECIAL FINISHES FOR INTERIOR SPACES, IF ANY.
    4. ALL EQUIPMENT AND MATERIALS SO IDENTIFIED ON THE CONSTRUCTION DRAWINGS.
    5. CHEMICAL GROUNDING DESIGN
  - D. ALTERNATES: AT THE COMPANY'S REQUEST, ANY ALTERNATIVES TO THE MATERIALS OR METHODS SPECIFIED SHALL BE SUBMITTED TO SPRINT'S CONSTRUCTION MANAGER FOR APPROVAL PRIOR TO BEING SHIPPED TO SITE. SPRINT WILL REVIEW AND APPROVE ONLY THOSE REQUESTS MADE IN WRITING. NO VERBAL APPROVALS WILL BE CONSIDERED. SUBMITTAL FOR APPROVAL SHALL INCLUDE A STATEMENT OF COST REDUCTION PROPOSED FOR USE OF ALTERNATE PRODUCT.

**1.4 TESTS AND INSPECTIONS:**

- A. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CONSTRUCTION TESTS, INSPECTIONS AND PROJECT DOCUMENTATION.
- B. CONTRACTOR SHALL ACCOMPLISH TESTING INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
  1. COAX SWEEPS AND FIBER TESTS PER TS-0200 REV 4 ANTENNA LINE ACCEPTANCE STANDARDS.
  2. AGL, AZIMUTH AND DOWNTILT USING ELECTRONIC COMMERCIAL MADE-FOR-THE-PURPOSE ANTENNA ALIGNMENT TOOL.
  3. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN SITE INSPECTION ACTIVITIES AND/OR AS A RESULT OF TESTING.
- C. REQUIRED CLOSEOUT DOCUMENTATION INCLUDES, BUT IS NOT LIMITED TO THE FOLLOWING:
  1. AZIMUTH, DOWNTILT, AGL - UPLOAD REPORT FROM ANTENNA ALIGNMENT TOOL TO SITERRA TASK 465. INSTALLED AZIMUTH, DOWNTILT, AND AGL MUST CONFORM TO THE RF DATA SHEETS. SWEEP AND FIBER TESTS
  2. SCANABLE BARCODE PHOTOGRAPHS OF TOWER TOP AND INACCESSIBLE SERIALIZED EQUIPMENT
  3. ALL AVAILABLE JURISDICTIONAL INFORMATION
  4. PDF SCAN OF REDLINES PRODUCED IN FIELD

5. ELECTRONIC AS-BUILT DRAWINGS IN AUTOCAD AND PDF FORMATS. ANY FIELD CHANGE MUST BE REFLECTED BY MODIFYING THE PLANS, ELEVATIONS, AND DETAILS IN THE DRAWING SETS. GENERAL NOTES INDICATING MODIFICATIONS WILL NOT BE ACCEPTED. CHANGES SHALL BE HIGHLIGHTED AS "CLOUDS" IDENTIFIED AS THE "AS-BUILT" CONDITION.
6. LIEN WAIVERS
7. FINAL PAYMENT APPLICATION
8. REQUIRED FINAL CONSTRUCTION PHOTOS
9. CONSTRUCTION AND COMMISSIONING CHECKLIST COMPLETE WITH NO DEFICIENT ITEMS
10. ALL POST NTP TASKS INCLUDING DOCUMENT UPLOADS COMPLETED IN SITERRA (SPRINTS DOCUMENT REPOSITORY OF RECORD).

1.5 COMMISSIONING: PERFORM ALL COMMISSIONING AS REQUIRED BY APPLICABLE MOPs

1.6 INTEGRATION: PERFORM ALL INTEGRATION ACTIVITIES AS REQUIRED BY APPLICABLE MOPs

**PART 2 - PRODUCTS (NOT USED)**

**PART 3 - EXECUTION**

**3.1 REQUIREMENTS FOR TESTING:**

**A. THIRD PARTY TESTING AGENCY:**

1. WHEN THE USE OF A THIRD PARTY INDEPENDENT TESTING AGENCY IS REQUIRED, THE AGENCY THAT IS SELECTED MUST PERFORM SUCH WORK ON A REGULAR BASIS IN THE STATE WHERE THE PROJECT IS LOCATED AND HAVE A THOROUGH UNDERSTANDING OF LOCAL AVAILABLE MATERIALS, INCLUDING THE SOIL, ROCK, AND GROUNDWATER CONDITIONS.
2. THE THIRD PARTY TESTING AGENCY IS TO BE FAMILIAR WITH THE APPLICABLE REQUIREMENTS FOR THE TESTS TO BE DONE, EQUIPMENT TO BE USED, AND ASSOCIATED HEALTH AND SAFETY ISSUES.
3. EXPERIENCE IN SOILS, CONCRETE, MASONRY, AGGREGATE, AND ASPHALT TESTING USING ASTM, AASJTO, AND OTHER METHODS IS NEEDED.
4. EXPERIENCE IN SOILS, CONCRETE, MASONRY, AGGREGATE, AND ASPHALT TESTING USING ASTM, AASJTO, AND OTHER METHODS IS NEEDED.

**3.2 REQUIRED TESTS:**

**A. CONTRACTOR SHALL ACCOMPLISH TESTING INCLUDING BUT NOT LIMITED TO THE FOLLOWING:**

1. CONCRETE CYLINDER BREAK TESTS FOR THE TOWER AND ANCHOR FOUNDATIONS AS SPECIFIED IN SECTION: PORTLAND CEMENT CONCRETE PAVING.
2. ASPHALT ROADWAY COMPACTED THICKNESS, SURFACE SMOOTHNESS, AND COMPACTED DENSITY TESTING AS SPECIFIED IN SECTION: HOT MIX ASPHALT PAVING.
3. FIELD QUALITY CONTROL TESTING AS SPECIFIED IN SECTION: PORTLAND CEMENT CONCRETE PAVING.
4. TESTING REQUIRED UNDER SECTION: AGGREGATE BASE FOR ACCESS ROADS, PADS AND ANCHOR LOCATIONS
5. STRUCTURAL BACKFILL COMPACTION TESTS FOR THE TOWER FOUNDATION.
6. SITE RESISTANCE TO EARTH TESTING PER EXHIBIT: CELL SITE GROUNDING SYSTEM DESIGN.
7. ANTENNA AND COAX SWEEP TESTS PER EXHIBIT: ANTENNA TRANSMISSION LINE ACCEPTANCE STANDARDS.
8. GROUNDING AT ANTENNA MASTS FOR GPS AND ANTENNAS
9. ALL OTHER TESTS REQUIRED BY COMPANY OR JURISDICTION.

**3.3 REQUIRED INSPECTIONS**

**A. SCHEDULE INSPECTIONS WITH COMPANY REPRESENTATIVE.**

**B. CONDUCT INSPECTIONS INCLUDING BUT NOT LIMITED TO THE FOLLOWING:**

1. GROUNDING SYSTEM INSTALLATION PRIOR TO EARTH CONCEALMENT DOCUMENTED WITH DIGITAL PHOTOGRAPHS BY CONTRACTOR, APPROVED BY A&E OR SPRINT REPRESENTATIVE.
2. FORMING FOR CONCRETE AND REBAR PLACEMENT PRIOR TO POUR DOCUMENTED WITH DIGITAL PHOTOGRAPHS BY CONTRACTOR, APPROVED BY A&E OR SPRINT REPRESENTATIVE.
3. COMPACTION OF BACKFILL MATERIALS; AGGREGATE BASE FOR ROADS, PADS, AND ANCHORS; ASPHALT PAVING; AND SHAFT BACKFILL FOR CONCRETE AND WOOD POLES, BY INDEPENDENT THIRD PARTY AGENCY.
4. PRE- AND POST-CONSTRUCTION ROOFTOP AND STRUCTURAL INSPECTIONS ON EXISTING FACILITIES.
5. TOWER ERECTION SECTION STACKING AND PLATFORM ATTACHMENT DOCUMENTED BY DIGITAL PHOTOGRAPHS BY THIRD PARTY AGENCY.
6. ANTENNA AZIMUTH, DOWN TILT AND PER SUNLIGHT TOOL SUNSIGHT INSTRUMENTS - ANTENNALIGN ALIGNMENT TOOL (AAT)

PLANS PREPARED FOR:



PLANS PREPARED BY:



MLA PARTNER:



ENGINEERING LICENSE:



DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

NO.	DESCRIPTION	DATE	BY

ISSUED FOR CONSTRUCTION	3/17/14	MAP	0
-------------------------	---------	-----	---

SITE NAME:

**WEST HARTFORD PARKING GARAGE**

SITE CASCADE:

**CT03XC075**

SITE ADDRESS:

27-31 SOUTH MAIN ST  
WEST HARTFORD, CT 06110

SHEET DESCRIPTION:

**SPRINT SPECIFICATIONS**

SHEET NUMBER:

**SP-2**

**CONTINUE FROM SP-2**

- 7. VERIFICATION DOCUMENTED WITH THE ANTENNA CHECKLIST REPORT, BY A&E, SITE DEVELOPMENT REP, OR RF REP.
- 8. FINAL INSPECTION CHECKLIST AND HANDOFF WALK (HOC). SIGNED FORM SHOWING ACCEPTANCE BY FIELD OPS IS TO BE UPLOADED INTO SMS.
- 9. COAX SWEEP AND FIBER TESTING DOCUMENTS SUBMITTED VIA SMS FOR RF APPROVAL.
- 10. SCAN-ABLE BARCODE PHOTOGRAPHS OF TOWER TOP AND INACCESSIBLE SERIALIZED EQUIPMENT
- 11. ALL AVAILABLE JURISDICTIONAL INFORMATION
- 12. PDF SCAN OF REDLINES PRODUCED IN FIELD
- C. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN SITE INSPECTION ACTIVITIES AND/OR AS A RESULT OF TESTING.
- D. CONSTRUCTION INSPECTIONS AND CORRECTIVE MEASURES SHALL BE DOCUMENTED BY THE CONTRACTOR WITH WRITTEN REPORTS AND PHOTOGRAPHS. PHOTOGRAPHS MUST BE DIGITAL AND OF SUFFICIENT QUALITY TO CLEARLY SHOW THE SITE CONSTRUCTION. PHOTOGRAPHS MUST CLEARLY IDENTIFY THE PHOTOGRAPHED ITEM AND BE LABELED WITH THE SITE CASCADE NUMBER, SITE NAME, DESCRIPTION, AND DATE.
- 3.4 DELIVERABLES: TEST AND INSPECTION REPORTS AND CLOSEOUT DOCUMENTATION SHALL BE UPLOADED TO THE SMS AND/OR FORWARDED TO SPRINT FOR INCLUSION INTO THE PERMANENT SITE FILES.
  - A. THE FOLLOWING TEST AND INSPECTION REPORTS SHALL BE PROVIDED AS APPLICABLE.
    - 1. CONCRETE MIX AND CYLINDER BREAK REPORTS.
    - 2. STRUCTURAL BACKFILL COMPACTION REPORTS.
    - 3. SITE RESISTANCE TO EARTH TEST.
    - 4. ANTENNA AZIMUTH AND DOWN TILT VERIFICATION
    - 5. TOWER ERECTION INSPECTIONS AND MEASUREMENTS DOCUMENTING TOWER INSTALLED PER SUPPLIER'S REQUIREMENTS AND THE APPLICABLE SECTIONS HEREIN.
    - 6. COAX CABLE SWEEP TESTS PER COMPANY'S "ANTENNA LINE ACCEPTANCE STANDARDS".
  - B. REQUIRED CLOSEOUT DOCUMENTATION INCLUDES THE FOLLOWING;
    - 1. TEST WELLS AND TRENCHES: PHOTOGRAPHS OF ALL TEST WELLS; PHOTOGRAPHS SHOWING ALL OPEN EXCAVATIONS AND TRENCHING PRIOR TO BACKFILLING SHOWING A TAPE MEASURE VISIBLE IN THE EXCAVATIONS INDICATING DEPTH.
    - 2. CONDUITS, CONDUCTORS AND GROUNDING: PHOTOGRAPHS SHOWING TYPICAL INSTALLATION OF CONDUCTORS AND CONNECTORS; PHOTOGRAPHS SHOWING TYPICAL BEND RADIUS OF INSTALLED GROUND WIRES AND GROUND ROD SPACING;
    - 3. CONCRETE FORMS AND REINFORCING: CONCRETE FORMING AT TOWER AND EQUIPMENT/SHELTER PAD/FOUNDATIONS - PHOTOGRAPHS SHOWING ALL REINFORCING STEEL, UTILITY AND CONDUIT STUB OUTS; PHOTOGRAPHS SHOWING CONCRETE POUR OF SHELTER SLAB/FOUNDATION, TOWER FOUNDATION AND GUY ANCHORS WITH VIBRATOR IN USE; PHOTOGRAPHS SHOWING EACH ANCHOR ON GUYED TOWERS, BEFORE CONCRETE POUR.
    - 4. TOWER, ANTENNAS AND MAINLINE: INSPECTION AND PHOTOGRAPHS OF SECTION STACKING; INSPECTION AND PHOTOGRAPHS OF PLATFORM COMPONENT ATTACHMENT POINTS; PHOTOGRAPHS OF TOWER TOP GROUNDING; PHOTOS OF TOWER COAX LINE COLOR CODING AT THE TOP AND AT GROUND LEVEL; INSPECTION AND PHOTOGRAPHS OF OPERATIONAL OF TOWER LIGHTING, AND PLACEMENT OF FAA REGISTRATION SIGN; PHOTOGRAPHS SHOWING ADDITIONAL GROUNDING POINTS FOR TOWERS GREATER THAN 200 FEET.; PHOTOS OF ANTENNA GROUND BAR, EQUIPMENT GROUND BAR, AND MASTER GROUND BAR; PHOTOS OF GPS ANTENNA(S); PHOTOS OF EACH SECTOR OF ANTENNAS; ONE PHOTOGRAPH LOOKING AT THE SECTOR AND ONE FROM BEHIND SHOWING THE PROJECTED COVERAGE AREA; PHOTOS OF COAX WEATHERPROOFING - TOP AND BOTTOM; PHOTOS OF COAX GROUNDING--TOP AND BOTTOM; PHOTOS OF ANTENNA AND MAST GROUNDING; PHOTOS OF COAX CABLE ENTRY INTO SHELTER; PHOTOS OF PLATFORM MECHANICAL CONNECTIONS TO TOWER/MONOPOLE.
    - 5. ROOF TOPS: PRE-CONSTRUCTION AND POST-CONSTRUCTION VISUAL INSPECTION AND PHOTOGRAPHS OF THE ROOF AND INTERIOR TO DETERMINE AND DOCUMENT CONDITIONS; ROOF TOP CONSTRUCTION INSPECTIONS AS REQUIRED BY THE JURISDICTION; PHOTOGRAPHS OF CABLE TRAY AND/OR ICE BRIDGE; PHOTOGRAPHS OF DOGHOUSE/CABLE EXIT FROM ROOF;
    - 6. SITE LAYOUT - PHOTOGRAPHS OF THE OVERALL COMPOUND, INCLUDING EQUIPMENT PLATFORM FROM ALL FOUR CORNERS.
    - 7. FINISHED UTILITIES: CLOSE-UP PHOTOGRAPHS OF THE PPC BREAKER PANEL; CLOSE-UP PHOTOGRAPH OF THE INSIDE OF THE TELCO PANEL AND NIU; CLOSE-UP PHOTOGRAPH OF THE POWER METER AND DISCONNECT; PHOTOS OF POWER AND TELCO ENTRANCE TO COMPANY ENCLOSURE; PHOTOGRAPHS AT METER BOX AND/OR FACILITY DISTRIBUTION PANEL.
    - 8. REQUIRED MATERIALS CERTIFICATIONS: CONCRETE MIX DESIGNS; MILL CERTIFICATION FOR ALL REINFORCING AND STRUCTURAL STEEL; AND ASPHALT PAVING MIX DESIGN.
    - 9. ANY AND ALL SUBMITTALS BY THE JURISDICTION OR COMPANY.

**SECTION 01 400 - SUBMITTALS & TESTS**

**PART 1 - GENERAL**

- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
  - A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
  - B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.


**PART 2 - PRODUCTS (NOT USED)**

**PART 3 - EXECUTION**

- 3.1 WEEKLY REPORTS:
  - A. CONTRACTOR SHALL PROVIDE SPRINT WITH WEEKLY REPORTS SHOWING PROJECT STATUS. THIS STATUS REPORT FORMAT WILL BE PROVIDED TO THE CONTRACTOR BY SPRINT. THE REPORT WILL CONTAIN SITE ID NUMBER, THE MILESTONES FOR EACH SITE, INCLUDING THE BASELINE DATE, ESTIMATED COMPLETION DATE AND ACTUAL COMPLETION DATE.
  - B. REPORT INFORMATION WILL BE TRANSMITTED TO SPRINT VIA ELECTRONIC MEANS AS REQUIRED. THIS INFORMATION WILL PROVIDE A BASIS FOR PROGRESS MONITORING AND PAYMENT.
- 3.2 PROJECT CONFERENCE CALLS:
  - A. SPRINT MAY HOLD WEEKLY PROJECT CONFERENCE CALLS. CONTRACTOR WILL BE REQUIRED TO COMMUNICATE SITE STATUS, MILESTONE COMPLETIONS AND UPCOMING MILESTONE PROJECTIONS, AND ANSWER ANY OTHER SITE STATUS QUESTIONS AS NECESSARY.
- 3.3 PROJECT TRACKING IN SMS:
  - A. CONTRACTOR SHALL PROVIDE SCHEDULE UPDATES AND PROJECTIONS IN THE SMS SYSTEM ON A WEEKLY BASIS.
- 3.4 ADDITIONAL REPORTING:
  - A. ADDITIONAL OR ALTERNATE REPORTING REQUIREMENTS MAY BE ADDED TO THE REPORT AS DETERMINED TO BE REASONABLY NECESSARY BY COMPANY.
- 3.5 PROJECT PHOTOGRAPHS:
  - A. FILE DIGITAL PHOTOGRAPHS OF COMPLETED SITE IN JPEG FORMAT IN THE SMS PHOTO LIBRARY FOR THE RESPECTIVE SITE. PHOTOGRAPHS SHALL BE CLEARLY LABELED WITH SITE NUMBER, NAME AND DESCRIPTION, AND SHALL INCLUDE AT A MINIMUM THE FOLLOWING AS APPLICABLE:
    - 1. SHELTER AND TOWER OVERVIEW.
    - 2. TOWER FOUNDATION(S) - FORMS AND STEEL BEFORE POUR (EACH ANCHOR ON GUYED TOWERS).
    - 3. TOWER FOUNDATION(S) POUR WITH VIBRATOR IN USE (EACH ANCHOR ON GUYED TOWERS).
    - 4. TOWER STEEL AS BEING INSTALLED INTO HOLE (SHOW ANCHOR STEEL ON GUYED TOWERS).
    - 5. PHOTOS OF TOWER SECTION STACKING.
    - 6. CONCRETE TESTING / SAMPLES.
    - 7. PLACING OF ANCHOR BOLTS IN TOWER FOUNDATION.
    - 8. BUILDING/WATER TANK FROM ROAD FOR TENANT IMPROVEMENTS OR COMMENTS.
    - 9. SHELTER FOUNDATION--FORMS AND STEEL BEFORE POURING.
    - 10. SHELTER FOUNDATION POUR WITH VIBRATOR IN USE.
    - 11. COAX CABLE ENTRY INTO SHELTER.
    - 12. PLATFORM MECHANICAL CONNECTIONS TO TOWER/MONOPOLE.
    - 13. ROOFTOP PRE AND POST CONSTRUCTION PHOTOS TO INCLUDE PENETRATIONS AND INTERIOR CEILING.
    - 14. PHOTOS OF TOWER TOP COAX LINE COLOR CODING AND COLOR CODING AT GROUND LEVEL.
    - 15. PHOTOS OF ALL APPROPRIATE COMPANY OR REGULATORY SIGNAGE.
    - 16. PHOTOS OF EQUIPMENT BOLT DOWN INSIDE SHELTER.
    - 17. POWER AND TELCO ENTRANCE TO COMPANY ENCLOSURE AND POWER AND TELCO SUPPLY LOCATIONS INCLUDING METER/DISCONNECT.
    - 18. ELECTRICAL TRENCH(S) WITH ELECTRICAL / CONDUIT BEFORE BACKFILL.
    - 19. ELECTRICAL TRENCH(S) WITH FOIL-BACKED TAPE BEFORE FURTHER BACKFILL.
    - 20. TELCO TRENCH WITH TELEPHONE / CONDUIT BEFORE BACKFILL.
    - 21. TELCO TRENCH WITH FOIL-BACKED TAPE BEFORE FURTHER BACKFILL.
    - 22. SHELTER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADII).
    - 23. TOWER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADII).

- 24. FENCE GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADII).
  - 25. ALL BTS GROUND CONNECTIONS.
  - 26. ALL GROUND TEST WELLS.
  - 27. ANTENNA GROUND BAR AND EQUIPMENT GROUND BAR.
  - 28. ADDITIONAL GROUNDING POINTS ON TOWERS ABOVE 200'.
  - 29. HVAC UNITS INCLUDING CONDENSERS ON SPLIT SYSTEMS.
  - 30. GPS ANTENNAS.
  - 31. CABLE TRAY AND/OR WAVEGUIDE BRIDGE.
  - 32. DOGHOUSE/CABLE EXIT FROM ROOF.
  - 33. EACH SECTOR OF ANTENNAS; ONE PHOTOGRAPH LOOKING AT THE SECTOR AND ONE FROM BEHIND SHOWING THE PROJECTED COVERAGE AREA.
  - 34. MASTER BUS BAR.
  - 35. TELCO BOARD AND NIU.
  - 36. ELECTRICAL DISTRIBUTION WALL.
  - 37. CABLE ENTRY WITH SURGE SUPPRESSION.
  - 38. ENTRANCE TO EQUIPMENT ROOM.
  - 39. COAX WEATHERPROOFING--TOP AND BOTTOM OF TOWER.
  - 40. COAX GROUNDING --TOP AND BOTTOM OF TOWER.
  - 41. ANTENNA AND MAST GROUNDING.
  - 42. LANDSCAPING - WHERE APPLICABLE.
- 3.6 FINAL PROJECT ACCEPTANCE: COMPLETE ALL REQUIRED REPORTING TASKS PER CONTRACT, CONTRACT DOCUMENTS OR THE SPRINT INTEGRATED CONSTRUCTION STANDARDS FOR WIRELESS SITES AND UPLOAD INTO SITERRA.


PLANS PREPARED FOR:



6580 Sprint Parkway  
Overland Park, Kansas 66251

---


PLANS PREPARED BY:



1033 Watervliet Shaker Rd  
Albany, NY 12205  
Office # (518) 690-0790  
Fax # (518) 690-0793  
JOB NUMBER 353-000


---

MLA PARTNER:




---

ENGINEERING LICENSE:




---

DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

---

REVISIONS:


---

ISSUED FOR CONSTRUCTION: 3/17/14 MAP 0

---

SITE NAME:

**WEST HARTFORD PARKING GARAGE**

---

SITE CASCADE:

**CT03XC075**

---

SITE ADDRESS:

27-31 SOUTH MAIN ST  
WEST HARTFORD, CT 06110

---

SHEET DESCRIPTION:



**SPRINT SPECIFICATIONS**

---

SHEET NUMBER:



**SP-3**

INFORMATION CONTAINED WITHIN DRAWINGS ARE BASED ON PROVIDED INFORMATION AND ARE NOT THE RESULT OF A FIELD SURVEY.



OVERALL SITE PLAN

SCALE: AS NOTED 1



SPRINT EQUIPMENT PLAN

SCALE: AS NOTED 2

PLANS PREPARED FOR:

6580 Sprint Parkway  
Overland Park, Kansas 66251

PLANS PREPARED BY:

Design. Build. Deliver.

1033 Watervliet Shaker Rd  
Albany, NY 12205  
Office # (518) 690-0790  
Fax # (518) 690-0793

JOB NUMBER 353-000

MLA PARTNER:

CROWN CASTLE

ENGINEERING LICENSE:

STATE OF CONNECTICUT  
JOHN S. STEVENS  
No. 24705  
LICENSED PROFESSIONAL ENGINEER

DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

NO.	DESCRIPTION	DATE

ISSUED FOR CONSTRUCTION 3/17/14 MAP 0

SITE NAME:

WEST HARTFORD PARKING GARAGE

SITE CASCADE:

CT03XC075

SITE ADDRESS:

27-31 SOUTH MAIN ST  
WEST HARTFORD, CT 06110

SHEET DESCRIPTION:


SITE PLAN

SHEET NUMBER:

A-1

**NOTE:**  
SPRINT TOWER TOP WORK CONTINGENT ON FOLLOWING:  
COMPLETION OF STRUCTURAL ANALYSIS PROVIDED BY  
CROWN CASTLE, COMPLETION OF ANTENNA/RRH  
MOUNTING ASSESSMENT (PROVIDED BY AE)

**NOTE:**  
BASED ON THE ANALYSIS PROVIDED BY GPD GROUP,  
DATED 3/7/14, THE EXISTING STRUCTURE IS CAPABLE  
OF SUPPORTING THE PROPOSED EQUIPMENT  
CONFIGURATION. THE ANALYSIS INDICATES THE TOWER  
AND ITS FOUNDATION HAVE SUFFICIENT CAPACITY TO  
CARRY THE EXISTING, RESERVED, AND PROPOSED LOADS.  
NO MODIFICATIONS ARE REQUIRED AT THIS TIME.




**NOTE:**  
SEE DETAIL 2 ON A-3  
FOR ANTENNA LAYOUT

PLANS PREPARED FOR:  
**Sprint**  
6580 Sprint Parkway  
Overland Park, Kansas 66251

PLANS PREPARED BY:  
**INFINIGY** Design.  
Build.  
Deliver.  
1033 Watervliet Shaker Rd  
Albany, NY 12205  
Office # (518) 690-0790  
Fax # (518) 690-0793  
JOB NUMBER 353-000

MLA PARTNER:  
**CROWN CASTLE**



DRAWING NOTICE:  
THESE DOCUMENTS ARE CONFIDENTIAL AND ARE  
THE SOLE PROPERTY OF SPRINT AND MAY NOT BE  
REPRODUCED, DISSEMINATED OR REDISTRIBUTED  
WITHOUT THE EXPRESS WRITTEN CONSENT OF  
SPRINT.

REVISIONS:

ISSUED FOR CONSTRUCTION	3/17/14	MAP	0

SITE NAME:  
**WEST HARTFORD  
PARKING GARAGE**

SITE CASCADE:  
**CT03XC075**

SITE ADDRESS:  
**27-31 SOUTH MAIN ST  
WEST HARTFORD, CT 06110**

SHEET DESCRIPTION:  
**TOWER ELEVATION  
& CABLE PLAN**

SHEET NUMBER:  
**A-2**





**INFINIGY** Design. Build. Deliver.  
 1033 Watervliet Shaker Rd  
 Albany, NY 12205  
 Office # (518) 690-0790  
 Fax # (518) 690-0793  
**JOB NUMBER 353-000**



**DRAWING NOTICE:**  
 THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

**REVISIONS:**

NO.	DESCRIPTION	DATE	BY

ISSUED FOR CONSTRUCTION 3/17/14 MAP 0

**SITE NAME:**  
 WEST HARTFORD PARKING GARAGE

**SITE CASCADE:**  
 CT03XC075


**SITE ADDRESS:**  
 27-31 SOUTH MAIN ST  
 WEST HARTFORD, CT 06110

**SHEET DESCRIPTION:**  
 ANTENNA LAYOUT & MOUNTING DETAILS

**SHEET NUMBER:**  
 A-3


THE CONFIGURATION PLANS ARE BASED ON PROVIDED INFORMATION AND ARE FOR CONCEPTUAL PURPOSES ONLY. CONTRACTOR TO VERIFY FIELD CONDITIONS PRIOR TO CONSTRUCTION.

**NOTE:**  
 JUMPERS FROM 2.5 RRH TO THE 2.5 ANTENNA CANNOT EXCEED 15 FEET




**FINAL ANTENNA LAYOUT**

NO SCALE 2



**EXISTING ANTENNA & RRU LAYOUT**

NO SCALE 1



- NOTES:**
- CUT DC CONDUCTORS TO LENGTH.
  - COIL FIBER CABLE AND SECURE AT SIDE OF RRU.
  - DO NOT EXCEED BEND RADIUS.

**NOTE:**  
 CONTRACTOR TO POSITION RRU ON MOUNT BEHIND ANTENNA SUCH THAT THE RRU DOES NOT INTERFERE WITH THE EXISTING PLATFORM/T-ARM MOUNTING HARDWARE.

**NOTE:**  
 SPARE DC CABLES ARE COILED UP ON NV RRHS AT SPRINT ARRAY. THESE ARE TO BE USED TO POWER UP THE 2.5 RRHS AND TIED INTO EXISTING DC BREAKERS INSIDE THE FIBER JUNCTION BOX LOCATED AT EQUIPMENT.

**NOTE:**  
 THE DIAGRAM IS FOR CONCEPTUAL PURPOSES ONLY. CONTRACTOR IS TO REFER TO PASSING STRUCTURAL ANALYSIS FOR ANTENNA AND RRU MOUNTING DETAILS

**TYPICAL ANTENNA & RRU MOUNTING DETAILS**

NO SCALE 4

**DETAIL NOT USED**


NO SCALE 3

NV CABLES			
BAND	INDICATOR	PORT	COLOR
800-1	YEL GRN	NV-1	GRN
1900-1	YEL RED	NV-2	BLU
1900-2	YEL BRN	NV-3	BRN
1900-3	YEL BLU	NV-4	WHT
1900-4	YEL SLT	NV-5	RED
800-2	YEL ORG	NV-6	SLT
SPARE	YEL WHT	NV-7	PPL
2500	YEL PPL	NV-8	ORG

HYBRID	
HYBRID	COLOR
1	GRN
2	BLU
3	BRN
4	WHT
5	RED
6	SLT
7	PPL
8	ORG

2.5 Band		
2500 Radio 1	COLOR	
YEL WHT	GRN	
YEL WHT	BLU	
YEL WHT	BRN	
YEL WHT	WHT	
YEL WHT	RED	
YEL WHT	SLT	
YEL WHT	PPL	
YEL WHT	ORG	

Figure 1: Antenna Orientation






NOTES:

- ALL CABLES SHALL BE MARKED WITH 2" WIDE, UV STABILIZED, UL APPROVED TAPE.
- THE FIRST RING SHALL BE CLOSEST TO THE END OF THE CABLE AND SPACED APPROXIMATELY 2" FROM THE END CONNECTOR, WEATHERPROOFING, OR BREAK-OUT CYLINDER. THERE SHALL BE A 1" SPACE BETWEEN EACH RING FOR THE CABLE IDENTIFIER, AND NO SPACES BETWEEN THE FREQUENCY BANDS.
- A 2" GAP SHALL SEPARATE THE CABLE COLOR CODE FROM THE FREQUENCY COLOR CODE. THE 2" COLOR RINGS FOR THE FREQUENCY CODE SHALL BE PLACED NEXT TO EACH OTHER WITH NO SPACES.
- THE 2" COLORED TAPE(S) SHALL EACH BE WRAPPED A MINIMUM OF 3 TIMES AROUND THE INDIVIDUAL CABLES, AND THE TAPE SHALL BE KEPT IN THE SAME LOCATION AS MUCH AS POSSIBLE.
- SITES WITH MORE THAN FOUR (4) SECTORS WILL REQUIRE ADDITIONAL RINGS FOR EACH SECTOR, FOLLOWING THE PATTERN. HIGH CAPACITY SITES WILL USE THE NEXT COLOR IN THE SEQUENCE FOR ADDITIONAL CABLES IN EACH SECTOR.
- HYBRID FIBER CABLE SHALL BE SECTOR IDENTIFIED INSIDE THE CABINET ON FREQUENCY BUNDLES, ON THE SEALTITE, ON THE MAIN LINE UPON EXIT OF SEALTITE, AND BEFORE AND AFTER THE BREAKOUT UNIT (MEDUSA), AS WELL AS BEFORE AND AFTER ANY ENTRANCE OR EXIT.
- HFC "MAIN TRUNK" WILL NOT BE MARKED WITH THE FREQUENCY CODES, AS IT CONTAINS ALL FREQUENCIES.
- INDIVIDUAL POWER PAIRS AND FIBER BUNDLES SHALL BE LABELED WITH BOTH THE CABLE AND FREQUENCY.

Sector	Cable	First Ring	Second Ring	Third Ring
1 Alpha	1	Green	No Tape	No Tape
	2	Blue	No Tape	No Tape
	3	Brown	No Tape	No Tape
	4	White	No Tape	No Tape
	5	Red	No Tape	No Tape
	6	Grey	No Tape	No Tape
	7	Purple	No Tape	No Tape
	8	Orange	No Tape	No Tape
2 Beta	1	Green	Green	No Tape
	2	Blue	Blue	No Tape
	3	Brown	Brown	No Tape
	4	White	White	No Tape
	5	Red	Red	No Tape
	6	Grey	Grey	No Tape
	7	Purple	Purple	No Tape
	8	Orange	Orange	No Tape
3 Gamma	1	Green	Green	Green
	2	Blue	Blue	Blue
	3	Brown	Brown	Brown
	4	White	White	White
	5	Red	Red	Red
	6	Grey	Grey	Grey
	7	Purple	Purple	Purple
	8	Orange	Orange	Orange

NV FREQUENCY	INDICATOR	ID
800-1	YEL	GRN
1900-1	YEL	RED
1900-2	YEL	BRN
1900-3	YEL	BLU
1900-4	YEL	SLT
800-1	YEL	ORG
RESERVED	YEL	WHT
RESERVED	YEL	PPL

2.5 FREQUENCY	INDICATOR		ID
2500 -1	YEL	WHT	GRN
2500 -2	YEL	WHT	RED
2500 -3	YEL	WHT	BRN
2500 -4	YEL	WHT	BLU
2500 -5	YEL	WHT	SLT
2500 -6	YEL	WHT	ORG
2500 -7	YEL	WHT	WHT
2500 -8	YEL	WHT	PPL



PLANS PREPARED FOR:

6580 Sprint Parkway  
Overland Park, Kansas 66251

PLANS PREPARED BY:

Design. Build. Deliver.  
1033 Watervliet Shaker Rd  
Albany, NY 12205  
Office # (518) 690-0790  
Fax # (518) 690-0793  
JOB NUMBER 353-000

MLA PARTNER:

ENGINEERING LICENSE:

DRAWING NOTICE:  
THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

NO.	DESCRIPTION	DATE	BY

ISSUED FOR CONSTRUCTION 3/17/14 MAP 0

SITE NAME:  
WEST HARTFORD PARKING GARAGE

SITE CASCADE:  
CT03XC075


SITE ADDRESS:  
27-31 SOUTH MAIN ST  
WEST HARTFORD, CT 06110

SHEET DESCRIPTION:  
COLOR CODING AND NOTES


SHEET NUMBER:  
A-4

RRU: ALCATEL LUCENT TD-RRH8X20

COLOR: LIGHT GREY  
WEIGHT: 70 LBS.



**NOTES**  
COMPLY WITH MANUFACTURERS INSTRUCTIONS TO ENSURE THAT ALL RRU'S RECEIVE ELECTRICAL POWER WITHIN 24 HOURS OF BEING REMOVED FROM THE MANUFACTURER'S PACKAGING. DO NOT OPEN RRU PACKAGES IN THE RAIN.



2.5 RRU'S

NO SCALE

1


NEW EQUIPMENT IN EXISTING CABINET

NO SCALE

2

ANTENNA: RFS APXVTM14-C-I20

RADOME MATERIAL: ASA  
RADOME COLOR: LIGHT GRAY  
DIMENSIONS, HxWxD.in(mim): 56.3"x12.6"x6.3" (1430x320x160mm)  
WEIGHT: 52.9 lbs  
CONNECTORS: (8) 4.1/9.5 DIN FEMALE  
(1) NF - CALIBRATION CONNECTOR



2.5 ANTENNA

NO SCALE

3

DETAIL NOT USED

NO SCALE

4

PLANS PREPARED FOR:

6580 Sprint Parkway  
Overland Park, Kansas 66251

PLANS PREPARED BY:

Design. Build. Deliver.  
1033 Watervliet Shaker Rd  
Albany, NY 12205  
Office # (518) 690-0790  
Fax # (518) 690-0793  
JOB NUMBER 353-000

MILA PARTNER:

ENGINEERING LICENSE:

DRAWING NOTICE:  
THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

NO.	DESCRIPTION	DATE	BY	CHKD

ISSUED FOR CONSTRUCTION 3/17/14 MAP 0

SITE NAME:  
WEST HARTFORD PARKING GARAGE

SITE CASCADE:  
CT03XC075

SITE ADDRESS:  
27-31 SOUTH MAIN ST  
WEST HARTFORD, CT 06110

SHEET DESCRIPTION:  
EQUIPMENT & MOUNTING DETAILS

SHEET NUMBER:  
A-5


**RFS HYBRIFLEX RISER CABLE SCHEDULE**

Fiber Only (Existing DC Power)	Hybrid cable MN: HB058-M12-050F 12x multi-mode fiber pairs, Top: Outdoor protected connectors, Bottom: LC Connectors, 5/8 cable, 50 ft	50 ft
	MN: HB058-M12-075F	75 ft
	MN: HB058-M12-100F	100 ft
	MN: HB058-M12-125F	125 ft
	MN: HB058-M12-150F	150 ft
	MN: HB058-M12-175F	175 ft
	MN: HB058-M12-200F	200 ft
8 AWG Power	Hybrid cable MN: HB114-08U3M12-050F 3x 8 AWG power pairs, 12x multi-mode fiber pairs, Outdoor rated connectors & LC Connectors, 1 1/4 cable, 50 ft	50 ft
	MN: HB114-08U3M12-075F	75 ft
	MN: HB114-08U3M12-100F	100 ft
	MN: HB114-08U3M12-125F	125 ft
	MN: HB114-08U3M12-150F	150 ft
6 AWG Power	Hybrid cable MN: HB114-13U3M12-225F 3x 6 AWG power pair, 12x multi-mode fiber pairs, Outdoor rated connectors & LC Connectors, 1 1/4 cable, 225 ft	225 ft
	MN: HB114-13U3M12-250F	250 ft
	MN: HB114-13U3M12-275F	275 ft
4 AWG Power	Hybrid cable MN: HB114-21U3M12-325F 3x 4 AWG power pair, 12x multi-mode fiber pairs, Outdoor rated connectors & LC Connectors, 1 1/4 cable, 325 ft	325 ft
	MN: HB114-21U3M12-350F	350 ft
	MN: HB114-21U3M12-375F	375 ft


**RFS HYBRIFLEX JUMPER CABLE SCHEDULE**

Fiber Only	Hybrid Jumper cable MN: HBF012-M3-5F1 5 ft, 3x multi-mode fiber pairs, Outdoor & LC connectors, 1/2 cable	5 ft
	MN: HBF012-M3-10F1	10 ft
	MN: HBF012-M3-15F1	15 ft
	MN: HBF012-M3-20F1	20 ft
	MN: HBF012-M3-25F1	25 ft
	MN: HBF012-M3-30F1	30 ft
8 AWG Power	Hybrid Jumper cable MN: HBF058-08U1M3-5F1 5 ft, 1x 8 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 5/8 cable	5 ft
	MN: HBF058-08U1M3-10F1	10 ft
	MN: HBF058-08U1M3-15F1	15 ft
	MN: HBF058-08U1M3-20F1	20 ft
	MN: HBF058-08U1M3-25F1	25 ft
6 AWG Power	Hybrid Jumper cable MN: HBF058-13U1M3-5F1 5 ft, 1x 6 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 5/8 cable	5 ft
	MN: HBF058-13U1M3-10F1	10 ft
	MN: HBF058-13U1M3-15F1	15 ft
	MN: HBF058-13U1M3-20F1	20 ft
	MN: HBF058-13U1M3-25F1	25 ft
4 AWG Power	Hybrid Jumper cable MN: HBF078-21U1M3-5F1 5 ft, 1x 4 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 7/8 cable	5 ft
	MN: HBF078-21U1M3-10F1	10 ft
	MN: HBF078-21U1M3-15F1	15 ft
	MN: HBF078-21U1M3-20F1	20 ft
	MN: HBF078-21U1M3-25F1	25 ft
	MN: HBF078-21U1M3-30F1	30 ft


**NOTE:**  
SPRINT CM TO CONFIRM HYBRID OR FIBER RISER CABLE AND HYBRID OR FIBER JUMPER CABLE MODEL NUMBERS IF HYBRID CABLES ARE REQUIRED BEFORE PREPARING BOM.




**4 AWG**



**8 & 6 AWG**



**FIBER ONLY**



**FIBER JUNCTION BOX PENETRATION**

NO SCALE

2

**2.5 CABLE CROSS SECTION DATA**

NO SCALE

3

**DETAIL NOT USED**

NO SCALE

3

PLANS PREPARED FOR:



PLANS PREPARED BY:



1033 Watervliet Shaker Rd  
Albany, NY 12205  
Office # (518) 690-0790  
Fax # (518) 690-0793

JOB NUMBER 353-000

MLA PARTNER:



ENGINEERING LICENSE:



DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

ISSUED FOR CONSTRUCTION	3/17/14	MAP	0

SITE NAME:

**WEST HARTFORD  
PARKING GARAGE**

SITE CASCADE:

**CT03XC075**

SITE ADDRESS:

27-31 SOUTH MAIN ST  
WEST HARTFORD, CT 06110

SHEET DESCRIPTION:

**CIVIL DETAILS**

SHEET NUMBER:

**A-6**

DRAWING NOTICE:  
 THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:



SITE NAME:  
**WEST HARTFORD PARKING GARAGE**

SITE CASCADE:  
**CT03XC075**


SITE ADDRESS:  
 27-31 SOUTH MAIN ST  
 WEST HARTFORD, CT 06110

SHEET DESCRIPTION:  
**PLUMBING DIAGRAM**


SHEET NUMBER:  
**A-7**



**ALU 2.5 ALU SCENARIO 1**



**RAN WIRING DIAGRAM**





**RF 2.5 ALU SCENARIO 1**

PLAN NOT USED

NO SCALE

1

- LEGEND:**
- G — EXISTING GROUND RING
  - CADWELD CONNECTION (EXOTHERMIC WELD)
  - ▲ MECHANICAL CONNECTION
  - ⊗ GROUND ROD
  - CABLE GROUND KIT



NOTE:  
DEPICTION IS FOR CONCEPTUAL PURPOSES ONLY. CONTRACTOR IS TO FIELD VERIFY PRIOR TO CONSTRUCTION

DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

NO.	DESCRIPTION	DATE

ISSUED FOR CONSTRUCTION 3/17/14 MAP 0

SITE NAME:

WEST HARTFORD PARKING GARAGE

SITE CASCADE:

CT03XC075

SITE ADDRESS:

27-31 SOUTH MAIN ST  
WEST HARTFORD, CT 06110

SHEET DESCRIPTION:

ELECTRICAL & GROUNDING PLAN

SHEET NUMBER:

E-1

TYPICAL ANTENNA GROUNDING PLAN

NO SCALE

2

TYPICAL EQUIPMENT GROUNDING PLAN (ELEVATION)

NO SCALE

3



**INFINIGY** Design. Build. Deliver.  
 1033 Watervliet Shaker Rd  
 Albany, NY 12205  
 Office # (518) 690-0790  
 Fax # (518) 690-0793  
 JOB NUMBER 353-000



THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

NO.	DESCRIPTION	DATE

ISSUED FOR CONSTRUCTION 3/17/14 MAP 0

**WEST HARTFORD PARKING GARAGE**


**CT03XC075**

27-31 SOUTH MAIN ST  
 WEST HARTFORD, CT 06110

**ELECTRICAL & GROUNDING DETAILS**

**E-2**


**NOTES**  
 CG SHALL REFERENCE ALL SPECS FOR "CONNECTING THE POWER SUPPLY" OF THE NEW INSTALLATION DOCUMENTS, FOR ALL CONNECTION SPECIFICATIONS.



CIRCUIT SCHEDULE			
NO	FROM	TO	CONFIGURATION
①	UTILITY SOURCE	METER/DISCONNECT	EXISTING
②	METER/DISCONNECT	TRANSFER & LOAD CENTER	EXISTING
③	TRANSFER & LOAD CENTER	GENERATOR RECEPTACLE	EXISTING
④	TRANSFER & LOAD CENTER	EXISTING SPRINT BBU CABINET	EXISTING
⑤	TRANSFER & LOAD CENTER	EXISTING SPRINT MMBS CABINET	EXISTING

**ELECTRICAL ONE-LINE DIAGRAM**


NO SCALE 1



- NOTES**
1. APPLY NO-OX TO LUG AND BAR CONTACT SURFACE. DO NOT COAT INLINE LUG.
  2. IF STOLEN GROUND BARS ARE ENCOUNTERED, CONTACT SPRINT CM FOR REPLACEMENT THREADED ROD KIT.


**INSTALLATION OF GROUNDING CONDUCTOR TO GROUNDING BAR**

NO SCALE 2



**TWO HOLE LUG**

NO SCALE 3



**GROUNDING RISER DIAGRAM**

NO SCALE 4

Date: **March 7<sup>th</sup>, 2014**

Cheryl Schultz  
Crown Castle  
3530 Toringdon Way Suite 300  
Charlotte, NC 28277  
(704) 405-6632



GPD Group  
520 South Main Street, Suite 2531  
Akron, OH 44311  
(614) 859-1607  
dpalkovic@gpdgroup.com

**Subject: Structural Analysis Report**

**Carrier Designation:** **Sprint PCS Co-Locate** Scenario 2.5 B  
**Carrier Site Number:** CT03XC075  
**Carrier Site Name:** West Hartford Parking Garage

**Crown Castle Designation:** **Crown Castle BU Number:** 876328  
**Crown Castle Site Name:** West Hartford Parking Garage  
**Crown Castle JDE Job Number:** 251934  
**Crown Castle Work Order Number:** 696196  
**Crown Castle Application Number:** 205590 Rev. 2

**Engineering Firm Designation:** **GPD Group Project Number:** 2014777.876328.01

**Site Data:** **27-31 South Main St., West Hartford, Hartford County, CT 06110**  
**Latitude 41° 45' 36.41", Longitude -72° 44' 35.25"**  
**40.25 Foot – Rohn Self Support Tower**

Dear Ms. Cheryl Schultz,

GPD Group is pleased to submit this **"Structural Analysis Report"** to determine the structural integrity of the above mentioned tower. This analysis has been performed in accordance with the Crown Castle Structural 'Statement of Work' and the terms of Crown Castle Purchase Order Number 607348, in accordance with application 205590, revision 2.

The purpose of the analysis is to determine acceptability of the tower stress level. Based on our analysis we have determined the tower stress level for the structure and foundation, under the following load case, to be:

LC5: Existing + Proposed Equipment **Sufficient Capacity**  
Note: See Table I and Table II for the proposed and existing/reserved loading, respectively.

The analysis has been performed in accordance with the TIA/EIA-222-F standard and the 2005 Connecticut State Building Code based upon a wind speed of 80 mph fastest mile.

We at GPD Group appreciate the opportunity of providing our continuing professional services to you and Crown Castle. If you have any questions or need further assistance on this or any other projects please give us a call.

Respectfully submitted by:

John N. Kabak, P.E.  
Connecticut #: PEN.0028336

03/07/2014



## TABLE OF CONTENTS

### 1) INTRODUCTION

### 2) ANALYSIS CRITERIA

Table 1 - Proposed Antenna and Cable Information

Table 2 - Existing and Reserved Antenna and Cable Information

Table 3 - Design Antenna and Cable Information

### 3) ANALYSIS PROCEDURE

Table 4 - Documents Provided

3.1) Analysis Method

3.2) Assumptions

### 4) ANALYSIS RESULTS

Table 5 - Section Capacity (Summary)

Table 6 – Tower Components vs. Capacity

4.1) Recommendations

### 5) APPENDIX A

tnxTower Output

### 6) APPENDIX B

Base Level Drawing

### 7) APPENDIX C

Additional Calculations

## 1) INTRODUCTION

The tower is supported on three legs and has eight two sections. It has a triangular cross section made of bolted connections, with an "X" frame configuration. The tower is fabricated with pipe round legs, angle diagonals. The tower is galvanized and has no tower lightning.

This tower is a 40 ft Self Support tower designed by ROHN in April of 1997. The tower was originally designed for a wind speed of 85 mph per TIA/EIA-222-E.

## 2) ANALYSIS CRITERIA

The structural analysis was performed for this tower in accordance with the requirements of TIA/EIA-222-F Structural Standards for Steel Antenna Towers and Antenna Supporting Structures using a fastest mile wind speed of 80 mph with no ice, 38 mph with 1 inch ice thickness (in accordance with ASCE 7 Ice conditions) and 50 mph under service loads.

**Table 1 - Proposed Antenna and Cable Information**

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)	Note
102.0	103.0	3	Alcatel lucent	TD-RRH8x20-25	1	5/8	1
		3	RFS Celwave	APXVTM14-C-120			

Notes:

- 1) See Appendix B for the proposed coax layout.

**Table 2 - Existing and Reserved Antenna and Cable Information**

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)	Note
102.0	103.0	1	RFS Celwave	APXV9ERR18-C-A20	3	1-1/4	
		2	RFS Celwave	APXVSPP18-C-A20			
		1	Alcatel Lucent	800MHz 2X50W RRH W/FILTER			
		2	Alcatel Lucent	1900MHz RRH (65MHz)			
	102.0	1	Alcatel Lucent	1900MHz RRH (65MHz)			
		2	Alcatel Lucent	800MHz 2X50W RRH W/FILTER			
		1		Sector Mount [SM 502-3]			
92.0	92.0	1		T-Arm Mount [TA 702-3]	6 2	1-5/8 3/4	
		3	Ericsson	RRUS-11			
		12	Powerwave Technologies	LGP2140X			
	89.0	3	Powerwave Technologies	7770.00			
		1	Andrew	SBNH-1D6565C			
		1	Powerwave Technologies	P65-15-XLH-RR			
		1	Powerwave Technologies	P65E-17-XLH-RR			
75.0	77.0	1	Lucent	KS24019-L112A	1	1/2	
	75.0	1		Side Arm Mount [SO 302-1]			

**Table 3 - Design Antenna and Cable Information**

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)
105	105	12		DB980H90	12	1-5/8
		3		Leg Mounting Frame		
75	75	1		GPS Antenna	1	1-5/8
		1		3' Side Arm		

### 3) ANALYSIS PROCEDURE

**Table 4 - Documents Provided**

Document	Remarks	Reference	Source
Tower Manufacturer Drawings	Rohn Eng. File#: 345895W, dated: 4/15/1997	Doc ID#: 1440544	Crown DMZ
Tower Mapping Report	GPD Project #: 2014777.876328.03, dated: 03/04/2014	D. Palkovic	GPD

#### 3.1) Analysis Method

tnxTower (version 6.1.3.1), a commercially available analysis software package, was used to create a three-dimensional model of the tower and calculate member stresses for various loading cases. Selected output from the analysis is included in Appendix A.

#### 3.2) Assumptions

- 1) Tower and structures were built in accordance with the manufacturer's specifications.
- 2) The tower and structures have been maintained in accordance with the manufacturer's specification.
- 3) The configuration of antennas, transmission cables, mounts and other appurtenances are as specified in Tables 1 and 2 and the referenced drawings.
- 4) When applicable, transmission cables are considered as structural components for calculating wind loads as allowed by TIA/EIA-222-F.
- 5) Mount sizes, weights, and manufacturers are best estimates based on site photos provided and were determined without the benefit of a site visit by GPD.
- 6) All member connections and foundation steel reinforcing are assumed designed to meet or exceed the load carrying capacity of the connected member and surrounding soils respectively unless otherwise specified in this report.
- 7) The capacity of the rooftop was not evaluated in this analysis.
- 8) All equipment model numbers, quantities, and centerline elevations are as provided in the CCI CAD package dated 01/02/2014 with any adjustments as noted below.

This analysis may be affected if any assumptions are not valid or have been made in error. GPD Group should be notified to determine the effect on the structural integrity of the tower.

#### 4) ANALYSIS RESULTS

**Table 5 - Section Capacity (Summary)**

Section No.	Elevation (ft)	Component Type	Size	Critical Element	P (K)	SF*P <sub>allow</sub> (K)	% Capacity	Pass / Fail
T1	105.25 - 85.125	Leg	ROHN 2.5 STD	2	-13.64	54.96	24.8	Pass
T2	85.125 - 65	Leg	ROHN 2.5 STD	38	-35.90	50.20	71.5	Pass
T1	105.25 - 85.125	Diagonal	L1 1/2x1 1/2x1/8	8	-2.65	3.35	79.0 94.3 (b)	Pass
T2	85.125 - 65	Diagonal	L1 3/4x1 3/4x3/16	46	-2.76	4.49	61.6	Pass
T1	105.25 - 85.125	Top Girt	L2x2x1/8	5	-0.30	2.83	10.7	Pass
T2	85.125 - 65	Top Girt	L2x2x1/8	41	-0.12	3.60	3.4	Pass
							Summary	
						Leg (T2)	71.5	Pass
						Diagonal (T1)	94.3	Pass
						Top Girt (T1)	10.7	Pass
						Bolt Checks	94.3	Pass
						Rating =	94.3	Pass

**Table 6 - Tower Component Stresses vs. Capacity – LC5**

Notes	Component	Elevation (ft)	% Capacity	Pass / Fail
-	Anchor Bolts	65	54.3	Pass
1	Base I-Beam Frame	65	67.3	Pass

<b>Structure Rating (max from all components) =</b>	<b>94.3%</b>
---	--------------

Notes:

- 1) See additional documentation in "Appendix C – Additional Calculations" for calculations supporting the % capacity consumed.

#### 4.1) Recommendations

The design of the tower and its foundations are sufficient for the proposed loading and does not require modifications.

## 5) DISCLAIMER OF WARRANTIES

GPD GROUP has not performed a site visit to the tower to verify the member sizes or antenna/coax loading. If the existing conditions are not as represented on the tower elevation contained in this report, we should be contacted immediately to evaluate the significance of the discrepancy. This is not a condition assessment of the tower or foundation. This report does not replace a full tower inspection. The tower and foundations are assumed to have been properly fabricated, erected, maintained, in good condition, twist free, and plumb.

The engineering services rendered by GPD GROUP in connection with this Structural Analysis are limited to a computer analysis of the tower structure and theoretical capacity of its main structural members. All tower components have been assumed to only resist dead loads when no other loads are applied. No allowance was made for any damaged, bent, missing, loose, or rusted members (above and below ground). No allowance was made for loose bolts or cracked welds.

GPD GROUP does not analyze the fabrication of the structure (including welding). It is not possible to have all the very detailed information needed to perform a thorough analysis of every structural sub-component and connection of an existing tower. GPD GROUP provides a limited scope of service in that we cannot verify the adequacy of every weld, plate connection detail, etc. The purpose of this report is to assess the feasibility of adding appurtenances usually accompanied by transmission lines to the structure.

It is the owner's responsibility to determine the amount of ice accumulation in excess of the code specified amount, if any, that should be considered in the structural analysis.

The attached sketches are a schematic representation of the analyzed tower. If any material is fabricated from these sketches, the contractor shall be responsible for field verifying the existing conditions, proper fit, and clearance in the field. Any mentions of structural modifications are reasonable estimates and should not be used as a precise construction document. Precise modification drawings are obtainable from GPD GROUP, but are beyond the scope of this report.


Miscellaneous items such as antenna mounts, etc., have not been designed or detailed as a part of our work. We recommend that material of adequate size and strength be purchased from a reputable tower manufacturer.

Towers are designed to carry gravity, wind, and ice loads. All members, legs, diagonals, struts, and redundant members provide structural stability to the tower with little redundancy. Absence or removal of a member can trigger catastrophic failure unless a substitute is provided before any removal. Legs carry axial loads and derive their strength from shorter unbraced lengths by the presence of redundant members and their connection to the diagonals with bolts or welds. If the bolts or welds are removed without providing any substitute to the frame, the leg is subjected to a higher unbraced length that immediately reduces its load carrying capacity. If a diagonal is also removed in addition to the connection, the unbraced length of the leg is greatly increased, jeopardizing its load carrying capacity. Failure of one leg can result in a tower collapse because there is no redundancy. Redundant members and diagonals are critical to the stability of the tower.

GPD GROUP makes no warranties, expressed and/or implied, in connection with this report and disclaims any liability arising from material, fabrication, and erection of this tower. GPD GROUP will not be responsible whatsoever for, or on account of, consequential or incidental damages sustained by any person, firm, or organization as a result of any data or conclusions contained in this report. The maximum liability of GPD GROUP pursuant to this report will be limited to the total fee received for preparation of this report.

**APPENDIX A**  
**TNXTOWER OUTPUT**

Section	T1	105.3 ft
Legs	ROHN 2.5 STD	
Leg Grade	A572-50	
Diagonals	L1 1/2x1 1/2x1/8	
Diagonal Grade	A36	
Top Chits	L2x2x1/8	
Face Width (ft)	8.5625	
# Panels @ (ft)	5 @ 4.025	0.7
Weight (K)	1.5	
		65.0 ft
		85.1 ft
		0.8
		4 @ 5.01042
		L1 3/4x1 3/4x3/16
		A36
		A572-50
		ROHN 2.5 STD
	T2	



**DESIGNED APPURTENANCE LOADING**

TYPE	ELEVATION	TYPE	ELEVATION
Sector Mount [SM 502-3]	102	7x2 1/2" Pipe Mount	102
APXVSPP18-C-A20 w/ Mount Pipe	102	7x2 1/2" Pipe Mount	102
APXVSPP18-C-A20 w/ Mount Pipe	102	T-Arm Mount [TA 702-3]	92
APXV9ERR18-C-A20 w/ Mount Pipe	102	7770.00 w/ Mount Pipe	92
1900MHz RRH (65MHz)	102	7770.00 w/ Mount Pipe	92
1900MHz RRH (65MHz)	102	7770.00 w/ Mount Pipe	92
1900MHz RRH (65MHz)	102	P65-15-XLH-RR w/ Mount Pipe	92
800MHz 2X50W RRH W/FILTER	102	SBNH-1D6565C w/ Mount Pipe	92
800MHz 2X50W RRH W/FILTER	102	P65E-17-XLH-RR w/ Mount Pipe	92
800MHz 2X50W RRH W/FILTER	102	(4) LGP2140X	92
APXVTM14-C-120 w/ Mount Pipe	102	(4) LGP2140X	92
APXVTM14-C-120 w/ Mount Pipe	102	(4) LGP2140X	92
APXVTM14-C-120 w/ Mount Pipe	102	RRUS-11	92
TD-RRH8x20-25	102	RRUS-11	92
TD-RRH8x20-25	102	RRUS-11	92
TD-RRH8x20-25	102	Side Arm Mount [SO 302-1]	75
7x2 1/2" Pipe Mount	102	KS24019-L112A	75

**MATERIAL STRENGTH**

GRADE	Fy	Fu	GRADE	Fy	Fu
A572-50	50 ksi	65 ksi	A36	36 ksi	58 ksi


**TOWER DESIGN NOTES**

1. Tower is located in Hartford County, Connecticut.
2. Tower designed for a 80 mph basic wind in accordance with the TIA/EIA-222-F Standard.
3. Tower is also designed for a 38 mph basic wind with 1.00 in ice. Ice is considered to increase in thickness with height.
4. Deflections are based upon a 50 mph wind.
5. TOWER RATING: 94.3%


**MAX. CORNER REACTIONS AT BASE:**

DOWN: 36 K  
SHEAR: 5 K

UPLIFT: -30 K  
SHEAR: 5 K




TORQUE 4 kip-ft  
REACTIONS - 80 mph WIND

 <p><b>GPD Group</b> 520 S. Main St. Akron, OH 44311 Phone: (330) 572-2100 FAX: (330) 572-2102</p>	<p>Job: <b>WEST HARTFORD PARKING GARAGE - BU#: 876328</b></p>
	<p>Project: <b>2014777.876328.01</b></p>
	<p>Client: Crown Castle USA, Inc. Drawn by: MSaid App'd:</p>
	<p>Code: TIA/EIA-222-F Date: 03/07/14 Scale: NTS</p>
<p>Path: T:\Crown\876328\01\TX\876328.eri Dwg No. E-1</p>	



# Feed Line Distribution Chart 65' - 105'3"

— Round   
 — Flat   
 — App In Face   
 — App Out Face   
 — Truss Leg



 <b>GPD Group</b> 520 S. Main St. Akron, OH 44311 Phone: (330) 572-2100 FAX: (330) 572-2102 Consulting Engineers	<b>Job: WEST HARTFORD PARKING GARAGE - BU#: 876328</b>		
	Project: <b>2014777.876328.01</b>		
	Client: Crown Castle USA, Inc.	Drawn by: MSaid	App'd:
	Code: TIA/EIA-222-F	Date: 03/07/14	Scale: NTS
	Path: T:\Crown\876328\01\TNX\876328.eri		Dwg No. E-7

## Tower Input Data

The main tower is a 3x free standing tower with an overall height of 105.25 ft above the ground line.

The base of the tower is set at an elevation of 65.00 ft above the ground line.

The face width of the tower is 6.56 ft at the top and 8.56 ft at the base.

This tower is designed using the TIA/EIA-222-F standard.

The following design criteria apply:

Tower is located in Hartford County, Connecticut.

Basic wind speed of 80 mph.

Nominal ice thickness of 1.0000 in.

Ice thickness is considered to increase with height.

Ice density of 56 pcf.

A wind speed of 38 mph is used in combination with ice.

Temperature drop of 50 °F.

Deflections calculated using a wind speed of 50 mph.


Pressures are calculated at each section.

Stress ratio used in tower member design is 1.333.

Local bending stresses due to climbing loads, feed line supports, and appurtenance mounts are not considered.

## Options

<ul style="list-style-type: none"> <li>Consider Moments - Legs</li> <li>Consider Moments - Horizontals</li> <li>Consider Moments - Diagonals</li> <li>Use Moment Magnification</li> <li>√ Use Code Stress Ratios</li> <li>√ Use Code Safety Factors - Guys</li> <li>√ Escalate Ice</li> <li>Always Use Max Kz</li> <li>Use Special Wind Profile</li> <li>√ Include Bolts In Member Capacity</li> <li>Leg Bolts Are At Top Of Section</li> <li>√ Secondary Horizontal Braces Leg</li> <li>Use Diamond Inner Bracing (4 Sided)</li> <li>Add IBC .6D+W Combination</li> </ul>	<ul style="list-style-type: none"> <li>Distribute Leg Loads As Uniform</li> <li>Assume Legs Pinned</li> <li>√ Assume Rigid Index Plate</li> <li>√ Use Clear Spans For Wind Area</li> <li>√ Use Clear Spans For KL/r</li> <li>Retention Guys To Initial Tension</li> <li>√ Bypass Mast Stability Checks</li> <li>√ Use Azimuth Dish Coefficients</li> <li>√ Project Wind Area of Appurt.</li> <li>Autocalc Torque Arm Areas</li> <li>√ SR Members Have Cut Ends</li> <li>√ Sort Capacity Reports By Component</li> <li>Triangulate Diamond Inner Bracing</li> <li>Use TIA-222-G Tension Splice Capacity</li> <li>Exemption</li> </ul>	<ul style="list-style-type: none"> <li>Treat Feedline Bundles As Cylinder</li> <li>Use ASCE 10 X-Brace Ly Rules</li> <li>√ Calculate Redundant Bracing Forces</li> <li>Ignore Redundant Members in FEA</li> <li>SR Leg Bolts Resist Compression</li> <li>√ All Leg Panels Have Same Allowable</li> <li>√ Offset Girt At Foundation</li> <li>√ Consider Feedline Torque</li> <li>√ Include Angle Block Shear Check</li> </ul>
		Poles
		<ul style="list-style-type: none"> <li>Include Shear-Torsion Interaction</li> <li>Always Use Sub-Critical Flow</li> <li>Use Top Mounted Sockets</li> </ul>



**Triangular Tower**

**Tower Section Geometry**

Tower Section	Tower Elevation	Assembly Database	Description	Section Width	Number of Sections	Section Length
	ft			ft		ft
T1	105.25-85.13			6.56	1	20.13
T2	85.13-65.00			6.56	1	20.13

**Tower Section Geometry (cont'd)**

Tower Section	Tower Elevation	Diagonal Spacing	Bracing Type	Has K Brace End Panels	Has Horizontals	Top Girt Offset	Bottom Girt Offset
	ft	ft				in	in
T1	105.25-85.13	4.03	X Brace	No	No	0.0000	0.0000
T2	85.13-65.00	5.01	X Brace	No	No	0.0000	1.0000

**Tower Section Geometry (cont'd)**

Tower Elevation	Leg Type	Leg Size	Leg Grade	Diagonal Type	Diagonal Size	Diagonal Grade
ft						
T1 105.25-85.13	Pipe	ROHN 2.5 STD	A572-50 (50 ksi)	Equal Angle	L1 1/2x1 1/2x1/8	A36 (36 ksi)
T2 85.13-65.00	Pipe	ROHN 2.5 STD	A572-50 (50 ksi)	Equal Angle	L1 3/4x1 3/4x3/16	A36 (36 ksi)

### Tower Section Geometry (cont'd)

Tower Elevation ft	Top Girt Type	Top Girt Size	Top Girt Grade	Bottom Girt Type	Bottom Girt Size	Bottom Girt Grade
T1 105.25-85.13	Equal Angle	L2x2x1/8	A36 (36 ksi)	Solid Round		A36 (36 ksi)
T2 85.13-65.00	Equal Angle	L2x2x1/8	A36 (36 ksi)	Solid Round		A36 (36 ksi)

### Tower Section Geometry (cont'd)

Tower Elevation ft	Gusset Area (per face) ft <sup>2</sup>	Gusset Thickness in	Gusset Grade	Adjust. Factor A <sub>f</sub>	Adjust. Factor A <sub>r</sub>	Weight Mult.	Double Angle Stitch Bolt Spacing Diagonals in	Double Angle Stitch Bolt Spacing Horizontal in
T1 105.25-85.13	0.00	0.0000	A36 (36 ksi)	1	1	1	36.0000	36.0000
T2 85.13-65.00	0.00	0.0000	A36 (36 ksi)	1	1	1	36.0000	36.0000

### Tower Section Geometry (cont'd)

Tower Elevation ft	Calc K Single Angles	Calc K Solid Rounds	K Factors <sup>1</sup>								
			Legs	X Brace Diags	K Brace Diags	Single Diags	Girts	Horiz.	Sec. Horiz.	Inner Brace	
T1 105.25-85.13	Yes	No	1	1 1	1 1	1 1	1 1	1 1	1 1	1 1	1 1
T2 85.13-65.00	Yes	No	1	1 1	1 1	1 1	1 1	1 1	1 1	1 1	1 1

<sup>1</sup>Note: K factors are applied to member segment lengths. K-braces without inner supporting members will have the K factor in the out-of-plane direction applied to the overall length.

### Tower Section Geometry (cont'd)

Tower Elevation ft	Leg		Diagonal		Top Girt		Bottom Girt		Mid Girt		Long Horizontal		Short Horizontal	
	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U
T1 105.25-85.13	0.0000	1	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75
T2 85.13-65.00	0.0000	1	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75

### Tower Section Geometry (cont'd)

Tower Elevation ft	Leg Connection Type	Leg		Diagonal		Top Girt		Bottom Girt		Mid Girt		Long Horizontal		Short Horizontal	
		Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.
T1 105.25-85.13	Flange	0.6250 A325N	4	0.5000 A325N	1	0.5000 A325N	1	0.6250 A325N	0	0.6250 A325N	0	0.6250 A325N	0	0.6250 A325N	0
T2 85.13-65.00	Flange	0.6250 A325N	4	0.5000 A325N	1	0.6250 A325N	0	0.6250 A325N	0	0.6250 A325N	0	0.6250 A325N	0	0.6250 A325N	0

### Feed Line/Linear Appurtenances - Entered As Round Or Flat

Description	Face or Leg	Allow Shield	Component Type	Placement  ft	Face Offset in	Lateral Offset (Frac FW)	#	# Per Row	Clear Spacing in	Width or Diameter in	Perimeter in	Weight plf
HB114-1-08U4-M5J(1 1/4")	B	Yes	Ar (CfAe)	102.00 - 65.00	0.0000	0	3	3	0.7500	1.5400		1.08
HB058-M12-XXXF(5/8")	B	Yes	Ar (CfAe)	102.00 - 65.00	0.0000	0	1	1	0.7500	0.8400		0.24
LDF4-50A(1/2")	B	Yes	Ar (CfAe)	102.00 - 65.00	0.0000	0	1	1	0.5000	0.6300		0.15
Feedline Ladder (Af)	B	Yes	Af (CfAe)	85.00 - 65.00	0.0000	0.4	1	1	3.0000	3.0000	12.0000	8.40
LDF7-50A(1-5/8")	B	Yes	Ar (CfAe)	92.00 - 65.00	0.0000	0.4	6	6	0.7500	1.9800		0.82
WR-VG86ST-BRD( 3/4)	B	Yes	Ar (CfAe)	92.00 - 65.00	0.0000	0.4	2	2	0.5000	0.0000		0.58
Feedline Ladder (Af)	B	Yes	Af (CfAe)	105.00 - 65.00	0.0000	0	1	1	3.0000	3.0000	12.0000	8.40
Climbing Ladder (CCI)	B	No	Af (Leg)	105.00 - 65.00	0.0000	0.25	1	1	3.8400	3.8400	15.3600	4.81
Safety Line (3/8")	B	No	Ar (Leg)	105.00 - 65.00	0.0000	0.25	1	1	0.3750	0.3750		0.22

### Feed Line/Linear Appurtenances Section Areas

Tower Section	Tower Elevation ft	Face	A <sub>R</sub> ft <sup>2</sup>	A <sub>F</sub> ft <sup>2</sup>	C <sub>AA</sub> In Face ft <sup>2</sup>	C <sub>AA</sub> Out Face ft <sup>2</sup>	Weight K
T1	105.25-85.13	A	0.000	0.000	0.000	0.000	0.00
		B	15.991	11.329	0.000	0.000	0.37
		C	0.621	6.360	0.000	0.000	0.00
T2	85.13-65.00	A	0.000	0.000	0.000	0.000	0.00
		B	30.766	16.471	0.000	0.000	0.63
		C	0.629	6.440	0.000	0.000	0.00

### Feed Line/Linear Appurtenances Section Areas - With Ice

Tower Section	Tower Elevation ft	Face or Leg	Ice Thickness in	A <sub>R</sub> ft <sup>2</sup>	A <sub>F</sub> ft <sup>2</sup>	C <sub>AA</sub> In Face ft <sup>2</sup>	C <sub>AA</sub> Out Face ft <sup>2</sup>	Weight K
T1	105.25-85.13	A	1.136	0.000	0.000	0.000	0.000	0.00
		B		21.933	30.892	0.000	0.000	1.13
		C		4.383	8.868	0.000	0.000	0.00
T2	85.13-65.00	A	1.104	0.000	0.000	0.000	0.000	0.00
		B		31.208	55.271	0.000	0.000	1.85
		C		4.331	8.908	0.000	0.000	0.00

### Feed Line Shielding

Section	Elevation ft	Face	A <sub>R</sub> ft <sup>2</sup>	A <sub>R</sub> Ice ft <sup>2</sup>	A <sub>F</sub> ft <sup>2</sup>	A <sub>F</sub> Ice ft <sup>2</sup>
T1	105.25-85.13	A	0.000	0.000	0.000	0.000
		B	0.000	4.888	1.650	3.313
		C	0.000	0.000	0.000	0.000
T2	85.13-65.00	A	0.000	0.000	0.000	0.000
		B	0.000	7.347	3.133	5.904
		C	0.000	0.000	0.000	0.000

### Feed Line Center of Pressure

Section	Elevation ft	CP <sub>X</sub> in	CP <sub>Z</sub> in	CP <sub>X</sub> Ice in	CP <sub>Z</sub> Ice in
T1	105.25-85.13	6.8949	0.4212	4.5179	0.3427
T2	85.13-65.00	12.9103	2.8331	8.3296	1.6621

## Discrete Tower Loads

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment °	Placement ft		C <sub>AA</sub> Front ft <sup>2</sup>	C <sub>AA</sub> Side ft <sup>2</sup>	Weight K
Sector Mount [SM 502-3]	C	None		0.0000	102.00	No Ice	33.02	33.02	1.67
						1/2" Ice	47.36	47.36	2.22
						1" Ice	61.70	61.70	2.77
						2" Ice	90.38	90.38	3.88
						4" Ice	147.74	147.74	6.08
APXVSPP18-C-A20 w/ Mount Pipe	A	From Leg	4.00	0.0000	102.00	No Ice	8.26	6.71	0.08
			0.00			1/2" Ice	8.81	7.66	0.14
			1.00			1" Ice	9.36	8.49	0.22
						2" Ice	10.50	10.20	0.39
						4" Ice	12.88	13.98	0.87
APXVSPP18-C-A20 w/ Mount Pipe	B	From Leg	4.00	0.0000	102.00	No Ice	8.26	6.71	0.08
			0.00			1/2" Ice	8.81	7.66	0.14
			1.00			1" Ice	9.36	8.49	0.22
						2" Ice	10.50	10.20	0.39
						4" Ice	12.88	13.98	0.87
APXV9ERR18-C-A20 w/ Mount Pipe	C	From Leg	4.00	0.0000	102.00	No Ice	8.73	7.18	0.08
			0.00			1/2" Ice	9.49	8.46	0.15
			1.00			1" Ice	10.21	9.60	0.23
						2" Ice	11.60	11.53	0.41
						4" Ice	14.51	15.77	0.94
1900MHz RRH (65MHz)	A	From Leg	4.00	0.0000	102.00	No Ice	2.70	2.77	0.06
			0.00			1/2" Ice	2.94	3.01	0.08
			1.00			1" Ice	3.18	3.26	0.11
						2" Ice	3.70	3.78	0.18
						4" Ice	4.85	4.93	0.35
1900MHz RRH (65MHz)	B	From Leg	4.00	0.0000	102.00	No Ice	2.70	2.77	0.06
			0.00			1/2" Ice	2.94	3.01	0.08
			1.00			1" Ice	3.18	3.26	0.11
						2" Ice	3.70	3.78	0.18
						4" Ice	4.85	4.93	0.35
1900MHz RRH (65MHz)	C	From Leg	4.00	0.0000	102.00	No Ice	2.70	2.77	0.06
			0.00			1/2" Ice	2.94	3.01	0.08
			0.00			1" Ice	3.18	3.26	0.11
						2" Ice	3.70	3.78	0.18
						4" Ice	4.85	4.93	0.35
800MHz 2X50W RRH W/FILTER	A	From Leg	4.00	0.0000	102.00	No Ice	2.40	2.25	0.06
			0.00			1/2" Ice	2.61	2.46	0.09
			0.00			1" Ice	2.83	2.68	0.11
						2" Ice	3.30	3.13	0.17
						4" Ice	4.34	4.15	0.34
800MHz 2X50W RRH W/FILTER	B	From Leg	4.00	0.0000	102.00	No Ice	2.40	2.25	0.06
			0.00			1/2" Ice	2.61	2.46	0.09
			0.00			1" Ice	2.83	2.68	0.11
						2" Ice	3.30	3.13	0.17
						4" Ice	4.34	4.15	0.34
800MHz 2X50W RRH W/FILTER	C	From Leg	4.00	0.0000	102.00	No Ice	2.40	2.25	0.06
			0.00			1/2" Ice	2.61	2.46	0.09
			1.00			1" Ice	2.83	2.68	0.11
						2" Ice	3.30	3.13	0.17
						4" Ice	4.34	4.15	0.34
APXVTM14-C-120 w/ Mount Pipe	A	From Leg	4.00	0.0000	102.00	No Ice	7.13	4.96	0.08
			0.00			1/2" Ice	7.66	5.75	0.13
			1.00			1" Ice	8.18	6.47	0.19
						2" Ice	9.26	8.01	0.34
						4" Ice	11.53	11.41	0.75
APXVTM14-C-120 w/ Mount Pipe	B	From Leg	4.00	0.0000	102.00	No Ice	7.13	4.96	0.08
			0.00			1/2" Ice	7.66	5.75	0.13
			1.00			1" Ice	8.18	6.47	0.19
						2" Ice	9.26	8.01	0.34
						4" Ice	11.53	11.41	0.75
APXVTM14-C-120 w/ Mount Pipe	C	From Leg	4.00	0.0000	102.00	No Ice	7.13	4.96	0.08

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment °	Placement ft	C <sub>AA</sub> Front ft <sup>2</sup>	C <sub>AA</sub> Side ft <sup>2</sup>	Weight K	
			0.00			1/2" Ice	7.66	5.75	0.13
			1.00			1" Ice	8.18	6.47	0.19
						2" Ice	9.26	8.01	0.34
						4" Ice	11.53	11.41	0.75
TD-RRH8x20-25	A	From Leg	4.00	0.0000	102.00	No Ice	4.72	1.70	0.07
			0.00			1/2" Ice	5.01	1.92	0.10
			1.00			1" Ice	5.32	2.15	0.13
						2" Ice	5.95	2.62	0.20
						4" Ice	7.31	3.68	0.40
TD-RRH8x20-25	B	From Leg	4.00	0.0000	102.00	No Ice	4.72	1.70	0.07
			0.00			1/2" Ice	5.01	1.92	0.10
			1.00			1" Ice	5.32	2.15	0.13
						2" Ice	5.95	2.62	0.20
						4" Ice	7.31	3.68	0.40
TD-RRH8x20-25	C	From Leg	4.00	0.0000	102.00	No Ice	4.72	1.70	0.07
			0.00			1/2" Ice	5.01	1.92	0.10
			1.00			1" Ice	5.32	2.15	0.13
						2" Ice	5.95	2.62	0.20
						4" Ice	7.31	3.68	0.40
7'x2 1/2" Pipe Mount	A	From Leg	4.00	0.0000	102.00	No Ice	2.01	2.01	0.04
			0.00			1/2" Ice	2.59	2.59	0.06
			0.00			1" Ice	3.02	3.02	0.07
						2" Ice	3.90	3.90	0.13
						4" Ice	5.78	5.78	0.30
7'x2 1/2" Pipe Mount	B	From Leg	4.00	0.0000	102.00	No Ice	2.01	2.01	0.04
			0.00			1/2" Ice	2.59	2.59	0.06
			0.00			1" Ice	3.02	3.02	0.07
						2" Ice	3.90	3.90	0.13
						4" Ice	5.78	5.78	0.30
7'x2 1/2" Pipe Mount	C	From Leg	4.00	0.0000	102.00	No Ice	2.01	2.01	0.04
			0.00			1/2" Ice	2.59	2.59	0.06
			0.00			1" Ice	3.02	3.02	0.07
						2" Ice	3.90	3.90	0.13
						4" Ice	5.78	5.78	0.30
T-Arm Mount [TA 702-3]	C	None		0.0000	92.00	No Ice	5.64	5.64	0.34
						1/2" Ice	6.55	6.55	0.43
						1" Ice	7.46	7.46	0.52
						2" Ice	9.28	9.28	0.70
						4" Ice	12.92	12.92	1.06
7770.00 w/ Mount Pipe	A	From Leg	0.50	0.0000	92.00	No Ice	6.22	4.35	0.06
			0.00			1/2" Ice	6.77	5.20	0.11
			-3.00			1" Ice	7.30	5.92	0.16
						2" Ice	8.38	7.41	0.29
						4" Ice	10.69	10.76	0.68
7770.00 w/ Mount Pipe	B	From Leg	0.50	0.0000	92.00	No Ice	6.22	4.35	0.06
			0.00			1/2" Ice	6.77	5.20	0.11
			-3.00			1" Ice	7.30	5.92	0.16
						2" Ice	8.38	7.41	0.29
						4" Ice	10.69	10.76	0.68
7770.00 w/ Mount Pipe	C	From Leg	0.50	0.0000	92.00	No Ice	6.22	4.35	0.06
			0.00			1/2" Ice	6.77	5.20	0.11
			-3.00			1" Ice	7.30	5.92	0.16
						2" Ice	8.38	7.41	0.29
						4" Ice	10.69	10.76	0.68
P65-15-XLH-RR w/ Mount Pipe	A	From Leg	0.50	0.0000	92.00	No Ice	6.55	4.38	0.06
			0.00			1/2" Ice	7.36	5.51	0.11
			-3.00			1" Ice	8.10	6.50	0.17
						2" Ice	9.42	8.17	0.31
						4" Ice	12.24	11.86	0.72
SBNH-1D6565C w/ Mount Pipe	B	From Leg	0.50	0.0000	92.00	No Ice	11.45	9.60	0.09
			0.00			1/2" Ice	12.06	11.02	0.18
			-3.00			1" Ice	12.69	12.29	0.27
						2" Ice	14.03	14.51	0.50
						4" Ice	17.05	19.14	1.12

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C <sub>AA</sub> Front	C <sub>AA</sub> Side	Weight
			Horz	Lateral Vert					
P65E-17-XLH-RR w/ Mount Pipe	C	From Leg	0.50	0.0000	92.00	No Ice	11.47	8.70	0.10
			0.00			1/2" Ice	12.08	10.11	0.18
			-3.00			1" Ice	12.71	11.38	0.27
						2" Ice	14.07	13.58	0.49
						4" Ice	17.08	18.18	1.10
(4) LGP2140X	A	From Leg	0.50	0.0000	92.00	No Ice	1.26	0.38	0.01
			0.00			1/2" Ice	1.42	0.49	0.02
			0.00			1" Ice	1.58	0.62	0.03
						2" Ice	1.94	0.89	0.05
						4" Ice	2.75	1.54	0.13
(4) LGP2140X	B	From Leg	0.50	0.0000	92.00	No Ice	1.26	0.38	0.01
			0.00			1/2" Ice	1.42	0.49	0.02
			0.00			1" Ice	1.58	0.62	0.03
						2" Ice	1.94	0.89	0.05
						4" Ice	2.75	1.54	0.13
(4) LGP2140X	C	From Leg	0.50	0.0000	92.00	No Ice	1.26	0.38	0.01
			0.00			1/2" Ice	1.42	0.49	0.02
			0.00			1" Ice	1.58	0.62	0.03
						2" Ice	1.94	0.89	0.05
						4" Ice	2.75	1.54	0.13
RRUS-11	A	From Leg	0.50	0.0000	92.00	No Ice	2.94	1.19	0.06
			0.00			1/2" Ice	3.17	1.35	0.07
			0.00			1" Ice	3.41	1.52	0.10
						2" Ice	3.91	1.89	0.15
						4" Ice	5.02	2.72	0.30
RRUS-11	B	From Leg	0.50	0.0000	92.00	No Ice	2.94	1.19	0.06
			0.00			1/2" Ice	3.17	1.35	0.07
			0.00			1" Ice	3.41	1.52	0.10
						2" Ice	3.91	1.89	0.15
						4" Ice	5.02	2.72	0.30
RRUS-11	C	From Leg	0.50	0.0000	92.00	No Ice	2.94	1.19	0.06
			0.00			1/2" Ice	3.17	1.35	0.07
			0.00			1" Ice	3.41	1.52	0.10
						2" Ice	3.91	1.89	0.15
						4" Ice	5.02	2.72	0.30
Side Arm Mount [SO 302-1]	A	From Leg	2.00	0.0000	75.00	No Ice	1.67	3.27	0.06
			0.00			1/2" Ice	2.51	4.99	0.09
			0.00			1" Ice	3.35	6.71	0.12
						2" Ice	5.03	10.15	0.19
						4" Ice	8.39	17.03	0.32
KS24019-L112A	A	From Leg	4.00	0.0000	75.00	No Ice	0.16	0.16	0.01
			0.00			1/2" Ice	0.22	0.22	0.01
			2.00			1" Ice	0.30	0.30	0.01
						2" Ice	0.48	0.48	0.02
						4" Ice	0.95	0.95	0.06



## Load Combinations

Comb. No.	Description
1	Dead Only
2	Dead+Wind 0 deg - No Ice
3	Dead+Wind 30 deg - No Ice
4	Dead+Wind 60 deg - No Ice
5	Dead+Wind 90 deg - No Ice
6	Dead+Wind 120 deg - No Ice
7	Dead+Wind 150 deg - No Ice
8	Dead+Wind 180 deg - No Ice
9	Dead+Wind 210 deg - No Ice
10	Dead+Wind 240 deg - No Ice
11	Dead+Wind 270 deg - No Ice
12	Dead+Wind 300 deg - No Ice
13	Dead+Wind 330 deg - No Ice
14	Dead+Ice+Temp
15	Dead+Wind 0 deg+Ice+Temp
16	Dead+Wind 30 deg+Ice+Temp
17	Dead+Wind 60 deg+Ice+Temp
18	Dead+Wind 90 deg+Ice+Temp
19	Dead+Wind 120 deg+Ice+Temp
20	Dead+Wind 150 deg+Ice+Temp
21	Dead+Wind 180 deg+Ice+Temp
22	Dead+Wind 210 deg+Ice+Temp
23	Dead+Wind 240 deg+Ice+Temp
24	Dead+Wind 270 deg+Ice+Temp
25	Dead+Wind 300 deg+Ice+Temp
26	Dead+Wind 330 deg+Ice+Temp
27	Dead+Wind 0 deg - Service
28	Dead+Wind 30 deg - Service
29	Dead+Wind 60 deg - Service
30	Dead+Wind 90 deg - Service
31	Dead+Wind 120 deg - Service
32	Dead+Wind 150 deg - Service
33	Dead+Wind 180 deg - Service
34	Dead+Wind 210 deg - Service
35	Dead+Wind 240 deg - Service
36	Dead+Wind 270 deg - Service
37	Dead+Wind 300 deg - Service
38	Dead+Wind 330 deg - Service

## Maximum Tower Deflections - Service Wind

Section No.	Elevation <i>ft</i>	Horz. Deflection <i>in</i>	Gov. Load Comb.	Tilt <i>°</i>	Twist <i>°</i>
T1	105.25 - 85.125	0.416	31	0.0617	0.0090
T2	85.125 - 65	0.139	31	0.0487	0.0060

## Critical Deflections and Radius of Curvature - Service Wind

Elevation <i>ft</i>	Appurtenance	Gov. Load Comb.	Deflection <i>in</i>	Tilt <i>°</i>	Twist <i>°</i>	Radius of Curvature <i>ft</i>
102.00	Sector Mount [SM 502-3]	31	0.366	0.0610	0.0086	94538
92.00	T-Arm Mount [TA 702-3]	31	0.221	0.0564	0.0073	35675
75.00	Side Arm Mount [SO 302-1]	31	0.056	0.0275	0.0032	47269

### Maximum Tower Deflections - Design Wind

Section No.	Elevation <i>ft</i>	Horz. Deflection <i>in</i>	Gov. Load Comb.	Tilt <i>°</i>	Twist <i>°</i>
T1	105.25 - 85.125	1.054	6	0.1557	0.0230
T2	85.125 - 65	0.353	6	0.1230	0.0152

### Critical Deflections and Radius of Curvature - Design Wind

Elevation <i>ft</i>	Appurtenance	Gov. Load Comb.	Deflection <i>in</i>	Tilt <i>°</i>	Twist <i>°</i>	Radius of Curvature <i>ft</i>
102.00	Sector Mount [SM 502-3]	6	0.928	0.1539	0.0220	37458
92.00	T-Arm Mount [TA 702-3]	6	0.560	0.1426	0.0186	14135
75.00	Side Arm Mount [SO 302-1]	6	0.143	0.0696	0.0083	18729

### Bolt Design Data

Section No.	Elevation <i>ft</i>	Component Type	Bolt Grade	Bolt Size <i>in</i>	Number Of Bolts	Maximum Load per Bolt <i>K</i>	Allowable Load <i>K</i>	Ratio Load Allowable	Allowable Ratio	Criteria	
T1	105.25	Leg	A325N	0.6250	4	2.52	13.50	0.186	✓	1.333	Bolt Tension
		Diagonal	A325N	0.5000	1	2.62	2.08	1.257	✓	1.333	Member Block Shear
		Top Girt	A325N	0.5000	1	0.30	2.72	0.109	✓	1.333	Member Bearing
T2	85.125	Leg	A325N	0.6250	4	7.57	13.39	0.565	✓	1.333	Bolt Tension
		Diagonal	A325N	0.5000	1	2.75	3.81	0.724	✓	1.333	Member Block Shear

### Compression Checks

#### Leg Design Data (Compression)

Section No.	Elevation <i>ft</i>	Size	<i>L</i> <i>ft</i>	<i>L<sub>a</sub></i> <i>ft</i>	<i>Kl/r</i>	<i>F<sub>a</sub></i> <i>ksi</i>	<i>A</i> <i>in<sup>2</sup></i>	Actual <i>P</i> <i>K</i>	Allow. <i>P<sub>a</sub></i> <i>K</i>	Ratio $\frac{P}{P_a}$
T1	105.25 - 85.125	ROHN 2.5 STD	20.13	4.02	51.0 K=1.00	24.197	1.7040	-13.64	41.23	0.331
T2	85.125 - 65	ROHN 2.5 STD	20.16	5.02	63.6 K=1.00	22.099	1.7040	-35.90	37.66	0.953



#### Diagonal Design Data (Compression)

Section No.	Elevation <i>ft</i>	Size	<i>L</i> <i>ft</i>	<i>L<sub>a</sub></i> <i>ft</i>	<i>Kl/r</i>	<i>F<sub>a</sub></i> <i>ksi</i>	<i>A</i> <i>in<sup>2</sup></i>	Actual <i>P</i> <i>K</i>	Allow. <i>P<sub>a</sub></i> <i>K</i>	Ratio $\frac{P}{P_a}$
T1	105.25 - 85.125	L1 1/2x1 1/2x1/8	7.70	3.60	146.0 K=1.00	7.002	0.3594	-2.65	2.52	1.054
T2	85.125 - 65	L1 3/4x1 3/4x3/16	9.70	4.75	166.0 K=1.00	5.418	0.6211	-2.76	3.36	0.822



#### Top Girt Design Data (Compression)

Section No.	Elevation <i>ft</i>	Size	<i>L</i> <i>ft</i>	<i>L<sub>a</sub></i> <i>ft</i>	<i>Kl/r</i>	<i>F<sub>a</sub></i> <i>ksi</i>	<i>A</i> <i>in<sup>2</sup></i>	Actual <i>P</i> <i>K</i>	Allow. <i>P<sub>a</sub></i> <i>K</i>	Ratio $\frac{P}{P_a}$
T1	105.25 - 85.125	L2x2x1/8	6.56	6.11	184.6 K=1.00	4.384	0.4844	-0.30	2.12	0.143
T2	85.125 - 65	L2x2x1/8	6.56	6.32	163.6 K=0.86	5.581	0.4844	-0.12	2.70	0.046



### Tension Checks

#### Leg Design Data (Tension)

Section No.	Elevation <i>ft</i>	Size	<i>L</i> <i>ft</i>	<i>L<sub>a</sub></i> <i>ft</i>	<i>Kl/r</i>	<i>F<sub>a</sub></i> <i>ksi</i>	<i>A</i> <i>in<sup>2</sup></i>	Actual <i>P</i> <i>K</i>	Allow. <i>P<sub>a</sub></i> <i>K</i>	Ratio $\frac{P}{P_a}$
T1	105.25 - 85.125	ROHN 2.5 STD	20.13	4.02	51.0	30.000	1.7040	10.07	51.12	0.197
T2	85.125 - 65	ROHN 2.5 STD	20.16	5.02	63.6	30.000	1.7040	30.29	51.12	0.593



### Diagonal Design Data (Tension)

Section No.	Elevation <i>ft</i>	Size	<i>L</i> <i>ft</i>	<i>L<sub>a</sub></i> <i>ft</i>	<i>Kl/r</i>	<i>F<sub>a</sub></i> <i>ksi</i>	<i>A</i> <i>in<sup>2</sup></i>	Actual <i>P</i> <i>K</i>	Allow. <i>P<sub>a</sub></i> <i>K</i>	Ratio $\frac{P}{P_a}$
T1	105.25 - 85.125	L1 1/2x1 1/2x1/8	7.70	3.60	95.7	29.000	0.2109	2.62	6.12	0.428
T2	85.125 - 65	L1 3/4x1 3/4x3/16	9.70	4.75	108.5	29.000	0.3779	2.75	10.96	0.251



### Top Girt Design Data (Tension)

Section No.	Elevation <i>ft</i>	Size	<i>L</i> <i>ft</i>	<i>L<sub>a</sub></i> <i>ft</i>	<i>Kl/r</i>	<i>F<sub>a</sub></i> <i>ksi</i>	<i>A</i> <i>in<sup>2</sup></i>	Actual <i>P</i> <i>K</i>	Allow. <i>P<sub>a</sub></i> <i>K</i>	Ratio $\frac{P}{P_a}$
T1	105.25 - 85.125	L2x2x1/8	6.56	6.11	121.2	29.000	0.3047	0.30	8.84	0.033
T2	85.125 - 65	L2x2x1/8	6.56	6.32	121.2	21.600	0.4844	0.23	10.46	0.022*



\* DL controls

### Section Capacity Table

Section No.	Elevation <i>ft</i>	Component Type	Size	Critical Element	<i>P</i> <i>K</i>	<i>SF*P<sub>allow</sub></i> <i>K</i>	% Capacity	Pass Fail
T1	105.25 - 85.125	Leg	ROHN 2.5 STD	2	-13.64	54.96	24.8	Pass
T2	85.125 - 65	Leg	ROHN 2.5 STD	38	-35.90	50.20	71.5	Pass
T1	105.25 - 85.125	Diagonal	L1 1/2x1 1/2x1/8	8	-2.65	3.35	79.0	Pass
T2	85.125 - 65	Diagonal	L1 3/4x1 3/4x3/16	46	-2.76	4.49	61.6	Pass
T1	105.25 - 85.125	Top Girt	L2x2x1/8	5	-0.30	2.83	10.7	Pass
T2	85.125 - 65	Top Girt	L2x2x1/8	41	-0.12	3.60	3.4	Pass


Summary	ELC:	Load Case 5
Leg (T2)	71.5	Pass
Diagonal (T1)	94.3	Pass
Top Girt (T1)	10.7	Pass
Bolt Checks	94.3	Pass
Rating =	94.3	Pass

**APPENDIX B**  
**BASE LEVEL DRAWING**



(INSTALLED)  
 (1) 3/4" TO 82 FT LEVEL  
 (2) 3/4" TO 82 FT LEVEL  
 (6) 1-5/8" TO 92 FT LEVEL

(PROPOSED)  
 (1) 5/8" TO 102 FT LEVEL  
 (INSTALLED)  
 (1) 1/2" TO 75 FT LEVEL  
 (3) 1-1/4" TO 102 FT LEVEL



BUSINESS UNIT: 876328 TOWER ID: C-BASELEVEL

BASE LEVEL DRAWING

SCALE: 1/8" = 1'

SHEET NUMBER: 1

CROWN REGION/ADDRESS  
 USA

- 18/01/08 NEW BUILD PER WORK ORDER # 188443 RMK
- 20/12/11 AS-BUILT INFORMATION ADDED PER WORK ORDER # 451953 KAH
- 11/10/12 APPLICATION ADDED PER WORK ORDER # 540606 MOB
- 05/02/13 UPDATED PER WORK ORDER # 573421 N.M.H
- 02/01/14 APPLICATION ADDED PER WORK ORDER # 686184 KT
- 22/01/14 UPDATED PER WORK ORDER # 686541 ADJ
- 11/02/14 UPDATED PER WORK ORDER # 711482 TDG

DRAWN BY: RMK  
 CHECKED BY: RMM  
 DRAWING DATE: 18/1/08

SITE NUMBER: \_\_\_\_\_  
 SITE NAME: \_\_\_\_\_  
 WEST HARTFORD PARKING GARAGE  
 BUSINESS UNIT NUMBER: 876328  
 SITE ADDRESS: 27-31 SOUTH MAIN ST  
 WEST HARTFORD, CT 06110  
 HARTFORD COUNTY  
 USA  
 SHEET TITLE: BASE LEVEL  
 SHEET NUMBER: \_\_\_\_\_

**APPENDIX C**  
**ADDITIONAL CALCULATIONS**



GPD GROUP®  
Glaus, Pyle, Schomer, Burns & DeHaven, Inc.

Job 2014777-876328-01

Sheet No. 1 of 1

Calculated by MS Date 03/07/2014

Checked by JH Date 03/07/2014

Beam Properties: W12 x 35

$$b_f = 6.56''$$

$$d = 12.5''$$

$$F_y = 36 \text{ ksi}$$

$$t_f = 0.520''$$

$$t_w = 0.30''$$

$$I_x = 285 \text{ in}^4$$

$$f_b = \frac{M_c}{I} = \frac{36 \text{ K} \times \frac{9'}{4} \times \frac{12''}{1'} \times \frac{12.5''}{2}}{285 \text{ in}^4} = 21.3 \text{ ksi}$$

$$F_b = 0.66 F_y \times S.F. = 31.68 \text{ ksi}$$

$$\text{Beam Rating} : \frac{f_b}{F_b} \times 100 = \frac{21.3}{31.68 \text{ ksi}} = 67.3 \%$$



RADIO FREQUENCY FCC REGULATORY COMPLIANCE  
MAXIMUM PERMISSIBLE EXPOSURE (MPE) ASSESSMENT

Sprint Existing Facility

Site ID: CT03XC075

West Hartford Parking Garage

27 - 31 South Main Street  
West Hartford, CT 06110

**April 7, 2014**

**EBI Project Number: 62141886**

April 7, 2014

Sprint  
Attn: RF Engineering Manager  
1 International Boulevard, Suite 800  
Mahwah, NJ 07495

Re: Radio Frequency Maximum Permissible Exposure (MPE) Assessment for Site:  
**CT03XC075 - West Hartford Parking Garage**

**Site Total: 67.789% - MPE% in full compliance (At Ground Level)**

**Site Total: 237.188% - MPE% Not in full compliance (At Rooftop Level)**

EBI Consulting was directed to analyze the proposed upgrades to the existing Sprint facility located at 27 - 31 South Main Street, West Hartford, CT, for the purpose of determining whether the radio frequency (RF) exposure levels from the proposed Sprint equipment upgrades on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter ( $\mu\text{W}/\text{cm}^2$ ). The number of  $\mu\text{W}/\text{cm}^2$  calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits, therefore it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) – (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general public may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general public would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

Public exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter ( $\mu\text{W}/\text{cm}^2$ ). The general population exposure limit for the cellular band (850 MHz Band) is approximately  $567 \mu\text{W}/\text{cm}^2$ , and the general population exposure limit for the 1900 MHz and 2500 MHz

bands is  $1000 \mu\text{W}/\text{cm}^2$ . Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.

Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure. Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

## CALCULATIONS

Calculations were done for the proposed upgrades to the existing Sprint Wireless antenna facility located at 27 - 31 South Main Street, West Hartford, CT, using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. All calculations were performed assuming the main lobe of the antenna was focused at the base of the tower to present a worst case scenario. Actual values seen from this site will be dramatically less than those shown in this report. For this report the sample point is the top of a 6 foot person standing at the base of the tower. Additionally, calculations were performed for the 6 foot person standing on the roof level of the parking garage.

For all calculations, all emissions were calculated using the following assumptions:

- 1) 4 channels in the 1900 MHz Band were considered for each sector of the proposed installation.
- 2) 1 channel in the 800 MHz Band was considered for each sector of the proposed installation
- 3) 2 channels in the 2500 MHz Band were considered for each sector of the proposed installation.
- 4) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 - Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.
- 5) For the following calculations the sample point was the top of a six foot person standing at the base of the tower. Additionally, Calculations were performed for the 6 foot person standing on the roof level of the parking garage. The maximum gain of the antenna per the antenna manufactures supplied specifications was used in this direction in both scenarios.

- 6) The antennas used in this modeling are the RFS APXVSPP18-C-A20 and the RFS APXVTMM-C-120. This is based on feedback from the carrier with regards to anticipated antenna selection. The RFS APXVSPP18-C-A20 has a 15.9 dBd gain value at its main lobe at 1900 MHz and 13.4 dBd at its main lobe for 850 MHz. The RFS APXVTMM-C-120 has a 15.9 dBd gain value at its main lobe at 2500 MHz. All calculations were performed assuming the main lobe of the antenna was focused at the base of the tower to present a worst case scenario.
- 7) The antenna mounting height centerline for the proposed antennas is **103 feet** above ground level (AGL) and 52 feet above the rooftop level (ARL).
- 8) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.

All calculation were done with respect to uncontrolled / general public threshold limits

Site ID	CT03XC075 - West Hartford Parking Garage (ground Level)
Site Address	27 - 31 South Main Street, West Hartford, CT 06110
Site Type	Self Support Tower

**Sector 1**

Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain in direction of sample point (dBd)	Antenna Height (ft)	analysis height	Cable Size	Cable Loss (dB)	Additional Loss (dB)	ERP	Power Density Percentage
1a	RFS	APXVSP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	4	80	15.9	103	97	1/2 "	0.5	3	1390.2407	5.31193%
1a	RFS	APXVSP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	13.4	103	97	1/2 "	0.5	3	195.44744	1.31707%
1B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	13.4	103	97	1/2 "	0.5	3	390.89489	2.63414%
Sector total Power Density Value:																9.263%

**Sector 2**

Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain in direction of sample point (dBd)	Antenna Height (ft)	analysis height	Cable Size	Cable Loss (dB)	Additional Loss (dB)	ERP	Power Density Percentage
2a	RFS	APXVSP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	4	80	15.9	103	97	1/2 "	0.5	3	1390.2407	5.31193%
2a	RFS	APXVSP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	13.4	103	97	1/2 "	0.5	3	195.44744	1.31707%
2B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	13.4	103	97	1/2 "	0.5	3	390.89489	2.63414%
Sector total Power Density Value:																9.263%

**Sector 3**

Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain in direction of sample point (dBd)	Antenna Height (ft)	analysis height	Cable Size	Cable Loss (dB)	Additional Loss (dB)	ERP	Power Density Percentage
3a	RFS	APXVSP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	4	80	15.9	103	97	1/2 "	0.5	3	1390.2407	5.31193%
3a	RFS	APXVSP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	13.4	103	97	1/2 "	0.5	3	195.44744	1.31707%
3B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	13.4	103	97	1/2 "	0.5	3	390.89489	2.63414%
Sector total Power Density Value:																9.263%

Site Composite MPE %	
Carrier	MPE %
Sprint	27.789%
AT&T	40.000%
<b>Total Site MPE %</b>	<b>67.789%</b>

Site ID	CT03XC075 - West Hartford Parking Garage (Roof Level)
Site Address	27 - 31 South Main Street, West Hartford, CT 06110
Site Type	Self Support Tower

**Sector 1**

Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain in direction of sample point (dBd)	Antenna Height (ft)	analysis height	Cable Size	Cable Loss (dB)	Additional Loss (dB)	ERP	Power Density Percentage
1a	RFS	APXVSP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	4	80	15.9	52	46	1/2 "	0.5	3	1390.2407	23.62002%
1a	RFS	APXVSP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	13.4	52	46	1/2 "	0.5	3	195.44744	5.85649%
1B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	13.4	52	46	1/2 "	0.5	3	390.89489	11.71298%
Sector total Power Density Value:																41.189%

**Sector 2**

Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain in direction of sample point (dBd)	Antenna Height (ft)	analysis height	Cable Size	Cable Loss (dB)	Additional Loss (dB)	ERP	Power Density Percentage
2a	RFS	APXVSP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	4	80	15.9	52	46	1/2 "	0.5	3	1390.2407	23.62002%
2a	RFS	APXVSP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	13.4	52	46	1/2 "	0.5	3	195.44744	5.85649%
2B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	13.4	52	46	1/2 "	0.5	3	390.89489	11.71298%
Sector total Power Density Value:																41.189%

**Sector 3**

Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain in direction of sample point (dBd)	Antenna Height (ft)	analysis height	Cable Size	Cable Loss (dB)	Additional Loss (dB)	ERP	Power Density Percentage
3a	RFS	APXVSP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	4	80	15.9	52	46	1/2 "	0.5	3	1390.2407	23.62002%
3a	RFS	APXVSP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	13.4	52	46	1/2 "	0.5	3	195.44744	5.85649%
3B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	13.4	52	46	1/2 "	0.5	3	390.89489	11.71298%
Sector total Power Density Value:																41.189%

Site Composite MPE %	
Carrier	MPE %
Sprint	123.568%
AT&T	113.620%
<b>Total Site MPE %</b>	<b>237.188%</b>

## Summary

All calculations performed for this analysis yielded results that were well within the allowable limits for general public Maximum Permissible Exposure (MPE) to radio frequency energy at ground level. At the Rooftop level there are areas that may exceed the general public Maximum Permissible Exposure (MPE) to radio frequency energy.

The anticipated Maximum Composite contributions from the Sprint facility are **27.789% (9.263% from each sector)** of the allowable FCC established general public limit considering all three sectors simultaneously sampled at the ground level.

The anticipated composite MPE value for this site assuming all carriers present is **57.862%** of the allowable FCC established general public limit sampled at 6 feet above ground level. This total composite site value is based upon MPE values listed in the Connecticut Siting Council database for existing carrier emissions.

Additionally, Since the Connecticut Siting Council database has values listed for the parking garage rooftop level as well these calculations were performed. The anticipated Maximum Composite contributions from the Sprint facility for a 6 foot person at the parking garage rooftop level is **123.568% (41.189% from each sector)** of the allowable FCC established general public limit considering all three sectors simultaneously sampled at the parking garage rooftop level.

The anticipated composite MPE value for this site assuming all carriers present is **237.188%** of the allowable FCC established general public limit for a 6 foot person at the parking garage rooftop level. This total composite site value is based upon MPE values listed in the Connecticut Siting Council database for existing carrier emissions.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance.



Scott Heffernan  
RF Engineering Director

### EBI Consulting

21 B Street  
Burlington, MA 01803