



August 17th, 2018

Melanie Bachman, Executive Director
Connecticut Siting Council
10 Franklin Square
New Britain, CT 06051

RE: Notice of Exempt Modification – Antenna Swap for wireless facility located at 668 JONES HILL ROAD, WEST HAVEN, CONNECTICUT – CT52XC076 (lat. 41° 15' 23.044" N, long. - 72° 58' 20.491" W)

Dear Ms. Bachman:

Sprint Spectrum, LP ("Sprint") currently maintains wireless telecommunications antennas at the (151-foot level) on an existing (150-foot Monopole Tower) at the above-referenced address. The property and the tower are owned by AMERICAN TOWER CORPORATION.

Sprint's proposed work involves antenna replacement and tower work. Sprint intends to replace three (3) antennas, add an additional three (3) antennas, and add nine (9) new RRHs onto the tower. All the proposed work is contained within the existing fenced area. Please refer to the attached drawings for site plans prepared by Infinigy Engineering.

Please accept this letter as notification pursuant to R.C.S.A. § 16-50j-73, for construction that constitutes an exempt modification pursuant to R.C.S.A. § 16-50j-72(b). In accordance with R.C.S.A. § 16-50j-73, a copy of this letter is being sent to NANCY ROSSI, MAYOR and FRED MESSORE, COMMISSIONER of the City of West Haven. A copy of this letter is also being sent to JUSTINE PAUL the manager for AMERICAN TOWER CORPORATION who manages the tower and owns the land.

The planned modifications to the facility fall squarely within those activities explicitly provided for in R.C.S.A. § 16-50j-72(b).

1. The proposed modifications will not result in an increase in the height of the existing tower.
2. The antennas work is a one-for-one replacement of facility components.
3. The proposed modifications will include the addition of ground base equipment as depicted on the attached drawings; however, the proposed equipment will not require



an extension of the site boundaries.

4. The proposed modifications will not increase noise levels at the facility by six decibels or more.
5. The additional ground based equipment will not increase radio frequency (RF) emissions at the facility to a level at or above the Federal Communications Commission (FCC) adopted safety standard.

For the foregoing reasons, Sprint respectfully submits that the proposed modifications to the above referenced telecommunications facility constitutes an exempt modification under R.C.S.A. § 16-50j-72(b).

If you have any questions or require any additional information regarding this request, please do not hesitate to give me a call at (518) 350-4222 or email me to aperkowski@airosmithdevelopment.com

Kind Regards,

A handwritten signature in black ink, appearing to read 'Arthur Perkowski', is written over a large, light-colored oval shape that serves as a placeholder for a signature.

Arthur Perkowski
Airosmith Development Inc.
32 Clinton Street
Saratoga Springs, NY 12866
518-306-1711 desk & fax
518-871-3707 cell
aperkowski@airosmithdevelopment.com

Attachment

CC: NANCY ROSSI (MAYOR, West Haven, CT)
Justine Paul (American Tower Corporation)
Fred Messore (COMMISSIONER, West Haven, CT)

7018 0680 0002 1201 6064

**U.S. Postal Service™
CERTIFIED MAIL® RECEIPT**
Domestic Mail Only

For delivery information, visit our website at www.usps.com®.

WEST HAVEN CT 06516

OFFICIAL USE

Certified Mail Fee	\$3.45
Extra Services & Fees (check box, add fee to postage)	\$2.75
<input type="checkbox"/> Return Receipt (hardcopy)	\$0.00
<input type="checkbox"/> Return Receipt (electronic)	\$0.00
<input type="checkbox"/> Certified Mail Restricted Delivery	\$0.00
<input type="checkbox"/> Adult Signature Required	\$0.00
<input type="checkbox"/> Adult Signature Restricted Delivery	\$0.00
Postage	\$0.50
Total Postage and Fees	\$6.70

Sent To: Nancy Ross CTSDXCC076
Street and Apt. No. (or PO Box No.): 355 Main St 3rd Floor
City, State, ZIP+4®: West Haven CT 06516

PS Form 3800, April 2015 PSN 7530-02-000-9047 See Reverse for Instructions



8175 1021 2000 0990 8104

**U.S. Postal Service™
CERTIFIED MAIL® RECEIPT**
Domestic Mail Only

For delivery information, visit our website at www.usps.com®.

WEST HAVEN CT 06516

OFFICIAL USE

Certified Mail Fee	\$3.45
Extra Services & Fees (check box, add fee to postage)	\$2.75
<input type="checkbox"/> Return Receipt (hardcopy)	\$0.00
<input type="checkbox"/> Return Receipt (electronic)	\$0.00
<input type="checkbox"/> Certified Mail Restricted Delivery	\$0.00
<input type="checkbox"/> Adult Signature Required	\$0.00
<input type="checkbox"/> Adult Signature Restricted Delivery	\$0.00
Postage	\$0.50
Total Postage and Fees	\$6.70

Sent To: Fred Messore CTSDXCC076
Street and Apt. No. (or PO Box No.): 355 Main St
City, State, ZIP+4®: West Haven CT 06516

PS Form 3800, April 2015 PSN 7530-02-000-9047 See Reverse for Instructions



7018 0680 0002 1201 6057

**U.S. Postal Service™
CERTIFIED MAIL® RECEIPT**
Domestic Mail Only

For delivery information, visit our website at www.usps.com®.

WOBBURN MA 01801

OFFICIAL USE

Certified Mail Fee	\$3.45
Extra Services & Fees (check box, add fee to postage)	\$2.75
<input type="checkbox"/> Return Receipt (hardcopy)	\$0.00
<input type="checkbox"/> Return Receipt (electronic)	\$0.00
<input type="checkbox"/> Certified Mail Restricted Delivery	\$0.00
<input type="checkbox"/> Adult Signature Required	\$0.00
<input type="checkbox"/> Adult Signature Restricted Delivery	\$0.00
Postage	\$0.50
Total Postage and Fees	\$6.70

Sent To: Jodie Peir CTSDXCC076
Street and Apt. No. (or PO Box No.): 10 Presidential Way
City, State, ZIP+4®: Woburn MA 01801

PS Form 3800, April 2015 PSN 7530-02-000-9047 See Reverse for Instructions





Property Information


Owner	AMERICAN TOWERS INC.
Co-Owner	ATTN TAX DEPT
Address	668 JONES HILL RD
Mailing Address	PO BOX 723597 ATLANTA GA 31139
Land Use	431V TEL REL TW MDL-00
Land Class	I

Vision ID	102767
Census Tract	
Neighborhood	
Zoning Code	
Acreage	0
Utilities	

Photo



Sketch



Primary Construction Details

Actual Year Built	
Effective Year Built	
Stories	
Building Style	
Building Use	
Building Condition	
Total Rooms	

Bedrooms	
Full Bathrooms	
Half Bathrooms	
Bath Style	
Kitchen Style	
Roof Style	
Roof Cover	

Exterior Walls	
Interior Walls	
Heating Type	
Heating Fuel	
AC Type	
Gross Bldg Area	
Total Living Area	0



Valuation Summary (Assessed value = 70% of Appraised Value)

Item	Appraised	Assessed
Buildings	0	0
Outbuildings	431800	302260
Improvements	431800	302260
Extras	0	0
Land	0	0
Total	431800	302260

Outbuilding and Extra Items

Description	Units
FENCE-6' CHAIN	200 L.F.
TOWER	2 SITES
CELL SHED	288 S.F.

Sub Areas


Subarea Type	Gross Area (sq ft)	Living Area (sq ft)
Total Area		

Sales History

Owner of Record	Book/ Page	Sale Date	Sale Price
AMERICAN TOWERS INC.	000/ 000	10/1/2010	0


City of West Haven, Connecticut - Assessment Parcel Map

Parcel: 019-0001-0-000 Address: 690 JONES HILL RD #41



N

Approximate Scale: 1 inch = 150 feet



Map Produced: January 2015

Disclaimer: This map is for informational purposes only. All information is subject to verification by any user. The City of West Haven and its mapping contractors assume no legal responsibility for the information contained herein.



RADIO FREQUENCY EMISSIONS ANALYSIS REPORT EVALUATION OF HUMAN EXPOSURE POTENTIAL TO NON-IONIZING EMISSIONS

SPRINT Existing Facility

Site ID: CT52XC076

West Haven & RT 162 CT
668 Jones Hill Road
West Haven, CT 06516

July 27, 2018

EBI Project Number: 6218005218

Site Compliance Summary	
Compliance Status:	COMPLIANT
Site total MPE% of FCC general population allowable limit:	11.99 %



July 27, 2018

SPRINT

Attn: RF Engineering Manager
1 International Boulevard, Suite 800
Mahwah, NJ 07495

Emissions Analysis for Site: **CT52XC076 – West Haven & RT 162 CT**

EBI Consulting was directed to analyze the proposed SPRINT facility located at **668 Jones Hill Road, West Haven, CT**, for the purpose of determining whether the emissions from the Proposed SPRINT Antenna Installation located on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter ($\mu\text{W}/\text{cm}^2$). The number of $\mu\text{W}/\text{cm}^2$ calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits, therefore it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) – (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general population may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general population would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

General population exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter ($\mu\text{W}/\text{cm}^2$). The general population exposure limits for the 850 MHz Band is approximately $567 \mu\text{W}/\text{cm}^2$. The general population exposure limit for the 1900 MHz (PCS), 2500 MHz (BRS), 11 GHz microwave and 23 GHz microwave bands is $1000 \mu\text{W}/\text{cm}^2$. Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.



Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure. Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

CALCULATIONS

Calculations were done for the proposed SPRINT Wireless antenna facility located at **668 Jones Hill Road, West Haven, CT**, using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. Since SPRINT is proposing highly focused directional panel antennas, which project most of the emitted energy out toward the horizon, all calculations were performed assuming a lobe representing the maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB for directional panel antennas and 20 dB for highly focused parabolic microwave dishes, was focused at the base of the tower. For this report the sample point is the top of a 6-foot person standing at the base of the tower.

For all calculations, all equipment was calculated using the following assumptions:

- 1) 1 CDMA channels (850 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 20 Watts per Channel.
- 2) 2 LTE channels (850 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 50 Watts per Channel.
- 3) 5 CDMA channels (1900 MHz (PCS)) were considered for each sector of the proposed installation. These Channels have a transmit power of 16 Watts per Channel.
- 4) 2 LTE channels (1900 MHz (PCS)) were considered for each sector of the proposed installation. These Channels have a transmit power of 40 Watts per Channel.
- 5) 8 LTE channels (2500 MHz (BRS)) were considered for each sector of the proposed installation. These Channels have a transmit power of 20 Watts per Channel.
- 6) 1 microwave (23 GHz) backhaul channel was considered for sector A. This channel has a transmit power of 1 Watt.



- 7) 2 microwave (11 GHz) backhaul channels were considered for sectors B & C. These channels have a transmit power of 1 Watt per channel.
- 8) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 - Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.
- 9) For the following calculations, the sample point was the top of a 6-foot person standing at the base of the tower. The maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB for directional panel antennas and 20 dB for highly focused parabolic microwave dishes, was used in this direction. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 10) The antennas used in this modeling are the **Commscope NNVV-65B-R4** and the **Nokia AAHC** for transmission in the 850 MHz, 1900 MHz (PCS) and 2500 MHz (BRS) frequency bands and the **Dragonwave A-ANT-23G-1-C** and **Dragonwave A-ANT-11G-2-C** for the 23 GHz and 11 GHz microwave links respectively. This is based on feedback from the carrier with regards to anticipated antenna selection. Maximum gain values for all antennas are listed in the Inventory and Power Data table below. The maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB for directional panel antennas and 20 dB for highly focused parabolic microwave dishes, was used for all calculations. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 11) The antenna mounting height centerlines of the proposed panel antennas are **154 feet** above ground level (AGL) for **Sectors A, B & C**. The antenna mounting height centerlines of the proposed microwave dishes are **151 feet** above ground level (AGL) for **Sectors A, B & C**
- 12) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.

All calculations were done with respect to uncontrolled / general population threshold limits.



SPRINT Site Inventory and Power Data by Antenna

Sector:	A	Sector:	B	Sector:	C
Antenna #:	1	Antenna #:	1	Antenna #:	1
Make / Model:	Commscope NNVV-65B-R4	Make / Model:	Commscope NNVV-65B-R4	Make / Model:	Commscope NNVV-65B-R4
Gain:	12.75 / 15.05 dBd	Gain:	12.75 / 15.05 dBd	Gain:	12.75 / 15.05 dBd
Height (AGL):	154 feet	Height (AGL):	154 feet	Height (AGL):	154 feet
Frequency Bands	850 MHz / 1900 MHz (PCS)	Frequency Bands	850 MHz / 1900 MHz (PCS)	Frequency Bands	850 MHz / 1900 MHz (PCS)
Channel Count	10	Channel Count	10	Channel Count	10
Total TX Power(W):	280 Watts	Total TX Power(W):	280 Watts	Total TX Power(W):	280 Watts
ERP (W):	7,378.61	ERP (W):	7,378.61	ERP (W):	7,378.61
Antenna A1 MPE%	1.50 %	Antenna B1 MPE%	1.50 %	Antenna C1 MPE%	1.50 %
Antenna #:	2	Antenna #:	2	Antenna #:	2
Make / Model:	Nokia AAHC	Make / Model:	Nokia AAHC	Make / Model:	Nokia AAHC
Gain:	15.05 dBd	Gain:	15.05 dBd	Gain:	15.05 dBd
Height (AGL):	154 feet	Height (AGL):	154 feet	Height (AGL):	154 feet
Frequency Bands	2500 MHz (BRS)	Frequency Bands	2500 MHz (BRS)	Frequency Bands	2500 MHz (BRS)
Channel Count	8	Channel Count	8	Channel Count	8
Total TX Power(W):	160 Watts	Total TX Power(W):	160 Watts	Total TX Power(W):	160 Watts
ERP (W):	5,118.23	ERP (W):	5,118.23	ERP (W):	5,118.23
Antenna A2 MPE%	0.84 %	Antenna B2 MPE%	0.84 %	Antenna C2 MPE%	0.84 %

Microwave Backhaul Data

Antenna Type:	Gain (dBd)	Height (feet AGL):	Frequency Bands	Channel Count	Total TX Power(W)	ERP (W)	MPE %	Sector
Dragonwave A-ANT-23G-1-C	33.15 dBd	151	23 GHz	1	1	2,065.38	0.03	A
Dragonwave A-ANT-11G-2-C	32.35 dBd	151	11 GHz	1	1	1,717.91	0.02	B
Dragonwave A-ANT-11G-2-C	32.35 dBd	151	11 GHz	1	1	1,717.91	0.02	C

Site Composite MPE%	
Carrier	MPE%
SPRINT -Sector A	2.37 %
T-Mobile	1.53 %
Clearwire	0.12 %
MetroPCS	1.02 %
Computer Hospital	0.23 %
Verizon Wireless	2.42 %
AT&T	4.30 %
Site Total MPE %:	11.99 %

SPRINT Sector A Total:	2.37 %
SPRINT Sector B Total:	2.36 %
SPRINT Sector C Total:	2.36 %
Site Total:	
	11.99 %



Sprint Maximum Power Values (Sector A)

SPRINT _ Frequency Band / Technology (All Sectors)	# Channels	Watts ERP (Per Channel)	Height (feet)	Total Power Density ($\mu\text{W}/\text{cm}^2$)	Frequency (MHz)	Allowable MPE ($\mu\text{W}/\text{cm}^2$)	Calculated % MPE
Sprint 850 MHz CDMA	1	376.73	154	0.62	850 MHz	567	0.11%
Sprint 850 MHz LTE	2	941.82	154	3.09	850 MHz	567	0.55%
Sprint 1900 MHz (PCS) CDMA	5	511.82	154	4.20	1900 MHz (PCS)	1000	0.42%
Sprint 1900 MHz (PCS) LTE	2	1,279.56	154	4.20	1900 MHz (PCS)	1000	0.42%
Sprint 2500 MHz (BRS) LTE	8	639.78	154	8.40	2500 MHz (BRS)	1000	0.84%
Sprint 23 GHz Microwave	1	2,065.38	154	0.34	23 GHz	1000	0.03%
						Total:	2.37%



Summary

All calculations performed for this analysis yielded results that were **within** the allowable limits for general population exposure to RF Emissions.

The anticipated maximum composite contributions from the SPRINT facility as well as the site composite emissions value with regards to compliance with FCC's allowable limits for general population exposure to RF Emissions are shown here:

SPRINT Sector	Power Density Value (%)
Sector A:	2.37 %
Sector B:	2.36 %
Sector C:	2.36 %
SPRINT Maximum MPE % (Sector A):	2.37 %
Site Total:	11.99 %
Site Compliance Status:	COMPLIANT

The anticipated composite MPE value for this site assuming all carriers present is **11.99 %** of the allowable FCC established general population limit sampled at the ground level. This is based upon values listed in the Connecticut Siting Council database for existing carrier emissions.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.

INFINIGY

FROM ZERO TO INFINIGY
the solutions are endless


1033 WATERVLIET SHAKER RD, ALBANY, NY 12205

Mount Analysis Report

June 7, 2018

Site Name	CT52XC076
Infinigy Job Number	526-104
Client	Airosmith
Proposed Carrier	Sprint
Site Location	668 Jones Hill Road West Haven, CT 06516 41.25640° N NAD83 72.97236° W NAD83
Mount Centerline El.	151 ft.
Mount Classification	T-Arm
Failing Structural Usage	> 200%
Passing Structural Usage	68.4%
Overall Result	Contingent Pass- See Required Modification Below.
Note	Replace existing mounts with new SitePro1 RMV5-296 with addition 96" long 2.375" OD Sch 40 mount pipes 18" from left side of frame. See appended documents for details.

Upon reviewing the results of this analysis, it is our opinion that the structure meets the specified TIA code requirements. The mounts for the proposed carrier are therefore deemed adequate to support the final loading configuration as listed in this report.



Nathaniel R. Ober, E.I.T.
Northeast Structural Region Lead

AZ CA CO FL GA MD NC NH NJ NY TX WA

INFINIGY

Contents

Introduction.....	3
Supporting Documentation.....	3
Analysis Code Requirements.....	3
Conclusion.....	3
Final Configuration Loading.....	4
Structure Usages.....	4
Mount Connection Reactions.....	4
Assumptions and Limitations.....	5
Calculations.....	Appended

Introduction

Infinigy Engineering has been requested to perform a mount analysis on the existing Sprint mounts. All supporting documents have been obtained from the client and are assumed to be accurate and applicable to this site. The mount was analyzed using RISA-3D Version 16.0.3 analysis software.

Supporting Documentation

Colo App	ATC Eng #OAA714853, dated April 18, 2018
-----------------	--

Analysis Code Requirements

Wind Speed	97 mph (3-Second Gust, Vasd) / 125 mph (3-Second Gust, Vult)
Wind Speed w/ ice	50 mph (3-Second Gust, Vasd) w/ 3/4" Ice
TIA Revision	ANSI/TIA-222-G
Adopted IBC	2012 IBC
Jurisdictional Code	2016 Connecticut State Building Code
Structure Class	II
Exposure Category	C
Topographic Category	1
Calculated Crest Height	0 ft.

Conclusion

Upon reviewing the results of this analysis, it is our opinion that the structure meets the specified TIA code requirements. The mounts for the proposed carrier are therefore deemed adequate to support the final loading configuration as listed in this report.

If you have any questions, require additional information, or actual conditions differ from those as detailed in this report please contact me via the information below:

Nathaniel R Ober E.I.T.
 Northeast Structural Region Lead | Infinigy
 1033 Watervliet Shaker Road, Albany, NY 12205
 (O) (518) 690-0790 | (M) (303) 704-0322
nober@infinigy.com | www.infinigy.com

Final Configuration Loading

Mount CL (ft)	Rad. HT (ft)	Vert. O/S (ft)	Horiz. O/S (ft)*	Qty	Appurtenance	Carrier
151.0	151.0	0.0	5.0	3	Commscope NNVV-65B-R4	Sprint
			1.5,5.0	6	Alcatel-Lucent RRH2x50-08	
			5.0	3	Alcatel-Lucent 1900MHz 4x45 RRH	
			1.5	3	Nokia AAHC	
			0.0	3	DragonWave Horizon Compact	
			0.0	1	DragonWave A-ANT-23G-1-C	
			0.0	2	Dragon Wave A-ANT-11G-2-C	

*Horizontal Offset is defined as the distance from the left most edge of the mount face horizontal when viewed facing the tower

Structure Usages



Stand off	36.7	Pass
Horizontal	38.5	Pass
Mount Pipe	64.8	Pass
RATING =	64.8	Pass

Assumptions and Limitations

Our structural calculations are completed assuming all information provided to Infinigy Engineering is accurate and applicable to this site. For the purposes of calculations, we assume an overall structure condition of “like new” and all members and connections to be free of corrosion and/or structural defects. The structure owner and/or contractor shall verify the structure’s condition prior to installation of any proposed equipment. If actual conditions differ from those described in this report Infinigy Engineering should be notified immediately to complete a revised evaluation.

Our evaluation is completed using standard TIA, AISC, ACI, and ASCE methods and procedures. Our structural results are proprietary and should not be used by others as their own. Infinigy Engineering is not responsible for decisions made by others that are or are not based on our supplied assumptions and conclusions.

This report is an evaluation of the proposed carriers mount structure only and does not reflect adequacy of the existing tower, other mounts, or coax mounting attachments. These elements are assumed to be adequate for the purposes of this analysis and are assumed to have been installed per their manufacturer requirements.



Envelope Only Solution

Infinigy Engineering PLLC	RMV5-296	
NRO		June 7, 2018 at 11:19 AM
526-104		RMV5-296.r3d

Member Primary Data

	Label	I Joint	J Joint	K Joint	Rotate(deg)	Section/Shape	Type	Design List	Material	Design Rules
1	M1	N2	N1			HSS 4"x4"x1/2"	Beam	None	A53 Gr.B	Typical
2	M2	N4	N3			3" STD Pipe	Beam	None	A53 Gr.B	Typical
3	M3	N6	N5			4" STD Pipe	Beam	None	A53 Gr.B	Typical
4	MP1	N20	N21			2" STD Pipe	Beam	None	A53 Gr.B	Typical
5	MP3	N22	N23			2" STD Pipe	Beam	None	A53 Gr.B	Typical
6	MP2	N20A	N19			2" STD Pipe	Beam	None	A53 Gr.B	Typical

Material Takeoff

	Material	Size	Pieces	Length[in]	Weight[K]
1	Hot Rolled Steel				
2	A53 Gr.B	HSS4x4x8	1	36	0
3	A53 Gr.B	PIPE 2.0	3	288	0
4	A53 Gr.B	PIPE 3.0	1	60	0
5	A53 Gr.B	PIPE 4.0	1	18	0
6	Total HR Steel		6	402	.2

Basic Load Cases

	BLC Description	Category	X Gravity	Y Gravity	Z Gravity	Joint	Point	Distribut..	Area(M...)	Surface...
1	Self Weight	DL		-1			9			
2	Wind Load AZI 000	WLZ					9		1	
3	Wind Load AZI 090	WLX					9		1	
4	Ice Weight	OL1					9	6		
5	Wind + Ice Load AZI 000	OL2					9		1	
6	Wind + Ice Load AZI 090	OL3					9		1	
7	Service Live 1	LL				2				
8	BLC 2 Transient Area Loads	None						5		
9	BLC 3 Transient Area Loads	None						5		
10	BLC 5 Transient Area Loads	None						5		
11	BLC 6 Transient Area Loads	None						5		

Load Combinations

	Description	So...P...	S...	BLCFac..											
1	1.4D	Yes	Y	DL	1.4										
2	1.2D + 1.6W AZI 000	Yes	Y	DL	1.2	W...	1.6								
3	1.2D + 1.6W AZI 030	Yes	Y	DL	1.2	W...	1.3...	W...	.8						
4	1.2D + 1.6W AZI 060	Yes	Y	DL	1.2	W...	.8	W...	1.3...						
5	1.2D + 1.6W AZI 090	Yes	Y	DL	1.2			W...	1.6						
6	1.2D + 1.6W AZI 120	Yes	Y	DL	1.2	W...	-.8	W...	1.3...						
7	1.2D + 1.6W AZI 150	Yes	Y	DL	1.2	W...	-1.3...	W...	.8						
8	1.2D + 1.6W AZI 180	Yes	Y	DL	1.2	W...	-1.6								
9	1.2D + 1.6W AZI 210	Yes	Y	DL	1.2	W...	-1.3...	W...	-.8						
10	1.2D + 1.6W AZI 240	Yes	Y	DL	1.2	W...	-.8	W...	-1.3...						
11	1.2D + 1.6W AZI 270	Yes	Y	DL	1.2			W...	-1.6						
12	1.2D + 1.6W AZI 300	Yes	Y	DL	1.2	W...	.8	W...	-1.3...						
13	1.2D + 1.6W AZI 330	Yes	Y	DL	1.2	W...	1.3...	W...	-.8						
14	0.9D + 1.6W AZI 000	Yes	Y	DL	.9	W...	1.6								
15	0.9D + 1.6W AZI 030	Yes	Y	DL	.9	W...	1.3...	W...	.8						
16	0.9D + 1.6W AZI 060	Yes	Y	DL	.9	W...	.8	W...	1.3...						
17	0.9D + 1.6W AZI 090	Yes	Y	DL	.9			W...	1.6						
18	0.9D + 1.6W AZI 120	Yes	Y	DL	.9	W...	-.8	W...	1.3...						
19	0.9D + 1.6W AZI 150	Yes	Y	DL	.9	W...	-1.3...	W...	.8						

Load Combinations (Continued)

	Description	So...	P...	S...	BLCFac..									
20	0.9D + 1.6W AZI 180	Yes	Y		DL	.9	W...	-1.6						
21	0.9D + 1.6W AZI 210	Yes	Y		DL	.9	W...	-1.3	W...	-.8				
22	0.9D + 1.6W AZI 240	Yes	Y		DL	.9	W...	-.8	W...	-1.3				
23	0.9D + 1.6W AZI 270	Yes	Y		DL	.9	W...		W...	-1.6				
24	0.9D + 1.6W AZI 300	Yes	Y		DL	.9	W...	.8	W...	-1.3				
25	0.9D + 1.6W AZI 330	Yes	Y		DL	.9	W...	1.3	W...	-.8				
26	1.2D + 1.0Di	Yes	Y		DL	1.2	OL1	1						
27	1.2D + 1.0Di + 1.0Wi A...	Yes	Y		DL	1.2	OL1	1	OL2	1				
28	1.2D + 1.0Di + 1.0Wi A...	Yes	Y		DL	1.2	OL1	1	OL2	.866	OL3	.5		
29	1.2D + 1.0Di + 1.0Wi A...	Yes	Y		DL	1.2	OL1	1	OL2	.5	OL3	.866		
30	1.2D + 1.0Di + 1.0Wi A...	Yes	Y		DL	1.2	OL1	1			OL3	1		
31	1.2D + 1.0Di + 1.0Wi A...	Yes	Y		DL	1.2	OL1	1	OL2	-.5	OL3	.866		
32	1.2D + 1.0Di + 1.0Wi A...	Yes	Y		DL	1.2	OL1	1	OL2	-.866	OL3	.5		
33	1.2D + 1.0Di + 1.0Wi A...	Yes	Y		DL	1.2	OL1	1	OL2	-.1				
34	1.2D + 1.0Di + 1.0Wi A...	Yes	Y		DL	1.2	OL1	1	OL2	-.866	OL3	-.5		
35	1.2D + 1.0Di + 1.0Wi A...	Yes	Y		DL	1.2	OL1	1	OL2	-.5	OL3	-.866		
36	1.2D + 1.0Di + 1.0Wi A...	Yes	Y		DL	1.2	OL1	1			OL3	-.1		
37	1.2D + 1.0Di + 1.0Wi A...	Yes	Y		DL	1.2	OL1	1	OL2	.5	OL3	-.866		
38	1.2D + 1.0Di + 1.0Wi A...	Yes	Y		DL	1.2	OL1	1	OL2	.866	OL3	-.5		
39	1.2D + 1.5L + 1.0WL (...)	Yes	Y		DL	1.2	LL	1.5	W...	.111				
40	1.2D + 1.5L + 1.0WL (...)	Yes	Y		DL	1.2	LL	1.5	W...	.096	W...	.056		
41	1.2D + 1.5L + 1.0WL (...)	Yes	Y		DL	1.2	LL	1.5	W...	.056	W...	.096		
42	1.2D + 1.5L + 1.0WL (...)	Yes	Y		DL	1.2	LL	1.5			W...	.111		
43	1.2D + 1.5L + 1.0WL (...)	Yes	Y		DL	1.2	LL	1.5	W...	-.056	W...	.096		
44	1.2D + 1.5L + 1.0WL (...)	Yes	Y		DL	1.2	LL	1.5	W...	-.096	W...	.056		
45	1.2D + 1.5L + 1.0WL (...)	Yes	Y		DL	1.2	LL	1.5	W...	-.111				
46	1.2D + 1.5L + 1.0WL (...)	Yes	Y		DL	1.2	LL	1.5	W...	-.096	W...	-.056		
47	1.2D + 1.5L + 1.0WL (...)	Yes	Y		DL	1.2	LL	1.5	W...	-.056	W...	-.096		
48	1.2D + 1.5L + 1.0WL (...)	Yes	Y		DL	1.2	LL	1.5			W...	-.111		
49	1.2D + 1.5L + 1.0WL (...)	Yes	Y		DL	1.2	LL	1.5	W...	.056	W...	-.096		
50	1.2D + 1.5L + 1.0WL (...)	Yes	Y		DL	1.2	LL	1.5	W...	.096	W...	-.056		

Envelope Joint Reactions

Joint		X [lb]	LC	Y [lb]	LC	Z [lb]	LC	MX [lb-ft]	LC	MY [lb-ft]	LC	MZ [lb-ft]	LC
1	N1	max	5	2170.263	37	2153.988	2	-1568.487	14	3446.751	5	305.952	5
2		min	11	584.533	17	-2153.988	8	-6342.161	33	-3443.696	11	92.775	23
3	Totals:	max	5	2170.263	37	2153.988	2						
4		min	11	584.533	17	-2153.988	8						

Envelope AISC 14th(360-10): LRFD Steel Code Checks

Member	Shape	Code Check	Lo.....	Shear C...	Loc[in]...	LC	phi*Pnc...	phi*Pnt...	phi*...	phi*...	Eqn
1	MP1 PIPE_2.0	.684	48 8	.050	48	20	14916....	32130	1871...	1871....	H1-...
2	MP3 PIPE_2.0	.398	48 8	.039	48	20	14916....	32130	1871...	1871....	H1-...
3	M2 PIPE_3.0	.385	30 2	.097	30	8	57037....	65205	5748...	5748....	H1-...
4	M1 HSS4x...	.367	36058	36 y	30	183372...	189630	2021...	2021....	H1-...
5	MP2 PIPE_2.0	.284	48 8	.027	48	8	14916....	32130	1871...	1871....	H1-...
6	M3 PIPE_4.0	.001	9 9	.001	9	9	92571....	93240	1063...	1063....	H1-...



AMERICAN TOWER®
CORPORATION

Structural Analysis Report

Structure : 149 ft Monopole
ATC Site Name : West Haven & Rt 162 CT, CT
ATC Site Number : 243036
Engineering Number : OAA714853_C3_06
Proposed Carrier : Clearwire
Carrier Site Name : West Haven & Rt 162 CT
Carrier Site Number : CT52XC076
Site Location : 668 Jones Hill Road
West Haven, CT 06516-6311
41.256400,-72.972400
County : New Haven
Date : August 2, 2018
Max Usage : 78%
Result : Pass

Prepared By:
Christiana Lancaster
Structural Engineer I

Reviewed By:

COA: PEC.0001553



Table of Contents

Introduction	1
Supporting Documents	1
Analysis	1
Conclusion.....	1
Existing and Reserved Equipment.....	2
Equipment to be Removed.....	2
Proposed Equipment	2
Structure Usages	3
Foundations	3
Deflection and Sway	3
Standard Conditions	4
Calculations	Attached



Introduction

The purpose of this report is to summarize results of a structural analysis performed on the 149 ft monopole to reflect the change in loading by Clearwire.

Supporting Documents

Tower Drawings	Sabre Job #06-08204, dated August 19, 2005
Foundation Drawing	Sabre Job #06-10095, dated October 12, 2005
Geotechnical Report	EBI Project #61051509, dated July 12, 2005

Analysis

The tower was analyzed using American Tower Corporation's tower analysis software. This program considers an elastic three-dimensional model and second-order effects per ANSI/TIA-222.

Basic Wind Speed:	97 mph (3-Second Gust, V_{asd}) / 125 mph (3-second Gust, V_{ult})
Basic Wind Speed w/ Ice:	50 mph (3-Second Gust) w/ 3/4" radial ice concurrent
Code:	ANSI/TIA-222-G / 2012 IBC / 2016 Connecticut State Building Code
Structure Class:	II
Exposure Category:	B
Topographic Category:	1
Crest Height:	0 ft
Spectral Response:	$S_s = 0.19$, $S_1 = 0.06$
Site Class:	D - Stiff Soil

Conclusion

Based on the analysis results, the structure meets the requirements per the applicable codes listed above. The tower and foundation can support the equipment as described in this report.

If you have any questions or require additional information, please contact American Tower via email at Engineering@americantower.com. Please include the American Tower site name, site number, and engineering number in the subject line for any questions.



Existing and Reserved Equipment

Elevation ¹ (ft)		Qty	Antenna	Mount Type	Lines	Carrier
Mount	RAD					
149.0	151.0	3	DragonWave Horizon Compact	-	(3) 1/2" Coax	Clearwire
		1	DragonWave A-ANT-23G-1-C			
		2	DragonWave A-ANT-11G-2-C			
144.0	144.0	3	Kathrein Smart Bias Tee	Low Profile Platform	(15) 1 5/8" Coax (2) 1 1/4" Hybriflex	T-Mobile
		3	Ericsson KRY 112 14			
		3	Ericsson KRY 112 489/1			
		3	Ericsson RRUS 11 B12			
		3	Commscope SBNHH-1D65A			
		3	Ericsson AIR-32 B2A/B66Aa			
136.0	137.0	3	Alcatel-Lucent RRH2x40-AWS	Low Profile Platform	(12) 1 5/8" Coax (1) 1 5/8" Fiber	Verizon
		3	Antel BXA-171063-12BF-EDIN-X			
		3	Antel BXA-185085/12CF			
		3	Andrew DB854DG65ESX			
		3	Commscope LNX-6514DS-A1M			
	136.0	6	RFS FD9R6004/2C-3L			
		1	RFS DB-T1-6Z-8AB-0Z			
126.0	126.0	1	Raycap DC6-48-60-0-8F	Platform w/ Handrails	(2) 0.78" 8 AWG 6 (1) 0.39" Fiber Trunk (1) 3" Conduit	AT&T Mobility
		3	Ericsson RRUS-11 800MHz			
		3	Ericsson RRUS 32			
		3	CCI CCI-HPA-65R-BUU-H8			
115.0	115.0	3	RFS APXV18-206517S-C	Flush	(6) 1 5/8" Coax	Metro PCS
106.0	106.0	1	Proxim 5054-R-LR	Side Arm	(1) 0.28" RG-6	Other
		1	3' Dish w/ Radome			

Equipment to be Removed

Elevation ¹ (ft)		Qty	Antenna	Mount Type	Lines	Carrier
Mount	RAD					
149.0	151.0	3	Argus LLPX310R	Side Arms	(6) 5/16" Coax	Clearwire
		3	NextNet BTS-2500			

Proposed Equipment

Elevation ¹ (ft)		Qty	Antenna	Mount Type	Lines	Carrier
Mount	RAD					
149.0	154.0	6	Alcatel-Lucent RRH2x50-08	T-Arms	(3) 1 1/4" Hybriflex (1) 1.7" Hybrid	Clearwire
		3	Alcatel-Lucent 1900MHz 4x45 RRH			
		3	Nokia 2.5G MAA - AAHC(64T64R)			
		3	Commscope NNVV-65B-R4			

¹Mount elevation is defined as height above bottom of steel structure to the bottom of mount, RAD elevation is defined as center of antenna above ground level (AGL).

Install proposed coax inside the pole shaft.



Structure Usages

Structural Component	Controlling Usage	Pass/Fail
Anchor Bolts	47%	Pass
Shaft	78%	Pass
Base Plate	37%	Pass

Foundations

Reaction Component	Original Design Reactions	Factored Design Reactions*	Analysis Reactions	% of Design
Moment (Kips-Ft)	2,840.0	3,834.0	2,351.3	61%
Shear (Kips)	26.3	35.5	21.0	59%

* The design reactions are factored by 1.35 per ANSI/TIA-222-G, Sec. 15.5.1

The structure base reactions resulting from this analysis are acceptable when compared to those shown on the original structure drawings, therefore no modification or reinforcement of the foundation will be required.

Deflection and Sway*

Antenna Elevation (ft)	Antenna	Carrier	Deflection (ft)	Sway (Rotation) (°)
149.0	DragonWave A-ANT-23G-1-C	Clearwire	1.878	1.492
	Alcatel-Lucent RRH2x50-08			
	Alcatel-Lucent 1900 MHz 4x45 RRH			
	Nokia 2.5G MAA - AAHC(64T64R)			
	DragonWave A-ANT-11G-2-C			
	Commscope NNVV-65B-R4			
106.0	3' Dish w/ Radome	Other	0.880	1.045

*Deflection and Sway was evaluated considering a design wind speed of 60 mph (3-Second Gust) per ANSI/TIA-222-G



Standard Conditions

All engineering services performed by A.T. Engineering Service, PLLC are prepared on the basis that the information used is current and correct. This information may consist of, but is not limited to the following:

- Information supplied by the client regarding antenna, mounts and feed line loading
- Information from drawings, design and analysis documents, and field notes in the possession of A.T. Engineering Service, PLLC


It is the responsibility of the client to ensure that the information provided to A.T. Engineering Service, PLLC and used in the performance of our engineering services is correct and complete.

All assets of American Tower Corporation, its affiliates and subsidiaries (collectively "American Tower") are inspected at regular intervals. Based upon these inspections and in the absence of information to the contrary, American Tower assumes that all structures were constructed in accordance with the drawings and specifications.

Unless explicitly agreed by both the client and A.T. Engineering Service, PLLC, all services will be performed in accordance with the current revision of ANSI/TIA-222.

All services are performed, results obtained, and recommendations made in accordance with generally accepted engineering principles and practices. A.T. Engineering Service, PLLC is not responsible for the conclusions, opinions and recommendations made by others based on the information supplied herein.

© 2007 - 2018 by ATC IP LLC. All rights reserved.




Job Information	
Pole : 243036	Code: ANSI/TIA-222-G
Location : WEST HAVEN & RT 162 CT, CT	
Description : Tower Model Verified: 12/13/2012	
Client : CLEARWIRE CORPORATION	Structure Class : II
Shape : 18 Sides	Exposure : B
Height : 149.00 (ft)	Topo : 1
Base Elev (ft): 0.00	
Taper: 0.234964(in/ft)	

Sections Properties						
Shaft Section	Length (ft)	Diameter (in)		Thick Joint (in)	Overlap Length (in)	Steel Grade
		Top	Bottom			
1	53.250	39.49	52.01	0.375	0.000	18 Sides 65
2	53.500	28.78	41.35	0.313 Slip Joint	63.000	18 Sides 65
3	51.250	18.00	30.04	0.188 Slip Joint	45.000	18 Sides 65

Discrete Appurtenance			
Attach Elev (ft)	Force Elev (ft)	Qty	Description
149.000	149.000	3	Flat T-Arm
149.000	154.000	3	Nokia 2.5G MAA -
149.000	154.000	3	Alcatel-Lucent 1900 MHz 4x45
149.000	154.000	6	Alcatel-Lucent RRR2x50-08
149.000	154.000	3	Commscope NNVV-65B-R4
149.000	151.000	1	DragonWave A-ANT-23G-1-C
149.000	151.000	3	DragonWave Horizon Compact
149.000	151.000	2	DragonWave A-ANT-11G-2-C
144.000	144.000	1	Flat Low Profile Platform
144.000	144.000	3	Ericsson AIR-32 B2A/B66Aa
144.000	144.000	3	Commscope SBNHH-1D65A
144.000	144.000	3	Ericsson RRUS 11 B12
144.000	144.000	3	Ericsson KRY 112 489/1
144.000	144.000	3	Ericsson KRY 112 14
144.000	144.000	3	Kathrein Smart Bias Tee
136.000	136.000	1	Round Low Profile Platform
136.000	137.000	3	Commscope LNX-6514DS-A1M
136.000	137.000	3	Andrew DB854DG65ESX
136.000	136.000	1	RFS DB-T1-6Z-8AB-0Z
136.000	137.000	3	Antel BXA-185085/12CF
136.000	137.000	3	Amphenol Antel BXA-171063-
136.000	137.000	3	Alcatel-Lucent RRR2x40-AWS
136.000	136.000	6	RFS FD9R6004/2C-3L
126.000	126.000	1	Round Platform w/ Handrails
126.000	126.000	3	CCI CCI-HPA-65R-BUU-H8
126.000	126.000	3	Ericsson RRUS 32
126.000	126.000	3	Ericsson RRUS-11 800 MHz
126.000	126.000	1	Raycap DC6-48-60-0-8F
115.000	115.000	3	RFS APXV18-206517S-C
106.000	106.000	1	Flat Side Arm
106.000	106.000	1	Proxim 5054-R-LR
106.000	106.000	1	3' Dish w/ Radome

Linear Appurtenance			
Elev (ft)		Description	Exposed To Wind
From	To		
4.000	106.0	0.28" RG-6	No
4.000	115.0	1 5/8" Coax	No
4.000	126.0	0.39" Fiber Trunk	No
4.000	126.0	0.78" 8 AWG 6	No
4.000	126.0	3" Conduit	No
4.000	136.0	1 5/8" (1.63"-	No




4.000	136.0	1 5/8" Coax	No
4.000	144.0	1 1/4" Hybriflex	Yes
4.000	144.0	1 5/8" Coax	No
4.000	149.0	1 1/4" Hybriflex	No
4.000	149.0	1.7" (43.2mm)	No
4.000	149.0	1/2" Coax	No

Load Cases	
1.2D + 1.6W	97 mph with No Ice
0.9D + 1.6W	97 mph with No Ice (Reduced DL)
1.2D + 1.0Di + 1.0Wi	50 mph with 0.75 in Radial Ice
(1.2 + 0.2Sds) * DL + E	Seismic Equivalent Lateral Forces Method
(1.2 + 0.2Sds) * DL + E	Seismic Equivalent Modal Analysis Method
(0.9 - 0.2Sds) * DL + E	Seismic (Reduced DL) Equivalent Lateral
(0.9 - 0.2Sds) * DL + E	Seismic (Reduced DL) Equivalent Modal
1.0D + 1.0W	Serviceability 60 mph

Reactions			
Load Case	Moment (kip-ft)	Shear (kip)	Axial (kip)
1.2D + 1.6W	2351.27	21.03	40.05
0.9D + 1.6W	2319.59	21.01	30.03
1.2D + 1.0Di + 1.0Wi	665.25	5.99	61.16
(1.2 + 0.2Sds) * DL + E ELFM	166.21	1.31	40.08
(1.2 + 0.2Sds) * DL + E EMAM	299.57	2.43	40.08
(0.9 - 0.2Sds) * DL + E ELFM	163.44	1.30	27.79
(0.9 - 0.2Sds) * DL + E EMAM	294.20	2.43	27.79
1.0D + 1.0W	557.87	5.02	33.40

Dish Deflections			
Load Case	Attach Elev (ft)	Deflection (in)	Rotation (deg)
1.0D + 1.0W	106.00	10.556	1.045
1.0D + 1.0W	149.00	22.540	1.492
1.0D + 1.0W	149.00	22.540	1.492

Load Case : 1.2D + 1.6W
Max Ratio 78.12% at 101.5 ft



Site Number: 243036

Code: ANSI/TIA-222-G

© 2007 - 2018 by ATC IP LLC. All rights reserved.

Site Name: WEST HAVEN & RT 162 CT, CT Engineering Number: OAA714853_C3_06

8/2/2018 9:22:01 AM

Customer: CLEARWIRE

Analysis Parameters

Location :	NEW HAVEN County, CT	Height (ft) :	149
Code :	ANSI/TIA-222-G	Base Diameter (in) :	52.01
Shape :	18 Sides	Top Diameter (in) :	18.00
Pole Type :	Taper	Taper (in/ft) :	0.235
Pole Manufacturer :	Sabre	Rotation (deg) :	0.00

Ice & Wind Parameters

Structure Class:	II	Design Wind Speed Without Ice:	97 mph
Exposure Category:	B	Design Wind Speed With Ice:	50 mph
Topographic Category:	1	Operational Wind Speed:	60 mph
Crest Height:	0 ft	Design Ice Thickness:	0.75 in

Seismic Parameters

Analysis Method:	Equivalent Modal Analysis & Equivalent Lateral Force Methods		
Site Class:	D - Stiff Soil		
Period Based on Rayleigh Method (sec):	2.54		
T _L (sec):	6	p:	1.3
S _s :	0.188	S ₁ :	0.062
F _a :	1.600	F _v :	2.400
S _{ds} :	0.201	S _{d1} :	0.099
		C _s :	0.030
		C _s Max:	0.030
		C _s Min:	0.030

Load Cases

1.2D + 1.6W	97 mph with No Ice
0.9D + 1.6W	97 mph with No Ice (Reduced DL)
1.2D + 1.0Di + 1.0Wi	50 mph with 0.75 in Radial Ice
(1.2 + 0.2S _{ds}) * DL + E ELFM	Seismic Equivalent Lateral Forces Method
(1.2 + 0.2S _{ds}) * DL + E EMAM	Seismic Equivalent Modal Analysis Method
(0.9 - 0.2S _{ds}) * DL + E ELFM	Seismic (Reduced DL) Equivalent Lateral Forces Method
(0.9 - 0.2S _{ds}) * DL + E EMAM	Seismic (Reduced DL) Equivalent Modal Analysis Method
1.0D + 1.0W	Serviceability 60 mph

Site Number: 243036

Code: ANSI/TIA-222-G

© 2007 - 2018 by ATC IP LLC. All rights reserved.

Site Name: WEST HAVEN & RT 162 CT, CT Engineering Number: OAA714853_C3_06

8/2/2018 9:22:01 AM

Customer: CLEARWIRE

Shaft Section Properties

Sect Info	Length (ft)	Thick (in)	Fy (ksi)	Joint Type	Joint Len (in)	Weight (lb)	Bottom						Top						
							Dia (in)	Elev (ft)	Area (in ²)	Ix (in ⁴)	W/t Ratio	D/t Ratio	Dia (in)	Elev (ft)	Area (in ²)	Ix (in ⁴)	W/t Ratio	D/t Ratio	Taper (in/ft)
1-18	53.250	0.3750	65		0.00	9,787	52.01	0.00	61.46	20701.4	22.69	138.69	39.49	53.25	46.56	9004.7	16.81	105.33	0.234964
2-18	53.500	0.3125	65	Slip	63.00	6,276	41.35	48.00	40.71	8664.4	21.57	132.34	28.78	101.50	28.24	2892.7	14.48	92.11	0.234964
3-18	51.250	0.1875	65	Slip	45.00	2,473	30.04	97.75	17.77	2000.7	26.49	160.22	18.00	149.00	10.60	424.9	15.16	96.00	0.234964
Shaft Weight						18,536													

Discrete Appurtenance Properties

Attach Elev (ft)	Description	Qty	Distance From Face (ft)	Vert Ecc (ft)	Weight (lb)	No Ice EPAa (sf)	Orientation Factor
149.00	Alcatel-Lucent 1900 MHz 4x45 R	3	0.000	5.000	60.00	2.320	0.50
149.00	Alcatel-Lucent RRH2x50-08	6	0.000	5.000	52.90	1.700	0.50
149.00	Commscope NNVV-65B-R4	3	0.000	5.000	77.40	12.270	0.64
149.00	DragonWave A-ANT-11G-2-C	2	0.000	2.000	27.00	4.690	1.00
149.00	DragonWave A-ANT-23G-1-C	1	0.000	2.000	15.00	1.610	1.00
149.00	DragonWave Horizon Compact	3	0.000	2.000	10.60	0.430	0.50
149.00	Flat T-Arm	3	0.000	0.000	250.00	12.900	0.67
149.00	Nokia 2.5G MAA - AAHC(64T64R)	3	0.000	5.000	103.60	4.200	0.64
144.00	Commscope SBNHH-1D65A	3	0.000	0.000	33.50	5.880	0.69
144.00	Ericsson AIR-32 B2A/B66Aa	3	0.000	0.000	132.20	6.510	0.71
144.00	Ericsson KRY 112 14	3	0.000	0.000	12.10	0.580	0.50
144.00	Ericsson KRY 112 489/1	3	0.000	0.000	15.40	0.650	0.50
144.00	Ericsson RRUS 11 B12	3	0.000	0.000	50.70	2.790	0.67
144.00	Flat Low Profile Platform	1	0.000	0.000	1500.00	26.100	1.00
144.00	Kathrein Smart Bias Tee	3	0.000	0.000	3.31	0.090	0.50
136.00	Alcatel-Lucent RRH2x40-AWS	3	0.000	1.000	44.00	2.160	0.50
136.00	Amphenol Antel BXA-171063-	3	0.000	1.000	15.00	4.730	0.72
136.00	Andrew DB854DG65ESX	3	0.000	1.000	18.50	5.250	0.65
136.00	Antel BXA-185085/12CF	3	0.000	1.000	13.00	4.790	0.72
136.00	Commscope LNX-6514DS-A1M	3	0.000	1.000	38.80	8.170	0.69
136.00	RFS DB-T1-6Z-8AB-0Z	1	0.000	0.000	44.00	4.800	0.50
136.00	RFS FD9R6004/2C-3L	6	0.000	0.000	2.60	0.370	0.50
136.00	Round Low Profile Platform	1	0.000	0.000	1500.00	21.700	1.00
126.00	CCI CCI-HPA-65R-BUU-H8	3	0.000	0.000	68.00	12.980	0.67
126.00	Ericsson RRUS 32	3	0.000	0.000	50.80	2.690	0.50
126.00	Ericsson RRUS-11 800 MHz	3	0.000	0.000	54.00	2.520	0.50
126.00	Raycap DC6-48-60-0-8F	1	0.000	0.000	32.80	1.280	1.00
126.00	Round Platform w/ Handrails	1	0.000	0.000	2000.00	27.200	1.00
115.00	RFS APXV18-206517S-C	3	0.000	0.000	26.40	5.160	0.68
106.00	3' Dish w/ Radome	1	0.000	0.000	100.00	6.100	1.00
106.00	Flat Side Arm	1	0.000	0.000	150.00	6.300	1.00
106.00	Proxim 5054-R-LR	1	0.000	0.000	6.00	1.320	1.00
Totals	Num Loadings:32	83			8966.73		

Linear Appurtenance Properties

Elev From (ft)	Elev To (ft)	Qty	Description	Coax Diameter (in)	Coax Weight (lb/ft)	Projected Width Flat (in)	Exposed To Wind	Carrier	
4.00	149.00	3	1 1/4" Hybriflex Cable	1.54	1.00	N	0.00	N	Clearwire
4.00	149.00	1	1.7" (43.2mm) Hybrid	1.70	1.78	N	0.00	N	Clearwire
4.00	149.00	3	1/2" Coax	0.63	0.15	N	0.00	N	Clearwire
4.00	144.00	2	1 1/4" Hybriflex Cable	1.54	1.00	N	1.54	Y	T-Mobile
4.00	144.00	15	1 5/8" Coax	1.98	0.82	N	0.00	N	T-Mobile

Site Number: 243036

Code: ANSI/TIA-222-G

© 2007 - 2018 by ATC IP LLC. All rights reserved.

Site Name: WEST HAVEN & RT 162 CT, CT Engineering Number: OAA714853_C3_06

8/2/2018 9:22:01 AM

Customer: CLEARWIRE

4.00	136.00	1	1 5/8" (1.63"-41.3mm)	1.63	1.61	N	0.00	N	Verizon
4.00	136.00	12	1 5/8" Coax	1.98	0.82	N	0.00	N	Verizon
4.00	126.00	1	0.39" Fiber Trunk	0.39	0.06	N	0.00	N	AT&T Mobility
4.00	126.00	2	0.78" 8 AWG 6	0.78	0.59	N	0.00	N	AT&T Mobility
4.00	126.00	1	3" Conduit	3.50	7.58	N	0.00	N	AT&T Mobility
4.00	115.00	6	1 5/8" Coax	1.98	0.82	N	0.00	N	Metro PCS
4.00	106.00	1	0.28" RG-6	0.28	0.03	N	0.00	N	-

Segment Properties (Max Len : 5. ft)

Seg Top Elev (ft)	Description	Thick (in)	Flat Dia (in)	Area (in ²)	Ix (in ⁴)	W/t Ratio	D/t Ratio	F'y (ksi)	S (in ³)	Z (in ³)	Weight (lb)
0.00		0.3750	52.010	61.456	20,701.4	22.69	138.69	74.7	784.0	0.0	0.0
5.00		0.3750	50.835	60.058	19,320.3	22.14	135.56	75.4	748.6	0.0	1,033.7
10.00		0.3750	49.660	58.659	18,002.0	21.59	132.43	76.0	714.0	0.0	1,009.9
15.00		0.3750	48.485	57.261	16,745.1	21.03	129.29	76.7	680.2	0.0	986.1
20.00		0.3750	47.310	55.863	15,548.1	20.48	126.16	77.3	647.3	0.0	962.3
25.00		0.3750	46.136	54.465	14,409.6	19.93	123.03	78.0	615.2	0.0	938.5
30.00		0.3750	44.961	53.066	13,328.0	19.38	119.90	78.6	583.9	0.0	914.8
35.00		0.3750	43.786	51.668	12,301.9	18.83	116.76	79.3	553.4	0.0	891.0
40.00		0.3750	42.611	50.270	11,329.9	18.27	113.63	79.9	523.7	0.0	867.2
45.00		0.3750	41.436	48.871	10,410.6	17.72	110.50	80.6	494.9	0.0	843.4
48.00	Bot - Section 2	0.3750	40.731	48.032	9,883.6	17.39	108.62	80.9	477.9	0.0	494.6
50.00		0.3750	40.261	47.473	9,542.3	17.17	107.36	81.2	466.8	0.0	600.4
53.25	Top - Section 1	0.3125	40.123	39.485	7,906.5	20.88	128.39	76.8	388.1	0.0	960.8
55.00		0.3125	39.712	39.078	7,664.0	20.64	127.08	77.1	380.1	0.0	233.9
60.00		0.3125	38.537	37.912	6,998.6	19.98	123.32	77.9	357.7	0.0	654.9
65.00		0.3125	37.362	36.747	6,373.0	19.32	119.56	78.7	336.0	0.0	635.1
70.00		0.3125	36.187	35.582	5,785.7	18.66	115.80	79.5	314.9	0.0	615.3
75.00		0.3125	35.012	34.417	5,235.7	17.99	112.04	80.2	294.5	0.0	595.5
80.00		0.3125	33.838	33.251	4,721.7	17.33	108.28	81.0	274.8	0.0	575.6
85.00		0.3125	32.663	32.086	4,242.5	16.67	104.52	81.8	255.8	0.0	555.8
90.00		0.3125	31.488	30.921	3,796.9	16.00	100.76	82.6	237.5	0.0	536.0
95.00		0.3125	30.313	29.756	3,383.6	15.34	97.00	82.6	219.9	0.0	516.2
97.75	Bot - Section 3	0.3125	29.667	29.115	3,169.7	14.98	94.93	82.6	210.4	0.0	275.4
100.0		0.3125	29.138	28.591	3,001.5	14.68	93.24	82.6	202.9	0.0	355.7
101.5	Top - Section 2	0.1875	29.161	17.242	1,828.7	25.66	155.52	71.2	123.5	0.0	233.6
105.0		0.1875	28.338	16.753	1,677.4	24.89	151.14	72.1	116.6	0.0	202.4
106.0		0.1875	28.103	16.613	1,635.7	24.67	149.89	72.4	114.6	0.0	56.8
110.0		0.1875	27.164	16.054	1,476.0	23.78	144.87	73.4	107.0	0.0	222.3
115.0		0.1875	25.989	15.354	1,291.4	22.68	138.61	74.7	97.9	0.0	267.2
117.9		0.1875	25.299	14.944	1,190.5	22.03	134.93	75.5	92.7	0.0	151.4
120.0		0.1875	24.814	14.655	1,122.9	21.57	132.34	76.0	89.1	0.0	103.9
125.0		0.1875	23.639	13.956	969.8	20.47	126.08	77.3	80.8	0.0	243.4
126.0		0.1875	23.404	13.816	940.9	20.25	124.82	77.6	79.2	0.0	47.3
130.0		0.1875	22.464	13.257	831.2	19.36	119.81	78.6	72.9	0.0	184.2
135.0		0.1875	21.290	12.558	706.5	18.26	113.54	79.9	65.4	0.0	219.6
136.0		0.1875	21.055	12.418	683.2	18.04	112.29	80.2	63.9	0.0	42.5
140.0		0.1875	20.115	11.859	595.0	17.15	107.28	81.2	58.3	0.0	165.2
144.0		0.1875	19.175	11.299	514.7	16.27	102.27	82.3	52.9	0.0	157.6
145.0		0.1875	18.940	11.160	495.8	16.05	101.01	82.5	51.6	0.0	38.2
149.0		0.1875	18.000	10.600	424.9	15.16	96.00	82.6	46.5	0.0	148.1
18,536.1											

Load Case: 1.2D + 1.6W	97 mph with No Ice	26 Iterations
Gust Response Factor :1.10		Wind Importance Factor :1.00
Dead Load Factor :1.20		
Wind Load Factor :1.60		

Applied Segment Forces Summary

Seg Elev (ft)	Description	Shaft Forces		Discrete Forces			Linear Forces		Sum of Forces				
		Wind FX (lb)	Dead Load (lb)	Wind FX (lb)	Torsion MY (lb-ft)	Moment MZ (lb-ft)	Dead Load (lb)	Wind FX (lb)	Dead Load (lb)	Wind FX (lb)	Dead Load (lb)	Torsion MY (lb-ft)	Moment MZ (lb)
0.00		199.3	0.0					0.0	0.0	199.3	0.0	0.0	0.0
5.00		394.1	1,240.5					0.0	53.7	394.1	1,294.2	0.0	0.0
10.00		385.0	1,211.9					0.0	268.5	385.0	1,480.4	0.0	0.0
15.00		375.9	1,183.4					0.0	268.5	375.9	1,451.9	0.0	0.0
20.00		366.8	1,154.8					0.0	268.5	366.8	1,423.3	0.0	0.0
25.00		357.7	1,126.3					0.0	268.5	357.7	1,394.8	0.0	0.0
30.00		352.7	1,097.7					0.0	268.5	352.7	1,366.2	0.0	0.0
35.00		354.8	1,069.2					0.0	268.5	354.8	1,337.7	0.0	0.0
40.00		358.7	1,040.6					0.0	268.5	358.7	1,309.1	0.0	0.0
45.00		288.5	1,012.1					0.0	268.5	288.5	1,280.6	0.0	0.0
48.00	Bot - Section 2	181.8	593.5					0.0	161.1	181.8	754.6	0.0	0.0
50.00		192.7	720.5					0.0	107.4	192.7	827.9	0.0	0.0
53.25	Top - Section 1	183.4	1,153.0					0.0	174.5	183.4	1,327.5	0.0	0.0
55.00		247.0	280.7					0.0	94.0	247.0	374.7	0.0	0.0
60.00		364.4	785.9					0.0	268.5	364.4	1,054.4	0.0	0.0
65.00		361.5	762.1					0.0	268.5	361.5	1,030.6	0.0	0.0
70.00		357.6	738.4					0.0	268.5	357.6	1,006.9	0.0	0.0
75.00		352.9	714.6					0.0	268.5	352.9	983.1	0.0	0.0
80.00		347.4	690.8					0.0	268.5	347.4	959.3	0.0	0.0
85.00		341.2	667.0					0.0	268.5	341.2	935.5	0.0	0.0
90.00		334.3	643.2					0.0	268.5	334.3	911.7	0.0	0.0
95.00		254.7	619.4					0.0	268.5	254.7	887.9	0.0	0.0
97.75	Bot - Section 3	162.4	330.5					0.0	147.7	162.4	478.2	0.0	0.0
100.00		121.4	426.9					0.0	120.8	121.4	547.7	0.0	0.0
101.50	Top - Section 2	159.4	280.3					0.0	80.6	159.4	360.8	0.0	0.0
105.00		142.5	242.9					0.0	188.0	142.5	430.9	0.0	0.0
106.00	Appurtenance(s)	155.0	68.1	555.2	0.0	0.0	307.2	0.0	53.7	710.3	429.0	0.0	0.0
110.00		274.1	266.8					0.0	214.7	274.1	481.4	0.0	0.0
115.00	Appurtenance(s)	236.5	320.6	436.0	0.0	0.0	95.0	0.0	268.3	672.6	684.0	0.0	0.0
117.94		145.6	181.7					0.0	140.3	145.6	322.0	0.0	0.0
120.00		199.9	124.6					0.0	98.5	199.9	223.1	0.0	0.0
125.00		168.0	292.1					0.0	238.8	168.0	530.9	0.0	0.0
126.00	Appurtenance(s)	135.2	56.7	2,281.1	0.0	0.0	3,061.4	0.0	47.8	2,416.3	3,165.9	0.0	0.0
130.00		237.5	221.1					0.0	148.7	237.5	369.8	0.0	0.0
135.00		155.0	263.5					0.0	185.9	155.0	449.4	0.0	0.0
136.00	Appurtenance(s)	124.1	51.0	2,840.0	0.0	1,775.0	2,337.0	0.0	37.2	2,964.1	2,425.2	0.0	0.0
140.00		193.9	198.3					0.0	93.7	193.9	292.0	0.0	0.0
144.00	Appurtenance(s)	118.2	189.1	2,341.0	0.0	0.0	2,690.0	0.0	93.7	2,459.3	2,972.8	0.0	0.0
145.00		113.4	45.9					0.0	6.3	113.4	52.1	0.0	0.0
149.00	Appurtenance(s)	90.3	177.7	2,830.6	0.0	8,270.8	2,269.4	0.0	25.1	2,920.9	2,472.2	0.0	0.0
Totals:										21,168.9	40,079.7	0.00	0.00

Site Number: 243036

Code: ANSI/TIA-222-G

© 2007 - 2018 by ATC IP LLC. All rights reserved.

Site Name: WEST HAVEN & RT 162 CT, CT

Engineering Number: OAA714853_C3_06

8/2/2018 9:22:06 AM

Customer: CLEARWIRE

Load Case: 1.2D + 1.6W

97 mph with No Ice

26 Iterations

Gust Response Factor :1.10

Wind Importance Factor :1.00

Dead Load Factor :1.20

Wind Load Factor :1.60

Calculated Forces

Seg	Pu	Vu	Tu	Mu	Mu	Resultant	phi	phi	phi	phi	Total		
Elev	FY (-)	FX (-)	MY	MZ	MX	Moment	Pn	Vn	Tn	Mn	Deflect	Rotation	Ratio
(ft)	(kips)	(kips)	(ft-kips)	(ft-kips)	(ft-kips)	(ft-kips)	(kips)	(kips)	(ft-kips)	(ft-kips)	(in)	(deg)	
0.00	-40.05	-21.03	0.00	-2,351.27	0.00	2,351.27	4,132.29	2,066.14	8,772.59	4,392.82	0.00	0.00	0.545
5.00	-38.70	-20.74	0.00	-2,246.15	0.00	2,246.15	4,073.39	2,036.69	8,449.37	4,230.97	0.08	-0.16	0.540
10.00	-37.16	-20.45	0.00	-2,142.46	0.00	2,142.46	4,012.85	2,006.43	8,128.58	4,070.33	0.34	-0.32	0.536
15.00	-35.65	-20.17	0.00	-2,040.20	0.00	2,040.20	3,950.68	1,975.34	7,810.43	3,911.02	0.76	-0.48	0.531
20.00	-34.18	-19.89	0.00	-1,939.35	0.00	1,939.35	3,886.87	1,943.43	7,495.19	3,753.17	1.36	-0.65	0.526
25.00	-32.73	-19.62	0.00	-1,839.89	0.00	1,839.89	3,821.43	1,910.71	7,183.08	3,596.88	2.14	-0.83	0.520
30.00	-31.30	-19.34	0.00	-1,741.81	0.00	1,741.81	3,754.35	1,877.17	6,874.35	3,442.28	3.10	-1.00	0.514
35.00	-29.91	-19.05	0.00	-1,645.12	0.00	1,645.12	3,685.64	1,842.82	6,569.23	3,289.50	4.24	-1.18	0.508
40.00	-28.55	-18.76	0.00	-1,549.84	0.00	1,549.84	3,615.29	1,807.64	6,267.96	3,138.64	5.58	-1.37	0.502
45.00	-27.23	-18.51	0.00	-1,456.05	0.00	1,456.05	3,543.30	1,771.65	5,970.78	2,989.83	7.12	-1.56	0.495
48.00	-26.45	-18.35	0.00	-1,400.51	0.00	1,400.51	3,499.33	1,749.66	5,794.53	2,901.57	8.13	-1.67	0.490
50.00	-25.59	-18.18	0.00	-1,363.81	0.00	1,363.81	3,469.68	1,734.84	5,677.92	2,843.18	8.85	-1.75	0.487
53.25	-24.24	-18.00	0.00	-1,304.71	0.00	1,304.71	2,730.90	1,365.45	4,467.29	2,236.97	10.09	-1.88	0.592
55.00	-23.83	-17.80	0.00	-1,273.21	0.00	1,273.21	2,712.29	1,356.15	4,390.67	2,198.60	10.80	-1.95	0.588
60.00	-22.72	-17.49	0.00	-1,184.20	0.00	1,184.20	2,658.02	1,329.01	4,173.50	2,089.85	12.97	-2.18	0.575
65.00	-21.63	-17.18	0.00	-1,096.74	0.00	1,096.74	2,602.11	1,301.05	3,959.12	1,982.50	15.38	-2.41	0.562
70.00	-20.57	-16.86	0.00	-1,010.85	0.00	1,010.85	2,544.56	1,272.28	3,747.77	1,876.67	18.03	-2.65	0.547
75.00	-19.54	-16.54	0.00	-926.54	0.00	926.54	2,485.39	1,242.69	3,539.70	1,772.48	20.93	-2.89	0.531
80.00	-18.53	-16.22	0.00	-843.83	0.00	843.83	2,424.57	1,212.29	3,335.13	1,670.04	24.09	-3.13	0.513
85.00	-17.55	-15.90	0.00	-762.71	0.00	762.71	2,362.12	1,181.06	3,134.31	1,569.49	27.49	-3.37	0.494
90.00	-16.59	-15.59	0.00	-683.18	0.00	683.18	2,297.27	1,148.64	2,936.51	1,470.44	31.15	-3.61	0.472
95.00	-15.68	-15.33	0.00	-605.26	0.00	605.26	2,210.70	1,105.35	2,718.30	1,361.17	35.06	-3.85	0.452
97.75	-15.18	-15.16	0.00	-563.11	0.00	563.11	2,163.09	1,081.54	2,601.88	1,302.87	37.32	-3.99	0.439
100.00	-14.62	-15.03	0.00	-529.00	0.00	529.00	2,124.13	1,062.07	2,508.52	1,256.12	39.23	-4.10	0.428
101.50	-14.24	-14.87	0.00	-506.46	0.00	506.46	1,105.19	552.59	1,317.56	659.76	40.52	-4.17	0.781
105.00	-13.79	-14.73	0.00	-454.41	0.00	454.41	1,087.53	543.77	1,259.48	630.68	43.64	-4.34	0.734
106.00	-13.37	-14.03	0.00	-439.68	0.00	439.68	1,082.34	541.17	1,242.93	622.39	44.56	-4.41	0.719
110.00	-12.83	-13.79	0.00	-383.57	0.00	383.57	1,060.92	530.46	1,177.04	589.40	48.38	-4.70	0.664
115.00	-12.15	-13.11	0.00	-314.64	0.00	314.64	1,032.68	516.34	1,095.47	548.55	53.48	-5.04	0.586
117.94	-11.81	-12.97	0.00	-276.11	0.00	276.11	1,015.32	507.66	1,048.03	524.80	56.64	-5.23	0.538
120.00	-11.56	-12.80	0.00	-249.36	0.00	249.36	1,002.79	501.40	1,014.98	508.24	58.92	-5.36	0.503
125.00	-11.01	-12.61	0.00	-185.38	0.00	185.38	971.28	485.64	935.83	468.61	64.68	-5.63	0.408
126.00	-8.08	-9.91	0.00	-172.77	0.00	172.77	964.78	482.39	920.18	460.77	65.87	-5.69	0.384
130.00	-7.70	-9.66	0.00	-133.14	0.00	133.14	938.12	469.06	858.24	429.76	70.70	-5.87	0.318
135.00	-7.25	-9.47	0.00	-84.84	0.00	84.84	903.33	451.67	782.47	391.82	76.95	-6.06	0.225
136.00	-5.15	-6.27	0.00	-73.59	0.00	73.59	896.18	448.09	767.56	384.35	78.22	-6.09	0.197
140.00	-4.87	-6.06	0.00	-48.49	0.00	48.49	866.91	433.46	708.75	354.90	83.36	-6.19	0.142
144.00	-2.18	-3.29	0.00	-24.26	0.00	24.26	836.60	418.30	651.40	326.19	88.57	-6.26	0.077
145.00	-2.14	-3.17	0.00	-20.97	0.00	20.97	828.85	414.43	637.31	319.13	89.88	-6.27	0.068
149.00	0.00	-2.92	0.00	-8.27	0.00	8.27	787.55	393.77	574.90	287.88	95.14	-6.31	0.029

Load Case: 0.9D + 1.6W	97 mph with No Ice (Reduced DL)	25 Iterations
Gust Response Factor :1.10		Wind Importance Factor :1.00
Dead Load Factor :0.90		
Wind Load Factor :1.60		

Applied Segment Forces Summary

Seg Elev (ft)	Description	Shaft Forces		Discrete Forces			Linear Forces		Sum of Forces				
		Wind FX (lb)	Dead Load (lb)	Wind FX (lb)	Torsion MY (lb-ft)	Moment MZ (lb-ft)	Dead Load (lb)	Wind FX (lb)	Dead Load (lb)	Wind FX (lb)	Dead Load (lb)	Torsion MY (lb-ft)	Moment MZ (lb)
0.00		199.3	0.0					0.0	0.0	199.3	0.0	0.0	0.0
5.00		394.1	930.3					0.0	40.3	394.1	970.6	0.0	0.0
10.00		385.0	908.9					0.0	201.4	385.0	1,110.3	0.0	0.0
15.00		375.9	887.5					0.0	201.4	375.9	1,088.9	0.0	0.0
20.00		366.8	866.1					0.0	201.4	366.8	1,067.5	0.0	0.0
25.00		357.7	844.7					0.0	201.4	357.7	1,046.1	0.0	0.0
30.00		352.7	823.3					0.0	201.4	352.7	1,024.7	0.0	0.0
35.00		354.8	801.9					0.0	201.4	354.8	1,003.2	0.0	0.0
40.00		358.7	780.5					0.0	201.4	358.7	981.8	0.0	0.0
45.00		288.5	759.0					0.0	201.4	288.5	960.4	0.0	0.0
48.00	Bot - Section 2	181.8	445.2					0.0	120.8	181.8	566.0	0.0	0.0
50.00		192.7	540.4					0.0	80.5	192.7	621.0	0.0	0.0
53.25	Top - Section 1	183.4	864.8					0.0	130.9	183.4	995.7	0.0	0.0
55.00		247.0	210.5					0.0	70.5	247.0	281.0	0.0	0.0
60.00		364.4	589.5					0.0	201.4	364.4	790.8	0.0	0.0
65.00		361.5	571.6					0.0	201.4	361.5	773.0	0.0	0.0
70.00		357.6	553.8					0.0	201.4	357.6	755.1	0.0	0.0
75.00		352.9	535.9					0.0	201.4	352.9	737.3	0.0	0.0
80.00		347.4	518.1					0.0	201.4	347.4	719.5	0.0	0.0
85.00		341.2	500.2					0.0	201.4	341.2	701.6	0.0	0.0
90.00		334.3	482.4					0.0	201.4	334.3	683.8	0.0	0.0
95.00		254.7	464.6					0.0	201.4	254.7	665.9	0.0	0.0
97.75	Bot - Section 3	162.4	247.9					0.0	110.8	162.4	358.7	0.0	0.0
100.00		121.4	320.2					0.0	90.6	121.4	410.8	0.0	0.0
101.50	Top - Section 2	159.4	210.2					0.0	60.4	159.4	270.6	0.0	0.0
105.00		142.5	182.2					0.0	141.0	142.5	323.2	0.0	0.0
106.00	Appurtenance(s)	155.0	51.1	555.2	0.0	0.0	230.4	0.0	40.3	710.3	321.8	0.0	0.0
110.00		274.1	200.1					0.0	161.0	274.1	361.1	0.0	0.0
115.00	Appurtenance(s)	236.5	240.5	436.0	0.0	0.0	71.3	0.0	201.2	672.6	513.0	0.0	0.0
117.94		145.6	136.3					0.0	105.2	145.6	241.5	0.0	0.0
120.00		199.9	93.5					0.0	73.9	199.9	167.4	0.0	0.0
125.00		168.0	219.1					0.0	179.1	168.0	398.2	0.0	0.0
126.00	Appurtenance(s)	135.2	42.5	2,281.1	0.0	0.0	2,296.1	0.0	35.8	2,416.3	2,374.4	0.0	0.0
130.00		237.5	165.8					0.0	111.5	237.5	277.4	0.0	0.0
135.00		155.0	197.6					0.0	139.4	155.0	337.1	0.0	0.0
136.00	Appurtenance(s)	124.1	38.2	2,840.0	0.0	1,775.0	1,752.7	0.0	27.9	2,964.1	1,818.9	0.0	0.0
140.00		193.9	148.7					0.0	70.3	193.9	219.0	0.0	0.0
144.00	Appurtenance(s)	118.2	141.8	2,341.0	0.0	0.0	2,017.5	0.0	70.3	2,459.3	2,229.6	0.0	0.0
145.00		113.4	34.4					0.0	4.7	113.4	39.1	0.0	0.0
149.00	Appurtenance(s)	90.3	133.3	2,830.6	0.0	8,270.8	1,702.1	0.0	18.8	2,920.9	1,854.2	0.0	0.0
Totals:										21,168.9	30,059.8	0.00	0.00

Load Case: 0.9D + 1.6W

97 mph with No Ice (Reduced DL)

25 Iterations

Gust Response Factor :1.10

Wind Importance Factor :1.00

Dead Load Factor :0.90

Wind Load Factor :1.60

Calculated Forces

Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	phi Pn (kips)	phi Vn (kips)	phi Tn (ft-kips)	phi Mn (ft-kips)	Total Deflect (in)	Rotation (deg)	Ratio
0.00	-30.03	-21.01	0.00	-2,319.59	0.00	2,319.59	4,132.29	2,066.14	8,772.59	4,392.82	0.00	0.00	0.535
5.00	-29.00	-20.69	0.00	-2,214.54	0.00	2,214.54	4,073.39	2,036.69	8,449.37	4,230.97	0.08	-0.16	0.531
10.00	-27.84	-20.38	0.00	-2,111.07	0.00	2,111.07	4,012.85	2,006.43	8,128.58	4,070.33	0.33	-0.32	0.526
15.00	-26.69	-20.08	0.00	-2,009.15	0.00	2,009.15	3,950.68	1,975.34	7,810.43	3,911.02	0.75	-0.48	0.521
20.00	-25.57	-19.77	0.00	-1,908.77	0.00	1,908.77	3,886.87	1,943.43	7,495.19	3,753.17	1.34	-0.64	0.515
25.00	-24.47	-19.48	0.00	-1,809.90	0.00	1,809.90	3,821.43	1,910.71	7,183.08	3,596.88	2.11	-0.81	0.510
30.00	-23.39	-19.18	0.00	-1,712.52	0.00	1,712.52	3,754.35	1,877.17	6,874.35	3,442.28	3.05	-0.99	0.504
35.00	-22.34	-18.88	0.00	-1,616.62	0.00	1,616.62	3,685.64	1,842.82	6,569.23	3,289.50	4.18	-1.17	0.498
40.00	-21.31	-18.56	0.00	-1,522.23	0.00	1,522.23	3,615.29	1,807.64	6,267.96	3,138.64	5.50	-1.35	0.491
45.00	-20.31	-18.31	0.00	-1,429.41	0.00	1,429.41	3,543.30	1,771.65	5,970.78	2,989.83	7.01	-1.53	0.484
48.00	-19.71	-18.14	0.00	-1,374.49	0.00	1,374.49	3,499.33	1,749.66	5,794.53	2,901.57	8.01	-1.65	0.479
50.00	-19.07	-17.96	0.00	-1,338.21	0.00	1,338.21	3,469.68	1,734.84	5,677.92	2,843.18	8.72	-1.73	0.476
53.25	-18.05	-17.78	0.00	-1,279.83	0.00	1,279.83	2,730.90	1,365.45	4,467.29	2,236.97	9.94	-1.85	0.579
55.00	-17.73	-17.57	0.00	-1,248.71	0.00	1,248.71	2,712.29	1,356.15	4,390.67	2,198.60	10.63	-1.92	0.575
60.00	-16.88	-17.25	0.00	-1,160.86	0.00	1,160.86	2,658.02	1,329.01	4,173.50	2,089.85	12.76	-2.15	0.562
65.00	-16.06	-16.92	0.00	-1,074.63	0.00	1,074.63	2,602.11	1,301.05	3,959.12	1,982.50	15.13	-2.37	0.548
70.00	-15.25	-16.59	0.00	-990.05	0.00	990.05	2,544.56	1,272.28	3,747.77	1,876.67	17.74	-2.60	0.534
75.00	-14.47	-16.26	0.00	-907.10	0.00	907.10	2,485.39	1,242.69	3,539.70	1,772.48	20.59	-2.84	0.518
80.00	-13.70	-15.93	0.00	-825.80	0.00	825.80	2,424.57	1,212.29	3,335.13	1,670.04	23.69	-3.07	0.500
85.00	-12.95	-15.61	0.00	-746.13	0.00	746.13	2,362.12	1,181.06	3,134.31	1,569.49	27.03	-3.31	0.481
90.00	-12.23	-15.28	0.00	-668.09	0.00	668.09	2,297.27	1,148.64	2,936.51	1,470.44	30.62	-3.55	0.460
95.00	-11.53	-15.02	0.00	-591.67	0.00	591.67	2,210.70	1,105.35	2,718.30	1,361.17	34.46	-3.78	0.440
97.75	-11.15	-14.86	0.00	-550.35	0.00	550.35	2,163.09	1,081.54	2,601.88	1,302.87	36.68	-3.91	0.428
100.00	-10.73	-14.73	0.00	-516.92	0.00	516.92	2,124.13	1,062.07	2,508.52	1,256.12	38.55	-4.02	0.417
101.50	-10.44	-14.57	0.00	-494.82	0.00	494.82	1,105.19	552.59	1,317.56	659.76	39.82	-4.09	0.760
105.00	-10.10	-14.43	0.00	-443.82	0.00	443.82	1,087.53	543.77	1,259.48	630.68	42.88	-4.26	0.714
106.00	-9.79	-13.73	0.00	-429.40	0.00	429.40	1,082.34	541.17	1,242.93	622.39	43.78	-4.33	0.700
110.00	-9.38	-13.47	0.00	-374.49	0.00	374.49	1,060.92	530.46	1,177.04	589.40	47.53	-4.61	0.645
115.00	-8.87	-12.80	0.00	-307.12	0.00	307.12	1,032.68	516.34	1,095.47	548.55	52.53	-4.94	0.569
117.94	-8.61	-12.66	0.00	-269.52	0.00	269.52	1,015.32	507.66	1,048.03	524.80	55.62	-5.12	0.523
120.00	-8.41	-12.47	0.00	-243.41	0.00	243.41	1,002.79	501.40	1,014.98	508.24	57.86	-5.25	0.488
125.00	-8.00	-12.29	0.00	-181.05	0.00	181.05	971.28	485.64	935.83	468.61	63.50	-5.52	0.395
126.00	-5.85	-9.67	0.00	-168.75	0.00	168.75	964.78	482.39	920.18	460.77	64.66	-5.57	0.373
130.00	-5.57	-9.42	0.00	-130.08	0.00	130.08	938.12	469.06	858.24	429.76	69.40	-5.75	0.309
135.00	-5.23	-9.24	0.00	-82.97	0.00	82.97	903.33	451.67	782.47	391.82	75.52	-5.93	0.218
136.00	-3.72	-6.11	0.00	-71.95	0.00	71.95	896.18	448.09	767.56	384.35	76.77	-5.97	0.192
140.00	-3.52	-5.90	0.00	-47.50	0.00	47.50	866.91	433.46	708.75	354.90	81.80	-6.06	0.138
144.00	-1.56	-3.22	0.00	-23.90	0.00	23.90	836.60	418.30	651.40	326.19	86.90	-6.13	0.075
145.00	-1.53	-3.10	0.00	-20.68	0.00	20.68	828.85	414.43	637.31	319.13	88.19	-6.15	0.067
149.00	0.00	-2.92	0.00	-8.27	0.00	8.27	787.55	393.77	574.90	287.88	93.34	-6.18	0.029

Load Case: 1.2D + 1.0Di + 1.0Wi	50 mph with 0.75 in Radial Ice	25 Iterations
Gust Response Factor :1.10	Ice Dead Load Factor :1.00	Wind Importance Factor :1.00
Dead Load Factor :1.20		Ice Importance Factor :1.00
Wind Load Factor :1.00		

Applied Segment Forces Summary

Seg Elev (ft)	Description	Shaft Forces		Discrete Forces			Linear Forces		Sum of Forces				
		Wind FX (lb)	Dead Load (lb)	Wind FX (lb)	Torsion MY (lb-ft)	Moment MZ (lb-ft)	Dead Load (lb)	Wind FX (lb)	Dead Load (lb)	Wind FX (lb)	Dead Load (lb)	Torsion MY (lb-ft)	Moment MZ (lb)
0.00		63.8	0.0					0.0	0.0	63.8	0.0	0.0	0.0
5.00		126.6	1,617.9					0.0	58.5	126.6	1,676.4	0.0	0.0
10.00		124.3	1,624.7					0.0	296.2	124.3	1,920.9	0.0	0.0
15.00		121.7	1,608.4					0.0	298.1	121.7	1,906.5	0.0	0.0
20.00		119.1	1,584.4					0.0	299.4	119.1	1,883.9	0.0	0.0
25.00		116.5	1,556.5					0.0	300.5	116.5	1,857.0	0.0	0.0
30.00		115.2	1,526.1					0.0	301.4	115.2	1,827.5	0.0	0.0
35.00		116.2	1,494.0					0.0	302.1	116.2	1,796.1	0.0	0.0
40.00		117.8	1,460.6					0.0	302.8	117.8	1,763.3	0.0	0.0
45.00		94.9	1,426.2					0.0	303.4	94.9	1,729.5	0.0	0.0
48.00	Bot - Section 2	59.9	840.2					0.0	182.3	59.9	1,022.5	0.0	0.0
50.00		63.6	886.5					0.0	121.6	63.6	1,008.1	0.0	0.0
53.25	Top - Section 1	60.6	1,419.2					0.0	197.8	60.6	1,617.0	0.0	0.0
55.00		81.7	423.3					0.0	106.6	81.7	529.9	0.0	0.0
60.00		120.8	1,184.4					0.0	304.8	120.8	1,489.2	0.0	0.0
65.00		120.2	1,152.3					0.0	305.2	120.2	1,457.5	0.0	0.0
70.00		119.3	1,119.8					0.0	305.6	119.3	1,425.4	0.0	0.0
75.00		118.1	1,086.9					0.0	306.0	118.1	1,392.9	0.0	0.0
80.00		116.7	1,053.7					0.0	306.4	116.7	1,360.0	0.0	0.0
85.00		115.0	1,020.2					0.0	306.7	115.0	1,326.8	0.0	0.0
90.00		113.1	986.4					0.0	307.0	113.1	1,293.4	0.0	0.0
95.00		86.5	952.4					0.0	307.3	86.5	1,259.6	0.0	0.0
97.75	Bot - Section 3	55.3	510.7					0.0	169.1	55.3	679.9	0.0	0.0
100.00		41.4	574.0					0.0	138.4	41.4	712.4	0.0	0.0
101.50	Top - Section 2	54.5	377.4					0.0	92.3	54.5	469.8	0.0	0.0
105.00		48.7	464.1					0.0	215.5	48.7	679.6	0.0	0.0
106.00	Appurtenance(s)	53.2	131.0	119.1	0.0	0.0	460.5	0.0	61.6	172.4	653.1	0.0	0.0
110.00		94.4	510.8					0.0	246.4	94.4	757.2	0.0	0.0
115.00	Appurtenance(s)	81.8	614.5	89.4	0.0	0.0	435.1	0.0	308.2	171.2	1,357.8	0.0	0.0
117.94		50.5	350.7					0.0	163.8	50.5	514.5	0.0	0.0
120.00		69.7	241.4					0.0	115.1	69.7	356.5	0.0	0.0
125.00		58.7	563.5					0.0	279.1	58.7	842.6	0.0	0.0
126.00	Appurtenance(s)	47.5	110.6	587.7	0.0	0.0	5,172.5	0.0	55.9	635.2	5,338.9	0.0	0.0
130.00		83.9	429.1					0.0	181.2	83.9	610.3	0.0	0.0
135.00		54.9	511.8					0.0	226.7	54.9	738.5	0.0	0.0
136.00	Appurtenance(s)	44.3	100.3	695.3	0.0	375.0	4,693.1	0.0	45.4	739.6	4,838.7	0.0	0.0
140.00		69.5	387.6					0.0	126.5	69.5	514.1	0.0	0.0
144.00	Appurtenance(s)	42.6	370.8	569.3	0.0	0.0	4,579.6	0.0	126.7	611.9	5,077.1	0.0	0.0
145.00		41.2	90.9					0.0	6.3	41.2	97.1	0.0	0.0
149.00	Appurtenance(s)	32.8	349.9	652.5	0.0	1,747.5	5,009.5	0.0	25.1	685.3	5,384.4	0.0	0.0
Totals:									6,029.71	61,166.2	0.00	0.00	

Site Number: 243036

Code: ANSI/TIA-222-G

© 2007 - 2018 by ATC IP LLC. All rights reserved.

Site Name: WEST HAVEN & RT 162 CT, CT Engineering Number: OAA714853_C3_06

8/2/2018 9:22:14 AM

Customer: CLEARWIRE

Load Case: 1.2D + 1.0Di + 1.0Wi

50 mph with 0.75 in Radial Ice

25 Iterations

Gust Response Factor :1.10

Ice Dead Load Factor :1.00

Wind Importance Factor :1.00

Dead Load Factor :1.20

Ice Importance Factor :1.00

Wind Load Factor :1.00

Calculated Forces

Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	phi Pn (kips)	phi Vn (kips)	phi Tn (ft-kips)	phi Mn (ft-kips)	Total Deflect (in)	Rotation (deg)	Ratio
0.00	-61.16	-5.99	0.00	-665.25	0.00	665.25	4,132.29	2,066.14	8,772.59	4,392.82	0.00	0.00	0.166
5.00	-59.48	-5.91	0.00	-635.30	0.00	635.30	4,073.39	2,036.69	8,449.37	4,230.97	0.02	-0.04	0.165
10.00	-57.56	-5.83	0.00	-605.75	0.00	605.75	4,012.85	2,006.43	8,128.58	4,070.33	0.10	-0.09	0.163
15.00	-55.65	-5.75	0.00	-576.61	0.00	576.61	3,950.68	1,975.34	7,810.43	3,911.02	0.21	-0.14	0.162
20.00	-53.76	-5.67	0.00	-547.86	0.00	547.86	3,886.87	1,943.43	7,495.19	3,753.17	0.38	-0.18	0.160
25.00	-51.90	-5.59	0.00	-519.51	0.00	519.51	3,821.43	1,910.71	7,183.08	3,596.88	0.60	-0.23	0.158
30.00	-50.06	-5.51	0.00	-491.55	0.00	491.55	3,754.35	1,877.17	6,874.35	3,442.28	0.88	-0.28	0.156
35.00	-48.26	-5.43	0.00	-463.98	0.00	463.98	3,685.64	1,842.82	6,569.23	3,289.50	1.20	-0.33	0.154
40.00	-46.50	-5.34	0.00	-436.83	0.00	436.83	3,615.29	1,807.64	6,267.96	3,138.64	1.58	-0.39	0.152
45.00	-44.76	-5.27	0.00	-410.11	0.00	410.11	3,543.30	1,771.65	5,970.78	2,989.83	2.01	-0.44	0.150
48.00	-43.74	-5.22	0.00	-394.30	0.00	394.30	3,499.33	1,749.66	5,794.53	2,901.57	2.30	-0.47	0.148
50.00	-42.73	-5.17	0.00	-383.85	0.00	383.85	3,469.68	1,734.84	5,677.92	2,843.18	2.50	-0.50	0.147
53.25	-41.11	-5.12	0.00	-367.04	0.00	367.04	2,730.90	1,365.45	4,467.29	2,236.97	2.85	-0.53	0.179
55.00	-40.58	-5.06	0.00	-358.08	0.00	358.08	2,712.29	1,356.15	4,390.67	2,198.60	3.05	-0.55	0.178
60.00	-39.08	-4.97	0.00	-332.78	0.00	332.78	2,658.02	1,329.01	4,173.50	2,089.85	3.66	-0.62	0.174
65.00	-37.62	-4.88	0.00	-307.93	0.00	307.93	2,602.11	1,301.05	3,959.12	1,982.50	4.34	-0.68	0.170
70.00	-36.19	-4.78	0.00	-283.55	0.00	283.55	2,544.56	1,272.28	3,747.77	1,876.67	5.09	-0.75	0.165
75.00	-34.80	-4.68	0.00	-259.64	0.00	259.64	2,485.39	1,242.69	3,539.70	1,772.48	5.91	-0.81	0.160
80.00	-33.43	-4.59	0.00	-236.22	0.00	236.22	2,424.57	1,212.29	3,335.13	1,670.04	6.80	-0.88	0.155
85.00	-32.10	-4.49	0.00	-213.28	0.00	213.28	2,362.12	1,181.06	3,134.31	1,569.49	7.76	-0.95	0.149
90.00	-30.81	-4.39	0.00	-190.83	0.00	190.83	2,297.27	1,148.64	2,936.51	1,470.44	8.79	-1.02	0.143
95.00	-29.55	-4.31	0.00	-168.88	0.00	168.88	2,210.70	1,105.35	2,718.30	1,361.17	9.89	-1.08	0.137
97.75	-28.86	-4.26	0.00	-157.04	0.00	157.04	2,163.09	1,081.54	2,601.88	1,302.87	10.52	-1.12	0.134
100.00	-28.15	-4.21	0.00	-147.46	0.00	147.46	2,124.13	1,062.07	2,508.52	1,256.12	11.06	-1.15	0.131
101.50	-27.68	-4.17	0.00	-141.14	0.00	141.14	1,105.19	552.59	1,317.56	659.76	11.42	-1.17	0.239
105.00	-27.00	-4.12	0.00	-126.56	0.00	126.56	1,087.53	543.77	1,259.48	630.68	12.30	-1.22	0.226
106.00	-26.35	-3.96	0.00	-122.44	0.00	122.44	1,082.34	541.17	1,242.93	622.39	12.56	-1.24	0.221
110.00	-25.59	-3.88	0.00	-106.62	0.00	106.62	1,060.92	530.46	1,177.04	589.40	13.63	-1.32	0.205
115.00	-24.23	-3.71	0.00	-87.20	0.00	87.20	1,032.68	516.34	1,095.47	548.55	15.07	-1.41	0.182
117.94	-23.71	-3.67	0.00	-76.30	0.00	76.30	1,015.32	507.66	1,048.03	524.80	15.95	-1.47	0.169
120.00	-23.35	-3.61	0.00	-68.74	0.00	68.74	1,002.79	501.40	1,014.98	508.24	16.59	-1.50	0.159
125.00	-22.51	-3.55	0.00	-50.69	0.00	50.69	971.28	485.64	935.83	468.61	18.21	-1.58	0.131
126.00	-17.19	-2.77	0.00	-47.14	0.00	47.14	964.78	482.39	920.18	460.77	18.54	-1.59	0.120
130.00	-16.58	-2.69	0.00	-36.05	0.00	36.05	938.12	469.06	858.24	429.76	19.90	-1.64	0.102
135.00	-15.84	-2.62	0.00	-22.62	0.00	22.62	903.33	451.67	782.47	391.82	21.64	-1.69	0.075
136.00	-11.03	-1.74	0.00	-19.63	0.00	19.63	896.18	448.09	767.56	384.35	22.00	-1.70	0.063
140.00	-10.51	-1.66	0.00	-12.67	0.00	12.67	866.91	433.46	708.75	354.90	23.44	-1.73	0.048
144.00	-5.46	-0.89	0.00	-6.04	0.00	6.04	836.60	418.30	651.40	326.19	24.89	-1.75	0.025
145.00	-5.36	-0.85	0.00	-5.15	0.00	5.15	828.85	414.43	637.31	319.13	25.26	-1.75	0.023
149.00	0.00	-0.69	0.00	-1.75	0.00	1.75	787.55	393.77	574.90	287.88	26.73	-1.76	0.006

Load Case: 1.0D + 1.0W	Serviceability 60 mph	24 Iterations
Gust Response Factor :1.10		Wind Importance Factor :1.00
Dead Load Factor :1.00		
Wind Load Factor :1.00		

Applied Segment Forces Summary

Seg Elev (ft)	Description	Shaft Forces		Discrete Forces			Linear Forces		Sum of Forces				
		Wind FX (lb)	Dead Load (lb)	Wind FX (lb)	Torsion MY (lb-ft)	Moment MZ (lb-ft)	Dead Load (lb)	Wind FX (lb)	Dead Load (lb)	Wind FX (lb)	Dead Load (lb)	Torsion MY (lb-ft)	Moment MZ (lb)
0.00		47.7	0.0					0.0	0.0	47.7	0.0	0.0	0.0
5.00		94.2	1,033.7					0.0	44.8	94.2	1,078.5	0.0	0.0
10.00		92.1	1,009.9					0.0	223.8	92.1	1,233.7	0.0	0.0
15.00		89.9	986.1					0.0	223.8	89.9	1,209.9	0.0	0.0
20.00		87.7	962.3					0.0	223.8	87.7	1,186.1	0.0	0.0
25.00		85.5	938.5					0.0	223.8	85.5	1,162.3	0.0	0.0
30.00		84.3	914.8					0.0	223.8	84.3	1,138.5	0.0	0.0
35.00		84.8	891.0					0.0	223.8	84.8	1,114.7	0.0	0.0
40.00		85.8	867.2					0.0	223.8	85.8	1,090.9	0.0	0.0
45.00		69.0	843.4					0.0	223.8	69.0	1,067.1	0.0	0.0
48.00	Bot - Section 2	43.5	494.6					0.0	134.3	43.5	628.9	0.0	0.0
50.00		46.1	600.4					0.0	89.5	46.1	689.9	0.0	0.0
53.25	Top - Section 1	43.9	960.8					0.0	145.4	43.9	1,106.3	0.0	0.0
55.00		59.1	233.9					0.0	78.3	59.1	312.2	0.0	0.0
60.00		87.1	654.9					0.0	223.8	87.1	878.7	0.0	0.0
65.00		86.4	635.1					0.0	223.8	86.4	858.9	0.0	0.0
70.00		85.5	615.3					0.0	223.8	85.5	839.0	0.0	0.0
75.00		84.4	595.5					0.0	223.8	84.4	819.2	0.0	0.0
80.00		83.1	575.6					0.0	223.8	83.1	799.4	0.0	0.0
85.00		81.6	555.8					0.0	223.8	81.6	779.6	0.0	0.0
90.00		80.0	536.0					0.0	223.8	80.0	759.7	0.0	0.0
95.00		60.9	516.2					0.0	223.8	60.9	739.9	0.0	0.0
97.75	Bot - Section 3	38.8	275.4					0.0	123.1	38.8	398.5	0.0	0.0
100.00		29.0	355.7					0.0	100.7	29.0	456.4	0.0	0.0
101.50	Top - Section 2	38.1	233.6					0.0	67.1	38.1	300.7	0.0	0.0
105.00		34.1	202.4					0.0	156.6	34.1	359.1	0.0	0.0
106.00	Appurtenance(s)	37.1	56.8	132.8	0.0	0.0	256.0	0.0	44.8	169.8	357.5	0.0	0.0
110.00		65.5	222.3					0.0	178.9	65.5	401.2	0.0	0.0
115.00	Appurtenance(s)	56.6	267.2	104.3	0.0	0.0	79.2	0.0	223.6	160.8	570.0	0.0	0.0
117.94		34.8	151.4					0.0	116.9	34.8	268.3	0.0	0.0
120.00		47.8	103.9					0.0	82.1	47.8	186.0	0.0	0.0
125.00		40.2	243.4					0.0	199.0	40.2	442.4	0.0	0.0
126.00	Appurtenance(s)	32.3	47.3	545.5	0.0	0.0	2,551.2	0.0	39.8	577.8	2,638.3	0.0	0.0
130.00		56.8	184.2					0.0	123.9	56.8	308.2	0.0	0.0
135.00		37.1	219.6					0.0	154.9	37.1	374.5	0.0	0.0
136.00	Appurtenance(s)	29.7	42.5	679.1	0.0	424.5	1,947.5	0.0	31.0	708.8	2,021.0	0.0	0.0
140.00		46.4	165.2					0.0	78.1	46.4	243.3	0.0	0.0
144.00	Appurtenance(s)	28.3	157.6	559.8	0.0	0.0	2,241.6	0.0	78.1	588.1	2,477.4	0.0	0.0
145.00		27.1	38.2					0.0	5.2	27.1	43.4	0.0	0.0
149.00	Appurtenance(s)	21.6	148.1	676.9	0.0	1,977.8	1,891.2	0.0	20.9	698.5	2,060.2	0.0	0.0
Totals:									5,062.19	33,399.8	0.00	0.00	

Site Number: 243036

Code: ANSI/TIA-222-G

© 2007 - 2018 by ATC IP LLC. All rights reserved.

Site Name: WEST HAVEN & RT 162 CT, CT Engineering Number: OAA714853_C3_06

8/2/2018 9:22:19 AM

Customer: CLEARWIRE

Load Case: 1.0D + 1.0W

Serviceability 60 mph

24 Iterations

Gust Response Factor :1.10

Wind Importance Factor :1.00

Dead Load Factor :1.00

Wind Load Factor :1.00

Calculated Forces

Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	phi Pn (kips)	phi Vn (kips)	phi Tn (ft-kips)	phi Mn (ft-kips)	Total Deflect (in)	Rotation (deg)	Ratio
0.00	-33.40	-5.02	0.00	-557.87	0.00	557.87	4,132.29	2,066.14	8,772.59	4,392.82	0.00	0.00	0.135
5.00	-32.32	-4.95	0.00	-532.75	0.00	532.75	4,073.39	2,036.69	8,449.37	4,230.97	0.02	-0.04	0.134
10.00	-31.08	-4.88	0.00	-507.99	0.00	507.99	4,012.85	2,006.43	8,128.58	4,070.33	0.08	-0.08	0.133
15.00	-29.87	-4.81	0.00	-483.59	0.00	483.59	3,950.68	1,975.34	7,810.43	3,911.02	0.18	-0.11	0.131
20.00	-28.68	-4.74	0.00	-459.55	0.00	459.55	3,886.87	1,943.43	7,495.19	3,753.17	0.32	-0.16	0.130
25.00	-27.51	-4.67	0.00	-435.86	0.00	435.86	3,821.43	1,910.71	7,183.08	3,596.88	0.51	-0.20	0.128
30.00	-26.37	-4.60	0.00	-412.52	0.00	412.52	3,754.35	1,877.17	6,874.35	3,442.28	0.73	-0.24	0.127
35.00	-25.25	-4.53	0.00	-389.53	0.00	389.53	3,685.64	1,842.82	6,569.23	3,289.50	1.01	-0.28	0.125
40.00	-24.16	-4.46	0.00	-366.88	0.00	366.88	3,615.29	1,807.64	6,267.96	3,138.64	1.32	-0.32	0.124
45.00	-23.09	-4.39	0.00	-344.60	0.00	344.60	3,543.30	1,771.65	5,970.78	2,989.83	1.69	-0.37	0.122
48.00	-22.46	-4.36	0.00	-331.42	0.00	331.42	3,499.33	1,749.66	5,794.53	2,901.57	1.93	-0.40	0.121
50.00	-21.77	-4.31	0.00	-322.71	0.00	322.71	3,469.68	1,734.84	5,677.92	2,843.18	2.10	-0.42	0.120
53.25	-20.66	-4.27	0.00	-308.68	0.00	308.68	2,730.90	1,365.45	4,467.29	2,236.97	2.39	-0.45	0.146
55.00	-20.35	-4.22	0.00	-301.21	0.00	301.21	2,712.29	1,356.15	4,390.67	2,198.60	2.56	-0.46	0.145
60.00	-19.46	-4.15	0.00	-280.10	0.00	280.10	2,658.02	1,329.01	4,173.50	2,089.85	3.07	-0.52	0.141
65.00	-18.60	-4.07	0.00	-259.37	0.00	259.37	2,602.11	1,301.05	3,959.12	1,982.50	3.64	-0.57	0.138
70.00	-17.76	-3.99	0.00	-239.02	0.00	239.02	2,544.56	1,272.28	3,747.77	1,876.67	4.27	-0.63	0.134
75.00	-16.94	-3.92	0.00	-219.06	0.00	219.06	2,485.39	1,242.69	3,539.70	1,772.48	4.96	-0.68	0.130
80.00	-16.14	-3.84	0.00	-199.48	0.00	199.48	2,424.57	1,212.29	3,335.13	1,670.04	5.71	-0.74	0.126
85.00	-15.35	-3.76	0.00	-180.29	0.00	180.29	2,362.12	1,181.06	3,134.31	1,569.49	6.51	-0.80	0.121
90.00	-14.59	-3.69	0.00	-161.48	0.00	161.48	2,297.27	1,148.64	2,936.51	1,470.44	7.38	-0.86	0.116
95.00	-13.85	-3.62	0.00	-143.06	0.00	143.06	2,210.70	1,105.35	2,718.30	1,361.17	8.31	-0.91	0.111
97.75	-13.45	-3.59	0.00	-133.09	0.00	133.09	2,163.09	1,081.54	2,601.88	1,302.87	8.84	-0.94	0.108
100.00	-12.99	-3.55	0.00	-125.02	0.00	125.02	2,124.13	1,062.07	2,508.52	1,256.12	9.29	-0.97	0.106
101.50	-12.69	-3.52	0.00	-119.69	0.00	119.69	1,105.19	552.59	1,317.56	659.76	9.60	-0.99	0.193
105.00	-12.33	-3.48	0.00	-107.39	0.00	107.39	1,087.53	543.77	1,259.48	630.68	10.34	-1.03	0.182
106.00	-11.97	-3.32	0.00	-103.90	0.00	103.90	1,082.34	541.17	1,242.93	622.39	10.56	-1.04	0.178
110.00	-11.57	-3.26	0.00	-90.64	0.00	90.64	1,060.92	530.46	1,177.04	589.40	11.46	-1.11	0.165
115.00	-11.00	-3.10	0.00	-74.36	0.00	74.36	1,032.68	516.34	1,095.47	548.55	12.67	-1.19	0.146
117.94	-10.73	-3.06	0.00	-65.26	0.00	65.26	1,015.32	507.66	1,048.03	524.80	13.42	-1.24	0.135
120.00	-10.54	-3.02	0.00	-58.94	0.00	58.94	1,002.79	501.40	1,014.98	508.24	13.96	-1.27	0.127
125.00	-10.10	-2.98	0.00	-43.84	0.00	43.84	971.28	485.64	935.83	468.61	15.32	-1.33	0.104
126.00	-7.47	-2.34	0.00	-40.86	0.00	40.86	964.78	482.39	920.18	460.77	15.60	-1.35	0.096
130.00	-7.17	-2.28	0.00	-31.49	0.00	31.49	938.12	469.06	858.24	429.76	16.75	-1.39	0.081
135.00	-6.79	-2.24	0.00	-20.08	0.00	20.08	903.33	451.67	782.47	391.82	18.23	-1.43	0.059
136.00	-4.79	-1.48	0.00	-17.42	0.00	17.42	896.18	448.09	767.56	384.35	18.53	-1.44	0.051
140.00	-4.55	-1.43	0.00	-11.49	0.00	11.49	866.91	433.46	708.75	354.90	19.75	-1.46	0.038
144.00	-2.08	-0.78	0.00	-5.76	0.00	5.76	836.60	418.30	651.40	326.19	20.98	-1.48	0.020
145.00	-2.04	-0.75	0.00	-4.98	0.00	4.98	828.85	414.43	637.31	319.13	21.29	-1.48	0.018
149.00	0.00	-0.70	0.00	-1.98	0.00	1.98	787.55	393.77	574.90	287.88	22.54	-1.49	0.007

Equivalent Lateral Forces Method Analysis

(Based on ASCE7-10 Chapters 11, 12, 15)

Spectral Response Acceleration for Short Period (S_s):	0.19
Spectral Response Acceleration at 1.0 Second Period (S_1):	0.06
Long-Period Transition Period (T_L):	6
Importance Factor (I_E):	1.00
Site Coefficient F_a :	1.60
Site Coefficient F_v :	2.40
Response Modification Coefficient (R):	1.50
Design Spectral Response Acceleration at Short Period (S_{ds}):	0.20
Design Spectral Response Acceleration at 1.0 Second Period (S_{d1}):	0.10
Seismic Response Coefficient (C_s):	0.03
Upper Limit C_s	0.03
Lower Limit C_s	0.03
Period based on Rayleigh Method (sec):	2.54
Redundancy Factor (ρ):	1.30
Seismic Force Distribution Exponent (k):	2.00
Total Unfactored Dead Load:	33.40 k
Seismic Base Shear (E):	1.30 k

Load Case (1.2 + 0.2Sds) * DL + E ELFM Seismic Equivalent Lateral Forces Method

Segment	Height Above Base (ft)	Weight (lb)	W_z (lb-ft)	C_{vx}	Horizontal Force (lb)	Vertical Force (lb)
39	147.00	169	3,652	0.013	17	210
38	144.50	43	907	0.003	4	54
37	142.00	236	4,753	0.017	22	292
36	138.00	243	4,634	0.016	21	302
35	135.50	73	1,349	0.005	6	91
34	132.50	375	6,575	0.023	30	464
33	128.00	308	5,049	0.018	23	382
32	125.50	87	1,371	0.005	6	108
31	122.50	442	6,639	0.023	30	549
30	118.97	186	2,632	0.009	12	231
29	116.47	268	3,640	0.013	16	333
28	112.50	491	6,212	0.022	28	609
27	108.00	401	4,680	0.016	21	498
26	105.50	102	1,130	0.004	5	126
25	103.25	359	3,828	0.013	17	445
24	100.75	301	3,052	0.011	14	373
23	98.88	456	4,462	0.016	20	566
22	96.38	399	3,701	0.013	17	494
21	92.50	740	6,331	0.022	29	918
20	87.50	760	5,817	0.020	26	942
19	82.50	780	5,306	0.018	24	967
18	77.50	799	4,801	0.017	22	991
17	72.50	819	4,306	0.015	20	1,016

Site Number: 243036

Code: ANSI/TIA-222-G

© 2007 - 2018 by ATC IP LLC. All rights reserved.

Site Name: WEST HAVEN & RT 162 CT, CT

Engineering Number: OAA714853_C3_06

8/2/2018 9:22:19 AM

Customer: CLEARWIRE

16	67.50	839	3,823	0.013	17	1,041
15	62.50	859	3,355	0.012	15	1,065
14	57.50	879	2,905	0.010	13	1,090
13	54.13	312	915	0.003	4	387
12	51.63	1,106	2,948	0.010	13	1,372
11	49.00	690	1,657	0.006	8	856
10	46.50	629	1,360	0.005	6	780
9	42.50	1,067	1,928	0.007	9	1,323
8	37.50	1,091	1,534	0.005	7	1,353
7	32.50	1,115	1,177	0.004	5	1,382
6	27.50	1,139	861	0.003	4	1,412
5	22.50	1,162	588	0.002	3	1,441
4	17.50	1,186	363	0.001	2	1,471
3	12.50	1,210	189	0.001	1	1,500
2	7.50	1,234	69	0.000	0	1,530
1	2.50	1,078	7	0.000	0	1,337
DragonWave Horizon C	149.00	32	706	0.002	3	39
DragonWave A-ANT-23G	149.00	15	333	0.001	2	19
Alcatel-Lucent RRH2x	149.00	317	7,047	0.025	32	394
Alcatel-Lucent 1900	149.00	180	3,996	0.014	18	223
Nokia 2.5G MAA - AAH	149.00	311	6,900	0.024	31	385
DragonWave A-ANT-11G	149.00	54	1,199	0.004	5	67
Commscope NNVV-65B-R	149.00	232	5,155	0.018	23	288
Flat T-Arm	149.00	750	16,651	0.058	75	930
Kathrein Smart Bias	144.00	10	206	0.001	1	12
Ericsson KRY 112 14	144.00	36	753	0.003	3	45
Ericsson KRY 112 489	144.00	46	958	0.003	4	57
Ericsson RRUS 11 B12	144.00	152	3,154	0.011	14	189
Commscope SBNHH-1D65	144.00	101	2,084	0.007	9	125
Ericsson AIR-32 B2A/	144.00	397	8,224	0.029	37	492
Flat Low Profile Pla	144.00	1,500	31,104	0.108	141	1,860
RFS FD9R6004/2C-3L	136.00	16	289	0.001	1	19
Alcatel-Lucent RRH2x	136.00	132	2,441	0.008	11	164
Amphenol Antel BXA-	136.00	45	832	0.003	4	56
Antel BXA-185085/12C	136.00	39	721	0.003	3	48
RFS DB-T1-6Z-8AB-OZ	136.00	44	814	0.003	4	55
Andrew DB854DG65ESX	136.00	56	1,027	0.004	5	69
Commscope LNX-6514DS	136.00	116	2,153	0.007	10	144
Round Low Profile PI	136.00	1,500	27,744	0.097	126	1,860
Raycap DC6-48-60-0-8	126.00	33	521	0.002	2	41
Ericsson RRUS-11 800	126.00	162	2,572	0.009	12	201
Ericsson RRUS 32	126.00	152	2,420	0.008	11	189
CCI CCI-HPA-65R-BUU-	126.00	204	3,239	0.011	15	253
Round Platform w/ Ha	126.00	2,000	31,752	0.110	144	2,480
RFS APXV18-206517S-C	115.00	79	1,047	0.004	5	98
Proxim 5054-R-LR	106.00	6	67	0.000	0	7
3' Dish w/ Radome	106.00	100	1,124	0.004	5	124
Flat Side Arm	106.00	150	1,685	0.006	8	186
		33,400	287,423	1.000	1,303	41,419

Load Case (0.9 - 0.2Sds) * DL + E ELFM

Seismic (Reduced DL) Equivalent Lateral Forces Method

Segment	Height Above Base (ft)	Weight (lb)	W _z (lb-ft)	C _{vx}	Horizontal Force (lb)	Vertical Force (lb)
39	147.00	169	3,652	0.013	17	145
38	144.50	43	907	0.003	4	37
37	142.00	236	4,753	0.017	22	203
36	138.00	243	4,634	0.016	21	209
35	135.50	73	1,349	0.005	6	63
34	132.50	375	6,575	0.023	30	322

33	128.00	308	5,049	0.018	23	265
32	125.50	87	1,371	0.005	6	75
31	122.50	442	6,639	0.023	30	380
30	118.97	186	2,632	0.009	12	160
29	116.47	268	3,640	0.013	16	231
28	112.50	491	6,212	0.022	28	422
27	108.00	401	4,680	0.016	21	345
26	105.50	102	1,130	0.004	5	87
25	103.25	359	3,828	0.013	17	309
24	100.75	301	3,052	0.011	14	259
23	98.88	456	4,462	0.016	20	392
22	96.38	399	3,701	0.013	17	343
21	92.50	740	6,331	0.022	29	636
20	87.50	760	5,817	0.020	26	653
19	82.50	780	5,306	0.018	24	670
18	77.50	799	4,801	0.017	22	687
17	72.50	819	4,306	0.015	20	704
16	67.50	839	3,823	0.013	17	721
15	62.50	859	3,355	0.012	15	739
14	57.50	879	2,905	0.010	13	756
13	54.13	312	915	0.003	4	268
12	51.63	1,106	2,948	0.010	13	951
11	49.00	690	1,657	0.006	8	593
10	46.50	629	1,360	0.005	6	541
9	42.50	1,067	1,928	0.007	9	918
8	37.50	1,091	1,534	0.005	7	938
7	32.50	1,115	1,177	0.004	5	959
6	27.50	1,139	861	0.003	4	979
5	22.50	1,162	588	0.002	3	999
4	17.50	1,186	363	0.001	2	1,020
3	12.50	1,210	189	0.001	1	1,040
2	7.50	1,234	69	0.000	0	1,061
1	2.50	1,078	7	0.000	0	927
DragonWave Horizon C	149.00	32	706	0.002	3	27
DragonWave A-ANT-23G	149.00	15	333	0.001	2	13
Alcatel-Lucent RRH2x	149.00	317	7,047	0.025	32	273
Alcatel-Lucent 1900	149.00	180	3,996	0.014	18	155
Nokia 2.5G MAA - AAH	149.00	311	6,900	0.024	31	267
DragonWave A-ANT-11G	149.00	54	1,199	0.004	5	46
Commscope NNVV-65B-R	149.00	232	5,155	0.018	23	200
Flat T-Arm	149.00	750	16,651	0.058	75	645
Kathrein Smart Bias	144.00	10	206	0.001	1	9
Ericsson KRY 112 14	144.00	36	753	0.003	3	31
Ericsson KRY 112 489	144.00	46	958	0.003	4	40
Ericsson RRUS 11 B12	144.00	152	3,154	0.011	14	131
Commscope SBNHH-1D65	144.00	101	2,084	0.007	9	86
Ericsson AIR-32 B2A/	144.00	397	8,224	0.029	37	341
Flat Low Profile Pla	144.00	1,500	31,104	0.108	141	1,290
RFS FD9R6004/2C-3L	136.00	16	289	0.001	1	13
Alcatel-Lucent RRH2x	136.00	132	2,441	0.008	11	114
Amphenol Antel BXA-	136.00	45	832	0.003	4	39
Antel BXA-185085/12C	136.00	39	721	0.003	3	34
RFS DB-T1-6Z-8AB-0Z	136.00	44	814	0.003	4	38
Andrew DB854DG65ESX	136.00	56	1,027	0.004	5	48
Commscope LNX-6514DS	136.00	116	2,153	0.007	10	100
Round Low Profile PI	136.00	1,500	27,744	0.097	126	1,290
Raycap DC6-48-60-0-8	126.00	33	521	0.002	2	28
Ericsson RRUS-11 800	126.00	162	2,572	0.009	12	139
Ericsson RRUS 32	126.00	152	2,420	0.008	11	131
CCI CCI-HPA-65R-BUU-	126.00	204	3,239	0.011	15	175
Round Platform w/ Ha	126.00	2,000	31,752	0.110	144	1,720
RFS APXV18-206517S-C	115.00	79	1,047	0.004	5	68
Proxim 5054-R-LR	106.00	6	67	0.000	0	5
3' Dish w/ Radome	106.00	100	1,124	0.004	5	86

Site Number: 243036

Code: ANSI/TIA-222-G © 2007 - 2018 by ATC IP LLC. All rights reserved.

Site Name: WEST HAVEN & RT 162 CT, CT Engineering Number: OAA714853_C3_06

8/2/2018 9:22:19 AM

Customer: CLEARWIRE

Flat Side Arm	106.00	150	1,685	0.006	8	129
		33,400	287,423	1.000	1,303	28,720

Load Case (1.2 + 0.2Sds) * DL + E ELFM Seismic Equivalent Lateral Forces Method

Calculated Forces

Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	phi Pn (kips)	phi Vn (kips)	phi Tn (ft-kips)	phi Mn (ft-kips)	Total Deflect (in)	Rotation (deg)	Ratio
0.00	-40.08	-1.31	0.00	-166.21	0.00	166.21	4,132.29	2,066.14	8,772.59	4,392.82	0.00	0.00	0.048
5.00	-38.55	-1.31	0.00	-159.69	0.00	159.69	4,073.39	2,036.69	8,449.37	4,230.97	0.01	-0.01	0.047
10.00	-37.05	-1.32	0.00	-153.12	0.00	153.12	4,012.85	2,006.43	8,128.58	4,070.33	0.02	-0.02	0.047
15.00	-35.58	-1.32	0.00	-146.53	0.00	146.53	3,950.68	1,975.34	7,810.43	3,911.02	0.05	-0.03	0.046
20.00	-34.14	-1.33	0.00	-139.90	0.00	139.90	3,886.87	1,943.43	7,495.19	3,753.17	0.10	-0.05	0.046
25.00	-32.73	-1.33	0.00	-133.27	0.00	133.27	3,821.43	1,910.71	7,183.08	3,596.88	0.15	-0.06	0.046
30.00	-31.34	-1.33	0.00	-126.62	0.00	126.62	3,754.35	1,877.17	6,874.35	3,442.28	0.22	-0.07	0.045
35.00	-29.99	-1.33	0.00	-119.97	0.00	119.97	3,685.64	1,842.82	6,569.23	3,289.50	0.30	-0.09	0.045
40.00	-28.67	-1.32	0.00	-113.32	0.00	113.32	3,615.29	1,807.64	6,267.96	3,138.64	0.40	-0.10	0.044
45.00	-27.89	-1.32	0.00	-106.70	0.00	106.70	3,543.30	1,771.65	5,970.78	2,989.83	0.51	-0.11	0.044
48.00	-27.03	-1.32	0.00	-102.74	0.00	102.74	3,499.33	1,749.66	5,794.53	2,901.57	0.58	-0.12	0.043
50.00	-25.66	-1.30	0.00	-100.11	0.00	100.11	3,469.68	1,734.84	5,677.92	2,843.18	0.64	-0.13	0.043
53.25	-25.27	-1.30	0.00	-95.87	0.00	95.87	2,730.90	1,365.45	4,467.29	2,236.97	0.73	-0.14	0.052
55.00	-24.18	-1.29	0.00	-93.59	0.00	93.59	2,712.29	1,356.15	4,390.67	2,198.60	0.78	-0.14	0.051
60.00	-23.12	-1.28	0.00	-87.14	0.00	87.14	2,658.02	1,329.01	4,173.50	2,089.85	0.93	-0.16	0.050
65.00	-22.08	-1.27	0.00	-80.74	0.00	80.74	2,602.11	1,301.05	3,959.12	1,982.50	1.11	-0.18	0.049
70.00	-21.06	-1.25	0.00	-74.42	0.00	74.42	2,544.56	1,272.28	3,747.77	1,876.67	1.30	-0.19	0.048
75.00	-20.07	-1.23	0.00	-68.17	0.00	68.17	2,485.39	1,242.69	3,539.70	1,772.48	1.51	-0.21	0.047
80.00	-19.10	-1.21	0.00	-62.02	0.00	62.02	2,424.57	1,212.29	3,335.13	1,670.04	1.74	-0.23	0.045
85.00	-18.16	-1.18	0.00	-55.98	0.00	55.98	2,362.12	1,181.06	3,134.31	1,569.49	1.99	-0.25	0.043
90.00	-17.24	-1.16	0.00	-50.06	0.00	50.06	2,297.27	1,148.64	2,936.51	1,470.44	2.26	-0.26	0.042
95.00	-16.75	-1.14	0.00	-44.28	0.00	44.28	2,210.70	1,105.35	2,718.30	1,361.17	2.54	-0.28	0.040
97.75	-16.18	-1.12	0.00	-41.14	0.00	41.14	2,163.09	1,081.54	2,601.88	1,302.87	2.71	-0.29	0.039
100.00	-15.81	-1.11	0.00	-38.62	0.00	38.62	2,124.13	1,062.07	2,508.52	1,256.12	2.85	-0.30	0.038
101.50	-15.36	-1.09	0.00	-36.96	0.00	36.96	1,105.19	552.59	1,317.56	659.76	2.94	-0.30	0.070
105.00	-15.24	-1.09	0.00	-33.15	0.00	33.15	1,087.53	543.77	1,259.48	630.68	3.17	-0.32	0.067
106.00	-14.42	-1.05	0.00	-32.06	0.00	32.06	1,082.34	541.17	1,242.93	622.39	3.24	-0.32	0.065
110.00	-13.81	-1.02	0.00	-27.86	0.00	27.86	1,060.92	530.46	1,177.04	589.40	3.52	-0.34	0.060
115.00	-13.38	-1.01	0.00	-22.74	0.00	22.74	1,032.68	516.34	1,095.47	548.55	3.89	-0.37	0.054
117.94	-13.15	-0.99	0.00	-19.78	0.00	19.78	1,015.32	507.66	1,048.03	524.80	4.12	-0.38	0.051
120.00	-12.60	-0.96	0.00	-17.73	0.00	17.73	1,002.79	501.40	1,014.98	508.24	4.29	-0.39	0.047
125.00	-12.49	-0.96	0.00	-12.92	0.00	12.92	971.28	485.64	935.83	468.61	4.71	-0.41	0.040
126.00	-8.95	-0.73	0.00	-11.96	0.00	11.96	964.78	482.39	920.18	460.77	4.79	-0.41	0.035
130.00	-8.48	-0.70	0.00	-9.04	0.00	9.04	938.12	469.06	858.24	429.76	5.15	-0.43	0.030
135.00	-8.39	-0.69	0.00	-5.56	0.00	5.56	903.33	451.67	782.47	391.82	5.60	-0.44	0.023
136.00	-5.68	-0.49	0.00	-4.86	0.00	4.86	896.18	448.09	767.56	384.35	5.69	-0.44	0.019
140.00	-5.39	-0.46	0.00	-2.92	0.00	2.92	866.91	433.46	708.75	354.90	6.06	-0.45	0.014
144.00	-2.55	-0.23	0.00	-1.06	0.00	1.06	836.60	418.30	651.40	326.19	6.44	-0.45	0.006
145.00	-2.34	-0.21	0.00	-0.83	0.00	0.83	828.85	414.43	637.31	319.13	6.53	-0.45	0.005
149.00	0.00	-0.19	0.00	0.00	0.00	0.00	787.55	393.77	574.90	287.88	6.91	-0.45	0.000

Load Case (0.9 - 0.2Sds) * DL + E ELMF

Seismic (Reduced DL) Equivalent Lateral Forces Method

Calculated Forces

Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	phi Pn (kips)	phi Vn (kips)	phi Tn (ft-kips)	phi Mn (ft-kips)	Total Deflect (in)	Rotation (deg)	Ratio
0.00	-27.79	-1.30	0.00	-163.44	0.00	163.44	4,132.29	2,066.14	8,772.59	4,392.82	0.00	0.00	0.044
5.00	-26.73	-1.31	0.00	-156.91	0.00	156.91	4,073.39	2,036.69	8,449.37	4,230.97	0.01	-0.01	0.044
10.00	-25.69	-1.31	0.00	-150.37	0.00	150.37	4,012.85	2,006.43	8,128.58	4,070.33	0.02	-0.02	0.043
15.00	-24.67	-1.32	0.00	-143.80	0.00	143.80	3,950.68	1,975.34	7,810.43	3,911.02	0.05	-0.03	0.043
20.00	-23.67	-1.32	0.00	-137.22	0.00	137.22	3,886.87	1,943.43	7,495.19	3,753.17	0.10	-0.05	0.043
25.00	-22.69	-1.32	0.00	-130.63	0.00	130.63	3,821.43	1,910.71	7,183.08	3,596.88	0.15	-0.06	0.042
30.00	-21.73	-1.32	0.00	-124.04	0.00	124.04	3,754.35	1,877.17	6,874.35	3,442.28	0.22	-0.07	0.042
35.00	-20.79	-1.31	0.00	-117.46	0.00	117.46	3,685.64	1,842.82	6,569.23	3,289.50	0.30	-0.08	0.041
40.00	-19.88	-1.31	0.00	-110.89	0.00	110.89	3,615.29	1,807.64	6,267.96	3,138.64	0.39	-0.10	0.041
45.00	-19.34	-1.30	0.00	-104.36	0.00	104.36	3,543.30	1,771.65	5,970.78	2,989.83	0.50	-0.11	0.040
48.00	-18.74	-1.30	0.00	-100.45	0.00	100.45	3,499.33	1,749.66	5,794.53	2,901.57	0.57	-0.12	0.040
50.00	-17.79	-1.28	0.00	-97.85	0.00	97.85	3,469.68	1,734.84	5,677.92	2,843.18	0.62	-0.12	0.040
53.25	-17.52	-1.28	0.00	-93.68	0.00	93.68	2,730.90	1,365.45	4,467.29	2,236.97	0.71	-0.13	0.048
55.00	-16.77	-1.27	0.00	-91.43	0.00	91.43	2,712.29	1,356.15	4,390.67	2,198.60	0.76	-0.14	0.048
60.00	-16.03	-1.26	0.00	-85.08	0.00	85.08	2,658.02	1,329.01	4,173.50	2,089.85	0.92	-0.16	0.047
65.00	-15.31	-1.24	0.00	-78.79	0.00	78.79	2,602.11	1,301.05	3,959.12	1,982.50	1.09	-0.17	0.046
70.00	-14.60	-1.23	0.00	-72.58	0.00	72.58	2,544.56	1,272.28	3,747.77	1,876.67	1.28	-0.19	0.044
75.00	-13.91	-1.21	0.00	-66.45	0.00	66.45	2,485.39	1,242.69	3,539.70	1,772.48	1.48	-0.21	0.043
80.00	-13.24	-1.18	0.00	-60.43	0.00	60.43	2,424.57	1,212.29	3,335.13	1,670.04	1.71	-0.22	0.042
85.00	-12.59	-1.16	0.00	-54.51	0.00	54.51	2,362.12	1,181.06	3,134.31	1,569.49	1.95	-0.24	0.040
90.00	-11.95	-1.13	0.00	-48.72	0.00	48.72	2,297.27	1,148.64	2,936.51	1,470.44	2.21	-0.26	0.038
95.00	-11.61	-1.11	0.00	-43.07	0.00	43.07	2,210.70	1,105.35	2,718.30	1,361.17	2.49	-0.27	0.037
97.75	-11.22	-1.09	0.00	-40.01	0.00	40.01	2,163.09	1,081.54	2,601.88	1,302.87	2.65	-0.28	0.036
100.00	-10.96	-1.08	0.00	-37.55	0.00	37.55	2,124.13	1,062.07	2,508.52	1,256.12	2.79	-0.29	0.035
101.50	-10.65	-1.06	0.00	-35.93	0.00	35.93	1,105.19	552.59	1,317.56	659.76	2.88	-0.30	0.064
105.00	-10.56	-1.06	0.00	-32.21	0.00	32.21	1,087.53	543.77	1,259.48	630.68	3.10	-0.31	0.061
106.00	-10.00	-1.02	0.00	-31.15	0.00	31.15	1,082.34	541.17	1,242.93	622.39	3.17	-0.31	0.059
110.00	-9.58	-1.00	0.00	-27.06	0.00	27.06	1,060.92	530.46	1,177.04	589.40	3.44	-0.33	0.055
115.00	-9.28	-0.98	0.00	-22.07	0.00	22.07	1,032.68	516.34	1,095.47	548.55	3.81	-0.36	0.049
117.94	-9.12	-0.97	0.00	-19.20	0.00	19.20	1,015.32	507.66	1,048.03	524.80	4.03	-0.37	0.046
120.00	-8.74	-0.94	0.00	-17.21	0.00	17.21	1,002.79	501.40	1,014.98	508.24	4.19	-0.38	0.043
125.00	-8.66	-0.93	0.00	-12.54	0.00	12.54	971.28	485.64	935.83	468.61	4.60	-0.40	0.036
126.00	-6.20	-0.71	0.00	-11.61	0.00	11.61	964.78	482.39	920.18	460.77	4.69	-0.40	0.032
130.00	-5.88	-0.68	0.00	-8.78	0.00	8.78	938.12	469.06	858.24	429.76	5.03	-0.42	0.027
135.00	-5.82	-0.67	0.00	-5.39	0.00	5.39	903.33	451.67	782.47	391.82	5.47	-0.43	0.020
136.00	-3.94	-0.47	0.00	-4.72	0.00	4.72	896.18	448.09	767.56	384.35	5.56	-0.43	0.017
140.00	-3.73	-0.45	0.00	-2.83	0.00	2.83	866.91	433.46	708.75	354.90	5.93	-0.44	0.012
144.00	-1.77	-0.22	0.00	-1.03	0.00	1.03	836.60	418.30	651.40	326.19	6.29	-0.44	0.005
145.00	-1.62	-0.20	0.00	-0.81	0.00	0.81	828.85	414.43	637.31	319.13	6.39	-0.44	0.005
149.00	0.00	-0.19	0.00	0.00	0.00	0.00	787.55	393.77	574.90	287.88	6.75	-0.44	0.000

Equivalent Modal Forces Analysis

(Based on ASCE7-10 Chapters 11, 12 & 15 and ANSI/TIA-G, section 2.7)

Spectral Response Acceleration for Short Period (S_s):	0.19
Spectral Response Acceleration at 1.0 Second Period (S_1):	0.06
Importance Factor (I_E):	1.00
Site Coefficient F_a :	1.60
Site Coefficient F_v :	2.40
Response Modification Coefficient (R):	1.50
Design Spectral Response Acceleration at Short Period (S_{ds}):	0.20
Design Spectral Response Acceleration at 1.0 Second Period (S_{d1}):	0.10
Period Based on Rayleigh Method (sec):	2.54
Redundancy Factor (p):	1.30

Load Case (1.2 + 0.2Sds) * DL + E EMAM Seismic Equivalent Modal Analysis Method

Segment	Height Above Base (ft)	Weight (lb)	a	b	c	Saz	Horizontal Force (lb)	Vertical Force (lb)
39	147.00	169	1.840	1.725	1.047	0.345	51	210
38	144.50	43	1.778	1.438	0.939	0.305	12	54
37	142.00	236	1.717	1.186	0.840	0.268	55	292
36	138.00	243	1.621	0.846	0.699	0.212	45	302
35	135.50	73	1.563	0.669	0.621	0.180	11	91
34	132.50	375	1.495	0.488	0.536	0.144	47	464
33	128.00	308	1.395	0.274	0.426	0.096	26	382
32	125.50	87	1.341	0.181	0.373	0.072	5	108
31	122.50	442	1.278	0.091	0.317	0.047	18	549
30	118.97	186	1.205	0.009	0.258	0.020	3	231
29	116.47	268	1.155	-0.034	0.222	0.004	1	333
28	112.50	491	1.077	-0.082	0.173	-0.018	-8	609
27	108.00	401	0.993	-0.112	0.128	-0.036	-13	498
26	105.50	102	0.948	-0.119	0.107	-0.044	-4	126
25	103.25	359	0.908	-0.122	0.090	-0.049	-15	445
24	100.75	301	0.864	-0.120	0.074	-0.053	-14	373
23	98.88	456	0.832	-0.117	0.064	-0.054	-21	566
22	96.38	399	0.791	-0.110	0.051	-0.054	-19	494
21	92.50	740	0.728	-0.095	0.036	-0.050	-32	918
20	87.50	760	0.652	-0.071	0.021	-0.038	-25	942
19	82.50	780	0.579	-0.045	0.012	-0.021	-14	967
18	77.50	799	0.511	-0.020	0.008	-0.001	-1	991
17	72.50	819	0.447	0.002	0.006	0.019	13	1,016
16	67.50	839	0.388	0.022	0.007	0.035	25	1,041
15	62.50	859	0.333	0.037	0.010	0.046	34	1,065
14	57.50	879	0.281	0.049	0.014	0.053	40	1,090
13	54.13	312	0.249	0.055	0.017	0.055	15	387
12	51.63	1,106	0.227	0.059	0.020	0.057	54	1,372
11	49.00	690	0.204	0.062	0.023	0.057	34	856
10	46.50	629	0.184	0.065	0.025	0.057	31	780
9	42.50	1,067	0.154	0.068	0.030	0.057	52	1,323
8	37.50	1,091	0.120	0.070	0.034	0.056	53	1,353
7	32.50	1,115	0.090	0.071	0.038	0.054	52	1,382
6	27.50	1,139	0.064	0.072	0.041	0.053	52	1,412

Site Number: 243036

Code: ANSI/TIA-222-G

© 2007 - 2018 by ATC IP LLC. All rights reserved.

Site Name: WEST HAVEN & RT 162 CT, CT

Engineering Number: OAA714853_C3_06

8/2/2018 9:22:19 AM

Customer: CLEARWIRE

5	22.50	1,162	0.043	0.071	0.042	0.051	52	1,441
4	17.50	1,186	0.026	0.067	0.040	0.049	50	1,471
3	12.50	1,210	0.013	0.059	0.034	0.044	46	1,500
2	7.50	1,234	0.005	0.044	0.025	0.035	38	1,530
1	2.50	1,078	0.001	0.018	0.010	0.017	16	1,337
DragonWave Horizon C	149.00	32	1.890	1.980	1.140	0.379	10	39
DragonWave A-ANT-23G	149.00	15	1.890	1.980	1.140	0.379	5	19
Alcatel-Lucent RRH2x	149.00	317	1.890	1.980	1.140	0.379	104	394
Alcatel-Lucent 1900	149.00	180	1.890	1.980	1.140	0.379	59	223
Nokia 2.5G MAA - AAH	149.00	311	1.890	1.980	1.140	0.379	102	385
DragonWave A-ANT-11G	149.00	54	1.890	1.980	1.140	0.379	18	67
Commscope NNVV-	149.00	232	1.890	1.980	1.140	0.379	76	288
Flat T-Arm	149.00	750	1.890	1.980	1.140	0.379	246	930
Kathrein Smart Bias	144.00	10	1.765	1.385	0.919	0.298	3	12
Ericsson KRY 112 14	144.00	36	1.765	1.385	0.919	0.298	9	45
Ericsson KRY 112 489	144.00	46	1.765	1.385	0.919	0.298	12	57
Ericsson RRUS 11 B12	144.00	152	1.765	1.385	0.919	0.298	39	189
Commscope SBNHH-	144.00	101	1.765	1.385	0.919	0.298	26	125
Ericsson AIR-32 B2A/	144.00	397	1.765	1.385	0.919	0.298	102	492
Flat Low Profile Pla	144.00	1,500	1.765	1.385	0.919	0.298	387	1,860
RFS FD9R6004/2C-3L	136.00	16	1.575	0.702	0.636	0.186	3	19
Alcatel-Lucent RRH2x	136.00	132	1.575	0.702	0.636	0.186	21	164
Amphenol Antel BXA-	136.00	45	1.575	0.702	0.636	0.186	7	56
Antel BXA-185085/12C	136.00	39	1.575	0.702	0.636	0.186	6	48
RFS DB-T1-6Z-8AB-0Z	136.00	44	1.575	0.702	0.636	0.186	7	55
Andrew DB854DG65ESX	136.00	56	1.575	0.702	0.636	0.186	9	69
Commscope LNX-	136.00	116	1.575	0.702	0.636	0.186	19	144
Round Low Profile PI	136.00	1,500	1.575	0.702	0.636	0.186	242	1,860
Raycap DC6-48-60-0-8	126.00	33	1.352	0.198	0.384	0.077	2	41
Ericsson RRUS-11 800	126.00	162	1.352	0.198	0.384	0.077	11	201
Ericsson RRUS 32	126.00	152	1.352	0.198	0.384	0.077	10	189
CCI CCI-HPA-65R-BUU-	126.00	204	1.352	0.198	0.384	0.077	14	253
Round Platform w/ Ha	126.00	2,000	1.352	0.198	0.384	0.077	134	2,480
RFS APXV18-206517S-C	115.00	79	1.126	-0.054	0.203	-0.005	0	98
Proxim 5054-R-LR	106.00	6	0.957	-0.118	0.111	-0.043	0	7
3' Dish w/ Radome	106.00	100	0.957	-0.118	0.111	-0.043	-4	124
Flat Side Arm	106.00	150	0.957	-0.118	0.111	-0.043	-6	186
		33,400	78.926	38.487	30.553	8.928	2,441	41,419

Load Case (0.9 - 0.2Sds) * DL + E EMAM

Seismic (Reduced DL) Equivalent Modal Analysis Method

Segment	Height Above Base (ft)	Weight (lb)	a	b	c	Saz	Horizontal Force (lb)	Vertical Force (lb)
39	147.00	169	1.840	1.725	1.047	0.345	51	145
38	144.50	43	1.778	1.438	0.939	0.305	12	37
37	142.00	236	1.717	1.186	0.840	0.268	55	203
36	138.00	243	1.621	0.846	0.699	0.212	45	209
35	135.50	73	1.563	0.669	0.621	0.180	11	63
34	132.50	375	1.495	0.488	0.536	0.144	47	322
33	128.00	308	1.395	0.274	0.426	0.096	26	265
32	125.50	87	1.341	0.181	0.373	0.072	5	75
31	122.50	442	1.278	0.091	0.317	0.047	18	380
30	118.97	186	1.205	0.009	0.258	0.020	3	160
29	116.47	268	1.155	-0.034	0.222	0.004	1	231
28	112.50	491	1.077	-0.082	0.173	-0.018	-8	422
27	108.00	401	0.993	-0.112	0.128	-0.036	-13	345
26	105.50	102	0.948	-0.119	0.107	-0.044	-4	87
25	103.25	359	0.908	-0.122	0.090	-0.049	-15	309
24	100.75	301	0.864	-0.120	0.074	-0.053	-14	259

23	98.88	456	0.832	-0.117	0.064	-0.054	-21	392
22	96.38	399	0.791	-0.110	0.051	-0.054	-19	343
21	92.50	740	0.728	-0.095	0.036	-0.050	-32	636
20	87.50	760	0.652	-0.071	0.021	-0.038	-25	653
19	82.50	780	0.579	-0.045	0.012	-0.021	-14	670
18	77.50	799	0.511	-0.020	0.008	-0.001	-1	687
17	72.50	819	0.447	0.002	0.006	0.019	13	704
16	67.50	839	0.388	0.022	0.007	0.035	25	721
15	62.50	859	0.333	0.037	0.010	0.046	34	739
14	57.50	879	0.281	0.049	0.014	0.053	40	756
13	54.13	312	0.249	0.055	0.017	0.055	15	268
12	51.63	1,106	0.227	0.059	0.020	0.057	54	951
11	49.00	690	0.204	0.062	0.023	0.057	34	593
10	46.50	629	0.184	0.065	0.025	0.057	31	541
9	42.50	1,067	0.154	0.068	0.030	0.057	52	918
8	37.50	1,091	0.120	0.070	0.034	0.056	53	938
7	32.50	1,115	0.090	0.071	0.038	0.054	52	959
6	27.50	1,139	0.064	0.072	0.041	0.053	52	979
5	22.50	1,162	0.043	0.071	0.042	0.051	52	999
4	17.50	1,186	0.026	0.067	0.040	0.049	50	1,020
3	12.50	1,210	0.013	0.059	0.034	0.044	46	1,040
2	7.50	1,234	0.005	0.044	0.025	0.035	38	1,061
1	2.50	1,078	0.001	0.018	0.010	0.017	16	927
DragonWave Horizon C	149.00	32	1.890	1.980	1.140	0.379	10	27
DragonWave A-ANT-23G	149.00	15	1.890	1.980	1.140	0.379	5	13
Alcatel-Lucent RRH2x	149.00	317	1.890	1.980	1.140	0.379	104	273
Alcatel-Lucent 1900	149.00	180	1.890	1.980	1.140	0.379	59	155
Nokia 2.5G MAA - AAH	149.00	311	1.890	1.980	1.140	0.379	102	267
DragonWave A-ANT-11G	149.00	54	1.890	1.980	1.140	0.379	18	46
Commscope NNVV-Flat T-Arm	149.00	232	1.890	1.980	1.140	0.379	76	200
Kathrein Smart Bias	144.00	10	1.765	1.385	0.919	0.298	3	9
Ericsson KRY 112 14	144.00	36	1.765	1.385	0.919	0.298	9	31
Ericsson KRY 112 489	144.00	46	1.765	1.385	0.919	0.298	12	40
Ericsson RRUS 11 B12	144.00	152	1.765	1.385	0.919	0.298	39	131
Commscope SBNHH-	144.00	101	1.765	1.385	0.919	0.298	26	86
Ericsson AIR-32 B2A/	144.00	397	1.765	1.385	0.919	0.298	102	341
Flat Low Profile Pla	144.00	1,500	1.765	1.385	0.919	0.298	387	1,290
RFS FD9R6004/2C-3L	136.00	16	1.575	0.702	0.636	0.186	3	13
Alcatel-Lucent RRH2x	136.00	132	1.575	0.702	0.636	0.186	21	114
Amphenol Antel BXA-	136.00	45	1.575	0.702	0.636	0.186	7	39
Antel BXA-185085/12C	136.00	39	1.575	0.702	0.636	0.186	6	34
RFS DB-T1-6Z-8AB-OZ	136.00	44	1.575	0.702	0.636	0.186	7	38
Andrew DB854DG65ESX	136.00	56	1.575	0.702	0.636	0.186	9	48
Commscope LNX-	136.00	116	1.575	0.702	0.636	0.186	19	100
Round Low Profile PI	136.00	1,500	1.575	0.702	0.636	0.186	242	1,290
Raycap DC6-48-60-0-8	126.00	33	1.352	0.198	0.384	0.077	2	28
Ericsson RRUS-11 800	126.00	162	1.352	0.198	0.384	0.077	11	139
Ericsson RRUS 32	126.00	152	1.352	0.198	0.384	0.077	10	131
CCI CCI-HPA-65R-BUU-	126.00	204	1.352	0.198	0.384	0.077	14	175
Round Platform w/ Ha	126.00	2,000	1.352	0.198	0.384	0.077	134	1,720
RFS APXV18-206517S-C	115.00	79	1.126	-0.054	0.203	-0.005	0	68
Proxim 5054-R-LR	106.00	6	0.957	-0.118	0.111	-0.043	0	5
3' Dish w/ Radome	106.00	100	0.957	-0.118	0.111	-0.043	-4	86
Flat Side Arm	106.00	150	0.957	-0.118	0.111	-0.043	-6	129
		33,400	78.926	38.487	30.553	8.928	2,441	28,720

Load Case (1.2 + 0.2Sds) * DL + E EMAM Seismic Equivalent Modal Analysis Method

Calculated Forces

Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	phi Pn (kips)	phi Vn (kips)	phi Tn (ft-kips)	phi Mn (ft-kips)	Total Deflect (in)	Rotation (deg)	Ratio
0.00	-40.08	-2.43	0.00	-299.57	0.00	299.57	4,132.29	2,066.14	8,772.59	4,392.82	0.00	0.00	0.078
5.00	-38.55	-2.41	0.00	-287.41	0.00	287.41	4,073.39	2,036.69	8,449.37	4,230.97	0.01	-0.02	0.077
10.00	-37.05	-2.37	0.00	-275.38	0.00	275.38	4,012.85	2,006.43	8,128.58	4,070.33	0.04	-0.04	0.077
15.00	-35.58	-2.34	0.00	-263.51	0.00	263.51	3,950.68	1,975.34	7,810.43	3,911.02	0.10	-0.06	0.076
20.00	-34.14	-2.30	0.00	-251.83	0.00	251.83	3,886.87	1,943.43	7,495.19	3,753.17	0.17	-0.08	0.076
25.00	-32.72	-2.25	0.00	-240.35	0.00	240.35	3,821.43	1,910.71	7,183.08	3,596.88	0.27	-0.11	0.075
30.00	-31.34	-2.21	0.00	-229.08	0.00	229.08	3,754.35	1,877.17	6,874.35	3,442.28	0.40	-0.13	0.075
35.00	-29.99	-2.17	0.00	-218.03	0.00	218.03	3,685.64	1,842.82	6,569.23	3,289.50	0.55	-0.15	0.074
40.00	-28.66	-2.12	0.00	-207.19	0.00	207.19	3,615.29	1,807.64	6,267.96	3,138.64	0.72	-0.18	0.074
45.00	-27.88	-2.10	0.00	-196.56	0.00	196.56	3,543.30	1,771.65	5,970.78	2,989.83	0.92	-0.20	0.074
48.00	-27.03	-2.07	0.00	-190.26	0.00	190.26	3,499.33	1,749.66	5,794.53	2,901.57	1.05	-0.22	0.073
50.00	-25.65	-2.02	0.00	-186.12	0.00	186.12	3,469.68	1,734.84	5,677.92	2,843.18	1.15	-0.23	0.073
53.25	-25.27	-2.01	0.00	-179.57	0.00	179.57	2,730.90	1,365.45	4,467.29	2,236.97	1.31	-0.25	0.090
55.00	-24.18	-1.97	0.00	-176.06	0.00	176.06	2,712.29	1,356.15	4,390.67	2,198.60	1.40	-0.26	0.089
60.00	-23.11	-1.94	0.00	-166.21	0.00	166.21	2,658.02	1,329.01	4,173.50	2,089.85	1.69	-0.29	0.088
65.00	-22.07	-1.93	0.00	-156.49	0.00	156.49	2,602.11	1,301.05	3,959.12	1,982.50	2.01	-0.32	0.087
70.00	-21.05	-1.92	0.00	-146.87	0.00	146.87	2,544.56	1,272.28	3,747.77	1,876.67	2.37	-0.36	0.087
75.00	-20.06	-1.93	0.00	-137.27	0.00	137.27	2,485.39	1,242.69	3,539.70	1,772.48	2.76	-0.39	0.086
80.00	-19.09	-1.95	0.00	-127.64	0.00	127.64	2,424.57	1,212.29	3,335.13	1,670.04	3.19	-0.43	0.084
85.00	-18.15	-1.97	0.00	-117.92	0.00	117.92	2,362.12	1,181.06	3,134.31	1,569.49	3.65	-0.46	0.083
90.00	-17.23	-2.01	0.00	-108.05	0.00	108.05	2,297.27	1,148.64	2,936.51	1,470.44	4.16	-0.50	0.081
95.00	-16.73	-2.03	0.00	-97.99	0.00	97.99	2,210.70	1,105.35	2,718.30	1,361.17	4.71	-0.54	0.080
97.75	-16.17	-2.06	0.00	-92.40	0.00	92.40	2,163.09	1,081.54	2,601.88	1,302.87	5.03	-0.56	0.078
100.00	-15.79	-2.07	0.00	-87.78	0.00	87.78	2,124.13	1,062.07	2,508.52	1,256.12	5.30	-0.58	0.077
101.50	-15.35	-2.09	0.00	-84.67	0.00	84.67	1,105.19	552.59	1,317.56	659.76	5.48	-0.59	0.142
105.00	-15.22	-2.09	0.00	-77.37	0.00	77.37	1,087.53	543.77	1,259.48	630.68	5.93	-0.62	0.137
106.00	-14.40	-2.11	0.00	-75.28	0.00	75.28	1,082.34	541.17	1,242.93	622.39	6.06	-0.63	0.134
110.00	-13.79	-2.13	0.00	-66.82	0.00	66.82	1,060.92	530.46	1,177.04	589.40	6.61	-0.68	0.126
115.00	-13.36	-2.13	0.00	-56.18	0.00	56.18	1,032.68	516.34	1,095.47	548.55	7.36	-0.74	0.115
117.94	-13.13	-2.13	0.00	-49.91	0.00	49.91	1,015.32	507.66	1,048.03	524.80	7.83	-0.78	0.108
120.00	-12.58	-2.12	0.00	-45.51	0.00	45.51	1,002.79	501.40	1,014.98	508.24	8.17	-0.80	0.102
125.00	-12.47	-2.12	0.00	-34.93	0.00	34.93	971.28	485.64	935.83	468.61	9.03	-0.85	0.087
126.00	-8.93	-1.87	0.00	-32.81	0.00	32.81	964.78	482.39	920.18	460.77	9.21	-0.86	0.080
130.00	-8.46	-1.82	0.00	-25.33	0.00	25.33	938.12	469.06	858.24	429.76	9.95	-0.90	0.068
135.00	-8.37	-1.81	0.00	-16.22	0.00	16.22	903.33	451.67	782.47	391.82	10.91	-0.93	0.051
136.00	-5.66	-1.41	0.00	-14.41	0.00	14.41	896.18	448.09	767.56	384.35	11.10	-0.94	0.044
140.00	-5.37	-1.35	0.00	-8.77	0.00	8.77	866.91	433.46	708.75	354.90	11.90	-0.96	0.031
144.00	-2.54	-0.71	0.00	-3.36	0.00	3.36	836.60	418.30	651.40	326.19	12.71	-0.97	0.013
145.00	-2.33	-0.66	0.00	-2.64	0.00	2.64	828.85	414.43	637.31	319.13	12.91	-0.97	0.011
149.00	0.00	-0.62	0.00	0.00	0.00	0.00	787.55	393.77	574.90	287.88	13.73	-0.97	0.000

Load Case (0.9 - 0.2Sds) * DL + E EMAM Seismic (Reduced DL) Equivalent Modal Analysis Method

Calculated Forces

Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	phi Pn (kips)	phi Vn (kips)	phi Tn (ft-kips)	phi Mn (ft-kips)	Total Deflect (in)	Rotation (deg)	Ratio
0.00	-27.79	-2.43	0.00	-294.20	0.00	294.20	4,132.29	2,066.14	8,772.59	4,392.82	0.00	0.00	0.074
5.00	-26.73	-2.40	0.00	-282.06	0.00	282.06	4,073.39	2,036.69	8,449.37	4,230.97	0.01	-0.02	0.073
10.00	-25.69	-2.36	0.00	-270.05	0.00	270.05	4,012.85	2,006.43	8,128.58	4,070.33	0.04	-0.04	0.073
15.00	-24.67	-2.32	0.00	-258.24	0.00	258.24	3,950.68	1,975.34	7,810.43	3,911.02	0.10	-0.06	0.072
20.00	-23.67	-2.28	0.00	-246.63	0.00	246.63	3,886.87	1,943.43	7,495.19	3,753.17	0.17	-0.08	0.072
25.00	-22.69	-2.23	0.00	-235.25	0.00	235.25	3,821.43	1,910.71	7,183.08	3,596.88	0.27	-0.10	0.071
30.00	-21.73	-2.19	0.00	-224.08	0.00	224.08	3,754.35	1,877.17	6,874.35	3,442.28	0.39	-0.13	0.071
35.00	-20.79	-2.14	0.00	-213.15	0.00	213.15	3,685.64	1,842.82	6,569.23	3,289.50	0.54	-0.15	0.070
40.00	-19.87	-2.09	0.00	-202.45	0.00	202.45	3,615.29	1,807.64	6,267.96	3,138.64	0.71	-0.17	0.070
45.00	-19.33	-2.07	0.00	-191.98	0.00	191.98	3,543.30	1,771.65	5,970.78	2,989.83	0.90	-0.20	0.070
48.00	-18.74	-2.04	0.00	-185.78	0.00	185.78	3,499.33	1,749.66	5,794.53	2,901.57	1.03	-0.21	0.069
50.00	-17.79	-1.98	0.00	-181.71	0.00	181.71	3,469.68	1,734.84	5,677.92	2,843.18	1.13	-0.23	0.069
53.25	-17.52	-1.97	0.00	-175.27	0.00	175.27	2,730.90	1,365.45	4,467.29	2,236.97	1.28	-0.24	0.085
55.00	-16.76	-1.93	0.00	-171.82	0.00	171.82	2,712.29	1,356.15	4,390.67	2,198.60	1.38	-0.25	0.084
60.00	-16.02	-1.90	0.00	-162.16	0.00	162.16	2,658.02	1,329.01	4,173.50	2,089.85	1.66	-0.28	0.084
65.00	-15.30	-1.88	0.00	-152.64	0.00	152.64	2,602.11	1,301.05	3,959.12	1,982.50	1.97	-0.32	0.083
70.00	-14.59	-1.87	0.00	-143.22	0.00	143.22	2,544.56	1,272.28	3,747.77	1,876.67	2.32	-0.35	0.082
75.00	-13.91	-1.88	0.00	-133.85	0.00	133.85	2,485.39	1,242.69	3,539.70	1,772.48	2.70	-0.38	0.081
80.00	-13.23	-1.90	0.00	-124.45	0.00	124.45	2,424.57	1,212.29	3,335.13	1,670.04	3.12	-0.42	0.080
85.00	-12.58	-1.93	0.00	-114.96	0.00	114.96	2,362.12	1,181.06	3,134.31	1,569.49	3.58	-0.45	0.079
90.00	-11.94	-1.96	0.00	-105.34	0.00	105.34	2,297.27	1,148.64	2,936.51	1,470.44	4.07	-0.49	0.077
95.00	-11.60	-1.98	0.00	-95.54	0.00	95.54	2,210.70	1,105.35	2,718.30	1,361.17	4.60	-0.53	0.075
97.75	-11.20	-2.00	0.00	-90.09	0.00	90.09	2,163.09	1,081.54	2,601.88	1,302.87	4.91	-0.55	0.074
100.00	-10.94	-2.02	0.00	-85.58	0.00	85.58	2,124.13	1,062.07	2,508.52	1,256.12	5.18	-0.57	0.073
101.50	-10.64	-2.03	0.00	-82.55	0.00	82.55	1,105.19	552.59	1,317.56	659.76	5.36	-0.58	0.135
105.00	-10.55	-2.04	0.00	-75.44	0.00	75.44	1,087.53	543.77	1,259.48	630.68	5.79	-0.61	0.129
106.00	-9.98	-2.06	0.00	-73.40	0.00	73.40	1,082.34	541.17	1,242.93	622.39	5.92	-0.62	0.127
110.00	-9.56	-2.07	0.00	-65.15	0.00	65.15	1,060.92	530.46	1,177.04	589.40	6.46	-0.67	0.120
115.00	-9.26	-2.08	0.00	-54.79	0.00	54.79	1,032.68	516.34	1,095.47	548.55	7.19	-0.72	0.109
117.94	-9.10	-2.08	0.00	-48.69	0.00	48.69	1,015.32	507.66	1,048.03	524.80	7.65	-0.76	0.102
120.00	-8.71	-2.06	0.00	-44.41	0.00	44.41	1,002.79	501.40	1,014.98	508.24	7.98	-0.78	0.096
125.00	-8.64	-2.06	0.00	-34.12	0.00	34.12	971.28	485.64	935.83	468.61	8.83	-0.83	0.082
126.00	-6.18	-1.83	0.00	-32.07	0.00	32.07	964.78	482.39	920.18	460.77	9.00	-0.84	0.076
130.00	-5.86	-1.78	0.00	-24.76	0.00	24.76	938.12	469.06	858.24	429.76	9.72	-0.88	0.064
135.00	-5.80	-1.77	0.00	-15.87	0.00	15.87	903.33	451.67	782.47	391.82	10.66	-0.91	0.047
136.00	-3.92	-1.38	0.00	-14.11	0.00	14.11	896.18	448.09	767.56	384.35	10.85	-0.92	0.041
140.00	-3.72	-1.32	0.00	-8.59	0.00	8.59	866.91	433.46	708.75	354.90	11.63	-0.93	0.028
144.00	-1.76	-0.70	0.00	-3.29	0.00	3.29	836.60	418.30	651.40	326.19	12.42	-0.95	0.012
145.00	-1.62	-0.65	0.00	-2.59	0.00	2.59	828.85	414.43	637.31	319.13	12.61	-0.95	0.010
149.00	0.00	-0.62	0.00	0.00	0.00	0.00	787.55	393.77	574.90	287.88	13.41	-0.95	0.000

Site Number: 243036

Code: ANSI/TIA-222-G

© 2007 - 2018 by ATC IP LLC. All rights reserved.

Site Name: WEST HAVEN & RT 162 CT, CT Engineering Number: OAA714853_C3_06

8/2/2018 9:22:20 AM

Customer: CLEARWIRE

Analysis Summary

Load Case	Reactions						Max Usage	
	Shear FX (kips)	Shear FZ (kips)	Axial FY (kips)	Moment MX (ft-kips)	Moment MY (ft-kips)	Moment MZ (ft-kips)	Elev (ft)	Interaction Ratio
1.2D + 1.6W	21.03	0.00	40.05	0.00	0.00	2351.27	101.50	0.78
0.9D + 1.6W	21.01	0.00	30.03	0.00	0.00	2319.59	101.50	0.76
1.2D + 1.0Di + 1.0Wi	5.99	0.00	61.16	0.00	0.00	665.25	101.50	0.24
(1.2 + 0.2Sds) * DL + E ELFM	1.31	0.00	40.08	0.00	0.00	166.21	101.50	0.07
(1.2 + 0.2Sds) * DL + E EMAM	2.43	0.00	40.08	0.00	0.00	299.57	101.50	0.14
(0.9 - 0.2Sds) * DL + E ELFM	1.30	0.00	27.79	0.00	0.00	163.44	101.50	0.06
(0.9 - 0.2Sds) * DL + E EMAM	2.43	0.00	27.79	0.00	0.00	294.20	101.50	0.13
1.0D + 1.0W	5.02	0.00	33.40	0.00	0.00	557.87	101.50	0.19




Base Plate & Anchor Rod Analysis

Pole Dimensions		
Number of Sides	18	-
Diameter	52.01	in
Thickness	0.375	in
Orientation Offset	0	°

Base Reactions		
Moment, Mu	2351.3	k-ft
Axial, Pu	40.1	k
Shear, Vu	21.0	k
Neutral Axis	39	°

Report Capacities		
Component	Capacity	Result
Base Plate	37%	Pass
Anchor Rods	47%	Pass
Dwyidag	-	-

Base Plate		
Shape	Square	-
Width	59	in
Thickness	2 3/4	in
Grade	Other	-
Yield Strength, Fy	60	ksi
Tensile Strength, Fu	80	ksi
Clip	12	in
Orientation Offset	0	°
Anchor Rod Detail	d	η=0.5
Clear Distance	3	in
Applied Moment, Mu	1175.2	k
Bending Stress, φMn	3183.1	k



Original Anchor Rods		
Arrangement	Cluster	-
Quantity	16	-
Diameter, φ	2 1/4	in
Bolt Circle	59	in
Grade	A615-75	
Yield Strength, Fy	75	ksi
Tensile Strength, Fu	100	ksi
Spacing	6.0	in
Orientation Offset	0	°
Applied Force, Pu	122.0	k
Anchor Rods, φPn	259.8	k

Calculations for Monopole Base Plate & Anchor Rod Analysis

Reaction Distribution

Reaction	Shear Vu	Moment Mu	Factor
-	k	k-ft	-
Base Forces	21.0	2351.3	1.00
Anchor Rod Forces	21.0	2351.3	1.00
Additional Bolt (Grp1) Forces	0.0	0.0	0.00
Additional Bolt (Grp2) Forces	0.0	0.0	0.00
Dywidag Forces	0.0	0.0	0.00
Stiffener Forces	0.0	0.0	0.00

Geometric Properties

Section	Gross Area	Net Area	Individual Inertia	Threads per Inch	Moment of Inertia
-	in ²	in ²	in ⁴	#	in ⁴
Pole	60.5227	3.3624	0.1582		20173.34
Bolt	3.9761	3.2477	0.8393	4.5	22623.84
Bolt1	0.0000	0.0000	0.0000	0	0.00
Bolt2	0.0000	0.0000	0.0000	0	0.00
Dywidag	0.0000	0.0000	0.0000		0.00
Stiffener	0.0000	0.0000	0.0000		0.00

Base Plate		
Shape	Square	-
Width, W	59	in
Thickness, t	2.75	in
Yield Strength, Fy	60	ksi
Tensile Strength, Fu	80	ksi
Base Plate Chord	27.856	in
Detail Type	d	-
Detail Factor	0.50	-
Clear Distance	3	-

Anchor Rods		
Anchor Rod Quantity, N	16	-
Rod Diameter, d	2.25	in
Bolt Circle, BC	59	in
Yield Strength, Fy	75	ksi
Tensile Strength, Fu	100	ksi
Applied Axial, Pu	122.0	k
Applied Shear, Vu	0.0	k
Compressive Capacity, φPn	259.8	k
Tensile Capacity, φRnt	0.470	OK
Interaction Capacity	0.470	OK

Base Plate Stiffeners		
Applied Axial Force, Pu	0.0	k
Applied Horizontal Force, Vu	0.00	k

External Base Plate		
Chord Length AA	31.179	in
Additional AA	0.000	in
Section Modulus, Z	58.947	in ³
Applied Moment, Mu	1175.2	k-ft
Bending Capacity, φMn	3183.1	k-ft
Capacity, Mu/φMn	0.369	OK

Additional Bolt Group 1		
Bolt Quantity, N	0	-
Bolt Diameter, d	0	in
Bolt Circle, BC	0	in
Yield Strength, Fy	0	ksi
Tensile Strength, Fu	0	ksi
Applied Axial, Pu	0.0	k
Applied Shear, Vu	0.0	k
Compressive Capacity, φPn	0.0	k
Compressive Capacity, φPn		
Interaction Capacity		

Vertical Weld		
Vert.-to-Stiffener a=e _x /l	#DIV/0!	-
Spacing Ratio, k	#DIV/0!	-
Weld Coefficient, C	#DIV/0!	-
Compressive Capacity, φPn	#DIV/0!	k
Vert.-to-Plate a=e _x /l	#DIV/0!	-
Spacing Ratio, k	#DIV/0!	-
Weld Coefficient, C	#DIV/0!	-
Shear Capacity, φVn	#DIV/0!	k
P _u /φ _p P _n + V _u /φ _v V _n	-	

Chord Length AB	30.372	in
Additional AB	0.000	in
Section Modulus, Z	57.423	in ³
Applied Moment, Mu	984.5	k-ft
Bending Capacity, φMn	3100.8	k-ft
Capacity, Mu/φMn	0.318	OK

Additional Bolt Group 2		
Bolt Quantity, N	0	-
Bolt Diameter, d	0	in
Bolt Circle, BC	0	in
Yield Strength, Fy	0	ksi
Tensile Strength, Fu	0	ksi
Applied Axial, Pu	0.0	k
Applied Shear, Vu	0.0	k
Compressive Capacity, φPn	0.0	k
Compressive Capacity, φPn		
Interaction Capacity		

Horizontal Weld		
Horz.-to-Stiffener a=e _x /l	#DIV/0!	-
Spacing Ratio, k	#DIV/0!	-
Weld Coefficient, C	#DIV/0!	-
Effective Fillet	0.000	in
Compressive Capacity, φPn	#DIV/0!	k
Horz.-to-Pole a=e _x /l	#DIV/0!	-
Spacing Ratio, k	#DIV/0!	-
Weld Coefficient, C	#DIV/0!	-
Shear Capacity, φVn	#DIV/0!	k
P _u /φ _p P _n + V _u /φ _v V _n	-	

Bend Line Length	0.000	in
Additional Bend Line	0.000	in
Section Modulus, Z	0.000	in ³
Applied Moment, Mu	0.0	k-ft
Bending Capacity, φMn	0.0	k-ft
Capacity, Mu/φMn		

Plate Tension		
Gross Cross Section	0.000	in ²
Net Cross Section	0.000	in ²
Tensile Capacity, φTn	0.0	k
Capacity, Tu/φTn	-	

Internal Base Plate		
Arc Length	0.000	in
Section Modulus, Z	0.000	in ³
Moment Arm	0.000	in
Applied Moment, Mu	0.0	k-ft
Bending Capacity, φMn	0.0	k-ft
Capacity, Mu/φMn		

Dywidag Reinforcement		
Dywidag Quantity, N	0	-
Dywidag Diameter, d	2.5	in
Bolt Circle, BC	58.89	in
Yield Strength, Fy	80	ksi
Tensile Strength, Fu	100	ksi
Applied Axial, Pu	0.0	k
Compressive Capacity, φPn	0.0	k
Capacity, Pu/φPn		

Plate Compression		
Radius of Gyration	#DIV/0!	in ³
kl/r	#DIV/0!	-
4.71 √(E/Fy)	0.00	-
Buckling Stress(F _e)	0.0	-
Crit. Buckling Stress(F _{cr})	0.0	ksi
Compressive Capacity, φPn	0.0	k
Capacity, Pu/φPn	-	

THESE OUTLINE SPECIFICATIONS IN CONJUNCTION WITH THE SPRINT STANDARD CONSTRUCTION SPECIFICATIONS, INCLUDING CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

SECTION 01 100 – SCOPE OF WORK

PART 1 – GENERAL

- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE SPRINT CONSTRUCTION STANDARDS FOR WIRELESS SITES, CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
 - A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
 - B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HERewith.
- 1.3 PRECEDENCE: SHOULD CONFLICTS OCCUR BETWEEN THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES INCLUDING THE STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES AND THE CONSTRUCTION DRAWINGS, INFORMATION ON THE CONSTRUCTION DRAWINGS SHALL TAKE PRECEDENCE. NOTIFY SPRINT CONSTRUCTION MANAGER IF THIS OCCURS.
- 1.4 NATIONALLY RECOGNIZED CODES AND STANDARDS:
 - A. THE WORK SHALL COMPLY WITH APPLICABLE NATIONAL AND LOCAL CODES AND STANDARDS, LATEST EDITION, AND PORTIONS THEREOF, INCLUDED BUT NOT LIMITED TO THE FOLLOWING:
 - 1. GR-63-CORE NEBS REQUIREMENTS: PHYSICAL PROTECTION
 - 5. GR-78-CORE GENERIC REQUIREMENTS FOR THE PHYSICAL DESIGN AND MANUFACTURE OF TELECOMMUNICATIONS EQUIPMENT.
 - 3. GR-1089 CORE, ELECTROMAGNETIC COMPATIBILITY AND ELECTRICAL SAFETY -GENERIC CRITERIA FOR NETWORK TELECOMMUNICATIONS EQUIPMENT.
 - 4. NATIONAL FIRE PROTECTION ASSOCIATION CODES AND STANDARDS (NFPA) INCLUDING NFPA 70 (NATIONAL ELECTRICAL CODE - "NEC") AND NFPA 101 (LIFE SAFETY CODE).
 - 5. AMERICAN SOCIETY FOR TESTING OF MATERIALS (ASTM)
 - 6. INSTITUTE OF ELECTRONIC AND ELECTRICAL ENGINEERS (IEEE)
 - 7. AMERICAN CONCRETE INSTITUTE (ACI)
 - 8. AMERICAN WIRE PRODUCERS ASSOCIATION (AWPA)
 - 9. CONCRETE REINFORCING STEEL INSTITUTE (CRSI)
 - 10. AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)
 - 11. PORTLAND CEMENT ASSOCIATION (PCA)
 - 12. NATIONAL CONCRETE MASONRY ASSOCIATION (NCMA)
 - 13. BRICK INDUSTRY ASSOCIATION (BIA)
 - 14. AMERICAN WELDING SOCIETY (AWS)
 - 15. NATIONAL ROOFING CONTRACTORS ASSOCIATION (NRCA)
 - 16. SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)
 - 17. DOOR AND HARDWARE INSTITUTE (DHI)
 - 18. OCCUPATIONAL SAFETY AND HEALTH ACT (OSHA)
 - 19. APPLICABLE BUILDING CODES INCLUDING UNIFORM BUILDING CODE, SOUTHERN BUILDING CODE, BOCA, AND THE INTERNATIONAL BUILDING CODE.

1.5 DEFINITIONS:

- A. WORK: THE SUM OF TASKS AND RESPONSIBILITIES IDENTIFIED IN THE CONTRACT DOCUMENTS.
- B. COMPANY: SPRINT CORPORATION
- C. ENGINEER: SYNONYMOUS WITH ARCHITECT & ENGINEER AND "A&E". THE DESIGN PROFESSIONAL HAVING PROFESSIONAL RESPONSIBILITY FOR DESIGN OF THE PROJECT.
- D. CONTRACTOR: CONSTRUCTION CONTRACTOR; CONSTRUCTION VENDOR; INDIVIDUAL OR ENTITY WHO AFTER EXECUTION OF A CONTRACT IS BOUND TO ACCOMPLISH THE WORK.
- E. THIRD PARTY VENDOR OR AGENCY: A VENDOR OR AGENCY ENGAGED SEPARATELY BY THE COMPANY, A&E, OR CONTRACTOR TO PROVIDE MATERIALS OR TO ACCOMPLISH SPECIFIC TASKS RELATED TO BUT NOT INCLUDED IN THE WORK.
- F. OFCI: OWNER FURNISHED, CONTRACTOR INSTALLED EQUIPMENT.
- G. CONSTRUCTION MANAGER – ALL PROJECTS RELATED COMMUNICATION TO FLOW THROUGH SPRINT REPRESENTATIVE IN CHARGE OF PROJECT...

- 1.6 SITE FAMILIARITY: CONTRACTOR SHALL BE RESPONSIBLE FOR FAMILIARIZING HIMSELF WITH ALL CONTRACT DOCUMENTS, FIELD CONDITIONS AND DIMENSIONS PRIOR TO PROCEEDING WITH CONSTRUCTION. ANY DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE SPRINT CONSTRUCTION MANAGER PRIOR TO THE COMMENCEMENT OF WORK. NO COMPENSATION WILL BE AWARDED BASED ON CLAIM OF LACK OF KNOWLEDGE OR FIELD CONDITIONS.
- 1.7 POINT OF CONTACT: COMMUNICATION BETWEEN SPRINT AND THE CONTRACTOR SHALL FLOW THROUGH THE SINGLE SPRINT CONSTRUCTION MANAGER APPOINTED TO MANAGE THE PROJECT FOR SPRINT.
- 1.8 ON-SITE SUPERVISION: THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK AND SHALL BE RESPONSIBLE FOR CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES IN ACCORDANCE WITH THE CONTRACT DOCUMENTS. THE CONTRACTOR SHALL EMPLOY A COMPETENT SUPERINTENDENT WHO SHALL BE IN ATTENDANCE AT THE SITE AT ALL TIMES DURING PERFORMANCE OF THE WORK.
- 1.9 DRAWINGS, SPECIFICATIONS AND DETAILS REQUIRED AT JOBSITE: THE CONSTRUCTION CONTRACTOR SHALL MAINTAIN A FULL SET OF THE CONSTRUCTION DRAWINGS, STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES AND THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES AT THE JOBSITE FROM MOBILIZATION THROUGH CONSTRUCTION COMPLETION.
 - A. THE JOBSITE DRAWINGS, SPECIFICATIONS AND DETAILS SHALL BE CLEARLY MARKED DAILY IN RED PENCIL WITH ANY CHANGES IN CONSTRUCTION OVER WHAT IS DEPICTED IN THE DOCUMENTS. AT CONSTRUCTION COMPLETION, THIS JOBSITE MARKUP SET SHALL BE DELIVERED TO THE COMPANY OR COMPANY'S DESIGNATED REPRESENTATIVE TO BE FORWARDED TO THE COMPANY'S A&E VENDOR FOR PRODUCTION OF "AS-BUILT" DRAWINGS.
 - B. DETAILS ARE INTENDED TO SHOW DESIGN INTENT. MODIFICATIONS MAY BE REQUIRED TO SUIT JOB DIMENSIONS OR CONDITIONS, AND SUCH MODIFICATIONS SHALL BE INCLUDED AS PART OF THE WORK. CONTRACTOR SHALL NOTIFY SPRINT CONSTRUCTION MANAGER OF ANY VARIATIONS PRIOR TO PROCEEDING WITH THE WORK.
 - C. DIMENSIONS SHOWN ARE TO FINISH SURFACES UNLESS NOTED OTHERWISE. SPACING BETWEEN EQUIPMENT IS THE REQUIRED CLEARANCE. SHOULD THERE BE ANY QUESTIONS REGARDING THE CONTRACT DOCUMENTS, EXISTING CONDITIONS AND/OR DESIGN INTENT, THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING A CLARIFICATION FROM THE SPRINT CONSTRUCTION MANAGER PRIOR TO PROCEEDING WITH THE WORK.
- 1.10 USE OF JOB SITE: THE CONTRACTOR SHALL CONFINE ALL CONSTRUCTION AND RELATED OPERATIONS INCLUDING STAGING AND STORAGE OF MATERIALS AND EQUIPMENT, PARKING, TEMPORARY FACILITIES, AND WASTE STORAGE TO THE LEASE PARCEL UNLESS OTHERWISE PERMITTED BY THE CONTRACT DOCUMENTS.
- 1.11 UTILITIES SERVICES: WHERE NECESSARY TO CUT EXISTING PIPES, ELECTRICAL WIRES, CONDUITS, CABLES, ETC., OF UTILITY SERVICES, OR OF FIRE PROTECTION OR COMMUNICATIONS SYSTEMS, THEY SHALL BE CUT AND CAPPED AT SUITABLE PLACES OR WHERE SHOWN. ALL SUCH ACTIONS SHALL BE COORDINATED WITH THE UTILITY COMPANY INVOLVED.
- 1.12 PERMITS / FEES: WHEN REQUIRED THAT A PERMIT OR CONNECTION FEE BE PAID TO A PUBLIC UTILITY PROVIDER FOR NEW SERVICE TO THE CONSTRUCTION PROJECT, PAYMENT OF SUCH FEE SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.
- 1.13 CONTRACTOR SHALL TAKE ALL MEASURES AND PROVIDE ALL MATERIAL NECESSARY FOR PROTECTING EXISTING EQUIPMENT AND PROPERTY.
- 1.14 METHODS OF PROCEDURE (MOPS) FOR CONSTRUCTION: CONTRACTOR SHALL PERFORM WORK AS DESCRIBED IN THE FOLLOWING INSTALLATION AND COMMISSIONING MOPS.

NOTE: IN SHORT-FORM SPECIFICATIONS ON THE DRAWINGS, A/E TO INSERT LIST OF APPLICABLE MOPS INCLUDING EN-2012-001, EN-2013-002, EL-0568, AND TS-0193

1.15 USE OF ELECTRONIC PROJECT MANAGEMENT SYSTEMS:

PART 2 – PRODUCTS (NOT USED)

PART 3 – EXECUTION

- 3.1 TEMPORARY UTILITIES AND FACILITIES: THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL TEMPORARY UTILITIES AND FACILITIES NECESSARY EXCEPT AS OTHERWISE INDICATED IN THE CONSTRUCTION DOCUMENTS. TEMPORARY UTILITIES AND FACILITIES INCLUDE POTABLE WATER, HEAT, HVAC, ELECTRICITY, SANITARY FACILITIES, WASTE DISPOSAL FACILITIES, AND TELEPHONE/COMMUNICATION SERVICES. PROVIDE TEMPORARY UTILITIES AND FACILITIES IN ACCORDANCE WITH OSHA AND THE AUTHORITY HAVING JURISDICTION. CONTRACTOR MAY UTILIZE THE COMPANY ELECTRICAL SERVICE IN THE COMPLETION OF THE WORK WHEN IT BECOMES AVAILABLE. USE OF THE LESSORS OR SITE OWNER'S UTILITIES OR FACILITIES IS EXPRESSLY FORBIDDEN EXCEPT AS OTHERWISE ALLOWED IN THE CONTRACT DOCUMENTS.
- 3.2 ACCESS TO WORK: THE CONTRACTOR SHALL PROVIDE ACCESS TO THE JOB SITE FOR AUTHORIZED COMPANY PERSONNEL AND AUTHORIZED REPRESENTATIVES OF THE ARCHITECT/ENGINEER DURING ALL PHASES OF THE WORK.
- 3.3 TESTING: REQUIREMENTS FOR TESTING BY THIS CONTRACTOR SHALL BE AS INDICATED HERewith, ON THE CONSTRUCTION DRAWINGS, AND IN THE INDIVIDUAL SECTIONS OF THESE SPECIFICATIONS. SHOULD COMPANY CHOOSE TO ENGAGE ANY THIRD-PARTY TO CONDUCT ADDITIONAL TESTING, THE CONTRACTOR SHALL COOPERATE WITH AND PROVIDE A WORK AREA FOR COMPANY'S TEST AGENCY.
- 3.4 DIMENSIONS: VERIFY DIMENSIONS INDICATED ON DRAWINGS WITH FIELD DIMENSIONS BEFORE FABRICATION OR ORDERING OF MATERIALS. DO NOT SCALE DRAWINGS.

3.5 EXISTING CONDITIONS: NOTIFY THE SPRINT CONSTRUCTION MANAGER OF EXISTING CONDITIONS DIFFERING FROM THOSE INDICATED ON THE DRAWINGS. DO NOT REMOVE OR ALTER STRUCTURAL COMPONENTS WITHOUT PRIOR WRITTEN APPROVAL FROM THE ARCHITECT AND ENGINEER.

SECTION 01 200 – COMPANY FURNISHED MATERIAL AND EQUIPMENT

PART 1 – GENERAL

- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
 - A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
 - B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HERewith.

PART 2 – PRODUCTS (NOT USED)

PART 3 – EXECUTION

- 3.1 RECEIPT OF MATERIAL AND EQUIPMENT:
 - A. A COMPANY FURNISHED MATERIAL AND EQUIPMENT IS IDENTIFIED ON THE RF DATA SHEET IN THE CONSTRUCTION DOCUMENTS.
 - B. THE CONTRACTOR IS RESPONSIBLE FOR SPRINT PROVIDED MATERIAL AND EQUIPMENT AND UPON RECEIPT SHALL:
 - 1. ACCEPT DELIVERIES AS SHIPPED AND TAKE RECEIPT.
 - 2. VERIFY COMPLETENESS AND CONDITION OF ALL DELIVERIES.
 - 3. TAKE RESPONSIBILITY FOR EQUIPMENT AND PROVIDE INSURANCE PROTECTION AS REQUIRED IN AGREEMENT.
 - 4. RECORD ANY DEFECTS OR DAMAGES AND WITHIN TWENTY-FOUR HOURS AFTER RECEIPT, REPORT TO SPRINT OR ITS DESIGNATED PROJECT REPRESENTATIVE OF SUCH.
 - 5. PROVIDE SECURE AND NECESSARY WEATHER PROTECTED WAREHOUSING.
 - 6. COORDINATE SAFE AND SECURE TRANSPORTATION OF MATERIAL AND EQUIPMENT, DELIVERING AND OFF-LOADING FROM CONTRACTOR'S WAREHOUSE TO SITE.
- 3.2 DELIVERABLES:
 - A. COMPLETE SHIPPING AND RECEIPT DOCUMENTATION IN ACCORDANCE WITH COMPANY PRACTICE.
 - B. IF APPLICABLE, COMPLETE LOST/STOLEN/DAMAGED DOCUMENTATION REPORT AS NECESSARY IN ACCORDANCE WITH COMPANY PRACTICE, AND AS DIRECTED BY COMPANY.
 - C. UPLOAD DOCUMENTATION INTO SPRINT SITE MANAGEMENT SYSTEM (SMS) AND/OR PROVIDE HARD COPY DOCUMENTATION AS REQUESTED.

SECTION 01 300 – CELL SITE CONSTRUCTION CO.

PART 1 – GENERAL

- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
 - A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
 - B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HERewith.
- 1.3 NOTICE TO PROCEED
 - A. NO WORK SHALL COMMENCE PRIOR TO COMPANY'S WRITTEN NOTICE TO PROCEED AND THE ISSUANCE OF THE WORK ORDER.
 - B. UPON RECEIVING NOTICE TO PROCEED, CONTRACTOR SHALL FULLY PERFORM ALL WORK NECESSARY TO PROVIDE SPRINT WITH AN OPERATIONAL WIRELESS FACILITY.

PART 2 – PRODUCTS (NOT USED)

PART 3 – EXECUTION

- 3.1 FUNCTIONAL REQUIREMENTS:
 - A. THE ACTIVITIES DESCRIBED IN THIS PARAGRAPH REPRESENT MINIMUM ACTIONS AND PROCESSES REQUIRED TO SUCCESSFULLY COMPLETE THE WORK. THE ACTIVITIES DESCRIBED ARE NOT EXHAUSTIVE, AND CONTRACTOR SHALL TAKE ANY AND ALL ACTIONS AS NECESSARY TO SUCCESSFULLY COMPLETE THE CONSTRUCTION OF A FULLY FUNCTIONING WIRELESS FACILITY AT THE SITE IN ACCORDANCE WITH COMPANY PROCESSES.
 - B. SUBMIT SPECIFIC DOCUMENTATION AS INDICATED HEREIN, AND OBTAIN REQUIRED APPROVALS WHILE THE WORK IS BEING PERFORMED.
 - C. MANAGE AND CONDUCT ALL FIELD CONSTRUCTION SERVICE RELATED ACTIVITIES
 - D. PROVIDE CONSTRUCTION ACTIVITIES TO THE EXTENT REQUIRED BY THE CONTRACT DOCUMENTS, INCLUDING BUT NOT LIMITED TO THE FOLLOWING:

PLANS PREPARED FOR:



PLANS PREPARED BY:



FROM ZERO TO INFINIGY
the solutions are endless

1033 Watervliet Shaker Rd | Albany, NY 12205
Phone: 518-690-0790 | Fax: 518-690-0793
www.infinigy.com
JOB NUMBER: 526-104

PROJECT MANAGER:



32 CLINTON ST.
SARATOGA SPRINGS, NY 12888
OFFICE# (518) 306-3740

ENGINEERING LICENSE:



DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:	DESCRIPTION	DATE	BY	REV.
ISSUED FOR PERMIT		06/27/18	MAP	0

SITE NAME:

WEST HAVEN & RT 162 CT

SITE NUMBER:

CT52XC076

SITE ADDRESS:

**668 JONES HILL ROAD
WEST HAVEN, CT 06516**

SHEET DESCRIPTION:

SPRINT SPECIFICATIONS

SHEET NUMBER:

SP-1

CONTINUE FROM SP-1

1. PERFORM ANY REQUIRED SITE ENVIRONMENTAL MITIGATION.
2. PREPARE GROUND SITES; PROVIDE DE-GRUBBING; AND ROUGH AND FINAL GRADING, AND COMPOUND SURFACE TREATMENTS.
3. MANAGE AND CONDUCT ALL ACTIVITIES FOR INSTALLATION OF UTILITIES INCLUDING ELECTRICAL AND TELCO BACKHAUL.
4. INSTALL UNDERGROUND FACILITIES INCLUDING UNDERGROUND POWER AND COMMUNICATIONS CONDUITS, AND UNDERGROUND GROUNDING SYSTEM.
5. INSTALL ABOVE GROUND GROUNDING SYSTEMS.
6. PROVIDE NEW HVAC INSTALLATIONS AND MODIFICATIONS.
7. INSTALL "H-FRAMES", CABINETS AND SHELTERS AS INDICATED.
8. INSTALL ROADS, ACCESS WAYS, CURBS AND DRAINS AS INDICATED.
9. ACCOMPLISH REQUIRED MODIFICATION OF EXISTING FACILITIES.
10. PROVIDE ANTENNA SUPPORT STRUCTURE FOUNDATIONS.
11. PROVIDE SLABS AND EQUIPMENT PLATFORMS.
12. INSTALL COMPOUND FENCING, SIGHT SHIELDING, LANDSCAPING AND ACCESS BARRIERS.
13. PERFORM INSPECTION AND MATERIAL TESTING AS REQUIRED HEREINAFTER.
14. CONDUCT SITE RESISTANCE TO EARTH TESTING AS REQUIRED HEREINAFTER.
15. INSTALL FIXED GENERATOR SETS AND OTHER STANDBY POWER SOLUTIONS.
16. INSTALL TOWERS, ANTENNA SUPPORT STRUCTURES AND PLATFORMS ON EXISTING TOWERS AS REQUIRED.
17. INSTALL CELL SITE RADIOS, MICROWAVE, GPS, COAXIAL MAINLINE, ANTENNAS, CROSS BAND COUPLERS, TOWER TOP AMPLIFIERS, LOW NOISE AMPLIFIERS AND RELATED EQUIPMENT.
18. PERFORM, DOCUMENT, AND CLOSE OUT ANY CONSTRUCTION CONTROL DOCUMENTS THAT MAY BE REQUIRED BY GOVERNMENT AGENCIES AND LANDLORDS.
19. PERFORM ANTENNA AND COAX SWEEP TESTING AND MAKE ANY AND ALL NECESSARY CORRECTIONS.
20. REMAIN ON SITE MOBILIZED THROUGHOUT HAND-OFF AND INTEGRATION TO ASSIST AS NEEDED UNTIL SITE IS DEEMED SUBSTANTIALLY COMPLETE AND PLACED "ON AIR."

3.2 GENERAL REQUIREMENTS FOR CIVIL CONSTRUCTION:

- A. CONTRACTOR SHALL KEEP THE SITE FREE FROM ACCUMULATING WASTE MATERIAL, DEBRIS, AND TRASH. AT THE COMPLETION OF THE WORK, CONTRACTOR SHALL REMOVE FROM THE SITE ALL REMAINING RUBBISH, IMPLEMENTS, TEMPORARY FACILITIES, AND SURPLUS MATERIALS.
- B. EQUIPMENT ROOMS SHALL AT ALL TIMES BE MAINTAINED "BROOM CLEAN" AND CLEAR OF DEBRIS.
- C. CONTRACTOR SHALL TAKE ALL REASONABLE PRECAUTIONS TO DISCOVER AND LOCATE ANY HAZARDOUS CONDITION.
 1. IN THE EVENT CONTRACTOR ENCOUNTERS ANY HAZARDOUS CONDITION WHICH HAS NOT BEEN ABATED OR OTHERWISE MITIGATED, CONTRACTOR AND ALL OTHER PERSONS SHALL IMMEDIATELY STOP WORK IN THE AFFECTED AREA AND NOTIFY COMPANY IN WRITING. THE WORK IN THE AFFECTED AREA SHALL NOT BE RESUMED EXCEPT BY WRITTEN NOTIFICATION BY COMPANY.
 2. CONTRACTOR AGREES TO USE CARE WHILE ON THE SITE AND SHALL NOT TAKE ANY ACTION THAT WILL OR MAY RESULT IN OR CAUSE THE HAZARDOUS CONDITION TO BE FURTHER RELEASED IN THE ENVIRONMENT, OR TO FURTHER EXPOSE INDIVIDUALS TO THE HAZARD.
- D. CONTRACTOR'S ACTIVITIES SHALL BE RESTRICTED TO THE PROJECT LIMITS. SHOULD AREAS OUTSIDE THE PROJECT LIMITS BE AFFECTED BY CONTRACTOR'S ACTIVITIES, CONTRACTOR SHALL IMMEDIATELY RETURN THEM TO ORIGINAL CONDITION
- E. CONDUCT TESTING AS REQUIRED HEREIN.

3.3 DELIVERABLES:

- A. CONTRACTOR SHALL REVIEW, APPROVE, AND SUBMIT TO SPRINT SHOP DRAWINGS, PRODUCT DATA, SAMPLES, AND SIMILAR SUBMITTALS AS REQUIRED HEREINAFTER
- B. PROVIDE DOCUMENTATION INCLUDING, BUT NOT LIMITED TO, THE FOLLOWING. DOCUMENTATION SHALL BE FORWARDED IN ORIGINAL FORMAT AND/OR UPLOADED INTO SMS.
 1. ALL CORRESPONDENCE AND PRELIMINARY CONSTRUCTION REPORTS.
 2. PROJECT PROGRESS REPORTS.
 3. CIVIL CONSTRUCTION START DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
 4. ELECTRICAL SERVICE COMPLETION DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).

5. LINES AND ANTENNA INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
6. POWER INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
7. TELCO READY DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
8. PPC (OR SHELTER) INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
9. TOWER CONSTRUCTION START DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
10. TOWER CONSTRUCTION COMPLETE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
11. BTS AND RADIO EQUIPMENT DELIVERED AT SITE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
12. NETWORK OPERATIONS HANDOFF CHECKLIST (HOC WALK) COMPLETE (UPLOAD FORM IN SMS)
13. CIVIL CONSTRUCTION COMPLETE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
14. SITE CONSTRUCTION PROGRESS PHOTOS UNLOADED INTO SMS.

SECTION 01 400 - SUBMITTALS & TESTS

PART 1 - GENERAL

- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
 - A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
 - B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.
- 1.3 SUBMITTALS:
 - A. THE WORK IN ALL ASPECTS SHALL COMPLY WITH THE CONSTRUCTION DRAWINGS AND THESE SPECIFICATIONS.
 - B. SUBMIT THE FOLLOWING TO COMPANY REPRESENTATIVE FOR APPROVAL
 1. CONCRETE MIX-DESIGNS FOR TOWER FOUNDATIONS, ANCHORS PIERS, AND CONCRETE PAVING.
 2. CONCRETE BREAK TESTS AS SPECIFIED HEREIN.
 3. SPECIAL FINISHES FOR INTERIOR SPACES, IF ANY.
 4. ALL EQUIPMENT AND MATERIALS SO IDENTIFIED ON THE CONSTRUCTION DRAWINGS.
 5. CHEMICAL GROUNDING DESIGN
 - D. ALTERNATES: AT THE COMPANY'S REQUEST, ANY ALTERNATIVES TO THE MATERIALS OR METHODS SPECIFIED SHALL BE SUBMITTED TO SPRINT'S CONSTRUCTION MANAGER FOR APPROVAL PRIOR TO BEING SHIPPED TO SITE. SPRINT WILL REVIEW AND APPROVE ONLY THOSE REQUESTS MADE IN WRITING. NO VERBAL APPROVALS WILL BE CONSIDERED. SUBMITTAL FOR APPROVAL SHALL INCLUDE A STATEMENT OF COST REDUCTION PROPOSED FOR USE OF ALTERNATE PRODUCT.

1.4 TESTS AND INSPECTIONS:

- A. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CONSTRUCTION TESTS, INSPECTIONS AND PROJECT DOCUMENTATION.
- B. CONTRACTOR SHALL ACCOMPLISH TESTING INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
 1. COAX SWEEPS AND FIBER TESTS PER TS-0200 REV 4 ANTENNA LINE ACCEPTANCE STANDARDS.
 2. AGL, AZIMUTH AND DOWNTILT USING ELECTRONIC COMMERCIAL MADE-FOR-THE-PURPOSE ANTENNA ALIGNMENT TOOL.
 3. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN SITE INSPECTION ACTIVITIES AND/OR AS A RESULT OF TESTING.
- C. REQUIRED CLOSEOUT DOCUMENTATION INCLUDES, BUT IS NOT LIMITED TO THE FOLLOWING:
 1. AZIMUTH, DOWNTILT, AGL - UPLOAD REPORT FROM ANTENNA ALIGNMENT TOOL TO SITERRA TASK 485. INSTALLED AZIMUTH, DOWNTILT, AND AGL MUST CONFORM TO THE RF DATA SHEETS. SWEEP AND FIBER TESTS
 2. SCANABLE BARCODE PHOTOGRAPHS OF TOWER TOP AND INACCESSIBLE SERIALIZED EQUIPMENT
 3. ALL AVAILABLE JURISDICTIONAL INFORMATION
 4. PDF SCAN OF REDLINES PRODUCED IN FIELD

5. ELECTRONIC AS-BUILT DRAWINGS IN AUTOCAD AND PDF FORMATS. ANY FIELD CHANGE MUST BE REFLECTED BY MODIFYING THE PLANS, ELEVATIONS, AND DETAILS IN THE DRAWING SETS. GENERAL NOTES INDICATING MODIFICATIONS WILL NOT BE ACCEPTED. CHANGES SHALL BE HIGHLIGHTED AS "CLOUDS" IDENTIFIED AS THE "AS-BUILT" CONDITION.
6. LIEN WAIVERS
7. FINAL PAYMENT APPLICATION
8. REQUIRED FINAL CONSTRUCTION PHOTOS
9. CONSTRUCTION AND COMMISSIONING CHECKLIST COMPLETE WITH NO DEFICIENT ITEMS
10. ALL POST NTP TASKS INCLUDING DOCUMENT UPLOADS COMPLETED IN SITERRA (SPRINTS DOCUMENT REPOSITORY OF RECORD).

1.5 COMMISSIONING: PERFORM ALL COMMISSIONING AS REQUIRED BY APPLICABLE MOPs

1.6 INTEGRATION: PERFORM ALL INTEGRATION ACTIVITIES AS REQUIRED BY APPLICABLE MOPs

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION

3.1 REQUIREMENTS FOR TESTING:

A. THIRD PARTY TESTING AGENCY:

1. WHEN THE USE OF A THIRD PARTY INDEPENDENT TESTING AGENCY IS REQUIRED, THE AGENCY THAT IS SELECTED MUST PERFORM SUCH WORK ON A REGULAR BASIS IN THE STATE WHERE THE PROJECT IS LOCATED AND HAVE A THOROUGH UNDERSTANDING OF LOCAL AVAILABLE MATERIALS, INCLUDING THE SOIL, ROCK, AND GROUNDWATER CONDITIONS.
2. THE THIRD PARTY TESTING AGENCY IS TO BE FAMILIAR WITH THE APPLICABLE REQUIREMENTS FOR THE TESTS TO BE DONE, EQUIPMENT TO BE USED, AND ASSOCIATED HEALTH AND SAFETY ISSUES.
3. EXPERIENCE IN SOILS, CONCRETE, MASONRY, AGGREGATE, AND ASPHALT TESTING USING ASTM, AASHTO, AND OTHER METHODS IS NEEDED.
4. EXPERIENCE IN SOILS, CONCRETE, MASONRY, AGGREGATE, AND ASPHALT TESTING USING ASTM, AASHTO, AND OTHER METHODS IS NEEDED.

3.2 REQUIRED TESTS:

A. CONTRACTOR SHALL ACCOMPLISH TESTING INCLUDING BUT NOT LIMITED TO THE FOLLOWING:

1. CONCRETE CYLINDER BREAK TESTS FOR THE TOWER AND ANCHOR FOUNDATIONS AS SPECIFIED IN SECTION: PORTLAND CEMENT CONCRETE PAVING.
2. ASPHALT ROADWAY COMPACTED THICKNESS, SURFACE SMOOTHNESS, AND COMPACTED DENSITY TESTING AS SPECIFIED IN SECTION: HOT MIX ASPHALT PAVING.
3. FIELD QUALITY CONTROL TESTING AS SPECIFIED IN SECTION: PORTLAND CEMENT CONCRETE PAVING.
4. TESTING REQUIRED UNDER SECTION: AGGREGATE BASE FOR ACCESS ROADS, PADS AND ANCHOR LOCATIONS
5. STRUCTURAL BACKFILL COMPACTION TESTS FOR THE TOWER FOUNDATION.
6. SITE RESISTANCE TO EARTH TESTING PER EXHIBIT: CELL SITE GROUNDING SYSTEM DESIGN.
7. ANTENNA AND COAX SWEEP TESTS PER EXHIBIT: ANTENNA TRANSMISSION LINE ACCEPTANCE STANDARDS.
8. GROUNDING AT ANTENNA MASTS FOR GPS AND ANTENNAS
9. ALL OTHER TESTS REQUIRED BY COMPANY OR JURISDICTION.

3.3 REQUIRED INSPECTIONS

A. SCHEDULE INSPECTIONS WITH COMPANY REPRESENTATIVE.

B. CONDUCT INSPECTIONS INCLUDING BUT NOT LIMITED TO THE FOLLOWING:

1. GROUNDING SYSTEM INSTALLATION PRIOR TO EARTH CONCEALMENT DOCUMENTED WITH DIGITAL PHOTOGRAPHS BY CONTRACTOR, APPROVED BY A&E OR SPRINT REPRESENTATIVE.
2. FORMING FOR CONCRETE AND REBAR PLACEMENT PRIOR TO POUR DOCUMENTED WITH DIGITAL PHOTOGRAPHS BY CONTRACTOR, APPROVED BY A&E OR SPRINT REPRESENTATIVE.
3. COMPACTION OF BACKFILL MATERIALS; AGGREGATE BASE FOR ROADS, PADS, AND ANCHORS; ASPHALT PAVING; AND SHAFT BACKFILL FOR CONCRETE AND WOOD POLES, BY INDEPENDENT THIRD PARTY AGENCY.
4. PRE- AND POST-CONSTRUCTION ROOFTOP AND STRUCTURAL INSPECTIONS ON EXISTING FACILITIES.
5. TOWER ERECTION SECTION STACKING AND PLATFORM ATTACHMENT DOCUMENTED BY DIGITAL PHOTOGRAPHS BY THIRD PARTY AGENCY.
6. ANTENNA AZIMUTH, DOWN TILT AND PER SUNLIGHT TOOL SUNSIGHT INSTRUMENTS - ANTENNA ALIGNMENT TOOL (AAT)

PLANS PREPARED FOR:



PLANS PREPARED BY:

INFINIGY
FROM ZERO TO INFINIGY
the solutions are endless
1033 Watervliet Shaker Rd | Albany, NY 12205
Phone: 518-690-0790 | Fax: 518-690-0793
www.infinigy.com
JOB NUMBER 528-104

PROJECT MANAGER:

AIRSMITH
DEVELOPMENT
32 CLINTON ST.
SARATOGA SPRINGS, NY 12866
OFFICE: (518) 308-3740

ENGINEERING LICENSE:



DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR PERMIT	06/27/18	MAP	0

SITE NAME:

WEST HAVEN & RT 162 CT

SITE NUMBER:

CT52XC076

SITE ADDRESS:

**668 JONES HILL ROAD
WEST HAVEN, CT 06516**

SHEET DESCRIPTION:

SPRINT SPECIFICATIONS

SHEET NUMBER:

SP-2

CONTINUE FROM SP-2

7. VERIFICATION DOCUMENTED WITH THE ANTENNA CHECKLIST REPORT, BY A&E, SITE DEVELOPMENT REP, OR RF REP.
 8. FINAL INSPECTION CHECKLIST AND HANDOFF WALK (HOC). SIGNED FORM SHOWING ACCEPTANCE BY FIELD OPS IS TO BE UPLOADED INTO SMS.
 9. COAX SWEEP AND FIBER TESTING DOCUMENTS SUBMITTED VIA SMS FOR RF APPROVAL
 10. SCAN-ABLE BARCODE PHOTOGRAPHS OF TOWER TOP AND INACCESSIBLE SERIALIZED EQUIPMENT
 11. ALL AVAILABLE JURISDICTIONAL INFORMATION
 12. PDF SCAN OF REDLINES PRODUCED IN FIELD
- C. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN SITE INSPECTION ACTIVITIES AND/OR AS A RESULT OF TESTING.
- D. CONSTRUCTION INSPECTIONS AND CORRECTIVE MEASURES SHALL BE DOCUMENTED BY THE CONTRACTOR WITH WRITTEN REPORTS AND PHOTOGRAPHS. PHOTOGRAPHS MUST BE DIGITAL AND OF SUFFICIENT QUALITY TO CLEARLY SHOW THE SITE CONSTRUCTION. PHOTOGRAPHS MUST CLEARLY IDENTIFY THE PHOTOGRAPHED ITEM AND BE LABELED WITH THE SITE CASCADE NUMBER, SITE NAME, DESCRIPTION, AND DATE.
- 3.4 DELIVERABLES: TEST AND INSPECTION REPORTS AND CLOSEOUT DOCUMENTATION SHALL BE UPLOADED TO THE SMS AND/OR FORWARDED TO SPRINT FOR INCLUSION INTO THE PERMANENT SITE FILES.
- A. THE FOLLOWING TEST AND INSPECTION REPORTS SHALL BE PROVIDED AS APPLICABLE.
1. CONCRETE MIX AND CYLINDER BREAK REPORTS.
 2. STRUCTURAL BACKFILL COMPACTION REPORTS.
 3. SITE RESISTANCE TO EARTH TEST.
 4. ANTENNA AZIMUTH AND DOWN TILT VERIFICATION
 5. TOWER ERECTION INSPECTIONS AND MEASUREMENTS DOCUMENTING TOWER INSTALLED PER SUPPLIER'S REQUIREMENTS AND THE APPLICABLE SECTIONS HEREIN.
 6. COAX CABLE SWEEP TESTS PER COMPANY'S "ANTENNA LINE ACCEPTANCE STANDARDS".
- B. REQUIRED CLOSEOUT DOCUMENTATION INCLUDES THE FOLLOWING;
1. TEST WELLS AND TRENCHES: PHOTOGRAPHS OF ALL TEST WELLS; PHOTOGRAPHS SHOWING ALL OPEN EXCAVATIONS AND TRENCHING PRIOR TO BACKFILLING SHOWING A TAPE MEASURE VISIBLE IN THE EXCAVATIONS INDICATING DEPTH.
 2. CONDUITS, CONDUCTORS AND GROUNDING: PHOTOGRAPHS SHOWING TYPICAL INSTALLATION OF CONDUCTORS AND CONNECTORS; PHOTOGRAPHS SHOWING TYPICAL BEND RADIUS OF INSTALLED GROUND WIRES AND GROUND ROD SPACING;
 3. CONCRETE FORMS AND REINFORCING: CONCRETE FORMING AT TOWER AND EQUIPMENT/SHELTER PAD/FOUNDATIONS - PHOTOGRAPHS SHOWING ALL REINFORCING STEEL, UTILITY AND CONDUIT STUB OUTS; PHOTOGRAPHS SHOWING CONCRETE POUR OF SHELTER SLAB/FOUNDATION, TOWER FOUNDATION AND GUY ANCHORS WITH VIBRATOR IN USE; PHOTOGRAPHS SHOWING EACH ANCHOR ON GUYED TOWERS, BEFORE CONCRETE POUR.
 4. TOWER, ANTENNAS AND MAINLINE: INSPECTION AND PHOTOGRAPHS OF SECTION STACKING; INSPECTION AND PHOTOGRAPHS OF PLATFORM COMPONENT ATTACHMENT POINTS; PHOTOGRAPHS OF TOWER TOP GROUNDING; PHOTOS OF TOWER COAX LINE COLOR CODING AT THE TOP AND AT GROUND LEVEL; INSPECTION AND PHOTOGRAPHS OF OPERATIONAL OF TOWER LIGHTING, AND PLACEMENT OF FAA REGISTRATION SIGN; PHOTOGRAPHS SHOWING ADDITIONAL GROUNDING POINTS FOR TOWERS GREATER THAN 200 FEET.; PHOTOS OF ANTENNA GROUND BAR, EQUIPMENT GROUND BAR, AND MASTER GROUND BAR; PHOTOS OF GPS ANTENNA(S); PHOTOS OF EACH SECTOR OF ANTENNAS; ONE PHOTOGRAPH LOOKING AT THE SECTOR AND ONE FROM BEHIND SHOWING THE PROJECTED COVERAGE AREA; PHOTOS OF COAX WEATHERPROOFING - TOP AND BOTTOM; PHOTOS OF COAX GROUNDING---TOP AND BOTTOM; PHOTOS OF ANTENNA AND MAST GROUNDING; PHOTOS OF COAX CABLE ENTRY INTO SHELTER; PHOTOS OF PLATFORM MECHANICAL CONNECTIONS TO TOWER/MONOPOLE.
 5. ROOF TOPS: PRE-CONSTRUCTION AND POST-CONSTRUCTION VISUAL INSPECTION AND PHOTOGRAPHS OF THE ROOF AND INTERIOR TO DETERMINE AND DOCUMENT CONDITIONS; ROOF TOP CONSTRUCTION INSPECTIONS AS REQUIRED BY THE JURISDICTION; PHOTOGRAPHS OF CABLE TRAY AND/OR ICE BRIDGE; PHOTOGRAPHS OF DOGHOUSE/CABLE EXIT FROM ROOF;
 6. SITE LAYOUT - PHOTOGRAPHS OF THE OVERALL COMPOUND, INCLUDING EQUIPMENT PLATFORM FROM ALL FOUR CORNERS.
 7. FINISHED UTILITIES: CLOSE-UP PHOTOGRAPHS OF THE PPC BREAKER PANEL; CLOSE-UP PHOTOGRAPH OF THE INSIDE OF THE TELCO PANEL AND NIU; CLOSE-UP PHOTOGRAPH OF THE POWER METER AND DISCONNECT; PHOTOS OF POWER AND TELCO ENTRANCE TO COMPANY ENCLOSURE; PHOTOGRAPHS AT METER BOX AND/OR FACILITY DISTRIBUTION PANEL.
 8. REQUIRED MATERIALS CERTIFICATIONS: CONCRETE MIX DESIGNS; MILL CERTIFICATION FOR ALL REINFORCING AND STRUCTURAL STEEL; AND ASPHALT PAVING MIX DESIGN.
 9. ANY AND ALL SUBMITTALS BY THE JURISDICTION OR COMPANY.

SECTION 01 400 - SUBMITTALS & TESTS

PART 1 - GENERAL

- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
 - A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
 - B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION

- 3.1 WEEKLY REPORTS:
 - A. CONTRACTOR SHALL PROVIDE SPRINT WITH WEEKLY REPORTS SHOWING PROJECT STATUS. THIS STATUS REPORT FORMAT WILL BE PROVIDED TO THE CONTRACTOR BY SPRINT. THE REPORT WILL CONTAIN SITE ID NUMBER, THE MILESTONES FOR EACH SITE, INCLUDING THE BASELINE DATE, ESTIMATED COMPLETION DATE AND ACTUAL COMPLETION DATE.
 - B. REPORT INFORMATION WILL BE TRANSMITTED TO SPRINT VIA ELECTRONIC MEANS AS REQUIRED. THIS INFORMATION WILL PROVIDE A BASIS FOR PROGRESS MONITORING AND PAYMENT.
- 3.2 PROJECT CONFERENCE CALLS:
 - A. SPRINT MAY HOLD WEEKLY PROJECT CONFERENCE CALLS. CONTRACTOR WILL BE REQUIRED TO COMMUNICATE SITE STATUS, MILESTONE COMPLETIONS AND UPCOMING MILESTONE PROJECTIONS, AND ANSWER ANY OTHER SITE STATUS QUESTIONS AS NECESSARY.
- 3.3 PROJECT TRACKING IN SMS:
 - A. CONTRACTOR SHALL PROVIDE SCHEDULE UPDATES AND PROJECTIONS IN THE SMS SYSTEM ON A WEEKLY BASIS.
- 3.4 ADDITIONAL REPORTING:
 - A. ADDITIONAL OR ALTERNATE REPORTING REQUIREMENTS MAY BE ADDED TO THE REPORT AS DETERMINED TO BE REASONABLY NECESSARY BY COMPANY.
- 3.5 PROJECT PHOTOGRAPHS:
 - A. FILE DIGITAL PHOTOGRAPHS OF COMPLETED SITE IN JPEG FORMAT IN THE SMS PHOTO LIBRARY FOR THE RESPECTIVE SITE. PHOTOGRAPHS SHALL BE CLEARLY LABELED WITH SITE NUMBER, NAME AND DESCRIPTION, AND SHALL INCLUDE AT A MINIMUM THE FOLLOWING AS APPLICABLE:
 1. SHELTER AND TOWER OVERVIEW.
 2. TOWER FOUNDATION(S) - FORMS AND STEEL BEFORE POUR (EACH ANCHOR ON GUYED TOWERS).
 3. TOWER FOUNDATION(S) POUR WITH VIBRATOR IN USE (EACH ANCHOR ON GUYED TOWERS).
 4. TOWER STEEL AS BEING INSTALLED INTO HOLE (SHOW ANCHOR STEEL ON GUYED TOWERS).
 5. PHOTOS OF TOWER SECTION STACKING.
 6. CONCRETE TESTING / SAMPLES.
 7. PLACING OF ANCHOR BOLTS IN TOWER FOUNDATION.
 8. BUILDING/WATER TANK FROM ROAD FOR TENANT IMPROVEMENTS OR COMMENTS.
 9. SHELTER FOUNDATION---FORMS AND STEEL BEFORE POURING.
 10. SHELTER FOUNDATION POUR WITH VIBRATOR IN USE.
 11. COAX CABLE ENTRY INTO SHELTER.
 12. PLATFORM MECHANICAL CONNECTIONS TO TOWER/MONOPOLE.
 13. ROOFTOP PRE AND POST CONSTRUCTION PHOTOS TO INCLUDE PENETRATIONS AND INTERIOR CEILING.
 14. PHOTOS OF TOWER TOP COAX LINE COLOR CODING AND COLOR CODING AT GROUND LEVEL.
 15. PHOTOS OF ALL APPROPRIATE COMPANY OR REGULATORY SIGNAGE.
 16. PHOTOS OF EQUIPMENT BOLT DOWN INSIDE SHELTER.
 17. POWER AND TELCO ENTRANCE TO COMPANY ENCLOSURE AND POWER AND TELCO SUPPLY LOCATIONS INCLUDING METER/DISCONNECT.
 18. ELECTRICAL TRENCH(S) WITH ELECTRICAL / CONDUIT BEFORE BACKFILL.
 19. ELECTRICAL TRENCH(S) WITH FOIL-BACKED TAPE BEFORE FURTHER BACKFILL.
 20. TELCO TRENCH WITH TELEPHONE / CONDUIT BEFORE BACKFILL.
 21. TELCO TRENCH WITH FOIL-BACKED TAPE BEFORE FURTHER BACKFILL.
 22. SHELTER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADII).
 23. TOWER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADII).

24. FENCE GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADII).
 25. ALL BTS GROUND CONNECTIONS.
 26. ALL GROUND TEST WELLS.
 27. ANTENNA GROUND BAR AND EQUIPMENT GROUND BAR.
 28. ADDITIONAL GROUNDING POINTS ON TOWERS ABOVE 200'.
 29. HVAC UNITS INCLUDING CONDENSERS ON SPLIT SYSTEMS.
 30. GPS ANTENNAS.
 31. CABLE TRAY AND/OR WAVEGUIDE BRIDGE.
 32. DOGHOUSE/CABLE EXIT FROM ROOF.
 33. EACH SECTOR OF ANTENNAS; ONE PHOTOGRAPH LOOKING AT THE SECTOR AND ONE FROM BEHIND SHOWING THE PROJECTED COVERAGE AREA.
 34. MASTER BUS BAR.
 35. TELCO BOARD AND NIU.
 36. ELECTRICAL DISTRIBUTION WALL.
 37. CABLE ENTRY WITH SURGE SUPPRESSION.
 38. ENTRANCE TO EQUIPMENT ROOM.
 39. COAX WEATHERPROOFING--TOP AND BOTTOM OF TOWER.
 40. COAX GROUNDING --TOP AND BOTTOM OF TOWER.
 41. ANTENNA AND MAST GROUNDING.
 42. LANDSCAPING - WHERE APPLICABLE.
- 3.6 FINAL PROJECT ACCEPTANCE: COMPLETE ALL REQUIRED REPORTING TASKS PER CONTRACT, CONTRACT DOCUMENTS OR THE SPRINT INTEGRATED CONSTRUCTION STANDARDS FOR WIRELESS SITES AND UPLOAD INTO SITERRA.

PLANS PREPARED FOR:




PLANS PREPARED BY:

INFINIGY
FROM ZERO TO INFINIGY
the solutions are endless
1033 Watervliet Shaker Rd | Albany, NY 12205
Phone: 518-690-0790 | Fax: 518-690-0793
www.Infinigy.com
JOB NUMBER 526-104

PROJECT MANAGER:

AIRSMITH
DEVELOPMENT
32 CLINTON ST.
SARATOGA SPRINGS, NY 12868
OFFICE# (518) 306-3740

ENGINEERING LICENSE:



DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:	DESCRIPTION	DATE	BY	REV.
ISSUED FOR PERMIT		06/27/18	MAP	0

SITE NAME:
**WEST HAVEN &
RT 162 CT**

SITE NUMBER:
CT52XC076

SITE ADDRESS:
**668 JONES HILL ROAD
WEST HAVEN, CT 06516**

SHEET DESCRIPTION:
SPRINT SPECIFICATIONS

SHEET NUMBER:
SP-3

PLANS PREPARED FOR:



PLANS PREPARED BY:

INFINIGY
 FROM ZERO TO INFINIGY
 the solutions are endless
 1033 Watervliet Shaker Rd | Albany, NY 12205
 Phone: 518-690-0790 | Fax: 518-690-0793
 www.infinigy.com
 JOB NUMBER 526-104

PROJECT MANAGER:

AIRSMITH
 DEVELOPMENT
 32 CLINTON ST.
 SARATOGA SPRINGS, NY 12866
 OFFICE# (518) 308-3740

ENGINEERING LICENSE:



DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:	DESCRIPTION	DATE	BY	REV.

ISSUED FOR PERMIT: 06/27/18 MAP 0





SITE NAME:
WEST HAVEN & RT 162 CT

SITE NUMBER:
CT52XC076

SITE ADDRESS:
**668 JONES HILL ROAD
 WEST HAVEN, CT 06516**

SHEET DESCRIPTION:
SITE PLAN

SHEET NUMBER:
A-1



INFORMATION CONTAINED WITHIN DRAWINGS ARE BASED ON PROVIDED INFORMATION AND ARE NOT THE RESULT OF A FIELD SURVEY.

OVERALL SITE PLAN

SCALE: AS NOTED 1

SPRINT EQUIPMENT PLAN

SCALE: AS NOTED 2



PLANS PREPARED BY:
INFINIGY
FROM ZERO TO INFINIGY
the solutions are endless
1033 Watervliet Shaker Rd | Albany, NY 12205
Phone: 518-690-0790 | Fax: 518-690-0793
www.infinigy.com
JOB NUMBER 526-104

PROJECT MANAGER:
AIRSMITH DEVELOPMENT
32 CLINTON ST.
SARATOGA SPRINGS, NY 12866
OFFICER, (518) 308-3740



DRAWING NOTICE:
THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:	DESCRIPTION	DATE	BY	REV.

ISSUED FOR PERMIT: 06/27/18 MAP 0

SITE NAME:
WEST HAVEN & RT 162 CT


SITE NUMBER:
CT52XC076

SITE ADDRESS:
**668 JONES HILL ROAD
WEST HAVEN, CT 06516**

SHEET DESCRIPTION:
**ANTENNA LAYOUT
& MOUNTING DETAILS**

SHEET NUMBER:
A-3

THE CONFIGURATION PLANS ARE BASED ON PROVIDED INFORMATION AND ARE FOR CONCEPTUAL PURPOSES ONLY. CONTRACTOR TO VERIFY FIELD CONDITIONS PRIOR TO CONSTRUCTION.




0' = TRUE NORTH

EXISTING ANTENNA LAYOUT

NO SCALE

1




0' = TRUE NORTH

FINAL ANTENNA & RRH LAYOUT

NO SCALE

2

NOTE:
JUMPERS FROM 2.5 RRH TO THE 2.5 ANTENNA CANNOT EXCEED 15 FEET



NOTE:
CONTRACTOR TO POSITION RRH ON MOUNT BEHIND ANTENNA SUCH THAT THE RRH DOES NOT INTERFERE WITH THE EXISTING PLATFORM/T-ARM MOUNTING HARDWARE.


NOTE:
THE DIAGRAM IS FOR CONCEPTUAL PURPOSES ONLY. CONTRACTOR IS TO REFER TO PASSING STRUCTURAL ANALYSIS FOR ANTENNA AND RRH MOUNTING DETAILS

- NOTES:
- CUT DC CONDUCTORS TO LENGTH.
 - COIL FIBER CABLE AND SECURE AT SIDE OF RRH.
 - DO NOT EXCEED BEND RADIUS.

TYPICAL 2.5 ANTENNA MOUNTING DETAILS

NO SCALE

3



NOTE:
CONTRACTOR TO POSITION RRH ON MOUNT BEHIND ANTENNA SUCH THAT THE RRH DOES NOT INTERFERE WITH THE EXISTING PLATFORM/T-ARM MOUNTING HARDWARE.

NOTE:
THE DIAGRAM IS FOR CONCEPTUAL PURPOSES ONLY. CONTRACTOR IS TO REFER TO PASSING STRUCTURAL ANALYSIS FOR ANTENNA AND RRH MOUNTING DETAILS

- NOTES:
- CUT DC CONDUCTORS TO LENGTH.
 - COIL FIBER CABLE AND SECURE AT SIDE OF RRH.
 - DO NOT EXCEED BEND RADIUS.


TYPICAL DUAL BAND ANTENNA & RRH MOUNTING DETAILS

NO SCALE

4

ANTENNA NOKIA AAHC


RADOME MATERIAL: FIBERGLASS
 RADOME COLOR: LIGHT GREY
 DIMENSIONS, HxWxD.in(mim): 25.6"x19.7"x9.9" (651x501x245mm)
 WEIGHT: 99.2 lbs
 CONNECTORS: (2) 7/16" DIN FEMALE
 (8) 4.1/9.5 DIN FEMALE



2.5 ANTENNA DETAIL

NO SCALE 1

RRH: ALCATEL LUCENT 1900 MHz
 COLOR: LIGHT GREY
 WEIGHT: 70 LBS.
 (INCLUDING OPTIONAL SOLAR SHIELD)



FRONT VIEW

SIDE VIEW


TOP VIEW

1900 MHz RRH


NO SCALE 2

ANTENNA COMMSCOPE NNVV-65B-R4

RADOME MATERIAL: FIBERGLASS
 RADOME COLOR: LIGHT GREY
 DIMENSIONS, HxWxD.in(mim): 71.9"x19.6"x7.8" (1826x498x198mm)
 WEIGHT: 77.4 lbs
 CONNECTORS: (2) 7/16" DIN FEMALE
 (8) 4.1/9.5 DIN FEMALE



PLAN VIEW




SIDE VIEW

FRONT VIEW

DUAL BAND ANTENNA

NO SCALE 3

RRH: ALCATEL LUCENT RRH 800 MHz 2x50W
 COLOR: LIGHT GREY
 WEIGHT: 53 LBS.



SIDE VIEW

FRONT VIEW

PLAN VIEW

800 MHz RRH

NO SCALE 4

NOTES

COMPLY WITH MANUFACTURERS INSTRUCTIONS TO ENSURE THAT ALL RRH'S RECEIVE ELECTRICAL POWER WITHIN 24 HOURS OF BEING REMOVED FROM THE MANUFACTURER'S PACKAGING. DO NOT OPEN RRH PACKAGES IN THE RAIN.

PLANS PREPARED FOR:

PLANS PREPARED BY:

FROM ZERO TO INFINIGY
 the solutions are endless
 1033 Watervliet Shaker Rd | Albany, NY 12205
 Phone: 518-690-0790 | Fax: 518-690-0793
 www.infinigy.com
 JOB NUMBER 526-104

PROJECT MANAGER:

32 CLINTON ST.
 SARATOGA SPRINGS, NY 12868
 OFFICE# (518) 306-3740

ENGINEERING LICENSE:

DRAWING NOTICE:
 THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:	DESCRIPTION	DATE	BY	REV
ISSUED FOR PERMIT		06/27/18	MAP	0


SITE NAME:
WEST HAVEN & RT 162 CT

SITE NUMBER:
CT52XC076

SITE ADDRESS:
**668 JONES HILL ROAD
 WEST HAVEN, CT 06516**

SHEET DESCRIPTION:
EQUIPMENT & MOUNTING DETAILS

SHEET NUMBER:
A-4




ELTEK ECAB EXTERIOR CABINET
P/N: ESOA220-SCA02

EQUIPMENT CABINET DETAIL

NO SCALE

1




ELTEK POWER PROTECTION CABINET
P/N: 5811122212

EQUIPMENT CABINET DETAIL

NO SCALE


2



H-FRAME DETAIL

NO SCALE

3



SUPPORT POST MOUNTING DETAIL

NO SCALE

4

PLANS PREPARED FOR:

PLANS PREPARED BY:

INFINIGY
FROM ZERO TO INFINIGY
the solutions are endless

1033 Watervliet Shaker Rd | Albany, NY 12205
Phone: 518-690-0790 | Fax: 518-690-0793
www.infinigy.com
JOB NUMBER: 526-104

PROJECT MANAGER:

AIRSMITH
DEVELOPMENT

32 CLINTON ST.
SARATOGA SPRINGS, NY 12866
OFFICE# (518) 306-3740

ENGINEERING LICENSE:

DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:	DESCRIPTION	DATE	BY	REV.
ISSUED FOR PERMIT		06/27/18	MAP	0

SITE NAME:

WEST HAVEN & RT 162 CT

SITE NUMBER:

CT52XC076

SITE ADDRESS:

**668 JONES HILL ROAD
WEST HAVEN, CT 06516**

SHEET DESCRIPTION:




EQUIPMENT & MOUNTING DETAILS

SHEET NUMBER:

A-5

RFS HYBRIFLEX RISER CABLE SCHEDULE


Fiber Only (Existing DC Power)	Hybrid cable MN: HB058-M12-050F 12x multi-mode fiber pairs, Top: Outdoor protected connectors, Bottom: LC Connectors, 5/8 cable, 50 ft	50 ft
	MN: HB058-M12-075F	75 ft
	MN: HB058-M12-100F	100 ft
	MN: HB058-M12-125F	125 ft
	MN: HB058-M12-150F	150 ft
	MN: HB058-M12-175F	175 ft
	MN: HB058-M12-200F	200 ft
8 AWG Power	Hybrid cable MN: HB114-08U3M12-050F 3x 8 AWG power pairs, 12x multi-mode fiber pairs, Outdoor rated connectors & LC Connectors, 1 1/4 cable, 50 ft	50 ft
	MN: HB114-08U3M12-075F	75 ft
	MN: HB114-08U3M12-100F	100 ft
	MN: HB114-08U3M12-125F	125 ft
	MN: HB114-08U3M12-150F	150 ft
	MN: HB114-08U3M12-175F	175 ft
	MN: HB114-08U3M12-200F	200 ft
6 AWG Power	Hybrid cable MN: HB114-13U3M12-225F 3x 6 AWG power pair, 12x multi-mode fiber pairs, Outdoor rated connectors & LC Connectors, 1 1/4 cable, 225 ft	225 ft
	MN: HB114-13U3M12-250F	250 ft
	MN: HB114-13U3M12-275F	275 ft
	MN: HB114-13U3M12-300F	300 ft
4 AWG Power	Hybrid cable MN: HB114-21U3M12-325F 3x 4 AWG power pair, 12x multi-mode fiber pairs, Outdoor rated connectors & LC Connectors, 1 1/4 cable, 325 ft	325 ft
	MN: HB114-21U3M12-350F	350 ft
	MN: HB114-21U3M12-375F	375 ft



RFS HYBRIFLEX JUMPER CABLE SCHEDULE

Fiber Only	Hybrid Jumper cable MN: HBF012-M3-5F1 5 ft, 3x multi-mode fiber pairs, Outdoor & LC connectors, 1/2 cable	5 ft
	MN: HBF012-M3-10F1	10 ft
	MN: HBF012-M3-15F1	15 ft
	MN: HBF012-M3-20F1	20 ft
	MN: HBF012-M3-25F1	25 ft
	MN: HBF012-M3-30F1	30 ft
8 AWG Power	Hybrid Jumper cable MN: HBF058-08U1M3-5F1 5 ft, 3x 8 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 5/8 cable	5 ft
	MN: HBF058-08U1M3-10F1	10 ft
	MN: HBF058-08U1M3-15F1	15 ft
	MN: HBF058-08U1M3-20F1	20 ft
	MN: HBF058-08U1M3-25F1	25 ft
	MN: HBF058-08U1M3-30F1	30 ft
6 AWG Power	Hybrid Jumper cable MN: HBF058-13U1M3-5F1 5 ft, 3x 6 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 5/8 cable	5 ft
	MN: HBF058-13U1M3-10F1	10 ft
	MN: HBF058-13U1M3-15F1	15 ft
	MN: HBF058-13U1M3-20F1	20 ft
	MN: HBF058-13U1M3-25F1	25 ft
	MN: HBF058-13U1M3-30F1	30 ft
4 AWG Power	Hybrid Jumper cable MN: HBF078-21U1M3-5F1 5 ft, 3x 4 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 7/8 cable	5 ft
	MN: HBF078-21U1M3-10F1	10 ft
	MN: HBF078-21U1M3-15F1	15 ft
	MN: HBF078-21U1M3-20F1	20 ft
	MN: HBF078-21U1M3-25F1	25 ft
	MN: HBF078-21U1M3-30F1	30 ft

NOTE:
SPRINT CM TO CONFIRM HYBRID OR FIBER RISER CABLE
AND HYBRID OR FIBER JUMPER CABLE MODEL NUMBERS IF
HYBRID CABLES ARE REQUIRED BEFORE PREPARING BOM.



OPTIONAL HYBRID SLACK BOX

NO SCALE 2

PLANS PREPARED FOR:
Sprint

PLANS PREPARED BY:
INFINIGY
FROM ZERO TO INFINIGY
the solutions are endless
1033 Watervliet Shaker Rd | Albany, NY 12205
Phone: 518-690-0790 | Fax: 518-690-0793
www.infinigy.com
JOB NUMBER 526-104

PROJECT MANAGER:
AIRSMITH DEVELOPMENT
32 CLINTON ST.
SARATOGA SPRINGS, NY 12866
OFFICE: (518) 306-3740

ENGINEERING LICENSE:
JOHN S. STEVENS
No. 24705
1.8.2018
PROFESSIONAL ENGINEER

DRAWING NOTICE:
THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:	DESCRIPTION	DATE	BY	REV
ISSUED FOR PERMIT		06/27/18	MAP	0

SITE NAME:
WEST HAVEN & RT 162 CT

SITE NUMBER:
CT52XC076

SITE ADDRESS:
**668 JONES HILL ROAD
WEST HAVEN, CT 06516**

SHEET DESCRIPTION:
CIVIL DETAILS

SHEET NUMBER:
A-6

* PROPOSED CABLE LENGTH WAS DETERMINED USING THE SUM OF THE RAD CENTER OF ANTENNAS, AND DISTANCE FROM EXISTING EQUIPMENT AREA TO TOWER BASE WITH AN ADDITIONAL 20' BUFFER. LENGTH TO BE VERIFIED IN FIELD PRIOR TO ORDERING MATERIALS.


800/1900/2500 CABLE CROSS SECTION DATA

NO SCALE 1

DETAIL NOT USED

NO SCALE 3

ALU 21-MIMO NNVV-65B-R4 wo Filters



PLUMBING DIAGRAM

NO SCALE

1

PLANS PREPARED FOR:




PLANS PREPARED BY:

INFINIGY
FROM ZERO TO INFINIGY
the solutions are endless
1033 Watervliet Shaker Rd | Albany, NY 12205
Phone: 518-690-0790 | Fax: 518-690-0793
www.infinigy.com
JOB NUMBER: 526-104

PROJECT MANAGER:

AIRSMITH
DEVELOPMENT
32 CLINTON ST.
SARATOGA SPRINGS, NY 12866
OFFICE# (518) 306-3740

ENGINEERING LICENSE:



DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV.
ISSUED FOR PERMIT	06/27/18	MAP	0

SITE NAME:

WEST HAVEN &
RT 162 CT

SITE NUMBER:

CT52XC076

SITE ADDRESS:


668 JONES HILL ROAD
WEST HAVEN, CT 06516

SHEET DESCRIPTION:

PLUMBING DIAGRAM

SHEET NUMBER:

A-7



ONE LINE DIAGRAM

NO SCALE

1

GENERAL ELECTRICAL NOTES:

- ALL ELECTRICAL WORK SHALL BE IN ACCORDANCE WITH THE LATEST VERSION OF THE NATIONAL ELECTRICAL CODE AND ALL LOCAL AND STATE CODES, LAWS, AND ORDINANCES.
- ALL UNDERGROUND CONDUIT SHALL BE PVC SCHEDULE 40 UNLESS OTHERWISE INDICATED. CONDUITS EXPOSED ABOVE GROUND SHALL BE RIGID GALVANIZED STEEL. ALL UNDERGROUND CONDUIT SHALL TRANSITION FROM PVC TO RIGID ABOVE GRADE. PROVIDE 36" SEPARATION BETWEEN UNDERGROUND POWER AND TELEPHONE CONDUITS. SUPPLY UTILITY MARKING TAPE BURIED 12" BELOW GRADE ALONG ENTIRE LENGTH OF UNDERGROUND CONDUITS.
- ALL CONDUCTORS SHALL BE COPPER WITH THHN/THWN INSULATION. CONTROL CONDUCTORS SHALL BE STRANDED, POWER & LIGHTING CONDUCTORS SHALL BE SOLID FOR #10 & #12 CONDUCTORS AND STRANDED FOR ALL OTHER SIZES.
- ELECTRICAL DRAWINGS ARE IN PART DIAGRAMMATIC. COORDINATE ELECTRICAL WORK WITH SITE CONDITIONS.
- LOCATE ALL UNDERGROUND UTILITIES BEFORE TRENCHING. IF CONFLICTS ARISE, CONTACT UTILITY COMPANY AND ENGINEER IMMEDIATELY.
- ALL EXPOSED CONDUITS SHALL HAVE WEATHERPROOF CAPS NOT DUCT TAPE.
- PROVIDE 200 LB TEST PULL WIRES IN EACH TELEPHONE AND POWER CONDUIT.
- PULL BOXES SHALL BE INSTALLED AS NEEDED PER NEC UTILITY REQUIREMENTS.

ELECTRICAL NOTES

NO SCALE

2

GENERAL GROUNDING NOTES:

- TO ENSURE PROPER BONDING, ALL CONNECTIONS SHALL BE AS FOLLOWS:
 - #2/0 BARE TINNED SOLID COPPER CONDUCTOR: CADWELDED TO RODS OR GROUND RING
 - LUGS AND BUS BAR (UNLESS NOTED OTHERWISE): SANDED CLEAN, COATED WITH OXIDE INHIBITOR AND BOLTED FOR MAXIMUM SURFACE CONTACT. ALL LUGS SHALL BE COPPER (NO ALUMINUM SHALL BE PERMITTED). PROVIDE LOCK WASHERS FOR ALL MECHANICAL CONNECTIONS FOR GROUND CONDUCTORS. USE STAINLESS STEEL HARDWARE THROUGHOUT.
- ALL GROUNDING CABLE IN CONCRETE OR THROUGH WALLS SHALL BE IN 3/4" PVC CONDUIT. SEAL AROUND CONDUIT THROUGH WALLS. NO METALLIC CONDUIT SHALL BE USED FOR GROUNDING CONDUCTORS.
- OWNER'S REPRESENTATIVE WILL INSPECT CADWELDS AND CONDUCT MEGGER TEST PRIOR TO BURIAL. MAXIMUM 5 OHMS RESISTANCE IS REQUIRED.
- DO NOT INSTALL GROUND RING OUTSIDE OF LEASED AREA.
- MAKE ALL GROUND CONNECTIONS AS SHORT AND DIRECT AS POSSIBLE. AVOID SHARP BENDS. ALL BENDS SHALL BE A MINIMUM 8" RADIUS AND NO GREATER THAN 90 DEGREES.
- ALL CADWELDS TO BURIED GROUND RING SHALL BE THE PARALLEL TYPE, EXCEPT FOR THE GROUND RODS WHICH SHALL BE THE TEE TYPE.
- BOND SERVICE CONDUITS TO GROUND RING AS THEY CROSS. DO NOT EXOTHERMICALLY WELD TO CONDUITS.
- THE CONTRACTOR SHALL NOTIFY THE CONSTRUCTION MANAGER WHEN THE GROUNDING SYSTEM IS COMPLETE. THE CONSTRUCTION MANAGER SHALL INSPECT THE GROUNDING SYSTEM PRIOR TO BACKFILLING.
- THE MINIMUM SPACING BETWEEN GROUND RODS SHALL BE 10'-0" (MAX. 15'-0").
- BOND CIGBE TO EXTERNAL GROUND RING WITH 2 RUNS OF #2 BARE, TINNED, SOLID COPPER CONDUCTOR IN PVC. CONNECT BAR END WITH 2 HOLE LUG, AND "CADWELD" THE OTHER END TO THE EXTERNAL GROUND ROD.
- THE PREFERRED LOCATION FOR COAX GROUNDING IS AT THE BASE OF THE TOWER PRIOR TO THE COAX BEND. BONDING IS SHOWN ON THE ICE BRIDGE DUE TO DIFFICULTY WITH WELDING OR ATTACHING TO TOWER LEGS. CONTRACTOR SHALL ADVISE CONSTRUCTION MANAGER PRIOR TO PLACING CIGBE ON ICE BRIDGE IF MOUNTING TO TOWER LEG IS POSSIBLE.
- BONDING OF THE GROUNDED CONDUCTOR (NEUTRAL) AND THE GROUNDING CONDUCTOR SHALL BE AT THE SERVICE DISCONNECTING MEANS. BONDING JUMPER SHALL BE INSTALLED PER N.E.C. ARTICLE 250-30.

GROUNDING NOTES

NO SCALE

3

PLANS PREPARED FOR:



PLANS PREPARED BY:

INFINIGY
FROM ZERO TO INFINIGY
the solutions are endless
1033 Watervliet Shaker Rd | Albany, NY 12205
Phone: 518-690-0790 | Fax: 518-690-0793
www.infinigy.com
JOB NUMBER 526-104

PROJECT MANAGER:

AIRSMITH
DEVELOPMENT
32 CLINTON ST.
SARATOGA SPRINGS, NY 12886
OFFICE# (518) 306-3740

ENGINEERING LICENSE:



DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR PERMIT	06/27/18	MAP	0

SITE NAME:

WEST HAVEN &
RT 162 CT

SITE NUMBER:

CT52XC076

SITE ADDRESS:

668 JONES HILL ROAD
WEST HAVEN, CT 06516

SHEET DESCRIPTION:

ELECTRICAL &
GROUNDING PLAN

SHEET NUMBER:

E-1



INFINIGY
FROM ZERO TO INFINIGY
the solutions are endless
1033 Watervliet Shaker Rd | Albany, NY 12205
Phone: 518-690-0790 | Fax: 518-690-0793
www.infinigy.com
JOB NUMBER 526-104

AIRSMITH
DEVELOPMENT
32 CLINTON ST.
SARATOGA SPRINGS, NY 12888
OFFICE# (518) 306-3740



DRAWING NOTICE:
THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:	DESCRIPTION	DATE	BY	REV.
ISSUED FOR PERMIT		06/27/18	MAP	0


SITE NAME:
WEST HAVEN & RT 162 CT

SITE NUMBER:
CT52XC076

SITE ADDRESS:
**668 JONES HILL ROAD
WEST HAVEN, CT 06516**

SHEET DESCRIPTION:
ELECTRICAL & GROUNDING PLAN


SHEET NUMBER:
E-2



- LEGEND:**
- EXISTING GROUND RING
 - CADWELD CONNECTION (EXOTHERMIC WELD)
 - ▲ MECHANICAL CONNECTION
 - ⊗ GROUND ROD


GROUNDING PLAN

NO SCALE 1




- LEGEND**
- 1 - TINNED COPPER GROUND BAR, 1/4" x 4" x 24"
 - 2 - INSULATORS (NO INSULATORS ON TOWER)
 - 3 - 5/8" LOCK WASHERS
 - 4 - MOUNTING BRACKET (MOUNT HORIZONTAL ON VERTICAL CABLE LADDER)
 - 5 - 5/8-11 x 1" H.H.C.S.BOLTS
 - 6 - "LOCTITE" THREAD LOCK (RED) ON ALL REMOVABLE BOLTS

- NOTE:**
1. COPPER GROUND BAR 1/4"x4"x24" 2-HOLE CENTERS TO MATCH NEMA DOUBLE LUG CONFIGURATION.
 2. SIMILAR INSTALLATION FOR TOP AND BOTTOM TOWER GROUND BARS AND FOR COAX ENTRY PORT GROUND BARS.



ANTENNA GROUND WIRE INSTALLATION


NO SCALE 3



- NOTE:**
ALL MECHANICAL EXTERNAL TERMINATION SURFACES SHALL BE TREATED WITH T&B KOPR-SHIELD CP6 ANTI-OXIDATION COMPOUND.
"DO NOT DISCONNECT" TAG ON ALL GROUND BAR INTERCONNECTS

EQUIPMENT GROUND CONNECTION

NO SCALE 4



- NOTE:**
DO NOT INSTALL CABLE GROUND KIT AT A BEND AND ALWAYS DIRECT GROUND WIRE DOWN TO GROUND BAR.

CABLE GROUND KIT CONNECTION

NO SCALE 5


TINNED GROUND BAR DETAIL

NO SCALE 2



INFINIGY
 FROM ZERO TO INFINIGY
 the solutions are endless
 1033 Watervliet Shaker Rd | Albany, NY 12205
 Phone: 518-690-0790 | Fax: 518-690-0793
 www.infinigy.com
 JOB NUMBER 526-104

AIRSMITH DEVELOPMENT
 32 CLINTON ST.
 SARATOGA SPRINGS, NY 12866
 OFFICE# (518) 306-3740



THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:	DESCRIPTION	DATE	BY	REV.
ISSUED FOR PERMIT		06/27/18	MAP	0


WEST HAVEN & RT 162 CT

CT52XC076

**668 JONES HILL ROAD
 WEST HAVEN, CT 06516**


ELECTRICAL & GROUNDING DETAILS

E-3



GROUND ROD & INSPECTION SLEEVE DETAIL


NO SCALE 1



CONNECTION OF GROUND WIRES TO GROUND BARS & ANTENNAS


NO SCALE 2

- LEGEND:**
- EXISTING GROUND RING
 - CADWELD CONNECTION (EXOTHERMIC WELD)
 - ▲ MECHANICAL CONNECTION
 - ⊗ GROUND ROD
 - CABLE GROUND KIT



TYPICAL ANTENNA GROUNDING PLAN

NO SCALE 3



GROUNDING RISER DIAGRAM

NO SCALE 4