



Together with Nextel

10 Industrial Ave, Suite 3  
Mahwah, NJ 07430  
Phone: (845)499-4712  
Jennifer Notaro  
Real Estate Consultant

November 4, 2014

**Hand Delivered**

Ms. Melanie A. Bachman  
Acting Executive Director  
Connecticut Siting Council  
10 Franklin Square  
New Britain, CT 06051

CC to Property Owner  
TOWN OF WESTON  
56 Norfield Road  
Weston, CT 06883

RE: Sprint Spectrum L.P. notice of intent to modify an existing telecommunications facility located at 237 Godfrey Road Weston, CT 06883. Known to Sprint Spectrum L.P. as site CT33XC522.

Dear Ms. Bachman:

In order to accommodate technological changes, implement Code Division Multiple Access (“CDMA”) and/or Long Term Evolution (“LTE”) capabilities, and enhance system performance in the state of Connecticut, Sprint Spectrum L.P. plans to modify the equipment configurations at many of its existing cell sites. Please accept this letter and attachments as notification, pursuant to R.C.S.A. Section 16-50j-73, of construction which constitutes an exempt modification pursuant to R.C.S.A. Section 16-50j-72(b)(2). In compliance with R.C.S.A. Section 16-50j-73, a copy of this letter and its attachments is being sent to the chief elected official of the municipality in which affected cell site is located.

CDMA employs Spread-Spectrum technology and special coding scheme to allow multiple users to be multiplexed over the same physical channel.

LTE is a new high-performance air interface for cellular mobile communications. It is designed to increase the capacity and speed of mobile telephone networks.

Attached is a summary of the planned modifications, including power density calculations reflecting the change in Sprint's operations at the site. Also included is documentation of the structural sufficiency of the tower to accommodate the revised antenna configuration.

The changes to the facility do not constitute modification as defined Connecticut General Statutes ("C.G.S.") Section 16-50i(d) because the general physical characteristics of the facility will not be significantly changed or altered. Rather, the planned changes to the facility fall squarely within those activities explicitly provided for the R.C.S.A. Section 16-50j-72(b)(2).

1. The height of the overall structure will not be affected.
2. The proposed changes will not extend the site boundaries. There will be no effect on the site compound.
3. The proposed changes will not increase the noise level at the existing facility by 6 decibels or more.
4. Radio Frequency power density may increase due to the use of one or more CDMA transmissions. Moreover, LTE will utilize additional radio frequencies newly licensed by the FCC for cellular mobile communications. However, the changes will not increase the calculated "worst case" power density for the combined operations at the site to a level at or above the applicable standard for uncontrolled environments as calculated for a mixed frequency site.

For the foregoing reasons Sprint Spectrum L.P. respectfully submits that the proposed changes at the referenced site constitute exempt modifications under R.C.S.A. Section 16-50j-72(b)(2).

Please feel free to call me at (201)-704-8157 or email [JArdis@Transcendwireless.com](mailto:JArdis@Transcendwireless.com) with questions concerning this matter. Thank you for your consideration.

Sincerely,

Jennifer Ardis  
Real Estate Consultant

RADIO FREQUENCY FCC REGULATORY COMPLIANCE  
MAXIMUM PERMISSIBLE EXPOSURE (MPE) ASSESSMENT

Sprint Existing Facility

Site ID: CT33XC522

Transfer Station

237 Godfrey Road  
Weston, CT 06883

**November 4, 2014**

**EBI Project Number: 62145909**

November 4, 2014

Sprint  
Attn: RF Engineering Manager  
1 International Boulevard, Suite 800  
Mahwah, NJ 07495

Re: Radio Frequency Maximum Permissible Exposure (MPE) Assessment for Site:  
**CT33XC522 - Transfer Station**

**Site Total: 31.13% - MPE% in full compliance**

EBI Consulting was directed to analyze the proposed upgrades to the existing Sprint facility located at **237 Godfrey Road, Weston, CT**, for the purpose of determining whether the radio frequency (RF) exposure levels from the proposed Sprint equipment upgrades on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter ( $\mu\text{W}/\text{cm}^2$ ). The number of  $\mu\text{W}/\text{cm}^2$  calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits, therefore it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) – (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general public may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general public would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

Public exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter ( $\mu\text{W}/\text{cm}^2$ ). The general population exposure limit for the cellular band (850 MHz Band) is approximately  $567 \mu\text{W}/\text{cm}^2$ , and the general population exposure limit for the 1900 MHz and 2500 MHz bands is  $1000 \mu\text{W}/\text{cm}^2$ . Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.

Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure. Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

## **CALCULATIONS**

Calculations were done for the proposed upgrades to the existing Sprint Wireless antenna facility located at **237 Godfrey Road, Weston, CT**, using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. All calculations were performed assuming a lobe representing the maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was focused at the base of the tower. For this report the sample point is the top of a 6 foot person standing at the base of the tower.

For all calculations, all emissions were calculated using the following assumptions:

- 1) 2 channels in the 1900 MHz Band were considered for each sector of the proposed installation.
- 2) 1 channel in the 800 MHz Band was considered for each sector of the proposed installation.
- 3) 2 channels in the 2500 MHz Band were considered for each sector of the proposed installation.
- 4) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 - Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.

- 5) For the following calculations the sample point was the top of a six foot person standing at the base of the tower. The maximum gain of the antenna per the antenna manufactures supplied specifications minus 10 dB was used in this direction. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 6) The antennas used in this modeling are the RFS APXVSPP18-C-A20 and the RFS APXVTM14-C-I20. This is based on feedback from the carrier with regards to anticipated antenna selection. The RFS APXVSPP18-C-A20 has a 15.9 dBd gain value at its main lobe at 1900 MHz and 13.4 dBd at its main lobe for 850 MHz. The RFS APXVTM14-C-I20 has a 15.9 dBd gain value at its main lobe at 2500 MHz. The maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was used for all calculations. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 7) The antenna mounting height centerline for the proposed antennas is **174 feet** above ground level (AGL).
- 8) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.

All calculation were done with respect to uncontrolled / general public threshold limits

Site ID	CT33XC52Z - Transfer Station
Site Address	237 Godfrey Road, Weston, CT, 06883
Site Type	Self Support Tower

Sector 1																
Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain (10 db reduction)	Antenna Height (ft)	analysis height	Cable Size	Cable Loss (dB)	Additional Loss (dB)	ERP	Power Density Percentage
1a	RFS	APXVSP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	2	40	5.9	174	168	1/2 "	0.5	0	138.69	0.18%
1a	RFS	APXVSP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	3.4	174	168	1/2 "	0.5	0	39.00	0.09%
1B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	5.9	174	168	1/2 "	0.5	0	138.69	0.31%
Sector total Power Density Value:													0.58%			

Sector 2																
Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain (10 db reduction)	Antenna Height (ft)	analysis height	Cable Size	Cable Loss (dB)	Additional Loss (dB)	ERP	Power Density Percentage
2a	RFS	APXVSP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	2	40	5.9	174	168	1/2 "	0.5	0	138.69	0.18%
2a	RFS	APXVSP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	3.4	174	168	1/2 "	0.5	0	39.00	0.09%
2B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	5.9	174	168	1/2 "	0.5	0	138.69	0.31%
Sector total Power Density Value:													0.58%			

Sector 3																
Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain (10 db reduction)	Antenna Height (ft)	analysis height	Cable Size	Cable Loss (dB)	Additional Loss (dB)	ERP	Power Density Percentage
3a	RFS	APXVSP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	2	40	5.9	174	168	1/2 "	0.5	0	138.69	0.18%
3a	RFS	APXVSP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	3.4	174	168	1/2 "	0.5	0	39.00	0.09%
3B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	5.9	174	168	1/2 "	0.5	0	138.69	0.31%
Sector total Power Density Value:													0.58%			

Site Composite MPE %	
Carrier	MPE %
Sprint	1.73%
Weston Police	0.22%
Weston FD	0.23%
Weston EMS	0.23%
Weston Public Works	0.22%
Verizon Wireless	19.46%
AT&T	8.93%
T-Mobile	0.11%
<b>Total Site MPE %</b>	<b>31.13%</b>

## Summary

All calculations performed for this analysis yielded results that were well within the allowable limits for general public Maximum Permissible Exposure (MPE) to radio frequency energy.

The anticipated Maximum Composite contributions from the Sprint facility are **1.73% (0.58% from sector 1, 0.58% from sector 2 and 0.58% from sector 3)** of the allowable FCC established general public limit considering all three sectors simultaneously sampled at the ground level.

The anticipated composite MPE value for this site assuming all carriers present is **31.13%** of the allowable FCC established general public limit sampled at 6 feet above ground level. This total composite site value is based upon MPE values listed in the Connecticut Siting Council database for existing carrier emissions.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.



**Scott Heffernan**  
RF Engineering Director

**EBI Consulting**  
21 B Street  
Burlington, MA 01803





# RAMAKER & ASSOCIATES, INC.

## STRUCTURAL ASSESSMENT - 185-FOOT SELF-SUPPORT TOWER FOR: TRANSCEND WIRELESS - SPRINT


**SITE NAME: TRANSFER STATION**  
**SITE ID: CT33XC522**

**TOWER: PASS - 96.1% (WITH MODIFICATIONS)**  
**FOUNDATION: PASS (WITH MODIFICATIONS)**  
**MOUNT: PASS**

**RAMAKER & ASSOCIATES, INC.**  
**JOB NUMBER: 28737**

1120 Dallas Street, Sauk City, WI 53583  
Phone: 608-643-4100 ▲ Fax: 608-643-7999  
[www.ramaker.com](http://www.ramaker.com)

MATCHLINE SEE SHEET C106



**TRANSFER STATION (CT33XC522)**

---

---

**STRUCTURAL ASSESSMENT**

**SITE:** Transfer Station (CT33XC522)  
237 Godfrey Road  
Weston, Fairfield County, Connecticut 06883

**PREPARED FOR:** Transcend Wireless

**CONTACT PERSON:** Mike Kithcart  
Transcend Wireless  
48 Spruce Street, Oakland, NJ 07436


**PREPARED BY:** Ramaker & Associates, Inc.  
1120 Dallas Street  
Sauk City, Wisconsin 53583  
Telephone: (608) 643-4100  
Facsimile: (608) 643-7999

**RAMAKER JOB NUMBER:** 28737

**DATE OF REPORT ISSUANCE:** October 15, 2014

  
\_\_\_\_\_  
Adam Kraus  
Engineering Technician

10/15/14  
Date

  
\_\_\_\_\_  
James R. Skowronski, P.E.  
Supervising Engineer

10/15/14  
Date



**TABLE OF CONTENTS**

**EXECUTIVE SUMMARY..... 3**

**INTRODUCTION..... 4**

    2.1 PROJECT INFORMATION

    2.2 PURPOSE OF REPORT

    2.3 SCOPE OF SERVICES

**MODEL DEVELOPMENT..... 5**

    3.1 INTRODUCTION

    3.2 EXISTING STRUCTURE INFORMATION

    3.3 TOWER LOADING

    3.4 PROPOSED TOWER AND FOUNDATION MODIFICATIONS

    3.5 WIND AND ICE LOAD

**ANALYSIS RESULTS..... 7**

    4.1 ANALYSIS RESULTS

    4.2 BASE REACTIONS

    4.3 MOUNT ASSESSMENT

**LIMITATIONS..... 9**

**REFERENCES.....10**

**LIST OF APPENDICES**

- A. TOWER FIGURES
- B. TOWER CALCULATIONS
- C. MOUNT CALCULATIONS
- D. TOWER AND FOUNDATION MODIFICATION DRAWINGS

**SECTION 1**  
**EXECUTIVE SUMMARY**

This report summarizes the structural analysis conducted by Ramaker & Associates, Inc. (RAMAKER) for Transcend Wireless on behalf of Sprint, who intends to install additional equipment on an existing tower.

The Sprint proposed loading installing three (3) RFS APXV9TM14-ALU-120 panel antennas and three (3) Alcatel-Lucent TD-RRH8x20 units on the three (3) existing T-frames at a centerline elevation of 174-feet AGL. The proposed antennas shall be fed with one (1) proposed 1-1/4-inch hybrid cable that shall be routed up the existing Sprint feedline ladder.

Existing tower members and the existing foundation could become overstressed under proposed loading conditions. ***The existing tower and foundation shall be modified per the modification drawings in Appendix D of this report prior to any equipment loading changes.***

Results of our tower analysis show that the ***modified*** tower will be stressed to a maximum of 96.1 percent of capacity under proposed loading conditions ***after all required tower modifications have been completed.***

The ***modified*** foundation was analyzed utilizing the foundation drawings and geotechnical report referenced below and it was determined that the ***modified*** foundation will provide adequate strength under proposed loading conditions ***after all required foundation modifications have been completed.***

Results of our mount assessment show that by engineering calculation and inspection, the antenna and RRH mounting structure is capable of supporting the existing and proposed Sprint 2.5 equipment deployment without causing an overstress condition in the antenna and RRH mounting structure.

In summary, the ***modified*** tower and ***modified*** foundation will pass the TIA/EIA-222-F code requirements under proposed loading conditions ***after all required tower and foundation modifications have been completed.*** The mounting structure will pass the TIA-222 code requirements under proposed loading conditions.

**SECTION 2  
INTRODUCTION**

**2.1 PROJECT INFORMATION**

This report summarizes the structural analysis conducted by Ramaker & Associates, Inc. (RAMAKER) for Transcend Wireless on behalf of Sprint, who intends to install additional equipment on an existing tower.

**2.2 PURPOSE OF REPORT**

The analysis activities of this report were conducted for the purposes of creating and analyzing a model of the subject structure under the required loading conditions. Base reactions from the resulting model were also determined for tower foundation and support development. Recommendations regarding the analysis results, loading configuration, and structural modifications are also provided.

**2.3 SCOPE OF SERVICES**

RAMAKER developed a finite element model (FEM) of the tower, using tnxTower, for member force, joint deflection, and structure reaction determinations. Subsequently, this report was drafted to provide our engineering recommendations. All information contained herein is valid only for the described structure configuration and loading conditions. RAMAKER reserves the right to modify our recommendations should alterations to the tower loading occur.

**SECTION 3  
MODEL DEVELOPMENT**

**3.1 INTRODUCTION**

RAMAKER developed a FEM of the tower superstructure. Required static loads consisting of the antenna configuration, wind forces, ice loads, and linear appurtenances (including cable loads) were then applied to the FEM. As a result, all member forces, allowable capacities, and base reactions were computed. Additionally, potentially overstressed members were identified.

**3.2 EXISTING STRUCTURE INFORMATION**

Existing structure information was gathered from:

- Tower and foundation drawings by Sabre, proposal #06-8653-MJB-R3, dated June 20, 2006
- Previous structural analysis by Centek Engineering, project #14001.010, dated April 9, 2014
- Previous structural analysis by CHA, project #22702-1018-28000-R1, dated July 22, 2011

**\*\* Note: It was assumed that all modifications to the original tower and foundation have been or will be completed as modeled and specified in the previous structural analyses by Centek Engineering and CHA referenced above. The contractor shall be responsible for verifying these modifications prior to any new equipment installation.**

**3.3 TOWER LOADING**

RAMAKER understands that the tower loading to be used for this analysis will consist of the existing and proposed antenna, mount, and cable configurations as shown in the following chart:

Elevation	Appurtenance	Mount	Coax	Owner	Status
185	(2) 8' Dipole	Leg Mount	(3) 7/8	Municipal	Existing
	(1) 15' Omni				
185	(4) Ericsson AIR 21 B2A B4P	(3) T-Frames	(12) 1-5/8 (1) 1-1/4 Hybrid	T-Mobile	Existing & Future
	(2) Ericsson AIR 21 B2A B2P				
	(6) Ericsson KRY 112 71				
174	(3) RFS APXVSP18-C	(3) T-Frames	(3) 1-1/4 Hybrid	Sprint	Existing
	(3) Alcatel-Lucent 1900MHz RRH				
	(3) Alcatel-Lucent 800MHz RRH				
	(3) RFS APXV9TM14-ALU-120		(1) 1-1/4 Hybrid		Proposed
	(3) Alcatel-Lucent TD-RRH8x20				
164	(3) Antel BXA-70063-6CF	(3) T-Frames	(18) 1-5/8 (1) 1-5/8 Hybrid	Verizon	Existing & Future
	(4) Decibel DB846F65ZAXY				
	(2) Decibel DB846H80E-SX				
	(6) Kathrein Scala 742 213				
	(3) Alcatel-Lucent RRH2x40-AWS				
	(1) RFS DB-T1-6Z-8AB-OZ				

## TRANSFER STATION (CT33XC522)

Elevation	Appurtenance	Mount	Coax	Owner	Status
154	(6) Powerwave 7770	(3) T-Frames	(12) 1-5/8 (2) Power (1) Fiber	AT&T	Existing
	(3) Powerwave P65-16-XLH-RR				
	(6) Powerwave LGP214nn				
	(3) Powerwave TT19-08BP111-001				
	(3) Ericsson RRUS-11				
	(1) Raycap DC6-48-60-18-8F				
146	(1) 15' Omni	(2) 6' Standoffs	(4) 7/8	Municipal	Existing
	(2) 8' Dipole				
138	(1) 3' Dish w/Radome	(1) 2' Standoff	(1) 1/2	Municipal	Existing

### 3.4 PROPOSED TOWER AND FOUNDATION MODIFICATIONS

*The existing tower and foundation shall be modified per the modification drawings in Appendix D of this report prior to any equipment loading changes.* All existing secondary and redundant bracing members and their associated hardware from 0- to 80-feet AGL and 100- to 140-feet AGL shall be removed. New secondary horizontal bracing shall be installed from 140- to 160-feet AGL. The existing diagonal members from 0- to 20-feet AGL, 40- to 60-feet AGL, 80- to 100-feet AGL, and 140- to 180-feet AGL shall be replaced with new diagonal members. The existing tower legs from 0- to 140-feet AGL shall be reinforced with new reinforcing angles along the length of each leg section. The existing foundation shall be modified by placing concrete on top of the existing footing up to the top of the existing piers. Further details regarding the required tower and foundation modifications can be found in Appendix D of this report.

### 3.5 WIND AND ICE LOAD

Wind forces used in model development are in compliance with the TIA/EIA-222-F Standard. These guidelines call for an analysis to be performed which assumes a basic wind speed of 85 miles-per-hour (mph) without ice in Fairfield County. The tower is also designed for a 74 mph basic wind speed with 0.50-inch of radial ice.

**SECTION 4**  
**ANALYSIS RESULTS**

**4.1 ANALYSIS RESULTS**

The *modified* tower superstructure was analyzed with the combined existing and proposed antenna loading with and without radial ice. The computed maximum tower member stress capacities are as follows:

Component Type	Percent Capacity
Leg	89.9
Diagonal	90.0
Horizontal	21.5
Secondary Horizontal	10.0
Bolt	96.1
<b>RATING =</b>	<b>96.1</b>

**4.2 BASE REACTIONS**

The computed maximum reactions under the corresponding maximum moment are as follows:

Load Type	Proposed Model
Total Axial (k)	88.8
Total Shear (k)	57.5
Total Moment (k-ft)	6223.7
Leg Uplift (k)	297.5
Leg Compression (k)	371.8
Leg Shear (k)	31.7

The *modified* foundation was analyzed utilizing the foundation drawings and geotechnical report referenced below and it was determined that the *modified* foundation will provide adequate strength under proposed loading conditions *after all required foundation modifications have been completed.*



## **TRANSFER STATION (CT33XC522)**

---

---

### **4.3 MOUNT ASSESSMENT**

By engineering calculation and inspection, the antenna mounting structure is capable of supporting the existing and proposed Sprint 2.5 equipment deployment without causing an overstress condition in the antenna mounting structure.

This assessment is inclusive of the entire antenna mounting structure, including tower platforms, arms, and all other aspects of the mounting structure that will support the Sprint 2.5 equipment deployment. This assessment assumes that the mounting structure(s) has been installed correctly, is free from deterioration, and is maintained properly.

**SECTION 5  
LIMITATIONS**

The recommendations contained within this report were developed using general project information provided by the owner, tower manufacturer, general field observations, reference information and laboratory testing data, as applicable. All recommendations pertain only to the proposed tower construction, location, and loading as described in this report. RAMAKER assumes no responsibility for failures caused by factors beyond our control. These include but are not limited to the following:

1. Missing, corroding, and/or deteriorating members
2. Improper manufacturing and/or construction
3. Improper maintenance

RAMAKER assumes no responsibility for modifications completed prior to or hereafter in which RAMAKER was not directly involved. These modifications include but are not limited to the following:

1. Replacing or strengthening bracing members
2. Reinforcing or extending vertical members
3. Installing or removing antenna mounting gates or side arms
4. Changing loading configurations

Furthermore, RAMAKER hereby states that this document represents the entire report and that it assumes no liability for any factual changes that may occur after the date of this report. All representations, recommendations and conclusions are based on the information contained and set forth herein. If you are aware of any information contrary to that contained herein, or if you are aware of any defects arising from the original design, material, fabrication and erection deficiencies, you should disregard this report and immediately contact RAMAKER. RAMAKER isn't liable for any representation, recommendation or conclusion not expressly stated herein.


The tower owner is responsible for verifying that the existing loading on the tower is consistent with the loading applied to the tower within this report.

**SECTION 6**  
**REFERENCES**

1. 2003 International Building Code.
2. Telecommunications Industries Association, Structural Standards for Steel Antenna Towers and Antenna Supporting Structures, TIA Standard TIA/EIA-222-F 1996, Washington, D.C.

**APPENDIX A**  
**TOWER FIGURES**

Section	11	12	13	14	15	16	17	18	19	20	21
Lease	P2.5x.203	P2.5x.375	P3.5x0.319 + L3.5x3.5x0.375	P3.5x0.319 + L3.5x0.375	P5x0.238 + L5.5x0.375	P5x0.375 + L5x0.375	P5x0.375 + L5x0.500	P8x0.322 + L8x8x0.500	P8x0.322 + L8x8x0.500	P8x0.322 + L8x8x0.500	P8x0.322 + L8x8x0.500
Leg Grade	L2x2x1/4	L2x2x1/4	L2x2x3/16	L2x2x3/16	L3x3x3/16	L3x3x3/16	L3x3x3/8	L3x3x3/8	L3x3x3/8	L3x3x3/8	L3x3x3/8
Diagonals											
Diagonal Grade											
Top Chls											
Sec. Horizontal											
Face Width (ft.)											
# Panels @ (ft.)											
Weight (lb) / 2684.2											



MAX. CORNER REACTIONS AT BASE:

DOWN: 371821 lb  
SHEAR: 31685 lb

UPLIFT: -297453 lb  
SHEAR: 30176 lb

AXIAL 88817 lb

SHEAR 57462 lb      MOMENT 6223742 lb-ft

TORQUE 9519 lb-ft  
74 mph WIND - 0.5000 in ICE

AXIAL 56475 lb

SHEAR 56156 lb      MOMENT 6098448 lb-ft

TORQUE 8251 lb-ft  
REACTIONS - 85 mph WIND

**DESIGNED APPURTENANCE LOADING**

TYPE	ELEVATION	TYPE	ELEVATION
8 Dipole (Municipal)	185	DB846F65ZAXY w/ Mount Pipe (Verizon)	164
19 Omni (Municipal)	185	742 213 w/ Mount Pipe (Verizon)	164
8 Dipole (Municipal)	185	742 213 w/ Mount Pipe (Verizon)	164
Andrew 12-4" Universal Sector Frame (T-Mobile)	185	742 213 w/ Mount Pipe (Verizon)	164
Andrew 12-4" Universal Sector Frame (T-Mobile)	185	742 213 w/ Mount Pipe (Verizon)	164
Andrew 12-4" Universal Sector Frame (T-Mobile)	185	742 213 w/ Mount Pipe (Verizon)	164
(2) A/R 21 B2A B4P w/ Mount Pipe (T-Mobile)	185	742 213 w/ Mount Pipe (Verizon)	164
(2) A/R 21 B2A B4P w/ Mount Pipe (T-Mobile)	185	RRH 2x40 AW S (Verizon)	164
(2) A/R 21 B2A B4P w/ Mount Pipe (T-Mobile)	185	RRH 2x40 AW S (Verizon)	164
(2) KRY 112 71 (T-Mobile)	185	RRH 2x40 AW S (Verizon)	164
(2) KRY 112 71 (T-Mobile)	185	DB-T1-62-84B-02 (Verizon)	164
(2) KRY 112 71 (T-Mobile)	185	Andrew 12-4" Quik-Tea Sector Frame (ATT)	154
Andrew 12-4" Universal Sector Frame (Sprint)	174	Andrew 12-4" Quik-Tea Sector Frame (ATT)	154
Andrew 12-4" Universal Sector Frame (Sprint)	174	Andrew 12-4" Quik-Tea Sector Frame (ATT)	154
Andrew 12-4" Universal Sector Frame (Sprint)	174	RA21.7770.00(ATT)	154
APXVSPPI8-C w/ Mount Pipe (Sprint)	174	RA21.7770.00(ATT)	154
APXVSPPI8-C w/ Mount Pipe (Sprint)	174	RA21.7770.00(ATT)	154
APXVSPPI8-C w/ Mount Pipe (Sprint)	174	RA21.7770.00(ATT)	154
1900MHz 4x40W RRH (Sprint)	174	RA21.7770.00(ATT)	154
1900MHz 4x40W RRH (Sprint)	174	RA21.7770.00(ATT)	154
1900MHz 4x40W RRH (Sprint)	174	P65-16-XLH-RR w/ Mount Pipe (ATT)	154
800MHz 2x50W RRH (Sprint)	174	P65-16-XLH-RR w/ Mount Pipe (ATT)	154
800MHz 2x50W RRH (Sprint)	174	P65-16-XLH-RR w/ Mount Pipe (ATT)	154
800MHz 2x50W RRH (Sprint)	174	(2) LSP214m (ATT)	154
APXV9T114-C-20 w/ Mount Pipe (Sprint)	174	(2) LSP214m (ATT)	154
APXV9T114-C-20 w/ Mount Pipe (Sprint)	174	(2) LSP214m (ATT)	154
APXV9T114-C-20 w/ Mount Pipe (Sprint)	174	TT19-08BP11-001 (ATT)	154
TD-RRH&20-25 (Sprint)	174	TT19-08BP11-001 (ATT)	154
TD-RRH&20-25 (Sprint)	174	TT19-08BP11-001 (ATT)	154
TD-RRH&20-25 (Sprint)	174	RRUS-11 (ATT)	154
Andrew 12-4" Quik-Tea Sector Frame (Verizon)	164	RRUS-11 (ATT)	154
Andrew 12-4" Quik-Tea Sector Frame (Verizon)	164	RRUS-11 (ATT)	154
Andrew 12-4" Quik-Tea Sector Frame (Verizon)	164	DC6-48-60-18-8F (ATT)	154
BXA-70063-6CF-EDN-X w/ Mount Pipe (Verizon)	164	6' Standoff (Municipal)	146
BXA-70063-6CF-EDN-X w/ Mount Pipe (Verizon)	164	6' Standoff (Municipal)	146
BXA-70063-6CF-EDN-X w/ Mount Pipe (Verizon)	164	15' Omni (Municipal)	146
DB846F65ZAXY w/ Mount Pipe (Verizon)	164	8' Dipole (Municipal)	146
DB846F65ZAXY w/ Mount Pipe (Verizon)	164	8' Dipole (Municipal)	146
DB846F65ZAXY w/ Mount Pipe (Verizon)	164	Z Standoff (Dash)	138
DB846F65ZAXY w/ Mount Pipe (Verizon)	164	Andrew 3 w/ Radome (Sprint)	138
DB846F65ZAXY w/ Mount Pipe (Verizon)	164		

**MATERIAL STRENGTH**

GRADE	Fy	Fu	GRADE	Fy	Fu
A572-50	50 ksi	65 ksi	A36	36 ksi	58 ksi


**TOWER DESIGN NOTES**

1. Tower is located in Fairfield County, Connecticut.
2. Tower designed for a 85 mph basic wind in accordance with the TIA/EIA-222-F Standard.
3. Tower is also designed for a 74 mph basic wind with 0.50 in ice.
4. Deflections are based upon a 60 mph wind.
5. TOWER RATING: 96.1%

<p><b>Ramaker &amp; Associates</b> 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999</p>	<p>Project: <b>28737</b></p> <p>Client: <b>Transcend Wireless / Sprint</b></p> <p>Code: <b>TIA/EIA-222-F</b></p> <p>Path: <b>1:2400@24737@inc\local\mc28737.rvt.dwg</b></p>	<p>Drawn by: <b>A. Kraus</b></p> <p>Date: <b>10/10/14</b></p> <p>Scale: <b>NTS</b></p> <p>Dwg No. <b>E-1</b></p>
	<p>Project: <b>Transfer Station (CT33XC522)</b></p>	
	<p>App'd:</p>	
	<p>Scale: <b>NTS</b></p>	

TIA/EIA-222-F - 85 mph/74 mph 0.5000 in Ice

Leg Capacity ——— Leg Compression (lb)



 <p><b>Ramaker &amp; Associates</b> 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999</p>	<b>Job: Transfer Station (CT33XC522)</b>		
	Project: 28737		
	Client: Transcend Wireless / Sprint	Drawn by: A. Kraus	App'd:
	Code: TIA/EIA-222-F	Date: 10/10/14	Scale: NTS
	Path: I:\28700\28737\Structural\Inxi\28737 rev1.rvt		Dwg No. E-3


Vx

Vz


Mx

Mz




Global Mast Shear (lb)



Global Mast Moment (lb-ft)



 <p><b>Ramaker &amp; Associates</b> 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999</p>	<b>Job: Transfer Station (CT33XC522)</b>		
	Project: 28737		
	Client: Transcend Wireless / Sprint	Drawn by: A. Kraus	App'd:
	Code: TIA/EIA-222-F	Date: 10/10/14	Scale: NTS
	Path: I:\28700\28737\Structural\Inx\28737_rev1.er		Dwg No. E-4




 <p><b>Ramaker &amp; Associates</b> 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999</p>	<b>Job: Transfer Station (CT33XC522)</b>		
	Project: 28737		
	Client: Transcend Wireless / Sprint	Drawn by: A. Kraus	App'd:
	Code: TIA/EIA-222-F	Date: 10/10/14	Scale: NTS
	Path: I:\28700\28737\Structural\Inx\28737 rev1.eri		Dwg No. E-5



# Feed Line Plan

— Round   
 — Flat   
 — App In Face   
 — App Out Face




	<b>Ramaker &amp; Associates</b>			<b>Job: Transfer Station (CT33XC522)</b>		
	1120 Dallas St.			Project: <b>28737</b>		
	Sauk City, WI 53583			Client: Transcend Wireless / Sprint		Drawn by: A. Kraus
	Phone: (608) 643-4100			Code: TIA/EIA-222-F		Date: 10/10/14
	FAX: (608) 643-7999			Path: I:\28700\28737\Structural\ltx\28737 rev1.dwg		Scale: NTS
					Dwg No. E-7	

# Feed Line Distribution Chart

## 0' - 185'

— Round   
 — Flat   
 — App In Face   
 — App Out Face   
 — Truss Leg




 <b>Ramaker &amp; Associates</b> 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job: Transfer Station (CT33XC522)</b>		
	Project: <b>28737</b>		
	Client: Transcend Wireless / Sprint	Drawn by: A. Kraus	App'd:
	Code: TIA/EIA-222-F	Date: 10/10/14	Scale: NTS
	Path: I:\28700\28737\Structural\Inx\28737_rev1.rvt		Dwg No. E-7

# Stress Distribution Chart

0' - 185'

■ > 100% 
 ■ 90%-100% 
 ■ 75%-90% 
 ■ 50%-75% 
 ■ < 50% Overstress



 <b>Ramaker &amp; Associates</b> 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job: Transfer Station (CT33XC522)</b>		
	Project: <b>28737</b>		
	Client: Transcend Wireless / Sprint	Drawn by: A. Kraus	App'd:
	Code: TIA/EIA-222-F	Date: 10/10/14	Scale: NTS
	Path: I:\28700\28737\Structural\Inx\28737 rev1.eri		Dwg No. E-8

**APPENDIX B**  
**TOWER CALCULATIONS**


<p><b>tnxTower</b></p> <p><b>Ramaker &amp; Associates</b>  1120 Dallas St.  Sauk City, WI 53583  Phone: (608) 643-4100  FAX: (608) 643-7999</p>	<b>Job</b> Transfer Station (CT33XC522)	<b>Page</b> 1 of 26
	<b>Project</b> 28737	<b>Date</b> 07:13:39 10/10/14
	<b>Client</b> Transcend Wireless / Sprint	<b>Designed by</b> A. Kraus

**Tower Input Data**

The main tower is a 3x free standing tower with an overall height of 185.00 ft above the ground line.  
The base of the tower is set at an elevation of 0.00 ft above the ground line.  
The face width of the tower is 5.00 ft at the top and 21.00 ft at the base.  
This tower is designed using the TIA/EIA-222-F standard.

The following design criteria apply:

- Tower is located in Fairfield County, Connecticut.
- Basic wind speed of 85 mph.
- Nominal ice thickness of 0.5000 in.
- Ice density of 56 pcf.
- A wind speed of 74 mph is used in combination with ice.
- Temperature drop of 50 °F.
- Deflections calculated using a wind speed of 60 mph.
- A non-linear (P-delta) analysis was used.
- Pressures are calculated at each section.
- Stress ratio used in tower member design is 1.333.
- Local bending stresses due to climbing loads, feed line supports, and appurtenance mounts are not considered.



**Triangular Tower**

**Tower Section Geometry**

<b>tnxTower</b>  <b>Ramaker &amp; Associates</b> 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b>	Transfer Station (CT33XC522)	<b>Page</b>	2 of 26
	<b>Project</b>	28737	<b>Date</b>	07:13:39 10/10/14
	<b>Client</b>	Transcend Wireless / Sprint	<b>Designed by</b>	A. Kraus

Tower Section	Tower Elevation	Assembly Database	Description	Section Width	Number of Sections	Section Length
	<i>ft</i>			<i>ft</i>		<i>ft</i>
T1	185.00-180.00			5.00	1	5.00
T2	180.00-160.00			5.00	1	20.00
T3	160.00-140.00			5.00	1	20.00
T4	140.00-120.00			7.00	1	20.00
T5	120.00-100.00			9.00	1	20.00
T6	100.00-80.00			11.00	1	20.00
T7	80.00-60.00			13.00	1	20.00
T8	60.00-40.00			15.00	1	20.00
T9	40.00-20.00			17.00	1	20.00
T10	20.00-0.00			19.00	1	20.00

### Tower Section Geometry (cont'd)

Tower Section	Tower Elevation	Diagonal Spacing	Bracing Type	Has K Brace End Panels	Has Horizontals	Top Girt Offset	Bottom Girt Offset
	<i>ft</i>	<i>ft</i>				<i>in</i>	<i>in</i>
T1	185.00-180.00	5.00	X Brace	No	Yes	0.0000	0.0000
T2	180.00-160.00	5.00	X Brace	No	Yes	0.0000	0.0000
T3	160.00-140.00	5.00	X Brace	No	Yes	0.0000	0.0000
T4	140.00-120.00	5.00	X Brace	No	Yes	0.0000	0.0000
T5	120.00-100.00	6.67	X Brace	No	Yes	0.0000	0.0000
T6	100.00-80.00	6.67	X Brace	No	Yes	0.0000	0.0000
T7	80.00-60.00	6.67	X Brace	No	Yes	0.0000	0.0000
T8	60.00-40.00	10.00	X Brace	No	Yes	0.0000	0.0000
T9	40.00-20.00	10.00	X Brace	No	Yes	0.0000	0.0000
T10	20.00-0.00	10.00	X Brace	No	Yes	0.0000	0.0000

### Tower Section Geometry (cont'd)

Tower Elevation	Leg Type	Leg Size	Leg Grade	Diagonal Type	Diagonal Size	Diagonal Grade
<i>ft</i>						
T1 185.00-180.00	Pipe	P2x.154	A572-50 (50 ksi)	Equal Angle	L2x2x1/8	A36 (36 ksi)
T2 180.00-160.00	Pipe	P2.5x.203	A572-50 (50 ksi)	Equal Angle	L2x2x1/4	A36 (36 ksi)
T3 160.00-140.00	Pipe	P2.5x.375	A572-50 (50 ksi)	Equal Angle	L2x2x1/4	A36 (36 ksi)
T4 140.00-120.00	Arbitrary Shape	P3.5x0.318 + L3.5x3.5x0.375	A572-50 (50 ksi)	Equal Angle	L2x2x3/16	A36 (36 ksi)
T5 120.00-100.00	Arbitrary Shape	P5x0.258 + L5x5x0.375	A572-50 (50 ksi)	Equal Angle	L2 1/2x2 1/2x3/16	A36 (36 ksi)
T6 100.00-80.00	Arbitrary Shape	P5x0.375 + L5x5x0.375	A572-50 (50 ksi)	Equal Angle	L2 1/2x2 1/2x5/16	A36 (36 ksi)
T7 80.00-60.00	Arbitrary Shape	P5x0.375 + L5x5x0.375	A572-50 (50 ksi)	Equal Angle	L3x3x3/16	A36 (36 ksi)
T8 60.00-40.00	Arbitrary Shape	P5x0.500 + L5x5x0.500	A572-50 (50 ksi)	Equal Angle	L3x3x3/8	A36 (36 ksi)
T9 40.00-20.00	Arbitrary Shape	P8x0.322 + L8x8x0.500	A572-50 (50 ksi)	Equal Angle	L3 1/2x3 1/2x1/4	A36 (36 ksi)
T10 20.00-0.00	Arbitrary Shape	P8x0.322 + L8x8x0.500	A572-50	Equal Angle	L3 1/2x3 1/2x3/8	A36

<b>tnxTower</b>  <b>Ramaker &amp; Associates</b> 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b>	Transfer Station (CT33XC522)	<b>Page</b>	3 of 26
	<b>Project</b>	28737	<b>Date</b>	07:13:39 10/10/14
	<b>Client</b>	Transcend Wireless / Sprint	<b>Designed by</b>	A. Kraus

Tower Elevation ft	Leg Type	Leg Size	Leg Grade	Diagonal Type	Diagonal Size	Diagonal Grade
			(50 ksi)			(36 ksi)

### Tower Section Geometry (cont'd)

Tower Elevation ft	Top Girt Type	Top Girt Size	Top Girt Grade	Bottom Girt Type	Bottom Girt Size	Bottom Girt Grade
T1 185.00-180.00	Equal Angle	L2x2x1/8	A36 (36 ksi)	Equal Angle		A36 (36 ksi)
T2 180.00-160.00	Equal Angle	L2x2x1/8	A36 (36 ksi)	Solid Round		A36 (36 ksi)
T3 160.00-140.00	Equal Angle	L2x2x1/8	A36 (36 ksi)	Solid Round		A36 (36 ksi)

### Tower Section Geometry (cont'd)

Tower Elevation ft	Secondary Horizontal Type	Secondary Horizontal Size	Secondary Horizontal Grade	Inner Bracing Type	Inner Bracing Size	Inner Bracing Grade
T3 160.00-140.00	Equal Angle	L2x2x1/4	A36 (36 ksi)	Solid Round		A572-50 (50 ksi)

### Tower Section Geometry (cont'd)

Tower Elevation ft	Gusset Area (per face) ft <sup>2</sup>	Gusset Thickness in	Gusset Grade	Adjust. Factor A <sub>f</sub>	Adjust. Factor A <sub>r</sub>	Weight Mult.	Double Angle Stitch Bolt Spacing Diagonals in	Double Angle Stitch Bolt Spacing Horizontal in
T1 185.00-180.00	0.00	0.0000	A36 (36 ksi)	1	1	1	36.0000	36.0000
T2 180.00-160.00	0.00	0.0000	A36 (36 ksi)	1	1	1	36.0000	36.0000
T3 160.00-140.00	0.00	0.0000	A36 (36 ksi)	1	1	1	36.0000	36.0000
T4 140.00-120.00	0.00	0.0000	A36 (36 ksi)	1	1	1	36.0000	36.0000
T5 120.00-100.00	0.00	0.0000	A36 (36 ksi)	1	1	1	36.0000	36.0000
T6 100.00-80.00	0.00	0.0000	A36 (36 ksi)	1	1	1	36.0000	36.0000
T7 80.00-60.00	0.00	0.0000	A36 (36 ksi)	1	1	1	36.0000	36.0000
T8 60.00-40.00	0.00	0.0000	A36 (36 ksi)	1	1	1	36.0000	36.0000
T9 40.00-20.00	0.00	0.0000	A36	1	1	1	36.0000	36.0000





<b>tnxTower</b>  <b>Ramaker &amp; Associates</b> 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b>	Transfer Station (CT33XC522)	<b>Page</b>	5 of 26
	<b>Project</b>	28737	<b>Date</b>	07:13:39 10/10/14
	<b>Client</b>	Transcend Wireless / Sprint	<b>Designed by</b>	A. Kraus

Tower Elevation ft	Leg		Diagonal		Top Girt		Bottom Girt		Mid Girt		Long Horizontal		Short Horizontal	
	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U
T5 120.00-100.00	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1
T6 100.00-80.00	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1
T7 80.00-60.00	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1
T8 60.00-40.00	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1
T9 40.00-20.00	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1
T10 20.00-0.00	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1

### Tower Section Geometry (cont'd)

Tower Elevation ft	Leg Connection Type	Leg		Diagonal		Top Girt		Bottom Girt		Mid Girt		Long Horizontal		Short Horizontal	
		Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.
T1 185.00-180.00	Flange	0.7500 A325X	6	0.6250 A325X	1	0.6250 A325X	1	0.0000 A325X	0	0.6250 A325X	0	0.6250 A325N	0	0.6250 A325N	0
T2 180.00-160.00	Flange	0.7500 A325X	6	0.6250 A325X	1	0.6250 A325X	1	0.6250 A325X	0	0.6250 A325X	0	0.6250 A325N	0	0.6250 A325N	0
T3 160.00-140.00	Flange	1.0000 A325X	6	0.6250 A325X	1	0.6250 A325X	1	0.6250 A325X	0	0.6250 A325X	0	0.6250 A325N	0	0.6250 A325X	1
T4 140.00-120.00	Flange	1.0000 A325X	6	0.6250 A325N	1	1.0000 A325X	0	0.6250 A325X	0	0.6250 A325X	0	0.6250 A325N	0	0.7500 A325N	0
T5 120.00-100.00	Flange	1.0000 A325X	6	0.6250 A325X	1	1.0000 A325X	0	0.6250 A325X	0	0.6250 A325X	0	0.7500 A325N	0	0.6250 A325N	0
T6 100.00-80.00	Flange	1.0000 A325X	6	0.6250 A325X	1	1.0000 A325X	0	0.6250 A325X	0	0.6250 A325X	0	0.6250 A325N	0	0.6250 A325N	0
T7 80.00-60.00	Flange	1.0000 A325X	6	0.7500 A325X	1	1.0000 A325X	0	0.6250 A325X	0	0.6250 A325X	0	0.7500 A325N	0	0.7500 A325N	0
T8 60.00-40.00	Flange	1.2500 A325X	6	0.7500 A325X	1	1.0000 A325X	0	0.6250 A325X	0	0.6250 A325X	0	0.7500 A325N	0	0.7500 A325N	0
T9 40.00-20.00	Flange	1.2500 A325X	6	0.7500 A325X	1	1.0000 A325X	0	0.6250 A325X	0	0.6250 A325X	0	0.7500 A325N	0	0.7500 A325N	0
T10 20.00-0.00	Flange	1.5000 A572-50	6	0.7500 A325X	1	1.0000 A325X	0	0.6250 A325X	0	0.6250 A325X	0	0.7500 A325N	0	0.7500 A325N	0

### Feed Line/Linear Appurtenances - Entered As Round Or Flat

Description	Face or Leg	Allow Shield	Component Type	Placement ft	Face Offset in	Lateral Offset (Frac FW)	#	# Per Row	Clear Spacing in	Width or Diameter in	Perimeter in	Weight plf
Climbing Ladder (Af) (Tower)	A	Yes	Af (CfAe)	185.00 - 0.00	0.0000	0.1	1	1	1.8000	1.8000	7.2000	7.90
Safety Line 1/2 (Tower)	A	Yes	Ar (CfAe)	185.00 - 0.00	3.0000	0.1	1	1	0.5000	0.5000		0.35
Step Bolts (Tower)	A	No	Ar (Leg)	60.00 - 0.00	0.0000	-0.01	1	1	0.2920	0.2920		0.49
Step Bolts	B	No	Ar (Leg)	60.00 - 0.00	0.0000	-0.01	1	1	0.2920	0.2920		0.49

<p><b>tnxTower</b></p> <p><b>Ramaker &amp; Associates</b> 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999</p>	<b>Job</b>	Transfer Station (CT33XC522)	<b>Page</b>	6 of 26
	<b>Project</b>	28737	<b>Date</b>	07:13:39 10/10/14
	<b>Client</b>	Transcend Wireless / Sprint	<b>Designed by</b>	A. Kraus

Description	Face or Leg	Allow Shield	Component Type	Placement ft	Face Offset in	Lateral Offset (Frac FW)	#	# Per Row	Clear Spacing in	Width or Diameter in	Perimeter in	Weight plf
(Tower) Step Bolts	C	No	Ar (Leg)	60.00 - 0.00	0.0000	-0.01	1	1	0.2920	0.2920		0.49
(Tower) *****												
Feedline Ladder (Af) (Tower - 180')	C	Yes	Af (CfAe)	180.00 - 0.00	-1.0000	-0.1	1	1	3.0000	3.0000	12.0000	8.40
(Tower - 180') *****												
Feedline Ladder (Af) (Municipal - 185')	B	Yes	Af (CfAe)	185.00 - 0.00	-1.0000	0.1	1	1	3.0000	3.0000	12.0000	8.40
(Municipal - 185') 7/8	B	Yes	Ar (CfAe)	185.00 - 0.00	-2.0000	0.08	3	3	0.7500	1.1100		0.54
(Municipal - 185') 7/8	B	Yes	Ar (CfAe)	146.00 - 0.00	-2.0000	0.11	4	4	1.0000	1.1100		0.54
(Municipal - 146') 1/2	B	Yes	Ar (CfAe)	138.00 - 0.00	-2.0000	0.13	1	1	1.1100 0.5800	0.5800		0.25
(Municipal - 138') *****												
Feedline Ladder (Af) (T-Mobile - 185')	B	Yes	Af (CfAe)	185.00 - 0.00	0.0000	0.1	1	1	3.0000	3.0000	12.0000	8.40
(T-Mobile - 185') 1 5/8	B	Yes	Ar (CfAe)	185.00 - 0.00	0.0000	0.125	6	3	0.7500	1.9800		1.04
(T-Mobile - 185') 1 5/8	B	Yes	Ar (CfAe)	185.00 - 0.00	0.0000	0.075	6	3	0.7500	1.9800		1.04
(T-Mobile - 185') 1 1/4	B	Yes	Ar (CfAe)	185.00 - 0.00	0.0000	0.1	1	1	1.5500	1.5500		0.66
(T-Mobile - 185') *****												
Feedline Ladder (Af) (Sprint - 180')	C	Yes	Af (CfAe)	180.00 - 0.00	0.0000	-0.1	1	1	3.0000	3.0000	12.0000	8.40
(Sprint - 180') 1 1/4	C	Yes	Ar (CfAe)	174.00 - 0.00	0.0000	-0.08	3	3	1.0000	1.5500		0.66
(Sprint - 174') 1 1/4	C	Yes	Ar (CfAe)	174.00 - 0.00	0.0000	-0.12	1	1	1.5500	1.5500		0.66
(Sprint - 174') *****												
Feedline Ladder (Af) (Verizon - 164')	A	Yes	Af (CfAe)	164.00 - 0.00	-1.0000	-0.1	1	1	3.0000	3.0000	12.0000	8.40
(Verizon - 164') 1 5/8	A	Yes	Ar (CfAe)	164.00 - 0.00	-4.0000	-0.08	18	9	0.7500	1.9800		1.04
(Verizon - 164') 1 5/8	A	Yes	Ar (CfAe)	164.00 - 0.00	-2.0000	-0.14	1	1	0.7500	1.9800		1.04
(Verizon - 164') *****												
Feedline Ladder (Af) (AT&T - 154')	A	Yes	Af (CfAe)	154.00 - 0.00	0.0000	-0.1	1	1	3.0000	3.0000	12.0000	8.40
(AT&T - 154') 1 5/8	A	Yes	Ar (CfAe)	154.00 - 0.00	0.0000	-0.07	12	6	0.7500	1.9800		1.04
(AT&T - 154') PWRT-608-S Power Cable	A	Yes	Ar (CfAe)	154.00 - 0.00	0.0000	-0.12	2	2	0.8200	0.8200		0.62
(AT&T - 154') RFFT-36SM-001-175M Fiber Cable	A	Yes	Ar (CfAe)	154.00 - 0.00	0.0000	-0.14	1	1	0.4000	0.4000		0.09
(AT&T - 154')												

### Feed Line/Linear Appurtenances Section Areas

Tower Section	Tower Elevation ft	Face	A <sub>R</sub> ft <sup>2</sup>	A <sub>F</sub> ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> In Face ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> Out Face ft <sup>2</sup>	Weight lb
T1	185.00-180.00	A	0.208	0.750	0.000	0.000	41.25
		B	6.983	2.500	0.000	0.000	157.80

<b>tnxTower</b>  <b>Ramaker &amp; Associates</b> 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b>	Transfer Station (CT33XC522)	<b>Page</b>	7 of 26
	<b>Project</b>	28737	<b>Date</b>	07:13:39 10/10/14
	<b>Client</b>	Transcend Wireless / Sprint	<b>Designed by</b>	A. Kraus

Tower Section	Tower Elevation ft	Face	$A_R$ ft <sup>2</sup>	$A_F$ ft <sup>2</sup>	$C_A A_A$ In Face ft <sup>2</sup>	$C_A A_A$ Out Face ft <sup>2</sup>	Weight lb
T2	180.00-160.00	C	0.000	0.000	0.000	0.000	0.00
		A	7.433	4.000	0.000	0.000	277.64
		B	27.933	10.000	0.000	0.000	631.20
T3	160.00-140.00	C	7.233	10.000	0.000	0.000	372.96
		A	50.073	11.500	0.000	0.000	1039.15
		B	30.153	10.000	0.000	0.000	644.16
T4	140.00-120.00	C	10.333	10.000	0.000	0.000	388.80
		A	57.033	13.000	0.000	0.000	1172.42
		B	36.203	10.000	0.000	0.000	678.90
T5	120.00-100.00	C	10.333	10.000	0.000	0.000	388.80
		A	57.033	13.000	0.000	0.000	1172.42
		B	36.300	10.000	0.000	0.000	679.40
T6	100.00-80.00	C	10.333	10.000	0.000	0.000	388.80
		A	57.033	13.000	0.000	0.000	1172.42
		B	36.300	10.000	0.000	0.000	679.40
T7	80.00-60.00	C	10.333	10.000	0.000	0.000	388.80
		A	57.033	13.000	0.000	0.000	1172.42
		B	36.300	10.000	0.000	0.000	679.40
T8	60.00-40.00	C	10.333	10.000	0.000	0.000	388.80
		A	58.007	13.000	0.000	0.000	1182.16
		B	37.273	10.000	0.000	0.000	689.14
T9	40.00-20.00	C	11.307	10.000	0.000	0.000	398.54
		A	58.007	13.000	0.000	0.000	1182.16
		B	37.273	10.000	0.000	0.000	689.14
T10	20.00-0.00	C	11.307	10.000	0.000	0.000	398.54
		A	58.007	13.000	0.000	0.000	1182.16
		B	37.273	10.000	0.000	0.000	689.14
		C	11.307	10.000	0.000	0.000	398.54

### Feed Line/Linear Appurtenances Section Areas - With Ice

Tower Section	Tower Elevation ft	Face or Leg	Ice Thickness in	$A_R$ ft <sup>2</sup>	$A_F$ ft <sup>2</sup>	$C_A A_A$ In Face ft <sup>2</sup>	$C_A A_A$ Out Face ft <sup>2</sup>	Weight lb
T1	185.00-180.00	A	0.500	0.625	1.028	0.000	0.000	53.14
		B		4.425	9.156	0.000	0.000	315.65
		C		0.000	0.000	0.000	0.000	0.00
T2	180.00-160.00	A	0.500	4.487	12.613	0.000	0.000	473.36
		B		17.700	36.622	0.000	0.000	1262.60
		C		5.950	18.172	0.000	0.000	566.34
T3	160.00-140.00	A	0.500	19.667	68.738	0.000	0.000	2203.08
		B		18.755	39.787	0.000	0.000	1305.85
		C		8.500	20.722	0.000	0.000	618.74
T4	140.00-120.00	A	0.500	22.767	78.217	0.000	0.000	2497.33
		B		23.587	47.172	0.000	0.000	1423.15
		C		8.500	20.722	0.000	0.000	618.74
T5	120.00-100.00	A	0.500	22.767	78.217	0.000	0.000	2497.33
		B		23.850	47.172	0.000	0.000	1424.97
		C		8.500	20.722	0.000	0.000	618.74
T6	100.00-80.00	A	0.500	22.767	78.217	0.000	0.000	2497.33
		B		23.850	47.172	0.000	0.000	1424.97
		C		8.500	20.722	0.000	0.000	618.74
T7	80.00-60.00	A	0.500	22.767	78.217	0.000	0.000	2497.33
		B		23.850	47.172	0.000	0.000	1424.97
		C		8.500	20.722	0.000	0.000	618.74
T8	60.00-40.00	A	0.500	27.073	78.217	0.000	0.000	2516.74
		B		28.157	47.172	0.000	0.000	1444.38
		C		12.807	20.722	0.000	0.000	638.16

<b>tnxTower</b>  <b>Ramaker &amp; Associates</b> 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b>	Transfer Station (CT33XC522)	<b>Page</b>	8 of 26
	<b>Project</b>	28737	<b>Date</b>	07:13:39 10/10/14
	<b>Client</b>	Transcend Wireless / Sprint	<b>Designed by</b>	A. Kraus

Tower Section	Tower Elevation ft	Face or Leg	Ice Thickness in	$A_R$ ft <sup>2</sup>	$A_F$ ft <sup>2</sup>	$C_{AA}$ In Face ft <sup>2</sup>	$C_{AA}$ Out Face ft <sup>2</sup>	Weight lb
T9	40.00-20.00	A	0.500	27.073	78.217	0.000	0.000	2516.74
		B		28.157	47.172	0.000	0.000	1444.38
		C		12.807	20.722	0.000	0.000	638.16
T10	20.00-0.00	A	0.500	27.073	78.217	0.000	0.000	2516.74
		B		28.157	47.172	0.000	0.000	1444.38
		C		12.807	20.722	0.000	0.000	638.16

### Feed Line Shielding

Section	Elevation ft	Face	$A_R$ ft <sup>2</sup>	$A_R$ Ice ft <sup>2</sup>	$A_F$ ft <sup>2</sup>	$A_F$ Ice ft <sup>2</sup>
T1	185.00-180.00	A	0.000	0.114	0.122	0.229
		B	0.000	0.884	1.210	1.769
		C	0.000	0.000	0.000	0.000
T2	180.00-160.00	A	0.000	0.912	1.173	1.823
		B	0.000	2.844	3.893	5.688
		C	0.000	1.295	1.768	2.589
T3	160.00-140.00	A	0.000	5.792	7.933	11.584
		B	0.000	3.843	5.173	7.686
		C	0.000	1.954	2.620	3.908
T4	140.00-120.00	A	0.000	4.042	5.516	8.085
		B	0.000	2.830	3.639	5.661
		C	0.000	1.195	1.601	2.389
T5	120.00-100.00	A	0.000	3.088	5.267	7.720
		B	0.000	2.170	3.482	5.425
		C	0.000	0.912	1.529	2.281
T6	100.00-80.00	A	0.000	2.938	5.010	7.344
		B	0.000	2.064	3.312	5.161
		C	0.000	0.868	1.455	2.170
T7	80.00-60.00	A	0.000	2.843	5.820	8.530
		B	0.000	1.998	3.848	5.994
		C	0.000	0.840	1.690	2.521
T8	60.00-40.00	A	0.000	2.018	4.131	6.054
		B	0.000	1.418	2.731	4.255
		C	0.000	0.596	1.199	1.789
T9	40.00-20.00	A	0.000	1.958	4.674	6.851
		B	0.000	1.376	3.090	4.815
		C	0.000	0.578	1.357	2.025
T10	20.00-0.00	A	0.000	1.913	4.568	6.696
		B	0.000	1.344	3.020	4.705
		C	0.000	0.565	1.326	1.979

### Feed Line Center of Pressure

Section	Elevation ft	$CP_x$ in	$CP_z$ in	$CP_x$ Ice in	$CP_z$ Ice in
T1	185.00-180.00	5.8872	-1.8690	3.5231	-1.4155
T2	180.00-160.00	4.8864	0.5577	3.1001	0.4518
T3	160.00-140.00	-0.9235	-0.3740	-1.3859	-0.2798
T4	140.00-120.00	-1.4980	-0.8259	-1.7903	-0.6955

<b>tnxTower</b>  <b>Ramaker &amp; Associates</b> 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b>	Transfer Station (CT33XC522)	<b>Page</b>	9 of 26
	<b>Project</b>	28737	<b>Date</b>	07:13:39 10/10/14
	<b>Client</b>	Transcend Wireless / Sprint	<b>Designed by</b>	A. Kraus

Section	Elevation	CP <sub>X</sub>	CP <sub>Z</sub>	CP <sub>X</sub> Ice	CP <sub>Z</sub> Ice
	ft	in	in	in	in
T5	120.00-100.00	-1.7293	-0.9570	-2.0884	-0.8463
T6	100.00-80.00	-2.0757	-1.1460	-2.4755	-1.0196
T7	80.00-60.00	-2.2829	-1.2583	-2.7402	-1.1313
T8	60.00-40.00	-2.7569	-1.5177	-3.1919	-1.3523
T9	40.00-20.00	-2.5886	-1.4238	-3.1212	-1.3234
T10	20.00-0.00	-2.8474	-1.5649	-3.4222	-1.4582

### Discrete Tower Loads

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment °	Placement ft	C <sub>A</sub> A <sub>A</sub> Front ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> Side ft <sup>2</sup>	Weight lb
8' Dipole (Municipal)	A	From Leg	0.00 0.00 4.00	0.0000	185.00	No Ice 1/2" Ice 6.40	4.80 6.40	45.00 89.00
15' Omni (Municipal)	B	From Leg	0.00 0.00 7.50	0.0000	185.00	No Ice 1/2" Ice 5.28	3.75 5.28	40.00 67.80
8' Dipole (Municipal)	C	From Leg	0.00 0.00 4.00	0.0000	185.00	No Ice 1/2" Ice 6.40	4.80 6.40	45.00 89.00
*****								
Andrew 12'-6" Universal Sector Frame (T-Mobile)	A	From Leg	3.00 0.00 0.00	0.0000	185.00	No Ice 1/2" Ice 15.10	10.80 15.10	525.00 675.00
Andrew 12'-6" Universal Sector Frame (T-Mobile)	B	From Leg	3.00 0.00 0.00	0.0000	185.00	No Ice 1/2" Ice 15.10	10.80 15.10	525.00 675.00
Andrew 12'-6" Universal Sector Frame (T-Mobile)	C	From Leg	3.00 0.00 0.00	0.0000	185.00	No Ice 1/2" Ice 15.10	10.80 15.10	525.00 675.00
(2) AIR 21 B2A B4P w/Mount Pipe (T-Mobile)	A	From Leg	3.00 0.00 0.00	0.0000	185.00	No Ice 1/2" Ice 7.15	6.69 6.35	120.25 177.83
(2) AIR 21 B2A B4P w/Mount Pipe (T-Mobile)	B	From Leg	3.00 0.00 0.00	0.0000	185.00	No Ice 1/2" Ice 7.15	6.69 6.35	120.25 177.83
(2) AIR 21 B2A B2P w/Mount Pipe (T-Mobile)	C	From Leg	3.00 0.00 0.00	0.0000	185.00	No Ice 1/2" Ice 7.15	6.69 6.35	119.15 176.73
(2) KRY 112 71 (T-Mobile)	A	From Leg	2.00 0.00 0.00	0.0000	185.00	No Ice 1/2" Ice 0.80	0.68 0.56	13.20 18.38
(2) KRY 112 71 (T-Mobile)	B	From Leg	2.00 0.00 0.00	0.0000	185.00	No Ice 1/2" Ice 0.80	0.68 0.56	13.20 18.38
(2) KRY 112 71 (T-Mobile)	C	From Leg	2.00 0.00 0.00	0.0000	185.00	No Ice 1/2" Ice 0.80	0.68 0.56	13.20 18.38
*****								
Andrew 12'-6" Universal Sector Frame	A	From Leg	3.00 0.00	0.0000	174.00	No Ice 1/2" Ice 15.10	10.80 15.10	525.00 675.00

<b>Job</b>	Transfer Station (CT33XC522)	<b>Page</b>	10 of 26
<b>Project</b>	28737	<b>Date</b>	07:13:39 10/10/14
<b>Client</b>	Transcend Wireless / Sprint	<b>Designed by</b>	A. Kraus

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C <sub>AA</sub> Front	C <sub>AA</sub> Side	Weight
			Horz	Vert					
			ft	ft	°	ft	ft <sup>2</sup>	ft <sup>2</sup>	lb
(Sprint)			0.00						
Andrew 12'-6" Universal Sector Frame	B	From Leg	3.00		0.0000	174.00	No Ice 1/2" Ice	10.80 15.10	525.00 675.00
(Sprint)			0.00						
Andrew 12'-6" Universal Sector Frame	C	From Leg	3.00		0.0000	174.00	No Ice 1/2" Ice	10.80 15.10	525.00 675.00
(Sprint)			0.00						
APXVSPP18-C w/Mount Pipe	A	From Leg	3.00		0.0000	174.00	No Ice 1/2" Ice	8.26 8.81	78.90 144.31
(Sprint)			2.00						
APXVSPP18-C w/Mount Pipe	B	From Leg	3.00		0.0000	174.00	No Ice 1/2" Ice	8.26 8.81	78.90 144.31
(Sprint)			2.00						
APXVSPP18-C w/Mount Pipe	C	From Leg	3.00		0.0000	174.00	No Ice 1/2" Ice	8.26 8.81	78.90 144.31
(Sprint)			2.00						
1900MHz 4x40W RRH	A	From Leg	2.00		0.0000	174.00	No Ice 1/2" Ice	2.71 2.95	60.00 83.12
(Sprint)			-2.00						
1900MHz 4x40W RRH	B	From Leg	2.00		0.0000	174.00	No Ice 1/2" Ice	2.71 2.95	60.00 83.12
(Sprint)			-2.00						
1900MHz 4x40W RRH	C	From Leg	2.00		0.0000	174.00	No Ice 1/2" Ice	2.71 2.95	60.00 83.12
(Sprint)			-2.00						
800MHz 2x50W RRH	A	From Leg	2.50		0.0000	174.00	No Ice 1/2" Ice	2.40 2.61	64.00 86.12
(Sprint)			-2.00						
800MHz 2x50W RRH	B	From Leg	2.50		0.0000	174.00	No Ice 1/2" Ice	2.40 2.61	64.00 86.12
(Sprint)			-2.00						
800MHz 2x50W RRH	C	From Leg	2.50		0.0000	174.00	No Ice 1/2" Ice	2.40 2.61	64.00 86.12
(Sprint)			-2.00						
APXV9TM14-C-I20 w/Mount Pipe	A	From Leg	3.00		0.0000	174.00	No Ice 1/2" Ice	6.99 7.46	93.02 151.55
(Sprint)			-6.00						
APXV9TM14-C-I20 w/Mount Pipe	B	From Leg	3.00		0.0000	174.00	No Ice 1/2" Ice	6.99 7.46	93.02 151.55
(Sprint)			-6.00						
APXV9TM14-C-I20 w/Mount Pipe	C	From Leg	3.00		0.0000	174.00	No Ice 1/2" Ice	6.99 7.46	93.02 151.55
(Sprint)			-6.00						
TD-RRH8x20-25	A	From Leg	2.00		0.0000	174.00	No Ice 1/2" Ice	4.72 5.01	70.00 97.14
(Sprint)			-6.00						
TD-RRH8x20-25	B	From Leg	2.00		0.0000	174.00	No Ice 1/2" Ice	4.72 5.01	70.00 97.14
(Sprint)			-6.00						
TD-RRH8x20-25	C	From Leg	2.00		0.0000	174.00	No Ice 1/2" Ice	4.72 5.01	70.00 97.14
(Sprint)			-6.00						
*****			1.00						
Andrew 12'-6" Quik-Tee Sector Frame	A	From Leg	4.00		0.0000	164.00	No Ice 1/2" Ice	16.30 20.60	509.80 644.29
(Verizon)			-1.00						
Andrew 12'-6" Quik-Tee Sector	B	From Leg	4.00		0.0000	164.00	No Ice	16.30	509.80

<b>Job</b>	Transfer Station (CT33XC522)	<b>Page</b>	11 of 26
<b>Project</b>	28737	<b>Date</b>	07:13:39 10/10/14
<b>Client</b>	Transcend Wireless / Sprint	<b>Designed by</b>	A. Kraus

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment °	Placement ft	C <sub>AA</sub> Front ft <sup>2</sup>	C <sub>AA</sub> Side ft <sup>2</sup>	Weight lb
Frame (Verizon)			0.00 -1.00			1/2" Ice 20.60	20.60	644.29
Andrew 12'-6" Quik-Tee Sector Frame (Verizon)	C	From Leg	4.00 0.00 -1.00	0.0000	164.00	No Ice 1/2" Ice 20.60	16.30 20.60	509.80 644.29
BXA-70063-6CF-EDIN-X w/Mount Pipe (Verizon)	A	From Leg	4.00 0.00 0.00	0.0000	164.00	No Ice 1/2" Ice 8.64	7.99 6.99	42.55 103.53
BXA-70063-6CF-EDIN-X w/Mount Pipe (Verizon)	B	From Leg	4.00 0.00 0.00	0.0000	164.00	No Ice 1/2" Ice 8.64	7.99 6.99	42.55 103.53
BXA-70063-6CF-EDIN-X w/Mount Pipe (Verizon)	C	From Leg	4.00 0.00 0.00	0.0000	164.00	No Ice 1/2" Ice 8.64	7.99 6.99	42.55 103.53
DB846F65ZAXY w/Mount Pipe (Verizon)	A	From Leg	4.00 -4.50 0.00	0.0000	164.00	No Ice 1/2" Ice 7.88	7.82 9.01	46.55 113.93
DB846F65ZAXY w/Mount Pipe (Verizon)	A	From Leg	4.00 4.50 0.00	0.0000	164.00	No Ice 1/2" Ice 7.88	7.82 9.01	46.55 113.93
DB846H80E-SX w/Mount Pipe (Verizon)	B	From Leg	4.00 -4.50 0.00	0.0000	164.00	No Ice 1/2" Ice 5.87	7.73 8.92	40.55 98.56
DB846H80E-SX w/Mount Pipe (Verizon)	B	From Leg	4.00 4.50 0.00	0.0000	164.00	No Ice 1/2" Ice 5.87	7.73 8.92	40.55 98.56
DB846F65ZAXY w/Mount Pipe (Verizon)	C	From Leg	4.00 -4.50 0.00	0.0000	164.00	No Ice 1/2" Ice 7.88	7.82 9.01	46.55 113.93
DB846F65ZAXY w/Mount Pipe (Verizon)	C	From Leg	4.00 4.50 0.00	0.0000	164.00	No Ice 1/2" Ice 7.88	7.82 9.01	46.55 113.93
742 213 w/Mount Pipe (Verizon)	A	From Leg	4.00 -6.00 0.00	0.0000	164.00	No Ice 1/2" Ice 5.68	4.53 5.73	48.03 90.76
742 213 w/Mount Pipe (Verizon)	A	From Leg	4.00 6.00 0.00	0.0000	164.00	No Ice 1/2" Ice 5.68	4.53 5.73	48.03 90.76
742 213 w/Mount Pipe (Verizon)	B	From Leg	4.00 -6.00 0.00	0.0000	164.00	No Ice 1/2" Ice 5.68	4.53 5.73	48.03 90.76
742 213 w/Mount Pipe (Verizon)	B	From Leg	4.00 6.00 0.00	0.0000	164.00	No Ice 1/2" Ice 5.68	4.53 5.73	48.03 90.76
742 213 w/Mount Pipe (Verizon)	C	From Leg	4.00 -6.00 0.00	0.0000	164.00	No Ice 1/2" Ice 5.68	4.53 5.73	48.03 90.76
742 213 w/Mount Pipe (Verizon)	C	From Leg	4.00 6.00 0.00	0.0000	164.00	No Ice 1/2" Ice 5.68	4.53 5.73	48.03 90.76
RRH 2x40 AWS (Verizon)	A	From Leg	3.00 -6.00 0.00	0.0000	164.00	No Ice 1/2" Ice 2.75	1.59 1.80	44.00 61.40
RRH 2x40 AWS (Verizon)	B	From Leg	3.00 -6.00 0.00	0.0000	164.00	No Ice 1/2" Ice 2.75	1.59 1.80	44.00 61.40
RRH 2x40 AWS	C	From Leg	3.00	0.0000	164.00	No Ice	2.52 1.59	44.00

<b>tnxTower</b>  <b>Ramaker &amp; Associates</b> 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b>	Transfer Station (CT33XC522)	<b>Page</b>	12 of 26
	<b>Project</b>	28737	<b>Date</b>	07:13:39 10/10/14
	<b>Client</b>	Transcend Wireless / Sprint	<b>Designed by</b>	A. Kraus

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment °	Placement ft	C <sub>AA</sub> Front ft <sup>2</sup>	C <sub>AA</sub> Side ft <sup>2</sup>	Weight lb
(Verizon)			-6.00 0.00			1/2" Ice 2.75	1.80	61.40
DB-T1-6Z-8AB-0Z	C	From Leg	1.50	0.0000	164.00	No Ice 5.60	2.33	44.00
(Verizon)			0.00 0.00			1/2" Ice 5.92	2.56	80.13
*****								
Andrew 12'-6" Quik-Tee Sector Frame (AT&T)	A	From Leg	3.00 0.00 -1.00	0.0000	154.00	No Ice 1/2" Ice 16.30 20.60	16.30 20.60	509.80 644.29
Andrew 12'-6" Quik-Tee Sector Frame (AT&T)	B	From Leg	3.00 0.00 -1.00	0.0000	154.00	No Ice 1/2" Ice 16.30 20.60	16.30 20.60	509.80 644.29
Andrew 12'-6" Quik-Tee Sector Frame (AT&T)	C	From Leg	3.00 0.00 -1.00	0.0000	154.00	No Ice 1/2" Ice 16.30 20.60	16.30 20.60	509.80 644.29
RA21.7770.00 (AT&T)	A	From Leg	3.00 -6.00 0.00	0.0000	154.00	No Ice 1/2" Ice 6.79 7.28	3.51 3.90	37.20 74.53
RA21.7770.00 (AT&T)	A	From Leg	3.00 -2.00 0.00	0.0000	154.00	No Ice 1/2" Ice 6.79 7.28	3.51 3.90	37.20 74.53
RA21.7770.00 (AT&T)	B	From Leg	3.00 -6.00 0.00	0.0000	154.00	No Ice 1/2" Ice 6.79 7.28	3.51 3.90	37.20 74.53
RA21.7770.00 (AT&T)	B	From Leg	3.00 -2.00 0.00	0.0000	154.00	No Ice 1/2" Ice 6.79 7.28	3.51 3.90	37.20 74.53
RA21.7770.00 (AT&T)	C	From Leg	3.00 -6.00 0.00	0.0000	154.00	No Ice 1/2" Ice 6.79 7.28	3.51 3.90	37.20 74.53
RA21.7770.00 (AT&T)	C	From Leg	3.00 -2.00 0.00	0.0000	154.00	No Ice 1/2" Ice 6.79 7.28	3.51 3.90	37.20 74.53
P65-16-XLH-RR w/Mount Pipe (AT&T)	A	From Leg	3.00 6.00 0.00	0.0000	154.00	No Ice 1/2" Ice 8.40 8.95	6.13 7.07	85.90 149.07
P65-16-XLH-RR w/Mount Pipe (AT&T)	B	From Leg	3.00 6.00 0.00	0.0000	154.00	No Ice 1/2" Ice 8.40 8.95	6.13 7.07	85.90 149.07
P65-16-XLH-RR w/Mount Pipe (AT&T)	C	From Leg	3.00 6.00 0.00	0.0000	154.00	No Ice 1/2" Ice 8.40 8.95	6.13 7.07	85.90 149.07
(2) LGP214nn (AT&T)	A	From Leg	3.00 -6.00 0.00	0.0000	154.00	No Ice 1/2" Ice 1.30 1.45	0.23 0.31	14.10 21.30
(2) LGP214nn (AT&T)	B	From Leg	3.00 -6.00 0.00	0.0000	154.00	No Ice 1/2" Ice 1.30 1.45	0.23 0.31	14.10 21.30
(2) LGP214nn (AT&T)	C	From Leg	3.00 -6.00 0.00	0.0000	154.00	No Ice 1/2" Ice 1.30 1.45	0.23 0.31	14.10 21.30
TT19-08BP111-001 (AT&T)	A	From Leg	3.00 -2.00 0.00	0.0000	154.00	No Ice 1/2" Ice 0.64 0.76	0.52 0.62	16.00 21.80
TT19-08BP111-001 (AT&T)	B	From Leg	3.00 -2.00 0.00	0.0000	154.00	No Ice 1/2" Ice 0.64 0.76	0.52 0.62	16.00 21.80



<b>tnxTower</b>  <b>Ramaker &amp; Associates</b> 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b>	Transfer Station (CT33XC522)	<b>Page</b>	13 of 26
	<b>Project</b>	28737	<b>Date</b>	07:13:39 10/10/14
	<b>Client</b>	Transcend Wireless / Sprint	<b>Designed by</b>	A. Kraus

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment °	Placement ft	Ice	C <sub>AA</sub> Front ft <sup>2</sup>	C <sub>AA</sub> Side ft <sup>2</sup>	Weight lb
TT19-08BP111-001 (AT&T)	C	From Leg	3.00 -2.00 0.00	0.0000	154.00	No Ice 1/2" Ice	0.64 0.76	0.52 0.62	16.00 21.80
RRUS-11 (AT&T)	A	From Leg	1.00 0.00 3.00	0.0000	154.00	No Ice 1/2" Ice	2.94 3.17	1.25 1.41	55.00 74.32
RRUS-11 (AT&T)	B	From Leg	1.00 0.00 3.00	0.0000	154.00	No Ice 1/2" Ice	2.94 3.17	1.25 1.41	55.00 74.32
RRUS-11 (AT&T)	C	From Leg	1.00 0.00 3.00	0.0000	154.00	No Ice 1/2" Ice	2.94 3.17	1.25 1.41	55.00 74.32
DC6-48-60-18-8F (AT&T)	C	From Leg	1.00 0.00 0.00	0.0000	154.00	No Ice 1/2" Ice	1.47 1.67	1.47 1.67	33.00 50.72
*****									
6' Standoff (Municipal)	A	From Leg	3.00 0.00 0.00	0.0000	146.00	No Ice 1/2" Ice	4.97 6.12	4.97 6.12	70.00 130.00
6' Standoff (Municipal)	C	From Leg	3.00 0.00 0.00	0.0000	146.00	No Ice 1/2" Ice	4.97 6.12	4.97 6.12	70.00 130.00
15' Omni (Municipal)	A	From Leg	6.00 0.00 8.00	0.0000	146.00	No Ice 1/2" Ice	3.75 5.28	3.75 5.28	40.00 67.80
8' Dipole (Municipal)	A	From Leg	6.00 0.00 -5.00	0.0000	146.00	No Ice 1/2" Ice	4.80 6.40	4.80 6.40	45.00 89.00
8' Dipole (Municipal)	C	From Leg	6.00 0.00 -5.00	0.0000	146.00	No Ice 1/2" Ice	4.80 6.40	4.80 6.40	45.00 89.00
*****									
2' Standoff (Dish)	B	From Leg	1.00 0.00 0.00	0.0000	138.00	No Ice 1/2" Ice	1.80 3.30	1.80 3.30	33.00 59.00

### Dishes

Description	Face or Leg	Dish Type	Offset Type	Offsets: Horz Lateral Vert ft	Azimuth Adjustment °	3 dB Beam Width °	Elevation ft	Outside Diameter ft	Aperture Area ft <sup>2</sup>	Weight lb	
Andrew 3' w/Radome (Sprint)	B	Paraboloid w/Radome	From Leg	2.00 0.00 0.00	0.0000		138.00	3.00	No Ice 1/2" Ice	7.07 7.47	100.00 138.35

### Force Totals

<p><b>tnxTower</b></p> <p><b>Ramaker &amp; Associates</b> 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999</p>	<p><b>Job</b></p> <p>Transfer Station (CT33XC522)</p>	<p><b>Page</b></p> <p>14 of 26</p>
	<p><b>Project</b></p> <p>28737</p>	<p><b>Date</b></p> <p>07:13:39 10/10/14</p>
	<p><b>Client</b></p> <p>Transcend Wireless / Sprint</p>	<p><b>Designed by</b></p> <p>A. Kraus</p>

Load Case	Vertical Forces lb	Sum of Forces X lb	Sum of Forces Z lb	Sum of Overturning Moments, M <sub>x</sub> lb-ft	Sum of Overturning Moments, M <sub>z</sub> lb-ft	Sum of Torques lb-ft
Leg Weight	16537.36					
Bracing Weight	10304.94					
Total Member Self-Weight	26842.30					
Total Weight	56475.46					
Wind 0 deg - No Ice		74.17	-56075.41	-6055805.36	-5177.82	-6990.47
Wind 30 deg - No Ice		26436.79	-45755.78	-5035879.64	-2901752.99	-8227.27
Wind 60 deg - No Ice		44784.98	-25925.37	-2876749.68	-4949312.79	-7454.39
Wind 90 deg - No Ice		52792.78	-93.78	-19304.99	-5795533.24	-4923.59
Wind 120 deg - No Ice		48516.48	27957.55	3008925.16	-5225737.66	-1052.01
Wind 150 deg - No Ice		26315.17	45674.20	5014463.57	-2880519.84	3145.52
Wind 180 deg - No Ice		-105.82	51667.44	5712371.61	24801.44	6436.30
Wind 210 deg - No Ice		-26487.45	45726.53	5024255.06	2924000.01	8227.27
Wind 240 deg - No Ice		-48618.22	28101.94	3033301.61	5257603.27	8042.48
Wind 270 deg - No Ice		-52854.02	93.18	11634.96	5819240.92	4843.76
Wind 300 deg - No Ice		-44781.22	-25801.00	-2855136.35	4961480.28	1018.09
Wind 330 deg - No Ice		-26346.31	-45726.94	-5029330.41	2900072.46	-3065.69
Member Ice	8355.57					
Total Weight Ice	88816.85					
Wind 0 deg - Ice		56.72	-57400.26	-6171554.47	10308.15	-9043.11
Wind 30 deg - Ice		26082.13	-45150.58	-4965650.49	-2842661.29	-9435.80
Wind 60 deg - Ice		43603.29	-25227.62	-2805034.86	-4801894.41	-7882.82
Wind 90 deg - Ice		52103.81	-72.25	-24431.14	-5693663.34	-4661.73
Wind 120 deg - Ice		49674.52	28638.40	3056824.73	-5307773.29	106.98
Wind 150 deg - Ice		25989.33	45087.99	4930075.29	-2826420.77	4648.74
Wind 180 deg - Ice		-81.80	50313.57	5549650.56	33388.84	7837.17
Wind 210 deg - Ice		-26122.28	45127.40	4937496.45	2888437.15	9435.80
Wind 240 deg - Ice		-49753.08	28749.25	3075556.12	5360833.30	8936.13
Wind 270 deg - Ice		-52152.35	71.78	-589.18	5740596.68	4598.47
Wind 300 deg - Ice		-43602.37	-25132.64	-2788493.06	4840020.85	45.66
Wind 330 deg - Ice		-26014.01	-45129.78	-4960798.60	2870061.49	-4585.48
Total Weight	56475.46					
Wind 0 deg - Service		36.96	-27940.69	-3015871.01	-5916.62	-3483.14
Wind 30 deg - Service		13172.65	-22798.73	-2507672.72	-1449192.82	-4099.40
Wind 60 deg - Service		22315.01	-12917.83	-1431843.26	-2469430.23	-3714.30
Wind 90 deg - Service		26305.05	-46.73	-8064.59	-2891076.41	-2453.28
Wind 120 deg - Service		24174.30	13930.41	1500811.33	-2607164.43	-524.19
Wind 150 deg - Service		13112.06	22758.08	2500110.75	-1438612.99	1567.32
Wind 180 deg - Service		-52.73	25744.33	2847857.31	9021.15	3207.01
Wind 210 deg - Service		-13197.90	22784.15	2504989.55	1453604.51	4099.40
Wind 240 deg - Service		-24224.99	14002.35	1512957.38	2616368.77	4007.33
Wind 270 deg - Service		-26335.57	46.43	7351.85	2896215.91	2413.50
Wind 300 deg - Service		-22313.13	-12855.86	-1421073.99	2468819.60	507.28
Wind 330 deg - Service		-13127.57	-22784.36	-2504409.44	1441682.14	-1527.54

### Load Combinations

Comb. No.	Description
1	Dead Only
2	Dead+Wind 0 deg - No Ice
3	Dead+Wind 30 deg - No Ice
4	Dead+Wind 60 deg - No Ice
5	Dead+Wind 90 deg - No Ice
6	Dead+Wind 120 deg - No Ice
7	Dead+Wind 150 deg - No Ice

<b>tnxTower</b>  <b>Ramaker &amp; Associates</b> 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b> Transfer Station (CT33XC522)	<b>Page</b> 15 of 26
	<b>Project</b> 28737	<b>Date</b> 07:13:39 10/10/14
	<b>Client</b> Transcend Wireless / Sprint	<b>Designed by</b> A. Kraus

Comb. No.	Description
8	Dead+Wind 180 deg - No Ice
9	Dead+Wind 210 deg - No Ice
10	Dead+Wind 240 deg - No Ice
11	Dead+Wind 270 deg - No Ice
12	Dead+Wind 300 deg - No Ice
13	Dead+Wind 330 deg - No Ice
14	Dead+Ice+Temp
15	Dead+Wind 0 deg+Ice+Temp
16	Dead+Wind 30 deg+Ice+Temp
17	Dead+Wind 60 deg+Ice+Temp
18	Dead+Wind 90 deg+Ice+Temp
19	Dead+Wind 120 deg+Ice+Temp
20	Dead+Wind 150 deg+Ice+Temp
21	Dead+Wind 180 deg+Ice+Temp
22	Dead+Wind 210 deg+Ice+Temp
23	Dead+Wind 240 deg+Ice+Temp
24	Dead+Wind 270 deg+Ice+Temp
25	Dead+Wind 300 deg+Ice+Temp
26	Dead+Wind 330 deg+Ice+Temp
27	Dead+Wind 0 deg - Service
28	Dead+Wind 30 deg - Service
29	Dead+Wind 60 deg - Service
30	Dead+Wind 90 deg - Service
31	Dead+Wind 120 deg - Service
32	Dead+Wind 150 deg - Service
33	Dead+Wind 180 deg - Service
34	Dead+Wind 210 deg - Service
35	Dead+Wind 240 deg - Service
36	Dead+Wind 270 deg - Service
37	Dead+Wind 300 deg - Service
38	Dead+Wind 330 deg - Service

### Maximum Member Forces

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Force lb	Major Axis Moment lb-ft	Minor Axis Moment lb-ft
T1	185 - 180	Leg	Max Tension	8	1850.33	-0.00	-0.00
			Max. Compression	19	-3263.60	17.52	-2.37
			Max. Mx	6	399.09	39.12	17.12
			Max. My	2	399.64	-15.98	-45.75
			Max. Vy	5	-1021.33	-0.00	-0.00
			Max. Vx	2	1023.23	-0.00	-0.00
		Diagonal	Max Tension	13	1451.28	0.00	0.00
			Max. Compression	7	-1706.42	0.00	0.00
			Max. Mx	15	79.22	8.25	0.55
			Max. My	25	-1365.57	3.17	-0.99
			Max. Vy	15	6.82	8.25	0.55
			Max. Vx	25	-0.31	0.00	0.00
		Top Girt	Max Tension	23	552.68	0.00	0.00
			Max. Compression	8	-371.50	0.00	0.00
			Max. Mx	14	123.80	-11.20	0.00
			Max. My	23	-93.74	0.00	-0.00
Max. Vy	14		8.96	0.00	0.00		
Max. Vx	23		0.00	0.00	0.00		
T2	180 - 160	Leg	Max Tension	4	31260.73	-517.23	294.73
			Max. Compression	19	-37645.24	-290.55	-164.93
			Max. Mx	11	-31087.24	-823.83	29.43
			Max. My	2	-36189.15	-7.63	-831.27

<b>tnxTower</b>  <b>Ramaker &amp; Associates</b> 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b> Transfer Station (CT33XC522)	<b>Page</b> 16 of 26
	<b>Project</b> 28737	<b>Date</b> 07:13:39 10/10/14
	<b>Client</b> Transcend Wireless / Sprint	<b>Designed by</b> A. Kraus

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Force lb	Major Axis Moment lb-ft	Minor Axis Moment lb-ft
T3	160 - 140	Diagonal	Max. Vy	5	-1421.19	-602.74	-13.40
			Max. Vx	2	1431.16	-1.24	621.02
			Max Tension	8	6301.47	0.00	0.00
			Max. Compression	2	-6675.26	0.00	0.00
			Max. Mx	19	4296.35	56.05	-2.90
			Max. My	3	-6294.77	-31.59	-8.75
		Top Girt	Max. Vy	19	-22.37	56.05	-2.90
			Max. Vx	3	-2.48	0.00	0.00
			Max Tension	4	492.38	0.00	0.00
			Max. Compression	2	-404.33	0.00	0.00
			Max. Mx	14	56.03	-11.20	0.00
			Max. My	23	241.79	0.00	-0.00
		Leg	Max. Vy	14	8.96	0.00	0.00
			Max. Vx	23	0.00	0.00	0.00
			Max Tension	4	81105.27	162.36	98.21
			Max. Compression	15	-93458.66	-205.95	-38.52
			Max. Mx	4	56604.44	665.45	-7.91
			Max. My	3	-3545.21	-66.08	-744.90
		Diagonal	Max. Vy	12	-867.10	-202.92	7.40
			Max. Vx	7	-1303.91	-64.02	-743.92
			Max Tension	9	6354.10	0.00	0.00
			Max. Compression	9	-6459.30	0.00	0.00
			Max. Mx	15	4637.62	52.16	2.56
			Max. My	7	-5079.55	-21.65	7.77
		Secondary Horizontal	Max. Vy	15	-21.30	52.16	2.56
			Max. Vx	20	-2.49	0.00	0.00
			Max Tension	15	1620.77	0.00	0.00
			Max. Compression	15	-1620.77	0.00	0.00
			Max. Mx	14	147.05	-29.12	0.00
			Max. My	17	843.54	0.00	0.84
Top Girt	Max. Vy	14	17.28	0.00	0.00		
	Max. Vx	17	-0.50	0.00	0.00		
	Max Tension	4	1005.02	0.00	0.00		
	Max. Compression	10	-1002.32	0.00	0.00		
	Max. Mx	14	40.69	-11.20	0.00		
	Max. My	17	-406.19	0.00	0.32		
Leg	Max. Vy	14	8.96	0.00	0.00		
	Max. Vx	17	-0.26	0.00	0.00		
	Max Tension	4	123828.95	-340.44	1.06		
	Max. Compression	23	-142063.02	646.25	-14.03		
	Max. Mx	10	-139793.19	655.07	-12.96		
	Max. My	11	-6211.59	-10.08	-616.77		
Diagonal	Max. Vy	10	-206.84	546.97	12.08		
	Max. Vx	3	-128.88	-21.37	-389.33		
	Max Tension	9	6023.07	0.00	0.00		
	Max. Compression	9	-6083.53	0.00	0.00		
	Max. Mx	23	4995.72	25.64	-1.26		
	Max. My	17	-5062.53	5.52	4.07		
Leg	Max. Vy	17	14.70	25.02	2.01		
	Max. Vx	17	-1.15	0.00	0.00		
	Max Tension	4	157115.30	-644.24	3.48		
	Max. Compression	23	-182576.35	1160.14	-27.31		
	Max. Mx	23	-182576.35	1160.14	-27.31		
	Max. My	11	-7561.47	2.06	-959.56		
Diagonal	Max. Vy	6	-137.84	1152.81	5.33		
	Max. Vx	5	-100.13	9.19	957.77		
	Max Tension	22	6534.61	0.00	0.00		
	Max. Compression	22	-6678.87	0.00	0.00		
	Max. Mx	23	5483.04	48.15	-2.94		
	Max. My	16	-6537.20	-2.65	5.93		
		Max. Vy	23	-21.90	48.15	-2.94	

<b>tnxTower</b>  <b>Ramaker &amp; Associates</b> 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b>	Transfer Station (CT33XC522)	<b>Page</b>	17 of 26
	<b>Project</b>	28737	<b>Date</b>	07:13:39 10/10/14
	<b>Client</b>	Transcend Wireless / Sprint	<b>Designed by</b>	A. Kraus

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Force lb	Major Axis Moment lb-ft	Minor Axis Moment lb-ft
T6	100 - 80	Leg	Max. Vx	17	-1.52	0.00	0.00
			Max Tension	4	188228.76	-845.74	9.76
			Max. Compression	23	-222365.84	495.60	12.86
			Max. Mx	23	-195863.22	1160.14	-27.31
			Max. My	11	-7895.60	2.03	-959.56
			Max. Vy	6	131.14	1152.81	5.33
		Diagonal	Max. Vx	5	108.50	9.15	957.77
			Max Tension	22	6940.89	0.00	0.00
			Max. Compression	22	-7108.67	0.00	0.00
			Max. Mx	23	6029.55	69.18	-4.79
			Max. My	17	-5875.92	28.30	7.96
			Max. Vy	25	32.93	67.37	-5.92
			Max. Vx	17	-1.88	0.00	0.00
			Max Tension	4	217056.55	-634.97	-0.37
T7	80 - 60	Leg	Max. Compression	23	-260048.90	1314.82	-43.31
			Max. Mx	17	203408.35	-1544.86	37.53
			Max. My	11	-11016.80	13.58	-1129.11
			Max. Vy	17	211.29	-1544.86	37.53
			Max. Vx	5	-156.93	20.19	1127.47
			Max Tension	22	7278.07	0.00	0.00
		Diagonal	Max. Compression	22	-7428.38	0.00	0.00
			Max. Mx	23	6219.46	73.73	-5.32
			Max. My	16	-7104.04	22.91	10.37
			Max. Vy	25	32.91	72.45	-6.17
			Max. Vx	16	-2.04	0.00	0.00
			Max Tension	4	241835.92	-643.13	12.28
			Max. Compression	23	-293628.89	303.55	-3.41
			Max. Mx	17	226279.20	-1761.01	8.29
T8	60 - 40	Leg	Max. My	11	-11481.79	13.55	-1129.11
			Max. Vy	17	227.46	-1761.01	8.29
			Max. Vx	13	119.29	-73.39	945.37
			Max Tension	22	8650.19	0.00	0.00
			Max. Compression	22	-8750.73	0.00	0.00
			Max. Mx	23	7737.65	146.54	-13.19
		Diagonal	Max. My	16	-8693.49	49.29	21.08
			Max. Vy	25	56.13	139.61	-14.42
			Max. Vx	16	-3.63	0.00	0.00
			Max Tension	4	267108.37	-1771.87	8.01
			Max. Compression	23	-329551.71	-1796.67	-43.88
			Max. Mx	17	248852.33	-6853.75	42.09
			Max. My	11	-14181.70	-142.54	-2195.85
			Max. Vy	17	877.22	-6853.75	42.09
T9	40 - 20	Leg	Max. Vx	11	272.56	-142.54	-2195.85
			Max Tension	22	9916.73	0.00	0.00
			Max. Compression	22	-9231.22	0.00	0.00
			Max. Mx	23	6989.28	148.00	-13.68
			Max. My	17	-7650.13	90.03	16.34
			Max. Vy	25	54.11	147.75	-14.33
		Diagonal	Max. Vx	17	-2.93	0.00	0.00
			Max Tension	4	291481.49	-1706.01	14.71
			Max. Compression	23	-365807.96	-0.00	-0.00
			Max. Mx	23	-344409.45	6941.21	4.08
			Max. My	11	-16575.40	-213.24	-3598.40
			Max. Vy	17	-1167.35	-6853.75	42.09
			Max. Vx	11	-474.09	-213.29	-3598.40
			Max Tension	22	12563.14	0.00	0.00
T10	20 - 0	Leg	Max. Compression	22	-11588.50	0.00	0.00
			Max. Mx	25	4577.16	263.07	24.18
			Max. My	16	-11527.28	164.42	34.01
			Max. Vy	25	81.10	263.07	24.18
			Max. Vx	16	-4.95	0.00	0.00
			Max Tension	4	291481.49	-1706.01	14.71
		Diagonal	Max. Compression	23	-365807.96	-0.00	-0.00
			Max. Mx	23	-344409.45	6941.21	4.08
			Max. My	11	-16575.40	-213.24	-3598.40
			Max. Vy	17	-1167.35	-6853.75	42.09
			Max. Vx	11	-474.09	-213.29	-3598.40
			Max Tension	22	12563.14	0.00	0.00
			Max. Compression	22	-11588.50	0.00	0.00
			Max. Mx	25	4577.16	263.07	24.18

<b>tnxTower</b>  <b>Ramaker &amp; Associates</b> 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b>	Transfer Station (CT33XC522)	<b>Page</b>	18 of 26
	<b>Project</b>	28737	<b>Date</b>	07:13:39 10/10/14
	<b>Client</b>	Transcend Wireless / Sprint	<b>Designed by</b>	A. Kraus

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Force lb	Major Axis Moment lb-ft	Minor Axis Moment lb-ft
-------------	--------------	----------------	-----------	-----------------	----------	-------------------------	-------------------------

### Maximum Reactions

Location	Condition	Gov. Load Comb.	Vertical lb	Horizontal, X lb	Horizontal, Z lb
Leg C	Max. Vert	23	371821.41	27303.93	-16075.35
	Max. H <sub>x</sub>	10	354152.80	30502.71	-17869.65
	Max. H <sub>z</sub>	17	-278384.13	-29342.21	17173.75
	Min. Vert	4	-297453.32	-26030.96	15263.06
	Min. H <sub>x</sub>	17	-278384.13	-29342.21	17173.75
	Min. H <sub>z</sub>	10	354152.80	30502.71	-17869.65
Leg B	Max. Vert	19	368761.01	-27337.11	-15781.29
	Max. H <sub>x</sub>	25	-279747.45	29443.57	17000.43
	Max. H <sub>z</sub>	25	-279747.45	29443.57	17000.43
	Min. Vert	12	-297435.33	26089.06	15096.02
	Min. H <sub>x</sub>	6	351954.73	-30497.65	-17640.02
	Min. H <sub>z</sub>	6	351954.73	-30497.65	-17640.02
Leg A	Max. Vert	15	371332.81	-271.24	31643.76
	Max. H <sub>x</sub>	11	18182.85	3221.80	1326.13
	Max. H <sub>z</sub>	2	353375.77	-196.34	35297.21
	Min. Vert	8	-296776.19	173.71	-30122.36
	Min. H <sub>x</sub>	5	19894.24	-3237.42	1450.88
	Min. H <sub>z</sub>	21	-277748.54	200.77	-33955.11

### Tower Mast Reaction Summary

Load Combination	Vertical lb	Shear <sub>x</sub> lb	Shear <sub>z</sub> lb	Overturning Moment, M <sub>x</sub> lb-ft	Overturning Moment, M <sub>z</sub> lb-ft	Torque lb-ft
Dead Only	56475.46	0.00	-0.00	-3794.25	7628.18	0.01
Dead+Wind 0 deg - No Ice	56475.46	74.17	-56075.41	-6084316.10	-5217.74	-7019.31
Dead+Wind 30 deg - No Ice	56475.46	26436.79	-45755.78	-5059877.43	-2915585.35	-8251.41
Dead+Wind 60 deg - No Ice	56475.46	44784.98	-25925.37	-2890545.04	-4972991.04	-7484.45
Dead+Wind 90 deg - No Ice	56475.46	52792.78	-93.78	-19443.00	-5823145.53	-4952.88
Dead+Wind 120 deg - No Ice	56475.46	48516.48	27957.55	3023068.67	-5250351.67	-1057.03
Dead+Wind 150 deg - No Ice	56475.46	26315.17	45674.20	5038344.13	-2894226.36	3166.36
Dead+Wind 180 deg - No Ice	56475.46	-105.82	51667.44	5739694.40	24939.93	6461.12
Dead+Wind 210 deg - No Ice	56475.46	-26487.45	45726.53	5048182.52	2937939.30	8250.82
Dead+Wind 240 deg - No Ice	56475.46	-48618.22	28101.94	3047575.10	5282362.37	8076.35
Dead+Wind 270 deg - No Ice	56475.46	-52854.02	93.18	11681.25	5846933.98	4874.48
Dead+Wind 300 deg - No Ice	56475.46	-44781.22	-25801.00	-2868782.56	4985177.81	1023.34
Dead+Wind 330 deg - No Ice	56475.46	-26346.31	-45726.94	-5053264.86	2913861.59	-3087.35
Dead+Ice+Temp	88816.85	0.00	0.00	-12492.21	20123.58	0.04
Dead+Wind 0 deg+Ice+Temp	88816.84	56.72	-57400.21	-6214833.01	10405.22	-9125.42
Dead+Wind 30 deg+Ice+Temp	88816.84	26082.12	-45150.54	-5001282.33	-2863109.29	-9518.94
Dead+Wind 60 deg+Ice+Temp	88816.85	43603.29	-25227.62	-2825312.03	-4836589.91	-7976.39
Dead+Wind 90 deg+Ice+Temp	88816.84	52103.77	-72.26	-24659.13	-5734552.24	-4738.93
Dead+Wind 120 deg+Ice+Temp	88816.84	49674.48	28638.37	3078245.68	-5345037.39	86.59
Dead+Wind 150 deg+Ice+Temp	88816.84	25989.31	45087.96	4965451.61	-2846701.40	4691.99
Dead+Wind 180 deg+Ice+Temp	88816.85	-81.80	50313.57	5589706.66	33624.11	7911.08
Dead+Wind 210 deg+Ice+Temp	88816.84	-26122.25	45127.37	4972927.71	2909138.00	9518.55
Dead+Wind 240 deg+Ice+Temp	88816.84	-49753.04	28749.22	3097062.89	5398441.57	9038.86

<p><b>tnxTower</b></p> <p><b>Ramaker &amp; Associates</b> 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999</p>	<p><b>Job</b></p> <p>Transfer Station (CT33XC522)</p>	<p><b>Page</b></p> <p>19 of 26</p>
	<p><b>Project</b></p> <p>28737</p>	<p><b>Date</b></p> <p>07:13:39 10/10/14</p>
	<p><b>Client</b></p> <p>Transcend Wireless / Sprint</p>	<p><b>Designed by</b></p> <p>A. Kraus</p>

Load Combination	Vertical lb	Shear <sub>x</sub> lb	Shear <sub>z</sub> lb	Overturning Moment, M <sub>x</sub> lb-ft	Overturning Moment, M <sub>z</sub> lb-ft	Torque lb-ft
Dead+Wind 270 deg+Ice+Temp	88816.84	-52152.31	71.78	-596.97	5781717.72	4676.84
Dead+Wind 300 deg+Ice+Temp	88816.85	-43602.37	-25132.64	-2808590.08	4874874.22	65.36
Dead+Wind 330 deg+Ice+Temp	88816.84	-26013.99	-45129.75	-4996350.50	2890596.58	-4629.44
Dead+Wind 0 deg - Service	56475.46	36.96	-27940.69	-3033615.53	1233.98	-3497.36
Dead+Wind 30 deg - Service	56475.46	13172.66	-22798.72	-2523149.56	-1448946.21	-4114.19
Dead+Wind 60 deg - Service	56475.46	22315.01	-12917.83	-1442207.61	-2474109.64	-3729.73
Dead+Wind 90 deg - Service	56475.46	26305.05	-46.73	-11594.36	-2897724.59	-2465.20
Dead+Wind 120 deg - Service	56475.46	24174.30	13930.41	1504430.13	-2612314.05	-526.73
Dead+Wind 150 deg - Service	56475.46	13112.06	22758.08	2508598.05	-1438300.32	1574.90
Dead+Wind 180 deg - Service	56475.46	-52.73	25744.33	2858064.69	16260.23	3219.85
Dead+Wind 210 deg - Service	56475.46	-13197.89	22784.15	2513502.88	1467752.27	4114.02
Dead+Wind 240 deg - Service	56475.46	-24224.99	14002.35	1516645.35	2635939.21	4024.09
Dead+Wind 270 deg - Service	56475.46	-26335.57	46.43	3913.24	2917254.15	2425.81
Dead+Wind 300 deg - Service	56475.46	-22313.13	-12855.86	-1431367.74	2487855.18	510.12
Dead+Wind 330 deg - Service	56475.46	-13127.57	-22784.36	-2519857.74	1455759.48	-1535.34

## Solution Summary

Load Comb.	Sum of Applied Forces			Sum of Reactions			% Error
	PX lb	PY lb	PZ lb	PX lb	PY lb	PZ lb	
1	0.00	-56475.46	-0.00	-0.00	56475.46	0.00	0.000%
2	74.17	-56475.46	-56075.41	-74.17	56475.46	56075.41	0.000%
3	26436.79	-56475.46	-45755.78	-26436.79	56475.46	45755.78	0.000%
4	44784.98	-56475.46	-25925.37	-44784.98	56475.46	25925.37	0.000%
5	52792.78	-56475.46	-93.78	-52792.78	56475.46	93.78	0.000%
6	48516.48	-56475.46	27957.55	-48516.48	56475.46	-27957.55	0.000%
7	26315.18	-56475.46	45674.20	-26315.17	56475.46	-45674.20	0.000%
8	-105.82	-56475.46	51667.44	105.82	56475.46	-51667.44	0.000%
9	-26487.45	-56475.46	45726.53	26487.45	56475.46	-45726.53	0.000%
10	-48618.22	-56475.46	28101.94	48618.22	56475.46	-28101.94	0.000%
11	-52854.02	-56475.46	93.18	52854.02	56475.46	-93.18	0.000%
12	-44781.22	-56475.46	-25801.00	44781.22	56475.46	25801.00	0.000%
13	-26346.31	-56475.46	-45726.94	26346.31	56475.46	45726.94	0.000%
14	0.00	-88816.85	-0.00	-0.00	88816.85	-0.00	0.000%
15	56.72	-88816.85	-57400.26	-56.72	88816.84	57400.21	0.000%
16	26082.13	-88816.85	-45150.58	-26082.12	88816.84	45150.54	0.000%
17	43603.29	-88816.85	-25227.62	-43603.29	88816.85	25227.62	0.000%
18	52103.81	-88816.85	-72.25	-52103.77	88816.84	72.26	0.000%
19	49674.52	-88816.85	28638.40	-49674.48	88816.84	-28638.37	0.000%
20	25989.33	-88816.85	45087.99	-25989.31	88816.84	-45087.96	0.000%
21	-81.80	-88816.85	50313.57	81.80	88816.85	-50313.57	0.000%
22	-26122.28	-88816.85	45127.40	26122.25	88816.84	-45127.37	0.000%
23	-49753.08	-88816.85	28749.25	49753.04	88816.84	-28749.22	0.000%
24	-52152.35	-88816.85	71.78	52152.31	88816.84	-71.78	0.000%
25	-43602.37	-88816.85	-25132.64	43602.37	88816.85	25132.64	0.000%
26	-26014.01	-88816.85	-45129.78	26013.99	88816.84	45129.75	0.000%
27	36.96	-56475.46	-27940.69	-36.96	56475.46	27940.69	0.000%
28	13172.65	-56475.46	-22798.73	-13172.66	56475.46	22798.72	0.000%
29	22315.01	-56475.46	-12917.83	-22315.01	56475.46	12917.83	0.000%
30	26305.05	-56475.46	-46.73	-26305.05	56475.46	46.73	0.000%
31	24174.30	-56475.46	13930.41	-24174.30	56475.46	-13930.41	0.000%
32	13112.06	-56475.46	22758.08	-13112.06	56475.46	-22758.08	0.000%
33	-52.73	-56475.46	25744.33	52.73	56475.46	-25744.33	0.000%
34	-13197.90	-56475.46	22784.15	13197.89	56475.46	-22784.15	0.000%
35	-24224.99	-56475.46	14002.35	24224.99	56475.46	-14002.35	0.000%
36	-26335.57	-56475.46	46.43	26335.57	56475.46	-46.43	0.000%
37	-22313.13	-56475.46	-12855.86	22313.13	56475.46	12855.86	0.000%

<b>tnxTower</b>  <b>Ramaker &amp; Associates</b> 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b>	Transfer Station (CT33XC522)	<b>Page</b>	20 of 26
	<b>Project</b>	28737	<b>Date</b>	07:13:39 10/10/14
	<b>Client</b>	Transcend Wireless / Sprint	<b>Designed by</b>	A. Kraus

Load Comb.	Sum of Applied Forces			Sum of Reactions			% Error
	PX lb	PY lb	PZ lb	PX lb	PY lb	PZ lb	
38	-13127.57	-56475.46	-22784.36	13127.57	56475.46	22784.36	0.000%

### Non-Linear Convergence Results

Load Combination	Converged?	Number of Cycles	Displacement Tolerance	Force Tolerance
1	Yes	4	0.0000001	0.0000001
2	Yes	4	0.0000001	0.0000001
3	Yes	4	0.0000001	0.00000069
4	Yes	4	0.0000001	0.00000069
5	Yes	4	0.0000001	0.00000097
6	Yes	4	0.0000001	0.0000001
7	Yes	4	0.0000001	0.00000079
8	Yes	4	0.0000001	0.00000062
9	Yes	4	0.0000001	0.00000069
10	Yes	4	0.0000001	0.00000061
11	Yes	4	0.0000001	0.00000096
12	Yes	4	0.0000001	0.0000001
13	Yes	4	0.0000001	0.00000078
14	Yes	4	0.0000001	0.0000001
15	Yes	4	0.0000001	0.00000158
16	Yes	4	0.0000001	0.00000180
17	Yes	4	0.0000001	0.00000195
18	Yes	4	0.0000001	0.00000197
19	Yes	4	0.0000001	0.00000156
20	Yes	4	0.0000001	0.00000187
21	Yes	4	0.0000001	0.00000193
22	Yes	4	0.0000001	0.00000180
23	Yes	4	0.0000001	0.00000164
24	Yes	4	0.0000001	0.00000196
25	Yes	4	0.0000001	0.00000190
26	Yes	4	0.0000001	0.00000186
27	Yes	4	0.0000001	0.0000001
28	Yes	4	0.0000001	0.0000001
29	Yes	4	0.0000001	0.0000001
30	Yes	4	0.0000001	0.0000001
31	Yes	4	0.0000001	0.0000001
32	Yes	4	0.0000001	0.0000001
33	Yes	4	0.0000001	0.0000001
34	Yes	4	0.0000001	0.0000001
35	Yes	4	0.0000001	0.0000001
36	Yes	4	0.0000001	0.0000001
37	Yes	4	0.0000001	0.0000001
38	Yes	4	0.0000001	0.0000001

### Maximum Tower Deflections - Service Wind

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
T1	185 - 180	9.775	35	0.5772	0.0154
T2	180 - 160	9.165	35	0.5736	0.0152



<b>tnxTower</b>  <b>Ramaker &amp; Associates</b> 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b>	Transfer Station (CT33XC522)	<b>Page</b>	21 of 26
	<b>Project</b>	28737	<b>Date</b>	07:13:39 10/10/14
	<b>Client</b>	Transcend Wireless / Sprint	<b>Designed by</b>	A. Kraus

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
T3	160 - 140	6.838	35	0.4985	0.0165
T4	140 - 120	4.942	35	0.3728	0.0156
T5	120 - 100	3.468	35	0.2932	0.0104
T6	100 - 80	2.316	35	0.2260	0.0072
T7	80 - 60	1.444	35	0.1689	0.0054
T8	60 - 40	0.785	35	0.1120	0.0032
T9	40 - 20	0.372	35	0.0677	0.0021
T10	20 - 0	0.109	35	0.0339	0.0009

### Critical Deflections and Radius of Curvature - Service Wind

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
185.00	8' Dipole	35	9.775	0.5772	0.0154	68542
174.00	Andrew 12'-6" Universal Sector Frame	35	8.440	0.5610	0.0154	23795
164.00	Andrew 12'-6" Quik-Tee Sector Frame	35	7.277	0.5205	0.0162	10942
154.00	Andrew 12'-6" Quik-Tee Sector Frame	35	6.218	0.4609	0.0167	9602
146.00	6' Standoff	35	5.461	0.4084	0.0164	10504
138.00	Andrew 3' w/Radome	35	4.777	0.3625	0.0152	11594

### Maximum Tower Deflections - Design Wind

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
T1	185 - 180	19.674	23	1.1583	0.0375
T2	180 - 160	18.463	23	1.1512	0.0373
T3	160 - 140	13.833	23	1.0003	0.0392
T4	140 - 120	10.042	23	0.7495	0.0364
T5	120 - 100	7.068	23	0.5929	0.0247
T6	100 - 80	4.731	23	0.4589	0.0172
T7	80 - 60	2.955	23	0.3439	0.0129
T8	60 - 40	1.608	23	0.2285	0.0074
T9	40 - 20	0.763	23	0.1384	0.0049
T10	20 - 0	0.223	23	0.0694	0.0020

### Critical Deflections and Radius of Curvature - Design Wind

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
185.00	8' Dipole	23	19.674	1.1583	0.0375	34762
174.00	Andrew 12'-6" Universal Sector Frame	23	17.021	1.1264	0.0376	11948
164.00	Andrew 12'-6" Quik-Tee Sector Frame	23	14.706	1.0447	0.0388	5483
154.00	Andrew 12'-6" Quik-Tee Sector Frame	23	12.597	0.9246	0.0395	4802
146.00	6' Standoff	23	11.084	0.8192	0.0385	5237
138.00	Andrew 3' w/Radome	23	9.711	0.7293	0.0355	5781

<b>tnxTower</b>  <b>Ramaker &amp; Associates</b> 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b>	Transfer Station (CT33XC522)	<b>Page</b>	22 of 26
	<b>Project</b>	28737	<b>Date</b>	07:13:39 10/10/14
	<b>Client</b>	Transcend Wireless / Sprint	<b>Designed by</b>	A. Kraus

### Bolt Design Data

Section No.	Elevation ft	Component Type	Bolt Grade	Bolt Size in	Number Of Bolts	Maximum Load per Bolt lb	Allowable Load lb	Ratio Load		Allowable Ratio	Criteria
									Allowable		
T1	185	Leg	A325X	0.7500	6	308.39	19435.50	0.016	✓	1.333	Bolt Tension
		Diagonal	A325X	0.6250	1	1451.28	3443.75	0.421	✓	1.333	Member Block Shear
		Top Girt	A325X	0.6250	1	552.68	3443.75	0.160	✓	1.333	Member Block Shear
T2	180	Leg	A325X	0.7500	6	5210.12	19432.20	0.268	✓	1.333	Bolt Tension
		Diagonal	A325X	0.6250	1	6301.47	6887.50	0.915	✓	1.333	Member Block Shear
		Top Girt	A325X	0.6250	1	492.38	3443.75	0.143	✓	1.333	Member Block Shear
T3	160	Leg	A325X	1.0000	6	13504.20	34557.40	0.391	✓	1.333	Bolt Tension
		Diagonal	A325X	0.6250	1	6354.10	6887.50	0.923	✓	1.333	Member Block Shear
		Secondary Horizontal	A325X	0.6250	1	1620.77	6071.88	0.267	✓	1.333	Member Block Shear
		Top Girt	A325X	0.6250	1	1005.02	3443.75	0.292	✓	1.333	Member Block Shear
T4	140	Leg	A325X	1.0000	6	20638.20	34557.50	0.597	✓	1.333	Bolt Tension
		Diagonal	A325N	0.6250	1	6023.07	5165.63	1.166	✓	1.333	Member Block Shear
T5	120	Leg	A325X	1.0000	6	26185.90	34557.50	0.758	✓	1.333	Bolt Tension
		Diagonal	A325X	0.6250	1	6534.61	6117.19	1.068	✓	1.333	Member Bearing
T6	100	Leg	A325X	1.0000	6	31371.50	34557.50	0.908	✓	1.333	Bolt Tension
		Diagonal	A325X	0.6250	1	7108.67	9203.88	0.772	✓	1.333	Bolt Shear
T7	80	Leg	A325X	1.0000	6	36176.10	34557.50	1.047	✓	1.333	Bolt Tension
		Diagonal	A325X	0.7500	1	7278.07	6796.88	1.071	✓	1.333	Member Bearing
T8	60	Leg	A325X	1.2500	6	40306.00	53996.10	0.746	✓	1.333	Bolt Tension
		Diagonal	A325X	0.7500	1	8750.73	13253.60	0.660	✓	1.333	Bolt Shear
T9	40	Leg	A325X	1.2500	6	44518.10	53996.10	0.824	✓	1.333	Bolt Tension
		Diagonal	A325X	0.7500	1	9916.73	9062.50	1.094	✓	1.333	Member Bearing
T10	20	Leg	A572-50	1.5000	6	48580.20	37905.30	1.282	✓	1.333	Bolt Tension
		Diagonal	A325X	0.7500	1	12563.10	13253.60	0.948	✓	1.333	Bolt Shear

### Compression Checks

### Leg Design Data (Compression)

<b>tnxTower</b>  <b>Ramaker &amp; Associates</b> 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b>	Transfer Station (CT33XC522)	<b>Page</b>	23 of 26
	<b>Project</b>	28737	<b>Date</b>	07:13:39 10/10/14
	<b>Client</b>	Transcend Wireless / Sprint	<b>Designed by</b>	A. Kraus

Section No.	Elevation ft	Size	L ft	L <sub>a</sub> ft	KI/r	F <sub>a</sub> ksi	A in <sup>2</sup>	Actual P lb	Allow. P <sub>a</sub> lb	Ratio P P <sub>a</sub>
T1	185 - 180	P2x.154	5.00	5.00	76.2 K=1.00	19.756	1.0745	-3263.60	21228.60	0.154
T2	180 - 160	P2.5x.203	20.00	5.00	63.3 K=1.00	22.141	1.7040	-37645.20	37729.30	0.998
T3	160 - 140	P2.5x.375	20.03	2.62	35.2 K=1.00	26.484	2.9452	-93458.70	78001.30	1.198
T4	140 - 120	P3.5x0.318 + L3.5x3.5x0.375	20.03	5.01	63.1 K=1.40	22.184	5.9300	-142063.00	131554.00	1.080
T5	120 - 100	P5x0.258 + L5x5x0.375	20.03	6.68	58.3 K=1.39	23.009	7.6600	-182576.00	176245.00	1.036
T6	100 - 80	P5x0.375 + L5x5x0.375	20.03	6.68	58.7 K=1.38	22.934	9.3700	-222366.00	214896.00	1.035
T7	80 - 60	P5x0.375 + L5x5x0.375	20.03	6.68	47.0 K=1.11	24.808	9.3700	-260049.00	232454.00	1.119
T8	60 - 40	P5x0.500 + L5x5x0.500	20.03	10.02	71.5 K=1.11	20.651	12.2400	-293629.00	252770.00	1.162
T9	40 - 20	P8x0.322 + L8x8x0.500	20.03	10.02	55.0 K=1.38	23.552	15.6900	-329552.00	369523.00	0.892
T10	20 - 0	P8x0.322 + L8x8x0.500	20.03	10.02	55.0 K=1.38	23.552	15.6900	-365808.00	369523.00	0.990

### Diagonal Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L <sub>a</sub> ft	KI/r	F <sub>a</sub> ksi	A in <sup>2</sup>	Actual P lb	Allow. P <sub>a</sub> lb	Ratio P P <sub>a</sub>
T1	185 - 180	L2x2x1/8	7.07	3.26	103.8 K=1.05	12.288	0.4844	-1706.42	5952.00	0.287
T2	180 - 160	L2x2x1/4	7.07	3.23	104.4 K=1.05	12.418	0.9380	-6675.26	11647.90	0.573
T3	160 - 140	L2x2x1/4	8.40	4.21	129.1 K=1.00	8.957	0.9380	-6459.30	8401.49	0.769
T4	140 - 120	L2x2x3/16	10.08	4.81	146.5 K=1.00	6.957	0.7150	-5965.79	4974.11	1.199
T5	120 - 100	L2 1/2x2 1/2x3/16	12.58	6.00	145.5 K=1.00	7.049	0.9020	-6678.87	6358.51	1.050
T6	100 - 80	L2 1/2x2 1/2x5/16	14.32	6.88	168.8 K=1.00	5.242	1.4600	-7108.67	7653.89	0.929
T7	80 - 60	L3x3x3/16	16.11	7.77	156.4 K=1.00	6.102	1.0900	-7289.98	6651.42	1.096
T8	60 - 40	L3x3x3/8	19.30	9.45	193.2 K=1.00	4.001	2.1100	-8508.90	8442.74	1.008
T9	40 - 20	L3 1/2x3 1/2x1/4	21.03	10.12	175.0 K=1.00	4.878	1.6900	-9022.85	8244.66	1.094
T10	20 - 0	L3 1/2x3 1/2x3/8	21.92	10.57	184.6 K=1.00	4.382	2.4800	-11588.50	10866.60	1.066

<b>tnxTower</b>  <b>Ramaker &amp; Associates</b> 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b> Transfer Station (CT33XC522)	<b>Page</b> 24 of 26
	<b>Project</b> 28737	<b>Date</b> 07:13:39 10/10/14
	<b>Client</b> Transcend Wireless / Sprint	<b>Designed by</b> A. Kraus

### Secondary Horizontal Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L <sub>a</sub> ft	KI/r	F <sub>a</sub> ksi	A in <sup>2</sup>	Actual P lb	Allow. P <sub>a</sub> lb	Ratio P P <sub>a</sub>
T3	160 - 140	L2x2x1/4	6.74	6.50	99.8 K=0.50	13.008	0.9380	-1620.77	12201.40	0.133 

### Top Girt Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L <sub>a</sub> ft	KI/r	F <sub>a</sub> ksi	A in <sup>2</sup>	Actual P lb	Allow. P <sub>a</sub> lb	Ratio P P <sub>a</sub>
T1	185 - 180	L2x2x1/8	5.00	4.53	136.8 K=1.00	7.982	0.4844	-371.50	3866.35	0.096 
T2	180 - 160	L2x2x1/8	5.00	4.53	136.8 K=1.00	7.982	0.4844	-404.33	3866.35	0.105 
T3	160 - 140	L2x2x1/8	5.00	4.76	143.7 K=1.00	7.232	0.4844	-1002.32	3503.06	0.286 

### Tension Checks

### Leg Design Data (Tension)

Section No.	Elevation ft	Size	L ft	L <sub>a</sub> ft	KI/r	F <sub>a</sub> ksi	A in <sup>2</sup>	Actual P lb	Allow. P <sub>a</sub> lb	Ratio P P <sub>a</sub>
T1	185 - 180	P2x.154	5.00	5.00	76.2	30.000	1.0745	1850.33	32235.90	0.057 
T2	180 - 160	P2.5x.203	20.00	5.00	63.3	30.000	1.7040	31260.70	51121.50	0.611 
T3	160 - 140	P2.5x.375	20.03	2.62	35.2	30.000	2.9452	81105.30	88357.30	0.918 
T4	140 - 120	P3.5x0.318 + L3.5x3.5x0.375	20.03	5.01	45.2	30.000	5.9300	123829.00	177900.00	0.696 
T5	120 - 100	P5x0.258 + L5x5x0.375	20.03	6.68	41.8	30.000	7.6600	157115.00	229800.00	0.684 
T6	100 - 80	P5x0.375 + L5x5x0.375	20.03	6.68	42.4	30.000	9.3700	188229.00	281100.00	0.670 
T7	80 - 60	P5x0.375 + L5x5x0.375	20.03	6.68	42.4	30.000	9.3700	217057.00	281100.00	0.772 
T8	60 - 40	P5x0.500 + L5x5x0.500	20.03	10.02	64.6	30.000	12.2400	241836.00	367200.00	0.659 
T9	40 - 20	P8x0.322 + L8x8x0.500	20.03	10.02	39.9	30.000	15.6900	267108.00	470700.00	0.567 
T10	20 - 0	P8x0.322 + L8x8x0.500	20.03	10.02	39.9	30.000	15.6900	291482.00	470700.00	0.619 

<b>tnxTower</b>  <b>Ramaker &amp; Associates</b> 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b>	Transfer Station (CT33XC522)	<b>Page</b>	25 of 26
	<b>Project</b>	28737	<b>Date</b>	07:13:39 10/10/14
	<b>Client</b>	Transcend Wireless / Sprint	<b>Designed by</b>	A. Kraus

### Diagonal Design Data (Tension)

Section No.	Elevation ft	Size	L ft	L <sub>a</sub> ft	Kl/r	F <sub>a</sub> ksi	A in <sup>2</sup>	Actual P lb	Allow. P <sub>a</sub> lb	Ratio P P <sub>a</sub>
T1	185 - 180	L2x2x1/8	7.07	3.26	65.1	21.600	0.4844	1451.28	10462.50	0.139
T2	180 - 160	L2x2x1/4	7.07	3.23	66.3	21.600	0.9380	6301.47	20260.80	0.311
T3	160 - 140	L2x2x1/4	8.40	4.21	82.9	21.600	0.9380	6354.10	20260.80	0.314
T4	140 - 120	L2x2x3/16	8.81	4.18	84.0	21.600	0.7150	6023.07	15444.00	0.390
T5	120 - 100	L2 1/2x2 1/2x3/16	12.02	5.73	90.4	21.600	0.9020	6534.61	19483.20	0.335
T6	100 - 80	L2 1/2x2 1/2x5/16	14.32	6.88	110.6	21.600	1.4600	6940.89	31536.00	0.220
T7	80 - 60	L3x3x3/16	16.11	7.77	101.2	21.600	1.0900	7278.07	23544.00	0.309
T8	60 - 40	L3x3x3/8	19.30	9.45	126.1	21.600	2.1100	8650.19	45576.00	0.190
T9	40 - 20	L3 1/2x3 1/2x1/4	21.03	10.12	113.0	21.600	1.6900	9916.73	36504.00	0.272
T10	20 - 0	L3 1/2x3 1/2x3/8	22.81	11.01	125.1	21.600	2.4800	12563.10	53568.00	0.235

### Secondary Horizontal Design Data (Tension)

Section No.	Elevation ft	Size	L ft	L <sub>a</sub> ft	Kl/r	F <sub>a</sub> ksi	A in <sup>2</sup>	Actual P lb	Allow. P <sub>a</sub> lb	Ratio P P <sub>a</sub>
T3	160 - 140	L2x2x1/4	6.74	6.50	128.1	21.600	0.9380	1620.77	20260.80	0.080


### Top Girt Design Data (Tension)

Section No.	Elevation ft	Size	L ft	L <sub>a</sub> ft	Kl/r	F <sub>a</sub> ksi	A in <sup>2</sup>	Actual P lb	Allow. P <sub>a</sub> lb	Ratio P P <sub>a</sub>
T1	185 - 180	L2x2x1/8	5.00	4.53	92.0	21.600	0.4844	552.68	10462.50	0.053
T2	180 - 160	L2x2x1/8	5.00	4.53	92.0	21.600	0.4844	492.38	10462.50	0.047
T3	160 - 140	L2x2x1/8	5.00	4.76	91.2	21.600	0.4844	1005.02	10462.50	0.096

<b>tnxTower</b>  <b>Ramaker &amp; Associates</b> 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b> Transfer Station (CT33XC522)	<b>Page</b> 26 of 26
	<b>Project</b> 28737	<b>Date</b> 07:13:39 10/10/14
	<b>Client</b> Transcend Wireless / Sprint	<b>Designed by</b> A. Kraus

### Section Capacity Table

Section No.	Elevation ft	Component Type	Size	Critical Element	P lb	SF*P <sub>allow</sub> lb	% Capacity	Pass Fail	
T1	185 - 180	Leg	P2x.154	2	-3263.60	28297.72	11.5	Pass	
T2	180 - 160	Leg	P2.5x.203	14	-37645.20	50293.16	74.9	Pass	
T3	160 - 140	Leg	P2.5x.375	45	-93458.70	103975.72	89.9	Pass	
T4	140 - 120	Leg	P3.5x0.318 + L3.5x3.5x0.375	85	-142063.00	175361.47	81.0	Pass	
T5	120 - 100	Leg	P5x0.258 + L5x5x0.375	112	-182576.00	234934.58	77.7	Pass	
T6	100 - 80	Leg	P5x0.375 + L5x5x0.375	133	-222366.00	286456.36	77.6	Pass	
T7	80 - 60	Leg	P5x0.375 + L5x5x0.375	154	-260049.00	309861.17	83.9	Pass	
T8	60 - 40	Leg	P5x0.500 + L5x5x0.500	175	-293629.00	336942.40	87.1	Pass	
T9	40 - 20	Leg	P8x0.322 + L8x8x0.500	190	-329552.00	492574.14	66.9	Pass	
T10	20 - 0	Leg	P8x0.322 + L8x8x0.500	205	-365808.00	492574.14	74.3	Pass	
T1	185 - 180	Diagonal	L2x2x1/8	9	-1706.42	7934.02	21.5	Pass	
T2	180 - 160	Diagonal	L2x2x1/4	22	-6675.26	15526.65	43.0	Pass	
T3	160 - 140	Diagonal	L2x2x1/4	54	-6459.30	11199.19	57.7	Pass	
T4	140 - 120	Diagonal	L2x2x3/16	93	-5965.79	6630.49	90.0	Pass	
T5	120 - 100	Diagonal	L2 1/2x2 1/2x3/16	120	-6678.87	8475.89	78.8	Pass	
T6	100 - 80	Diagonal	L2 1/2x2 1/2x5/16	141	-7108.67	10202.64	69.7	Pass	
T7	80 - 60	Diagonal	L3x3x3/16	162	-7289.98	8866.34	82.2	Pass	
T8	60 - 40	Diagonal	L3x3x3/8	182	-8508.90	11254.17	75.6	Pass	
T9	40 - 20	Diagonal	L3 1/2x3 1/2x1/4	197	-9022.85	10990.13	82.1	Pass	
T10	20 - 0	Diagonal	L3 1/2x3 1/2x3/8	219	-11588.50	14485.18	80.0	Pass	
T3	160 - 140	Secondary Horizontal	L2x2x1/4	56	-1620.77	16264.47	10.0	Pass	
T1	185 - 180	Top Girt	L2x2x1/8	4	-371.50	5153.84	7.2	Pass	
T2	180 - 160	Top Girt	L2x2x1/8	16	-404.33	5153.84	7.8	Pass	
T3	160 - 140	Top Girt	L2x2x1/8	47	-1002.32	4669.58	21.5	Pass	
							Summary		
							Leg (T3)	89.9	Pass
							Diagonal (T4)	90.0	Pass
							Secondary Horizontal (T3)	10.0	Pass
							Top Girt (T3)	21.5	Pass
							Bolt Checks	96.1	Pass
							<b>RATING =</b>	<b>96.1</b>	<b>Pass</b>



Results for LC 69, 0.9D+1.6Wind0

Ramaker & Associates

A. Kraus


28737

Transfer Station (CT33XC522)

SK - 1

Oct 13, 2014 at 4:55 PM

28737 rev1 MODS.FND



Results for LC 69, 0.9D+1.6Wind0

Ramaker & Associates

A. Kraus

28737

Transfer Station (CT33XC522)

SK - 2

Oct 13, 2014 at 4:56 PM

28737 rev1 MODS.FND





**Pedestals/Posts**

	Label	Type	Shape	Material	Design Rules	Angle(deg)	Height[in]
1	R3D_N172	Pedestal	CRND42	Conc3000NW	Typical	0	0
2	R3D_N173	Pedestal	CRND42	Conc3000NW	Typical	0	0
3	R3D_N174	Pedestal	CRND42	Conc3000NW	Typical	0	0

**Slabs**

	Label	Thickness[in]	Material
1	S1	66	Conc3000NW

**Load Categories**

	Category	Point Loads	Line Loads	Area Loads
1	LL	9		
2	SL	9		
3	EPL			1
4	OL1	12		
5	OL2	12		
6	OL3	12		
7	OL4	12		
8	OL5	12		
9	OL6	12		
10	OL7	12		
11	OL8	12		
12	WL+X	12		
13	WL+Z	12		
14	WL-X	12		
15	WL-Z	12		
16	ELX+Z	12		
17	ELX-Z	12		
18	ELZ+X	12		
19	ELZ-X	12		
20	ELX+Y	12		
21	ELX-Y	12		
22	ELZ+Y	12		
23	ELZ-Y	12		
24	NL	5		
25	WLX+R	12		
26	WLZ+R	12		
27	WLX-R	12		
28	WLZ-R	12		

**Load Combinations**

Label	Sol...	Se...	AB...	SF	Cate...	F...	Cate...	F...	Cate...	F...	Cate...	Fa...	Cate...	Fa...	Cate...	Factor	Cate...	Factor	
1	<b>** SERVICE **</b>																		
2	Dead Only	Yes	Yes		LL	1						DL	.8	EPL	.5				
3	Dead+Wind 0 deg	Yes	Yes	1.3...	LL	1	WL-Z	1				DL	.8	EPL	.5				
4	Dead+Wind 30 deg	Yes	Yes	1.3...	LL	1	OL1	1				DL	.8	EPL	.5				
5	Dead+Wind 60 deg	Yes	Yes	1.3...	LL	1	OL2	1				DL	.8	EPL	.5				
6	Dead+Wind 90 deg	Yes	Yes	1.3...	LL	1	WL+X	1				DL	.8	EPL	.5				
7	Dead+Wind 120 de	Yes	Yes	1.3...	LL	1	OL3	1				DL	.8	EPL	.5				
8	Dead+Wind 150 de	Yes	Yes	1.3...	LL	1	OL4	1				DL	.8	EPL	.5				
9	Dead+Wind 180 de	Yes	Yes	1.3...	LL	1	WL+Z	1				DL	.8	EPL	.5				
10	Dead+Wind 210 de	Yes	Yes	1.3...	LL	1	OL5	1				DL	.8	EPL	.5				
11	Dead+Wind 240 de	Yes	Yes	1.3...	LL	1	OL6	1				DL	.8	EPL	.5				
12	Dead+Wind 270 de	Yes	Yes	1.3...	LL	1	WL-X	1				DL	.8	EPL	.5				
13	Dead+Wind 300 de	Yes	Yes	1.3...	LL	1	OL7	1				DL	.8	EPL	.5				
14	Dead+Wind 330 de	Yes	Yes	1.3...	LL	1	OL8	1				DL	.8	EPL	.5				



**Load Combinations (Continued)**

Label	Sol	Se	AB	SF	Cate	F	Cate	F	Cate	F	Category	F	Cate	Fa	Cate	Fa	Cate	Factor	Cate	Factor
15	Dead+Ice+Temp	Yes	Yes		LL	1	SL	1	NL	1				DL	.8	EPL	.5			
16	Dead+Wind 0 deg+	Yes	Yes	1.3	LL	1	SL	1	NL	1	WLZ-R	1	DL	.8	EPL	.5				
17	Dead+Wind 30 deg+	Yes	Yes	1.3	LL	1	SL	1	NL	1	ELZ-X	1	DL	.8	EPL	.5				
18	Dead+Wind 60 deg+	Yes	Yes	1.3	LL	1	SL	1	NL	1	ELZ-Y	1	DL	.8	EPL	.5				
19	Dead+Wind 90 deg+	Yes	Yes	1.3	LL	1	SL	1	NL	1	WLX+R	1	DL	.8	EPL	.5				
20	Dead+Wind 120 de	Yes	Yes	1.3	LL	1	SL	1	NL	1	ELX+Y	1	DL	.8	EPL	.5				
21	Dead+Wind 150 de	Yes	Yes	1.3	LL	1	SL	1	NL	1	ELX+Z	1	DL	.8	EPL	.5				
22	Dead+Wind 180 de	Yes	Yes	1.3	LL	1	SL	1	NL	1	WLZ+R	1	DL	.8	EPL	.5				
23	Dead+Wind 210 de	Yes	Yes	1.3	LL	1	SL	1	NL	1	ELZ+X	1	DL	.8	EPL	.5				
24	Dead+Wind 240 de	Yes	Yes	1.3	LL	1	SL	1	NL	1	ELZ+Y	1	DL	.8	EPL	.5				
25	Dead+Wind 270 de	Yes	Yes	1.3	LL	1	SL	1	NL	1	WLX-R	1	DL	.8	EPL	.5				
26	Dead+Wind 300 de	Yes	Yes	1.3	LL	1	SL	1	NL	1	ELX-Y	1	DL	.8	EPL	.5				
27	Dead+Wind 330 de	Yes	Yes	1.3	LL	1	SL	1	NL	1	ELX-Z	1	DL	.8	EPL	.5				
28	Dead Only	Yes	Yes		LL	1							DL	.667	EPL	.667				
29	Dead+Wind 0 deg -	Yes	Yes	1.3	LL	1	WL-Z	1					DL	.667	EPL	.667				
30	Dead+Wind 30 deg	Yes	Yes	1.3	LL	1	OL1	1					DL	.667	EPL	.667				
31	Dead+Wind 60 deg	Yes	Yes	1.3	LL	1	OL2	1					DL	.667	EPL	.667				
32	Dead+Wind 90 deg	Yes	Yes	1.3	LL	1	WL+X	1					DL	.667	EPL	.667				
33	Dead+Wind 120 de	Yes	Yes	1.3	LL	1	OL3	1					DL	.667	EPL	.667				
34	Dead+Wind 150 de	Yes	Yes	1.3	LL	1	OL4	1					DL	.667	EPL	.667				
35	Dead+Wind 180 de	Yes	Yes	1.3	LL	1	WL+Z	1					DL	.667	EPL	.667				
36	Dead+Wind 210 de	Yes	Yes	1.3	LL	1	OL5	1					DL	.667	EPL	.667				
37	Dead+Wind 240 de	Yes	Yes	1.3	LL	1	OL6	1					DL	.667	EPL	.667				
38	Dead+Wind 270 de	Yes	Yes	1.3	LL	1	WL-X	1					DL	.667	EPL	.667				
39	Dead+Wind 300 de	Yes	Yes	1.3	LL	1	OL7	1					DL	.667	EPL	.667				
40	Dead+Wind 330 de	Yes	Yes	1.3	LL	1	OL8	1					DL	.667	EPL	.667				
41	Dead+Ice+Temp	Yes	Yes		LL	1	SL	1	NL	1			DL	.667	EPL	.667				
42	Dead+Wind 0 deg+	Yes	Yes	1.3	LL	1	SL	1	NL	1	WLZ-R	1	DL	.667	EPL	.667				
43	Dead+Wind 30 deg	Yes	Yes	1.3	LL	1	SL	1	NL	1	ELZ-X	1	DL	.667	EPL	.667				
44	Dead+Wind 60 deg	Yes	Yes	1.3	LL	1	SL	1	NL	1	ELZ-Y	1	DL	.667	EPL	.667				
45	Dead+Wind 90 deg	Yes	Yes	1.3	LL	1	SL	1	NL	1	WLX+R	1	DL	.667	EPL	.667				
46	Dead+Wind 120 de	Yes	Yes	1.3	LL	1	SL	1	NL	1	ELX+Y	1	DL	.667	EPL	.667				
47	Dead+Wind 150 de	Yes	Yes	1.3	LL	1	SL	1	NL	1	ELX+Z	1	DL	.667	EPL	.667				
48	Dead+Wind 180 de	Yes	Yes	1.3	LL	1	SL	1	NL	1	WLZ+R	1	DL	.667	EPL	.667				
49	Dead+Wind 210 de	Yes	Yes	1.3	LL	1	SL	1	NL	1	ELZ+X	1	DL	.667	EPL	.667				
50	Dead+Wind 240 de	Yes	Yes	1.3	LL	1	SL	1	NL	1	ELZ+Y	1	DL	.667	EPL	.667				
51	Dead+Wind 270 de	Yes	Yes	1.3	LL	1	SL	1	NL	1	WLX-R	1	DL	.667	EPL	.667				
52	Dead+Wind 300 de	Yes	Yes	1.3	LL	1	SL	1	NL	1	ELX-Y	1	DL	.667	EPL	.667				
53	Dead+Wind 330 de	Yes	Yes	1.3	LL	1	SL	1	NL	1	ELX-Z	1	DL	.667	EPL	.667				
54																				
55	** STRENGTH DE...																			
56	1.4D	Yes			LL	1.4							DL	1.4	EPL	1.4				
57	1.2D+1.6Wind0	Yes			LL	1.2	WL-Z	1.6					DL	1.2	EPL	1.2				
58	1.2D+1.6Wind30	Yes			LL	1.2	OL1	1.6					DL	1.2	EPL	1.2				
59	1.2D+1.6Wind60	Yes			LL	1.2	OL2	1.6					DL	1.2	EPL	1.2				
60	1.2D+1.6Wind90	Yes			LL	1.2	WL+X	1.6					DL	1.2	EPL	1.2				
61	1.2D+1.6Wind120	Yes			LL	1.2	OL3	1.6					DL	1.2	EPL	1.2				
62	1.2D+1.6Wind150	Yes			LL	1.2	OL4	1.6					DL	1.2	EPL	1.2				
63	1.2D+1.6Wind180	Yes			LL	1.2	WL+Z	1.6					DL	1.2	EPL	1.2				
64	1.2D+1.6Wind210	Yes			LL	1.2	OL5	1.6					DL	1.2	EPL	1.2				
65	1.2D+1.6Wind240	Yes			LL	1.2	OL6	1.6					DL	1.2	EPL	1.2				
66	1.2D+1.6Wind270	Yes			LL	1.2	WL-X	1.6					DL	1.2	EPL	1.2				
67	1.2D+1.6Wind300	Yes			LL	1.2	OL7	1.6					DL	1.2	EPL	1.2				
68	1.2D+1.6Wind330	Yes			LL	1.2	OL8	1.6					DL	1.2	EPL	1.2				
69	0.9D+1.6Wind0	Yes			LL	.9	WL-Z	1.6					DL	.9	EPL	.9				
70	0.9D+1.6Wind30	Yes			LL	.9	OL1	1.6					DL	.9	EPL	.9				
71	0.9D+1.6Wind60	Yes			LL	.9	OL2	1.6					DL	.9	EPL	.9				



**Load Combinations (Continued)**

Label	Sol.	Se.	AB	SF	Cate	F	Cate	F	Cate	F	Cate	F	Cate	Fa	Cate	Fa	Cate	Factor	Cate	Factor
72	0.9D+1.6Wind90	Yes			LL	.9	WL+X	1.6						DL	.9	EPL	.9			
73	0.9D+1.6Wind120	Yes			LL	.9	OL3	1.6						DL	.9	EPL	.9			
74	0.9D+1.6Wind150	Yes			LL	.9	OL4	1.6						DL	.9	EPL	.9			
75	0.9D+1.6Wind180	Yes			LL	.9	WL+Z	1.6						DL	.9	EPL	.9			
76	0.9D+1.6Wind210	Yes			LL	.9	OL5	1.6						DL	.9	EPL	.9			
77	0.9D+1.6Wind240	Yes			LL	.9	OL6	1.6						DL	.9	EPL	.9			
78	0.9D+1.6Wind270	Yes			LL	.9	WL-X	1.6						DL	.9	EPL	.9			
79	0.9D+1.6Wind300	Yes			LL	.9	OL7	1.6						DL	.9	EPL	.9			
80	0.9D+1.6Wind330	Yes			LL	.9	OL8	1.6						DL	.9	EPL	.9			
81	1.2D+1.6Wind0 (w/...	Yes			LL	1.2	SL	1	NL	1	WLZ-R	1		DL	1.2	EPL	1.2			
82	1.2D+1.6Wind30 (w...	Yes			LL	1.2	SL	1	NL	1	ELZ-X	1		DL	1.2	EPL	1.2			
83	1.2D+1.6Wind60 (w...	Yes			LL	1.2	SL	1	NL	1	ELZ-Y	1		DL	1.2	EPL	1.2			
84	1.2D+1.6Wind90 (w...	Yes			LL	1.2	SL	1	NL	1	WLX+R	1		DL	1.2	EPL	1.2			
85	1.2D+1.6Wind120 (...)	Yes			LL	1.2	SL	1	NL	1	ELX+Y	1		DL	1.2	EPL	1.2			
86	1.2D+1.6Wind150 (...)	Yes			LL	1.2	SL	1	NL	1	ELX+Z	1		DL	1.2	EPL	1.2			
87	1.2D+1.6Wind180 (...)	Yes			LL	1.2	SL	1	NL	1	WLZ+R	1		DL	1.2	EPL	1.2			
88	1.2D+1.6Wind210 (...)	Yes			LL	1.2	SL	1	NL	1	ELZ+X	1		DL	1.2	EPL	1.2			
89	1.2D+1.6Wind240 (...)	Yes			LL	1.2	SL	1	NL	1	ELZ+Y	1		DL	1.2	EPL	1.2			
90	1.2D+1.6Wind270 (...)	Yes			LL	1.2	SL	1	NL	1	WLX-R	1		DL	1.2	EPL	1.2			
91	1.2D+1.6Wind300 (...)	Yes			LL	1.2	SL	1	NL	1	ELX-Y	1		DL	1.2	EPL	1.2			
92	1.2D+1.6Wind330 (...)	Yes			LL	1.2	SL	1	NL	1	ELX-Z	1		DL	1.2	EPL	1.2			

**Point Loads and Moments (Cat 2 : LL)**

Label	Direction	Magnitude[k, k-ft]	
1	R3D_N172	X	-1.247
2	R3D_N172	Y	19.084
3	R3D_N172	Z	.728
4	R3D_N173	X	1.24
5	R3D_N173	Y	18.358
6	R3D_N173	Z	.715
7	R3D_N174	X	.008
8	R3D_N174	Y	19.034
9	R3D_N174	Z	-1.443

**Point Loads and Moments (Cat 5 : SL)**

Label	Direction	Magnitude[k, k-ft]	
1	R3D_N172	X	-.682
2	R3D_N172	Y	11.136
3	R3D_N172	Z	.41
4	R3D_N173	X	.669
5	R3D_N173	Y	9.947
6	R3D_N173	Z	.388
7	R3D_N174	X	.013
8	R3D_N174	Y	11.258
9	R3D_N174	Z	-.797

**Point Loads and Moments (Cat 16 : OL1)**

Label	Direction	Magnitude[k, k-ft]	
1	R3D_N172	X	23.19
2	R3D_N172	Y	-276.889
3	R3D_N172	Z	-15.454
4	R3D_N172	MY	-.014
5	R3D_N173	X	1.459
6	R3D_N173	Y	.195
7	R3D_N173	Z	-2.503



**Point Loads and Moments (Cat 16 : OL1) (Continued)**

	Label	Direction	Magnitude[k, k-ft]
8	R3D_N173	MY	.027
9	R3D_N174	X	1.787
10	R3D_N174	Y	276.693
11	R3D_N174	Z	-27.799
12	R3D_N174	MY	-.014

**Point Loads and Moments (Cat 17 : OL2)**

	Label	Direction	Magnitude[k, k-ft]
1	R3D_N172	X	27.158
2	R3D_N172	Y	-315.031
3	R3D_N172	Z	-15.917
4	R3D_N172	MY	-.000326
5	R3D_N173	X	14.806
6	R3D_N173	Y	157.059
7	R3D_N173	Z	5.765
8	R3D_N173	MY	.024
9	R3D_N174	X	2.82
10	R3D_N174	Y	157.972
11	R3D_N174	Z	-15.773
12	R3D_N174	MY	-.024

**Point Loads and Moments (Cat 18 : OL3)**

	Label	Direction	Magnitude[k, k-ft]
1	R3D_N172	X	16.171
2	R3D_N172	Y	-166.38
3	R3D_N172	Z	-5.941
4	R3D_N172	MY	.023
5	R3D_N173	X	29.339
6	R3D_N173	Y	332.037
7	R3D_N173	Z	16.977
8	R3D_N173	MY	.000342
9	R3D_N174	X	3.006
10	R3D_N174	Y	-165.657
11	R3D_N174	Z	16.922
12	R3D_N174	MY	-.023

**Point Loads and Moments (Cat 19 : OL4)**

	Label	Direction	Magnitude[k, k-ft]
1	R3D_N172	X	1.578
2	R3D_N172	Y	.436
3	R3D_N172	Z	2.796
4	R3D_N172	MY	.027
5	R3D_N173	X	23.262
6	R3D_N173	Y	275.497
7	R3D_N173	Z	15.134
8	R3D_N173	MY	-.013
9	R3D_N174	X	1.475
10	R3D_N174	Y	-275.933
11	R3D_N174	Z	27.744
12	R3D_N174	MY	-.013

**Point Loads and Moments (Cat 20 : OL5)**

	Label	Direction	Magnitude[k, k-ft]
1	R3D_N172	X	-23.207
2	R3D_N172	Y	277.111



**Point Loads and Moments (Cat 20 : OL5) (Continued)**

	Label	Direction	Magnitude[k, k-ft]
3	R3D_N172	Z	15.462
4	R3D_N172	MY	.014
5	R3D_N173	X	-1.491
6	R3D_N173	Y	-.639
7	R3D_N173	Z	2.484
8	R3D_N173	MY	-.027
9	R3D_N174	X	-1.789
10	R3D_N174	Y	-276.471
11	R3D_N174	Z	27.78
12	R3D_N174	MY	.014

**Point Loads and Moments (Cat 21 : OL6)**

	Label	Direction	Magnitude[k, k-ft]
1	R3D_N172	X	-29.338
2	R3D_N172	Y	333.497
3	R3D_N172	Z	17.193
4	R3D_N172	MY	.000299
5	R3D_N173	X	-16.086
6	R3D_N173	Y	-166.5
7	R3D_N173	Z	-6.109
8	R3D_N173	MY	-.024
9	R3D_N174	X	-3.195
10	R3D_N174	Y	-166.997
11	R3D_N174	Z	17.018
12	R3D_N174	MY	.024

**Point Loads and Moments (Cat 22 : OL7)**

	Label	Direction	Magnitude[k, k-ft]
1	R3D_N172	X	-14.925
2	R3D_N172	Y	157.479
3	R3D_N172	Z	5.631
4	R3D_N172	MY	-.023
5	R3D_N173	X	-27.203
6	R3D_N173	Y	-314.262
7	R3D_N173	Z	-15.742
8	R3D_N173	MY	-.000364
9	R3D_N174	X	-2.65
10	R3D_N174	Y	156.784
11	R3D_N174	Z	-15.689
12	R3D_N174	MY	.023

**Point Loads and Moments (Cat 23 : OL8)**

	Label	Direction	Magnitude[k, k-ft]
1	R3D_N172	X	-1.578
2	R3D_N172	Y	-.431
3	R3D_N172	Z	-2.796
4	R3D_N172	MY	-.027
5	R3D_N173	X	-23.29
6	R3D_N173	Y	-275.902
7	R3D_N173	Z	-15.154
8	R3D_N173	MY	.013
9	R3D_N174	X	-1.479
10	R3D_N174	Y	276.333
11	R3D_N174	Z	-27.778
12	R3D_N174	MY	.013



**Point Loads and Moments (Cat 32 : WL+X)**

	Label	Direction	Magnitude[k, k-ft]
1	R3D_N172	X	24.794
2	R3D_N172	Y	-276.768
3	R3D_N172	Z	-12.667
4	R3D_N172	MY	.013
5	R3D_N173	X	24.74
6	R3D_N173	Y	275.915
7	R3D_N173	Z	12.636
8	R3D_N173	MY	.014
9	R3D_N174	X	3.26
10	R3D_N174	Y	.853
11	R3D_N174	Z	-.062
12	R3D_N174	MY	-.027

**Point Loads and Moments (Cat 34 : WL+Z)**

	Label	Direction	Magnitude[k, k-ft]
1	R3D_N172	X	-12.264
2	R3D_N172	Y	157.972
3	R3D_N172	Z	10.305
4	R3D_N172	MY	.023
5	R3D_N173	X	12.336
6	R3D_N173	Y	156.336
7	R3D_N173	Z	9.938
8	R3D_N173	MY	-.023
9	R3D_N174	X	-.178
10	R3D_N174	Y	-314.308
11	R3D_N174	Z	31.425
12	R3D_N174	MY	.000699

**Point Loads and Moments (Cat 35 : WL-X)**

	Label	Direction	Magnitude[k, k-ft]
1	R3D_N172	X	-24.824
2	R3D_N172	Y	277.168
3	R3D_N172	Z	12.681
4	R3D_N172	MY	-.013
5	R3D_N173	X	-24.771
6	R3D_N173	Y	-276.32
7	R3D_N173	Z	-12.65
8	R3D_N173	MY	-.014
9	R3D_N174	X	-3.259
10	R3D_N174	Y	-.848
11	R3D_N174	Z	.062
12	R3D_N174	MY	.027

**Point Loads and Moments (Cat 37 : WL-Z)**

	Label	Direction	Magnitude[k, k-ft]
1	R3D_N172	X	13.155
2	R3D_N172	Y	-166.997
3	R3D_N172	Z	-11.251
4	R3D_N172	MY	-.023
5	R3D_N173	X	-13.273
6	R3D_N173	Y	-165.777
7	R3D_N173	Z	-10.874
8	R3D_N173	MY	.023
9	R3D_N174	X	.192
10	R3D_N174	Y	332.774



**Point Loads and Moments (Cat 37 : WL-Z) (Continued)**

	Label	Direction	Magnitude[k, k-ft]
11	R3D_N174	Z	-33.95
12	R3D_N174	MY	-.000649

**Point Loads and Moments (Cat 42 : ELX+Z)**

	Label	Direction	Magnitude[k, k-ft]
1	R3D_N172	X	1.593
2	R3D_N172	Y	.335
3	R3D_N172	Z	2.807
4	R3D_N172	MY	.024
5	R3D_N173	X	22.975
6	R3D_N173	Y	271.434
7	R3D_N173	Z	14.907
8	R3D_N173	MY	-.012
9	R3D_N174	X	1.422
10	R3D_N174	Y	-271.769
11	R3D_N174	Z	27.374
12	R3D_N174	MY	-.011

**Point Loads and Moments (Cat 43 : ELX-Z)**

	Label	Direction	Magnitude[k, k-ft]
1	R3D_N172	X	-1.593
2	R3D_N172	Y	-.331
3	R3D_N172	Z	-2.807
4	R3D_N172	MY	-.024
5	R3D_N173	X	-22.997
6	R3D_N173	Y	-271.755
7	R3D_N173	Z	-14.922
8	R3D_N173	MY	.012
9	R3D_N174	X	-1.425
10	R3D_N174	Y	272.087
11	R3D_N174	Z	-27.401
12	R3D_N174	MY	.011

**Point Loads and Moments (Cat 44 : ELZ+X)**

	Label	Direction	Magnitude[k, k-ft]
1	R3D_N172	X	-22.859
2	R3D_N172	Y	272.675
3	R3D_N172	Z	15.286
4	R3D_N172	MY	.012
5	R3D_N173	X	-1.453
6	R3D_N173	Y	-.498
7	R3D_N173	Z	2.44
8	R3D_N173	MY	-.024
9	R3D_N174	X	-1.81
10	R3D_N174	Y	-272.177
11	R3D_N174	Z	27.401
12	R3D_N174	MY	.013

**Point Loads and Moments (Cat 45 : ELZ-X)**

	Label	Direction	Magnitude[k, k-ft]
1	R3D_N172	X	22.846
2	R3D_N172	Y	-272.499
3	R3D_N172	Z	-15.28
4	R3D_N172	MY	-.012
5	R3D_N173	X	1.428



**Point Loads and Moments (Cat 45 : ELZ-X) (Continued)**

	Label	Direction	Magnitude[k, k-ft]
6	R3D_N173	Y	.146
7	R3D_N173	Z	-2.455
8	R3D_N173	MY	.024
9	R3D_N174	X	1.809
10	R3D_N174	Y	272.353
11	R3D_N174	Z	-27.416
12	R3D_N174	MY	-.013

**Point Loads and Moments (Cat 48 : ELX+Y)**

	Label	Direction	Magnitude[k, k-ft]
1	R3D_N172	X	16.571
2	R3D_N172	Y	-169.326
3	R3D_N172	Z	-6.011
4	R3D_N172	MY	.02
5	R3D_N173	X	30.028
6	R3D_N173	Y	338.094
7	R3D_N173	Z	17.333
8	R3D_N173	MY	.000332
9	R3D_N174	X	3.075
10	R3D_N174	Y	-168.768
11	R3D_N174	Z	17.316
12	R3D_N174	MY	-.02

**Point Loads and Moments (Cat 49 : ELX-Y)**

	Label	Direction	Magnitude[k, k-ft]
1	R3D_N172	X	-14.545
2	R3D_N172	Y	153.199
3	R3D_N172	Z	5.449
4	R3D_N172	MY	-.02
5	R3D_N173	X	-26.501
6	R3D_N173	Y	-305.84
7	R3D_N173	Z	-15.302
8	R3D_N173	MY	-.000351
9	R3D_N174	X	-2.556
10	R3D_N174	Y	152.641
11	R3D_N174	Z	-15.28
12	R3D_N174	MY	.02

**Point Loads and Moments (Cat 54 : ELZ+Y)**

	Label	Direction	Magnitude[k, k-ft]
1	R3D_N172	X	-29.975
2	R3D_N172	Y	339.219
3	R3D_N172	Z	17.59
4	R3D_N172	MY	.00036
5	R3D_N173	X	-16.454
6	R3D_N173	Y	-169.421
7	R3D_N173	Z	-6.23
8	R3D_N173	MY	-.021
9	R3D_N174	X	-3.324
10	R3D_N174	Y	-169.798
11	R3D_N174	Z	17.39
12	R3D_N174	MY	.021

**Point Loads and Moments (Cat 55 : ELZ-Y)**

	Label	Direction	Magnitude[k, k-ft]
--	-------	-----------	--------------------





**Point Loads and Moments (Cat 55 : ELZ-Y) (Continued)**

	Label	Direction	Magnitude[k, k-ft]
1	R3D_N172	X	26.423
2	R3D_N172	Y	-306.395
3	R3D_N172	Z	-15.506
4	R3D_N172	MY	-.000377
5	R3D_N173	X	14.411
6	R3D_N173	Y	152.844
7	R3D_N173	Z	5.622
8	R3D_N173	MY	.021
9	R3D_N174	X	2.77
10	R3D_N174	Y	153.551
11	R3D_N174	Z	-15.344
12	R3D_N174	MY	-.021

**Point Loads and Moments (Cat 59 : NL)**

	Label	Direction	Magnitude[k, k-ft]
1	R3D_N172	X	4.606
2	R3D_N172	Z	-2.659
3	R3D_N173	X	-4.606
4	R3D_N173	Z	-2.659
5	R3D_N174	Z	5.318

**Point Loads and Moments (Cat 60 : WLX+R)**

	Label	Direction	Magnitude[k, k-ft]
1	R3D_N172	X	24.459
2	R3D_N172	Y	-272.414
3	R3D_N172	Z	-12.48
4	R3D_N172	MY	.012
5	R3D_N173	X	24.417
6	R3D_N173	Y	271.756
7	R3D_N173	Z	12.455
8	R3D_N173	MY	.012
9	R3D_N174	X	3.228
10	R3D_N174	Y	.657
11	R3D_N174	Z	-.048
12	R3D_N174	MY	-.024

**Point Loads and Moments (Cat 62 : WLZ+R)**

	Label	Direction	Magnitude[k, k-ft]
1	R3D_N172	X	-11.904
2	R3D_N172	Y	153.551
3	R3D_N172	Z	10.069
4	R3D_N172	MY	.021
5	R3D_N173	X	12.038
6	R3D_N173	Y	152.286
7	R3D_N173	Z	9.65
8	R3D_N173	MY	-.02
9	R3D_N174	X	-.216
10	R3D_N174	Y	-305.837
11	R3D_N174	Z	30.595
12	R3D_N174	MY	.000734

**Point Loads and Moments (Cat 63 : WLX-R)**

	Label	Direction	Magnitude[k, k-ft]
1	R3D_N172	X	-24.483
2	R3D_N172	Y	272.731



**Point Loads and Moments (Cat 63 : WLX-R) (Continued)**

	Label	Direction	Magnitude[k, k-ft]
3	R3D_N172	Z	12.491
4	R3D_N172	MY	-.012
5	R3D_N173	X	-24.442
6	R3D_N173	Y	-272.077
7	R3D_N173	Z	-12.467
8	R3D_N173	MY	-.012
9	R3D_N174	X	-3.228
10	R3D_N174	Y	-.654
11	R3D_N174	Z	.048
12	R3D_N174	MY	.024

**Point Loads and Moments (Cat 65 : WLZ-R)**

	Label	Direction	Magnitude[k, k-ft]
1	R3D_N172	X	13.397
2	R3D_N172	Y	-169.798
3	R3D_N172	Z	-11.575
4	R3D_N172	MY	-.021
5	R3D_N173	X	-13.588
6	R3D_N173	Y	-168.863
7	R3D_N173	Z	-11.112
8	R3D_N173	MY	.021
9	R3D_N174	X	.248
10	R3D_N174	Y	338.66
11	R3D_N174	Z	-34.713
12	R3D_N174	MY	-.000698

**Area Loads (Cat 14 : EPL)**

	Label	Base Mag[ksf]	Peak Mag[ksf]
1	AL1	0	0

**Design Strips**

	Label	Rebar Angle from P...	No. of Design Cuts	Design Rule
1	DS1	0	50	Typical
2	DS2	90	50	Typical

**Slab Soil Pressures**

	LC	Label	UC	Soil Pressure[ksf]	Allowable Bearing[ksf]	Point
1	2	S1	.109	.724	6.625	N218
2	3	S1	.283	2.498	8.831	N230
3	4	S1	.333	2.943	8.831	N6
4	5	S1	.327	2.89	8.831	N6
5	6	S1	.264	2.328	8.831	N957
6	7	S1	.358	3.165	8.831	N7
7	8	S1	.337	2.98	8.831	N7
8	9	S1	.256	2.263	8.831	N8
9	10	S1	.34	3.007	8.831	N8
10	11	S1	.362	3.198	8.831	N8
11	12	S1	.266	2.346	8.831	N764
12	13	S1	.327	2.886	8.831	N5
13	14	S1	.333	2.938	8.831	N5
14	15	S1	.115	.762	6.625	N218
15	16	S1	.285	2.515	8.831	N230
16	17	S1	.319	2.817	8.831	N6
17	18	S1	.308	2.724	8.831	N6
18	19	S1	.255	2.25	8.831	N899



**Slab Soil Pressures (Continued)**

LC	Label	UC	Soil Pressure[ksf]	Allowable Bearing[ksf]	Point	
19	20	S1	.358	3.164	N7	
20	21	S1	.323	2.857	N7	
21	22	S1	.245	2.159	N8	
22	23	S1	.327	2.886	N8	
23	24	S1	.363	3.204	N8	
24	25	S1	.258	2.276	N764	
25	26	S1	.31	2.735	N5	
26	27	S1	.32	2.827	N5	
27	28	S1	.093	.614	6.625	N218
28	29	S1	.33	2.912	8.831	N230
29	30	S1	.378	3.34	8.831	N6
30	31	S1	.37	3.264	8.831	N6
31	32	S1	.295	2.609	8.831	N824
32	33	S1	.413	3.649	8.831	N7
33	34	S1	.38	3.359	8.831	N7
34	35	S1	.287	2.534	8.831	N8
35	36	S1	.385	3.397	8.831	N8
36	37	S1	.419	3.702	8.831	N8
37	38	S1	.299	2.638	8.831	N923
38	39	S1	.369	3.26	8.831	N5
39	40	S1	.377	3.333	8.831	N5
40	41	S1	.098	.652	6.625	N218
41	42	S1	.32	2.829	8.831	N230
42	43	S1	.348	3.076	8.831	N6
43	44	S1	.334	2.948	8.831	N6
44	45	S1	.272	2.399	8.831	N957
45	46	S1	.402	3.547	8.831	N7
46	47	S1	.351	3.096	8.831	N7
47	48	S1	.26	2.293	8.831	N8
48	49	S1	.355	3.136	8.831	N8
49	50	S1	.409	3.61	8.831	N8
50	51	S1	.276	2.437	8.831	N923
51	52	S1	.336	2.966	8.831	N5
52	53	S1	.35	3.088	8.831	N5

**Pedestals/Posts Design Values**

Label	UC	Gov LC	Shear UC	Dir	Phi Used	Vertical Reinf	Shear Reinf
1 R3D_N172	NC	NC	NC	NC	NC	NC	NC
2 R3D_N173	NC	NC	NC	NC	NC	NC	NC
3 R3D_N174	NC	NC	NC	NC	NC	NC	NC

**Pedestals/Posts Punching Shear Values**

Label	UC	Gov LC	Location	Vuy[k]	Muz[k-ft]	Mux[k-ft]	Total Stress[...]	Phi*Vny[ksi]
1 R3D_N172	.168	65	EDGE	394.209	133.2	78.051	.028	.164
2 R3D_N173	.168	61	EDGE	392.625	-133.185	77.057	.028	.164
3 R3D_N174	.238	57	EDGE	419.288	-.87	-154.143	.039	.164

**Pedestals/Posts Punching Shear Geometries**

Label	Shape	Location	Effective De...	L1[in]	L2[in]	Polar Mome...	Polar Mome...	Gamma-x	Gamma-z
1 R3D_N172	CRND42	EDGE	62.365	95.352	104.676	3.61095e+7	2.7345e+7	.389	.411
2 R3D_N173	CRND42	EDGE	62.365	95.352	104.676	3.61095e+7	2.7345e+7	.389	.411
3 R3D_N174	CRND42	EDGE	62.365	85.184	95.352	1.6785e+7	3.05833e+7	.387	.414



Company : Ramaker & Associates  
 Designer : A. Kraus  
 Job Number : 28737  
 Model Name : Transfer Station (CT33XC522)

Oct 13, 2014

Checked By: \_\_\_\_\_

### Strip Reinforcing

	Label	UC Top	Top Bars	Governing Desig...	UC Bot	Bot Bars/... Governin...	UC Shear Governin...
1	DS1	.058	#10@6.4in	DS1-X36	.192	#10@6.4in DS1-X34	.305 DS1-X40
2	DS2	.131	#10@6.4in	DS2-X26	.139	#10@6.4in DS2-X26	.251 DS2-X7

### Slab Overturning Safety Factors

	LC	Slab	Mo-XX[k-ft]	Ms-XX[k-ft]	Mo-ZZ[k-ft]	Ms-ZZ[k-ft]	Ms-XX/Mo-XX	Ms-ZZ/Mo-ZZ
1	2	S1	0	10220.43	0	10231.843	9.999+	9.999+
2	3	S1	6360.427	10220.43	13.217	10231.843	1.607	9.999+
3	4	S1	5283.75	10220.43	3054.785	10231.843	1.934	3.349
4	5	S1	3015.557	10220.43	5203.254	10231.843	3.389	1.966
5	6	S1	16.027	10220.43	6093.53	10231.843	9.999+	1.679
6	7	S1	3166.493	10228.02	5500.212	10231.843	3.23	1.86
7	8	S1	5269.473	10228.02	3032.88	10231.843	1.941	3.374
8	9	S1	6000.338	10228.02	17.756	10216.608	1.705	9.999+
9	10	S1	5279.553	10228.02	3062.055	10216.608	1.937	3.337
10	11	S1	3191.664	10228.02	5517.374	10216.608	3.205	1.852
11	12	S1	15.941	10228.02	6102.319	10216.608	9.999+	1.674
12	13	S1	2993.259	10220.43	5199.555	10216.608	3.414	1.965
13	14	S1	5277.042	10220.43	3037.348	10216.608	1.937	3.364
14	15	S1	0	10704.945	0	10737.531	9.999+	9.999+
15	16	S1	6474.759	10704.945	10.129	10737.531	1.653	9.999+
16	17	S1	5201.49	10704.945	3006.226	10737.531	2.058	3.572
17	18	S1	2931.308	10704.945	5061.834	10737.531	3.652	2.121
18	19	S1	12.351	10704.945	6000.354	10737.531	9.999+	1.789
19	20	S1	3226.821	10729.902	5601.113	10737.531	3.325	1.917
20	21	S1	5190.527	10729.902	2989.484	10737.531	2.067	3.592
21	22	S1	5838.841	10729.902	13.727	10697.317	1.838	9.999+
22	23	S1	5198.164	10729.902	3011.987	10697.317	2.064	3.552
23	24	S1	3246.162	10729.902	5614.368	10697.317	3.305	1.905
24	25	S1	12.284	10729.902	6007.319	10697.317	9.999+	1.781
25	26	S1	2914.244	10704.945	5059.714	10697.317	3.673	2.114
26	27	S1	5196.525	10704.945	2993.024	10697.317	2.06	3.574
27	28	S1	0	8659.94	0	8671.352	9.999+	9.999+
28	29	S1	6360.427	8659.94	13.217	8671.352	1.362	9.999+
29	30	S1	5283.75	8659.94	3054.785	8671.352	1.639	2.839
30	31	S1	3015.557	8659.94	5203.254	8671.352	2.872	1.667
31	32	S1	16.027	8659.94	6093.53	8671.352	9.999+	1.423
32	33	S1	3166.493	8667.53	5500.212	8671.352	2.737	1.577
33	34	S1	5269.473	8667.53	3032.88	8671.352	1.645	2.859
34	35	S1	6000.338	8667.53	17.756	8656.117	1.445	9.999+
35	36	S1	5279.553	8667.53	3062.055	8656.117	1.642	2.827
36	37	S1	3191.664	8667.53	5517.374	8656.117	2.716	1.569
37	38	S1	15.941	8667.53	6102.319	8656.117	9.999+	1.418
38	39	S1	2993.259	8659.94	5199.555	8656.117	2.893	1.665
39	40	S1	5277.042	8659.94	3037.348	8656.117	1.641	2.85
40	41	S1	0	9144.455	0	9177.041	9.999+	9.999+
41	42	S1	6474.759	9144.455	10.129	9177.041	1.412	9.999+
42	43	S1	5201.49	9144.455	3006.226	9177.041	1.758	3.053
43	44	S1	2931.308	9144.455	5061.834	9177.041	3.12	1.813
44	45	S1	12.351	9144.455	6000.354	9177.041	9.999+	1.529
45	46	S1	3226.821	9169.412	5601.113	9177.041	2.842	1.638
46	47	S1	5190.527	9169.412	2989.484	9177.041	1.767	3.07
47	48	S1	5838.841	9169.412	13.727	9136.826	1.57	9.999+
48	49	S1	5198.164	9169.412	3011.987	9136.826	1.764	3.033
49	50	S1	3246.162	9169.412	5614.368	9136.826	2.825	1.627
50	51	S1	12.284	9169.412	6007.319	9136.826	9.999+	1.521
51	52	S1	2914.244	9144.455	5059.714	9136.826	3.138	1.806



Company : Ramaker & Associates  
 Designer : A. Kraus  
 Job Number : 28737  
 Model Name : Transfer Station (CT33XC522)

Oct 13, 2014

Checked By: \_\_\_\_\_

**Slab Overturning Safety Factors (Continued)**

LC	Slab	Mo-XX[k-ft]	Ms-XX[k-ft]	Mo-ZZ[k-ft]	Ms-ZZ[k-ft]	Ms-XX/Mo-XX	Ms-ZZ/Mo-ZZ	
52	53	S1	5196.525	9144.455	2993.024	9136.826	1.76	3.053

**Slab Sliding Safety Factors**

LC	Slab	Va-XX[k]	Vr-XX[k]	Va-ZZ[k]	Vr-ZZ[k]	SR-XX	SR-ZZ	
1	2	S1	0	201.132	0	201.132	9.999+	9.999+
2	3	S1	.075	201.132	56.075	201.132	9.999+	3.587
3	4	S1	26.438	201.132	45.756	201.132	7.608	4.396
4	5	S1	44.786	201.132	25.926	201.132	4.491	7.758
5	6	S1	52.794	201.132	.094	201.132	3.81	9.999+
6	7	S1	48.517	201.132	27.958	201.132	4.146	7.194
7	8	S1	26.316	201.132	45.674	201.132	7.643	4.404
8	9	S1	.105	201.132	51.667	201.132	9.999+	3.893
9	10	S1	26.486	201.132	45.727	201.132	7.594	4.399
10	11	S1	48.617	201.132	28.102	201.132	4.137	7.157
11	12	S1	52.853	201.132	.093	201.132	3.805	9.999+
12	13	S1	44.776	201.132	25.801	201.132	4.492	7.795
13	14	S1	26.345	201.132	45.727	201.132	7.634	4.399
14	15	S1	0	210.835	0	210.835	9.999+	9.999+
15	16	S1	.058	210.835	57.4	210.835	9.999+	3.673
16	17	S1	26.083	210.835	45.151	210.835	8.083	4.67
17	18	S1	43.604	210.835	25.228	210.835	4.835	8.357
18	19	S1	52.105	210.835	.072	210.835	4.046	9.999+
19	20	S1	49.676	210.835	28.638	210.835	4.244	7.362
20	21	S1	25.99	210.835	45.088	210.835	8.112	4.676
21	22	S1	.081	210.835	50.313	210.835	9.999+	4.19
22	23	S1	26.121	210.835	45.127	210.835	8.071	4.672
23	24	S1	49.752	210.835	28.749	210.835	4.238	7.334
24	25	S1	52.151	210.835	.072	210.835	4.043	9.999+
25	26	S1	43.601	210.835	25.133	210.835	4.835	8.389
26	27	S1	26.013	210.835	45.13	210.835	8.105	4.672
27	28	S1	0	170.434	0	170.434	9.999+	9.999+
28	29	S1	.075	170.434	56.075	170.434	9.999+	3.039
29	30	S1	26.438	170.434	45.756	170.434	6.447	3.725
30	31	S1	44.786	170.434	25.926	170.434	3.806	6.574
31	32	S1	52.794	170.434	.094	170.434	3.228	9.999+
32	33	S1	48.517	170.434	27.958	170.434	3.513	6.096
33	34	S1	26.316	170.434	45.674	170.434	6.476	3.732
34	35	S1	.105	170.434	51.667	170.434	9.999+	3.299
35	36	S1	26.486	170.434	45.727	170.434	6.435	3.727
36	37	S1	48.617	170.434	28.102	170.434	3.506	6.065
37	38	S1	52.853	170.434	.093	170.434	3.225	9.999+
38	39	S1	44.776	170.434	25.801	170.434	3.806	6.606
39	40	S1	26.345	170.434	45.727	170.434	6.469	3.727
40	41	S1	0	180.136	0	180.136	9.999+	9.999+
41	42	S1	.058	180.136	57.4	180.136	9.999+	3.138
42	43	S1	26.083	180.136	45.151	180.136	6.906	3.99
43	44	S1	43.604	180.136	25.228	180.136	4.131	7.14
44	45	S1	52.105	180.136	.072	180.136	3.457	9.999+
45	46	S1	49.676	180.136	28.638	180.136	3.626	6.29
46	47	S1	25.99	180.136	45.088	180.136	6.931	3.995
47	48	S1	.081	180.136	50.313	180.136	9.999+	3.58
48	49	S1	26.121	180.136	45.127	180.136	6.896	3.992
49	50	S1	49.752	180.136	28.749	180.136	3.621	6.266
50	51	S1	52.151	180.136	.072	180.136	3.454	9.999+
51	52	S1	43.601	180.136	25.133	180.136	4.131	7.167
52	53	S1	26.013	180.136	45.13	180.136	6.925	3.992

**APPENDIX C**  
**MOUNT CALCULATIONS**

## Search Results

Latitude: 41.2444  
Longitude: -73.3634

**ASCE 7-10 Wind Speeds  
(3-sec peak gust MPH\*):**

**Risk Category I:** 109  
**Risk Category II:** 119  
**Risk Category III-IV:** 128  
**MRI\*\* 10 Year:** 76  
**MRI\*\* 25 Year:** 86  
**MRI\*\* 50 Year:** 91  
**MRI\*\* 100 Year:** 97

**ASCE 7-05:** 105  
**ASCE 7-93:** 80



\*MPH(Miles per hour)

\*\*MRI Mean Recurrence Interval (years)

Users should consult with local building officials  
to determine if there are community-specific wind speed  
requirements that govern.

### WIND SPEED WEB SITE DISCLAIMER:

While the information presented on this web site is believed to be correct, ATC assumes no responsibility or liability for its accuracy. The material presented in the wind speed report should not be used or relied upon for any specific application without competent examination and verification of its accuracy, suitability and applicability by engineers or other licensed professionals. ATC does not intend that the use of this information replace the sound judgment of such competent professionals, having experience and knowledge in the field of practice, nor to substitute for the standard of care required of such professionals in interpreting and applying the results of the wind speed report provided by this web site. Users of the information from this web site assume all liability arising from such use. Use of the output of this web site does not imply approval by the governing building code bodies responsible for building code approval and interpretation for the building site(s) described by latitude/longitude location in the wind speed report.



1120 Dallas Street  
 Sauk City, WI 53583  
 Office: (608) 643-4100

Job: 28737  
 Project: Transfer Station (CT33XC522-C)  
 By: JMO  
 Date: 8/29/2014

**Wind Load on Antennas TIA-222**

**2.6.9.6 Velocity Pressure**

$$q_z = 0.00256 K_z K_{zt} K_d V^2 I$$

Occupancy:	II	Classification of Structures (Table 2-1)
Exposure:	B	Exposure Category
V:	105 mph	Basic Wind Speed (Annex B)
z:	174 ft	Height above ground level to the center of the antenna
I:	1.00	Importance Factor (Table 2-3)
K <sub>z</sub> :	1.16	Velocity Pressure Coefficient (2.6.5.2)
K <sub>zt</sub> :	1	Topographic Factor (2.6.6.4)
K <sub>d</sub> :	0.95	Wind Direction Probability Factor (Table 2-2)

**q<sub>z</sub> = 31.0 psf**

G<sub>h</sub>: 1.00 Appurtenances and their Connections

**Mount & Antenna Wind Loads**

Appurtenance	Height	Width	h/D	Shape	C <sub>a</sub>	A <sub>f</sub>	F = q <sub>z</sub> G <sub>h</sub> C <sub>a</sub> A <sub>a</sub>	
Pipe2STD x 12 ft	144.0 in	2.4 in	60.5	Round	1.200	2.38 sf	<b>88.7 lb</b>	7.4 plf
Pipe3STD x 4.5 ft	54.0 in	3.5 in	15.4	Round	0.966	1.31 sf	<b>39.3 lb</b>	8.7 plf
HSS3X3X1/4 x 24 ft	288.0 in	3.0 in	96.0	Flat	2.000	6.00 sf	<b>372.5 lb</b>	15.5 plf
APXV9TM14-ALU-I20	56.3 in	12.6 in	4.5	Flat	1.287	4.93 sf	<b>196.9 lb</b>	
TD-RRH8x20-25	26.1 in	18.6 in	1.4	Flat	1.200	3.37 sf	<b>125.6 lb</b>	
APXVSPP18-C-A20	72.0 in	11.9 in	6.1	Flat	1.358	5.95 sf	<b>250.6 lb</b>	
1900MHz 4x40W RRH	25.1 in	11.1 in	2.3	Flat	1.200	1.93 sf	<b>72.1 lb</b>	
800MHz 2x50W RRH	19.0 in	13.0 in	1.5	Flat	1.200	1.72 sf	<b>63.9 lb</b>	





1120 Dallas Street  
 Sauk City, WI 53583  
 Office: (608) 643-4100

Job: 28737  
 Project: Transfer Station (CT33XC522-C)  
 By: JMO  
 Date: 8/29/2014

**Wind Load on Antennas TIA-222**

**2.6.9.6 Velocity Pressure**

$$q_z = 0.00256 K_z K_{zt} K_d V^2 I$$


Occupancy:	II	Classification of Structures (Table 2-1)
Exposure:	B	Exposure Category
V:	105 mph	Basic Wind Speed (Annex B)
z:	174 ft	Height above ground level to the center of the antenna
I:	1.00	Importance Factor (Table 2-3)
K <sub>z</sub> :	1.16	Velocity Pressure Coefficient (2.6.5.2)
K <sub>zt</sub> :	1	Topographic Factor (2.6.6.4)
K <sub>d</sub> :	0.95	Wind Direction Probability Factor (Table 2-2)

**q<sub>z</sub> = 31.0 psf**

G<sub>h</sub>: 1.00 Appurtenances and their Connections

**Mount & Antenna Wind Loads**

Appurtenance	Height	Depth	h/D	Shape	C <sub>a</sub>	A <sub>f</sub>	F = q <sub>z</sub> G <sub>h</sub> C <sub>a</sub> A <sub>a</sub>	
Pipe2STD x 12 ft	144.0 in	2.4 in	60.5	Round	1.200	2.38 sf	<b>88.7 lb</b>	7.4 plf
Pipe3STD x 4.5 ft	54.0 in	3.5 in	15.4	Round	0.966	1.31 sf	<b>39.3 lb</b>	8.7 plf
HSS3X3X1/4 x 24 ft	288.0 in	3.0 in	96.0	Flat	2.000	6.00 sf	<b>372.5 lb</b>	15.5 plf
APXV9TM14-ALU-I20	56.3 in	6.3 in	8.9	Flat	1.465	2.46 sf	<b>112.0 lb</b>	
TD-RRH8x20-25	26.1 in	6.7 in	3.9	Flat	1.262	1.21 sf	<b>47.6 lb</b>	
APXVSPP18-C-A20	72.0 in	7.0 in	10.3	Flat	1.509	3.50 sf	<b>164.2 lb</b>	
1900MHz 4x40W RRH	25.1 in	10.7 in	2.3	Flat	1.200	1.86 sf	<b>69.4 lb</b>	
800MHz 2x50W RRH	19.0 in	12.2 in	1.6	Flat	1.200	1.61 sf	<b>60.0 lb</b>	




Envelope Only Solution

Ramaker & Associates
JMO
28737

Transfer Station (CT33XC522-C)

SK - 1
Aug 29, 2014 at 8:05 AM
28737 Mount.r3d



Envelope Only Solution

Ramaker & Associates
JMO
28737

Transfer Station (CT33XC522-C)

SK - 2
Aug 29, 2014 at 8:06 AM
28737 Mount.r3d



### Hot Rolled Steel Properties

	Label	E [ksi]	G [ksi]	Nu	Therm (1/E...)	Density[k/ft...]	Yield[ksi]	Ry	Fu[ksi]	Rt
1	A36 Gr.36	29000	11154	.3	.65	.49	36	1.5	58	1.2
2	A572 Gr.50	29000	11154	.3	.65	.49	50	1.1	65	1.1
3	A992	29000	11154	.3	.65	.49	50	1.1	65	1.1
4	A500 Gr.42	29000	11154	.3	.65	.49	42	1.4	58	1.3
5	A500 Gr.46	29000	11154	.3	.65	.49	46	1.4	58	1.3
6	A53 Gr. B	29000	11154	.3	.65	.49	35	1.5	60	1.2

### Hot Rolled Steel Section Sets

	Label	Shape	Type	Design List	Material	Design R...	A [in2]	Iyy [in4]	Izz [in4]	J [in4]
1	pipe 2.0	PIPE 2.0	Beam	Pipe	A53 Gr. B	Typical	1.02	.627	.627	1.25
2	HSS3x3x1/4	HSS3x3x4	Beam	SquareTube	A36 Gr.36	Typical	2.44	3.02	3.02	5.08
3	pipe 3.0	PIPE_3.0	Beam	Pipe	A53 Gr. B	Typical	2.07	2.85	2.85	5.69

### Member Primary Data

	Label	I Joint	J Joint	K Joint	Rotate(deg)	Section/Shape	Type	Design List	Material	Design Rules
1	M1	N1	N2			pipe 2.0	Beam	Pipe	A53 Gr. B	Typical
2	M2	N11	N7			pipe 2.0	Beam	Pipe	A53 Gr. B	Typical
3	M5	N14	N10			pipe 2.0	Beam	Pipe	A53 Gr. B	Typical
4	M6	N15	N16			pipe 2.0	Beam	Pipe	A53 Gr. B	Typical
5	M9	N49	N50			pipe 3.0	Beam	Pipe	A53 Gr. B	Typical
6	M10	N48	N47			pipe 2.0	Beam	Pipe	A53 Gr. B	Typical
7	M11	N44	N46			HSS3x3x1/4	Beam	SquareTube	A36 Gr.36	Typical
8	M12	N43	N45			HSS3x3x1/4	Beam	SquareTube	A36 Gr.36	Typical
9	M13	N44	N22			RIGID	None	None	RIGID	Typical
10	M14	N43	N21			RIGID	None	None	RIGID	Typical
11	M13A	N31	N30			pipe 2.0	Beam	Pipe	A53 Gr. B	Typical
12	M4	N35A	N34			pipe 2.0	Beam	Pipe	A53 Gr. B	Typical
13	M13B	N36	N39			pipe 2.0	Beam	Pipe	A53 Gr. B	Typical

### Joint Coordinates and Temperatures

	Label	X [ft]	Y [ft]	Z [ft]	Temp [F]	Detach From Diap...
1	N1	.25	.25	0	0	
2	N2	12.25	.25	0	0	
3	N3	.5	.25	0	0	
4	N6	12	.25	0	0	
5	N7	.5	5.5	0	0	
6	N10	12	5.5	0	0	
7	N11	.5	-.5	0	0	
8	N14	12	-.5	0	0	
9	N15	.25	4.25	0	0	
10	N16	12.25	4.25	0	0	
11	N17	.5	4.25	0	0	
12	N20	12	4.25	0	0	
13	N21	6.25	.25	0	0	
14	N22	6.25	4.25	0	0	
15	N36	12	1.25	0	0	
16	N43	6.25	.25	-.25	0	
17	N44	6.25	4.25	-.25	0	
18	N45	6.25	.25	-2.25	0	
19	N46	6.25	4.25	-2.25	0	
20	N47	6.25	.25	-2.125	0	



**Joint Coordinates and Temperatures (Continued)**

	Label	X [ft]	Y [ft]	Z [ft]	Temp [F]	Detach From Diap...
21	N48	6.25	4.25	-2.125	0	
22	N49	6.25	4.5	-.25	0	
23	N50	6.25	0	-.25	0	
24	N29	4.25	.25	0	0	
25	N30	4.25	5.5	0	0	
26	N31	4.25	-.5	0	0	
27	N32	4.25	4.25	0	0	
28	N33	8.25	.25	0	0	
29	N34	8.25	5.5	0	0	
30	N35A	8.25	-.5	0	0	
31	N36A	8.25	4.25	0	0	
32	APXV9TM14-ALU-I20_TOP	12	5	0	0	
33	APXVSP18-C-A20_TOP	4.25	5	0	0	
34	APXV9TM14-ALU-I20_BOT	12	.5	0	0	
35	APXVSP18-C-A20_BOT	4.25	.5	0	0	
36	1900&800-RRH	8.25	3.25	0	0	
37	TD-RRH8X20	12	3.25	0	0	
38	N39	8.859438	1.25	-6.255947	0	

**Joint Boundary Conditions**

	Joint Label	X [k/in]	Y [k/in]	Z [k/in]	X Rot.[k-ft/rad]	Y Rot.[k-ft/rad]	Z Rot.[k-ft/rad]	Footing
1	N46	Reaction	Reaction	Reaction		Reaction	Reaction	
2	N45	Reaction	Reaction	Reaction		Reaction	Reaction	
3	N39	Reaction	Reaction	Reaction				

**Joint Loads and Enforced Displacements (BLC 1 : DL)**

	Joint Label	L,D,M	Direction	Magnitude[(lb,lb-ft), (in,rad), (lb*...]
1	APXV9TM14-ALU-I20_TOP	L	Y	-27.5
2	APXV9TM14-ALU-I20_BOT	L	Y	-27.5
3	TD-RRH8X20	L	Y	-70
4	1900&800-RRH	L	Y	-124
5	APXVSP18-C-A20_TOP	L	Y	-28.5
6	APXVSP18-C-A20_BOT	L	Y	-28.5

**Joint Loads and Enforced Displacements (BLC 2 : WLz)**

	Joint Label	L,D,M	Direction	Magnitude[(lb,lb-ft), (in,rad), (lb*...]
1	APXV9TM14-ALU-I20_TOP	L	Z	-98.4
2	APXV9TM14-ALU-I20_BOT	L	Z	-98.4
3	TD-RRH8X20	L	Z	-125.6
4	1900&800-RRH	L	Z	-72.1
5	APXVSP18-C-A20_TOP	L	Z	-125.3
6	APXVSP18-C-A20_BOT	L	Z	-125.3

**Joint Loads and Enforced Displacements (BLC 3 : WLx)**

	Joint Label	L,D,M	Direction	Magnitude[(lb,lb-ft), (in,rad), (lb*...]
1	APXV9TM14-ALU-I20_TOP	L	X	-56
2	APXV9TM14-ALU-I20_BOT	L	X	-56
3	TD-RRH8X20	L	X	-47.6
4	1900&800-RRH	L	X	-129.4
5	APXVSP18-C-A20_TOP	L	X	-82.1
6	APXVSP18-C-A20_BOT	L	X	-82.1



**Member Distributed Loads (BLC 2 : WLz)**

	Member Label	Direction	Start Magnitude[lb/ft.F]	End Magnitude[lb/ft.F]	Start Location[ft.%]	End Location[ft.%]
1	M1	PZ	-7.4	-7.4	0	0
2	M2	PZ	-7.4	-7.4	0	0
3	M6	PZ	-7.4	-7.4	0	0
4	M13B	PZ	-7.4	-7.4	0	0
5	M10	PZ	-7.4	-7.4	0	0
6	M9	PZ	-8.7	-8.7	0	0
7	M4	PZ	-7.4	-7.4	0	2.75
8	M4	PZ	-7.4	-7.4	4.75	6

**Member Distributed Loads (BLC 3 : WLx)**

	Member Label	Direction	Start Magnitude[lb/ft.F]	End Magnitude[lb/ft.F]	Start Location[ft.%]	End Location[ft.%]
1	M2	PX	-7.4	-7.4	0	0
2	M5	PX	-7.4	-7.4	0	0
3	M10	PX	-7.4	-7.4	0	0
4	M13A	PX	-7.4	-7.4	0	0
5	M4	PX	-7.4	-7.4	0	0
6	M13B	PX	-7.4	-7.4	0	0
7	M9	PX	-8.7	-8.7	0	0
8	M11	PX	-15.5	-15.5	0	0
9	M12	PX	-15.5	-15.5	0	0

**Member Area Loads**

Joint A	Joint B	Joint C	Joint D	Direction	Distribution	Magnitude[psf]
No Data to Print ...						

**Basic Load Cases**

	BLC Description	Category	X Gravity	Y Gravity	Z Gravity	Joint	Point	Distributed Area(Me...)	Surface(P...
1	DL	DL		-1		6			
2	WLz	WLZ				6		8	
3	WLx	WLX				6		9	
4	LL1	LL					1		
5	LL2	None					1		

**Load Combinations**

	Description	Sol..	PDelta	SR..	BLC Fact..	BLC Fact..	BLC Fact..	BLC Fact..	BLC Fact..	BLC Fact..	BLC Fact..	BLC Fact..
1	1.4DL	Yes	Y		DL	1.4						
2	1.2DL+1.6WLz	Yes	Y		DL	1.2	WLZ	1.6				
3	1.2DL-1.6WLz	Yes	Y		DL	1.2	WLZ	-1.6				
4	1.2DL+1.6WLx	Yes	Y		DL	1.2	W...	1.6				
5	1.2DL-1.6WLx	Yes	Y		DL	1.2	W...	-1.6				
6	1.2DL+1.6(0.75WLz+0.75WLx)	Yes	Y		DL	1.2	WLZ	1.2	W...	1.2		
7	1.2DL+1.6(0.75WLz-0.75WLx)	Yes	Y		DL	1.2	WLZ	1.2	W...	-1.2		
8	1.2DL-1.6(0.75WLz-0.75WLx)	Yes	Y		DL	1.2	WLZ	-1.2	W...	1.2		
9	1.2DL-1.6(0.75WLz+0.75WLx)	Yes	Y		DL	1.2	WLZ	-1.2	W...	-1.2		
10	1.2DL+1.5LLend	Yes	Y		DL	1.2	LL	1.5				
11	1.2DL+1.5LLmid	Yes	Y		DL	1.2	5	1.5				
12	1.2DL+1.5LL+10%1.6WLz	Yes	Y		DL	1.2	LL	1.5	WLZ	.16		
13	1.2DL+1.5LL-10%1.6WLz	Yes	Y		DL	1.2	LL	1.5	WLZ	-.16		
14	1.2DL+1.5LL+10%1.6WLx	Yes	Y		DL	1.2	LL	1.5	W...	.16		
15	1.2DL+1.5LL-10%1.6WLx	Yes	Y		DL	1.2	LL	1.5	W...	-.16		
16	1.2DL+1.5LL+10%1.6(0.75WLz+...)	Yes	Y		DL	1.2	LL	1.5	WLZ	.12	W...	.12



**Load Combinations (Continued)**

	Description	Sol.	PDelta	SR	BLC Fact.	BLC Fact.	BLC Fact.	BLC Fact.	BLC Fact.	BLC Fact.	BLC Fact.	BLC Fact.	BLC Fact.
17	1.2DL+1.5LL+10%1.6(0.75WLz-...	Yes	Y		DL 1.2	LL 1.5	WLZ .12	W...	-.12				
18	1.2DL+1.5LL-10%1.6(0.75WLz-0...	Yes	Y		DL 1.2	LL 1.5	WLZ -.12	W...	.12				
19	1.2DL+1.5LL-10%1.6(0.75WLz+...	Yes	Y		DL 1.2	LL 1.5	WLZ -.12	W...	-.12				
20	1.2DL+1.5LL+10%1.6WLz	Yes	Y		DL 1.2	5 1.5	WLZ .16						
21	1.2DL+1.5LL-10%1.6WLz	Yes	Y		DL 1.2	5 1.5	WLZ -.16						
22	1.2DL+1.5LL+10%1.6WLx	Yes	Y		DL 1.2	5 1.5	W...	.16					
23	1.2DL+1.5LL-10%1.6WLx	Yes	Y		DL 1.2	5 1.5	W...	-.16					
24	1.2DL+1.5LL+10%1.6(0.75WLz+...	Yes	Y		DL 1.2	5 1.5	WLZ .12	W...	.12				
25	1.2DL+1.5LL+10%1.6(0.75WLz-...	Yes	Y		DL 1.2	5 1.5	WLZ .12	W...	-.12				
26	1.2DL+1.5LL-10%1.6(0.75WLz-0...	Yes	Y		DL 1.2	5 1.5	WLZ -.12	W...	.12				
27	1.2DL+1.5LL-10%1.6(0.75WLz+...	Yes	Y		DL 1.2	5 1.5	WLZ -.12	W...	-.12				
28	DL		Y		DL 1								
29	WLz		Y		WLZ 1								
30	WLx		Y		W... 1								

**Envelope Joint Reactions**

Joint		X [lb]	LC	Y [lb]	LC	Z [lb]	LC	MX [lb-ft]	LC	MY [lb-ft]	LC	MZ [lb-ft]	LC	
1	N46	max	523.178	4	529.154	13	412.481	2	0	1	1056.274	4	114.008	5
2		min	-971	5	285.357	2	-1140.878	3	0	1	-1705.087	5	-91.723	14
3	N45	max	791.986	8	528.247	20	612.932	2	0	1	1365.109	4	146.316	5
4		min	-344.525	7	319.782	3	114.374	3	0	1	-709.79	5	-94.851	14
5	N39	max	278.099	2	56.739	2	556.491	2	0	1	0	1	0	1
6		min	-277.316	3	-12.45	3	-555.4	3	0	1	0	1	0	1
7	Totals:	max	1292.551	4	1065.827	21	1581.904	2						
8		min	-1292.551	5	690.826	2	-1581.904	3						


**Envelope AISC 13th(360-05): LRFD Steel Code Checks**

Member	Shape	Code Ch...	Loc[ft]	LC	Shear ...	Loc[ft]	Dir	LC	phi*Pnc ...	phi*Pnt [...]	phi*Mn ...	phi*Mn ...	Cb	Eqn	
1	M1	PIPE 2.0	.446	6	3	.101	6		2	20866.7...	32130	1871.625	1871.625	1...	H1-1b
2	M2	PIPE 2.0	.218	4.75	14	.023	4.75		18	20866.7...	32130	1871.625	1871.625	1...	H1-1b
3	M5	PIPE 2.0	.334	1.75	2	.152	1.75		3	20866.7...	32130	1871.625	1871.625	1...	H1-1b
4	M6	PIPE 2.0	.506	6	3	.178	8		3	20866.7...	32130	1871.625	1871.625	1...	H1-1b
5	M9	PIPE 3.0	.136	4.219	21	.045	4.219		7	58506.3...	65205	5748.75	5748.75	2...	H1-1b
6	M10	PIPE 2.0	.166	0	21	.019	0		18	29628.5...	32130	1871.625	1871.625	2...	H1-1b
7	M11	HSS3x3x4	.262	1.875	5	.070	1.875	z	5	77142.6...	79056	6696	6696	2...	H1-1b
8	M12	HSS3x3x4	.215	1.875	4	.050	1.875	z	8	77142.6...	79056	6696	6696	2...	H1-1b
9	M13A	PIPE 2.0	.264	4.75	14	.037	4.75		3	20866.7...	32130	1871.625	1871.625	1...	H1-1b
10	M4	PIPE 2.0	.213	4.75	9	.118	3.75		3	20866.7...	32130	1871.625	1871.625	1...	H1-1b
11	M13B	PIPE 2.0	.182	0	2	.006	7		2	17855.0...	32130	1871.625	1871.625	1...	H1-1b

**APPENDIX D**

**TOWER AND FOUNDATION MODIFICATION DRAWINGS**






- NOTES:
- CONTRACTOR SHALL BE RESPONSIBLE FOR STABILITY OF THE TOWER DURING CONSTRUCTION.
  - ALL PROPOSED STEEL SHALL BE HOT DIPPED GALVANIZED.
  - ALL PROPOSED DIAGONAL MEMBERS HORIZONTAL MEMBERS, AND PLATES SHALL BE ASTM A36 STEEL, OR APPROVED EQUAL.
  - ALL PROPOSED LEG REINFORCEMENT ANGLES SHALL BE ASTM A572-50 STEEL, OR APPROVED EQUAL.
  - ALL PROPOSED BOLTS SHALL BE ASTM A325-X BOLTS (UNO). CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING BOLT THREADS ARE NOT IN SHEAR PLANE OF CONNECTION.

MODIFIED TOWER ELEVATION (1)  
 SCALE: 1" = 25'

ELEVATION	REPLACEMENT DIAGONAL SIZE	MINIMUM END CONNECTION END DISTANCE
0' - 20'	1 3/8" x 3 1/2" x 3/8"	1 1/2"
40' - 60'	1 3/8" x 3" x 3/8"	1 1/2"
80' - 100'	1 1/2" x 2 1/2" x 3/8"	1 1/2"
140' - 180'	1 1/2" x 2" x 3/8"	1 1/2"

- NOTES:
- REPLACE ALL EXISTING DIAGONAL BOLTS WITH NEW A325-X BOLTS OF SAME DIAMETER
  - DO NOT REUSE EXISTING BOLTS



REPLACEMENT DIAGONAL INFORMATION (2)  
 SCALE: NTS

6580 SPRINT PARKWAY  
 OVERLAND PARK, KANSAS 66251

1120 Dallas Street, Sauk City, WI 53583  
 Phone: 608-643-4100 Fax: 608-643-7999  
 www.Ramaker.com

48 SPRUCE STREET  
 OAKLAND, NJ 07346

Continuation of State License No. 28286, State of Connecticut, Professional Engineer, James P. Skowronski, No. 28286, State of Connecticut, Professional Engineer, dated 10/15/2014.

James P. Skowronski  
 10/15/2014

NO.	DATE	DESCRIPTION	DATE	BY
1	10/15/2014	FINAL CONSTRUCTION DRAWING REVIEWS		
2				
3				
4				
5				
6				
7				
8				
9				
10				
11				
12				
13				
14				
15				
16				
17				
18				
19				
20				
21				
22				
23				
24				
25				
26				
27				
28				
29				
30				
31				
32				
33				
34				
35				
36				
37				
38				
39				
40				
41				
42				
43				
44				
45				
46				
47				
48				
49				
50				
51				
52				
53				
54				
55				
56				
57				
58				
59				
60				
61				
62				
63				
64				
65				
66				
67				
68				
69				
70				
71				
72				
73				
74				
75				
76				
77				
78				
79				
80				
81				
82				
83				
84				
85				
86				
87				
88				
89				
90				
91				
92				
93				
94				
95				
96				
97				
98				
99				
100				


PROJECT TITLE:  
**TRANSFER STATION**  
**CT33XC522-C**

PROJECT INFORMATION:  
 237 GODFREY ROAD  
 WESTON, CT 06883  
 FAIRFIELD COUNTY


SHEET TITLE:  
**STRUCTURAL DETAILS**

SCALE:  
 AS NOTED


PROJECT NUMBER: 28737  
 SHEET NUMBER: S-1



6580 SPRINT PARKWAY  
OVERLAND PARK, KANSAS 66251




**RAMAKER & ASSOCIATES, INC.**  
1120 Dallas Street, Sauk City, WI 53583  
Phone: 608-643-4100 Fax: 608-643-7999  
www.Ramaker.com



48 SPRUCE STREET  
OAKLAND, NJ 07346

Certification & Seal: This Seal is the property of the State of Connecticut. It is to be reproduced, distributed, used or disclosed other in whole or in part except as authorized by Ramaker & Associates, Inc.  
 James P. Skowronski, No. 28286, Professional Engineer, State of Connecticut, License No. 28286, dated 10/15/2014



NO.	DATE	DESCRIPTION
1	10/15/2014	FINAL CONSTRUCTION DRAWING REVISED


NAME: JAMES P. SKOWRONSKI  
 PHASE: FINAL  
 DATE ISSUED: 10/15/2014  
 PROJECT TITLE: TRANSFER STATION  
 CT33XC522-C

PROJECT INFORMATION:  
 237 GODFREY ROAD  
 WESTON, CT 06893  
 FAIRFIELD COUNTY


SHEET TITLE:  
 STRUCTURAL DEATILS

SCALE:  
 AS NOTED

PROJECT NUMBER: 28737  
 SHEET NUMBER: 5-2



PLAN VIEW




ELEVATION VIEW


NOTE: REFER TO TABLE IN THIS DETAIL FOR REQUIRED SIZES OF SECONDARY HORIZONTALS AND BOLT ASSEMBLIES.

ELEVATION	PROPOSED SECONDARY HORIZONTAL	BOLT SIZE
1-40 - 1.60' AGL	L2 x 2 x 4	3/8" DIA.



TYP. SECONDARY HORIZONTAL ASSEMBLY 1  
 SCALE: NTS



TYP. LEG REINFORCEMENT ANGLE CLAMP 2  
SCALE: NTS



TYP. LEG REINFORCEMENT ANGLE WELD 3  
SCALE: NTS



ELEVATION	LEG REINFORCEMENT ANGLE SIZE	MAXIMUM ANGLE CLAMP SPACING
0° - 40°	1.8 x 0.5/2	1/2
40° - 60°	1.5 x 0.5/2	1/4
60° - 80°	1.3 x 0.5/2	1/4
80° - 100°	1.5 x 0.5/2	1/2
100° - 120°	1.5 x 0.5/2	1/2
120° - 140°	1.3/2 x 3/4 x 5/8	1/2

TYPICAL LEG REINFORCEMENT 1  
SCALE: NTS



Confirmation & Seal: I, James R. Skowronski, PE, hereby certify that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.  
 No. 28288  
 JAMES R. SKOWRONSKI  
 PROFESSIONAL ENGINEER  
 STATE OF CONNECTICUT  
 DATE: 10/15/2014  
 PROJECT TITLE: TRANSFER STATION  
 CT33XC522-C


MARK	DATE	DESCRIPTION
1	01/15/2014	FINAL
2	01/15/2014	FINAL
3	01/15/2014	FINAL
4	01/15/2014	FINAL
5	01/15/2014	FINAL

PROJECT INFORMATION:  
237 GODFREY ROAD  
WESTON, CT 06893  
FAIRFIELD COUNTY


STRUCTURAL DETAILS

SCALE: AS NOTED

28737  
S-3



1  
 MODIFIED FOUNDATION PLAN  
 SCALE: 1" = 7'-9"



2  
 MODIFIED FOUNDATION SECTION  
 SCALE: 1" = 7'-9"

6580 SPRINT PARKWAY  
OVERLAND PARK, KANSAS 66251

1120 Dallas Street, Sauk City, WI 53583  
 Phone: 608-643-4100 Fax: 608-643-7999  
 www.Ramaker.com

48 SPRUCE STREET  
OAKLAND, NJ 07346

Continuation Sheet  
 This drawing shall not be used without the approval of the Professional Engineer under the laws of the State of Connecticut.

James Skowronski  
 State of Connecticut  
 Professional Engineer  
 No. 28286  
 License Expires 10/15/2014

NO.	DATE	DESCRIPTION
1	10/15/2014	FINAL CONSTRUCTION DRAWING REVISIONS

PHASE: FINAL DATE: 10/15/2014


PROJECT TITLE:  
**TRANSFER STATION  
 CT33XC522-C**

PROJECT INFORMATION:  
 237 GODFREY ROAD  
 WESTON, CT 06893  
 FAIRFIELD COUNTY


SHEET TITLE:  
**STRUCTURAL DETAILS**

SCALE:  
 AS NOTED


DESIGNER NUMBER: 28737  
 CHECKER NUMBER: 5-4



**Sprint**  
 6580 SPRINT PARKWAY  
 OVERLAND PARK, KANSAS 66251



**RAMAKER & ASSOCIATES, INC.**  
 1120 Dallas Street, Sauk City, WI 53583  
 Phone: 608-643-4100 Fax: 608-643-7999  
 www.Ramaker.com



**Transcend Wireless**  
 48 SPRUCE STREET  
 OAKLAND, NJ 07346

Certification is based on the information provided by the client. The Engineer is not responsible for the accuracy of the information provided by the client or for any errors or omissions in the drawings. The Engineer is not responsible for the accuracy of the information provided by the client or for any errors or omissions in the drawings. The Engineer is not responsible for the accuracy of the information provided by the client or for any errors or omissions in the drawings.

**PROJECT:** 2.5 EQUIPMENT DEPLOYMENT

**SITE NAME:** TRANSFER STATION

**SITE CASCADE:** CT33XC522-C

**SITE ADDRESS:** 237 GODFREY ROAD  
WESTON, CT 06883

**SITE TYPE:** 185'-0' SELF SUPPORT TOWER



# Sprint

SHEET INDEX	
SHT NO:	SHEET TITLE:
T-1	TITLE SHEET
SP-1	SPRINT SPECIFICATIONS
SP-2	SPRINT SPECIFICATIONS
SP-3	SPRINT SPECIFICATIONS
A-1	SITE PLAN
A-2	EQUIPMENT PLAN
A-3	BUILDING ELEVATION & ANTENNA DETAILS
A-4	RF DATA SHEET
A-5	FIBER FLOORING DIAGRAM
A-6	CABLE COLOR CODING
A-7	ANTENNA & HYBRID CABLE DETAILS
A-8	EQUIPMENT DETAILS
S-1	STRUCTURAL DETAILS
S-2	STRUCTURAL DETAILS
S-3	STRUCTURAL DETAILS
S-4	STRUCTURAL DETAILS
E-1	EQUIPMENT UTILITY & GROUNDING PLAN
E-2	GROUNDING DETAILS
E-3	DC POWER DETAILS & PANEL SCHEDULES


**PROJECT DESCRIPTION**

- INSTALL NEW 2.5 EQUIPMENT IN EXISTING BVS CABINET
  - (1) RECTIFIER SHELF AND (8) RECTIFIERS
  - (1) BASE BAND UNIT
- INSTALL NEW BATTERY STRING IN EXISTING BATTERY CABINET
- INSTALL (3) PANEL ANTENNAS
- INSTALL (3) RRHS ON TOWER
- INSTALL (1) HYBRID CABLE AND (3) SECTION JUMPERS
- INSTALL (27) ANTENNA / RRH JUMPERS

**APPLICABLE CODES**

- INTERNATIONAL BUILDING CODE
- ANSI/ISA-222 STRUCTURAL STANDARD FOR ANTENNA STRUCTURES
- NFPA 750 - LIGHTNING PROTECTION CODE
- NATIONAL ELECTRIC CODE

\* ALL WORK SHALL BE PERFORMED AND MATERIALS INSTALLED IN ACCORDANCE WITH THE FOLLOWING CODES AS ADOPTED BY THE LOCAL GOVERNING AUTHORITIES. NOTHING IN THESE PLANS IS TO BE CONSIDERED TO LIMIT WORKING CONFORMING TO THESE CODES!



**SITE INFORMATION**

**PROPERTY OWNER:**  
 TOWN OF WESTON  
 56 NORFELD ROAD  
 WESTON, CT 06883

**SITE ADDRESS:**  
 237 GODFREY ROAD  
 WESTON, CT 06883  
 FAIRFIELD COUNTY

**GEOGRAPHIC COORDINATES:**  
 LATITUDE: 41.244896141° N (43° 29' 28.91")  
 LONGITUDE: -73.3633366 (73° 21' 46.1896")

**ZONING JURISDICTION:**  
 TOWN OF WESTON

**ZONING DISTRICT:**  
 R-2A


**POWER COMPANY:**  
 SPRINT & POWER  
 575 W. 10TH ST  
 PHILADELPHIA, PA 19107  
 PH: (800) 245-5000  
 E-MAIL: gary.wood@sprint.com

**AAV PROVIDER:**  
 PH: (201) 852-14105

**SPRINT CONSTRUCTION MANAGER:**  
 NAME: GARY WOOD  
 PHONE: (860) 340-9168  
 E-MAIL: gary.wood@sprint.com

**EQUIPMENT SUPPLIER:**  
 AGC/TELECOM  
 600-700 MOUNTAIN AVENUE  
 MURRAY HILL, NJ 07974  
 PH: (608) 508-8080

**PLANS PREPARED BY:**  
 RAMAKER & ASSOCIATES, INC.  
 CONTACT: KETH BORNISACK, PROJECT MANAGER  
 PH: (608) 643-4100  
 E-MAIL: kbornisack@ramaker.com



6580 SPRINT PARKWAY  
OVERLAND PARK, KANSAS 66251



1120 Dallas Street, Sauk City, WI 53583  
Phone: 608-643-4100 Fax: 608-643-7999  
www.Ramaker.com



48 SPRUCE STREET  
OAKLAND, NJ 07346



Contractor's Date: 10/20/2014  
Professional Engineer under the laws of the State of Connecticut

Table with 3 columns: MARK, DATE, DESCRIPTION. Includes rows for PHASE FINAL and DATE 10/20/2014.

TRANSFER STATION  
CT33XC52-C

PROJECT INFORMATION:  
237 GODFREY ROAD  
WESTON, CT 06883  
FAIRFIELD COUNTY

SPRINT SPECIFICATIONS

SCALE: NONE

287-37  
SIP-1

- 10. PROVIDE ANTENNA SUPPORT STRUCTURE FOUNDATIONS.
11. INSTALL COMPOUND FENCING, SIGHT SHIELDING, LANDSCAPING AND ACCESS BARRIERS.
12. PERFORM INSPECTION AND MATERIAL TESTING AS REQUIRED HEREIN.
13. INSTALL FIBER GENERATOR SITES AND OTHER STANDBY TOWER SOLUTIONS.
14. INSTALL TOWERS, ANTENNA SUPPORT STRUCTURES AND PLATFORMS ON EXISTING TOWERS AS APPLICABLE.
15. INSTALL CELL SITES RADIOS, MICROWAVE, GPS, COAXIAL MANLINE, ANTENNAS, CROSS BAND COUPLERS, TOWER TOP AMPIFIERS, LOW NOISE AMPIFIERS AND RELATED EQUIPMENT.
16. CONDUCT ALL REQUIRED TESTS AND INSPECTIONS.
17. ANY CONSTRUCTION CONTROL DOCUMENTS THAT MAY BE REQUIRED BY GOVERNMENT AGENCIES AND LANDLORDS.
18. PROVIDE ALL NECESSARY PERMITS AND APPROVALS.
19. OBTAIN ALL NECESSARY APPROVALS FROM ALL APPLICABLE AGENCIES AND LANDLORDS.
20. OBTAIN ALL NECESSARY APPROVALS FROM ALL APPLICABLE AGENCIES AND LANDLORDS.

- 1. ALL CORRESPONDENCE AND PRELIMINARY CONSTRUCTION REPORTS.
2. PROJECT PROGRESS REPORTS.
3. THE CONSTRUCTION MEETING NOTES.
4. ALLER WARNERS.
5. ALL NECESSARY CONSTRUCTION PHOTOS.
6. CONSTRUCTION AND COMMISSIONING CHECKLIST COMPLETE WITH NO DEFICIENT ITEMS.
7. LISTS OF SUBCONTRACTORS.
8. ALL NECESSARY PERMITS AND APPROVALS.
9. ALL NECESSARY APPROVALS FROM ALL APPLICABLE AGENCIES AND LANDLORDS.
10. ALL NECESSARY APPROVALS FROM ALL APPLICABLE AGENCIES AND LANDLORDS.

- 1. ALL CORRESPONDENCE AND PRELIMINARY CONSTRUCTION REPORTS.
2. PROJECT PROGRESS REPORTS.
3. THE CONSTRUCTION MEETING NOTES.
4. ALLER WARNERS.
5. ALL NECESSARY CONSTRUCTION PHOTOS.
6. CONSTRUCTION AND COMMISSIONING CHECKLIST COMPLETE WITH NO DEFICIENT ITEMS.
7. LISTS OF SUBCONTRACTORS.
8. ALL NECESSARY PERMITS AND APPROVALS.
9. ALL NECESSARY APPROVALS FROM ALL APPLICABLE AGENCIES AND LANDLORDS.
10. ALL NECESSARY APPROVALS FROM ALL APPLICABLE AGENCIES AND LANDLORDS.

- 1. ALL CORRESPONDENCE AND PRELIMINARY CONSTRUCTION REPORTS.
2. PROJECT PROGRESS REPORTS.
3. THE CONSTRUCTION MEETING NOTES.
4. ALLER WARNERS.
5. ALL NECESSARY CONSTRUCTION PHOTOS.
6. CONSTRUCTION AND COMMISSIONING CHECKLIST COMPLETE WITH NO DEFICIENT ITEMS.
7. LISTS OF SUBCONTRACTORS.
8. ALL NECESSARY PERMITS AND APPROVALS.
9. ALL NECESSARY APPROVALS FROM ALL APPLICABLE AGENCIES AND LANDLORDS.
10. ALL NECESSARY APPROVALS FROM ALL APPLICABLE AGENCIES AND LANDLORDS.

- 1. ALL CORRESPONDENCE AND PRELIMINARY CONSTRUCTION REPORTS.
2. PROJECT PROGRESS REPORTS.
3. THE CONSTRUCTION MEETING NOTES.
4. ALLER WARNERS.
5. ALL NECESSARY CONSTRUCTION PHOTOS.
6. CONSTRUCTION AND COMMISSIONING CHECKLIST COMPLETE WITH NO DEFICIENT ITEMS.
7. LISTS OF SUBCONTRACTORS.
8. ALL NECESSARY PERMITS AND APPROVALS.
9. ALL NECESSARY APPROVALS FROM ALL APPLICABLE AGENCIES AND LANDLORDS.
10. ALL NECESSARY APPROVALS FROM ALL APPLICABLE AGENCIES AND LANDLORDS.

- 1. ALL CORRESPONDENCE AND PRELIMINARY CONSTRUCTION REPORTS.
2. PROJECT PROGRESS REPORTS.
3. THE CONSTRUCTION MEETING NOTES.
4. ALLER WARNERS.
5. ALL NECESSARY CONSTRUCTION PHOTOS.
6. CONSTRUCTION AND COMMISSIONING CHECKLIST COMPLETE WITH NO DEFICIENT ITEMS.
7. LISTS OF SUBCONTRACTORS.
8. ALL NECESSARY PERMITS AND APPROVALS.
9. ALL NECESSARY APPROVALS FROM ALL APPLICABLE AGENCIES AND LANDLORDS.
10. ALL NECESSARY APPROVALS FROM ALL APPLICABLE AGENCIES AND LANDLORDS.

- 1. ALL CORRESPONDENCE AND PRELIMINARY CONSTRUCTION REPORTS.
2. PROJECT PROGRESS REPORTS.
3. THE CONSTRUCTION MEETING NOTES.
4. ALLER WARNERS.
5. ALL NECESSARY CONSTRUCTION PHOTOS.
6. CONSTRUCTION AND COMMISSIONING CHECKLIST COMPLETE WITH NO DEFICIENT ITEMS.
7. LISTS OF SUBCONTRACTORS.
8. ALL NECESSARY PERMITS AND APPROVALS.
9. ALL NECESSARY APPROVALS FROM ALL APPLICABLE AGENCIES AND LANDLORDS.
10. ALL NECESSARY APPROVALS FROM ALL APPLICABLE AGENCIES AND LANDLORDS.

- 1. ALL CORRESPONDENCE AND PRELIMINARY CONSTRUCTION REPORTS.
2. PROJECT PROGRESS REPORTS.
3. THE CONSTRUCTION MEETING NOTES.
4. ALLER WARNERS.
5. ALL NECESSARY CONSTRUCTION PHOTOS.
6. CONSTRUCTION AND COMMISSIONING CHECKLIST COMPLETE WITH NO DEFICIENT ITEMS.
7. LISTS OF SUBCONTRACTORS.
8. ALL NECESSARY PERMITS AND APPROVALS.
9. ALL NECESSARY APPROVALS FROM ALL APPLICABLE AGENCIES AND LANDLORDS.
10. ALL NECESSARY APPROVALS FROM ALL APPLICABLE AGENCIES AND LANDLORDS.

- 1. ALL CORRESPONDENCE AND PRELIMINARY CONSTRUCTION REPORTS.
2. PROJECT PROGRESS REPORTS.
3. THE CONSTRUCTION MEETING NOTES.
4. ALLER WARNERS.
5. ALL NECESSARY CONSTRUCTION PHOTOS.
6. CONSTRUCTION AND COMMISSIONING CHECKLIST COMPLETE WITH NO DEFICIENT ITEMS.
7. LISTS OF SUBCONTRACTORS.
8. ALL NECESSARY PERMITS AND APPROVALS.
9. ALL NECESSARY APPROVALS FROM ALL APPLICABLE AGENCIES AND LANDLORDS.
10. ALL NECESSARY APPROVALS FROM ALL APPLICABLE AGENCIES AND LANDLORDS.

SECTION 01 400 - TESTS, INSPECTIONS, SUBMITTALS, AND PROJECT CLOSEOUT

SECTION 01 200 - COMPANY FURNISHED MATERIAL AND EQUIPMENT

SECTION 01 300 - CELL SITE CONSTRUCTION

- 1. ALL CORRESPONDENCE AND PRELIMINARY CONSTRUCTION REPORTS.
2. PROJECT PROGRESS REPORTS.
3. THE CONSTRUCTION MEETING NOTES.
4. ALLER WARNERS.
5. ALL NECESSARY CONSTRUCTION PHOTOS.
6. CONSTRUCTION AND COMMISSIONING CHECKLIST COMPLETE WITH NO DEFICIENT ITEMS.
7. LISTS OF SUBCONTRACTORS.
8. ALL NECESSARY PERMITS AND APPROVALS.
9. ALL NECESSARY APPROVALS FROM ALL APPLICABLE AGENCIES AND LANDLORDS.
10. ALL NECESSARY APPROVALS FROM ALL APPLICABLE AGENCIES AND LANDLORDS.

- 1. ALL CORRESPONDENCE AND PRELIMINARY CONSTRUCTION REPORTS.
2. PROJECT PROGRESS REPORTS.
3. THE CONSTRUCTION MEETING NOTES.
4. ALLER WARNERS.
5. ALL NECESSARY CONSTRUCTION PHOTOS.
6. CONSTRUCTION AND COMMISSIONING CHECKLIST COMPLETE WITH NO DEFICIENT ITEMS.
7. LISTS OF SUBCONTRACTORS.
8. ALL NECESSARY PERMITS AND APPROVALS.
9. ALL NECESSARY APPROVALS FROM ALL APPLICABLE AGENCIES AND LANDLORDS.
10. ALL NECESSARY APPROVALS FROM ALL APPLICABLE AGENCIES AND LANDLORDS.

- 1. ALL CORRESPONDENCE AND PRELIMINARY CONSTRUCTION REPORTS.
2. PROJECT PROGRESS REPORTS.
3. THE CONSTRUCTION MEETING NOTES.
4. ALLER WARNERS.
5. ALL NECESSARY CONSTRUCTION PHOTOS.
6. CONSTRUCTION AND COMMISSIONING CHECKLIST COMPLETE WITH NO DEFICIENT ITEMS.
7. LISTS OF SUBCONTRACTORS.
8. ALL NECESSARY PERMITS AND APPROVALS.
9. ALL NECESSARY APPROVALS FROM ALL APPLICABLE AGENCIES AND LANDLORDS.
10. ALL NECESSARY APPROVALS FROM ALL APPLICABLE AGENCIES AND LANDLORDS.

- 1. ALL CORRESPONDENCE AND PRELIMINARY CONSTRUCTION REPORTS.
2. PROJECT PROGRESS REPORTS.
3. THE CONSTRUCTION MEETING NOTES.
4. ALLER WARNERS.
5. ALL NECESSARY CONSTRUCTION PHOTOS.
6. CONSTRUCTION AND COMMISSIONING CHECKLIST COMPLETE WITH NO DEFICIENT ITEMS.
7. LISTS OF SUBCONTRACTORS.
8. ALL NECESSARY PERMITS AND APPROVALS.
9. ALL NECESSARY APPROVALS FROM ALL APPLICABLE AGENCIES AND LANDLORDS.
10. ALL NECESSARY APPROVALS FROM ALL APPLICABLE AGENCIES AND LANDLORDS.

- 1. ALL CORRESPONDENCE AND PRELIMINARY CONSTRUCTION REPORTS.
2. PROJECT PROGRESS REPORTS.
3. THE CONSTRUCTION MEETING NOTES.
4. ALLER WARNERS.
5. ALL NECESSARY CONSTRUCTION PHOTOS.
6. CONSTRUCTION AND COMMISSIONING CHECKLIST COMPLETE WITH NO DEFICIENT ITEMS.
7. LISTS OF SUBCONTRACTORS.
8. ALL NECESSARY PERMITS AND APPROVALS.
9. ALL NECESSARY APPROVALS FROM ALL APPLICABLE AGENCIES AND LANDLORDS.
10. ALL NECESSARY APPROVALS FROM ALL APPLICABLE AGENCIES AND LANDLORDS.

- 1. ALL CORRESPONDENCE AND PRELIMINARY CONSTRUCTION REPORTS.
2. PROJECT PROGRESS REPORTS.
3. THE CONSTRUCTION MEETING NOTES.
4. ALLER WARNERS.
5. ALL NECESSARY CONSTRUCTION PHOTOS.
6. CONSTRUCTION AND COMMISSIONING CHECKLIST COMPLETE WITH NO DEFICIENT ITEMS.
7. LISTS OF SUBCONTRACTORS.
8. ALL NECESSARY PERMITS AND APPROVALS.
9. ALL NECESSARY APPROVALS FROM ALL APPLICABLE AGENCIES AND LANDLORDS.
10. ALL NECESSARY APPROVALS FROM ALL APPLICABLE AGENCIES AND LANDLORDS.

- 1. ALL CORRESPONDENCE AND PRELIMINARY CONSTRUCTION REPORTS.
2. PROJECT PROGRESS REPORTS.
3. THE CONSTRUCTION MEETING NOTES.
4. ALLER WARNERS.
5. ALL NECESSARY CONSTRUCTION PHOTOS.
6. CONSTRUCTION AND COMMISSIONING CHECKLIST COMPLETE WITH NO DEFICIENT ITEMS.
7. LISTS OF SUBCONTRACTORS.
8. ALL NECESSARY PERMITS AND APPROVALS.
9. ALL NECESSARY APPROVALS FROM ALL APPLICABLE AGENCIES AND LANDLORDS.
10. ALL NECESSARY APPROVALS FROM ALL APPLICABLE AGENCIES AND LANDLORDS.

- 1. ALL CORRESPONDENCE AND PRELIMINARY CONSTRUCTION REPORTS.
2. PROJECT PROGRESS REPORTS.
3. THE CONSTRUCTION MEETING NOTES.
4. ALLER WARNERS.
5. ALL NECESSARY CONSTRUCTION PHOTOS.
6. CONSTRUCTION AND COMMISSIONING CHECKLIST COMPLETE WITH NO DEFICIENT ITEMS.
7. LISTS OF SUBCONTRACTORS.
8. ALL NECESSARY PERMITS AND APPROVALS.
9. ALL NECESSARY APPROVALS FROM ALL APPLICABLE AGENCIES AND LANDLORDS.
10. ALL NECESSARY APPROVALS FROM ALL APPLICABLE AGENCIES AND LANDLORDS.

- 1. ALL CORRESPONDENCE AND PRELIMINARY CONSTRUCTION REPORTS.
2. PROJECT PROGRESS REPORTS.
3. THE CONSTRUCTION MEETING NOTES.
4. ALLER WARNERS.
5. ALL NECESSARY CONSTRUCTION PHOTOS.
6. CONSTRUCTION AND COMMISSIONING CHECKLIST COMPLETE WITH NO DEFICIENT ITEMS.
7. LISTS OF SUBCONTRACTORS.
8. ALL NECESSARY PERMITS AND APPROVALS.
9. ALL NECESSARY APPROVALS FROM ALL APPLICABLE AGENCIES AND LANDLORDS.
10. ALL NECESSARY APPROVALS FROM ALL APPLICABLE AGENCIES AND LANDLORDS.

- 1. ALL CORRESPONDENCE AND PRELIMINARY CONSTRUCTION REPORTS.
2. PROJECT PROGRESS REPORTS.
3. THE CONSTRUCTION MEETING NOTES.
4. ALLER WARNERS.
5. ALL NECESSARY CONSTRUCTION PHOTOS.
6. CONSTRUCTION AND COMMISSIONING CHECKLIST COMPLETE WITH NO DEFICIENT ITEMS.
7. LISTS OF SUBCONTRACTORS.
8. ALL NECESSARY PERMITS AND APPROVALS.
9. ALL NECESSARY APPROVALS FROM ALL APPLICABLE AGENCIES AND LANDLORDS.
10. ALL NECESSARY APPROVALS FROM ALL APPLICABLE AGENCIES AND LANDLORDS.

- 1. ALL CORRESPONDENCE AND PRELIMINARY CONSTRUCTION REPORTS.
2. PROJECT PROGRESS REPORTS.
3. THE CONSTRUCTION MEETING NOTES.
4. ALLER WARNERS.
5. ALL NECESSARY CONSTRUCTION PHOTOS.
6. CONSTRUCTION AND COMMISSIONING CHECKLIST COMPLETE WITH NO DEFICIENT ITEMS.
7. LISTS OF SUBCONTRACTORS.
8. ALL NECESSARY PERMITS AND APPROVALS.
9. ALL NECESSARY APPROVALS FROM ALL APPLICABLE AGENCIES AND LANDLORDS.
10. ALL NECESSARY APPROVALS FROM ALL APPLICABLE AGENCIES AND LANDLORDS.

- 1. ALL CORRESPONDENCE AND PRELIMINARY CONSTRUCTION REPORTS.
2. PROJECT PROGRESS REPORTS.
3. THE CONSTRUCTION MEETING NOTES.
4. ALLER WARNERS.
5. ALL NECESSARY CONSTRUCTION PHOTOS.
6. CONSTRUCTION AND COMMISSIONING CHECKLIST COMPLETE WITH NO DEFICIENT ITEMS.
7. LISTS OF SUBCONTRACTORS.
8. ALL NECESSARY PERMITS AND APPROVALS.
9. ALL NECESSARY APPROVALS FROM ALL APPLICABLE AGENCIES AND LANDLORDS.
10. ALL NECESSARY APPROVALS FROM ALL APPLICABLE AGENCIES AND LANDLORDS.



**SUPPORTING DEVICES:**

- A. INSTALL SUPPORTING DEVICES TO FASTEN ELECTRICAL COMPONENTS SECURELY AND PERMANENTLY IN ACCORDANCE WITH NEC.
- B. COORDINATE WITH THE BUILDING STRUCTURAL SYSTEM AND WITH OTHER TRADES.
- C. UNLESS OTHERWISE INDICATED ON THE DRAWINGS, FASTEN ELECTRICAL ITEMS AND THEIR SUPPORTING HARDWARE SECURELY TO THE STRUCTURE IN ACCORDANCE WITH THE FOLLOWING:
  - 1. ENSURE THAT THE LOAD APPLIED BY ANY FASTENER DOES NOT EXCEED 25 PERCENT OF THE PROOF TEST LOAD.
  - 2. USE VIBRATION AND SHOCK-RESISTANT FASTENERS FOR ATTACHMENTS TO CONCRETE SLABS.

**ELECTRICAL IDENTIFICATION:**

- A. UPDATE AND PROVIDE TYPED CIRCUIT BREAKER SCHEDULES IN THE MOUNTING BRACKET, INSIDE DOORS OF AC PANEL BOARDS WITH ANY CHANGES MADE TO THE AC SYSTEM.
- B. BRANCH CIRCUITS FEEDING AVIATION OBSTRUCTION LIGHTING EQUIPMENT SHALL BE CLEARLY IDENTIFIED AS SUCH AT THE BRANCH CIRCUIT PANELEBOARD.

**SECTION 26 200 - ELECTRICAL MATERIALS AND EQUIPMENT**

- A. RIGID GALVANIZED STEEL (RGS) CONDUIT SHALL BE USED FOR EXTERIOR LOCATIONS ABOVE GROUND AND IN UNFINISHED INTERIOR LOCATIONS AND FOR UNDERGROUND RUNS. RIGID CONDUIT AND FITTINGS SHALL BE STEEL COATED WITH ZINC EXTERIOR AND INTERIOR BY THE HOT DIP GALVANIZING PROCESS. CONDUIT SHALL BE PRODUCED TO ANSI SPECIFICATIONS GOVT. FEDERAL SPECIFICATION HT-35. CONDUIT SHALL BE MANUFACTURED TO MEET THE REQUIREMENTS OF FEDERAL SPECIFICATION HT-35. RGS CONDUITS SHALL BE MANUFACTURED BY ALLED, REPUBLIC OR WHEATLAND.
- B. UNDERGROUND CONDUIT IN CONCRETE SHALL BE POLYVINYLCHLORIDE (PVC) SUITABLE FOR DIRECT BURIAL AS APPLICABLE. JOINTS SHALL BE BELLED, AND FLUSH SOLVENT WELDED IN ACCORDANCE WITH MANUFACTURERS INSTRUCTIONS. CONDUIT SHALL BE CARBON ELECTRICAL PRODUCTS OR APPROVED EQUAL.
- C. TRANSITIONS BETWEEN PVC AND RIGID (RGS) SHALL BE MADE WITH PVC COATED METALLIC LONG SWEEP 90-DIGREE ELBOWS.
- D. EMT OR RIGID GALVANIZED STEEL CONDUIT MAY BE USED IN FINISHED SPACES CONCEALED IN WALLS AND CEILING. EMT SHALL BE MILD STEEL, ELECTRICALLY WELDED, ELECTRO-GALVANIZED OR HOT-DIP GALVANIZED. EMT SHALL BE MANUFACTURED BY ALLED, REPUBLIC OR WHEATLAND, OR APPROVED EQUAL. FITTINGS SHALL BE METALLIC COMPRESSION. SET SCREW CONNECTIONS SHALL NOT BE ACCEPTABLE.
- E. LIQUID TIGHT FLEXIBLE METALLIC CONDUIT SHALL BE USED FOR FINAL CONNECTION TO EQUIPMENT. FITTINGS SHALL BE METALLIC GRIND TYPE COMPRESSION FITTINGS, MAINTAINING THE INTEGRITY OF THE CONDUIT. FLEXIBLE CONDUIT SHALL NOT EXCEED 6 FEET. EMT SHALL BE PROTECTED AND SUPPORTED AS REQUIRED BY NEC. MANUFACTURERS OF FLEXIBLE CONDUITS SHALL BE CAROL, ANACONDA METAL HOSE OR UNIVERSAL METAL HOSE, OR APPROVED EQUAL.
- F. MINIMUM SIZE CONDUIT SHALL BE 3/4 INCH (2 INMM).

**HUBS AND BOXES:**

- A. AT ENTRANCES TO CABINETS OR OTHER EQUIPMENT NOT HAVING INTEGRAL THREADED HUBS PROVIDE CONDUIT HUBS AND FITTINGS TO BE METALLIC. CONDUIT SHALL BE PROTECTED AND SUPPORTED AS REQUIRED BY NEC. MANUFACTURERS SHALL PROVIDE IMPACT RESISTANT 105 DEGREE C PLASTIC BUSHINGS TO PROTECT CABLE INSULATION.
- B. CABLE TERMINATION FITTINGS FOR CONDUIT
  - 1. CABLE TERMINATORS FOR RGS CONDUITS SHALL BE TYPE CRC BY O-Z/GEDNEY OR EQUAL BY ROMETE.
  - 2. CABLE TERMINATORS FOR EMT SHALL BE ETCO - G12075, OR MADE FOR THE PURPOSE PRODUCTS BY ROMETE.
- C. EXTERIOR PULL BOXES AND PULL BOXES IN INTERIOR INDUSTRIAL AREAS SHALL BE PLATED CAST ALLOY, HEAVY DUTY, WEATHERPROOF, DUST PROOF, WITH GASKET, PLATED IRON ALLOY COVER AND STAINLESS STEEL COVER SOCKETS, CROUSE-HINDS WAB SERIES OR EQUAL.
- D. CONDUIT OUTLET BODIES SHALL BE PLATED CAST ALLOY WITH SIMILAR GASKET COVERS. OUTLET BODIES SHALL BE OF THE CONFIGURATION AND SIZE SUITABLE FOR THE APPLICATION, PROVIDE CROUSE-HINDS FORM 8 OR EQUAL.
- E. MANUFACTURER FOR BOXES AND COVERS SHALL BE HOFFMAN, SQUARE D, CROUSE-HINDS, COOPER, ADALET, APTECON, O-Z GEDNEY, RACO, OR APPROVED EQUAL.

**SUPPLEMENTAL GROUNDING SYSTEM:**

- A. FINISH AND INSTALL A SUPPLEMENTAL GROUNDING SYSTEM TO THE POINT INDICATED ON THE DRAWINGS. SUPPORT SYSTEM WITH NON-MAGNETIC STAINLESS STEEL CLIPS WITH RUBBER GROMMETS. GROUNDING CONNECTORS SHALL BE TINNED COPPER WIRE, SIZES AS INDICATED ON THE DRAWINGS. PROVIDE STRANDED OR SOLDER BARE OR INSULATED CONDUCTORS EXCEPT AS OTHERWISE NOTED.
- B. SUPPLEMENTAL GROUNDING SYSTEM: ALL CONNECTIONS TO BE MADE WITH CAD WELDS, EXCEPT AT EQUIPMENT USE LUGS OR OTHER AVAILABLE GROUNDING MEANS AS REQUIRED BY MANUFACTURER, AT GROUND BARS USE TWO HOLE SPACERS WITH INCON.
- C. STOLEN GROUND BARS: IN THE EVENT OF STOLEN GROUND BARS, CONTACT SPRINT CM FOR REPLACEMENT INSTRUCTION USING THREADED ROD KITS.

**EXISTING STRUCTURE:**

- A. EXISTING PRESSED WIRING AND ALL EXPOSED OUTLETS, RECEPTACLES, SWITCHES, DEVICES, BOXES, AND OTHER EQUIPMENT THAT ARE NOT TO BE UTILIZED IN THE COMPLETED PROJECT SHALL BE REMOVED OR DE-ENERGIZED AND CAPPED IN THE WALL, CEILING, OR FLOOR SO THAT THEY ARE CONCEALED AND SAFE. WALL, CEILING, OR FLOOR SHALL BE PATCHED TO MATCH THE ADJACENT CONSTRUCTION.

**CONDUIT AND CONDUCTOR INSTALLATION:**

- A. CONDUITS SHALL BE FASTENED SECURELY IN PLACE WITH APPROVED, NON-PERFORATED STRAPS AND HANGERS. EXPLOSIVE DEVICES FOR ATTACHING HANGERS TO STRUCTURE WILL NOT BE PERMITTED. CLOSELY FOLLOW THE LINES OF THE STRUCTURE, MAINTAIN CLOSE PROXIMITY TO THE STRUCTURE AND MAINTAIN PROXIMITY TO THE STRUCTURE. CONDUITS SHALL BE INSTALLED IN A NEAT AND WORKMANLIKE MANNER. CONDUIT SHALL BE INSTALLED IN A NEAT AND WORKMANLIKE MANNER, PARALLEL AND PERPENDICULAR TO STRUCTURE WALL AND CEILING LINES. ALL CONDUIT SHALL BE FISHED TO CLEAR OBSTRUCTIONS. ENDS OF CONDUITS SHALL BE TEMPORARILY CAPPED TO PREVENT DAMAGE TO THE CONDUIT. CONDUITS SHALL BE INSTALLED INSIDE AND OUTSIDE OF THE STRUCTURE. GALVANIZED MALLEABLE IRON BUSHING ON INSIDE AND GALVANIZED MALLEABLE IRON LOCATIONS OUTSIDE AND INSIDE.
- B. CONDUCTORS SHALL BE PULLED IN ACCORDANCE WITH ACCEPTED GOOD PRACTICE.



6580 SPRINT PARKWAY  
OVERLAND PARK, KANSAS 66251




1120 Dallas Street, Sauk City, WI 53583  
Phone: 608-643-4100 Fax: 608-643-7999  
www.Ramaker.com



48 SPRUCE STREET  
OAKLAND, NJ 07346

Certification & Seal  
I hereby certify that the above is the work of the Professional Engineer named by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



10/20/2014  
DATE ISSUED

MARK	DATE	DESCRIPTION
ISSUE	FINAL	
PHASE		

PROJECT TITLE:  
**TRANSFER STATION  
CT33XC522-C**


PROJECT INFORMATION:  
237 GODFREY ROAD  
WESTON, CT 06883  
FAIRFIELD COUNTY

SHEET TITLE:  
**SPRINT SPECIFICATIONS**

SCALE: NONE

PROJECT NUMBER: 28737  
SHEET NUMBER: SP-3





**Sprint**  
 6580 SPRINT PARKWAY  
 OVERLAND PARK, KANSAS 66251

**RAMAKER & ASSOCIATES, INC.**  
 1120 Dallas Street, Sauk City, WI 53583  
 Phone: 608-643-4100 Fax: 608-643-7999  
 www.Ramaker.com

**Transcend Wireless**  
 48 SPRUCE STREET  
 OAKLAND, NJ 07346

Confirmation & Seal: I hereby certify that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.  
**JAMES P. SKOWRONSKI**  
 No. 28286  
 PROFESSIONAL ENGINEER  
 STATE OF CONNECTICUT  
 10/20/2014

MARK	DATE	DESCRIPTION
ISSUE	FINAL	DATE ISSUED: 10/20/2014
PROJECT TITLE:		

**TRANSFER STATION**  
**CT33XC522-C**

PROJECT INFORMATION:  
 237 GODFREY ROAD  
 WESTON, CT 06893  
 FAIRFIELD COUNTY

SHEET TITLE:  
**SITE PLAN**

0 5' 10' 20'

1" = 17'  
 2.2" x 3.4" = 1" = 5'  
 SHEET NUMBER: **28737**  
 SHEET NUMBER: **A-1**

**SITE PLAN**  
 SCALE: 1" = 10'



6580 SPRINT PARKWAY  
OVERLAND PARK, KANSAS 66251



**RAMAKER & ASSOCIATES, INC.**  
1120 Dallas Street, Sauk City, WI 53583  
Phone: 608-643-4100 Fax: 608-643-7999  
www.Ramaker.com



48 SPRUCE STREET  
OAKLAND, NJ 07346

Certification & Seal: I am a duly Licensed Professional Engineer under the laws of the State of Connecticut. My license No. 28286 expires on 10/20/2014. I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.




*James Skowronski*  
Professional Engineer  
10/20/2014

MARK	DATE	DESCRIPTION
ISSUE	FINAL	DATE ISSUED: 10/20/2014

PROJECT TITLE:  
**TRANSFER STATION  
CT33XC522-C**

PROJECT INFORMATION:  
237 GODFREY ROAD  
WESTON, CT 06893  
FAIRFIELD COUNTY

SHEET TITLE:  
**EQUIPMENT PLAN**




0 1.25' 2.5' 5'


1" x 1/4" - 1" = 2.5'  
2.2" x 3/4" - 1" = 1.25"

PROJECT NUMBER: 28737  
SHEET NUMBER: A-2


This document contains confidential or proprietary information of Ramaker & Associates, Inc. Notice this document is to be reproduced, distributed, used or disclosed other in whole or in part except as authorized by Ramaker & Associates, Inc.




6580 SPRINT PARKWAY  
OVERLAND PARK, KANSAS 66251



**RAMAKER & ASSOCIATES, INC.**  
 1120 Dallas Street, Sauk City, WI 53583  
 Phone: 608-643-4100 Fax: 608-643-7999  
 www.Ramaker.com



48 SPRUCE STREET  
OAKLAND, NJ 07346



10/20/2014

MARK	DATE	DESCRIPTION
VALUE	FINAL	DATE
PHASE	FINAL	10/20/2014

PROJECT TITLE:  
**TRANSFER STATION  
CT33XC522-C**





PROJECT INFORMATION:  
237 GODFREY ROAD  
WESTON, CT 06883  
FAIRFIELD COUNTY

SHEET TITLE:  
**BUILDING ELEVATIONS &  
ANTENNA DETAILS**

SCALE:  
AS NOTED

NO. SHEET  
287/37

OTHER  
A-3





**RFDS Sheet**

**General Site Information**

Site ID	CT33XC522
Market	Southern Connecticut
Region	Northeast
M/LA	N/A
Structure Type	Lattice Tower
BTS Type	

Equipment Vendor	Alcatel-Lucent
Latitude	41.244386
Longitude	-73.363386
LL SITE ID	N/A

Solution ID	
-------------	--

Siteria SR Equipment type	Alcatel-Lucent
---------------------------	----------------

Incremental Power Draw needed by added Equipment

TBD
-----

**Base Equipment**

BBU Kit	ALU BBU Kit	1	None
BBU Kit Qty			N/A
Growth Cabinet			N/A
Growth Cabinet Qty			N/A
Growth Cabinet Dimensions			N/A
Growth Cabinet Weight			N/A

Top Hat	None
Top Hat Qty	N/A
Top Hat Dimensions	N/A
Top Hat Weight (lbs)	N/A

**RF Path Information**

RRH	TD-RRH820-25
RRH Qty	3
RRH Dimensions	26.1"x18.6"x6.7"
RRH Weight, lbs.	70
RRH Mount Weight, Lbs.	10
Power and Fiber Cable	ALU Hybrid
Cable Qty	1
Weight per foot, Lbs.	0.992
Diameter, Inches.	1.25
Length Ft.	209
Coax Jumper	TBD
Coax Jumper Qty	27
Coax Jumper Length, Feet.	8
Coax Jumper Weight	1.7
Coax Jumper Diameter, Inches	0.5
AISG Cable	Commscope ATCB-B01-006
AISG Cable Qty	3
AISG Diameter, Inches.	0.315
AISG Cable length.	8
Weight of entire AISG cable, Lbs.	1.3

(calculated as antenna height plus 20%)

**Antenna Sector Information**

Antenna make/model	Sector 1	Sector 2	Sector 3
Antenna qty	RFS APXV9TM14-ALU-120	RFS APXV9TM14-ALU-120	RFS APXV9TM14-ALU-120
Antenna Dimensions, inches	1	1	1
Antenna Weight, Lbs	56.3"x12.6"x6.3"	56.3"x12.6"x6.3"	56.3"x12.6"x6.3"
Antenna Mounting Kit Weight, Lbs.	55.12	55.12	55.12
CL Height	11.5	11.5	11.5
Antenna Azimuth	174	174	174
Antenna Mechanical Downtilt	340	100	220
Antenna etilt	0	0	0
	-2	-2	-2

\* RFDS SHEET WAS GENERATED BY RAMAKER & ASSOCIATES FROM PLAN OF RECORD (POR). PROVIDED BY SPRINT. CONTRACTOR SHALL VERIFY AND OBTAIN FINAL RFDS FROM SPRINT CONSTRUCTION MANAGER PRIOR TO CONSTRUCTION.

**NOTES:**

- GENERAL CONTRACTOR TO FIELD VERIFY AZIMUTH AND CL HEIGHT AND MECHANICAL DOWNTILT. IF DIFFERENT THAN CALLED OUT BELOW, CONTRACTOR SHALL WORK WITH SPRINT AND ENGINEER TO CORRECT. IF ENGINEER DOES NOT ANSWER, BUT STILL LEAVE A MESSAGE TO BE ENGINEER USING CONTACT INFORMATION PROVIDED TO CONTRACTOR, SPRINT DOES NOT RESPOND WITHIN ONE HOUR. PLACE 2.5GHZ ANTENNA AT SAME CL HEIGHT AS 1.9GHZ ANTENNA AND SWAL CORRECT CL HEIGHT. AS-BUILT DRAWINGS WITH CORRECT CL HEIGHT. ALSO SWAL CORRECT 1.9GHZ AND 200MHZ ANTENNA CL HEIGHT AND MECHANICAL DOWNTILT TO RF ENGINEER.
- ALSO TESTS TO VERIFY OPERATION IS TO BE ANTENNAS AND AISG CABLES HAVE BEEN CONNECTED. VERIFY OPERATION OF ALL EXISTING SPRINT AISG EQUIPMENT WITHIN 100 FEET OF ANTENNA. ALL TESTS TO INCLUDE COMPLETE DOWNTILT, AZIMUTH (IF APPLICABLE) AND BEAMWIDTH SWINGS (IF APPLICABLE). DOCUMENT AISG TEST RESULTS IN COAX SHEET TEST SPREADSHEET.
- GENERAL CONTRACTOR MUST INSURE THAT NO CABLES ARE PLACED IN FRONT OF ANTENNA, AND RIGHT OF FRONT OF ANTENNA OR 7 DEGREES UP AND DOWN FROM CENTER OF ANTENNA. IF THIS IS NOT POSSIBLE, CONTACT RF ENGINEER FOR FURTHER INSTRUCTIONS. ALL ANTENNAS MUST BE PLACED IN FRONT OF ANY OTHER ANTENNA USING THE SAME 45 DEGREE RULE. THIS INCLUDES SPRINT AND NON-SPRINT ANTENNAS.
- 2.5GHZ ANTENNA MUST BE AT LEAST 6' FROM 1.9GHZ ANTENNA, 30' FROM 800MHZ ANTENNA AND 30' FROM DUAL BAND 1.9GHZ AND 800MHZ ANTENNA.
- GENERAL CONTRACTOR IS REQUIRED TO USE A DIGITAL DOWNTILT ANTENNA. ALL ANTENNAS MUST BE WITHIN 1 DEGREE DOWNTILT AND ROLL (LEFT TO RIGHT TILT) IS TO BE WITHIN 0.1 DEGREES. IF FOR SOME REASON AS-BUILT DRAWINGS AND EXISTING SPRINT RF ENGINEER WITH AS-BUILT SETTINGS, USE 32 RF ALIGNMENT TOOL OR EQUIVALENT TOOL.

6580 SPRINT PARKWAY  
OVERLAND PARK, KANSAS 66251

1120 Dallas Street, Sauk City, WI 53583  
Phone: 608-643-4100 Fax: 608-643-7999  
www.Ramaker.com

48 SPRUCE STREET  
OAKLAND, NJ 07346

Certification & Seal  
James P. Skowronski, P.E.  
Professional Engineer under the laws of the State of Connecticut  
No. 28286  
10/20/2014



MARK	DATE	DESCRIPTION
ISSUE	FINAL	
PHASE	DESIGN	
DATE	10/20/2014	




**TRANSFER STATION**  
CT33XC522-C

PROJECT INFORMATION:  
237 GODFREY ROAD  
WESTON, CT 06893  
FAIRFIELD COUNTY


SHEET TITLE:  
RF DATA SHEET

SCALE:  
AS NOTED


PROJECT NUMBER: 28737  
SHEET NUMBER: A-4




1 TYPICAL FIBER DISTRIBUTION BOX DETAIL  
SCALE: NTS



3 8T8R DETAIL  
SCALE: NTS



4 BT5 TO DISTRIBUTION BOX FIBER CONNECTIVITY DETAIL  
SCALE: NTS



5 RRH TO DISTRIBUTION BOX FIBER CONNECTIVITY DETAIL  
SCALE: NTS

**Sprint**  
 6580 SPRINT PARKWAY  
 OVERLAND PARK, KANSAS 66251

**RAMAKER & ASSOCIATES, INC.**  
 1120 Dallas Street, Sauk City, WI 53583  
 Phone: 608-643-4100 Fax: 608-643-7999  
 www.Ramaker.com

**Transcend Wireless**  
 48 SPRUCE STREET  
 OAKLAND, NJ 07346

Confirmation: State of Connecticut, No. 28286, Professional Engineer, James P. Skowronski, License No. 28286, dated 10/20/2014.  
 I, *James P. Skowronski*, Professional Engineer, No. 28286, State of Connecticut, hereby certify that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



MARK	DATE	DESCRIPTION
ISSUE	FINAL	
DATE	10/20/2014	

PROJECT TITLE:  
**TRANSFER STATION**  
**CT33XC522-C**

PROJECT INFORMATION:  
 237 GODFREY ROAD  
 WESTON, CT 06893  
 FAIRFIELD COUNTY

SHEET TITLE:  
**FIBER PLUMBING DIAGRAM**

SCALE:  
**A5 NOTED**



OTHER NUMBER:  
**28737**

REVISION:  
**A-5**

Sector	Cable	First Ring	Second Ring	Third Ring
1 Alpha	1	Green	No Tape	No Tape
	2	Blue	No Tape	No Tape
	3	Brown	No Tape	No Tape
	4	White	No Tape	No Tape
	5	Red	No Tape	No Tape
	6	Grey	No Tape	No Tape
	7	Purple	No Tape	No Tape
	8	Orange	No Tape	No Tape
2 Beta	1	Green	Green	No Tape
	2	Blue	Blue	No Tape
	3	Brown	Brown	No Tape
	4	White	White	No Tape
	5	Red	Red	No Tape
	6	Grey	Grey	No Tape
	7	Purple	Purple	No Tape
	8	Orange	Orange	No Tape
3 Gamma	1	Green	Green	Green
	2	Blue	Blue	Blue
	3	Brown	Brown	Brown
	4	White	White	White
	5	Red	Red	Red
	6	Grey	Grey	Grey
	7	Purple	Purple	Purple
	8	Orange	Orange	Orange

2-5 FREQUENCY	INDICATOR	ID
2500 -1	YEL	WHT
2500 -2	YEL	WHT
2500 -3	YEL	WHT
2500 -4	YEL	WHT
2500 -5	YEL	WHT
2500 -6	YEL	WHT
2500 -7	YEL	WHT
2500 -8	YEL	WHT

NV FREQUENCY	INDICATOR	ID
800-1	YEL	GRN
1900-1	YEL	RED
1900-2	YEL	BRN
1900-3	YEL	BLU
1900-4	YEL	SLT
800-1	YEL	ORG
RESERVED	YEL	WHT
RESERVED	YEL	PPL



COLOR CODING CHARTS  
 SCALE: 1/8" = 1'-0"

**CABLE MARKING NOTES**

1. ALL CABLES SHALL BE MARKED WITH 2" WIDE, UV STABILIZED, UL APPROVED TAPE.
2. THE FIRST RING SHALL BE CLOSEST TO THE END OF THE CABLE. THE SECOND RING SHALL BE AT THE END CONNECTOR, WEATHERPROOFING, OR BREAKOUT UNIT. THERE SHALL BE 1" SPACE BETWEEN EACH RING.
3. A 2" GAP SHALL SEPARATE THE CABLE COLOR CODE FROM THE FREQUENCY COLOR CODE. THE 2" GAP SHALL BE MARKED WITH TAPE. THE TAPE SHALL BE PLACED NEXT TO EACH OTHER WITH NO SPACES.
4. THE 2" COLORED TUBES SHALL BE MARKED A MINIMUM OF 3" TIMES AROUND THE INDIVIDUAL CABLES AND THE TAPE SHALL BE KEPT IN THE SAME LOCATION AS MUCH AS POSSIBLE.
5. SITES WITH MORE THAN FOUR (4) SECTORS WILL REQUIRE ADDITIONAL RINGS FOR EACH SECTOR. ADDITIONAL RINGS SHALL BE KEPT IN THE SAME LOCATION AS MUCH AS POSSIBLE. THE TAPE WILL USE THE SECOND CABLE IDENTIFIED BY BLUE BANDS OF TAPE.
6. HYBRID FIBER CABLE SHALL BE SECTOR IDENTIFIED INSIDE THE CABINET ON FREQUENCY BUNDLES ON THE SEALTITE, ON THE MAIN LINE UPON EXIT OF THE CABINET, AND ON THE MAIN LINE UPON EXIT OF THE MAINLINE AS WELL AS BEFORE AND AFTER ANY ENTRANCE OR EXIT.
7. HFC MAIN TRUNKS WILL NOT BE MARKED WITH THE FREQUENCY CODES, AS IT CONTAINS ALL FREQUENCIES.
8. INDIVIDUAL POWER PABS AND FIBER BUNDLES SHALL BE LABELED WITH BOTH THE CABLE AND FREQUENCY.

6580 SPRINT PARKWAY  
 OVERLAND PARK, KANSAS 66251

1120 Dallas Street, Sauk City, WI 53583  
 Phone: 608-643-4100 Fax: 608-643-7999  
 www.Ramaker.com

48 SPRUCE STREET  
 OAKLAND, NJ 07346

Certification & State  
 James P. Skowronski, No. 28286  
 PROFESSIONAL ENGINEER  
 STATE OF CONNECTICUT  
 10/20/2014

MARK	DATE	DESCRIPTION
ISSUE	FINAL	DATE ISSUED: 10/20/2014
PHASE		PROJECT TITLE:

**TRANSFER STATION**  
**CT33XC522-C**

PROJECT INFORMATION:  
 237 GODFREY ROAD  
 WESTON, CT 06883  
 FAIRFIELD COUNTY

SHEET TITLE:  
 CABLE COLOR CODING

SCALE:  
 AS NOTED

NO. OF SHEETS:  
 28737

SHEET NUMBER:  
 A-6



**Sprint**  
 6580 SPRINT PARKWAY  
 OVERLAND PARK, KANSAS 66251



**RAMAKER & ASSOCIATES, INC.**  
 1120 Dallas Street, Sauk City, WI 53583  
 Phone: 608-643-4100 Fax: 608-643-7999  
 www.Ramaker.com



**Transcend Wireless**  
 48 SPRUCE STREET  
 OAKLAND, NJ 07346

Certification & Seal: This is the official seal of the Professional Engineer, James P. Skowronski, No. 28286, State of Connecticut. It is valid only when used by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



*James P. Skowronski*  
 10/20/2014

MARK	DATE	DESCRIPTION
ISSUE	FINAL	DATE ISSUED: 10/20/2014
PHASE		

**TRANSFER STATION**  
**CT33XC522-C**

PROJECT INFORMATION:  
 237 GODFREY ROAD  
 WESTON, CT 06883  
 FAIRFIELD COUNTY

SHEET TITLE:  
**ANTENNA & HYBRID CABLE**  
**DETAILS**


SCALE:  
 AS NOTED

OTHER NUMBER  
 28737


A-7

**RF5: APXV9TM I 4-ALU- I 20**

DIMENSIONS, HW&D: 56.3" x 1.2" x 6.3"  
 WEIGHT, WITHOUT PRE-MOUNTED BRACKETS: 55.12 lbs.  
 CONNECTOR: (9) MINI-DIN FEMALE/BOTTOM



**2.5 ANTENNA DETAIL**  
 SCALE: NTS



**2.5 RRH DETAIL**  
 SCALE: NTS

ALCATEL-LUCENT: TD-RRHx20  
 HW&D = 26.1" x 1.9" x 6.7"  
 WEIGHT = 70 lbs.

**HYBRID CABLE DC CONDUCTOR SIZE GUIDELINE**


CABLE	LENGTH	DC CONDUCTOR	CABLE DIAMETER
Hybrid	200'	3x 16 AWG	1.140"
Hybrid	250-300'	6 AWG	1.140"
Hybrid	300-375'	4 AWG	1.140"

**RF5 HYBRID/FIBER CABLE SCHEDULE**

POWER	DESCRIPTION	LENGTH	CONDUCTOR	DIAMETER
FIBER ONLY (EXISTING DC POWER)	MN-HB14-0813M-12-09FP	50 ft	12 CHANNEL FIBER DIST.	0.91
	Bentail LC	50 cable, 50 ft		0.91
	MN-HB14-0813M-12-09FP	75 ft	12 CHANNEL FIBER DIST.	0.91
	MN-HB14-0813M-12-09FP	100 ft	12 CHANNEL FIBER DIST.	0.91
	MN-HB14-0813M-12-09FP	125 ft	12 CHANNEL FIBER DIST.	0.91
	MN-HB14-0813M-12-09FP	150 ft	12 CHANNEL FIBER DIST.	0.91
4 AWG POWER	MN-HB14-0813M-12-09FP	175 ft	4 AWG	0.91
	MN-HB14-0813M-12-09FP	200 ft	4 AWG	0.91
	MN-HB14-0813M-12-09FP	225 ft	4 AWG	0.91
	MN-HB14-0813M-12-09FP	250 ft	4 AWG	0.91
	MN-HB14-0813M-12-09FP	275 ft	4 AWG	0.91
	MN-HB14-0813M-12-09FP	300 ft	4 AWG	0.91
6 AWG POWER	MN-HB14-0813M-12-09FP	325 ft	6 AWG	0.91
	MN-HB14-0813M-12-09FP	350 ft	6 AWG	0.91
	MN-HB14-0813M-12-09FP	375 ft	6 AWG	0.91
	MN-HB14-0813M-12-09FP	400 ft	6 AWG	0.91
	MN-HB14-0813M-12-09FP	425 ft	6 AWG	0.91
	MN-HB14-0813M-12-09FP	450 ft	6 AWG	0.91

**RF5 HYBRID/FIBER CABLE SCHEDULE**

POWER	DESCRIPTION	LENGTH	CONDUCTOR	DIAMETER
FIBER ONLY	MN-HB14-0813M-12-09FP	50 ft	12 CHANNEL FIBER DIST.	0.91
	Bentail LC	50 cable, 50 ft		0.91
	MN-HB14-0813M-12-09FP	75 ft	12 CHANNEL FIBER DIST.	0.91
	MN-HB14-0813M-12-09FP	100 ft	12 CHANNEL FIBER DIST.	0.91
	MN-HB14-0813M-12-09FP	125 ft	12 CHANNEL FIBER DIST.	0.91
	MN-HB14-0813M-12-09FP	150 ft	12 CHANNEL FIBER DIST.	0.91
4 AWG POWER	MN-HB14-0813M-12-09FP	175 ft	4 AWG	0.91
	MN-HB14-0813M-12-09FP	200 ft	4 AWG	0.91
	MN-HB14-0813M-12-09FP	225 ft	4 AWG	0.91
	MN-HB14-0813M-12-09FP	250 ft	4 AWG	0.91
	MN-HB14-0813M-12-09FP	275 ft	4 AWG	0.91
	MN-HB14-0813M-12-09FP	300 ft	4 AWG	0.91
6 AWG POWER	MN-HB14-0813M-12-09FP	325 ft	6 AWG	0.91
	MN-HB14-0813M-12-09FP	350 ft	6 AWG	0.91
	MN-HB14-0813M-12-09FP	375 ft	6 AWG	0.91
	MN-HB14-0813M-12-09FP	400 ft	6 AWG	0.91
	MN-HB14-0813M-12-09FP	425 ft	6 AWG	0.91
	MN-HB14-0813M-12-09FP	450 ft	6 AWG	0.91




**2.5 ANTENNA DETAIL**  
 SCALE: NTS

**2.5 RRH DETAIL**  
 SCALE: NTS

\*NOTE: SPRINT CM TO CONFIRM HYBRID/FIBER RISER CABLE & HYBRID/FIBER JUMPER CABLE MODEL NUMBERS BEFORE PREPARING BOM.


**HYBRID CABLE CROSS SECTION #**  
 SCALE: NTS



HYBRID BREAKOUT DETAIL  
SCALE: NTS



EXISTING BBU CABINET  
SCALE: NTS



CABLE ROUTE FROM CABINET  
SCALE: NTS

MARK	DATE	DESCRIPTION	DATE ISSUED
VALUE	FINAL		10/20/2014
PHASE			

PROJECT TITLE:  
**TRANSFER STATION  
 CT33XC522-C**

PROJECT INFORMATION:  
 237 GODFREY ROAD  
 WESTON, CT 06883  
 FAIRFIELD COUNTY

SHEET TITLE:  
**EQUIPMENT DETAILS**

SCALE:  
 AS NOTED

PROJECT NUMBER:  
 28737

SHEET NUMBER:  
 A-8

EXISTING MMBS CABINET  
SCALE: NTS

6580 SPRINT PARKWAY  
 OVERLAND PARK, KANSAS 66251

1120 Dallas Street, Sauk City, WI 53583  
 Phone: 608-643-4100 Fax: 608-643-7999  
 www.Ramaker.com


48 SPRUCE STREET  
 OAKLAND, NJ 07346

Certification & State: **Professional Engineer** in the State of Connecticut  
 License No. 28286  
 Date: 10/20/2014

James P. Stewart








- NOTES:
- CONTRACTOR SHALL BE RESPONSIBLE FOR STABILITY OF THE TOWER DURING CONSTRUCTION.
  - ALL PROPOSED STEEL SHALL BE HOT DIPPED GALVANIZED.
  - ALL PROPOSED DIAGONAL MEMBERS HORIZONTAL MEMBERS, AND PLATES SHALL BE ASTM A36 STEEL, OR APPROVED EQUAL.
  - ALL PROPOSED LEG REINFORCEMENT ANGLES SHALL BE ASTM A572-50 STEEL, OR APPROVED EQUAL.
  - ALL PROPOSED BOLTS SHALL BE ASTM A325-X BOLTS (UNO). CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING BOLT THREADS ARE NOT IN SHEAR PLANE OF CONNECTION.

MODIFIED TOWER ELEVATION (1)  
 SCALE: 1" = 25'

ELEVATION	REPLACEMENT DIAGONAL SIZE	MINIMUM END CONNECTION END DISTANCE
0' - 20'	1.3 1/2" x 3 1/2" x 3/8"	1 1/2"
40' - 60'	1.3" x 3" x 3/8"	1 1/2"
80' - 100'	1.2 1/2" x 2 1/2" x 3/8"	1 1/2"
140' - 180'	1.2" x 2" x 1/4"	1 1/4"

NOTES:

- REPLACE ALL EXISTING DIAGONAL BOLTS WITH NEW A325-X BOLTS OF SAME DIAMETER
- DO NOT REUSE EXISTING BOLTS



REPLACEMENT DIAGONAL INFORMATION (2)  
 SCALE: NTS

6580 SPRINT PARKWAY  
 OVERLAND PARK, KANSAS 66251

1120 Dallas Street, Sauk City, WI 53583  
 Phone: 608-643-4100 Fax: 608-643-7999  
 www.Ramaker.com

48 SPRUCE STREET  
 OAKLAND, NJ 07346

Continuation of State License No. 28286, State of Connecticut, Professional Engineer, James P. Skowronski, No. 28286, dated 10/20/2014.

James P. Skowronski  
 10/20/2014

MARK	DATE	DESCRIPTION
ISSUE	FINAL	DATE ISSUED
PHASE		10/20/2014


TRANSFER STATION  
 CT33XC522-C

PROJECT INFORMATION:  
 237 GODFREY ROAD  
 WESTON, CT 06883  
 FAIRFIELD COUNTY


SHEET TITLE:  
 STRUCTURAL DETAILS

SCALE:  
 AS NOTED


TOWER NUMBER	28737
SHEET NUMBER	S-1



6580 SPRINT PARKWAY  
OVERLAND PARK, KANSAS 66251




**RAMAKER & ASSOCIATES, INC.**  
1120 Dallas Street, Sauk City, WI 53583  
Phone: 608-643-4100 Fax: 608-643-7999  
www.Ramaker.com



48 SPRUCE STREET  
OAKLAND, NJ 07346

Certification & Seal: This Seal is the property of the State of Connecticut. It is to be used only by the holder of the seal and is not to be reproduced, distributed, used or disclosed other in whole or in part except as authorized by Ramaker and Associates, Inc.



*James Skowronski*  
Professional Engineer  
10/20/2014

MARK	DATE	DESCRIPTION
ISSUE	FINAL	10/20/2014
PROJECT TITLE:		


**TRANSFER STATION**  
CT33XC522-C

PROJECT INFORMATION:  
237 GODFREY ROAD  
WESTON, CT 06893  
FAIRFIELD COUNTY


SHEET TITLE:  
STRUCTURAL DETAILS

SCALE:  
AS NOTED

PROJECT NUMBER: 28737  
SHEET NUMBER: 5-2



PLAN VIEW






ELEVATION VIEW

**NOTE:**  
REFER TO TABLE IN THIS DETAIL FOR REQUIRED SIZES OF SECONDARY HORIZONTALS AND BOLT ASSEMBLIES.

ELEVATION	PROPOSED SECONDARY HORIZONTAL	BOLT SIZE
1-40 - 1.60' AGL	L2 x 2 x 4	3/8" DIA.

TYP. SECONDARY HORIZONTAL ASSEMBLY ①  
SCALE: NTS



6580 SPRINT PARKWAY  
 OVERLAND PARK, KANSAS 66251

**RAMAKER & ASSOCIATES, INC.**  
 1120 Dallas Street, Sauk City, WI 53583  
 Phone: 608-643-4100 Fax: 608-643-7999  
 www.Ramaker.com

48 SPRUCE STREET  
 OAKLAND, NJ 07346

Confirmation & Seal: I, James P. Skowronski, hereby certify that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.

James P. Skowronski  
 10/20/2014  
 DATE

MARK	DATE	DESCRIPTION
VALUE	FINAL	DATE
PHASE		ISSUED

PROJECT TITLE: TRANSFER STATION CT33XC522-C

PROJECT INFORMATION:  
 237 GODFREY ROAD  
 WESTON, CT 06893  
 FAIRFIELD COUNTY

SHEET TITLE: STRUCTURAL DETAILS

SCALE: AS NOTED

NUMBER OF SHEETS: 287/37

SHEET NUMBER: 5-3



6580 SPRINT PARKWAY  
OVERLAND PARK, KANSAS 66251



1120 Dallas Street, Sauk City, WI 53583  
Phone: 608-643-4100 Fax: 608-643-7999  
www.Ramaker.com



48 SPRUCE STREET  
OAKLAND, NJ 07346

Continuation Sheet  
 This drawing shall not be used without the approval of the Engineer by whom it was prepared and shall not be used for any other project without the approval of the Professional Engineer under the laws of the State of Connecticut.



James P. Skowronski  
Professional Engineer  
10/20/2014

MARK	DATE	DESCRIPTION
VALUE	FINAL	10/20/2014
PHASE		


**TRANSFER STATION**  
CT33XC522-C

PROJECT INFORMATION:  
237 GODFREY ROAD  
WESTON, CT 06893  
FAIRFIELD COUNTY


SHEET TITLE:  
**STRUCTURAL DETAILS**

SCALE:  
AS NOTED



PROJECT NUMBER: 28737  
SHEET NUMBER: 5-4



MODIFIED FOUNDATION SECTION 2  
SCALE: 1" = 7.5'



MODIFIED FOUNDATION PLAN 1  
SCALE: 1" = 7.5'



**GROUNDING NOTES:**

- CONTRACTOR TO ENSURE PROPER SEQUENCING OF GROUNDING AND UNDERGROUND CONDUIT INSTALLATION TO PREVENT ANY LOSS OF CONTINUITY IN THE GROUNDING SYSTEM AND/OR DAMAGE TO THE CONDUIT.
- ALL EXTERIOR GROUND CONDUCTORS SHALL BE #2 AWG SOLID TINNED COPPER.
- ALL GROUNDING CONNECTIONS SHALL BE MADE WITH #2 AWG SOLID TINNED COPPER.
- ALL GROUND CONNECTIONS BELOW GRADE SHALL BE PROTECTIVE (GALVANIZED).
- ALL GROUND CONNECTIONS ABOVE GRADE AND/OR INTERIOR SHALL BE COMPRESSION TYPE, TWO-HOLE LUGS OR DOUBLE-CRIMP "C" TAPS.
- ALL GROUNDING CONNECTIONS SHALL BE PREPARED TO A BARE BRASS FINISH AND COATED WITH AN ANTI-OXIDATION MATERIAL BEFORE CONNECTIONS ARE MADE.
- MAXIMUM RESISTANCE OF THE COMPLETED GROUND SYSTEM SHALL NOT EXCEED 5 OHMS.
- WHERE GROUNDING CONNECTIONS ARE MADE TO PAINTED METAL SURFACES, PAINT SHALL BE REMOVED TO BARE METAL TO ENSURE PROPER CONTACT AND RESTORED/PAINTE TO ORIGINAL FINISH.
- GROUND DEPTH SHALL BE 30" MINIMUM BELOW FINISHED GRADE, OR 6" BELOW FROST LINE, WHICHEVER IS GREATER.

**LEGEND:**

---	EXISTING GROUND CABLE
- - - - -	PROPOSED GROUND CABLE
▲	MECHANICAL CONNECTION
■	DIATHERMIC CONNECTION
---	PROPOSED ELECTRIC

6580 SPRINT PARKWAY  
OVERLAND PARK, KANSAS 66251

1120 Dallas Street, Sauk City, WI 53583  
Phone: 608-643-4100 Fax: 608-643-7999  
www.Ramaker.com

48 SPRUCE STREET  
OAKLAND, NJ 07346

Continuation of State of Connecticut Professional Engineer License No. 28286  
 James P. Skowronski  
 10/20/2014  
 DATE ISSUED

MARK	DATE	DESCRIPTION
ISSUE	FINAL	10/20/2014
PHASE	FINAL	
PROJECT TITLE:		
TRANSFER STATION CT33XC522-C		
PROJECT INFORMATION:		
237 GODFREY ROAD WESTON, CT 06893 FAIRFIELD COUNTY		
SHEET TITLE:		
EQUIPMENT UTILITY & GROUNDING PLAN		
SCALE:		
AS NOTED		
PROJECT NUMBER	28737	
SHEET NUMBER	E-1	



6580 SPRINT PARKWAY  
OVERLAND PARK, KANSAS 66251



1120 Dallas Street, Sauk City, WI 53583  
Phone: 608-643-4100 Fax: 608-643-7999  
www.Ramaker.com



48 SPRUCE STREET  
OAKLAND, NJ 07346

Confirmation & Seal: This Seal is valid only when the information herein is reproduced, distributed, used or disclosed other in whole or in part except as authorized by Ramaker and Associates, Inc. by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



James P. Skowronski  
10/20/2014

MARK	DATE	DESCRIPTION
ISSUE	FINAL	DATE ISSUED: 10/20/2014
PHASE		PROJECT TITLE:




**TRANSFER STATION**  
CT33XC522-C


PROJECT INFORMATION:  
237 GODFREY ROAD  
WESTON, CT 06893  
FAIRFIELD COUNTY

SHEET TITLE:  
GROUNDING DETAILS

SCALE:  
AS NOTED

DATE PLOTTED: 10/20/2014  
DRAWN BY: TWS  
CHECKED BY: KMB







**A/C PANEL SCHEDULE**

VOLTAGE:	240V/120	EXISTING	N TO GROUND BOND:	YES
MAIN BREAKER:	200 AMP	TBD	INTERNAL TYS:	YES
MOUNT:	GROUND	1	WIRE:	3
ENCLOSURE TYPE:	NEMA 3R	200 AMP	GROUND BAR:	YES

Ckt	DESCRIPTION	BREAKER AMPS	BREAKER POLES	PHASE A/V/A	BREAKER STATUS	BREAKER POLES	BREAKER AMPS	DESCRIPTION	Ckt
1	SURGE ARRESTOR	20	2	ON	OFF	2	30	RECTIFIER #2	2
3								RECTIFIER #4	4
5	RECTIFIER #1	30	2	OFF	OFF	2	30	RECTIFIER #6	6
7								RECTIFIER #8	8
9	RECTIFIER #3	30	2	OFF	OFF	2	30	RECTIFIER #10	10
11								RECTIFIER #12	12
13	RECTIFIER #5	30	2	OFF	OFF	2	30	RECTIFIER #14	14
15								RECTIFIER #16	16
17	RECTIFIER #7	30	2	OFF	OFF	2	30	RECTIFIER #18	18
19								RECTIFIER #20	20
21	RECTIFIER #9 SPARE	30	2	OFF	ON	2	50	HVAC #2	22
23									24
25	HVAC #1	50	2	ON	ON	2	100	BTS	26
27									28
29	HVAC #3 SPARE	35	2	OFF	ON	1	20	LIGHTING	30
31									32
33	RECEPTACLE	20	1	OFF	OFF	2	40	SMOKE DETECTOR	34
35	RECEPTACLE	20	1	OFF	ON	1	20	BTS	36
37	RECEPTACLE	20	1	OFF	ON	1	20	EXT. RECEPTACLE	38
39	RECEPTACLE	20	1	OFF	ON	1	20	RECEPTACLE	40
41	BLANK (UNUSED)	-	-	-	-	-	-	BLANK (UNUSED)	42



6580 SPRINT PARKWAY  
OVERLAND PARK, KANSAS 66251

1120 Dallas Street, Sauk City, WI 53583  
Phone: 608-643-4100 Fax: 608-643-7999  
www.Ramaker.com

48 SPRUCE STREET  
OAKLAND, NJ 07346

Professional Engineer under the laws of the State of Connecticut.

10/20/2014

DATE

10/20/2014

DATE

**TRANSFER STATION**  
**CT33XC522-C**

PROJECT INFORMATION:  
237 GODFREY ROAD  
WESTON, CT 06883  
FAIRFIELD COUNTY

SHEET TITLE:  
DC POWER DETAILS  
# PANEL SCHEDULES

SCALE:  
AS NOTED

OTHER NUMBER:  
28737

SCALE: NTS

SCALE: NTS