



1280 Route 46 West, Suite 9, Parsippany NJ, 07054

Ms. Melanie Bachman  
Executive Director  
CT Siting Council  
10 Franklin Square  
New Britain, CT 06051

Re: Notice of Exempt Modification Application  
237 Godfrey Road, Weston, CT 06883

October 30, 2017

Dear Ms. Bachman:

Sprint Spectrum Realty Company, L.P. ("Sprint"), is submitting to the Connecticut Siting Council for a Notice of Exempt Modification for Proposed Modifications to an Existing Telecommunications Facility located at the above-referenced site. Sprint currently maintains 3 existing panel antenna and 6 remote radio units at the 174' level of the Tower. Sprint proposes to add 3 panel antennas (1 per sector) and 3 remote radio units (1 per sector) at 174' tower level as well as 1 hybrid cable and 27 Antenna-RRH jumper cables, new battery string in existing ground based battery cabinet and new 2.5 equipment in existing radio cabinet.

The Sprint installation was initially approved on 7/28/2006 by the CT Siting Council and a BP was issued by the Town of Weston on 10/24/2006. The documents enclosed reflect the reality of the current installations on the Tower.

If you have any questions, please feel free to contact me.

Thank you,

By: *Paul F. Sagristano*

Paul F. Sagristano  
Cherundolo Consulting  
917.841.0247  
[psagristano@lrivassoc.com](mailto:psagristano@lrivassoc.com)



1280 Route 46 West, Suite 9, Parsippany NJ, 07054

Ms. Melanie Bachman  
Executive Director  
CT Siting Council  
10 Franklin Square  
New Britain, CT 06051

Re: Notice of Exempt Modification Application  
237 Godfrey Road Road, Weston CT 06883

Latitude : N41.3680  
Longitude: W72.8093

Dear Ms. Bachman:

Sprint currently maintains 3 existing panel antenna and 6 remote radio units at the 174' centerline level of the existing monopole. Sprint proposes to add 3 panel antenna and 3 remote radio unit at 174' centerline on the tower. Sprint further proposes to add 1 hybrid cable, 27 Antenna to RRH jumper cables, a new 2.5 radio equipment in the existing ground based radio cabinet, and a new battery string the existing ground based battery cabinet. Sprint is performing a new high-performance upgrade for cellular mobile communications. It is designed to increase the capacity and speed of mobile telephone networks.

The original CT Siting Council approval for a Tower Share was approved July 28, 2006. The original building permit was issued by Weston on October 24, 2006.

Please accept this letter as notification to the Council, pursuant to R.C.S.A. Section 16-50j-73, for construction which constitutes an exempt modification pursuant to R.C.S.A. Section 16-50j-72(b)(2). In compliance with R.C.S.A. Section 16-50j-73, a copy of this letter is being sent to and to Jonathan Ruiz, Town Manager for Weston as well as James Pjura, Zoning Enforcement official for the Town Weston. This tower is owned by the Town of Weston

Attached is a summary of the planned modifications, including power density calculations reflecting the change in Sprint's operations at the site. Also included is documentation of the structural sufficiency of the tower with proposed modifications to accommodate the revised antenna configuration.

### **Existing Facility**

The Northford facility is located at 237 Godfrey Road, and is owned by The Town of Weston, the Site coordinates are: N41.24438, W73.36338.

The existing facility consists of a 185' Self Support Lattice Tower. Sprint currently operates wireless communications equipment on a platform on a concrete slab at the facility and has 3 antennas and 3 RRU's mounted on at a centerline of 174' feet.

### **Statutory Considerations**

The planned modifications to the facility fall within the activities explicitly provided for in R.C.S.A. 16-50j-72(b)(2)

1. The height of the overall structure will be unaffected.
2. The proposed changes will not require an extension of the property boundaries.
3. The proposed additions will not increase the noise level at the existing facility by six decibels or more, or to levels that exceed state and/or local criteria
4. The changes will not increase the calculated "worst case" power density for the combined operations at the site to a level at or above the Federal Communications Commission safety standard.
5. The proposed modifications will not cause a change or alteration in the physical or environmental characteristics of the site.
6. The existing structure and its foundation can support the proposed loading.

For the foregoing reasons, Sprint respectfully submits that the proposed changes at the referenced site constitute exempt modifications under R.C.S.A Section §16-50j-72(b)(2).

Respectfully submitted,

*Paul F. Sagristano*

Paul F. Sagristano  
Charles Cherundolo Consulting  
917-841-0247  
[psagristano@lrvassoc.com](mailto:psagristano@lrvassoc.com)

PFS/mtf

Additional Recipients:

Jonathan Ruiz, Town Administrator for Weston – Via Fed Ex  
James Pjura, Zoning Enforcement official Town of Weston - Via Fed Ex



November 2, 2017

Dear Customer:

The following is the proof-of-delivery for tracking number **770631594362**.

---

**Delivery Information:**

<b>Status:</b>	Delivered	<b>Delivered to:</b>	Receptionist/Front Desk
<b>Signed for by:</b>	D.ANASTASIA	<b>Delivery location:</b>	56 NORFIELD RD WESTON, CT 06883
<b>Service type:</b>	FedEx Express Saver	<b>Delivery date:</b>	Nov 2, 2017 12:24
<b>Special Handling:</b>	Deliver Weekday  Direct Signature Required		



---

**Shipping Information:**

<b>Tracking number:</b>	770631594362	<b>Ship date:</b>	Oct 31, 2017
		<b>Weight:</b>	2.0 lbs/0.9 kg

**Recipient:**  
Nina Daniel 1st Selectman  
Town of Weston  
56 Norfield Road  
WESTON, CT 06883 US

**Shipper:**  
Paul Sagristano  
CCC  
4 Davis Road West  
Suite 5  
OLD LYME, CT 06371 US  
CT33XC522 CSC to 1st Selectman

**Reference**

Thank you for choosing FedEx.



November 2, 2017

Dear Customer:

The following is the proof-of-delivery for tracking number **770631563180**.

---

**Delivery Information:**

<b>Status:</b>	Delivered	<b>Delivered to:</b>	Receptionist/Front Desk
<b>Signed for by:</b>	D.ANASTASIA	<b>Delivery location:</b>	56 NORFIELD RD WESTON, CT 06883
<b>Service type:</b>	FedEx Express Saver	<b>Delivery date:</b>	Nov 2, 2017 12:24
<b>Special Handling:</b>	Deliver Weekday  Direct Signature Required		



---

**Shipping Information:**

<b>Tracking number:</b>	770631563180	<b>Ship date:</b>	Oct 31, 2017
		<b>Weight:</b>	2.0 lbs/0.9 kg

**Recipient:**  
James Pjura, ZEO  
Town of Weston  
56 Norfield Road  
WESTON, CT 06883 US

**Shipper:**  
Paul Sagristano  
CCC  
4 Davis Road West  
Suite 5  
OLD LYME, CT 06371 US  
CT33XC522 CSC to ZEO

**Reference**

Thank you for choosing FedEx.



November 2, 2017

Dear Customer:

The following is the proof-of-delivery for tracking number **770631514928**.

---

**Delivery Information:**

<b>Status:</b>	Delivered	<b>Delivered to:</b>	Receptionist/Front Desk
<b>Signed for by:</b>	D.ANASTASIA	<b>Delivery location:</b>	56 NORFIELD RD WESTON, CT 06883
<b>Service type:</b>	FedEx Express Saver	<b>Delivery date:</b>	Nov 2, 2017 12:24
<b>Special Handling:</b>	Deliver Weekday  Direct Signature Required		



---

**Shipping Information:**


<b>Tracking number:</b>	770631514928	<b>Ship date:</b>	Oct 31, 2017
		<b>Weight:</b>	2.0 lbs/0.9 kg

**Recipient:**  
Jonathan Ruiz, Town Admin  
Town of Weston  
56 Norfield Road  
WESTON, CT 06883 US


**Shipper:**  
Paul Sagristano  
CCC  
4 Davis Road West  
Suite 5  
OLD LYME, CT 06371 US  
CT33XC522 CSC to Town Admin

**Reference**

Thank you for choosing FedEx.



TAX MAP  
TOWN OF  
**WESTON, CONNECTICUT**  
SCALE: 1"=200' JAN. 5, 1988  
COMPILED FROM MAPS OF RECORD, 1988  
PREPARED BY B.G. ROOT, SURVEYOR—WESTPORT, CONN.



SHEET 16





# Town of Weston, CT

[Recent Sales in Neighborhood](#)
[Previous Parcel](#)
[Next Parcel](#)
[Field Definitions](#)
[Return to Main Search](#)
[Weston Home](#)

### Owner and Parcel Information

<b>Owner Name</b>	TOWN OF WESTON LANDFILL/TRANSFER STATION	<b>Today's Date</b>	October 31, 2017
<b>Mailing Address</b>	237 GODFREY RD WESTON, CT 06883	<b>Parcel ID</b>	13105 (Account #: E00131)
<b>Location Address</b>	237 GODFREY ROAD	<b>Map/Block/Lot</b>	16/1/35
<b>Subdivision Map / Lot</b>	1957 /	<b>Acreage</b>	57.35
<b>Use Class / Description</b>	901 Municipal	<b>Subdivision</b>	

### Current Appraised Value Information

Building Value	XF Value	OB Value	Land Value	Special Land Value	Total Appraised Value	Net Appraised Value	Current Assessment
\$ 27,300	\$ 0	\$ 71,800	\$ 2,007,000		\$ 2,106,100	\$ 2,106,100	\$ 1,474,400

### Assessment History

Year	Building	OB/Misc	Land	Total Assessment
2016	\$ 19,100	\$ 50,400	\$ 1,404,900	\$ 1,474,400
2015	\$ 19,100	\$ 50,400	\$ 1,404,900	\$ 1,474,400
2014	\$ 19,100	\$ 50,400	\$ 1,404,900	\$ 1,474,400

### Land Information

Use	Class	Area	Value
Municipal	E	2 AC	\$ 900,000
Municipal	E	55.35 AC	\$ 1,107,000


### Commercial Building Information

Style	Year Built	Eff Year Built	Gross Area	Stories	Grade	Exterior Wall	Interior Wall	Wall Height	# Units
Warehouse	1980	2002	726	1	C	Concrete	Minimum	10	0
Roof Cover	Roof Structure	Floor Type	Heat Type	Heat Fuel	AC Type	Sprinkler	Construction	Plumbing	Comm Walls
Asphalt Shingl	Gable	Concr Abv Grad	Oil	Forced Air	Heat/AC Split	%	Reinforced Cnc	Light	0%

#### Building Sub Areas

Code	Description	Living Area	Gross Area
BAS	First Floor	220	220
FGR	Garage	0	506
<b>Totals</b>		<b>220</b>	<b>726</b>

#### Building Sketch [Enlarge](#)



#### Building Photo [Enlarge](#)



### Out Buildings / Extra Features

Description	Sub Description	Area	Year Built	Value
Garage	Masonry	912 S.F.	1992	\$ 21,500
Studio/Office		207 S.F.	1980	\$ 12,400
Shed		460 S.F.	1980	\$ 2,800
Shed		676 S.F.	1980	\$ 3,000
Shed		288 S.F.	1980	\$ 1,300
Paving Asph.		19,000 S.F.	1980	\$ 30,800



Sale Information						
Sale Date	Sale Price	Deed Book/Page	Sale Qualification	Reason	Vacant or Improved	Owner
00/00/0000		74/ 498				TOWN OF WESTON LANDFILL/TRANSFER STATION

Permit Information								
Permit ID	Issue Date	Type	Description	Amount	Inspection Date	% Complete	Date Complete	Comments
7891	04/17/2017			\$ 23,500		100		ADD 3 ANTENNA
7486	11/24/2014			\$ 25,000	04/30/2015	100	12/15/2014	SEE PERMIT
7293	06/03/2014			\$ 25,000	12/24/2014	100	08/01/2014	ANTENNAS
7392	06/03/2014			\$ 10,000	12/24/2014	100	08/01/2014	ANTENNAS & FIBER CABLE
7169	03/14/2013			\$ 25,000	11/06/2013	100	10/01/2013	SEE PERMIT
7043	06/20/2012			\$ 15,000	11/06/2013	100	10/01/2012	ELECTRICAL
6932	08/30/2011			\$ 20,000	11/06/2013	100	10/01/2011	SEE PERMIT
6565	04/08/2009				10/30/2009	100	10/01/2009	SEE PERMIT
6547	02/25/2009			\$ 50,000	10/30/2009	100	10/01/2009	INSTALL ANTENNAS, EQUIP SHED, GENERATOR
6110	10/24/2006			\$ 285,000		100		CELL TOWER

<a href="#">Recent Sales in Neighborhood</a>	<a href="#">Previous Parcel</a>	<a href="#">Next Parcel</a>	<a href="#">Field Definitions</a>	<a href="#">Return to Main Search Page</a>	<a href="#">Weston Home</a>
<p>The Town of Weston Assessor's Office makes every effort to produce the most accurate information possible. No warranties, expressed or implied, are provided for the data herein, its use or interpretation. Website Updated: October 29, 2017</p>					

© 2012 by the Town of Weston, CT | Website design by [qpublic.net](#)



July 28, 2006

# STATE OF CONNECTICUT

## CONNECTICUT SITING COUNCIL

Ten Franklin Square, New Britain, CT 06051

Phone: (860) 827-2935 Fax: (860) 827-2950

E-Mail: [siting.council@ct.gov](mailto:siting.council@ct.gov)

[www.ct.gov/csc](http://www.ct.gov/csc)

Thomas J. Regan, Esq.  
Brown Rudnick Berlack Israels LLP  
CityPlace I, 185 Asylum Street  
Hartford, CT 06103

RE: **TS-NEXTEL-157-060516** - Sprint Nextel Corporation request for an order to approve tower sharing at a telecommunications facility located at 237 Godfrey Road, Weston, Connecticut.

Dear Attorney Regan:

At a public meeting held July 27, 2006, the Connecticut Siting Council (Council) ruled that the shared use of this tower site is technically, legally, environmentally, and economically feasible and meets public safety concerns, and therefore, in compliance with General Statutes § 16-50aa, the Council has ordered the shared use of this facility to avoid the unnecessary proliferation of tower structures. This facility has also been carefully modeled to ensure that radio frequency emissions are conservatively below State and federal standards applicable to the frequencies now used on this tower.

This decision is under the exclusive jurisdiction of the Council. Any additional change to this facility may require an explicit request to this agency pursuant to General Statutes § 16-50aa or notice pursuant to Regulations of Connecticut State Agencies Section 16-50j-73, as applicable. Such request or notice shall include all relevant information regarding the proposed change with cumulative worst-case modeling of radio frequency exposure at the closest point of uncontrolled access to the tower base, consistent with Federal Communications Commission, Office of Engineering and Technology, Bulletin 65. Any deviation from this format may result in the Council implementing enforcement proceedings pursuant to General Statutes § 16-50u including, without limitation, imposition of expenses resulting from such failure and of civil penalties in an amount not less than one thousand dollars per day for each day of construction or operation in material violation.

This decision applies only to this request for tower sharing and is not applicable to any other request or construction. Please be advised that the validity of this action shall expire one year from the date of this letter.

The proposed shared use is to be implemented as specified in your letter dated May 15, 2006, and additional information dated June 27, 2006, including the placement of all necessary equipment and shelters within the tower compound.

Thank you for your attention and cooperation.

Very truly yours,

Colin C. Tait  
Chairman

CCT/laf

c: The Honorable Woody Bliss, First Selectman, Town of Weston  
Robert P. Turner, Zoning Enforcement Officer, Town of Weston

**TOWN OF WESTON**  
P.O. Box 1007/56 Norfield Road  
Weston, CT 06883  
(203) 222-2659

**Building Official**

*R.E. Olsen*

**Building Permit**

**Permit Number: 6110**

Page 1 of 2

Printed: 10/24/2006

**Applicant**

**Approval Date: 10/24/2006**

**Name:** Town of Weston  
**Address:** 56 Norfield Road  
Weston, CT 06883  
**Phone:** 203-222-2677

**Parcel**

**Parcel Number:** Map 16 Block 1 Lot 35  
**Address:** 237 Godfrey Road  
**Section:** Township:  
**Addition:** Block:  
**Legal Description:**

**Zoning:**  
Weston, CT 06883  
**Range:**  
**Lot(s):**

**Owners**

**Name:** Town of Weston  
**Address:** 56 Norfield Road  
Weston, CT 06883  
**Phone:** 203-222-2677

**Contractors**

**Contractor Type: Major Contractor**

**Name:** McPhee Electric Ltd, LLC  
**Address:** McPhee Electric Ltd, LLC  
505 Main St.  
Farmington, Ct 06032  
**Phone:** 860-655-9438

**Fees and Receipts:**

Number	Description	Amount
052419	Building Permit fee (Auto)	\$2,381.25
<b>Total Fees:</b>		<b>\$2,381.25</b>
052419		\$2,381.25
<b>Total Receipts:</b>		<b>\$2,381.25</b>

---

**Description**

**Structure Use:** Commercial  
**Purpose:** Other  
**Construction Value:** \$285,000.00

**Start Date:**  
**End Date:**

**Floor Areas**

**Living Space:**  
**Basement/Storage:**  
**Garage:**  
**Decks:**  
**Porches:**  
**Other:**  
**Total Area:**

**Impervious Surfaces**

**House:**  
**Garage:**  
**Driveways:**  
**Porch/Walk:**  
**Other:**  
**Total:**

**Structure Area:**

**Site Area:**

**Percentage of Site:**

---

**Conditions**

**Date:**                      **Status:**                      **Code:**  
**Condition Description:**  
**Condition Comments:**

---

**Other Fields:**

---



## RADIO FREQUENCY EMISSIONS ANALYSIS REPORT EVALUATION OF HUMAN EXPOSURE POTENTIAL TO NON-IONIZING EMISSIONS

SPRINT Existing Facility

Site ID: CT33XC522

Transfer Station  
237 Godfrey Road  
Weston, CT 06883

**October 18, 2017**

**EBI Project Number: 6217004505**

Site Compliance Summary	
Compliance Status:	<b>COMPLIANT</b>
Site total MPE% of FCC general population allowable limit:	<b>6.34 %</b>



October 18, 2017

SPRINT

Attn: RF Engineering Manager  
1 International Boulevard, Suite 800  
Mahwah, NJ 07495

## Emissions Analysis for Site: **CT33XC522 – Transfer Station**

EBI Consulting was directed to analyze the proposed SPRINT facility located at **237 Godfrey Road, Weston, CT**, for the purpose of determining whether the emissions from the Proposed SPRINT Antenna Installation located on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter ( $\mu\text{W}/\text{cm}^2$ ). The number of  $\mu\text{W}/\text{cm}^2$  calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits, therefore it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) – (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general population may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general population would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

Public exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter ( $\mu\text{W}/\text{cm}^2$ ). The general population exposure limits for the 850 MHz Band is approximately  $567 \mu\text{W}/\text{cm}^2$ . The general population exposure limit for the 1900 MHz (PCS) and 2500 MHz (BRS) bands is  $1000 \mu\text{W}/\text{cm}^2$ . Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.



Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure. Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

## CALCULATIONS

Calculations were done for the proposed SPRINT Wireless antenna facility located at **237 Godfrey Road, Weston, CT**, using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. Since SPRINT is proposing highly focused directional panel antennas, which project most of the emitted energy out toward the horizon, all calculations were performed assuming a lobe representing the maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was focused at the base of the tower. For this report the sample point is the top of a 6-foot person standing at the base of the tower.

For all calculations, all equipment was calculated using the following assumptions:

- 1) 1 CDMA channels (850 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 20 Watts per Channel.
- 2) 2 LTE channels (850 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 20 Watts per Channel.
- 3) 5 CDMA channels (1900 MHz (PCS)) were considered for each sector of the proposed installation. These Channels have a transmit power of 16 Watts per Channel.
- 4) 2 LTE channels (1900 MHz (PCS)) were considered for each sector of the proposed installation. These Channels have a transmit power of 40 Watts per Channel.
- 5) 8 LTE channels (2500 MHz (BRS)) were considered for each sector of the proposed installation. These Channels have a transmit power of 20 Watts per Channel.



- 6) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 - Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.
- 7) For the following calculations, the sample point was the top of a 6-foot person standing at the base of the tower. The maximum gain of the antenna per the antenna manufactures supplied specifications minus 10 dB was used in this direction. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 8) The antennas used in this modeling are the **RFS APXVSP18-C-A20** and the **RFS APXV9TM14-C-I20** for transmission in the 850 MHz, 1900 MHz (PCS) and 2500 MHz (BRS) frequency bands. This is based on feedback from the carrier with regards to anticipated antenna selection. Maximum gain values for all antennas are listed in the Inventory and Power Data table below. The maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was used for all calculations. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 9) The antenna mounting height centerlines of the proposed antennas are **174 feet** above ground level (AGL) for **Sector A**, **174 feet** above ground level (AGL) for **Sector B** and **174 feet** above ground level (AGL) for Sector C.
- 10) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.

All calculations were done with respect to uncontrolled / general population threshold limits.





## SPRINT Site Inventory and Power Data by Antenna

Sector:	A	Sector:	B	Sector:	C
Antenna #:	<b>1</b>	Antenna #:	<b>1</b>	Antenna #:	<b>1</b>
Make / Model:	RFS APXVSPPI8-C-A20	Make / Model:	RFS APXVSPPI8-C-A20	Make / Model:	RFS APXVSPPI8-C-A20
Gain:	13.4 / 15.9 dBd	Gain:	13.4 / 15.9 dBd	Gain:	13.4 / 15.9 dBd
Height (AGL):	<b>174 feet</b>	Height (AGL):	<b>174 feet</b>	Height (AGL):	<b>174 feet</b>
Frequency Bands	850 MHz / 1900 MHz (PCS)	Frequency Bands	850 MHz / 1900 MHz (PCS)	Frequency Bands	850 MHz / 1900 MHz (PCS)
Channel Count	10	Channel Count	10	Channel Count	10
Total TX Power(W):	220 Watts	Total TX Power(W):	220 Watts	Total TX Power(W):	220 Watts
ERP (W):	7,537.38	ERP (W):	7,537.38	ERP (W):	7,537.38
Antenna A1 MPE%	<b>1.09 %</b>	Antenna B1 MPE%	<b>1.09 %</b>	Antenna C1 MPE%	<b>1.09 %</b>
Antenna #:	<b>2</b>	Antenna #:	<b>2</b>	Antenna #:	<b>2</b>
Make / Model:	RFS APXV9TM14-C-I20	Make / Model:	RFS APXV9TM14-C-I20	Make / Model:	RFS APXV9TM14-C-I20
Gain:	15.9 dBd	Gain:	15.9 dBd	Gain:	15.9 dBd
Height (AGL):	<b>174 feet</b>	Height (AGL):	<b>174 feet</b>	Height (AGL):	<b>174 feet</b>
Frequency Bands	2500 MHz (BRS)	Frequency Bands	2500 MHz (BRS)	Frequency Bands	2500 MHz (BRS)
Channel Count	8	Channel Count	8	Channel Count	8
Total TX Power(W):	160 Watts	Total TX Power(W):	160 Watts	Total TX Power(W):	160 Watts
ERP (W):	6,224.72	ERP (W):	6,224.72	ERP (W):	6,224.72
Antenna A2 MPE%	<b>0.79 %</b>	Antenna B2 MPE%	<b>0.79 %</b>	Antenna C2 MPE%	<b>0.79 %</b>

Site Composite MPE%	
Carrier	MPE%
SPRINT – Max per sector	<b>1.88 %</b>
Weston Police	0.02 %
Weston FD	0.02 %
Weston EMS	0.02 %
Weston Public Works	0.02 %
Verizon Wireless	2.10 %
AT&T	0.97 %
T-Mobile	1.31 %
<b>Site Total MPE %:</b>	<b>6.34 %</b>

SPRINT Sector A Total:	1.88 %
SPRINT Sector B Total:	1.88 %
SPRINT Sector C Total:	1.88 %
<b>Site Total:</b>	<b>6.34 %</b>

SPRINT _ Max Values per Frequency Band / Technology Per Sector	# Channels	Watts ERP (Per Channel)	Height (feet)	Total Power Density ( $\mu\text{W}/\text{cm}^2$ )	Frequency (MHz)	Allowable MPE ( $\mu\text{W}/\text{cm}^2$ )	Calculated % MPE
Sprint 850 MHz CDMA	1	437.55	174	0.56	850 MHz	567	0.10%
Sprint 850 MHz LTE	2	437.55	174	1.11	850 MHz	567	0.20%
Sprint 1900 MHz (PCS) CDMA	5	622.47	174	3.96	1900 MHz (PCS)	1000	0.40%
Sprint 1900 MHz (PCS) LTE	2	1,556.18	174	3.96	1900 MHz (PCS)	1000	0.40%
Sprint 2500 MHz (BRS) LTE	8	778.09	174	7.93	2500 MHz (BRS)	1000	0.79%
<b>Total:</b>							<b>1.88%</b>

## Summary

All calculations performed for this analysis yielded results that were **within** the allowable limits for general population exposure to RF Emissions.

The anticipated maximum composite contributions from the SPRINT facility as well as the site composite emissions value with regards to compliance with FCC's allowable limits for general population exposure to RF Emissions are shown here:

SPRINT Sector	Power Density Value (%)
Sector A:	1.88 %
Sector B:	1.88 %
Sector C:	1.88 %
SPRINT Maximum Total (per sector):	1.88 %
Site Total:	6.34 %
Site Compliance Status:	<b>COMPLIANT</b>

The anticipated composite MPE value for this site assuming all carriers present is **6.34 %** of the allowable FCC established general population limit sampled at the ground level. This is based upon values listed in the Connecticut Siting Council database for existing carrier emissions.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.



September 27, 2017

Tom Jupin  
Charles Cherundolo Consulting, Inc.  
1280 Rt. 46 West  
Parsippany, NJ 07054

Ramaker & Associates, Inc.  
855 Community Drive  
Sauk City, WI 53583

**SUBJECT: MOUNT ASSESSMENT**

**CARRIER: SPRINT**

**SITE: TRANSFER STATION (CT33XC522)**  
**237 GODFREY ROAD**  
**WESTON, FAIRFIELD COUNTY, CONNECTICUT 06883**  
**RAMAKER & ASSOCIATES PROJECT NUMBER: 28737**

**RESULTS: MOUNT: PASS**

Dear Tom Jupin:

Ramaker & Associates, Inc. (RAMAKER) respectfully submits this mount assessment for the above mentioned site. The purpose of this report is to determine the structural integrity of the mounting structure with the proposed loading configurations. Engineering recommendations regarding the analysis results are provided in the following pages.

RAMAKER developed a finite element model of the mount(s) using RISA analysis software. All information contained herein is valid only for the described structure configuration and loading conditions. RAMAKER reserves the right to modify our recommendations should alterations to the mount loading occur.

If you have any questions or comments, please do not hesitate to contact our office.

Sincerely,

RAMAKER & ASSOCIATES, INC.

*Ryan J. Nelson*  
Ryan J. Nelson  
Project Engineer

*James R. Skowronski*  
James R. Skowronski, P.E.  
Supervising Engineer



**ANALYSIS CRITERIA**

State Building Code	2016 CT State Building Code
Adopted Building Code	2012 IBC
Referenced Standard	TIA-222-G
Risk Category	II
Ultimate Design Wind Speed, $V_{ult}$	120 mph (3 sec. gust)
Nominal Design Wind Speed, $V_{asd}$	93 mph (3 sec. gust)
Design Wind Speed w/ Ice	50 mph (3 sec. gust)
Ice Thickness	3/4 inch
Exposure Category	B
Topographic Category	1
Crest Height	N/A

**SUPPORTING DOCUMENTATION**

- Construction drawings by RAMAKER, project number 28737
- Site visit(s) conducted by RAMAKER
- Other pertinent data procured or assumed by RAMAKER during site due diligence activities

**MOUNT LOADING**

RAMAKER understands that the loading to be used for this analysis will consist of the antennas and equipment configurations as shown in the following chart(s):

Antenna Mount – All Sectors				
Elevation	Position	Appurtenance	Mount Type	Status
174	1	(1) RFS APXV9TM14-ALU-120	T-Frame	Proposed
		(1) ALU TD-RRH8x20		
	2	(3) ALU 800MHz RRH		Existing
		(3) ALU 1900MHz RRH		
	3	(3) RFS APXVSP18-C		
4	---			

**MOUNT RESULTS**

By engineering calculation and inspection, the antenna and equipment mounting structure(s) are capable of supporting the proposed loading configurations without causing an overstress condition in the antenna and equipment mounting structure(s).

**LIMITATIONS**

The recommendations contained within this report were developed using the supporting documentation as previously described. All recommendations pertain only to the proposed antenna installation activities as described in this report. RAMAKER assumes no responsibility for failures caused by factors beyond our control. These include but are not limited to the following:

- Missing, corroding, and/or deteriorating members
- Improper manufacturing and/or construction
- Improper maintenance
- Member grades less than assumed grades show below:


Assumed Steel Member Grades	
Angles/Plates/Solid Rods	ASTM A36, 36 ksi
Pipes	ASTM A53 Gr. B, 35 ksi
HSS (Square Tube)	ASTM A36, 36 ksi

RAMAKER is not responsible for verifying that the existing loading on the structure is consistent with the loading applied to the structure within this report. If there is any information contrary to that contained herein, or if there are any defects arising from the original design, material, fabrication and erection deficiencies, this report should be disregarded and RAMAKER should be contacted immediately. RAMAKER is not liable for any representation, recommendation, or conclusion not expressly stated herein.

This analysis pertains only to the mounting structure, and no analyses or conclusions were made regarding the supporting structure. Analysis and certification of the supporting structure is performed and submitted separately.

**ATTACHMENTS**

- Analysis Figures
- Analysis Calculations




Envelope Only Solution

Ramaker & Associates, Inc.  
RJN  
28737

Transfer Station (CT33XC522-C)

SK - 1  
Aug 17, 2017 at 8:43 AM  
28737 Mount Rev1.r3d



Envelope Only Solution

Ramaker & Associates, Inc.  
RJN  
28737

Transfer Station (CT33XC522-C)

SK - 2  
Aug 17, 2017 at 8:45 AM  
28737 Mount Rev1.r3d





### Hot Rolled Steel Properties

	Label	E [ksi]	G [ksi]	Nu	Therm (1E...	Density[k/ft...	Yield[ksi]	Ry	Fu[ksi]	Rt
1	A36 Gr.36	29000	11154	.3	.65	.49	36	1.5	58	1.2
2	A572 Gr.50	29000	11154	.3	.65	.49	50	1.1	65	1.1
3	A992	29000	11154	.3	.65	.49	50	1.1	65	1.1
4	A500 Gr.42	29000	11154	.3	.65	.49	42	1.4	58	1.3
5	A500 Gr.46	29000	11154	.3	.65	.49	46	1.4	58	1.3
6	A53 Gr. B	29000	11154	.3	.65	.49	35	1.5	60	1.2

### Hot Rolled Steel Section Sets

	Label	Shape	Type	Design List	Material	Design Rules	A [in2]	Iyy [in4]	Izz [in4]	J [in4]
1	pipe 2.0	PIPE 2.0	Beam	Pipe	A53 Gr. B	Typical	1.02	.627	.627	1.25
2	HSS3x3x1/4	HSS3x3x4	Beam	SquareTube	A36 Gr.36	Typical	2.44	3.02	3.02	5.08
3	pipe 3.0	PIPE_3.0	Beam	Pipe	A53 Gr. B	Typical	2.07	2.85	2.85	5.69

### Member Primary Data

	Label	I Joint	J Joint	K Joint	Rotate(deg)	Section/Shape	Type	Design List	Material	Design Rules
1	BH	N1	N2			pipe 2.0	Beam	Pipe	A53 Gr. B	Typical
2	MP4	N11	N7			pipe 2.0	Beam	Pipe	A53 Gr. B	Typical
3	MP1	N14	N10			pipe 2.0	Beam	Pipe	A53 Gr. B	Typical
4	TH	N15	N16			pipe 2.0	Beam	Pipe	A53 Gr. B	Typical
5	V1	N49	N50			pipe 3.0	Beam	Pipe	A53 Gr. B	Typical
6	V2	N48	N47			pipe 2.0	Beam	Pipe	A53 Gr. B	Typical
7	SA1	N44	N46			HSS3x3x1/4	Beam	SquareTube	A36 Gr.36	Typical
8	SA2	N43	N45			HSS3x3x1/4	Beam	SquareTube	A36 Gr.36	Typical
9	M13	N44	N22			RIGID	None	None	RIGID	Typical
10	M14	N43	N21			RIGID	None	None	RIGID	Typical
11	MP3	N31	N30			pipe 2.0	Beam	Pipe	A53 Gr. B	Typical
12	MP2	N35A	N34			pipe 2.0	Beam	Pipe	A53 Gr. B	Typical
13	TB1	N36	N39			pipe 2.0	Beam	Pipe	A53 Gr. B	Typical

### Basic Load Cases

	BLC Description	Category	X Gravity	Y Gravity	Z Gravity	Joint	Point	Distributed Area(Me...	Surface(P...
1	Dead Load	None		-1			7		
2	Antenna Wind 0	None					14		
3	Antenna Wind 30	None					14		
4	Antenna Wind 45	None					14		
5	Antenna Wind 60	None					14		
6	Antenna Wind 90	None					14		
7	Antenna Wind 120	None					14		
8	Antenna Wind 135	None					14		
9	Antenna Wind 150	None					14		
10	Antenna Wind 180	None					14		
11	Antenna Wind 210	None					14		
12	Antenna Wind 225	None					14		
13	Antenna Wind 240	None					14		
14	Antenna Wind 270	None					14		
15	Antenna Wind 300	None					14		
16	Antenna Wind 315	None					14		
17	Antenna Wind 330	None					14		
18	Antenna Ice Dead Load	None					7		
19	Antenna Wind w/Ice 0	None					14		
20	Antenna Wind w/Ice 30	None					14		



**Basic Load Cases (Continued)**

	BLC Description	Category	X Gravity	Y Gravity	Z Gravity	Joint	Point	Distributed Area(Me...	Surface(P...
21	Antenna Wind w/Ice 45	None					14		
22	Antenna Wind w/Ice 60	None					14		
23	Antenna Wind w/Ice 90	None					14		
24	Antenna Wind w/Ice 1...	None					14		
25	Antenna Wind w/Ice 1...	None					14		
26	Antenna Wind w/Ice 1...	None					14		
27	Antenna Wind w/Ice 1...	None					14		
28	Antenna Wind w/Ice 2...	None					14		
29	Antenna Wind w/Ice 2...	None					14		
30	Antenna Wind w/Ice 2...	None					14		
31	Antenna Wind w/Ice 2...	None					14		
32	Antenna Wind w/Ice 3...	None					14		
33	Antenna Wind w/Ice 3...	None					14		
34	Antenna Wind w/Ice 3...	None					14		
35	Member Wind 0	None						22	
36	Member Wind 30	None						22	
37	Member Wind 45	None						22	
38	Member Wind 60	None						22	
39	Member Wind 90	None						22	
40	Member Wind 120	None						22	
41	Member Wind 135	None						22	
42	Member Wind 150	None						22	
43	Member Wind 180	None						22	
44	Member Wind 210	None						22	
45	Member Wind 225	None						22	
46	Member Wind 240	None						22	
47	Member Wind 270	None						22	
48	Member Wind 300	None						22	
49	Member Wind 315	None						22	
50	Member Wind 330	None						22	
51	Member Ice Dead Load	None						11	
52	Member Wind w/Ice 0	None						22	
53	Member Wind w/Ice 30	None						22	
54	Member Wind w/Ice 45	None						22	
55	Member Wind w/Ice 60	None						22	
56	Member Wind w/Ice 90	None						22	
57	Member Wind w/Ice 1...	None						22	
58	Member Wind w/Ice 1...	None						22	
59	Member Wind w/Ice 1...	None						22	
60	Member Wind w/Ice 1...	None						22	
61	Member Wind w/Ice 2...	None						22	
62	Member Wind w/Ice 2...	None						22	
63	Member Wind w/Ice 2...	None						22	
64	Member Wind w/Ice 2...	None						22	
65	Member Wind w/Ice 3...	None						22	
66	Member Wind w/Ice 3...	None						22	
67	Member Wind w/Ice 3...	None						22	
68	Live Load - Area	None							
69	Live Load - Point 1	None					2		
70	Live Load - Point 2	None					2		
71	Live Load - Point 3	None					2		
72	Railing Dist. LL z	None							
73	Railing Dist. LL x	None							
74	Railing Point LL z	None							
75	Railing Point LL x	None							



**Load Combinations**

	Description	So...	P...	S...	BLC Fac...	BLC Fac...	BLC Fac...	BLC Fac...	BLC Fac...	BLC Fac...	BLC Fac...	BLC Fac...	BLC Fac...	BLC Fac...	BLC Fac...
1	1.4D	Yes	Y		1	1.4									
2	0.9D + 1.6 (0-W...	Yes	Y		1	.9	2	1.6	35	1.6					
3	0.9D + 1.6 (30-...	Yes	Y		1	.9	3	1.6	36	1.6					
4	0.9D + 1.6 (45-...	Yes	Y		1	.9	4	1.6	37	1.6					
5	0.9D + 1.6 (60-...	Yes	Y		1	.9	5	1.6	38	1.6					
6	0.9D + 1.6 (90-...	Yes	Y		1	.9	6	1.6	39	1.6					
7	0.9D + 1.6 (120-...	Yes	Y		1	.9	7	1.6	40	1.6					
8	0.9D + 1.6 (135-...	Yes	Y		1	.9	8	1.6	41	1.6					
9	0.9D + 1.6 (150-...	Yes	Y		1	.9	9	1.6	42	1.6					
10	0.9D + 1.6 (180-...	Yes	Y		1	.9	10	1.6	43	1.6					
11	0.9D + 1.6 (210-...	Yes	Y		1	.9	11	1.6	44	1.6					
12	0.9D + 1.6 (225-...	Yes	Y		1	.9	12	1.6	45	1.6					
13	0.9D + 1.6 (240-...	Yes	Y		1	.9	13	1.6	46	1.6					
14	0.9D + 1.6 (270-...	Yes	Y		1	.9	14	1.6	47	1.6					
15	0.9D + 1.6 (300-...	Yes	Y		1	.9	15	1.6	48	1.6					
16	0.9D + 1.6 (315-...	Yes	Y		1	.9	16	1.6	49	1.6					
17	0.9D + 1.6 (330-...	Yes	Y		1	.9	17	1.6	50	1.6					
18	1.2D + 1.6 (0-W...	Yes	Y		1	1.2	2	1.6	35	1.6					
19	1.2D + 1.6 (30-...	Yes	Y		1	1.2	3	1.6	36	1.6					
20	1.2D + 1.6 (45-...	Yes	Y		1	1.2	4	1.6	37	1.6					
21	1.2D + 1.6 (60-...	Yes	Y		1	1.2	5	1.6	38	1.6					
22	1.2D + 1.6 (90-...	Yes	Y		1	1.2	6	1.6	39	1.6					
23	1.2D + 1.6 (120-...	Yes	Y		1	1.2	7	1.6	40	1.6					
24	1.2D + 1.6 (135-...	Yes	Y		1	1.2	8	1.6	41	1.6					
25	1.2D + 1.6 (150-...	Yes	Y		1	1.2	9	1.6	42	1.6					
26	1.2D + 1.6 (180-...	Yes	Y		1	1.2	10	1.6	43	1.6					
27	1.2D + 1.6 (210-...	Yes	Y		1	1.2	11	1.6	44	1.6					
28	1.2D + 1.6 (225-...	Yes	Y		1	1.2	12	1.6	45	1.6					
29	1.2D + 1.6 (240-...	Yes	Y		1	1.2	13	1.6	46	1.6					
30	1.2D + 1.6 (270-...	Yes	Y		1	1.2	14	1.6	47	1.6					
31	1.2D + 1.6 (300-...	Yes	Y		1	1.2	15	1.6	48	1.6					
32	1.2D + 1.6 (315-...	Yes	Y		1	1.2	16	1.6	49	1.6					
33	1.2D + 1.6 (330-...	Yes	Y		1	1.2	17	1.6	50	1.6					
34	1.2D + 1.0Di + 1...	Yes	Y		1	1.2	18	1	51	1	19	1	52	1	
35	1.2D + 1.0Di + 1...	Yes	Y		1	1.2	18	1	51	1	20	1	53	1	
36	1.2D + 1.0Di + 1...	Yes	Y		1	1.2	18	1	51	1	21	1	54	1	
37	1.2D + 1.0Di + 1...	Yes	Y		1	1.2	18	1	51	1	22	1	55	1	
38	1.2D + 1.0Di + 1...	Yes	Y		1	1.2	18	1	51	1	23	1	56	1	
39	1.2D + 1.0Di + 1...	Yes	Y		1	1.2	18	1	51	1	24	1	57	1	
40	1.2D + 1.0Di + 1...	Yes	Y		1	1.2	18	1	51	1	25	1	58	1	
41	1.2D + 1.0Di + 1...	Yes	Y		1	1.2	18	1	51	1	26	1	59	1	
42	1.2D + 1.0Di + 1...	Yes	Y		1	1.2	18	1	51	1	27	1	60	1	
43	1.2D + 1.0Di + 1...	Yes	Y		1	1.2	18	1	51	1	28	1	61	1	
44	1.2D + 1.0Di + 1...	Yes	Y		1	1.2	18	1	51	1	29	1	62	1	
45	1.2D + 1.0Di + 1...	Yes	Y		1	1.2	18	1	51	1	30	1	63	1	
46	1.2D + 1.0Di + 1...	Yes	Y		1	1.2	18	1	51	1	31	1	64	1	
47	1.2D + 1.0Di + 1...	Yes	Y		1	1.2	18	1	51	1	32	1	65	1	
48	1.2D + 1.0Di + 1...	Yes	Y		1	1.2	18	1	51	1	33	1	66	1	
49	1.2D + 1.0Di + 1...	Yes	Y		1	1.2	18	1	51	1	34	1	67	1	
50	1.0D + 1.5LL + ...	Yes	Y		1	1	68	1.5	72	1.5					
51	1.0D + 1.5LL + ...	Yes	Y		1	1	68	1.5	73	1.5					
52	1.0D + 1.5LL + ...	Yes	Y		1	1	68	1.5	74	1.5					
53	1.0D + 1.5LL + ...	Yes	Y		1	1	68	1.5	75	1.5					
54	1.0D + 1.5LL + ...	Yes	Y		1	1	69	1.5	72	1.5					
55	1.0D + 1.5LL + ...	Yes	Y		1	1	69	1.5	73	1.5					
56	1.0D + 1.5LL + ...	Yes	Y		1	1	69	1.5	74	1.5					



**Load Combinations (Continued)**

Description	So...	P...	S...	BLC Fac...	BLC Fac...	BLC Fac...	BLC Fac...	BLC Fac...	BLC Fac...	BLC Fac...	BLC Fac...	BLC Fac...	BLC Fac...	BLC Fac...
57	1.0D + 1.5LL + ...	Yes	Y	1	1	69	1.5	75	1.5					
58	1.0D + 1.5LL + ...	Yes	Y	1	1	70	1.5	72	1.5					
59	1.0D + 1.5LL + ...	Yes	Y	1	1	70	1.5	73	1.5					
60	1.0D + 1.5LL + ...	Yes	Y	1	1	70	1.5	74	1.5					
61	1.0D + 1.5LL + ...	Yes	Y	1	1	70	1.5	75	1.5					
62	1.0D + 1.5LL + ...	Yes	Y	1	1	71	1.5	72	1.5					
63	1.0D + 1.5LL + ...	Yes	Y	1	1	71	1.5	73	1.5					
64	1.0D + 1.5LL + ...	Yes	Y	1	1	71	1.5	74	1.5					
65	1.0D + 1.5LL + ...	Yes	Y	1	1	71	1.5	75	1.5					
66	Serviceability (0...	Yes	Y	1	1	2	.372	35	.372					
67	Serviceability (3...	Yes	Y	1	1	3	.372	36	.372					
68	Serviceability (4...	Yes	Y	1	1	4	.372	37	.372					
69	Serviceability (6...	Yes	Y	1	1	5	.372	38	.372					
70	Serviceability (9...	Yes	Y	1	1	6	.372	39	.372					
71	Serviceability (1...	Yes	Y	1	1	7	.372	40	.372					
72	Serviceability (1...	Yes	Y	1	1	8	.372	41	.372					
73	Serviceability (1...	Yes	Y	1	1	9	.372	42	.372					
74	Serviceability (1...	Yes	Y	1	1	10	.372	43	.372					
75	Serviceability (2...	Yes	Y	1	1	11	.372	44	.372					
76	Serviceability (2...	Yes	Y	1	1	12	.372	45	.372					
77	Serviceability (2...	Yes	Y	1	1	13	.372	46	.372					
78	Serviceability (2...	Yes	Y	1	1	14	.372	47	.372					
79	Serviceability (3...	Yes	Y	1	1	15	.372	48	.372					
80	Serviceability (3...	Yes	Y	1	1	16	.372	49	.372					
81	Serviceability (3...	Yes	Y	1	1	17	.372	50	.372					

**Envelope Joint Reactions**

Joint		X [lb]	LC	Y [lb]	LC	Z [lb]	LC	MX [lb-ft]	LC	MY [lb-ft]	LC	MZ [lb-ft]	LC	
1	N46	max	434.957	13	935.286	42	498.039	2	0	1	0	1	0	1
2		min	-905.002	21	234.211	2	-1206.62	42	0	1	0	1	0	1
3	N45	max	829.731	29	930.837	35	1122.753	49	0	1	0	1	0	1
4		min	-376.155	5	232.415	10	-154.817	8	0	1	0	1	0	1
5	N39	max	314.228	3	47.97	44	659.167	3	0	1	0	1	0	1
6		min	-298.098	11	8.47	4	-650.705	11	0	1	0	1	0	1
7	Totals:	max	960.891	14	1900.088	43	1402.202	2						
8		min	-960.891	22	512.296	3	-1402.202	26						

**Envelope AISC 14th(360-10): LRFD Steel Code Checks**

Member	Shape	Code C...	Loc[ft]	LC	Shear ...	Loc[ft]	Dir	LC	phi*Pnc [lb]	phi*Pnt [lb]	phi*Mn y...	phi*Mn z...	Cb	Eqn	
1	BH	PIPE 2.0	.817	6	31	.152	6	35	20866.733	32130	1871.625	1871.625	1...	H1-1b	
2	MP4	PIPE 2.0	.214	4.75	54	.023	.75	54	20866.733	32130	1871.625	1871.625	1...	H1-1b	
3	MP1	PIPE 2.0	.319	4.75	37	.170	1.75	27	20866.733	32130	1871.625	1871.625	1...	H1-1b	
4	TH	PIPE 2.0	.808	6	24	.189	8	19	20866.733	32130	1871.625	1871.625	1...	H1-1b	
5	V1	PIPE 3.0	.231	.281	43	.167	.281	58	58506.375	65205	5748.75	5748.75	2...	H1-1b	
6	V2	PIPE 2.0	.334	0	39	.168	0	58	29628.564	32130	1871.625	1871.625	2...	H1-1b	
7	SA1	HSS3x3x4	.353	0	37	.102	1.875	z	58	77142.698	79056	6696	6696	2...	H1-1b
8	SA2	HSS3x3x4	.359	0	45	.102	1.875	z	58	77142.698	79056	6696	6696	2...	H1-1b
9	MP3	PIPE 2.0	.253	.75	54	.049	.75	39	20866.733	32130	1871.625	1871.625	1...	H1-1b	
10	MP2	PIPE 2.0	.418	4.75	38	.150	4.75	19	20866.733	32130	1871.625	1871.625	1...	H1-1b	
11	TB1	PIPE 2.0	.051	3.5	21	.005	7	45	17855.085	32130	1871.625	1871.625	1...	H1-1b	

**Wind Load on Antennas TIA-222-G**

$$q_z = 0.00256 K_z K_{zt} K_d V^2 I$$

$$F = q_z G_h C_a A_a$$

Occupancy:	II	Classification of Structures (Table 2-1)
Exposure:	B	Exposure Category
V:	93 mph	Basic Wind Speed (Annex B)
z:	174 ft	Height above ground level to the center of the antenna
I:	1.00	Importance Factor (Table 2-3)
K <sub>z</sub> :	1.16	Velocity Pressure Coefficient (2.6.5.2)
K <sub>zt</sub> :	1.00	Topographic Factor (2.6.6.4)
K <sub>d</sub> :	0.95	Wind Direction Probability Factor (Table 2-2)
q <sub>z</sub> :	24.4 psf	Velocity Pressure at Height z
G <sub>h</sub> :	1.00	Strength Design of Appurtenances and their Connections

**Mount & Antenna Wind Loads**

Appurtenance	Height	Width	h/D	Shape	C <sub>a</sub>	A <sub>f</sub>	Force	Force
	<i>in</i>	<i>in</i>				<i>sq ft</i>	<i>lb</i>	<i>plf</i>
APXVTM14-C-120	56.3	12.6	4.5	Flat	1.287	4.93	154.4	
TD-RRH8x20	26.1	18.6	1.4	Flat	1.200	3.37	98.5	
APXVSPP18-C-A20	72.0	11.9	6.1	Flat	1.358	5.95	196.6	
1900MHz 4x40W RRH	25.1	11.1	2.3	Flat	1.200	1.93	56.5	
800MHz 2x50W RRH	19.0	13.0	1.5	Flat	1.200	1.72	50.1	
Pipe2STD x 12 ft	144.0	2.4	60.6	Round	1.200	2.38	69.4	5.8
Pipe2STD x 7 ft	84.0	2.4	35.4	Round	1.200	1.39	40.5	5.8
Pipe2STD x 6 ft	72.0	2.4	30.3	Round	1.200	1.19	34.7	5.8
Pipe2STD x 4 ft	48.0	2.4	20.2	Round	1.094	0.79	21.1	5.3
Pipe3STD x 4.5 ft	54.0	3.5	15.4	Round	0.987	1.31	31.6	7.0
HSS3X3X1/4 x 2.25 ft	27.0	3.0	9.0	Flat	1.467	0.56	20.1	8.9

**Wind Load on Antennas TIA-222-G**

$$q_z = 0.00256 K_z K_{zt} K_d V^2 I$$

$$F = q_z G_h C_a A_a$$

Occupancy:	II	Classification of Structures (Table 2-1)
Exposure:	B	Exposure Category
V:	93 mph	Basic Wind Speed (Annex B)
z:	174 ft	Height above ground level to the center of the antenna
I:	1.00	Importance Factor (Table 2-3)
K <sub>z</sub> :	1.16	Velocity Pressure Coefficient (2.6.5.2)
K <sub>zt</sub> :	1.00	Topographic Factor (2.6.6.4)
K <sub>d</sub> :	0.95	Wind Direction Probability Factor (Table 2-2)
q <sub>z</sub> :	24.4 psf	Velocity Pressure at Height z
G <sub>h</sub> :	1.00	Strength Design of Appurtenances and their Connections

**Mount & Antenna Wind Loads**

Appurtenance	Height <i>in</i>	Depth <i>in</i>	h/D	Shape	C <sub>a</sub>	A <sub>f</sub> <i>sq ft</i>	Force <i>lb</i>	Force <i>plf</i>
APXVTM14-C-120	56.3	6.3	8.9	Flat	1.465	2.46	87.8	
TD-RRH8x20	26.1	6.7	3.9	Flat	1.262	1.21	37.3	
APXVSPP18-C-A20	72.0	7.0	10.3	Flat	1.509	3.50	128.8	
1900MHz 4x40W RRH	25.1	10.7	2.3	Flat	1.200	1.86	54.4	
800MHz 2x50W RRH	19.0	12.2	1.6	Flat	1.200	1.61	47.0	
Pipe2STD x 12 ft	144.0	2.4	60.6	Round	1.200	2.38	69.4	5.8
Pipe2STD x 7 ft	84.0	2.4	35.4	Round	1.200	1.39	40.5	5.8
Pipe2STD x 6 ft	72.0	2.4	30.3	Round	1.200	1.19	34.7	5.8
Pipe2STD x 4 ft	48.0	2.4	20.2	Round	1.094	0.79	21.1	5.3
Pipe3STD x 4.5 ft	54.0	3.5	15.4	Round	0.987	1.31	31.6	7.0
HSS3X3X1/4 x 2.25 ft	27.0	3.0	9.0	Flat	1.467	0.56	20.1	8.9

**Ice Wind Load on Antennas TIA-222-G**

$$q_z = 0.00256 K_z K_{zt} K_d V^2 I$$

$$F = q_z G_h C_a A_a$$

Occupancy:	II	Classification of Structures (Table 2-1)
Exposure:	B	Exposure Category
V <sub>i</sub> :	50 mph	Basic Wind Speed (Annex B)
z:	174 ft	Height above ground level to the center of the antenna
I:	1.00	Importance Factor (Table 2-3)
K <sub>z</sub> :	1.16	Velocity Pressure Coefficient (2.6.5.2)
K <sub>zt</sub> :	1.00	Topographic Factor (2.6.6.4)
K <sub>d</sub> :	0.95	Wind Direction Probability Factor (Table 2-2)
q <sub>z</sub> :	7.04 psf	Velocity Pressure at Height z
G <sub>h</sub> :	1.00	Strength Design of Appurtenances and their Connections
K <sub>iz</sub> :	1.18	Height Escalation Factor for Ice Thickness
t <sub>iz</sub> :	1.77 in	Factored Thickness of Radial Glaze Ice at Height z

**Mount & Antenna Ice Wind Loads**

Appurtenance	Height <i>in</i>	Width <i>in</i>	h/D	Shape	C <sub>a</sub>	A <sub>f</sub> <i>sq ft</i>	Force <i>lb</i>	Force <i>plf</i>
APXVTM14-C-120	59.8	16.1	3.7	Flat	1.254	6.71	59.2	
TD-RRH8x20	29.6	22.1	1.3	Flat	1.200	4.56	38.5	
APXVSPP18-C-A20	75.6	15.4	4.9	Flat	1.306	8.10	74.5	
1900MHz 4x40W RRH	28.6	14.6	2.0	Flat	1.200	2.91	24.6	
800MHz 2x50W RRH	22.5	16.5	1.4	Flat	1.200	2.59	21.9	
Pipe2STD x 12 ft	147.5	5.9	24.9	Round	1.199	6.06	51.1	4.2
Pipe2STD x 7 ft	87.5	5.9	14.8	Round	0.973	3.60	24.6	3.4
Pipe2STD x 6 ft	75.5	5.9	12.8	Round	0.928	3.10	20.3	3.2
Pipe2STD x 4 ft	51.5	5.9	8.7	Round	0.838	2.12	12.5	2.9
Pipe3STD x 4.5 ft	57.5	7.0	8.2	Round	0.826	2.81	16.4	3.4
HSS3X3X1/4 x 2.25 ft	30.5	6.5	4.7	Flat	1.296	1.39	12.7	5.0

**Ice Wind Load on Antennas TIA-222-G**

$$q_z = 0.00256 K_z K_{zt} K_d V^2 I$$

$$F = q_z G_h C_a A_a$$

Occupancy:	II	Classification of Structures (Table 2-1)
Exposure:	B	Exposure Category
V <sub>i</sub> :	50 mph	Basic Wind Speed (Annex B)
z:	174 ft	Height above ground level to the center of the antenna
I:	1.00	Importance Factor (Table 2-3)
K <sub>z</sub> :	1.16	Velocity Pressure Coefficient (2.6.5.2)
K <sub>zt</sub> :	1.00	Topographic Factor (2.6.6.4)
K <sub>d</sub> :	0.95	Wind Direction Probability Factor (Table 2-2)
q <sub>z</sub> :	7.04 psf	Velocity Pressure at Height z
G <sub>h</sub> :	1.00	Strength Design of Appurtenances and their Connections
K <sub>iz</sub> :	1.18	Height Escalation Factor for Ice Thickness
t <sub>iz</sub> :	1.77 in	Factored Thickness of Radial Glaze Ice at Height z

**Mount & Antenna Ice Wind Loads**

Appurtenance	Height <i>in</i>	Depth <i>in</i>	h/D	Shape	C <sub>a</sub>	A <sub>f</sub> <i>sq ft</i>	Force <i>lb</i>	Force <i>plf</i>
APXVTM14-C-120	59.8	9.8	6.1	Flat	1.359	4.09	39.1	
TD-RRH8x20	29.6	10.2	2.9	Flat	1.218	2.11	18.1	
APXVSPP18-C-A20	75.6	10.6	7.2	Flat	1.405	5.54	54.8	
1900MHz 4x40W RRH	28.6	14.2	2.0	Flat	1.200	2.83	23.9	
800MHz 2x50W RRH	22.5	15.7	1.4	Flat	1.200	2.46	20.8	
Pipe2STD x 12 ft	147.5	5.9	24.9	Round	1.199	6.06	51.1	4.2
Pipe2STD x 7 ft	87.5	5.9	14.8	Round	0.973	3.60	24.6	3.4
Pipe2STD x 6 ft	75.5	5.9	12.8	Round	0.928	3.10	20.3	3.2
Pipe2STD x 4 ft	51.5	5.9	8.7	Round	0.838	2.12	12.5	2.9
Pipe3STD x 4.5 ft	57.5	7.0	8.2	Round	0.826	2.81	16.4	3.4
HSS3X3X1/4 x 2.25 ft	30.5	6.5	4.7	Flat	1.296	1.39	12.7	5.0



**Ice Load on Antennas TIA-222-G**

Ice Weight:	56 pcf	Ice Density
t <sub>i</sub> :	0.75	Design Ice Thickness
Occupancy:	II	Classification of Structures (Table 2-1)
Exposure:	B	Exposure Category
V <sub>i</sub> :	50 mph	Basic Wind Speed (Annex B)
z:	174 ft	Height above ground level to the center of the antenna
I:	1.00	Importance Factor (Table 2-3)
K <sub>iz</sub> :	1.18	Height Escalation Factor for Ice Thickness
K <sub>zt</sub> :	1.00	Topographic Factor (2.6.6.4)
t <sub>iz</sub> :	1.77 in	Factored Thickness of Radial Glaze Ice at Height z

Platform Grating: **None**  
 Ice Load: psf

**Mount & Antenna Ice Wind Loads**

Appurtenance	Height	Width	Depth	Diam.	Area	Perim.	Ice Weight	
	<i>in</i>	<i>in</i>	<i>in</i>	<i>in</i>	<i>sq in</i>	<i>in</i>	<i>lb</i>	<i>plf</i>
APXVTM14-C-120	59.8	16.1	9.8	14.09	88.25	44.89	161.0	
TD-RRH8x20	29.6	22.1	10.2	19.77	119.87	57.69	101.4	
APXVSPP18-C-A20	75.6	15.4	10.6	13.80	86.66	44.88	202.2	
1900MHz 4x40W RRH	28.6	14.6	14.2	15.41	95.61	50.67	77.8	
800MHz 2x50W RRH	22.5	16.5	15.7	17.83	109.07	57.49	67.2	
Pipe2STD x 12 ft	147.5	5.9	5.9	2.38	23.07	13.03	107.7	9.0
Pipe2STD x 7 ft	87.5	5.9	5.9	2.38	23.07	13.03	62.8	9.0
Pipe2STD x 6 ft	75.5	5.9	5.9	2.38	23.07	13.03	53.8	9.0
Pipe2STD x 4 ft	51.5	5.9	5.9	2.38	23.07	13.03	35.9	9.0
Pipe3STD x 4.5 ft	57.5	7.0	7.0	3.50	29.33	16.56	51.3	11.4
HSS3X3X1/4 x 2.25 ft	30.5	6.5	6.5	3.78	30.87	23.55	27.0	12.0



September 27, 2017

Tom Jupin  
Charles Cherundolo Consulting, Inc.  
1280 Rt. 46 West  
Parsippany, NJ 07054

Ramaker & Associates, Inc.  
855 Community Drive  
Sauk City, WI 53583

**SUBJECT: STRUCTURAL ASSESSMENT  
185-FOOT SELF-SUPPORT TOWER**

**CARRIER: SPRINT**

**SITE: TRANSFER STATION (CT33XC522)  
237 GODFREY ROAD  
WESTON, FAIRFIELD COUNTY, CONNECTICUT 06883  
RAMAKER & ASSOCIATES PROJECT NUMBER: 28737**

<b>RESULTS:</b>	<b>TOWER:</b>	<b>98.8%</b>	<b>PASS WITH MODIFICATIONS</b>
	<b>FOUNDATION:</b>	<b>97.3%</b>	<b>PASS</b>

Dear Tom Jupin:


Ramaker & Associates, Inc. (RAMAKER) respectfully submits this structural assessment for the above mentioned site. The purpose of this report is to determine the structural integrity of the structure(s) with the proposed loading configurations. Engineering recommendations regarding the analysis results are provided in the following pages.


RAMAKER developed a finite element model of the tower using tnxTower analysis software. All information contained herein is valid only for the described structure configuration and loading conditions. RAMAKER reserves the right to modify our recommendations should alterations to the tower loading occur.

If you have any questions or comments, please do not hesitate to contact our office.

Sincerely,

RAMAKER & ASSOCIATES, INC.

  
Thomas E. Moore  
Project Engineer

  
James R. Skowronski, P.E.  
Supervising Engineer



**ANALYSIS CRITERIA**

State Building Code	2016 CT State Building Code
Adopted Building Code	2012 IBC
Referenced Standard	TIA-222-G
Risk Category	II
Ultimate Design Wind Speed, $V_{ult}$	120 mph (3 sec. gust)
Nominal Design Wind Speed, $V_{asd}$	93 mph (3 sec. gust)
Design Wind Speed w/ Ice	50 mph (3 sec. gust)
Ice Thickness	3/4 inch
Exposure Category	B
Topographic Category	1
Crest Height	N/A

**SUPPORTING DOCUMENTATION**

- Tower and foundation drawings by Sabre, proposal number 06-8653-MJB-R3, dated June 20, 2006
- Tower member data from Sabre, by email, on September 26, 2017
- Geotechnical report by JGI Eastern, Inc., job number 06113G, dated February 16, 2006
- Structural analysis by CHA, job number 22702-1018-28000-R1, dated July 22, 2011
- Structural analysis by Centek Engineering, job number 14001.010, dated April 09, 2014
- Structural analysis by RAMAKER, job number 28737, dated October 15, 2014
- Structural analysis by Destek Engineering, job number 1675003, dated January 24, 2017
- Construction drawings by RAMAKER, project number 28737
- Site visit(s) conducted by RAMAKER
- Other pertinent data procured or assumed by RAMAKER during site due diligence activities

**TOWER LOADING**

RAMAKER understands that the loading to be used for this analysis will consist of the antenna equipment, mount, and cable configurations as shown in the following chart:

Elevation	Appurtenance	Mount	Coax	Owner	Status
185	(1) 12' Omni	Leg Mount	(3) 7/8	Municipal	Existing
	(2) 6' Dipole				
	(2) Ericsson AIR 21 B2A B4P	(3) T-Frame	(12) 1-5/8	T-Mobile	Existing
	(4) Ericsson AIR 21 B2A B2P				
	(3) Ericsson KRY 112 71				
	(3) Commscope LNX-6515DS-A1M				
	(3) Ericsson RRUS-11				
174	(3) RFS APXVSP18-C	(3) T-Frame	(3) 1-1/4 Hybrid	Sprint	Existing
	(3) ALU 1900MHz RRH				
	(3) ALU 800MHz RRH				
	(3) RFS APXV9TM14-ALU-120				(1) 1-1/4 Hybrid
	(3) ALU TD-RRH8x20				
164	(3) Antel BXA-70063-6CF	(3) T-Frame	(18) 1-5/8	Verizon	Existing
	(4) Decibel DB846F65ZAXY				
	(2) Decibel DB846H80E-SX				
	(6) Kathrein Scala 742 213				
	(3) ALU RRH2x40-AWS				
	(1) RFS DB-T1-6Z-8AB-OZ				
154	(6) Powerwave 7770	(3) T-Frame	(12) 1-5/8	AT&T	Existing
	(3) Powerwave P65-16-XLH-RR				
	(6) Powerwave LGP214nn				
	(3) Powerwave TT19-08BP111-001				
	(3) Ericsson RRUS-11				
	(1) Raycap DC6-48-60-18-8F				
146	(1) 15' Omni	(2) 6' Standoff	(4) 7/8	Municipal	Existing
	(2) 8' Dipole				
138	(1) 3' Dish w/Radome	(1) 2' Standoff	(1) 1/2	Municipal	Existing

**TOWER RESULTS**

The maximum tower member stress capacities under the loading conditions previously described are as follows:

<b>Component Type</b>	<b>Percent Capacity</b>	<b>Pass/Fail</b>
Leg	89.9	Pass
Diagonal	98.8	Pass
Horizontal	23.4	Pass
Secondary Horizontal	46.1	Pass
Redundant Bracing	15.4	Pass
Bolt	86.1	Pass
Anchor Rod	79.9	Pass
<b>RATING</b>	<b>98.8</b>	<b>PASS</b>

Results of the analysis show that the modified tower will be stressed to a maximum of 98.8 percent of capacity. Therefore, the modified tower will pass the TIA-222-G analysis requirements under proposed loading conditions. The required tower modifications are included in the attachments.

**DISH TWIST/SWAY RESULTS**

The twist/sway results for a 60 mph service wind speed are as follows:

<b>Elevation</b>	<b>Dish</b>	<b>Deflection (in)</b>	<b>Tilt (deg)</b>	<b>Twist (deg)</b>
138	Andrew 3' Dish	3.836	0.2864	0.0089

**FOUNDATION RESULTS**

The maximum foundation stress capacities are as follows:

<b>Component Type</b>	<b>Percent Capacity</b>	<b>Pass/Fail</b>
Soil Interaction	65.6	Pass
Structural	97.3	Pass
<b>RATING</b>	<b>97.3</b>	<b>PASS</b>

Results of the analysis show that the existing foundation will be stressed to a maximum of 97.3 percent of capacity. Therefore, the existing foundation will pass the TIA-222-G analysis requirements under proposed loading conditions.

**LIMITATIONS**

The recommendations contained within this report were developed using the supporting documentation as previously described. All recommendations pertain only to the proposed antenna installation activities as described in this report. RAMAKER assumes no responsibility for failures caused by factors beyond our control. These include but are not limited to the following:

- Missing, corroding, and/or deteriorating members
- Improper manufacturing and/or construction
- Improper maintenance

RAMAKER assumes no responsibility for modifications completed prior to or hereafter in which RAMAKER was not directly involved. These modifications include but are not limited to the following:

- Replacing or strengthening bracing members
- Reinforcing or extending vertical members
- Installing or removing antenna mounting gates or side arms
- Changing loading configurations

The tower owner is responsible for verifying that the existing loading on the structure is consistent with the loading applied to the structure within this report. If there is any information contrary to that contained herein, or if there are any defects arising from the original design, material, fabrication and erection deficiencies, this report should be disregarded and RAMAKER should be contacted immediately. RAMAKER is not liable for any representation, recommendation, or conclusion not expressly stated herein.

This analysis pertains only to the tower structure, and no analyses or conclusions were made regarding the antenna and equipment mounting structure(s). Analysis and certification of the antenna and equipment mounting structure(s) is performed and submitted separately.

**ATTACHMENTS**

- Analysis Figures
- Analysis Calculations



**DESIGNED APPURTENANCE LOADING**

TYPE	ELEVATION	TYPE	ELEVATION
6' Dipole (Municipal)	185	DB846H80E-SX w/Mount Pipe (Verizon)	164
12' Omni (Municipal)	185	DB846H80E-SX w/Mount Pipe (Verizon)	164
6' Dipole (Municipal)	185	DB846F65ZAXY w/Mount Pipe (Verizon)	164
(2) AIR 21 B2A B4P w/Mount Pipe (T-Mobile)	185	DB846F65ZAXY w/Mount Pipe (Verizon)	164
(2) AIR 21 B2A B4P w/Mount Pipe (T-Mobile)	185	DB846F65ZAXY w/Mount Pipe (Verizon)	164
(2) AIR 21 B2A B2P w/Mount Pipe (T-Mobile)	185	742 213 w/Mount Pipe (Verizon)	164
KRY 112 71 (T-Mobile)	185	742 213 w/Mount Pipe (Verizon)	164
KRY 112 71 (T-Mobile)	185	742 213 w/Mount Pipe (Verizon)	164
KRY 112 71 (T-Mobile)	185	742 213 w/Mount Pipe (Verizon)	164
LNK-6515DS-A1M w/Mount Pipe (T-Mobile)	185	742 213 w/Mount Pipe (Verizon)	164
LNK-6515DS-A1M w/Mount Pipe (T-Mobile)	185	RRH 2x40 AWS (Verizon)	164
LNK-6515DS-A1M w/Mount Pipe (T-Mobile)	185	RRH 2x40 AWS (Verizon)	164
RRUS-11 (T-Mobile)	185	RRH 2x40 AWS (Verizon)	164
RRUS-11 (T-Mobile)	185	DB-T1-6Z-8AB-0Z (Verizon)	164
RRUS-11 (T-Mobile)	185	Sector Mount [SM 104-1] (Verizon)	164
Sector Mount [SM 403-1] (T-Mobile)	185	Sector Mount [SM 104-1] (Verizon)	164
Sector Mount [SM 403-1] (T-Mobile)	185	Sector Mount [SM 104-1] (Verizon)	164
Sector Mount [SM 403-1] (T-Mobile)	185	7770.00 w/Mount Pipe (ATT)	154
Sector Mount [SM 403-1] (T-Mobile)	185	7770.00 w/Mount Pipe (ATT)	154
Sector Mount [SM 403-1] (T-Mobile)	185	7770.00 w/Mount Pipe (ATT)	154
APXVSPP18-C w/Mount Pipe (Sprint)	174	7770.00 w/Mount Pipe (ATT)	154
APXVSPP18-C w/Mount Pipe (Sprint)	174	7770.00 w/Mount Pipe (ATT)	154
APXVSPP18-C w/Mount Pipe (Sprint)	174	7770.00 w/Mount Pipe (ATT)	154
1900MHz 4x40W RRH (Sprint)	174	P65-16-XLH-RR w/Mount Pipe (ATT)	154
1900MHz 4x40W RRH (Sprint)	174	P65-16-XLH-RR w/Mount Pipe (ATT)	154
1900MHz 4x40W RRH (Sprint)	174	P65-16-XLH-RR w/Mount Pipe (ATT)	154
800MHz 2x50W RRH (Sprint)	174	(2) LGP214nn (ATT)	154
800MHz 2x50W RRH (Sprint)	174	(2) LGP214nn (ATT)	154
800MHz 2x50W RRH (Sprint)	174	(2) LGP214nn (ATT)	154
APXV9TM14-ALU-120 w/Mount Pipe (Sprint)	174	TT19-08BP111-001 (ATT)	154
APXV9TM14-ALU-120 w/Mount Pipe (Sprint)	174	TT19-08BP111-001 (ATT)	154
APXV9TM14-ALU-120 w/Mount Pipe (Sprint)	174	RRUS-11 (ATT)	154
APXV9TM14-ALU-120 w/Mount Pipe (Sprint)	174	RRUS-11 (ATT)	154
TD-RRH8x20-25 (Sprint)	174	RRUS-11 (ATT)	154
TD-RRH8x20-25 (Sprint)	174	DC6-48-60-18-8F (ATT)	154
TD-RRH8x20-25 (Sprint)	174	Sector Mount [SM 104-1] (ATT)	154
Sector Mount [SM 403-1] (Sprint)	174	Sector Mount [SM 104-1] (ATT)	154
Sector Mount [SM 403-1] (Sprint)	174	Sector Mount [SM 104-1] (ATT)	154
Sector Mount [SM 403-1] (Sprint)	174	15' Omni (Municipal)	146
BXA-70063-6CF-EDIN-X w/Mount Pipe (Verizon)	164	8' Dipole (Municipal)	146
BXA-70063-6CF-EDIN-X w/Mount Pipe (Verizon)	164	8' Dipole (Municipal)	146
BXA-70063-6CF-EDIN-X w/Mount Pipe (Verizon)	164	Side Arm Mount [SO 308-1] (Municipal)	146
BXA-70063-6CF-EDIN-X w/Mount Pipe (Verizon)	164	Side Arm Mount [SO 308-1] (Municipal)	146
DB846F65ZAXY w/Mount Pipe (Verizon)	164	2' Standoff (Dish)	138
DB846F65ZAXY w/Mount Pipe (Verizon)	164	Andrew 3' w/Radome (Sprint)	138

ALL REAC ARE FACT  
MAX. COR DOWN: SHEAR  
UPLIFT: SHEAR.

**SYMBOL LIST**

MARK	SIZE	MARK	SIZE
A	P2x.154	C	2L3x3x1/4x3/8
B	2L2 1/2x2 1/2x3/16x3/8		


**MATERIAL STRENGTH**

GRADE	Fy	Fu	GRADE	Fy	Fu
A572-50	50 ksi	65 ksi	A36	36 ksi	58 ksi

**TOWER DESIGN NOTES**

- Tower is located in Fairfield County, Connecticut.
- Tower designed for Exposure B to the TIA-222-G Standard.
- Tower designed for a 93 mph basic wind in accordance with the TIA-222-G Standard.
- Tower is also designed for a 50 mph basic wind with 0.75 in ice. Ice is considered to increase in thickness with height.
- Deflections are based upon a 60 mph wind.
- Tower Structure Class II.
- Topographic Category 1 with Crest Height of 0.00 ft
- TOWER RATING: 98.8%

Section	T1	T2	T3	T4	T5	T6	T7	T8	T9	T10	T11	T12	T13
Legs	P2.5x.203		P2.5x.375	P3.5x.318	P5x.258	P5x.375				P5x.5		P8x.322	
Leg Grade													
Diagonals													
Diagonal Grade													
Top Glirts													
Horizontals													
Sec. Horizontals													
Red. Horizontals													
Red. Diagonals													
Face Width (ft)													
# Panels @ (ft)													
Weight (lb)													



**Ramaker & Associates, Inc.**  
855 Community Drive  
Sauk City, WI 53583  
Phone: (608) 643-4100  
FAX: (608) 643-7999

**Job: Transfer Station (CT33XC522)**

Project: 28737

Client: Transcend Wireless / Sprint    Drawn by: TEM    App'd:

Code: TIA-222-G    Date: 09/26/17    Scale: NTS

Path: I:\28700\28737\Structural\trnx\28737 rev3.rvt    Dwg No. E-1

**SYMBOL LIST**

MARK	SIZE	MARK	SIZE
A	P2x.154	C	2L3x3x1/4x3/8
B	2L2 1/2x2 1/2x3/16x3/8		


**MATERIAL STRENGTH**

GRADE	Fy	Fu	GRADE	Fy	Fu
A572-50	50 ksi	65 ksi	A36	36 ksi	58 ksi

**TOWER DESIGN NOTES**

1. Tower is located in Fairfield County, Connecticut.
2. Tower designed for Exposure B to the TIA-222-G Standard.
3. Tower designed for a 93 mph basic wind in accordance with the TIA-222-G Standard.
4. Tower is also designed for a 50 mph basic wind with 0.75 in ice. Ice is considered to increase in thickness with height.
5. Deflections are based upon a 60 mph wind.
6. Tower Structure Class II.
7. Topographic Category 1 with Crest Height of 0.00 ft
8. TOWER RATING: 98.8%

Section	T1	T2	T3	T4	T5	T6	T7	T8	T9	T10	T11	T12	T13
Legs		P2.5x.203	P2.5x.375	P3.5x.318	P5x.258	P5x.375				P5x.5		P8x.322	
Leg Grade						A572-50							
Diagonals				L2x2x3/16	L2 1/2x2 1/2x3/16	B			L3x3x3/16	C		L3 1/2x3 1/2x1/4	
Diagonal Grade													
Top Girts						A36							
Horizontals				L2x2x1/4	L2 1/2x2 1/2x3/8				L3x3x3/8			L3x3x1/2	
Sec. Horizontals													
Red. Horizontals					L3x3x1/2				L3x3x1/2			L3x3x1/2	
Red. Diagonals					L3x3x1/2				L3x3x1/2			L3x3x1/2	
Face Width (ft)									13 @ 12.33333	11	15	17	19
# Panels @ (ft)									6 @ 3.33333	6 @ 3.33333	4 @ 10	4 @ 5	4 @ 5
Weight (lb) 30434.0									5675.4	944.1	899.5	608.8	3028.5
									1608.6	936.4	652.3	148.5	




ALL REACTIONS ARE FACTORED


MAX. CORNER REACTIONS AT BASE:

DOWN: 347561 lb  
SHEAR: 37351 lb


UPLIFT: -293401 lb  
SHEAR: 31868 lb



TORQUE 2811 lb-ft  
50 mph WIND - 0.7500 in ICE




TORQUE 10383 lb-ft  
REACTIONS - 93 mph WIND

 <p><b>Ramaker &amp; Associates, Inc.</b> 855 Community Drive Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999</p>	<b>Job: Transfer Station (CT33XC522)</b>		
	Project: 28737		
	Client: Transcend Wireless / Sprint	Drawn by: TEM	App'd:
	Code: TIA-222-G	Date: 09/26/17	Scale: NTS
	Path: I:\28700\28737\Structural\trnx\28737_rev3.dwg		
		Dwg No. E-1	

# Feed Line Plan

— Round   
 — Flat   
 — App In Face   
 — App Out Face



<p><b>Ramaker &amp; Associates, Inc.</b>                  855 Community Drive                  Sauk City, WI 53583                  Phone: (608) 643-4100                  FAX: (608) 643-7999</p>	<b>Job: Transfer Station (CT33XC522)</b>		
	Project: <b>28737</b>		
	Client: Transcend Wireless / Sprint	Drawn by: TEM	App'd:
	Code: TIA-222-G	Date: 09/26/17	Scale: NTS
	Path: I:\28700\28737\Structural\trnx\28737_rev3.dwg		Dwg No. E-7

<b>tnxTower</b>  <b>Ramaker &amp; Associates, Inc.</b> 855 Community Drive Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b> Transfer Station (CT33XC522)	<b>Page</b> 1 of 37
	<b>Project</b> 28737	<b>Date</b> 15:01:07 09/26/17
	<b>Client</b> Transcend Wireless / Sprint	<b>Designed by</b> TEM

## Tower Input Data

The main tower is a 3x free standing tower with an overall height of 185.00 ft above the ground line.

The base of the tower is set at an elevation of 0.00 ft above the ground line.

The face width of the tower is 5.00 ft at the top and 21.00 ft at the base.

This tower is designed using the TIA-222-G standard.

The following design criteria apply:

Tower is located in Fairfield County, Connecticut.

ASCE 7-10 Wind Data is used (wind speeds converted to nominal values).

Basic wind speed of 93 mph.

Structure Class II.

Exposure Category B.

Topographic Category 1.

Crest Height 0.00 ft.

Nominal ice thickness of 0.7500 in.

Ice thickness is considered to increase with height.

Ice density of 56 pcf.

A wind speed of 50 mph is used in combination with ice.

Temperature drop of 50 °F.


Deflections calculated using a wind speed of 60 mph.

A non-linear (P-delta) analysis was used.

Pressures are calculated at each section.

Stress ratio used in tower member design is 1.

Local bending stresses due to climbing loads, feed line supports, and appurtenance mounts are not considered.



**Triangular Tower**

<b>tnxTower</b>  <b>Ramaker &amp; Associates, Inc.</b> 855 Community Drive Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b> Transfer Station (CT33XC522)	<b>Page</b> 2 of 37
	<b>Project</b> 28737	<b>Date</b> 15:01:07 09/26/17
	<b>Client</b> Transcend Wireless / Sprint	<b>Designed by</b> TEM

### Tower Section Geometry

Tower Section	Tower Elevation <i>ft</i>	Assembly Database	Description	Section Width <i>ft</i>	Number of Sections	Section Length <i>ft</i>
T1	185.00-180.00			5.00	1	5.00
T2	180.00-160.00			5.00	1	20.00
T3	160.00-140.00			5.00	1	20.00
T4	140.00-120.00			7.00	1	20.00
T5	120.00-100.00			9.00	1	20.00
T6	100.00-93.33			11.00	1	6.67
T7	93.33-86.67			11.67	1	6.67
T8	86.67-80.00			12.33	1	6.67
T9	80.00-60.00			13.00	1	20.00
T10	60.00-50.00			15.00	1	10.00
T11	50.00-40.00			16.00	1	10.00
T12	40.00-20.00			17.00	1	20.00
T13	20.00-0.00			19.00	1	20.00

### Tower Section Geometry (cont'd)

Tower Section	Tower Elevation <i>ft</i>	Diagonal Spacing <i>ft</i>	Bracing Type	Has K Brace End Panels	Has Horizontals	Top Girt Offset <i>in</i>	Bottom Girt Offset <i>in</i>
T1	185.00-180.00	5.00	X Brace	No	Yes	0.0000	0.0000
T2	180.00-160.00	5.00	X Brace	No	Yes	0.0000	0.0000
T3	160.00-140.00	5.00	X Brace	No	Yes	0.0000	0.0000
T4	140.00-120.00	5.00	X Brace	No	Yes	0.0000	0.0000
T5	120.00-100.00	3.33	Double K1	No	Yes	0.0000	0.0000
T6	100.00-93.33	6.67	X Brace	No	Yes	0.0000	0.0000
T7	93.33-86.67	6.67	X Brace	No	Yes	0.0000	0.0000
T8	86.67-80.00	6.67	X Brace	No	Yes	0.0000	0.0000
T9	80.00-60.00	3.33	Double K1	No	Yes	0.0000	0.0000
T10	60.00-50.00	10.00	X Brace	No	Yes	0.0000	0.0000
T11	50.00-40.00	10.00	X Brace	No	Yes	0.0000	0.0000
T12	40.00-20.00	10.00	X Brace	No	Yes	0.0000	0.0000
T13	20.00-0.00	5.00	Double K1	No	Yes	0.0000	0.0000

### Tower Section Geometry (cont'd)

Tower Elevation <i>ft</i>	Leg Type	Leg Size	Leg Grade	Diagonal Type	Diagonal Size	Diagonal Grade
T1 185.00-180.00	Pipe	P2x.154	A572-50 (50 ksi)	Equal Angle	L2x2x1/8	A36 (36 ksi)
T2 180.00-160.00	Pipe	P2.5x.203	A572-50 (50 ksi)	Equal Angle	L2x2x1/8	A36 (36 ksi)
T3 160.00-140.00	Pipe	P2.5x.375	A572-50 (50 ksi)	Equal Angle	L2x2x1/8	A36 (36 ksi)
T4 140.00-120.00	Pipe	P3.5x.318	A572-50 (50 ksi)	Equal Angle	L2x2x3/16	A36 (36 ksi)

<b>tnxTower</b>  <b>Ramaker &amp; Associates, Inc.</b> 855 Community Drive Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b> Transfer Station (CT33XC522)	<b>Page</b> 3 of 37
	<b>Project</b> 28737	<b>Date</b> 15:01:07 09/26/17
	<b>Client</b> Transcend Wireless / Sprint	<b>Designed by</b> TEM

Tower Elevation ft	Leg Type	Leg Size	Leg Grade	Diagonal Type	Diagonal Size	Diagonal Grade
T5 120.00-100.00	Pipe	P5x.258	A572-50 (50 ksi)	Equal Angle	L2 1/2x2 1/2x3/16	A36 (36 ksi)
T6 100.00-93.33	Pipe	P5x.375	A572-50 (50 ksi)	Equal Angle	L2 1/2x2 1/2x3/16	A36 (36 ksi)
T7 93.33-86.67	Pipe	P5x.375	A572-50 (50 ksi)	Equal Angle	L2 1/2x2 1/2x3/16	A36 (36 ksi)
T8 86.67-80.00	Pipe	P5x.375	A572-50 (50 ksi)	Double Equal Angle	2L2 1/2x2 1/2x3/16x3/8	A36 (36 ksi)
T9 80.00-60.00	Pipe	P5x.375	A572-50 (50 ksi)	Equal Angle	L3x3x3/16	A36 (36 ksi)
T10 60.00-50.00	Pipe	P5x.5	A572-50 (50 ksi)	Equal Angle	L3x3x1/4	A36 (36 ksi)
T11 50.00-40.00	Pipe	P5x.5	A572-50 (50 ksi)	Double Equal Angle	2L3x3x1/4x3/8	A36 (36 ksi)
T12 40.00-20.00	Pipe	P8x.322	A572-50 (50 ksi)	Equal Angle	L3 1/2x3 1/2x1/4	A36 (36 ksi)
T13 20.00-0.00	Pipe	P8x.322	A572-50 (50 ksi)	Equal Angle	L3 1/2x3 1/2x1/4	A36 (36 ksi)

### Tower Section Geometry (cont'd)

Tower Elevation ft	Top Girt Type	Top Girt Size	Top Girt Grade	Bottom Girt Type	Bottom Girt Size	Bottom Girt Grade
T1 185.00-180.00	Equal Angle	L2x2x1/8	A36 (36 ksi)	Equal Angle		A36 (36 ksi)
T2 180.00-160.00	Equal Angle	L2x2x1/8	A36 (36 ksi)	Equal Angle		A36 (36 ksi)
T3 160.00-140.00	Equal Angle	L2x2x1/8	A36 (36 ksi)	Equal Angle		A36 (36 ksi)

### Tower Section Geometry (cont'd)

Tower Elevation ft	No. of Mid Girts	Mid Girt Type	Mid Girt Size	Mid Girt Grade	Horizontal Type	Horizontal Size	Horizontal Grade
T5 120.00-100.00	None	Solid Round		A572-50 (50 ksi)	Equal Angle	L2 1/2x2 1/2x3/8	A36 (36 ksi)
T9 80.00-60.00	None	Solid Round		A572-50 (50 ksi)	Equal Angle	L3x3x3/8	A36 (36 ksi)
T13 20.00-0.00	None	Solid Round		A572-50 (50 ksi)	Equal Angle	L3 1/2x3 1/2x1/2	A36 (36 ksi)

### Tower Section Geometry (cont'd)

<b>tnxTower</b>  <b>Ramaker &amp; Associates, Inc.</b> 855 Community Drive Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b> Transfer Station (CT33XC522)	<b>Page</b> 4 of 37
	<b>Project</b> 28737	<b>Date</b> 15:01:07 09/26/17
	<b>Client</b> Transcend Wireless / Sprint	<b>Designed by</b> TEM

Tower Elevation <i>ft</i>	Secondary Horizontal Type	Secondary Horizontal Size	Secondary Horizontal Grade	Inner Bracing Type	Inner Bracing Size	Inner Bracing Grade
T4 140.00-120.00	Equal Angle	L2x2x1/4	A36 (36 ksi)	Equal Angle		A36 (36 ksi)
T10 60.00-50.00	Equal Angle	L3x3x7/16	A36 (36 ksi)	Equal Angle		A36 (36 ksi)
T11 50.00-40.00	Equal Angle	L3x3x7/16	A36 (36 ksi)	Equal Angle		A36 (36 ksi)
T12 40.00-20.00	Equal Angle	L3x3x1/2	A36 (36 ksi)	Equal Angle		A36 (36 ksi)

### Tower Section Geometry (cont'd)

Tower Elevation <i>ft</i>	Redundant Bracing Grade	Redundant Type	Redundant Size	K Factor
T5 120.00-100.00	A36 (36 ksi)	Horizontal (1) Diagonal (1)	Equal Angle L3x3x1/2	1
T9 80.00-60.00	A36 (36 ksi)	Horizontal (1) Diagonal (1)	Equal Angle L3x3x1/2	1
T13 20.00-0.00	A36 (36 ksi)	Horizontal (1) Diagonal (1)	Equal Angle L3x3x1/2	1

### Tower Section Geometry (cont'd)

Tower Elevation <i>ft</i>	Gusset Area (per face) <i>ft<sup>2</sup></i>	Gusset Thickness <i>in</i>	Gusset Grade	Adjust. Factor <i>A<sub>f</sub></i>	Adjust. Factor <i>A<sub>r</sub></i>	Weight Mult.	Double Angle Stitch Bolt Spacing Diagonals <i>in</i>	Double Angle Stitch Bolt Spacing Horizontal <i>in</i>	Double Angle Stitch Bolt Spacing Redundants <i>in</i>
T1 185.00-180.00	0.00	0.3750	A36 (36 ksi)	1	1	1	36.0000	36.0000	36.0000
T2 180.00-160.00	0.00	0.3750	A36 (36 ksi)	1	1	1	36.0000	36.0000	36.0000
T3 160.00-140.00	0.00	0.3750	A36 (36 ksi)	1	1	1	36.0000	36.0000	36.0000
T4 140.00-120.00	0.00	0.3750	A36 (36 ksi)	1	1	1	36.0000	36.0000	36.0000
T5 120.00-100.00	0.00	0.3750	A36 (36 ksi)	1	1	1	36.0000	36.0000	36.0000
T6 100.00-93.33	0.00	0.3750	A36 (36 ksi)	1	1	1	36.0000	36.0000	36.0000
T7 93.33-86.67	0.00	0.3750	A36 (36 ksi)	1	1	1	36.0000	36.0000	36.0000
T8 86.67-80.00	0.00	0.3750	A36 (36 ksi)	1	1	1	Third-Pt	36.0000	36.0000
T9 80.00-60.00	0.00	0.3750	A36 (36 ksi)	1	1	1	36.0000	36.0000	36.0000
T10 60.00-50.00	0.00	0.3750	A36 (36 ksi)	1	1	1	36.0000	36.0000	36.0000
T11 50.00-40.00	0.00	0.3750	A36 (36 ksi)	1	1	1	Third-Pt	36.0000	36.0000
T12 40.00-20.00	0.00	0.3750	A36	1	1	1	36.0000	36.0000	36.0000





<b>tnxTower</b>  <b>Ramaker &amp; Associates, Inc.</b> 855 Community Drive Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b>	Transfer Station (CT33XC522)	<b>Page</b>	6 of 37
	<b>Project</b>	28737	<b>Date</b>	15:01:07 09/26/17
	<b>Client</b>	Transcend Wireless / Sprint	<b>Designed by</b>	TEM

Tower Elevation ft	Leg		Diagonal		Top Girt		Bottom Girt		Mid Girt		Long Horizontal		Short Horizontal	
	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U
T3 160.00-140.00	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1
T4 140.00-120.00	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1
T5 120.00-100.00	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1
T6 100.00-93.33	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1
T7 93.33-86.67	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1
T8 86.67-80.00	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1
T9 80.00-60.00	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1
T10 60.00-50.00	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1
T11 50.00-40.00	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1
T12 40.00-20.00	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1
T13 20.00-0.00	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1

### Tower Section Geometry (cont'd)

Tower Elevation ft	Leg Connection Type	Leg		Diagonal		Top Girt		Bottom Girt		Mid Girt		Long Horizontal		Short Horizontal	
		Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.
T1 185.00-180.00	Flange	0.7500	6	0.6250	1	0.6250	1	0.0000	0	0.6250	0	0.6250	0	0.6250	0
		A325X		A325X		A325X		A325X		A325X		A325N		A325N	
T2 180.00-160.00	Flange	0.7500	6	0.6250	1	0.6250	1	0.6250	0	0.6250	0	0.6250	0	0.6250	0
		A325X		A325X		A325X		A325X		A325X		A325N		A325N	
T3 160.00-140.00	Flange	1.0000	6	0.6250	1	0.6250	1	0.6250	0	0.6250	0	0.6250	0	0.6250	0
		A325X		A325X		A325X		A325X		A325X		A325N		A325N	
T4 140.00-120.00	Flange	1.0000	6	0.6250	1	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.7500	1
		A325X		A325X		A325X		A325X		A325X		A325N		A325N	
T5 120.00-100.00	Flange	1.0000	6	0.6250	1	0.6250	0	0.6250	0	0.6250	0	0.7500	1	0.6250	0
		A325X		A325X		A325X		A325X		A325X		A325N		A325N	
T6 100.00-93.33	Flange	1.0000	0	0.6250	1	0.6250	0	0.0000	0	0.6250	0	0.6250	0	0.6250	0
		A325X		A325X		A325X		A325X		A325X		A325N		A325N	
T7 93.33-86.67	Flange	1.0000	0	0.6250	1	0.6250	0	0.0000	0	0.6250	0	0.6250	0	0.6250	0
		A325X		A325X		A325N		A325X		A325X		A325N		A325N	
T8 86.67-80.00	Flange	1.0000	6	0.6250	1	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
		A325X		A325X		A325N		A325X		A325X		A325N		A325N	
T9 80.00-60.00	Flange	1.0000	6	0.7500	1	0.7500	0	0.6250	0	0.6250	0	0.7500	1	0.7500	0
		A325X		A325X		A325X		A325X		A325X		A325N		A325N	
T10 60.00-50.00	Flange	1.2500	0	0.7500	1	0.7500	0	0.0000	0	0.6250	0	0.7500	0	0.7500	1
		A325X		A325X		A325X		A325X		A325X		A325N		A325N	
T11 50.00-40.00	Flange	1.2500	6	0.7500	1	0.7500	0	0.6250	0	0.6250	0	0.7500	0	0.7500	1
		A325X		A325X		A325N		A325X		A325X		A325N		A325N	
T12 40.00-20.00	Flange	1.2500	6	0.7500	1	0.7500	0	0.6250	0	0.6250	0	0.7500	0	0.7500	1
		A325X		A325X		A325X		A325X		A325X		A325N		A325N	
T13 20.00-0.00	Flange	1.5000	0	0.7500	1	0.7500	0	0.6250	0	0.6250	0	0.7500	1	0.7500	0
		A572-50		A325X		A325X		A325X		A325X		A325N		A325N	

**Feed Line/Linear Appurtenances - Entered As Round Or Flat**

<b>tnxTower</b>  <b>Ramaker &amp; Associates, Inc.</b> 855 Community Drive Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b>	Transfer Station (CT33XC522)	<b>Page</b>	7 of 37
	<b>Project</b>	28737	<b>Date</b>	15:01:07 09/26/17
	<b>Client</b>	Transcend Wireless / Sprint	<b>Designed by</b>	TEM

Description	Face or Leg	Allow Shield	Component Type	Placement ft	Face Offset in	Lateral Offset (Frac FW)	#	# Per Row	Clear Spacing in	Width or Diameter in	Perimeter in	Weight plf
*****												
Climbing Ladder (Af) (Tower)	A	No	Af (CaAa)	185.00 - 0.00	0.0000	0.1	1	1	1.8000	2.5000		7.90
Safety Line 3/8 (Tower)	A	No	Ar (CaAa)	185.00 - 0.00	3.0000	0.1	1	1	0.3750	0.3750		0.22
*****												
Feedline Ladder (Af) (Municipal - 185) 7/8	B	No	Af (CaAa)	185.00 - 0.00	-1.0000	0	1	1	3.0000	3.0000		8.40
(Municipal - 185)	B	No	Ar (CaAa)	185.00 - 0.00	-2.0000	-0.02	3	3	1.0000	1.1100		0.54
*****												
Feedline Ladder (Af) (T-Mobile - 185) 1 5/8	B	No	Af (CaAa)	185.00 - 0.00	0.0000	0	1	1	3.0000	3.0000		8.40
(T-Mobile - 185)	B	No	Ar (CaAa)	185.00 - 0.00	0.0000	0	12	6	1.0000	1.9800		1.04
(T-Mobile - 185)	B	No	Ar (CaAa)	185.00 - 0.00	0.0000	0.06	1	1	1.5500	1.5500		0.66
*****												
Feedline Ladder (Af) (Tower - 180)	C	No	Af (CaAa)	180.00 - 0.00	-1.0000	0.1	1	1	3.0000	3.0000		8.40
*****												
Feedline Ladder (Af) (Sprint - 180) 1 1/4	C	No	Af (CaAa)	180.00 - 0.00	0.0000	0.1	1	1	3.0000	3.0000		8.40
(Sprint - 174)	C	No	Ar (CaAa)	174.00 - 0.00	0.0000	0.08	3	3	0.7500	1.5500		0.66
(Sprint - 174)	C	No	Ar (CaAa)	174.00 - 0.00	0.0000	0.12	1	1	1.5500	1.5500		0.66
*****												
Feedline Ladder (Af) (Verizon - 164) 1 5/8	A	No	Af (CaAa)	164.00 - 0.00	-1.0000	-0.1	1	1	3.0000	3.0000		8.40
(Verizon - 164)	A	No	Ar (CaAa)	164.00 - 0.00	-4.0000	-0.08	18	9	1.0000	1.9800		1.04
(Verizon - 164)	A	No	Ar (CaAa)	164.00 - 0.00	-2.0000	-0.14	1	1	1.9800	1.9800		1.04
*****												
Feedline Ladder (Af) (ATT - 154) 1 5/8	A	No	Af (CaAa)	154.00 - 0.00	0.0000	-0.1	1	1	3.0000	3.0000		8.40
(ATT - 154)	A	No	Ar (CaAa)	154.00 - 0.00	0.0000	-0.07	12	6	1.0000	1.9800		1.04
Power Cable (ATT - 154)	A	No	Ar (CaAa)	154.00 - 0.00	0.0000	-0.12	2	2	1.0000	0.8750		0.60
Fiber Cable (ATT - 154)	A	No	Ar (CaAa)	154.00 - 0.00	0.0000	-0.14	1	1	0.7875	0.7875		0.17
*****												
7/8 (Municipal - 146)	B	No	Ar (CaAa)	146.00 - 0.00	-2.0000	0.01	4	4	1.0000	1.1100		0.54
*****												
1/2 (Municipal - 138)	B	No	Ar (CaAa)	138.00 - 0.00	-2.0000	0.03	1	1	0.5800	0.5800		0.25
*****												

### Feed Line/Linear Appurtenances - Entered As Area

Description	Face or Leg	Allow Shield	Component Type	Placement ft	Total Number	C <sub>A</sub> A <sub>A</sub> ft <sup>2</sup> /ft	Weight plf
-------------	-------------	--------------	----------------	-----------------	--------------	--	---------------

<b>tnxTower</b>  <b>Ramaker &amp; Associates, Inc.</b> 855 Community Drive Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b> Transfer Station (CT33XC522)	<b>Page</b> 8 of 37
	<b>Project</b> 28737	<b>Date</b> 15:01:07 09/26/17
	<b>Client</b> Transcend Wireless / Sprint	<b>Designed by</b> TEM

Description	Face or Leg	Allow Shield	Component Type	Placement ft	Total Number	C <sub>A</sub> A <sub>A</sub> ft <sup>2</sup> /ft	Weight plf
*****							

### Feed Line/Linear Appurtenances Section Areas

Tower Section	Tower Elevation ft	Face	A <sub>R</sub> ft <sup>2</sup>	A <sub>F</sub> ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> In Face ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> Out Face ft <sup>2</sup>	Weight lb
T1	185.00-180.00	A	0.000	0.000	2.271	0.000	40.60
		B	0.000	0.000	19.320	0.000	157.80
		C	0.000	0.000	0.000	0.000	0.00
T2	180.00-160.00	A	0.000	0.000	26.131	0.000	275.04
		B	0.000	0.000	77.280	0.000	631.20
		C	0.000	0.000	28.680	0.000	372.96
T3	160.00-140.00	A	0.000	0.000	138.140	0.000	1037.10
		B	0.000	0.000	79.944	0.000	644.16
		C	0.000	0.000	32.400	0.000	388.80
T4	140.00-120.00	A	0.000	0.000	156.918	0.000	1170.60
		B	0.000	0.000	87.204	0.000	678.90
		C	0.000	0.000	32.400	0.000	388.80
T5	120.00-100.00	A	0.000	0.000	156.918	0.000	1170.60
		B	0.000	0.000	87.320	0.000	679.40
		C	0.000	0.000	32.400	0.000	388.80
T6	100.00-93.33	A	0.000	0.000	52.306	0.000	390.20
		B	0.000	0.000	29.107	0.000	226.47
		C	0.000	0.000	10.800	0.000	129.60
T7	93.33-86.67	A	0.000	0.000	52.306	0.000	390.20
		B	0.000	0.000	29.107	0.000	226.47
		C	0.000	0.000	10.800	0.000	129.60
T8	86.67-80.00	A	0.000	0.000	52.306	0.000	390.20
		B	0.000	0.000	29.107	0.000	226.47
		C	0.000	0.000	10.800	0.000	129.60
T9	80.00-60.00	A	0.000	0.000	156.918	0.000	1170.60
		B	0.000	0.000	87.320	0.000	679.40
		C	0.000	0.000	32.400	0.000	388.80
T10	60.00-50.00	A	0.000	0.000	78.459	0.000	585.30
		B	0.000	0.000	43.660	0.000	339.70
		C	0.000	0.000	16.200	0.000	194.40
T11	50.00-40.00	A	0.000	0.000	78.459	0.000	585.30
		B	0.000	0.000	43.660	0.000	339.70
		C	0.000	0.000	16.200	0.000	194.40
T12	40.00-20.00	A	0.000	0.000	156.918	0.000	1170.60
		B	0.000	0.000	87.320	0.000	679.40
		C	0.000	0.000	32.400	0.000	388.80
T13	20.00-0.00	A	0.000	0.000	156.918	0.000	1170.60
		B	0.000	0.000	87.320	0.000	679.40
		C	0.000	0.000	32.400	0.000	388.80

### Feed Line/Linear Appurtenances Section Areas - With Ice

Tower Section	Tower Elevation ft	Face or Leg	Ice Thickness in	A <sub>R</sub> ft <sup>2</sup>	A <sub>F</sub> ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> In Face ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> Out Face ft <sup>2</sup>	Weight lb
T1	185.00-180.00	A	1.780	0.000	0.000	5.830	0.000	121.95
		B		0.000	0.000	31.230	0.000	643.61
		C		0.000	0.000	0.000	0.000	0.00

<b>tnxTower</b>  <b>Ramaker &amp; Associates, Inc.</b> 855 Community Drive Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b> Transfer Station (CT33XC522)	<b>Page</b> 9 of 37
	<b>Project</b> 28737	<b>Date</b> 15:01:07 09/26/17
	<b>Client</b> Transcend Wireless / Sprint	<b>Designed by</b> TEM

Tower Section	Tower Elevation ft	Face or Leg	Ice Thickness in	A <sub>R</sub> ft <sup>2</sup>	A <sub>F</sub> ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> In Face ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> Out Face ft <sup>2</sup>	Weight lb
T2	180.00-160.00	A	1.767	0.000	0.000	44.120	0.000	972.18
		B		0.000	0.000	124.603	0.000	2560.43
		C		0.000	0.000	60.397	0.000	1194.05
T3	160.00-140.00	A	1.745	0.000	0.000	197.025	0.000	4282.74
		B		0.000	0.000	132.941	0.000	2646.73
		C		0.000	0.000	71.239	0.000	1325.94
T4	140.00-120.00	A	1.720	0.000	0.000	225.855	0.000	4826.54
		B		0.000	0.000	160.143	0.000	2963.94
		C		0.000	0.000	70.774	0.000	1308.40
T5	120.00-100.00	A	1.692	0.000	0.000	224.610	0.000	4769.95
		B		0.000	0.000	159.927	0.000	2934.17
		C		0.000	0.000	70.240	0.000	1288.40
T6	100.00-93.33	A	1.670	0.000	0.000	74.554	0.000	1575.69
		B		0.000	0.000	53.050	0.000	967.97
		C		0.000	0.000	23.278	0.000	424.43
T7	93.33-86.67	A	1.658	0.000	0.000	74.381	0.000	1567.90
		B		0.000	0.000	52.908	0.000	962.48
		C		0.000	0.000	23.203	0.000	421.68
T8	86.67-80.00	A	1.646	0.000	0.000	74.196	0.000	1559.59
		B		0.000	0.000	52.756	0.000	956.62
		C		0.000	0.000	23.124	0.000	418.76
T9	80.00-60.00	A	1.617	0.000	0.000	221.346	0.000	4623.30
		B		0.000	0.000	157.252	0.000	2830.78
		C		0.000	0.000	68.840	0.000	1236.77
T10	60.00-50.00	A	1.579	0.000	0.000	109.832	0.000	2274.38
		B		0.000	0.000	77.937	0.000	1389.15
		C		0.000	0.000	34.059	0.000	605.32
T11	50.00-40.00	A	1.547	0.000	0.000	109.148	0.000	2244.30
		B		0.000	0.000	77.377	0.000	1367.98
		C		0.000	0.000	33.766	0.000	594.80
T12	40.00-20.00	A	1.486	0.000	0.000	215.616	0.000	4372.00
		B		0.000	0.000	152.560	0.000	2654.03
		C		0.000	0.000	66.381	0.000	1148.97
T13	20.00-0.00	A	1.331	0.000	0.000	208.884	0.000	4086.69
		B		0.000	0.000	147.054	0.000	2454.06
		C		0.000	0.000	63.493	0.000	1050.43

### Feed Line Center of Pressure

Section	Elevation ft	CP <sub>X</sub> in	CP <sub>Z</sub> in	CP <sub>X</sub> Ice in	CP <sub>Z</sub> Ice in
T1	185.00-180.00	2.4367	-1.8693	1.6105	-1.8668
T2	180.00-160.00	1.0705	-0.5760	0.5346	-0.2669
T3	160.00-140.00	-1.2764	-0.8055	-1.1451	-0.4684
T4	140.00-120.00	-1.8019	-1.1270	-1.4390	-0.7044
T5	120.00-100.00	-2.0796	-1.2909	-1.7049	-0.7902
T6	100.00-93.33	-2.5637	-1.5844	-2.0528	-1.0311
T7	93.33-86.67	-2.7141	-1.6743	-2.1685	-1.0906
T8	86.67-80.00	-2.8635	-1.7635	-2.2834	-1.1498
T9	80.00-60.00	-2.7703	-1.7015	-2.2000	-1.0560
T10	60.00-50.00	-3.4191	-2.0946	-2.7266	-1.3819
T11	50.00-40.00	-3.6283	-2.2196	-2.8915	-1.4697
T12	40.00-20.00	-3.7451	-2.2868	-3.0456	-1.5568
T13	20.00-0.00	-3.8295	-2.3336	-3.0913	-1.6030

<b>tnxTower</b>  <b>Ramaker &amp; Associates, Inc.</b> 855 Community Drive Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b> Transfer Station (CT33XC522)	<b>Page</b> 10 of 37
	<b>Project</b> 28737	<b>Date</b> 15:01:07 09/26/17
	<b>Client</b> Transcend Wireless / Sprint	<b>Designed by</b> TEM

## Shielding Factor Ka

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K <sub>a</sub> No Ice	K <sub>a</sub> Ice
T1	2	Climbing Ladder (Af)	180.00 - 185.00	0.6000	0.5100
T1	3	Safety Line 3/8	180.00 - 185.00	0.6000	0.5100
T1	8	Feedline Ladder (Af)	180.00 - 185.00	0.6000	0.5100
T1	9	7/8	180.00 - 185.00	0.6000	0.5100
T1	11	Feedline Ladder (Af)	180.00 - 185.00	0.6000	0.5100
T1	12	1 5/8	180.00 - 185.00	0.6000	0.5100
T1	13	1 1/4	180.00 - 185.00	0.6000	0.5100
T2	2	Climbing Ladder (Af)	160.00 - 180.00	0.6000	0.5623
T2	3	Safety Line 3/8	160.00 - 180.00	0.6000	0.5623
T2	8	Feedline Ladder (Af)	160.00 - 180.00	0.6000	0.5623
T2	9	7/8	160.00 - 180.00	0.6000	0.5623
T2	11	Feedline Ladder (Af)	160.00 - 180.00	0.6000	0.5623
T2	12	1 5/8	160.00 - 180.00	0.6000	0.5623
T2	13	1 1/4	160.00 - 180.00	0.6000	0.5623
T2	15	Feedline Ladder (Af)	160.00 - 180.00	0.6000	0.5623
T2	17	Feedline Ladder (Af)	160.00 - 180.00	0.6000	0.5623
T2	18	1 1/4	160.00 - 174.00	0.6000	0.5623
T2	19	1 1/4	160.00 - 174.00	0.6000	0.5623
T2	21	Feedline Ladder (Af)	160.00 - 164.00	0.6000	0.5623
T2	22	1 5/8	160.00 - 164.00	0.6000	0.5623
T2	23	1 5/8	160.00 - 164.00	0.6000	0.5623
T3	2	Climbing Ladder (Af)	140.00 - 160.00	0.6000	0.6000
T3	3	Safety Line 3/8	140.00 - 160.00	0.6000	0.6000
T3	8	Feedline Ladder (Af)	140.00 - 160.00	0.6000	0.6000
T3	9	7/8	140.00 - 160.00	0.6000	0.6000
T3	11	Feedline Ladder (Af)	140.00 - 160.00	0.6000	0.6000
T3	12	1 5/8	140.00 - 160.00	0.6000	0.6000
T3	13	1 1/4	140.00 - 160.00	0.6000	0.6000
T3	15	Feedline Ladder (Af)	140.00 - 160.00	0.6000	0.6000
T3	17	Feedline Ladder (Af)	140.00 - 160.00	0.6000	0.6000
T3	18	1 1/4	140.00 - 160.00	0.6000	0.6000
T3	19	1 1/4	140.00 - 160.00	0.6000	0.6000
T3	21	Feedline Ladder (Af)	140.00 - 160.00	0.6000	0.6000
T3	22	1 5/8	140.00 - 160.00	0.6000	0.6000
T3	23	1 5/8	140.00 - 160.00	0.6000	0.6000
T3	25	Feedline Ladder (Af)	140.00 - 154.00	0.6000	0.6000
T3	26	1 5/8	140.00 - 154.00	0.6000	0.6000
T3	27	Power Cable	140.00 - 154.00	0.6000	0.6000
T3	28	Fiber Cable	140.00 - 154.00	0.6000	0.6000
T3	30	7/8	140.00 - 146.00	0.6000	0.6000
T4	2	Climbing Ladder (Af)	120.00 - 140.00	0.6000	0.5847
T4	3	Safety Line 3/8	120.00 - 140.00	0.6000	0.5847
T4	8	Feedline Ladder (Af)	120.00 - 140.00	0.6000	0.5847
T4	9	7/8	120.00 - 140.00	0.6000	0.5847
T4	11	Feedline Ladder (Af)	120.00 - 140.00	0.6000	0.5847
T4	12	1 5/8	120.00 - 140.00	0.6000	0.5847
T4	13	1 1/4	120.00 - 140.00	0.6000	0.5847
T4	15	Feedline Ladder (Af)	120.00 - 140.00	0.6000	0.5847
T4	17	Feedline Ladder (Af)	120.00 - 140.00	0.6000	0.5847
T4	18	1 1/4	120.00 - 140.00	0.6000	0.5847
T4	19	1 1/4	120.00 - 140.00	0.6000	0.5847
T4	21	Feedline Ladder (Af)	120.00 - 140.00	0.6000	0.5847
T4	22	1 5/8	120.00 - 140.00	0.6000	0.5847
T4	23	1 5/8	120.00 - 140.00	0.6000	0.5847
T4	25	Feedline Ladder (Af)	120.00 - 140.00	0.6000	0.5847

<b>Job</b>	Transfer Station (CT33XC522)	<b>Page</b>	11 of 37
<b>Project</b>	28737	<b>Date</b>	15:01:07 09/26/17
<b>Client</b>	Transcend Wireless / Sprint	<b>Designed by</b>	TEM

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K <sub>a</sub> No Ice	K <sub>a</sub> Ice
T4	26	1 5/8	120.00 - 140.00	0.6000	0.5847
T4	27	Power Cable	120.00 - 140.00	0.6000	0.5847
T4	28	Fiber Cable	120.00 - 140.00	0.6000	0.5847
T4	30	7/8	120.00 - 140.00	0.6000	0.5847
T4	32	1/2	120.00 - 138.00	0.6000	0.5847
T5	2	Climbing Ladder (Af)	100.00 - 120.00	0.6000	0.4900
T5	3	Safety Line 3/8	100.00 - 120.00	0.6000	0.4900
T5	8	Feedline Ladder (Af)	100.00 - 120.00	0.6000	0.4900
T5	9	7/8	100.00 - 120.00	0.6000	0.4900
T5	11	Feedline Ladder (Af)	100.00 - 120.00	0.6000	0.4900
T5	12	1 5/8	100.00 - 120.00	0.6000	0.4900
T5	13	1 1/4	100.00 - 120.00	0.6000	0.4900
T5	15	Feedline Ladder (Af)	100.00 - 120.00	0.6000	0.4900
T5	17	Feedline Ladder (Af)	100.00 - 120.00	0.6000	0.4900
T5	18	1 1/4	100.00 - 120.00	0.6000	0.4900
T5	19	1 1/4	100.00 - 120.00	0.6000	0.4900
T5	21	Feedline Ladder (Af)	100.00 - 120.00	0.6000	0.4900
T5	22	1 5/8	100.00 - 120.00	0.6000	0.4900
T5	23	1 5/8	100.00 - 120.00	0.6000	0.4900
T5	25	Feedline Ladder (Af)	100.00 - 120.00	0.6000	0.4900
T5	26	1 5/8	100.00 - 120.00	0.6000	0.4900
T5	27	Power Cable	100.00 - 120.00	0.6000	0.4900
T5	28	Fiber Cable	100.00 - 120.00	0.6000	0.4900
T5	30	7/8	100.00 - 120.00	0.6000	0.4900
T5	32	1/2	100.00 - 120.00	0.6000	0.4900
T6	2	Climbing Ladder (Af)	93.33 - 100.00	0.6000	0.6000
T6	3	Safety Line 3/8	93.33 - 100.00	0.6000	0.6000
T6	8	Feedline Ladder (Af)	93.33 - 100.00	0.6000	0.6000
T6	9	7/8	93.33 - 100.00	0.6000	0.6000
T6	11	Feedline Ladder (Af)	93.33 - 100.00	0.6000	0.6000
T6	12	1 5/8	93.33 - 100.00	0.6000	0.6000
T6	13	1 1/4	93.33 - 100.00	0.6000	0.6000
T6	15	Feedline Ladder (Af)	93.33 - 100.00	0.6000	0.6000
T6	17	Feedline Ladder (Af)	93.33 - 100.00	0.6000	0.6000
T6	18	1 1/4	93.33 - 100.00	0.6000	0.6000
T6	19	1 1/4	93.33 - 100.00	0.6000	0.6000
T6	21	Feedline Ladder (Af)	93.33 - 100.00	0.6000	0.6000
T6	22	1 5/8	93.33 - 100.00	0.6000	0.6000
T6	23	1 5/8	93.33 - 100.00	0.6000	0.6000
T6	25	Feedline Ladder (Af)	93.33 - 100.00	0.6000	0.6000
T6	26	1 5/8	93.33 - 100.00	0.6000	0.6000
T6	27	Power Cable	93.33 - 100.00	0.6000	0.6000
T6	28	Fiber Cable	93.33 - 100.00	0.6000	0.6000
T6	30	7/8	93.33 - 100.00	0.6000	0.6000
T6	32	1/2	93.33 - 100.00	0.6000	0.6000
T7	2	Climbing Ladder (Af)	86.67 - 93.33	0.6000	0.6000
T7	3	Safety Line 3/8	86.67 - 93.33	0.6000	0.6000
T7	8	Feedline Ladder (Af)	86.67 - 93.33	0.6000	0.6000
T7	9	7/8	86.67 - 93.33	0.6000	0.6000
T7	11	Feedline Ladder (Af)	86.67 - 93.33	0.6000	0.6000
T7	12	1 5/8	86.67 - 93.33	0.6000	0.6000
T7	13	1 1/4	86.67 - 93.33	0.6000	0.6000
T7	15	Feedline Ladder (Af)	86.67 - 93.33	0.6000	0.6000
T7	17	Feedline Ladder (Af)	86.67 - 93.33	0.6000	0.6000
T7	18	1 1/4	86.67 - 93.33	0.6000	0.6000
T7	19	1 1/4	86.67 - 93.33	0.6000	0.6000
T7	21	Feedline Ladder (Af)	86.67 - 93.33	0.6000	0.6000
T7	22	1 5/8	86.67 - 93.33	0.6000	0.6000
T7	23	1 5/8	86.67 - 93.33	0.6000	0.6000
T7	25	Feedline Ladder (Af)	86.67 - 93.33	0.6000	0.6000
T7	26	1 5/8	86.67 - 93.33	0.6000	0.6000
T7	27	Power Cable	86.67 - 93.33	0.6000	0.6000

<b>Job</b>	Transfer Station (CT33XC522)	<b>Page</b>	12 of 37
<b>Project</b>	28737	<b>Date</b>	15:01:07 09/26/17
<b>Client</b>	Transcend Wireless / Sprint	<b>Designed by</b>	TEM

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K <sub>a</sub> No Ice	K <sub>a</sub> Ice
T7	28	Fiber Cable	86.67 - 93.33	0.6000	0.6000
T7	30	7/8	86.67 - 93.33	0.6000	0.6000
T7	32	1/2	86.67 - 93.33	0.6000	0.6000
T8	2	Climbing Ladder (Af)	80.00 - 86.67	0.6000	0.6000
T8	3	Safety Line 3/8	80.00 - 86.67	0.6000	0.6000
T8	8	Feedline Ladder (Af)	80.00 - 86.67	0.6000	0.6000
T8	9	7/8	80.00 - 86.67	0.6000	0.6000
T8	11	Feedline Ladder (Af)	80.00 - 86.67	0.6000	0.6000
T8	12	1 5/8	80.00 - 86.67	0.6000	0.6000
T8	13	1 1/4	80.00 - 86.67	0.6000	0.6000
T8	15	Feedline Ladder (Af)	80.00 - 86.67	0.6000	0.6000
T8	17	Feedline Ladder (Af)	80.00 - 86.67	0.6000	0.6000
T8	18	1 1/4	80.00 - 86.67	0.6000	0.6000
T8	19	1 1/4	80.00 - 86.67	0.6000	0.6000
T8	21	Feedline Ladder (Af)	80.00 - 86.67	0.6000	0.6000
T8	22	1 5/8	80.00 - 86.67	0.6000	0.6000
T8	23	1 5/8	80.00 - 86.67	0.6000	0.6000
T8	25	Feedline Ladder (Af)	80.00 - 86.67	0.6000	0.6000
T8	26	1 5/8	80.00 - 86.67	0.6000	0.6000
T8	27	Power Cable	80.00 - 86.67	0.6000	0.6000
T8	28	Fiber Cable	80.00 - 86.67	0.6000	0.6000
T8	30	7/8	80.00 - 86.67	0.6000	0.6000
T8	32	1/2	80.00 - 86.67	0.6000	0.6000
T9	2	Climbing Ladder (Af)	60.00 - 80.00	0.6000	0.5244
T9	3	Safety Line 3/8	60.00 - 80.00	0.6000	0.5244
T9	8	Feedline Ladder (Af)	60.00 - 80.00	0.6000	0.5244
T9	9	7/8	60.00 - 80.00	0.6000	0.5244
T9	11	Feedline Ladder (Af)	60.00 - 80.00	0.6000	0.5244
T9	12	1 5/8	60.00 - 80.00	0.6000	0.5244
T9	13	1 1/4	60.00 - 80.00	0.6000	0.5244
T9	15	Feedline Ladder (Af)	60.00 - 80.00	0.6000	0.5244
T9	17	Feedline Ladder (Af)	60.00 - 80.00	0.6000	0.5244
T9	18	1 1/4	60.00 - 80.00	0.6000	0.5244
T9	19	1 1/4	60.00 - 80.00	0.6000	0.5244
T9	21	Feedline Ladder (Af)	60.00 - 80.00	0.6000	0.5244
T9	22	1 5/8	60.00 - 80.00	0.6000	0.5244
T9	23	1 5/8	60.00 - 80.00	0.6000	0.5244
T9	25	Feedline Ladder (Af)	60.00 - 80.00	0.6000	0.5244
T9	26	1 5/8	60.00 - 80.00	0.6000	0.5244
T9	27	Power Cable	60.00 - 80.00	0.6000	0.5244
T9	28	Fiber Cable	60.00 - 80.00	0.6000	0.5244
T9	30	7/8	60.00 - 80.00	0.6000	0.5244
T9	32	1/2	60.00 - 80.00	0.6000	0.5244
T10	2	Climbing Ladder (Af)	50.00 - 60.00	0.6000	0.6000
T10	3	Safety Line 3/8	50.00 - 60.00	0.6000	0.6000
T10	8	Feedline Ladder (Af)	50.00 - 60.00	0.6000	0.6000
T10	9	7/8	50.00 - 60.00	0.6000	0.6000
T10	11	Feedline Ladder (Af)	50.00 - 60.00	0.6000	0.6000
T10	12	1 5/8	50.00 - 60.00	0.6000	0.6000
T10	13	1 1/4	50.00 - 60.00	0.6000	0.6000
T10	15	Feedline Ladder (Af)	50.00 - 60.00	0.6000	0.6000
T10	17	Feedline Ladder (Af)	50.00 - 60.00	0.6000	0.6000
T10	18	1 1/4	50.00 - 60.00	0.6000	0.6000
T10	19	1 1/4	50.00 - 60.00	0.6000	0.6000
T10	21	Feedline Ladder (Af)	50.00 - 60.00	0.6000	0.6000
T10	22	1 5/8	50.00 - 60.00	0.6000	0.6000
T10	23	1 5/8	50.00 - 60.00	0.6000	0.6000
T10	25	Feedline Ladder (Af)	50.00 - 60.00	0.6000	0.6000
T10	26	1 5/8	50.00 - 60.00	0.6000	0.6000
T10	27	Power Cable	50.00 - 60.00	0.6000	0.6000
T10	28	Fiber Cable	50.00 - 60.00	0.6000	0.6000
T10	30	7/8	50.00 - 60.00	0.6000	0.6000

<b>Job</b>	Transfer Station (CT33XC522)	<b>Page</b>	13 of 37
<b>Project</b>	28737	<b>Date</b>	15:01:07 09/26/17
<b>Client</b>	Transcend Wireless / Sprint	<b>Designed by</b>	TEM

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K <sub>a</sub> No Ice	K <sub>a</sub> Ice
T10	32	1/2	50.00 - 60.00	0.6000	0.6000
T11	2	Climbing Ladder (Af)	40.00 - 50.00	0.6000	0.6000
T11	3	Safety Line 3/8	40.00 - 50.00	0.6000	0.6000
T11	8	Feedline Ladder (Af)	40.00 - 50.00	0.6000	0.6000
T11	9	7/8	40.00 - 50.00	0.6000	0.6000
T11	11	Feedline Ladder (Af)	40.00 - 50.00	0.6000	0.6000
T11	12	1 5/8	40.00 - 50.00	0.6000	0.6000
T11	13	1 1/4	40.00 - 50.00	0.6000	0.6000
T11	15	Feedline Ladder (Af)	40.00 - 50.00	0.6000	0.6000
T11	17	Feedline Ladder (Af)	40.00 - 50.00	0.6000	0.6000
T11	18	1 1/4	40.00 - 50.00	0.6000	0.6000
T11	19	1 1/4	40.00 - 50.00	0.6000	0.6000
T11	21	Feedline Ladder (Af)	40.00 - 50.00	0.6000	0.6000
T11	22	1 5/8	40.00 - 50.00	0.6000	0.6000
T11	23	1 5/8	40.00 - 50.00	0.6000	0.6000
T11	25	Feedline Ladder (Af)	40.00 - 50.00	0.6000	0.6000
T11	26	1 5/8	40.00 - 50.00	0.6000	0.6000
T11	27	Power Cable	40.00 - 50.00	0.6000	0.6000
T11	28	Fiber Cable	40.00 - 50.00	0.6000	0.6000
T11	30	7/8	40.00 - 50.00	0.6000	0.6000
T11	32	1/2	40.00 - 50.00	0.6000	0.6000
T12	2	Climbing Ladder (Af)	20.00 - 40.00	0.6000	0.6000
T12	3	Safety Line 3/8	20.00 - 40.00	0.6000	0.6000
T12	8	Feedline Ladder (Af)	20.00 - 40.00	0.6000	0.6000
T12	9	7/8	20.00 - 40.00	0.6000	0.6000
T12	11	Feedline Ladder (Af)	20.00 - 40.00	0.6000	0.6000
T12	12	1 5/8	20.00 - 40.00	0.6000	0.6000
T12	13	1 1/4	20.00 - 40.00	0.6000	0.6000
T12	15	Feedline Ladder (Af)	20.00 - 40.00	0.6000	0.6000
T12	17	Feedline Ladder (Af)	20.00 - 40.00	0.6000	0.6000
T12	18	1 1/4	20.00 - 40.00	0.6000	0.6000
T12	19	1 1/4	20.00 - 40.00	0.6000	0.6000
T12	21	Feedline Ladder (Af)	20.00 - 40.00	0.6000	0.6000
T12	22	1 5/8	20.00 - 40.00	0.6000	0.6000
T12	23	1 5/8	20.00 - 40.00	0.6000	0.6000
T12	25	Feedline Ladder (Af)	20.00 - 40.00	0.6000	0.6000
T12	26	1 5/8	20.00 - 40.00	0.6000	0.6000
T12	27	Power Cable	20.00 - 40.00	0.6000	0.6000
T12	28	Fiber Cable	20.00 - 40.00	0.6000	0.6000
T12	30	7/8	20.00 - 40.00	0.6000	0.6000
T12	32	1/2	20.00 - 40.00	0.6000	0.6000
T13	2	Climbing Ladder (Af)	0.00 - 20.00	0.6000	0.6000
T13	3	Safety Line 3/8	0.00 - 20.00	0.6000	0.6000
T13	8	Feedline Ladder (Af)	0.00 - 20.00	0.6000	0.6000
T13	9	7/8	0.00 - 20.00	0.6000	0.6000
T13	11	Feedline Ladder (Af)	0.00 - 20.00	0.6000	0.6000
T13	12	1 5/8	0.00 - 20.00	0.6000	0.6000
T13	13	1 1/4	0.00 - 20.00	0.6000	0.6000
T13	15	Feedline Ladder (Af)	0.00 - 20.00	0.6000	0.6000
T13	17	Feedline Ladder (Af)	0.00 - 20.00	0.6000	0.6000
T13	18	1 1/4	0.00 - 20.00	0.6000	0.6000
T13	19	1 1/4	0.00 - 20.00	0.6000	0.6000
T13	21	Feedline Ladder (Af)	0.00 - 20.00	0.6000	0.6000
T13	22	1 5/8	0.00 - 20.00	0.6000	0.6000
T13	23	1 5/8	0.00 - 20.00	0.6000	0.6000
T13	25	Feedline Ladder (Af)	0.00 - 20.00	0.6000	0.6000
T13	26	1 5/8	0.00 - 20.00	0.6000	0.6000
T13	27	Power Cable	0.00 - 20.00	0.6000	0.6000
T13	28	Fiber Cable	0.00 - 20.00	0.6000	0.6000
T13	30	7/8	0.00 - 20.00	0.6000	0.6000
T13	32	1/2	0.00 - 20.00	0.6000	0.6000



<b>tnxTower</b>  <b>Ramaker &amp; Associates, Inc.</b> 855 Community Drive Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b>	Transfer Station (CT33XC522)	<b>Page</b>	14 of 37
	<b>Project</b>	28737	<b>Date</b>	15:01:07 09/26/17
	<b>Client</b>	Transcend Wireless / Sprint	<b>Designed by</b>	TEM

## Discrete Tower Loads

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C <sub>A</sub> A <sub>A</sub> Front	C <sub>A</sub> A <sub>A</sub> Side	Weight
			Horz Lateral	Vert					
*****									
6' Dipole (Municipal)	A	From Leg	0.00	0.0000	185.00	No Ice	1.77	1.77	12.00
			0.00			1/2" Ice	2.13	2.13	25.00
			4.00			1" Ice	2.49	2.49	38.00
12' Omni (Municipal)	B	From Leg	0.00	0.0000	185.00	No Ice	3.30	3.30	35.00
			0.00			1/2" Ice	4.53	4.53	59.18
			7.50			1" Ice	5.78	5.78	91.13
6' Dipole (Municipal)	C	From Leg	0.00	0.0000	185.00	No Ice	1.77	1.77	12.00
			0.00			1/2" Ice	2.13	2.13	25.00
			4.00			1" Ice	2.49	2.49	38.00
*****									
*****									
(2) AIR 21 B2A B4P w/Mount Pipe (T-Mobile)	A	From Leg	3.00	0.0000	185.00	No Ice	6.37	5.74	104.90
			0.00			1/2" Ice	6.85	6.59	162.47
			0.00			1" Ice	7.30	7.31	226.82
(2) AIR 21 B2A B4P w/Mount Pipe (T-Mobile)	B	From Leg	3.00	0.0000	185.00	No Ice	6.37	5.74	104.90
			0.00			1/2" Ice	6.85	6.59	162.47
			0.00			1" Ice	7.30	7.31	226.82
(2) AIR 21 B2A B2P w/Mount Pipe (T-Mobile)	C	From Leg	3.00	0.0000	185.00	No Ice	6.69	5.64	119.15
			0.00			1/2" Ice	7.15	6.35	176.73
			0.00			1" Ice	7.63	7.09	241.60
KRY 112 71 (T-Mobile)	A	From Leg	2.00	0.0000	185.00	No Ice	0.58	0.40	13.20
			0.00			1/2" Ice	0.69	0.49	18.38
			0.00			1" Ice	0.80	0.59	25.16
KRY 112 71 (T-Mobile)	B	From Leg	2.00	0.0000	185.00	No Ice	0.58	0.40	13.20
			0.00			1/2" Ice	0.69	0.49	18.38
			0.00			1" Ice	0.80	0.59	25.16
KRY 112 71 (T-Mobile)	C	From Leg	2.00	0.0000	185.00	No Ice	0.58	0.40	13.20
			0.00			1/2" Ice	0.69	0.49	18.38
			0.00			1" Ice	0.80	0.59	25.16
LNx-6515DS-A1M w/Mount Pipe (T-Mobile)	A	From Leg	3.00	0.0000	185.00	No Ice	11.70	9.85	76.55
			-2.00			1/2" Ice	12.42	11.38	166.25
			0.00			1" Ice	13.14	12.92	265.92
LNx-6515DS-A1M w/Mount Pipe (T-Mobile)	B	From Leg	3.00	0.0000	185.00	No Ice	11.70	9.85	76.55
			-2.00			1/2" Ice	12.42	11.38	166.25
			0.00			1" Ice	13.14	12.92	265.92
LNx-6515DS-A1M w/Mount Pipe (T-Mobile)	C	From Leg	3.00	0.0000	185.00	No Ice	11.70	9.85	76.55
			-2.00			1/2" Ice	12.42	11.38	166.25
			0.00			1" Ice	13.14	12.92	265.92
RRUS-11 (T-Mobile)	A	From Leg	2.50	0.0000	185.00	No Ice	2.78	1.19	50.71
			-2.00			1/2" Ice	2.99	1.33	71.49
			0.00			1" Ice	3.21	1.49	95.32
RRUS-11 (T-Mobile)	B	From Leg	2.50	0.0000	185.00	No Ice	2.78	1.19	50.71
			-2.00			1/2" Ice	2.99	1.33	71.49
			0.00			1" Ice	3.21	1.49	95.32
RRUS-11 (T-Mobile)	C	From Leg	2.50	0.0000	185.00	No Ice	2.78	1.19	50.71
			-2.00			1/2" Ice	2.99	1.33	71.49

<b>tnxTower</b>  <b>Ramaker &amp; Associates, Inc.</b> 855 Community Drive Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b>	Transfer Station (CT33XC522)	<b>Page</b>	15 of 37
	<b>Project</b>	28737	<b>Date</b>	15:01:07 09/26/17
	<b>Client</b>	Transcend Wireless / Sprint	<b>Designed by</b>	TEM

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C <sub>A</sub> A <sub>A</sub> Front	C <sub>A</sub> A <sub>A</sub> Side	Weight	
			Horz Lateral	Vert						°
Sector Mount [SM 403-1] (T-Mobile)	A	From Leg	0.00	3.00	0.0000	185.00	No Ice	3.21	1.49	95.32
			0.00	0.00			1/2" Ice	10.22	7.05	291.16
			0.00	0.00			1" Ice	14.32	10.13	422.38
Sector Mount [SM 403-1] (T-Mobile)	B	From Leg	0.00	3.00	0.0000	185.00	No Ice	10.22	7.05	291.16
			0.00	0.00			1/2" Ice	14.32	10.13	422.38
			0.00	0.00			1" Ice	18.42	13.21	553.60
Sector Mount [SM 403-1] (T-Mobile)	C	From Leg	0.00	3.00	0.0000	185.00	No Ice	10.22	7.05	291.16
			0.00	0.00			1/2" Ice	14.32	10.13	422.38
			0.00	0.00			1" Ice	18.42	13.21	553.60
*****										
*****										
APXVSPP18-C w/Mount Pipe (Sprint)	A	From Leg	3.00	0.0000	174.00	No Ice	8.31	6.95	82.55	
			2.00			1/2" Ice	8.87	8.13	150.82	
			1.00			1" Ice	9.40	9.03	227.06	
APXVSPP18-C w/Mount Pipe (Sprint)	B	From Leg	3.00	0.0000	174.00	No Ice	8.31	6.95	82.55	
			2.00			1/2" Ice	8.87	8.13	150.82	
			1.00			1" Ice	9.40	9.03	227.06	
APXVSPP18-C w/Mount Pipe (Sprint)	C	From Leg	3.00	0.0000	174.00	No Ice	8.31	6.95	82.55	
			2.00			1/2" Ice	8.87	8.13	150.82	
			1.00			1" Ice	9.40	9.03	227.06	
1900MHz 4x40W RRH (Sprint)	A	From Leg	2.00	0.0000	174.00	No Ice	2.32	2.24	59.50	
			-2.00			1/2" Ice	2.53	2.44	82.62	
			1.00			1" Ice	2.74	2.65	108.98	
1900MHz 4x40W RRH (Sprint)	B	From Leg	2.00	0.0000	174.00	No Ice	2.32	2.24	59.50	
			-2.00			1/2" Ice	2.53	2.44	82.62	
			1.00			1" Ice	2.74	2.65	108.98	
1900MHz 4x40W RRH (Sprint)	C	From Leg	2.00	0.0000	174.00	No Ice	2.32	2.24	59.50	
			-2.00			1/2" Ice	2.53	2.44	82.62	
			1.00			1" Ice	2.74	2.65	108.98	
800MHz 2x50W RRH (Sprint)	A	From Leg	2.50	0.0000	174.00	No Ice	2.06	1.93	64.00	
			-2.00			1/2" Ice	2.24	2.11	86.12	
			1.00			1" Ice	2.43	2.29	111.30	
800MHz 2x50W RRH (Sprint)	B	From Leg	2.50	0.0000	174.00	No Ice	2.06	1.93	64.00	
			-2.00			1/2" Ice	2.24	2.11	86.12	
			1.00			1" Ice	2.43	2.29	111.30	
800MHz 2x50W RRH (Sprint)	C	From Leg	2.50	0.0000	174.00	No Ice	2.06	1.93	64.00	
			-2.00			1/2" Ice	2.24	2.11	86.12	
			1.00			1" Ice	2.43	2.29	111.30	
APXV9TM14-ALU-120 w/Mount Pipe (Sprint)	A	From Leg	3.00	0.0000	174.00	No Ice	6.65	5.03	77.02	
			-6.00			1/2" Ice	7.14	5.89	132.43	
			1.00			1" Ice	7.60	6.63	194.59	
APXV9TM14-ALU-120 w/Mount Pipe (Sprint)	B	From Leg	3.00	0.0000	174.00	No Ice	6.65	5.03	77.02	
			-6.00			1/2" Ice	7.14	5.89	132.43	
			1.00			1" Ice	7.60	6.63	194.59	
APXV9TM14-ALU-120 w/Mount Pipe (Sprint)	C	From Leg	3.00	0.0000	174.00	No Ice	6.65	5.03	77.02	
			-6.00			1/2" Ice	7.14	5.89	132.43	
			1.00			1" Ice	7.60	6.63	194.59	
TD-RRH8x20-25 (Sprint)	A	From Leg	2.00	0.0000	174.00	No Ice	4.05	1.53	70.00	
			-6.00			1/2" Ice	4.30	1.71	97.14	
			1.00			1" Ice	4.56	1.90	127.80	
TD-RRH8x20-25 (Sprint)	B	From Leg	2.00	0.0000	174.00	No Ice	4.05	1.53	70.00	
			-6.00			1/2" Ice	4.30	1.71	97.14	
			1.00			1" Ice	4.56	1.90	127.80	
TD-RRH8x20-25 (Sprint)	C	From Leg	2.00	0.0000	174.00	No Ice	4.05	1.53	70.00	
			-6.00			1/2" Ice	4.30	1.71	97.14	
			1.00			1" Ice	4.56	1.90	127.80	

<b>tnxTower</b>  <b>Ramaker &amp; Associates, Inc.</b> 855 Community Drive Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b>	Transfer Station (CT33XC522)	<b>Page</b>	16 of 37
	<b>Project</b>	28737	<b>Date</b>	15:01:07 09/26/17
	<b>Client</b>	Transcend Wireless / Sprint	<b>Designed by</b>	TEM

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C <sub>A</sub> A <sub>A</sub> Front	C <sub>A</sub> A <sub>A</sub> Side	Weight
			Horz Lateral ft ft ft	Vert ft					
Sector Mount [SM 403-1] (Sprint)	A	From Leg	3.00	0.0000	174.00	No Ice	10.22	7.05	291.16
			0.00			1/2" Ice	14.32	10.13	422.38
			0.00			1" Ice	18.42	13.21	553.60
Sector Mount [SM 403-1] (Sprint)	B	From Leg	3.00	0.0000	174.00	No Ice	10.22	7.05	291.16
			0.00			1/2" Ice	14.32	10.13	422.38
			0.00			1" Ice	18.42	13.21	553.60
Sector Mount [SM 403-1] (Sprint)	C	From Leg	3.00	0.0000	174.00	No Ice	10.22	7.05	291.16
			0.00			1/2" Ice	14.32	10.13	422.38
			0.00			1" Ice	18.42	13.21	553.60
*****									
*****									
BXA-70063-6CF-EDIN-X w/Mount Pipe (Verizon)	A	From Leg	4.00	0.0000	164.00	No Ice	7.83	5.82	42.55
			0.00			1/2" Ice	8.39	6.99	103.53
			0.00			1" Ice	8.91	7.87	172.25
BXA-70063-6CF-EDIN-X w/Mount Pipe (Verizon)	B	From Leg	4.00	0.0000	164.00	No Ice	7.83	5.82	42.55
			0.00			1/2" Ice	8.39	6.99	103.53
			0.00			1" Ice	8.91	7.87	172.25
BXA-70063-6CF-EDIN-X w/Mount Pipe (Verizon)	C	From Leg	4.00	0.0000	164.00	No Ice	7.83	5.82	42.55
			0.00			1/2" Ice	8.39	6.99	103.53
			0.00			1" Ice	8.91	7.87	172.25
DB846F65ZAXY w/Mount Pipe (Verizon)	A	From Leg	4.00	0.0000	164.00	No Ice	7.27	7.82	46.55
			-4.50			1/2" Ice	7.83	9.01	113.93
			0.00			1" Ice	8.35	9.91	189.25
DB846F65ZAXY w/Mount Pipe (Verizon)	A	From Leg	4.00	0.0000	164.00	No Ice	7.27	7.82	46.55
			4.50			1/2" Ice	7.83	9.01	113.93
			0.00			1" Ice	8.35	9.91	189.25
DB846H80E-SX w/Mount Pipe (Verizon)	B	From Leg	4.00	0.0000	164.00	No Ice	5.32	7.73	40.55
			-4.50			1/2" Ice	5.87	8.92	98.56
			0.00			1" Ice	6.39	9.82	164.31
DB846H80E-SX w/Mount Pipe (Verizon)	B	From Leg	4.00	0.0000	164.00	No Ice	5.32	7.73	40.55
			4.50			1/2" Ice	5.87	8.92	98.56
			0.00			1" Ice	6.39	9.82	164.31
DB846F65ZAXY w/Mount Pipe (Verizon)	C	From Leg	4.00	0.0000	164.00	No Ice	7.27	7.82	46.55
			-4.50			1/2" Ice	7.83	9.01	113.93
			0.00			1" Ice	8.35	9.91	189.25
DB846F65ZAXY w/Mount Pipe (Verizon)	C	From Leg	4.00	0.0000	164.00	No Ice	7.27	7.82	46.55
			4.50			1/2" Ice	7.83	9.01	113.93
			0.00			1" Ice	8.35	9.91	189.25
742 213 w/Mount Pipe (Verizon)	A	From Leg	4.00	0.0000	164.00	No Ice	5.31	4.65	49.85
			-6.00			1/2" Ice	5.85	5.96	93.89
			0.00			1" Ice	6.37	6.86	145.56
742 213 w/Mount Pipe (Verizon)	A	From Leg	4.00	0.0000	164.00	No Ice	5.31	4.65	49.85
			6.00			1/2" Ice	5.85	5.96	93.89
			0.00			1" Ice	6.37	6.86	145.56
742 213 w/Mount Pipe (Verizon)	B	From Leg	4.00	0.0000	164.00	No Ice	5.31	4.65	49.85
			-6.00			1/2" Ice	5.85	5.96	93.89
			0.00			1" Ice	6.37	6.86	145.56
742 213 w/Mount Pipe (Verizon)	B	From Leg	4.00	0.0000	164.00	No Ice	5.31	4.65	49.85
			6.00			1/2" Ice	5.85	5.96	93.89
			0.00			1" Ice	6.37	6.86	145.56
742 213 w/Mount Pipe (Verizon)	C	From Leg	4.00	0.0000	164.00	No Ice	5.31	4.65	49.85
			-6.00			1/2" Ice	5.85	5.96	93.89
			0.00			1" Ice	6.37	6.86	145.56
742 213 w/Mount Pipe (Verizon)	C	From Leg	4.00	0.0000	164.00	No Ice	5.31	4.65	49.85
			6.00			1/2" Ice	5.85	5.96	93.89
			0.00			1" Ice	6.37	6.86	145.56
RRH 2x40 AWS	A	From Leg	3.00	0.0000	164.00	No Ice	2.16	1.42	44.00

<b>Job</b>	Transfer Station (CT33XC522)	<b>Page</b>	17 of 37
<b>Project</b>	28737	<b>Date</b>	15:01:07 09/26/17
<b>Client</b>	Transcend Wireless / Sprint	<b>Designed by</b>	TEM

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment °	Placement ft	C <sub>A</sub> A <sub>A</sub> Front ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> Side ft <sup>2</sup>	Weight lb	
(Verizon)			-6.00			1/2" Ice	2.36	1.59	61.40
			0.00			1" Ice	2.57	1.77	81.69
RRH 2x40 AWS (Verizon)	B	From Leg	3.00	0.0000	164.00	No Ice	2.16	1.42	44.00
			-6.00			1/2" Ice	2.36	1.59	61.40
			0.00			1" Ice	2.57	1.77	81.69
RRH 2x40 AWS (Verizon)	C	From Leg	3.00	0.0000	164.00	No Ice	2.16	1.42	44.00
			-6.00			1/2" Ice	2.36	1.59	61.40
			0.00			1" Ice	2.57	1.77	81.69
DB-T1-6Z-8AB-0Z (Verizon)	C	From Leg	1.50	0.0000	164.00	No Ice	5.60	2.33	44.00
			0.00			1/2" Ice	5.92	2.56	80.13
			0.00			1" Ice	6.24	2.79	120.22
Sector Mount [SM 104-1] (Verizon)	A	From Leg	3.00	0.0000	164.00	No Ice	16.40	10.28	317.50
			0.00			1/2" Ice	21.70	14.27	468.20
			0.00			1" Ice	27.00	18.26	618.90
Sector Mount [SM 104-1] (Verizon)	B	From Leg	3.00	0.0000	164.00	No Ice	16.40	10.28	317.50
			0.00			1/2" Ice	21.70	14.27	468.20
			0.00			1" Ice	27.00	18.26	618.90
Sector Mount [SM 104-1] (Verizon)	C	From Leg	3.00	0.0000	164.00	No Ice	16.40	10.28	317.50
			0.00			1/2" Ice	21.70	14.27	468.20
			0.00			1" Ice	27.00	18.26	618.90
*****									
*****									
7770.00 w/Mount Pipe (ATT)	A	From Leg	3.00	0.0000	154.00	No Ice	5.66	4.11	30.35
			-6.00			1/2" Ice	6.04	4.76	76.38
			0.00			1" Ice	6.44	5.43	128.70
7770.00 w/Mount Pipe (ATT)	B	From Leg	3.00	0.0000	154.00	No Ice	5.66	4.11	30.35
			-6.00			1/2" Ice	6.04	4.76	76.38
			0.00			1" Ice	6.44	5.43	128.70
7770.00 w/Mount Pipe (ATT)	C	From Leg	3.00	0.0000	154.00	No Ice	5.66	4.11	30.35
			-6.00			1/2" Ice	6.04	4.76	76.38
			0.00			1" Ice	6.44	5.43	128.70
7770.00 w/Mount Pipe (ATT)	A	From Leg	3.00	0.0000	154.00	No Ice	5.66	4.11	30.35
			-2.00			1/2" Ice	6.04	4.76	76.38
			0.00			1" Ice	6.44	5.43	128.70
7770.00 w/Mount Pipe (ATT)	B	From Leg	3.00	0.0000	154.00	No Ice	5.66	4.11	30.35
			-2.00			1/2" Ice	6.04	4.76	76.38
			0.00			1" Ice	6.44	5.43	128.70
7770.00 w/Mount Pipe (ATT)	C	From Leg	3.00	0.0000	154.00	No Ice	5.66	4.11	30.35
			-2.00			1/2" Ice	6.04	4.76	76.38
			0.00			1" Ice	6.44	5.43	128.70
P65-16-XLH-RR w/Mount Pipe (ATT)	A	From Leg	3.00	0.0000	154.00	No Ice	8.13	6.13	85.90
			6.00			1/2" Ice	8.59	7.07	149.07
			0.00			1" Ice	9.05	7.90	219.94
P65-16-XLH-RR w/Mount Pipe (ATT)	B	From Leg	3.00	0.0000	154.00	No Ice	8.13	6.13	85.90
			6.00			1/2" Ice	8.59	7.07	149.07
			0.00			1" Ice	9.05	7.90	219.94
P65-16-XLH-RR w/Mount Pipe (ATT)	C	From Leg	3.00	0.0000	154.00	No Ice	8.13	6.13	85.90
			6.00			1/2" Ice	8.59	7.07	149.07
			0.00			1" Ice	9.05	7.90	219.94
(2) LGP214nn (ATT)	A	From Leg	3.00	0.0000	154.00	No Ice	1.11	0.21	14.10
			-6.00			1/2" Ice	1.25	0.28	21.30
			0.00			1" Ice	1.39	0.35	30.39
(2) LGP214nn (ATT)	B	From Leg	3.00	0.0000	154.00	No Ice	1.11	0.21	14.10
			-6.00			1/2" Ice	1.25	0.28	21.30
			0.00			1" Ice	1.39	0.35	30.39
(2) LGP214nn (ATT)	C	From Leg	3.00	0.0000	154.00	No Ice	1.11	0.21	14.10
			-6.00			1/2" Ice	1.25	0.28	21.30

<b>Job</b>	Transfer Station (CT33XC522)	<b>Page</b>	18 of 37
<b>Project</b>	28737	<b>Date</b>	15:01:07 09/26/17
<b>Client</b>	Transcend Wireless / Sprint	<b>Designed by</b>	TEM

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C <sub>A</sub> A <sub>A</sub> Front	C <sub>A</sub> A <sub>A</sub> Side	Weight	
			Horz	Lateral						
			ft	ft	°	ft	ft <sup>2</sup>	ft <sup>2</sup>	lb	
TT19-08BP111-001 (ATT)	A	From Leg	0.00		0.0000	154.00	1" Ice	1.39	0.35	30.39
			3.00				No Ice	0.55	0.45	16.00
			-2.00				1/2" Ice	0.65	0.53	21.80
TT19-08BP111-001 (ATT)	B	From Leg	0.00		0.0000	154.00	1" Ice	0.75	0.63	29.22
			3.00				No Ice	0.55	0.45	16.00
			-2.00				1/2" Ice	0.65	0.53	21.80
TT19-08BP111-001 (ATT)	C	From Leg	0.00		0.0000	154.00	1" Ice	0.75	0.63	29.22
			3.00				No Ice	0.55	0.45	16.00
			-2.00				1/2" Ice	0.65	0.53	21.80
RRUS-11 (ATT)	A	From Leg	0.00		0.0000	154.00	1" Ice	0.75	0.63	29.22
			1.00				No Ice	2.78	1.19	50.71
			0.00				1/2" Ice	2.99	1.33	71.49
RRUS-11 (ATT)	B	From Leg	3.00		0.0000	154.00	1" Ice	3.21	1.49	95.32
			1.00				No Ice	2.78	1.19	50.71
			0.00				1/2" Ice	2.99	1.33	71.49
RRUS-11 (ATT)	C	From Leg	3.00		0.0000	154.00	1" Ice	3.21	1.49	95.32
			1.00				No Ice	2.78	1.19	50.71
			0.00				1/2" Ice	2.99	1.33	71.49
DC6-48-60-18-8F (ATT)	C	From Leg	3.00		0.0000	154.00	1" Ice	3.21	1.49	95.32
			1.00				No Ice	0.92	0.92	32.80
			0.00				1/2" Ice	1.46	1.46	50.52
Sector Mount [SM 104-1] (ATT)	A	From Leg	0.00		0.0000	154.00	1" Ice	1.64	1.64	70.72
			3.00				No Ice	16.40	10.28	317.50
			0.00				1/2" Ice	21.70	14.27	468.20
Sector Mount [SM 104-1] (ATT)	B	From Leg	0.00		0.0000	154.00	1" Ice	27.00	18.26	618.90
			3.00				No Ice	16.40	10.28	317.50
			0.00				1/2" Ice	21.70	14.27	468.20
Sector Mount [SM 104-1] (ATT)	C	From Leg	0.00		0.0000	154.00	1" Ice	27.00	18.26	618.90
			3.00				No Ice	16.40	10.28	317.50
			0.00				1/2" Ice	21.70	14.27	468.20
*****										
15' Omni (Municipal)	A	From Leg	6.00		0.0000	146.00	No Ice	4.13	4.13	40.00
			0.00				1/2" Ice	5.66	5.66	70.14
			8.00				1" Ice	7.20	7.20	109.87
8' Dipole (Municipal)	A	From Leg	6.00		0.0000	146.00	No Ice	2.80	2.80	45.00
			0.00				1/2" Ice	3.41	3.41	65.06
			-5.00				1" Ice	3.89	3.89	90.52
8' Dipole (Municipal)	C	From Leg	6.00		0.0000	146.00	No Ice	2.80	2.80	45.00
			0.00				1/2" Ice	3.41	3.41	65.06
			-5.00				1" Ice	3.89	3.89	90.52
Side Arm Mount [SO 308-1] (Municipal)	A	From Leg	3.00		0.0000	146.00	No Ice	0.98	3.03	53.00
			0.00				1/2" Ice	1.70	5.22	78.75
			0.00				1" Ice	2.42	7.41	104.50
Side Arm Mount [SO 308-1] (Municipal)	C	From Leg	3.00		0.0000	146.00	No Ice	0.98	3.03	53.00
			0.00				1/2" Ice	1.70	5.22	78.75
			0.00				1" Ice	2.42	7.41	104.50
*****										
2' Standoff (Dish)	B	From Leg	1.00		0.0000	138.00	No Ice	1.80	1.80	33.00
			0.00				1/2" Ice	3.30	3.30	59.00
			0.00				1" Ice	4.80	4.80	85.00
*****										

<b>tnxTower</b>  <b>Ramaker &amp; Associates, Inc.</b> 855 Community Drive Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b> Transfer Station (CT33XC522)	<b>Page</b> 19 of 37
	<b>Project</b> 28737	<b>Date</b> 15:01:07 09/26/17
	<b>Client</b> Transcend Wireless / Sprint	<b>Designed by</b> TEM

### Dishes

Description	Face or Leg	Dish Type	Offset Type	Offsets: Horz Lateral Vert	Azimuth Adjustment °	3 dB Beam Width °	Elevation ft	Outside Diameter ft	Aperture Area ft <sup>2</sup>	Weight lb
*****										
Andrew 3' w/Radome (Sprint)	B	Paraboloid w/Radome	From Leg	2.00 0.00 0.00	0.0000		138.00	3.00	No Ice 1/2" Ice 1" Ice	100.00 138.35 176.70
*****										

### Force Totals

Load Case	Vertical Forces lb	Sum of Forces X lb	Sum of Forces Z lb	Sum of Overturning Moments, M <sub>x</sub> lb-ft	Sum of Overturning Moments, M <sub>z</sub> lb-ft	Sum of Torques lb-ft
Leg Weight	10198.44					
Bracing Weight	20235.60					
Total Member Self-Weight	30434.04					
Total Weight	57498.63					
Wind 0 deg - No Ice		25.23	-31111.28	-3250552.60	14772.07	-5219.85
Wind 30 deg - No Ice		14853.63	-25697.40	-2735962.83	-1557639.79	-6129.76
Wind 60 deg - No Ice		26974.54	-15587.21	-1657611.29	-2829964.47	-6002.59
Wind 90 deg - No Ice		33650.75	-36.14	-16360.82	-3475382.33	-4241.52
Wind 120 deg - No Ice		30507.54	17577.51	1784848.15	-3099506.61	-837.98
Wind 150 deg - No Ice		15719.35	27236.60	2825480.73	-1616037.26	2616.40
Wind 180 deg - No Ice		-42.84	29194.43	3080817.56	26984.04	4870.62
Wind 210 deg - No Ice		-14881.82	25681.12	2713787.26	1600855.66	6129.76
Wind 240 deg - No Ice		-28643.39	16530.38	1710479.65	3000240.71	6380.59
Wind 270 deg - No Ice		-33684.83	35.81	-3614.29	3519410.97	4197.10
Wind 300 deg - No Ice		-28893.22	-16645.48	-1733517.30	3015405.62	809.21
Wind 330 deg - No Ice		-15736.68	-27265.95	-2849460.40	1657753.86	-2571.98
Member Ice	45792.11					
Total Weight Ice	176483.82					
Wind 0 deg - Ice		-3.53	-15206.29	-1670208.51	70112.69	-2150.14
Wind 30 deg - Ice		7498.36	-12978.37	-1443473.66	-737848.65	-2596.92
Wind 60 deg - Ice		13409.57	-7733.18	-875532.09	-1368561.62	-2449.77
Wind 90 deg - Ice		16076.32	-0.24	-46540.74	-1638646.56	-1600.34
Wind 120 deg - Ice		14102.22	8130.12	810532.78	-1417266.65	-239.56
Wind 150 deg - Ice		7682.13	13285.89	1371197.92	-749851.40	1113.55
Wind 180 deg - Ice		-2.56	14750.28	1543105.75	70696.71	2089.87
Wind 210 deg - Ice		-7508.11	12972.74	1350400.36	879162.63	2596.92
Wind 240 deg - Ice		-13807.53	7955.91	799910.49	1539093.69	2506.51
Wind 270 deg - Ice		-16088.10	0.13	-45771.95	1780241.48	1584.99
Wind 300 deg - Ice		-13732.06	-7916.41	-887461.72	1530617.76	242.95
Wind 330 deg - Ice		-7688.12	-13296.04	-1464894.83	890647.15	-1098.19
Total Weight	57498.63					
Wind 0 deg - Service		10.50	-12949.54	-1348988.61	-1584.40	-2172.67
Wind 30 deg - Service		6182.57	-10696.11	-1134799.31	-656074.25	-2551.41
Wind 60 deg - Service		11227.70	-6487.91	-685953.72	-1185657.88	-2498.48
Wind 90 deg - Service		14006.56	-15.04	-2810.97	-1454302.15	-1765.46
Wind 120 deg - Service		12698.25	7316.34	746911.81	-1297850.24	-348.79
Wind 150 deg - Service		6542.92	11336.77	1180057.52	-680381.21	1089.03
Wind 180 deg - Service		-17.83	12151.69	1286337.17	3498.63	2027.31

<b>tnxTower</b>  <b>Ramaker &amp; Associates, Inc.</b> 855 Community Drive Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b> Transfer Station (CT33XC522)	<b>Page</b> 20 of 37
	<b>Project</b> 28737	<b>Date</b> 15:01:07 09/26/17
	<b>Client</b> Transcend Wireless / Sprint	<b>Designed by</b> TEM

Load Case	Vertical Forces lb	Sum of Forces X lb	Sum of Forces Z lb	Sum of Overturning Moments, M <sub>x</sub> lb-ft	Sum of Overturning Moments, M <sub>z</sub> lb-ft	Sum of Torques lb-ft
Wind 210 deg - Service		-6194.31	10689.33	1133567.01	658596.07	2551.41
Wind 240 deg - Service		-11922.32	6880.49	715957.18	1241066.44	2655.81
Wind 270 deg - Service		-14020.74	14.91	2494.56	1457162.28	1746.97
Wind 300 deg - Service		-12026.31	-6928.40	-717548.31	1247378.58	336.82
Wind 330 deg - Service		-6550.13	-11348.99	-1182040.76	682278.99	-1070.54

## Load Combinations

Comb. No.	Description
1	Dead Only
2	1.2 Dead+1.6 Wind 0 deg - No Ice
3	0.9 Dead+1.6 Wind 0 deg - No Ice
4	1.2 Dead+1.6 Wind 30 deg - No Ice
5	0.9 Dead+1.6 Wind 30 deg - No Ice
6	1.2 Dead+1.6 Wind 60 deg - No Ice
7	0.9 Dead+1.6 Wind 60 deg - No Ice
8	1.2 Dead+1.6 Wind 90 deg - No Ice
9	0.9 Dead+1.6 Wind 90 deg - No Ice
10	1.2 Dead+1.6 Wind 120 deg - No Ice
11	0.9 Dead+1.6 Wind 120 deg - No Ice
12	1.2 Dead+1.6 Wind 150 deg - No Ice
13	0.9 Dead+1.6 Wind 150 deg - No Ice
14	1.2 Dead+1.6 Wind 180 deg - No Ice
15	0.9 Dead+1.6 Wind 180 deg - No Ice
16	1.2 Dead+1.6 Wind 210 deg - No Ice
17	0.9 Dead+1.6 Wind 210 deg - No Ice
18	1.2 Dead+1.6 Wind 240 deg - No Ice
19	0.9 Dead+1.6 Wind 240 deg - No Ice
20	1.2 Dead+1.6 Wind 270 deg - No Ice
21	0.9 Dead+1.6 Wind 270 deg - No Ice
22	1.2 Dead+1.6 Wind 300 deg - No Ice
23	0.9 Dead+1.6 Wind 300 deg - No Ice
24	1.2 Dead+1.6 Wind 330 deg - No Ice
25	0.9 Dead+1.6 Wind 330 deg - No Ice
26	1.2 Dead+1.0 Ice+1.0 Temp
27	1.2 Dead+1.0 Wind 0 deg+1.0 Ice+1.0 Temp
28	1.2 Dead+1.0 Wind 30 deg+1.0 Ice+1.0 Temp
29	1.2 Dead+1.0 Wind 60 deg+1.0 Ice+1.0 Temp
30	1.2 Dead+1.0 Wind 90 deg+1.0 Ice+1.0 Temp
31	1.2 Dead+1.0 Wind 120 deg+1.0 Ice+1.0 Temp
32	1.2 Dead+1.0 Wind 150 deg+1.0 Ice+1.0 Temp
33	1.2 Dead+1.0 Wind 180 deg+1.0 Ice+1.0 Temp
34	1.2 Dead+1.0 Wind 210 deg+1.0 Ice+1.0 Temp
35	1.2 Dead+1.0 Wind 240 deg+1.0 Ice+1.0 Temp
36	1.2 Dead+1.0 Wind 270 deg+1.0 Ice+1.0 Temp
37	1.2 Dead+1.0 Wind 300 deg+1.0 Ice+1.0 Temp
38	1.2 Dead+1.0 Wind 330 deg+1.0 Ice+1.0 Temp
39	Dead+Wind 0 deg - Service
40	Dead+Wind 30 deg - Service
41	Dead+Wind 60 deg - Service
42	Dead+Wind 90 deg - Service
43	Dead+Wind 120 deg - Service
44	Dead+Wind 150 deg - Service
45	Dead+Wind 180 deg - Service
46	Dead+Wind 210 deg - Service

<b>tnxTower</b>  <b>Ramaker &amp; Associates, Inc.</b> 855 Community Drive Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b> Transfer Station (CT33XC522)	<b>Page</b> 21 of 37
	<b>Project</b> 28737	<b>Date</b> 15:01:07 09/26/17
	<b>Client</b> Transcend Wireless / Sprint	<b>Designed by</b> TEM

Comb. No.	Description
47	Dead+Wind 240 deg - Service
48	Dead+Wind 270 deg - Service
49	Dead+Wind 300 deg - Service
50	Dead+Wind 330 deg - Service

### Maximum Member Forces

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Axial lb	Major Axis Moment lb-ft	Minor Axis Moment lb-ft
T1	185 - 180	Leg	Max Tension	6	1688.83	0.00	-0.00
			Max. Compression	31	-2848.82	-4.74	-5.08
			Max. Mx	10	213.50	29.32	7.43
			Max. My	2	219.11	-10.66	-32.87
			Max. Vy	20	927.45	-0.00	-0.00
			Max. Vx	14	-937.03	0.00	0.00
		Diagonal	Max Tension	25	1342.17	0.00	0.00
			Max. Compression	12	-1559.68	0.00	0.00
			Max. Mx	30	100.53	15.20	-0.17
			Max. My	14	-1262.94	2.27	0.99
			Max. Vy	30	-19.41	15.20	-0.17
			Max. Vx	27	0.32	0.00	0.00
		Top Girt	Max Tension	18	499.07	0.00	0.00
			Max. Compression	7	-358.31	0.00	0.00
			Max. Mx	37	98.41	-37.49	0.00
			Max. My	18	-126.94	0.00	-0.00
			Max. Vy	37	29.99	0.00	0.00
			Max. Vx	18	0.00	0.00	0.00
T2	180 - 160	Leg	Max Tension	7	27179.27	-340.41	199.23
			Max. Compression	2	-32295.55	-14.69	343.97
			Max. Mx	20	-26997.01	-556.51	27.07
			Max. My	2	-31563.98	-13.18	-557.56
			Max. Vy	8	-947.18	-404.72	-7.90
			Max. Vx	2	973.26	1.30	428.80
		Diagonal	Max Tension	8	4967.68	0.00	0.00
			Max. Compression	18	-5144.57	0.00	0.00
			Max. Mx	27	1059.03	30.06	0.18
			Max. My	4	-5097.63	-14.31	-3.97
			Max. Vy	27	-23.49	30.06	0.18
			Max. Vx	4	-1.13	0.00	0.00
		Top Girt	Max Tension	6	406.67	0.00	0.00
			Max. Compression	19	-290.03	0.00	0.00
			Max. Mx	37	283.31	-37.19	0.00
			Max. My	18	226.20	0.00	-0.00
			Max. Vy	37	29.75	0.00	0.00
			Max. Vx	18	0.00	0.00	0.00
T3	160 - 140	Leg	Max Tension	7	68498.83	-123.58	60.67
			Max. Compression	18	-78888.14	50.55	15.96
			Max. Mx	6	46746.39	405.62	33.90
			Max. My	12	-3652.32	-30.01	354.81
			Max. Vy	6	-675.34	-265.93	-3.94
			Max. Vx	24	678.05	-29.58	319.51
		Diagonal	Max Tension	16	5175.93	0.00	0.00
			Max. Compression	16	-5272.29	0.00	0.00
			Max. Mx	27	1319.93	30.10	2.86
			Max. My	35	6.09	20.53	-4.31
			Max. Vy	27	-26.58	30.10	2.86
			Max. Vx	35	1.80	0.00	0.00
		Top Girt	Max Tension	7	401.92	0.00	0.00



<b>tnxTower</b>  <b>Ramaker &amp; Associates, Inc.</b> 855 Community Drive Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b>	Transfer Station (CT33XC522)	<b>Page</b>	22 of 37
	<b>Project</b>	28737	<b>Date</b>	15:01:07 09/26/17
	<b>Client</b>	Transcend Wireless / Sprint	<b>Designed by</b>	TEM

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Axial lb	Major Axis Moment lb-ft	Minor Axis Moment lb-ft	
T4	140 - 120	Leg	Max. Compression	18	-427.02	0.00	0.00	
			Max. Mx	26	-24.54	-36.64	0.00	
			Max. My	29	-89.60	0.00	1.06	
			Max. Vy	26	-29.31	0.00	0.00	
			Max. Vx	29	-0.85	0.00	0.00	
			Max Tension	7	105414.32	546.01	5.87	
			Max. Compression	18	-119664.33	1518.91	1.35	
			Max. Mx	18	-119613.67	-2017.78	1.39	
			Max. My	20	-6365.15	-155.12	-868.84	
			Max. Vy	18	1388.68	1518.94	1.40	
		Diagonal	Max. Vx	20	409.41	-155.12	-868.84	
			Max Tension	5	5835.35	19.26	1.34	
			Max. Compression	16	-6053.98	0.00	0.00	
			Max. Mx	27	1152.97	41.93	3.58	
			Max. My	18	-5372.21	-10.82	-5.14	
			Max. Vy	37	35.52	38.23	-2.92	
			Max. Vx	29	1.82	0.00	0.00	
			Max Tension	18	2075.23	0.00	0.00	
			Max. Compression	18	-2075.23	4.34	-1.37	
			Max. Mx	29	-50.03	32.51	7.36	
T5	120 - 100	Leg	Max. My	36	-117.36	32.24	8.10	
			Max. Vy	29	-36.69	32.51	7.36	
			Max. Vx	27	-2.80	0.00	0.00	
			Max Tension	23	136914.83	1412.04	0.66	
			Max. Compression	18	-156555.59	2941.82	61.98	
			Max. Mx	18	-154281.28	5821.80	-59.00	
			Max. My	20	-6820.16	-411.93	-1465.46	
			Max. Vy	18	-6508.54	5821.80	-59.00	
			Max. Vx	20	1252.85	-411.93	-1465.46	
			Max Tension	7	8468.07	35.65	-2.15	
		Diagonal	Max. Compression	18	-9430.09	0.00	0.00	
			Max. Mx	18	2192.43	100.94	1.82	
			Max. My	36	-960.13	5.91	-6.20	
			Max. Vy	18	-40.23	100.94	1.82	
			Max. Vx	36	-2.68	0.00	0.00	
			Max Tension	18	2715.01	0.00	0.00	
			Max. Compression	18	-2715.01	20.79	14.41	
			Max. Mx	27	-75.92	60.54	36.30	
			Max. My	27	86.34	60.39	36.55	
			Max. Vy	27	-58.98	60.54	36.30	
Horizontal	Max. Vx	27	-8.38	0.00	0.00			
	Max Tension	18	6294.35	0.00	0.00			
	Max. Compression	7	-5643.10	0.00	0.00			
	Max. Mx	26	839.04	-20.88	0.00			
	Max. My	29	2004.31	0.00	0.60			
	Max. Vy	26	31.32	0.00	0.00			
	Max. Vx	29	-0.90	0.00	0.00			
	Max Tension	7	3458.35	0.00	0.00			
	Max. Compression	18	-3974.55	0.00	0.00			
	Max. Mx	38	279.19	-26.03	0.00			
Redund Horz 1 Bracing	Max. My	35	17.70	0.00	0.92			
	Max. Vy	38	32.38	0.00	0.00			
	Max. Vx	35	-1.14	0.00	0.00			
	Max Tension	23	149511.17	511.23	-2.94			
	Max. Compression	18	-171097.72	770.89	4.84			
	Max. Mx	18	-170871.59	-870.94	-17.88			
	Max. My	20	-9299.09	-180.79	-1247.23			
	Max. Vy	18	-294.01	770.89	4.84			
	Max. Vx	20	-190.19	-180.79	-1247.23			
	Max Tension	16	6757.32	0.00	0.00			
Redund Diag 1 Bracing	Max. Compression	4	-6795.90	0.00	0.00			
	T6	100 - 93.3333	Leg	Max. Compression	18	-427.02	0.00	0.00
				Max. Mx	26	-24.54	-36.64	0.00
				Max. My	29	-89.60	0.00	1.06
				Max. Vy	26	-29.31	0.00	0.00
				Max. Vx	29	-0.85	0.00	0.00
			Diagonal	Max Tension	7	105414.32	546.01	5.87
				Max. Compression	18	-119664.33	1518.91	1.35
				Max. Mx	18	-119613.67	-2017.78	1.39
				Max. My	20	-6365.15	-155.12	-868.84
Max. Vy				18	1388.68	1518.94	1.40	

<b>tnxTower</b>  <b>Ramaker &amp; Associates, Inc.</b> 855 Community Drive Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b>	Transfer Station (CT33XC522)	<b>Page</b>	23 of 37
	<b>Project</b>	28737	<b>Date</b>	15:01:07 09/26/17
	<b>Client</b>	Transcend Wireless / Sprint	<b>Designed by</b>	TEM

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Axial lb	Major Axis Moment lb-ft	Minor Axis Moment lb-ft
T7	93.3333 - 86.6667	Leg	Max. Mx	27	1940.90	77.82	-7.86
			Max. My	35	133.49	64.07	-10.52
			Max. Vy	37	52.93	75.42	9.40
			Max. Vx	35	3.00	0.00	0.00
			Max Tension	23	160479.51	-645.83	3.24
			Max. Compression	18	-183428.74	1457.68	-36.44
			Max. Mx	19	-180157.44	1458.59	-36.57
		Diagonal	Max. My	20	-10023.04	-12.69	-972.49
			Max. Vy	6	167.80	-1396.94	35.88
			Max. Vx	8	-148.59	-7.48	968.79
			Max Tension	16	6721.37	0.00	0.00
			Max. Compression	4	-6949.55	0.00	0.00
			Max. Mx	27	1724.06	80.89	9.11
			Max. My	35	105.70	67.59	-11.32
T8	86.6667 - 80	Leg	Max. Vy	37	55.13	79.51	-10.37
			Max. Vx	35	-3.10	0.00	0.00
			Max Tension	23	171293.01	-1385.38	-5.80
			Max. Compression	18	-195841.04	-1793.00	37.48
			Max. Mx	18	-195841.04	-1793.00	37.48
			Max. My	20	-10442.47	-12.70	-972.49
			Max. Vy	10	536.05	1455.91	6.87
		Diagonal	Max. Vx	8	136.35	-7.50	968.79
			Max Tension	4	7296.79	0.00	0.00
			Max. Compression	4	-7580.82	0.00	0.00
			Max. Mx	27	1958.88	-143.14	13.84
			Max. My	35	101.92	-117.71	18.58
			Max. Vy	37	-88.65	-137.84	-16.33
			Max. Vx	35	-4.87	0.00	0.00
T9	80 - 60	Leg	Max Tension	23	201488.23	916.61	0.21
			Max. Compression	18	-233199.76	1986.40	75.70
			Max. Mx	18	-231399.83	5851.04	-77.14
			Max. My	20	-13723.23	-343.45	-2069.56
			Max. Vy	18	-6069.67	5851.04	-77.14
			Max. Vx	8	-1726.41	-355.02	2059.94
			Diagonal	Max Tension	7	8672.76	25.73
		Max. Compression		18	-9881.02	0.00	0.00
		Max. Mx		18	3872.47	123.82	2.68
		Max. My		29	-1884.45	18.15	-10.09
		Max. Vy		35	-47.75	75.16	7.94
		Max. Vx		28	-3.46	0.00	0.00
		Horizontal		Max Tension	18	4044.18	0.00
			Max. Compression	18	-4044.18	49.58	25.58
			Max. Mx	31	-149.58	129.25	61.87
			Max. My	27	151.67	121.02	65.40
			Max. Vy	27	-90.53	121.17	65.11
			Max. Vx	27	-11.19	0.00	0.00
			Redund Horz 1 Bracing	Max Tension	18	5840.87	0.00
		Max. Compression		7	-5235.94	0.00	0.00
		Max. Mx		37	1514.80	-38.31	0.00
		Max. My		36	2374.35	0.00	1.11
		Max. Vy		37	41.79	0.00	0.00
		Max. Vx		36	-1.21	0.00	0.00
Redund Diag 1 Bracing	Max Tension	7		2934.14	0.00	0.00	
	Max. Compression	18	-3445.90	0.00	0.00		
	Max. Mx	38	254.27	-43.90	0.00		
	Max. My	35	34.77	0.00	1.42		
	Max. Vy	38	42.79	0.00	0.00		
	Max. Vx	35	-1.38	0.00	0.00		
	T10	60 - 50	Leg	Max Tension	23	214462.03	1157.80
Max. Compression				18	-248555.61	-1949.65	-26.21
Max. Mx				18	-248341.05	3169.89	11.50

<b>tnxTower</b>  <b>Ramaker &amp; Associates, Inc.</b> 855 Community Drive Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b> Transfer Station (CT33XC522)	<b>Page</b> 24 of 37
	<b>Project</b> 28737	<b>Date</b> 15:01:07 09/26/17
	<b>Client</b> Transcend Wireless / Sprint	<b>Designed by</b> TEM

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Axial lb	Major Axis Moment lb-ft	Minor Axis Moment lb-ft
T11	50 - 40	Diagonal	Max. My	20	-14837.49	-274.50	-2482.63
			Max. Vy	18	-1072.61	3169.79	11.32
			Max. Vx	20	640.25	-274.50	-2482.63
			Max Tension	5	8924.50	77.08	4.31
			Max. Compression	16	-9491.07	0.00	0.00
			Max. Mx	37	1553.87	173.02	-9.81
			Max. My	18	-9398.23	3.20	-21.03
			Max. Vy	37	86.64	173.02	-9.81
			Max. Vx	28	4.16	0.00	0.00
			Max Tension	18	4310.48	0.00	0.00
			Max. Compression	18	-4310.48	56.41	2.81
			Max. Mx	34	-90.66	168.90	38.98
		Max. My	36	-104.01	168.71	39.65	
		Max. Vy	34	-103.65	168.90	38.98	
		Max. Vx	38	-7.59	0.00	0.00	
		Secondary Horizontal	Max Tension	23	229950.03	1400.37	-0.37
			Max. Compression	18	-267241.85	-3215.47	26.12
			Max. Mx	18	-267027.70	3645.69	-3.12
			Max. My	20	-15706.95	-274.52	-2482.62
			Max. Vy	18	1360.82	3645.69	-3.12
			Max. Vx	20	-698.85	-274.52	-2482.62
			Max Tension	5	9292.66	-167.66	7.57
			Max. Compression	4	-10003.93	0.00	0.00
			Max. Mx	27	2471.97	-290.96	44.60
Max. My	36		2724.64	-284.23	46.13		
Max. Vy	37		-141.78	-280.30	-38.55		
Max. Vx	36		-8.53	0.00	0.00		
Leg	Max Tension	18	4634.54	0.00	0.00		
	Max. Compression	18	-4634.54	82.62	-18.49		
	Max. Mx	36	858.61	169.09	10.47		
	Max. My	20	-1594.62	78.35	30.51		
	Max. Vy	36	106.48	169.09	10.47		
	Max. Vx	38	-5.20	0.00	0.00		
	Max Tension	23	258493.15	3249.99	5.84		
	Max. Compression	18	-301887.24	7949.47	7.36		
	Max. Mx	18	-301659.41	7949.54	7.48		
	Max. My	20	-17564.77	-601.86	-3660.21		
	Max. Vy	18	3091.97	7949.54	7.48		
	Max. Vx	20	822.47	-601.86	-3660.21		
Diagonal	Max Tension	5	10417.51	115.71	-4.71		
	Max. Compression	18	-11453.08	0.00	0.00		
	Max. Mx	27	1566.71	245.45	-24.16		
	Max. My	28	855.30	226.87	26.56		
	Max. Vy	37	109.04	224.31	22.39		
	Max. Vx	36	-5.33	0.00	0.00		
	Max Tension	18	5235.37	0.00	0.00		
	Max. Compression	18	-5235.37	114.46	4.46		
	Max. Mx	34	40.42	227.29	36.34		
	Max. My	36	-370.50	225.01	39.51		
	Max. Vy	35	122.41	207.99	33.60		
	Max. Vx	38	-7.32	0.00	0.00		
Secondary Horizontal	Max Tension	23	285152.43	1459.40	2.66		
	Max. Compression	18	-337052.77	5406.85	147.43		
	Max. Mx	18	-317327.67	12450.87	-106.56		
	Max. My	20	-20400.49	-1326.08	-5036.04		
	Max. Vy	18	-9528.69	12090.26	-114.53		
	Max. Vx	20	2389.57	-1326.08	-5036.04		
	Max Tension	7	11518.53	71.32	-5.09		
	Max. Compression	18	-13341.06	0.00	0.00		
	Max. Mx	18	4161.74	188.54	8.20		
	Max. My	34	-5713.15	29.27	-18.70		
	Max. Vy	34	-5713.15	29.27	-18.70		

<b>tnxTower</b>  <b>Ramaker &amp; Associates, Inc.</b> 855 Community Drive Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b>	Transfer Station (CT33XC522)	<b>Page</b>	25 of 37
	<b>Project</b>	28737	<b>Date</b>	15:01:07 09/26/17
	<b>Client</b>	Transcend Wireless / Sprint	<b>Designed by</b>	TEM

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Axial lb	Major Axis Moment lb-ft	Minor Axis Moment lb-ft
		Horizontal	Max. Vy	35	-68.26	142.46	15.42
			Max. Vx	34	-4.74	0.00	0.00
		Redund Horz 1 Bracing	Max Tension	18	5845.21	0.00	0.00
			Max. Compression	18	-5845.21	191.02	70.22
			Max. Mx	27	-592.68	342.76	133.97
			Max. My	27	307.05	342.70	134.11
			Max. Vy	27	-149.60	342.76	133.97
		Redund Diag 1 Bracing	Max. Vx	27	-17.09	0.00	0.00
			Max Tension	18	8655.74	0.00	0.00
			Max. Compression	7	-7354.63	0.00	0.00
			Max. Mx	32	2527.17	-66.60	0.00
			Max. My	27	2893.17	0.00	1.92
			Max. Vy	32	51.98	0.00	0.00
			Max. Vx	27	-1.50	0.00	0.00
			Max Tension	7	4142.50	0.00	0.00
			Max. Compression	18	-5133.24	0.00	0.00
			Max. Mx	38	673.78	-77.44	0.00
			Max. My	35	111.16	0.00	2.50
			Max. Vy	38	53.27	0.00	0.00
			Max. Vx	35	-1.72	0.00	0.00

### Maximum Reactions

Location	Condition	Gov. Load Comb.	Vertical lb	Horizontal, X lb	Horizontal, Z lb
Leg C	Max. Vert	18	347561.47	32194.28	-18936.92
	Max. H <sub>x</sub>	18	347561.47	32194.28	-18936.92
	Max. H <sub>z</sub>	7	-292030.36	-27453.56	16142.73
	Min. Vert	7	-292030.36	-27453.56	16142.73
	Min. H <sub>x</sub>	7	-292030.36	-27453.56	16142.73
	Min. H <sub>z</sub>	18	347561.47	32194.28	-18936.92
Leg B	Max. Vert	10	344328.24	-32225.17	-18646.68
	Max. H <sub>x</sub>	23	-293400.85	27579.14	15968.24
	Max. H <sub>z</sub>	23	-293400.85	27579.14	15968.24
	Min. Vert	23	-293400.85	27579.14	15968.24
	Min. H <sub>x</sub>	10	344328.24	-32225.17	-18646.68
	Min. H <sub>z</sub>	10	344328.24	-32225.17	-18646.68
Leg A	Max. Vert	2	346618.74	-253.17	37286.31
	Max. H <sub>x</sub>	21	17184.85	2613.33	1573.79
	Max. H <sub>z</sub>	2	346618.74	-253.17	37286.31
	Min. Vert	15	-291330.44	199.52	-31788.41
	Min. H <sub>x</sub>	9	18315.48	-2656.51	1656.16
	Min. H <sub>z</sub>	15	-291330.44	199.52	-31788.41

### Tower Mast Reaction Summary

Load Combination	Vertical lb	Shear <sub>x</sub> lb	Shear <sub>z</sub> lb	Overturning Moment, M <sub>x</sub> lb-ft	Overturning Moment, M <sub>z</sub> lb-ft	Torque lb-ft
Dead Only	57498.63	0.00	-0.00	-9969.18	19670.08	0.08
1.2 Dead+1.6 Wind 0 deg - No Ice	68998.36	40.37	-56731.25	-5885512.91	15869.28	-8533.08
0.9 Dead+1.6 Wind 0 deg - No Ice	51748.77	40.37	-56731.25	-5870841.24	9922.54	-8489.78

<p style="text-align: center;"><b>tnxTower</b></p> <p style="text-align: center;"><b>Ramaker &amp; Associates, Inc.</b> 855 Community Drive Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999</p>	<p style="text-align: center;"><b>Job</b></p> <p style="text-align: center;">Transfer Station (CT33XC522)</p>	<p style="text-align: center;"><b>Page</b></p> <p style="text-align: center;">26 of 37</p>
	<p style="text-align: center;"><b>Project</b></p> <p style="text-align: center;">28737</p>	<p style="text-align: center;"><b>Date</b></p> <p style="text-align: center;">15:01:07 09/26/17</p>
	<p style="text-align: center;"><b>Client</b></p> <p style="text-align: center;">Transcend Wireless / Sprint</p>	<p style="text-align: center;"><b>Designed by</b></p> <p style="text-align: center;">TEM</p>

Load Combination	Vertical	Shear <sub>x</sub>	Shear <sub>z</sub>	Overturning Moment, M <sub>x</sub>	Overturning Moment, M <sub>z</sub>	Torque
	lb	lb	lb	lb-ft	lb-ft	lb-ft
1.2 Dead+1.6 Wind 30 deg - No Ice	68998.36	26934.34	-46603.91	-4890402.17	-2798303.77	-9993.14
0.9 Dead+1.6 Wind 30 deg - No Ice	51748.77	26934.34	-46603.90	-4877636.61	-2798634.31	-9943.34
1.2 Dead+1.6 Wind 60 deg - No Ice	68998.36	46540.20	-26891.52	-2838480.73	-4864900.05	-9772.68
0.9 Dead+1.6 Wind 60 deg - No Ice	51748.77	46540.20	-26891.51	-2829794.05	-4861096.58	-9729.82
1.2 Dead+1.6 Wind 90 deg - No Ice	68998.36	53841.22	-57.82	-22445.63	-5612612.76	-6893.55
0.9 Dead+1.6 Wind 90 deg - No Ice	51748.77	53841.22	-57.82	-19384.77	-5607335.41	-6868.96
1.2 Dead+1.6 Wind 120 deg - No Ice	68998.36	49145.44	28316.49	2915844.57	-5064440.90	-1340.17
0.9 Dead+1.6 Wind 120 deg - No Ice	51748.77	49145.44	28316.49	2913077.24	-5060327.00	-1340.75
1.2 Dead+1.6 Wind 150 deg - No Ice	68998.36	26870.53	46556.94	4857469.58	-2785447.22	4298.05
0.9 Dead+1.6 Wind 150 deg - No Ice	51748.77	26870.53	46556.93	4850785.77	-2785820.63	4272.54
1.2 Dead+1.6 Wind 180 deg - No Ice	68998.36	-68.55	53664.29	5620227.27	35632.16	7966.12
0.9 Dead+1.6 Wind 180 deg - No Ice	51748.77	-68.55	53664.29	5612001.08	29630.91	7924.83
1.2 Dead+1.6 Wind 210 deg - No Ice	68998.36	-26979.46	46577.86	4862648.18	2852154.53	9992.24
0.9 Dead+1.6 Wind 210 deg - No Ice	51748.77	-26979.46	46577.86	4855946.58	2840534.84	9942.49
1.2 Dead+1.6 Wind 240 deg - No Ice	68998.36	-49210.36	28400.58	2931494.03	5123303.44	10382.93
0.9 Dead+1.6 Wind 240 deg - No Ice	51748.77	-49210.36	28400.58	2928681.47	5107218.91	10338.50
1.2 Dead+1.6 Wind 270 deg - No Ice	68998.36	-53895.75	57.30	-1825.65	5667709.17	6824.91
0.9 Dead+1.6 Wind 270 deg - No Ice	51748.77	-53895.74	57.30	1177.37	5650476.57	6800.31
1.2 Dead+1.6 Wind 300 deg - No Ice	68998.36	-46562.52	-26825.24	-2825247.09	4913231.37	1297.18
0.9 Dead+1.6 Wind 300 deg - No Ice	51748.77	-46562.52	-26825.24	-2816603.84	4897492.36	1296.95
1.2 Dead+1.6 Wind 330 deg - No Ice	68998.36	-26898.25	-46603.90	-4888073.05	2836853.86	-4228.45
0.9 Dead+1.6 Wind 330 deg - No Ice	51748.77	-26898.25	-46603.89	-4875320.59	2825274.92	-4202.88
1.2 Dead+1.0 Ice+1.0 Temp	187983.55	0.00	0.00	-49263.73	75430.71	1.03
1.2 Dead+1.0 Wind 0 deg+1.0 Ice+1.0 Temp	187983.54	-3.53	-16348.27	-1821880.59	75660.03	-2325.50
1.2 Dead+1.0 Wind 30 deg+1.0 Ice+1.0 Temp	187983.54	8030.51	-13900.07	-1562960.39	-799468.53	-2811.25
1.2 Dead+1.0 Wind 60 deg+1.0 Ice+1.0 Temp	187983.54	13791.22	-7953.52	-919321.35	-1433337.35	-2647.07
1.2 Dead+1.0 Wind 90 deg+1.0 Ice+1.0 Temp	187983.54	16076.30	-0.25	-49771.26	-1675977.81	-1728.38
1.2 Dead+1.0 Wind 120 deg+1.0 Ice+1.0 Temp	187983.54	14178.44	8174.13	836585.88	-1462483.58	-264.98
1.2 Dead+1.0 Wind 150 deg+1.0 Ice+1.0 Temp	187983.54	8037.94	13902.18	1464181.64	-799849.57	1198.30
1.2 Dead+1.0 Wind 180 deg+1.0 Ice+1.0 Temp	187983.54	-2.56	15902.62	1689300.40	76297.53	2261.93
1.2 Dead+1.0 Wind 210 deg+1.0 Ice+1.0 Temp	187983.54	-8040.25	13894.45	1463472.59	951940.12	2811.11
1.2 Dead+1.0 Wind 240 deg+1.0 Ice+1.0 Temp	187983.54	-14180.21	8171.08	836822.44	1614212.11	2706.98
1.2 Dead+1.0 Wind 270 deg+1.0 Ice+1.0 Temp	187983.54	-16088.08	0.12	-48943.87	1828732.17	1712.86
1.2 Dead+1.0 Wind 300 deg+1.0 Ice+1.0 Temp	187983.54	-13808.29	-7960.42	-919622.54	1586456.02	268.11
1.2 Dead+1.0 Wind 330 deg+1.0 Ice+1.0 Temp	187983.54	-8043.93	-13912.32	-1564302.84	951789.83	-1182.76
Dead+Wind 0 deg - Service	57498.63	10.50	-14758.38	-1536037.72	17724.76	-2212.62
Dead+Wind 30 deg - Service	57498.63	7006.85	-12123.80	-1277476.65	-713417.11	-2594.94
Dead+Wind 60 deg - Service	57498.63	12107.23	-6995.71	-744367.06	-1250369.64	-2534.22
Dead+Wind 90 deg - Service	57498.63	14006.56	-15.04	-12709.05	-1444611.30	-1786.66
Dead+Wind 120 deg - Service	57498.63	12784.97	7366.41	750682.44	-1302206.87	-348.82
Dead+Wind 150 deg - Service	57498.63	6990.25	12111.58	1255116.00	-710096.09	1110.33
Dead+Wind 180 deg - Service	57498.63	-17.83	13960.53	1453316.69	22853.52	2065.39
Dead+Wind 210 deg - Service	57498.63	-7018.59	12117.03	1256464.71	754625.76	2594.86
Dead+Wind 240 deg - Service	57498.63	-12801.86	7388.29	754752.69	1344706.40	2694.78
Dead+Wind 270 deg - Service	57498.63	-14020.74	14.91	-7351.64	1486146.98	1768.00
Dead+Wind 300 deg - Service	57498.63	-12113.04	-6978.47	-740933.95	1290133.56	338.57
Dead+Wind 330 deg - Service	57498.63	-6997.46	-12123.80	-1276890.50	750642.04	-1093.19

## Solution Summary

Load Comb.	Sum of Applied Forces			Sum of Reactions			% Error
	PX lb	PY lb	PZ lb	PX lb	PY lb	PZ lb	
1	0.00	-57498.63	0.00	-0.00	57498.63	0.00	0.000%
2	40.37	-68998.36	-56731.23	-40.37	68998.36	56731.25	0.000%
3	40.37	-51748.77	-56731.23	-40.37	51748.77	56731.25	0.000%
4	26934.34	-68998.36	-46603.89	-26934.34	68998.36	46603.91	0.000%
5	26934.34	-51748.77	-46603.89	-26934.34	51748.77	46603.90	0.000%

<b>tnxTower</b>  <b>Ramaker &amp; Associates, Inc.</b> 855 Community Drive Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b>	Transfer Station (CT33XC522)	<b>Page</b>	27 of 37
	<b>Project</b>	28737	<b>Date</b>	15:01:07 09/26/17
	<b>Client</b>	Transcend Wireless / Sprint	<b>Designed by</b>	TEM

Load Comb.	Sum of Applied Forces			Sum of Reactions			% Error
	PX lb	PY lb	PZ lb	PX lb	PY lb	PZ lb	
6	46540.19	-68998.36	-26891.50	-46540.20	68998.36	26891.52	0.000%
7	46540.19	-51748.77	-26891.50	-46540.20	51748.77	26891.51	0.000%
8	53841.20	-68998.36	-57.83	-53841.22	68998.36	57.82	0.000%
9	53841.20	-51748.77	-57.83	-53841.22	51748.77	57.82	0.000%
10	49145.42	-68998.36	28316.48	-49145.44	68998.36	-28316.49	0.000%
11	49145.42	-51748.77	28316.48	-49145.44	51748.77	-28316.49	0.000%
12	26870.52	-68998.36	46556.92	-26870.53	68998.36	-46556.94	0.000%
13	26870.52	-51748.77	46556.92	-26870.53	51748.77	-46556.93	0.000%
14	-68.55	-68998.36	53664.27	68.55	68998.36	-53664.29	0.000%
15	-68.55	-51748.77	53664.27	68.55	51748.77	-53664.29	0.000%
16	-26979.44	-68998.36	46577.85	26979.46	68998.36	-46577.86	0.000%
17	-26979.44	-51748.77	46577.85	26979.46	51748.77	-46577.86	0.000%
18	-49210.34	-68998.36	28400.58	49210.36	68998.36	-28400.58	0.000%
19	-49210.34	-51748.77	28400.58	49210.36	51748.77	-28400.58	0.000%
20	-53895.73	-68998.36	57.30	53895.75	68998.36	-57.30	0.000%
21	-53895.73	-51748.77	57.30	53895.74	51748.77	-57.30	0.000%
22	-46562.51	-68998.36	-26825.23	46562.52	68998.36	26825.24	0.000%
23	-46562.51	-51748.77	-26825.23	46562.52	51748.77	26825.24	0.000%
24	-26898.24	-68998.36	-46603.88	26898.25	68998.36	46603.90	0.000%
25	-26898.24	-51748.77	-46603.88	26898.25	51748.77	46603.89	0.000%
26	0.00	-187983.55	0.00	-0.00	187983.55	-0.00	0.000%
27	-3.53	-187983.55	-16348.29	3.53	187983.54	16348.27	0.000%
28	8030.52	-187983.55	-13900.09	-8030.51	187983.54	13900.07	0.000%
29	13791.23	-187983.55	-7953.53	-13791.22	187983.54	7953.52	0.000%
30	16076.32	-187983.55	-0.24	-16076.30	187983.54	0.25	0.000%
31	14178.46	-187983.55	8174.14	-14178.44	187983.54	-8174.13	0.000%
32	8037.95	-187983.55	13902.19	-8037.94	187983.54	-13902.18	0.000%
33	-2.56	-187983.55	15902.63	2.56	187983.54	-15902.62	0.000%
34	-8040.26	-187983.55	13894.46	8040.25	187983.54	-13894.45	0.000%
35	-14180.23	-187983.55	8171.09	14180.21	187983.54	-8171.08	0.000%
36	-16088.10	-187983.55	0.13	16088.08	187983.54	-0.12	0.000%
37	-13808.30	-187983.55	-7960.43	13808.29	187983.54	7960.42	0.000%
38	-8043.94	-187983.55	-13912.34	8043.93	187983.54	13912.32	0.000%
39	10.50	-57498.63	-14758.38	-10.50	57498.63	14758.38	0.000%
40	7006.85	-57498.63	-12123.80	-7006.85	57498.63	12123.80	0.000%
41	12107.23	-57498.63	-6995.71	-12107.23	57498.63	6995.71	0.000%
42	14006.56	-57498.63	-15.04	-14006.56	57498.63	15.04	0.000%
43	12784.97	-57498.63	7366.41	-12784.97	57498.63	-7366.41	0.000%
44	6990.25	-57498.63	12111.58	-6990.25	57498.63	-12111.58	0.000%
45	-17.83	-57498.63	13960.53	17.83	57498.63	-13960.53	0.000%
46	-7018.59	-57498.63	12117.03	7018.59	57498.63	-12117.03	0.000%
47	-12801.86	-57498.63	7388.29	12801.86	57498.63	-7388.29	0.000%
48	-14020.74	-57498.63	14.91	14020.74	57498.63	-14.91	0.000%
49	-12113.04	-57498.63	-6978.47	12113.04	57498.63	6978.47	0.000%
50	-6997.46	-57498.63	-12123.80	6997.46	57498.63	12123.80	0.000%

### Non-Linear Convergence Results

Load Combination	Converged?	Number of Cycles	Displacement Tolerance	Force Tolerance
1	Yes	4	0.00000001	0.00000001
2	Yes	4	0.00000001	0.00000111
3	Yes	4	0.00000001	0.00000050
4	Yes	4	0.00000001	0.00000138
5	Yes	4	0.00000001	0.00000079
6	Yes	4	0.00000001	0.00000150

<b>tnxTower</b>  <b>Ramaker &amp; Associates, Inc.</b> 855 Community Drive Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b>	Transfer Station (CT33XC522)	<b>Page</b>	28 of 37
	<b>Project</b>	28737	<b>Date</b>	15:01:07 09/26/17
	<b>Client</b>	Transcend Wireless / Sprint	<b>Designed by</b>	TEM

7	Yes	4	0.00000001	0.00000083
8	Yes	4	0.00000001	0.00000151
9	Yes	4	0.00000001	0.00000093
10	Yes	4	0.00000001	0.00000110
11	Yes	4	0.00000001	0.00000047
12	Yes	4	0.00000001	0.00000147
13	Yes	4	0.00000001	0.00000087
14	Yes	4	0.00000001	0.00000149
15	Yes	4	0.00000001	0.00000080
16	Yes	4	0.00000001	0.00000138
17	Yes	4	0.00000001	0.00000079
18	Yes	4	0.00000001	0.00000112
19	Yes	4	0.00000001	0.00000052
20	Yes	4	0.00000001	0.00000151
21	Yes	4	0.00000001	0.00000093
22	Yes	4	0.00000001	0.00000148
23	Yes	4	0.00000001	0.00000082
24	Yes	4	0.00000001	0.00000146
25	Yes	4	0.00000001	0.00000087
26	Yes	4	0.00000001	0.00000331
27	Yes	4	0.00000001	0.00004629
28	Yes	4	0.00000001	0.00004590
29	Yes	4	0.00000001	0.00004565
30	Yes	4	0.00000001	0.00004504
31	Yes	4	0.00000001	0.00004480
32	Yes	4	0.00000001	0.00004474
33	Yes	4	0.00000001	0.00004523
34	Yes	4	0.00000001	0.00004552
35	Yes	4	0.00000001	0.00004604
36	Yes	4	0.00000001	0.00004635
37	Yes	4	0.00000001	0.00004667
38	Yes	4	0.00000001	0.00004646
39	Yes	4	0.00000001	0.00000001
40	Yes	4	0.00000001	0.00000001
41	Yes	4	0.00000001	0.00000001
42	Yes	4	0.00000001	0.00000001
43	Yes	4	0.00000001	0.00000001
44	Yes	4	0.00000001	0.00000001
45	Yes	4	0.00000001	0.00000001
46	Yes	4	0.00000001	0.00000001
47	Yes	4	0.00000001	0.00000001
48	Yes	4	0.00000001	0.00000001
49	Yes	4	0.00000001	0.00000001
50	Yes	4	0.00000001	0.00000001

### Maximum Tower Deflections - Service Wind

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
T1	185 - 180	7.326	47	0.3819	0.0106
T2	180 - 160	6.923	47	0.3804	0.0107
T3	160 - 140	5.350	47	0.3462	0.0112
T4	140 - 120	3.962	47	0.2921	0.0092
T5	120 - 100	2.821	47	0.2345	0.0066
T6	100 - 93.3333	1.919	47	0.1803	0.0050
T7	93.3333 - 86.6667	1.664	47	0.1669	0.0044
T8	86.6667 - 80	1.428	47	0.1533	0.0039
T9	80 - 60	1.217	47	0.1393	0.0036
T10	60 - 50	0.684	47	0.0973	0.0023

<b>tnxTower</b>  <b>Ramaker &amp; Associates, Inc.</b> 855 Community Drive Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b>	Transfer Station (CT33XC522)	<b>Page</b>	29 of 37
	<b>Project</b>	28737	<b>Date</b>	15:01:07 09/26/17
	<b>Client</b>	Transcend Wireless / Sprint	<b>Designed by</b>	TEM

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
T11	50 - 40	0.481	47	0.0807	0.0018
T12	40 - 20	0.324	47	0.0638	0.0015
T13	20 - 0	0.095	47	0.0319	0.0007

### Critical Deflections and Radius of Curvature - Service Wind

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
185.00	6' Dipole	47	7.326	0.3819	0.0106	297187
174.00	APXVSP18-C w/Mount Pipe	47	6.441	0.3744	0.0109	69374
164.00	BXA-70063-6CF-EDIN-X w/Mount Pipe	47	5.655	0.3557	0.0112	28096
154.00	7770.00 w/Mount Pipe	47	4.910	0.3309	0.0108	21299
146.00	15' Omni	47	4.353	0.3091	0.0100	19706
138.00	Andrew 3' w/Radome	47	3.836	0.2864	0.0089	18744

### Maximum Tower Deflections - Design Wind

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
T1	185 - 180	28.090	18	1.4668	0.0408
T2	180 - 160	26.544	18	1.4608	0.0413
T3	160 - 140	20.507	18	1.3280	0.0431
T4	140 - 120	15.182	18	1.1199	0.0354
T5	120 - 100	10.808	18	0.8985	0.0255
T6	100 - 93.3333	7.352	18	0.6907	0.0193
T7	93.3333 - 86.6667	6.377	18	0.6393	0.0171
T8	86.6667 - 80	5.472	18	0.5872	0.0149
T9	80 - 60	4.662	18	0.5334	0.0138
T10	60 - 50	2.622	18	0.3725	0.0089
T11	50 - 40	1.845	18	0.3089	0.0069
T12	40 - 20	1.240	18	0.2441	0.0060
T13	20 - 0	0.366	18	0.1220	0.0028

### Critical Deflections and Radius of Curvature - Design Wind

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
185.00	6' Dipole	18	28.090	1.4668	0.0408	80514
174.00	APXVSP18-C w/Mount Pipe	18	24.694	1.4377	0.0422	18180
164.00	BXA-70063-6CF-EDIN-X w/Mount Pipe	18	21.675	1.3648	0.0433	7322
154.00	7770.00 w/Mount Pipe	18	18.816	1.2688	0.0418	5548
146.00	15' Omni	18	16.683	1.1849	0.0384	5129
138.00	Andrew 3' w/Radome	18	14.701	1.0981	0.0343	4890



<b>tnxTower</b>  <b>Ramaker &amp; Associates, Inc.</b> 855 Community Drive Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b> Transfer Station (CT33XC522)	<b>Page</b> 30 of 37
	<b>Project</b> 28737	<b>Date</b> 15:01:07 09/26/17
	<b>Client</b> Transcend Wireless / Sprint	<b>Designed by</b> TEM

### Bolt Design Data

Section No.	Elevation ft	Component Type	Bolt Grade	Bolt Size in	Number Of Bolts	Maximum Load per Bolt lb	Allowable Load lb	Ratio Load Allowable	Allowable Ratio	Criteria
T1	185	Leg	A325X	0.7500	6	281.47	29820.60	0.009	✓	1 Bolt Tension
		Diagonal	A325X	0.6250	1	1342.17	6009.38	0.223	✓	1 Member Block Shear
		Top Girt	A325X	0.6250	1	499.07	4553.91	0.110	✓	1 Member Block Shear
T2	180	Leg	A325X	0.7500	6	4529.88	29820.60	0.152	✓	1 Bolt Tension
		Diagonal	A325X	0.6250	1	4967.68	6009.38	0.827	✓	1 Member Block Shear
		Top Girt	A325X	0.6250	1	406.67	4553.91	0.089	✓	1 Member Block Shear
T3	160	Leg	A325X	1.0000	6	11416.50	53014.40	0.215	✓	1 Bolt Tension
		Diagonal	A325X	0.6250	1	5175.93	6009.38	0.861	✓	1 Member Block Shear
		Top Girt	A325X	0.6250	1	401.92	4553.91	0.088	✓	1 Member Block Shear
T4	140	Leg	A325X	1.0000	6	17541.50	53014.40	0.331	✓	1 Bolt Tension
		Diagonal	A325X	0.6250	1	5835.35	8634.38	0.676	✓	1 Member Block Shear
		Secondary Horizontal	A325N	0.7500	1	2075.23	9243.75	0.225	✓	1 Member Block Shear
T5	120	Leg	A325X	1.0000	6	22774.40	53014.40	0.430	✓	1 Bolt Tension
		Diagonal	A325X	0.6250	1	8468.07	10673.40	0.793	✓	1 Member Block Shear
		Horizontal	A325N	0.7500	1	2715.01	17892.40	0.152	✓	1 Bolt Shear
T6	100	Diagonal	A325X	0.6250	1	6757.32	10673.40	0.633	✓	1 Member Block Shear
T7	93.3333	Diagonal	A325X	0.6250	1	6721.37	10673.40	0.630	✓	1 Member Block Shear
		Leg	A325X	1.0000	6	28548.80	53014.40	0.539	✓	1 Bolt Tension
T8	86.6667	Diagonal	A325X	0.6250	1	7296.79	15660.00	0.466	✓	1 Gusset Bearing
		Leg	A325X	1.0000	6	33543.50	53014.40	0.633	✓	1 Bolt Tension
T9	80	Diagonal	A325X	0.7500	1	8672.76	11183.20	0.776	✓	1 Member Block Shear
		Horizontal	A325N	0.7500	1	4044.18	17892.40	0.226	✓	1 Bolt Shear
		Diagonal	A325X	0.7500	1	8924.50	14910.90	0.599	✓	1 Member Block Shear
T10	60	Secondary Horizontal	A325N	0.7500	1	4310.48	17892.40	0.241	✓	1 Bolt Shear
		Leg	A325X	1.2500	6	38285.10	82835.00	0.462	✓	1 Bolt Tension
T11	50	Diagonal	A325X	0.7500	1	9292.66	18922.50	0.491	✓	1 Gusset Bearing
		Secondary Horizontal	A325N	0.7500	1	4634.54	17892.40	0.259	✓	1 Bolt Shear
		Leg	A325X	1.2500	6	43014.60	82835.00	0.519	✓	1 Bolt Tension
T12	40	Diagonal	A325X	0.7500	1	10417.50	17629.70	0.591	✓	1 Member Block Shear
		Secondary Horizontal	A325N	0.7500	1	5235.37	17892.40	0.293	✓	1 Bolt Shear
		Diagonal	A325X	0.7500	1	11518.50	17629.70	0.653	✓	1 Member Block Shear
T13	20	Horizontal	A325N	0.7500	1	5845.21	17892.40	0.327	✓	1 Bolt Shear

### Compression Checks

<b>tnxTower</b>  <b>Ramaker &amp; Associates, Inc.</b> 855 Community Drive Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b> Transfer Station (CT33XC522)	<b>Page</b> 31 of 37
	<b>Project</b> 28737	<b>Date</b> 15:01:07 09/26/17
	<b>Client</b> Transcend Wireless / Sprint	<b>Designed by</b> TEM

### Leg Design Data (Compression)

Section No.	Elevation <i>ft</i>	Size	L <i>ft</i>	L <sub>u</sub> <i>ft</i>	Kl/r	A <i>in</i> <sup>2</sup>	P <sub>u</sub> <i>lb</i>	φP <sub>n</sub> <i>lb</i>	Ratio $\frac{P_u}{\phi P_n}$
T1	185 - 180	P2x.154	5.00	5.00	76.2 K=1.00	1.0745	-2848.82	31617.20	0.090 <sup>1</sup>
T2	180 - 160	P2.5x.203	20.00	5.00	63.3 K=1.00	1.7040	-32295.60	57192.30	0.565 <sup>1</sup>
T3	160 - 140	P2.5x.375	20.03	5.01	67.2 K=1.00	2.9452	-78888.10	95225.20	0.828 <sup>1</sup>
T4	140 - 120	P3.5x.318	20.03	2.59	23.8 K=1.00	3.6784	-119664.00	158818.00	0.753 <sup>1</sup>
T5	120 - 100	P5x.258	20.03	1.67	10.7 K=1.00	4.2999	-156556.00	191890.00	0.816 <sup>1</sup>
T6	100 - 93.3333	P5x.375	6.68	6.68	43.6 K=1.00	6.1120	-171098.00	239388.00	0.715 <sup>1</sup>
T7	93.3333 - 86.6667	P5x.375	6.68	6.68	43.6 K=1.00	6.1120	-183429.00	239388.00	0.766 <sup>1</sup>
T8	86.6667 - 80	P5x.375	6.68	6.68	43.6 K=1.00	6.1120	-195841.00	239388.00	0.818 <sup>1</sup>
T9	80 - 60	P5x.375	20.03	1.67	10.9 K=1.00	6.1120	-233200.00	272663.00	0.855 <sup>1</sup>
T10	60 - 50	P5x.5	10.02	5.17	34.5 K=1.00	7.9529	-248556.00	328070.00	0.758 <sup>1</sup>
T11	50 - 40	P5x.5	10.02	5.16	34.4 K=1.00	7.9529	-267242.00	328178.00	0.814 <sup>1</sup>
T12	40 - 20	P8x.322	20.03	5.15	21.0 K=1.00	8.3993	-301887.00	365926.00	0.825 <sup>1</sup>
T13	20 - 0	P8x.322	20.03	2.50	10.2 K=1.00	8.3993	-337053.00	375086.00	0.899 <sup>1</sup>

<sup>1</sup> P<sub>u</sub> / φP<sub>n</sub> controls

### Diagonal Design Data (Compression)

Section No.	Elevation <i>ft</i>	Size	L <i>ft</i>	L <sub>u</sub> <i>ft</i>	Kl/r	A <i>in</i> <sup>2</sup>	P <sub>u</sub> <i>lb</i>	φP <sub>n</sub> <i>lb</i>	Ratio $\frac{P_u}{\phi P_n}$
T1	185 - 180	L2x2x1/8	7.07	3.22	102.9 K=1.06	0.4844	-1559.68	8852.07	0.176 <sup>1</sup>
T2	180 - 160	L2x2x1/8	7.07	3.19	102.2 K=1.06	0.4844	-5144.57	8913.86	0.577 <sup>1</sup>
T3	160 - 140	L2x2x1/8	8.40	4.03	121.7 K=1.00	0.4844	-5272.29	7142.85	0.738 <sup>1</sup>
T4	140 - 120	L2x2x3/16	10.08	4.82	146.9 K=1.00	0.7150	-6053.98	7480.29	0.809 <sup>1</sup>
T5	120 - 100	L2 1/2x2 1/2x3/16	6.15	5.55	102.8 K=1.20	0.9020	-9430.09	16761.30	0.563 <sup>1</sup>
T6	100 - 93.3333	L2 1/2x2 1/2x3/16	13.15	6.33	153.5 K=1.00	0.9020	-6795.90	8645.55	0.786 <sup>1</sup>

<b>tnxTower</b>  <b>Ramaker &amp; Associates, Inc.</b> 855 Community Drive Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b> Transfer Station (CT33XC522)	<b>Page</b> 32 of 37
	<b>Project</b> 28737	<b>Date</b> 15:01:07 09/26/17
	<b>Client</b> Transcend Wireless / Sprint	<b>Designed by</b> TEM

Section No.	Elevation ft	Size	L ft	L <sub>u</sub> ft	Kl/r	A in <sup>2</sup>	P <sub>u</sub> lb	φP <sub>n</sub> lb	Ratio $\frac{P_u}{\phi P_n}$
T7	93.3333 - 86.6667	L2 1/2x2 1/2x3/16	13.73	6.62	160.6 K=1.00	0.9020	-6949.55	7904.00	0.879 <sup>1</sup>
T8	86.6667 - 80	2L2 1/2x2 1/2x3/16x3/8	14.32	6.92	106.7 K=1.00	1.8047	-7580.82	32125.70	0.236 <sup>1</sup>
T9	80 - 60	L3x3x3/16	7.90	7.32	106.8 K=1.14	1.0900	-9881.02	19110.00	0.517 <sup>1</sup>
T10	60 - 50	L3x3x1/4	18.45	9.08	184.0 K=1.00	1.4400	-9491.07	9604.97	0.988 <sup>1</sup>
T11	50 - 40	2L3x3x1/4x3/8	19.30	9.50	122.6 K=1.00	2.8750	-10003.90	42238.70	0.237 <sup>1</sup>
T12	40 - 20	L3 1/2x3 1/2x1/4	21.03	10.22	176.8 K=1.00	1.6900	-11453.10	12214.20	0.938 <sup>1</sup>
T13	20 - 0	L3 1/2x3 1/2x1/4	11.18	10.45	117.5 K=1.02	1.6900	-13341.10	26464.10	0.504 <sup>1</sup>

<sup>1</sup> P<sub>u</sub> / φP<sub>n</sub> controls

### Horizontal Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L <sub>u</sub> ft	Kl/r	A in <sup>2</sup>	P <sub>u</sub> lb	φP <sub>n</sub> lb	Ratio $\frac{P_u}{\phi P_n}$
T5	120 - 100	L2 1/2x2 1/2x3/8	10.67	4.97	122.4 K=1.00	1.7300	-2715.01	25482.20	0.107 <sup>1</sup>
T9	80 - 60	L3x3x3/8	14.67	6.97	142.4 K=1.00	2.1100	-4044.18	23504.60	0.172 <sup>1</sup>
T13	20 - 0	L3 1/2x3 1/2x1/2	20.50	9.76	171.4 K=1.00	3.2500	-5845.21	24993.60	0.234 <sup>1</sup>

<sup>1</sup> P<sub>u</sub> / φP<sub>n</sub> controls

### Secondary Horizontal Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L <sub>u</sub> ft	Kl/r	A in <sup>2</sup>	P <sub>u</sub> lb	φP <sub>n</sub> lb	Ratio $\frac{P_u}{\phi P_n}$
T4	140 - 120	L2x2x1/4	8.74	8.14	160.4 K=1.00	0.9380	-2075.23	8239.59	0.252 <sup>1</sup>
T10	60 - 50	L3x3x7/16	15.48	14.75	195.6 K=1.00	2.4300	-4310.48	14352.50	0.300 <sup>1</sup>
T11	50 - 40	L3x3x7/16	16.48	15.75	208.8 K=1.00	2.4300	-4634.54	12586.20	0.368 <sup>1</sup>
T12	40 - 20	L3x3x1/2	18.49	17.50	233.8 K=1.00	2.7500	-5235.37	11364.20	0.461 <sup>1</sup>

<b>tnxTower</b>  <b>Ramaker &amp; Associates, Inc.</b> 855 Community Drive Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b> Transfer Station (CT33XC522)	<b>Page</b> 33 of 37
	<b>Project</b> 28737	<b>Date</b> 15:01:07 09/26/17
	<b>Client</b> Transcend Wireless / Sprint	<b>Designed by</b> TEM

<sup>1</sup>  $P_u / \phi P_n$  controls

### Top Girt Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L <sub>u</sub> ft	Kl/r	A in <sup>2</sup>	P <sub>u</sub> lb	$\phi P_n$ lb	Ratio $\frac{P_u}{\phi P_n}$
T1	185 - 180	L2x2x1/8	5.00	4.56	137.7 K=1.00	0.4844	-358.31	5769.26	0.062 <sup>1</sup> ✓
T2	180 - 160	L2x2x1/8	5.00	4.56	137.7 K=1.00	0.4844	-290.03	5769.26	0.050 <sup>1</sup> ✓
T3	160 - 140	L2x2x1/8	5.00	4.52	136.5 K=1.00	0.4844	-427.02	5876.09	0.073 <sup>1</sup> ✓

<sup>1</sup>  $P_u / \phi P_n$  controls

### Redundant Horizontal (1) Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L <sub>u</sub> ft	Kl/r	A in <sup>2</sup>	$\parallel_{Tr}$ lb	$\phi P_n$ lb	Ratio $\frac{P_u}{\phi P_n}$
T5	120 - 100	L3x3x1/2	2.67	2.43	85.0 K=1.70	2.7500	-5643.10	60901.70	0.093 <sup>1</sup> ✓
T9	80 - 60	L3x3x1/2	3.67	3.43	95.3 K=1.35	2.7500	-5235.94	55242.90	0.095 <sup>1</sup> ✓
T13	20 - 0	L3x3x1/2	5.13	4.77	109.0 K=1.11	2.7500	-7354.63	47690.30	0.154 <sup>1</sup> ✓

<sup>1</sup>  $P_u / \phi P_n$  controls

### Redundant Diagonal (1) Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L <sub>u</sub> ft	Kl/r	A in <sup>2</sup>	P <sub>u</sub> lb	$\phi P_n$ lb	Ratio $\frac{P_u}{\phi P_n}$
T5	120 - 100	L3x3x1/2	3.22	2.94	90.2 K=1.49	2.7500	-3926.00	58054.10	0.068 <sup>1</sup> ✓
T9	80 - 60	L3x3x1/2	4.10	3.85	99.5 K=1.26	2.7500	-3445.90	52887.70	0.065 <sup>1</sup> ✓
T13	20 - 0	L3x3x1/2	5.82	5.41	115.6 K=1.04	2.7500	-5133.24	44081.10	0.116 <sup>1</sup> ✓

<sup>1</sup>  $P_u / \phi P_n$  controls

### Tension Checks

<b>tnxTower</b>  <b>Ramaker &amp; Associates, Inc.</b> 855 Community Drive Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b> Transfer Station (CT33XC522)	<b>Page</b> 34 of 37
	<b>Project</b> 28737	<b>Date</b> 15:01:07 09/26/17
	<b>Client</b> Transcend Wireless / Sprint	<b>Designed by</b> TEM

### Leg Design Data (Tension)

Section No.	Elevation <i>ft</i>	Size	<i>L</i> <i>ft</i>	<i>L<sub>u</sub></i> <i>ft</i>	<i>Kl/r</i>	<i>A</i> <i>in<sup>2</sup></i>	<i>P<sub>u</sub></i> <i>lb</i>	$\phi P_n$ <i>lb</i>	Ratio $\frac{P_u}{\phi P_n}$
T1	185 - 180	P2x.154	5.00	5.00	76.2	1.0745	1688.83	48353.90	0.035 <sup>1</sup>
T2	180 - 160	P2.5x.203	20.00	5.00	63.3	1.7040	27179.30	76682.30	0.354 <sup>1</sup>
T3	160 - 140	P2.5x.375	20.03	5.01	67.2	2.9452	68498.80	132536.00	0.517 <sup>1</sup>
T4	140 - 120	P3.5x.318	20.03	2.59	23.8	3.6784	105414.00	165529.00	0.637 <sup>1</sup>
T5	120 - 100	P5x.258	20.03	1.67	10.7	4.2999	136915.00	193494.00	0.708 <sup>1</sup>
T6	100 - 93.3333	P5x.375	6.68	6.68	43.6	6.1120	149511.00	275039.00	0.544 <sup>1</sup>
T7	93.3333 - 86.6667	P5x.375	6.68	6.68	43.6	6.1120	160480.00	275039.00	0.583 <sup>1</sup>
T8	86.6667 - 80	P5x.375	6.68	6.68	43.6	6.1120	171293.00	275039.00	0.623 <sup>1</sup>
T9	80 - 60	P5x.375	20.03	1.67	10.9	6.1120	201488.00	275039.00	0.733 <sup>1</sup>
T10	60 - 50	P5x.5	10.02	5.17	34.5	7.9529	214462.00	357882.00	0.599 <sup>1</sup>
T11	50 - 40	P5x.5	10.02	5.16	34.4	7.9529	229950.00	357882.00	0.643 <sup>1</sup>
T12	40 - 20	P8x.322	20.03	5.15	21.0	8.3993	258493.00	377967.00	0.684 <sup>1</sup>
T13	20 - 0	P8x.322	20.03	2.50	10.2	8.3993	285152.00	377967.00	0.754 <sup>1</sup>

<sup>1</sup>  $P_u / \phi P_n$  controls

### Diagonal Design Data (Tension)

Section No.	Elevation <i>ft</i>	Size	<i>L</i> <i>ft</i>	<i>L<sub>u</sub></i> <i>ft</i>	<i>Kl/r</i>	<i>A</i> <i>in<sup>2</sup></i>	<i>P<sub>u</sub></i> <i>lb</i>	$\phi P_n$ <i>lb</i>	Ratio $\frac{P_u}{\phi P_n}$
T1	185 - 180	L2x2x1/8	7.07	3.22	65.1	0.4844	1342.17	15693.80	0.086 <sup>1</sup>
T2	180 - 160	L2x2x1/8	7.07	3.19	64.5	0.4844	4967.68	15693.80	0.317 <sup>1</sup>
T3	160 - 140	L2x2x1/8	8.40	4.03	80.6	0.4844	5175.93	15693.80	0.330 <sup>1</sup>
T4	140 - 120	L2x2x3/16	10.08	4.82	97.1	0.7150	5835.35	23166.00	0.252 <sup>1</sup>
T5	120 - 100	L2 1/2x2 1/2x3/16	6.15	5.55	90.7	0.9020	8468.07	29224.80	0.290 <sup>1</sup>
T6	100 - 93.3333	L2 1/2x2 1/2x3/16	13.15	6.33	100.3	0.9020	6757.32	29224.80	0.231 <sup>1</sup>

<b>tnxTower</b>  <b>Ramaker &amp; Associates, Inc.</b> 855 Community Drive Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b> Transfer Station (CT33XC522)	<b>Page</b> 35 of 37
	<b>Project</b> 28737	<b>Date</b> 15:01:07 09/26/17
	<b>Client</b> Transcend Wireless / Sprint	<b>Designed by</b> TEM

Section No.	Elevation ft	Size	L ft	L <sub>u</sub> ft	Kl/r	A in <sup>2</sup>	P <sub>u</sub> lb	φP <sub>n</sub> lb	Ratio $\frac{P_u}{\phi P_n}$
T7	93.3333 - 86.6667	L2 1/2x2 1/2x3/16	13.73	6.62	104.7	0.9020	6721.37	29224.80	0.230 <sup>1</sup>
T8	86.6667 - 80	2L2 1/2x2 1/2x3/16x3/8	14.32	6.92	109.2	1.8047	7296.79	58471.90	0.125 <sup>1</sup>
T9	80 - 60	L3x3x3/16	7.90	7.32	97.8	1.0900	8672.76	35316.00	0.246 <sup>1</sup>
T10	60 - 50	L3x3x1/4	18.45	9.08	119.3	1.4400	8924.50	46656.00	0.191 <sup>1</sup>
T11	50 - 40	2L3x3x1/4x3/8	19.30	9.50	124.7	2.8750	9292.66	93150.00	0.100 <sup>1</sup>
T12	40 - 20	L3 1/2x3 1/2x1/4	21.03	10.22	114.4	1.6900	10417.50	54756.00	0.190 <sup>1</sup>
T13	20 - 0	L3 1/2x3 1/2x1/4	11.18	10.45	118.7	1.6900	11518.50	54756.00	0.210 <sup>1</sup>

<sup>1</sup> P<sub>u</sub> / φP<sub>n</sub> controls

### Horizontal Design Data (Tension)

Section No.	Elevation ft	Size	L ft	L <sub>u</sub> ft	Kl/r	A in <sup>2</sup>	P <sub>u</sub> lb	φP <sub>n</sub> lb	Ratio $\frac{P_u}{\phi P_n}$
T5	120 - 100	L2 1/2x2 1/2x3/8	10.67	4.97	121.9	1.7300	2715.01	56052.00	0.048 <sup>1</sup>
T9	80 - 60	L3x3x3/8	14.67	6.97	140.0	2.1100	4044.18	68364.00	0.059 <sup>1</sup>
T13	20 - 0	L3 1/2x3 1/2x1/2	20.50	9.76	168.0	3.2500	5845.21	105300.00	0.056 <sup>1</sup>

<sup>1</sup> P<sub>u</sub> / φP<sub>n</sub> controls

### Secondary Horizontal Design Data (Tension)

Section No.	Elevation ft	Size	L ft	L <sub>u</sub> ft	Kl/r	A in <sup>2</sup>	P <sub>u</sub> lb	φP <sub>n</sub> lb	Ratio $\frac{P_u}{\phi P_n}$
T4	140 - 120	L2x2x1/4	8.74	8.14	165.7	0.9380	2075.23	30391.20	0.068 <sup>1</sup>
T10	60 - 50	L3x3x7/16	15.48	14.75	199.2	2.4300	4310.48	78732.00	0.055 <sup>1</sup>
T11	50 - 40	L3x3x7/16	16.48	15.75	212.4	2.4300	4634.54	78732.00	0.059 <sup>1</sup>
T12	40 - 20	L3x3x1/2	18.49	17.50	237.4	2.7500	5235.37	89100.00	0.059 <sup>1</sup>

<b>tnxTower</b>  <b>Ramaker &amp; Associates, Inc.</b> 855 Community Drive Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b> Transfer Station (CT33XC522)	<b>Page</b> 36 of 37
	<b>Project</b> 28737	<b>Date</b> 15:01:07 09/26/17
	<b>Client</b> Transcend Wireless / Sprint	<b>Designed by</b> TEM

<sup>1</sup>  $P_u / \phi P_n$  controls

### Top Girt Design Data (Tension)

Section No.	Elevation <i>ft</i>	Size	<i>L</i> <i>ft</i>	<i>L<sub>u</sub></i> <i>ft</i>	<i>Kl/r</i>	<i>A</i> <i>in<sup>2</sup></i>	<i>P<sub>u</sub></i> <i>lb</i>	$\phi P_n$ <i>lb</i>	Ratio $\frac{P_u}{\phi P_n}$
T1	185 - 180	L2x2x1/8	5.00	4.56	92.0	0.4844	499.07	15693.80	0.032 <sup>1</sup>
T2	180 - 160	L2x2x1/8	5.00	4.56	92.0	0.4844	406.67	15693.80	0.026 <sup>1</sup>
T3	160 - 140	L2x2x1/8	5.00	4.52	91.2	0.4844	401.92	15693.80	0.026 <sup>1</sup>

<sup>1</sup>  $P_u / \phi P_n$  controls

### Redundant Horizontal (1) Design Data (Tension)

Section No.	Elevation <i>ft</i>	Size	<i>L</i> <i>ft</i>	<i>L<sub>u</sub></i> <i>ft</i>	<i>Kl/r</i>	<i>A</i> <i>in<sup>2</sup></i>	<i>P<sub>u</sub></i> <i>lb</i>	$\phi P_n$ <i>lb</i>	Ratio $\frac{P_u}{\phi P_n}$
T5	120 - 100	L3x3x1/2	2.67	2.43	32.5	2.7500	6294.35	89100.00	0.071 <sup>1</sup>
T9	80 - 60	L3x3x1/2	3.67	3.43	45.9	2.7500	5840.87	89100.00	0.066 <sup>1</sup>
T13	20 - 0	L3x3x1/2	5.13	4.77	63.7	2.7500	8655.74	89100.00	0.097 <sup>1</sup>

<sup>1</sup>  $P_u / \phi P_n$  controls

### Redundant Diagonal (1) Design Data (Tension)

Section No.	Elevation <i>ft</i>	Size	<i>L</i> <i>ft</i>	<i>L<sub>u</sub></i> <i>ft</i>	<i>Kl/r</i>	<i>A</i> <i>in<sup>2</sup></i>	<i>P<sub>u</sub></i> <i>lb</i>	$\phi P_n$ <i>lb</i>	Ratio $\frac{P_u}{\phi P_n}$
T5	120 - 100	L3x3x1/2	3.07	2.80	37.4	2.7500	3458.35	89100.00	0.039 <sup>1</sup>
T9	80 - 60	L3x3x1/2	4.10	3.85	51.4	2.7500	2934.14	89100.00	0.033 <sup>1</sup>
T13	20 - 0	L3x3x1/2	5.82	5.41	72.3	2.7500	4142.50	89100.00	0.046 <sup>1</sup>

<sup>1</sup>  $P_u / \phi P_n$  controls

<b>tnxTower</b>  <b>Ramaker &amp; Associates, Inc.</b> 855 Community Drive Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	<b>Job</b> Transfer Station (CT33XC522)	<b>Page</b> 37 of 37
	<b>Project</b> 28737	<b>Date</b> 15:01:07 09/26/17
	<b>Client</b> Transcend Wireless / Sprint	<b>Designed by</b> TEM

### Section Capacity Table

Section No.	Elevation ft	Component Type	Size	Critical Element	P lb	$\phi P_{allow}$ lb	% Capacity	Pass Fail	
T1	185 - 180	Leg	P2x.154	2	-2848.82	31617.20	9.0	Pass	
		Diagonal	L2x2x1/8	9	-1559.68	8852.07	17.6	Pass	
		Top Girt	L2x2x1/8	5	-358.31	5769.26	6.2	Pass	
T2	180 - 160	Leg	P2.5x.203	15	-32295.60	57192.30	56.5	Pass	
		Diagonal	L2x2x1/8	19	-5144.57	8913.86	57.7	Pass	
		Top Girt	L2x2x1/8	17	-290.03	5769.26	5.0	Pass	
T3	160 - 140	Leg	P2.5x.375	43	-78888.10	95225.20	82.8	Pass	
		Diagonal	L2x2x1/8	54	-5272.29	7142.85	73.8	Pass	
		Top Girt	L2x2x1/8	47	-427.02	5876.09	7.3	Pass	
T4	140 - 120	Leg	P3.5x.318	73	-119664.00	158818.00	75.3	Pass	
		Diagonal	L2x2x3/16	81	-6053.98	7480.29	80.9	Pass	
		Secondary Horizontal	L2x2x1/4	82	-2075.23	8239.59	25.2	Pass	
T5	120 - 100	Leg	P5x.258	112	-156556.00	191890.00	81.6	Pass	
		Diagonal	L2 1/2x2 1/2x3/16	172	-9430.09	16761.30	56.3	Pass	
		Horizontal	L2 1/2x2 1/2x3/8	115	-2715.01	25482.20	10.7	Pass	
		Redund Horiz 1 Bracing	L3x3x1/2	152	-5643.10	60901.70	9.3	Pass	
T6	100 - 93.3333	Redund Diag 1 Bracing	L3x3x1/2	153	-3926.00	58054.10	6.8	Pass	
		Leg	P5x.375	232	-171098.00	239388.00	71.5	Pass	
		Diagonal	L2 1/2x2 1/2x3/16	239	-6795.90	8645.55	78.6	Pass	
T7	93.3333 - 86.6667	Leg	P5x.375	241	-183429.00	239388.00	76.6	Pass	
		Diagonal	L2 1/2x2 1/2x3/16	248	-6949.55	7904.00	87.9	Pass	
T8	86.6667 - 80	Leg	P5x.375	250	-195841.00	239388.00	81.8	Pass	
		Diagonal	2L2 1/2x2 1/2x3/16x3/8	257	-7580.82	32125.70	23.6	Pass	
T9	80 - 60	Leg	P5x.375	259	-233200.00	272663.00	85.5	Pass	
		Diagonal	L3x3x3/16	319	-9881.02	19110.00	51.7	Pass	
		Horizontal	L3x3x3/8	262	-4044.18	23504.60	17.2	Pass	
		Redund Horiz 1 Bracing	L3x3x1/2	299	-5235.94	55242.90	9.5	Pass	
		Redund Diag 1 Bracing	L3x3x1/2	300	-3445.90	52887.70	6.5	Pass	
T10	60 - 50	Leg	P5x.5	379	-248556.00	328070.00	75.8	Pass	
		Diagonal	L3x3x1/4	387	-9491.07	9604.97	98.8	Pass	
		Secondary Horizontal	L3x3x7/16	388	-4310.48	14352.50	30.0	Pass	
T11	50 - 40	Leg	P5x.5	391	-267242.00	328178.00	81.4	Pass	
		Diagonal	2L3x3x1/4x3/8	398	-10003.90	42238.70	23.7	Pass	
		Secondary Horizontal	L3x3x7/16	402	-4634.54	12586.20	36.8	Pass	
T12	40 - 20	Leg	P8x.322	403	-301887.00	365926.00	82.5	Pass	
		Diagonal	L3 1/2x3 1/2x1/4	411	-11453.10	12214.20	93.8	Pass	
T13	20 - 0	Secondary Horizontal	L3x3x1/2	412	-5235.37	11364.20	46.1	Pass	
		Leg	P8x.322	424	-337053.00	375086.00	89.9	Pass	
		Diagonal	L3 1/2x3 1/2x1/4	484	-13341.10	26464.10	50.4	Pass	
		Horizontal	L3 1/2x3 1/2x1/2	441	-5845.21	24993.60	23.4	Pass	
		Redund Horiz 1 Bracing	L3x3x1/2	464	-7354.63	47690.30	15.4	Pass	
		Redund Diag 1 Bracing	L3x3x1/2	465	-5133.24	44081.10	11.6	Pass	
							Summary		
							Leg (T13)	89.9	Pass
							Diagonal (T10)	98.8	Pass
							Horizontal (T13)	23.4	Pass
							Secondary Horizontal (T12)	46.1	Pass
							Top Girt (T3)	7.3	Pass
							Redund Horiz 1 Bracing (T13)	15.4	Pass
							Redund Diag 1 Bracing (T13)	11.6	Pass
							Bolt Checks	86.1	Pass
							<b>RATING =</b>	<b>98.8</b>	<b>Pass</b>





**Self Support Tower Anchor Rod Check - TIA-222-G**

Eta, $\eta$ :	0.55
Tension, Pu:	293.401 kip
Shear, Vu:	31.868 kip
Quantity:	6
Diameter:	1.5 in
Grade:	A572 Gr. 50 (1/4 to 4)

Fy:	50 ksi
Fu:	65 ksi


Anchor Force:	58.6 kip
Design Capacity:	73.3 kip
Stress Ratio:	79.9%

Length, lar:	in
Moment, Mu:	kip-in
Stress Ratio:	

Maximum Acceptable:	105%
---------------------	------

**Governing Stress Ratio:** **79.9%** **Pass**

**Anchor Rod Detail Types**



# SST Unit Base Foundation

Project #: 28737  
 Site Name: CT33XC522

TIA-222 Revision: G

Tower Centroid Offset?:   
 Block Foundation?:

Superstructure Analysis Reactions		
Global Moment, <b>M</b> :	5902.702	ft-kips
Global Axial, <b>P</b> :	68.998	kips
Global Shear, <b>V</b> :	56.818	kips
Leg Compression, <b>P<sub>comp</sub></b> :	347.561	kips
Leg Comp. Shear, <b>V<sub>u_comp</sub></b> :	37.351	kips
Leg Uplift, <b>P<sub>uplift</sub></b> :	293.401	kips
Leg Uplift. Shear, <b>V<sub>u_uplift</sub></b> :	31.868	kips
Tower Height, <b>H</b> :	185	ft
Base Face Width, <b>BW</b> :	21	ft
BP Dist. Above Fdn, <b>bp<sub>dist</sub></b> :	1	in

Foundation Analysis Checks				
	Capacity	Demand	Rating	Check
<i>Lateral (Sliding) (kips)</i>	241.39	56.82	23.5%	Pass
<i>Bearing Pressure (ksf)</i>	9.47	2.09	22.1%	Pass
<i>Overtuning (kip*ft)</i>	9476.85	6219.94	65.6%	Pass
<i>Pier Flexure (Comp.) (kip*ft)</i>	889.65	149.40	16.8%	Pass
<i>Pier Flexure (Tension) (kip*ft)</i>	193.19	127.47	66.0%	Pass
<i>Pier Compression (kip)</i>	4101.51	354.49	8.6%	Pass
<i>Pad Flexure (kip*ft)</i>	3236.15	1357.71	42.0%	Pass
<i>Pad Shear - 1-way (kips)</i>	393.77	288.21	73.2%	Pass
<i>Pad Shear - 2-way (ksi)</i>	0.16	0.16	97.3%	Pass

Pier Properties		
Pier Shape:	Circular	
Pier Diameter, <b>dpier</b> :	3.5	ft
Ext. Above Grade, <b>E</b> :	0.5	ft
Pier Rebar Size, <b>Sc</b> :	7	
Pier Rebar Quantity, <b>mc</b> :	12	
Pier Tie/Spiral Size, <b>St</b> :	4	
Pier Tie/Spiral Quantity, <b>mt</b> :	7	
Pier Reinforcement Type:	Tie	
Pier Clear Cover, <b>cc<sub>pier</sub></b> :	3	in

Soil Rating: 65.6%  
 Structural Rating: 97.3%

Pad Properties		
Depth, <b>D</b> :	5	ft
Pad Width, <b>W</b> :	30.5	ft
Pad Thickness, <b>T</b> :	1.5	ft
Pad Rebar Size (Bottom), <b>Sp</b> :	10	
Pad Rebar Quantity (Bottom), <b>mp</b> :	58	
Pad Clear Cover, <b>cc<sub>pad</sub></b> :	3	in

Material Properties		
Rebar Grade, <b>Fy</b> :	60000	psi
Concrete Compressive Strength, <b>F'c</b> :	3000	psi
Dry Concrete Density, <b>δc</b> :	150	pcf

Soil Properties		
Total Soil Unit Weight, <b>γ</b> :	125	pcf
Ultimate Net Bearing, <b>Qnet</b> :	12	ksf
Cohesion, <b>Cu</b> :		ksf
Friction Angle, <b>φ</b> :	32	degrees
SPT Blow Count, <b>N<sub>blows</sub></b> :		
Base Friction, <b>μ</b> :		
Neglected Depth, <b>N</b> :	3.33	ft
Foundation Bearing on Rock?	No	

<-- Toggle between Gross and Net



PROJECT: 2.5 EQUIPMENT DEPLOYMENT

SITE NAME: TRANSFER STATION

SITE CASCADE: CT33XC522-C

SITE ADDRESS: 237 GODFREY ROAD  
WESTON, CT 06883

SITE TYPE: 185'-0' SELF SUPPORT  
TOWER



6580 SPRINT PARKWAY  
OVERLAND PARK, KANSAS 66251




855 Community Drive, Sauk City, WI 53583  
 Phone: 608-643-4100 Fax: 608-643-7999  
 www.Ramaker.com

**Charles Cherundolo  
 Consulting, Inc.**

713 Clover Lane, Moscow, PA 18444  
 Phone: 570-840-5084 Fax: 570-842-5592

Certification & Seal:  
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



*James R. Skowronski* 10/06/2017  
 Signature: Date:

MARK	DATE	DESCRIPTION
ISSUE PHASE	FINAL	DATE ISSUED 10/06/17

PROJECT TITLE:  
**TRANSFER STATION  
 CT33XC522-C**

PROJECT INFORMATION:  
 237 GODFREY ROAD  
 WESTON, CT 06883  
 FAIRFIELD COUNTY

SHEET TITLE:  
**TITLE SHEET**

SCALE: NONE

PROJECT NUMBER: 28737  
 SHEET NUMBER: T-1

**SITE INFORMATION**

**PROPERTY OWNER:**  
 TOWN OF WESTON  
 56 NORFIELD ROAD  
 WESTON, CT 06883

**SITE ADDRESS:**  
 237 GODFREY ROAD  
 WESTON, CT 06883  
 FAIRFIELD COUNTY

**GEOGRAPHIC COORDINATES:**  
 LATITUDE: 41.244386 (41° 14' 39.789"N)  
 LONGITUDE: -73.363386 (73° 21' 48.189"W)

**ZONING JURISDICTION:**  
 TOWN OF WESTON

**ZONING DISTRICT:**  
 R-2A

**POWER COMPANY:**  
 CONNECTICUT LIGHT & POWER  
 PH.: (800) 286-2000


**AAV PROVIDER:**  
 AT&T  
 PH.: (210) 821-4105

**SPRINT CONSTRUCTION MANAGER:**  
 NAME: GARY WOOD  
 PHONE: (860) 940-9168  
 E-MAIL: gary.wood@sprint.com


**EQUIPMENT SUPPLIER:**  
 ALCATEL-LUCENT  
 600-700 MOUNTAIN AVENUE  
 MURRAY HILL, NJ 07974  
 PH.: (908) 508-8080

**PLANS PREPARED BY:**  
 RAMAKER & ASSOCIATES, INC.  
 CONTACT: KEITH BOHNSACK, PROJECT MANAGER  
 PH.: (608) 643-4100  
 EMAIL: kbohnsack@ramaker.com

**AREA MAP**



**LOCATION MAP**



**PROJECT DESCRIPTION**

- INSTALL NEW 2.5 EQUIPMENT IN EXISTING BTS CABINET  
 \*(1) RECTIFIER SHELF AND (3) RECTIFIERS  
 \*(1) BASE BAND UNIT
- INSTALL NEW BATTERY STRING IN EXISTING BATTERY CABINET
- INSTALL (3) PANEL ANTENNAS
- INSTALL (3) RRH'S ON TOWER
- INSTALL (1) HYBRID CABLE AND (3) SECTOR JUMPERS
- INSTALL (27) ANTENNA / RRH JUMPERS

**APPLICABLE CODES**

\* ALL WORK SHALL BE PERFORMED AND MATERIALS INSTALLED IN ACCORDANCE WITH THE FOLLOWING CODES AS ADOPTED BY THE LOCAL GOVERNING AUTHORITIES. NOTHING IN THESE PLANS IS TO BE CONSTRUED TO PERMIT WORK NOT CONFORMING TO THESE CODES.

1. 2016 CT STATE BUILDING CODE
2. 2016 CT FIRE SAFETY CODE
3. 2014 NATIONAL ELECTRIC CODE W/ CT AMENDMENTS
4. 2012 IECC W/ CT AMENDMENTS



**SECTION 01 100 - SCOPE OF WORK**

**THE WORK:**  
THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE CONSTRUCTION DRAWINGS AND ASSOCIATED OUTLINE SPECIFICATIONS AND THE SITE SPECIFIC WORK ORDER, DESCRIBE THE WORK TO BE PERFORMED BY THIS CONSTRUCTION CONTRACTOR (SUPPLIER).

**RELATED DOCUMENTS:**  
A. THE REQUIREMENTS OF EACH SECTION OF THIS SPECIFICATION APPLY TO ALL SECTIONS, INDIVIDUALLY AND COLLECTIVELY.  
B. RELATED DOCUMENTS: THE CONTRACTOR SHALL COMPLY WITH THE MOST CURRENT VERSION OF THE FOLLOWING SUPPLEMENTAL REQUIREMENTS FOR INSTALLATION AND TESTING.  
1. EN-201 2-001 : (FIBER OPTIC, DC CABLE, AND DC CIRCUIT BREAKER TAGGING STANDARDS)  
2. TS-0200 - (TRANSMISSION ANTENNA LINE ACCEPTANCE STANDARDS)  
3. EL-0568: (FIBER TESTING POLICY)  
4. NP-312-201 : (EXTERIOR GROUNDING SYSTEM TESTING)  
5. NP-760-500: ETHERNET, MICROWAVE, TESTING AND ACCEPTANCE

**PRECEDENCE:**  
SHOULD CONFLICTS OCCUR BETWEEN THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES AND THE CONSTRUCTION DRAWINGS, INFORMATION ON THE CONSTRUCTION DRAWINGS SHALL TAKE PRECEDENCE. NOTIFY SPRINT CONSTRUCTION MANAGER IF THIS OCCURS.

**NATIONALLY RECOGNIZED CODES AND STANDARDS:**  
THE WORK SHALL COMPLY WITH APPLICABLE NATIONAL AND LOCAL CODES AND STANDARDS, LATEST EDITION, AND PORTIONS THEREOF, INCLUDED BUT NOT LIMITED TO THE FOLLOWING:  
A. GR-63-CORE NEBS REQUIREMENTS: PHYSICAL PROTECTION  
B. GR-78-CORE GENERIC REQUIREMENTS FOR THE PHYSICAL DESIGN AND MANUFACTURE OF TELECOMMUNICATIONS EQUIPMENT.  
C. GR-1089 CORE, ELECTROMAGNETIC COMPATIBILITY AND ELECTRICAL SAFETY -GENERIC CRITERIA FOR NETWORK TELECOMMUNICATIONS EQUIPMENT.  
D. NATIONAL FIRE PROTECTION ASSOCIATION CODES AND STANDARDS (NFPA) INCLUDING NFPA 70 (NATIONAL ELECTRICAL CODE - "NEC") AND NFPA 101 (LIFE SAFETY CODE).  
E. AMERICAN SOCIETY FOR TESTING OF MATERIALS (ASTM)  
F. INSTITUTE OF ELECTRONIC AND ELECTRICAL ENGINEERS (IEEE)  
G. AMERICAN CONCRETE INSTITUTE (ACI)  
H. AMERICAN WIRE PRODUCERS ASSOCIATION (AWPA)  
I. CONCRETE REINFORCING STEEL INSTITUTE (CRSI)  
J. AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)  
K. PORTLAND CEMENT ASSOCIATION (PCA)  
L. NATIONAL CONCRETE MASONRY ASSOCIATION (NCMA)  
M. BRICK INDUSTRY ASSOCIATION (BIA)  
N. AMERICAN WELDING SOCIETY (AWS)  
O. NATIONAL ROOFING CONTRACTORS ASSOCIATION (NRCA)  
P. SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)  
Q. DOOR AND HARDWARE INSTITUTE (DHI)  
R. OCCUPATIONAL SAFETY AND HEALTH ACT (OSHA)  
S. APPLICABLE BUILDING CODES INCLUDING UNIFORM BUILDING CODE, SOUTHERN BUILDING CODE, BOCA, AND THE INTERNATIONAL BUILDING CODE.

**DEFINITIONS:**  
A. WORK: THE SUM OF TASKS AND RESPONSIBILITIES IDENTIFIED IN THE CONTRACT DOCUMENTS.  
B. COMPANY: "SPRINT"; SPRINT NEXTEL CORPORATION AND ITS OPERATING ENTITIES.  
C. ENGINEER: SYNONYMOUS WITH ARCHITECT & ENGINEER AND "A&E". THE DESIGN PROFESSIONAL HAVING PROFESSIONAL RESPONSIBILITY FOR DESIGN OF THE PROJECT.  
D. CONTRACTOR: CONSTRUCTION CONTRACTOR, SUPPLIER, CONSTRUCTION VENDOR, INDIVIDUAL OR ENTITY WHO AFTER EXECUTION OF A CONTRACT IS BOUND TO ACCOMPLISH THE WORK.  
E. THIRD PARTY VENDOR OR AGENCY: A VENDOR OR AGENCY ENGAGED SEPARATELY BY THE COMPANY, A&E, OR CONTRACTOR TO PROVIDE MATERIALS OR TO ACCOMPLISH SPECIFIC TASKS RELATED TO BUT NOT INCLUDED IN THE WORK.  
F. CONSTRUCTION MANAGER - ALL PROJECTS RELATED COMMUNICATION TO FLOW THROUGH SPRINT REPRESENTATIVE IN CHARGE OF PROJECT.

**SITE FAMILIARITY:**  
CONTRACTOR SHALL BE RESPONSIBLE FOR FAMILIARIZING HIMSELF WITH ALL CONTRACT DOCUMENTS, FIELD CONDITIONS AND DIMENSIONS PRIOR TO PROCEEDING WITH CONSTRUCTION. ANY DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE SPRINT CONSTRUCTION MANAGER PRIOR TO THE COMMENCEMENT OF WORK. NO COMPENSATION WILL BE AWARDED BASED ON CLAIM OF LACK OF KNOWLEDGE OR FIELD CONDITIONS.

**POINT OF CONTACT:**  
COMMUNICATION BETWEEN SPRINT AND THE CONTRACTOR SHALL FLOW THROUGH THE SINGLE SPRINT CONSTRUCTION MANAGER APPOINTED TO MANAGE THE PROJECT FOR SPRINT.

**ON-SITE SUPERVISION:**  
THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK AND SHALL BE RESPONSIBLE FOR CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES IN ACCORDANCE WITH THE CONTRACT DOCUMENTS. THE CONTRACTOR SHALL EMPLOY A COMPETENT SUPERINTENDENT WHO SHALL BE IN ATTENDANCE AT THE SITE AT ALL TIMES DURING PERFORMANCE OF THE WORK.

**DRAWINGS REQUIRED AT JOBSITE:**  
THE CONSTRUCTION CONTRACTOR SHALL MAINTAIN A FULL SET OF THE CONSTRUCTION DRAWINGS FOR WIRELESS SITES AND THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES AT THE JOBSITE FROM MOBILIZATION THROUGH CONSTRUCTION COMPLETION.  
A. THE JOBSITE DRAWINGS SHALL BE CLEARLY MARKED DAILY IN RED PENCIL WITH ANY CHANGES IN CONSTRUCTION OVER WHAT IS DEPICTED IN THE DOCUMENTS. AT CONSTRUCTION COMPLETION, THIS JOBSITE MARKUP SET SHALL BE DELIVERED TO THE COMPANY OR COMPANY'S DESIGNATED REPRESENTATIVE TO BE FORWARDED TO THE COMPANY'S A&E VENDOR FOR PRODUCTION OF "AS-BUILT" DRAWINGS.  
B. DIMENSIONS SHOWN ARE TO FINISH SURFACES UNLESS NOTED OTHERWISE. SPACING BETWEEN EQUIPMENT IS THE REQUIRED CLEARANCE. SHOULD THERE BE ANY QUESTIONS REGARDING THE CONTRACT DOCUMENTS, EXISTING CONDITIONS AND/OR DESIGN INTENT, THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING A CLARIFICATION FROM THE SPRINT CONSTRUCTION MANAGER PRIOR TO PROCEEDING WITH THE WORK.

**USE OF JOB SITE:**  
THE CONTRACTOR SHALL CONFINE ALL CONSTRUCTION AND RELATED OPERATIONS INCLUDING STAGING AND STORAGE OF MATERIALS AND EQUIPMENT, PARKING, TEMPORARY FACILITIES, AND WASTE STORAGE TO THE LEASE PARCEL UNLESS OTHERWISE PERMITTED BY THE CONTRACT DOCUMENTS.

**UTILITY SERVICES:**  
WHERE NECESSARY TO CUT EXISTING PIPES, ELECTRICAL WIRES, CONDUITS, CABLES, ETC., OF UTILITY SERVICES, OR OF FIRE PROTECTION OR COMMUNICATIONS SYSTEMS, THEY SHALL BE CUT AND CAPPED AT SUITABLE PLACES OR WHERE SHOWN. ALL SUCH ACTIONS SHALL BE COORDINATED WITH THE UTILITY COMPANY INVOLVED:

**PERMITS/FEEES:**  
WHEN REQUIRED THAT A PERMIT OR CONNECTION FEE BE PAID TO A PUBLIC UTILITY PROVIDER FOR NEW SERVICE TO THE CONSTRUCTION PROJECT, PAYMENT OF SUCH FEE SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.

**CONTRACTOR:**  
CONTRACTOR SHALL TAKE ALL MEASURES AND PROVIDE ALL MATERIAL NECESSARY FOR PROTECTING EXISTING EQUIPMENT AND PROPERTY.

**USE OF ELECTRONIC PROJECT MANAGEMENT SYSTEMS:**  
CONTRACTOR WILL UTILIZE ITS BEST EFFORTS TO WORK WITH SPRINT ELECTRONIC PROJECT MANAGEMENT SYSTEMS. CONTRACTOR UNDERSTANDS THAT SUFFICIENT INTERNET ACCESS, EQUIVALENT TO "BROADBAND" OR BETTER, IS REQUIRED TO TIMELY AND EFFECTIVELY UTILIZE SPRINT DATA AND DOCUMENT MANAGEMENT SYSTEMS AND AGREES TO MAINTAIN APPROPRIATE CONNECTIONS FOR CONTRACTORS STAFF AND OFFICES THAT ARE COMPATIBLE WITH SPRINT DATA AND DOCUMENT MANAGEMENT SYSTEMS

**TEMPORARY UTILITIES AND FACILITIES:**  
THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL TEMPORARY UTILITIES AND FACILITIES NECESSARY EXCEPT AS OTHERWISE INDICATED IN THE CONSTRUCTION DOCUMENTS. TEMPORARY UTILITIES AND FACILITIES INCLUDE POTABLE WATER, HEAT, HVAC, ELECTRICITY, SANITARY FACILITIES, WASTE DISPOSAL FACILITIES, AND TELEPHONE/COMMUNICATION SERVICES. PROVIDE TEMPORARY UTILITIES AND FACILITIES IN ACCORDANCE WITH OSHA AND THE AUTHORITY HAVING JURISDICTION. CONTRACTOR MAY UTILIZE THE COMPANY ELECTRICAL SERVICE IN THE COMPLETION OF THE WORK WHEN IT BECOMES AVAILABLE. USE OF THE LESSOR'S OR SITE OWNER'S UTILITIES OR FACILITIES IS EXPRESSLY FORBIDDEN EXCEPT AS OTHERWISE ALLOWED IN THE CONTRACT DOCUMENTS.

**ACCESS TO WORK:**  
THE CONTRACTOR SHALL PROVIDE ACCESS TO THE JOB SITE FOR AUTHORIZED COMPANY PERSONNEL AND AUTHORIZED REPRESENTATIVES OF THE ARCHITECT/ENGINEER DURING ALL PHASES OF THE WORK.

**DIMENSIONS:**  
VERIFY DIMENSIONS INDICATED ON DRAWINGS WITH FIELD DIMENSIONS BEFORE FABRICATION OR ORDERING OF MATERIALS. DO NOT SCALE DRAWINGS.

**EXISTING CONDITIONS:**  
NOTIFY THE SPRINT CONSTRUCTION MANAGER OF EXISTING CONDITIONS DIFFERING FROM THOSE INDICATED ON THE DRAWINGS. DO NOT REMOVE OR ALTER STRUCTURAL COMPONENTS WITHOUT PRIOR WRITTEN APPROVAL FROM THE ARCHITECT AND ENGINEER.

**SECTION 01 200 - COMPANY FURNISHED MATERIAL AND EQUIPMENT**

**FURNISHED MATERIALS:**  
COMPANY FURNISHED MATERIALS AND EQUIPMENT TO BE INSTALLED BY THE CONTRACTOR (OFIC) IS IDENTIFIED ON THE RF DATA SHEET IN THE CONSTRUCTION DOCUMENTS.

**RECEIPT OF MATERIAL AND EQUIPMENT:**  
A. THE CONTRACTOR IS RESPONSIBLE FOR SPRINT PROVIDED MATERIAL AND EQUIPMENT AND UPON RECEIPT SHALL:  
1. ACCEPT DELIVERIES AS SHIPPED AND TAKE RECEIPT.  
2. VERIFY COMPLETENESS AND CONDITION OF ALL DELIVERIES.  
3. TAKE RESPONSIBILITY FOR EQUIPMENT AND PROVIDE INSURANCE PROTECTION AS REQUIRED IN AGREEMENT.  
B. RECORD ANY DEFECTS OR DAMAGES AND WITHIN TWENTY-FOUR HOURS AFTER RECEIPT, REPORT TO SPRINT OR ITS DESIGNATED PROJECT REPRESENTATIVE OF SUCH.  
C. PROVIDE SECURE AND NECESSARY WEATHER PROTECTED WAREHOUSING.  
D. COORDINATE SAFE AND SECURE TRANSPORTATION OF MATERIAL AND EQUIPMENT, DELIVERING AND OFF-LOADING FROM CONTRACTORS WAREHOUSE TO SITE.

**DELIVERABLES:**  
A. COMPLETE SHIPPING AND RECEIPT DOCUMENTATION IN ACCORDANCE WITH COMPANY PRACTICE.  
B. IF APPLICABLE, COMPLETE LOST/STOLEN/DAMAGED DOCUMENTATION REPORT AS NECESSARY IN ACCORDANCE WITH COMPANY PRACTICE, AND AS DIRECTED BY COMPANY.

**SECTION 01 300 - CELL SITE CONSTRUCTION**

**NOTICE TO PROCEED:**  
A. NO WORK SHALL COMMENCE PRIOR TO COMPANY'S ISSUANCE OF THE WORK ORDER.  
B. UPON RECEIVING NOTICE TO PROCEED, CONTRACTOR SHALL FULLY PERFORM ALL WORK NECESSARY TO PROVIDE SPRINT WITH AN OPERATIONAL WIRELESS FACILITY.

**GENERAL REQUIREMENTS FOR CONSTRUCTION:**  
A. CONTRACTOR SHALL KEEP THE SITE FREE FROM ACCUMULATING WASTE MATERIAL, DEBRIS, AND TRASH. AT THE COMPLETION OF THE WORK, CONTRACTOR SHALL REMOVE FROM THE SITE ALL REMAINING RUBBISH, IMPLEMENTS, TEMPORARY FACILITIES, AND SURPLUS MATERIALS.  
B. EQUIPMENT ROOMS SHALL AT ALL TIMES BE MAINTAINED "BROOM CLEAN" AND CLEAR OF DEBRIS.  
C. CONTRACTOR SHALL TAKE ALL REASONABLE PRECAUTIONS TO DISCOVER AND LOCATE ANY HAZARDOUS CONDITION.  
1. IN THE EVENT CONTRACTOR ENCOUNTERS ANY HAZARDOUS CONDITION WHICH HAS NOT BEEN ABATED OR OTHERWISE MITIGATED, CONTRACTOR AND ALL OTHER PERSONS SHALL IMMEDIATELY STOP WORK IN THE AFFECTED AREA AND NOTIFY COMPANY IN WRITING. THE WORK IN THE AFFECTED AREA SHALL NOT BE RESUMED EXCEPT BY WRITTEN NOTIFICATION BY COMPANY.  
2. CONTRACTOR AGREES TO USE CARE WHILE ON THE SITE AND SHALL NOT TAKE ANY ACTION THAT WILL OR MAY RESULT IN OR CAUSE THE HAZARDOUS CONDITION TO BE FURTHER RELEASED IN THE ENVIRONMENT, OR TO FURTHER EXPOSE INDIVIDUALS TO THE HAZARD.  
D. CONTRACTOR'S ACTIVITIES SHALL BE RESTRICTED TO THE PROJECT LIMITS. SHOULD AREAS OUTSIDE THE PROJECT LIMITS BE AFFECTED BY CONTRACTOR'S ACTIVITIES, CONTRACTOR SHALL IMMEDIATELY RETURN THEM TO ORIGINAL CONDITION

**FUNCTIONAL REQUIREMENTS:**  
A. THE ACTIVITIES DESCRIBED IN THIS PARAGRAPH REPRESENT MINIMUM ACTIONS AND PROCESSES REQUIRED TO SUCCESSFULLY COMPLETE THE WORK. CONTRACTOR SHALL TAKE ALL ACTIONS AS NECESSARY TO SUCCESSFULLY COMPLETE THE CONSTRUCTION OF A FULLY FUNCTIONING WIRELESS FACILITY AT THE SITE IN ACCORDANCE WITH COMPANY PROCESSES.  
B. SUBMIT SPECIFIC DOCUMENTATION AS INDICATED HEREIN, AND OBTAIN REQUIRED APPROVALS WHILE THE WORK IS BEING PERFORMED.  
C. MANAGE AND CONDUCT ALL FIELD CONSTRUCTION SERVICE RELATED ACTIVITIES  
D. PROVIDE CONSTRUCTION ACTIVITIES TO THE EXTENT REQUIRED BY THE CONTRACT DOCUMENTS, INCLUDING BUT NOT LIMITED TO THE FOLLOWING:  
1. PERFORM ANY REQUIRED SITE ENVIRONMENTAL MITIGATION.  
2. PREPARE GROUND SITES; PROVIDE DE-GRUBBING; AND ROUGH AND FINAL GRADING, AND COMPOUND SURFACE TREATMENTS.  
3. MANAGE AND CONDUCT ALL ACTIVITIES FOR INSTALLATION OF UTILITIES INCLUDING ELECTRICAL AND BACKHAUL (FIBER, COPPER, OR MICROWAVE).  
4. INSTALL UNDERGROUND FACILITIES INCLUDING UNDERGROUND POWER AND COMMUNICATIONS CONDUITS, AND UNDERGROUND GROUNDING SYSTEM.  
5. INSTALL ABOVE GROUND GROUNDING SYSTEMS, CONDUIT AND BOXES.  
6. PROVIDE NEW HVAC INSTALLATIONS AND MODIFICATIONS.  
7. INSTALL "H-FRAMES", CABINETS AND PADS AND PLATFORMS AS INDICATED.  
8. INSTALL ROADS, ACCESS WAYS, CURBS AND DRAINS AS INDICATED.  
9. ACCOMPLISH REQUIRED MODIFICATION OF EXISTING FACILITIES.

- 10. PROVIDE ANTENNA SUPPORT STRUCTURE FOUNDATIONS.
- 11. PROVIDE SLABS AND EQUIPMENT PLATFORMS.
- 12. INSTALL COMPOUND FENCING, SIGHT SHIELDING, LANDSCAPING AND ACCESS BARRIERS.
- 13. PERFORM INSPECTION AND MATERIAL TESTING AS REQUIRED HEREINAFTER.
- 14. CONDUCT SITE RESISTANCE TO EARTH TESTING AS REQUIRED HEREINAFTER.
- 15. INSTALL FIXED GENERATOR SETS AND OTHER STANDBY POWER SOLUTIONS.
- 16. INSTALL TOWERS, ANTENNA SUPPORT STRUCTURES AND PLATFORMS ON EXISTING TOWERS AS REQUIRED.
- 17. INSTALL CELL SITE RADIOS, MICROWAVE, GPS, COAXIAL MAINLINE, ANTENNAS, CROSS BAND COUPLERS, TOWER TOP AMPLIFIERS, SIGHT SHIELDING, LANDSCAPING AND ACCESS BARRIERS.
- 18. CONDUCT ALL REQUIRED TESTS AND INSPECTIONS
- 19. PERFORM, DOCUMENT, AND CLOSE OUT ALL JURISDICTIONAL PERMITTING REQUIREMENTS AND ANY CONSTRUCTION CONTROL DOCUMENTS THAT MAY BE REQUIRED BY GOVERNMENT AGENCIES AND LANDLORDS.
- 20. PERFORM ALL ADDITIONAL WORK AS IDENTIFIED IN SCOPE OF SERVICES ATTACHED TO THE SUPPLIER AGREEMENT FOR THIS PROJECT. THIS WORK MAY INCLUDE COMMISSIONING, INTEGRATION, SPECIAL WAREHOUSING, REVERSE LOGISTICS ACTIVITIES, ETC. PERFORM COMMISSIONING AND INTEGRATION ACTIVITIES PER APPLICABLE MOPS.

**DELIVERABLES:**  
A. THE CONTRACTOR SHALL PROVIDE ALL REQUIRED TEST REPORTS AND DOCUMENTATION INCLUDED BUT NOT LIMITED TO THE FOLLOWING:  
1. PRODUCT SPECIFICATIONS FOR MATERIALS OR SPECIAL CONSTRUCTION IF REQUESTED BY SPRINT  
2. ACTUALIZE ALL CONSTRUCTION RELATED MILESTONES IN SITERRA AND COMPLETE ALL ON-LINE FORMS AND COMPLETE DOCUMENT UP-LOADS. UPLDAD ALL REQUIRED CLOSEOUT DOCUMENTS AND FINAL SITE PHOTOS  
3. SCANABLE BARCODE PHOTOGRAPHS OF TOWER TOP AND INACCESSIBLE SERIALIZED EQUIPMENT LEFT ON SITE INSIDE BASE OF MAIN RF CABINET IN A PROTECTIVE POUCH.  
4. ALL REQUIRED TEST REPORTS.  
5. REQUIRED CLOSEOUT DOCUMENTATION INCLUDING BUT NOT LIMITED TO:  
a. ALL JURISDICTIONAL PERMITTING AND OCCUPANCY INFORMATION  
b. PDF SCAN OF REDLINES PRODUCED IN THE FIELD  
c. ELECTRONIC AS-BUILT DRAWINGS IN AUTOCAD AND PDF FORMATS  
d. LIEN WAIVERS  
e. FINAL PAYMENT APPLICATION  
f. REQUIRED FINAL CONSTRUCTION PHOTOS  
g. CONSTRUCTION AND COMMISSIONING CHECKLIST COMPLETE WITH NO DEFICIENT ITEMS  
h. LISTS OF SUBCONTRACTORS  
B. PROVIDE ADDITIONAL DOCUMENTATION INCLUDING, BUT NOT LIMITED TO, THE FOLLOWING. DOCUMENTATION SHALL BE FORWARDED IN ORIGINAL FORMAT AND/OR UPLADED INTO SMS.  
1. ALL CORRESPONDENCE AND PRELIMINARY CONSTRUCTION REPORTS.  
2. PROJECT PROGRESS REPORTS.  
3. PRE-CONSTRUCTION MEETING NOTES.

**SECTION 01 400 - TESTS, INSPECTIONS, SUBMITTALS, AND PROJECT CLOSEOUT**

**TESTS AND INSPECTIONS:**  
A. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CONSTRUCTION TESTS, INSPECTIONS AND PROJECT DOCUMENTATION.  
B. CONTRACTOR SHALL ACCOMPLISH TESTING INCLUDING BUT NOT LIMITED TO THE FOLLOWING:  
1. COAX SWEEPS AND FIBER TESTS PER TS-0200 (CURRENT VERSION) ANTENNA LINE ACCEPTANCE STANDARDS  
2. POST CONSTRUCTION HEIGHT VERIFICATION, AZIMUTH AND DOWNTILT USING ELECTRONIC COMMERCIAL MADE-FOR-THE-PURPOSE ANTENNA ALIGNMENT TOOL.  
3. CONCRETE BREAK TESTS  
4. SITE RESISTANCE TO EARTH TEST  
5. STRUCTURAL BACKFILL COMPACTION TESTS  
6. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN SITE INSPECTION ACTIVITIES AND/OR AS A RESULT OF TESTING.  
7. ADDITIONAL TESTING AS REQUIRED ELSEWHERE IN THIS SPECIFICATION.

**SUBMITTALS:**  
A. THE WORK IN ALL ASPECTS SHALL COMPLY WITH THE CONSTRUCTION DRAWINGS AND THESE SPECIFICATIONS.  
B. UPLOAD THE FOLLOWING TO SITERRA AS APPLICABLE INCLUDING BUT NOT LIMITED TO THE FOLLOWING:  
1. CONCRETE MIX-DESIGNS FOR TOWER FOUNDATIONS, ANCHORS PIERS, AND CONCRETE PAVING.  
2. CONCRETE BREAK TESTS AS SPECIFIED HEREIN.  
3. CHEMICAL GROUNDING SYSTEM  
4. REINFORCEMENT CERTIFICATIONS  
5. STRUCTURAL BACKFILL TEST RESULTS  
6. SWEEP AND FIBER TESTS  
7. ANTENNA AZIMUTH AND DOWN-TILT VERIFICATION  
8. POST CONSTRUCTION HEIGHT VERIFICATION  
9. ADDITIONAL SUBMITTALS MAY BE REQUIRED FOR SPECIAL CONSTRUCTION OR MINOR MATERIALS  
C. ALTERNATES: AT THE COMPANY'S REQUEST, ANY ALTERNATIVES TO THE MATERIALS OR METHODS SPECIFIED SHALL BE SUBMITTED TO SPRINT'S CONSTRUCTION MANAGER FOR APPROVAL PRIOR TO BEING SHIPPED TO SITE. SPRINT WILL REVIEW AND APPROVE ONLY THOSE REQUESTS MADE IN WRITING. NO VERBAL APPROVALS WILL BE CONSIDERED. SUBMITTAL FOR APPROVAL SHALL INCLUDE A STATEMENT OF COST REDUCTION PROPOSED FOR USE OF ALTERNATE PRODUCT.

**TESTING BY THIRD PARTY AGENCY:**  
A. EMPLOY AN AGENCY OF ENGINEERS AND SCIENTISTS WHO IS REGULARLY ENGAGED IN FIELD AND LABORATORY TESTING AND ANALYSIS. AGENCY SHALL HAVE BEEN IN BUSINESS A MINIMUM OF FIVE YEARS, AND BE LICENSED AS PROFESSIONAL ENGINEERS IN THE STATE WHERE THE PROJECT IS LOCATED. AGENCY IS SUBJECT TO APPROVAL BY COMPANY.  
1. AGENCY MUST HAVE A THOROUGH UNDERSTANDING OF LOCAL AVAILABLE MATERIALS, INCLUDING THE SOIL, ROCK, AND GROUNDWATER CONDITIONS.  
2. AGENCY IS TO BE FAMILIAR WITH THE APPLICABLE REQUIREMENTS FOR THE TESTS TO BE DONE, EQUIPMENT TO BE USED, AND ASSOCIATED HEALTH AND SAFETY ISSUES.  
3. EXPERIENCE IN SOILS, CONCRETE, MASONRY, AGGREGATE, AND ASPHALT TESTING USING ASTM, AASJTO, AND OTHER METHODS IS NEEDED.  
B. REQUIRED THIRD PARTY TESTS:  
1. SITE RESISTANCE TO EARTH TEST PER NP-312-201  
2. CONCRETE CYLINDER BREAK TESTS FOR TOWER PIER AND ANCHORS PER NATIONALLY RECOGNIZED STANDARDS  
3. STRUCTURAL SOILS COMPACTION TESTS PER NATIONALLY RECOGNIZED STANDARDS  
4. REBAR PLACEMENT VERIFICATION WITH REPORT  
5. TESTING TENSION STUDY FOR ROCK ANCHORS  
6. ALL THIRD PARTY TESTS AS REQUIRED BY LOCAL JURISDICTION  
C. REQUIRED TESTS BY CONTRACTOR  
1. COAX SWEEP TESTS PER SPRINT STANDARD TS-0200  
2. FIBER TESTS PER SPRINT STANDARD EL-0568  
3. MICROWAVE LINK TESTS PER NP-760-500  
4. ANTENNA AZIMUTHS AND DOWN TILT USING ELECTRONIC ALIGNMENT TOOL PER ANTENNA INSTALLATION SPECIFICATION HEREIN.



6580 SPRINT PARKWAY  
OVERLAND PARK, KANSAS 66251



855 Community Drive, Sauk City, WI 53583  
Phone: 608-643-4100 Fax: 608-643-7999  
www.Ramaker.com

**Charles Cherundolo Consulting, Inc.**

713 Clover Lane, Moscow, PA 18444  
Phone: 570-840-5084 Fax: 570-842-5592

**Certification & Seal:**  
I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 10/06/2017

MARK	DATE	DESCRIPTION
ISSUE PHASE	FINAL	DATE ISSUED 10/06/17

PROJECT TITLE:  
**TRANSFER STATION CT33XC522-C**

PROJECT INFORMATION:  
237 GODFREY ROAD  
WESTON, CT 06883  
FAIRFIELD COUNTY

SHEET TITLE:  
**SPRINT SPECIFICATIONS**

SCALE: NONE

PROJECT NUMBER	28737
SHEET NUMBER	SP-1

5. POST CONSTRUCTION HEIGHT VERIFICATION AS REQUIRED HERewith IN THE TOWER INSTALLATION SPECIFICATIONS.
  6. ASPHALT ROADWAY COMPACTED THICKNESS, SURFACE SMOOTHNESS, AND COMPACTED DENSITY TESTING AS SPECIFIED HERewith IN THE ASPHALT PAVING SPECIFICATIONS.
  7. FIELD QUALITY CONTROL TESTING AS SPECIFIED HERewith IN THE CONCRETE PAVING SPECIFICATIONS.
  8. TESTING REQUIRED HERewith UNDER SPECIFICATIONS FOR AGGREGATE BASE FOR ROADWAYS
  9. ALL OTHER TESTS REQUIRED BY LOCAL JURISDICTION
- D. INSPECTIONS BY COMPANY: THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN INSPECTION ACTIVITIES, FINAL ACCEPTANCE / PUNCH WALK REVIEW, AND/OR AS A RESULT OF TESTING
- E. SPRINT RESERVES THE RIGHT TO INSPECT THE CONSTRUCTION SITE AT ANY TIME VIA SITE WALKS AND/OR PHOTO REVIEWS. CONTRACTOR SHALL GIVE SPRINT 24 HOURS NOTICE PRIOR TO THE COMMENCEMENT OF THE FOLLOWING CONSTRUCTION ACTIVITIES AND PHOTOGRAPHS OF THE IN-PROGRESS WORK.
1. GROUNDING SYSTEM AND BURIED UTILITIES INSTALLATION PRIOR TO EARTH CONCEALMENT DOCUMENTED WITH DIGITAL PHOTOGRAPHS BY CONTRACTOR, APPROVED BY A&E OR SPRINT REPRESENTATIVE.
  2. FORMING FOR CONCRETE AND REBAR PLACEMENT PRIOR TO POUR DOCUMENTED WITH DIGITAL PHOTOGRAPHS BY CONTRACTOR, APPROVED BY A&E OR SPRINT REPRESENTATIVE.
  3. COMPACTION OF BACKFILL MATERIALS, AGGREGATE BASE FOR ROADS, PADS, AND ANCHORS, ASPHALT PAVING, AND SHAFT BACKFILL FOR CONCRETE AND WOOD POLES, BY INDEPENDENT THIRD PARTY AGENCY.
  4. PRE AND POST CONSTRUCTION ROOFTOP AND STRUCTURAL INSPECTIONS ON EXISTING FACILITIES. PRIOR TO CONSTRUCTION ACTIVITIES AND AFTER CONSTRUCTION IS COMPLETE, PROVIDE PHOTOGRAPHIC DOCUMENTATION OF ROOF, FLASHINGS, AND PARAPETS, BOTH BEFORE AND AFTER CONSTRUCTION IS COMPLETE.
  5. TOWER ERECTION SECTION STACKING AND PLATFORM ATTACHMENT DOCUMENTED BY DIGITAL PHOTOGRAPHS BY THIRD PARTY AGENCY.
  6. TOWER TOP AND INACCESSIBLE EQUIPMENT (RRUS, ANTENNAS, AND CABLING): PROVIDE PHOTOS OF THE BACKS OF ALL ANTENNAS, RRUS, COMBINERS, FILTERS, FIBER AND DC CABLING, CABLE COLOR CODING, EQUIPMENT GROUNDING AND CONNECTOR WATER PROOFING INCLUDING NAME PLATE AND SERIAL NUMBER FOR ALL SERIALIZED EQUIPMENT.

**PROJECT CLOSEOUT:**

A. FINAL ACCEPTANCE PUNCH WALK AND INSPECTION: AS IDENTIFIED IN THE SCOPE OF SERVICES, SPRINT WILL CONDUCT A FINAL PUNCH WALK OR FINAL DESK TOP PHOTO REVIEW (SITE MODIFICATIONS). PUNCH WALKS MUST BE SCHEDULED IN ADVANCE AS REQUIRED. AT THE PUNCH WALK / REVIEW, SPRINT MAY IDENTIFY CRITICAL DEFICIENCIES WHICH MUST BE CORRECTED PRIOR TO PUTTING SITE ON AIR. MINOR DEFICIENCIES MUST BE CORRECTED WITHIN 30 DAYS EXCEPT AS OTHERWISE REQUIRED. VERIFICATIONS OF CORRECTIONS MAY BE MADE BY COMPANY DURING A REPEAT SITE WALK OR DESK TOP PHOTO REVIEW AT COMPANY'S SOLE DISCRETION.

B. CLOSEOUT DOCUMENTATION: ALL CLOSEOUT DOCUMENTATION AND PHOTOGRAPHS SHALL BE UPLOADED PRIOR TO FINAL ACCEPTANCE. SPRINT WILL REVIEW CLOSEOUT DOCUMENTATION FOR PRESENCE AND CONTENT. CLOSEOUT DOCUMENTATION SHALL INCLUDE BUT IS NOT LIMITED TO THE FOLLOWING AS APPLICABLE:

1. COAX SWEEP TESTS:
2. FIBER TESTS:
3. JURISDICTION FINAL INSPECTION DOCUMENTATION
4. REINFORCEMENT CERTIFICATION (MILL CERTIFICATION)
5. CONCRETE MIX DESIGN AND PRODUCT DATA (TOWER FOUNDATION)
6. LIEN WAIVERS AND RELEASES.
7. POST CONSTRUCTION HEIGHT VERIFICATION
8. JURISDICTION CERTIFICATE OF OCCUPANCY
9. ELECTRONIC ANTENNA AZIMUTH AND DOWN TILT VERIFICATION
10. STRUCTURAL BACKFILL TEST RESULTS (IF APPLICABLE)
  11. CELL SITE UTILITY SETUP
12. AS-BUILT REDLINE CONSTRUCTION DRAWINGS (PDF SCAN OF FIELD MARKS)
13. AS-BUILT CONSTRUCTION DRAWINGS IN DWG AND PDF FORMATS
14. LIST OF SUB CONTRACTORS
15. APPROVED PERMITTING DOCUMENTS
16. FINAL SITE PHOTOS UP-LOADED TO SITERRA. INCLUDE THE FOLLOWING AS APPLICABLE:
  - a. TOWER, ANTENNAS, RRUS, AND MAINLINE: INSPECTION AND PHOTOGRAPHS OF SECTION STACKING; INSPECTION AND PHOTOGRAPHS OF PLATFORM COMPONENT ATTACHMENT POINTS; PHOTOGRAPHS OF TOWER TOP GROUNDING; PHOTOS OF TOWER COAX/CABLE LINE COLOR CODING AT THE TOP AND AT GROUND LEVEL; INSPECTION AND PHOTOGRAPHS OF OPERATIONAL OF TOWER LIGHTING, AND PLACEMENT OF FAA REGISTRATION SIGN; PHOTOGRAPHS SHOWING ADDITIONAL GROUNDING POINTS FOR TOWERS GREATER THAN 200 FEET.; PHOTOS OF ANTENNA GROUND BAR, EQUIPMENT GROUND BAR, AND MASTER GROUND BAR; PHOTOS OF GPS ANTENNA(S); PHOTOS OF EACH SECTOR OF ANTENNAS; ONE PHOTOGRAPH LOOKING AT THE SECTOR AND ONE FROM BEHIND SHOWING THE PROJECTED COVERAGE AREA; PHOTOS OF COAX WEATHERPROOFING - TOP AND BOTTOM; PHOTOS OF COAX GROUNDING--TOP AND BOTTOM; PHOTOS OF ANTENNA AND MAST GROUNDING; PHOTOS OF COAX CABLE ENTRY INTO SHELTER; PHOTOS OF PLATFORM MECHANICAL CONNECTIONS TO TOWER/MONOPOLE.
  - b. ROOF TOPS: PRE-CONSTRUCTION AND POST-CONSTRUCTION VISUAL INSPECTION AND PHOTOGRAPHS OF THE ROOF AND INTERIOR TO DETERMINE AND DOCUMENT CONDITIONS; ROOF TOP CONSTRUCTION INSPECTIONS AS REQUIRED BY THE JURISDICTION; PHOTOGRAPHS OF CABLE TRAY AND/OR ICE BRIDGE; PHOTOGRAPHS OF DOGHOUSE/CABLE EXIT FROM ROOF;
  - c. SITE LAYOUT - PHOTOGRAPHS OF THE OVERALL COMPOUND, INCLUDING EQUIPMENT PLATFORM FROM ALL FOUR CORNERS.
  - d. FINISHED UTILITIES: CLOSE-UP PHOTOGRAPHS OF THE PPC BREAKER PANEL; CLOSE-UP PHOTOGRAPH OF THE INSIDE OF THE TELCO PANEL AND NIU; CLOSE-UP PHOTOGRAPH OF THE POWER METER AND DISCONNECT; PHOTOS OF POWER AND TELCO ENTRANCE TO COMPANY ENCLOSURE; PHOTOGRAPHS AT METER BOX AND/OR FACILITY DISTRIBUTION PANEL.

**PROJECT PHOTOGRAPHS:**

A. PROVIDE PROJECT CLOSEOUT GENERAL ARRANGEMENT PHOTOS OF ALL NEW WORK. THE FOLLOWING LIST REPRESENTS MINIMUM REQUIREMENTS AND MINIMUM QUANTITY. ADDITIONAL PHOTOS MAY BE REQUIRED TO ADEQUATELY DOCUMENT THE WORK.

1. ASR AND RF MPE SIGNAGE (IF NOT IN PLACE, SUPPLIER NOTIFIES EMS FIELD REPRESENTATIVE)
2. BACK OF ANTENNAS AND RRUS (1 EACH SECTOR)
3. BACK OF ANTENNAS AND RRUS (1 EACH SECTOR) CLOSE UP SHOWING WEATHERPROOFING AND GROUNDING (AS REQUIRED). CLOSE-UP OF BACK SIDE OF EACH PERMANENT RRU SHOWING SERIAL NUMBER/BAR CODE.
4. VIEW (1 EACH SECTOR) ALONG THE AZIMUTH AND TILT OF THE ANTENNAS
5. TOP OF TOWER FROM GROUND, 1 EACH SECTOR
6. MAINLINE HYBRID CABLE ROUTE DOWN TOWER SHOWING FASTENERS AND SUPPORT
7. MAINLINE/HYBRID CABLE ROUTE ALONG ICE BRIDGE OR IN CABLE TRAY SHOWING FASTENERS AND SUPPORT
8. GROUND MOUNTED RRU RACKS (FRONT AND BACK)
9. FRONT, SIDE AND BACK ELEVATIONS OF ALL GROUND CABINETS
10. VIEW OF COMPOUND FROM A DISTANCE
  11. VIEW OF EACH GROUND CABINET (POWER, RF, FIBER SPOOL, PPC POWER, PPC TELCO WITH DOOR OPEN)
12. BACKHAUL FIBER MEET-ME-POINT AND CONDUIT ROUTE (MICROWAVE INSTALLATION IF NOT FIBER)
13. AAV NETWORK INTERFACE DEVICE OR MICROWAVE RADIO INSTALLATION

**DEFICIENCY CORRECTIONS:**  
CONTRACTOR IS RESPONSIBLE FOR ALL CORRECTIONS TO DEFICIENCIES IDENTIFIED THROUGH TESTING, REVIEW OF SUBMITTALS, INSPECTIONS AND CLOSEOUT REVIEWS.

### SECTION 01 500 - PROJECT REPORTING

**WEEKLY REPORTS:**  
A. CONTRACTOR SHALL REPORT TO SPRINT AT MINIMUM ON A WEEKLY BASIS VIA SITERRA BY UPDATING ALL APPLICABLE POST END KEEPING MILESTONES WITH ACTUAL AND FORECASTED COMPLETION DATES.  
B. ADDITIONAL REQUIREMENTS FOR REPORTING MAY BE IDENTIFIED ELSEWHERE OR REQUIRED BY THE SCOPE OF SERVICES OR SPRINTS LOCAL MARKET CONSTRUCTION MANAGER. THIS INFORMATION WILL PROVIDE A BASIS FOR PROGRESS MONITORING AND PAYMENT.

**PROJECT CONFERENCE CALLS:**  
SPRINT MAY HOLD PERIODIC PROJECT CONFERENCE CALLS. CONTRACTOR WILL BE REQUIRED TO COMMUNICATE SITE STATUS, MILESTONE COMPLETIONS AND UPCOMING MILESTONE PROJECTIONS, AND ANSWER ANY OTHER SITE STATUS QUESTIONS AS NECESSARY.

**FINAL PROJECT ACCEPTANCE:** PRIOR TO SPRINTS FINAL PROJECT ACCEPTANCE. ALL REQUIRED MILESTONE ACTUALS MUST BE UPDATED IN SITERRA AND ALL REQUIRED REPORTING TASKS MUST BE COMPLETE.

### SECTION 11 700 - ANTENNA ASSEMBLY, REMOTE RADIO UNITS AND CABLE INSTALLATION

**SUMMARY:**  
THIS SECTION SPECIFIES INSTALLATION OF ANTENNAS, RRUS, AND CABLE EQUIPMENT, INSTALLATION, AND TESTING OF COAXIAL FIBER CABLE.

**ANTENNAS AND RRUS:**  
THE NUMBER AND TYPE OF ANTENNAS AND RRUS TO BE INSTALLED IS DETAILED ON THE CONSTRUCTION DRAWINGS.

**HYBRID CABLE:**  
HYBRID CABLE WILL BE DC/FIBER AND FURNISHED FOR INSTALLATION AT EACH SITE. CABLE SHALL BE INSTALLED PER THE CONSTRUCTION DRAWINGS AND THE APPLICABLE MANUFACTURER'S REQUIREMENTS.

**JUMPERS AND CONNECTORS:**  
FURNISH AND INSTALL 1/2" COAX JUMPER CABLES BETWEEN THE RRUS AND ANTENNAS. JUMPERS SHALL BE TYPE LDF 4, FLC 1 2-50, CR 540, OR FXL 540. SUPER-FLEX CABLES ARE NOT ACCEPTABLE. JUMPERS BETWEEN THE RRUS AND ANTENNAS OR TOWER TOP AMPLIFIERS SHALL CONSIST OF 1/2 INCH FOAM DIELECTRIC, OUTDOOR RATED COAXIAL CABLE, MIN. LENGTH FOR JUMPER SHALL BE 1'0"-0".

**REMOTE ELECTRICAL TILT (RET) CABLES:**

**MISCELLANEOUS:**  
INSTALL SPLITTERS, COMBINERS, FILTERS PER RF DATA SHEET, FURNISHED BY SPRINT.

**ANTENNA INSTALLATION:**  
THE CONTRACTOR SHALL ASSEMBLE ALL ANTENNAS ONSITE IN ACCORDANCE WITH THE INSTRUCTIONS SUPPLIED BY THE MANUFACTURER. ANTENNA HEIGHT, AZIMUTH, AND FEED ORIENTATION INFORMATION SHALL BE A DESIGNATED ON THE CONSTRUCTION DRAWINGS.

A. THE CONTRACTOR SHALL POSITION THE ANTENNA ON TOWER PIPE MOUNTS SO THAT THE BOTTOM STRUT IS LEVEL. THE PIPE MOUNTS SHALL BE PLUMB TO WITHIN 1 DEGREE.

B. ANTENNA MOUNTING REQUIREMENTS: PROVIDE ANTENNA MOUNTING HARDWARE AS INDICATED ON THE DRAWINGS.

**HYBRID CABLE INSTALLATION:**

A. THE CONTRACTOR SHALL ROUTE, TEST, AND INSTALL ALL CABLES AS INDICATED ON THE CONSTRUCTION DRAWINGS AND IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS.

B. THE INSTALLED RADIUS OF THE CABLES SHALL NOT BE LESS THAN THE MANUFACTURER'S SPECIFICATIONS FOR BENDING RADII.

C. EXTREME CARE SHALL BE TAKEN TO AVOID DAMAGE TO THE CABLES DURING HANDLING AND INSTALLATION.

1. FASTENING MAIN HYBRID CABLES: ALL CABLES SHALL BE INSTALLED INSIDE MONOPOLE WITH CABLE SUPPORT GRIPS AS REQUIRED BY THE MANUFACTURER.
2. FASTENING INDIVIDUAL FIBER AND DC CABLES ABOVE BREAKOUT ENCLOSURE (MEDUSA), WITHIN THE MMBS CABINET AND ANY INTERMEDIATE DISTRIBUTION BOXES:
  - a. FIBER: SUPPORT FIBER BUNDLES USING 1/2" VELCRO STRAPS OF THE REQUIRED LENGTH AT 18" O.C. STRAPS SHALL BE UV, OIL AND WATER RESISTANT AND SUITABLE FOR INDUSTRIAL INSTALLATIONS AS MANUFACTURED BY TEXTOL OR APPROVED EQUAL.
  - b. DC: SUPPORT DC BUNDLES WITH ZIP TIES OF THE ADEQUATE LENGTH. ZIP TIES TO BE UV STABILIZED, BLACK NYLON, WITH TENSILE STRENGTH AT 12,000 PSI AS MANUFACTURED BY NELCO PRODUCTS OR EQUAL.
3. FASTENING JUMPERS: SECURE JUMPERS TO THE SIDE ARMS OR HEAD FRAMES USING STAINLESS STEEL TIE WRAPS OR STAINLESS STEEL BUTTERFLY CLIPS.
4. CABLE INSTALLATION:
  - a. INSPECT CABLE PRIOR TO USE FOR SHIPPING DAMAGE, NOTIFY THE CONSTRUCTION MANAGER.
  - b. CABLE ROUTING: CABLE INSTALLATION SHALL BE PLANNED TO ENSURE THAT THE LINES WILL BE PROPERLY ROUTED IN THE CABLE ENVELOPE AS INDICATED ON THE DRAWINGS. AVOID TWISTING AND CROSSEOVERS.
  - c. HOIST CABLE USING PROPER HOISTING GRIPS. DO NOT EXCEED MANUFACTURER'S RECOMMENDED MAXIMUM BEND RADIUS.
5. GROUNDING OF TRANSMISSION LINES: ALL TRANSMISSION LINES SHALL BE GROUNDED AS INDICATED ON DRAWINGS.
6. HYBRID CABLE COLOR CODING: ALL COLOR CODING SHALL BE AS REQUIRED IN TS 0200 (CURRENT VERSION).
7. HYBRID CABLE LABELING: INDIVIDUAL HYBRID AND DC BUNDLES SHALL BE LABELED ALPHA-NUMERICALLY ACCORDING TO SPRINT CELL SITE ENGINEERING NOTICE - EN 2012-001, REV 1

### WEATHERPROOFING EXTERIOR CONNECTORS AND HYBRID CABLE GROUND KITS:

A. ALL FIBER & COAX CONNECTORS AND GROUND KITS SHALL BE WEATHERPROOFED.

B. WEATHERPROOFED USING ONE OF THE FOLLOWING METHODS. ALL INSTALLATIONS MUST BE DONE IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS AND INDUSTRY BEST PRACTICES.

1. COLD SHRINK: ENCOMPASS CONNECTOR IN COLD SHRINK TUBING AND PROVIDE A DOUBLE WRAP OF 2" ELECTRICAL TAPE EXTENDING 2" BEYOND TUBING. PROVIDE 3M COLD SHRINK CXS SERIES OR EQUAL.
2. SELF-AMALGAMATING TAPE: CLEAN SURFACES. APPLY A DOUBLE WRAP OF SELF-AMALGAMATING TAPE 2" BEYOND CONNECTOR. APPLY A SECOND WRAP OF SELF-AMALGAMATING TAPE IN OPPOSITE DIRECTION. APPLY DOUBLE WRAP OF 2" WIDE ELECTRICAL TAPE EXTENDING 2" BEYOND THE SELF-AMALGAMATING TAPE.
3. 3M SLIM LOCK CLOSURE 716: SUBSTITUTIONS WILL NOT BE ALLOWED.
4. OPEN FLAME ON JOB SITE IS NOT ACCEPTABLE

### SECTION 11 800 - INSTALLATION OF MULTIMODAL BASE STATIONS (MMBS) AND RELATED EQUIPMENT

**SUMMARY:**

A. THIS SECTION SPECIFIES MMBS CABINETS, POWER CABINETS, AND INTERNAL EQUIPMENT INCLUDING BY NOT LIMITED TO RECTIFIERS, POWER DISTRIBUTION UNITS, BASE BAND UNITS, SURGE ARRESTORS, BATTERIES, AND SIMILAR EQUIPMENT FURNISHED BY THE COMPANY FOR INSTALLATION BY THE CONTRACTOR (OFCI).

B. CONTRACTOR SHALL PROVIDE AND INSTALL ALL MISCELLANEOUS MATERIALS AND PROVIDE ALL LABOR REQUIRED FOR INSTALLATION EQUIPMENT IN EXISTING CABINET OR NEW CABINET AS SHOWN ON DRAWINGS AND AS REQUIRED BY THE APPLICABLE INSTALLATION MOPS.

C. COMPLY WITH MANUFACTURER'S INSTALLATION AND START-UP REQUIREMENTS.

### DC CIRCUIT BREAKER LABELING

A. NEW DC CIRCUIT IS REQUIRED IN MMBS CABINET SHALL BE CLEARLY IDENTIFIED AS TO RRU BEING SERVICED.

### SECTION 26 100 - BASIC ELECTRICAL REQUIREMENTS

**SUMMARY:**

THIS SECTION SPECIFIES BASIC ELECTRICAL REQUIREMENTS FOR SYSTEMS AND COMPONENTS

### QUALITY ASSURANCE:

A. ALL EQUIPMENT FURNISHED UNDER DIVISION 26 SHALL CARRY UL LABELS AND LISTINGS WHERE SUCH LABELS AND LISTINGS ARE AVAILABLE IN THE INDUSTRY.

B. MANUFACTURERS OF EQUIPMENT SHALL HAVE A MINIMUM OF THREE YEARS EXPERIENCE WITH THEIR EQUIPMENT INSTALLED AND OPERATING IN THE FIELD IN A USE SIMILAR TO THE PROPOSED USE FOR THIS PROJECT.

C. MATERIALS AND EQUIPMENT: ALL MATERIALS AND EQUIPMENT SPECIFIED IN DIVISION 26 OF THE SAME TYPE SHALL BE OF THE SAME MANUFACTURER AND SHALL BE NEW, OF THE BEST QUALITY AND DESIGN, AND FREE FROM DEFECTS.

### SUPPORTING DEVICES:

A. MANUFACTURED STRUCTURAL SUPPORT MATERIALS: SUBJECT TO COMPLIANCE WITH REQUIREMENTS, PROVIDE PRODUCTS BY THE FOLLOWING:

1. ALLIED TUBE AND CONDUIT.
2. B-LINE SYSTEM.
3. UNISTRUT DIVERSIFIED PRODUCTS.
4. THOMAS & BETTS.

B. FASTENERS: TYPES, MATERIALS, AND CONSTRUCTION FEATURES AS FOLLOWS:

1. EXPANSION ANCHORS: CARBON STEEL WEDGE OR SLEEVE TYPE.
2. POWER-DRIVEN THREADED STUDS: HEAT-TREATED STEEL, DESIGNED SPECIFICALLY FOR THE INTENDED SERVICE.
3. FASTEN BY MEANS OF WOOD SCREWS ON WOOD.
4. TOGGLE BOLTS ON HOLLOW MASONRY UNITS.
5. CONCRETE INSERTS OR EXPANSION BOLTS ON CONCRETE OR SOLID MASONRY.
6. MACHINE SCREWS, WELDED THREADED STUDS, OR SPRING-TENSION CLAMPS ON STEEL.
7. EXPLOSIVE DEVICES FOR ATTACHING HANGERS TO STRUCTURE SHALL NOT BE PERMITTED.
8. DO NOT WELD CONDUIT, PIPE STRAPS, OR ITEMS OTHER THAN THREADED STUDS TO STEEL STRUCTURES.
9. IN PARTITIONS OF LIGHT STEEL CONSTRUCTION, USE SHEET METAL SCREWS.



6580 SPRINT PARKWAY  
OVERLAND PARK, KANSAS 66251




855 Community Drive, Sauk City, WI 53583  
Phone: 608-643-4100 Fax: 608-643-7999  
www.Ramaker.com

## Charles Cherundolo Consulting, Inc.

713 Clover Lane, Moscow, PA 18444  
Phone: 570-840-5084 Fax: 570-842-5592

Certification & Seal:  
I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 10/06/2017

MARK	DATE	DESCRIPTION

ISSUE PHASE	FINAL	DATE ISSUED	10/06/17
-------------	-------	-------------	----------

PROJECT TITLE:  
**TRANSFER STATION  
CT33XC522-C**

PROJECT INFORMATION:  
237 GODFREY ROAD  
WESTON, CT 06883  
FAIRFIELD COUNTY

SHEET TITLE:  
**SPRINT SPECIFICATIONS**

SCALE: NONE

PROJECT NUMBER	28737
SHEET NUMBER	SP-2

SUPPORTING DEVICES:

- A. INSTALL SUPPORTING DEVICES TO FASTEN ELECTRICAL COMPONENTS SECURELY AND PERMANENTLY IN ACCORDANCE WITH NEC.
- B. COORDINATE WITH THE BUILDING STRUCTURAL SYSTEM AND WITH OTHER TRADES.
- C. UNLESS OTHERWISE INDICATED ON THE DRAWINGS, FASTEN ELECTRICAL ITEMS AND THEIR SUPPORTING HARDWARE SECURELY TO THE STRUCTURE IN ACCORDANCE WITH THE FOLLOWING:
  - 1. ENSURE THAT THE LOAD APPLIED BY ANY FASTENER DOES NOT EXCEED 25 PERCENT OF THE PROOF TEST LOAD.
  - 2. USE VIBRATION AND SHOCK-RESISTANT FASTENERS FOR ATTACHMENTS TO CONCRETE SLABS.

ELECTRICAL IDENTIFICATION:

- A. UPDATE AND PROVIDE TYPED CIRCUIT BREAKER SCHEDULES IN THE MOUNTING BRACKET, INSIDE DOORS OF AC PANEL BOARDS WITH ANY CHANGES MADE TO THE AC SYSTEM.
- B. BRANCH CIRCUITS FEEDING AVIATION OBSTRUCTION LIGHTING EQUIPMENT SHALL BE CLEARLY IDENTIFIED AS SUCH AT THE BRANCH CIRCUIT PANELBOARD.

SECTION 26 200 - ELECTRICAL MATERIALS AND EQUIPMENT

- A. RIGID GALVANIZED STEEL (RGS) CONDUIT SHALL BE USED FOR EXTERIOR LOCATIONS ABOVE GROUND AND IN UNFINISHED INTERIOR LOCATIONS AND FOR UNDERGROUND RUNS. RIGID CONDUIT AND FITTINGS SHALL BE STEEL, COATED WITH ZINC EXTERIOR AND INTERIOR BY THE HOT DIP GALVANIZING PROCESS. CONDUIT SHALL BE PRODUCED TO ANSI SPECIFICATIONS C80.1, FEDERAL SPECIFICATION WW-C-581 AND SHALL BE LISTED WITH THE UNDERWRITERS' LABORATORIES. FITTINGS SHALL BE THREADED - SET SCREW OR COMPRESSION FITTINGS WILL NOT BE ACCEPTABLE. RGS CONDUITS SHALL BE MANUFACTURED BY ALLIED, REPUBLIC OR WHEATLAND.
- B. UNDERGROUND CONDUIT IN CONCRETE SHALL BE POLYVINYLCHLORIDE (PVC) SUITABLE FOR DIRECT BURIAL AS APPLICABLE. JOINTS SHALL BE BELLED, AND FLUSH SOLVENT WELDED IN ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS. CONDUIT SHALL BE CARLON ELECTRICAL PRODUCTS OR APPROVED EQUAL.
- C. TRANSITIONS BETWEEN PVC AND RIGID (RGS) SHALL BE MADE WITH PVC COATED METALLIC LONG SWEEP RADIUS ELBOWS.
- D. EMT OR RIGID GALVANIZED STEEL CONDUIT MAY BE USED IN FINISHED SPACES CONCEALED IN WALLS AND CEILINGS. EMT SHALL BE MILD STEEL, ELECTRICALLY WELDED, ELECTRO-GALVANIZED OR HOT-DIPPED GALVANIZED AND PRODUCED TO ANSI SPECIFICATION C80.3, FEDERAL SPECIFICATION WW-C-563, AND SHALL BE UL LISTED. EMT SHALL BE MANUFACTURED BY ALLIED, REPUBLIC OR WHEATLAND, OR APPROVED EQUAL. FITTINGS SHALL BE METALLIC COMPRESSION. SET SCREW CONNECTIONS SHALL NOT BE ACCEPTABLE.
- E. LIQUID TIGHT FLEXIBLE METALLIC CONDUIT SHALL BE USED FOR FINAL CONNECTION TO EQUIPMENT. FITTINGS SHALL BE METALLIC GLAND TYPE COMPRESSION FITTINGS, MAINTAINING THE INTEGRITY OF CONDUIT SYSTEM. SET SCREW CONNECTIONS SHALL NOT BE ACCEPTABLE. MAXIMUM LENGTH OF FLEXIBLE CONDUIT SHALL NOT EXCEED 6-FEET. LFMC SHALL BE PROTECTED AND SUPPORTED AS REQUIRED BY NEC. MANUFACTURERS OF FLEXIBLE CONDUITS SHALL BE CAROL, ANACONDA METAL HOSE OR UNIVERSAL METAL HOSE, OR APPROVED EQUAL.
- F. MINIMUM SIZE CONDUIT SHALL BE 3/4 INCH (21 MM).

HUBS AND BOXES:

- A. AT ENTRANCES TO CABINETS OR OTHER EQUIPMENT NOT HAVING INTEGRAL THREADED HUBS PROVIDE METALLIC THREADED HUBS OF THE SIZE AND CONFIGURATION REQUIRED. HUB SHALL INCLUDE LOCKNUT AND NEOPRENE O-RING SEAL. PROVIDE IMPACT RESISTANT 105 DEGREE C PLASTIC BUSHINGS TO PROTECT CABLE INSULATION.
- B. CABLE TERMINATION FITTINGS FOR CONDUIT
  - 1. CABLE TERMINATORS FOR RGS CONDUITS SHALL BE TYPE CRC BY O-Z/GEDNEY OR EQUAL BY ROXTEC.
  - 2. CABLE TERMINATORS FOR LFMC SHALL BE ETCO - CL2075; OR MADE FOR THE PURPOSE PRODUCTS BY ROXTEC.
- C. EXTERIOR PULL BOXES AND PULL BOXES IN INTERIOR INDUSTRIAL AREAS SHALL BE PLATED CAST ALLOY, HEAVY DUTY, WEATHERPROOF, DUST PROOF, WITH GASKET, PLATED IRON ALLOY COVER AND STAINLESS STEEL COVER SCREWS, CROUSE-HINDS WAB SERIES OR EQUAL.
- D. CONDUIT OUTLET BODIES SHALL BE PLATED CAST ALLOY WITH SIMILAR GASKET COVERS. OUTLET BODIES SHALL BE OF THE CONFIGURATION AND SIZE SUITABLE FOR THE APPLICATION. PROVIDE CROUSE-HINDS FORM B OR EQUAL.
- E. MANUFACTURER FOR BOXES AND COVERS SHALL BE HOFFMAN, SQUARE "D", CROUSE-HINDS, COOPER, ADALET, APPLETON, O-Z GEDNEY, RACO, OR APPROVED EQUAL.

SUPPLEMENTAL GROUNDING SYSTEM:

- A. FURNISH AND INSTALL A SUPPLEMENTAL GROUNDING SYSTEM TO THE EXTENT INDICATED ON THE DRAWINGS. SUPPORT SYSTEM WITH NON-MAGNETIC STAINLESS STEEL CLIPS WITH RUBBER GROMMETS. GROUNDING CONNECTORS SHALL BE TINNED COPPER WIRE, SIZES AS INDICATED ON THE DRAWINGS. PROVIDE STRANDED OR SOLID BARE OR INSULATED CONDUCTORS EXCEPT AS OTHERWISE NOTED.
- B. SUPPLEMENTAL GROUNDING SYSTEM: ALL CONNECTIONS TO BE MADE WITH CAD WELDS, EXCEPT AT EQUIPMENT USE LUGS OR OTHER AVAILABLE GROUNDING MEANS AS REQUIRED BY MANUFACTURER; AT GROUND BARS USE TWO HOLE SPADES WITH NO-OX.
- C. STOLEN GROUND-BARS: IN THE EVENT OF STOLEN GROUND BARS, CONTACT SPRINT CM FOR REPLACEMENT INSTRUCTION USING THREADED ROD KITS.

EXISTING STRUCTURE:

- A. EXISTING EXPOSED WIRING AND ALL EXPOSED OUTLETS, RECEPTACLES, SWITCHES, DEVICES, BOXES, AND OTHER EQUIPMENT THAT ARE NOT TO BE UTILIZED IN THE COMPLETED PROJECT SHALL BE REMOVED OR DE-ENERGIZED AND CAPPED IN THE WALL, CEILING, OR FLOOR SO THAT THEY ARE CONCEALED AND SAFE. WALL, CEILING, OR FLOOR SHALL BE PATCHED TO MATCH THE ADJACENT CONSTRUCTION.

CONDUIT AND CONDUCTOR INSTALLATION:

- A. CONDUITS SHALL BE FASTENED SECURELY IN PLACE WITH APPROVED NON-PERFORATED STRAPS AND HANGERS. EXPLOSIVE DEVICES FOR ATTACHING HANGERS TO STRUCTURE WILL NOT BE PERMITTED. CLOSELY FOLLOW THE LINES OF THE STRUCTURE, MAINTAIN CLOSE PROXIMITY TO THE STRUCTURE AND KEEP CONDUITS IN TIGHT ENVELOPES. CHANGES IN DIRECTION TO ROUTE AROUND OBSTACLES SHALL BE MADE WITH CONDUIT OUTLET BODIES. CONDUIT SHALL BE INSTALLED IN A NEAT AND WORKMANLIKE MANNER, PARALLEL AND PERPENDICULAR TO STRUCTURE WALL AND CEILING LINES. ALL CONDUIT SHALL BE FISHED TO CLEAR OBSTRUCTIONS. ENDS OF CONDUITS SHALL BE TEMPORARILY CAPPED TO PREVENT CONCRETE, PLASTER OR DIRT FROM ENTERING. CONDUITS SHALL BE RIGIDLY CLAMPED TO BOXES BY GALVANIZED MALLEABLE IRON BUSHING ON INSIDE AND GALVANIZED MALLEABLE IRON LOCKNUT ON OUTSIDE AND INSIDE.
- B. CONDUCTORS SHALL BE PULLED IN ACCORDANCE WITH ACCEPTED GOOD PRACTICE.



6580 SPRINT PARKWAY  
 OVERLAND PARK, KANSAS 66251




855 Community Drive, Sauk City, WI 53583  
 Phone: 608-643-4100 Fax: 608-643-7999  
 www.Ramaker.com

**Charles Cherundolo**  
**Consulting, Inc.**

713 Clover Lane, Moscow, PA 18444  
 Phone: 570-840-5084 Fax: 570-842-5592

Certification & Seal:  
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



*James R. Skowronski* 10/06/2017  
 Signature: Date:

MARK	DATE	DESCRIPTION
ISSUE PHASE	FINAL	DATE ISSUED 10/06/17


PROJECT TITLE:  
**TRANSFER STATION  
 CT33XC522-C**

PROJECT INFORMATION:  
 237 GODFREY ROAD  
 WESTON, CT 06883  
 FAIRFIELD COUNTY

SHEET TITLE:  
**SPRINT SPECIFICATIONS**

SCALE: NONE

PROJECT NUMBER	28737
SHEET NUMBER	SP-3



SITE PLAN  
 SCALE: 1" = 10'



6580 SPRINT PARKWAY  
 OVERLAND PARK, KANSAS 66251



855 Community Drive, Sauk City, WI 53583  
 Phone: 608-643-4100 Fax: 608-643-7999  
 www.Ramaker.com

**Charles Cherundolo**  
 Consulting, Inc.

713 Clover Lane, Moscow, PA 18444  
 Phone: 570-840-5084 Fax: 570-842-5592

Certification & Seal:  
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.




Signature: *James R. Skowronski* Date: 10/06/2017

MARK	DATE	DESCRIPTION
ISSUE	FINAL	DATE ISSUED 10/06/17

PROJECT TITLE:  
**TRANSFER STATION  
 CT33XC522-C**


PROJECT INFORMATION:  
 237 GODFREY ROAD  
 WESTON, CT 06883  
 FAIRFIELD COUNTY

SHEET TITLE:  
**SITE PLAN**



PROJECT NUMBER: 28737  
 SHEET NUMBER: A-1

This document contains confidential or proprietary information of Ramaker & Associates, Inc. Neither this document nor the information herein is to be reproduced, distributed, used or disclosed either in whole or in part except as authorized by Ramaker and Associates, Inc.



**EQUIPMENT PLAN**  
 SCALE: 1" = 2.5'



6580 SPRINT PARKWAY  
 OVERLAND PARK, KANSAS 66251




855 Community Drive, Sauk City, WI 53583  
 Phone: 608-643-4100 Fax: 608-643-7999  
 www.Ramaker.com

**Charles Cherundolo**  
 Consulting, Inc.

713 Clover Lane, Moscow, PA 18444  
 Phone: 570-840-5084 Fax: 570-842-5592

Certification & Seal:  
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



*James R. Skowronski* Signature: \_\_\_\_\_ Date: 10/06/2017


MARK	DATE	DESCRIPTION

ISSUE PHASE	FINAL	DATE ISSUED	10/06/17
-------------	-------	-------------	----------

PROJECT TITLE:  
**TRANSFER STATION  
 CT33XC522-C**


PROJECT INFORMATION:  
 237 GODFREY ROAD  
 WESTON, CT 06883  
 FAIRFIELD COUNTY

SHEET TITLE:  
**EQUIPMENT PLAN**




PROJECT NUMBER: 28737  
 SHEET NUMBER: A-2






**ANTENNA & RRH MOUNTING DETAILS**  
 SCALE: NTS




**EXISTING ANTENNA ARRAY**  
 SCALE: NTS



**BUILDING ELEVATION**  
 SCALE: 1" = 40'

0 20' 40' 80'

11" x 17" - 1" = 40'  
 22" x 34" - 1" = 20'



**PROPOSED ANTENNA ARRAY**  
 SCALE: NTS



6580 SPRINT PARKWAY  
 OVERLAND PARK, KANSAS 66251




855 Community Drive, Sauk City, WI 53583  
 Phone: 608-643-4100 Fax: 608-643-7999  
 www.Ramaker.com

**Charles Cherundolo**  
 Consulting, Inc.

713 Clover Lane, Moscow, PA 18444  
 Phone: 570-840-5084 Fax: 570-842-5592

Certification & Seal:  
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 10/06/2017

MARK	DATE	DESCRIPTION
ISSUE	FINAL	DATE ISSUED 10/06/17

PROJECT TITLE:  
**TRANSFER STATION  
 CT33XC522-C**

PROJECT INFORMATION:  
 237 GODFREY ROAD  
 WESTON, CT 06883  
 FAIRFIELD COUNTY

SHEET TITLE:  
**BUILDING ELEVATIONS &  
 ANTENNA DETAILS**

SCALE:  
 AS NOTED

PROJECT NUMBER: 28737  
 SHEET NUMBER: A-3

### RFDS Sheet

#### General Site Information

Site ID	CT33XC522	Equipment Vendor	Alcatel-Lucent
Market	Southern Connecticut	Latitude	41.244386
Region	Northeast	Longitude	-73.363386
MLA	N/A	LL SITE ID	N/A
Structure Type	Lattice Tower		
BTS Type			

Solution ID		Siterra SR Equipment type		Incremental Power Draw needed by added Equipment	TBD
		Equipment Vendor	Alcatel-Lucent		

#### Base Equipment

BBU Kit	ALU BBU Kit	Top Hat	None
BBU Kit Qty	1	Top Hat Qty	N/A
Growth Cabinet	None	Top Hat Dimensions	N/A
Growth Cabinet Qty	N/A	Top Hat Weight (lbs)	N/A
Growth Cabinet Dimensions	N/A		
Growth Cabinet Weight	N/A		

#### RF Path Information

RRH	TD-RRH8x20-25	
RRH Qty	3	
RRH Dimensions	26.1"x18.6"x6.7"	
RRH Weight. lbs.	70	
RRH Mount Weight. Lbs.	10	
Power and Fiber Cable	ALU Hybrid	
Cable Qty	1	
Weight per foot. Lbs.	0.992	
Diameter. Inches.	1.25	
Length Ft.	209	(calculated as antenna height plus 20%)
Coax Jumper	TBD	
Coax Jumper Qty	27	
Coax Jumper Length. Feet.	8	
Coax Jumper Weight	1.7	
Coax Jumper Diameter. Inches	0.5	
AISG Cable	Commscope ATCB-B01-006	
AISG Cable Qty	3	
AISG Diameter. Inches.	0.315	
AISG Cable length.	8	
Weight of entire AISG cable. Lbs.	1.3	

#### Antenna Sector Information

	Sector 1	Sector 2	Sector 3
Antenna make/model	RFS APXV9TM14-ALU-I20	RFS APXV9TM14-ALU-I20	RFS APXV9TM14-ALU-I20
Antenna qty	1	1	1
Antenna Dimensions. Inches	56.3"x12.6"x6.3"	56.3"x12.6"x6.3"	56.3"x12.6"x6.3"
Antenna Weight. Lbs	55.12	55.12	55.12
Antenna Mounting Kit Weight. Lbs.	11.5	11.5	11.5
CL Height	174	174	174
Antenna Azimuth	340	100	220
Antenna Mechanical Downtilt	0	0	0
Antenna etilt	-2	-2	-2

\*RFDS SHEET WAS GENERATED BY RAMAKER & ASSOCIATES FROM PLAN OF RECORD (POR) PROVIDED BY SPRINT. CONTRACTOR SHALL VERIFY AND OBTAIN FINAL RFDS FROM SPRINT CONSTRUCTION MANAGER PRIOR TO CONSTRUCTION.

#### NOTES:

- GENERAL CONTRACTOR TO FIELD VERIFY AZIMUTH AND C/L HEIGHT AND MECHANICAL DOWNTILT. IF DIFFERENT THAN CALLED OUT BELOW, HALT ANTENNA WORK FOR ONE HOUR, CALL SPRINT RF ENGINEER (OR MANAGER IF RF ENGINEER DOES NOT ANSWER, BUT STILL LEAVE A MESSAGE TO RF ENGINEER) USING CONTACT INFORMATION ABOVE FOR FURTHER INSTRUCTIONS. IF SPRINT DOES NOT RESPOND WITHIN ONE HOUR, PLACE 2.5GHZ ANTENNA AT SAME C/L HEIGHT AS 1.9GHZ ANTENNA AND EMAIL CORRECT C/L HEIGHT AND AZIMUTH TO SPRINT RF ENGINEER. UPDATE AS-BUILT DRAWING WITH CORRECT C/L HEIGHT. ALSO EMAIL CORRECT 1.9GHZ AND 800MHZ ANTENNA C/L HEIGHT, AZIMUTH AND MECHANICAL DOWNTILT TO RF ENGINEER.
- AISG TESTS TO VERIFY OPERATION IS TO BE PERFORMED AFTER FINAL INSTALLATION OF ANTENNAS AND AISG CABLES HAVE BEEN CONNECTED. VERIFY OPERATION OF ALL EXISTING SPRINT AISG EQUIPMENT INCLUDING 800MHZ, 1.9GHZ AND 2.5GHZ. TEST TO INCLUDE COMPLETE DOWNTILT, AZIMUTH (IF APPLICABLE) AND BEAMWIDTH SWINGS (IF APPLICABLE). DOCUMENT AISG TEST RESULTS IN COAX SWEEP TEST SPREADSHEET.
- GENERAL CONTRACTOR MUST ENSURE THAT NO OBJECT IS LOCATED WITHIN 45 DEGREES OF LEFT AND RIGHT OF FRONT OF ANTENNA OR 7 DEGREES UP AND DOWN FROM CENTER OF ANTENNA. IF THIS IS NOT POSSIBLE, CONTACT RF ENGINEER FOR FURTHER INSTRUCTION. IN ADDITION, 2.5GHZ ANTENNA IS NOT TO BE PLACED IN FRONT OF ANY OTHER ANTENNA USING THE SAME 45 DEGREE RULE. THIS INCLUDES SPRINT AND NON-SPRINT ANTENNAS.
- 2.5GHZ ANTENNA MUST BE AT LEAST 6" FROM 1.9GHZ ANTENNA, 30" FROM 800MHZ ANTENNA AND 30" FROM DUAL BAND 1.9GHZ AND 800MHZ ANTENNA.
- GENERAL CONTRACTOR IS REQUIRED TO USE A DIGITAL ALIGNMENT TOOL TO SET AZIMUTH, ROLL AND DOWNTILT. AZIMUTH ACCURACY IS TO BE WITHIN 1 DEGREE. DOWNTILT AND ROLL (LEFT TO RIGHT TILT) IS TO BE WITHIN 0.1 DEGREES. IF FOR SOME REASON THIS ACCURACY CANNOT BE ACHIEVED, UPDATE AS-BUILT DRAWINGS AND EMAIL SPRINT RF ENGINEER WITH AS-BUILT SETTINGS. USE 3Z RF ALIGNMENT TOOL OR EQUIVALENT TOOL.



6580 SPRINT PARKWAY  
 OVERLAND PARK, KANSAS 66251




855 Community Drive, Sauk City, WI 53583  
 Phone: 608-643-4100 Fax: 608-643-7999  
 www.Ramaker.com

**Charles Cherundolo**  
 Consulting, Inc.

713 Clover Lane, Moscow, PA 18444  
 Phone: 570-840-5084 Fax: 570-842-5592

Certification & Seal:  
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



*James R. Skowronski* 10/06/2017  
 Signature: Date:

MARK	DATE	DESCRIPTION
ISSUE PHASE	FINAL	DATE ISSUED 10/06/17


PROJECT TITLE:  
**TRANSFER STATION  
 CT33XC522-C**

PROJECT INFORMATION:  
 237 GODFREY ROAD  
 WESTON, CT 06883  
 FAIRFIELD COUNTY


SHEET TITLE:  
**RF DATA SHEET**

SCALE:  
 AS NOTED


PROJECT NUMBER: 28737  
 SHEET NUMBER: A-4




TYPICAL FIBER DISTRIBUTION BOX DETAIL  
 SCALE: NTS




RRH TO DISTRIBUTION BOX POWER CONNECTIVITY DETAIL  
 SCALE: NTS



8T8R DETAIL  
 SCALE: NTS



BTS TO DISTRIBUTION BOX FIBER CONNECTIVITY DETAIL  
 SCALE: NTS



RRH TO DISTRIBUTION BOX FIBER CONNECTIVITY DETAIL  
 SCALE: NTS



6580 SPRINT PARKWAY  
 OVERLAND PARK, KANSAS 66251




855 Community Drive, Sauk City, WI 53583  
 Phone: 608-643-4100 Fax: 608-643-7999  
 www.Ramaker.com

**Charles Cherundolo**  
 Consulting, Inc.

713 Clover Lane, Moscow, PA 18444  
 Phone: 570-840-5084 Fax: 570-842-5592

Certification & Seal:  
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 10/06/2017

MARK	DATE	DESCRIPTION
ISSUE	FINAL	DATE ISSUED 10/06/17

PROJECT INFORMATION:  
 237 GODFREY ROAD  
 WESTON, CT 06883  
 FAIRFIELD COUNTY

SHEET TITLE:  
 FIBER PLUMBING DIAGRAM





SCALE:  
 AS NOTED

PROJECT NUMBER: 28737  
 SHEET NUMBER: A-5

2.5 FREQUENCY	INDICATOR		ID
2500 -1	YEL	WHT	GRN
2500 -2	YEL	WHT	RED
2500 -3	YEL	WHT	BRN
2500 -4	YEL	WHT	BLU
2500 -5	YEL	WHT	SLT
2500 -6	YEL	WHT	ORG
2500 -7	YEL	WHT	WHT
2500 -8	YEL	WHT	PPL

NV FREQUENCY	INDICATOR	ID
800-1	YEL	GRN
1900-1	YEL	RED
1900-2	YEL	BRN
1900-3	YEL	BLU
1900-4	YEL	SLT
800-1	YEL	ORG
RESERVED	YEL	WHT
RESERVED	YEL	PPL

Sector	Cable	First Ring	Second Ring	Third Ring
<b>1 Alpha</b>	<b>1</b>	Green	No Tape	No Tape
<b>1</b>	<b>2</b>	Blue	No Tape	No Tape
<b>1</b>	<b>3</b>	Brown	No Tape	No Tape
<b>1</b>	<b>4</b>	White	No Tape	No Tape
<b>1</b>	<b>5</b>	Red	No Tape	No Tape
<b>1</b>	<b>6</b>	Grey	No Tape	No Tape
<b>1</b>	<b>7</b>	Purple	No Tape	No Tape
<b>1</b>	<b>8</b>	Orange	No Tape	No Tape
<b>2 Beta</b>	<b>1</b>	Green	Green	No Tape
<b>2</b>	<b>2</b>	Blue	Blue	No Tape
<b>2</b>	<b>3</b>	Brown	Brown	No Tape
<b>2</b>	<b>4</b>	White	White	No Tape
<b>2</b>	<b>5</b>	Red	Red	No Tape
<b>2</b>	<b>6</b>	Grey	Grey	No Tape
<b>2</b>	<b>7</b>	Purple	Purple	No Tape
<b>2</b>	<b>8</b>	Orange	Orange	No Tape
<b>3 Gamma</b>	<b>1</b>	Green	Green	Green
<b>3</b>	<b>2</b>	Blue	Blue	Blue
<b>3</b>	<b>3</b>	Brown	Brown	Brown
<b>3</b>	<b>4</b>	White	White	White
<b>3</b>	<b>5</b>	Red	Red	Red
<b>3</b>	<b>6</b>	Grey	Grey	Grey
<b>3</b>	<b>7</b>	Purple	Purple	Purple
<b>3</b>	<b>8</b>	Orange	Orange	Orange



COLOR CODING CHARTS  
 SCALE: NTS

CABLE MARKING NOTES

- ALL CABLES SHALL BE MARKED WITH 2" WIDE, UV STABILIZED, UL APPROVED TAPE.
- THE FIRST RING SHALL BE CLOSEST TO THE END OF THE CABLE AND SPACED APPROXIMATELY 2" FROM THE END CONNECTOR, WEATHERPROOFING, OR BREAKOUT UNIT. THERE SHALL BE 1" SPACE BETWEEN EACH RING.
- A 2" GAP SHALL SEPARATE THE CABLE COLOR CODE FROM THE FREQUENCY COLOR CODE. THE 2" COLOR RINGS FOR THE FREQUENCY CODE SHALL BE PLACED NEXT TO EACH OTHER WITH NO SPACES.
- THE 2" COLORED TAPE(S) SHALL BE WRAPPED A MINIMUM OF 3 TIMES AROUND THE INDIVIDUAL CABLES, AND THE TAPE SHALL BE KEPT IN THE SAME LOCATION AS MUCH AS POSSIBLE.
- SITES WITH MORE THAN FOUR (4) SECTORS WILL REQUIRE ADDITIONAL RINGS FOR EACH SECTOR, FOLLOWING THE PATTERN. HIGH CAPACITY SITES WILL USE THE SECOND CABLE IDENTIFIED BY BLUE BANDS OF TAPE.
- HYBRID FIBER CABLE SHALL BE SECTOR IDENTIFIED INSIDE THE CABINET ON FREQUENCY BUNDLES, ON THE SEALTITE, ON THE MAIN LINE UPON EXIT OF SEALTITE, AND BEFORE AND AFTER THE BREAKOUT UNIT (MEDUSA), AS WELL AS BEFORE AND AFTER ANY ENTRANCE OR EXIT.
- HFC "MAIN TRUNK" WILL NOT BE MARKED WITH THE FREQUENCY CODES, AS IT CONTAINS ALL FREQUENCIES.
- INDIVIDUAL POWER PAIRS AND FIBER BUNDLES SHALL BE LABELED WITH BOTH THE CABLE AND FREQUENCY.



6580 SPRINT PARKWAY  
 OVERLAND PARK, KANSAS 66251




855 Community Drive, Sauk City, WI 53583  
 Phone: 608-643-4100 Fax: 608-643-7999  
 www.Ramaker.com

**Charles Cherundolo**  
 Consulting, Inc.

713 Clover Lane, Moscow, PA 18444  
 Phone: 570-840-5084 Fax: 570-842-5592

Certification & Seal:  
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 10/06/2017

MARK	DATE	DESCRIPTION
ISSUE	FINAL	DATE ISSUED 10/06/17

PROJECT TITLE:  
**TRANSFER STATION  
 CT33XC522-C**

PROJECT INFORMATION:  
 237 GODFREY ROAD  
 WESTON, CT 06883  
 FAIRFIELD COUNTY

SHEET TITLE:  
**CABLE COLOR CODING**

SCALE:  
 AS NOTED

PROJECT NUMBER	28737
SHEET NUMBER	A-6

Copyright 2017 - Ramaker & Associates, Inc. - All Rights Reserved  
 CHECKED BY: KAB  
 DRAWN BY: TMS  
 Printed by: steves on Oct 06, 2017 - 10:16am  
 C:\Users\steves\local settings\temp\AcPublish\_1006828737 Sprint 2\_5\_Charles.dwg

HYBRID CABLE DC CONDUCTOR SIZE GUIDELINE  
MANUF:RFS




CABLE	LENGTH	DC CONDUCTOR	CABLE DIAMETER
Fiber Only	Varies	Use NV Hybriflex	5/8"
Hybriflex	<200'	8 AWG	1-1/4"
Hybriflex	225-300'	6 AWG	1-1/4"
Hybriflex	325-375'	4 AWG	1-1/4"

RFS HYBRIFLEX RISER CABLE SCHEDULE

FIBER ONLY (EXISTING DC POWER)	Hybrid cable	
MN-HB058-M12-050F	12x multi-mode fiber pairs, Top:Outdoor protected connectors, Bottom:LC Connectors, 5/8 cable, 50 ft	50 ft
MN-HB058-M12-075F		75 ft
MN-HB058-M12-100F		100 ft
MN-HB058-M12-125F		125 ft
MN-HB058-M12-150F		150 ft
MN-HB058-M12-175F		175 ft
MN-HB058-M12-200F		200 ft
8 AWG Power	Hybrid cable	
MN-HB114-08U3M12-050F	3x 8 AWG power pairs, 12x multi-mode fiber pairs, Outdoor rated connectors & LC connectors. 1 1/4 cable, 50 ft	50 ft
MN-HB114-08U3M12-075F		75 ft
MN-HB114-08U3M12-100F		100 ft
MN-HB114-08U3M12-125F		125 ft
MN-HB114-08U3M12-150F		150 ft
MN-HB114-08U3M12-175F		175 ft
MN-HB114-08U3M12-200F		200 ft
6 AWG Power	Hybrid cable	
MN-HB114-13U3M12-225F	3x 6 AWG power pairs, 12x multi-mode fiber pairs, Outdoor rated connectors & LC connectors. 1 1/4 cable, 225 ft	225 ft
MN-HB114-13U3M12-250F		250 ft
MN-HB114-13U3M12-275F		275 ft
MN-HB114-13U3M12-300F		300 ft
4 AWG Power	Hybrid cable	
MN-HB114-21U3M12-325F	3x 4 AWG power pairs, 12x multi-mode fiber pairs, Outdoor rated connectors & LC connectors. 1 1/4 cable, 325 ft	325 ft
MN-HB114-21U3M12-350F		350 ft
MN-HB114-21U3M12-375F		375 ft

RFS HYBRIFLEX JUMPER CABLE SCHEDULE

FIBER ONLY	Hybrid Jumper cable	
MN-HBF012-M3-5F1	5 ft, 3x multi-mode fiber pairs, Outdoor & LC connectors, 1/2 cable	5 ft
MN-HBF012-M3-10F1		10 ft
MN-HBF012-M3-15F1		15 ft
SPECIAL INSTALLATION NOTE: JUMPERS FROM 2.5 RRH TO 2.5 ANTENNA SHALL NOT EXCEED 15' NOTIFY SPRINT CM OF ANY DISCREPANCY		
8 AWG POWER	Hybrid Jumper cable	
MN-HBF058-08U1M3-5F1	5 ft, 1x 8 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC connectors, 5/8 cable	5 ft
MN-HBF058-08U1M3-10F1		10 ft
MN-HBF058-08U1M3-15F1		15 ft
SPECIAL INSTALLATION NOTE: JUMPERS FROM 2.5 RRH TO 2.5 ANTENNA SHALL NOT EXCEED 15' NOTIFY SPRINT CM OF ANY DISCREPANCY		
6 AWG POWER	Hybrid Jumper cable	
MN-HBF058-13U1M3-5F1	5 ft, 1x 6 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC connectors, 7/8 cable	5 ft
MN-HBF058-13U1M3-10F1		10 ft
MN-HBF058-13U1M3-15F1		15 ft
SPECIAL INSTALLATION NOTE: JUMPERS FROM 2.5 RRH TO 2.5 ANTENNA SHALL NOT EXCEED 15' NOTIFY SPRINT CM OF ANY DISCREPANCY		
4 AWG POWER	Hybrid Jumper cable	
MN-HBF078-21U1M3-5F1	5 ft, 1x 4 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC connectors, 7/8 cable	5 ft
MN-HBF078-21U1M3-10F1		10 ft
MN-HBF078-21U1M3-15F1		15 ft
SPECIAL INSTALLATION NOTE: JUMPERS FROM 2.5 RRH TO 2.5 ANTENNA SHALL NOT EXCEED 15' NOTIFY SPRINT CM OF ANY DISCREPANCY		




\*NOTE: SPRINT CM TO CONFIRM HYBRID/FIBER RISER CABLE # HYBRID/FIBER JUMPER CABLE MODEL NUMBERS BEFORE PREPARING BOM.


HYBRID CABLE CROSS SECTION #  
DATA  
SCALE: NTS

RFS: APXV9TM | 4-ALU-1 20

DIMENSIONS, HxWxD: 56.3" x 12.6" x 6.3"  
WEIGHT, WITHOUT PRE-MOUNTED BRACKETS: 55.12 lbs.  
CONNECTOR: (9) MINI-DIN FEMALE/BOTTOM



2.5 ANTENNA DETAIL  
SCALE: NTS



ALCATEL-LUCENT: TD-RRH8x20  
HxWxD = 26.1" x 18.6" x 6.7"  
WEIGHT = 70 lbs.

2.5 RRH DETAIL  
SCALE: NTS



6580 SPRINT PARKWAY  
OVERLAND PARK, KANSAS 66251




855 Community Drive, Sauk City, WI 53583  
Phone: 608-643-4100 Fax: 608-643-7999  
www.Ramaker.com

**Charles Cherundolo**  
Consulting, Inc.

713 Clover Lane, Moscow, PA 18444  
Phone: 570-840-5084 Fax: 570-842-5592

Certification & Seal:  
I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 10/06/2017

MARK	DATE	DESCRIPTION
ISSUE	FINAL	DATE ISSUED 10/06/17

PROJECT TITLE:  
**TRANSFER STATION  
CT33XC522-C**


PROJECT INFORMATION:  
237 GODFREY ROAD  
WESTON, CT 06883  
FAIRFIELD COUNTY

SHEET TITLE:  
**ANTENNA & HYBRID CABLE  
DETAILS**


SCALE:  
AS NOTED

PROJECT NUMBER	28737
SHEET NUMBER	A-7

This document contains confidential or proprietary information of Ramaker & Associates, Inc. Neither this document nor the information herein is to be reproduced, distributed, used or disclosed either in whole or in part except as authorized by Ramaker and Associates, Inc.



HYBRID BREAKOUT DETAIL  
 SCALE: NTS



CABLE ROUTE FROM CABINET  
 SCALE: NTS




(1) PROPOSED BATTERY STRING TO BE INSTALLED IN EXISTING BATTERY CABINET

EXISTING BBU CABINET  
 SCALE: NTS



INSTALL NEW 2.5 EQUIPMENT, INCLUDING BASE BAND UNIT, CELL SITE ROUTER, RECTIFIERS, AND SURGE ARRESTORS AS NEEDED IN EXISTING MM-BTS CABINET



EXISTING MMBS CABINET  
 SCALE: NTS



6580 SPRINT PARKWAY  
 OVERLAND PARK, KANSAS 66251




855 Community Drive, Sauk City, WI 53583  
 Phone: 608-643-4100 Fax: 608-643-7999  
 www.Ramaker.com

**Charles Cherundolo Consulting, Inc.**

713 Clover Lane, Moscow, PA 18444  
 Phone: 570-840-5084 Fax: 570-842-5592

Certification & Seal:  
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 10/06/2017

MARK	DATE	DESCRIPTION
ISSUE	FINAL	DATE ISSUED 10/06/17

PROJECT TITLE:  
**TRANSFER STATION CT33XC522-C**

PROJECT INFORMATION:  
 237 GODFREY ROAD  
 WESTON, CT 06883  
 FAIRFIELD COUNTY

SHEET TITLE:  
**EQUIPMENT DETAILS**

SCALE:  
 AS NOTED

PROJECT NUMBER: 28737  
 SHEET NUMBER: A-8

**GENERAL NOTES:**

1. ALL WORK PRESENTED ON THESE DRAWINGS MUST BE COMPLETED BY THE CONTRACTOR UNLESS NOTED OTHERWISE. THE CONTRACTOR MUST HAVE CONSIDERABLE EXPERIENCE IN PERFORMANCE OF WORK SIMILAR TO THAT DESCRIBED HEREIN. BY ACCEPTANCE OF THIS ASSIGNMENT, THE CONTRACTOR IS ATTESTING THAT HE DOES HAVE SUFFICIENT EXPERIENCE AND ABILITY, THAT HE IS KNOWLEDGEABLE OF THE WORK TO BE PERFORMED AND THAT HE IS PROPERLY LICENSED AND PROPERLY REGISTERED TO DO THIS WORK IN THE STATE.
2. WORK SHALL BE COMPLETED IN ACCORDANCE WITH THE CURRENT STATE BUILDING CODE.
3. UNLESS SHOWN OR NOTED OTHERWISE ON THE CONTRACT DRAWINGS, OR IN THE SPECIFICATIONS, THE FOLLOWING NOTES SHALL APPLY TO THE MATERIALS LISTED HEREIN, AND TO THE PROCEDURES TO BE USED ON THIS PROJECT.
4. ALL HARDWARE ASSEMBLY MANUFACTURER'S INSTRUCTIONS SHALL BE FOLLOWED EXACTLY AND SHALL SUPERSEDE ANY CONFLICTING NOTES ENCLOSED HEREIN.
5. IT IS THE CONTRACTOR'S SOLE RESPONSIBILITY TO DETERMINE THE ERECTION PROCEDURE AND SEQUENCE TO INSURE THE SAFETY OF THE STRUCTURE AND ITS COMPONENT PARTS DURING ERECTION AND/OR FIELD MODIFICATIONS. THIS INCLUDES, BUT IS NOT LIMITED TO, THE ADDITION OF TEMPORARY BRACING, GUYS, OR TIE DOWNS THAT MAY BE NECESSARY. SUCH MATERIAL SHALL BE REMOVED AND SHALL REMAIN THE PROPERTY OF THE CONTRACTOR AFTER THE COMPLETION OF THE PROJECT.
6. ALL DIMENSIONS, ELEVATIONS, AND EXISTING CONDITIONS SHOWN ON THE DRAWINGS SHALL BE FIELD VERIFIED BY THE CONTRACTOR PRIOR TO BEGINNING ANY MATERIALS ORDERING, FABRICATION, OR CONSTRUCTION WORK ON THIS PROJECT. CONTRACTOR SHALL NOT SCALE CONTRACT DRAWINGS IN LIEU OF FIELD VERIFICATIONS. ANY DISCREPANCIES SHALL BE IMMEDIATELY BROUGHT TO THE ATTENTION OF THE OWNER AND THE OWNER'S ENGINEER. THE DISCREPANCIES MUST BE RESOLVED BEFORE THE CONTRACTOR IS TO PROCEED WITH THE WORK. THE CONTRACT DOCUMENTS DO NOT INDICATE THE METHOD OF CONSTRUCTION. THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK AND SHALL BE SOLELY RESPONSIBLE FOR ALL CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES. OBSERVATION VISITS TO THE SITE BY THE OWNER AND/OR THE ENGINEER SHALL NOT INCLUDE INSPECTION OF THE PROTECTIVE MEASURES OR THE PROCEDURES.
7. ALL MATERIALS AND EQUIPMENT FURNISHED SHALL BE NEW AND OF GOOD QUALITY, FREE FROM FAULTS AND DEFECTS, AND IN CONFORMANCE WITH THE CONTRACT DOCUMENTS. ANY AND ALL SUBSTITUTIONS MUST BE PROPERLY APPROVED AND AUTHORIZED IN WRITING BY THE OWNER AND ENGINEER PRIOR TO INSTALLATION. THE CONTRACTOR SHALL FURNISH SATISFACTORY EVIDENCE AS TO THE KIND AND QUALITY OF THE MATERIALS AND EQUIPMENT BEING SUBSTITUTED.
8. THE CONTRACTOR SHALL BE RESPONSIBLE FOR INITIATING, MAINTAINING, AND SUPERVISING ALL SAFETY PRECAUTIONS AND PROGRAMS IN CONNECTION WITH THE WORK. THE CONTRACTOR IS RESPONSIBLE FOR ENSURING THAT THIS PROJECT AND RELATED WORK COMPLIES WITH ALL APPLICABLE LOCAL, STATE, AND FEDERAL SAFETY CODES AND REGULATIONS GOVERNING THIS WORK.
9. THE CONTRACTOR SHALL COORDINATE ACCESS AND CONSTRUCTION ACTIVITY, INCLUDING WORK SCHEDULE AND MATERIALS ACCESS, WITH THE LEASING AGENT FOR APPROVAL.
10. ALL PERMITS THAT MUST BE OBTAINED ARE THE RESPONSIBILITY OF THE CONTRACTOR. THE CONTRACTOR WILL BE RESPONSIBLE FOR ABIDING BY ALL CONDITIONS AND REQUIREMENTS OF THE PERMITS.
11. 24 HOURS PRIOR TO THE BEGINNING OF ANY CONSTRUCTION, THE CONTRACTOR MUST NOTIFY THE APPLICABLE JURISDICTIONAL (STATE, COUNTY, OR CITY) ENGINEER.
12. ALL MATERIALS AND WORKMANSHIP SHALL BE WARRANTED FOR ONE YEAR FROM ACCEPTANCE DATE.
13. ALL TOWER DIMENSIONS SHALL BE VERIFIED WITH THE PLANS (LATEST REVISION) PRIOR TO COMMENCING CONSTRUCTION. NOTIFY THE ENGINEER IMMEDIATELY IF ANY DISCREPANCIES ARE DISCOVERED. THE OWNER SHALL HAVE A SET OF APPROVED PLANS AVAILABLE AT THE SITE AT ALL TIMES WHILE WORK IS BEING PERFORMED. A DESIGNATED RESPONSIBLE EMPLOYEE SHALL BE AVAILABLE FOR CONTACT BY THE GOVERNING AGENCY INSPECTORS.
14. ALL TOWER MODIFICATION WORK SHALL BE IN ACCORDANCE WITH TIA-1019-A-2012, "STANDARD FOR INSTALLATION, ALTERATION AND MAINTENANCE OF ANTENNA SUPPORTING STRUCTURES AND ANTENNAS."
15. THE CLIMBING FACILITIES, SAFETY CLIMB, AND ALL PARTS THEREOF SHALL NOT BE IMPEDED, MODIFIED, OR ALTERED WITHOUT THE EXPRESS WRITTEN APPROVAL OF THE TOWER OWNER OR ENGINEER OF RECORD.
16. ALL CONSTRUCTION MEANS AND METHODS, INCLUDING BUT NOT LIMITED TO, ERECTION PLANS, RIGGING PLANS, CLIMBING PLANS, AND RESCUE PLANS SHALL BE THE RESPONSIBILITY OF THE GENERAL CONTRACTOR. EXECUTION OF THE WORK CONTAINED HEREIN AND SHALL MEET THE ANSI/TIA-1019-A, OSHA, AND GENERAL INDUSTRY STANDARDS. ALL RIGGING PLANS SHALL ADHERE TO ANSI/TIA-1019-A, INCLUDING THE REQUIRED INVOLVEMENT OF A QUALIFIED ENGINEER FOR CLASS IV CONSTRUCTION.
17. ANTENNAS AND OTHER APPURTENANCES MAY NEED TO BE TEMPORARILY RELOCATED DURING THE INSTALLATION OF MODIFICATIONS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING ALL EXISTING AND NEW COAXIAL CABLES AND OTHER EQUIPMENT DURING CONSTRUCTION.

**STRUCTURAL STEEL NOTES:**

1. STRUCTURAL STEEL MATERIALS, FABRICATION, DETAILING, AND WORKMANSHIP SHALL CONFORM TO THE LATEST EDITION OF THE AISC SPECIFICATION FOR STRUCTURAL STEEL BUILDINGS, THE RCSC SPECIFICATION FOR STRUCTURAL JOINTS USING HIGH-STRENGTH BOLTS, AND THE CODE OF STANDARD PRACTICE FOR STEEL BUILDINGS AND BRIDGES.
  2. UNLESS OTHERWISE NOTED, ALL STRUCTURAL ELEMENTS SHALL CONFORM TO THE FOLLOWING REQUIREMENTS:
    - A. ANGLE: ASTM A36
    - B. PIPE/TUBE: ASTM A500-46
    - C. PLATE: ASTM A36 (SELF-SUPPORTING AND GUYED TOWERS)
    - D. PLATE: ASTM A572-65 (MONOPOLES)
    - E. BOLTS: ASTM A325 TYPE 1 GALVANIZED HIGH STRENGTH BOLTS
    - F. U-BOLTS: ASTM A193 GRADE B7
    - G. NUTS: ASTM A563 CARBON AND ALLOY STEEL NUTS
    - H. WASHERS: ASTM F436 HARDENED STEEL WASHERS
  3. ALL CONNECTIONS NOT FULLY DETAILED IN THESE PLANS SHALL BE DETAILED BY THE STEEL FABRICATOR IN ACCORDANCE WITH THE LATEST AISC STEEL CONSTRUCTION MANUAL.
  4. HOLES SHALL NOT BE FLAME CUT THROUGH STEEL UNLESS APPROVED BY THE ENGINEER.
  5. HOT-DIP GALVANIZE ALL ITEMS UNLESS OTHERWISE NOTED, AFTER FABRICATION WHERE PRACTICABLE. GALVANIZING: ASTM A123, ASTM, A153/A153M OR ASTM A653/A653M, G90, AS APPLICABLE. ADDITIONALLY, ALL NEW STEEL SHALL BE PAINTED TO MATCH EXISTING STEEL. CONTRACTOR SHALL OBTAIN WRITTEN PERMISSION TO PROTECT STEEL BY ANY OTHER MEANS.
  6. REPAIR DAMAGED SURFACES WITH GALVANIZING REPAIR METHOD AND PAINT CONFORMING TO ASTM A780 OR BY APPLICATION OF STICK OR THICK PASTED MATERIAL SPECIFICALLY DESIGNED FOR REPAIR OF GALVANIZING. CLEAN AREAS TO BE REPAIRED AND REMOVE SLAG FROM WELDS. HEAT SURFACES TO WHICH STICK OR PASTE MATERIAL IS APPLIED, WITH A TORCH TO A TEMPERATURE SUFFICIENT TO MELT THE METALLICS IN STICK OR PASTED; SPREAD MOLTEN MATERIAL UNIFORMLY OVER SURFACES TO BE COATED AND WIPE OFF EXCESS MATERIAL. AFTER REPAIR, STEEL SHALL BE REPAINTED TO MATCH EXISTING FINISH (IF APPLICABLE).
  7. A NUT LOCKING DEVICE SHALL BE INSTALLED ON ALL PROPOSED AND/OR REPLACED BOLTS. GALVANIZED ASTM A325 BOLTS SHALL NOT BE REUSED.
  8. ALL PROPOSED AND /OR REPLACED BOLTS SHALL BE OF SUFFICIENT LENGTH SUCH THAT THE END OF THE BOLT BE AT LEAST FLUSH WITH THE FACE OF THE NUT. IT IS NOT PERMITTED FOR THE BOLT END TO BE BELOW THE FACE OF THE NUT AFTER TIGHTENING IS COMPLETED.
- WELDING NOTES:**
1. ALL WELDING SHALL BE IN ACCORDANCE WITH THE LATEST AWS D1.1/D1.1M: "STRUCTURAL WELDING CODE - STEEL".
  2. ALL WELDING SHALL BE PERFORMED BY AWS CERTIFIED WELDERS.
  3. CONTRACTOR SHALL RETAIN AN AWS CERTIFIED WELD INSPECTOR TO PERFORM VISUAL INSPECTIONS ON FIELD WELDS. A LETTER AND REPORT SHALL BE ISSUED TO THE CONTRACTOR. CONTRACTOR SHALL SUBMIT A LETTER AND REPORT TO RAMAKER.
  4. GRIND THE SURFACE ADJACENT TO THE WELD FOR A DISTANCE OF 2" MINIMUM ALL AROUND. GRIND THE SURFACE OF THE ROD TO BE INSTALLED FOR A DISTANCE OF 2" MINIMUM ALL AROUND THE AREA TO BE WELDED. ENSURE BOTH AREAS ARE 100% FREE OF ALL GALVANIZING. SURFACES TO BE WELDED SHALL BE FREE FROM SCALE, SLAG, RUST, MOISTURE, GREASE OR ANY OTHER FOREIGN MATERIAL THAT WOULD PREVENT PROPER WELDING.
  5. DO NOT WELD IF THE TEMPERATURE OF THE STEEL IN THE VICINITY OF THE WELD AREA IS BELOW 0 DEG F. THE MINIMUM PREHEAT AND INTERPASS TEMPERATURE REQUIREMENTS SHALL COMPLY WITH SECTION 3.5.1 AND TABLE 3.2 OF THE AWS D1.1/D1.1M.
  6. DO NOT WELD ON WET OR FROST-COVERED SURFACES AND PROVIDE ADEQUATE PROTECTION FROM HIGH WINDS.
  7. USE 70 KSI LOW HYDROGEN ELECTRODES FOR ALL WELDING. POLYGONAL MONOPOLE REINFORCEMENT SHALL USE 80 KSI ELECTRODES. THE ELECTRODES SHALL BE APPROPRIATE FOR THE WELDING POSITION REQUIRED TO MAKE THE JOINT.
  8. AFTER FINAL INSPECTION, THE AREA OF THE WELDS AND ALL SURFACES DAMAGED BY WELDING OR GRINDING SHALL RECEIVE AT LEAST TWO (2) COATS OF ZRC COLD GALVANIZING COMPOUND. THIS COATING SHALL BE APPLIED BY BRUSH. OTHER APPROVED GALVANIZING COMPOUNDS SHALL CONTAIN A MINIMUM OF 95% ± PURE ZINC. THE FINISHED COATING SHALL BE A MINIMUM THICKNESS OF 3 MILS. CONTACT ZRC AT 1-800-831-3275 FOR PRODUCT INFORMATION.
  9. FOR MONOPOLE TOWERS FULL PENETRATION WELDS IN THE VICINITY OF THE BASE OF THE TOWER ARE REQUIRED TO BE 100% NDE INSPECTED BY ULTRASONIC TESTING (UT) IN ACCORDANCE WITH AWS D1.1.
  10. FOR MONOPOLE TOWERS PARTIAL PENETRATION AND FILLET WELDS IN THE VICINITY OF THE BASE OF THE TOWER ARE REQUIRED TO BE 50% NDE INSPECTED BY MAGNETIC PARTICLE (MT) IN ACCORDANCE WITH AWS D1.1.

**BOLT TIGHTENING PROCEDURE:**

1. CONNECTION BOLTS SUBJECT TO DIRECT TENSION SHALL BE INSTALLED AND TIGHTENED AS PER SECTION 8.2.1 OF THE AISC SPECIFICATION FOR STRUCTURAL JOINTS USING HIGH-STRENGTH BOLTS, LOCATED IN THE AISC MANUAL OF STEEL CONSTRUCTION. ALL OTHER BOLTED CONNECTIONS SHALL BE BROUGHT TO A SNUG TIGHT CONDITION AS DEFINED IN SECTION 8.1 OF THE SPECIFICATION.
2. PRETENSIONED JOINTS SHALL BE UTILIZE PROPERLY ALIGNED HOLES AND FASTENERS SHALL BE TIGHTENED BY ONE OF THE METHODS FROM SECTIONS 8.2.1 THROUGH 8.2.4.
  - 8.1. SNUG-TIGHTENED JOINTS
 

ALL BOLT HOLES SHALL BE ALIGNED TO PERMIT INSERTION OF THE BOLTS WITHOUT UNDUE DAMAGE TO THE THREADS. BOLTS SHALL BE PLACED IN ALL HOLES WITH WASHERS POSITIONED AS REQUIRED IN SECTION 6.1 AND NUTS THREADED TO COMPLETE THE ASSEMBLY. COMPACTING THE JOINT TO THE SNUG-TIGHT CONDITION SHALL PROGRESS SYSTEMATICALLY FROM THE MOST RIGID PART OF THE JOINT. THE SNUG TIGHTENED CONDITION IS THE TIGHTNESS THAT IS ATTAINED WITH A FEW IMPACTS OF AN IMPACT WRENCH OR THE FULL EFFORT OF AN IRONWORKER USING AN ORDINARY SPUD WRENCH TO BRING THE PLIES INTO FIRM CONTACT.

8.2.1. TURN-OF-THE-NUT PRETENSIONING  
ALL BOLTS SHALL BE INSTALLED IN ACCORDANCE WITH THE REQUIREMENTS IN SECTION 8.1, WITH WASHERS POSITIONED AS REQUIRED IN SECTION 6.2. SUBSEQUENTLY, THE NUT OR HEAD ROTATION SPECIFIED IN TABLE 8.2 SHALL BE APPLIED TO ALL FASTENER ASSEMBLIES IN THE JOINT, PROGRESSING SYSTEMATICALLY FROM THE MOST RIGID PART OF THE JOINT IN A MANNER THAT WILL MINIMIZE RELAXATION OF PREVIOUSLY PRETENSIONED BOLTS. THE PART NOT TURNED BY THE WRENCH SHALL BE PREVENTED FROM ROTATING DURING THIS OPERATION. UPON COMPLETION OF THE APPLICATION OF THE REQUIRED NUT ROTATION FOR PRETENSIONING, IT IS NOT PERMITTED TO TURN THE NUT IN THE LOOSENING DIRECTION EXCEPT FOR THE PURPOSE OF COMPLETE REMOVAL OF THE INDIVIDUAL FASTENER ASSEMBLY.

PROVIDE NUT ROTATION FROM THE SNUG-TIGHT CONDITION TO TURN-OF-NUT PRETENSIONING, USING THE CHART BELOW (PARTIAL RCSC TABLE 8.2):

BOLT LENGTHS UP TO AND INCLUDING FOUR DIAMETERS:		
1/2" BOLT	LENGTH ≤ 2.0 INCHES	+ 1/3 TURN BEYOND SNUG TIGHT
5/8" BOLT	LENGTH ≤ 2.5 INCHES	+ 1/3 TURN BEYOND SNUG TIGHT
3/4" BOLT	LENGTH ≤ 3.0 INCHES	+ 1/3 TURN BEYOND SNUG TIGHT
7/8" BOLT	LENGTH ≤ 3.5 INCHES	+ 1/3 TURN BEYOND SNUG TIGHT
1" BOLT	LENGTH ≤ 4.0 INCHES	+ 1/3 TURN BEYOND SNUG TIGHT

BOLT LENGTHS OVER FOUR DIAMETERS BUT NOT EXCEEDING EIGHT DIAMETERS:		
1/2" BOLT	LENGTH = 2.25 TO 4.0 INCHES	+ 1/2 TURN BEYOND SNUG TIGHT
5/8" BOLT	LENGTH = 2.75 TO 5.0 INCHES	+ 1/2 TURN BEYOND SNUG TIGHT
3/4" BOLT	LENGTH = 3.25 TO 6.0 INCHES	+ 1/2 TURN BEYOND SNUG TIGHT
7/8" BOLT	LENGTH = 3.75 TO 7.0 INCHES	+ 1/2 TURN BEYOND SNUG TIGHT
1" BOLT	LENGTH = 4.25 TO 8.0 INCHES	+ 1/2 TURN BEYOND SNUG TIGHT
  - 8.2.2 CALIBRATED WRENCH PRETENSIONING  
THE PRE-INSTALLATION VERIFICATION PROCEDURES IN SECTION 7 SHALL BE PERFORMED DAILY FOR THE CALIBRATION OF THE INSTALLATION WRENCH. TORQUE VALUES DETERMINED FROM TABLES OR FROM EQUATIONS THAT CLAIM TO RELATE TORQUE TO PRETENSION WITHOUT VERIFICATION SHALL NOT BE USED. ALL BOLTS SHALL BE INSTALLED IN ACCORDANCE WITH THE REQUIREMENTS IN SECTION 8.1, WITH WASHERS POSITIONED AS REQUIRED IN SECTION 6.2. SUBSEQUENTLY, THE INSTALLATION TORQUE DETERMINED IN THE PRE-INSTALLATION VERIFICATION OF THE FASTENER ASSEMBLY (SECTION 7) SHALL BE APPLIED TO ALL BOLTS IN THE JOINT, PROGRESSING SYSTEMATICALLY FROM THE MOST RIGID PART OF THE JOINT IN A MANNER THAT WILL MINIMIZE RELAXATION OF PREVIOUSLY PRETENSIONED BOLTS. THE PART NOT TURNED BY THE WRENCH SHALL BE PREVENTED FROM ROTATING DURING THIS OPERATION. APPLICATION OF THE INSTALLATION TORQUE NEED NOT PRODUCE A RELATIVE ROTATION BETWEEN THE BOLT AND NUT THAT IS GREATER THAN THE ROTATION SPECIFIED IN TABLE 8.2.
  - 8.2.3. TWIST-OFF-TYPE TENSION-CONTROL BOLT PRETENSIONING  
TWIST-OFF-TYPE TENSION CONTROL BOLT ASSEMBLIES THAT MEET THE REQUIREMENTS OF ASTM F1852 OR F2280 SHALL BE USED. ALL FASTENER ASSEMBLIES SHALL BE INSTALLED IN ACCORDANCE WITH THE REQUIREMENTS IN SECTION 8.1 WITHOUT SEVERING THE SPLINED END AND WITH WASHERS POSITIONED AS REQUIRED IN SECTION 6.2. IF A SPLINED END IS SEVERED DURING THIS OPERATION, THE FASTENER ASSEMBLY SHALL BE REMOVED AND REPLACED. SUBSEQUENTLY, ALL BOLTS IN THE JOINT SHALL BE PRETENSIONED WITH THE TWIST-OFF-TYPE TENSION-CONTROL BOLT INSTALLATION WRENCH, PROGRESSING SYSTEMATICALLY FROM THE MOST RIGID PART OF THE JOINT IN A MANNER THAT WILL MINIMIZE RELAXATION OF PREVIOUSLY PRETENSIONED BOLTS.
  - 8.2.4. DIRECT-TENSION-INDICATOR PRETENSIONING  
DIRECT TENSION INDICATORS THAT MEET THE REQUIREMENTS OF ASTM F959 SHALL BE USED. THE PRE-INSTALLATION VERIFICATION PROCEDURES SPECIFIED IN SECTION 7 SHALL DEMONSTRATE THAT, WHEN THE PRETENSION IN THE BOLT REACHES THAT REQUIRED IN TABLE 7.1, THE GAP IS NOT LESS THAN THE JOB INSPECTION GAP IN ACCORDANCE WITH ASTM F959. ALL BOLTS SHALL BE INSTALLED IN ACCORDANCE WITH THE REQUIREMENTS IN SECTION 8.1, WITH WASHERS POSITIONED AS REQUIRED IN SECTION 6.2. THE INSTALLER SHALL VERIFY THAT THE DIRECT-TENSION-INDICATOR PROTRUSIONS HAVE NOT BEEN COMPRESSED TO A GAP THAT IS LESS THAN THE JOB INSPECTION GAP DURING THIS OPERATION, AND IF THIS HAS OCCURRED, THE DIRECT TENSION INDICATOR SHALL BE REMOVED AND REPLACED. SUBSEQUENTLY, ALL BOLTS IN THE JOINT SHALL BE PRETENSIONED, PROGRESSING SYSTEMATICALLY FROM THE MOST RIGID PART OF THE JOINT IN A MANNER THAT WILL MINIMIZE RELAXATION OF PREVIOUSLY PRETENSIONED BOLTS. THE INSTALLER SHALL VERIFY THAT THE DIRECT TENSION INDICATOR PROTRUSIONS HAVE BEEN COMPRESSED TO A GAP THAT IS LESS THAN THE JOB INSPECTION GAP.



6580 SPRINT PARKWAY  
OVERLAND PARK, KANSAS 66251



855 Community Drive, Sauk City, WI 53583  
Phone: 608-643-4100 Fax: 608-643-7999  
www.Ramaker.com

**Charles Cherundolo Consulting, Inc.**

713 Clover Lane, Moscow, PA 18444  
Phone: 570-840-5084 Fax: 570-842-5592

Certification & Seal:  
I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 10/06/2017



MARK	DATE	DESCRIPTION
ISSUE PHASE	FINAL	DATE ISSUED 10/06/17
PROJECT TITLE: <b>TRANSFER STATION CT33XC522-C</b>		

PROJECT INFORMATION:  
237 GODFREY ROAD  
WESTON, CT 06883  
FAIRFIELD COUNTY

SHEET TITLE:  
**STRUCTURAL NOTES**

SCALE: NONE

PROJECT NUMBER	28737
SHEET NUMBER	S-1



NO.	TOWER MODIFICATION SCHEDULE	ELEVATIONS (FT)
1	INSTALL DOUBLE ANGLE DIAGONALS, SEE DETAIL SHEET S-3	86.7 - 80
2	INSTALL DOUBLE ANGLE DIAGONALS, SEE DETAIL SHEET S-4	50 - 40

NOTES:  
 1. ALL PROPOSED STEEL AND HARDWARE TO BE HOT-DIPPED GALVANIZED.  
 2. ALL PROPOSED BOLTS TO BE GRADE A325, UNLESS NOTED OTHERWISE.  
 3. ALL PROPOSED STEEL GRADE A36, UNLESS NOTED OTHERWISE.  
 4. DO NOT REUSE EXISTING BOLTS, INSTALL NEW BOLTS.  
 5. APPLY COLD GALVANIZING COMPOUND TO FIELD INSTALLED BOLT HOLES.  
 6. CONTRACTOR SHALL BE RESPONSIBLE FOR THE STABILITY OF THE TOWER DURING CONSTRUCTION.  
 7. SEE STRUCTURAL NOTES ON PAGE S-1

NOMINAL HOLE DIMENSIONS		
BOLT DIA.	STANDARD HOLE	SHORT SLOT
1/2	5/8	5/8 x 1 1/8
5/8	1 1/8	1 1/8 x 7/8
3/4	1 3/8	1 3/8 x 1
7/8	1 5/8	1 5/8 x 1 1/8
1	1 7/8	1 7/8 x 1 5/8


NOTE: DIMENSIONS GIVEN IN INCHES

BOLT EDGE AND SPACING		
BOLT DIA.	MIN. EDGE	SPACING
1/2	7/8	1 1/2
5/8	1 1/8	1 7/8
3/4	1 1/4	2 1/4
7/8	1 1/2	2 5/8
1	1 3/4	3

NOTE: DIMENSIONS GIVEN IN INCHES.

WORKABLE GAGES						
LEG	4	3 1/2	3	2 1/2	2	1 3/4
G	2 1/2	2	1 3/4	1 1/8	1 1/8	1

NOTE:  
 • WORKABLE GAGES GIVEN IN INCHES  
 • MATCH EXISTING WHEN APPLICABLE



MODIFIED TOWER ELEVATION ①  
 SCALE: 1" = 20'



6580 SPRINT PARKWAY  
 OVERLAND PARK, KANSAS 66251




855 Community Drive, Sauk City, WI 53583  
 Phone: 608-643-4100 Fax: 608-643-7999  
 www.Ramaker.com

**Charles Cherundolo**  
 Consulting, Inc.

713 Clover Lane, Moscow, PA 18444  
 Phone: 570-840-5084 Fax: 570-842-5592

Certification & Seal:  
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.




Signature: *James R. Skowronski* Date: 10/06/2017

MARK	DATE	DESCRIPTION
ISSUE	FINAL	DATE ISSUED 10/06/17

PROJECT TITLE:  
**TRANSFER STATION  
 CT33XC522-C**



PROJECT INFORMATION:  
 237 GODFREY ROAD  
 WESTON, CT 06883  
 FAIRFIELD COUNTY

SHEET TITLE:  
**STRUCTURAL DETAILS**





PROJECT NUMBER	28737
SHEET NUMBER	S-2





DOUBLE ANGLE BOLT STITCHING DETAIL  
 SCALE: NTS



DOUBLE ANGLE GUSSET DETAIL  
 SCALE: NTS



6580 SPRINT PARKWAY  
 OVERLAND PARK, KANSAS 66251




855 Community Drive, Sauk City, WI 53583  
 Phone: 608-643-4100 Fax: 608-643-7999  
 www.Ramaker.com

**Charles Cherundolo**  
 Consulting, Inc.

713 Clover Lane, Moscow, PA 18444  
 Phone: 570-840-5084 Fax: 570-842-5592

Certification & Seal:  
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 10/06/2017

MARK	DATE	DESCRIPTION
ISSUE	FINAL	DATE ISSUED 10/06/17



PROJECT TITLE:  
**TRANSFER STATION  
 CT33XC522-C**

PROJECT INFORMATION:  
 237 GODFREY ROAD  
 WESTON, CT 06883  
 FAIRFIELD COUNTY

SHEET TITLE:  
**STRUCTURAL DETAILS**

SCALE: NONE



PROJECT NUMBER: 28737  
 SHEET NUMBER: S-3



DOUBLE ANGLE BOLT STITCHING DETAIL

SCALE: NTS

1



DOUBLE ANGLE GUSSET W/ HORIZONTAL DETAIL

SCALE: NTS

2



6580 SPRINT PARKWAY  
 OVERLAND PARK, KANSAS 66251



855 Community Drive, Sauk City, WI 53583  
 Phone: 608-643-4100 Fax: 608-643-7999  
 www.Ramaker.com

**Charles Cherundolo**  
 Consulting, Inc.

713 Clover Lane, Moscow, PA 18444  
 Phone: 570-840-5084 Fax: 570-842-5592

Certification & Seal:  
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 10/06/2017

MARK	DATE	DESCRIPTION


ISSUE PHASE	FINAL	DATE ISSUED	10/06/17
PROJECT TITLE:	TRANSFER STATION CT33XC522-C		

PROJECT INFORMATION:  
 237 GODFREY ROAD  
 WESTON, CT 06883  
 FAIRFIELD COUNTY


SHEET TITLE:  
 STRUCTURAL DETAILS

SCALE: NONE

PROJECT NUMBER	28737
SHEET NUMBER	S-4



EQUIPMENT UTILITY & GROUNDING PLAN  
 SCALE: NTS



ANTENNA GROUNDING DETAIL  
 SCALE: NTS

GROUNDING NOTES:

1. CONTRACTOR TO ENSURE PROPER SEQUENCING OF GROUNDING AND UNDERGROUND CONDUIT INSTALLATION TO PREVENT ANY LOSS OF CONTINUITY IN THE GROUNDING SYSTEM AND/OR DAMAGE TO THE CONDUIT.
2. ALL EXTERIOR GROUND CONDUCTORS SHALL BE #2 AWG SOLID TINNED COPPER UNLESS NOTED OTHERWISE.
3. ALL GROUND CONNECTIONS BELOW GRADE SHALL BE EXOTHERMIC (CADWELD).
4. ALL GROUND CONNECTIONS ABOVE GRADE AND/OR INTERIOR SHALL BE COMPRESSION TYPE, TWO-HOLE LUGS OR DOUBLE-CRIMP "C" TAPS.
5. CONTACT AREAS WHERE CONNECTIONS ARE MADE SHALL BE PREPARED TO A BARE BRIGHT FINISH AND COATED WITH AN ANTI-OXIDATION MATERIAL BEFORE CONNECTIONS ARE MADE.
6. MAXIMUM RESISTANCE OF THE COMPLETED GROUND SYSTEM SHALL NOT EXCEED 5 OHMS.
7. WHERE GROUNDING CONNECTIONS ARE MADE TO PAINTED METAL SURFACES, PAINT SHALL BE REMOVED TO BEAR METAL TO ENSURE PROPER CONTACT AND RESTORED/PAINTED TO ORIGINAL FINISH.
8. GROUND DEPTH SHALL BE 30" MINIMUM BELOW FINISHED GRADE, OR 6" BELOW FROST LINE, WHICHEVER IS GREATER.

LEGEND:	
---	EXISTING GROUND CABLE
---	PROPOSED GROUND CABLE
▲	MECHANICAL CONNECTION
■	EXOTHERMIC CONNECTION
—E—E—E—E—E—E—	PROPOSED ELECTRIC



6580 SPRINT PARKWAY  
 OVERLAND PARK, KANSAS 66251




855 Community Drive, Sauk City, WI 53583  
 Phone: 608-643-4100 Fax: 608-643-7999  
 www.Ramaker.com

**Charles Cherundolo**  
 Consulting, Inc.

713 Clover Lane, Moscow, PA 18444  
 Phone: 570-840-5084 Fax: 570-842-5592

Certification & Seal:  
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 10/06/2017

MARK	DATE	DESCRIPTION
ISSUE	FINAL	DATE ISSUED 10/06/17


PROJECT TITLE:  
**TRANSFER STATION  
 CT33XC522-C**

PROJECT INFORMATION:  
 237 GODFREY ROAD  
 WESTON, CT 06883  
 FAIRFIELD COUNTY


SHEET TITLE:  
**EQUIPMENT UTILITY &  
 GROUNDING PLAN**

SCALE:  
 AS NOTED

PROJECT NUMBER	28737
SHEET NUMBER	E-1




**GROUNDING RISER DIAGRAM**  
 SCALE: NTS



NOTES:

1. APPLY NO-OX TO LUG AND GROUND BAR CONTACT SURFACE. DO NOT COAT INLINE LUG.
2. IF STOLEN GROUND BARS ARE ENCOUNTERED, CONTACT SPRINT CM FOR REPLACEMENT THREADED ROD KIT.

**GROUNDING CONDUCTOR INSTALLATION**  
 SCALE: NTS



**TWO-HOLE LUG**  
 SCALE: NTS



6580 SPRINT PARKWAY  
 OVERLAND PARK, KANSAS 66251




855 Community Drive, Sauk City, WI 53583  
 Phone: 608-643-4100 Fax: 608-643-7999  
 www.Ramaker.com

**Charles Cherundolo Consulting, Inc.**

713 Clover Lane, Moscow, PA 18444  
 Phone: 570-840-5084 Fax: 570-842-5592

Certification & Seal:  
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 10/06/2017

MARK	DATE	DESCRIPTION
ISSUE	FINAL	DATE ISSUED 10/06/17

PROJECT TITLE:  
**TRANSFER STATION CT33XC522-C**


PROJECT INFORMATION:  
 237 GODFREY ROAD  
 WESTON, CT 06883  
 FAIRFIELD COUNTY

SHEET TITLE:  
**GROUNDING DETAILS**

SCALE:  
 AS NOTED



PROJECT NUMBER: 28737  
 SHEET NUMBER: E-2

Copyright 2017 - Ramaker & Associates, Inc. - All Rights Reserved  
 DRAWN BY: TMS  
 CHECKED BY: KAB  
 Printed by: steves on Oct 06, 2017 - 10:16am  
 C:\Users\steves\local settings\temp\AcPublish\_1006828737 Sprint 2\_5\_Charles.dwg



A/C PANEL SCHEDULE									
VOLTAGE:	240V/120	PANEL STATUS:	EXISTING	N TO GROUND BOND:	YES				
MAIN BREAKER:	200 AMP	MODEL NUMBER:	TBD	INTERNAL TVSS:	YES				
MOUNT:	GROUND	PHASE:	1	WIRE:	3				
ENCLOSURE TYPE:	NEMA 3R	BUSS RATING:	200 AMP	GROUND BAR:	YES				
		NEUTRAL BAR:	YES						

CKT	DESCRIPTION	BREAKER AMPS	BREAKER POLES	BREAKER STATUS	PHASE A VA	PHASE B VA	BREAKER STATUS	BREAKER POLES	BREAKER AMPS	DESCRIPTION	CKT
1	SURGE ARRESTOR	20	2	ON			OFF	2	30	RECTIFIER #2	2
3											4
5	RECTIFIER #1	30	2	OFF			OFF	2	30	RECTIFIER #4	6
7											8
9	RECTIFIER #3	30	2	OFF			OFF	2	30	RECTIFIER #6	10
11											12
13	RECTIFIER #5	30	2	OFF			OFF	2	30	RECTIFIER #8	14
15											16
17	RECTIFIER #7	30	2	OFF			OFF	2	30	RECTIFIER #8	18
19											20
21	RECTIFIER #9 SPARE	30	2	OFF			ON	2	50	HVAC #2	22
23											24
25	HVAC #1	50	2	ON			ON	2	100	BTS	26
27											28
29	HVAC #3 SPARE	35	2	OFF			ON	1	20	LIGHTING	30
31											32
33	RECEPTACLE	20	1	OFF			OFF	2	40	BTS	34
35	RECEPTACLE	20	1	OFF			ON	1	20	EXT. RECEPTACLE	38
37	RECEPTACLE	20	1	OFF			ON	1	20	RECEPTACLE	40
39	RECEPTACLE	20	1	OFF			ON	1	20	RECEPTACLE	40
41	BLANK (UNUSED)	-	-	-			-	-	-	BLANK (UNUSED)	42



**5850 SPRINT PARKWAY  
OVERLAND PARK, KANSAS 66251**

---

855 Community Drive, Sauk City, WI 53583  
Phone: 608-643-4100 Fax: 608-643-7999  
www.Ramaker.com

---

**Charles Cherundolo  
Consulting, Inc.**

713 Clover Lane, Moscow, PA 18444  
Phone: 570-840-5084 Fax: 570-842-5592

---

Certification & Seal:  
I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.

*James R. Skowronski*      10/06/2017  
Signature:      Date:

---

MARK	DATE	DESCRIPTION
ISSUE	FINAL	DATE ISSUED 10/06/17
PROJECT TITLE:		
<b>TRANSFER STATION CT33XC522-C</b>		
PROJECT INFORMATION:		
237 GODFREY ROAD WESTON, CT 06883 FAIRFIELD COUNTY		
SHEET TITLE:		
<b>DC POWER DETAILS &amp; PANEL SCHEDULES</b>		
SCALE:		
AS NOTED		
PROJECT NUMBER	28737	
SHEET NUMBER	E-3	

This document contains confidential or proprietary information of Ramaker & Associates, Inc. Neither this document nor the information herein is to be reproduced, distributed, used or disclosed either in whole or in part except as authorized by Ramaker and Associates, Inc.