

Northeast Site Solutions Victoria Masse 420 Main Street #2, Sturbridge, MA 01566 860-306-2326 victoria@northeastsitesolutions.com

May 6, 2021

Members of the Siting Council Connecticut Siting Council Ten Franklin Square New Britain, CT 06051

RE: Notice of Exempt Modification 56 Norfield Rd. (Town Hall), Weston CT 06883 Latitude: 41.20236152 Longitude: -73.37961590 T-Mobile Site#: CT11118C\_NHP

Dear Ms. Bachman:

T-Mobile currently maintains six (6) antennas at the 170-foot mount on the existing 190-foot Monopole Tower, located at 56 Norfield Road, Weston, CT. The tower is owned by Crown Castle and the property is owned by the Town of Weston. T-Mobile now intends to add a 25Kw generator to an expanded 4' X 10' concrete pad within existing compound.

Planned Modifications: Ground work only-Install New: (1) GENERAC RD 25 KW AC DIESEL GENERATOR – 240-gallon double walled self-contained tank with fuel sensor. Requires two (2) 12-minute run cycles by-weekly. (1) 4'x10" Concrete pad in new 40-ft lease area.



The facility was approved by the Planning & Zoning Commission of the Town of Weston on July 26, 1999. No conditions of approval were applied that would impact this exempt modification application.

Please accept this letter as notification pursuant to Regulations of Connecticut State Agencies §16-50j-73, for construction that constitutes an exempt modification pursuant to R.C.S.A. § 16-50j-72(b)(2). In accordance with R.C.S.A. § 16-50j-73, a copy of this letter is being sent to Chris Spaulding, First Selectman for the Town of Weston, as the municipality and the property owner, James Pjura, Town of Weston Zoning Enforcement Officer, and Crown Castle is the tower owner.

The planned modifications to the facility fall squarely within those activities explicitly provided for in R.C.S; A. 16-50j-72(b)(2).

1. The proposed modifications will not result in an increase in the height of the existing structure.

2. The proposed modifications will not require the extension of the site boundary.

3. The proposed modifications will not increase noise levels at the facility by six decibels or more, or to levels that exceed state and local criteria.

4. The operation of the replacement antennas will not increase radio frequency emissions at the facility to a level at or above the Federal Communications Commission safety standard.

5. The proposed modifications will not cause a change or alteration in the physical or environmental characteristics of the site.

6. The existing structure and its foundation can support the proposed loading.

For the foregoing reasons, T-Mobile respectfully submits that the proposed modifications to the above referenced telecommunications facility constitute an exempt modification under R.C.S.A. § 16-50j-72(b)(2).

Sincerely,

Victoria Masse Mobile: 860-306-2326 Fax: 413-521-0558 Office: 420 Main Street, Unit 2, Sturbridge MA 01566 Email: victoria@northeastsitesolutions.com



Attachments

cc: Chris Spaulding, First Selectman (via email only to cspaulding@westonct.gov) Weston Town Hall 56 Norfield Road Weston, CT 06883

James Pjura, Zoning Enforcement Officer (via email only to jpjura@westonct.gov) Weston Town Hall Annex 24 School Road Weston, CT 06883

Crown Castle - as tower owner 3 Corporate Park Drive, Suite 101 Clifton Park, NY 12065

# Exhibit A

1100354



Planning & Zoning Commission

#### 8-24 Report

#### **Town of Weston Omnipoint Communications Monopole Tower**

At a regularly scheduled meeting of the Planning & Zoning Commission held on July 26, 1999, the Commission unanimously approved the plan presented by the First Selectman George Guidera and Town Administrator Roy Hill to service six communication companies plus the Town of Weston antennas for public safety and radio emergency equipment on a monopole tower, in accordance with letter dated July 1, 1999 and the standard lease agreement dated May 24, 1999, which will be modified to include maintenance of the building.

ASCEIVED FOR RECORD 400 \* 10:14 A MATTEST Caller OF

#### PLANNING & ZONING MINUTES FOR JULY 12, 1999

#### 8-24 REPORT: TOWN OF WESTON OMNIPOINT COMMUNICATION MONOPOLE TOWER

First Selectman George Guidera presented an 8-24 Report for a communication monopole tower. Roy Hill, Town Administrator was also present. Mr. Guidera stated that the Town has been working on this project for almost 4 years to replace the existing emergency services radio tower located at the rear of the Town Hall complex. The existing tower is 20 plus years old and in need of replacement. There is noticeable deterioration of the cement base and several companies have described the tower as having lasted its useful life expectancy. The Town determined that the emergency services radio tower needed to be replaced and upgrading the need for better cellular phone service in Weston. The recommendation of the Communications Tower and Antenna Advisory Committee, it was decided to replace the existing emergency services radio tower with a 190 foot monopole tower in essentially the same as the current tower.

The Omnipoint Communications, Inc. will build this 190 foot monopole tower for the Town of Weston and pay \$72,000. rent per year. After construction the tower will be leased back to Omnipoint Communications. Besides the antennas for all radio's of the Weston Fire, EMS, Highway, and Police Departments, it will also have 6 cellular/PCS (personal communications services) carriers on board. In the agreement with Omnipoint, the Town of Weston has the top of the tower allocated for the emergency services radios as appropriate by radio frequency.

An equipment building will also have to built next to the monopole tower to house the radio equipment for the police, fire and EMS, along with equipment for the six cellular/PCS carriers. The proposed building is a white brick, single story structure, approximately 77' by 23' in size.

Due to the placement of the existing underground utilities the most effective location for the new antenna is where the Police/Fire/EMS Fitness Center currently is. It is proposed that the fitness center be moved from its current location on the northeast corner of the of the firehouse to the northwest corner of the firehouse. This proposed tower will eliminate the tower planned at Timber Mill.

Mark Finely of Omnipoint introduced his staff and went over the tower in detail. He also stated that this 8-24 report if only for the tower at Town Hall and showed the coverage this tower would have for the Town.

#### PLANNING & ZONING MINUTES FOR JULY 12, 1999

#### 8-24 REPORT: TOWER CONTINUED:

Questions from the Commission:

1. Will the tower need guy wires? The tower does not need quy wires.

The architect from Omnipoint stated it is extremely safe and has to sustain winds of 100 miles per hour and is designed to crumple down into itself.

2. Address land use issues such as the parking at Town Hall and the possible loss of parking spaces for the utility building. Also the increased traffic for maintenance of the tower.

3. Questioned the use of the land on the other side of the Fire House for the location of the tower. The Town Engineer explained that this area contains a new drainage system and could not withstand the weight of a tower.

4. Omnipoint will install the utility building and the Town will pay for the equipment.

5. Questioned the construction details of the tower and concerned about icing on the platforms. Omnipoint stated that they had not had this problem.

The Commission requested that the utility building be staked for this site walk on July 17.

### PUBLIC HEARING CONT: 2 LOT RESUB. 35 SALEM ROAD MITCHELL (BARR)

Mel Barr was present, representing the owner R. Mitchell. The Commissioners walked the site and expressed concern about saving the trees and also a better site line for the driveway as the vegetation is on Town land and needs to be removed. Also discussed possible conditions for the approval including horses on Salem Road during construction, and an updated letter from the Fire Marshal.

Don Saltzman moved that the Commission close the public hearing. Seconded by Michael Widland. Vote in favor (7-0).

### PUBLIC HEARING CONT: OLIVE PHILLIPS CALVIN ROAD 4 LOT SUB. (ROMANO)

Peter Romano of Richard Bennett Associates was present for the applicant. Mr. Romano and the Commission discussed the site walk and that the parcel they saw with the foundation is not a lot that is included in the subdivision. Also a discussion followed about the access to this lot which is off the subdivision road "Quail Road". The question arose as to why this lot is not part of the subdivision. Mr. Romano stated that they received a site specific approval from Conservation for this lot. Michael Widland was concerned about two curb cuts onto Georgetown Road and a discussion about the site lines and safety of the access to Georgetown Road. The Chairman requested that the applicant incorporate the adjacent 2 acre lot into the subdivision. Peter Romano agreed to submit a new map and also walk this thru with the Conservation officer as it was included in the subdivision when it was approved by Conservation.

#### PLANNING & ZONING MINUTES FOR JULY 26, 1999

129

#### 8-24 REPORT CONT: TOWN OF WESTON OMNIPOINT COMMUNICATIONS MONOPOLE TOWER

First Selectman George Guidera, Town Administrator Roy Hill and members of Omnipoint Communications were present. The Commissioners walked the site and had the following concerns:

Don Saltzman looked at other potential locations and feels that the proposed location is the best location. Also concerned about ice buildup on 6 platforms and asked if there was a way to heat the platforms? The Omnipoint representative stated they have no technology for this and to his knowledge they have never had a problem. He felt the ground space around the tower is enough are to catch any ice. A discussion then followed regarding insurance and if the Town is covered. George Guidera stated that the Town has its own insurance and feels the Town is adequately protected. Mr. Saltzman was also concerned about having it in writing that the towers will be at Town Hall and possibly at the Landfill and not at Timbermill. A discussion followed regarding the 6 carriers on one pole.

Michael Widland clarified that the Commission is only dealing with this tower at Town Hall. Marguerite Terzian is concerned about service trucks regarding safety in the Town Hall parking lot and had considered some other location. Ms. Terzian then read the following letter from the Fire Chief, dated 7/20/99:

"I was chairman of the original tower fact-finding committee comprised of representatives from the police department, communications center, fire department, EMS, and the town engineer. When Selectman Guidera appointed a Town Tower Committee I forwarded our findings and became a member of that committee. Many hours have been spent examining in detail all feasible options for a tower location. The area behind the Communications Center is best for a number of short and long term reasons. The further away the tower is from the Communications Center, the greater the potential for problems. The Town Hall building will help screen the tower. When the Communications center expands it will have room to do so back toward the school. Locating the tower and radio building to the west side of the firehouse will make future expansion of Norfield Station impossible. At a minimum I anticipate the need for an aerial ladder truck which will require an additional bay. Parking for volunteers responding during the week is becoming very scarce. Taking space from Station 1's west side will only compound a growing problem. When a firefighter dormitory is added it will have to be at ground level, With no room on the west side the only option would be to build north into the school playing fields. It's highly unlikely the Board of Ed would approve. Marguerite, I cannot emphasize too strongly that the tower will help save lives and property by providing the emergency services the required antenna height for uninterrupted communications. It will also give residents access to emergency services while on the roads, in the woods, or at their homes when conventional telephones are

#### 8-24 REPORT TOWER CONTINUED:

unavailable or out of service. The increasing portability of cellular phones will make 24 hour a day, anywhere in Weston emergency help a reality, particularly for the elderly, infirm and handicapped. Finally, we anticipate mobile computer data exchange in our emergency vehicles for transferring vital statistics to and from the field. We have been working on this very important project for years and are available to you for help and to answer any questions". Ms. Terzian stated that this letter convinced me that the other side of the Fire House was important to the Fire Department.

Town Engineer John Conte showed a map and went over in detail the drainage implications on the other side of the Fire House.

Don Saltzman suggested Omnipoint coordinate their installation with the trench wiring for the Technology Plan for Town Hall.

Michael Widland asked if the lease been amended? The Town Administrator stated it covers at least four and Mr. Widland wants to make sure there are six carriers.

There was a discussion regarding the block house and maintenance and that it is part of Omnipoint's responsibility. The Commission expressed concern about traffic involved for the maintenance and the Town Hall parking and to consider proper signage for same. It was noted by the Town Engineer that there will no loss of parking spaces for the construction of the block house.

Don Saltzman moved that the Commission approve the plan presented by the First Selectman George Guidera and Town Administrator Roy Hill to service six communication companies plus the Town of Weston antennas for public safety and radio emergency equipment on a monopole tower, in accordance with letter dated July 1, 1999 and the standard lease agreement dated May 24, 1999, which will be modified to include maintenance of the building. Seconded by Michael Widland. Vote in favor (6-0). Paul Schultz absent.

## PUBLIC HEARING CONT: OLIVE PHILLIPS CALVIN ROAD 4 LOT SUB. (ROMANO)

This application was withdrawn.

## PUBLIC HEARING CONT: SPECIAL PERMIT APARTMENT 7 NIMROD FARM (MATTERA)

This application was withdrawn

# Exhibit B

The Assessor's office is responsible for the maintenance of records on the ownership of properties. Assessments are computed at 70% of the estimated market value of real property at the time of the last revaluation which was 2018.



Information on the Property Records for the Municipality of Weston was last updated on 4/4/2020.

## Parcel Information

| Location:                | 56 NORFIELD ROAD | Property Use:     | Public Use | Primary Use:      | Governmental Building |
|--------------------------|------------------|-------------------|------------|-------------------|-----------------------|
| Unique ID:               | E00116           | Map Block<br>Lot: | 22 6 28+31 | Acres:            | 0.00                  |
| 490 Acres:               | 0.00             | Zone:             | С          | Volume /<br>Page: | 42/ 272               |
| Developers<br>Map / Lot: | 569A,569B,3471   | Census:           |            |                   |                       |

## Value Information

|                       | Appraised Value | Assessed Value |
|-----------------------|-----------------|----------------|
| Land                  | 0               | 0              |
| Buildings             | 4,401,064       | 3,080,740      |
| Detached Outbuildings | 280,222         | 196,160        |
| Total                 | 4,681,286       | 3,276,900      |


## **Owner's Information**

#### Owner's Data

TOWN OF WESTON TOWN HALL & FIRE STATION 56 NORFIELD RRD WESTON CT 06883

## Building 1





| Category: | Public Use | Use:          | Governmental Building | GLA:        | 7,858 |
|-----------|------------|---------------|-----------------------|-------------|-------|
| Stories:  | 1.00       | Construction: | Wood Frame            | Year Built: | 1956  |

| Heating: | Hot Water                | Fuel:          | Natural Gas | Cooling<br>Percent: | 100 |
|----------|--------------------------|----------------|-------------|---------------------|-----|
| Siding:  | Wood Frame/Wood<br>Frame | Roof Material: | Slate       | Beds/Units:         | 1   |


## Special Features

## Attached Components

| Туре:       | Year Built: | Area: |
|-------------|-------------|-------|
| Brick Patio | 1956        | 400   |
| Stone Patio | 1956        | 120   |
| Open Porch  | 1956        | 45    |
| Open Porch  | 1956        | 32    |

Building 2





| Category: | Public Use               | Use:           | Governmental Building | GLA:                | 1,854 |
|-----------|--------------------------|----------------|-----------------------|---------------------|-------|
| Stories:  | 1.00                     | Construction:  | Wood Frame            | Year Built:         | 1956  |
| Heating:  | Forced Hot Air           | Fuel:          | Natural Gas           | Cooling<br>Percent: | 100   |
| Siding:   | Wood Frame/Wood<br>Frame | Roof Material: | Slate                 | Beds/Units:         | 1     |


## Special Features

## Attached Components

| Туре:          | Year Built: | Area: |
|----------------|-------------|-------|
| Frame Garage   | 1956        | 1,444 |
| Enclosed Porch | 1956        | 84    |
| Enclosed Porch | 1956        | 84    |
| Open Porch     | 1956        | 49    |

## Building 3





| Category: | Public Use | Use:          | Fire Station - Volunteer | GLA:        | 4,654 |  |
|-----------|------------|---------------|--------------------------|-------------|-------|--|
| Stories:  | 2.00       | Construction: | Wood Frame               | Year Built: | 1956  |  |

| Heating: | Hot Water                | Fuel:          | Natural Gas | Cooling<br>Percent: | 100 |
|----------|--------------------------|----------------|-------------|---------------------|-----|
| Siding:  | Wood Frame/Wood<br>Frame | Roof Material: | Asphalt     | Beds/Units:         | 1   |

## **Special Features**

## Attached Components

| Туре:           | Year Built: | Area: |
|-----------------|-------------|-------|
| Frame Garage    | 1956        | 1,120 |
| Frame Garage    | 1956        | 3,716 |
| Frame Garage    | 1956        | 592   |
| Utility Storage | 1956        | 1,156 |

## Detached Outbuildings

| Туре:             | Year Built: | Length:   | Width: | Area:  |
|-------------------|-------------|-----------|--------|--------|
| Studio Office     | 2008        | 32.00     | 24.00  | 768    |
| Average Work Shop | 2008        | 20.00     | 12.00  | 240    |
| Lights in W/PL    | 2008        | 0.00      | 0.00   | 7      |
| Gazebo            | 2008        | 0.00      | 0.00   | 100    |
| Paving            | 2008        | 25,600.00 | 0.00   | 25,600 |
| Paving            | 2008        | 9,600.00  | 0.00   | 9,600  |
| Light Poles 2     | 2008        | 0.00      | 0.00   | 1      |

## Owner History - Sales

| Owner Name     | Volume | Page | Sale Date  | Deed Type     | Valid Sale | Sale Price |
|----------------|--------|------|------------|---------------|------------|------------|
| TOWN OF WESTON | 42     | 272  | 12/21/1948 | Warranty Deed | No         | \$23,500   |

## **Building Permits**


| Permit<br>Number | Permit<br>Type | Date<br>Opened | Date<br>Closed | Permit<br>Status | Reason                                                                            |
|------------------|----------------|----------------|----------------|------------------|-----------------------------------------------------------------------------------|
| 8325             | Building       | 11/07/2019     |                | Permit<br>Issued | VERIZON REMOVE & REPLACE ANTENNAS. RADIOS, OPV BOX & CABLE                        |
| 8105             | Building       | 06/12/2018     |                | Reval            | AT&T ATENNAS                                                                      |
| 7970             |                | 09/28/2017     |                | Closed           | SPRINT ADDING 3 ANTENNAS 3 RRHS 1 HYBRID CABLE TO<br>EXSISTING EQUIPMENT ON TOWER |
| 7857             |                | 01/12/2017     |                | Closed           | SEE PERMIT                                                                        |
| 7832             |                | 10/27/2016     |                | Closed           | SEE PERMIT                                                                        |
| 7790             |                | 07/12/2016     |                | Closed           | INTERIOR RENOVATIONS TO LIBRARY                                                   |
| 7702             |                | 12/17/2015     |                | Closed           | AT&T REMOVE AND REPLCE ANTENNAS                                                   |
| 7502             |                | 01/13/2015     |                | Closed           | SEE PERMIT                                                                        |
| 7429             |                | 08/20/2014     |                | Closed           | ANTENNAS                                                                          |
| 7346             |                | 03/19/2014     |                | Closed           | SEE PERMIT                                                                        |
| 7291             |                | 11/05/2013     |                | Closed           | ELECTRICAL                                                                        |
| 6512             |                | 11/05/2008     |                | Closed           | FOOD PANTRY                                                                       |
| 6490             |                | 09/19/2008     |                | Closed           | REPLACE ROOF                                                                      |
| 5362             |                | 10/06/2003     |                | Closed           | CELL TOWER                                                                        |

Information Published With Permission From The Assessor

# Exhibit C

**T-MOBILE NORTHEAST LLC** 

SITE NUMBER: CT11118C SITE NAME: WESTON / RT-57 / NORFIELD R SITE ADDRESS: 56 NORFIELD ROAD **WESTON, CT 06883** 



THE CONTRACTOR SHALL GIVE ALL NOTICES AND COMPLY WITH ALL LAWS, ORDINANCES, RULES, REGULATIONS AND LAWFUL ORDERS OF ANY PUBLIC AUTHORITY, MUNICIPAL AND UTILITY COMPANY SPECIFICATIONS, AND LOCAL AND STATE JURISDICTIONAL CODES BEARING ON THE PERFORMANCE OF THE WORK. THE WORK PERFORMED ON THE PROJECT AND THE MATERIALS INSTALLED SHALL BE IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES. REGULATIONS, AND ORDINANCES.

THE ARCHITECT/ENGINEER HAS MADE EVERY EFFORT TO SET FORTH IN THE CONSTRUCTION AND CONTRACT DOCUMENTS THE COMPLETE SCOPE OF WORK. THE CONTRACTOR BIDDING THE JOB IS NEVERTHELESS CAUTIONED THAT MINOR OMISSIONS OR ERRORS IN THE DRAWINGS AND OR SPECIFICATIONS SHALL NOT EXCUSE SAID CONTRACTOR FROM COMPLETING THE PROJECT AND IMPROVEMENTS IN ACCORDANCE WITH THE INTENT OF THESE DOCUMENTS.

THE CONTRACTOR OR BIDDER SHALL BEAR THE RESPONSIBILITY OF NOTIFYING (IN WRITING) THE CLIENT'S REPRESENTATIVE OF ANY CONFLICTS, ERRORS, OR OMISSIONS PRIOR TO THE SUBMISSION OF CONTRACTOR'S PROPOSAL OR PERFORMANCE OF WORK

THE CONTRACTOR SHALL VISIT THE JOB SITE PRIOR TO THE SUBMISSION OF BIDS OR PERFORMING WORK TO FAMILIARIZE HIMSELF WITH THE FIELD CONDITIONS AND TO VERIFY THAT THE PROJECT CAN BE CONSTRUCTED IN ACCORDANCE WITH THE CONSTRUCTION DOCUMENTS.

THE CONTRACTOR SHALL INSTALL ALL EQUIPMENT AND MATERIALS ACCORDING TO THE MANUFACTURER'S / VENDOR'S SPECIFICATIONS UNLESS NOTED OTHERWISE OR WHERE LOCAL CODES OR ORDINANCES TAKE PRECEDENCE.

THE CONTRACTOR SHALL MAKE NECESSARY PROVISIONS TO PROTECT EXISTING IMPROVEMENTS DURING CONSTRUCTION

THE CONTRACTOR SHALL COMPLY WITH ALL PERTINENT SECTIONS OF THE BASIC STATE BUILDING CODE, LATEST EDITION. AND ALL OSHA REQUIREMENTS AS THEY APPLY TO THIS PROJEC

THE CONTRACTOR SHALL NOTIFY THE CLIENT'S REPRESENTATIVE IN WRITING WHERE A CONFLICT OCCURS ON ANY OF THE CONTRACT DOCUMENTS. THE CONTRACTOR IS NOT TO ORDER MATERIAL OR CONSTRUCT ANY PORTION OF THE WORK THAT IS IN CONFLICT UNTIL CONFLICT IS RESOLVED BY THE CLIENT'S REPRESENTATIVE.

10 THE WORK SHALL CONFORM TO THE CODES AND STANDARDS OF THE FOLLOWING AGENCIES AS FURTHER CITED HEREIN

ASTM: AMERICAN SOCIETY FOR TESTING AND MATERIALS, AS PUBLISHED IN "COMPILATION OF ASTM STANDARDS BUILDING CODES" OR LATEST EDITION

AWS: AMERICAN WELDING SOCIETY INC. AS PUBLISHED IN "STANDARD D1.1-08, STRUCTURAL WELDING CODE" OR LATEST B EDITION.

AISC: AMERICAN INSTITUTE FOR STEEL CONSTRUCTION AS PUBLISHED IN "CODE FOR STANDARD PRACTICE FOR STEEL BUILDINGS AND BRIDGES"; "SPECIFICATIONS FOR THE DESIGN, FABRICATION AND ERECTION OF STRUCTURAL STEEL FOR BUILDINGS" (LATEST EDITION)

11. BOLTING:

BOLTS SHALL BE CONFORMING TO ASTM A325 HIGH STRENGTH. HOT DIP GALVANIZED WITH ASTM A153 HEAVY HEX TYPE Δ NUTS

BOLTS SHALL BE 3/4" Ø MINIMUM (UNLESS OTHERWISE NOTED) B.

ALL CONNECTIONS SHALL BE 2 BOLTS MINIMUM. C.

12. FABRICATION:

FABRICATION OF STEEL SHALL CONFORM TO THE AISC AND AWS STANDARDS AND CODES (LATEST EDITION) Α.

ALL STRUCTURAL STEEL SHALL BE HOT-DIP GALVANIZED AFTER FABRICATION IN ACCORDANCE WITH ASTM A123 (LATEST в EDITION), UNLESS OTHERWISE NOTED.

13. ERECTION OF STEEL:

PROVIDE ALL ERECTION EQUIPMENT, BRACING, PLANKING, FIELD BOLTS, NUTS, WASHERS, DRIFT PINS, AND SIMILAR MATERIALS WHICH DO NOT FORM A PART OF THE COMPLETED CONSTRUCTION BUT ARE NECESSARY FOR ITS PROPER ERECTION.

ERECT AND ANCHOR ALL STRUCTURAL STEEL IN ACCORDANCE WITH AISC REFERENCE STANDARDS. ALL WORK SHALL BE ACCURATELY SET TO ESTABLISHED LINES AND ELEVATIONS AND RIGIDLY FASTENED IN PLACE WITH SUITABLE ATTACHMENTS TO THE CONSTRUCTION OF THE BUILDING.

TEMPORARY BRACING, GUYING AND SUPPORT SHALL BE PROVIDED TO KEEP THE STRUCTURE SAFE AND ALIGNED AT ALL TIMES DURING CONSTRUCTION, AND TO PREVENT DANGER TO PERSONS AND PROPERTY. CHECK ALL TEMPORARY LOADS AND STAY WITHIN SAFE CAPACITY OF ALL BUILDING COMPONENTS.

14. ANTENNA INSTALLATION:

A. INSTALL ANTENNAS AS INDICATED ON DRAWINGS AND CLIENT'S REPRESENTATIVE SPECIFICATIONS. B. INSTALL GALVANIZED STEEL ANTENNA MOUNTS AS INDICATED ON DRAWINGS.

INSTALL COAXIAL / FIBER CABLES AND TERMINATIONS BETWEEN ANTENNAS AND EQUIPMENT PER MANUFACTURER'S RECOMMENDATIONS. WEATHERPROOF ALL CONNECTORS BETWEEN THE ANTENNA AND EQUIPMENT PER MANUFACTURER'S REQUIREMENTS

15. ANTENNA AND COAXIAL / FIBER CABLE GROUNDING:

Α. ALL EXTERIOR #6 GREEN GROUND WIRE "DAISY CHAIN" CONNECTIONS ARE TO BE WEATHER SEALED WITH ANDREWS CONNECTOR/SPLICE WEATHERPROOFING KIT TYPE #221213 OR EQUAL.

ALL COAXIAL / FIBER CABLE GROUNDING KITS ARE TO BE INSTALLED ON STRAIGHT RUNS OF COAXIAL / FIBER CABLE (NOT WITHIN BENDS)

16 RELATED WORK, FURNISH THE FOLLOWING WORK AS SPECIFIED UNDER CONSTRUCTION DOCUMENTS, BUT COORDINATE WITH OTHER TRADES PRIOR TO BID:

- FLASHING OF OPENING INTO OUTSIDE WALLS Α.
- SEALING AND CAULKING ALL OPENINGS B.
- PAINTING C.
- CUTTING AND PATCHING D.
- 17. REQUIREMENTS OF REGULATORY AGENCIES:

A. FURNISH U.L. LISTED EQUIPMENT WHERE SUCH LABEL IS AVAILABLE. INSTALL IN CONFORMANCE WITH U.L. STANDARDS WHERE APPLICABLE.

INSTALL ANTENNA, ANTENNA CABLES, GROUNDING SYSTEM IN ACCORDANCE WITH DRAWINGS AND SPECIFICATION IN EFFECT AT PROJECT LOCATION AND RECOMMENDATIONS OF STATE AND LOCAL BUILDING CODES, AND SPECIAL CODES HAVING JURISDICTION OVER SPECIFIC PORTIONS OF WORK. THIS WORK INCLUDES BUT IS NOT LIMITED TO THE FOLLOWING:

C. TIA-EIA - 222 (LATEST EDITION). STRUCTURAL STANDARDS FOR STEEL ANTENNA TOWERS AND ANTENNA SUPPORTING STRUCTURES.

D. FAA - FEDERAL AVIATION ADMINISTRATION ADVISORY CIRCULAR AC 70/7460-IH, OBSTRUCTION MARKING AND LIGHTING.

E FCC - FEDERAL COMMUNICATIONS COMMISSION RULES AND REGULATIONS FORM 715, OBSTRUCTION MARKING AND LIGHTING SPECIFICATION FOR ANTENNA STRUCTURES AND FORM 715A, HIGH INTENSITY OBSTRUCTION LIGHTING SPECIFICATIONS FOR ANTENNA STRUCTURES.


AISC - AMERICAN INSTITUTE OF STEEL CONSTRUCTION SPECIFICATION FOR STRUCTURAL JOINTS USING ASTM A325 BOLTS (LATEST EDITION).


- NEC NATIONAL ELECTRICAL CODE ON TOWER LIGHTING KITS.
- UL UNDERWRITER'S LABORATORIES APPROVED ELECTRICAL PRODUCTS. Н


IN ALL CASES, PART 77 OF THE FAA RULES AND PARTS 17 AND 22 OF THE FCC RULES ARE APPLICABLE AND IN THE EVENT OF CONFLICT, SUPERSEDE ANY OTHER STANDARDS OR SPECIFICATIONS


J. 2018 LIFE SAFETY CODE NFPA - 101.

























#### GENERAL ELECTRICAL NOTES

1. ALL ELECTRICAL WORK SHALL CONFORM TO THE REQUIREMENTS OF THE NATIONAL ELECTRICAL CODE (NEC) AS WELL AS APPLICABLE STATE AND LOCAL CODES INCLUDING LATEST EDITIONS OF:

NFPA - NATIONAL FIRE PROTECTION ASSOCIATION

NEC - 2017 NATIONAL ELECTRICAL CODE NEMA - NATIONAL ELECTRIC

MANUFACTURERS ASSOCIATION

OSHA - OCCUPATIONAL SAFETY AND HEALTH ACT

IBC - 2015 INTERNATIONAL BUILDING CODE

2. ALL ELECTRICAL ITEMS SHALL BE U.L. APPROVED OR LISTED AND PRODUCED PER SPECIFICATION REQUIREMENTS.

3. THE ELECTRICAL WORK INCLUDES ALL LABOR AND MATERIAL DESCRIBED BY DRAWINGS AND SPECIFICATION INCLUDING INCIDENTAL WORK TO PROVIDE COMPLETE OPERATING AND APPROVED ELECTRICAL SYSTEM.

4. GENERAL CONTRACTOR SHALL PAY FEES FOR PERMITS, AND RESPONSIBLE FOR OBTAINING SAID PERMITS AND COORDINATION OF INSPECTIONS.

5. ELECTRICAL AND TELCO WIRING OUTSIDE A BUILDING AND EXPOSED TO WEATHER SHALL BE IN WATER TIGHT GALVANIZED RIGID STEEL CONDUITS OR SCHEDULE 80 PVC (AS PERMITTED BY CODE) ND WHERE REQUIRED IN LIQUID TIGHT FLEXIBLE METAL OR NONMETALLIC CONDUITS.

6. RIGID STEEL CONDUITS SHALL BE GROUNDED AT BOTH ENDS.

7. ELECTRICAL WIRING SHALL BE COPPER WITH TYPE XHHW, THWN, OR THIN INSULATION.

8. ALL EQUIPMENT LOCATED OUTSIDE SHALL HAVE NAME 3R ENCLOSURE.

9. GROUNDING SHALL COMPLY WITH NEC ART. 250.

10. GROUNDING COAX CABLE SHIELDS MINIMUM AT BOTH ENDS USING MANUFACTURES COAX CABLE GROUNDING KITS SUPPLIED BY PROJECT OWNER.

11. USE #6 COPPER STRANDED WIRE WITH GREEN COLOR INSTALLATION FOR ABOVE GRADE GROUNDING (UNLESS OTHERWISE SPECIFIED) AND #2 SOLID TINNED BARE COPPER WIRE FOR BELOW GRADE GROUNDING AS INDICATED ON THE GROUND.

12. ALL GROUND CONNECTION TO BE BURNDY HYGROUND COMPRESSION TYPE CONNECTORS OR CADWELD EXOTHERMIC WELD. DO NOT ALLOW BARE COPPER WIRE TO BE IN CONTACT WITH GALVANIZED STEEL.

13. ROUTE GROUNDING CONDUCTORS ALONG THE SHORTEST AND STRAIGHTEST PATH POSSIBLE, EXCEPT AS OTHERWISE INDICATED. GROUNDING LEADS SHOULD NEVER BE BENT AS RIGHT ANGLE. ALWAYS MAKE AT LEAST 12" RADIUS BENDS. #6 WIRE CAN BE BENT AT 6" RADIUS WHEN NECESSARY BOND ANY METER OBJECTS WITHIN 7 FEET OF PROPOSED EQUIPMENT OR CABINET TO MASTER GROUND BAR.

14. CONNECTIONS TO MGB SHALL BE ARRANGED IN THREE MAIN GROUPS: SURGE PROCEDURES (COAXIAL CABLE GROUND KITS, TELCO AND POWER PANEL GROUND); (GROUNDING ELECTRODE RING OR BUILDING STEEL); NON-SURGING OBJECTS (EGB GROUND IN RBS UNIT).

15. CONNECTIONS TO GROUND BARS SHALL BE MADE WITH TWO HOLE COMPRESSION TYPE COPPER LUGS. APPLY OXIDE INHIBITING COMPOUND TO ALL LOCATIONS.

16. APPLY OXIDE INHIBITING COMPOUND TO ALL COMPRESSION TYPE GROUND CONNECTION.

17. TEST COMPLETED GROUND SYSTEM AND RECORD RESULTS FOR PROJECT CLOSE-OUT DOCUMENTATION.

18. BOND ANY METAL OBJECTS WITHIN 7 FEET OF PROPOSED EQUIPMENT OR CABINET TO MASTER GROUND BAR.

19. VERIFY PROPOSED SERVICE UPGRADE WITH LOCAL UTILITY COMPANY PRIOR TO CONSTRUCTION.

20. EXISTING UNDERGROUND UTILITY LOCATIONS ARE UNKNOWN. GENERAL CONTRACTOR SHALL HAND-EXCAVATE TO REQUIRED SUB-GRADE DEPTH, SUFFICIENT TEST HOLES OR AS DIRECTED / REQUIRED BY CONSTRUCTION MANAGER. ALL PROPOSED UNDERGROUND UTILITY TRENCHES SHALL BE HAND-EXCAVATE AS REQUIRED. GENERAL CONTRACTOR IS RESPONSIBLE FOR ANY REQUIRED SPECIAL TEMPORARY PROTECTION OF, PHYSICAL DAMAGE TO, OR REPAIR OF EXISTING UNDERGROUND CONDUIT INCLUDING RESTORATION OF SERVICE.

21. PROVIDE SLIP JOINS WHERE CONDUITS TRANSITION FROM UNDERGROUND TO ABOVE GROUND.

#### NOTES:

DIAGRAM AS SHOWN, IS A GENERIC ROUTING SCHEMATIC BASED ON AVAILABLE INFORMATION AND MAY NOT REPRESENT ACTUAL FIELD CONDITIONS. CONTRACTOR SHOULD INSTALL THE GENERATOR, EQUIPMENT AND CONNECTIONS BASED ON VERIFIED ELECTRICAL AUDITS AND PER MANUFACTURER'S INSTALLATION GUIDELINES AS WELL AS ALL APPLICABLE LOCAL AND NATIONAL CODES AND REQUIREMENTS.

#### GROUNDING NOTES:

1. GROUNDING SHALL COMPLY WITH NEC ART. 250 AND MANUFACTURER'S RECOMMENDATIONS. TIE INTO THE EXISTING GROUNDING SYSTEM.

2. CONTRACTOR SHALL INSTALL GROUND RODS ON ALL UNDERGROUND GROUNDING RUNS LONGER THAN 10'. GROUND RODS WILL BE INSTALLED ON 20' CENTERS MAXIMUM.

3. ALL DOWN CONDUCTORS MUST GO DOWN PER NFPA 780.

4. CONTRACTOR SHALL NOTIFY THE CONSTRUCTION MANAGER WHEN THE GROUNDING SYSTEM IS COMPLETE. THE CONSTRUCTION MANAGER SHALL INSPECT THE GROUNDING SYSTEM PRIOR TO BACKFILLING.

5. CONTRACTOR MY USE EXISTING CONDUITS AND CONDUCTORS PROVIDED THEY ARE IN GOOD CONDITION AND ARE SUFFICIENTLY RATED.

UTILITY POWER

М


DISCONNECT

PROPOSED 2-1/2" CONDUIT


FROM DISCONNECT TO ATS


PROPOSED 2-1/2" CONDUIT


FROM ATS TO PANEL



SCALE: N.T.S








# Exhibit D



# **Generac RD025 Design Document**

Diesel, AC, 25kW External Fill Tank Model#7192-0 SKU#33651




The following are responsible for this project document:

Kevin Smith

SR. Engineer (770) 256-3594

| Project Design Spec Revision | 1.0                                                                                                                      | Last Date:08/23/2018 | 5/14/2018                 |
|------------------------------|--------------------------------------------------------------------------------------------------------------------------|----------------------|---------------------------|
|                              |                                                                                                                          |                      |                           |
| Final doc URL (~Dnnnnn):     |                                                                                                                          |                      |                           |
| Location                     | Use the InfoRouter Search (Advanced) putting the Document ID (nnnnn with D) to find the location of the master document. |                      | nt ID (nnnnnn without the |
| Template URL:                | http://docs.eng.t-mobile.com/InfoRouter/docs/~D423750 Slightly updated 1/2011                                            |                      |                           |

© Copyright 2011 T-Mobile USA, Inc. All rights reserved. Confidential and proprietary information of T-Mobile USA, Inc. Not for distribution outside T-Mobile.





## **Table of Contents**

| 1   | Introduction / Project Summary | 3  |
|-----|--------------------------------|----|
| 1.1 | Purpose of Project             | 3  |
| 1.2 | Feature Description            | 3  |
| 1.3 | Dimensions                     | 3  |
| 2   | Fuel Tanks                     |    |
| 3   | RXSC200A3 ATS/ Controller      | 4  |
| 3.1 | Hardware                       | 4  |
| 4   | Architecture/Alarms            | 7  |
| 4.1 | Interfaces and Alarming        | 7  |
| 5   | Regulatory Requirements        | 9  |
| 6   | Configuration/Diagrams         | 9  |
| 7   | Maintenance                    | 14 |



## **1** Introduction / Project Summary

#### 1.1 Purpose of Project


T-Mobile's nationwide cell site hardening plan is providing a refuellable backup power system capable of powering a site for a minimum of 48 hours before refueling is required. The purpose of this project is to give T-Mobile customers reliable service during power outages and provide a sufficient layer of coverage. This design document is for Generac's RD025 model#7192-0, which is a Diesel AC generator with a capacity of 25kW.

#### **1.2 Feature Description**

The Generac RD025 is a 25kW AC, diesel generator is one of the generators selected as part of the T-Mobile RFP in support of the nationwide cell site hardening plan. The RD025 has a Level 2 acoustic enclosure, 3 phase sensing, and +-0.25% digital voltage regulation. It is equipped with RS232, RS485 and canbus remote ports and Evolution control panel. It is also equipped with a automatic transfer switch, the RXSC200A3 (Automatic Transfer Switch) Controls the process of transferring commercial AC power and generator power. The RXSC200A3 is a 200Amp, switch that is programmed to perform engine test runs and also has adjustable engine run time capabilities. For RXSC200A3 Owners Manual and full feature descriptions LINK.

#### **1.3 Dimensions**

The dimensions of a level 2 Acoustic Enclosure L x W x H in inches  $103.4 \times 35 \times 91.7$ . T-Mobile requires a 36-inch radius around the generator that will cover the 18'' door swing on the generator.




Weights and Dimensions

| Unit Weight - Ibs | Unit Weight with Skid - Ibs | Dimensions (L x W x H) - in |
|-------------------|-----------------------------|-----------------------------|
| 2,123             | 2,161                       | 103.4 x 35.0 x 73.8         |

# T - Mobile-

## 2 Fuel Tanks

The RD025 has a 102.7" 240 Gallon Double-Wall UL142 Base tank to provide 98 hours of backup power at full load deployed on site. Below is the Install drawing for the 240-gallon tank for the RD025kW.



## 3 RXSC200A3 ATS/ Controller

### 3.1 Hardware

The RD025 will come with a RXSC200A3 and an Evollution controller. The sites considered for the RD025 should not have a DC power consumption above 20kW




RXSC200A3 Link

RXSC200A3 install drawing Link

Evollution controller spec sheet Link

### RD025 installation drawings and supporting documentation Link




## 3.2 RXSC200A3 Automatic Transfer Switch


The RXSC200A3 (Automatic Transfer Switch) is equiped with the following functions. Utility voltage drop-out <65%. Timer to Generator start: 10 second factory set, adjustable between 2-1500 seconds. Engine Warm up delay: 5 seconds. Standby Voltage Sensor: 65% for 5 seconds. Utility Voltage Pickup >80%. Re-Transfer Time Delay: 15 seconds. Engine Cool-Down Timer: 60 seconds. Exerciser: 5 or 12 minute adjustable weekly/by-weekly/monthly.The transfer switch can also be operated manually without power applied

## T · · Mobile ·

## **RXSC200A3** Dimensions

| Mo                 | del        | RXSC200A3   |
|--------------------|------------|-------------|
| Height<br>(in./mm) | HI         | 17.24/437.9 |
|                    | H2         | 20/508      |
| Width<br>(in./mm)  | WI         | 12.5/317.5  |
|                    | W2         | 14.6/370.8  |
| Depth (i           | in./mm)    | 7.09/180.1  |
| Weight (I          | bs./kilos) | 20/9.07     |







# 4 Architecture/Alarms

#### 4.1 Interfaces and Alarming

The generator will be monitored by external alarms, conduit and cat five cables have to be installed from the Evolution Controllers Low Voltage Box located in the Generac generator to the appropriate cell site equipment. Nokia FSEB or FSEE and in Ericsson the SAU.

At a Nokia site, this connection is at the FSEB or an FSEE module. For the wiring diagram and instructions for the FSEB click the <u>Link</u>. (The FSEE is the Nokia module that will be replacing the FSEB. For details on the FSEE contact: HQNokiaCellsiteDesigns@T-Moblie.com)

Ericsson sites will connect to the SAU module via OVP Expansion Kit for 8 External Alarms. Product number: UTOVP-ALM8EXP. For the wiring diagram and instructions for this click the <u>link</u>.

The RXSC200A3 has auxiliary contacts that will facilitate the *ATS in Emergency position* alarm and will be a Normally Closed contact. Below is the wiring schematic for this contact and it can be found in the RXSC200A3 owners manual.

#### Auxiliary Contact

See **Figure 3-4**. If desired, there is one normally-closed Auxiliary Contact (A) on the transfer switch to operate customer accessories, remote advisory lights, or remote annunciator devices. A suitable power source must be connected to the common terminal. If needed, an extra auxiliary contact can be added.




Figure 3-4. Auxiliary Contact

The auxiliary contact is normally closed when the transfer switch is in utility mode. The contacts will open when the transfer switch is in the standby power mode.

**NOTE:** Auxiliary Contact is rated 10 amps at 125 or 250 volts AC, and 0.6 amps at 125 volts DC.


#### **ACAUTION**

Equipment damage. Exceeding rated voltage and current will damage the auxiliary contacts. Verify that voltage and current are within specification before energizing this equipment. (000134a)

T-Mobile USA, INC. Confidential



T-Mobile has four relays available from the Generac controller that are user-defined. T-Mobile can have four-alarm categories and a limitless number of subcategories. T- Mobile will utilize Normally Closed (NC) dry contacts for alarms in Low Voltage Connection box in the spare outputs section. Ericsson cabinets need to be equipped with the alarm expansion kit (UTOVP-ALM8EXP) to handle external alarms.



#### Ericsson UTOVP- ALM8EXP



# UTOVP-ALM8EXPOVP Expansion Kit for 8 External AlarmsQtyProduct noDenominationUTOVP-ALM8EXPOVP Expansion Kit for 8 External Alarms1NFD30234/08OVERVOLTAGE ARRESTER/OVP-ALM 81RPM777143/01200CABLE WITH CONNECTOR/SIGNAL CABLE2



| Evolution Controller Customer |                                    |                           |
|-------------------------------|------------------------------------|---------------------------|
| Connections                   | Nokia FSEB Alarm Connections 13-24 | T-Mobile Standard Alarms  |
| NC#8-Gen Running              | NC 4110 grd 4111 pin 13            | Generator Running         |
| NC#11-Not In Auto             | NC 4110 grd 4111 pin 14            | Generator Alarm Critical  |
| NC#2-Door Alarm               | NC 4110 grd 4111 pin 15            | Generator Alarm NSI       |
| NC#5-Low Fuel                 | NC 4110 grd 4111 pin 16            | Low Fuel                  |
| RXSC200A3-Auxiliary Contacts  | NC 4110 grd 4111 pin 17            | ATS in Emergency Position |

| Evolution Controller Customer |                                |                           |
|-------------------------------|--------------------------------|---------------------------|
| Connections                   | Ericsson Alarm 8expConnections | T-Mobile Standard Alarms  |
| NC#8- Gen. Running            | NC - A5                        | Generator Running         |
| NC#11-Not In Auto             | NC - A6                        | Generator Alarm Critical  |
| NC#2-Door Alarm               | NC - A7                        | Generator Alarm NSI       |
| NC#5-Low Fuel                 | NC - A8                        | Low Fuel                  |
| RXSC200A3-Auxiliary Contacts  | NC - A9                        | ATS in Emergency Position |

# **5** Regulatory Requirements


Level 2 Acoustic Enclosure provides a noise level of 67.5dBA. It is EPA certified and meets NFPA 99 and 110 requirements(NFPA National Fire Protection Association). The RD025 generator engines is a tier 4 engine and meets the EPA final standards.

# 6 Configuration/Diagrams

The physical configuration of the Generator and the RXSC200A3 is, ATS before the PPC to ensure overcurrent protection when commercial power is restored. The RD025 and the RXSC200A3 has to be wired to Commercial AC power.




# Commercial Power Connection Points On The RXSC200A3




# T · · Mobile ·

Generac RD025 Design Document



 $\mathbf{T}$  · · Mobile ·

# **Compound Diagram:**



# **T** · · Mobile ·

# 7 Maintenance

T-Mobile is recommending preventive maintenance to be performed every 250 hours of runtime or every 12 months, whichever comes first.

T-Mobile requires this minimum service checklist for the generator engine:


- Check engine mounts and support. Tighten fasteners.
- Check all the engine hoses and clamps for proper fit, and any signs of cracking and fatigue from wear.
- Inspect all belts for signs of cracking and fatigue from wear and adjust for proper tension.
- Inspect the exhaust system for leaks, burns and wet stacking. Drain exhaust line and tighten any clamps and flange bolts.
- Inspect silencer and plumbing for leaks, cracks or any other signs of wear.
- Inspect the system for fuel, oil and coolant leaks and signs of corrosion.
- Replace water separator.
- Replace water filter/ conditioner.
- Check Anti-Freeze (Spector-Analysis).
- Check coolant level and add, if needed.
- Inspect radiator mounting for signs or wear and cracking.
- Inspect/ clean air filter and change per manufacturer specifications.
- Inspect air intakes and outlets and tighten clamps and brackets, if applicable.
- Replace fuel filter.
- Inspect the carburetor fuel injection system, fuel injection pump and choke, if equipped. Adjust to manufacturers specifications.
- Change engine oil, oil filter and record the date on the filter casing.
- Check engine heater operation, if equipped.
- Check and adjust the battery charger operations, and charge rate within the manufacturer's recommended operating specifications.

# **T** · · Mobile ·

- Inspect the battery housing, hardware connections, and cables for corrosion and wear.
- Check the battery electrolyte levels and specific gravity levels.
- Load test generator battery.
- Check, adjust and record generator output voltage, as necessary.
- Check and record the alternator charge rate.
- During inspection run the generator for 30 minutes under load. During this time, and after the engine is at full operational speed and has reached engine operating temperature; determine and record the condition of all inspection points: oil pressure, water/ coolant temperature, Fuel pressure, generator gauge, indicator operations, generator battery.
- Check the engine timing and adjust to manufacturers specifications, if necessary.
- Inspect, adjust and record governor and frequency, if necessary.
- Verify that the low fuel alarm is operational and configured correctly to trigger when the fuel tank reaches 50% of fuel tank capacity.

Check fuel level and refuel the generator during the preventive/ corrective maintenance visit.

# Exhibit E



Cut on dotted line.


### Instructions

- 1. Each Click-N-Ship® label is unique. Labels are to be used as printed and used only once. DO NOT PHOTO COPY OR ALTER LABEL.
- 2. Place your label so it does not wrap around the edge of the package.
- 3. Adhere your label to the package. A self-adhesive label is recommended. If tape or glue is used, DO NOT TAPE OVER BARCODE. Be sure all edges are secure.
- 4. To mail your package with PC Postage®, you may schedule a Package Pickup online, hand to your letter carrier, take to a Post Office™, or drop in a USPS collection box.
- 5. Mail your package on the "Ship Date" you selected when creating this label.

# Click-N-Ship® Label Record



**UNITED STATES POSTAL SERVICE** Thank you for shipping with the United States Postal Service! Check the status of your shipment on the USPS Tracking® page at usps.com



Cut on dotted line.

## Instructions

- 1. Each Click-N-Ship® label is unique. Labels are to be used as printed and used only once. DO NOT PHOTO COPY OR ALTER LABEL.
- 2. Place your label so it does not wrap around the edge of the package.
- 3. Adhere your label to the package. A self-adhesive label is recommended. If tape or glue is used, DO NOT TAPE OVER BARCODE. Be sure all edges are secure.
- 4. To mail your package with PC Postage®, you may schedule a Package Pickup online, hand to your letter carrier, take to a Post Office™, or drop in a USPS collection box.
- 5. Mail your package on the "Ship Date" you selected when creating this label.

## Click-N-Ship® Label Record



**UNITED STATES POSTAL SERVICE** Thank you for shipping with the United States Postal Service! Check the status of your shipment on the USPS Tracking® page at usps.com

# Exhibit F

#### **Deborah Chase**

| From:        | Deborah Chase                                                                  |
|--------------|--------------------------------------------------------------------------------|
| Sent:        | Wednesday, May 12, 2021 9:26 AM                                                |
| То:          | 'roborisforcouncil@gmail.com'                                                  |
| Subject:     | 1119 Summit Road, Cheshire 06801 T-Mobile EM Application (CT11352C-NHP)        |
| Attachments: | 1119 SUMMIT ROAD, CHESHIRE CT 06801 T-MOBILE EM APPLICATION (CT11352C-NHP).pdf |

Dear Chairman Oris,

Attached please find T-Mobile's exempt modification application that is being submitted to the

Connecticut Siting Council today, May 12,2021

In light of the present circumstances with Covid-19, the Council has advised that electronic notification of this filing is acceptable.

If you could kindly confirm receipt.

Thank you very much

#### **Deborah Chase**

Senior Project Coordinator & Analyst Mobile: 860-490-8839



Save a tree. Refuse.Reduce. Reuse. Recycle.

#### **Deborah Chase**

| From:        | Deborah Chase                                                                  |
|--------------|--------------------------------------------------------------------------------|
| Sent:        | Wednesday, May 12, 2021 9:25 AM                                                |
| То:          | 'wvoelker@cheshirect.org'                                                      |
| Subject:     | 1119 Summit Road, Cheshire 06801 T-Mobile EM Application (CT11352C-NHP)        |
| Attachments: | 1119 SUMMIT ROAD, CHESHIRE CT 06801 T-MOBILE EM APPLICATION (CT11352C-NHP).pdf |

Dear Mr. Voelker,

Attached please find T-Mobile's exempt modification application that is being submitted to the

Connecticut Siting Council today, May 12,2021

In light of the present circumstances with Covid-19, the Council has advised that electronic notification of this filing is acceptable.

If you could kindly confirm receipt.

Thank you very much

#### **Deborah Chase**

Senior Project Coordinator & Analyst Mobile: 860-490-8839



Save a tree. Refuse.Reduce. Reuse. Recycle.