



2255 Sewell Mill Road, Suite 130  
Marietta, Georgia 30062  
Phone: (678) 444-4463  
Fax: (678) 444-4472  
[www.infinigy.com](http://www.infinigy.com)

---

December 15, 2014

Connecticut Siting Council  
Ten Franklin Square  
New Britain, CT 06051  
Attn: Ms. Melanie Bachman, Executive Director

**Re: 2 Sunny Lane (Now renamed Allen Raymond Lane)– Westport, CT**


Dear Ms. Bachman,

On behalf of Sprint Nextel Corporation ("Sprint"), enclosed for filing are One (1) original and two (2) copies of Sprint's Notice of Exempt Modification for Proposed Modifications to an Existing Telecommunications Facility located at the above-referenced site.

I also enclose herewith a check in the amount of \$625.00 representing the fee for the Notice of Exempt Modification.

If you have any questions, please feel free to contact me.

Thank you,

By: Paul F. Sagristano  Digitally signed by Paul F. Sagristano  
DN: cn=Paul F. Sagristano, o, ou,  
email=psagristano@yahoo.com, c=US  
Date: 2014.12.15 15:07:45 -05'00'

Name: Paul F. Sagristano  
Vertical Development LLC  
20 Commercial Street  
Branford, CT 06405  
Phone – 917-841-0247  
Fax – 401-633-6202  
[psagristano@verticaldevelopmentllc.com](mailto:psagristano@verticaldevelopmentllc.com)

CC: Mr. Jim Marpe, First Selectman  
Westport Town Hall  
110 Myrtle Avenue, Room 310  
Westport CT 06880

Verizon Wireless  
c/o Sandy Carter  
99 East River Drive 9<sup>th</sup> Flr.  
East Hartford, CT 06108

**Notice of Exempt Modification**  
**2 Sunny Lane Westport, CT**  
**(Recently renamed Allen Raymond Lane)**

Sprint Nextel Corporation ("Sprint") submits this Notice of Exempt Modification to the Connecticut Siting Council ("Council") pursuant to Sections 16-50j-73 and 16-50j-72(b) of the Regulations of Connecticut State Agencies ("Regulations") in connection with Sprint's planned modification of antennas and associated equipment on an existing 130' Monopole tower located at 2 Sunny Lane in the Town of Westport. More particularly, Sprint plans to upgrade this site by adding 4G LTE technology to its facilities. The proposed modifications will not increase the tower height, extend the boundaries of the tower site, increase noise levels at the tower site boundary by six (6) decibels, or add radio frequency sending or receiving capability which increases the total radio frequency electromagnetic radiation power density measured at the tower site boundary to or above the standard adopted by the State Department of Environmental Protection pursuant to Connecticut General Statutes § 22a-162. To better meet the growing voice and data demands of its wireless customers, Sprint is upgrading their network nationwide to include the 2500 MHz band to its current 4G technology, which will provide faster service and better overall performance. Pursuant to the 2500 MHz upgrade at this site, Sprint will add antennas, install RRHs, and install related equipment to its equipment area within the fenced compound at the base of the tower.

The 130' Monopole tower located at 2 Sunny Lane in the Town of New Westport (lat. 41.1628, long. -73.3733) is owned by Verizon Towers. It is in an approx. 375 square foot section of the larger equipment building. Sprint currently has Three (3) antennas, one (1) per sector, behind which, mounted to the same pipe, are one (1) of each ALU 800 MHz RRH and ALU 1900 MHz RRH for a total of six (6) at a centerline of 120' installed on the tower and associated transmission lines (one (1) per antenna). Sprint's base station equipment is located adjacent to the base of the tower within the fenced compound. A site plan depicting this is attached. Sprint plans to add three (3) RFS

APXVTM14-C-120 antennas, one (1) per sector, all with a centerline of 120 ', and associated transmission lines (one (1) per antenna). Connected to each new RFS antenna will be one (1) ALU-TD-RRH8x20 25 RRH located behind the antenna on a pipe mount. The height of the tower will not need to be increased. Sprint also plans to install new batteries within an existing cabinet inside their existing equipment space within the existing equipment room and retrofit the existing BTS cabinet. Neither the existing Sprint room, nor the compound's boundaries will not need to be extended. Other than brief, construction-related noise, these modifications will not increase noise levels at the tower site boundary by six (6) decibels.

Sprint commissioned Centek Engineering, LLC, to perform a structural analysis of the tower to verify that it can support the proposed loading. The tower "Passes with completed modifications (69% Highest Tower Component Capacity)" (see section 1-5 pages 6 & 7 of Structural Analysis Report, December 11, 2014). The proposed modifications will not add radio frequency sending or receiving capability which increases the total radio frequency electromagnetic radiation power density measured at the tower site boundary to or above the standard adopted by the State Department of Environmental Protection pursuant to Connecticut General Statutes § 22a-162. A radio frequency emissions analysis prepared by EBI Consulting indicates that the proposed final configuration (including other carriers on the tower) will emit 61.18% of the allowable FCC established general public limit sampled at the ground level (see the 5th page of Radio Frequency Emissions Analysis Report - Evaluation of Human Exposure Potential to Non-Ionizing Emissions, December 12, 2014). Emission values for the Sprint antennas have been calculated from the sample point, which is the top of a six foot person standing at the base of the tower. Emissions values for additional carriers were based upon values listed in Connecticut Siting Council active database (see the 3rd and 4th page of Radio Frequency Emissions Analysis Report - Evaluation of Human Exposure Potential to Non-Ionizing Emissions, December 12, 2014). The information used in the report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1 (see the second page of Radio Frequency Emissions Analysis Report -

Evaluation of Human Exposure Potential to Non-Ionizing Emissions, December 12, 2014).

In conclusion, Sprint's proposed modifications do not constitute a modification subject to the Council's review because Sprint will not change the height of the tower, will not extend the boundaries of the compound, will not increase the noise levels at the site, and will not increase the total radio frequency electromagnetic radiation power density at the site to levels above applicable standards. Therefore, Sprint respectfully requests that the Council acknowledge that this Notice of Exempt Modification meets the Council's exemption criteria.

# Sprint



**PROJECT:** 2.5 EQUIPMENT DEPLOYMENT  
**SITE NAME:** WESTPORT / BAM  
**SITE CASCADE:** CT03XC382  
**SITE ADDRESS:** 2 SUNNY LANE  
 WESTPORT, CT 06880  
**SITE TYPE:** MONOPOLE TOWER  
**MARKET:** SOUTHERN CONNECTICUT

PLANS PREPARED FOR:

**Sprint**  
 6580 Sprint Parkway  
 Overland Park, Kansas 66251

PLANS PREPARED BY:

**INFINIGY** Design. Build. Deliver.  
 1033 Watervliet Shaker Rd  
 Albany, NY 12205  
 Office # (518) 690-0790  
 Fax # (518) 690-0793  
 JOB NUMBER 333-000

ENGINEERING LICENSE:

DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR PERMIT	7/28/14	SKB	0

SITE NAME:  
**WESTPORT / BAM**

SITE CASCADE:  
**CT03XC382**

SITE ADDRESS:  
**2 SUNNY LANE  
WESTPORT, CT 06880**

SHEET DESCRIPTION:  
**TITLE SHEET  
& PROJECT DATA**

SHEET NUMBER:  
**T-1**

**SITE INFORMATION**

**TOWER OWNER:**  
 VERIZON WIRELESS  
 20 ALEXANDER DR  
 WALLINGFORD, CT 06492

**LATITUDE (NAD83):**  
 41° 9' 46.0794" N  
 41.1628°

**LONGITUDE (NAD83):**  
 73° 22' 23.88" W  
 -73.3733°

**COUNTY:**  
 FAIRFIELD



**ZONING JURISDICTION:**  
 CONNECTICUT SITING COUNCIL

**ZONING DISTRICT:**  
 TBD

**POWER COMPANY:**  
 CONNECTICUT LIGHT & POWER  
 (800) 286-2000

**AAV PROVIDER:**  
 AT&T  
 (800) 246-2020

**SPRINT CM:**  
 GARY WOOD  
 PHONE: (860) 940-9168  
 gary.wood@sprint.com



**PROJECT DESCRIPTION**

SPRINT PROPOSES TO MODIFY AN EXISTING UNMANNED TELECOMMUNICATIONS FACILITY.

- INSTALL NEW EQUIPMENT INSIDE EXISTING N.V. MM BTS CABINET
- INSTALL (4) BATTERIES IN EXISTING SPRINT BATTERY CABINET
- INSTALL (3) PANEL ANTENNAS
- INSTALL (3) RRU'S TO TOWER
- INSTALL (27) JUMPER CABLES
- INSTALL (1) FIBER CABLE

THESE PLANS HAVE BEEN DEVELOPED FOR THE MODIFICATION OF AN EXISTING UNMANNED TELECOMMUNICATIONS FACILITY OWNED OR LEASED BY SPRINT IN ACCORDANCE WITH THE SCOPE OF WORK PROVIDED BY SPRINT. INFINIGY HAS INCORPORATED THIS SCOPE OF WORK IN THE PLANS. THESE PLANS ARE NOT FOR CONSTRUCTION UNLESS ACCOMPANIED BY A PASSING STRUCTURAL STABILITY ANALYSIS PREPARED BY A LICENSED STRUCTURAL ENGINEER. STRUCTURAL ANALYSIS MUST INCLUDE BOTH TOWER AND MOUNT.

**APPLICABLE CODES**

ALL WORK SHALL BE PERFORMED AND MATERIALS INSTALL IN ACCORDANCE WITH THE CURRENT EDITIONS OF THE FOLLOWING CODES AS ADOPTED BY THE LOCAL GOVERNING AUTHORITIES. NOTHING IN THESE PLANS IS TO BE CONSTRUED TO PERMIT WORK NOT CONFORMING TO THESE CODES.

1. INTERNATIONAL BUILDING CODE (2012 IBC)
2. TIA-EIA-222-G OR LATEST EDITION
3. NFPA 780 - LIGHTNING PROTECTION CODE
4. 2011 NATIONAL ELECTRIC CODE OR LATEST EDITION
5. ANY OTHER NATIONAL OR LOCAL APPLICABLE CODES, MOST RECENT EDITIONS
6. CT BUILDING CODE
7. LOCAL BUILDING CODE
8. CITY/COUNTY ORDINANCES

**DRAWING INDEX**

SHEET NO.	SHEET TITLE	REV.
T-1	TITLE SHEET & PROJECT DATA	0
SP-1	SPRINT SPECIFICATIONS	0
SP-2	SPRINT SPECIFICATIONS	0
SP-3	SPRINT SPECIFICATIONS	0
A-1	SITE PLAN	0
A-1A	EXISTING EQUIPMENT DETAILS	0
A-2	TOWER ELEVATION & CABLE PLAN	0
A-3	ANTENNA LAYOUT & MOUNTING DETAILS	0
A-4	COLOR CODING & NOTES	0
A-5	EQUIPMENT & MOUNTING DETAILS	0
A-6	CIVIL DETAILS	0
A-7	PLUMBING DIAGRAM	0
E-1	ELECTRICAL & GROUNDING PLAN	0
E-2	ELECTRICAL & GROUNDING DETAILS	0



THESE OUTLINE SPECIFICATIONS IN CONJUNCTION WITH THE SPRINT STANDARD CONSTRUCTION SPECIFICATIONS, INCLUDING CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

**SECTION 01 100 – SCOPE OF WORK**

**PART 1 – GENERAL**

- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE SPRINT CONSTRUCTION STANDARDS FOR WIRELESS SITES, CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
  - A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
  - B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.
- 1.3 PRECEDENCE: SHOULD CONFLICTS OCCUR BETWEEN THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES INCLUDING THE STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES AND THE CONSTRUCTION DRAWINGS, INFORMATION ON THE CONSTRUCTION DRAWINGS SHALL TAKE PRECEDENCE. NOTIFY SPRINT CONSTRUCTION MANAGER IF THIS OCCURS.
- 1.4 NATIONALLY RECOGNIZED CODES AND STANDARDS:
  - A. THE WORK SHALL COMPLY WITH APPLICABLE NATIONAL AND LOCAL CODES AND STANDARDS, LATEST EDITION, AND PORTIONS THEREOF, INCLUDED BUT NOT LIMITED TO THE FOLLOWING:
    - 1. GR-63-CORE NEBS REQUIREMENTS: PHYSICAL PROTECTION
    - 5. GR-78-CORE GENERIC REQUIREMENTS FOR THE PHYSICAL DESIGN AND MANUFACTURE OF TELECOMMUNICATIONS EQUIPMENT.
    - 3. GR-1089 CORE, ELECTROMAGNETIC COMPATIBILITY AND ELECTRICAL SAFETY -GENERIC CRITERIA FOR NETWORK TELECOMMUNICATIONS EQUIPMENT.
    - 4. NATIONAL FIRE PROTECTION ASSOCIATION CODES AND STANDARDS (NFPA) INCLUDING NFPA 70 (NATIONAL ELECTRICAL CODE – "NEC") AND NFPA 101 (LIFE SAFETY CODE).
    - 5. AMERICAN SOCIETY FOR TESTING OF MATERIALS (ASTM)
    - 6. INSTITUTE OF ELECTRONIC AND ELECTRICAL ENGINEERS (IEEE)
    - 7. AMERICAN CONCRETE INSTITUTE (ACI)
    - 8. AMERICAN WIRE PRODUCERS ASSOCIATION (AWPA)
    - 9. CONCRETE REINFORCING STEEL INSTITUTE (CRSI)
    - 10. AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)
    - 11. PORTLAND CEMENT ASSOCIATION (PCA)
    - 12. NATIONAL CONCRETE MASONRY ASSOCIATION (NCMA)
    - 13. BRICK INDUSTRY ASSOCIATION (BIA)
    - 14. AMERICAN WELDING SOCIETY (AWS)
    - 15. NATIONAL ROOFING CONTRACTORS ASSOCIATION (NRCA)
    - 16. SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)
    - 17. DOOR AND HARDWARE INSTITUTE (DHI)
    - 18. OCCUPATIONAL SAFETY AND HEALTH ACT (OSHA)
    - 19. APPLICABLE BUILDING CODES INCLUDING UNIFORM BUILDING CODE, SOUTHERN BUILDING CODE, BOCA, AND THE INTERNATIONAL BUILDING CODE.

**1.5 DEFINITIONS:**

- A. WORK: THE SUM OF TASKS AND RESPONSIBILITIES IDENTIFIED IN THE CONTRACT DOCUMENTS.
- B. COMPANY: SPRINT CORPORATION
- C. ENGINEER: SYNONYMOUS WITH ARCHITECT & ENGINEER AND "A&E". THE DESIGN PROFESSIONAL HAVING PROFESSIONAL RESPONSIBILITY FOR DESIGN OF THE PROJECT.
- D. CONTRACTOR: CONSTRUCTION CONTRACTOR; CONSTRUCTION VENDOR; INDIVIDUAL OR ENTITY WHO AFTER EXECUTION OF A CONTRACT IS BOUND TO ACCOMPLISH THE WORK.
- E. THIRD PARTY VENDOR OR AGENCY: A VENDOR OR AGENCY ENGAGED SEPARATELY BY THE COMPANY, A&E, OR CONTRACTOR TO PROVIDE MATERIALS OR TO ACCOMPLISH SPECIFIC TASKS RELATED TO BUT NOT INCLUDED IN THE WORK.
- F. OFCI: OWNER FURNISHED, CONTRACTOR INSTALLED EQUIPMENT.
- G. CONSTRUCTION MANAGER – ALL PROJECTS RELATED COMMUNICATION TO FLOW THROUGH SPRINT REPRESENTATIVE IN CHARGE OF PROJECT...

1.6 SITE FAMILIARITY: CONTRACTOR SHALL BE RESPONSIBLE FOR FAMILIARIZING HIMSELF WITH ALL CONTRACT DOCUMENTS, FIELD CONDITIONS AND DIMENSIONS PRIOR TO PROCEEDING WITH CONSTRUCTION. ANY DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE SPRINT CONSTRUCTION MANAGER PRIOR TO THE COMMENCEMENT OF WORK. NO COMPENSATION WILL BE AWARDED BASED ON CLAIM OF LACK OF KNOWLEDGE OR FIELD CONDITIONS.

1.7 POINT OF CONTACT: COMMUNICATION BETWEEN SPRINT AND THE CONTRACTOR SHALL FLOW THROUGH THE SINGLE SPRINT CONSTRUCTION MANAGER APPOINTED TO MANAGE THE PROJECT FOR SPRINT.

1.8 ON-SITE SUPERVISION: THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK AND SHALL BE RESPONSIBLE FOR CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES IN ACCORDANCE WITH THE CONTRACT DOCUMENTS. THE CONTRACTOR SHALL EMPLOY A COMPETENT SUPERINTENDENT WHO SHALL BE IN ATTENDANCE AT THE SITE AT ALL TIMES DURING PERFORMANCE OF THE WORK.

1.9 DRAWINGS, SPECIFICATIONS AND DETAILS REQUIRED AT JOBSITE: THE CONSTRUCTION CONTRACTOR SHALL MAINTAIN A FULL SET OF THE CONSTRUCTION DRAWINGS, STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES AND THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES AT THE JOBSITE FROM MOBILIZATION THROUGH CONSTRUCTION COMPLETION.

A. THE JOBSITE DRAWINGS, SPECIFICATIONS AND DETAILS SHALL BE CLEARLY MARKED DAILY IN RED PENCIL WITH ANY CHANGES IN CONSTRUCTION OVER WHAT IS DEPICTED IN THE DOCUMENTS. AT CONSTRUCTION COMPLETION, THIS JOBSITE MARKUP SET SHALL BE DELIVERED TO THE COMPANY OR COMPANY'S DESIGNATED REPRESENTATIVE TO BE FORWARDED TO THE COMPANY'S A&E VENDOR FOR PRODUCTION OF "AS-BUILT" DRAWINGS.

B. DETAILS ARE INTENDED TO SHOW DESIGN INTENT. MODIFICATIONS MAY BE REQUIRED TO SUIT JOB DIMENSIONS OR CONDITIONS, AND SUCH MODIFICATIONS SHALL BE INCLUDED AS PART OF THE WORK. CONTRACTOR SHALL NOTIFY SPRINT CONSTRUCTION MANAGER OF ANY VARIATIONS PRIOR TO PROCEEDING WITH THE WORK.

C. DIMENSIONS SHOWN ARE TO FINISH SURFACES UNLESS NOTED OTHERWISE. SPACING BETWEEN EQUIPMENT IS THE REQUIRED CLEARANCE. SHOULD THERE BE ANY QUESTIONS REGARDING THE CONTRACT DOCUMENTS, EXISTING CONDITIONS AND/OR DESIGN INTENT, THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING A CLARIFICATION FROM THE SPRINT CONSTRUCTION MANAGER PRIOR TO PROCEEDING WITH THE WORK.

1.10 USE OF JOB SITE: THE CONTRACTOR SHALL CONFINE ALL CONSTRUCTION AND RELATED OPERATIONS INCLUDING STAGING AND STORAGE OF MATERIALS AND EQUIPMENT, PARKING, TEMPORARY FACILITIES, AND WASTE STORAGE TO THE LEASE PARCEL UNLESS OTHERWISE PERMITTED BY THE CONTRACT DOCUMENTS.

1.11 UTILITIES SERVICES: WHERE NECESSARY TO CUT EXISTING PIPES, ELECTRICAL WIRES, CONDUITS, CABLES, ETC., OF UTILITY SERVICES, OR OF FIRE PROTECTION OR COMMUNICATIONS SYSTEMS, THEY SHALL BE CUT AND CAPPED AT SUITABLE PLACES OR WHERE SHOWN. ALL SUCH ACTIONS SHALL BE COORDINATED WITH THE UTILITY COMPANY INVOLVED.

1.12 PERMITS / FEES: WHEN REQUIRED THAT A PERMIT OR CONNECTION FEE BE PAID TO A PUBLIC UTILITY PROVIDER FOR NEW SERVICE TO THE CONSTRUCTION PROJECT, PAYMENT OF SUCH FEE SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.

1.13 CONTRACTOR SHALL TAKE ALL MEASURES AND PROVIDE ALL MATERIAL NECESSARY FOR PROTECTING EXISTING EQUIPMENT AND PROPERTY.

1.14 METHODS OF PROCEDURE (MOPS) FOR CONSTRUCTION: CONTRACTOR SHALL PERFORM WORK AS DESCRIBED IN THE FOLLOWING INSTALLATION AND COMMISSIONING MOPS.

NOTE: IN SHORT-FORM SPECIFICATIONS ON THE DRAWINGS, A/E TO INSERT LIST OF APPLICABLE MOPS INCLUDING EN-2012-001, EN-2013-002, EL-0568, AND TS-0193

1.15 USE OF ELECTRONIC PROJECT MANAGEMENT SYSTEMS:

**PART 2 – PRODUCTS (NOT USED)**

**PART 3 – EXECUTION**

3.1 TEMPORARY UTILITIES AND FACILITIES: THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL TEMPORARY UTILITIES AND FACILITIES NECESSARY EXCEPT AS OTHERWISE INDICATED IN THE CONSTRUCTION DOCUMENTS. TEMPORARY UTILITIES AND FACILITIES INCLUDE POTABLE WATER, HEAT, HVAC, ELECTRICITY, SANITARY FACILITIES, WASTE DISPOSAL FACILITIES, AND TELEPHONE/COMMUNICATION SERVICES. PROVIDE TEMPORARY UTILITIES AND FACILITIES IN ACCORDANCE WITH OSHA AND THE AUTHORITY HAVING JURISDICTION. CONTRACTOR MAY UTILIZE THE COMPANY ELECTRICAL SERVICE IN THE COMPLETION OF THE WORK WHEN IT BECOMES AVAILABLE. USE OF THE LESSORS OR SITE OWNER'S UTILITIES OR FACILITIES IS EXPRESSLY FORBIDDEN EXCEPT AS OTHERWISE ALLOWED IN THE CONTRACT DOCUMENTS.

3.2 ACCESS TO WORK: THE CONTRACTOR SHALL PROVIDE ACCESS TO THE JOB SITE FOR AUTHORIZED COMPANY PERSONNEL AND AUTHORIZED REPRESENTATIVES OF THE ARCHITECT/ENGINEER DURING ALL PHASES OF THE WORK.

3.3 TESTING: REQUIREMENTS FOR TESTING BY THIS CONTRACTOR SHALL BE AS INDICATED HEREWITH, ON THE CONSTRUCTION DRAWINGS, AND IN THE INDIVIDUAL SECTIONS OF THESE SPECIFICATIONS. SHOULD COMPANY CHOOSE TO ENGAGE ANY THIRD-PARTY TO CONDUCT ADDITIONAL TESTING, THE CONTRACTOR SHALL COOPERATE WITH AND PROVIDE A WORK AREA FOR COMPANY'S TEST AGENCY.

3.4 DIMENSIONS: VERIFY DIMENSIONS INDICATED ON DRAWINGS WITH FIELD DIMENSIONS BEFORE FABRICATION OR ORDERING OF MATERIALS. DO NOT SCALE DRAWINGS.

3.5 EXISTING CONDITIONS: NOTIFY THE SPRINT CONSTRUCTION MANAGER OF EXISTING CONDITIONS DIFFERING FROM THOSE INDICATED ON THE DRAWINGS. DO NOT REMOVE OR ALTER STRUCTURAL COMPONENTS WITHOUT PRIOR WRITTEN APPROVAL FROM THE ARCHITECT AND ENGINEER.

**SECTION 01 200 – COMPANY FURNISHED MATERIAL AND EQUIPMENT**

**PART 1 – GENERAL**

1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

**1.2 RELATED DOCUMENTS:**

- A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
- B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.

**PART 2 – PRODUCTS (NOT USED)**

**PART 3 – EXECUTION**

**3.1 RECEIPT OF MATERIAL AND EQUIPMENT:**

- A. A COMPANY FURNISHED MATERIAL AND EQUIPMENT IS IDENTIFIED ON THE RF DATA SHEET IN THE CONSTRUCTION DOCUMENTS.
- B. THE CONTRACTOR IS RESPONSIBLE FOR SPRINT PROVIDED MATERIAL AND EQUIPMENT AND UPON RECEIPT SHALL:
  - 1. ACCEPT DELIVERIES AS SHIPPED AND TAKE RECEIPT.
  - 2. VERIFY COMPLETENESS AND CONDITION OF ALL DELIVERIES.
  - 3. TAKE RESPONSIBILITY FOR EQUIPMENT AND PROVIDE INSURANCE PROTECTION AS REQUIRED IN AGREEMENT.
  - 4. RECORD ANY DEFECTS OR DAMAGES AND WITHIN TWENTY-FOUR HOURS AFTER RECEIPT, REPORT TO SPRINT OR ITS DESIGNATED PROJECT REPRESENTATIVE OF SUCH.
  - 5. PROVIDE SECURE AND NECESSARY WEATHER PROTECTED WAREHOUSING.
  - 6. COORDINATE SAFE AND SECURE TRANSPORTATION OF MATERIAL AND EQUIPMENT, DELIVERING AND OFF-LOADING FROM CONTRACTOR'S WAREHOUSE TO SITE.

**3.2 DELIVERABLES:**

- A. COMPLETE SHIPPING AND RECEIPT DOCUMENTATION IN ACCORDANCE WITH COMPANY PRACTICE.
- B. IF APPLICABLE, COMPLETE LOST/STOLEN/DAMAGED DOCUMENTATION REPORT AS NECESSARY IN ACCORDANCE WITH COMPANY PRACTICE, AND AS DIRECTED BY COMPANY.
- C. UPLOAD DOCUMENTATION INTO SPRINT SITE MANAGEMENT SYSTEM (SMS) AND/OR PROVIDE HARD COPY DOCUMENTATION AS REQUESTED.

**SECTION 01 300 – CELL SITE CONSTRUCTION CO.**

**PART 1 – GENERAL**

1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

**1.2 RELATED DOCUMENTS:**

- A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
- B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.

**1.3 NOTICE TO PROCEED**

- A. NO WORK SHALL COMMENCE PRIOR TO COMPANY'S WRITTEN NOTICE TO PROCEED AND THE ISSUANCE OF THE WORK ORDER.
- B. UPON RECEIVING NOTICE TO PROCEED, CONTRACTOR SHALL FULLY PERFORM ALL WORK NECESSARY TO PROVIDE SPRINT WITH AN OPERATIONAL WIRELESS FACILITY.

**PART 2 – PRODUCTS (NOT USED)**

**PART 3 – EXECUTION**

**3.1 FUNCTIONAL REQUIREMENTS:**

- A. THE ACTIVITIES DESCRIBED IN THIS PARAGRAPH REPRESENT MINIMUM ACTIONS AND PROCESSES REQUIRED TO SUCCESSFULLY COMPLETE THE WORK. THE ACTIVITIES DESCRIBED ARE NOT EXHAUSTIVE, AND CONTRACTOR SHALL TAKE ANY AND ALL ACTIONS AS NECESSARY TO SUCCESSFULLY COMPLETE THE CONSTRUCTION OF A FULLY FUNCTIONING WIRELESS FACILITY AT THE SITE IN ACCORDANCE WITH COMPANY PROCESSES.
- B. SUBMIT SPECIFIC DOCUMENTATION AS INDICATED HEREIN, AND OBTAIN REQUIRED APPROVALS WHILE THE WORK IS BEING PERFORMED.
- C. MANAGE AND CONDUCT ALL FIELD CONSTRUCTION SERVICE RELATED ACTIVITIES
- D. PROVIDE CONSTRUCTION ACTIVITIES TO THE EXTENT REQUIRED BY THE CONTRACT DOCUMENTS, INCLUDING BUT NOT LIMITED TO THE FOLLOWING:

PLANS PREPARED FOR:



PLANS PREPARED BY:



ENGINEERING LICENSE:



DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR PERMIT	7/28/14	SKB	0

SITE NAME:

WESTPORT / BAM

SITE CASCADE:

CT03XC382

SITE ADDRESS:

2 SUNNY LANE  
WESTPORT, CT 06880

SHEET DESCRIPTION:

SPRINT SPECIFICATIONS

SHEET NUMBER:

SP-1



**CONTINUE FROM SP-2**

- 7. VERIFICATION DOCUMENTED WITH THE ANTENNA CHECKLIST REPORT, BY A&E, SITE DEVELOPMENT REP, OR RF REP.
  - 8. FINAL INSPECTION CHECKLIST AND HANDOFF WALK (HOC). SIGNED FORM SHOWING ACCEPTANCE BY FIELD OPS IS TO BE UPLOADED INTO SMS.
  - 9. COAX SWEEP AND FIBER TESTING DOCUMENTS SUBMITTED VIA SMS FOR RF APPROVAL.
  - 10. SCAN-ABLE BARCODE PHOTOGRAPHS OF TOWER TOP AND INACCESSIBLE SERIALIZED EQUIPMENT
  - 11. ALL AVAILABLE JURISDICTIONAL INFORMATION
  - 12. PDF SCAN OF REDLINES PRODUCED IN FIELD
- C. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN SITE INSPECTION ACTIVITIES AND/OR AS A RESULT OF TESTING.
- D. CONSTRUCTION INSPECTIONS AND CORRECTIVE MEASURES SHALL BE DOCUMENTED BY THE CONTRACTOR WITH WRITTEN REPORTS AND PHOTOGRAPHS. PHOTOGRAPHS MUST BE DIGITAL AND OF SUFFICIENT QUALITY TO CLEARLY SHOW THE SITE CONSTRUCTION. PHOTOGRAPHS MUST CLEARLY IDENTIFY THE PHOTOGRAPHED ITEM AND BE LABELED WITH THE SITE CASCADE NUMBER, SITE NAME, DESCRIPTION, AND DATE.
- 3.4 DELIVERABLES: TEST AND INSPECTION REPORTS AND CLOSEOUT DOCUMENTATION SHALL BE UPLOADED TO THE SMS AND/OR FORWARDED TO SPRINT FOR INCLUSION INTO THE PERMANENT SITE FILES.
- A. THE FOLLOWING TEST AND INSPECTION REPORTS SHALL BE PROVIDED AS APPLICABLE.
- 1. CONCRETE MIX AND CYLINDER BREAK REPORTS.
  - 2. STRUCTURAL BACKFILL COMPACTION REPORTS.
  - 3. SITE RESISTANCE TO EARTH TEST.
  - 4. ANTENNA AZIMUTH AND DOWN TILT VERIFICATION
  - 5. TOWER ERECTION INSPECTIONS AND MEASUREMENTS DOCUMENTING TOWER INSTALLED PER SUPPLIER'S REQUIREMENTS AND THE APPLICABLE SECTIONS HEREIN.
  - 6. COAX CABLE SWEEP TESTS PER COMPANY'S "ANTENNA LINE ACCEPTANCE STANDARDS".
- B. REQUIRED CLOSEOUT DOCUMENTATION INCLUDES THE FOLLOWING;
- 1. TEST WELLS AND TRENCHES: PHOTOGRAPHS OF ALL TEST WELLS; PHOTOGRAPHS SHOWING ALL OPEN EXCAVATIONS AND TRENCHING PRIOR TO BACKFILLING SHOWING A TAPE MEASURE VISIBLE IN THE EXCAVATIONS INDICATING DEPTH.
  - 2. CONDUITS, CONDUCTORS AND GROUNDING: PHOTOGRAPHS SHOWING TYPICAL INSTALLATION OF CONDUCTORS AND CONNECTORS; PHOTOGRAPHS SHOWING TYPICAL BEND RADIUS OF INSTALLED GROUND WIRES AND GROUND ROD SPACING;
  - 3. CONCRETE FORMS AND REINFORCING: CONCRETE FORMING AT TOWER AND EQUIPMENT/SHELTER PAD/FOUNDATIONS - PHOTOGRAPHS SHOWING ALL REINFORCING STEEL, UTILITY AND CONDUIT STUB OUTS; PHOTOGRAPHS SHOWING CONCRETE POUR OF SHELTER SLAB/FOUNDATION, TOWER FOUNDATION AND GUY ANCHORS WITH VIBRATOR IN USE; PHOTOGRAPHS SHOWING EACH ANCHOR ON GUYED TOWERS, BEFORE CONCRETE POUR.
  - 4. TOWER, ANTENNAS AND MAINLINE: INSPECTION AND PHOTOGRAPHS OF SECTION STACKING; INSPECTION AND PHOTOGRAPHS OF PLATFORM COMPONENT ATTACHMENT POINTS; PHOTOGRAPHS OF TOWER TOP GROUNDING; PHOTOS OF TOWER COAX LINE COLOR CODING AT THE TOP AND AT GROUND LEVEL; INSPECTION AND PHOTOGRAPHS OF OPERATIONAL OF TOWER LIGHTING, AND PLACEMENT OF FAA REGISTRATION SIGN; PHOTOGRAPHS SHOWING ADDITIONAL GROUNDING POINTS FOR TOWERS GREATER THAN 200 FEET.; PHOTOS OF ANTENNA GROUND BAR, EQUIPMENT GROUND BAR, AND MASTER GROUND BAR; PHOTOS OF GPS ANTENNA(S); PHOTOS OF EACH SECTOR OF ANTENNAS; ONE PHOTOGRAPH LOOKING AT THE SECTOR AND ONE FROM BEHIND SHOWING THE PROJECTED COVERAGE AREA; PHOTOS OF COAX WEATHERPROOFING - TOP AND BOTTOM; PHOTOS OF COAX GROUNDING--TOP AND BOTTOM; PHOTOS OF ANTENNA AND MAST GROUNDING; PHOTOS OF COAX CABLE ENTRY INTO SHELTER; PHOTOS OF PLATFORM MECHANICAL CONNECTIONS TO TOWER/MONOPOLE.
  - 5. ROOF TOPS: PRE-CONSTRUCTION AND POST-CONSTRUCTION VISUAL INSPECTION AND PHOTOGRAPHS OF THE ROOF AND INTERIOR TO DETERMINE AND DOCUMENT CONDITIONS; ROOF TOP CONSTRUCTION INSPECTIONS AS REQUIRED BY THE JURISDICTION; PHOTOGRAPHS OF CABLE TRAY AND/OR ICE BRIDGE; PHOTOGRAPHS OF DOGHOUSE/CABLE EXIT FROM ROOF;
  - 6. SITE LAYOUT - PHOTOGRAPHS OF THE OVERALL COMPOUND, INCLUDING EQUIPMENT PLATFORM FROM ALL FOUR CORNERS.
  - 7. FINISHED UTILITIES: CLOSE-UP PHOTOGRAPHS OF THE PPC BREAKER PANEL; CLOSE-UP PHOTOGRAPH OF THE INSIDE OF THE TELCO PANEL AND NIU; CLOSE-UP PHOTOGRAPH OF THE POWER METER AND DISCONNECT; PHOTOS OF POWER AND TELCO ENTRANCE TO COMPANY ENCLOSURE; PHOTOGRAPHS AT METER BOX AND/OR FACILITY DISTRIBUTION PANEL.
  - 8. REQUIRED MATERIALS CERTIFICATIONS: CONCRETE MIX DESIGNS; MILL CERTIFICATION FOR ALL REINFORCING AND STRUCTURAL STEEL; AND ASPHALT PAVING MIX DESIGN.
  - 9. ANY AND ALL SUBMITTALS BY THE JURISDICTION OR COMPANY.

**SECTION 01 400 - SUBMITTALS & TESTS**

**PART 1 - GENERAL**

- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
  - A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
  - B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.

**PART 2 - PRODUCTS (NOT USED)**

**PART 3 - EXECUTION**

- 3.1 WEEKLY REPORTS:
  - A. CONTRACTOR SHALL PROVIDE SPRINT WITH WEEKLY REPORTS SHOWING PROJECT STATUS. THIS STATUS REPORT FORMAT WILL BE PROVIDED TO THE CONTRACTOR BY SPRINT. THE REPORT WILL CONTAIN SITE ID NUMBER, THE MILESTONES FOR EACH SITE, INCLUDING THE BASELINE DATE, ESTIMATED COMPLETION DATE AND ACTUAL COMPLETION DATE.
  - B. REPORT INFORMATION WILL BE TRANSMITTED TO SPRINT VIA ELECTRONIC MEANS AS REQUIRED. THIS INFORMATION WILL PROVIDE A BASIS FOR PROGRESS MONITORING AND PAYMENT.
- 3.2 PROJECT CONFERENCE CALLS:
  - A. SPRINT MAY HOLD WEEKLY PROJECT CONFERENCE CALLS. CONTRACTOR WILL BE REQUIRED TO COMMUNICATE SITE STATUS, MILESTONE COMPLETIONS AND UPCOMING MILESTONE PROJECTIONS, AND ANSWER ANY OTHER SITE STATUS QUESTIONS AS NECESSARY.
- 3.3 PROJECT TRACKING IN SMS:
  - A. CONTRACTOR SHALL PROVIDE SCHEDULE UPDATES AND PROJECTIONS IN THE SMS SYSTEM ON A WEEKLY BASIS.
- 3.4 ADDITIONAL REPORTING:
  - A. ADDITIONAL OR ALTERNATE REPORTING REQUIREMENTS MAY BE ADDED TO THE REPORT AS DETERMINED TO BE REASONABLY NECESSARY BY COMPANY.
- 3.5 PROJECT PHOTOGRAPHS:
  - A. FILE DIGITAL PHOTOGRAPHS OF COMPLETED SITE IN JPEG FORMAT IN THE SMS PHOTO LIBRARY FOR THE RESPECTIVE SITE. PHOTOGRAPHS SHALL BE CLEARLY LABELED WITH SITE NUMBER, NAME AND DESCRIPTION, AND SHALL INCLUDE AT A MINIMUM THE FOLLOWING AS APPLICABLE:
    - 1. SHELTER AND TOWER OVERVIEW.
    - 2. TOWER FOUNDATION(S) - FORMS AND STEEL BEFORE POUR (EACH ANCHOR ON GUYED TOWERS).
    - 3. TOWER FOUNDATION(S) POUR WITH VIBRATOR IN USE (EACH ANCHOR ON GUYED TOWERS).
    - 4. TOWER STEEL AS BEING INSTALLED INTO HOLE (SHOW ANCHOR STEEL ON GUYED TOWERS).
    - 5. PHOTOS OF TOWER SECTION STACKING.
    - 6. CONCRETE TESTING / SAMPLES.
    - 7. PLACING OF ANCHOR BOLTS IN TOWER FOUNDATION.
    - 8. BUILDING/WATER TANK FROM ROAD FOR TENANT IMPROVEMENTS OR COMMENTS.
    - 9. SHELTER FOUNDATION--FORMS AND STEEL BEFORE POURING.
    - 10. SHELTER FOUNDATION POUR WITH VIBRATOR IN USE.
    - 11. COAX CABLE ENTRY INTO SHELTER.
    - 12. PLATFORM MECHANICAL CONNECTIONS TO TOWER/MONOPOLE.
    - 13. ROOFTOP PRE AND POST CONSTRUCTION PHOTOS TO INCLUDE PENETRATIONS AND INTERIOR CEILING.
    - 14. PHOTOS OF TOWER TOP COAX LINE COLOR CODING AND COLOR CODING AT GROUND LEVEL.
    - 15. PHOTOS OF ALL APPROPRIATE COMPANY OR REGULATORY SIGNAGE.
    - 16. PHOTOS OF EQUIPMENT BOLT DOWN INSIDE SHELTER.
    - 17. POWER AND TELCO ENTRANCE TO COMPANY ENCLOSURE AND POWER AND TELCO SUPPLY LOCATIONS INCLUDING METER/DISCONNECT.
    - 18. ELECTRICAL TRENCH(S) WITH ELECTRICAL / CONDUIT BEFORE BACKFILL.
    - 19. ELECTRICAL TRENCH(S) WITH FOIL-BACKED TAPE BEFORE FURTHER BACKFILL.
    - 20. TELCO TRENCH WITH TELEPHONE / CONDUIT BEFORE BACKFILL.
    - 21. TELCO TRENCH WITH FOIL-BACKED TAPE BEFORE FURTHER BACKFILL.
    - 22. SHELTER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADII).
    - 23. TOWER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADII).

- 24. FENCE GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADII).
  - 25. ALL BTS GROUND CONNECTIONS.
  - 26. ALL GROUND TEST WELLS.
  - 27. ANTENNA GROUND BAR AND EQUIPMENT GROUND BAR.
  - 28. ADDITIONAL GROUNDING POINTS ON TOWERS ABOVE 200'.
  - 29. HVAC UNITS INCLUDING CONDENSERS ON SPLIT SYSTEMS.
  - 30. GPS ANTENNAS.
  - 31. CABLE TRAY AND/OR WAVEGUIDE BRIDGE.
  - 32. DOGHOUSE/CABLE EXIT FROM ROOF.
  - 33. EACH SECTOR OF ANTENNAS; ONE PHOTOGRAPH LOOKING AT THE SECTOR AND ONE FROM BEHIND SHOWING THE PROJECTED COVERAGE AREA.
  - 34. MASTER BUS BAR.
  - 35. TELCO BOARD AND NIU.
  - 36. ELECTRICAL DISTRIBUTION WALL.
  - 37. CABLE ENTRY WITH SURGE SUPPRESSION.
  - 38. ENTRANCE TO EQUIPMENT ROOM.
  - 39. COAX WEATHERPROOFING--TOP AND BOTTOM OF TOWER.
  - 40. COAX GROUNDING -TOP AND BOTTOM OF TOWER.
  - 41. ANTENNA AND MAST GROUNDING.
  - 42. LANDSCAPING - WHERE APPLICABLE.
- 3.6 FINAL PROJECT ACCEPTANCE: COMPLETE ALL REQUIRED REPORTING TASKS PER CONTRACT, CONTRACT DOCUMENTS OR THE SPRINT INTEGRATED CONSTRUCTION STANDARDS FOR WIRELESS SITES AND UPLOAD INTO SITERRA.

PLANS PREPARED FOR:



PLANS PREPARED BY:



ENGINEERING LICENSE:



DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:	DESCRIPTION	DATE	BY	REV
ISSUED FOR PERMIT		7/25/14	SKB	0

SITE NAME:  
**WESTPORT / BAM**

SITE CASCADE:  
**CT03XC382**


SITE ADDRESS:  
**2 SUNNY LANE  
WESTPORT, CT 06880**

SHEET DESCRIPTION:  
**SPRINT SPECIFICATIONS**

SHEET NUMBER:  
**SP-3**




INFORMATION CONTAINED WITHIN DRAWINGS ARE BASED ON PROVIDED INFORMATION AND ARE NOT THE RESULT OF A FIELD SURVEY.



OVERALL SITE PLAN

SCALE: 24"x36" SHEET 1" = 10'-0"  
SCALE: 11"x17" SHEET 1" = 20'-0"



SPRINT EQUIPMENT PLAN

SCALE: 24"x36" SHEET 1" = 2'-0"  
SCALE: 11"x17" SHEET 1" = 4'-0"

PLANS PREPARED FOR:

6580 Sprint Parkway  
Overland Park, Kansas 66251

PLANS PREPARED BY:

Design. Build. Deliver.  
1033 Watervliet Shaker Rd  
Albany, NY 12205  
Office # (518) 690-0790  
Fax # (518) 690-0793  
JOB NUMBER 333-000

ENGINEERING LICENSE:

DRAWING NOTICE:  
THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR PERMIT	7/28/14	SKB	0

SITE NAME:  
**WESTPORT / BAM**

SITE CASCADE:  
**CT03XC382**

SITE ADDRESS:  
**2 SUNNY LANE  
WESTPORT, CT 06880**


SHEET DESCRIPTION:  
**SITE PLAN**

SHEET NUMBER:  
**A-1**

EXISTING SPRINT  
N.V. MMBS CABINET

EXISTING SPRINT  
BATTERY CABINET

EXISTING  
EQUIPMENT RACK



CABINET LINEUP PHOTO

SCALE: AS NOTED 1

INSTALL (4) BATTERIES IN  
EXISTING BATTERY CABINET




EXISTING BATTERY (TYP.  
OF (4) PER STALL)


EXISTING SPRINT  
BATTERY CABINET

EXISTING BATTERY CABINET PHOTO

SCALE: AS NOTED 2




TOP VIEW




FRONT VIEW

MANUFACTURER: ALU  
MODEL: 9927

N.V. MMBS CABINET



TOP VIEW



REAR VIEW

MANUFACTURER: ALU  
MODEL: BCZ4

BATTERY CABINET

EXISTING EQUIPMENT DETAIL

SCALE: AS NOTED 3

PLANS PREPARED FOR:

**Sprint**  
6580 Sprint Parkway  
Overland Park, Kansas 66251

PLANS PREPARED BY:

**INFINIGY** Design. Build. Deliver.  
1033 Watervliet Shaker Rd  
Albany, NY 12205  
Office # (518) 690-0790  
Fax # (518) 690-0793  
JOB NUMBER 333-000

ENGINEERING LICENSE:



DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR PERMIT	7/28/14	SKB	0

SITE NAME:

**WESTPORT / BAM**

SITE CASCADE:

**CT03XC382**

SITE ADDRESS:

**2 SUNNY LANE  
WESTPORT, CT 06880**

SHEET DESCRIPTION:


**SITE PLAN**

SHEET NUMBER:


**A-1A**

**NOTE:**  
 INFINIGY ENGINEERING HAS NOT EVALUATED THE EXISTING STRUCTURE FOR THIS SITE, AND ASSUMES NO RESPONSIBILITY FOR ITS STRUCTURAL INTEGRITY. REFER TO STRUCTURAL ANALYSIS BY OTHERS PRIOR TO ANY CONSTRUCTION.

**NOTE:**  
 SEE DETAIL 2 ON A-3 FOR ANTENNA LAYOUT



EXISTING CLEARWIRE PANEL ANTENNA



ALPHA

INSTALL (1) SPRINT 2.5 ANTENNA EACH SECTOR (SEE SHEET A-5 DETAIL 3)

INSTALL (1) RRU-2.5 EACH SECTOR (SEE SHEET A-5 DETAILS 1)

EXISTING CLEARWIRE PANEL ANTENNA

INSTALL (1) RRU-2.5 EACH SECTOR (SEE SHEET A-5 DETAILS 1)

INSTALL (1) SPRINT 2.5 ANTENNA EACH SECTOR (SEE SHEET A-5 DETAIL 3)

EXISTING CLEARWIRE PANEL ANTENNA

INSTALL (1) RRU-2.5 EACH SECTOR (SEE SHEET A-5 DETAILS 1)

INSTALL (1) SPRINT 2.5 ANTENNA EACH SECTOR (SEE SHEET A-5 DETAIL 3)



BETA



GAMMA

PLANS PREPARED FOR:



6580 Sprint Parkway  
 Overland Park, Kansas 66251

PLANS PREPARED BY:



1033 Watervliet Shaker Rd  
 Albany, NY 12205  
 Office # (518) 690-0790  
 Fax # (518) 690-0793

JOB NUMBER 333-000

ENGINEERING LICENSE:



DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR PERMIT	7/28/14	SKB	0

SITE NAME:

WESTPORT / BAM

SITE CASCADE:

CT03XC382

SITE ADDRESS:


2 SUNNY LANE  
 WESTPORT, CT 06880

SHEET DESCRIPTION:

TOWER ELEVATION  
 & CABLE PLAN

SHEET NUMBER:


A-2



EXISTING ANTENNA & RRU LAYOUT

NO SCALE


1



FINAL ANTENNA LAYOUT

NO SCALE

2



**NOTE:** CONTRACTOR TO POSITION RRU ON MOUNT BEHIND ANTENNA SUCH THAT THE RRU DOES NOT INTERFERE WITH THE EXISTING MOUNTING HARDWARE.

**NOTE:** SPARE DC CABLES ARE COILED UP ON NV RRHS AT SPRINT ARRAY. THESE ARE TO BE USED TO POWER UP THE 2.5 RRHS AND TIED INTO EXISTING DC BREAKERS INSIDE THE FIBER JUNCTION BOX LOCATED AT EQUIPMENT.

**NOTE:** THE DIAGRAM IS FOR CONCEPTUAL PURPOSES ONLY. CONTRACTOR IS TO REFER TO PASSING STRUCTURAL ANALYSIS FOR ANTENNA AND RRU MOUNTING DETAILS.

- NOTES:**
- CUT DC CONDUCTORS TO LENGTH.
  - COIL FIBER CABLE AND SECURE AT SIDE OF RRU.
  - DO NOT EXCEED BEND RADIUS.

DETAIL NOT USED

NO SCALE

3

TYPICAL ANTENNA & RRU MOUNTING DETAILS

NO SCALE

4

PLANS PREPARED FOR:



PLANS PREPARED BY:



ENGINEERING LICENSE:



DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR PERMIT	7/28/14	SKB	0

SITE NAME:

WESTPORT / BAM

SITE CASCADE:

CT03XC382

SITE ADDRESS:

2 SUNNY LANE  
WESTPORT, CT 06880

SHEET DESCRIPTION:

ANTENNA LAYOUT  
& MOUNTING DETAILS

SHEET NUMBER:


A-3

NV CABLES				
BAND	INDICATOR	PORT	COLOR	
800-1	YEL GRN	NV-1	GRN	
1900-1	YEL RED	NV-2	BLU	
1900-2	YEL BRN	NV-3	BRN	
1900-3	YEL BLU	NV-4	WHT	
1900-4	YEL SLT	NV-5	SLT	
800-2	YEL ORG	NV-6	SLT	
SPARE	YEL WHT	NV-7	WHT	
2500	YEL ORG	NV-8	ORG	

HYBRID	
HYBRID	COLOR
1	GRN
2	BLU
3	BRN
4	WHT
5	SLT
6	SLT
7	WHT
8	ORG

2.5 Band		
2500 Radio 1	COLOR	
YEL WHT	GRN	
YEL WHT	BLU	
YEL WHT	BRN	
YEL WHT	WHT	
YEL WHT	RED	
YEL WHT	SLT	
YEL WHT	SLT	
YEL WHT	ORG	

Figure 1: Antenna Orientation






NOTES:

- ALL CABLES SHALL BE MARKED WITH 2" WIDE, UV STABILIZED, UL APPROVED TAPE.
- THE FIRST RING SHALL BE CLOSEST TO THE END OF THE CABLE AND SPACED APPROXIMATELY 2" FROM THE END CONNECTOR, WEATHERPROOFING, OR BREAK-OUT CYLINDER. THERE SHALL BE A 1" SPACE BETWEEN EACH RING FOR THE CABLE IDENTIFIER, AND NO SPACES BETWEEN THE FREQUENCY BANDS.
- A 2" GAP SHALL SEPARATE THE CABLE COLOR CODE FROM THE FREQUENCY COLOR CODE. THE 2" COLOR RINGS FOR THE FREQUENCY CODE SHALL BE PLACED NEXT TO EACH OTHER WITH NO SPACES.
- THE 2" COLORED TAPE(S) SHALL EACH BE WRAPPED A MINIMUM OF 3 TIMES AROUND THE INDIVIDUAL CABLES, AND THE TAPE SHALL BE KEPT IN THE SAME LOCATION AS MUCH AS POSSIBLE.
- SITES WITH MORE THAN FOUR (4) SECTORS WILL REQUIRE ADDITIONAL RINGS FOR EACH SECTOR, FOLLOWING THE PATTERN. HIGH CAPACITY SITES WILL USE THE NEXT COLOR IN THE SEQUENCE FOR ADDITIONAL CABLES IN EACH SECTOR.
- HYBRID FIBER CABLE SHALL BE SECTOR IDENTIFIED INSIDE THE CABINET ON FREQUENCY BUNDLES, ON THE SEALTITE, ON THE MAIN LINE UPON EXIT OF SEALTITE, AND BEFORE AND AFTER THE BREAKOUT UNIT (MEDUSA), AS WELL AS BEFORE AND AFTER ANY ENTRANCE OR EXIT.
- HFC "MAIN TRUNK" WILL NOT BE MARKED WITH THE FREQUENCY CODES, AS IT CONTAINS ALL FREQUENCIES.
- INDIVIDUAL POWER PAIRS AND FIBER BUNDLES SHALL BE LABELED WITH BOTH THE CABLE AND FREQUENCY.

Sector	Cable	First Ring	Second Ring	Third Ring
1 Alpha	1	Green	No Tape	No Tape
	2	Blue	No Tape	No Tape
	3	White	No Tape	No Tape
	4	White	No Tape	No Tape
	5	Red	No Tape	No Tape
	6	Grey	No Tape	No Tape
	7	Purple	No Tape	No Tape
	8	Orange	No Tape	No Tape
2 Beta	1	Green	Green	No Tape
	2	Blue	Blue	No Tape
	3	White	White	No Tape
	4	White	White	No Tape
	5	Red	Red	No Tape
	6	Grey	Grey	No Tape
	7	Purple	Purple	No Tape
	8	Orange	Orange	No Tape
3 Gamma	1	Green	Green	Green
	2	Blue	Blue	Blue
	3	White	White	White
	4	White	White	White
	5	Red	Red	Red
	6	Grey	Grey	Grey
	7	Purple	Purple	Purple
	8	Orange	Orange	Orange

NV		
FREQUENCY	INDICATOR	ID
800-1	YEL	GRN
1900-1	YEL	RED
1900-2	YEL	BRN
1900-3	YEL	BLU
1900-4	YEL	SLT
800-1	YEL	ORG
RESERVED	YEL	WHT
RESERVED	YEL	WHT

2.5		
FREQUENCY	INDICATOR	ID
2500 -1	YEL	WHT GRN
2500 -2	YEL	WHT RED
2500 -3	YEL	WHT BRN
2500 -4	YEL	WHT BLU
2500 -5	YEL	WHT SLT
2500 -6	YEL	WHT ORG
2500 -7	YEL	WHT WHT
2500 -8	YEL	WHT WHT



PLANS PREPARED FOR:

6580 Sprint Parkway  
Overland Park, Kansas 66251

PLANS PREPARED BY:

1033 Watervliet Shaker Rd  
Albany, NY 12205  
Office # (518) 690-0790  
Fax # (518) 690-0793  
JOB NUMBER 333-000

ENGINEERING LICENSE:

DRAWING NOTICE:  
THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:	DESCRIPTION	DATE	BY	REV
ISSUED FOR PERMIT		7/28/14	SKB	0

SITE NAME:  
**WESTPORT / BAM**

SITE CASCADE:  
**CT03XC382**




SITE ADDRESS:  
**2 SUNNY LANE  
WESTPORT, CT 06880**

SHEET DESCRIPTION:  
**COLOR CODING AND NOTES**

SHEET NUMBER:  
**A-4**


RRU: ALCATEL LUCENT TD-RRH8X20

COLOR: LIGHT GREY  
WEIGHT: 70 LBS.



**NOTES**

COMPLY WITH MANUFACTURERS INSTRUCTIONS TO ENSURE THAT ALL RRU'S RECEIVE ELECTRICAL POWER WITHIN 24 HOURS OF BEING REMOVED FROM THE MANUFACTURER'S PACKAGING. DO NOT OPEN RRU PACKAGES IN THE RAIN.



PLANS PREPARED FOR:

6580 Sprint Parkway  
Overland Park, Kansas 66251

PLANS PREPARED BY:

Design. Build. Deliver.

1033 Watervliet Shaker Rd  
Albany, NY 12205  
Office # (518) 690-0790  
Fax # (518) 690-0793

JOB NUMBER 333-000

ENGINEERING LICENSE:

2.5 RRU'S

NO SCALE

1




EXISTING MMBS WITH 2.5 EQUIPMENT

NO SCALE

2

**ANTENNA RFS APXVTM14-C-120**

RADOME MATERIAL: ASA  
RADOME COLOR: LIGHT GREY  
DIMENSIONS, HxWxD.in(mim): 56.3"x12.6"x6.3" (1430x320x160mm)  
WEIGHT: 52.9 lbs  
CONNECTORS: (8) 4.1/9.5 DIN FEMALE  
(1) NF - CALIBRATION CONNECTOR



**INFINIGY ESTIMATES**

* Riser Cable Length Estimate		Units
At Grade	182	Feet
Vertical Rise	120	Feet
At Sprint Centerline	0	Feet
<b>Sub-Total</b>	<b>302</b>	<b>Feet</b>
15% Buffer	46	Feet
<b>Total</b>	<b>348</b>	<b>Feet</b>

ABOVE LENGTH IS AN ESTIMATE AND SHOULD BE VERIFIED IN FIELD PRIOR TO ORDERING MATERIALS.

** Hybrid/Fiber Jumper Length Estimate		Units
From Connector To RRU	7	Feet

ABOVE LENGTH IS AN ESTIMATE AND SHOULD BE VERIFIED IN FIELD PRIOR TO ORDERING MATERIALS.

Coax Jumper Length Estimate		Units
From RRU to Antenna	5	Feet

ABOVE LENGTH IS AN ESTIMATE AND SHOULD BE VERIFIED IN FIELD PRIOR TO ORDERING MATERIALS.

**NOTE:**  
\* & \*\*: REFERENCE SHEET A-6, DETAIL 1 FOR CORRESPONDING PART NUMBERS.

**CABLE LENGTH NOTE:**  
APPROXIMATE LENGTH OF NEW CABLE IS SHOWN IN CHART ON THIS SHEET. CONTRACTOR TO CONFIRM EXACT CABLE LENGTH REQUIRED PRIOR TO ORDERING MATERIALS.

DRAWING NOTICE:  
THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR PERMIT	7/28/14	SKB	0

SITE NAME:  
**WESTPORT / BAM**

SITE CASCADE:  
**CT03XC382**

SITE ADDRESS:  
**2 SUNNY LANE  
WESTPORT, CT 06880**

SHEET DESCRIPTION:  
**EQUIPMENT & MOUNTING DETAILS**

SHEET NUMBER:  
**A-5**

2.5 ANTENNA

NO SCALE

3


EQUIPMENT MOUNTING DETAIL

NO SCALE

4

**RFS HYBRIFLEX RISER CABLE SCHEDULE**



Fiber Only (Existing DC Power)	Hybrid cable MN: HB058-M12-050F 12x multi-mode fiber pairs, Top: Outdoor protected connectors, Bottom: LC Connectors, 5/8 cable, 50 ft	50 ft
	MN: HB058-M12-075F	75 ft
	MN: HB058-M12-100F	100 ft
	MN: HB058-M12-125F	125 ft
	MN: HB058-M12-150F	150 ft
	MN: HB058-M12-175F	175 ft
	MN: HB058-M12-200F	200 ft
8 AWG Power	Hybrid cable MN: HB114-08U3M12-050F 3x 8 AWG power pairs, 12x multi-mode fiber pairs, Outdoor rated connectors & LC Connectors, 1 1/4 cable, 50 ft	50 ft
	MN: HB114-08U3M12-075F	75 ft
	MN: HB114-08U3M12-100F	100 ft
	MN: HB114-08U3M12-125F	125 ft
	MN: HB114-08U3M12-150F	150 ft
	MN: HB114-08U3M12-175F	175 ft
	MN: HB114-08U3M12-200F	200 ft
6 AWG Power	Hybrid cable MN: HB114-13U3M12-225F 3x 6 AWG power pair, 12x multi-mode fiber pairs, Outdoor rated connectors & LC Connectors, 1 1/4 cable, 225 ft	225 ft
	MN: HB114-13U3M12-250F	250 ft
	MN: HB114-13U3M12-275F	275 ft
	MN: HB114-13U3M12-300F	300 ft
4 AWG Power	Hybrid cable MN: HB114-21U3M12-325F 3x 4 AWG power pair, 12x multi-mode fiber pairs, Outdoor rated connectors & LC Connectors, 1 1/4 cable, 325 ft	325 ft
	MN: HB114-21U3M12-350F	350 ft
	MN: HB114-21U3M12-375F	375 ft



SEE NOTE THIS SHEET

**RFS HYBRIFLEX JUMPER CABLE SCHEDULE**

Fiber Only	Hybrid Jumper cable MN: HBF012-M3-5F1 5 ft, 3x multi-mode fiber pairs, Outdoor & LC connectors, 1/2 cable	5 ft
	MN: HBF012-M3-10F1	10 ft
	MN: HBF012-M3-15F1	15 ft
	MN: HBF012-M3-20F1	20 ft
	MN: HBF012-M3-25F1	25 ft
8 AWG Power	Hybrid Jumper cable MN: HBF058-08U1M3-5F1 5 ft, 3x 8 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 5/8 cable	5 ft
	MN: HBF058-08U1M3-10F1	10 ft
	MN: HBF058-08U1M3-15F1	15 ft
	MN: HBF058-08U1M3-20F1	20 ft
	MN: HBF058-08U1M3-25F1	25 ft
6 AWG Power	Hybrid Jumper cable MN: HBF058-13U1M3-5F1 5 ft, 3x 6 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 5/8 cable	5 ft
	MN: HBF058-13U1M3-10F1	10 ft
	MN: HBF058-13U1M3-15F1	15 ft
	MN: HBF058-13U1M3-20F1	20 ft
	MN: HBF058-13U1M3-25F1	25 ft
4 AWG Power	Hybrid Jumper cable MN: HBF078-21U1M3-5F1 5 ft, 3x 4 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 7/8 cable	5 ft
	MN: HBF078-21U1M3-10F1	10 ft
	MN: HBF078-21U1M3-15F1	15 ft
	MN: HBF078-21U1M3-20F1	20 ft
	MN: HBF078-21U1M3-25F1	25 ft




NOTE: SPRINT CM TO CONFIRM HYBRID OR FIBER RISER CABLE AND HYBRID OR FIBER JUMPER CABLE MODEL NUMBERS IF HYBRID CABLES ARE REQUIRED BEFORE PREPARING BOM.

NOTE: ABOVE CABLE SELECTION BASED ON INFINIGY ESTIMATED LENGTH OF RISER CABLE. SPRINT RF DESIGN DEPICTS SITE SHOULD BE A "FIBER ONLY" RISER CABLE. BASED ON CABLE LENGTH, A HYBRID CABLE WAS SELECTED FROM THE ABOVE. CONTRACTOR TO COORDINATE WITH SPRINT CONSTRUCTION MANAGER PRIOR TO ORDERING MATERIALS.

**2.5 CABLE CROSS SECTION DATA**

NO SCALE 1



**FIBER JUNCTION BOX PENETRATION**

NO SCALE 2

**IMPORTANT!!** Line up white markings on jumper and riser IP-MPO connectors and slide the riser connector to the jumper connector. Push the white mark on the jumper connector flush against the red seal on the riser connector.




**IMPORTANT!!** Rotate the bayonet housing clock wise until you hear a click sound (means a good connection is in place).



INFORMATION BASED ON PROVIDED INFORMATION FROM ALCATEL-LUCENT 2.5 GHz UPGRADE INSTALLATION GUIDE.

**HYBRIFLEX RISER/JUMPER CONNECTION DETAIL**

NO SCALE 3



**2.5 HYBRID RISER CABLE (FIBER AND DC FEEDERS)**

**FIBER ONLY RISER CABLE**

**TRUNK LINE DETAIL (TYP.)**

NO SCALE 4

PLANS PREPARED FOR:



PLANS PREPARED BY:



ENGINEERING LICENSE:



DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR PERMIT	7/28/14	SKB	0

SITE NAME:

WESTPORT / BAM

SITE CASCADE:

CT03XC382

SITE ADDRESS:


2 SUNNY LANE  
WESTPORT, CT 06880

SHEET DESCRIPTION:


CIVIL DETAILS

SHEET NUMBER:


A-6



ALU 2.5 ALU SCENARIO 1



RAN WIRING DIAGRAM



RF 2.5 ALU SCENARIO 1



DRAWING NOTICE:  
 THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:	DESCRIPTION	DATE	BY	REV
ISSUED FOR PERMIT		7/28/14	SKB	0

SITE NAME:  
**WESTPORT / BAM**

SITE CASCADE:  
**CT03XC382**

SITE ADDRESS:  
 2 SUNNY LANE  
 WESTPORT, CT 06880

SHEET DESCRIPTION:  
**PLUMBING DIAGRAM**

SHEET NUMBER:  
**A-7**



DRAWING NOTICE:  
THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR PERMIT	7/28/14	SKB	0

SITE NAME:  
**WESTPORT / BAM**



SITE CASCADE:  
**CT03XC382**

SITE ADDRESS:  
**2 SUNNY LANE  
WESTPORT, CT 06880**

SHEET DESCRIPTION:  
**ELECTRICAL &  
GROUNDING PLAN**

SHEET NUMBER:  
**E-1**


**PLAN NOT USED** NO SCALE 1



**TYPICAL ANTENNA GROUNDING PLAN** **TYPICAL EQUIPMENT GROUNDING PLAN (ELEVATION)**

NO SCALE 2 NO SCALE 3

**NOTES**  
 CG SHALL REFERENCE ALL SPECS FOR "CONNECTING THE POWER SUPPLY" OF THE NEW INSTALLATION DOCUMENTS, FOR ALL CONNECTION SPECIFICATIONS.



CIRCUIT SCHEDULE			
NO	FROM	TO	CONFIGURATION
①	UTILITY SOURCE	METER/DISCONNECT	EXISTING
②	METER/DISCONNECT	TRANSFER & LOAD CENTER	EXISTING
③	TRANSFER & LOAD CENTER	GENERATOR RECEPTACLE	EXISTING
④	TRANSFER & LOAD CENTER	EXISTING SPRINT BATTERY CABINET	EXISTING
⑤	TRANSFER & LOAD CENTER	EXISTING SPRINT MMBS CABINET	EXISTING

PLANS PREPARED FOR:  
**Sprint**  
 6580 Sprint Parkway  
 Overland Park, Kansas 66251

PLANS PREPARED BY:  
**INFINIGY** Design. Build. Deliver.  
 1033 Watervliet Shaker Rd  
 Albany, NY 12205  
 Office # (518) 690-0790  
 Fax # (518) 690-0793  
 JOB NUMBER 333-000

ENGINEERING LICENSE:  
  
 JOHN S. STEVENS  
 No. 24705  
 LICENSED PROFESSIONAL ENGINEER

DRAWING NOTICE:  
 THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:			
DESCRIPTION	DATE	BY	REV
ISSUED FOR PERMIT	7/28/14	SKB	0

SITE NAME:  
**WESTPORT / BAM**

SITE CASCADE:  
**CT03XC382**


SITE ADDRESS:  
**2 SUNNY LANE  
 WESTPORT, CT 06880**

SHEET DESCRIPTION:  
**ELECTRICAL &  
 GROUNDING DETAILS**

SHEET NUMBER:  
**E-2**

**ELECTRICAL ONE-LINE DIAGRAM**

NO SCALE 1




**NOTES**  
 1. APPLY NO-OX TO LUG AND BAR CONTACT SURFACE. DO NOT COAT INLINE LUG.  
 2. IF STOLEN GROUND BARS ARE ENCOUNTERED, CONTACT SPRINT CM FOR REPLACEMENT THREADED ROD KIT.

**INSTALLATION OF GROUNDING CONDUCTOR TO GROUNDING BAR**

NO SCALE


2



**TWO HOLE LUG**

NO SCALE

3



**GROUNDING RISER DIAGRAM**

NO SCALE

4

## *Structural Analysis Report*

*130-ft Existing EEl Monopole*

*Proposed Sprint  
Antenna Upgrade*

*Sprint Site Ref: CT03XC382*

*Verizon Site Ref: Cranbury*

*2 Sunny Lane  
Westport, CT*

*Centek Project No. 14033.012*

*Date: November 11, 2014*



**Prepared for:**  
*Sprint Nextel  
8 Airline Drive, Suite 105  
Albany, NY 12205*

## **Table of Contents**

### **SECTION 1 - REPORT**

- INTRODUCTION.
- ANTENNA AND APPURTENANCE SUMMARY.
- PRIMARY ASSUMPTIONS USED IN THE ANALYSIS.
- ANALYSIS.
- TOWER LOADING.
- TOWER CAPACITY.
- FOUNDATION AND ANCHORS.
- CONCLUSION.

### **SECTION 2 – CONDITIONS & SOFTWARE**

- STANDARD ENGINEERING CONDITIONS.
- GENERAL DESCRIPTION OF STRUCTURAL ANALYSIS PROGRAM.

### **SECTION 3 – CALCULATIONS**

- tnxTower INPUT/OUTPUT SUMMARY.
- tnxTower DETAILED OUTPUT.
- ANCHOR BOLT AND BASE PLATE ANALYSIS.
- FOUNDATION ANALYSIS.

### **SECTION 4 – REFERENCE MATERIAL**

- SPRINT CD'S PREPARED BY INFINIGY DATED MAY 15, 2014.

## *Introduction*

The purpose of this report is to summarize the results of the non-linear, P- $\Delta$  structural analysis of the antenna upgrade proposed by Sprint on the existing monopole (tower) owned and operated by Verizon Wireless, located in Westport, CT.

The host tower is a 130-ft tall, three-section, eighteen sided, tapered monopole, originally designed and manufactured by Engineered Endeavors Incorporated (EEI job no; 10847-E01), signed and sealed June 6, 2002. The manufacturer's drawings and calculations were unavailable for use in this report. The tower geometry, structure member sizes and foundation system information were obtained from a previous structural analysis report prepared by Centek Engineering, Inc., job no; 13001.051, marked Revision #1, dated September 26, 2013.

Antenna and appurtenance information were obtained from the aforementioned structural report a tower mapping report prepared by Eastern Communications dated October 20, 2014 and Sprint CD's.

The tower consists of three (3) tapered steel vertical sections conforming to ASTM A572-65. The vertical tower sections are slip joint connected. The diameter of the pole (flat-flat) is 28.18-in at the top and 62.0-in at the base.

Sprint proposes the installation of three (3) panel antennas and three (3) remote radio heads mounted to the existing antenna platform. Refer to the Antenna and Appurtenance Summary below for a detailed description of the proposed antenna and appurtenance configuration.

## *Antenna and Appurtenance Summary*

The existing, proposed and future loads considered in this analysis consist of the following:

- VERIZON WIRELESS (Existing/Reserved):  
Antennas: Six (6) Antel LPA-80063-6CF panel antennas, six (6) Antel BXA-70063-6CF panel antennas, six (6) LPA-171063-12CF panel antennas, six (6) RFS FD9R6004/2C-3L diplexers, six (6) RRH's and one (1) main distribution box mounted on a low profile platform with a RAD center elevation of 130-ft above grade level.  
Coax Cables: Twelve (12) 1-5/8"  $\varnothing$  coax cables running on the inside of the existing tower and six (6) 1-5/8"  $\varnothing$  coax cables and two (2) 1-5/8"  $\varnothing$  fiber cables running on the exterior of the existing tower.
- T-MOBILE (Existing):  
Antennas: Six (6) RR90-17-02DP panel antennas, six (6) Ericsson AIR21-B2A/B4P panel antennas, three (3) RFS ATMP1412D-1A20 TMA's and one (1) GPS mounted on an existing low profile platform with a RAD center elevation of 110-ft above the existing tower base plate.  
Coax Cables: Twelve (12) 1-5/8"  $\varnothing$ , six (6) 7/8"  $\varnothing$ , one (1) 1/2"  $\varnothing$  coax cables and one (1) 1-5/8"  $\varnothing$  hybrid cable running on the inside of the existing tower.

- **AT&T (Existing):**  
Antennas: Three (3) Ericsson RRUS-11 and one (1) Raycap DC6-48-60-18-8F surge arrester mounted to one (1) universal ring mount with a RAD center elevation of 104-ft above grade level.  
Coax Cables: One (1) fiber cable and two (2) dc control cables running within the interior of the existing tower.
- **AT&T (Existing):**  
Antennas: Six (6) Powerwave 7770 panel antennas, three (3) Powerwave P65-16-XLH-RR panel antennas, twelve (12) Powerwave LGP21401 TMA's and one (1) GPS mounted on an existing low profile platform with a RAD center elevation of 100-ft above the existing tower base plate.  
Coax Cables: Twelve (12) 1-5/8" Ø coax cables, one (1) 1/2" Ø coax cable and three (3) 3/8" Ø RET cables running on the inside of the existing tower.
- **VACANT (Existing):**  
Antennas: One (1) low profile platform with an elevation of 89-ft above the existing tower base plate.
- **UNKNOWN (Existing):**  
GPS Antennas: Five (5) GPS antennas and mounted on five GPS stand-off mounts with RAD center elevations of 70-ft and 72-ft above grade level.  
Coax Cables: Five (5) 1/2" Ø coax cables running within the interior of the existing tower.
- **AT&T (Existing):**  
LTE GPS Antenna: One (1) LTE GPS antenna and mounted on one (1) SitePro1 2-ft GPS stand-off mount (P/N #CHGPS) with a RAD center elevation of 60-ft above grade level.  
Coax Cables: One (1) 1/2" Ø coax cable running within the interior of the existing tower.
- **SPRINT/CLEARWIRE (Existing to Remain):**  
Antennas: Three (3) Kathrein 840-10054 panel antennas w/ Samsung Remote Radio Heads U-RAS , one (1) Andrew VHLP800-11-DW1 microwave dish, three (3) RFS APXVSP18-C-A20 panel antennas, three (3) ALU 1900 MHz RRH's and three (3) ALU 800 MHz RRH's mounted on an existing low profile platform with a RAD center elevation of 120-ft above the existing tower base plate.  
Coax Cables: Two (2) 2" Ø flex conduits (with three (3) fiber and three (3) dc control cables running in each one), one (1) 7/8" Ø coax cable and three (3) 1-1/4" Ø Hybriflex cables running on the interior of the existing tower.
- **SPRINT (Proposed):**  
Antennas: **Three (3) RFS APXVTM14-C-I20 panel antennas and three (3) Alcatel-Lucent TD-RRH8x20 remote radio heads mounted on an existing low profile platform with a RAD center elevation of 120-ft above the existing tower base plate.**  
Coax Cables: **One (1) 1-1/4" Ø Hybriflex cable running on the interior of the existing tower.**

*Primary Assumptions Used in the Analysis*

- The tower structure's theoretical capacity not including any assessment of the condition of the tower.
- The tower carries the horizontal and vertical loads due to the weight of antennas, ice load and wind.
- Tower is properly installed and maintained.
- Tower is in plumb condition.
- Tower loading for antennas and mounts as listed in this report.
- All bolts are appropriately tightened providing the necessary connection continuity.
- All welds are fabricated with ER-70S-6 electrodes.
- All members are assumed to be as specified in the original tower design documents or reinforcement drawings.
- All members are "hot dipped" galvanized in accordance with ASTM A123 and ASTM A153 Standards.
- All member protective coatings are in good condition.
- All tower members were properly designed, detailed, fabricated, installed and have been properly maintained since erection.
- Any deviation from the analyzed antenna loading will require a new analysis for verification of structural adequacy.
- All existing coax cables to be installed as indicated in this report.

## A n a l y s i s

The existing tower was analyzed using a comprehensive computer program entitled tnxTower. The program analyzes the tower, considering the worst case loading condition. The tower is considered as loaded by concentric forces along the tower shaft, and the model assumes that the shaft members are subjected to bending, axial, and shear forces.

The existing tower was analyzed for the controlling basic wind speed (fastest mile) with no ice and a 75% reduction of wind force with ½ inch accumulative ice to determine stresses in members as per guidelines of TIA/EIA-222-F-96 entitled “Structural Standards for Steel Antenna Towers and Antenna Supporting Structures”, the American Institute of Steel Construction (AISC) and the Manual of Steel Construction; Allowable Stress Design (ASD).

The controlling wind speed is determined by evaluating the local available wind speed data as provided in Appendix K of the CSBC<sup>1</sup> and the wind speed data available in the TIA/EIA-222-F-96 Standard. The higher of the two wind speeds is utilized in preparation on the tower analysis.

## T o w e r L o a d i n g

Tower loading was determined by the basic wind speed as applied to projected surface areas with modification factors per TIA/EIA-222-F, gravity loads of the tower structure and its components, and the application of ½” radial ice on the tower structure and its components.

Basic Wind Speed:	Fairfield; v = 85 mph (fastest mile)	[Section 16 of TIA/EIA-222-F-96]
	Westport; v = 110 mph (3 second gust) equivalent to v = 90 mph (fastest mile)	[Appendix K of the 2005 CT Building Code Supplement]
	<i>Appendix K wind speed controls.</i>	
Load Cases:	<u>Load Case 1</u> ; 90 mph wind speed w/ no ice plus gravity load – used in calculation of tower stresses and rotation.	[Section 2.3.16 of TIA/EIA-222-F-96]
	<u>Load Case 2</u> ; 78 mph wind speed w/ ½” radial ice plus gravity load – used in calculation of tower stresses. The 78 mph wind speed velocity represents 75% of the wind pressure generated by the 90 mph wind speed.	[Section 2.3.16 of TIA/EIA-222-F-96]
	<u>Load Case 3</u> ; Seismic – not checked	[Section 1614.5 of State Bldg. Code 2005] does not control in the design of this structure type

---

<sup>1</sup> The 2005 Connecticut State Building Code as amended by the 2009 CT State Supplement. (CSBC)



## Tower Capacity

Tower stresses were calculated utilizing the structural analysis software tnxTower. Allowable stresses were determined based on Table 5 of the TIA/EIA code with a 1/3 increase per Section 3.1.1.1 of the same code.

- Calculated stresses were found to be within allowable limits. In Load Case 1, per tnxTower “Section Capacity Table”, the maximum tower steel usage was found to be at **69.0%** of its total capacity.

Tower Section	Elevation	Stress Ratio (percentage of capacity)	Result
Pole Shaft (L1)	82.17'-130.00'	49.0%	<b>PASS</b>
Pole Shaft (L2)	42.01'-82.17'	66.8%	<b>PASS</b>
Pole Shaft (L3)	0.00'-42.01'	69.0%	<b>PASS</b>

## Foundation and Anchors

The existing foundation consists of an 8.0-ft  $\varnothing$  x 2.5-ft long reinforced concrete pier on a 29.5-ft square x 3.0-ft thick reinforce concrete pad. The sub-grade conditions used in the analysis of the existing foundation were obtained from the aforementioned structural report prepared by Centek. The base of the tower is connected to the foundation by means of (20) 2.25"  $\varnothing$ , ASTM A615-75 anchor bolts embedded approximately 6-ft into the concrete foundation structure.

- The tower base reactions developed from the governing Load Case 1 were used in the verification of the foundation and its anchors:

Location	Vector	Proposed Reactions
Base	Shear	39 kips
	Compression	47 kips
	Moment	3824 kip-ft

- The foundation was found to be within allowable limits.

Foundation	Design Limit	IBC 2003/2005 CT State Building Code Section 3108.4.2 (FS) <sup>(1)</sup>	Proposed Loading (FS) <sup>(1)</sup>	Result
Reinforced Concrete Pad and Pier	OTM <sup>(2)</sup>	2.0	2.4	<b>PASS</b>

Note 1: FS denotes Factor of Safety.

Note 2: OTM denotes Overturning Moment

- The anchor bolts and base plate were found to be within allowable limits.

Tower Component	Design Limit	Stress Ratio (percentage of capacity)	Result
Anchor Bolts	Combined Axial & Bending	67.6%	PASS
Base Plate	Bending	88.1%	PASS


### Conclusion

This analysis shows that the subject tower **is adequate** to support the proposed modified antenna configuration.

The analysis is based, in part, on the information provided to this office by Sprint. If the existing conditions are different than the information in this report, Centek Engineering, Inc. must be contacted for resolution of any potential issues.

Please feel free to call with any questions or comments.

Respectfully Submitted by:



Timothy J. Lynn, PE  
Structural Engineer



*Standard Conditions for Furnishing of  
Professional Engineering Services on  
Existing Structures*

All engineering services are performed on the basis that the information used is current and correct. This information may consist of, but is not necessarily limited to:

- Information supplied by the client regarding the structure itself, its foundations, the soil conditions, the antenna and feed line loading on the structure and its components, or other relevant information.
- Information from the field and/or drawings in the possession of Centek Engineering, Inc. or generated by field inspections or measurements of the structure.
- It is the responsibility of the client to ensure that the information provided to Centek Engineering, Inc. and used in the performance of our engineering services is correct and complete. In the absence of information to the contrary, we assume that all structures were constructed in accordance with the drawings and specifications and are in an uncorroded condition and have not deteriorated. It is therefore assumed that its capacity has not significantly changed from the “as new” condition.
- All services will be performed to the codes specified by the client, and we do not imply to meet any other codes or requirements unless explicitly agreed in writing. If wind and ice loads or other relevant parameters are to be different from the minimum values recommended by the codes, the client shall specify the exact requirement. In the absence of information to the contrary, all work will be performed in accordance with the latest revision of ANSI/ASCE10 & ANSI/EIA-222
- All services performed, results obtained, and recommendations made are in accordance with generally accepted engineering principles and practices. Centek Engineering, Inc. is not responsible for the conclusions, opinions and recommendations made by others based on the information we supply.


## GENERAL DESCRIPTION OF STRUCTURAL ANALYSIS PROGRAM

tnxTower, is an integrated structural analysis and design software package for Designed specifically for the telecommunications industry, tnxTower, formerly RISATower, automates much of the tower analysis and design required by the TIA/EIA 222 Standard.

### tnxTower Features:

- tnxTower can analyze and design 3- and 4-sided guyed towers, 3- and 4-sided self-supporting towers and either round or tapered ground mounted poles with or without guys.
- The program analyzes towers using the TIA-222-G (2005) standard or any of the previous TIA/EIA standards back to RS-222 (1959). Steel design is checked using the AISC ASD 9th Edition or the AISC LRFD specifications.
- Linear and non-linear (P-delta) analyses can be used in determining displacements and forces in the structure. Wind pressures and forces are automatically calculated.
- Extensive graphics plots include material take-off, shear-moment, leg compression, displacement, twist, feed line, guy anchor and stress plots.
- tnxTower contains unique features such as True Cable behavior, hog rod take-up, foundation stiffness and much more.

Section	1	2	3
Length (ft)	47.830	45.830	49.010
Number of Sides	18	18	18
Thickness (in)	0.313	0.375	0.438
Socket Length (ft)	5.670	7.000	
Top Dia (in)	28.180	39.049	48.781
Bot Dia (in)	41.220	51.420	62.000
Grade	A572-65	A572-65	
Weight (K)	5.6	8.3	12.7



**DESIGNED APPURTENANCE LOADING**


TYPE	ELEVATION	TYPE	ELEVATION
LPA-80063/6CF (Verizon - Reserved)	130	FD-RRH 4x40 1900 (Sprint - Existing)	117
LPA-171063-12CF (Verizon - Reserved)	130	Valmont Uni-Tri Bracket (Sprint - Existing)	117
BXA-70063/6CF (Verizon - Reserved)	130	GPS (T-Mobile - Existing)	113
BXA-70063/6CF (Verizon - Reserved)	130	RR90-17-02DP (T-Mobile - Existing)	110
LPA-171063-12CF (Verizon - Reserved)	130	RR90-17-02DP (T-Mobile - Existing)	110
LPA-80063/6CF (Verizon - Reserved)	130	RR90-17-02DP (T-Mobile - Existing)	110
LPA-80063/6CF (Verizon - Reserved)	130	RR90-17-02DP (T-Mobile - Existing)	110
LPA-171063-12CF (Verizon - Reserved)	130	RR90-17-02DP (T-Mobile - Existing)	110
BXA-70063/6CF (Verizon - Reserved)	130	ATMAP1412D-1A20 (T-Mobile - Existing)	110
BXA-70063/6CF (Verizon - Reserved)	130	ATMAP1412D-1A20 (T-Mobile - Existing)	110
LPA-171063-12CF (Verizon - Reserved)	130	ATMAP1412D-1A20 (T-Mobile - Existing)	110
LPA-80063/6CF (Verizon - Reserved)	130	RR90-17-02DP (T-Mobile - Existing)	110
LPA-80063/6CF (Verizon - Reserved)	130	AIR21 (T-Mobile - Existing)	110
LPA-171063-12CF (Verizon - Reserved)	130	AIR21 (T-Mobile - Existing)	110
BXA-70063/6CF (Verizon - Reserved)	130	AIR21 (T-Mobile - Existing)	110
BXA-70063/6CF (Verizon - Reserved)	130	AIR21 (T-Mobile - Existing)	110
LPA-171063-12CF (Verizon - Reserved)	130	AIR21 (T-Mobile - Existing)	110
LPA-80063/6CF (Verizon - Reserved)	130	AIR21 (T-Mobile - Existing)	110
(2) FD9R6004/2C-3L Diplexer (Verizon - Reserved)	130	EEL Low Profile Platform (T-Mobile - Existing)	109
(2) FD9R6004/2C-3L Diplexer (Verizon - Reserved)	130	GPS (ATI - Existing)	104
(2) FD9R6004/2C-3L Diplexer (Verizon - Reserved)	130	RRUS-11 (ATI - Existing)	104
RRH2x40-AWS (Verizon - Reserved)	130	RRUS-11 (ATI - Existing)	104
RRH2x40-AWS (Verizon - Reserved)	130	RRUS-11 (ATI - Existing)	104
RRH2x40-AWS (Verizon - Reserved)	130	DC6-48-60-18-8F Surge Arrestor (ATI - Existing)	104
RRH2x40-07-U (Verizon - Reserved)	130	Valmont Uni-Tri Bracket (ATI - Existing)	102.5
RRH2x40-07-U (Verizon - Reserved)	130	(4) LGP21401 TMA (ATI - Existing)	100
RRH2x40-07-U (Verizon - Reserved)	130	(4) LGP21401 TMA (ATI - Existing)	100
DB-T1-6Z-8AB-0Z (Verizon - Reserved)	130	(4) LGP21401 TMA (ATI - Existing)	100
EEL Low Profile Platform (Verizon - Existing)	129	7770.00 (ATI - Existing)	100
VHLP800-11-DW1 (Clearwire - Existing)	124	P65-16-XLH-RR (ATI - Existing)	100
APXVSP18-C-A20 (Sprint - Existing)	120	P65-16-XLH-RR (ATI - Existing)	100
APXVSP18-C-A20 (Sprint - Existing)	120	P65-16-XLH-RR (ATI - Existing)	100
APXVSP18-C-A20 (Sprint - Existing)	120	7770.00 (ATI - Existing)	100
APXVTM14 (Sprint - Proposed)	120	7770.00 (ATI - Existing)	100
APXVTM14 (Sprint - Proposed)	120	7770.00 (ATI - Existing)	100
APXVTM14 (Sprint - Proposed)	120	7770.00 (ATI - Existing)	100
840-10054 (Clearwire - Existing)	120	7770.00 (ATI - Existing)	100
840-10054 (Clearwire - Existing)	120	7770.00 (ATI - Existing)	100
840-10054 (Clearwire - Existing)	120	EEL Low Profile Platform (ATI - Existing)	99
840-10054 (Clearwire - Existing)	120	(3) 6"x3" Pipe Mount (Vacant)	90
RRH (Clearwire - Existing)	120	(3) 6"x3" Pipe Mount (Vacant)	90
RRH (Clearwire - Existing)	120	(3) 6"x3" Pipe Mount (Vacant)	90
RRH (Clearwire - Existing)	120	EEL Low Profile Platform (Vacant)	89
6"x3" Pipe Mount (Clearwire - Existing)	120	GPS	72
6"x3" Pipe Mount (Clearwire - Existing)	120	GPS	72
Filter Box (Clearwire - Existing)	120	3' GPS Stand-off Mount	72
EEL Low Profile Platform (Sprint - Existing)	119	3' GPS Stand-off Mount	72
TD-RRH8x20-25 (Sprint - Proposed)	117	3' GPS Stand-off Mount	70
TD-RRH8x20-25 (Sprint - Proposed)	117	3' GPS Stand-off Mount	70
TD-RRH8x20-25 (Sprint - Proposed)	117	Valmont B2069 2' GPS Mount	70
FD-RRH 2x50 800 (Sprint - Existing)	117	GPS	70
FD-RRH 2x50 800 (Sprint - Existing)	117	GPS	70
FD-RRH 2x50 800 (Sprint - Existing)	117	GPS	70
FD-RRH 4x40 1900 (Sprint - Existing)	117	3' GPS Stand-off Mount (ATI - Existing)	60
FD-RRH 4x40 1900 (Sprint - Existing)	117	GPS (ATI - Existing)	60

**MATERIAL STRENGTH**

GRADE	Fy	Fu	GRADE	Fy	Fu
A572-65	65 ksi	80 ksi			

**TOWER DESIGN NOTES**

1. Tower is located in Fairfield County, Connecticut.
2. Tower designed for a 90 mph basic wind in accordance with the TIA/EIA-222-F Standard.
3. Tower is also designed for a 78 mph basic wind with 0.50 in ice.
4. Deflections are based upon a 50 mph wind.
5. Weld together tower sections have flange connections.
6. Connections use galvanized A325 bolts, nuts and locking devices. Installation per TIA/EIA-222 and AISC Specifications.
7. Tower members are "hot dipped" galvanized in accordance with ASTM A123 and ASTM A153 Standards.
8. Welds are fabricated with ER-70S-6 electrodes.
9. TOWER RATING: 69%



<b>Centek Engineering Inc.</b> 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job: <b>14033.012 - CT03XC382</b>
	Project: <b>130-ft EEI Monopole - 2 Sunny Lane Westport, CT</b>
	Client: <b>Sprint</b>
	Code: <b>TIA/EIA-222-F</b>
	Drawn by: <b>TJL</b>
	Date: <b>11/11/14</b>
	App'd: <b>NTS</b>
	Scale: <b>NTS</b>
	Dwg No. <b>E-1</b>

<b>tnxTower</b>  <b>Centek Engineering Inc.</b> 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	<b>Job</b> 14033.012 - CT03XC382	<b>Page</b> 1 of 23
	<b>Project</b> 130-ft EEI Monopole - 2 Sunny Lane Westport, CT	<b>Date</b> 10:54:01 11/11/14
	<b>Client</b> Sprint	<b>Designed by</b> TJL

## Tower Input Data

There is a pole section.

This tower is designed using the TIA/EIA-222-F standard.

The following design criteria apply:

- Tower is located in Fairfield County, Connecticut.
- Basic wind speed of 90 mph.
- Nominal ice thickness of 0.500 in.
- Ice density of 56 pcf.
- A wind speed of 78 mph is used in combination with ice.
- Temperature drop of 50 °F.
- Deflections calculated using a wind speed of 50 mph.
- Weld together tower sections have flange connections..
- Connections use galvanized A325 bolts, nuts and locking devices. Installation per TIA/EIA-222 and AISC Specifications..
- Tower members are "hot dipped" galvanized in accordance with ASTM A123 and ASTM A153 Standards..
- Welds are fabricated with ER-70S-6 electrodes..
- A non-linear (P-delta) analysis was used.
- Pressures are calculated at each section.
- Stress ratio used in pole design is 1.333.
- Local bending stresses due to climbing loads, feedline supports, and appurtenance mounts are not considered.

## Options

- |  |  |  |
|--|--|--|
| <ul style="list-style-type: none"> <li>Consider Moments - Legs</li> <li>Consider Moments - Horizontals</li> <li>Consider Moments - Diagonals</li> <li>Use Moment Magnification</li> <li>√ Use Code Stress Ratios</li> <li>Use Code Safety Factors - Guys</li> <li>Escalate Ice</li> <li>Always Use Max Kz</li> <li>Use Special Wind Profile</li> <li>Include Bolts In Member Capacity</li> <li>Leg Bolts Are At Top Of Section</li> <li>Secondary Horizontal Braces Leg</li> <li>Use Diamond Inner Bracing (4 Sided)</li> <li>Add IBC .6D+W Combination</li> </ul> | <ul style="list-style-type: none"> <li>Distribute Leg Loads As Uniform</li> <li>Assume Legs Pinned</li> <li>√ Assume Rigid Index Plate</li> <li>Use Clear Spans For Wind Area</li> <li>Use Clear Spans For KL/r</li> <li>Retension Guys To Initial Tension</li> <li>√ Bypass Mast Stability Checks</li> <li>Use Azimuth Dish Coefficients</li> <li>√ Project Wind Area of Appurt.</li> <li>Autocalc Torque Arm Areas</li> <li>SR Members Have Cut Ends</li> <li>√ Sort Capacity Reports By Component</li> <li>Triangulate Diamond Inner Bracing</li> </ul> | <ul style="list-style-type: none"> <li>Treat Feedline Bundles As Cylinder</li> <li>Use ASCE 10 X-Brace Ly Rules</li> <li>Calculate Redundant Bracing Forces</li> <li>Ignore Redundant Members in FEA</li> <li>SR Leg Bolts Resist Compression</li> <li>All Leg Panels Have Same Allowable</li> <li>Offset Girt At Foundation</li> <li>Consider Feedline Torque</li> <li>Include Angle Block Shear Check</li> <li style="text-align: center;"><b>Poles</b></li> <li>√ Include Shear-Torsion Interaction</li> <li>Always Use Sub-Critical Flow</li> <li>Use Top Mounted Sockets</li> </ul> |
|--|--|--|

## Tapered Pole Section Geometry

Section	Elevation	Section Length	Splice Length	Number of Sides	Top Diameter	Bottom Diameter	Wall Thickness	Bend Radius	Pole Grade
	ft	ft	ft		in	in	in	in	
L1	130.000-82.170	47.830	5.670	18	28.180	41.220	0.313	1.250	A572-65 (65 ksi)
L2	82.170-42.010	45.830	7.000	18	39.049	51.420	0.375	1.500	A572-65 (65 ksi)
L3	42.010-0.000	49.010		18	48.781	62.000	0.438	1.750	A572-65

<b>tnxTower</b>  <b>Centek Engineering Inc.</b> 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	<b>Job</b> 14033.012 - CT03XC382	<b>Page</b> 2 of 23
	<b>Project</b> 130-ft EEI Monopole - 2 Sunny Lane Westport, CT	<b>Date</b> 10:54:01 11/11/14
	<b>Client</b> Sprint	<b>Designed by</b> TJL

Section	Elevation ft	Section Length ft	Splice Length ft	Number of Sides	Top Diameter in	Bottom Diameter in	Wall Thickness in	Bend Radius in	Pole Grade  (65 ksi)
---------	-----------------	-------------------------	------------------------	-----------------------	-----------------------	--------------------------	-------------------------	----------------------	----------------------------

### Tapered Pole Properties

Section	Tip Dia. in	Area in <sup>2</sup>	I in <sup>4</sup>	r in	C in	I/C in <sup>3</sup>	J in <sup>4</sup>	It/Q in <sup>2</sup>	w in	w/t
L1	28.615	27.641	2711.992	9.893	14.315	189.445	5427.553	13.823	4.410	14.111
	41.856	40.575	8578.339	14.522	20.940	409.668	17167.966	20.291	6.705	21.455
L2	41.206	46.032	8698.389	13.729	19.837	438.494	17408.223	23.020	6.213	16.567
	52.213	60.756	20000.243	18.121	26.121	765.666	40026.802	30.384	8.390	22.373
L3	51.450	67.130	19820.893	17.162	24.780	799.859	39667.867	33.572	7.815	17.864
	62.956	85.487	40932.774	21.855	31.496	1299.618	81919.408	42.752	10.142	23.182

Tower Elevation ft	Gusset Area (per face) ft <sup>2</sup>	Gusset Thickness in	Gusset Grade	Adjust. Factor A <sub>f</sub>	Adjust. Factor A <sub>r</sub>	Weight Mult.	Double Angle Stitch Bolt Spacing Diagonals in	Double Angle Stitch Bolt Spacing Horizontals in
L1 130.000-82.17 0				1	1	1		
L2 82.170-42.010				1	1	1		
L3 42.010-0.000				1	1	1		

### Feed Line/Linear Appurtenances - Entered As Area

Description	Face or Leg	Allow Shield	Component Type	Placement ft	Total Number	C <sub>A</sub> A <sub>A</sub> ft <sup>2</sup> /ft	Weight klf
1 5/8 (Verizon - Existing)	C	No	Inside Pole	130.000 - 3.000	12	No Ice 1/2" Ice	0.000 0.000
2" dia Flex Conduit (Clearwire - Existing)	A	No	Inside Pole	120.000 - 3.000	2	No Ice	0.000
1/2 (Clearwire - Existing)	A	No	Inside Pole	120.000 - 3.000	1	No Ice	0.000
7/8 (T-Mobile - Existing)	C	No	Inside Pole	110.000 - 3.000	6	No Ice	0.000
1/2 (T-Mobile - Existing)	C	No	Inside Pole	110.000 - 3.000	1	No Ice	0.000
1 5/8 (AT&T - Existing)	C	No	Inside Pole	100.000 - 3.000	12	No Ice	0.000
1/2 (AT&T - Existing)	C	No	Inside Pole	100.000 - 3.000	1	No Ice	0.000
1/2 (GPS)	C	No	Inside Pole	72.000 - 3.000	2	No Ice	0.000
1/2 (GPS)	C	No	Inside Pole	70.000 - 3.000	3	No Ice	0.000
RG6-Fiber (AT&T - Existing)	C	No	Inside Pole	130.000 - 3.000	1	No Ice	0.000
#8 AWG Copper Wire	C	No	Inside Pole	130.000 - 3.000	2	No Ice	0.000

<b>tnxTower</b>  <b>Centek Engineering Inc.</b> 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	<b>Job</b> 14033.012 - CT03XC382	<b>Page</b> 3 of 23
	<b>Project</b> 130-ft EEI Monopole - 2 Sunny Lane Westport, CT	<b>Date</b> 10:54:01 11/11/14
	<b>Client</b> Sprint	<b>Designed by</b> TJL

Description	Face or Leg	Allow Shield	Component Type	Placement ft	Total Number		C <sub>AA</sub> ft <sup>2</sup> /ft	Weight klf
(AT&T - Existing) 0.3" dia RET	C	No	Inside Pole	100.000 - 0.000	3	1/2" Ice No Ice	0.000 0.000	0.000 0.000
(AT&T - Existing) 1/2	C	No	Inside Pole	60.000 - 3.000	1	1/2" Ice No Ice	0.000 0.000	0.000 0.000
(AT&T - Existing) 1 5/8	C	No	Inside Pole	110.000 - 3.000	12	1/2" Ice No Ice	0.000 0.000	0.000 0.001
(T-Mobile - Existing) 1 5/8	C	No	Inside Pole	110.000 - 3.000	1	1/2" Ice No Ice	0.000 0.000	0.000 0.001
(T-Mobile - Existing) HYBRIFLEX 1-1/4"	C	No	Inside Pole	120.000 - 3.000	3	1/2" Ice No Ice	0.000 0.000	0.000 0.001
(Sprint - Existing) HYBRIFLEX 1-5/8"	C	No	CaAa (Out Of Face)	130.000 - 3.000	2	1/2" Ice No Ice	0.000 0.000	0.000 0.002
(Verizon - Reserved) 1 5/8	C	No	CaAa (Out Of Face)	130.000 - 3.000	1	1/2" Ice No Ice	0.000 0.198	0.000 0.001
(Verizon - Reserved) 1 5/8	C	No	CaAa (Out Of Face)	130.000 - 3.000	5	1/2" Ice No Ice	0.298 0.000	0.003 0.001
(Verizon - Reserved) HYBRIFLEX 1-1/4"	C	No	Inside Pole	120.000 - 3.000	1	1/2" Ice No Ice	0.000 0.000	0.000 0.001
(Sprint - Proposed)						1/2" Ice	0.000	0.001

### Feed Line/Linear Appurtenances Section Areas

Tower Section	Tower Elevation ft	Face	A <sub>R</sub> ft <sup>2</sup>	A <sub>F</sub> ft <sup>2</sup>	C <sub>AA</sub> In Face ft <sup>2</sup>	C <sub>AA</sub> Out Face ft <sup>2</sup>	Weight K
L1	130.000-82.170	A	0.000	0.000	0.000	0.000	0.388
		B	0.000	0.000	0.000	0.000	0.000
		C	0.000	0.000	0.000	9.470	2.027
L2	82.170-42.010	A	0.000	0.000	0.000	0.000	0.412
		B	0.000	0.000	0.000	0.000	0.000
		C	0.000	0.000	0.000	7.952	2.392
L3	42.010-0.000	A	0.000	0.000	0.000	0.000	0.400
		B	0.000	0.000	0.000	0.000	0.000
		C	0.000	0.000	0.000	7.724	2.343

### Feed Line/Linear Appurtenances Section Areas - With Ice

Tower Section	Tower Elevation ft	Face or Leg	Ice Thickness in	A <sub>R</sub> ft <sup>2</sup>	A <sub>F</sub> ft <sup>2</sup>	C <sub>AA</sub> In Face ft <sup>2</sup>	C <sub>AA</sub> Out Face ft <sup>2</sup>	Weight K
L1	130.000-82.170	A	0.500	0.000	0.000	0.000	0.000	0.388
		B		0.000	0.000	0.000	0.000	0.000
		C		0.000	0.000	0.000	14.253	2.605
L2	82.170-42.010	A	0.500	0.000	0.000	0.000	0.000	0.412
		B		0.000	0.000	0.000	0.000	0.000
		C		0.000	0.000	0.000	11.968	2.878
L3	42.010-0.000	A	0.500	0.000	0.000	0.000	0.000	0.400
		B		0.000	0.000	0.000	0.000	0.000
		C		0.000	0.000	0.000	11.625	2.815

### Discrete Tower Loads



<b>tnxTower</b>  <b>Centek Engineering Inc.</b> 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	<b>Job</b>		14033.012 - CT03XC382		<b>Page</b>		4 of 23	
	<b>Project</b>		130-ft EEI Monopole - 2 Sunny Lane Westport, CT		<b>Date</b>		10:54:01 11/11/14	
	<b>Client</b>		Sprint		<b>Designed by</b>		TJL	

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C <sub>A</sub> A		Weight	
			Horz	Vert			Front	Side		
			ft	ft	°	ft	ft <sup>2</sup>	ft <sup>2</sup>	K	
EEI Low Profile Platform	C	None			0.000	129.000	No Ice	22.500	22.500	1.500
(Verizon - Existing)							1/2" Ice	28.200	28.200	2.250
LPA-80063/6CF	A	From Face	3.000		0.000	130.000	No Ice	10.308	9.005	0.027
(Verizon - Reserved)			6.000				1/2" Ice	10.868	9.554	0.101
			0.000							
LPA-171063-12CF	A	From Face	3.000		0.000	130.000	No Ice	5.994	6.054	0.012
(Verizon - Reserved)			4.000				1/2" Ice	6.462	6.523	0.055
			0.000							
BXA-70063/6CF	A	From Face	3.000		0.000	130.000	No Ice	7.731	4.158	0.017
(Verizon - Reserved)			1.000				1/2" Ice	8.268	4.595	0.059
			0.000							
BXA-70063/6CF	A	From Face	3.000		0.000	130.000	No Ice	7.731	4.158	0.017
(Verizon - Reserved)			-1.000				1/2" Ice	8.268	4.595	0.059
			0.000							
LPA-171063-12CF	A	From Face	3.000		0.000	130.000	No Ice	5.994	6.054	0.012
(Verizon - Reserved)			-4.000				1/2" Ice	6.462	6.523	0.055
			0.000							
LPA-80063/6CF	A	From Face	3.000		0.000	130.000	No Ice	10.308	9.005	0.027
(Verizon - Reserved)			-6.000				1/2" Ice	10.868	9.554	0.101
			0.000							
LPA-80063/6CF	B	From Face	3.000		0.000	130.000	No Ice	10.308	9.005	0.027
(Verizon - Reserved)			6.000				1/2" Ice	10.868	9.554	0.101
			0.000							
LPA-171063-12CF	B	From Face	3.000		0.000	130.000	No Ice	5.994	6.054	0.012
(Verizon - Reserved)			4.000				1/2" Ice	6.462	6.523	0.055
			0.000							
BXA-70063/6CF	B	From Face	3.000		0.000	130.000	No Ice	7.731	4.158	0.017
(Verizon - Reserved)			1.000				1/2" Ice	8.268	4.595	0.059
			0.000							
BXA-70063/6CF	B	From Face	3.000		0.000	130.000	No Ice	7.731	4.158	0.017
(Verizon - Reserved)			-1.000				1/2" Ice	8.268	4.595	0.059
			0.000							
LPA-171063-12CF	B	From Face	3.000		0.000	130.000	No Ice	5.994	6.054	0.012
(Verizon - Reserved)			-4.000				1/2" Ice	6.462	6.523	0.055
			0.000							
LPA-80063/6CF	B	From Face	3.000		0.000	130.000	No Ice	10.308	9.005	0.027
(Verizon - Reserved)			-6.000				1/2" Ice	10.868	9.554	0.101
			0.000							
LPA-80063/6CF	C	From Face	3.000		0.000	130.000	No Ice	10.308	9.005	0.027
(Verizon - Reserved)			6.000				1/2" Ice	10.868	9.554	0.101
			0.000							
LPA-171063-12CF	C	From Face	3.000		0.000	130.000	No Ice	5.994	6.054	0.012
(Verizon - Reserved)			4.000				1/2" Ice	6.462	6.523	0.055
			0.000							
BXA-70063/6CF	C	From Face	3.000		0.000	130.000	No Ice	7.731	4.158	0.017
(Verizon - Reserved)			1.000				1/2" Ice	8.268	4.595	0.059
			0.000							
BXA-70063/6CF	C	From Face	3.000		0.000	130.000	No Ice	7.731	4.158	0.017
(Verizon - Reserved)			-1.000				1/2" Ice	8.268	4.595	0.059
			0.000							
LPA-171063-12CF	C	From Face	3.000		0.000	130.000	No Ice	5.994	6.054	0.012
(Verizon - Reserved)			-4.000				1/2" Ice	6.462	6.523	0.055
			0.000							
LPA-80063/6CF	C	From Face	3.000		0.000	130.000	No Ice	10.308	9.005	0.027
(Verizon - Reserved)			-6.000				1/2" Ice	10.868	9.554	0.101
			0.000							

<b>tnxTower</b>  <b>Centek Engineering Inc.</b> 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	<b>Job</b>		14033.012 - CT03XC382		<b>Page</b>		5 of 23	
	<b>Project</b>		130-ft EEI Monopole - 2 Sunny Lane Westport, CT		<b>Date</b>		10:54:01 11/11/14	
	<b>Client</b>		Sprint		<b>Designed by</b>		TJL	

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment °	Placement ft	C <sub>AA</sub> Front ft <sup>2</sup>	C <sub>AA</sub> Side ft <sup>2</sup>	Weight K
			Horz Lateral ft	Vert ft					
(2) FD9R6004/2C-3L Diplexer (Verizon - Reserved)	A	From Face	3.000 0.000 0.000	0.000	0.000	130.000	No Ice 1/2" Ice 0.367 0.451	0.085 0.136	0.003 0.005
(2) FD9R6004/2C-3L Diplexer (Verizon - Reserved)	B	From Face	3.000 0.000 0.000	0.000	0.000	130.000	No Ice 1/2" Ice 0.367 0.451	0.085 0.136	0.003 0.005
(2) FD9R6004/2C-3L Diplexer (Verizon - Reserved)	C	From Face	3.000 0.000 0.000	0.000	0.000	130.000	No Ice 1/2" Ice 0.367 0.451	0.085 0.136	0.003 0.005
RRH2x40-AWS (Verizon - Reserved)	A	From Face	3.000 0.000 0.000	0.000	0.000	130.000	No Ice 1/2" Ice 2.522 2.753	1.589 1.795	0.044 0.061
RRH2x40-AWS (Verizon - Reserved)	B	From Face	3.000 0.000 0.000	0.000	0.000	130.000	No Ice 1/2" Ice 2.522 2.753	1.589 1.795	0.044 0.061
RRH2x40-AWS (Verizon - Reserved)	C	From Face	3.000 0.000 0.000	0.000	0.000	130.000	No Ice 1/2" Ice 2.522 2.753	1.589 1.795	0.044 0.061
RRH2x40-07-U (Verizon - Reserved)	A	From Face	3.000 0.000 0.000	0.000	0.000	130.000	No Ice 1/2" Ice 2.246 2.447	1.228 1.385	0.050 0.067
RRH2x40-07-U (Verizon - Reserved)	B	From Face	3.000 0.000 0.000	0.000	0.000	130.000	No Ice 1/2" Ice 2.246 2.447	1.228 1.385	0.050 0.067
RRH2x40-07-U (Verizon - Reserved)	C	From Face	3.000 0.000 0.000	0.000	0.000	130.000	No Ice 1/2" Ice 2.246 2.447	1.228 1.385	0.050 0.067
DB-T1-6Z-8AB-0Z (Verizon - Reserved)	A	From Face	3.000 0.000 0.000	0.000	0.000	130.000	No Ice 1/2" Ice 5.600 5.915	2.333 2.558	0.044 0.080
EEI Low Profile Platform (Sprint - Existing)	C	None		0.000	0.000	119.000	No Ice 1/2" Ice 22.500 28.200	22.500 28.200	1.500 2.250
APXVSP18-C-A20 (Sprint - Existing)	A	From Face	3.500 6.000 0.000	0.000	0.000	120.000	No Ice 1/2" Ice 8.260 8.807	5.283 5.736	0.057 0.107
APXVSP18-C-A20 (Sprint - Existing)	B	From Face	3.500 -6.000 0.000	0.000	0.000	120.000	No Ice 1/2" Ice 8.260 8.807	5.283 5.736	0.057 0.107
APXVSP18-C-A20 (Sprint - Existing)	C	From Face	3.500 6.000 0.000	0.000	0.000	120.000	No Ice 1/2" Ice 8.260 8.807	5.283 5.736	0.057 0.107
APXVTM14 (Sprint - Proposed)	A	From Face	3.500 -6.000 0.000	0.000	0.000	120.000	No Ice 1/2" Ice 6.897 7.348	3.607 3.967	0.056 0.096
APXVTM14 (Sprint - Proposed)	B	From Face	3.500 -6.000 0.000	0.000	0.000	120.000	No Ice 1/2" Ice 6.897 7.348	3.607 3.967	0.056 0.096
APXVTM14 (Sprint - Proposed)	C	From Face	3.500 -6.000 0.000	0.000	0.000	120.000	No Ice 1/2" Ice 6.897 7.348	3.607 3.967	0.056 0.096
TD-RRH8x20-25 (Sprint - Proposed)	A	From Face	0.500 -1.000 0.000	0.000	0.000	117.000	No Ice 1/2" Ice 4.720 5.014	1.700 1.917	0.070 0.097
TD-RRH8x20-25 (Sprint - Proposed)	B	From Face	0.500 -1.000 0.000	0.000	0.000	117.000	No Ice 1/2" Ice 4.720 5.014	1.700 1.917	0.070 0.097
TD-RRH8x20-25	C	From Face	0.500	0.000	0.000	117.000	No Ice	1.700	0.070

<b>tnxTower</b>  <b>Centek Engineering Inc.</b> 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	<b>Job</b>	14033.012 - CT03XC382	<b>Page</b>	6 of 23
	<b>Project</b>	130-ft EEI Monopole - 2 Sunny Lane Westport, CT	<b>Date</b>	10:54:01 11/11/14
	<b>Client</b>	Sprint	<b>Designed by</b>	TJL

<i>Description</i>	<i>Face or Leg</i>	<i>Offset Type</i>	<i>Offsets: Horz Lateral Vert</i> <i>ft ft ft</i>	<i>Azimuth Adjustment</i> <i>°</i>	<i>Placement</i> <i>ft</i>	<i>C<sub>AA</sub> Front</i> <i>ft<sup>2</sup></i>	<i>C<sub>AA</sub> Side</i> <i>ft<sup>2</sup></i>	<i>Weight</i> <i>K</i>
(Sprint - Proposed)			-1.000 0.000			1/2" Ice 5.014	1.917	0.097
FD-RRH 2x50 800 (Sprint - Existing)	A	From Face	0.500 -1.000 0.000	0.000	117.000	No Ice 1/2" Ice 2.401 2.613	2.254 2.460	0.064 0.086
FD-RRH 2x50 800 (Sprint - Existing)	B	From Face	0.500 -1.000 0.000	0.000	117.000	No Ice 1/2" Ice 2.401 2.613	2.254 2.460	0.064 0.086
FD-RRH 2x50 800 (Sprint - Existing)	C	From Face	0.500 -1.000 0.000	0.000	117.000	No Ice 1/2" Ice 2.401 2.613	2.254 2.460	0.064 0.086
FD-RRH 4x40 1900 (Sprint - Existing)	A	From Face	0.500 1.000 0.000	0.000	117.000	No Ice 1/2" Ice 2.609 2.845	2.709 2.948	0.060 0.083
FD-RRH 4x40 1900 (Sprint - Existing)	B	From Face	0.500 1.000 0.000	0.000	117.000	No Ice 1/2" Ice 2.609 2.845	2.709 2.948	0.060 0.083
FD-RRH 4x40 1900 (Sprint - Existing)	C	From Face	0.500 1.000 0.000	0.000	117.000	No Ice 1/2" Ice 2.609 2.845	2.709 2.948	0.060 0.083
Valmont Uni-Tri Bracket (Sprint - Existing)	C	None		0.000	117.000	No Ice 1/2" Ice 1.750 1.940	1.750 1.940	0.290 0.306
840-10054 (Clearwire - Existing)	A	From Face	3.500 2.000 0.000	0.000	120.000	No Ice 1/2" Ice 5.186 5.545	1.361 1.620	0.000 0.024
840-10054 (Clearwire - Existing)	B	From Face	3.500 2.000 0.000	0.000	120.000	No Ice 1/2" Ice 5.186 5.545	1.361 1.620	0.000 0.024
840-10054 (Clearwire - Existing)	C	From Face	3.500 2.000 0.000	0.000	120.000	No Ice 1/2" Ice 5.186 5.545	1.361 1.620	0.000 0.024
RRH (Clearwire - Existing)	A	From Face	3.000 0.000 0.000	0.000	120.000	No Ice 1/2" Ice 1.804 2.000	0.778 0.920	0.033 0.045
RRH (Clearwire - Existing)	B	From Face	3.000 0.000 0.000	0.000	120.000	No Ice 1/2" Ice 1.804 2.000	0.778 0.920	0.033 0.045
RRH (Clearwire - Existing)	C	From Face	3.000 0.000 0.000	0.000	120.000	No Ice 1/2" Ice 1.804 2.000	0.778 0.920	0.033 0.045
6'x3" Pipe Mount (Clearwire - Existing)	A	From Face	3.500 -2.000 0.000	0.000	120.000	No Ice 1/2" Ice 1.767 2.129	1.767 2.129	0.035 0.048
6'x3" Pipe Mount (Clearwire - Existing)	B	From Face	3.500 -2.000 0.000	0.000	120.000	No Ice 1/2" Ice 1.767 2.129	1.767 2.129	0.035 0.048
Filter Box (Clearwire - Existing)	A	From Face	3.500 2.000 0.000	0.000	120.000	No Ice 1/2" Ice 3.500 3.751	1.400 1.573	0.040 0.063
EEI Low Profile Platform (T-Mobile - Existing)	C	None		0.000	109.000	No Ice 1/2" Ice 22.500 28.200	22.500 28.200	1.500 2.250
RR90-17-02DP (T-Mobile - Existing)	A	From Face	3.500 -2.000 0.000	0.000	110.000	No Ice 1/2" Ice 4.356 4.775	1.974 2.312	0.018 0.040
RR90-17-02DP (T-Mobile - Existing)	A	From Face	3.500 -6.000 0.000	0.000	110.000	No Ice 1/2" Ice 4.356 4.775	1.974 2.312	0.018 0.040

<b>tnxTower</b>  <b>Centek Engineering Inc.</b> 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	<b>Job</b>	14033.012 - CT03XC382	<b>Page</b>	7 of 23
	<b>Project</b>	130-ft EEI Monopole - 2 Sunny Lane Westport, CT	<b>Date</b>	10:54:01 11/11/14
	<b>Client</b>	Sprint	<b>Designed by</b>	TJL

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C <sub>AA</sub> Front	C <sub>AA</sub> Side	Weight	
			Horz	Vert						
			ft	ft	°	ft	ft <sup>2</sup>	ft <sup>2</sup>	K	
RR90-17-02DP (T-Mobile - Existing)	B	From Face	3.500	-2.000	0.000	110.000	No Ice 1/2" Ice	4.356 4.775	1.974 2.312	0.018 0.040
RR90-17-02DP (T-Mobile - Existing)	B	From Face	3.500	-6.000	0.000	110.000	No Ice 1/2" Ice	4.356 4.775	1.974 2.312	0.018 0.040
RR90-17-02DP (T-Mobile - Existing)	C	From Face	3.500	-2.000	0.000	110.000	No Ice 1/2" Ice	4.356 4.775	1.974 2.312	0.018 0.040
RR90-17-02DP (T-Mobile - Existing)	C	From Face	3.500	-6.000	0.000	110.000	No Ice 1/2" Ice	4.356 4.775	1.974 2.312	0.018 0.040
ATMAP1412D-1A20 (T-Mobile - Existing)	A	From Face	3.500	2.000	0.000	110.000	No Ice 1/2" Ice	1.167 1.314	0.467 0.575	0.013 0.021
ATMAP1412D-1A20 (T-Mobile - Existing)	B	From Face	3.500	2.000	0.000	110.000	No Ice 1/2" Ice	1.167 1.314	0.467 0.575	0.013 0.021
ATMAP1412D-1A20 (T-Mobile - Existing)	C	From Face	3.500	2.000	0.000	110.000	No Ice 1/2" Ice	1.167 1.314	0.467 0.575	0.013 0.021
GPS (T-Mobile - Existing)	A	From Face	2.000	0.000	0.000	113.000	No Ice 1/2" Ice	1.000 1.500	1.000 1.500	0.010 0.015
AIR21 (T-Mobile - Existing)	A	From Face	3.500	6.000	0.000	110.000	No Ice 1/2" Ice	6.533 6.978	4.356 4.775	0.083 0.125
AIR21 (T-Mobile - Existing)	A	From Face	3.500	2.000	0.000	110.000	No Ice 1/2" Ice	6.533 6.978	4.356 4.775	0.083 0.125
AIR21 (T-Mobile - Existing)	B	From Face	3.500	6.000	0.000	110.000	No Ice 1/2" Ice	6.533 6.978	4.356 4.775	0.083 0.125
AIR21 (T-Mobile - Existing)	B	From Face	3.500	2.000	0.000	110.000	No Ice 1/2" Ice	6.533 6.978	4.356 4.775	0.083 0.125
AIR21 (T-Mobile - Existing)	C	From Face	3.500	6.000	0.000	110.000	No Ice 1/2" Ice	6.533 6.978	4.356 4.775	0.083 0.125
AIR21 (T-Mobile - Existing)	C	From Face	3.500	2.000	0.000	110.000	No Ice 1/2" Ice	6.533 6.978	4.356 4.775	0.083 0.125
EEI Low Profile Platform (AT&T - Existing)	C	None			0.000	99.000	No Ice 1/2" Ice	22.500 28.200	22.500 28.200	1.500 2.250
7770.00 (AT&T - Existing)	A	From Face	3.000	-6.000	0.000	100.000	No Ice 1/2" Ice	5.882 6.314	2.928 3.273	0.035 0.068
7770.00 (AT&T - Existing)	A	From Face	3.000	6.000	0.000	100.000	No Ice 1/2" Ice	5.882 6.314	2.928 3.273	0.035 0.068
7770.00 (AT&T - Existing)	B	From Face	3.000	-6.000	0.000	100.000	No Ice 1/2" Ice	5.882 6.314	2.928 3.273	0.035 0.068
7770.00 (AT&T - Existing)	B	From Face	3.000	6.000	0.000	100.000	No Ice 1/2" Ice	5.882 6.314	2.928 3.273	0.035 0.068
7770.00	C	From Face	3.000		0.000	100.000	No Ice	5.882	2.928	0.035

<b>tnxTower</b>  <b>Centek Engineering Inc.</b> 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	<b>Job</b>		14033.012 - CT03XC382		<b>Page</b>		8 of 23	
	<b>Project</b>		130-ft EEI Monopole - 2 Sunny Lane Westport, CT		<b>Date</b>		10:54:01 11/11/14	
	<b>Client</b>		Sprint		<b>Designed by</b>		TJL	

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment °	Placement ft	C <sub>AA</sub> Front ft <sup>2</sup>	C <sub>AA</sub> Side ft <sup>2</sup>	Weight K
(AT&T - Existing)			-6.000 0.000		1/2" Ice	6.314	3.273	0.068
7770.00 (AT&T - Existing)	C	From Face	3.000 6.000 0.000	0.000	100.000	No Ice 5.882	2.928	0.035
(4) LGP21401 TMA (AT&T - Existing)	A	From Face	3.000 0.000 0.000	0.000	100.000	No Ice 1/2" Ice 1.093	0.367 0.480	0.018 0.023
(4) LGP21401 TMA (AT&T - Existing)	B	From Face	3.000 0.000 0.000	0.000	100.000	No Ice 1/2" Ice 1.093	0.367 0.480	0.018 0.023
(4) LGP21401 TMA (AT&T - Existing)	C	From Face	3.000 0.000 0.000	0.000	100.000	No Ice 1/2" Ice 1.093	0.367 0.480	0.018 0.023
GPS (AT&T - Existing)	B	From Face	2.000 0.000 0.000	0.000	104.000	No Ice 1/2" Ice 1.500	1.000 1.500	0.010 0.015
P65-16-XLH-RR (AT&T - Existing)	A	From Face	3.000 6.000 0.000	0.000	100.000	No Ice 1/2" Ice 8.949	4.700 5.147	0.060 0.107
P65-16-XLH-RR (AT&T - Existing)	B	From Face	3.000 6.000 0.000	0.000	100.000	No Ice 1/2" Ice 8.949	4.700 5.147	0.060 0.107
P65-16-XLH-RR (AT&T - Existing)	C	From Face	3.000 6.000 0.000	0.000	100.000	No Ice 1/2" Ice 8.949	4.700 5.147	0.060 0.107
RRUS-11 (AT&T - Existing)	A	From Face	0.500 0.000 0.000	0.000	104.000	No Ice 1/2" Ice 3.226	1.246 1.412	0.050 0.070
RRUS-11 (AT&T - Existing)	B	From Face	0.500 0.000 0.000	0.000	104.000	No Ice 1/2" Ice 3.226	1.246 1.412	0.050 0.070
RRUS-11 (AT&T - Existing)	C	From Face	0.500 0.000 0.000	0.000	104.000	No Ice 1/2" Ice 3.226	1.246 1.412	0.050 0.070
DC6-48-60-18-8F Surge Arrestor (AT&T - Existing)	C	From Face	0.500 0.000 0.000	0.000	104.000	No Ice 1/2" Ice 2.447	2.228 2.447	0.020 0.039
Valmont Uni-Tri Bracket (AT&T - Existing)	C	None		0.000	102.500	No Ice 1/2" Ice 1.940	1.750 1.940	0.290 0.306
EEI Low Profile Platform (Vacant)	C	None		0.000	89.000	No Ice 1/2" Ice 28.200	22.500 28.200	1.500 2.250
(3) 6'x3" Pipe Mount (Vacant)	A	From Face	3.000 0.000 0.000	0.000	90.000	No Ice 1/2" Ice 2.129	1.767 2.129	0.035 0.048
(3) 6'x3" Pipe Mount (Vacant)	B	From Face	3.000 0.000 0.000	0.000	90.000	No Ice 1/2" Ice 2.129	1.767 2.129	0.035 0.048
(3) 6'x3" Pipe Mount (Vacant)	C	From Face	3.000 0.000 0.000	0.000	90.000	No Ice 1/2" Ice 2.129	1.767 2.129	0.035 0.048
GPS	A	From Face	1.000 0.000 0.000	0.000	70.000	No Ice 1/2" Ice 1.500	1.000 1.500	0.010 0.015
GPS	B	From Face	1.000 0.000 0.000	0.000	70.000	No Ice 1/2" Ice 1.500	1.000 1.500	0.010 0.015

<b>tnxTower</b>  <b>Centek Engineering Inc.</b> 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	<b>Job</b>	14033.012 - CT03XC382	<b>Page</b>	9 of 23
	<b>Project</b>	130-ft EEI Monopole - 2 Sunny Lane Westport, CT	<b>Date</b>	10:54:01 11/11/14
	<b>Client</b>	Sprint	<b>Designed by</b>	TJL

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C <sub>AA</sub> Front	C <sub>AA</sub> Side	Weight	
			Horz	Vert						
			ft	ft	°	ft	ft <sup>2</sup>	ft <sup>2</sup>	K	
GPS	C	From Face	1.000	0.000	0.000	70.000	No Ice	1.000	1.000	0.010
			0.000				1/2" Ice	1.500	1.500	0.015
			0.000							
GPS	A	From Face	1.000	0.000	0.000	72.000	No Ice	1.000	1.000	0.010
			0.000				1/2" Ice	1.500	1.500	0.015
			0.000							
GPS	C	From Face	1.000	0.000	0.000	72.000	No Ice	1.000	1.000	0.010
			0.000				1/2" Ice	1.500	1.500	0.015
			0.000							
3' GPS Stand-off Mount	A	From Face	1.500	0.000	0.000	70.000	No Ice	2.450	2.450	0.051
			0.000				1/2" Ice	3.980	3.980	0.075
			0.000							
3' GPS Stand-off Mount	B	From Face	1.500	0.000	0.000	70.000	No Ice	2.450	2.450	0.051
			0.000				1/2" Ice	3.980	3.980	0.075
			0.000							
Valmont B2069 2' GPS Mount	C	From Face	1.000	0.000	0.000	70.000	No Ice	0.780	0.680	0.025
			0.000				1/2" Ice	1.100	1.100	0.033
			0.000							
3' GPS Stand-off Mount	A	From Face	1.500	0.000	0.000	72.000	No Ice	2.450	2.450	0.051
			0.000				1/2" Ice	3.980	3.980	0.075
			0.000							
3' GPS Stand-off Mount	C	From Face	1.500	0.000	0.000	72.000	No Ice	2.450	2.450	0.051
			0.000				1/2" Ice	3.980	3.980	0.075
			0.000							
GPS (AT&T - Existing)	B	From Face	2.000	0.000	0.000	60.000	No Ice	1.000	1.000	0.010
			0.000				1/2" Ice	1.500	1.500	0.015
			0.000							
3' GPS Stand-off Mount (AT&T - Existing)	B	From Face	1.500	0.000	0.000	60.000	No Ice	2.450	2.450	0.051
			0.000				1/2" Ice	3.980	3.980	0.075
			0.000							

### Dishes

Description	Face or Leg	Dish Type	Offset Type	Offsets:		Azimuth Adjustment	3 dB Beam Width	Elevation	Outside Diameter	Aperture Area	Weight	
				Horz	Vert							
			ft	ft	°	°	ft	ft	ft <sup>2</sup>	K		
VHLP800-11-DW1 (Clearwire - Existing)	A	Paraboloid w/Radome	From Face	3.500	-2.000	0.000	Worst	124.000	2.500	No Ice	4.910	0.049
										1/2" Ice	5.240	0.076

### Tower Pressures - No Ice

$$G_H = 1.690$$

<b>tnxTower</b>  <b>Centek Engineering Inc.</b> 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	<b>Job</b> 14033.012 - CT03XC382	<b>Page</b> 10 of 23
	<b>Project</b> 130-ft EEI Monopole - 2 Sunny Lane Westport, CT	<b>Date</b> 10:54:01 11/11/14
	<b>Client</b> Sprint	<b>Designed by</b> TJL

Section Elevation ft	z ft	K <sub>Z</sub>	q <sub>z</sub> ksf	A <sub>G</sub> ft <sup>2</sup>	F a c e ft <sup>2</sup>	A <sub>F</sub> ft <sup>2</sup>	A <sub>R</sub> ft <sup>2</sup>	A <sub>leg</sub> ft <sup>2</sup>	Leg %	C <sub>AA</sub> In Face ft <sup>2</sup>	C <sub>AA</sub> Out Face ft <sup>2</sup>
L1 130.000-82.170	104.971	1.392	0.029	138.308	A	0.000	138.308	138.308	100.00	0.000	0.000
					B	0.000	138.308		100.00	0.000	0.000
					C	0.000	138.308		100.00	0.000	9.470
L2 82.170-42.010	61.769	1.196	0.025	153.946	A	0.000	153.946	153.946	100.00	0.000	0.000
					B	0.000	153.946		100.00	0.000	0.000
					C	0.000	153.946		100.00	0.000	7.952
L3 42.010-0.000	20.301	1	0.021	197.217	A	0.000	197.217	197.217	100.00	0.000	0.000
					B	0.000	197.217		100.00	0.000	0.000
					C	0.000	197.217		100.00	0.000	7.724

### Tower Pressure - With Ice

$$G_H = 1.690$$

Section Elevation ft	z ft	K <sub>Z</sub>	q <sub>z</sub> ksf	t <sub>z</sub> in	A <sub>G</sub> ft <sup>2</sup>	F a c e ft <sup>2</sup>	A <sub>F</sub> ft <sup>2</sup>	A <sub>R</sub> ft <sup>2</sup>	A <sub>leg</sub> ft <sup>2</sup>	Leg %	C <sub>AA</sub> In Face ft <sup>2</sup>	C <sub>AA</sub> Out Face ft <sup>2</sup>
L1 130.000-82.170	104.971	1.392	0.022	0.500	142.294	A	0.000	142.294	142.294	100.00	0.000	0.000
						B	0.000	142.294		100.00	0.000	0.000
						C	0.000	142.294		100.00	0.000	14.253
L2 82.170-42.010	61.769	1.196	0.019	0.500	157.293	A	0.000	157.293	157.293	100.00	0.000	0.000
						B	0.000	157.293		100.00	0.000	0.000
						C	0.000	157.293		100.00	0.000	11.968
L3 42.010-0.000	20.301	1	0.016	0.500	200.718	A	0.000	200.718	200.718	100.00	0.000	0.000
						B	0.000	200.718		100.00	0.000	0.000
						C	0.000	200.718		100.00	0.000	11.625

### Tower Pressure - Service

$$G_H = 1.690$$

Section Elevation ft	z ft	K <sub>Z</sub>	q <sub>z</sub> ksf	A <sub>G</sub> ft <sup>2</sup>	F a c e ft <sup>2</sup>	A <sub>F</sub> ft <sup>2</sup>	A <sub>R</sub> ft <sup>2</sup>	A <sub>leg</sub> ft <sup>2</sup>	Leg %	C <sub>AA</sub> In Face ft <sup>2</sup>	C <sub>AA</sub> Out Face ft <sup>2</sup>
L1 130.000-82.170	104.971	1.392	0.009	138.308	A	0.000	138.308	138.308	100.00	0.000	0.000
					B	0.000	138.308		100.00	0.000	0.000
					C	0.000	138.308		100.00	0.000	9.470
L2 82.170-42.010	61.769	1.196	0.008	153.946	A	0.000	153.946	153.946	100.00	0.000	0.000
					B	0.000	153.946		100.00	0.000	0.000
					C	0.000	153.946		100.00	0.000	7.952
L3 42.010-0.000	20.301	1	0.006	197.217	A	0.000	197.217	197.217	100.00	0.000	0.000
					B	0.000	197.217		100.00	0.000	0.000
					C	0.000	197.217		100.00	0.000	7.724

### Tower Forces - No Ice - Wind Normal To Face

<b>tnxTower</b>  <b>Centek Engineering Inc.</b> 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	<b>Job</b> 14033.012 - CT03XC382	<b>Page</b> 11 of 23
	<b>Project</b> 130-ft EEI Monopole - 2 Sunny Lane Westport, CT	<b>Date</b> 10:54:01 11/11/14
	<b>Client</b> Sprint	<b>Designed by</b> TJL

Section Elevation ft	Add Weight K	Self Weight K	F a c e	e	C <sub>F</sub>	R <sub>R</sub>	D <sub>F</sub>	D <sub>R</sub>	A <sub>E</sub> ft <sup>2</sup>	F K	w klf	Ctrl. Face
L1 130.000-82.170	2.415	5.551	A	1	0.65	1	1	1	138.308	4.835	0.101	C
			B	1	0.65	1	1	1	138.308			
			C	1	0.65	1	1	1	138.308			
L2 82.170-42.010	2.804	8.327	A	1	0.65	1	1	1	153.946	4.506	0.112	C
			B	1	0.65	1	1	1	153.946			
			C	1	0.65	1	1	1	153.946			
L3 42.010-0.000	2.743	12.726	A	1	0.65	1	1	1	197.217	4.763	0.113	C
			B	1	0.65	1	1	1	197.217			
			C	1	0.65	1	1	1	197.217			
Sum Weight:	7.962	26.604						OTM	882.586 kip-ft	14.104		

**Tower Forces - No Ice - Wind 45 To Face**

Section Elevation ft	Add Weight K	Self Weight K	F a c e	e	C <sub>F</sub>	R <sub>R</sub>	D <sub>F</sub>	D <sub>R</sub>	A <sub>E</sub> ft <sup>2</sup>	F K	w klf	Ctrl. Face
L1 130.000-82.170	2.415	5.551	A	1	0.65	1	1	1	138.308	4.835	0.101	C
			B	1	0.65	1	1	1	138.308			
			C	1	0.65	1	1	1	138.308			
L2 82.170-42.010	2.804	8.327	A	1	0.65	1	1	1	153.946	4.506	0.112	C
			B	1	0.65	1	1	1	153.946			
			C	1	0.65	1	1	1	153.946			
L3 42.010-0.000	2.743	12.726	A	1	0.65	1	1	1	197.217	4.763	0.113	C
			B	1	0.65	1	1	1	197.217			
			C	1	0.65	1	1	1	197.217			
Sum Weight:	7.962	26.604						OTM	882.586 kip-ft	14.104		

**Tower Forces - No Ice - Wind 60 To Face**

Section Elevation ft	Add Weight K	Self Weight K	F a c e	e	C <sub>F</sub>	R <sub>R</sub>	D <sub>F</sub>	D <sub>R</sub>	A <sub>E</sub> ft <sup>2</sup>	F K	w klf	Ctrl. Face
L1 130.000-82.170	2.415	5.551	A	1	0.65	1	1	1	138.308	4.835	0.101	C
			B	1	0.65	1	1	1	138.308			
			C	1	0.65	1	1	1	138.308			
L2 82.170-42.010	2.804	8.327	A	1	0.65	1	1	1	153.946	4.506	0.112	C
			B	1	0.65	1	1	1	153.946			
			C	1	0.65	1	1	1	153.946			
L3 42.010-0.000	2.743	12.726	A	1	0.65	1	1	1	197.217	4.763	0.113	C
			B	1	0.65	1	1	1	197.217			
			C	1	0.65	1	1	1	197.217			
Sum Weight:	7.962	26.604						OTM	882.586 kip-ft	14.104		



<b>tnxTower</b>  <b>Centek Engineering Inc.</b> 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	<b>Job</b> 14033.012 - CT03XC382	<b>Page</b> 12 of 23
	<b>Project</b> 130-ft EEI Monopole - 2 Sunny Lane Westport, CT	<b>Date</b> 10:54:01 11/11/14
	<b>Client</b> Sprint	<b>Designed by</b> TJJ

**Tower Forces - No Ice - Wind 90 To Face**

Section Elevation ft	Add Weight K	Self Weight K	F a c e	e	C <sub>F</sub>	R <sub>R</sub>	D <sub>F</sub>	D <sub>R</sub>	A <sub>E</sub> ft <sup>2</sup>	F K	w klf	Ctrl. Face
L1 130.000-82.170	2.415	5.551	A	1	0.65	1	1	1	138.308	4.835	0.101	C
			B	1	0.65	1	1	1	138.308			
			C	1	0.65	1	1	1	138.308			
L2 82.170-42.010	2.804	8.327	A	1	0.65	1	1	1	153.946	4.506	0.112	C
			B	1	0.65	1	1	1	153.946			
			C	1	0.65	1	1	1	153.946			
L3 42.010-0.000	2.743	12.726	A	1	0.65	1	1	1	197.217	4.763	0.113	C
			B	1	0.65	1	1	1	197.217			
			C	1	0.65	1	1	1	197.217			
Sum Weight:	7.962	26.604						OTM	882.586 kip-ft	14.104		

**Tower Forces - With Ice - Wind Normal To Face**

Section Elevation ft	Add Weight K	Self Weight K	F a c e	e	C <sub>F</sub>	R <sub>R</sub>	D <sub>F</sub>	D <sub>R</sub>	A <sub>E</sub> ft <sup>2</sup>	F K	w klf	Ctrl. Face
L1 130.000-82.170	2.993	6.590	A	1	0.65	1	1	1	142.294	3.896	0.081	C
			B	1	0.65	1	1	1	142.294			
			C	1	0.65	1	1	1	142.294			
L2 82.170-42.010	3.290	9.479	A	1	0.65	1	1	1	157.293	3.573	0.089	C
			B	1	0.65	1	1	1	157.293			
			C	1	0.65	1	1	1	157.293			
L3 42.010-0.000	3.215	14.200	A	1	0.65	1	1	1	200.718	3.735	0.089	C
			B	1	0.65	1	1	1	200.718			
			C	1	0.65	1	1	1	200.718			
Sum Weight:	9.497	30.269						OTM	705.448 kip-ft	11.203		

**Tower Forces - With Ice - Wind 45 To Face**

Section Elevation ft	Add Weight K	Self Weight K	F a c e	e	C <sub>F</sub>	R <sub>R</sub>	D <sub>F</sub>	D <sub>R</sub>	A <sub>E</sub> ft <sup>2</sup>	F K	w klf	Ctrl. Face
L1 130.000-82.170	2.993	6.590	A	1	0.65	1	1	1	142.294	3.896	0.081	C
			B	1	0.65	1	1	1	142.294			
			C	1	0.65	1	1	1	142.294			
L2 82.170-42.010	3.290	9.479	A	1	0.65	1	1	1	157.293	3.573	0.089	C
			B	1	0.65	1	1	1	157.293			
			C	1	0.65	1	1	1	157.293			
L3 42.010-0.000	3.215	14.200	A	1	0.65	1	1	1	200.718	3.735	0.089	C
			B	1	0.65	1	1	1	200.718			
			C	1	0.65	1	1	1	200.718			
Sum Weight:	9.497	30.269						OTM	705.448 kip-ft	11.203		

<b>tnxTower</b>  <b>Centek Engineering Inc.</b> 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	<b>Job</b> 14033.012 - CT03XC382	<b>Page</b> 13 of 23
	<b>Project</b> 130-ft EEI Monopole - 2 Sunny Lane Westport, CT	<b>Date</b> 10:54:01 11/11/14
	<b>Client</b> Sprint	<b>Designed by</b> TJL

**Tower Forces - With Ice - Wind 60 To Face**

Section Elevation ft	Add Weight K	Self Weight K	F a c e	e	C <sub>F</sub>	R <sub>R</sub>	D <sub>F</sub>	D <sub>R</sub>	A <sub>E</sub> ft <sup>2</sup>	F K	w klf	Ctrl. Face
L1 130.000-82.170	2.993	6.590	A	1	0.65	1	1	1	142.294	3.896	0.081	C
			B	1	0.65	1	1	1	142.294			
			C	1	0.65	1	1	1	142.294			
L2 82.170-42.010	3.290	9.479	A	1	0.65	1	1	1	157.293	3.573	0.089	C
			B	1	0.65	1	1	1	157.293			
			C	1	0.65	1	1	1	157.293			
L3 42.010-0.000	3.215	14.200	A	1	0.65	1	1	1	200.718	3.735	0.089	C
			B	1	0.65	1	1	1	200.718			
			C	1	0.65	1	1	1	200.718			
Sum Weight:	9.497	30.269						OTM	705.448 kip-ft	11.203		

**Tower Forces - With Ice - Wind 90 To Face**

Section Elevation ft	Add Weight K	Self Weight K	F a c e	e	C <sub>F</sub>	R <sub>R</sub>	D <sub>F</sub>	D <sub>R</sub>	A <sub>E</sub> ft <sup>2</sup>	F K	w klf	Ctrl. Face
L1 130.000-82.170	2.993	6.590	A	1	0.65	1	1	1	142.294	3.896	0.081	C
			B	1	0.65	1	1	1	142.294			
			C	1	0.65	1	1	1	142.294			
L2 82.170-42.010	3.290	9.479	A	1	0.65	1	1	1	157.293	3.573	0.089	C
			B	1	0.65	1	1	1	157.293			
			C	1	0.65	1	1	1	157.293			
L3 42.010-0.000	3.215	14.200	A	1	0.65	1	1	1	200.718	3.735	0.089	C
			B	1	0.65	1	1	1	200.718			
			C	1	0.65	1	1	1	200.718			
Sum Weight:	9.497	30.269						OTM	705.448 kip-ft	11.203		

**Tower Forces - Service - Wind Normal To Face**

Section Elevation ft	Add Weight K	Self Weight K	F a c e	e	C <sub>F</sub>	R <sub>R</sub>	D <sub>F</sub>	D <sub>R</sub>	A <sub>E</sub> ft <sup>2</sup>	F K	w klf	Ctrl. Face
L1 130.000-82.170	2.415	5.551	A	1	0.65	1	1	1	138.308	1.492	0.031	C
			B	1	0.65	1	1	1	138.308			
			C	1	0.65	1	1	1	138.308			
L2 82.170-42.010	2.804	8.327	A	1	0.65	1	1	1	153.946	1.391	0.035	C
			B	1	0.65	1	1	1	153.946			
			C	1	0.65	1	1	1	153.946			
L3 42.010-0.000	2.743	12.726	A	1	0.65	1	1	1	197.217	1.470	0.035	C
			B	1	0.65	1	1	1	197.217			
			C	1	0.65	1	1	1	197.217			
Sum Weight:	7.962	26.604						OTM	272.403	4.353		

<b>tnxTower</b>  <b>Centek Engineering Inc.</b> 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	<b>Job</b> 14033.012 - CT03XC382	<b>Page</b> 14 of 23
	<b>Project</b> 130-ft EEI Monopole - 2 Sunny Lane Westport, CT	<b>Date</b> 10:54:01 11/11/14
	<b>Client</b> Sprint	<b>Designed by</b> TJJ

Section Elevation	Add Weight	Self Weight	F a c e	e	C <sub>F</sub>	R <sub>R</sub>	D <sub>F</sub>	D <sub>R</sub>	A <sub>E</sub>	F	w	Ctrl. Face
ft	K	K							ft <sup>2</sup>	K	klf	
									kip-ft			

**Tower Forces - Service - Wind 45 To Face**

Section Elevation	Add Weight	Self Weight	F a c e	e	C <sub>F</sub>	R <sub>R</sub>	D <sub>F</sub>	D <sub>R</sub>	A <sub>E</sub>	F	w	Ctrl. Face
ft	K	K							ft <sup>2</sup>	K	klf	
L1	2.415	5.551	A	1	0.65	1	1	1	138.308	1.492	0.031	C
130.000-82.170			B	1	0.65	1	1	1	138.308			
			C	1	0.65	1	1	1	138.308			
L2	2.804	8.327	A	1	0.65	1	1	1	153.946	1.391	0.035	C
82.170-42.010			B	1	0.65	1	1	1	153.946			
			C	1	0.65	1	1	1	153.946			
L3	2.743	12.726	A	1	0.65	1	1	1	197.217	1.470	0.035	C
42.010-0.000			B	1	0.65	1	1	1	197.217			
			C	1	0.65	1	1	1	197.217			
Sum Weight:	7.962	26.604						OTM	272.403	4.353		
									kip-ft			

**Tower Forces - Service - Wind 60 To Face**

Section Elevation	Add Weight	Self Weight	F a c e	e	C <sub>F</sub>	R <sub>R</sub>	D <sub>F</sub>	D <sub>R</sub>	A <sub>E</sub>	F	w	Ctrl. Face
ft	K	K							ft <sup>2</sup>	K	klf	
L1	2.415	5.551	A	1	0.65	1	1	1	138.308	1.492	0.031	C
130.000-82.170			B	1	0.65	1	1	1	138.308			
			C	1	0.65	1	1	1	138.308			
L2	2.804	8.327	A	1	0.65	1	1	1	153.946	1.391	0.035	C
82.170-42.010			B	1	0.65	1	1	1	153.946			
			C	1	0.65	1	1	1	153.946			
L3	2.743	12.726	A	1	0.65	1	1	1	197.217	1.470	0.035	C
42.010-0.000			B	1	0.65	1	1	1	197.217			
			C	1	0.65	1	1	1	197.217			
Sum Weight:	7.962	26.604						OTM	272.403	4.353		
									kip-ft			

**Tower Forces - Service - Wind 90 To Face**

Section Elevation	Add Weight	Self Weight	F a c e	e	C <sub>F</sub>	R <sub>R</sub>	D <sub>F</sub>	D <sub>R</sub>	A <sub>E</sub>	F	w	Ctrl. Face
ft	K	K							ft <sup>2</sup>	K	klf	
L1	2.415	5.551	A	1	0.65	1	1	1	138.308	1.492	0.031	C
130.000-82.170			B	1	0.65	1	1	1	138.308			
			C	1	0.65	1	1	1	138.308			

<b>tnxTower</b>  <b>Centek Engineering Inc.</b> 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	<b>Job</b> 14033.012 - CT03XC382	<b>Page</b> 15 of 23
	<b>Project</b> 130-ft EEI Monopole - 2 Sunny Lane Westport, CT	<b>Date</b> 10:54:01 11/11/14
	<b>Client</b> Sprint	<b>Designed by</b> TJL

Section Elevation	Add Weight	Self Weight	F a c e	e	C <sub>F</sub>	R <sub>R</sub>	D <sub>F</sub>	D <sub>R</sub>	A <sub>E</sub>	F	w	Ctrl. Face
ft	K	K							ft <sup>2</sup>	K	klf	
L2 82.170-42.010	2.804	8.327	A	1	0.65	1	1	1	153.946	1.391	0.035	C
			B	1	0.65	1	1	1	153.946			
			C	1	0.65	1	1	1	153.946			
L3 42.010-0.000	2.743	12.726	A	1	0.65	1	1	1	197.217	1.470	0.035	C
			B	1	0.65	1	1	1	197.217			
			C	1	0.65	1	1	1	197.217			
Sum Weight:	7.962	26.604						OTM	272.403 kip-ft	4.353		

### Force Totals

Load Case	Vertical Forces	Sum of Forces X	Sum of Forces Z	Sum of Overturning Moments, M <sub>x</sub>	Sum of Overturning Moments, M <sub>z</sub>	Sum of Torques
	K	K	K	kip-ft	kip-ft	kip-ft
Leg Weight	26.604					
Bracing Weight	0.000					
Total Member Self-Weight	26.604					
Total Weight	46.601			-1.151	0.930	
Wind 0 deg - No Ice		-0.119	-38.970	-3729.862	15.994	-4.319
Wind 30 deg - No Ice		19.448	-33.690	-3222.778	-1858.925	-6.686
Wind 45 deg - No Ice		27.566	-27.472	-2627.096	-2637.099	-7.220
Wind 60 deg - No Ice		33.805	-19.382	-1852.461	-3235.497	-7.261
Wind 90 deg - No Ice		39.104	0.119	13.913	-3744.871	-5.891
Wind 120 deg - No Ice		33.925	19.589	1876.250	-3250.561	-2.942
Wind 135 deg - No Ice		27.735	27.641	2646.098	-2658.403	-1.111
Wind 150 deg - No Ice		19.655	33.809	3235.540	-1885.016	0.795
Wind 180 deg - No Ice		0.119	38.970	3727.560	-14.133	4.319
Wind 210 deg - No Ice		-19.448	33.690	3220.476	1860.786	6.686
Wind 225 deg - No Ice		-27.566	27.472	2624.794	2638.960	7.220
Wind 240 deg - No Ice		-33.805	19.382	1850.159	3237.358	7.261
Wind 270 deg - No Ice		-39.104	-0.119	-16.215	3746.732	5.891
Wind 300 deg - No Ice		-33.925	-19.589	-1878.552	3252.422	2.942
Wind 315 deg - No Ice		-27.735	-27.641	-2648.400	2660.264	1.111
Wind 330 deg - No Ice		-19.655	-33.809	-3237.842	1886.877	-0.795
Member Ice	3.665					
Total Weight Ice	58.534			-1.958	1.586	
Wind 0 deg - Ice		-0.092	-32.550	-3130.275	13.237	-3.485
Wind 30 deg - Ice		16.248	-28.143	-2705.335	-1559.209	-5.488
Wind 45 deg - Ice		23.026	-22.951	-2205.774	-2211.742	-5.957
Wind 60 deg - Ice		28.235	-16.195	-1556.027	-2713.441	-6.020
Wind 90 deg - Ice		32.657	0.092	9.693	-3140.183	-4.939
Wind 120 deg - Ice		28.328	16.355	1572.290	-2725.091	-2.535
Wind 135 deg - Ice		23.157	23.082	2218.335	-2228.218	-1.028
Wind 150 deg - Ice		16.408	28.235	2713.070	-1579.388	0.549
Wind 180 deg - Ice		0.092	32.550	3126.360	-10.064	3.485
Wind 210 deg - Ice		-16.248	28.143	2701.420	1562.382	5.488
Wind 225 deg - Ice		-23.026	22.951	2201.859	2214.915	5.957
Wind 240 deg - Ice		-28.235	16.195	1552.112	2716.614	6.020
Wind 270 deg - Ice		-32.657	-0.092	-13.608	3143.356	4.939
Wind 300 deg - Ice		-28.328	-16.355	-1576.206	2728.264	2.535
Wind 315 deg - Ice		-23.157	-23.082	-2222.250	2231.391	1.028
Wind 330 deg - Ice		-16.408	-28.235	-2716.985	1582.561	-0.549
Total Weight	46.601			-1.151	0.930	
Wind 0 deg - Service		-0.037	-12.028	-1151.988	5.580	-1.333
Wind 30 deg - Service		6.003	-10.398	-995.480	-573.099	-2.064

<b>tnxTower</b>  <b>Centek Engineering Inc.</b> 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	<b>Job</b> 14033.012 - CT03XC382	<b>Page</b> 16 of 23
	<b>Project</b> 130-ft EEI Monopole - 2 Sunny Lane Westport, CT	<b>Date</b> 10:54:01 11/11/14
	<b>Client</b> Sprint	<b>Designed by</b> TJL

Load Case	Vertical Forces K	Sum of Forces X K	Sum of Forces Z K	Sum of Overturning Moments, $M_x$ kip-ft	Sum of Overturning Moments, $M_z$ kip-ft	Sum of Torques kip-ft
Wind 45 deg - Service		8.508	-8.479	-811.628	-813.276	-2.228
Wind 60 deg - Service		10.434	-5.982	-572.543	-997.967	-2.241
Wind 90 deg - Service		12.069	0.037	3.498	-1155.181	-1.818
Wind 120 deg - Service		10.471	6.046	578.294	-1002.616	-0.908
Wind 135 deg - Service		8.560	8.531	815.901	-819.851	-0.343
Wind 150 deg - Service		6.066	10.435	997.828	-581.152	0.245
Wind 180 deg - Service		0.037	12.028	1149.686	-3.719	1.333
Wind 210 deg - Service		-6.003	10.398	993.178	574.960	2.064
Wind 225 deg - Service		-8.508	8.479	809.326	815.137	2.228
Wind 240 deg - Service		-10.434	5.982	570.241	999.828	2.241
Wind 270 deg - Service		-12.069	-0.037	-5.800	1157.042	1.818
Wind 300 deg - Service		-10.471	-6.046	-580.596	1004.477	0.908
Wind 315 deg - Service		-8.560	-8.531	-818.203	821.712	0.343
Wind 330 deg - Service		-6.066	-10.435	-1000.130	583.013	-0.245

## Load Combinations

Comb. No.	Description
1	Dead Only
2	Dead+Wind 0 deg - No Ice
3	Dead+Wind 30 deg - No Ice
4	Dead+Wind 45 deg - No Ice
5	Dead+Wind 60 deg - No Ice
6	Dead+Wind 90 deg - No Ice
7	Dead+Wind 120 deg - No Ice
8	Dead+Wind 135 deg - No Ice
9	Dead+Wind 150 deg - No Ice
10	Dead+Wind 180 deg - No Ice
11	Dead+Wind 210 deg - No Ice
12	Dead+Wind 225 deg - No Ice
13	Dead+Wind 240 deg - No Ice
14	Dead+Wind 270 deg - No Ice
15	Dead+Wind 300 deg - No Ice
16	Dead+Wind 315 deg - No Ice
17	Dead+Wind 330 deg - No Ice
18	Dead+Ice+Temp
19	Dead+Wind 0 deg+Ice+Temp
20	Dead+Wind 30 deg+Ice+Temp
21	Dead+Wind 45 deg+Ice+Temp
22	Dead+Wind 60 deg+Ice+Temp
23	Dead+Wind 90 deg+Ice+Temp
24	Dead+Wind 120 deg+Ice+Temp
25	Dead+Wind 135 deg+Ice+Temp
26	Dead+Wind 150 deg+Ice+Temp
27	Dead+Wind 180 deg+Ice+Temp
28	Dead+Wind 210 deg+Ice+Temp
29	Dead+Wind 225 deg+Ice+Temp
30	Dead+Wind 240 deg+Ice+Temp
31	Dead+Wind 270 deg+Ice+Temp
32	Dead+Wind 300 deg+Ice+Temp
33	Dead+Wind 315 deg+Ice+Temp
34	Dead+Wind 330 deg+Ice+Temp
35	Dead+Wind 0 deg - Service
36	Dead+Wind 30 deg - Service
37	Dead+Wind 45 deg - Service

<b>tnxTower</b>  <b>Centek Engineering Inc.</b> 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	<b>Job</b> 14033.012 - CT03XC382	<b>Page</b> 17 of 23
	<b>Project</b> 130-ft EEI Monopole - 2 Sunny Lane Westport, CT	<b>Date</b> 10:54:01 11/11/14
	<b>Client</b> Sprint	<b>Designed by</b> TJJ

Comb. No.	Description
38	Dead+Wind 60 deg - Service
39	Dead+Wind 90 deg - Service
40	Dead+Wind 120 deg - Service
41	Dead+Wind 135 deg - Service
42	Dead+Wind 150 deg - Service
43	Dead+Wind 180 deg - Service
44	Dead+Wind 210 deg - Service
45	Dead+Wind 225 deg - Service
46	Dead+Wind 240 deg - Service
47	Dead+Wind 270 deg - Service
48	Dead+Wind 300 deg - Service
49	Dead+Wind 315 deg - Service
50	Dead+Wind 330 deg - Service

### Maximum Member Forces

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Force K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
L1	130 - 82.17	Pole	Max Tension	1	0.000	0.000	0.000
			Max. Compression	18	-26.587	1.622	1.800
			Max. Mx	14	-17.397	786.435	5.610
			Max. My	2	-17.409	5.536	781.160
			Max. Vy	14	-29.130	786.435	5.610
			Max. Vx	2	-28.989	5.536	781.160
			Max. Torque	4			7.201
L2	82.17 - 42.01	Pole	Max Tension	1	0.000	0.000	0.000
			Max. Compression	18	-38.905	1.599	1.971
			Max. Mx	14	-28.450	2017.310	10.589
			Max. My	2	-28.456	10.371	2006.754
			Max. Vy	14	-34.183	2017.310	10.589
			Max. Vx	2	-34.046	10.371	2006.754
			Max. Torque	4			7.313
L3	42.01 - 0	Pole	Max Tension	1	0.000	0.000	0.000
			Max. Compression	18	-58.534	1.599	1.971
			Max. Mx	14	-46.581	3814.402	16.545
			Max. My	2	-46.581	16.322	3797.207
			Max. Vy	14	-39.128	3814.402	16.545
			Max. Vx	2	-38.994	16.322	3797.207
			Max. Torque	5			7.216

### Maximum Reactions

Location	Condition	Gov. Load Comb.	Vertical K	Horizontal, X K	Horizontal, Z K
Pole	Max. Vert	31	58.534	32.657	0.092
	Max. H <sub>x</sub>	14	46.601	39.104	0.119
	Max. H <sub>z</sub>	2	46.601	0.119	38.970
	Max. M <sub>x</sub>	2	3797.207	0.119	38.970
	Max. M <sub>z</sub>	6	3812.483	-39.104	-0.119
	Max. Torsion	5	7.213	-33.805	19.382
	Min. Vert	1	46.601	0.000	0.000
	Min. H <sub>x</sub>	6	46.601	-39.104	-0.119
	Min. H <sub>z</sub>	10	46.601	-0.119	-38.970

<b>tnxTower</b>  <b>Centek Engineering Inc.</b> 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	<b>Job</b> 14033.012 - CT03XC382	<b>Page</b> 18 of 23
	<b>Project</b> 130-ft EEI Monopole - 2 Sunny Lane Westport, CT	<b>Date</b> 10:54:01 11/11/14
	<b>Client</b> Sprint	<b>Designed by</b> TJL

Location	Condition	Gov. Load Comb.	Vertical K	Horizontal, X K	Horizontal, Z K
	Min. M <sub>x</sub>	10	-3794.838	-0.119	-38.970
	Min. M <sub>z</sub>	14	-3814.402	39.104	0.119
	Min. Torsion	13	-7.212	33.805	-19.382

## Tower Mast Reaction Summary

Load Combination	Vertical K	Shear <sub>x</sub> K	Shear <sub>z</sub> K	Overturning Moment, M <sub>x</sub> kip-ft	Overturning Moment, M <sub>z</sub> kip-ft	Torque kip-ft
Dead Only	46.601	0.000	0.000	-1.151	0.930	0.000
Dead+Wind 0 deg - No Ice	46.601	-0.119	-38.970	-3797.207	16.322	-4.287
Dead+Wind 30 deg - No Ice	46.601	19.448	-33.690	-3280.954	-1892.476	-6.640
Dead+Wind 45 deg - No Ice	46.601	27.566	-27.472	-2674.506	-2684.711	-7.170
Dead+Wind 60 deg - No Ice	46.601	33.805	-19.382	-1885.875	-3293.917	-7.213
Dead+Wind 90 deg - No Ice	46.601	39.104	0.119	14.195	-3812.483	-5.853
Dead+Wind 120 deg - No Ice	46.601	33.925	19.589	1910.127	-3309.253	-2.925
Dead+Wind 135 deg - No Ice	46.601	27.735	27.641	2693.860	-2706.414	-1.107
Dead+Wind 150 deg - No Ice	46.601	19.655	33.809	3293.935	-1919.074	0.786
Dead+Wind 180 deg - No Ice	46.601	0.119	38.970	3794.838	-14.417	4.287
Dead+Wind 210 deg - No Ice	46.601	-19.448	33.690	3278.597	1894.375	6.640
Dead+Wind 225 deg - No Ice	46.601	-27.566	27.472	2672.155	2686.613	7.170
Dead+Wind 240 deg - No Ice	46.601	-33.805	19.382	1883.527	3295.823	7.212
Dead+Wind 270 deg - No Ice	46.601	-39.104	-0.119	-16.544	3814.402	5.853
Dead+Wind 300 deg - No Ice	46.601	-33.925	-19.589	-1912.488	3311.177	2.925
Dead+Wind 315 deg - No Ice	46.601	-27.735	-27.641	-2696.226	2708.335	1.107
Dead+Wind 330 deg - No Ice	46.601	-19.655	-33.809	-3296.306	1920.990	-0.786
Dead+Ice+Temp	58.534	0.000	0.000	-1.971	1.599	-0.000
Dead+Wind 0 deg+Ice+Temp	58.534	-0.092	-32.550	-3209.818	13.639	-3.455
Dead+Wind 30 deg+Ice+Temp	58.534	16.248	-28.143	-2774.065	-1598.779	-5.443
Dead+Wind 45 deg+Ice+Temp	58.534	23.026	-22.951	-2261.803	-2267.900	-5.909
Dead+Wind 60 deg+Ice+Temp	58.534	28.235	-16.195	-1595.542	-2782.351	-5.973
Dead+Wind 90 deg+Ice+Temp	58.534	32.657	0.092	9.950	-3219.942	-4.902
Dead+Wind 120 deg+Ice+Temp	58.534	28.328	16.355	1612.219	-2794.314	-2.518
Dead+Wind 135 deg+Ice+Temp	58.534	23.157	23.082	2274.661	-2284.826	-1.023
Dead+Wind 150 deg+Ice+Temp	58.534	16.408	28.235	2781.953	-1619.520	0.541
Dead+Wind 180 deg+Ice+Temp	58.534	0.092	32.550	3205.730	-10.331	3.455
Dead+Wind 210 deg+Ice+Temp	58.534	-16.248	28.143	2769.988	1602.082	5.443
Dead+Wind 225 deg+Ice+Temp	58.534	-23.026	22.951	2257.732	2271.205	5.909
Dead+Wind 240 deg+Ice+Temp	58.534	-28.235	16.195	1591.474	2785.661	5.972
Dead+Wind 270 deg+Ice+Temp	58.534	-32.657	-0.092	-14.019	3223.263	4.902
Dead+Wind 300 deg+Ice+Temp	58.534	-28.328	-16.355	-1616.298	2797.640	2.517
Dead+Wind 315 deg+Ice+Temp	58.534	-23.157	-23.082	-2278.746	2288.151	1.023
Dead+Wind 330 deg+Ice+Temp	58.534	-16.408	-28.235	-2786.042	1622.840	-0.541
Dead+Wind 0 deg - Service	46.601	-0.037	-12.028	-1173.283	5.708	-1.328
Dead+Wind 30 deg - Service	46.601	6.003	-10.398	-1013.878	-583.668	-2.056
Dead+Wind 45 deg - Service	46.601	8.508	-8.479	-826.628	-828.286	-2.220
Dead+Wind 60 deg - Service	46.601	10.434	-5.982	-583.124	-1016.392	-2.233
Dead+Wind 90 deg - Service	46.601	12.069	0.037	3.559	-1176.516	-1.812
Dead+Wind 120 deg - Service	46.601	10.471	6.046	588.969	-1021.136	-0.906
Dead+Wind 135 deg - Service	46.601	8.560	8.531	830.963	-834.996	-0.343
Dead+Wind 150 deg - Service	46.601	6.066	10.435	1016.247	-591.887	0.244
Dead+Wind 180 deg - Service	46.601	0.037	12.028	1170.906	-3.784	1.328
Dead+Wind 210 deg - Service	46.601	-6.003	10.398	1011.503	585.592	2.056
Dead+Wind 225 deg - Service	46.601	-8.508	8.479	824.252	830.210	2.220
Dead+Wind 240 deg - Service	46.601	-10.434	5.982	580.749	1018.316	2.233
Dead+Wind 270 deg - Service	46.601	-12.069	-0.037	-5.934	1178.442	1.812
Dead+Wind 300 deg - Service	46.601	-10.471	-6.046	-591.345	1023.063	0.906

<b>tnxTower</b>  <b>Centek Engineering Inc.</b> 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	<b>Job</b> 14033.012 - CT03XC382	<b>Page</b> 19 of 23
	<b>Project</b> 130-ft EEI Monopole - 2 Sunny Lane Westport, CT	<b>Date</b> 10:54:01 11/11/14
	<b>Client</b> Sprint	<b>Designed by</b> TJL

Load Combination	Vertical K	Shear <sub>x</sub> K	Shear <sub>z</sub> K	Overturning Moment, M <sub>x</sub> kip-ft	Overturning Moment, M <sub>z</sub> kip-ft	Torque kip-ft
Dead+Wind 315 deg - Service	46.601	-8.560	-8.531	-833.340	836.922	0.343
Dead+Wind 330 deg - Service	46.601	-6.066	-10.435	-1018.624	593.812	-0.244

## Solution Summary

Load Comb.	Sum of Applied Forces			Sum of Reactions			% Error
	PX K	PY K	PZ K	PX K	PY K	PZ K	
1	0.000	-46.601	0.000	0.000	46.601	0.000	0.000%
2	-0.119	-46.601	-38.970	0.119	46.601	38.970	0.000%
3	19.448	-46.601	-33.690	-19.448	46.601	33.690	0.000%
4	27.566	-46.601	-27.472	-27.566	46.601	27.472	0.000%
5	33.805	-46.601	-19.382	-33.805	46.601	19.382	0.000%
6	39.104	-46.601	0.119	-39.104	46.601	-0.119	0.000%
7	33.925	-46.601	19.589	-33.925	46.601	-19.589	0.000%
8	27.735	-46.601	27.641	-27.735	46.601	-27.641	0.000%
9	19.655	-46.601	33.809	-19.655	46.601	-33.809	0.000%
10	0.119	-46.601	38.970	-0.119	46.601	-38.970	0.000%
11	-19.448	-46.601	33.690	19.448	46.601	-33.690	0.000%
12	-27.566	-46.601	27.472	27.566	46.601	-27.472	0.000%
13	-33.805	-46.601	19.382	33.805	46.601	-19.382	0.000%
14	-39.104	-46.601	-0.119	39.104	46.601	0.119	0.000%
15	-33.925	-46.601	-19.589	33.925	46.601	19.589	0.000%
16	-27.735	-46.601	-27.641	27.735	46.601	27.641	0.000%
17	-19.655	-46.601	-33.809	19.655	46.601	33.809	0.000%
18	0.000	-58.534	0.000	0.000	58.534	0.000	0.000%
19	-0.092	-58.534	-32.550	0.092	58.534	32.550	0.000%
20	16.248	-58.534	-28.143	-16.248	58.534	28.143	0.000%
21	23.026	-58.534	-22.951	-23.026	58.534	22.951	0.000%
22	28.235	-58.534	-16.195	-28.235	58.534	16.195	0.000%
23	32.657	-58.534	0.092	-32.657	58.534	-0.092	0.000%
24	28.328	-58.534	16.355	-28.328	58.534	-16.355	0.000%
25	23.157	-58.534	-23.082	23.157	58.534	-23.082	0.000%
26	16.408	-58.534	28.235	-16.408	58.534	-28.235	0.000%
27	0.092	-58.534	32.550	-0.092	58.534	-32.550	0.000%
28	-16.248	-58.534	28.143	16.248	58.534	-28.143	0.000%
29	-23.026	-58.534	22.951	23.026	58.534	-22.951	0.000%
30	-28.235	-58.534	16.195	28.235	58.534	-16.195	0.000%
31	-32.657	-58.534	-0.092	32.657	58.534	0.092	0.000%
32	-28.328	-58.534	-16.355	28.328	58.534	16.355	0.000%
33	-23.157	-58.534	-23.082	23.157	58.534	23.082	0.000%
34	-16.408	-58.534	-28.235	16.408	58.534	28.235	0.000%
35	-0.037	-46.601	-12.028	0.037	46.601	12.028	0.000%
36	6.003	-46.601	-10.398	-6.003	46.601	10.398	0.000%
37	8.508	-46.601	-8.479	-8.508	46.601	8.479	0.000%
38	10.434	-46.601	-5.982	-10.434	46.601	5.982	0.000%
39	12.069	-46.601	0.037	-12.069	46.601	-0.037	0.000%
40	10.471	-46.601	6.046	-10.471	46.601	-6.046	0.000%
41	8.560	-46.601	8.531	-8.560	46.601	-8.531	0.000%
42	6.066	-46.601	10.435	-6.066	46.601	-10.435	0.000%
43	0.037	-46.601	12.028	-0.037	46.601	-12.028	0.000%
44	-6.003	-46.601	10.398	6.003	46.601	-10.398	0.000%
45	-8.508	-46.601	8.479	8.508	46.601	-8.479	0.000%
46	-10.434	-46.601	5.982	10.434	46.601	-5.982	0.000%
47	-12.069	-46.601	-0.037	12.069	46.601	0.037	0.000%
48	-10.471	-46.601	-6.046	10.471	46.601	6.046	0.000%
49	-8.560	-46.601	-8.531	8.560	46.601	8.531	0.000%
50	-6.066	-46.601	-10.435	6.066	46.601	10.435	0.000%



<b>tnxTower</b>  <b>Centek Engineering Inc.</b> 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	<b>Job</b>	14033.012 - CT03XC382	<b>Page</b>	20 of 23
	<b>Project</b>	130-ft EEI Monopole - 2 Sunny Lane Westport, CT	<b>Date</b>	10:54:01 11/11/14
	<b>Client</b>	Sprint	<b>Designed by</b>	TJL

## Non-Linear Convergence Results

<i>Load Combination</i>	<i>Converged?</i>	<i>Number of Cycles</i>	<i>Displacement Tolerance</i>	<i>Force Tolerance</i>
1	Yes	4	0.00000001	0.00000001
2	Yes	4	0.00000001	0.00023252
3	Yes	4	0.00000001	0.00098945
4	Yes	5	0.00000001	0.00002724
5	Yes	5	0.00000001	0.00002781
6	Yes	4	0.00000001	0.00027555
7	Yes	5	0.00000001	0.00002205
8	Yes	5	0.00000001	0.00002640
9	Yes	5	0.00000001	0.00002288
10	Yes	4	0.00000001	0.00020942
11	Yes	5	0.00000001	0.00002735
12	Yes	5	0.00000001	0.00002714
13	Yes	4	0.00000001	0.00098276
14	Yes	4	0.00000001	0.00029896
15	Yes	5	0.00000001	0.00002515
16	Yes	5	0.00000001	0.00002651
17	Yes	5	0.00000001	0.00002398
18	Yes	4	0.00000001	0.00000001
19	Yes	5	0.00000001	0.00003638
20	Yes	5	0.00000001	0.00006476
21	Yes	5	0.00000001	0.00007594
22	Yes	5	0.00000001	0.00007231
23	Yes	5	0.00000001	0.00003699
24	Yes	5	0.00000001	0.00006655
25	Yes	5	0.00000001	0.00007532
26	Yes	5	0.00000001	0.00006737
27	Yes	5	0.00000001	0.00003614
28	Yes	5	0.00000001	0.00007171
29	Yes	5	0.00000001	0.00007582
30	Yes	5	0.00000001	0.00006463
31	Yes	5	0.00000001	0.00003727
32	Yes	5	0.00000001	0.00007002
33	Yes	5	0.00000001	0.00007579
34	Yes	5	0.00000001	0.00006873
35	Yes	4	0.00000001	0.00003432
36	Yes	4	0.00000001	0.00005771
37	Yes	4	0.00000001	0.00008429
38	Yes	4	0.00000001	0.00009235
39	Yes	4	0.00000001	0.00004228
40	Yes	4	0.00000001	0.00005444
41	Yes	4	0.00000001	0.00006866
42	Yes	4	0.00000001	0.00005715
43	Yes	4	0.00000001	0.00003325
44	Yes	4	0.00000001	0.00008905
45	Yes	4	0.00000001	0.00008384
46	Yes	4	0.00000001	0.00005885
47	Yes	4	0.00000001	0.00004341
48	Yes	4	0.00000001	0.00007120
49	Yes	4	0.00000001	0.00006973
50	Yes	4	0.00000001	0.00006354

<b>tnxTower</b>  <b>Centek Engineering Inc.</b> 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	<b>Job</b> 14033.012 - CT03XC382	<b>Page</b> 21 of 23
	<b>Project</b> 130-ft EEI Monopole - 2 Sunny Lane Westport, CT	<b>Date</b> 10:54:01 11/11/14
	<b>Client</b> Sprint	<b>Designed by</b> TJL

### Maximum Tower Deflections - Service Wind

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
L1	130 - 82.17	14.593	48	0.946	0.009
L2	87.84 - 42.01	6.871	48	0.738	0.004
L3	49.01 - 0	2.132	48	0.396	0.001

### Critical Deflections and Radius of Curvature - Service Wind

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
130.000	LPA-80063/6CF	48	14.593	0.946	0.009	59087
129.000	EEI Low Profile Platform	48	14.398	0.942	0.009	59087
124.000	VHLP800-11-DW1	48	13.423	0.923	0.008	49239
120.000	APXVSPP18-C-A20	48	12.648	0.907	0.007	29543
119.000	EEI Low Profile Platform	48	12.455	0.903	0.007	26858
117.000	TD-RRH8x20-25	48	12.070	0.895	0.007	22726
113.000	GPS	48	11.308	0.878	0.007	17378
110.000	RR90-17-02DP	48	10.743	0.864	0.006	14771
109.000	EEI Low Profile Platform	48	10.556	0.860	0.006	14068
104.000	GPS	48	9.637	0.835	0.005	11362
102.500	Valmont Uni-Tri Bracket	48	9.366	0.828	0.005	10742
100.000	7770.00	48	8.920	0.814	0.005	9847
99.000	EEI Low Profile Platform	48	8.743	0.809	0.005	9529
90.000	(3) 6"x3" Pipe Mount	48	7.218	0.753	0.004	7403
89.000	EEI Low Profile Platform	48	7.056	0.746	0.004	7247
72.000	GPS	48	4.575	0.609	0.002	6143
70.000	GPS	48	4.319	0.591	0.002	6049
60.000	GPS	48	3.160	0.498	0.002	5618

### Maximum Tower Deflections - Design Wind

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
L1	130 - 82.17	47.136	15	3.052	0.029
L2	87.84 - 42.01	22.213	15	2.385	0.012
L3	49.01 - 0	6.898	15	1.282	0.004

### Critical Deflections and Radius of Curvature - Design Wind

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
130.000	LPA-80063/6CF	15	47.136	3.052	0.029	18466
129.000	EEI Low Profile Platform	15	46.507	3.040	0.028	18466
124.000	VHLP800-11-DW1	15	43.362	2.978	0.026	15388
120.000	APXVSPP18-C-A20	15	40.860	2.928	0.024	9233

<b>tnxTower</b>  <b>Centek Engineering Inc.</b> 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	<b>Job</b>	14033.012 - CT03XC382	<b>Page</b>	22 of 23
	<b>Project</b>	130-ft EEI Monopole - 2 Sunny Lane Westport, CT	<b>Date</b>	10:54:01 11/11/14
	<b>Client</b>	Sprint	<b>Designed by</b>	TJL

Elevation	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
119.000	EEI Low Profile Platform	15	40.237	2.915	0.024	8393
117.000	TD-RRH8x20-25	15	38.997	2.889	0.023	7102
113.000	GPS	15	36.536	2.835	0.021	5430
110.000	RR90-17-02DP	15	34.714	2.792	0.020	4615
109.000	EEI Low Profile Platform	15	34.112	2.777	0.019	4395
104.000	GPS	15	31.143	2.699	0.017	3549
102.500	Valmont Uni-Tri Bracket	15	30.269	2.674	0.017	3356
100.000	7770.00	15	28.829	2.631	0.016	3076
99.000	EEI Low Profile Platform	15	28.260	2.613	0.015	2976
90.000	(3) 6'x3" Pipe Mount	15	23.336	2.434	0.012	2311
89.000	EEI Low Profile Platform	15	22.813	2.412	0.012	2262
72.000	GPS	15	14.797	1.969	0.008	1910
70.000	GPS	15	13.969	1.910	0.007	1879
60.000	GPS	15	10.220	1.611	0.006	1742

### Compression Checks

### Pole Design Data

Section No.	Elevation ft	Size	L ft	L <sub>a</sub> ft	Kl/r	F <sub>a</sub> ksi	A in <sup>2</sup>	Actual P K	Allow. P <sub>a</sub> K	Ratio P/P <sub>a</sub>
L1	130 - 82.17 (1)	TP41.22x28.18x0.313	47.830	0.000	0.0	39.000	39.042	-17.390	1522.630	0.011
L2	82.17 - 42.01 (2)	TP51.42x39.049x0.375	45.830	0.000	0.0	39.000	58.507	-28.446	2281.790	0.012
L3	42.01 - 0 (3)	TP62x48.781x0.438	49.010	0.000	0.0	39.000	85.487	-46.581	3334.000	0.014

### Pole Bending Design Data

Section No.	Elevation ft	Size	Actual M <sub>x</sub> kip-ft	Actual f <sub>bx</sub> ksi	Allow. F <sub>bx</sub> ksi	Ratio f <sub>bx</sub> /F <sub>bx</sub>	Actual M <sub>y</sub> kip-ft	Actual f <sub>by</sub> ksi	Allow. F <sub>by</sub> ksi	Ratio f <sub>by</sub> /F <sub>by</sub>
L1	130 - 82.17 (1)	TP41.22x28.18x0.313	789.521	24.986	39.000	0.641	0.000	0.000	39.000	0.000
L2	82.17 - 42.01 (2)	TP51.42x39.049x0.375	2023.23	34.203	39.000	0.877	0.000	0.000	39.000	0.000
L3	42.01 - 0 (3)	TP62x48.781x0.438	3823.80	35.307	39.000	0.905	0.000	0.000	39.000	0.000

### Pole Shear Design Data

Section No.	Elevation ft	Size	Actual V K	Actual f <sub>v</sub> ksi	Allow. F <sub>v</sub> ksi	Ratio f <sub>v</sub> /F <sub>v</sub>	Actual T kip-ft	Actual f <sub>vt</sub> ksi	Allow. F <sub>vt</sub> ksi	Ratio f <sub>vt</sub> /F <sub>vt</sub>
L1	130 - 82.17 (1)	TP41.22x28.18x0.313	29.201	0.748	26.000	0.058	2.658	0.041	26.000	0.002
L2	82.17 - 42.01 (2)	TP51.42x39.049x0.375	34.255	0.585	26.000	0.045	2.927	0.024	26.000	0.001
L3	42.01 - 0 (3)	TP62x48.781x0.438	39.198	0.459	26.000	0.035	2.925	0.013	26.000	0.001

<b>tnxTower</b>  <b>Centek Engineering Inc.</b> 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	<b>Job</b> 14033.012 - CT03XC382	<b>Page</b> 23 of 23
	<b>Project</b> 130-ft EEI Monopole - 2 Sunny Lane Westport, CT	<b>Date</b> 10:54:01 11/11/14
	<b>Client</b> Sprint	<b>Designed by</b> TJL

Section No.	Elevation ft	Size	Actual V K	Actual f <sub>v</sub> ksi	Allow. F <sub>v</sub> ksi	Ratio f <sub>v</sub> / F <sub>v</sub>	Actual T kip-ft	Actual f <sub>vt</sub> ksi	Allow. F <sub>vt</sub> ksi	Ratio f <sub>vt</sub> / F <sub>vt</sub>
-------------	-----------------	------	------------------	---------------------------------	---------------------------------	---	-----------------------	----------------------------------	----------------------------------	---

### Pole Interaction Design Data

Section No.	Elevation ft	Ratio P P <sub>a</sub>	Ratio f <sub>bx</sub> F <sub>bx</sub>	Ratio f <sub>by</sub> F <sub>by</sub>	Ratio f <sub>v</sub> F <sub>v</sub>	Ratio f <sub>vt</sub> F <sub>vt</sub>	Comb. Stress Ratio	Allow. Stress Ratio	Criteria
L1	130 - 82.17 (1)	0.011	0.641	0.000	0.058	0.002	0.653 ✓	1.333	H1-3+VT ✓
L2	82.17 - 42.01 (2)	0.012	0.877	0.000	0.045	0.001	0.890 ✓	1.333	H1-3+VT ✓
L3	42.01 - 0 (3)	0.014	0.905	0.000	0.035	0.001	0.920 ✓	1.333	H1-3+VT ✓

### Section Capacity Table

Section No.	Elevation ft	Component Type	Size	Critical Element	P K	SF*P <sub>allow</sub> K	% Capacity	Pass Fail
L1	130 - 82.17	Pole	TP41.22x28.18x0.313	1	-17.390	2029.666	49.0	Pass
L2	82.17 - 42.01	Pole	TP51.42x39.049x0.375	2	-28.446	3041.626	66.8	Pass
L3	42.01 - 0	Pole	TP62x48.781x0.438	3	-46.581	4444.222	69.0	Pass
Summary								
Pole (L3)							69.0	Pass
<b>RATING =</b>							<b>69.0</b>	<b>Pass</b>

Subject:

Anchor Bolt and Baseplate Analysis

Location:

130-ft EEI Monopole  
 Westport, CT

Rev. 0: 11/11/14

Prepared by: T.J.L Checked by: C.F.C.  
 Job No. 14033.012

**Anchor Bolt and Base Plate Analysis:**

**Input Data:**

Tower Reactions:

Overturing Moment = OM := 3824-ft-kips (Input From tnxTower)  
 Shear Force = Shear := 39-kips (Input From tnxTower)  
 Axial Force = Axial := 47-kips (Input From tnxTower)

Anchor Bolt Data:

Use ASTM A615 Grade 75  
 Number of Anchor Bolts = N := 20 (User Input)  
 Diameter of Bolt Circle =  $D_{bc}$  := 71.00-in (User Input)  
 Bolt "Column" Distance = l := 3.25-in (User Input)  
 Bolt Ultimate Strenght =  $F_u$  := 100-ksi (User Input)  
 Bolt Yeild Strenght =  $F_y$  := 75-ksi (User Input)  
 Bolt Modulus = E := 29000-ksi (User Input)  
 Diameter of Anchor Bolts = D := 2.25-in (User Input)  
 Threads per Inch = n := 4.5 (User Input)

Base Plate Data:

Use ASTM A572 Mod 60  
 Plate Yield Strength =  $F_{y_{bp}}$  := 60-ksi (User Input)  
 Base Plate Thickness =  $t_{bp}$  := 2.0-in (User Input)  
 Base Plate Diameter =  $D_{bp}$  := 77.00-in (User Input)  
 Outer Pole Diameter =  $D_{pole}$  := 62.00-in (User Input)

**Geometric Layout Data:**

Distance from Bolts to Centroid of Pole:

Radius of Bolt Circle =:  $R_{bc} := \frac{D_{bc}}{2} = 35.5\text{-in}$

Distance to Bolts =  $i := 1..N$

$$d_i := \begin{cases} \theta \leftarrow 2\pi \cdot \left(\frac{i}{N}\right) \\ d \leftarrow R_{bc} \cdot \sin(\theta) \end{cases}$$

	$d_1 = 10.97\text{-in}$	$d_7 = 28.72\text{-in}$
	$d_2 = 20.87\text{-in}$	$d_8 = 20.87\text{-in}$
	$d_3 = 28.72\text{-in}$	$d_9 = 10.97\text{-in}$
	$d_4 = 33.76\text{-in}$	$d_{10} = 0.00\text{-in}$
	$d_5 = 35.50\text{-in}$	$d_{11} = -10.97\text{-in}$
	$d_6 = 33.76\text{-in}$	etc.

Critical Distances For Bending in Plate:

Outer Pole Radius =  $R_{pole} := \frac{D_{pole}}{2} = 31\text{-in}$

Moment Arms of Bolts about Neutral Axis =  $MA_i := \text{if}(d_i \geq R_{pole}, d_i - R_{pole}, 0\text{in})$

$MA_1 = 0.00\text{-in}$	$MA_7 = 0.00\text{-in}$
$MA_2 = 0.00\text{-in}$	$MA_8 = 0.00\text{-in}$
$MA_3 = 0.00\text{-in}$	$MA_9 = 0.00\text{-in}$
$MA_4 = 2.76\text{-in}$	$MA_{10} = 0.00\text{-in}$
$MA_5 = 4.50\text{-in}$	$MA_{11} = 0.00\text{-in}$
$MA_6 = 2.76\text{-in}$	etc

Effective Width of Baseplate for Bending =  $B_{eff} := .8 \cdot 2 \cdot \sqrt{\left(\frac{D_{bp}}{2}\right)^2 - \left(\frac{D_{pole}}{2}\right)^2} = 36.53\text{-in}$

### Anchor Bolt Analysis:

#### Calculated Anchor Bolt Properties:

Polar Moment of Inertia =  $I_p := \sum_i (d_i)^2 = 1.26 \times 10^4 \cdot \text{in}^2$

Gross Area of Bolt =  $A_g := \frac{\pi}{4} \cdot D^2 = 3.976 \cdot \text{in}^2$

Net Area of Bolt =  $A_n := \frac{\pi}{4} \cdot \left( D - \frac{0.9743 \cdot \text{in}}{n} \right)^2 = 3.248 \cdot \text{in}^2$

Net Diameter =  $D_n := \frac{2 \cdot \sqrt{A_n}}{\sqrt{\pi}} = 2.033 \cdot \text{in}$

Radius of Gyration of Bolt =  $r := \frac{D_n}{4} = 0.508 \cdot \text{in}$

Section Modulus of Bolt =  $S_x := \frac{\pi \cdot D_n^3}{32} = 0.826 \cdot \text{in}^3$

#### Check Anchor Bolt Tension Force:

Maximum Tensile Force =  $T_{\text{Max}} := \text{OM} \cdot \frac{R_{bc}}{I_p} - \frac{\text{Axial}}{N} = 126.9 \cdot \text{kips}$

Allowable Tensile Force =  $T_{\text{ALL.Gross}} := 1.333 \cdot (0.33 \cdot A_g \cdot F_u) = 174.9 \cdot \text{kips}$  (1.333 increase allowed per TIA/EIA)

$T_{\text{ALL.Net}} := 1.333 \cdot (0.60 \cdot A_n \cdot F_y) = 194.8 \cdot \text{kips}$  (1.333 increase allowed per TIA/EIA)

Bolt Tension % of Capacity =  $\frac{T_{\text{Max}}}{T_{\text{ALL.Net}}} = 65.1\%$  Bolts are "upset bolts". Use net area per AISC

Condition1 =  $\text{Condition1} := \text{if} \left( \frac{T_{\text{Max}}}{T_{\text{ALL.Net}}} \leq 1.00, \text{"OK"}, \text{"Overstressed"} \right)$

Condition1 = "OK"

#### Check Anchor Bolt Bending Stress:

Maximum Bending Moment =  $M_x := \left( \frac{\text{Shear}}{N} \right) \cdot l = 0.528 \cdot \text{ft-kips}$

Maximum Bending Stress =  $f_{bx} := \frac{M_x}{S_x} = 7.7 \cdot \text{ksi}$

Allowable Bending Stress =  $F_{bx} := 1.333 \cdot 0.6 \cdot F_y = 60 \cdot \text{ksi}$  (1.333 increase allowed per TIA/EIA)

Check Combined Stress Requirement:

Per ASCE Manual 72: "If the clearance between the base plate and concrete does not exceed two times the bolt diameter a bending stress analysis of the bolts is NOT normally required."

$$l := \begin{cases} l & \text{if } l > 2 \cdot D_n = 0 \text{ in} \\ 0 & \text{otherwise} \end{cases}$$

$$f_{bx} := \begin{cases} f_{bx} & \text{if } l > 2 \cdot D_n = 0 \text{ ksi} \\ 0 & \text{otherwise} \end{cases}$$

Check Anchor Bolt Compression/Combined Stress:

Maximum Compressive Force =

$$C_{Max} := OM \cdot \frac{R_{bc}}{I_p} + \frac{Axial}{N} = 131.6 \text{ kips}$$

Maximum Compressive Stress =

$$f_a := \frac{C_{Max}}{A_n} = 40.5 \text{ ksi}$$

$$K := 0.65$$

$$C_c := \sqrt{\frac{2 \cdot \pi^2 \cdot E}{F_y}} = 87.364$$

$$F_a := \begin{cases} \frac{\left[ 1 - \frac{\left( \frac{K \cdot l}{r} \right)^2}{2 \cdot C_c^2} \right] \cdot F_y}{\frac{5}{3} + \frac{3 \cdot \left( \frac{K \cdot l}{r} \right)}{8 \cdot C_c} - \frac{\left( \frac{K \cdot l}{r} \right)^3}{8 \cdot C_c^3}} & \text{if } \frac{K \cdot l}{r} \leq C_c = 45 \text{ ksi} \\ \frac{12 \cdot \pi^2 \cdot E}{23 \cdot \left( \frac{K \cdot l}{r} \right)^2} & \text{if } \frac{K \cdot l}{r} > C_c \end{cases}$$

Allowable Compressive Stress =

$$F_a := 1.333 \cdot F_a = 60 \text{ ksi} \quad (1.333 \text{ increase allowed per TIA/EIA})$$

Combined Stress % of Capacity =

$$\left( \frac{f_a}{F_a} + \frac{f_{bx}}{F_{bx}} \right) = 67.6 \%$$

Condition 2 =

$$\text{Condition2} := \text{if} \left( \frac{f_a}{F_a} + \frac{f_{bx}}{F_{bx}} \leq 1.00, \text{"OK"}, \text{"Overstressed"} \right)$$

Condition2 = "OK"



Subject:

Anchor Bolt and Baseplate Analysis

Location:

130-ft EEI Monopole  
 Westport, CT

Rev. 0: 11/11/14

Prepared by: T.J.L Checked by: C.F.C.  
 Job No. 14033.012

**Base Plate Analysis:**

Force from Bolts =  $C_i := \frac{OM \cdot d_i}{I_p} + \frac{Axial}{N}$

$C_1 = 42.3$ -kips	$C_7 = 106.9$ -kips
$C_2 = 78.3$ -kips	$C_8 = 78.3$ -kips
$C_3 = 106.9$ -kips	$C_9 = 42.3$ -kips
$C_4 = 125.3$ -kips	$C_{10} = 2.4$ -kips
$C_5 = 131.6$ -kips	$C_{11} = -37.6$ -kips
$C_6 = 125.3$ -kips	etc.

Maximum Bending Stress in Plate =  $f_{bp} := \sum_i \frac{6 \cdot C_i \cdot MA_i}{(B_{eff} t_{bp})^2} = 52.7$ -ksi

Allowable Bending Stress in Plate =  $F_{bp} := 1.33 \cdot 0.75 \cdot F_{y_{bp}} = 59.9$ -ksi

Plate Bending Stress % of Capacity =  $\frac{f_{bp}}{F_{bp}} = 88.1$ -%

Condition3 =  $\text{Condition3} := \text{if} \left( \frac{f_{bp}}{F_{bp}} < 1.00, \text{"Ok"}, \text{"Overstressed"} \right)$

Condition3 = "Ok"

**Standard Monopole Foundation:**

**Input Data:**

Tower Data

Overturning Moment = OM := 3824-ft-kips (User Input from tnxTower)  
 Shear Force = Shear := 39-kip (User Input from tnxTower)  
 Axial Force = Axial := 47-kip (User Input from tnxTower)  
 Tower Height =  $H_t := 130$ -ft (User Input)

Footing Data:

Overall Depth of Footing =  $D_f := 5.5$ -ft (User Input)  
 Length of Pier =  $L_p := 2.5$ -ft (User Input)  
 Extension of Pier Above Grade =  $L_{pag} := 1.0$ -ft (User Input)  
 Diameter of Pier =  $d_p := 8$ -ft (User Input)  
 Thickness of Footing =  $T_f := 3$ -ft (User Input)  
 Width of Footing =  $W_f := 29.5$ -ft (User Input)

Anchor Bolt Data:

Length of Anchor Bolts =  $L_{st} := 72.0$ -in (User Input)  
 Projection of Anchor Bolts Above Pier =  $A_{BP} := 12.0$ -in (User Input)  
 Anchor Bolt Diameter =  $d_{anchor} := 2.25$ -in (User Input)  
 Base Plate Bolt Circle =  $MP := 72.76$ -in (User Input)

Material Properties:

Concrete Compressive Strength =  $f_c := 4000$ -psi (User Input)  
 Steel Reinforcement Yield Strength =  $f_y := 60000$ -psi (User Input)  
 Anchor Bolt Yield Strength =  $f_{ya} := 75000$ -psi (User Input)  
 Internal Friction Angle of Soil =  $\Phi_s := 30$ -deg (User Input)  
 Allowable Soil Bearing Capacity =  $q_s := 3000$ -psf (User Input)  
 Unit Weight of Soil =  $\gamma_{soil} := 100$ -pcf (User Input)  
 Unit Weight of Concrete =  $\gamma_{conc} := 150$ -pcf (User Input)  
 Foundation Bouyancy = Bouyancy := 0 (User Input) (Yes=1 / No=0)  
 Depth to Neglect =  $n := 0$ -ft (User Input)  
 Cohesion of Clay Type Soil =  $c := 0$ -ksf (User Input) (Use 0 for Sandy Soil)  
 Seismic Zone Factor =  $Z := 2$  (User Input) (UBC-1997 Fig 23-2)  
 Coefficient of Friction Between Concrete =  $\mu := 0.45$  (User Input)

Pier Reinforcement:

Bar Size =	$BS_{\text{pier}} := 8$	(User Input)	
Bar Diameter =	$d_{\text{bpier}} := 1.000 \cdot \text{in}$	(User Input)	
Number of Bars =	$NB_{\text{pier}} := 44$	(User Input)	
Clear Cover of Reinforcement =	$Cvr_{\text{pier}} := 3 \cdot \text{in}$	(User Input)	
Reinforcement Location Factor =	$\alpha_{\text{pier}} := 1.0$	(User Input)	(ACI-2008 12.2.4)
Coating Factor =	$\beta_{\text{pier}} := 1.0$	(User Input)	(ACI-2008 12.2.4)
Concrete Strength Factor =	$\lambda_{\text{pier}} := 1.0$	(User Input)	(ACI-2008 12.2.4)
Reinforcement Size Factor =	$\gamma_{\text{pier}} := 1.0$	(User Input)	(ACI-2008 12.2.4)
Diameter of Tie =	$d_{\text{Tie}} := 3 \cdot \text{in}$	(User Input)	

Pad Reinforcement:

Bar Size =	$BS_{\text{top}} := 8$	(User Input)	(Top of Pad)
Bar Diameter =	$d_{\text{btop}} := 1.000 \cdot \text{in}$	(User Input)	(Top of Pad)
Number of Bars =	$NB_{\text{top}} := 28$	(User Input)	(Top of Pad)
Bar Size =	$BS_{\text{bot}} := 8$	(User Input)	(Bottom of Pad)
Bar Diameter =	$d_{\text{bbot}} := 1.000 \cdot \text{in}$	(User Input)	(Bottom of Pad)
Number of Bars =	$NB_{\text{bot}} := 44$	(User Input)	(Bottom of Pad)
Clear Cover of Reinforcement =	$Cvr_{\text{pad}} := 3.0 \cdot \text{in}$	(User Input)	
Reinforcement Location Factor =	$\alpha_{\text{pad}} := 1.0$	(User Input)	(ACI-2008 12.2.4)
Coating Factor =	$\beta_{\text{pad}} := 1.0$	(User Input)	(ACI-2008 12.2.4)
Concrete Strength Factor =	$\lambda_{\text{pad}} := 1.0$	(User Input)	(ACI-2008 12.2.4)
Reinforcement Size Factor =	$\gamma_{\text{pad}} := 1.0$	(User Input)	(ACI-2008 12.2.4)

**Calculated Factors:**

Pier Reinforcement Bar Area =	$A_{\text{bpier}} := \frac{\pi \cdot d_{\text{bpier}}^2}{4} = 0.785 \cdot \text{in}^2$	
Pad Top Reinforcement Bar Area =	$A_{\text{btop}} := \frac{\pi \cdot d_{\text{btop}}^2}{4} = 0.785 \cdot \text{in}^2$	
Pad Bottom Reinforcement Bar Area =	$A_{\text{bbot}} := \frac{\pi \cdot d_{\text{bbot}}^2}{4} = 0.785 \cdot \text{in}^2$	
Coefficient of Lateral Soil Pressure =	$K_p := \frac{1 + \sin(\Phi_s)}{1 - \sin(\Phi_s)} = 3$	
Load Factor =	$LF := \begin{cases} 1.333 & \text{if } H_t \leq 700 \cdot \text{ft} \\ 1.7 & \text{if } H_t \geq 1200 \cdot \text{ft} \\ 1.333 + \left( \frac{H_t - 700 \cdot \text{ft}}{1200 \cdot \text{ft} - 700 \cdot \text{ft}} \right) \cdot 0.4 & \text{otherwise} \end{cases}$	= 1.333

**Stability of Footing:**

Adjusted Concrete Unit Weight =  $\gamma_c := \text{if}(\text{Bouyancy} = 1, \gamma_{\text{conc}} - 62.4\text{pcf}, \gamma_{\text{conc}}) = 150\text{-pcf}$

Adjusted Soil Unit Weight =  $\gamma_s := \text{if}(\text{Bouyancy} = 1, \gamma_{\text{soil}} - 62.4\text{pcf}, \gamma_{\text{soil}}) = 100\text{-pcf}$

Passive Pressure =  $P_{pn} := K_p \cdot \gamma_s \cdot n + c \cdot 2 \cdot \sqrt{K_p} = 0\text{-ksf}$

$P_{pt} := K_p \cdot \gamma_s \cdot (D_f - T_f) + c \cdot 2 \cdot \sqrt{K_p} = 0.75\text{-ksf}$

$P_{top} := \text{if}[n < (D_f - T_f), P_{pt}, P_{pn}] = 0.75\text{-ksf}$

$P_{bot} := K_p \cdot \gamma_s \cdot D_f + c \cdot 2 \cdot \sqrt{K_p} = 1.65\text{-ksf}$

$P_{ave} := \frac{P_{top} + P_{bot}}{2} = 1.2\text{-ksf}$

$T_p := \text{if}[n < (D_f - T_f), T_f, (D_f - n)] = 3$

$A_p := W_f \cdot T_p = 88.5$

Ultimate Shear =  $S_u := P_{ave} \cdot A_p = 106.2\text{-kip}$

Weight of Concrete Pad =  $WT_c := [(W_f^2 \cdot T_f) + d_p^2 \cdot L_p] \cdot \gamma_c = 415.613\text{-kip}$

Weight of Soil Above Footing =  $WT_{s1} := \left[ \begin{array}{l} (W_f^2 - d_p^2) \cdot \left[ (L_p - L_{pag} - n) \text{ if } (L_p - L_{pag} - n) \geq 0 \right. \\ \left. 0 \text{ if } (L_p - L_{pag} - n) \leq 0 \right] \end{array} \right] \cdot \gamma_s = 120.94\text{-kip}$

Weight of Soil Wedge at Back Face =  $WT_{s2} := \left( \frac{D_f^2 \cdot \tan(\phi_s)}{2} \cdot W_f \right) \cdot \gamma_s = 25.761\text{-kip}$

Weight of Soil Wedge at back face Corners =  $WT_{s3} := 2 \cdot \left[ (D_f)^3 \cdot \frac{\tan(\phi_s)}{3} \right] \cdot \gamma_s = 6.404\text{-kips}$

Total Weight =  $WT_{tot} := WT_c + WT_{s1} + \text{Axial} = 583.55\text{-kip}$

Resisting Moment =  $M_r := (WT_{tot}) \cdot \frac{W_f}{2} + S_u \cdot \frac{T_f}{3} + \left[ (WT_{s2} + WT_{s3}) \cdot \left( W_f + \frac{D_f \cdot \tan(\phi_s)}{3} \right) \right] = 9696\text{-kip-ft}$

Overturning Moment =  $M_{ot} := \text{OM} + \text{Shear} \cdot (L_p + T_f) = 4039\text{-kip-ft}$

Factor of Safety Actual =  $FS := \frac{M_r}{M_{ot}} = 2.4$

Factor of Safety Required =  $FS_{req} := 2$

OverTurning\_Moment\_Check :=  $\text{if}(FS \geq FS_{req}, \text{"Okay"}, \text{"No Good"})$

OverTurning\_Moment\_Check = "Okay"

### Shear Capacity in Pier:

Shear Resistance of Pier =  $S_p := \frac{\mu \cdot W_{T_{tot}}}{F_{S_{req}}} = 131.299 \cdot \text{kips}$

Shear\_Check := if( $S_p > \text{Shear}$ , "Okay", "No Good")

Shear\_Check = "Okay"

### Bearing Pressure Caused by Footing:

Area of the Mat =  $A_{mat} := W_f^2 = 870.25$

Section Modulus of Mat =  $S := \frac{W_f^3}{6} = 4278.73 \cdot \text{ft}^3$

Maximum Pressure in Mat =  $P_{max} := \frac{(W_{T_c} + \text{Axial})}{A_{mat}} + \frac{M_{ot}}{S} = 1.475 \cdot \text{ksf}$

Max\_Pressure\_Check := if( $P_{max} < q_s$ , "Okay", "No Good")

Max\_Pressure\_Check = "Okay"

Minimum Pressure in Mat =  $P_{min} := \frac{(W_{T_c} + \text{Axial})}{A_{mat}} - \frac{M_{ot}}{S} = -0.412 \cdot \text{ksf}$

Min\_Pressure\_Check := if( $(P_{min} \geq 0) \cdot (P_{min} < q_s)$ , "Okay", "No Good")

Min\_Pressure\_Check = "No Good"

Distance to Resultant of Pressure Distribution =  $X_p := \frac{P_{max}}{P_{max} - P_{min}} \cdot \frac{1}{3} = 7.686$

Distance to Kern =  $X_k := \frac{W_f}{6} = 4.917$  Since Resultant Force is Not in Kern, Area to which Pressure is Applied Must be Reduced.

Eccentricity =  $e := \frac{M_{ot}}{W_{T_{tot}}} = 6.921$

Adjusted Soil Pressure =  $P_a := \frac{2 \cdot (W_{T_c} + \text{Axial})}{3 \cdot W_f \left( \frac{W_f}{2} - e \right)} = 1.335 \cdot \text{ksf}$

$q_{adj} := \text{if}(P_{min} < 0, P_a, P_{max}) = 1.335 \cdot \text{ksf}$

Pressure\_Check := if( $q_{adj} < q_s$ , "Okay", "No Good")

Pressure\_Check = "Okay"

### Concrete Bearing Capacity:

Strength Reduction Factor =  $\Phi_c := 0.65$  (ACI-2008 9.3.2.2)

Bearing Strength Between Pier and Pad =  $P_b := \Phi_c \cdot 0.85 \cdot f_c \cdot \frac{\pi \cdot d_p^2}{4} = 1.6 \times 10^4 \cdot \text{kips}$  (ACI-2008 10.14)

Bearing\_Check := if( $P_b > \text{LF} \cdot \text{Axial}$ , "Okay", "No Good")

Bearing\_Check = "Okay"

### Shear Strength of Concrete:

Beam Shear: (Critical section located at a distance d from the face of Pier) (ACI 11.3.1.1)

$\Phi_c := 0.85$  (ACI 9.3.2.5)

$d := T_f - C_{vr\_pad} - d_{bbot} = 32 \cdot \text{in}$

$d_1 := \frac{W_f}{2} - \frac{d_p}{2}$

$d_2 := d_1 - d$

$L := \left( \frac{W_f}{2} - e \right) \cdot 3$

Slope := if( $L > W_f$ ,  $\frac{P_{max} - P_{min}}{W_f}$ ,  $\frac{q_{adj}}{L}$ )

$V_{req} := \text{LF} \cdot \left[ (q_{adj} - \text{Slope} \cdot d_1) + \left( \frac{\text{Slope} \cdot d_1}{2} \right) \right] \cdot W_f \cdot d_1$

$V_{Avail} := \Phi_c \cdot 2 \cdot \sqrt{f_c \cdot \psi} \cdot W_f \cdot d$  (ACI-2008 11.2.1.1)

Beam\_Shear\_Check := if( $V_{req} < V_{Avail}$ , "Okay", "No Good")

Beam\_Shear\_Check = "Okay"

### Punching Shear:

(Critical Section Located at a distance of d/2 from the face of pier) (ACI 11.11.1.2)

Critical Perimeter of Punching Shear =  $b_o := (d_p + d) \cdot \pi = 33.5$

Area Included Inside Perimeter =  $A_{bo} := \frac{\pi \cdot (d_p + d)^2}{4} = 89.4$

Area Outside of Perimeter =  $A_{out} := A_{mat} - A_{bo} = 780.9$

Guess Value =

$$v_u := 1 \text{ksf}$$

(From "Foundation Analysis and design", By Joseph Bowles, Eq. 8-9)

Given

$$d^2 + d_p \cdot d = \frac{W_{T_{tot}}}{\pi \cdot v_u}$$

$$v_u := \text{Find}(v_u) = 6.5 \cdot \text{ksf}$$

$$V_u := v_u \cdot d \cdot W_f = 513.7 \cdot \text{kips}$$

Required Shear Strength =

$$V_{req} := LF \cdot V_u = 684.8 \cdot \text{kips}$$

Available Shear Strength =

$$V_{Avail} := \phi_c \cdot 4 \cdot \sqrt{f_c \cdot \text{psi}} \cdot b_o \cdot d = 2767.1 \cdot \text{kip} \quad (\text{ACI-2008 11.11.2.1})$$

$$\text{Punching\_Shear\_Check} := \text{if}(V_{req} < V_{Avail}, \text{"Okay"}, \text{"No Good"})$$

$$\text{Punching\_Shear\_Check} = \text{"Okay"}$$

### Steel Reinforcement in Pad:

Required Reinforcement for Bending:

Strength Reduction Factor =

$$\phi_m := .90$$

(ACI-2008 9.3.2.1)

$$q_b := q_{adj} - d_1 \cdot \text{Slope} = 0.724 \cdot \text{ksf}$$

Maximum Bending at Face of Pier =

$$M_u := LF \cdot \left[ (q_{adj} - q_b) \cdot \frac{d_1^2}{3} + q_b \cdot \frac{d_1^2}{2} \right] \cdot W_f = 2571.1 \cdot \text{kip-ft}$$

$$\beta := \begin{cases} 0.85 & \text{if } 2500 \cdot \text{psi} \leq f_c \leq 4000 \cdot \text{psi} \\ 0.65 & \text{if } f_c > 8000 \cdot \text{psi} \end{cases} = 0.85$$

(ACI-2008 10.2.7.3)

$$\left[ \left[ \left[ \frac{f_c}{\text{psi}} - 4000 \right] \right] \right] \cdot 0.5 \quad \text{otherwise}$$

$$R_n := \frac{M_u}{\phi_m \cdot W_f \cdot d^2} = 94.6 \cdot \text{psi}$$

$$\rho := \frac{0.85 \cdot f_c}{f_y} \left( 1 - \sqrt{1 - \frac{2 \cdot R_n}{0.85 \cdot f_c}} \right) = 0.0016$$

$$\rho_{min} := \rho = 0.0016$$

Required Reinforcement for Temperature and Shrinkage:

$$\rho_{sh} := \begin{cases} .0018 & \text{if } f_y \geq 60000 \text{ psi} \\ .0020 & \text{otherwise} \end{cases} \quad (\text{ACI -2008 7.12.2.1})$$

Check Bottom Bars:

$$A_s := \begin{cases} \rho_{min} \cdot W_f \cdot d & \text{if } \rho_{min} > \frac{\rho_{sh}}{2} \\ \rho_{sh} \cdot W_f \cdot \frac{d}{2} & \text{otherwise} \end{cases} = 18.111 \cdot \text{in}^2$$

$$A_{s_{prov}} := A_{bbot} \cdot NB_{bot} = 34.6 \cdot \text{in}^2$$

$$\text{Pad\_Reinforcement\_Bot} := \text{if}(A_{s_{prov}} > A_s, \text{"Okay"}, \text{"No Good"})$$

Pad\_Reinforcement\_Bot = "Okay"

Check top Bars:

$$A_s := \rho_{sh} \cdot \left( W_f \cdot \frac{d}{2} \right) = 10.2 \cdot \text{in}^2$$

$$A_{s_{prov}} := A_{btop} \cdot NB_{top} = 22 \cdot \text{in}^2$$

$$\text{Pad\_Reinforcement\_Top} := \text{if}(A_{s_{prov}} > A_s, \text{"Okay"}, \text{"No Good"})$$

Pad\_Reinforcement\_Top = "Okay"

### Development Length Pad Reinforcement:

Bar Spacing =

$$B_{sPad} := \frac{W_f - 2 \cdot C_{vr_{pad}} - NB_{bot} \cdot d_{bbot}}{NB_{bot} - 1} = 7.07 \cdot \text{in}$$

Spacing or Cover Dimension =

$$c := \text{if} \left( C_{vr_{pad}} < \frac{B_{sPad}}{2}, C_{vr_{pad}}, \frac{B_{sPad}}{2} \right) = 3 \cdot \text{in}$$

Transverse Reinforcement Index =

$$k_{tr} := 0 \quad (\text{ACI-2008 12.2.3})$$

$$L_{dbt} := \frac{3 \cdot f_y \cdot \alpha_{pad} \cdot \beta_{pad} \cdot \gamma_{pad} \cdot \lambda_{pad}}{40 \cdot \sqrt{f_c \cdot \text{psi}} \cdot \frac{c + k_{tr}}{d_{bbot}}} \cdot d_{bbot} = 23.7 \cdot \text{in}$$

Minimum Development Length =

$$L_{dbmin} := 12 \cdot \text{in} \quad (\text{ACI-2008 12.2.1})$$

$$L_{dbtCheck} := \text{if}(L_{dbt} \geq L_{dbmin}, \text{"Use } L_{dbt}\text{"}, \text{"Use } L_{dbmin}\text{"})$$

Available Length in Pad =

$$L_{Pad} := \frac{W_f}{2} - \frac{d_p}{2} - C_{vr_{pad}} = 126 \cdot \text{in}$$

$$L_{pad\_Check} := \text{if}(L_{Pad} > L_{dbt}, \text{"Okay"}, \text{"No Good"})$$

Lpad\_Check = "Okay"



**Steel Reinforcement in Pier:**

Bar Spacing In Pier =  $B_{sPier} := \frac{d_p \cdot \pi}{NB_{pier}} - d_{bpier} = 5.854 \cdot \text{in}$

Diameter of Reinforcement Cage =  $Diam_{cage} := d_p - 2 \cdot C_{vr_{pier}} = 90 \cdot \text{in}$

Maximum Moment in Pier =  $M_p := \left[ OM + Shear \cdot \left( L_p + \frac{A_{BP}}{2} \right) \right] \cdot LF = 63040.2 \cdot \text{in} \cdot \text{kips}$

Pier Check evaluated from outside program and results are listed below;

$$(D \ N \ n \ P_u \ M_{xu}) := \left( d_p^{12} \ NB_{pier} \ BS_{pier} \frac{Axial \cdot 1.333}{\text{kips}} \frac{M_p}{\text{in} \cdot \text{kips}} \right)$$

$$(D \ N \ n \ P_u \ M_{xu}) = (96 \ 44 \ 8 \ 62.651 \ 6.304 \times 10^4)$$

$$(\phi P_n \ \phi M_{xn} \ f_{sp} \ \rho) := (0 \ 0 \ 0 \ 0)$$

$$(\phi P_n \ \phi M_{xn} \ f_{sp} \ \rho) := \phi P'_n (D, N, n, P_u, M_{xu})^T$$

$$(\phi P_n \ \phi M_{xn} \ f_{sp} \ \rho) = (78.781 \ 7.927 \times 10^4 \ -60 \ 4.802 \times 10^{-3})$$

$$Axial\_Load\_Check := \text{if}(\phi P_n \geq P_u, \text{"Okay"}, \text{"No Good"})$$

Axial\_Load\_Check = "Okay"

$$Bending\_Check := \text{if}(\phi M_{xn} \geq M_{xu}, \text{"Okay"}, \text{"No Good"})$$

Bending\_Check = "Okay"

**Development Length Pier Reinforcement:**

Available Length in Foundation:

$$L_{\text{pier}} := L_p - C_{\text{vr}}_{\text{pier}} = 27 \cdot \text{in}$$

$$L_{\text{pad}} := T_f - C_{\text{vr}}_{\text{pad}} = 33 \cdot \text{in}$$

Tension:

(ACI-2008 12.2.3)

Spacing or Cover Dimension =

$$c := \text{if} \left( C_{\text{vr}}_{\text{pier}} < \frac{B_{\text{sPier}}}{2}, C_{\text{vr}}_{\text{pier}}, \frac{B_{\text{sPier}}}{2} \right) = 2.927 \cdot \text{in}$$

Transverse Reinforcement =

$$k_{\text{tr}} := 0 \quad (\text{ACI-2008 12.2.3})$$

$$L_{\text{dbt}} := \frac{3 \cdot f_y \cdot \alpha_{\text{pier}} \cdot \beta_{\text{pier}} \cdot \gamma_{\text{pier}} \cdot \lambda_{\text{pier}}}{40 \cdot \sqrt{f_c} \cdot \text{psi} \cdot \left( \frac{c + k_{\text{tr}}}{d_{\text{bpier}}} \right)} \cdot d_{\text{bpier}} = 24.31 \cdot \text{in}$$

Minimum Development Length =

$$L_{\text{dh}} := \frac{1200 \cdot d_{\text{bpier}}}{\sqrt{\frac{f_c}{\text{psi}}}} \cdot .7 = 13.282 \cdot \text{in} \quad (\text{ACI 12.2.1})$$

Pier reinforcement bars are standard 90 degree hooks and therefore development in the pad is computed as follows:

$$L_{\text{db}} := \max(L_{\text{dbt}}, L_{\text{dbmin}})$$

$$L_{\text{tension\_Check}} := \text{if}(L_{\text{pier}} + L_{\text{pad}} > L_{\text{dbt}}, \text{"Okay"}, \text{"No Good"})$$

$$L_{\text{tension\_Check}} = \text{"Okay"}$$

Compression:

(ACI-2008 12.3.2)

$$L_{\text{dbc1}} := \frac{.02 \cdot d_{\text{bpier}} \cdot f_y}{\sqrt{f_c} \cdot \text{psi}} = 18.974 \cdot \text{in}$$

$$L_{\text{dbmin}} := 0.0003 \cdot \frac{\text{in}^2}{l_b} \cdot (d_{\text{bpier}} \cdot f_y) = 18 \cdot \text{in}$$

$$L_{\text{dbc}} := \text{if}(L_{\text{dbc1}} \geq L_{\text{dbmin}}, L_{\text{dbc1}}, L_{\text{dbmin}}) = 18.974 \cdot \text{in}$$

$$L_{\text{compression\_Check}} := \text{if}(L_{\text{pier}} + L_{\text{pad}} > L_{\text{dbc}}, \text{"Okay"}, \text{"No Good"})$$

$$L_{\text{compression\_Check}} = \text{"Okay"}$$

**Tie Size and Spacing in Column:**

Minimum Tie Size =  $Tie_{min} := \text{if}(BS_{pier} \leq 10, 3, 4) = 3$

Used #4 Ties

Seismic Factor =  $z := \text{if}(Z \leq 2, 1, 0.5) = 1$  (ACI-2008 21.10.5)

$s_{lim1} := 16 \cdot d_{bpier} \cdot z = 16 \cdot \text{in}$

$s_{lim2} := 48 \cdot d_{Tie} \cdot z = 144 \cdot \text{in}$

$s_{lim3} := D_r \cdot z = 66 \cdot \text{in}$

$s_{lim4} := 18 \cdot \text{in}$

Maximum Spacing =  $s_{tie} := \min \left( \begin{matrix} s_{lim1} \\ s_{lim2} \\ s_{lim3} \\ s_{lim4} \end{matrix} \right) = 16 \cdot \text{in}$

Number of Ties Required =  $n_{tie} := \frac{L_{pier} - 3 \cdot \text{in}}{s_{tie}} + 1 = 2.5$

**Check Anchor Steel Embedment:**

Depth Available =  $D_{ab} := L_{st} - A_{BP} = 5 \cdot \text{ft}$

Length of Anchor Bolt =  $L_{anchor} := \frac{(0.11 \cdot f_{ya}) \cdot \text{in}}{\sqrt{f_c \cdot \text{psi}}} = 10.87 \cdot \text{ft}$

Depth\_Check :=  $\text{if}(D_{ab} \geq L_{anchor}, \text{"Okay"}, \text{"No Good"})$

Depth\_Check = "No Good"

**Note:** Anchor plate is provided



PROJECT: 2.5 EQUIPMENT DEPLOYMENT  
 SITE NAME: WESTPORT / BAM  
 SITE CASCADE: CT03XC382  
 SITE ADDRESS: 2 SUNNY LANE  
 WESTPORT, CT 06880  
 SITE TYPE: MONOPOLE TOWER  
 MARKET: SOUTHERN CONNECTICUT

PLANS PREPARED FOR:

6580 Sprint Parkway  
Overland Park, Kansas 66251

PLANS PREPARED BY:

1033 Watervliet Shaker Rd  
Albany, NY 12205  
Office # (518) 690-0790  
Fax # (518) 690-0793  
JOB NUMBER 333-000

ENGINEERING LICENSE:

**SITE INFORMATION**

**TOWER OWNER:**  
 VERIZON WIRELESS  
 20 ALEXANDER DR  
 WALLINGFORD, CT 06492

**LATITUDE (NAD83):**  
 41° 9' 46.0794" N  
 41.1628°

**LONGITUDE (NAD83):**  
 73° 22' 23.88" W  
 -73.3733°

**COUNTY:**  
 FAIRFIELD

**ZONING JURISDICTION:**  
 TOWN OF WESTPORT

**ZONING DISTRICT:**  
 TBD

**POWER COMPANY:**  
 CONNECTICUT LIGHT & POWER  
 (800) 286-2000


**AAV PROVIDER:**  
 AT&T  
 (800) 246-2020

**SPRINT CM:**  
 GARY WOOD  
 PHONE: (860) 940-9168  
 gary.wood@sprint.com

**AREA MAP**



**LOCATION MAP**



**PROJECT DESCRIPTION**

SPRINT PROPOSES TO MODIFY AN EXISTING UNMANNED TELECOMMUNICATIONS FACILITY.

- INSTALL (1) 9929 EQUIPMENT CABINET
- INSTALL (4) BATTERIES IN EXISTING SPRINT BBU CABINET
- INSTALL (3) PANEL ANTENNAS
- INSTALL (3) RRU'S TO TOWER
- INSTALL (27) JUMPER CABLES
- INSTALL (1) FIBER CABLE

THESE PLANS HAVE BEEN DEVELOPED FOR THE MODIFICATION OF AN EXISTING UNMANNED TELECOMMUNICATIONS FACILITY OWNED OR LEASED BY SPRINT IN ACCORDANCE WITH THE SCOPE OF WORK PROVIDED BY SPRINT. INFINIGY HAS INCORPORATED THIS SCOPE OF WORK IN THE PLANS. THESE PLANS ARE NOT FOR CONSTRUCTION UNLESS ACCOMPANIED BY A PASSING STRUCTURAL STABILITY ANALYSIS PREPARED BY A LICENSED STRUCTURAL ENGINEER. STRUCTURAL ANALYSIS MUST INCLUDE BOTH TOWER AND MOUNT.

**APPLICABLE CODES**

ALL WORK SHALL BE PERFORMED AND MATERIALS INSTALL IN ACCORDANCE WITH THE CURRENT EDITIONS OF THE FOLLOWING CODES AS ADOPTED BY THE LOCAL GOVERNING AUTHORITIES. NOTHING IN THESE PLANS IS TO BE CONSTRUED TO PERMIT WORK NOT CONFORMING TO THESE CODES.

1. INTERNATIONAL BUILDING CODE (2012 IBC)
2. TIA-EIA-222-G OR LATEST EDITION
3. NFPA 780 - LIGHTNING PROTECTION CODE
4. 2011 NATIONAL ELECTRIC CODE OR LATEST EDITION
5. ANY OTHER NATIONAL OR LOCAL APPLICABLE CODES, MOST RECENT EDITIONS
6. CT BUILDING CODE
7. LOCAL BUILDING CODE
8. CITY/COUNTY ORDINANCES



**DRAWING INDEX**

SHEET NO.	SHEET TITLE	REV.
T-1	TITLE SHEET & PROJECT DATA	A
SP-1	SPRINT SPECIFICATIONS	A
SP-2	SPRINT SPECIFICATIONS	A
SP-3	SPRINT SPECIFICATIONS	A
A-1	SITE PLAN	A
A-2	TOWER ELEVATION & CABLE PLAN	A
A-3	ANTENNA LAYOUT & MOUNTING DETAILS	A
A-4	COLOR CODING & NOTES	A
A-5	EQUIPMENT & MOUNTING DETAILS	A
A-6	CIVIL DETAILS	A
A-7	PLUMBING DIAGRAM	A
E-1	ELECTRICAL & GROUNDING PLAN	A
E-2	ELECTRICAL & GROUNDING DETAILS	A

ENGINEERING LICENSE:

DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR REVIEW	05/15/14	JDV	A

SITE NAME:

WESTPORT / BAM

SITE CASCADE:

CT03XC382

SITE ADDRESS:

2 SUNNY LANE  
WESTPORT, CT 06880

SHEET DESCRIPTION:

TITLE SHEET & PROJECT DATA

SHEET NUMBER:

T-1

THESE OUTLINE SPECIFICATIONS IN CONJUNCTION WITH THE SPRINT STANDARD CONSTRUCTION SPECIFICATIONS, INCLUDING CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

**SECTION 01 100 – SCOPE OF WORK**

**PART 1 – GENERAL**

- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE SPRINT CONSTRUCTION STANDARDS FOR WIRELESS SITES, CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
  - A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
  - B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.
- 1.3 PRECEDENCE: SHOULD CONFLICTS OCCUR BETWEEN THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES INCLUDING THE STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES AND THE CONSTRUCTION DRAWINGS, INFORMATION ON THE CONSTRUCTION DRAWINGS SHALL TAKE PRECEDENCE. NOTIFY SPRINT CONSTRUCTION MANAGER IF THIS OCCURS.
- 1.4 NATIONALLY RECOGNIZED CODES AND STANDARDS:
  - A. THE WORK SHALL COMPLY WITH APPLICABLE NATIONAL AND LOCAL CODES AND STANDARDS, LATEST EDITION, AND PORTIONS THEREOF, INCLUDED BUT NOT LIMITED TO THE FOLLOWING:
    - 1. GR-63-CORE NEBS REQUIREMENTS: PHYSICAL PROTECTION
    - 5. GR-78-CORE GENERIC REQUIREMENTS FOR THE PHYSICAL DESIGN AND MANUFACTURE OF TELECOMMUNICATIONS EQUIPMENT.
    - 3. GR-1089 CORE, ELECTROMAGNETIC COMPATIBILITY AND ELECTRICAL SAFETY –GENERIC CRITERIA FOR NETWORK TELECOMMUNICATIONS EQUIPMENT.
    - 4. NATIONAL FIRE PROTECTION ASSOCIATION CODES AND STANDARDS (NFPA) INCLUDING NFPA 70 (NATIONAL ELECTRICAL CODE – 'NEC') AND NFPA 101 (LIFE SAFETY CODE).
    - 5. AMERICAN SOCIETY FOR TESTING OF MATERIALS (ASTM)
    - 6. INSTITUTE OF ELECTRONIC AND ELECTRICAL ENGINEERS (IEEE)
    - 7. AMERICAN CONCRETE INSTITUTE (ACI)
    - 8. AMERICAN WIRE PRODUCERS ASSOCIATION (AWPA)
    - 9. CONCRETE REINFORCING STEEL INSTITUTE (CRSI)
    - 10. AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (ASHTO)
    - 11. PORTLAND CEMENT ASSOCIATION (PCA)
    - 12. NATIONAL CONCRETE MASONRY ASSOCIATION (NCMA)
    - 13. BRICK INDUSTRY ASSOCIATION (BIA)
    - 14. AMERICAN WELDING SOCIETY (AWS)
    - 15. NATIONAL ROOFING CONTRACTORS ASSOCIATION (NRCA)
    - 16. SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)
    - 17. DOOR AND HARDWARE INSTITUTE (DHI)
    - 18. OCCUPATIONAL SAFETY AND HEALTH ACT (OSHA)
    - 19. APPLICABLE BUILDING CODES INCLUDING UNIFORM BUILDING CODE, SOUTHERN BUILDING CODE, BOCA, AND THE INTERNATIONAL BUILDING CODE.
- 1.5 DEFINITIONS:
  - A. WORK: THE SUM OF TASKS AND RESPONSIBILITIES IDENTIFIED IN THE CONTRACT DOCUMENTS.
  - B. COMPANY: SPRINT CORPORATION
  - C. ENGINEER: SYNONYMOUS WITH ARCHITECT & ENGINEER AND "A&E". THE DESIGN PROFESSIONAL HAVING PROFESSIONAL RESPONSIBILITY FOR DESIGN OF THE PROJECT.
  - D. CONTRACTOR: CONSTRUCTION CONTRACTOR; CONSTRUCTION VENDOR; INDIVIDUAL OR ENTITY WHO AFTER EXECUTION OF A CONTRACT IS BOUND TO ACCOMPLISH THE WORK.
  - E. THIRD PARTY VENDOR OR AGENCY: A VENDOR OR AGENCY ENGAGED SEPARATELY BY THE COMPANY, A&E, OR CONTRACTOR TO PROVIDE MATERIALS OR TO ACCOMPLISH SPECIFIC TASKS RELATED TO BUT NOT INCLUDED IN THE WORK.
  - F. OFCI: OWNER FURNISHED, CONTRACTOR INSTALLED EQUIPMENT.
  - G. CONSTRUCTION MANAGER – ALL PROJECTS RELATED COMMUNICATION TO FLOW THROUGH SPRINT REPRESENTATIVE IN CHARGE OF PROJECT...

- 1.6 SITE FAMILIARITY: CONTRACTOR SHALL BE RESPONSIBLE FOR FAMILIARIZING HIMSELF WITH ALL CONTRACT DOCUMENTS, FIELD CONDITIONS AND DIMENSIONS PRIOR TO PROCEEDING WITH CONSTRUCTION. ANY DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE SPRINT CONSTRUCTION MANAGER PRIOR TO THE COMMENCEMENT OF WORK. NO COMPENSATION WILL BE AWARDED BASED ON CLAIM OF LACK OF KNOWLEDGE OR FIELD CONDITIONS.
- 1.7 POINT OF CONTACT: COMMUNICATION BETWEEN SPRINT AND THE CONTRACTOR SHALL FLOW THROUGH THE SINGLE SPRINT CONSTRUCTION MANAGER APPOINTED TO MANAGE THE PROJECT FOR SPRINT.
- 1.8 ON-SITE SUPERVISION: THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK AND SHALL BE RESPONSIBLE FOR CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES IN ACCORDANCE WITH THE CONTRACT DOCUMENTS. THE CONTRACTOR SHALL EMPLOY A COMPETENT SUPERINTENDENT WHO SHALL BE IN ATTENDANCE AT THE SITE AT ALL TIMES DURING PERFORMANCE OF THE WORK.
- 1.9 DRAWINGS, SPECIFICATIONS AND DETAILS REQUIRED AT JOBSITE: THE CONSTRUCTION CONTRACTOR SHALL MAINTAIN A FULL SET OF THE CONSTRUCTION DRAWINGS, STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES AND THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES AT THE JOBSITE FROM MOBILIZATION THROUGH CONSTRUCTION COMPLETION.
  - A. THE JOBSITE DRAWINGS, SPECIFICATIONS AND DETAILS SHALL BE CLEARLY MARKED DAILY IN RED PENCIL WITH ANY CHANGES IN CONSTRUCTION OVER WHAT IS DEPICTED IN THE DOCUMENTS. AT CONSTRUCTION COMPLETION, THIS JOBSITE MARKUP SET SHALL BE DELIVERED TO THE COMPANY OR COMPANY'S DESIGNATED REPRESENTATIVE TO BE FORWARDED TO THE COMPANY'S A&E VENDOR FOR PRODUCTION OF "AS-BUILT" DRAWINGS.
  - B. DETAILS ARE INTENDED TO SHOW DESIGN INTENT. MODIFICATIONS MAY BE REQUIRED TO SUIT JOB DIMENSIONS OR CONDITIONS, AND SUCH MODIFICATIONS SHALL BE INCLUDED AS PART OF THE WORK. CONTRACTOR SHALL NOTIFY SPRINT CONSTRUCTION MANAGER OF ANY VARIATIONS PRIOR TO PROCEEDING WITH THE WORK.
  - C. DIMENSIONS SHOWN ARE TO FINISH SURFACES UNLESS NOTED OTHERWISE. SPACING BETWEEN EQUIPMENT IS THE REQUIRED CLEARANCE. SHOULD THERE BE ANY QUESTIONS REGARDING THE CONTRACT DOCUMENTS, EXISTING CONDITIONS AND/OR DESIGN INTENT, THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING A CLARIFICATION FROM THE SPRINT CONSTRUCTION MANAGER PRIOR TO PROCEEDING WITH THE WORK.
- 1.10 USE OF JOB SITE: THE CONTRACTOR SHALL CONFINE ALL CONSTRUCTION AND RELATED OPERATIONS INCLUDING STAGING AND STORAGE OF MATERIALS AND EQUIPMENT, PARKING, TEMPORARY FACILITIES, AND WASTE STORAGE TO THE LEASE PARCEL UNLESS OTHERWISE PERMITTED BY THE CONTRACT DOCUMENTS.
- 1.11 UTILITIES SERVICES: WHERE NECESSARY TO CUT EXISTING PIPES, ELECTRICAL WIRES, CONDUITS, CABLES, ETC., OF UTILITY SERVICES, OR OF FIRE PROTECTION OR COMMUNICATIONS SYSTEMS, THEY SHALL BE CUT AND CAPPED AT SUITABLE PLACES OR WHERE SHOWN. ALL SUCH ACTIONS SHALL BE COORDINATED WITH THE UTILITY COMPANY INVOLVED:
- 1.12 PERMITS / FEES: WHEN REQUIRED THAT A PERMIT OR CONNECTION FEE BE PAID TO A PUBLIC UTILITY PROVIDER FOR NEW SERVICE TO THE CONSTRUCTION PROJECT, PAYMENT OF SUCH FEE SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.
- 1.13 CONTRACTOR SHALL TAKE ALL MEASURES AND PROVIDE ALL MATERIAL NECESSARY FOR PROTECTING EXISTING EQUIPMENT AND PROPERTY.
- 1.14 METHODS OF PROCEDURE (MOPS) FOR CONSTRUCTION: CONTRACTOR SHALL PERFORM WORK AS DESCRIBED IN THE FOLLOWING INSTALLATION AND COMMISSIONING MOPS.
 

NOTE: IN SHORT-FORM SPECIFICATIONS ON THE DRAWINGS, A/E TO INSERT LIST OF APPLICABLE MOPS INCLUDING EN-2012-001, EN-2013-002, EL-0568, AND TS-0193
- 1.15 USE OF ELECTRONIC PROJECT MANAGEMENT SYSTEMS:

**PART 2 – PRODUCTS (NOT USED)**

**PART 3 – EXECUTION**

- 3.1 TEMPORARY UTILITIES AND FACILITIES: THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL TEMPORARY UTILITIES AND FACILITIES NECESSARY EXCEPT AS OTHERWISE INDICATED IN THE CONSTRUCTION DOCUMENTS. TEMPORARY UTILITIES AND FACILITIES INCLUDE POTABLE WATER, HEAT, HVAC, ELECTRICITY, SANITARY FACILITIES, WASTE DISPOSAL FACILITIES, AND TELEPHONE/COMMUNICATION SERVICES. PROVIDE TEMPORARY UTILITIES AND FACILITIES IN ACCORDANCE WITH OSHA AND THE AUTHORITY HAVING JURISDICTION. CONTRACTOR MAY UTILIZE THE COMPANY ELECTRICAL SERVICE IN THE COMPLETION OF THE WORK WHEN IT BECOMES AVAILABLE. USE OF THE LESSORS OR SITE OWNER'S UTILITIES OR FACILITIES IS EXPRESSLY FORBIDDEN EXCEPT AS OTHERWISE ALLOWED IN THE CONTRACT DOCUMENTS.
- 3.2 ACCESS TO WORK: THE CONTRACTOR SHALL PROVIDE ACCESS TO THE JOB SITE FOR AUTHORIZED COMPANY PERSONNEL AND AUTHORIZED REPRESENTATIVES OF THE ARCHITECT/ENGINEER DURING ALL PHASES OF THE WORK.
- 3.3 TESTING: REQUIREMENTS FOR TESTING BY THIS CONTRACTOR SHALL BE AS INDICATED HEREWITH. ON THE CONSTRUCTION DRAWINGS, AND IN THE INDIVIDUAL SECTIONS OF THESE SPECIFICATIONS. SHOULD COMPANY CHOOSE TO ENGAGE ANY THIRD-PARTY TO CONDUCT ADDITIONAL TESTING, THE CONTRACTOR SHALL COOPERATE WITH AND PROVIDE A WORK AREA FOR COMPANY'S TEST AGENCY.
- 3.4 DIMENSIONS: VERIFY DIMENSIONS INDICATED ON DRAWINGS WITH FIELD DIMENSIONS BEFORE FABRICATION OR ORDERING OF MATERIALS. DO NOT SCALE DRAWINGS.

3.5 EXISTING CONDITIONS: NOTIFY THE SPRINT CONSTRUCTION MANAGER OF EXISTING CONDITIONS DIFFERING FROM THOSE INDICATED ON THE DRAWINGS. DO NOT REMOVE OR ALTER STRUCTURAL COMPONENTS WITHOUT PRIOR WRITTEN APPROVAL FROM THE ARCHITECT AND ENGINEER.

**SECTION 01 200 – COMPANY FURNISHED MATERIAL AND EQUIPMENT**

**PART 1 – GENERAL**

- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
  - A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
  - B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.

**PART 2 – PRODUCTS (NOT USED)**

**PART 3 – EXECUTION**

- 3.1 RECEIPT OF MATERIAL AND EQUIPMENT:
  - A. A COMPANY FURNISHED MATERIAL AND EQUIPMENT IS IDENTIFIED ON THE RF DATA SHEET IN THE CONSTRUCTION DOCUMENTS.
  - B. THE CONTRACTOR IS RESPONSIBLE FOR SPRINT PROVIDED MATERIAL AND EQUIPMENT AND UPON RECEIPT SHALL:
    - 1. ACCEPT DELIVERIES AS SHIPPED AND TAKE RECEIPT.
    - 2. VERIFY COMPLETENESS AND CONDITION OF ALL DELIVERIES.
    - 3. TAKE RESPONSIBILITY FOR EQUIPMENT AND PROVIDE INSURANCE PROTECTION AS REQUIRED IN AGREEMENT.
    - 4. RECORD ANY DEFECTS OR DAMAGES AND WITHIN TWENTY-FOUR HOURS AFTER RECEIPT, REPORT TO SPRINT OR ITS DESIGNATED PROJECT REPRESENTATIVE OF SUCH.
    - 5. PROVIDE SECURE AND NECESSARY WEATHER PROTECTED WAREHOUSING.
    - 6. COORDINATE SAFE AND SECURE TRANSPORTATION OF MATERIAL AND EQUIPMENT, DELIVERING AND OFF-LOADING FROM CONTRACTOR'S WAREHOUSE TO SITE.
- 3.2 DELIVERABLES:
  - A. COMPLETE SHIPPING AND RECEIPT DOCUMENTATION IN ACCORDANCE WITH COMPANY PRACTICE.
  - B. IF APPLICABLE, COMPLETE LOST/STOLEN/DAMAGED DOCUMENTATION REPORT AS NECESSARY IN ACCORDANCE WITH COMPANY PRACTICE, AND AS DIRECTED BY COMPANY.
  - C. UPLOAD DOCUMENTATION INTO SPRINT SITE MANAGEMENT SYSTEM (SMS) AND/OR PROVIDE HARD COPY DOCUMENTATION AS REQUESTED.

**SECTION 01 300 – CELL SITE CONSTRUCTION CO.**

**PART 1 – GENERAL**

- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
  - A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
  - B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.
- 1.3 NOTICE TO PROCEED
  - A. NO WORK SHALL COMMENCE PRIOR TO COMPANY'S WRITTEN NOTICE TO PROCEED AND THE ISSUANCE OF THE WORK ORDER.
  - B. UPON RECEIVING NOTICE TO PROCEED, CONTRACTOR SHALL FULLY PERFORM ALL WORK NECESSARY TO PROVIDE SPRINT WITH AN OPERATIONAL WIRELESS FACILITY.

**PART 2 – PRODUCTS (NOT USED)**

**PART 3 – EXECUTION**

- 3.1 FUNCTIONAL REQUIREMENTS:
  - A. THE ACTIVITIES DESCRIBED IN THIS PARAGRAPH REPRESENT MINIMUM ACTIONS AND PROCESSES REQUIRED TO SUCCESSFULLY COMPLETE THE WORK. THE ACTIVITIES DESCRIBED ARE NOT EXHAUSTIVE, AND CONTRACTOR SHALL TAKE ANY AND ALL ACTIONS AS NECESSARY TO SUCCESSFULLY COMPLETE THE CONSTRUCTION OF A FULLY FUNCTIONING WIRELESS FACILITY AT THE SITE IN ACCORDANCE WITH COMPANY PROCESSES.
  - B. SUBMIT SPECIFIC DOCUMENTATION AS INDICATED HEREIN, AND OBTAIN REQUIRED APPROVALS WHILE THE WORK IS BEING PERFORMED.
  - C. MANAGE AND CONDUCT ALL FIELD CONSTRUCTION SERVICE RELATED ACTIVITIES
  - D. PROVIDE CONSTRUCTION ACTIVITIES TO THE EXTENT REQUIRED BY THE CONTRACT DOCUMENTS, INCLUDING BUT NOT LIMITED TO THE FOLLOWING:

PLANS PREPARED FOR:



6580 Sprint Parkway  
Overland Park, Kansas 66251

PLANS PREPARED BY:



1033 Watervliet Shaker Rd  
Albany, NY 12205  
Office # (518) 690-0790  
Fax # (518) 690-0793  
JOB NUMBER 333-000

ENGINEERING LICENSE:

DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR REVIEW	05/15/14	JDV	A

SITE NAME:

**WESTPORT / BAM**

SITE CASCADE:

**CT03XC382**

SITE ADDRESS:

**2 SUNNY LANE  
WESTPORT, CT 06880**

SHEET DESCRIPTION:

**SPRINT SPECIFICATIONS**

SHEET NUMBER:

**SP-1**

CONTINUE FROM SP-1

1. PERFORM ANY REQUIRED SITE ENVIRONMENTAL MITIGATION.
2. PREPARE GROUND SITES; PROVIDE DE-GRUBBING; AND ROUGH AND FINAL GRADING, AND COMPOUND SURFACE TREATMENTS.
3. MANAGE AND CONDUCT ALL ACTIVITIES FOR INSTALLATION OF UTILITIES INCLUDING ELECTRICAL AND TELCO BACKHAUL.
4. INSTALL UNDERGROUND FACILITIES INCLUDING UNDERGROUND POWER AND COMMUNICATIONS CONDUITS, AND UNDERGROUND GROUNDING SYSTEM.
5. INSTALL ABOVE GROUND GROUNDING SYSTEMS.
6. PROVIDE NEW HVAC INSTALLATIONS AND MODIFICATIONS.
7. INSTALL "H-FRAMES", CABINETS AND SHELTERS AS INDICATED.
8. INSTALL ROADS, ACCESS WAYS, CURBS AND DRAINS AS INDICATED.
9. ACCOMPLISH REQUIRED MODIFICATION OF EXISTING FACILITIES.
10. PROVIDE ANTENNA SUPPORT STRUCTURE FOUNDATIONS.
11. PROVIDE SLABS AND EQUIPMENT PLATFORMS.
12. INSTALL COMPOUND FENCING, SIGHT SHIELDING, LANDSCAPING AND ACCESS BARRIERS.
13. PERFORM INSPECTION AND MATERIAL TESTING AS REQUIRED HEREINAFTER.
14. CONDUCT SITE RESISTANCE TO EARTH TESTING AS REQUIRED HEREINAFTER
15. INSTALL FIXED GENERATOR SETS AND OTHER STANDBY POWER SOLUTIONS.
16. INSTALL TOWERS, ANTENNA SUPPORT STRUCTURES AND PLATFORMS ON EXISTING TOWERS AS REQUIRED.
17. INSTALL CELL SITE RADIOS, MICROWAVE, GPS, COAXIAL MAINLINE, ANTENNAS, CROSS BAND COUPLERS, TOWER TOP AMPLIFIERS, LOW NOISE AMPLIFIERS AND RELATED EQUIPMENT.
18. PERFORM, DOCUMENT, AND CLOSE OUT ANY CONSTRUCTION CONTROL DOCUMENTS THAT MAY BE REQUIRED BY GOVERNMENT AGENCIES AND LANDLORDS.
19. PERFORM ANTENNAL AND COAX SWEEP TESTING AND MAKE ANY AND ALL NECESSARY CORRECTIONS.
20. REMAIN ON SITE MOBILIZED THROUGHOUT HAND-OFF AND INTEGRATION TO ASSIST AS NEEDED UNTIL SITE IS DEEMED SUBSTANTIALLY COMPLETE AND PLACED "ON AIR."

3.2 GENERAL REQUIREMENTS FOR CIVIL CONSTRUCTION:

- A. CONTRACTOR SHALL KEEP THE SITE FREE FROM ACCUMULATING WASTE MATERIAL, DEBRIS, AND TRASH. AT THE COMPLETION OF THE WORK, CONTRACTOR SHALL REMOVE FROM THE SITE ALL REMAINING RUBBISH, IMPLEMENTS, TEMPORARY FACILITIES, AND SURPLUS MATERIALS.
- B. EQUIPMENT ROOMS SHALL AT ALL TIMES BE MAINTAINED "BROOM CLEAN" AND CLEAR OF DEBRIS.
- C. CONTRACTOR SHALL TAKE ALL REASONABLE PRECAUTIONS TO DISCOVER AND LOCATE ANY HAZARDOUS CONDITION.
  1. IN THE EVENT CONTRACTOR ENCOUNTERS ANY HAZARDOUS CONDITION WHICH HAS NOT BEEN ABATED OR OTHERWISE MITIGATED, CONTRACTOR AND ALL OTHER PERSONS SHALL IMMEDIATELY STOP WORK IN THE AFFECTED AREA AND NOTIFY COMPANY IN WRITING. THE WORK IN THE AFFECTED AREA SHALL NOT BE RESUMED EXCEPT BY WRITTEN NOTIFICATION BY COMPANY.
  2. CONTRACTOR AGREES TO USE CARE WHILE ON THE SITE AND SHALL NOT TAKE ANY ACTION THAT WILL OR MAY RESULT IN OR CAUSE THE HAZARDOUS CONDITION TO BE FURTHER RELEASED IN THE ENVIRONMENT, OR TO FURTHER EXPOSE INDIVIDUALS TO THE HAZARD.
- D. CONTRACTOR'S ACTIVITIES SHALL BE RESTRICTED TO THE PROJECT LIMITS. SHOULD AREAS OUTSIDE THE PROJECT LIMITS BE AFFECTED BY CONTRACTOR'S ACTIVITIES, CONTRACTOR SHALL IMMEDIATELY RETURN THEM TO ORIGINAL CONDITION
- E. CONDUCT TESTING AS REQUIRED HEREIN.

3.3 DELIVERABLES:

- A. CONTRACTOR SHALL REVIEW, APPROVE, AND SUBMIT TO SPRINT SHOP DRAWINGS, PRODUCT DATA, SAMPLES, AND SIMILAR SUBMITTALS AS REQUIRED HEREINAFTER
- B. PROVIDE DOCUMENTATION INCLUDING, BUT NOT LIMITED TO, THE FOLLOWING. DOCUMENTATION SHALL BE FORWARDED IN ORIGINAL FORMAT AND/OR UPLOADED INTO SMS.
  1. ALL CORRESPONDENCE AND PRELIMINARY CONSTRUCTION REPORTS.
  2. PROJECT PROGRESS REPORTS.
  3. CIVIL CONSTRUCTION START DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
  4. ELECTRICAL SERVICE COMPLETION DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).

5. LINES AND ANTENNA INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
6. POWER INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
7. TELCO READY DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
8. PPC (OR SHELTER) INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
9. TOWER CONSTRUCTION START DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
10. TOWER CONSTRUCTION COMPLETE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
11. BTS AND RADIO EQUIPMENT DELIVERED AT SITE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
12. NETWORK OPERATIONS HANDOFF CHECKLIST (HOC WALK) COMPLETE (UPLOAD FORM IN SMS)
13. CIVIL CONSTRUCTION COMPLETE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
14. SITE CONSTRUCTION PROGRESS PHOTOS UNLOADED INTO SMS.

SECTION 01 400 - SUBMITTALS & TESTS

PART 1 - GENERAL

1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

1.2 RELATED DOCUMENTS:

- A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
- B. SPRINT STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HERewith.

1.3 SUBMITTALS:

- A. THE WORK IN ALL ASPECTS SHALL COMPLY WITH THE CONSTRUCTION DRAWINGS AND THESE SPECIFICATIONS.
- B. SUBMIT THE FOLLOWING TO COMPANY REPRESENTATIVE FOR APPROVAL.
  1. CONCRETE MIX-DESIGNS FOR TOWER FOUNDATIONS, ANCHORS PIERS, AND CONCRETE PAVING.
  2. CONCRETE BREAK TESTS AS SPECIFIED HEREIN.
  3. SPECIAL FINISHES FOR INTERIOR SPACES, IF ANY.
  4. ALL EQUIPMENT AND MATERIALS SO IDENTIFIED ON THE CONSTRUCTION DRAWINGS.
  5. CHEMICAL GROUNDING DESIGN
- D. ALTERNATES: AT THE COMPANY'S REQUEST, ANY ALTERNATIVES TO THE MATERIALS OR METHODS SPECIFIED SHALL BE SUBMITTED TO SPRINT'S CONSTRUCTION MANAGER FOR APPROVAL PRIOR TO BEING SHIPPED TO SITE. SPRINT WILL REVIEW AND APPROVE ONLY THOSE REQUESTS MADE IN WRITING. NO VERBAL APPROVALS WILL BE CONSIDERED. SUBMITTAL FOR APPROVAL SHALL INCLUDE A STATEMENT OF COST REDUCTION PROPOSED FOR USE OF ALTERNATE PRODUCT.

1.4 TESTS AND INSPECTIONS:

- A. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CONSTRUCTION TESTS, INSPECTIONS AND PROJECT DOCUMENTATION.
- B. CONTRACTOR SHALL ACCOMPLISH TESTING INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
  1. COAX SWEEPS AND FIBER TESTS PER TS-0200 REV 4 ANTENNA LINE ACCEPTANCE STANDARDS.
  2. AGL, AZIMUTH AND DOWNTILT USING ELECTRONIC COMMERCIAL MADE-FOR-THE-PURPOSE ANTENNA ALIGNMENT TOOL.
  3. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN SITE INSPECTION ACTIVITIES AND/OR AS A RESULT OF TESTING.
- C. REQUIRED CLOSEOUT DOCUMENTATION INCLUDES, BUT IS NOT LIMITED TO THE FOLLOWING:
  1. AZIMUTH, DOWNTILT, AGL - UPLOAD REPORT FROM ANTENNA ALIGNMENT TOOL TO SITERRA TASK 465. INSTALLED AZIMUTH, DOWNTILT, AND AGL MUST CONFORM TO THE RF DATA SHEETS. SWEEP AND FIBER TESTS
  2. SCANABLE BARCODE PHOTOGRAPHS OF TOWER TOP AND INACCESSIBLE EQUIPMENT
  3. ALL AVAILABLE JURISDICTIONAL INFORMATION
  4. PDF SCAN OF REDLINES PRODUCED IN FIELD

5. ELECTRONIC AS-BUILT DRAWINGS IN AUTOCAD AND PDF FORMATS. ANY FIELD CHANGE MUST BE REFLECTED BY MODIFYING THE PLANS, ELEVATIONS, AND DETAILS IN THE DRAWING SETS. GENERAL NOTES INDICATING MODIFICATIONS WILL NOT BE ACCEPTED. CHANGES SHALL BE HIGHLIGHTED AS "CLOUDS" IDENTIFIED AS THE "AS-BUILT" CONDITION.
6. LIEN WAIVERS
7. FINAL PAYMENT APPLICATION
8. REQUIRED FINAL CONSTRUCTION PHOTOS
9. CONSTRUCTION AND COMMISSIONING CHECKLIST COMPLETE WITH NO DEFICIENT ITEMS
10. ALL POST NTP TASKS INCLUDING DOCUMENT UPLOADS COMPLETED IN SITERRA (SPRINTS DOCUMENT REPOSITORY OF RECORD).

1.5 COMMISSIONING: PERFORM ALL COMMISSIONING AS REQUIRED BY APPLICABLE MOPs

1.6 INTEGRATION: PERFORM ALL INTEGRATION ACTIVITIES AS REQUIRED BY APPLICABLE MOPs

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION

3.1 REQUIREMENTS FOR TESTING:

A. THIRD PARTY TESTING AGENCY:

1. WHEN THE USE OF A THIRD PARTY INDEPENDENT TESTING AGENCY IS REQUIRED, THE AGENCY THAT IS SELECTED MUST PERFORM SUCH WORK ON A REGULAR BASIS IN THE STATE WHERE THE PROJECT IS LOCATED AND HAVE A THOROUGH UNDERSTANDING OF LOCAL AVAILABLE MATERIALS, INCLUDING THE SOIL, ROCK, AND GROUNDWATER CONDITIONS.
2. THE THIRD PARTY TESTING AGENCY IS TO BE FAMILIAR WITH THE APPLICABLE REQUIREMENTS FOR THE TESTS TO BE DONE, EQUIPMENT TO BE USED, AND ASSOCIATED HEALTH AND SAFETY ISSUES.
3. EXPERIENCE IN SOILS, CONCRETE, MASONRY, AGGREGATE, AND ASPHALT TESTING USING ASTM, AASJTO, AND OTHER METHODS IS NEEDED.
4. EXPERIENCE IN SOILS, CONCRETE, MASONRY, AGGREGATE, AND ASPHALT TESTING USING ASTM, AASJTO, AND OTHER METHODS IS NEEDED.

3.2 REQUIRED TESTS:

- A. CONTRACTOR SHALL ACCOMPLISH TESTING INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
  1. CONCRETE CYLINDER BREAK TESTS FOR THE TOWER AND ANCHOR FOUNDATIONS AS SPECIFIED IN SECTION: PORTLAND CEMENT CONCRETE PAVING.
  2. ASPHALT ROADWAY COMPACTED THICKNESS, SURFACE SMOOTHNESS, AND COMPACTED DENSITY TESTING AS SPECIFIED IN SECTION: HOT MIX ASPHALT PAVING.
  3. FIELD QUALITY CONTROL TESTING AS SPECIFIED IN SECTION: PORTLAND CEMENT CONCRETE PAVING.
  4. TESTING REQUIRED UNDER SECTION: AGGREGATE BASE FOR ACCESS ROADS, PADS AND ANCHOR LOCATIONS
  5. STRUCTURAL BACKFILL COMPACTION TESTS FOR THE TOWER FOUNDATION.
  6. SITE RESISTANCE TO EARTH TESTING PER EXHIBIT: CELL SITE GROUNDING SYSTEM DESIGN.
  7. ANTENNA AND COAX SWEEP TESTS PER EXHIBIT: ANTENNA TRANSMISSION LINE ACCEPTANCE STANDARDS.
  8. GROUNDING AT ANTENNA MASTS FOR GPS AND ANTENNAS
  9. ALL OTHER TESTS REQUIRED BY COMPANY OR JURISDICTION.

3.3 REQUIRED INSPECTIONS

- A. SCHEDULE INSPECTIONS WITH COMPANY REPRESENTATIVE.
- B. CONDUCT INSPECTIONS INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
  1. GROUNDING SYSTEM INSTALLATION PRIOR TO EARTH CONCEALMENT DOCUMENTED WITH DIGITAL PHOTOGRAPHS BY CONTRACTOR, APPROVED BY A&E OR SPRINT REPRESENTATIVE.
  2. FORMING FOR CONCRETE AND REBAR PLACEMENT PRIOR TO POUR DOCUMENTED WITH DIGITAL PHOTOGRAPHS BY CONTRACTOR, APPROVED BY A&E OR SPRINT REPRESENTATIVE.
  3. COMPACTION OF BACKFILL MATERIALS; AGGREGATE BASE FOR ROADS, PADS, AND ANCHORS; ASPHALT PAVING; AND SHAFT BACKFILL FOR CONCRETE AND WOOD POLES, BY INDEPENDENT THIRD PARTY AGENCY.
  4. PRE- AND POST-CONSTRUCTION ROOFTOP AND STRUCTURAL INSPECTIONS ON EXISTING FACILITIES.
  5. TOWER ERECTION SECTION STACKING AND PLATFORM ATTACHMENT DOCUMENTED BY DIGITAL PHOTOGRAPHS BY THIRD PARTY AGENCY.
  6. ANTENNA AZIMUTH, DOWN TILT AND PER SUNLIGHT TOOL SUNSIGHT INSTRUMENTS - ANTENNALIGN ALIGNMENT TOOL (AAT)

PLANS PREPARED FOR:



PLANS PREPARED BY:



1033 Watervliet Shaker Rd, Albany, NY 12205, Office # (518) 690-0790, Fax # (518) 690-0793

JOB NUMBER 333-000

ENGINEERING LICENSE:

DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR REVIEW	05/15/14	JDV	A

SITE NAME:

WESTPORT / BAM

SITE CASCADE:

CT03XC382

SITE ADDRESS:

2 SUNNY LANE, WESTPORT, CT 06880

SHEET DESCRIPTION:

SPRINT SPECIFICATIONS

SHEET NUMBER:

SP-2

**CONTINUE FROM SP-2**

7. VERIFICATION DOCUMENTED WITH THE ANTENNA CHECKLIST REPORT, BY A&E, SITE DEVELOPMENT REP, OR RF REP.
  8. FINAL INSPECTION CHECKLIST AND HANDOFF WALK (HOC.). SIGNED FORM SHOWING ACCEPTANCE BY FIELD OPS IS TO BE UPLOADED INTO SMS.
  9. COAX SWEEP AND FIBER TESTING DOCUMENTS SUBMITTED VIA SMS FOR RF APPROVAL.
  10. SCAN-ABLE BARCODE PHOTOGRAPHS OF TOWER TOP AND INACCESSIBLE SERIALIZED EQUIPMENT
  11. ALL AVAILABLE JURISDICTIONAL INFORMATION
  12. PDF SCAN OF REDLINES PRODUCED IN FIELD
  - C. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN SITE INSPECTION ACTIVITIES AND/OR AS A RESULT OF TESTING.
  - D. CONSTRUCTION INSPECTIONS AND CORRECTIVE MEASURES SHALL BE DOCUMENTED BY THE CONTRACTOR WITH WRITTEN REPORTS AND PHOTOGRAPHS. PHOTOGRAPHS MUST BE DIGITAL AND OF SUFFICIENT QUALITY TO CLEARLY SHOW THE SITE CONSTRUCTION. PHOTOGRAPHS MUST CLEARLY IDENTIFY THE PHOTOGRAPHED ITEM AND BE LABELED WITH THE SITE CASCADE NUMBER, SITE NAME, DESCRIPTION, AND DATE.
- 3.4 DELIVERABLES: TEST AND INSPECTION REPORTS AND CLOSEOUT DOCUMENTATION SHALL BE UPLOADED TO THE SMS AND/OR FORWARDED TO SPRINT FOR INCLUSION INTO THE PERMANENT SITE FILES.
- A. THE FOLLOWING TEST AND INSPECTION REPORTS SHALL BE PROVIDED AS APPLICABLE.
    1. CONCRETE MIX AND CYLINDER BREAK REPORTS.
    2. STRUCTURAL BACKFILL COMPACTION REPORTS.
    3. SITE RESISTANCE TO EARTH TEST.
    4. ANTENNA AZIMUTH AND DOWN TILT VERIFICATION
    5. TOWER ERECTION INSPECTIONS AND MEASUREMENTS DOCUMENTING TOWER INSTALLED PER SUPPLIER'S REQUIREMENTS AND THE APPLICABLE SECTIONS HEREIN.
    6. COAX CABLE SWEEP TESTS PER COMPANY'S "ANTENNA LINE ACCEPTANCE STANDARDS".
  - B. REQUIRED CLOSEOUT DOCUMENTATION INCLUDES THE FOLLOWING;
    1. TEST WELLS AND TRENCHES: PHOTOGRAPHS OF ALL TEST WELLS; PHOTOGRAPHS SHOWING ALL OPEN EXCAVATIONS AND TRENCHING PRIOR TO BACKFILLING SHOWING A TAPE MEASURE VISIBLE IN THE EXCAVATIONS INDICATING DEPTH.
    2. CONDUITS, CONDUCTORS AND GROUNDING: PHOTOGRAPHS SHOWING TYPICAL INSTALLATION OF CONDUCTORS AND CONNECTORS; PHOTOGRAPHS SHOWING TYPICAL BEND RADIUS OF INSTALLED GROUND WIRES AND GROUND ROD SPACING;
    3. CONCRETE FORMS AND REINFORCING: CONCRETE FORMING AT TOWER AND EQUIPMENT/SHELTER PAD/FOUNDATIONS - PHOTOGRAPHS SHOWING ALL REINFORCING STEEL, UTILITY AND CONDUIT STUB OUTS; PHOTOGRAPHS SHOWING CONCRETE POUR OF SHELTER SLAB/FOUNDATION, TOWER FOUNDATION AND GUY ANCHORS WITH VIBRATOR IN USE; PHOTOGRAPHS SHOWING EACH ANCHOR ON GUYED TOWERS, BEFORE CONCRETE POUR.
    4. TOWER, ANTENNAS AND MAINLINE: INSPECTION AND PHOTOGRAPHS OF SECTION STACKING; INSPECTION AND PHOTOGRAPHS OF PLATFORM COMPONENT ATTACHMENT POINTS; PHOTOGRAPHS OF TOWER TOP GROUNDING; PHOTOS OF TOWER COAX LINE COLOR CODING AT THE TOP AND AT GROUND LEVEL; INSPECTION AND PHOTOGRAPHS OF OPERATIONAL OF TOWER LIGHTING, AND PLACEMENT OF FAA REGISTRATION SIGN; PHOTOGRAPHS SHOWING ADDITIONAL GROUNDING POINTS FOR TOWERS GREATER THAN 200 FEET.; PHOTOS OF ANTENNA GROUND BAR, EQUIPMENT GROUND BAR, AND MASTER GROUND BAR; PHOTOS OF GPS ANTENNA(S); PHOTOS OF EACH SECTOR OF ANTENNAS; ONE PHOTOGRAPH LOOKING AT THE SECTOR AND ONE FROM BEHIND SHOWING THE PROJECTED COVERAGE AREA; PHOTOS OF COAX WEATHERPROOFING - TOP AND BOTTOM; PHOTOS OF COAX GROUNDING--TOP AND BOTTOM; PHOTOS OF ANTENNA AND MAST GROUNDING; PHOTOS OF COAX CABLE ENTRY INTO SHELTER; PHOTOS OF PLATFORM MECHANICAL CONNECTIONS TO TOWER/MONOPOLE.
    5. ROOF TOPS: PRE-CONSTRUCTION AND POST-CONSTRUCTION VISUAL INSPECTION AND PHOTOGRAPHS OF THE ROOF AND INTERIOR TO DETERMINE AND DOCUMENT CONDITIONS; ROOF TOP CONSTRUCTION INSPECTIONS AS REQUIRED BY THE JURISDICTION; PHOTOGRAPHS OF CABLE TRAY AND/OR ICE BRIDGE; PHOTOGRAPHS OF DOGHOUSE/CABLE EXIT FROM ROOF;
    6. SITE LAYOUT - PHOTOGRAPHS OF THE OVERALL COMPOUND, INCLUDING EQUIPMENT PLATFORM FROM ALL FOUR CORNERS.
    7. FINISHED UTILITIES: CLOSE-UP PHOTOGRAPHS OF THE PPC BREAKER PANEL; CLOSE-UP PHOTOGRAPH OF THE INSIDE OF THE TELCO PANEL AND NIU; CLOSE-UP PHOTOGRAPH OF THE POWER METER AND DISCONNECT; PHOTOS OF POWER AND TELCO ENTRANCE TO COMPANY ENCLOSURE; PHOTOGRAPHS AT METER BOX AND/OR FACILITY DISTRIBUTION PANEL.
    8. REQUIRED MATERIALS CERTIFICATIONS: CONCRETE MIX DESIGNS; MILL CERTIFICATION FOR ALL REINFORCING AND STRUCTURAL STEEL; AND ASPHALT PAVING MIX DESIGN.
    9. ANY AND ALL SUBMITTALS BY THE JURISDICTION OR COMPANY.

**SECTION 01 400 - SUBMITTALS & TESTS**

**PART 1 - GENERAL**

- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
  - A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
  - B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.

**PART 2 - PRODUCTS (NOT USED)**

**PART 3 - EXECUTION**

- 3.1 WEEKLY REPORTS:
  - A. CONTRACTOR SHALL PROVIDE SPRINT WITH WEEKLY REPORTS SHOWING PROJECT STATUS. THIS STATUS REPORT FORMAT WILL BE PROVIDED TO THE CONTRACTOR BY SPRINT. THE REPORT WILL CONTAIN SITE ID NUMBER, THE MILESTONES FOR EACH SITE, INCLUDING THE BASELINE DATE, ESTIMATED COMPLETION DATE AND ACTUAL COMPLETION DATE.
  - B. REPORT INFORMATION WILL BE TRANSMITTED TO SPRINT VIA ELECTRONIC MEANS AS REQUIRED. THIS INFORMATION WILL PROVIDE A BASIS FOR PROGRESS MONITORING AND PAYMENT.
- 3.2 PROJECT CONFERENCE CALLS:
  - A. SPRINT MAY HOLD WEEKLY PROJECT CONFERENCE CALLS. CONTRACTOR WILL BE REQUIRED TO COMMUNICATE SITE STATUS, MILESTONE COMPLETIONS AND UPCOMING MILESTONE PROJECTIONS, AND ANSWER ANY OTHER SITE STATUS QUESTIONS AS NECESSARY.
- 3.3 PROJECT TRACKING IN SMS:
  - A. CONTRACTOR SHALL PROVIDE SCHEDULE UPDATES AND PROJECTIONS IN THE SMS SYSTEM ON A WEEKLY BASIS.
- 3.4 ADDITIONAL REPORTING:
  - A. ADDITIONAL OR ALTERNATE REPORTING REQUIREMENTS MAY BE ADDED TO THE REPORT AS DETERMINED TO BE REASONABLY NECESSARY BY COMPANY.
- 3.5 PROJECT PHOTOGRAPHS:
  - A. FILE DIGITAL PHOTOGRAPHS OF COMPLETED SITE IN JPEG FORMAT IN THE SMS PHOTO LIBRARY FOR THE RESPECTIVE SITE. PHOTOGRAPHS SHALL BE CLEARLY LABELED WITH SITE NUMBER, NAME AND DESCRIPTION, AND SHALL INCLUDE AT A MINIMUM THE FOLLOWING AS APPLICABLE:
    1. SHELTER AND TOWER OVERVIEW.
    2. TOWER FOUNDATION(S) - FORMS AND STEEL BEFORE POUR (EACH ANCHOR ON GUYED TOWERS).
    3. TOWER FOUNDATION(S) POUR WITH VIBRATOR IN USE (EACH ANCHOR ON GUYED TOWERS).
    4. TOWER STEEL AS BEING INSTALLED INTO HOLE (SHOW ANCHOR STEEL ON GUYED TOWERS).
    5. PHOTOS OF TOWER SECTION STACKING.
    6. CONCRETE TESTING / SAMPLES.
    7. PLACING OF ANCHOR BOLTS IN TOWER FOUNDATION.
    8. BUILDING/WATER TANK FROM ROAD FOR TENANT IMPROVEMENTS OR COMMENTS.
    9. SHELTER FOUNDATION--FORMS AND STEEL BEFORE POURING.
    10. SHELTER FOUNDATION POUR WITH VIBRATOR IN USE.
    11. COAX CABLE ENTRY INTO SHELTER.
    12. PLATFORM MECHANICAL CONNECTIONS TO TOWER/MONOPOLE.
    13. ROOFTOP PRE AND POST CONSTRUCTION PHOTOS TO INCLUDE PENETRATIONS AND INTERIOR CEILING.
    14. PHOTOS OF TOWER TOP COAX LINE COLOR CODING AND COLOR CODING AT GROUND LEVEL.
    15. PHOTOS OF ALL APPROPRIATE COMPANY OR REGULATORY SIGNAGE.
    16. PHOTOS OF EQUIPMENT BOLT DOWN INSIDE SHELTER.
    17. POWER AND TELCO ENTRANCE TO COMPANY ENCLOSURE AND POWER AND TELCO SUPPLY LOCATIONS INCLUDING METER/DISCONNECT.
    18. ELECTRICAL TRENCH(S) WITH ELECTRICAL / CONDUIT BEFORE BACKFILL.
    19. ELECTRICAL TRENCH(S) WITH FOIL-BACKED TAPE BEFORE FURTHER BACKFILL.
    20. TELCO TRENCH WITH TELEPHONE / CONDUIT BEFORE BACKFILL.
    21. TELCO TRENCH WITH FOIL-BACKED TAPE BEFORE FURTHER BACKFILL.
    22. SHELTER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADII).
    23. TOWER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADII).

24. FENCE GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADII).
25. ALL BTS GROUND CONNECTIONS.
26. ALL GROUND TEST WELLS.
27. ANTENNA GROUND BAR AND EQUIPMENT GROUND BAR.
28. ADDITIONAL GROUNDING POINTS ON TOWERS ABOVE 200'.
29. HVAC UNITS INCLUDING CONDENSERS ON SPLIT SYSTEMS.
30. GPS ANTENNAS.
31. CABLE TRAY AND/OR WAVEGUIDE BRIDGE.
32. DOGHOUSE/CABLE EXIT FROM ROOF.
33. EACH SECTOR OF ANTENNAS; ONE PHOTOGRAPH LOOKING AT THE SECTOR AND ONE FROM BEHIND SHOWING THE PROJECTED COVERAGE AREA.
34. MASTER BUS BAR.
35. TELCO BOARD AND NIU.
36. ELECTRICAL DISTRIBUTION WALL.
37. CABLE ENTRY WITH SURGE SUPPRESSION.
38. ENTRANCE TO EQUIPMENT ROOM.
39. COAX WEATHERPROOFING--TOP AND BOTTOM OF TOWER.
40. COAX GROUNDING -TOP AND BOTTOM OF TOWER.
41. ANTENNA AND MAST GROUNDING.
42. LANDSCAPING - WHERE APPLICABLE.

3.6 FINAL PROJECT ACCEPTANCE: COMPLETE ALL REQUIRED REPORTING TASKS PER CONTRACT, CONTRACT DOCUMENTS OR THE SPRINT INTEGRATED CONSTRUCTION STANDARDS FOR WIRELESS SITES AND UPLOAD INTO SITERRA.

PLANS PREPARED FOR:



PLANS PREPARED BY:



ENGINEERING LICENSE:

DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR REVIEW	05/15/14	JDV	A

SITE NAME:

**WESTPORT / BAM**

SITE CASCADE:

**CT03XC382**

SITE ADDRESS:

**2 SUNNY LANE  
WESTPORT, CT 06880**



SHEET DESCRIPTION:

**SPRINT SPECIFICATIONS**

SHEET NUMBER:


**SP-3**

INFORMATION CONTAINED WITHIN DRAWINGS ARE BASED ON PROVIDED INFORMATION AND ARE NOT THE RESULT OF A FIELD SURVEY.



OVERALL SITE PLAN

SCALE: AS NOTED 1



SPRINT EQUIPMENT PLAN

SCALE: AS NOTED 2

PLANS PREPARED FOR:

6580 Sprint Parkway  
Overland Park, Kansas 66251

PLANS PREPARED BY:

1033 Watervliet Shaker Rd  
Albany, NY 12205  
Office # (518) 690-0790  
Fax # (518) 690-0793  
JOB NUMBER 333-000

ENGINEERING LICENSE:

DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR REVIEW	05/15/14	JDV	A

SITE NAME:  
**WESTPORT / BAM**

SITE CASCADE:  
**CT03XC382**

SITE ADDRESS:  
**2 SUNNY LANE  
WESTPORT, CT 06880**


SHEET DESCRIPTION:  
**SITE PLAN**

SHEET NUMBER:  
**A-1**



**NOTE:**  
 INFINIGY ENGINEERING HAS NOT EVALUATED THE EXISTING STRUCTURE FOR THIS SITE, AND ASSUMES NO RESPONSIBILITY FOR ITS STRUCTURAL INTEGRITY. REFER TO STRUCTURAL ANALYSIS BY OTHERS PRIOR TO ANY CONSTRUCTION.

**NOTE:**  
 SEE DETAIL 2 ON A-3 FOR ANTENNA LAYOUT



PLANS PREPARED FOR:

**Sprint**

6580 Sprint Parkway  
 Overland Park, Kansas 66251

PLANS PREPARED BY:

**INFINIGY** Design. Build. Deliver.

1033 Watervliet Shaker Rd  
 Albany, NY 12205  
 Office # (518) 690-0790  
 Fax # (518) 690-0793

JOB NUMBER 333-000

ENGINEERING LICENSE:

DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR REVIEW	05/15/14	JDV	A

SITE NAME:

**WESTPORT / BAM**

SITE CASCADE:

**CT03XC382**

SITE ADDRESS:


**2 SUNNY LANE  
 WESTPORT, CT 06880**

SHEET DESCRIPTION:

**TOWER ELEVATION  
 & CABLE PLAN**

SHEET NUMBER:


**A-2**



EXISTING ANTENNA & RRU LAYOUT

NO SCALE


1



FINAL ANTENNA LAYOUT

NO SCALE


2



DETAIL NOT USED

NO SCALE

3



TYPICAL ANTENNA & RRU MOUNTING DETAILS

NO SCALE

4

PLANS PREPARED FOR:

6580 Sprint Parkway  
Overland Park, Kansas 66251

PLANS PREPARED BY:

1033 Watervliet Shaker Rd  
Albany, NY 12205  
Office # (518) 690-0790  
Fax # (518) 690-0793  
JOB NUMBER 333-000

ENGINEERING LICENSE:

DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR REVIEW	05/15/14	JDV	A

SITE NAME:  
WESTPORT / BAM

SITE CASCADE:  
CT03XC382

SITE ADDRESS:  
2 SUNNY LANE  
WESTPORT, CT 06880

SHEET DESCRIPTION:  
ANTENNA LAYOUT  
& MOUNTING DETAILS


SHEET NUMBER:  
A-3

NV CABLES				
BAND	INDICATOR		PORT	COLOR
800-1	YEL	GRN	NV-1	GRN
1900-1	YEL	RED	NV-2	BLU
1900-2	YEL	BRN	NV-3	BRN
1900-3	YEL	BLU	NV-4	WHT
1900-4	YEL	SLT	NV-5	RED
800-2	YEL	ORG	NV-6	SLT
SPARE	YEL	WHT	NV-7	PPL
2500	YEL	PPL	NV-8	ORG

HYBRID	
HYBRID	COLOR
1	GRN
2	BLU
3	BRN
4	WHT
5	RED
6	SLT
7	PPL
8	ORG

2.5 Band		
2500 Radio 1	COLOR	
YEL	WHT	GRN
YEL	WHT	BLU
YEL	WHT	BRN
YEL	WHT	WHT
YEL	WHT	RED
YEL	WHT	SLT
YEL	WHT	PPL
YEL	WHT	ORG

Figure 1: Antenna Orientation






NOTES:

- ALL CABLES SHALL BE MARKED WITH 2" WIDE, UV STABILIZED, UL APPROVED TAPE.
- THE FIRST RING SHALL BE CLOSEST TO THE END OF THE CABLE AND SPACED APPROXIMATELY 2" FROM THE END CONNECTOR, WEATHERPROOFING, OR BREAK-OUT CYLINDER. THERE SHALL BE A 1" SPACE BETWEEN EACH RING FOR THE CABLE IDENTIFIER, AND NO SPACES BETWEEN THE FREQUENCY BANDS.
- A 2" GAP SHALL SEPARATE THE CABLE COLOR CODE FROM THE FREQUENCY COLOR CODE. THE 2" COLOR RINGS FOR THE FREQUENCY CODE SHALL BE PLACED NEXT TO EACH OTHER WITH NO SPACES.
- THE 2" COLORED TAPE(S) SHALL EACH BE WRAPPED A MINIMUM OF 3 TIMES AROUND THE INDIVIDUAL CABLES, AND THE TAPE SHALL BE KEPT IN THE SAME LOCATION AS MUCH AS POSSIBLE.
- SITES WITH MORE THAN FOUR (4) SECTORS WILL REQUIRE ADDITIONAL RINGS FOR EACH SECTOR, FOLLOWING THE PATTERN. HIGH CAPACITY SITES WILL USE THE NEXT COLOR IN THE SEQUENCE FOR ADDITIONAL CABLES IN EACH SECTOR.
- HYBRID FIBER CABLE SHALL BE SECTOR IDENTIFIED INSIDE THE CABINET ON FREQUENCY BUNDLES, ON THE SEALTITE, ON THE MAIN LINE UPON EXIT OF SEALTITE, AND BEFORE AND AFTER THE BREAKOUT UNIT (MEDUSA), AS WELL AS BEFORE AND AFTER ANY ENTRANCE OR EXIT.
- HFC "MAIN TRUNK" WILL NOT BE MARKED WITH THE FREQUENCY CODES, AS IT CONTAINS ALL FREQUENCIES.
- INDIVIDUAL POWER PAIRS AND FIBER BUNDLES SHALL BE LABELED WITH BOTH THE CABLE AND FREQUENCY.

Sector	Cable	First Ring	Second Ring	Third Ring
1 Alpha	1	Green	No Tape	No Tape
1	2	Blue	No Tape	No Tape
1	3	Brown	No Tape	No Tape
1	4	White	No Tape	No Tape
1	5	Red	No Tape	No Tape
1	6	Grey	No Tape	No Tape
1	7	Purple	No Tape	No Tape
1	8	Orange	No Tape	No Tape
2 Beta	1	Green	Green	No Tape
2	2	Blue	Blue	No Tape
2	3	Brown	Brown	No Tape
2	4	White	White	No Tape
2	5	Red	Red	No Tape
2	6	Grey	Grey	No Tape
2	7	Purple	Purple	No Tape
2	8	Orange	Orange	No Tape
3 Gamma	1	Green	Green	Green
3	2	Blue	Blue	Blue
3	3	Brown	Brown	Brown
3	4	White	White	White
3	5	Red	Red	Red
3	6	Grey	Grey	Grey
3	7	Purple	Purple	Purple
3	8	Orange	Orange	Orange

NV FREQUENCY	INDICATOR	ID
800-1	YEL	GRN
1900-1	YEL	RED
1900-2	YEL	BRN
1900-3	YEL	BLU
1900-4	YEL	SLT
800-1	YEL	ORG
RESERVED	YEL	WHT
RESERVED	YEL	PPL

2.5 FREQUENCY	INDICATOR	ID
2500 -1	YEL	WHT
2500 -2	YEL	WHT
2500 -3	YEL	WHT
2500 -4	YEL	WHT
2500 -5	YEL	WHT
2500 -6	YEL	WHT
2500 -7	YEL	WHT
2500 -8	YEL	WHT



PLANS PREPARED FOR:

6580 Sprint Parkway  
Overland Park, Kansas 66251

PLANS PREPARED BY:

1033 Watervliet Shaker Rd  
Albany, NY 12205  
Office # (518) 690-0790  
Fax # (518) 690-0793  
JOB NUMBER 333-000

ENGINEERING LICENSE:

DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:	DESCRIPTION	DATE	BY	REV
ISSUED FOR REVIEW		05/15/14	JDV	A

SITE NAME:  
WESTPORT / BAM

SITE CASCADE:  
CT03XC382



SITE ADDRESS:  
2 SUNNY LANE  
WESTPORT, CT 06880

SHEET DESCRIPTION:  
COLOR CODING AND NOTES


SHEET NUMBER:  
A-4

RRU: ALCATEL LUCENT TD-RRH8X20

COLOR: LIGHT GREY  
WEIGHT: 70 LBS.




FRONT VIEW




PLAN VIEW

**NOTES**

COMPLY WITH MANUFACTURERS INSTRUCTIONS TO ENSURE THAT ALL RRU'S RECEIVE ELECTRICAL POWER WITHIN 24 HOURS OF BEING REMOVED FROM THE MANUFACTURER'S PACKAGING. DO NOT OPEN RRU PACKAGES IN THE RAIN.



BOTTOM VIEW



SIDE VIEW

2.5 RRU'S

NO SCALE

1


9929 GROWTH CABINET

NO SCALE


2

**ANTENNA RFS APXVTM14-C-I20**

RADOME MATERIAL: ASA  
RADOME COLOR: LIGHT GREY  
DIMENSIONS, HxWxD.in(mim): 56.3"x12.6"x6.3" (1430x320x160mm)  
WEIGHT: 52.9 lbs  
CONNECTORS: (8) 4.1/9.5 DIN FEMALE  
(1) NF - CALIBRATION CONNECTOR



PLAN VIEW




SIDE VIEW

FRONT VIEW

2.5 ANTENNA

NO SCALE

3



**NOTES:**

1. VERIFY BOLT HOLE SPACING WITH EQUIPMENT CUT SHEETS.
2. NEW EQUIPMENT CABINET TO BE MOUNTED TO EXISTING CONCRETE PAD WITH BOLT-DOWN SYSTEM PER MANUFACTURER'S SPECIFICATION. FIELD DRILL HOLES IN EXISTING CONCRETE AS REQUIRED.

EQUIPMENT MOUNT DETAIL

NO SCALE

4

PLANS PREPARED FOR:



PLANS PREPARED BY:



1033 Watervliet Shaker Rd  
Albany, NY 12205  
Office # (518) 690-0790  
Fax # (518) 690-0793

JOB NUMBER 333-000

ENGINEERING LICENSE:

DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR REVIEW	05/15/14	JDV	A

SITE NAME:

WESTPORT / BAM

SITE CASCADE:

CT03XC382

SITE ADDRESS:

2 SUNNY LANE  
WESTPORT, CT 06880

SHEET DESCRIPTION:

EQUIPMENT &  
MOUNTING DETAILS

SHEET NUMBER:

A-5


**RFS HYBRIFLEX RISER CABLE SCHEDULE**

Fiber Only (Existing DC Power)	Hybrid cable MN: HB058-M12-050F 12x multi-mode fiber pairs, Top: Outdoor protected connectors, Bottom: LC Connectors, 5/8 cable, 50 ft	50 ft
	MN: HB058-M12-075F	75 ft
	MN: HB058-M12-100F	100 ft
	MN: HB058-M12-125F	125 ft
	MN: HB058-M12-150F	150 ft
	MN: HB058-M12-175F	175 ft
MN: HB058-M12-200F	200 ft	
8 AWG Power	Hybrid cable MN: HB114-08U3M12-050F 3x 8 AWG power pairs, 12x multi-mode fiber pairs, Outdoor rated connectors & LC Connectors, 1 1/4 cable, 50 ft	50 ft
	MN: HB114-08U3M12-075F	75 ft
	MN: HB114-08U3M12-100F	100 ft
	MN: HB114-08U3M12-125F	125 ft
	MN: HB114-08U3M12-150F	150 ft
	MN: HB114-08U3M12-175F	175 ft
MN: HB114-08U3M12-200F	200 ft	
6 AWG Power	Hybrid cable MN: HB114-13U3M12-225F 3x 6 AWG power pair, 12x multi-mode fiber pairs, Outdoor rated connectors & LC Connectors, 1 1/4 cable, 225 ft	225 ft
	MN: HB114-13U3M12-250F	250 ft
	MN: HB114-13U3M12-275F	275 ft
4 AWG Power	Hybrid cable MN: HB114-21U3M12-325F 3x 4 AWG power pair, 12x multi-mode fiber pairs, Outdoor rated connectors & LC Connectors, 1 1/4 cable, 325 ft	325 ft
	MN: HB114-21U3M12-350F	350 ft
	MN: HB114-21U3M12-375F	375 ft


**RFS HYBRIFLEX JUMPER CABLE SCHEDULE**

Fiber Only	Hybrid Jumper cable MN: HBF012-M3-5F1 5 ft, 3x multi-mode fiber pairs, Outdoor & LC connectors, 1/2 cable	5 ft
	MN: HBF012-M3-10F1	10 ft
	MN: HBF012-M3-15F1	15 ft
	MN: HBF012-M3-20F1	20 ft
	MN: HBF012-M3-25F1	25 ft
	MN: HBF012-M3-30F1	30 ft
8 AWG Power	Hybrid Jumper cable MN: HBF058-08U1M3-5F1 5 ft, 1x 8 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 5/8 cable	5 ft
	MN: HBF058-08U1M3-10F1	10 ft
	MN: HBF058-08U1M3-15F1	15 ft
	MN: HBF058-08U1M3-20F1	20 ft
	MN: HBF058-08U1M3-25F1	25 ft
	MN: HBF058-08U1M3-30F1	30 ft
6 AWG Power	Hybrid Jumper cable MN: HBF058-13U1M3-5F1 5 ft, 1x 6 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 5/8 cable	5 ft
	MN: HBF058-13U1M3-10F1	10 ft
	MN: HBF058-13U1M3-15F1	15 ft
	MN: HBF058-13U1M3-20F1	20 ft
	MN: HBF058-13U1M3-25F1	25 ft
	MN: HBF058-13U1M3-30F1	30 ft
4 AWG Power	Hybrid Jumper cable MN: HBF078-21U1M3-5F1 5 ft, 1x 4 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 7/8 cable	5 ft
	MN: HBF078-21U1M3-10F1	10 ft
	MN: HBF078-21U1M3-15F1	15 ft
	MN: HBF078-21U1M3-20F1	20 ft
	MN: HBF078-21U1M3-25F1	25 ft
	MN: HBF078-21U1M3-30F1	30 ft


NOTE:  
SPRINT CM TO CONFIRM HYBRID OR FIBER RISER CABLE AND HYBRID OR FIBER JUMPER CABLE MODEL NUMBERS IF HYBRID CABLES ARE REQUIRED BEFORE PREPARING BOM.




**4 AWG**



**8 & 6 AWG**



**FIBER ONLY**



**FIBER JUNCTION BOX PENETRATION**

NO SCALE

2

2.5 CABLE CROSS SECTION DATA

NO SCALE

1

DETAIL NOT USED

NO SCALE

3

PLANS PREPARED FOR:



PLANS PREPARED BY:



1033 Watervliet Shaker Rd  
Albany, NY 12205  
Office # (518) 690-0790  
Fax # (518) 690-0793

JOB NUMBER 333-000

ENGINEERING LICENSE:

DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR REVIEW	05/15/14	JDV	A

SITE NAME:

WESTPORT / BAM

SITE CASCADE:

CT03XC382

SITE ADDRESS:


2 SUNNY LANE  
WESTPORT, CT 06880

SHEET DESCRIPTION:


CIVIL DETAILS

SHEET NUMBER:


A-6



ALU 2.5 ALU SCENARIO 1



RAN WIRING DIAGRAM



RF 2.5 ALU SCENARIO 1

PLANS PREPARED FOR:



PLANS PREPARED BY:



1033 Watervliet Shaker Rd  
Albany, NY 12205  
Office # (518) 690-0790  
Fax # (518) 690-0793

JOB NUMBER 333-000

ENGINEERING LICENSE:

DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR REVIEW	05/15/14	JDV	A

SITE NAME:

WESTPORT / BAM

SITE CASCADE:

CT03XC382

SITE ADDRESS:

2 SUNNY LANE  
WESTPORT, CT 06880

SHEET DESCRIPTION:



PLUMBING DIAGRAM

SHEET NUMBER:


A-7

**PLAN NOT USED**

NO SCALE 1



**NOTES**  
 GC SHALL REFERENCE ALL SPECS FOR "CONNECTING THE POWER SUPPLY" OF THE NEW INSTALLATION DOCUMENTS, FOR ALL CONNECTION SPECIFICATIONS.



CIRCUIT SCHEDULE			
NO	FROM	TO	CONFIGURATION
①	UTILITY SOURCE	METER/DISCONNECT	EXISTING
②	METER/DISCONNECT	TRANSFER & LOAD CENTER	EXISTING
③	TRANSFER & LOAD CENTER	GENERATOR RECEPTACLE	EXISTING
④	TRANSFER & LOAD CENTER	EXISTING BATTERY CABINET	EXISTING
⑤	TRANSFER & LOAD CENTER	EXISTING NV MMBS CABINET	EXISTING
⑥	TRANSFER & LOAD CENTER	INSTALL SPRINT 9929 GROWTH CABINET	(3) #2 AWG, (1) #8 GND IN 2" CONDUIT

PLANS PREPARED FOR:  
**Sprint**  
 6580 Sprint Parkway  
 Overland Park, Kansas 66251

PLANS PREPARED BY:  
**INFINIGY** Design. Build. Deliver.  
 1033 Watervliet Shaker Rd  
 Albany, NY 12205  
 Office # (518) 690-0790  
 Fax # (518) 690-0793  
 JOB NUMBER 333-000

ENGINEERING LICENSE:

DRAWING NOTICE:  
 THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR REVIEW	05/15/14	JDV	A

SITE NAME:  
**WESTPORT / BAM**

SITE CASCADE:  
**CT03XC382**

SITE ADDRESS:  
**2 SUNNY LANE  
 WESTPORT, CT 06880**

SHEET DESCRIPTION:  
**ELECTRICAL &  
 GROUNDING DETAILS**

SHEET NUMBER:  
**E-2**


**ELECTRICAL ONE-LINE DIAGRAM**

NO SCALE 1

**LEGEND:**

- G — EXISTING GROUND RING
- CADWELD CONNECTION (EXOTHERMIC WELD)
- ▲ MECHANICAL CONNECTION
- ⊗ GROUND ROD
- CABLE GROUND KIT


**NOTE:**  
 USE #6 AWG BARE SOLID TINNED COPPER UNLESS NOTED OTHERWISE



**GROUNDING RISER DIAGRAM**

NO SCALE 4


#4 OR #6 AWG SOLID CU CONDUCTOR WITH GREEN, 600V, THWN-2 INSULATION



**NOTES**  
 1. APPLY NO-OX TO LUG AND BAR CONTACT SURFACE. DO NOT COAT INLINE LUG.  
 2. IF STOLEN GROUND BARS ARE ENCOUNTERED, CONTACT SPRINT CM FOR REPLACEMENT THREADED ROD KIT.

**INSTALLATION OF GROUNDING CONDUCTOR TO GROUNDING BAR**

NO SCALE 2



**TWO HOLE LUG**

NO SCALE 3



# INFINIGY Design. Build. Deliver.

1033 Watervliet Shaker Road | Albany, NY 12205  
Phone: 518-690-0790 | Fax: 518-690-0793  
www.infinigy.com

---

**November 20, 2014**

Gary Wood  
Construction Project Manager III  
Southern Connecticut  
9 Barnes Industrial Road South  
Wallingford, CT 06492

**RE: Sprint 2.5 Project Antenna and RRH Support Evaluation**

Sprint Site Number: CT03XC382  
Sprint Site Name: WESTPORT/BAM  
Site Address: 2 Sunny Lane, Westport, CT 06880  
Jurisdiction: Town of Westport

Dear Mr. Wood:

Per your request, Infinigy Engineering has reviewed the adequacy of the antenna and RRH supports at the above referenced site for the Sprint 2.5 Project. The purpose of this review was to determine if the existing and/or proposed mounts to be used are in conformance with the governing International Building Code (2003), 2005 CT Supplement and 2013 CT Amendment and the applicable industry standard TIA-222-G 2005 (Structural Standard for Antenna Supporting Structures and Antennas).

Based on a review of the information from the Structural Analysis Report (dated 11/11/14) provided by Centek Engineering (Project Number 14033.012) and Construction Drawings (dated 07/28/14) provided by Infinigy, we have concluded that **the antenna and RRH supports will be adequate** to support the Sprint 2.5 equipment to be deployed at this site once a **Site Pro 1 HRK-12 handrail kit is installed with L3"x3"x 3/8" bracing angles having a minimum length of 48" connecting handrail to handrail.**

This certification assumes that all structural members are in good condition and have not been altered from the manufacturer's original design. Prior to installation of any new antennas and/or RRHs, the contractor shall inspect the condition of all relevant members and connections. The contractor shall be responsible for the means and methods of construction.

Should there be any questions, please do not hesitate to contact us.

Sincerely,

Joseph R. Johnston, P.E.  
Department Manager - Structural  
Connecticut PE License Number: PEN.0029460



---

NJ Office: 479 Rte 17 North | Mahwah, NJ 07430

GA Office: 2255 Sewell Mill Road | Ste 130 | Marietta, GA 30062

CA Office: 26455 Rancho Parkway South | Lake Forest, CA 92630

RADIO FREQUENCY FCC REGULATORY COMPLIANCE  
MAXIMUM PERMISSIBLE EXPOSURE (MPE) ASSESSMENT

Sprint Existing Facility

Site ID: CT03XC382

Westport / BAM

2 Sunny Lane  
Westport, CT 06880

**December 12, 2014**

**EBI Project Number: 62146528**

December 12, 2014

Sprint  
Attn: RF Engineering Manager  
1 International Boulevard, Suite 800  
Mahwah, NJ 07495

Re: Radio Frequency Maximum Permissible Exposure (MPE) Assessment for Site:  
**CT03XC382 - Westport / BAM**

**Site Total: 61.18% - MPE% in full compliance**

EBI Consulting was directed to analyze the proposed upgrades to the existing Sprint facility located at **2 Sunny Lane, Westport, CT**, for the purpose of determining whether the radio frequency (RF) exposure levels from the proposed Sprint equipment upgrades on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter ( $\mu\text{W}/\text{cm}^2$ ). The number of  $\mu\text{W}/\text{cm}^2$  calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits, therefore it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) – (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general public may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general public would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

Public exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter ( $\mu\text{W}/\text{cm}^2$ ). The general population exposure limit for the cellular band (850 MHz Band) is approximately  $567 \mu\text{W}/\text{cm}^2$ , and the general population exposure limit for the 1900 MHz and 2500 MHz bands is  $1000 \mu\text{W}/\text{cm}^2$ . Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.

Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure. Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

## **CALCULATIONS**

Calculations were done for the proposed upgrades to the existing Sprint Wireless antenna facility located at **2 Sunny Lane, Westport, CT**, using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. All calculations were performed assuming a lobe representing the maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was focused at the base of the tower. For this report the sample point is the top of a 6 foot person standing at the base of the tower.

For all calculations, all emissions were calculated using the following assumptions:

- 1) 2 channels in the 1900 MHz Band were considered for each sector of the proposed installation.
- 2) 1 channel in the 800 MHz Band was considered for each sector of the proposed installation.
- 3) 2 channels in the 2500 MHz Band were considered for each sector of the proposed installation.
- 4) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 - Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.

- 5) For the following calculations the sample point was the top of a six foot person standing at the base of the tower. The maximum gain of the antenna per the antenna manufactures supplied specifications minus 10 dB was used in this direction. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 6) The antennas used in this modeling are the RFS APXVSPP18-C-A20 and the RFS APXVTM14-C-I20. This is based on feedback from the carrier with regards to anticipated antenna selection. The RFS APXVSPP18-C-A20 has a 15.9 dBd gain value at its main lobe at 1900 MHz and 13.4 dBd at its main lobe for 850 MHz. The RFS APXVTM14-C-I20 has a 15.9 dBd gain value at its main lobe at 2500 MHz. The maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was used for all calculations. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 7) The antenna mounting height centerline for the proposed antennas is **120 feet** above ground level (AGL).
- 8) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.

All calculation were done with respect to uncontrolled / general public threshold limits

Site ID	CT03XC382 - Westport / BAM
Site Address	2 Sunny Lane, Westport, CT, 06880
Site Type	Monopole

**Sector 1**

Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain (10 db reduction)	Antenna Height (ft)	analysis height	Cable Size	Cable Loss (dB)	Additional Loss (dB)	ERP	Power Density Percentage
1a	RFS	APXVSP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	2	40	5.9	120	114	1/2 "	0.5	0	138.69	0.38%
1a	RFS	APXVSP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	3.4	120	114	1/2 "	0.5	0	39.00	0.19%
1B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	5.9	120	114	1/2 "	0.5	0	138.69	0.68%
Sector total Power Density Value:																1.25%

**Sector 2**

Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain (10 db reduction)	Antenna Height (ft)	analysis height	Cable Size	Cable Loss (dB)	Additional Loss (dB)	ERP	Power Density Percentage
2a	RFS	APXVSP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	2	40	5.9	120	114	1/2 "	0.5	0	138.69	0.38%
2a	RFS	APXVSP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	3.4	120	114	1/2 "	0.5	0	39.00	0.19%
2B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	5.9	120	114	1/2 "	0.5	0	138.69	0.68%
Sector total Power Density Value:																1.25%

**Sector 3**

Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain (10 db reduction)	Antenna Height (ft)	analysis height	Cable Size	Cable Loss (dB)	Additional Loss (dB)	ERP	Power Density Percentage
3a	RFS	APXVSP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	2	40	5.9	120	114	1/2 "	0.5	0	138.69	0.38%
3a	RFS	APXVSP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	3.4	120	114	1/2 "	0.5	0	39.00	0.19%
3B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	5.9	120	114	1/2 "	0.5	0	138.69	0.68%
Sector total Power Density Value:																1.25%

Site Composite MPE %	
Carrier	MPE %
Sprint	3.75%
T-Mobile	0.29%
Clearwire	1.29%
Nextel	3.67%
Verizon Wireless	27.37%
AT&T	24.81%
<b>Total Site MPE %</b>	<b>61.18%</b>

## Summary

All calculations performed for this analysis yielded results that were well within the allowable limits for general public Maximum Permissible Exposure (MPE) to radio frequency energy.

The anticipated Maximum Composite contributions from the Sprint facility are **3.75% (1.25% from sector 1, 1.25% from sector 2 and 1.25% from sector 3)** of the allowable FCC established general public limit considering all three sectors simultaneously sampled at the ground level.

The anticipated composite MPE value for this site assuming all carriers present is **61.18%** of the allowable FCC established general public limit sampled at 6 feet above ground level. This total composite site value is based upon MPE values listed in the Connecticut Siting Council database for existing carrier emissions.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.



**Scott Heffernan**  
RF Engineering Director

**EBI Consulting**  
21 B Street  
Burlington, MA 01803