

June 26, 2024

Via Electronic Mail

Melanie A. Bachman, Esq.
Executive Director/Staff Attorney
Connecticut Siting Council
10 Franklin Square
New Britain, CT 06051

Re: **Notice of Exempt Modification – Facility Modification
Post Road (a/k/a 880 Post Road), Westport, Connecticut**

Dear Attorney Bachman:

Cellco Partnership d/b/a Verizon Wireless (“Cellco”) currently maintains an existing wireless telecommunications facility at the above-referenced property address (the “Property”). The facility consists of antennas on an existing tower and related equipment on the ground, near the base of the tower. The tower and Cellco’s use of the tower were approved by the Siting Council (“Council”) in March of 1990 (Docket No. 123). A copy of the Council’s Docket No. 123 Decision and Order is included in [Attachment 1](#).

Cellco now intends to modify its facility by removing five (5) antennas and two (2) remote radio heads (“RRHs”) and installing seven (7) new antennas and four (4) new RRHs on its existing antenna support structure. A set of project plans showing Cellco’s proposed facility modifications and the specifications for Cellco’s new antennas and RRHs are included in [Attachment 2](#).

Please accept this letter as notification pursuant to R.C.S.A. § 16-50j-73, for construction that constitutes an exempt modification pursuant to R.C.S.A. § 16-50j-72(b)(2). In accordance with R.C.S.A. § 16-50j-73, a copy of this letter is being sent to Westport’s Chief Elected Official and Land Use Officer and the tower owner. A copy of this letter is being sent to the owner of the Property.

The planned modifications to the facility fall squarely within those activities explicitly provided for in R.C.S.A. § 16-50j-72(b)(2).

29696407-v1

Robinson+Cole

Melanie A. Bachman, Esq.
June 26, 2024
Page 2

1. The proposed modifications will not result in an increase in the height of the existing tower. Cellco's new antennas and RRHs will be installed at the same height on the tower.

2. The proposed modifications will not involve any change to ground-mounted equipment and, therefore, will not require the extension of the site boundary.

3. The proposed modifications will not increase noise levels at the facility by six decibels or more, or to levels that exceed state and local criteria.

4. The installation of Cellco's new antennas will not increase radio frequency (RF) emissions at the facility to a level at or above the Federal Communications Commission (FCC) safety standard. Included in Attachment 3 is a Calculated Radio Frequency Emissions Report demonstrating that the proposed modified facility will comply with the FCC safety standards. The modified facility will be capable of providing Cellco's 5G wireless service.

5. The proposed modifications will not cause a change or alteration in the physical or environmental characteristics of the site.

6. According to the attached Structural Analysis Report ("SA") and Antenna Mount Analysis Report ("MA"), the existing tower, tower foundation, antenna supports and antenna mounts, with certain modifications, can support Cellco's proposed modifications. Copies of the SA and MA are included in Attachment 4.

A copy of the parcel map and Property owner information is included in Attachment 5. A Certificate of Mailing verifying that this filing was sent to municipal officials and the property owner is included in Attachment 6.

For the foregoing reasons, Cellco respectfully submits that the proposed modifications to the above-referenced telecommunications facility constitutes an exempt modification under R.C.S.A. § 16-50j-72(b)(2).

Sincerely,



Kenneth C. Baldwin

Enclosures

Copy to:

Jennifer Tooker, First Selectwoman
Mary Young, Planning and Zoning Director
State of Connecticut, Property Owner
Aleksy Tyurin

ATTACHMENT 1

An application of the Department	:	Docket 123
of Public Safety, Division of	:	
State Police, for a Certificate of	:	Connecticut
Environmental Compatibility and Public	:	Siting
Need for the construction, operation,	:	Council
and maintenance of a telecommunications	:	
tower and associated equipment in the	:	
Town of Westport, Connecticut.	:	March 29, 1990

DECISION AND ORDER

Pursuant to the foregoing Findings of Fact and Opinion, the Connecticut Siting Council finds that the effects associated with the construction, operation, and maintenance of a telecommunications tower, building, and associated equipment at the proposed Westport, Connecticut, site including effects on the natural environment; ecological integrity and balance; public health and safety; scenic, historic, and recreational values; forests and parks; air and water purity; and fish and wildlife are not significant either alone or cumulatively with other effects, are not in conflict with the policies of the State concerning such effects, and are not sufficient reason to deny the application, and therefore directs that a Certificate of Environmental Compatibility and Public Need, as provided by Section 16-50k of the General Statutes of Connecticut (CGS), be issued to Department of Public Safety, Division of State Police, for the construction, operation, and maintenance of a telecommunications tower, associated equipment, and building at the proposed Troop "G" site in Westport, Connecticut.

The facility shall be constructed, operated, and maintained substantially as specified in the Council's record in this proceeding, and subject to the following conditions:

1. The self-supporting lattice tower shall be no taller than necessary to provide the proposed communications and in no event shall the Westport, Troop "G", tower exceed 180 feet above ground level, with antennas and all appurtenances.
2. The facility shall be constructed in accordance with the State of Connecticut Basic Building Code.
3. The Certificate Holder shall prepare a Development and Management (D&M) Plan for this site in compliance with Sections 16-50j-75 through 16-50j-77 of the Regulations of State Agencies. The D&M plan shall include detailed plans for the site's preparation including the tower and building foundation, site access, and erosion and sedimentation controls.
4. The Certificate Holder shall comply with any future radio frequency (RF) standards, promulgated by State or federal regulatory agencies. Upon the establishment of any new governmental RF standards, the facilities granted in this Decision and Order shall be brought into compliance with such standards.

5. The Certificate Holder shall provide the Council a recalculated report of power density if and when circumstances in operation cause a change in power density above the levels originally calculated and provided in the application.
6. The Certificate Holder shall permit public or private entities to share space on the proposed tower for fair consideration, or shall provide any requesting entity with specific legal, technical, environmental, or economic reasons precluding such tower sharing.
7. If the facility does not initially provide, or permanently ceases to provide telecommunications service following completion of construction, this Decision and Order shall be void, and the tower and all associated equipment shall be dismantled and removed or reapplication for any new use shall be made to the Council before any such new use is made.
8. Unless otherwise approved by the Council, this Decision and Order shall be void if all construction authorized herein is not completed within three years of the effective date of this Decision and Order.

Pursuant to Section 16-50p, we hereby direct that a copy of the Findings of Fact, Opinion, and Decision and Order be served on each person listed below. A notice of issuance shall be published in the Bridgeport Post, The Hour, and the Advocate.

By this Decision and Order, the Council disposes of the legal rights, duties, and privileges of each party named or admitted to the proceeding in accordance with section 16-50j-17 of the Regulations of State Agencies.

The parties or intervenors to this proceeding are:

<u>Party</u>	<u>Its Representatives</u>
Department of Public Safety Division of State Police	Captain Ronald P. Milkulka Commanding Officer Connecticut State Police Police Support Services 294 Colony Street Building No. 5 Meriden, Connecticut 06450
	L.D. McCallum and Robert F. Vachelli Assistant Attorneys General MacKenzie Hall 110 Sherman Street Hartford, Connecticut 06105

Party

Metro Mobile CTS, of
Fairfield County, Inc.
50 Rockland Road
South Norwalk, Connecticut 06854

Its Representative

Henry H. Sprague, Esq.
Robinson & Cole
One Commercial Plaza
Hartford, Connecticut 06105

Party

Metro Mobile CTS, of
110 East 59th Street
New York, New York 10022

Its Representative

Henry H. Sprague, Esq.
Robinson & Cole
One Commercial Plaza
Hartford, Connecticut 06105

Party

Town of Westport
110 Myrtle Avenue
Westport, Connecticut 06880

Its Representative









Paul L. Brozdowski
Office of Town Attorney
110 Myrtle Avenue
Westport, Connecticut 06880

4052E

CERTIFICATION



The undersigned members of the Connecticut Siting Council hereby certify that they have heard this case in Docket No. 123 - An application of the Department of Public Safety, Division of State Police for a Certificate of Environmental Compatibility and Public Need for the construction, operation, and maintenance of a telecommunications tower and associated equipment in the Town of Westport, Connecticut or read the record thereof, and that we voted as follows:

Dated at New Britain, Connecticut the 26th day of March, 1990.

<u>Council Members</u>	<u>Vote Cast</u>
 Gloria Dibble Pond Chairperson	Yes
 Commissioner Peter Boucher Designee: Mark Marcus	Abstain
 Commissioner Leslie Carothers Designee: Brian Emerick	Yes
 Harry E. Covey	Yes
 Mortimer A. Gelston	Yes
 Daniel P. Lynch, Jr.	Yes
 Paulann H. Sheets	Abstain
 William H. Smith	Yes
<hr/> Colin C. Tait	Absent



ATTACHMENT 2

REV	DATE	DESCRIPTION
1	08/22/23	ISSUE FOR PERMIT
2	08/22/23	REVISIONS
3	08/22/23	REVISIONS
4	08/22/23	REVISIONS
5	08/22/23	REVISIONS
6	08/22/23	REVISIONS
7	08/22/23	REVISIONS
8	08/22/23	REVISIONS
9	08/22/23	REVISIONS



NOTE: AGL ELEVATIONS SHOWN HEREON FOR GENERAL REFERENCE ONLY. REFER TO LOCAL ANTENNA MOUNT ANALYSIS BY COLLIER ENGINEERING & DESIGN AND SHEET X-1 FOR REQUIRED EQUIPMENT MOUNTING CONFIGURATION INCLUDING VERTICAL AND HORIZONTAL MOUNTING LOCATIONS LISTED IN TABLES. COORDINATE EQUIPMENT LOCATIONS AND ANY CONFLICTS WITH COLLIER ENGINEERING & DESIGN.

SECTOR A
5' (LIE'S)
SECTOR B
55' (LIE'S)
30' (CBRS & MT6413-77A)



GROUND ELEVATION:
85.0± AMSL
(RECORD VERIZON FUZE INFO)

180' (CBRS & MT6413-77A)
SECTOR G
180' (LIE'S)

SECTOR B
SECTOR G
180' (LIE'S)

SECTOR G
280' (LIE'S)

SECTOR D
280' (LIE'S)

SECTOR C
280' (LIE'S)

SECTOR B
280' (LIE'S)

SECTOR A
280' (LIE'S)

SECTOR A
280' (LIE'S)

SECTOR A
280' (LIE'S)

SECTOR A
280' (LIE'S)

SECTOR A
280' (LIE'S)

SECTOR A
280' (LIE'S)

SECTOR A
280' (LIE'S)

SECTOR A
280' (LIE'S)

SECTOR A
280' (LIE'S)

SECTOR A
280' (LIE'S)

SECTOR A
280' (LIE'S)

SECTOR A
280' (LIE'S)

SECTOR A
280' (LIE'S)

SECTOR A
280' (LIE'S)

SECTOR A
280' (LIE'S)

SECTOR A
280' (LIE'S)

SECTOR A
280' (LIE'S)

SECTOR A
280' (LIE'S)

SECTOR A
280' (LIE'S)

SECTOR A
280' (LIE'S)

SECTOR A
280' (LIE'S)

SECTOR A
280' (LIE'S)

SECTOR A
280' (LIE'S)

SECTOR A
280' (LIE'S)

SECTOR A
280' (LIE'S)

SECTOR A
280' (LIE'S)

SECTOR A
280' (LIE'S)

SECTOR A
280' (LIE'S)

SECTOR A
280' (LIE'S)

SECTOR A
280' (LIE'S)

SECTOR A
280' (LIE'S)

SECTOR A
280' (LIE'S)

SECTOR A
280' (LIE'S)

SECTOR A
280' (LIE'S)

SECTOR A
280' (LIE'S)

SECTOR A
280' (LIE'S)

SECTOR A
280' (LIE'S)

SECTOR A
280' (LIE'S)

SECTOR A
280' (LIE'S)

SECTOR A
280' (LIE'S)

SECTOR A
280' (LIE'S)

SECTOR A
280' (LIE'S)

SECTOR A
280' (LIE'S)

SECTOR A
280' (LIE'S)

SECTOR A
280' (LIE'S)

SECTOR A
280' (LIE'S)


SECTOR A
280' (LIE'S)

SECTOR A
280' (LIE'S)


PREPARED BY: _____

REVISIONS

REV	DATE	DESCRIPTION
01	08/22/22	ISSUE FOR PERMIT
02	08/22/22	REVISED PER COMMENTS
03	08/22/22	REVISED PER COMMENTS
04	08/22/22	REVISED PER COMMENTS
05	08/22/22	REVISED PER COMMENTS
06	08/22/22	REVISED PER COMMENTS
07	08/22/22	REVISED PER COMMENTS
08	08/22/22	REVISED PER COMMENTS
09	08/22/22	REVISED PER COMMENTS
10	08/22/22	REVISED PER COMMENTS
11	08/22/22	REVISED PER COMMENTS
12	08/22/22	REVISED PER COMMENTS
13	08/22/22	REVISED PER COMMENTS
14	08/22/22	REVISED PER COMMENTS
15	08/22/22	REVISED PER COMMENTS
16	08/22/22	REVISED PER COMMENTS
17	08/22/22	REVISED PER COMMENTS
18	08/22/22	REVISED PER COMMENTS
19	08/22/22	REVISED PER COMMENTS
20	08/22/22	REVISED PER COMMENTS
21	08/22/22	REVISED PER COMMENTS
22	08/22/22	REVISED PER COMMENTS
23	08/22/22	REVISED PER COMMENTS
24	08/22/22	REVISED PER COMMENTS
25	08/22/22	REVISED PER COMMENTS
26	08/22/22	REVISED PER COMMENTS
27	08/22/22	REVISED PER COMMENTS
28	08/22/22	REVISED PER COMMENTS
29	08/22/22	REVISED PER COMMENTS
30	08/22/22	REVISED PER COMMENTS
31	08/22/22	REVISED PER COMMENTS
32	08/22/22	REVISED PER COMMENTS
33	08/22/22	REVISED PER COMMENTS
34	08/22/22	REVISED PER COMMENTS
35	08/22/22	REVISED PER COMMENTS
36	08/22/22	REVISED PER COMMENTS
37	08/22/22	REVISED PER COMMENTS
38	08/22/22	REVISED PER COMMENTS
39	08/22/22	REVISED PER COMMENTS
40	08/22/22	REVISED PER COMMENTS
41	08/22/22	REVISED PER COMMENTS
42	08/22/22	REVISED PER COMMENTS
43	08/22/22	REVISED PER COMMENTS
44	08/22/22	REVISED PER COMMENTS
45	08/22/22	REVISED PER COMMENTS
46	08/22/22	REVISED PER COMMENTS
47	08/22/22	REVISED PER COMMENTS
48	08/22/22	REVISED PER COMMENTS
49	08/22/22	REVISED PER COMMENTS
50	08/22/22	REVISED PER COMMENTS



- INSTALLATION NOTES:**
1. INSTALL ALL EQUIPMENT, MOUNTING BRACKETS, AND HARDWARE IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS.
 2. GROUND DISTRIBUTION BOXES, MOUNTING PIPES, AND RRHS IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS.
 3. INSTALL EQUIPMENT AND MOUNTING BRACKETS TO PRESERVE CLIMBING ACCESS ON TOWER.
 4. EQUIPMENT TO BE INSTALLED AT VERIZON RAD, CENTER IN ACCORDANCE WITH GLOBAL TOWER STRUCTURAL ANALYSIS AND MOUNT ANALYSIS (BY OTHERS).




MODEL	HEIGHT	WIDTH	DEPTH	WEIGHT
SAMSUNG - MT6413-77A	28.9"±	15.8"±	5.5"±	57±lbs.

(P) L-SUB6 ANTENNA DETAIL

2
D-1

SCALE: NONE



MODEL	HEIGHT	WIDTH	DEPTH	WEIGHT	MOUNT BRACKET KIT
JMA MX06FR0640-02	72.0"	19.8"	10.7"	69±lbs.	91900314-02



(P) PANEL ANTENNA DETAIL

1
D-1

SCALE: NONE

REVISIONS


REV	DATE	DESCRIPTION
1	05/28/22	ISSUE FOR PERMIT
2	06/08/22	REVISED PER COMMENTS
3	06/22/22	REVISED PER COMMENTS
4	06/22/22	REVISED PER COMMENTS
5	07/07/22	REVISED PER COMMENTS
6	07/23/22	REVISED PER COMMENTS
7	08/24/22	REVISED PER COMMENTS
8	09/26/22	REVISED PER COMMENTS
9	10/19/22	REVISED PER COMMENTS



(P) 700/850 RRH MOUNTING DETAIL

SCALE: NONE


2
D-2



(P) AWS/PCS RRH MOUNTING DETAIL

SCALE: NONE

1
D-2



(P) LARGE JUNCTION BOX MOUNTING DETAIL

SCALE: NONE

3
D-2

- INSTALLATION NOTES:**
1. INSTALL ALL EQUIPMENT, MOUNTING BRACKETS, AND HARDWARE IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS.
 2. GROUND DISTRIBUTION BOXES, MOUNTING PIPES, AND RRHs IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS.
 3. INSTALL EQUIPMENT AND MOUNTING BRACKETS TO PRESERVE CLIMBING ACCESS ON TOWER.
 4. EQUIPMENT TO BE INSTALLED AT VERIZON RAD. CENTER IN ACCORDANCE WITH GLOBAL TOWER STRUCTURAL ANALYSIS AND MOUNT ANALYSIS (BY OTHERS).


C-band 64T64R

Gen 2

SAMSUNG

Gen 2 : Higher conducted power radio with reduced size/volume/weight vs Gen 1 and also SOC embedded for flexibility to support new features

Item	Gen 2 64T64R (MT6413-77A)
Air Technology	NR n77/TDD
Frequency	3700 ~ 3980 MHz
IBW	200 MHz
OBW	200 MHz
Carrier Bandwidth	20MHz ready/40/60/80/100 MHz
# of Carriers	2 carriers
Layer	DL : 16L, UL : 16RX (8L)
RF Chain	64T64R
Antenna Configuration	4V16H with 192 AE
EIRP	80.5 dBm @320W (55 dBm + 25.5 dB)
Conductive Power	320W
Spectrum Analyzer	TX/RX support
RX Sensitivity	Typical -97.8dBm @(1Rx, 18.36MHz with 30kHz,51RBs)
Modulation	DL 256QAM support, (DL 1024QAM with 1~2dB power back-off)
Function Split	DL/UL option 7-2x
Input Power	-48 VDC (-38 VDC to -57 VDC)
Power Consumption	1,287W (100% load, room temp.)
Size (WHD)	400 x 734 x 140 mm (15.75 x 28.90 x 5.51 inch)
Volume	41.1L
Weight	26kg (57.3 lb)
Operating Temperature	-40°C - 55°C (w/o solar load)
Cooling	Natural convection 3GPP 38 104
Unwanted Emission	FCC 47 CFR 27.53 : < -13dBm/MHz < -40 dBm/MHz @ above 4 GHz < -50 dBm /MHz @ 4.040 ~ 4.050 MHz < -60 dBm /MHz @ above 4.050 MHz
Optic Interface	15km, 4 ports (25Gbps x 4), SFP28, single mode, Bi-di (Option: Duplex)
Mounting Options	Pole, wall
NB-IoT	Nat support
External Alarm	4RX
Fronthaul Interface	eCPRI



* Preliminary Design: External appearance and mechanical design can be subject to change


Gen 2. 64T64R C-band MMU Dimensions	
Size (WxHxD)	400 x 734 x 140 mm (15.75 x 28.90 x 5.51 inch)
Weight	26kg (57.3 lb)

MX06FRO640-02

NWAV™ X-Pol Antenna | Hex-Port | 6 ft | 40°

X-Pol, Hex-Port 6 ft 40° Fast Roll-Off with Smart Bias-T (2) 698–894 MHz & (4) 1695–2180 MHz

- Fast Roll-Off (FRO™) Azimuth beam pattern improves Intra- and Inter-cell SINR
- Excellent Passive Intermodulation (PIM) performance reduces harmful interference
- Fully integrated (iRETs) with *independent* RET control for low and high bands for ease of network optimization
- SON-Ready array spacing supports beamforming capabilities
- Suitable for LTE/CDMA/PCS/UMTS/GSM air interface technologies
- Integrated Smart BIAS-Ts reduces leasing costs



Electrical specification (minimum/ maximum)	Ports 1,2		Ports 3,4,5,6		
	698–798	824–894	1695–1880	1850–1990	1920–2180
Frequency bands, MHz	698–798	824–894	1695–1880	1850–1990	1920–2180
Polarization	± 45°		± 45°		
Average gain over all tilts, dBi	16.3	17.2	19.3	20.1	20.4
Horizontal beamwidth (HBW), degrees ¹	42°	37°	40°	39°	37°
Front-to-back ratio, co-polar power @180° ± 30°, dB	>25.0	>25.0	>28.0	>28.0	>28.0
X-Pol discrimination (CPR) at boresight, dB	>18.0	>15.0	>18	>18	>15
Sector power ratio, percent	<4.5	<3.5	<3.7	<3.8	<3.6
Vertical beamwidth, (VBW), degrees ¹	13.1°	11.8°	6.0°	5.7°	5.3°
Electrical downtilt (EDT) range, degrees	2-14	2-14	0-9		
First upper side lobe (USLS) suppression, dB ¹	≤ -15.0	≤ -15.0	≤ -16.0	≤ -16.0	≤ -16.0
Minimum cross polar isolation, port-to-port, dB	25	25	25	25	25
Maximum VSWR/ return loss, dB	1.5/ -14.0	1.5/ -14.0	1.5/ -14.0	1.5/ -14.0	1.5/ -14.0
Maximum passive Intermodulation (PIM), 2x 20W carrier, dBc	-153	-153	-153		
Maximum input power per any port, watts	300		250		
Total composite power all ports, watts			1500		


¹ Typical value over frequency and tilt

MX06FRO640-02

NWAV™ X-Pol Antenna | Hex-Port | 6 ft | 40°



Mechanical specifications	
Dimensions height/ width/ depth, inches (mm)	72/ 19.8/ 10.7 (1829/504/271)
Shipping dimensions length/ width/ height, inches (mm)	84/ 26/ 15 (2134/ 660/ 381)
No. of RF input ports, connector type & location	6 x 4.3-10 female, bottom
RF connector torque	96 lbf-in (10.85 N-m or 8 lbf-ft)
Net antenna weight, lb (kg)	70 (31.8)
Shipping weight, lb (kg)	100 (45.4)
Antenna mounting and downtilt kit included with antenna	91900318
Net weight of the mounting and downtilt kit, lb (kg)	18 (8.2)
Range of mechanical up/ down tilt	-2° to 14°
Rated wind survival speed, mph (km/h)	150 (241)
Frontal, lateral & rear wind loading @ 150 km/h, lbf (N)	263 (1170), 112 (498), 263 (1170)
Equivalent flat plate @100 mph and Cd=2, sq ft	6.03



Ordering information	
Antenna model	Description
MX06FRO640-02	6F X- Pol HEX FRO 40° 2-14°/ 0-9° RET, 4.3-10 & SBT
Optional accessories	
992100-CA030-SC	Optional AISG jumper cable, M/F, 3.0 meters
PCU-1000	Primary control unit, USB

MX06FRO640-02

NWAV™ X-Pol Antenna | Hex-Port | 6 ft | 40°

Remote Electrical Tilt (RET 1000) information	
RET location	Integrated into antenna
RET interface connector type	8-pin AISG connector per IEC 60130-9
RET interface connector quantity	2 pairs of AISG male/ female connectors
RET interface connector location	Bottom of the antenna
Total No. of internal RETs low bands	1
Total No. of internal RETs high bands	1
RET input operating voltage, vdc	10–30
RET max. power consumption, idle state, W	≤ 2.0
RET max. power consumption, normal operating conditions, W	≤ 13.0
RET communication protocol	AISG 2.0/ 3GPP

RET & RF connector topology

Each RET device can be controlled either via the designated external AISG connector or RF port as shown below

RET Device	Band	RF Port
1	698–894	1–2

RET Device	Band	RF Port
2	1695–2180	3–6

Array topology

3 sets of radiating arrays

R1: 698–894 MHz
 B1: 1695–2180 MHz
 B2: 1695–2180 MHz

Band	RF Port
1695–2180	3–4
698–894	1–2
1695–2180	5–6

SAMSUNG

AWS/PCS MACRO RADIO

DUAL-BAND AND HIGH POWER
FOR MACRO COVERAGE

Samsung's future proof dual-band radio is designed to help effectively increase the coverage areas in wireless networks. This AWS/PCS 4T4R dual-band radio has 4Tx/4Rx to 2Tx/2Rx RF chains options and a total output power of 320W, making it ideal for macro sites.

Model Code RF4439d-25A



Homepage
samsungnetworks.com




Youtube
www.youtube.com/samsung5g

Points of Differentiation

Continuous Migration


Samsung's AWS/PCS macro radio can support each incumbent CPRI interface as well as advanced eCPRI interfaces. This feature provides installable options for both legacy LTE networks and added NR networks.



O-RAN Compliant

A standardized O-RAN radio can help in implementing cost-effective networks, which are capable of sending more data without compromising additional investments.


Samsung's state-of-the-art O-RAN technology will help accelerate the effort toward constructing a solid O-RAN ecosystem.



Optimum Spectrum Utilization

The number of required carriers varies according to site (region). Supporting many carriers is essential for using all frequencies that the operator has available.

The new AWS/PCS dual-band radio can support up to 3 carriers in the PCS (1.9GHz) band and 4 carriers in the AWS (2.1GHz) band, respectively.



Brand New Features in a Compact Size

Samsung's AWS/PCS macro radio offers several features, such as dual connectivity for baseband for both CDU and vDU, O-RAN capability, more carriers and an enlarged PCS spectrum, combined into an incumbent radio volume of 36.8L.



- 2 FH connectivity
- O-RAN capability
- More carriers and spectrum

Same as an Incumbent radio volume

Technical Specifications

Item	Specification
Tech	LTE / NR
Brand	B25(PCS), B66(AWS)
Frequency Band	DL: 1930 – 1995MHz, UL: 1850 – 1915MHz DL: 2110 – 2200MHz, UL: 1710 – 1780MHz
RF Power	(B25) 4 × 40W or 2 × 60W (B66) 4 × 60W or 2 × 80W
IBW/OBW	(B25) 65MHz / 30MHz (B66) DL 90MHz, UL 70MHz / 60MHz
Installation	Pole, Wall
Size/Weight	14.96 x 14.96 x 10.04inch (36.8L) / 74.7lb

700/850 4T4R Macro 320W ORU - New Filter (RF4461d-13A)

SAMSUNG

Specifications

Item	Specification
Air Interface	LTE_MR(HW resource ready)
Band	Band13 (700MHz) Band5 (850MHz)
Frequency	DL: 746~756MHz UL: 869~894MHz
IBW	UL: 777~787MHz 25MHz
OBW	25MHz
Carrier Bandwidth	LTE/NR 5*10MHz
# of carriers	2C+
Total # of carriers	4C + B13 (5DL) 1C
RF Chain	4T4R/2T4R/2T2R/1T2R 2T2R~2T2R bi-sector Total: 320W
RF Output Power	4 x 40W or 2 x 60W
Spectrum Analyzer	TX/RX Support
RX Sensitivity	Typ. -104.5dBm @1Rx (25RBs 5MHz)
Modulation	256QAM support, (1024QAM with 1~2dB power back-off)
Input Power	-48VDC (-38VDC to -57VDC)
Power Consumption	1.165 Watt @ 100% RF load, room temperature
Size (WHD)	380 x 380 x 260 mm (14.96 x 14.96 x 10.23 inch)
Volume	37.5 L
Weight (W/o Solar Shield & finger guard)	35.9 kg (79.1 lb)
Operating Temperature	-40°C (-40°F) ~ 55°C (131°F) (Without solar load)
Cooling	Natural convection
Unwanted Emission	3GPP 36.104 FCC 47 CFR 27.53 c, f)
CPR1 Cascade	3GPP 36.104 FCC 47 CFR 22.917
Optic Interface	Not supported
RET & TMA Interface	-69 dBm/100 kHz per path @ 896 ~901MHz
Bias-T	AISG 3.0
Mounting Options	4 ports (2 ports per band)
NB-IoT	Pole, wall
PIM Cancellation	Support
# of antenna port	25A~2GB or 2GB~2IB or 4GB
External Alarm	Support
Fronthaul Interface	4
CPR1 compression	Opt. 8 CPR1 / Opt. 7-2x selectable (not simultaneous support) Not Support



* 5MHz supporting in B13(700MHz) depends on 3GPP std. and UE capability.
External filters in interferer and victim sides for Mexican boarder to support 5MHz service need to be considered
** Finger guard is not needed.

ATTACHMENT 3



C Squared Systems, LLC
65 Dartmouth Drive
Auburn, NH 03032
(603) 644-2800
support@csquaredsystems.com

Calculated Radio Frequency Emissions Report

verizon[✓]

Westport

880 Post Road East Unit 1, Westport, CT

June 21, 2024

Table of Contents

1. Introduction	1
2. FCC Guidelines for Evaluating RF Radiation Exposure Limits.....	1
3. RF Exposure Prediction Methods.....	2
4. Antenna Inventory.....	3
5. Calculation Results.....	4
6. Conclusion.....	6
7. Statement of Certification.....	6
Attachment A: References	7
Attachment B: FCC Limits for Maximum Permissible Exposure (MPE).....	8
Attachment C: Verizon Antenna Model Data Sheets and Electrical Patterns	10

List of Figures

Figure 1: Graph of General Population % MPE vs. Distance	4
Figure 2: Graph of FCC Limits for Maximum Permissible Exposure (MPE).....	9

List of Tables

Table 1: Proposed Antenna Inventory	3
Table 2: Maximum Percent of General Population Exposure Values	5
Table 3: FCC Limits for Maximum Permissible Exposure	8

1. Introduction

The purpose of this report is to investigate compliance with applicable FCC regulations for the proposed modification of Verizon's antenna arrays mounted at 160' on a transmission tower located at 880 Post Road East Unit 1 in Westport, CT. The coordinates of the tower are 41° 08' 14.91" N, 73° 20' 3.7" W.

Verizon is proposing the following:

- 1) Install fourteen (14) multi-band antennas to support its commercial LTE and 5G network.

This report considers the planned antenna configuration for Verizon¹ as well as existing antenna configuration for AT&T², DISH³, T-Mobile⁴, D&K and CSP⁵ to derive the resulting % MPE of its proposed modification.

2. FCC Guidelines for Evaluating RF Radiation Exposure Limits

In 1985, the FCC established rules to regulate radio frequency (RF) exposure from FCC licensed antenna facilities. In 1996, the FCC updated these rules, which were further amended in August 1997 by OET Bulletin 65 Edition 97-01. These new rules include Maximum Permissible Exposure (MPE) limits for transmitters operating between 300 kHz and 100 GHz. The FCC MPE limits are based upon those recommended by the National Council on Radiation Protection and Measurements (NCRP), developed by the Institute of Electrical and Electronics Engineers, Inc., (IEEE) and adopted by the American National Standards Institute (ANSI).

The FCC general population/uncontrolled limits set the maximum exposure to which most people may be subjected. General population/uncontrolled exposures apply in situations in which the general public may be exposed, or in which persons that are exposed as a consequence of their employment may not be fully aware of the potential for exposure or cannot exercise control over their exposure.

Public exposure to radio frequencies is regulated and enforced in units of milliwatts per square centimeter (mW/cm²). The general population exposure limits for the various frequency ranges are defined in the attached "FCC Limits for Maximum Permissible Exposure (MPE)" in Attachment C of this report.

Higher exposure limits are permitted under the occupational/controlled exposure category, but only for persons who are exposed as a consequence of their employment and who have been made fully aware of the potential for exposure, and they must be able to exercise control over their exposure. General population/uncontrolled limits are five times more stringent than the levels that are acceptable for occupational, or radio frequency trained individuals. Attachment C contains excerpts from OET Bulletin 65 and defines the Maximum Exposure Limit.

Finally, it should be noted that the MPE limits adopted by the FCC for both general population/uncontrolled exposure and for occupational/controlled exposure incorporate a substantial margin of safety and have been established to be well below levels generally accepted as having the potential to cause adverse health effects.

¹ As referenced to Verizon's Radio Frequency Design Sheet updated 11/08/2023.

² As referenced to AT&T's Connecticut Siting Council Notice of Exempt Modification – 880 Post Road East, Westport, Connecticut, dated 02/17/2023

³ As referenced to DISH's Connecticut Siting Council Tower Share Application – 880 Post Road East, Westport, Connecticut, dated 01/19/2023

⁴ As referenced to AT&T's Connecticut Siting Council Notice of Exempt Modification – 880 Post Road East, Westport, Connecticut, dated 02/17/2023

⁵ As referenced to AT&T's Connecticut Siting Council Notice of Exempt Modification – 880 Post Road East, Westport, Connecticut, dated 02/17/2023

3. RF Exposure Prediction Methods

The emission field calculation results displayed in the following figures were generated using the following formula as outlined in FCC bulletin OET 65:

$$\text{Power Density} = \left(\frac{\text{GRF}^2 \times 1.64 \times \text{ERP}}{4\pi \times R^2} \right) \times \text{Off Beam Loss}$$

Where:

EIRP = Effective Isotropic Radiated Power

R = Radial Distance = $\sqrt{(H^2 + V^2)}$

H = Horizontal Distance from antenna in meters

V = Vertical Distance from radiation center of antenna in meters

Off Beam Loss is determined by the selected antenna patterns

Ground reflection factor (GRF) of 1.6

These calculations assume that the antennas are operating at 100 percent capacity, that all antenna channels are transmitting simultaneously, and that the radio transmitters are operating at full power. Obstructions (trees, buildings, etc.) that would normally attenuate the signal are not taken into account. The calculations assume even terrain in the area of study and do not take into account actual terrain elevations which could attenuate the signal. As a result, the predicted signal levels reported below are much higher than the actual signal levels will be from the final installations.

4. Antenna Inventory

Table 1 below outlines Verizon’s proposed antenna configuration for the site. The associated data sheets and antenna patterns for these specific antenna models are included in Attachments C.

Operator	Sector / Azimuth	TX Freq (MHz)	Power at Antenna (Watts)	Ant Gain (dBi)	Power EIRP (Watts)	Antenna Model	Beam Width	Mech. Tilt	Length (ft)	Antenna Centerline Height (ft)
Verizon	Alpha / 5°	700	160	16.3	6825	MX06FRO640-02	42	0	6	160
		850	160	17.2	8397		37			
		1900	160	20.1	16373		39			
		2100	240	20.4	26315		37			
	Alpha / 30°	3500	20	12.5	356	XXDWMM-12.5-65	65	0	2.46	160
		3700	320	25.5	113540	MT6413-77A	-			
	Alpha / 55°	700	160	16.3	6825	MX06FRO640-02	42	0	6	160
		850	160	17.2	8397		37			
		1900	160	20.1	16373		39			
		2100	240	20.4	26315		37			
	Beta / 180°	700	160	14.5	4509	JAHH-65B-R3B	67	0	6	160
		850	160	15.8	6083		65			
		1900	160	18.4	11069		63			
		2100	240	18.5	16991		65			
		3500	20	12.5	356	XXDWMM-12.5-65	65	0	1	160
		3700	320	25.5	113540	MT6413-77A	-	0	2.46	160
	Gamma / 280°	700	160	14.5	4509	JAHH-65B-R3B	67	0	6	160
		850	160	15.8	6083		65			
		1900	160	18.4	11069		63			
		2100	240	18.5	16991		65			
3500		20	12.5	356	XXDWMM-12.5-65	65	0	2.46	160	
3700		320	25.5	113540	MT6413-77A	-				

Table 1: Proposed Antenna Inventory^{6 7}

⁶ Antenna heights are in reference to Verizon’s Radio Frequency Design Sheet updated 11/08/2023.

⁷ Transmit power assumes 0 dB of cable loss.

5. Calculation Results

The calculated power density results are shown in Figure 1 below. For completeness, the calculations for this analysis range from 0 feet horizontal distance (directly below the antennas) to a value of 3,000 feet horizontal distance from the site. In addition to the other worst-case scenario considerations that were previously mentioned, the power density calculations to each horizontal distance point away from the antennas was completed using a local maximum off beam antenna gain (within ± 5 degrees of the true mathematical angle) to incorporate a realistic worst-case scenario.




Figure 1: Graph of General Population % MPE vs. Distance

The highest percent of MPE (12.83% of the General Population limit) is calculated to occur at a horizontal distance of 606 feet from antennas. Please note that the percent of MPE calculations close to the site take into account off beam loss, which is determined from the vertical pattern of the antennas used. Therefore, RF power density levels may increase as the distance from the site increases. At distances of approximately 1500 feet and beyond, one would now be in the main beam of the antenna pattern and off beam loss is no longer considered. Beyond this point, RF levels become calculated solely on distance from the site and the percent of MPE decreases significantly as distance from the site increases.

Table 2 below lists percent of MPE values as well as the associated parameters that were included in the calculations. The highest percent of MPE value was calculated to occur at a horizontal distance of 606 feet from the site (reference Figure 1).

As stated in Section 3, all calculations assume that the antennas are operating at 100 percent capacity, that all antenna channels are transmitting simultaneously, and that the radio transmitters are operating at full power. Obstructions (trees, buildings etc.) that would normally attenuate the signal are not taken into account. In addition, a six foot height offset was considered in this analysis to account for average human height. As a result, the predicted signal levels are significantly higher than the actual signal levels will be from the final configuration. The results presented in Figure 1 and Table 2 assume level ground elevation from the base of the tower out to the horizontal distances calculated.

Carrier	Number of Transmitters	Power out of Base Station Per Transmitter (Watts)	Antenna Height (Feet)	Distance to the Base of Antennas (Feet)	Power Density (mW/cm ²)	Limit (mW/cm ²)	% MPE
AT&T 5G 3450 MHz	1	108.8	134.8	606	0.020681	1.000	2.07%
AT&T 5G 3840 MHz	1	108.4	134.8	606	0.019059	1.000	1.91%
AT&T 5G 850 MHz	1	120.0	133.0	606	0.000920	0.567	0.16%
AT&T LTE 2300 MHz	1	75.0	133.0	606	0.000480	1.000	0.05%
AT&T LTE 700 MHz	1	120.0	133.0	606	0.001114	0.467	0.24%
AT&T LTE 700 MHz	1	120.0	133.0	606	0.001162	0.467	0.25%
AT&T LTE 700 MHz	1	60.0	133.0	606	0.000551	0.467	0.12%
AT&T LTE/5G 1900 MHz	1	120.0	133.0	606	0.000653	1.000	0.07%
AT&T LTE/5G 2100 MHz	1	120.0	133.0	606	0.000892	1.000	0.09%
CSP	1	100.0	169.0	606	0.000097	0.300	0.03%
CSP	1	100.0	113.0	606	0.000161	0.200	0.08%
CSP-22	1	100.0	181.0	606	0.000066	0.300	0.02%
CSP-47	1	160.0	170.0	606	0.000089	0.567	0.02%
D&K-51 CSP-1	1	100.0	187.0	606	0.000053	0.300	0.02%
D&K-52 CSP-42	1	1.0	177.0	606	0.000000	1.000	0.00%
DISH 5G 2000 MHz	1	160.0	144.0	606	0.000266	1.000	0.03%
DISH 5G 2100 MHz	1	160.0	144.0	606	0.000239	1.000	0.02%
DISH 5G 600 MHz	1	120.0	144.0	606	0.000953	0.400	0.24%
T-Mobile GSM 1900 MHz	1	120.0	125.0	606	0.001511	1.000	0.15%
T-Mobile LTE 1900 MHz	1	120.0	125.0	606	0.001511	1.000	0.15%
T-Mobile LTE 2100 MHz	1	120.0	125.0	606	0.001064	1.000	0.11%
T-Mobile LTE 2500 MHz	1	240.0	125.0	606	0.000210	1.000	0.02%
T-Mobile LTE 600 MHz	1	120.0	125.0	606	0.001286	0.400	0.32%
T-Mobile LTE 700 MHz	1	120.0	125.0	606	0.001106	0.467	0.24%
T-Mobile UMTS 1900 MHz	1	60.0	125.0	606	0.000755	1.000	0.08%
Verizon 5G 3500 MHz	1	20.0	160.0	606	0.000202	1.000	0.02%
Verizon 5G 3700 MHz	1	320.0	160.0	606	0.057690	1.000	5.77%
Verizon LTE 1900 MHz	1	160.0	160.0	606	0.000234	1.000	0.02%
Verizon LTE 2100 MHz	1	240.0	160.0	606	0.000364	1.000	0.04%
Verizon LTE 750 MHz	1	160.0	160.0	606	0.001256	0.500	0.25%
Verizon LTE 850 MHz	1	160.0	160.0	606	0.001482	0.567	0.26%
						Total	12.83%

Table 2: Maximum Percent of General Population Exposure Values^{8,9,10,11}

⁸ Frequencies listed are representative of the operating band and are not the specific operating frequency.

⁹ The total % MPE listed is a summation of each unrounded contribution. Therefore, summing each rounded value may not reflect the total value listed in the table.

¹⁰ In the case where antenna pattern data was unavailable from the manufacturer, generic antenna pattern was used based on the frequency, bandwidth and gain of the antenna.

¹¹ Reasonable assumptions for the frequency and power were used in the calculation for absolute worst case %MPE for CSP and D&K.

6. Conclusion

The above analysis verifies that RF exposure levels from the site with Verizon’s proposed antenna configuration will be well below the maximum permissible levels as outlined by the FCC in the OET Bulletin 65 Ed. 97-01. Using the conservative calculation methods and parameters detailed above, the maximum cumulative percent of MPE in consideration of all transmitters is calculated to be **12.83%** of the FCC limit (General Population/Uncontrolled). This maximum cumulative percent of MPE value is calculated to occur 606 feet away from the site.


7. Statement of Certification

I certify to the best of my knowledge that the statements in this report are true and accurate. The calculations follow guidelines set forth in ANSI/IEEE Std. C95.3, ANSI/IEEE Std. C95.1 and FCC OET Bulletin 65 Edition 97-01.



Report Prepared By: Ram Acharya
RF Engineer
C Squared Systems, LLC

June 20, 2024
Date



Reviewed/Approved By: Martin Lavin
Senior RF Engineer
C Squared Systems, LLC

June 21, 2024
Date

Attachment A: References

OET Bulletin 65 - Edition 97-01 - August 1997 Federal Communications Commission Office of Engineering & Technology

IEEE C95.1-2019, IEEE Standard Safety Levels With Respect to Human Exposure to Electric, Magnetic, and Electromagnetic Fields, 0 Hz to 300 GHz IEEE-SA Standards Board

IEEE C95.3-2021, IEEE Recommended Practice for Measurements and Computations of Electric, Magnetic, and Electromagnetic Fields with Respect to Human Exposure to Such Fields, 0 Hz-300 GHz IEEE-SA Standards Board

Attachment B: FCC Limits for Maximum Permissible Exposure (MPE)

(A) Limits for Occupational/Controlled Exposure¹²

Frequency Range (MHz)	Electric Field Strength (E) (V/m)	Magnetic Field Strength (E) (A/m)	Power Density (S) (mW/cm ²)	Averaging Time E ² , H ² or S (minutes)
0.3-3.0	614	1.63	(100)*	6
3.0-30	1842/f	4.89/f	(900/f ²)*	6
30-300	61.4	0.163	1.0	6
300-1500	-	-	f/300	6
1500-100,000	-	-	5	6

(B) Limits for General Population/Uncontrolled Exposure¹³

Frequency Range (MHz)	Electric Field Strength (E) (V/m)	Magnetic Field Strength (E) (A/m)	Power Density (S) (mW/cm ²)	Averaging Time E ² , H ² or S (minutes)
0.3-1.34	614	1.63	(100)*	30
1.34-30	824/f	2.19/f	(180/f ²)*	30
30-300	27.5	0.073	0.2	30
300-1500	-	-	f/1500	30
1500-100,000	-	-	1.0	30

f = frequency in MHz * Plane-wave equivalent power density

Table 3: FCC Limits for Maximum Permissible Exposure

¹² Occupational/controlled limits apply in situations in which persons are exposed as a consequence of their employment provided those persons are fully aware of the potential for exposure and can exercise control over their exposure. Limits for occupational/controlled exposure also apply in situations when an individual is transient through a location where occupational/controlled limits apply provided he or she is made aware of the potential for exposure.

¹³ General population/uncontrolled exposures apply in situations in which the general public may be exposed, or in which persons that are exposed as a consequence of their employment may not be fully aware of the potential for exposure or cannot exercise control over their exposure.








Figure 2: Graph of FCC Limits for Maximum Permissible Exposure (MPE)

Attachment C: Verizon Antenna Model Data Sheets and Electrical Patterns

<p>750 MHz</p> <p>Manufacturer: COMMSCOPE Model #: JAHH-65B-R3B Frequency Band: 698-787 MHz Gain: 14.5 dBi Vertical Beamwidth: 12.1° Horizontal Beamwidth: 67° Polarization: ±45° Dimensions (L x W x D): 71.9" x 13.78" x 8.2"</p>	 <p>A polar plot radiation pattern for 750 MHz. The plot shows a main lobe centered at 0 degrees, extending to approximately 30 degrees on both sides. There are several smaller side lobes and nulls. The plot is marked with angles from -180 to 180 degrees in 30-degree increments.</p>
<p>850 MHz</p> <p>Manufacturer: COMMSCOPE Model #: JAHH-65B-R3B Frequency Band: 806-894 MHz Gain: 15.8 dBi Vertical Beamwidth: 10.5° Horizontal Beamwidth: 65° Polarization: ±45° Dimensions (L x W x D): 71.9" x 13.78" x 8.2"</p>	 <p>A polar plot radiation pattern for 850 MHz. The plot shows a main lobe centered at 0 degrees, extending to approximately 30 degrees on both sides. There are several smaller side lobes and nulls. The plot is marked with angles from -180 to 180 degrees in 30-degree increments.</p>

<p>1900 MHz</p> <p>Manufacturer: COMMSCOPE Model #: JAHH-65B-R3B Frequency Band: 1850-1990 MHz Gain: 18.4 dBi Vertical Beamwidth: 5.2° Horizontal Beamwidth: 63° Polarization: ±45° Dimensions (L x W x D): 71.9" x 13.78" x 8.2"</p>	
<p>2100 MHz</p> <p>Manufacturer: COMMSCOPE Model #: JAHH-65B-R3B Frequency Band: 1920-2200 MHz Gain: 18.5 dBi Vertical Beamwidth: 5.5° Horizontal Beamwidth: 65° Polarization: ±45° Dimensions (L x W x D): 71.9" x 13.78" x 8.2"</p>	

ATTACHMENT 4

Structural Analysis Report

180' Existing Lattice Tower

Verizon Antenna Upgrade

CSP Tower Ref: #32

*880 Post Road East
Westport, CT*

CEN TEK Project No. 22027.01

~~Date: April 5, 2022~~

Rev 6: June 11, 2024

Max Stress Ratio = 94%



Prepared for:
Verizon Wireless
20 Alexander Drive
Wallingford, CT 06492

Table of Contents

SECTION 1 - REPORT

- INTRODUCTION
- ANTENNA AND APPURTENANCE SUMMARY
- PRIMARY ASSUMPTIONS USED IN THE ANALYSIS
- ANALYSIS
- TOWER LOADING
- TOWER CAPACITY
- FOUNDATION AND ANCHORS
- CONCLUSION

SECTION 2 – CONDITIONS & SOFTWARE

- STANDARD ENGINEERING CONDITIONS
- GENERAL DESCRIPTION OF STRUCTURAL ANALYSIS PROGRAM

SECTION 3 – CALCULATIONS

- tnxTower INPUT/OUTPUT SUMMARY
- tnxTower FEED LINE PLAN
- tnxTower FEED LINE DISTRIBUTION
- tnxTower DETAILED OUTPUT
- tnxTower INPUT/OUTPUT SUMMARY (REV.F FOR TWIST AND SWAY)
- tnxTower DETAILED OUTPUT (REV.F FOR TWIST AND SWAY)
- ANCHOR BOLT ANALYSIS
- FOUNDATION ANALYSIS

Introduction

The purpose of this report is to summarize the results of the non-linear, P- Δ structural analysis of the antenna upgrade by Verizon on the existing lattice tower located in Westport, Connecticut.

The host tower is a 180-ft, three legged, lattice tower originally designed and manufactured by Rohn Industries. File no. 26263DL dated February 1, 1991. The tower geometry, structure member sizes and foundation information were taken from a previous structural analysis report prepared by Centek job no. 22089.02 dated May 1, 2023. The tower has been previously reinforced. All previous reinforcements are assumed to be installed. See Primary Assumptions Section below for detailed reinforcement reference reports.

Antenna and appurtenance inventory was taken from the aforementioned structural analysis and information provided by Verizon.

The tower consists of nine (9) vertical sections consisting of steel pipe legs conforming to ASTM A572-50 and steel pipe lateral bracing. The vertical tower sections are connected by bolted flange plates with the diagonal and horizontal bracing to pipe legs consisting of bolted connections. The width of the tower face is 8.5-ft at the top and 27.7-ft at the bottom.

Antenna and Appurtenance Summary

The existing and proposed loads considered in the analysis consist of the following:

Antenna Type	Carrier	Mount	Antenna Centerline Elevation	Cable
(1) Telewave ANT490Y10-WR Yagi	D&K-51 CSP-1 (existing)	Leg Mounted	187'	(1) LDF5-50A
(1) Telewave ANT490Y10-WR Yagi	CSP-22 (existing)	Leg Mounted	181'	(1) LDF5-50A
(1) Celwave PA6-65 Dish	D&K-52 CSP-42 (existing)	Pipe Mounted to tower Leg	177'	(1) EW-63
(3) RFI BPA7496-180-14 Panel Antennas (1) Bird TTA unit	CSP-47,80-82 (existing)	(1) USF12-396 Sector Frame	170'	(3) AVA7-50A (1) LDF4-50A
(1) 3-ft Yagi	CSP (existing)	Pipe Mounted to tower Leg	169'	(1) LDF5-50A
(2) BXA-70063-4CF (1) BXA-70080-4CF (2) JAHH-65B-R3B (2) B5/B13 RRHs (1) CBC78T-DS-43	VZW (existing to remove)	See Below Mount	160'	(6) 1 5/8" Coax Cables

CEN TEK Engineering, Inc.
Structural Analysis - 180-ft Lattice Tower #32 Westport
Antenna Upgrade – Verizon
Westport, CT
Rev 6 ~ June 11, 2024

Antenna Type	Carrier	Mount	Antenna Centerline Elevation	Cable
(4) MX06FRO640-02 (3) MT6413-77A (1) 4439d-25A RRH (3) 4461d-13A RRH (1) OVP Unit	VZW (Proposed)	See Below Mount	160'	(1) 12x24 Hybrid Cable
(4) JAHH-65B-R3B (3) XXDWMM-12.5-65-8T (3) B2/B66A RRHs (1) B5/B13 RRHs (3) RT4401-48A RRHs (2) CBC78T-DS-43 (1) OVP Units	VZW (existing to remain)	(3) 15-ft Gate Booms	160'	(1) 12x24 Hybrid Cable
(3) FFVV-65B-R2 (3) TA08025-B605 (3) TA08025-B604 (3) RD1DC-9181-PF-48	Dish (Reserved)	Commscope MTC3975083	144'	(3) 12x24 Hybrid Cable
(3) QD6616-7 (3) DMP65R-BU6DA (3) AIR6419 (3) AIR6449 (3) 4478 B14 RRH Units (3) 4449 B5/12 RRH Units (9) RRUS-32 RRH Units (2) DC6-48-60-18-8F (1) DC9	AT&T (existing)	(3) 14-ft V Frames (p/n VFA14-H10- 2120)	133'	(6) 1 1/4" Coax Cables (3) Fiber Cables (7) DC Cables
(6) Ericsson AIR21 (3) Andrew LNX-6515DS (3) RRUS-11 (3) TMAs	T-Mobile (existing)	(3) 12-ft T-Frames	125'	(18) 1 5/8" Coax Cables (1) 6x12 Hybrid Cables
(1) Telewave ANT150D Dipole	CSP (existing)	Pipe Mounted to tower Leg	113'	(1) LDF4-50A
(1) GPS Antenna	D&K-1 CSP-43 (existing)	Leg Mounted	61'	(1) LDF4-50A

Primary Assumptions Used in the Analysis

- The tower structure's theoretical capacity not including any assessment of the condition of the tower.
- The tower carries the horizontal and vertical loads due to the weight of antennas, ice load and wind.
- Tower is properly installed and maintained.
- Tower is in plumb condition.
- Tower loading for antennas and mounts as listed in this report.
- All bolts are appropriately tightened providing the necessary connection continuity.
- All welds are fabricated with ER-70S-6 electrodes.
- All members are assumed to be as specified in the original tower design documents.
- All members are "hot dipped" galvanized in accordance with ASTM A123 and ASTM A153 Standards.
- All member protective coatings are in good condition.
- All tower members were properly designed, detailed, fabricated, installed and have been properly maintained since erection.
- Any deviation from the analyzed antenna loading will require a new analysis for verification of structural adequacy.
- All coax cables should be routed as specified in section 3 of this report.
- **All previous reinforcements per the below listed structural analysis and modification reports are assumed to be installed.**
 - **Structural report prepared by AECOM Corp for AT&T project no. SMK-004 / 60581632 dated 7/13/18.**
 - **Structural report prepared by AECOM Corp for Verizon project no. VZ5-224 / 60620140 dated 7/10/20.**
- **The Verizon antenna mount information was taken from the mount analysis report and modification drawings prepared by Maser Consulting job no. 21777772 dated November 20, 2023**

A n a l y s i s

The existing tower was analyzed using a comprehensive computer program entitled tnxTower. The program analyzes the tower, considering the worst case loading condition. The tower is considered as loaded by concentric forces along the tower, and the model assumes that the tower members are subjected to bending, axial, and shear forces.

The existing tower was analyzed for the controlling basic wind speed with no ice and the applicable wind and ice combination to determine stresses in members as per guidelines of TIA-222-H entitled “Structural Standard for Antenna Support Structures, Antennas and Small Wind Turbine Support Structures”, the American Institute of Steel Construction (AISC) and the Manual of Steel Construction; Load and Resistance Factor Design (LRFD).

The controlling wind speed is determined by evaluating the local available wind speed data as provided in Appendix P of the CSBC¹ and the wind speed data available in the TIA-222-H Standard.

T o w e r L o a d i n g

Tower loading was determined by the basic wind speed as applied to projected surface areas with modification factors per TIA-222-H, gravity loads of the tower structure and its components, and the application of 1.0” radial ice on the tower structure and its components.

Load Cases:	<u>Load Case 1</u> ; 130 mph (Risk Cat III) wind speed w/ no ice plus gravity load – used in calculation of tower stresses and rotation.	<i>[Appendix P of the 2022 CT Building Code]</i>
	<u>Load Case 2</u> ; 50 mph wind speed w/ 1.00” radial ice plus gravity load – used in calculation of tower stresses.	<i>[Annex B of TIA-222-H]</i>
	<u>Load Case 3</u> ; 90 mph wind speed w/ 0.5” radial ice plus gravity load – used in calculation of tower twist and sway.	<i>[TIA-222-F used for calculation of tower twist and sway per the requirements of the CSP]</i>

¹ The 2021 International Building Code as amended by the 2022 Connecticut State Building Code (CSBC).

Tower Capacity

- Calculated stresses **were found to be within allowable limits.**

Tower Section	Elevation	Stress Ratio (percentage of capacity)	Result
Leg (T12)	20.0' - 30.0'	62.6%	PASS
Diagonal (T12)	20.0' - 30.0'	93.8%	PASS
Horizontal (T11)	30.0' - 40.0'	87.0%	PASS

- The tower combined deflection **was found to be within allowable limits.**

Deflection Criteria	Proposed (degrees)	Allowable (degrees)	Result
Sway (Tilt)	0.4384	n/a	n/a
Twist	0.2765	n/a	n/a
Combined	0.7149	0.75	PASS

TIA-222-F standard used for calculation of tower twist and sway per the requirements of the CSP.

Foundation and Anchors

The existing foundation consists of three (3) 4.5-ft diameter x 27-ft long reinforced concrete caissons. The base of the tower is connected to the foundation by means of (10) 1.00"Ø anchor bolts per leg embedded into the concrete foundation structure.

- The tower reactions developed from the governing Load Case were used in the verification of the foundation and anchor bolts:

Load Effect	Proposed Tower Reactions
Leg Shear	50.4 kips
Leg Compression	353.6 kips
Leg Tension	308.5 kips
Base Moment	7,954 ft-kips
Base Shear	87.0 kips

- The anchor bolts **were found** to be within allowable limits.

Tower Section	Component	Stress Ratio (percentage of capacity)	Result
Anchor Bolts	Combined Compression and Shear	48%	PASS

- The foundation was found to be within allowable limits.

Foundation	Design Limit	(percentage of capacity)	Result
(3) Reinforced Concrete Caisson	Uplift	35%	PASS
	Bearing	47%	PASS

Conclusion

This analysis shows that the subject tower **is adequate** to support the proposed antenna configuration.

The analysis is based, in part, on the information provided to this office by Verizon and the CSP. If the existing conditions are different than the information in this report, Centek Engineering, Inc. must be contacted for resolution of any potential issues.

Please feel free to call with any questions or comments.

Respectfully Submitted by:



Timothy J. Lynn, PE
 Structural Engineer



Standard Conditions for Furnishing of
Professional Engineering Services on
Existing Structures

All engineering services are performed on the basis that the information used is current and correct. This information may consist of, but is not necessarily limited to:

- Information supplied by the client regarding the structure itself, its foundations, the soil conditions, the antenna and feed line loading on the structure and its components, or other relevant information.
- Information from the field and/or drawings in the possession of Centek Engineering, Inc. or generated by field inspections or measurements of the structure.
- It is the responsibility of the client to ensure that the information provided to Centek Engineering, Inc. and used in the performance of our engineering services is correct and complete. In the absence of information to the contrary, we assume that all structures were constructed in accordance with the drawings and specifications and are in an un-corroded condition and have not deteriorated. It is therefore assumed that its capacity has not significantly changed from the “as new” condition.
- All services will be performed to the codes specified by the client, and we do not imply to meet any other codes or requirements unless explicitly agreed in writing. If wind and ice loads or other relevant parameters are to be different from the minimum values recommended by the codes, the client shall specify the exact requirement. In the absence of information to the contrary, all work will be performed in accordance with the latest revision of ANSI/ASCE10 & ANSI/EIA-222
- All services performed, results obtained, and recommendations made are in accordance with generally accepted engineering principles and practices. Centek Engineering, Inc. is not responsible for the conclusions, opinions and recommendations made by others based on the information we supply.

CENTEK Engineering, Inc.
Structural Analysis - 180-ft Lattice Tower #32 Westport
Antenna Upgrade – Verizon
Westport, CT
Rev 6 ~ June 11, 2024

GENERAL DESCRIPTION OF STRUCTURAL ANALYSIS PROGRAM


tnxTower, is an integrated structural analysis and design software package for Designed specifically for the telecommunications industry, tnxTower, formerly RISA Tower, automates much of the tower analysis and design required by the TIA/EIA 222 Standard.

tnxTower Features:

- tnxTower can analyze and design 3- and 4-sided guyed towers, 3- and 4-sided self-supporting towers and either round or tapered ground mounted poles with or without guys.
- The program analyzes towers using the TIA-222-H standard or any of the previous TIA/EIA standards back to RS-222 (1959). Steel design is checked using the AISC ASD or the AISC LRFD specifications.
- Linear and non-linear (P-delta) analyses can be used in determining displacements and forces in the structure. Wind pressures and forces are automatically calculated.
- Extensive graphics plots include material take-off, shear-moment, leg compression, displacement, twist, feed line, guy anchor and stress plots.
- tnxTower contains unique features such as True Cable behavior, hog rod take-up, foundation stiffness and much more.

Feed Line Plan


Round
Flat
App In Face
App Out Face



Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587		Job: 22027.01 - Westport	
		Project: 180-ft Lattice Tower (CSP #32)	
Client: Verizon	Drawn by: T.JL	App'd:	
Code: TIA-222-H	Date: 01/22/24	Scale: NTS	
Path:		Dwg No. E-7	

Feed Line Distribution Chart 0' - 180'

— Round
 — Flat
 — App In Face
 — App Out Face
 — Truss Leg



Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587		Job: 22027.01 - Westport	
		Project: 180-ft Lattice Tower (CSP #32)	
Client: Verizon	Drawn by: T.JL	App'd:	
Code: TIA-222-H	Date: 01/22/24	Scale: NTS	
Path:		Dwg No: E-7	

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 1 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by TJL

Tower Input Data

The main tower is a 3x free standing tower with an overall height of 180.00 ft above the ground line.
 The base of the tower is set at an elevation of 0.00 ft above the ground line.
 The face width of the tower is 8.54 ft at the top and 27.68 ft at the base.
 This tower is designed using the TIA-222-H standard.


The following design criteria apply:

- Tower base elevation above sea level: 0.00 ft.
- Basic wind speed of 130 mph.
- Risk Category III.
- Exposure Category C.
- Simplified Topographic Factor Procedure for wind speed-up calculations is used.
- Topographic Category: 1.
- Crest Height: 0.00 ft.
- Nominal ice thickness of 1.0000 in.
- Ice thickness is considered to increase with height.
- Ice density of 56 pcf.
- A wind speed of 50 mph is used in combination with ice.
- Deflections calculated using a wind speed of 60 mph.
- P-Delta for analysis does not apply for this case - TIA-222-H Section 3.5.
- Pressures are calculated at each section.
- Stress ratio used in tower member design is 1.
- Local bending stresses due to climbing loads, feed line supports, and appurtenance mounts are not considered.

Options

- | | | |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <ul style="list-style-type: none"> Consider Moments - Legs Consider Moments - Horizontals Consider Moments - Diagonals Use Moment Magnification √ Use Code Stress Ratios √ Use Code Safety Factors - Guys Escalate Ice Always Use Max Kz Use Special Wind Profile √ Include Bolts In Member Capacity √ Leg Bolts Are At Top Of Section √ Secondary Horizontal Braces Leg Use Diamond Inner Bracing (4 Sided) √ SR Members Have Cut Ends SR Members Are Concentric Distribute Leg Loads As Uniform | <ul style="list-style-type: none"> Assume Legs Pinned Assume Rigid Index Plate √ Use Clear Spans For Wind Area √ Use Clear Spans For KL/r Retension Guys To Initial Tension √ Bypass Mast Stability Checks √ Use Azimuth Dish Coefficients √ Project Wind Area of Appurtenances Alternative Appurt. EPA Calculation Autocalc Torque Arm Areas Add IBC .6D+W Combination √ Sort Capacity Reports By Component Triangulate Diamond Inner Bracing Treat Feed Line Bundles As Cylinder Ignore KL/ry For 60 Deg. Angle Legs Use ASCE 10 X-Brace Ly Rules | <ul style="list-style-type: none"> √ Calculate Redundant Bracing Forces Ignore Redundant Members in FEA √ SR Leg Bolts Resist Compression √ All Leg Panels Have Same Allowable Offset Girt At Foundation √ Consider Feed Line Torque √ Include Angle Block Shear Check Use TIA-222-H Bracing Resist. Exemption Use TIA-222-H Tension Splice Exemption <li style="text-align: center;">Poles √ Include Shear-Torsion Interaction Always Use Sub-Critical Flow Use Top Mounted Sockets Pole Without Linear Attachments Pole With Shroud Or No Appurtenances Outside and Inside Corner Radii Are Known |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 2 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by TJJ



Tower Section Geometry

Tower Section	Tower Elevation	Assembly Database	Description	Section Width	Number of Sections	Section Length
	ft			ft		ft
T1	180.00-160.00			8.54	1	20.00
T2	160.00-140.00			8.63	1	20.00
T3	140.00-133.33			10.71	1	6.67
T4	133.33-126.67			11.40	1	6.67
T5	126.67-120.00			12.10	1	6.67
T6	120.00-100.00			12.79	1	20.00
T7	100.00-90.00			15.04	1	10.00
T8	90.00-80.00			16.36	1	10.00
T9	80.00-60.00			17.68	1	20.00
T10	60.00-40.00			20.18	1	20.00
T11	40.00-30.00			22.68	1	10.00
T12	30.00-20.00			23.93	1	10.00
T13	20.00-0.00			25.18	1	20.00

Tower Section Geometry (cont'd)

Tower Section	Tower Elevation	Diagonal Spacing	Bracing Type	Has K Brace End Panels	Has Horizontals	Top Girt Offset	Bottom Girt Offset
	ft	ft				in	in
T1	180.00-160.00	6.67	K Brace Down	No	Yes	0.0000	0.0000
T2	160.00-140.00	6.67	K Brace Down	No	Yes	0.0000	0.0000

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 3 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by TJL

Tower Section	Tower Elevation ft	Diagonal Spacing ft	Bracing Type	Has K Brace End Panels	Has Horizontals	Top Girt Offset in	Bottom Girt Offset in
T3	140.00-133.33	6.67	K Brace Down	No	Yes	0.0000	0.0000
T4	133.33-126.67	6.67	K Brace Down	No	Yes	0.0000	0.0000
T5	126.67-120.00	6.67	K Brace Down	No	Yes	0.0000	0.0000
T6	120.00-100.00	10.00	K Brace Down	No	Yes	0.0000	0.0000
T7	100.00-90.00	10.00	K Brace Down	No	Yes	0.0000	0.0000
T8	90.00-80.00	10.00	K Brace Down	No	Yes	0.0000	0.0000
T9	80.00-60.00	10.00	K Brace Down	No	Yes	0.0000	0.0000
T10	60.00-40.00	10.00	K Brace Down	No	Yes	0.0000	0.0000
T11	40.00-30.00	10.00	K Brace Down	No	Yes	0.0000	0.0000
T12	30.00-20.00	10.00	K Brace Down	No	Yes	0.0000	0.0000
T13	20.00-0.00	20.00	K1 Down	No	Yes	0.0000	0.0000

Tower Section Geometry (cont'd)

Tower Elevation ft	Leg Type	Leg Size	Leg Grade	Diagonal Type	Diagonal Size	Diagonal Grade
T1 180.00-160.00	Pipe	ROHN 3 STD	A572-50 (50 ksi)	Pipe	ROHN 2 STD	A572-50 (50 ksi)
T2 160.00-140.00	Pipe	ROHN 4 STD	A572-50 (50 ksi)	Pipe	ROHN 2 STD	A572-50 (50 ksi)
T3 140.00-133.33	Pipe	ROHN 5 EH	A572-50 (50 ksi)	Pipe	ROHN 2 EH	A572-50 (50 ksi)
T4 133.33-126.67	Pipe	ROHN 5 EH	A572-50 (50 ksi)	Pipe	ROHN 2 EH	A572-50 (50 ksi)
T5 126.67-120.00	Pipe	ROHN 5 EH	A572-50 (50 ksi)	Pipe	ROHN 2 XXS	A572-50 (50 ksi)
T6 120.00-100.00	Pipe	ROHN 6 EHS	A572-50 (50 ksi)	Pipe	Pipe 2.5 XXS	A572-50 (50 ksi)
T7 100.00-90.00	Pipe	ROHN 6 EH	A572-50 (50 ksi)	Pipe	ROHN 3 STD	A572-50 (50 ksi)
T8 90.00-80.00	Pipe	ROHN 6 EH	A572-50 (50 ksi)	Pipe	ROHN 3 STD	A572-50 (50 ksi)
T9 80.00-60.00	Arbitrary Shape	120deg_9.6250x0.375 BU on ROHN 8 EHS	A572-50 (50 ksi)	Pipe	ROHN 3 STD	A572-50 (50 ksi)
T10 60.00-40.00	Arbitrary Shape	1/3 9.6250x0.375 on ROHN 8 EHS Leg Pipe	A572-42 (42 ksi)	Pipe	ROHN 3 EH	A572-50 (50 ksi)
T11 40.00-30.00	Arbitrary Shape	1/3 9.6250x0.375 on ROHN 8 EHS Leg Pipe	A572-42 (42 ksi)	Pipe	ROHN 3 EH	A572-50 (50 ksi)
T12 30.00-20.00	Arbitrary Shape	1/3 9.6250x0.375 on ROHN 8 EHS Leg Pipe	A572-42 (42 ksi)	Pipe	ROHN 3 EH	A572-50 (50 ksi)
T13 20.00-0.00	Arbitrary Shape	1/3 9.6250x0.375 on ROHN 8 EH Leg Pipe	A572-42 (42 ksi)	Pipe	ROHN 3 EH	A572-50 (50 ksi)

Tower Section Geometry (cont'd)

Tower Elevation ft	Top Girt Type	Top Girt Size	Top Girt Grade	Bottom Girt Type	Bottom Girt Size	Bottom Girt Grade
T4 133.33-126.67	Pipe	ROHN 2 STD	A572-50 (50 ksi)	Solid Round		A36 (36 ksi)
T5 126.67-120.00	Pipe	ROHN 2 STD	A572-50	Solid Round		A36

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 4 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by TJL

Tower Elevation ft	Top Girt Type	Top Girt Size	Top Girt Grade	Bottom Girt Type	Bottom Girt Size	Bottom Girt Grade
T8 90.00-80.00	Pipe	ROHN 2 STD	(50 ksi) A572-50	Single Angle		(36 ksi) A36
T12 30.00-20.00	Pipe	ROHN 2.5 EH	(50 ksi) A572-50	Single Angle		(36 ksi) A36

Tower Section Geometry (cont'd)

Tower Elevation ft	No. of Mid Girts	Mid Girt Type	Mid Girt Size	Mid Girt Grade	Horizontal Type	Horizontal Size	Horizontal Grade
T1 180.00-160.00	None	Flat Bar		A36 (36 ksi)	Pipe	ROHN 1.5 STD	A572-50 (50 ksi)
T2 160.00-140.00	None	Flat Bar		A36 (36 ksi)	Pipe	ROHN 1.5 STD	A572-50 (50 ksi)
T3 140.00-133.33	None	Flat Bar		A36 (36 ksi)	Pipe	ROHN 2 STD	A572-50 (50 ksi)
T4 133.33-126.67	None	Flat Bar		A36 (36 ksi)	Pipe	ROHN 2 STD	A572-50 (50 ksi)
T5 126.67-120.00	None	Flat Bar		A36 (36 ksi)	Pipe	ROHN 2 STD	A572-50 (50 ksi)
T6 120.00-100.00	None	Single Angle		A36 (36 ksi)	Pipe	ROHN 2 STD	A572-50 (50 ksi)
T7 100.00-90.00	None	Flat Bar		A36 (36 ksi)	Pipe	ROHN 2 STD	A572-50 (50 ksi)
T8 90.00-80.00	None	Flat Bar		A36 (36 ksi)	Pipe	ROHN 2 STD	A572-50 (50 ksi)
T9 80.00-60.00	None	Flat Bar		A36 (36 ksi)	Pipe	ROHN 2.5 STD	A572-50 (50 ksi)
T10 60.00-40.00	None	Single Angle		A36 (36 ksi)	Pipe	ROHN 2.5 STD	A572-50 (50 ksi)
T11 40.00-30.00	None	Flat Bar		A36 (36 ksi)	Pipe	ROHN 2.5 STD	A572-50 (50 ksi)
T12 30.00-20.00	None	Flat Bar		A36 (36 ksi)	Pipe	ROHN 2.5 STD	A572-50 (50 ksi)
T13 20.00-0.00	None	Flat Bar		A36 (36 ksi)	Pipe	P3.5x.226	A572-50 (50 ksi)

Tower Section Geometry (cont'd)

Tower Elevation ft	Secondary Horizontal Type	Secondary Horizontal Size	Secondary Horizontal Grade	Inner Bracing Type	Inner Bracing Size	Inner Bracing Grade
T1 180.00-160.00	Solid Round		A36 (36 ksi)	Single Angle	L2x2x1/8	A36 (36 ksi)
T2 160.00-140.00	Solid Round		A36 (36 ksi)	Single Angle	L2x2x1/8	A36 (36 ksi)
T3 140.00-133.33	Solid Round		A36 (36 ksi)	Single Angle	L2x2x1/8	A36 (36 ksi)

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 5 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by TJL

Tower Elevation	Secondary Horizontal Type	Secondary Horizontal Size	Secondary Horizontal Grade	Inner Bracing Type	Inner Bracing Size	Inner Bracing Grade
ft						
T4 133.33-126.67	Solid Round		A36 (36 ksi)	Single Angle	L2x2x1/8	A36 (36 ksi)
T5 126.67-120.00	Solid Round		A36 (36 ksi)	Single Angle	L2x2x1/8	A36 (36 ksi)
T6 120.00-100.00	Single Angle		A36 (36 ksi)	Single Angle	L2 1/2x2 1/2x3/16	A36 (36 ksi)
T7 100.00-90.00	Solid Round		A36 (36 ksi)	Single Angle	L2 1/2x2 1/2x3/16	A36 (36 ksi)
T8 90.00-80.00	Solid Round		A36 (36 ksi)	Single Angle	L2 1/2x2 1/2x3/16	A36 (36 ksi)
T9 80.00-60.00	Solid Round		A36 (36 ksi)	Single Angle	L3x3x3/16	A36 (36 ksi)
T10 60.00-40.00	Single Angle		A36 (36 ksi)	Single Angle	L3 1/2x3 1/2x1/4	A572-50 (50 ksi)
T11 40.00-30.00	Single Angle		A572-50 (50 ksi)	Single Angle	L3 1/2x3 1/2x1/4	A572-50 (50 ksi)
T12 30.00-20.00	Single Angle		A572-50 (50 ksi)	Single Angle	L3 1/2x3 1/2x1/4	A572-50 (50 ksi)
T13 20.00-0.00	Solid Round		A36 (36 ksi)	Pipe	ROHN 2 STD	A572-50 (50 ksi)

Tower Section Geometry (cont'd)

Tower Elevation	Redundant Bracing Grade	Redundant Type	Redundant Size	K Factor	
ft					
T13 20.00-0.00	A572-50 (50 ksi)	Horizontal (1)	Pipe	ROHN 1.5 STD	1
	A572-50 (50 ksi)	Diagonal (1)	Pipe	ROHN 2 STD	1
	A572-50 (50 ksi)	Hip (1)	Pipe	ROHN 2.5 STD	1

Tower Section Geometry (cont'd)

Tower Elevation	Gusset Area (per face)	Gusset Thickness	Gusset Grade	Adjust. Factor A_f	Adjust. Factor A_r	Weight Mult.	Double Angle Stitch Bolt Spacing Diagonals	Double Angle Stitch Bolt Spacing Horizontals	Double Angle Stitch Bolt Spacing Redundants
ft	ft ²	in					in	in	in
T1 180.00-160.00	0.00	0.0000	A36 (36 ksi)	1	1	1	36.0000	36.0000	36.0000
T2 160.00-140.00	0.00	0.0000	A36 (36 ksi)	1	1	1	36.0000	36.0000	36.0000
T3 140.00-133.33	0.00	0.0000	A36 (36 ksi)	1	1	1	36.0000	36.0000	36.0000
T4 133.33-126.67	0.00	0.0000	A36 (36 ksi)	1	1	1	36.0000	36.0000	36.0000
T5 126.67-120.00	0.00	0.0000	A36 (36 ksi)	1	1	1	36.0000	36.0000	36.0000
T6 120.00-100.00	0.00	0.0000	A36 (36 ksi)	1	1	1	36.0000	36.0000	36.0000
T7 100.00-90.00	0.00	0.0000	A36 (36 ksi)	1	1	1	36.0000	36.0000	36.0000

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 6 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by TJJ

Tower Elevation	Gusset Area (per face)	Gusset Thickness	Gusset Grade	Adjust. Factor A_f	Adjust. Factor A_r	Weight Mult.	Double Angle Stitch Bolt Spacing Diagonals	Double Angle Stitch Bolt Spacing Horizontals	Double Angle Stitch Bolt Spacing Redundants
ft	ft ²	in					in	in	in
T8 90.00-80.00	0.00	0.0000	A36 (36 ksi)	1	1	1	36.0000	36.0000	36.0000
T9 80.00-60.00	0.00	0.0000	A36 (36 ksi)	1	1	1	36.0000	36.0000	36.0000
T10 60.00-40.00	0.00	0.0000	A36 (36 ksi)	1	1	1	36.0000	36.0000	36.0000
T11 40.00-30.00	0.00	0.0000	A36 (36 ksi)	1	1	1	36.0000	36.0000	36.0000
T12 30.00-20.00	0.00	0.0000	A36 (36 ksi)	1	1	1	36.0000	36.0000	36.0000
T13 20.00-0.00	0.00	0.0000	A36 (36 ksi)	1	1	1	36.0000	36.0000	36.0000

Tower Section Geometry (cont'd)

Tower Elevation	Calc K Single Angles	Calc K Solid Rounds	K Factors ¹							
			Legs	X Brace Diags	K Brace Diags	Single Diags	Girts	Horiz.	Sec. Horiz.	Inner Brace
			X Y	X Y	X Y	X Y	X Y	X Y	X Y	X Y
T1 180.00-160.00	Yes	Yes	1	1	1	1	1	1	1	1
T2 160.00-140.00	Yes	Yes	1	1	1	1	1	1	1	1
T3 140.00-133.33	Yes	Yes	1	1	1	1	1	1	1	1
T4 133.33-126.67	Yes	Yes	1	1	1	1	1	1	1	1
T5 126.67-120.00	Yes	Yes	1	1	1	1	1	1	1	1
T6 120.00-100.00	Yes	Yes	1	1	1	1	1	1	1	1
T7 100.00-90.00	Yes	Yes	1	1	1	1	1	1	1	1
T8 90.00-80.00	Yes	Yes	1	1	1	1	1	1	1	1
T9 80.00-60.00	Yes	Yes	1	1	1	1	1	1	1	1
T10 60.00-40.00	Yes	Yes	1	1	1	1	1	1	1	1
T11 40.00-30.00	Yes	Yes	1	1	1	1	1	1	1	1
T12 30.00-20.00	Yes	Yes	1	1	1	1	1	1	1	1
T13 20.00-0.00	Yes	Yes	1	1	0.5	1	1	1	1	1

¹Note: K factors are applied to member segment lengths. K-braces without inner supporting members will have the K factor in the out-of-plane direction applied to the overall length.

Tower Section Geometry (cont'd)

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 7 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by TJL

Tower Elevation ft	Leg		Diagonal		Top Girt		Bottom Girt		Mid Girt		Long Horizontal		Short Horizontal	
	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U
T1 180.00-160.00	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75
T2 160.00-140.00	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75
T3 140.00-133.33	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75
T4 133.33-126.67	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75
T5 126.67-120.00	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75
T6 120.00-100.00	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75
T7 100.00-90.00	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75
T8 90.00-80.00	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75
T9 80.00-60.00	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75
T10 60.00-40.00	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75
T11 40.00-30.00	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75
T12 30.00-20.00	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75
T13 20.00-0.00	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75

Tower Elevation ft	Redundant Horizontal		Redundant Diagonal		Redundant Sub-Diagonal		Redundant Sub-Horizontal		Redundant Vertical		Redundant Hip		Redundant Hip Diagonal	
	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U
T1 180.00-160.00	0.0000	0.75 (1)	0.0000	0.75 (1)	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75 (1)	0.0000	0.75 (1)
	0.0000	0.75 (2)	0.0000	0.75 (2)							0.0000	0.75 (2)	0.0000	0.75 (2)
	0.0000	0.75 (3)	0.0000	0.75 (3)							0.0000	0.75 (3)	0.0000	0.75 (3)
	0.0000	0.75 (4)	0.0000	0.75 (4)							0.0000	0.75 (4)	0.0000	0.75 (4)
T2 160.00-140.00	0.0000	0.75 (1)	0.0000	0.75 (1)	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75 (1)	0.0000	0.75 (1)
	0.0000	0.75 (2)	0.0000	0.75 (2)							0.0000	0.75 (2)	0.0000	0.75 (2)
	0.0000	0.75 (3)	0.0000	0.75 (3)							0.0000	0.75 (3)	0.0000	0.75 (3)
	0.0000	0.75 (4)	0.0000	0.75 (4)							0.0000	0.75 (4)	0.0000	0.75 (4)
T3 140.00-133.33	0.0000	0.75 (1)	0.0000	0.75 (1)	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75 (1)	0.0000	0.75 (1)
	0.0000	0.75 (2)	0.0000	0.75 (2)							0.0000	0.75 (2)	0.0000	0.75 (2)
	0.0000	0.75 (3)	0.0000	0.75 (3)							0.0000	0.75 (3)	0.0000	0.75 (3)
	0.0000	0.75 (4)	0.0000	0.75 (4)							0.0000	0.75 (4)	0.0000	0.75 (4)

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 8 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by TJL

Tower Elevation ft	Redundant Horizontal		Redundant Diagonal		Redundant Sub-Diagonal		Redundant Sub-Horizontal		Redundant Vertical		Redundant Hip		Redundant Hip Diagonal	
	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U
T4 133.33-126.67	0.0000	0.75 (1)	0.0000	0.75 (1)	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75 (1)	0.0000	0.75 (1)
	0.0000	0.75 (2)	0.0000	0.75 (2)							0.0000	0.75 (2)	0.0000	0.75 (2)
	0.0000	0.75 (3)	0.0000	0.75 (3)							0.0000	0.75 (3)	0.0000	0.75 (3)
	0.0000	0.75 (4)	0.0000	0.75 (4)							0.0000	0.75 (4)	0.0000	0.75 (4)
T5 126.67-120.00	0.0000	0.75 (1)	0.0000	0.75 (1)	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75 (1)	0.0000	0.75 (1)
	0.0000	0.75 (2)	0.0000	0.75 (2)							0.0000	0.75 (2)	0.0000	0.75 (2)
	0.0000	0.75 (3)	0.0000	0.75 (3)							0.0000	0.75 (3)	0.0000	0.75 (3)
	0.0000	0.75 (4)	0.0000	0.75 (4)							0.0000	0.75 (4)	0.0000	0.75 (4)
T6 120.00-100.00	0.0000	0.75 (1)	0.0000	0.75 (1)	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75 (1)	0.0000	0.75 (1)
	0.0000	0.75 (2)	0.0000	0.75 (2)							0.0000	0.75 (2)	0.0000	0.75 (2)
	0.0000	0.75 (3)	0.0000	0.75 (3)							0.0000	0.75 (3)	0.0000	0.75 (3)
	0.0000	0.75 (4)	0.0000	0.75 (4)							0.0000	0.75 (4)	0.0000	0.75 (4)
T7 100.00-90.00	0.0000	0.75 (1)	0.0000	0.75 (1)	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75 (1)	0.0000	0.75 (1)
	0.0000	0.75 (2)	0.0000	0.75 (2)							0.0000	0.75 (2)	0.0000	0.75 (2)
	0.0000	0.75 (3)	0.0000	0.75 (3)							0.0000	0.75 (3)	0.0000	0.75 (3)
	0.0000	0.75 (4)	0.0000	0.75 (4)							0.0000	0.75 (4)	0.0000	0.75 (4)
T8 90.00-80.00	0.0000	0.75 (1)	0.0000	0.75 (1)	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75 (1)	0.0000	0.75 (1)
	0.0000	0.75 (2)	0.0000	0.75 (2)							0.0000	0.75 (2)	0.0000	0.75 (2)
	0.0000	0.75 (3)	0.0000	0.75 (3)							0.0000	0.75 (3)	0.0000	0.75 (3)
	0.0000	0.75 (4)	0.0000	0.75 (4)							0.0000	0.75 (4)	0.0000	0.75 (4)
T9 80.00-60.00	0.0000	0.75 (1)	0.0000	0.75 (1)	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75 (1)	0.0000	0.75 (1)
	0.0000	0.75 (2)	0.0000	0.75 (2)							0.0000	0.75 (2)	0.0000	0.75 (2)
	0.0000	0.75 (3)	0.0000	0.75 (3)							0.0000	0.75 (3)	0.0000	0.75 (3)
	0.0000	0.75 (4)	0.0000	0.75 (4)							0.0000	0.75 (4)	0.0000	0.75 (4)
T10 60.00-40.00	0.0000	0.75 (1)	0.0000	0.75 (1)	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75 (1)	0.0000	0.75 (1)
	0.0000	0.75 (2)	0.0000	0.75 (2)							0.0000	0.75 (2)	0.0000	0.75 (2)
	0.0000	0.75 (3)	0.0000	0.75 (3)							0.0000	0.75 (3)	0.0000	0.75 (3)
	0.0000	0.75 (4)	0.0000	0.75 (4)							0.0000	0.75 (4)	0.0000	0.75 (4)

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 9 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by TJL

Tower Elevation ft	Redundant Horizontal		Redundant Diagonal		Redundant Sub-Diagonal		Redundant Sub-Horizontal		Redundant Vertical		Redundant Hip		Redundant Hip Diagonal	
	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U
T11 40.00-30.00	0.0000	0.75 (1)	0.0000	0.75 (1)	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75 (1)	0.0000	0.75 (1)
	0.0000	0.75 (2)	0.0000	0.75 (2)							0.0000	0.75 (2)	0.0000	0.75 (2)
	0.0000	0.75 (3)	0.0000	0.75 (3)							0.0000	0.75 (3)	0.0000	0.75 (3)
	0.0000	0.75 (4)	0.0000	0.75 (4)							0.0000	0.75 (4)	0.0000	0.75 (4)
T12 30.00-20.00	0.0000	0.75 (1)	0.0000	0.75 (1)	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75 (1)	0.0000	0.75 (1)
	0.0000	0.75 (2)	0.0000	0.75 (2)							0.0000	0.75 (2)	0.0000	0.75 (2)
	0.0000	0.75 (3)	0.0000	0.75 (3)							0.0000	0.75 (3)	0.0000	0.75 (3)
	0.0000	0.75 (4)	0.0000	0.75 (4)							0.0000	0.75 (4)	0.0000	0.75 (4)
T13 20.00-0.00	0.0000	0.75 (1)	0.0000	0.75 (1)	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75 (1)	0.0000	0.75 (1)
	0.0000	0.75 (2)	0.0000	0.75 (2)							0.0000	0.75 (2)	0.0000	0.75 (2)
	0.0000	0.75 (3)	0.0000	0.75 (3)							0.0000	0.75 (3)	0.0000	0.75 (3)
	0.0000	0.75 (4)	0.0000	0.75 (4)							0.0000	0.75 (4)	0.0000	0.75 (4)

Tower Section Geometry (cont'd)

Tower Elevation ft	Connection Offsets							
	Diagonal				K-Bracing			
	Vert. Top	Horiz. Top	Vert. Bot.	Horiz. Bot.	Vert. Top	Horiz. Top	Vert. Bot.	Horiz. Bot.
	in	in	in	in	in	in	in	in
T1 180.00-160.00	0.0000	3.0000	0.0000	3.0000	0.0000	0.0000	0.0000	0.0000
T2 160.00-140.00	0.0000	3.0000	0.0000	3.0000	0.0000	0.0000	0.0000	0.0000
T3 140.00-133.33	0.0000	3.0000	0.0000	3.0000	0.0000	0.0000	0.0000	0.0000
T4 133.33-126.67	0.0000	3.0000	0.0000	3.0000	0.0000	0.0000	0.0000	0.0000
T5 126.67-120.00	0.0000	3.0000	0.0000	3.0000	0.0000	0.0000	0.0000	0.0000

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 10 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by TJL

Tower Elevation	Connection Offsets							
	Diagonal				K-Bracing			
	Vert. Top	Horiz. Top	Vert. Bot.	Horiz. Bot.	Vert. Top	Horiz. Top	Vert. Bot.	Horiz. Bot.
ft	in	in	in	in	in	in	in	in
T6	0.0000	3.0000	0.0000	3.0000	0.0000	0.0000	0.0000	0.0000
120.00-100.00								
T7	0.0000	3.0000	0.0000	3.0000	0.0000	0.0000	0.0000	0.0000
100.00-90.00								
T8	0.0000	3.0000	0.0000	3.0000	0.0000	0.0000	0.0000	0.0000
90.00-80.00								
T9	0.0000	3.0000	0.0000	3.0000	0.0000	0.0000	0.0000	0.0000
80.00-60.00								
T10	0.0000	3.0000	0.0000	3.0000	0.0000	0.0000	0.0000	0.0000
60.00-40.00								
T11	0.0000	3.0000	0.0000	3.0000	0.0000	0.0000	0.0000	0.0000
40.00-30.00								
T12	0.0000	3.0000	0.0000	3.0000	0.0000	0.0000	0.0000	0.0000
30.00-20.00								
T13	0.0000	3.0000	0.0000	3.0000	0.0000	0.0000	0.0000	0.0000
20.00-0.00								

Tower Section Geometry (cont'd)

Tower Elevation ft	Leg Connection Type	Leg		Diagonal		Top Girt		Bottom Girt		Mid Girt		Long Horizontal		Short Horizontal	
		Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.
T1	Flange	0.8750	0	0.6250	3	0.6250	2	0.6250	0	0.6250	0	0.6250	2	0.6250	0
180.00-160.00		A325N		A325N		A325N		A325N		A325N		A325N		A325N	
T2	Flange	0.8750	4	0.6250	3	0.6250	2	0.6250	0	0.6250	0	0.6250	2	0.6250	0
160.00-140.00		A325N		A325N		A325N		A325N		A325N		A325N		A325N	
T3	Flange	1.0000	4	0.6250	3	0.6250	2	0.0000	0	0.6250	0	0.6250	2	0.6250	0
140.00-133.33		A325N		A325N		A325N		A325N		A325N		A325N		A325N	
T4	Flange	0.7500	0	0.6250	3	0.6250	2	0.0000	0	0.6250	0	0.6250	2	0.6250	0
133.33-126.67		A325N		A325N		A325N		A325N		A325N		A325N		A325N	
T5	Flange	0.7500	0	0.6250	3	0.6250	2	0.6250	0	0.6250	0	0.6250	2	0.6250	0
126.67-120.00		A325N		A325N		A325N		A325N		A325N		A325N		A325N	
T6	Flange	1.0000	6	0.6250	3	0.6250	2	0.0000	0	0.6250	0	0.6250	2	0.6250	0
120.00-100.00		A325N		A325N		A325N		A325N		A325N		A325N		A325N	
T7	Flange	1.0000	6	0.6250	3	0.6250	2	0.0000	0	0.6250	0	0.6250	2	0.6250	0
100.00-90.00		A325N		A325N		A325N		A325N		A325N		A325N		A325N	
T8	Flange	1.0000	0	0.6250	3	0.6250	2	0.6250	0	0.6250	0	0.6250	2	0.6250	0
90.00-80.00		A325N		A325N		A325N		A325N		A325N		A325N		A325N	
T9	Flange	1.0000	8	0.6250	3	0.6250	2	0.6250	0	0.6250	0	0.6250	2	0.6250	0
80.00-60.00		A325N		A325N		A325N		A325N		A325N		A325N		A325N	
T10	Flange	1.0000	8	0.6250	3	0.6250	2	0.6250	0	0.6250	0	0.6250	2	0.6250	0
60.00-40.00		A325N		A325N		A325N		A325N		A325N		A325N		A325N	
T11	Flange	1.0000	8	0.6250	3	0.6250	2	0.6250	0	0.6250	0	0.6250	2	0.6250	0
40.00-30.00		A325N		A325N		A325N		A325N		A325N		A325N		A325N	
T12	Flange	1.0000	0	0.6250	3	0.6250	2	0.6250	0	0.6250	0	0.6250	2	0.6250	0
30.00-20.00		A325N		A325N		A325N		A325N		A325N		A325N		A325N	
T13	Flange	1.0000	8	0.6250	3	0.6250	2	0.6250	0	0.6250	0	0.7500	2	0.6250	0
20.00-0.00		A325N		A325X		A325N		A325N		A325N		A325N		A325N	

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 11 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by TJL

Feed Line/Linear Appurtenances - Entered As Round Or Flat

Description	Face or Leg	Allow Shield	Exclude From Torque Calculation	Component Type	Placement ft	Face Offset in	Lateral Offset (Frac FW)	#	# Per Row	Clear Spacing in	Width or Diameter in	Perimeter in	Weight plf
* LDF6-50A (1-1/4 FOAM) (AT&T)	B	No	No	Ar (CaAa)	133.00 - 0.00	0.0000	0.46	6	6	1.5500	1.5500		0.66
DC Cable WR-VG122S T (AT&T)	B	No	No	Ar (CaAa)	133.00 - 0.00	0.0000	0.43	4	4	0.4000	0.4000		0.25
1 5/8" Hybridflex (AT&T)	B	No	No	Ar (CaAa)	133.00 - 0.00	0.0000	0.41	3	1	1.6250	1.6250		1.13
DC Cable WR-VG122S T (AT&T)	B	No	No	Ar (CaAa)	133.00 - 0.00	0.0000	0.42	3	3	0.4000	0.4000		0.25
* LDF7-50A (1-5/8 FOAM) (T-Mobile)	B	No	No	Ar (CaAa)	125.00 - 0.00	0.0000	-0.41	18	9	1.9800	1.9800		0.82
Hubner-Suhner Hybrid Cable (T-Mobile)	B	No	No	Ar (CaAa)	125.00 - 0.00	0.0000	-0.385	1	1	0.7087	0.7087		0.48
* HYBRIFLEX 1-5/8" (Verizon)	A	No	No	Ar (CaAa)	160.00 - 0.00	0.0000	-0.48	2	2	1.9800	1.9800		1.90
* LDF5-50A (7/8 FOAM) (CSP-1)	A	No	No	Ar (CaAa)	180.00 - 0.00	0.0000	0.48	1	1	1.0900	1.0900		0.33
EW63 (CSP-42)	A	No	No	Af (CaAa)	177.00 - 0.00	0.0000	0.44	1	1	1.5742	1.5742		0.51
LDF5-50A (7/8 FOAM) (CSP-22)	A	No	No	Ar (CaAa)	170.00 - 0.00	0.0000	0.42	1	1	1.0900	1.0900		0.33
AVA7-50 (1-5/8 LOW DENS. FOAM) (CSP-80)	A	No	No	Ar (CaAa)	170.00 - 0.00	0.0000	0.4	1	1	1.9800	1.9800		0.72
AVA7-50 (1-5/8 LOW DENS. FOAM) (CSP-81)	A	No	No	Ar (CaAa)	170.00 - 0.00	0.0000	0.38	1	1	1.9800	1.9800		0.72
AVA7-50 (1-5/8 LOW DENS. FOAM) (CSP-82)	A	No	No	Ar (CaAa)	170.00 - 0.00	0.0000	0.36	1	1	1.9800	1.9800		0.72
LDF4-50A (1/2 FOAM) (CSP-47)	A	No	No	Ar (CaAa)	170.00 - 0.00	0.0000	0.34	1	1	0.6300	0.6300		0.15
LDF5-50A (7/8 FOAM) (CSP - Yagi)	A	No	No	Ar (CaAa)	169.00 - 0.00	0.0000	0.32	1	1	1.0900	1.0900		0.33
LDF4-50A	A	No	No	Ar (CaAa)	113.00 - 0.00	0.0000	0.3	1	1	0.6300	0.6300		0.15

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 12 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by TJL

Description	Face or Shield Leg	Allow	Exclude From Torque Calculation	Component Type	Placement ft	Face Offset in	Lateral Offset (Frac FW)	#	# Per Row	Clear Spacing in	Width or Diameter in	Perimeter in	Weight plf
(1/2 FOAM) (CSP - Dipole)					0.00								
LDF4-50A (1/2 FOAM) (CSP)	A	No	No	Ar (CaAa)	61.00 - 0.00	0.0000	0.28	1	1	0.6300	0.6300		0.15
HYBRIFLEX 1-5/8" (Dish - Reserved)	B	No	No	Ar (CaAa)	140.00 - 0.00	0.0000	0.25	3	3	1.9800	1.9800		1.90

Feed Line/Linear Appurtenances Section Areas

Tower Section	Tower Elevation ft	Face	A _R ft ²	A _F ft ²	C _{AAA} In Face ft ²	C _{AAA} Out Face ft ²	Weight lb
T1	180.00-160.00	A	0.000	0.000	15.281	0.000	44.64
		B	0.000	0.000	0.000	0.000	0.00
		C	0.000	0.000	0.000	0.000	0.00
T2	160.00-140.00	A	0.000	0.000	32.847	0.000	152.20
		B	0.000	0.000	0.000	0.000	0.00
		C	0.000	0.000	0.000	0.000	0.00
T3	140.00-133.33	A	0.000	0.000	10.949	0.000	50.73
		B	0.000	0.000	3.960	0.000	38.00
		C	0.000	0.000	0.000	0.000	0.00
T4	133.33-126.67	A	0.000	0.000	10.949	0.000	50.73
		B	0.000	0.000	14.711	0.000	95.63
		C	0.000	0.000	0.000	0.000	0.00
T5	126.67-120.00	A	0.000	0.000	10.949	0.000	50.73
		B	0.000	0.000	33.451	0.000	174.87
		C	0.000	0.000	0.000	0.000	0.00
T6	120.00-100.00	A	0.000	0.000	33.666	0.000	154.15
		B	0.000	0.000	118.527	0.000	600.82
		C	0.000	0.000	0.000	0.000	0.00
T7	100.00-90.00	A	0.000	0.000	17.054	0.000	77.60
		B	0.000	0.000	59.264	0.000	300.41
		C	0.000	0.000	0.000	0.000	0.00
T8	90.00-80.00	A	0.000	0.000	17.054	0.000	77.60
		B	0.000	0.000	59.264	0.000	300.41
		C	0.000	0.000	0.000	0.000	0.00
T9	80.00-60.00	A	0.000	0.000	34.170	0.000	155.35
		B	0.000	0.000	118.527	0.000	600.82
		C	0.000	0.000	0.000	0.000	0.00
T10	60.00-40.00	A	0.000	0.000	35.367	0.000	158.20
		B	0.000	0.000	118.527	0.000	600.82
		C	0.000	0.000	0.000	0.000	0.00
T11	40.00-30.00	A	0.000	0.000	17.684	0.000	79.10
		B	0.000	0.000	59.264	0.000	300.41
		C	0.000	0.000	0.000	0.000	0.00
T12	30.00-20.00	A	0.000	0.000	17.684	0.000	79.10
		B	0.000	0.000	59.264	0.000	300.41
		C	0.000	0.000	0.000	0.000	0.00
T13	20.00-0.00	A	0.000	0.000	35.367	0.000	158.20
		B	0.000	0.000	118.527	0.000	600.82
		C	0.000	0.000	0.000	0.000	0.00

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 13 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by TJL

Feed Line/Linear Appurtenances Section Areas - With Ice

Tower Section	Tower Elevation ft	Face or Leg	Ice Thickness in	A_R ft ²	A_F ft ²	C_{AA} In Face ft ²	C_{AA} Out Face ft ²	Weight lb
T1	180.00-160.00	A	1.355	0.000	0.000	41.294	0.000	492.24
		B		0.000	0.000	0.000	0.000	0.00
		C		0.000	0.000	0.000	0.000	0.00
T2	160.00-140.00	A	1.338	0.000	0.000	92.227	0.000	1113.48
		B		0.000	0.000	0.000	0.000	0.00
		C		0.000	0.000	0.000	0.000	0.00
T3	140.00-133.33	A	1.326	0.000	0.000	30.582	0.000	367.07
		B		0.000	0.000	11.149	0.000	152.82
		C		0.000	0.000	0.000	0.000	0.00
T4	133.33-126.67	A	1.319	0.000	0.000	30.497	0.000	364.90
		B		0.000	0.000	45.555	0.000	529.46
		C		0.000	0.000	0.000	0.000	0.00
T5	126.67-120.00	A	1.312	0.000	0.000	30.407	0.000	362.64
		B		0.000	0.000	72.258	0.000	1126.78
		C		0.000	0.000	0.000	0.000	0.00
T6	120.00-100.00	A	1.297	0.000	0.000	94.834	0.000	1114.98
		B		0.000	0.000	241.107	0.000	3932.80
		C		0.000	0.000	0.000	0.000	0.00
T7	100.00-90.00	A	1.278	0.000	0.000	48.142	0.000	558.82
		B		0.000	0.000	120.152	0.000	1949.05
		C		0.000	0.000	0.000	0.000	0.00
T8	90.00-80.00	A	1.264	0.000	0.000	47.840	0.000	551.47
		B		0.000	0.000	119.851	0.000	1936.11
		C		0.000	0.000	0.000	0.000	0.00
T9	80.00-60.00	A	1.240	0.000	0.000	94.951	0.000	1080.90
		B		0.000	0.000	238.670	0.000	3827.93
		C		0.000	0.000	0.000	0.000	0.00
T10	60.00-40.00	A	1.199	0.000	0.000	98.941	0.000	1092.92
		B		0.000	0.000	236.929	0.000	3753.77
		C		0.000	0.000	0.000	0.000	0.00
T11	40.00-30.00	A	1.157	0.000	0.000	48.489	0.000	524.08
		B		0.000	0.000	117.574	0.000	1839.30
		C		0.000	0.000	0.000	0.000	0.00
T12	30.00-20.00	A	1.119	0.000	0.000	47.594	0.000	504.11
		B		0.000	0.000	116.765	0.000	1805.39
		C		0.000	0.000	0.000	0.000	0.00
T13	20.00-0.00	A	1.021	0.000	0.000	90.613	0.000	909.68
		B		0.000	0.000	229.396	0.000	3440.18
		C		0.000	0.000	0.000	0.000	0.00

Feed Line Center of Pressure

Section	Elevation ft	CP_x in	CP_z in	CP_x Ice in	CP_z Ice in
T1	180.00-160.00	-1.5005	-14.6984	-1.9995	-19.2026
T2	160.00-140.00	-8.2189	-15.5796	-11.0579	-18.2466
T3	140.00-133.33	-3.9146	-14.4724	-5.5568	-16.6931
T4	133.33-126.67	14.9057	-2.5135	19.0686	-0.5551
T5	126.67-120.00	14.2056	-24.6943	18.6350	-14.7368
T6	120.00-100.00	15.0320	-32.6335	19.6790	-20.8751
T7	100.00-90.00	16.2759	-35.7700	21.4830	-23.2625

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 14 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by TJL

Section	Elevation	CP _x	CP _z	CP _x Ice	CP _z Ice
	ft	in	in	in	in
T8	90.00-80.00	17.3812	-38.3290	23.0292	-24.9242
T9	80.00-60.00	14.6908	-34.1820	22.6627	-25.3205
T10	60.00-40.00	15.9988	-38.1000	24.5231	-28.8962
T11	40.00-30.00	17.0827	-40.7788	26.3364	-30.9032
T12	30.00-20.00	17.7961	-42.5399	27.5472	-32.1898
T13	20.00-0.00	19.1837	-45.9657	29.8283	-34.4697

Shielding Factor Ka

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K _a No Ice	K _a Ice
T1	17	LDF5-50A (7/8 FOAM)	160.00 - 180.00	1.0000	1.0000
T1	19	EW63	160.00 - 177.00	1.0000	1.0000
T1	20	LDF5-50A (7/8 FOAM)	160.00 - 170.00	1.0000	1.0000
T1	21	AVA7-50 (1-5/8 LOW DENSI. FOAM)	160.00 - 170.00	1.0000	1.0000
T1	22	AVA7-50 (1-5/8 LOW DENSI. FOAM)	160.00 - 170.00	1.0000	1.0000
T1	23	AVA7-50 (1-5/8 LOW DENSI. FOAM)	160.00 - 170.00	1.0000	1.0000
T1	24	LDF4-50A (1/2 FOAM)	160.00 - 170.00	1.0000	1.0000
T1	25	LDF5-50A (7/8 FOAM)	160.00 - 169.00	1.0000	1.0000
T2	15	HYBRIFLEX 1-5/8"	140.00 - 160.00	1.0000	1.0000
T2	17	LDF5-50A (7/8 FOAM)	140.00 - 160.00	1.0000	1.0000
T2	19	EW63	140.00 - 160.00	1.0000	1.0000
T2	20	LDF5-50A (7/8 FOAM)	140.00 - 160.00	1.0000	1.0000
T2	21	AVA7-50 (1-5/8 LOW DENSI. FOAM)	140.00 - 160.00	1.0000	1.0000
T2	22	AVA7-50 (1-5/8 LOW DENSI. FOAM)	140.00 - 160.00	1.0000	1.0000
T2	23	AVA7-50 (1-5/8 LOW DENSI. FOAM)	140.00 - 160.00	1.0000	1.0000
T2	24	LDF4-50A (1/2 FOAM)	140.00 - 160.00	1.0000	1.0000
T2	25	LDF5-50A (7/8 FOAM)	140.00 - 160.00	1.0000	1.0000
T3	15	HYBRIFLEX 1-5/8"	133.33 - 140.00	1.0000	1.0000
T3	17	LDF5-50A (7/8 FOAM)	133.33 - 140.00	1.0000	1.0000
T3	19	EW63	133.33 - 140.00	1.0000	1.0000
T3	20	LDF5-50A (7/8 FOAM)	133.33 - 140.00	1.0000	1.0000
T3	21	AVA7-50 (1-5/8 LOW DENSI. FOAM)	133.33 - 140.00	1.0000	1.0000

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 15 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by TJL

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K _a No Ice	K _a Ice
T3	22	AVA7-50 (1-5/8 LOW DENS. FOAM)	133.33 - 140.00	1.0000	1.0000
T3	23	AVA7-50 (1-5/8 LOW DENS. FOAM)	133.33 - 140.00	1.0000	1.0000
T3	24	LDF4-50A (1/2 FOAM)	133.33 - 140.00	1.0000	1.0000
T3	25	LDF5-50A (7/8 FOAM)	133.33 - 140.00	1.0000	1.0000
T3	28	HYBRIFLEX 1-5/8"	133.33 - 140.00	0.6000	0.6000
T4	2	LDF6-50A (1-1/4 FOAM)	126.67 - 133.00	1.0000	1.0000
T4	3	DC Cable WR-VG122ST	126.67 - 133.00	1.0000	1.0000
T4	4	1 5/8" Hybriflex	126.67 - 133.00	1.0000	1.0000
T4	6	DC Cable WR-VG122ST	126.67 - 133.00	1.0000	1.0000
T4	15	HYBRIFLEX 1-5/8"	126.67 - 133.33	1.0000	1.0000
T4	17	LDF5-50A (7/8 FOAM)	126.67 - 133.33	1.0000	1.0000
T4	19	EW63	126.67 - 133.33	1.0000	1.0000
T4	20	LDF5-50A (7/8 FOAM)	126.67 - 133.33	1.0000	1.0000
T4	21	AVA7-50 (1-5/8 LOW DENS. FOAM)	126.67 - 133.33	1.0000	1.0000
T4	22	AVA7-50 (1-5/8 LOW DENS. FOAM)	126.67 - 133.33	1.0000	1.0000
T4	23	AVA7-50 (1-5/8 LOW DENS. FOAM)	126.67 - 133.33	1.0000	1.0000
T4	24	LDF4-50A (1/2 FOAM)	126.67 - 133.33	1.0000	1.0000
T4	25	LDF5-50A (7/8 FOAM)	126.67 - 133.33	1.0000	1.0000
T4	28	HYBRIFLEX 1-5/8"	126.67 - 133.33	0.6000	0.6000
T5	2	LDF6-50A (1-1/4 FOAM)	120.00 - 126.67	1.0000	1.0000
T5	3	DC Cable WR-VG122ST	120.00 - 126.67	1.0000	1.0000
T5	4	1 5/8" Hybriflex	120.00 - 126.67	1.0000	1.0000
T5	6	DC Cable WR-VG122ST	120.00 - 126.67	1.0000	1.0000
T5	10	LDF7-50A (1-5/8 FOAM)	120.00 - 125.00	1.0000	1.0000
T5	11	Hubner-Suhner Hybrid Cable	120.00 - 125.00	1.0000	1.0000
T5	15	HYBRIFLEX 1-5/8"	120.00 - 126.67	1.0000	1.0000
T5	17	LDF5-50A (7/8 FOAM)	120.00 - 126.67	1.0000	1.0000
T5	19	EW63	120.00 - 126.67	1.0000	1.0000
T5	20	LDF5-50A (7/8 FOAM)	120.00 - 126.67	1.0000	1.0000
T5	21	AVA7-50 (1-5/8 LOW DENS. FOAM)	120.00 - 126.67	1.0000	1.0000
T5	22	AVA7-50 (1-5/8 LOW DENS. FOAM)	120.00 - 126.67	1.0000	1.0000

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 16 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by TJL

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K ₀ No Ice	K _a Ice
T5	23	AVA7-50 (1-5/8 LOW DENS. FOAM)	120.00 - 126.67	1.0000	1.0000
T5	24	LDF4-50A (1/2 FOAM)	120.00 - 126.67	1.0000	1.0000
T5	25	LDF5-50A (7/8 FOAM)	120.00 - 126.67	1.0000	1.0000
T5	28	HYBRIFLEX 1-5/8"	120.00 - 126.67	0.6000	0.6000
T6	2	LDF6-50A (1-1/4 FOAM)	100.00 - 120.00	1.0000	1.0000
T6	3	DC Cable WR-VG122ST	100.00 - 120.00	1.0000	1.0000
T6	4	1 5/8" Hybriflex	100.00 - 120.00	1.0000	1.0000
T6	6	DC Cable WR-VG122ST	100.00 - 120.00	1.0000	1.0000
T6	10	LDF7-50A (1-5/8 FOAM)	100.00 - 120.00	1.0000	1.0000
T6	11	Hubner-Suhner Hybrid Cable	100.00 - 120.00	1.0000	1.0000
T6	15	HYBRIFLEX 1-5/8"	100.00 - 120.00	1.0000	1.0000
T6	17	LDF5-50A (7/8 FOAM)	100.00 - 120.00	1.0000	1.0000
T6	19	EW63	100.00 - 120.00	1.0000	1.0000
T6	20	LDF5-50A (7/8 FOAM)	100.00 - 120.00	1.0000	1.0000
T6	21	AVA7-50 (1-5/8 LOW DENS. FOAM)	100.00 - 120.00	1.0000	1.0000
T6	22	AVA7-50 (1-5/8 LOW DENS. FOAM)	100.00 - 120.00	1.0000	1.0000
T6	23	AVA7-50 (1-5/8 LOW DENS. FOAM)	100.00 - 120.00	1.0000	1.0000
T6	24	LDF4-50A (1/2 FOAM)	100.00 - 120.00	1.0000	1.0000
T6	25	LDF5-50A (7/8 FOAM)	100.00 - 120.00	1.0000	1.0000
T6	26	LDF4-50A (1/2 FOAM)	100.00 - 113.00	1.0000	1.0000
T6	28	HYBRIFLEX 1-5/8"	100.00 - 120.00	0.6000	0.6000
T7	2	LDF6-50A (1-1/4 FOAM)	90.00 - 100.00	1.0000	1.0000
T7	3	DC Cable WR-VG122ST	90.00 - 100.00	1.0000	1.0000
T7	4	1 5/8" Hybriflex	90.00 - 100.00	1.0000	1.0000
T7	6	DC Cable WR-VG122ST	90.00 - 100.00	1.0000	1.0000
T7	10	LDF7-50A (1-5/8 FOAM)	90.00 - 100.00	1.0000	1.0000
T7	11	Hubner-Suhner Hybrid Cable	90.00 - 100.00	1.0000	1.0000
T7	15	HYBRIFLEX 1-5/8"	90.00 - 100.00	1.0000	1.0000
T7	17	LDF5-50A (7/8 FOAM)	90.00 - 100.00	1.0000	1.0000
T7	19	EW63	90.00 - 100.00	1.0000	1.0000
T7	20	LDF5-50A (7/8 FOAM)	90.00 - 100.00	1.0000	1.0000
T7	21	AVA7-50 (1-5/8 LOW DENS. FOAM)	90.00 - 100.00	1.0000	1.0000
T7	22	AVA7-50 (1-5/8 LOW DENS. FOAM)	90.00 - 100.00	1.0000	1.0000
T7	23	AVA7-50 (1-5/8 LOW DENS. FOAM)	90.00 - 100.00	1.0000	1.0000
T7	24	LDF4-50A (1/2 FOAM)	90.00 - 100.00	1.0000	1.0000
T7	25	LDF5-50A (7/8 FOAM)	90.00 - 100.00	1.0000	1.0000
T7	26	LDF4-50A (1/2 FOAM)	90.00 - 100.00	1.0000	1.0000
T7	28	HYBRIFLEX 1-5/8"	90.00 - 100.00	0.6000	0.6000

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 17 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by TJL

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K _a No Ice	K _a Ice
T8	2	LDF6-50A (1-1/4 FOAM)	80.00 - 90.00	1.0000	1.0000
T8	3	DC Cable WR-VG122ST	80.00 - 90.00	1.0000	1.0000
T8	4	1 5/8" Hybriflex	80.00 - 90.00	1.0000	1.0000
T8	6	DC Cable WR-VG122ST	80.00 - 90.00	1.0000	1.0000
T8	10	LDF7-50A (1-5/8 FOAM)	80.00 - 90.00	1.0000	1.0000
T8	11	Hubner-Suhner Hybrid Cable	80.00 - 90.00	1.0000	1.0000
T8	15	HYBRIFLEX 1-5/8"	80.00 - 90.00	1.0000	1.0000
T8	17	LDF5-50A (7/8 FOAM)	80.00 - 90.00	1.0000	1.0000
T8	19	EW63	80.00 - 90.00	1.0000	1.0000
T8	20	LDF5-50A (7/8 FOAM)	80.00 - 90.00	1.0000	1.0000
T8	21	AVA7-50 (1-5/8 LOW DENS. FOAM)	80.00 - 90.00	1.0000	1.0000
T8	22	AVA7-50 (1-5/8 LOW DENS. FOAM)	80.00 - 90.00	1.0000	1.0000
T8	23	AVA7-50 (1-5/8 LOW DENS. FOAM)	80.00 - 90.00	1.0000	1.0000
T8	24	LDF4-50A (1/2 FOAM)	80.00 - 90.00	1.0000	1.0000
T8	25	LDF5-50A (7/8 FOAM)	80.00 - 90.00	1.0000	1.0000
T8	26	LDF4-50A (1/2 FOAM)	80.00 - 90.00	1.0000	1.0000
T8	28	HYBRIFLEX 1-5/8"	80.00 - 90.00	0.6000	0.6000
T9	2	LDF6-50A (1-1/4 FOAM)	60.00 - 80.00	1.0000	1.0000
T9	3	DC Cable WR-VG122ST	60.00 - 80.00	1.0000	1.0000
T9	4	1 5/8" Hybriflex	60.00 - 80.00	1.0000	1.0000
T9	6	DC Cable WR-VG122ST	60.00 - 80.00	1.0000	1.0000
T9	10	LDF7-50A (1-5/8 FOAM)	60.00 - 80.00	1.0000	1.0000
T9	11	Hubner-Suhner Hybrid Cable	60.00 - 80.00	1.0000	1.0000
T9	15	HYBRIFLEX 1-5/8"	60.00 - 80.00	1.0000	1.0000
T9	17	LDF5-50A (7/8 FOAM)	60.00 - 80.00	1.0000	1.0000
T9	19	EW63	60.00 - 80.00	1.0000	1.0000
T9	20	LDF5-50A (7/8 FOAM)	60.00 - 80.00	1.0000	1.0000
T9	21	AVA7-50 (1-5/8 LOW DENS. FOAM)	60.00 - 80.00	1.0000	1.0000
T9	22	AVA7-50 (1-5/8 LOW DENS. FOAM)	60.00 - 80.00	1.0000	1.0000
T9	23	AVA7-50 (1-5/8 LOW DENS. FOAM)	60.00 - 80.00	1.0000	1.0000
T9	24	LDF4-50A (1/2 FOAM)	60.00 - 80.00	1.0000	1.0000
T9	25	LDF5-50A (7/8 FOAM)	60.00 - 80.00	1.0000	1.0000
T9	26	LDF4-50A (1/2 FOAM)	60.00 - 80.00	1.0000	1.0000
T9	27	LDF4-50A (1/2 FOAM)	60.00 - 61.00	1.0000	1.0000
T9	28	HYBRIFLEX 1-5/8"	60.00 - 80.00	0.6000	0.6000
T10	2	LDF6-50A (1-1/4 FOAM)	40.00 - 60.00	1.0000	1.0000
T10	3	DC Cable WR-VG122ST	40.00 - 60.00	1.0000	1.0000
T10	4	1 5/8" Hybriflex	40.00 - 60.00	1.0000	1.0000
T10	6	DC Cable WR-VG122ST	40.00 - 60.00	1.0000	1.0000
T10	10	LDF7-50A (1-5/8 FOAM)	40.00 - 60.00	1.0000	1.0000
T10	11	Hubner-Suhner Hybrid Cable	40.00 - 60.00	1.0000	1.0000
T10	15	HYBRIFLEX 1-5/8"	40.00 - 60.00	1.0000	1.0000
T10	17	LDF5-50A (7/8 FOAM)	40.00 - 60.00	1.0000	1.0000
T10	19	EW63	40.00 - 60.00	1.0000	1.0000
T10	20	LDF5-50A (7/8 FOAM)	40.00 - 60.00	1.0000	1.0000
T10	21	AVA7-50 (1-5/8 LOW DENS. FOAM)	40.00 - 60.00	1.0000	1.0000
T10	22	AVA7-50 (1-5/8 LOW DENS. FOAM)	40.00 - 60.00	1.0000	1.0000
T10	23	AVA7-50 (1-5/8 LOW DENS. FOAM)	40.00 - 60.00	1.0000	1.0000
T10	24	LDF4-50A (1/2 FOAM)	40.00 - 60.00	1.0000	1.0000
T10	25	LDF5-50A (7/8 FOAM)	40.00 - 60.00	1.0000	1.0000
T10	26	LDF4-50A (1/2 FOAM)	40.00 - 60.00	1.0000	1.0000
T10	27	LDF4-50A (1/2 FOAM)	40.00 - 60.00	1.0000	1.0000
T10	28	HYBRIFLEX 1-5/8"	40.00 - 60.00	0.6000	0.6000

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 18 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by T.J.L.

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K _a No Ice	K _a Ice
T11	2	LDF6-50A (1-1/4 FOAM)	30.00 - 40.00	1.0000	1.0000
T11	3	DC Cable WR-VG122ST	30.00 - 40.00	1.0000	1.0000
T11	4	1 5/8" Hybriflex	30.00 - 40.00	1.0000	1.0000
T11	6	DC Cable WR-VG122ST	30.00 - 40.00	1.0000	1.0000
T11	10	LDF7-50A (1-5/8 FOAM)	30.00 - 40.00	1.0000	1.0000
T11	11	Hubner-Subner Hybrid Cable	30.00 - 40.00	1.0000	1.0000
T11	15	HYBRIFLEX 1-5/8"	30.00 - 40.00	1.0000	1.0000
T11	17	LDF5-50A (7/8 FOAM)	30.00 - 40.00	1.0000	1.0000
T11	19	EW63	30.00 - 40.00	1.0000	1.0000
T11	20	LDF5-50A (7/8 FOAM)	30.00 - 40.00	1.0000	1.0000
T11	21	AVA7-50 (1-5/8 LOW DENS. FOAM)	30.00 - 40.00	1.0000	1.0000
T11	22	AVA7-50 (1-5/8 LOW DENS. FOAM)	30.00 - 40.00	1.0000	1.0000
T11	23	AVA7-50 (1-5/8 LOW DENS. FOAM)	30.00 - 40.00	1.0000	1.0000
T11	24	LDF4-50A (1/2 FOAM)	30.00 - 40.00	1.0000	1.0000
T11	25	LDF5-50A (7/8 FOAM)	30.00 - 40.00	1.0000	1.0000
T11	26	LDF4-50A (1/2 FOAM)	30.00 - 40.00	1.0000	1.0000
T11	27	LDF4-50A (1/2 FOAM)	30.00 - 40.00	1.0000	1.0000
T11	28	HYBRIFLEX 1-5/8"	30.00 - 40.00	0.6000	0.6000
T12	2	LDF6-50A (1-1/4 FOAM)	20.00 - 30.00	1.0000	1.0000
T12	3	DC Cable WR-VG122ST	20.00 - 30.00	1.0000	1.0000
T12	4	1 5/8" Hybriflex	20.00 - 30.00	1.0000	1.0000
T12	6	DC Cable WR-VG122ST	20.00 - 30.00	1.0000	1.0000
T12	10	LDF7-50A (1-5/8 FOAM)	20.00 - 30.00	1.0000	1.0000
T12	11	Hubner-Subner Hybrid Cable	20.00 - 30.00	1.0000	1.0000
T12	15	HYBRIFLEX 1-5/8"	20.00 - 30.00	1.0000	1.0000
T12	17	LDF5-50A (7/8 FOAM)	20.00 - 30.00	1.0000	1.0000
T12	19	EW63	20.00 - 30.00	1.0000	1.0000
T12	20	LDF5-50A (7/8 FOAM)	20.00 - 30.00	1.0000	1.0000
T12	21	AVA7-50 (1-5/8 LOW DENS. FOAM)	20.00 - 30.00	1.0000	1.0000
T12	22	AVA7-50 (1-5/8 LOW DENS. FOAM)	20.00 - 30.00	1.0000	1.0000
T12	23	AVA7-50 (1-5/8 LOW DENS. FOAM)	20.00 - 30.00	1.0000	1.0000
T12	24	LDF4-50A (1/2 FOAM)	20.00 - 30.00	1.0000	1.0000
T12	25	LDF5-50A (7/8 FOAM)	20.00 - 30.00	1.0000	1.0000
T12	26	LDF4-50A (1/2 FOAM)	20.00 - 30.00	1.0000	1.0000
T12	27	LDF4-50A (1/2 FOAM)	20.00 - 30.00	1.0000	1.0000
T12	28	HYBRIFLEX 1-5/8"	20.00 - 30.00	0.6000	0.6000
T13	2	LDF6-50A (1-1/4 FOAM)	0.00 - 20.00	1.0000	1.0000
T13	3	DC Cable WR-VG122ST	0.00 - 20.00	1.0000	1.0000
T13	4	1 5/8" Hybriflex	0.00 - 20.00	1.0000	1.0000
T13	6	DC Cable WR-VG122ST	0.00 - 20.00	1.0000	1.0000
T13	10	LDF7-50A (1-5/8 FOAM)	0.00 - 20.00	1.0000	1.0000
T13	11	Hubner-Subner Hybrid Cable	0.00 - 20.00	1.0000	1.0000
T13	15	HYBRIFLEX 1-5/8"	0.00 - 20.00	1.0000	1.0000
T13	17	LDF5-50A (7/8 FOAM)	0.00 - 20.00	1.0000	1.0000
T13	19	EW63	0.00 - 20.00	1.0000	1.0000
T13	20	LDF5-50A (7/8 FOAM)	0.00 - 20.00	1.0000	1.0000
T13	21	AVA7-50 (1-5/8 LOW DENS. FOAM)	0.00 - 20.00	1.0000	1.0000
T13	22	AVA7-50 (1-5/8 LOW DENS. FOAM)	0.00 - 20.00	1.0000	1.0000
T13	23	AVA7-50 (1-5/8 LOW DENS. FOAM)	0.00 - 20.00	1.0000	1.0000
T13	24	LDF4-50A (1/2 FOAM)	0.00 - 20.00	1.0000	1.0000
T13	25	LDF5-50A (7/8 FOAM)	0.00 - 20.00	1.0000	1.0000
T13	26	LDF4-50A (1/2 FOAM)	0.00 - 20.00	1.0000	1.0000
T13	27	LDF4-50A (1/2 FOAM)	0.00 - 20.00	1.0000	1.0000

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 19 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by TJL

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K _a No Ice	K _a Ice
T13	28	HYBRIFLEX 1-5/8"	0.00 - 20.00	0.6000	0.6000

Discrete Tower Loads

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C _{AA} Front	C _{AA} Side	Weight
			Horz Lateral	Vert					
			ft	ft	°	ft	ft ²	ft ²	lb
*									
ROHN 6'x15' Boom Gate (1) (Verizon)	A	None			0.0000	160.00	No Ice 17.75 1/2" Ice 21.10 1" Ice 24.50	17.75 21.10 24.50	600.00 75.00 890.00
ROHN 6'x15' Boom Gate (1) (Verizon)	B	None			0.0000	160.00	No Ice 17.75 1/2" Ice 21.10 1" Ice 24.50	17.75 21.10 24.50	600.00 75.00 890.00
ROHN 6'x15' Boom Gate (1) (Verizon)	C	None			0.0000	160.00	No Ice 17.75 1/2" Ice 21.10 1" Ice 24.50	17.75 21.10 24.50	600.00 75.00 890.00
MX06FRO640-02 (Verizon)	A	From Leg	3.00 6.50 0.00		0.0000	160.00	No Ice 12.38 1/2" Ice 12.88 1" Ice 13.38	7.43 7.88 8.33	70.00 151.39 239.61
MX06FRO640-02 (Verizon)	A	From Leg	3.00 5.50 0.00		0.0000	160.00	No Ice 12.38 1/2" Ice 12.88 1" Ice 13.38	7.43 7.88 8.33	70.00 151.39 239.61
XXDWMM-12.5-65-8T-CBR S Panel (Verizon)	A	From Leg	3.00 1.00 0.00		0.0000	160.00	No Ice 4.80 1/2" Ice 5.07 1" Ice 5.35	2.40 2.60 2.81	20.00 59.31 102.70
MT6413-77A (Verizon)	A	From Leg	3.00 -2.00 0.00		0.0000	160.00	No Ice 3.79 1/2" Ice 4.04 1" Ice 4.30	1.46 1.65 1.85	60.00 84.38 112.21
MX06FRO640-02 (Verizon)	A	From Leg	3.00 -6.50 0.00		0.0000	160.00	No Ice 12.38 1/2" Ice 12.88 1" Ice 13.38	7.43 7.88 8.33	70.00 151.39 239.61
MX06FRO640-02 (Verizon)	A	From Leg	3.00 -5.50 0.00		0.0000	160.00	No Ice 12.38 1/2" Ice 12.88 1" Ice 13.38	7.43 7.88 8.33	70.00 151.39 239.61
B2/B66A RRH (Verizon)	A	From Leg	3.00 0.00 0.00		0.0000	160.00	No Ice 2.54 1/2" Ice 2.75 1" Ice 2.97	1.61 1.79 1.98	60.00 80.12 103.35
B5/B13 RRH (Verizon)	A	From Leg	3.00 0.00 0.00		0.0000	160.00	No Ice 1.87 1/2" Ice 2.03 1" Ice 2.21	1.02 1.15 1.29	70.00 86.42 105.50
CBRS RRR-RT4401-48A (Verizon)	A	From Leg	3.00 0.00 0.00		0.0000	160.00	No Ice 0.86 1/2" Ice 0.98 1" Ice 1.10	0.42 0.51 0.61	20.00 26.90 35.60
RF4439d-25A (B2/B66A RRH) (Verizon)	A	From Leg	3.00 0.00 0.00		0.0000	160.00	No Ice 1.88 1/2" Ice 2.05 1" Ice 2.22	1.25 1.39 1.54	75.00 93.34 114.47
RF4461d-13A (Verizon)	A	From Leg	3.00 0.00 0.00		0.0000	160.00	No Ice 1.87 1/2" Ice 2.03 1" Ice 2.21	1.28 1.42 1.57	80.00 98.51 119.81
JAHH-65B-R3B Panel	B	From Leg	3.00		0.0000	160.00	No Ice 9.66	7.71	130.00

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 20 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by T.JL

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C _A A _A		Weight
			Horz	Lateral			Front	Side	
			Vert						
			ft	ft	°	ft	ft ²	ft ²	lb
			ft	ft					
Antenna (Verizon)			6.50			1/2" Ice	10.22	8.53	204.15
JAHH-65B-R3B Panel	B	From Leg	0.00		0.0000	1" Ice	10.79	9.37	289.72
Antenna (Verizon)			3.00			No Ice	9.66	7.71	130.00
XXDWM-12.5-65-8T-CBR S Panel (Verizon)	B	From Leg	5.50			1/2" Ice	10.22	8.53	204.15
MT6413-77A (Verizon)	B	From Leg	0.00			1" Ice	10.79	9.37	289.72
CBC78T-DS-43-2X Diplexer (Verizon)	B	From Leg	3.00		0.0000	No Ice	4.80	2.40	20.00
B2/B66A RRH (Verizon)	B	From Leg	-1.00			1/2" Ice	5.07	2.60	59.31
RF4461d-13A (Verizon)	B	From Leg	0.00			1" Ice	5.35	2.81	102.70
CBR-RRH-RT4401-48A (Verizon)	B	From Leg	3.00		0.0000	No Ice	3.79	1.46	60.00
JAHH-65B-R3B Panel	C	From Leg	-6.00			1/2" Ice	4.04	1.65	84.38
Antenna (Verizon)			0.00			1" Ice	4.30	1.85	112.21
XXDWM-12.5-65-8T-CBR S Panel (Verizon)	C	From Leg	3.00		0.0000	No Ice	0.37	0.51	22.00
MT6413-77A (Verizon)	C	From Leg	0.00			1/2" Ice	0.45	0.60	28.34
CBC78T-DS-43-2X Diplexer (Verizon)	C	From Leg	0.00			1" Ice	0.53	0.70	36.37
B2/B66A RRH (Verizon)	C	From Leg	3.00		0.0000	No Ice	2.54	1.61	60.00
RF4461d-13A (Verizon)	C	From Leg	0.00			1/2" Ice	2.75	1.79	80.12
CBR-RRH-RT4401-48A (Verizon)	C	From Leg	0.00			1" Ice	2.97	1.98	103.35
JAHH-65B-R3B Panel	B	From Leg	3.00		0.0000	No Ice	1.87	1.28	80.00
Antenna (Verizon)			0.00			1/2" Ice	2.03	1.42	98.51
XXDWM-12.5-65-8T-CBR S Panel (Verizon)	B	From Leg	0.00			1" Ice	2.21	1.57	119.81
MT6413-77A (Verizon)	B	From Leg	3.00		0.0000	No Ice	0.86	0.42	20.00
CBC78T-DS-43-2X Diplexer (Verizon)	B	From Leg	0.00			1/2" Ice	0.98	0.51	26.90
B2/B66A RRH (Verizon)	B	From Leg	0.00			1" Ice	1.10	0.61	35.60
RF4461d-13A (Verizon)	B	From Leg	3.00		0.0000	No Ice	9.66	7.71	130.00
CBR-RRH-RT4401-48A (Verizon)	B	From Leg	6.50			1/2" Ice	10.22	8.53	204.15
JAHH-65B-R3B Panel	C	From Leg	0.00			1" Ice	10.79	9.37	289.72
Antenna (Verizon)			3.00		0.0000	No Ice	9.66	7.71	130.00
XXDWM-12.5-65-8T-CBR S Panel (Verizon)	C	From Leg	5.50			1/2" Ice	10.22	8.53	204.15
MT6413-77A (Verizon)	C	From Leg	0.00			1" Ice	10.79	9.37	289.72
CBC78T-DS-43-2X Diplexer (Verizon)	C	From Leg	3.00		0.0000	No Ice	4.80	2.40	20.00
B2/B66A RRH (Verizon)	C	From Leg	-1.00			1/2" Ice	5.07	2.60	59.31
RF4461d-13A (Verizon)	C	From Leg	0.00			1" Ice	5.35	2.81	102.70
CBR-RRH-RT4401-48A (Verizon)	C	From Leg	3.00		0.0000	No Ice	3.79	1.46	60.00
JAHH-65B-R3B Panel	C	From Leg	-6.00			1/2" Ice	4.04	1.65	84.38
Antenna (Verizon)			0.00			1" Ice	4.30	1.85	112.21
XXDWM-12.5-65-8T-CBR S Panel (Verizon)	C	From Leg	3.00		0.0000	No Ice	0.37	0.51	22.00
MT6413-77A (Verizon)	C	From Leg	0.00			1/2" Ice	0.45	0.60	28.34
CBC78T-DS-43-2X Diplexer (Verizon)	C	From Leg	0.00			1" Ice	0.53	0.70	36.37
B2/B66A RRH (Verizon)	C	From Leg	3.00		0.0000	No Ice	2.54	1.61	60.00
RF4461d-13A (Verizon)	C	From Leg	0.00			1/2" Ice	2.75	1.79	80.12
CBR-RRH-RT4401-48A (Verizon)	C	From Leg	0.00			1" Ice	2.97	1.98	103.35
JAHH-65B-R3B Panel	A	From Leg	3.00		0.0000	No Ice	1.87	1.28	80.00
Antenna (Verizon)			0.00			1/2" Ice	2.03	1.42	98.51
XXDWM-12.5-65-8T-CBR S Panel (Verizon)	A	From Leg	0.00			1" Ice	2.21	1.57	119.81
MT6413-77A (Verizon)	A	From Leg	3.00		0.0000	No Ice	0.86	0.42	20.00
CBC78T-DS-43-2X Diplexer (Verizon)	A	From Leg	0.00			1/2" Ice	0.98	0.51	26.90
B2/B66A RRH (Verizon)	A	From Leg	0.00			1" Ice	1.10	0.61	35.60
RF4461d-13A (Verizon)	A	From Leg	3.00		0.0000	No Ice	5.60	2.33	50.00
CBR-RRH-RT4401-48A (Verizon)	A	From Leg	0.00			1/2" Ice	5.92	2.56	81.13
JAHH-65B-R3B Panel	B	From Leg	0.00			1" Ice	6.24	2.79	121.22
Antenna (Verizon)			3.00		0.0000	No Ice	5.60	2.33	50.00
XXDWM-12.5-65-8T-CBR S Panel (Verizon)	B	From Leg	0.00			1/2" Ice	5.92	2.56	81.13
MT6413-77A (Verizon)	B	From Leg	0.00			1" Ice	6.24	2.79	121.22
CBC78T-DS-43-2X Diplexer (Verizon)	A	None			0.0000	No Ice	13.60	13.60	465.00
B2/B66A RRH (Verizon)	A	None				1/2" Ice	18.40	18.40	600.00
RF4461d-13A (Verizon)	A	None				1" Ice	23.20	23.20	735.00
CBR-RRH-RT4401-48A (Verizon)	B	None			0.0000	No Ice	13.60	13.60	465.00

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job	22027.01 - Westport	Page	21 of 73
	Project	180-ft Lattice Tower (CSP #32)	Date	15:45:34 06/11/24
	Client	Verizon	Designed by	TJL

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert	Azimuth Adjustment	Placement	C _{AA} Front	C _{AA} Side	Weight
			ft ft ft	°	ft	ft ²	ft ²	lb
(T-Mobile)						1/2" Ice 18.40	18.40	600.00
LTF12=372 Sector Mount (1)	C	None		0.0000	125.00	1" Ice 23.20	23.20	735.00
(T-Mobile)						No Ice 13.60	13.60	465.00
						1/2" Ice 18.40	18.40	600.00
AIR21 B4A/B2P	A	From Face	3.00	0.0000	125.00	1" Ice 23.20	23.20	735.00
(T-Mobile)			-4.00			No Ice 6.05	4.36	83.00
			0.00			1/2" Ice 6.42	4.70	124.90
AIR21 B4A/B2P	B	From Face	3.00	0.0000	125.00	1" Ice 6.80	5.06	171.93
(T-Mobile)			-4.00			No Ice 6.05	4.36	83.00
			0.00			1/2" Ice 6.42	4.70	124.90
AIR21 B4A/B2P	C	From Face	3.00	0.0000	125.00	1" Ice 6.80	5.06	171.93
(T-Mobile)			-4.00			No Ice 6.05	4.36	83.00
			0.00			1/2" Ice 6.42	4.70	124.90
Generic Twin TMA unit	A	From Face	3.00	0.0000	125.00	1" Ice 6.80	5.06	171.93
(T-Mobile)			0.00			No Ice 0.37	0.96	25.00
			0.00			1/2" Ice 0.46	1.09	32.19
Generic Twin TMA unit	B	From Face	3.00	0.0000	125.00	1" Ice 0.55	1.22	41.21
(T-Mobile)			0.00			No Ice 0.37	0.96	25.00
			0.00			1/2" Ice 0.46	1.09	32.19
Generic Twin TMA unit	C	From Face	3.00	0.0000	125.00	1" Ice 0.55	1.22	41.21
(T-Mobile)			0.00			No Ice 0.37	0.96	25.00
			0.00			1/2" Ice 0.46	1.09	32.19
AIR21 B2A/B4P	A	From Face	3.00	0.0000	125.00	1" Ice 0.55	1.22	41.21
(T-Mobile)			0.00			No Ice 6.05	4.36	83.00
			0.00			1/2" Ice 6.42	4.70	124.90
AIR21 B2A/B4P	B	From Face	3.00	0.0000	125.00	1" Ice 6.80	5.06	171.93
(T-Mobile)			0.00			No Ice 6.05	4.36	83.00
			0.00			1/2" Ice 6.42	4.70	124.90
AIR21 B2A/B4P	C	From Face	3.00	0.0000	125.00	1" Ice 6.80	5.06	171.93
(T-Mobile)			0.00			No Ice 6.05	4.36	83.00
			0.00			1/2" Ice 6.42	4.70	124.90
LNX-6515DS	A	From Face	3.00	0.0000	125.00	1" Ice 6.80	5.06	171.93
(T-Mobile)			4.00			No Ice 11.45	7.70	55.00
			0.00			1/2" Ice 12.06	8.29	120.87
LNX-6515DS	B	From Face	3.00	0.0000	125.00	1" Ice 12.69	8.89	194.41
(T-Mobile)			4.00			No Ice 11.45	7.70	55.00
			0.00			1/2" Ice 12.06	8.29	120.87
LNX-6515DS	C	From Face	3.00	0.0000	125.00	1" Ice 12.69	8.89	194.41
(T-Mobile)			4.00			No Ice 11.45	7.70	55.00
			0.00			1/2" Ice 12.06	8.29	120.87
RRUS-11	A	From Face	3.00	0.0000	125.00	1" Ice 12.69	8.89	194.41
(T-Mobile)			0.00			No Ice 2.57	1.07	50.00
			0.00			1/2" Ice 2.76	1.21	69.57
RRUS-11	B	From Face	3.00	0.0000	125.00	1" Ice 2.97	1.36	92.08
(T-Mobile)			0.00			No Ice 2.57	1.07	50.00
			0.00			1/2" Ice 2.76	1.21	69.57
RRUS-11	C	From Face	3.00	0.0000	125.00	1" Ice 2.97	1.36	92.08
(T-Mobile)			0.00			No Ice 2.57	1.07	50.00
			0.00			1/2" Ice 2.76	1.21	69.57
QD6616-7	A	From Face	3.00	0.0000	133.00	1" Ice 2.97	1.36	92.08
(AT&T)			-6.00			No Ice 13.58	6.80	130.00
			0.00			1/2" Ice 14.08	7.27	213.97
AIR6419	A	From Face	3.00	0.0000	133.00	1" Ice 14.60	7.72	304.84
(AT&T)			0.00			No Ice 4.17	2.02	56.00
			2.00			1/2" Ice 4.44	2.23	85.19
AIR6449	A	From Face	3.00	0.0000	133.00	1" Ice 4.71	2.44	118.11
						No Ice 4.05	2.74	96.00

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job		22027.01 - Westport		Page	22 of 73
	Project		180-ft Lattice Tower (CSP #32)		Date	15:45:34 06/11/24
	Client		Verizon		Designed by	TJL

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C _A A _A Front	C _A A _A Side	Weight
			Horz	Lateral					
(AT&T)			0.00			1/2" Ice	4.32	2.97	129.62
			-2.00			1" Ice	4.59	3.20	167.14
DMP65R-BU6D	A	From Face	3.00	0.0000	133.00	No Ice	12.71	5.62	96.00
(AT&T)			6.00			1/2" Ice	13.21	6.07	169.96
			0.00			1" Ice	13.71	6.53	250.56
QD6616-7	B	From Face	3.00	0.0000	133.00	No Ice	13.58	6.80	130.00
(AT&T)			-6.00			1/2" Ice	14.08	7.27	213.97
			0.00			1" Ice	14.60	7.72	304.84
AIR6419	B	From Face	3.00	0.0000	133.00	No Ice	4.17	2.02	56.00
(AT&T)			0.00			1/2" Ice	4.44	2.23	85.19
			2.00			1" Ice	4.71	2.44	118.11
AIR6449	B	From Face	3.00	0.0000	133.00	No Ice	4.05	2.74	96.00
(AT&T)			0.00			1/2" Ice	4.32	2.97	129.62
			-2.00			1" Ice	4.59	3.20	167.14
DMP65R-BU6D	B	From Face	3.00	0.0000	133.00	No Ice	12.71	5.62	96.00
(AT&T)			6.00			1/2" Ice	13.21	6.07	169.96
			0.00			1" Ice	13.71	6.53	250.56
QD6616-7	C	From Face	3.00	0.0000	133.00	No Ice	13.58	6.80	130.00
(AT&T)			-6.00			1/2" Ice	14.08	7.27	213.97
			0.00			1" Ice	14.60	7.72	304.84
AIR6419	C	From Face	3.00	0.0000	133.00	No Ice	4.17	2.02	56.00
(AT&T)			0.00			1/2" Ice	4.44	2.23	85.19
			2.00			1" Ice	4.71	2.44	118.11
AIR6449	C	From Face	3.00	0.0000	133.00	No Ice	4.05	2.74	96.00
(AT&T)			0.00			1/2" Ice	4.32	2.97	129.62
			-2.00			1" Ice	4.59	3.20	167.14
DMP65R-BU6D	C	From Face	3.00	0.0000	133.00	No Ice	12.71	5.62	96.00
(AT&T)			6.00			1/2" Ice	13.21	6.07	169.96
			0.00			1" Ice	13.71	6.53	250.56
RRUS-32 B66	A	From Face	3.00	0.0000	133.00	No Ice	3.20	1.85	60.00
(AT&T)			6.00			1/2" Ice	3.46	2.08	81.11
			0.00			1" Ice	3.73	2.31	105.42
RRUS-32	A	From Face	3.00	0.0000	133.00	No Ice	3.31	2.42	77.00
(AT&T)			-2.00			1/2" Ice	3.56	2.64	104.93
			0.00			1" Ice	3.81	2.86	136.47
RRUS-32	A	From Face	3.00	0.0000	133.00	No Ice	3.31	2.42	77.00
(AT&T)			-2.00			1/2" Ice	3.56	2.64	104.93
			0.00			1" Ice	3.81	2.86	136.47
RRUS-32 B66	B	From Face	3.00	0.0000	133.00	No Ice	3.20	1.85	60.00
(AT&T)			6.00			1/2" Ice	3.46	2.08	81.11
			0.00			1" Ice	3.73	2.31	105.42
RRUS-32	B	From Face	3.00	0.0000	133.00	No Ice	3.31	2.42	77.00
(AT&T)			-2.00			1/2" Ice	3.56	2.64	104.93
			0.00			1" Ice	3.81	2.86	136.47
RRUS-32	B	From Face	3.00	0.0000	133.00	No Ice	3.31	2.42	77.00
(AT&T)			-2.00			1/2" Ice	3.56	2.64	104.93
			0.00			1" Ice	3.81	2.86	136.47
RRUS-32 B66	C	From Face	3.00	0.0000	133.00	No Ice	3.20	1.85	60.00
(AT&T)			6.00			1/2" Ice	3.46	2.08	81.11
			0.00			1" Ice	3.73	2.31	105.42
RRUS-32	C	From Face	3.00	0.0000	133.00	No Ice	3.31	2.42	77.00
(AT&T)			-2.00			1/2" Ice	3.56	2.64	104.93
			0.00			1" Ice	3.81	2.86	136.47
RRUS-32	C	From Face	3.00	0.0000	133.00	No Ice	3.31	2.42	77.00
(AT&T)			-2.00			1/2" Ice	3.56	2.64	104.93
			0.00			1" Ice	3.81	2.86	136.47
4478 B14	A	From Face	3.00	0.0000	133.00	No Ice	1.84	1.06	60.00

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 23 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by TJL

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C _{AA} Front	C _{AA} Side	Weight
			Horz Lateral	Vert					
(AT&T)			-2.00			1/2" Ice	2.01	1.20	75.88
			0.00			1" Ice	2.19	1.34	94.39
4478 B14	B	From Face	3.00		0.0000	No Ice	1.84	1.06	60.00
(AT&T)			-2.00			1/2" Ice	2.01	1.20	75.88
			0.00			1" Ice	2.19	1.34	94.39
4478 B14	C	From Face	3.00		0.0000	No Ice	1.84	1.06	60.00
(AT&T)			-2.00			1/2" Ice	2.01	1.20	75.88
			0.00			1" Ice	2.19	1.34	94.39
4449 B5/B12	A	From Face	3.00		0.0000	No Ice	1.97	1.41	71.00
(AT&T)			-2.00			1/2" Ice	2.14	1.56	89.51
			0.00			1" Ice	2.33	1.73	110.84
4449 B5/B12	B	From Face	3.00		0.0000	No Ice	1.97	1.41	71.00
(AT&T)			-2.00			1/2" Ice	2.14	1.56	89.51
			0.00			1" Ice	2.33	1.73	110.84
4449 B5/B12	C	From Face	3.00		0.0000	No Ice	1.97	1.41	71.00
(AT&T)			-2.00			1/2" Ice	2.14	1.56	89.51
			0.00			1" Ice	2.33	1.73	110.84
DC6-48-60-18-8F (Squid)	C	From Face	3.00		0.0000	No Ice	1.27	1.27	20.00
Suppressor			0.00			1/2" Ice	1.46	1.46	35.12
(AT&T)			0.00			1" Ice	1.66	1.66	52.57
DC6-48-60-18-8F (Squid)	A	From Face	3.00		0.0000	No Ice	1.27	1.27	20.00
Suppressor			0.00			1/2" Ice	1.46	1.46	35.12
(AT&T)			0.00			1" Ice	1.66	1.66	52.57
DC9	B	From Leg	3.00		0.0000	No Ice	1.91	1.91	20.00
(AT&T)			-2.00			1/2" Ice	2.10	2.10	39.36
			0.00			1" Ice	2.29	2.29	61.70
SitePro VFA14-10	A	None			0.0000	No Ice	30.00	30.00	950.00
(AT&T)						1/2" Ice	35.00	35.00	1400.00
						1" Ice	40.00	40.00	1850.00
SitePro VFA14-10	B	None			0.0000	No Ice	30.00	30.00	950.00
(AT&T)						1/2" Ice	35.00	35.00	1400.00
						1" Ice	40.00	40.00	1850.00
SitePro VFA14-10	C	None			0.0000	No Ice	30.00	30.00	950.00
(AT&T)						1/2" Ice	35.00	35.00	1400.00
						1" Ice	40.00	40.00	1850.00
* CSP									
ANT940Y10-WR	A	From Leg	0.00		0.0000	No Ice	0.19	0.19	2.50
(CSP)			0.00			1/2" Ice	0.34	0.34	3.25
			0.00			1" Ice	0.49	0.49	4.00
ANT940Y10-WR	C	From Leg	0.50		0.0000	No Ice	0.19	0.19	2.50
(CSP - Yagi Antenna)			0.00			1/2" Ice	0.34	0.34	3.25
			0.00			1" Ice	0.49	0.49	4.00
RFI BPS7496-180-14 Panel	A	From Face	4.00		0.0000	No Ice	5.83	3.75	20.00
Antenna			-6.00			1/2" Ice	6.21	4.13	56.42
(CSP-80)			0.00			1" Ice	6.60	4.51	97.99
RFI BPS7496-180-14 Panel	A	From Face	4.00		0.0000	No Ice	5.83	3.75	20.00
Antenna			0.00			1/2" Ice	6.21	4.13	56.42
(CSP-81)			0.00			1" Ice	6.60	4.51	97.99
RFI BPS7496-180-14 Panel	A	From Face	4.00		0.0000	No Ice	5.83	3.75	20.00
Antenna			6.00			1/2" Ice	6.21	4.13	56.42
(CSP-82)			0.00			1" Ice	6.60	4.51	97.99
SitePro1 USF12-396-U	A	From Leg	0.00		0.0000	No Ice	16.23	9.80	491.09
Mount Assembly w/ (3) 96"			0.00			1/2" Ice	22.18	13.27	630.09
Mount Pipes			0.00			1" Ice	28.15	16.68	815.09
(CSP 47, 80, 81, 82)									
432E-831-01T TTA Unit	A	From Leg	4.00		0.0000	No Ice	2.85	0.97	25.00
(Re-Located TMA (CSP))			0.00			1/2" Ice	3.06	1.11	44.70

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job	22027.01 - Westport	Page	24 of 73
	Project	180-ft Lattice Tower (CSP #32)	Date	15:45:34 06/11/24
	Client	Verizon	Designed by	TJL

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C _{AA} Front	C _{AA} Side	Weight	
			Horz	Vert						
			ft	ft	°	ft	ft ²	ft ²	lb	
3' Yagi (CSP)	C	From Leg	0.00		0.0000	169.00	1" Ice	3.28	1.26	67.39
			0.50				No Ice	2.08	2.08	30.95
			0.00				1/2" Ice	3.79	3.79	52.87
			0.00				1" Ice	5.52	5.52	85.27
ANT150D (CSP - 1-Bay Dipole)	A	From Leg	0.00		0.0000	113.00	No Ice	0.80	0.80	5.50
			0.00				1/2" Ice	1.44	1.44	7.15
			0.00				1" Ice	2.08	2.08	8.80
			0.00				No Ice	1.00	1.00	10.00
GPS (DNK-1 / GPS)	C	From Leg	0.00		0.0000	60.00	1/2" Ice	1.50	1.50	15.00
			0.00				1" Ice	2.00	2.00	20.00
			2.00				No Ice	3.42	3.42	110.00
			0.00				1/2" Ice	3.67	3.67	147.19
4' Standoff (DNK-1 / GPS)	C	From Leg	0.00		0.0000	60.00	1" Ice	3.92	3.92	187.07
			0.00				No Ice	12.27	5.72	75.00
			0.00				1/2" Ice	12.76	6.18	147.00
			0.00				1" Ice	13.26	6.64	225.63
FFVV-65B-R2 (Dish - Reserved)	A	From Leg	3.00		0.0000	144.00	No Ice	12.27	5.72	75.00
			-3.00				1/2" Ice	12.76	6.18	147.00
			0.00				1" Ice	13.26	6.64	225.63
			0.00				No Ice	12.27	5.72	75.00
FFVV-65B-R2 (Dish - Reserved)	B	From Leg	3.00		0.0000	144.00	1/2" Ice	12.76	6.18	147.00
			-3.00				1" Ice	13.26	6.64	225.63
			0.00				No Ice	12.27	5.72	75.00
			0.00				1/2" Ice	12.76	6.18	147.00
FFVV-65B-R2 (Dish - Reserved)	C	From Leg	3.00		0.0000	144.00	1" Ice	13.26	6.64	225.63
			-3.00				No Ice	1.98	1.04	65.00
			0.00				1/2" Ice	2.15	1.18	81.85
			0.00				1" Ice	2.33	1.32	101.41
TA08025-B604 (Dish - Reserved)	A	From Leg	3.00		0.0000	144.00	No Ice	1.98	1.04	65.00
			-3.00				1/2" Ice	2.15	1.18	81.85
			0.00				1" Ice	2.33	1.32	101.41
			0.00				No Ice	1.98	1.04	65.00
TA08025-B604 (Dish - Reserved)	B	From Leg	3.00		0.0000	144.00	1/2" Ice	2.15	1.18	81.85
			3.00				1" Ice	2.33	1.32	101.41
			0.00				No Ice	1.98	1.04	65.00
			0.00				1/2" Ice	2.15	1.18	81.85
TA08025-B604 (Dish - Reserved)	C	From Leg	3.00		0.0000	144.00	1" Ice	2.33	1.32	101.41
			3.00				No Ice	1.98	1.04	65.00
			0.00				1/2" Ice	2.15	1.18	81.85
			0.00				1" Ice	2.33	1.32	101.41
TA08025-B605 (Dish - Reserved)	A	From Leg	3.00		0.0000	144.00	No Ice	1.98	1.04	65.00
			3.00				1/2" Ice	2.15	1.34	93.09
			0.00				1" Ice	2.33	1.49	113.96
			0.00				No Ice	1.98	1.20	75.00
TA08025-B605 (Dish - Reserved)	B	From Leg	3.00		0.0000	144.00	1/2" Ice	2.15	1.34	93.09
			3.00				1" Ice	2.33	1.49	113.96
			0.00				No Ice	1.98	1.20	75.00
			0.00				1/2" Ice	2.15	1.34	93.09
TA08025-B605 (Dish - Reserved)	C	From Leg	3.00		0.0000	144.00	1" Ice	2.33	1.49	113.96
			3.00				No Ice	1.98	1.20	75.00
			0.00				1/2" Ice	2.15	1.34	93.09
			0.00				1" Ice	2.33	1.49	113.96
RD1DC-9181-PF-48 (Dish - Reserved)	A	From Leg	3.00		0.0000	144.00	No Ice	1.87	1.07	22.00
			3.00				1/2" Ice	2.04	1.20	38.30
			0.00				1" Ice	2.21	1.35	57.26
			0.00				No Ice	1.87	1.07	22.00
RD1DC-9181-PF-48 (Dish - Reserved)	B	From Leg	3.00		0.0000	144.00	1/2" Ice	2.04	1.20	38.30
			3.00				1" Ice	2.21	1.35	57.26
			0.00				No Ice	1.87	1.07	22.00
			0.00				1/2" Ice	2.04	1.20	38.30
RD1DC-9181-PF-48 (Dish - Reserved)	C	From Leg	3.00		0.0000	144.00	1" Ice	2.21	1.35	57.26
			3.00				No Ice	1.87	1.07	22.00
			0.00				1/2" Ice	2.04	1.20	38.30
			0.00				1" Ice	2.21	1.35	57.26
Commscope MTC3975083 8-ft V-Frame (Dish - Reserved)	A	From Leg	3.00		0.0000	144.00	No Ice	12.00	12.00	360.00
			0.00				1/2" Ice	18.00	18.00	500.00
			0.00				1" Ice	24.00	24.00	640.00
			0.00				No Ice	12.00	12.00	360.00
Commscope MTC3975083 8-ft V-Frame (Dish - Reserved)	B	From Leg	3.00		0.0000	144.00	1/2" Ice	18.00	18.00	500.00
			0.00				1" Ice	24.00	24.00	640.00
			0.00				No Ice	12.00	12.00	360.00
			0.00				1/2" Ice	18.00	18.00	500.00
Commscope MTC3975083 8-ft V-Frame	C	From Leg	3.00		0.0000	144.00	No Ice	12.00	12.00	360.00
			0.00				1/2" Ice	18.00	18.00	500.00

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 25 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by TJL

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment °	Placement ft	C _{AA} Front ft ²	C _{AA} Side ft ²	Weight lb
(Dish - Reserved)			0.00		1" Ice	24.00	24.00	640.00

Dishes

Description	Face or Leg	Dish Type	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment °	3 dB Beam Width °	Elevation ft	Outside Diameter ft	Aperture Area ft ²	Weight lb	
PA6-65AC (DNK-52 / CSP-42)	C	Paraboloid w/Radome	From Leg	1.00 0.00 0.00	-55.0000		177.00	6.00	No Ice 1/2" Ice 1" Ice	28.27 29.05 29.83	90.00 240.00 390.00

222-H Verification Constants

Constant	Value
K _d	0.85
Ice Thickness Importance Factor	1.15
Z _p	900
a	9.5
K _{zmin}	0.85
K _c	n/a
K _i	1
f	1
K _e	1

222-H Section Verification ArRr By Element

Section Elevation ft	Elem. Num.	Size	C	C w/Ice	F a c e	e	e w/Ice	A _r ft ²	A _r w/Ice ft ²	A _r R _r ft ²	A _r R _r w/Ice ft ²
T1 180.00-160.00	1	ROHN 3 STD	45.107	30.78	C	0.139	0.273	5.833	10.350	3.165	6.117
	1	ROHN 3 STD	45.107	30.78	A	0.139	0.273	5.833	10.350	3.165	6.117
	2	ROHN 3 STD	45.107	30.78	C	0.139	0.273	5.833	10.350	3.165	6.117
	2	ROHN 3 STD	45.107	30.78	B	0.139	0.273	5.833	10.350	3.165	6.117
	3	ROHN 3 STD	45.107	30.78	B	0.139	0.273	5.833	10.350	3.165	6.117
	3	ROHN 3 STD	45.107	30.78	A	0.139	0.273	5.833	10.350	3.165	6.117
	4	ROHN 1.5 STD	24.486	22.849	C	0.139	0.273	1.306	3.169	0.740	1.873
	5	ROHN 1.5 STD	24.486	22.849	B	0.139	0.273	1.306	3.169	0.740	1.873
	6	ROHN 1.5 STD	24.486	22.849	A	0.139	0.273	1.306	3.169	0.740	1.873
	7	ROHN 1.5 STD	24.486	22.849	C	0.139	0.273	1.315	3.191	0.745	1.886
	8	ROHN 2 STD	30.608	25.204	C	0.139	0.273	1.518	3.251	0.860	1.921
	9	ROHN 2 STD	30.608	25.204	C	0.139	0.273	1.518	3.251	0.860	1.921

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 26 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by T.JL

Section Elevation	Elem. Num.	Size	C	C w/Ice	F a c e	e	e w/Ice	A _r	A _r w/Ice	A _r R _r	A _r R _r w/Ice
ft								ft ²	ft ²	ft ²	ft ²
	10	ROHN 1.5 STD	24.486	22.849	B	0.139	0.273	1.315	3.191	0.745	1.886
	11	ROHN 2 STD	30.608	25.204	B	0.139	0.273	1.518	3.251	0.860	1.921
	12	ROHN 2 STD	30.608	25.204	B	0.139	0.273	1.518	3.251	0.860	1.921
	13	ROHN 1.5 STD	24.486	22.849	A	0.139	0.273	1.315	3.191	0.745	1.886
	14	ROHN 2 STD	30.608	25.204	A	0.139	0.273	1.518	3.251	0.860	1.921
	15	ROHN 2 STD	30.608	25.204	A	0.139	0.273	1.518	3.251	0.860	1.921
	19	ROHN 1.5 STD	24.486	22.849	C	0.139	0.273	1.311	3.180	0.743	1.879
	20	ROHN 2 STD	30.608	25.204	C	0.139	0.273	1.517	3.247	0.859	1.919
	21	ROHN 2 STD	30.608	25.204	C	0.139	0.273	1.517	3.247	0.859	1.919
	22	ROHN 1.5 STD	24.486	22.849	B	0.139	0.273	1.311	3.180	0.743	1.879
	23	ROHN 2 STD	30.608	25.204	B	0.139	0.273	1.517	3.247	0.859	1.919
	24	ROHN 2 STD	30.608	25.204	B	0.139	0.273	1.517	3.247	0.859	1.919
	25	ROHN 1.5 STD	24.486	22.849	A	0.139	0.273	1.311	3.180	0.743	1.879
	26	ROHN 2 STD	30.608	25.204	A	0.139	0.273	1.517	3.247	0.859	1.919
	27	ROHN 2 STD	30.608	25.204	A	0.139	0.273	1.517	3.247	0.859	1.919
	31	ROHN 2 STD	30.608	25.204	C	0.139	0.273	1.515	3.244	0.858	1.917
	32	ROHN 2 STD	30.608	25.204	C	0.139	0.273	1.515	3.244	0.858	1.917
	33	ROHN 2 STD	30.608	25.204	B	0.139	0.273	1.515	3.244	0.858	1.917
	34	ROHN 2 STD	30.608	25.204	B	0.139	0.273	1.515	3.244	0.858	1.917
	35	ROHN 2 STD	30.608	25.204	A	0.139	0.273	1.515	3.244	0.858	1.917
	36	ROHN 2 STD	30.608	25.204	A	0.139	0.273	1.515	3.244	0.858	1.917
					A		Sum:	24.699	49.722	13.713	29.387
					B			24.699	49.722	13.713	29.387
					C			24.699	49.722	13.713	29.387
					C	0.143	0.265	7.514	11.982	3.727	7.056
T2	40	ROHN 4 STD	57.235	35.104	C	0.143	0.265	7.514	11.982	3.727	7.056
160.00-140.00	40	ROHN 4 STD	57.235	35.104	A	0.143	0.265	7.514	11.982	3.727	7.056
	41	ROHN 4 STD	57.235	35.104	C	0.143	0.265	7.514	11.982	3.727	7.056
	41	ROHN 4 STD	57.235	35.104	B	0.143	0.265	7.514	11.982	3.727	7.056
	42	ROHN 4 STD	57.235	35.104	B	0.143	0.265	7.514	11.982	3.727	7.056
	42	ROHN 4 STD	57.235	35.104	A	0.143	0.265	7.514	11.982	3.727	7.056
	43	ROHN 1.5 STD	24.166	22.385	C	0.143	0.265	1.526	3.676	0.865	2.165
	44	ROHN 2 STD	30.207	24.709	C	0.143	0.265	1.634	3.474	0.926	2.046
	45	ROHN 2 STD	30.207	24.709	C	0.143	0.265	1.634	3.474	0.926	2.046
	46	ROHN 1.5 STD	24.166	22.385	B	0.143	0.265	1.526	3.676	0.865	2.165
	47	ROHN 2 STD	30.207	24.709	B	0.143	0.265	1.634	3.474	0.926	2.046
	48	ROHN 2 STD	30.207	24.709	B	0.143	0.265	1.634	3.474	0.926	2.046
	49	ROHN 1.5 STD	24.166	22.385	A	0.143	0.265	1.526	3.676	0.865	2.165
	50	ROHN 2 STD	30.207	24.709	A	0.143	0.265	1.634	3.474	0.926	2.046
	51	ROHN 2 STD	30.207	24.709	A	0.143	0.265	1.634	3.474	0.926	2.046
	55	ROHN 1.5 STD	24.166	22.385	C	0.143	0.265	1.416	3.411	0.803	2.009
	56	ROHN 2 STD	30.207	24.709	C	0.143	0.265	1.589	3.379	0.901	1.990
	57	ROHN 2 STD	30.207	24.709	C	0.143	0.265	1.589	3.379	0.901	1.990
	58	ROHN 1.5 STD	24.166	22.385	B	0.143	0.265	1.416	3.411	0.803	2.009
	59	ROHN 2 STD	30.207	24.709	B	0.143	0.265	1.589	3.379	0.901	1.990
	60	ROHN 2 STD	30.207	24.709	B	0.143	0.265	1.589	3.379	0.901	1.990
	61	ROHN 1.5 STD	24.166	22.385	A	0.143	0.265	1.416	3.411	0.803	2.009
	62	ROHN 2 STD	30.207	24.709	A	0.143	0.265	1.589	3.379	0.901	1.990
	63	ROHN 2 STD	30.207	24.709	A	0.143	0.265	1.589	3.379	0.901	1.990
	67	ROHN 1.5 STD	24.166	22.385	C	0.143	0.265	1.306	3.146	0.741	1.853
	68	ROHN 2 STD	30.207	24.709	C	0.143	0.265	1.546	3.287	0.876	1.936
	69	ROHN 2 STD	30.207	24.709	C	0.143	0.265	1.546	3.287	0.876	1.936
	70	ROHN 1.5 STD	24.166	22.385	B	0.143	0.265	1.306	3.146	0.741	1.853
	71	ROHN 2 STD	30.207	24.709	B	0.143	0.265	1.546	3.287	0.876	1.936
	72	ROHN 2 STD	30.207	24.709	B	0.143	0.265	1.546	3.287	0.876	1.936
	73	ROHN 1.5 STD	24.166	22.385	A	0.143	0.265	1.306	3.146	0.741	1.853
	74	ROHN 2 STD	30.207	24.709	A	0.143	0.265	1.546	3.287	0.876	1.936
	75	ROHN 2 STD	30.207	24.709	A	0.143	0.265	1.546	3.287	0.876	1.936
					A		Sum:	28.812	54.476	15.269	32.082
					B			28.812	54.476	15.269	32.082

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 27 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by TJL

Section Elevation	Elem. Num.	Size	C	C w/Ice	F a c e	e	e w/Ice	A _r	A _r w/Ice	A _r R _r	A _r R _r w/Ice	
ft								ft ²	ft ²	ft ²	ft ²	
T3 140.00-133.33	79	ROHN 5 EH	70.065	39.791	C	0.151	0.262	28.812	54.476	15.269	32.082	
					C			3.096	4.572	1.391	2.688	
		79	ROHN 5 EH	70.065	39.791	A	0.151	0.262	3.096	4.572	1.391	2.688
		80	ROHN 5 EH	70.065	39.791	C	0.151	0.262	3.096	4.572	1.391	2.688
		80	ROHN 5 EH	70.065	39.791	B	0.151	0.262	3.096	4.572	1.391	2.688
		81	ROHN 5 EH	70.065	39.791	B	0.151	0.262	3.096	4.572	1.391	2.688
		81	ROHN 5 EH	70.065	39.791	A	0.151	0.262	3.096	4.572	1.391	2.688
		82	ROHN 2 STD	29.913	24.348	C	0.151	0.262	2.028	4.291	1.151	2.523
		83	ROHN 2 EH	29.976	24.372	C	0.151	0.262	1.670	3.529	0.948	2.075
		84	ROHN 2 EH	29.976	24.372	C	0.151	0.262	1.670	3.529	0.948	2.075
		85	ROHN 2 STD	29.913	24.348	B	0.151	0.262	2.028	4.291	1.151	2.523
		86	ROHN 2 EH	29.976	24.372	B	0.151	0.262	1.670	3.529	0.948	2.075
		87	ROHN 2 EH	29.976	24.372	B	0.151	0.262	1.670	3.529	0.948	2.075
		88	ROHN 2 STD	29.913	24.348	A	0.151	0.262	2.028	4.291	1.151	2.523
		89	ROHN 2 EH	29.976	24.372	A	0.151	0.262	1.670	3.529	0.948	2.075
		90	ROHN 2 EH	29.976	24.372	A	0.151	0.262	1.670	3.529	0.948	2.075
						A		Sum:	11.559	20.494	5.828	12.050
						B			11.559	20.494	5.828	12.050
						C			11.559	20.494	5.828	12.050
	T4 133.33-126.67	94	ROHN 5 EH	69.697	39.518	C	0.145	0.253	3.096	4.564	1.388	2.673
		94	ROHN 5 EH	69.697	39.518	A	0.145	0.253	3.096	4.564	1.388	2.673
		95	ROHN 5 EH	69.697	39.518	C	0.145	0.253	3.096	4.564	1.388	2.673
		95	ROHN 5 EH	69.697	39.518	B	0.145	0.253	3.096	4.564	1.388	2.673
		96	ROHN 5 EH	69.697	39.518	B	0.145	0.253	3.096	4.564	1.388	2.673
		96	ROHN 5 EH	69.697	39.518	A	0.145	0.253	3.096	4.564	1.388	2.673
		97	ROHN 2 STD	29.756	24.156	C	0.145	0.253	2.165	4.570	1.228	2.676
		98	ROHN 2 STD	29.756	24.156	B	0.145	0.253	2.165	4.570	1.228	2.676
		99	ROHN 2 STD	29.756	24.156	A	0.145	0.253	2.165	4.570	1.228	2.676
		100	ROHN 2 EH	29.818	24.18	C	0.145	0.253	1.717	3.621	0.974	2.121
		101	ROHN 2 EH	29.818	24.18	C	0.145	0.253	1.717	3.621	0.974	2.121
		102	ROHN 2 EH	29.818	24.18	B	0.145	0.253	1.717	3.621	0.974	2.121
		103	ROHN 2 EH	29.818	24.18	B	0.145	0.253	1.717	3.621	0.974	2.121
		104	ROHN 2 EH	29.818	24.18	A	0.145	0.253	1.717	3.621	0.974	2.121
		105	ROHN 2 EH	29.818	24.18	A	0.145	0.253	1.717	3.621	0.974	2.121
						A		Sum:	11.792	20.941	5.951	12.264
						B			11.792	20.941	5.951	12.264
					C			11.792	20.941	5.951	12.264	
T5 126.67-120.00	109	ROHN 5 EH	69.312	39.234	C	0.14	0.244	3.096	4.557	1.386	2.659	
		109	ROHN 5 EH	69.312	39.234	A	0.14	0.244	3.096	4.557	1.386	2.659
		110	ROHN 5 EH	69.312	39.234	C	0.14	0.244	3.096	4.557	1.386	2.659
		110	ROHN 5 EH	69.312	39.234	B	0.14	0.244	3.096	4.557	1.386	2.659
		111	ROHN 5 EH	69.312	39.234	B	0.14	0.244	3.096	4.557	1.386	2.659
		111	ROHN 5 EH	69.312	39.234	A	0.14	0.244	3.096	4.557	1.386	2.659
		112	ROHN 2 STD	29.591	23.956	C	0.14	0.244	2.303	4.847	1.305	2.829
		113	ROHN 2 STD	29.591	23.956	B	0.14	0.244	2.303	4.847	1.305	2.829
		114	ROHN 2 STD	29.591	23.956	A	0.14	0.244	2.303	4.847	1.305	2.829
		115	ROHN 2 XXS	29.591	23.956	C	0.14	0.244	1.763	3.710	0.999	2.165
		116	ROHN 2 XXS	29.591	23.956	C	0.14	0.244	1.763	3.710	0.999	2.165
		117	ROHN 2 XXS	29.591	23.956	B	0.14	0.244	1.763	3.710	0.999	2.165
		118	ROHN 2 XXS	29.591	23.956	B	0.14	0.244	1.763	3.710	0.999	2.165
		119	ROHN 2 XXS	29.591	23.956	A	0.14	0.244	1.763	3.710	0.999	2.165
	120	ROHN 2 XXS	29.591	23.956	A	0.14	0.244	1.763	3.710	0.999	2.165	
					A		Sum:	12.020	21.380	6.074	12.478	
					B			12.020	21.380	6.074	12.478	
					C			12.020	21.380	6.074	12.478	
T6 120.00-100.00	124	ROHN 6 EHS	81.556	43.651	C	0.133	0.215	11.065	15.398	4.541	8.888	

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 28 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by TJL

Section Elevation	Elem. Num.	Size	C	C w/Ice	F a c e	e	e w/Ice	A _r	A _r w/Ice	A _r R _r	A _r R _r w/Ice
ft								ft ²	ft ²	ft ²	ft ²
	124	ROHN 6 EHS	81.556	43.651	A	0.133	0.215	11.065	15.398	4.541	8.888
	125	ROHN 6 EHS	81.556	43.651	C	0.133	0.215	11.065	15.398	4.541	8.888
	125	ROHN 6 EHS	81.556	43.651	B	0.133	0.215	11.065	15.398	4.541	8.888
	126	ROHN 6 EHS	81.556	43.651	B	0.133	0.215	11.065	15.398	4.541	8.888
	126	ROHN 6 EHS	81.556	43.651	A	0.133	0.215	11.065	15.398	4.541	8.888
	127	ROHN 2 STD	29.237	23.528	C	0.133	0.215	2.645	5.534	1.497	3.195
	128	Pipe 2.5 XXS	35.392	25.896	C	0.133	0.215	2.889	5.496	1.635	3.172
	129	Pipe 2.5 XXS	35.392	25.896	C	0.133	0.215	2.889	5.496	1.635	3.172
	130	ROHN 2 STD	29.237	23.528	B	0.133	0.215	2.645	5.534	1.497	3.195
	131	Pipe 2.5 XXS	35.392	25.896	B	0.133	0.215	2.889	5.496	1.635	3.172
	132	Pipe 2.5 XXS	35.392	25.896	B	0.133	0.215	2.889	5.496	1.635	3.172
	133	ROHN 2 STD	29.237	23.528	A	0.133	0.215	2.645	5.534	1.497	3.195
	134	Pipe 2.5 XXS	35.392	25.896	A	0.133	0.215	2.889	5.496	1.635	3.172
	135	Pipe 2.5 XXS	35.392	25.896	A	0.133	0.215	2.889	5.496	1.635	3.172
	139	ROHN 2 STD	29.237	23.528	C	0.133	0.215	2.422	5.069	1.371	2.926
	140	Pipe 2.5 XXS	35.392	25.896	C	0.133	0.215	2.804	5.334	1.587	3.079
	141	Pipe 2.5 XXS	35.392	25.896	C	0.133	0.215	2.804	5.334	1.587	3.079
	142	ROHN 2 STD	29.237	23.528	B	0.133	0.215	2.422	5.069	1.371	2.926
	143	Pipe 2.5 XXS	35.392	25.896	B	0.133	0.215	2.804	5.334	1.587	3.079
	144	Pipe 2.5 XXS	35.392	25.896	B	0.133	0.215	2.804	5.334	1.587	3.079
	145	ROHN 2 STD	29.237	23.528	A	0.133	0.215	2.422	5.069	1.371	2.926
	146	Pipe 2.5 XXS	35.392	25.896	A	0.133	0.215	2.804	5.334	1.587	3.079
	147	Pipe 2.5 XXS	35.392	25.896	A	0.133	0.215	2.804	5.334	1.587	3.079
					A		Sum:	38.583	63.059	18.396	36.398
					B			38.583	63.059	18.396	36.398
					C			38.583	63.059	18.396	36.398
T7 100.00-90.00	151	ROHN 6 EH	80.307	42.807	C	0.131	0.206	5.537	7.673	2.265	4.416
	151	ROHN 6 EH	80.307	42.807	A	0.131	0.206	5.537	7.673	2.265	4.416
	152	ROHN 6 EH	80.307	42.807	C	0.131	0.206	5.537	7.673	2.265	4.416
	152	ROHN 6 EH	80.307	42.807	B	0.131	0.206	5.537	7.673	2.265	4.416
	153	ROHN 6 EH	80.307	42.807	B	0.131	0.206	5.537	7.673	2.265	4.416
	153	ROHN 6 EH	80.307	42.807	A	0.131	0.206	5.537	7.673	2.265	4.416
	154	ROHN 2 STD	28.789	22.992	C	0.131	0.206	2.868	5.955	1.623	3.427
	155	ROHN 3 STD	42.426	28.237	C	0.131	0.206	3.643	6.303	2.011	3.628
	156	ROHN 3 STD	42.426	28.237	C	0.131	0.206	3.643	6.303	2.011	3.628
	157	ROHN 2 STD	28.789	22.992	B	0.131	0.206	2.868	5.955	1.623	3.427
	158	ROHN 3 STD	42.426	28.237	B	0.131	0.206	3.643	6.303	2.011	3.628
	159	ROHN 3 STD	42.426	28.237	B	0.131	0.206	3.643	6.303	2.011	3.628
	160	ROHN 2 STD	28.789	22.992	A	0.131	0.206	2.868	5.955	1.623	3.427
	161	ROHN 3 STD	42.426	28.237	A	0.131	0.206	3.643	6.303	2.011	3.628
	162	ROHN 3 STD	42.426	28.237	A	0.131	0.206	3.643	6.303	2.011	3.628
					A		Sum:	21.227	33.908	10.175	19.516
					B			21.227	33.908	10.175	19.516
					C			21.227	33.908	10.175	19.516
T8 90.00-80.00	166	ROHN 6 EH	79.372	42.178	C	0.124	0.195	5.537	7.650	2.247	4.389
	166	ROHN 6 EH	79.372	42.178	A	0.124	0.195	5.537	7.650	2.247	4.389
	167	ROHN 6 EH	79.372	42.178	C	0.124	0.195	5.537	7.650	2.247	4.389
	167	ROHN 6 EH	79.372	42.178	B	0.124	0.195	5.537	7.650	2.247	4.389
	168	ROHN 6 EH	79.372	42.178	B	0.124	0.195	5.537	7.650	2.247	4.389
	168	ROHN 6 EH	79.372	42.178	A	0.124	0.195	5.537	7.650	2.247	4.389
	169	ROHN 2 STD	28.454	22.594	C	0.124	0.195	3.129	6.459	1.769	3.705
	170	ROHN 2 STD	28.454	22.594	B	0.124	0.195	3.129	6.459	1.769	3.705
	171	ROHN 2 STD	28.454	22.594	A	0.124	0.195	3.129	6.459	1.769	3.705
	172	ROHN 3 STD	41.933	27.778	C	0.124	0.195	3.773	6.498	2.088	3.728
	173	ROHN 3 STD	41.933	27.778	C	0.124	0.195	3.773	6.498	2.088	3.728
	174	ROHN 3 STD	41.933	27.778	B	0.124	0.195	3.773	6.498	2.088	3.728
	175	ROHN 3 STD	41.933	27.778	B	0.124	0.195	3.773	6.498	2.088	3.728
	176	ROHN 3 STD	41.933	27.778	A	0.124	0.195	3.773	6.498	2.088	3.728
	177	ROHN 3 STD	41.933	27.778	A	0.124	0.195	3.773	6.498	2.088	3.728
					A		Sum:	21.747	34.754	10.439	19.938

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 29 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by TJL

Section Elevation	Elem. Num.	Size	C	C w/Ice	F a c e	e	e w/Ice	A _r	A _r w/Ice	A _r R _r	A _r R _r w/Ice
ft								ft ²	ft ²	ft ²	ft ²
T9 80.00-60.00	184	ROHN 2.5 STD	33.748	24.175	C	0.14	0.199	21.747	34.754	10.439	19.938
	185	ROHN 3 STD	41.084	26.997	C	0.14	0.199	21.747	34.754	10.439	19.938
	186	ROHN 3 STD	41.084	26.997	C	0.14	0.199	4.360	8.120	2.470	4.663
	187	ROHN 2.5 STD	33.748	24.175	B	0.14	0.199	3.995	6.825	2.231	3.919
	188	ROHN 3 STD	41.084	26.997	B	0.14	0.199	3.995	6.825	2.231	3.919
	189	ROHN 3 STD	41.084	26.997	B	0.14	0.199	3.995	6.825	2.231	3.919
	190	ROHN 2.5 STD	33.748	24.175	A	0.14	0.199	4.360	8.120	2.470	4.663
	191	ROHN 3 STD	41.084	26.997	A	0.14	0.199	3.995	6.825	2.231	3.919
	192	ROHN 3 STD	41.084	26.997	A	0.14	0.199	3.995	6.825	2.231	3.919
	196	ROHN 2.5 STD	33.748	24.175	C	0.14	0.199	4.060	7.562	2.301	4.343
	197	ROHN 3 STD	41.084	26.997	C	0.14	0.199	3.862	6.599	2.157	3.789
	198	ROHN 3 STD	41.084	26.997	C	0.14	0.199	3.862	6.599	2.157	3.789
	199	ROHN 2.5 STD	33.748	24.175	B	0.14	0.199	4.060	7.562	2.301	4.343
	200	ROHN 3 STD	41.084	26.997	B	0.14	0.199	3.862	6.599	2.157	3.789
	201	ROHN 3 STD	41.084	26.997	B	0.14	0.199	3.862	6.599	2.157	3.789
	202	ROHN 2.5 STD	33.748	24.175	A	0.14	0.199	4.060	7.562	2.301	4.343
	203	ROHN 3 STD	41.084	26.997	A	0.14	0.199	3.862	6.599	2.157	3.789
	204	ROHN 3 STD	41.084	26.997	A	0.14	0.199	3.862	6.599	2.157	3.789
					A		Sum:	24.135	42.530	13.546	24.424
					B			24.135	42.530	13.546	24.424
				C			24.135	42.530	13.546	24.424	
T10 60.00-40.00	211	ROHN 2.5 STD	32.573	22.976	C	0.129	0.184	4.959	9.094	2.805	5.200
	212	ROHN 3 EH	39.655	25.7	C	0.129	0.184	4.269	7.193	2.404	4.113
	213	ROHN 3 EH	39.655	25.7	C	0.129	0.184	4.269	7.193	2.404	4.113
	214	ROHN 2.5 STD	32.573	22.976	B	0.129	0.184	4.959	9.094	2.805	5.200
	215	ROHN 3 EH	39.655	25.7	B	0.129	0.184	4.269	7.193	2.404	4.113
	216	ROHN 3 EH	39.655	25.7	B	0.129	0.184	4.269	7.193	2.404	4.113
	217	ROHN 2.5 STD	32.573	22.976	A	0.129	0.184	4.959	9.094	2.805	5.200
	218	ROHN 3 EH	39.655	25.7	A	0.129	0.184	4.269	7.193	2.404	4.113
	219	ROHN 3 EH	39.655	25.7	A	0.129	0.184	4.269	7.193	2.404	4.113
	223	ROHN 2.5 STD	32.573	22.976	C	0.129	0.184	4.659	8.545	2.636	4.886
	224	ROHN 3 EH	39.655	25.7	C	0.129	0.184	4.130	6.960	2.326	3.980
	225	ROHN 3 EH	39.655	25.7	C	0.129	0.184	4.130	6.960	2.326	3.980
	226	ROHN 2.5 STD	32.573	22.976	B	0.129	0.184	4.659	8.545	2.636	4.886
	227	ROHN 3 EH	39.655	25.7	B	0.129	0.184	4.130	6.960	2.326	3.980
	228	ROHN 3 EH	39.655	25.7	B	0.129	0.184	4.130	6.960	2.326	3.980
	229	ROHN 2.5 STD	32.573	22.976	A	0.129	0.184	4.659	8.545	2.636	4.886
	230	ROHN 3 EH	39.655	25.7	A	0.129	0.184	4.130	6.960	2.326	3.980
231	ROHN 3 EH	39.655	25.7	A	0.129	0.184	4.130	6.960	2.326	3.980	
				A		Sum:	26.417	45.945	14.901	26.273	
				B			26.417	45.945	14.901	26.273	
				C			26.417	45.945	14.901	26.273	
T11 40.00-30.00	238	ROHN 2.5 STD	31.373	21.777	C	0.123	0.174	5.258	9.490	2.973	5.413
	239	ROHN 3 EH	38.193	24.4	C	0.123	0.174	4.410	7.326	2.493	4.179
	240	ROHN 3 EH	38.193	24.4	C	0.123	0.174	4.410	7.326	2.493	4.179
	241	ROHN 2.5 STD	31.373	21.777	B	0.123	0.174	5.258	9.490	2.973	5.413
	242	ROHN 3 EH	38.193	24.4	B	0.123	0.174	4.410	7.326	2.493	4.179
	243	ROHN 3 EH	38.193	24.4	B	0.123	0.174	4.410	7.326	2.493	4.179
	244	ROHN 2.5 STD	31.373	21.777	A	0.123	0.174	5.258	9.490	2.973	5.413
	245	ROHN 3 EH	38.193	24.4	A	0.123	0.174	4.410	7.326	2.493	4.179
	246	ROHN 3 EH	38.193	24.4	A	0.123	0.174	4.410	7.326	2.493	4.179
					A		Sum:	14.079	24.142	7.959	13.771
				B			14.079	24.142	7.959	13.771	
				C			14.079	24.142	7.959	13.771	
T12 30.00-20.00	253	ROHN 2.5 EH	30.281	20.709	C	0.119	0.168	5.558	9.882	3.141	5.629
	254	ROHN 2.5 EH	30.281	20.709	B	0.119	0.168	5.558	9.882	3.141	5.629
	255	ROHN 2.5 EH	30.281	20.709	A	0.119	0.168	5.558	9.882	3.141	5.629
	256	ROHN 3 EH	36.864	23.241	C	0.119	0.168	4.555	7.466	2.574	4.252

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 30 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by T.J.L

Section Elevation ft	Elem. Num.	Size	C	C w/Ice	F a c e	e	e w/Ice	A _r ft ²	A _r w/Ice ft ²	A _r R _r ft ²	A _r R _r w/Ice ft ²
T13 20.00-0.00	257	ROHN 3 EH	36.864	23.241	C	0.119	0.168	4.555	7.466	2.574	4.252
	258	ROHN 3 EH	36.864	23.241	B	0.119	0.168	4.555	7.466	2.574	4.252
	259	ROHN 3 EH	36.864	23.241	B	0.119	0.168	4.555	7.466	2.574	4.252
	260	ROHN 3 EH	36.864	23.241	A	0.119	0.168	4.555	7.466	2.574	4.252
	261	ROHN 3 EH	36.864	23.241	A	0.119	0.168	4.555	7.466	2.574	4.252
					A		Sum:	14.667	24.813	8.288	14.133
					B			14.667	24.813	8.288	14.133
					C			14.667	24.813	8.288	14.133
	268	P3.5x.226	39.951	23.207	C	0.108	0.148	8.153	12.313	4.570	6.986
	269	ROHN 3 EH	34.957	21.286	C	0.108	0.148	6.913	10.944	3.903	6.209
	270	ROHN 1.5 STD	18.977	15.14	C	0.108	0.148	0.940	1.949	0.531	1.106
	271	ROHN 2 STD	23.721	16.965	C	0.108	0.148	2.132	3.965	1.204	2.249
	272	ROHN 3 EH	34.957	21.286	C	0.108	0.148	6.913	10.944	3.903	6.209
	273	ROHN 1.5 STD	18.977	15.14	C	0.108	0.148	0.940	1.949	0.531	1.106
	274	ROHN 2 STD	23.721	16.965	C	0.108	0.148	2.132	3.965	1.204	2.249
	275	P3.5x.226	39.951	23.207	B	0.108	0.148	8.153	12.313	4.570	6.986
	276	ROHN 3 EH	34.957	21.286	B	0.108	0.148	6.913	10.944	3.903	6.209
	277	ROHN 1.5 STD	18.977	15.14	B	0.108	0.148	0.940	1.949	0.531	1.106
	278	ROHN 2 STD	23.721	16.965	B	0.108	0.148	2.132	3.965	1.204	2.249
	279	ROHN 3 EH	34.957	21.286	B	0.108	0.148	6.913	10.944	3.903	6.209
	280	ROHN 1.5 STD	18.977	15.14	B	0.108	0.148	0.940	1.949	0.531	1.106
	281	ROHN 2 STD	23.721	16.965	B	0.108	0.148	2.132	3.965	1.204	2.249
	283	P3.5x.226	39.951	23.207	A	0.108	0.148	8.153	12.313	4.570	6.986
	284	ROHN 3 EH	34.957	21.286	A	0.108	0.148	6.913	10.944	3.903	6.209
	285	ROHN 1.5 STD	18.977	15.14	A	0.108	0.148	0.940	1.949	0.531	1.106
	286	ROHN 2 STD	23.721	16.965	A	0.108	0.148	2.132	3.965	1.204	2.249
	287	ROHN 3 EH	34.957	21.286	A	0.108	0.148	6.913	10.944	3.903	6.209
	288	ROHN 1.5 STD	18.977	15.14	A	0.108	0.148	0.940	1.949	0.531	1.106
	289	ROHN 2 STD	23.721	16.965	A	0.108	0.148	2.132	3.965	1.204	2.249
					A		Sum:	28.122	46.029	15.844	26.114
					B			28.122	46.029	15.844	26.114
					C			28.122	46.029	15.844	26.114

222-H Section Verification Tables - No Ice

Section Elevation ft	z _{wind} ft	z _{ice} ft	K _s	K _h	K _z	t _z in	q _z psf	F a c e	e	A _r R _r ft ²
T1 180.00-160.00	170.00		1.415	1	1		52	A	0.139	13.713
								B	0.139	13.713
								C	0.139	13.713
T2 160.00-140.00	150.00		1.378	1	1		51	A	0.143	15.269
								B	0.143	15.269
								C	0.143	15.269
T3 140.00-133.33	136.67		1.352	1	1		50	A	0.151	5.828
								B	0.151	5.828
								C	0.151	5.828
T4 133.33-126.67	130.00		1.337	1	1		49	A	0.145	5.951
								B	0.145	5.951
								C	0.145	5.951
T5 126.67-120.00	123.33		1.323	1	1		49	A	0.14	6.074
								B	0.14	6.074
								C	0.14	6.074

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 31 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by TJL

Section Elevation ft	z_{wind} ft	z_{ice} ft	K_z	K_b	K_{zt}	t_z in	q_z psf	F_{ac} e	e	$A_e R_e$ ft ²
T6 120.00-100.00	110.00		1.291	1	1		47	C	0.14	6.074
								A	0.133	18.396
								B	0.133	18.396
T7 100.00-90.00	95.00		1.252	1	1		46	C	0.133	18.396
								A	0.131	10.175
								B	0.131	10.175
T8 90.00-80.00	85.00		1.223	1	1		45	C	0.131	10.175
								A	0.124	10.439
								B	0.124	10.439
T9 80.00-60.00	70.00		1.174	1	1		43	C	0.124	10.439
								A	0.14	13.546
								B	0.14	13.546
T10 60.00-40.00	50.00		1.094	1	1		40	C	0.14	13.546
								A	0.129	14.901
								B	0.129	14.901
T11 40.00-30.00	35.00		1.015	1	1		37	C	0.129	14.901
								A	0.123	7.959
								B	0.123	7.959
T12 30.00-20.00	25.00		0.945	1	1		35	C	0.123	7.959
								A	0.119	8.288
								B	0.119	8.288
T13 20.00-0.00	10.00		0.85	1	1		31	C	0.119	8.288
								A	0.108	15.844
								B	0.108	15.844
								C	0.108	15.844

222-H Section Verification Tables - Ice

Section Elevation ft	z_{wind} ft	z_{ice} ft	K_z	K_b	K_{zt}	t_z in	q_z psf	F_{ac} e	e	$A_e R_e$ ft ²
T1 180.00-160.00	170.00	170.00	1.415	1	1	1.3549	8	A	0.273	29.387
								B	0.273	29.387
								C	0.273	29.387
T2 160.00-140.00	150.00	150.00	1.378	1	1	1.3380	7	A	0.265	32.082
								B	0.265	32.082
								C	0.265	32.082
T3 140.00-133.33	136.67	136.67	1.352	1	1	1.3256	7	A	0.262	12.050
								B	0.262	12.050
								C	0.262	12.050
T4 133.33-126.67	130.00	130.00	1.337	1	1	1.3190	7	A	0.253	12.264
								B	0.253	12.264
								C	0.253	12.264
T5 126.67-120.00	123.33	123.33	1.323	1	1	1.3121	7	A	0.244	12.478
								B	0.244	12.478
								C	0.244	12.478
T6 120.00-100.00	110.00	110.00	1.291	1	1	1.2971	7	A	0.215	36.398
								B	0.215	36.398
								C	0.215	36.398
T7 100.00-90.00	95.00	95.00	1.252	1	1	1.2783	7	A	0.206	19.516
								B	0.206	19.516
								C	0.206	19.516
T8 90.00-80.00	85.00	85.00	1.223	1	1	1.2641	7	A	0.195	19.938
								B	0.195	19.938
								C	0.195	19.938
T9 80.00-60.00	70.00	70.00	1.174	1	1	1.2398	6	A	0.199	24.424

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 32 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by TJL

Section Elevation ft	z_{wind} ft	z_{ice} ft	K_z	K_h	K_{st}	t_z in	q_z psf	F a c e	e	$A_r R_r$ ft ²		
T10 60.00-40.00	50.00	50.00	1.094	1	1	1,1988	6	B	0.199	24.424		
								C	0.199	24.424		
								A	0.184	26.273		
T11 40.00-30.00	35.00	35.00	1.015	1	1	1,1568	6	B	0.184	26.273		
								C	0.184	26.273		
								A	0.174	13.771		
T12 30.00-20.00	25.00	25.00	0.945	1	1	1,1185	5	B	0.174	13.771		
								C	0.174	13.771		
								A	0.168	14.133		
T13 20.00-0.00	10.00	10.00	0.85	1	1	1.0206	5	B	0.168	14.133		
								C	0.168	14.133		
								A	0.148	26.114		
										B	0.148	26.114
										C	0.148	26.114

222-H Section Verification Tables - Service

Section Elevation ft	z_{wind} ft	z_{ice} ft	K_z	K_h	K_{st}	t_z in	q_z psf	F a c e	e	$A_r R_r$ ft ²
T1 180.00-160.00	170.00		1.415	1	1		11	A	0.139	13.993
								B	0.139	13.993
								C	0.139	13.993
T2 160.00-140.00	150.00		1.378	1	1		11	A	0.143	16.334
								B	0.143	16.334
								C	0.143	16.334
T3 140.00-133.33	136.67		1.352	1	1		11	A	0.151	6.561
								B	0.151	6.561
								C	0.151	6.561
T4 133.33-126.67	130.00		1.337	1	1		10	A	0.145	6.687
								B	0.145	6.687
								C	0.145	6.687
T5 126.67-120.00	123.33		1.323	1	1		10	A	0.14	6.810
								B	0.14	6.810
								C	0.14	6.810
T6 120.00-100.00	110.00		1.291	1	1		10	A	0.133	21.840
								B	0.133	21.840
								C	0.133	21.840
T7 100.00-90.00	95.00		1.252	1	1		10	A	0.131	12.011
								B	0.131	12.011
								C	0.131	12.011
T8 90.00-80.00	85.00		1.223	1	1		10	A	0.124	12.296
								B	0.124	12.296
								C	0.124	12.296
T9 80.00-60.00	70.00		1.174	1	1		9	A	0.14	13.674
								B	0.14	13.674
								C	0.14	13.674
T10 60.00-40.00	50.00		1.094	1	1		9	A	0.129	14.945
								B	0.129	14.945
								C	0.129	14.945
T11 40.00-30.00	35.00		1.015	1	1		8	A	0.123	7.959
								B	0.123	7.959
								C	0.123	7.959
T12 30.00-20.00	25.00		0.945	1	1		7	A	0.119	8.288
								B	0.119	8.288
								C	0.119	8.288

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 33 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by TJL

Section Elevation	z_{wind}	z_{ice}	K_z	K_b	K_{zt}	t_z	q_z	F_a	e	A_{R_e}
ft	ft	ft				in	psf	c		ft ²
T13 20.00-0.00	10.00		0.85	1	1		7	A	0.108	15.877
								B	0.108	15.877
								C	0.108	15.877

Tower Pressures - No Ice

$G_H = 0.850$

Section Elevation	z	K_z	q_z	A_G	F_a	A_F	A_R	A_{leg}	Leg %	C_{AA} In Face	C_{AA} Out Face
ft	ft		psf	ft ²	c	ft ²	ft ²	ft ²	%	ft ²	ft ²
T1 180.00-160.00	170.00	1.415	52	177.503	A	0.000	24.699	11.667	47.24	15.281	0.000
					B	0.000	24.699		47.24	0.000	0.000
					C	0.000	24.699		47.24	0.000	0.000
T2 160.00-140.00	150.00	1.378	51	200.850	A	0.000	28.812	15.027	52.16	32.847	0.000
					B	0.000	28.812		52.16	0.000	0.000
					C	0.000	28.812		52.16	0.000	0.000
T3 140.00-133.33	136.67	1.352	50	76.803	A	0.000	11.559	6.192	53.57	10.949	0.000
					B	0.000	11.559		53.57	3.960	0.000
					C	0.000	11.559		53.57	0.000	0.000
T4 133.33-126.67	130.00	1.337	49	81.431	A	0.000	11.792	6.192	52.51	10.949	0.000
					B	0.000	11.792		52.51	14.711	0.000
					C	0.000	11.792		52.51	0.000	0.000
T5 126.67-120.00	123.33	1.323	49	86.060	A	0.000	12.020	6.192	51.52	10.949	0.000
					B	0.000	12.020		51.52	33.451	0.000
					C	0.000	12.020		51.52	0.000	0.000
T6 120.00-100.00	110.00	1.291	47	289.399	A	0.000	38.583	22.130	57.36	33.666	0.000
					B	0.000	38.583		57.36	118.527	0.000
					C	0.000	38.583		57.36	0.000	0.000
T7 100.00-90.00	95.00	1.252	46	162.540	A	0.000	21.227	11.074	52.17	17.054	0.000
					B	0.000	21.227		52.17	59.264	0.000
					C	0.000	21.227		52.17	0.000	0.000
T8 90.00-80.00	85.00	1.223	45	175.715	A	0.000	21.747	11.074	50.92	17.054	0.000
					B	0.000	21.747		50.92	59.264	0.000
					C	0.000	21.747		50.92	0.000	0.000
T9 80.00-60.00	70.00	1.174	43	390.971	A	30.496	24.135	30.496	55.82	34.170	0.000
					B	30.496	24.135		55.82	118.527	0.000
					C	30.496	24.135		55.82	0.000	0.000
T10 60.00-40.00	50.00	1.094	40	440.971	A	30.496	26.417	30.496	53.58	35.367	0.000
					B	30.496	26.417		53.58	118.527	0.000
					C	30.496	26.417		53.58	0.000	0.000
T11 40.00-30.00	35.00	1.015	37	239.236	A	15.248	14.079	15.248	51.99	17.684	0.000
					B	15.248	14.079		51.99	59.264	0.000
					C	15.248	14.079		51.99	0.000	0.000
T12 30.00-20.00	25.00	0.945	35	251.736	A	15.248	14.667	15.248	50.97	17.684	0.000
					B	15.248	14.667		50.97	59.264	0.000
					C	15.248	14.667		50.97	0.000	0.000
T13 20.00-0.00	10.00	0.85	31	541.368	A	30.078	28.122	30.078	51.68	35.367	0.000
					B	30.078	28.122		51.68	118.527	0.000
					C	30.078	28.122		51.68	0.000	0.000

Tower Pressure - With Ice

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 34 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by T.J.L.

$$G_H = 0.850$$

Section Elevation ft	z ft	K _Z	q _z psf	t _z in	A _G ft ²	F a c e	A _F ft ²	A _R ft ²	A _{leg} ft ²	Leg %	C _A A _A In Face ft ²	C _A A _A Out Face ft ²
T1 180.00-160.00	170.00	1.415	8	1.3549	182.020	A	0.000	49.722	20.699	41.63	41.294	0.000
						B	0.000	49.722		41.63	0.000	0.000
						C	0.000	49.722		41.63	0.000	0.000
T2 160.00-140.00	150.00	1.378	7	1.3380	205.316	A	0.000	54.476	23.963	43.99	92.227	0.000
						B	0.000	54.476		43.99	0.000	0.000
						C	0.000	54.476		43.99	0.000	0.000
T3 140.00-133.33	136.67	1.352	7	1.3256	78.277	A	0.000	20.494	9.143	44.62	30.582	0.000
						B	0.000	20.494		44.62	11.149	0.000
						C	0.000	20.494		44.62	0.000	0.000
T4 133.33-126.67	130.00	1.337	7	1.3190	82.899	A	0.000	20.941	9.129	43.59	30.497	0.000
						B	0.000	20.941		43.59	45.555	0.000
						C	0.000	20.941		43.59	0.000	0.000
T5 126.67-120.00	123.33	1.323	7	1.3121	87.520	A	0.000	21.380	9.113	42.62	30.407	0.000
						B	0.000	21.380		42.62	72.258	0.000
						C	0.000	21.380		42.62	0.000	0.000
T6 120.00-100.00	110.00	1.291	7	1.2971	293.730	A	0.000	63.059	30.796	48.84	94.834	0.000
						B	0.000	63.059		48.84	241.107	0.000
						C	0.000	63.059		48.84	0.000	0.000
T7 100.00-90.00	95.00	1.252	7	1.2783	164.675	A	0.000	33.908	15.347	45.26	48.142	0.000
						B	0.000	33.908		45.26	120.152	0.000
						C	0.000	33.908		45.26	0.000	0.000
T8 90.00-80.00	85.00	1.223	7	1.2641	177.827	A	0.000	34.754	15.299	44.02	47.840	0.000
						B	0.000	34.754		44.02	119.851	0.000
						C	0.000	34.754		44.02	0.000	0.000
T9 80.00-60.00	70.00	1.174	6	1.2398	395.112	A	36.020	42.530	36.020	45.86	94.951	0.000
						B	36.020	42.530		45.86	238.670	0.000
						C	36.020	42.530		45.86	0.000	0.000
T10 60.00-40.00	50.00	1.094	6	1.1988	444.975	A	35.838	45.945	35.838	43.82	98.941	0.000
						B	35.838	45.945		43.82	236.929	0.000
						C	35.838	45.945		43.82	0.000	0.000
T11 40.00-30.00	35.00	1.015	6	1.1568	241.167	A	17.825	24.142	17.825	42.47	48.489	0.000
						B	17.825	24.142		42.47	117.574	0.000
						C	17.825	24.142		42.47	0.000	0.000
T12 30.00-20.00	25.00	0.945	5	1.1185	253.603	A	17.740	24.813	17.740	41.69	47.594	0.000
						B	17.740	24.813		41.69	116.765	0.000
						C	17.740	24.813		41.69	0.000	0.000
T13 20.00-0.00	10.00	0.85	5	1.0206	544.777	A	34.626	46.029	34.626	42.93	90.613	0.000
						B	34.626	46.029		42.93	229.396	0.000
						C	34.626	46.029		42.93	0.000	0.000

Tower Pressure - Service

$$G_H = 0.850$$

Section Elevation ft	z ft	K _Z	q _z psf	A _G ft ²	F a c e	A _F ft ²	A _R ft ²	A _{leg} ft ²	Leg %	C _A A _A In Face ft ²	C _A A _A Out Face ft ²
T1 180.00-160.00	170.00	1.415	11	177.503	A	0.000	24.699	11.667	47.24	15.281	0.000
					B	0.000	24.699		47.24	0.000	0.000
					C	0.000	24.699		47.24	0.000	0.000
T2 160.00-140.00	150.00	1.378	11	200.850	A	0.000	28.812	15.027	52.16	32.847	0.000
					B	0.000	28.812		52.16	0.000	0.000

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 35 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by TJL

Section Elevation	z	Kz	qz	AG	F a c e	AF	AR	Aleg	Leg %	CAAA In Face	CAAA Out Face
ft	ft		psf	ft ²	e	ft ²	ft ²	ft ²		ft ²	ft ²
T3 140.00-133.33	136.67	1.352	11	76.803	C	0.000	28.812	6.192	52.16	0.000	0.000
					A	0.000	11.559			53.57	10.949
					B	0.000	11.559			53.57	3.960
T4 133.33-126.67	130.00	1.337	10	81.431	C	0.000	11.559	6.192	52.51	0.000	0.000
					A	0.000	11.792			52.51	10.949
					B	0.000	11.792			52.51	14.711
T5 126.67-120.00	123.33	1.323	10	86.060	C	0.000	11.792	6.192	51.52	0.000	0.000
					A	0.000	12.020			51.52	10.949
					B	0.000	12.020			51.52	33.451
T6 120.00-100.00	110.00	1.291	10	289.399	C	0.000	12.020	22.130	57.36	0.000	0.000
					A	0.000	38.583			57.36	33.666
					B	0.000	38.583			57.36	118.527
T7 100.00-90.00	95.00	1.252	10	162.540	C	0.000	38.583	11.074	52.17	0.000	0.000
					A	0.000	21.227			52.17	17.054
					B	0.000	21.227			52.17	59.264
T8 90.00-80.00	85.00	1.223	10	175.715	C	0.000	21.227	11.074	50.92	0.000	0.000
					A	0.000	21.747			50.92	17.054
					B	0.000	21.747			50.92	59.264
T9 80.00-60.00	70.00	1.174	9	390.971	C	0.000	21.747	30.496	55.82	0.000	0.000
					A	30.496	24.135			55.82	34.170
					B	30.496	24.135			55.82	118.527
T10 60.00-40.00	50.00	1.094	9	440.971	C	30.496	24.135	30.496	53.58	0.000	0.000
					A	30.496	26.417			53.58	35.367
					B	30.496	26.417			53.58	118.527
T11 40.00-30.00	35.00	1.015	8	239.236	C	30.496	26.417	15.248	51.99	0.000	0.000
					A	15.248	14.079			51.99	17.684
					B	15.248	14.079			51.99	59.264
T12 30.00-20.00	25.00	0.945	7	251.736	C	15.248	14.079	15.248	50.97	0.000	0.000
					A	15.248	14.667			50.97	17.684
					B	15.248	14.667			50.97	59.264
T13 20.00-0.00	10.00	0.85	7	541.368	C	15.248	14.667	30.078	51.68	0.000	0.000
					A	30.078	28.122			51.68	35.367
					B	30.078	28.122			51.68	118.527
					C	30.078	28.122		51.68	0.000	0.000

Tower Forces - No Ice - Wind Normal To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	CF	qz	DF	DR	AE	F	w	Ctrl. Face
ft	lb	lb	e			psf			ft ²	lb	plf	
T1 180.00-160.00	44.64	1250.43	A	0.139	2.812	52	1	1	13.713	2381.65	119.08	C
			B	0.139	2.812		1	1	13.713			
			C	0.139	2.812		1	1	13.713			
T2 160.00-140.00	152.20	1495.62	A	0.143	2.796	51	1	1	15.269	3254.56	162.73	C
			B	0.143	2.796		1	1	15.269			
			C	0.143	2.796		1	1	15.269			
T3 140.00-133.33	88.73	825.91	A	0.151	2.77	50	1	1	5.828	1244.94	186.74	C
			B	0.151	2.77		1	1	5.828			
			C	0.151	2.77		1	1	5.828			
T4 133.33-126.67	146.37	842.18	A	0.145	2.791	49	1	1	5.951	1700.85	255.13	C
			B	0.145	2.791		1	1	5.951			
			C	0.145	2.791		1	1	5.951			
T5 126.67-120.00	225.61	1080.40	A	0.14	2.81	49	1	1	6.074	2475.95	371.39	C
			B	0.14	2.81		1	1	6.074			
			C	0.14	2.81		1	1	6.074			
T6	754.97	3821.31	A	0.133	2.834	47	1	1	18.396	8055.32	402.77	C

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 36 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by TJL

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	q _z	D _F	D _R	A _E	F	w	Ctrl. Face
ft	lb	lb				psf			ft ²	lb	plf	
120.00-100.00			B	0.133	2.834		1	1	18.396			
			C	0.133	2.834		1	1	18.396			
T7	378.01	1682.80	A	0.131	2.844	46	1	1	10.175	4026.36	402.64	C
100.00-90.00			B	0.131	2.844		1	1	10.175			
			C	0.131	2.844		1	1	10.175			
T8	378.01	1722.73	A	0.124	2.87	45	1	1	10.439	3972.29	397.23	C
90.00-80.00			B	0.124	2.87		1	1	10.439			
			C	0.124	2.87		1	1	10.439			
T9	756.17	4897.54	A	0.14	2.81	43	1	1	44.041	9970.67	498.53	C
80.00-60.00			B	0.14	2.81		1	1	44.041			
			C	0.14	2.81		1	1	44.041			
T10	759.02	5700.46	A	0.129	2.85	40	1	1	45.397	9522.62	476.13	C
60.00-40.00			B	0.129	2.85		1	1	45.397			
			C	0.129	2.85		1	1	45.397			
T11	379.51	2942.46	A	0.123	2.875	37	1	1	23.207	4481.20	448.12	C
40.00-30.00			B	0.123	2.875		1	1	23.207			
			C	0.123	2.875		1	1	23.207			
T12	379.51	3139.03	A	0.119	2.889	35	1	1	23.536	4212.83	421.28	C
30.00-20.00			B	0.119	2.889		1	1	23.536			
			C	0.119	2.889		1	1	23.536			
T13	759.02	6187.56	A	0.108	2.934	31	1	1	45.922	7542.54	377.13	C
20.00-0.00			B	0.108	2.934		1	1	45.922			
			C	0.108	2.934		1	1	45.922			
Sum Weight:	5201.77	35588.43						OTM	4707.59 kip-ft	62841.79		

Tower Forces - No Ice - Wind 45 To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	q _z	D _F	D _R	A _E	F	w	Ctrl. Face
ft	lb	lb				psf			ft ²	lb	plf	
T1	44.64	1250.43	A	0.139	2.812	52	0.825	1	13.713	2381.65	119.08	C
180.00-160.00			B	0.139	2.812		0.825	1	13.713			
			C	0.139	2.812		0.825	1	13.713			
T2	152.20	1495.62	A	0.143	2.796	51	0.825	1	15.269	3254.56	162.73	C
160.00-140.00			B	0.143	2.796		0.825	1	15.269			
			C	0.143	2.796		0.825	1	15.269			
T3	88.73	825.91	A	0.151	2.77	50	0.825	1	5.828	1244.94	186.74	C
140.00-133.33			B	0.151	2.77		0.825	1	5.828			
			C	0.151	2.77		0.825	1	5.828			
T4	146.37	842.18	A	0.145	2.791	49	0.825	1	5.951	1700.85	255.13	C
133.33-126.67			B	0.145	2.791		0.825	1	5.951			
			C	0.145	2.791		0.825	1	5.951			
T5	225.61	1080.40	A	0.14	2.81	49	0.825	1	6.074	2475.95	371.39	C
126.67-120.00			B	0.14	2.81		0.825	1	6.074			
			C	0.14	2.81		0.825	1	6.074			
T6	754.97	3821.31	A	0.133	2.834	47	0.825	1	18.396	8055.32	402.77	C
120.00-100.00			B	0.133	2.834		0.825	1	18.396			
			C	0.133	2.834		0.825	1	18.396			
T7	378.01	1682.80	A	0.131	2.844	46	0.825	1	10.175	4026.36	402.64	C
100.00-90.00			B	0.131	2.844		0.825	1	10.175			
			C	0.131	2.844		0.825	1	10.175			
T8	378.01	1722.73	A	0.124	2.87	45	0.825	1	10.439	3972.29	397.23	C

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 37 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by TJJ

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	q _z	D _F	D _R	A _E	F	w	Ctrl. Face
ft	lb	lb				psf			ft ²	lb	plf	
90.00-80.00			B	0.124	2.87		0.825	1	10.439			
			C	0.124	2.87		0.825	1	10.439			
T9	756.17	4897.54	A	0.14	2.81	43	0.825	1	38.705	9420.39	471.02	C
80.00-60.00			B	0.14	2.81		0.825	1	38.705			
			C	0.14	2.81		0.825	1	38.705			
T10	759.02	5700.46	A	0.129	2.85	40	0.825	1	40.060	9002.60	450.13	C
60.00-40.00			B	0.129	2.85		0.825	1	40.060			
			C	0.129	2.85		0.825	1	40.060			
T11	379.51	2942.46	A	0.123	2.875	37	0.825	1	20.539	4237.89	423.79	C
40.00-30.00			B	0.123	2.875		0.825	1	20.539			
			C	0.123	2.875		0.825	1	20.539			
T12	379.51	3139.03	A	0.119	2.889	35	0.825	1	20.868	3985.01	398.50	C
30.00-20.00			B	0.119	2.889		0.825	1	20.868			
			C	0.119	2.889		0.825	1	20.868			
T13	759.02	6187.56	A	0.108	2.934	31	0.825	1	40.659	7132.21	356.61	C
20.00-0.00			B	0.108	2.934		0.825	1	40.659			
			C	0.108	2.934		0.825	1	40.659			
Sum Weight:	5201.77	35588.43						OTM	4624.75 kip-ft	60890.03		

Tower Forces - No Ice - Wind 60 To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	q _z	D _F	D _R	A _E	F	w	Ctrl. Face
ft	lb	lb				psf			ft ²	lb	plf	
T1	44.64	1250.43	A	0.139	2.812	52	0.8	1	13.713	2381.65	119.08	C
180.00-160.00			B	0.139	2.812		0.8	1	13.713			
			C	0.139	2.812		0.8	1	13.713			
T2	152.20	1495.62	A	0.143	2.796	51	0.8	1	15.269	3254.56	162.73	C
160.00-140.00			B	0.143	2.796		0.8	1	15.269			
			C	0.143	2.796		0.8	1	15.269			
T3	88.73	825.91	A	0.151	2.77	50	0.8	1	5.828	1244.94	186.74	C
140.00-133.33			B	0.151	2.77		0.8	1	5.828			
			C	0.151	2.77		0.8	1	5.828			
T4	146.37	842.18	A	0.145	2.791	49	0.8	1	5.951	1700.85	255.13	C
133.33-126.67			B	0.145	2.791		0.8	1	5.951			
			C	0.145	2.791		0.8	1	5.951			
T5	225.61	1080.40	A	0.14	2.81	49	0.8	1	6.074	2475.95	371.39	C
126.67-120.00			B	0.14	2.81		0.8	1	6.074			
			C	0.14	2.81		0.8	1	6.074			
T6	754.97	3821.31	A	0.133	2.834	47	0.8	1	18.396	8055.32	402.77	C
120.00-100.00			B	0.133	2.834		0.8	1	18.396			
			C	0.133	2.834		0.8	1	18.396			
T7	378.01	1682.80	A	0.131	2.844	46	0.8	1	10.175	4026.36	402.64	C
100.00-90.00			B	0.131	2.844		0.8	1	10.175			
			C	0.131	2.844		0.8	1	10.175			
T8	378.01	1722.73	A	0.124	2.87	45	0.8	1	10.439	3972.29	397.23	C
90.00-80.00			B	0.124	2.87		0.8	1	10.439			
			C	0.124	2.87		0.8	1	10.439			
T9	756.17	4897.54	A	0.14	2.81	43	0.8	1	37.942	9341.78	467.09	C
80.00-60.00			B	0.14	2.81		0.8	1	37.942			
			C	0.14	2.81		0.8	1	37.942			
T10	759.02	5700.46	A	0.129	2.85	40	0.8	1	39.297	8928.31	446.42	C

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 38 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by T.J.L

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	q _z	D _F	D _R	A _E	F	w	Ctrl. Face
ft	lb	lb				psf			ft ²	lb	plf	
60.00-40.00			B	0.129	2.85		0.8	1	39.297			
			C	0.129	2.85		0.8	1	39.297			
T11	379.51	2942.46	A	0.123	2.875	37	0.8	1	20.158	4203.14	420.31	C
40.00-30.00			B	0.123	2.875		0.8	1	20.158			
			C	0.123	2.875		0.8	1	20.158			
T12	379.51	3139.03	A	0.119	2.889	35	0.8	1	20.487	3952.47	395.25	C
30.00-20.00			B	0.119	2.889		0.8	1	20.487			
			C	0.119	2.889		0.8	1	20.487			
T13	759.02	6187.56	A	0.108	2.934	31	0.8	1	39.907	7073.60	353.68	C
20.00-0.00			B	0.108	2.934		0.8	1	39.907			
			C	0.108	2.934		0.8	1	39.907			
Sum Weight:	5201.77	35588.43						OTM	4612.92 kip-ft	60611.21		

Tower Forces - No Ice - Wind 90 To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	q _z	D _F	D _R	A _E	F	w	Ctrl. Face
ft	lb	lb				psf			ft ²	lb	plf	
T1	44.64	1250.43	A	0.139	2.812	52	0.85	1	13.713	2381.65	119.08	C
180.00-160.00			B	0.139	2.812		0.85	1	13.713			
			C	0.139	2.812		0.85	1	13.713			
T2	152.20	1495.62	A	0.143	2.796	51	0.85	1	15.269	3254.56	162.73	C
160.00-140.00			B	0.143	2.796		0.85	1	15.269			
			C	0.143	2.796		0.85	1	15.269			
T3	88.73	825.91	A	0.151	2.77	50	0.85	1	5.828	1244.94	186.74	C
140.00-133.33			B	0.151	2.77		0.85	1	5.828			
			C	0.151	2.77		0.85	1	5.828			
T4	146.37	842.18	A	0.145	2.791	49	0.85	1	5.951	1700.85	255.13	C
133.33-126.67			B	0.145	2.791		0.85	1	5.951			
			C	0.145	2.791		0.85	1	5.951			
T5	225.61	1080.40	A	0.14	2.81	49	0.85	1	6.074	2475.95	371.39	C
126.67-120.00			B	0.14	2.81		0.85	1	6.074			
			C	0.14	2.81		0.85	1	6.074			
T6	754.97	3821.31	A	0.133	2.834	47	0.85	1	18.396	8055.32	402.77	C
120.00-100.00			B	0.133	2.834		0.85	1	18.396			
			C	0.133	2.834		0.85	1	18.396			
T7	378.01	1682.80	A	0.131	2.844	46	0.85	1	10.175	4026.36	402.64	C
100.00-90.00			B	0.131	2.844		0.85	1	10.175			
			C	0.131	2.844		0.85	1	10.175			
T8	378.01	1722.73	A	0.124	2.87	45	0.85	1	10.439	3972.29	397.23	C
90.00-80.00			B	0.124	2.87		0.85	1	10.439			
			C	0.124	2.87		0.85	1	10.439			
T9	756.17	4897.54	A	0.14	2.81	43	0.85	1	39.467	9499.00	474.95	C
80.00-60.00			B	0.14	2.81		0.85	1	39.467			
			C	0.14	2.81		0.85	1	39.467			
T10	759.02	5700.46	A	0.129	2.85	40	0.85	1	40.822	9076.89	453.84	C
60.00-40.00			B	0.129	2.85		0.85	1	40.822			
			C	0.129	2.85		0.85	1	40.822			
T11	379.51	2942.46	A	0.123	2.875	37	0.85	1	20.920	4272.65	427.27	C
40.00-30.00			B	0.123	2.875		0.85	1	20.920			
			C	0.123	2.875		0.85	1	20.920			
T12	379.51	3139.03	A	0.119	2.889	35	0.85	1	21.249	4017.56	401.76	C

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 39 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by TJL

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	q _z	D _F	D _R	A _E	F	w	Ctrl. Face
ft	lb	lb				psf			ft ²	lb	plf	
30.00-20.00			B	0.119	2.889		0.85	1	21.249			
			C	0.119	2.889		0.85	1	21.249			
T13	759.02	6187.56	A	0.108	2.934	31	0.85	1	41.411	7190.83	359.54	C
20.00-0.00			B	0.108	2.934		0.85	1	41.411			
			C	0.108	2.934		0.85	1	41.411			
Sum Weight:	5201.77	35588.43						OTM	4636.58 kip-ft	61168.85		

Tower Forces - With Ice - Wind Normal To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	q _z	D _F	D _R	A _E	F	w	Ctrl. Face
ft	lb	lb				psf			ft ²	lb	plf	
T1	492.24	3296.69	A	0.273	2.37	8	1	1	29.387	725.96	36.30	C
180.00-160.00			B	0.273	2.37		1	1	29.387			
			C	0.273	2.37		1	1	29.387			
T2	1113.48	3710.35	A	0.265	2.392	7	1	1	32.082	1077.01	53.85	C
160.00-140.00			B	0.265	2.392		1	1	32.082			
			C	0.265	2.392		1	1	32.082			
T3	519.89	1666.01	A	0.262	2.403	7	1	1	12.050	413.89	62.08	C
140.00-133.33			B	0.262	2.403		1	1	12.050			
			C	0.262	2.403		1	1	12.050			
T4	894.36	1704.37	A	0.253	2.43	7	1	1	12.264	627.08	94.06	C
133.33-126.67			B	0.253	2.43		1	1	12.264			
			C	0.253	2.43		1	1	12.264			
T5	1489.41	1963.86	A	0.244	2.455	7	1	1	12.478	788.09	118.21	C
126.67-120.00			B	0.244	2.455		1	1	12.478			
			C	0.244	2.455		1	1	12.478			
T6	5047.78	6329.32	A	0.215	2.548	7	1	1	36.398	2480.09	124.00	C
120.00-100.00			B	0.215	2.548		1	1	36.398			
			C	0.215	2.548		1	1	36.398			
T7	2507.87	3059.90	A	0.206	2.576	7	1	1	19.516	1227.03	122.70	C
100.00-90.00			B	0.206	2.576		1	1	19.516			
			C	0.206	2.576		1	1	19.516			
T8	2487.58	3136.47	A	0.195	2.611	7	1	1	19.938	1205.42	120.54	C
90.00-80.00			B	0.195	2.611		1	1	19.938			
			C	0.195	2.611		1	1	19.938			
T9	4908.83	8816.59	A	0.199	2.6	6	1	1	60.444	2592.92	129.65	C
80.00-60.00			B	0.199	2.6		1	1	60.444			
			C	0.199	2.6		1	1	60.444			
T10	4846.69	9758.08	A	0.184	2.651	6	1	1	62.111	2465.45	123.27	C
60.00-40.00			B	0.184	2.651		1	1	62.111			
			C	0.184	2.651		1	1	62.111			
T11	2363.38	4973.51	A	0.174	2.685	6	1	1	31.596	1146.80	114.68	C
40.00-30.00			B	0.174	2.685		1	1	31.596			
			C	0.174	2.685		1	1	31.596			
T12	2309.50	5147.00	A	0.168	2.707	5	1	1	31.873	1067.46	106.75	C
30.00-20.00			B	0.168	2.707		1	1	31.873			
			C	0.168	2.707		1	1	31.873			
T13	4349.86	9424.22	A	0.148	2.779	5	1	1	60.740	1871.60	93.58	C
20.00-0.00			B	0.148	2.779		1	1	60.740			
			C	0.148	2.779		1	1	60.740			
Sum Weight:	33330.89	62986.34						OTM	1402.40	17688.80		

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 40 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by TJL

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	q _z	D _F	D _R	A _E	F	w	Ctrl. Face
ft	lb	lb				psf			ft ²	lb	plf	
									kip-ft			

Tower Forces - With Ice - Wind 45 To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	q _z	D _F	D _R	A _E	F	w	Ctrl. Face
ft	lb	lb				psf			ft ²	lb	plf	
T1 180.00-160.00	492.24	3296.69	A	0.273	2.37	8	0.825	1	29.387	725.96	36.30	C
			B	0.273	2.37		0.825	1	29.387			
			C	0.273	2.37		0.825	1	29.387			
T2 160.00-140.00	1113.48	3710.35	A	0.265	2.392	7	0.825	1	32.082	1077.01	53.85	C
			B	0.265	2.392		0.825	1	32.082			
			C	0.265	2.392		0.825	1	32.082			
T3 140.00-133.33	519.89	1666.01	A	0.262	2.403	7	0.825	1	12.050	413.89	62.08	C
			B	0.262	2.403		0.825	1	12.050			
			C	0.262	2.403		0.825	1	12.050			
T4 133.33-126.67	894.36	1704.37	A	0.253	2.43	7	0.825	1	12.264	627.08	94.06	C
			B	0.253	2.43		0.825	1	12.264			
			C	0.253	2.43		0.825	1	12.264			
T5 126.67-120.00	1489.41	1963.86	A	0.244	2.455	7	0.825	1	12.478	788.09	118.21	C
			B	0.244	2.455		0.825	1	12.478			
			C	0.244	2.455		0.825	1	12.478			
T6 120.00-100.00	5047.78	6329.32	A	0.215	2.548	7	0.825	1	36.398	2480.09	124.00	C
			B	0.215	2.548		0.825	1	36.398			
			C	0.215	2.548		0.825	1	36.398			
T7 100.00-90.00	2507.87	3059.90	A	0.206	2.576	7	0.825	1	19.516	1227.03	122.70	C
			B	0.206	2.576		0.825	1	19.516			
			C	0.206	2.576		0.825	1	19.516			
T8 90.00-80.00	2487.58	3136.47	A	0.195	2.611	7	0.825	1	19.938	1205.42	120.54	C
			B	0.195	2.611		0.825	1	19.938			
			C	0.195	2.611		0.825	1	19.938			
T9 80.00-60.00	4908.83	8816.59	A	0.199	2.6	6	0.825	1	54.141	2503.95	125.20	C
			B	0.199	2.6		0.825	1	54.141			
			C	0.199	2.6		0.825	1	54.141			
T10 60.00-40.00	4846.69	9758.08	A	0.184	2.651	6	0.825	1	55.839	2381.37	119.07	C
			B	0.184	2.651		0.825	1	55.839			
			C	0.184	2.651		0.825	1	55.839			
T11 40.00-30.00	2363.38	4973.51	A	0.174	2.685	6	0.825	1	28.477	1107.50	110.75	C
			B	0.174	2.685		0.825	1	28.477			
			C	0.174	2.685		0.825	1	28.477			
T12 30.00-20.00	2309.50	5147.00	A	0.168	2.707	5	0.825	1	28.769	1030.72	103.07	C
			B	0.168	2.707		0.825	1	28.769			
			C	0.168	2.707		0.825	1	28.769			
T13 20.00-0.00	4349.86	9424.22	A	0.148	2.779	5	0.825	1	54.680	1805.42	90.27	C
			B	0.148	2.779		0.825	1	54.680			
			C	0.148	2.779		0.825	1	54.680			
Sum Weight:	33330.89	62986.34						OTM	1389.02 kip-ft	17373.53		

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 41 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by T.J.L.

Tower Forces - With Ice - Wind 60 To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	q _z	D _F	D _R	A _E	F	w	Ctrl. Face
ft	lb	lb				psf			ft ²	lb	plf	
T1 180.00-160.00	492.24	3296.69	A	0.273	2.37	8	0.8	1	29.387	725.96	36.30	C
			B	0.273	2.37		0.8		29.387			
			C	0.273	2.37		0.8		29.387			
T2 160.00-140.00	1113.48	3710.35	A	0.265	2.392	7	0.8	1	32.082	1077.01	53.85	C
			B	0.265	2.392		0.8		32.082			
			C	0.265	2.392		0.8		32.082			
T3 140.00-133.33	519.89	1666.01	A	0.262	2.403	7	0.8	1	12.050	413.89	62.08	C
			B	0.262	2.403		0.8		12.050			
			C	0.262	2.403		0.8		12.050			
T4 133.33-126.67	894.36	1704.37	A	0.253	2.43	7	0.8	1	12.264	627.08	94.06	C
			B	0.253	2.43		0.8		12.264			
			C	0.253	2.43		0.8		12.264			
T5 126.67-120.00	1489.41	1963.86	A	0.244	2.455	7	0.8	1	12.478	788.09	118.21	C
			B	0.244	2.455		0.8		12.478			
			C	0.244	2.455		0.8		12.478			
T6 120.00-100.00	5047.78	6329.32	A	0.215	2.548	7	0.8	1	36.398	2480.09	124.00	C
			B	0.215	2.548		0.8		36.398			
			C	0.215	2.548		0.8		36.398			
T7 100.00-90.00	2507.87	3059.90	A	0.206	2.576	7	0.8	1	19.516	1227.03	122.70	C
			B	0.206	2.576		0.8		19.516			
			C	0.206	2.576		0.8		19.516			
T8 90.00-80.00	2487.58	3136.47	A	0.195	2.611	7	0.8	1	19.938	1205.42	120.54	C
			B	0.195	2.611		0.8		19.938			
			C	0.195	2.611		0.8		19.938			
T9 80.00-60.00	4908.83	8816.59	A	0.199	2.6	6	0.8	1	53.240	2491.24	124.56	C
			B	0.199	2.6		0.8		53.240			
			C	0.199	2.6		0.8		53.240			
T10 60.00-40.00	4846.69	9758.08	A	0.184	2.651	6	0.8	1	54.943	2369.35	118.47	C
			B	0.184	2.651		0.8		54.943			
			C	0.184	2.651		0.8		54.943			
T11 40.00-30.00	2363.38	4973.51	A	0.174	2.685	6	0.8	1	28.031	1101.88	110.19	C
			B	0.174	2.685		0.8		28.031			
			C	0.174	2.685		0.8		28.031			
T12 30.00-20.00	2309.50	5147.00	A	0.168	2.707	5	0.8	1	28.325	1025.48	102.55	C
			B	0.168	2.707		0.8		28.325			
			C	0.168	2.707		0.8		28.325			
T13 20.00-0.00	4349.86	9424.22	A	0.148	2.779	5	0.8	1	53.815	1795.97	89.80	C
			B	0.148	2.779		0.8		53.815			
			C	0.148	2.779		0.8		53.815			
Sum Weight:	33330.89	62986.34						OTM	1387.10 kip-ft	17328.49		

Tower Forces - With Ice - Wind 90 To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	q _z	D _F	D _R	A _E	F	w	Ctrl. Face
ft	lb	lb				psf			ft ²	lb	plf	
T1 180.00-160.00	492.24	3296.69	A	0.273	2.37	8	0.85	1	29.387	725.96	36.30	C
			B	0.273	2.37		0.85		29.387			
			C	0.273	2.37		0.85		29.387			

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 42 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by TJL

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	q _z	D _F	D _R	A _E	F	w	Ctrl. Face
ft	lb	lb	e			psf			ft ²	lb	plf	
T2 160.00-140.00	1113.48	3710.35	A	0.265	2.392	7	0.85	1	32.082	1077.01	53.85	C
			B	0.265	2.392		0.85	1	32.082			
			C	0.265	2.392		0.85	1	32.082			
T3 140.00-133.33	519.89	1666.01	A	0.262	2.403	7	0.85	1	12.050	413.89	62.08	C
			B	0.262	2.403		0.85	1	12.050			
			C	0.262	2.403		0.85	1	12.050			
T4 133.33-126.67	894.36	1704.37	A	0.253	2.43	7	0.85	1	12.264	627.08	94.06	C
			B	0.253	2.43		0.85	1	12.264			
			C	0.253	2.43		0.85	1	12.264			
T5 126.67-120.00	1489.41	1963.86	A	0.244	2.455	7	0.85	1	12.478	788.09	118.21	C
			B	0.244	2.455		0.85	1	12.478			
			C	0.244	2.455		0.85	1	12.478			
T6 120.00-100.00	5047.78	6329.32	A	0.215	2.548	7	0.85	1	36.398	2480.09	124.00	C
			B	0.215	2.548		0.85	1	36.398			
			C	0.215	2.548		0.85	1	36.398			
T7 100.00-90.00	2507.87	3059.90	A	0.206	2.576	7	0.85	1	19.516	1227.03	122.70	C
			B	0.206	2.576		0.85	1	19.516			
			C	0.206	2.576		0.85	1	19.516			
T8 90.00-80.00	2487.58	3136.47	A	0.195	2.611	7	0.85	1	19.938	1205.42	120.54	C
			B	0.195	2.611		0.85	1	19.938			
			C	0.195	2.611		0.85	1	19.938			
T9 80.00-60.00	4908.83	8816.59	A	0.199	2.6	6	0.85	1	55.041	2516.66	125.83	C
			B	0.199	2.6		0.85	1	55.041			
			C	0.199	2.6		0.85	1	55.041			
T10 60.00-40.00	4846.69	9758.08	A	0.184	2.651	6	0.85	1	56.735	2393.38	119.67	C
			B	0.184	2.651		0.85	1	56.735			
			C	0.184	2.651		0.85	1	56.735			
T11 40.00-30.00	2363.38	4973.51	A	0.174	2.685	6	0.85	1	28.922	1113.11	111.31	C
			B	0.174	2.685		0.85	1	28.922			
			C	0.174	2.685		0.85	1	28.922			
T12 30.00-20.00	2309.50	5147.00	A	0.168	2.707	5	0.85	1	29.212	1035.97	103.60	C
			B	0.168	2.707		0.85	1	29.212			
			C	0.168	2.707		0.85	1	29.212			
T13 20.00-0.00	4349.86	9424.22	A	0.148	2.779	5	0.85	1	55.546	1814.88	90.74	C
			B	0.148	2.779		0.85	1	55.546			
			C	0.148	2.779		0.85	1	55.546			
Sum Weight:	33330.89	62986.34						OTM	1390.93 kip-ft	17418.57		

Tower Forces - Service - Wind Normal To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	q _z	D _F	D _R	A _E	F	w	Ctrl. Face
ft	lb	lb	e			psf			ft ²	lb	plf	
T1 180.00-160.00	44.64	1250.43	A	0.139	2.812	11	1	1	13.993	514.75	25.74	C
			B	0.139	2.812		1	1	13.993			
			C	0.139	2.812		1	1	13.993			
T2 160.00-140.00	152.20	1495.62	A	0.143	2.796	11	1	1	16.334	720.60	36.03	C
			B	0.143	2.796		1	1	16.334			
			C	0.143	2.796		1	1	16.334			
T3 140.00-133.33	88.73	825.91	A	0.151	2.77	11	1	1	6.561	283.47	42.52	C
			B	0.151	2.77		1	1	6.561			
			C	0.151	2.77		1	1	6.561			

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 43 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by TJJ

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	q _z	D _F	D _R	A _E	F	w	Ctrl. Face
ft	lb	lb				psf			ft ²	lb	plf	
T4 133.33-126.67	146.37	842.18	A	0.145	2.791	10	1	1	6.687	380.60	57.09	C
			B	0.145	2.791		1	1	6.687			
			C	0.145	2.791		1	1	6.687			
T5 126.67-120.00	225.61	1080.40	A	0.14	2.81	10	1	1	6.810	545.65	81.85	C
			B	0.14	2.81		1	1	6.810			
			C	0.14	2.81		1	1	6.810			
T6 120.00-100.00	754.97	3821.31	A	0.133	2.834	10	1	1	21.840	1799.85	89.99	C
			B	0.133	2.834		1	1	21.840			
			C	0.133	2.834		1	1	21.840			
T7 100.00-90.00	378.01	1682.80	A	0.131	2.844	10	1	1	12.011	901.22	90.12	C
			B	0.131	2.844		1	1	12.011			
			C	0.131	2.844		1	1	12.011			
T8 90.00-80.00	378.01	1722.73	A	0.124	2.87	10	1	1	12.296	889.58	88.96	C
			B	0.124	2.87		1	1	12.296			
			C	0.124	2.87		1	1	12.296			
T9 80.00-60.00	756.17	4897.54	A	0.14	2.81	9	1	1	44.170	2126.75	106.34	C
			B	0.14	2.81		1	1	44.170			
			C	0.14	2.81		1	1	44.170			
T10 60.00-40.00	759.02	5700.46	A	0.129	2.85	9	1	1	45.441	2029.41	101.47	C
			B	0.129	2.85		1	1	45.441			
			C	0.129	2.85		1	1	45.441			
T11 40.00-30.00	379.51	2942.46	A	0.123	2.875	8	1	1	23.207	954.58	95.46	C
			B	0.123	2.875		1	1	23.207			
			C	0.123	2.875		1	1	23.207			
T12 30.00-20.00	379.51	3139.03	A	0.119	2.889	7	1	1	23.536	897.41	89.74	C
			B	0.119	2.889		1	1	23.536			
			C	0.119	2.889		1	1	23.536			
T13 20.00-0.00	759.02	6187.56	A	0.108	2.934	7	1	1	45.955	1607.24	80.36	C
			B	0.108	2.934		1	1	45.955			
			C	0.108	2.934		1	1	45.955			
Sum Weight:	5201.77	35588.43						OTM	1032.59 kip-ft	13651.11		

Tower Forces - Service - Wind 45 To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	q _z	D _F	D _R	A _E	F	w	Ctrl. Face
ft	lb	lb				psf			ft ²	lb	plf	
T1 180.00-160.00	44.64	1250.43	A	0.139	2.812	11	0.825	1	13.993	514.75	25.74	C
			B	0.139	2.812		0.825	1	13.993			
			C	0.139	2.812		0.825	1	13.993			
T2 160.00-140.00	152.20	1495.62	A	0.143	2.796	11	0.825	1	16.334	720.60	36.03	C
			B	0.143	2.796		0.825	1	16.334			
			C	0.143	2.796		0.825	1	16.334			
T3 140.00-133.33	88.73	825.91	A	0.151	2.77	11	0.825	1	6.561	283.47	42.52	C
			B	0.151	2.77		0.825	1	6.561			
			C	0.151	2.77		0.825	1	6.561			
T4 133.33-126.67	146.37	842.18	A	0.145	2.791	10	0.825	1	6.687	380.60	57.09	C
			B	0.145	2.791		0.825	1	6.687			
			C	0.145	2.791		0.825	1	6.687			
T5 126.67-120.00	225.61	1080.40	A	0.14	2.81	10	0.825	1	6.810	545.65	81.85	C
			B	0.14	2.81		0.825	1	6.810			
			C	0.14	2.81		0.825	1	6.810			

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 44 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by T.J.L.

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	q _z	D _F	D _R	A _E	F	w	Ctrl. Face
ft	lb	lb				psf			ft ²	lb	plf	
T6 120.00-100.00	754.97	3821.31	A	0.133	2.834	10	0.825	1	21.840	1799.85	89.99	C
			B	0.133	2.834		0.825	1	21.840			
			C	0.133	2.834		0.825	1	21.840			
T7 100.00-90.00	378.01	1682.80	A	0.131	2.844	10	0.825	1	12.011	901.22	90.12	C
			B	0.131	2.844		0.825	1	12.011			
			C	0.131	2.844		0.825	1	12.011			
T8 90.00-80.00	378.01	1722.73	A	0.124	2.87	10	0.825	1	12.296	889.58	88.96	C
			B	0.124	2.87		0.825	1	12.296			
			C	0.124	2.87		0.825	1	12.296			
T9 80.00-60.00	756.17	4897.54	A	0.14	2.81	9	0.825	1	38.833	2009.53	100.48	C
			B	0.14	2.81		0.825	1	38.833			
			C	0.14	2.81		0.825	1	38.833			
T10 60.00-40.00	759.02	5700.46	A	0.129	2.85	9	0.825	1	40.104	1918.63	95.93	C
			B	0.129	2.85		0.825	1	40.104			
			C	0.129	2.85		0.825	1	40.104			
T11 40.00-30.00	379.51	2942.46	A	0.123	2.875	8	0.825	1	20.539	902.75	90.27	C
			B	0.123	2.875		0.825	1	20.539			
			C	0.123	2.875		0.825	1	20.539			
T12 30.00-20.00	379.51	3139.03	A	0.119	2.889	7	0.825	1	20.868	848.88	84.89	C
			B	0.119	2.889		0.825	1	20.868			
			C	0.119	2.889		0.825	1	20.868			
T13 20.00-0.00	759.02	6187.56	A	0.108	2.934	7	0.825	1	40.692	1519.84	75.99	C
			B	0.108	2.934		0.825	1	40.692			
			C	0.108	2.934		0.825	1	40.692			
Sum Weight:	5201.77	35588.43						OTM	1014.94 kip-ft	13235.35		

Tower Forces - Service - Wind 60 To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	q _z	D _F	D _R	A _E	F	w	Ctrl. Face
ft	lb	lb				psf			ft ²	lb	plf	
T1 180.00-160.00	44.64	1250.43	A	0.139	2.812	11	0.8	1	13.993	514.75	25.74	C
			B	0.139	2.812		0.8	1	13.993			
			C	0.139	2.812		0.8	1	13.993			
T2 160.00-140.00	152.20	1495.62	A	0.143	2.796	11	0.8	1	16.334	720.60	36.03	C
			B	0.143	2.796		0.8	1	16.334			
			C	0.143	2.796		0.8	1	16.334			
T3 140.00-133.33	88.73	825.91	A	0.151	2.77	11	0.8	1	6.561	283.47	42.52	C
			B	0.151	2.77		0.8	1	6.561			
			C	0.151	2.77		0.8	1	6.561			
T4 133.33-126.67	146.37	842.18	A	0.145	2.791	10	0.8	1	6.687	380.60	57.09	C
			B	0.145	2.791		0.8	1	6.687			
			C	0.145	2.791		0.8	1	6.687			
T5 126.67-120.00	225.61	1080.40	A	0.14	2.81	10	0.8	1	6.810	545.65	81.85	C
			B	0.14	2.81		0.8	1	6.810			
			C	0.14	2.81		0.8	1	6.810			
T6 120.00-100.00	754.97	3821.31	A	0.133	2.834	10	0.8	1	21.840	1799.85	89.99	C
			B	0.133	2.834		0.8	1	21.840			
			C	0.133	2.834		0.8	1	21.840			
T7 100.00-90.00	378.01	1682.80	A	0.131	2.844	10	0.8	1	12.011	901.22	90.12	C
			B	0.131	2.844		0.8	1	12.011			
			C	0.131	2.844		0.8	1	12.011			

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 45 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by TJL

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	q _z	D _F	D _R	A _E	F	w	Ctrl. Face
ft	lb	lb				psf			ft ²	lb	plf	
T8 90.00-80.00	378.01	1722.73	A	0.124	2.87	10	0.8	1	12.296	889.58	88.96	C
			B	0.124	2.87		0.8	1	12.296			
			C	0.124	2.87		0.8	1	12.296			
T9 80.00-60.00	756.17	4897.54	A	0.14	2.81	9	0.8	1	38.071	1992.79	99.64	C
			B	0.14	2.81		0.8	1	38.071			
			C	0.14	2.81		0.8	1	38.071			
T10 60.00-40.00	759.02	5700.46	A	0.129	2.85	9	0.8	1	39.342	1902.81	95.14	C
			B	0.129	2.85		0.8	1	39.342			
			C	0.129	2.85		0.8	1	39.342			
T11 40.00-30.00	379.51	2942.46	A	0.123	2.875	8	0.8	1	20.158	895.34	89.53	C
			B	0.123	2.875		0.8	1	20.158			
			C	0.123	2.875		0.8	1	20.158			
T12 30.00-20.00	379.51	3139.03	A	0.119	2.889	7	0.8	1	20.487	841.95	84.19	C
			B	0.119	2.889		0.8	1	20.487			
			C	0.119	2.889		0.8	1	20.487			
T13 20.00-0.00	759.02	6187.56	A	0.108	2.934	7	0.8	1	39.940	1507.35	75.37	C
			B	0.108	2.934		0.8	1	39.940			
			C	0.108	2.934		0.8	1	39.940			
Sum Weight:	5201.77	35588.43						OTM	1012.42 kip-ft	13175.95		

Tower Forces - Service - Wind 90 To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	q _z	D _F	D _R	A _E	F	w	Ctrl. Face
ft	lb	lb				psf			ft ²	lb	plf	
T1 180.00-160.00	44.64	1250.43	A	0.139	2.812	11	0.85	1	13.993	514.75	25.74	C
			B	0.139	2.812		0.85	1	13.993			
			C	0.139	2.812		0.85	1	13.993			
T2 160.00-140.00	152.20	1495.62	A	0.143	2.796	11	0.85	1	16.334	720.60	36.03	C
			B	0.143	2.796		0.85	1	16.334			
			C	0.143	2.796		0.85	1	16.334			
T3 140.00-133.33	88.73	825.91	A	0.151	2.77	11	0.85	1	6.561	283.47	42.52	C
			B	0.151	2.77		0.85	1	6.561			
			C	0.151	2.77		0.85	1	6.561			
T4 133.33-126.67	146.37	842.18	A	0.145	2.791	10	0.85	1	6.687	380.60	57.09	C
			B	0.145	2.791		0.85	1	6.687			
			C	0.145	2.791		0.85	1	6.687			
T5 126.67-120.00	225.61	1080.40	A	0.14	2.81	10	0.85	1	6.810	545.65	81.85	C
			B	0.14	2.81		0.85	1	6.810			
			C	0.14	2.81		0.85	1	6.810			
T6 120.00-100.00	754.97	3821.31	A	0.133	2.834	10	0.85	1	21.840	1799.85	89.99	C
			B	0.133	2.834		0.85	1	21.840			
			C	0.133	2.834		0.85	1	21.840			
T7 100.00-90.00	378.01	1682.80	A	0.131	2.844	10	0.85	1	12.011	901.22	90.12	C
			B	0.131	2.844		0.85	1	12.011			
			C	0.131	2.844		0.85	1	12.011			
T8 90.00-80.00	378.01	1722.73	A	0.124	2.87	10	0.85	1	12.296	889.58	88.96	C
			B	0.124	2.87		0.85	1	12.296			
			C	0.124	2.87		0.85	1	12.296			
T9 80.00-60.00	756.17	4897.54	A	0.14	2.81	9	0.85	1	39.595	2026.28	101.31	C
			B	0.14	2.81		0.85	1	39.595			
			C	0.14	2.81		0.85	1	39.595			

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 46 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by TJL

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	q _z	D _F	D _R	A _E	F	w	Ctrl. Face
ft	lb	lb				psf			ft ²	lb	plf	
T10 60.00-40.00	759.02	5700.46	A	0.129	2.85	9	0.85	1	40.867	1934.46	96.72	C
			B	0.129	2.85		0.85	1	40.867			
			C	0.129	2.85		0.85	1	40.867			
T11 40.00-30.00	379.51	2942.46	A	0.123	2.875	8	0.85	1	20.920	910.15	91.02	C
			B	0.123	2.875		0.85	1	20.920			
			C	0.123	2.875		0.85	1	20.920			
T12 30.00-20.00	379.51	3139.03	A	0.119	2.889	7	0.85	1	21.249	855.81	85.58	C
			B	0.119	2.889		0.85	1	21.249			
			C	0.119	2.889		0.85	1	21.249			
T13 20.00-0.00	759.02	6187.56	A	0.108	2.934	7	0.85	1	41.444	1532.32	76.62	C
			B	0.108	2.934		0.85	1	41.444			
			C	0.108	2.934		0.85	1	41.444			
Sum Weight:	5201.77	35588.43						OTM	1017.46 kip-ft	13294.74		

Force Totals

Load Case	Vertical Forces	Sum of Forces X	Sum of Forces Z	Sum of Overturning Moments, M _x	Sum of Overturning Moments, M _z	Sum of Torques
	lb	lb	lb	kip-ft	kip-ft	kip-ft
Leg Weight	17198.81					
Bracing Weight	18389.62					
Total Member Self-Weight	35588.43			-18.52	-9.48	
Total Weight	54379.73			-18.52	-9.48	
Wind 0 deg - No Ice		1.43	-86954.21	-8208.96	-9.74	59.45
Wind 30 deg - No Ice		42441.04	-73545.11	-6999.25	-4036.22	-40.17
Wind 45 deg - No Ice		59583.97	-59678.15	-5681.55	-5655.84	-86.03
Wind 60 deg - No Ice		72418.73	-41955.78	-4000.14	-6861.45	-125.86
Wind 90 deg - No Ice		83841.63	-179.39	-50.27	-7887.10	-179.68
Wind 120 deg - No Ice		74341.86	42852.20	3970.24	-6939.40	-187.89
Wind 135 deg - No Ice		60295.26	60328.31	5651.10	-5673.25	-172.36
Wind 150 deg - No Ice		42368.31	73459.32	6944.51	-4021.90	-144.49
Wind 180 deg - No Ice		19.18	84488.04	8035.55	-12.88	-60.27
Wind 210 deg - No Ice		-42285.64	73266.92	6912.97	3989.75	38.09
Wind 225 deg - No Ice		-59325.38	59379.32	5591.61	5591.10	83.97
Wind 240 deg - No Ice		-74094.35	42772.02	3957.50	6879.14	123.79
Wind 270 deg - No Ice		-83783.41	-146.87	-44.52	7857.83	177.93
Wind 300 deg - No Ice		-72534.78	-42064.33	-4017.90	6860.51	186.87
Wind 315 deg - No Ice		-59743.74	-59881.89	-5715.24	5662.78	171.29
Wind 330 deg - No Ice		-42542.27	-73788.58	-7039.83	4033.72	143.53
Member Ice	27397.91					
Total Weight Ice	127229.50			-156.82	-66.07	
Wind 0 deg - Ice		0.23	-22746.10	-2287.99	-66.11	26.51
Wind 30 deg - Ice		11200.75	-19405.80	-1982.83	-1119.76	4.19
Wind 45 deg - Ice		15762.05	-15776.89	-1640.48	-1547.11	-7.52
Wind 60 deg - Ice		19205.08	-11110.88	-1201.27	-1868.11	-18.69
Wind 90 deg - Ice		22199.76	-28.27	-161.82	-2139.34	-36.89
Wind 120 deg - Ice		19514.27	11255.68	888.80	-1880.47	-45.66
Wind 135 deg - Ice		15875.85	15881.06	1327.77	-1549.75	-45.41
Wind 150 deg - Ice		11188.43	19390.80	1666.15	-1117.35	-41.96
Wind 180 deg - Ice		3.02	22348.66	1952.48	-66.61	-26.64
Wind 210 deg - Ice		-11176.27	19361.96	1661.43	983.28	-4.52
Wind 225 deg - Ice		-15721.30	15729.80	1318.50	1407.75	7.19

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 47 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by TJL

Load Case	Vertical Forces lb	Sum of Forces X lb	Sum of Forces Z lb	Sum of Overturning Moments, M _x kip-ft	Sum of Overturning Moments, M _z kip-ft	Sum of Torques kip-ft
Wind 240 deg - Ice		-19476.76	11243.91	886.93	1742.07	18.36
Wind 270 deg - Ice		-22190.59	-23.14	-160.92	2005.57	36.61
Wind 300 deg - Ice		-19221.88	-11127.12	-1203.92	1738.55	45.50
Wind 315 deg - Ice		-15785.82	-15807.59	-1645.55	1418.80	45.24
Wind 330 deg - Ice		-11215.85	-19442.68	-1988.97	990.06	41.81
Total Weight	54379.73			-18.52		
Wind 0 deg - Service		0.30	-18787.48	-1777.54	3.40	12.66
Wind 30 deg - Service		9173.04	-15895.64	-1515.86	-869.21	-8.56
Wind 45 deg - Service		12879.61	-12899.67	-1230.43	-1220.39	-18.33
Wind 60 deg - Service		15655.70	-9069.67	-866.09	-1481.94	-26.81
Wind 90 deg - Service		18124.45	-38.21	-9.81	-1704.41	-38.28
Wind 120 deg - Service		16065.36	9260.62	861.52	-1498.54	-40.02
Wind 135 deg - Service		13031.12	13038.17	1225.75	-1224.10	-36.72
Wind 150 deg - Service		9157.55	15877.37	1506.00	-866.16	-30.78
Wind 180 deg - Service		4.09	18262.14	1742.40	2.73	-12.84
Wind 210 deg - Service		-9139.94	15836.38	1499.28	870.25	8.11
Wind 225 deg - Service		-12824.52	12836.01	1213.08	1217.54	17.89
Wind 240 deg - Service		-16012.64	9243.54	858.81	1496.65	26.37
Wind 270 deg - Service		-18112.04	-31.28	-8.58	1709.11	37.90
Wind 300 deg - Service		-15680.42	-9092.79	-869.88	1492.68	39.81
Wind 315 deg - Service		-12913.64	-12943.07	-1237.61	1232.81	36.49
Wind 330 deg - Service		-9194.60	-15947.51	-1524.51	879.62	30.57

Load Combinations

Comb. No.	Description
1	Dead Only
2	1.2 Dead+1.0 Wind 0 deg - No Ice
3	0.9 Dead+1.0 Wind 0 deg - No Ice
4	1.2 Dead+1.0 Wind 30 deg - No Ice
5	0.9 Dead+1.0 Wind 30 deg - No Ice
6	1.2 Dead+1.0 Wind 45 deg - No Ice
7	0.9 Dead+1.0 Wind 45 deg - No Ice
8	1.2 Dead+1.0 Wind 60 deg - No Ice
9	0.9 Dead+1.0 Wind 60 deg - No Ice
10	1.2 Dead+1.0 Wind 90 deg - No Ice
11	0.9 Dead+1.0 Wind 90 deg - No Ice
12	1.2 Dead+1.0 Wind 120 deg - No Ice
13	0.9 Dead+1.0 Wind 120 deg - No Ice
14	1.2 Dead+1.0 Wind 135 deg - No Ice
15	0.9 Dead+1.0 Wind 135 deg - No Ice
16	1.2 Dead+1.0 Wind 150 deg - No Ice
17	0.9 Dead+1.0 Wind 150 deg - No Ice
18	1.2 Dead+1.0 Wind 180 deg - No Ice
19	0.9 Dead+1.0 Wind 180 deg - No Ice
20	1.2 Dead+1.0 Wind 210 deg - No Ice
21	0.9 Dead+1.0 Wind 210 deg - No Ice
22	1.2 Dead+1.0 Wind 225 deg - No Ice
23	0.9 Dead+1.0 Wind 225 deg - No Ice
24	1.2 Dead+1.0 Wind 240 deg - No Ice
25	0.9 Dead+1.0 Wind 240 deg - No Ice
26	1.2 Dead+1.0 Wind 270 deg - No Ice
27	0.9 Dead+1.0 Wind 270 deg - No Ice
28	1.2 Dead+1.0 Wind 300 deg - No Ice
29	0.9 Dead+1.0 Wind 300 deg - No Ice

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 48 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by TJJ

Comb. No.	Description
30	1.2 Dead+1.0 Wind 315 deg - No Ice
31	0.9 Dead+1.0 Wind 315 deg - No Ice
32	1.2 Dead+1.0 Wind 330 deg - No Ice
33	0.9 Dead+1.0 Wind 330 deg - No Ice
34	1.2 Dead+1.0 Ice
35	1.2 Dead+1.0 Wind 0 deg+1.0 Ice
36	1.2 Dead+1.0 Wind 30 deg+1.0 Ice
37	1.2 Dead+1.0 Wind 45 deg+1.0 Ice
38	1.2 Dead+1.0 Wind 60 deg+1.0 Ice
39	1.2 Dead+1.0 Wind 90 deg+1.0 Ice
40	1.2 Dead+1.0 Wind 120 deg+1.0 Ice
41	1.2 Dead+1.0 Wind 135 deg+1.0 Ice
42	1.2 Dead+1.0 Wind 150 deg+1.0 Ice
43	1.2 Dead+1.0 Wind 180 deg+1.0 Ice
44	1.2 Dead+1.0 Wind 210 deg+1.0 Ice
45	1.2 Dead+1.0 Wind 225 deg+1.0 Ice
46	1.2 Dead+1.0 Wind 240 deg+1.0 Ice
47	1.2 Dead+1.0 Wind 270 deg+1.0 Ice
48	1.2 Dead+1.0 Wind 300 deg+1.0 Ice
49	1.2 Dead+1.0 Wind 315 deg+1.0 Ice
50	1.2 Dead+1.0 Wind 330 deg+1.0 Ice
51	Dead+Wind 0 deg - Service
52	Dead+Wind 30 deg - Service
53	Dead+Wind 45 deg - Service
54	Dead+Wind 60 deg - Service
55	Dead+Wind 90 deg - Service
56	Dead+Wind 120 deg - Service
57	Dead+Wind 135 deg - Service
58	Dead+Wind 150 deg - Service
59	Dead+Wind 180 deg - Service
60	Dead+Wind 210 deg - Service
61	Dead+Wind 225 deg - Service
62	Dead+Wind 240 deg - Service
63	Dead+Wind 270 deg - Service
64	Dead+Wind 300 deg - Service
65	Dead+Wind 315 deg - Service
66	Dead+Wind 330 deg - Service

Maximum Member Forces

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Axial lb	Major Axis Moment kip-ft	Minor Axis Moment kip-ft	
T1	180 - 160	Leg	Max Tension	31	2515.64	-0.27	-0.18	
			Max. Compression	2	-4183.04	-0.06	-0.02	
			Max. Mx	14	-410.23	-0.53	-0.01	
			Max. My	33	-144.55	-0.01	-0.92	
			Max. Vy	3	328.07	0.52	0.33	
			Max. Vx	32	-471.79	-0.01	0.74	
		Diagonal	Max Tension	5	4061.67	0.00	0.00	
			Max. Compression	4	-4128.96	0.00	0.00	
			Max. Mx	34	-69.73	0.05	0.00	
			Max. Vy	34	22.77	0.00	0.00	
			Horizontal	Max Tension	4	2233.61	-0.01	-0.00
				Max. Compression	5	-2199.42	-0.01	-0.00
		Max. Mx		49	-126.51	-0.02	-0.00	
		Max. My		3	-297.94	-0.00	0.00	
		Max. Vy		49	23.92	-0.02	-0.00	
		Max. Vx		3	-0.81	0.00	0.00	

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job	22027.01 - Westport	Page	49 of 73
	Project	180-ft Lattice Tower (CSP #32)	Date	15:45:34 06/11/24
	Client	Verizon	Designed by	TJL

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Axial lb	Major Axis Moment kip-ft	Minor Axis Moment kip-ft	
T2	160 - 140	Top Girt	Max Tension	33	324.64	-0.01	0.00	
			Max. Compression	2	-352.97	-0.01	-0.00	
			Max. Mx	49	15.92	-0.02	-0.00	
			Max. My	3	-51.93	-0.00	0.00	
			Max. Vy	49	-23.10	-0.02	-0.00	
			Max. Vx	3	-0.13	0.00	0.00	
		Inner Bracing	Max Tension	3	1.84	0.00	0.00	
			Max. Compression	18	-1.84	0.00	0.00	
			Max. Mx	34	-0.10	-0.02	0.00	
			Max. Vy	34	19.13	0.00	0.00	
			Leg	Max Tension	19	21755.95	-0.58	-0.03
				Max. Compression	2	-29174.98	0.79	0.08
		Max. Mx		8	19255.83	1.03	0.09	
		Max. My		18	-15607.62	0.37	0.90	
		Max. Vy		18	-2396.71	0.07	0.02	
		Max. Vx		8	2301.54	-0.02	-0.08	
		Diagonal	Max Tension	5	9263.08	0.00	0.00	
			Max. Compression	4	-9339.82	0.00	0.00	
			Max. Mx	34	-194.19	0.06	0.00	
			Max. Vy	34	-28.02	0.00	0.00	
			Horizontal	Max Tension	5	5811.45	-0.01	0.00
				Max. Compression	5	-5810.94	-0.01	0.00
		Max. Mx		49	22.05	-0.03	-0.00	
		Max. My		2	2246.18	-0.01	0.01	
Max. Vy	49	-27.90		-0.03	-0.00			
Max. Vx	2	-2.40		-0.01	0.01			
Inner Bracing	Max Tension	3	4.62	0.00	0.00			
	Max. Compression	18	-6.50	0.00	0.00			
	Max. Mx	34	-3.22	-0.03	0.00			
	Max. Vy	34	22.00	0.00	0.00			
	Leg	Max Tension	19	30667.07	-0.84	-0.08		
		Max. Compression	2	-39111.98	0.01	-0.04		
Max. Mx		18	29620.46	-0.85	-0.08			
Max. My		11	-3856.22	-0.02	0.86			
Max. Vy		18	-190.80	-0.85	-0.08			
Max. Vx		10	242.29	-0.03	0.86			
Diagonal	Max Tension	5	10037.79	0.00	0.00			
	Max. Compression	4	-10147.34	0.00	0.00			
	Max. Mx	34	-214.84	0.08	0.00			
	Max. Vy	34	-34.37	0.00	0.00			
	Horizontal	Max Tension	5	6544.21	-0.01	0.00		
		Max. Compression	5	-6536.27	-0.01	0.00		
Max. Mx		48	-298.90	-0.04	-0.00			
Max. My		3	1361.43	-0.00	0.01			
Max. Vy		48	-36.05	-0.04	-0.00			
Max. Vx		3	2.59	0.00	0.00			
Inner Bracing	Max Tension	3	4.60	0.00	0.00			
	Max. Compression	18	-7.43	0.00	0.00			
	Max. Mx	34	-3.80	-0.03	0.00			
	Max. Vy	34	-23.31	0.00	0.00			
	Leg	Max Tension	19	40590.95	-0.01	0.04		
		Max. Compression	2	-51882.14	1.17	-0.01		
Max. Mx		18	37448.23	-1.24	0.01			
Max. My		11	-5815.56	-0.03	1.30			
Max. Vy		28	-2430.43	-0.02	-0.02			
Max. Vx		4	-2536.18	-0.01	0.04			
Diagonal	Max Tension	5	12523.41	0.00	0.00			
	Max. Compression	4	-12641.14	0.00	0.00			
	Max. Mx	34	-208.92	0.08	0.00			
	Max. Vy	34	-36.33	0.00	0.00			

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job	22027.01 - Westport	Page	50 of 73
	Project	180-ft Lattice Tower (CSP #32)	Date	15:45:34 06/11/24
	Client	Verizon	Designed by	TJL

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Axial lb	Major Axis Moment kip-ft	Minor Axis Moment kip-ft	
T5	126.667 - 120	Top Girt	Max Tension	7	8471.02	-0.01	0.01	
			Max. Compression	4	-8463.67	-0.02	0.00	
			Max. Mx	48	-537.67	-0.05	-0.00	
			Max. My	2	726.75	-0.01	0.02	
			Max. Vy	48	-38.40	-0.05	-0.00	
			Max. Vx	2	3.57	0.00	0.00	
		Inner Bracing	Max Tension	3	6.79	0.00	0.00	
			Max. Compression	18	-9.77	0.00	0.00	
			Max. Mx	34	-4.01	-0.04	0.00	
			Max. Vy	34	-24.69	0.00	0.00	
			Leg	Max Tension	19	52845.22	-1.23	0.01
				Max. Compression	2	-67259.41	0.80	-0.11
		Max. Mx		18	51119.68	-1.24	0.01	
		Max. My		11	-6039.00	-0.03	1.30	
		Max. Vy		18	-1147.74	-1.24	0.01	
		Max. Vx		10	1237.84	-0.04	1.30	
		Diagonal		Max Tension	5	14075.62	0.00	0.00
				Max. Compression	4	-14258.96	0.00	0.00
			Max. Mx	34	-229.10	0.12	0.00	
			Max. Vy	34	53.61	0.00	0.00	
Top Girt	Max Tension	5	9772.94	-0.02	0.00			
	Max. Compression	5	-9772.56	-0.02	0.00			
	Max. Mx	48	-493.64	-0.06	-0.01			
	Max. My	3	1653.27	-0.00	0.02			
	Max. Vy	48	40.50	-0.06	-0.01			
	Max. Vx	3	-3.56	-0.00	0.02			
T6	120 - 100	Inner Bracing	Max Tension	3	6.17	0.00	0.00	
			Max. Compression	18	-10.60	0.00	0.00	
			Max. Mx	34	-4.93	-0.04	0.00	
			Max. Vy	34	26.06	0.00	0.00	
			Leg	Max Tension	19	90268.60	-0.56	0.17
				Max. Compression	2	-108254.33	0.28	-0.15
		Max. Mx		18	65668.44	-0.84	0.11	
		Max. My		11	-7189.84	-0.01	1.09	
		Max. Vy		18	-143.53	-0.84	0.11	
		Max. Vx		28	-374.56	0.25	-0.90	
		Diagonal		Max Tension	5	17940.66	0.00	0.00
				Max. Compression	4	-18251.70	0.00	0.00
Max. Mx	34		-302.14	0.27	0.00			
Max. Vy	34		-86.80	0.00	0.00			
Horizontal	Max Tension	6	10966.10	-0.02	0.01			
	Max. Compression	15	-10834.39	-0.03	-0.01			
	Max. Mx	38	-543.37	-0.08	-0.01			
	Max. My	18	-1058.17	-0.05	-0.02			
	Max. Vy	38	46.35	-0.08	-0.01			
	Max. Vx	18	-3.23	-0.05	-0.02			
	Inner Bracing	Max Tension	3	3.56	0.00	0.00		
		Max. Compression	18	-12.09	0.00	0.00		
Max. Mx		34	-8.55	-0.07	0.00			
Max. Vy		34	39.46	0.00	0.00			
T7	100 - 90	Leg	Max Tension	19	112503.78	-0.31	0.15	
			Max. Compression	2	-132360.06	0.64	-0.14	
			Max. Mx	18	109516.59	-0.69	0.14	
			Max. My	10	-11786.76	-0.02	0.91	
			Max. Vy	18	151.79	-0.69	0.14	
			Max. Vx	29	362.12	0.31	-0.87	
		Diagonal	Max Tension	15	17223.83	0.00	0.00	
			Max. Compression	14	-17456.40	0.00	0.00	
			Max. Mx	34	-330.13	0.22	0.00	
			Max. Vy	34	-67.81	0.00	0.00	
			Horizontal	Max Tension	31	11196.15	0.00	0.00

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 51 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by T.J.L.

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Axial lb	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
T8	90 - 80	Inner Bracing	Max. Compression	14	-11222.23	-0.04	-0.00
			Max. Mx	38	-778.64	-0.08	-0.00
			Max. My	18	-958.32	-0.05	-0.02
			Max. Vy	38	48.84	-0.08	-0.00
			Max. Vx	18	2.53	0.00	0.00
			Max Tension	3	2.54	0.00	0.00
			Max. Compression	43	-10.24	0.00	0.00
			Max. Mx	34	-8.65	-0.08	0.00
			Max. Vy	34	-42.12	0.00	0.00
			Max Tension	19	132619.88	-0.68	0.14
		Leg	Max. Compression	2	-154045.60	0.59	-0.14
			Max. Mx	18	129829.48	-0.69	0.14
			Max. My	10	-12693.35	-0.03	1.05
			Max. Vy	18	-117.93	-0.69	0.14
			Max. Vx	12	-332.43	-0.33	1.00
			Max Tension	15	17808.28	0.00	0.00
			Max. Compression	14	-18058.72	0.00	0.00
			Max. Mx	34	-355.62	0.24	0.00
			Max. Vy	34	-72.80	0.00	0.00
			Max Tension	30	12042.99	0.00	0.00
Diagonal	Max. Compression	15	-12002.68	-0.03	-0.00		
	Max. Mx	38	-596.04	-0.09	-0.00		
	Max. My	18	-1072.43	-0.06	-0.02		
	Max. Vy	38	52.37	-0.09	-0.00		
	Max. Vx	18	-2.18	-0.06	-0.02		
	Max Tension	3	1.59	0.00	0.00		
	Max. Compression	43	-10.47	0.00	0.00		
	Max. Mx	34	-9.06	-0.09	0.00		
	Max. Vy	34	45.38	0.00	0.00		
	Max Tension	19	172100.21	-1.16	0.08		
Top Girt	Max. Compression	2	-197499.29	1.76	-0.17		
	Max. Mx	18	168180.30	-1.77	0.18		
	Max. My	10	-15037.39	-0.02	1.95		
	Max. Vy	18	264.83	-1.77	0.18		
	Max. Vx	13	-486.88	-0.89	1.81		
	Max Tension	15	19772.08	0.00	0.00		
	Max. Compression	14	-20108.08	0.00	0.00		
	Max. Mx	34	-442.43	0.29	0.00		
	Max. Vy	34	82.17	0.00	0.00		
	Max Tension	30	14315.32	0.00	0.00		
Horizontal	Max. Compression	15	-14293.07	-0.07	-0.01		
	Max. Mx	38	-561.42	-0.16	-0.01		
	Max. My	3	374.99	-0.03	0.03		
	Max. Vy	38	79.36	-0.16	-0.01		
	Max. Vx	18	-2.89	-0.10	-0.03		
	Max Tension	3	2.64	0.00	0.00		
	Max. Compression	43	-12.32	0.00	0.00		
	Max. Mx	34	-10.57	-0.14	0.00		
	Max. Vy	34	60.35	0.00	0.00		
	Max Tension	19	212123.82	-1.18	0.09		
Inner Bracing	Max. Compression	2	-242594.77	1.05	-0.10		
	Max. Mx	18	188378.63	-1.77	0.18		
	Max. My	10	-15615.57	-0.03	1.95		
	Max. Vy	8	-306.27	-1.73	0.32		
	Max. Vx	11	470.34	-0.02	1.95		
	Max Tension	15	21552.49	0.00	0.00		
	Max. Compression	14	-22044.13	0.00	0.00		
	Max. Mx	34	-558.04	0.41	0.00		
	Max. Vy	34	-108.89	0.00	0.00		
	Max Tension	30	16442.28	0.00	0.00		
Horizontal	Max. Compression	15	-16397.63	-0.08	-0.01		

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job	22027.01 - Westport	Page	52 of 73
	Project	180-ft Lattice Tower (CSP #32)	Date	15:45:34 06/11/24
	Client	Verizon	Designed by	TJL

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Axial lb	Major Axis Moment kip-ft	Minor Axis Moment kip-ft	
T11	40 - 30	Inner Bracing	Max. Mx	38	-496.96	-0.20	-0.01	
			Max. My	3	1814.20	-0.04	0.03	
			Max. Vy	38	87.65	-0.20	-0.01	
			Max. Vx	3	-2.65	0.00	0.00	
			Max Tension	3	0.65	0.00	0.00	
			Max. Compression	43	-14.71	0.00	0.00	
			Max. Mx	34	-13.18	-0.23	0.00	
			Max. Vy	34	85.20	0.00	0.00	
			Max Tension	19	232115.95	-1.12	0.10	
			Max. Compression	2	-265467.44	2.47	-0.07	
			Max. Mx	2	-265467.44	2.47	-0.07	
			Max. My	10	-18350.96	-0.06	1.31	
		Leg	Max. Vy	3	-303.24	2.45	-0.07	
			Max. Vx	12	376.65	-0.60	1.22	
			Max Tension	15	22257.57	0.00	0.00	
			Max. Compression	14	-22784.95	0.00	0.00	
			Max. Mx	34	-594.85	0.44	0.00	
			Max. Vy	34	-113.09	0.00	0.00	
			Diagonal	Max Tension	30	17358.60	0.00	0.00
				Max. Compression	15	-17342.36	-0.09	-0.01
				Max. Mx	38	-533.50	-0.21	-0.01
				Max. My	3	2030.93	-0.06	0.03
				Max. Vy	38	90.67	-0.21	-0.01
				Max. Vx	3	-2.30	0.00	0.00
Horizontal	Max Tension	1	0.00	0.00	0.00			
	Max. Compression	43	-14.96	0.00	0.00			
	Max. Mx	34	-13.53	-0.25	0.00			
	Max. Vy	34	88.05	0.00	0.00			
	Inner Bracing	Max Tension	19	251901.83	-2.27	0.08		
		Max. Compression	2	-288285.84	-2.13	-0.32		
		Max. Mx	2	-287621.09	2.47	-0.07		
		Max. My	10	-20405.22	-0.55	4.79		
		Max. Vy	2	605.97	2.47	-0.07		
		Max. Vx	10	-692.47	-0.55	4.79		
	Leg	Max Tension	15	22878.32	0.00	0.00		
		Max. Compression	14	-23490.97	0.00	0.00		
Max. Mx		34	-650.13	0.47	0.00			
Max. Vy		34	-117.29	0.00	0.00			
Diagonal		Max Tension	14	18179.78	-0.17	-0.01		
		Max. Compression	15	-18017.42	-0.13	-0.01		
	Max. Mx	38	780.92	-0.28	-0.01			
	Max. My	3	-459.89	-0.10	0.02			
	Max. Vy	38	-110.82	-0.28	-0.01			
	Max. Vx	3	1.98	0.00	0.00			
Top Girt	Max Tension	1	0.00	0.00	0.00			
	Max. Compression	43	-15.80	0.00	0.00			
	Max. Mx	34	-14.57	-0.27	0.00			
	Max. Vy	34	90.88	0.00	0.00			
	Inner Bracing	Max Tension	19	269969.01	1.23	0.33		
		Max. Compression	2	-310698.07	0.00	0.00		
Max. Mx		2	-309913.34	7.16	0.40			
Max. My		10	-21456.57	-0.55	4.79			
Max. Vy		2	-1053.47	7.16	0.40			
Max. Vx		10	1169.73	-0.55	4.79			
Leg	Max Tension	31	33802.81	-0.14	0.04			
	Max. Compression	14	-35039.49	0.00	0.00			
	Max. Mx	30	13066.72	-0.24	-0.03			
	Max. My	2	-27370.75	-0.03	0.05			
	Diagonal	Max. Vy	50	-78.19	-0.19	0.00		
		Max. Vx	2	3.72	0.00	0.00		
Horizontal		Max Tension	30	19348.68	0.00	0.00		

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job	22027.01 - Westport	Page	53 of 73
	Project	180-ft Lattice Tower (CSP #32)	Date	15:45:34 06/11/24
	Client	Verizon	Designed by	TJL

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Axial lb	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
			Max. Compression	15	-19566.81	-0.20	-0.01
			Max. Mx	38	-868.38	-0.40	-0.01
			Max. My	3	2719.97	-0.07	0.05
			Max. Vy	38	139.94	-0.40	-0.01
			Max. Vx	3	4.23	0.00	0.00
		Redund Horz 1 Bracing	Max Tension	4	1317.92	0.00	0.00
			Max. Compression	5	-1173.77	0.00	0.00
			Max. Mx	34	188.76	0.03	0.00
			Max. Vy	34	-21.73	0.00	0.00
		Redund Diag 1 Bracing	Max Tension	4	1255.45	0.00	0.00
			Max. Compression	5	-1107.30	0.00	0.00
			Max. Mx	34	96.20	0.07	0.00
			Max. Vy	34	-24.49	0.00	0.00
		Redund Hip 1 Bracing	Max Tension	3	1.82	0.00	0.00
			Max. Compression	18	-17.58	0.00	0.00
			Max. Mx	34	-13.55	0.06	0.00
			Max. Vy	34	-37.18	0.00	0.00
		Inner Bracing	Max Tension	1	0.00	0.00	0.00
			Max. Compression	43	-14.23	0.00	0.00
			Max. Mx	34	-12.55	0.17	0.00
			Max. Vy	34	54.27	0.00	0.00

Maximum Reactions

Location	Condition	Gov. Load Comb.	Vertical lb	Horizontal, X lb	Horizontal, Z lb
Leg C	Max. Vert	24	341930.23	41521.25	-26965.10
	Max. H _x	24	341930.23	41521.25	-26965.10
	Max. H _z	7	-296293.50	-36156.98	25662.94
	Min. Vert	9	-304452.43	-38001.64	24967.61
	Min. H _x	9	-304452.43	-38001.64	24967.61
	Min. H _z	22	330071.26	38699.33	-27096.56
Leg B	Max. Vert	12	344510.36	-40999.51	-28214.57
	Max. H _x	29	-304857.44	37442.63	26108.87
	Max. H _z	31	-297315.65	35390.74	27271.54
	Min. Vert	29	-304857.44	37442.63	26108.87
	Min. H _x	12	344510.36	-40999.51	-28214.57
	Min. H _z	14	334289.47	-38360.74	-29094.89
Leg A	Max. Vert	2	353608.21	1247.47	50354.54
	Max. H _x	26	23763.73	12843.11	1927.24
	Max. H _z	2	353608.21	1247.47	50354.54
	Min. Vert	19	-308494.80	-1251.87	-45868.48
	Min. H _x	11	18334.13	-12868.10	1489.60
	Min. H _z	19	-308494.80	-1251.87	-45868.48

Tower Mast Reaction Summary

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 54 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by T.J.L.

Load Combination	Vertical lb	Shear _x lb	Shear _z lb	Overturning Moment, M _x kip-ft	Overturning Moment, M _z kip-ft	Torque kip-ft
Dead Only	54379.73	0.00	-0.00	-18.52	-9.48	0.00
1.2 Dead+1.0 Wind 0 deg - No Ice	65255.68	1.43	-86954.21	-7954.26	-11.63	59.45
0.9 Dead+1.0 Wind 0 deg - No Ice	48941.76	1.43	-86954.21	-7948.70	-8.79	59.45
1.2 Dead+1.0 Wind 30 deg - No Ice	65255.68	42441.04	-73545.11	-6783.28	-3911.29	-40.17
0.9 Dead+1.0 Wind 30 deg - No Ice	48941.76	42441.04	-73545.11	-6777.73	-3908.45	-40.17
1.2 Dead+1.0 Wind 45 deg - No Ice	65255.68	59583.97	-59678.15	-5506.45	-5478.94	-86.03
0.9 Dead+1.0 Wind 45 deg - No Ice	48941.76	59583.97	-59678.15	-5500.90	-5476.09	-86.03
1.2 Dead+1.0 Wind 60 deg - No Ice	65255.68	72418.73	-41955.78	-3877.81	-6645.05	-125.86
0.9 Dead+1.0 Wind 60 deg - No Ice	48941.76	72418.73	-41955.78	-3872.25	-6642.21	-125.86
1.2 Dead+1.0 Wind 90 deg - No Ice	65255.68	83841.63	-179.39	-53.98	-7635.34	-179.68
0.9 Dead+1.0 Wind 90 deg - No Ice	48941.76	83841.63	-179.39	-48.42	-7632.49	-179.68
1.2 Dead+1.0 Wind 120 deg - No Ice	65255.68	74341.86	42852.20	3837.33	-6717.50	-187.89
0.9 Dead+1.0 Wind 120 deg - No Ice	48941.76	74341.86	42852.20	3842.88	-6714.66	-187.89
1.2 Dead+1.0 Wind 135 deg - No Ice	65255.68	60295.26	60328.31	5466.35	-5494.10	-172.36
0.9 Dead+1.0 Wind 135 deg - No Ice	48941.76	60295.26	60328.31	5471.91	-5491.26	-172.36
1.2 Dead+1.0 Wind 150 deg - No Ice	65255.68	42368.31	73459.32	6721.13	-3896.97	-144.49
0.9 Dead+1.0 Wind 150 deg - No Ice	48941.76	42368.31	73459.32	6726.69	-3894.12	-144.49
1.2 Dead+1.0 Wind 180 deg - No Ice	65255.68	19.18	84488.04	7779.78	-14.78	-60.27
0.9 Dead+1.0 Wind 180 deg - No Ice	48941.76	19.18	84488.04	7785.34	-11.93	-60.27
1.2 Dead+1.0 Wind 210 deg - No Ice	65255.68	-42285.64	73266.92	6689.59	3861.03	38.08
0.9 Dead+1.0 Wind 210 deg - No Ice	48941.76	-42285.64	73266.92	6695.15	3863.87	38.08
1.2 Dead+1.0 Wind 225 deg - No Ice	65255.68	-59325.38	59379.32	5409.11	5410.41	83.97
0.9 Dead+1.0 Wind 225 deg - No Ice	48941.76	-59325.38	59379.32	5414.66	5413.25	83.97
1.2 Dead+1.0 Wind 240 deg - No Ice	65255.68	-74094.35	42772.02	3824.59	6653.45	123.79
0.9 Dead+1.0 Wind 240 deg - No Ice	48941.76	-74094.35	42772.02	3830.14	6656.29	123.79
1.2 Dead+1.0 Wind 270 deg - No Ice	65255.68	-83783.41	-146.87	-48.22	7602.27	177.93
0.9 Dead+1.0 Wind 270 deg - No Ice	48941.76	-83783.41	-146.87	-42.67	7605.12	177.93
1.2 Dead+1.0 Wind 300 deg - No Ice	65255.68	-72534.78	-42064.33	-3895.57	6640.31	186.86
0.9 Dead+1.0 Wind 300 deg - No Ice	48941.76	-72534.78	-42064.33	-3890.01	6643.16	186.86
1.2 Dead+1.0 Wind 315 deg - No Ice	65255.68	-59743.75	-59881.89	-5540.14	5482.09	171.29
0.9 Dead+1.0 Wind 315 deg - No Ice	48941.76	-59743.75	-59881.89	-5534.59	5484.93	171.29

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 55 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by TJL

Load Combination	Vertical lb	Shear _x lb	Shear _z lb	Overturning Moment, M _x kip-ft	Overturning Moment, M _z kip-ft	Torque kip-ft
1.2 Dead+1.0 Wind 330 deg - No Ice	65255.68	-42542.27	-73788.58	-6823.86	3905.00	143.53
0.9 Dead+1.0 Wind 330 deg - No Ice	48941.76	-42542.27	-73788.58	-6818.31	3907.84	143.53
1.2 Dead+1.0 Ice	138105.45	0.00	-0.00	-160.52	-67.97	0.00
1.2 Dead+1.0 Wind 0 deg+1.0 Ice	138105.45	0.23	-22746.10	-2213.02	-68.01	26.51
1.2 Dead+1.0 Wind 30 deg+1.0 Ice	138105.45	11200.76	-19405.80	-1919.20	-1082.78	4.20
1.2 Dead+1.0 Wind 45 deg+1.0 Ice	138105.45	15762.05	-15776.89	-1589.31	-1494.13	-7.52
1.2 Dead+1.0 Wind 60 deg+1.0 Ice	138105.45	19205.08	-11110.88	-1166.24	-1802.94	-18.69
1.2 Dead+1.0 Wind 90 deg+1.0 Ice	138105.45	22199.76	-28.27	-165.53	-2063.49	-36.89
1.2 Dead+1.0 Wind 120 deg+1.0 Ice	138105.45	19514.27	11255.68	845.76	-1814.23	-45.66
1.2 Dead+1.0 Wind 135 deg+1.0 Ice	138105.45	15875.85	15881.06	1268.76	-1496.34	-45.41
1.2 Dead+1.0 Wind 150 deg+1.0 Ice	138105.45	11188.43	19390.80	1595.11	-1080.37	-41.96
1.2 Dead+1.0 Wind 180 deg+1.0 Ice	138105.45	3.02	22348.66	1871.33	-68.51	-26.64
1.2 Dead+1.0 Wind 210 deg+1.0 Ice	138105.45	-11176.27	19361.96	1590.39	942.50	-4.52
1.2 Dead+1.0 Wind 225 deg+1.0 Ice	138105.45	-15721.30	15729.80	1259.93	1350.98	7.19
1.2 Dead+1.0 Wind 240 deg+1.0 Ice	138105.45	-19476.76	11243.91	843.89	1672.04	18.36
1.2 Dead+1.0 Wind 270 deg+1.0 Ice	138105.45	-22190.59	-23.14	-164.62	1925.92	36.61
1.2 Dead+1.0 Wind 300 deg+1.0 Ice	138105.45	-19221.88	-11127.12	-1168.90	1669.58	45.50
1.2 Dead+1.0 Wind 315 deg+1.0 Ice	138105.45	-15785.82	-15807.59	-1594.38	1362.03	45.24
1.2 Dead+1.0 Wind 330 deg+1.0 Ice	138105.45	-11215.85	-19442.68	-1925.34	949.28	41.81
Dead+Wind 0 deg - Service	54379.73	0.30	-18787.48	-1737.43	-9.54	12.66
Dead+Wind 30 deg - Service	54379.73	9173.04	-15895.64	-1484.07	-854.86	-8.56
Dead+Wind 45 deg - Service	54379.73	12879.61	-12899.67	-1207.44	-1194.85	-18.33
Dead+Wind 60 deg - Service	54379.73	15655.70	-9069.67	-854.45	-1447.90	-26.81
Dead+Wind 90 deg - Service	54379.73	18124.45	-38.21	-25.29	-1662.77	-38.28
Dead+Wind 120 deg - Service	54379.73	16065.36	9260.62	818.25	-1463.33	-40.02
Dead+Wind 135 deg - Service	54379.73	13031.12	13038.17	1171.32	-1198.08	-36.72
Dead+Wind 150 deg - Service	54379.73	9157.55	15877.37	1443.26	-851.80	-30.78
Dead+Wind 180 deg - Service	54379.73	4.09	18262.14	1672.69	-10.21	-12.84
Dead+Wind 210 deg - Service	54379.73	-9139.94	15836.38	1436.54	830.03	8.11
Dead+Wind 225 deg - Service	54379.73	-12824.52	12836.01	1159.13	1166.13	17.89
Dead+Wind 240 deg - Service	54379.73	-16012.64	9243.54	815.54	1435.57	26.37
Dead+Wind 270 deg - Service	54379.73	-18112.04	-31.28	-24.06	1641.60	37.90
Dead+Wind 300 deg - Service	54379.73	-15680.42	-9092.79	-858.24	1432.77	39.81
Dead+Wind 315 deg - Service	54379.73	-12913.64	-12943.07	-1214.62	1181.40	36.49
Dead+Wind 330 deg - Service	54379.73	-9194.60	-15947.51	-1492.72	839.40	30.57

Solution Summary

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job	22027.01 - Westport	Page	56 of 73	
	Project	180-ft Lattice Tower (CSP #32)		Date	15:45:34 06/11/24
	Client	Verizon		Designed by	TJL

Load Comb.	Sum of Applied Forces			Sum of Reactions			% Error
	PX lb	PY lb	PZ lb	PX lb	PY lb	PZ lb	
1	0.00	-54379.73	0.00	-0.00	54379.73	0.00	0.000%
2	1.43	-65255.68	-86954.21	-1.43	65255.68	86954.21	0.000%
3	1.43	-48941.76	-86954.21	-1.43	48941.76	86954.21	0.000%
4	42441.04	-65255.68	-73545.11	-42441.04	65255.68	73545.11	0.000%
5	42441.04	-48941.76	-73545.11	-42441.04	48941.76	73545.11	0.000%
6	59583.97	-65255.68	-59678.15	-59583.97	65255.68	59678.15	0.000%
7	59583.97	-48941.76	-59678.15	-59583.97	48941.76	59678.15	0.000%
8	72418.73	-65255.68	-41955.78	-72418.73	65255.68	41955.78	0.000%
9	72418.73	-48941.76	-41955.78	-72418.73	48941.76	41955.78	0.000%
10	83841.63	-65255.68	-179.39	-83841.63	65255.68	179.39	0.000%
11	83841.63	-48941.76	-179.39	-83841.63	48941.76	179.39	0.000%
12	74341.86	-65255.68	42852.20	-74341.86	65255.68	-42852.20	0.000%
13	74341.86	-48941.76	42852.20	-74341.86	48941.76	-42852.20	0.000%
14	60295.26	-65255.68	60328.31	-60295.26	65255.68	-60328.31	0.000%
15	60295.26	-48941.76	60328.31	-60295.26	48941.76	-60328.31	0.000%
16	42368.31	-65255.68	73459.32	-42368.31	65255.68	-73459.32	0.000%
17	42368.31	-48941.76	73459.32	-42368.31	48941.76	-73459.32	0.000%
18	19.18	-65255.68	84488.04	-19.18	65255.68	-84488.04	0.000%
19	19.18	-48941.76	84488.04	-19.18	48941.76	-84488.04	0.000%
20	-42285.64	-65255.68	73266.92	42285.64	65255.68	-73266.92	0.000%
21	-42285.64	-48941.76	73266.92	42285.64	48941.76	-73266.92	0.000%
22	-59325.38	-65255.68	59379.32	59325.38	65255.68	-59379.32	0.000%
23	-59325.38	-48941.76	59379.32	59325.38	48941.76	-59379.32	0.000%
24	-74094.35	-65255.68	42772.02	74094.35	65255.68	-42772.02	0.000%
25	-74094.35	-48941.76	42772.02	74094.35	48941.76	-42772.02	0.000%
26	-83783.41	-65255.68	-146.87	83783.41	65255.68	146.87	0.000%
27	-83783.41	-48941.76	-146.87	83783.41	48941.76	146.87	0.000%
28	-72534.78	-65255.68	-42064.33	72534.78	65255.68	42064.33	0.000%
29	-72534.78	-48941.76	-42064.33	72534.78	48941.76	42064.33	0.000%
30	-59743.74	-65255.68	-59881.89	59743.75	65255.68	59881.89	0.000%
31	-59743.74	-48941.76	-59881.89	59743.75	48941.76	59881.89	0.000%
32	-42542.27	-65255.68	-73788.58	42542.27	65255.68	73788.58	0.000%
33	-42542.27	-48941.76	-73788.58	42542.27	48941.76	73788.58	0.000%
34	0.00	-138105.45	0.00	-0.00	138105.45	0.00	0.000%
35	0.23	-138105.45	-22746.10	-0.23	138105.45	22746.10	0.000%
36	11200.75	-138105.45	-19405.80	-11200.76	138105.45	19405.80	0.000%
37	15762.05	-138105.45	-15776.89	-15762.05	138105.45	15776.89	0.000%
38	19205.08	-138105.45	-11110.88	-19205.08	138105.45	11110.88	0.000%
39	22199.76	-138105.45	-28.27	-22199.76	138105.45	28.27	0.000%
40	19514.27	-138105.45	11255.68	-19514.27	138105.45	-11255.68	0.000%
41	15875.85	-138105.45	15881.06	-15875.85	138105.45	-15881.06	0.000%
42	11188.43	-138105.45	19390.80	-11188.43	138105.45	-19390.80	0.000%
43	3.02	-138105.45	22348.66	-3.02	138105.45	-22348.66	0.000%
44	-11176.27	-138105.45	19361.96	11176.27	138105.45	-19361.96	0.000%
45	-15721.30	-138105.45	15729.80	15721.30	138105.45	-15729.80	0.000%
46	-19476.76	-138105.45	11243.91	19476.76	138105.45	-11243.91	0.000%
47	-22190.59	-138105.45	-23.14	22190.59	138105.45	23.14	0.000%
48	-19221.88	-138105.45	-11127.12	19221.88	138105.45	11127.12	0.000%
49	-15785.82	-138105.45	-15807.59	15785.82	138105.45	15807.59	0.000%
50	-11215.85	-138105.45	-19442.68	11215.85	138105.45	19442.68	0.000%
51	0.30	-54379.73	-18787.48	-0.30	54379.73	18787.48	0.000%
52	9173.04	-54379.73	-15895.64	-9173.04	54379.73	15895.64	0.000%
53	12879.61	-54379.73	-12899.67	-12879.61	54379.73	12899.67	0.000%
54	15655.70	-54379.73	-9069.67	-15655.70	54379.73	9069.67	0.000%
55	18124.45	-54379.73	-38.21	-18124.45	54379.73	38.21	0.000%
56	16065.36	-54379.73	9260.62	-16065.36	54379.73	-9260.62	0.000%
57	13031.12	-54379.73	13038.17	-13031.12	54379.73	-13038.17	0.000%
58	9157.55	-54379.73	15877.37	-9157.55	54379.73	-15877.37	0.000%
59	4.09	-54379.73	18262.14	-4.09	54379.73	-18262.14	0.000%
60	-9139.94	-54379.73	15836.38	9139.94	54379.73	-15836.38	0.000%
61	-12824.52	-54379.73	12836.01	12824.52	54379.73	-12836.01	0.000%

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 57 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by TJL

Load Comb.	Sum of Applied Forces			Sum of Reactions			% Error
	PX lb	PY lb	PZ lb	PX lb	PY lb	PZ lb	
62	-16012.64	-54379.73	9243.54	16012.64	54379.73	-9243.54	0.000%
63	-18112.04	-54379.73	-31.28	18112.04	54379.73	31.28	0.000%
64	-15680.42	-54379.73	-9092.79	15680.42	54379.73	9092.79	0.000%
65	-12913.64	-54379.73	-12943.07	12913.64	54379.73	12943.07	0.000%
66	-9194.60	-54379.73	-15947.51	9194.60	54379.73	15947.51	0.000%

Maximum Tower Deflections - Service Wind

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
T1	180 - 160	1.991	51	0.0854	0.0575
T2	160 - 140	1.629	51	0.0839	0.0522
T3	140 - 133.333	1.267	51	0.0763	0.0440
T4	133.333 - 126.667	1.155	51	0.0740	0.0425
T5	126.667 - 120	1.044	51	0.0712	0.0407
T6	120 - 100	0.939	51	0.0675	0.0393
T7	100 - 90	0.672	51	0.0540	0.0351
T8	90 - 80	0.553	51	0.0475	0.0313
T9	80 - 60	0.449	51	0.0404	0.0273
T10	60 - 40	0.270	51	0.0312	0.0198
T11	40 - 30	0.135	51	0.0207	0.0133
T12	30 - 20	0.083	51	0.0152	0.0099
T13	20 - 0	0.044	62	0.0094	0.0069

Critical Deflections and Radius of Curvature - Service Wind

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
187.00	ANT940Y10-WR	51	1.991	0.0854	0.0575	496094
181.00	ANT940Y10-WR	51	1.991	0.0854	0.0575	496094
177.00	PA6-65AC	51	1.937	0.0854	0.0572	496094
170.00	RFI BPS7496-180-14 Panel Antenna	51	1.812	0.0853	0.0560	248047
169.00	3' Yagi	51	1.794	0.0852	0.0558	225498
160.00	ROHN 6'x15' Boom Gate (1)	51	1.629	0.0839	0.0522	147218
144.00	FFVV-65B-R2	51	1.336	0.0779	0.0453	85493
133.00	QD6616-7	51	1.150	0.0739	0.0424	290354
125.00	LTF12=372 Sector Mount (1)	51	1.017	0.0704	0.0403	59362
113.00	ANT150D	51	0.839	0.0630	0.0381	76796
60.00	GPS	51	0.270	0.0312	0.0198	99661

Maximum Tower Deflections - Design Wind

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
-------------	--------------	---------------------	-----------------	--------	---------

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 58 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by TJL

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
T1	180 - 160	9.082	2	0.3836	0.2700
T2	160 - 140	7.452	2	0.3787	0.2451
T3	140 - 133.333	5.799	2	0.3478	0.2065
T4	133.333 - 126.667	5.289	2	0.3374	0.1993
T5	126.667 - 120	4.778	2	0.3248	0.1910
T6	120 - 100	4.300	2	0.3083	0.1846
T7	100 - 90	3.077	2	0.2464	0.1647
T8	90 - 80	2.536	2	0.2167	0.1471
T9	80 - 60	2.058	2	0.1844	0.1282
T10	60 - 40	1.240	2	0.1422	0.0930
T11	40 - 30	0.623	2	0.0945	0.0624
T12	30 - 20	0.383	3	0.0692	0.0464
T13	20 - 0	0.204	3	0.0430	0.0322

Critical Deflections and Radius of Curvature - Design Wind

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
187.00	ANT940Y10-WR	2	9.082	0.3836	0.2700	127393
181.00	ANT940Y10-WR	2	9.082	0.3836	0.2700	127393
177.00	PA6-65AC	2	8.841	0.3839	0.2684	127393
170.00	RFI BPS7496-180-14 Panel Antenna	2	8.275	0.3839	0.2631	63697
169.00	3' Yagi	2	8.194	0.3837	0.2620	57906
160.00	ROHN 6'x15' Boom Gate (1)	2	7.452	0.3787	0.2451	38442
144.00	FFVV-65B-R2	2	6.117	0.3545	0.2126	18961
133.00	QD6616-7	2	5.263	0.3368	0.1989	65720
125.00	LTF12=372 Sector Mount (1)	2	4.654	0.3211	0.1891	12908
113.00	ANT150D	2	3.843	0.2874	0.1786	16767
60.00	GPS	2	1.240	0.1422	0.0930	21884

Bolt Design Data

Section No.	Elevation ft	Component Type	Bolt Grade	Bolt Size in	Number Of Bolts	Maximum Load per Bolt lb	Allowable Load per Bolt lb	Ratio Load Allowable	Allowable Ratio	Criteria	
T1	180	Diagonal	A325N	0.6250	3	1376.32	13805.80	0.100	✓	1	Bolt Shear
		Horizontal	A325N	0.6250	2	1116.80	13805.80	0.081	✓	1	Bolt Shear
		Top Girt	A325N	0.6250	2	176.49	13805.80	0.013	✓	1	Bolt Shear
T2	160	Leg	A325N	0.8750	4	1501.13	41556.00	0.036	✓	1	Bolt Tension
		Diagonal	A325N	0.6250	3	3113.27	13805.80	0.226	✓	1	Bolt Shear
		Horizontal	A325N	0.6250	2	2905.72	13805.80	0.210	✓	1	Bolt Shear
T3	140	Leg	A325N	1.0000	4	7666.77	54517.00	0.141	✓	1	Bolt Tension
		Diagonal	A325N	0.6250	3	3382.45	13805.80	0.245	✓	1	Bolt Shear
		Horizontal	A325N	0.6250	2	3272.11	13805.80	0.237	✓	1	Bolt Shear

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job	22027.01 - Westport	Page	59 of 73
	Project	180-ft Lattice Tower (CSP #32)	Date	15:45:34 06/11/24
	Client	Verizon	Designed by	TJL

Section No.	Elevation ft	Component Type	Bolt Grade	Bolt Size in	Number Of Bolts	Maximum Load per Bolt lb	Allowable Load per Bolt lb	Ratio Load Allowable	Allowable Ratio	Criteria	
T4	133.333	Diagonal	A325N	0.6250	3	4213.71	13805.80	0.305	✓	1	Bolt Shear
		Top Girt	A325N	0.6250	2	4235.51	13805.80	0.307	✓	1	Bolt Shear
T5	126.667	Diagonal	A325N	0.6250	3	4752.99	13805.80	0.344	✓	1	Bolt Shear
		Top Girt	A325N	0.6250	2	4886.47	13805.80	0.354	✓	1	Bolt Shear
T6	120	Leg	A325N	1.0000	6	11292.90	54517.00	0.207	✓	1	Bolt Tension
		Diagonal	A325N	0.6250	3	6083.90	13805.80	0.441	✓	1	Bolt Shear
		Horizontal	A325N	0.6250	2	5483.05	13805.80	0.397	✓	1	Bolt Shear
T7	100	Leg	A325N	1.0000	6	18750.60	54517.00	0.344	✓	1	Bolt Tension
		Diagonal	A325N	0.6250	3	5818.80	13805.80	0.421	✓	1	Bolt Shear
		Horizontal	A325N	0.6250	2	5611.11	13805.80	0.406	✓	1	Bolt Shear
T8	90	Diagonal	A325N	0.6250	3	6019.57	13805.80	0.436	✓	1	Bolt Shear
		Top Girt	A325N	0.6250	2	6021.50	13805.80	0.436	✓	1	Bolt Shear
T9	80	Leg	A325N	1.0000	8	19034.60	54517.00	0.349	✓	1	Bolt Tension
		Diagonal	A325N	0.6250	3	6702.69	13805.80	0.485	✓	1	Bolt Shear
		Horizontal	A325N	0.6250	2	7157.66	13805.80	0.518	✓	1	Bolt Shear
T10	60	Leg	A325N	1.0000	8	23997.70	54517.00	0.440	✓	1	Bolt Tension
		Diagonal	A325N	0.6250	3	7348.04	13805.80	0.532	✓	1	Bolt Shear
		Horizontal	A325N	0.6250	2	8221.14	13805.80	0.595	✓	1	Bolt Shear
T11	40	Leg	A325N	1.0000	8	29014.50	54517.00	0.532	✓	1	Bolt Tension
		Diagonal	A325N	0.6250	3	7594.98	13805.80	0.550	✓	1	Bolt Shear
		Horizontal	A325N	0.6250	2	8679.30	13805.80	0.629	✓	1	Bolt Shear
T12	30	Diagonal	A325N	0.6250	3	7830.32	13805.80	0.567	✓	1	Bolt Shear
		Top Girt	A325N	0.6250	2	9089.89	13805.80	0.658	✓	1	Bolt Shear
T13	20	Leg	A325N	1.0000	8	33746.10	54517.00	0.619	✓	1	Bolt Tension
		Diagonal	A325X	0.6250	3	11679.80	17257.30	0.677	✓	1	Bolt Shear
		Horizontal	A325N	0.7500	2	9783.40	19880.40	0.492	✓	1	Bolt Shear

Compression Checks

Leg Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio $\frac{P_u}{\phi P_n}$
T1	180 - 160	ROHN 3 STD	20.00	6.67	68.8 K=1.00	2.2285	-4183.04	70976.40	0.059 ¹ ✓
T2	160 - 140	ROHN 4 STD	20.04	6.68	53.1 K=1.00	3.1741	-29175.00	116229.00	0.251 ¹ ✓

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 60 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by TJL

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio P _u / φP _n
T3	140 - 133.333	ROHN 5 EH	6.68	6.68	43.6 K=1.00	6.1120	-39112.00	239378.00	0.163 ¹
T4	133.333 - 126.667	ROHN 5 EH	6.68	6.68	43.6 K=1.00	6.1120	-51882.10	239378.00	0.217 ¹
T5	126.667 - 120	ROHN 5 EH	6.68	6.68	43.6 K=1.00	6.1120	-67259.40	239378.00	0.281 ¹
T6	120 - 100	ROHN 6 EHS	20.04	10.02	54.0 K=1.00	6.7133	-108254.00	244017.00	0.444 ¹
T7	100 - 90	ROHN 6 EH	10.03	10.03	54.8 K=1.00	8.4049	-132360.00	303585.00	0.436 ¹
T8	90 - 80	ROHN 6 EH	10.03	10.03	54.8 K=1.00	8.4049	-154046.00	303585.00	0.507 ¹
T9	80 - 60	120deg_9.6250x0.375 BU on ROHN 8 EHS	20.05	10.03	42.2 K=1.00	13.6005	-197499.00	537270.00	0.368 ¹
T10	60 - 40	1/3 9.6250x0.375 on ROHN 8 EHS Leg Pipe	20.05	10.03	42.2 K=1.00	13.6005	-242595.00	460811.00	0.526 ¹
T11	40 - 30	1/3 9.6250x0.375 on ROHN 8 EHS Leg Pipe	10.03	10.03	42.2 K=1.00	13.6005	-265467.00	460811.00	0.576 ¹
T12	30 - 20	1/3 9.6250x0.375 on ROHN 8 EHS Leg Pipe	10.03	10.03	42.2 K=1.00	13.6005	-288286.00	460811.00	0.626 ¹
T13	20 - 0	1/3 9.6250x0.375 on ROHN 8 EH Leg Pipe	20.05	10.03	42.9 K=1.00	16.6002	-310698.00	560408.00	0.554 ¹

¹ P_u / φP_n controls

Diagonal Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio P _u / φP _n
T1	180 - 160	ROHN 2 STD	7.94	7.67	117.0 K=1.00	1.0745	-4128.96	17747.50	0.233 ¹
T2	160 - 140	ROHN 2 STD	8.55	8.25	125.8 K=1.00	1.0745	-9339.82	15331.30	0.609 ¹
T3	140 - 133.333	ROHN 2 EH	8.77	8.42	131.5 K=1.00	1.4807	-10147.30	19347.50	0.524 ¹
T4	133.333 - 126.667	ROHN 2 EH	9.00	8.66	135.3 K=1.00	1.4807	-12641.10	18285.10	0.691 ¹
T5	126.667 - 120	ROHN 2 XXS	9.24	8.91	152.1 K=1.00	2.6559	-14259.00	25935.80	0.550 ¹
T6	120 - 100	Pipe 2.5 XXS	12.52	12.06	171.4 K=1.00	4.0285	-18251.70	30977.00	0.589 ¹
T7	100 - 90	ROHN 3 STD	12.92	12.49	128.8 K=1.00	2.2285	-17456.40	30346.40	0.575 ¹
T8	90 - 80	ROHN 3 STD	13.35	12.93	133.4 K=1.00	2.2285	-18058.70	28290.90	0.638 ¹
T9	80 - 60	ROHN 3 STD	14.21	13.70	141.2 K=1.00	2.2285	-20108.10	25233.20	0.797 ¹
T10	60 - 40	ROHN 3 EH	15.12	14.64	154.6 K=1.00	3.0159	-22044.10	28518.80	0.773 ¹

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 61 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by TJL

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio $\frac{P_u}{\phi P_n}$
T11	40 - 30	ROHN 3 EH	15.60	15.12	159.7 K=1.00	3.0159	-22785.00	26718.70	0.853 ¹ ✓
T12	30 - 20	ROHN 3 EH	16.08	15.62	164.9 K=1.00	3.0159	-23491.00	25055.10	0.938 ¹ ✓
T13	20 - 0	ROHN 3 EH	24.33	23.70	125.1 K=0.50	3.0159	-35039.50	43506.30	0.805 ¹ ✓

¹ P_u / φP_n controls

Horizontal Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio $\frac{P_u}{\phi P_n}$
T1	180 - 160	ROHN 1.5 STD	8.60	4.15	80.0 K=1.00	0.7995	-2199.42	22519.90	0.098 ¹ ✓
T2	160 - 140	ROHN 1.5 STD	10.01	4.82	92.9 K=1.00	0.7995	-5810.94	19142.00	0.304 ¹ ✓
T3	140 - 133.333	ROHN 2 STD	10.71	5.12	78.1 K=1.00	1.0745	-6536.27	30956.80	0.211 ¹ ✓
T6	120 - 100	ROHN 2 STD	13.92	6.68	101.9 K=1.00	1.0745	-10834.40	22639.20	0.479 ¹ ✓
T7	100 - 90	ROHN 2 STD	15.04	7.24	110.5 K=1.00	1.0745	-11222.20	19817.20	0.566 ¹ ✓
T9	80 - 60	ROHN 2.5 STD	18.93	9.10	115.2 K=1.00	1.7040	-14293.10	28984.30	0.493 ¹ ✓
T10	60 - 40	ROHN 2.5 STD	21.43	10.35	131.1 K=1.00	1.7040	-16397.60	22405.40	0.732 ¹ ✓
T11	40 - 30	ROHN 2.5 STD	22.68	10.97	139.0 K=1.00	1.7040	-17342.40	19925.90	0.870 ¹ ✓
T13	20 - 0	P3.5x.226	25.18	12.23	109.8 K=1.00	2.6795	-19566.80	49951.20	0.392 ¹ ✓

¹ P_u / φP_n controls

Top Girt Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio $\frac{P_u}{\phi P_n}$
T1	180 - 160	ROHN 1.5 STD	8.54	4.13	79.5 K=1.00	0.7995	-352.97	22660.50	0.016 ¹ ✓
T4	133.333 - 126.667	ROHN 2 STD	11.40	5.47	83.4 K=1.00	1.0745	-8463.67	29081.40	0.291 ¹ ✓
T5	126.667 - 120	ROHN 2 STD	12.10	5.82	88.7 K=1.00	1.0745	-9772.57	27207.90	0.359 ¹ ✓

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job	22027.01 - Westport	Page	62 of 73
	Project	180-ft Lattice Tower (CSP #32)	Date	15:45:34 06/11/24
	Client	Verizon	Designed by	TJL

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio $\frac{P_u}{\phi P_n}$
T8	90 - 80	ROHN 2 STD	16.36	7.90	120.5 K=1.00	1.0745	-12002.70	16719.60	0.718 ¹
T12	30 - 20	ROHN 2.5 EH	23.93	11.60	150.6 K=1.00	2.2535	-18017.40	22438.80	0.803 ¹

¹ P_u / φP_n controls

Redundant Horizontal (1) Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio $\frac{P_u}{\phi P_n}$
T13	20 - 0	ROHN 1.5 STD	6.29	5.93	114.4 K=1.00	0.7995	-5391.94	13802.80	0.391 ¹

¹ P_u / φP_n controls

Redundant Diagonal (1) Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio $\frac{P_u}{\phi P_n}$
T13	20 - 0	ROHN 2 STD	11.50	10.77	164.2 K=1.00	1.0745	-4926.09	8998.85	0.547 ¹

¹ P_u / φP_n controls

Redundant Hip (1) Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio $\frac{P_u}{\phi P_n}$
T13	20 - 0	ROHN 2.5 STD	6.29	6.29	79.7 K=1.00	1.7040	-17.58	48180.50	0.000 ¹

¹ P_u / φP_n controls

Inner Bracing Design Data (Compression)

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 63 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by TJL

Section No.	Elevation ft	Size	L ft	L _w ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio $\frac{P_u}{\phi P_n}$
T1	180 - 160	L2x2x1/8	4.30	4.30	129.8 K=1.00	0.4844	-1.84	8234.10	0.000 ¹
T2	160 - 140	L2x2x1/8	5.01	5.01	151.1 K=1.00	0.4844	-4.87	6068.75	0.001 ¹
T3	140 - 133.333	L2x2x1/8	5.35	5.35	161.6 K=1.00	0.4844	-7.43	5306.96	0.001 ¹
T4	133.333 - 126.667	L2x2x1/8	5.70	5.70	172.1 K=1.00	0.4844	-9.77	4680.37	0.002 ¹
T5	126.667 - 120	L2x2x1/8	6.05	6.05	182.6 K=1.00	0.4844	-10.60	4158.54	0.003 ¹
T6	120 - 100	L2 1/2x2 1/2x3/16	6.96	6.96	168.7 K=1.00	0.9020	-11.49	9072.37	0.001 ¹
T7	100 - 90	L2 1/2x2 1/2x3/16	7.52	7.52	182.3 K=1.00	0.9020	-10.24	7766.06	0.001 ¹
T8	90 - 80	L2 1/2x2 1/2x3/16	8.18	8.18	198.3 K=1.00	0.9020	-10.47	6565.57	0.002 ¹
T9	80 - 60	L3x3x3/16	9.46	9.46	190.5 K=1.00	1.0900	-12.32	8593.12	0.001 ¹
T10	60 - 40	L3 1/2x3 1/2x1/4	10.71	10.71	185.2 K=1.00	1.6900	-14.71	14095.40	0.001 ¹
T11	40 - 30	L3 1/2x3 1/2x1/4	11.34	11.34	196.1 K=1.00	1.6900	-14.96	12584.30	0.001 ¹
T12	30 - 20	L3 1/2x3 1/2x1/4	11.96	11.96	206.9 K=1.00	1.6900	-15.80	11303.80	0.001 ¹
T13	20 - 0	ROHN 2 STD	12.59	12.59	191.9 K=1.00	1.0745	-14.23	6590.81	0.002 ¹

¹ P_u / φP_n controls

Tension Checks

Leg Design Data (Tension)

Section No.	Elevation ft	Size	L ft	L _w ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio $\frac{P_u}{\phi P_n}$
T1	180 - 160	ROHN 3 STD	20.00	6.67	68.8	1.6713	2515.64	81478.40	0.031 ¹
T2	160 - 140	ROHN 4 STD	20.04	6.68	53.1	2.3805	21755.90	116051.00	0.187 ¹
T3	140 - 133.333	ROHN 5 EH	6.68	6.68	43.6	4.5840	30667.10	223469.00	0.137 ¹
T4	133.333 - 126.667	ROHN 5 EH	6.68	6.68	43.6	4.5840	40590.90	223469.00	0.182 ¹
T5	126.667 - 120	ROHN 5 EH	6.68	6.68	43.6	4.5840	52845.20	223469.00	0.236 ¹
T6	120 - 100	ROHN 6 EHS	20.04	10.02	54.0	5.0349	90268.60	245454.00	0.368 ¹

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 64 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by TJL

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio $\frac{P_u}{\phi P_n}$
T7	100 - 90	ROHN 6 EH	10.03	10.03	54.8	6.3037	112504.00	307306.00	0.366 ¹
T8	90 - 80	ROHN 6 EH	10.03	10.03	54.8	6.3037	132620.00	307306.00	0.432 ¹
T9	80 - 60	120deg_9.6250x0.375 BU on ROHN 8 EHS	20.05	10.03	42.2	13.6005	172100.00	612023.00	0.281 ¹
T10	60 - 40	1/3 9.6250x0.375 on ROHN 8 EHS Leg Pipe	20.05	10.03	42.2	13.6005	212124.00	514099.00	0.413 ¹
T11	40 - 30	1/3 9.6250x0.375 on ROHN 8 EHS Leg Pipe	10.03	10.03	42.2	13.6005	232116.00	514099.00	0.452 ¹
T12	30 - 20	1/3 9.6250x0.375 on ROHN 8 EHS Leg Pipe	10.03	10.03	42.2	13.6005	251902.00	514099.00	0.490 ¹
T13	20 - 0	1/3 9.6250x0.375 on ROHN 8 EH Leg Pipe	20.05	10.03	42.9	16.6002	269969.00	627488.00	0.430 ¹

¹ P_u / φP_n controls

Diagonal Design Data (Tension)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio $\frac{P_u}{\phi P_n}$
T1	180 - 160	ROHN 2 STD	7.94	7.67	117.0	0.6326	4061.67	30841.60	0.132 ¹
T2	160 - 140	ROHN 2 STD	8.55	8.25	125.8	0.6326	9263.08	30841.60	0.300 ¹
T3	140 - 133.333	ROHN 2 EH	8.77	8.42	131.5	0.8653	10037.80	42181.50	0.238 ¹
T4	133.333 - 126.667	ROHN 2 EH	9.00	8.66	135.3	0.8653	12523.40	42181.50	0.297 ¹
T5	126.667 - 120	ROHN 2 XXS	9.24	8.91	152.1	1.5014	14075.60	73195.00	0.192 ¹
T6	120 - 100	Pipe 2.5 XXS	12.52	12.06	171.4	2.4003	17940.70	117017.00	0.153 ¹
T7	100 - 90	ROHN 3 STD	12.92	12.49	128.8	1.4283	17223.80	69632.20	0.247 ¹
T8	90 - 80	ROHN 3 STD	13.35	12.93	133.4	1.4283	17808.30	69632.20	0.256 ¹
T9	80 - 60	ROHN 3 STD	14.21	13.70	141.2	1.4283	19772.10	69632.20	0.284 ¹
T10	60 - 40	ROHN 3 EH	15.12	14.64	154.6	1.9245	21552.50	93816.80	0.230 ¹
T11	40 - 30	ROHN 3 EH	15.60	15.12	159.7	1.9245	22257.60	93816.80	0.237 ¹
T12	30 - 20	ROHN 3 EH	16.08	15.62	164.9	1.9245	22878.30	93816.80	0.244 ¹
T13	20 - 0	ROHN 3 EH	24.33	23.70	250.3	1.9245	33802.80	93816.80	0.360 ¹

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 65 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by TJL

¹ $P_u / \phi P_n$ controls

Horizontal Design Data (Tension)

Section No.	Elevation <i>ft</i>	Size	<i>L</i> <i>ft</i>	<i>L_u</i> <i>ft</i>	<i>Kl/r</i>	<i>A</i> <i>in²</i>	<i>P_u</i> <i>lb</i>	ϕP_n <i>lb</i>	Ratio $\frac{P_u}{\phi P_n}$
T1	180 - 160	ROHN 1.5 STD	8.60	4.15	80.0	0.4365	2233.61	21277.80	0.105 ¹
T2	160 - 140	ROHN 1.5 STD	10.01	4.82	92.9	0.4365	5811.45	21277.80	0.273 ¹
T3	140 - 133.333	ROHN 2 STD	10.71	5.12	78.1	0.6326	6544.21	30841.60	0.212 ¹
T6	120 - 100	ROHN 2 STD	13.92	6.68	101.9	0.6326	10966.10	30841.60	0.356 ¹
T7	100 - 90	ROHN 2 STD	15.04	7.24	110.5	0.6326	11196.10	30841.60	0.363 ¹
T9	80 - 60	ROHN 2.5 STD	18.93	9.10	115.2	1.0497	14315.30	51171.10	0.280 ¹
T10	60 - 40	ROHN 2.5 STD	21.43	10.35	131.1	1.0497	16442.30	51171.10	0.321 ¹
T11	40 - 30	ROHN 2.5 STD	22.68	10.97	139.0	1.0497	17358.60	51171.10	0.339 ¹
T13	20 - 0	P3.5x.226	25.18	12.23	109.8	1.7130	19348.70	83510.20	0.232 ¹

¹ $P_u / \phi P_n$ controls

Top Girt Design Data (Tension)

Section No.	Elevation <i>ft</i>	Size	<i>L</i> <i>ft</i>	<i>L_u</i> <i>ft</i>	<i>Kl/r</i>	<i>A</i> <i>in²</i>	<i>P_u</i> <i>lb</i>	ϕP_n <i>lb</i>	Ratio $\frac{P_u}{\phi P_n}$
T1	180 - 160	ROHN 1.5 STD	8.54	4.13	79.5	0.4365	324.64	21277.80	0.015 ¹
T4	133.333 - 126.667	ROHN 2 STD	11.40	5.47	83.4	0.6326	8471.02	30841.60	0.275 ¹
T5	126.667 - 120	ROHN 2 STD	12.10	5.82	88.7	0.6326	9772.94	30841.60	0.317 ¹
T8	90 - 80	ROHN 2 STD	16.36	7.90	120.5	0.6326	12043.00	30841.60	0.390 ¹
T12	30 - 20	ROHN 2.5 EH	23.93	11.60	150.6	1.3797	18179.80	67258.20	0.270 ¹

¹ $P_u / \phi P_n$ controls

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 66 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by TJL

Redundant Horizontal (1) Design Data (Tension)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio $\frac{P_u}{\phi P_n}$
T13	20 - 0	ROHN 1.5 STD	6.29	5.93	114.4	0.5996	5391.94	29230.10	0.184 ¹ ✓

¹ P_u / φP_n controls

Redundant Diagonal (1) Design Data (Tension)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio $\frac{P_u}{\phi P_n}$
T13	20 - 0	ROHN 2 STD	11.50	10.77	164.2	0.8059	4926.09	39287.60	0.125 ¹ ✓

¹ P_u / φP_n controls

Redundant Hip (1) Design Data (Tension)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio $\frac{P_u}{\phi P_n}$
T13	20 - 0	ROHN 2.5 STD	6.29	6.29	79.7	1.2780	1.82	62304.30	0.000 ¹ ✓

¹ P_u / φP_n controls

Inner Bracing Design Data (Tension)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio $\frac{P_u}{\phi P_n}$
T1	180 - 160	L2x2x1/8	4.30	4.30	82.4	0.4844	1.84	15693.80	0.000 ¹ ✓
T2	160 - 140	L2x2x1/8	4.31	4.31	82.6	0.4844	4.62	15693.80	0.000 ¹ ✓
T3	140 - 133.333	L2x2x1/8	5.35	5.35	102.6	0.4844	4.60	15693.80	0.000 ¹ ✓
T4	133.333 - 126.667	L2x2x1/8	5.70	5.70	109.3	0.4844	6.79	15693.80	0.000 ¹ ✓
T5	126.667 - 120	L2x2x1/8	6.05	6.05	115.9	0.4844	6.17	15693.80	0.000 ¹ ✓
T6	120 - 100	L2 1/2x2 1/2x3/16	6.40	6.40	98.7	0.9020	3.56	29224.80	0.000 ¹ ✓

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 67 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by TJL

Section No.	Elevation ft	Size	L ft	L _w ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio $\frac{P_u}{\phi P_n}$
T7	100 - 90	L2 1/2x2 1/2x3/16	7.52	7.52	116.0	0.9020	2.54	29224.80	0.000 ¹ ✓
T8	90 - 80	L2 1/2x2 1/2x3/16	8.18	8.18	126.2	0.9020	1.59	29224.80	0.000 ¹ ✓
T9	80 - 60	L3x3x3/16	8.84	8.84	113.0	1.0900	2.64	35316.00	0.000 ¹ ✓
T10	60 - 40	L3 1/2x3 1/2x1/4	10.09	10.09	111.1	1.6900	0.65	76050.00	0.000 ¹ ✓

¹ P_u / φP_n controls

Section Capacity Table

Section No.	Elevation ft	Component Type	Size	Critical Element	P lb	φP _{allow} lb	% Capacity	Pass Fail
T1	180 - 160	Leg	ROHN 3 STD	1	-2857.24	70976.40	4.0	Pass
		Leg	ROHN 3 STD	2	-2545.09	70976.40	3.6	Pass
		Leg	ROHN 3 STD	3	-4183.04	70976.40	5.9	Pass
T2	160 - 140	Leg	ROHN 4 STD	40	-25044.60	116229.00	21.5	Pass
		Leg	ROHN 4 STD	41	-24924.10	116229.00	21.4	Pass
		Leg	ROHN 4 STD	42	-29175.00	116229.00	25.1	Pass
T3	140 - 133.333	Leg	ROHN 5 EH	79	-34209.30	239378.00	14.3	Pass
		Leg	ROHN 5 EH	80	-34303.30	239378.00	14.3	Pass
		Leg	ROHN 5 EH	81	-39112.00	239378.00	16.3	Pass
T4	133.333 - 126.667	Leg	ROHN 5 EH	94	-46333.70	239378.00	19.4	Pass
		Leg	ROHN 5 EH	95	-46679.30	239378.00	19.5	Pass
		Leg	ROHN 5 EH	96	-51882.10	239378.00	21.7	Pass
T5	126.667 - 120	Leg	ROHN 5 EH	109	-61038.10	239378.00	25.5	Pass
		Leg	ROHN 5 EH	110	-61609.30	239378.00	25.7	Pass
		Leg	ROHN 5 EH	111	-67259.40	239378.00	28.1	Pass
T6	120 - 100	Leg	ROHN 6 EHS	124	-100520.00	244017.00	41.2	Pass
		Leg	ROHN 6 EHS	125	-101622.00	244017.00	41.6	Pass
		Leg	ROHN 6 EHS	126	-108254.00	244017.00	44.4	Pass
T7	100 - 90	Leg	ROHN 6 EH	151	-123919.00	303585.00	40.8	Pass
		Leg	ROHN 6 EH	152	-125267.00	303585.00	41.3	Pass
		Leg	ROHN 6 EH	153	-132360.00	303585.00	43.6	Pass
T8	90 - 80	Leg	ROHN 6 EH	166	-145096.00	303585.00	47.8	Pass
		Leg	ROHN 6 EH	167	-146647.00	303585.00	48.3	Pass
		Leg	ROHN 6 EH	168	-154046.00	303585.00	50.7	Pass
T9	80 - 60	Leg	120deg_9.6250x0.375 BU on ROHN 8 EHS	181	-187676.00	537270.00	34.9	Pass
		Leg	120deg_9.6250x0.375 BU on ROHN 8 EHS	182	-189579.00	537270.00	35.3	Pass
		Leg	120deg_9.6250x0.375 BU on ROHN 8 EHS	183	-197499.00	537270.00	36.8	Pass
T10	60 - 40	Leg	1/3 9.6250x0.375 on ROHN 8 EHS Leg Pipe	208	-232161.00	460811.00	50.4	Pass
		Leg	1/3 9.6250x0.375 on ROHN 8 EHS Leg Pipe	209	-234227.00	460811.00	50.8	Pass
		Leg	1/3 9.6250x0.375 on ROHN 8 EHS Leg Pipe	210	-242595.00	460811.00	52.6	Pass
T11	40 - 30	Leg	1/3 9.6250x0.375 on ROHN 8	235	-254697.00	460811.00	55.3	Pass

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 68 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by TJL

Section No.	Elevation ft	Component Type	Size	Critical Element	P lb	ϕP_{allow} lb	% Capacity	Pass Fail
			EHS Leg Pipe					
		Leg	1/3 9.6250x0.375 on ROHN 8	236	-256907.00	460811.00	55.8	Pass
			EHS Leg Pipe					
		Leg	1/3 9.6250x0.375 on ROHN 8	237	-265467.00	460811.00	57.6	Pass
			EHS Leg Pipe					
T12	30 - 20	Leg	1/3 9.6250x0.375 on ROHN 8	250	-277211.00	460811.00	60.2	Pass
			EHS Leg Pipe					
		Leg	1/3 9.6250x0.375 on ROHN 8	251	-279554.00	460811.00	60.7	Pass
			EHS Leg Pipe					
		Leg	1/3 9.6250x0.375 on ROHN 8	252	-288286.00	460811.00	62.6	Pass
			EHS Leg Pipe					
T13	20 - 0	Leg	1/3 9.6250x0.375 on ROHN 8	265	-299204.00	560408.00	53.4	Pass
			EH Leg Pipe				61.0 (b)	
		Leg	1/3 9.6250x0.375 on ROHN 8	266	-301792.00	560408.00	53.9	Pass
			EH Leg Pipe				61.1 (b)	
		Leg	1/3 9.6250x0.375 on ROHN 8	267	-310698.00	560408.00	55.4	Pass
			EH Leg Pipe				61.9 (b)	
T1	180 - 160	Diagonal	ROHN 2 STD	8	-2239.24	17747.50	12.6	Pass
		Diagonal	ROHN 2 STD	9	-1974.04	17747.50	11.1	Pass
		Diagonal	ROHN 2 STD	11	-2194.53	17747.50	12.4	Pass
		Diagonal	ROHN 2 STD	12	-2307.96	17747.50	13.0	Pass
		Diagonal	ROHN 2 STD	14	-4128.96	17747.50	23.3	Pass
		Diagonal	ROHN 2 STD	15	-3694.09	17747.50	20.8	Pass
		Diagonal	ROHN 2 STD	20	-1751.63	17782.20	9.9	Pass
		Diagonal	ROHN 2 STD	21	-1440.75	17782.20	8.1	Pass
		Diagonal	ROHN 2 STD	23	-995.30	17782.20	5.6	Pass
		Diagonal	ROHN 2 STD	24	-1130.12	17782.20	6.4	Pass
		Diagonal	ROHN 2 STD	26	-2799.69	17782.20	15.7	Pass
		Diagonal	ROHN 2 STD	27	-2295.38	17782.20	12.9	Pass
		Diagonal	ROHN 2 STD	31	-513.18	17817.00	2.9	Pass
		Diagonal	ROHN 2 STD	32	-387.54	17817.00	2.2	Pass
		Diagonal	ROHN 2 STD	33	-147.80	17817.00	0.8	Pass
		Diagonal	ROHN 2 STD	34	-143.01	17817.00	0.8	Pass
		Diagonal	ROHN 2 STD	35	-610.84	17817.00	3.4	Pass
		Diagonal	ROHN 2 STD	36	-503.56	17817.00	2.8	Pass
T2	160 - 140	Diagonal	ROHN 2 STD	44	-5804.58	15331.30	37.9	Pass
		Diagonal	ROHN 2 STD	45	-5698.12	15331.30	37.2	Pass
		Diagonal	ROHN 2 STD	47	-7242.62	15331.30	47.2	Pass
		Diagonal	ROHN 2 STD	48	-7227.16	15331.30	47.1	Pass
		Diagonal	ROHN 2 STD	50	-9339.82	15331.30	60.9	Pass
		Diagonal	ROHN 2 STD	51	-9063.79	15331.30	59.1	Pass
		Diagonal	ROHN 2 STD	56	-4744.41	16154.50	29.4	Pass
		Diagonal	ROHN 2 STD	57	-4618.93	16154.50	28.6	Pass
		Diagonal	ROHN 2 STD	59	-6249.70	16154.50	38.7	Pass
		Diagonal	ROHN 2 STD	60	-6238.97	16154.50	38.6	Pass
		Diagonal	ROHN 2 STD	62	-8431.80	16154.50	52.2	Pass
		Diagonal	ROHN 2 STD	63	-8124.77	16154.50	50.3	Pass
		Diagonal	ROHN 2 STD	68	-4997.30	17005.60	29.4	Pass
		Diagonal	ROHN 2 STD	69	-4850.52	17005.60	28.5	Pass
		Diagonal	ROHN 2 STD	71	-6483.43	17005.60	38.1	Pass
		Diagonal	ROHN 2 STD	72	-6468.25	17005.60	38.0	Pass
		Diagonal	ROHN 2 STD	74	-8808.71	17005.60	51.8	Pass
		Diagonal	ROHN 2 STD	75	-8454.92	17005.60	49.7	Pass
T3	140 - 133.333	Diagonal	ROHN 2 EH	83	-6644.98	19347.50	34.3	Pass
		Diagonal	ROHN 2 EH	84	-6551.42	19347.50	33.9	Pass
		Diagonal	ROHN 2 EH	86	-8093.81	19347.50	41.8	Pass
		Diagonal	ROHN 2 EH	87	-8073.65	19347.50	41.7	Pass
		Diagonal	ROHN 2 EH	89	-10147.30	19347.50	52.4	Pass
		Diagonal	ROHN 2 EH	90	-9896.12	19347.50	51.1	Pass
T4	133.333 - 126.667	Diagonal	ROHN 2 EH	100	-9539.68	18285.10	52.2	Pass

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 69 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by TJL

Section No.	Elevation ft	Component Type	Size	Critical Element	P lb	ϕP_{allow} lb	% Capacity	Pass Fail
T5	126.667 - 120	Diagonal	ROHN 2 EH	101	-9453.07	18285.10	51.7	Pass
		Diagonal	ROHN 2 EH	102	-10970.10	18285.10	60.0	Pass
		Diagonal	ROHN 2 EH	103	-10958.80	18285.10	59.9	Pass
		Diagonal	ROHN 2 EH	104	-12641.10	18285.10	69.1	Pass
		Diagonal	ROHN 2 EH	105	-12415.20	18285.10	67.9	Pass
		Diagonal	ROHN 2 XXS	115	-11320.40	25935.80	43.6	Pass
		Diagonal	ROHN 2 XXS	116	-11235.90	25935.80	43.3	Pass
		Diagonal	ROHN 2 XXS	117	-12992.10	25935.80	50.1	Pass
		Diagonal	ROHN 2 XXS	118	-12980.10	25935.80	50.0	Pass
		Diagonal	ROHN 2 XXS	119	-14259.00	25935.80	55.0	Pass
T6	120 - 100	Diagonal	ROHN 2 XXS	120	-14052.50	25935.80	54.2	Pass
		Diagonal	Pipe 2.5 XXS	128	-13840.00	30977.00	44.7	Pass
		Diagonal	Pipe 2.5 XXS	129	-13741.70	30977.00	44.4	Pass
		Diagonal	Pipe 2.5 XXS	131	-18108.10	30977.00	58.5	Pass
		Diagonal	Pipe 2.5 XXS	132	-18080.00	30977.00	58.4	Pass
		Diagonal	Pipe 2.5 XXS	134	-18251.70	30977.00	58.9	Pass
		Diagonal	Pipe 2.5 XXS	135	-18073.60	30977.00	58.3	Pass
		Diagonal	Pipe 2.5 XXS	140	-14148.70	32743.10	43.2	Pass
		Diagonal	Pipe 2.5 XXS	141	-14046.30	32743.10	42.9	Pass
		Diagonal	Pipe 2.5 XXS	143	-17280.50	32743.10	52.8	Pass
T7	100 - 90	Diagonal	Pipe 2.5 XXS	144	-17253.40	32743.10	52.7	Pass
		Diagonal	Pipe 2.5 XXS	146	-18173.10	32743.10	55.5	Pass
		Diagonal	Pipe 2.5 XXS	147	-17956.10	32743.10	54.8	Pass
		Diagonal	ROHN 3 STD	155	-12450.70	30346.40	41.0	Pass
		Diagonal	ROHN 3 STD	156	-12355.10	30346.40	40.7	Pass
		Diagonal	ROHN 3 STD	158	-17456.40	30346.40	57.5	Pass
		Diagonal	ROHN 3 STD	159	-17398.00	30346.40	57.3	Pass
		Diagonal	ROHN 3 STD	161	-17007.20	30346.40	56.0	Pass
		Diagonal	ROHN 3 STD	162	-16881.50	30346.40	55.6	Pass
		Diagonal	ROHN 3 STD	172	-12397.00	28290.90	43.8	Pass
T8	90 - 80	Diagonal	ROHN 3 STD	173	-12304.40	28290.90	43.5	Pass
		Diagonal	ROHN 3 STD	174	-18058.70	28290.90	63.8	Pass
		Diagonal	ROHN 3 STD	175	-18005.60	28290.90	63.6	Pass
		Diagonal	ROHN 3 STD	176	-17238.80	28290.90	60.9	Pass
		Diagonal	ROHN 3 STD	177	-17139.20	28290.90	60.6	Pass
		Diagonal	ROHN 3 STD	185	-13394.50	25233.20	53.1	Pass
		Diagonal	ROHN 3 STD	186	-13307.90	25233.20	52.7	Pass
		Diagonal	ROHN 3 STD	188	-20108.10	25233.20	79.7	Pass
		Diagonal	ROHN 3 STD	189	-19988.40	25233.20	79.2	Pass
		Diagonal	ROHN 3 STD	191	-18641.30	25233.20	73.9	Pass
T9	80 - 60	Diagonal	ROHN 3 STD	192	-18574.40	25233.20	73.6	Pass
		Diagonal	ROHN 3 STD	197	-12907.10	26922.60	47.9	Pass
		Diagonal	ROHN 3 STD	198	-12816.80	26922.60	47.6	Pass
		Diagonal	ROHN 3 STD	200	-19206.30	26922.60	71.3	Pass
		Diagonal	ROHN 3 STD	201	-19140.60	26922.60	71.1	Pass
		Diagonal	ROHN 3 STD	203	-18043.10	26922.60	67.0	Pass
		Diagonal	ROHN 3 STD	204	-17959.20	26922.60	66.7	Pass
		Diagonal	ROHN 3 EH	212	-14459.10	28518.80	50.7	Pass
		Diagonal	ROHN 3 EH	213	-14380.20	28518.80	50.4	Pass
		Diagonal	ROHN 3 EH	215	-22044.10	28518.80	77.3	Pass
T10	60 - 40	Diagonal	ROHN 3 EH	216	-21836.20	28518.80	76.6	Pass
		Diagonal	ROHN 3 EH	218	-20114.30	28518.80	70.5	Pass
		Diagonal	ROHN 3 EH	219	-20071.20	28518.80	70.4	Pass
		Diagonal	ROHN 3 EH	224	-14094.00	30411.50	46.3	Pass
		Diagonal	ROHN 3 EH	225	-14014.20	30411.50	46.1	Pass
		Diagonal	ROHN 3 EH	227	-21335.20	30411.50	70.2	Pass
		Diagonal	ROHN 3 EH	228	-21160.90	30411.50	69.6	Pass
		Diagonal	ROHN 3 EH	230	-19637.40	30411.50	64.6	Pass
		Diagonal	ROHN 3 EH	231	-19578.80	30411.50	64.4	Pass
		Diagonal	ROHN 3 EH	239	-14790.80	26718.70	55.4	Pass
T11	40 - 30	Diagonal	ROHN 3 EH	240	-14710.50	26718.70	55.1	Pass

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 70 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by TJL

Section No.	Elevation ft	Component Type	Size	Critical Element	P lb	ϕP_{allow} lb	% Capacity	Pass Fail
T12	30 - 20	Diagonal	ROHN 3 EH	242	-22785.00	26718.70	85.3	Pass
		Diagonal	ROHN 3 EH	243	-22537.00	26718.70	84.3	Pass
		Diagonal	ROHN 3 EH	245	-20622.60	26718.70	77.2	Pass
		Diagonal	ROHN 3 EH	246	-20594.80	26718.70	77.1	Pass
		Diagonal	ROHN 3 EH	256	-15392.10	25055.10	61.4	Pass
		Diagonal	ROHN 3 EH	257	-15313.80	25055.10	61.1	Pass
		Diagonal	ROHN 3 EH	258	-23491.00	25055.10	93.8	Pass
		Diagonal	ROHN 3 EH	259	-23245.30	25055.10	92.8	Pass
		Diagonal	ROHN 3 EH	260	-21202.60	25055.10	84.6	Pass
T13	20 - 0	Diagonal	ROHN 3 EH	261	-21181.50	25055.10	84.5	Pass
		Diagonal	ROHN 3 EH	269	-22175.20	43506.30	51.0	Pass
		Diagonal	ROHN 3 EH	272	-22057.20	43506.30	50.7	Pass
		Diagonal	ROHN 3 EH	276	-35039.50	43506.30	80.5	Pass
		Diagonal	ROHN 3 EH	279	-34340.10	43506.30	78.9	Pass
		Diagonal	ROHN 3 EH	284	-30744.70	43506.30	70.7	Pass
		Diagonal	ROHN 3 EH	287	-31280.80	43506.30	71.9	Pass
T1	180 - 160	Horizontal	ROHN 1.5 STD	7	1433.26	21277.80	6.7	Pass
		Horizontal	ROHN 1.5 STD	10	1383.44	21277.80	6.5	Pass
		Horizontal	ROHN 1.5 STD	13	2233.61	21277.80	10.5	Pass
		Horizontal	ROHN 1.5 STD	19	1272.84	21277.80	6.0	Pass
		Horizontal	ROHN 1.5 STD	22	762.45	21277.80	3.6	Pass
		Horizontal	ROHN 1.5 STD	25	1505.69	21277.80	7.1	Pass
T2	160 - 140	Horizontal	ROHN 1.5 STD	43	-3597.22	19142.00	18.8	Pass
		Horizontal	ROHN 1.5 STD	46	-4621.62	19142.00	24.1	Pass
		Horizontal	ROHN 1.5 STD	49	-5810.94	19142.00	30.4	Pass
		Horizontal	ROHN 1.5 STD	55	-2803.40	20895.80	13.4	Pass
		Horizontal	ROHN 1.5 STD	58	-3749.47	20895.80	17.9	Pass
		Horizontal	ROHN 1.5 STD	61	-5017.79	20895.80	24.0	Pass
		Horizontal	ROHN 1.5 STD	67	3363.71	21277.80	15.8	Pass
		Horizontal	ROHN 1.5 STD	70	4001.11	21277.80	18.8	Pass
		Horizontal	ROHN 1.5 STD	73	5075.25	21277.80	23.9	Pass
		Horizontal	ROHN 1.5 STD	82	4269.22	30841.60	13.8	Pass
T3	140 - 133.333	Horizontal	ROHN 2 STD	85	5322.99	30841.60	17.3	Pass
		Horizontal	ROHN 2 STD	88	6544.21	30841.60	21.2	Pass
		Horizontal	ROHN 2 STD	88	6544.21	30841.60	21.2	Pass
T6	120 - 100	Horizontal	ROHN 2 STD	127	-8116.83	22639.20	35.9	Pass
		Horizontal	ROHN 2 STD	130	-10834.40	22639.20	47.9	Pass
		Horizontal	ROHN 2 STD	133	-10771.90	22639.20	47.6	Pass
		Horizontal	ROHN 2 STD	139	-7920.03	25586.40	31.0	Pass
		Horizontal	ROHN 2 STD	142	-9833.30	25586.40	38.4	Pass
		Horizontal	ROHN 2 STD	145	-10222.10	25586.40	40.0	Pass
T7	100 - 90	Horizontal	ROHN 2 STD	154	-7762.68	19817.20	39.2	Pass
		Horizontal	ROHN 2 STD	157	-11222.20	19817.20	56.6	Pass
		Horizontal	ROHN 2 STD	160	-10854.80	19817.20	54.8	Pass
T9	80 - 60	Horizontal	ROHN 2.5 STD	184	-9291.23	28984.30	32.1	Pass
		Horizontal	ROHN 2.5 STD	187	-14293.10	28984.30	49.3	Pass
		Horizontal	ROHN 2.5 STD	190	-13192.60	28984.30	45.5	Pass
		Horizontal	ROHN 2.5 STD	196	-8664.40	33028.40	26.2	Pass
		Horizontal	ROHN 2.5 STD	199	-13155.60	33028.40	39.8	Pass
		Horizontal	ROHN 2.5 STD	202	-12293.90	33028.40	37.2	Pass
		Horizontal	ROHN 2.5 STD	211	-10489.00	22405.40	46.8	Pass
		Horizontal	ROHN 2.5 STD	214	-16397.60	22405.40	73.2	Pass
		Horizontal	ROHN 2.5 STD	217	-14907.10	22405.40	66.5	Pass
		Horizontal	ROHN 2.5 STD	217	-14907.10	22405.40	66.5	Pass

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 71 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by TJL

Section No.	Elevation ft	Component Type	Size	Critical Element	P lb	σP_{allow} lb	% Capacity	Pass Fail
T11	40 - 30	Horizontal	ROHN 2.5 STD	223	-10007.90	25378.10	39.4	Pass
		Horizontal	ROHN 2.5 STD	226	-15557.50	25378.10	61.3	Pass
		Horizontal	ROHN 2.5 STD	229	-14264.80	25378.10	56.2	Pass
		Horizontal	ROHN 2.5 STD	238	-10965.50	19925.90	55.0	Pass
		Horizontal	ROHN 2.5 STD	241	-17342.40	19925.90	87.0	Pass
T13	20 - 0	Horizontal	ROHN 2.5 STD	244	-15650.20	19925.90	78.5	Pass
		Horizontal	P3.5x.226	268	-12111.80	49951.20	24.2	Pass
T1	180 - 160	Horizontal	P3.5x.226	275	-19566.80	49951.20	30.5 (b)	Pass
		Horizontal	P3.5x.226	283	-17443.80	49951.20	39.2	Pass
		Horizontal	P3.5x.226	283	-17443.80	49951.20	49.2 (b)	Pass
T4	133.333 - 126.667	Top Girt	ROHN 1.5 STD	4	324.64	21277.80	34.9	Pass
		Top Girt	ROHN 1.5 STD	5	-118.96	22660.50	44.1 (b)	Pass
T5	126.667 - 120	Top Girt	ROHN 1.5 STD	6	-352.97	22660.50	1.5	Pass
		Top Girt	ROHN 2 STD	97	-6429.58	29081.40	0.5	Pass
		Top Girt	ROHN 2 STD	98	-7645.62	29081.40	1.6	Pass
T8	90 - 80	Top Girt	ROHN 2 STD	99	-8463.67	29081.40	22.1	Pass
		Top Girt	ROHN 2 STD	99	-8463.67	29081.40	23.3 (b)	Pass
T12	30 - 20	Top Girt	ROHN 2 STD	112	-7739.11	27207.90	26.3	Pass
		Top Girt	ROHN 2 STD	113	-9083.31	27207.90	27.7 (b)	Pass
T13	20 - 0	Redund Horz 1 Bracing	ROHN 2 STD	114	-9772.57	27207.90	29.1	Pass
		Redund Horz 1 Bracing	ROHN 2 STD	114	-9772.57	27207.90	30.7 (b)	Pass
T13	20 - 0	Redund Horz 1 Bracing	ROHN 2 STD	169	-8053.45	16719.60	28.4	Pass
		Redund Horz 1 Bracing	ROHN 2 STD	170	-12002.70	16719.60	33.4	Pass
T13	20 - 0	Redund Horz 1 Bracing	ROHN 2.5 EH	171	-11391.30	16719.60	35.9	Pass
		Redund Horz 1 Bracing	ROHN 2.5 EH	171	-11391.30	16719.60	48.2	Pass
T13	20 - 0	Redund Horz 1 Bracing	ROHN 2.5 EH	253	-11575.40	22438.80	71.8	Pass
		Redund Horz 1 Bracing	ROHN 2.5 EH	254	-18017.40	22438.80	68.1	Pass
T13	20 - 0	Redund Horz 1 Bracing	ROHN 2.5 EH	255	-16199.90	22438.80	51.6	Pass
		Redund Horz 1 Bracing	ROHN 2.5 EH	255	-16199.90	22438.80	80.3	Pass
T13	20 - 0	Redund Horz 1 Bracing	ROHN 1.5 STD	270	-5192.47	13802.80	72.2	Pass
		Redund Horz 1 Bracing	ROHN 1.5 STD	270	-5192.47	13802.80	37.6	Pass
T13	20 - 0	Redund Horz 1 Bracing	ROHN 1.5 STD	273	-5237.37	13802.80	37.9	Pass
		Redund Horz 1 Bracing	ROHN 1.5 STD	273	-5237.37	13802.80	37.9	Pass
T13	20 - 0	Redund Horz 1 Bracing	ROHN 1.5 STD	277	-5237.37	13802.80	37.9	Pass
		Redund Horz 1 Bracing	ROHN 1.5 STD	277	-5237.37	13802.80	37.9	Pass
T13	20 - 0	Redund Horz 1 Bracing	ROHN 1.5 STD	280	-5391.94	13802.80	39.1	Pass
		Redund Horz 1 Bracing	ROHN 1.5 STD	280	-5391.94	13802.80	39.1	Pass
T13	20 - 0	Redund Horz 1 Bracing	ROHN 1.5 STD	285	-5391.94	13802.80	39.1	Pass
		Redund Horz 1 Bracing	ROHN 1.5 STD	285	-5391.94	13802.80	39.1	Pass
T13	20 - 0	Redund Horz 1 Bracing	ROHN 1.5 STD	288	-5192.47	13802.80	37.6	Pass
		Redund Horz 1 Bracing	ROHN 1.5 STD	288	-5192.47	13802.80	37.6	Pass
T13	20 - 0	Redund Diag 1 Bracing	ROHN 2 STD	271	-4743.86	8998.85	52.7	Pass
		Redund Diag 1 Bracing	ROHN 2 STD	271	-4743.86	8998.85	52.7	Pass
T13	20 - 0	Redund Diag 1 Bracing	ROHN 2 STD	274	-4784.88	8998.85	53.2	Pass
		Redund Diag 1 Bracing	ROHN 2 STD	274	-4784.88	8998.85	53.2	Pass
T13	20 - 0	Redund Diag 1 Bracing	ROHN 2 STD	278	-4784.88	8998.85	53.2	Pass
		Redund Diag 1 Bracing	ROHN 2 STD	278	-4784.88	8998.85	53.2	Pass
T13	20 - 0	Redund Diag 1 Bracing	ROHN 2 STD	281	-4926.09	8998.85	54.7	Pass
		Redund Diag 1 Bracing	ROHN 2 STD	281	-4926.09	8998.85	54.7	Pass
T13	20 - 0	Redund Diag 1 Bracing	ROHN 2 STD	286	-4926.09	8998.85	54.7	Pass
		Redund Diag 1 Bracing	ROHN 2 STD	286	-4926.09	8998.85	54.7	Pass
T13	20 - 0	Redund Diag 1 Bracing	ROHN 2 STD	289	-4743.86	8998.85	52.7	Pass
		Redund Diag 1 Bracing	ROHN 2 STD	289	-4743.86	8998.85	52.7	Pass
T13	20 - 0	Redund Hip 1 Bracing	ROHN 2.5 STD	282	-17.44	48180.50	0.2	Pass
		Redund Hip 1 Bracing	ROHN 2.5 STD	282	-17.44	48180.50	0.2	Pass
T13	20 - 0	Redund Hip 1 Bracing	ROHN 2.5 STD	290	-17.58	48180.50	0.2	Pass
		Redund Hip 1 Bracing	ROHN 2.5 STD	290	-17.58	48180.50	0.2	Pass
T13	20 - 0	Redund Hip 1 Bracing	ROHN 2.5 STD	291	-17.46	48180.50	0.2	Pass
		Redund Hip 1 Bracing	ROHN 2.5 STD	291	-17.46	48180.50	0.2	Pass
T1	180 - 160	Inner Bracing	L2x2x1/8	16	-1.80	8234.10	0.4	Pass

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 72 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by TJL

Section No.	Elevation ft	Component Type	Size	Critical Element	P lb	ϕP_{allow} lb	% Capacity	Pass Fail
		Inner Bracing	L2x2x1/8	17	-1.84	8234.10	0.4	Pass
		Inner Bracing	L2x2x1/8	18	-1.71	8234.10	0.4	Pass
		Inner Bracing	L2x2x1/8	28	-1.40	8287.35	0.4	Pass
		Inner Bracing	L2x2x1/8	29	-1.41	8287.35	0.4	Pass
		Inner Bracing	L2x2x1/8	30	-1.38	8287.35	0.4	Pass
		Inner Bracing	L2x2x1/8	37	-0.29	8341.12	0.4	Pass
		Inner Bracing	L2x2x1/8	38	-0.28	8341.12	0.4	Pass
		Inner Bracing	L2x2x1/8	39	-0.32	8341.12	0.4	Pass
T2	160 - 140	Inner Bracing	L2x2x1/8	52	-4.71	6068.75	0.5	Pass
		Inner Bracing	L2x2x1/8	53	-4.87	6068.75	0.5	Pass
		Inner Bracing	L2x2x1/8	54	-4.69	6068.75	0.5	Pass
		Inner Bracing	L2x2x1/8	64	-4.25	7007.17	0.4	Pass
		Inner Bracing	L2x2x1/8	65	-4.44	7007.17	0.4	Pass
		Inner Bracing	L2x2x1/8	66	-4.22	7007.17	0.4	Pass
		Inner Bracing	L2x2x1/8	76	-6.18	8181.36	0.4	Pass
		Inner Bracing	L2x2x1/8	77	-6.50	8181.36	0.4	Pass
		Inner Bracing	L2x2x1/8	78	-6.12	8181.36	0.4	Pass
T3	140 - 133.333	Inner Bracing	L2x2x1/8	91	-7.23	5306.96	0.5	Pass
		Inner Bracing	L2x2x1/8	92	-7.43	5306.96	0.5	Pass
		Inner Bracing	L2x2x1/8	93	-7.20	5306.96	0.5	Pass
T4	133.333 - 126.667	Inner Bracing	L2x2x1/8	106	-9.60	4680.37	0.5	Pass
		Inner Bracing	L2x2x1/8	107	-9.77	4680.37	0.5	Pass
		Inner Bracing	L2x2x1/8	108	-9.58	4680.37	0.5	Pass
T5	126.667 - 120	Inner Bracing	L2x2x1/8	121	-10.46	4158.54	0.5	Pass
		Inner Bracing	L2x2x1/8	122	-10.60	4158.54	0.5	Pass
		Inner Bracing	L2x2x1/8	123	-10.44	4158.54	0.5	Pass
T6	120 - 100	Inner Bracing	L2 1/2x2 1/2x3/16	136	-11.40	9072.37	0.4	Pass
		Inner Bracing	L2 1/2x2 1/2x3/16	137	-11.49	9072.37	0.4	Pass
		Inner Bracing	L2 1/2x2 1/2x3/16	138	-11.39	9072.37	0.4	Pass
		Inner Bracing	L2 1/2x2 1/2x3/16	148	-11.97	10738.30	0.4	Pass
		Inner Bracing	L2 1/2x2 1/2x3/16	149	-12.09	10738.30	0.4	Pass
		Inner Bracing	L2 1/2x2 1/2x3/16	150	-11.96	10738.30	0.4	Pass
T7	100 - 90	Inner Bracing	L2 1/2x2 1/2x3/16	163	-10.15	7766.06	0.5	Pass
		Inner Bracing	L2 1/2x2 1/2x3/16	164	-10.24	7766.06	0.5	Pass
		Inner Bracing	L2 1/2x2 1/2x3/16	165	-10.13	7766.06	0.5	Pass
T8	90 - 80	Inner Bracing	L2 1/2x2 1/2x3/16	178	-10.38	6565.57	0.5	Pass
		Inner Bracing	L2 1/2x2 1/2x3/16	179	-10.47	6565.57	0.5	Pass
		Inner Bracing	L2 1/2x2 1/2x3/16	180	-10.36	6565.57	0.5	Pass
T9	80 - 60	Inner Bracing	L3x3x3/16	193	-12.22	8593.12	0.6	Pass
		Inner Bracing	L3x3x3/16	194	-12.32	8593.12	0.6	Pass
		Inner Bracing	L3x3x3/16	195	-12.18	8593.12	0.6	Pass
		Inner Bracing	L3x3x3/16	205	-11.79	9851.38	0.5	Pass
		Inner Bracing	L3x3x3/16	206	-11.90	9851.38	0.5	Pass
		Inner Bracing	L3x3x3/16	207	-11.75	9851.38	0.5	Pass
T10	60 - 40	Inner Bracing	L3 1/2x3 1/2x1/4	220	-14.62	14095.40	0.4	Pass
		Inner Bracing	L3 1/2x3 1/2x1/4	221	-14.71	14095.40	0.4	Pass
		Inner Bracing	L3 1/2x3 1/2x1/4	222	-14.58	14095.40	0.4	Pass
		Inner Bracing	L3 1/2x3 1/2x1/4	232	-14.16	15896.00	0.3	Pass
		Inner Bracing	L3 1/2x3 1/2x1/4	233	-14.25	15896.00	0.3	Pass
		Inner Bracing	L3 1/2x3 1/2x1/4	234	-14.11	15896.00	0.3	Pass
T11	40 - 30	Inner Bracing	L3 1/2x3 1/2x1/4	247	-14.88	12584.30	0.4	Pass
		Inner Bracing	L3 1/2x3 1/2x1/4	248	-14.96	12584.30	0.4	Pass
		Inner Bracing	L3 1/2x3 1/2x1/4	249	-14.83	12584.30	0.4	Pass
T12	30 - 20	Inner Bracing	L3 1/2x3 1/2x1/4	262	-15.72	11303.80	0.4	Pass
		Inner Bracing	L3 1/2x3 1/2x1/4	263	-15.80	11303.80	0.4	Pass
		Inner Bracing	L3 1/2x3 1/2x1/4	264	-15.68	11303.80	0.4	Pass
T13	20 - 0	Inner Bracing	ROHN 2 STD	292	-13.80	6590.81	0.4	Pass
		Inner Bracing	ROHN 2 STD	293	-14.23	6590.81	0.4	Pass
		Inner Bracing	ROHN 2 STD	294	-13.53	6590.81	0.4	Pass

Summary

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 73 of 73
	Project 180-ft Lattice Tower (CSP #32)	Date 15:45:34 06/11/24
	Client Verizon	Designed by TJL

Section No.	Elevation ft	Component Type	Size	Critical Element	P lb	θP_{allow} lb	% Capacity	Pass Fail
						Leg (T12)	62.6	Pass
						Diagonal (T12)	93.8	Pass
						Horizontal (T11)	87.0	Pass
						Top Girt (T12)	80.3	Pass
						Redund Horz 1 Bracing (T13)	39.1	Pass
						Redund Diag 1 Bracing (T13)	54.7	Pass
						Redund Hip 1 Bracing (T13)	0.2	Pass
						Inner Bracing (T9)	0.6	Pass
						Bolt Checks	67.7	Pass
						RATING =	93.8	Pass

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 1 of 3
	Project 180-ft Lattice Tower (CSP #32)	Date 15:49:07 06/11/24
	Client Verizon	Designed by TJL

Load Combinations

Comb. No.	Description
1	Dead Only
2	Dead+Wind 0 deg - No Ice
3	Dead+Wind 30 deg - No Ice
4	Dead+Wind 45 deg - No Ice
5	Dead+Wind 60 deg - No Ice
6	Dead+Wind 90 deg - No Ice
7	Dead+Wind 120 deg - No Ice
8	Dead+Wind 135 deg - No Ice
9	Dead+Wind 150 deg - No Ice
10	Dead+Wind 180 deg - No Ice
11	Dead+Wind 210 deg - No Ice
12	Dead+Wind 225 deg - No Ice
13	Dead+Wind 240 deg - No Ice
14	Dead+Wind 270 deg - No Ice
15	Dead+Wind 300 deg - No Ice
16	Dead+Wind 315 deg - No Ice
17	Dead+Wind 330 deg - No Ice
18	Dead+Ice
19	Dead+Wind 0 deg+Ice
20	Dead+Wind 30 deg+Ice
21	Dead+Wind 45 deg+Ice
22	Dead+Wind 60 deg+Ice
23	Dead+Wind 90 deg+Ice
24	Dead+Wind 120 deg+Ice
25	Dead+Wind 135 deg+Ice
26	Dead+Wind 150 deg+Ice
27	Dead+Wind 180 deg+Ice
28	Dead+Wind 210 deg+Ice
29	Dead+Wind 225 deg+Ice
30	Dead+Wind 240 deg+Ice
31	Dead+Wind 270 deg+Ice
32	Dead+Wind 300 deg+Ice
33	Dead+Wind 315 deg+Ice
34	Dead+Wind 330 deg+Ice
35	Dead+Wind 0 deg - Service
36	Dead+Wind 30 deg - Service
37	Dead+Wind 45 deg - Service
38	Dead+Wind 60 deg - Service
39	Dead+Wind 90 deg - Service
40	Dead+Wind 120 deg - Service
41	Dead+Wind 135 deg - Service
42	Dead+Wind 150 deg - Service
43	Dead+Wind 180 deg - Service
44	Dead+Wind 210 deg - Service
45	Dead+Wind 225 deg - Service
46	Dead+Wind 240 deg - Service
47	Dead+Wind 270 deg - Service
48	Dead+Wind 300 deg - Service
49	Dead+Wind 315 deg - Service
50	Dead+Wind 330 deg - Service

Maximum Tower Deflections - Service Wind

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 2 of 3
	Project 180-ft Lattice Tower (CSP #32)	Date 15:49:07 06/11/24
	Client Verizon	Designed by TJL

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
T1	180 - 160	8.354	35	0.3549	0.2410
T2	160 - 140	6.848	35	0.3507	0.2178
T3	140 - 133.333	5.311	35	0.3230	0.1695
T4	133.333 - 126.667	4.836	35	0.3133	0.1642
T5	126.667 - 120	4.361	35	0.3017	0.1575
T6	120 - 100	3.917	35	0.2862	0.1522
T7	100 - 90	2.782	35	0.2282	0.1360
T8	90 - 80	2.282	35	0.2003	0.1212
T9	80 - 60	1.842	35	0.1700	0.1054
T10	60 - 40	1.096	35	0.1305	0.0765
T11	40 - 30	0.541	35	0.0863	0.0512
T12	30 - 20	0.328	35	0.0630	0.0381
T13	20 - 0	0.173	35	0.0390	0.0265

Critical Deflections and Radius of Curvature - Service Wind

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
187.00	ANT940Y10-WR	35	8.354	0.3549	0.2410	127179
181.00	ANT940Y10-WR	35	8.354	0.3549	0.2410	127179
177.00	PA6-65AC	35	8.131	0.3552	0.2397	127179
170.00	RFLBPS7496-180-14 Panel	35	7.609	0.3552	0.2348	63590
	Antenna					
169.00	3' Yagi	35	7.534	0.3551	0.2336	57809
160.00	ROHN 6'x15' Boom Gate (1)	35	6.848	0.3507	0.2178	38281
144.00	FFVV-65B-R2	35	5.606	0.3291	0.1743	20225
133.00	QD6616-7	35	4.813	0.3128	0.1640	65414
125.00	LTF12=372 Sector Mount (1)	35	4.246	0.2982	0.1559	13679
113.00	ANT150D	35	3.492	0.2667	0.1479	17884
60.00	GPS	35	1.096	0.1305	0.0765	23035

Maximum Tower Deflections - Design Wind

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
T1	180 - 160	10.393	19	0.4384	0.2765
T2	160 - 140	8.532	19	0.4334	0.2511
T3	140 - 133.333	6.638	19	0.3994	0.2094
T4	133.333 - 126.667	6.051	19	0.3878	0.2018
T5	126.667 - 120	5.465	19	0.3736	0.1943
T6	120 - 100	4.915	19	0.3548	0.1884
T7	100 - 90	3.504	19	0.2841	0.1672
T8	90 - 80	2.879	19	0.2499	0.1485
T9	80 - 60	2.328	19	0.2126	0.1288
T10	60 - 40	1.388	19	0.1637	0.0931
T11	40 - 30	0.687	19	0.1085	0.0621
T12	30 - 20	0.418	19	0.0793	0.0462
T13	20 - 0	0.221	30	0.0491	0.0321

tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job 22027.01 - Westport	Page 3 of 3
	Project 180-ft Lattice Tower (CSP #32)	Date 15:49:07 06/11/24
	Client Verizon	Designed by TJL

Critical Deflections and Radius of Curvature - Design Wind

<i>Elevation</i>	<i>Appurtenance</i>	<i>Gov. Load Comb.</i>	<i>Deflection</i>	<i>Tilt</i>	<i>Twist</i>	<i>Radius of Curvature</i>
<i>ft</i>			<i>in</i>	<i>°</i>	<i>°</i>	<i>ft</i>
187.00	ANT940Y10-WR	19	10.393	0.4384	0.2765	108684
181.00	ANT940Y10-WR	19	10.393	0.4384	0.2765	108684
177.00	PA6-65AC	19	10.117	0.4389	0.2751	108684
170.00	RFI BPS7496-180-14 Panel Antenna	19	9.471	0.4390	0.2700	54342
169.00	3' Yagi	19	9.378	0.4388	0.2689	49402
160.00	ROHN 6'x15' Boom Gate (1)	19	8.532	0.4334	0.2511	32610
144.00	FFVV-65B-R2	19	7.003	0.4068	0.2155	17631
133.00	QD6616-7	19	6.022	0.3871	0.2014	65414
125.00	LTF12=372 Sector Mount (1)	19	5.323	0.3693	0.1926	11577
113.00	ANT150D	19	4.388	0.3310	0.1825	14814
60.00	GPS	19	1.388	0.1637	0.0931	18432

Subject:

Anchor Bolt Analysis

Location:

180-ft Lattice Tower
 Westport, CT

Rev. 5: 1/22/24

Prepared by: T.J.L. Checked by: C.F.C.
 Job No. 22027.01

Anchor Bolt Analysis:

Input Data:

Tower Reactions

Tension Force =	Tension := 309-kips	(Input From InxTower)
Compression Force =	Compression := 355-kips	(Input From InxTower)
Shear Force =	Shear := 51-kips	(Input From InxTower)

Anchor Bolt Data:

ASTMA354 Grade BC		
Number of Anchor Bolts =	N := 10	(User Input)
Bolt Ultimate Strength =	$F_u := 125$ -ksi	(User Input)
Bolt Yield Strength =	$F_y := 109$ -ksi	(User Input)
Bolt Modulus =	E := 29000-ksi	(User Input)
Diameter of Anchor Bolts =	D := 1.00-in	(User Input)
Threads per Inch =	n := 8	(User Input)
Length from Top of Pier to Bottom of Leveling Nut =	$L_{ar} := 0$ -in	(User Input)

Anchor Bolt Analysis:

Calculated Anchor Bolt Properties:

Gross Area of Bolt =	$A_g := \frac{\pi}{4} \cdot D^2 = 0.785 \cdot \text{in}^2$
Net Area of Bolt =	$A_n := \frac{\pi}{4} \cdot \left(D - \frac{0.9743 \cdot \text{in}}{n} \right)^2 = 0.606 \cdot \text{in}^2$
Net Diameter =	$D_n := \frac{2 \cdot \sqrt{A_n}}{\sqrt{\pi}} = 0.878 \cdot \text{in}$
Radius of Gyration of Bolt =	$r := \frac{D_n}{4} = 0.22 \cdot \text{in}$
Elastic Section Modulus of Bolt =	$S_x := \frac{\pi \cdot D_n^3}{32} = 0.066 \cdot \text{in}^3$
Plastic Section Modulus of Bolt =	$Z_x := \frac{D_n^3}{6} = 0.113 \cdot \text{in}^3$

Anchor Bolt Design Strength:

Resistance Factor for Flexure =	$\phi_f := 0.9$
Resistance Factor for Compression =	$\phi_c := 0.9$
Resistance Factor for Tension =	$\phi_t := 0.75$
Resistance Factor for Shear =	$\phi_v := 0.75$
Design Tensile Strength =	$\Phi R_{nt} := \phi_t \cdot F_u \cdot A_n = 56.8 \cdot \text{k}$
Design Compression Strength =	$\Phi R_{nc} := \phi_c \cdot F_y \cdot A_g = 77 \cdot \text{k}$
Design Shear Strength (Tension) =	$\Phi R_{nv} := \phi_v \cdot 0.5 F_u \cdot A_g = 36.8 \cdot \text{k}$
Design Shear Strength (Compression) =	$\Phi R_{nvc} := \phi_c \cdot 0.6 F_y \cdot A_g \cdot 0.75 = 34.7 \cdot \text{k}$

Check Anchor Bolt Tension Force:

Maximum Tensile Force = $P_{ut} := \frac{\text{Tension}}{N} = 30.9 \cdot \text{kips}$

Maximum Compressive Force = $P_{uc} := \frac{\text{Compression}}{N} = 35.5 \cdot \text{kips}$

Maximum Shear Force = $V_u := \frac{\text{Shear}}{N} = 5.1 \cdot \text{kips}$

Condition1 = $\left[\text{if} \left[\left(\frac{P_{ut}}{\Phi R_{nt}} \right)^2 + \left(\frac{V_u}{\Phi R_{nv}} \right)^2 \right] \leq 1.00, \text{"OK"}, \text{"Overstressed"} \right]$

Condition1 = "OK"

Condition2 = $\left[\text{if} \left[\left(\frac{P_{uc}}{\Phi R_{nc}} \right) + \left(\frac{V_u}{\Phi R_{nvc}} \right)^2 \right] \leq 1.00, \text{"OK"}, \text{"Overstressed"} \right]$

Condition2 = "OK"

Bolt % of Capacity = $\max \left[\left(\frac{P_{ut}}{\Phi R_{nt}} \right)^2 + \left(\frac{V_u}{\Phi R_{nv}} \right)^2, \left(\frac{P_{uc}}{\Phi R_{nc}} \right) + \left(\frac{V_u}{\Phi R_{nvc}} \right)^2 \right] = 48.2\%$

Caisson Foundation:

Input Data:

Tower Data

Uplift = Uplift := 309-kips (User Input)
 Compression = Comp := 355-kips (User Input)
 Shear Force = Shear := 51-kips (User Input)
 Tower Height = H_t := 180-ft (User Input)

Footing Data:

Length of Caisson = L_c := 27-ft (User Input)
 Extension of Caisson Above Grade = L_{cag} := 1-ft (User Input)
 Diameter of Caisson = d_c := 4.5-ft (User Input)
 Length of Caisson Above Water Table = $L_{c,AWT}$:= 27-ft (User Input)
 Length of Caisson Below Water Table = $L_{c,BWT}$:= 0-ft (User Input)

Material Properties:

Concrete Compressive Strength = f_c := 4000-psi (User Input)
 Steel Reinforcement Yield Strength = f_y := 60000-psi (User Input)
 Ultimate Skin Friction (Above Water Table) = μ_1 := 3.73-ksf (User Input)
 Ultimate Skin Friction (Below Water Table) = μ_2 := 3.73-ksf (User Input)
 Ultimate Soil Bearing Capacity = q_u := 6000-psf (Assumed Conservative User Input)
 Unit Weight of Soil = γ_{soil} := 120-pcf (User Input)
 Unit Weight of Concrete = γ_{conc} := 150-pcf (User Input)
 Depth to Neglect = n := 5-ft (User Input)
 Resistance Factor for Bearing = $\Phi_{sBearing}$:= 0.75 (TIA-222-H 9.7)
 Resistance Factor for Friction = $\Phi_{sFriction}$:= 0.75 (TIA-222-H 9.7)

Calculated Properties:

Adjusted Concrete Unit Weight = $\gamma_c := \gamma_{conc} - 62.4 \text{pcf} = 87.6 \text{pcf}$

Weight of Concrete Caisson (no water) = $WT_{c,comp} := \frac{\pi}{4} \cdot (d_c^2 \cdot L_c) \cdot \gamma_{conc} = 64.412 \cdot \text{kips}$

Weight of Concrete Caisson (water) = $WT_{c,uplift} := \frac{\pi}{4} \cdot \left[(d_c^2 \cdot L_{c,AWT}) \cdot \gamma_{conc} + (d_c^2 \cdot L_{c,BWT}) \cdot \gamma_c \right] = 64.412 \cdot \text{kips}$

Check Uplift:

Uplift Resistance from Concrete Weight = $Uplift_{conc} := (WT_{c,uplift}) \cdot 0.9 = 57.971 \cdot \text{kips}$

Uplift Resistance from Skin Friction = $Uplift_{SF} := \Phi_{sFriction} \cdot \pi \cdot d_c \cdot \left[(L_{c,AWT} - L_{cag} - \eta) \cdot \mu_1 + L_{c,BWT} \cdot \mu_2 \right] = 831 \cdot \text{kips}$

Total Uplift Resistance = $Uplift_R := Uplift_{conc} + Uplift_{SF} = 888.494 \cdot \text{kips}$

Uplift Check = $\frac{Uplift}{Uplift_R} = 34.78\%$

$Uplift_Check := \text{if} \left(\frac{Uplift_R}{Uplift} \geq 1.0, \text{"Okay"}, \text{"No Good"} \right)$

Uplift_Check = "Okay"

Check Compression:

Total Compression Force = $Comp_{tot} := WT_{c,comp} + Comp = 419 \cdot \text{kips}$

Compression Resistance from Bearing = $Comp_{bearing} := \Phi_{sBearing} \cdot \left(\frac{\pi}{4} \cdot d_c^2 \cdot q_u \right) = 72 \cdot \text{kips}$

Compression Resistance from Skin Friction = $Comp_{SF} := \Phi_{sFriction} \cdot \pi \cdot d_c \cdot \left[(L_{c,AWT} - L_{cag} - \eta) \cdot \mu_1 + L_{c,BWT} \cdot \mu_2 \right] = 831 \cdot \text{kips}$

Total Compression Resistance = $Comp_R := Comp_{bearing} + Comp_{SF} = 902 \cdot \text{kips}$

Compression Check = $\frac{Comp_{tot}}{Comp_R} = 46.49\%$

$Compression_Check := \text{if} \left(\frac{Comp_R}{Comp_{tot}} \geq 1.0, \text{"Okay"}, \text{"No Good"} \right)$

Compression_Check = "Okay"



Colliers Engineering & Design,
Architecture, Landscape Architecture, Surveying, CT P.C.
1055 Washington Boulevard
Stamford, CT 06901
203.324.0800
peter.albano@collierseng.com

Post-Modification Antenna Mount Analysis Report and PMI Requirements

Mount ReAnalysis-VZW

SMART Tool Project #: 10214355
Colliers Engineering & Design Project #: 21777772 (Rev. 3)

November 20, 2023

Site Information

Site ID: 5000104750-VZW / WESTPORT CT
Site Name: WESTPORT CT
Carrier Name: Verizon Wireless
Address: 880 Post Rd. East Unit 1
Westport, Connecticut 06880
Fairfield County
Latitude: 41.137475°
Longitude: -73.334364°

Structure Information

Tower Type: 180-Ft Self Support
Mount Type: 15.00-Ft Sector Frame

FUZE ID # 16242132

Analysis Results

Sector Frame: 70.2% Pass w/ Modifications*

*Antennas and equipment to be installed in compliance with PMI Requirements of this mount analysis.

***Contractor PMI Requirements:

Included at the end of this MA report

Available & Submitted via portal at <https://pmi.vzwsmart.com>

For additional questions and support, please reach out to:

pmisupport@colliersengineering.com

Report Prepared By: Prasanna Dhakal



11/21/2023

Executive Summary:

The objective of this report is to summarize the analysis results of the antenna support mount including the proposed modifications at the subject facility for the final wireless telecommunications configuration, per the applicable codes and standards.

This analysis is inclusive of the mount structure only and does not address the structural capacity of the supporting structure. This mounting frame was not analyzed as an anchor attachment point for fall protection. All climbing activities are required to have a fall protection plan completed by a competent person.

Sources of Information:

Document Type	Remarks
Radio Frequency Data Sheet (RFDS)	Verizon RFDS, Site ID: 325126, dated November 8, 2023
Mount Mapping Report	Structural Components, Site ID: 16242132, dated October 19, 2021
Previous Mount Analysis Report	Maser Consulting Connecticut, Project #: 21777772A, dated November 2, 2021
Mount Modification Drawings	Colliers Engineering & Design Project #: 21777772A, dated July 18, 2023

Analysis Criteria:

Codes and Standards:	ANSI/TIA-222-H 2022 Connecticut State Building Code (CSBC), Effective October 1, 2022
Wind Parameters:	Basic Wind Speed (Ultimate 3-sec. Gust), V_{ULT} : 120 mph Ice Wind Speed (3-sec. Gust): 50 mph Design Ice Thickness: 1.00 in Risk Category: II Exposure Category: B Topographic Category: 1 Topographic Feature Considered: N/A Topographic Method: N/A Ground Elevation Factor, K_e : 0.998
Seismic Parameters:	S_s : 0.232 g S_1 : 0.056 g
Maintenance Parameters:	Wind Speed (3-sec. Gust): 30 mph Maintenance Load, L_v : 250 lbs. Maintenance Load, L_m : 500 lbs.
Analysis Software:	RISA-3D (V17)

Final Loading Configuration:

The following equipment has been considered for the analysis of the mounts:

Mount Elevation (ft)	Equipment Elevation (ft)	Quantity	Manufacturer	Model	Status
159.00	161.80	1	Samsung	MT6413-77A	Added
	160.00	4	JMA	MX06FRO640-02	
		2	Samsung	MT6413-77A	
		1	Samsung	RF4439d-25A	
		3	Samsung	RF4461d-13A	
		4	Commscope	JAHH-65B-R3B	
	2	Samsung	XXDWMM-12.5-65	Retained	
	2	Commscope	CBC78T-DS-43-2X		
	3	Samsung	B2/B66A RRH-BR049		
	1	Samsung	B5/B13 RRH-BR04C		
	1	Raycap	RHSDC-6627-PF-48*		
	158.50	1	Samsung	XXDWMM-12.5-65	

* Equipment is flush mounted directly to the Self Support. It is not mounted on Sector Frame mounts and is not included in this mount analysis.

The recent mount mapping reported existing OVP units. It is acceptable to install up to any three (3) of the OVP model numbers listed below as required at any location other than the mount face without affecting the structural capacity of the mount. If OVP units are installed on the mount face, a mount re-analysis may be required unless replacing an existing OVP.

Model Number	Ports	AKA
DB-B1-6C-12AB-0Z	6	OVP-6
RVZDC-6627-PF-48	12	OVP-12

Standard Conditions:

1. All engineering services are performed on the basis that the information provided to Colliers Engineering & Design and used in this analysis is current and correct. The existing equipment loading has been applied at locations determined from the supplied documentation. Any deviation from the loading locations specified in this report shall be communicated to Colliers Engineering & Design to verify deviation will not adversely impact the analysis.
2. Mounts are assumed to have been properly fabricated, installed and maintained in good condition, twist free and plumb in accordance with its original design and manufacturer's specifications.

Obvious safety and structural issues/deficiencies noticed at the time of the mount mapping and reported in the Mount Mapping Report are assumed to be corrected and documented as part of the PMI process and are not considered in the mount analysis.

The mount analysis and the mount mapping are not a condition assessment of the mount. Proper maintenance and condition assessments are still required post analysis.

3. For mount analyses completed from other data sources (including new replacement mounts) and not specifically mapped in accordance with the NSTD-446 Standard, the mounts are assumed to have been properly fabricated, installed and maintained in good condition, twist free and plumb in accordance with its original design and manufacturer's specifications.

4. All member connections are assumed to have been designed to meet or exceed the load carrying capacity of the connected member unless otherwise specified in this report.
5. The mount was checked up to, and including, the bolts that fasten it to the mount collar/attachment and threaded rod connections in collar members if applicable. Local deformation and interaction between the mount collar/attachment and the supporting tower structure are outside the scope of this analysis.
6. All services are performed, results obtained, and recommendations made in accordance with generally accepted engineering principles and practices. Colliers Engineering & Design is not responsible for the conclusion, opinions, and recommendations made by others based on the information supplied.
7. Structural Steel Grades have been assumed as follows, if applicable, unless otherwise noted in this analysis:
 - o Channel, Solid Round, Angle, Plate ASTM A36 (Gr. 36)
 - o HSS (Rectangular) ASTM 500 (Gr. B-46)
 - o Pipe ASTM A53 (Gr. B-35)
 - o Threaded Rod F1554 (Gr. 36)
 - o Bolts ASTM A325
8. Any mount modifications listed under Sources of Information are assumed to have been installed per the design specifications.

Discrepancies between in-field conditions and the assumptions listed above may render this analysis invalid unless explicitly approved by Colliers Engineering & Design.

Analysis Results:

Component	Utilization %	Pass/Fail
Standoff Bar	70.2%	Pass
Face Horizontal	34.4%	Pass
Standoff Horizontal	33.9%	Pass
Standoff Diagonal	31.8%	Pass
Standoff Vertical	3.1%	Pass
Mount Pipe	43.1%	Pass
Unistrut	11.2%	Pass
Mod Tieback	4.5%	Pass
Mount Connection	57.2%	Pass

Structure Rating – (Controlling Utilization of all Components)	70.2%
-----------------------------------------------------------------------	--------------

Mount Steel (EPA)_a per ANSI/TIA-222-H Section 2.6.11.2:

Ice Thickness (In)	Mount Pipes Excluded		Mount Pipes Included	
	Front (EPA) _a (Sq. Ft.)	Side (EPA) _a (Sq. Ft.)	Front (EPA) _a (Sq. Ft.)	Side (EPA) _a (Sq. Ft.)
0	26.8	17.0	33.6	23.8
0.5	38.1	24.8	47.8	34.5
1	48.7	31.8	61.3	44.4

Notes:

- (EPA)_a values listed above may be used in the absence of more precise information
- (EPA)_a values in the table above include 1 sector.
- K_a factors included in (EPA)_a calculations

Requirements:

The existing mounts will be **SUFFICIENT** for the final loading configuration (attachment 2) after the modifications detailed in attachment 3 are successfully completed.

ANSI/ASSP rigging plan review services compliant with the requirements of ANSI/TIA 322 are available for a Construction Class IV site or other, if required. Separate review fees will apply.

Attachments:

1. **Contractor Required PMI Report Deliverables**
2. Antenna Placement Diagrams
3. Mount Modification Drawings
4. Mount Photos
5. Mount Mapping Report (for reference only)
6. Analysis Calculations

Mount Desktop – Post Modification Inspection (PMI) Report Requirements

Documents & Photos Required from Contractor – Mount Modification

Electronic pdf version of this can be downloaded at <https://pmi.vzwsmart.com>

For additional questions and support, please reach out to pmisupport@colliersengineering.com

MDG #: 5000104750

SMART Project #: 10214355

Fuze Project ID: 16242132

Purpose – to upload the proper documentation to the SMART Tool in order to allow the SMART Tool engineering vendor to complete the required Mount Desktop review of the Post Modification Inspection Report.

- Contractor is responsible for making certain the photos provided as noted below provide confirmation that the modification was completed in accordance with the modification drawings.
- Contractor shall relay any data that can impact the performance of the mount or the mount modification, this includes safety issues.

Base Requirements:

- If installation of the modification will cause damage to the structure, the climbing facility, or safety climb if present or any installed system, SMART Tool vendor to be notified prior to install. Any special photos outside of the standard requirements will be indicated on the drawings.
- Provide “as built drawings” showing contractor’s name, preparer’s signature, and date. Any deviations from the drawings (proposed modification) shall be shown. NOTE: If loading is different than what is conveyed in the post-modification passing mount analysis (MA) contact the SMART Tool vendor immediately.
- Each photo shall be time and date stamped.
- Photos should be high resolution.
- Contractor shall ensure that the safety climb wire rope is not adversely impacted by the install of the modification components. This may involve the install of wire rope guides, or other items to protect the wire rope. If there is conflict, contact the SMART Tool engineer for recommendations.
- The PMI can be accessed at the following portal: <https://pmi.vzwsmart.com>

Photo Requirements:

- Photos taken at ground level
 - Photo of Gate Signs showing the tower owner, site name, and number.
 - Overall tower structure after installation of the modifications.
 - Photos of the mount after installation of the modifications; if the mounts are at different rad elevations, pictures must be provided for all elevations that the modifications were installed
- Photos taken at Mount Elevation
 - Photos showing the safety climb wire rope above and below the mount prior to modification.
 - Photos showing the climbing facility and safety climb if present.

- Photos showing each individual sector after installation of modifications. Each entire sector must be in one photo to show the interconnection of members.
 - These photos shall also certify that the placement and geometry of the equipment on the mount is as depicted in the antenna placement diagram in this form.
- Photos that show the model number of each antenna and piece of equipment installed per sector.
- Photos of each installed modification per the modification drawings; pictures shall also include connection hardware (U-bolts, bolts, nuts, all-threaded rods, etc.)
- Photos showing the distances (relative distance between collars) of the installed modifications from the appropriate reference locations shown in the modification drawings.
- Photos showing the installed modifications onto the tower (i.e. ring/collar mounts, tie-backs, V-bracing kits, etc.); if the existing mount elevation needs to be changed according to the modification drawings, an elevation measurement shall be provided before the elevation change.

Material Certification:

- Materials utilized must be as per specification on the drawings or the equivalent as validated by the SMART Tool vendor.
 - If the materials are as specified on the drawings
 - The contractor shall provide the packing list, or the materials certifications for the materials utilized to perform the mount modification
 - Commscope, Metrosite, Perfect Vision, Sabre, and Site Pro have all agreed to support Verizon vendors with the necessary material certifications
 - If seeking permission to use an equivalent
 - It is required that the SMART Tool engineering vendor approval of such is included in the contractor submission package. There may be an additional charge for approval if the equivalent submission doesn't meet specifications as prescribed in the drawings.

All hardware has been properly installed, and the existing hardware was inspected.

The material utilized was as specified on the SMART Tool engineering vendor Mount Modification Drawings and included in the material certification folder is a packing list or invoice for these materials.

OR

The material utilized was approved by a SMART Tool engineering vendor as an "equivalent" and this approval is included as part of the contractor submission.

Antenna & Equipment Placement and Geometry Confirmation:

The contractor certifies that the photos support and the equipment on the mount is as depicted on the sketch and table included in this form and with the mount analysis provided.

OR

- The contractor notes that the equipment on the mount is not in accordance with the sketch and has noted the differences below and provided photo documentation of any alterations.

Comments:

Was the mount modification completed in conjunction with the equipment change / installation?

- Yes No

Special Instructions / Validation as required from the MA or Mod Drawings:

Issue:

1. Contractor shall inspect climbing facilities and safety climb and ensure they are in good condition. Contractor shall install safety climb wire rope guides in locations where wire rope is rubbing against the mount or mount-to-tower connection steel. Wire brush clean any observed corrosion and protect with two (2) coats of cold galvanization (Zinga or Zinc Kote). Contractor shall provide photos of wire rope guide installation as part of PMI documents. Contact EOR if additional guidance is required.

Response:

Special Instruction Confirmation:

- The contractor has read and acknowledges the above special instructions.

Comments:

Contractor certifies that the climbing facility / safety climb was not damaged prior to starting work:

- Yes No

Contractor certifies no new damage created during the current installation:

- Yes No

Contractor to certify the condition of the safety climb and verify no damage when leaving the site:

- Safety Climb in Good Condition Safety Climb Damaged

Comments:

--

Certifying Individual:

Company:	
Employee Name:	
Contact Phone:	
Email:	
Date:	

Structure: 5000104750-VZW - WESTPORT CT

Sector: A

11/20/2023


Structure Type: Self Support

10214355



Mount Elev: 159.00

Page: 1



Ref#	Model	Height (in)	Width (in)	H Dist Frm L.	Pipe #	Pipe Pos V	Ant Pos	C. Ant Frm T.	Ant H Off	Status	Validation
A1	MX06FRO640-02	72	19.8	169	1	a	Front	24	-11	Added	
A1	MX06FRO640-02	72	19.8	169	1	b	Front	24	11	Added	
R4	RF4461d-13A	15	15	169	1	a	Behind	24	0	Added	
A2	MT6413-77A	28.9	15.8	78	2	a	Front	3	0	Added	
A6	XXDWMM-12.5-65	16.2	11.4	78	2	a	Front	42	0	Retained	10/19/2021
R3	RF4439d-25A	15	15	78	2	a	Behind	24	0	Added	
R9	B2/B66A RRH-BR049	15	15	47.5	3	a	Behind	24	0	Retained	10/19/2021
A1	MX06FRO640-02	72	19.8	3	4	a	Front	24	-11	Added	
A1	MX06FRO640-02	72	19.8	3	4	b	Front	24	11	Added	
R4	RF4461d-13A	15	15	3	4	a	Behind	24	0	Added	


Sector: **B**
 Structure Type: Self Support
 Mount Elev: 159.00

10214355

11/20/2023



Page: 2



Ref#	Model	Height (in)	Width (in)	H Dist Fm L.	Pipe #	Pipe Pos V	Ant Pos	C. Ant Fm T.	Ant H Off	Status	Validation
A5	JAHH-65B-R3B	72	13.8	169	1	a	Front	24	-7.5	Retained	10/19/2021
A5	JAHH-65B-R3B	72	13.8	169	1	b	Front	24	7.5	Retained	10/19/2021
R7	CBC78T-DS-43-2X	6.4	6.9	169	1	a	Behind	24	0	Retained	10/19/2021
A6	XXDWMM-12.5-65	16.2	11.4	78	2	a	Front	24	0	Retained	10/19/2021
R10	B5/B13 RRH-BR04C	15	15	47.5	3	a	Behind	24	0	Retained	10/19/2021
A2	MT6413-77A	28.9	15.8	3	4	a	Front	24	0	Added	
R9	B2/B66A RRH-BR049	15	15			Member				Retained	10/19/2021

Structure: 5000104750-VZW - WESTPORT CT


Sector: C
 Structure Type: Self Support
 Mount Elev: 159.00

10214355

11/20/2023



Page: 3



Ref#	Model	Height (in)	Width (in)	H Dist Fm L.	Pipe #	Pipe Pos V	Ant Pos	C. Ant Fm T.	Ant H Off	Status	Validation
A5	JAHH-65B-R3B	72	13.8	169	1	a	Front	24	-7.5	Retained	10/19/2021
A5	JAHH-65B-R3B	72	13.8	169	1	b	Front	24	7.5	Retained	10/19/2021
R7	CBC78T-DS-43-2X	6.4	6.9	169	1	a	Behind	24	0	Retained	10/19/2021
A6	XXDWMM-12.5-65	16.2	11.4	78	2	a	Front	24	0	Retained	10/19/2021
R4	RF4461d-13A	15	15	47.5	3	a	Behind	24	0	Added	
A2	MT6413-77A	28.9	15.8	3	4	a	Front	24	0	Added	
R9	B2/B66A RRH-BR049	15	15			Member				Retained	10/19/2021



**MOUNT MODIFICATION DRAWINGS
EXISTING 15.00' SECTOR FRAME**

**TOWER OWNER: CSP CORPORATION
TOWER OWNER SITE NUMBER: N/A**

**CARRIER SITE NAME: WESTPORT CT
CARRIER SITE NUMBER: 5000104750
FUZE ID: 16242132**

**880 POST RD. EAST UNIT 1
WESTPORT, CT 06880
FAIRFIELD COUNTY**

**LATITUDE: 41.137475° N
LONGITUDE: 73.334364° W**



www.colliumengineering.com
100 Weymouth Avenue
Westport, CT 06880
Tel: 203.334.4800
Fax: 203.334.4801
collium@colliumeng.com



NO.	AS SHOWN	DESCRIPTION	QUANTITY
1	REBAR	REBAR	1000
2	CONCRETE	CONCRETE	1000
3	STEEL	STEEL	1000
4	WELD	WELD	1000
5	PAINT	PAINT	1000
6	FINISH	FINISH	1000

DESIGN CRITERIA

WIND LOADS
BASIC WIND SPEED (3 SECOND GUST), V = 120 MPH
EXPOSURE CATEGORY B
TOPOGRAPHIC CATEGORY 1
MEAN BASE ELEVATION (AMSL) = 63.27'

ICE LOADS
ICE WIND SPEED (3 SECOND GUST), V = 50 MPH
ICE THICKNESS = 1.00 IN

SEISMIC LOADS
SEISMIC DESIGN CATEGORY B
SHORT TERM PCER GROUND MOTION, S₁ = 232
LONG TERM PCER GROUND MOTION, S₂ = 056

PROJECT INFORMATION

APPLICANT/LESSEE
COMPANY: VERIZON WIRELESS
CLIENT REPRESENTATIVE: PETER ALJANO
COMPANY: VERIZON WIRELESS

PROJECT MANAGER
COMPANY: COLLIER ENGINEERING & DESIGN CT, P.C.
CONTACT: PETER ALJANO
PHONE: 203.334.4800
EMAIL: PETER.ALJANO@COLLIUMENG.COM

CONTRACTOR PMI REQUIREMENTS
PMI LOCATION: [HTTPS://PMI.VERIZON.COM](https://pmi.verizon.com)
SMART TOOL PROJECT #: 10007445
PMI LOCATION CODE (MCO): 5000104750
ANALYSIS DATE: 7/18/2023

PMI REQUIREMENTS EMBEDDED WITHIN MOUNT MODIFICATION REPORT

SHEET INDEX

SHEET	DESCRIPTION
ST-1	TITLE SHEET
SB00H-1	BILL OF MATERIALS
SGN-1	GENERAL NOTES
SCF-1	CLIMBING FACILITY DETAIL
SS-1	MOUNTING DETAILS
SS-2	MOUNT PHOTOS
	SPECIFICATION SHEETS

**COPYRIGHT ©2023
COLLIERS ENGINEERING & DESIGN CT, P.C.**
ALL RIGHTS RESERVED
THIS DRAWING AND ALL THE INFORMATION CONTAINED HEREIN IS AUTHORIZED FOR USE ONLY BY THE PARTY FOR WHOM THE WORK WAS CONTRACTED OR TO WHOM IT IS CERTIFIED. THIS DRAWING MAY NOT BE COPIED, REPRODUCED, Duplicated, OR REPRODUCED IN ANY MANNER WITHOUT THE WRITTEN CONSENT OF COLLIER ENGINEERING & DESIGN CT, P.C.

NOTE: DO NOT SCALE DIMENSIONS FOR CONSTRUCTION

BILL OF MATERIALS

SECTION 1 - VZWSMART KITS

QUANTITY	MANUFACTURER	PART NUMBER	DESCRIPTION	NOTES	UNIT WEIGHT (LBS)	WEIGHT (LBS)
1	VZWSMART	VZWSMART-SIK1	TIE BACK ASSEMBLY	CONNECT OTHER END TO ADJACENT TOWER LEG. REINFORC TIE-BACK SHALL EXTEND NO MORE THAN 12" BEYOND THE TOWER LEG. CONTRACTOR SHALL TRIM AS REQUIRED AND PROTECT CUT END WITH TWO COATS OF ZINGA OR ZINC COTE	84	84
6	VZWSMART	VZWSMART-FHSKI	CROSSOVER PLATE			

SECTION 2 - OTHER REQUIRED PARTS

QUANTITY	MANUFACTURER	PART NUMBER	DESCRIPTION	NOTES	UNIT WEIGHT (LBS)	WEIGHT (LBS)

SECTION 3 - REQUIRED SAFETY CLIMB PARTS

QUANTITY	MANUFACTURER	PART NUMBER	DESCRIPTION	NOTES	UNIT WEIGHT (LBS)	WEIGHT (LBS)
1	PERFECT VISION	PV-CLAMP-LW-0106	CLAMP BRACKET	OR FOR APPROVED EQUIVALENT	*	*
1	PERFECT VISION	PV-CHK-CG-SM	WIRE ROPE GUIDE	OR FOR APPROVED EQUIVALENT	*	*
			TOTAL			84

NOTES:

1. THE MANUFACTURERS LISTED ARE THE APPROVED VENDORS FOR THE VZW MOUNT KITS. EACH MANUFACTURER WILL BE AWARE OF WHICH KITS HAVE BEEN THROUGH THE VZW APPROVAL PROCESS AND THEY ARE IN TURN APPROVED TO SELL. PLEASE NOTE THAT THE MATERIAL UTILIZED ON THE MOUNT MODIFICATIONS WILL BE REVIEWED AS A PART OF THE DESKTOP PMI COMPLETED BY THE SMART TOOL VENDOR. IT WILL BE REQUIRED THAT THE VZW KITS SPECIFIED ARE UTILIZED IN THE MODIFICATIONS.

2. ALL MATERIALS REQUIRED FOR THE DESIGNED MODIFICATIONS BUT NOT LISTED IN THIS SHEET ARE ASSUMED TO BE PROVIDED BY THE CONTRACTOR.

VZWSMART KITS - APPROVED VENDORS

CONTACT	SALVADOR ANGUIANO
PHONE	(817) 306-1492
EMAIL	SALVADOR.ANGUIANO@COMMSCOPE.COM
WEBSITE	WWW.COMMSCOPE.COM
CONTACT	KENT BANEY
PHONE	(260) 335-506 (O), (764) 983-9786 (M)
EMAIL	KENT@METROSITE.ILC.COM
WEBSITE	METROSITEFABRICATORS.COM

CONTACT	WIRELESS SALES
PHONE	(841) 887-6723
EMAIL	WWW.PERFECT-VISION.COM
WEBSITE	WIRELESS@PERFECT-VISION.COM
CONTACT	ANGE WELCH
PHONE	(866) 424-4937
EMAIL	ANGWEL@AMBIINDUSTRIES.COM
WEBSITE	WWW.SABRITESOLUTIONS.COM

CONTACT	PAULA BOSWELL
PHONE	(972) 236-8949
EMAIL	PAULA.BOSWELL@VALMOUNT.COM
WEBSITE	WWW.SITEPRO1.COM
CONTACT	NEWAVE SALES TEAM
PHONE	(717) 237-4166
EMAIL	SALES@NEWAVETC.COM
WEBSITE	WWW.NEWAVETC.COM

CONTACT	DAVID STANBERRY
PHONE	(615) 515-0990 (O), (615) 631-2329 (M)
EMAIL	DLJ@BETTERMETAL.COM
WEBSITE	WWW.BETTERMETAL.COM

Collins Engineering & Design
www.collinseng.com



1	CONCRETE FOUNDATION	100	100
2	STEEL BRACKET	100	100
3	STEEL BRACKET	100	100
4	STEEL BRACKET	100	100
5	STEEL BRACKET	100	100
6	STEEL BRACKET	100	100
7	STEEL BRACKET	100	100
8	STEEL BRACKET	100	100
9	STEEL BRACKET	100	100
10	STEEL BRACKET	100	100

COLBERT ENGINEERING DESIGN, P.C.
1275 W. 10TH ST.
DALLAS, TX 75201

IT IS A VIOLATION OF LAW FOR ANY PERSON TO BE RESPONSIBLE FOR THE DESIGN OR CONSTRUCTION OF THE PROJECTS LISTED IN THIS BILL OF MATERIALS.

SITE NAME:
WESTPORT CT
5000104750
880 POST RD, EAST UNIT 1
WESTPORT, CT 06880
FAIRFIELD COUNTY

Collins Engineering & Design
1005 S. MAIN ST.
WESTPORT, CT 06880
Phone: (203) 348-0001
Fax: (203) 348-0002
www.collinseng.com

BILL OF MATERIALS
SBOM-1

PROJECT NOTES

1. SEE MODIFICATION NOTES
2. THE CONTRACTOR SHALL COMPLY WITH ALL APPLICABLE CODES, REGULATIONS AND ORDINANCES, UTILITIES, UTILITY COMPANIES OR OTHER PUBLIC GOVERNING AUTHORITIES
3. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL PERMITS AND INSPECTIONS THAT MAY BE REQUIRED BY ANY FEDERAL, STATE, COUNTY OR MUNICIPAL AUTHORITIES.
4. THE CONTRACTOR SHALL NOTIFY THE CONSTRUCTION MANAGER IN WRITING OF ANY MODIFICATIONS PRIOR TO THE SUBMISSION OF BIDS OR PERFORMANCE OF WORK.
5. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING ALL EXISTING SITE IMPROVEMENTS PRIOR TO COMMENCING CONSTRUCTION. THE CONTRACTOR SHALL REPAIR ANY DAMAGE AS A RESULT OF CONSTRUCTION OF THE PROJECT. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE SATISFACTION OF THE OWNER.
6. THE SCOPE OF WORK FOR THIS PROJECT SHALL INCLUDE PROVIDING ALL MATERIALS, EQUIPMENT AND LABOR REQUIRED TO COMPLETE THIS PROJECT. ALL EQUIPMENT SHALL BE INSTALLED IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS.
7. THE CONTRACTOR SHALL NOTIFY THE PROJECT SITE PRIOR TO SUBMITTING THE DESIGN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL PERMITS AND INSPECTIONS THAT MAY BE REQUIRED BY ANY FEDERAL, STATE, COUNTY OR MUNICIPAL AUTHORITIES.
8. THE CONTRACTOR SHALL VERIFY ALL EXISTING DIMENSIONS AND CONDITIONS PRIOR TO COMMENCING ANY WORK. ALL DIMENSIONS OF EXISTING STRUCTURES SHALL BE VERIFIED BY THE CONTRACTOR PRIOR TO ORDERING MATERIAL OR PROCEEDING WITH CONSTRUCTION.
9. SINCE THE CELL SITE MAY BE ACTIVE, ALL SAFETY PRECAUTIONS MUST BE OBSERVED. EQUIPMENT SHOULD BE SHUT DOWN PRIOR TO PERFORMING ANY WORK THAT COULD EXPOSE THE WORKER TO DANGER. PERSONAL PROTECTIVE EQUIPMENT IS REQUIRED TO BE WORN TO AVOID ANY POTENTIALLY DANGEROUS EXPOSURE LEVELS.
10. NO FIRE, SMOKE, DUST OR ODOR WILL RESULT FROM THIS FACILITY AS TO CAUSE ANNUANCE.
11. THE FACILITY IS UNMANNED AND NOT FOR HUMAN HABITATION (NO HANDICAP ACCESS IS REQUIRED).

GENERAL NOTES

1. THESE MODIFICATIONS HAVE BEEN DESIGNED IN ACCORDANCE WITH THE GOVERNING PROVISIONS OF THE TELECOMMUNICATIONS INDUSTRY STANDARD (TIA-222-B) AND THE NATIONAL ELECTRICAL SAFETY CODE (NFPA 70E). THE CONTRACTOR SHALL CONFORM TO THE ABOVE MENTIONED CODES.
2. CONTRACTOR SHALL TAKE ALL PRECAUTIONS NECESSARY TO PREVENT DAMAGE TO EXISTING STRUCTURES, ANY DAMAGE TO EXISTING STRUCTURES AS A RESULT OF THE CONTRACTOR'S WORK OR FROM DAMAGE DUE TO OTHER CAUSES SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE TO THE SATISFACTION OF THE OWNER.
3. CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL PERMITS AND INSPECTIONS PRIOR TO COMMENCING ANY WORK. ALL DIMENSIONS OF EXISTING STRUCTURES SHALL BE VERIFIED BY THE CONTRACTOR PRIOR TO ORDERING MATERIAL OR PROCEEDING WITH CONSTRUCTION.
4. IT IS ASSUMED THAT ANY STRUCTURAL MODIFICATION WORK SPECIFIED ON THESE PLANS WILL BE ACCOMPLISHED BY KNOWLEDGEABLE WORKMEN WITH TOWER CONSTRUCTION EXPERIENCE.
5. THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK AND SHALL BE RESPONSIBLE FOR THE SAFETY OF ALL PERSONNEL AND THE PROTECTION OF ALL UTILITIES, SEQUENCES, AND PROCEDURES.
6. ALL CONSTRUCTION MEANS AND METHODS INCLUDING BUT NOT LIMITED TO, ERECTION PLANS, RIGGING PLANS, CLIMBING PLANS, AND RECLE PLANS SHALL BE THE RESPONSIBILITY OF THE GENERAL CONTRACTOR RESPONSIBLE FOR THE EXECUTION OF THE WORK. CONTRACTOR HERIN AND SHALL MEET ALL STANDARDS INCLUDING THE REQUIRED INVOLVEMENT OF A QUALIFIED ENGINEER FOR CLASS V CONSTRUCTION.
7. THE CONTRACTOR IS SOLELY RESPONSIBLE FOR INITIATING, MANAGING, AND COMPLETING ALL SAFETY PROGRAMS IN ACCORDANCE WITH APPLICABLE SAFETY CODES.
8. WORK SHALL ONLY BE PERFORMED DURING CALM DRY DAYS (WINDS LESS THAN 30 MPH). THE STRUCTURE SHOWN ON THE DRAWINGS IS STRUCTURALLY SOUND ONLY IN THE COMPLETED FORM. THE

CONTRACTOR RESPONSIBILITY FOR THE STRENGTH AND STABILITY OF THE STRUCTURE

1. CONTRACTOR SHALL BE RESPONSIBLE FOR THE STRENGTH AND STABILITY OF THE STRUCTURE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE DESIGN, FABRICATION, ERECTION AND MAINTENANCE OF THE STRUCTURE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE DESIGN, FABRICATION, ERECTION AND MAINTENANCE OF THE STRUCTURE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE DESIGN, FABRICATION, ERECTION AND MAINTENANCE OF THE STRUCTURE.
2. CONTRACTOR SHALL SECURE SITE BACK TO EXISTING CONDITION UNDER ALL CIRCUMSTANCES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE DESIGN, FABRICATION, ERECTION AND MAINTENANCE OF THE STRUCTURE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE DESIGN, FABRICATION, ERECTION AND MAINTENANCE OF THE STRUCTURE.
3. CONTRACTOR SHALL SECURE SITE BACK TO EXISTING CONDITION UNDER ALL CIRCUMSTANCES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE DESIGN, FABRICATION, ERECTION AND MAINTENANCE OF THE STRUCTURE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE DESIGN, FABRICATION, ERECTION AND MAINTENANCE OF THE STRUCTURE.
4. CONTRACTOR SHALL SECURE SITE BACK TO EXISTING CONDITION UNDER ALL CIRCUMSTANCES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE DESIGN, FABRICATION, ERECTION AND MAINTENANCE OF THE STRUCTURE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE DESIGN, FABRICATION, ERECTION AND MAINTENANCE OF THE STRUCTURE.
5. CONTRACTOR SHALL SECURE SITE BACK TO EXISTING CONDITION UNDER ALL CIRCUMSTANCES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE DESIGN, FABRICATION, ERECTION AND MAINTENANCE OF THE STRUCTURE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE DESIGN, FABRICATION, ERECTION AND MAINTENANCE OF THE STRUCTURE.
6. CONTRACTOR SHALL SECURE SITE BACK TO EXISTING CONDITION UNDER ALL CIRCUMSTANCES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE DESIGN, FABRICATION, ERECTION AND MAINTENANCE OF THE STRUCTURE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE DESIGN, FABRICATION, ERECTION AND MAINTENANCE OF THE STRUCTURE.
7. CONTRACTOR SHALL SECURE SITE BACK TO EXISTING CONDITION UNDER ALL CIRCUMSTANCES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE DESIGN, FABRICATION, ERECTION AND MAINTENANCE OF THE STRUCTURE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE DESIGN, FABRICATION, ERECTION AND MAINTENANCE OF THE STRUCTURE.
8. CONTRACTOR SHALL SECURE SITE BACK TO EXISTING CONDITION UNDER ALL CIRCUMSTANCES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE DESIGN, FABRICATION, ERECTION AND MAINTENANCE OF THE STRUCTURE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE DESIGN, FABRICATION, ERECTION AND MAINTENANCE OF THE STRUCTURE.
9. CONTRACTOR SHALL SECURE SITE BACK TO EXISTING CONDITION UNDER ALL CIRCUMSTANCES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE DESIGN, FABRICATION, ERECTION AND MAINTENANCE OF THE STRUCTURE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE DESIGN, FABRICATION, ERECTION AND MAINTENANCE OF THE STRUCTURE.
10. CONTRACTOR SHALL SECURE SITE BACK TO EXISTING CONDITION UNDER ALL CIRCUMSTANCES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE DESIGN, FABRICATION, ERECTION AND MAINTENANCE OF THE STRUCTURE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE DESIGN, FABRICATION, ERECTION AND MAINTENANCE OF THE STRUCTURE.
11. CONTRACTOR SHALL SECURE SITE BACK TO EXISTING CONDITION UNDER ALL CIRCUMSTANCES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE DESIGN, FABRICATION, ERECTION AND MAINTENANCE OF THE STRUCTURE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE DESIGN, FABRICATION, ERECTION AND MAINTENANCE OF THE STRUCTURE.
12. CONTRACTOR SHALL SECURE SITE BACK TO EXISTING CONDITION UNDER ALL CIRCUMSTANCES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE DESIGN, FABRICATION, ERECTION AND MAINTENANCE OF THE STRUCTURE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE DESIGN, FABRICATION, ERECTION AND MAINTENANCE OF THE STRUCTURE.
13. CONTRACTOR SHALL SECURE SITE BACK TO EXISTING CONDITION UNDER ALL CIRCUMSTANCES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE DESIGN, FABRICATION, ERECTION AND MAINTENANCE OF THE STRUCTURE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE DESIGN, FABRICATION, ERECTION AND MAINTENANCE OF THE STRUCTURE.
14. CONTRACTOR SHALL SECURE SITE BACK TO EXISTING CONDITION UNDER ALL CIRCUMSTANCES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE DESIGN, FABRICATION, ERECTION AND MAINTENANCE OF THE STRUCTURE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE DESIGN, FABRICATION, ERECTION AND MAINTENANCE OF THE STRUCTURE.
15. CONTRACTOR SHALL SECURE SITE BACK TO EXISTING CONDITION UNDER ALL CIRCUMSTANCES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE DESIGN, FABRICATION, ERECTION AND MAINTENANCE OF THE STRUCTURE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE DESIGN, FABRICATION, ERECTION AND MAINTENANCE OF THE STRUCTURE.


STRUCTURAL STEEL

1. DESIGN DETAILING, FABRICATION AND ERECTION OF STRUCTURAL STEEL SHALL CONFORM TO THE FOLLOWING PUBLICATIONS EXCEPT AS SPECIFICALLY INDICATED IN THE CONTRACT DOCUMENTS.
 - a. AMERICAN INSTITUTE OF STEEL CONSTRUCTION (AISC) MANUAL OF STEEL CONSTRUCTION (15TH EDITION)
 - b. SPECIFICATION FOR STRUCTURAL JOINTS USING ASTM A335 OR A490 BOLTS
 - c. AISC CODE OF STANDARD PRACTICE
 - d. AISC CODE OF STANDARD PRACTICE
 - e. LOCKING STRUCTURAL GRADE
2. CHANNELS, ANGLES, PLATES, ETC. ASTM A36 (GR. 36)
3. STEEL PIPE ASTM A53 (GR. 35)
4. BOLTS ASTM A325
5. NUTS ASTM A563
6. LOCK WASHERS LOCKING STRUCTURAL GRADE
7. ALL SUBSTITUTIONS PROPOSED BY THE CONTRACTOR SHALL BE APPROVED IN WRITING BY THE ENGINEER. CONTRACTOR SHALL PROVIDE DOCUMENTATION TO ENGINEER VERIFYING THE SUBSTITUTIONS FROM THE ORIGINAL DESIGNER'S ORIGINAL DESIGN CRITERIA. SUBSTITUTIONS FROM THE ORIGINAL DESIGNER'S ORIGINAL DESIGN CRITERIA SHALL BE APPROVED BY THE ENGINEER. CONTRACTOR SHALL PROVIDE DOCUMENTATION TO ENGINEER VERIFYING THE SUBSTITUTIONS FROM THE ORIGINAL DESIGNER'S ORIGINAL DESIGN CRITERIA. SUBSTITUTIONS FROM THE ORIGINAL DESIGNER'S ORIGINAL DESIGN CRITERIA SHALL BE APPROVED BY THE ENGINEER. CONTRACTOR SHALL PROVIDE DOCUMENTATION TO ENGINEER VERIFYING THE SUBSTITUTIONS FROM THE ORIGINAL DESIGNER'S ORIGINAL DESIGN CRITERIA.
8. WITH THE SUBSTITUTION (INCLUDING REDESIGN COSTS AND COSTS TO SUB-CONTRACTORS) SHALL BE PROVIDED TO THE ENGINEER. CONTRACTOR SHALL PROVIDE DOCUMENTATION AND/OR SPECIFICATIONS TO THE ENGINEER AS REQUESTED.
9. PROVIDE STRUCTURAL STEEL SHOP DRAWINGS TO ENGINEER FOR APPROVAL PRIOR TO FABRICATION.
 - a. SUBMIT SHOP DRAWINGS TO PETERALBANO@COLLIERENGINE.COM
 - b. PROVIDE MASTER CONSULTING CONNECTICUT PROJECT # AND MASTER CONSULTING CONNECTICUT PROJECT ENGINEER CONTACT IN THE BODY OF THE EMAIL.
10. DRILLING HOLES IN ANY NEW OR EXISTING STRUCTURAL STEEL MEMBERS OTHER THAN THOSE SHOWN ON STRUCTURAL DRAWINGS WITHOUT THE APPROVAL OF THE ENGINEER OF RECORD.
11. GALVANIZED ASTM A335 BOLTS SHALL NOT BE RELEASED.
12. ALL NEW STEEL SHALL BE HOT DIP GALVANIZED FOR FULL WEATHER PROTECTION. IN ADDITION ALL NEW STEEL SHALL BE PAINTED TO MATCH PROTECT STEEL BY ANY OTHER MEANS.
13. CONTRACTOR SHALL PROTECT CUT EDGE OF ALL DRILL-CUT STEEL WITH TWO (2) COATS OF COLD GALVANIZATION (ZINGAR OR ZINC COATS).
14. ALL BOLT ASSEMBLIES FOR STRUCTURAL MEMBERS REPRESENTED IN THE DRAWING REQUIRE LOCKING DEVICES TO BE INSTALLED IN ACCORDANCE WITH TIA-222-B SECTION 4.9.2 REQUIREMENTS.
15. WHERE CONNECTIONS ARE NOT FULLY DETAILED ON THESE DRAWINGS, FABRICATOR SHALL DESIGN CONNECTIONS TO RESIST LOADS AND FORCES WHERE SHOWN ON DRAWINGS AND AS OUTLINED IN SPECIFICATIONS. FOR MEMBERS BEING REPLACED, PROVIDE NEW BOLTS AND MATCH EXISTING SIZE AND GRADE. MAINTAIN AISC REQUIREMENTS FOR PLAIN END BOLT.


WELDING NOTES

1. ALL WELDING SHALL BE DONE IN ACCORDANCE WITH AWS D1.9 (LATEST EDITION). THIS SHALL INCLUDE CERTIFIED WELD INSPECTION (CWI) FOR ALL WELDING AND POST INSTALLATION USING THE ACCEPTANCE CRITERIA OF AWS D11. CONTRACTOR IS RESPONSIBLE FOR COMMISSIONING A THIRD PARTY CERTIFIED WELD INSPECTOR (CWI) THROUGHOUT THE ENTIRETY OF THE PROJECT. A PASSING CWI REPORT SHALL BE PROVIDED TO THE ENGINEER UPON COMPLETION OF THE PROJECT.
2. THE CERTIFIED WELD INSPECTOR SHALL INDICATE IN A WRITTEN CWI REPORT THE LOCATION OF ALL WELDS. ALL WELDS SHALL BE PHOTOGRAPHED AND DOCUMENTATION SUPPORTING THE ACCEPTANCE OR REJECTION OF ALL WELDING. ALL CWI WELD INSPECTION DOCUMENTATION AND PHOTOS SHALL BE SUBMITTED DURING THE PH. IN CASES WHERE A WELD IS SPACED BETWEEN TWO MEMBERS IN WHICH THE SIZE OF WELD ON THE MEMBER IS EQUAL TO THAT SHOWN IN THE DRAWINGS.
3. OXY FUEL GAS WELDING OR BRAZING IS STRICTLY PROHIBITED SPECIFICALLY. NO TORCH CUTTING IS PERMITTED ON SITE. ALL HOLES SHALL BE CUT WITH A GRINDER.
4. CONTRACTOR SHALL EXERCISE CAUTION WHEN WELDING A GALVANIZED SURFACE.
5. CONTRACTOR SHALL HAVE A FIRE PROTECTION PLAN IN PLACE THAT CONFORMS TO MASS 809 CMR, 809A29.1, AND LOCAL JURISDICTIONAL REQUIREMENTS.

ALLOWABLE COPING



TYP. BOLT ASSEMBLY



WORKABLE GAGES (IN.)

LEG	GAGE
4	2 1/2
3 1/2	2
3	1 3/4
2 1/2	1 3/8
2	1 1/8

BOLT SCHEDULE (IN.)

BOLT DIAMETER	STANDARD HOLE	SHORT SLOT	MIN. EDGE DISTANCE	SPACING
1/2	9/16	9/16 x 1 1/16	7/8	1 1/2
5/8	1 1/16	1 1/16 x 7/8	1 1/4	1 7/8
3/4	1 3/16	1 3/16 x 1	1 1/4	2 1/4
7/8	1 5/16	1 5/16 x 1 1/8	1 1/2	2 5/8
1	1 7/16	1 7/16 x 1 5/16	1 3/4	3

DETAILS AND SPACING

1. ALL PROPOSED AND/OR REPLACED BOLTS SHALL BE OF SUFFICIENT LENGTH SUCH THAT THE END OF THE BOLT IS AT LEAST FLUSH WITH THE FACE OF THE MEMBER AND TO BE BELOW THE FACE OF THE NUT AFTER TIGHTENING IS COMPLETED.
2. ALL EXISTING PAINTED GALVANIZED SURFACES DAMAGED DURING REPAIRS INCLUDING AREAS UNDER STRENGTHENING PLATES SHALL BE WIRE BRUSHED CLEAN, REPAIRED BY COLD GALVANIZING (ZINGAR OR ZINC COATS), AND REPAINTED TO MATCH THE EXISTING FINISH (IF APPLICABLE).
3. ALL HOLES IN STEEL MEMBERS SHALL BE SIZED 1/16" LARGER THAN THE BOLT DIAMETER. STANDARD HOLES SHALL BE USED UNLESS NOTED OTHERWISE.

NOTES

1. ALL DIMENSIONS REPRESENTED IN THE DRAWINGS SHALL BE IN UNLESS OTHERWISE NOTED.
2. THE DIMENSIONS PROVIDED ARE MINIMUM REQUIREMENTS. ACTUAL DIMENSIONS MAY VARY FROM THESE DRAWINGS WITHIN THE AISC MINIMUM REQUIREMENTS.
3. SHORT SLOT HOLES SHALL ONLY BE USED WHEN DEPICTED IN THE DRAWINGS.
4. MATCH EXISTING GAGES WHEN APPLICABLE UNLESS MINIMUM EDGE DISTANCES ARE COMPROMISED.

COLLIER ENGINEERING & DESIGN

105 Westport Ave. Westport, CT 06880
 860.439.1111
 www.colliereng.com


VERIZON

811
 FOR MORE INFORMATION VISIT
 www.811.com


MODIFICATION NOTES

SGN-1

NOTE: DO NOT SCALE DRAWINGS FOR CONSTRUCTION



2 PROPOSED WIRE ROPE GUIDE ATTACHMENT - PLAN VIEW
SCALE INT.S.



1 CLIMBING FACILITY LOCATION
SCALE INT.S.

- STRUCTURAL NOTES:
- PER THE MOUNT MAPPING COMPLETED BY STRUCTURAL COMPONENTS ON 10/19/2021, THE SAFETY CLIMB AND CLIMBING FACILITIES UP TO THE VERIZON MOUNT ELEVATION (159'-0") ARE IN GOOD CONDITION. MASER DOES NOT WARRANT THIS INFORMATION.
 - INSTALL SHALL NOT CAUSE HARM TO THE STRUCTURE, CLIMBING FACILITY, SAFETY CLIMB, OR ANY SYSTEM INSTALLED ON THE STRUCTURE. TIMELY NOTICE AND DOCUMENTATION SHALL BE PROVIDED BY CONTRACTORS TO THE EOR (OF STRUCTURAL DESIGN) IF AN OBSTRUCTION WAS REQUIRED TO MEET THE RF SYSTEM DESIGN REQUIREMENTS AND PERFORMANCES.



CLIMBING FACILITY PHOTO

LEGEND:


- PROPOSED
- RELOCATED
- EXISTING

MOUNT MODIFICATION SCHEDULE

NO.	ELEVATION	QUANTITY	DESCRIPTION	NOTES
1	139'-0"	1	PROPOSED TIERBACK ASSEMBLY (PART #: VZVSMART-SRK1)	CONNECT NEW TIE BACK TO EXISTING BOTTOM FACE HORIZONTAL. CONNECT OTHER END TO ADJACENT TOWER LEG. PROPOSED TIE-BACK SHALL EXTEND NO MORE THAN 12" BEYOND THE TOWER LEG. CONTRACTOR SHALL TRIM AS REQUIRED AND PROTECT CUT END WITH TWO COATS OF ZINGA OR ZINC COAT. (ALPHA SECTOR ONLY). SEE GENERAL NOTE A.
2		3	RELOCATED MOUNT PIPE	CONNECT RELOCATED MOUNT PIPE IN POSITION 3 TO EXISTING FACE HORIZONTALS WITH CROSSOVER PLATES (PART #: VZVSMART-MSK1) AT EACH CONNECTION.

GENERAL NOTES:

- A. THREADED ROD FROM PROPOSED KITS SHALL BE TRIMMED TO EXTEND NO MORE THAN 3" BEYOND THE LOCK NUT. TREAT ALL CUT ENDS WITH (2) COATS OF COLD GALVANIZATION (ZINGA OR ZINC COAT).
- B. REMOVE EXISTING TIE BACK AND ASSOCIATED CONNECTIONS (ALPHA SECTOR ONLY).
- C. MOUNT MEMBER NOT SHOWN FOR CLARITY UNO.



PROPOSED ISOMETRIC VIEW (ALPHA SECTOR SHOWN, SIMILAR ON BETA AND GAMMA SECTORS)

SCALE: N.T.S.

1

Collins Engineering & Design
www.collinseng.com



811
Call before you dig
for more information visit
www.811.com

NO.	DATE	DESCRIPTION
1	10/15/2014	ISSUED FOR PERMIT
2	10/15/2014	REVISED PER COMMENTS
3	10/15/2014	REVISED PER COMMENTS
4	10/15/2014	REVISED PER COMMENTS
5	10/15/2014	REVISED PER COMMENTS
6	10/15/2014	REVISED PER COMMENTS
7	10/15/2014	REVISED PER COMMENTS
8	10/15/2014	REVISED PER COMMENTS
9	10/15/2014	REVISED PER COMMENTS
10	10/15/2014	REVISED PER COMMENTS

COLLINS ENGINEERING & DESIGN, P.C.
100 WESTINGHOUSE BLVD
WESTPORT, CT 06880

IT IS A VIOLATION OF LAW FOR ANY PERSON, OTHER THAN THE REGISTERED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SITE NAME:
WESTPORT CT
5000104750
880 POST RD. EAST UNIT 1
WESTPORT, CT 06880
FAIRFIELD COUNTY

Collins Engineering & Design
100 Westinghouse Blvd
Westport, CT 06880
www.collinseng.com

MODIFICATION DETAILS
SS-1



MOUNT PHOTO 1



MOUNT PHOTO 2



MOUNT PHOTO 3



MOUNT PHOTO 4



www.colliersengineering.com

Colliers Engineering & Design is a registered professional engineering firm in the state of Connecticut. The firm is not responsible for the design of any structure or equipment shown on this drawing unless specifically stated otherwise on the drawing. The firm is not responsible for the design of any structure or equipment shown on this drawing unless specifically stated otherwise on the drawing.



811
Call Before You Dig
www.811.ct.gov

REGISTERED PROFESSIONAL ENGINEER
No. 10100
www.southern.com

NO.	DATE	DESCRIPTION	BY	CHK'D
1	10/18/14	ISSUED FOR PERMIT	AM	AM
2	10/18/14	ISSUED FOR PERMIT	AM	AM
3	10/18/14	ISSUED FOR PERMIT	AM	AM
4	10/18/14	ISSUED FOR PERMIT	AM	AM
5	10/18/14	ISSUED FOR PERMIT	AM	AM
6	10/18/14	ISSUED FOR PERMIT	AM	AM
7	10/18/14	ISSUED FOR PERMIT	AM	AM
8	10/18/14	ISSUED FOR PERMIT	AM	AM
9	10/18/14	ISSUED FOR PERMIT	AM	AM
10	10/18/14	ISSUED FOR PERMIT	AM	AM
11	10/18/14	ISSUED FOR PERMIT	AM	AM
12	10/18/14	ISSUED FOR PERMIT	AM	AM
13	10/18/14	ISSUED FOR PERMIT	AM	AM
14	10/18/14	ISSUED FOR PERMIT	AM	AM
15	10/18/14	ISSUED FOR PERMIT	AM	AM
16	10/18/14	ISSUED FOR PERMIT	AM	AM
17	10/18/14	ISSUED FOR PERMIT	AM	AM
18	10/18/14	ISSUED FOR PERMIT	AM	AM
19	10/18/14	ISSUED FOR PERMIT	AM	AM
20	10/18/14	ISSUED FOR PERMIT	AM	AM
21	10/18/14	ISSUED FOR PERMIT	AM	AM
22	10/18/14	ISSUED FOR PERMIT	AM	AM
23	10/18/14	ISSUED FOR PERMIT	AM	AM
24	10/18/14	ISSUED FOR PERMIT	AM	AM
25	10/18/14	ISSUED FOR PERMIT	AM	AM
26	10/18/14	ISSUED FOR PERMIT	AM	AM
27	10/18/14	ISSUED FOR PERMIT	AM	AM
28	10/18/14	ISSUED FOR PERMIT	AM	AM
29	10/18/14	ISSUED FOR PERMIT	AM	AM
30	10/18/14	ISSUED FOR PERMIT	AM	AM
31	10/18/14	ISSUED FOR PERMIT	AM	AM
32	10/18/14	ISSUED FOR PERMIT	AM	AM
33	10/18/14	ISSUED FOR PERMIT	AM	AM
34	10/18/14	ISSUED FOR PERMIT	AM	AM
35	10/18/14	ISSUED FOR PERMIT	AM	AM
36	10/18/14	ISSUED FOR PERMIT	AM	AM
37	10/18/14	ISSUED FOR PERMIT	AM	AM
38	10/18/14	ISSUED FOR PERMIT	AM	AM
39	10/18/14	ISSUED FOR PERMIT	AM	AM
40	10/18/14	ISSUED FOR PERMIT	AM	AM
41	10/18/14	ISSUED FOR PERMIT	AM	AM
42	10/18/14	ISSUED FOR PERMIT	AM	AM
43	10/18/14	ISSUED FOR PERMIT	AM	AM
44	10/18/14	ISSUED FOR PERMIT	AM	AM
45	10/18/14	ISSUED FOR PERMIT	AM	AM
46	10/18/14	ISSUED FOR PERMIT	AM	AM
47	10/18/14	ISSUED FOR PERMIT	AM	AM
48	10/18/14	ISSUED FOR PERMIT	AM	AM
49	10/18/14	ISSUED FOR PERMIT	AM	AM
50	10/18/14	ISSUED FOR PERMIT	AM	AM
51	10/18/14	ISSUED FOR PERMIT	AM	AM
52	10/18/14	ISSUED FOR PERMIT	AM	AM
53	10/18/14	ISSUED FOR PERMIT	AM	AM
54	10/18/14	ISSUED FOR PERMIT	AM	AM
55	10/18/14	ISSUED FOR PERMIT	AM	AM
56	10/18/14	ISSUED FOR PERMIT	AM	AM
57	10/18/14	ISSUED FOR PERMIT	AM	AM
58	10/18/14	ISSUED FOR PERMIT	AM	AM
59	10/18/14	ISSUED FOR PERMIT	AM	AM
60	10/18/14	ISSUED FOR PERMIT	AM	AM
61	10/18/14	ISSUED FOR PERMIT	AM	AM
62	10/18/14	ISSUED FOR PERMIT	AM	AM
63	10/18/14	ISSUED FOR PERMIT	AM	AM
64	10/18/14	ISSUED FOR PERMIT	AM	AM
65	10/18/14	ISSUED FOR PERMIT	AM	AM
66	10/18/14	ISSUED FOR PERMIT	AM	AM
67	10/18/14	ISSUED FOR PERMIT	AM	AM
68	10/18/14	ISSUED FOR PERMIT	AM	AM
69	10/18/14	ISSUED FOR PERMIT	AM	AM
70	10/18/14	ISSUED FOR PERMIT	AM	AM
71	10/18/14	ISSUED FOR PERMIT	AM	AM
72	10/18/14	ISSUED FOR PERMIT	AM	AM
73	10/18/14	ISSUED FOR PERMIT	AM	AM
74	10/18/14	ISSUED FOR PERMIT	AM	AM
75	10/18/14	ISSUED FOR PERMIT	AM	AM
76	10/18/14	ISSUED FOR PERMIT	AM	AM
77	10/18/14	ISSUED FOR PERMIT	AM	AM
78	10/18/14	ISSUED FOR PERMIT	AM	AM
79	10/18/14	ISSUED FOR PERMIT	AM	AM
80	10/18/14	ISSUED FOR PERMIT	AM	AM
81	10/18/14	ISSUED FOR PERMIT	AM	AM
82	10/18/14	ISSUED FOR PERMIT	AM	AM
83	10/18/14	ISSUED FOR PERMIT	AM	AM
84	10/18/14	ISSUED FOR PERMIT	AM	AM
85	10/18/14	ISSUED FOR PERMIT	AM	AM
86	10/18/14	ISSUED FOR PERMIT	AM	AM
87	10/18/14	ISSUED FOR PERMIT	AM	AM
88	10/18/14	ISSUED FOR PERMIT	AM	AM
89	10/18/14	ISSUED FOR PERMIT	AM	AM
90	10/18/14	ISSUED FOR PERMIT	AM	AM
91	10/18/14	ISSUED FOR PERMIT	AM	AM
92	10/18/14	ISSUED FOR PERMIT	AM	AM
93	10/18/14	ISSUED FOR PERMIT	AM	AM
94	10/18/14	ISSUED FOR PERMIT	AM	AM
95	10/18/14	ISSUED FOR PERMIT	AM	AM
96	10/18/14	ISSUED FOR PERMIT	AM	AM
97	10/18/14	ISSUED FOR PERMIT	AM	AM
98	10/18/14	ISSUED FOR PERMIT	AM	AM
99	10/18/14	ISSUED FOR PERMIT	AM	AM
100	10/18/14	ISSUED FOR PERMIT	AM	AM

PROJECT: 2111717A

COLLIERS ENGINEERING & DESIGN, P.C.
1000 WESTPORT ROAD
WESTPORT, CT 06880

IT IS A VIOLATION OF LAW FOR ANY PERSON TO REPRODUCE OR TRANSMIT THIS DRAWING OR ANY PART THEREOF WITHOUT THE WRITTEN PERMISSION OF COLLIERS ENGINEERING & DESIGN, P.C.

SITE NAME:
WESTPORT CT
500010/6750

880 POST RD. EAST UNIT 1
WESTPORT, CT 06880
FAIRFIELD COUNTY

3000 WESTPORT ROAD
WESTPORT, CT 06880
Phone: 203.337.8861
www.colliers.com
CONSULTANTS TO: COLLIERS ENGINEERING & DESIGN, P.C.

PROJECT: 2111717A
SHEET: 55-2

DATE: 10/18/14
BY: AM

DESCRIPTION: ISSUED FOR PERMIT

PROJECT: 2111717A

SHEET: 55-2



Observed Safety and Structural Issues During the Mount Mapping		
Issue #	Description of Issue	Photo #
1		
2		
3		
4		
5		
6		
7		
8		

Observed Obstructions to Tower Lighting System			
If the tower lighting system is being obstructed by the carrier's equipment (for example: a light nested by the antennas), please provide photos and fill in the information below.			
Description of Obstruction:			Photo #
Type of Light:	Photo #	Additional Comments:	
Lighting Technology:	Photo #		
Elevation (AGL) at base of light (FT.):	Photo #		
Is a service loop available?	Photo #		
Is beacon installed on an extension?	Photo #		

Mapping Notes
<ol style="list-style-type: none"> 1. Please report any visible structural or safety issues observed on the antenna mounts (Damaged members, loose connections, tilting mounts, safety climb issues, etc.) 2. If the thickness of the existing pipes or tubing can't be obtained from a general tool (such as Caliper), please use an ultrasonic measurement tool (thickness gauge) to measure the thickness. 3. Please create all required detail sketches of the mounts and insert them into the "Sketches" tab. 4. Please measure and enter the bolt sizes and types under the Members Box in the spreadsheet of the mount type. 5. Take and label the photos of the tower, mounts, connections, antennas and all measurements. Minimum 50 photos are required. 6. Please measure and report the size and length of all existing antenna mounting pipes. 7. Please measure and report the antenna information for all sectors. 8. Don't delete or rearrange any sheet or contents of any sheet from this mapping form.

Standard Conditions
<ol style="list-style-type: none"> 1. Obvious safety and structural issues/deficiencies noticed at the time of the mount mapping are to be reported in this mapping. However, this mount mapping is not a condition assessment of the mount.




Antenna Mount Mapping Form (PATENT PENDING)

FCC #



Tower Owner:	CSP	Mapping Date:	10/19/2021
Site Name:	WESTPORT_CT	Tower Type:	Self Support
Site Number or ID:	16242132	Tower Height (FT):	180
Mapping Contractor:	Structural Components	Mount Elevation (FT):	158

This antenna mapping form is the property of TES and under PATENT PENDING. The formation contained herein is considered confidential in nature and is to be used only for the specific customer it was intended for. Reproduction, transmission, publication, modification or disclosure by any method is prohibited except by express written permission of TES. All means and methods are the responsibility of the contractor and the work shall be compliant with ANSI/ASSE A 10.48, OSHA, FCC, FAA and other safety requirements that may apply. TES is not warranting the usability of the safety climb as it must be assessed prior to each use in compliance with OSHA requirements.

Please Insert Sketches of the Antenna Mount



Leg Attach: L4x3x3/8 x 5 1/2 LLV
 (2) 1/2" Ø UB, 1 3/4" clc
 41" clc





10/17/21

2001

Tc Back S			
Sector	From L	to tower	from R to tower
A		NA	$\sqrt{\quad}$ B
B	20'	leg A	NA
C	12'	leg B	NA

10/19/2021 15:57



Envelope Only Solution

Colliers Engineering & De...


Project # 21777772

Colliers Engineering & Design


SK - 1

Nov 20, 2023 at 11:39 AM

5000104750-VZW_MT_LOT_A_H...






Code Check (Env)	
Black	No Calc
Red	> 1.0
Orange	.90-1.0
Yellow	.75-.90
Light Green	.50-.75
Dark Green	0-.50



Member Code Checks Displayed (Enveloped)
Envelope Only Solution

Colliers Engineering & De...	Colliers Engineering & Design	SK - 2
Project # 21777772		Nov 20, 2023 at 11:40 AM
		5000104750-VZW_MT_LOT_A_H....



Member Shear Checks Displayed (Enveloped)
Envelope Only Solution

Colliers Engineering & De...

SK - 3

Colliers Engineering & Design

Nov 20, 2023 at 11:41 AM

Project # 21777772

5000104750-VZW_MT_LOT_A_H...



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 21777772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Basic Load Cases

	BLC Description	Category	X Gr...	Y Gr...	Z Gr...	Joint	Point	Distributed	Area(Member)	Surfa...
1	Antenna D	None					45			
2	Antenna Di	None					45			
3	Antenna Wo (0 Deg)	None					45			
4	Antenna Wo (30 Deg)	None					45			
5	Antenna Wo (60 Deg)	None					45			
6	Antenna Wo (90 Deg)	None					45			
7	Antenna Wo (120 Deg)	None					45			
8	Antenna Wo (150 Deg)	None					45			
9	Antenna Wo (180 Deg)	None					45			
10	Antenna Wo (210 Deg)	None					45			
11	Antenna Wo (240 Deg)	None					45			
12	Antenna Wo (270 Deg)	None					45			
13	Antenna Wo (300 Deg)	None					45			
14	Antenna Wo (330 Deg)	None					45			
15	Antenna Wi (0 Deg)	None					45			
16	Antenna Wi (30 Deg)	None					45			
17	Antenna Wi (60 Deg)	None					45			
18	Antenna Wi (90 Deg)	None					45			
19	Antenna Wi (120 Deg)	None					45			
20	Antenna Wi (150 Deg)	None					45			
21	Antenna Wi (180 Deg)	None					45			
22	Antenna Wi (210 Deg)	None					45			
23	Antenna Wi (240 Deg)	None					45			
24	Antenna Wi (270 Deg)	None					45			
25	Antenna Wi (300 Deg)	None					45			
26	Antenna Wi (330 Deg)	None					45			
27	Antenna Wm (0 Deg)	None					45			
28	Antenna Wm (30 Deg)	None					45			
29	Antenna Wm (60 Deg)	None					45			
30	Antenna Wm (90 Deg)	None					45			
31	Antenna Wm (120 Deg)	None					45			
32	Antenna Wm (150 Deg)	None					45			
33	Antenna Wm (180 Deg)	None					45			
34	Antenna Wm (210 Deg)	None					45			
35	Antenna Wm (240 Deg)	None					45			
36	Antenna Wm (270 Deg)	None					45			
37	Antenna Wm (300 Deg)	None					45			
38	Antenna Wm (330 Deg)	None					45			
39	Structure D	None		-1						
40	Structure Di	None						41		
41	Structure Wo (0 Deg)	None						82		
42	Structure Wo (30 Deg)	None						82		
43	Structure Wo (60 Deg)	None						82		
44	Structure Wo (90 Deg)	None						82		
45	Structure Wo (120 Deg)	None						82		
46	Structure Wo (150 Deg)	None						82		
47	Structure Wo (180 Deg)	None						82		
48	Structure Wo (210 Deg)	None						82		
49	Structure Wo (240 Deg)	None						82		
50	Structure Wo (270 Deg)	None						82		
51	Structure Wo (300 Deg)	None						82		
52	Structure Wo (330 Deg)	None						82		
53	Structure Wi (0 Deg)	None						82		
54	Structure Wi (30 Deg)	None						82		
55	Structure Wi (60 Deg)	None						82		
56	Structure Wi (90 Deg)	None						82		



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 21777772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Basic Load Cases (Continued)

BLC Description	Category	X Gr...	Y Gr...	Z Gr...	Joint	Point	Distributed	Area(Member)	Surfa...
57 Structure Wi (120 Deg)	None						82		
58 Structure Wi (150 Deg)	None						82		
59 Structure Wi (180 Deg)	None						82		
60 Structure Wi (210 Deg)	None						82		
61 Structure Wi (240 Deg)	None						82		
62 Structure Wi (270 Deg)	None						82		
63 Structure Wi (300 Deg)	None						82		
64 Structure Wi (330 Deg)	None						82		
65 Structure Wm (0 Deg)	None						82		
66 Structure Wm (30 Deg)	None						82		
67 Structure Wm (60 Deg)	None						82		
68 Structure Wm (90 Deg)	None						82		
69 Structure Wm (120 Deg)	None						82		
70 Structure Wm (150 Deg)	None						82		
71 Structure Wm (180 Deg)	None						82		
72 Structure Wm (210 Deg)	None						82		
73 Structure Wm (240 Deg)	None						82		
74 Structure Wm (270 Deg)	None						82		
75 Structure Wm (300 Deg)	None						82		
76 Structure Wm (330 Deg)	None						82		
77 Lm1	None					1			
78 Lm2	None					1			
79 Lv1	None					1			
80 Lv2	None					1			
81 Antenna Ev	None					45			
82 Antenna Eh (0 Deg)	None					30			
83 Antenna Eh (90 Deg)	None					30			
84 Structure Ev	ELY			-0495					
85 Structure Eh (0 Deg)	ELZ								
86 Structure Eh (90 Deg)	ELX			.1237					

Load Combinations

Description	S...	PDel...	SR...	BLC	Fa...	BLC	Fa...	BLC	Fa...	B...	Fa...	B...	Fa...	B...	Fa...	BLC	Fa...	B...	Fa...	B...	Fa...	B...	Fa...
1 1.2D+1.0Wo (0 Deg) Yes	Y			1	1.2	39	1.2	3	1	41	1												
2 1.2D+1.0Wo (30 Deg) Yes	Y			1	1.2	39	1.2	4	1	42	1												
3 1.2D+1.0Wo (60 Deg) Yes	Y			1	1.2	39	1.2	5	1	43	1												
4 1.2D+1.0Wo (90 Deg) Yes	Y			1	1.2	39	1.2	6	1	44	1												
5 1.2D+1.0Wo (120 De... Yes	Y			1	1.2	39	1.2	7	1	45	1												
6 1.2D+1.0Wo (150 De... Yes	Y			1	1.2	39	1.2	8	1	46	1												
7 1.2D+1.0Wo (180 De... Yes	Y			1	1.2	39	1.2	9	1	47	1												
8 1.2D+1.0Wo (210 De... Yes	Y			1	1.2	39	1.2	10	1	48	1												
9 1.2D+1.0Wo (240 De... Yes	Y			1	1.2	39	1.2	11	1	49	1												
10 1.2D+1.0Wo (270 De... Yes	Y			1	1.2	39	1.2	12	1	50	1												
11 1.2D+1.0Wo (300 De... Yes	Y			1	1.2	39	1.2	13	1	51	1												
12 1.2D+1.0Wo (330 De... Yes	Y			1	1.2	39	1.2	14	1	52	1												
13 1.2D + 1.0Di + 1.0Wi... Yes	Y			1	1.2	39	1.2	2	1	40	1	15	1	53	1								
14 1.2D + 1.0Di + 1.0Wi... Yes	Y			1	1.2	39	1.2	2	1	40	1	16	1	54	1								
15 1.2D + 1.0Di + 1.0Wi... Yes	Y			1	1.2	39	1.2	2	1	40	1	17	1	55	1								
16 1.2D + 1.0Di + 1.0Wi... Yes	Y			1	1.2	39	1.2	2	1	40	1	18	1	56	1								
17 1.2D + 1.0Di + 1.0Wi... Yes	Y			1	1.2	39	1.2	2	1	40	1	19	1	57	1								
18 1.2D + 1.0Di + 1.0Wi... Yes	Y			1	1.2	39	1.2	2	1	40	1	20	1	58	1								
19 1.2D + 1.0Di + 1.0Wi... Yes	Y			1	1.2	39	1.2	2	1	40	1	21	1	59	1								
20 1.2D + 1.0Di + 1.0Wi... Yes	Y			1	1.2	39	1.2	2	1	40	1	22	1	60	1								
21 1.2D + 1.0Di + 1.0Wi... Yes	Y			1	1.2	39	1.2	2	1	40	1	23	1	61	1								
22 1.2D + 1.0Di + 1.0Wi... Yes	Y			1	1.2	39	1.2	2	1	40	1	24	1	62	1								



Load Combinations (Continued)

Description	S...	PDel...	SR...	BLC	Fa...	BLC	Fa...	BLC	Fa...	B...	Fa...	B...	Fa...	B...	Fa...	BLC	Fa...	B...	Fa...	B...	Fa...	B...	Fa...
23	1.2D + 1.0Di + 1.0Wi...	Yes	Y		1	1.2	39	1.2	2	1	40	1	25	1	63	1							
24	1.2D + 1.0Di + 1.0Wi...	Yes	Y		1	1.2	39	1.2	2	1	40	1	26	1	64	1							
25	1.2D + 1.5Lm1 + 1.0...	Yes	Y		1	1.2	39	1.2	77	1.5	27	1	65	1									
26	1.2D + 1.5Lm1 + 1.0...	Yes	Y		1	1.2	39	1.2	77	1.5	28	1	66	1									
27	1.2D + 1.5Lm1 + 1.0...	Yes	Y		1	1.2	39	1.2	77	1.5	29	1	67	1									
28	1.2D + 1.5Lm1 + 1.0...	Yes	Y		1	1.2	39	1.2	77	1.5	30	1	68	1									
29	1.2D + 1.5Lm1 + 1.0...	Yes	Y		1	1.2	39	1.2	77	1.5	31	1	69	1									
30	1.2D + 1.5Lm1 + 1.0...	Yes	Y		1	1.2	39	1.2	77	1.5	32	1	70	1									
31	1.2D + 1.5Lm1 + 1.0...	Yes	Y		1	1.2	39	1.2	77	1.5	33	1	71	1									
32	1.2D + 1.5Lm1 + 1.0...	Yes	Y		1	1.2	39	1.2	77	1.5	34	1	72	1									
33	1.2D + 1.5Lm1 + 1.0...	Yes	Y		1	1.2	39	1.2	77	1.5	35	1	73	1									
34	1.2D + 1.5Lm1 + 1.0...	Yes	Y		1	1.2	39	1.2	77	1.5	36	1	74	1									
35	1.2D + 1.5Lm1 + 1.0...	Yes	Y		1	1.2	39	1.2	77	1.5	37	1	75	1									
36	1.2D + 1.5Lm1 + 1.0...	Yes	Y		1	1.2	39	1.2	77	1.5	38	1	76	1									
37	1.2D + 1.5Lm2 + 1.0...	Yes	Y		1	1.2	39	1.2	78	1.5	27	1	65	1									
38	1.2D + 1.5Lm2 + 1.0...	Yes	Y		1	1.2	39	1.2	78	1.5	28	1	66	1									
39	1.2D + 1.5Lm2 + 1.0...	Yes	Y		1	1.2	39	1.2	78	1.5	29	1	67	1									
40	1.2D + 1.5Lm2 + 1.0...	Yes	Y		1	1.2	39	1.2	78	1.5	30	1	68	1									
41	1.2D + 1.5Lm2 + 1.0...	Yes	Y		1	1.2	39	1.2	78	1.5	31	1	69	1									
42	1.2D + 1.5Lm2 + 1.0...	Yes	Y		1	1.2	39	1.2	78	1.5	32	1	70	1									
43	1.2D + 1.5Lm2 + 1.0...	Yes	Y		1	1.2	39	1.2	78	1.5	33	1	71	1									
44	1.2D + 1.5Lm2 + 1.0...	Yes	Y		1	1.2	39	1.2	78	1.5	34	1	72	1									
45	1.2D + 1.5Lm2 + 1.0...	Yes	Y		1	1.2	39	1.2	78	1.5	35	1	73	1									
46	1.2D + 1.5Lm2 + 1.0...	Yes	Y		1	1.2	39	1.2	78	1.5	36	1	74	1									
47	1.2D + 1.5Lm2 + 1.0...	Yes	Y		1	1.2	39	1.2	78	1.5	37	1	75	1									
48	1.2D + 1.5Lm2 + 1.0...	Yes	Y		1	1.2	39	1.2	78	1.5	38	1	76	1									
49	1.2D + 1.5Lv1	Yes	Y		1	1.2	39	1.2	79	1.5													
50	1.2D + 1.5Lv2	Yes	Y		1	1.2	39	1.2	80	1.5													
51	1.4D	Yes	Y		1	1.4	39	1.4															
52	1.2D + 1.0Ev + 1.0E...	Yes	Y		1	1.2	39	1.2	81	1	E...	1	82	1	83	ELZ	1	E...					
53	1.2D + 1.0Ev + 1.0E...	Yes	Y		1	1.2	39	1.2	81	1	E...	1	82	.866	83	.5	ELZ	.866	E...	.5			
54	1.2D + 1.0Ev + 1.0E...	Yes	Y		1	1.2	39	1.2	81	1	E...	1	82	.5	83	.866	ELZ	.5	E...	.866			
55	1.2D + 1.0Ev + 1.0E...	Yes	Y		1	1.2	39	1.2	81	1	E...	1	82		83	1	ELZ		E...	1			
56	1.2D + 1.0Ev + 1.0E...	Yes	Y		1	1.2	39	1.2	81	1	E...	1	82	-.5	83	.866	ELZ	-.5	E...	.866			
57	1.2D + 1.0Ev + 1.0E...	Yes	Y		1	1.2	39	1.2	81	1	E...	1	82	-.8...	83	.5	ELZ	-.8...	E...	.5			
58	1.2D + 1.0Ev + 1.0E...	Yes	Y		1	1.2	39	1.2	81	1	E...	1	82	-1	83		ELZ	-1	E...				
59	1.2D + 1.0Ev + 1.0E...	Yes	Y		1	1.2	39	1.2	81	1	E...	1	82	-.8...	83	-.5	ELZ	-.8...	E...	-.5			
60	1.2D + 1.0Ev + 1.0E...	Yes	Y		1	1.2	39	1.2	81	1	E...	1	82	-.5	83	-.8...	ELZ	-.5	E...	-.8...			
61	1.2D + 1.0Ev + 1.0E...	Yes	Y		1	1.2	39	1.2	81	1	E...	1	82		83	-1	ELZ		E...	-1			
62	1.2D + 1.0Ev + 1.0E...	Yes	Y		1	1.2	39	1.2	81	1	E...	1	82	.5	83	-.8...	ELZ	.5	E...	-.8...			
63	1.2D + 1.0Ev + 1.0E...	Yes	Y		1	1.2	39	1.2	81	1	E...	1	82	.866	83	-.5	ELZ	.866	E...	-.5			
64	0.9D - 1.0Ev + 1.0Eh...	Yes	Y		1	.9	39	.9	81	-1	E...	-1	82	1	83	ELZ	1	E...					
65	0.9D - 1.0Ev + 1.0Eh...	Yes	Y		1	.9	39	.9	81	-1	E...	-1	82	.866	83	.5	ELZ	.866	E...	.5			
66	0.9D - 1.0Ev + 1.0Eh...	Yes	Y		1	.9	39	.9	81	-1	E...	-1	82	.5	83	.866	ELZ	.5	E...	.866			
67	0.9D - 1.0Ev + 1.0Eh...	Yes	Y		1	.9	39	.9	81	-1	E...	-1	82		83	1	ELZ		E...	1			
68	0.9D - 1.0Ev + 1.0Eh...	Yes	Y		1	.9	39	.9	81	-1	E...	-1	82	-.5	83	.866	ELZ	-.5	E...	.866			
69	0.9D - 1.0Ev + 1.0Eh...	Yes	Y		1	.9	39	.9	81	-1	E...	-1	82	-.8...	83	.5	ELZ	-.8...	E...	.5			
70	0.9D - 1.0Ev + 1.0Eh...	Yes	Y		1	.9	39	.9	81	-1	E...	-1	82	-1	83		ELZ	-1	E...				
71	0.9D - 1.0Ev + 1.0Eh...	Yes	Y		1	.9	39	.9	81	-1	E...	-1	82	-.8...	83	-.5	ELZ	-.8...	E...	-.5			
72	0.9D - 1.0Ev + 1.0Eh...	Yes	Y		1	.9	39	.9	81	-1	E...	-1	82	-.5	83	-.8...	ELZ	-.5	E...	-.8...			
73	0.9D - 1.0Ev + 1.0Eh...	Yes	Y		1	.9	39	.9	81	-1	E...	-1	82		83	-1	ELZ		E...	-1			
74	0.9D - 1.0Ev + 1.0Eh...	Yes	Y		1	.9	39	.9	81	-1	E...	-1	82	.5	83	-.8...	ELZ	.5	E...	-.8...			
75	0.9D - 1.0Ev + 1.0Eh...	Yes	Y		1	.9	39	.9	81	-1	E...	-1	82	.866	83	-.5	ELZ	.866	E...	-.5			



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 2177772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Joint Coordinates and Temperatures

	Label	X [ft]	Y [ft]	Z [ft]	Temp [F]	Detach From Diap...
1	N1	-0.166667	0	0.166667	0	
2	N2	-0.447917	0	0.166667	0	
3	N3	0.114583	0	0.166667	0	
4	N4	-0.166667	0	0	0	
5	N5	-0.209803	-3.416667	0.160988	0	
6	N6	-0.447917	-3.416667	0.166667	0	
7	N7	0.114583	-3.416667	0.166667	0	
8	N10	-4.5	0	4.583333	0	
9	N11	4.166667	0	4.583333	0	
10	N11A	-7.666667	0	4.583333	0	
11	N12	7.333333	0	4.583333	0	
12	N14	-4.5	-3.416667	4.583333	0	
13	N15	4.166667	-3.416667	4.583333	0	
14	N16	-7.666667	-3.416667	4.583333	0	
15	N17	7.333333	-3.416667	4.583333	0	
16	N17A	-0.341752	0	0.345119	0	
17	N18	0.008419	0	0.345119	0	
18	N19	-0.341752	-3.416667	0.345119	0	
19	N20	0.008419	-3.416667	0.345119	0	
20	N21	0.38777	0	0.731765	0	
21	N22	0.38777	-3.416667	0.731765	0	
22	N23	2.08026	0	2.456803	0	
23	N24	2.08026	-3.416667	2.456803	0	
24	N25	3.77275	0	4.181841	0	
25	N26	3.77275	-3.416667	4.181841	0	
26	N27	0.38777	-3.291667	0.731765	0	
27	N28	2.08026	-3.291667	2.456803	0	
28	N29	0.38777	-.125	0.731765	0	
29	N30	2.08026	-.125	2.456803	0	
30	N31	3.77275	-2.916667	4.181841	0	
31	N32	3.77275	-.5	4.181841	0	
32	N33	-0.721103	0	0.731765	0	
33	N34	-0.721103	-3.416667	0.731765	0	
34	N35	-2.413593	0	2.456803	0	
35	N36	-2.413593	-3.416667	2.456803	0	
36	N37	-4.106083	0	4.181841	0	
37	N38	-4.106083	-3.416667	4.181841	0	
38	N39	-0.721103	-3.291667	0.731765	0	
39	N40	-2.413593	-3.291667	2.456803	0	
40	N41	-0.721103	-.125	0.731765	0	
41	N42	-2.413593	-.125	2.456803	0	
42	N43	-4.106083	-2.916667	4.181841	0	
43	N44	-4.106083	-.5	4.181841	0	
44	N45	-7.083333	0	4.583333	0	
45	N46	-7.083333	-3.416667	4.583333	0	
46	N47	-7.083333	0	4.833333	0	
47	N48	-7.083333	-3.416667	4.833333	0	
48	N49	-7.083333	1.25	4.833333	0	
49	N50	-7.083333	-4.75	4.833333	0	
50	N51	-3.375	0	4.583333	0	
51	N52	-3.375	-3.416667	4.583333	0	
52	N53	-3.375	0	4.833333	0	
53	N54	-3.375	-3.416667	4.833333	0	
54	N55	-3.375	1.25	4.833333	0	
55	N56	-3.375	-4.75	4.833333	0	
56	N57	-0.833333	0	4.583333	0	



Joint Coordinates and Temperatures (Continued)

	Label	X [ft]	Y [ft]	Z [ft]	Temp [F]	Detach From Diap...
57	N58	-0.833333	-3.416667	4.583333	0	
58	N59	-0.833333	0	4.833333	0	
59	N60	-0.833333	-3.416667	4.833333	0	
60	N61	-0.833333	1.25	4.833333	0	
61	N62	-0.833333	-4.75	4.833333	0	
62	N65	-0.166667	-3.416667	0	0	
63	N65A	6.75	0	4.583333	0	
64	N66	6.75	-3.416667	4.583333	0	
65	N67	6.75	0	4.833333	0	
66	N68	6.75	-3.416667	4.833333	0	
67	N69	6.75	1.25	4.833333	0	
68	N70	6.75	-4.75	4.833333	0	
69	N71	8.550037	-3.416667	-0.762613	0	
70	N80	1.671718	0	2.040405	0	
71	N81	1.87963	0	2.252315	0	
72	N98	1.671718	-3.416667	2.040405	0	
73	N99	1.87963	-3.416667	2.252315	0	
74	N77	1.494941	0	2.217181	0	
75	N78	1.702853	0	2.429092	0	
76	N79	1.494941	-3.416667	2.217181	0	
77	N80A	1.702853	-3.416667	2.429092	0	
78	N81A	1.494941	-3.666667	2.217181	0	
79	N82	1.702853	-3.666667	2.429092	0	
80	N83	1.494941	.25	2.217181	0	
81	N84	1.702853	.25	2.429092	0	
82	N85	1.494941	-1.708333	2.217181	0	
83	N86	1.702853	-1.708333	2.429092	0	
84	N85A	5.5	-3.416667	4.583333	0	

Hot Rolled Steel Section Sets

	Label	Shape	Type	Design List	Material	Desig... A [in2]	Iyy [i... lzz [i... J [in4]
1	Mount Pipe	PIPE 2.0	Column	Pipe	A53 Gr. B	Typical 1.02	.627 .627 1.25
2	Standoff Horizontal	PIPE 2.0	Beam	Pipe	A53 Gr. B	Typical 1.02	.627 .627 1.25
3	Standoff Vertical	PIPE 2.0	Beam	Pipe	A53 Gr. B	Typical 1.02	.627 .627 1.25
4	Standoff Diagonal	1.5 w 0.06 th	Beam	Pipe	A53 Gr. B	Typical .271	.07 .07 .141
5	TES Standoff Diagonal	PIPE 1.5	Beam	Pipe	A53 Gr. B	Typical .749	.293 .293 .586
6	Face Horizontal	PIPE 2.5	Beam	Pipe	A53 Gr. B	Typical 1.61	1.45 1.45 2.89
7	Mod Tieback	PIPE 2.0	Beam	Pipe	A53 Gr. B	Typical 1.02	.627 .627 1.25
8	Standoff Bar	PL3/8x3	Beam	RECT	A36 Gr.36	Typical 1.125	.013 .844 .049
9	Mount Angle	L4X3X6	Beam	Single Angle	A36 Gr.36	Typical 2.49	1.89 3.94 .123

Cold Formed Steel Section Sets

	Label	Shape	Type	Design ...	Material	Design ... A [in2]	Iyy [in4]	Izz [in4]	J [in4]
1	Unistrut	P1000	Column	CS	A570 Gr.33	Typical .497	.1373	.213	.002

Hot Rolled Steel Properties

	Label	E [ksj]	G [ksj]	Nu	Therm (/...	Density[k/ft^3]	Yield[ksj]	Ry	Fu[ksj]	Rt
1	A36 Gr.36	29000	11154	.3	.65	.49	36	1.5	58	1.2
2	A53 Gr. B	29000	11154	.3	.65	.49	35	1.5	60	1.2
3	A572 Gr.50	29000	11154	.3	.65	.49	50	1.1	65	1.1
4	A992	29000	11154	.3	.65	.49	50	1.1	65	1.1
5	A500 Gr. B 42	29000	11154	.3	.65	.49	42	1.4	58	1.3



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 21777772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Hot Rolled Steel Properties (Continued)

	Label	E [ksi]	G [ksi]	Nu	Therm (/...	Density[k/ft^3]	Yield[ksi]	Rv	Fu[ksi]	Rt
6	A500 Gr. B 46	29000	11154	.3	.65	.49	46	1.4	58	1.3

Cold Formed Steel Properties

	Label	E [ksi]	G [ksi]	Nu	Therm (/1E5 F)	Density[k/ft^3]	Yield[ksi]	Fu[ksi]
1	A570 Gr.33	29500	11346	.3	.65	.49	33	52
2	A607 C1 Gr.55	29500	11346	.3	.65	.49	55	70

Member Primary Data

	Label	I Joint	J Joint	K Joint	Rotate(d...	Section/Shape	Type	Design List	Material	Design Ru...
1	M1	N2	N3		90	Mount Angle	Beam	Single Angle	A36 Gr.36	Typical
2	M2	N1	N4			RIGID	None	None	RIGID	Typical
3	M3	N6	N7		90	Mount Angle	Beam	Single Angle	A36 Gr.36	Typical
4	M5	N1	N17A		90	Standoff Bar	Beam	RECT	A36 Gr.36	Typical
5	M6	N1	N18		90	Standoff Bar	Beam	RECT	A36 Gr.36	Typical
6	M7	N11A	N12			Face Horizontal	Beam	Pipe	A53 Gr. B	Typical
7	M8	N5	N19		90	Standoff Bar	Beam	RECT	A36 Gr.36	Typical
8	M9	N5	N20		90	Standoff Bar	Beam	RECT	A36 Gr.36	Typical
9	M10	N16	N17			Face Horizontal	Beam	Pipe	A53 Gr. B	Typical
10	M11	N17A	N10			Standoff Horizontal	Beam	Pipe	A53 Gr. B	Typical
11	M12	N18	N11			Standoff Horizontal	Beam	Pipe	A53 Gr. B	Typical
12	M13	N19	N14			Standoff Horizontal	Beam	Pipe	A53 Gr. B	Typical
13	M14	N20	N15			Standoff Horizontal	Beam	Pipe	A53 Gr. B	Typical
14	M15	N21	N29	N1		Standoff Bar	Beam	RECT	A36 Gr.36	Typical
15	M16	N21	N24		90	Standoff Diagonal	Beam	Pipe	A53 Gr. B	Typical
16	M17	N23	N30	N1		Standoff Bar	Beam	RECT	A36 Gr.36	Typical
17	M18	N23	N26		90	Standoff Diagonal	Beam	Pipe	A53 Gr. B	Typical
18	M19	N26	N31	N1		Standoff Bar	Beam	RECT	A36 Gr.36	Typical
19	M20	N27	N22	N1		Standoff Bar	Beam	RECT	A36 Gr.36	Typical
20	M21	N28	N24	N1		Standoff Bar	Beam	RECT	A36 Gr.36	Typical
21	M22	N29	N27	N1		Standoff Diagonal	Beam	Pipe	A53 Gr. B	Typical
22	M23	N30	N28	N1		Standoff Diagonal	Beam	Pipe	A53 Gr. B	Typical
23	M24	N31	N32	N1		Standoff Vertical	Beam	Pipe	A53 Gr. B	Typical
24	M25	N32	N25	N1		Standoff Bar	Beam	RECT	A36 Gr.36	Typical
25	M26	N33	N41	N1		Standoff Bar	Beam	RECT	A36 Gr.36	Typical
26	M27	N33	N36		90	Standoff Diagonal	Beam	Pipe	A53 Gr. B	Typical
27	M28	N35	N42	N1		Standoff Bar	Beam	RECT	A36 Gr.36	Typical
28	M29	N35	N38		90	Standoff Diagonal	Beam	Pipe	A53 Gr. B	Typical
29	M30	N38	N43	N1		Standoff Bar	Beam	RECT	A36 Gr.36	Typical
30	M31	N39	N34	N1		Standoff Bar	Beam	RECT	A36 Gr.36	Typical
31	M32	N40	N36	N1		Standoff Bar	Beam	RECT	A36 Gr.36	Typical
32	M33	N41	N39	N1		Standoff Diagonal	Beam	Pipe	A53 Gr. B	Typical
33	M34	N42	N40	N1		Standoff Diagonal	Beam	Pipe	A53 Gr. B	Typical
34	M35	N43	N44	N1		Standoff Vertical	Beam	Pipe	A53 Gr. B	Typical
35	M36	N44	N37	N1		Standoff Bar	Beam	RECT	A36 Gr.36	Typical
36	M37	N45	N47			RIGID	None	None	RIGID	Typical
37	M38	N46	N48			RIGID	None	None	RIGID	Typical
38	MP4A	N49	N50			Mount Pipe	Column	Pipe	A53 Gr. B	Typical
39	M40	N51	N53			RIGID	None	None	RIGID	Typical
40	M41	N52	N54			RIGID	None	None	RIGID	Typical
41	MP3A	N55	N56			Mount Pipe	Column	Pipe	A53 Gr. B	Typical
42	M43	N57	N59			RIGID	None	None	RIGID	Typical
43	M44	N58	N60			RIGID	None	None	RIGID	Typical
44	MP2A	N61	N62			Mount Pipe	Column	Pipe	A53 Gr. B	Typical
45	M46A	N5	N65			RIGID	None	None	RIGID	Typical



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 2177772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Primary Data (Continued)

	Label	I Joint	J Joint	K Joint	Rotate(d...	Section/Shape	Type	Design List	Material	Design Ru...
46	M47	N65A	N67			RIGID	None	None	RIGID	Typical
47	M48	N66	N68			RIGID	None	None	RIGID	Typical
48	MP1A	N69	N70			Mount Pipe	Column	Pipe	A53 Gr. B	Typical
49	EQUIP	N83	N81A		50	Unistrut	Column	CS	A570 Gr...	Typical
50	M51	N84	N82		50	Unistrut	Column	CS	A570 Gr...	Typical
51	M52	N98	N79			RIGID	None	None	RIGID	Typical
52	M53	N99	N80A			RIGID	None	None	RIGID	Typical
53	M54	N81	N78			RIGID	None	None	RIGID	Typical
54	M55	N80	N77			RIGID	None	None	RIGID	Typical
55	M55A	N85A	N71			Mod Tieback	Beam	Pipe	A53 Gr. B	Typical
56	OVP	N85	N86			RIGID	None	None	RIGID	Typical

Member Advanced Data

	Label	I Release	J Release	I Offset[in]	J Offset[in]	T/C Only	Physical	Defl Ratio Opti...	Analysis ...	Inactive	Seismi...
1	M1						Yes				None
2	M2						Yes	** NA **			None
3	M3						Yes				None
4	M5						Yes	Default			None
5	M6						Yes	Default			None
6	M7						Yes				None
7	M8						Yes	Default			None
8	M9						Yes	Default			None
9	M10						Yes				None
10	M11						Yes				None
11	M12						Yes				None
12	M13						Yes				None
13	M14						Yes				None
14	M15	00000X					Yes				None
15	M16	BenPIN	BenPIN				Yes	Default			None
16	M17	00000X					Yes				None
17	M18	BenPIN	BenPIN				Yes	Default			None
18	M19	00000X					Yes				None
19	M20		000000				Yes				None
20	M21		000000				Yes				None
21	M22						Yes				None
22	M23						Yes				None
23	M24						Yes				None
24	M25		000000				Yes	Default			None
25	M26	00000X					Yes				None
26	M27	BenPIN	BenPIN				Yes				None
27	M28	00000X					Yes				None
28	M29	BenPIN	BenPIN				Yes				None
29	M30	00000X					Yes				None
30	M31		000000				Yes				None
31	M32		000000				Yes				None
32	M33						Yes				None
33	M34						Yes				None
34	M35						Yes				None
35	M36		000000				Yes				None
36	M37						Yes	** NA **			None
37	M38						Yes	** NA **			None
38	MP4A						Yes	** NA **			None
39	M40						Yes	** NA **			None
40	M41						Yes	** NA **			None
41	MP3A						Yes	** NA **			None



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 2177772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Advanced Data (Continued)

	Label	I Release	J Release	I Offset[in]	J Offset[in]	T/C Only	Physical	Defl Ratio	Opti...	Analysis ...	Inactive	Seismi...
42	M43						Yes	** NA **				None
43	M44						Yes	** NA **				None
44	MP2A						Yes	** NA **				None
45	M46A						Yes	** NA **				None
46	M47						Yes	** NA **				None
47	M48						Yes	** NA **				None
48	MP1A						Yes	** NA **				None
49	EQUIP						Yes	** NA **				None
50	M51						Yes	** NA **				None
51	M52		000X00				Yes	** NA **				None
52	M53		000X00				Yes	** NA **				None
53	M54		000X00				Yes	** NA **				None
54	M55		000X00				Yes	** NA **				None
55	M55A	BenPIN					Yes	Default				None
56	OVP						Yes	** NA **				None

Member Point Loads (BLC 1 : Antenna D)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft,%]
1	MP1A	Y	-43.5	.5
2	MP1A	My	-.0464	.5
3	MP1A	Mz	-.0224	.5
4	MP1A	Y	-43.5	3.5
5	MP1A	My	-.0464	3.5
6	MP1A	Mz	-.0224	3.5
7	MP1A	Y	-43.5	.5
8	MP1A	My	-.0127	.5
9	MP1A	Mz	.0499	.5
10	MP1A	Y	-43.5	3.5
11	MP1A	My	-.0127	3.5
12	MP1A	Mz	.0499	3.5
13	MP4A	Y	-43.5	.5
14	MP4A	My	-.0127	.5
15	MP4A	Mz	-.0499	.5
16	MP4A	Y	-43.5	3.5
17	MP4A	My	-.0127	3.5
18	MP4A	Mz	-.0499	3.5
19	MP4A	Y	-43.5	.5
20	MP4A	My	-.0464	.5
21	MP4A	Mz	.0224	.5
22	MP4A	Y	-43.5	3.5
23	MP4A	My	-.0464	3.5
24	MP4A	Mz	.0224	3.5
25	MP2A	Y	-28.65	.25
26	MP2A	My	-.0143	.25
27	MP2A	Mz	0	.25
28	MP2A	Y	-28.65	1.25
29	MP2A	My	-.0143	1.25
30	MP2A	Mz	0	1.25
31	MP2A	Y	-74.7	2
32	MP2A	My	.0374	2
33	MP2A	Mz	0	2
34	MP1A	Y	-79.1	2
35	MP1A	My	.0396	2
36	MP1A	Mz	0	2
37	MP4A	Y	-79.1	2



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 21777772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Point Loads (BLC 1 : Antenna D) (Continued)

	Member Label	Direction	Magnitude[lb,k-ft]	Location[ft,%]
38	MP4A	My	.0396	2
39	MP4A	Mz	0	2
40	MP2A	Y	-23.2	3.5
41	MP2A	My	-.0116	3.5
42	MP2A	Mz	0	3.5
43	MP3A	Y	-84.4	2
44	MP3A	My	.0422	2
45	MP3A	Mz	0	2

Member Point Loads (BLC 2 : Antenna Di)

	Member Label	Direction	Magnitude[lb,k-ft]	Location[ft,%]
1	MP1A	Y	-98.5744	.5
2	MP1A	My	-.1052	.5
3	MP1A	Mz	-.0506	.5
4	MP1A	Y	-98.5744	3.5
5	MP1A	My	-.1052	3.5
6	MP1A	Mz	-.0506	3.5
7	MP1A	Y	-98.5744	.5
8	MP1A	My	-.0288	.5
9	MP1A	Mz	.1131	.5
10	MP1A	Y	-98.5744	3.5
11	MP1A	My	-.0288	3.5
12	MP1A	Mz	.1131	3.5
13	MP4A	Y	-98.5744	.5
14	MP4A	My	-.0288	.5
15	MP4A	Mz	-.1131	.5
16	MP4A	Y	-98.5744	3.5
17	MP4A	My	-.0288	3.5
18	MP4A	Mz	-.1131	3.5
19	MP4A	Y	-98.5744	.5
20	MP4A	My	-.1052	.5
21	MP4A	Mz	.0506	.5
22	MP4A	Y	-98.5744	3.5
23	MP4A	My	-.1052	3.5
24	MP4A	Mz	.0506	3.5
25	MP2A	Y	-30.2502	.25
26	MP2A	My	-.0151	.25
27	MP2A	Mz	0	.25
28	MP2A	Y	-30.2502	1.25
29	MP2A	My	-.0151	1.25
30	MP2A	Mz	0	1.25
31	MP2A	Y	-45.6168	2
32	MP2A	My	.0228	2
33	MP2A	Mz	0	2
34	MP1A	Y	-46.0998	2
35	MP1A	My	.0231	2
36	MP1A	Mz	0	2
37	MP4A	Y	-46.0998	2
38	MP4A	My	.0231	2
39	MP4A	Mz	0	2
40	MP2A	Y	-30.3553	3.5
41	MP2A	My	-.0152	3.5
42	MP2A	Mz	0	3.5
43	MP3A	Y	-45.6168	2
44	MP3A	My	.0228	2
45	MP3A	Mz	0	2



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 21777772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Point Loads (BLC 3 : Antenna Wo (0 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft. %]
1	MP1A	X	0	.5
2	MP1A	Z	-116.192	.5
3	MP1A	Mx	.0597	.5
4	MP1A	X	0	3.5
5	MP1A	Z	-116.192	3.5
6	MP1A	Mx	.0597	3.5
7	MP1A	X	0	.5
8	MP1A	Z	-116.192	.5
9	MP1A	Mx	-.1334	.5
10	MP1A	X	0	3.5
11	MP1A	Z	-116.192	3.5
12	MP1A	Mx	-.1334	3.5
13	MP4A	X	0	.5
14	MP4A	Z	-116.192	.5
15	MP4A	Mx	.1334	.5
16	MP4A	X	0	3.5
17	MP4A	Z	-116.192	3.5
18	MP4A	Mx	.1334	3.5
19	MP4A	X	0	.5
20	MP4A	Z	-116.192	.5
21	MP4A	Mx	-.0597	.5
22	MP4A	X	0	3.5
23	MP4A	Z	-116.192	3.5
24	MP4A	Mx	-.0597	3.5
25	MP2A	X	0	.25
26	MP2A	Z	-67.233	.25
27	MP2A	Mx	0	.25
28	MP2A	X	0	1.25
29	MP2A	Z	-67.233	1.25
30	MP2A	Mx	0	1.25
31	MP2A	X	0	2
32	MP2A	Z	-54.993	2
33	MP2A	Mx	0	2
34	MP1A	X	0	2
35	MP1A	Z	-66.346	2
36	MP1A	Mx	0	2
37	MP4A	X	0	2
38	MP4A	Z	-66.346	2
39	MP4A	Mx	0	2
40	MP2A	X	0	3.5
41	MP2A	Z	-54.283	3.5
42	MP2A	Mx	0	3.5
43	MP3A	X	0	2
44	MP3A	Z	-54.993	2
45	MP3A	Mx	0	2

Member Point Loads (BLC 4 : Antenna Wo (30 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft. %]
1	MP1A	X	42.198	.5
2	MP1A	Z	-73.09	.5
3	MP1A	Mx	-.0075	.5
4	MP1A	X	42.198	3.5
5	MP1A	Z	-73.09	3.5
6	MP1A	Mx	-.0075	3.5
7	MP1A	X	42.198	.5
8	MP1A	Z	-73.09	.5



Member Point Loads (BLC 4 : Antenna Wo (30 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
9	MP1A	Mx	-.0962	.5
10	MP1A	X	42.198	3.5
11	MP1A	Z	-73.09	3.5
12	MP1A	Mx	-.0962	3.5
13	MP4A	X	63.617	.5
14	MP4A	Z	-110.189	.5
15	MP4A	Mx	.1079	.5
16	MP4A	X	63.617	3.5
17	MP4A	Z	-110.189	3.5
18	MP4A	Mx	.1079	3.5
19	MP4A	X	63.617	.5
20	MP4A	Z	-110.189	.5
21	MP4A	Mx	-.1245	.5
22	MP4A	X	63.617	3.5
23	MP4A	Z	-110.189	3.5
24	MP4A	Mx	-.1245	3.5
25	MP2A	X	28.449	.25
26	MP2A	Z	-49.276	.25
27	MP2A	Mx	-.0142	.25
28	MP2A	X	28.449	1.25
29	MP2A	Z	-49.276	1.25
30	MP2A	Mx	-.0142	1.25
31	MP2A	X	25.235	2
32	MP2A	Z	-43.708	2
33	MP2A	Mx	.0126	2
34	MP1A	X	30.534	2
35	MP1A	Z	-52.887	2
36	MP1A	Mx	.0153	2
37	MP4A	X	30.534	2
38	MP4A	Z	-52.887	2
39	MP4A	Mx	.0153	2
40	MP2A	X	23.703	3.5
41	MP2A	Z	-41.056	3.5
42	MP2A	Mx	-.0119	3.5
43	MP3A	X	25.235	2
44	MP3A	Z	-43.708	2
45	MP3A	Mx	.0126	2

Member Point Loads (BLC 5 : Antenna Wo (60 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
1	MP1A	X	55.117	.5
2	MP1A	Z	-31.822	.5
3	MP1A	Mx	-.0425	.5
4	MP1A	X	55.117	3.5
5	MP1A	Z	-31.822	3.5
6	MP1A	Mx	-.0425	3.5
7	MP1A	X	55.117	.5
8	MP1A	Z	-31.822	.5
9	MP1A	Mx	-.0526	.5
10	MP1A	X	55.117	3.5
11	MP1A	Z	-31.822	3.5
12	MP1A	Mx	-.0526	3.5
13	MP4A	X	92.216	.5
14	MP4A	Z	-53.241	.5
15	MP4A	Mx	.0341	.5
16	MP4A	X	92.216	3.5



Member Point Loads (BLC 5 : Antenna Wo (60 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft,%]
17	MP4A	Z	-53.241	3.5
18	MP4A	Mx	.0341	3.5
19	MP4A	X	92.216	.5
20	MP4A	Z	-53.241	.5
21	MP4A	Mx	-.1258	.5
22	MP4A	X	92.216	3.5
23	MP4A	Z	-53.241	3.5
24	MP4A	Mx	-.1258	3.5
25	MP2A	X	31.376	.25
26	MP2A	Z	-18.115	.25
27	MP2A	Mx	-.0157	.25
28	MP2A	X	31.376	1.25
29	MP2A	Z	-18.115	1.25
30	MP2A	Mx	-.0157	1.25
31	MP2A	X	35.873	2
32	MP2A	Z	-20.711	2
33	MP2A	Mx	.0179	2
34	MP1A	X	43.746	2
35	MP1A	Z	-25.257	2
36	MP1A	Mx	.0219	2
37	MP4A	X	43.746	2
38	MP4A	Z	-25.257	2
39	MP4A	Mx	.0219	2
40	MP2A	X	29.145	3.5
41	MP2A	Z	-16.827	3.5
42	MP2A	Mx	-.0146	3.5
43	MP3A	X	35.873	2
44	MP3A	Z	-20.711	2
45	MP3A	Mx	.0179	2

Member Point Loads (BLC 6 : Antenna Wo (90 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft,%]
1	MP1A	X	74.686	.5
2	MP1A	Z	0	.5
3	MP1A	Mx	-.0797	.5
4	MP1A	X	74.686	3.5
5	MP1A	Z	0	3.5
6	MP1A	Mx	-.0797	3.5
7	MP1A	X	74.686	.5
8	MP1A	Z	0	.5
9	MP1A	Mx	-.0218	.5
10	MP1A	X	74.686	3.5
11	MP1A	Z	0	3.5
12	MP1A	Mx	-.0218	3.5
13	MP4A	X	74.686	.5
14	MP4A	Z	0	.5
15	MP4A	Mx	-.0218	.5
16	MP4A	X	74.686	3.5
17	MP4A	Z	0	3.5
18	MP4A	Mx	-.0218	3.5
19	MP4A	X	74.686	.5
20	MP4A	Z	0	.5
21	MP4A	Mx	-.0797	.5
22	MP4A	X	74.686	3.5
23	MP4A	Z	0	3.5
24	MP4A	Mx	-.0797	3.5



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 21777772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Point Loads (BLC 6 : Antenna Wo (90 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb,k-ft]	Location[ft,%]
25	MP2A	X	25.895	.25
26	MP2A	Z	0	.25
27	MP2A	Mx	-.0129	.25
28	MP2A	X	25.895	1.25
29	MP2A	Z	0	1.25
30	MP2A	Mx	-.0129	1.25
31	MP2A	X	36.898	2
32	MP2A	Z	0	2
33	MP2A	Mx	.0184	2
34	MP1A	X	45.236	2
35	MP1A	Z	0	2
36	MP1A	Mx	.0226	2
37	MP4A	X	45.236	2
38	MP4A	Z	0	2
39	MP4A	Mx	.0226	2
40	MP2A	X	26.778	3.5
41	MP2A	Z	0	3.5
42	MP2A	Mx	-.0134	3.5
43	MP3A	X	36.898	2
44	MP3A	Z	0	2
45	MP3A	Mx	.0184	2

Member Point Loads (BLC 7 : Antenna Wo (120 Deg))

	Member Label	Direction	Magnitude[lb,k-ft]	Location[ft,%]
1	MP1A	X	92.216	.5
2	MP1A	Z	53.241	.5
3	MP1A	Mx	-.1258	.5
4	MP1A	X	92.216	3.5
5	MP1A	Z	53.241	3.5
6	MP1A	Mx	-.1258	3.5
7	MP1A	X	92.216	.5
8	MP1A	Z	53.241	.5
9	MP1A	Mx	.0341	.5
10	MP1A	X	92.216	3.5
11	MP1A	Z	53.241	3.5
12	MP1A	Mx	.0341	3.5
13	MP4A	X	55.117	.5
14	MP4A	Z	31.822	.5
15	MP4A	Mx	-.0526	.5
16	MP4A	X	55.117	3.5
17	MP4A	Z	31.822	3.5
18	MP4A	Mx	-.0526	3.5
19	MP4A	X	55.117	.5
20	MP4A	Z	31.822	.5
21	MP4A	Mx	-.0425	.5
22	MP4A	X	55.117	3.5
23	MP4A	Z	31.822	3.5
24	MP4A	Mx	-.0425	3.5
25	MP2A	X	31.376	.25
26	MP2A	Z	18.115	.25
27	MP2A	Mx	-.0157	.25
28	MP2A	X	31.376	1.25
29	MP2A	Z	18.115	1.25
30	MP2A	Mx	-.0157	1.25
31	MP2A	X	35.873	2
32	MP2A	Z	20.711	2



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 21777772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Point Loads (BLC 7 : Antenna Wo (120 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
33	MP2A	Mx	.0179	2
34	MP1A	X	43.746	2
35	MP1A	Z	25.257	2
36	MP1A	Mx	.0219	2
37	MP4A	X	43.746	2
38	MP4A	Z	25.257	2
39	MP4A	Mx	.0219	2
40	MP2A	X	29.145	3.5
41	MP2A	Z	16.827	3.5
42	MP2A	Mx	-.0146	3.5
43	MP3A	X	35.873	2
44	MP3A	Z	20.711	2
45	MP3A	Mx	.0179	2

Member Point Loads (BLC 8 : Antenna Wo (150 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
1	MP1A	X	63.617	.5
2	MP1A	Z	110.189	.5
3	MP1A	Mx	-.1245	.5
4	MP1A	X	63.617	3.5
5	MP1A	Z	110.189	3.5
6	MP1A	Mx	-.1245	3.5
7	MP1A	X	63.617	.5
8	MP1A	Z	110.189	.5
9	MP1A	Mx	.1079	.5
10	MP1A	X	63.617	3.5
11	MP1A	Z	110.189	3.5
12	MP1A	Mx	.1079	3.5
13	MP4A	X	42.198	.5
14	MP4A	Z	73.09	.5
15	MP4A	Mx	-.0962	.5
16	MP4A	X	42.198	3.5
17	MP4A	Z	73.09	3.5
18	MP4A	Mx	-.0962	3.5
19	MP4A	X	42.198	.5
20	MP4A	Z	73.09	.5
21	MP4A	Mx	-.0075	.5
22	MP4A	X	42.198	3.5
23	MP4A	Z	73.09	3.5
24	MP4A	Mx	-.0075	3.5
25	MP2A	X	28.449	.25
26	MP2A	Z	49.276	.25
27	MP2A	Mx	-.0142	.25
28	MP2A	X	28.449	1.25
29	MP2A	Z	49.276	1.25
30	MP2A	Mx	-.0142	1.25
31	MP2A	X	25.235	2
32	MP2A	Z	43.708	2
33	MP2A	Mx	.0126	2
34	MP1A	X	30.534	2
35	MP1A	Z	52.887	2
36	MP1A	Mx	.0153	2
37	MP4A	X	30.534	2
38	MP4A	Z	52.887	2
39	MP4A	Mx	.0153	2
40	MP2A	X	23.703	3.5



Member Point Loads (BLC 8 : Antenna Wo (150 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
41	MP2A	Z	41.056	3.5
42	MP2A	Mx	-.0119	3.5
43	MP3A	X	25.235	2
44	MP3A	Z	43.708	2
45	MP3A	Mx	.0126	2

Member Point Loads (BLC 9 : Antenna Wo (180 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
1	MP1A	X	0	.5
2	MP1A	Z	116.192	.5
3	MP1A	Mx	-.0597	.5
4	MP1A	X	0	3.5
5	MP1A	Z	116.192	3.5
6	MP1A	Mx	-.0597	3.5
7	MP1A	X	0	.5
8	MP1A	Z	116.192	.5
9	MP1A	Mx	.1334	.5
10	MP1A	X	0	3.5
11	MP1A	Z	116.192	3.5
12	MP1A	Mx	.1334	3.5
13	MP4A	X	0	.5
14	MP4A	Z	116.192	.5
15	MP4A	Mx	-.1334	.5
16	MP4A	X	0	3.5
17	MP4A	Z	116.192	3.5
18	MP4A	Mx	-.1334	3.5
19	MP4A	X	0	.5
20	MP4A	Z	116.192	.5
21	MP4A	Mx	.0597	.5
22	MP4A	X	0	3.5
23	MP4A	Z	116.192	3.5
24	MP4A	Mx	.0597	3.5
25	MP2A	X	0	.25
26	MP2A	Z	67.233	.25
27	MP2A	Mx	0	.25
28	MP2A	X	0	1.25
29	MP2A	Z	67.233	1.25
30	MP2A	Mx	0	1.25
31	MP2A	X	0	2
32	MP2A	Z	54.993	2
33	MP2A	Mx	0	2
34	MP1A	X	0	2
35	MP1A	Z	66.346	2
36	MP1A	Mx	0	2
37	MP4A	X	0	2
38	MP4A	Z	66.346	2
39	MP4A	Mx	0	2
40	MP2A	X	0	3.5
41	MP2A	Z	54.283	3.5
42	MP2A	Mx	0	3.5
43	MP3A	X	0	2
44	MP3A	Z	54.993	2
45	MP3A	Mx	0	2

Member Point Loads (BLC 10 : Antenna Wo (210 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
--	--------------	-----------	--------------------	----------------



Member Point Loads (BLC 10 : Antenna Wo (210 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft. %]
1	MP1A	X	-42.198	.5
2	MP1A	Z	73.09	.5
3	MP1A	Mx	.0075	.5
4	MP1A	X	-42.198	3.5
5	MP1A	Z	73.09	3.5
6	MP1A	Mx	.0075	3.5
7	MP1A	X	-42.198	.5
8	MP1A	Z	73.09	.5
9	MP1A	Mx	.0962	.5
10	MP1A	X	-42.198	3.5
11	MP1A	Z	73.09	3.5
12	MP1A	Mx	.0962	3.5
13	MP4A	X	-63.617	.5
14	MP4A	Z	110.189	.5
15	MP4A	Mx	-.1079	.5
16	MP4A	X	-63.617	3.5
17	MP4A	Z	110.189	3.5
18	MP4A	Mx	-.1079	3.5
19	MP4A	X	-63.617	.5
20	MP4A	Z	110.189	.5
21	MP4A	Mx	.1245	.5
22	MP4A	X	-63.617	3.5
23	MP4A	Z	110.189	3.5
24	MP4A	Mx	.1245	3.5
25	MP2A	X	-28.449	.25
26	MP2A	Z	49.276	.25
27	MP2A	Mx	.0142	.25
28	MP2A	X	-28.449	1.25
29	MP2A	Z	49.276	1.25
30	MP2A	Mx	.0142	1.25
31	MP2A	X	-25.235	2
32	MP2A	Z	43.708	2
33	MP2A	Mx	-.0126	2
34	MP1A	X	-30.534	2
35	MP1A	Z	52.887	2
36	MP1A	Mx	-.0153	2
37	MP4A	X	-30.534	2
38	MP4A	Z	52.887	2
39	MP4A	Mx	-.0153	2
40	MP2A	X	-23.703	3.5
41	MP2A	Z	41.056	3.5
42	MP2A	Mx	.0119	3.5
43	MP3A	X	-25.235	2
44	MP3A	Z	43.708	2
45	MP3A	Mx	-.0126	2

Member Point Loads (BLC 11 : Antenna Wo (240 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft. %]
1	MP1A	X	-55.117	.5
2	MP1A	Z	31.822	.5
3	MP1A	Mx	.0425	.5
4	MP1A	X	-55.117	3.5
5	MP1A	Z	31.822	3.5
6	MP1A	Mx	.0425	3.5
7	MP1A	X	-55.117	.5
8	MP1A	Z	31.822	.5



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 2177772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Point Loads (BLC 11 : Antenna Wo (240 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb,k-ft]	Location[ft,%]
9	MP1A	Mx	.0526	.5
10	MP1A	X	-55.117	3.5
11	MP1A	Z	31.822	3.5
12	MP1A	Mx	.0526	3.5
13	MP4A	X	-92.216	.5
14	MP4A	Z	53.241	.5
15	MP4A	Mx	-.0341	.5
16	MP4A	X	-92.216	3.5
17	MP4A	Z	53.241	3.5
18	MP4A	Mx	-.0341	3.5
19	MP4A	X	-92.216	.5
20	MP4A	Z	53.241	.5
21	MP4A	Mx	.1258	.5
22	MP4A	X	-92.216	3.5
23	MP4A	Z	53.241	3.5
24	MP4A	Mx	.1258	3.5
25	MP2A	X	-31.376	.25
26	MP2A	Z	18.115	.25
27	MP2A	Mx	.0157	.25
28	MP2A	X	-31.376	1.25
29	MP2A	Z	18.115	1.25
30	MP2A	Mx	.0157	1.25
31	MP2A	X	-35.873	2
32	MP2A	Z	20.711	2
33	MP2A	Mx	-.0179	2
34	MP1A	X	-43.746	2
35	MP1A	Z	25.257	2
36	MP1A	Mx	-.0219	2
37	MP4A	X	-43.746	2
38	MP4A	Z	25.257	2
39	MP4A	Mx	-.0219	2
40	MP2A	X	-29.145	3.5
41	MP2A	Z	16.827	3.5
42	MP2A	Mx	.0146	3.5
43	MP3A	X	-35.873	2
44	MP3A	Z	20.711	2
45	MP3A	Mx	-.0179	2

Member Point Loads (BLC 12 : Antenna Wo (270 Deg))

	Member Label	Direction	Magnitude[lb,k-ft]	Location[ft,%]
1	MP1A	X	-74.686	.5
2	MP1A	Z	0	.5
3	MP1A	Mx	.0797	.5
4	MP1A	X	-74.686	3.5
5	MP1A	Z	0	3.5
6	MP1A	Mx	.0797	3.5
7	MP1A	X	-74.686	.5
8	MP1A	Z	0	.5
9	MP1A	Mx	.0218	.5
10	MP1A	X	-74.686	3.5
11	MP1A	Z	0	3.5
12	MP1A	Mx	.0218	3.5
13	MP4A	X	-74.686	.5
14	MP4A	Z	0	.5
15	MP4A	Mx	.0218	.5
16	MP4A	X	-74.686	3.5



Member Point Loads (BLC 12 : Antenna Wo (270 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft,%]
17	MP4A	Z	0	3.5
18	MP4A	Mx	.0218	3.5
19	MP4A	X	-74.686	.5
20	MP4A	Z	0	.5
21	MP4A	Mx	.0797	.5
22	MP4A	X	-74.686	3.5
23	MP4A	Z	0	3.5
24	MP4A	Mx	.0797	3.5
25	MP2A	X	-25.895	.25
26	MP2A	Z	0	.25
27	MP2A	Mx	.0129	.25
28	MP2A	X	-25.895	1.25
29	MP2A	Z	0	1.25
30	MP2A	Mx	.0129	1.25
31	MP2A	X	-36.898	2
32	MP2A	Z	0	2
33	MP2A	Mx	-.0184	2
34	MP1A	X	-45.236	2
35	MP1A	Z	0	2
36	MP1A	Mx	-.0226	2
37	MP4A	X	-45.236	2
38	MP4A	Z	0	2
39	MP4A	Mx	-.0226	2
40	MP2A	X	-26.778	3.5
41	MP2A	Z	0	3.5
42	MP2A	Mx	.0134	3.5
43	MP3A	X	-36.898	2
44	MP3A	Z	0	2
45	MP3A	Mx	-.0184	2

Member Point Loads (BLC 13 : Antenna Wo (300 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft,%]
1	MP1A	X	-92.216	.5
2	MP1A	Z	-53.241	.5
3	MP1A	Mx	.1258	.5
4	MP1A	X	-92.216	3.5
5	MP1A	Z	-53.241	3.5
6	MP1A	Mx	.1258	3.5
7	MP1A	X	-92.216	.5
8	MP1A	Z	-53.241	.5
9	MP1A	Mx	-.0341	.5
10	MP1A	X	-92.216	3.5
11	MP1A	Z	-53.241	3.5
12	MP1A	Mx	-.0341	3.5
13	MP4A	X	-55.117	.5
14	MP4A	Z	-31.822	.5
15	MP4A	Mx	.0526	.5
16	MP4A	X	-55.117	3.5
17	MP4A	Z	-31.822	3.5
18	MP4A	Mx	.0526	3.5
19	MP4A	X	-55.117	.5
20	MP4A	Z	-31.822	.5
21	MP4A	Mx	.0425	.5
22	MP4A	X	-55.117	3.5
23	MP4A	Z	-31.822	3.5
24	MP4A	Mx	.0425	3.5



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 21777772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Point Loads (BLC 13 : Antenna Wo (300 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft. %]
25	MP2A	X	-31.376	.25
26	MP2A	Z	-18.115	.25
27	MP2A	Mx	.0157	.25
28	MP2A	X	-31.376	1.25
29	MP2A	Z	-18.115	1.25
30	MP2A	Mx	.0157	1.25
31	MP2A	X	-35.873	2
32	MP2A	Z	-20.711	2
33	MP2A	Mx	-.0179	2
34	MP1A	X	-43.746	2
35	MP1A	Z	-25.257	2
36	MP1A	Mx	-.0219	2
37	MP4A	X	-43.746	2
38	MP4A	Z	-25.257	2
39	MP4A	Mx	-.0219	2
40	MP2A	X	-29.145	3.5
41	MP2A	Z	-16.827	3.5
42	MP2A	Mx	.0146	3.5
43	MP3A	X	-35.873	2
44	MP3A	Z	-20.711	2
45	MP3A	Mx	-.0179	2

Member Point Loads (BLC 14 : Antenna Wo (330 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft. %]
1	MP1A	X	-63.617	.5
2	MP1A	Z	-110.189	.5
3	MP1A	Mx	.1245	.5
4	MP1A	X	-63.617	3.5
5	MP1A	Z	-110.189	3.5
6	MP1A	Mx	.1245	3.5
7	MP1A	X	-63.617	.5
8	MP1A	Z	-110.189	.5
9	MP1A	Mx	-.1079	.5
10	MP1A	X	-63.617	3.5
11	MP1A	Z	-110.189	3.5
12	MP1A	Mx	-.1079	3.5
13	MP4A	X	-42.198	.5
14	MP4A	Z	-73.09	.5
15	MP4A	Mx	.0962	.5
16	MP4A	X	-42.198	3.5
17	MP4A	Z	-73.09	3.5
18	MP4A	Mx	.0962	3.5
19	MP4A	X	-42.198	.5
20	MP4A	Z	-73.09	.5
21	MP4A	Mx	.0075	.5
22	MP4A	X	-42.198	3.5
23	MP4A	Z	-73.09	3.5
24	MP4A	Mx	.0075	3.5
25	MP2A	X	-28.449	.25
26	MP2A	Z	-49.276	.25
27	MP2A	Mx	.0142	.25
28	MP2A	X	-28.449	1.25
29	MP2A	Z	-49.276	1.25
30	MP2A	Mx	.0142	1.25
31	MP2A	X	-25.235	2
32	MP2A	Z	-43.708	2



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 21777772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Point Loads (BLC 14 : Antenna Wo (330 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
33	MP2A	Mx	-.0126	2
34	MP1A	X	-30.534	2
35	MP1A	Z	-52.887	2
36	MP1A	Mx	-.0153	2
37	MP4A	X	-30.534	2
38	MP4A	Z	-52.887	2
39	MP4A	Mx	-.0153	2
40	MP2A	X	-23.703	3.5
41	MP2A	Z	-41.056	3.5
42	MP2A	Mx	.0119	3.5
43	MP3A	X	-25.235	2
44	MP3A	Z	-43.708	2
45	MP3A	Mx	-.0126	2

Member Point Loads (BLC 15 : Antenna Wi (0 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
1	MP1A	X	0	.5
2	MP1A	Z	-38.328	.5
3	MP1A	Mx	.0197	.5
4	MP1A	X	0	3.5
5	MP1A	Z	-38.328	3.5
6	MP1A	Mx	.0197	3.5
7	MP1A	X	0	.5
8	MP1A	Z	-38.328	.5
9	MP1A	Mx	-.044	.5
10	MP1A	X	0	3.5
11	MP1A	Z	-38.328	3.5
12	MP1A	Mx	-.044	3.5
13	MP4A	X	0	.5
14	MP4A	Z	-38.328	.5
15	MP4A	Mx	.044	.5
16	MP4A	X	0	3.5
17	MP4A	Z	-38.328	3.5
18	MP4A	Mx	.044	3.5
19	MP4A	X	0	.5
20	MP4A	Z	-38.328	.5
21	MP4A	Mx	-.0197	.5
22	MP4A	X	0	3.5
23	MP4A	Z	-38.328	3.5
24	MP4A	Mx	-.0197	3.5
25	MP2A	X	0	.25
26	MP2A	Z	-13.367	.25
27	MP2A	Mx	0	.25
28	MP2A	X	0	1.25
29	MP2A	Z	-13.367	1.25
30	MP2A	Mx	0	1.25
31	MP2A	X	0	2
32	MP2A	Z	-13.816	2
33	MP2A	Mx	0	2
34	MP1A	X	0	2
35	MP1A	Z	-13.816	2
36	MP1A	Mx	0	2
37	MP4A	X	0	2
38	MP4A	Z	-13.816	2
39	MP4A	Mx	0	2
40	MP2A	X	0	3.5



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 21777772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Point Loads (BLC 15 : Antenna Wi (0 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
41	MP2A	Z	-11.578	3.5
42	MP2A	Mx	0	3.5
43	MP3A	X	0	2
44	MP3A	Z	-13.816	2
45	MP3A	Mx	0	2

Member Point Loads (BLC 16 : Antenna Wi (30 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
1	MP1A	X	15.289	.5
2	MP1A	Z	-26.481	.5
3	MP1A	Mx	-.0027	.5
4	MP1A	X	15.289	3.5
5	MP1A	Z	-26.481	3.5
6	MP1A	Mx	-.0027	3.5
7	MP1A	X	15.289	.5
8	MP1A	Z	-26.481	.5
9	MP1A	Mx	-.0349	.5
10	MP1A	X	15.289	3.5
11	MP1A	Z	-26.481	3.5
12	MP1A	Mx	-.0349	3.5
13	MP4A	X	20.51	.5
14	MP4A	Z	-35.524	.5
15	MP4A	Mx	.0348	.5
16	MP4A	X	20.51	3.5
17	MP4A	Z	-35.524	3.5
18	MP4A	Mx	.0348	3.5
19	MP4A	X	20.51	.5
20	MP4A	Z	-35.524	.5
21	MP4A	Mx	-.0401	.5
22	MP4A	X	20.51	3.5
23	MP4A	Z	-35.524	3.5
24	MP4A	Mx	-.0401	3.5
25	MP2A	X	5.719	.25
26	MP2A	Z	-9.906	.25
27	MP2A	Mx	-.0029	.25
28	MP2A	X	5.719	1.25
29	MP2A	Z	-9.906	1.25
30	MP2A	Mx	-.0029	1.25
31	MP2A	X	6.383	2
32	MP2A	Z	-11.055	2
33	MP2A	Mx	.0032	2
34	MP1A	X	6.404	2
35	MP1A	Z	-11.092	2
36	MP1A	Mx	.0032	2
37	MP4A	X	6.404	2
38	MP4A	Z	-11.092	2
39	MP4A	Mx	.0032	2
40	MP2A	X	5.124	3.5
41	MP2A	Z	-8.875	3.5
42	MP2A	Mx	-.0026	3.5
43	MP3A	X	6.383	2
44	MP3A	Z	-11.055	2
45	MP3A	Mx	.0032	2

Member Point Loads (BLC 17 : Antenna Wi (60 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
--	--------------	-----------	--------------------	----------------



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 21777772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Point Loads (BLC 17 : Antenna Wi (60 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb,k-ft]	Location[ft, %]
1	MP1A	X	22.1	.5
2	MP1A	Z	-12.759	.5
3	MP1A	Mx	-.017	.5
4	MP1A	X	22.1	3.5
5	MP1A	Z	-12.759	3.5
6	MP1A	Mx	-.017	3.5
7	MP1A	X	22.1	.5
8	MP1A	Z	-12.759	.5
9	MP1A	Mx	-.0211	.5
10	MP1A	X	22.1	3.5
11	MP1A	Z	-12.759	3.5
12	MP1A	Mx	-.0211	3.5
13	MP4A	X	31.143	.5
14	MP4A	Z	-17.98	.5
15	MP4A	Mx	.0115	.5
16	MP4A	X	31.143	3.5
17	MP4A	Z	-17.98	3.5
18	MP4A	Mx	.0115	3.5
19	MP4A	X	31.143	.5
20	MP4A	Z	-17.98	.5
21	MP4A	Mx	-.0425	.5
22	MP4A	X	31.143	3.5
23	MP4A	Z	-17.98	3.5
24	MP4A	Mx	-.0425	3.5
25	MP2A	X	6.565	.25
26	MP2A	Z	-3.79	.25
27	MP2A	Mx	-.0033	.25
28	MP2A	X	6.565	1.25
29	MP2A	Z	-3.79	1.25
30	MP2A	Mx	-.0033	1.25
31	MP2A	X	9.237	2
32	MP2A	Z	-5.333	2
33	MP2A	Mx	.0046	2
34	MP1A	X	9.346	2
35	MP1A	Z	-5.396	2
36	MP1A	Mx	.0047	2
37	MP4A	X	9.346	2
38	MP4A	Z	-5.396	2
39	MP4A	Mx	.0047	2
40	MP2A	X	6.572	3.5
41	MP2A	Z	-3.794	3.5
42	MP2A	Mx	-.0033	3.5
43	MP3A	X	9.237	2
44	MP3A	Z	-5.333	2
45	MP3A	Mx	.0046	2

Member Point Loads (BLC 18 : Antenna Wi (90 Deg))

	Member Label	Direction	Magnitude[lb,k-ft]	Location[ft, %]
1	MP1A	X	28.21	.5
2	MP1A	Z	0	.5
3	MP1A	Mx	-.0301	.5
4	MP1A	X	28.21	3.5
5	MP1A	Z	0	3.5
6	MP1A	Mx	-.0301	3.5
7	MP1A	X	28.21	.5
8	MP1A	Z	0	.5



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 21777772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Point Loads (BLC 18 : Antenna Wi (90 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft. %]
9	MP1A	Mx	-.0082	.5
10	MP1A	X	28.21	3.5
11	MP1A	Z	0	3.5
12	MP1A	Mx	-.0082	3.5
13	MP4A	X	28.21	.5
14	MP4A	Z	0	.5
15	MP4A	Mx	-.0082	.5
16	MP4A	X	28.21	3.5
17	MP4A	Z	0	3.5
18	MP4A	Mx	-.0082	3.5
19	MP4A	X	28.21	.5
20	MP4A	Z	0	.5
21	MP4A	Mx	-.0301	.5
22	MP4A	X	28.21	3.5
23	MP4A	Z	0	3.5
24	MP4A	Mx	-.0301	3.5
25	MP2A	X	5.652	.25
26	MP2A	Z	0	.25
27	MP2A	Mx	-.0028	.25
28	MP2A	X	5.652	1.25
29	MP2A	Z	0	1.25
30	MP2A	Mx	-.0028	1.25
31	MP2A	X	9.616	2
32	MP2A	Z	0	2
33	MP2A	Mx	.0048	2
34	MP1A	X	9.784	2
35	MP1A	Z	0	2
36	MP1A	Mx	.0049	2
37	MP4A	X	9.784	2
38	MP4A	Z	0	2
39	MP4A	Mx	.0049	2
40	MP2A	X	6.258	3.5
41	MP2A	Z	0	3.5
42	MP2A	Mx	-.0031	3.5
43	MP3A	X	9.616	2
44	MP3A	Z	0	2
45	MP3A	Mx	.0048	2

Member Point Loads (BLC 19 : Antenna Wi (120 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft. %]
1	MP1A	X	31.143	.5
2	MP1A	Z	17.98	.5
3	MP1A	Mx	-.0425	.5
4	MP1A	X	31.143	3.5
5	MP1A	Z	17.98	3.5
6	MP1A	Mx	-.0425	3.5
7	MP1A	X	31.143	.5
8	MP1A	Z	17.98	.5
9	MP1A	Mx	.0115	.5
10	MP1A	X	31.143	3.5
11	MP1A	Z	17.98	3.5
12	MP1A	Mx	.0115	3.5
13	MP4A	X	22.1	.5
14	MP4A	Z	12.759	.5
15	MP4A	Mx	-.0211	.5
16	MP4A	X	22.1	3.5



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 21777772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Point Loads (BLC 19 : Antenna Wi (120 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft. %]
17	MP4A	Z	12.759	3.5
18	MP4A	Mx	-.0211	3.5
19	MP4A	X	22.1	.5
20	MP4A	Z	12.759	.5
21	MP4A	Mx	-.017	.5
22	MP4A	X	22.1	3.5
23	MP4A	Z	12.759	3.5
24	MP4A	Mx	-.017	3.5
25	MP2A	X	6.565	.25
26	MP2A	Z	3.79	.25
27	MP2A	Mx	-.0033	.25
28	MP2A	X	6.565	1.25
29	MP2A	Z	3.79	1.25
30	MP2A	Mx	-.0033	1.25
31	MP2A	X	9.237	2
32	MP2A	Z	5.333	2
33	MP2A	Mx	.0046	2
34	MP1A	X	9.346	2
35	MP1A	Z	5.396	2
36	MP1A	Mx	.0047	2
37	MP4A	X	9.346	2
38	MP4A	Z	5.396	2
39	MP4A	Mx	.0047	2
40	MP2A	X	6.572	3.5
41	MP2A	Z	3.794	3.5
42	MP2A	Mx	-.0033	3.5
43	MP3A	X	9.237	2
44	MP3A	Z	5.333	2
45	MP3A	Mx	.0046	2

Member Point Loads (BLC 20 : Antenna Wi (150 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft. %]
1	MP1A	X	20.51	.5
2	MP1A	Z	35.524	.5
3	MP1A	Mx	-.0401	.5
4	MP1A	X	20.51	3.5
5	MP1A	Z	35.524	3.5
6	MP1A	Mx	-.0401	3.5
7	MP1A	X	20.51	.5
8	MP1A	Z	35.524	.5
9	MP1A	Mx	.0348	.5
10	MP1A	X	20.51	3.5
11	MP1A	Z	35.524	3.5
12	MP1A	Mx	.0348	3.5
13	MP4A	X	15.289	.5
14	MP4A	Z	26.481	.5
15	MP4A	Mx	-.0349	.5
16	MP4A	X	15.289	3.5
17	MP4A	Z	26.481	3.5
18	MP4A	Mx	-.0349	3.5
19	MP4A	X	15.289	.5
20	MP4A	Z	26.481	.5
21	MP4A	Mx	-.0027	.5
22	MP4A	X	15.289	3.5
23	MP4A	Z	26.481	3.5
24	MP4A	Mx	-.0027	3.5



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 21777772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Point Loads (BLC 20 : Antenna Wi (150 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft. %]
25	MP2A	X	5.719	.25
26	MP2A	Z	9.906	.25
27	MP2A	Mx	-.0029	.25
28	MP2A	X	5.719	1.25
29	MP2A	Z	9.906	1.25
30	MP2A	Mx	-.0029	1.25
31	MP2A	X	6.383	2
32	MP2A	Z	11.055	2
33	MP2A	Mx	.0032	2
34	MP1A	X	6.404	2
35	MP1A	Z	11.092	2
36	MP1A	Mx	.0032	2
37	MP4A	X	6.404	2
38	MP4A	Z	11.092	2
39	MP4A	Mx	.0032	2
40	MP2A	X	5.124	3.5
41	MP2A	Z	8.875	3.5
42	MP2A	Mx	-.0026	3.5
43	MP3A	X	6.383	2
44	MP3A	Z	11.055	2
45	MP3A	Mx	.0032	2

Member Point Loads (BLC 21 : Antenna Wi (180 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft. %]
1	MP1A	X	0	.5
2	MP1A	Z	38.328	.5
3	MP1A	Mx	-.0197	.5
4	MP1A	X	0	3.5
5	MP1A	Z	38.328	3.5
6	MP1A	Mx	-.0197	3.5
7	MP1A	X	0	.5
8	MP1A	Z	38.328	.5
9	MP1A	Mx	.044	.5
10	MP1A	X	0	3.5
11	MP1A	Z	38.328	3.5
12	MP1A	Mx	.044	3.5
13	MP4A	X	0	.5
14	MP4A	Z	38.328	.5
15	MP4A	Mx	-.044	.5
16	MP4A	X	0	3.5
17	MP4A	Z	38.328	3.5
18	MP4A	Mx	-.044	3.5
19	MP4A	X	0	.5
20	MP4A	Z	38.328	.5
21	MP4A	Mx	.0197	.5
22	MP4A	X	0	3.5
23	MP4A	Z	38.328	3.5
24	MP4A	Mx	.0197	3.5
25	MP2A	X	0	.25
26	MP2A	Z	13.367	.25
27	MP2A	Mx	0	.25
28	MP2A	X	0	1.25
29	MP2A	Z	13.367	1.25
30	MP2A	Mx	0	1.25
31	MP2A	X	0	2
32	MP2A	Z	13.816	2



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 2177772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Point Loads (BLC 21 : Antenna Wi (180 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft. %]
33	MP2A	Mx	0	2
34	MP1A	X	0	2
35	MP1A	Z	13.816	2
36	MP1A	Mx	0	2
37	MP4A	X	0	2
38	MP4A	Z	13.816	2
39	MP4A	Mx	0	2
40	MP2A	X	0	3.5
41	MP2A	Z	11.578	3.5
42	MP2A	Mx	0	3.5
43	MP3A	X	0	2
44	MP3A	Z	13.816	2
45	MP3A	Mx	0	2

Member Point Loads (BLC 22 : Antenna Wi (210 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft. %]
1	MP1A	X	-15.289	.5
2	MP1A	Z	26.481	.5
3	MP1A	Mx	.0027	.5
4	MP1A	X	-15.289	3.5
5	MP1A	Z	26.481	3.5
6	MP1A	Mx	.0027	3.5
7	MP1A	X	-15.289	.5
8	MP1A	Z	26.481	.5
9	MP1A	Mx	.0349	.5
10	MP1A	X	-15.289	3.5
11	MP1A	Z	26.481	3.5
12	MP1A	Mx	.0349	3.5
13	MP4A	X	-20.51	.5
14	MP4A	Z	35.524	.5
15	MP4A	Mx	-.0348	.5
16	MP4A	X	-20.51	3.5
17	MP4A	Z	35.524	3.5
18	MP4A	Mx	-.0348	3.5
19	MP4A	X	-20.51	.5
20	MP4A	Z	35.524	.5
21	MP4A	Mx	.0401	.5
22	MP4A	X	-20.51	3.5
23	MP4A	Z	35.524	3.5
24	MP4A	Mx	.0401	3.5
25	MP2A	X	-5.719	.25
26	MP2A	Z	9.906	.25
27	MP2A	Mx	.0029	.25
28	MP2A	X	-5.719	1.25
29	MP2A	Z	9.906	1.25
30	MP2A	Mx	.0029	1.25
31	MP2A	X	-6.383	2
32	MP2A	Z	11.055	2
33	MP2A	Mx	-.0032	2
34	MP1A	X	-6.404	2
35	MP1A	Z	11.092	2
36	MP1A	Mx	-.0032	2
37	MP4A	X	-6.404	2
38	MP4A	Z	11.092	2
39	MP4A	Mx	-.0032	2
40	MP2A	X	-5.124	3.5



Member Point Loads (BLC 22 : Antenna Wi (210 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb,k-ft]	Location[ft,%]
41	MP2A	Z	8.875	3.5
42	MP2A	Mx	.0026	3.5
43	MP3A	X	-6.383	2
44	MP3A	Z	11.055	2
45	MP3A	Mx	-.0032	2

Member Point Loads (BLC 23 : Antenna Wi (240 Deg))

	Member Label	Direction	Magnitude[lb,k-ft]	Location[ft,%]
1	MP1A	X	-22.1	.5
2	MP1A	Z	12.759	.5
3	MP1A	Mx	.017	.5
4	MP1A	X	-22.1	3.5
5	MP1A	Z	12.759	3.5
6	MP1A	Mx	.017	3.5
7	MP1A	X	-22.1	.5
8	MP1A	Z	12.759	.5
9	MP1A	Mx	.0211	.5
10	MP1A	X	-22.1	3.5
11	MP1A	Z	12.759	3.5
12	MP1A	Mx	.0211	3.5
13	MP4A	X	-31.143	.5
14	MP4A	Z	17.98	.5
15	MP4A	Mx	-.0115	.5
16	MP4A	X	-31.143	3.5
17	MP4A	Z	17.98	3.5
18	MP4A	Mx	-.0115	3.5
19	MP4A	X	-31.143	.5
20	MP4A	Z	17.98	.5
21	MP4A	Mx	.0425	.5
22	MP4A	X	-31.143	3.5
23	MP4A	Z	17.98	3.5
24	MP4A	Mx	.0425	3.5
25	MP2A	X	-6.565	.25
26	MP2A	Z	3.79	.25
27	MP2A	Mx	.0033	.25
28	MP2A	X	-6.565	1.25
29	MP2A	Z	3.79	1.25
30	MP2A	Mx	.0033	1.25
31	MP2A	X	-9.237	2
32	MP2A	Z	5.333	2
33	MP2A	Mx	-.0046	2
34	MP1A	X	-9.346	2
35	MP1A	Z	5.396	2
36	MP1A	Mx	-.0047	2
37	MP4A	X	-9.346	2
38	MP4A	Z	5.396	2
39	MP4A	Mx	-.0047	2
40	MP2A	X	-6.572	3.5
41	MP2A	Z	3.794	3.5
42	MP2A	Mx	.0033	3.5
43	MP3A	X	-9.237	2
44	MP3A	Z	5.333	2
45	MP3A	Mx	-.0046	2

Member Point Loads (BLC 24 : Antenna Wi (270 Deg))

	Member Label	Direction	Magnitude[lb,k-ft]	Location[ft,%]
--	--------------	-----------	--------------------	----------------



Member Point Loads (BLC 24 : Antenna Wi (270 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft. %]
1	MP1A	X	-28.21	.5
2	MP1A	Z	0	.5
3	MP1A	Mx	.0301	.5
4	MP1A	X	-28.21	3.5
5	MP1A	Z	0	3.5
6	MP1A	Mx	.0301	3.5
7	MP1A	X	-28.21	.5
8	MP1A	Z	0	.5
9	MP1A	Mx	.0082	.5
10	MP1A	X	-28.21	3.5
11	MP1A	Z	0	3.5
12	MP1A	Mx	.0082	3.5
13	MP4A	X	-28.21	.5
14	MP4A	Z	0	.5
15	MP4A	Mx	.0082	.5
16	MP4A	X	-28.21	3.5
17	MP4A	Z	0	3.5
18	MP4A	Mx	.0082	3.5
19	MP4A	X	-28.21	.5
20	MP4A	Z	0	.5
21	MP4A	Mx	.0301	.5
22	MP4A	X	-28.21	3.5
23	MP4A	Z	0	3.5
24	MP4A	Mx	.0301	3.5
25	MP2A	X	-5.652	.25
26	MP2A	Z	0	.25
27	MP2A	Mx	.0028	.25
28	MP2A	X	-5.652	1.25
29	MP2A	Z	0	1.25
30	MP2A	Mx	.0028	1.25
31	MP2A	X	-9.616	2
32	MP2A	Z	0	2
33	MP2A	Mx	-.0048	2
34	MP1A	X	-9.784	2
35	MP1A	Z	0	2
36	MP1A	Mx	-.0049	2
37	MP4A	X	-9.784	2
38	MP4A	Z	0	2
39	MP4A	Mx	-.0049	2
40	MP2A	X	-6.258	3.5
41	MP2A	Z	0	3.5
42	MP2A	Mx	.0031	3.5
43	MP3A	X	-9.616	2
44	MP3A	Z	0	2
45	MP3A	Mx	-.0048	2

Member Point Loads (BLC 25 : Antenna Wi (300 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft. %]
1	MP1A	X	-31.143	.5
2	MP1A	Z	-17.98	.5
3	MP1A	Mx	.0425	.5
4	MP1A	X	-31.143	3.5
5	MP1A	Z	-17.98	3.5
6	MP1A	Mx	.0425	3.5
7	MP1A	X	-31.143	.5
8	MP1A	Z	-17.98	.5



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 21777772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Point Loads (BLC 25 : Antenna Wi (300 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft. %]
9	MP1A	Mx	-.0115	.5
10	MP1A	X	-31.143	3.5
11	MP1A	Z	-17.98	3.5
12	MP1A	Mx	-.0115	3.5
13	MP4A	X	-22.1	.5
14	MP4A	Z	-12.759	.5
15	MP4A	Mx	.0211	.5
16	MP4A	X	-22.1	3.5
17	MP4A	Z	-12.759	3.5
18	MP4A	Mx	.0211	3.5
19	MP4A	X	-22.1	.5
20	MP4A	Z	-12.759	.5
21	MP4A	Mx	.017	.5
22	MP4A	X	-22.1	3.5
23	MP4A	Z	-12.759	3.5
24	MP4A	Mx	.017	3.5
25	MP2A	X	-6.565	.25
26	MP2A	Z	-3.79	.25
27	MP2A	Mx	.0033	.25
28	MP2A	X	-6.565	1.25
29	MP2A	Z	-3.79	1.25
30	MP2A	Mx	.0033	1.25
31	MP2A	X	-9.237	2
32	MP2A	Z	-5.333	2
33	MP2A	Mx	-.0046	2
34	MP1A	X	-9.346	2
35	MP1A	Z	-5.396	2
36	MP1A	Mx	-.0047	2
37	MP4A	X	-9.346	2
38	MP4A	Z	-5.396	2
39	MP4A	Mx	-.0047	2
40	MP2A	X	-6.572	3.5
41	MP2A	Z	-3.794	3.5
42	MP2A	Mx	.0033	3.5
43	MP3A	X	-9.237	2
44	MP3A	Z	-5.333	2
45	MP3A	Mx	-.0046	2

Member Point Loads (BLC 26 : Antenna Wi (330 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft. %]
1	MP1A	X	-20.51	.5
2	MP1A	Z	-35.524	.5
3	MP1A	Mx	.0401	.5
4	MP1A	X	-20.51	3.5
5	MP1A	Z	-35.524	3.5
6	MP1A	Mx	.0401	3.5
7	MP1A	X	-20.51	.5
8	MP1A	Z	-35.524	.5
9	MP1A	Mx	-.0348	.5
10	MP1A	X	-20.51	3.5
11	MP1A	Z	-35.524	3.5
12	MP1A	Mx	-.0348	3.5
13	MP4A	X	-15.289	.5
14	MP4A	Z	-26.481	.5
15	MP4A	Mx	.0349	.5
16	MP4A	X	-15.289	3.5



Member Point Loads (BLC 26 : Antenna Wi (330 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft. %]
17	MP4A	Z	-26.481	3.5
18	MP4A	Mx	.0349	3.5
19	MP4A	X	-15.289	.5
20	MP4A	Z	-26.481	.5
21	MP4A	Mx	.0027	.5
22	MP4A	X	-15.289	3.5
23	MP4A	Z	-26.481	3.5
24	MP4A	Mx	.0027	3.5
25	MP2A	X	-5.719	.25
26	MP2A	Z	-9.906	.25
27	MP2A	Mx	.0029	.25
28	MP2A	X	-5.719	1.25
29	MP2A	Z	-9.906	1.25
30	MP2A	Mx	.0029	1.25
31	MP2A	X	-6.383	2
32	MP2A	Z	-11.055	2
33	MP2A	Mx	-.0032	2
34	MP1A	X	-6.404	2
35	MP1A	Z	-11.092	2
36	MP1A	Mx	-.0032	2
37	MP4A	X	-6.404	2
38	MP4A	Z	-11.092	2
39	MP4A	Mx	-.0032	2
40	MP2A	X	-5.124	3.5
41	MP2A	Z	-8.875	3.5
42	MP2A	Mx	.0026	3.5
43	MP3A	X	-6.383	2
44	MP3A	Z	-11.055	2
45	MP3A	Mx	-.0032	2

Member Point Loads (BLC 27 : Antenna Wm (0 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft. %]
1	MP1A	X	0	.5
2	MP1A	Z	-7.262	.5
3	MP1A	Mx	.0037	.5
4	MP1A	X	0	3.5
5	MP1A	Z	-7.262	3.5
6	MP1A	Mx	.0037	3.5
7	MP1A	X	0	.5
8	MP1A	Z	-7.262	.5
9	MP1A	Mx	-.0083	.5
10	MP1A	X	0	3.5
11	MP1A	Z	-7.262	3.5
12	MP1A	Mx	-.0083	3.5
13	MP4A	X	0	.5
14	MP4A	Z	-7.262	.5
15	MP4A	Mx	.0083	.5
16	MP4A	X	0	3.5
17	MP4A	Z	-7.262	3.5
18	MP4A	Mx	.0083	3.5
19	MP4A	X	0	.5
20	MP4A	Z	-7.262	.5
21	MP4A	Mx	-.0037	.5
22	MP4A	X	0	3.5
23	MP4A	Z	-7.262	3.5
24	MP4A	Mx	-.0037	3.5



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 21777772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Point Loads (BLC 27 : Antenna Wm (0 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
25	MP2A	X	0	.25
26	MP2A	Z	-4.202	.25
27	MP2A	Mx	0	.25
28	MP2A	X	0	1.25
29	MP2A	Z	-4.202	1.25
30	MP2A	Mx	0	1.25
31	MP2A	X	0	2
32	MP2A	Z	-3.437	2
33	MP2A	Mx	0	2
34	MP1A	X	0	2
35	MP1A	Z	-4.147	2
36	MP1A	Mx	0	2
37	MP4A	X	0	2
38	MP4A	Z	-4.147	2
39	MP4A	Mx	0	2
40	MP2A	X	0	3.5
41	MP2A	Z	-3.393	3.5
42	MP2A	Mx	0	3.5
43	MP3A	X	0	2
44	MP3A	Z	-3.437	2
45	MP3A	Mx	0	2

Member Point Loads (BLC 28 : Antenna Wm (30 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
1	MP1A	X	2.637	.5
2	MP1A	Z	-4.568	.5
3	MP1A	Mx	-.000467	.5
4	MP1A	X	2.637	3.5
5	MP1A	Z	-4.568	3.5
6	MP1A	Mx	-.000467	3.5
7	MP1A	X	2.637	.5
8	MP1A	Z	-4.568	.5
9	MP1A	Mx	-.006	.5
10	MP1A	X	2.637	3.5
11	MP1A	Z	-4.568	3.5
12	MP1A	Mx	-.006	3.5
13	MP4A	X	3.976	.5
14	MP4A	Z	-6.887	.5
15	MP4A	Mx	.0067	.5
16	MP4A	X	3.976	3.5
17	MP4A	Z	-6.887	3.5
18	MP4A	Mx	.0067	3.5
19	MP4A	X	3.976	.5
20	MP4A	Z	-6.887	.5
21	MP4A	Mx	-.0078	.5
22	MP4A	X	3.976	3.5
23	MP4A	Z	-6.887	3.5
24	MP4A	Mx	-.0078	3.5
25	MP2A	X	1.778	.25
26	MP2A	Z	-3.08	.25
27	MP2A	Mx	-.000889	.25
28	MP2A	X	1.778	1.25
29	MP2A	Z	-3.08	1.25
30	MP2A	Mx	-.000889	1.25
31	MP2A	X	1.577	2
32	MP2A	Z	-2.732	2



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 21777772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Point Loads (BLC 28 : Antenna Wm (30 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
33	MP2A	Mx	.000788	2
34	MP1A	X	1.908	2
35	MP1A	Z	-3.305	2
36	MP1A	Mx	.000954	2
37	MP4A	X	1.908	2
38	MP4A	Z	-3.305	2
39	MP4A	Mx	.000954	2
40	MP2A	X	1.481	3.5
41	MP2A	Z	-2.566	3.5
42	MP2A	Mx	-.00074	3.5
43	MP3A	X	1.577	2
44	MP3A	Z	-2.732	2
45	MP3A	Mx	.000788	2

Member Point Loads (BLC 29 : Antenna Wm (60 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
1	MP1A	X	3.445	.5
2	MP1A	Z	-1.989	.5
3	MP1A	Mx	-.0027	.5
4	MP1A	X	3.445	3.5
5	MP1A	Z	-1.989	3.5
6	MP1A	Mx	-.0027	3.5
7	MP1A	X	3.445	.5
8	MP1A	Z	-1.989	.5
9	MP1A	Mx	-.0033	.5
10	MP1A	X	3.445	3.5
11	MP1A	Z	-1.989	3.5
12	MP1A	Mx	-.0033	3.5
13	MP4A	X	5.763	.5
14	MP4A	Z	-3.328	.5
15	MP4A	Mx	.0021	.5
16	MP4A	X	5.763	3.5
17	MP4A	Z	-3.328	3.5
18	MP4A	Mx	.0021	3.5
19	MP4A	X	5.763	.5
20	MP4A	Z	-3.328	.5
21	MP4A	Mx	-.0079	.5
22	MP4A	X	5.763	3.5
23	MP4A	Z	-3.328	3.5
24	MP4A	Mx	-.0079	3.5
25	MP2A	X	1.961	.25
26	MP2A	Z	-1.132	.25
27	MP2A	Mx	-.00098	.25
28	MP2A	X	1.961	1.25
29	MP2A	Z	-1.132	1.25
30	MP2A	Mx	-.00098	1.25
31	MP2A	X	2.242	2
32	MP2A	Z	-1.294	2
33	MP2A	Mx	.0011	2
34	MP1A	X	2.734	2
35	MP1A	Z	-1.579	2
36	MP1A	Mx	.0014	2
37	MP4A	X	2.734	2
38	MP4A	Z	-1.579	2
39	MP4A	Mx	.0014	2
40	MP2A	X	1.822	3.5



Member Point Loads (BLC 29 : Antenna Wm (60 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
41	MP2A	Z	-1.052	3.5
42	MP2A	Mx	-.000911	3.5
43	MP3A	X	2.242	2
44	MP3A	Z	-1.294	2
45	MP3A	Mx	.0011	2

Member Point Loads (BLC 30 : Antenna Wm (90 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
1	MP1A	X	4.668	.5
2	MP1A	Z	0	.5
3	MP1A	Mx	-.005	.5
4	MP1A	X	4.668	3.5
5	MP1A	Z	0	3.5
6	MP1A	Mx	-.005	3.5
7	MP1A	X	4.668	.5
8	MP1A	Z	0	.5
9	MP1A	Mx	-.0014	.5
10	MP1A	X	4.668	3.5
11	MP1A	Z	0	3.5
12	MP1A	Mx	-.0014	3.5
13	MP4A	X	4.668	.5
14	MP4A	Z	0	.5
15	MP4A	Mx	-.0014	.5
16	MP4A	X	4.668	3.5
17	MP4A	Z	0	3.5
18	MP4A	Mx	-.0014	3.5
19	MP4A	X	4.668	.5
20	MP4A	Z	0	.5
21	MP4A	Mx	-.005	.5
22	MP4A	X	4.668	3.5
23	MP4A	Z	0	3.5
24	MP4A	Mx	-.005	3.5
25	MP2A	X	1.618	.25
26	MP2A	Z	0	.25
27	MP2A	Mx	-.000809	.25
28	MP2A	X	1.618	1.25
29	MP2A	Z	0	1.25
30	MP2A	Mx	-.000809	1.25
31	MP2A	X	2.306	2
32	MP2A	Z	0	2
33	MP2A	Mx	.0012	2
34	MP1A	X	2.827	2
35	MP1A	Z	0	2
36	MP1A	Mx	.0014	2
37	MP4A	X	2.827	2
38	MP4A	Z	0	2
39	MP4A	Mx	.0014	2
40	MP2A	X	1.674	3.5
41	MP2A	Z	0	3.5
42	MP2A	Mx	-.000837	3.5
43	MP3A	X	2.306	2
44	MP3A	Z	0	2
45	MP3A	Mx	.0012	2

Member Point Loads (BLC 31 : Antenna Wm (120 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
--	--------------	-----------	--------------------	----------------



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 21777772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Point Loads (BLC 31 : Antenna Wm (120 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
1	MP1A	X	5.763	.5
2	MP1A	Z	3.328	.5
3	MP1A	Mx	-.0079	.5
4	MP1A	X	5.763	3.5
5	MP1A	Z	3.328	3.5
6	MP1A	Mx	-.0079	3.5
7	MP1A	X	5.763	.5
8	MP1A	Z	3.328	.5
9	MP1A	Mx	.0021	.5
10	MP1A	X	5.763	3.5
11	MP1A	Z	3.328	3.5
12	MP1A	Mx	.0021	3.5
13	MP4A	X	3.445	.5
14	MP4A	Z	1.989	.5
15	MP4A	Mx	-.0033	.5
16	MP4A	X	3.445	3.5
17	MP4A	Z	1.989	3.5
18	MP4A	Mx	-.0033	3.5
19	MP4A	X	3.445	.5
20	MP4A	Z	1.989	.5
21	MP4A	Mx	-.0027	.5
22	MP4A	X	3.445	3.5
23	MP4A	Z	1.989	3.5
24	MP4A	Mx	-.0027	3.5
25	MP2A	X	1.961	.25
26	MP2A	Z	1.132	.25
27	MP2A	Mx	-.00098	.25
28	MP2A	X	1.961	1.25
29	MP2A	Z	1.132	1.25
30	MP2A	Mx	-.00098	1.25
31	MP2A	X	2.242	2
32	MP2A	Z	1.294	2
33	MP2A	Mx	.0011	2
34	MP1A	X	2.734	2
35	MP1A	Z	1.579	2
36	MP1A	Mx	.0014	2
37	MP4A	X	2.734	2
38	MP4A	Z	1.579	2
39	MP4A	Mx	.0014	2
40	MP2A	X	1.822	3.5
41	MP2A	Z	1.052	3.5
42	MP2A	Mx	-.000911	3.5
43	MP3A	X	2.242	2
44	MP3A	Z	1.294	2
45	MP3A	Mx	.0011	2

Member Point Loads (BLC 32 : Antenna Wm (150 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
1	MP1A	X	3.976	.5
2	MP1A	Z	6.887	.5
3	MP1A	Mx	-.0078	.5
4	MP1A	X	3.976	3.5
5	MP1A	Z	6.887	3.5
6	MP1A	Mx	-.0078	3.5
7	MP1A	X	3.976	.5
8	MP1A	Z	6.887	.5



Member Point Loads (BLC 32 : Antenna Wm (150 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft. %]
9	MP1A	Mx	.0067	.5
10	MP1A	X	3.976	3.5
11	MP1A	Z	6.887	3.5
12	MP1A	Mx	.0067	3.5
13	MP4A	X	2.637	.5
14	MP4A	Z	4.568	.5
15	MP4A	Mx	-.006	.5
16	MP4A	X	2.637	3.5
17	MP4A	Z	4.568	3.5
18	MP4A	Mx	-.006	3.5
19	MP4A	X	2.637	.5
20	MP4A	Z	4.568	.5
21	MP4A	Mx	-.000467	.5
22	MP4A	X	2.637	3.5
23	MP4A	Z	4.568	3.5
24	MP4A	Mx	-.000467	3.5
25	MP2A	X	1.778	.25
26	MP2A	Z	3.08	.25
27	MP2A	Mx	-.000889	.25
28	MP2A	X	1.778	1.25
29	MP2A	Z	3.08	1.25
30	MP2A	Mx	-.000889	1.25
31	MP2A	X	1.577	2
32	MP2A	Z	2.732	2
33	MP2A	Mx	.000788	2
34	MP1A	X	1.908	2
35	MP1A	Z	3.305	2
36	MP1A	Mx	.000954	2
37	MP4A	X	1.908	2
38	MP4A	Z	3.305	2
39	MP4A	Mx	.000954	2
40	MP2A	X	1.481	3.5
41	MP2A	Z	2.566	3.5
42	MP2A	Mx	-.00074	3.5
43	MP3A	X	1.577	2
44	MP3A	Z	2.732	2
45	MP3A	Mx	.000788	2

Member Point Loads (BLC 33 : Antenna Wm (180 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft. %]
1	MP1A	X	0	.5
2	MP1A	Z	7.262	.5
3	MP1A	Mx	-.0037	.5
4	MP1A	X	0	3.5
5	MP1A	Z	7.262	3.5
6	MP1A	Mx	-.0037	3.5
7	MP1A	X	0	.5
8	MP1A	Z	7.262	.5
9	MP1A	Mx	.0083	.5
10	MP1A	X	0	3.5
11	MP1A	Z	7.262	3.5
12	MP1A	Mx	.0083	3.5
13	MP4A	X	0	.5
14	MP4A	Z	7.262	.5
15	MP4A	Mx	-.0083	.5
16	MP4A	X	0	3.5



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 21777772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Point Loads (BLC 33 : Antenna Wm (180 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb,k-ft]	Location[ft, %]
17	MP4A	Z	7.262	3.5
18	MP4A	Mx	-.0083	3.5
19	MP4A	X	0	.5
20	MP4A	Z	7.262	.5
21	MP4A	Mx	.0037	.5
22	MP4A	X	0	3.5
23	MP4A	Z	7.262	3.5
24	MP4A	Mx	.0037	3.5
25	MP2A	X	0	.25
26	MP2A	Z	4.202	.25
27	MP2A	Mx	0	.25
28	MP2A	X	0	1.25
29	MP2A	Z	4.202	1.25
30	MP2A	Mx	0	1.25
31	MP2A	X	0	2
32	MP2A	Z	3.437	2
33	MP2A	Mx	0	2
34	MP1A	X	0	2
35	MP1A	Z	4.147	2
36	MP1A	Mx	0	2
37	MP4A	X	0	2
38	MP4A	Z	4.147	2
39	MP4A	Mx	0	2
40	MP2A	X	0	3.5
41	MP2A	Z	3.393	3.5
42	MP2A	Mx	0	3.5
43	MP3A	X	0	2
44	MP3A	Z	3.437	2
45	MP3A	Mx	0	2

Member Point Loads (BLC 34 : Antenna Wm (210 Deg))

	Member Label	Direction	Magnitude[lb,k-ft]	Location[ft, %]
1	MP1A	X	-2.637	.5
2	MP1A	Z	4.568	.5
3	MP1A	Mx	.000467	.5
4	MP1A	X	-2.637	3.5
5	MP1A	Z	4.568	3.5
6	MP1A	Mx	.000467	3.5
7	MP1A	X	-2.637	.5
8	MP1A	Z	4.568	.5
9	MP1A	Mx	.006	.5
10	MP1A	X	-2.637	3.5
11	MP1A	Z	4.568	3.5
12	MP1A	Mx	.006	3.5
13	MP4A	X	-3.976	.5
14	MP4A	Z	6.887	.5
15	MP4A	Mx	-.0067	.5
16	MP4A	X	-3.976	3.5
17	MP4A	Z	6.887	3.5
18	MP4A	Mx	-.0067	3.5
19	MP4A	X	-3.976	.5
20	MP4A	Z	6.887	.5
21	MP4A	Mx	.0078	.5
22	MP4A	X	-3.976	3.5
23	MP4A	Z	6.887	3.5
24	MP4A	Mx	.0078	3.5



Member Point Loads (BLC 34 : Antenna Wm (210 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
25	MP2A	X	-1.778	.25
26	MP2A	Z	3.08	.25
27	MP2A	Mx	.000889	.25
28	MP2A	X	-1.778	1.25
29	MP2A	Z	3.08	1.25
30	MP2A	Mx	.000889	1.25
31	MP2A	X	-1.577	2
32	MP2A	Z	2.732	2
33	MP2A	Mx	-.000788	2
34	MP1A	X	-1.908	2
35	MP1A	Z	3.305	2
36	MP1A	Mx	-.000954	2
37	MP4A	X	-1.908	2
38	MP4A	Z	3.305	2
39	MP4A	Mx	-.000954	2
40	MP2A	X	-1.481	3.5
41	MP2A	Z	2.566	3.5
42	MP2A	Mx	.00074	3.5
43	MP3A	X	-1.577	2
44	MP3A	Z	2.732	2
45	MP3A	Mx	-.000788	2

Member Point Loads (BLC 35 : Antenna Wm (240 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
1	MP1A	X	-3.445	.5
2	MP1A	Z	1.989	.5
3	MP1A	Mx	.0027	.5
4	MP1A	X	-3.445	3.5
5	MP1A	Z	1.989	3.5
6	MP1A	Mx	.0027	3.5
7	MP1A	X	-3.445	.5
8	MP1A	Z	1.989	.5
9	MP1A	Mx	.0033	.5
10	MP1A	X	-3.445	3.5
11	MP1A	Z	1.989	3.5
12	MP1A	Mx	.0033	3.5
13	MP4A	X	-5.763	.5
14	MP4A	Z	3.328	.5
15	MP4A	Mx	-.0021	.5
16	MP4A	X	-5.763	3.5
17	MP4A	Z	3.328	3.5
18	MP4A	Mx	-.0021	3.5
19	MP4A	X	-5.763	.5
20	MP4A	Z	3.328	.5
21	MP4A	Mx	.0079	.5
22	MP4A	X	-5.763	3.5
23	MP4A	Z	3.328	3.5
24	MP4A	Mx	.0079	3.5
25	MP2A	X	-1.961	.25
26	MP2A	Z	1.132	.25
27	MP2A	Mx	.00098	.25
28	MP2A	X	-1.961	1.25
29	MP2A	Z	1.132	1.25
30	MP2A	Mx	.00098	1.25
31	MP2A	X	-2.242	2
32	MP2A	Z	1.294	2



Member Point Loads (BLC 35 : Antenna Wm (240 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
33	MP2A	Mx	-.0011	2
34	MP1A	X	-2.734	2
35	MP1A	Z	1.579	2
36	MP1A	Mx	-.0014	2
37	MP4A	X	-2.734	2
38	MP4A	Z	1.579	2
39	MP4A	Mx	-.0014	2
40	MP2A	X	-1.822	3.5
41	MP2A	Z	1.052	3.5
42	MP2A	Mx	.000911	3.5
43	MP3A	X	-2.242	2
44	MP3A	Z	1.294	2
45	MP3A	Mx	-.0011	2

Member Point Loads (BLC 36 : Antenna Wm (270 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
1	MP1A	X	-4.668	.5
2	MP1A	Z	0	.5
3	MP1A	Mx	.005	.5
4	MP1A	X	-4.668	3.5
5	MP1A	Z	0	3.5
6	MP1A	Mx	.005	3.5
7	MP1A	X	-4.668	.5
8	MP1A	Z	0	.5
9	MP1A	Mx	.0014	.5
10	MP1A	X	-4.668	3.5
11	MP1A	Z	0	3.5
12	MP1A	Mx	.0014	3.5
13	MP4A	X	-4.668	.5
14	MP4A	Z	0	.5
15	MP4A	Mx	.0014	.5
16	MP4A	X	-4.668	3.5
17	MP4A	Z	0	3.5
18	MP4A	Mx	.0014	3.5
19	MP4A	X	-4.668	.5
20	MP4A	Z	0	.5
21	MP4A	Mx	.005	.5
22	MP4A	X	-4.668	3.5
23	MP4A	Z	0	3.5
24	MP4A	Mx	.005	3.5
25	MP2A	X	-1.618	.25
26	MP2A	Z	0	.25
27	MP2A	Mx	.000809	.25
28	MP2A	X	-1.618	1.25
29	MP2A	Z	0	1.25
30	MP2A	Mx	.000809	1.25
31	MP2A	X	-2.306	2
32	MP2A	Z	0	2
33	MP2A	Mx	-.0012	2
34	MP1A	X	-2.827	2
35	MP1A	Z	0	2
36	MP1A	Mx	-.0014	2
37	MP4A	X	-2.827	2
38	MP4A	Z	0	2
39	MP4A	Mx	-.0014	2
40	MP2A	X	-1.674	3.5



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 21777772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Point Loads (BLC 36 : Antenna Wm (270 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb,k-ft]	Location[ft,%]
41	MP2A	Z	0	3.5
42	MP2A	Mx	.000837	3.5
43	MP3A	X	-2.306	2
44	MP3A	Z	0	2
45	MP3A	Mx	-.0012	2

Member Point Loads (BLC 37 : Antenna Wm (300 Deg))

	Member Label	Direction	Magnitude[lb,k-ft]	Location[ft,%]
1	MP1A	X	-5.763	.5
2	MP1A	Z	-3.328	.5
3	MP1A	Mx	.0079	.5
4	MP1A	X	-5.763	3.5
5	MP1A	Z	-3.328	3.5
6	MP1A	Mx	.0079	3.5
7	MP1A	X	-5.763	.5
8	MP1A	Z	-3.328	.5
9	MP1A	Mx	-.0021	.5
10	MP1A	X	-5.763	3.5
11	MP1A	Z	-3.328	3.5
12	MP1A	Mx	-.0021	3.5
13	MP4A	X	-3.445	.5
14	MP4A	Z	-1.989	.5
15	MP4A	Mx	.0033	.5
16	MP4A	X	-3.445	3.5
17	MP4A	Z	-1.989	3.5
18	MP4A	Mx	.0033	3.5
19	MP4A	X	-3.445	.5
20	MP4A	Z	-1.989	.5
21	MP4A	Mx	.0027	.5
22	MP4A	X	-3.445	3.5
23	MP4A	Z	-1.989	3.5
24	MP4A	Mx	.0027	3.5
25	MP2A	X	-1.961	.25
26	MP2A	Z	-1.132	.25
27	MP2A	Mx	.00098	.25
28	MP2A	X	-1.961	1.25
29	MP2A	Z	-1.132	1.25
30	MP2A	Mx	.00098	1.25
31	MP2A	X	-2.242	2
32	MP2A	Z	-1.294	2
33	MP2A	Mx	-.0011	2
34	MP1A	X	-2.734	2
35	MP1A	Z	-1.579	2
36	MP1A	Mx	-.0014	2
37	MP4A	X	-2.734	2
38	MP4A	Z	-1.579	2
39	MP4A	Mx	-.0014	2
40	MP2A	X	-1.822	3.5
41	MP2A	Z	-1.052	3.5
42	MP2A	Mx	.000911	3.5
43	MP3A	X	-2.242	2
44	MP3A	Z	-1.294	2
45	MP3A	Mx	-.0011	2

Member Point Loads (BLC 38 : Antenna Wm (330 Deg))

	Member Label	Direction	Magnitude[lb,k-ft]	Location[ft,%]
--	--------------	-----------	--------------------	----------------



Member Point Loads (BLC 38 : Antenna Wm (330 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft. %]
1	MP1A	X	-3.976	.5
2	MP1A	Z	-6.887	.5
3	MP1A	Mx	.0078	.5
4	MP1A	X	-3.976	3.5
5	MP1A	Z	-6.887	3.5
6	MP1A	Mx	.0078	3.5
7	MP1A	X	-3.976	.5
8	MP1A	Z	-6.887	.5
9	MP1A	Mx	-.0067	.5
10	MP1A	X	-3.976	3.5
11	MP1A	Z	-6.887	3.5
12	MP1A	Mx	-.0067	3.5
13	MP4A	X	-2.637	.5
14	MP4A	Z	-4.568	.5
15	MP4A	Mx	.006	.5
16	MP4A	X	-2.637	3.5
17	MP4A	Z	-4.568	3.5
18	MP4A	Mx	.006	3.5
19	MP4A	X	-2.637	.5
20	MP4A	Z	-4.568	.5
21	MP4A	Mx	.000467	.5
22	MP4A	X	-2.637	3.5
23	MP4A	Z	-4.568	3.5
24	MP4A	Mx	.000467	3.5
25	MP2A	X	-1.778	.25
26	MP2A	Z	-3.08	.25
27	MP2A	Mx	.000889	.25
28	MP2A	X	-1.778	1.25
29	MP2A	Z	-3.08	1.25
30	MP2A	Mx	.000889	1.25
31	MP2A	X	-1.577	2
32	MP2A	Z	-2.732	2
33	MP2A	Mx	-.000788	2
34	MP1A	X	-1.908	2
35	MP1A	Z	-3.305	2
36	MP1A	Mx	-.000954	2
37	MP4A	X	-1.908	2
38	MP4A	Z	-3.305	2
39	MP4A	Mx	-.000954	2
40	MP2A	X	-1.481	3.5
41	MP2A	Z	-2.566	3.5
42	MP2A	Mx	.00074	3.5
43	MP3A	X	-1.577	2
44	MP3A	Z	-2.732	2
45	MP3A	Mx	-.000788	2

Member Point Loads (BLC 77 : Lm1)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft. %]
1	M38	Y	-500	0

Member Point Loads (BLC 78 : Lm2)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft. %]
1	M48	Y	-500	0

Member Point Loads (BLC 79 : Lv1)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft. %]
--	--------------	-----------	--------------------	-----------------



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 2177772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Point Loads (BLC 79 : Lv1) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
1	M10	Y	-250	%50

Member Point Loads (BLC 80 : Lv2)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
1	M10	Y	-250	0

Member Point Loads (BLC 81 : Antenna Ev)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
1	MP1A	Y	-2.153	.5
2	MP1A	My	-.0023	.5
3	MP1A	Mz	-.0011	.5
4	MP1A	Y	-2.153	3.5
5	MP1A	My	-.0023	3.5
6	MP1A	Mz	-.0011	3.5
7	MP1A	Y	-2.153	.5
8	MP1A	My	-.000629	.5
9	MP1A	Mz	.0025	.5
10	MP1A	Y	-2.153	3.5
11	MP1A	My	-.000629	3.5
12	MP1A	Mz	.0025	3.5
13	MP4A	Y	-2.153	.5
14	MP4A	My	-.000629	.5
15	MP4A	Mz	-.0025	.5
16	MP4A	Y	-2.153	3.5
17	MP4A	My	-.000629	3.5
18	MP4A	Mz	-.0025	3.5
19	MP4A	Y	-2.153	.5
20	MP4A	My	-.0023	.5
21	MP4A	Mz	.0011	.5
22	MP4A	Y	-2.153	3.5
23	MP4A	My	-.0023	3.5
24	MP4A	Mz	.0011	3.5
25	MP2A	Y	-1.418	.25
26	MP2A	My	-.000709	.25
27	MP2A	Mz	0	.25
28	MP2A	Y	-1.418	1.25
29	MP2A	My	-.000709	1.25
30	MP2A	Mz	0	1.25
31	MP2A	Y	-3.6972	2
32	MP2A	My	.0018	2
33	MP2A	Mz	0	2
34	MP1A	Y	-3.9149	2
35	MP1A	My	.002	2
36	MP1A	Mz	0	2
37	MP4A	Y	-3.9149	2
38	MP4A	My	.002	2
39	MP4A	Mz	0	2
40	MP2A	Y	-1.1482	3.5
41	MP2A	My	-.000574	3.5
42	MP2A	Mz	0	3.5
43	MP3A	Y	-4.1772	2
44	MP3A	My	.0021	2
45	MP3A	Mz	0	2

Member Point Loads (BLC 82 : Antenna Eh (0 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
--	--------------	-----------	--------------------	----------------



Member Point Loads (BLC 82 : Antenna Eh (0 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft. %]
1	MP1A	Z	-5.3824	.5
2	MP1A	Mx	.0028	.5
3	MP1A	Z	-5.3824	3.5
4	MP1A	Mx	.0028	3.5
5	MP1A	Z	-5.3824	.5
6	MP1A	Mx	-.0062	.5
7	MP1A	Z	-5.3824	3.5
8	MP1A	Mx	-.0062	3.5
9	MP4A	Z	-5.3824	.5
10	MP4A	Mx	.0062	.5
11	MP4A	Z	-5.3824	3.5
12	MP4A	Mx	.0062	3.5
13	MP4A	Z	-5.3824	.5
14	MP4A	Mx	-.0028	.5
15	MP4A	Z	-5.3824	3.5
16	MP4A	Mx	-.0028	3.5
17	MP2A	Z	-3.545	.25
18	MP2A	Mx	0	.25
19	MP2A	Z	-3.545	1.25
20	MP2A	Mx	0	1.25
21	MP2A	Z	-9.2429	2
22	MP2A	Mx	0	2
23	MP1A	Z	-9.7873	2
24	MP1A	Mx	0	2
25	MP4A	Z	-9.7873	2
26	MP4A	Mx	0	2
27	MP2A	Z	-2.8706	3.5
28	MP2A	Mx	0	3.5
29	MP3A	Z	-10.4431	2
30	MP3A	Mx	0	2

Member Point Loads (BLC 83 : Antenna Eh (90 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft. %]
1	MP1A	X	5.3824	.5
2	MP1A	Mx	-.0057	.5
3	MP1A	X	5.3824	3.5
4	MP1A	Mx	-.0057	3.5
5	MP1A	X	5.3824	.5
6	MP1A	Mx	-.0016	.5
7	MP1A	X	5.3824	3.5
8	MP1A	Mx	-.0016	3.5
9	MP4A	X	5.3824	.5
10	MP4A	Mx	-.0016	.5
11	MP4A	X	5.3824	3.5
12	MP4A	Mx	-.0016	3.5
13	MP4A	X	5.3824	.5
14	MP4A	Mx	-.0057	.5
15	MP4A	X	5.3824	3.5
16	MP4A	Mx	-.0057	3.5
17	MP2A	X	3.545	.25
18	MP2A	Mx	-.0018	.25
19	MP2A	X	3.545	1.25
20	MP2A	Mx	-.0018	1.25
21	MP2A	X	9.2429	2
22	MP2A	Mx	.0046	2
23	MP1A	X	9.7873	2



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 2177772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Point Loads (BLC 83 : Antenna Eh (90 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
24	MP1A	Mx	.0049	2
25	MP4A	X	9.7873	2
26	MP4A	Mx	.0049	2
27	MP2A	X	2.8706	3.5
28	MP2A	Mx	-.0014	3.5
29	MP3A	X	10.4431	2
30	MP3A	Mx	.0052	2

Member Distributed Loads (BLC 40 : Structure Di)

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location[ft.]	End Location[ft.]
1	M1	Y	-8.822	-8.822	0	%100
2	M3	Y	-8.822	-8.822	0	%100
3	M5	Y	-5.9959	-5.9959	0	%100
4	M6	Y	-5.9959	-5.9959	0	%100
5	M7	Y	-5.7838	-5.7838	0	%100
6	M8	Y	-5.9959	-5.9959	0	%100
7	M9	Y	-5.9959	-5.9959	0	%100
8	M10	Y	-5.7838	-5.7838	0	%100
9	M11	Y	-5.0689	-5.0689	0	%100
10	M12	Y	-5.0689	-5.0689	0	%100
11	M13	Y	-5.0689	-5.0689	0	%100
12	M14	Y	-5.0689	-5.0689	0	%100
13	M15	Y	-5.9959	-5.9959	0	%100
14	M16	Y	-4.3898	-4.3898	0	%100
15	M17	Y	-5.9959	-5.9959	0	%100
16	M18	Y	-4.3898	-4.3898	0	%100
17	M19	Y	-5.9959	-5.9959	0	%100
18	M20	Y	-5.9959	-5.9959	0	%100
19	M21	Y	-5.9959	-5.9959	0	%100
20	M22	Y	-4.3898	-4.3898	0	%100
21	M23	Y	-4.3898	-4.3898	0	%100
22	M24	Y	-5.0689	-5.0689	0	%100
23	M25	Y	-5.9959	-5.9959	0	%100
24	M26	Y	-5.9959	-5.9959	0	%100
25	M27	Y	-4.3898	-4.3898	0	%100
26	M28	Y	-5.9959	-5.9959	0	%100
27	M29	Y	-4.3898	-4.3898	0	%100
28	M30	Y	-5.9959	-5.9959	0	%100
29	M31	Y	-5.9959	-5.9959	0	%100
30	M32	Y	-5.9959	-5.9959	0	%100
31	M33	Y	-4.3898	-4.3898	0	%100
32	M34	Y	-4.3898	-4.3898	0	%100
33	M35	Y	-5.0689	-5.0689	0	%100
34	M36	Y	-5.9959	-5.9959	0	%100
35	MP4A	Y	-5.0689	-5.0689	0	%100
36	MP3A	Y	-5.0689	-5.0689	0	%100
37	MP2A	Y	-5.0689	-5.0689	0	%100
38	MP1A	Y	-5.0689	-5.0689	0	%100
39	EQUIP	Y	-4.9589	-4.9589	0	%100
40	M51	Y	-4.9589	-4.9589	0	%100
41	M55A	Y	-5.0689	-5.0689	0	%100

Member Distributed Loads (BLC 41 : Structure Wo (0 Deg))

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location[ft.]	End Location[ft.]
1	M1	X	0	0	0	%100



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 21777772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Distributed Loads (BLC 41 : Structure Wo (0 Deg)) (Continued)

	Member Label	Direction	Start Magnitude	End Magnitude	Start Locationft	End Locationft
2	M1	Z	-10.6438	-10.6438	0	%100
3	M3	X	0	0	0	%100
4	M3	Z	-10.6438	-10.6438	0	%100
5	M5	X	0	0	0	%100
6	M5	Z	-6.526	-6.526	0	%100
7	M6	X	0	0	0	%100
8	M6	Z	-6.526	-6.526	0	%100
9	M7	X	0	0	0	%100
10	M7	Z	-10.2003	-10.2003	0	%100
11	M8	X	0	0	0	%100
12	M8	Z	-4.514	-4.514	0	%100
13	M9	X	0	0	0	%100
14	M9	Z	-7.772	-7.772	0	%100
15	M10	X	0	0	0	%100
16	M10	Z	-10.2003	-10.2003	0	%100
17	M11	X	0	0	0	%100
18	M11	Z	-4.1329	-4.1329	0	%100
19	M12	X	0	0	0	%100
20	M12	Z	-4.1329	-4.1329	0	%100
21	M13	X	0	0	0	%100
22	M13	Z	-4.1329	-4.1329	0	%100
23	M14	X	0	0	0	%100
24	M14	Z	-4.1329	-4.1329	0	%100
25	M15	X	0	0	0	%100
26	M15	Z	-1.4044	-1.4044	0	%100
27	M16	X	0	0	0	%100
28	M16	Z	-5.5957	-5.5957	0	%100
29	M17	X	0	0	0	%100
30	M17	Z	-1.4044	-1.4044	0	%100
31	M18	X	0	0	0	%100
32	M18	Z	-5.5957	-5.5957	0	%100
33	M19	X	0	0	0	%100
34	M19	Z	-1.8848	-1.8848	0	%100
35	M20	X	0	0	0	%100
36	M20	Z	-1.4044	-1.4044	0	%100
37	M21	X	0	0	0	%100
38	M21	Z	-1.4044	-1.4044	0	%100
39	M22	X	0	0	0	%100
40	M22	Z	-6.1169	-6.1169	0	%100
41	M23	X	0	0	0	%100
42	M23	Z	-6.1169	-6.1169	0	%100
43	M24	X	0	0	0	%100
44	M24	Z	-6.4306	-6.4306	0	%100
45	M25	X	0	0	0	%100
46	M25	Z	-1.8848	-1.8848	0	%100
47	M26	X	0	0	0	%100
48	M26	Z	-1.4044	-1.4044	0	%100
49	M27	X	0	0	0	%100
50	M27	Z	-5.5957	-5.5957	0	%100
51	M28	X	0	0	0	%100
52	M28	Z	-1.4044	-1.4044	0	%100
53	M29	X	0	0	0	%100
54	M29	Z	-5.5957	-5.5957	0	%100
55	M30	X	0	0	0	%100
56	M30	Z	-1.8848	-1.8848	0	%100
57	M31	X	0	0	0	%100
58	M31	Z	-1.4044	-1.4044	0	%100



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 2177772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Distributed Loads (BLC 41 : Structure Wo (0 Deg)) (Continued)

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location	End Location
59	M32	X	0	0	0	%100
60	M32	Z	-1.4044	-1.4044	0	%100
61	M33	X	0	0	0	%100
62	M33	Z	-6.1169	-6.1169	0	%100
63	M34	X	0	0	0	%100
64	M34	Z	-6.1169	-6.1169	0	%100
65	M35	X	0	0	0	%100
66	M35	Z	-6.4306	-6.4306	0	%100
67	M36	X	0	0	0	%100
68	M36	Z	-1.8848	-1.8848	0	%100
69	MP4A	X	0	0	0	%100
70	MP4A	Z	-8.4263	-8.4263	0	%100
71	MP3A	X	0	0	0	%100
72	MP3A	Z	-8.4263	-8.4263	0	%100
73	MP2A	X	0	0	0	%100
74	MP2A	Z	-8.4263	-8.4263	0	%100
75	MP1A	X	0	0	0	%100
76	MP1A	Z	-8.4263	-8.4263	0	%100
77	EQUIP	X	0	0	0	%100
78	EQUIP	Z	-9.609	-9.609	0	%100
79	M51	X	0	0	0	%100
80	M51	Z	-9.609	-9.609	0	%100
81	M55A	X	0	0	0	%100
82	M55A	Z	-2.0693	-2.0693	0	%100

Member Distributed Loads (BLC 42 : Structure Wo (30 Deg))

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location	End Location
1	M1	X	3.9914	3.9914	0	%100
2	M1	Z	-6.9133	-6.9133	0	%100
3	M3	X	3.9914	3.9914	0	%100
4	M3	Z	-6.9133	-6.9133	0	%100
5	M5	X	.0414	.0414	0	%100
6	M5	Z	-.0718	-.0718	0	%100
7	M6	X	.6175	.6175	0	%100
8	M6	Z	-1.0695	-1.0695	0	%100
9	M7	X	3.8251	3.8251	0	%100
10	M7	Z	-6.6253	-6.6253	0	%100
11	M8	X	.0064	.0064	0	%100
12	M8	Z	-.0111	-.0111	0	%100
13	M9	X	.6445	.6445	0	%100
14	M9	Z	-1.1164	-1.1164	0	%100
15	M10	X	3.8251	3.8251	0	%100
16	M10	Z	-6.6253	-6.6253	0	%100
17	M11	X	.2625	.2625	0	%100
18	M11	Z	-.4547	-.4547	0	%100
19	M12	X	3.9105	3.9105	0	%100
20	M12	Z	-6.7733	-6.7733	0	%100
21	M13	X	.2625	.2625	0	%100
22	M13	Z	-.4547	-.4547	0	%100
23	M14	X	3.9105	3.9105	0	%100
24	M14	Z	-6.7733	-6.7733	0	%100
25	M15	X	1.8571	1.8571	0	%100
26	M15	Z	-3.2166	-3.2166	0	%100
27	M16	X	3.2898	3.2898	0	%100
28	M16	Z	-5.6981	-5.6981	0	%100
29	M17	X	1.8571	1.8571	0	%100



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 21777772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Distributed Loads (BLC 42 : Structure Wo (30 Deg)) (Continued)

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location(ft)	End Location(ft)
30	M17	Z	-3.2166	-3.2166	0	%100
31	M18	X	3.2898	3.2898	0	%100
32	M18	Z	-5.6981	-5.6981	0	%100
33	M19	X	2.0373	2.0373	0	%100
34	M19	Z	-3.5287	-3.5287	0	%100
35	M20	X	1.8571	1.8571	0	%100
36	M20	Z	-3.2166	-3.2166	0	%100
37	M21	X	1.8571	1.8571	0	%100
38	M21	Z	-3.2166	-3.2166	0	%100
39	M22	X	3.0584	3.0584	0	%100
40	M22	Z	-5.2974	-5.2974	0	%100
41	M23	X	3.0584	3.0584	0	%100
42	M23	Z	-5.2974	-5.2974	0	%100
43	M24	X	3.2153	3.2153	0	%100
44	M24	Z	-5.5691	-5.5691	0	%100
45	M25	X	2.0373	2.0373	0	%100
46	M25	Z	-3.5287	-3.5287	0	%100
47	M26	X	1.8571	1.8571	0	%100
48	M26	Z	-3.2166	-3.2166	0	%100
49	M27	X	2.3166	2.3166	0	%100
50	M27	Z	-4.0125	-4.0125	0	%100
51	M28	X	1.8571	1.8571	0	%100
52	M28	Z	-3.2166	-3.2166	0	%100
53	M29	X	2.3166	2.3166	0	%100
54	M29	Z	-4.0125	-4.0125	0	%100
55	M30	X	2.0373	2.0373	0	%100
56	M30	Z	-3.5287	-3.5287	0	%100
57	M31	X	1.8571	1.8571	0	%100
58	M31	Z	-3.2166	-3.2166	0	%100
59	M32	X	1.8571	1.8571	0	%100
60	M32	Z	-3.2166	-3.2166	0	%100
61	M33	X	3.0584	3.0584	0	%100
62	M33	Z	-5.2974	-5.2974	0	%100
63	M34	X	3.0584	3.0584	0	%100
64	M34	Z	-5.2974	-5.2974	0	%100
65	M35	X	3.2153	3.2153	0	%100
66	M35	Z	-5.5691	-5.5691	0	%100
67	M36	X	2.0373	2.0373	0	%100
68	M36	Z	-3.5287	-3.5287	0	%100
69	MP4A	X	4.2132	4.2132	0	%100
70	MP4A	Z	-7.2974	-7.2974	0	%100
71	MP3A	X	4.2132	4.2132	0	%100
72	MP3A	Z	-7.2974	-7.2974	0	%100
73	MP2A	X	4.2132	4.2132	0	%100
74	MP2A	Z	-7.2974	-7.2974	0	%100
75	MP1A	X	4.2132	4.2132	0	%100
76	MP1A	Z	-7.2974	-7.2974	0	%100
77	EQUIP	X	4.8045	4.8045	0	%100
78	EQUIP	Z	-8.3216	-8.3216	0	%100
79	M51	X	4.8045	4.8045	0	%100
80	M51	Z	-8.3216	-8.3216	0	%100
81	M55A	X	.000111	.000111	0	%100
82	M55A	Z	-.000192	-.000192	0	%100

Member Distributed Loads (BLC 43 : Structure Wo (60 Deg))

Member Label Direction Start Magnitude...End Magnitude[...Start Location[ft...End Location[ft...



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 21777772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Distributed Loads (BLC 43 : Structure Wo (60 Deg)) (Continued)

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location[ft...]	End Location[ft...]
1	M1	X	2.3044	2.3044	0	%100
2	M1	Z	-1.3305	-1.3305	0	%100
3	M3	X	2.3044	2.3044	0	%100
4	M3	Z	-1.3305	-1.3305	0	%100
5	M5	X	.0828	.0828	0	%100
6	M5	Z	-.0478	-.0478	0	%100
7	M6	X	1.0804	1.0804	0	%100
8	M6	Z	-.6238	-.6238	0	%100
9	M7	X	2.2084	2.2084	0	%100
10	M7	Z	-1.275	-1.275	0	%100
11	M8	X	.1962	.1962	0	%100
12	M8	Z	-.1133	-.1133	0	%100
13	M9	X	1.0195	1.0195	0	%100
14	M9	Z	-.5886	-.5886	0	%100
15	M10	X	2.2084	2.2084	0	%100
16	M10	Z	-1.275	-1.275	0	%100
17	M11	X	.5242	.5242	0	%100
18	M11	Z	-.3026	-.3026	0	%100
19	M12	X	6.8427	6.8427	0	%100
20	M12	Z	-3.9507	-3.9507	0	%100
21	M13	X	.5242	.5242	0	%100
22	M13	Z	-.3026	-.3026	0	%100
23	M14	X	6.8427	6.8427	0	%100
24	M14	Z	-3.9507	-3.9507	0	%100
25	M15	X	7.2174	7.2174	0	%100
26	M15	Z	-4.167	-4.167	0	%100
27	M16	X	5.7166	5.7166	0	%100
28	M16	Z	-3.3005	-3.3005	0	%100
29	M17	X	7.2174	7.2174	0	%100
30	M17	Z	-4.167	-4.167	0	%100
31	M18	X	5.7166	5.7166	0	%100
32	M18	Z	-3.3005	-3.3005	0	%100
33	M19	X	7.3214	7.3214	0	%100
34	M19	Z	-4.227	-4.227	0	%100
35	M20	X	7.2174	7.2174	0	%100
36	M20	Z	-4.167	-4.167	0	%100
37	M21	X	7.2174	7.2174	0	%100
38	M21	Z	-4.167	-4.167	0	%100
39	M22	X	5.2974	5.2974	0	%100
40	M22	Z	-3.0584	-3.0584	0	%100
41	M23	X	5.2974	5.2974	0	%100
42	M23	Z	-3.0584	-3.0584	0	%100
43	M24	X	5.5691	5.5691	0	%100
44	M24	Z	-3.2153	-3.2153	0	%100
45	M25	X	7.3214	7.3214	0	%100
46	M25	Z	-4.227	-4.227	0	%100
47	M26	X	7.2174	7.2174	0	%100
48	M26	Z	-4.167	-4.167	0	%100
49	M27	X	4.031	4.031	0	%100
50	M27	Z	-2.3273	-2.3273	0	%100
51	M28	X	7.2174	7.2174	0	%100
52	M28	Z	-4.167	-4.167	0	%100
53	M29	X	4.031	4.031	0	%100
54	M29	Z	-2.3273	-2.3273	0	%100
55	M30	X	7.3214	7.3214	0	%100
56	M30	Z	-4.227	-4.227	0	%100
57	M31	X	7.2174	7.2174	0	%100



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 21777772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Distributed Loads (BLC 43 : Structure Wo (60 Deg)) (Continued)

	Member Label	Direction	Start Magnitude	End Magnitude	Start Locationft	End Locationft
58	M31	Z	-4.167	-4.167	0	%100
59	M32	X	7.2174	7.2174	0	%100
60	M32	Z	-4.167	-4.167	0	%100
61	M33	X	5.2974	5.2974	0	%100
62	M33	Z	-3.0584	-3.0584	0	%100
63	M34	X	5.2974	5.2974	0	%100
64	M34	Z	-3.0584	-3.0584	0	%100
65	M35	X	5.5691	5.5691	0	%100
66	M35	Z	-3.2153	-3.2153	0	%100
67	M36	X	7.3214	7.3214	0	%100
68	M36	Z	-4.227	-4.227	0	%100
69	MP4A	X	7.2974	7.2974	0	%100
70	MP4A	Z	-4.2132	-4.2132	0	%100
71	MP3A	X	7.2974	7.2974	0	%100
72	MP3A	Z	-4.2132	-4.2132	0	%100
73	MP2A	X	7.2974	7.2974	0	%100
74	MP2A	Z	-4.2132	-4.2132	0	%100
75	MP1A	X	7.2974	7.2974	0	%100
76	MP1A	Z	-4.2132	-4.2132	0	%100
77	EQUIP	X	8.3216	8.3216	0	%100
78	EQUIP	Z	-4.8045	-4.8045	0	%100
79	M51	X	8.3216	8.3216	0	%100
80	M51	Z	-4.8045	-4.8045	0	%100
81	M55A	X	1.8569	1.8569	0	%100
82	M55A	Z	-1.0721	-1.0721	0	%100

Member Distributed Loads (BLC 44 : Structure Wo (90 Deg))

	Member Label	Direction	Start Magnitude	End Magnitude	Start Locationft	End Locationft
1	M1	X	0	0	0	%100
2	M1	Z	0	0	0	%100
3	M3	X	0	0	0	%100
4	M3	Z	0	0	0	%100
5	M5	X	.6779	.6779	0	%100
6	M5	Z	0	0	0	%100
7	M6	X	.6779	.6779	0	%100
8	M6	Z	0	0	0	%100
9	M7	X	0	0	0	%100
10	M7	Z	0	0	0	%100
11	M8	X	.8791	.8791	0	%100
12	M8	Z	0	0	0	%100
13	M9	X	.5533	.5533	0	%100
14	M9	Z	0	0	0	%100
15	M10	X	0	0	0	%100
16	M10	Z	0	0	0	%100
17	M11	X	4.2934	4.2934	0	%100
18	M11	Z	0	0	0	%100
19	M12	X	4.2934	4.2934	0	%100
20	M12	Z	0	0	0	%100
21	M13	X	4.2934	4.2934	0	%100
22	M13	Z	0	0	0	%100
23	M14	X	4.2934	4.2934	0	%100
24	M14	Z	0	0	0	%100
25	M15	X	10.6438	10.6438	0	%100
26	M15	Z	0	0	0	%100
27	M16	X	5.6385	5.6385	0	%100
28	M16	Z	0	0	0	%100



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 21777772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Distributed Loads (BLC 44 : Structure Wo (90 Deg)) (Continued)

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location	End Location
29	M17	X	10.6438	10.6438	0	%100
30	M17	Z	0	0	0	%100
31	M18	X	5.6385	5.6385	0	%100
32	M18	Z	0	0	0	%100
33	M19	X	10.6438	10.6438	0	%100
34	M19	Z	0	0	0	%100
35	M20	X	10.6438	10.6438	0	%100
36	M20	Z	0	0	0	%100
37	M21	X	10.6438	10.6438	0	%100
38	M21	Z	0	0	0	%100
39	M22	X	6.1169	6.1169	0	%100
40	M22	Z	0	0	0	%100
41	M23	X	6.1169	6.1169	0	%100
42	M23	Z	0	0	0	%100
43	M24	X	6.4306	6.4306	0	%100
44	M24	Z	0	0	0	%100
45	M25	X	10.6438	10.6438	0	%100
46	M25	Z	0	0	0	%100
47	M26	X	10.6438	10.6438	0	%100
48	M26	Z	0	0	0	%100
49	M27	X	5.6385	5.6385	0	%100
50	M27	Z	0	0	0	%100
51	M28	X	10.6438	10.6438	0	%100
52	M28	Z	0	0	0	%100
53	M29	X	5.6385	5.6385	0	%100
54	M29	Z	0	0	0	%100
55	M30	X	10.6438	10.6438	0	%100
56	M30	Z	0	0	0	%100
57	M31	X	10.6438	10.6438	0	%100
58	M31	Z	0	0	0	%100
59	M32	X	10.6438	10.6438	0	%100
60	M32	Z	0	0	0	%100
61	M33	X	6.1169	6.1169	0	%100
62	M33	Z	0	0	0	%100
63	M34	X	6.1169	6.1169	0	%100
64	M34	Z	0	0	0	%100
65	M35	X	6.4306	6.4306	0	%100
66	M35	Z	0	0	0	%100
67	M36	X	10.6438	10.6438	0	%100
68	M36	Z	0	0	0	%100
69	MP4A	X	8.4263	8.4263	0	%100
70	MP4A	Z	0	0	0	%100
71	MP3A	X	8.4263	8.4263	0	%100
72	MP3A	Z	0	0	0	%100
73	MP2A	X	8.4263	8.4263	0	%100
74	MP2A	Z	0	0	0	%100
75	MP1A	X	8.4263	8.4263	0	%100
76	MP1A	Z	0	0	0	%100
77	EQUIP	X	9.609	9.609	0	%100
78	EQUIP	Z	0	0	0	%100
79	M51	X	9.609	9.609	0	%100
80	M51	Z	0	0	0	%100
81	M55A	X	6.3571	6.3571	0	%100
82	M55A	Z	0	0	0	%100

Member Distributed Loads (BLC 45 : Structure Wo (120 Deg))

Member Label Direction Start Magnitude End Magnitude Start Location End Location



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 21777772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Distributed Loads (BLC 45 : Structure Wo (120 Deg)) (Continued)

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location[ft...]	End Location[ft...]
1	M1	X	2.3044	2.3044	0	%100
2	M1	Z	1.3305	1.3305	0	%100
3	M3	X	2.3044	2.3044	0	%100
4	M3	Z	1.3305	1.3305	0	%100
5	M5	X	1.0804	1.0804	0	%100
6	M5	Z	.6238	.6238	0	%100
7	M6	X	.0828	.0828	0	%100
8	M6	Z	.0478	.0478	0	%100
9	M7	X	2.2084	2.2084	0	%100
10	M7	Z	1.275	1.275	0	%100
11	M8	X	1.1412	1.1412	0	%100
12	M8	Z	.6588	.6588	0	%100
13	M9	X	.0358	.0358	0	%100
14	M9	Z	.0207	.0207	0	%100
15	M10	X	2.2084	2.2084	0	%100
16	M10	Z	1.275	1.275	0	%100
17	M11	X	6.8427	6.8427	0	%100
18	M11	Z	3.9507	3.9507	0	%100
19	M12	X	.5242	.5242	0	%100
20	M12	Z	.3026	.3026	0	%100
21	M13	X	6.8427	6.8427	0	%100
22	M13	Z	3.9507	3.9507	0	%100
23	M14	X	.5242	.5242	0	%100
24	M14	Z	.3026	.3026	0	%100
25	M15	X	7.2174	7.2174	0	%100
26	M15	Z	4.167	4.167	0	%100
27	M16	X	4.031	4.031	0	%100
28	M16	Z	2.3273	2.3273	0	%100
29	M17	X	7.2174	7.2174	0	%100
30	M17	Z	4.167	4.167	0	%100
31	M18	X	4.031	4.031	0	%100
32	M18	Z	2.3273	2.3273	0	%100
33	M19	X	7.3214	7.3214	0	%100
34	M19	Z	4.227	4.227	0	%100
35	M20	X	7.2174	7.2174	0	%100
36	M20	Z	4.167	4.167	0	%100
37	M21	X	7.2174	7.2174	0	%100
38	M21	Z	4.167	4.167	0	%100
39	M22	X	5.2974	5.2974	0	%100
40	M22	Z	3.0584	3.0584	0	%100
41	M23	X	5.2974	5.2974	0	%100
42	M23	Z	3.0584	3.0584	0	%100
43	M24	X	5.5691	5.5691	0	%100
44	M24	Z	3.2153	3.2153	0	%100
45	M25	X	7.3214	7.3214	0	%100
46	M25	Z	4.227	4.227	0	%100
47	M26	X	7.2174	7.2174	0	%100
48	M26	Z	4.167	4.167	0	%100
49	M27	X	5.7166	5.7166	0	%100
50	M27	Z	3.3005	3.3005	0	%100
51	M28	X	7.2174	7.2174	0	%100
52	M28	Z	4.167	4.167	0	%100
53	M29	X	5.7166	5.7166	0	%100
54	M29	Z	3.3005	3.3005	0	%100
55	M30	X	7.3214	7.3214	0	%100
56	M30	Z	4.227	4.227	0	%100
57	M31	X	7.2174	7.2174	0	%100



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 2177772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Distributed Loads (BLC 45 : Structure Wo (120 Deg)) (Continued)

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location	End Location
58	M31	Z	4.167	4.167	0	%100
59	M32	X	7.2174	7.2174	0	%100
60	M32	Z	4.167	4.167	0	%100
61	M33	X	5.2974	5.2974	0	%100
62	M33	Z	3.0584	3.0584	0	%100
63	M34	X	5.2974	5.2974	0	%100
64	M34	Z	3.0584	3.0584	0	%100
65	M35	X	5.5691	5.5691	0	%100
66	M35	Z	3.2153	3.2153	0	%100
67	M36	X	7.3214	7.3214	0	%100
68	M36	Z	4.227	4.227	0	%100
69	MP4A	X	7.2974	7.2974	0	%100
70	MP4A	Z	4.2132	4.2132	0	%100
71	MP3A	X	7.2974	7.2974	0	%100
72	MP3A	Z	4.2132	4.2132	0	%100
73	MP2A	X	7.2974	7.2974	0	%100
74	MP2A	Z	4.2132	4.2132	0	%100
75	MP1A	X	7.2974	7.2974	0	%100
76	MP1A	Z	4.2132	4.2132	0	%100
77	EQUIP	X	8.3216	8.3216	0	%100
78	EQUIP	Z	4.8045	4.8045	0	%100
79	M51	X	8.3216	8.3216	0	%100
80	M51	Z	4.8045	4.8045	0	%100
81	M55A	X	7.2972	7.2972	0	%100
82	M55A	Z	4.2131	4.2131	0	%100

Member Distributed Loads (BLC 46 : Structure Wo (150 Deg))

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location	End Location
1	M1	X	3.9914	3.9914	0	%100
2	M1	Z	6.9133	6.9133	0	%100
3	M3	X	3.9914	3.9914	0	%100
4	M3	Z	6.9133	6.9133	0	%100
5	M5	X	.6175	.6175	0	%100
6	M5	Z	1.0695	1.0695	0	%100
7	M6	X	.0414	.0414	0	%100
8	M6	Z	.0718	.0718	0	%100
9	M7	X	3.8251	3.8251	0	%100
10	M7	Z	6.6253	6.6253	0	%100
11	M8	X	.5519	.5519	0	%100
12	M8	Z	.956	.956	0	%100
13	M9	X	.0766	.0766	0	%100
14	M9	Z	.1328	.1328	0	%100
15	M10	X	3.8251	3.8251	0	%100
16	M10	Z	6.6253	6.6253	0	%100
17	M11	X	3.9105	3.9105	0	%100
18	M11	Z	6.7733	6.7733	0	%100
19	M12	X	.2625	.2625	0	%100
20	M12	Z	.4547	.4547	0	%100
21	M13	X	3.9105	3.9105	0	%100
22	M13	Z	6.7733	6.7733	0	%100
23	M14	X	.2625	.2625	0	%100
24	M14	Z	.4547	.4547	0	%100
25	M15	X	1.8571	1.8571	0	%100
26	M15	Z	3.2166	3.2166	0	%100
27	M16	X	2.3166	2.3166	0	%100
28	M16	Z	4.0125	4.0125	0	%100



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 21777772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Distributed Loads (BLC 46 : Structure Wo (150 Deg)) (Continued)

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location(ft)	End Location(ft)
29	M17	X	1.8571	1.8571	0	%100
30	M17	Z	3.2166	3.2166	0	%100
31	M18	X	2.3166	2.3166	0	%100
32	M18	Z	4.0125	4.0125	0	%100
33	M19	X	2.0373	2.0373	0	%100
34	M19	Z	3.5287	3.5287	0	%100
35	M20	X	1.8571	1.8571	0	%100
36	M20	Z	3.2166	3.2166	0	%100
37	M21	X	1.8571	1.8571	0	%100
38	M21	Z	3.2166	3.2166	0	%100
39	M22	X	3.0584	3.0584	0	%100
40	M22	Z	5.2974	5.2974	0	%100
41	M23	X	3.0584	3.0584	0	%100
42	M23	Z	5.2974	5.2974	0	%100
43	M24	X	3.2153	3.2153	0	%100
44	M24	Z	5.5691	5.5691	0	%100
45	M25	X	2.0373	2.0373	0	%100
46	M25	Z	3.5287	3.5287	0	%100
47	M26	X	1.8571	1.8571	0	%100
48	M26	Z	3.2166	3.2166	0	%100
49	M27	X	3.2898	3.2898	0	%100
50	M27	Z	5.6981	5.6981	0	%100
51	M28	X	1.8571	1.8571	0	%100
52	M28	Z	3.2166	3.2166	0	%100
53	M29	X	3.2898	3.2898	0	%100
54	M29	Z	5.6981	5.6981	0	%100
55	M30	X	2.0373	2.0373	0	%100
56	M30	Z	3.5287	3.5287	0	%100
57	M31	X	1.8571	1.8571	0	%100
58	M31	Z	3.2166	3.2166	0	%100
59	M32	X	1.8571	1.8571	0	%100
60	M32	Z	3.2166	3.2166	0	%100
61	M33	X	3.0584	3.0584	0	%100
62	M33	Z	5.2974	5.2974	0	%100
63	M34	X	3.0584	3.0584	0	%100
64	M34	Z	5.2974	5.2974	0	%100
65	M35	X	3.2153	3.2153	0	%100
66	M35	Z	5.5691	5.5691	0	%100
67	M36	X	2.0373	2.0373	0	%100
68	M36	Z	3.5287	3.5287	0	%100
69	MP4A	X	4.2132	4.2132	0	%100
70	MP4A	Z	7.2974	7.2974	0	%100
71	MP3A	X	4.2132	4.2132	0	%100
72	MP3A	Z	7.2974	7.2974	0	%100
73	MP2A	X	4.2132	4.2132	0	%100
74	MP2A	Z	7.2974	7.2974	0	%100
75	MP1A	X	4.2132	4.2132	0	%100
76	MP1A	Z	7.2974	7.2974	0	%100
77	EQUIP	X	4.8045	4.8045	0	%100
78	EQUIP	Z	8.3216	8.3216	0	%100
79	M51	X	4.8045	4.8045	0	%100
80	M51	Z	8.3216	8.3216	0	%100
81	M55A	X	3.1411	3.1411	0	%100
82	M55A	Z	5.4406	5.4406	0	%100

Member Distributed Loads (BLC 47 : Structure Wo (180 Deg))

Member Label Direction Start Magnitude End Magnitude Start Location(ft) End Location(ft)



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 2177772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Distributed Loads (BLC 47 : Structure Wo (180 Deg)) (Continued)

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location	End Location
1	M1	X	0	0	0	%100
2	M1	Z	10.6438	10.6438	0	%100
3	M3	X	0	0	0	%100
4	M3	Z	10.6438	10.6438	0	%100
5	M5	X	0	0	0	%100
6	M5	Z	.6526	.6526	0	%100
7	M6	X	0	0	0	%100
8	M6	Z	.6526	.6526	0	%100
9	M7	X	0	0	0	%100
10	M7	Z	10.2003	10.2003	0	%100
11	M8	X	0	0	0	%100
12	M8	Z	.4514	.4514	0	%100
13	M9	X	0	0	0	%100
14	M9	Z	.7772	.7772	0	%100
15	M10	X	0	0	0	%100
16	M10	Z	10.2003	10.2003	0	%100
17	M11	X	0	0	0	%100
18	M11	Z	4.1329	4.1329	0	%100
19	M12	X	0	0	0	%100
20	M12	Z	4.1329	4.1329	0	%100
21	M13	X	0	0	0	%100
22	M13	Z	4.1329	4.1329	0	%100
23	M14	X	0	0	0	%100
24	M14	Z	4.1329	4.1329	0	%100
25	M15	X	0	0	0	%100
26	M15	Z	1.4044	1.4044	0	%100
27	M16	X	0	0	0	%100
28	M16	Z	5.5957	5.5957	0	%100
29	M17	X	0	0	0	%100
30	M17	Z	1.4044	1.4044	0	%100
31	M18	X	0	0	0	%100
32	M18	Z	5.5957	5.5957	0	%100
33	M19	X	0	0	0	%100
34	M19	Z	1.8848	1.8848	0	%100
35	M20	X	0	0	0	%100
36	M20	Z	1.4044	1.4044	0	%100
37	M21	X	0	0	0	%100
38	M21	Z	1.4044	1.4044	0	%100
39	M22	X	0	0	0	%100
40	M22	Z	6.1169	6.1169	0	%100
41	M23	X	0	0	0	%100
42	M23	Z	6.1169	6.1169	0	%100
43	M24	X	0	0	0	%100
44	M24	Z	6.4306	6.4306	0	%100
45	M25	X	0	0	0	%100
46	M25	Z	1.8848	1.8848	0	%100
47	M26	X	0	0	0	%100
48	M26	Z	1.4044	1.4044	0	%100
49	M27	X	0	0	0	%100
50	M27	Z	5.5957	5.5957	0	%100
51	M28	X	0	0	0	%100
52	M28	Z	1.4044	1.4044	0	%100
53	M29	X	0	0	0	%100
54	M29	Z	5.5957	5.5957	0	%100
55	M30	X	0	0	0	%100
56	M30	Z	1.8848	1.8848	0	%100
57	M31	X	0	0	0	%100



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 2177772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Distributed Loads (BLC 47 : Structure Wo (180 Deg)) (Continued)

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location	End Location
58	M31	Z	1.4044	1.4044	0	%100
59	M32	X	0	0	0	%100
60	M32	Z	1.4044	1.4044	0	%100
61	M33	X	0	0	0	%100
62	M33	Z	6.1169	6.1169	0	%100
63	M34	X	0	0	0	%100
64	M34	Z	6.1169	6.1169	0	%100
65	M35	X	0	0	0	%100
66	M35	Z	6.4306	6.4306	0	%100
67	M36	X	0	0	0	%100
68	M36	Z	1.8848	1.8848	0	%100
69	MP4A	X	0	0	0	%100
70	MP4A	Z	8.4263	8.4263	0	%100
71	MP3A	X	0	0	0	%100
72	MP3A	Z	8.4263	8.4263	0	%100
73	MP2A	X	0	0	0	%100
74	MP2A	Z	8.4263	8.4263	0	%100
75	MP1A	X	0	0	0	%100
76	MP1A	Z	8.4263	8.4263	0	%100
77	EQUIP	X	0	0	0	%100
78	EQUIP	Z	9.609	9.609	0	%100
79	M51	X	0	0	0	%100
80	M51	Z	9.609	9.609	0	%100
81	M55A	X	0	0	0	%100
82	M55A	Z	2.0693	2.0693	0	%100

Member Distributed Loads (BLC 48 : Structure Wo (210 Deg))

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location	End Location
1	M1	X	-3.9914	-3.9914	0	%100
2	M1	Z	6.9133	6.9133	0	%100
3	M3	X	-3.9914	-3.9914	0	%100
4	M3	Z	6.9133	6.9133	0	%100
5	M5	X	-.0414	-.0414	0	%100
6	M5	Z	.0718	.0718	0	%100
7	M6	X	-.6175	-.6175	0	%100
8	M6	Z	1.0695	1.0695	0	%100
9	M7	X	-3.8251	-3.8251	0	%100
10	M7	Z	6.6253	6.6253	0	%100
11	M8	X	-.0064	-.0064	0	%100
12	M8	Z	.0111	.0111	0	%100
13	M9	X	-.6445	-.6445	0	%100
14	M9	Z	1.1164	1.1164	0	%100
15	M10	X	-3.8251	-3.8251	0	%100
16	M10	Z	6.6253	6.6253	0	%100
17	M11	X	-.2625	-.2625	0	%100
18	M11	Z	.4547	.4547	0	%100
19	M12	X	-3.9105	-3.9105	0	%100
20	M12	Z	6.7733	6.7733	0	%100
21	M13	X	-.2625	-.2625	0	%100
22	M13	Z	.4547	.4547	0	%100
23	M14	X	-3.9105	-3.9105	0	%100
24	M14	Z	6.7733	6.7733	0	%100
25	M15	X	-1.8571	-1.8571	0	%100
26	M15	Z	3.2166	3.2166	0	%100
27	M16	X	-3.2898	-3.2898	0	%100
28	M16	Z	5.6981	5.6981	0	%100



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 2177772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Distributed Loads (BLC 48 : Structure Wo (210 Deg)) (Continued)

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location	End Location
29	M17	X	-1.8571	-1.8571	0	%100
30	M17	Z	3.2166	3.2166	0	%100
31	M18	X	-3.2898	-3.2898	0	%100
32	M18	Z	5.6981	5.6981	0	%100
33	M19	X	-2.0373	-2.0373	0	%100
34	M19	Z	3.5287	3.5287	0	%100
35	M20	X	-1.8571	-1.8571	0	%100
36	M20	Z	3.2166	3.2166	0	%100
37	M21	X	-1.8571	-1.8571	0	%100
38	M21	Z	3.2166	3.2166	0	%100
39	M22	X	-3.0584	-3.0584	0	%100
40	M22	Z	5.2974	5.2974	0	%100
41	M23	X	-3.0584	-3.0584	0	%100
42	M23	Z	5.2974	5.2974	0	%100
43	M24	X	-3.2153	-3.2153	0	%100
44	M24	Z	5.5691	5.5691	0	%100
45	M25	X	-2.0373	-2.0373	0	%100
46	M25	Z	3.5287	3.5287	0	%100
47	M26	X	-1.8571	-1.8571	0	%100
48	M26	Z	3.2166	3.2166	0	%100
49	M27	X	-2.3166	-2.3166	0	%100
50	M27	Z	4.0125	4.0125	0	%100
51	M28	X	-1.8571	-1.8571	0	%100
52	M28	Z	3.2166	3.2166	0	%100
53	M29	X	-2.3166	-2.3166	0	%100
54	M29	Z	4.0125	4.0125	0	%100
55	M30	X	-2.0373	-2.0373	0	%100
56	M30	Z	3.5287	3.5287	0	%100
57	M31	X	-1.8571	-1.8571	0	%100
58	M31	Z	3.2166	3.2166	0	%100
59	M32	X	-1.8571	-1.8571	0	%100
60	M32	Z	3.2166	3.2166	0	%100
61	M33	X	-3.0584	-3.0584	0	%100
62	M33	Z	5.2974	5.2974	0	%100
63	M34	X	-3.0584	-3.0584	0	%100
64	M34	Z	5.2974	5.2974	0	%100
65	M35	X	-3.2153	-3.2153	0	%100
66	M35	Z	5.5691	5.5691	0	%100
67	M36	X	-2.0373	-2.0373	0	%100
68	M36	Z	3.5287	3.5287	0	%100
69	MP4A	X	-4.2132	-4.2132	0	%100
70	MP4A	Z	7.2974	7.2974	0	%100
71	MP3A	X	-4.2132	-4.2132	0	%100
72	MP3A	Z	7.2974	7.2974	0	%100
73	MP2A	X	-4.2132	-4.2132	0	%100
74	MP2A	Z	7.2974	7.2974	0	%100
75	MP1A	X	-4.2132	-4.2132	0	%100
76	MP1A	Z	7.2974	7.2974	0	%100
77	EQUIP	X	-4.8045	-4.8045	0	%100
78	EQUIP	Z	8.3216	8.3216	0	%100
79	M51	X	-4.8045	-4.8045	0	%100
80	M51	Z	8.3216	8.3216	0	%100
81	M55A	X	-.000111	-.000111	0	%100
82	M55A	Z	.000192	.000192	0	%100

Member Distributed Loads (BLC 49 : Structure Wo (240 Deg))

Member Label Direction Start Magnitude End Magnitude Start Location End Location



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 21777772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Distributed Loads (BLC 49 : Structure Wo (240 Deg)) (Continued)

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location[ft]	End Location[ft]
1	M1	X	-2.3044	-2.3044	0	%100
2	M1	Z	1.3305	1.3305	0	%100
3	M3	X	-2.3044	-2.3044	0	%100
4	M3	Z	1.3305	1.3305	0	%100
5	M5	X	-.0828	-.0828	0	%100
6	M5	Z	.0478	.0478	0	%100
7	M6	X	-1.0804	-1.0804	0	%100
8	M6	Z	.6238	.6238	0	%100
9	M7	X	-2.2084	-2.2084	0	%100
10	M7	Z	1.275	1.275	0	%100
11	M8	X	-.1962	-.1962	0	%100
12	M8	Z	.1133	.1133	0	%100
13	M9	X	-1.0195	-1.0195	0	%100
14	M9	Z	.5886	.5886	0	%100
15	M10	X	-2.2084	-2.2084	0	%100
16	M10	Z	1.275	1.275	0	%100
17	M11	X	-.5242	-.5242	0	%100
18	M11	Z	.3026	.3026	0	%100
19	M12	X	-6.8427	-6.8427	0	%100
20	M12	Z	3.9507	3.9507	0	%100
21	M13	X	-.5242	-.5242	0	%100
22	M13	Z	.3026	.3026	0	%100
23	M14	X	-6.8427	-6.8427	0	%100
24	M14	Z	3.9507	3.9507	0	%100
25	M15	X	-7.2174	-7.2174	0	%100
26	M15	Z	4.167	4.167	0	%100
27	M16	X	-5.7166	-5.7166	0	%100
28	M16	Z	3.3005	3.3005	0	%100
29	M17	X	-7.2174	-7.2174	0	%100
30	M17	Z	4.167	4.167	0	%100
31	M18	X	-5.7166	-5.7166	0	%100
32	M18	Z	3.3005	3.3005	0	%100
33	M19	X	-7.3214	-7.3214	0	%100
34	M19	Z	4.227	4.227	0	%100
35	M20	X	-7.2174	-7.2174	0	%100
36	M20	Z	4.167	4.167	0	%100
37	M21	X	-7.2174	-7.2174	0	%100
38	M21	Z	4.167	4.167	0	%100
39	M22	X	-5.2974	-5.2974	0	%100
40	M22	Z	3.0584	3.0584	0	%100
41	M23	X	-5.2974	-5.2974	0	%100
42	M23	Z	3.0584	3.0584	0	%100
43	M24	X	-5.5691	-5.5691	0	%100
44	M24	Z	3.2153	3.2153	0	%100
45	M25	X	-7.3214	-7.3214	0	%100
46	M25	Z	4.227	4.227	0	%100
47	M26	X	-7.2174	-7.2174	0	%100
48	M26	Z	4.167	4.167	0	%100
49	M27	X	-4.031	-4.031	0	%100
50	M27	Z	2.3273	2.3273	0	%100
51	M28	X	-7.2174	-7.2174	0	%100
52	M28	Z	4.167	4.167	0	%100
53	M29	X	-4.031	-4.031	0	%100
54	M29	Z	2.3273	2.3273	0	%100
55	M30	X	-7.3214	-7.3214	0	%100
56	M30	Z	4.227	4.227	0	%100
57	M31	X	-7.2174	-7.2174	0	%100



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 2177772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Distributed Loads (BLC 49 : Structure Wo (240 Deg)) (Continued)

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location	End Location
58	M31	Z	4.167	4.167	0	%100
59	M32	X	-7.2174	-7.2174	0	%100
60	M32	Z	4.167	4.167	0	%100
61	M33	X	-5.2974	-5.2974	0	%100
62	M33	Z	3.0584	3.0584	0	%100
63	M34	X	-5.2974	-5.2974	0	%100
64	M34	Z	3.0584	3.0584	0	%100
65	M35	X	-5.5691	-5.5691	0	%100
66	M35	Z	3.2153	3.2153	0	%100
67	M36	X	-7.3214	-7.3214	0	%100
68	M36	Z	4.227	4.227	0	%100
69	MP4A	X	-7.2974	-7.2974	0	%100
70	MP4A	Z	4.2132	4.2132	0	%100
71	MP3A	X	-7.2974	-7.2974	0	%100
72	MP3A	Z	4.2132	4.2132	0	%100
73	MP2A	X	-7.2974	-7.2974	0	%100
74	MP2A	Z	4.2132	4.2132	0	%100
75	MP1A	X	-7.2974	-7.2974	0	%100
76	MP1A	Z	4.2132	4.2132	0	%100
77	EQUIP	X	-8.3216	-8.3216	0	%100
78	EQUIP	Z	4.8045	4.8045	0	%100
79	M51	X	-8.3216	-8.3216	0	%100
80	M51	Z	4.8045	4.8045	0	%100
81	M55A	X	-1.8569	-1.8569	0	%100
82	M55A	Z	1.0721	1.0721	0	%100

Member Distributed Loads (BLC 50 : Structure Wo (270 Deg))

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location	End Location
1	M1	X	0	0	0	%100
2	M1	Z	0	0	0	%100
3	M3	X	0	0	0	%100
4	M3	Z	0	0	0	%100
5	M5	X	-6.779	-6.779	0	%100
6	M5	Z	0	0	0	%100
7	M6	X	-6.779	-6.779	0	%100
8	M6	Z	0	0	0	%100
9	M7	X	0	0	0	%100
10	M7	Z	0	0	0	%100
11	M8	X	-8.791	-8.791	0	%100
12	M8	Z	0	0	0	%100
13	M9	X	-5.533	-5.533	0	%100
14	M9	Z	0	0	0	%100
15	M10	X	0	0	0	%100
16	M10	Z	0	0	0	%100
17	M11	X	-4.2934	-4.2934	0	%100
18	M11	Z	0	0	0	%100
19	M12	X	-4.2934	-4.2934	0	%100
20	M12	Z	0	0	0	%100
21	M13	X	-4.2934	-4.2934	0	%100
22	M13	Z	0	0	0	%100
23	M14	X	-4.2934	-4.2934	0	%100
24	M14	Z	0	0	0	%100
25	M15	X	-10.6438	-10.6438	0	%100
26	M15	Z	0	0	0	%100
27	M16	X	-5.6385	-5.6385	0	%100
28	M16	Z	0	0	0	%100



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 21777772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Distributed Loads (BLC 50 : Structure Wo (270 Deg)) (Continued)

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location(ft)	End Location(ft)
29	M17	X	-10.6438	-10.6438	0	%100
30	M17	Z	0	0	0	%100
31	M18	X	-5.6385	-5.6385	0	%100
32	M18	Z	0	0	0	%100
33	M19	X	-10.6438	-10.6438	0	%100
34	M19	Z	0	0	0	%100
35	M20	X	-10.6438	-10.6438	0	%100
36	M20	Z	0	0	0	%100
37	M21	X	-10.6438	-10.6438	0	%100
38	M21	Z	0	0	0	%100
39	M22	X	-6.1169	-6.1169	0	%100
40	M22	Z	0	0	0	%100
41	M23	X	-6.1169	-6.1169	0	%100
42	M23	Z	0	0	0	%100
43	M24	X	-6.4306	-6.4306	0	%100
44	M24	Z	0	0	0	%100
45	M25	X	-10.6438	-10.6438	0	%100
46	M25	Z	0	0	0	%100
47	M26	X	-10.6438	-10.6438	0	%100
48	M26	Z	0	0	0	%100
49	M27	X	-5.6385	-5.6385	0	%100
50	M27	Z	0	0	0	%100
51	M28	X	-10.6438	-10.6438	0	%100
52	M28	Z	0	0	0	%100
53	M29	X	-5.6385	-5.6385	0	%100
54	M29	Z	0	0	0	%100
55	M30	X	-10.6438	-10.6438	0	%100
56	M30	Z	0	0	0	%100
57	M31	X	-10.6438	-10.6438	0	%100
58	M31	Z	0	0	0	%100
59	M32	X	-10.6438	-10.6438	0	%100
60	M32	Z	0	0	0	%100
61	M33	X	-6.1169	-6.1169	0	%100
62	M33	Z	0	0	0	%100
63	M34	X	-6.1169	-6.1169	0	%100
64	M34	Z	0	0	0	%100
65	M35	X	-6.4306	-6.4306	0	%100
66	M35	Z	0	0	0	%100
67	M36	X	-10.6438	-10.6438	0	%100
68	M36	Z	0	0	0	%100
69	MP4A	X	-8.4263	-8.4263	0	%100
70	MP4A	Z	0	0	0	%100
71	MP3A	X	-8.4263	-8.4263	0	%100
72	MP3A	Z	0	0	0	%100
73	MP2A	X	-8.4263	-8.4263	0	%100
74	MP2A	Z	0	0	0	%100
75	MP1A	X	-8.4263	-8.4263	0	%100
76	MP1A	Z	0	0	0	%100
77	EQUIP	X	-9.609	-9.609	0	%100
78	EQUIP	Z	0	0	0	%100
79	M51	X	-9.609	-9.609	0	%100
80	M51	Z	0	0	0	%100
81	M55A	X	-6.3571	-6.3571	0	%100
82	M55A	Z	0	0	0	%100

Member Distributed Loads (BLC 51 : Structure Wo (300 Deg))

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location(ft)	End Location(ft)
--	--------------	-----------	-----------------	---------------	--------------------	------------------



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 21777772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Distributed Loads (BLC 51 : Structure Wo (300 Deg)) (Continued)

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location[ft]	End Location[ft]
1	M1	X	-2.3044	-2.3044	0	%100
2	M1	Z	-1.3305	-1.3305	0	%100
3	M3	X	-2.3044	-2.3044	0	%100
4	M3	Z	-1.3305	-1.3305	0	%100
5	M5	X	-1.0804	-1.0804	0	%100
6	M5	Z	-.6238	-.6238	0	%100
7	M6	X	-.0828	-.0828	0	%100
8	M6	Z	-.0478	-.0478	0	%100
9	M7	X	-2.2084	-2.2084	0	%100
10	M7	Z	-1.275	-1.275	0	%100
11	M8	X	-1.1412	-1.1412	0	%100
12	M8	Z	-.6588	-.6588	0	%100
13	M9	X	-.0358	-.0358	0	%100
14	M9	Z	-.0207	-.0207	0	%100
15	M10	X	-2.2084	-2.2084	0	%100
16	M10	Z	-1.275	-1.275	0	%100
17	M11	X	-6.8427	-6.8427	0	%100
18	M11	Z	-3.9507	-3.9507	0	%100
19	M12	X	-.5242	-.5242	0	%100
20	M12	Z	-.3026	-.3026	0	%100
21	M13	X	-6.8427	-6.8427	0	%100
22	M13	Z	-3.9507	-3.9507	0	%100
23	M14	X	-.5242	-.5242	0	%100
24	M14	Z	-.3026	-.3026	0	%100
25	M15	X	-7.2174	-7.2174	0	%100
26	M15	Z	-4.167	-4.167	0	%100
27	M16	X	-4.031	-4.031	0	%100
28	M16	Z	-2.3273	-2.3273	0	%100
29	M17	X	-7.2174	-7.2174	0	%100
30	M17	Z	-4.167	-4.167	0	%100
31	M18	X	-4.031	-4.031	0	%100
32	M18	Z	-2.3273	-2.3273	0	%100
33	M19	X	-7.3214	-7.3214	0	%100
34	M19	Z	-4.227	-4.227	0	%100
35	M20	X	-7.2174	-7.2174	0	%100
36	M20	Z	-4.167	-4.167	0	%100
37	M21	X	-7.2174	-7.2174	0	%100
38	M21	Z	-4.167	-4.167	0	%100
39	M22	X	-5.2974	-5.2974	0	%100
40	M22	Z	-3.0584	-3.0584	0	%100
41	M23	X	-5.2974	-5.2974	0	%100
42	M23	Z	-3.0584	-3.0584	0	%100
43	M24	X	-5.5691	-5.5691	0	%100
44	M24	Z	-3.2153	-3.2153	0	%100
45	M25	X	-7.3214	-7.3214	0	%100
46	M25	Z	-4.227	-4.227	0	%100
47	M26	X	-7.2174	-7.2174	0	%100
48	M26	Z	-4.167	-4.167	0	%100
49	M27	X	-5.7166	-5.7166	0	%100
50	M27	Z	-3.3005	-3.3005	0	%100
51	M28	X	-7.2174	-7.2174	0	%100
52	M28	Z	-4.167	-4.167	0	%100
53	M29	X	-5.7166	-5.7166	0	%100
54	M29	Z	-3.3005	-3.3005	0	%100
55	M30	X	-7.3214	-7.3214	0	%100
56	M30	Z	-4.227	-4.227	0	%100
57	M31	X	-7.2174	-7.2174	0	%100



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 2177772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Distributed Loads (BLC 51 : Structure Wo (300 Deg)) (Continued)

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location(ft)	End Location(ft)
58	M31	Z	-4.167	-4.167	0	%100
59	M32	X	-7.2174	-7.2174	0	%100
60	M32	Z	-4.167	-4.167	0	%100
61	M33	X	-5.2974	-5.2974	0	%100
62	M33	Z	-3.0584	-3.0584	0	%100
63	M34	X	-5.2974	-5.2974	0	%100
64	M34	Z	-3.0584	-3.0584	0	%100
65	M35	X	-5.5691	-5.5691	0	%100
66	M35	Z	-3.2153	-3.2153	0	%100
67	M36	X	-7.3214	-7.3214	0	%100
68	M36	Z	-4.227	-4.227	0	%100
69	MP4A	X	-7.2974	-7.2974	0	%100
70	MP4A	Z	-4.2132	-4.2132	0	%100
71	MP3A	X	-7.2974	-7.2974	0	%100
72	MP3A	Z	-4.2132	-4.2132	0	%100
73	MP2A	X	-7.2974	-7.2974	0	%100
74	MP2A	Z	-4.2132	-4.2132	0	%100
75	MP1A	X	-7.2974	-7.2974	0	%100
76	MP1A	Z	-4.2132	-4.2132	0	%100
77	EQUIP	X	-8.3216	-8.3216	0	%100
78	EQUIP	Z	-4.8045	-4.8045	0	%100
79	M51	X	-8.3216	-8.3216	0	%100
80	M51	Z	-4.8045	-4.8045	0	%100
81	M55A	X	-7.2972	-7.2972	0	%100
82	M55A	Z	-4.2131	-4.2131	0	%100

Member Distributed Loads (BLC 52 : Structure Wo (330 Deg))

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location(ft)	End Location(ft)
1	M1	X	-3.9914	-3.9914	0	%100
2	M1	Z	-6.9133	-6.9133	0	%100
3	M3	X	-3.9914	-3.9914	0	%100
4	M3	Z	-6.9133	-6.9133	0	%100
5	M5	X	-6.175	-6.175	0	%100
6	M5	Z	-1.0695	-1.0695	0	%100
7	M6	X	-0.414	-0.414	0	%100
8	M6	Z	-0.718	-0.718	0	%100
9	M7	X	-3.8251	-3.8251	0	%100
10	M7	Z	-6.6253	-6.6253	0	%100
11	M8	X	-5.519	-5.519	0	%100
12	M8	Z	-9.56	-9.56	0	%100
13	M9	X	-0.766	-0.766	0	%100
14	M9	Z	-1.328	-1.328	0	%100
15	M10	X	-3.8251	-3.8251	0	%100
16	M10	Z	-6.6253	-6.6253	0	%100
17	M11	X	-3.9105	-3.9105	0	%100
18	M11	Z	-6.7733	-6.7733	0	%100
19	M12	X	-2.625	-2.625	0	%100
20	M12	Z	-4.547	-4.547	0	%100
21	M13	X	-3.9105	-3.9105	0	%100
22	M13	Z	-6.7733	-6.7733	0	%100
23	M14	X	-2.625	-2.625	0	%100
24	M14	Z	-4.547	-4.547	0	%100
25	M15	X	-1.8571	-1.8571	0	%100
26	M15	Z	-3.2166	-3.2166	0	%100
27	M16	X	-2.3166	-2.3166	0	%100
28	M16	Z	-4.0125	-4.0125	0	%100



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 21777772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Distributed Loads (BLC 52 : Structure Wo (330 Deg)) (Continued)

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location	End Location
29	M17	X	-1.8571	-1.8571	0	%100
30	M17	Z	-3.2166	-3.2166	0	%100
31	M18	X	-2.3166	-2.3166	0	%100
32	M18	Z	-4.0125	-4.0125	0	%100
33	M19	X	-2.0373	-2.0373	0	%100
34	M19	Z	-3.5287	-3.5287	0	%100
35	M20	X	-1.8571	-1.8571	0	%100
36	M20	Z	-3.2166	-3.2166	0	%100
37	M21	X	-1.8571	-1.8571	0	%100
38	M21	Z	-3.2166	-3.2166	0	%100
39	M22	X	-3.0584	-3.0584	0	%100
40	M22	Z	-5.2974	-5.2974	0	%100
41	M23	X	-3.0584	-3.0584	0	%100
42	M23	Z	-5.2974	-5.2974	0	%100
43	M24	X	-3.2153	-3.2153	0	%100
44	M24	Z	-5.5691	-5.5691	0	%100
45	M25	X	-2.0373	-2.0373	0	%100
46	M25	Z	-3.5287	-3.5287	0	%100
47	M26	X	-1.8571	-1.8571	0	%100
48	M26	Z	-3.2166	-3.2166	0	%100
49	M27	X	-3.2898	-3.2898	0	%100
50	M27	Z	-5.6981	-5.6981	0	%100
51	M28	X	-1.8571	-1.8571	0	%100
52	M28	Z	-3.2166	-3.2166	0	%100
53	M29	X	-3.2898	-3.2898	0	%100
54	M29	Z	-5.6981	-5.6981	0	%100
55	M30	X	-2.0373	-2.0373	0	%100
56	M30	Z	-3.5287	-3.5287	0	%100
57	M31	X	-1.8571	-1.8571	0	%100
58	M31	Z	-3.2166	-3.2166	0	%100
59	M32	X	-1.8571	-1.8571	0	%100
60	M32	Z	-3.2166	-3.2166	0	%100
61	M33	X	-3.0584	-3.0584	0	%100
62	M33	Z	-5.2974	-5.2974	0	%100
63	M34	X	-3.0584	-3.0584	0	%100
64	M34	Z	-5.2974	-5.2974	0	%100
65	M35	X	-3.2153	-3.2153	0	%100
66	M35	Z	-5.5691	-5.5691	0	%100
67	M36	X	-2.0373	-2.0373	0	%100
68	M36	Z	-3.5287	-3.5287	0	%100
69	MP4A	X	-4.2132	-4.2132	0	%100
70	MP4A	Z	-7.2974	-7.2974	0	%100
71	MP3A	X	-4.2132	-4.2132	0	%100
72	MP3A	Z	-7.2974	-7.2974	0	%100
73	MP2A	X	-4.2132	-4.2132	0	%100
74	MP2A	Z	-7.2974	-7.2974	0	%100
75	MP1A	X	-4.2132	-4.2132	0	%100
76	MP1A	Z	-7.2974	-7.2974	0	%100
77	EQUIP	X	-4.8045	-4.8045	0	%100
78	EQUIP	Z	-8.3216	-8.3216	0	%100
79	M51	X	-4.8045	-4.8045	0	%100
80	M51	Z	-8.3216	-8.3216	0	%100
81	M55A	X	-3.1411	-3.1411	0	%100
82	M55A	Z	-5.4406	-5.4406	0	%100

Member Distributed Loads (BLC 53 : Structure Wi (0 Deg))

Member Label Direction Start Magnitude End Magnitude Start Location End Location



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 21777772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Distributed Loads (BLC 53 : Structure Wi (0 Deg)) (Continued)

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location[ft...]	End Location[ft...]
1	M1	X	0	0	0	%100
2	M1	Z	-2.6991	-2.6991	0	%100
3	M3	X	0	0	0	%100
4	M3	Z	-2.6991	-2.6991	0	%100
5	M5	X	0	0	0	%100
6	M5	Z	-5258	-5258	0	%100
7	M6	X	0	0	0	%100
8	M6	Z	-5258	-5258	0	%100
9	M7	X	0	0	0	%100
10	M7	Z	-3.2126	-3.2126	0	%100
11	M8	X	0	0	0	%100
12	M8	Z	-3637	-3637	0	%100
13	M9	X	0	0	0	%100
14	M9	Z	-6262	-6262	0	%100
15	M10	X	0	0	0	%100
16	M10	Z	-3.2126	-3.2126	0	%100
17	M11	X	0	0	0	%100
18	M11	Z	-1.4246	-1.4246	0	%100
19	M12	X	0	0	0	%100
20	M12	Z	-1.4246	-1.4246	0	%100
21	M13	X	0	0	0	%100
22	M13	Z	-1.4246	-1.4246	0	%100
23	M14	X	0	0	0	%100
24	M14	Z	-1.4246	-1.4246	0	%100
25	M15	X	0	0	0	%100
26	M15	Z	-1.0848	-1.0848	0	%100
27	M16	X	0	0	0	%100
28	M16	Z	-2.0897	-2.0897	0	%100
29	M17	X	0	0	0	%100
30	M17	Z	-1.0848	-1.0848	0	%100
31	M18	X	0	0	0	%100
32	M18	Z	-2.0897	-2.0897	0	%100
33	M19	X	0	0	0	%100
34	M19	Z	-1.1699	-1.1699	0	%100
35	M20	X	0	0	0	%100
36	M20	Z	-1.0848	-1.0848	0	%100
37	M21	X	0	0	0	%100
38	M21	Z	-1.0848	-1.0848	0	%100
39	M22	X	0	0	0	%100
40	M22	Z	-2.2696	-2.2696	0	%100
41	M23	X	0	0	0	%100
42	M23	Z	-2.2696	-2.2696	0	%100
43	M24	X	0	0	0	%100
44	M24	Z	-2.2215	-2.2215	0	%100
45	M25	X	0	0	0	%100
46	M25	Z	-1.1699	-1.1699	0	%100
47	M26	X	0	0	0	%100
48	M26	Z	-1.0848	-1.0848	0	%100
49	M27	X	0	0	0	%100
50	M27	Z	-2.0897	-2.0897	0	%100
51	M28	X	0	0	0	%100
52	M28	Z	-1.0848	-1.0848	0	%100
53	M29	X	0	0	0	%100
54	M29	Z	-2.0897	-2.0897	0	%100
55	M30	X	0	0	0	%100
56	M30	Z	-1.1699	-1.1699	0	%100
57	M31	X	0	0	0	%100



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 2177772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Distributed Loads (BLC 53 : Structure Wi (0 Deg)) (Continued)

	Member Label	Direction	Start Magnitude...	End Magnitude ...	Start Locationft...	End Locationft...
58	M31	Z	-1.0848	-1.0848	0	%100
59	M32	X	0	0	0	%100
60	M32	Z	-1.0848	-1.0848	0	%100
61	M33	X	0	0	0	%100
62	M33	Z	-2.2696	-2.2696	0	%100
63	M34	X	0	0	0	%100
64	M34	Z	-2.2696	-2.2696	0	%100
65	M35	X	0	0	0	%100
66	M35	Z	-2.2215	-2.2215	0	%100
67	M36	X	0	0	0	%100
68	M36	Z	-1.1699	-1.1699	0	%100
69	MP4A	X	0	0	0	%100
70	MP4A	Z	-2.9046	-2.9046	0	%100
71	MP3A	X	0	0	0	%100
72	MP3A	Z	-2.9046	-2.9046	0	%100
73	MP2A	X	0	0	0	%100
74	MP2A	Z	-2.9046	-2.9046	0	%100
75	MP1A	X	0	0	0	%100
76	MP1A	Z	-2.9046	-2.9046	0	%100
77	EQUIP	X	0	0	0	%100
78	EQUIP	Z	-2.9786	-2.9786	0	%100
79	M51	X	0	0	0	%100
80	M51	Z	-2.9786	-2.9786	0	%100
81	M55A	X	0	0	0	%100
82	M55A	Z	-7.133	-7.133	0	%100

Member Distributed Loads (BLC 54 : Structure Wi (30 Deg))

	Member Label	Direction	Start Magnitude...	End Magnitude ...	Start Locationft...	End Locationft...
1	M1	X	1.0122	1.0122	0	%100
2	M1	Z	-1.7531	-1.7531	0	%100
3	M3	X	1.0122	1.0122	0	%100
4	M3	Z	-1.7531	-1.7531	0	%100
5	M5	X	.0334	.0334	0	%100
6	M5	Z	-.0578	-.0578	0	%100
7	M6	X	.4975	.4975	0	%100
8	M6	Z	-.8617	-.8617	0	%100
9	M7	X	1.2047	1.2047	0	%100
10	M7	Z	-2.0866	-2.0866	0	%100
11	M8	X	.0052	.0052	0	%100
12	M8	Z	-.0089	-.0089	0	%100
13	M9	X	.5193	.5193	0	%100
14	M9	Z	-.8995	-.8995	0	%100
15	M10	X	1.2047	1.2047	0	%100
16	M10	Z	-2.0866	-2.0866	0	%100
17	M11	X	.0905	.0905	0	%100
18	M11	Z	-.1567	-.1567	0	%100
19	M12	X	1.348	1.348	0	%100
20	M12	Z	-2.3348	-2.3348	0	%100
21	M13	X	.0905	.0905	0	%100
22	M13	Z	-.1567	-.1567	0	%100
23	M14	X	1.348	1.348	0	%100
24	M14	Z	-2.3348	-2.3348	0	%100
25	M15	X	.7429	.7429	0	%100
26	M15	Z	-1.2868	-1.2868	0	%100
27	M16	X	1.2286	1.2286	0	%100
28	M16	Z	-2.1279	-2.1279	0	%100



Company : Colliers Engineering & Design
Designer :
Job Number : Project # 21777772
Model Name : Colliers Engineering & Design

Nov 20, 2023
11:41 AM
Checked By: _____

Member Distributed Loads (BLC 54 : Structure Wi (30 Deg)) (Continued)

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location[ft]	End Location[ft]
29	M17	X	.7429	.7429	0	%100
30	M17	Z	-1.2868	-1.2868	0	%100
31	M18	X	1.2286	1.2286	0	%100
32	M18	Z	-2.1279	-2.1279	0	%100
33	M19	X	.775	.775	0	%100
34	M19	Z	-1.3424	-1.3424	0	%100
35	M20	X	.7429	.7429	0	%100
36	M20	Z	-1.2868	-1.2868	0	%100
37	M21	X	.7429	.7429	0	%100
38	M21	Z	-1.2868	-1.2868	0	%100
39	M22	X	1.1348	1.1348	0	%100
40	M22	Z	-1.9656	-1.9656	0	%100
41	M23	X	1.1348	1.1348	0	%100
42	M23	Z	-1.9656	-1.9656	0	%100
43	M24	X	1.1107	1.1107	0	%100
44	M24	Z	-1.9238	-1.9238	0	%100
45	M25	X	.775	.775	0	%100
46	M25	Z	-1.3424	-1.3424	0	%100
47	M26	X	.7429	.7429	0	%100
48	M26	Z	-1.2868	-1.2868	0	%100
49	M27	X	.8651	.8651	0	%100
50	M27	Z	-1.4984	-1.4984	0	%100
51	M28	X	.7429	.7429	0	%100
52	M28	Z	-1.2868	-1.2868	0	%100
53	M29	X	.8651	.8651	0	%100
54	M29	Z	-1.4984	-1.4984	0	%100
55	M30	X	.775	.775	0	%100
56	M30	Z	-1.3424	-1.3424	0	%100
57	M31	X	.7429	.7429	0	%100
58	M31	Z	-1.2868	-1.2868	0	%100
59	M32	X	.7429	.7429	0	%100
60	M32	Z	-1.2868	-1.2868	0	%100
61	M33	X	1.1348	1.1348	0	%100
62	M33	Z	-1.9656	-1.9656	0	%100
63	M34	X	1.1348	1.1348	0	%100
64	M34	Z	-1.9656	-1.9656	0	%100
65	M35	X	1.1107	1.1107	0	%100
66	M35	Z	-1.9238	-1.9238	0	%100
67	M36	X	.775	.775	0	%100
68	M36	Z	-1.3424	-1.3424	0	%100
69	MP4A	X	1.4523	1.4523	0	%100
70	MP4A	Z	-2.5154	-2.5154	0	%100
71	MP3A	X	1.4523	1.4523	0	%100
72	MP3A	Z	-2.5154	-2.5154	0	%100
73	MP2A	X	1.4523	1.4523	0	%100
74	MP2A	Z	-2.5154	-2.5154	0	%100
75	MP1A	X	1.4523	1.4523	0	%100
76	MP1A	Z	-2.5154	-2.5154	0	%100
77	EQUIP	X	1.4893	1.4893	0	%100
78	EQUIP	Z	-2.5795	-2.5795	0	%100
79	M51	X	1.4893	1.4893	0	%100
80	M51	Z	-2.5795	-2.5795	0	%100
81	M55A	X	3.8e-5	3.8e-5	0	%100
82	M55A	Z	-6.6e-5	-6.6e-5	0	%100

Member Distributed Loads (BLC 55 : Structure Wi (60 Deg))

Member Label Direction Start Magnitude End Magnitude Start Location[ft] End Location[ft]



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 2177772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Distributed Loads (BLC 55 : Structure Wi (60 Deg)) (Continued)

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location	End Location
1	M1	X	.5844	.5844	0	%100
2	M1	Z	-.3374	-.3374	0	%100
3	M3	X	.5844	.5844	0	%100
4	M3	Z	-.3374	-.3374	0	%100
5	M5	X	.0667	.0667	0	%100
6	M5	Z	-.0385	-.0385	0	%100
7	M6	X	.8705	.8705	0	%100
8	M6	Z	-.5026	-.5026	0	%100
9	M7	X	.6955	.6955	0	%100
10	M7	Z	-.4016	-.4016	0	%100
11	M8	X	.1581	.1581	0	%100
12	M8	Z	-.0913	-.0913	0	%100
13	M9	X	.8214	.8214	0	%100
14	M9	Z	-.4742	-.4742	0	%100
15	M10	X	.6955	.6955	0	%100
16	M10	Z	-.4016	-.4016	0	%100
17	M11	X	.1807	.1807	0	%100
18	M11	Z	-.1043	-.1043	0	%100
19	M12	X	2.3587	2.3587	0	%100
20	M12	Z	-1.3618	-1.3618	0	%100
21	M13	X	.1807	.1807	0	%100
22	M13	Z	-.1043	-.1043	0	%100
23	M14	X	2.3587	2.3587	0	%100
24	M14	Z	-1.3618	-1.3618	0	%100
25	M15	X	1.9813	1.9813	0	%100
26	M15	Z	-1.1439	-1.1439	0	%100
27	M16	X	2.1348	2.1348	0	%100
28	M16	Z	-1.2325	-1.2325	0	%100
29	M17	X	1.9813	1.9813	0	%100
30	M17	Z	-1.1439	-1.1439	0	%100
31	M18	X	2.1348	2.1348	0	%100
32	M18	Z	-1.2325	-1.2325	0	%100
33	M19	X	2.0009	2.0009	0	%100
34	M19	Z	-1.1552	-1.1552	0	%100
35	M20	X	1.9813	1.9813	0	%100
36	M20	Z	-1.1439	-1.1439	0	%100
37	M21	X	1.9813	1.9813	0	%100
38	M21	Z	-1.1439	-1.1439	0	%100
39	M22	X	1.9656	1.9656	0	%100
40	M22	Z	-1.1348	-1.1348	0	%100
41	M23	X	1.9656	1.9656	0	%100
42	M23	Z	-1.1348	-1.1348	0	%100
43	M24	X	1.9238	1.9238	0	%100
44	M24	Z	-1.1107	-1.1107	0	%100
45	M25	X	2.0009	2.0009	0	%100
46	M25	Z	-1.1552	-1.1552	0	%100
47	M26	X	1.9813	1.9813	0	%100
48	M26	Z	-1.1439	-1.1439	0	%100
49	M27	X	1.5053	1.5053	0	%100
50	M27	Z	-.8691	-.8691	0	%100
51	M28	X	1.9813	1.9813	0	%100
52	M28	Z	-1.1439	-1.1439	0	%100
53	M29	X	1.5053	1.5053	0	%100
54	M29	Z	-.8691	-.8691	0	%100
55	M30	X	2.0009	2.0009	0	%100
56	M30	Z	-1.1552	-1.1552	0	%100
57	M31	X	1.9813	1.9813	0	%100



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 21777772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Distributed Loads (BLC 55 : Structure Wi (60 Deg)) (Continued)

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location[ft]	End Location[ft]
58	M31	Z	-1.1439	-1.1439	0	%100
59	M32	X	1.9813	1.9813	0	%100
60	M32	Z	-1.1439	-1.1439	0	%100
61	M33	X	1.9656	1.9656	0	%100
62	M33	Z	-1.1348	-1.1348	0	%100
63	M34	X	1.9656	1.9656	0	%100
64	M34	Z	-1.1348	-1.1348	0	%100
65	M35	X	1.9238	1.9238	0	%100
66	M35	Z	-1.1107	-1.1107	0	%100
67	M36	X	2.0009	2.0009	0	%100
68	M36	Z	-1.1552	-1.1552	0	%100
69	MP4A	X	2.5154	2.5154	0	%100
70	MP4A	Z	-1.4523	-1.4523	0	%100
71	MP3A	X	2.5154	2.5154	0	%100
72	MP3A	Z	-1.4523	-1.4523	0	%100
73	MP2A	X	2.5154	2.5154	0	%100
74	MP2A	Z	-1.4523	-1.4523	0	%100
75	MP1A	X	2.5154	2.5154	0	%100
76	MP1A	Z	-1.4523	-1.4523	0	%100
77	EQUIP	X	2.5795	2.5795	0	%100
78	EQUIP	Z	-1.4893	-1.4893	0	%100
79	M51	X	2.5795	2.5795	0	%100
80	M51	Z	-1.4893	-1.4893	0	%100
81	M55A	X	.6401	.6401	0	%100
82	M55A	Z	-.3695	-.3695	0	%100

Member Distributed Loads (BLC 56 : Structure Wi (90 Deg))

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location[ft]	End Location[ft]
1	M1	X	0	0	0	%100
2	M1	Z	0	0	0	%100
3	M3	X	0	0	0	%100
4	M3	Z	0	0	0	%100
5	M5	X	.5462	.5462	0	%100
6	M5	Z	0	0	0	%100
7	M6	X	.5462	.5462	0	%100
8	M6	Z	0	0	0	%100
9	M7	X	0	0	0	%100
10	M7	Z	0	0	0	%100
11	M8	X	.7083	.7083	0	%100
12	M8	Z	0	0	0	%100
13	M9	X	.4458	.4458	0	%100
14	M9	Z	0	0	0	%100
15	M10	X	0	0	0	%100
16	M10	Z	0	0	0	%100
17	M11	X	1.48	1.48	0	%100
18	M11	Z	0	0	0	%100
19	M12	X	1.48	1.48	0	%100
20	M12	Z	0	0	0	%100
21	M13	X	1.48	1.48	0	%100
22	M13	Z	0	0	0	%100
23	M14	X	1.48	1.48	0	%100
24	M14	Z	0	0	0	%100
25	M15	X	2.6889	2.6889	0	%100
26	M15	Z	0	0	0	%100
27	M16	X	2.1057	2.1057	0	%100
28	M16	Z	0	0	0	%100



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 2177772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Distributed Loads (BLC 56 : Structure Wi (90 Deg)) (Continued)

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location[ft]	End Location[ft]
29	M17	X	2.6889	2.6889	0	%100
30	M17	Z	0	0	0	%100
31	M18	X	2.1057	2.1057	0	%100
32	M18	Z	0	0	0	%100
33	M19	X	2.6906	2.6906	0	%100
34	M19	Z	0	0	0	%100
35	M20	X	2.6889	2.6889	0	%100
36	M20	Z	0	0	0	%100
37	M21	X	2.6889	2.6889	0	%100
38	M21	Z	0	0	0	%100
39	M22	X	2.2696	2.2696	0	%100
40	M22	Z	0	0	0	%100
41	M23	X	2.2696	2.2696	0	%100
42	M23	Z	0	0	0	%100
43	M24	X	2.2215	2.2215	0	%100
44	M24	Z	0	0	0	%100
45	M25	X	2.6906	2.6906	0	%100
46	M25	Z	0	0	0	%100
47	M26	X	2.6889	2.6889	0	%100
48	M26	Z	0	0	0	%100
49	M27	X	2.1057	2.1057	0	%100
50	M27	Z	0	0	0	%100
51	M28	X	2.6889	2.6889	0	%100
52	M28	Z	0	0	0	%100
53	M29	X	2.1057	2.1057	0	%100
54	M29	Z	0	0	0	%100
55	M30	X	2.6906	2.6906	0	%100
56	M30	Z	0	0	0	%100
57	M31	X	2.6889	2.6889	0	%100
58	M31	Z	0	0	0	%100
59	M32	X	2.6889	2.6889	0	%100
60	M32	Z	0	0	0	%100
61	M33	X	2.2696	2.2696	0	%100
62	M33	Z	0	0	0	%100
63	M34	X	2.2696	2.2696	0	%100
64	M34	Z	0	0	0	%100
65	M35	X	2.2215	2.2215	0	%100
66	M35	Z	0	0	0	%100
67	M36	X	2.6906	2.6906	0	%100
68	M36	Z	0	0	0	%100
69	MP4A	X	2.9046	2.9046	0	%100
70	MP4A	Z	0	0	0	%100
71	MP3A	X	2.9046	2.9046	0	%100
72	MP3A	Z	0	0	0	%100
73	MP2A	X	2.9046	2.9046	0	%100
74	MP2A	Z	0	0	0	%100
75	MP1A	X	2.9046	2.9046	0	%100
76	MP1A	Z	0	0	0	%100
77	EQUIP	X	2.9786	2.9786	0	%100
78	EQUIP	Z	0	0	0	%100
79	M51	X	2.9786	2.9786	0	%100
80	M51	Z	0	0	0	%100
81	M55A	X	2.1913	2.1913	0	%100
82	M55A	Z	0	0	0	%100

Member Distributed Loads (BLC 57 : Structure Wi (120 Deg))

Member Label Direction Start Magnitude End Magnitude Start Location[ft] End Location[ft]



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 21777772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Distributed Loads (BLC 57 : Structure Wi (120 Deg)) (Continued)

	Member Label	Direction	Start Magnitude	End Magnitude	Start Locationft...	End Locationft...
1	M1	X	.5844	.5844	0	%100
2	M1	Z	.3374	.3374	0	%100
3	M3	X	.5844	.5844	0	%100
4	M3	Z	.3374	.3374	0	%100
5	M5	X	.8705	.8705	0	%100
6	M5	Z	.5026	.5026	0	%100
7	M6	X	.0667	.0667	0	%100
8	M6	Z	.0385	.0385	0	%100
9	M7	X	.6955	.6955	0	%100
10	M7	Z	.4016	.4016	0	%100
11	M8	X	.9194	.9194	0	%100
12	M8	Z	.5308	.5308	0	%100
13	M9	X	.0289	.0289	0	%100
14	M9	Z	.0167	.0167	0	%100
15	M10	X	.6955	.6955	0	%100
16	M10	Z	.4016	.4016	0	%100
17	M11	X	2.3587	2.3587	0	%100
18	M11	Z	1.3618	1.3618	0	%100
19	M12	X	.1807	.1807	0	%100
20	M12	Z	.1043	.1043	0	%100
21	M13	X	2.3587	2.3587	0	%100
22	M13	Z	1.3618	1.3618	0	%100
23	M14	X	.1807	.1807	0	%100
24	M14	Z	.1043	.1043	0	%100
25	M15	X	1.9813	1.9813	0	%100
26	M15	Z	1.1439	1.1439	0	%100
27	M16	X	1.5053	1.5053	0	%100
28	M16	Z	.8691	.8691	0	%100
29	M17	X	1.9813	1.9813	0	%100
30	M17	Z	1.1439	1.1439	0	%100
31	M18	X	1.5053	1.5053	0	%100
32	M18	Z	.8691	.8691	0	%100
33	M19	X	2.0009	2.0009	0	%100
34	M19	Z	1.1552	1.1552	0	%100
35	M20	X	1.9813	1.9813	0	%100
36	M20	Z	1.1439	1.1439	0	%100
37	M21	X	1.9813	1.9813	0	%100
38	M21	Z	1.1439	1.1439	0	%100
39	M22	X	1.9656	1.9656	0	%100
40	M22	Z	1.1348	1.1348	0	%100
41	M23	X	1.9656	1.9656	0	%100
42	M23	Z	1.1348	1.1348	0	%100
43	M24	X	1.9238	1.9238	0	%100
44	M24	Z	1.1107	1.1107	0	%100
45	M25	X	2.0009	2.0009	0	%100
46	M25	Z	1.1552	1.1552	0	%100
47	M26	X	1.9813	1.9813	0	%100
48	M26	Z	1.1439	1.1439	0	%100
49	M27	X	2.1348	2.1348	0	%100
50	M27	Z	1.2325	1.2325	0	%100
51	M28	X	1.9813	1.9813	0	%100
52	M28	Z	1.1439	1.1439	0	%100
53	M29	X	2.1348	2.1348	0	%100
54	M29	Z	1.2325	1.2325	0	%100
55	M30	X	2.0009	2.0009	0	%100
56	M30	Z	1.1552	1.1552	0	%100
57	M31	X	1.9813	1.9813	0	%100



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 21777772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Distributed Loads (BLC 57 : Structure Wi (120 Deg)) (Continued)

	Member Label	Direction	Start Magnitude...	End Magnitude[...	Start Location[ft...	End Location[ft...
58	M31	Z	1.1439	1.1439	0	%100
59	M32	X	1.9813	1.9813	0	%100
60	M32	Z	1.1439	1.1439	0	%100
61	M33	X	1.9656	1.9656	0	%100
62	M33	Z	1.1348	1.1348	0	%100
63	M34	X	1.9656	1.9656	0	%100
64	M34	Z	1.1348	1.1348	0	%100
65	M35	X	1.9238	1.9238	0	%100
66	M35	Z	1.1107	1.1107	0	%100
67	M36	X	2.0009	2.0009	0	%100
68	M36	Z	1.1552	1.1552	0	%100
69	MP4A	X	2.5154	2.5154	0	%100
70	MP4A	Z	1.4523	1.4523	0	%100
71	MP3A	X	2.5154	2.5154	0	%100
72	MP3A	Z	1.4523	1.4523	0	%100
73	MP2A	X	2.5154	2.5154	0	%100
74	MP2A	Z	1.4523	1.4523	0	%100
75	MP1A	X	2.5154	2.5154	0	%100
76	MP1A	Z	1.4523	1.4523	0	%100
77	EQUIP	X	2.5795	2.5795	0	%100
78	EQUIP	Z	1.4893	1.4893	0	%100
79	M51	X	2.5795	2.5795	0	%100
80	M51	Z	1.4893	1.4893	0	%100
81	M55A	X	2.5154	2.5154	0	%100
82	M55A	Z	1.4523	1.4523	0	%100

Member Distributed Loads (BLC 58 : Structure Wi (150 Deg))

	Member Label	Direction	Start Magnitude...	End Magnitude[...	Start Location[ft...	End Location[ft...
1	M1	X	1.0122	1.0122	0	%100
2	M1	Z	1.7531	1.7531	0	%100
3	M3	X	1.0122	1.0122	0	%100
4	M3	Z	1.7531	1.7531	0	%100
5	M5	X	.4975	.4975	0	%100
6	M5	Z	.8617	.8617	0	%100
7	M6	X	.0334	.0334	0	%100
8	M6	Z	.0578	.0578	0	%100
9	M7	X	1.2047	1.2047	0	%100
10	M7	Z	2.0866	2.0866	0	%100
11	M8	X	.4447	.4447	0	%100
12	M8	Z	.7702	.7702	0	%100
13	M9	X	.0618	.0618	0	%100
14	M9	Z	.107	.107	0	%100
15	M10	X	1.2047	1.2047	0	%100
16	M10	Z	2.0866	2.0866	0	%100
17	M11	X	1.348	1.348	0	%100
18	M11	Z	2.3348	2.3348	0	%100
19	M12	X	.0905	.0905	0	%100
20	M12	Z	.1567	.1567	0	%100
21	M13	X	1.348	1.348	0	%100
22	M13	Z	2.3348	2.3348	0	%100
23	M14	X	.0905	.0905	0	%100
24	M14	Z	.1567	.1567	0	%100
25	M15	X	.7429	.7429	0	%100
26	M15	Z	1.2868	1.2868	0	%100
27	M16	X	.8651	.8651	0	%100
28	M16	Z	1.4984	1.4984	0	%100



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 21777772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Distributed Loads (BLC 58 : Structure Wi (150 Deg)) (Continued)

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location(ft)	End Location(ft)
29	M17	X	.7429	.7429	0	%100
30	M17	Z	1.2868	1.2868	0	%100
31	M18	X	.8651	.8651	0	%100
32	M18	Z	1.4984	1.4984	0	%100
33	M19	X	.775	.775	0	%100
34	M19	Z	1.3424	1.3424	0	%100
35	M20	X	.7429	.7429	0	%100
36	M20	Z	1.2868	1.2868	0	%100
37	M21	X	.7429	.7429	0	%100
38	M21	Z	1.2868	1.2868	0	%100
39	M22	X	1.1348	1.1348	0	%100
40	M22	Z	1.9656	1.9656	0	%100
41	M23	X	1.1348	1.1348	0	%100
42	M23	Z	1.9656	1.9656	0	%100
43	M24	X	1.1107	1.1107	0	%100
44	M24	Z	1.9238	1.9238	0	%100
45	M25	X	.775	.775	0	%100
46	M25	Z	1.3424	1.3424	0	%100
47	M26	X	.7429	.7429	0	%100
48	M26	Z	1.2868	1.2868	0	%100
49	M27	X	1.2286	1.2286	0	%100
50	M27	Z	2.1279	2.1279	0	%100
51	M28	X	.7429	.7429	0	%100
52	M28	Z	1.2868	1.2868	0	%100
53	M29	X	1.2286	1.2286	0	%100
54	M29	Z	2.1279	2.1279	0	%100
55	M30	X	.775	.775	0	%100
56	M30	Z	1.3424	1.3424	0	%100
57	M31	X	.7429	.7429	0	%100
58	M31	Z	1.2868	1.2868	0	%100
59	M32	X	.7429	.7429	0	%100
60	M32	Z	1.2868	1.2868	0	%100
61	M33	X	1.1348	1.1348	0	%100
62	M33	Z	1.9656	1.9656	0	%100
63	M34	X	1.1348	1.1348	0	%100
64	M34	Z	1.9656	1.9656	0	%100
65	M35	X	1.1107	1.1107	0	%100
66	M35	Z	1.9238	1.9238	0	%100
67	M36	X	.775	.775	0	%100
68	M36	Z	1.3424	1.3424	0	%100
69	MP4A	X	1.4523	1.4523	0	%100
70	MP4A	Z	2.5154	2.5154	0	%100
71	MP3A	X	1.4523	1.4523	0	%100
72	MP3A	Z	2.5154	2.5154	0	%100
73	MP2A	X	1.4523	1.4523	0	%100
74	MP2A	Z	2.5154	2.5154	0	%100
75	MP1A	X	1.4523	1.4523	0	%100
76	MP1A	Z	2.5154	2.5154	0	%100
77	EQUIP	X	1.4893	1.4893	0	%100
78	EQUIP	Z	2.5795	2.5795	0	%100
79	M51	X	1.4893	1.4893	0	%100
80	M51	Z	2.5795	2.5795	0	%100
81	M55A	X	1.0828	1.0828	0	%100
82	M55A	Z	1.8754	1.8754	0	%100

Member Distributed Loads (BLC 59 : Structure Wi (180 Deg))

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location(ft)	End Location(ft)
--	--------------	-----------	-----------------	---------------	--------------------	------------------



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 21777772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Distributed Loads (BLC 59 : Structure Wi (180 Deg)) (Continued)

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location	End Location
1	M1	X	0	0	0	%100
2	M1	Z	2.6991	2.6991	0	%100
3	M3	X	0	0	0	%100
4	M3	Z	2.6991	2.6991	0	%100
5	M5	X	0	0	0	%100
6	M5	Z	.5258	.5258	0	%100
7	M6	X	0	0	0	%100
8	M6	Z	.5258	.5258	0	%100
9	M7	X	0	0	0	%100
10	M7	Z	3.2126	3.2126	0	%100
11	M8	X	0	0	0	%100
12	M8	Z	.3637	.3637	0	%100
13	M9	X	0	0	0	%100
14	M9	Z	.6262	.6262	0	%100
15	M10	X	0	0	0	%100
16	M10	Z	3.2126	3.2126	0	%100
17	M11	X	0	0	0	%100
18	M11	Z	1.4246	1.4246	0	%100
19	M12	X	0	0	0	%100
20	M12	Z	1.4246	1.4246	0	%100
21	M13	X	0	0	0	%100
22	M13	Z	1.4246	1.4246	0	%100
23	M14	X	0	0	0	%100
24	M14	Z	1.4246	1.4246	0	%100
25	M15	X	0	0	0	%100
26	M15	Z	1.0848	1.0848	0	%100
27	M16	X	0	0	0	%100
28	M16	Z	2.0897	2.0897	0	%100
29	M17	X	0	0	0	%100
30	M17	Z	1.0848	1.0848	0	%100
31	M18	X	0	0	0	%100
32	M18	Z	2.0897	2.0897	0	%100
33	M19	X	0	0	0	%100
34	M19	Z	1.1699	1.1699	0	%100
35	M20	X	0	0	0	%100
36	M20	Z	1.0848	1.0848	0	%100
37	M21	X	0	0	0	%100
38	M21	Z	1.0848	1.0848	0	%100
39	M22	X	0	0	0	%100
40	M22	Z	2.2696	2.2696	0	%100
41	M23	X	0	0	0	%100
42	M23	Z	2.2696	2.2696	0	%100
43	M24	X	0	0	0	%100
44	M24	Z	2.2215	2.2215	0	%100
45	M25	X	0	0	0	%100
46	M25	Z	1.1699	1.1699	0	%100
47	M26	X	0	0	0	%100
48	M26	Z	1.0848	1.0848	0	%100
49	M27	X	0	0	0	%100
50	M27	Z	2.0897	2.0897	0	%100
51	M28	X	0	0	0	%100
52	M28	Z	1.0848	1.0848	0	%100
53	M29	X	0	0	0	%100
54	M29	Z	2.0897	2.0897	0	%100
55	M30	X	0	0	0	%100
56	M30	Z	1.1699	1.1699	0	%100
57	M31	X	0	0	0	%100



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 21777772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Distributed Loads (BLC 59 : Structure Wi (180 Deg)) (Continued)

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location	End Location
58	M31	Z	1.0848	1.0848	0	%100
59	M32	X	0	0	0	%100
60	M32	Z	1.0848	1.0848	0	%100
61	M33	X	0	0	0	%100
62	M33	Z	2.2696	2.2696	0	%100
63	M34	X	0	0	0	%100
64	M34	Z	2.2696	2.2696	0	%100
65	M35	X	0	0	0	%100
66	M35	Z	2.2215	2.2215	0	%100
67	M36	X	0	0	0	%100
68	M36	Z	1.1699	1.1699	0	%100
69	MP4A	X	0	0	0	%100
70	MP4A	Z	2.9046	2.9046	0	%100
71	MP3A	X	0	0	0	%100
72	MP3A	Z	2.9046	2.9046	0	%100
73	MP2A	X	0	0	0	%100
74	MP2A	Z	2.9046	2.9046	0	%100
75	MP1A	X	0	0	0	%100
76	MP1A	Z	2.9046	2.9046	0	%100
77	EQUIP	X	0	0	0	%100
78	EQUIP	Z	2.9786	2.9786	0	%100
79	M51	X	0	0	0	%100
80	M51	Z	2.9786	2.9786	0	%100
81	M55A	X	0	0	0	%100
82	M55A	Z	.7133	.7133	0	%100

Member Distributed Loads (BLC 60 : Structure Wi (210 Deg))

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location	End Location
1	M1	X	-1.0122	-1.0122	0	%100
2	M1	Z	1.7531	1.7531	0	%100
3	M3	X	-1.0122	-1.0122	0	%100
4	M3	Z	1.7531	1.7531	0	%100
5	M5	X	-.0334	-.0334	0	%100
6	M5	Z	.0578	.0578	0	%100
7	M6	X	-.4975	-.4975	0	%100
8	M6	Z	.8617	.8617	0	%100
9	M7	X	-1.2047	-1.2047	0	%100
10	M7	Z	2.0866	2.0866	0	%100
11	M8	X	-.0052	-.0052	0	%100
12	M8	Z	.0089	.0089	0	%100
13	M9	X	-.5193	-.5193	0	%100
14	M9	Z	.8995	.8995	0	%100
15	M10	X	-1.2047	-1.2047	0	%100
16	M10	Z	2.0866	2.0866	0	%100
17	M11	X	-.0905	-.0905	0	%100
18	M11	Z	.1567	.1567	0	%100
19	M12	X	-1.348	-1.348	0	%100
20	M12	Z	2.3348	2.3348	0	%100
21	M13	X	-.0905	-.0905	0	%100
22	M13	Z	.1567	.1567	0	%100
23	M14	X	-1.348	-1.348	0	%100
24	M14	Z	2.3348	2.3348	0	%100
25	M15	X	-.7429	-.7429	0	%100
26	M15	Z	1.2868	1.2868	0	%100
27	M16	X	-1.2286	-1.2286	0	%100
28	M16	Z	2.1279	2.1279	0	%100



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 21777772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Distributed Loads (BLC 60 : Structure Wi (210 Deg)) (Continued)

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location	End Location
29	M17	X	-7429	-7429	0	%100
30	M17	Z	1.2868	1.2868	0	%100
31	M18	X	-1.2286	-1.2286	0	%100
32	M18	Z	2.1279	2.1279	0	%100
33	M19	X	-775	-775	0	%100
34	M19	Z	1.3424	1.3424	0	%100
35	M20	X	-7429	-7429	0	%100
36	M20	Z	1.2868	1.2868	0	%100
37	M21	X	-7429	-7429	0	%100
38	M21	Z	1.2868	1.2868	0	%100
39	M22	X	-1.1348	-1.1348	0	%100
40	M22	Z	1.9656	1.9656	0	%100
41	M23	X	-1.1348	-1.1348	0	%100
42	M23	Z	1.9656	1.9656	0	%100
43	M24	X	-1.1107	-1.1107	0	%100
44	M24	Z	1.9238	1.9238	0	%100
45	M25	X	-775	-775	0	%100
46	M25	Z	1.3424	1.3424	0	%100
47	M26	X	-7429	-7429	0	%100
48	M26	Z	1.2868	1.2868	0	%100
49	M27	X	-8651	-8651	0	%100
50	M27	Z	1.4984	1.4984	0	%100
51	M28	X	-7429	-7429	0	%100
52	M28	Z	1.2868	1.2868	0	%100
53	M29	X	-8651	-8651	0	%100
54	M29	Z	1.4984	1.4984	0	%100
55	M30	X	-775	-775	0	%100
56	M30	Z	1.3424	1.3424	0	%100
57	M31	X	-7429	-7429	0	%100
58	M31	Z	1.2868	1.2868	0	%100
59	M32	X	-7429	-7429	0	%100
60	M32	Z	1.2868	1.2868	0	%100
61	M33	X	-1.1348	-1.1348	0	%100
62	M33	Z	1.9656	1.9656	0	%100
63	M34	X	-1.1348	-1.1348	0	%100
64	M34	Z	1.9656	1.9656	0	%100
65	M35	X	-1.1107	-1.1107	0	%100
66	M35	Z	1.9238	1.9238	0	%100
67	M36	X	-775	-775	0	%100
68	M36	Z	1.3424	1.3424	0	%100
69	MP4A	X	-1.4523	-1.4523	0	%100
70	MP4A	Z	2.5154	2.5154	0	%100
71	MP3A	X	-1.4523	-1.4523	0	%100
72	MP3A	Z	2.5154	2.5154	0	%100
73	MP2A	X	-1.4523	-1.4523	0	%100
74	MP2A	Z	2.5154	2.5154	0	%100
75	MP1A	X	-1.4523	-1.4523	0	%100
76	MP1A	Z	2.5154	2.5154	0	%100
77	EQUIP	X	-1.4893	-1.4893	0	%100
78	EQUIP	Z	2.5795	2.5795	0	%100
79	M51	X	-1.4893	-1.4893	0	%100
80	M51	Z	2.5795	2.5795	0	%100
81	M55A	X	-3.8e-5	-3.8e-5	0	%100
82	M55A	Z	6.6e-5	6.6e-5	0	%100

Member Distributed Loads (BLC 61 : Structure Wi (240 Deg))

Member Label Direction Start Magnitude End Magnitude Start Location End Location



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 21777772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Distributed Loads (BLC 61 : Structure Wi (240 Deg)) (Continued)

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location(ft)	End Location(ft)
1	M1	X	- .5844	- .5844	0	%100
2	M1	Z	.3374	.3374	0	%100
3	M3	X	- .5844	- .5844	0	%100
4	M3	Z	.3374	.3374	0	%100
5	M5	X	- .0667	- .0667	0	%100
6	M5	Z	.0385	.0385	0	%100
7	M6	X	- .8705	- .8705	0	%100
8	M6	Z	.5026	.5026	0	%100
9	M7	X	- .6955	- .6955	0	%100
10	M7	Z	.4016	.4016	0	%100
11	M8	X	- .1581	- .1581	0	%100
12	M8	Z	.0913	.0913	0	%100
13	M9	X	- .8214	- .8214	0	%100
14	M9	Z	.4742	.4742	0	%100
15	M10	X	- .6955	- .6955	0	%100
16	M10	Z	.4016	.4016	0	%100
17	M11	X	- .1807	- .1807	0	%100
18	M11	Z	.1043	.1043	0	%100
19	M12	X	- 2.3587	- 2.3587	0	%100
20	M12	Z	1.3618	1.3618	0	%100
21	M13	X	- .1807	- .1807	0	%100
22	M13	Z	.1043	.1043	0	%100
23	M14	X	- 2.3587	- 2.3587	0	%100
24	M14	Z	1.3618	1.3618	0	%100
25	M15	X	- 1.9813	- 1.9813	0	%100
26	M15	Z	1.1439	1.1439	0	%100
27	M16	X	- 2.1348	- 2.1348	0	%100
28	M16	Z	1.2325	1.2325	0	%100
29	M17	X	- 1.9813	- 1.9813	0	%100
30	M17	Z	1.1439	1.1439	0	%100
31	M18	X	- 2.1348	- 2.1348	0	%100
32	M18	Z	1.2325	1.2325	0	%100
33	M19	X	- 2.0009	- 2.0009	0	%100
34	M19	Z	1.1552	1.1552	0	%100
35	M20	X	- 1.9813	- 1.9813	0	%100
36	M20	Z	1.1439	1.1439	0	%100
37	M21	X	- 1.9813	- 1.9813	0	%100
38	M21	Z	1.1439	1.1439	0	%100
39	M22	X	- 1.9656	- 1.9656	0	%100
40	M22	Z	1.1348	1.1348	0	%100
41	M23	X	- 1.9656	- 1.9656	0	%100
42	M23	Z	1.1348	1.1348	0	%100
43	M24	X	- 1.9238	- 1.9238	0	%100
44	M24	Z	1.1107	1.1107	0	%100
45	M25	X	- 2.0009	- 2.0009	0	%100
46	M25	Z	1.1552	1.1552	0	%100
47	M26	X	- 1.9813	- 1.9813	0	%100
48	M26	Z	1.1439	1.1439	0	%100
49	M27	X	- 1.5053	- 1.5053	0	%100
50	M27	Z	.8691	.8691	0	%100
51	M28	X	- 1.9813	- 1.9813	0	%100
52	M28	Z	1.1439	1.1439	0	%100
53	M29	X	- 1.5053	- 1.5053	0	%100
54	M29	Z	.8691	.8691	0	%100
55	M30	X	- 2.0009	- 2.0009	0	%100
56	M30	Z	1.1552	1.1552	0	%100
57	M31	X	- 1.9813	- 1.9813	0	%100



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 2177772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Distributed Loads (BLC 61 : Structure Wi (240 Deg)) (Continued)

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location(ft)	End Location(ft)
58	M31	Z	1.1439	1.1439	0	%100
59	M32	X	-1.9813	-1.9813	0	%100
60	M32	Z	1.1439	1.1439	0	%100
61	M33	X	-1.9656	-1.9656	0	%100
62	M33	Z	1.1348	1.1348	0	%100
63	M34	X	-1.9656	-1.9656	0	%100
64	M34	Z	1.1348	1.1348	0	%100
65	M35	X	-1.9238	-1.9238	0	%100
66	M35	Z	1.1107	1.1107	0	%100
67	M36	X	-2.0009	-2.0009	0	%100
68	M36	Z	1.1552	1.1552	0	%100
69	MP4A	X	-2.5154	-2.5154	0	%100
70	MP4A	Z	1.4523	1.4523	0	%100
71	MP3A	X	-2.5154	-2.5154	0	%100
72	MP3A	Z	1.4523	1.4523	0	%100
73	MP2A	X	-2.5154	-2.5154	0	%100
74	MP2A	Z	1.4523	1.4523	0	%100
75	MP1A	X	-2.5154	-2.5154	0	%100
76	MP1A	Z	1.4523	1.4523	0	%100
77	EQUIP	X	-2.5795	-2.5795	0	%100
78	EQUIP	Z	1.4893	1.4893	0	%100
79	M51	X	-2.5795	-2.5795	0	%100
80	M51	Z	1.4893	1.4893	0	%100
81	M55A	X	-.6401	-.6401	0	%100
82	M55A	Z	.3695	.3695	0	%100

Member Distributed Loads (BLC 62 : Structure Wi (270 Deg))

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location(ft)	End Location(ft)
1	M1	X	0	0	0	%100
2	M1	Z	0	0	0	%100
3	M3	X	0	0	0	%100
4	M3	Z	0	0	0	%100
5	M5	X	-.5462	-.5462	0	%100
6	M5	Z	0	0	0	%100
7	M6	X	-.5462	-.5462	0	%100
8	M6	Z	0	0	0	%100
9	M7	X	0	0	0	%100
10	M7	Z	0	0	0	%100
11	M8	X	-.7083	-.7083	0	%100
12	M8	Z	0	0	0	%100
13	M9	X	-.4458	-.4458	0	%100
14	M9	Z	0	0	0	%100
15	M10	X	0	0	0	%100
16	M10	Z	0	0	0	%100
17	M11	X	-1.48	-1.48	0	%100
18	M11	Z	0	0	0	%100
19	M12	X	-1.48	-1.48	0	%100
20	M12	Z	0	0	0	%100
21	M13	X	-1.48	-1.48	0	%100
22	M13	Z	0	0	0	%100
23	M14	X	-1.48	-1.48	0	%100
24	M14	Z	0	0	0	%100
25	M15	X	-2.6889	-2.6889	0	%100
26	M15	Z	0	0	0	%100
27	M16	X	-2.1057	-2.1057	0	%100
28	M16	Z	0	0	0	%100



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 21777772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Distributed Loads (BLC 62 : Structure Wi (270 Deg)) (Continued)

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location	End Location
29	M17	X	-2.6889	-2.6889	0	%100
30	M17	Z	0	0	0	%100
31	M18	X	-2.1057	-2.1057	0	%100
32	M18	Z	0	0	0	%100
33	M19	X	-2.6906	-2.6906	0	%100
34	M19	Z	0	0	0	%100
35	M20	X	-2.6889	-2.6889	0	%100
36	M20	Z	0	0	0	%100
37	M21	X	-2.6889	-2.6889	0	%100
38	M21	Z	0	0	0	%100
39	M22	X	-2.2696	-2.2696	0	%100
40	M22	Z	0	0	0	%100
41	M23	X	-2.2696	-2.2696	0	%100
42	M23	Z	0	0	0	%100
43	M24	X	-2.2215	-2.2215	0	%100
44	M24	Z	0	0	0	%100
45	M25	X	-2.6906	-2.6906	0	%100
46	M25	Z	0	0	0	%100
47	M26	X	-2.6889	-2.6889	0	%100
48	M26	Z	0	0	0	%100
49	M27	X	-2.1057	-2.1057	0	%100
50	M27	Z	0	0	0	%100
51	M28	X	-2.6889	-2.6889	0	%100
52	M28	Z	0	0	0	%100
53	M29	X	-2.1057	-2.1057	0	%100
54	M29	Z	0	0	0	%100
55	M30	X	-2.6906	-2.6906	0	%100
56	M30	Z	0	0	0	%100
57	M31	X	-2.6889	-2.6889	0	%100
58	M31	Z	0	0	0	%100
59	M32	X	-2.6889	-2.6889	0	%100
60	M32	Z	0	0	0	%100
61	M33	X	-2.2696	-2.2696	0	%100
62	M33	Z	0	0	0	%100
63	M34	X	-2.2696	-2.2696	0	%100
64	M34	Z	0	0	0	%100
65	M35	X	-2.2215	-2.2215	0	%100
66	M35	Z	0	0	0	%100
67	M36	X	-2.6906	-2.6906	0	%100
68	M36	Z	0	0	0	%100
69	MP4A	X	-2.9046	-2.9046	0	%100
70	MP4A	Z	0	0	0	%100
71	MP3A	X	-2.9046	-2.9046	0	%100
72	MP3A	Z	0	0	0	%100
73	MP2A	X	-2.9046	-2.9046	0	%100
74	MP2A	Z	0	0	0	%100
75	MP1A	X	-2.9046	-2.9046	0	%100
76	MP1A	Z	0	0	0	%100
77	EQUIP	X	-2.9786	-2.9786	0	%100
78	EQUIP	Z	0	0	0	%100
79	M51	X	-2.9786	-2.9786	0	%100
80	M51	Z	0	0	0	%100
81	M55A	X	-2.1913	-2.1913	0	%100
82	M55A	Z	0	0	0	%100

Member Distributed Loads (BLC 63 : Structure Wi (300 Deg))

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location	End Location
--	--------------	-----------	-----------------	---------------	----------------	--------------



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 2177772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Distributed Loads (BLC 63 : Structure Wi (300 Deg)) (Continued)

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location[ft]	End Location[ft]
1	M1	X	-5844	-5844	0	%100
2	M1	Z	-3374	-3374	0	%100
3	M3	X	-5844	-5844	0	%100
4	M3	Z	-3374	-3374	0	%100
5	M5	X	-8705	-8705	0	%100
6	M5	Z	-5026	-5026	0	%100
7	M6	X	-0667	-0667	0	%100
8	M6	Z	-0385	-0385	0	%100
9	M7	X	-6955	-6955	0	%100
10	M7	Z	-4016	-4016	0	%100
11	M8	X	-9194	-9194	0	%100
12	M8	Z	-5308	-5308	0	%100
13	M9	X	-0289	-0289	0	%100
14	M9	Z	-0167	-0167	0	%100
15	M10	X	-6955	-6955	0	%100
16	M10	Z	-4016	-4016	0	%100
17	M11	X	-2.3587	-2.3587	0	%100
18	M11	Z	-1.3618	-1.3618	0	%100
19	M12	X	-1.807	-1.807	0	%100
20	M12	Z	-1.043	-1.043	0	%100
21	M13	X	-2.3587	-2.3587	0	%100
22	M13	Z	-1.3618	-1.3618	0	%100
23	M14	X	-1.807	-1.807	0	%100
24	M14	Z	-1.043	-1.043	0	%100
25	M15	X	-1.9813	-1.9813	0	%100
26	M15	Z	-1.1439	-1.1439	0	%100
27	M16	X	-1.5053	-1.5053	0	%100
28	M16	Z	-8691	-8691	0	%100
29	M17	X	-1.9813	-1.9813	0	%100
30	M17	Z	-1.1439	-1.1439	0	%100
31	M18	X	-1.5053	-1.5053	0	%100
32	M18	Z	-8691	-8691	0	%100
33	M19	X	-2.0009	-2.0009	0	%100
34	M19	Z	-1.1552	-1.1552	0	%100
35	M20	X	-1.9813	-1.9813	0	%100
36	M20	Z	-1.1439	-1.1439	0	%100
37	M21	X	-1.9813	-1.9813	0	%100
38	M21	Z	-1.1439	-1.1439	0	%100
39	M22	X	-1.9656	-1.9656	0	%100
40	M22	Z	-1.1348	-1.1348	0	%100
41	M23	X	-1.9656	-1.9656	0	%100
42	M23	Z	-1.1348	-1.1348	0	%100
43	M24	X	-1.9238	-1.9238	0	%100
44	M24	Z	-1.1107	-1.1107	0	%100
45	M25	X	-2.0009	-2.0009	0	%100
46	M25	Z	-1.1552	-1.1552	0	%100
47	M26	X	-1.9813	-1.9813	0	%100
48	M26	Z	-1.1439	-1.1439	0	%100
49	M27	X	-2.1348	-2.1348	0	%100
50	M27	Z	-1.2325	-1.2325	0	%100
51	M28	X	-1.9813	-1.9813	0	%100
52	M28	Z	-1.1439	-1.1439	0	%100
53	M29	X	-2.1348	-2.1348	0	%100
54	M29	Z	-1.2325	-1.2325	0	%100
55	M30	X	-2.0009	-2.0009	0	%100
56	M30	Z	-1.1552	-1.1552	0	%100
57	M31	X	-1.9813	-1.9813	0	%100



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 21777772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Distributed Loads (BLC 63 : Structure Wi (300 Deg)) (Continued)

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location	End Location
58	M31	Z	-1.1439	-1.1439	0	%100
59	M32	X	-1.9813	-1.9813	0	%100
60	M32	Z	-1.1439	-1.1439	0	%100
61	M33	X	-1.9656	-1.9656	0	%100
62	M33	Z	-1.1348	-1.1348	0	%100
63	M34	X	-1.9656	-1.9656	0	%100
64	M34	Z	-1.1348	-1.1348	0	%100
65	M35	X	-1.9238	-1.9238	0	%100
66	M35	Z	-1.1107	-1.1107	0	%100
67	M36	X	-2.0009	-2.0009	0	%100
68	M36	Z	-1.1552	-1.1552	0	%100
69	MP4A	X	-2.5154	-2.5154	0	%100
70	MP4A	Z	-1.4523	-1.4523	0	%100
71	MP3A	X	-2.5154	-2.5154	0	%100
72	MP3A	Z	-1.4523	-1.4523	0	%100
73	MP2A	X	-2.5154	-2.5154	0	%100
74	MP2A	Z	-1.4523	-1.4523	0	%100
75	MP1A	X	-2.5154	-2.5154	0	%100
76	MP1A	Z	-1.4523	-1.4523	0	%100
77	EQUIP	X	-2.5795	-2.5795	0	%100
78	EQUIP	Z	-1.4893	-1.4893	0	%100
79	M51	X	-2.5795	-2.5795	0	%100
80	M51	Z	-1.4893	-1.4893	0	%100
81	M55A	X	-2.5154	-2.5154	0	%100
82	M55A	Z	-1.4523	-1.4523	0	%100

Member Distributed Loads (BLC 64 : Structure Wi (330 Deg))

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location	End Location
1	M1	X	-1.0122	-1.0122	0	%100
2	M1	Z	-1.7531	-1.7531	0	%100
3	M3	X	-1.0122	-1.0122	0	%100
4	M3	Z	-1.7531	-1.7531	0	%100
5	M5	X	-4975	-4975	0	%100
6	M5	Z	-8617	-8617	0	%100
7	M6	X	-0334	-0334	0	%100
8	M6	Z	-0578	-0578	0	%100
9	M7	X	-1.2047	-1.2047	0	%100
10	M7	Z	-2.0866	-2.0866	0	%100
11	M8	X	-4447	-4447	0	%100
12	M8	Z	-7702	-7702	0	%100
13	M9	X	-0618	-0618	0	%100
14	M9	Z	-107	-107	0	%100
15	M10	X	-1.2047	-1.2047	0	%100
16	M10	Z	-2.0866	-2.0866	0	%100
17	M11	X	-1.348	-1.348	0	%100
18	M11	Z	-2.3348	-2.3348	0	%100
19	M12	X	-0905	-0905	0	%100
20	M12	Z	-1567	-1567	0	%100
21	M13	X	-1.348	-1.348	0	%100
22	M13	Z	-2.3348	-2.3348	0	%100
23	M14	X	-0905	-0905	0	%100
24	M14	Z	-1567	-1567	0	%100
25	M15	X	-7429	-7429	0	%100
26	M15	Z	-1.2868	-1.2868	0	%100
27	M16	X	-8651	-8651	0	%100
28	M16	Z	-1.4984	-1.4984	0	%100



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 21777772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Distributed Loads (BLC 64 : Structure Wi (330 Deg)) (Continued)

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location	End Location
29	M17	X	-.7429	-.7429	0	%100
30	M17	Z	-1.2868	-1.2868	0	%100
31	M18	X	-.8651	-.8651	0	%100
32	M18	Z	-1.4984	-1.4984	0	%100
33	M19	X	-.775	-.775	0	%100
34	M19	Z	-1.3424	-1.3424	0	%100
35	M20	X	-.7429	-.7429	0	%100
36	M20	Z	-1.2868	-1.2868	0	%100
37	M21	X	-.7429	-.7429	0	%100
38	M21	Z	-1.2868	-1.2868	0	%100
39	M22	X	-1.1348	-1.1348	0	%100
40	M22	Z	-1.9656	-1.9656	0	%100
41	M23	X	-1.1348	-1.1348	0	%100
42	M23	Z	-1.9656	-1.9656	0	%100
43	M24	X	-1.1107	-1.1107	0	%100
44	M24	Z	-1.9238	-1.9238	0	%100
45	M25	X	-.775	-.775	0	%100
46	M25	Z	-1.3424	-1.3424	0	%100
47	M26	X	-.7429	-.7429	0	%100
48	M26	Z	-1.2868	-1.2868	0	%100
49	M27	X	-1.2286	-1.2286	0	%100
50	M27	Z	-2.1279	-2.1279	0	%100
51	M28	X	-.7429	-.7429	0	%100
52	M28	Z	-1.2868	-1.2868	0	%100
53	M29	X	-1.2286	-1.2286	0	%100
54	M29	Z	-2.1279	-2.1279	0	%100
55	M30	X	-.775	-.775	0	%100
56	M30	Z	-1.3424	-1.3424	0	%100
57	M31	X	-.7429	-.7429	0	%100
58	M31	Z	-1.2868	-1.2868	0	%100
59	M32	X	-.7429	-.7429	0	%100
60	M32	Z	-1.2868	-1.2868	0	%100
61	M33	X	-1.1348	-1.1348	0	%100
62	M33	Z	-1.9656	-1.9656	0	%100
63	M34	X	-1.1348	-1.1348	0	%100
64	M34	Z	-1.9656	-1.9656	0	%100
65	M35	X	-1.1107	-1.1107	0	%100
66	M35	Z	-1.9238	-1.9238	0	%100
67	M36	X	-.775	-.775	0	%100
68	M36	Z	-1.3424	-1.3424	0	%100
69	MP4A	X	-1.4523	-1.4523	0	%100
70	MP4A	Z	-2.5154	-2.5154	0	%100
71	MP3A	X	-1.4523	-1.4523	0	%100
72	MP3A	Z	-2.5154	-2.5154	0	%100
73	MP2A	X	-1.4523	-1.4523	0	%100
74	MP2A	Z	-2.5154	-2.5154	0	%100
75	MP1A	X	-1.4523	-1.4523	0	%100
76	MP1A	Z	-2.5154	-2.5154	0	%100
77	EQUIP	X	-1.4893	-1.4893	0	%100
78	EQUIP	Z	-2.5795	-2.5795	0	%100
79	M51	X	-1.4893	-1.4893	0	%100
80	M51	Z	-2.5795	-2.5795	0	%100
81	M55A	X	-1.0828	-1.0828	0	%100
82	M55A	Z	-1.8754	-1.8754	0	%100

Member Distributed Loads (BLC 65 : Structure Wm (0 Deg))

Member Label Direction Start Magnitude End Magnitude Start Location End Location



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 21777772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Distributed Loads (BLC 65 : Structure Wm (0 Deg)) (Continued)

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location[ft...]	End Location[ft...]
1	M1	X	0	0	0	%100
2	M1	Z	-6652	-6652	0	%100
3	M3	X	0	0	0	%100
4	M3	Z	-6652	-6652	0	%100
5	M5	X	0	0	0	%100
6	M5	Z	-0408	-0408	0	%100
7	M6	X	0	0	0	%100
8	M6	Z	-0408	-0408	0	%100
9	M7	X	0	0	0	%100
10	M7	Z	-6375	-6375	0	%100
11	M8	X	0	0	0	%100
12	M8	Z	-0282	-0282	0	%100
13	M9	X	0	0	0	%100
14	M9	Z	-0486	-0486	0	%100
15	M10	X	0	0	0	%100
16	M10	Z	-6375	-6375	0	%100
17	M11	X	0	0	0	%100
18	M11	Z	-2583	-2583	0	%100
19	M12	X	0	0	0	%100
20	M12	Z	-2583	-2583	0	%100
21	M13	X	0	0	0	%100
22	M13	Z	-2583	-2583	0	%100
23	M14	X	0	0	0	%100
24	M14	Z	-2583	-2583	0	%100
25	M15	X	0	0	0	%100
26	M15	Z	-0878	-0878	0	%100
27	M16	X	0	0	0	%100
28	M16	Z	-3497	-3497	0	%100
29	M17	X	0	0	0	%100
30	M17	Z	-0878	-0878	0	%100
31	M18	X	0	0	0	%100
32	M18	Z	-3497	-3497	0	%100
33	M19	X	0	0	0	%100
34	M19	Z	-1178	-1178	0	%100
35	M20	X	0	0	0	%100
36	M20	Z	-0878	-0878	0	%100
37	M21	X	0	0	0	%100
38	M21	Z	-0878	-0878	0	%100
39	M22	X	0	0	0	%100
40	M22	Z	-3823	-3823	0	%100
41	M23	X	0	0	0	%100
42	M23	Z	-3823	-3823	0	%100
43	M24	X	0	0	0	%100
44	M24	Z	-4019	-4019	0	%100
45	M25	X	0	0	0	%100
46	M25	Z	-1178	-1178	0	%100
47	M26	X	0	0	0	%100
48	M26	Z	-0878	-0878	0	%100
49	M27	X	0	0	0	%100
50	M27	Z	-3497	-3497	0	%100
51	M28	X	0	0	0	%100
52	M28	Z	-0878	-0878	0	%100
53	M29	X	0	0	0	%100
54	M29	Z	-3497	-3497	0	%100
55	M30	X	0	0	0	%100
56	M30	Z	-1178	-1178	0	%100
57	M31	X	0	0	0	%100



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 2177772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Distributed Loads (BLC 65 : Structure Wm (0 Deg)) (Continued)

	Member Label	Direction	Start Magnitude...	End Magnitude[...	Start Locationft...	End Locationft...
58	M31	Z	-.0878	-.0878	0	%100
59	M32	X	0	0	0	%100
60	M32	Z	-.0878	-.0878	0	%100
61	M33	X	0	0	0	%100
62	M33	Z	-.3823	-.3823	0	%100
63	M34	X	0	0	0	%100
64	M34	Z	-.3823	-.3823	0	%100
65	M35	X	0	0	0	%100
66	M35	Z	-.4019	-.4019	0	%100
67	M36	X	0	0	0	%100
68	M36	Z	-.1178	-.1178	0	%100
69	MP4A	X	0	0	0	%100
70	MP4A	Z	-.5266	-.5266	0	%100
71	MP3A	X	0	0	0	%100
72	MP3A	Z	-.5266	-.5266	0	%100
73	MP2A	X	0	0	0	%100
74	MP2A	Z	-.5266	-.5266	0	%100
75	MP1A	X	0	0	0	%100
76	MP1A	Z	-.5266	-.5266	0	%100
77	EQUIP	X	0	0	0	%100
78	EQUIP	Z	-.6006	-.6006	0	%100
79	M51	X	0	0	0	%100
80	M51	Z	-.6006	-.6006	0	%100
81	M55A	X	0	0	0	%100
82	M55A	Z	-.1293	-.1293	0	%100

Member Distributed Loads (BLC 66 : Structure Wm (30 Deg))

	Member Label	Direction	Start Magnitude...	End Magnitude[...	Start Locationft...	End Locationft...
1	M1	X	.2495	.2495	0	%100
2	M1	Z	-.4321	-.4321	0	%100
3	M3	X	.2495	.2495	0	%100
4	M3	Z	-.4321	-.4321	0	%100
5	M5	X	.0026	.0026	0	%100
6	M5	Z	-.0045	-.0045	0	%100
7	M6	X	.0386	.0386	0	%100
8	M6	Z	-.0668	-.0668	0	%100
9	M7	X	.2391	.2391	0	%100
10	M7	Z	-.4141	-.4141	0	%100
11	M8	X	.0004	.0004	0	%100
12	M8	Z	-.000692	-.000692	0	%100
13	M9	X	.0403	.0403	0	%100
14	M9	Z	-.0698	-.0698	0	%100
15	M10	X	.2391	.2391	0	%100
16	M10	Z	-.4141	-.4141	0	%100
17	M11	X	.0164	.0164	0	%100
18	M11	Z	-.0284	-.0284	0	%100
19	M12	X	.2444	.2444	0	%100
20	M12	Z	-.4233	-.4233	0	%100
21	M13	X	.0164	.0164	0	%100
22	M13	Z	-.0284	-.0284	0	%100
23	M14	X	.2444	.2444	0	%100
24	M14	Z	-.4233	-.4233	0	%100
25	M15	X	.1161	.1161	0	%100
26	M15	Z	-.201	-.201	0	%100
27	M16	X	.2056	.2056	0	%100
28	M16	Z	-.3561	-.3561	0	%100



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 21777772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Distributed Loads (BLC 66 : Structure Wm (30 Deg)) (Continued)

	Member Label	Direction	Start Magnitude	End Magnitude	Start Locationft	End Locationft
29	M17	X	.1161	.1161	0	%100
30	M17	Z	-.201	-.201	0	%100
31	M18	X	.2056	.2056	0	%100
32	M18	Z	-.3561	-.3561	0	%100
33	M19	X	.1273	.1273	0	%100
34	M19	Z	-.2205	-.2205	0	%100
35	M20	X	.1161	.1161	0	%100
36	M20	Z	-.201	-.201	0	%100
37	M21	X	.1161	.1161	0	%100
38	M21	Z	-.201	-.201	0	%100
39	M22	X	.1912	.1912	0	%100
40	M22	Z	-.3311	-.3311	0	%100
41	M23	X	.1912	.1912	0	%100
42	M23	Z	-.3311	-.3311	0	%100
43	M24	X	.201	.201	0	%100
44	M24	Z	-.3481	-.3481	0	%100
45	M25	X	.1273	.1273	0	%100
46	M25	Z	-.2205	-.2205	0	%100
47	M26	X	.1161	.1161	0	%100
48	M26	Z	-.201	-.201	0	%100
49	M27	X	.1448	.1448	0	%100
50	M27	Z	-.2508	-.2508	0	%100
51	M28	X	.1161	.1161	0	%100
52	M28	Z	-.201	-.201	0	%100
53	M29	X	.1448	.1448	0	%100
54	M29	Z	-.2508	-.2508	0	%100
55	M30	X	.1273	.1273	0	%100
56	M30	Z	-.2205	-.2205	0	%100
57	M31	X	.1161	.1161	0	%100
58	M31	Z	-.201	-.201	0	%100
59	M32	X	.1161	.1161	0	%100
60	M32	Z	-.201	-.201	0	%100
61	M33	X	.1912	.1912	0	%100
62	M33	Z	-.3311	-.3311	0	%100
63	M34	X	.1912	.1912	0	%100
64	M34	Z	-.3311	-.3311	0	%100
65	M35	X	.201	.201	0	%100
66	M35	Z	-.3481	-.3481	0	%100
67	M36	X	.1273	.1273	0	%100
68	M36	Z	-.2205	-.2205	0	%100
69	MP4A	X	.2633	.2633	0	%100
70	MP4A	Z	-.4561	-.4561	0	%100
71	MP3A	X	.2633	.2633	0	%100
72	MP3A	Z	-.4561	-.4561	0	%100
73	MP2A	X	.2633	.2633	0	%100
74	MP2A	Z	-.4561	-.4561	0	%100
75	MP1A	X	.2633	.2633	0	%100
76	MP1A	Z	-.4561	-.4561	0	%100
77	EQUIP	X	.3003	.3003	0	%100
78	EQUIP	Z	-.5201	-.5201	0	%100
79	M51	X	.3003	.3003	0	%100
80	M51	Z	-.5201	-.5201	0	%100
81	M55A	X	7e-6	7e-6	0	%100
82	M55A	Z	-1.2e-5	-1.2e-5	0	%100

Member Distributed Loads (BLC 67 : Structure Wm (60 Deg))

Member Label Direction Start Magnitude End Magnitude Start Locationft End Locationft



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 21777772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Distributed Loads (BLC 67 : Structure Wm (60 Deg)) (Continued)

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location(ft)	End Location(ft)
1	M1	X	.144	.144	0	%100
2	M1	Z	-.0832	-.0832	0	%100
3	M3	X	.144	.144	0	%100
4	M3	Z	-.0832	-.0832	0	%100
5	M5	X	.0052	.0052	0	%100
6	M5	Z	-.003	-.003	0	%100
7	M6	X	.0675	.0675	0	%100
8	M6	Z	-.039	-.039	0	%100
9	M7	X	.138	.138	0	%100
10	M7	Z	-.0797	-.0797	0	%100
11	M8	X	.0123	.0123	0	%100
12	M8	Z	-.0071	-.0071	0	%100
13	M9	X	.0637	.0637	0	%100
14	M9	Z	-.0368	-.0368	0	%100
15	M10	X	.138	.138	0	%100
16	M10	Z	-.0797	-.0797	0	%100
17	M11	X	.0328	.0328	0	%100
18	M11	Z	-.0189	-.0189	0	%100
19	M12	X	.4277	.4277	0	%100
20	M12	Z	-.2469	-.2469	0	%100
21	M13	X	.0328	.0328	0	%100
22	M13	Z	-.0189	-.0189	0	%100
23	M14	X	.4277	.4277	0	%100
24	M14	Z	-.2469	-.2469	0	%100
25	M15	X	.4511	.4511	0	%100
26	M15	Z	-.2604	-.2604	0	%100
27	M16	X	.3573	.3573	0	%100
28	M16	Z	-.2063	-.2063	0	%100
29	M17	X	.4511	.4511	0	%100
30	M17	Z	-.2604	-.2604	0	%100
31	M18	X	.3573	.3573	0	%100
32	M18	Z	-.2063	-.2063	0	%100
33	M19	X	.4576	.4576	0	%100
34	M19	Z	-.2642	-.2642	0	%100
35	M20	X	.4511	.4511	0	%100
36	M20	Z	-.2604	-.2604	0	%100
37	M21	X	.4511	.4511	0	%100
38	M21	Z	-.2604	-.2604	0	%100
39	M22	X	.3311	.3311	0	%100
40	M22	Z	-.1912	-.1912	0	%100
41	M23	X	.3311	.3311	0	%100
42	M23	Z	-.1912	-.1912	0	%100
43	M24	X	.3481	.3481	0	%100
44	M24	Z	-.201	-.201	0	%100
45	M25	X	.4576	.4576	0	%100
46	M25	Z	-.2642	-.2642	0	%100
47	M26	X	.4511	.4511	0	%100
48	M26	Z	-.2604	-.2604	0	%100
49	M27	X	.2519	.2519	0	%100
50	M27	Z	-.1455	-.1455	0	%100
51	M28	X	.4511	.4511	0	%100
52	M28	Z	-.2604	-.2604	0	%100
53	M29	X	.2519	.2519	0	%100
54	M29	Z	-.1455	-.1455	0	%100
55	M30	X	.4576	.4576	0	%100
56	M30	Z	-.2642	-.2642	0	%100
57	M31	X	.4511	.4511	0	%100



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 21777772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Distributed Loads (BLC 67 : Structure Wm (60 Deg)) (Continued)

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location	End Location
58	M31	Z	-.2604	-.2604	0	%100
59	M32	X	.4511	.4511	0	%100
60	M32	Z	-.2604	-.2604	0	%100
61	M33	X	.3311	.3311	0	%100
62	M33	Z	-.1912	-.1912	0	%100
63	M34	X	.3311	.3311	0	%100
64	M34	Z	-.1912	-.1912	0	%100
65	M35	X	.3481	.3481	0	%100
66	M35	Z	-.201	-.201	0	%100
67	M36	X	.4576	.4576	0	%100
68	M36	Z	-.2642	-.2642	0	%100
69	MP4A	X	.4561	.4561	0	%100
70	MP4A	Z	-.2633	-.2633	0	%100
71	MP3A	X	.4561	.4561	0	%100
72	MP3A	Z	-.2633	-.2633	0	%100
73	MP2A	X	.4561	.4561	0	%100
74	MP2A	Z	-.2633	-.2633	0	%100
75	MP1A	X	.4561	.4561	0	%100
76	MP1A	Z	-.2633	-.2633	0	%100
77	EQUIP	X	.5201	.5201	0	%100
78	EQUIP	Z	-.3003	-.3003	0	%100
79	M51	X	.5201	.5201	0	%100
80	M51	Z	-.3003	-.3003	0	%100
81	M55A	X	.1161	.1161	0	%100
82	M55A	Z	-.067	-.067	0	%100

Member Distributed Loads (BLC 68 : Structure Wm (90 Deg))

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location	End Location
1	M1	X	0	0	0	%100
2	M1	Z	0	0	0	%100
3	M3	X	0	0	0	%100
4	M3	Z	0	0	0	%100
5	M5	X	.0424	.0424	0	%100
6	M5	Z	0	0	0	%100
7	M6	X	.0424	.0424	0	%100
8	M6	Z	0	0	0	%100
9	M7	X	0	0	0	%100
10	M7	Z	0	0	0	%100
11	M8	X	.0549	.0549	0	%100
12	M8	Z	0	0	0	%100
13	M9	X	.0346	.0346	0	%100
14	M9	Z	0	0	0	%100
15	M10	X	0	0	0	%100
16	M10	Z	0	0	0	%100
17	M11	X	.2683	.2683	0	%100
18	M11	Z	0	0	0	%100
19	M12	X	.2683	.2683	0	%100
20	M12	Z	0	0	0	%100
21	M13	X	.2683	.2683	0	%100
22	M13	Z	0	0	0	%100
23	M14	X	.2683	.2683	0	%100
24	M14	Z	0	0	0	%100
25	M15	X	.6652	.6652	0	%100
26	M15	Z	0	0	0	%100
27	M16	X	.3524	.3524	0	%100
28	M16	Z	0	0	0	%100



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 2177772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Distributed Loads (BLC 68 : Structure Wm (90 Deg)) (Continued)

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location(ft)	End Location(ft)
29	M17	X	.6652	.6652	0	%100
30	M17	Z	0	0	0	%100
31	M18	X	.3524	.3524	0	%100
32	M18	Z	0	0	0	%100
33	M19	X	.6652	.6652	0	%100
34	M19	Z	0	0	0	%100
35	M20	X	.6652	.6652	0	%100
36	M20	Z	0	0	0	%100
37	M21	X	.6652	.6652	0	%100
38	M21	Z	0	0	0	%100
39	M22	X	.3823	.3823	0	%100
40	M22	Z	0	0	0	%100
41	M23	X	.3823	.3823	0	%100
42	M23	Z	0	0	0	%100
43	M24	X	.4019	.4019	0	%100
44	M24	Z	0	0	0	%100
45	M25	X	.6652	.6652	0	%100
46	M25	Z	0	0	0	%100
47	M26	X	.6652	.6652	0	%100
48	M26	Z	0	0	0	%100
49	M27	X	.3524	.3524	0	%100
50	M27	Z	0	0	0	%100
51	M28	X	.6652	.6652	0	%100
52	M28	Z	0	0	0	%100
53	M29	X	.3524	.3524	0	%100
54	M29	Z	0	0	0	%100
55	M30	X	.6652	.6652	0	%100
56	M30	Z	0	0	0	%100
57	M31	X	.6652	.6652	0	%100
58	M31	Z	0	0	0	%100
59	M32	X	.6652	.6652	0	%100
60	M32	Z	0	0	0	%100
61	M33	X	.3823	.3823	0	%100
62	M33	Z	0	0	0	%100
63	M34	X	.3823	.3823	0	%100
64	M34	Z	0	0	0	%100
65	M35	X	.4019	.4019	0	%100
66	M35	Z	0	0	0	%100
67	M36	X	.6652	.6652	0	%100
68	M36	Z	0	0	0	%100
69	MP4A	X	.5266	.5266	0	%100
70	MP4A	Z	0	0	0	%100
71	MP3A	X	.5266	.5266	0	%100
72	MP3A	Z	0	0	0	%100
73	MP2A	X	.5266	.5266	0	%100
74	MP2A	Z	0	0	0	%100
75	MP1A	X	.5266	.5266	0	%100
76	MP1A	Z	0	0	0	%100
77	EQUIP	X	.6006	.6006	0	%100
78	EQUIP	Z	0	0	0	%100
79	M51	X	.6006	.6006	0	%100
80	M51	Z	0	0	0	%100
81	M55A	X	.3973	.3973	0	%100
82	M55A	Z	0	0	0	%100

Member Distributed Loads (BLC 69 : Structure Wm (120 Deg))

Member Label Direction Start Magnitude End Magnitude Start Location(ft) End Location(ft)



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 21777772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Distributed Loads (BLC 69 : Structure Wm (120 Deg)) (Continued)

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location	End Location
1	M1	X	.144	.144	0	%100
2	M1	Z	.0832	.0832	0	%100
3	M3	X	.144	.144	0	%100
4	M3	Z	.0832	.0832	0	%100
5	M5	X	.0675	.0675	0	%100
6	M5	Z	.039	.039	0	%100
7	M6	X	.0052	.0052	0	%100
8	M6	Z	.003	.003	0	%100
9	M7	X	.138	.138	0	%100
10	M7	Z	.0797	.0797	0	%100
11	M8	X	.0713	.0713	0	%100
12	M8	Z	.0412	.0412	0	%100
13	M9	X	.0022	.0022	0	%100
14	M9	Z	.0013	.0013	0	%100
15	M10	X	.138	.138	0	%100
16	M10	Z	.0797	.0797	0	%100
17	M11	X	.4277	.4277	0	%100
18	M11	Z	.2469	.2469	0	%100
19	M12	X	.0328	.0328	0	%100
20	M12	Z	.0189	.0189	0	%100
21	M13	X	.4277	.4277	0	%100
22	M13	Z	.2469	.2469	0	%100
23	M14	X	.0328	.0328	0	%100
24	M14	Z	.0189	.0189	0	%100
25	M15	X	.4511	.4511	0	%100
26	M15	Z	.2604	.2604	0	%100
27	M16	X	.2519	.2519	0	%100
28	M16	Z	.1455	.1455	0	%100
29	M17	X	.4511	.4511	0	%100
30	M17	Z	.2604	.2604	0	%100
31	M18	X	.2519	.2519	0	%100
32	M18	Z	.1455	.1455	0	%100
33	M19	X	.4576	.4576	0	%100
34	M19	Z	.2642	.2642	0	%100
35	M20	X	.4511	.4511	0	%100
36	M20	Z	.2604	.2604	0	%100
37	M21	X	.4511	.4511	0	%100
38	M21	Z	.2604	.2604	0	%100
39	M22	X	.3311	.3311	0	%100
40	M22	Z	.1912	.1912	0	%100
41	M23	X	.3311	.3311	0	%100
42	M23	Z	.1912	.1912	0	%100
43	M24	X	.3481	.3481	0	%100
44	M24	Z	.201	.201	0	%100
45	M25	X	.4576	.4576	0	%100
46	M25	Z	.2642	.2642	0	%100
47	M26	X	.4511	.4511	0	%100
48	M26	Z	.2604	.2604	0	%100
49	M27	X	.3573	.3573	0	%100
50	M27	Z	.2063	.2063	0	%100
51	M28	X	.4511	.4511	0	%100
52	M28	Z	.2604	.2604	0	%100
53	M29	X	.3573	.3573	0	%100
54	M29	Z	.2063	.2063	0	%100
55	M30	X	.4576	.4576	0	%100
56	M30	Z	.2642	.2642	0	%100
57	M31	X	.4511	.4511	0	%100



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 2177772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Distributed Loads (BLC 69 : Structure Wm (120 Deg)) (Continued)

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location	End Location
58	M31	Z	.2604	.2604	0	%100
59	M32	X	.4511	.4511	0	%100
60	M32	Z	.2604	.2604	0	%100
61	M33	X	.3311	.3311	0	%100
62	M33	Z	.1912	.1912	0	%100
63	M34	X	.3311	.3311	0	%100
64	M34	Z	.1912	.1912	0	%100
65	M35	X	.3481	.3481	0	%100
66	M35	Z	.201	.201	0	%100
67	M36	X	.4576	.4576	0	%100
68	M36	Z	.2642	.2642	0	%100
69	MP4A	X	.4561	.4561	0	%100
70	MP4A	Z	.2633	.2633	0	%100
71	MP3A	X	.4561	.4561	0	%100
72	MP3A	Z	.2633	.2633	0	%100
73	MP2A	X	.4561	.4561	0	%100
74	MP2A	Z	.2633	.2633	0	%100
75	MP1A	X	.4561	.4561	0	%100
76	MP1A	Z	.2633	.2633	0	%100
77	EQUIP	X	.5201	.5201	0	%100
78	EQUIP	Z	.3003	.3003	0	%100
79	M51	X	.5201	.5201	0	%100
80	M51	Z	.3003	.3003	0	%100
81	M55A	X	.4561	.4561	0	%100
82	M55A	Z	.2633	.2633	0	%100

Member Distributed Loads (BLC 70 : Structure Wm (150 Deg))

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location	End Location
1	M1	X	.2495	.2495	0	%100
2	M1	Z	.4321	.4321	0	%100
3	M3	X	.2495	.2495	0	%100
4	M3	Z	.4321	.4321	0	%100
5	M5	X	.0386	.0386	0	%100
6	M5	Z	.0668	.0668	0	%100
7	M6	X	.0026	.0026	0	%100
8	M6	Z	.0045	.0045	0	%100
9	M7	X	.2391	.2391	0	%100
10	M7	Z	.4141	.4141	0	%100
11	M8	X	.0345	.0345	0	%100
12	M8	Z	.0597	.0597	0	%100
13	M9	X	.0048	.0048	0	%100
14	M9	Z	.0083	.0083	0	%100
15	M10	X	.2391	.2391	0	%100
16	M10	Z	.4141	.4141	0	%100
17	M11	X	.2444	.2444	0	%100
18	M11	Z	.4233	.4233	0	%100
19	M12	X	.0164	.0164	0	%100
20	M12	Z	.0284	.0284	0	%100
21	M13	X	.2444	.2444	0	%100
22	M13	Z	.4233	.4233	0	%100
23	M14	X	.0164	.0164	0	%100
24	M14	Z	.0284	.0284	0	%100
25	M15	X	.1161	.1161	0	%100
26	M15	Z	.201	.201	0	%100
27	M16	X	.1448	.1448	0	%100
28	M16	Z	.2508	.2508	0	%100



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 21777772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Distributed Loads (BLC 70 : Structure Wm (150 Deg)) (Continued)

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location	End Location
29	M17	X	.1161	.1161	0	%100
30	M17	Z	.201	.201	0	%100
31	M18	X	.1448	.1448	0	%100
32	M18	Z	.2508	.2508	0	%100
33	M19	X	.1273	.1273	0	%100
34	M19	Z	.2205	.2205	0	%100
35	M20	X	.1161	.1161	0	%100
36	M20	Z	.201	.201	0	%100
37	M21	X	.1161	.1161	0	%100
38	M21	Z	.201	.201	0	%100
39	M22	X	.1912	.1912	0	%100
40	M22	Z	.3311	.3311	0	%100
41	M23	X	.1912	.1912	0	%100
42	M23	Z	.3311	.3311	0	%100
43	M24	X	.201	.201	0	%100
44	M24	Z	.3481	.3481	0	%100
45	M25	X	.1273	.1273	0	%100
46	M25	Z	.2205	.2205	0	%100
47	M26	X	.1161	.1161	0	%100
48	M26	Z	.201	.201	0	%100
49	M27	X	.2056	.2056	0	%100
50	M27	Z	.3561	.3561	0	%100
51	M28	X	.1161	.1161	0	%100
52	M28	Z	.201	.201	0	%100
53	M29	X	.2056	.2056	0	%100
54	M29	Z	.3561	.3561	0	%100
55	M30	X	.1273	.1273	0	%100
56	M30	Z	.2205	.2205	0	%100
57	M31	X	.1161	.1161	0	%100
58	M31	Z	.201	.201	0	%100
59	M32	X	.1161	.1161	0	%100
60	M32	Z	.201	.201	0	%100
61	M33	X	.1912	.1912	0	%100
62	M33	Z	.3311	.3311	0	%100
63	M34	X	.1912	.1912	0	%100
64	M34	Z	.3311	.3311	0	%100
65	M35	X	.201	.201	0	%100
66	M35	Z	.3481	.3481	0	%100
67	M36	X	.1273	.1273	0	%100
68	M36	Z	.2205	.2205	0	%100
69	MP4A	X	.2633	.2633	0	%100
70	MP4A	Z	.4561	.4561	0	%100
71	MP3A	X	.2633	.2633	0	%100
72	MP3A	Z	.4561	.4561	0	%100
73	MP2A	X	.2633	.2633	0	%100
74	MP2A	Z	.4561	.4561	0	%100
75	MP1A	X	.2633	.2633	0	%100
76	MP1A	Z	.4561	.4561	0	%100
77	EQUIP	X	.3003	.3003	0	%100
78	EQUIP	Z	.5201	.5201	0	%100
79	M51	X	.3003	.3003	0	%100
80	M51	Z	.5201	.5201	0	%100
81	M55A	X	.1963	.1963	0	%100
82	M55A	Z	.34	.34	0	%100

Member Distributed Loads (BLC 71 : Structure Wm (180 Deg))

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location	End Location
--	--------------	-----------	-----------------	---------------	----------------	--------------



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 2177772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Distributed Loads (BLC 71 : Structure Wm (180 Deg)) (Continued)

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location[ft]	End Location[ft]
1	M1	X	0	0	0	%100
2	M1	Z	.6652	.6652	0	%100
3	M3	X	0	0	0	%100
4	M3	Z	.6652	.6652	0	%100
5	M5	X	0	0	0	%100
6	M5	Z	.0408	.0408	0	%100
7	M6	X	0	0	0	%100
8	M6	Z	.0408	.0408	0	%100
9	M7	X	0	0	0	%100
10	M7	Z	.6375	.6375	0	%100
11	M8	X	0	0	0	%100
12	M8	Z	.0282	.0282	0	%100
13	M9	X	0	0	0	%100
14	M9	Z	.0486	.0486	0	%100
15	M10	X	0	0	0	%100
16	M10	Z	.6375	.6375	0	%100
17	M11	X	0	0	0	%100
18	M11	Z	.2583	.2583	0	%100
19	M12	X	0	0	0	%100
20	M12	Z	.2583	.2583	0	%100
21	M13	X	0	0	0	%100
22	M13	Z	.2583	.2583	0	%100
23	M14	X	0	0	0	%100
24	M14	Z	.2583	.2583	0	%100
25	M15	X	0	0	0	%100
26	M15	Z	.0878	.0878	0	%100
27	M16	X	0	0	0	%100
28	M16	Z	.3497	.3497	0	%100
29	M17	X	0	0	0	%100
30	M17	Z	.0878	.0878	0	%100
31	M18	X	0	0	0	%100
32	M18	Z	.3497	.3497	0	%100
33	M19	X	0	0	0	%100
34	M19	Z	.1178	.1178	0	%100
35	M20	X	0	0	0	%100
36	M20	Z	.0878	.0878	0	%100
37	M21	X	0	0	0	%100
38	M21	Z	.0878	.0878	0	%100
39	M22	X	0	0	0	%100
40	M22	Z	.3823	.3823	0	%100
41	M23	X	0	0	0	%100
42	M23	Z	.3823	.3823	0	%100
43	M24	X	0	0	0	%100
44	M24	Z	.4019	.4019	0	%100
45	M25	X	0	0	0	%100
46	M25	Z	.1178	.1178	0	%100
47	M26	X	0	0	0	%100
48	M26	Z	.0878	.0878	0	%100
49	M27	X	0	0	0	%100
50	M27	Z	.3497	.3497	0	%100
51	M28	X	0	0	0	%100
52	M28	Z	.0878	.0878	0	%100
53	M29	X	0	0	0	%100
54	M29	Z	.3497	.3497	0	%100
55	M30	X	0	0	0	%100
56	M30	Z	.1178	.1178	0	%100
57	M31	X	0	0	0	%100



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 21777772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Distributed Loads (BLC 71 : Structure Wm (180 Deg)) (Continued)

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location	End Location
58	M31	Z	.0878	.0878	0	%100
59	M32	X	0	0	0	%100
60	M32	Z	.0878	.0878	0	%100
61	M33	X	0	0	0	%100
62	M33	Z	.3823	.3823	0	%100
63	M34	X	0	0	0	%100
64	M34	Z	.3823	.3823	0	%100
65	M35	X	0	0	0	%100
66	M35	Z	.4019	.4019	0	%100
67	M36	X	0	0	0	%100
68	M36	Z	.1178	.1178	0	%100
69	MP4A	X	0	0	0	%100
70	MP4A	Z	.5266	.5266	0	%100
71	MP3A	X	0	0	0	%100
72	MP3A	Z	.5266	.5266	0	%100
73	MP2A	X	0	0	0	%100
74	MP2A	Z	.5266	.5266	0	%100
75	MP1A	X	0	0	0	%100
76	MP1A	Z	.5266	.5266	0	%100
77	EQUIP	X	0	0	0	%100
78	EQUIP	Z	.6006	.6006	0	%100
79	M51	X	0	0	0	%100
80	M51	Z	.6006	.6006	0	%100
81	M55A	X	0	0	0	%100
82	M55A	Z	.1293	.1293	0	%100

Member Distributed Loads (BLC 72 : Structure Wm (210 Deg))

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location	End Location
1	M1	X	-.2495	-.2495	0	%100
2	M1	Z	.4321	.4321	0	%100
3	M3	X	-.2495	-.2495	0	%100
4	M3	Z	.4321	.4321	0	%100
5	M5	X	-.0026	-.0026	0	%100
6	M5	Z	.0045	.0045	0	%100
7	M6	X	-.0386	-.0386	0	%100
8	M6	Z	.0668	.0668	0	%100
9	M7	X	-.2391	-.2391	0	%100
10	M7	Z	.4141	.4141	0	%100
11	M8	X	-.0004	-.0004	0	%100
12	M8	Z	.000692	.000692	0	%100
13	M9	X	-.0403	-.0403	0	%100
14	M9	Z	.0698	.0698	0	%100
15	M10	X	-.2391	-.2391	0	%100
16	M10	Z	.4141	.4141	0	%100
17	M11	X	-.0164	-.0164	0	%100
18	M11	Z	.0284	.0284	0	%100
19	M12	X	-.2444	-.2444	0	%100
20	M12	Z	.4233	.4233	0	%100
21	M13	X	-.0164	-.0164	0	%100
22	M13	Z	.0284	.0284	0	%100
23	M14	X	-.2444	-.2444	0	%100
24	M14	Z	.4233	.4233	0	%100
25	M15	X	-.1161	-.1161	0	%100
26	M15	Z	.201	.201	0	%100
27	M16	X	-.2056	-.2056	0	%100
28	M16	Z	.3561	.3561	0	%100



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 2177772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Distributed Loads (BLC 72 : Structure Wm (210 Deg)) (Continued)

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location	End Location
29	M17	X	-.1161	-.1161	0	%100
30	M17	Z	.201	.201	0	%100
31	M18	X	-.2056	-.2056	0	%100
32	M18	Z	.3561	.3561	0	%100
33	M19	X	-.1273	-.1273	0	%100
34	M19	Z	.2205	.2205	0	%100
35	M20	X	-.1161	-.1161	0	%100
36	M20	Z	.201	.201	0	%100
37	M21	X	-.1161	-.1161	0	%100
38	M21	Z	.201	.201	0	%100
39	M22	X	-.1912	-.1912	0	%100
40	M22	Z	.3311	.3311	0	%100
41	M23	X	-.1912	-.1912	0	%100
42	M23	Z	.3311	.3311	0	%100
43	M24	X	-.201	-.201	0	%100
44	M24	Z	.3481	.3481	0	%100
45	M25	X	-.1273	-.1273	0	%100
46	M25	Z	.2205	.2205	0	%100
47	M26	X	-.1161	-.1161	0	%100
48	M26	Z	.201	.201	0	%100
49	M27	X	-.1448	-.1448	0	%100
50	M27	Z	.2508	.2508	0	%100
51	M28	X	-.1161	-.1161	0	%100
52	M28	Z	.201	.201	0	%100
53	M29	X	-.1448	-.1448	0	%100
54	M29	Z	.2508	.2508	0	%100
55	M30	X	-.1273	-.1273	0	%100
56	M30	Z	.2205	.2205	0	%100
57	M31	X	-.1161	-.1161	0	%100
58	M31	Z	.201	.201	0	%100
59	M32	X	-.1161	-.1161	0	%100
60	M32	Z	.201	.201	0	%100
61	M33	X	-.1912	-.1912	0	%100
62	M33	Z	.3311	.3311	0	%100
63	M34	X	-.1912	-.1912	0	%100
64	M34	Z	.3311	.3311	0	%100
65	M35	X	-.201	-.201	0	%100
66	M35	Z	.3481	.3481	0	%100
67	M36	X	-.1273	-.1273	0	%100
68	M36	Z	.2205	.2205	0	%100
69	MP4A	X	-.2633	-.2633	0	%100
70	MP4A	Z	.4561	.4561	0	%100
71	MP3A	X	-.2633	-.2633	0	%100
72	MP3A	Z	.4561	.4561	0	%100
73	MP2A	X	-.2633	-.2633	0	%100
74	MP2A	Z	.4561	.4561	0	%100
75	MP1A	X	-.2633	-.2633	0	%100
76	MP1A	Z	.4561	.4561	0	%100
77	EQUIP	X	-.3003	-.3003	0	%100
78	EQUIP	Z	.5201	.5201	0	%100
79	M51	X	-.3003	-.3003	0	%100
80	M51	Z	.5201	.5201	0	%100
81	M55A	X	-7e-6	-7e-6	0	%100
82	M55A	Z	1.2e-5	1.2e-5	0	%100

Member Distributed Loads (BLC 73 : Structure Wm (240 Deg))

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location	End Location
--	--------------	-----------	-----------------	---------------	----------------	--------------



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 21777772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Distributed Loads (BLC 73 : Structure Wm (240 Deg)) (Continued)

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location[ft]	End Location[ft]
1	M1	X	-.144	-.144	0	%100
2	M1	Z	.0832	.0832	0	%100
3	M3	X	-.144	-.144	0	%100
4	M3	Z	.0832	.0832	0	%100
5	M5	X	-.0052	-.0052	0	%100
6	M5	Z	.003	.003	0	%100
7	M6	X	-.0675	-.0675	0	%100
8	M6	Z	.039	.039	0	%100
9	M7	X	-.138	-.138	0	%100
10	M7	Z	.0797	.0797	0	%100
11	M8	X	-.0123	-.0123	0	%100
12	M8	Z	.0071	.0071	0	%100
13	M9	X	-.0637	-.0637	0	%100
14	M9	Z	.0368	.0368	0	%100
15	M10	X	-.138	-.138	0	%100
16	M10	Z	.0797	.0797	0	%100
17	M11	X	-.0328	-.0328	0	%100
18	M11	Z	.0189	.0189	0	%100
19	M12	X	-.4277	-.4277	0	%100
20	M12	Z	.2469	.2469	0	%100
21	M13	X	-.0328	-.0328	0	%100
22	M13	Z	.0189	.0189	0	%100
23	M14	X	-.4277	-.4277	0	%100
24	M14	Z	.2469	.2469	0	%100
25	M15	X	-.4511	-.4511	0	%100
26	M15	Z	.2604	.2604	0	%100
27	M16	X	-.3573	-.3573	0	%100
28	M16	Z	.2063	.2063	0	%100
29	M17	X	-.4511	-.4511	0	%100
30	M17	Z	.2604	.2604	0	%100
31	M18	X	-.3573	-.3573	0	%100
32	M18	Z	.2063	.2063	0	%100
33	M19	X	-.4576	-.4576	0	%100
34	M19	Z	.2642	.2642	0	%100
35	M20	X	-.4511	-.4511	0	%100
36	M20	Z	.2604	.2604	0	%100
37	M21	X	-.4511	-.4511	0	%100
38	M21	Z	.2604	.2604	0	%100
39	M22	X	-.3311	-.3311	0	%100
40	M22	Z	.1912	.1912	0	%100
41	M23	X	-.3311	-.3311	0	%100
42	M23	Z	.1912	.1912	0	%100
43	M24	X	-.3481	-.3481	0	%100
44	M24	Z	.201	.201	0	%100
45	M25	X	-.4576	-.4576	0	%100
46	M25	Z	.2642	.2642	0	%100
47	M26	X	-.4511	-.4511	0	%100
48	M26	Z	.2604	.2604	0	%100
49	M27	X	-.2519	-.2519	0	%100
50	M27	Z	.1455	.1455	0	%100
51	M28	X	-.4511	-.4511	0	%100
52	M28	Z	.2604	.2604	0	%100
53	M29	X	-.2519	-.2519	0	%100
54	M29	Z	.1455	.1455	0	%100
55	M30	X	-.4576	-.4576	0	%100
56	M30	Z	.2642	.2642	0	%100
57	M31	X	-.4511	-.4511	0	%100



Member Distributed Loads (BLC 73 : Structure Wm (240 Deg)) (Continued)

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location	End Location
58	M31	Z	.2604	.2604	0	%100
59	M32	X	-.4511	-.4511	0	%100
60	M32	Z	.2604	.2604	0	%100
61	M33	X	-.3311	-.3311	0	%100
62	M33	Z	.1912	.1912	0	%100
63	M34	X	-.3311	-.3311	0	%100
64	M34	Z	.1912	.1912	0	%100
65	M35	X	-.3481	-.3481	0	%100
66	M35	Z	.201	.201	0	%100
67	M36	X	-.4576	-.4576	0	%100
68	M36	Z	.2642	.2642	0	%100
69	MP4A	X	-.4561	-.4561	0	%100
70	MP4A	Z	.2633	.2633	0	%100
71	MP3A	X	-.4561	-.4561	0	%100
72	MP3A	Z	.2633	.2633	0	%100
73	MP2A	X	-.4561	-.4561	0	%100
74	MP2A	Z	.2633	.2633	0	%100
75	MP1A	X	-.4561	-.4561	0	%100
76	MP1A	Z	.2633	.2633	0	%100
77	EQUIP	X	-.5201	-.5201	0	%100
78	EQUIP	Z	.3003	.3003	0	%100
79	M51	X	-.5201	-.5201	0	%100
80	M51	Z	.3003	.3003	0	%100
81	M55A	X	-.1161	-.1161	0	%100
82	M55A	Z	.067	.067	0	%100

Member Distributed Loads (BLC 74 : Structure Wm (270 Deg))

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location	End Location
1	M1	X	0	0	0	%100
2	M1	Z	0	0	0	%100
3	M3	X	0	0	0	%100
4	M3	Z	0	0	0	%100
5	M5	X	-.0424	-.0424	0	%100
6	M5	Z	0	0	0	%100
7	M6	X	-.0424	-.0424	0	%100
8	M6	Z	0	0	0	%100
9	M7	X	0	0	0	%100
10	M7	Z	0	0	0	%100
11	M8	X	-.0549	-.0549	0	%100
12	M8	Z	0	0	0	%100
13	M9	X	-.0346	-.0346	0	%100
14	M9	Z	0	0	0	%100
15	M10	X	0	0	0	%100
16	M10	Z	0	0	0	%100
17	M11	X	-.2683	-.2683	0	%100
18	M11	Z	0	0	0	%100
19	M12	X	-.2683	-.2683	0	%100
20	M12	Z	0	0	0	%100
21	M13	X	-.2683	-.2683	0	%100
22	M13	Z	0	0	0	%100
23	M14	X	-.2683	-.2683	0	%100
24	M14	Z	0	0	0	%100
25	M15	X	-.6652	-.6652	0	%100
26	M15	Z	0	0	0	%100
27	M16	X	-.3524	-.3524	0	%100
28	M16	Z	0	0	0	%100



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 21777772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Distributed Loads (BLC 74 : Structure Wm (270 Deg)) (Continued)

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location[ft]	End Location[ft]
29	M17	X	-6652	-6652	0	%100
30	M17	Z	0	0	0	%100
31	M18	X	-3524	-3524	0	%100
32	M18	Z	0	0	0	%100
33	M19	X	-6652	-6652	0	%100
34	M19	Z	0	0	0	%100
35	M20	X	-6652	-6652	0	%100
36	M20	Z	0	0	0	%100
37	M21	X	-6652	-6652	0	%100
38	M21	Z	0	0	0	%100
39	M22	X	-3823	-3823	0	%100
40	M22	Z	0	0	0	%100
41	M23	X	-3823	-3823	0	%100
42	M23	Z	0	0	0	%100
43	M24	X	-4019	-4019	0	%100
44	M24	Z	0	0	0	%100
45	M25	X	-6652	-6652	0	%100
46	M25	Z	0	0	0	%100
47	M26	X	-6652	-6652	0	%100
48	M26	Z	0	0	0	%100
49	M27	X	-3524	-3524	0	%100
50	M27	Z	0	0	0	%100
51	M28	X	-6652	-6652	0	%100
52	M28	Z	0	0	0	%100
53	M29	X	-3524	-3524	0	%100
54	M29	Z	0	0	0	%100
55	M30	X	-6652	-6652	0	%100
56	M30	Z	0	0	0	%100
57	M31	X	-6652	-6652	0	%100
58	M31	Z	0	0	0	%100
59	M32	X	-6652	-6652	0	%100
60	M32	Z	0	0	0	%100
61	M33	X	-3823	-3823	0	%100
62	M33	Z	0	0	0	%100
63	M34	X	-3823	-3823	0	%100
64	M34	Z	0	0	0	%100
65	M35	X	-4019	-4019	0	%100
66	M35	Z	0	0	0	%100
67	M36	X	-6652	-6652	0	%100
68	M36	Z	0	0	0	%100
69	MP4A	X	-5266	-5266	0	%100
70	MP4A	Z	0	0	0	%100
71	MP3A	X	-5266	-5266	0	%100
72	MP3A	Z	0	0	0	%100
73	MP2A	X	-5266	-5266	0	%100
74	MP2A	Z	0	0	0	%100
75	MP1A	X	-5266	-5266	0	%100
76	MP1A	Z	0	0	0	%100
77	EQUIP	X	-6006	-6006	0	%100
78	EQUIP	Z	0	0	0	%100
79	M51	X	-6006	-6006	0	%100
80	M51	Z	0	0	0	%100
81	M55A	X	-3973	-3973	0	%100
82	M55A	Z	0	0	0	%100

Member Distributed Loads (BLC 75 : Structure Wm (300 Deg))

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location[ft]	End Location[ft]
--	--------------	-----------	-----------------	---------------	--------------------	------------------



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 2177772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Distributed Loads (BLC 75 : Structure Wm (300 Deg)) (Continued)

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location[ft]	End Location[ft]
1	M1	X	-.144	-.144	0	%100
2	M1	Z	-.0832	-.0832	0	%100
3	M3	X	-.144	-.144	0	%100
4	M3	Z	-.0832	-.0832	0	%100
5	M5	X	-.0675	-.0675	0	%100
6	M5	Z	-.039	-.039	0	%100
7	M6	X	-.0052	-.0052	0	%100
8	M6	Z	-.003	-.003	0	%100
9	M7	X	-.138	-.138	0	%100
10	M7	Z	-.0797	-.0797	0	%100
11	M8	X	-.0713	-.0713	0	%100
12	M8	Z	-.0412	-.0412	0	%100
13	M9	X	-.0022	-.0022	0	%100
14	M9	Z	-.0013	-.0013	0	%100
15	M10	X	-.138	-.138	0	%100
16	M10	Z	-.0797	-.0797	0	%100
17	M11	X	-.4277	-.4277	0	%100
18	M11	Z	-.2469	-.2469	0	%100
19	M12	X	-.0328	-.0328	0	%100
20	M12	Z	-.0189	-.0189	0	%100
21	M13	X	-.4277	-.4277	0	%100
22	M13	Z	-.2469	-.2469	0	%100
23	M14	X	-.0328	-.0328	0	%100
24	M14	Z	-.0189	-.0189	0	%100
25	M15	X	-.4511	-.4511	0	%100
26	M15	Z	-.2604	-.2604	0	%100
27	M16	X	-.2519	-.2519	0	%100
28	M16	Z	-.1455	-.1455	0	%100
29	M17	X	-.4511	-.4511	0	%100
30	M17	Z	-.2604	-.2604	0	%100
31	M18	X	-.2519	-.2519	0	%100
32	M18	Z	-.1455	-.1455	0	%100
33	M19	X	-.4576	-.4576	0	%100
34	M19	Z	-.2642	-.2642	0	%100
35	M20	X	-.4511	-.4511	0	%100
36	M20	Z	-.2604	-.2604	0	%100
37	M21	X	-.4511	-.4511	0	%100
38	M21	Z	-.2604	-.2604	0	%100
39	M22	X	-.3311	-.3311	0	%100
40	M22	Z	-.1912	-.1912	0	%100
41	M23	X	-.3311	-.3311	0	%100
42	M23	Z	-.1912	-.1912	0	%100
43	M24	X	-.3481	-.3481	0	%100
44	M24	Z	-.201	-.201	0	%100
45	M25	X	-.4576	-.4576	0	%100
46	M25	Z	-.2642	-.2642	0	%100
47	M26	X	-.4511	-.4511	0	%100
48	M26	Z	-.2604	-.2604	0	%100
49	M27	X	-.3573	-.3573	0	%100
50	M27	Z	-.2063	-.2063	0	%100
51	M28	X	-.4511	-.4511	0	%100
52	M28	Z	-.2604	-.2604	0	%100
53	M29	X	-.3573	-.3573	0	%100
54	M29	Z	-.2063	-.2063	0	%100
55	M30	X	-.4576	-.4576	0	%100
56	M30	Z	-.2642	-.2642	0	%100
57	M31	X	-.4511	-.4511	0	%100



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 21777772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Distributed Loads (BLC 75 : Structure Wm (300 Deg)) (Continued)

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location(ft)	End Location(ft)
58	M31	Z	-2604	-2604	0	%100
59	M32	X	-4511	-4511	0	%100
60	M32	Z	-2604	-2604	0	%100
61	M33	X	-3311	-3311	0	%100
62	M33	Z	-1912	-1912	0	%100
63	M34	X	-3311	-3311	0	%100
64	M34	Z	-1912	-1912	0	%100
65	M35	X	-3481	-3481	0	%100
66	M35	Z	-201	-201	0	%100
67	M36	X	-4576	-4576	0	%100
68	M36	Z	-2642	-2642	0	%100
69	MP4A	X	-4561	-4561	0	%100
70	MP4A	Z	-2633	-2633	0	%100
71	MP3A	X	-4561	-4561	0	%100
72	MP3A	Z	-2633	-2633	0	%100
73	MP2A	X	-4561	-4561	0	%100
74	MP2A	Z	-2633	-2633	0	%100
75	MP1A	X	-4561	-4561	0	%100
76	MP1A	Z	-2633	-2633	0	%100
77	EQUIP	X	-5201	-5201	0	%100
78	EQUIP	Z	-3003	-3003	0	%100
79	M51	X	-5201	-5201	0	%100
80	M51	Z	-3003	-3003	0	%100
81	M55A	X	-4561	-4561	0	%100
82	M55A	Z	-2633	-2633	0	%100

Member Distributed Loads (BLC 76 : Structure Wm (330 Deg))

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location(ft)	End Location(ft)
1	M1	X	-2495	-2495	0	%100
2	M1	Z	-4321	-4321	0	%100
3	M3	X	-2495	-2495	0	%100
4	M3	Z	-4321	-4321	0	%100
5	M5	X	-0386	-0386	0	%100
6	M5	Z	-0668	-0668	0	%100
7	M6	X	-0026	-0026	0	%100
8	M6	Z	-0045	-0045	0	%100
9	M7	X	-2391	-2391	0	%100
10	M7	Z	-4141	-4141	0	%100
11	M8	X	-0345	-0345	0	%100
12	M8	Z	-0597	-0597	0	%100
13	M9	X	-0048	-0048	0	%100
14	M9	Z	-0083	-0083	0	%100
15	M10	X	-2391	-2391	0	%100
16	M10	Z	-4141	-4141	0	%100
17	M11	X	-2444	-2444	0	%100
18	M11	Z	-4233	-4233	0	%100
19	M12	X	-0164	-0164	0	%100
20	M12	Z	-0284	-0284	0	%100
21	M13	X	-2444	-2444	0	%100
22	M13	Z	-4233	-4233	0	%100
23	M14	X	-0164	-0164	0	%100
24	M14	Z	-0284	-0284	0	%100
25	M15	X	-1161	-1161	0	%100
26	M15	Z	-201	-201	0	%100
27	M16	X	-1448	-1448	0	%100
28	M16	Z	-2508	-2508	0	%100



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 2177772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____

Member Distributed Loads (BLC 76 : Structure Wm (330 Deg)) (Continued)

	Member Label	Direction	Start Magnitude	End Magnitude	Start Location(ft)	End Location(ft)
29	M17	X	-.1161	-.1161	0	%100
30	M17	Z	-.201	-.201	0	%100
31	M18	X	-.1448	-.1448	0	%100
32	M18	Z	-.2508	-.2508	0	%100
33	M19	X	-.1273	-.1273	0	%100
34	M19	Z	-.2205	-.2205	0	%100
35	M20	X	-.1161	-.1161	0	%100
36	M20	Z	-.201	-.201	0	%100
37	M21	X	-.1161	-.1161	0	%100
38	M21	Z	-.201	-.201	0	%100
39	M22	X	-.1912	-.1912	0	%100
40	M22	Z	-.3311	-.3311	0	%100
41	M23	X	-.1912	-.1912	0	%100
42	M23	Z	-.3311	-.3311	0	%100
43	M24	X	-.201	-.201	0	%100
44	M24	Z	-.3481	-.3481	0	%100
45	M25	X	-.1273	-.1273	0	%100
46	M25	Z	-.2205	-.2205	0	%100
47	M26	X	-.1161	-.1161	0	%100
48	M26	Z	-.201	-.201	0	%100
49	M27	X	-.2056	-.2056	0	%100
50	M27	Z	-.3561	-.3561	0	%100
51	M28	X	-.1161	-.1161	0	%100
52	M28	Z	-.201	-.201	0	%100
53	M29	X	-.2056	-.2056	0	%100
54	M29	Z	-.3561	-.3561	0	%100
55	M30	X	-.1273	-.1273	0	%100
56	M30	Z	-.2205	-.2205	0	%100
57	M31	X	-.1161	-.1161	0	%100
58	M31	Z	-.201	-.201	0	%100
59	M32	X	-.1161	-.1161	0	%100
60	M32	Z	-.201	-.201	0	%100
61	M33	X	-.1912	-.1912	0	%100
62	M33	Z	-.3311	-.3311	0	%100
63	M34	X	-.1912	-.1912	0	%100
64	M34	Z	-.3311	-.3311	0	%100
65	M35	X	-.201	-.201	0	%100
66	M35	Z	-.3481	-.3481	0	%100
67	M36	X	-.1273	-.1273	0	%100
68	M36	Z	-.2205	-.2205	0	%100
69	MP4A	X	-.2633	-.2633	0	%100
70	MP4A	Z	-.4561	-.4561	0	%100
71	MP3A	X	-.2633	-.2633	0	%100
72	MP3A	Z	-.4561	-.4561	0	%100
73	MP2A	X	-.2633	-.2633	0	%100
74	MP2A	Z	-.4561	-.4561	0	%100
75	MP1A	X	-.2633	-.2633	0	%100
76	MP1A	Z	-.4561	-.4561	0	%100
77	EQUIP	X	-.3003	-.3003	0	%100
78	EQUIP	Z	-.5201	-.5201	0	%100
79	M51	X	-.3003	-.3003	0	%100
80	M51	Z	-.5201	-.5201	0	%100
81	M55A	X	-.1963	-.1963	0	%100
82	M55A	Z	-.34	-.34	0	%100



Member Area Loads

Joint A	Joint B	Joint C	Joint D	Direction	Distribution	Magnitude[ksf]
No Data to Print ...						

Envelope Joint Reactions

Joint	X [lb]	LC	Y [lb]	LC	Z [lb]	LC	MX [k-ft]	LC	MY [k-ft]	LC	MZ [k-ft]	LC
1 N4	1633.575	34	1698.338	16	-220.109	1	-155	74	0	75	.125	40
2	-1396.281	40	527.96	73	-4379.654	19	-493	16	0	1	-.112	34
3 N65	1343.904	44	1440.366	22	4277.776	24	-141	65	0	75	.058	40
4	-1581.798	27	460.935	67	650.575	6	-437	19	0	1	-.151	34
5 N71	468.167	10	29.285	22	785.583	4	0	75	0	75	0	75
6	-467.086	4	8.999	67	-784.775	10	0	1	0	1	0	1
7 Totals:	1494.513	10	3151.206	21	2275.386	1						
8	-1494.512	4	1002.992	67	-2275.392	7						

Envelope AISC 15th(360-16): LRFD Steel Code Checks

Member	Shape	Code Check	Lo...	LC	Shear Check	Lo.....	LC	phi*Pnc...	phi*Pnt [...]	phi*Mn y...	phi*Mn...	Cb	Eqn
1	M1	L4X3X6	.000	281 18	.000	281 z	24	80199.0...	80676	2.686	7.063	1.563	H2-1
2	M3	L4X3X6	.000	.24 20	.000	.24 z	24	80199.0...	80676	2.686	7.063	1.869	H2-1
3	M5	PL3/8x3	.679	0 35	.161	.25 y	34	34985.7...	36450	.284	2.279	1.021	H1-...
4	M6	PL3/8x3	.702	0 40	.190	.25 y	40	34985.7...	36450	.284	2.279	1.014	H1-...
5	M7	PIPE_2.5	.344	11... 6	.091	11...	10	10110.2...	50715	3.596	3.596	1.516	H1-...
6	M8	PL3/8x3	.650	0 23	.247	.227 y	35	35243.3...	36450	.284	2.279	1.398	H1-...
7	M9	PL3/8x3	.632	0 40	.093	286 y	10	34551.7...	36450	.284	2.279	1.21	H1-...
8	M10	PIPE_2.5	.273	11... 12	.120	11...	10	10110.2...	50715	3.596	3.596	1.931	H1-...
9	M11	PIPE_2.0	.301	.495 34	.111	5....	34	21054.34	32130	1.872	1.872	2.181	H1-...
10	M12	PIPE_2.0	.321	.495 41	.119	0	40	21054.34	32130	1.872	1.872	2.261	H1-...
11	M13	PIPE_2.0	.339	.557 35	.129	5....	35	21054.34	32130	1.872	1.872	2.095	H1-...
12	M14	PIPE_2.0	.301	.557 40	.132	5....	38	21054.34	32130	1.872	1.872	1.888	H1-...
13	M15	PL3/8x3	.059	0 38	.056	0 y	35	36078.2...	36450	.284	2.279	1.656	H1-...
14	M16	1.5 w 0.0...	.302	2.... 15	.034	0	3	5179.054	8536.5	.325	.325	1.136	H1-...
15	M17	PL3/8x3	.083	0 36	.026	0 y	5	36078.2...	36450	.284	2.279	1.656	H1-...
16	M18	1.5 w 0.0...	.267	2.... 38	.057	0	6	5179.054	8536.5	.325	.325	1.136	H1-...
17	M19	PL3/8x3	.058	0 11	.065	0 y	10	30936.41	36450	.284	2.279	1.572	H1-...
18	M20	PL3/8x3	.029	.125 37	.056	.125 y	35	36078.2...	36450	.284	2.279	1.663	H1-...
19	M21	PL3/8x3	.070	.125 36	.026	.125 y	5	36078.2...	36450	.284	2.279	1.656	H1-...
20	M22	1.5 w 0.0...	.134	3.... 40	.041	3....	34	6412.349	8536.5	.325	.325	1.113	H1-...
21	M23	1.5 w 0.0...	.285	0 38	.023	3....	5	6412.349	8536.5	.325	.325	1.113	H1-...
22	M24	PIPE_2.0	.031	0 41	.010	0	10	29957.0...	32130	1.872	1.872	1.062	H1-...
23	M25	PL3/8x3	.060	.5 36	.065	.5 y	10	30936.41	36450	.284	2.279	1.614	H1-...
24	M26	PL3/8x3	.047	0 35	.059	0 y	34	36078.2...	36450	.284	2.279	1.645	H1-...
25	M27	1.5 w 0.0...	.318	2.... 24	.031	4....	11	5179.054	8536.5	.325	.325	1.136	H1-...
26	M28	PL3/8x3	.054	.125 34	.034	0 y	4	36078.2...	36450	.284	2.279	1.641	H1-...
27	M29	1.5 w 0.0...	.270	2.... 36	.035	0	1	5179.054	8536.5	.325	.325	1.136	H1-...
28	M30	PL3/8x3	.045	0 28	.030	0 y	5	30936.41	36450	.284	2.279	1.555	H1-...
29	M31	PL3/8x3	.038	.125 33	.059	.125 y	34	36078.2...	36450	.284	2.279	1.645	H1-...
30	M32	PL3/8x3	.054	.125 34	.034	.125 y	4	36078.2...	36450	.284	2.279	1.641	H1-...
31	M33	1.5 w 0.0...	.165	3.... 34	.044	0	35	6412.349	8536.5	.325	.325	1.113	H1-...
32	M34	1.5 w 0.0...	.315	0 35	.028	3....	4	6412.349	8536.5	.325	.325	1.111	H1-...
33	M35	PIPE_2.0	.030	0 33	.005	0	5	29957.0...	32130	1.872	1.872	1.062	H1-...
34	M36	PL3/8x3	.043	.5 26	.030	.5 y	5	30936.41	36450	.284	2.279	1.614	H1-...
35	MP4A	PIPE_2.0	.412	1.25 33	.106	4....	6	20866.7...	32130	1.872	1.872	1.584	H1-...
36	MP3A	PIPE_2.0	.161	4.... 4	.046	1....	10	20866.7...	32130	1.872	1.872	1.636	H1-...
37	MP2A	PIPE_2.0	.238	4.... 4	.062	4....	4	20866.7...	32130	1.872	1.872	1.633	H1-...
38	MP1A	PIPE_2.0	.431	1.25 42	.137	4....	8	20866.7...	32130	1.872	1.872	1.582	H1-...



Company : Colliers Engineering & Design
 Designer :
 Job Number : Project # 21777772
 Model Name : Colliers Engineering & Design

Nov 20, 2023
 11:41 AM
 Checked By: _____


Envelope AISC 15th(360-16): LRFD Steel Code Checks (Continued)

Member	Shape	Code Check	Lo...	LC	Shear Check	Lo.....	LC	phi*Pnc...	phi*Pnt [..	phi*Mn y...	phi*Mn...	Cb	Eqn
39	M55A PIPE 2.0	.045	6....	4	.003	0	23	20401.1...	32130	1.872	1.872	1.136	H1-...

Envelope AISI S100-16: LRFD Cold Formed Steel Code Checks

Memb...	Shape	Code Check	Locf...	LC	Shear Check	Loc.....	phi*P...	phi*T...	phi*M...	phi*M...	phi...	phi...	Cb	Eqn
1	EQUIP P1000	.086	1.958	4	.013	3.6...y	5	6976...	1475...	.334	.649	212..425..	1.5...	H1.2...
2	M51 P1000	.112	1.958	4	.014	3.6...y	5	6976...	1475...	.334	.649	212..425..	1.5...	H1.2...

ATTACHMENT 5



POST RD E

Location POST RD E

Mblu F09/ / 063/000 /

Acct# 29409

Owner CONNECTICUT STATE OF

Assessment \$689,500

Appraisal \$985,000

PID 100302

Building Count 1

Current Value

Appraisal			
Valuation Year	Improvements	Land	Total
2020	\$985,000	\$0	\$985,000
Assessment			
Valuation Year	Improvements	Land	Total
2020	\$689,500	\$0	\$689,500

Owner of Record

Owner CONNECTICUT STATE OF
Co-Owner CELL TOWER/WALGREENS
Address 30 TRINITY ST
 HARTFORD, CT 06106

Sale Price \$0
Certificate
Book & Page 0000/0000
Sale Date 10/01/2005

Ownership History

Ownership History				
Owner	Sale Price	Certificate	Book & Page	Sale Date
CONNECTICUT STATE OF	\$0		0000/0000	10/01/2005

Building Information

Building 1 : Section 1

Year Built:
Living Area: 0
Replacement Cost: \$0
Building Percent Good:
Replacement Cost
Less Depreciation: \$0

Building Attributes	
Field	Description

ATTACHMENT 6



Certificate of Mailing — Firm

<p>UNITED STATES POSTAL SERVICE®</p> <p>Name and Address of Sender</p> <p>Kenneth C. Baldwin, Esq. Robinson & Cole LLP 280 Trumbull Street Hartford, CT 06103</p>	<p>TOTAL NO. of Pieces Listed by Sender</p> <p>4</p>	<p>TOTAL NO. of Pieces Received at Post Office™</p> <p>4</p>	<p>Affix Stamp Here Postmark with Date of Receipt.</p>	
<p>Postmaster, per (name of receiving enterprise)</p> <p><i>[Signature]</i></p>		<p>Address (Name, Street, City, State, and ZIP Code™)</p> <p>Jennifer Tooker, First Selectwoman Town of Westport 110 Myrtle Avenue Westport, CT 06880 Mary Young, Planning and Zoning Director Town of Westport 110 Myrtle Avenue Westport, CT 06880 State of Connecticut 30 Trinity Street Hartford, CT 06106 Department of Public Safety Connecticut State Police - c/o Brian Benito P.O. Box 2794 Middletown, CT 06457</p>		
<p>USPS® Tracking Number Firm-specific Identifier</p>	<p>Postage</p>	<p>Fee</p>	<p>Special Handling</p>	<p>Parcel Airlift</p>
<p>1.</p>	<p>Old State House Station 06108</p>	<p>4.86</p>		
<p>2.</p>				
<p>3.</p>				
<p>4.</p>				
<p>5.</p>				
<p>6.</p>				

quadrant
CORRECTION
IM4
\$004.00
US POSTAGE

