

10 Industrial Ave, Suite 3 Mahwah, NJ 07430 Phone: 908-447-4716 Kyle Richers Real Estate Consultant

October 9th, 2014

#### **Hand Delivered**

Ms. Melanie A. Bachman Acting Executive Director Connecticut Siting Council 10 Franklin Square New Britain, CT 06051

RE: Sprint Spectrum L.P. notice of intent to modify an existing telecommunications facility located at 23 Kelleher Court, Wethersfield, CT 06109. Known to Sprint Spectrum L.P. as site CT58XC967.

#### Dear Ms. Bachman:

In order to accommodate technological changes, implement Code Division Multiple Access ("CDMA") and/or Long Term Evolution ("LTE") capabilities, and enhance system performance in the state of Connecticut, Sprint Spectrum L.P. plans to modify the equipment configurations at many of its existing cell sites. Please accept this letter and attachments as notification, pursuant to R.C.S.A. Section 16-50j-73, of construction which constitutes an exempt modification pursuant to R.C.S.A. Section 16-50j-72(b)(2). In compliance with R.C.S.A. Section 16-50j-73, a copy of this letter and its attachments is being sent to the chief elected official of the municipality in which affected cell site is located.

CDMA employs Spread-Spectrum technology and special coding scheme to allow multiple users to be multiplexed over the same physical channel.

LTE is a new high-performance air interface for cellular mobile communications. It is designed to increase the capacity and speed of mobile telephone networks.

Attached is a summary of the planned modifications, including power density calculations reflecting the change in Sprint's operations at the site. Also included is documentation of the structural sufficiency of the tower to accommodate the revised antenna configuration.

The changes to the facility do not constitute modification as defined Connecticut General Statues ("C.G.S.") Section 16-50i(d) because the general physical characteristics of the facility will not be significantly changed or altered. Rather, the planned changes to the facility fall squarely within those activities explicitly provided for the R.C.S.A. Section 16-50j-72(b)(2).

- 1. The height of the overall structure will not be affected.
- 2. The proposed changes will not extend the site boundaries. There will be no effect on the site compound.
- 3. The proposed changes will not increase the noise level at the existing facility by 6 decibels or more.
- 4. Radio Frequency power density may increase due to the use of one or more CDMA transmissions. Moreover, LTE will utilize additional radio frequencies newly licensed by the FCC for cellular mobile communications. However, the changes will not increase the calculated "worst case" power density for the combined operations at the site to a level at or above the applicable standard for uncontrolled environments as calculated for a mixed frequency site.

For the foregoing reasons Sprint Spectrum L.P. respectfully submits that the proposed changes at the referenced site constitute exempt modifications under R.C.S.A. Section 16-50j-72(b)(2).

Please feel free to call me at 908-447-4716 or email krichers@transcendwireless.com with questions concerning this matter. Thank you for your consideration.

Sincerely,

Kyle Richers Real Estate Consultant



## RADIO FREQUENCY FCC REGULATORY COMPLIANCE MAXIMUM PERMISSIBLE EXPOSURE (MPE) ASSESSMENT

**Sprint Existing Facility** 

Site ID: CT58XC967

Wethersfield Colo

23 Kelleher Court Wethersfield, CT 06109

September 9, 2014

EBI Project Number: 62144654

21 B Street Burlington, MA 01803 Tel: (781) 273.2500 Fax: (781) 273.3311



September 9, 2014

Sprint Attn: RF Engineering Manager 1 International Boulevard, Suite 800 Mahwah, NJ 07495

Re: Radio Frequency Maximum Permissible Exposure (MPE) Assessment for Site: CT58XC967 - Wethersfield Colo

Site Total: 65.46% - MPE% in full compliance

EBI Consulting was directed to analyze the proposed upgrades to the existing Sprint facility located at **23 Kelleher Court, Wethersfield, CT**, for the purpose of determining whether the radio frequency (RF) exposure levels from the proposed Sprint equipment upgrades on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter ( $\mu$ W/cm2). The number of  $\mu$ W/cm2 calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits, therefore it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) - (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general public may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general public would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

Public exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter ( $\mu$ W/cm<sup>2</sup>). The general population exposure limit for the cellular band (850 MHz Band) is approximately 567  $\mu$ W/cm<sup>2</sup>, and the general population exposure limit for the 1900 MHz and 2500 MHz bands is 1000  $\mu$ W/cm<sup>2</sup>. Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.



Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure. Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

#### **CALCULATIONS**

Calculations were done for the proposed upgrades to the existing Sprint Wireless antenna facility located at **23 Kelleher Court, Wethersfield, CT**, using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. All calculations were performed assuming a lobe representing the maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was focused at the base of the tower. For this report the sample point is the top of a 6 foot person standing at the base of the tower.

For all calculations, all emissions were calculated using the following assumptions:

- 1) 4 channels in the 1900 MHz Band were considered for each sector of the proposed installation.
- 2) 1 channel in the 800 MHz Band was considered for each sector of the proposed installation.
- 3) 2 channels in the 2500 MHz Band were considered for each sector of the proposed installation.
- 4) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.



- 5) For the following calculations the sample point was the top of a six foot person standing at the base of the tower. The maximum gain of the antenna per the antenna manufactures supplied specifications minus 10 dB was used in this direction. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 6) The antennas used in this modeling are the RFS APXVSPP18-C-A20, POWERWAVE P40-16-XLPP-RR-A and the RFS APXVTM14-C-I20. This is based on feedback from the carrier with regards to anticipated antenna selection. The RFS APXVSPP18-C-A20 has a 15.9 dBd gain value at its main lobe at 1900 MHz and 13.4 dBd at its main lobe for 850 MHz. The POWERWAVE P40-16-XLPP-RR-A has a 15.9 dBd gain value at its main lobe at 1900 MHz and 13.4 dBd at its main lobe for 850 MHz. The RFS APXVTM14-C-I20 has a 15.9 dBd gain value at its main lobe at 2500 MHz. The maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was used for all calculations. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 7) The antenna mounting height centerline for the proposed antennas is **123 feet** above ground level (AGL).
- 8) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.

All calculation were done with respect to uncontrolled / general public threshold limits

					_											
	Site ID		967 - Wethersfi													
	Site Addresss	23 Kelleher Co	ourt , Wethersfi	eld, CT, 06109												
	Site Type		Monopole													
							Sector 1									
						Power										
						Out Per			Antenna Gain							Power
Antenna								Composite	(10 db	Antenna	analysis		Cable Loss			Density
Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	(Watts)	Channels	Power		Height (ft)	height	Cable Size	_ , ,	Loss (dB)	ERP	Percentage
1a	Powerwave	P40-16-XLPP-RR-A	RRH	1900 MHz	CDMA / LTE	20	4	80	5.9	123	117	1/2 "	0.5	0	277.39	0.73%
1a	Powerwave	P40-16-XLPP-RR-A	RRH	850 MHz	CDMA / LTE	20	2	20 40	4.2	123 123	117	1/2 "	0.5	0	46.88	0.22%
1B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20		40	5.9	123	117			ensity Value:	138.69 1.59%	0.64%
												Sector to	ital Power L	ensity value.	1.59%	
							Sector 2									
						Power										
						Out Per			Antenna Gain							Power
Antenna						Channel	Number of	Composite	(10 db	Antenna	analysis		Cable Loss	Additional		Density
Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	(Watts)	Channels	Power	reduction)	Height (ft)	height	Cable Size	(dB)	Loss (dB)	ERP	Percentage
2a	RFS	APXVSPP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	4	80	5.9	123	117	1/2 "	0.5	0	277.39	0.73%
2a	RFS	APXVSPP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	3.4	123	117	1/2 "	0.5	0	39.00	0.18%
2B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	5.9	123	117	1/2 "	0.5	0	138.69	0.64%
												Sector to	otal Power D	ensity Value:	1.55%	
							Sector 3									
						Power										
						Out Per			Antenna Gain							Power
Antenna							Number of	Composite	(10 db	Antenna	analysis		Cable Loss	Additional		Density
Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	(Watts)	Channels	Power	reduction)	Height (ft)	-	Cable Size	(dB)	Loss (dB)	ERP	Percentage
3a	RFS	APXVSPP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	4	80	5.9	123	117	1/2 "	0.5	0	277.39	0.73%
3a	RFS	APXVSPP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	3.4	123	117	1/2 "	0.5	0	39.00	0.18%
3B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	5.9	123	117	1/2 "	0.5	0	138.69	0.64%
												Sector to	otal Power D	ensity Value:	1.55%	

Site Composite MPE %										
Carrier	MPE %									
Sprint	4.69%									
Town of Wethersfield	2.25%									
Clearwire	0.68%									
AT&T	17.54%									
Verizon Wireless	26.26%									
Nextel	13.89%									
T-Mobile	0.15%									
Total Site MPE %	65.46%									



#### **Summary**

All calculations performed for this analysis yielded results that were well within the allowable limits for general public Maximum Permissible Exposure (MPE) to radio frequency energy.

The anticipated Maximum Composite contributions from the Sprint facility are 4.69% (1.59% from sector 1, 1.55% from sector 2 and 1.55% from sector 3) of the allowable FCC established general public limit considering all three sectors simultaneously sampled at the ground level.

The anticipated composite MPE value for this site assuming all carriers present is **65.46**% of the allowable FCC established general public limit sampled at 6 feet above ground level. This total composite site value is based upon MPE values listed in the Connecticut Siting Council database for existing carrier emissions.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.


Scott Heffernan

RF Engineering Director

**EBI Consulting** 

21 B Street

Burlington, MA 01803



#### STRUCTURAL ASSESSMENT

SITE: Wethersfield Colo (CT58XC967)

23 Kelleher Court - Firehouse #3

Wethersfield, Hartford County, Connecticut 06109

**PREPARED FOR:** Transcend Wireless

**CONTACT PERSON:** Mike Kithcart

**Transcend Wireless** 

48 Spruce Street, Oakland, NJ 07436

**PREPARED BY:** Ramaker & Associates, Inc.

1120 Dallas Street

Sauk City, Wisconsin 53583 Telephone: (608) 643-4100 Facsimile: (608) 643-7999

RAMAKER JOB NUMBER: 28752

**DATE OF REPORT ISSUANCE:** August 5, 2014

Jonathan Styx

**Engineering Technician** 

08/05/14

Date

James R. Skowronski, P.E.

Supervising Engineer

Date

### **TABLE OF CONTENTS**

3	UTIVE SUMMARY	EXECU1
4	DUCTION	INTROD
	PURPOSE OF REPORT	2.1 2.2 2.3
5	L DEVELOPMENT	MODEL
	EXISTING STRUCTURE INFORMATION TOWER LOADING	3.1 3.2 3.3 3.4
7	YSIS RESULTS	ANALYS
	ANALYSIS RESULTS BASE REACTIONS MOUNT ASSESSMENT	
9	ATIONS	LIMITA
10	RENCES	REFERI

#### **LIST OF APPENDICES**

- A. TOWER FIGURES
- **B. TOWER CALCULATIONS**
- C. MOUNT CALCULATIONS

## SECTION 1 EXECUTIVE SUMMARY

This report summarizes the structural analysis conducted by Ramaker & Associates, Inc. (RAMAKER) for Transcend Wireless on behalf of Sprint, who intends to install additional equipment on an existing tower.

The Sprint proposed loading includes installing three (3) RFS APXV9TM14-ALU-I20 panel antennas and three (3) Alcatel-Lucent TD-RRH8x20-25 RRH units on the existing t-frame at a centerline elevation of 174-feet AGL. The proposed antennas shall be fed with one (1) 1-1/4-inch hybrid cable that was assumed to be routed up inside the tower.

The existing tower base plate and anchor bolts could become overstressed under the proposed loading conditions. The tower base plate shall be modified to include the addition of fifteen (15) new stiffener plates per the modification drawings included in this report. The base plate shall also be grouted with the inclusion of drainage channels through the grout per the modification drawings included in this report. The required modifications shall be completed prior to any equipment loading changes.

Results of our tower analysis show that the *modified* tower will be stressed to a maximum of **97.4** percent of capacity under proposed loading conditions *after all proposed modifications are made to the tower per construction documents by RAMAKER are completed*.

All proposed model reactions exceed the previous design reactions by URS. However the foundation was further analyzed and was determined to provide adequate strength for the proposed loading conditions.

Results of our mount assessment show that by engineering calculation and inspection, the antenna and RRH mounting structure is capable of supporting the existing and proposed Sprint 2.5 equipment deployment without causing an overstress condition in the antenna and RRH mounting structure.

In summary, the *modified* tower will pass the TIA/EIA-222-F code requirements under proposed loading conditions *after all proposed tower modifications have been completed.* The mounting structure will pass the TIA-222 code requirements under proposed loading conditions.

## SECTION 2 INTRODUCTION

#### 2.1 PROJECT INFORMATION

This report summarizes the structural analysis conducted by Ramaker & Associates, Inc. (RAMAKER) for Transcend Wireless on behalf of Sprint, who intends to install additional equipment on an existing tower.

#### 2.2 PURPOSE OF REPORT

The analysis activities of this report were conducted for the purposes of creating and analyzing a model of the subject structure under the required loading conditions. Base reactions from the resulting model were also determined for tower foundation and support development. Recommendations regarding the analysis results, loading configuration, and structural modifications are also provided.

#### 2.3 SCOPE OF SERVICES

RAMAKER developed a finite element model (FEM) of the tower, using tnxTower, for member force, joint deflection, and structure reaction determinations. Subsequently, this report was drafted to provide our engineering recommendations. All information contained herein is valid only for the described structure configuration and loading conditions. RAMAKER reserves the right to modify our recommendations should alterations to the tower loading occur.

## SECTION 3 MODEL DEVELOPMENT

#### 3.1 INTRODUCTION

RAMAKER developed a FEM of the tower superstructure. Required static loads consisting of the antenna configuration, wind forces, ice loads, and linear appurtenances (including cable loads) were then applied to the FEM. As a result, all member forces, allowable capacities, and base reactions were computed. Additionally, potentially overstressed members were identified.

#### 3.2 EXISTING STRUCTURE INFORMATION

Existing structure information was gathered from:

- Previous structural analysis by URS Corp., dated October 11, 2004,
- Previous structural analysis by Tectonic, Tec W.O., 6318.58-967, dated November 12, 2012.
- Previous structural analysis by URS Corp., dated May 22, 2014.

#### 3.3 TOWER LOADING

RAMAKER understands that the tower loading to be used for this analysis will consist of the existing and proposed antenna, mount, and cable configurations as shown in the following chart:

Elevation	Appurtenance	Mount	Coax	Owner	Status	
	(1) 20' Omni					
	(1) 10' Omni		(2) 1-5/8			
180	(1) 8' Dipole	(3) 4' T-Arms	(3) 7/8 (1) 5/8	Town	Existing	
	(2) Sinclair SC473-HF1LDF Omni		(5) 1/2			
	(1) DPSpectra DS4C03F36U-D					
	(1) Powerwave P40-16XLPP-RR				Existing	
174	(2) RFS APXVSPP18-C	(3) 12' T-Arms	(6) 1-5/8		LAISTING	
174	(3) RFS APXV9TM14-ALU-120	(3) 12 1-411115	(3) 1-1/4	Cariat	Proposed	
	(3) ALU TD-RRH 8x20		Hybriflex	Sprint	Торозец	
169	(3) ALU 1900 MHz	(1) Ring Mount	(1) Hybriflex		Existing	
109	(3) ALU 800 MHz RRH	(I) King Mount				
163	(1) 2' Dish	Ring Mount	(2) 1-5/8	Town	Evicting	
103	(1) 1' Microwave Dish	King Wount	(2) 1-5/6	TOWIT	Existing	
151	(6) Ericsson AIR B2A/B4P	(2) 10' T Armo	(12) 1-5/8	T-Mobile	Existing	
131	(3) 4"x8"x4" TMA's	(3) 12' T-Arms	(6) 1-5/8	1-Mobile		
146	(1) 2' Dish	Ring Mount	(1) 1-5/8	Town	Existing	
140	(6) Allgon 7770 Panels	(2) T Arm w/ Platform	(12) 1 5/9	AT&T	Foliation	
140	(1) Andrew SBNH-1D6565C	(3) T-Arm w/ Platform	(12) 1-5/8	AIQI	Existing	

#### **WETHERSFIELD COLO (CT58XC967)**

Elevation	Appurtenance	Mount	Coax	Owner	Status	
	(1) Powerwave P65-15-XLH-RR					
	(1) KMW AM-X-CD-16-6-00T			AT&T (Cont.)		
140 (Cont.)	(12) 4"x8"x4" TMA's	(Cont.)	(Cont.)		Existing (Cont.)	
	(6) Ericsson RRUS-11				,	
	(1) Raycap DC6-48-60-18-8F					
	(3) Antel BXA 171063-12CF-EDIN-2					
	(3) Antel BXA-70063-4CF-EDIN-X		(12) 1-5/8	Verizon	Existing	
130	(3) Antel BXA-70063-6CF-EDIN-X	(1) Low Profile Platform	(6) 1-5/8 (1) 1-5/8			
	(3) Rymsa MGD3-900TX		Hybriflex			
	(3) Ericsson RRUS-12					
123	(3) RFS APXV18-206517-C	(1) Ring Mount	(3) 1-5/8	Metro PCS	Existing	
50	(5) GPS Antennas	Flush Mount	(5) LMR-400	Town	Existing	

#### 3.4 WIND AND ICE LOAD

Wind forces used in model development are in compliance with the TIA/EIA-222-F Standard. These guidelines call for an analysis to be performed which assumes a basic wind speed of 80 miles-perhour (mph) without ice in Hartford County. The tower is also designed for a 69 mph basic wind speed with 0.50-inch of radial ice.

## SECTION 4 ANALYSIS RESULTS

#### 4.1 ANALYSIS RESULTS

The *modified* tower superstructure was analyzed with the combined existing and proposed antenna loading with and without radial ice. The computed maximum tower member stress capacities are as follows:

Component Type	Percent Capacity
Section 1	36.6
Section 2	59.5
Section 3	77.2
Section 4	97.4
Base Plate	92.9
Anchor Bolts	88.7
RATING =	97.4

Results of our analysis show that the *modified* tower will be stressed to a maximum of 97.4 percent of capacity under the proposed loading conditions *after all proposed tower modifications have been completed.* 

#### 4.2 BASE REACTIONS

The computed maximum reactions under the corresponding maximum moment are as follows:

Load Type	URS Analysis	Proposed Model		
Axial (k)	53	55.8		
Shear (k)	39	44.8		
Moment (k-ft)	4502	5015.6		

All proposed model reactions exceed the previous design reactions by URS. However the foundation was further analyzed and was determined to provide adequate strength for the proposed loading conditions.

#### **WETHERSFIELD COLO (CT58XC967)**

#### 4.3 MOUNT ASSESSMENT

By engineering calculation and inspection, the antenna mounting structure is capable of supporting the existing and proposed Sprint 2.5 equipment deployment without causing an overstress condition in the antenna mounting structure.

This assessment is inclusive of the entire antenna mounting structure, including tower platforms, arms, and all other aspects of the mounting structure that will support the Sprint 2.5 equipment deployment. This assessment assumes that the mounting structure(s) has been installed correctly, is free from deterioration, and is maintained properly.

## SECTION 5 LIMITATIONS

The recommendations contained within this report were developed using general project information provided by the owner, tower manufacturer, general field observations, reference information and laboratory testing data, as applicable. All recommendations pertain only to the proposed tower construction, location, and loading as described in this report. RAMAKER assumes no responsibility for failures caused by factors beyond our control. These include but are not limited to the following:

- 1. Missing, corroding, and/or deteriorating members
- 2. Improper manufacturing and/or construction
- 3. Improper maintenance

RAMAKER assumes no responsibility for modifications completed prior to or hereafter in which RAMAKER was not directly involved. These modifications include but are not limited to the following:

- 1. Replacing or strengthening bracing members
- 2. Reinforcing or extending vertical members
- 3. Installing or removing antenna mounting gates or side arms
- 4. Changing loading configurations

Furthermore, RAMAKER hereby states that this document represents the entire report and that it assumes no liability for any factual changes that may occur after the date of this report. All representations, recommendations and conclusions are based on the information contained and set forth herein. If you are aware of any information contrary to that contained herein, or if you are aware of any defects arising from the original design, material, fabrication and erection deficiencies, you should disregard this report and immediately contact RAMAKER. RAMAKER isn't liable for any representation, recommendation or conclusion not expressly stated herein.

The tower owner is responsible for verifying that the existing loading on the tower is consistent with the loading applied to the tower within this report.

## SECTION 6 REFERENCES

- 1. 2003 International Building Code.
- 2. Telecommunications Industries Association, <u>Structural Standards for Steel Antenna Towers and Antenna Supporting Structures</u>, TIA Standard TIA/EIA-222-F 1996, Washington, D.C.

## APPENDIX A

### **TOWER FIGURES**


									<u>180.0 ft</u>		4' T-Arm (1 4' T-Arm (1 4' T-Arm (1 (3) 6' x 2"   (3) 6' x 2"
-	37.75	18	0.2500	4.33	23.1000	33,2490		2846.3	1423 ft		20 Ormi ( 10 Orm
2	53.00	16	03750	5.92	31.5849	45.8330		8270.2	New China		Tri-Antenn Tri-Antenn Tri-OMHz : 1900MHz : 1900MHz : 1900MHz : 1900MHz : 1900MHz : 1900MHz : 2 B00MHz : 2 H P Dish Tri-OMHz : 12 T-Arm 13 T-Arm 14 T-Arm 15 T-Arm 15 T-Arm 16 T-Arm 17 T-Arm 17 T-Arm 18 T-Arm 18 T-Arm 18 T-Arm 18 T-Arm 19 T-Arm 19 T-Arm 19 T-Arm 19 T-Arm 10 T-Arm 10 T-Arm 10 T-Arm 10 T-Arm 10 T-Arm 11 T-Arm 12 T-Arm 12 T-Arm 12 T-Arm 12 T-Arm 13 T-Arm 14 T-Arm 15 T-Arm 16 T-Arm 17 T-Arm 17 T-Arm 17 T-Arm 18 T-Arm 18 T-Arm 18 T-Arm 18 T-Arm 18 T-Arm 19 T-Arm 10
п	63.00	16	0.3750	7.50	43.4915	57.7420	A572-65	10839.2	93.6 ft		2. Towe 3. Defile 4. Weld 5. Conn 6. Towe 7. Weld: 8. TOW
٩	53.00	16	0.3750		54.9754	69 2250		13316.7	46.5 ft_	38568 lb	MOMENT 24184 lb-ft ICE MOMENT 115600 lb-ft
Section	Length (ff)	Number of Sides	Thickness (in)	Socket Length (ff)	Top Dia (in)	Bot Dia (in)	Grade	Weight (lb) 35272.4	<u>1.0 ft</u>	TORQUE 273 lb-ft REACTIONS - 80 mph WI	IND

#### DESIGNED APPURTENANCE LOADING


TYPE	ELEVATION	TYPE	ELEVATION
4' T-Arm (Town)	181	RRUS-11 (ATT)	143
4' T-Arm (Town)	181	RRUS-11 (ATT)	143
4' T-Arm (Town)	181	RRUS-11 (ATT)	143
(3) 6' x 2" Pipe Mount (Town)	181	RRUS-11 (ATT)	143
(3) 6' x 2" Pipe Mount (Town)	181	RRUS-11 (ATT)	143
(3) 6' x 2" Pipe Mount (Town)	181	(2) TMA 8"x8"x3" (ATT)	141
20' Omni (Town)	181	(2) TMA 8"x8"x3" (ATT)	141
10' Omni (Town)	181	(2) TMA 8"x8"x3" (ATT)	141
8' Dipole (Town)	181	(2) TMA 8"x8"x3" (ATT)	141
SC473-HF1LDF (4.875' Omni) (Town)	181	(2) TMA 8"x8"x3" (ATT)	141
SC473-HF1LDF (4.875' Omni) (Town)	181	(2) TMA 8"x8"x3" (ATT)	141
DS4C03F36U-D (8' Omni) (Town)	181	(2) 7770 w/ mount pipe (ATT)	141
Dual Diversity TTA 432-83H-01-T (Town)	181	(2) 7770 w/ mount pipe (ATT)	141
12' T-Arm (Sprint)	174	(2) 7770 w/ mount pipe (ATT)	141
12' T-Arm (Sprint)	174	SBNH-1D6565C w/Mount Pipe (ATT)	141
12' T-Arm (Sprint)	174	P65-15-XLH-RR w/Mount Pipe (ATT)	141
P40-16XLPP-RR w/Mount Pipe (Sprint)	174	AM-X-CD-16-65-00T w/Mount Pipe (ATT)	141
APXVSPP18-C w/Mount Pipe (Sprint)	174	DC6-48-60-18-8F (ATT)	141
APXVSPP18-C w/Mount Pipe (Sprint)	174	14' T-Arm (ATT)	141
APXV9TM14-ALU-120 w/ 3.5" mount pipe (Sprint)	174	14' T-Arm (ATT)	141
APXV9TM14-ALU-120 w/ 3.5" mount pipe (Sprint)	174	14' T-Arm (ATT)	141
APXV9TM14-ALU-120 w/ 3.5" mount pipe (Sprint)	174	RYMSA MGD3-900TX w/Mount Pipe (Verizon)	131
TD-RRH 8x20 (Sprint)	174	BXA-171063-12CF-EDIN-2 w/ Mount Pipe	131
TD-RRH 8x20 (Sprint)	174	(Verizon)	
TD-RRH 8x20 (Sprint)	174	BXA-171063-12CF-EDIN-2 w/ Mount Pipe (Verizon)	131
Tri-Antenna Mount (Sprint)	170	,	
Tri-Antenna Mount (Sprint)	170	BXA-171063-12CF-EDIN-2 w/ Mount Pipe (Verizon)	131
Tri-Antenna Mount (Sprint)	170	BXA-70063-4CF-EDIN-X w/Mount Pipe (Verizon)	131
1900MHz 4x40W RRH (Sprint)	170	BXA-70063-4CF-EDIN-X W/Mount Pipe (Verizon)	131
1900MHz 4x40W RRH (Sprint)	170	BXA-70063-4CF-EDIN-X W/Mount Pipe (Verizon)  BXA-70063-4CF-EDIN-X w/Mount Pipe (Verizon)	131
1900MHz 4x40W RRH (Sprint)	170	BXA-70063-4CF-EDIN-X W/Mount Pipe (Verizon)  BXA-70063-6CF-EDIN-X w/Mount Pipe (Verizon)	131
800MHz 2x50W RRH (Sprint)	170	BXA-70063-6CF-EDIN-X W/Mount Pipe (Verizon)	131
800MHz 2x50W RRH (Sprint)	170	BXA-70063-6CF-EDIN-X w/Mount Pipe (Verizon)	131
800MHz 2x50W RRH (Sprint)	170	RRUS-12 (Verizon)	131
2' HP Dish (Town)	164	RRUS-12 (Verizon)	131
1' Dish w/o radome (Town)	163	RRUS-12 (Verizon)	131
12' T-Arm (T-Mobile)	152	Andrew 14'6" Low-Profile Platform (Verizon)	131
(2) AIR B2A/B4P w/ Mount Pipe (T-Mobile)	152	RYMSA MGD3-900TX w/Mount Pipe (Verizon)	131
(2) AIR B2A/B4P w/ Mount Pipe (T-Mobile)	152	RYMSA MGD3-900TX w/Mount Pipe (Verizon)	131
(2) AIR B2A/B4P w/ Mount Pipe (T-Mobile)	152	APXV18-206517-C w/Mount Pipe (Metro PCS)	124
TMA 4"x8"x4" (T-Mobile)	152	APXV18-206517-C w/Mount Pipe (Metro PCS)  APXV18-206517-C w/Mount Pipe (Metro PCS)	124
TMA 4"x8"x4" (T-Mobile)	152		124
TMA 4"x8"x4" (T-Mobile)	152	APXV18-206517-C w/Mount Pipe (Metro PCS)  GPS (Town)	124
12' T-Arm (T-Mobile)	152		51
12' T-Arm (T-Mobile)	152	(2) GPS (Town)	51
2' HP Dish (Dish)	147	(2) GPS (Town)	101
RRUS-11 (ATT)	143	7	


GRADE	Fy	Fu	GRADE	Fy	Fu
A572-65	65 ksi	80 ksi		-	
<ol> <li>Tower is also</li> <li>Deflections a</li> <li>Weld togethe</li> <li>Connections</li> <li>Tower memb</li> </ol>	designed for a 69 mph are based upon a 60 mph ar tower sections have f use galvanized A325 b ers are "hot dipped" gal bricated with ER-70S-6	wind in accordance with basic wind with 0.50 in h wind. lange connections. olts, nuts and locking de lvanized in accordance	ice.	e-F Standard.	


TIA/EIA-222-F - 80 mph/69 mph 0.5000 in Ice Leg Compression (lb)















Round

Flat

Elevation (ft)




Ramaker & Associates Wethersfield Colo (CT58XC967) Project: **28752** 1120 Dallas St. Client: Sprint Drawn by: JDS App'd: Sauk City, WI 53583 Phone: (608) 643-4100 Code: TIA/EIA-222-F Date: 08/05/14 Scale: NTS FAX: (608) 643-7999 Path: I:\28700\28752\Structural\tnx\28752 rev1.eri

Truss Leg

### Stress Distribution Chart

1' - 180'







# APPENDIX B TOWER CALCULATIONS

#### Ramaker & Associates

1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999

Job		Page
	Wethersfield Colo (CT58XC967)	1 of 22
Project		Date
	28752	09:31:24 08/05/14
Client		Designed by
	Sprint	JDS

#### **Tower Input Data**

There is a pole section.

This tower is designed using the TIA/EIA-222-F standard.

The following design criteria apply:

- Basic wind speed of 80 mph.
- Nominal ice thickness of 0.5000 in.
- Ice density of 56 pcf.
- A wind speed of 69 mph is used in combination with ice.
- Temperature drop of 50 °F.
- Deflections calculated using a wind speed of 60 mph.
- Weld together tower sections have flange connections..
- Connections use galvanized A325 bolts, nuts and locking devices. Installation per TIA/EIA-222 and AISC Specifications..
- Tower members are "hot dipped" galvanized in accordance with ASTM A123 and ASTM A153 Standards...
- Welds are fabricated with ER-70S-6 electrodes..
- A non-linear (P-delta) analysis was used.
- Pressures are calculated at each section.
- Stress ratio used in pole design is 1.333.
- Local bending stresses due to climbing loads, feed line supports, and appurtenance mounts are not considered.

#### **Options**

Consider Moments - Legs Consider Moments - Horizontals Consider Moments - Diagonals Use Moment Magnification

- √ Use Code Stress Ratios
- ✓ Use Code Safety Factors Guys
   Escalate Ice
   Always Use Max Kz
   Use Special Wind Profile
   Include Bolts In Member Capacity
   Leg Bolts Are At Top Of Section
- √ Secondary Horizontal Braces Leg
   Use Diamond Inner Bracing (4 Sided)
   Add IBC .6D+W Combination

Distribute Leg Loads As Uniform Assume Legs Pinned

- √ Assume Rigid Index Plate
- √ Use Clear Spans For Wind Area
- √ Use Clear Spans For KL/r
   Retension Guys To Initial Tension
   Bypass Mast Stability Checks
- √ Use Azimuth Dish Coefficients
- √ Project Wind Area of Appurt.
- √ Autocalc Torque Arm Areas
  SR Members Have Cut Ends
  Sort Capacity Reports By Component
  Triangulate Diamond Inner Bracing
  Use TIA-222-G Tension Splice Capacity
  Exemption

Treat Feedline Bundles As Cylinder Use ASCE 10 X-Brace Ly Rules

- √ Calculate Redundant Bracing Forces Ignore Redundant Members in FEA SR Leg Bolts Resist Compression
- √ All Leg Panels Have Same Allowable Offset Girt At Foundation
- √ Consider Feedline Torque
- √ Include Angle Block Shear Check Poles

Include Shear-Torsion Interaction Always Use Sub-Critical Flow Use Top Mounted Sockets

### **Tapered Pole Section Geometry**

Section	Elevation	Section	Splice	Number	Top	Bottom	Wall	Bend	Pole Grade
		Length	Length	of	Diameter	Diameter	Thickness	Radius	
	ft	ft	ft	Sides	in	in	in	in	
L1	180.00-142.25	37.75	4.33	18	23.1000	33.2490	0.2500	1.0000	A572-65
									(65 ksi)
L2	142.25-93.58	53.00	5.92	16	31.5849	45.8330	0.3750	1.5000	A572-65
									(65 ksi)

#### Ramaker & Associates

1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999

Job		Page
	Wethersfield Colo (CT58XC967)	2 of 22
Project		Date
	28752	09:31:24 08/05/14
Client		Designed by
	Sprint	JDS

Section	Elevation	Section	Splice	Number	Top	Bottom	Wall	Bend	Pole Grade
		Length	Length	of	Diameter	Diameter	Thickness	Radius	
	ft	ft	ft	Sides	in	in	in	in	
L3	93.58-46.50	53.00	7.50	16	43.4915	57.7420	0.3750	1.5000	A572-65
									(65 ksi)
L4	46.50-1.00	53.00		16	54.9754	69.2250	0.3750	1.5000	A572-65
									(65 ksi)

			7	<b>Tapere</b>	d Pole F	Properti	es			
Section	Tip Dia.	Area	<i>I</i>	r	<i>C</i>	I/C	<i>J</i>	It/Q	w	w/t
	in	in²	in <sup>4</sup>	in	in	in <sup>3</sup>	in	in <sup>2</sup>	in	
L1	23.4564	18.1315	1196.0325	8.1118	11.7348	101.9219	2393.6388	9.0675	3.6256	14.502
	33.7619	26.1847	3602.3567	11.7146	16.8905	213.2772	7209.4536	13.0948	5.4118	21.647
L2	33.3905	37.3348	4594.2331	11.1107	16.1083	285.2092	9258.0285	18.4601	5.5391	14.771
	46.7309	54.3791	14196.0424	16.1830	23.3748	607.3217	28607.0301	26.8876	8.3745	22.332
L3	45.9665	51.5781	12113.4320	15.3495	22.1807	546.1256	24410.2761	25.5027	7.9086	21.089
	58.8732	68.6253	28531.3769	20.4227	29.4484	968.8593	57494.7536	33.9316	10.7444	28.652
L4	58.1084	65.3158	24599.3885	19.4378	28.0375	877.3756	49571.2418	32.2952	10.1939	27.184
	70.5812	82.3618	49322.8482	24.5106	35.3047	1397.0598	99392.5044	40.7236	13.0295	34.745

Tower Elevation	Gusset Area	Gusset Thickness	Gusset Grade	$Adjust.\ Factor \ A_f$	Adjust. Factor	Weight Mult.	Double Angle Stitch Bolt	Double Angle Stitch Bolt
	(per face)			,	$A_r$		Spacing	Spacing
							Diagonals	Horizontals
ft	ft <sup>2</sup>	in					in	in
L1 180.00-142.25				1	1	1		
L2 142.25-93.58				1	1	1		
L3 93.58-46.50				1	1	1		
L4 46.50-1.00				1	1	1		

### **Monopole Base Plate Data**

Base Plate Da	ta
Base plate is square	
Base plate is grouted	$\checkmark$
Anchor bolt grade	A615-75
Anchor bolt size	2.2500 in
Number of bolts	16
Embedment length	87.0000 in
f'c	4 ksi
Grout space	2.0000 in
Base plate grade	A633-50
Base plate thickness	2.2500 in
Bolt circle diameter	76.0000 in
Outer diameter	82.0000 in
Inner diameter	67.7500 in
Base plate type	Stiffened Plate
Bolts per stiffener	1
Stiffener thickness	0.5000 in
Stiffener height	12.0000 in

Ramaker & Associates

1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999

Job		Page
	Wethersfield Colo (CT58XC967)	3 of 22
Project		Date
	28752	09:31:24 08/05/14
Client		Designed by
	Sprint	JDS

## Feed Line/Linear Appurtenances - Entered As Area

Description	Face	Allow Shield	Component	Placement	Total Number		$C_A A_A$	Weight
	or Leg	Sniela	Type	ft	Number		ft²/ft	plf
1 5/8	A	No	Inside Pole	180.00 - 1.00	1	No Ice	0.00	1.04
(Town)						1/2" Ice	0.00	1.04
1 5/8	Α	No	CaAa (Out Of	180.00 - 1.00	1	No Ice	0.20	1.04
(Town)			Face)		_	1/2" Ice	0.30	2.55
7/8	Α	No	Inside Pole	180.00 - 1.00	1	No Ice	0.00	0.54
(Town)	11	110	made i die	100.00 1.00		1/2" Ice	0.00	0.54
7/8	۸	No	CaAa (Out Of	180.00 - 1.00	1	No Ice	0.11	0.54
	A	NO	`	100.00 - 1.00	1	1/2" Ice	0.11	1.52
(Town)		N.T.	Face)	100.00 1.00	1			
5/8	A	No	Inside Pole	180.00 - 1.00	1	No Ice	0.00	0.40
(Town)				100.00 1.00	_	1/2" Ice	0.00	0.40
1/2	Α	No	Inside Pole	180.00 - 1.00	5	No Ice	0.00	0.25
(Town) *****						1/2" Ice	0.00	0.25
HB114-13U3M12-225F	В	No	CaAa (Out Of	174.00 - 1.00	1	No Ice	0.13	0.37
(Sprint)			Face)			1/2" Ice	0.23	1.44
HB114-13U3M12-225F	В	No	CaAa (Out Of	174.00 - 1.00	2	No Ice	0.13	0.37
(Sprint)			Face)			1/2" Ice	0.23	1.44
HB114-13U3M12-225F	В	No	Inside Pole	174.00 - 1.00	1	No Ice	0.00	0.37
(Sprint) *****						1/2" Ice	0.00	0.37
1 5/8	Α	No	Inside Pole	164.00 - 1.00	1	No Ice	0.00	1.04
(Town Dish)	71	110	mside i oie	104.00 1.00	1	1/2" Ice	0.00	1.04
1 5/8	A	No	Inside Pole	153.00 - 1.00	12	No Ice	0.00	1.04
(T-Mobile)						1/2" Ice	0.00	1.04
1 5/8	Α	No	CaAa (Out Of	153.00 - 1.00	1	No Ice	0.20	1.04
(T-Mobile)	А	140	Face)	133.00 - 1.00	1	1/2" Ice	0.30	2.55
1 5/8	Α	No	CaAa (Out Of	153.00 - 1.00	5	No Ice	0.20	1.04
(T-Mobile) ****	Α	NO	Face)	133.00 - 1.00	3	1/2" Ice	0.30	2.55
1 5/8	В	No	Inside Pole	143.00 - 1.00	1	No Ice	0.00	1.04
(Town Dish)	ь	NO	filside Fole	143.00 - 1.00	1	1/2" Ice	0.00	1.04
****								
1 5/8	C	No	Inside Pole	141.00 - 1.00	12	No Ice	0.00	1.04
(ATT)						1/2" Ice	0.00	1.04
1 5/8	В	No	CaAa (Out Of	141.00 - 1.00	1	No Ice	0.20	1.04
(ATT)			Face)			1/2" Ice	0.30	2.55
1 5/8	В	No	CaAa (Out Of	141.00 - 1.00	5	No Ice	0.20	1.04
(ATT)			Face)			1/2" Ice	0.30	2.55
1 5/8	В	No	CaAa (Out Of	141.00 - 1.00	6	No Ice	0.20	1.04
(ATT) *****			Face)			1/2" Ice	0.30	2.55
1 5/8	В	No	Inside Pole	131.00 - 1.00	12	No Ice	0.00	1.04
	Б	140	HISIUC FUIC	131.00 - 1.00	1 4	1/2" Ice	0.00	1.04
(Verizon)	D	Mo	Co A o (Out Of	121.00 1.00	7			
1 5/8	В	No	CaAa (Out Of	131.00 - 1.00	7	No Ice	0.20	1.04
(Verizon) ****			Face)			1/2" Ice	0.30	2.55
1 5/8	C	No	Inside Pole	121.00 - 1.00	6	No Ice	0.00	1.04
(Metro PCS)  ****						1/2" Ice	0.00	1.04
LMR-400	В	No	CaAa (Out Of	51.00 - 1.00	1	No Ice	0.04	0.07
(Town)			Face)			1/2" Ice	0.14	0.62
LMR-400	В	No	CaAa (Out Of	51.00 - 1.00	4	No Ice	0.04	0.07
(Town) ****			Face)			1/2" Ice	0.14	0.62
Step Bolts	C	No	CaAa (Out Of	131.00 - 1.00	1	No Ice	0.03	0.49
(Tower)	-		Face)		-	1/2" Ice	0.13	0.97

Ramaker & Associates
1120 Dallas St.
Sauk City, WI 53583

Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999

Job		Page
	Wethersfield Colo (CT58XC967)	4 of 22
Project		Date
	28752	09:31:24 08/05/14
Client		Designed by
	Sprint	JDS

Feed Line/Linear Appurtenances Section Areas									
Tower Section	Tower Elevation	Face	$A_R$	$A_F$	C <sub>A</sub> A <sub>A</sub> In Face	$C_{A}A_{A}$ Out Face	Weight		
	ft		$ft^2$	ft <sup>2</sup>	$ft^2$	$ft^2$	lb		
L1	180.00-142.25	A	0.000	0.000	0.000	24.436	405.44		
		В	0.000	0.000	0.000	11.907	47.77		
		C	0.000	0.000	0.000	0.000	0.00		
L2	142.25-93.58	A	0.000	0.000	0.000	72.859	1195.82		
		В	0.000	0.000	0.000	182.786	1453.87		
		C	0.000	0.000	0.000	1.093	781.13		
L3	93.58-46.50	A	0.000	0.000	0.000	70.479	1156.76		
		В	0.000	0.000	0.000	195.682	1638.03		
		C	0.000	0.000	0.000	1.375	904.27		
L4	46.50-1.00	A	0.000	0.000	0.000	68.114	1117.93		
		В	0.000	0.000	0.000	197.448	1597.05		
		C	0.000	0.000	0.000	1.329	873.92		

Tower	Tower	Face	Ice Thickness	$A_R$	$A_F$	$C_A A_A$	$C_A A_A$	Weight
Section	Elevation	or	in			In Face	Out Face	
	ft	Leg		$ft^2$	ft <sup>2</sup>	$ft^2$	ft <sup>2</sup>	lb
L1	180.00-142.25	A	0.500	0.000	0.000	0.000	38.435	596.83
		В		0.000	0.000	0.000	21.431	149.59
		C		0.000	0.000	0.000	0.000	0.00
L2	142.25-93.58	A	0.500	0.000	0.000	0.000	111.793	1757.96
		В		0.000	0.000	0.000	280.481	2864.74
		C		0.000	0.000	0.000	4.835	799.23
L3	93.58-46.50	A	0.500	0.000	0.000	0.000	108.141	1700.53
		В		0.000	0.000	0.000	301.504	3152.18
		C		0.000	0.000	0.000	6.083	927.04
L4	46.50-1.00	A	0.500	0.000	0.000	0.000	104.512	1643.46
		В		0.000	0.000	0.000	320.293	3174.13
		C		0.000	0.000	0.000	5.879	895.93

Feed Line Center of Pressure									
Section	Elevation	$CP_X$	$CP_Z$	$CP_X$	$CP_Z$				
				Ice	Ice				
	ft	in	in	in	in				
L1	180.00-142.25	0.2989	-0.5624	0.4434	-0.6941				
L2	142.25-93.58	1.8822	0.2401	2.1186	0.2876				
L3	93.58-46.50	2.3058	0.3848	2.6493	0.4740				
L4	46.50-1.00	2.6470	0.4874	3.1880	0.6858				

## **Discrete Tower Loads**

## Ramaker & Associates 1120 Dallas St.

Job		Page
	Wethersfield Colo (CT58XC967)	5 of 22
Project		Date
	28752	09:31:24 08/05/14
Client	Sprint	Designed by JDS

Description	Face or	Offset Type	Offsets: Horz	Azimuth Adjustment	Placement		$C_A A_A$ Front	$C_AA_A$ Side	Weight
	Leg		Lateral						
			Vert	0	ft		$ft^2$	ft <sup>2</sup>	lb
			ft ft ft		Ji		jί	Ji	ib
4' T-Arm	A	From Face	2.00	0.0000	181.00	No Ice	2.67	2.67	150.00
(Town)			0.00			1/2" Ice	3.00	3.00	200.00
4' T-Arm	В	From Face	2.00	0.0000	181.00	No Ice	2.67	2.67	150.00
(Town)			0.00 0.00			1/2" Ice	3.00	3.00	200.00
4' T-Arm	C	From Face	2.00	0.0000	181.00	No Ice	2.67	2.67	150.00
(Town)			0.00			1/2" Ice	3.00	3.00	200.00
(2) 6! v 2" Dina Maunt	A	From Face	0.00	0.0000	191.00	No Ioo	1 42	1.42	21.00
(3) 6' x 2" Pipe Mount (Town)	A	From Face	2.00 0.00	0.0000	181.00	No Ice 1/2" Ice	1.43 1.92	1.43 1.92	21.90 32.73
			0.00						
(3) 6' x 2" Pipe Mount	В	From Face	2.00	0.0000	181.00	No Ice	1.43	1.43	21.90
(Town)			0.00 0.00			1/2" Ice	1.92	1.92	32.73
(3) 6' x 2" Pipe Mount	C	From Face	2.00	0.0000	181.00	No Ice	1.43	1.43	21.90
(Town)	C	1 Tom 1 ucc	0.00 0.00	0.0000	101.00	1/2" Ice	1.92	1.92	32.73
20' Omni	В	From Face	2.00	0.0000	181.00	No Ice	5.00	5.00	55.00
(Town)	Б	rioni race	0.00	0.0000	161.00	1/2" Ice	7.03	7.03	91.96
101.0		Б Б	10.00	0.0000	101.00		2.50	2.50	20.00
10' Omni	A	From Face	2.00	0.0000	181.00	No Ice	2.50	2.50	30.00
(Town)			0.00 5.00			1/2" Ice	3.53	3.53	48.64
8' Dipole	C	From Face	2.00	0.0000	181.00	No Ice	4.80	4.80	45.00
(Town)			0.00 6.00			1/2" Ice	6.40	6.40	89.00
SC473-HF1LDF (4.875' Omni)	A	From Face	2.00	0.0000	181.00	No Ice	1.44	1.44	17.00
(Town)	71	1 Tom 1 acc	2.00 3.00	0.0000	101.00	1/2" Ice	1.74	1.74	29.43
SC473-HF1LDF (4.875' Omni)	В	From Face	2.00	0.0000	181.00	No Ice	1.44	1.44	17.00
(Town)	Ь	110m race	2.00 2.00 3.00	0.0000	181.00	1/2" Ice	1.74	1.74	29.43
DS4C03F36U-D (8' Omni)	C	From Face	2.00	0.0000	181.00	No Ice	2.56	2.56	20.00
(Town)	C	Trom Tucc	2.00 4.00	0.0000	101.00	1/2" Ice	3.28	3.28	38.53
Dual Diversity TTA	A	From Face	1.00	0.0000	181.00	No Ice	1.63	0.95	25.00
432-83H-01-T (Town) *****		1101 400	0.00 0.00	0.0000	101.00	1/2" Ice	1.81	1.09	37.44
12' T-Arm	Α	From Face	3.00	0.0000	174.00	No Ice	8.00	8.00	250.00
(Sprint)	71	Trom ruce	0.00 0.00	0.0000	171.00	1/2" Ice	10.67	10.67	400.00
12' T-Arm	В	From Face	3.00	0.0000	174.00	No Ice	8.00	8.00	250.00
(Sprint)	٥	1101 400	0.00 0.00	0.000	17 7.00	1/2" Ice	10.67	10.67	400.00
12' T-Arm	C	From Face	3.00	0.0000	174.00	No Ice	8.00	8.00	250.00
(Sprint)	C	i ioni i acc	0.00	0.0000	174.00	1/2" Ice	10.67	10.67	400.00
MO LOVI DD DD AL AR		Е Е	0.00	0.0000	174.00	NI. T	0.22	4.60	01.02
240-16XLPP-RR w/Mount Pipe (Sprint)	A	From Face	3.00 0.00	0.0000	174.00	No Ice 1/2" Ice	9.32 9.80	4.68 5.31	81.03 142.30
			1.50					_	
APXVSPP18-C w/Mount Pipe (Sprint)	В	From Face	3.00 0.00	0.0000	174.00	No Ice 1/2" Ice	8.26 8.81	6.71 7.66	78.90 144.31
			1.50						
APXVSPP18-C w/Mount Pipe	C	From Face	3.00	0.0000	174.00	No Ice	8.26	6.71	78.90

#### Ramaker & Associates

Job		Page
	Wethersfield Colo (CT58XC967)	6 of 22
Project		Date
	28752	09:31:24 08/05/14
Client		Designed by
	Sprint	JDS

Description	Face or Leg	Offset Type	Offsets: Horz Lateral	Azimuth Adjustment	Placement		C <sub>A</sub> A <sub>A</sub> Front	$C_AA_A$ Side	Weight
	Lig		Vert ft ft ft	0	ft		ft²	ft²	lb
			1.50						
*** APXV9TM14-ALU-120 w/ 3.5"	A	From Face	3.00	0.0000	174.00	No Ice	8.20	6.75	128.00
mount pipe (Sprint)	А	1 Tom Pace	-6.00 1.50	0.0000	174.00	1/2" Ice	8.85	7.59	201.91
(Sprint) APXV9TM14-ALU-120 w/ 3.5"	В	From Face	3.00	0.0000	174.00	No Ice	8.20	6.75	128.00
mount pipe			-6.00			1/2" Ice	8.85	7.59	201.91
(Sprint)	~		1.50		454.00		0.00		420.00
APXV9TM14-ALU-120 w/ 3.5"	С	From Face	3.00	0.0000	174.00	No Ice	8.20	6.75	128.00
mount pipe (Sprint)			-6.00 1.50			1/2" Ice	8.85	7.59	201.91
TD-RRH 8x20	A	From Face	1.50	0.0000	174.00	No Ice	4.32	1.41	66.13
(Sprint)			0.00			1/2" Ice	4.60	1.61	90.06
			0.00						
TD-RRH 8x20	В	From Face	1.50	0.0000	174.00	No Ice	4.32	1.41	66.13
(Sprint)			0.00			1/2" Ice	4.60	1.61	90.06
TD-RRH 8x20	C	From Face	1.50	0.0000	174.00	No Ice	4.32	1.41	66.13
(Sprint)			0.00			1/2" Ice	4.60	1.61	90.06
			0.00						
***		E E	1.00	0.0000	170.00	NI. I	£ 00	5.00	270.00
Tri-Antenna Mount (Sprint)	Α	From Face	1.00 0.00	0.0000	170.00	No Ice 1/2" Ice	5.00 6.00	5.00 6.00	270.00 290.00
(Зріші)			0.00			1/2 100	0.00	0.00	290.00
Tri-Antenna Mount	В	From Face	1.00	0.0000	170.00	No Ice	5.00	5.00	270.00
(Sprint)			0.00			1/2" Ice	6.00	6.00	290.00
T. A	C	г г	0.00	0.0000	170.00	NI I	5.00	5.00	270.00
Tri-Antenna Mount (Sprint)	С	From Face	1.00 0.00	0.0000	170.00	No Ice 1/2" Ice	5.00 6.00	5.00 6.00	270.00 290.00
(Зріші)			0.00			1/2 100	0.00	0.00	290.00
1900MHz 4x40W RRH	A	From Face	1.50	0.0000	170.00	No Ice	2.71	2.61	60.00
(Sprint)			-1.00			1/2" Ice	2.95	2.84	83.12
1000MH - 440W/ DDH	D	E E	0.00	0.0000	170.00	NI. I	2.71	2.61	co.oo
1900MHz 4x40W RRH (Sprint)	В	From Face	1.50 -1.00	0.0000	170.00	No Ice 1/2" Ice	2.71 2.95	2.61 2.84	60.00 83.12
(Зріші)			0.00			1/2 100	2.75	2.04	05.12
1900MHz 4x40W RRH	C	From Face	1.50	0.0000	170.00	No Ice	2.71	2.61	60.00
(Sprint)			-1.00			1/2" Ice	2.95	2.84	83.12
200MH 2 50W DDH		г г	0.00	0.0000	170.00	NI I	2.40	2.25	64.00
800MHz 2x50W RRH (Sprint)	Α	From Face	1.50 1.00	0.0000	170.00	No Ice 1/2" Ice	2.40 2.61	2.25 2.46	64.00 86.12
(бринг)			0.00			1/2 100	2.01	2.40	00.12
800MHz 2x50W RRH	В	From Face	1.50	0.0000	170.00	No Ice	2.40	2.25	64.00
(Sprint)			1.00			1/2" Ice	2.61	2.46	86.12
900MH- 2-50W DDH	C	E E	0.00	0.0000	170.00	NI. I	2.40	2.25	C4.00
800MHz 2x50W RRH (Sprint)	C	From Face	1.50 1.00	0.0000	170.00	No Ice 1/2" Ice	2.40 2.61	2.25 2.46	64.00 86.12
(Бринг)			0.00			1/2 100	2.01	2.10	00.12
*****									
12' T-Arm	A	From Face	3.00	0.0000	152.00	No Ice	8.00	8.00	250.00
(T-Mobile)			0.00			1/2" Ice	10.67	10.67	400.00
12' T-Arm	В	From Face	0.00 3.00	0.0000	152.00	No Ice	8.00	8.00	250.00
(T-Mobile)	5	1101111 400	0.00	0.0000	132.00	1/2" Ice	10.67	10.67	400.00
,			0.00						
12' T-Arm	C	From Face	3.00	0.0000	152.00	No Ice	8.00	8.00	250.00
(T-Mobile)			0.00			1/2" Ice	10.67	10.67	400.00

## Ramaker & Associates 1120 Dallas St.

Job		Page
	Wethersfield Colo (CT58XC967)	7 of 22
Project		Date
	28752	09:31:24 08/05/14
Client	Sprint	Designed by JDS

Description	Face or	Offset Type	Offsets: Horz Lateral	Azimuth Adjustment	Placement		$C_A A_A$ Front	$C_AA_A$ Side	Weight
	Leg		Vert ft ft	0	ft		ft²	ft²	lb
			ft						
(2) AIR B2A/B4P w/ Mount Pipe (T-Mobile)	A	From Face	0.00 3.00 0.00	0.0000	152.00	No Ice 1/2" Ice	7.23 8.02	6.12 7.36	112.20 174.30
(2) AIR B2A/B4P w/ Mount Pipe (T-Mobile)	В	From Face	1.00 3.00 0.00 1.00	0.0000	152.00	No Ice 1/2" Ice	7.23 8.02	6.12 7.36	112.20 174.30
(2) AIR B2A/B4P w/ Mount Pipe (T-Mobile)	С	From Face	3.00 0.00 1.00	0.0000	152.00	No Ice 1/2" Ice	7.23 8.02	6.12 7.36	112.20 174.30
TMA 4"x8"x4" (T-Mobile)	A	From Face	3.00 -6.00 0.00	0.0000	152.00	No Ice 1/2" Ice	0.31 0.39	0.16 0.21	5.00 8.14
TMA 4"x8"x4" (T-Mobile)	В	From Face	3.00 -6.00 0.00	0.0000	152.00	No Ice 1/2" Ice	0.31 0.39	0.16 0.21	5.00 8.14
TMA 4"x8"x4" (T-Mobile)	С	From Face	3.00 -6.00 0.00	0.0000	152.00	No Ice 1/2" Ice	0.31 0.39	0.16 0.21	5.00 8.14
*****			0.00						
14' T-Arm (ATT)	A	From Face	3.00 0.00 0.00	0.0000	141.00	No Ice 1/2" Ice	9.33 11.33	9.33 11.33	275.00 450.00
14' T-Arm (ATT)	В	From Face	3.00 0.00 0.00	0.0000	141.00	No Ice 1/2" Ice	9.33 11.33	9.33 11.33	275.00 450.00
14' T-Arm (ATT)	С	From Face	3.00 0.00 0.00	0.0000	141.00	No Ice 1/2" Ice	9.33 11.33	9.33 11.33	275.00 450.00
(2) 7770 w/ mount pipe (ATT)	A	From Face	3.00 0.00 0.00	0.0000	141.00	No Ice 1/2" Ice	6.86 7.65	5.23 6.41	81.32 138.82
(2) 7770 w/ mount pipe (ATT)	В	From Face	3.00 0.00 0.00	0.0000	141.00	No Ice 1/2" Ice	6.86 7.65	5.23 6.41	81.32 138.82
(2) 7770 w/ mount pipe (ATT)	С	From Face	3.00 0.00 0.00	0.0000	141.00	No Ice 1/2" Ice	6.86 7.65	5.23 6.41	81.32 138.82
SBNH-1D6565C w/Mount Pipe (ATT)	A	From Face	3.00 0.00 0.00	0.0000	141.00	No Ice 1/2" Ice	11.41 12.03	10.00 11.42	107.17 197.75
P65-15-XLH-RR w/Mount Pipe (ATT)	В	From Face	3.00 0.00 0.00	0.0000	141.00	No Ice 1/2" Ice	5.95 6.36	3.95 4.52	54.60 99.63
AM-X-CD-16-65-00T w/Mount Pipe (ATT)	С	From Face	3.00 0.00 0.00	0.0000	141.00	No Ice 1/2" Ice	6.62 7.05	5.16 5.83	49.43 102.89
(2) TMA 8"x8"x3" (ATT)	A	From Face	3.00 0.00 1.00	0.0000	141.00	No Ice 1/2" Ice	0.62 0.73	0.23 0.31	8.00 12.28
(2) TMA 8"x8"x3" (ATT)	A	From Face	3.00 0.00 1.00	0.0000	141.00	No Ice 1/2" Ice	0.62 0.73	0.23 0.31	8.00 12.28
(2) TMA 8"x8"x3" (ATT)	В	From Face	3.00 0.00 1.00	0.0000	141.00	No Ice 1/2" Ice	0.62 0.73	0.23 0.31	8.00 12.28
(2) TMA 8"x8"x3"	В	From Face	3.00	0.0000	141.00	No Ice	0.62	0.23	8.00

## Ramaker & Associates 1120 Dallas St.

Job		Page
	Wethersfield Colo (CT58XC967)	8 of 22
Project		Date
	28752	09:31:24 08/05/14
Client	Sprint	Designed by JDS

Description	Face or	Offset Type	Offsets: Horz Lateral	Azimuth Adjustment	Placement		$C_A A_A$ Front	$C_AA_A$ Side	Weight
	Leg		Laierai Vert						
			ft ft	0	ft		ft <sup>2</sup>	ft <sup>2</sup>	lb
(ATT)			0.00			1/2" Ice	0.73	0.31	12.28
(2) TEN (A OIL OIL 2II		F F	1.00	0.0000	141.00	NI I	0.62	0.22	0.00
(2) TMA 8"x8"x3" (ATT)	С	From Face	3.00 0.00 1.00	0.0000	141.00	No Ice 1/2" Ice	0.62 0.73	0.23 0.31	8.00 12.28
(2) TMA 8"x8"x3"	C	From Face	3.00	0.0000	141.00	No Ice	0.62	0.23	8.00
(ATT)			0.00 1.00			1/2" Ice	0.73	0.31	12.28
RRUS-11	A	From Face	1.00	0.0000	143.00	No Ice	2.94	1.25	55.00
(ATT)			1.00 0.00			1/2" Ice	3.17	1.41	74.32
RRUS-11	В	From Face	1.00	0.0000	143.00	No Ice	2.94	1.25	55.00
(ATT)			1.00 0.00			1/2" Ice	3.17	1.41	74.32
RRUS-11	C	From Face	1.00	0.0000	143.00	No Ice	2.94	1.25	55.00
(ATT)			1.00 0.00			1/2" Ice	3.17	1.41	74.32
RRUS-11	A	From Face	1.00	0.0000	143.00	No Ice	2.94	1.25	55.00
(ATT)			0.00 0.00			1/2" Ice	3.17	1.41	74.32
RRUS-11	В	From Face	1.00	0.0000	143.00	No Ice	2.94	1.25	55.00
(ATT)			0.00 0.00			1/2" Ice	3.17	1.41	74.32
RRUS-11	C	From Face	1.00	0.0000	143.00	No Ice	2.94	1.25	55.00
(ATT)			0.00			1/2" Ice	3.17	1.41	74.32
DC6-48-60-18-8F (ATT)	С	From Face	1.50 0.00 1.00	0.0000	141.00	No Ice 1/2" Ice	1.47 1.67	1.47 1.67	33.00 50.72
****			1.00						
Andrew 14'6" Low-Profile Platform	С	None		0.0000	131.00	No Ice 1/2" Ice	10.20 13.10	10.20 13.10	1235.0 1500.0
(Verizon)	<b>A</b>	From Face	3.00	0.0000	131.00	No Ice	4.98	4.74	112.00
RYMSA MGD3-900TX w/Mount Pipe (Verizon)	A	riom race	3.00 3.00 1.50	0.0000	131.00	1/2" Ice	5.43	5.68	113.90 156.47
RYMSA MGD3-900TX	В	From Face	3.00	0.0000	131.00	No Ice	4.98	4.74	113.90
w/Mount Pipe (Verizon)			3.00 1.50			1/2" Ice	5.43	5.68	156.47
RYMSA MGD3-900TX	C	From Face	3.00	0.0000	131.00	No Ice	4.98	4.74	113.90
w/Mount Pipe			3.00			1/2" Ice	5.43	5.68	156.47
(Verizon) 3XA-171063-12CF-EDIN-2 w/	Α	From Face	1.50 3.00	0.0000	131.00	No Ice	5.26	5.53	42.00
Mount Pipe (Verizon)	11	Trom ruce	-7.00 1.50	0.0000	131.00	1/2" Ice	5.92	6.79	90.59
3XA-171063-12CF-EDIN-2 w/	В	From Face	3.00	0.0000	131.00	No Ice	5.26	5.53	42.00
Mount Pipe (Verizon)			-7.00 1.50			1/2" Ice	5.92	6.79	90.59
3XA-171063-12CF-EDIN-2 w/ Mount Pipe	C	From Face	3.00 -7.00	0.0000	131.00	No Ice 1/2" Ice	5.26 5.92	5.53 6.79	42.00 90.59
(Verizon)			1.50						
BXA-70063-4CF-EDIN-X	Α	From Face	3.00	0.0000	131.00	No Ice	5.41	3.70	28.15
w/Mount Pipe (Verizon)	Б	E E	7.00 1.75	0.0000	121.00	1/2" Ice	5.86	4.32	70.61
BXA-70063-4CF-EDIN-X w/Mount Pipe	В	From Face	3.00 7.00	0.0000	131.00	No Ice 1/2" Ice	5.41 5.86	3.70 4.32	28.15 70.61
(Verizon)			1.75			1,2 100	2.00	1.32	70.01

Ramaker & Associates
1120 Dallas St.

Job		Page
	Wethersfield Colo (CT58XC967)	9 of 22
Project		Date
	28752	09:31:24 08/05/14
Client	Sprint	Designed by JDS

Description	Face or Leg	Offset Type	Offsets: Horz Lateral	Azimuth Adjustment	Placement		$C_AA_A$ Front	$C_AA_A$ Side	Weight
			Vert ft ft ft	٥	ft		ft <sup>2</sup>	ft <sup>2</sup>	lb
BXA-70063-4CF-EDIN-X	С	From Face	3.00	0.0000	131.00	No Ice	5.41	3.70	28.15
w/Mount Pipe			7.00			1/2" Ice	5.86	4.32	70.61
(Verizon)			1.75						
BXA-70063-6CF-EDIN-X	A	From Face	3.00	0.0000	131.00	No Ice	7.99	5.82	42.55
w/Mount Pipe			-1.00			1/2" Ice	8.64	6.99	103.53
(Verizon)			1.75						
BXA-70063-6CF-EDIN-X	В	From Face	3.00	0.0000	131.00	No Ice	7.99	5.82	42.55
w/Mount Pipe			-1.00			1/2" Ice	8.64	6.99	103.53
(Verizon)			1.75	0.0000	121.00		<b>7</b> .00		10.55
BXA-70063-6CF-EDIN-X	C	From Face	3.00	0.0000	131.00	No Ice	7.99	5.82	42.55
w/Mount Pipe			-1.00			1/2" Ice	8.64	6.99	103.53
(Verizon) RRUS-12	A	From Face	1.75 3.00	0.0000	131.00	No Ice	3.69	1.47	57.90
(Verizon)	Α	rioiii race	7.00	0.0000	131.00	1/2" Ice	3.95	1.47	81.09
(Verizon)			1.00			1/2 100	3.93	1.03	61.09
RRUS-12	В	From Face	3.00	0.0000	131.00	No Ice	3.69	1.47	57.90
(Verizon)	ь	1 Tom 1 acc	7.00	0.0000	131.00	1/2" Ice	3.95	1.65	81.09
(Verizon)			1.00			1/2 100	3.73	1.05	01.07
RRUS-12	C	From Face	3.00	0.0000	131.00	No Ice	3.69	1.47	57.90
(Verizon)	Ü	11011111100	7.00	0.0000	151.00	1/2" Ice	3.95	1.65	81.09
			1.00						
*****									
APXV18-206517-C w/Mount	A	From Face	1.00	0.0000	124.00	No Ice	5.17	4.46	48.30
Pipe			0.00			1/2" Ice	5.62	5.39	90.79
(Metro PCS)			0.00						
APXV18-206517-C w/Mount	В	From Face	1.00	0.0000	124.00	No Ice	5.17	4.46	48.30
Pipe			0.00			1/2" Ice	5.62	5.39	90.79
(Metro PCS)			0.00						
APXV18-206517-C w/Mount	C	From Face	1.00	0.0000	124.00	No Ice	5.17	4.46	48.30
Pipe			0.00			1/2" Ice	5.62	5.39	90.79
(Metro PCS) *****			0.00						
GPS	A	None		0.0000	51.00	No Ice	1.00	1.00	10.00
(Town)	А	TOHC		0.0000	31.00	1/2" Ice	1.50	1.50	15.00
(2) GPS	В	None		0.0000	51.00	No Ice	1.00	1.00	10.00
(Town)		1.5110		0.0000	21.00	1/2" Ice	1.50	1.50	15.00
(2) GPS	C	None		0.0000	51.00	No Ice	1.00	1.00	10.00
(Town)	-					1/2" Ice	1.50	1.50	15.00

	Dishes										
Description	Face or Leg	Dish Type	Offset Type	Offsets: Horz Lateral Vert	Azimuth Adjustment	3 dB Beam Width	Elevation	Outside Diameter		Aperture Area	Weight
				ft	۰	0	ft	ft		$ft^2$	lb
2' HP Dish	С	Paraboloid	From	1.50	0.0000		164.00	2.00	No Ice	3.14	25.00
(Town)		w/Shroud (HP)	Face	0.00					1/2" Ice	3.41	43.00
1' Dish w/o radome (Town)	C	Paraboloid w/o Radome	From Face	1.50 -1.00	0.0000		163.00	1.00	No Ice 1/2" Ice	0.79 0.92	15.00 19.72

# Ramaker & Associates

1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999

Job		Page
	Wethersfield Colo (CT58XC967)	10 of 22
Project		Date
	28752	09:31:24 08/05/14
Client		Designed by
	Sprint	JDS

Description	Face or Leg	Dish Type	Offset Type	Offsets: Horz Lateral	Azimuth Adjustment	3 dB Beam Width	Elevation	Outside Diameter		Aperture Area	Weight
****				Vert ft 0.00	0	٥	ft	ft		ft <sup>2</sup>	lb
2' HP Dish (Dish)	A	Paraboloid w/Shroud (HP)	From Face	1.50 0.00 0.00	0.0000		147.00	2.00	No Ice 1/2" Ice	3.14 3.41	25.00 43.00

# **Tower Pressures - No Ice**

 $G_H=1.690$ 

Section	z	$K_Z$	$q_z$	$A_G$	F	$A_F$	$A_R$	$A_{leg}$	Leg	$C_AA_A$	$C_A A_A$
Elevation					а				%	In	Out
					c					Face	Face
ft	ft		psf	$ft^2$	e	$ft^2$	$ft^2$	$ft^2$		$ft^2$	$ft^2$
L1 180.00-142.25	160.15	1.57	26	88.632	A	0.000	88.632	88.632	100.00	0.000	24.436
					В	0.000	88.632		100.00	0.000	11.907
					C	0.000	88.632		100.00	0.000	0.000
L2 142.25-93.58	116.92	1.435	23	159.358	Α	0.000	159.358	159.358	100.00	0.000	72.859
					В	0.000	159.358		100.00	0.000	182.786
					C	0.000	159.358		100.00	0.000	1.093
L3 93.58-46.50	69.64	1.238	20	201.709	Α	0.000	201.709	201.709	100.00	0.000	70.479
					В	0.000	201.709		100.00	0.000	195.682
					C	0.000	201.709		100.00	0.000	1.375
L4 46.50-1.00	23.11	1	17	239.286	Α	0.000	239.286	239.286	100.00	0.000	68.114
					В	0.000	239.286		100.00	0.000	197.448
					C	0.000	239.286		100.00	0.000	1.329

# **Tower Pressure - With Ice**

 $G_H = 1.690$ 

Section	Z	$K_Z$	$q_z$	$t_Z$	$A_G$	F	$A_F$	$A_R$	$A_{leg}$	Leg	$C_A A_A$	$C_A A_A$
Elevation						a				%	In	Out
						c					Face	Face
ft	ft		psf	in	$ft^2$	e	ft <sup>2</sup>	$ft^2$	$ft^2$		$ft^2$	$ft^2$
L1 180.00-142.25	160.15	1.57	19	0.5000	91.778	A	0.000	91.778	91.778	100.00	0.000	38.435
						В	0.000	91.778		100.00	0.000	21.431
						C	0.000	91.778		100.00	0.000	0.000
L2 142.25-93.58	116.92	1.435	18	0.5000	163.413	Α	0.000	163.413	163.413	100.00	0.000	111.793
						В	0.000	163.413		100.00	0.000	280.481
						C	0.000	163.413		100.00	0.000	4.835
L3 93.58-46.50	69.64	1.238	15	0.5000	205.632	Α	0.000	205.632	205.632	100.00	0.000	108.141
						В	0.000	205.632		100.00	0.000	301.504
						C	0.000	205.632		100.00	0.000	6.083
L4 46.50-1.00	23.11	1	12	0.5000	243.078	A	0.000	243.078	243.078	100.00	0.000	104.512
						В	0.000	243.078		100.00	0.000	320.293
						C	0.000	243.078		100.00	0.000	5.879

Ramaker & Associates
1120 Dallas St.

Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999

Job		Page
	Wethersfield Colo (CT58XC967)	11 of 22
Project		Date
	28752	09:31:24 08/05/14
Client		Designed by
	Sprint	JDS

# **Tower Pressure - Service**

 $G_H=1.690$ 

Section	z	$K_Z$	$q_z$	$A_G$	F	$A_F$	$A_R$	$A_{leg}$	Leg	$C_A A_A$	$C_A A_A$
Elevation					a				%	In	Out
					c					Face	Face
ft	ft		psf	ft <sup>2</sup>	e	ft <sup>2</sup>	ft <sup>2</sup>	$ft^2$		$ft^2$	$ft^2$
L1 180.00-142.25	160.15	1.57	14	88.632	A	0.000	88.632	88.632	100.00	0.000	24.436
					В	0.000	88.632		100.00	0.000	11.907
					C	0.000	88.632		100.00	0.000	0.000
L2 142.25-93.58	116.92	1.435	13	159.358	A	0.000	159.358	159.358	100.00	0.000	72.859
					В	0.000	159.358		100.00	0.000	182.786
					C	0.000	159.358		100.00	0.000	1.093
L3 93.58-46.50	69.64	1.238	11	201.709	A	0.000	201.709	201.709	100.00	0.000	70.479
					В	0.000	201.709		100.00	0.000	195.682
					C	0.000	201.709		100.00	0.000	1.375
L4 46.50-1.00	23.11	1	9	239.286	A	0.000	239.286	239.286	100.00	0.000	68.114
					В	0.000	239.286		100.00	0.000	197.448
					C	0.000	239.286		100.00	0.000	1.329

# **Tower Forces - No Ice - Wind Normal To Face**

Section	Add	Self	F	e	$C_F$	$R_R$	$D_F$	$D_R$	$A_E$	F	W	Ctrl.
Elevation	Weight	Weight	а									Face
			c						_			
ft	lb	lb	e						$ft^2$	lb	plf	
L1	453.21	2846.33	A	1	0.65	1	1	1	88.632	4082.71	108.15	C
180.00-142.25			В	1	0.65	1	1	1	88.632			
			C	1	0.65	1	1	1	88.632			
L2 142.25-93.58	3430.82	8270.21	Α	1	0.973	1	1	1	159.358	16334.81	335.62	C
			В	1	0.973	1	1	1	159.358			
			C	1	0.973	1	1	1	159.358			
L3 93.58-46.50	3699.05	10839.22	Α	1	0.998	1	1	1	201.709	15987.02	339.57	C
			В	1	0.998	1	1	1	201.709			
			C	1	0.998	1	1	1	201.709			
L4 46.50-1.00	3588.90	13316.68	Α	1	1.013	1	1	1	239.286	14214.56	312.41	C
			В	1	1.013	1	1	1	239.286			
			C	1	1.013	1	1	1	239.286			
Sum Weight:	11171.98	35272.44						OTM	3954981.37	50619.10		
									lb-ft			

# **Tower Forces - No Ice - Wind 60 To Face**

Section	Add	Self	F	e	$C_F$	$R_R$	$D_F$	$D_R$	$A_E$	F	w	Ctrl.
Elevation	Weight	Weight	a									Face
			c									
ft	lb	lb	e						ft <sup>2</sup>	lb	plf	
L1	453.21	2846.33	A	1	0.65	1	1	1	88.632	4082.71	108.15	С
180.00-142.25			В	1	0.65	1	1	1	88.632			
			C	1	0.65	1	1	1	88.632			
L2 142.25-93.58	3430.82	8270.21	Α	1	0.973	1	1	1	159.358	16334.81	335.62	C
			В	1	0.973	1	1	1	159.358			
			C	1	0.973	1	1	1	159.358			
L3 93.58-46.50	3699.05	10839.22	Α	1	0.998	1	1	1	201.709	15987.02	339.57	C

Ramaker & Associates

1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999

Job		Page
	Wethersfield Colo (CT58XC967)	12 of 22
Project		Date
	28752	09:31:24 08/05/14
Client	0	Designed by
	Sprint	JDS

Section	Add	Self	F	e	$C_F$	$R_R$	$D_F$	$D_R$	$A_E$	F	w	Ctrl.
Elevation	Weight	Weight	a									Face
			c						_			
ft	lb	lb	e						$ft^2$	lb	plf	
			В	1	0.998	1	1	1	201.709			
			C	1	0.998	1	1	1	201.709			
L4 46.50-1.00	3588.90	13316.68	Α	1	1.013	1	1	1	239.286	14214.56	312.41	C
			В	1	1.013	1	1	1	239.286			
			C	1	1.013	1	1	1	239.286			
Sum Weight:	11171.98	35272.44						OTM	3954981.37	50619.10		
									lb-ft			

# **Tower Forces - No Ice - Wind 90 To Face**

Section	Add	Self	F	e	$C_F$	$R_R$	$D_F$	$D_R$	$A_E$	F	W	Ctrl.
Elevation	Weight	Weight	a									Face
			c									
ft	lb	lb	e						ft <sup>2</sup>	lb	plf	
L1	453.21	2846.33	A	1	0.65	1	1	1	88.632	4082.71	108.15	C
180.00-142.25			В	1	0.65	1	1	1	88.632			
			C	1	0.65	1	1	1	88.632			
L2 142.25-93.58	3430.82	8270.21	A	1	0.973	1	1	1	159.358	16334.81	335.62	C
			В	1	0.973	1	1	1	159.358			
			C	1	0.973	1	1	1	159.358			
L3 93.58-46.50	3699.05	10839.22	Α	1	0.998	1	1	1	201.709	15987.02	339.57	C
			В	1	0.998	1	1	1	201.709			
			C	1	0.998	1	1	1	201.709			
L4 46.50-1.00	3588.90	13316.68	A	1	1.013	1	1	1	239.286	14214.56	312.41	C
			В	1	1.013	1	1	1	239.286			
			C	1	1.013	1	1	1	239.286			
Sum Weight:	11171.98	35272.44						OTM	3954981.37	50619.10		
									lb-ft			

# Tower Forces - With Ice - Wind Normal To Face

Section	Add	Self	F	e	$C_F$	$R_R$	$D_F$	$D_R$	$A_E$	F	w	Ctrl.
Elevation	Weight	Weight	а									Face
			С						_			
ft	lb	lb	e						$ft^2$	lb	plf	
L1	746.42	3514.39	Α	1	0.65	1	1	1	91.778	3895.34	103.19	C
180.00-142.25			В	1	0.65	1	1	1	91.778			
			C	1	0.65	1	1	1	91.778			
L2 142.25-93.58	5421.93	9471.46	Α	1	0.973	1	1	1	163.413	16544.49	339.93	C
			В	1	0.973	1	1	1	163.413			
			C	1	0.973	1	1	1	163.413			
L3 93.58-46.50	5779.75	12355.21	Α	1	0.998	1	1	1	205.632	15879.81	337.29	C
			В	1	0.998	1	1	1	205.632			
			C	1	0.998	1	1	1	205.632			
L4 46.50-1.00	5713.53	15111.87	Α	1	1.013	1	1	1	243.078	14169.31	311.41	C
			В	1	1.013	1	1	1	243.078			
			C	1	1.013	1	1	1	243.078			
Sum Weight:	17661.63	40452.93						OTM	3941109.26	50488.96		
									lb-ft			

Ramaker & Associates

1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999

Job		Page
	Wethersfield Colo (CT58XC967)	13 of 22
Project		Date
	28752	09:31:24 08/05/14
Client	Cariat	Designed by
	Sprint	JDS

# **Tower Forces - With Ice - Wind 60 To Face**

Section	Add	Self	F	e	$C_F$	$R_R$	$D_F$	$D_R$	$A_E$	F	w	Ctrl.
Elevation	Weight	Weight	а									Face
			C						?			
ft	lb	lb	e						ft <sup>2</sup>	lb	plf	
L1	746.42	3514.39	Α	1	0.65	1	1	1	91.778	3895.34	103.19	C
180.00-142.25			В	1	0.65	1	1	1	91.778			
			C	1	0.65	1	1	1	91.778			
L2 142.25-93.58	5421.93	9471.46	Α	1	0.973	1	1	1	163.413	16544.49	339.93	C
			В	1	0.973	1	1	1	163.413			
			C	1	0.973	1	1	1	163.413			
L3 93.58-46.50	5779.75	12355.21	Α	1	0.998	1	1	1	205.632	15879.81	337.29	C
			В	1	0.998	1	1	1	205.632			
			C	1	0.998	1	1	1	205.632			
L4 46.50-1.00	5713.53	15111.87	A	1	1.013	1	1	1	243.078	14169.31	311.41	C
			В	1	1.013	1	1	1	243.078			
			C	1	1.013	1	1	1	243.078			
Sum Weight:	17661.63	40452.93						OTM	3941109.26	50488.96		
Ü									lb-ft			

# **Tower Forces - With Ice - Wind 90 To Face**

Section	Add	Self	F	e	$C_F$	$R_R$	$D_F$	$D_R$	$A_E$	F	w	Ctrl.
Elevation	Weight	Weight	а									Face
			c						_			
ft	lb	lb	e						$ft^2$	lb	plf	
L1	746.42	3514.39	Α	1	0.65	1	1	1	91.778	3895.34	103.19	C
180.00-142.25			В	1	0.65	1	1	1	91.778			
			C	1	0.65	1	1	1	91.778			
L2 142.25-93.58	5421.93	9471.46	Α	1	0.973	1	1	1	163.413	16544.49	339.93	C
			В	1	0.973	1	1	1	163.413			
			C	1	0.973	1	1	1	163.413			
L3 93.58-46.50	5779.75	12355.21	Α	1	0.998	1	1	1	205.632	15879.81	337.29	C
			В	1	0.998	1	1	1	205.632			
			C	1	0.998	1	1	1	205.632			
L4 46.50-1.00	5713.53	15111.87	Α	1	1.013	1	1	1	243.078	14169.31	311.41	C
			В	1	1.013	1	1	1	243.078			
			C	1	1.013	1	1	1	243.078			
Sum Weight:	17661.63	40452.93						OTM	3941109.26	50488.96		
									lb-ft			

# **Tower Forces - Service - Wind Normal To Face**

Section Elevation	Add Weight	Self Weight	F a	e	$C_F$	$R_R$	$D_F$	$D_R$	$A_E$	F	W	Ctrl. Face
ft	lb	lb	с е						$ft^2$	lb	plf	
L1	453.21	2846.33	A	1	0.65	1	1	1	88.632	2296.52	60.84	С
180.00-142.25			В	1	0.65	1	1	1	88.632			
			C	1	0.65	1	1	1	88.632			
L2 142.25-93.58	3430.82	8270.21	Α	1	0.973	1	1	1	159.358	9188.33	188.79	C
			В	1	0.973	1	1	1	159.358			

Ramaker & Associates

1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999

Job		Page
	Wethersfield Colo (CT58XC967)	14 of 22
Project		Date
	28752	09:31:24 08/05/14
Client		Designed by
	Sprint	JDS

Section	Add	Self	F	e	$C_F$	$R_R$	$D_F$	$D_R$	$A_E$	F	w	Ctrl.
Elevation	Weight	Weight	a									Face
			С									
ft	lb	lb	e						$ft^2$	lb	plf	
			C	1	0.973	1	1	1	159.358			
L3 93.58-46.50	3699.05	10839.22	Α	1	0.998	1	1	1	201.709	8992.70	191.01	C
			В	1	0.998	1	1	1	201.709			
			C	1	0.998	1	1	1	201.709			
L4 46.50-1.00	3588.90	13316.68	Α	1	1.013	1	1	1	239.286	7995.69	175.73	C
			В	1	1.013	1	1	1	239.286			
			C	1	1.013	1	1	1	239.286			
Sum Weight:	11171.98	35272.44						OTM	2224677.02	28473.24		
									lb-ft			

# **Tower Forces - Service - Wind 60 To Face**

Section	Add	Self	F	e	$C_F$	$R_R$	$D_F$	$D_R$	$A_E$	F	w	Ctrl.
Elevation	Weight	Weight	а									Face
			С									
ft	lb	lb	е						$ft^2$	lb	plf	
L1	453.21	2846.33	Α	1	0.65	1	1	1	88.632	2296.52	60.84	C
180.00-142.25			В	1	0.65	1	1	1	88.632			
			C	1	0.65	1	1	1	88.632			
L2 142.25-93.58	3430.82	8270.21	Α	1	0.973	1	1	1	159.358	9188.33	188.79	C
			В	1	0.973	1	1	1	159.358			
			C	1	0.973	1	1	1	159.358			
L3 93.58-46.50	3699.05	10839.22	Α	1	0.998	1	1	1	201.709	8992.70	191.01	C
			В	1	0.998	1	1	1	201.709			
			C	1	0.998	1	1	1	201.709			
L4 46.50-1.00	3588.90	13316.68	Α	1	1.013	1	1	1	239.286	7995.69	175.73	C
			В	1	1.013	1	1	1	239.286			
			C	1	1.013	1	1	1	239.286			
Sum Weight:	11171.98	35272.44						OTM	2224677.02	28473.24		
									lb-ft			

# **Tower Forces - Service - Wind 90 To Face**

Section	Add	Self	F	e	$C_F$	$R_R$	$D_F$	$D_R$	$A_E$	F	w	Ctrl.
Elevation	Weight	Weight	а									Face
			С									
ft	lb	lb	e						$ft^2$	lb	plf	
L1	453.21	2846.33	Α	1	0.65	1	1	1	88.632	2296.52	60.84	C
180.00-142.25			В	1	0.65	1	1	1	88.632			
			C	1	0.65	1	1	1	88.632			
L2 142.25-93.58	3430.82	8270.21	Α	1	0.973	1	1	1	159.358	9188.33	188.79	C
			В	1	0.973	1	1	1	159.358			
			C	1	0.973	1	1	1	159.358			
L3 93.58-46.50	3699.05	10839.22	Α	1	0.998	1	1	1	201.709	8992.70	191.01	C
			В	1	0.998	1	1	1	201.709			
			C	1	0.998	1	1	1	201.709			
L4 46.50-1.00	3588.90	13316.68	Α	1	1.013	1	1	1	239.286	7995.69	175.73	C
			В	1	1.013	1	1	1	239.286			
			C	1	1.013	1	1	1	239.286			
Sum Weight:	11171.98	35272.44						OTM	2224677.02	28473.24		
									lb-ft			

# Ramaker & Associates

1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999

Job		Page
	Wethersfield Colo (CT58XC967)	15 of 22
Project		Date
	28752	09:31:24 08/05/14
Client	Sprint	Designed by
	Орин	JDS

# **Force Totals**

Load	Vertical	Sum of	Sum of	Sum of Overturning	Sum of Overturning	Sum of Torques
Case	Forces	Forces	Forces	Moments, $M_x$	Moments, $M_z$	
		X	Z	lb-ft	lb-ft	
	lb	lb	lb	Ť	, and the second	lb-ft
Leg Weight	35272.44					
Bracing Weight	0.00					
Total Member Self-Weight	35272.44			684.69	-5023.56	
Total Weight	55823.46			684.69	-5023.56	
Wind 0 deg - No Ice		-115.24	-68799.99	-6715744.04	14021.87	8207.72
Wind 30 deg - No Ice		34291.14	-59569.59	-5813306.32	-3345263.26	7836.73
Wind 60 deg - No Ice		59544.52	-34349.84	-3349500.59	-5814759.88	5543.03
Wind 90 deg - No Ice		68823.08	131.42	22354.41	-6725096.57	1714.61
Wind 120 deg - No Ice		59636.00	34489.14	3373848.91	-5830620.03	-2656.26
Wind 150 deg - No Ice		34500.74	59598.38	5820074.56	-3379807.51	-6310.61
Wind 180 deg - No Ice		146.96	68756.53	6709919.71	-28701.08	-8247.10
Wind 210 deg - No Ice		-34322.89	59493.15	5802489.48	3339947.81	-7863.58
Wind 240 deg - No Ice		-59539.25	34300.21	3342418.93	5804225.45	-5529.47
Wind 270 deg - No Ice		-68789.88	-90.38	-14470.10	6710202.31	-1707.24
Wind 300 deg - No Ice		-59590.53	-34546.10	-3382001.06	5813650.19	2781.48
Wind 330 deg - No Ice		-34468.83	-59636.58	-5825307.31	3365006.37	6383.23
Member Ice	5180.49					
Total Weight Ice	72215.43			2060.51	-13257.03	
Wind 0 deg - Ice		-85.09	-66620.74	-6391386.54	1003.40	9819.23
Wind 30 deg - Ice		33223.17	-57689.53	-5533399.46	-3195516.55	9413.14
Wind 60 deg - Ice		57658.67	-33278.89	-3189495.29	-5543706.84	6631.69
Wind 90 deg - Ice		66628.12	98.29	18462.27	-6407990.25	2030.23
Wind 120 deg - Ice		57724.85	33374.74	3209771.47	-5555443.71	-3180.18
Wind 150 deg - Ice		33379.56	57702.62	5540408.46	-3221623.23	-7534.88
Wind 180 deg - Ice		110.93	66584.34	6389484.87	-31290.26	-9850.29
Wind 210 deg - Ice		-33249.89	57625.67	5527337.46	3172995.42	-9436.00
Wind 240 deg - Ice		-57654.81	33236.05	3186340.38	5516866.67	-6619.85
Wind 270 deg - Ice		-66601.08	-64.82	-9027.18	6377528.24	-2024.27
Wind 300 deg - Ice		-57687.37	-33423.55	-3213798.29	5523220.34	3286.22
Wind 330 deg - Ice	7.7020.45	-33352.72	-57735.32	-5541922.28	3191098.02	7598.19
Total Weight	55823.46	54.00	20.500.00	684.69	-5023.56	454504
Wind 0 deg - Service		-64.82	-38699.99	-3777975.99	10950.50	4616.84
Wind 30 deg - Service		19288.77	-33507.90	-3270354.77	-1878647.39	4408.16
Wind 60 deg - Service		33493.79	-19321.78	-1884464.05	-3267739.24	3117.96
Wind 90 deg - Service		38712.98	73.92	12204.39	-3779803.63	964.47
Wind 120 deg - Service		33545.25	19400.14	1897420.05	-3276660.57	-1494.15
Wind 150 deg - Service		19406.66	33524.09	3273421.97	-1898078.53	-3549.72
Wind 180 deg - Service		82.67	38675.55	3773959.87	-13081.16	-4638.99
Wind 210 deg - Service		-19306.62	33464.90	3263530.37	1881783.84	-4423.26
Wind 240 deg - Service		-33490.83	19293.87	1879740.68	3267940.01	-3110.33
Wind 270 deg - Service		-38694.31	-50.84	-8509.40	3777552.00	-960.32
Wind 300 deg - Service		-33519.67	-19432.18	-1902745.56	3273241.42	1564.58
Wind 330 deg - Service		-19388.72	-33545.58	-3277105.33	1895879.28	3590.56

# **Load Combinations**

Comb.	Description	
No.		

# Ramaker & Associates 1120 Dallas St.

1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999

Job		Page
	Wethersfield Colo (CT58XC967)	16 of 22
Project		Date
	28752	09:31:24 08/05/14
Client	Sprint	Designed by JDS

Comb.		Description
No.		
2	Dead+Wind 0 deg - No Ice	
3	Dead+Wind 30 deg - No Ice	
4	Dead+Wind 60 deg - No Ice	
5	Dead+Wind 90 deg - No Ice	
6	Dead+Wind 120 deg - No Ice	
7	Dead+Wind 150 deg - No Ice	
8	Dead+Wind 180 deg - No Ice	
9	Dead+Wind 210 deg - No Ice	
10	Dead+Wind 240 deg - No Ice	
11	Dead+Wind 270 deg - No Ice	
12	Dead+Wind 300 deg - No Ice	
13	Dead+Wind 330 deg - No Ice	
14	Dead+Ice+Temp	
15	Dead+Wind 0 deg+Ice+Temp	
16	Dead+Wind 30 deg+Ice+Temp	
17	Dead+Wind 60 deg+Ice+Temp	
18	Dead+Wind 90 deg+Ice+Temp	
19	Dead+Wind 120 deg+Ice+Temp	
20	Dead+Wind 150 deg+Ice+Temp	
21	Dead+Wind 180 deg+Ice+Temp	
22	Dead+Wind 210 deg+Ice+Temp	
23	Dead+Wind 240 deg+Ice+Temp	
24	Dead+Wind 270 deg+Ice+Temp	
25	Dead+Wind 300 deg+Ice+Temp	
26	Dead+Wind 330 deg+Ice+Temp	
27	Dead+Wind 0 deg - Service	
28 29	Dead+Wind 30 deg - Service Dead+Wind 60 deg - Service	
30	Dead+Wind 60 deg - Service Dead+Wind 90 deg - Service	
31	Dead+Wind 120 deg - Service	
32	Dead+Wind 150 deg - Service  Dead+Wind 150 deg - Service	
33	Dead+Wind 180 deg - Service	
34	Dead+Wind 210 deg - Service	
35	Dead+Wind 240 deg - Service	
36	Dead+Wind 270 deg - Service	
37	Dead+Wind 300 deg - Service	
38	Dead+Wind 330 deg - Service	
	Dead Ind 350 deg Del 100	

# **Maximum Member Forces**

Section	Elevation	Component	Condition	Gov.	Force	Major Axis	Minor Axis
No.	ft	Type		Load		Moment	Moment
				Comb.	lb	lb-ft	lb-ft
L1	180 - 142.25	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	14	-11227.05	-111.64	121.69
			Max. Mx	5	-7091.86	-268526.60	-2444.53
			Max. My	2	-7094.39	2294.17	268236.70
			Max. Vy	5	12855.17	-268526.60	-2444.53
			Max. Vx	2	-12841.60	2294.17	268236.70
			Max. Torque	10			824.70
L2	142.25 - 93.58	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	14	-31277.09	-2802.83	-173.72
			Max. Mx	5	-21395.01	-1358156.79	-9049.31
			Max. My	2	-21399.00	6976.21	1355743.98
			Max. Vy	5	28820.90	-1358156.79	-9049.31
			Max. Vx	2	-28795.76	6976.21	1355743.98
			Max. Torque	7			-682.47
L3	93.58 - 46.5	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	14	-48407.44	-7127.95	-887.16

# Ramaker & Associates

1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999

Job		Page
	Wethersfield Colo (CT58XC967)	17 of 22
Project		Date
	28752	09:31:24 08/05/14
Client		Designed by
	Sprint	JDS

Section	Elevation	Component	Condition	Gov.	Force	Major Axis	Minor Axis
No.	ft	Type		Load		Moment	Moment
		• •		Comb.	lb	lb-ft	lb-ft
			Max. Mx	5	-35585.46	-2845512.74	-15565.50
			Max. My	2	-35588.00	10753.48	2840036.41
			Max. Vy	5	36421.78	-2845512.74	-15565.50
			Max. Vx	2	-36396.84	10753.48	2840036.41
			Max. Torque	7			-435.09
L4	46.5 - 1	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	14	-72215.43	-13541.66	-2093.17
			Max. Mx	5	-55796.29	-5003932.99	-23096.32
			Max. My	2	-55796.36	14533.39	4994332.61
			Max. Vy	5	44744.94	-5003932.99	-23096.32
			Max. Vx	2	-44721.79	14533.39	4994332.61
			Max. Torque	26			-398.87

Maximum Reactions							
Location	Condition	Gov. Load Comb.	Vertical lb	Horizontal, X lb	Horizontal, 2 lb		
Pole	Max. Vert	18	72215.43	-38517.13	-98.29		
	Max. H <sub>x</sub>	11	55823.46	44677.85	90.38		
	Max. H <sub>z</sub>	2	55823.46	115.24	44687.96		
	Max. M <sub>x</sub>	2	4994332.61	115.24	44687.96		
	Max. M <sub>z</sub>	5	5003932.99	-44711.05	-131.42		
	Max. Torsion	20	331.42	-19324.07	-33357.79		
	Min. Vert	1	55823.46	0.00	0.00		
	Min. H <sub>x</sub>	5	55823.46	-44711.05	-131.42		
	Min. H <sub>z</sub>	8	55823.46	-146.96	-44644.50		
	Min. M <sub>x</sub>	8	-4988307.70	-146.96	-44644.50		
	Min. $M_{\tau}$	11	-4988654.66	44677.85	90.38		
	Min. Torsion	26	-398.86	19297.22	33390.49		

# **Tower Mast Reaction Summary**

Load	Vertical	$Shear_x$	$Shear_z$	Overturning	Overturning	Torque
Combination				Moment, $M_x$	Moment, $M_z$	
	lb	lb	lb	lb-ft	lb-ft	lb-ft
Dead Only	55823.46	0.00	0.00	684.69	-5023.56	0.00
Dead+Wind 0 deg - No Ice	55823.46	-115.24	-44687.96	-4994332.61	14533.39	45.86
Dead+Wind 30 deg - No Ice	55823.46	22235.12	-38687.96	-4322442.86	-2484103.61	-144.58
Dead+Wind 60 deg - No Ice	55823.46	38662.88	-22293.82	-2488532.89	-4323891.03	-120.82
Dead+Wind 90 deg - No Ice	55823.46	44711.05	131.42	23096.33	-5003932.99	-114.14
Dead+Wind 120 deg - No Ice	55823.46	38754.36	22433.12	2513653.11	-4340252.98	-153.81
Dead+Wind 150 deg - No Ice	55823.46	22444.72	38716.74	4329391.54	-2519785.30	-146.46
Dead+Wind 180 deg - No Ice	55823.46	146.96	44644.50	4988307.70	-29616.56	-75.71
Dead+Wind 210 deg - No Ice	55823.46	-22266.87	38611.51	4311274.64	2478687.30	121.17
Dead+Wind 240 deg - No Ice	55823.46	-38657.61	22244.19	2481199.63	4313108.49	129.75
Dead+Wind 270 deg - No Ice	55823.46	-44677.85	-90.38	-14973.42	4988654.66	112.37
Dead+Wind 300 deg - No Ice	55823.46	-38708.89	-22490.08	-2522109.78	4322816.05	273.49
Dead+Wind 330 deg - No Ice	55823.46	-22412.81	-38754.94	-4334826.44	2504574.69	224.47
Dead+Ice+Temp	72215.43	0.00	0.00	2093.17	-13541.66	0.03
Dead+Wind 0 deg+Ice+Temp	72215.43	-85.09	-38509.75	-4398567.47	1203.80	272.67
Dead+Wind 30 deg+Ice+Temp	72215.43	19167.68	-33344.70	-3807482.82	-2198937.12	74.75
Dead+Wind 60 deg+Ice+Temp	72215.43	33313.84	-19223.39	-2192812.79	-3818090.80	2.38

# Ramaker & Associates

1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999

Job		Page
	Wethersfield Colo (CT58XC967)	18 of 22
Project		Date
	28752	09:31:24 08/05/14
Client		Designed by
	Sprint	JDS

Load	Vertical	$Shear_x$	$Shear_z$	Overturning	Overturning	Torque
Combination				Moment, $M_x$	Moment, $M_z$	
	lb	lb	lb	lb-ft	lb-ft	lb-ft
Dead+Wind 90 deg+Ice+Temp	72215.43	38517.13	98.29	19298.93	-4415752.79	-113.83
Dead+Wind 120 deg+Ice+Temp	72215.43	33380.02	19319.24	2213962.66	-3830374.90	-259.61
Dead+Wind 150 deg+Ice+Temp	72215.43	19324.07	33357.79	3814745.03	-2226264.91	-331.42
Dead+Wind 180 deg+Ice+Temp	72215.43	110.93	38473.35	4396511.08	-32606.94	-296.18
Dead+Wind 210 deg+Ice+Temp	72215.43	-19194.40	33280.84	3801097.38	2175648.01	-94.70
Dead+Wind 240 deg+Ice+Temp	72215.43	-33309.98	19180.55	2189447.03	3790319.89	6.07
Dead+Wind 270 deg+Ice+Temp	72215.43	-38490.09	-64.82	-9501.71	4384206.23	112.63
Dead+Wind 300 deg+Ice+Temp	72215.43	-33342.54	-19368.06	-2218269.66	3796970.61	361.19
Dead+Wind 330 deg+Ice+Temp	72215.43	-19297.22	-33390.49	-3816421.37	2194616.92	398.86
Dead+Wind 0 deg - Service	55823.46	-64.82	-25136.98	-2810619.84	5927.50	24.10
Dead+Wind 30 deg - Service	55823.46	12507.25	-21761.98	-2432457.09	-1400359.01	-82.33
Dead+Wind 60 deg - Service	55823.46	21747.87	-12540.27	-1400293.97	-2435833.52	-67.43
Dead+Wind 90 deg - Service	55823.46	25149.96	73.92	13307.52	-2818588.99	-62.35
Dead+Wind 120 deg - Service	55823.46	21799.33	12618.63	1415057.32	-2445063.73	-85.34
Dead+Wind 150 deg - Service	55823.46	12625.15	21778.17	2436996.66	-1420455.31	-82.42
Dead+Wind 180 deg - Service	55823.46	82.67	25112.53	2807833.23	-18926.01	-43.16
Dead+Wind 210 deg - Service	55823.46	-12525.11	21718.97	2426773.68	1392797.39	68.34
Dead+Wind 240 deg - Service	55823.46	-21744.90	12512.36	1396773.10	2425249.46	73.58
Dead+Wind 270 deg - Service	55823.46	-25131.29	-50.84	-8123.72	2805472.83	63.51
Dead+Wind 300 deg - Service	55823.46	-21773.75	-12650.67	-1419204.90	2430736.47	154.08
Dead+Wind 330 deg - Service	55823.46	-12607.21	-21799.65	-2439446.35	1407385.41	125.12

# **Solution Summary**

	Sı	ım of Applied Forces			Sum of Reactions	1	
Load	PX	PY	PZ	PX	PY	PZ	% Error
Comb.	lb	lb	lb	lb	lb	lb	
1	0.00	-55823.46	0.00	0.00	55823.46	0.00	0.000%
2	-115.24	-55823.46	-44687.95	115.24	55823.46	44687.96	0.000%
3	22235.12	-55823.46	-38687.96	-22235.12	55823.46	38687.96	0.000%
4	38662.88	-55823.46	-22293.82	-38662.88	55823.46	22293.82	0.000%
5	44711.04	-55823.46	131.42	-44711.05	55823.46	-131.42	0.000%
6	38754.36	-55823.46	22433.12	-38754.36	55823.46	-22433.12	0.000%
7	22444.72	-55823.46	38716.74	-22444.72	55823.46	-38716.74	0.000%
8	146.96	-55823.46	44644.49	-146.96	55823.46	-44644.50	0.000%
9	-22266.87	-55823.46	38611.51	22266.87	55823.46	-38611.51	0.000%
10	-38657.61	-55823.46	22244.19	38657.61	55823.46	-22244.19	0.000%
11	-44677.84	-55823.46	-90.38	44677.85	55823.46	90.38	0.000%
12	-38708.89	-55823.46	-22490.08	38708.89	55823.46	22490.08	0.000%
13	-22412.81	-55823.46	-38754.94	22412.81	55823.46	38754.94	0.000%
14	0.00	-72215.43	0.00	-0.00	72215.43	-0.00	0.000%
15	-85.09	-72215.43	-38509.74	85.09	72215.43	38509.75	0.000%
16	19167.67	-72215.43	-33344.68	-19167.68	72215.43	33344.70	0.000%
17	33313.82	-72215.43	-19223.39	-33313.84	72215.43	19223.39	0.000%
18	38517.12	-72215.43	98.29	-38517.13	72215.43	-98.29	0.000%
19	33380.00	-72215.43	19319.24	-33380.02	72215.43	-19319.24	0.000%
20	19324.06	-72215.43	33357.77	-19324.07	72215.43	-33357.79	0.000%
21	110.93	-72215.43	38473.33	-110.93	72215.43	-38473.35	0.000%
22	-19194.39	-72215.43	33280.83	19194.40	72215.43	-33280.84	0.000%
23	-33309.96	-72215.43	19180.54	33309.98	72215.43	-19180.55	0.000%
24	-38490.08	-72215.43	-64.82	38490.09	72215.43	64.82	0.000%
25	-33342.52	-72215.43	-19368.05	33342.54	72215.43	19368.06	0.000%
26	-19297.22	-72215.43	-33390.48	19297.22	72215.43	33390.49	0.000%
27	-64.82	-55823.46	-25136.97	64.82	55823.46	25136.98	0.000%
28	12507.25	-55823.46	-21761.98	-12507.25	55823.46	21761.98	0.000%
29	21747.87	-55823.46	-12540.27	-21747.87	55823.46	12540.27	0.000%
30	25149.96	-55823.46	73.92	-25149.96	55823.46	-73.92	0.000%
31	21799.33	-55823.46	12618.63	-21799.33	55823.46	-12618.63	0.000%

# Ramaker & Associates

1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999

Job		Page
	Wethersfield Colo (CT58XC967)	19 of 22
Project		Date
	28752	09:31:24 08/05/14
Client		Designed by
	Sprint	JDS

	Sı	ım of Applied Forces			Sum of Reactions	,	
Load	PX	PY	PZ	PX	PY	PZ	% Error
Comb.	lb	lb	lb	lb	lb	lb	
32	12625.15	-55823.46	21778.17	-12625.15	55823.46	-21778.17	0.000%
33	82.67	-55823.46	25112.53	-82.67	55823.46	-25112.53	0.000%
34	-12525.11	-55823.46	21718.97	12525.11	55823.46	-21718.97	0.000%
35	-21744.90	-55823.46	12512.36	21744.90	55823.46	-12512.36	0.000%
36	-25131.28	-55823.46	-50.84	25131.29	55823.46	50.84	0.000%
37	-21773.75	-55823.46	-12650.67	21773.75	55823.46	12650.67	0.000%
38	-12607.21	-55823.46	-21799.65	12607.21	55823.46	21799.65	0.000%

# **Non-Linear Convergence Results**

Load	Converged?	Number	Displacement	Force
Combination		of Cycles	Tolerance	Tolerance
1	Yes	4	0.0000001	0.00000001
2	Yes	4	0.0000001	0.00013783
3	Yes	5	0.0000001	0.00022856
4	Yes	5	0.0000001	0.00022933
5	Yes	4	0.0000001	0.00018088
6	Yes	5	0.0000001	0.00023495
7	Yes	5	0.0000001	0.00023242
8	Yes	4	0.0000001	0.00012066
9	Yes	5	0.0000001	0.00022825
10	Yes	5	0.0000001	0.00022862
11	Yes	4	0.0000001	0.00010052
12	Yes	5	0.0000001	0.00023275
13	Yes	5	0.0000001	0.00023334
14	Yes	4	0.0000001	0.00001107
15	Yes	5	0.0000001	0.00015308
16	Yes	5	0.0000001	0.00050858
17	Yes	5	0.0000001	0.00050858
18	Yes	5	0.0000001	0.00015378
19	Yes	5	0.0000001	0.00051835
20	Yes	5	0.0000001	0.00051647
21	Yes	5	0.0000001	0.00015326
22	Yes	5	0.0000001	0.00050272
23	Yes	5	0.0000001	0.00050496
24	Yes	5	0.0000001	0.00015274
25	Yes	5	0.0000001	0.00051319
26	Yes	5	0.0000001	0.00051161
27	Yes	4	0.0000001	0.00006869
28	Yes	5	0.0000001	0.00005966
29	Yes	5	0.0000001	0.00005989
30	Yes	4	0.0000001	0.00007960
31	Yes	5	0.0000001	0.00006188
32	Yes	5	0.0000001	0.00006089
33	Yes	4	0.0000001	0.00006452
34	Yes	5	0.0000001	0.00005946
35	Yes	5	0.0000001	0.00005940
36	Yes	4	0.0000001	0.00005561
37	Yes	5	0.0000001	0.00006086
38	Yes	5	0.0000001	0.00006115

# **Maximum Tower Deflections - Service Wind**

tn	cTa	ow	er
	~ - 1		

# Ramaker & Associates

1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999

Job		Page
	Wethersfield Colo (CT58XC967)	20 of 22
Project		Date
	28752	09:31:24 08/05/14
Client		Designed by
	Sprint	JDS

Elevation	Horz.	Gov.	Tilt	Twist
	Deflection	Load		
ft	in	Comb.	0	۰
180 - 142.25	53.716	31	2.5198	0.0021
146.58 - 93.58	36.682	31	2.2752	0.0008
99.5 - 46.5	17.039	31	1.6302	0.0002
54 - 1	4.975	31	0.8560	0.0001
	ft 180 - 142.25 146.58 - 93.58 99.5 - 46.5	ft         in           180 - 142.25         53.716           146.58 - 93.58         36.682           99.5 - 46.5         17.039	ft         in         Load Comb.           180 - 142.25         53.716         31           146.58 - 93.58         36.682         31           99.5 - 46.5         17.039         31	ft         in         Load Comb.           180 - 142.25         53.716         31         2.5198           146.58 - 93.58         36.682         31         2.2752           99.5 - 46.5         17.039         31         1.6302

# **Critical Deflections and Radius of Curvature - Service Wind**

Elevation	Appurtenance	Gov.	Deflection	Tilt	Twist	Radius of Curvature
		Load				ft
ft		Comb.	in	0	0	·
181.00	4' T-Arm	31	53.716	2.5198	0.0023	31980
174.00	12' T-Arm	31	50.576	2.4830	0.0020	26650
170.00	Tri-Antenna Mount	31	48.491	2.4578	0.0017	15989
164.00	2' HP Dish	31	45.388	2.4178	0.0014	9993
163.00	1' Dish w/o radome	31	44.874	2.4108	0.0013	9405
152.00	12' T-Arm	31	39.327	2.3251	0.0008	5709
147.00	2' HP Dish	31	36.884	2.2793	0.0008	4921
143.00	RRUS-11	31	34.974	2.2389	0.0008	4690
141.00	14' T-Arm	31	34.033	2.2174	0.0008	4636
131.00	Andrew 14'6" Low-Profile Platform	31	29.491	2.0985	0.0007	4394
124.00	APXV18-206517-C w/Mount Pipe	31	26.473	2.0051	0.0006	4237
51.00	GPS	31	4.476	0.8056	0.0001	2845

# **Maximum Tower Deflections - Design Wind**

Section	Elevation	Horz.	Gov.	Tilt	Twist
No.		Deflection	Load		
	ft	in	Comb.	•	0
L1	180 - 142.25	95.270	6	4.4720	0.0036
L2	146.58 - 93.58	65.074	6	4.0381	0.0015
L3	99.5 - 46.5	30.237	6	2.8934	0.0004
L4	54 - 1	8.832	6	1.5196	0.0001

# Critical Deflections and Radius of Curvature - Design Wind

Elevation	Appurtenance	Gov.	Deflection	Tilt	Twist	Radius of Curvature
		Load				ft
ft		Comb.	in	0	0	· ·
181.00	4' T-Arm	6	95.270	4.4720	0.0043	18189
174.00	12' T-Arm	6	89.705	4.4067	0.0036	15157
170.00	Tri-Antenna Mount	6	86.009	4.3620	0.0032	9094
164.00	2' HP Dish	6	80.508	4.2911	0.0026	5682
163.00	1' Dish w/o radome	6	79.598	4.2787	0.0025	5348
152.00	12' T-Arm	6	69.764	4.1266	0.0015	3245
147.00	2' HP Dish	6	65.433	4.0454	0.0015	2796
143.00	RRUS-11	6	62.045	3.9736	0.0015	2664
141.00	14' T-Arm	6	60.378	3.9355	0.0015	2633
131.00	Andrew 14'6" Low-Profile Platform	6	52.323	3.7245	0.0013	2493

# Ramaker & Associates

1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999

Job		Page
	Wethersfield Colo (CT58XC967)	21 of 22
Project		Date
	28752	09:31:24 08/05/14
Client		Designed by
	Sprint	JDS

Elevation	Appurtenance	Gov.	Deflection	Tilt	Twist	Radius of Curvature
		Load				ft
ft		Comb.	in	0	0	
124.00	APXV18-206517-C w/Mount Pipe	6	46.972	3.5587	0.0011	2403
51.00	GPS	6	7.946	1.4301	0.0001	1604

	Base Plate Design Data								
Plate	Number of	Anchor Bolt	Actual	Actual	Actual	Actual	Controlling	Critical	
Thickness	Anchor Bolts	Size	Allowable	Allowable	Allowable	Allowable	Condition	Ratio	
			Ratio	Ratio	Ratio	Ratio			
			Bolt	Concrete Stress	Plate	Stiffener			
			Tension	ksi	Stress	Stress			
			lb		ksi	ksi			
in		in							
2.2500	16	2.2500	154202.00	2.624	46.448	18.394	Plate	1.24	
			131210.58	2.800	37.500	37.500		1.24	
			1.18	0.94	1.24	0.49			

# **Compression Checks**

	Pole Design Data									
Section No.	Elevation	Size	L	$L_u$	Kl/r	$F_a$	A	Actual P	Allow.	Ratio P
1.0.	ft		ft	ft		ksi	$in^2$	lb	lb	$P_a$
L1	180 - 142.25 (1)	TP33.249x23.1x0.25	37.75	179.00	190.1	4.134	25.2610	-7085.27	104423.00	0.068
L2	142.25 - 93.58 (2)	TP45.833x31.5849x0.375	53.00	179.00	137.5	7.893	52.4753	-21387.30	414194.00	0.052
L3	93.58 - 46.5 (3)	TP57.742x43.4915x0.375	53.00	179.00	109.0	12.567	66.2129	-35581.10	832084.00	0.043
L4	46.5 - 1 (4)	TP69.225x54.9754x0.375	53.00	179.00	87.6	19.142	82.3618	-55796.20	1576570.00	0.035

	Pole Bending Design Data									
Section	Elevation	Size	Actual	Actual	Allow.	Ratio	Actual	Actual	Allow.	Ratio
No.			$M_{x}$	$f_{bx}$	$F_{bx}$	$f_{bx}$	$M_{y}$	$f_{by}$	$F_{by}$	$f_{by}$
	ft		lb-ft	ksi	ksi	$\overline{F_{bx}}$	lb-ft	ksi	ksi	$\overline{F_{by}}$
L1	180 - 142.25 (1)	TP33.249x23.1x0.25	270637.50	-16.366	39.000	0.420	0.00	0.000	39.000	0.000
L2	142.25 - 93.58 (2)	TP45.833x31.5849x0.375	1363141.67	-28.933	39.000	0.742	0.00	0.000	39.000	0.000
L3	93.58 - 46.5 (3)	TP57.742x43.4915x0.375	2853633.33	-37.975	38.509	0.986	0.00	0.000	38.509	0.000
L4	46.5 - 1 (4)	TP69.225x54.9754x0.375	5015600.00	-43.081	34.127	1.262	0.00	0.000	34.127	0.000

# Pole Interaction Design Data

tnx <sub>T</sub>	'ower

# Ramaker & Associates

1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999

Job		Page
	Wethersfield Colo (CT58XC967)	22 of 22
Project		Date
	28752	09:31:24 08/05/14
Client	Sprint	Designed by JDS

Section No.	Elevation	Size	Ratio P	Ratio $f_{bx}$	$Ratio \ f_{by}$	Comb. Stress Ratio	Allow. Stress Ratio	Criteria
	ft		$P_a$	$\overline{F_{bx}}$	$F_{by}$	_		
L1	180 - 142.25 (1)	TP33.249x23.1x0.25	0.068	0.420	0.000	0.487	1.333	H1-3
L2	142.25 - 93.58 (2)	TP45.833x31.5849x0.375	0.052	0.742	0.000	0.793	1.333	H1-3
L3	93.58 - 46.5 (3)	TP57.742x43.4915x0.375	0.043	0.986	0.000	1.029	1.333	H1-3
L4	46.5 - 1 (4)	TP69.225x54.9754x0.375	0.035	1.262	0.000	1.298	1.333	H1-3

# **Section Capacity Table**


Section No.	Elevation ft	Component Type	Size	Critical Element	P lb	$SF*P_{allow} \ lb$	% Capacity	Pass Fail
L1	180 - 142.25	Pole	TP33.249x23.1x0.25	1	-7085.27	139195.85	36.6	Pass
L2	142.25 - 93.58	Pole	TP45.833x31.5849x0.375	2	-21387.30	552120.58	59.5	Pass
L3	93.58 - 46.5	Pole	TP57.742x43.4915x0.375	3	-35581.10	1109167.93	77.2	Pass
L4	46.5 - 1	Pole	TP69.225x54.9754x0.375	4	-55796.20	2101567.72	97.4	Pass
							Summary	
						Pole (L4)	97.4	Pass
						Base Plate	92.9	Pass
						RATING =	97.4	Pass


 $Program\ Version\ 6.1.3.1\ -\ 7/25/2013\ File: I:/28700/28752/Structural/tnx/28752\ rev1.eri$ 

Company : Ramaker & Associates August 5, 2014


Designer : JDS
Job Number : 28752 Wethersfield (CT58XC967) Rev.1 Checked By:\_\_\_\_\_

# Sketch






# Details









X Dir. Steel: 20.99 in<sup>2</sup> (min)(21 #9) Z Dir. Steel: 20.99 in<sup>2</sup> (21 #9)

Top Rebar Plan





Pedestal Rebar Plan

Company : Ramaker & Associates August 5, 2014

Designer : JDS

Job Number: 28752 Wethersfield (CT58XC967) Rev.1 Checked By:\_\_\_\_

# Geometry, Materials and Criteria

Length :30 ft eX:0 in Net Allowable Bearing : 4000 psf (net) Steel fy :60 ksi Width :30 ft eZ:0 in Concrete Weight Minimum Steel :.0018 :145 pcf Thickness: 30 in Concrete f'c Maximum Steel :.0075 pX:102 in :3 ksi

Height : 54 in pZ : 102 in Design Code : ACI 318-05


Footing Top Bar Cover :3.5 in Overturning Safety Factor :1 Phi for Flexure :0.9 Footing Bottom Bar Cover :3.5 in Coefficient of Friction :0.3 Phi for Shear :0.75 Pedestal Longitudinal Bar Cover :1.5 in Passive Resistance of Soil :0 k Phi for Bearing :0.65

# Loads


	P (k)	Vx (k)	Vz (k)	Mx (k-ft)	Mz (k-ft)	Overburden (psf)
DL						400
OL1	55.823	44.779		5015.6		
OL2	55.823	31.664	31.664	3546.6	3546.6	
OL3	72.215	38.568		4424.2		
OL4	72.215	27.272	27.272	3128.4	3128.4	
	+P	+Vx	+Vz	+Mx	+Mz	+Over
		A D	D C	D C	A D	

# Soil Bearing


Description	Categories and Factors	Gross Allow.(psf)	Max Bearing (psf)	Max/Allowable Ratio
Service1	1.2DL+1OL1	4782.77	2197.46 (B)	.459
Service2	1.2DL+1OL2	4782.77	2650.88 (B)	.554
Service3	1.2DL+1OL3	4782.77	2062.76 (B)	.431
Service4	1.2DL+1OL4	4782.77	2432.77 (B)	.509



1.2DL+1OL1 QA: 0 psf QB: 2197.46 psf QC: 2049.68 psf QD: 0 psf NAZ: 351.181 in NAX: 5353.13 in




1.2DL+1OL2 QA: 1081.82 psf QB: 2650.88 psf QC: 881.911 psf QD: 0 psf NAZ: 608.212 in NAX: 539.477 in



QA: 96.39 psf QB: 2062.76 psf QC: 1942.72 psf QD: 0 psf NAZ: 377.647 in NAX: 6186.22 in

1.2DL+1OL3



1.2DL+1OL4 QA: 1099.19 psf QB: 2432.77 psf QC: 928.927 psf QD: 0 psf NAZ: 656.725 in NAX: 582.373 in

# Footing Flexure Design (Bottom Bars)

Description	Categories and Factors	Mu-XX (k-ft)	Z Dir As (in²)	Mu-ZZ (k-ft)	X Dir As (in <sup>2</sup> )
Strength1	1.2DL+1OL1	1628.57	14.208	242.159	2.08
Strength2	1.2DL+1OL2	1150.97	9.987	1282.84	11.148
Strength3	1.2DL+1OL3	1478.39	12.876	260.424	2.238
Strength4	1.2DL+1OL4	1051.43	9.113	1163.75	10.1

# Footing Flexure Design (Top Bars)

Description	Categories and Factors	Mu-XX (k-ft)	Z Dir As (in <sup>2</sup> )	Mu-ZZ (k-ft)	X Dir As (in <sup>2</sup> )			
SW+OB	1SW+1OB-(Strength1,Strength2)	1041.92	9.03	649.264	5.603			
Moment Capacity of Plain Concrete Section Along XX and ZZ=590.445k-ft,590.445k-ft Per Chapter 22 of ACI 318.								

Company : Ramaker & Associates August 5, 2014

Designer : **JDS** 

Job Number: 28752 Wethersfield (CT58XC967) Rev.1 Checked By:\_\_\_\_

# Footing Shear Check

Two Way (Punching) Vc: 2907.88 k One Way (X Dir. Cut) Vc 1022.81 k One Way (Z Dir. Cut) Vc: 1022.81 k

		Punching		X Dir. Cut		Z Dir. Cut	
Description	Categories and Factors	Vu(k)	Vu/ <i>⊗</i> Vc	Vu(k)	Vu/ <i>⊗</i> Vc	Vu(k)	Vu/ <i>⊘</i> Vc
Strength1	1.2DL+1OL1	68.366	.031	228.316	.298	35.122	.046
Strength2	1.2DL+1OL2	70.114	.032	161.499	.211	179.881	.234
Strength3	1.2DL+1OL3	82.223	.038	207.742	.271	37.977	.05
Strength4	1.2DL+1OL4	82.848	.038	148.142	.193	163.797	.214

# Pedestal Design

Shear Check Results (Envelope):

Shear Along X Direction Vc: 1112.45 k Vs: 73.308 k Vu: 44.779 k Vu/ $\varnothing$  Vn: .05  $\varnothing$ : .75

Shear Along Z Direction Vc: 1112.45 k Vs: 73.308 k Vu: 31.664 k Vu/Ø Vn: .036

Pedestal Ties: #3 @ 18 in

Bending Check Results (Envelope):

 Unity Check: .413
 Phi : .9
 Parme Beta: .65

 Pu : 0 k
 Mux : 5015.6 k-ft
 Muz: : 0 k-ft

 Pn : 0 k
 Mnx : 13488.3 k-ft
 Mnz: : NA

Mnox: NA Mnoz : NA

Pedestal Bars: 56 #9 % Steel: .538

Compression Development Length Pedestal Bars (Envelope): Lreq.: 24.713 in Lpro.: 23.116 in Lreq./Lpro.: 1.069

# Concrete Bearing Check (Vertical Loads Only)

Bearing Bc: 53060.4 k

Description	Categories and Factors	Bearing Bu (k)	Bearing Bu/øBc
Strength1	1.2DL+1OL1	901.215	.026
Strength2	1.2DL+1OL2	901.215	.026
Strength3	1.2DL+1OL3	917.607	.027
Strength4	1.2DL+1OL4	917.607	.027

# Overturning Check (Service)

Description	Categories and Factors	Mo-XX (k-ft)	Ms-XX (k-ft)	Mo-ZZ (k-ft)	Ms-ZZ (k-ft)	OSF-XX	OSF-ZZ
Service1	1.2DL+1OL1	5015.6	13518.2	313.453	13518.2	2.695	43.127
Service2	1.2DL+1OL2	3546.6	13739.9	3768.25	13518.2	3.874	3.587
Service3	1.2DL+1OL3	4424.2	13764.1	269.976	13764.1	3.111	50.983
Service4	1.2DL+1OL4	3128.4	13955	3319.3	13764.1	4.461	4.147

Mo-XX: Governing Overturning Moment about AD or BC Ms-XX: Governing Stablizing Moment about AD or BC

OSF-XX: Ratio of Ms-XX to Mo-XX

Company August 5, 2014 : Ramaker & Associates

Designer : JDS

Wethersfield (CT58XC967) Rev.1 Checked By:\_\_\_ Job Number : **28752** 

# Sliding Check (Service)

Description	Categories and Factors	Va-XX (k)	Vr-XX (k)	Va-ZZ (k)	Vr-ZZ (k)	SR-XX	SR-ZZ
Service1	1.2DL+1OL1	44.779	270.364	0	270.364	6.038	NA
Service2	1.2DL+1OL2	31.664	270.364	31.664	270.364	8.539	8.539
Service3	1.2DL+1OL3	38.568	275.282	0	275.282	7.138	NA
Service4	1.2DL+1OL4	27.272	275.282	27.272	275.282	10.094	10.094

Va-XX: Applied Lateral Force to Cause Sliding Along XX Axis Vr-XX: Resisting Lateral Force Against Sliding Along XX Axis

SR-XX: Ratio of Vr-XX to Va-XX

# APPENDIX C MOUNT CALCULATIONS



# WINDSPEED BY LOCATION

# **Search Results**

**Latitude:** 41.7154 **Longitude:** -72.6906

ASCE 7-10 Wind Speeds (3-sec peak gust MPH\*):

Risk Category II: 112 Risk Category III: 123 Risk Category III-IV: 132

MRI\*\* 10 Year: 76 MRI\*\* 25 Year: 87 MRI\*\* 50 Year: 93 MRI\*\* 100 Year: 99

**ASCE 7-05**: 100 **ASCE 7-93**: 80

\*MPH(Miles per hour)

\*\*MRI Mean Recurrence Interval (years)
Users should consult with local building officials
to determine if there are community-specific wind speed
requirements that govern.



# WIND SPEED WEB SITE DISCLAIMER:

While the information presented on this web site is believed to be correct, ATC assumes no responsibility or liability for its accuracy. The material presented in the wind speed report should not be used or relied upon for any specific application without competent examination and verification of its accuracy, suitability and applicability by engineers or other licensed professionals. ATC does not intend that the use of this information replace the sound judgment of such competent professionals, having experience and knowledge in the field of practice, nor to substitute for the standard of care required of such professionals in interpreting and applying the results of the wind speed report provided by this web site. Users of the information from this web site assume all liability arising from such use. Use of the output of this web site does not imply approval by the governing building code bodies responsible for building code approval and interpretation for the building site(s) described by latitude/longitude location in the wind speed report.

Sponsored by the ATC Endowment Fund Applied Technology Council 201 Redwood Shores Parkway, Suite 240 Redwood City, California 94065 (650) 595-1542



1120 Dallas Street Sauk City, WI 53583

Office: (608) 643-4100

Job: 28752

Project: Wethersfield Colo (CT58XC967-B)

By: JMO Date: 7/7/2014

# Wind Load on Antennas TIA-222

# 2.6.9.6 Velocity Pressure

 $q_z = 0.00256 K_z K_{zt} K_d V^2 I$ 

Occupancy: II Classification of Structures (Table 2-1)

Exposure: C Exposure Category

V: 100 mph Basic Wind Speed (Annex B)

z: 174 ft Height above ground level to the center of the antenna

I: 1.00 Importance Factor (Table 2-3)

K<sub>z</sub>: 1.42 Velocity Pressure Coefficient (2.6.5.2)

K<sub>zt</sub>: 1 Topographic Factor (2.6.6.4)

K<sub>d</sub>: 0.95 Wind Direction Probability Factor (Table 2-2)

 $q_z = 34.6$  psf

G<sub>h</sub>: 1.00 Appurtenances and their Connections

# **Mount & Antenna Wind Loads**

Appurtenance	Height	Depth	h/D	Shape	$C_a$	$A_f$	$F = q_z G_h C_a A_a$	
Pipe3STD x 13 ft	156.0 in	3.5 in	44.6	Round	1.104	3.79 sf	144.8 lb	11.1 plf
HSS4X4X3/16 x 4.67 ft	56.0 in	4.0 in	14.0	Flat	1.634	1.56 sf	88.0 lb	18.8 plf
Pipe2STD x 5.33 ft	64.0 in	2.4 in	26.9	Round	1.200	1.06 sf	43.9 lb	8.2 plf
Pipe2STD x 3 ft	36.0 in	2.4 in	15.1	Round	0.981	0.60 sf	20.2 lb	6.7 plf
APXV9TM14-ALU-120	56.3 in	6.3 in	8.9	Flat	1.465	2.46 sf	124.8 lb	
TD-RRH8x20	26.1 in	6.7 in	3.9	Flat	1.262	1.21 sf	53.0 lb	
APXVSPP18-C-A20	72.0 in	7.0 in	10.3	Flat	1.509	3.50 sf	182.9 lb	
1900MHz 4x45W RRH	25.1 in	10.7 in	2.3	Flat	1.200	1.86 sf	77.3 lb	
800MHz 2x50W RRH	19.0 in	12.2 in	1.6	Flat	1.200	1.61 sf	66.8 lb	
P40-16-XLPP-RR	54.0 in	6.5 in	8.3	Flat	1.444	2.44 sf	121.7 lb	



1120 Dallas Street Sauk City, WI 53583

Office: (608) 643-4100

Job: 28752

Project: Wethersfield Colo (CT58XC967-B)

By: JMO 7/7/2014 Date:

# Wind Load on Antennas TIA-222

# 2.6.9.6 Velocity Pressure

 $q_z = 0.00256 K_z K_{zt} K_d V^2 I$ 

Classification of Structures (Table 2-1) Occupancy: Ш

Exposure: С **Exposure Category** 

> Basic Wind Speed (Annex B) V: 100 mph

Height above ground level to the center of the antenna 174 ft z:

Importance Factor (Table 2-3) I: 1.00

K<sub>z</sub>: 1.42 Velocity Pressure Coefficient (2.6.5.2)

K<sub>zt</sub>: 1 Topographic Factor (2.6.6.4)


K<sub>d</sub>: 0.95 Wind Direction Probability Factor (Table 2-2)


 $q_z =$ 34.6 psf

> G<sub>h</sub>: 1.00 Appurtenances and their Connections

# **Mount & Antenna Wind Loads**

Appurtenance	Height	Width	h/D	Shape	$C_a$	$A_f$	$F = q_z G_h C_a A_a$	
Pipe3STD x 13 ft	156.0 in	3.5 in	44.6	Round	1.104	3.79 sf	144.8 lb	11.1 plf
HSS4X4X3/16 x 4.67 ft	56.0 in	4.0 in	14.0	Flat	1.634	1.56 sf	88.0 lb	18.8 plf
Pipe2STD x 5.33 ft	64.0 in	2.4 in	26.9	Round	1.200	1.06 sf	43.9 lb	8.2 plf
Pipe2STD x 3 ft	36.0 in	2.4 in	15.1	Round	0.981	0.60 sf	20.2 lb	6.7 plf
APXV9TM14-ALU-120	56.3 in	12.6 in	4.5	Flat	1.287	4.93 sf	219.4 lb	
TD-RRH8x20	26.1 in	18.6 in	1.4	Flat	1.200	3.37 sf	139.9 lb	
APXVSPP18-C-A20	72.0 in	11.9 in	6.1	Flat	1.358	5.95 sf	279.3 lb	
1900MHz 4x45W RRH	25.1 in	11.1 in	2.3	Flat	1.200	1.93 sf	80.3 lb	
800MHz 2x50W RRH	19.0 in	13.0 in	1.5	Flat	1.200	1.72 sf	71.2 lb	
P40-16-XLPP-RR	54.0 in	17.4 in	3.1	Flat	1.227	6.53 sf	276.9 lb	







Company : Ramaker & Associates Designer : JMO Job Number : 28752

Model Name : Wethersfield Colo (CT58XC967-B)

July 7, 2014

Checked By:\_\_

# **Hot Rolled Steel Properties**

	Label	E [ksi]	G [ksi]	Nu	Therm (\1E	Density[k/ft	Yield[ksi]	Ry	Fu[ksi]	Rt
1	A36 Gr.36	29000	11154	.3	.65	.49	36	1.5	58	1.2
2	A572 Gr.50	29000	11154	.3	.65	.49	50	1.1	65	1.1
3	A992	29000	11154	.3	.65	.49	50	1.1	65	1.1
4	A500 Gr.42	29000	11154	.3	.65	.49	42	1.4	58	1.3
5	A500 Gr.46	29000	11154	.3	.65	.49	46	1.4	58	1.3
6	A53 Gr. B	29000	11154	.3	.65	.49	35	1.5	60	1.2
7	Q235	29000	11154	.3	.65	.49	34	1.5	58	1.2

# **Hot Rolled Steel Section Sets**

	Label	Shape	Type	Design List	Material	Design R	A [in2]	lyy [in4]	Izz [in4]	J [in4]
1	Pipe Mount	PIPE 2.0	Beam	Pipe	A53 Gr. B	Typical	1.02	.627	.627	1.25
2	face	PIPE 3.0	Beam	Pipe	A53 Gr. B	Typical	2.07	2.85	2.85	5.69
3	standoff	HSS4x4x3	Beam	Pipe	A36 Gr.36	Typical	2.58	6.21	6.21	10

# Member Primary Data

	Label	I Joint	J Joint	K Joint	Rotate(deg)	Section/Shape	Type	Design List	Material	Design Rules
1	M1	N1	N2		, ,,	Pipe Mount	Beam	Pipe	A53 Gr. B	Typical
2	M2	N4	N9			standoff	Beam	Pipe	A36 Gr.36	Typical
3	M3	N9A	N8			face	Beam	Pipe	A53 Gr. B	Typical
4	M4	N10	N11			Pipe Mount	Beam	Pipe	A53 Gr. B	Typical
5	M5	N13	N14			Pipe Mount	Beam	Pipe	A53 Gr. B	
6	M6	N16	N17			Pipe Mount	Beam	Pipe	A53 Gr. B	Typical

# Joint Coordinates and Temperatures

	Label	X [ft]	Y [ft]	Z [ft]	Temp [F]	Detach From Diap
1	N1	Ó	1	Ô	0	
2	N2	0	-4.33	0	0	
3	N4	-1.208685	-3	-4.510874	0	
4	APXVTM14-C-I20 TOP	6.	.75	0.	0	
5	APXVTM14-C-I20 BOT	6.	-3.25	0.	0	
6	TD-RRH8X20	-0.517638	-2.5	-1.931852	0	
7	N9	0	-3	0	0	
8	N8	6.5	-3	0.	0	
9	N9A	-6.5	-3	0.	0	
10	N10	-0.517638	-1.5	-1.931852	0	
11	N11	-0.517638	-4.5	-1.931852	0	
12	N12	-0.517638	-3	-1.931852	0	
13	N13	6.	1	0.	0	
14	N14	6.	-4.33	0.	0	
15	N15	6.	-3	0.	0	
16	N16	-6	1	0.	0	
17	N17	-6	-4.33	0.	0	
18	N18	-6	-3	0.	0	
19	APXVSPP18-C-A20 TOP	0	.75	0	0	
20	APXVSPP18-C-A20 BOT	0	-4	0	0	



Company Designer Job Number : Ramaker & Associates

: JMO : 28752

Model Name : Wethersfield Colo (CT58XC967-B)

July 7, 2014

Checked By:\_\_\_

# **Joint Boundary Conditions**

	Joint Label	X [k/in]	Y [k/in]	Z [k/in]	X Rot.[k-ft/rad]	Y Rot.[k-ft/rad]	Z Rot.[k-ft/rad]	Footing
1	N2							
2	N4	Reaction	Reaction	Reaction	Reaction	Reaction	Reaction	
3	TD-RRH8X20							
4	N9							
5	N8							
6	N9A							
7	N10							
8	N11							
9	N12							
10	N14							
11	N15							
12	N17							
13	N18		·					

# Joint Loads and Enforced Displacements (BLC 1 : DL)

	Joint Label	L,D,M	Direction	Magnitude[(lb,lb-ft), (in,rad), (lb*
1	APXVTM14-C-I20 TOP	L	Υ	-27.5
2	TD-RRH8X20	L	Υ	-70
3	APXVTM14-C-I20 BOT	L	Υ	-27.5
4	APXVSPP18-C-A20 TOP	L	Υ	-28.5
5	APXVSPP18-C-A20_BOT	L	Υ	-28.5

# Joint Loads and Enforced Displacements (BLC 2 : WLz)

	Joint Label	L,D,M	Direction	Magnitude[(lb,lb-ft), (in,rad), (lb*
1	APXVTM14-C-I20 TOP	L	Z	-109.7
2	APXVTM14-C-I20 BOT	L	Z	-109.7
3	TD-RRH8X20	L	Z	-139.9
4	APXVSPP18-C-A20 TOP	L	Z	-139.6
5	APXVSPP18-C-A20 BOT	L	Z	-139.6

# Joint Loads and Enforced Displacements (BLC 3 : WLx)

	Joint Label	L,D,M	Direction	Magnitude[(lb,lb-ft), (in,rad), (lb*
1	APXVTM14-C-I20 TOP	L	X	-62.4
2	APXVTM14-C-I20 BOT	L	X	-62.4
3	TD-RRH8X20	L	X	-53
4	APXVSPP18-C-A20 TOP	L	X	-91.5
5	APXVSPP18-C-A20 BOT	L	X	-91.5

# Member Distributed Loads (BLC 2 : WLz)

	Member Label	Direction	Start Magnitude[lb/ft,F]	End Magnitude[lb/ft,F]	Start Location[ft,%]	End Location[ft,%]
1	M3	Z	-11.1	-11.1	0	0
2	M2	PZ	-18.8	-18.8	0	0
3	M4	Z	-6.7	-6.7	0	0
4	M6	Ζ	-8.2	-8.2	0	0

# Member Distributed Loads (BLC 3 : WLx)

	Member Label	Direction	Start Magnitude[lb/ft,F]	End Magnitude[lb/ft,F]	Start Location[ft,%]	End Location[ft,%]
1	M1	X	-8.2	-8.2	0	0
2	M2	PX	-18.8	-18.8	0	0
3	M5	Χ	-8.2	-8.2	0	0
4	M6	X	-8.2	-8.2	0	0



Company : Ramaker & Associates
Designer : JMO
Job Number : 28752
Model Name : Wethersfield Colo (CT58XC967-B)

July 7, 2014

Checked By:\_\_\_

# Member Area Loads

Joint A	Joint B	Joint C	Joint D	Direction	Distribution	Magnitude[psf]
		No Da	ata to Print			

# **Basic Load Cases**

	<b>BLC Description</b>	Category	X Gravity	Y Gravity	Z Gravity	Joint	Point	Distributed	Area(Me	Surface(P
1	DL	DĽ		-1		5			,	,
2	WLz	WLZ				5		4		
3	WLx	WLX				5		4		
4	LL1	LL					1			
5	LL2	None					1			

# **Load Combinations**

	Description	Sol	PDelta	SR	.BLC	Fact.	.BLC	Fact.	BLC	Fact	BLC	Fact.	BLC	Fact	BLC	Fact.	BLC	Fact	BLC	Fact
1	1.4DL	Yes				1.4														
2	1.2DL+1.6WLz	Yes	Υ		DL	1.2	WLZ	1.6												
3	1.2DL-1.6WLz	Yes			DL	1.2	WLZ	-1.6												
4	1.2DL+1.6WLx	Yes			DL	1.2	W	1.6												
5	1.2DL-1.6WLx	Yes	Υ		DL	1.2	W	-1.6												
6	1.2DL+1.6(0.75WLz+0.75WLx)	Yes	Υ		DL			1.2												
7	1.2DL+1.6(0.75WLz-0.75WLx)	Yes	Υ		DL	1.2	WLZ	1.2	W	-1.2										
8	1.2DL-1.6(0.75WLz-0.75WLx)	Yes			DL			-1.2												
9	1.2DL-1.6(0.75WLz+0.75WLx)	Yes			DL	1.2	WLZ	-1.2	W	-1.2										
10	1.2DL+1.5LLend	Yes			DL	1.2	LL	1.5												
11	1.2DL+1.5LLmid	Yes			DL	1.2	5	1.5												
12	1.2DL+1.5LL+10%1.6WLz	Yes	Υ		DL	1.2	LL	1.5	WLZ	.16										
13	1.2DL+1.5LL-10%1.6WLz	Yes	Υ		DL	1.2	LL	1.5	WLZ	16										
14	1.2DL+1.5LL+10%1.6WLx	Yes			DL	1.2	LL	1.5	W	.16										
15	1.2DL+1.5LL-10%1.6WLx	Yes	Υ		DL	1.2	LL	1.5	W	16										
16	1.2DL+1.5LL+10%1.6(0.75WLz+	.Yes	Υ		DL	1.2	LL		WLZ											
17	1.2DL+1.5LL+10%1.6(0.75WLz	. Yes	Υ		DL	1.2	LL		WLZ											
18	1.2DL+1.5LL-10%1.6(0.75WLz-0.	.Yes			DL	1.2	LL	1.5	WLZ	12	W	.12								
19	1.2DL+1.5LL-10%1.6(0.75WLz+	. Yes	Υ		DL	1.2	LL	1.5	WLZ	12	W	12								
20	1.2DL+1.5LL+10%1.6WLz	Yes	Υ		DL	1.2	5		WLZ											
21	1.2DL+1.5LL-10%1.6WLz	Yes	Υ		DL	1.2	5		WLZ											
22	1.2DL+1.5LL+10%1.6WLx	Yes	Υ		DL	1.2	5	1.5	W	.16										
23	1.2DL+1.5LL-10%1.6WLx	Yes	Υ		DL	1.2	5		W											
24	1.2DL+1.5LL+10%1.6(0.75WLz+	.Yes	Υ		DL	1.2	5	1.5	WLZ	.12	W	.12								
25	1.2DL+1.5LL+10%1.6(0.75WLz	. Yes	Υ		DL	1.2	5					12								
26	1.2DL+1.5LL-10%1.6(0.75WLz-0.	Yes			DL	1.2	5	1.5	WLZ	12	W	.12								
27	1.2DL+1.5LL-10%1.6(0.75WLz+	. Yes	Υ		DL	1.2	5	1.5	WLZ	12	W	12								
28	DL		Υ		DL	1														
29	WLz		Υ		WLZ	1														
30	WLx		Υ		W	1														

# **Envelope Joint Reactions**

		Joint		X [lb]	LC	Y [lb]	LC	Z [lb]	LC	MX [lb-ft]	LC	MY [lb-ft]	LC	MZ [lb-ft]	LC
	1	N4	max	922.756	4	831.574	24	1390.927	2	-321.991	2	5173.027	8	3683.342	15
	2		min	-922.756	5	456.574	9	-1390.927	3	-3597.132	21	-5186.232	7	-212.001	4
Γ	3	Totals:	max	922.756	4	831.574	24	1390.927	2						
	4		min	-922.756	5	456.574	9	-1390.927	3						



Company Designer Job Number Model Name

: Ramaker & Associates: JMO: 28752

: Wethersfield Colo (CT58XC967-B)

July 7, 2014

Checked By:\_

# Envelope AISC 13th(360-05): LRFD Steel Code Checks

	Member	Shape	Code Ch	. Loc[ft]	LC	Shear	Loc[ft]	Dir	LC	phi*Pncph	ni*Pnt [	phi*Mn	phi*Mn	Cb Eqn
1	M1	PIPE 2.0	.450	3.998	3	.023	3.998		9	22855.0 (	32130	1871.625	1871.625	1H1-1b
2	M2	HSS4x4x3	.804	0	8	.358	0	У	17	78043.0 {	33592	9909	9909	1H1-1b
3	M3	PIPE 3.0	.523	6.5	15	.146	6.5	,	3	26386.7 (	65205	5748.75	5748.75	1H1-1b
4	M4	PIPE 2.0	.068	1.5	3	.025	1.5		3	28843.4 3	32130	1871.625	1871.625	1H1-1b
5	M5	PIPE 2.0	.355	3.998	3	.018	.278		3	22855.0 3	32130	1871.625	1871.625	1H1-1b
6	M6	PIPE 2.0	.060	3.998	9	.006	3.998		9	22855.0 3	32130	1871.625	1871.625	1H1-1b

**EQUIPMENT SUPPLIER:** 

ALCATEL-LUCENT 600-700 MOUNTAIN AVENUE PH.: (908) 508-8080

PLANS PREPARED BY:

PH.: (608) 643-4100



2.5 EQUIPMENT DEPLOYMENT PROJECT:

WETHERSFIELD COLO SITE NAME:

SITE CASCADE: CT58XC967-B

SITE ADDRESS: 23 KELLEHER COURT-FIREHOUSE#3

WETHERSFIELD, CT 06 I 09

180' MONOPOLE SITE TYPE:

# SITE INFORMATION

# PROPERTY OWNER:

TOWN OF WETHERSFIELD 505 SILAS DEANE HWY, WETHERSFIELD, CT 06 1 09

# SITE ADDRESS:

23 KELLEHER COURT-FIREHOUSE #3 WETHERSFIELD, CT 06 | 09

# GEOGRAPHIC COORDINATES:

LATITUDE: 41.715444 LONGITUDE: -72.690556

# ZONING JURISDICTION:

CONNECTICUT SITING COUNCIL

# ZONING DISTRICT:

A-I RESIDENTIAL

# POWER COMPANY:

CONN. LIGHT AND POWER PH.: (800) 286-2000

# AAV PROVIDER:


PH.: (888) 944-0447

# SPRINT CONSTRUCTION MANAGER:

NAME: MIKE DELIA PHONE: (781) 316-6348 E-MAIL: michael.delia@sprint.com

RAMAKER & ASSOCIATES, INC. CONTACT: KEITH BOHNSACK, PROJECT MANAGER EMAIL: kbohnsack@ramaker.com

# AREA MAP



LOCATION MAP

# PROJECT DESCRIPTION

- INSTALL NEW 2.5 EQUIPMENT IN EXISTING BTS CABINET \*(1) RECTIFIER SHELF AND (3) RECTIFIERS
  \*(1) BASE BAND UNIT
- INSTALL NEW BATTERY STRING IN EXISTING BATTERY CABINET.
- INSTALL (3) PANEL ANTENNAS
- INSTALL (3) RRH'S ON TOWER
- INSTALL (1) HYBRID CABLE AND (2) SECTOR JUMPERS
- INSTALL (27) ANTENNA / RRH JUMPERS

# APPLICABLE CODES



- I. INTERNATIONAL BUILDING CODE
- 2. ANSI/TIA-222 STRUCTURAL STANDARD FOR ANTENNA STRUCTURES
- 3. NEPA 780 LIGHTNING PROTECTION CODE
- 4. NATIONAL ELECTRIC CODE



# SHEET INDEX

SHT NO:	SHEET TITLE:	REV:	ENGINEER:
T-I	TITLE SHEET	Α	JRS
SP-I	SPRINT SPECIFICATIONS	А	JRS
SP-2	SPRINT SPECIFICATIONS	А	JRS
SP-3	SPRINT SPECIFICATIONS	А	JRS
A- I	SITE PLAN	А	JRS
A-2	EQUIPMENT PLAN	А	JRS
A-3	BUILDING ELEVATION \$ ANTENNA DETAILS	А	JRS
A-4	RF DATA SHEET	А	JRS
A-5	FIBER PLUMBING DIAGRAM	А	JRS
A-6	CABLE COLOR CODING	А	JRS
A-7	ANTENNA \$ HYBRID CABLE DETAILS	А	JRS
A-8	EQUIPMENT DETAILS	Α	JRS
5-1	STRUCTURAL DETAILS	А	JRS
E-I	EQUIPMENT UTILITY & GROUNDING PLAN	Α	JRS
E-2	GROUNDING DETAILS	Α	JRS
E-3	DC POWER DETAILS & PANEL SCHEDULES	А	JRS

# WETHERSFIELD COLO SITE#:CT58XC967

23 KELLEHER COURT-FIREHOUSE#3 WETHERSFIELD, CT 06 I 09 HARTFORD COUNTY

SCALE: NONE

PROJECT NUMBER	28752
NUMBER	20752
SHFFT	T 1
NUMBER	1-1

RAMAKER 1120 Dallas Street, Sauk City, WI 53583 Phone: 608-643-4100 Fax: 608-643-7999 www.Ramaker.com

Sprint<sup>®</sup>

6580 SPRINT PARKWAY **OVERLAND PARK, KANSAS 66251** 



**48 SPRUCE STREET** OAKLAND, NJ 07346

hereby certify that this plan, specification, or report was prepare by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of <u>Connecticut</u>.



BSUE FINAL DATE 10/08/2014

TITLE SHEET

SECTION OI 100 - SCOPE OF WORK

3.EL-0568: (FIBER TESTING POLICY)

TELECOMMUNICATIONS EQUIPMENT.

K. PORTLAND CEMENT ASSOCIATION (PCA)

M. BRICK INDUSTRY ASSOCIATION (BIA)

I. AMERICAN WELDING SOCIETY (AWS)

Q DOOR AND HARDWARF INSTITUTE (DHI)

INCLUDED IN THE WORK

CONDITIONS.

BE PERFORMED BY THIS CONSTRUCTION CONTRACTOR (SUPPLIER).

4.NP-3 | 2-20 |: (EXTERIOR GROUNDING SYSTEM TESTING)

FOLLOWING SUPPLEMENTAL REQUIREMENTS FOR INSTALLATION AND TESTING

5.NP-760-500: ETHERNET, MICROWAVE, TESTING AND ACCEPTANCE

PRECEDENCE. NOTIFY SPRINT CONSTRUCTION MANAGER IF THIS OCCURS.

(NATIONAL ELECTRICAL CODE - "NEC") AND NFPA IOI (LIFE SAFETY CODE). E. AMERICAN SOCIETY FOR TESTING OF MATERIALS (ASTM)

F. INSTITUTE OF ELECTRONIC AND ELECTRICAL ENGINEERS (IEEE)
G. AMERICAN CONCRETE INSTITUTE (ACI)

NATIONAL CONCRETE MASONRY ASSOCIATION (NCMA)

O. NATIONAL ROOFING CONTRACTORS ASSOCIATION (NRCA)

AMERICAN WIRE PRODUCERS ASSOCIATION (AWPA)

CONCRETE REINFORCING STEEL INSTITUTE (CRSI)

R. OCCUPATIONAL SAFETY AND HEALTH ACT (OSHA)

AND THE INTERNATIONAL BUILDING CODE.

REPRESENTATIVE IN CHARGE OF PROJECT.

EDITION, AND PORTIONS THEREOF, INCLUDED BUT NOT LIMITED TO THE FOLLOWING:

A. GR-63-CORE NEBS REQUIREMENTS: PHYSICAL PROTECTION
B. GR-78-CORE GENERIC REQUIREMENTS FOR THE PHYSICAL DESIGN AND MANUFACTURE OF

THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE CONSTRUCTION DRAWINGS AND ASSOCIATED OUTLINE SPECIFICATIONS AND THE SITE SPECIFIC WORK ORDER, DESCRIBE THE WORK TO

A. THE REQUIREMENTS OF EACH SECTION OF THIS SPECIFICATION APPLY TO ALL SECTIONS, INDIVIDUALLY

B. RELATED DOCUMENTS: THE CONTRACTOR SHALL COMPLY WITH THE MOST CURRENT VERSION OF THE

SHOULD CONFLICTS OCCUR BETWEEN THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES

I . EN-2012-001: (FIBER OPTIC, DC CABLE, AND DC CIRCUIT BREAKER TAGGING STANDARDS) 2.TS-0200 - (TRANSMISSION ANTENNA LINE ACCEPTANCE STANDARDS)

AND THE CONSTRUCTION DRAWINGS, INFORMATION ON THE CONSTRUCTION DRAWINGS SHALL TAKE

NATIONALLY RECOGNIZED CODES AND STANDARDS:
THE WORK SHALL COMPLY WITH APPLICABLE NATIONAL AND LOCAL CODES AND STANDARDS, LATEST

C. GR-1089 CORE, ELECTROMAGNETIC COMPATIBILITY AND ELECTRICAL SAFETY -GENERIC CRITERIA FOR

NETWORK TELECOMMUNICATIONS EQUIPMENT.
D. NATIONAL FIRE PROTECTION ASSOCIATION CODES AND STANDARDS (NFPA) INCLUDING NFPA 70

AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)

SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)

DEFINITIONS:

A. WORK: THE SUM OF TASKS AND RESPONSIBILITIES IDENTIFIED IN THE CONTRACT DOCUMENTS.

B. COMPANY: "SPRINT"; SPRINT NEXTEL CORPORATION AND IT'S OPERATING ENTITIES.

S. APPLICABLE BUILDING CODES INCLUDING UNIFORM BUILDING CODE, SOUTHERN BUILDING CODE, BOCA,

C. ENGINEER: SYNONYMOUS WITH ARCHITECT & ENGINEER AND "A&E". THE DESIGN PROFESSIONAL HAVING PROFESSIONAL RESPONSIBILITY FOR DESIGN OF THE PROJECT.

THIRD PARTY VENDOR OR AGENCY: A VENDOR OR AGENCY ENGAGED SEPARATELY BY THE COMPANY, A&E, OR CONTRACTOR TO PROVIDE MATERIALS OR TO ACCOMPLISH SPECIFIC TASKS RELATED TO BUT NOT

CONTRACTOR SHALL BE RESPONSIBLE FOR FAMILIARIZING HIMSELF WITH ALL CONTRACT DOCUMENTS. FIELD

CONDITIONS AND DIMENSIONS PRIOR TO PROCEEDING WITH CONSTRUCTION. ANY DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE SPRINT CONSTRUCTION MANAGER PRIOR TO THE COMMENCEMENT

OF WORK. NO COMPENSATION WILL BE AWARDED BASED ON CLAIM OF LACK OF KNOWLEDGE OR FIELD

COMMUNICATION BETWEEN SPRINT AND THE CONTRACTOR SHALL FLOW THROUGH THE SINGLE SPRINT

CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES IN ACCORDANCE WITH

THE CONSTRUCTION CONTRACTOR SHALL MAINTAIN A FULL SET OF THE CONSTRUCTION DRAWINGS FOR

THE JOBSITE DRAWINGS SHALL BE CLEARLY MARKED DAILY IN RED PENCIL WITH ANY CHANGES IN

JOBSITE MARKUP SET SHALL BE DELIVERED TO THE COMPANY OR COMPANY'S DESIGNATED

B. DIMENSIONS SHOWN ARE TO FINISH SURFACES UNLESS NOTED OTHERWISE. SPACING BETWEEN

WIRELESS SITES AND THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES AT THE JOBSITE

CONSTRUCTION OVER WHAT IS DEPICTED IN THE DOCUMENTS. AT CONSTRUCTION COMPLETION, THIS

REPRESENTATIVE TO BE FORWARDED TO THE COMPANY'S A\$E VENDOR FOR PRODUCTION OF "AS-BUILT"

EQUIPMENT IS THE REQUIRED CLEARANCE. SHOULD THERE BE ANY QUESTIONS REGARDING THE CONTRACT DOCUMENTS, EXISTING CONDITIONS AND/OR DESIGN INTENT, THE CONTRACTOR SHALL BE

RESPONSIBLE FOR OBTAINING A CLARIFICATION FROM THE SPRINT CONSTRUCTION MANAGER PRIOR TO

THE CONTRACTOR SHALL CONFINE ALL CONSTRUCTION AND RELATED OPERATIONS INCLUDING STAGING AND STORAGE OF MATERIALS AND EQUIPMENT, PARKING, TEMPORARY FACILITIES, AND WASTE STORAGE TO THE

THE CONTRACT DOCUMENTS. THE CONTRACTOR SHALL EMPLOY A COMPETENT SUPERINTENDENT WHO SHALL

THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK AND SHALL BE RESPONSIBLE FOR

CONSTRUCTION MANAGER APPOINTED TO MANAGE THE PROJECT FOR SPRINT.

BE IN ATTENDANCE AT THE SITE AT ALL TIMES DURING PERFORMANCE OF THE WORK

LEASE PARCEL UNLESS OTHERWISE PERMITTED BY THE CONTRACT DOCUMENTS.

FROM MOBILIZATION THROUGH CONSTRUCTION COMPLETION.

D. CONTRACTOR: CONSTRUCTION CONTRACTOR, SUPPLIER, CONSTRUCTION VENDOR; INDIVIDUAL OR ENTITY WHO AFTER EXECUTION OF A CONTRACT IS BOUND TO ACCOMPLISH THE WORK.

F. CONSTRUCTION MANAGER - ALL PROJECTS RELATED COMMUNICATION TO FLOW THROUGH SPRINT

DRAWINGS

PROCEEDING WITH THE WORK

WHERE NECESSARY TO CUT EXISTING PIPES, ELECTRICAL WIRES, CONDUITS, CABLES, ETC., OF UTILITY SERVICES, OR OF FIRE PROTECTION OR COMMUNICATIONS SYSTEMS, THEY SHALL BE CUT AND CAPPED AT SUITABLE PLACES OR WHERE SHOWN. ALL SUCH ACTIONS SHALL BE COORDINATED WITH THE UTILITY

WHEN REQUIRED THAT A PERMIT OR CONNECTION FEE BE PAID TO A PUBLIC LITILITY PROVIDER FOR NEW SERVICE TO THE CONSTRUCTION PROJECT, PAYMENT OF SUCH FEE SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.

CONTRACTOR:
CONTRACTOR SHALL TAKE ALL MEASURES AND PROVIDE ALL MATERIAL NECESSARY FOR PROTECTING EXISTING EQUIPMENT AND PROPERTY.

JSE OF ELECTRONIC PROJECT MANAGEMENT SYSTEMS: CONTRACTOR WILL UTILIZE ITS BEST EFFORTS TO WORK WITH SPRINT ELECTRONIC PROJECT MANAGEMENT SYSTEMS, CONTRACTOR UNDERSTANDS THAT SUFFICIENT INTERNET ACCESS, EQUIVALENT TO "BROADBAND" OR BETTER, IS REQUIRED TO TIMELY AND EFFECTIVELY UTILIZE SPRINT DATA AND DOCUMENT MANAGEMENT YSTEMS AND AGREES TO MAINTAIN APPROPRIATE CONNECTIONS FOR CONTRACTOR'S STAFF AND OFFICES THAT ARE COMPATIBLE WITH SPRINT DATA AND DOCUMENT MANAGEMENT SYSTEMS

## TEMPORARY UTILITIES AND FACILITIES

THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL TEMPORARY UTILITIES AND FACILITIES NECESSARY EXCEPT AS OTHERWISE INDICATED IN THE CONSTRUCTION DOCUMENTS, TEMPORARY UTILITIES AND FACILITIES INCLUDE POTABLE WATER, HEAT, HVAC, ELECTRICITY, SANITARY FACILITIES, WASTE DISPOSAL FACILITIES, AND TELEPHONE/COMMUNICATION SERVICES. PROVIDE TEMPORARY UTILITIES AND FACILITIES IN ACCORDANCE WITH OSHA AND THE AUTHORITY HAVING JURISDICTION. CONTRACTOR MAY UTILIZE THE COMPANY ELECTRICAL SERVICE IN THE COMPLETION OF THE WORK WHEN IT BECOMES AVAILABLE. USE OF THE LESSOR'S OR SITE OWNER'S UTILITIES OR FACILITIES IS EXPRESSLY FORBIDDEN EXCEPT AS OTHERWISE ALLOWED IN THE CONTRACT DOCUMENTS.

THE CONTRACTOR SHALL PROVIDE ACCESS TO THE JOB SITE FOR AUTHORIZED COMPANY PERSONNEL AND AUTHORIZED REPRESENTATIVES OF THE ARCHITECT/ENGINEER DURING ALL PHASES OF THE WORK.

VERIFY DIMENSIONS INDICATED ON DRAWINGS WITH FIELD DIMENSIONS BEFORE FABRICATION OR ORDERING OF MATERIALS. DO NOT SCALE DRAWINGS.

NOTIFY THE SPRINT CONSTRUCTION MANAGER OF EXISTING CONDITIONS DIFFERING FROM THOSE INDICATED ON THE DRAWINGS. DO NOT REMOVE OR ALTER STRUCTURAL COMPONENTS WITHOUT PRIOR WRITTEN APPROVAL FROM THE ARCHITECT AND ENGINEER.

# SECTION O I 200 - COMPANY FURNISHED MATERIAL AND EQUIPMENT

COMPANY FURNISHED MATERIALS AND EQUIPMENT TO BE INSTALLED BY THE CONTRACTOR (OFIC) IS IDENTIFIED ON THE RF DATA SHEET IN THE CONSTRUCTION DOCUMENTS.

RECEIPT OF MATERIAL AND EQUIPMENT:

A. THE CONTRACTOR IS RESPONSIBLE FOR SPRINT PROVIDED MATERIAL AND EQUIPMENT AND UPON RECEIPT

## L. ACCEPT DELIVERIES AS SHIPPED AND TAKE RECEIPT.

# 2. VERIFY COMPLETENESS AND CONDITION OF ALL DELIVERIES

3. TAKE RESPONSIBILITY FOR EQUIPMENT AND PROVIDE INSURANCE PROTECTION AS REQUIRED IN

B.RECORD ANY DEFECTS OR DAMAGES AND WITHIN TWENTY-FOUR HOURS AFTER RECEIPT. REPORT TO SPRINT OR ITS DESIGNATED PROJECT REPRESENTATIVE OF SUCH.

C PROVIDE SECURE AND NECESSARY WEATHER PROTECTED WAREHOUSING

D.COORDINATE SAFE AND SECURE TRANSPORTATION OF MATERIAL AND EQUIPMENT, DELIVERING AND OFF-LOADING FROM CONTRACTOR'S WAREHOUSE TO SITE.

A.COMPLETE SHIPPING AND RECEIPT DOCUMENTATION IN ACCORDANCE WITH COMPANY PRACTICE. B.IF APPLICABLE, COMPLETE LOST/STOLEN/DAMAGED DOCUMENTATION REPORT AS NECESSARY IN ACCORDANCE WITH COMPANY PRACTICE, AND AS DIRECTED BY COMPANY.

# SECTION 01 300 - CELL SITE CONSTRUCTION

A NO WORK SHALL COMMENCE PRIOR TO COMPANYS ISSUANCE OF THE WORK ORDER.
B.UPON RECEIVING NOTICE TO PROCEED, CONTRACTOR SHALL FULLY PERFORM ALL WORK NECESSARY TO PROVIDE SPRINT WITH AN OPERATIONAL WIRELESS FACILITY.

GENERAL REQUIREMENTS FOR CONSTRUCTION:

A.CONTRACTOR SHALL KEEP THE SITE FREE FROM ACCUMULATING WASTE MATERIAL, DEBRIS, AND TRASH. AT THE COMPLETION OF THE WORK, CONTRACTOR SHALL REMOVE FROM THE SITE ALL REMAINING RUBBISH, IMPLEMENTS, TEMPORARY FACILITIES, AND SURPLUS MATERIALS.

B.EQUIPMENT ROOMS SHALL AT ALL TIMES BE MAINTAINED "BROOM CLEAN" AND CLEAR OF DEBRIS.

C.CONTRACTOR SHALL TAKE ALL REASONABLE PRECAUTIONS TO DISCOVER AND LOCATE ANY HAZARDOUS

I IN THE EVENT CONTRACTOR ENCOUNTERS ANY HAZARDOUS CONDITION WHICH HAS NOT BEEN ABATED OR OTHERWISE MITIGATED, CONTRACTOR AND ALL OTHER PERSONS SHALL IMMEDIATELY STOP WORK IN THE AFFECTED AREA AND NOTIFY COMPANY IN WRITING. THE WORK IN THE AFFECTED AREA SHALL NOT BE RESUMED EXCEPT BY WRITTEN NOTIFICATION BY COMPANY.

2. CONTRACTOR AGREES TO USE CARE WHILE ON THE SITE AND SHALL NOT TAKE ANY ACTION THAT WILL

OR MAY RESULT IN OR CAUSE THE HAZARDOUS CONDITION TO BE FURTHER RELEASED IN THE ENVIRONMENT OR TO FURTHER EXPOSE INDIVIDUALS TO THE HAZARD

D.CONTRACTOR'S ACTIVITIES SHALL BE RESTRICTED TO THE PROJECT LIMITS. SHOULD AREAS OUTSIDE THE PROJECT LIMITS BE AFFECTED BY CONTRACTOR'S ACTIVITIES, CONTRACTOR SHALL IMMEDIATELY RETURN THEM TO ORIGINAL CONDITION

A THE ACTIVITIES DESCRIBED IN THIS PARAGRAPH REPRESENT MINIMUM ACTIONS AND PROCESSES REQUIRED TO SUCCESSFULLY COMPLETE THE WORK. CONTRACTOR SHALL TAKE ALL ACTIONS AS NECESSARY TO SUCCESSFULLY COMPLETE THE CONSTRUCTION OF A FULLY FUNCTIONING WIRELESS FACILITY AT THE SITE IN ACCORDANCE WITH COMPANY PROCESSES.

B. SUBMIT SPECIFIC DOCUMENTATION AS INDICATED HEREIN, AND OBTAIN REQUIRED APPROVALS WHILE THE WORK IS BEING PERFORMED.

C.MANAGE AND CONDUCT ALL FIELD CONSTRUCTION SERVICE RELATED ACTIVITIES D.PROVIDE CONSTRUCTION ACTIVITIES TO THE EXTENT REQUIRED BY THE CONTRACT DOCUMENTS,

INCLUDING BUT NOT LIMITED TO THE FOLLOWING:

I. PERFORM ANY REQUIRED SITE ENVIRONMENTAL MITIGATION.

2. PREPARE GROUND SITES; PROVIDE DE-GRUBBING; AND ROUGH AND FINAL GRADING, AND COMPOUND SURFACE TREATMENTS. 3.MANAGE AND CONDUCT ALL ACTIVITIES FOR INSTALLATION OF UTILITIES INCLUDING ELECTRICAL AND BACKHAUL (FIBER, COPPER, OR MICROWAVE).

4.INSTALL UNDERGROUND FACILITIES INCLUDING UNDERGROUND POWER AND COMMUNICATIONS CONDUITS. AND UNDERGROUND GROUNDING SYSTEM.

5.INSTALL ABOVE GROUND GROUNDING SYSTEMS, CONDUIT AND BOXES 6.PROVIDE NEW HVAC INSTALLATIONS AND MODIFICATIONS.

7.INSTALL "H-FRAMES", CABINETS AND PADS AND PLATFORMS AS INDICATED. 8.INSTALL ROADS, ACCESS WAYS, CURBS AND DRAINS AS INDICATED.

9.ACCOMPLISH REQUIRED MODIFICATION OF EXISTING FACILITIES.

LO PROVIDE ANTENNA SUPPORT STRUCTURE FOUNDATIONS

PROVIDE SLABS AND EQUIPMENT PLATFORMS.

INSTALL COMPOUND FENCING, SIGHT SHIELDING, LANDSCAPING AND ACCESS BARRIERS. PERFORM INSPECTION AND MATERIAL TESTING AS REQUIRED HEREINAFTER.

CONDUCT SITE RESISTANCE TO EARTH TESTING AS REQUIRED HEREINAFTER INSTALL FIXED GENERATOR SETS AND OTHER STANDBY POWER SOLUTIONS.

INSTALL TOWERS, ANTENNA SUPPORT STRUCTURES AND PLATFORMS ON EXISTING TOWERS AS REQUIRED.

INSTALL CELL SITE RADIOS, MICROWAVE, GPS, COAXIAL MAINLINE, ANTENNAS, CROSS BAND COUPLERS, TOWER TOP AMPLIFIERS, LOW NOISE AMPLIFIERS AND RELATED EQUIPMENT.

CONDUCT ALL REQUIRED TESTS AND INSPECTIONS

PERFORM, DOCUMENT, AND CLOSE OUT ALL JURISDICTIONAL PERMITTING REQUIREMENTS AND ANY CONSTRUCTION CONTROL DOCUMENTS THAT MAY BE REQUIRED BY GOVERNMENT AGENCIES AND LANDLORDS.

20. PERFORM ALL ADDITIONAL WORK AS IDENTIFIED IN SCOPE OF SERVICES ATTACHED TO THE SUPPLIER AGREEMENT FOR THIS PROJECT. THIS WORK MAY INCLUDE COMMISSIONING INTEGRATION, SPECIAL WAREHOUSING, REVERSE LOGISTICS ACTIVITIES, ETC. PERFORM COMMISSIONING AND INTEGRATION ACTIVITIES PER APPLICABLE MOPS

DELIVERABLES:
A. THE CONTRACTOR SHALL PROVIDE ALL REQUIRED TEST REPORTS AND DOCUMENTATION INCLUDED BUT

PRODUCT SPECIFICATIONS FOR MATERIALS OR SPECIAL CONSTRUCTION IF REQUESTED BY SPRINT 2. ACTUALIZE ALL CONSTRUCTION RELATED MILESTONES IN SITERRA AND COMPLETE ALL ON-LINE FORMS AND COMPLETE DOCUMENT UP-LOADS. UPLOAD ALL REQUIRED CLOSEOUT DOCUMENTS AND FINAL

3. SCANABLE BARCODE PHOTOGRAPHS OF TOWER TOP AND INACCESSIBLE SERIALIZED EQUIPMENT LEFT ON SITE INSIDE BASE OF MAIN RF CABINET IN A PROTECTIVE POUCH.

4 ALL REQUIRED TEST REPORTS

5. REQUIRED CLOSEOUT DOCUMENTATION INCLUDING BUT NOT LIMITED TO:

a. ALL JURISDICTIONAL PERMITTING AND OCCUPANCY INFORMATION b. PDF SCAN OF REDLINES PRODUCED IN THE FIELD

c. ELECTRONIC AS-BUILT DRAWINGS IN AUTOCAD AND PDF FORMATS

d.LIEN WAIVERS

E. FINAL PAYMENT APPLICATION

f. REQUIRED FINAL CONSTRUCTION PHOTOS

CONSTRUCTION AND COMMISSIONING CHECKLIST COMPLETE WITH NO DEFICIENT ITEMS h. LISTS OF SUBCONTRACTORS

B.PROVIDE ADDITIONAL DOCUMENTATION INCLUDING, BUT NOT LIMITED TO, THE FOLLOWING. DOCUMENTATION SHALL BE FORWARDED IN ORIGINAL FORMAT AND/OR UPLOADED INTO SMS.

ALL CORRESPONDENCE AND PRELIMINARY CONSTRUCTION REPORTS. 2. PROJECT PROGRESS REPORTS

3. PRE-CONSTRUCTION MEETING NOTES

# SECTION 01 400 - TESTS, INSPECTIONS, SUBMITTALS, AND PROJECT

A. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CONSTRUCTION TESTS, INSPECTIONS AND PROJECT B CONTRACTOR SHALL ACCOMPLISH TESTING INCLUDING BUT NOT LIMITED TO THE FOLLOWING

I. COAX SWEEPS AND FIBER TESTS PER TS-0200 (CURRENT VERSION) ANTENNA LINE ACCEPTANCE

STANDARDS 2. POST CONSTRUCTION HEIGHT VERIFICATION, AZIMUTH AND DOWNTILT USING ELECTRONIC

COMMERCIAL MADE-FOR-THE-PURPOSE ANTENNA ALIGNMENT TOOL.

3. CONCRETE BREAK TESTS

SITE RESISTANCE TO EARTH TEST
 STRUCTURAL BACKFILL COMPACTION TESTS

6. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN SITE INSPECTION ACTIVITIES AND/OR AS A RESULT OF TESTING.

7. ADDITIONAL TESTING AS REQUIRED ELSEWHERE IN THIS SPECIFICATION.

A. THE WORK IN ALL ASPECTS SHALL COMPLY WITH THE CONSTRUCTION DRAWINGS AND THESE

B.UPLOAD THE FOLLOWING TO SITERRA AS APPLICABLE INCLUDING BUT NOT LIMITED TO THE FOLLOWING: CONCRETE MIX-DESIGNS FOR TOWER FOUNDATIONS, ANCHORS PIERS, AND CONCRETE PAVING.
 CONCRETE BREAK TESTS AS SPECIFIED HEREIN.

CHEMICAL GROUNDING SYSTEM 4 REINFORCEMENT CERTIFICATIONS

STRUCTURAL BACKFILL TEST RESULTS

6. SWEEP AND FIBER TESTS

ANTENNA AZIMUTH AND DOWN-TILT VERIFICATION

8 POST CONSTRUCTION HEIGHT VERIFICATION

ADDITIONAL SUBMITTALS MAY BE REQUIRED FOR SPECIAL CONSTRUCTION OR MINOR MATERIALS C.ALTERNATES: AT THE COMPANY'S REQUEST, ANY ALTERNATIVES TO THE MATERIALS OR METHODS SPECIFIED SHALL BE SUBMITTED TO SPRINT'S CONSTRUCTION MANAGER FOR APPROVAL PRIOR TO BEING SHIPPED TO SITE. SPRINT WILL REVIEW AND APPROVE ONLY THOSE REQUESTS MADE IN WRITING. NO VERBAL APPROVALS WILL BE CONSIDERED. SUBMITTAL FOR APPROVAL SHALL INCLUDE A STATEMENT OF COST REDUCTION PROPOSED FOR USE OF ALTERNATE PRODUCT.

A.EMPLOY AN AGENCY OF ENGINEERS AND SCIENTISTS WHO IS REGULARLY ENGAGED IN FIELD AND LABORATORY TESTING AND ANALYSIS. AGENCY SHALL HAVE BEEN IN BUSINESS A MINIMUM OF FIVE YEARS, AND BE LICENSED AS PROFESSIONAL ENGINEERS IN THE STATE WHERE THE PROJECT IS LOCATED. AGENCY IS SUBJECT TO APPROVAL BY COMPANY.

I. AGENCY MUST HAVE A THOROUGH UNDERSTANDING OF LOCAL AVAILABLE MATERIALS, INCLUDING THE SOIL, ROCK, AND GROUNDWATER CONDITIONS.

2. AGENCY IS TO BE FAMILIAR WITH THE APPLICABLE REQUIREMENTS FOR THE TESTS TO BE DONE,

EQUIPMENT TO BE USED, AND ASSOCIATED HEALTH AND SAFETY ISSUES.

3. EXPERIENCE IN SOILS, CONCRETE, MASONRY, AGGREGATE, AND ASPHALT TESTING USING ASTM,

AASJTO, AND OTHER METHODS IS NEEDED.
B.REQUIRED THIRD PARTY TESTS:

SITE RESISTANCE TO EARTH TEST PER NP-3 | 2-20 |

2. CONCRETE CYLINDER BREAK TESTS FOR TOWER PIER AND ANCHORS PER NATIONALLY RECOGNIZED

3. STRUCTURAL SOILS COMPACTION TESTS PER NATIONALLY RECOGNIZED STANDARDS REBAR PLACEMENT VERIFICATION WITH REPORT TESTING TENSION STUDY FOR ROCK ANCHORS

ALL THIRD PARTY TESTS AS REQUIRED BY LOCAL JURISDICTION

C.REQUIRED TESTS BY CONTRACTOR

COAX SWEEP TESTS PER SPRINT STANDARD TS-0200

2 FIBER TESTS PER SPRINT STANDARD FL-0568

. MICROWAVE LINK TESTS PER NP-760-500

4. ANTENNA AZIMUTHS AND DOWN TILT USING ELECTRONIC ALIGNMENT TOOL PER ANTENNA INSTALLATION SPECIFICATION HEREIN



6580 SPRINT PARKWAY OVERLAND PARK, KANSAS 66251



1120 Dallas Street, Sauk City, WI 53583 Phone: 608-643-4100 Fax: 608-643-7999 www.Ramaker.com



**48 SPRUCE STREET** OAKLAND, NJ 07346

hereby certify that this plan, specification, or report was pi y me or under my direct supervision and that I am a duly Licensec rofessional Engineer under the laws of the State of Connecticut



WETHERSFIELD COLO

FINIAL

23 KELLEHER COURT-FIREHOUSE#3 WETHERSFIELD, CT 06 I 09

SITE#:CT58XC967

SPRINT SPECIFICATIONS

SCALE: NONE

HARTFORD COUNTY

28752

DATE 10/08/2014

- POST CONSTRUCTION HEIGHT VERIFICATION AS REQUIRED HEREWITH IN THE TOWER INSTALLATION SPECIFICATIONS
- ASPHALT ROADWAY COMPACTED THICKNESS, SURFACE SMOOTHNESS, AND COMPACTED DENSITY TESTING AS SPECIFIED HEREWITH IN THE ASPHALT PAVING SPECIFICATIONS
- FIELD QUALITY CONTROL TESTING AS SPECIFIED HEREWITH IN THE CONCRETE PAVING SPECIFICATIONS
- TESTING REQUIRED HEREWITH UNDER SPECIFICATIONS FOR AGGREGATE BASE FOR ROADWAYS
- 9. ALL OTHER TESTS REQUIRED BY LOCAL JURISDICTION
  D.INSPECTIONS BY COMPANY: THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN INSPECTION ACTIVITIES, FINAL ACCEPTANCE / PUNCH WALK REVIEW, AND/OR AS A RESULT OF TESTING
- E. SPRINT RESERVES THE RIGHT TO INSPECT THE CONSTRUCTION SITE AT ANY TIME VIA SITE WAIKS AND/OR PHOTO REVIEWS. CONTRACTOR SHALL GIVE SPRINT 24 HOURS NOTICE PRIOR TO THE COMMENCEMENT OF THE FOLLOWING CONSTRUCTION ACTIVITIES AND PHOTOGRAPHS OF THE IN-PROGRESS WORK, I. GROUNDING SYSTEM AND BURIED UTILITIES INSTALLATION PRIOR TO EARTH CONCEALMENT
  - DOCUMENTED WITH DIGITAL PHOTOGRAPHS BY CONTRACTOR, APPROVED BY A¢E OR SPRINT REPRESENTATIVE
  - FORMING FOR CONCRETE AND REBAR PLACEMENT PRIOR TO POUR DOCUMENTED WITH DIGITAL PHOTOGRAPHS BY CONTRACTOR, APPROVED BY A\$E OR SPRINT REPRESENTATIVE.
  - COMPACTION OF BACKFILL MATERIALS AGGREGATE BASE FOR ROADS, PADS, AND ANCHORS ASPHALT PAVING, AND SHAFT BACKFILL FOR CONCRETE AND WOOD POLES. BY INDEPENDENT THIRD PARTY AGENCY.
  - PRE AND POST CONSTRUCTION ROOFTOP AND STRUCTURAL INSPECTIONS ON EXISTING FACILITIES. PRIOR TO CONSTRUCTION ACTIVITIES AND AFTER CONSTRUCTION IS COMPLETE, PROVIDE PHOTOGRAPHIC DOCUMENTATION OF ROOF, FLASHINGS, AND PARAPETS, BOTH BEFORE AND AFTER CONSTRUCTION IS COMPLETE
- TOWER ERECTION SECTION STACKING AND PLATFORM ATTACHMENT DOCUMENTED BY DIGITAL PHOTOGRAPHS BY THIRD PARTY AGENCY.
- TOWER TOP AND INACCESSIBLE EQUIPMENT (RRUS, ANTENNAS, AND CABLING): PROVIDE PHOTOS OF THE BACKS OF ALL ANTENNAS, RRUS, COMBINERS, FILTERS, FIBER AND DC CABLING, CABLE COLOR CODING, EQUIPMENT GROUNDING AND CONNECTOR WATER PROOFING INCLUDING NAME PLATE AND SERIAL NUMBER FOR ALL SERIALIZED EQUIPMENT.

A.FINAL ACCEPTANCE PUNCH WALK AND INSPECTION: AS IDENTIFIED IN THE SCOPE OF SERVICES, SPRINT WILL CONDUCT A FINAL PUNCH WALK OR FINAL DESK TOP PHOTO REVIEW (SITE MODIFICATIONS). PUNCI WALKS MUST BE SCHEDULED IN ADVANCE AS REQUIRED. AT THE PUNCH WALK / REVIEW. SPRINT MAY IDENTIFY CRITICAL DEFICIENCIES WHICH MUST BE CORRECTED PRIOR TO PUTTING SITE ON AIR. MINOR DEFICIENCIES MUST BE CORRECTED WITHIN 30 DAYS EXCEPT AS OTHERWISE REQUIRED. VERIFICATIONS OF CORRECTIONS MAY BE MADE BY COMPANY DURING A REPEAT SITE WALK OR DESK TOP PHOTO REVIEW AT COMPANYS SOLE DISCRETION.

B.CLOSEOUT DOCUMENTATION: ALL CLOSEOUT DOCUMENTATION AND PHOTOGRAPHS SHALL BE UPLOADED

PRIOR TO FINAL ACCEPTANCE. SPRINT WILL REVIEW CLOSEOUT DOCUMENTATION FOR PRESENCE AND CONTENT. CLOSEOUT DOCUMENTATION SHALL INCLUDE BUT IS NOT LIMITED TO THE FOLLOWING AS APPLICABLE:

- COAX SWEEP TESTS:
- FIBER TESTS:
  JURISDICTION FINAL INSPECTION DOCUMENTATION
- REINFORCEMENT CERTIFICATION (MILL CERTIFICATION)
  CONCRETE MIX DESIGN AND PRODUCT DATA (TOWER FOUNDATION)
- LIEN WAIVERS AND RELEASES.
  POST -CONSTRUCTION HEIGHT VERIFICATION
- JURISDICTION CERTIFICATE OF OCCUPANCY
  ELECTRONIC ANTENNA AZIMUTH AND DOWN TILT VERIFICATION
- STRUCTURAL BACKFILL TEST RESULTS (IF APPLICABLE)
- CELL SITE UTILITY SETUP
- AS-BUILT REDLINE CONSTRUCTION DRAWINGS (PDF SCAN OF FIELD MARKS)
- 13. AS-BUILT CONSTRUCTION DRAWINGS IN DWG AND PDF FORMATS
- 14. LIST OF SUB CONTRACTORS
- 15. APPROVED PERMITTING DOCUMENTS
- 16. FINAL SITE PHOTOS UP-LOADED TO SITERRA. INCLUDE THE FOLLOWING AS APPLICABLE: a. TOWER, ANTENNAS, RRUS, AND MAINLINE: INSPECTION AND PHOTOGRAPHS OF SECTION
  - STACKING; INSPECTION AND PHOTOGRAPHS OF PLATFORM COMPONENT ATTACHMENT POINTS; PHOTOGRAPHS OF TOWER TOP GROUNDING: PHOTOS OF TOWER COAX/CABLE LINE COLOR CODING AT THE TOP AND AT GROUND LEVEL; INSPECTION AND PHOTOGRAPHS OF OPERATIONAL OF TOWER LIGHTING, AND PLACEMENT OF FAA REGISTRATION SIGN; PHOTOGRAPHS SHOWING ADDITIONAL GROUNDING POINTS FOR TOWERS GREATER THAN 200 FEET.; PHOTOS OF ANTENNA GROUND BAR, EQUIPMENT GROUND BAR, AND MASTER GROUND BAR, PHOTOS OF GPS ANTENNA(S); PHOTOS OF EACH SECTOR OF ANTENNAS; ONE PHOTOGRAPH LOOKING AT THE SECTOR AND ONE FROM BEHIND SHOWING THE PROJECTED COVERAGE AREA: PHOTOS OF COAX WEATHERPROOFING - TOP AND BOTTOM; PHOTOS OF COAX GROUNDING--TOP AND BOTTOM; PHOTOS OF ANTENNA AND MAST GROUNDING; PHOTOS OF COAX CABLE ENTRY INTO SHELTER; PHOTOS OF PLATFORM MECHANICAL CONNECTIONS TO TOWER/MONOPOLE.
  - b. ROOF TOPS: PRE-CONSTRUCTION AND POST-CONSTRUCTION VISUAL INSPECTION AND PHOTOGRAPHS OF THE ROOF AND INTERIOR TO DETERMINE AND DOCUMENT CONDITIONS; ROOF TOP CONSTRUCTION INSPECTIONS AS REQUIRED BY THE JURISDICTION; PHOTOGRAPHS OF CABLE TRAY AND/OR ICE BRIDGE; PHOTOGRAPHS OF DOGHOUSE/CABLE EXIT FROM ROOF;
  - c. SITE LAYOUT PHOTOGRAPHS OF THE OVERALL COMPOUND, INCLUDING EQUIPMENT PLATFORM FROM ALL FOUR CORNERS.
  - ALFINISHED UTILITIES: CLOSE-UP PHOTOGRAPHS OF THE PPC BREAKER PANEL; CLOSE-UP PHOTOGRAPH OF THE INSIDE OF THE TELCO PANEL AND NIU; CLOSE-UP PHOTOGRAPH OF THE POWER METER AND DISCONNECT; PHOTOS OF POWER AND TELCO ENTRANCE TO COMPANY ENCLOSURE; PHOTOGRAPHS AT METER BOX AND/OR FACILITY DISTRIBUTION PANEL.

A.PROVIDE PROJECT CLOSEOUT GENERAL ARRANGEMENT PHOTOS OF ALL NEW WORK. THE FOLLOWING LIST REPRESENTS MINIMUM REQUIREMENTS AND MINIMUM QUANTITY. ADDITIONAL PHOTOS MAY BE REQUIRED TO ADEQUATELY DOCUMENT THE WORK.

- ASR AND RF MPE SIGNAGE (IF NOT IN PLACE, SUPPLIER NOTIFIES EMS FIELD REPRESENTATIVE)
- BACK OF ANTENNAS AND RRUS (I EACH SECTOR)
  BACK OF ANTENNAS AND RRUS (I EACH SECTOR) CLOSE UP SHOWING WEATHERPROOFING AND GROUNDING (AS REQUIRED). CLOSE-UP OF BACK SIDE OF EACH PERMANENT RRU SHOWING SERIAL NUMBER/BAR CODE
- VIEW (I EACH SECTOR) ALONG THE AZIMUTH AND TILT OF THE ANTENNAS
- TOP OF TOWER FROM GROUND, I EACH SECTOR
  MAINLINE HYBRID CABLE ROUTE DOWN TOWER SHOWING FASTENERS AND SUPPORT
- MAINLINE/HYBRID CABLE ROUTE ALONG ICE BRIDGE OR IN CABLE TRAY SHOWING FASTENERS AND
- GROUND MOUNTED RRU RACKS (FRONT AND BACK)
- FRONT, SIDE AND BACK ELEVATIONS OF ALL GROUND CABINETS
- LO VIEW OF COMPOUND FROM A DISTANCE
- 11. VIEW OF EACH GROUND CABINET (POWER, RF, FIBER SPOOL, PPC POWER, PPC TELCO WITH DOOR
- 12. BACKHAUL FIBER MEET-ME-POINT AND CONDUIT ROUTE (MICROWAVE INSTALLATION IF NOT FIBER)
- 13. AAV NETWORK INTERFACE DEVICE OR MICROWAVE RADIO INSTALLATION

CONTRACTOR IS RESPONSIBLE FOR ALL CORRECTIONS TO DEFICIENCIES IDENTIFIED THROUGH TESTING, REVIEW OF SUBMITTALS, INSPECTIONS AND CLOSEOUT REVIEWS.

# SECTION O I 500 - PROJECT REPORTING

A CONTRACTOR SHALL REPORT TO SPRINT AT MINIMUM ON A WEEKLY BASIS VIA SITERRA BY LIPDATING ALL APPLICABLE POST END KEEPING MILESTONES WITH ACTUAL AND FORECASTED COMPLETION DATES, B. ADDITIONAL REQUIREMENTS FOR REPORTING MAY BE IDENTIFIED ELSEWHERE OR REQUIRED BY THE SCOPE

# OF SERVICES OR SPRINTS LOCAL MARKET CONSTRUCTION MANAGER. THIS INFORMATION WILL PROVIDE A BASIS FOR PROGRESS MONITORING AND PAYMENT.

SPRINT MAY HOLD PERIODIC PROJECT CONFERENCE CALLS. CONTRACTOR WILL BE REQUIRED TO COMMUNICATE SITE STATUS, MILESTONE COMPLETIONS AND UPCOMING MILESTONE PROJECTIONS, AND ANSWER ANY OTHER SITE STATUS QUESTIONS AS NECESSARY.

FINAL PROJECT ACCEPTANCE: PRIOR TO SPRINTS FINAL PROJECT ACCEPTANCE. ALL REQUIRED MILESTONE ACTUALS MUST BE UPDATED IN SITERRA AND ALL REQUIRED REPORTING TASKS MUST BE COMPLETE.

# SECTION I I 700 - ANTENNA ASSEMBLY, REMOTE RADIO UNITS AND CABLE INSTALLATION

THIS SECTION SPECIFIES INSTALLATION OF ANTENNAS, RRU'S, AND CABLE EQUIPMENT, INSTALLATION, AND TESTING OF COAXIAL FIBER CABLE.

THE NUMBER AND TYPE OF ANTENNAS AND RRU'S TO BE INSTALLED IS DETAILED ON THE CONSTRUCTION DRAWINGS.

HYBRID CABLE WILL BE DC/FIBER AND FURNISHED FOR INSTALLATION AT EACH SITE. CABLE SHALL BE INSTALLED PER THE CONSTRUCTION DRAWINGS AND THE APPLICABLE MANUFACTURER'S REQUIREMENTS

JUMPERS AND CONNECTORS: FURNISH AND INSTALL 1/2" COAX JUMPER CABLES BETWEEN THE RRUS AND ANTENNAS, JUMPERS SHALL BE TYPE LDF 4, FLC 12-50, CR 540, OR FXL 540. SUPER-FLEX CABLES ARE NOT ACCEPTABLE. JUMPERS BETWEEN THE RRU'S AND ANTENNAS OR TOWER TOP AMPLIFIERS SHALL CONSIST OF 1/2 INCH FOAM DIELECTRIC, OUTDOOR RATED COAXIAL CABLE, MIN. LENGTH FOR JUMPER SHALL BE 10"-0".

INSTALL SPLITTERS, COMBINERS, FILTERS PER RF DATA SHEET, FURNISHED BY SPRINT.

THE CONTRACTOR SHALL ASSEMBLE ALL ANTENNAS ONSITE IN ACCORDANCE WITH THE INSTRUCTIONS SUPPLIED BY THE MANUFACTURER. ANTENNA HEIGHT, AZIMUTH, AND FEED ORIENTATION INFORMATION SHALL BE A DESIGNATED ON THE CONSTRUCTION DRAWINGS.

- A. THE CONTRACTOR SHALL POSITION THE ANTENNA ON TOWER PIPE MOUNTS SO THAT THE BOTTOM STRUT IS LEVEL. THE PIPE MOUNTS SHALL BE PLUMB TO WITHIN I DEGREE.
- B.ANTENNA MOUNTING REQUIREMENTS: PROVIDE ANTENNA MOUNTING HARDWARE AS INDICATED ON THE

# HYBRID CABLE INSTALLATION:

- A. THE CONTRACTOR SHALL ROUTE, TEST, AND INSTALL ALL CABLES AS INDICATED ON THE CONSTRUCTION DRAWINGS AND IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS
- B THE INSTALLED RADIUS OF THE CABLES SHALL NOT BE LESS THAN THE MANUFACTURER'S SPECIFICATIONS

C.EXTREME CARE SHALL BE TAKEN TO AVOID DAMAGE TO THE CABLES DURING HANDLING AND INSTALLATION.

- I. FASTENING MAIN HYBRID CABLES: ALL CABLES SHALL BE INSTALLED INSIDE MONOPOLE WITH CABLE SUPPORT GRIPS AS REQUIRED BY THE MANUFACTURER.
- 2. FASTENING INDIVIDUAL FIBER AND DC CABLES ABOVE BREAKOUT ENCLOSURE (MEDUSA), WITHIN THE MMBS CABINET AND ANY INTERMEDIATE DISTRIBUTION BOXES:
  - a. FIBER: SUPPORT FIBER BUNDLES USING 1/2" VELCRO STRAPS OF THE REQUIRED LENGTH AT 18" O.C. STRAPS SHALL BE UV, OIL AND WATER RESISTANT AND SUITABLE FOR INDUSTRIAL INSTALLATIONS AS MANUFACTURED BY TEXTOL OR APPROVED EQUAL.
  - b. DC: SUPPORT DC BUNDLES WITH ZIP TIES OF THE ADEQUATE LENGTH. ZIP TIES TO BE UV STABILIZED, BLACK NYLON, WITH TENSILE STRENGTH AT 12,000 PSI AS MANUFACTURED BY NELCO PRODUCTS OR EQUAL.
- 3. FASTENING JUMPERS: SECURE JUMPERS TO THE SIDE ARMS OR HEAD FRAMES USING STAINLESS STEEL TIE WRAPS OR STAINLESS STEEL BUTTERFLY CLIPS.
- 4. CABLE INSTALLATION
  - a. INSPECT CABLE PRIOR TO USE FOR SHIPPING DAMAGE, NOTIFY THE CONSTRUCTION
  - b. CABLE ROUTING: CABLE INSTALLATION SHALL BE PLANNED TO ENSURE THAT THE LINES MILL BE PROPERLY ROUTED IN THE CABLE ENVELOP AS INDICATED ON THE DRAWINGS. AVOID TWISTING AND CROSSOVERS.
  - c. HOIST CABLE USING PROPER HOISTING GRIPS. DO NOT EXCEED MANUFACTURER'S RECOMMENDED MAXIMUM BEND RADIUS
- 5. GROUNDING OF TRANSMISSION LINES: ALL TRANSMISSION LINES SHALL BE GROUNDED AS INDICATED ON DRAWINGS
- 7. HYBRID CABLE LABELING: INDIVIDUAL HYBRID AND DC BUNDLES SHALL BE LABELED ALPHA-NUMERICALLY ACCORDING TO SPRINT CELL SITE ENGINEERING NOTICE - EN 2012-001, REV I

6. HYBRID CABLE COLOR CODING: ALL COLOR CODING SHALL BE AS REQUIRED IN TS 0200 (CURRENT

# WEATHERPROOFING EXTERIOR CONNECTORS AND HYBRID CABLE GROUND KITS:

A. ALL FIBER ¢ COAX CONNECTORS AND GROUND KITS SHALL BE WEATHERPROOFED

- B. WEATHERPROOFED USING ONE OF THE FOLLOWING METHODS. ALL INSTALLATIONS MUST BE DONE IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS AND INDUSTRY BEST PRACTICES.
- COLD SHRINK: ENCOMPASS CONNECTOR IN COLD SHRINK TUBING AND PROVIDE A DOUBLE WRAP OF " ELECTRICAL TAPE EXTENDING 2" BEYOND TUBING. PROVIDE 3M COLD SHRINK CXS SERIES OR
- 2 SELF-AMALGAMATING TAPE: CLEAN SURFACES, APPLY A DOUBLE WRAP OF SELF-AMALGAMATING TAPE 2" BEYOND CONNECTOR. APPLY A SECOND WRAP OF SELF-AMALGAMATING TAPE IN OPPOSITE DIRECTION. APPLY DOUBLE WRAP OF 2" WIDE ELECTRICAL TAPE EXTENDING 2" BEYOND THE
- 3. 3M SLIM LOCK CLOSURE 716: SUBSTITUTIONS WILL NOT BE ALLOWED.
- 4. OPEN FLAME ON JOB SITE IS NOT ACCEPTABLE

# SECTION 1 1 800 - INSTALLATION OF MULTIMODAL BASE STATIONS (MMBS)

## SUMMARY

- A. THIS SECTION SPECIFIES MMBS CABINETS, POWER CABINETS, AND INTERNAL EQUIPMENT INCLUDING BY NOT LIMITED TO RECTIFIERS, POWER DISTRIBUTION UNITS, BASE BAND UNITS, SURGE ARRESTORS, BATTERIES, AND SIMILAR EQUIPMENT FURNISHED BY THE COMPANY FOR INSTALLATION BY THE CONTRACTOR (OFCI)
- B.CONTRACTOR SHALL PROVIDE AND INSTALL ALL MISCELLANEOUS MATERIALS AND PROVIDE ALL LABOR REQUIRED FOR INSTALLATION EQUIPMENT IN EXISTING CABINET OR NEW CABINET AS SHOWN ON DRAWINGS AND AS REQUIRED BY THE APPLICABLE INSTALLATION MOPS.

C.COMPLY WITH MANUFACTURER'S INSTALLATION AND START-UP REQUIREMENTS.

## DC CIRCUIT BREAKER LABELING

A.NEW DC CIRCUIT IS REQUIRED IN MMBS CABINET SHALL BE CLEARLY IDENTIFIED AS TO RRU BEING SERVICED.

# SECTION 26 100 - BASIC ELECTRICAL REQUIREMENTS

THIS SECTION SPECIFIES BASIC ELECTRICAL REQUIREMENTS FOR SYSTEMS AND COMPONENTS

# QUALITY ASSURANCE:

- A.ALL EQUIPMENT FURNISHED UNDER DIVISION 26 SHALL CARRY UL LABELS AND LISTINGS WHERE SUCH LABELS AND LISTINGS ARE AVAILABLE IN THE INDUSTRY.
- B.MANUFACTURERS OF EQUIPMENT SHALL HAVE A MINIMUM OF THREE YEARS EXPERIENCE WITH THEIR EQUIPMENT INSTALLED AND OPERATING IN THE FIELD IN A USE SIMILAR TO THE PROPOSED USE FOR THIS
- C.MATERIALS AND EQUIPMENT: ALL MATERIALS AND EQUIPMENT SPECIFIED IN DIVISION 26 OF THE SAME TYPE SHALL BE OF THE SAME MANUFACTURER AND SHALL BE NEW, OF THE BEST QUALITY AND DESIGN, AND FREE FROM DEFECTS.

# SUPPORTING DEVICES

- A.MANUFACTURED STRUCTURAL SUPPORT MATERIALS: SUBJECT TO COMPLIANCE WITH REQUIREMENTS, PROVIDE PRODUCTS BY THE FOLLOWING:
- I. ALLIED TUBE AND CONDUIT.
- 2. B-LINE SYSTEM.
- 3. UNISTRUT DIVERSIFIED PRODUCTS.
- 4. THOMAS # BETTS

B.FASTENERS: TYPES, MATERIALS, AND CONSTRUCTION FEATURES AS FOLLOWS

- I. EXPANSION ANCHORS: CARBON STEEL WEDGE OR SLEEVE TYPE.
- 2. POWER-DRIVEN THREADED STUDS: HEAT-TREATED STEEL, DESIGNED SPECIFICALLY FOR THE INTENDED
- 3. FASTEN BY MEANS OF WOOD SCREWS ON WOOD
- 4. TOGGLE BOLTS ON HOLLOW MASONRY UNITS.
- 5. CONCRETE INSERTS OR EXPANSION BOLTS ON CONCRETE OR SOLID MASONRY.
- 6. MACHINE SCREWS, WELDED THREADED STUDS, OR SPRING-TENSION CLAMPS ON STEEL
- 7. EXPLOSIVE DEVICES FOR ATTACHING HANGERS TO STRUCTURE SHALL NOT BE PERMITTED
- 8. DO NOT WELD CONDUIT, PIPE STRAPS, OR ITEMS OTHER THAN THREADED STUDS TO STEEL
- 9. IN PARTITIONS OF LIGHT STEEL CONSTRUCTION, USE SHEET METAL SCREWS.



6580 SPRINT PARKWAY OVERLAND PARK, KANSAS 66251



1120 Dallas Street, Sauk City, WI 53583 Phone: 608-643-4100 Fax: 608-643-7999 www.Ramaker.com



**48 SPRUCE STREET** OAKLAND, NJ 07346

## ertification \$ Seal:

hereby certify that this plan, specification, or report was pi by me or under my direct supervision and that I am a duly Lic y me or under my direct supervision and that I am a duly Licensec rofessional Engineer under the laws of the State of Connecticut



FINIAL

WETHERSFIELD COLO SITE#:CT58XC967

DATE 10/08/2014

23 KELLEHER COURT-FIREHOUSE#3 WETHERSFIELD, CT 06 I 09

HARTFORD COUNTY

SPRINT SPECIFICATIONS

SCALE: NONE

28752

## SUPPORTING DEVICES:

- A. INSTALL SUPPORTING DEVICES TO FASTEN ELECTRICAL COMPONENTS SECURELY AND PERMANENTLY IN
- B. COORDINATE WITH THE BUILDING STRUCTURAL SYSTEM AND WITH OTHER TRADES.
- C. UNLESS OTHERWISE INDICATED ON THE DRAWINGS, FASTEN ELECTRICAL ITEMS AND THEIR SUPPORTING HARDWARE SECURELY TO THE STRUCTURE IN ACCORDANCE WITH THE FOLLOWING
- I. ENSURE THAT THE LOAD APPLIED BY ANY FASTENER DOES NOT EXCEED 25 PERCENT OF
- 2. USE VIBRATION AND SHOCK-RESISTANT FASTENERS FOR ATTACHMENTS TO CONCRETE

## ELECTRICAL IDENTIFICATION:

- A. UPDATE AND PROVIDE TYPED CIRCUIT BREAKER SCHEDULES IN THE MOUNTING BRACKET, INSIDE DOORS
- BRANCH CIRCUITS FEEDING AVIATION OBSTRUCTION LIGHTING EQUIPMENT SHALL BE CLEARLY IDENTIFIED AS SUCH AT THE BRANCH CIRCUIT PANELBOARD.

# SECTION 26 200 - ELECTRICAL MATERIALS AND EQUIPMENT

- A. RIGID GALVANIZED STEEL (RGS) CONDUIT SHALL BE USED FOR EXTERIOR LOCATIONS ABOVE GROUND AND IN UNFINISHED INTERIOR LOCATIONS AND FOR UNDERGROUND RUNS. RIGID CONDUIT AND FITTINGS SHALL BE STEEL, COATED WITH ZINC EXTERIOR AND INTERIOR BY THE HOT DIP GALVANIZING PROCESS, CONDUIT SHALL BE PRODUCED TO ANSI SPECIFICATIONS CO. I, FEDERAL SPECIFICATION WW-C-58 I AND SHALL BE LISTED WITH THE UNDERWRITERS' LABORATORIES, FITTINGS SHALL BE THREADED - SET SCREW OR COMPRESSION FITTINGS WILL NOT BE ACCEPTABLE. RGS CONDUITS SHALL BE MANUFACTURED BY ALLIED, REPUBLIC OR WHEATLAND.
- B. UNDERGROUND CONDUIT IN CONCRETE SHALL BE POLYVINYLCHLORIDE (PVC) SUITABLE FOR DIRECT BURIAL AS APPLICABLE. JOINTS SHALL BE BELLED, AND FLUSH SOLVENT WELDED IN ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS. CONDUIT SHALL BE CARLON ELECTRICAL PRODUCTS OR APPROVED
- C. TRANSITIONS BETWEEN PVC AND RIGID (RGS) SHALL BE MADE WITH PVC COATED METALLIC LONG SWEEP
- D. FMT OR RIGID GALVANIZED STEEL CONDUIT MAY BE LISED IN FINISHED SPACES CONCEALED IN WALLS AND CEILINGS. EMT SHALL BE MILD STEEL, ELECTRICALLY WELDED, ELECTRO-GALVANIZED OR HOT-DIPPED GALVANIZED AND PRODUCED TO ANSI SPÉCIFICATION C80.3, FEDERAL SPÉCIFICATION WW-C-563, AND SHALL BE UL LISTED. EMT SHALL BE MANUFACTURED BY ALLIED, REPUBLIC OR WHEATLAND, OR APPROVED EQUAL. FITTINGS SHALL BE METALLIC COMPRESSION. SET SCREW CONNECTIONS SHALL NOT
- LIQUID TIGHT FLEXIBLE METALLIC CONDUIT SHALL BE USED FOR FINAL CONNECTION TO EQUIPMENT. FITTINGS SHALL BE METALLIC GLAND TYPE COMPRESSION FITTINGS, MAINTAINING THE INTEGRITY OF CONDUIT SYSTEM. SET SCREW CONNECTIONS SHALL NOT BE ACCEPTABLE. MAXIMUM LENGTH OF FLEXIBLE CONDUIT SHALL NOT EXCED G-FEET. LFMC SHALL BE PROTECTED AND EXPORTED AS REQUIRED BY NEC. MANUFACTURERS OF FLEXIBLE CONDUITS SHALL BE CAROL, ANACONDA METAL HOSE OR UNIVERSAL METAL HOSE, OR APPROVED EQUAL.
- F. MINIMUM SIZE CONDUIT SHALL BE 3/4 INCH (2 I MM).

# HUBS AND BOXES:

- A. AT ENTRANCES TO CABINETS OR OTHER EQUIPMENT NOT HAVING INTEGRAL THREADED HUBS PROVIDE METALLIC THREADED HUBS OF THE SIZE AND CONFIGURATION REQUIRED. HUB SHALL INCLUDE LOCKNUT AND NEOPRENE O-RING SEAL. PROVIDE IMPACT RESISTANT 105 DEGREE C PLASTIC BUSHINGS TO PROTECT CABLE INSULATION.
- B. CABLE TERMINATION FITTINGS FOR CONDUIT
  - CABLE TERMINATORS FOR RGS CONDUITS SHALL BE TYPE CRC BY O-Z/GEDNEY OR EQUAL BY
  - CABLE TERMINATORS FOR LFMC SHALL BE ETCO CL2075; OR MADE FOR THE PURPOSE PRODUCTS BY ROXTEC
- C. EXTERIOR PULL BOXES AND PULL BOXES IN INTERIOR INDUSTRIAL AREAS SHALL BE PLATED CAST ALLOY HEAVY DUTY, WEATHERPROOF, DUST PROOF, WITH GASKET, PLATED IRON ALLOY COVER AND STAINLESS STEEL COVER SCREWS, CROUSE-HINDS WAB SERIES OR EQUAL.
- CONDUIT OUTLET BODIES SHALL BE PLATED CAST ALLOY WITH SIMILAR GASKET COVERS. OUTLET BODIES SHALL BE OF THE CONFIGURATION AND SIZE SUITABLE FOR THE APPLICATION. PROVIDE CROUSE-HINDS FORM 8 OR EQUAL
- E. MANUFACTURER FOR BOXES AND COVERS SHALL BE HOFFMAN, SQUARE "D", CROUSE-HINDS, COOPER, ADALET, APPLETON, O-Z GEDNEY, RACO, OR APPROVED EQUAL.

# SUPPLEMENTAL GROUNDING SYSTEM:

- A. FURNISH AND INSTALL A SUPPLEMENTAL GROUNDING SYSTEM TO THE EXTENT INDICATED ON THE DRAWINGS, SUPPORT SYSTEM WITH NON-MAGNETIC STAINLESS STEEL CLIPS WITH RUBBER GROMMETS. GROUNDING CONNECTORS SHALL BE TINNED COPPER WIRE, SIZES AS INDICATED ON THE DRAWINGS. PROVIDE STRANDED OR SOLID BARE OR INSULATED CONDUCTORS EXCEPT AS OTHERWISE NOTED.
- B. SUPPLEMENTAL GROUNDING SYSTEM: ALL CONNECTIONS TO BE MADE WITH CAD WELDS. EXCEPT AT EQUIPMENT USE LUGS OR OTHER AVAILABLE GROUNDING MEANS AS REQUIRED BY MANUFACTURER; AT GROUND BARS USE TWO HOLE SPADES WITH NO-OX.
- C. STOLEN GROUND-BARS: IN THE EVENT OF STOLEN GROUND BARS, CONTACT SPRINT CM FOR REPLACEMENT INSTRUCTION USING THREADED ROD KITS.

# EXISTING STRUCTURE:

A. EXISTING EXPOSED WIRING AND ALL EXPOSED OUTLETS, RECEPTACLES, SWITCHES, DEVICES, BOXES, AND OTHER EQUIPMENT THAT ARE NOT TO BE UTILIZED IN THE COMPLETED PROJECT SHALL BE REMOVED OR DE-ENERGIZED AND CAPPED IN THE WALL, CEILING, OR FLOOR SO THAT THEY ARE CONCEALED AND SAFE. WALL, CEILING, OR FLOOR SHALL BE PATCHED TO MATCH THE ADJACENT CONSTRUCTION

## CONDUIT AND CONDUCTOR INSTALLATION:

A.CONDUITS SHALL BE FASTENED SECURELY IN PLACE WITH APPROVED NON-PERFORATED STRAPS AND HANGERS, EXPLOSIVE DEVICES FOR ATTACHING HANGERS TO STRUCTURE WILL NOT BE PERMITTED.
CLOSELY FOLLOW THE LINES OF THE STRUCTURE, MAINTAIN CLOSE PROXIMITY TO THE STRUCTURE AND KEEP CONDUITS IN TIGHT ENVELOPES. CHANGES IN DIRECTION TO ROUTE AROUND OBSTACLES SHALL BE MADE WITH CONDUIT OUTLET BODIES. CONDUIT SHALL BE INSTALLED IN A NEAT AND WORKMANLIKE MANNER, PARALLEL AND PERPENDICULAR TO STRUCTURE WALL AND CEILING LINES. ALL CONDUIT SHALL BE FISHED TO CLEAR OBSTRUCTIONS. ENDS OF CONDUITS SHALL BE TEMPORARILY CAPPED TO PREVENT CONCRETE, PLASTER OR DIRT FROM ENTERING. CONDUITS SHALL BE RIGIDLY CLAMPED TO BOXES BY GALVANIZED MALLEABLE IRON BUSHING ON INSIDE AND GALVANIZED MALLEABLE IRON LOCKNUT ON

B.CONDUCTORS SHALL BE PULLED IN ACCORDANCE WITH ACCEPTED GOOD PRACTICE.



6580 SPRINT PARKWAY **OVERLAND PARK, KANSAS 66251** 



1120 Dallas Street, Sauk City, WI 53583 Phone: 608-643-4100 Fax: 608-643-7999 www.Ramaker.com



**48 SPRUCE STREET** OAKLAND, NJ 07346

ertification \$ Seal:

hereby certify that this plan, specification, or report was pre y me or under my direct supervision and that I am a duly License. Professional Engineer under the laws of the State of <u>Connecticut</u>



DATE 10/08/2014 FINAL

# WETHERSFIELD COLO SITE#:CT58XC967

23 KELLEHER COURT-FIREHOUSE#3 WETHERSFIELD, CT 06 I 09 HARTFORD COUNTY

SPRINT SPECIFICATIONS

SCALE: NONE

28752 SP-3 SHEET

Sprint

6580 SPRINT PARKWAY OVERLAND PARK, KANSAS 66251



1120 Dallas Street, Sauk City, WI 53583 Phone: 608-643-4100 Fax: 608-643-7999 www.Ramaker.com

# Transcend Wireless

48 SPRUCE STREET OAKLAND, NJ 07346

# Certification & Seal: I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut. CONN SKO No. 26266 CENS ONA Signature: 10/08/20 I Date:

WETHERSFIELD COLO SITE#:CT58XC967

DATE ISSUED 10/08/2014

PROJECT INFORMATION:
23 KELLEHER COURT-FIREHOUSE#3
WETHERSFIELD, CT 06 I 09
HARTFORD COUNTY

SITE PLAN

0	5' '	10'	20'
11" × 17" 22" × 34"		" = 10'  " = 5'	
PROJECT NUMBER		28752	
SHEET NUMBER		A- I	





6580 SPRINT PARKWAY OVERLAND PARK, KANSAS 66251



1120 Dallas Street, Sauk City, WI 53583 Phone: 608-643-4100 Fax: 608-643-7999 www.Ramaker.com

# Transcend Wireless

48 SPRUCE STREET OAKLAND, NJ 07346

# Certification & Seal: I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut. CONVENTION OF THE PROPERTY OF THE PROPERTY

RK DATE DESCRIPTION

BUE ASE FINAL DATE ISSUED 10/08/2014

DUECT TITLE:


# WETHERSFIELD COLO SITE#:CT58XC967

PROJECT INFORMATION:
23 KELLEHER COURT-FIREHOUSE#3
WETHERSFIELD, CT 06 | 09
HARTFORD COUNTY


SHEET TITLE:


EQUIPMENT PLAN

0		1.8	75' I	3.7	75' I	7.5	7
							-1
1 I 22	" x 2" x	17" 34"			3.75' 1.875'		
PRC NUN	JECT JBER				28752		7
SH	IEET //BER				A-2		٦,




EQUIPMENT PLAN
SCALE: I" = 3.75'






EXISTING ANTENNA ARRAY



- I" = 50' - I" = 25'

11" x 17" 22" x 34"





6580 SPRINT PARKWAY OVERLAND PARK, KANSAS 66251



1120 Dallas Street, Sauk City, WI 53583 Phone: 608-643-4100 Fax: 608-643-7999 www.Ramaker.com



48 SPRUCE STREET OAKLAND, NJ 07346

## ertification ¢ Seal:

I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of <u>Connecticut</u>.



MARK DATE DESCRIPTION
ISSUE FINAL DATE ISSUED 10/08/2014
PROJECT TILE:

# WETHERSFIELD COLO SITE#:CT58XC967

PROJECT INFORMATION:
23 KELLEHER COURT-FIREHOUSE#3
WETHERSFIELD, CT 06 | 09
HARTFORD COUNTY

HEET TITLE:

BUILDING ELEVATIONS \$
ANTENNA DETAILS

SCALE: AS NOTED

PROJECT 28752
SHEET A-3

# **RFDS Sheet**

# **General Site Information**

Site ID	CT58XC967
Market	Northern Connecticut
Region	Northeast
MLA	N/A
Structure Type	monopole
BTS Type	

Alcatel-Lucent **Equipment Vendor** Lattitude 41.715444 -72.690556 Longitude LL SITE ID N/A

Solution ID

Siterra SR Equipment type **Equipment Vendor** Alcatel-Lucent

Incremental Power Draw needed by added Equipment N/A

None

N/A

N/A

N/A

# **Base Equipment**

BBU Kit	
BBU Kit Qty	

ALU BBU Kit
1

None N/A

N/A N/A

0.315

1.3'

Top Hat
Top Hat Qty
op Hat Dimenstions
op Hat Weight (lbs)

**Growth Cabinet** 

Growth Cabinet Qty
<b>Growth Cabinet Dimensions</b>
Growth Cabinet Weight

# RF Path Information

RF Path Information	
RRH	TD-RRH8x20-25
RRH Qty	3
RRH Dimensions	26.1"x18.6"x6.7"
RRH Weight. lbs.	70
RRH Mount Weight. Lbs.	10
Power and Fiber Cable	ALU HYBRID CABLE
Cable Qty	1
Weight per foot. Lbs.	1.05
Diameter. Inches.	1.24
Length Ft.	210
Coax Jumper	0.625
Coax Jumper Qty	27
Coax Jumper Length. Feet.	8
Coax Jumper Weight	1.7
Coax Jumper Diameter. Inches	0.5
AISG Cable	COMMSCOPE ATCB-B01-006

(calculated as antenna height plus 20%)

# **Antenna Sector Information**

Weight of entire AISG cable. Lbs.

AISG Cable Qty

AISG Cable length.

AISG Diameter. Inches.

Antenna make/model
Antenna qty
Antenna Dimensions. Inches
Antenna Weight. Lbs
Antenna Mounting Kit Weight. Lbs.
CL Height
Antenna Azimuth
Antenna Mechanical Downtilt

Sector 1	Sector 2	Sector 3
RFS APXV9TM14-ALU-I20	RFS APXV9TM14-ALU-I20	RFS APXV9TM14-ALU-I20
1	1	1
56.3"x12.6"x6.3"	56.3"x12.6"x6.3"	56.3"x12.6"x6.3"
55.12	55.12	55.12
11.5	11.5	11.5
*174	*174	*174
340	140	230
0	0	0
-2	-2	-2

Antenna etilt

RFDS SHEET WAS GENERATED BY RAMAKER & ASSOCIATES FROM PLAN OF RECORD (POR) PROVIDED BY SPRINT. CONTRACTOR SHALL VERIFY AND OBTAIN FINAL RFDS FROM SPRINT CONSTRUCTION MANAGER PRIOR TO CONSTRUCTION.

# NOTES:

- I. GENERAL CONTRACTOR TO FIELD VERIFY AZIMUTH AND C/L HEIGHT AND MECHANICAL DOWNTILT. IF DIFFERENT THAN CALLED OUT BELOW, HALT ANTENNA WORK FOR ONE HOUR, CALL SPRINT RF ENGINEER (OR MANAGER IF RF ENGINEER DOES NOT ANSWER, BUT STILL LEAVE A MESSAGE TO RF ENGINEER) USING CONTACT INFORMATION ABOVE FOR FURTHER INSTRUCTIONS. IF SPRINT DOES NOT RESPOND WITHIN ONE HOUR, PLACE 2.5GHZ ANTENNA AT SAME C/L HEIGHT AS PLACE 2.56H2 ANI ENNA A1 5AME (J. HEIGH1 A5 1.96H2 ANTENNA AND EMAIL CORRECT C/L HEIGHT AND AZIMUTH TO SPRINT RF ENGINEER. UPDATE AS-BUILD DRAWING WITH CORRECT C/L HEIGHT. ALSO EMAIL CORRECT 1.96H2 AND 800MHZ ANTENNA C/L HEIGHT, AZIMUTH AND MECHANICAL DOWNTILT TO RF ENCINEER. ENGINEER.
- AISG TESTS TO VERIPY OPERATION IS TO BE
  PERFORMED AFTER FINAL INSTALLATION OF ANTENNAS
  AND AISG CABLES HAVE BEEN CONNECTED. VERIPY OPERATION OF ALL EXISTING SPRINT AISG EQUIPMENT INCLUDING 800MHZ, I.9GHZ AND 2.5GHZ. TEST TO INCLUDE COMPLETE DOWNTILT, AZIMUTH (IF APPLICABLE) AND BEAMWIDTH SWINGS (IF APPLICABLE). DOCUMENT AISG TEST RESULTS IN COAX SWEEP TEST SPREADSHEET.
- 3. GENERAL CONTRACTOR MUST ENSURE THAT NO OBJECT 19 LOCATED WITHIN 45 DEGREES OF LEFT AND RIGHT OF FRONT OF ANTENNA OR 7 DEGREES UP AND DOWN FROM CENTER OF ANTENNA. IF THIS IS NOT POSSIBLE, CONTACT RF ENGINEER FOR FURTHER INSTRUCTION. IN ADDITION, 2.5GHZ ANTENNA IS NOT TO BE PLACED IN FRONT OF ANY OTHER ANTENNA
  USING THE SAME 45 DEGREE RULE. THIS INCLUDES SPRINT AND NON-SPRINT ANTENNAS.
- 4. 2.5GHZ ANTENNA MUST BE AT LEAST 6" FROM 1.9GHZ ANTENNA, 30" FROM 800MHZ ANTENNA AND 30" FROM DUAL BAND I .9GHZ AND 800MHZ ANTENNA.
- 5. GENERAL CONTRACT IS REQUIRED TO USE A DIGITAL ALIGNMENT TOOL TO SET AZIMUTH, ROLL AND DOWNTILT. AZIMUTH ACCURACY IS TO BE WITHIN I DEGREE. DOWNTILT AND ROLL (LEFT TO RIGHT TILT) IS TO BE WITHIN O. I DEGREES. IF FOR SOME REASON THIS ACCURACY CANNOT BE ACHIEVED LIPDATE AS-BUILT DRAWINGS AND EMAIL SPRINT RF ENGINEER
  WITH AS-BUILT SETTINGS. USE 3Z RF ALIGNMENT TOOL OR EQUIVALENT TOOL.



6580 SPRINT PARKWAY **OVERLAND PARK, KANSAS 66251** 



1120 Dallas Street, Sauk City, WI 53583 Phone: 608-643-4100 Fax: 608-643-7999 www.Ramaker.com



**48 SPRUCE STREET** OAKLAND, NJ 07346

## ertification \$ Seal:

hereby certify that this plan, specification, or report was prepare by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of <u>Connecticut</u>.



MARK	DATE	DESCRIPTION

SUE FINAL

DATE ISSUED 10/08/2014

# WETHERSFIELD COLO SITE#:CT58XC967

23 KELLEHER COURT-FIREHOUSE#3 WETHERSFIELD, CT 06 I 09 HARTFORD COUNTY

RF DATA SHEET


SCALE: AS NOTED

28752 A-4 SHEET

<sup>\*</sup> PER ACTUAL FIELD CONDITIONS

8T8R DETAIL


(3)



200 to 325 Feet / Three (3) to Six (6) Existing RRHs **Existing SNV Hybriflex** Alpha 8 AWG Power **Existing SNV Hybriflex** Beta 8 AWG Power 800 MHz Beta 1900 MHz Existing SNV Hybriflex Gamma 8 AWG Power Gamma 800 MHz Alpha 2.5 GHz Beta 2.5 GHz 6 AWG Power Gamma 2.5 GHz

> RRH TO DISTRIBUTION BOX POWER CONNECTIVITY DETAIL SCALE: NTS





Gamma Beta Alpha C2 C2 C1 SPARE SPARE MPO Connectors See BTS to Distribution Box **Fiber Connectivity** 

RRH TO DISTRIBUTION BOX FIBER CONNECTIVITY DETAIL

Sprint

6580 SPRINT PARKWAY **OVERLAND PARK, KANSAS 66251** 



1120 Dallas Street, Sauk City, WI 53583 Phone: 608-643-4100 Fax: 608-643-7999 www.Ramaker.com



**48 SPRUCE STREET** OAKLAND, NJ 07346

hereby certify that this plan, specification, or report was prepare, by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of <u>Connecticut</u>.



FINAL DATE ISSUED 10/08/2014


# WETHERSFIELD COLO SITE#:CT58XC967

23 KELLEHER COURT-FIREHOUSE#3 WETHERSFIELD, CT 06 I 09 HARTFORD COUNTY

FIBER PLUMBING DIAGRAM

SCALE: AS NOTED

28752 SHEET A-5





BTS TO DISTRIBUTION BOX FIBER CONNECTIVITY DETAIL


2.5			
<b>FREQUENCY</b>	INDICATOR		ID
2500 -1	YEL	WHT	GRN
2500 -2	YEL	WHT	RED
2500 -3	YEL	WHT	BRN
2500 -4	YEL	WHT	BLU
2500 -5	YEL	WHT	SLT
2500 -6	YEL	WHT	ORG
2500 -7	YEL	WHT	WHT
2500 -8	YEL	WHT	PPL


NV		
FREQUENCY	INDICATOR	ID
800-1	YEL	GRN
1900-1	YEL	RED
1900-2	YEL	BRN
1900-3	YEL	BLU
1900-4	YEL	SLT
800-1	YEL	ORG
RESERVED	YEL	WHT
RESERVED	YEL	PPL

			Second	
Sector	Cable	First Ring	Ring	Third Ring
1 Alpha	1	Green	No Tape	No Tape
1	2		No Tape	No Tape
1	3	Brown	No Tape	No Tape
1	4	White	No Tape	No Tape
1	5	Red	No Tape	No Tape
1	6	Grey	No Tape	No Tape
1	7	Purple	No Tape	No Tape
1	8	Orange	No Tape	No Tape
2 Beta	1	Green	Green	No Tape
2	2			No Tape
2	3	Brown	Brown	No Tape
2	4	White	White	No Tape
2	5	Red	Red	No Tape
2	6	Grey	Grey	No Tape
2	7	Purple	Purple	No Tape
2	8	Orange	Orange	No Tape
3 Gamma	1	Green	Green	Green
3	2			Blue
3	3	Brown	Brown	Brown
3	4	White	White	White
3	5	Red	Red	Red
3	6	Grey	Grey	Grey
3	7	Purple	Purple	Purple
3	8	Orange	Orange	Orange









COLOR CODING CHARTS
SCALE: NTS

# CABLE MARKING NOTES

- ALL CABLES SHALL BE MARKED WITH 2" WIDE, UV STABILIZED, UL APPROVED TAPE.
- THE FIRST RING SHALL BE CLOSEST TO THE END OF THE CABLE AND SPACED APPROXIMATELY 2" FROM THE END CONNECTOR, WEATHERPROOFING, OR BREAKOUT UNIT. THERE SHALL BE 1" SPACE BETWEEN EACH RING.
- 3. A 2" GAP SHALL SEPARATE THE CABLE COLOR CODE FROM THE FREQUENCY COLOR CODE. THE 2" COLOR RINGS FOR THE FREQUENCY CODE SHALL BE PLACED NEXT TO EACH OTHER WITH NO SPACES.
- 4. THE 2" COLORED TAPE(S) SHALL BE WRAPPED A MINIMUM OF 3 TIMES AROUND THE INDIVIDUAL CABLES, AND THE TAPE SHALL BE KEPT IN THE SAME LOCATION AS MUCH AS POSSIBLE.
- 5. SITES WITH MORE THAN FOUR (4) SECTORS WILL REQUIRE ADDITIONAL RINGS FOR EACH SECTOR, FOLLOWING THE PATTERN. HIGH CAPACITY SITES WILL USE THE SECOND CABLE IDENTIFIED BY BLUE BANDS OF TAPE
- G. HYBRID FIBER CABLE SHALL BE SECTOR IDENTIFIED INSIDE THE CABINET ON FREQUENCY BUNDLES, ON THE SEALTITE, ON THE MAIN LINE UPON EXIT OF SEALTITE, AND BEFORE AND AFTER THE BREAKOUT UNIT (MEDUSA), AS WELL AS BEFORE AND AFTER ANY ENTRANCE OR EXIT.
- HFC "MAIN TRUNK" WILL NOT BE MARKED WITH THE FREQUENCY CODES, AS IT CONTAINS ALL FREQUENCIES.
- INDIVIDUAL POWER PAIRS AND FIBER BUNDLES
   SHALL BE LABELED WITH BOTH THE CABLE AND
   FREQUENCY.



6580 SPRINT PARKWAY OVERLAND PARK, KANSAS 66251



1120 Dallas Street, Sauk City, WI 53583 Phone: 608-643-4100 Fax: 608-643-7999 www.Ramaker.com



48 SPRUCE STREET OAKLAND, NJ 07346

## ertification \$ Seal:

I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of <u>Connecticut</u>.



RK DATE DESCRIPTION

DATE SSUED 10/08/2014

# WETHERSFIELD COLO SITE#:CT58XC967

PROJECT INFORMATION:
23 KELLEHER COURT-FIREHOUSE#3
WETHERSFIELD, CT 06 | 09
HARTFORD COUNTY

SHEET TITL

CABLE COLOR CODING

SCALE: AS NOTED

PROJECT 28752
SHEET A-6

FIBER ONLY

4 AWG POWER

# HYBRID CABLE DC CONDUCTOR SIZE GUIDELINE

CABLE	LENGTH	DC CONDUCTOR	CABLE DIAMETER
Fiber Only	Varies	Use NV Hybriflex	5/8"
Hybriflex	<200'	8 AWG	1-1/4"
Hybriflex	225-300'	6 AWG	1-1/4"
Hybriflex	325-375'	4 AWG	1-1/4"

# RFS HYBRIFLEX RISER CABLE SCHEDULE

FIBER ONLY (EXISTING DC POWER)	Hybrid cable	
	MN:HB058-M12-050F	
	12x multi-mode fiber pairs, Top:Outdoor protected connectors, Bottom:LC	50 ft
	Connectors, 5/8 cable, 50 ft	
	MN:HB058-M12-075F	75 ft
	MN:HB058-M12-100F	100 ft
	*MN:HB058-M12-125F	125 ft
	MN:HB058-M12-150F	150 ft
	MN:HB058-M12-175F	175 ft
	MN:HB058-M12-200F	200 ft
8 AWG Power	Hybrid cable	
	MALLIDAMA OCCUPANO OCCE	1

3x 8 AWG power pairs, 12x multi-mode fiber pairs, Outdoor rated connectors & LC connectors. 1 1/4 cable, 50 ft

MN:HB114-08U3M12-075F

MN:HB114-08U3M12-100F

Hybrid Jumper cable MN:HBF012-M3-5F1

	WINTER 14-0005W172-125F	12511
	MN:HB114-08U3M12-150F	150 ft
	MN:HB114-08U3M12-175F	175 ft
	MN:HB114-08U3M12-200F	200 ft
6 AWG Power	Hybrid cable	
	MN:HB114-13U3M12-225F	225 ft
	3x 6 AWG power pairs, 12x multi-mode fiber pairs, Outdoor rated connectors & LC connectors. 1 1/4 cable, 225 ft	
	MN:HB114-13U3M12-250F	250 ft
	MN:HB114-13U3M12-275F	275 ft
	MN:HB114-13U3M12-300F	300 ft
4 AWG Power	Hybrid cable	
	MN:HB114-21U3M12-325F	325 ft

AWG Power	Hybrid cable		
	MN:HB114-21U3M12-325F	325 ft	
	3x 4 AWG power pairs, 12x multi-mode fiber pairs, Outdoor rated connectors & LC connectors. 1 1/4 cable, 325 ft		
	MN:HB114-21U3M12-350F	350 ft	
	MN:HB114-21U3M12-375F	375 ft	

# RFS HYBRIFLEX JUMPER CABLE SCHEDULE

	5 ft, 3x multi-mode fiber pairs, Outdoor & LC connectors, 1/2 cable		
	MN:HBF012-M3-10F1	10 ft	
	*MN:HBF012-M3-15F1	15 ft	
	SPECIAL INSTALLATION NOTE:		
	JUMPERS FROM 2.5 RRH TO 2.5 ANTENNA SHALL NOT EXCEED 15'		
	NOTIFY SPRINT CM OF ANY DISCREPANCY		
8 AWG POWER	Hybrid Jumper cable		
	MN:HBF058-08U1M3-5F1	5.ft	
	5 ft, 1x 8 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC connectors, 5/8 cable	311	
	MN:HBF058-08U1M3-10F1	10 ft	
	MN:HBF058-08U1M3-15F1	15 ft	
	SPECIAL INSTALLATION NOTE:		
	JUMPERS FROM 2.5 RRH TO 2.5 ANTENNA SHALL NOT EXCEED 15'		
	NOTIFY SPRINT CM OF ANY DISCREPANCY		
6 AWG POWER	Hybrid Jumper cable		
	MN:HBF058-13U1M3-5F1		
	5 ft, 1x 6 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC connectors, 5/8 cable	5 ft	

SPECIAL INSTALLATION NOTE

Hybrid Jumper cable

MN:HBF078-21U1M3-5F1

connectors, 7/8 cable MN:HBF078-21U1M3-10F1


MN:HBF078-21U1M3-15F1

SPECIAL INSTALLATION NOTE

NOTIFY SPRINT CM OF ANY DISCREPANCY

NOTIFY SPRINT CM OF ANY DISCREPANCY

5 ft, 1x 4 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC



50 ft


75 ft


100 ft


5 ft

\*NOTE: SPRINT CM TO CONFIRM HYBRID/FIBER RISER CABLE & HYBRID/FIBER JUMPER CABLE MODEL NUMBERS BEFORE PREPARING BOM.


HYBRID CABLE CROSS SECTION \$ DATA SCALE: NTS







# RFS: APXV9TM | 4-ALU- | 20



56.3" x 12.6" x 6.3" DIMENSIONS, HxWxD:

WEIGHT, WITHOUT PRE-MOUNTED BRACKETS: 55.12 lbs.

CONNECTOR: (9) XX" MINI-DIN FEMALE/BOTTOM



6580 SPRINT PARKWAY **OVERLAND PARK, KANSAS 66251** 



1120 Dallas Street, Sauk City, WI 53583 Phone: 608-643-4100 Fax: 608-643-7999 www.Ramaker.com



48 SPRUCE STREET OAKLAND, NJ 07346

## ertification \$ Seal:

hereby certify that this plan, specification, or report was prepare, by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of <u>Connecticut</u>.



FINAL DATE ISSUED 10/08/2014


WETHERSFIELD COLO SITE#:CT58XC967

23 KELLEHER COURT-FIREHOUSE#3 WETHERSFIELD, CT 06 I 09 HARTFORD COUNTY

ANTENNA \$ HYBRID CABLE DETAILS

SCALE: AS NOTED

28752 SHEET A-7



2.5 ANTENNA DETAIL

SCALE: NTS


BOTTOM VIEW


ALCATEL-LUCENT: TD-RRH8x20-25

 $HxWxD = (26.1" \times 18.6" \times 6.7")$ 


WEIGHT = 70 lbs.


2.5 RRH DETAIL SCALE: NTS





BASE PLATE MODIFICATIONS







6580 SPRINT PARKWAY OVERLAND PARK, KANSAS 66251



1120 Dallas Street, Sauk City, WI 53583 Phone: 608-643-4100 Fax: 608-643-7999 www.Ramaker.com

# Transcend Wireless

**48 SPRUCE STREET** OAKLAND, NJ 07346

# ertification \$ Seal: hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of <u>Connecticut</u>.

WETHERSFIELD COLO SITE#:CT58XC967

DATE ISSUED 10/08/2014

23 KELLEHER COURT-FIREHOUSE#3 WETHERSFIELD, CT 06 I 09 HARTFORD COUNTY

HASE FINAL


STRUCTURAL DETAILS

SCALE: AS NOTED

> 28752 S-1 SHEET

STIFFNER PLATE SIDE ELEVATION VIEW SCALE: NTS

SCALE: NTS



PROVIDE NEW GROUND FOR 2.5 ANTENNA PIPE MOUNT TO EXISTING SECTOR GROUND BAR (USE EXISTING GROUND IF PRESENT) INSTALL SPRINT 2.5 EXISTING SPRINT NETWORK ANTENNA & RRH UNIT (TYP. PER VISION ANTENNA (TYP. OF I PER SECTOR) SECTOR) EXISTING SPRINT SECTOR PROVIDE NEW GROUND CONNECTION FOR 2.5 RRH TO EXISTING SECTOR GROUND BAR (TYP. EACH SECTOR) GROUND BAR TO BE UTILIZED, TYP. PROVIDE NEW GROUND FOR HYBRID . BREAKOUT UNIT TO EXISTING SECTOR GROUND BAR

ANTENNA GROUNDING DETAIL

GROUNDING NOTES:

- I. CONTRACTOR TO ENSURE PROPER SEQUENCING OF GROUNDING AND UNDERGROUND CONDUIT INSTALLATION TO PREVENT ANY LOSS OF CONTINUITY IN THE GROUNDING SYSTEM AND/OR DAMAGE TO THE CONDUIT.
- 2. ALL EXTERIOR GROUND CONDUCTORS SHALL BE #2 AWG SOLID TINNED COPPER UNLESS NOTED OTHERWISE.
  3. ALL GROUND CONNECTIONS BELOW GRADE SHALL BE EXOTHERMIC (CADWELD).
- ALL GROUND CONNECTIONS DELOW GRADE SHALL BE LASTHERNIC (CAUNLES).

   ALL GROUND CONNECTIONS ABOVE GRADE AND/OR INTERIOR SHALL BE COMPRESSION TYPE, TWO-HOLE LUGS OR DOUBLE-CRIMP "C" TAPS.

   CONTACT AREAS WHERE CONNECTIONS ARE MADE SHALL BE PREPARED TO A BARE.
- BRIGHT FINISH AND COATED WITH AN ANTI-OXIDATION MATERIAL BEFORE CONNECTIONS ARE MADE.
- 6. MAXIMUM RESISTANCE OF THE COMPLETED GROUND SYSTEM SHALL NOT EXCEED 5 OHMS.
- 7. WHERE GROUNDING CONNECTIONS ARE MADE TO PAINTED METAL SURFACES, PAINT SHALL BE REMOVED TO BEAR METAL TO ENSURE PROPER CONTACT AND RESTORED/PAINTED TO ORIGINAL FINISH.
- 8. GROUND DEPTH SHALL BE 30" MINIMUM BELOW FINISHED GRADE, OR 6" BELOW FROST LINE, WHICHEVER IS GREATER.

LEGEND:		
	EXISTING GROUND CABLE	
	PROPOSED GROUND CABLE	
<b>A</b>	MECHANICAL CONNECTION	
	EXOTHERMIC CONNECTION	
— E — E — E —	PROPOSED ELECTRIC	



6580 SPRINT PARKWAY OVERLAND PARK, KANSAS 66251



1120 Dallas Street, Sauk City, WI 53583 Phone: 608-643-4100 Fax: 608-643-7999 www.Ramaker.com



48 SPRUCE STREET OAKLAND, NJ 07346

ertification \$ Seal:

I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of <u>Connecticut</u>.



MARK DATE DESCRIPTION

SUE FINAL

WETHERSFIELD COLO SITE#:CT58XC967

DATE 10/08/2014

WETHERSFIELD, CT OG I O9
HARTFORD COUNTY

SHEET TITLE:

EQUIPMENT UTILITY & GROUNDING PLAN

SCALE: AS NOTED

PROJECT 28752
SHEET E-I

LECEND


SCALE: NTS

- KOPR SHIELD #4 OR #6 AWG SOLID CU CONDUCTOR WITH GREEN, GOOV THWN-2 INSULATION EXISTING GROUND -EXISTING CADWELD TO EXISTING GROUND SOURCE TWO HOLE SPADE TO BE USED TO CONNECT TO GROUND BAR - FLAT WASHERS ON BOTH SIDES OF BUSS BAR

NOTES:
I. APPLY NO-OX TO LUG AND GROUND BAR CONTACT SURFACE. DO NOT COAT INLINE LUG.

2. IF STOLEN GROUND BARS ARE ENCOUNTERED, CONTACT SPRINT CM FOR REPLACEMENT THREADED

GROUNDING CONDUCTOR INSTALLATION



TWO-HOLE LUG

SCALE: NTS



6580 SPRINT PARKWAY **OVERLAND PARK, KANSAS 66251** 



1120 Dallas Street, Sauk City, WI 53583 Phone: 608-643-4100 Fax: 608-643-7999 www.Ramaker.com



**48 SPRUCE STREET** OAKLAND, NJ 07346

ertification \$ Seal:

hereby certify that this plan, specification, or report was prepare, by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of <u>Connecticut</u>.



FINAL DATE ISSUED 10/08/2014

# WETHERSFIELD COLO SITE#:CT58XC967

23 KELLEHER COURT-FIREHOUSE#3 WETHERSFIELD, CT 06 I 09 HARTFORD COUNTY

GROUNDING DETAILS

SCALE: AS NOTED

28752 E-2 SHEET

GROUNDING RISER DIAGRAM

