

# STATE OF CONNECTICUT

## CONNECTICUT SITING COUNCIL

Ten Franklin Square, New Britain, CT 06051

Phone: (860) 827-2935 Fax: (860) 827-2950

E-Mail: [siting.council@ct.gov](mailto:siting.council@ct.gov)

[www.ct.gov/csc](http://www.ct.gov/csc)

VIA ELECTRONIC MAIL

February 6, 2020

Ryan G. Bailey  
Charles Cherundolo Consulting  
1280 Route 46 West, Suite 9  
Parsippany, NJ 07054

RE: **EM-SPRINT-161-191211** – Sprint notice of intent to modify an existing telecommunications facility located at 24 ½ Richdale Drive, Wilton, Connecticut.

Dear Mr. Bailey:

The Connecticut Siting Council (Council) received a notice of intent to modify the above-referenced facility on December 11, 2019. On December 17, 2019, the Council issued a letter (enclosed) stating that the request for exempt modification was incomplete because of the following deficiencies:

- 1) The Construction Drawings (CD) provided in the electronic filing was for a site at Round Hill Road in Greenwich;
- 2) No Structural Analysis (SA) had been provided for this request;
- 3) No Mount Analysis (MA) was included with the request for exempt modification; therefore, it is unclear whether the proposed antenna mount was capable of supporting the proposed equipment load;
- 4) The request lacked proof that the entire request for exempt modification was physically mailed to the underlying property owner;
- 5) The exempt modification request lacked documentation of the original facility approval and any conditions of such approval or correspondence with the Town of Wilton stating that the town no longer retains records of its decision; and
- 6) A property card and parcel map for the underlying property had not been provided with the request.

The Council recommended that Charles Cherundolo Consulting provide an electronic copy of the CD for the above-referenced facility, a passing ( $\leq 100\%$ ) SA and MA for the proposed modification that is stamped and signed by a professional engineer duly licensed in the State of Connecticut, a property card and parcel map for the underlying property, documentation showing the original facility approval with conditions if any or correspondence with the Town stating that there are no records of the original facility approval and proof of proper notice of this exempt modification request to the underlying property owner.

Council staff reviewed the February 5, 2020 response to the incomplete request and identified the following deficiencies:

1. The CD prepared by Ramaker & Associates, Inc. and dated April 25, 2019, references the 2016 Connecticut State Building Code (CSBC); however the State of Connecticut has adopted the 2018 CSBC effective October 1, 2018;
2. The ROHN quotation and the Designed Appurtenance Loading do not qualify as a SA and are not stamped and signed by a Professional Engineer licensed in the State of Connecticut;



3. The SA provided is for a facility at 395 Round Hill Road in Greenwich;
4. The MA provided does not indicate the % stress capacity for the proposed antenna mount under the proposed equipment loading; and
5. The building permit for a modification to existing equipment does not represent the original approval of the tower and compound.

Therefore, the exempt modification request remains incomplete at this time. The Council recommends that Charles Cherundolo Consulting provide an updated CD that references the 2018 CSBC, a full and complete passing ( $\leq 100\%$ ) SA that is stamped and signed by a Professional Engineer licensed in the State of Connecticut, a MA that indicates the % stress capacity of the antenna mount for the proposed modification and documentation showing the original facility approval with conditions if any or correspondence with the Town stating that there are no records of the original facility approval, on or before March 9, 2020. If additional time is needed to gather the requested information, please submit a written request for an extension of time prior to March 9, 2020. **Please provide an electronic version and one hard copy of the requested information for the incomplete exempt modification to be rendered complete and processed. Please include the Council's exempt modification identification number referenced above with the submittal.**

This notice of incompleteness shall have the effect of tolling the Federal Communications Commission (FCC) 60-day timeframe in accordance with Paragraph 217 of the FCC Wireless Infrastructure Report and Order issued on October 21, 2014 (FCC 14-153).

Thank you for your attention to this matter. Should you have any questions, please feel free to contact me at 860-827-2951.

Sincerely,



Melanie Bachman  
Executive Director

MAB/IN/emr

Enclosure: Incomplete Letter dated December 17, 2019.

c: The Honorable Lynne Vanderslice, First Selectwoman, Town of Wilton  
Michael Wrinn, AICP, Director of Planning and Land Use Management, Town of Wilton



# STATE OF CONNECTICUT

## CONNECTICUT SITING COUNCIL

Ten Franklin Square, New Britain, CT 06051

Phone: (860) 827-2935 Fax: (860) 827-2950

E-Mail: [siting.council@ct.gov](mailto:siting.council@ct.gov)

[www.ct.gov/csc](http://www.ct.gov/csc)

### VIA ELECTRONIC MAIL

December 17, 2019

Ryan G. Bailey  
Charles Cherundolo Consulting  
1280 Route 46 West, Suite 9  
Parsippany, NJ 07054

RE: **EM-SPRINT-161-191211** – Sprint notice of intent to modify an existing telecommunications facility located at 24 ½ Richdale Drive, Wilton, Connecticut.

Dear Mr. Bailey:

The Connecticut Siting Council (Council) received a notice of intent to modify the above-referenced facility on December 11, 2019.

According to Section 16-50j-71 of the Regulations of Connecticut State Agencies, "...any modification, as defined in Section 16-50j-2a of the Regulations of Connecticut State Agencies, to an existing tower site, except as specified in Sections 16-50j-72 and 16-50j-88 of the Regulations of Connecticut State Agencies, may have a substantial adverse environmental effect."

Staff has reviewed this exempt modification request for completeness and has identified the following deficiencies in the request:

- 1) The Construction Drawings (CD) provided in the electronic filing are for a site at Round Hill Road in Greenwich;
- 2) No Structural Analysis (SA) has been provided for this request;
- 3) No Mount Analysis (MA) is included with the request for exempt modification; therefore, it is unclear whether the proposed antenna mount is capable of supporting the proposed equipment load;
- 4) The request lacks proof that the entire request for exempt modification was physically mailed to the underlying property owner;
- 5) The exempt modification request lacks documentation of the original facility approval and any conditions of such approval or correspondence with the Town of Wilton stating that the town no longer retains records of its decision; and
- 6) A property card and parcel map for the underlying property has not been provided with the request.


Therefore, the exempt modification request is incomplete at this time. The Council recommends that Charles Cherundolo Consulting provide an electronic copy of the CD for the above-referenced facility, a passing ( $\leq 100\%$ ) SA and MA for the proposed modification that is stamped and signed by a professional engineer duly licensed in the State of Connecticut, a property card and parcel map for the underlying property, documentation showing the original facility approval with conditions if any or correspondence with the Town stating that there are no records of the original facility approval and proof of proper notice of this exempt modification request to the underlying property owner, on or before January 21, 2020. If

additional time is needed to gather the requested information, please submit a written request for an extension of time prior to January 21, 2020. **Please provide an electronic version and one hard copy of the requested information for the incomplete exempt modification to be rendered complete and processed. Please include the Council's exempt modification identification number referenced above with the submittal.**

This notice of incompleteness shall have the effect of tolling the Federal Communications Commission (FCC) 60-day timeframe in accordance with Paragraph 217 of the FCC Wireless Infrastructure Report and Order issued on October 21, 2014 (FCC 14-153).

Thank you for your attention to this matter. Should you have any questions, please feel free to contact me at 860-827-2951.

Sincerely,



Melanie Bachman  
Executive Director

MAB/IN/emr

- c: The Honorable Lynne Vanderslice, First Selectwoman, Town of Wilton  
Robert Nerney, AICP, Director of Planning and Land Use Management, Town of Wilton





1280 Route 46 West, Suite 9, Parsippany NJ, 07054

Melanie Bachman  
Executive Director  
CT Siting Council  
10 Franklin Square  
New Britain, CT 06051

Re: Notice of Exempt Modification Application  
24 ½ Richdale Drive, Wilton, CT 06897

Latitude: N41.20516  
Longitude: W73.4361

Dear Ms. Bachman:

Sprint currently maintains 3 existing panel antennas and three RRH units at the 68' centerline level of the existing 71' wooden pole. Sprint proposes to swap the 71' wooden pole for a 70' steel pole as well as replace the 3 panel antennas and 3 RRH units at the 68' centerline on the pole. Sprint further proposes to add 3 remote radio heads at the base of the pole. Sprint is performing a new high-performance upgrade for cellular mobile communications. It is designed to increase the capacity and speed of mobile telephone networks.

Please accept this letter as notification to the Council, pursuant to R.C.S.A. Section 16-50j-73, for construction which constitutes an exempt modification pursuant to R.C.S.A. Section 16-50j-72(b)(2). In compliance with R.C.S.A. Section 16-50j-73, a copy of this letter is being sent to First Selectwomen Lynne Vanderslice of the Town of Wilton as well as Robert Nerney, Director of Planning for the Town of Wilton and Knapp Properties, owner of the property

Attached is a summary of the planned modifications, including power density calculations reflecting the change in Sprint's operations at the site. Also included is documentation of the structural sufficiency of the tower with proposed modifications to accommodate the revised antenna configuration as well as the latest CSC decision, tax sheet and tax map.

### **Existing Facility**

CSC Summary Statement – CT60XC001 – 24 ½  
Richdale Dr, Wilton CT 06897

The Communications Tower facility is located at 24 ½ Richdale Dr, Wilton CT and is owned by Knapp Properties LLC, the Site coordinates are: N41.20516 W73.43619.

The existing facility consists of a 71' wooden pole. Sprint currently operates wireless communications equipment in a shelter on the ground near the pole and has 3 antennas and 3 RRH units mounted at centerline of 68'.

## **Statutory Considerations**

The planned modifications to the facility fall within the activities explicitly provided for in R.C.S.A. 16-50j-72(b)(2)

1. The height of the overall structure will be unaffected.
2. The proposed changes will not require an extension of the property boundaries.
3. The proposed additions will not increase the noise level at the existing facility by six decibels or more, or to levels that exceed state and/or local criteria
4. The changes will not increase the calculated "worst case" power density for the combined operations at the site to a level at or above the Federal Communications Commission safety standard.
5. The proposed modifications will not cause a change or alteration in the physical or environmental characteristics of the site.
6. The new structure and its foundation can support the proposed loading.

For the foregoing reasons, Sprint respectfully submits that the proposed changes at the referenced site constitute exempt modifications under R.C.S.A Section §16-50j-72(b)(2).

Respectfully submitted,




Ryan G Bailey  
Charles Cherundolo Consulting  
856-625-1596  
[ryan@mackenzierealtyconsulting.com](mailto:ryan@mackenzierealtyconsulting.com)

### Additional Recipients:

First Selectwoman Lynne Vanderslice for the Town of Wilton– Via FedEx  
Robert Nerney, Director of Planning for the Town of Wilton - Via FedEx  
Knapp Properties, LLC, owner of the property





PROJECT: 2.5 EQUIPMENT DEPLOYMENT  
 SITE NAME: (R2E) CT60-001 to CT0065 WILTON-RICHDALE TERRACE  
 SITE CASCADE: CT60XC001-R  
 SITE ADDRESS: 24 1/2 RICHDALE DRIVE WILTON, CT 06897  
 SITE TYPE: NEW MONOPOLE



1 INTERNATIONAL BLVD, SUITE 800  
MAHWAH, NJ 07495



100% EMPLOYEE-OWNED  
 123 Broadway, Woodcliff Lake, NJ 07677  
 608-643-4100 www.Ramaker.com  
 Sauk City, WI • Willmar, MN  
 Woodcliff Lake, NJ • Bayamon, PR

**Charles Cherundolo Consulting, Inc.**

713 Clover Lane, Moscow, PA 18444  
 Phone: 570-840-5084 Fax: 570-842-5592

Certification & Seal:  
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



*James R. Skowronski*  
 Signature: \_\_\_\_\_ Date: 4/25/2019

0 04/25/19 FINAL CDs ISSUED

| MARK  | DATE  | DESCRIPTION            |
|-------|-------|------------------------|
| ISSUE | FINAL | DATE ISSUED 04/25/2019 |

PROJECT TITLE:  
 (R2E) CT60-001 to CT0065  
 WILTON-RICHDALE TERRACE  
 CT60XC001-R

PROJECT INFORMATION:  
 24 1/2 RICHDALE DRIVE  
 WILTON, CT 06897  
 FAIRFIELD COUNTY

SHEET TITLE:  
 TITLE SHEET

SCALE: NONE

PROJECT NUMBER: 28753  
 SHEET NUMBER: T-1

**SITE INFORMATION**

**PROPERTY OWNER:**  
 KNAPP PROPERTIES, LLC  
 P.O. BOX 264  
 GEORGETOWN, CT 06829

**SITE ADDRESS:**  
 24 1/2 RICHDALE DRIVE  
 WILTON, CT 06897  
 FAIRFIELD COUNTY

**GEOGRAPHIC COORDINATES:**  
 LATITUDE: 41.20516111° (41° 12' 18.58" N)  
 LONGITUDE: -73.43619722° (73° 26' 10.31" W)

**ZONING JURISDICTION:**  
 THE CONNECTICUT SITING COUNCIL

**ZONING DISTRICT:**  
 R-2A SINGLE-FAMILY RESIDENCE DISTRICT

**POWER COMPANY:**  
 CONNECTICUT LIGHT & POWER  
 PH.: (888) 783-6617

**AAV PROVIDER:**  
 XXX  
 PH.: (XXX) XXX-XXXX


**SPRINT CONSTRUCTION MANAGER:**  
 NAME: GARY WOOD  
 PHONE: (860) 940-9168  
 E-MAIL: gary.wood@sprint.com

**EQUIPMENT SUPPLIER:**  
 ALCATEL-LUCENT  
 600-700 MOUNTAIN AVENUE  
 MURRAY HILL, NJ 07974  
 PH.: (908) 508-8080


**SITE ACQUISITION:**  
 CHARLES CHERUNDOLO CONSULTING, INC.  
 1280 RT. 46 WEST  
 PARSIPPANY, NJ 07054  
 CONTACT: TOM JUPIN, PMP, PROJECT MANAGER  
 CELL: (973) 819-9033  
 EMAIL: tom.jupin@cherundoloconsulting.com

**PLANS PREPARED BY:**  
 RAMAKER & ASSOCIATES, INC.  
 CONTACT: KEITH BOHNSACK, PROJECT MANAGER  
 PH.: (608) 643-4100  
 EMAIL: kbohnsack@ramaker.com

**AREA MAP**



**LOCATION MAP**



**PROJECT DESCRIPTION**

- REPLACE EXISTING WOOD PLE WIT NEW MONOPOLE TOWER AND FOUNDATION (DESIGN BY OTHERS)
- INSTALL NEW 2.5 EQUIPMENT IN EXISTING BTS CABINET  
 \*(1) RECTIFIER SHELF AND (3) RECTIFIERS  
 \*(1) BASE BAND UNIT
- INSTALL NEW BATTERY STRING(S) IN EXISTING BATTERY CABINET
- RELOCATE (6) EXISTING RRHs AND INSTALL (6) NEW RRHs ON NEW TOWER
- RELOCATE (1) EXISTING HYBRID CABLE AND INSTALL (1) NEW HYBRID CABLE FROM EXISTING EQUIPMENT TO NEW TOWER
- INSTALL (1) NEW ANTENNA MOUNT PLATFORM ON NEW TOWER
- INSTALL (3) NEW PANEL ANTENNAS ON NEW TOWER

**APPLICABLE CODES**

- \* ALL WORK SHALL BE PERFORMED AND MATERIALS INSTALLED IN ACCORDANCE WITH THE FOLLOWING CODES AS ADOPTED BY THE LOCAL GOVERNING AUTHORITIES. NOTHING IN THESE PLANS IS TO BE CONSTRUED TO PERMIT WORK NOT CONFORMING TO THESE CODES.
- 2016 CT STATE BUILDING CODE
  - 2016 CT FIRE SAFETY CODE
  - 2014 NATIONAL ELECTRIC CODE W/ CT AMENDMENTS
  - 2012 IECC W/ CT AMENDMENTS



**SHEET INDEX**

| SHT NO: | SHEET TITLE:                       | REV: | ENGINEER: |
|---------|------------------------------------|------|-----------|
| T-1     | TITLE SHEET                        | 0    | JRS       |
| SP-1    | SPRINT SPECIFICATIONS              | 0    | JRS       |
| SP-2    | SPRINT SPECIFICATIONS              | 0    | JRS       |
| SP-3    | SPRINT SPECIFICATIONS              | 0    | JRS       |
| A-1     | SITE PLAN                          | 0    | JRS       |
| A-2     | EQUIPMENT PLAN                     | 0    | JRS       |
| A-3     | POLE ELEVATION & ANTENNA DETAILS   | 0    | JRS       |
| A-4     | RF DATA SHEET                      | 0    | JRS       |
| A-5     | FIBER PLUMBING DIAGRAM             | 0    | JRS       |
| A-6     | CABLE COLOR CODING                 | 0    | JRS       |
| A-7     | ANTENNA & HYBRID CABLE DETAILS     | 0    | JRS       |
| A-8     | EQUIPMENT DETAILS                  | 0    | JRS       |
| S-1     | STRUCTURAL DETAILS                 | 0    | JRS       |
| E-1     | EQUIPMENT UTILITY & GROUNDING PLAN | 0    | JRS       |
| E-2     | GROUNDING DETAILS                  | 0    | JRS       |
| E-3     | GROUNDING DETAILS                  | 0    | JRS       |
| E-4     | GROUNDING DETAILS                  | 0    | JRS       |
| E-5     | DC POWER DETAILS & PANEL SCHEDULES | 0    | JRS       |



**SECTION 01 100 - SCOPE OF WORK**

**THE WORK:**  
THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE CONSTRUCTION DRAWINGS AND ASSOCIATED OUTLINE SPECIFICATIONS AND THE SITE SPECIFIC WORK ORDER, DESCRIBE THE WORK TO BE PERFORMED BY THIS CONSTRUCTION CONTRACTOR (SUPPLIER).

**RELATED DOCUMENTS:**

- A. THE REQUIREMENTS OF EACH SECTION OF THIS SPECIFICATION APPLY TO ALL SECTIONS, INDIVIDUALLY AND COLLECTIVELY.
- B. RELATED DOCUMENTS: THE CONTRACTOR SHALL COMPLY WITH THE MOST CURRENT VERSION OF THE FOLLOWING SUPPLEMENTAL REQUIREMENTS FOR INSTALLATION AND TESTING.
  - 1. EN-201 2-001 : (FIBER OPTIC, DC CABLE, AND DC CIRCUIT BREAKER TAGGING STANDARDS)
  - 2. TS-0200 - (TRANSMISSION ANTENNA LINE ACCEPTANCE STANDARDS)
  - 3. EL-0568: (FIBER TESTING POLICY)
  - 4. NP-312-201 : (EXTERIOR GROUNDING SYSTEM TESTING)
  - 5. NP-760-500: ETHERNET, MICROWAVE, TESTING AND ACCEPTANCE

**PRECEDENCE:**

SHOULD CONFLICTS OCCUR BETWEEN THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES AND THE CONSTRUCTION DRAWINGS, INFORMATION ON THE CONSTRUCTION DRAWINGS SHALL TAKE PRECEDENCE. NOTIFY SPRINT CONSTRUCTION MANAGER IF THIS OCCURS.

**NATIONALLY RECOGNIZED CODES AND STANDARDS:**

THE WORK SHALL COMPLY WITH APPLICABLE NATIONAL AND LOCAL CODES AND STANDARDS, LATEST EDITION, AND PORTIONS THEREOF, INCLUDED BUT NOT LIMITED TO THE FOLLOWING:

- A. GR-63-CORE NEBS REQUIREMENTS: PHYSICAL PROTECTION
- B. GR-78-CORE GENERIC REQUIREMENTS FOR THE PHYSICAL DESIGN AND MANUFACTURE OF TELECOMMUNICATIONS EQUIPMENT.
- C. GR-1089 CORE, ELECTROMAGNETIC COMPATIBILITY AND ELECTRICAL SAFETY -GENERIC CRITERIA FOR NETWORK TELECOMMUNICATIONS EQUIPMENT.
- D. NATIONAL FIRE PROTECTION ASSOCIATION CODES AND STANDARDS (NFPA) INCLUDING NFPA 70 (NATIONAL ELECTRICAL CODE - "NEC") AND NFPA 101 (LIFE SAFETY CODE).
- E. AMERICAN SOCIETY FOR TESTING OF MATERIALS (ASTM)
- F. INSTITUTE OF ELECTRONIC AND ELECTRICAL ENGINEERS (IEEE)
- G. AMERICAN CONCRETE INSTITUTE (ACI)
- H. AMERICAN WIRE PRODUCERS ASSOCIATION (AWPA)
- I. CONCRETE REINFORCING STEEL INSTITUTE (CRSI)
- J. AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)
- K. PORTLAND CEMENT ASSOCIATION (PCA)
- L. NATIONAL CONCRETE MASONRY ASSOCIATION (NCMA)
- M. BRICK INDUSTRY ASSOCIATION (BIA)
- N. AMERICAN WELDING SOCIETY (AWS)
- O. NATIONAL ROOFING CONTRACTORS ASSOCIATION (NRCA)
- P. SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)
- Q. DOOR AND HARDWARE INSTITUTE (DHI)
- R. OCCUPATIONAL SAFETY AND HEALTH ACT (OSHA)
- 5. APPLICABLE BUILDING CODES INCLUDING UNIFORM BUILDING CODE, SOUTHERN BUILDING CODE, BOCA, AND THE INTERNATIONAL BUILDING CODE.

**DEFINITIONS:**

- A. WORK: THE SUM OF TASKS AND RESPONSIBILITIES IDENTIFIED IN THE CONTRACT DOCUMENTS.
- B. COMPANY: "SPRINT"; SPRINT NEXTEL CORPORATION AND ITS OPERATING ENTITIES.
- C. ENGINEER: SYNONYMOUS WITH ARCHITECT & ENGINEER AND "A&E", THE DESIGN PROFESSIONAL HAVING PROFESSIONAL RESPONSIBILITY FOR DESIGN OF THE PROJECT.
- D. CONTRACTOR: CONSTRUCTION CONTRACTOR, SUPPLIER, CONSTRUCTION VENDOR, INDIVIDUAL OR ENTITY WHO AFTER EXECUTION OF A CONTRACT IS BOUND TO ACCOMPLISH THE WORK.
- E. THIRD PARTY VENDOR OR AGENCY: A VENDOR OR AGENCY ENGAGED SEPARATELY BY THE COMPANY, A&E, OR CONTRACTOR TO PROVIDE MATERIALS OR TO ACCOMPLISH SPECIFIC TASKS RELATED TO BUT NOT INCLUDED IN THE WORK.
- F. CONSTRUCTION MANAGER - ALL PROJECTS RELATED COMMUNICATION TO FLOW THROUGH SPRINT REPRESENTATIVE IN CHARGE OF PROJECT.

**SITE FAMILIARITY:**

CONTRACTOR SHALL BE RESPONSIBLE FOR FAMILIARIZING HIMSELF WITH ALL CONTRACT DOCUMENTS, FIELD CONDITIONS AND DIMENSIONS PRIOR TO PROCEEDING WITH CONSTRUCTION. ANY DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE SPRINT CONSTRUCTION MANAGER PRIOR TO THE COMMENCEMENT OF WORK. NO COMPENSATION WILL BE AWARDED BASED ON CLAIM OF LACK OF KNOWLEDGE OR FIELD CONDITIONS.

**POINT OF CONTACT:**

COMMUNICATION BETWEEN SPRINT AND THE CONTRACTOR SHALL FLOW THROUGH THE SINGLE SPRINT CONSTRUCTION MANAGER APPOINTED TO MANAGE THE PROJECT FOR SPRINT.

**ON-SITE SUPERVISION:**

THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK AND SHALL BE RESPONSIBLE FOR CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES IN ACCORDANCE WITH THE CONTRACT DOCUMENTS. THE CONTRACTOR SHALL EMPLOY A COMPETENT SUPERINTENDENT WHO SHALL BE IN ATTENDANCE AT THE SITE AT ALL TIMES DURING PERFORMANCE OF THE WORK.

**DRAWINGS REQUIRED AT JOBSITE:**

THE CONSTRUCTION CONTRACTOR SHALL MAINTAIN A FULL SET OF THE CONSTRUCTION DRAWINGS FOR WIRELESS SITES AND THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES AT THE JOBSITE FROM MOBILIZATION THROUGH CONSTRUCTION COMPLETION.

- A. THE JOBSITE DRAWINGS SHALL BE CLEARLY MARKED DAILY IN RED PENCIL WITH ANY CHANGES IN CONSTRUCTION OVER WHAT IS DEPICTED IN THE DOCUMENTS. AT CONSTRUCTION COMPLETION, THIS JOBSITE MARKUP SET SHALL BE DELIVERED TO THE COMPANY OR COMPANY'S DESIGNATED REPRESENTATIVE TO BE FORWARDED TO THE COMPANY'S A&E VENDOR FOR PRODUCTION OF "AS-BUILT" DRAWINGS.
- B. DIMENSIONS SHOWN ARE TO FINISH SURFACES UNLESS NOTED OTHERWISE. SPACING BETWEEN EQUIPMENT IS THE REQUIRED CLEARANCE. SHOULD THERE BE ANY QUESTIONS REGARDING THE CONTRACT DOCUMENTS, EXISTING CONDITIONS AND/OR DESIGN INTENT, THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING A CLARIFICATION FROM THE SPRINT CONSTRUCTION MANAGER PRIOR TO PROCEEDING WITH THE WORK.

**USE OF JOB SITE:**

THE CONTRACTOR SHALL CONFINE ALL CONSTRUCTION AND RELATED OPERATIONS INCLUDING STAGING AND STORAGE OF MATERIALS AND EQUIPMENT, PARKING, TEMPORARY FACILITIES, AND WASTE STORAGE TO THE LEASE PARCEL UNLESS OTHERWISE PERMITTED BY THE CONTRACT DOCUMENTS.

**UTILITY SERVICES:**

WHERE NECESSARY TO CUT EXISTING PIPES, ELECTRICAL WIRES, CONDUITS, CABLES, ETC., OF UTILITY SERVICES, OR OF FIRE PROTECTION OR COMMUNICATIONS SYSTEMS, THEY SHALL BE CUT AND CAPPED AT SUITABLE PLACES OR WHERE SHOWN. ALL SUCH ACTIONS SHALL BE COORDINATED WITH THE UTILITY COMPANY INVOLVED:

**PERMITS/FEES:**

WHEN REQUIRED THAT A PERMIT OR CONNECTION FEE BE PAID TO A PUBLIC UTILITY PROVIDER FOR NEW SERVICE TO THE CONSTRUCTION PROJECT, PAYMENT OF SUCH FEE SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.

**CONTRACTOR:**

CONTRACTOR SHALL TAKE ALL MEASURES AND PROVIDE ALL MATERIAL NECESSARY FOR PROTECTING EXISTING EQUIPMENT AND PROPERTY.

**USE OF ELECTRONIC PROJECT MANAGEMENT SYSTEMS:**

CONTRACTOR WILL UTILIZE ITS BEST EFFORTS TO WORK WITH SPRINT ELECTRONIC PROJECT MANAGEMENT SYSTEMS. CONTRACTOR UNDERSTANDS THAT SUFFICIENT INTERNET ACCESS, EQUIVALENT TO "BROADBAND" OR BETTER, IS REQUIRED TO TIMELY AND EFFECTIVELY UTILIZE SPRINT DATA AND DOCUMENT MANAGEMENT SYSTEMS AND AGREES TO MAINTAIN APPROPRIATE CONNECTIONS FOR CONTRACTOR'S STAFF AND OFFICES THAT ARE COMPATIBLE WITH SPRINT DATA AND DOCUMENT MANAGEMENT SYSTEMS

**TEMPORARY UTILITIES AND FACILITIES:**

THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL TEMPORARY UTILITIES AND FACILITIES NECESSARY EXCEPT AS OTHERWISE INDICATED IN THE CONSTRUCTION DOCUMENTS. TEMPORARY UTILITIES AND FACILITIES INCLUDE POTABLE WATER, HEAT, HVAC, ELECTRICITY, SANITARY FACILITIES, WASTE DISPOSAL FACILITIES, AND TELEPHONE/COMMUNICATION SERVICES. PROVIDE TEMPORARY UTILITIES AND FACILITIES IN ACCORDANCE WITH OSHA AND THE AUTHORITY HAVING JURISDICTION. CONTRACTOR MAY UTILIZE THE COMPANY ELECTRICAL SERVICE IN THE COMPLETION OF THE WORK WHEN IT BECOMES AVAILABLE. USE OF THE LESSOR'S OR SITE OWNER'S UTILITIES OR FACILITIES IS EXPRESSLY FORBIDDEN EXCEPT AS OTHERWISE ALLOWED IN THE CONTRACT DOCUMENTS.

**ACCESS TO WORK:**

THE CONTRACTOR SHALL PROVIDE ACCESS TO THE JOB SITE FOR AUTHORIZED COMPANY PERSONNEL AND AUTHORIZED REPRESENTATIVES OF THE ARCHITECT/ENGINEER DURING ALL PHASES OF THE WORK.

**DIMENSIONS:**

VERIFY DIMENSIONS INDICATED ON DRAWINGS WITH FIELD DIMENSIONS BEFORE FABRICATION OR ORDERING OF MATERIALS. DO NOT SCALE DRAWINGS.

**EXISTING CONDITIONS:**

NOTIFY THE SPRINT CONSTRUCTION MANAGER OF EXISTING CONDITIONS DIFFERING FROM THOSE INDICATED ON THE DRAWINGS. DO NOT REMOVE OR ALTER STRUCTURAL COMPONENTS WITHOUT PRIOR WRITTEN APPROVAL FROM THE ARCHITECT AND ENGINEER.

**SECTION 01 200 - COMPANY FURNISHED MATERIAL AND EQUIPMENT**

**FURNISHED MATERIALS:**

COMPANY FURNISHED MATERIALS AND EQUIPMENT TO BE INSTALLED BY THE CONTRACTOR (OFC) IS IDENTIFIED ON THE RF DATA SHEET IN THE CONSTRUCTION DOCUMENTS.

**RECEIPT OF MATERIAL AND EQUIPMENT:**

A. THE CONTRACTOR IS RESPONSIBLE FOR SPRINT PROVIDED MATERIAL AND EQUIPMENT AND UPON RECEIPT SHALL:

- 1. ACCEPT DELIVERIES AS SHIPPED AND TAKE RECEIPT.
- 2. VERIFY COMPLETENESS AND CONDITION OF ALL DELIVERIES.
- 3. TAKE RESPONSIBILITY FOR EQUIPMENT AND PROVIDE INSURANCE PROTECTION AS REQUIRED IN AGREEMENT.

B. RECORD ANY DEFECTS OR DAMAGES AND WITHIN TWENTY-FOUR HOURS AFTER RECEIPT, REPORT TO SPRINT OR ITS DESIGNATED PROJECT REPRESENTATIVE OF SUCH.

C. PROVIDE SECURE AND NECESSARY WEATHER PROTECTED WAREHOUSING.

D. COORDINATE SAFE AND SECURE TRANSPORTATION OF MATERIAL AND EQUIPMENT, DELIVERING AND OFF-LOADING FROM CONTRACTOR'S WAREHOUSE TO SITE.

**DELIVERABLES:**

- A. COMPLETE SHIPPING AND RECEIPT DOCUMENTATION IN ACCORDANCE WITH COMPANY PRACTICE.
- B. IF APPLICABLE, COMPLETE LOSS/STOLEN/DAMAGED DOCUMENTATION REPORT AS NECESSARY IN ACCORDANCE WITH COMPANY PRACTICE, AND AS DIRECTED BY COMPANY.

**SECTION 01 300 - CELL SITE CONSTRUCTION**

**NOTICE TO PROCEED:**

A. NO WORK SHALL COMMENCE PRIOR TO COMPANY'S ISSUANCE OF THE WORK ORDER.

B. UPON RECEIVING NOTICE TO PROCEED, CONTRACTOR SHALL FULLY PERFORM ALL WORK NECESSARY TO PROVIDE SPRINT WITH AN OPERATIONAL WIRELESS FACILITY.

**GENERAL REQUIREMENTS FOR CONSTRUCTION:**

A. CONTRACTOR SHALL KEEP THE SITE FREE FROM ACCUMULATING WASTE MATERIAL, DEBRIS, AND TRASH. AT THE COMPLETION OF THE WORK, CONTRACTOR SHALL REMOVE FROM THE SITE ALL REMAINING RUBBISH, IMPLEMENTS, TEMPORARY FACILITIES, AND SURPLUS MATERIALS.

B. EQUIPMENT ROOMS SHALL AT ALL TIMES BE MAINTAINED "BROOM CLEAN" AND CLEAR OF DEBRIS.

C. CONTRACTOR SHALL TAKE ALL REASONABLE PRECAUTIONS TO DISCOVER AND LOCATE ANY HAZARDOUS CONDITION.

- 1. IN THE EVENT CONTRACTOR ENCOUNTERS ANY HAZARDOUS CONDITION WHICH HAS NOT BEEN ABATED OR OTHERWISE MITIGATED, CONTRACTOR AND ALL OTHER PERSONS SHALL IMMEDIATELY STOP WORK IN THE AFFECTED AREA AND NOTIFY COMPANY IN WRITING. THE WORK IN THE AFFECTED AREA SHALL NOT BE RESUMED EXCEPT BY WRITTEN NOTIFICATION BY COMPANY.
- 2. CONTRACTOR AGREES TO USE CARE WHILE ON THE SITE AND SHALL NOT TAKE ANY ACTION THAT WILL OR MAY RESULT IN OR CAUSE THE HAZARDOUS CONDITION TO BE FURTHER RELEASED IN THE ENVIRONMENT, OR TO FURTHER EXPOSE INDIVIDUALS TO THE HAZARD.

D. CONTRACTOR'S ACTIVITIES SHALL BE RESTRICTED TO THE PROJECT LIMITS. SHOULD AREAS OUTSIDE THE PROJECT LIMITS BE AFFECTED BY CONTRACTOR'S ACTIVITIES, CONTRACTOR SHALL IMMEDIATELY RETURN THEM TO ORIGINAL CONDITION

**FUNCTIONAL REQUIREMENTS:**

A. THE ACTIVITIES DESCRIBED IN THIS PARAGRAPH REPRESENT MINIMUM ACTIONS AND PROCESSES REQUIRED TO SUCCESSFULLY COMPLETE THE WORK. CONTRACTOR SHALL TAKE ALL ACTIONS AS NECESSARY TO SUCCESSFULLY COMPLETE THE CONSTRUCTION OF A FULLY FUNCTIONING WIRELESS FACILITY AT THE SITE IN ACCORDANCE WITH COMPANY PROCESSES.

B. SUBMIT SPECIFIC DOCUMENTATION AS INDICATED HEREIN, AND OBTAIN REQUIRED APPROVALS WHILE THE WORK IS BEING PERFORMED.

C. MANAGE AND CONDUCT ALL FIELD CONSTRUCTION SERVICE RELATED ACTIVITIES

D. PROVIDE CONSTRUCTION ACTIVITIES TO THE EXTENT REQUIRED BY THE CONTRACT DOCUMENTS, INCLUDING BUT NOT LIMITED TO THE FOLLOWING:

- 1. PERFORM ANY REQUIRED SITE ENVIRONMENTAL MITIGATION.
- 2. PREPARE GROUND SITES; PROVIDE DE-GRUBBING; AND ROUGH AND FINAL GRADING, AND COMPOUND SURFACE TREATMENTS.
- 3. MANAGE AND CONDUCT ALL ACTIVITIES FOR INSTALLATION OF UTILITIES INCLUDING ELECTRICAL AND BACKHAUL (FIBER, COPPER, OR MICROWAVE).
- 4. INSTALL UNDERGROUND FACILITIES INCLUDING UNDERGROUND POWER AND COMMUNICATIONS CONDUITS, AND UNDERGROUND GROUNDING SYSTEM.
- 5. INSTALL ABOVE GROUND GROUNDING SYSTEMS, CONDUIT AND BOXES.
- 6. PROVIDE NEW HVAC INSTALLATIONS AND MODIFICATIONS.
- 7. INSTALL "H-FRAMES", CABINETS AND PADS AND PLATFORMS AS INDICATED.
- 8. INSTALL ROADS, ACCESS WAYS, CURBS AND DRAINS AS INDICATED.
- 9. ACCOMPLISH REQUIRED MODIFICATION OF EXISTING FACILITIES.

10. PROVIDE ANTENNA SUPPORT STRUCTURE FOUNDATIONS.

11. PROVIDE SLABS AND EQUIPMENT PLATFORMS.

12. INSTALL COMPOUND FENCING, SIGHT SHIELDING, LANDSCAPING AND ACCESS BARRIERS.

13. PERFORM INSPECTION AND MATERIAL TESTING AS REQUIRED HEREINAFTER.

14. CONDUCT SITE RESISTANCE TO EARTH TESTING AS REQUIRED HEREINAFTER.

15. INSTALL FIXED GENERATOR SETS AND OTHER STANDBY POWER SOLUTIONS.

16. INSTALL TOWERS, ANTENNA SUPPORT STRUCTURES AND PLATFORMS ON EXISTING TOWERS AS REQUIRED.

17. INSTALL CELL SITE RADIOS, MICROWAVE, GPS, COAXIAL MAINLINE, ANTENNAS, CROSS BAND COUPLERS, TOWER TOP AMPLIFIERS, LOW NOISE AMPLIFIERS AND RELATED EQUIPMENT.

18. CONDUCT ALL REQUIRED TESTS AND INSPECTIONS

19. PERFORM, DOCUMENT, AND CLOSE OUT ALL JURISDICTIONAL PERMITTING REQUIREMENTS AND ANY CONSTRUCTION CONTROL DOCUMENTS THAT MAY BE REQUIRED BY GOVERNMENT AGENCIES AND LANDLORDS.

20. PERFORM ALL ADDITIONAL WORK AS IDENTIFIED IN SCOPE OF SERVICES ATTACHED TO THE SUPPLIER AGREEMENT FOR THIS PROJECT. THIS WORK MAY INCLUDE COMMISSIONING, INTEGRATION, SPECIAL WAREHOUSING, REVERSE LOGISTICS ACTIVITIES, ETC. PERFORM COMMISSIONING AND INTEGRATION ACTIVITIES PER APPLICABLE MOPS.

**DELIVERABLES:**

A. THE CONTRACTOR SHALL PROVIDE ALL REQUIRED TEST REPORTS AND DOCUMENTATION INCLUDED BUT NOT LIMITED TO THE FOLLOWING:

- 1. PRODUCT SPECIFICATIONS FOR MATERIALS OR SPECIAL CONSTRUCTION IF REQUESTED BY SPRINT
- 2. ACTUALIZE ALL CONSTRUCTION RELATED MILESTONES IN SITERRA AND COMPLETE ALL ON-LINE FORMS AND COMPLETE DOCUMENT UP-LOADS. UPLOAD ALL REQUIRED CLOSEOUT DOCUMENTS AND FINAL SITE PHOTOS
- 3. SCANABLE BARCODE PHOTOGRAPHS OF TOWER TOP AND INACCESSIBLE SERIALIZED EQUIPMENT LEFT ON SITE INSIDE BASE OF MAIN RF CABINET IN A PROTECTIVE POUCH.
- 4. ALL REQUIRED TEST REPORTS.
- 5. REQUIRED CLOSEOUT DOCUMENTATION INCLUDING BUT NOT LIMITED TO:
  - a. ALL JURISDICTIONAL PERMITTING AND OCCUPANCY INFORMATION
  - b. PDF SCAN OF REDLINES PRODUCED IN THE FIELD
  - c. ELECTRONIC AS-BUILT DRAWINGS IN AUTOCAD AND PDF FORMATS
  - d. LIEN WAIVERS
  - e. FINAL PAYMENT APPLICATION
  - f. REQUIRED FINAL CONSTRUCTION PHOTOS
  - g. CONSTRUCTION AND COMMISSIONING CHECKLIST COMPLETE WITH NO DEFICIENT ITEMS
  - h. LISTS OF SUBCONTRACTORS

B. PROVIDE ADDITIONAL DOCUMENTATION INCLUDING, BUT NOT LIMITED TO, THE FOLLOWING. DOCUMENTATION SHALL BE FORWARDED IN ORIGINAL FORMAT AND/OR UPLOADED INTO SMS.

- 1. ALL CORRESPONDENCE AND PRELIMINARY CONSTRUCTION REPORTS.
- 2. PROJECT PROGRESS REPORTS.
- 3. PRE-CONSTRUCTION MEETING NOTES.

**SECTION 01 400 - TESTS, INSPECTIONS, SUBMITTALS, AND PROJECT CLOSEOUT**

**TESTS AND INSPECTIONS:**

A. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CONSTRUCTION TESTS, INSPECTIONS AND PROJECT DOCUMENTATION.

B. CONTRACTOR SHALL ACCOMPLISH TESTING INCLUDING BUT NOT LIMITED TO THE FOLLOWING:

- 1. COAX SWEEPS AND FIBER TESTS PER TS-0200 (CURRENT VERSION) ANTENNA LINE ACCEPTANCE STANDARDS
- 2. POST CONSTRUCTION HEIGHT VERIFICATION, AZIMUTH AND DOWNTILT USING ELECTRONIC COMMERCIAL MADE-FOR-THE-PURPOSE ANTENNA ALIGNMENT TOOL.
- 3. CONCRETE BREAK TESTS
- 4. SITE RESISTANCE TO EARTH TEST
- 5. STRUCTURAL BACKFILL COMPACTION TESTS
- 6. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN SITE INSPECTION ACTIVITIES AND/OR AS A RESULT OF TESTING.
- 7. ADDITIONAL TESTING AS REQUIRED ELSEWHERE IN THIS SPECIFICATION.

**SUBMITTALS:**

A. THE WORK IN ALL ASPECTS SHALL COMPLY WITH THE CONSTRUCTION DRAWINGS AND THESE SPECIFICATIONS.

B. UPLOAD THE FOLLOWING TO SITERRA AS APPLICABLE INCLUDING BUT NOT LIMITED TO THE FOLLOWING:

- 1. CONCRETE MIX-DESIGNS FOR TOWER FOUNDATIONS, ANCHORS PIERS, AND CONCRETE PAVING.
  - 2. CONCRETE BREAK TESTS AS SPECIFIED HEREIN.
  - 3. CHEMICAL GROUNDING SYSTEM
  - 4. REINFORCEMENT CERTIFICATIONS
  - 5. STRUCTURAL BACKFILL TEST RESULTS
  - 6. SWEEP AND FIBER TESTS
  - 7. ANTENNA AZIMUTH AND DOWN-TILT VERIFICATION
  - 8. POST CONSTRUCTION HEIGHT VERIFICATION
  - 9. ADDITIONAL SUBMITTALS MAY BE REQUIRED FOR SPECIAL CONSTRUCTION OR MINOR MATERIALS
- C. ALTERNATES: AT THE COMPANY'S REQUEST, ANY ALTERNATIVES TO THE MATERIALS OR METHODS SPECIFIED SHALL BE SUBMITTED TO SPRINT'S CONSTRUCTION MANAGER FOR APPROVAL PRIOR TO BEING SHIPPED TO SITE. SPRINT WILL REVIEW AND APPROVE ONLY THOSE REQUESTS MADE IN WRITING. NO VERBAL APPROVALS WILL BE CONSIDERED. SUBMITTAL FOR APPROVAL SHALL INCLUDE A STATEMENT OF COST REDUCTION PROPOSED FOR USE OF ALTERNATE PRODUCT.

**TESTING BY THIRD PARTY AGENCY:**

A. EMPLOY AN AGENCY OF ENGINEERS AND SCIENTISTS WHO IS REGULARLY ENGAGED IN FIELD AND LABORATORY TESTING AND ANALYSIS. AGENCY SHALL HAVE BEEN IN BUSINESS A MINIMUM OF FIVE YEARS, AND BE LICENSED AS PROFESSIONAL ENGINEERS IN THE STATE WHERE THE PROJECT IS LOCATED. AGENCY IS SUBJECT TO APPROVAL BY COMPANY.

- 1. AGENCY MUST HAVE A THOROUGH UNDERSTANDING OF LOCAL AVAILABLE MATERIALS, INCLUDING THE SOIL, ROCK, AND GROUNDWATER CONDITIONS.
- 2. AGENCY IS TO BE FAMILIAR WITH THE APPLICABLE REQUIREMENTS FOR THE TESTS TO BE DONE, EQUIPMENT TO BE USED, AND ASSOCIATED HEALTH AND SAFETY ISSUES.
- 3. EXPERIENCE IN SOILS, CONCRETE, MASONRY, AGGREGATE, AND ASPHALT TESTING USING ASTM, AASHTO, AND OTHER METHODS IS NEEDED.

B. REQUIRED THIRD PARTY TESTS:

- 1. SITE RESISTANCE TO EARTH TEST PER NP-312-201
- 2. CONCRETE CYLINDER BREAK TESTS FOR TOWER PIER AND ANCHORS PER NATIONALLY RECOGNIZED STANDARDS
- 3. STRUCTURAL SOILS COMPACTION TESTS PER NATIONALLY RECOGNIZED STANDARDS
- 4. REBAR PLACEMENT VERIFICATION WITH REPORT
- 5. TESTING TENSION STUDY FOR ROCK ANCHORS
- 6. ALL THIRD PARTY TESTS AS REQUIRED BY LOCAL JURISDICTION

C. REQUIRED TESTS BY CONTRACTOR

- 1. COAX SWEEP TESTS PER SPRINT STANDARD TS-0200
- 2. FIBER TESTS PER SPRINT STANDARD EL-0568
- 3. MICROWAVE LINK TESTS PER NP-760-500
- 4. ANTENNA AZIMUTHS AND DOWN TILT USING ELECTRONIC ALIGNMENT TOOL PER ANTENNA INSTALLATION SPECIFICATION HEREIN.



1 INTERNATIONAL BLVD, SUITE 800  
MAHWAH, NJ 07495




123 Broadway, Woodcliff Lake, NJ 07677  
608-643-4100 www.Ramaker.com

Sauk City, WI • Willmar, MN  
Woodcliff Lake, NJ • Bayamon, PR

**Charles Cherundolo Consulting, Inc.**

713 Clover Lane, Moscow, PA 18444  
Phone: 570-840-5084 Fax: 570-842-5592

**Certification & Seal:**  
I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 4/25/2019

| MARK | DATE     | DESCRIPTION      |
|------|----------|------------------|
| 0    | 04/25/19 | FINAL CDs ISSUED |

| ISSUE PHASE | FINAL | DATE ISSUED | 04/25/2019 |
|-------------|-------|-------------|------------|
|-------------|-------|-------------|------------|

PROJECT TITLE:  
**(R2E) CT60-001 to CTO065  
WILTON-RICHDALE TERRACE  
CT60XCOO1-R**

PROJECT INFORMATION:  
24 1/2 RICHDALE DRIVE  
WILTON, CT 06897  
FAIRFIELD COUNTY

SHEET TITLE:  
**SPRINT SPECIFICATIONS**

SCALE: NONE

|                |       |
|----------------|-------|
| PROJECT NUMBER | 28753 |
| SHEET NUMBER   | SP-1  |



5. POST CONSTRUCTION HEIGHT VERIFICATION AS REQUIRED HERewith IN THE TOWER INSTALLATION SPECIFICATIONS.
  6. ASPHALT ROADWAY COMPACTED THICKNESS, SURFACE SMOOTHNESS, AND COMPACTED DENSITY TESTING AS SPECIFIED HERewith IN THE ASPHALT PAVING SPECIFICATIONS.
  7. FIELD QUALITY CONTROL TESTING AS SPECIFIED HERewith IN THE CONCRETE PAVING SPECIFICATIONS.
  8. TESTING REQUIRED HERewith UNDER SPECIFICATIONS FOR AGGREGATE BASE FOR ROADWAYS
  9. ALL OTHER TESTS REQUIRED BY LOCAL JURISDICTION
- D. INSPECTIONS BY COMPANY: THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN INSPECTION ACTIVITIES, FINAL ACCEPTANCE / PUNCH WALK REVIEW, AND/OR AS A RESULT OF TESTING
- E. SPRINT RESERVES THE RIGHT TO INSPECT THE CONSTRUCTION SITE AT ANY TIME VIA SITE WALKS AND/OR PHOTO REVIEWS. CONTRACTOR SHALL GIVE SPRINT 24 HOURS NOTICE PRIOR TO THE COMMENCEMENT OF THE FOLLOWING CONSTRUCTION ACTIVITIES AND PHOTOGRAPHS OF THE IN-PROGRESS WORK.
1. GROUNDING SYSTEM AND BURIED UTILITIES INSTALLATION PRIOR TO EARTH CONCEALMENT DOCUMENTED WITH DIGITAL PHOTOGRAPHS BY CONTRACTOR, APPROVED BY A&E OR SPRINT REPRESENTATIVE.
  2. FORMING FOR CONCRETE AND REBAR PLACEMENT PRIOR TO POUR DOCUMENTED WITH DIGITAL PHOTOGRAPHS BY CONTRACTOR, APPROVED BY A&E OR SPRINT REPRESENTATIVE.
  3. COMPACTION OF BACKFILL MATERIALS, AGGREGATE BASE FOR ROADS, PADS, AND ANCHORS, ASPHALT PAVING, AND SHAFT BACKFILL FOR CONCRETE AND WOOD POLES, BY INDEPENDENT THIRD PARTY AGENCY.
  4. PRE AND POST CONSTRUCTION ROOFTOP AND STRUCTURAL INSPECTIONS ON EXISTING FACILITIES. PRIOR TO CONSTRUCTION ACTIVITIES AND AFTER CONSTRUCTION IS COMPLETE, PROVIDE PHOTOGRAPHIC DOCUMENTATION OF ROOF, FLASHINGS, AND PARAPETS, BOTH BEFORE AND AFTER CONSTRUCTION IS COMPLETE.
  5. TOWER ERECTION SECTION STACKING AND PLATFORM ATTACHMENT DOCUMENTED BY DIGITAL PHOTOGRAPHS BY THIRD PARTY AGENCY.
  6. TOWER TOP AND INACCESSIBLE EQUIPMENT (RRUS, ANTENNAS, AND CABLING): PROVIDE PHOTOS OF THE BACKS OF ALL ANTENNAS, RRUS, COMBINERS, FILTERS, FIBER AND DC CABLING, CABLE COLOR CODING, EQUIPMENT GROUNDING AND CONNECTOR WATER PROOFING INCLUDING NAME PLATE AND SERIAL NUMBER FOR ALL SERIALIZED EQUIPMENT.

**PROJECT CLOSEOUT:**

- A. FINAL ACCEPTANCE PUNCH WALK AND INSPECTION: AS IDENTIFIED IN THE SCOPE OF SERVICES, SPRINT WILL CONDUCT A FINAL PUNCH WALK OR FINAL DESK TOP PHOTO REVIEW (SITE MODIFICATIONS). PUNCH WALKS MUST BE SCHEDULED IN ADVANCE AS REQUIRED. AT THE PUNCH WALK / REVIEW, SPRINT MAY IDENTIFY CRITICAL DEFICIENCIES WHICH MUST BE CORRECTED PRIOR TO PUTTING SITE ON AIR. MINOR DEFICIENCIES MUST BE CORRECTED WITHIN 30 DAYS EXCEPT AS OTHERWISE REQUIRED. VERIFICATIONS OF CORRECTIONS MAY BE MADE BY COMPANY DURING A REPEAT SITE WALK OR DESK TOP PHOTO REVIEW AT COMPANY'S SOLE DISCRETION.
- B. CLOSEOUT DOCUMENTATION: ALL CLOSEOUT DOCUMENTATION AND PHOTOGRAPHS SHALL BE UPLOADED PRIOR TO FINAL ACCEPTANCE. SPRINT WILL REVIEW CLOSEOUT DOCUMENTATION FOR PRESENCE AND CONTENT. CLOSEOUT DOCUMENTATION SHALL INCLUDE BUT IS NOT LIMITED TO THE FOLLOWING AS APPLICABLE:
1. COAX SWEEP TESTS:
  2. FIBER TESTS:
  3. JURISDICTION FINAL INSPECTION DOCUMENTATION
  4. REINFORCEMENT CERTIFICATION (MILL CERTIFICATION)
  5. CONCRETE MIX DESIGN AND PRODUCT DATA (TOWER FOUNDATION)
  6. LIEN WAIVERS AND RELEASES.
  7. POST -CONSTRUCTION HEIGHT VERIFICATION
  8. JURISDICTION CERTIFICATE OF OCCUPANCY
  9. ELECTRONIC ANTENNA AZIMUTH AND DOWN TILT VERIFICATION
  10. STRUCTURAL BACKFILL TEST RESULTS (IF APPLICABLE)
    11. CELL SITE UTILITY SETUP
    12. AS-BUILT REDLINE CONSTRUCTION DRAWINGS (PDF SCAN OF FIELD MARKS)
    13. AS-BUILT CONSTRUCTION DRAWINGS IN DWG AND PDF FORMATS
    14. LIST OF SUB CONTRACTORS
    15. APPROVED PERMITTING DOCUMENTS
  16. FINAL SITE PHOTOS UP-LOADED TO SITERRA. INCLUDE THE FOLLOWING AS APPLICABLE:
    - a. TOWER, ANTENNAS, RRUS, AND MAINLINE: INSPECTION AND PHOTOGRAPHS OF SECTION STACKING; INSPECTION AND PHOTOGRAPHS OF PLATFORM COMPONENT ATTACHMENT POINTS; PHOTOGRAPHS OF TOWER TOP GROUNDING; PHOTOS OF TOWER COAX/CABLE LINE COLOR CODING AT THE TOP AND AT GROUND LEVEL; INSPECTION AND PHOTOGRAPHS OF OPERATIONAL OF TOWER LIGHTING, AND PLACEMENT OF FAA REGISTRATION SIGN; PHOTOGRAPHS SHOWING ADDITIONAL GROUNDING POINTS FOR TOWERS GREATER THAN 200 FEET.; PHOTOS OF ANTENNA GROUND BAR, EQUIPMENT GROUND BAR, AND MASTER GROUND BAR; PHOTOS OF GPS ANTENNA(S); PHOTOS OF EACH SECTOR OF ANTENNAS; ONE PHOTOGRAPH LOOKING AT THE SECTOR AND ONE FROM BEHIND SHOWING THE PROJECTED COVERAGE AREA; PHOTOS OF COAX WEATHERPROOFING - TOP AND BOTTOM; PHOTOS OF COAX GROUNDING--TOP AND BOTTOM; PHOTOS OF ANTENNA AND MAST GROUNDING; PHOTOS OF COAX CABLE ENTRY INTO SHELTER; PHOTOS OF PLATFORM MECHANICAL CONNECTIONS TO TOWER/MONOPOLE.
    - b. ROOF TOPS: PRE-CONSTRUCTION AND POST-CONSTRUCTION VISUAL INSPECTION AND PHOTOGRAPHS OF THE ROOF AND INTERIOR TO DETERMINE AND DOCUMENT CONDITIONS; ROOF TOP CONSTRUCTION INSPECTIONS AS REQUIRED BY THE JURISDICTION; PHOTOGRAPHS OF CABLE TRAY AND/OR ICE BRIDGE; PHOTOGRAPHS OF DOGHOUSE/CABLE EXIT FROM ROOF;
    - c. SITE LAYOUT - PHOTOGRAPHS OF THE OVERALL COMPOUND, INCLUDING EQUIPMENT PLATFORM FROM ALL FOUR CORNERS.
    - d. FINISHED UTILITIES: CLOSE-UP PHOTOGRAPHS OF THE PPC BREAKER PANEL; CLOSE-UP PHOTOGRAPH OF THE INSIDE OF THE TELCO PANEL AND NIU; CLOSE-UP PHOTOGRAPH OF THE POWER METER AND DISCONNECT; PHOTOS OF POWER AND TELCO ENTRANCE TO COMPANY ENCLOSURE; PHOTOGRAPHS AT METER BOX AND/OR FACILITY DISTRIBUTION PANEL.

**PROJECT PHOTOGRAPHS:**

- A. PROVIDE PROJECT CLOSEOUT GENERAL ARRANGEMENT PHOTOS OF ALL NEW WORK. THE FOLLOWING LIST REPRESENTS MINIMUM REQUIREMENTS AND MINIMUM QUANTITY. ADDITIONAL PHOTOS MAY BE REQUIRED TO ADEQUATELY DOCUMENT THE WORK.
1. ASR AND RF MPE SIGNAGE (IF NOT IN PLACE, SUPPLIER NOTIFIES EMS FIELD REPRESENTATIVE)
  2. BACK OF ANTENNAS AND RRUS (1 EACH SECTOR)
  3. BACK OF ANTENNAS AND RRUS (1 EACH SECTOR) CLOSE UP SHOWING WEATHERPROOFING AND GROUNDING (AS REQUIRED). CLOSE-UP OF BACK SIDE OF EACH PERMANENT RRU SHOWING SERIAL NUMBER/BAR CODE.
  4. VIEW (1 EACH SECTOR) ALONG THE AZIMUTH AND TILT OF THE ANTENNAS
  5. TOP OF TOWER FROM GROUND, 1 EACH SECTOR
  6. MAINLINE HYBRID CABLE ROUTE DOWN TOWER SHOWING FASTENERS AND SUPPORT
  7. MAINLINE/HYBRID CABLE ROUTE ALONG ICE BRIDGE OR IN CABLE TRAY SHOWING FASTENERS AND SUPPORT
  8. GROUND MOUNTED RRU RACKS (FRONT AND BACK)
  9. FRONT, SIDE AND BACK ELEVATIONS OF ALL GROUND CABINETS
  10. VIEW OF COMPOUND FROM A DISTANCE
    11. VIEW OF EACH GROUND CABINET (POWER, RF, FIBER SPOOL, PPC POWER, PPC TELCO WITH DOOR OPEN)
    12. BACKHAUL FIBER MEET-ME-POINT AND CONDUIT ROUTE (MICROWAVE INSTALLATION IF NOT FIBER)
    13. AAV NETWORK INTERFACE DEVICE OR MICROWAVE RADIO INSTALLATION

**DEFICIENCY CORRECTIONS:**

CONTRACTOR IS RESPONSIBLE FOR ALL CORRECTIONS TO DEFICIENCIES IDENTIFIED THROUGH TESTING, REVIEW OF SUBMITTALS, INSPECTIONS AND CLOSEOUT REVIEWS.

**SECTION 01 500 - PROJECT REPORTING**

**WEEKLY REPORTS:**

- A. CONTRACTOR SHALL REPORT TO SPRINT AT MINIMUM ON A WEEKLY BASIS VIA SITERRA BY UPDATING ALL APPLICABLE POST END KEEPING MILESTONES WITH ACTUAL AND FORECASTED COMPLETION DATES.
- B. ADDITIONAL REQUIREMENTS FOR REPORTING MAY BE IDENTIFIED ELSEWHERE OR REQUIRED BY THE SCOPE OF SERVICES OR SPRINTS LOCAL MARKET CONSTRUCTION MANAGER. THIS INFORMATION WILL PROVIDE A BASIS FOR PROGRESS MONITORING AND PAYMENT.

**PROJECT CONFERENCE CALLS:**

SPRINT MAY HOLD PERIODIC PROJECT CONFERENCE CALLS. CONTRACTOR WILL BE REQUIRED TO COMMUNICATE SITE STATUS, MILESTONE COMPLETIONS AND UPCOMING MILESTONE PROJECTIONS, AND ANSWER ANY OTHER SITE STATUS QUESTIONS AS NECESSARY.

**FINAL PROJECT ACCEPTANCE:** PRIOR TO SPRINTS FINAL PROJECT ACCEPTANCE. ALL REQUIRED MILESTONE ACTUALS MUST BE UPDATED IN SITERRA AND ALL REQUIRED REPORTING TASKS MUST BE COMPLETE.

**SECTION 11 700 - ANTENNA ASSEMBLY, REMOTE RADIO UNITS AND CABLE INSTALLATION**

**SUMMARY:**

THIS SECTION SPECIFIES INSTALLATION OF ANTENNAS, RRUS, AND CABLE EQUIPMENT, INSTALLATION, AND TESTING OF COAXIAL FIBER CABLE.

**ANTENNAS AND RRUS:**

THE NUMBER AND TYPE OF ANTENNAS AND RRUS TO BE INSTALLED IS DETAILED ON THE CONSTRUCTION DRAWINGS.

**HYBRID CABLE:**

HYBRID CABLE WILL BE DC/FIBER AND FURNISHED FOR INSTALLATION AT EACH SITE. CABLE SHALL BE INSTALLED PER THE CONSTRUCTION DRAWINGS AND THE APPLICABLE MANUFACTURER'S REQUIREMENTS.

**JUMPERS AND CONNECTORS:**

FURNISH AND INSTALL 1/2" COAX JUMPER CABLES BETWEEN THE RRU'S AND ANTENNAS. JUMPERS SHALL BE TYPE LDF 4, FLC 1 2-50, CR 540, OR FXL 540. SUPER-FLEX CABLES ARE NOT ACCEPTABLE. JUMPERS BETWEEN THE RRUS AND ANTENNAS OR TOWER TOP AMPLIFIERS SHALL CONSIST OF 1/2 INCH FOAM DIELECTRIC, OUTDOOR RATED COAXIAL CABLE, MIN. LENGTH FOR JUMPER SHALL BE 10'-0".

**REMOTE ELECTRICAL TILT (RET) CABLES:**

**MISCELLANEOUS:**

INSTALL SPLITTERS, COMBINERS, FILTERS PER RF DATA SHEET, FURNISHED BY SPRINT.

**ANTENNA INSTALLATION:**

THE CONTRACTOR SHALL ASSEMBLE ALL ANTENNAS ONSITE IN ACCORDANCE WITH THE INSTRUCTIONS SUPPLIED BY THE MANUFACTURER. ANTENNA HEIGHT, AZIMUTH, AND FEED ORIENTATION INFORMATION SHALL BE A DESIGNATED ON THE CONSTRUCTION DRAWINGS.

A. THE CONTRACTOR SHALL POSITION THE ANTENNA ON TOWER PIPE MOUNTS SO THAT THE BOTTOM STRUT IS LEVEL. THE PIPE MOUNTS SHALL BE PLUMB TO WITHIN 1 DEGREE.

B. ANTENNA MOUNTING REQUIREMENTS: PROVIDE ANTENNA MOUNTING HARDWARE AS INDICATED ON THE DRAWINGS.

**HYBRID CABLE INSTALLATION:**

A. THE CONTRACTOR SHALL ROUTE, TEST, AND INSTALL ALL CABLES AS INDICATED ON THE CONSTRUCTION DRAWINGS AND IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS.

B. THE INSTALLED RADIUS OF THE CABLES SHALL NOT BE LESS THAN THE MANUFACTURER'S SPECIFICATIONS FOR BENDING RADIUS.

C. EXTREME CARE SHALL BE TAKEN TO AVOID DAMAGE TO THE CABLES DURING HANDLING AND INSTALLATION.

1. FASTENING MAIN HYBRID CABLES: ALL CABLES SHALL BE INSTALLED INSIDE MONOPOLE WITH CABLE SUPPORT GRIPS AS REQUIRED BY THE MANUFACTURER.
2. FASTENING INDIVIDUAL FIBER AND DC CABLES ABOVE BREAKOUT ENCLOSURE (MEDUSA), WITHIN THE MMBS CABINET AND ANY INTERMEDIATE DISTRIBUTION BOXES:
  - a. FIBER: SUPPORT FIBER BUNDLES USING 1/2" VELCRO STRAPS OF THE REQUIRED LENGTH AT 18" O.C. STRAPS SHALL BE UV, OIL AND WATER RESISTANT AND SUITABLE FOR INDUSTRIAL INSTALLATIONS AS MANUFACTURED BY TEXTOL OR APPROVED EQUAL.
  - b. DC: SUPPORT DC BUNDLES WITH ZIP TIES OF THE ADEQUATE LENGTH. ZIP TIES TO BE UV STABILIZED, BLACK NYLON, WITH TENSILE STRENGTH AT 12,000 PSI AS MANUFACTURED BY NELCO PRODUCTS OR EQUAL.
3. FASTENING JUMPERS: SECURE JUMPERS TO THE SIDE ARMS OR HEAD FRAMES USING STAINLESS STEEL TIE WRAPS OR STAINLESS STEEL BUTTERFLY CLIPS.
4. CABLE INSTALLATION:
  - a. INSPECT CABLE PRIOR TO USE FOR SHIPPING DAMAGE, NOTIFY THE CONSTRUCTION MANAGER.
  - b. CABLE ROUTING: CABLE INSTALLATION SHALL BE PLANNED TO ENSURE THAT THE LINES WILL BE PROPERLY ROUTED IN THE CABLE ENVELOP AS INDICATED ON THE DRAWINGS. AVOID TWISTING AND CROSSOVERS.
  - c. HOIST CABLE USING PROPER HOISTING GRIPS. DO NOT EXCEED MANUFACTURER'S RECOMMENDED MAXIMUM BEND RADIUS.
5. GROUNDING OF TRANSMISSION LINES: ALL TRANSMISSION LINES SHALL BE GROUNDED AS INDICATED ON DRAWINGS.
6. HYBRID CABLE COLOR CODING: ALL COLOR CODING SHALL BE AS REQUIRED IN TS 0200 (CURRENT VERSION).
7. HYBRID CABLE LABELING: INDIVIDUAL HYBRID AND DC BUNDLES SHALL BE LABELED ALPHA-NUMERICALLY ACCORDING TO SPRINT CELL SITE ENGINEERING NOTICE - EN 2012-001, REV 1

**WEATHERPROOFING EXTERIOR CONNECTORS AND HYBRID CABLE GROUND KITS:**

A. ALL FIBER & COAX CONNECTORS AND GROUND KITS SHALL BE WEATHERPROOFED.

B. WEATHERPROOFED USING ONE OF THE FOLLOWING METHODS. ALL INSTALLATIONS MUST BE DONE IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS AND INDUSTRY BEST PRACTICES.

1. COLD SHRINK: ENCOMPASS CONNECTOR IN COLD SHRINK TUBING AND PROVIDE A DOUBLE WRAP OF 2" ELECTRICAL TAPE EXTENDING 2" BEYOND TUBING. PROVIDE 3M COLD SHRINK CXS SERIES OR EQUAL.
2. SELF-AMALGAMATING TAPE: CLEAN SURFACES. APPLY A DOUBLE WRAP OF SELF-AMALGAMATING TAPE 2" BEYOND CONNECTOR. APPLY A SECOND WRAP OF SELF-AMALGAMATING TAPE IN OPPOSITE DIRECTION. APPLY DOUBLE WRAP OF 2" WIDE ELECTRICAL TAPE EXTENDING 2" BEYOND THE SELF-AMALGAMATING TAPE.
3. 3M SLIM LOCK CLOSURE 716: SUBSTITUTIONS WILL NOT BE ALLOWED.
4. OPEN FLAME ON JOB SITE IS NOT ACCEPTABLE

**SECTION 11 800 - INSTALLATION OF MULTIMODAL BASE STATIONS (MMBS) AND RELATED EQUIPMENT**

**SUMMARY:**

A. THIS SECTION SPECIFIES MMBS CABINETS, POWER CABINETS, AND INTERNAL EQUIPMENT INCLUDING BY NOT LIMITED TO RECTIFIERS, POWER DISTRIBUTION UNITS, BASE BAND UNITS, SURGE ARRESTORS, BATTERIES, AND SIMILAR EQUIPMENT FURNISHED BY THE COMPANY FOR INSTALLATION BY THE CONTRACTOR (OFCI).

B. CONTRACTOR SHALL PROVIDE AND INSTALL ALL MISCELLANEOUS MATERIALS AND PROVIDE ALL LABOR REQUIRED FOR INSTALLATION EQUIPMENT IN EXISTING CABINET OR NEW CABINET AS SHOWN ON DRAWINGS AND AS REQUIRED BY THE APPLICABLE INSTALLATION MOPS.

C. COMPLY WITH MANUFACTURER'S INSTALLATION AND START-UP REQUIREMENTS.

**DC CIRCUIT BREAKER LABELING**

A. NEW DC CIRCUIT IS REQUIRED IN MMBS CABINET SHALL BE CLEARLY IDENTIFIED AS TO RRU BEING SERVICED.

**SECTION 26 100 - BASIC ELECTRICAL REQUIREMENTS**

**SUMMARY:**

THIS SECTION SPECIFIES BASIC ELECTRICAL REQUIREMENTS FOR SYSTEMS AND COMPONENTS

**QUALITY ASSURANCE:**

A. ALL EQUIPMENT FURNISHED UNDER DIVISION 26 SHALL CARRY UL LABELS AND LISTINGS WHERE SUCH LABELS AND LISTINGS ARE AVAILABLE IN THE INDUSTRY.

B. MANUFACTURERS OF EQUIPMENT SHALL HAVE A MINIMUM OF THREE YEARS EXPERIENCE WITH THEIR EQUIPMENT INSTALLED AND OPERATING IN THE FIELD IN A USE SIMILAR TO THE PROPOSED USE FOR THIS PROJECT.

C. MATERIALS AND EQUIPMENT: ALL MATERIALS AND EQUIPMENT SPECIFIED IN DIVISION 26 OF THE SAME TYPE SHALL BE OF THE SAME MANUFACTURER AND SHALL BE NEW, OF THE BEST QUALITY AND DESIGN, AND FREE FROM DEFECTS.

**SUPPORTING DEVICES:**

A. MANUFACTURED STRUCTURAL SUPPORT MATERIALS: SUBJECT TO COMPLIANCE WITH REQUIREMENTS, PROVIDE PRODUCTS BY THE FOLLOWING:

1. ALLIED TUBE AND CONDUIT.
2. B-LINE SYSTEM.
3. UNISTRUT DIVERSIFIED PRODUCTS.
4. THOMAS & BETTS.

B. FASTENERS: TYPES, MATERIALS, AND CONSTRUCTION FEATURES AS FOLLOWS:

1. EXPANSION ANCHORS: CARBON STEEL WEDGE OR SLEEVE TYPE.
2. POWER-DRIVEN THREADED STUDS: HEAT-TREATED STEEL, DESIGNED SPECIFICALLY FOR THE INTENDED SERVICE.
3. FASTEN BY MEANS OF WOOD SCREWS ON WOOD.
4. TOGGLE BOLTS ON HOLLOW MASONRY UNITS.
5. CONCRETE INSERTS OR EXPANSION BOLTS ON CONCRETE OR SOLID MASONRY.
6. MACHINE SCREWS, WELDED THREADED STUDS, OR SPRING-TENSION CLAMPS ON STEEL.
7. EXPLOSIVE DEVICES FOR ATTACHING HANGERS TO STRUCTURE SHALL NOT BE PERMITTED.
8. DO NOT WELD CONDUIT, PIPE STRAPS, OR ITEMS OTHER THAN THREADED STUDS TO STEEL STRUCTURES.
9. IN PARTITIONS OF LIGHT STEEL CONSTRUCTION, USE SHEET METAL SCREWS.



1 INTERNATIONAL BLVD, SUITE 800  
MAHWAH, NJ 07495



123 Broadway, Woodcliff Lake, NJ 07677  
608-643-4100 www.Ramaker.com


Sauk City, WI • Willmar, MN  
Woodcliff Lake, NJ • Bayamon, PR

**Charles Cherundolo Consulting, Inc.**

713 Clover Lane, Moscow, PA 18444  
Phone: 570-840-5084 Fax: 570-842-5592

**Certification & Seal:**

I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



*James R. Skowronski* Signature: \_\_\_\_\_ Date: 4/25/2019

| MARK | DATE     | DESCRIPTION      |
|------|----------|------------------|
| 0    | 04/25/19 | FINAL CDs ISSUED |

ISSUE PHASE: FINAL DATE ISSUED: 04/25/2019

PROJECT TITLE:  
**(R2E) CT60-001 to CTO065  
WILTON-RICHDALE TERRACE  
CT60XCOO1-R**

PROJECT INFORMATION:  
24 1/2 RICHDALE DRIVE  
WILTON, CT 06897  
FAIRFIELD COUNTY

SHEET TITLE:  
**SPRINT SPECIFICATIONS**

SCALE: NONE

PROJECT NUMBER: 28753  
SHEET NUMBER: SP-2

SUPPORTING DEVICES:

- A. INSTALL SUPPORTING DEVICES TO FASTEN ELECTRICAL COMPONENTS SECURELY AND PERMANENTLY IN ACCORDANCE WITH NEC.
- B. COORDINATE WITH THE BUILDING STRUCTURAL SYSTEM AND WITH OTHER TRADES.
- C. UNLESS OTHERWISE INDICATED ON THE DRAWINGS, FASTEN ELECTRICAL ITEMS AND THEIR SUPPORTING HARDWARE SECURELY TO THE STRUCTURE IN ACCORDANCE WITH THE FOLLOWING:
  - 1. ENSURE THAT THE LOAD APPLIED BY ANY FASTENER DOES NOT EXCEED 25 PERCENT OF THE PROOF TEST LOAD.
  - 2. USE VIBRATION AND SHOCK-RESISTANT FASTENERS FOR ATTACHMENTS TO CONCRETE SLABS.

ELECTRICAL IDENTIFICATION:

- A. UPDATE AND PROVIDE TYPED CIRCUIT BREAKER SCHEDULES IN THE MOUNTING BRACKET, INSIDE DOORS OF AC PANEL BOARDS WITH ANY CHANGES MADE TO THE AC SYSTEM.
- B. BRANCH CIRCUITS FEEDING AVIATION OBSTRUCTION LIGHTING EQUIPMENT SHALL BE CLEARLY IDENTIFIED AS SUCH AT THE BRANCH CIRCUIT PANELBOARD.

SECTION 26 200 - ELECTRICAL MATERIALS AND EQUIPMENT

- A. RIGID GALVANIZED STEEL (RGS) CONDUIT SHALL BE USED FOR EXTERIOR LOCATIONS ABOVE GROUND AND IN UNFINISHED INTERIOR LOCATIONS AND FOR UNDERGROUND RUNS. RIGID CONDUIT AND FITTINGS SHALL BE STEEL, COATED WITH ZINC EXTERIOR AND INTERIOR BY THE HOT DIP GALVANIZING PROCESS. CONDUIT SHALL BE PRODUCED TO ANSI SPECIFICATIONS C80.1, FEDERAL SPECIFICATION WW-C-58.1 AND SHALL BE LISTED WITH THE UNDERWRITERS' LABORATORIES. FITTINGS SHALL BE THREADED - SET SCREW OR COMPRESSION FITTINGS WILL NOT BE ACCEPTABLE. RGS CONDUITS SHALL BE MANUFACTURED BY ALLIED, REPUBLIC OR WHEATLAND.
- B. UNDERGROUND CONDUIT IN CONCRETE SHALL BE POLYVINYLCHLORIDE (PVC) SUITABLE FOR DIRECT BURIAL AS APPLICABLE. JOINTS SHALL BE BELLED, AND FLUSH SOLVENT WELDED IN ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS. CONDUIT SHALL BE CARLON ELECTRICAL PRODUCTS OR APPROVED EQUAL.
- C. TRANSITIONS BETWEEN PVC AND RIGID (RGS) SHALL BE MADE WITH PVC COATED METALLIC LONG SWEEP RADIUS ELBOWS.
- D. EMT OR RIGID GALVANIZED STEEL CONDUIT MAY BE USED IN FINISHED SPACES CONCEALED IN WALLS AND CEILINGS. EMT SHALL BE MILD STEEL, ELECTRICALLY WELDED, ELECTRO-GALVANIZED OR HOT-DIPPED GALVANIZED AND PRODUCED TO ANSI SPECIFICATION C80.3, FEDERAL SPECIFICATION WW-C-563, AND SHALL BE UL LISTED. EMT SHALL BE MANUFACTURED BY ALLIED, REPUBLIC OR WHEATLAND, OR APPROVED EQUAL. FITTINGS SHALL BE METALLIC COMPRESSION. SET SCREW CONNECTIONS SHALL NOT BE ACCEPTABLE.
- E. LIQUID TIGHT FLEXIBLE METALLIC CONDUIT SHALL BE USED FOR FINAL CONNECTION TO EQUIPMENT. FITTINGS SHALL BE METALLIC GLAND TYPE COMPRESSION FITTINGS, MAINTAINING THE INTEGRITY OF CONDUIT SYSTEM. SET SCREW CONNECTIONS SHALL NOT BE ACCEPTABLE. MAXIMUM LENGTH OF FLEXIBLE CONDUIT SHALL NOT EXCEED 6- FEET. LFMC SHALL BE PROTECTED AND SUPPORTED AS REQUIRED BY NEC. MANUFACTURERS OF FLEXIBLE CONDUITS SHALL BE CAROL, ANACONDA METAL HOSE OR UNIVERSAL METAL HOSE, OR APPROVED EQUAL.
- F. MINIMUM SIZE CONDUIT SHALL BE 3/4 INCH (21MM).

HUBS AND BOXES:

- A. AT ENTRANCES TO CABINETS OR OTHER EQUIPMENT NOT HAVING INTEGRAL THREADED HUBS PROVIDE METALLIC THREADED HUBS OF THE SIZE AND CONFIGURATION REQUIRED. HUB SHALL INCLUDE LOCKNUT AND NEOPRENE O-RING SEAL. PROVIDE IMPACT RESISTANT 105 DEGREE C PLASTIC BUSHINGS TO PROTECT CABLE INSULATION.
- B. CABLE TERMINATION FITTINGS FOR CONDUIT
  - 1. CABLE TERMINATORS FOR RGS CONDUITS SHALL BE TYPE CRC BY O-Z/GEDNEY OR EQUAL BY ROXTEC.
  - 2. CABLE TERMINATORS FOR LFMC SHALL BE ETCO - CL2075; OR MADE FOR THE PURPOSE PRODUCTS BY ROXTEC.
- C. EXTERIOR PULL BOXES AND PULL BOXES IN INTERIOR INDUSTRIAL AREAS SHALL BE PLATED CAST ALLOY, HEAVY DUTY, WEATHERPROOF, DUST PROOF, WITH GASKET, PLATED IRON ALLOY COVER AND STAINLESS STEEL COVER SCREWS. CROUSE-HINDS WAB SERIES OR EQUAL.
- D. CONDUIT OUTLET BODIES SHALL BE PLATED CAST ALLOY WITH SIMILAR GASKET COVERS. OUTLET BODIES SHALL BE OF THE CONFIGURATION AND SIZE SUITABLE FOR THE APPLICATION. PROVIDE CROUSE-HINDS FORM 8 OR EQUAL.
- E. MANUFACTURER FOR BOXES AND COVERS SHALL BE HOFFMAN, SQUARE "D", CROUSE-HINDS, COOPER, ADALET, APPLETON, O-Z GEDNEY, RACO, OR APPROVED EQUAL.

SUPPLEMENTAL GROUNDING SYSTEM:

- A. FURNISH AND INSTALL A SUPPLEMENTAL GROUNDING SYSTEM TO THE EXTENT INDICATED ON THE DRAWINGS. SUPPORT SYSTEM WITH NON-MAGNETIC STAINLESS STEEL CLIPS WITH RUBBER GROMMETS. GROUNDING CONNECTORS SHALL BE TINNED COPPER WIRE, SIZES AS INDICATED ON THE DRAWINGS. PROVIDE STRANDED OR SOLID BARE OR INSULATED CONDUCTORS EXCEPT AS OTHERWISE NOTED.
- B. SUPPLEMENTAL GROUNDING SYSTEM: ALL CONNECTIONS TO BE MADE WITH CAD WELDS, EXCEPT AT EQUIPMENT USE LUGS OR OTHER AVAILABLE GROUNDING MEANS AS REQUIRED BY MANUFACTURER; AT GROUND BARS USE TWO HOLE SPADES WITH NO-OX.
- C. STOLEN GROUND-BARS: IN THE EVENT OF STOLEN GROUND BARS, CONTACT SPRINT CM FOR REPLACEMENT INSTRUCTION USING THREADED ROD KITS.

EXISTING STRUCTURE:

- A. EXISTING EXPOSED WIRING AND ALL EXPOSED OUTLETS, RECEPTACLES, SWITCHES, DEVICES, BOXES, AND OTHER EQUIPMENT THAT ARE NOT TO BE UTILIZED IN THE COMPLETED PROJECT SHALL BE REMOVED OR DE-ENERGIZED AND CAPPED IN THE WALL, CEILING, OR FLOOR SO THAT THEY ARE CONCEALED AND SAFE. WALL, CEILING, OR FLOOR SHALL BE PATCHED TO MATCH THE ADJACENT CONSTRUCTION.

CONDUIT AND CONDUCTOR INSTALLATION:

- A. CONDUITS SHALL BE FASTENED SECURELY IN PLACE WITH APPROVED NON-PERFORATED STRAPS AND HANGERS. EXPLOSIVE DEVICES FOR ATTACHING HANGERS TO STRUCTURE WILL NOT BE PERMITTED. CLOSELY FOLLOW THE LINES OF THE STRUCTURE, MAINTAIN CLOSE PROXIMITY TO THE STRUCTURE AND KEEP CONDUITS IN TIGHT ENVELOPES. CHANGES IN DIRECTION TO ROUTE AROUND OBSTACLES SHALL BE MADE WITH CONDUIT OUTLET BODIES. CONDUIT SHALL BE INSTALLED IN A NEAT AND WORKMANLIKE MANNER, PARALLEL AND PERPENDICULAR TO STRUCTURE WALL AND CEILING LINES. ALL CONDUIT SHALL BE FISHED TO CLEAR OBSTRUCTIONS. ENDS OF CONDUITS SHALL BE TEMPORARILY CAPPED TO PREVENT CONCRETE, PLASTER OR DIRT FROM ENTERING. CONDUITS SHALL BE RIGIDLY CLAMPED TO BOXES BY GALVANIZED MALLEABLE IRON BUSHING ON INSIDE AND GALVANIZED MALLEABLE IRON LOCKNUT ON OUTSIDE AND INSIDE.
- B. CONDUCTORS SHALL BE PULLED IN ACCORDANCE WITH ACCEPTED GOOD PRACTICE.



1 INTERNATIONAL BLVD, SUITE 800  
 MAHWAH, NJ 07495



123 Broadway, Woodcliff Lake, NJ 07677  
 608-643-4100 www.Ramaker.com


Sauk City, WI • Willmar, MN  
 Woodcliff Lake, NJ • Bayamon, PR

**Charles Cherundolo Consulting, Inc.**

713 Clover Lane, Moscow, PA 18444  
 Phone: 570-840-5084 Fax: 570-842-5592

Certification & Seal:

I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



*James R. Skowronski* 4/25/2019  
 Signature: Date:

|  |  |  |
|--|--|--|
|  |  |  |
|  |  |  |
|  |  |  |
|  |  |  |

|   |          |                  |
|---|----------|------------------|
| 0 | 04/25/19 | FINAL CDs ISSUED |
|---|----------|------------------|

|             |       |             |            |
|-------------|-------|-------------|------------|
| ISSUE PHASE | FINAL | DATE ISSUED | 04/25/2019 |
|-------------|-------|-------------|------------|

PROJECT TITLE:  
 (R2E) CT60-001 to CTO065  
 WILTON-RICHDALE TERRACE  
 CT60XCOO1-R


PROJECT INFORMATION:  
 24 1/2 RICHDALE DRIVE  
 WILTON, CT 06897  
 FAIRFIELD COUNTY

SHEET TITLE:  
 SPRINT SPECIFICATIONS

SCALE: NONE

|                |       |
|----------------|-------|
| PROJECT NUMBER | 28753 |
| SHEET NUMBER   | SP-3  |





SITE PLAN  
 SCALE: 1" = 10'

1



**Sprint**

1 INTERNATIONAL BLVD, SUITE 800  
 MAHWAH, NJ 07495

**RAMAKER & ASSOCIATES, INC.**  
 100% EMPLOYEE-OWNED


123 Broadway, Woodcliff Lake, NJ 07677  
 608-643-4100 www.Ramaker.com

Sauk City, WI • Willmar, MN  
 Woodcliff Lake, NJ • Bayamon, PR

**Charles Cherundolo Consulting, Inc.**

713 Clover Lane, Moscow, PA 18444  
 Phone: 570-840-5084 Fax: 570-842-5592

*Certification & Seal:*  
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



*James R. Skowronski*  
 Signature: \_\_\_\_\_ Date: 4/25/2019

|  |  |  |
|--|--|--|
|  |  |  |
|  |  |  |
|  |  |  |
|  |  |  |


|   |          |                  |
|---|----------|------------------|
| 0 | 04/25/19 | FINAL CDs ISSUED |
|---|----------|------------------|

|             |       |             |            |
|-------------|-------|-------------|------------|
| ISSUE PHASE | FINAL | DATE ISSUED | 04/25/2019 |
|-------------|-------|-------------|------------|

PROJECT TITLE:  
 (R2E) CT60-001 to CT0065  
 WILTON-RICHDALE TERRACE  
 CT60XCOO1-R

PROJECT INFORMATION:  
 24 1/2 RICHDALE DRIVE  
 WILTON, CT 06897  
 FAIRFIELD COUNTY

SHEET TITLE:  
 SITE PLAN



PROJECT NUMBER: 28753  
 SHEET NUMBER: A-1



**Sprint**

1 INTERNATIONAL BLVD, SUITE 800  
 MAHWAH, NJ 07495

**RAMAKER & ASSOCIATES, INC.**  
 100% EMPLOYEE-OWNED


123 Broadway, Woodcliff Lake, NJ 07677  
 608-643-4100 www.Ramaker.com

Sauk City, WI • Willmar, MN  
 Woodcliff Lake, NJ • Bayamon, PR

**Charles Cherundolo Consulting, Inc.**

713 Clover Lane, Moscow, PA 18444  
 Phone: 570-840-5084 Fax: 570-842-5592

Certification & Seal:  
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



*James R. Skowronski*  
 Signature: \_\_\_\_\_ Date: 4/25/2019


| MARK | DATE     | DESCRIPTION      |
|------|----------|------------------|
| 0    | 04/25/19 | FINAL CDs ISSUED |

ISSUE PHASE: FINAL DATE ISSUED: 04/25/2019


PROJECT TITLE:  
 (R2E) CT60-001 to CTO065  
 WILTON-RICHDALE TERRACE  
 CT60XCOO1-R

PROJECT INFORMATION:  
 24 1/2 RICHDALE DRIVE  
 WILTON, CT 06897  
 FAIRFIELD COUNTY

SHEET TITLE:  
 EQUIPMENT PLAN




PROJECT NUMBER: 28753  
 SHEET NUMBER: A-2




**EQUIPMENT PLAN**  
 SCALE: 1" = 2.5'




This document contains confidential or proprietary information of Ramaker & Associates, Inc. Neither this document nor the information herein is to be reproduced, distributed, used or disclosed either in whole or in part except as authorized by Ramaker and Associates, Inc.




**ANTENNA & RRH MOUNTING DETAILS**  
 SCALE: NTS



**BUILDING ELEVATION**  
 SCALE: 1" = 30'



**EXISTING ANTENNA ARRAY**  
 SCALE: NTS



**PROPOSED ANTENNA ARRAY**  
 SCALE: NTS



1 INTERNATIONAL BLVD, SUITE 800  
 MAHWAH, NJ 07495



100% EMPLOYEE-OWNED  
 123 Broadway, Woodcliff Lake, NJ 07677  
 608-643-4100 www.Ramaker.com  
 Sauk City, WI • Willmar, MN  
 Woodcliff Lake, NJ • Bayamon, PR

**Charles Cherundolo Consulting, Inc.**

713 Clover Lane, Moscow, PA 18444  
 Phone: 570-840-5084 Fax: 570-842-5592

Certification & Seal:  
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.




Signature: *James R. Skowronski* Date: 4/25/2019

| MARK        | DATE     | DESCRIPTION            |
|-------------|----------|------------------------|
| 0           | 04/25/19 | FINAL CDs ISSUED       |
| ISSUE PHASE | FINAL    | DATE ISSUED 04/25/2019 |

PROJECT TITLE:  
 (R2E) CT60-001 to CT0065  
 WILTON-RICHDALE TERRACE  
 CT60XCOO1-R

PROJECT INFORMATION:  
 24 1/2 RICHDALE DRIVE  
 WILTON, CT 06897  
 FAIRFIELD COUNTY

SHEET TITLE:  
 POLE ELEVATIONS &  
 ANTENNA DETAILS



PROJECT NUMBER: 28753  
 SHEET NUMBER: A-3

| 800/1900/2.5 EQUIPMENT SCHEDULE |          |  |         |            |  |                        |              |             |
|---------------------------------|----------|--|---------|------------|--|------------------------|--------------|-------------|
| SECTOR                          | POSITION | ANTENNA MAKE/MODEL                                     | AZIMUTH | CENTERLINE | RRH  | CABLE TYPE             | CABLE LENGTH | JUMPER TYPE |
| ALPHA                           | 1        | (1) RELOCATED WHIP ANTENNA                             | -       | -          | -  | -                      | -            | -           |
|                                 | 2        | (1) PROPOSED TRIBAND PANEL ANTENNA (KMW ETCR-654L12H6) | 50°     | 67'-0"     | (1) RELOCATED 800 RRH (ALU RRH-2x50-800)<br>(1) RELOCATED 1900 RRH (ALU RRH-4x45-1900) | EXISTING HYBRIFLEX     | N/A          | EXISTING    |
|                                 | 3        | -  | -       | -          | (1) PROPOSED 800 RRH (ALU RRH-2x50-800)<br>(1) PROPOSED 2500 RRH (NOKIA FZHN)          | (1) PROPOSED HYBRIFLEX | 144'         | 8' HYBRID   |
| BETA                            | 1        | -  | -       | -          | -  | -                      | -            | -           |
|                                 | 2        | (1) PROPOSED TRIBAND PANEL ANTENNA (KMW ETCR-654L12H6) | 160°    | 67'-0"     | (1) RELOCATED 800 RRH (ALU RRH-2x50-800)<br>(1) RELOCATED 1900 RRH (ALU RRH-4x45-1900) | EXISTING HYBRIFLEX     | N/A          | EXISTING    |
|                                 | 3        | -  | -       | -          | (1) PROPOSED 800 RRH (ALU RRH-2x50-800)<br>(1) PROPOSED 2500 RRH (NOKIA FZHN)          | SHARED W/ ALPHA        | 144'         | 8' HYBRID   |
| GAMMA                           | 1        | -  | -       | -          | -  | -                      | -            | -           |
|                                 | 2        | (1) PROPOSED TRIBAND PANEL ANTENNA (KMW ETCR-654L12H6) | 250°    | 67'-0"     | (1) RELOCATED 800 RRH (ALU RRH-2x50-800)<br>(1) RELOCATED 1900 RRH (ALU RRH-4x45-1900) | EXISTING HYBRIFLEX     | N/A          | EXISTING    |
|                                 | 3        | -  | -       | -          | (1) PROPOSED 800 RRH (ALU RRH-2x50-800)<br>(1) PROPOSED 2500 RRH (NOKIA FZHN)          | SHARED W/ ALPHA        | 144'         | 8' HYBRID   |

\*EQUIPMENT SCHEDULE WAS GENERATED BY RAMAKER & ASSOCIATES FROM PLAN OF RECORD (POR) PROVIDED BY SPRINT. CONTRACTOR SHALL VERIFY AND OBTAIN FINAL RFDS FROM SPRINT CONSTRUCTION MANAGER PRIOR TO CONSTRUCTION.

NOTES:

- GENERAL CONTRACTOR TO FIELD VERIFY AZIMUTH AND C/L HEIGHT AND MECHANICAL DOWNTILT. IF DIFFERENT THAN CALLED OUT BELOW, HALT ANTENNA WORK FOR ONE HOUR, CALL SPRINT RF ENGINEER (OR MANAGER IF RF ENGINEER DOES NOT ANSWER, BUT STILL LEAVE A MESSAGE TO RF ENGINEER) USING CONTACT INFORMATION ABOVE FOR FURTHER INSTRUCTIONS. IF SPRINT DOES NOT RESPOND WITHIN ONE HOUR, PLACE 2.5GHZ ANTENNA AT SAME C/L HEIGHT AS 1.9GHZ ANTENNA AND EMAIL CORRECT C/L HEIGHT AND AZIMUTH TO SPRINT RF ENGINEER. UPDATE AS-BUILT DRAWING WITH CORRECT C/L HEIGHT. ALSO EMAIL CORRECT 1.9GHZ AND 800MHZ ANTENNA C/L HEIGHT, AZIMUTH AND MECHANICAL DOWNTILT TO RF ENGINEER.
- AISG TESTS TO VERIFY OPERATION IS TO BE PERFORMED AFTER FINAL INSTALLATION OF ANTENNAS AND AISG CABLES HAVE BEEN CONNECTED. VERIFY OPERATION OF ALL EXISTING SPRINT AISG EQUIPMENT INCLUDING 800MHZ, 1.9GHZ AND 2.5GHZ. TEST TO INCLUDE COMPLETE DOWNTILT, AZIMUTH (IF APPLICABLE) AND BEAMWIDTH SWINGS (IF APPLICABLE). DOCUMENT AISG TEST RESULTS IN COAX SWEEP TEST SPREADSHEET.
- GENERAL CONTRACTOR MUST ENSURE THAT NO OBJECT IS LOCATED WITHIN 45 DEGREES OF LEFT AND RIGHT OF FRONT OF ANTENNA OR 7 DEGREES UP AND DOWN FROM CENTER OF ANTENNA. IF THIS IS NOT POSSIBLE, CONTACT RF ENGINEER FOR FURTHER INSTRUCTION. IN ADDITION, 2.5GHZ ANTENNA IS NOT TO BE PLACED IN FRONT OF ANY OTHER ANTENNA USING THE SAME 45 DEGREE RULE. THIS INCLUDES SPRINT AND NON-SPRINT ANTENNAS.
- 2.5GHZ ANTENNA MUST BE AT LEAST 6" FROM 1.9GHZ ANTENNA, 30" FROM 800MHZ ANTENNA AND 30" FROM DUAL BAND 1.9GHZ AND 800MHZ ANTENNA.
- GENERAL CONTRACTOR IS REQUIRED TO USE A DIGITAL ALIGNMENT TOOL TO SET AZIMUTH, ROLL AND DOWNTILT. AZIMUTH ACCURACY IS TO BE WITHIN 1 DEGREE. DOWNTILT AND ROLL (LEFT TO RIGHT TILT) IS TO BE WITHIN 0.1 DEGREES. IF FOR SOME REASON THIS ACCURACY CANNOT BE ACHIEVED, UPDATE AS-BUILT DRAWINGS AND EMAIL SPRINT RF ENGINEER WITH AS-BUILT SETTINGS. USE 3Z RF ALIGNMENT TOOL OR EQUIVALENT TOOL.



1 INTERNATIONAL BLVD, SUITE 800  
 MAHWAH, NJ 07495




123 Broadway, Woodcliff Lake, NJ 07677  
 608-643-4100 www.Ramaker.com

Sauk City, WI • Willmar, MN  
 Woodcliff Lake, NJ • Bayamon, PR

**Charles Cherundolo**  
 Consulting, Inc.

713 Clover Lane, Moscow, PA 18444  
 Phone: 570-840-5084 Fax: 570-842-5592

Certification & Seal:  
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



*James R. Skowronski* Signature: \_\_\_\_\_ Date: 4/25/2019

| 0    | 04/25/19 | FINAL CDs ISSUED |
|------|----------|------------------|
| MARK | DATE     | DESCRIPTION      |

ISSUE PHASE: FINAL DATE ISSUED: 04/25/2019

PROJECT TITLE:  
 (R2E) CT60-001 to CTO065  
 WILTON-RICHDALE TERRACE  
 CT60XCOO1-R


PROJECT INFORMATION:  
 24 1/2 RICHDALE DRIVE  
 WILTON, CT 06897  
 FAIRFIELD COUNTY

SHEET TITLE:  
 RF DATA SHEET


SCALE: NONE

PROJECT NUMBER: 28753  
 SHEET NUMBER: A-4







TYPICAL FIBER DISTRIBUTION BOX DETAIL  
 SCALE: NTS




RRH TO DISTRIBUTION BOX POWER CONNECTIVITY DETAIL  
 SCALE: NTS



8T8R DETAIL  
 SCALE: NTS



BTS TO DISTRIBUTION BOX FIBER CONNECTIVITY DETAIL  
 SCALE: NTS



RRH TO DISTRIBUTION BOX FIBER CONNECTIVITY DETAIL  
 SCALE: NTS



1 INTERNATIONAL BLVD, SUITE 800  
 MAHWAH, NJ 07495




100% EMPLOYEE-OWNED  
 123 Broadway, Woodcliff Lake, NJ 07677  
 608-643-4100 www.Ramaker.com  
 Sauk City, WI • Willmar, MN  
 Woodcliff Lake, NJ • Bayamon, PR

Charles Cherundolo  
 Consulting, Inc.

713 Clover Lane, Moscow, PA 18444  
 Phone: 570-840-5084 Fax: 570-842-5592

Certification & Seal:  
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



James R. Skowronski  
 Signature: Date: 4/25/2019

0 04/25/19 FINAL CDs ISSUED

ISSUE PHASE FINAL DATE ISSUED 04/25/2019

PROJECT TITLE:  
 (R2E) CT60-001 to CT0065  
 WILTON-RICHDALE TERRACE  
 CT60XCOO1-R

PROJECT INFORMATION:  
 24 1/2 RICHDALE DRIVE  
 WILTON, CT 06897  
 FAIRFIELD COUNTY


SHEET TITLE:  
 FIBER PLUMBING DIAGRAM

SCALE: NONE

PROJECT NUMBER 28753  
 SHEET NUMBER A-5





KMW 16 Port Nokia-A RRH 800, 1900, and 2500



ANTENNA COLOR CODING CHART  
SCALE: NTS

| Sector  | Cable | First Ring | Second Ring | Third Ring |
|---------|-------|------------|-------------|------------|
| 1 Alpha | 1     | Green      | No Tape     | No Tape    |
| 1       | 2     | Blue       | No Tape     | No Tape    |
| 1       | 3     | Brown      | No Tape     | No Tape    |
| 1       | 4     | White      | No Tape     | No Tape    |
| 1       | 5     | Red        | No Tape     | No Tape    |
| 1       | 6     | Grey       | No Tape     | No Tape    |
| 1       | 7     | Purple     | No Tape     | No Tape    |
| 1       | 8     | Orange     | No Tape     | No Tape    |
| 2 Beta  | 1     | Green      | Green       | No Tape    |
| 2       | 2     | Blue       | Blue        | No Tape    |
| 2       | 3     | Brown      | Brown       | No Tape    |
| 2       | 4     | White      | White       | No Tape    |
| 2       | 5     | Red        | Red         | No Tape    |
| 2       | 6     | Grey       | Grey        | No Tape    |
| 2       | 7     | Purple     | Purple      | No Tape    |
| 2       | 8     | Orange     | Orange      | No Tape    |
| 3 Gamma | 1     | Green      | Green       | Green      |
| 3       | 2     | Blue       | Blue        | Blue       |
| 3       | 3     | Brown      | Brown       | Brown      |
| 3       | 4     | White      | White       | White      |
| 3       | 5     | Red        | Red         | Red        |
| 3       | 6     | Grey       | Grey        | Grey       |
| 3       | 7     | Purple     | Purple      | Purple     |
| 3       | 8     | Orange     | Orange      | Orange     |



COLOR CODING CHARTS  
SCALE: NTS

| 2.5 FREQUENCY | INDICATOR |     | ID  |
|---------------|-----------|-----|-----|
| 2500 -1       | YEL       | WHT | GRN |
| 2500 -2       | YEL       | WHT | RED |
| 2500 -3       | YEL       | WHT | BRN |
| 2500 -4       | YEL       | WHT | BLU |
| 2500 -5       | YEL       | WHT | SLT |
| 2500 -6       | YEL       | WHT | ORG |
| 2500 -7       | YEL       | WHT | WHT |
| 2500 -8       | YEL       | WHT | PPL |

| NV FREQUENCY | INDICATOR | ID  |
|--------------|-----------|-----|
| 800-1        | YEL       | GRN |
| 1900-1       | YEL       | RED |
| 1900-2       | YEL       | BRN |
| 1900-3       | YEL       | BLU |
| 1900-4       | YEL       | SLT |
| 800-1        | YEL       | ORG |
| RESERVED     | YEL       | WHT |
| RESERVED     | YEL       | PPL |

CABLE MARKING NOTES

- ALL CABLES SHALL BE MARKED WITH 2" WIDE, UV STABILIZED, UL APPROVED TAPE.
- THE FIRST RING SHALL BE CLOSEST TO THE END OF THE CABLE AND SPACED APPROXIMATELY 2" FROM THE END CONNECTOR, WEATHERPROOFING, OR BREAKOUT UNIT. THERE SHALL BE 1" SPACE BETWEEN EACH RING.
- A 2" GAP SHALL SEPARATE THE CABLE COLOR CODE FROM THE FREQUENCY COLOR CODE. THE 2" COLOR RINGS FOR THE FREQUENCY CODE SHALL BE PLACED NEXT TO EACH OTHER WITH NO SPACES.
- THE 2" COLORED TAPE(S) SHALL BE WRAPPED A MINIMUM OF 3 TIMES AROUND THE INDIVIDUAL CABLES, AND THE TAPE SHALL BE KEPT IN THE SAME LOCATION AS MUCH AS POSSIBLE.
- SITES WITH MORE THAN FOUR (4) SECTORS WILL REQUIRE ADDITIONAL RINGS FOR EACH SECTOR, FOLLOWING THE PATTERN. HIGH CAPACITY SITES WILL USE THE SECOND CABLE IDENTIFIED BY BLUE BANDS OF TAPE.
- HYBRID FIBER CABLE SHALL BE SECTOR IDENTIFIED INSIDE THE CABINET ON FREQUENCY BUNDLES, ON THE SEALTITE, ON THE MAIN LINE UPON EXIT OF SEALTITE, AND BEFORE AND AFTER THE BREAKOUT UNIT (MEDUSA), AS WELL AS BEFORE AND AFTER ANY ENTRANCE OR EXIT.
- HFC "MAIN TRUNK" WILL NOT BE MARKED WITH THE FREQUENCY CODES, AS IT CONTAINS ALL FREQUENCIES.
- INDIVIDUAL POWER PAIRS AND FIBER BUNDLES SHALL BE LABELED WITH BOTH THE CABLE AND FREQUENCY.




1 INTERNATIONAL BLVD, SUITE 800  
MAHWAH, NJ 07495

**RAMAKER & ASSOCIATES, INC.**  
100% EMPLOYEE-OWNED  
123 Broadway, Woodcliff Lake, NJ 07677  
608-643-4100 www.Ramaker.com  
Sauk City, WI • Willmar, MN  
Woodcliff Lake, NJ • Bayamon, PR

**Charles Cherundolo Consulting, Inc.**

713 Clover Lane, Moscow, PA 18444  
Phone: 570-840-5084 Fax: 570-842-5592

Certification & Seal:  
I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 4/25/2019

| MARK        | DATE     | DESCRIPTION            |
|-------------|----------|------------------------|
| 0           | 04/25/19 | FINAL CDs ISSUED       |
| ISSUE PHASE | FINAL    | DATE ISSUED 04/25/2019 |

PROJECT TITLE:  
**(R2E) CT60-001 to CTO065 WILTON-RICHDALE TERRACE CT60XCOO1-R**


PROJECT INFORMATION:  
24 1/2 RICHDALE DRIVE  
WILTON, CT 06897  
FAIRFIELD COUNTY

SHEET TITLE:  
**CABLE COLOR CODING**

SCALE: NONE

PROJECT NUMBER: 28753  
SHEET NUMBER: A-6





| MECHANICAL        |                  |
|-------------------|------------------|
| DIMENSION (HxWxD) | 4.9"x16.6"x14.6" |
| WEIGHT            | 44 lbs           |

RRH MODEL: NOKIA #FZHN - RADIO SPECS



| MECHANICAL        |                      |
|-------------------|----------------------|
| DIMENSION (HxWxD) | 84.9" x 21.0" x 6.3" |
| WEIGHT            | 84.9 lbs             |

ANTENNA MODEL: KMW #ETCR-654L12H6 - ANTENNA SPECS

### 1900MHz Remote Radio Head (RRH)

#### Capacity & Features

CDMA / LTE Multi technology RRH 65MHz bandwidth (PCS A-G Band)

- Sprint is free to deploy any combination of CDMA (1XRTT or EVDO) and LTE carriers in Sprint's spectrum up to 160 Watts of RF power
- E.g. "A block" and "G block" both with 4 branch MIMO (4Tx & 4Rx)

2 CPRI Optical Connections for multi-carrier LTE and CDMA (1X & DO)

Power Supply: -48 VDC


Power Consumption: 700W Typical

Dimensions:

- Size: 282 x 271.5 x 637mm (11.1" x 10.69" x 25.1")
- Volume: 49 Liter  
56 liters with solar shield & mounting OD

Weight: 27 kg (59.5 lbs)

Operating Temp range -40°C/+55°C



Alcatel-Lucent's 65MHz RRH satisfies Sprint's requirements.

| MECHANICAL        |                   |
|-------------------|-------------------|
| DIMENSION (HxWxD) | 25.2"x11.8"x11.5" |
| WEIGHT            | 59.5 lbs          |

RRH MODEL: ALU #1900 MHZ 4X45W - RADIO SPECS

### 800MHz 2X50W Remote Radio Head (RRH)

Simultaneous CDMA & LTE Multi technology RRH 862-869 MHz

- Any combination of CDMA and LTE carriers supported by 100W RF Power

2 CPRI-like Optical Connections for daisy chaining  
Software Switchable External Filter for use before  
Public Safety is cleared

Dimensions: w/o Filter w/ Filter

- Height: 480 mm (19") 480 mm (19")
- Width: 330 mm (13") 330 mm (13")
- Depth: 218 mm (8.6") 310 (12.2")
- Weight: 24 kg (53 lbs) 29 kg (64 lbs)
- 49 liters, <29kg


Power Supply: -48 VDC

Power Consumption: <400W Typical


Operating Temp range -40°C to +55°C

Option to mount on Ground at tower base

Front/Top View



Bottom View



Alcatel-Lucent's 800 RRH satisfies Sprint's requirements.

| MECHANICAL        |                   |
|-------------------|-------------------|
| DIMENSION (HxWxD) | 19" x 13" x 12.2" |
| WEIGHT            | 64 lbs            |

RRH MODEL: ALU #800 MHz 2x50W - RADIO SPECS



1 INTERNATIONAL BLVD, SUITE 800  
MAHWAH, NJ 07495




100% EMPLOYEE-OWNED  
123 Broadway, Woodcliff Lake, NJ 07677  
608-643-4100 www.Ramaker.com

Sauk City, WI • Willmar, MN  
Woodcliff Lake, NJ • Bayamon, PR

## Charles Cherundolo Consulting, Inc.

713 Clover Lane, Moscow, PA 18444  
Phone: 570-840-5084 Fax: 570-842-5592

Certification & Seal:  
I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 4/25/2019

| MARK | DATE     | DESCRIPTION      |
|------|----------|------------------|
| 0    | 04/25/19 | FINAL CDs ISSUED |

| ISSUE PHASE    | FINAL | DATE ISSUED | 04/25/2019 |
|----------------|-------|-------------|------------|
| PROJECT TITLE: |       |             |            |

(R2E) CT60-001 to CTO065  
WILTON-RICHDALE TERRACE  
CT60XCOO1-R


PROJECT INFORMATION:  
24 1/2 RICHDALE DRIVE  
WILTON, CT 06897  
FAIRFIELD COUNTY

SHEET TITLE:  
ANTENNA & HYBRID CABLE  
DETAILS


SCALE: NONE

PROJECT NUMBER: 28753

SHEET NUMBER: A-7




HYBRID BREAKOUT DETAIL ①  
 SCALE: NTS



CABLE ROUTE FROM CABINET ②  
 SCALE: NTS



EXISTING BBU CABINET ③  
 SCALE: NTS



EXISTING MMBS CABINET ④  
 SCALE: NTS



1 INTERNATIONAL BLVD, SUITE 800  
 MAHWAH, NJ 07495




100% EMPLOYEE-OWNED  
 123 Broadway, Woodcliff Lake, NJ 07677  
 608-643-4100 www.Ramaker.com  
 Sauk City, WI • Willmar, MN  
 Woodcliff Lake, NJ • Bayamon, PR

**Charles Cherundolo Consulting, Inc.**

713 Clover Lane, Moscow, PA 18444  
 Phone: 570-840-5084 Fax: 570-842-5592

Certification & Seal:  
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 4/25/2019

| MARK        | DATE     | DESCRIPTION            |
|-------------|----------|------------------------|
| 0           | 04/25/19 | FINAL CDs ISSUED       |
| ISSUE PHASE | FINAL    | DATE ISSUED 04/25/2019 |

PROJECT TITLE:  
 (R2E) CT60-001 to CTO065  
 WILTON-RICHDALE TERRACE  
 CT60XCOO1-R


PROJECT INFORMATION:  
 24 1/2 RICHDALE DRIVE  
 WILTON, CT 06897  
 FAIRFIELD COUNTY

SHEET TITLE:  
 EQUIPMENT DETAILS

SCALE: NONE

|                |       |
|----------------|-------|
| PROJECT NUMBER | 28753 |
| SHEET NUMBER   | A-8   |





PROPOSED ANTENNA MOUNTING PLATFORM:  
 SITE PRO 1 #RMQP-396 W/ #HRK12 HANDRAIL ①  
 SCALE: NTS



1 INTERNATIONAL BLVD, SUITE 800  
 MAHWAH, NJ 07495




100% EMPLOYEE-OWNED  
 123 Broadway, Woodcliff Lake, NJ 07677  
 608-643-4100 www.Ramaker.com  
 Sauk City, WI • Willmar, MN  
 Woodcliff Lake, NJ • Bayamon, PR

**Charles Cherundolo  
 Consulting, Inc.**

713 Clover Lane, Moscow, PA 18444  
 Phone: 570-840-5084 Fax: 570-842-5592

Certification & Seal:  
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



*James R. Skowronski* 4/25/2019  
 Signature: Date:

|  |  |  |
|--|--|--|
|  |  |  |
|  |  |  |
|  |  |  |

|   |          |                  |
|---|----------|------------------|
| 0 | 04/25/19 | FINAL CDs ISSUED |
|---|----------|------------------|

|       |       |        |            |
|-------|-------|--------|------------|
| ISSUE | FINAL | DATE   | 04/25/2019 |
| PHASE |       | ISSUED |            |


PROJECT TITLE:  
 (R2E) CT60-001 to CT0065  
 WILTON-RICHDALE TERRACE  
 CT60XCOO1-R

PROJECT INFORMATION:  
 24 1/2 RICHDALE DRIVE  
 WILTON, CT 06897  
 FAIRFIELD COUNTY


SHEET TITLE:  
 STRUCTURAL DETAILS

SCALE: NONE

|                |       |
|----------------|-------|
| PROJECT NUMBER | 28753 |
| SHEET NUMBER   | S-1   |



**EQUIPMENT UTILITY & GROUNDING PLAN**  
 SCALE: NTS



**ANTENNA GROUNDING DETAIL**  
 SCALE: NTS

**GROUNDING NOTES:**

- CONTRACTOR TO ENSURE PROPER SEQUENCING OF GROUNDING AND UNDERGROUND CONDUIT INSTALLATION TO PREVENT ANY LOSS OF CONTINUITY IN THE GROUNDING SYSTEM AND/OR DAMAGE TO THE CONDUIT.
- ALL EXTERIOR GROUND CONDUCTORS SHALL BE #2 AWG SOLID TINNED COPPER UNLESS NOTED OTHERWISE.
- ALL GROUND CONNECTIONS BELOW GRADE SHALL BE EXOTHERMIC (CADWELD).
- ALL GROUND CONNECTIONS ABOVE GRADE AND/OR INTERIOR SHALL BE COMPRESSION TYPE, TWO-HOLE LUGS OR DOUBLE-CRIMP "C" TAPS.
- CONTACT AREAS WHERE CONNECTIONS ARE MADE SHALL BE PREPARED TO A BARE BRIGHT FINISH AND COATED WITH AN ANTI-OXIDATION MATERIAL BEFORE CONNECTIONS ARE MADE.
- MAXIMUM RESISTANCE OF THE COMPLETED GROUND SYSTEM SHALL NOT EXCEED 5 OHMS.
- WHERE GROUNDING CONNECTIONS ARE MADE TO PAINTED METAL SURFACES, PAINT SHALL BE REMOVED TO BARE METAL TO ENSURE PROPER CONTACT AND RESTORED/PAINTED TO ORIGINAL FINISH.
- GROUND DEPTH SHALL BE 30" MINIMUM BELOW FINISHED GRADE, OR 6" BELOW FROST LINE, WHICHEVER IS GREATER.

| LEGEND:     |                       |
|-------------|-----------------------|
| ---         | EXISTING GROUND CABLE |
| - - - - -   | PROPOSED GROUND CABLE |
| ▲           | MECHANICAL CONNECTION |
| ■           | EXOTHERMIC CONNECTION |
| —E—E—E—E—E— | PROPOSED ELECTRIC     |



1 INTERNATIONAL BLVD, SUITE 800  
 MAHWAH, NJ 07495




123 Broadway, Woodcliff Lake, NJ 07677  
 608-643-4100 www.Ramaker.com

Sauk City, WI • Willmar, MN  
 Woodcliff Lake, NJ • Bayamon, PR

**Charles Cherundolo Consulting, Inc.**

713 Clover Lane, Moscow, PA 18444  
 Phone: 570-840-5084 Fax: 570-842-5592

Certification & Seal:  
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



*James R. Skowronski* 4/25/2019  
 Signature: Date:

| MARK        | DATE     | DESCRIPTION            |
|-------------|----------|------------------------|
| 0           | 04/25/19 | FINAL CDs ISSUED       |
| ISSUE PHASE | FINAL    | DATE ISSUED 04/25/2019 |





PROJECT TITLE:  
**(R2E) CT60-001 to CTO065  
 WILTON-RICHDALE TERRACE  
 CT60XCOO1-R**

PROJECT INFORMATION:  
 24 1/2 RICHDALE DRIVE  
 WILTON, CT 06897  
 FAIRFIELD COUNTY

SHEET TITLE:  
**EQUIPMENT UTILITY &  
 GROUNDING PLAN**

SCALE: NONE

|                |       |
|----------------|-------|
| PROJECT NUMBER | 28753 |
| SHEET NUMBER   | E-1   |



**Sprint**

1 INTERNATIONAL BLVD, SUITE 800  
 MAHWAH, NJ 07495

**RAMAKER & ASSOCIATES, INC.**  
 100% EMPLOYEE-OWNED

123 Broadway, Woodcliff Lake, NJ 07677  
 608-643-4100 www.Ramaker.com

Sauk City, WI • Willmar, MN  
 Woodcliff Lake, NJ • Bayamon, PR

**Charles Cherundolo Consulting, Inc.**

713 Clover Lane, Moscow, PA 18444  
 Phone: 570-840-5084 Fax: 570-842-5592

Certification & Seal:  
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.

STATE OF CONNECTICUT  
 JAMES R. SKOWRONSKI  
 26266  
 LICENSED PROFESSIONAL ENGINEER

Signature: *James R. Skowronski* Date: 4/25/2019

| 0  | 04/25/19 | FINAL CDs ISSUED       |
|--|----------|------------------------|
| MARK   | DATE     | DESCRIPTION            |
| ISSUE  | FINAL    | DATE ISSUED 04/25/2019 |
| PROJECT TITLE:   |          |                        |
| (R2E) CT60-001 to CT0065<br>WILTON-RICHDALE TERRACE<br>CT60XCOO1-R |          |                        |


PROJECT INFORMATION:  
 24 1/2 RICHDALE DRIVE  
 WILTON, CT 06897  
 FAIRFIELD COUNTY

SHEET TITLE:  
**GROUNDING PLAN & DETAILS**


SCALE: NONE

|                |       |
|----------------|-------|
| PROJECT NUMBER | 28753 |
| SHEET NUMBER   | E-2   |





TEST WELL GROUNDING DETAIL (1)  
 SCALE: NTS




GROUND BAR DETAIL (2)  
 SCALE: NTS

EST. WEIGHT 7.5 LBS  
 PART NO. TGB114420SNP  
 TINNED 1/4 X 4 X 20 IN CU M PATTERN  
 SPRINT - NEXTEL CORPORATION


|                   |                  |
|-------------------|------------------|
| DRAWN BY:<br>DVEN | REVISION:<br>-   |
| CHECKED BY:<br>-  | SCALE:<br>3/8    |
| DATE:<br>011107   | SHEET:<br>1 OF 1 |

HARGER  
 301 ZIEGLER DRIVE  
 GRAYSLAKE, IL 60330  
 (847) 548-8700




- NOTE:
1. DOUBLING UP OR "STACKING" OF CONNECTIONS IS NOT PERMITTED.
  2. OXIDE INHIBITING COMPOUND TO BE USED AT ALL LOCATIONS.
  3. COAT WIRE END WITH ANTI-OXIDATION COMPOUND PRIOR TO INSERTION INTO LUG BARREL AND CRIMPING.
  4. APPLY ANTI-OXIDATION COMPOUND BETWEEN ALL LUGS AND BUSS BARS PRIOR TO MATING AND BOLTING.

GROUND BAR CONNECTION DETAIL (3)  
 SCALE: NTS



GROUND KIT DETAIL (4)  
 SCALE: NTS



GROUND ROD DETAIL (5)  
 SCALE: NTS



1 INTERNATIONAL BLVD, SUITE 800  
 MAHWAH, NJ 07495



100% EMPLOYEE-OWNED  
 123 Broadway, Woodcliff Lake, NJ 07677  
 608-643-4100 www.Ramaker.com

Sauk City, WI • Willmar, MN  
 Woodcliff Lake, NJ • Bayamon, PR

**Charles Cherundolo Consulting, Inc.**

713 Clover Lane, Moscow, PA 18444  
 Phone: 570-840-5084 Fax: 570-842-5592

Certification & Seal:  
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 4/25/2019

| 0     | 04/25/19 | FINAL CDs ISSUED       |
|-------|----------|------------------------|
| MARK  | DATE     | DESCRIPTION            |
| ISSUE | FINAL    | DATE ISSUED 04/25/2019 |

PROJECT TITLE:  
 (R2E) CT60-001 to CT0065  
 WILTON-RICHDALE TERRACE  
 CT60XC001-R


PROJECT INFORMATION:  
 24 1/2 RICHDALE DRIVE  
 WILTON, CT 06897  
 FAIRFIELD COUNTY

SHEET TITLE:  
 GROUNDING DETAILS


SCALE: NONE

PROJECT NUMBER: 28753  
 SHEET NUMBER: E-3






**GROUNDING RISER DIAGRAM**  
 SCALE: NTS



- NOTES:**
1. APPLY NO-OX TO LUG AND GROUND BAR CONTACT SURFACE. DO NOT COAT INLINE LUG.
  2. IF STOLEN GROUND BARS ARE ENCOUNTERED, CONTACT SPRINT CM FOR REPLACEMENT THREADED ROD KIT.

**GROUNDING CONDUCTOR INSTALLATION**  
 SCALE: NTS



**TWO-HOLE LUG**  
 SCALE: NTS



1 INTERNATIONAL BLVD, SUITE 800  
 MAHWAH, NJ 07495



100% EMPLOYEE-OWNED  
 123 Broadway, Woodcliff Lake, NJ 07677  
 608-643-4100 www.Ramaker.com

Sauk City, WI • Willmar, MN  
 Woodcliff Lake, NJ • Bayamon, PR

**Charles Cherundolo Consulting, Inc.**

713 Clover Lane, Moscow, PA 18444  
 Phone: 570-840-5084 Fax: 570-842-5592

**Certification & Seal:**  
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 4/25/2019

| MARK | DATE     | DESCRIPTION      |
|------|----------|------------------|
| 0    | 04/25/19 | FINAL CDs ISSUED |

ISSUE PHASE: FINAL DATE ISSUED: 04/25/2019


PROJECT TITLE:  
 (R2E) CT60-001 to CTO065  
 WILTON-RICHDALE TERRACE  
 CT60XCOO1-R

PROJECT INFORMATION:  
 24 1/2 RICHDALE DRIVE  
 WILTON, CT 06897  
 FAIRFIELD COUNTY

SHEET TITLE:  
 GROUNDING DETAILS

SCALE: NONE



PROJECT NUMBER: 28753  
 SHEET NUMBER: E-4



| A/C PANEL SCHEDULE |          |               |          |                   |     |
|--------------------|----------|---------------|----------|-------------------|-----|
| VOLTAGE:           | 240V/120 | PANEL STATUS: | EXISTING | N TO GROUND BOND: | YES |
| MAIN BREAKER:      | 200 AMP  | MODEL NUMBER: | TBD      | INTERNAL TVSS:    | YES |
| MOUNT:             | SHELTER  | PHASE:        | 1        | WIRE:             | 3   |
| ENCLOSURE TYPE:    | NEMA 3R  | BUSS RATING:  | 200 AMP  | GROUND BAR:       | YES |
|                    |          | NEUTRAL BAR:  | YES      |                   |     |

| CKT | DESCRIPTION    | BREAKER AMPS | BREAKER POLES | BREAKER STATUS | PHASE A VA | PHASE B VA | BREAKER STATUS | BREAKER POLES | BREAKER AMPS | DESCRIPTION    | CKT |
|-----|----------------|--------------|---------------|----------------|------------|------------|----------------|---------------|--------------|----------------|-----|
| 1   | NOT LABELED    | 20           | 1             | ON             |            |            | ON             | 1             | 20           | NOT LABELED    | 2   |
| 3   | NOT LABELED    | 20           | 1             | ON             |            |            | ON             | 1             | 20           | NOT LABELED    | 4   |
| 5   | NOT LABELED    | 20           | 1             | ON             |            |            | ON             | 1             | 20           | NOT LABELED    | 6   |
| 7   | NOT LABELED    | -            | 2             | ON             |            |            | ON             | 2             | -            | NOT LABELED    | 8   |
| 9   | NOT LABELED    | -            | 2             | ON             |            |            | ON             | 2             | -            | NOT LABELED    | 10  |
| 11  | NOT LABELED    | -            | 2             | ON             |            |            | OFF            | 2             | 20           | NOT LABELED    | 12  |
| 13  | NOT LABELED    | -            | 2             | ON             |            |            | OFF            | 2             | 20           | NOT LABELED    | 14  |
| 15  | NOT LABELED    | 15           | 1             | ON             |            |            | OFF            | 1             | 20           | NOT LABELED    | 16  |
| 17  | NOT LABELED    | 30           | 2             | ON             |            |            | ON             | 2             | 30           | NOT LABELED    | 18  |
| 19  | NOT LABELED    | 30           | 2             | ON             |            |            | ON             | 2             | 30           | NOT LABELED    | 20  |
| 21  | NOT LABELED    | 30           | 2             | ON             |            |            | ON             | 2             | 30           | NOT LABELED    | 22  |
| 23  | NOT LABELED    | 30           | 2             | ON             |            |            | ON             | 2             | 30           | NOT LABELED    | 24  |
| 25  | NOT LABELED    | 30           | 2             | ON             |            |            | ON             | 2             | 30           | NOT LABELED    | 26  |
| 27  | NOT LABELED    | 30           | 2             | ON             |            |            | ON             | 2             | 30           | NOT LABELED    | 28  |
| 29  | NOT LABELED    | 30           | 2             | ON             |            |            | ON             | 2             | 30           | NOT LABELED    | 30  |
| 31  | NOT LABELED    | 30           | 2             | ON             |            |            | ON             | 2             | 30           | NOT LABELED    | 32  |
| 33  | NOT LABELED    | 40           | 2             | ON             |            |            | OFF            | 1             | 20           | NOT LABELED    | 34  |
| 35  | NOT LABELED    | 40           | 2             | ON             |            |            | ON             | 2             | 100          | SPRINT MMBTS   | 36  |
| 37  | NOT LABELED    | 10           | 1             | ON             |            |            | ON             | 2             | 100          | SPRINT MMBTS   | 38  |
| 39  | BLANK (UNUSED) | -            | -             | -              |            |            | -              | -             | -            | BLANK (UNUSED) | 40  |

AC PANEL SCHEDULE  
 SCALE: NTS



| CIRCUIT SCHEDULE |                        |                        |  |
|------------------|------------------------|------------------------|--|
| NO.              | FROM                   | TO                     | CONFIGURATION                            |
| 1                | UTILITY SOURCE         | METER/DISCONNECT       | EXISTING                                 |
| 2                | METER/DISCONNECT       | TRANSFER # LOAD CENTER | EXISTING                                 |
| 3                | TRANSFER # LOAD CENTER | GENERATOR RECEPTACLE   | EXISTING                                 |
| 4                | TRANSFER # LOAD CENTER | EX. MMBTS CABINET      | (3) #2 AWG, (1) #8 GND IN 1 1/2" CONDUIT |
| 5                | TRANSFER # LOAD CENTER | EX. BBU CABINET        | (2) #12 AWG, (1) #12 GND IN 3/4" CONDUIT |

1 INTERNATIONAL BLVD, SUITE 800  
 MAHWAH, NJ 07495

100% EMPLOYEE-OWNED  
 123 Broadway, Woodcliff Lake, NJ 07677  
 608-643-4100 www.Ramaker.com  
 Sauk City, WI • Willmar, MN  
 Woodcliff Lake, NJ • Bayamon, PR

Charles Cherundolo  
 Consulting, Inc.  
 713 Clover Lane, Moscow, PA 18444  
 Phone: 570-840-5084 Fax: 570-842-5592

Certification & Seal:  
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.

James R. Skowronski  
 Signature: \_\_\_\_\_ Date: 4/25/2019

|   |          |                        |
|---|----------|------------------------|
| 0   | 04/25/19 | FINAL CDs ISSUED       |
| MARK  | DATE     | DESCRIPTION            |
| ISSUE   | FINAL    | DATE ISSUED 04/25/2019 |
| PROJECT TITLE:<br>(R2E) CT60-001 to CTO065<br>WILTON-RICHDALE TERRACE<br>CT60XCOO1-R  |          |                        |
| PROJECT INFORMATION:<br>24 1/2 RICHDALE DRIVE<br>WILTON, CT 06897<br>FAIRFIELD COUNTY |          |                        |
| SHEET TITLE:<br>DC POWER DETAILS<br>& PANEL SCHEDULES                                 |          |                        |
| SCALE: NONE   |          |                        |
| PROJECT NUMBER  | 28753    |                        |
| SHEET NUMBER  | E-5      |                        |



*Shipping Address*

#1 Fairholm Avenue, Peoria, Illinois 61603 USA

Phone: 309-566-3000

*Mailing Address*

P.O. Box 5999, Peoria, Illinois 61601-5999 USA

[www.rohntower.com](http://www.rohntower.com)

---

## QUOTATION

Please Reference This Quotation Number: Q19-11267 - 1

August 21, 2019

Sprint

Thank you for the opportunity to meet the supply requirements of your current need. ROHN is pleased to supply the attached quotation. We have carefully reviewed your requirements and believe our proposal meets those requirements, unless otherwise noted. Please note the validity period and related terms and conditions as attached.

Your quotation was prepared by:

Janelle Houge  
[j.houge@rohntower.com](mailto:j.houge@rohntower.com)  
309-566-3017

Your ROHN primary contact is:

Danny Otten  
[d.otten@rohntower.com](mailto:d.otten@rohntower.com)  
(309) 566-3018

Please carefully review the quotation supplied. Feel free to contact any of the persons listed above with additional questions or clarifications. ROHN believes you, as our valued client should have a single point of contact for your business with ROHN. That is normally your sales contact person. They can assist you answering a wide variety of questions and bring in additional resources as required.

Lastly, the entire ROHN team is here to serve your needs and requirements. Please call on any of us to assist you as needed. ROHN values both our relationship and your business.

Sincerely,

The ROHN Quotation Team



**Shipping Address**

#1 Fairholm Avenue, Peoria, Illinois 61603 USA

Phone: 309-566-3000

**Mailing Address**

P.O. Box 5999, Peoria, Illinois 61601-5999 USA

www.rohntower.com

**QUOTATION**

Quote To: Sprint  
Kimberly Hassebroek  
kimberly.hassebroek@sprint.com  
Phone Number: 321-280-2074

Proposal Number: Q19-11267 - 1  
Quote Date: 8/21/2019  
Quote Valid for: 30 days

ROHN Contact: Danny Otten

Phone: (309) 566-3018

Email: d.otten@rohntower.com

| Item #           | Qty | Description   | Unit Price         |
|------------------|-----|---|--------------------|
| C-21977          | 1   | ROHN Structure: 70ft Tapered Steel Pole Designed to Support the Antennas & Transmission Lines as shown on enclosed drawing "Q19-11267-1 PROFILE" for site "WILTON-RICHDALE TERRACE" located in Fairfield County, CT |                    |
|                  |     | <b>** EXCEPTION TO TOPO 3: ROHN DESIGNED AS TOPO CATEGORY 1 **</b>  |                    |
| STRUCTURE        |     | Rohn Structure Parts Total  | \$10,995.00        |
| C-21977-A        |     | Anchor Bolts & Templates  | \$1,850.00         |
| DESIGN           |     | Design Drawings & Calculations w/State of CT PE Seal & Conventional Foundation design based on submitted soil report  | \$1,500.00         |
| <b>SUB TOTAL</b> |     |   | <b>\$14,345.00</b> |
| <b>TOTAL</b>     |     |   | <b>\$14,345.00</b> |

**This Structure is designed for:**

Design Code: ANSI/TIA-222-REV G 2005  
Wind Speed: ASCE 7-16 Factored Wind Speed (No Ice) = 117 MPH  
Wind Speed With Ice: 50 MPH with 1.0 inches Ice  
Structure Class: II  
Exposure Category: B  
Topographic Category: 1

**Price above includes:**

- Pole Sections
- Step Bolts for Climbing
- Tuf Tug Safety Cable Type System w/o Trolley or Harness
- 3) Base Grounding Lugs - see Optional Items for pricing on TIA Grounding Materials
- (3) 8" x 20" Reinforced Hand Holes at 65ft
- (2) 11.5" x 31.5" Reinforced Exit Ports (Customer to Identify Elevations & Azimuths)

See Optional Items for Pricing on Mount, Grounding etc.

Any Applicable State Sales Tax is NOT INCLUDED in the Prices Quoted. Please provide Sales Tax Exemption Information if Applicable.

NOTES:

- Structure Height is Nominal, unless otherwise stated.
- Structure is designed to support the Antennas and Transmission Lines as per the attached preliminary profile drawing.
- Sealed Design Drawings and Calculations will be supplied in electronic format only unless otherwise requested.
- If Each Page of a Design set must be sealed, Please ADD \$250.00 for EACH set prepared in this manner.
- All welding conforms to AWS.  
Additional corrosion protection may be required for steel guy anchors and direct embedded poles that come in direct contact with soil. This additional corrosion protection is to be provided by others, unless otherwise indicated.
- Estimated foundation based on soil report (PROJECT # 28753): see attached drawing.
- Step Bolts are provided for Climbing.
- ROHN'S proposal does not include GROUNDING, unless, the Optional REV G Standard Base Grounding Kits are purchased.
- EXCEPTION: AFTER REVIEWING THE LATITUDE AND LONGITUDE - ROHN DETERMINED THE SITE IS A TOPOGRAPHIC CATEGORY 1 (NOT 3) AND HAVE DESIGNED AS SUCH. IF SPRINT FEELS THAT TOPO 3 IS REQUIRED, THEN ROHN RESERVES THE RIGHT TO REQUOTE THE POLE.

Please note that lead times are estimated and can fluctuate due to production capacity and material availability. The estimated lead times are reassessed upon receiving the Purchase Order. Please contact ROHN to verify current lead times or if a better delivery date is possible when placing an order.

Estimated Current Engineering Design Package Lead Time (ARO): 5-7 Business Days  
 Estimated Current Structure Lead Time (ARO): To Be Determined

**Optional Items: Not Included in Total Price. Price is Per Each Item**

| <b>Qty</b> | <b>Description</b>   | <b>Unit Price</b> | <b>Extended Price</b> |
|------------|--|-------------------|-----------------------|
| 1          | Trolley Only   | \$190.00          | \$190.00              |
| 1          | Journeyman Harness (Tuf Tug)   | \$150.00          | \$150.00              |
| 1          | (1) 5ft Lightning Rod (no download)  | \$75.00           | \$75.00               |
| 1          | TIA REV G Standard Grounding   | \$445.00          | \$445.00              |
| 1          | 14ft LP Platform w/(12) Mtg Pipes & Toprails   | \$6,525.00        | \$6,525.00            |
| 1          | Estimated Freight for Anchor Bolt Shipment to Wilton, CT 06897   | \$495.00          | \$495.00              |
| 1          | Estimated Freight Charges (1 FLAT BED TRAILER) for shipment of the Above Quoted Tower Material to an accessible delivery site in Wilton, CT 06897 with unloading by the customer | \$3,960.00        | \$3,960.00            |



FILE NO.

Q19-11267-1


| REVISIONS |             |     |         |
|-----------|-------------|-----|---------|
| REV#      | DESCRIPTION | DWN | CHK APP |
|           |             |     |         |

**POLE DESIGN LOADING**

| DESIGN WIND LOAD PER ANSI/TIA-222-G USING THE FOLLOWING DESIGN CRITERIA:<br>ASCE 7-16 FACTORED WIND SPEED (NO ICE): 117 MPH<br>BASIC WIND SPEED (WITH ICE): 50 MPH<br>DESIGN ICE THICKNESS: 1.0"<br>EXPOSURE CATEGORY: C<br>STRUCTURE CLASSIFICATION: II<br>TOPOGRAPHIC CATEGORY: 1<br>EARTHQUAKE SPECTRAL RESPONSE ACCELERATION, S <sub>s</sub> : 0.241<br>THIS POLE IS DESIGNED TO SUPPORT THE FOLLOWING LOADS: |   |                 |
|---|---|-----------------|
| ELEVATION (FT)  | ANTENNA TYPE                                      | LINE SIZE (NOM) |
| TOP   | LIGHTNING ROD                                     | -               |
| 67  | (3) PANEL ANTENNAS & (12) RRUS ON A 14FT LP MOUNT | (4) 1-5/8"      |

**GENERAL NOTES:**

- ROHN PRODUCTS POLE DESIGNS CONFORM TO ANSI/TIA-222-G UNLESS OTHERWISE SPECIFIED UNDER POLE DESIGN LOADING.
- THE DESIGN LOADING CRITERIA INDICATED HAS BEEN PROVIDED TO ROHN. THE DESIGN LOADING CRITERIA HAS BEEN ASSUMED TO BE BASED ON SITE-SPECIFIC DATA IN ACCORDANCE WITH ANSI/TIA-222-G AND MUST BE VERIFIED BY OTHERS PRIOR TO INSTALLATION.
- ANTENNAS AND LINES LISTED IN POLE DESIGN LOADING TABLE ARE PROVIDED BY OTHERS UNLESS OTHERWISE SPECIFIED.
- STEP BOLTS ARE PROVIDED AS A CLIMBING FACILITY FOR THE INSTALLATION OF THE STRUCTURE.
- POLE MEMBER DESIGN DOES NOT INCLUDE STRESSES DUE TO ERECTION SINCE ERECTION EQUIPMENT AND CONDITIONS ARE UNKNOWN. DESIGN ASSUMES COMPETENT AND QUALIFIED PERSONNEL WILL ERECT THE POLE. WORK SHALL BE IN ACCORDANCE WITH ANSI/TIA-222-G, "STRUCTURAL STANDARDS FOR STEEL ANTENNA TOWERS AND ANTENNA SUPPORTING STRUCTURES".
- FIELD CONNECTIONS SHALL BE BOLTED. NO FIELD WELDS SHALL BE ALLOWED.
- STRUCTURAL BOLTS SHALL CONFORM TO GRADE A325 PER ASTM F3125, EXCEPT WHERE NOTED.
- A NUT LOCKING DEVICE SHALL BE PROVIDED FOR ALL STRUCTURAL BOLTS ON THE POLE.
- STRUCTURAL STEEL AND CONNECTION BOLTS SHALL BE HOT-DIPPED GALVANIZED AFTER FABRICATION IN ACCORDANCE WITH ANSI/TIA-222-G.
- ALL HIGH STRENGTH BOLTS ARE TO BE TIGHTENED TO A "SNUG TIGHT" CONDITION AS DEFINED IN THE RSCC "SPECIFICATION FOR STRUCTURAL JOINTS USING HIGH-STRENGTH BOLTS". NO OTHER MINIMUM BOLT TENSION OR TORQUE VALUES ARE REQUIRED.
- PURCHASER SHALL VERIFY THE INSTALLATION IS IN CONFORMANCE WITH LOCAL, STATE, AND FEDERAL REQUIREMENTS FOR OBSTRUCTION MARKING AND LIGHTING.
- TOLERANCE ON POLE STEEL HEIGHT IS EQUAL TO PLUS 1% OR MINUS 1/2%.
- DESIGN ASSUMES THAT, AS A MINIMUM, MAINTENANCE AND INSPECTION WILL BE PERFORMED OVER THE LIFE OF THE STRUCTURE IN ACCORDANCE WITH ANSI/TIA-222-G.
- DESIGN ASSUMES LEVEL GRADE AT POLE SITE.
- FOUNDATIONS SHALL BE DESIGNED TO SUPPORT THE REACTIONS SHOWN FOR THE CONDITIONS EXISTING AT THE SITE.
- DESIGN ASSUMES ALL TRANSMISSION LINES ARE ROUTED INTERNALLY.
- POLE SHAFT CONFORMS TO ASTM A572 GR 50. POLE BASE PLATE AND TOP PLATE STEEL CONFORMS TO ASTM A572 GR 50. POLE ANCHOR BOLTS CONFORM TO ASTM F1554.



**MAXIMUM FACTORED REACTIONS**

|            |               |
|------------|---------------|
| DOWNLOAD = | 16.2 KIPS     |
| SHEAR =    | 5.4 KIPS      |
| O.T.M. =   | 285.8 FT-KIPS |

**SECTION SCHEDULE**

| SECTION | LENGTH (FT) | DIAMETER |       | WALL THICK (IN) | Fy (KSI) | WEIGHT (KIPS) |
|---------|-------------|----------|-------|-----------------|----------|---------------|
|         |             | BOT      | TOP   |                 |          |               |
| 1       | 24.42       | 19.67    | 16.00 | 0.1875          | 65.0     | 0.924         |
| 2       | 48.00       | 26.00    | 18.79 | 0.1875          | 65.0     | 2.300         |

FOR POLYGONAL POLES, DIAMETER IS MEASURED ACROSS FLATS.

**NOTE:** TABULATED WEIGHTS ARE APPROXIMATE. REFER TO ASSEMBLY DRAWING FOR FINAL WEIGHTS. ALL WEIGHTS SHALL BE VERIFIED PRIOR TO LIFTING.



PO BOX 5999  
PEORIA, IL 61601-5999  
TOLL FREE 800-727-ROHN

THIS DRAWING IS THE PROPERTY OF ROHN. IT IS NOT TO BE REPRODUCED, COPIED OR TRACED IN WHOLE OR IN PART WITHOUT OUR WRITTEN CONSENT.

**SPRINT**

DESIGN PROFILE  
70' TAPERED STEEL POLE  
WILTON, RICHDALE TERRACE, CT

DWN: SWG      CHK'D:      DATE: 8/20/2019


ENGR:      SHEET #: 1 OF 1

PRJ. ENGR: SWG      PRJ. MANGR:      REV: 0

DRAWING NO: Q19-11267-1 PROFILE




NOTE: SEE DRAWING NO. B090548 FOR STANDARD FOUNDATION NOTES.



**PLAN VIEW**

(2) NO. 4 CIRCULAR STIRRUPS ENCLOSING VERTICAL BARS @ 2'-1/2" C-C W/ 180 DEG. STAGGERED 6" MIN LAPS TERMINATED AT EACH END WITH A STD. ACI 318 HOOK ENGAGING A VERTICAL BAR WITH 2" COVER (TYP).

NO. 4 CIRCULAR STIRRUPS ENCLOSING VERTICAL BARS WITH 24" LAPS STAGGERED 180 DEG, ON 6" CENTERS



**ELEVATION VIEW**

**FACTORED REACTIONS**

O.T.M. = 285.8 FT-K  
 DOWNLOAD = 16.2 KIPS  
 SHEAR = 5.4 KIPS

**CONCRETE VOLUME**

SQUARE PIER 4.4 CU.YDS  
 PAD 6.5 CU.YDS  
 TOTAL 10.9 CU.YDS

FILE NO.

Q19-11267-1

REVISIONS

| REV | DESCRIPTION | DWN | CHK | APP |
|-----|-------------|-----|-----|-----|
|     |             |     |     |     |

PRELIMINARY  
NOT FOR CONSTRUCTION



PO BOX 5999  
 PEORIA, IL 61601-5999  
 TOLL FREE 800-727-ROHN

THIS DRAWING IS THE PROPERTY OF ROHN. IT IS NOT TO BE REPRODUCED, COPIED OR TRACED IN WHOLE OR IN PART WITHOUT OUR WRITTEN CONSENT.

MAT W/RAISED PIER  
 PRESUMPTIVE CLAY PER ANS/TTA-222-G

DWN: SWG      CHK'D:      DATE: 8/20/2019

ENGR:      SHEET #: 1 OF 1

PRJ. ENGR: SWG      PRJ. MANAGR:      REV: 0

DRAWING NO: Q19-11267-1 FOUNDATION

Quote Specific Terms:

- 1- This proposal is valid for 30 calendar days from the quotation date. Please refer to ROHN's proposal number when submitting your purchase order.
- 2- ROHN's Terms for Material Purchases are: 40% down payment with the order; 40% down payment –when fabrication is complete and the tower is ready to ship; 20% within 30 days of shipment from the point of manufacturing.
- 3- This proposal is subject to the attached Terms and Conditions of Sale.
- 4- Foundation and tower designs, if ordered independently, are \$1500. This cost is deductible from the overall price of the structure once the structure is released for production and shipped. Design work will be billed at the time the work is provided. Please specify as a separate line item on your purchase order.
- 5- Quoted prices do not include taxes. Refer to Terms and Conditions of Sale. Taxes will be invoiced unless an exemption certificate is provided with the order.
- 6- Shipment schedules are contingent upon the backlog at the time of order and the availability of materials and resources.
- 7- Certification of ROHN's products or foundation designs based on specifications provided to ROHN's do not include services for serving as a project's prime professional or engineer of record for the purposes of reviewing and coordinating documents submitted for a building permit, including deferred submittals and documents prepared by others. ROHN's has not verified that the design parameters provided to ROHN's for this proposal meets the requirements for the intended application or meets the requirements of the appropriate regulatory agencies. Price adjustments may apply for requirements in addition to those stated in this proposal.
- 8- Prices for foundation designs to be based on geotechnical data to be supplied at the time of an order are based on the design of conventional foundations consisting of pier and pad, caissons, mat and deadman anchor blocks. Other types of foundation designs, if required for site-specific conditions, will be quoted upon receipt of the geotechnical data.
- 9- Materials and work placed on hold for more than 30 days after placement of an order will be subject to a price review upon notification to proceed with the order. This may result in an increase to the quoted prices.
- 10- For structures to be shipped by the customer at the point of manufacturing, dunnage and loading charges of \$350 may apply and will be invoiced with the structure.
- 11- Storage charges will be .02% of invoice amount per day with a minimum charge of \$8.00 a day. These charges will be invoiced on a monthly basis for material requested to be withheld from shipment. Storage will begin 30 days from the date the buyer is notified that the shipment is ready for pickup or delivery.
- 12- Estimated freight pricing is obtained at the time the proposal is generated. If a significant amount of time elapses between the proposal and the customer's order date, freight prices may fluctuate. Final freight pricing will be reviewed and confirmed at the time an order is placed. Final freight pricing is subject to change.
- 13- Additional freight may apply for optional items ordered. Prices for optional items are based on the optional items being ordered with the structure.
- 14- Acceptance of an order is contingent on customer credit approval. Terms, as noted above, may be subject to change.
- 15- Design profile provided at time of quotation is preliminary and is subject to change based upon final design.
- 16- This quotation is proprietary, confidential and a trade secret of ROHN. This proposal is being provided for the exclusive use of our customer and is not to be disclosed to third parties.
- 17- Unless noted above, ROHN's general terms and conditions (attached) apply.
- 18- Purchaser agrees to accept delivery on the mutually agreed upon delivery date, typically stated in the customer's purchase order. If this date passes, and the product is completed and staged for delivery, the Purchaser acknowledges that they have accepted title to the goods by default. If customer has requested early shipment of partial materials, such materials may be invoiced at the time of shipment.
- 19- Sealed Design Drawings and Calculations will be supplied in ELECTRONIC format only unless otherwise requested.
- 20- If EACH Page of a Design set must be sealed, Please ADD \$250.00 for EACH set prepared in this manner.
- 21- For quotes including installation service the following apply:
  - a. Non-union, non-prevailing wages, and non-winter conditions.
  - b. In the event existing soil conditions are found to be other than assumed for design, change orders for a price adjustment from the quoted price may be required.
  - c. Customer agrees to obtain any and all required permits pursuant to the job.
  - d. Site accessible for over the road truck delivery of materials. Customer is responsible for unloading the truck in a timely manner, otherwise waiting charges may apply.
  - e. ROHN assumes sufficient room for delivery of tower and sufficient room for installation of tower and foundation (if applicable) at tower site.

## Rohn Products LLC Terms and Conditions Relating to All Sales

1. All quotation, proposals, prices, or other terms are made for acceptance within 30 days (after 30 days, prices in effect at time of shipment will apply) and shipment within 30 days of purchase order date, unless otherwise stated. They are subject to change without notice; however, ROHN invites your request for an extension. Prices are also subject to review prior to acceptance of any order due to raw material price fluctuations. No other price protection is available. Any order placed on hold will have the price reviewed and adjusted upon release.

2. Every effort will be made to maintain shipping schedules, either on ROHN equipment or via common carrier. ROHN cannot be responsible for delays in shipping caused by state or local agencies with regard to permits, routing, weather, detours, etc. All deliveries and schedules are contingent on availability of raw materials, fuel, and transportation. ROHN will not be liable for damages on account of any delays or abnormalities caused in shipping due to causes beyond our reasonable control. ROHN reserves the right to make partial shipments and to submit invoices accordingly.

3. Changes or modifications to orders can be made only by written agreement executed by all parties affected thereby, which agreement shall include any price modification.

4. ROHN's responsibility ceases upon delivery of all shipments to the carrier. The unloading of all shipments is the responsibility of the Buyer, not the carrier or ROHN. Buyer is warned against accepting for merchandise until careful inspection has been made. Any claim made against ROHN must be made within 90 days after receipt of merchandise. All merchandise leaving ROHN's factory has been carefully inspected and ROHN does not assume responsibility for damages or shortages which occur in transit. Buyer must make all claims and report all damages and losses to the delivering transportation company.

5. No federal, state, or local taxes are included in quoted prices. All quotations, proposals, prices, or other terms are subject to increase without notification by the amount of any sales, excise, or other tax levied or charged to seller by any governmental agency and any such tax will be passed onto purchaser as a tax or as an addition to the selling price. This also applies to all costs incurred due to local statutes or governmental regulations.

6. Orders are not subject to cancellation by Buyer except by written agreement with seller. Any order canceled, after any work has been done by ROHN, such as drawings, production, etc., will have a cancellation charge, to be determined solely at the discretion of ROHN for whatever work has been performed with a minimum of 25% of the purchase order price. If Buyer so chooses, he shall have the right to receive the material already performed at time of cancellation at the quoted price. If an order is canceled before any work has been done by ROHN, a \$200 cancellation charge will apply.

7. Material received may not be returned by Buyer except by written agreement with seller. In all cases, permission must be secured from ROHN prior to the returning of any goods for credit. All returned goods are subject to a minimum service charge of 25%, plus all transportation charges, and are subject to inspection by ROHN. Returned goods will be offered and paid for only upon proof of purchase (i.e. invoice no.) and credit will be issued against invoice value. ROHN reserves the sole right to determine amount of credit to be issued on all goods returned for credit. Only standard, currently manufactured ROHN products may be considered for return and credit. Unsaleable products will be scrapped and no credit will be received. If returned goods are determined to have no value and Buyer wishes them returned, the Buyer will be charged return freight. Safety equipment, erection equipment, insulators, transformers, nuts and bolts are not returnable.

8. ROHN warrants the commercial items of its manufacture only, to be reasonably fit for the purpose for which they are manufactured and sold, provided, however, that this warranty shall be effective only if purchaser installs all material according to ROHN's recommendations and specifications and that purchaser during the warranty period shall regularly, not less than semi-annually, inspect and properly maintain all items. Any item found unfit for its purpose within 12 months from date of delivery will be repaired or replaced free of charge, F.O.B. ROHN's plant. ROHN shall be immediately notified in writing of such unfitness. ROHN reserves the sole right to determine if any material is to be repaired or replaced free of charge or to be supplied at ROHN's standard prices. Such obligation shall be limited to parts returned for inspection, properly packed and expenses prepaid, and providing inspection shall satisfactorily indicate defects. The warranty herein made is in lieu of all other warranties and, except as expressly stated herein, ROHN does not make and there are no warranties or obligations of any kind or nature whatsoever either expressed or implied including, but not restricted to, warranty or obligations as to product, material, workmanship, or manufacture or as to the use of the items covered hereby. ROHN shall not under any circumstances be liable to third persons for any claims for damages including direct, special, indirect, or consequential damages for any reason. The Buyer agrees to indemnify and to hold ROHN harmless for, of, and from any loss, claims, damages, expenses and attorney's fees, including but not limited to, any fines, penalties and corrective measures ROHN may sustain by reason of Buyer's failure to comply with said laws, rules, and regulations in connection with the performance of this sale. The above warranty warranted applies only to items manufactured by ROHN. Items not manufactured by ROHN are guaranteed only to the extent and in the manner warranted and guaranteed to ROHN by the manufacturer of such items and then only to the extent ROHN is liable to enforce such warranty or guarantee.

ROHN will assume no responsibility for the adequacy of any product if material is used which is not totally supplied by ROHN. The above sets forth the only warranty made by ROHN in connection with items manufactured or sold by it, and any provisions in any proposals, specifications, advertising, or other provisions hereof, are merely descriptive and are not to be construed as warranties made by ROHN. All warranties are void on drawings made by others, whether by a professional engineer, sealed or not, that are not rechecked by ROHN and approved by ROHN. ROHN assumes no liability for the adequacy of the drawings or the product. Without limiting the generality of the foregoing, the Buyer hereby indemnifies ROHN and hold ROHN harmless from any and all claims and/or damages (including direct, special, indirect or consequential damages, attorneys' fees and costs) relating to or arising out of any highway structure or component not designed by ROHN.

**ROHN hereby disclaims any and all warranties, including express or implied warranties of merchantability and fitness for any particular purpose, relating to or arising out of metal fatigue.**

9. ROHN reserves the right to change or modify the product and construction of any product manufactured by ROHN and to substitute material equal to or superior to that originally specified.

10. Buyer agrees not to disclose or make available to any third party processes, drawings, specifications, reports, photographs, data and other technical or proprietary information relating to ROHN products without obtaining prior written consent of ROHN.

11. No proposal, order, quotation, or acceptance may be changed or varied by verbal agreement, and all orders are accepted only under the provisions set forth herein.

12. Purchase orders and requests for quotations must be submitted in writing to ROHN. It is the responsibility of the Buyer or Buyer Representative to provide ROHN design criteria (environmental loads, equipment loads, operational limitations, geotechnical information, etc.) based on site-specific data. In designing the product for the Buyer, ROHN is relying solely and entirely on design criteria provided by the Buyer to ROHN. Without limiting the generality of the indemnities in these Terms & Conditions, the Buyer hereby indemnifies ROHN and holds ROHN harmless from and against any and all claims and/or damages (including direct, special, indirect or consequential damages, attorneys' fees and costs) relating to or arising out of any inaccuracy or incompleteness in design criteria provided to ROHN by the Buyer, and the Buyer waives all claims against ROHN for same.

13. If outside source inspection, assembly, etc. is required prior to shipment of an order, \$50.00 per man hour (plus equipment time, if applicable) is chargeable, with \$300.00 as a minimum.

14. Any welding inspection required by Buyer or Buyer's specifications must be done at ROHN's plant prior to packing and shipment of material from ROHN's plant.

15. A minimum charge of \$25.00 will be billed for special handling and preparation of material for air shipments.

16. ROHN reserves the right to apply all remittances and credit memos to the oldest outstanding balance in your account. No credits will be issued for any reason against a purchase order whose billing is more than 90 days old. Buyer corrections or complaints must be made within this period of time.

17. Standard catalog prices do not include special drawings or product evaluations. If any are required, there will be a charge.

18. ROHN at all times reserves the right to take pictures of any or all of its products after installation for advertising purposes, except those which are under classified governmental control.

19. The Buyer will be responsible for any extra charges incurred on prepaid shipments.

20. A service charge not to exceed 2% per month or maximum allowable per State law will be billed on all accounts not paid within 30 days of invoice date.

21. Minimum total net worth of merchandise which can be ordered is \$100.00. Any orders placed for less will be billed at \$100.00.

22. Storage charges will be .02% of invoice amount per day with a minimum charge of \$8.00 a day. These charges will be invoiced on a monthly basis for material requested to be withheld from shipment. Storage will begin 30 days from the date the buyer is notified that the shipment is ready for pickup or delivery

23. All CIA requirements must be met with certified checks or money orders to insure prompt shipment.

24. Should it become necessary for ROHN to enforce the provisions of this contract, a purchase order or an invoice through pre-suit negotiations, or by instituting or participating in any legal (including bankruptcy) proceedings, including but not limited to injunctive or other equitable/legal relief, including any appeals associated with the foregoing, ROHN shall be entitled to recover for reasonable attorney's fees, costs of collection and court costs incurred whether the attorney's fees are incurred for the purpose of negotiation, trial, appellate or other legal services.

25. Once the equipment is ready for pickup or has been shipped, an invoice for payment in full shall be issued by ROHN.

26. Buyer is responsible for inspection of material upon delivery. ROHN should be notified of any shortages or discrepancies within 48 hours of delivery. ROHN will not be responsible for down time or equipment ordered.

**DESIGNED APPURTENANCE LOADING**

| TYPE                               | ELEVATION | TYPE                               | ELEVATION |
|------------------------------------|-----------|------------------------------------|-----------|
| 15 ft x 3" dia whip                | 74.5      | (12) RRU                           | 67        |
| 72.1" x 11.9" x 7.1" w/ mount pipe | 67        | 72.1" x 11.9" x 7.1" w/ mount pipe | 67        |
| 72.1" x 11.9" x 7.1" w/ mount pipe | 67        | 14' Platform w/ Handrail           | 67        |


**MATERIAL STRENGTH**

| GRADE   | Fy     | Fu     | GRADE | Fy | Fu |
|---------|--------|--------|-------|----|----|
| A572-65 | 65 ksi | 80 ksi |       |    |    |

**TOWER DESIGN NOTES**



1. Tower is located in Fairfield County, Connecticut.
2. Tower designed for Exposure B to the TIA-222-G Standard.
3. Tower designed for a 94 mph basic wind in accordance with the TIA-222-G Standard.
4. Tower is also designed for a 50 mph basic wind with 0.75 in ice. Ice is considered to increase in thickness with height.
5. Deflections are based upon a 60 mph wind.
6. Tower Structure Class II.
7. Topographic Category 3 with Crest Height of 125.00 ft
8. ANSI/TIA-222-G wind speeds are Vasd winds. Refer to IBC Table 1609.3.1 for Vult wind speed conversions.
9. TOWER RATING: 98.5%

|                    |         |         |     |
|--------------------|---------|---------|-----|
| Section            | 1       | 2       | 2.5 |
| Length (ft)        | 36.00   | 35.25   |     |
| Number of Sides    | 18      | 18      |     |
| Thickness (in)     | 0.1875  | 0.2188  |     |
| Socket Length (ft) | 2.25    |         |     |
| Top Dia (in)       | 10.5000 | 15.4443 |     |
| Bot Dia (in)       | 16.1739 | 21.0000 |     |
| Grade              | A572-65 |         |     |
| Weight (K)         | 1.0     | 1.5     | 2.5 |



95 MPH Vasd ASCE-7-05 POLE DESIGN IS EQUIVALENT TO AN ASCE-7-10 123 MPH Vult WIND SPEED

ALL REACTIONS ARE FACTORED



**DESIGN MEETS TIA-222-H**

**Preliminary Design**

**Not For Fabrication**

Estimated Total Structure Wt. = 2847 lbs



QUALITY STEEL POLES. DELIVERED.

Design may not be used without written permission from Michael F. Plahovinsak, PE

|               |  |
|---------------|--|
| BASE PLATE:   | 2" x 34" ROUND (50 KSI)                                |
| ANCHOR BOLTS: | (4) ANCHORS ON 28" B.C<br>2.25 in. A615 GR. 75 X 7'-0" |

|  |  |  |   |                 |                |
|--|--|--|---|-----------------|----------------|
| <b>Michael F. Plahovinsak, P.E.</b>  |  |  | <b>Job: 70-ft Monopole - MFP #23519-590</b>       |                 |                |
| 18301 State Route 161<br>Plain City, OH 43064<br>Phone: 614-398-6250<br>FAX: mike@mfpeng.com |  |  | Project: CT60XC001 Wilton Richdale Terrace        | Client: 19-0982 | Drawn by: Mike |
|  |  |  | Code: TIA-222-G                                   | Date: 08/14/19  | App'd:         |
|  |  |  | Path: J:\Projects\235-TAPP\23519-590\23519-590.er | Scale: NTS      | Dwg No. E-1    |



---

## Structural Analysis Report

Prepared for:

**KGI**


805 Las Cimas Parkway  
Building Three, Suite 370  
Austin, TX 78746

ATTN: Mr. Sean Rock

**Structure** : 114 ft Monopole  
**Site ID** : 27741\_B  
**Proposed Carrier** : Sprint  
**Site Name** : Round Hill CT  
**Site Location** : 395 Round Hill Road  
Greenwich, CT  
41.095117, -73.664219  
**County** : Greenwich  
**Date** : September 16, 2019  
**Max Usage** : 51%  
**Result** : Pass

Prepared By:  
Jung Hyun Hong  
Structural Engineer

A handwritten signature in black ink, appearing to read 'JH Hong'.







**Table of Contents**

|                                      |          |
|--------------------------------------|----------|
| Introduction .....                   | 1        |
| Supporting Documents .....           | 1        |
| Analysis .....                       | 1        |
| Conclusion.....                      | 1        |
| Existing and Reserved Equipment..... | 2        |
| Equipment to be Removed.....         | 2        |
| Proposed Equipment .....             | 2        |
| Structure Usages.....                | 3        |
| Foundations .....                    | 3        |
| Deflection, Twist, and Sway.....     | 3        |
| Standard Conditions .....            | 4        |
| Calculations .....                   | Attached |

**Introduction**

The purpose of this report is to summarize results of a structural analysis performed on the 114 ft monopole to reflect the change in loading by Sprint.

**Supporting Documents**

|                            |   |
|----------------------------|---|
| <b>Tower Drawings</b>      | EI Drawing #GS56652-2, dated September 28, 2007   |
| <b>Foundation Drawing</b>  | EI Drawing #14679S-115.0, dated February 12, 2007 |
| <b>Geotechnical Report</b> | Clarence Welti Associate, dated February 6, 2007  |

**Analysis**

The tower was analyzed using American Tower Corporation’s tower analysis software. This program considers an elastic three-dimensional model and second-order effects per ANSI/TIA-222.

|                                 |  |
|---------------------------------|--|
| <b>Basic Wind Speed:</b>        | 93 mph (3-Second Gust) Vasd / 120 mph (3-Second Gust) Vult       |
| <b>Basic Wind Speed w/ Ice:</b> | 50 mph (3-Second Gust) w/ 3/4" radial ice concurrent             |
| <b>Code:</b>                    | ANSI/TIA-222-G / 2015 IBC / 2018 Connecticut State Building Code |
| <b>Structure Class:</b>         | II   |
| <b>Exposure Category:</b>       | D (Hurricane Zone)   |
| <b>Topographic Category:</b>    | 1  |
| <b>Crest Height:</b>            | 0 ft   |
| <b>Spectral Response:</b>       | $S_s = 0.26, S_1 = 0.07$   |
| <b>Site Class:</b>              | D - Stiff Soil   |

**Conclusion**

Based on the analysis results, the structure meets the requirements per the applicable codes listed above. The tower and foundation can support the equipment as described in this report.

**The pier reinforcement is less than the minimum allowance. Due to this, the pier should be frequently monitored for cracking/spalling.**

If you have any questions or require additional information, please contact Semaan Engineering Solutions at 402-289-1888.

**Existing and Reserved Equipment**

This loading **is** included in the analysis.

| Centerline Elevation (ft) |        | Qty. | Antenna         | Mount Type                           | Coax (in)   | Carrier  |
|---------------------------|--------|------|-----------------|--------------------------------------|-------------|----------|
| Mount                     | Equip. |      |                 |                                      |             |          |
| 110.0                     | 110.0  | 3    | DBXNH-6565A-A2M | Flush Mount<br>Inside Canister       | (12) 1 5/8" | T-Mobile |
|                           |        | 3    | TMAT1921XB6811A |                                      |             |          |
|                           |        | 3    | 782 11066       |                                      |             |          |
| 100.0                     | -      | -    | -               | Flush Mount<br>Inside Canister       | (6) 1 5/8"  | Sprint   |
| 90.0                      | -      | -    | -               | Empty Flush Mount<br>Inside Canister | -           | -        |

**Equipment to be Removed**

This loading **is not** included in the analysis.

| Centerline Elevation (ft) |        | Qty. | Antenna        | Mount Type | Coax (in) | Carrier |
|---------------------------|--------|------|----------------|------------|-----------|---------|
| Mount                     | Equip. |      |                |            |           |         |
| 100.0                     | 100.0  | 3    | RR65-18-00DPL2 | -          | -         | Sprint  |

**Proposed Equipment**

This loading **is** included in the analysis.

| Centerline Elevation (ft) |        | Qty. | Antenna            | Mount Type                              | Coax (in)  | Carrier |
|---------------------------|--------|------|--------------------|---|------------|---------|
| Mount                     | Equip. |      |                    |   |            |         |
| 100.0                     | 100.0  | 3    | APXVSP18-C-A20     | Existing Flush Mount<br>Inside Canister | (2) 1 1/4" | Sprint  |
|                           |        | 6    | KIT-FD9R6004/1C-DL |   |            |         |
|                           |        | 9    | IBC1900HG-SA       |   |            |         |

Install proposed coax inside the pole shaft.





**Structure Usages**

| Structural Component | Controlling Usage | Pass/Fail |
|----------------------|-------------------|-----------|
| Shaft                | 31%               | Pass      |
| Base Plate           | 31%               | Pass      |
| Anchor Bolts         | 51%               | Pass      |
| Flange Bolts         | 9%                | Pass      |

**Foundations**

| Reaction Component               | Analysis Reactions | % of Usage |
|----------------------------------|--------------------|------------|
| Moment (Kips-Ft)                 | 504.0              | 46%        |
| Axial (Kips)                     | 27.0               | 18%        |
| Shear (Kips)                     | 8.9                | 19%        |
| Reinf. Conc. Foundation Capacity | N/A                | 22%        |

The structure base reactions resulting from this analysis were found to be acceptable through analysis based on geotechnical and foundation information, therefore no modification or reinforcement of the foundation will be required.

**Deflection and Sway\***

| Antenna Elevation (ft) | Antenna            | Carrier | Deflection (ft) | Sway (Rotation) (°) |
|------------------------|--------------------|---------|-----------------|---------------------|
| 100.0                  | APXVSP18-C-A20     | Sprint  | 0.390           | 0.752               |
|                        | KIT-FD9R6004/1C-DL |         |                 |                     |
|                        | IBC1900HG-SA       |         |                 |                     |

\*Deflection and Sway was evaluated considering a design wind speed of 60 mph (3-Second Gust) per ANSI/TIA-222-G



## **Standard Conditions**


All engineering services are performed on the basis that the information used is current and correct. This information may consist of, but is not necessary limited, to:

- Information supplied by the client regarding the structure itself, antenna, mounts and feed line loading on the structure and its components, or other relevant information.
- Information from drawings in the possession of Semaan Engineering Solutions, or generated by field inspections or measurements of the structure.

It is the responsibility of the client to ensure that the information provided to Semaan Engineering Solutions Holdings and used in the performance of our engineering services is correct and complete. In the absence of information to the contrary, we assume that all structures were constructed in accordance with the drawings and specifications and that their capacity has not significantly changed from the "as new" condition.

Unless explicitly agreed by both the client and Semaan Engineering Solutions, all services will be performed in accordance with the current revision of ANSI/TIA -222. The design basic wind speed will be determined based on the minimum basic wind speed as prescribed in ANSI/TIA-222. Although every effort is taken to ensure that the loading considered is adequate to meet the requirements of all applicable regulatory entities, we can provide no assurance to meet any other local and state codes or requirements. If wind and ice loads or other relevant parameters are to be different from the minimum values recommended by the codes, the client shall specify the exact requirement.

All services are performed, results obtained, and recommendations made in accordance with generally accepted engineering principles and practices. Semaan Engineering Solutions Holdings is not responsible for the conclusions, opinions and recommendations made by others based on the information we supply.




| Job Information                         |                      |
|---|----------------------|
| Pole : 27741_B                          | Code: ANSI/TIA-222-G |
| Description :                           |                      |
| Client : KGI                            | Struct Class : II    |
| Location : Round Hill CT, Greenwich, CT |                      |
| Shape : 18 Sides                        | Exposure : D         |
| Height : 114.00 (ft)                    | Topo : 1             |
| Base Elev (ft): 1.00                    |                      |
| Taper: 0.14434(in/ft)                   |                      |

| Sections Properties |             |               |        |            |            |             |               |                   |
|---------------------|-------------|---------------|--------|------------|------------|-------------|---------------|-------------------|
| Shaft Section       | Length (ft) | Diameter (in) |        | Thick (in) | Joint Type | Overlap     |               | Steel Grade (ksi) |
|                     |             | Top           | Bottom |            |            | Length (in) | Taper (in/ft) |                   |
| 1                   | 52.658      | 33.39         | 41.00  | 0.250      |            | 0.000       | 0.144341      | 65                |
| 2                   | 36.158      | 29.25         | 34.46  | 0.188      | Slip Joint | 57.781      | 0.144341      | 65                |
| 3                   | 10.000      | 5.750         | 5.750  | 2.875      | Butt Joint | 0.000       | 0.000000      | 50                |
| 4                   | 10.000      | 4.500         | 4.500  | 2.250      | Butt Joint | 0.000       | 0.000000      | 50                |
| 5                   | 10.000      | 4.500         | 4.500  | 0.674      | Butt Joint | 0.000       | 0.000000      | 35                |

| Discrete Appurtenance |                 |     |                    |  |
|-----------------------|-----------------|-----|--------------------|--|
| Attach Elev (ft)      | Force Elev (ft) | Qty | Description        |  |
| 110.000               | 110.000         | 3   | 782 11066          |  |
| 110.000               | 110.000         | 3   | TMAT1921XB6811A    |  |
| 110.000               | 110.000         | 3   | DBXNH-6565A-A2M    |  |
| 110.000               | 110.000         | 1   | Flush Mount        |  |
| 100.000               | 100.000         | 9   | IBC1900HG-SA       |  |
| 100.000               | 100.000         | 6   | KIT-FD9R6004/1C-DL |  |
| 100.000               | 100.000         | 3   | APXVSP18-C-A20     |  |
| 100.000               | 100.000         | 1   | Flush Mount        |  |
| 90.000                | 90.000          | 1   | Flush Mount        |  |
| 81.500                | 83.000          | 1   | GPS                |  |
| 81.500                | 81.500          | 1   | 3 ft Standoff      |  |

| Linear Appurtenance |        |             |                 |
|---------------------|--------|-------------|-----------------|
| Elev (ft) From      | To     | Description | Exposed To Wind |
| 104.0               | 114.0  | Concealment | Yes             |
| 94.000              | 104.0  | Concealment | Yes             |
| 84.000              | 94.000 | Concealment | Yes             |
| 0.000               | 100.0  | .32"        | No              |
| 0.000               | 100.0  | 1 1/4" Coax | No              |
| 0.000               | 100.0  | 1 5/8" Coax | No              |
| 0.000               | 110.0  | .32"        | No              |
| 0.000               | 110.0  | 1 5/8" Coax | No              |
| 0.000               | 81.500 | 1/2" Coax   | No              |


| Load Cases              |  |
|-------------------------|--|
| 1.2D + 1.6W             | 93 mph with No Ice                       |
| 0.9D + 1.6W             | 93 mph with No Ice (Reduced DL)          |
| 1.2D + 1.0Di + 1.0Wi    | 50 mph with 0.75 in Radial Ice           |
| (1.2 + 0.2Sds) * DL + E | Seismic Equivalent Lateral Forces Method |
| (1.2 + 0.2Sds) * DL + E | Seismic Equivalent Modal Analysis Method |
| (0.9 - 0.2Sds) * DL + E | Seismic (Reduced DL) Equivalent Lateral  |
| (0.9 - 0.2Sds) * DL + E | Seismic (Reduced DL) Equivalent Modal    |
| 1.0D + 1.0W             | Serviceability 60 mph                    |



| Reactions                    |                 |             |             |
|------------------------------|-----------------|-------------|-------------|
| Load Case                    | Moment (kip-ft) | Shear (kip) | Axial (kip) |
| 1.2D + 1.6W                  | 503.96          | 8.95        | 15.49       |
| 0.9D + 1.6W                  | 501.34          | 8.94        | 11.61       |
| 1.2D + 1.0Di + 1.0Wi         | 196.12          | 3.32        | 27.00       |
| (1.2 + 0.2Sds) * DL + E ELFM | 67.58           | 0.83        | 15.40       |
| (1.2 + 0.2Sds) * DL + E EMAM | 61.07           | 0.80        | 15.40       |
| (0.9 - 0.2Sds) * DL + E ELFM | 67.07           | 0.83        | 10.37       |
| (0.9 - 0.2Sds) * DL + E EMAM | 60.55           | 0.80        | 10.37       |
| 1.0D + 1.0W                  | 130.62          | 2.33        | 12.91       |

| Dish Deflections |                  |                 |                |
|------------------|------------------|-----------------|----------------|
| Load Case        | Attach Elev (ft) | Deflection (in) | Rotation (deg) |
|                  | 0.00             | 0.000           | 0.000          |





Site Number: 27741\_B

Code: ANSI/TIA-222-G

© 2007 - 2019 by ATC IP LLC. All rights reserved.

Site Name: Round Hill CT, Greenwich, CT

Engineering Number: REV01

9/16/2019 9:52:08 AM

Customer: KGI

### Analysis Parameters

|                    |   |                    |       |
|--------------------|---|--------------------|-------|
| Location:          | Greenwich County, CT  |                    |       |
| Code:              | ANSI/TIA-222-G  | Height (ft):       | 114   |
| Shape:             | 18 Sides. Sect 3: Round Solid. Sect 4: Round Solid. Sect 5: Round |                    | 41.00 |
| Pole Type:         | Custom  | Top Diameter (in): | 4.50  |
| Pole Manufacturer: | EI  | Taper (in/ft) :    | 0.144 |

### Ice & Wind Parameters

|                       |        |                                |         |
|-----------------------|--------|--------------------------------|---------|
| Structure Class:      | II     | Design Wind Speed Without Ice: | 93 mph  |
| Exposure Category:    | D      | Design Wind Speed With Ice:    | 50 mph  |
| Topographic Category: | 1      | Operational Wind Speed:        | 60 mph  |
| Crest Height:         | 0.0 ft | Design Ice Thickness:          | 0.75 in |

### Seismic Parameters

|  |  |            |       |
|--|--|------------|-------|
| Analysis Method:                       | Equivalent Modal Analysis & Equivalent Lateral Force Methods |            |       |
| Site Class:                            | D - Stiff Soil   |            |       |
| Period Based on Rayleigh Method (sec): | 1.53   |            |       |
| $T_L$ (sec):                           | 6  | $p$ :      | 1.3   |
| $S_s$ :                                | 0.259  | $S_1$ :    | 0.071 |
| $F_a$ :                                | 1.593  | $F_v$ :    | 2.400 |
| $S_{ds}$ :                             | 0.275  | $S_{d1}$ : | 0.114 |
|  |  | $C_s$ :    | 0.050 |
|  |  | $C_s$ Max: | 0.050 |
|  |  | $C_s$ Min: | 0.030 |

### Load Cases

|                              |   |
|------------------------------|---|
| 1.2D + 1.6W                  | 93 mph with No Ice                                    |
| 0.9D + 1.6W                  | 93 mph with No Ice (Reduced DL)                       |
| 1.2D + 1.0Di + 1.0Wi         | 50 mph with 0.75 in Radial Ice                        |
| (1.2 + 0.2Sds) * DL + E ELFM | Seismic Equivalent Lateral Forces Method              |
| (1.2 + 0.2Sds) * DL + E EMAM | Seismic Equivalent Modal Analysis Method              |
| (0.9 - 0.2Sds) * DL + E ELFM | Seismic (Reduced DL) Equivalent Lateral Forces Method |
| (0.9 - 0.2Sds) * DL + E EMAM | Seismic (Reduced DL) Equivalent Modal Analysis Method |
| 1.0D + 1.0W                  | Serviceability 60 mph                                 |

Site Number: 27741\_B

Code: ANSI/TIA-222-G

© 2007 - 2019 by ATC IP LLC. All rights reserved.

Site Name: Round Hill CT, Greenwich, CT

Engineering Number: REV01

9/16/2019 9:52:08 AM

Customer: KGI

**Shaft Section Properties**

| Sect Info    | Length (ft) | Thick (in) | Fy (ksi) | Joint Type | Slip Joint Len (in) | Weight (lb) | Bottom   |           |                         |                       |           |           | Top      |           |                         |                       |           |           |               |
|--------------|-------------|------------|----------|------------|---------------------|-------------|----------|-----------|-------------------------|-----------------------|-----------|-----------|----------|-----------|-------------------------|-----------------------|-----------|-----------|---------------|
|              |             |            |          |            |                     |             | Dia (in) | Elev (ft) | Area (in <sup>2</sup> ) | Ix (in <sup>4</sup> ) | W/t Ratio | D/t Ratio | Dia (in) | Elev (ft) | Area (in <sup>2</sup> ) | Ix (in <sup>4</sup> ) | W/t Ratio | D/t Ratio | Taper (in/ft) |
| 1-18         | 52.658      | 0.2500     | 65       |            | 0.00                | 5,253       | 41.00    | 0.00      | 32.33                   | 6783.7                | 27.51     | 164.00    | 33.39    | 52.66     | 26.30                   | 3651.8                | 22.15     | 133.60    | 0.144341      |
| 2-18         | 36.158      | 0.1875     | 65       | Slip       | 57.78               | 2,319       | 34.46    | 47.84     | 20.40                   | 3029.3                | 31.00     | 183.84    | 29.25    | 84.00     | 17.30                   | 1845.7                | 26.10     | 156.00    | 0.144341      |
| 3-RS         | 10.000      | 2.8750     | 50       | Butt       | 0.00                | 884         | 5.750    | 84.00     | 25.97                   | 53.7                  | 0.00      | 2.00      | 5.750    | 94.00     | 25.97                   | 53.7                  | 0.00      | 2.00      | 0.000000      |
| 4-RS         | 10.000      | 2.2500     | 50       | Butt       | 0.00                | 541         | 4.500    | 94.00     | 15.90                   | 20.1                  | 0.00      | 2.00      | 4.500    | 104.00    | 15.90                   | 20.1                  | 0.00      | 2.00      | 0.000000      |
| 5-R          | 10.000      | 0.6740     | 35       | Butt       | 0.00                | 276         | 4.500    | 104.00    | 8.10                    | 14.8                  | 0.00      | 6.68      | 4.500    | 114.00    | 8.10                    | 14.8                  | 0.00      | 6.68      | 0.000000      |
| Shaft Weight |             |            |          |            |                     | 9,273       |          |           |                         |                       |           |           |          |           |                         |                       |           |           |               |

**Discrete Appurtenance Properties**

| Attach Elev (ft) | Description        | Qty | Weight (lb) | No Ice EPAa (sf) | Orientation Factor | Weight (lb) | Ice EPAa (sf) | Orientation Factor | Distance From Face (ft) | Vert Ecc (ft) |
|------------------|--------------------|-----|-------------|------------------|--------------------|-------------|---------------|--------------------|-------------------------|---------------|
| 110.00           | 782 11066          | 3   | 1.76        | 0.000            | 1.00               | 5.33        | 0.000         | 1.00               | 0.000                   | 0.000         |
| 110.00           | DBXNH-6565A-A2M    | 3   | 34.20       | 0.000            | 1.00               | 153.17      | 0.000         | 1.00               | 0.000                   | 0.000         |
| 110.00           | Flush Mount        | 1   | 120.00      | 0.000            | 1.00               | 282.20      | 0.000         | 1.00               | 0.000                   | 0.000         |
| 110.00           | TMAT1921XB6811A    | 3   | 17.60       | 0.000            | 1.00               | 35.49       | 0.000         | 1.00               | 0.000                   | 0.000         |
| 100.00           | APXVSPP18-C-A20    | 3   | 57.00       | 0.000            | 1.00               | 171.46      | 0.000         | 1.00               | 0.000                   | 0.000         |
| 100.00           | Flush Mount        | 1   | 120.00      | 0.000            | 1.00               | 280.64      | 0.000         | 1.00               | 0.000                   | 0.000         |
| 100.00           | IBC1900HG-SA       | 9   | 22.00       | 0.000            | 1.00               | 66.18       | 0.000         | 1.00               | 0.000                   | 0.000         |
| 100.00           | KIT-FD9R6004/1C-DL | 6   | 6.40        | 0.000            | 1.00               | 17.57       | 0.000         | 1.00               | 0.000                   | 0.000         |
| 90.00            | Flush Mount        | 1   | 120.00      | 0.000            | 1.00               | 278.93      | 0.000         | 1.00               | 0.000                   | 0.000         |
| 81.50            | 3 ft Standoff      | 1   | 40.00       | 2.630            | 1.00               | 115.55      | 8.247         | 1.00               | 0.000                   | 0.000         |
| 81.50            | GPS                | 1   | 10.00       | 0.070            | 1.00               | 13.74       | 0.200         | 1.00               | 0.000                   | 1.500         |
| Totals           |                    | 32  | 978.08      |                  |                    | 2,768.38    |               |                    | Number of Loadings :    | 11            |

**Linear Appurtenance Properties**

| Elev From (ft) | Elev To (ft) | Qty | Description       | Coax Diameter (in) | Coax Weight (lb/ft) | Protected Flat | Protected Width (in) | Exposed To Wind | Carrier  |
|----------------|--------------|-----|-------------------|--------------------|---------------------|----------------|----------------------|-----------------|----------|
| 104.00         | 114.00       | 1   | Concealment (0.5) | 30.00              | 16.95               | N              | 12.75                | Y               |          |
| 0.00           | 110.00       | 1   | .32"              | 0.32               | 0.06                | N              | 0.00                 | N               | T-Mobile |
| 0.00           | 110.00       | 12  | 1 5/8" Coax       | 1.98               | 1.04                | N              | 0.00                 | N               | T-Mobile |
| 94.00          | 104.00       | 1   | Concealment (0.5) | 30.00              | 16.95               | N              | 12.75                | Y               |          |
| 0.00           | 100.00       | 1   | .32"              | 0.32               | 0.06                | N              | 0.00                 | N               | Sprint   |
| 0.00           | 100.00       | 2   | 1 1/4" Coax       | 1.55               | 0.66                | N              | 0.00                 | N               | Sprint   |
| 0.00           | 100.00       | 6   | 1 5/8" Coax       | 1.98               | 1.04                | N              | 0.00                 | N               | Sprint   |
| 84.00          | 94.00        | 1   | Concealment (0.5) | 30.00              | 16.95               | N              | 12.12                | Y               |          |
| 0.00           | 81.50        | 1   | 1/2" Coax         | 0.65               | 0.16                | N              | 0.00                 | N               | Sprint   |

Site Number: 27741\_B

Code: ANSI/TIA-222-G

© 2007 - 2019 by ATC IP LLC. All rights reserved.

Site Name: Round Hill CT, Greenwich, CT

Engineering Number: REV01

9/16/2019 9:52:09 AM

Customer: KGI

**Segment Properties** (Max Len : 5.ft)

| Seg Top Elev (ft) | Description     | Thick (in) | Flat Dia (in) | Area (in <sup>2</sup> ) | Ix (in <sup>4</sup> ) | W/t Ratio | D/t Ratio | Fy (ksi) | S (in <sup>3</sup> ) | Z (in <sup>3</sup> ) | Weight (lb) |
|-------------------|-----------------|------------|---------------|-------------------------|-----------------------|-----------|-----------|----------|----------------------|----------------------|-------------|
| 0.00              |                 | 0.2500     | 41.000        | 32.334                  | 6,783.7               | 27.51     | 164.00    | 69.0     | 325.9                | 0.0                  | 0.0         |
| 5.00              |                 | 0.2500     | 40.278        | 31.761                  | 6,429.6               | 27.00     | 161.11    | 69.6     | 314.4                | 0.0                  | 545.3       |
| 10.00             |                 | 0.2500     | 39.557        | 31.189                  | 6,088.1               | 26.49     | 158.23    | 70.2     | 303.1                | 0.0                  | 535.5       |
| 15.00             |                 | 0.2500     | 38.835        | 30.616                  | 5,758.9               | 25.98     | 155.34    | 70.8     | 292.1                | 0.0                  | 525.8       |
| 20.00             |                 | 0.2500     | 38.113        | 30.043                  | 5,441.7               | 25.47     | 152.45    | 71.4     | 281.2                | 0.0                  | 516.0       |
| 25.00             |                 | 0.2500     | 37.391        | 29.471                  | 5,136.4               | 24.96     | 149.57    | 72.0     | 270.6                | 0.0                  | 506.3       |
| 30.00             |                 | 0.2500     | 36.670        | 28.898                  | 4,842.8               | 24.45     | 146.68    | 72.6     | 260.1                | 0.0                  | 496.5       |
| 35.00             |                 | 0.2500     | 35.948        | 28.325                  | 4,560.6               | 23.94     | 143.79    | 73.2     | 249.9                | 0.0                  | 486.8       |
| 40.00             |                 | 0.2500     | 35.226        | 27.753                  | 4,289.5               | 23.43     | 140.91    | 73.8     | 239.8                | 0.0                  | 477.1       |
| 45.00             |                 | 0.2500     | 34.505        | 27.180                  | 4,029.4               | 22.93     | 138.02    | 74.4     | 230.0                | 0.0                  | 467.3       |
| 47.84             | Bot - Section 2 | 0.2500     | 34.094        | 26.855                  | 3,886.4               | 22.64     | 136.38    | 74.8     | 224.5                | 0.0                  | 261.3       |
| 50.00             |                 | 0.2500     | 33.783        | 26.607                  | 3,780.1               | 22.42     | 135.13    | 75.0     | 220.4                | 0.0                  | 345.3       |
| 52.66             | Top - Section 1 | 0.1875     | 33.774        | 19.988                  | 2,848.7               | 30.35     | 180.13    | 65.7     | 166.1                | 0.0                  | 421.0       |
| 55.00             |                 | 0.1875     | 33.436        | 19.786                  | 2,763.6               | 30.03     | 178.33    | 66.1     | 162.8                | 0.0                  | 158.5       |
| 60.00             |                 | 0.1875     | 32.715        | 19.357                  | 2,587.5               | 29.35     | 174.48    | 66.9     | 155.8                | 0.0                  | 333.0       |
| 65.00             |                 | 0.1875     | 31.993        | 18.927                  | 2,419.1               | 28.68     | 170.63    | 67.7     | 148.9                | 0.0                  | 325.7       |
| 70.00             |                 | 0.1875     | 31.271        | 18.498                  | 2,258.1               | 28.00     | 166.78    | 68.5     | 142.2                | 0.0                  | 318.4       |
| 75.00             |                 | 0.1875     | 30.549        | 18.069                  | 2,104.4               | 27.32     | 162.93    | 69.3     | 135.7                | 0.0                  | 311.1       |
| 80.00             |                 | 0.1875     | 29.828        | 17.639                  | 1,957.9               | 26.64     | 159.08    | 70.1     | 129.3                | 0.0                  | 303.8       |
| 81.50             |                 | 0.1875     | 29.611        | 17.510                  | 1,915.3               | 26.44     | 157.93    | 70.3     | 127.4                | 0.0                  | 89.7        |
| 84.00             | Top - Section 2 | 0.1875     | 29.250        | 17.295                  | 1,845.7               | 26.10     | 156.00    | 70.7     | 124.3                | 0.0                  | 148.0       |
| 84.00             | Bot - Section 3 | 2.8750     | 5.750         | 25.967                  | 53.7                  | 0.00      | 2.00      | 50.0     | 18.7                 | 31.7                 |             |
| 85.00             |                 | 2.8750     | 5.750         | 25.967                  | 53.7                  | 0.00      | 2.00      | 50.0     | 18.7                 | 31.7                 | 88.4        |
| 90.00             |                 | 2.8750     | 5.750         | 25.967                  | 53.7                  | 0.00      | 2.00      | 50.0     | 18.7                 | 31.7                 | 441.8       |
| 94.00             | Top - Section 3 | 2.8750     | 5.750         | 25.967                  | 53.7                  | 0.00      | 2.00      | 50.0     | 18.7                 | 31.7                 | 353.4       |
| 94.00             | Bot - Section 4 | 2.2500     | 4.500         | 15.904                  | 20.1                  | 0.00      | 2.00      | 50.0     | 8.9                  | 15.2                 |             |
| 95.00             |                 | 2.2500     | 4.500         | 15.904                  | 20.1                  | 0.00      | 2.00      | 50.0     | 8.9                  | 15.2                 | 54.1        |
| 100.0             |                 | 2.2500     | 4.500         | 15.904                  | 20.1                  | 0.00      | 2.00      | 50.0     | 8.9                  | 15.2                 | 270.6       |
| 104.0             | Top - Section 4 | 2.2500     | 4.500         | 15.904                  | 20.1                  | 0.00      | 2.00      | 50.0     | 8.9                  | 15.2                 | 216.5       |
| 104.0             | Bot - Section 5 | 0.6740     | 4.500         | 8.101                   | 14.8                  | 0.00      | 6.68      | 35.0     | 6.6                  | 10.0                 |             |
| 105.0             |                 | 0.6740     | 4.500         | 8.101                   | 14.8                  | 0.00      | 6.68      | 35.0     | 6.6                  | 10.0                 | 27.6        |
| 110.0             |                 | 0.6740     | 4.500         | 8.101                   | 14.8                  | 0.00      | 6.68      | 35.0     | 6.6                  | 10.0                 | 137.8       |
| 114.0             |                 | 0.6740     | 4.500         | 8.101                   | 14.8                  | 0.00      | 6.68      | 35.0     | 6.6                  | 10.0                 | 110.3       |
| 9,272.8           |                 |            |               |                         |                       |           |           |          |                      |                      |             |



Site Number: 27741\_B

Code: ANSI/TIA-222-G

© 2007 - 2019 by ATC IP LLC. All rights reserved.

Site Name: Round Hill CT, Greenwich, CT

Engineering Number: REV01

9/16/2019 9:52:09 AM

Customer: KGI

**Load Case:** 1.2D + 1.6W

93 mph with No Ice

25 Iterations

Gust Response Factor : 1.10

Wind Importance Factor : 1.00

Dead Load Factor : 1.20

Wind Load Factor : 1.60

**Applied Segment Forces Summary**

| Seg<br>Elev<br>(ft) | Description     | Shaft Forces    |                      | Discrete Forces |                          |                         | Linear Forces        |                 | Sum of Forces        |                 |                      |                          |                      |
|---------------------|-----------------|-----------------|----------------------|-----------------|--------------------------|-------------------------|----------------------|-----------------|----------------------|-----------------|----------------------|--------------------------|----------------------|
|                     |                 | Wind FX<br>(lb) | Dead<br>Load<br>(lb) | Wind FX<br>(lb) | Torsion<br>MY<br>(lb-ft) | Moment<br>MZ<br>(lb-ft) | Dead<br>Load<br>(lb) | Wind FX<br>(lb) | Dead<br>Load<br>(lb) | Wind FX<br>(lb) | Dead<br>Load<br>(lb) | Torsion<br>MY<br>(lb-ft) | Moment<br>MZ<br>(lb) |
| 0.00                |                 | 213.1           | 0.0                  |                 |                          |                         |                      | 0.0             | 0.0                  | 213.1           | 0.0                  | 0.0                      | 0.0                  |
| 5.00                |                 | 422.4           | 654.3                |                 |                          |                         |                      | 0.0             | 121.9                | 422.4           | 776.2                | 0.0                      | 0.0                  |
| 10.00               |                 | 414.8           | 642.6                |                 |                          |                         |                      | 0.0             | 121.9                | 414.8           | 764.5                | 0.0                      | 0.0                  |
| 15.00               |                 | 414.8           | 630.9                |                 |                          |                         |                      | 0.0             | 121.9                | 414.8           | 752.8                | 0.0                      | 0.0                  |
| 20.00               |                 | 423.3           | 619.2                |                 |                          |                         |                      | 0.0             | 121.9                | 423.3           | 741.2                | 0.0                      | 0.0                  |
| 25.00               |                 | 431.2           | 607.5                |                 |                          |                         |                      | 0.0             | 121.9                | 431.2           | 729.5                | 0.0                      | 0.0                  |
| 30.00               |                 | 436.1           | 595.8                |                 |                          |                         |                      | 0.0             | 121.9                | 436.1           | 717.8                | 0.0                      | 0.0                  |
| 35.00               |                 | 438.9           | 584.2                |                 |                          |                         |                      | 0.0             | 121.9                | 438.9           | 706.1                | 0.0                      | 0.0                  |
| 40.00               |                 | 439.9           | 572.5                |                 |                          |                         |                      | 0.0             | 121.9                | 439.9           | 694.4                | 0.0                      | 0.0                  |
| 45.00               |                 | 345.0           | 560.8                |                 |                          |                         |                      | 0.0             | 121.9                | 345.0           | 682.7                | 0.0                      | 0.0                  |
| 47.84               | Bot - Section 2 | 220.6           | 313.6                |                 |                          |                         |                      | 0.0             | 69.3                 | 220.6           | 382.9                | 0.0                      | 0.0                  |
| 50.00               |                 | 213.4           | 414.4                |                 |                          |                         |                      | 0.0             | 52.6                 | 213.4           | 467.0                | 0.0                      | 0.0                  |
| 52.66               | Top - Section 1 | 221.1           | 505.2                |                 |                          |                         |                      | 0.0             | 64.8                 | 221.1           | 570.0                | 0.0                      | 0.0                  |
| 55.00               |                 | 323.2           | 190.2                |                 |                          |                         |                      | 0.0             | 57.1                 | 323.2           | 247.3                | 0.0                      | 0.0                  |
| 60.00               |                 | 437.9           | 399.6                |                 |                          |                         |                      | 0.0             | 121.9                | 437.9           | 521.5                | 0.0                      | 0.0                  |
| 65.00               |                 | 434.1           | 390.8                |                 |                          |                         |                      | 0.0             | 121.9                | 434.1           | 512.7                | 0.0                      | 0.0                  |
| 70.00               |                 | 429.8           | 382.1                |                 |                          |                         |                      | 0.0             | 121.9                | 429.8           | 504.0                | 0.0                      | 0.0                  |
| 75.00               |                 | 424.8           | 373.3                |                 |                          |                         |                      | 0.0             | 121.9                | 424.8           | 495.2                | 0.0                      | 0.0                  |
| 80.00               |                 | 273.9           | 364.5                |                 |                          |                         |                      | 0.0             | 121.9                | 273.9           | 486.4                | 0.0                      | 0.0                  |
| 81.50               | Appertunance(s) | 166.9           | 107.6                | 138.5           | 0.0                      | 5.4                     | 60.0                 | 0.0             | 36.6                 | 305.4           | 204.2                | 0.0                      | 0.0                  |
| 84.00               | Top - Section 2 | 118.9           | 177.7                |                 |                          |                         |                      | 0.0             | 60.5                 | 118.9           | 238.1                | 0.0                      | 0.0                  |
| 85.00               |                 | 89.5            | 106.0                |                 |                          |                         |                      | 31.3            | 44.5                 | 120.8           | 150.6                | 0.0                      | 0.0                  |
| 90.00               | Appertunance(s) | 134.9           | 530.2                | 0.0             | 0.0                      | 0.0                     | 144.0                | 157.4           | 222.7                | 292.2           | 896.8                | 0.0                      | 0.0                  |
| 94.00               | Top - Section 3 | 72.1            | 424.1                |                 |                          |                         |                      | 127.0           | 178.1                | 199.1           | 602.3                | 0.0                      | 0.0                  |
| 95.00               |                 | 71.4            | 64.9                 |                 |                          |                         |                      | 33.5            | 44.5                 | 104.9           | 109.5                | 0.0                      | 0.0                  |
| 100.00              | Appertunance(s) | 107.5           | 324.7                | 0.0             | 0.0                      | 0.0                     | 632.9                | 168.6           | 222.7                | 276.2           | 1,180.3              | 0.0                      | 0.0                  |
| 104.00              | Top - Section 4 | 60.0            | 259.8                |                 |                          |                         |                      | 136.0           | 141.6                | 196.0           | 401.3                | 0.0                      | 0.0                  |
| 105.00              |                 | 72.6            | 33.1                 |                 |                          |                         |                      | 34.1            | 35.4                 | 106.7           | 68.5                 | 0.0                      | 0.0                  |
| 110.00              | Appertunance(s) | 109.3           | 165.4                | 0.0             | 0.0                      | 0.0                     | 336.8                | 171.5           | 176.9                | 280.8           | 679.2                | 0.0                      | 0.0                  |
| 114.00              |                 | 48.8            | 132.3                |                 |                          |                         |                      | 138.2           | 81.4                 | 186.9           | 213.7                | 0.0                      | 0.0                  |
| <b>Totals:</b>      |                 |                 |                      |                 |                          |                         |                      |                 |                      | <b>9,146.23</b> | <b>15,496.6</b>      | <b>0.00</b>              | <b>0.00</b>          |

**Load Case: 1.2D + 1.6W**

93 mph with No Ice

25 Iterations

Gust Response Factor : 1.10

Wind Importance Factor : 1.00

Dead Load Factor : 1.20

Wind Load Factor : 1.60

**Calculated Forces**

| Seg Elev (ft) | Pu FY (-) (kips) | Vu FX (-) (kips) | Tu MY (ft-kips) | Mu MZ (ft-kips) | Mu MX (ft-kips) | Resultant Moment (ft-kips) | phi Pn (kips) | phi Vn (kips) | phi Tn (ft-kips) | phi Mn (ft-kips) | Total Deflect (in) | Rotation (deg) | Ratio |
|---------------|------------------|------------------|-----------------|-----------------|-----------------|----------------------------|---------------|---------------|------------------|------------------|--------------------|----------------|-------|
| 0.00          | -15.49           | -8.95            | 0.00            | -503.96         | 0.00            | 503.96                     | 2,009.33      | 1,004.66      | 3,370.24         | 1,687.62         | 0.00               | 0.00           | 0.306 |
| 5.00          | -14.70           | -8.55            | 0.00            | -459.22         | 0.00            | 459.22                     | 1,990.85      | 995.43        | 3,279.75         | 1,642.31         | 0.05               | -0.10          | 0.287 |
| 10.00         | -13.92           | -8.16            | 0.00            | -416.48         | 0.00            | 416.48                     | 1,971.76      | 985.88        | 3,189.37         | 1,597.06         | 0.21               | -0.20          | 0.268 |
| 15.00         | -13.16           | -7.76            | 0.00            | -375.70         | 0.00            | 375.70                     | 1,952.06      | 976.03        | 3,099.16         | 1,551.88         | 0.47               | -0.29          | 0.249 |
| 20.00         | -12.41           | -7.35            | 0.00            | -336.91         | 0.00            | 336.91                     | 1,931.73      | 965.87        | 3,009.15         | 1,506.81         | 0.82               | -0.38          | 0.230 |
| 25.00         | -11.67           | -6.93            | 0.00            | -300.16         | 0.00            | 300.16                     | 1,910.79      | 955.40        | 2,919.43         | 1,461.88         | 1.26               | -0.46          | 0.211 |
| 30.00         | -10.95           | -6.50            | 0.00            | -265.52         | 0.00            | 265.52                     | 1,889.23      | 944.62        | 2,830.03         | 1,417.12         | 1.79               | -0.54          | 0.193 |
| 35.00         | -10.24           | -6.07            | 0.00            | -233.01         | 0.00            | 233.01                     | 1,867.06      | 933.53        | 2,741.01         | 1,372.54         | 2.40               | -0.61          | 0.175 |
| 40.00         | -9.54            | -5.63            | 0.00            | -202.68         | 0.00            | 202.68                     | 1,844.27      | 922.13        | 2,652.43         | 1,328.19         | 3.08               | -0.68          | 0.158 |
| 45.00         | -8.86            | -5.28            | 0.00            | -174.52         | 0.00            | 174.52                     | 1,820.86      | 910.43        | 2,564.34         | 1,284.08         | 3.82               | -0.74          | 0.141 |
| 47.84         | -8.48            | -5.06            | 0.00            | -159.50         | 0.00            | 159.50                     | 1,807.27      | 903.64        | 2,514.51         | 1,259.12         | 4.28               | -0.78          | 0.131 |
| 50.00         | -8.01            | -4.85            | 0.00            | -148.58         | 0.00            | 148.58                     | 1,796.83      | 898.42        | 2,476.80         | 1,240.24         | 4.63               | -0.80          | 0.124 |
| 52.66         | -7.44            | -4.62            | 0.00            | -135.69         | 0.00            | 135.69                     | 1,181.92      | 590.96        | 1,634.85         | 818.64           | 5.09               | -0.83          | 0.172 |
| 55.00         | -7.20            | -4.30            | 0.00            | -124.87         | 0.00            | 124.87                     | 1,176.68      | 588.34        | 1,611.12         | 806.76           | 5.50               | -0.85          | 0.161 |
| 60.00         | -6.68            | -3.86            | 0.00            | -103.37         | 0.00            | 103.37                     | 1,165.04      | 582.52        | 1,560.37         | 781.35           | 6.43               | -0.91          | 0.138 |
| 65.00         | -6.17            | -3.42            | 0.00            | -84.07          | 0.00            | 84.07                      | 1,152.79      | 576.40        | 1,509.51         | 755.88           | 7.41               | -0.96          | 0.117 |
| 70.00         | -5.67            | -2.99            | 0.00            | -66.95          | 0.00            | 66.95                      | 1,139.92      | 569.96        | 1,458.59         | 730.38           | 8.45               | -1.01          | 0.097 |
| 75.00         | -5.18            | -2.56            | 0.00            | -52.01          | 0.00            | 52.01                      | 1,126.44      | 563.22        | 1,407.67         | 704.88           | 9.52               | -1.05          | 0.078 |
| 80.00         | -4.70            | -2.28            | 0.00            | -39.22          | 0.00            | 39.22                      | 1,112.33      | 556.17        | 1,356.80         | 679.41           | 10.64              | -1.08          | 0.062 |
| 81.50         | -4.50            | -1.97            | 0.00            | -35.80          | 0.00            | 35.80                      | 1,107.98      | 553.99        | 1,341.56         | 671.78           | 10.98              | -1.08          | 0.057 |
| 84.00         | -4.27            | -1.85            | 0.00            | -30.88          | 0.00            | 30.88                      | 1,100.61      | 550.30        | 1,316.18         | 659.07           | 11.55              | -1.10          | 0.051 |
| 84.00         | -4.27            | -1.85            | 0.00            | -30.88          | 0.00            | 30.88                      | 1,168.53      | 584.26        | 139.98           | 118.82           | 11.55              | -1.10          | 0.264 |
| 85.00         | -4.11            | -1.75            | 0.00            | -29.03          | 0.00            | 29.03                      | 1,168.53      | 584.26        | 139.98           | 118.82           | 11.78              | -1.10          | 0.248 |
| 90.00         | -3.21            | -1.46            | 0.00            | -20.29          | 0.00            | 20.29                      | 1,168.53      | 584.26        | 139.98           | 118.82           | 13.30              | -1.76          | 0.174 |
| 94.00         | -2.61            | -1.25            | 0.00            | -14.45          | 0.00            | 14.45                      | 1,168.53      | 584.26        | 139.98           | 118.82           | 14.93              | -2.12          | 0.124 |
| 94.00         | -2.61            | -1.25            | 0.00            | -14.45          | 0.00            | 14.45                      | 715.69        | 357.85        | 67.10            | 56.95            | 14.93              | -2.12          | 0.257 |
| 95.00         | -2.49            | -1.16            | 0.00            | -13.20          | 0.00            | 13.20                      | 715.69        | 357.85        | 67.10            | 56.95            | 15.38              | -2.20          | 0.235 |
| 100.00        | -1.32            | -0.84            | 0.00            | -7.40           | 0.00            | 7.40                       | 715.69        | 357.85        | 67.10            | 56.95            | 18.10              | -2.93          | 0.132 |
| 104.00        | -0.93            | -0.63            | 0.00            | -4.03           | 0.00            | 4.03                       | 715.69        | 357.85        | 67.10            | 56.95            | 20.70              | -3.25          | 0.072 |
| 104.00        | -0.93            | -0.63            | 0.00            | -4.03           | 0.00            | 4.03                       | 255.19        | 127.60        | 34.57            | 26.17            | 20.70              | -3.25          | 0.158 |
| 105.00        | -0.86            | -0.52            | 0.00            | -3.40           | 0.00            | 3.40                       | 255.19        | 127.60        | 34.57            | 26.17            | 21.38              | -3.30          | 0.133 |
| 110.00        | -0.20            | -0.20            | 0.00            | -0.80           | 0.00            | 0.80                       | 255.19        | 127.60        | 34.57            | 26.17            | 24.97              | -3.50          | 0.031 |
| 114.00        | 0.00             | -0.19            | 0.00            | 0.00            | 0.00            | 0.00                       | 255.19        | 127.60        | 34.57            | 26.17            | 27.91              | -3.53          | 0.000 |

|                               |                                 |                               |
|-------------------------------|---------------------------------|-------------------------------|
| <b>Load Case:</b> 0.9D + 1.6W | 93 mph with No Ice (Reduced DL) | 25 Iterations                 |
| Gust Response Factor : 1.10   |                                 | Wind Importance Factor : 1.00 |
| Dead Load Factor : 0.90       |                                 |                               |
| Wind Load Factor : 1.60       |                                 |                               |

**Applied Segment Forces Summary**

| Seg Elev (ft)  | Description     | Shaft Forces |                | Discrete Forces |                    |                   | Linear Forces  |              | Sum of Forces  |                 |                 |                    |                |
|----------------|-----------------|--------------|----------------|-----------------|--------------------|-------------------|----------------|--------------|----------------|-----------------|-----------------|--------------------|----------------|
|                |                 | Wind FX (lb) | Dead Load (lb) | Wind FX (lb)    | Torsion MY (lb-ft) | Moment MZ (lb-ft) | Dead Load (lb) | Wind FX (lb) | Dead Load (lb) | Wind FX (lb)    | Dead Load (lb)  | Torsion MY (lb-ft) | Moment MZ (lb) |
| 0.00           |                 | 213.1        | 0.0            |                 |                    |                   |                | 0.0          | 0.0            | 213.1           | 0.0             | 0.0                | 0.0            |
| 5.00           |                 | 422.4        | 490.7          |                 |                    |                   |                | 0.0          | 91.4           | 422.4           | 582.2           | 0.0                | 0.0            |
| 10.00          |                 | 414.8        | 482.0          |                 |                    |                   |                | 0.0          | 91.4           | 414.8           | 573.4           | 0.0                | 0.0            |
| 15.00          |                 | 414.8        | 473.2          |                 |                    |                   |                | 0.0          | 91.4           | 414.8           | 564.6           | 0.0                | 0.0            |
| 20.00          |                 | 423.3        | 464.4          |                 |                    |                   |                | 0.0          | 91.4           | 423.3           | 555.9           | 0.0                | 0.0            |
| 25.00          |                 | 431.2        | 455.7          |                 |                    |                   |                | 0.0          | 91.4           | 431.2           | 547.1           | 0.0                | 0.0            |
| 30.00          |                 | 436.1        | 446.9          |                 |                    |                   |                | 0.0          | 91.4           | 436.1           | 538.3           | 0.0                | 0.0            |
| 35.00          |                 | 438.9        | 438.1          |                 |                    |                   |                | 0.0          | 91.4           | 438.9           | 529.6           | 0.0                | 0.0            |
| 40.00          |                 | 439.9        | 429.3          |                 |                    |                   |                | 0.0          | 91.4           | 439.9           | 520.8           | 0.0                | 0.0            |
| 45.00          |                 | 345.0        | 420.6          |                 |                    |                   |                | 0.0          | 91.4           | 345.0           | 512.0           | 0.0                | 0.0            |
| 47.84          | Bot - Section 2 | 220.6        | 235.2          |                 |                    |                   |                | 0.0          | 52.0           | 220.6           | 287.2           | 0.0                | 0.0            |
| 50.00          |                 | 213.4        | 310.8          |                 |                    |                   |                | 0.0          | 39.5           | 213.4           | 350.3           | 0.0                | 0.0            |
| 52.66          | Top - Section 1 | 221.1        | 378.9          |                 |                    |                   |                | 0.0          | 48.6           | 221.1           | 427.5           | 0.0                | 0.0            |
| 55.00          |                 | 323.2        | 142.7          |                 |                    |                   |                | 0.0          | 42.8           | 323.2           | 185.5           | 0.0                | 0.0            |
| 60.00          |                 | 437.9        | 299.7          |                 |                    |                   |                | 0.0          | 91.4           | 437.9           | 391.1           | 0.0                | 0.0            |
| 65.00          |                 | 434.1        | 293.1          |                 |                    |                   |                | 0.0          | 91.4           | 434.1           | 384.6           | 0.0                | 0.0            |
| 70.00          |                 | 429.8        | 286.5          |                 |                    |                   |                | 0.0          | 91.4           | 429.8           | 378.0           | 0.0                | 0.0            |
| 75.00          |                 | 424.8        | 280.0          |                 |                    |                   |                | 0.0          | 91.4           | 424.8           | 371.4           | 0.0                | 0.0            |
| 80.00          |                 | 273.9        | 273.4          |                 |                    |                   |                | 0.0          | 91.4           | 273.9           | 364.8           | 0.0                | 0.0            |
| 81.50          | Appertunance(s) | 166.9        | 80.7           | 138.5           | 0.0                | 5.4               | 45.0           | 0.0          | 27.4           | 305.4           | 153.2           | 0.0                | 0.0            |
| 84.00          | Top - Section 2 | 118.9        | 133.2          |                 |                    |                   |                | 0.0          | 45.4           | 118.9           | 178.6           | 0.0                | 0.0            |
| 85.00          |                 | 89.5         | 79.5           |                 |                    |                   |                | 31.3         | 33.4           | 120.8           | 112.9           | 0.0                | 0.0            |
| 90.00          | Appertunance(s) | 134.9        | 397.6          | 0.0             | 0.0                | 0.0               | 108.0          | 157.4        | 167.0          | 292.2           | 672.6           | 0.0                | 0.0            |
| 94.00          | Top - Section 3 | 72.1         | 318.1          |                 |                    |                   |                | 127.0        | 133.6          | 199.1           | 451.7           | 0.0                | 0.0            |
| 95.00          |                 | 71.4         | 48.7           |                 |                    |                   |                | 33.5         | 33.4           | 104.9           | 82.1            | 0.0                | 0.0            |
| 100.00         | Appertunance(s) | 107.5        | 243.5          | 0.0             | 0.0                | 0.0               | 474.7          | 168.6        | 167.0          | 276.2           | 885.2           | 0.0                | 0.0            |
| 104.00         | Top - Section 4 | 60.0         | 194.8          |                 |                    |                   |                | 136.0        | 106.2          | 196.0           | 301.0           | 0.0                | 0.0            |
| 105.00         |                 | 72.6         | 24.8           |                 |                    |                   |                | 34.1         | 26.5           | 106.7           | 51.4            | 0.0                | 0.0            |
| 110.00         | Appertunance(s) | 109.3        | 124.1          | 0.0             | 0.0                | 0.0               | 252.6          | 171.5        | 132.7          | 280.8           | 509.4           | 0.0                | 0.0            |
| 114.00         |                 | 48.8         | 99.2           |                 |                    |                   |                | 138.2        | 61.0           | 186.9           | 160.3           | 0.0                | 0.0            |
| <b>Totals:</b> |                 |              |                |                 |                    |                   |                |              |                | <b>9,146.23</b> | <b>11,622.4</b> | <b>0.00</b>        | <b>0.00</b>    |

**Load Case: 0.9D + 1.6W**

93 mph with No Ice (Reduced DL)

25 Iterations

Gust Response Factor : 1.10

Wind Importance Factor : 1.00

Dead Load Factor : 0.90

Wind Load Factor : 1.60

**Calculated Forces**

| Seg Elev (ft) | Pu FY (-) (kips) | Vu FX (-) (kips) | Tu MY (ft-kips) | Mu MZ (ft-kips) | Mu MX (ft-kips) | Resultant Moment (ft-kips) | phi Pn (kips) | phi Vn (kips) | phi Tn (ft-kips) | phi Mn (ft-kips) | Total Deflect (in) | Rotation (deg) | Ratio |
|---------------|------------------|------------------|-----------------|-----------------|-----------------|----------------------------|---------------|---------------|------------------|------------------|--------------------|----------------|-------|
| 0.00          | -11.61           | -8.94            | 0.00            | -501.34         | 0.00            | 501.34                     | 2,009.33      | 1,004.66      | 3,370.24         | 1,687.62         | 0.00               | 0.00           | 0.303 |
| 5.00          | -11.02           | -8.54            | 0.00            | -456.62         | 0.00            | 456.62                     | 1,990.85      | 995.43        | 3,279.75         | 1,642.31         | 0.05               | -0.10          | 0.284 |
| 10.00         | -10.43           | -8.14            | 0.00            | -413.92         | 0.00            | 413.92                     | 1,971.76      | 985.88        | 3,189.37         | 1,597.06         | 0.21               | -0.20          | 0.265 |
| 15.00         | -9.86            | -7.74            | 0.00            | -373.22         | 0.00            | 373.22                     | 1,952.06      | 976.03        | 3,099.16         | 1,551.88         | 0.47               | -0.29          | 0.246 |
| 20.00         | -9.29            | -7.33            | 0.00            | -334.53         | 0.00            | 334.53                     | 1,931.73      | 965.87        | 3,009.15         | 1,506.81         | 0.82               | -0.38          | 0.227 |
| 25.00         | -8.74            | -6.90            | 0.00            | -297.90         | 0.00            | 297.90                     | 1,910.79      | 955.40        | 2,919.43         | 1,461.88         | 1.26               | -0.46          | 0.208 |
| 30.00         | -8.20            | -6.47            | 0.00            | -263.39         | 0.00            | 263.39                     | 1,889.23      | 944.62        | 2,830.03         | 1,417.12         | 1.78               | -0.54          | 0.190 |
| 35.00         | -7.66            | -6.04            | 0.00            | -231.02         | 0.00            | 231.02                     | 1,867.06      | 933.53        | 2,741.01         | 1,372.54         | 2.38               | -0.61          | 0.172 |
| 40.00         | -7.14            | -5.60            | 0.00            | -200.83         | 0.00            | 200.83                     | 1,844.27      | 922.13        | 2,652.43         | 1,328.19         | 3.06               | -0.68          | 0.155 |
| 45.00         | -6.63            | -5.25            | 0.00            | -172.83         | 0.00            | 172.83                     | 1,820.86      | 910.43        | 2,564.34         | 1,284.08         | 3.80               | -0.74          | 0.138 |
| 47.84         | -6.34            | -5.03            | 0.00            | -157.90         | 0.00            | 157.90                     | 1,807.27      | 903.64        | 2,514.51         | 1,259.12         | 4.25               | -0.77          | 0.129 |
| 50.00         | -5.99            | -4.82            | 0.00            | -147.04         | 0.00            | 147.04                     | 1,796.83      | 898.42        | 2,476.80         | 1,240.24         | 4.60               | -0.80          | 0.122 |
| 52.66         | -5.57            | -4.59            | 0.00            | -134.23         | 0.00            | 134.23                     | 1,181.92      | 590.96        | 1,634.85         | 818.64           | 5.05               | -0.82          | 0.169 |
| 55.00         | -5.38            | -4.27            | 0.00            | -123.48         | 0.00            | 123.48                     | 1,176.68      | 588.34        | 1,611.12         | 806.76           | 5.47               | -0.85          | 0.158 |
| 60.00         | -5.00            | -3.83            | 0.00            | -102.12         | 0.00            | 102.12                     | 1,165.04      | 582.52        | 1,560.37         | 781.35           | 6.38               | -0.91          | 0.135 |
| 65.00         | -4.62            | -3.40            | 0.00            | -82.96          | 0.00            | 82.96                      | 1,152.79      | 576.40        | 1,509.51         | 755.88           | 7.36               | -0.96          | 0.114 |
| 70.00         | -4.24            | -2.96            | 0.00            | -65.98          | 0.00            | 65.98                      | 1,139.92      | 569.96        | 1,458.59         | 730.38           | 8.39               | -1.00          | 0.094 |
| 75.00         | -3.88            | -2.53            | 0.00            | -51.17          | 0.00            | 51.17                      | 1,126.44      | 563.22        | 1,407.67         | 704.88           | 9.45               | -1.04          | 0.076 |
| 80.00         | -3.52            | -2.25            | 0.00            | -38.50          | 0.00            | 38.50                      | 1,112.33      | 556.17        | 1,356.80         | 679.41           | 10.56              | -1.07          | 0.060 |
| 81.50         | -3.37            | -1.95            | 0.00            | -35.12          | 0.00            | 35.12                      | 1,107.98      | 553.99        | 1,341.56         | 671.78           | 10.89              | -1.08          | 0.055 |
| 84.00         | -3.19            | -1.82            | 0.00            | -30.25          | 0.00            | 30.25                      | 1,100.61      | 550.30        | 1,316.18         | 659.07           | 11.46              | -1.09          | 0.049 |
| 84.00         | -3.19            | -1.82            | 0.00            | -30.25          | 0.00            | 30.25                      | 1,168.53      | 584.26        | 139.98           | 118.82           | 11.46              | -1.09          | 0.257 |
| 85.00         | -3.07            | -1.72            | 0.00            | -28.43          | 0.00            | 28.43                      | 1,168.53      | 584.26        | 139.98           | 118.82           | 11.69              | -1.09          | 0.242 |
| 90.00         | -2.39            | -1.43            | 0.00            | -19.83          | 0.00            | 19.83                      | 1,168.53      | 584.26        | 139.98           | 118.82           | 13.19              | -1.73          | 0.169 |
| 94.00         | -1.95            | -1.22            | 0.00            | -14.10          | 0.00            | 14.10                      | 1,168.53      | 584.26        | 139.98           | 118.82           | 14.80              | -2.09          | 0.120 |
| 94.00         | -1.95            | -1.22            | 0.00            | -14.10          | 0.00            | 14.10                      | 715.69        | 357.85        | 67.10            | 56.95            | 14.80              | -2.09          | 0.250 |
| 95.00         | -1.86            | -1.13            | 0.00            | -12.88          | 0.00            | 12.88                      | 715.69        | 357.85        | 67.10            | 56.95            | 15.24              | -2.16          | 0.229 |
| 100.00        | -0.98            | -0.82            | 0.00            | -7.22           | 0.00            | 7.22                       | 715.69        | 357.85        | 67.10            | 56.95            | 17.91              | -2.87          | 0.128 |
| 104.00        | -0.69            | -0.61            | 0.00            | -3.93           | 0.00            | 3.93                       | 715.69        | 357.85        | 67.10            | 56.95            | 20.46              | -3.19          | 0.070 |
| 104.00        | -0.69            | -0.61            | 0.00            | -3.93           | 0.00            | 3.93                       | 255.19        | 127.60        | 34.57            | 26.17            | 20.46              | -3.19          | 0.153 |
| 105.00        | -0.64            | -0.51            | 0.00            | -3.32           | 0.00            | 3.32                       | 255.19        | 127.60        | 34.57            | 26.17            | 21.14              | -3.24          | 0.129 |
| 110.00        | -0.15            | -0.20            | 0.00            | -0.78           | 0.00            | 0.78                       | 255.19        | 127.60        | 34.57            | 26.17            | 24.65              | -3.44          | 0.031 |
| 114.00        | 0.00             | -0.19            | 0.00            | 0.00            | 0.00            | 0.00                       | 255.19        | 127.60        | 34.57            | 26.17            | 27.55              | -3.47          | 0.000 |



Site Number: 27741\_B

Code: ANSI/TIA-222-G

© 2007 - 2019 by ATC IP LLC. All rights reserved.

Site Name: Round Hill CT, Greenwich, CT

Engineering Number: REV01

9/16/2019 9:52:10 AM

Customer: KGI

|  |                                |                               |
|--|--------------------------------|-------------------------------|
| <b>Load Case:</b> 1.2D + 1.0Di + 1.0Wi | 50 mph with 0.75 in Radial Ice | 24 Iterations                 |
| Gust Response Factor : 1.10            | Ice Dead Load Factor : 1.00    | Wind Importance Factor : 1.00 |
| Dead Load Factor : 1.20                |                                | Ice Importance Factor : 1.00  |
| Wind Load Factor : 1.00                |                                |                               |

**Applied Segment Forces Summary**

| Seg Elev (ft)  | Description     | Shaft Forces |                | Discrete Forces |                    |                   | Linear Forces  |              | Sum of Forces  |              |                 |                    |                |             |
|----------------|-----------------|--------------|----------------|-----------------|--------------------|-------------------|----------------|--------------|----------------|--------------|-----------------|--------------------|----------------|-------------|
|                |                 | Wind FX (lb) | Dead Load (lb) | Wind FX (lb)    | Torsion MY (lb-ft) | Moment MZ (lb-ft) | Dead Load (lb) | Wind FX (lb) | Dead Load (lb) | Wind FX (lb) | Dead Load (lb)  | Torsion MY (lb-ft) | Moment MZ (lb) |             |
| 0.00           |                 | 75.2         | 0.0            |                 |                    |                   |                | 0.0          | 0.0            | 75.2         | 0.0             | 0.0                | 0.0            |             |
| 5.00           |                 | 149.5        | 965.7          |                 |                    |                   |                | 0.0          | 121.9          | 149.5        | 1,087.6         | 0.0                | 0.0            |             |
| 10.00          |                 | 147.6        | 977.9          |                 |                    |                   |                | 0.0          | 121.9          | 147.6        | 1,099.8         | 0.0                | 0.0            |             |
| 15.00          |                 | 148.1        | 976.4          |                 |                    |                   |                | 0.0          | 121.9          | 148.1        | 1,098.3         | 0.0                | 0.0            |             |
| 20.00          |                 | 151.7        | 969.7          |                 |                    |                   |                | 0.0          | 121.9          | 151.7        | 1,091.6         | 0.0                | 0.0            |             |
| 25.00          |                 | 154.9        | 960.3          |                 |                    |                   |                | 0.0          | 121.9          | 154.9        | 1,082.2         | 0.0                | 0.0            |             |
| 30.00          |                 | 157.1        | 949.0          |                 |                    |                   |                | 0.0          | 121.9          | 157.1        | 1,070.9         | 0.0                | 0.0            |             |
| 35.00          |                 | 158.5        | 936.5          |                 |                    |                   |                | 0.0          | 121.9          | 158.5        | 1,058.4         | 0.0                | 0.0            |             |
| 40.00          |                 | 159.3        | 923.1          |                 |                    |                   |                | 0.0          | 121.9          | 159.3        | 1,045.0         | 0.0                | 0.0            |             |
| 45.00          |                 | 125.2        | 908.9          |                 |                    |                   |                | 0.0          | 121.9          | 125.2        | 1,030.8         | 0.0                | 0.0            |             |
| 47.84          | Bot - Section 2 | 80.2         | 511.0          |                 |                    |                   |                | 0.0          | 69.3           | 80.2         | 580.3           | 0.0                | 0.0            |             |
| 50.00          |                 | 77.6         | 565.3          |                 |                    |                   |                | 0.0          | 52.6           | 77.6         | 617.9           | 0.0                | 0.0            |             |
| 52.66          | Top - Section 1 | 80.5         | 690.0          |                 |                    |                   |                | 0.0          | 64.8           | 80.5         | 754.8           | 0.0                | 0.0            |             |
| 55.00          |                 | 117.9        | 352.3          |                 |                    |                   |                | 0.0          | 57.1           | 117.9        | 409.5           | 0.0                | 0.0            |             |
| 60.00          |                 | 160.1        | 740.8          |                 |                    |                   |                | 0.0          | 121.9          | 160.1        | 862.7           | 0.0                | 0.0            |             |
| 65.00          |                 | 159.1        | 727.7          |                 |                    |                   |                | 0.0          | 121.9          | 159.1        | 849.6           | 0.0                | 0.0            |             |
| 70.00          |                 | 158.0        | 714.3          |                 |                    |                   |                | 0.0          | 121.9          | 158.0        | 836.3           | 0.0                | 0.0            |             |
| 75.00          |                 | 156.6        | 700.7          |                 |                    |                   |                | 0.0          | 121.9          | 156.6        | 822.6           | 0.0                | 0.0            |             |
| 80.00          |                 | 101.2        | 686.8          |                 |                    |                   |                | 0.0          | 121.9          | 101.2        | 808.7           | 0.0                | 0.0            |             |
| 81.50          | Appertunance(s) | 61.8         | 204.1          | 78.3            | 0.0                | 2.8               | 126.3          | 0.0          | 36.6           | 140.1        | 366.9           | 0.0                | 0.0            |             |
| 84.00          | Top - Section 2 | 42.8         | 336.9          |                 |                    |                   |                | 0.0          | 60.5           | 42.8         | 397.4           | 0.0                | 0.0            |             |
| 85.00          |                 | 25.5         | 120.9          |                 |                    |                   |                | 14.4         | 161.5          | 39.9         | 282.4           | 0.0                | 0.0            |             |
| 90.00          | Appertunance(s) | 38.4         | 605.0          | 0.0             | 0.0                | 0.0               | 422.9          | 72.4         | 808.1          | 110.8        | 1,836.0         | 0.0                | 0.0            |             |
| 94.00          | Top - Section 3 | 20.9         | 484.4          |                 |                    |                   |                | 58.5         | 647.4          | 79.4         | 1,131.8         | 0.0                | 0.0            |             |
| 95.00          |                 | 22.5         | 77.5           |                 |                    |                   |                | 15.3         | 162.0          | 37.8         | 239.5           | 0.0                | 0.0            |             |
| 100.00         | Appertunance(s) | 33.9         | 387.8          | 0.0             | 0.0                | 0.0               | 1,563.7        | 76.9         | 810.5          | 110.8        | 2,762.0         | 0.0                | 0.0            |             |
| 104.00         | Top - Section 4 | 19.0         | 310.5          |                 |                    |                   |                | 62.1         | 612.7          | 81.0         | 923.2           | 0.0                | 0.0            |             |
| 105.00         |                 | 23.0         | 45.8           |                 |                    |                   |                | 15.6         | 153.3          | 38.5         | 199.1           | 0.0                | 0.0            |             |
| 110.00         | Appertunance(s) | 34.6         | 229.3          | 0.0             | 0.0                | 0.0               | 921.9          | 78.4         | 767.1          | 113.0        | 1,918.2         | 0.0                | 0.0            |             |
| 114.00         |                 | 15.5         | 183.7          |                 |                    |                   |                | 63.2         | 554.2          | 78.7         | 737.9           | 0.0                | 0.0            |             |
| <b>Totals:</b> |                 |              |                |                 |                    |                   |                |              |                |              | <b>3,390.81</b> | <b>27,001.4</b>    | <b>0.00</b>    | <b>0.00</b> |

**Load Case:** 1.2D + 1.0Di + 1.0Wi

50 mph with 0.75 in Radial Ice

24 Iterations

Gust Response Factor : 1.10

Ice Dead Load Factor : 1.00

Wind Importance Factor : 1.00

Dead Load Factor : 1.20

Ice Importance Factor : 1.00

Wind Load Factor : 1.00

**Calculated Forces**

| Seg Elev (ft) | Pu FY (-) (kips) | Vu FX (-) (kips) | Tu MY (ft-kips) | Mu MZ (ft-kips) | Mu MX (ft-kips) | Resultant Moment (ft-kips) | phi Pn (kips) | phi Vn (kips) | phi Tn (ft-kips) | phi Mn (ft-kips) | Total Deflect (in) | Rotation (deg) | Ratio |
|---------------|------------------|------------------|-----------------|-----------------|-----------------|----------------------------|---------------|---------------|------------------|------------------|--------------------|----------------|-------|
| 0.00          | -27.00           | -3.32            | 0.00            | -196.12         | 0.00            | 196.12                     | 2,009.33      | 1,004.66      | 3,370.24         | 1,687.62         | 0.00               | 0.00           | 0.130 |
| 5.00          | -25.91           | -3.19            | 0.00            | -179.50         | 0.00            | 179.50                     | 1,990.85      | 995.43        | 3,279.75         | 1,642.31         | 0.02               | -0.04          | 0.122 |
| 10.00         | -24.81           | -3.06            | 0.00            | -163.54         | 0.00            | 163.54                     | 1,971.76      | 985.88        | 3,189.37         | 1,597.06         | 0.08               | -0.08          | 0.115 |
| 15.00         | -23.71           | -2.92            | 0.00            | -148.24         | 0.00            | 148.24                     | 1,952.06      | 976.03        | 3,099.16         | 1,551.88         | 0.18               | -0.11          | 0.108 |
| 20.00         | -22.62           | -2.78            | 0.00            | -133.61         | 0.00            | 133.61                     | 1,931.73      | 965.87        | 3,009.15         | 1,506.81         | 0.32               | -0.15          | 0.100 |
| 25.00         | -21.53           | -2.64            | 0.00            | -119.70         | 0.00            | 119.70                     | 1,910.79      | 955.40        | 2,919.43         | 1,461.88         | 0.50               | -0.18          | 0.093 |
| 30.00         | -20.46           | -2.49            | 0.00            | -106.51         | 0.00            | 106.51                     | 1,889.23      | 944.62        | 2,830.03         | 1,417.12         | 0.70               | -0.21          | 0.086 |
| 35.00         | -19.40           | -2.33            | 0.00            | -94.07          | 0.00            | 94.07                      | 1,867.06      | 933.53        | 2,741.01         | 1,372.54         | 0.94               | -0.24          | 0.079 |
| 40.00         | -18.36           | -2.18            | 0.00            | -82.39          | 0.00            | 82.39                      | 1,844.27      | 922.13        | 2,652.43         | 1,328.19         | 1.21               | -0.27          | 0.072 |
| 45.00         | -17.33           | -2.05            | 0.00            | -71.50          | 0.00            | 71.50                      | 1,820.86      | 910.43        | 2,564.34         | 1,284.08         | 1.51               | -0.30          | 0.065 |
| 47.84         | -16.75           | -1.98            | 0.00            | -65.66          | 0.00            | 65.66                      | 1,807.27      | 903.64        | 2,514.51         | 1,259.12         | 1.69               | -0.31          | 0.061 |
| 50.00         | -16.13           | -1.90            | 0.00            | -61.40          | 0.00            | 61.40                      | 1,796.83      | 898.42        | 2,476.80         | 1,240.24         | 1.83               | -0.32          | 0.058 |
| 52.66         | -15.37           | -1.82            | 0.00            | -56.35          | 0.00            | 56.35                      | 1,181.92      | 590.96        | 1,634.85         | 818.64           | 2.01               | -0.33          | 0.082 |
| 55.00         | -14.96           | -1.70            | 0.00            | -52.10          | 0.00            | 52.10                      | 1,176.68      | 588.34        | 1,611.12         | 806.76           | 2.18               | -0.34          | 0.077 |
| 60.00         | -14.10           | -1.54            | 0.00            | -43.60          | 0.00            | 43.60                      | 1,165.04      | 582.52        | 1,560.37         | 781.35           | 2.55               | -0.37          | 0.068 |
| 65.00         | -13.25           | -1.38            | 0.00            | -35.90          | 0.00            | 35.90                      | 1,152.79      | 576.40        | 1,509.51         | 755.88           | 2.94               | -0.39          | 0.059 |
| 70.00         | -12.42           | -1.22            | 0.00            | -29.00          | 0.00            | 29.00                      | 1,139.92      | 569.96        | 1,458.59         | 730.38           | 3.36               | -0.41          | 0.051 |
| 75.00         | -11.60           | -1.06            | 0.00            | -22.90          | 0.00            | 22.90                      | 1,126.44      | 563.22        | 1,407.67         | 704.88           | 3.79               | -0.42          | 0.043 |
| 80.00         | -10.79           | -0.95            | 0.00            | -17.60          | 0.00            | 17.60                      | 1,112.33      | 556.17        | 1,356.80         | 679.41           | 4.24               | -0.44          | 0.036 |
| 81.50         | -10.42           | -0.81            | 0.00            | -16.17          | 0.00            | 16.17                      | 1,107.98      | 553.99        | 1,341.56         | 671.78           | 4.38               | -0.44          | 0.033 |
| 84.00         | -10.02           | -0.77            | 0.00            | -14.13          | 0.00            | 14.13                      | 1,100.61      | 550.30        | 1,316.18         | 659.07           | 4.61               | -0.45          | 0.031 |
| 84.00         | -10.02           | -0.77            | 0.00            | -14.13          | 0.00            | 14.13                      | 1,168.53      | 584.26        | 139.98           | 118.82           | 4.61               | -0.45          | 0.128 |
| 85.00         | -9.74            | -0.75            | 0.00            | -13.37          | 0.00            | 13.37                      | 1,168.53      | 584.26        | 139.98           | 118.82           | 4.71               | -0.45          | 0.121 |
| 90.00         | -7.90            | -0.66            | 0.00            | -9.60           | 0.00            | 9.60                       | 1,168.53      | 584.26        | 139.98           | 118.82           | 5.34               | -0.75          | 0.088 |
| 94.00         | -6.77            | -0.57            | 0.00            | -6.98           | 0.00            | 6.98                       | 1,168.53      | 584.26        | 139.98           | 118.82           | 6.05               | -0.93          | 0.065 |
| 94.00         | -6.77            | -0.57            | 0.00            | -6.98           | 0.00            | 6.98                       | 715.69        | 357.85        | 67.10            | 56.95            | 6.05               | -0.93          | 0.132 |
| 95.00         | -6.53            | -0.55            | 0.00            | -6.41           | 0.00            | 6.41                       | 715.69        | 357.85        | 67.10            | 56.95            | 6.25               | -0.96          | 0.122 |
| 100.00        | -3.77            | -0.40            | 0.00            | -3.64           | 0.00            | 3.64                       | 715.69        | 357.85        | 67.10            | 56.95            | 7.46               | -1.32          | 0.069 |
| 104.00        | -2.85            | -0.30            | 0.00            | -2.02           | 0.00            | 2.02                       | 715.69        | 357.85        | 67.10            | 56.95            | 8.64               | -1.48          | 0.039 |
| 104.00        | -2.85            | -0.30            | 0.00            | -2.02           | 0.00            | 2.02                       | 255.19        | 127.60        | 34.57            | 26.17            | 8.64               | -1.48          | 0.088 |
| 105.00        | -2.65            | -0.26            | 0.00            | -1.72           | 0.00            | 1.72                       | 255.19        | 127.60        | 34.57            | 26.17            | 8.95               | -1.50          | 0.076 |
| 110.00        | -0.74            | -0.10            | 0.00            | -0.40           | 0.00            | 0.40                       | 255.19        | 127.60        | 34.57            | 26.17            | 10.59              | -1.61          | 0.018 |
| 114.00        | 0.00             | -0.08            | 0.00            | 0.00            | 0.00            | 0.00                       | 255.19        | 127.60        | 34.57            | 26.17            | 11.95              | -1.62          | 0.000 |

**Load Case:** 1.0D + 1.0W

Serviceability 60 mph

23 Iterations

Gust Response Factor : 1.10

Wind Importance Factor : 1.00

Dead Load Factor : 1.00

Wind Load Factor : 1.00

**Applied Segment Forces Summary**

| Seg<br>Elev<br>(ft) | Description     | Shaft Forces    |                      | Discrete Forces |                          |                         | Linear Forces        |                 | Sum of Forces        |                 |                      |                          |                      |
|---------------------|-----------------|-----------------|----------------------|-----------------|--------------------------|-------------------------|----------------------|-----------------|----------------------|-----------------|----------------------|--------------------------|----------------------|
|                     |                 | Wind FX<br>(lb) | Dead<br>Load<br>(lb) | Wind FX<br>(lb) | Torsion<br>MY<br>(lb-ft) | Moment<br>MZ<br>(lb-ft) | Dead<br>Load<br>(lb) | Wind FX<br>(lb) | Dead<br>Load<br>(lb) | Wind FX<br>(lb) | Dead<br>Load<br>(lb) | Torsion<br>MY<br>(lb-ft) | Moment<br>MZ<br>(lb) |
| 0.00                |                 | 55.4            | 0.0                  |                 |                          |                         |                      | 0.0             | 0.0                  | 55.4            | 0.0                  | 0.0                      | 0.0                  |
| 5.00                |                 | 109.9           | 545.3                |                 |                          |                         |                      | 0.0             | 101.6                | 109.9           | 646.9                | 0.0                      | 0.0                  |
| 10.00               |                 | 107.9           | 535.5                |                 |                          |                         |                      | 0.0             | 101.6                | 107.9           | 637.1                | 0.0                      | 0.0                  |
| 15.00               |                 | 107.9           | 525.8                |                 |                          |                         |                      | 0.0             | 101.6                | 107.9           | 627.4                | 0.0                      | 0.0                  |
| 20.00               |                 | 110.1           | 516.0                |                 |                          |                         |                      | 0.0             | 101.6                | 110.1           | 617.6                | 0.0                      | 0.0                  |
| 25.00               |                 | 112.2           | 506.3                |                 |                          |                         |                      | 0.0             | 101.6                | 112.2           | 607.9                | 0.0                      | 0.0                  |
| 30.00               |                 | 113.5           | 496.5                |                 |                          |                         |                      | 0.0             | 101.6                | 113.5           | 598.1                | 0.0                      | 0.0                  |
| 35.00               |                 | 114.2           | 486.8                |                 |                          |                         |                      | 0.0             | 101.6                | 114.2           | 588.4                | 0.0                      | 0.0                  |
| 40.00               |                 | 114.4           | 477.1                |                 |                          |                         |                      | 0.0             | 101.6                | 114.4           | 578.7                | 0.0                      | 0.0                  |
| 45.00               |                 | 89.7            | 467.3                |                 |                          |                         |                      | 0.0             | 101.6                | 89.7            | 568.9                | 0.0                      | 0.0                  |
| 47.84               | Bot - Section 2 | 57.4            | 261.3                |                 |                          |                         |                      | 0.0             | 57.8                 | 57.4            | 319.1                | 0.0                      | 0.0                  |
| 50.00               |                 | 55.5            | 345.3                |                 |                          |                         |                      | 0.0             | 43.8                 | 55.5            | 389.2                | 0.0                      | 0.0                  |
| 52.66               | Top - Section 1 | 57.5            | 421.0                |                 |                          |                         |                      | 0.0             | 54.0                 | 57.5            | 475.0                | 0.0                      | 0.0                  |
| 55.00               |                 | 84.1            | 158.5                |                 |                          |                         |                      | 0.0             | 47.6                 | 84.1            | 206.1                | 0.0                      | 0.0                  |
| 60.00               |                 | 113.9           | 333.0                |                 |                          |                         |                      | 0.0             | 101.6                | 113.9           | 434.6                | 0.0                      | 0.0                  |
| 65.00               |                 | 112.9           | 325.7                |                 |                          |                         |                      | 0.0             | 101.6                | 112.9           | 427.3                | 0.0                      | 0.0                  |
| 70.00               |                 | 111.8           | 318.4                |                 |                          |                         |                      | 0.0             | 101.6                | 111.8           | 420.0                | 0.0                      | 0.0                  |
| 75.00               |                 | 110.5           | 311.1                |                 |                          |                         |                      | 0.0             | 101.6                | 110.5           | 412.7                | 0.0                      | 0.0                  |
| 80.00               |                 | 71.3            | 303.8                |                 |                          |                         |                      | 0.0             | 101.6                | 71.3            | 405.4                | 0.0                      | 0.0                  |
| 81.50               | Appertunance(s) | 43.4            | 89.7                 | 36.0            | 0.0                      | 1.4                     | 50.0                 | 0.0             | 30.5                 | 79.4            | 170.2                | 0.0                      | 0.0                  |
| 84.00               | Top - Section 2 | 30.9            | 148.0                |                 |                          |                         |                      | 0.0             | 50.4                 | 30.9            | 198.4                | 0.0                      | 0.0                  |
| 85.00               |                 | 23.3            | 88.4                 |                 |                          |                         |                      | 8.1             | 37.1                 | 31.4            | 125.5                | 0.0                      | 0.0                  |
| 90.00               | Appertunance(s) | 35.1            | 441.8                | 0.0             | 0.0                      | 0.0                     | 120.0                | 40.9            | 185.5                | 76.0            | 747.4                | 0.0                      | 0.0                  |
| 94.00               | Top - Section 3 | 18.8            | 353.4                |                 |                          |                         |                      | 33.0            | 148.4                | 51.8            | 501.9                | 0.0                      | 0.0                  |
| 95.00               |                 | 18.6            | 54.1                 |                 |                          |                         |                      | 8.7             | 37.1                 | 27.3            | 91.2                 | 0.0                      | 0.0                  |
| 100.00              | Appertunance(s) | 28.0            | 270.6                | 0.0             | 0.0                      | 0.0                     | 527.4                | 43.9            | 185.5                | 71.8            | 983.5                | 0.0                      | 0.0                  |
| 104.00              | Top - Section 4 | 15.6            | 216.5                |                 |                          |                         |                      | 35.4            | 118.0                | 51.0            | 334.4                | 0.0                      | 0.0                  |
| 105.00              |                 | 18.9            | 27.6                 |                 |                          |                         |                      | 8.9             | 29.5                 | 27.8            | 57.1                 | 0.0                      | 0.0                  |
| 110.00              | Appertunance(s) | 28.4            | 137.8                | 0.0             | 0.0                      | 0.0                     | 280.7                | 44.6            | 147.4                | 73.1            | 566.0                | 0.0                      | 0.0                  |
| 114.00              |                 | 12.7            | 110.3                |                 |                          |                         |                      | 35.9            | 67.8                 | 48.6            | 178.1                | 0.0                      | 0.0                  |
| <b>Totals:</b>      |                 |                 |                      |                 |                          |                         |                      |                 |                      | 2,379.35        | 12,913.8             | 0.00                     | 0.00                 |

Site Number: 27741\_B

Code: ANSI/TIA-222-G

© 2007 - 2019 by ATC IP LLC. All rights reserved.

Site Name: Round Hill CT, Greenwich, CT

Engineering Number: REV01

9/16/2019 9:52:11 AM

Customer: KGI

**Load Case:** 1.0D + 1.0W

Serviceability 60 mph

23 Iterations

Gust Response Factor : 1.10

Wind Importance Factor : 1.00

Dead Load Factor : 1.00

Wind Load Factor : 1.00

**Calculated Forces**

| Seg Elev (ft) | Pu FY (-) (kips) | Vu FX (-) (kips) | Tu MY (ft-kips) | Mu MZ (ft-kips) | Mu MX (ft-kips) | Resultant Moment (ft-kips) | phi Pn (kips) | phi Vn (kips) | phi Tn (ft-kips) | phi Mn (ft-kips) | Total Deflect (in) | Rotation (deg) | Ratio |
|---------------|------------------|------------------|-----------------|-----------------|-----------------|----------------------------|---------------|---------------|------------------|------------------|--------------------|----------------|-------|
| 0.00          | -12.91           | -2.33            | 0.00            | -130.62         | 0.00            | 130.62                     | 2,009.33      | 1,004.66      | 3,370.24         | 1,687.62         | 0.00               | 0.00           | 0.084 |
| 5.00          | -12.27           | -2.22            | 0.00            | -118.99         | 0.00            | 118.99                     | 1,990.85      | 995.43        | 3,279.75         | 1,642.31         | 0.01               | -0.03          | 0.079 |
| 10.00         | -11.63           | -2.12            | 0.00            | -107.88         | 0.00            | 107.88                     | 1,971.76      | 985.88        | 3,189.37         | 1,597.06         | 0.06               | -0.05          | 0.073 |
| 15.00         | -11.00           | -2.01            | 0.00            | -97.28          | 0.00            | 97.28                      | 1,952.06      | 976.03        | 3,099.16         | 1,551.88         | 0.12               | -0.08          | 0.068 |
| 20.00         | -10.38           | -1.91            | 0.00            | -87.21          | 0.00            | 87.21                      | 1,931.73      | 965.87        | 3,009.15         | 1,506.81         | 0.21               | -0.10          | 0.063 |
| 25.00         | -9.77            | -1.80            | 0.00            | -77.67          | 0.00            | 77.67                      | 1,910.79      | 955.40        | 2,919.43         | 1,461.88         | 0.33               | -0.12          | 0.058 |
| 30.00         | -9.17            | -1.69            | 0.00            | -68.69          | 0.00            | 68.69                      | 1,889.23      | 944.62        | 2,830.03         | 1,417.12         | 0.46               | -0.14          | 0.053 |
| 35.00         | -8.59            | -1.57            | 0.00            | -60.26          | 0.00            | 60.26                      | 1,867.06      | 933.53        | 2,741.01         | 1,372.54         | 0.62               | -0.16          | 0.049 |
| 40.00         | -8.01            | -1.46            | 0.00            | -52.39          | 0.00            | 52.39                      | 1,844.27      | 922.13        | 2,652.43         | 1,328.19         | 0.80               | -0.18          | 0.044 |
| 45.00         | -7.44            | -1.37            | 0.00            | -45.10          | 0.00            | 45.10                      | 1,820.86      | 910.43        | 2,564.34         | 1,284.08         | 0.99               | -0.19          | 0.039 |
| 47.84         | -7.12            | -1.31            | 0.00            | -41.20          | 0.00            | 41.20                      | 1,807.27      | 903.64        | 2,514.51         | 1,259.12         | 1.11               | -0.20          | 0.037 |
| 50.00         | -6.73            | -1.26            | 0.00            | -38.37          | 0.00            | 38.37                      | 1,796.83      | 898.42        | 2,476.80         | 1,240.24         | 1.20               | -0.21          | 0.035 |
| 52.66         | -6.26            | -1.20            | 0.00            | -35.04          | 0.00            | 35.04                      | 1,181.92      | 590.96        | 1,634.85         | 818.64           | 1.32               | -0.21          | 0.048 |
| 55.00         | -6.05            | -1.11            | 0.00            | -32.23          | 0.00            | 32.23                      | 1,176.68      | 588.34        | 1,611.12         | 806.76           | 1.42               | -0.22          | 0.045 |
| 60.00         | -5.61            | -1.00            | 0.00            | -26.67          | 0.00            | 26.67                      | 1,165.04      | 582.52        | 1,560.37         | 781.35           | 1.66               | -0.24          | 0.039 |
| 65.00         | -5.19            | -0.89            | 0.00            | -21.67          | 0.00            | 21.67                      | 1,152.79      | 576.40        | 1,509.51         | 755.88           | 1.92               | -0.25          | 0.033 |
| 70.00         | -4.77            | -0.77            | 0.00            | -17.24          | 0.00            | 17.24                      | 1,139.92      | 569.96        | 1,458.59         | 730.38           | 2.19               | -0.26          | 0.028 |
| 75.00         | -4.36            | -0.66            | 0.00            | -13.38          | 0.00            | 13.38                      | 1,126.44      | 563.22        | 1,407.67         | 704.88           | 2.47               | -0.27          | 0.023 |
| 80.00         | -3.95            | -0.59            | 0.00            | -10.08          | 0.00            | 10.08                      | 1,112.33      | 556.17        | 1,356.80         | 679.41           | 2.75               | -0.28          | 0.018 |
| 81.50         | -3.78            | -0.51            | 0.00            | -9.19           | 0.00            | 9.19                       | 1,107.98      | 553.99        | 1,341.56         | 671.78           | 2.84               | -0.28          | 0.017 |
| 84.00         | -3.58            | -0.48            | 0.00            | -7.92           | 0.00            | 7.92                       | 1,100.61      | 550.30        | 1,316.18         | 659.07           | 2.99               | -0.28          | 0.015 |
| 84.00         | -3.58            | -0.48            | 0.00            | -7.92           | 0.00            | 7.92                       | 1,168.53      | 584.26        | 139.98           | 118.82           | 2.99               | -0.28          | 0.070 |
| 85.00         | -3.46            | -0.45            | 0.00            | -7.45           | 0.00            | 7.45                       | 1,168.53      | 584.26        | 139.98           | 118.82           | 3.05               | -0.28          | 0.066 |
| 90.00         | -2.71            | -0.37            | 0.00            | -5.20           | 0.00            | 5.20                       | 1,168.53      | 584.26        | 139.98           | 118.82           | 3.44               | -0.45          | 0.046 |
| 94.00         | -2.21            | -0.32            | 0.00            | -3.70           | 0.00            | 3.70                       | 1,168.53      | 584.26        | 139.98           | 118.82           | 3.86               | -0.55          | 0.033 |
| 94.00         | -2.21            | -0.32            | 0.00            | -3.70           | 0.00            | 3.70                       | 715.69        | 357.85        | 67.10            | 56.95            | 3.86               | -0.55          | 0.068 |
| 95.00         | -2.12            | -0.30            | 0.00            | -3.38           | 0.00            | 3.38                       | 715.69        | 357.85        | 67.10            | 56.95            | 3.98               | -0.57          | 0.062 |
| 100.00        | -1.13            | -0.22            | 0.00            | -1.90           | 0.00            | 1.90                       | 715.69        | 357.85        | 67.10            | 56.95            | 4.68               | -0.75          | 0.035 |
| 104.00        | -0.80            | -0.16            | 0.00            | -1.03           | 0.00            | 1.03                       | 715.69        | 357.85        | 67.10            | 56.95            | 5.34               | -0.83          | 0.019 |
| 104.00        | -0.80            | -0.16            | 0.00            | -1.03           | 0.00            | 1.03                       | 255.19        | 127.60        | 34.57            | 26.17            | 5.34               | -0.83          | 0.043 |
| 105.00        | -0.74            | -0.13            | 0.00            | -0.87           | 0.00            | 0.87                       | 255.19        | 127.60        | 34.57            | 26.17            | 5.52               | -0.85          | 0.036 |
| 110.00        | -0.18            | -0.05            | 0.00            | -0.21           | 0.00            | 0.21                       | 255.19        | 127.60        | 34.57            | 26.17            | 6.44               | -0.90          | 0.009 |
| 114.00        | 0.00             | -0.05            | 0.00            | 0.00            | 0.00            | 0.00                       | 255.19        | 127.60        | 34.57            | 26.17            | 7.20               | -0.91          | 0.000 |



**Equivalent Lateral Forces Method Analysis**

(Based on ASCE7-10 Chapters 11, 12, 15)

|  |         |
|--|---------|
| Spectral Response Acceleration for Short Period ( $S_s$ ):               | 0.26    |
| Spectral Response Acceleration at 1.0 Second Period ( $S_1$ ):           | 0.07    |
| Long-Period Transition Period ( $T_L$ ):                                 | 6       |
| Importance Factor ( $I_E$ ):   | 1.00    |
| Site Coefficient $F_a$ :   | 1.59    |
| Site Coefficient $F_v$ :   | 2.40    |
| Response Modification Coefficient (R):                                   | 1.50    |
| Design Spectral Response Acceleration at Short Period ( $S_{ds}$ ):      | 0.28    |
| Design Spectral Response Acceleration at 1.0 Second Period ( $S_{d1}$ ): | 0.11    |
| Seismic Response Coefficient ( $C_s$ ):                                  | 0.05    |
| Upper Limit $C_s$  | 0.05    |
| Lower Limit $C_s$  | 0.03    |
| Period based on Rayleigh Method (sec):                                   | 1.53    |
| Redundancy Factor (p):   | 1.30    |
| Seismic Force Distribution Exponent (k):                                 | 1.51    |
| Total Unfactored Dead Load:  | 12.91 k |
| Seismic Base Shear (E):  | 0.83 k  |

### Equivalent Modal Forces Analysis

(Based on ASCE7-10 Chapters 11, 12 & 15 and ANSI/TIA-G, section 2.7)

|  |      |
|--|------|
| Spectral Response Acceleration for Short Period ( $S_s$ ):               | 0.26 |
| Spectral Response Acceleration at 1.0 Second Period ( $S_1$ ):           | 0.07 |
| Importance Factor ( $I_E$ ):   | 1.00 |
| Site Coefficient $F_a$ :   | 1.59 |
| Site Coefficient $F_v$ :   | 2.40 |
| Response Modification Coefficient (R):                                   | 1.50 |
| Design Spectral Response Acceleration at Short Period ( $S_{ds}$ ):      | 0.28 |
| Design Spectral Response Acceleration at 1.0 Second Period ( $S_{d1}$ ): | 0.11 |
| Period Based on Rayleigh Method (sec):                                   | 1.53 |
| Redundancy Factor ( $\rho$ ):  | 1.30 |

**Load Case (1.2 + 0.2Sds) \* DL + E EFLM**

**Seismic Equivalent Lateral Forces Method**

| Segment         | Height<br>Above<br>Base<br>(ft) | Weight<br>(lb) | a     | b      | c     | Saz    | Horizontal<br>Force<br>(lb) | Vertical<br>Force<br>(lb) |
|-----------------|---------------------------------|----------------|-------|--------|-------|--------|-----------------------------|---------------------------|
| 29              | 112.00                          | 178            | 1.824 | 1.651  | 1.020 | 0.470  | 72                          | 150                       |
| 28              | 107.50                          | 285            | 1.681 | 1.050  | 0.785 | 0.348  | 86                          | 241                       |
| 27              | 104.50                          | 57             | 1.588 | 0.742  | 0.654 | 0.277  | 14                          | 48                        |
| 26              | 102.00                          | 334            | 1.513 | 0.534  | 0.558 | 0.223  | 65                          | 283                       |
| 25              | 97.50                           | 456            | 1.382 | 0.252  | 0.414 | 0.139  | 55                          | 385                       |
| 24              | 94.50                           | 91             | 1.299 | 0.119  | 0.335 | 0.092  | 7                           | 77                        |
| 23              | 92.00                           | 502            | 1.231 | 0.036  | 0.278 | 0.058  | 25                          | 424                       |
| 22              | 87.50                           | 627            | 1.113 | -0.062 | 0.195 | 0.010  | 6                           | 530                       |
| 21              | 84.50                           | 125            | 1.038 | -0.098 | 0.151 | -0.013 | -1                          | 106                       |
| 20              | 82.75                           | 198            | 0.996 | -0.111 | 0.129 | -0.023 | -4                          | 168                       |
| 19              | 80.75                           | 120            | 0.948 | -0.119 | 0.107 | -0.032 | -3                          | 102                       |
| 18              | 77.50                           | 405            | 0.873 | -0.121 | 0.077 | -0.040 | -14                         | 343                       |
| 17              | 72.50                           | 413            | 0.764 | -0.104 | 0.044 | -0.039 | -14                         | 349                       |
| 16              | 67.50                           | 420            | 0.663 | -0.075 | 0.023 | -0.023 | -9                          | 355                       |
| 15              | 62.50                           | 427            | 0.568 | -0.041 | 0.011 | 0.000  | 0                           | 361                       |
| 14              | 57.50                           | 435            | 0.481 | -0.009 | 0.006 | 0.025  | 10                          | 367                       |
| 13              | 53.83                           | 206            | 0.421 | 0.011  | 0.006 | 0.041  | 7                           | 174                       |
| 12              | 51.33                           | 475            | 0.383 | 0.023  | 0.007 | 0.050  | 21                          | 401                       |
| 11              | 48.92                           | 389            | 0.348 | 0.033  | 0.009 | 0.056  | 19                          | 329                       |
| 10              | 46.42                           | 319            | 0.313 | 0.042  | 0.011 | 0.062  | 17                          | 270                       |
| 9               | 42.50                           | 569            | 0.263 | 0.053  | 0.016 | 0.067  | 33                          | 481                       |
| 8               | 37.50                           | 579            | 0.205 | 0.062  | 0.023 | 0.069  | 34                          | 489                       |
| 7               | 32.50                           | 588            | 0.154 | 0.068  | 0.030 | 0.068  | 34                          | 497                       |
| 6               | 27.50                           | 598            | 0.110 | 0.071  | 0.036 | 0.065  | 34                          | 505                       |
| 5               | 22.50                           | 608            | 0.074 | 0.072  | 0.040 | 0.063  | 33                          | 514                       |
| 4               | 17.50                           | 618            | 0.045 | 0.071  | 0.042 | 0.060  | 32                          | 522                       |
| 3               | 12.50                           | 627            | 0.023 | 0.065  | 0.039 | 0.055  | 30                          | 530                       |
| 2               | 7.50                            | 637            | 0.008 | 0.052  | 0.030 | 0.045  | 25                          | 538                       |
| 1               | 2.50                            | 647            | 0.001 | 0.023  | 0.013 | 0.022  | 12                          | 547                       |
| Flush Mount     | 110.00                          | 120            | 1.760 | 1.362  | 0.909 | 0.414  | 43                          | 101                       |
| DBXNH-6565A-A2M | 110.00                          | 103            | 1.760 | 1.362  | 0.909 | 0.414  | 37                          | 87                        |
| TMAT1921XB6811A | 110.00                          | 53             | 1.760 | 1.362  | 0.909 | 0.414  | 19                          | 45                        |
| 782 11066       | 110.00                          | 5              | 1.760 | 1.362  | 0.909 | 0.414  | 2                           | 4                         |
| Flush Mount     | 100.00                          | 120            | 1.454 | 0.395  | 0.490 | 0.184  | 19                          | 101                       |

Site Number: 27741\_B

Code: ANSI/TIA-222-G

© 2007 - 2019 by ATC IP LLC. All rights reserved.

Site Name: Round Hill CT, Greenwich, CT

Engineering Number: REV01

9/16/2019 9:52:11 AM

Customer: KGI

|                    |        |        |        |        |        |        |     |        |
|--------------------|--------|--------|--------|--------|--------|--------|-----|--------|
| APXSPP18-C-A20     | 100.00 | 171    | 1.454  | 0.395  | 0.490  | 0.184  | 27  | 144    |
| KIT-FD9R6004/1C-DL | 100.00 | 38     | 1.454  | 0.395  | 0.490  | 0.184  | 6   | 32     |
| IBC1900HG-SA       | 100.00 | 198    | 1.454  | 0.395  | 0.490  | 0.184  | 32  | 167    |
| Flush Mount        | 90.00  | 120    | 1.178  | -0.015 | 0.239  | 0.035  | 4   | 101    |
| 3 ft Standoff      | 81.50  | 40     | 0.966  | -0.117 | 0.115  | -0.029 | -1  | 34     |
| GPS                | 81.50  | 10     | 0.966  | -0.117 | 0.115  | -0.029 | 0   | 8      |
|                    |        | 12,914 | 36.276 | 11.065 | 11.157 | 4.560  | 813 | 10,912 |

**Load Case (1.2 + 0.2Sds) \* DL + E EMAM**

**Seismic Equivalent Modal Analysis Method**

| Segment            | Height Above Base (ft) | Weight (lb) | a      | b      | c      | Saz    | Horizontal Force (lb) | Vertical Force (lb) |
|--------------------|------------------------|-------------|--------|--------|--------|--------|-----------------------|---------------------|
| 29                 | 112.00                 | 178         | 1.824  | 1.651  | 1.020  | 0.470  | 72                    | 150                 |
| 28                 | 107.50                 | 285         | 1.681  | 1.050  | 0.785  | 0.348  | 86                    | 241                 |
| 27                 | 104.50                 | 57          | 1.588  | 0.742  | 0.654  | 0.277  | 14                    | 48                  |
| 26                 | 102.00                 | 334         | 1.513  | 0.534  | 0.558  | 0.223  | 65                    | 283                 |
| 25                 | 97.50                  | 456         | 1.382  | 0.252  | 0.414  | 0.139  | 55                    | 385                 |
| 24                 | 94.50                  | 91          | 1.299  | 0.119  | 0.335  | 0.092  | 7                     | 77                  |
| 23                 | 92.00                  | 502         | 1.231  | 0.036  | 0.278  | 0.058  | 25                    | 424                 |
| 22                 | 87.50                  | 627         | 1.113  | -0.062 | 0.195  | 0.010  | 6                     | 530                 |
| 21                 | 84.50                  | 125         | 1.038  | -0.098 | 0.151  | -0.013 | -1                    | 106                 |
| 20                 | 82.75                  | 198         | 0.996  | -0.111 | 0.129  | -0.023 | -4                    | 168                 |
| 19                 | 80.75                  | 120         | 0.948  | -0.119 | 0.107  | -0.032 | -3                    | 102                 |
| 18                 | 77.50                  | 405         | 0.873  | -0.121 | 0.077  | -0.040 | -14                   | 343                 |
| 17                 | 72.50                  | 413         | 0.764  | -0.104 | 0.044  | -0.039 | -14                   | 349                 |
| 16                 | 67.50                  | 420         | 0.663  | -0.075 | 0.023  | -0.023 | -9                    | 355                 |
| 15                 | 62.50                  | 427         | 0.568  | -0.041 | 0.011  | 0.000  | 0                     | 361                 |
| 14                 | 57.50                  | 435         | 0.481  | -0.009 | 0.006  | 0.025  | 10                    | 367                 |
| 13                 | 53.83                  | 206         | 0.421  | 0.011  | 0.006  | 0.041  | 7                     | 174                 |
| 12                 | 51.33                  | 475         | 0.383  | 0.023  | 0.007  | 0.050  | 21                    | 401                 |
| 11                 | 48.92                  | 389         | 0.348  | 0.033  | 0.009  | 0.056  | 19                    | 329                 |
| 10                 | 46.42                  | 319         | 0.313  | 0.042  | 0.011  | 0.062  | 17                    | 270                 |
| 9                  | 42.50                  | 569         | 0.263  | 0.053  | 0.016  | 0.067  | 33                    | 481                 |
| 8                  | 37.50                  | 579         | 0.205  | 0.062  | 0.023  | 0.069  | 34                    | 489                 |
| 7                  | 32.50                  | 588         | 0.154  | 0.068  | 0.030  | 0.068  | 34                    | 497                 |
| 6                  | 27.50                  | 598         | 0.110  | 0.071  | 0.036  | 0.065  | 34                    | 505                 |
| 5                  | 22.50                  | 608         | 0.074  | 0.072  | 0.040  | 0.063  | 33                    | 514                 |
| 4                  | 17.50                  | 618         | 0.045  | 0.071  | 0.042  | 0.060  | 32                    | 522                 |
| 3                  | 12.50                  | 627         | 0.023  | 0.065  | 0.039  | 0.055  | 30                    | 530                 |
| 2                  | 7.50                   | 637         | 0.008  | 0.052  | 0.030  | 0.045  | 25                    | 538                 |
| 1                  | 2.50                   | 647         | 0.001  | 0.023  | 0.013  | 0.022  | 12                    | 547                 |
| Flush Mount        | 110.00                 | 120         | 1.760  | 1.362  | 0.909  | 0.414  | 43                    | 101                 |
| DBXNH-6565A-A2M    | 110.00                 | 103         | 1.760  | 1.362  | 0.909  | 0.414  | 37                    | 87                  |
| TMAT1921XB6811A    | 110.00                 | 53          | 1.760  | 1.362  | 0.909  | 0.414  | 19                    | 45                  |
| 782 11066          | 110.00                 | 5           | 1.760  | 1.362  | 0.909  | 0.414  | 2                     | 4                   |
| Flush Mount        | 100.00                 | 120         | 1.454  | 0.395  | 0.490  | 0.184  | 19                    | 101                 |
| APXSPP18-C-A20     | 100.00                 | 171         | 1.454  | 0.395  | 0.490  | 0.184  | 27                    | 144                 |
| KIT-FD9R6004/1C-DL | 100.00                 | 38          | 1.454  | 0.395  | 0.490  | 0.184  | 6                     | 32                  |
| IBC1900HG-SA       | 100.00                 | 198         | 1.454  | 0.395  | 0.490  | 0.184  | 32                    | 167                 |
| Flush Mount        | 90.00                  | 120         | 1.178  | -0.015 | 0.239  | 0.035  | 4                     | 101                 |
| 3 ft Standoff      | 81.50                  | 40          | 0.966  | -0.117 | 0.115  | -0.029 | -1                    | 34                  |
| GPS                | 81.50                  | 10          | 0.966  | -0.117 | 0.115  | -0.029 | 0                     | 8                   |
|                    |                        | 12,914      | 36.276 | 11.065 | 11.157 | 4.560  | 813                   | 10,912              |

**Load Case (0.9 - 0.2Sds) \* DL + E ELFM**

**Seismic (Reduced DL) Equivalent Lateral Forces Method**

| Segment            | Height Above Base (ft) | Weight (lb) | a      | b      | c      | Saz    | Horizontal Force (lb) | Vertical Force (lb) |
|--------------------|------------------------|-------------|--------|--------|--------|--------|-----------------------|---------------------|
| 29                 | 112.00                 | 178         | 1.824  | 1.651  | 1.020  | 0.470  | 72                    | 150                 |
| 28                 | 107.50                 | 285         | 1.681  | 1.050  | 0.785  | 0.348  | 86                    | 241                 |
| 27                 | 104.50                 | 57          | 1.588  | 0.742  | 0.654  | 0.277  | 14                    | 48                  |
| 26                 | 102.00                 | 334         | 1.513  | 0.534  | 0.558  | 0.223  | 65                    | 283                 |
| 25                 | 97.50                  | 456         | 1.382  | 0.252  | 0.414  | 0.139  | 55                    | 385                 |
| 24                 | 94.50                  | 91          | 1.299  | 0.119  | 0.335  | 0.092  | 7                     | 77                  |
| 23                 | 92.00                  | 502         | 1.231  | 0.036  | 0.278  | 0.058  | 25                    | 424                 |
| 22                 | 87.50                  | 627         | 1.113  | -0.062 | 0.195  | 0.010  | 6                     | 530                 |
| 21                 | 84.50                  | 125         | 1.038  | -0.098 | 0.151  | -0.013 | -1                    | 106                 |
| 20                 | 82.75                  | 198         | 0.996  | -0.111 | 0.129  | -0.023 | -4                    | 168                 |
| 19                 | 80.75                  | 120         | 0.948  | -0.119 | 0.107  | -0.032 | -3                    | 102                 |
| 18                 | 77.50                  | 405         | 0.873  | -0.121 | 0.077  | -0.040 | -14                   | 343                 |
| 17                 | 72.50                  | 413         | 0.764  | -0.104 | 0.044  | -0.039 | -14                   | 349                 |
| 16                 | 67.50                  | 420         | 0.663  | -0.075 | 0.023  | -0.023 | -9                    | 355                 |
| 15                 | 62.50                  | 427         | 0.568  | -0.041 | 0.011  | 0.000  | 0                     | 361                 |
| 14                 | 57.50                  | 435         | 0.481  | -0.009 | 0.006  | 0.025  | 10                    | 367                 |
| 13                 | 53.83                  | 206         | 0.421  | 0.011  | 0.006  | 0.041  | 7                     | 174                 |
| 12                 | 51.33                  | 475         | 0.383  | 0.023  | 0.007  | 0.050  | 21                    | 401                 |
| 11                 | 48.92                  | 389         | 0.348  | 0.033  | 0.009  | 0.056  | 19                    | 329                 |
| 10                 | 46.42                  | 319         | 0.313  | 0.042  | 0.011  | 0.062  | 17                    | 270                 |
| 9                  | 42.50                  | 569         | 0.263  | 0.053  | 0.016  | 0.067  | 33                    | 481                 |
| 8                  | 37.50                  | 579         | 0.205  | 0.062  | 0.023  | 0.069  | 34                    | 489                 |
| 7                  | 32.50                  | 588         | 0.154  | 0.068  | 0.030  | 0.068  | 34                    | 497                 |
| 6                  | 27.50                  | 598         | 0.110  | 0.071  | 0.036  | 0.065  | 34                    | 505                 |
| 5                  | 22.50                  | 608         | 0.074  | 0.072  | 0.040  | 0.063  | 33                    | 514                 |
| 4                  | 17.50                  | 618         | 0.045  | 0.071  | 0.042  | 0.060  | 32                    | 522                 |
| 3                  | 12.50                  | 627         | 0.023  | 0.065  | 0.039  | 0.055  | 30                    | 530                 |
| 2                  | 7.50                   | 637         | 0.008  | 0.052  | 0.030  | 0.045  | 25                    | 538                 |
| 1                  | 2.50                   | 647         | 0.001  | 0.023  | 0.013  | 0.022  | 12                    | 547                 |
| Flush Mount        | 110.00                 | 120         | 1.760  | 1.362  | 0.909  | 0.414  | 43                    | 101                 |
| DBXNH-6565A-A2M    | 110.00                 | 103         | 1.760  | 1.362  | 0.909  | 0.414  | 37                    | 87                  |
| TMAT1921XB6811A    | 110.00                 | 53          | 1.760  | 1.362  | 0.909  | 0.414  | 19                    | 45                  |
| 782 11066          | 110.00                 | 5           | 1.760  | 1.362  | 0.909  | 0.414  | 2                     | 4                   |
| Flush Mount        | 100.00                 | 120         | 1.454  | 0.395  | 0.490  | 0.184  | 19                    | 101                 |
| APXVSP18-C-A20     | 100.00                 | 171         | 1.454  | 0.395  | 0.490  | 0.184  | 27                    | 144                 |
| KIT-FD9R6004/1C-DL | 100.00                 | 38          | 1.454  | 0.395  | 0.490  | 0.184  | 6                     | 32                  |
| IBC1900HG-SA       | 100.00                 | 198         | 1.454  | 0.395  | 0.490  | 0.184  | 32                    | 167                 |
| Flush Mount        | 90.00                  | 120         | 1.178  | -0.015 | 0.239  | 0.035  | 4                     | 101                 |
| 3 ft Standoff      | 81.50                  | 40          | 0.966  | -0.117 | 0.115  | -0.029 | -1                    | 34                  |
| GPS                | 81.50                  | 10          | 0.966  | -0.117 | 0.115  | -0.029 | 0                     | 8                   |
|                    |                        | 12,914      | 36.276 | 11.065 | 11.157 | 4.560  | 813                   | 10,912              |

**Load Case (0.9 - 0.2Sds) \* DL + E EMAM**

**Seismic (Reduced DL) Equivalent Modal Analysis Method**

| Segment | Height Above Base (ft) | Weight (lb) | a     | b     | c     | Saz   | Horizontal Force (lb) | Vertical Force (lb) |
|---------|------------------------|-------------|-------|-------|-------|-------|-----------------------|---------------------|
| 29      | 112.00                 | 178         | 1.824 | 1.651 | 1.020 | 0.470 | 72                    | 150                 |
| 28      | 107.50                 | 285         | 1.681 | 1.050 | 0.785 | 0.348 | 86                    | 241                 |
| 27      | 104.50                 | 57          | 1.588 | 0.742 | 0.654 | 0.277 | 14                    | 48                  |
| 26      | 102.00                 | 334         | 1.513 | 0.534 | 0.558 | 0.223 | 65                    | 283                 |
| 25      | 97.50                  | 456         | 1.382 | 0.252 | 0.414 | 0.139 | 55                    | 385                 |



Site Number: 27741\_B

Code: ANSI/TIA-222-G

© 2007 - 2019 by ATC IP LLC. All rights reserved.

Site Name: Round Hill CT, Greenwich, CT

Engineering Number: REV01

9/16/2019 9:52:11 AM

Customer: KGI

|                    |        |        |        |        |        |        |     |        |
|--------------------|--------|--------|--------|--------|--------|--------|-----|--------|
| 24                 | 94.50  | 91     | 1.299  | 0.119  | 0.335  | 0.092  | 7   | 77     |
| 23                 | 92.00  | 502    | 1.231  | 0.036  | 0.278  | 0.058  | 25  | 424    |
| 22                 | 87.50  | 627    | 1.113  | -0.062 | 0.195  | 0.010  | 6   | 530    |
| 21                 | 84.50  | 125    | 1.038  | -0.098 | 0.151  | -0.013 | -1  | 106    |
| 20                 | 82.75  | 198    | 0.996  | -0.111 | 0.129  | -0.023 | -4  | 168    |
| 19                 | 80.75  | 120    | 0.948  | -0.119 | 0.107  | -0.032 | -3  | 102    |
| 18                 | 77.50  | 405    | 0.873  | -0.121 | 0.077  | -0.040 | -14 | 343    |
| 17                 | 72.50  | 413    | 0.764  | -0.104 | 0.044  | -0.039 | -14 | 349    |
| 16                 | 67.50  | 420    | 0.663  | -0.075 | 0.023  | -0.023 | -9  | 355    |
| 15                 | 62.50  | 427    | 0.568  | -0.041 | 0.011  | 0.000  | 0   | 361    |
| 14                 | 57.50  | 435    | 0.481  | -0.009 | 0.006  | 0.025  | 10  | 367    |
| 13                 | 53.83  | 206    | 0.421  | 0.011  | 0.006  | 0.041  | 7   | 174    |
| 12                 | 51.33  | 475    | 0.383  | 0.023  | 0.007  | 0.050  | 21  | 401    |
| 11                 | 48.92  | 389    | 0.348  | 0.033  | 0.009  | 0.056  | 19  | 329    |
| 10                 | 46.42  | 319    | 0.313  | 0.042  | 0.011  | 0.062  | 17  | 270    |
| 9                  | 42.50  | 569    | 0.263  | 0.053  | 0.016  | 0.067  | 33  | 481    |
| 8                  | 37.50  | 579    | 0.205  | 0.062  | 0.023  | 0.069  | 34  | 489    |
| 7                  | 32.50  | 588    | 0.154  | 0.068  | 0.030  | 0.068  | 34  | 497    |
| 6                  | 27.50  | 598    | 0.110  | 0.071  | 0.036  | 0.065  | 34  | 505    |
| 5                  | 22.50  | 608    | 0.074  | 0.072  | 0.040  | 0.063  | 33  | 514    |
| 4                  | 17.50  | 618    | 0.045  | 0.071  | 0.042  | 0.060  | 32  | 522    |
| 3                  | 12.50  | 627    | 0.023  | 0.065  | 0.039  | 0.055  | 30  | 530    |
| 2                  | 7.50   | 637    | 0.008  | 0.052  | 0.030  | 0.045  | 25  | 538    |
| 1                  | 2.50   | 647    | 0.001  | 0.023  | 0.013  | 0.022  | 12  | 547    |
| Flush Mount        | 110.00 | 120    | 1.760  | 1.362  | 0.909  | 0.414  | 43  | 101    |
| DBXNH-6565A-A2M    | 110.00 | 103    | 1.760  | 1.362  | 0.909  | 0.414  | 37  | 87     |
| TMAT1921XB6811A    | 110.00 | 53     | 1.760  | 1.362  | 0.909  | 0.414  | 19  | 45     |
| 782 11066          | 110.00 | 5      | 1.760  | 1.362  | 0.909  | 0.414  | 2   | 4      |
| Flush Mount        | 100.00 | 120    | 1.454  | 0.395  | 0.490  | 0.184  | 19  | 101    |
| APXVSP18-C-A20     | 100.00 | 171    | 1.454  | 0.395  | 0.490  | 0.184  | 27  | 144    |
| KIT-FD9R6004/1C-DL | 100.00 | 38     | 1.454  | 0.395  | 0.490  | 0.184  | 6   | 32     |
| IBC1900HG-SA       | 100.00 | 198    | 1.454  | 0.395  | 0.490  | 0.184  | 32  | 167    |
| Flush Mount        | 90.00  | 120    | 1.178  | -0.015 | 0.239  | 0.035  | 4   | 101    |
| 3 ft Standoff      | 81.50  | 40     | 0.966  | -0.117 | 0.115  | -0.029 | -1  | 34     |
| GPS                | 81.50  | 10     | 0.966  | -0.117 | 0.115  | -0.029 | 0   | 8      |
|                    |        | 12,914 | 36.276 | 11.065 | 11.157 | 4.560  | 813 | 10,912 |

Site Number: 27741\_B

Code: ANSI/TIA-222-G

© 2007 - 2019 by ATC IP LLC. All rights reserved.

Site Name: Round Hill CT, Greenwich, CT

Engineering Number: REV01

9/16/2019 9:52:11 AM

Customer: KGI

### Analysis Summary

| Load Case                    | Reactions             |                       |                       |                           |                           |                           | Max Usage    |                      |
|------------------------------|-----------------------|-----------------------|-----------------------|---------------------------|---------------------------|---------------------------|--------------|----------------------|
|                              | Shear<br>FX<br>(kips) | Shear<br>FZ<br>(kips) | Axial<br>FY<br>(kips) | Moment<br>MX<br>(ft-kips) | Moment<br>MY<br>(ft-kips) | Moment<br>MZ<br>(ft-kips) | Elev<br>(ft) | Interaction<br>Ratio |
| 1.2D + 1.6W                  | 8.95                  | 0.00                  | 15.49                 | 0.00                      | 0.00                      | 503.96                    | 0.00         | 0.31                 |
| 0.9D + 1.6W                  | 8.94                  | 0.00                  | 11.61                 | 0.00                      | 0.00                      | 501.34                    | 0.00         | 0.30                 |
| 1.2D + 1.0Di + 1.0Wi         | 3.32                  | 0.00                  | 27.00                 | 0.00                      | 0.00                      | 196.12                    | 94.00        | 0.13                 |
| (1.2 + 0.2Sds) * DL + E ELFM | 0.83                  | 0.00                  | 15.40                 | 0.00                      | 0.00                      | 67.58                     | 84.00        | 0.06                 |
| (1.2 + 0.2Sds) * DL + E EMAM | 0.80                  | 0.00                  | 15.40                 | 0.00                      | 0.00                      | 61.07                     | 94.00        | 0.09                 |
| (0.9 - 0.2Sds) * DL + E ELFM | 0.83                  | 0.00                  | 10.37                 | 0.00                      | 0.00                      | 67.07                     | 84.00        | 0.06                 |
| (0.9 - 0.2Sds) * DL + E EMAM | 0.80                  | 0.00                  | 10.37                 | 0.00                      | 0.00                      | 60.55                     | 94.00        | 0.09                 |
| 1.0D + 1.0W                  | 2.33                  | 0.00                  | 12.91                 | 0.00                      | 0.00                      | 130.62                    | 0.00         | 0.08                 |

Site Number: **27441\_B**  
 Site Name: **Round Hill CT**  
 Job Number: **REV01**  
 Engineer: **JHH**  
 Date: **9/16/2019**

**Base Plate and Bolt Analysis**

Reinforcement: **N**  
 Moment: **504.0 k-ft**  
 Shear/Leg: **9.0 k**  
 Compression/Leg: **15.5 k**

TIA-222 Code Revision (F/G): **G**  
 Anchor Bolt Arrangement: **Corners**  
 Monopole Shaft Diameter (Across Flats): **41.0 in**  
 Lower Monopole Thickness: **0.250 in**  
 # of Sides of Pole: **18**  
 Monopole Shaft Yield Strength: **65 ksi**  
 Baseplate Diameter / Length: **47.50**  
 Base Plate Thickness: **2.00 in**  
 Base Plate Yield Strength: **60 ksi**  
 Baseplate Detail Type: **D**  
 Include Plate Thickness Beyond Bolt Circle: **Y**  
 Stress Increase: **1.00**  
 Fillet Weld Size: **0.375 in**  
 Weld Type (CJP or F/F): **CJP**  
 Weld Strength: **70 ksi**

**Anchor Bolts**  
 Anchor Bolt Yield Strength: **75 ksi**  
 Anchor Bolt Ultimate Strength: **100 ksi**  
 Anchor Bolt Diameter: **2.25 in**  
 Anchor Bolt Circle: **49.00 in**  
 # of Anchor Bolts: **4**  
 Minimum Anchor Bolt Separation: **6.00 in**  
 Additional Anchor Bolts Installed: **N**

| Failure Mode: | Effective Width (in) | Baseplate Flexural Capacity |                        |                 |       | Baseplate Shear Capacity |                         |              |       |
|---------------|----------------------|-----------------------------|------------------------|-----------------|-------|--------------------------|-------------------------|--------------|-------|
|               |                      | Moment (k-in)               | S/Z (in <sup>3</sup> ) | Capacity (k-in) | Usage | Shear (k)                | Area (in <sup>2</sup> ) | Capacity (k) | Usage |
| AA            | 29.84                | 468.5                       | 29.8                   | 1611.4          | 0.29  | 127.2                    | 59.7                    | 1933.7       | 0.07  |
| AB            | 29.84                | 461.4                       | 29.8                   | 1611.4          | 0.29  | 127.2                    | 59.7                    | 1933.7       | 0.07  |
| BA            | 30.83                | 508.7                       | 30.8                   | 1665.0          | 0.31  | 127.2                    | 61.7                    | 1998.0       | 0.06  |
| BB            | 30.83                | 508.7                       | 30.8                   | 1665.0          | 0.31  | 127.2                    | 61.7                    | 1998.0       | 0.06  |

**Anchor Bolt Capacity**

Area of Bolt: **3.25 in<sup>2</sup>**  
 Inertia of Bolt: **0.84 in<sup>4</sup>**  
 Total Bolt Inertia: **3902.2 in<sup>4</sup>**  
 Maximum Bolt Tension: **119.4 k**  
 Maximum Bolt Compression: **127.2 k**  
 Bolt Shear: **2.2 k**  
 Tensile Bolt Capacity: **259.8 k**  
 Compressive Bolt Capacity: **259.8 k**  
 Shear Bolt Capacity: **140.3 k**  
 Interaction Equation: **0.51 Result: OK**

**Base Weld Capacity**

Force / Weld: **3.6 k/in**  
 Weld Capacity: **23.8 k/in**  
 Interaction Equation: **0.15 Result: OK**  
 SES Base Plate Design Moment: **508.7 k-in**  
 Design Stress: **15.8 ksi**  
 SES Base Plate Allowable Stress / Moment Capacity: **1738.9 ksi / k-in**  
 Usage: **0.29**  
 Moment Factor: **1.00**  
 Length Factor: **0.96**

|              |                  |
|--------------|------------------|
| Site Number: | <b>SE60XC302</b> |
| Site Name:   | <b>Splinter</b>  |
| Job Number:  | <b>REV01</b>     |
| Engineer:    | <b>AHB</b>       |
| Date:        | <b>9/16/2019</b> |

**Flange @ 84'**

|                  |                  |
|------------------|------------------|
| Reinforcement:   | <b>N</b>         |
| Moment:          | <b>30.9 k-ft</b> |
| Shear/Leg:       | <b>1.9 k</b>     |
| Compression/Leg: | <b>4.3 k</b>     |

|   |              |
|---|--------------|
| TIA-222 Code Revision (F/G):                | <b>G</b>     |
| Anchor Bolt Arrangement:                    | <b>Round</b> |
| Monopole Shaft Diameter:                    | <b>in</b>    |
| Lower Monopole Thickness:                   | <b>in</b>    |
| Monopole Shaft Yield Strength:              | <b>ksi</b>   |
| Baseplate Diameter / Length:                | <b>in</b>    |
| Base Plate Thickness:                       | <b>in</b>    |
| Base Plate Yield Strength:                  | <b>ksi</b>   |
| Fillet Weld Size:                           | <b>in</b>    |
| Weld Type (CJP or F/F):                     | <b>ksi</b>   |
| Weld Strength:                              | <b>ksi</b>   |
| Baseplate Detail Type:                      | <b>C</b>     |
| Include Plate Thickness Beyond Bolt Circle: | <b>Y</b>     |
| Stress Increase:                            | <b>1.00</b>  |
| Additional Anchor Bolts Installed:          | <b>N</b>     |

Anchor Bolts

|                                    |                 |
|------------------------------------|-----------------|
| Anchor Bolt Yield Strength:        | <b>92 ksi</b>   |
| Anchor Bolt Ultimate Strength:     | <b>120 ksi</b>  |
| Anchor Bolt Diameter:              | <b>1.00 in</b>  |
| Anchor Bolt Circle:                | <b>26.00 in</b> |
| # of Anchor Bolts:                 | <b>12</b>       |
| Minimum Anchor Bolt Separation:    | <b>6.00 in</b>  |
| Additional Anchor Bolts Installed: | <b>N</b>        |

Anchor Bolt Capacity

|                            |                             |
|----------------------------|-----------------------------|
| Area of Bolt:              | <b>0.61 in<sup>2</sup></b>  |
| Inertia of Bolt:           | <b>0.03 in<sup>4</sup></b>  |
| Total Bolt Inertia:        | <b>614.6 in<sup>4</sup></b> |
| Maximum Bolt Tension:      | <b>4.4 k</b>                |
| Maximum Bolt Compression:  | <b>5.1 k</b>                |
| Bolt Shear:                | <b>0.2 k</b>                |
| Tensile Bolt Capacity:     | <b>58.2 k</b>               |
| Compressive Bolt Capacity: | <b>58.2 k</b>               |
| Shear Bolt Capacity:       | <b>26.2 k</b>               |
| Interaction Equation:      | <b>0.09 Result:</b>         |
|                            | <b>OK</b>                   |



|              |                  |
|--------------|------------------|
| Site Number: | <b>SE60XC302</b> |
| Site Name:   | <b>Splinter</b>  |
| Job Number:  | <b>REV01</b>     |
| Engineer:    | <b>AHB</b>       |
| Date:        | <b>9/16/2019</b> |

**Flange @ 94'**

|                  |                  |
|------------------|------------------|
| Reinforcement:   | <b>N</b>         |
| Moment:          | <b>14.5 k-ft</b> |
| Shear/Leg:       | <b>1.3 k</b>     |
| Compression/Leg: | <b>2.6 k</b>     |

|   |              |
|---|--------------|
| TIA-222 Code Revision (F/G):                | <b>G</b>     |
| Anchor Bolt Arrangement:                    | <b>Round</b> |
| Monopole Shaft Diameter:                    | <b>in</b>    |
| Lower Monopole Thickness:                   | <b>in</b>    |
| Monopole Shaft Yield Strength:              | <b>ksi</b>   |
| Baseplate Diameter / Length:                | <b>in</b>    |
| Base Plate Thickness:                       | <b>in</b>    |
| Base Plate Yield Strength:                  | <b>ksi</b>   |
| Fillet Weld Size:                           | <b>in</b>    |
| Weld Type (CJP or F/F):                     | <b>ksi</b>   |
| Weld Strength:                              | <b>ksi</b>   |
| Baseplate Detail Type:                      | <b>C</b>     |
| Include Plate Thickness Beyond Bolt Circle: | <b>Y</b>     |
| Stress Increase:                            | <b>1.00</b>  |
| Additional Anchor Bolts Installed:          | <b>N</b>     |

Anchor Bolts

|                                    |                 |
|------------------------------------|-----------------|
| Anchor Bolt Yield Strength:        | <b>92 ksi</b>   |
| Anchor Bolt Ultimate Strength:     | <b>120 ksi</b>  |
| Anchor Bolt Diameter:              | <b>1.00 in</b>  |
| Anchor Bolt Circle:                | <b>26.00 in</b> |
| # of Anchor Bolts:                 | <b>12</b>       |
| Minimum Anchor Bolt Separation:    | <b>6.00 in</b>  |
| Additional Anchor Bolts Installed: | <b>N</b>        |

Anchor Bolt Capacity

|                            |                             |
|----------------------------|-----------------------------|
| Area of Bolt:              | <b>0.61 in<sup>2</sup></b>  |
| Inertia of Bolt:           | <b>0.03 in<sup>4</sup></b>  |
| Total Bolt Inertia:        | <b>614.6 in<sup>4</sup></b> |
| Maximum Bolt Tension:      | <b>2.0 k</b>                |
| Maximum Bolt Compression:  | <b>2.4 k</b>                |
| Bolt Shear:                | <b>0.1 k</b>                |
| Tensile Bolt Capacity:     | <b>58.2 k</b>               |
| Compressive Bolt Capacity: | <b>58.2 k</b>               |
| Shear Bolt Capacity:       | <b>26.2 k</b>               |
| Interaction Equation:      | <b>0.04 Result:</b>         |
|                            | <b>OK</b>                   |

|              |                  |
|--------------|------------------|
| Site Number: | <b>SE60XC302</b> |
| Site Name:   | <b>Splinter</b>  |
| Job Number:  | <b>REV01</b>     |
| Engineer:    | <b>AHB</b>       |
| Date:        | <b>9/16/2019</b> |

**Flange @ 104'**

|                  |          |
|------------------|----------|
| Reinforcement:   | <b>N</b> |
| Moment:          | 4.0 k-ft |
| Shear/Leg:       | 0.6 k    |
| Compression/Leg: | 0.9 k    |

|   |              |
|---|--------------|
| TIA-222 Code Revision (F/G):                | <b>G</b>     |
| Anchor Bolt Arrangement:                    | <b>Round</b> |
| Monopole Shaft Diameter:                    | in           |
| Lower Monopole Thickness:                   | in           |
| Monopole Shaft Yield Strength:              | ksi          |
| Baseplate Diameter / Length:                |              |
| Base Plate Thickness:                       | in           |
| Base Plate Yield Strength:                  | ksi          |
| Fillet Weld Size:                           | in           |
| Weld Type (CJP or F/F):                     |              |
| Weld Strength:                              | ksi          |
| Baseplate Detail Type:                      | <b>C</b>     |
| Include Plate Thickness Beyond Bolt Circle: | <b>Y</b>     |
| Stress Increase:                            | 1.00         |
| Additional Anchor Bolts Installed:          | <b>N</b>     |

Anchor Bolts


|                                    |               |
|------------------------------------|---------------|
| Anchor Bolt Yield Strength:        | <b>92</b> ksi |
| Anchor Bolt Ultimate Strength:     | 120 ksi       |
| Anchor Bolt Diameter:              | 1.00 in       |
| Anchor Bolt Circle:                | 26.00 in      |
| # of Anchor Bolts:                 | 12            |
| Minimum Anchor Bolt Separation:    | 6.00 in       |
| Additional Anchor Bolts Installed: | <b>N</b>      |

Anchor Bolt Capacity

|                            |                       |
|----------------------------|-----------------------|
| Area of Bolt:              | 0.61 in <sup>2</sup>  |
| Inertia of Bolt:           | 0.03 in <sup>4</sup>  |
| Total Bolt Inertia:        | 614.6 in <sup>4</sup> |
| Maximum Bolt Tension:      | 0.5 k                 |
| Maximum Bolt Compression:  | 0.7 k                 |
| Bolt Shear:                | 0.1 k                 |
| Tensile Bolt Capacity:     | 58.2 k                |
| Compressive Bolt Capacity: | 58.2 k                |
| Shear Bolt Capacity:       | 26.2 k                |
| Interaction Equation:      | 0.01 Result:          |
|                            | OK                    |

Site Name: Round Hill CT  
 Site Number: 27741\_B  
 Engineering Number: REV01  
 Engineer: JHH  
 Date: 09/16/19  
 Tower Type: MP

Program Last Updated: 5/13/2014



**Design Loads (Factored) - Analysis per TIA-222-G Standards**

| Design / Analysis / Mapping:               | Analysis            |                                     |                       |
|--|---------------------|-------------------------------------|-----------------------|
| Compression/Leg:                           | 0.0 k               | Concrete Strength ( $f'_c$ ):       | 4000 psi              |
| Uplift/Leg:                                | 0.0 k               | Pad Tension Steel Depth:            | 32.00 in              |
| Total Shear:                               | 9.0 k               | $\phi_{\text{Shear}}$ :             | 0.75                  |
| Moment:                                    | 504.0 k-ft          | $\phi_{\text{Flexure / Tension}}$ : | 0.90                  |
| Tower + Appurtenance Weight:               | 15.5 k              | $\phi_{\text{Compression}}$ :       | 0.65                  |
| Depth to Base of Foundation (l + t - h):   | 5.00 ft             | $\beta$ :                           | 0.85                  |
| Diameter of Pier (d):                      | 6.00 ft             | Bottom Pad Rebar Size #:            | 8                     |
| Height of Pier above Ground (h):           | 1.00                | # of Bottom Pad Rebar:              | 16                    |
| Width of Pad (W):                          | 15.00 ft            | Pad Bottom Steel Area:              | 12.64 in <sup>2</sup> |
| Length of Pad (L):                         | 15.00 ft            | Pad Steel $F_y$ :                   | 60000 psi             |
| Thickness of Pad (t):                      | 3.00 ft             | Top Pad Rebar Size #:               | 8                     |
| Tower Leg Center to Center:                | 0.00 ft             | # of Top Pad Rebar:                 | 16                    |
| Number of Tower Legs:                      | 1.0 (1 if MP or GT) | Pad Top Steel Area:                 | 12.64 in <sup>2</sup> |
| Tower Center from Mat Center:              | 0.00 ft             | Pier Rebar Size #:                  | 8                     |
| Depth Below Ground Surface to Water Table: | 99.00 ft            | Pier Steel Area (Single Bar):       | 0.79 in <sup>2</sup>  |
| Unit Weight of Concrete:                   | 150.0 pcf           | # of Pier Rebar:                    | 22                    |
| Unit Weight of Soil Above Water Table:     | 130.0 pcf           | Pier Steel $F_y$ :                  | 60000 psi             |
| Unit Weight of Water:                      | 62.4 pcf            | Pier Cage Diameter:                 | 64.0 in               |
| Unit Weight of Soil Below Water Table:     | 50.0 pcf            | Rebar Strain Limit:                 | 0.008                 |
| Friction Angle of Uplift:                  | 0.0 Degrees         | Steel Elastic Modulus:              | 29000 ksi             |
| Ultimate Coefficient of Shear Friction:    | 0.35                | Tie Rebar Size #:                   | 4                     |
| Ultimate Compressive Bearing Pressure:     | 12000.0 psf         | Tie Steel Area (Single Bar):        | 0.20 in <sup>2</sup>  |
| Ultimate Passive Pressure on Pad Face:     | 0.0 psf             | Tie Spacing:                        | 6 in                  |
| $\phi_{\text{Soil and Concrete Weight}}$ : | 0.9                 | Tie Steel $F_y$ :                   | 60000 psi             |
| $\phi_{\text{Soil}}$ :                     | 0.75                |                                     |                       |

**Overturing Moment Usage**

|                              |                 |
|------------------------------|-----------------|
| Design OTM:                  | 557.7 k-ft      |
| OTM Resistance:              | 1201.7 k-ft     |
| Design OTM / OTM Resistance: | 0.46 Result: OK |

**Soil Bearing Pressure Usage**

|   |                      |
|---|----------------------|
| Net Bearing Pressure:                                   | 1601 psf             |
| Factored Nominal Bearing Pressure:                      | 9000 psf             |
| Net Bearing Pressure/Factored Nominal Bearing Pressure: | 0.18 Result: OK      |
| Load Direction Controlling Design Bearing Pressure:     | Diagonal to Pad Edge |


**Sliding Factor of Safety**

|                                      |                 |
|--------------------------------------|-----------------|
| Total Factored Sliding Resistance:   | 46.7 k          |
| Sliding Design / Sliding Resistance: | 0.19 Result: OK |

### One Way Shear, Flexural Capacity, and Punching Shear

|   |   |
|---|---|
| Factored One Way Shear ( $V_u$ ):                 | 28.7 k  |
| One Way Shear Capacity ( $\phi V_c$ ):            | 359.9 k - ACI11.3.1.1                                     |
| $V_u / \phi V_c$ :                                | 0.08 Result: OK   |
| Load Direction Controlling Shear Capacity:        | Diagonal to Pad Edge                                      |
| Lower Steel Pad Factored Moment ( $M_u$ ):        | 162.9 k-ft  |
| Lower Steel Pad Moment Capacity ( $\phi M_n$ ):   | 1736.8 k-ft - ACI10.3                                     |
| $M_u / \phi M_n$ :                                | 0.09 Result: OK   |
| Load Direction Controlling Flexural Capacity:     | Diagonal to Pad Edge                                      |
| Upper Steel Pad Factored Moment ( $M_u$ ):        | 100.2 k-ft  |
| Upper Steel Pad Moment Capacity ( $\phi M_n$ ):   | 1790.2 k-ft   |
| $M_u / \phi M_n$ :                                | 0.06 Result: OK   |
| Lower Pad Flexural Reinforcement Ratio:           | 0.0022 OK - Minimum Reinforcement Ratio Met - ACI10.5.1   |
| Upper Pad Flexural Reinforcement Ratio:           | 0.0022 OK - Minimum Reinforcement Ratio Met - ACI10.5.1   |
| Lower Pad Reinforcement Spacing:                  | 11 in - Pad Reinforcing Spacing OK - ACI7.12.2.2 & 10.5.4 |
| Upper Pad Reinforcement Spacing:                  | 11 in - Pad Reinforcing Spacing OK - ACI7.12.2.2 & 10.5.4 |
| Factored Punching Shear ( $V_u$ ):                | 0.0 k   |
| Nominal Punching Shear Capacity ( $\phi_c V_n$ ): | 1983.7 k - ACI11.12.2.1                                   |
| $V_u / \phi V_c$ :                                | 0.00 Result: OK   |
| Factored Moment in Pier ( $M_u$ ):                | 530.8 k-ft  |
| Pier Moment Capacity ( $\phi M_n$ ):              | 2451.3 k-ft   |
| $M_u / \phi M_n$ :                                | 0.22 Result: OK   |
| Factored Shear in Pier ( $V_u$ ):                 | 9.0 k   |
| Pier Shear Capacity ( $\phi V_n$ ):               | 386.3 k   |
| $V_u / \phi V_c$ :                                | 0.02 Result: OK   |
| Pier Shear Reinforcement Ratio:                   | 0.0005 No Ties Necessary for Shear - ACI11.5.6.1          |
| Factored Tension in Pier ( $T_u$ ):               | 0.0 k   |
| Pier Tension Capacity ( $\phi T_n$ ):             | 938.5 k   |
| $T_u / \phi T_n$ :                                | 0.00 Result: OK   |
| Factored Compression in Pier ( $P_u$ ):           | 0.0 k   |
| Pier Compression Capacity ( $\phi P_n$ ):         | 7167.7 k - ACI10.3.6.2                                    |
| $P_u / \phi P_n$ :                                | 0.00 Result: OK   |
| Pier Compression Reinforcement Ratio:             | 0.004 NG - Increase Pier Steel - ACI10.9.1 & 10.8.4       |
| $M_u / \phi_B M_n + T_u / \phi_T T_n$ :           | 0.22 Result: OK   |

Nominal and Design Moment Capacity and Factored Design Loads






# ASCE 7 Hazards Report

**Address:**  
No Address at This  
Location

**Standard:** ASCE/SEI 7-10  
**Risk Category:** II  
**Soil Class:** D - Stiff Soil

**Elevation:** 378.96 ft (NAVD 88)  
**Latitude:** 41.095117  
**Longitude:** -73.664219





**Site Soil Class:** D - Stiff Soil

**Results:**

|            |       |                    |       |
|------------|-------|--------------------|-------|
| $S_s$ :    | 0.259 | $S_{DS}$ :         | 0.275 |
| $S_1$ :    | 0.071 | $S_{D1}$ :         | 0.113 |
| $F_a$ :    | 1.593 | $T_L$ :            | 6     |
| $F_v$ :    | 2.4   | PGA :              | 0.152 |
| $S_{MS}$ : | 0.412 | PGA <sub>M</sub> : | 0.228 |
| $S_{M1}$ : | 0.169 | F <sub>PGA</sub> : | 1.495 |
|            |       | $I_e$ :            | 1     |

**Seismic Design Category** B



**Data Accessed:**

Wed Sep 11 2019

**Date Source:**

USGS Seismic Design Maps based on ASCE/SEI 7-10, incorporating Supplement 1 and errata of March 31, 2013, and ASCE/SEI 7-10 Table 1.5-2. Additional data for site-specific ground motion procedures in accordance with ASCE/SEI 7-10 Ch. 21 are available from USGS.

## Ice

---

### Results:

Ice Thickness: 0.75 in.

Concurrent Temperature: 15 F

Gust Speed: 50 mph

**Data Source:** Standard ASCE/SEI 7-10, Figs. 10-2 through 10-8

**Date Accessed:** Wed Sep 11 2019

Ice thicknesses on structures in exposed locations at elevations higher than the surrounding terrain and in valleys and gorges may exceed the mapped values.

Values provided are equivalent radial ice thicknesses due to freezing rain with concurrent 3-second gust speeds, for a 50-year mean recurrence interval, and temperatures concurrent with ice thicknesses due to freezing rain. Thicknesses for ice accretions caused by other sources shall be obtained from local meteorological studies. Ice thicknesses in exposed locations at elevations higher than the surrounding terrain and in valleys and gorges may exceed the mapped values.

---

The ASCE 7 Hazard Tool is provided for your convenience, for informational purposes only, and is provided "as is" and without warranties of any kind. The location data included herein has been obtained from information developed, produced, and maintained by third party providers; or has been extrapolated from maps incorporated in the ASCE 7 standard. While ASCE has made every effort to use data obtained from reliable sources or methodologies, ASCE does not make any representations or warranties as to the accuracy, completeness, reliability, currency, or quality of any data provided herein. Any third-party links provided by this Tool should not be construed as an endorsement, affiliation, relationship, or sponsorship of such third-party content by or from ASCE.

ASCE does not intend, nor should anyone interpret, the results provided by this Tool to replace the sound judgment of a competent professional, having knowledge and experience in the appropriate field(s) of practice, nor to substitute for the standard of care required of such professionals in interpreting and applying the contents of this Tool or the ASCE 7 standard.

In using this Tool, you expressly assume all risks associated with your use. Under no circumstances shall ASCE or its officers, directors, employees, members, affiliates, or agents be liable to you or any other person for any direct, indirect, special, incidental, or consequential damages arising from or related to your use of, or reliance on, the Tool or any information obtained therein. To the fullest extent permitted by law, you agree to release and hold harmless ASCE from any and all liability of any nature arising out of or resulting from any use of data provided by the ASCE 7 Hazard Tool.

**(APPENDIX N) MUNICIPALITY - SPECIFIC STRUCTURAL DESIGN PARAMETERS**

| Municipality  | Ground Snow Load | MCE Spectral Accelerations (%g) |                | Wind Design Parameters                              |              |                 |  |              |                  |  |                                       |                         |
|---------------|------------------|---------------------------------|----------------|---|--------------|-----------------|--|--------------|------------------|--|---------------------------------------|-------------------------|
|               |                  | S <sub>s</sub>                  | S <sub>1</sub> | Ultimate Design Wind Speeds, V <sub>ult</sub> (mph) |              |                 | Nominal Design Wind Speeds, V <sub>asd</sub> (mph) |              |                  | Wind-Borne Debris Regions <sup>1</sup> |                                       | Hurricane-Prone Regions |
|               |                  |                                 |                | Risk Cat. I   | Risk Cat. II | Risk Cat III-IV | Risk Cat. I  | Risk Cat. II | Risk Cat. III-IV | Risk Cat. II & III except Occup I-2    | Risk Cat III Occup I-2 & Risk Cat. IV |                         |
| Enfield       | 35               | 0.176                           | 0.065          | 110   | 125          | 130             | 85   | 97           | 101              |  |                                       | Yes                     |
| Essex         | 30               | 0.168                           | 0.059          | 120   | 135          | 145             | 93   | 105          | 112              |  | Type A                                | Yes                     |
| Fairfield     | 30               | 0.215                           | 0.065          | 115   | 125          | 135             | 89   | 97           | 105              |  | Type B                                | Yes                     |
| Farmington    | 35               | 0.183                           | 0.064          | 115   | 125          | 135             | 89   | 97           | 105              |  |                                       | Yes                     |
| Franklin      | 30               | 0.171                           | 0.061          | 120   | 130          | 140             | 93   | 101          | 108              |  | Type A                                | Yes                     |
| Glastonbury   | 30               | 0.180                           | 0.063          | 115   | 125          | 135             | 89   | 97           | 105              |  |                                       | Yes                     |
| Goshen        | 40               | 0.181                           | 0.065          | 105   | 115          | 125             | 81   | 89           | 97               |  |                                       |                         |
| Granby        | 35               | 0.176                           | 0.065          | 110   | 120          | 130             | 85   | 93           | 101              |  |                                       | Yes                     |
| Greenwich     | 30               | 0.259                           | 0.070          | 110   | 120          | 130             | 85   | 93           | 101              |  |                                       | Yes                     |
| Griswold      | 30               | 0.168                           | 0.060          | 125   | 135          | 145             | 97   | 105          | 112              |  | Type A                                | Yes                     |
| Groton        | 30               | 0.160                           | 0.058          | 125   | 135          | 145             | 97   | 105          | 112              | Type B                                 | Type A                                | Yes                     |
| Guilford      | 30               | 0.176                           | 0.061          | 120   | 130          | 140             | 93   | 101          | 108              |  | Type B                                | Yes                     |
| Haddam        | 30               | 0.175                           | 0.061          | 120   | 130          | 140             | 93   | 101          | 108              |  |                                       | Yes                     |
| Hamden        | 30               | 0.185                           | 0.063          | 115   | 125          | 135             | 89   | 97           | 105              |  |                                       | Yes                     |
| Hampton       | 35               | 0.172                           | 0.062          | 120   | 130          | 140             | 93   | 101          | 108              |  |                                       | Yes                     |
| Hartford      | 30               | 0.181                           | 0.064          | 115   | 125          | 135             | 89   | 97           | 105              |  |                                       | Yes                     |
| Hartland      | 40               | 0.175                           | 0.065          | 110   | 120          | 125             | 85   | 93           | 97               |  |                                       | Yes                     |
| Harwinton     | 35               | 0.183                           | 0.065          | 110   | 120          | 130             | 85   | 93           | 101              |  |                                       | Yes                     |
| Hebron        | 30               | 0.177                           | 0.063          | 120   | 130          | 140             | 93   | 101          | 108              |  |                                       | Yes                     |
| Kent          | 40               | 0.188                           | 0.065          | 105   | 115          | 120             | 81   | 89           | 93               |  |                                       |                         |
| Killingly     | 40               | 0.171                           | 0.062          | 120   | 130          | 140             | 93   | 101          | 108              |  |                                       | Yes                     |
| Killingworth  | 30               | 0.173                           | 0.061          | 120   | 130          | 140             | 93   | 101          | 108              |  |                                       | Yes                     |
| Lebanon       | 30               | 0.173                           | 0.062          | 120   | 130          | 140             | 93   | 101          | 108              |  |                                       | Yes                     |
| Ledyard       | 30               | 0.163                           | 0.059          | 125   | 135          | 145             | 97   | 105          | 112              |  | Type A                                | Yes                     |
| Lisbon        | 30               | 0.169                           | 0.061          | 125   | 135          | 145             | 97   | 105          | 112              |  | Type A                                | Yes                     |
| Litchfield    | 40               | 0.184                           | 0.065          | 110   | 120          | 125             | 85   | 93           | 97               |  |                                       | Yes                     |
| Lyme          | 30               | 0.164                           | 0.059          | 125   | 135          | 145             | 97   | 105          | 112              |  | Type A                                | Yes                     |
| Madison       | 30               | 0.173                           | 0.060          | 120   | 130          | 140             | 93   | 101          | 108              |  | Type B                                | Yes                     |
| Manchester    | 30               | 0.178                           | 0.064          | 115   | 125          | 135             | 89   | 97           | 105              |  |                                       | Yes                     |
| Mansfield     | 35               | 0.173                           | 0.062          | 120   | 130          | 140             | 93   | 101          | 108              |  |                                       | Yes                     |
| Marlborough   | 30               | 0.177                           | 0.062          | 120   | 130          | 140             | 93   | 101          | 108              |  |                                       | Yes                     |
| Meriden       | 30               | 0.183                           | 0.063          | 115   | 125          | 135             | 89   | 97           | 105              |  |                                       | Yes                     |
| Middlebury    | 35               | 0.191                           | 0.064          | 110   | 120          | 130             | 85   | 93           | 101              |  |                                       | Yes                     |
| Middlefield   | 30               | 0.181                           | 0.063          | 115   | 125          | 135             | 89   | 97           | 105              |  |                                       | Yes                     |
| Middletown    | 30               | 0.180                           | 0.063          | 115   | 130          | 135             | 89   | 101          | 105              |  |                                       | Yes                     |
| Milford       | 30               | 0.194                           | 0.063          | 115   | 125          | 135             | 89   | 97           | 105              |  | Type B                                | Yes                     |
| Monroe        | 30               | 0.205                           | 0.065          | 110   | 120          | 130             | 85   | 93           | 101              |  |                                       | Yes                     |
| Montville     | 30               | 0.165                           | 0.059          | 125   | 135          | 145             | 97   | 105          | 112              |  | Type A                                | Yes                     |
| Morris        | 35               | 0.187                           | 0.065          | 110   | 120          | 125             | 85   | 93           | 97               |  |                                       | Yes                     |
| Naugatuck     | 30               | 0.190                           | 0.064          | 110   | 125          | 135             | 85   | 97           | 105              |  |                                       | Yes                     |
| New Britain   | 30               | 0.183                           | 0.064          | 115   | 125          | 135             | 89   | 97           | 105              |  |                                       | Yes                     |
| New Canaan    | 30               | 0.240                           | 0.068          | 110   | 120          | 130             | 85   | 93           | 101              |  |                                       | Yes                     |
| New Fairfield | 35               | 0.212                           | 0.067          | 105   | 115          | 125             | 81   | 89           | 97               |  |                                       |                         |
| New Hartford  | 40               | 0.180                           | 0.065          | 110   | 120          | 130             | 85   | 93           | 101              |  |                                       | Yes                     |

April 17, 2019

Tom Jupin  
Charles Cherundolo Consulting, Inc.  
1280 Route 46 West  
Parsippany, NJ 07054

Ramaker & Associates, Inc.  
855 Community Drive  
Sauk City, WI 53583

**SUBJECT: MOUNT ASSESSMENT**

**CARRIER: SPRINT**

**SITE: CT60XC001  
24 ½ RICHDALE DRIVE  
WILTON, FAIRFIELD COUNTY, CONNECTICUT 06897  
RAMAKER & ASSOCIATES PROJECT NUMBER: 28753**

**RESULTS: MOUNT: PASS**

Dear Tom Jupin:

Ramaker & Associates, Inc. (RAMAKER) respectfully submits this mount assessment for the above-mentioned site. The purpose of this report is to determine the structural integrity of the mounting structure with the proposed loading configurations. Engineering recommendations regarding the analysis results are provided in the following pages.

RAMAKER developed a finite element model of the mount(s) using RISA analysis software. All information contained herein is valid only for the described structure configuration and loading conditions. RAMAKER reserves the right to modify our recommendations should alterations to the mount loading occur.

If you have any questions or comments, please do not hesitate to contact our office.

Sincerely,

RAMAKER & ASSOCIATES, INC.



Tucker Schwab  
Structural Designer



James R. Skowronski, P.E.  
Supervising Engineer





**ANALYSIS CRITERIA**

|                                       |                             |
|---------------------------------------|-----------------------------|
| State Building Code                   | 2018 CT State Building Code |
| Adopted Building Code                 | 2015 IBC                    |
| Referenced Standard                   | TIA-222-G                   |
| Risk Category                         | II                          |
| Ultimate Design Wind Speed, $V_{ult}$ | 120mph (3 sec. gust)        |
| Nominal Design Wind Speed, $V_{asd}$  | 93 mph (3 sec. gust)        |
| Design Wind Speed w/ Ice              | 50 mph (3 sec. gust)        |
| Ice Thickness                         | 3/4 inch                    |
| Exposure Category                     | C                           |
| Topographic Feature                   | None                        |

**SUPPORTING DOCUMENTATION**

- Construction drawings by RAMAKER, project number 28753
- Site visit(s) conducted by RAMAKER
- Other pertinent data procured or assumed by RAMAKER during site due diligence activities

**MOUNT LOADING**

RAMAKER understands that the loading to be used for this analysis will consist of the antennas and equipment configurations as shown in the following chart(s):

| Antenna Mount – Alpha Sector |          |                          |                                      |           |
|------------------------------|----------|--------------------------|--------------------------------------|-----------|
| Elevation                    | Position | Appurtenance             | Mount Type                           | Status    |
| 67                           | 1        | (1) WHIP Antenna         | Site Pro 1 RMQP-396 Platform w/HRK12 | Relocated |
|                              | 2        | (1) RFS APXVSP18-C-A20   |                                      | Remove    |
|                              |          | (1) KMW ETCR-654L12H6    |                                      | Proposed  |
|                              |          | (1) ALU 800MHz 2x50W RRH |                                      | Relocated |
|                              |          | (1) ALU 1900MHz 4x45 RRH |                                      |           |
|                              | 3        | (1) ALU 800MHz 2x50W RRH |                                      | Proposed  |
|                              |          | (1) Nokia FZHN           |                                      |           |

| Antenna Mount – Beta and Gamma Sector |          |                          |   |           |
|---------------------------------------|----------|--------------------------|---|-----------|
| Elevation                             | Position | Appurtenance             | Mount Type                              | Status    |
| 67                                    | 1        | --                       | Site Pro 1 RMQP-396<br>Platform w/HRK12 | --        |
|                                       | 2        | (1) RFS APXVSP18-C-A20   |   | Remove    |
|                                       |          | (1) KMW ETCR-654L12H6    |   | Proposed  |
|                                       |          | (1) ALU 800MHz 2x50W RRH |   | Relocated |
|                                       |          | (1) ALU 1900MHz 4x45 RRH |   |           |
|                                       | 3        | (1) ALU 800MHz 2x50W RRH |   | Proposed  |
| (1) Nokia FZHN                        |          |                          |   |           |

### MOUNT RESULTS

By engineering calculation and inspection, the **proposed** antenna and equipment mounting structure(s) are capable of supporting the proposed loading configurations without causing an overstress condition in the antenna and equipment mounting structure(s). **The existing antenna and equipment mounting structure(s) shall be removed and replaced with the proposed antenna and equipment mounting structure(s) prior to antenna and equipment installation. See associated RAMAKER construction drawings for mount details.**

**LIMITATIONS**

The recommendations contained within this report were developed using the supporting documentation as previously described. All recommendations pertain only to the proposed antenna installation activities as described in this report. RAMAKER assumes no responsibility for failures caused by factors beyond our control. These include but are not limited to the following:

- Missing, corroding, and/or deteriorating members
- Improper manufacturing and/or construction
- Improper maintenance
- Member grades less than assumed grades show below:


| <b>Assumed Steel Member Grades</b> |                        |
|------------------------------------|------------------------|
| Angles/Plates/Channels/Solid Rods  | ASTM A36, 36 ksi       |
| Pipes                              | ASTM A53 Gr. B, 35 ksi |
| HSS (Square Tube)                  | ASTM A36, 36 ksi       |

RAMAKER is not responsible for verifying that the loading on the structure is consistent with the loading applied to the structure within this report. If there is any information contrary to that contained herein, or if there are any defects arising from the original design, material, fabrication and erection deficiencies, this report should be disregarded and RAMAKER should be contacted immediately. RAMAKER is not liable for any representation, recommendation, or conclusion not expressly stated herein.

This analysis pertains only to the mounting structure, and no analyses or conclusions were made regarding the supporting structure. Analysis and certification of the supporting structure is performed and submitted separately.

**ATTACHMENTS**

- Analysis Figures
- Analysis Calculations



Envelope Only Solution

Ramaker & Associates, Inc.

TJS

28753

CT60XC001

SK - 1

Apr 17, 2019 at 3:40 PM

28753 Platform.r3d





### Hot Rolled Steel Properties

|   | Label      | E [ksi] | G [ksi] | Nu | Therm (1...Density[k/... | Yield[ksi] | Ry | Fu[ksi] | Rt |     |
|---|------------|---------|---------|----|--------------------------|------------|----|---------|----|-----|
| 1 | A36 Gr.36  | 29000   | 11154   | .3 | .65                      | .49        | 36 | 1.5     | 58 | 1.2 |
| 2 | A572 Gr.50 | 29000   | 11154   | .3 | .65                      | .49        | 50 | 1.1     | 65 | 1.1 |
| 3 | A992       | 29000   | 11154   | .3 | .65                      | .49        | 50 | 1.1     | 65 | 1.1 |
| 4 | A500 Gr.42 | 29000   | 11154   | .3 | .65                      | .49        | 42 | 1.4     | 58 | 1.3 |
| 5 | A500 Gr.46 | 29000   | 11154   | .3 | .65                      | .49        | 46 | 1.4     | 58 | 1.3 |
| 6 | A53 Gr. B  | 29000   | 11154   | .3 | .65                      | .49        | 35 | 1.5     | 60 | 1.2 |

### Hot Rolled Steel Section Sets

|   | Label        | Shape      | Type | Design List  | Material  | Design Rules | A [in2] | Iyy [in4] | Izz [in4] | J [in4] |
|---|--------------|------------|------|--------------|-----------|--------------|---------|-----------|-----------|---------|
| 1 | HSS 4x4x4/16 | HSS4X4X4   | Beam | SquareTube   | A36 Gr.36 | Typical      | 3.37    | 7.8       | 7.8       | 12.8    |
| 2 | L2x2x3/16    | L2x2x3     | Beam | Single Angle | A36 Gr.36 | Typical      | .722    | .271      | .271      | .009    |
| 3 | L2.5x2.5x1/4 | L2.5x2.5x4 | Beam | Single Angle | A36 Gr.36 | Typical      | 1.19    | .692      | .692      | .026    |
| 4 | Pipe 3.0     | PIPE_3.0   | Beam | Pipe         | A53 Gr. B | Typical      | 2.07    | 2.85      | 2.85      | 5.69    |
| 5 | Pipe 2.0     | PIPE_2.0   | Beam | Pipe         | A53 Gr. B | Typical      | 1.02    | .627      | .627      | 1.25    |
| 6 | PL 6X1/2     | PL 6x1/2   | Beam | RECT         | A36 Gr.36 | Typical      | 3       | .063      | 9         | .237    |
| 7 | 1" SR        | 1" SR      | Beam | RECT         | A36 Gr.36 | Typical      | .785    | .049      | .049      | .098    |

### Member Primary Data

|    | Label | I Joint | J Joint | K Joint | Rotate(... | Section/Shape | Type | Design List  | Material   | Design R... |
|----|-------|---------|---------|---------|------------|---------------|------|--------------|------------|-------------|
| 1  | TH1   | N38     | N39     |         |            | Pipe 2.0      | Beam | Pipe         | A53 Gr. B  | Typical     |
| 2  | TH3   | N44     | N45     |         |            | Pipe 2.0      | Beam | Pipe         | A53 Gr. B  | Typical     |
| 3  | TH2   | N40     | N41     |         |            | Pipe 2.0      | Beam | Pipe         | A53 Gr. B  | Typical     |
| 4  | SA2   | N57     | N13     |         |            | HSS 4x4x4/16  | Beam | SquareTube   | A36 Gr.... | Typical     |
| 5  | SA1   | N58     | N14     |         |            | HSS 4x4x4/16  | Beam | SquareTube   | A36 Gr.... | Typical     |
| 6  | SA3   | N56     | N15     |         |            | HSS 4x4x4/16  | Beam | SquareTube   | A36 Gr.... | Typical     |
| 7  | M78   | N53     | N54     |         |            | RIGID         | None | None         | RIGID      | Typical     |
| 8  | M77   | N52     | N55     |         |            | RIGID         | None | None         | RIGID      | Typical     |
| 9  | M75   | N49     | N50     |         |            | RIGID         | None | None         | RIGID      | Typical     |
| 10 | M74A  | N48     | N51     |         |            | RIGID         | None | None         | RIGID      | Typical     |
| 11 | M74   | N43     | N46     |         |            | RIGID         | None | None         | RIGID      | Typical     |
| 12 | M73   | N42     | N47     |         |            | RIGID         | None | None         | RIGID      | Typical     |
| 13 | PL2   | N11     | N12     |         |            | PL 6X1/2      | Beam | RECT         | A36 Gr.... | Typical     |
| 14 | PL1   | N9      | N10     |         |            | PL 6X1/2      | Beam | RECT         | A36 Gr.... | Typical     |
| 15 | PL3   | N5      | N6      |         |            | PL 6X1/2      | Beam | RECT         | A36 Gr.... | Typical     |
| 16 | B2    | N48     | N49     |         | 90         | L2.5x2.5x1/4  | Beam | Single Angle | A36 Gr.... | Typical     |
| 17 | B1    | N52     | N53     |         | 90         | L2.5x2.5x1/4  | Beam | Single Angle | A36 Gr.... | Typical     |
| 18 | B3    | N42     | N43     |         | 90         | L2.5x2.5x1/4  | Beam | Single Angle | A36 Gr.... | Typical     |
| 19 | GS3   | N29     | N30     |         |            | L2x2x3/16     | Beam | Single Angle | A36 Gr.... | Typical     |
| 20 | GS2   | N31     | N32     |         | 270        | L2x2x3/16     | Beam | Single Angle | A36 Gr.... | Typical     |
| 21 | GS1   | N35     | N36     |         | 270        | L2x2x3/16     | Beam | Single Angle | A36 Gr.... | Typical     |
| 22 | GS6   | N33     | N34     |         | 270        | L2x2x3/16     | Beam | Single Angle | A36 Gr.... | Typical     |
| 23 | GS5   | N25     | N26     |         | 270        | L2x2x3/16     | Beam | Single Angle | A36 Gr.... | Typical     |
| 24 | GS4   | N27     | N28     |         |            | L2x2x3/16     | Beam | Single Angle | A36 Gr.... | Typical     |
| 25 | CB4   | N24     | N19     |         |            | HSS 4x4x4/16  | Beam | SquareTube   | A36 Gr.... | Typical     |
| 26 | CB3   | N23     | N24     |         |            | HSS 4x4x4/16  | Beam | SquareTube   | A36 Gr.... | Typical     |
| 27 | CB2   | N22     | N20     |         |            | HSS 4x4x4/16  | Beam | SquareTube   | A36 Gr.... | Typical     |
| 28 | CB1   | N21     | N22     |         |            | HSS 4x4x4/16  | Beam | SquareTube   | A36 Gr.... | Typical     |
| 29 | CB6   | N16     | N17     |         |            | HSS 4x4x4/16  | Beam | SquareTube   | A36 Gr.... | Typical     |
| 30 | CB5   | N17     | N18     |         |            | HSS 4x4x4/16  | Beam | SquareTube   | A36 Gr.... | Typical     |
| 31 | BH1   | N1      | N2      |         |            | Pipe 3.0      | Beam | Pipe         | A53 Gr. B  | Typical     |
| 32 | BH3   | N7      | N8      |         |            | Pipe 3.0      | Beam | Pipe         | A53 Gr. B  | Typical     |
| 33 | BH2   | N3      | N4      |         |            | Pipe 3.0      | Beam | Pipe         | A53 Gr. B  | Typical     |
| 34 | MPC1  | N61     | N60     |         |            | Pipe 2.0      | Beam | Pipe         | A53 Gr. B  | Typical     |



Company : Ramaker & Associates, Inc.  
 Designer : TJS  
 Job Number : 28753  
 Model Name : CT60XC001

Apr 17, 2019  
 3:40 PM  
 Checked By: \_\_\_\_\_

**Member Primary Data (Continued)**

|    | Label | I Joint | J Joint | K Joint | Rotate(... | Section/Shape | Type | Design List | Material   | Design R... |
|----|-------|---------|---------|---------|------------|---------------|------|-------------|------------|-------------|
| 35 | M56   | N59     | N63     |         |            | RIGID         | None | None        | RIGID      | Typical     |
| 36 | M57A  | N62     | N64     |         |            | RIGID         | None | None        | RIGID      | Typical     |
| 37 | MPC3  | N67     | N66     |         |            | Pipe 2.0      | Beam | Pipe        | A53 Gr. B  | Typical     |
| 38 | M68A  | N65     | N69     |         |            | RIGID         | None | None        | RIGID      | Typical     |
| 39 | M69A  | N68     | N70     |         |            | RIGID         | None | None        | RIGID      | Typical     |
| 40 | M44   | N71     | N75     |         |            | RIGID         | None | None        | RIGID      | Typical     |
| 41 | M45   | N74     | N76     |         |            | RIGID         | None | None        | RIGID      | Typical     |
| 42 | MPB1  | N79     | N78     |         |            | Pipe 2.0      | Beam | Pipe        | A53 Gr. B  | Typical     |
| 43 | M44A  | N77     | N81     |         |            | RIGID         | None | None        | RIGID      | Typical     |
| 44 | M45A  | N80     | N82     |         |            | RIGID         | None | None        | RIGID      | Typical     |
| 45 | MPB3  | N85     | N84     |         |            | Pipe 2.0      | Beam | Pipe        | A53 Gr. B  | Typical     |
| 46 | M47   | N83     | N87     |         |            | RIGID         | None | None        | RIGID      | Typical     |
| 47 | M48   | N86     | N88     |         |            | RIGID         | None | None        | RIGID      | Typical     |
| 48 | M50   | N89     | N93     |         |            | RIGID         | None | None        | RIGID      | Typical     |
| 49 | M51   | N92     | N94     |         |            | RIGID         | None | None        | RIGID      | Typical     |
| 50 | MPA1  | N97     | N96     |         |            | Pipe 2.0      | Beam | Pipe        | A53 Gr. B  | Typical     |
| 51 | M53   | N95     | N99     |         |            | RIGID         | None | None        | RIGID      | Typical     |
| 52 | M54   | N98     | N100    |         |            | RIGID         | None | None        | RIGID      | Typical     |
| 53 | MPA3  | N103    | N102    |         |            | Pipe 2.0      | Beam | Pipe        | A53 Gr. B  | Typical     |
| 54 | M56A  | N101    | N105    |         |            | RIGID         | None | None        | RIGID      | Typical     |
| 55 | M57   | N104    | N106    |         |            | RIGID         | None | None        | RIGID      | Typical     |
| 56 | M59   | N107    | N111    |         |            | RIGID         | None | None        | RIGID      | Typical     |
| 57 | M60   | N110    | N112    |         |            | RIGID         | None | None        | RIGID      | Typical     |
| 58 | MPC2  | N73     | N72     |         |            | Pipe 2.0      | Beam | Pipe        | A53 Gr. B  | Typical     |
| 59 | MPA2  | N109    | N108    |         |            | Pipe 2.0      | Beam | Pipe        | A53 Gr. B  | Typical     |
| 60 | MPB2  | N91     | N90     |         |            | Pipe 2.0      | Beam | Pipe        | A53 Gr. B  | Typical     |
| 61 | M61   | N89A    | N91A    |         |            | RIGID         | None | None        | RIGID      | Typical     |
| 62 | M62   | N96     | N90A    |         |            | RIGID         | None | None        | RIGID      | Typical     |
| 63 | WHIP1 | N91A    | N93A    |         |            | Pipe 2.0      | Beam | Pipe        | A53 Gr. B  | Typical     |
| 64 | WHIP2 | N93A    | N92A    |         |            | 1" SR         | Beam | RECT        | A36 Gr.... | Typical     |

**Basic Load Cases**

|    | BLC Description       | Category | X ... | Y Gravity | Z Gravity | Joint | Point | Distributed Area(Me... | Surface(P... |
|----|-----------------------|----------|-------|-----------|-----------|-------|-------|------------------------|--------------|
| 1  | Antenna Dead          | None     |       |           |           |       | 18    |                        |              |
| 2  | Antenna Wind 0        | None     |       |           |           |       | 36    |                        |              |
| 3  | Antenna Wind 30       | None     |       |           |           |       | 36    |                        |              |
| 4  | Antenna Wind 45       | None     |       |           |           |       | 36    |                        |              |
| 5  | Antenna Wind 60       | None     |       |           |           |       | 36    |                        |              |
| 6  | Antenna Wind 90       | None     |       |           |           |       | 36    |                        |              |
| 7  | Antenna Wind 120      | None     |       |           |           |       | 36    |                        |              |
| 8  | Antenna Wind 135      | None     |       |           |           |       | 36    |                        |              |
| 9  | Antenna Wind 150      | None     |       |           |           |       | 36    |                        |              |
| 10 | Antenna Wind 180      | None     |       |           |           |       | 36    |                        |              |
| 11 | Antenna Wind 210      | None     |       |           |           |       | 36    |                        |              |
| 12 | Antenna Wind 225      | None     |       |           |           |       | 36    |                        |              |
| 13 | Antenna Wind 240      | None     |       |           |           |       | 36    |                        |              |
| 14 | Antenna Wind 270      | None     |       |           |           |       | 36    |                        |              |
| 15 | Antenna Wind 300      | None     |       |           |           |       | 36    |                        |              |
| 16 | Antenna Wind 315      | None     |       |           |           |       | 36    |                        |              |
| 17 | Antenna Wind 330      | None     |       |           |           |       | 36    |                        |              |
| 18 | Antenna Ice Dead      | None     |       |           |           |       | 18    |                        |              |
| 19 | Antenna Wind w/Ice 0  | None     |       |           |           |       | 36    |                        |              |
| 20 | Antenna Wind w/Ice 30 | None     |       |           |           |       | 36    |                        |              |
| 21 | Antenna Wind w/Ice 45 | None     |       |           |           |       | 36    |                        |              |
| 22 | Antenna Wind w/Ice 60 | None     |       |           |           |       | 36    |                        |              |



Company : Ramaker & Associates, Inc.  
 Designer : TJS  
 Job Number : 28753  
 Model Name : CT60XC001

Apr 17, 2019  
 3:40 PM  
 Checked By: \_\_\_\_\_

**Basic Load Cases (Continued)**

|    | BLC Description        | Category | X ... | Y Gravity | Z Gravity | Joint | Point | Distributed Area(Me... | Surface(P... |
|----|------------------------|----------|-------|-----------|-----------|-------|-------|------------------------|--------------|
| 23 | Antenna Wind w/Ice 90  | None     |       |           |           |       | 36    |                        |              |
| 24 | Antenna Wind w/Ice 120 | None     |       |           |           |       | 36    |                        |              |
| 25 | Antenna Wind w/Ice 135 | None     |       |           |           |       | 36    |                        |              |
| 26 | Antenna Wind w/Ice 150 | None     |       |           |           |       | 36    |                        |              |
| 27 | Antenna Wind w/Ice 180 | None     |       |           |           |       | 36    |                        |              |
| 28 | Antenna Wind w/Ice 210 | None     |       |           |           |       | 36    |                        |              |
| 29 | Antenna Wind w/Ice 225 | None     |       |           |           |       | 36    |                        |              |
| 30 | Antenna Wind w/Ice 240 | None     |       |           |           |       | 36    |                        |              |
| 31 | Antenna Wind w/Ice 270 | None     |       |           |           |       | 36    |                        |              |
| 32 | Antenna Wind w/Ice 300 | None     |       |           |           |       | 36    |                        |              |
| 33 | Antenna Wind w/Ice 315 | None     |       |           |           |       | 36    |                        |              |
| 34 | Antenna Wind w/Ice 330 | None     |       |           |           |       | 36    |                        |              |
| 35 | Member Dead            | None     |       | -1        |           |       |       |                        | 3            |
| 36 | Member Wind 0          | None     |       |           |           |       |       | 70                     |              |
| 37 | Member Wind 30         | None     |       |           |           |       |       | 70                     |              |
| 38 | Member Wind 45         | None     |       |           |           |       |       | 70                     |              |
| 39 | Member Wind 60         | None     |       |           |           |       |       | 70                     |              |
| 40 | Member Wind 90         | None     |       |           |           |       |       | 70                     |              |
| 41 | Member Wind 120        | None     |       |           |           |       |       | 70                     |              |
| 42 | Member Wind 135        | None     |       |           |           |       |       | 70                     |              |
| 43 | Member Wind 150        | None     |       |           |           |       |       | 70                     |              |
| 44 | Member Wind 180        | None     |       |           |           |       |       | 70                     |              |
| 45 | Member Wind 210        | None     |       |           |           |       |       | 70                     |              |
| 46 | Member Wind 225        | None     |       |           |           |       |       | 70                     |              |
| 47 | Member Wind 240        | None     |       |           |           |       |       | 70                     |              |
| 48 | Member Wind 270        | None     |       |           |           |       |       | 70                     |              |
| 49 | Member Wind 300        | None     |       |           |           |       |       | 70                     |              |
| 50 | Member Wind 315        | None     |       |           |           |       |       | 70                     |              |
| 51 | Member Wind 330        | None     |       |           |           |       |       | 70                     |              |
| 52 | Member Ice Dead        | None     |       |           |           |       |       | 35                     | 3            |
| 53 | Member Wind w/Ice 0    | None     |       |           |           |       |       | 70                     |              |
| 54 | Member Wind w/Ice 30   | None     |       |           |           |       |       | 70                     |              |
| 55 | Member Wind w/Ice 45   | None     |       |           |           |       |       | 70                     |              |
| 56 | Member Wind w/Ice 60   | None     |       |           |           |       |       | 70                     |              |
| 57 | Member Wind w/Ice 90   | None     |       |           |           |       |       | 70                     |              |
| 58 | Member Wind w/Ice 120  | None     |       |           |           |       |       | 70                     |              |
| 59 | Member Wind w/Ice 135  | None     |       |           |           |       |       | 70                     |              |
| 60 | Member Wind w/Ice 150  | None     |       |           |           |       |       | 70                     |              |
| 61 | Member Wind w/Ice 180  | None     |       |           |           |       |       | 70                     |              |
| 62 | Member Wind w/Ice 210  | None     |       |           |           |       |       | 70                     |              |
| 63 | Member Wind w/Ice 225  | None     |       |           |           |       |       | 70                     |              |
| 64 | Member Wind w/Ice 240  | None     |       |           |           |       |       | 70                     |              |
| 65 | Member Wind w/Ice 270  | None     |       |           |           |       |       | 70                     |              |
| 66 | Member Wind w/Ice 300  | None     |       |           |           |       |       | 70                     |              |
| 67 | Member Wind w/Ice 315  | None     |       |           |           |       |       | 70                     |              |
| 68 | Member Wind w/Ice 330  | None     |       |           |           |       |       | 70                     |              |
| 69 | LV-1                   | None     |       |           |           |       | 1     |                        |              |
| 70 | LV-2                   | None     |       |           |           |       | 1     |                        |              |
| 71 | LV-3                   | None     |       |           |           |       | 1     |                        |              |
| 72 | LV-4                   | None     |       |           |           |       | 1     |                        |              |
| 73 | LV-5                   | None     |       |           |           |       | 1     |                        |              |
| 74 | LV-6                   | None     |       |           |           |       | 1     |                        |              |
| 75 | LV-7                   | None     |       |           |           |       | 1     |                        |              |
| 76 | LV-8                   | None     |       |           |           |       | 1     |                        |              |
| 77 | LV-9                   | None     |       |           |           |       | 1     |                        |              |
| 78 | LV-10                  | None     |       |           |           |       |       |                        |              |
| 79 | LV-11                  | None     |       |           |           |       |       |                        |              |



**Basic Load Cases (Continued)**

|     | BLC Description             | Category | X ... | Y Gravity | Z Gravity | Joint | Point | Distributed Area(Me... | Surface(P... |
|-----|-----------------------------|----------|-------|-----------|-----------|-------|-------|------------------------|--------------|
| 80  | LV-12                       | None     |       |           |           |       |       |                        |              |
| 81  | LV-13                       | None     |       |           |           |       |       |                        |              |
| 82  | LV-14                       | None     |       |           |           |       |       |                        |              |
| 83  | LV-15                       | None     |       |           |           |       |       |                        |              |
| 84  | LM-1                        | None     |       |           |           |       | 1     |                        |              |
| 85  | LM-2                        | None     |       |           |           |       | 1     |                        |              |
| 86  | LM-3                        | None     |       |           |           |       | 1     |                        |              |
| 87  | LM-4                        | None     |       |           |           |       | 1     |                        |              |
| 88  | LM-5                        | None     |       |           |           |       | 1     |                        |              |
| 89  | LM-6                        | None     |       |           |           |       | 1     |                        |              |
| 90  | LM-7                        | None     |       |           |           |       | 1     |                        |              |
| 91  | LM-8                        | None     |       |           |           |       | 1     |                        |              |
| 92  | LM-9                        | None     |       |           |           |       | 1     |                        |              |
| 93  | LM-10                       | None     |       |           |           |       |       |                        |              |
| 94  | LM-11                       | None     |       |           |           |       |       |                        |              |
| 95  | LM-12                       | None     |       |           |           |       |       |                        |              |
| 96  | LM-13                       | None     |       |           |           |       |       |                        |              |
| 97  | LM-14                       | None     |       |           |           |       |       |                        |              |
| 98  | LM-15                       | None     |       |           |           |       |       |                        |              |
| 99  | BLC 35 Transient Area Loads | None     |       |           |           |       |       | 57                     |              |
| 100 | BLC 52 Transient Area Loads | None     |       |           |           |       |       | 57                     |              |

**Load Combinations**

|    | Description           | S... | PD... | SRSS | B... | Fa... | B... | Fa... | B... | Fa... | B... | Fa... | B... | Fa... | B... | Fa... | B... | Fa... | B... | Fa... |
|----|-----------------------|------|-------|------|------|-------|------|-------|------|-------|------|-------|------|-------|------|-------|------|-------|------|-------|
| 1  | 1.4D                  | Yes  | Y     |      | 1    | 1.4   | 35   | 1.4   |      |       |      |       |      |       |      |       |      |       |      |       |
| 2  | 0.9D + 1.6 (0-Wind)   | Yes  | Y     |      | 1    | .9    | 35   | .9    | 2    | 1.6   | 36   | 1.6   |      |       |      |       |      |       |      |       |
| 3  | 0.9D + 1.6 (30-Wind)  | Yes  | Y     |      | 1    | .9    | 35   | .9    | 3    | 1.6   | 37   | 1.6   |      |       |      |       |      |       |      |       |
| 4  | 0.9D + 1.6 (45-Wind)  | Yes  | Y     |      | 1    | .9    | 35   | .9    | 4    | 1.6   | 38   | 1.6   |      |       |      |       |      |       |      |       |
| 5  | 0.9D + 1.6 (60-Wind)  | Yes  | Y     |      | 1    | .9    | 35   | .9    | 5    | 1.6   | 39   | 1.6   |      |       |      |       |      |       |      |       |
| 6  | 0.9D + 1.6 (90-Wind)  | Yes  | Y     |      | 1    | .9    | 35   | .9    | 6    | 1.6   | 40   | 1.6   |      |       |      |       |      |       |      |       |
| 7  | 0.9D + 1.6 (120-Wind) | Yes  | Y     |      | 1    | .9    | 35   | .9    | 7    | 1.6   | 41   | 1.6   |      |       |      |       |      |       |      |       |
| 8  | 0.9D + 1.6 (135-Wind) | Yes  | Y     |      | 1    | .9    | 35   | .9    | 8    | 1.6   | 42   | 1.6   |      |       |      |       |      |       |      |       |
| 9  | 0.9D + 1.6 (150-Wind) | Yes  | Y     |      | 1    | .9    | 35   | .9    | 9    | 1.6   | 43   | 1.6   |      |       |      |       |      |       |      |       |
| 10 | 0.9D + 1.6 (180-Wind) | Yes  | Y     |      | 1    | .9    | 35   | .9    | 10   | 1.6   | 44   | 1.6   |      |       |      |       |      |       |      |       |
| 11 | 0.9D + 1.6 (210-Wind) | Yes  | Y     |      | 1    | .9    | 35   | .9    | 11   | 1.6   | 45   | 1.6   |      |       |      |       |      |       |      |       |
| 12 | 0.9D + 1.6 (225-Wind) | Yes  | Y     |      | 1    | .9    | 35   | .9    | 12   | 1.6   | 46   | 1.6   |      |       |      |       |      |       |      |       |
| 13 | 0.9D + 1.6 (240-Wind) | Yes  | Y     |      | 1    | .9    | 35   | .9    | 13   | 1.6   | 47   | 1.6   |      |       |      |       |      |       |      |       |
| 14 | 0.9D + 1.6 (270-Wind) | Yes  | Y     |      | 1    | .9    | 35   | .9    | 14   | 1.6   | 48   | 1.6   |      |       |      |       |      |       |      |       |
| 15 | 0.9D + 1.6 (300-Wind) | Yes  | Y     |      | 1    | .9    | 35   | .9    | 15   | 1.6   | 49   | 1.6   |      |       |      |       |      |       |      |       |
| 16 | 0.9D + 1.6 (315-Wind) | Yes  | Y     |      | 1    | .9    | 35   | .9    | 16   | 1.6   | 50   | 1.6   |      |       |      |       |      |       |      |       |
| 17 | 0.9D + 1.6 (330-Wind) | Yes  | Y     |      | 1    | .9    | 35   | .9    | 17   | 1.6   | 51   | 1.6   |      |       |      |       |      |       |      |       |
| 18 | 1.2D + 1.6 (0-Wind)   | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 2    | 1.6   | 36   | 1.6   |      |       |      |       |      |       |      |       |
| 19 | 1.2D + 1.6 (30-Wind)  | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 3    | 1.6   | 37   | 1.6   |      |       |      |       |      |       |      |       |
| 20 | 1.2D + 1.6 (45-Wind)  | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 4    | 1.6   | 38   | 1.6   |      |       |      |       |      |       |      |       |
| 21 | 1.2D + 1.6 (60-Wind)  | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 5    | 1.6   | 39   | 1.6   |      |       |      |       |      |       |      |       |
| 22 | 1.2D + 1.6 (90-Wind)  | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 6    | 1.6   | 40   | 1.6   |      |       |      |       |      |       |      |       |
| 23 | 1.2D + 1.6 (120-Wind) | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 7    | 1.6   | 41   | 1.6   |      |       |      |       |      |       |      |       |
| 24 | 1.2D + 1.6 (135-Wind) | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 8    | 1.6   | 42   | 1.6   |      |       |      |       |      |       |      |       |
| 25 | 1.2D + 1.6 (150-Wind) | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 9    | 1.6   | 43   | 1.6   |      |       |      |       |      |       |      |       |
| 26 | 1.2D + 1.6 (180-Wind) | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 10   | 1.6   | 44   | 1.6   |      |       |      |       |      |       |      |       |
| 27 | 1.2D + 1.6 (210-Wind) | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 11   | 1.6   | 45   | 1.6   |      |       |      |       |      |       |      |       |
| 28 | 1.2D + 1.6 (225-Wind) | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 12   | 1.6   | 46   | 1.6   |      |       |      |       |      |       |      |       |
| 29 | 1.2D + 1.6 (240-Wind) | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 13   | 1.6   | 47   | 1.6   |      |       |      |       |      |       |      |       |
| 30 | 1.2D + 1.6 (270-Wind) | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 14   | 1.6   | 48   | 1.6   |      |       |      |       |      |       |      |       |
| 31 | 1.2D + 1.6 (300-Wind) | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 15   | 1.6   | 49   | 1.6   |      |       |      |       |      |       |      |       |



Company : Ramaker & Associates, Inc.  
 Designer : TJS  
 Job Number : 28753  
 Model Name : CT60XC001

Apr 17, 2019  
 3:40 PM  
 Checked By: \_\_\_\_\_

**Load Combinations (Continued)**

|    | Description                 | S... | PD... | SRSS | B... | Fa... | B... | Fa... | B... | Fa... | B... | Fa... | B... | Fa... | B... | Fa... | B... | Fa... | B... | Fa... | B... | Fa... |
|----|-----------------------------|------|-------|------|------|-------|------|-------|------|-------|------|-------|------|-------|------|-------|------|-------|------|-------|------|-------|
| 32 | 1.2D + 1.6 (315-Wind)       | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 16   | 1.6   | 50   | 1.6   |      |       |      |       |      |       |      |       |      |       |
| 33 | 1.2D + 1.6 (330-Wind)       | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 17   | 1.6   | 51   | 1.6   |      |       |      |       |      |       |      |       |      |       |
| 34 | 1.2D + 1.0Di + 1.0 (0-Wi... | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 18   | 1     | 52   | 1     | 19   | 1     | 53   | 1     |      |       |      |       |      |       |
| 35 | 1.2D + 1.0Di + 1.0 (30-W... | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 18   | 1     | 52   | 1     | 20   | 1     | 54   | 1     |      |       |      |       |      |       |
| 36 | 1.2D + 1.0Di + 1.0 (45-W... | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 18   | 1     | 52   | 1     | 21   | 1     | 55   | 1     |      |       |      |       |      |       |
| 37 | 1.2D + 1.0Di + 1.0 (60-W... | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 18   | 1     | 52   | 1     | 22   | 1     | 56   | 1     |      |       |      |       |      |       |
| 38 | 1.2D + 1.0Di + 1.0 (90-W... | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 18   | 1     | 52   | 1     | 23   | 1     | 57   | 1     |      |       |      |       |      |       |
| 39 | 1.2D + 1.0Di + 1.0 (120-... | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 18   | 1     | 52   | 1     | 24   | 1     | 58   | 1     |      |       |      |       |      |       |
| 40 | 1.2D + 1.0Di + 1.0 (135-... | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 18   | 1     | 52   | 1     | 25   | 1     | 59   | 1     |      |       |      |       |      |       |
| 41 | 1.2D + 1.0Di + 1.0 (150-... | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 18   | 1     | 52   | 1     | 26   | 1     | 60   | 1     |      |       |      |       |      |       |
| 42 | 1.2D + 1.0Di + 1.0 (180-... | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 18   | 1     | 52   | 1     | 27   | 1     | 61   | 1     |      |       |      |       |      |       |
| 43 | 1.2D + 1.0Di + 1.0 (210-... | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 18   | 1     | 52   | 1     | 28   | 1     | 62   | 1     |      |       |      |       |      |       |
| 44 | 1.2D + 1.0Di + 1.0 (225-... | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 18   | 1     | 52   | 1     | 29   | 1     | 63   | 1     |      |       |      |       |      |       |
| 45 | 1.2D + 1.0Di + 1.0 (240-... | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 18   | 1     | 52   | 1     | 30   | 1     | 64   | 1     |      |       |      |       |      |       |
| 46 | 1.2D + 1.0Di + 1.0 (270-... | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 18   | 1     | 52   | 1     | 31   | 1     | 65   | 1     |      |       |      |       |      |       |
| 47 | 1.2D + 1.0Di + 1.0 (300-... | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 18   | 1     | 52   | 1     | 32   | 1     | 66   | 1     |      |       |      |       |      |       |
| 48 | 1.2D + 1.0Di + 1.0 (315-... | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 18   | 1     | 52   | 1     | 33   | 1     | 67   | 1     |      |       |      |       |      |       |
| 49 | 1.2D + 1.0Di + 1.0 (330-... | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 18   | 1     | 52   | 1     | 34   | 1     | 68   | 1     |      |       |      |       |      |       |
| 50 | 1.2D + 1.5LV-1              | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 69   | 1.5   |      |       |      |       |      |       |      |       |      |       |      |       |
| 51 | 1.2D + 1.5LV-2              | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 70   | 1.5   |      |       |      |       |      |       |      |       |      |       |      |       |
| 52 | 1.2D + 1.5LV-3              | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 71   | 1.5   |      |       |      |       |      |       |      |       |      |       |      |       |
| 53 | 1.2D + 1.5LV-4              | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 72   | 1.5   |      |       |      |       |      |       |      |       |      |       |      |       |
| 54 | 1.2D + 1.5LV-5              | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 73   | 1.5   |      |       |      |       |      |       |      |       |      |       |      |       |
| 55 | 1.2D + 1.5LV-6              | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 74   | 1.5   |      |       |      |       |      |       |      |       |      |       |      |       |
| 56 | 1.2D + 1.5LV-7              | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 75   | 1.5   |      |       |      |       |      |       |      |       |      |       |      |       |
| 57 | 1.2D + 1.5LV-8              | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 76   | 1.5   |      |       |      |       |      |       |      |       |      |       |      |       |
| 58 | 1.2D + 1.5LV-9              | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 77   | 1.5   |      |       |      |       |      |       |      |       |      |       |      |       |
| 59 | 1.2D + 1.5LV-10             | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 78   | 1.5   |      |       |      |       |      |       |      |       |      |       |      |       |
| 60 | 1.2D + 1.5LV-11             | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 79   | 1.5   |      |       |      |       |      |       |      |       |      |       |      |       |
| 61 | 1.2D + 1.5LV-12             | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 80   | 1.5   |      |       |      |       |      |       |      |       |      |       |      |       |
| 62 | 1.2D + 1.5LV-13             | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 81   | 1.5   |      |       |      |       |      |       |      |       |      |       |      |       |
| 63 | 1.2D + 1.5LV-14             | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 82   | 1.5   |      |       |      |       |      |       |      |       |      |       |      |       |
| 64 | 1.2D + 1.5LV-15             | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 83   | 1.5   |      |       |      |       |      |       |      |       |      |       |      |       |
| 65 | 1.2D + 1.5LM-1 + Mainte...  | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 84   | 1.5   | 2    | .113  | 36   | .113  |      |       |      |       |      |       |      |       |
| 66 | 1.2D + 1.5LM-1 + Mainte...  | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 84   | 1.5   | 3    | .113  | 37   | .113  |      |       |      |       |      |       |      |       |
| 67 | 1.2D + 1.5LM-1 + Mainte...  | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 84   | 1.5   | 4    | .113  | 38   | .113  |      |       |      |       |      |       |      |       |
| 68 | 1.2D + 1.5LM-1 + Mainte...  | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 84   | 1.5   | 5    | .113  | 39   | .113  |      |       |      |       |      |       |      |       |
| 69 | 1.2D + 1.5LM-1 + Mainte...  | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 84   | 1.5   | 6    | .113  | 40   | .113  |      |       |      |       |      |       |      |       |
| 70 | 1.2D + 1.5LM-1 + Mainte...  | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 84   | 1.5   | 7    | .113  | 41   | .113  |      |       |      |       |      |       |      |       |
| 71 | 1.2D + 1.5LM-1 + Mainte...  | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 84   | 1.5   | 8    | .113  | 42   | .113  |      |       |      |       |      |       |      |       |
| 72 | 1.2D + 1.5LM-1 + Mainte...  | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 84   | 1.5   | 9    | .113  | 43   | .113  |      |       |      |       |      |       |      |       |
| 73 | 1.2D + 1.5LM-1 + Mainte...  | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 84   | 1.5   | 10   | .113  | 44   | .113  |      |       |      |       |      |       |      |       |
| 74 | 1.2D + 1.5LM-1 + Mainte...  | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 84   | 1.5   | 11   | .113  | 45   | .113  |      |       |      |       |      |       |      |       |
| 75 | 1.2D + 1.5LM-1 + Mainte...  | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 84   | 1.5   | 12   | .113  | 46   | .113  |      |       |      |       |      |       |      |       |
| 76 | 1.2D + 1.5LM-1 + Mainte...  | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 84   | 1.5   | 13   | .113  | 47   | .113  |      |       |      |       |      |       |      |       |
| 77 | 1.2D + 1.5LM-1 + Mainte...  | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 84   | 1.5   | 14   | .113  | 48   | .113  |      |       |      |       |      |       |      |       |
| 78 | 1.2D + 1.5LM-1 + Mainte...  | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 84   | 1.5   | 15   | .113  | 49   | .113  |      |       |      |       |      |       |      |       |
| 79 | 1.2D + 1.5LM-1 + Mainte...  | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 84   | 1.5   | 16   | .113  | 50   | .113  |      |       |      |       |      |       |      |       |
| 80 | 1.2D + 1.5LM-1 + Mainte...  | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 84   | 1.5   | 17   | .113  | 51   | .113  |      |       |      |       |      |       |      |       |
| 81 | 1.2D + 1.5LM-2 + Mainte...  | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 85   | 1.5   | 2    | .113  | 36   | .113  |      |       |      |       |      |       |      |       |
| 82 | 1.2D + 1.5LM-2 + Mainte...  | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 85   | 1.5   | 3    | .113  | 37   | .113  |      |       |      |       |      |       |      |       |
| 83 | 1.2D + 1.5LM-2 + Mainte...  | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 85   | 1.5   | 4    | .113  | 38   | .113  |      |       |      |       |      |       |      |       |
| 84 | 1.2D + 1.5LM-2 + Mainte...  | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 85   | 1.5   | 5    | .113  | 39   | .113  |      |       |      |       |      |       |      |       |
| 85 | 1.2D + 1.5LM-2 + Mainte...  | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 85   | 1.5   | 6    | .113  | 40   | .113  |      |       |      |       |      |       |      |       |
| 86 | 1.2D + 1.5LM-2 + Mainte...  | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 85   | 1.5   | 7    | .113  | 41   | .113  |      |       |      |       |      |       |      |       |
| 87 | 1.2D + 1.5LM-2 + Mainte...  | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 85   | 1.5   | 8    | .113  | 42   | .113  |      |       |      |       |      |       |      |       |
| 88 | 1.2D + 1.5LM-2 + Mainte...  | Yes  | Y     |      | 1    | 1.2   | 35   | 1.2   | 85   | 1.5   | 9    | .113  | 43   | .113  |      |       |      |       |      |       |      |       |















Company : Ramaker & Associates, Inc.  
 Designer : TJS  
 Job Number : 28753  
 Model Name : CT60XC001

Apr 17, 2019  
 3:40 PM  
 Checked By: \_\_\_\_\_

**Envelope Joint Reactions (Continued)**

| Joint | X [lb]        | LC | Y [lb]   | LC | Z [lb]    | LC | MX [lb-ft] | LC | MY [lb-ft] | LC | MZ [lb-ft] | LC |
|-------|---------------|----|----------|----|-----------|----|------------|----|------------|----|------------|----|
| 8     | min -3917.388 | 22 | 2039.484 | 7  | -3917.617 | 26 |            |    |            |    |            |    |

**Envelope AISC 14th(360-10): LRFD Steel Code Checks**

| Member | Shape | Code Ch... | Loc[ft] | LC    | Shear ... | Loc[ft] | Dir    | LC | phi*Pnc [...] | phi*Pnt [...] | phi*Mn y... | phi*Mn z... | Cb  | Eqn   |
|--------|-------|------------|---------|-------|-----------|---------|--------|----|---------------|---------------|-------------|-------------|-----|-------|
| 1      | TH1   | PIPE 2.0   | .192    | 6.25  | 24        | .015    | 6.25   | 23 | 6295.423      | 32130         | 1871.625    | 1871.625    | 1.7 | H1-1b |
| 2      | TH3   | PIPE 2.0   | .166    | 6.25  | 19        | .013    | 6.25   | 34 | 6295.422      | 32130         | 1871.625    | 1871.625    | 1.7 | H1-1b |
| 3      | TH2   | PIPE 2.0   | .190    | 6.25  | 26        | .025    | 12.109 | 31 | 6295.422      | 32130         | 1871.625    | 1871.625    | 1.7 | H1-1b |
| 4      | SA2   | HSS4X4X4   | .396    | 0     | 43        | .102    | 0      | y  | 1.97795.86    | 109188        | 12663       | 12663       | 3.0 | H1-1b |
| 5      | SA1   | HSS4X4X4   | .405    | 0     | 38        | .104    | 0      | y  | 1.97795.86    | 109188        | 12663       | 12663       | 3.0 | H1-1b |
| 6      | SA3   | HSS4X4X4   | .452    | 0     | 49        | .102    | 0      | y  | 1.97795.86    | 109188        | 12663       | 12663       | 3.0 | H1-1b |
| 7      | PL2   | PL 6x1/2   | .145    | .644  | 22        | .088    | .47    | y  | 1.53116.305   | 97200         | 1012.5      | 12150       | 1.3 | H1-1b |
| 8      | PL1   | PL 6x1/2   | .146    | .644  | 33        | .086    | .47    | y  | 1.53116.305   | 97200         | 1012.5      | 12150       | 1.3 | H1-1b |
| 9      | PL3   | PL 6x1/2   | .148    | .644  | 28        | .090    | .819   | y  | 2.53116.305   | 97200         | 1012.5      | 12150       | 1.3 | H1-1b |
| 10     | B2    | L2.5x2.5x4 | .112    | 1.302 | 25        | .139    | 0      | z  | 2936482.195   | 38556         | 1113.554    | 2537.388    | 1.7 | H2-1  |
| 11     | B1    | L2.5x2.5x4 | .140    | 0     | 32        | .116    | 0      | z  | 2236482.195   | 38556         | 1113.554    | 2537.388    | 1.7 | H2-1  |
| 12     | B3    | L2.5x2.5x4 | .240    | 1.302 | 31        | .220    | 0      | y  | 1836482.195   | 38556         | 1113.554    | 2537.388    | 1.7 | H2-1  |
| 13     | GS3   | L2x2x3     | .155    | 4.138 | 9         | .009    | 4.138  | y  | 349921.867    | 23392.8       | 557.717     | 1197.778    | 1.7 | H2-1  |
| 14     | GS2   | L2x2x3     | .171    | 4.138 | 6         | .009    | 4.138  | z  | 459921.867    | 23392.8       | 557.717     | 1213.665    | 1.7 | H2-1  |
| 15     | GS1   | L2x2x3     | .157    | 0     | 3         | .010    | 0      | z  | 459921.867    | 23392.8       | 557.717     | 1186.734    | 1.7 | H2-1  |
| 16     | GS6   | L2x2x3     | .171    | 4.138 | 17        | .009    | 4.138  | z  | 409921.867    | 23392.8       | 557.717     | 1217.055    | 1.7 | H2-1  |
| 17     | GS5   | L2x2x3     | .143    | 0     | 14        | .010    | 0      | z  | 409921.867    | 23392.8       | 557.717     | 1186.379    | 1.7 | H2-1  |
| 18     | GS4   | L2x2x3     | .171    | 0     | 11        | .010    | 0      | y  | 349921.867    | 23392.8       | 557.717     | 1209.417    | 1.7 | H2-1  |
| 19     | CB4   | HSS4X4X4   | .196    | 0     | 41        | .066    | 2.261  | y  | 36106586.000  | 109188        | 12663       | 12663       | 1.7 | H1-1b |
| 20     | CB3   | HSS4X4X4   | .198    | 2.713 | 37        | .058    | .452   | y  | 42106586.000  | 109188        | 12663       | 12663       | 1.7 | H1-1b |
| 21     | CB2   | HSS4X4X4   | .200    | 0     | 46        | .071    | 2.261  | y  | 47106586.000  | 109188        | 12663       | 12663       | 1.7 | H1-1b |
| 22     | CB1   | HSS4X4X4   | .205    | 2.713 | 47        | .061    | .452   | y  | 38106586.000  | 109188        | 12663       | 12663       | 1.7 | H1-1b |
| 23     | CB6   | HSS4X4X4   | .214    | 2.713 | 41        | .071    | .452   | y  | 41106586.000  | 109188        | 12663       | 12663       | 1.7 | H1-1b |
| 24     | CB5   | HSS4X4X4   | .212    | 0     | 42        | .068    | 2.261  | y  | 48106586.000  | 109188        | 12663       | 12663       | 1.7 | H1-1b |
| 25     | BH1   | PIPE 3.0   | .173    | 8.073 | 45        | .069    | 4.297  | 35 | 28250.555     | 65205         | 5748.75     | 5748.75     | 3.0 | H1-1b |
| 26     | BH3   | PIPE 3.0   | .169    | 8.073 | 34        | .072    | 8.203  | 29 | 28250.554     | 65205         | 5748.75     | 5748.75     | 2.0 | H1-1b |
| 27     | BH2   | PIPE 3.0   | .173    | 8.073 | 45        | .066    | 8.203  | 40 | 28250.554     | 65205         | 5748.75     | 5748.75     | 2.0 | H1-1b |
| 28     | MPC1  | PIPE 2.0   | .249    | 4     | 47        | .085    | 4      | 26 | 14916.096     | 32130         | 1871.625    | 1871.625    | 1.7 | H1-1b |
| 29     | MPC3  | PIPE 2.0   | .333    | 4     | 33        | .088    | 4      | 26 | 14916.096     | 32130         | 1871.625    | 1871.625    | 1.7 | H1-1b |
| 30     | MPB1  | PIPE 2.0   | .237    | 4     | 29        | .076    | 4      | 21 | 14916.096     | 32130         | 1871.625    | 1871.625    | 1.7 | H1-1b |
| 31     | MPB3  | PIPE 2.0   | .281    | 4     | 29        | .088    | 4      | 20 | 14916.096     | 32130         | 1871.625    | 1871.625    | 1.7 | H1-1b |
| 32     | MPA1  | PIPE 2.0   | .282    | 7     | 23        | .124    | 7      | 31 | 14916.096     | 32130         | 1871.625    | 1871.625    | 1.7 | H1-1b |
| 33     | MPA3  | PIPE 2.0   | .287    | 4     | 25        | .103    | 4      | 31 | 14916.096     | 32130         | 1871.625    | 1871.625    | 1.7 | H1-1b |
| 34     | MPC2  | PIPE 2.0   | .732    | 4     | 26        | .071    | 4      | 9  | 14916.096     | 32130         | 1871.625    | 1871.625    | 1.7 | H1-1b |
| 35     | MPA2  | PIPE 2.0   | .731    | 4     | 31        | .075    | 4      | 32 | 14916.096     | 32130         | 1871.625    | 1871.625    | 1.7 | H1-1b |
| 36     | MPB2  | PIPE 2.0   | .731    | 4     | 21        | .054    | 4      | 6  | 14916.096     | 32130         | 1871.625    | 1871.625    | 1.7 | H1-1b |

**Wind Load on Antennas TIA-222-G**

$$q_z = 0.00256 K_z K_{zt} K_d V^2 I$$

$$F = q_z G_h C_a A_a$$

|                   |          |  |
|-------------------|----------|--|
| Occupancy :       | II       | Classification of Structures (Table 2-1)               |
| Exposure :        | C        | Exposure Category                                      |
| V :               | 93 mph   | Basic Wind Speed (Annex B)                             |
| z :               | 67 ft    | Height above ground level to the center of the antenna |
| I :               | 1.00     | Importance Factor (Table 2-3)                          |
| K <sub>z</sub> :  | 1.16     | Velocity Pressure Coefficient (2.6.5.2)                |
| K <sub>zt</sub> : | 1.00     | Topographic Factor (2.6.6.4)                           |
| K <sub>d</sub> :  | 0.95     | Wind Direction Probability Factor (Table 2-2)          |
| q <sub>z</sub> :  | 24.5 psf | Velocity Pressure at Height z                          |
| G <sub>h</sub> :  | 1.00     | Strength Design of Appurtenances and their Connections |

**Mount & Antenna Wind Loads**

| Appurtenance        | Height<br><i>in</i> | Width<br><i>in</i> | h/D  | Shape | C <sub>a</sub> | A <sub>a</sub><br><i>sq ft</i> | Force<br><i>lb</i> | Force<br><i>plf</i> |
|---------------------|---------------------|--------------------|------|-------|----------------|--------------------------------|--------------------|---------------------|
| ETCR-654L12H6       | 84.9                | 21.0               | 4.0  | Flat  | 1.269          | 12.38                          | 384.3              |                     |
| 1900MHz 4x45W RRH   | 25.1                | 11.1               | 2.3  | Flat  | 1.200          | 1.93                           | 56.8               |                     |
| 800MHz 2x50W RRH    | 19.0                | 13.0               | 1.5  | Flat  | 1.200          | 1.72                           | 50.4               |                     |
| FZHN                | 14.6                | 16.6               | 1.1  | Flat  | 1.200          | 1.68                           | 49.4               |                     |
| Pipe2STD x 12.5 ft  | 150.0               | 2.4                | 63.2 | Round | 1.200          | 2.47                           | 72.6               | 5.8                 |
| Pipe3STD x 12.5 ft  | 150.0               | 3.5                | 42.9 | Round | 1.200          | 3.65                           | 107.1              | 8.6                 |
| Pipe2STD x 8 ft     | 96.0                | 2.4                | 40.4 | Round | 1.200          | 1.58                           | 46.5               | 5.8                 |
| HSS4X4X1/4 x 5.8 ft | 69.6                | 4.0                | 17.4 | Flat  | 1.747          | 1.93                           | 82.6               | 14.2                |
| HSS4X4X1/4 x 2.7 ft | 32.4                | 4.0                | 8.1  | Flat  | 1.437          | 0.90                           | 31.6               | 11.7                |
| L2X2X3/16 x 4.1 ft  | 49.2                | 2.0                | 24.6 | Flat  | 1.987          | 0.68                           | 33.2               | 8.1                 |
| PL 6x1/2 x 1.3 ft   | 15.6                | 6.0                | 2.6  | Flat  | 1.204          | 0.65                           | 19.2               | 14.7                |
| Pipe2STD x 8 ft     | 96.0                | 2.4                | 40.4 | Round | 1.200          | 1.58                           | 46.5               | 5.8                 |
| SR 1 x 5 ft         | 60.0                | 1.0                | 60.0 | Round | 1.200          | 0.42                           | 12.2               | 2.4                 |



**Wind Load on Antennas TIA-222-G**

$$q_z = 0.00256 K_z K_{zt} K_d V^2 I$$

$$F = q_z G_h C_a A_a$$

|                   |          |  |
|-------------------|----------|--|
| Occupancy :       | II       | Classification of Structures (Table 2-1)               |
| Exposure :        | C        | Exposure Category                                      |
| V :               | 93 mph   | Basic Wind Speed (Annex B)                             |
| z :               | 67 ft    | Height above ground level to the center of the antenna |
| I :               | 1.00     | Importance Factor (Table 2-3)                          |
| K <sub>z</sub> :  | 1.16     | Velocity Pressure Coefficient (2.6.5.2)                |
| K <sub>zt</sub> : | 1.00     | Topographic Factor (2.6.6.4)                           |
| K <sub>d</sub> :  | 0.95     | Wind Direction Probability Factor (Table 2-2)          |
| q <sub>z</sub> :  | 24.5 psf | Velocity Pressure at Height z                          |
| G <sub>h</sub> :  | 1.00     | Strength Design of Appurtenances and their Connections |

**Mount & Antenna Wind Loads**

| Appurtenance        | Height<br><i>in</i> | Depth<br><i>in</i> | h/D  | Shape | C <sub>a</sub> | A <sub>a</sub><br><i>sq ft</i> | Force<br><i>lb</i> | Force<br><i>plf</i> |
|---------------------|---------------------|--------------------|------|-------|----------------|--------------------------------|--------------------|---------------------|
| ETCR-654L12H6       | 84.9                | 6.3                | 13.5 | Flat  | 1.616          | 3.71                           | 146.9              |                     |
| 1900MHz 4x45W RRH   | 25.1                | 10.7               | 2.3  | Flat  | 1.200          | 1.86                           | 54.7               |                     |
| 800MHz 2x50W RRH    | 19.0                | 12.2               | 1.6  | Flat  | 1.200          | 1.61                           | 47.3               |                     |
| FZHN                | 14.6                | 4.9                | 3.0  | Flat  | 1.221          | 0.50                           | 14.8               |                     |
| Pipe2STD x 12.5 ft  | 150.0               | 2.4                | 63.2 | Round | 1.200          | 2.47                           | 72.6               | 5.8                 |
| Pipe3STD x 12.5 ft  | 150.0               | 3.5                | 42.9 | Round | 1.200          | 3.65                           | 107.1              | 8.6                 |
| Pipe2STD x 8 ft     | 96.0                | 2.4                | 40.4 | Round | 1.200          | 1.58                           | 46.5               | 5.8                 |
| HSS4X4X1/4 x 5.8 ft | 69.6                | 3.3                | 21.1 | Flat  | 1.870          | 1.60                           | 73.0               | 12.6                |
| HSS4X4X1/4 x 2.7 ft | 32.4                | 3.3                | 9.8  | Flat  | 1.494          | 0.74                           | 27.1               | 10.1                |
| L2X2X3/16 x 4.1 ft  | 49.2                | 2.0                | 24.6 | Flat  | 1.987          | 0.68                           | 33.2               | 8.1                 |
| PL 6x1/2 x 1.3 ft   | 15.6                | 0.5                | 31.2 | Flat  | 2.000          | 0.05                           | 2.7                | 2.0                 |
| Pipe2STD x 8 ft     | 96.0                | 2.4                | 40.4 | Round | 1.200          | 1.58                           | 46.5               | 5.8                 |
| SR 1 x 5 ft         | 60.0                | 1.0                | 60.0 | Round | 1.200          | 0.42                           | 12.2               | 2.4                 |



**Ice Wind Load on Antennas TIA-222-G**

$$q_z = 0.00256 K_z K_{zt} K_d V^2 I$$

$$F = q_z G_h C_a A_a$$

|             |          |  |
|-------------|----------|--|
| Occupancy : | II       | Classification of Structures (Table 2-1)               |
| Exposure :  | C        | Exposure Category                                      |
| $V_i$ :     | 50 mph   | Basic Wind Speed (Annex B)                             |
| $z$ :       | 67 ft    | Height above ground level to the center of the antenna |
| $I$ :       | 1.00     | Importance Factor (Table 2-3)                          |
| $K_z$ :     | 1.16     | Velocity Pressure Coefficient (2.6.5.2)                |
| $K_{zt}$ :  | 1.00     | Topographic Factor (2.6.6.4)                           |
| $K_d$ :     | 0.95     | Wind Direction Probability Factor (Table 2-2)          |
| $q_z$ :     | 7.07 psf | Velocity Pressure at Height $z$                        |
| $G_h$ :     | 1.00     | Strength Design of Appurtenances and their Connections |
| $t_{iz}$ :  | 1.61 in  | Design Thickness of Radial Ice at Height $z$ (2.6.8)   |

**Mount & Antenna Ice Wind Loads**

| Appurtenance        | Height<br><i>in</i> | Width<br><i>in</i> | h/D  | Shape | $C_a$ | $A_a$<br><i>sq ft</i> | Force<br><i>lb</i> | Force<br><i>plf</i> |
|---------------------|---------------------|--------------------|------|-------|-------|-----------------------|--------------------|---------------------|
| ETCR-654L12H6       | 88.1                | 24.2               | 3.6  | Flat  | 1.251 | 14.82                 | 131.1              |                     |
| 1900MHz 4x45W RRH   | 28.3                | 14.3               | 2.0  | Flat  | 1.200 | 2.82                  | 23.9               |                     |
| 800MHz 2x50W RRH    | 22.2                | 16.2               | 1.4  | Flat  | 1.200 | 2.50                  | 21.2               |                     |
| FZHN                | 17.8                | 19.8               | 1.1  | Flat  | 1.200 | 2.45                  | 20.8               |                     |
| Pipe2STD x 12.5 ft  | 153.2               | 5.6                | 27.4 | Round | 1.200 | 5.95                  | 50.5               | 4.0                 |
| Pipe3STD x 12.5 ft  | 153.2               | 6.7                | 22.8 | Round | 1.151 | 7.15                  | 58.2               | 4.6                 |
| Pipe2STD x 8 ft     | 99.2                | 5.6                | 17.7 | Round | 1.039 | 3.86                  | 28.3               | 3.4                 |
| HSS4X4X1/4 x 5.8 ft | 72.8                | 7.2                | 10.1 | Flat  | 1.503 | 3.65                  | 38.8               | 6.4                 |
| HSS4X4X1/4 x 2.7 ft | 35.6                | 7.2                | 4.9  | Flat  | 1.308 | 1.79                  | 16.5               | 5.6                 |
| L2X2X3/16 x 4.1 ft  | 52.4                | 5.2                | 10.0 | Flat  | 1.501 | 1.90                  | 20.2               | 4.6                 |
| PL 6x1/2 x 1.3 ft   | 18.8                | 9.2                | 2.0  | Flat  | 1.200 | 1.21                  | 10.2               | 6.5                 |
| Pipe2STD x 8 ft     | 99.2                | 5.6                | 17.7 | Round | 1.039 | 3.86                  | 28.3               | 3.4                 |
| SR 1 x 5 ft         | 63.2                | 4.2                | 15.0 | Round | 0.977 | 1.85                  | 12.8               | 2.4                 |

**Ice Wind Load on Antennas TIA-222-G**

$$q_z = 0.00256 K_z K_{zt} K_d V^2 I$$

$$F = q_z G_h C_a A_a$$

|             |          |  |
|-------------|----------|--|
| Occupancy : | II       | Classification of Structures (Table 2-1)               |
| Exposure :  | C        | Exposure Category                                      |
| $V_i$ :     | 50 mph   | Basic Wind Speed (Annex B)                             |
| $z$ :       | 67 ft    | Height above ground level to the center of the antenna |
| $I$ :       | 1.00     | Importance Factor (Table 2-3)                          |
| $K_z$ :     | 1.16     | Velocity Pressure Coefficient (2.6.5.2)                |
| $K_{zt}$ :  | 1.00     | Topographic Factor (2.6.6.4)                           |
| $K_d$ :     | 0.95     | Wind Direction Probability Factor (Table 2-2)          |
| $q_z$ :     | 7.07 psf | Velocity Pressure at Height $z$                        |
| $G_h$ :     | 1.00     | Strength Design of Appurtenances and their Connections |
| $t_{iz}$ :  | 1.61 in  | Design Thickness of Radial Ice at Height $z$ (2.6.8)   |

**Mount & Antenna Ice Wind Loads**

| Appurtenance        | Height<br><i>in</i> | Depth<br><i>in</i> | h/D  | Shape | $C_a$ | $A_a$<br><i>sq ft</i> | Force<br><i>lb</i> | Force<br><i>plf</i> |
|---------------------|---------------------|--------------------|------|-------|-------|-----------------------|--------------------|---------------------|
| ETCR-654L12H6       | 88.1                | 9.5                | 9.3  | Flat  | 1.475 | 5.83                  | 60.8               |                     |
| 1900MHz 4x45W RRH   | 28.3                | 13.9               | 2.0  | Flat  | 1.200 | 2.74                  | 23.2               |                     |
| 800MHz 2x50W RRH    | 22.2                | 15.4               | 1.4  | Flat  | 1.200 | 2.38                  | 20.2               |                     |
| FZHN                | 17.8                | 8.1                | 2.2  | Flat  | 1.200 | 1.00                  | 8.5                |                     |
| Pipe2STD x 12.5 ft  | 153.2               | 5.6                | 27.4 | Round | 1.200 | 5.95                  | 50.5               | 4.0                 |
| Pipe3STD x 12.5 ft  | 153.2               | 6.7                | 22.8 | Round | 1.151 | 7.15                  | 58.2               | 4.6                 |
| Pipe2STD x 8 ft     | 99.2                | 5.6                | 17.7 | Round | 1.039 | 3.86                  | 28.3               | 3.4                 |
| HSS4X4X1/4 x 5.8 ft | 72.8                | 6.5                | 11.2 | Flat  | 1.539 | 3.30                  | 35.9               | 5.9                 |
| HSS4X4X1/4 x 2.7 ft | 35.6                | 6.5                | 5.5  | Flat  | 1.332 | 1.61                  | 15.2               | 5.1                 |
| L2X2X3/16 x 4.1 ft  | 52.4                | 5.2                | 10.0 | Flat  | 1.501 | 1.90                  | 20.2               | 4.6                 |
| PL 6x1/2 x 1.3 ft   | 18.8                | 3.7                | 5.1  | Flat  | 1.314 | 0.49                  | 4.5                | 2.9                 |
| Pipe2STD x 8 ft     | 99.2                | 5.6                | 17.7 | Round | 1.039 | 3.86                  | 28.3               | 3.4                 |
| SR 1 x 5 ft         | 63.2                | 4.2                | 15.0 | Round | 0.977 | 1.85                  | 12.8               | 2.4                 |

**Ice Load on Antennas TIA-222-G**

|                   |      |     |  |
|-------------------|------|-----|--|
| Ice Weight :      | 56   | pcf | Ice Density  |
| t <sub>i</sub> :  | 0.75 |     | Design Ice Thickness                                   |
| Occupancy :       | II   |     | Classification of Structures (Table 2-1)               |
| Exposure :        | C    |     | Exposure Category                                      |
| V <sub>i</sub> :  | 50   | mph | Basic Wind Speed (Annex B)                             |
| z :               | 67   | ft  | Height above ground level to the center of the antenna |
| I :               | 1.00 |     | Importance Factor (Table 2-3)                          |
| K <sub>iz</sub> : | 1.07 |     | Height Escalation Factor for Ice Thickness             |
| K <sub>zt</sub> : | 1.00 |     | Topographic Factor (2.6.6.4)                           |
| t <sub>iz</sub> : | 1.61 | in  | Design Thickness of Radial Ice at Height z (2.6.8)     |

Platform Grating : Expanded

Ice Load : 7.5 psf

**Mount & Antenna Ice Wind Loads**

| Appurtenance        | Height    | Width     | Depth     | Diam.     | Area         | Perim.    | Ice Weight |            |
|---------------------|-----------|-----------|-----------|-----------|--------------|-----------|------------|------------|
|                     | <i>in</i> | <i>in</i> | <i>in</i> | <i>in</i> | <i>sq in</i> | <i>in</i> | <i>lb</i>  | <i>plf</i> |
| ETCR-654L12H6       | 88.1      | 24.2      | 9.5       | 21.92     | 119.04       | 61.04     | 327.5      |            |
| 1900MHz 4x45W RRH   | 28.3      | 14.3      | 13.9      | 15.41     | 86.09        | 50.02     | 70.0       |            |
| 800MHz 2x50W RRH    | 22.2      | 16.2      | 15.4      | 17.83     | 98.32        | 56.84     | 60.5       |            |
| FZHN                | 17.8      | 19.8      | 8.1       | 17.31     | 95.69        | 49.44     | 45.3       |            |
| Pipe2STD x 12.5 ft  | 153.2     | 5.6       | 5.6       | 2.38      | 20.16        | 12.52     | 98.0       | 7.8        |
| Pipe3STD x 12.5 ft  | 153.2     | 6.7       | 6.7       | 3.50      | 25.85        | 16.05     | 125.6      | 10.1       |
| Pipe2STD x 8 ft     | 99.2      | 5.6       | 5.6       | 2.38      | 20.16        | 12.52     | 62.7       | 7.8        |
| HSS4X4X1/4 x 5.8 ft | 72.8      | 7.2       | 6.5       | 5.19      | 34.40        | 26.42     | 77.6       | 13.4       |
| HSS4X4X1/4 x 2.7 ft | 35.6      | 7.2       | 6.5       | 5.19      | 34.40        | 26.42     | 36.1       | 13.4       |
| L2X2X3/16 x 4.1 ft  | 52.4      | 5.2       | 5.2       | 2.83      | 22.45        | 14.44     | 35.8       | 8.7        |
| PL 6x1/2 x 1.3 ft   | 18.8      | 9.2       | 3.7       | 6.02      | 38.60        | 19.44     | 19.5       | 15.0       |
| Pipe2STD x 8 ft     | 99.2      | 5.6       | 5.6       | 2.38      | 20.16        | 12.52     | 62.7       | 7.8        |
| SR 1 x 5 ft         | 63.2      | 4.2       | 4.2       | 1.00      | 13.20        | 8.20      | 25.7       | 5.1        |

# 24 RICHDAL DR

**Location** 24 RICHDAL DR

**Mblu** 75 / 9 / /

**Acct#** 002961

**Owner** KNAPP PROPERTIES LLC

**Assessment** \$986,510

**Appraisal** \$1,409,300

**PID** 4001

**Building Count** 3

## Current Value

| Appraisal      |              |           |             |
|----------------|--------------|-----------|-------------|
| Valuation Year | Improvements | Land      | Total       |
| 2018           | \$690,100    | \$719,200 | \$1,409,300 |

| Assessment     |              |           |           |
|----------------|--------------|-----------|-----------|
| Valuation Year | Improvements | Land      | Total     |
| 2018           | \$483,070    | \$503,440 | \$986,510 |

## Owner of Record

**Owner** KNAPP PROPERTIES LLC  
**Co-Owner**  
**Address** PO BOX 264  
 GEORGETOWN, CT 06829

**Sale Price** \$1,360,000  
**Certificate**  
**Book & Page** 1960/0117  
**Sale Date** 08/14/2007  
**Instrument** WD

## Ownership History

| Ownership History    |             |             |             |            |            |
|----------------------|-------------|-------------|-------------|------------|------------|
| Owner                | Sale Price  | Certificate | Book & Page | Instrument | Sale Date  |
| KNAPP PROPERTIES LLC | \$1,360,000 |             | 1960/0117   | WD         | 08/14/2007 |
| KNAPP RICHARD W      | \$0         |             | 0516/0143   | 00         | 11/01/1985 |


## Building Information

### Building 1 : Section 1

**Year Built:** 1900  
**Living Area:** 3,258  
**Replacement Cost:** \$243,527  
**Building Percent** 66  
**Good:**  
**Replacement Cost**  
**Less Depreciation:** \$160,700

### Building Photo

| Building Attributes |              |
|---------------------|--------------|
| Field               | Description  |
| Style               | Multi Family |



Q et.\$ex\$ 6464\$ 544\$xl



6û\$Puithe)m\$/fi

[ upr\$X\$: <=;



/ufinixrw



Wezm



Rmeff }



Wmrh\$\$syf\$  
ttstrm



Wtefin

\$x\$tw\$ie\$xr





Est. Cost \$25,000

GENERAL LAND USE CHECKLIST  
TOWN OF WILTON, CONNECTICUT

HI# \_\_\_\_\_ Exp Date \_\_\_\_\_

24 Richdale Drive  
Property Address

75 9  
Map # Lot #

*[Signature]*  
\* Tax Collector Approval

2/27/13  
Date

Telcom Engineering  
Applicant's Name

6 Horizon Road  
Applicant's Address

(201)-969-8812 T.C.  
Phone # OWNER verified

Knapp Properties, LLC  
Property Owner's Name

Po Box 264 Georgetown, CT 06829  
Address Phone # Site Phone #

Description of Proposed Work: Remove + Replace three (3) existing Antennas with three (3) New Antennas. Add Six (6) Remote Radio heads behind New Antennas  
No increase to height of tower No ground work required. Cabinets to  
be installed within existing shelter

TO AVOID UNNECESSARY DELAYS, THE APPLICANT SHALL OBTAIN APPROVALS IN THE ORDER SHOWN BELOW, UNLESS OTHERWISE DIRECTED. THE APPLICANT SHALL BE RESPONSIBLE FOR PROVIDING ANY INFORMATION REQUIRED BY EACH DEPARTMENT. THIS REVIEW PROCESS FOR OBTAINING PERMITS MAY TAKE 3 TO 10 DAYS WITH ADDITIONAL TIME FOR SITE INSPECTIONS OR COMMISSION REVIEW IF NECESSARY.

Any portion of structure  
being demolished? \_\_\_\_\_

APPROVALS REQUIRED

(Check here if): Well \_\_\_\_\_ Septic \_\_\_\_\_

SEQUENCE

NOTE: Plan Reviews- 8:00am to 10:00am only

CHECKED

PERMIT #

HEALTH DEPARTMENT: Sanitarian 8:00am-10:00am 563-0174  
Please bring PLOT PLAN showing existing structures WELL AND  
SEPTIC SYSTEMS and a SITE PLAN showing all proposed structures  
And their separating distance to well. Partial Demolitions - Asbestos Certification.

(Fee Required)

WETLANDS REVIEW: Dir. Env. Affairs 8:00am-10:00am- 563-0180  
Please bring PLOT PLAN, KNOWN WETLANDS, LIMITS AND  
REPORTS, SITE PLAN, showing existing features and general proposed  
Features including structures, grading and septic location.

Attach Plot Plan

EROSION AND SEDIMENT CONTROL: P&Z 8:00am-10:00am 563-0180  
Please bring SITE PLAN showing all proposed grading, structures, limit  
of disturbance, and E&S controls.

Attach Plot Plan

①

ZONING PERMIT: Zoning Enf. Officer, 8:00am-10:00am 563-0185  
Please bring SITE PLAN on a certified A-2 survey showing all existing  
And proposed structures.

*TB*

1/30/13

FIRE MARSHAL APPROVAL: Fire Marshal - By Appt. 834-6246  
Georgetown Fire Marshal: 203-544-8933  
This is a preliminary sign off certifying that the Fire Department has received  
the necessary plans/documents to do a complete review for approval.

RECEIVED  
FEB 27 2013

PUBLIC WORKS : Field Engineer, DPW/By Appt. 563-0153  
Please bring plan showing proposed driveway and features within the road  
Right-of-way. For sewer/water bring appropriate drawings as required.

WILTON BUILDING DEPT.

②

BUILDING DEPARTMENT: Building Official, 7:30am-10:00am 563-0177  
Please bring 2 sets of BUILDING PLANS showing floor plans, cross sections  
& elevations, ResCheck for additions, Letter of Authorization from owner,  
Home Improvement Number with expiration date, Workers Comp Cert.,  
Tax Collector approval, and all other approvals required above.

(Fee Required)

THE INFORMATION REQUESTED ABOVE IS PRELIMINARY AS ADDITIONAL MATERIAL MAY BE REQUIRED UPON FURTHER REVIEW OF THE PROJECT.

\*\*WHEN PARTIAL OR COMPLETE DEMOLITION OF A DWELLING IS BEING DONE YOU MAY BE REQUIRED TO OBTAIN A SEPARATE DEMOLITION PERMIT AND COMPLY WITH THE DEMOLITION DELAY ORDINANCE. - SEE BUILDING OFFICIAL

NO FINAL INSPECTION FOR A CERTIFICATE OF OCCUPANCY WILL BE ISSUED UNTIL THE FIRE MARSHAL, ZONING AND HEALTH DEPARTMENTS HAVE CONDUCTED FINAL INSPECTIONS AND THE BUILDING DEPARTMENT HAS RECEIVED APPROVAL DOCUMENTS




ORIGIN ID: LKKA (973) 477-8032  
STEVE SOFMAN  
CHARLES CHERUNDOLLO CONSULTING  
976 TABOR ROAD  
SUITE 4B  
MORRIS PLAINS, NJ 07950  
UNITED STATES US

SHIP DATE: 09DEC19  
ACTWGT: 1.00 LB  
CAD: 111040781/INET4160  
BILL SENDER

TO FIRST SELECTWOMEN, LYNNE VANDERSLIC  
TOWN OF WILTON  
238 DANBURY RD

WILTON CT 06897

(203) 563-0100 REF: CT80XC001  
INV: DEPT:  
PO:




J192119091901ur

THU - 12 DEC 4:30P  
EXPRESS SAVER  
TRK# 7771 8114 4226  
0201

K5 DXRA

06897  
CT-US SWF



567.J2/18DD.05A2

**After printing this label:**

1. Use the 'Print' button on this page to print your label to your laser or inkjet printer.
2. Fold the printed page along the horizontal line.
3. Place label in shipping pouch and affix it to your shipment so that the barcode portion of the label can be read and scanned.

**Warning:** Use only the printed original label for shipping. Using a photocopy of this label for shipping purposes is fraudulent and could result in additional billing charges, along with the cancellation of your FedEx account number.

Use of this system constitutes your agreement to the service conditions in the current FedEx Service Guide, available on fedex.com. FedEx will not be responsible for any claim in excess of \$100 per package, whether the result of loss, damage, delay, non-delivery, misdelivery, or misinformation, unless you declare a higher value, pay an additional charge, document your actual loss and file a timely claim. Limitations found in the current FedEx Service Guide apply. Your right to recover from FedEx for any loss, including intrinsic value of the package, loss of sales, income interest, profit, attorney's fees, costs, and other forms of damage whether direct, incidental, consequential, or special is limited to the greater of \$100 or the authorized declared value. Recovery cannot exceed actual documented loss. Maximum for items of extraordinary value is \$1,000, e.g. jewelry, precious metals, negotiable instruments and other items listed in our Service Guide. Written claims must be filed within strict time limits, see current FedEx Service Guide.

ORIGIN ID: LKKA (973) 477-8032  
STEVE SOFMAN  
CHARLES CHERUNDULO CONSULTING  
976 TABOR ROAD  
SUITE 4B  
MORRIS PLAINS, NJ 07950  
UNITED STATES US

SHIP DATE: 09DEC19  
ACTWGT: 1.00 LB  
CAD: 111040781/NET/4160  
BILL SENDER

TO ROBERT NERNEY  
TOWN OF WILTON  
238 DANBURY RD

WILTON CT 06897

(203) 563-0100 REF: CT80XC001  
INV/ DEPT:  
PO:




J192118891901ur

567.J2/18DD/05A2

TRK# 7771 8114 5005  
0201

THU - 12 DEC 4:30P  
EXPRESS SAVER

K5 DXRA 06897  
CT:US SWF



**After printing this label:**

1. Use the 'Print' button on this page to print your label to your laser or inkjet printer.
2. Fold the printed page along the horizontal line.
3. Place label in shipping pouch and affix it to your shipment so that the barcode portion of the label can be read and scanned.

**Warning:** Use only the printed original label for shipping. Using a photocopy of this label for shipping purposes is fraudulent and could result in additional billing charges, along with the cancellation of your FedEx account number.

Use of this system constitutes your agreement to the service conditions in the current FedEx Service Guide, available on fedex.com. FedEx will not be responsible for any claim in excess of \$100 per package, whether the result of loss, damage, delay, non-delivery, misdelivery, or misinformation, unless you declare a higher value, pay an additional charge, document your actual loss and file a timely claim. Limitations found in the current FedEx Service Guide apply. Your right to recover from FedEx for any loss, including intrinsic value of the package, loss of sales, income interest, profit, attorney's fees, costs, and other forms of damage whether direct, incidental, consequential, or special is limited to the greater of \$100 or the authorized declared value. Recovery cannot exceed actual documented loss. Maximum for items of extraordinary value is \$1,000, e.g. jewelry, precious metals, negotiable instruments and other items listed in our ServiceGuide. Written claims must be filed within strict time limits, see current FedEx Service Guide.

[Shipping](#)[Tracking](#)[Printing Services](#)[Locations](#)[Support](#)**FedEx Ship Manager<sup>®</sup>**[My Profile](#)[Logout](#)[Help](#)

|      |             |              |          |         |                |
|------|-------------|--------------|----------|---------|----------------|
| Ship | LTL Freight | Ship History | My Lists | Reports | Administration |
|------|-------------|--------------|----------|---------|----------------|

**Your Shipment Details**

|                      |   |                                       |                                    |
|----------------------|---|---------------------------------------|------------------------------------|
| <b>From:</b>         | Steve Sofman<br>Charles Cherundolo<br>Consulting<br>976 Tabor Road<br>Suite 4B<br>MORRIS PLAINS, NJ 07950<br>US<br>9734778032 | <b>Ship date:</b>                     | 12/09/2019                         |
|                      |   | <b>Weight:</b>                        | 1.00 LBS                           |
|                      |   | <b>Declared value:</b>                | 0.00 USD                           |
|                      |   | <b>Package Contents:</b>              |                                    |
|                      |   | <b>Document Description:</b>          |                                    |
|                      |   | <b>Shipment Purpose:</b>              |                                    |
|                      |   | <b>Invoice number:</b>                |                                    |
|                      |   | <b>Freight On Value:</b>              |                                    |
|                      |   | <b>Pricing Option:</b>                | FedEx Standard Rate                |
| <b>To:</b>           | Diane Knapp<br>Knapp Properties LLC<br>PO Box 264<br>GEORGETOWN, CT 06829<br>US<br>2039383629                                 | <b>Service type:</b>                  | FedEx Express Saver                |
|                      |   | <b>Package type:</b>                  | FedEx Pak                          |
|                      |   | <b>Pickup/Drop Off:</b>               | Drop off package at FedEx location |
|                      |   | <b>Shipper account number:</b>        | My Account - 429-429               |
|                      |   | <b>Bill transportation to:</b>        | My Account - 429-429               |
|                      |   | <b>Courtesy rate quote:*</b>          | 14.48 USD                          |
|                      |   | <b>Published rates:</b>               | 17.24                              |
| <b>Tracking no.:</b> | 777181158781  | <b>Effective net discount:</b>        | 2.76                               |
|                      |   | <b>Discounted variable %:</b>         |                                    |
|                      |   | <b>List variable %:</b>               |                                    |
|                      |   | <b>Special services:</b>              |                                    |
|                      |   | <b>Shipment type:</b>                 | Express                            |
|                      |   | <b>Commercial/Residential Status:</b> | Commercial                         |



**Please note :**

\* The courtesy rate shown here may be different than the actual charges for your shipment. Differences may occur based on actual weight, dimensions, and other factors. Consult the applicable [FedEx Service Guide](#) or the FedEx Rate Sheets for details on how shipping charges are calculated.

FedEx will not be responsible for any claim in excess of \$100 per package, whether the result of loss, damage, delay, non-delivery, misdelivery, or misinformation, unless you declare a higher value, pay an additional charge, document your actual loss and file a timely claim. Limitations found in the current FedEx Service Guide apply. Your right to recover from FedEx for any loss, including intrinsic value of the package, loss of sales, income interest, profit, attorney's fees, costs, and other forms of damage whether direct, incidental, consequential, or special is limited to the greater of \$100 or the authorized declared value. Recovery cannot exceed actual documented loss. Maximum for items of extraordinary value is \$1000, e.g., jewelry, precious metals, negotiable instruments and other items listed in our Service Guide. Written claims must be filed within strict time limits; Consult the applicable FedEx Service Guide for details.

**OUR COMPANY**

About FedEx  
Our Portfolio  
Investor Relations  
Careers

FedEx Blog  
Corporate Responsibility  
Newsroom  
Contact Us

**MORE FROM FEDEX**

FedEx Compatible  
Developer Resource Center  
FedEx Cross Border

**LANGUAGE**

Change Country

English

**FOLLOW FEDEX**