



*Daniel F. Caruso*  
*Chairman*

# STATE OF CONNECTICUT

## CONNECTICUT SITING COUNCIL

Ten Franklin Square, New Britain, CT 06051

Phone: (860) 827-2935 Fax: (860) 827-2950

E-Mail: [siting.council@ct.gov](mailto:siting.council@ct.gov)

Internet: [ct.gov/csc](http://ct.gov/csc)

November 2, 2010

Jennifer Young Gaudet  
T-Mobile USA, Inc.  
35 Griffin Rd. S  
Bloomfield, CT 06002

RE: **EM-T-MOBILE-162-100824** - Omnipoint Communications, as subsidiary of T-Mobile USA, Inc., notice of intent to modify an existing telecommunications facility located off of Oakdale Avenue, Winchester, Connecticut. Renewal of Acknowledgement.

Dear Ms. Gaudet:

The Connecticut Siting Council (Council) hereby acknowledges your notice to modify this existing telecommunications facility, pursuant to Section 16-50j-73 of the Regulations of Connecticut State Agencies with the following conditions:

- Not more than 45 days after completion of construction, a signed letter from a Professional Engineer duly licensed in the State of Connecticut shall be submitted to the Council to certify that the reinforcements have been properly completed and the tower does not exceed 100 percent of its post-construction structural rating.
- Any deviation from the proposed modification as specified in this notice and supporting materials with Council shall render this acknowledgement invalid;
- Any material changes to this modification as proposed shall require the filing of a new notice with the Council;
- Not less than 45 days after completion of construction, the Council shall be notified in writing that construction has been completed;
- The validity of this action shall expire one year from the date of this letter; and
- The applicant may file a request for an extension of time beyond the one year deadline provided that such request is submitted to the Council not less than 60 days prior to the expiration;

The proposed modifications including the placement of all necessary equipment and shelters within the tower compound are to be implemented as specified here and in your notice dated August 20, 2010. The modifications are in compliance with the exception criteria in Section 16-50j-72 (b) of the Regulations of Connecticut State Agencies as changes to an existing facility site that would not increase tower height, extend the boundaries of the tower site, increase noise levels at the tower site boundary by six decibels, and increase the total radio frequencies electromagnetic radiation power density measured at the tower site boundary to or above the standard adopted by the State Department of Environmental Protection pursuant to General Statutes § 22a-162. This facility has also been carefully modeled to ensure that radio frequency emissions are conservatively below State and federal standards applicable to the frequencies now used on this tower.

This decision is under the exclusive jurisdiction of the Council. Please be advised that the validity of this action shall expire one year from the date of this letter. Any additional change to this facility will require

explicit notice to this agency pursuant to Regulations of Connecticut State Agencies Section 16-50j-73. Such notice shall include all relevant information regarding the proposed change with cumulative worst-case modeling of radio frequency exposure at the closest point of uncontrolled access to the tower base, consistent with Federal Communications Commission, Office of Engineering and Technology, Bulletin 65. Thank you for your attention and cooperation.

Very truly yours,



Linda Roberts  
Executive Director

LR/CDM/laf

- c: The Honorable Kenneth J. Fracasso, Mayor, Town of Winchester
- Keith Robbins, Town Manager, Town of Winchester
- Anthony Cannavo, Planning and Zoning Chairman, Town of Winchester
- American Tower Corporation

**Martin, David C.**

---

**From:** Jennifer Gaudet [jgaudet@hpcdevelop.com]  
**Sent:** Tuesday, October 19, 2010 12:04 PM  
**To:** Martin, David C.  
**Subject:** FW: 302506 Winchester CT 3 - TMO CTNH403  
**Attachments:** PICT0009.jpg

David –

Per our conversation, please see the attached and e-mail below with ATC's representation that the tower modifications/reinforcement were accomplished.

Please let me know if you require anything additional.

Thanks.

*Jennifer*

Jennifer Young Gaudet  
Project Manager

HPC Development LLC  
46 Mill Plain Road  
Danbury, CT 06811  
Cell: (860) 798-7454  
Fax: (203) 797-1137  
[jgaudet@hpcdevelop.com](mailto:jgaudet@hpcdevelop.com)  
[www.hpcdevelop.com](http://www.hpcdevelop.com)

**CONFIDENTIALITY NOTICE:**

This message originates from the firm of HPC Development LLC. The information contained in this e-mail and any files transmitted with it may be a confidential communication or may otherwise be privileged and confidential and part of the work product doctrine. If the reader of this message, regardless of the address or routing, is not an intended recipient, you are hereby notified that you have received this transmittal in error and any review, use, distribution, dissemination or copying is strictly prohibited. If you have received this message in error, please delete this e-mail and all files transmitted with it from your system and immediately notify HPC Development LLC by sending a reply e-mail to the sender of this message. Thank you.

---

**From:** Andrew Gilbert [mailto:Andrew.Gilbert@AmericanTower.com]  
**Sent:** Wednesday, September 08, 2010 3:28 PM  
**To:** Jamie Ford  
**Cc:** Amy English  
**Subject:** RE: 302506 Winchester CT 3 - TMO CTNH403

Hi Jamie,

Those modifications were completed. A picture is attached showing the reinforced base plate.

Thanks,

Andrew Gilbert  
781.926.4938 (desk)  
617.594.2531 (cell)

---

**From:** Jamie Ford [mailto:jford@hpcdevelop.com]

10/19/2010


**Sent:** Wednesday, September 08, 2010 3:03 PM  
**To:** Andrew Gilbert  
**Cc:** Amy English  
**Subject:** 302506 Winchester CT 3 - TMO CTNH403

Hi Andrew –

We recently re-filed our exempt mod w/ the council for this site, and were requested to provide a bit of additional information to our application. Would ATC be able to provide a statement that the modifications specified in the structural were completed? We don't need a new SA, just confirmation that the modifications were done as the SA suggested. Please advise.

Thanks!!

Jamie Ford  
(774) 248-5373



2008/01/02 01:46



EM-T-MOBILE-162-100824

VIA OVERNIGHT DELIVERY

August 20, 2010

Connecticut Siting Council  
10 Franklin Square  
New Britain, Connecticut 06051  
Attn: Ms. Linda Roberts, Executive Director

RECEIVED  
ORIGINAL  
AUG 24 2010

Re: Omnipoint Communications, Inc. (T-Mobile) – exempt modification  
Oakdale Avenue, Winchester, Connecticut

CONNECTICUT  
SITING COUNCIL

Dear Ms. Roberts:

On October 29, 2008, Omnipoint Communications, Inc., predecessor-in-interest to T-Mobile Northeast LLC (“T-Mobile”) submitted an exempt modification for an installation at the American Tower Corp. site off of Oakdale Avenue in Winchester. That submission was acknowledged by Council letter dated November 25, 2008, a copy of which is attached.

T-Mobile’s site was not constructed within one year from the date of the Council’s acknowledgment, and no extension of the time frame was requested. At this time, T-Mobile intends to proceed with its installation as detailed in its October 2008 filing. As no changes from the previous filing are involved, a copy of T-Mobile’s previous submission is hereby resubmitted. T-Mobile is aware that changes by other carriers may have been implemented in the interim, and has confirmed that the structural analyses presented to the Council in connection with those changes properly reflect T-Mobile’s planned loading.

In compliance with R.C.S.A. Section 16-50j-73, a copy of this letter and attachments is being sent to the Mayor of Winchester.

Please contact me at (860) 798-7454 with any questions concerning this matter. Thank you for your consideration.

Respectfully yours,

Jennifer Young Gaudet

cc: Althea Candy Perez, Mayor, Town of Winchester  
William P. and Richard D. Stow (underlying property owners)

Attachments

T-Mobile USA, Inc.  
Office: (860) 692-7100  
Fax: (860) 692-7159  
35 Griffin Rd S  
Bloomfield, CT 06002



Daniel F. Caruso  
Chairman

# STATE OF CONNECTICUT

## CONNECTICUT SITING COUNCIL

Ten Franklin Square, New Britain, CT 06051

Phone: (860) 827-2935 Fax: (860) 827-2950

E-Mail: [siting.council@ct.gov](mailto:siting.council@ct.gov)

Internet: [ct.gov/csc](http://ct.gov/csc)

November 25, 2008

Jennifer Young Gaudet  
T-Mobile USA, Inc.  
35 Griffin Road S  
Bloomfield, CT 06002

RE: **EM-T-MOBILE-162-081031** – Omnipoint Communications, Inc. a.k.a. T-Mobile notice of intent to modify an existing telecommunication facility located at 15 Oakdale Avenue, Winchester, Connecticut.

Dear Ms. Gaudet:

The Connecticut Siting Council (Council) hereby acknowledges your notice to modify this existing telecommunications facility, pursuant to Section 16-50j-73 of the Regulations of Connecticut State Agencies with the following conditions:

- The base plate is reinforced per the attached drawings of the structural analysis report dated October 8, 2008 and sealed by Raphael Mohamed, P.E. prior to the antenna installation;
- A post-construction tower rating of not more than 100 percent is achieved; and
- A signed letter from a Professional Engineer duly licensed in the State of Connecticut shall be submitted to the Council to certify that the reinforcements have been properly completed and a post-construction tower rating of not more than 100 percent has been achieved.


The proposed modifications are to be implemented as specified here and in your notice dated October 29, 2008, including the placement of all necessary equipment and shelters within the tower compound. The modifications are in compliance with the exception criteria in Section 16-50j-72 (b) of the Regulations of Connecticut State Agencies as changes to an existing facility site that would not increase tower height, extend the boundaries of the tower site, increase noise levels at the tower site boundary by six decibels, and increase the total radio frequencies electromagnetic radiation power density measured at the tower site boundary to or above the standard adopted by the State Department of Environmental Protection pursuant to General Statutes § 22a-162. This facility has also been carefully modeled to ensure that radio frequency emissions are conservatively below State and federal standards applicable to the frequencies now used on this tower.

This decision is under the exclusive jurisdiction of the Council. Please be advised that the validity of this action shall expire one year from the date of this letter. Any additional change to this facility will require explicit notice to this agency pursuant to Regulations of Connecticut State Agencies Section 16-50j-73. Such notice shall include all relevant information regarding the proposed change with cumulative worst-case modeling of radio frequency exposure at the closest point of uncontrolled access to the tower base, consistent with Federal Communications Commission, Office of Engineering and Technology, Bulletin 65. Any deviation from this format may result in the Council implementing enforcement proceedings pursuant to

General Statutes § 16-50u including, without limitation, imposition of expenses resulting from such failure and of civil penalties in an amount not less than one thousand dollars per day for each day of construction or operation in material violation.

Thank you for your attention and cooperation.

Very truly yours,



S. Derek Phelps  
Executive Director

SDP/MP/laf

- c: The Honorable Kenneth J. Fracasso, Mayor, Town of Winchester
- Keith Robbins, Town Manager, Town of Winchester
- Anthony Cannavo, Planning and Zoning Chairman, Town of Winchester
- American Tower Corporation





VIA OVERNIGHT DELIVERY

October 29, 2008

Connecticut Siting Council  
10 Franklin Square  
New Britain, Connecticut 06051  
Attn: Mr. S. Derek Phelps, Executive Director

Re: Omnipoint Communications, Inc. (T-Mobile) – exempt modification  
Oakdale Avenue, Winchester, Connecticut

Dear Mr. Phelps:

This letter and attachments are submitted on behalf of Omnipoint Communications, Inc. (also referred to herein as “T-Mobile”). T-Mobile plans to install antennas and related equipment at the American Tower Corp. site off of Oakdale Avenue in Winchester (coordinates 41°55’18” N, -73°03’02” W). Please accept this letter and attachments as notification, pursuant to R.C.S.A. Section 16-50j-73, of construction which constitutes an exempt modification pursuant to R.C.S.A. Section 16-50j-72(b)(2). In compliance with R.C.S.A. Section 16-50j-73, a copy of this letter and attachments is being sent to the Mayor of Winchester.

T-Mobile will install nine antennas at the 166’ level of the tower. The antennas will be installed, three per sector, on T-arms; one TMA will be mounted behind two of the antennas in each sector. T-Mobile’s equipment cabinets will be placed on a concrete pad near the base of the tower. Attached are a compound plan and elevation depicting the planned changes. Also attached are a structural analysis and associated reinforcement modification plan, which will be implemented at the time of construction to achieve structural sufficiency for T-Mobile’s installation.

The changes to the facility do not constitute a modification as defined in Connecticut General Statutes (“C.G.S.”) Section 16-50i(d) because the general physical characteristics of the facility will not be significantly changed. Rather, the planned changes to the facility fall squarely within those activities explicitly provided for in R.C.S.A. Section 16-50j-72(b)(2).

1. The height of the overall structure will be unaffected. The top of the tower extends to approximately 180’; T-Mobile’s proposed antennas will be located with a center line of 166’ AGL.

T-Mobile USA, Inc.  
Office: (866) 692-7100  
Fax: (866) 692-7159  
35 Griffin Rd S  
Bloomfield, CT 06002

Mr. S. Derek Phelps  
October 29, 2008  
Page 2

2. The addition of T-Mobile's equipment will not require any extension of the site boundaries. All equipment will be located within the existing fenced compound.
3. The proposed changes will not increase the noise level at the existing facility by six decibels or more. The incremental effect of the additional cabinets will be negligible.
4. The changes to the facility will not increase the calculated "worst case" power density for the combined operations at the site to a level at or above the applicable standard for uncontrolled environments as calculated for a mixed frequency site. As indicated on the attached power density calculation, T-Mobile's operations at the site will result in a power density of 1.6353%; the combined site operations will result in a total power density of 27.765%.

Please feel free to call me at (860) 798-7454 with questions concerning this matter. Thank you for your consideration.

Respectfully yours,




Jennifer Young Gaudet

cc: Kenneth J. Fracasso, Mayor, Town of Winchester  
William P. and Richard D. Stow (underlying property owners)  
Attachments

**ALL-POINTS TECHNOLOGY CORPORATION, P.C.**

3 SADDLEBROOK DRIVE  
KILLINGWORTH, CT. 06419  
PHONE: (860)-663-1697  
FAX: (860)-663-0935  
www.allpointstech.com



**APT FILING NUMBER: CT-255T-160**

LE-1

SCALE: AS NOTED

DRAWN BY: AAJ

DATE: 09/10/08

CHECKED BY: SMC



35 GRIFFIN ROAD  
BLOOMFIELD, CT 06002  
OFFICE: (860)-692-7100

**T-MOBILE SITE NUMBER**


**CTNH403A**

WINCHESTER ATC  
108 OAKDALE AVENUE  
WINCHESTER, CT 06098

**NOTE:**

PER FCC MANDATE, ENHANCED EMERGENCY (E911) SERVICE IS REQUIRED TO MEET NATIONWIDE STANDARDS FOR WIRELESS COMMUNICATIONS SYSTEMS. OMNIPOINT COMMUNICATIONS INC. IMPLEMENTATION REQUIRES DEPLOYMENT OF EQUIPMENT AND ANTENNAS GENERALLY DEPICTED ON THIS PLAN, ATTACHED TO OR MOUNTED IN CLOSE PROXIMITY TO THE BTS RADIO CABINETS. OMNIPOINT COMMUNICATIONS INC. RESERVES THE RIGHT TO MAKE REASONABLE MODIFICATIONS TO E911 EQUIPMENT AND LOCATION AS TECHNOLOGY EVOLVES TO MEET REQUIRED SPECIFICATIONS. ALL EQUIPMENT LOCATIONS ARE APPROXIMATE AND ARE SUBJECT TO APPROVAL BY OMNIPOINT COMMUNICATIONS INC. STRUCTURAL & RF ENGINEERS. LOCATIONS OF POWER & TELEPHONE FACILITIES ARE SUBJECT TO APPROVAL BY UTILITY COMPANIES.

- REV1: 10/20/08: LEASE AREA SIZE: SMC
- REV2: 10/21/08: GENERAL COMMENTS: SMC
- REV3: 10/28/08: CHANGE ADDRESS: SMC
- REV4: 10/29/08: STR'L UPDATE: SMC



PROPOSED T-MOBILE 225 SF (15'x15')  
LEASE AREA W/ CABINETS, UTILITY  
CENTER, SERVICE LIGHT, ON  
PROPOSED CONCRETE SLAB

PROPOSED T-MOBILE  
HORIZONTAL CABLE TRAY TO  
EXISTING ACCESS PORT W/ GPS  
AND GSM ANTENNAS ON 8' MAST

PROPOSED UNDERGROUND  
ELECTRICAL AND TELCO SERVICE  
FROM EXISTING METER CENTER TO  
PROPOSED EQUIPMENT AREA

PROPOSED T-MOBILE ALPHA, BETA,  
AND GAMMA ANTENNAS (9 TOTAL) & 2  
TMAs/SECTOR (6 TOTAL) MOUNTED ON  
STANDOFF CROSS ARMS

EXISTING 180'± AGL MONOPOLE

EXISTING CARRIER EQUIPMENT (TYP.)


EXISTING MULTIMETER CENTER AND  
TELCO DEMARC ON SERVICE  
BACKBOARD



**COMPOUND PLAN**

SCALE : 1" = 20'-0"

**ALL-POINTS TECHNOLOGY CORPORATION, P.C.**  
 3 SADDLEBROOK DRIVE  
 KILLINGWORTH, CT. 06419  
 PHONE: (860)-663-1697  
 FAX: (860)-663-0935  
 www.allpointstech.com




**APT FILING NUMBER: CT-255T-160**  
 LE-2  
 SCALE: AS NOTED      DRAWN BY: AAJ  
 DATE: 09/10/08      CHECKED BY: SMC

**T-Mobile**  
 35 GRIFFIN ROAD  
 BLOOMFIELD, CT 06002  
 OFFICE: (860)-692-7100

**T-MOBILE SITE NUMBER**  
**CTNH403A**  
 WINCHESTER ATC  
 108 OAKDALE AVENUE  
 WINCHESTER, CT 06098

**NOTE:**  
 PER FCC MANDATE, ENHANCED EMERGENCY (E911) SERVICE IS REQUIRED TO MEET NATIONWIDE STANDARDS FOR WIRELESS COMMUNICATIONS SYSTEMS. OMNIPOINT COMMUNICATIONS INC. IMPLEMENTATION REQUIRES DEPLOYMENT OF EQUIPMENT AND ANTENNAS GENERALLY DEPICTED ON THIS PLAN, ATTACHED TO OR MOUNTED IN CLOSE PROXIMITY TO THE BTS RADIO CABINETS. OMNIPOINT COMMUNICATIONS INC. RESERVES THE RIGHT TO MAKE REASONABLE MODIFICATIONS TO E911 EQUIPMENT AND LOCATION AS TECHNOLOGY EVOLVES TO MEET REQUIRED SPECIFICATIONS. ALL EQUIPMENT LOCATIONS ARE APPROXIMATE AND ARE SUBJECT TO APPROVAL BY OMNIPOINT COMMUNICATIONS INC. STRUCTURAL & RF ENGINEERS. LOCATIONS OF POWER & TELEPHONE FACILITIES ARE SUBJECT TO APPROVAL BY UTILITY COMPANIES.

REV1: 10/20/08: LEASE AREA SIZE: SMC  
 REV2: 10/21/08: GENERAL COMMENTS: SMC  
 REV3: 10/28/08: CHANGE ADDRESS: SMC  
 REV4: 10/29/08: STRL UPDATE: SMC



**EASTERN ELEVATION**  
 SCALE: 1" = 30'-0"



**AMERICAN TOWER**

---

## Structural Analysis Report

**Structure** : 180 ft EEI Monopole  
**ATC Site Name** : Winchester CT 3, CT  
**ATC Site Number** : 302506  
**Proposed Carrier** : T-Mobile  
**Carrier Site Name** : Litchfield 6  
**Carrier Site Number** : CTNH403A  
**County** : Litchfield  
**Eng. Number** : 42523421  
**Date** : October 8, 2008\*  
**Usage** : 97% (Pole Shaft), 104% (Base Plate)  
**Portholes Required** : No

Submitted by:  
Zachary A. Medoff, E.I.  
Design Engineer

**American Tower Engineering Services**  
400 Regency Forest Drive  
Cary, NC 27518  
Phone: 919-468-0112



10-9-08

**Introduction**

The purpose of this report is to summarize results of the structural analysis performed on the 180 ft EEI Monopole located at 15 Oakdale Avenue, Winsted, CT 06098, Litchfield County (ATC site #302506). The tower was originally designed and manufactured by EEI (Job #7676, dated August 21, 2000).

**Analysis**

The tower was analyzed using Semaan Engineering Solutions, Inc., Software. The analysis assumes that the tower is in good, undamaged, and non-corroded condition.

Basic Wind Speed: 90 mph (3-Second Gust)  
 Radial Ice: 40 mph (3-Second Gust) w/ 1 1/4" ice  
 Code: ANSI/TIA-222-G / 2003 IBC w/ 2005 CT Supplement & 2008 CT Amendments

**Antenna Loads**

The following antenna loads were used in the tower analysis.

**Existing Antennas**

Elev. (ft)	Qty	Antennas	Mount	Coax (in)	Carrier
184.0	12	CSS DUO4-8670	Flat Low Profile Platform	(12) 1 5/8	AT&T Mobility
180.0	1	Yagi		(1) 1 5/8	CT Police Dept.
	1	10' Omni		(1) 7/8	USA Mobility
174.0	4	Antel LPD-7905/4	Flat Low Profile Platform	(12) 1 5/8	Alltel
	4	Nokia CS72993.07			
	2	Decibel 731DG85V1EXM			
142.0	1	56" Dipole	Side Arms	(1) 1/2	CT Police Dept.
	2	10' Omni		(4) 1 5/8	
134.0	9	Andrew DB980H90E-M	Flat Platform w/ Handrails	(9) 1 5/8	Sprint Nextel
125.0	2	Antel LPA-80063/6CF	Round Low Profile Platform	(12) 1 5/8	Verizon
	4	Antel LPA-80080/6CF			
	4	Decibel DB950F85E-M			
	2	Decibel DB950F65E-M			
114.5	12	Decibel DB844H90E-XY	Round Low Profile Platform	(12) 1 1/4	Sprint Nextel
46.5	1	Nokia CS72187.01	Pipe	(1) 1/2	AT&T Mobility

**Proposed Antennas**

Elev. (ft)	Qty	Antennas	Mount	Coax (in)	Carrier
166.0	6	CCI DTMA-1819-DD-12	T-Arms	-	T-Mobile
	9	RFS APX16PV-16PVL-E-00		(18) 1 5/8	

Install proposed coax on outside of monopole.

**Results**

The maximum structure usage is: 104% (Acceptable overstress)

Additional exit and/or entry ports may be required to accommodate the running of the proposed lines to the proposed antennas. These additional ports **may not** be installed without installation drawings providing the location, size and welding requirements of each port.

To ensure compliance with all conditions of this structural analysis, port installation drawings shall be provided by American Tower’s Engineering Department under a subsequent project.

Pole Reactions	Original Design Reactions	Factored Design Reactions*	Current Analysis Reactions	% Of Design
Moment (ft-kips)	3,377.9	4560.2	4,027.2	88
Shear (kips)	28.4	38.3	33.3	87

\* The design reactions are factored by 1.35 per ANSI/TIA-222-G, Sec. 15.5.1

The structure base reactions resulting from this analysis are acceptable when compared to the reactions shown on the original structure drawings, therefore no modification or reinforcement of the foundation will be required.

**Conclusion**

Based on the analysis results, the structure meets the requirements per ANSI/TIA-222-G and 2003 IBC with 2005 CT Supplement & 2008 CT Amendments. The tower and foundation can support the existing and proposed antennas with the TX line distribution as described in this report.

If you have any questions or require additional information, please call 919-465-6535.

# AMERICAN TOWER CORPORATION

400 REGENCY FOREST DRIVE  
 CARY, NORTH CAROLINA 27518  
 PHONE: (919) 468-0112 / FAX: (919) 466-5040

## 302506 - WINCHESTER CT 3, CT 180 FT. EEI MONOPOLE BASE PLATE REINFORCING

### PROJECT DESCRIPTION:

THE MODIFICATIONS PRESENTED ON THESE DRAWINGS ARE BASED ON THE RECOMMENDATIONS OUTLINED IN THE STRUCTURAL ANALYSIS COMPLETED UNDER ENGINEERING PROJECT NUMBER 42523432 DATED 10/23/08. SATISFACTORY COMPLETION OF THE WORK INDICATED ON THESE DRAWINGS WILL RESULT IN THE STRUCTURE MEETING THE REQUIREMENTS OF THE SPECIFICATIONS UNDER WHICH THE STRUCTURAL WAS COMPLETED.

DESCRIPTION	SIGNATURE	DATE
CONTRACTOR NAME		
CONTRACTOR REPRESENTATIVE (PRINT NAME)		
CONTRACTOR REPRESENTATIVE SIGNATURE		
REDEVELOPMENT P.M. (PRINT NAME)		
REDEVELOPMENT P.M. SIGNATURE		

### PROJECT SUMMARY

ATC PROJECT NUMBER: 42523432  
 CUSTOMER: T-MOBILE  
 CUSTOMER SITE NUMBER: CTNH403A  
 CUSTOMER SITE NAME: LITCHFIELD 6  
 SITE ADDRESS: 15 OAKDALE AVENUE  
 WINSTED, CT 06098  
 DATE: 10/24/08  
 REVISION: 0



I hereby certify that this engineering document was prepared by me or under my direct personal supervision and that I am a duly licensed Professional Engineer under the laws of the state of Connecticut.

### DRAWING INDEX

DRAWING NUMBER	DRAWING TITLE	REVISION
80M	BILL OF MATERIALS (1 PAGE)	0
CT0N	CT GENERAL NOTES	0
A-1	BASE PLATE STIFFENER INSTALLATION	0
ST0R15	STIFFENER	0







THESE DRAWINGS AND/OR THE ACCOMPANYING SPECIFICATION AS INSTRUMENTS OF SERVICE, ARE THE PROPERTY OF AMERICAN TOWER CORPORATION AND THEIR USE AND REPRODUCTION IN ANY MANNER WITHOUT THE WRITTEN PERMISSION OF AMERICAN TOWER CORPORATION IS PROHIBITED. THESE DRAWINGS AND/OR SPECIFICATIONS ARE TO BE USED IN CONNECTION WITH THE PROJECT AND WITHOUT PREJUDICE AND VISUAL CONTACT WITH ANY OTHER PROJECTS. THE ACCEPTANCE OF THESE RESTRICTIONS IS THE RESPONSIBILITY OF THE USER.

REV.	DESCRIPTION	BY	DATE
1	FIRST ISSUE	JMB	06/19/28

SITE NUMBER:  
**VARIOUS**

SITE NAME:  
**VARIOUS**

SITE ADDRESS:  
**VARIOUS**

DRAWN BY:	DMB
CHECKED BY:	BKL
DATE DRAWN:	06/20/08
AISC JOB NO.:	VARIOUS
SHEET TITLE:	

CT GENERAL NOTES	
SHEET NUMBER:	0
CTGN	

**SPECIAL INSPECTION**

1. A QUALIFIED INDEPENDENT TESTING LABORATORY, EMPLOYED BY THE OWNER, SHALL PERFORM INSPECTION AND TESTING IN ACCORDANCE WITH BIG 2003, SECTION 1704 AS REQUIRED BY PROJECT SPECIFICATIONS FOR THE FOLLOWING CONSTRUCTION WORK:
  - a) STRUCTURAL WELDING
  - b) HIGH STRENGTH BOLTS
2. THE INSPECTION AGENCY SHALL SUBMIT INSPECTION AND TEST REPORTS TO THE BUILDING DEPARTMENT, THE ENGINEER OF RECORD, AND THE OWNER IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS. WORK IS APPROVED BY THE BUILDING OFFICIAL TO PERFORM SUCH WORK WITHOUT THE SPECIAL INSPECTIONS.

**WELDING**

1. ALL WELDING TO BE PERFORMED BY AWS CERTIFIED WELDERS AND CONDUCTED IN ACCORDANCE WITH THE LATEST EDITION OF THE AWS WELDING CODE D1.1.
2. ALL ELECTRODES TO BE LOW HYDROGEN, MATCHING FILLER METAL, PER AWS D1.1, U.N.O.
3. MINIMUM WELD SIZE TO BE 0.1875 INCH FILLET WELDS, UNLESS NOTED OTHERWISE.
4. PRIOR TO FIELD WELDING GALVANIZED MATERIAL, CONTRACTORS SHALL SCRAPE OFF GALVANIZING 1/2" BEYOND ALL FIELD WELD SURFACES. AFTER WELD AND WELD INSPECTION IS COMPLETE, REPAIR ALL GROUND AND WELDED SURFACES WITH ZNC GALVANITE COLD GALVANIZING COMPOUND PER ASTM A790 AND MANUFACTURERS REQUIREMENTS.

**PAINT**

1. AS REQUIRED, CLEAN AND PAINT PROPOSED STEEL ACCORDING TO FAA ADVISORY CIRCULAR AC 707469-K.

**BOLT TIGHTENING PROCEDURE**

1. TIGHTEN FLANGE BOLTS BY ASC - "TURN OF THE NUT" METHOD, USING THE CHART BELOW:
 

BOLT LENGTHS UP TO AND INCLUDING FOUR DIA.	*1/2 TURN BEYOND SNUG TIGHT
1/2" BOLTS UP TO AND INCLUDING 2.4 INCH LENGTH	*1/2 TURN BEYOND SNUG TIGHT
3/4" BOLTS UP TO AND INCLUDING 3.0 INCH LENGTH	*1/2 TURN BEYOND SNUG TIGHT
7/8" BOLTS UP TO AND INCLUDING 3.5 INCH LENGTH	*1/2 TURN BEYOND SNUG TIGHT
1" BOLTS UP TO AND INCLUDING 4.0 INCH LENGTH	*1/2 TURN BEYOND SNUG TIGHT
1-1/8" BOLTS UP TO AND INCLUDING 4.5 INCH LENGTH	*1/2 TURN BEYOND SNUG TIGHT
1-1/4" BOLTS UP TO AND INCLUDING 5.0 INCH LENGTH	*1/2 TURN BEYOND SNUG TIGHT
1-1/2" BOLTS UP TO AND INCLUDING 5.0 INCH LENGTH	*1/2 TURN BEYOND SNUG TIGHT

BOLT LENGTHS OVER FOUR DIA. BUT NOT EXCEEDING 8 DIA.	*1/2 TURN BEYOND SNUG TIGHT
1/2" BOLTS 2.75 TO 4.0 INCH LENGTH	*1/2 TURN BEYOND SNUG TIGHT
5/8" BOLTS 3.25 TO 5.0 INCH LENGTH	*1/2 TURN BEYOND SNUG TIGHT
3/4" BOLTS 4.25 TO 6.0 INCH LENGTH	*1/2 TURN BEYOND SNUG TIGHT
7/8" BOLTS 5.75 TO 7.0 INCH LENGTH	*1/2 TURN BEYOND SNUG TIGHT
1" BOLTS 6.25 TO 8.0 INCH LENGTH	*1/2 TURN BEYOND SNUG TIGHT
1-1/8" BOLTS 6.75 TO 9.0 INCH LENGTH	*1/2 TURN BEYOND SNUG TIGHT
1-1/4" BOLTS 7.25 TO 10.0 INCH LENGTH	*1/2 TURN BEYOND SNUG TIGHT
1-1/2" BOLTS 8.25 TO 12.0 INCH LENGTH	*1/2 TURN BEYOND SNUG TIGHT
2. SPLICE BOLTS SUBJECT TO DIRECT TENSION SHALL BE INSTALLED AND TIGHTENED AS PER SECTION 8(6)(f) OF THE AISC SPECIFICATION FOR STRUCTURAL JOINTS USING A325 OR A490 BOLTS, LOCATED IN THE AISC MANUAL OF STEEL CONSTRUCTION. THE INSTALLATION PROCEDURE IS PARAPHRASED AS FOLLOWS:
 

\*FASTENERS SHALL BE INSTALLED IN PROPERLY ALIGNED HOLES AND TIGHTENED BY ONE OF THE METHODS DESCRIBED IN SUBSECTION 8(6)(f) THROUGH 8(6)(h).

8(6)(f) TURN-OF-THE-NUT TIGHTENING.

BOLTS SHALL BE INSTALLED IN ALL HOLES OF THE CONNECTION AND BROUGHT TO A SNUG TIGHT CONDITION AS DEFINED IN SECTION 8 (c), UNTIL ALL THE BOLTS ARE SIMULTANEOUSLY SNUG TIGHT AND THE CONNECTION IS FULLY COMPACTED. FOLLOWING THIS INITIAL OPERATION ALL BOLTS IN THE CONNECTION SHALL BE TIGHTENED FURTHER BY THE APPLICABLE AMOUNT OF ROTATION SPECIFIED ABOVE. DURING THE TIGHTENING OPERATION THERE SHALL BE NO SYSTEMATICALLY.
3. ALL OTHER BOLTED CONNECTIONS SHALL BE BROUGHT TO A SNUG TIGHT CONDITION AS DEFINED IN SECTION 8 (c) OF THE SPECIFICATION.

**GENERAL**

1. ALL METHODS, MATERIALS AND WORKMANSHIP SHALL FOLLOW THE DICTATES OF GOOD CONSTRUCTION PRACTICE.
2. ALL WORK INDICATED ON THESE DRAWINGS SHALL BE PERFORMED BY QUALIFIED CONTRACTORS EXPERIENCED IN TOWER AND FOUNDATION CONSTRUCTION.
3. THE CONTRACTOR SHALL NOTIFY THE ENGINEER OF RECORD IMMEDIATELY OF ANY CONDITIONS, DETAILS NOT SPECIFICALLY SHOWN ON THE DRAWINGS SHALL FOLLOW SIMILAR DETAILS FOR THIS JOB.
4. ANY SUBSTITUTIONS MUST CONFORM TO THE REQUIREMENTS OF THESE NOTES AND SPECIFICATIONS, AND SHOULD BE SIMILAR TO THOSE SHOWN. ALL SUBSTITUTIONS SHALL BE SUBMITTED TO THE ENGINEER OF RECORD FOR REVIEW AND APPROVAL PRIOR TO FABRICATION.

5. ANY MANUFACTURED DESIGN ELEMENTS MUST CONFORM TO THE REQUIREMENTS OF THESE NOTES AND SPECIFICATIONS AND SHOULD BE SIMILAR TO THOSE SHOWN. THESE DESIGN ELEMENTS MUST BE STAMPED BY AN ENGINEER PROFESSIONALLY REGISTERED IN THE STATE OF THE PROJECT AND SUBMITTED TO THE ENGINEER OF RECORD FOR APPROVAL PRIOR TO FABRICATION.
6. ALL WORK SHALL BE DONE IN ACCORDANCE WITH LOCAL CODES AND OSHA SAFETY REGULATIONS.
7. THE CONTRACTOR IS RESPONSIBLE FOR THE DESIGN AND EXECUTION OF ALL MISCELLANEOUS SHORING, BRACING, TEMPORARY SUPPORTS, ETC. NECESSARY TO PROVIDE A COMPLETE AND STABLE STRUCTURE AS SHOWN ON THESE DRAWINGS.
8. CONTRACTORS PROPOSED INSTALLATION SHALL NOT INTERFERE, NOR DENY ACCESS TO, ANY EXISTING OPERATIONAL AND SAFETY EQUIPMENT.
9. FIELD CUT EDGES, EXCEPT DRILLED HOLES, SHALL BE GROUND SMOOTH.
10. ALL FIELD CUT SURFACES SHALL BE REPAIRED WITH ZNC GALVANITE COLD GALVANIZING COMPOUND PER ASTM A790 AND MANUFACTURERS REQUIREMENTS.

**APPLICABLE CODES AND STANDARDS**

1. ANS/IEEE: STRUCTURAL STANDARDS FOR ANTENNA SUPPORTING STRUCTURES AND ANTENNAS, 222-G EDITION.
2. 2003 INTERNATIONAL BUILDING CODE WITH 2005 CONNECTICUT SUPPLEMENTS & 2008 CONNECTICUT AMENDMENTS.
3. ACI 318: AMERICAN CONCRETE INSTITUTE, BUILDING CODE REQUIREMENTS FOR STRUCTURAL CONCRETE, 318-08.
4. CRSI: CONCRETE REINFORCING STEEL INSTITUTE, MANUAL OF STANDARD PRACTICE, LATEST EDITION.
5. AISC: AMERICAN INSTITUTE OF STEEL CONSTRUCTION, MANUAL OF STEEL CONSTRUCTION, LATEST EDITION.
6. AWS: AMERICAN WELDING SOCIETY D1.1, STRUCTURAL WELDING CODE, LATEST EDITION.

**STRUCTURAL STEEL**

1. ALL DETAILING, FABRICATION AND ERECTION OF STRUCTURAL STEEL SHALL CONFORM TO THE AISC SPECIFICATIONS, LATEST EDITION.
2. ALL EXPOSED STRUCTURAL STEEL MEMBERS SHALL BE HOT-DIPPED GALVANIZED AFTER FABRICATION PER ASTM A123. EXPOSED STEEL HARDWARE AND ANCHOR BOLTS SHALL BE GALVANIZED PER ASTM A133 OR B95.
3. ALL U-BOLTS SHALL BE ASTM A307 OR EQUIVALENT, WITH LOCKING DEVICE, UNLESS NOTED OTHERWISE.




THESE DRAWINGS AND/OR THE ACCOMPANYING SPECIFICATIONS ARE THE PROPERTY OF AMERICAN TOWER STRUCTURAL ENGINEERING, INC. AND SHALL BE KEPT IN THE ORIGINAL SITE OFFICE. ANY REPRODUCTION OR TRANSMISSION OF ANY PART IS PROHIBITED EXCEPT BY WRITTEN PERMISSION OF AMERICAN TOWER CORPORATION. THESE DRAWINGS AND/OR SPECIFICATIONS SHALL REMAIN THE PROPERTY OF AMERICAN TOWER CORPORATION AND SHALL BE KEPT IN THE ORIGINAL SITE OFFICE. ANY REPRODUCTION OR TRANSMISSION OF ANY PART IS PROHIBITED EXCEPT BY WRITTEN PERMISSION OF AMERICAN TOWER CORPORATION. THESE DRAWINGS AND/OR SPECIFICATIONS SHALL REMAIN THE PROPERTY OF AMERICAN TOWER CORPORATION AND SHALL BE KEPT IN THE ORIGINAL SITE OFFICE. ANY REPRODUCTION OR TRANSMISSION OF ANY PART IS PROHIBITED EXCEPT BY WRITTEN PERMISSION OF AMERICAN TOWER CORPORATION.

REV.	DESCRIPTION	BY	DATE
1	ISSUE	JMB	06/19/2008
2			
3			


SITE NUMBER: 302506  
 SITE NAME: WINCHESTER CT 3  
 CONNECTICUT  
 SITE ADDRESS: 15 OAKDALE AVENUE  
 WINSTED, CT 06098

DRAWN BY:	JMB
CHECKED BY:	BKL
DATE DRAWN:	10/24/08
ATC JOB NO.:	49223432
SHEET TITLE:	


BASE PLATE STIFFENER INSTALLATION	
SHEET NUMBER:	A-1
REV. #	0



ELEVATION VIEW  
 BASE PLATE STIFFENER INSTALLATION



PLAN VIEW  
 BASE PLATE STIFFENER INSTALLATION



SECTION "A-A"  
 TYPICAL STIFFENER WELD



THESE DRAWINGS AND/OR THE ACCOMPANYING SPECIFICATIONS ARE THE PROPERTY OF AMERICAN TOWER. NO REUSE, REPRODUCTION, OR ADAPTATION OF THESE DRAWINGS OR SPECIFICATIONS IN ANY MANNER, OR IN ANY PART, IS PROHIBITED EXCEPT BY WRITTEN PERMISSION FROM AMERICAN TOWER CORPORATION. ANY SUCH VIOLATION SHALL BE DEEMED TO BE A VIOLATION OF THE PATENT RIGHTS OF AMERICAN TOWER CORPORATION, WHICH SHALL CONSTITUTE PRIMA FACIE EVIDENCE OF ACCEPTANCE OF THESE RESTRICTIONS.

REV.	DESCRIPTION	BY	DATE
1/0	FIRST ISSUE	JMB	10/22/08

SITE NUMBER:  
**VARIOUS**


SITE NAME:  
**VARIOUS**

SITE ADDRESS:  
**VARIOUS**

DRAWN BY:	JMB
CHECKED BY:	B KL
DATE DRAWN:	10/24/08
A.T.C. JOB NO.:	VARIOUS
SHEET TITLE:	

STIFFENER

SHEET NUMBER:	ST6615	REV. #	0
---------------	--------	--------	---



DESCRIPTION	LENGTH	REMARKS	REV	WT	TOTAL WEIGHT: 12.2#
PL 3/4" X 6"	1'-3"			11.6#	
MATERIAL:		A572 GR. 50	FINISH: GALVANIZE		
HOLES:		N/A	TOTAL WEIGHT: 12.2#		

## Technical Memo

To: Jennifer Gaudet  
From: Scott Heffernan - Radio Frequency Engineer  
cc: Jason Overbey  
Subject: Power Density Report for CTNH403A  
Date: October 29, 2008

### 1. Introduction:

This report is the result of an Electromagnetic Field Intensities (EMF - Power Densities) study for the T-Mobile PCS antenna installation on a Monopole at 15 Oakdale Ave, Winchester, CT. This study incorporates the most conservative consideration for determining the practical combined worst case power density levels that would be theoretically encountered from locations surrounding the transmitting location.

### 2. Discussion:

The following assumptions were used in the calculations:

- 1) The emissions from T-Mobile transmitters are in the 1935-1985 MHz frequency band.
- 2) The antenna array consists of three sectors, with 3 antennas per sector.
- 3) The model number for each antenna is APX16PV-16PVL-E.
- 4) The antenna center line height is 166 ft.
- 5) The maximum transmit power from any sector is 1908.23 Watts Effective Radiated Power (EIRP) assuming 8 channels per sector.
- 6) All the antennas are simultaneously transmitting and receiving, 24 hours a day.
- 7) Power levels emitting from the antennas are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.
- 8) The average ground level of the studied area does not change significantly with respect to the transmitting location

Equations given in "FCC OET Bulletin 65, Edition 97-01" were then used with the above information to perform the calculations.

### 3. Conclusion:

Based on the above worst case assumptions, the power density calculation from the T-Mobile PCS antenna installation on a Monopole at 15 Oakdale Ave, Winchester, CT, is 0.01635 mW/cm<sup>2</sup>. This value represents 1.635% of the Maximum Permissible Exposure (MPE) standard of 1 milliwatt per square centimeter (mW/cm<sup>2</sup>) set forth in the FCC/ANSI/IEEE C95.1-1991. Furthermore, the proposed antenna location for T-Mobile will not interfere with existing public safety communications, AM or FM radio broadcasts, TV, Police Communications, HAM Radio communications or any other signals in the area.

Total Site MPE %:	27.765%
-------------------	---------

# New England Market



## Worst Case Power Density

Site:	CTNH403A
Site Address:	15 Oakdale Ave
Town:	Winchester
Tower Height:	180 ft.
Tower Style:	Monopole
Base Station TX output	25 W
Number of channels	8
Antenna Model	APX16PV-16PVL-E
Cable Size	1 5/8
Cable Length	190 ft.
Antenna Height	166.0 ft.
Ground Reflection	1.6
Frequency	1945.0 MHz
Jumper & Connector loss	4.50 dB
Antenna Gain	16.5 dBi
Cable Loss per foot	0.0116 dB
Total Cable Loss	2.2040 dB
Total Attenuation	6.7040 dB
Total EIRP per Channel (In Watts)	53.78 dBm 238.53 W
Total EIRP per Sector (In Watts)	62.81 dBm 1908.23 W
nsg	9.7960
<b>Power Density (S) =</b>	<b>0.016353 mW/cm<sup>2</sup></b>
<b>T-Mobile Worst Case % MPE =</b>	<b>1.6353%</b>
Equation Used :	$S = \frac{(1000)(grf)^2 (Power)^{nsg}}{4\pi (R)^2}$
Office of Engineering and Technology (OET) Bulletin 65, Edition 97-01, August 1997	

Additional Carrier Information (% MPE)	
AT&T (TDMA)	2.90%
AT&T GSM (Cellular)	1.07%
AT&T GSM (PCS)	0.91%
Alltel (AT&T)	1.86%
CT State Police	5.25%
AT&T (PCS)	0.48%
Sprint (PCS)	7.97%
Verizon Wireless (PCS)	1.38%
Nextel (SMR)	4.31%
<b>Total % MPE for Site</b>	<b>27.765%</b>