



April 19, 2022

Melanie A. Bachman
Executive Director
Connecticut Siting Council
10 Franklin Square
New Britain, CT 06051

Re: Tower Share Application – Dish Wireless Site # 13733434
Dish Wireless Telecommunications Facility @ 87 West Quasset Road, Woodstock, CT 06281

Dear Ms. Bachman,

Dish Wireless (“Dish”) is proposing a wireless telecommunications facility on an existing one hundred forty nine (149) foot tall monopole tower at 87 West Quasset Road, Woodstock, CT 06281 (Latitude: 41.9297847, Longitude: -71.98933794) and within the existing fenced compound on the above referenced property. The monopole tower is owned and operated by American Tower Corporation. The subject property is owned by Quasset Hill Farm LLC. The tower was approved by the Siting Council on November 17, 2011, docket number 415.

Dish proposes to install a five (5) foot by seven (7) foot metal platform within the existing fenced compound to accommodate two (2) cabinets and related equipment, and to install three (3) antennas, a single antenna mount, six (6) RRUs, and cables on the existing tower at one hundred twenty seven (127) feet as more particularly detailed and described on the enclosed Construction Drawings. The overall height of the tower will remain at 149 feet and no changes will be made to the compound dimensions.

Please accept this letter as notification pursuant to Regulations of Connecticut State Agencies 16-50aa, of Dish's intent to share a telecommunications facility pursuant to R.C.S.A. 16-50j-88. In accordance with R.C.S.A §16-50j-73, a copy of this letter is being sent to the following individuals: American Tower Corporation as Tower Operator/Owner, Quasset Hill Farm LLC as Property Owner; the Honorable Jay Swan, the First Selectman of Woodstock, and Ashley Stephens, the Land Use Administrator & Zoning Enforcement Official for the Town of Woodstock.

The planned modifications to the facility fall squarely within those activities explicitly provided for in R.C.S.A. §16-50j-89. Specifically:

1. The proposed modifications will NOT result in an increase in the height of the existing structure.
2. The proposed modifications will NOT require an extension of the site boundary.



3. The proposed modifications will NOT increase noise levels at the facility by six decibels or more, or to levels that exceed state and local criteria.
4. The operation of the modified facility will NOT increase radio frequency emissions at the facility to a level at or above the Federal Communications Commission (FCC) safety standard. Please see the RF emissions calculation for DISH's modified facility enclosed herewith.
5. The proposed modifications will NOT cause an ineligible change or alteration in the physical or environmental characteristics of the site.
6. The existing structure and its foundation can support the proposed loading. Please see the structural analysis enclosed herewith.

Connecticut General Statute 16-50aa indicates that the Council must approve the shared use of a telecommunications facility provided it finds the shared use is technically, legally, environmentally, and economically feasible and meets public safety concerns. As demonstrated in this letter, Dish respectfully indicates that the shared use of this facility satisfies these criteria:

- A. **Technical Feasibility.** The existing monopole has been deemed structurally capable of supporting Dish's proposed loading (see attached Structural Analysis).
- B. **Legal Feasibility.** As referenced above, C.G.S. 16-50aa has been authorized to issue orders approving the shared use of an existing tower. Under the authority granted to the Council, an order of the Council approving the requested shared use would permit Dish to obtain a building permit for the proposed installation. Further, a Letter of Authorization is attached, authorizing Dish to file this application.
- C. **Environmental Feasibility.** The proposed use of this facility would have a minimal environmental impact. The installation of Dish equipment at the 127-foot level of the existing 149-foot tower would have an insignificant visual impact on the area around the tower. Dish ground equipment would be installed within the existing facility compound. The Dish proposal would therefore not cause any significant alteration in the physical or environmental characteristics of the existing site. Additionally, as evidenced by the attached EME study, the proposed antennas would not increase radio frequency emissions to a level at or above the Federal Communications Commission safety standard.
- D. **Economic Feasibility.** Dish will be entering into an agreement with the owner of this facility to mutually agreeable terms. As previously mentioned, the Letter of Authorization has been provided by the owner to assist Dish with this tower sharing application.
- E. **Public Safety Concerns.** As discussed above, the tower is structurally capable of supporting the proposed loading. Dish is not aware of any public safety concerns relative to the proposed sharing of the existing tower. Dish's intentions of providing new and improved wireless service through the shared use of this facility is expected to enhance the safety and welfare of local residents and individuals traveling through the area.



For the foregoing reasons, Dish respectfully requests that the Council approve this request for the shared use of this tower located at 87 West Quasset Road, Woodstock, CT 06281.

If you have any questions, please feel free to contact me.

Sincerely,

A handwritten signature in blue ink, appearing to read 'Jack Andrews', is written over a circular blue stamp or seal.

Jack Andrews
Zoning Manager, Centerline Communications
10130 Donleigh Drive
Columbia, MD 21046
443-677-0144

Enclosures: Exhibit 1 – Letter of Authorization from tower owner
 Exhibit 2 – Property Card and GIS
 Exhibit 3 – Construction Drawings
 Exhibit 4 – Structural Analysis Report
 Exhibit 5 – EME Study Report
 Exhibit 6 – Original Tower Approval
 Exhibit 7 – (4) Notice Confirmations

cc: American Tower Corporation - Tower Operator/Owner
 Quasset Hill Farm LLC - Property Owner
 The Honorable Jay Swan - First Selectman of Woodstock
 Ashley Stephens - Woodstock Land Use Administrator & Zoning Enforcement Official



LETTER OF AUTHORIZATION

SITE NO: See Site List Below

SITE NAME: See Site List Below

ADDRESS: See Site List Below

I, Margaret Robinson, Senior Counsel, US Tower Division on behalf of American Tower*, owner and/or operator of the tower facilities located at the addresses identified below (the "Tower Facilities"), do hereby authorize Centerline Communications, LLC ("Centerline"), its agents, successors and assigns, to act as American Tower's non-exclusive agent for the purpose of filing and securing any zoning, land-use, building permit and/or electrical permit application(s) and approvals of the applicable jurisdiction for and to conduct the construction of the installation of antennas and related telecommunications equipment owned and operated by DISH Network on the Tower Facilities located at the addresses identified below. This installation shall not affect adjoining lands and will occur only within the areas leased or owned by American Tower.

American Tower understands that the applications may be denied, modified or approved with conditions. The above authorization is limited to the acceptance by American Tower of conditions related to American Tower's installations. Any such conditions of approval or modifications will not be effective unless approved in writing by American Tower.

The above authorization does not permit Centerline to modify or alter any existing permit(s) and/or zoning or land-use conditions or impose any additional conditions unrelated to American Tower's installations of telecommunications equipment without the prior written approval of American Tower.

Site Authorized:

ATC PROJECT#	ATC SITE#	DISH SITE#	ADDRESS
13683503	302472	BOBDL00010A	104 Bunker Hill Road, Andover, Connecticut
13701209	302470	BOHVN00141A	401 Wakelee Ave, Ansonia, Connecticut
13702524	370641	BOHVN00148A	401-411 Lopus Road, Beacon Falls, Connecticut
13709244	88008	BOHVN00151A	9 Meyers Road, Bethany, Connecticut
13694329	283419	BOHVN00136A	123 Pine Orchard Road, Branford, Connecticut
13694332	283422	BOHVN00137A	171 Short Beach Road, Branford, Connecticut
13701211	302484	BOHVN00142A	405 Brushy Plain Rd, Branford, Connecticut
13709418	281862	BOHVN00200A	111 SECOND HILL RD, BRIDGEWATER, Connecticut
13733440	411216	BOBOS00893A	123 Palmer Road, Chaplin, Connecticut
13733449	208478	BOHVN00033A	1325 Cheshire Street, Cheshire, Connecticut
13694579	302496	BOBOS00887A	Chestnut Hill Road, Colchester, Connecticut
13694582	302465	BOBOS00890A	355 Route 85, Colchester, Connecticut
13733436	6270	BOBOS00031A	Rt 101 off Rt. 395 @1385 North Rd., Dayville, Connecticut
13702522	311305	BOHVN00147A	10 Tanner Marsh Road, Guilford, Connecticut
13733446	10029	BOBOS00894A	185 Fisk Road, Hampton, Connecticut
14046283	302466	BOBDL00079B	305 W. Service Rd., Hartford, Connecticut



13746611	302503	BOBOS00068B	20 Mel Road, Jewett City, Connecticut
13702514	302540	BOHVN00146A	8 Old 79, Madison, Connecticut
OAA745087	411260	Middlefield CT	484 Meriden Rd., Middlefield, Connecticut
13698061	283564	BOHVN00139A	234 Melba Street, Milford, Connecticut
13702496	302516	BOHVN00144A	438 Bridgeport Ave, Milford, Connecticut
13693709	411182	BOHVN00005A	20 Antolini Road, New Hartford, Connecticut
13702509	302523	BOHVN00145A	4 Elkington Farm Rd, New Milford, Connecticut
13693659	283418	BOHVN00135A	50 Devine Street, North Haven, Connecticut
13694578	6260	BOBOS00884A	118C Wintechog Hill Rd., North Stonington, Connecticut
13693124	311014	BOBOS00023A	202 N Wawecus Hill Rd, Norwich, Connecticut
13726721	302532	BOBOS00022A	1337 Route 85, Oakdale, Connecticut
13693120	284984	BOBOS00021A	166 Pawcatuck Ave, Pawcatuck, Connecticut
13701212	302501	BOHVN00143A	297 North Street, Plymouth, Connecticut
13693135	411184	BOBOS00026A	399 West Road, SALEM, Connecticut
13729958	208205	BOHVN00035A	80 Great Hill Road, Seymour, Connecticut
13693705	411188	BOHVN00006A	111 Upper Fishrock Road, Southbury, Connecticut
13733433	415784	BOBOS00029A	165 Elmwood Hill Road, THOMPSON, Connecticut
13693127	370623	BOBOS00024A	139 Sharp Hill Road, Uncasville, Connecticut
13701206	302467	BOHVN00140A	90 North Plains Industrial Rd., Wallingford, Connecticut
13693131	411183	BOBOS00025A	53 Dayton Rd., Waterford, Connecticut
13693702	243036	BOHVN00132A	668 Jones Hill Road, West Haven, Connecticut
13729960	207941	BOHVN00036A	164 County Road, Wolcott, Connecticut
13702538	411180	BOHVN00150A	481 GOOD HILL ROAD, Woodbury, Connecticut
13733429	415439	BOBOS00027A	40 Sherman Road, Woodstock, Connecticut
13733431	415484	BOBOS00028A	445 Prospect St, Woodstock, Connecticut
13733434	418609	BOBOS00030A	87 West Quasset Road, Woodstock, Connecticut
13733438	6300	BOBOS00032A	156 Lebanon Hill Rd., Woodstock, Connecticut
13741553	283425	BOBOS00019A	350 Route 198, WOODSTOCK VALLEY, Connecticut
13743708	305310	BOPWM00004A	491 Court Street, Auburn, Maine
13743725	371976	BOPWM00007A	840 North River Rd, Auburn, Maine
13741457	371989	BOAUG00001A	627 Coldbrook Rd, BANGOR, Maine
13741460	416485	BOAUG00002A	237 Bomarc Rd, BANGOR, Maine
13735679	305311	BOBOS00433A	19 Little Harbor Road, Berwick, Maine
13746623	416552	BOPWM00012A	60 Andrews Road, Biddeford, Maine
13741463	305313	BOBOS00434A	71 Brixham Road, Eliot, Maine
13743702	10044	BOPWM00002A	26 Dorrington Drive, Freeport, Maine
13743704	281252	BOPWM00003A	71 Finn Parker Road, GORHAM, Maine



13746621	371994	BOPWM00011A	4 Burnham Rd, Gorham, Maine
13746617	371990	BOPWM00009A	58 Buzzell Ln, Greene, Maine
13743722	371965	BOPWM00006A	67 Commercial Street, Lewiston, Maine
13746678	421397	BOPWM00013A	50 Potter Road, Lisbon, Maine
13743712	371964	BOPWM00005A	Pleasant Hill Rd, Sabattus, Maine
13738176	371992	BOBOS00777A	78 York Woods Rd, Rt 236, South Berwick, Maine
13743727	371978	BOPWM00008A	988 Roosevelt Trail, Windham, Maine
13746619	371993	BOPWM00010A	413 Roosevelt Tr, Windham, Maine
13734197	222167	BOBOS00393A	36 Knox trail, Acton, Massachusetts
13738223	371800	BOBOS00698A	107 South Main Street, Acushnet, Massachusetts
13738186	203692	BOBOS00788A	149 Haggets Pond Road, Andover, Massachusetts
13738208	371807	BOBOS00820A	165 South Main Street, ASSONET, Massachusetts
13728723	305010	BOBOS00387C	15 Washington Street, Attleboro, Massachusetts
13729951	92225	BOBOS00135A	55 Starkey Ave, Attleboro, Massachusetts
13729930	91563	BOBOS00133A	21 Parker Drive, Avon, Massachusetts
13738187	371838	BOBOS00791A	30 Shawsheen Ave, Bedford, Massachusetts
13734227	91567	BOBOS00612A	236 Maple Street, Bellingham, Massachusetts
13738231	88025	BOBOS00832A	39 Green Street, Berkley, Massachusetts
13746597	207264	BOBOS00281A	62R Anthony Street, Berkley, Massachusetts
13738152	283474	BOBOS00658A	347 Old Middlesex Turnpike, Billerica, Massachusetts
13734192	371816	BOBOS00616A	500 Morton Street, Boston, Massachusetts
13735268	305088	BOBOS00626A	22 Freeport Way, Boston, Massachusetts
13735650	262364	BOBOS00016A	53 C Pond Street, Boxford, Massachusetts
13729495	371820	BOBOS00004B	#26 Freemans Way Industrial Park, Brewster, Massachusetts
13735663	305054	BOBOS00111A	240 Burrill Avenue, Bridgewater, Massachusetts
13738201	414820	BOBOS00809A	434 Elm St., BRIDGEWATER, Massachusetts
13735259	371833	BOBOS00619A	1001 N Montello Street, Brockton, Massachusetts
13735275	371797	BOBOS00629A	500 Belmont Street, Brockton, Massachusetts
13735419	10008	BOBOS00646A	995 Belmont St., Brockton, Massachusetts
13738182	10342	BOBOS00670A	110 Mulberry Street, Brockton, Massachusetts
13738228	15456	BOBOS00389A	51 North Avenue, Burlington, Massachusetts
13746607	210761	BOBOS00139A	8 Springdale Avenue, Canton, Massachusetts
13734206	5870	BOBOS00395A	Off Montello Street, Carver, Massachusetts
13734212	15482	BOBOS00396A	31R Main Street, Carver, Massachusetts
13741598	10252	BOBOS00428A	31 J Hammond Road, Charlton, Massachusetts
13735290	371819	BOBOS00638A	7 Doris Drive, Chelmsford, Massachusetts
13759832	274893	BOBOS00636A	490 Stafford St., CHERRY VALLEY, Massachusetts



13729557	412707	BOBOS00125A	40y Annursnac Hill Road, CONCORD, Massachusetts
13738190	240688	BOBOS00793A	323 Locust St, Danvers, Massachusetts
13735284	371805	BOBOS00631A	303 Broadway, Dracut, Massachusetts
13729926	5820	BOBOS00131A	32 Old County Road, East Wareham, Massachusetts
13734265	207267	BOBOS00282A	Upper Union Street, Franklin, Massachusetts
13735297	371782	BOBOS00644A	119 Dean Avenue, Franklin, Massachusetts
13735315	16228	BOBOS00649A	60 EARL'S WAY, Franklin, Massachusetts
13735654	10321	BOBOS00102A	16 Kondelin Rd, Gloucester, Massachusetts
13735670	305111	BOBOS00192B	400 Blackburn Drive, Gloucester, Massachusetts
13746594	210758	BOBOS00137A	434-438 Asbury Street, Hamilton, Massachusetts
13735658	283651	BOBOS00108A	263 Winter Street, Hanover, Massachusetts
13735666	371796	BOBOS00114A	171 Phillips Street, Hanson, Massachusetts
13741290	283476	BOBOS00615A	75 Willow Avenue, Haverhill, Massachusetts
13741718	283472	BOBOS01024A	1 Masys Way, Haverhill, Massachusetts
13743700	15659	BOBOS00903A	260 River Street, Jefferson, Massachusetts
13738229	305004	BOBOS00831A	23 Freetown Steet, Lakeville, Massachusetts
13735281	305117	BOBOS00630A	670 South Union Street, LAWRENCE, Massachusetts
13735286	371778	BOBOS00633A	576 Haverhill St, Lawrence, Massachusetts
13735709	210759	BOBOS00138A	280 New Lancaster Road, Leominster, Massachusetts
13743687	371808	BOBOS00853A	650 Willard Street, Leominster, Massachusetts
13735656	222165	BOBOS00105A	2005 Mass Ave, Lunenburg, Massachusetts
13734270	207263	BOBOS00283A	13 Mill Street, Marion, Massachusetts
13729921	412712	BOBOS00128A	860 BOSTON POST ROAD, Marlborough, Massachusetts
13738193	284981	BOBOS00806A	969 Ocean Street, Marshfield, Massachusetts
13746615	207266	BOBOS00284A	Holyoke Avenue, Marshfield, Massachusetts
13772780	202550	BOBOS01156C	0 Snow Road, Marshfield, Massachusetts
13735659	305027	BOBOS00109A	34 Topalian Street, Mattapan, Massachusetts
13734275	208176	BOBOS00285A	Summer Hill Road, Maynard, Massachusetts
13734201	16489	BOBOS00391A	31 BEDFORD ST, Middleboro, Massachusetts
13738205	305006	BOBOS00813A	164 Everett Street, Middleboro, Massachusetts
13735294	283071	BOBOS00641A	11 Natsue Way, MIDDLETON, Massachusetts
13735657	283070	BOBOS00107A	197 N. Main Street, MIDDLETON, Massachusetts
13743676	283767	BOBOS00842A	120 Highland Street, MILFORD, Massachusetts
13749484	91566	BOBOS00355B	111 Cedar Street, Milford, Massachusetts
13729925	412713	BOBOS00129A	25 Glenwood Street, Natick, Massachusetts
13734249	5762	BOBOS00614A	1555 Central Ave, Needham, Massachusetts
13735272	5860	BOBOS00628A	148 Penniman St., New Bedford, Massachusetts



13737649	204458	BOBOS00651A	9 Eighth St, NEW BEDFORD, Massachusetts
13742882	305097	BOBOS00426A	127 R Duchaine Blvd., New Bedford, Massachusetts
13735652	1028	BOBOS00101A	1165 Chestnut Street, Newton, Massachusetts
13735266	305113	BOBOS00624A	20 Republic Road, North Billerica, Massachusetts
13742899	91886	BOBOS00758A	411 FAUNCE CORNER RD, North Dartmouth, Massachusetts
13738213	371810	BOBOS00829A	455 Somerset Avenue, North Dighton, Massachusetts
13741485	88027	BOBOS00833A	Maple Street, North Dighton, Massachusetts
13743644	91565	BOBOS00735A	38 Merriam District, North Oxford, Massachusetts
13735264	284980	BOBOS00620A	59 Davis Ave, Norwood, Massachusetts
13746603	207726	BOBOS00287A	15 Locust Road, Orleans, Massachusetts
13738197	15768	BOBOS00807A	171Mattakeesett Street, Pembroke, Massachusetts
13729507	371799	BOBOS00115A	75 Washington Street, Plainville, Massachusetts
13742871	10370	BOBOS00422A	50 Portside Drive, Pocasset, Massachusetts
13734236	10341	BOBOS00613A	106 Mazzeo Drive, Randolph, Massachusetts
13738200	305096	BOBOS00808A	1588 Broadway, Raynham, Massachusetts
13738203	10339	BOBOS00810A	678 Church Street, Raynham, Massachusetts
13738206	310959	BOBOS00817A	153 Cranberry Highway, Rochester, Massachusetts
13734282	207270	BOBOS00288A	320 Pleasant Street, Rockland, Massachusetts
13738199	305035	BOBOS00673A	488R Highland Avenue, Salem, Massachusetts
13742875	273378	BOBOS00423A	413 Rt 130, Sandwich, Massachusetts
13734198	10340	BOBOS00394A	1010 Chief Justice Cushing Highway, Scituate, Massachusetts
13741690	282810	BOBOS01155A	361 TILDEN RD, SCITUATE, Massachusetts
13729506	16459	BOBOS00103A	45 Vineyard Road, Seekonk, Massachusetts
13735664	207271	BOBOS00280A	212 Lake Street, Sherborn, Massachusetts
13738202	305051	BOBOS00674A	16 Kendall Avenue, Sherborn, Massachusetts
13735748	202086	BOBOS00659A	271 Spring Street, Shrewsbury, Massachusetts
13743636	91568	BOBOS00688A	800 Boston Turnpike, Shrewsbury, Massachusetts
13710032	371813	BOBOS00118A	3 Redemption Rock Trail, Sterling, Massachusetts
13741607	416056	BOBOS00866A	199 Raymond Rd., Sudbury, Massachusetts
13870803	371774	BOBOS00013D	142 North Road, Sudbury, Massachusetts
13743641	305009	BOBOS00733A	7 Kamaitas Road, Sutton, Massachusetts
13743672	305014	BOBOS00841A	194 Stone School Road, Sutton, Massachusetts
13742886	5830	BOBOS00427A	28 Dana Street, Taunton, Massachusetts
13729513	388560	BOBOS00122A	89 Progress Avenue, Tyngsboro, Massachusetts
13743680	305104	BOBOS00845A	87 Adams St., Upton, Massachusetts
13743669	305110	BOBOS00838A	70 Quaker Street, Uxbridge, Massachusetts
13734219	275069	BOBOS00601A	110 Bear Hill, Waltham, Massachusetts




13737625	5810	BOBOS00816A	Thatcher Street, Wareham, Massachusetts
13743683	274897	BOBOS00851A	0 Century Drive, West Boylston, Massachusetts
13749477	305068	BOBOS00664B	225 Rivermoor St., West Roxbury, Massachusetts
13682009	283067	BOBDL00158A	1201 Westfield Street, WEST SPRINGFIELD, Massachusetts
13743698	9238	BOBOS00878A	972 Gilbert Road, West Warren, Massachusetts
13735736	305105	BOBOS00637A	25 Brigham Street, Westborough, Massachusetts
13743638	282319	BOBOS00690A	50 SMITH VALVE PKWY, WESTBOROUGH, Massachusetts
13734203	305034	BOBOS00392A	8 Nixon Rd., Westford, Massachusetts
13734284	274896	BOBOS00334B	19 Oak Street, Weston, Massachusetts
13735662	305041	BOBOS00110A	0 Nonesuch Road, Weston, Massachusetts
13742877	91559	BOBOS00425A	251 State Road, Westport, Massachusetts
13729511	371818	BOBOS00120A	611 Pleasant Street, Weymouth, Massachusetts
13735271	305028	BOBOS00627A	106 Finnell Dr., Weymouth, Massachusetts
13735303	282706	BOBOS00645A	10 Presidential Way, Woburn, Massachusetts
13772775	305060	BOBOS01068A	Green Street, Wrentham, Massachusetts
13741478	15136	BOBOS00443A	73 State Route 111, Atkinson, New Hampshire
13743271	91575	BOBOS00457A	437 Patten Hill Road, Candia, New Hampshire
13743029	306604	BOBOS00446A	359 Chester Street, Chester, New Hampshire
13743257	373098	BOBOS00449A	50 Town Dump Road, Chester, New Hampshire
13743267	88065	BOBOS00455A	674 Haverhill Road, Chester, New Hampshire
13743035	373099	BOBOS00450A	203 Haverhill Road, East Kingston, New Hampshire
13738226	91574	BOBOS00768A	49 Shirking Road, Epping, New Hampshire
13743263	373114	BOBOS00453A	7 CONTINENTAL DRIVE, Exeter, New Hampshire
13738179	373094	BOBOS00781A	789 Main Street, Fremont, New Hampshire
13743264	413027	BOBOS00454A	169 HAYDEN ROAD, HOLLIS, New Hampshire
13741480	15138	BOBOS00444A	36 Depot Road, Kingston, New Hampshire
13738183	273268	BOBOS00785A	242 New Derry Rd, Litchfield, New Hampshire
13738224	373116	BOBOS00705A	94 STONEHEDGE ROAD, Londonderry, New Hampshire
13743269	88069	BOBOS00456A	187A Pillsbury Road, Londonderry, New Hampshire
13738211	91571	BOBOS00683A	20 Daniel Webster Highway, Merrimack, New Hampshire
13741468	10304	BOBOS00441A	211 Ford Farm Road, Milton, New Hampshire
13743256	311757	BOBOS00448A	61 Old Coach Road, New Boston, New Hampshire
13743258	373101	BOBOS00451A	85 South Main Street, Newton, New Hampshire
13743031	311755	BOBOS00447A	34 Tower Hill Road, Pelham, New Hampshire
13741470	15134	BOBOS00442A	36 Cross Road, Rochester, New Hampshire
13743027	240696	BOBOS00445A	40 Jessie Doe Road, Rollinsford, New Hampshire
13743259	373102	BOBOS00452A	393 Main Street, Sandown, New Hampshire



13714952	307060	SYSYR00023A	200 Irwin Road, Buffalo, New York
13767336	415364	SYSYR00507B	183 Saltonstall Street, Canandaigua, New York
13702046	373349	ALALB00011A	75 Van Dyke Road, Delmar, New York
13973540	392593	SYSYR00038A	571 Main Street, East Aurora, New York
13752077	413141	SYSYR00517B	91 Railroad Ave, Hamlin, New York
13713785	16467	SYSYR00015A	3181 Southwestern Blvd, Orchard Park, New York
13714492	414560	SYSYR00061A	4248 S. Taylor Road, Orchard Park, New York
13870807	91916	SYSYR00081A	County Route 6 and Fox Dr, Phoenix, New York
13712307	413140	SYSYR00407A	3830 Monroe Avenue, Pittsford, New York
13704766	91936	ALALB00020A	1245 Kings Road, SCHENECTADY, New York
OAA745429	280868	0190112-A	10790 Taylors Store Rd, Nashville, North Carolina
13741714	91582	BOBOS00881A	395 Woodville Road, Ashaway, Rhode Island
13738163	91983	BOBOS00662A	99 Tupelo Street, Bristol, Rhode Island
13743277	308765	BOBOS00586B	6 Minturn Farm Road, Bristol, Rhode Island
13742900	281265	BOBOS00899A	1380 Putnam Pike, CHEPACHET, Rhode Island
13735691	374117	BOBOS00522A	149 Laten Knight Road, Cranston, Rhode Island
13738222	374136	BOBOS00697A	1000 New London Avenue, Cranston, Rhode Island
13735296	374138	BOBOS00642A	500 Veterans Memorial Parkway, East Providence, Rhode Island
13738188	308768	BOBOS00672A	1 Dexter Road, East Providence, Rhode Island
13742895	1031	BOBOS00677A	2 Sunderland Road, Exeter, Rhode Island
13741622	374114	BOBOS00898A	2185 Putnam Pike, Glocester, Rhode Island
13743044	308772	BOBOS00519A	1677 Maple Valley Road, Greene, Rhode Island
13774131	91984	BOBOS00518B	2612 Victory Hwy, Harrisville, Rhode Island
13737644	91985	BOBOS00650A	74 Maria Ave., JOHNSTON, Rhode Island
13738150	273282	BOBOS00654A	32 Breakneck Hill Road, Lincoln, Rhode Island
13735720	6350	BOBOS00525A	1230 Chopmist Hill Rd. Rt. 102, North Scituate, Rhode Island
13743039	308766	BOBOS00517A	316 South Main St., Pascoag, Rhode Island
13738157	91581	BOBOS00661A	10 Dunnell Lane, Pawtucket, Rhode Island
13741493	91584	BOBOS00836A	205 Farnum Pike, Smithfield, Rhode Island
14049070	308759	BOBOS00587C	2935 Tower Hill Road, South Kingstown, Rhode Island
13738210	374137	BOBOS00828A	408 Stafford Road, Tiverton, Rhode Island
13738221	91986	BOBOS00696A	15 New Industrial Road, Warren, Rhode Island
13743273	308757	BOBOS00584B	289 Kilvert Street, Warwick, Rhode Island
13735687	374115	BOBOS00521A	244 Plain Road, West Greenwich, Rhode Island
13735723	91578	BOBOS00583A	830 Nooseneck Hill Road, West Greenwich, Rhode Island
13735700	374133	BOBOS00524A	226C Cowesett Avenue, West Warwick, Rhode Island
13735726	91579	BOBOS00585B	195 J.P. Murphy Highway, West Warwick, Rhode Island



13742891	207962	BOBOS00552A	37 Laurel Avenue, Westerly, Rhode Island
13735695	374119	BOBOS00523A	9 New Kings Factory Road, Wood River Junction, Rhode Island

Signature: 
Margaret Robinson, Senior Counsel
US Tower Division


NOTARY BLOCK

COMMONWEALTH OF MASSACHUSETTS
County of Middlesex

This instrument was acknowledged before me by Margaret Robinson, Senior Counsel of American Tower (owner and/or operator of the above referenced Tower Facilities), personally known to me (or proved to me on the basis of satisfactory evidence) to be the person whose name is subscribed to the within instrument and acknowledged to me that he/she executed the same.

WITNESS my hand and official seal, this 24th day of March, 2022.

NOTARY SEAL  **GERARD T. HEFFRON**
Notary Public
Commonwealth of Massachusetts
My Commission Expires
August 9, 2024


Notary Public Gerard T. Heffron
My Commission Expires: August 9th, 2024

* American Tower as used herein is defined as American Tower Corporation and any of its affiliates or subsidiaries.

DOCKET NO. 415 - Cellco Partnership d/b/a Verizon Wireless	}	Connecticut
application for a Certificate of Environmental Compatibility and	}	
Public Need for the construction, maintenance and operation of a	}	Siting
telecommunications facility located at 87 West Quasset Road,	}	
Woodstock, Connecticut.	}	Council

November 17, 2011

Decision and Order

Pursuant to the foregoing Findings of Fact and Opinion, the Connecticut Siting Council (Council) finds that the effects associated with the construction, maintenance, and operation of a telecommunications facility, including effects on the natural environment; ecological integrity and balance; public health and safety; scenic, historic, and recreational values; forests and parks; air and water purity; and fish and wildlife are not disproportionate, either alone or cumulatively with other effects, when compared to need, are not in conflict with the policies of the State concerning such effects, and are not sufficient reason to deny the application, and therefore directs that a Certificate of Environmental Compatibility and Public Need, as provided by General Statutes § 16-50k, be issued to Cellco Partnership d/b/a Verizon Wireless, hereinafter referred to as the Certificate Holder, for a telecommunications facility located at 87 West Quasset Road in Woodstock Connecticut. The Council denies certification of the proposed ATC replacement tower on the same parcel.

Unless otherwise approved by the Council, the facility shall be constructed, operated, and maintained substantially as specified in the Council's record in this matter, and subject to the following conditions:

1. The tower shall be constructed as a monopole, no taller than necessary to provide the proposed telecommunications services, sufficient to accommodate the antennas of the Certificate Holder and other entities, both public and private, but such tower shall not exceed a height of 150 feet above ground level. The height at the top of the Certificate Holder's antennas shall not exceed 150 feet above ground level.
2. The Certificate Holder shall prepare a Development and Management (D&M) Plan for this site in compliance with Sections 16-50j-75 through 16-50j-77 of the Regulations of Connecticut State Agencies. The D&M Plan shall be served on the Town of Woodstock for comment, and all parties and intervenors as listed in the service list, and submitted to and approved by the Council prior to the commencement of facility construction and shall include:
 - a) a final site plan(s) of site development to include specifications for the tower, tower foundation, antennas, equipment compound, radio equipment, access road, utility line, and landscaping; and,
 - b) construction plans for site clearing, grading, landscaping, water drainage, and erosion and sedimentation controls consistent with the 2002 Connecticut Guidelines for Soil Erosion and Sediment Control, as amended.
3. Prior to the commencement of operation, the Certificate Holder shall provide the Council worst-case modeling of the electromagnetic radio frequency power density of all proposed entities' antennas at the closest point of uncontrolled access to the tower base, consistent with Federal Communications Commission, Office of Engineering and Technology, Bulletin No. 65, August 1997. The Certificate Holder shall ensure a recalculated report of the electromagnetic radio frequency power density be submitted to the Council if and when circumstances in operation cause a change in power density above the levels calculated and provided pursuant to this Decision and Order.

4. Upon the establishment of any new State or federal radio frequency standards applicable to frequencies of this facility, the facility granted herein shall be brought into compliance with such standards.
5. The Certificate Holder shall permit public or private entities to share space on the proposed tower for fair consideration, or shall provide any requesting entity with specific legal, technical, environmental, or economic reasons precluding such tower sharing.
6. The Certificate Holder shall provide reasonable space on the tower for no compensation for any Town of Woodstock public safety services (police, fire and medical services), provided such use can be accommodated and is compatible with the structural integrity of the tower.
7. Unless otherwise approved by the Council, if the facility authorized herein is not fully constructed with at least one fully operational wireless telecommunications carrier providing wireless service within eighteen months from the date of the mailing of the Council's Findings of Fact, Opinion, and Decision and Order (collectively called "Final Decision"), this Decision and Order shall be void, and the Certificate Holder shall dismantle the tower and remove all associated equipment or reapply for any continued or new use to the Council before any such use is made. The time between the filing and resolution of any appeals of the Council's Final Decision shall not be counted in calculating this deadline. Authority to monitor and modify this schedule, as necessary, is delegated to the Executive Director. The Certificate Holder shall provide written notice to the Executive Director of any schedule changes as soon as is practicable.
8. Any request for extension of the time period referred to in Condition 7 shall be filed with the Council not later than 60 days prior to the expiration date of this Certificate and shall be served on all parties and intervenors, as listed in the service list, and the Town of Woodstock. Any proposed modifications to this Decision and Order shall likewise be so served.
9. If the facility ceases to provide wireless services for a period of one year, this Decision and Order shall be void, and the Certificate Holder shall dismantle the tower and remove all associated equipment or reapply for any continued or new use to the Council before any such use is made.
10. Any nonfunctioning antenna, and associated antenna mounting equipment, on this facility shall be removed within 60 days of the date the antenna ceased to function.
11. In accordance with Section 16-50j-77 of the Regulations of Connecticut State Agencies, the Certificate Holder shall provide the Council with written notice two weeks prior to the commencement of site construction activities. In addition, the Certificate Holder shall provide the Council with written notice of the completion of site construction, and the commencement of site operation.
12. The Certificate Holder shall remit timely payments associated with annual assessments and invoices submitted by the Council for expenses attributable to the facility under Conn. Gen. Stat. §16-50v.
13. This Certificate may be transferred in accordance with Conn. Gen. Stat. §16-50k(b), provided both the Certificate Holder/transferor and the transferee are current with payments to the Council for their respective annual assessments and invoices under Conn. Gen. Stat. §16-50v. In addition, both the Certificate Holder/transferor and the transferee shall provide the Council a written agreement as to the entity responsible for any quarterly assessment charges under Conn. Gen. Stat. §16-50v(b)(2) that may be associated with this facility.

14. The Certificate Holder shall maintain the facility and associated equipment, including but not limited to, the tower, tower foundation, antennas, equipment compound, radio equipment, access road, utility line and landscaping in a reasonable physical and operational condition that is consistent with this Decision and Order and a Development and Management Plan to be approved by the Council.
15. If the Certificate Holder is a wholly-owned subsidiary of a corporation or other entity and is sold/transferred to another corporation or other entity, the Council shall be notified of such sale and/or transfer and of any change in contact information for the individual or representative responsible for management and operations of the Certificate Holder within 30 days of the sale and/or transfer.

Pursuant to General Statutes § 16-50p, the Council hereby directs that a copy of the Findings of Fact, Opinion, and Decision and Order be served on each person listed below, and notice of issuance shall be published in the Norwich Bulletin.

By this Decision and Order, the Council disposes of the legal rights, duties, and privileges of each party named or admitted to the proceeding in accordance with Section 16-50j-17 of the Regulations of Connecticut State Agencies.

The parties and intervenors to this proceeding are:

Applicant

Cellco Partnership d/b/a Verizon Wireless

Its Representative

Kenneth C. Baldwin, Esq.
Robinson & Cole LLP
280 Trumbull Street
Hartford, CT 06103-3597


Sandy Carter, Regulatory Manager
Verizon Wireless
99 East River Drive
East Hartford, CT 06108

Intervenor

American Tower Corporation

Its Representative

Brandon Ruotolo, Esq.
Zoning Attorney
American Tower Corporation
10 Presidential Way
Woburn, MA 01801





87 W Quasset Rd

Woodstock, CT 06281
Building



Directions



Save



Nearby



Send to your
phone



Share



CT-169-6393-66-03



I want to...



Tools

Description



[Parcel Report](#) [Abutters Report](#)

Owner: QUASSET HILL FARM LLC

Address: 87 WEST QUASSET RD

Town: Woodstock

Hyperlinks

[Property Summary](#)

[Source Map](#)

Details

Owner Name

QUASSET HILL FARM LLC

Street Address

87 WEST QUASSET RD

Town

N/A

Gis ID

CT-169-6393-66-03

Account Number

B0029600



World To...



0 150 300ft

1:500



Home



Layers



CT-169-639...

87 WEST QUASSET RD

Location	87 WEST QUASSET RD	Mblu	6393/ 66/ 03/ /
Acct#	B0029600	Owner	QUASSET HILL FARM LLC
Assessment	\$208,090	Appraisal	\$436,200
PID	288	Building Count	1

Current Value

Appraisal			
Valuation Year	Improvements	Land	Total
2021	\$73,600	\$362,600	\$436,200
Assessment			
Valuation Year	Improvements	Land	Total
2021	\$51,500	\$156,590	\$208,090

Owner of Record

Owner	QUASSET HILL FARM LLC	Sale Price	\$0
Co-Owner		Certificate	1
Address	PO BOX 113	Book & Page	394/ 012
	WOODSTOCK , CT 06281	Sale Date	12/30/2003

Ownership History

Ownership History				
Owner	Sale Price	Certificate	Book & Page	Sale Date
QUASSET HILL FARM LLC	\$0	1	394/ 012	12/30/2003
BISHOP HAROLD R	\$0		63/ 241	05/13/1958

Building Information

Building 1 : Section 1

Year Built:

Living Area: 0

Replacement Cost: \$0

Building Percent Good:

Replacement Cost

Less Depreciation: \$0

Building Attributes	
Field	Description
Style	Outbuildings
Model	
Grade:	
Stories:	
Living Units	
Exterior Wall 1	
Exterior Wall 2	
Roof Structure:	
Roof Cover	
Interior Wall 1	

Building Photo



(<http://images.vgsi.com/photos/WoodstockCTPhotos//\00\00\01\79.JPG>)

Building Layout



Building Layout

(http://images.vgsi.com/photos/WoodstockCTPhotos//Sketches/288_288.jp)

Building Sub-Areas (sq ft)	Legend
----------------------------	--------

Interior Wall 2	
Interior Flr 1	
Interior Flr 2	
Heat Fuel	
Heat Type:	
AC Type:	
Total Bedrooms:	
Total Bthrms:	
Total Half Baths:	
Total Xtra Fixtrs:	
Total Rooms:	
Bath Style:	
Kitchen Style:	
Whirlpool Tubs	
Bsmt. Garages	

No Data for Building Sub-Areas

Building 1 : Section 1

Year Built:

Living Area: 0

Replacement Cost: \$0

Building Percent Good:

Replacement Cost

Less Depreciation: \$0

Building Attributes	
Field	Description
Style	Vacant Land
Model	

Grade:	
Stories:	
Living Units	
Exterior Wall 1	
Exterior Wall 2	
Roof Structure:	
Roof Cover	
Interior Wall 1	
Interior Wall 2	
Interior Flr 1	
Interior Flr 2	
Heat Fuel	
Heat Type:	
AC Type:	
Total Bedrooms:	
Total Bthrms:	
Total Half Baths:	
Total Xtra Fixtrs:	
Total Rooms:	
Bath Style:	
Kitchen Style:	
Whirlpool Tubs	
Bsmt. Garages	

Building Photo



(<http://images.vgsi.com/photos/WoodstockCTPhotos//default.jpg>)

Building Layout

(http://images.vgsi.com/photos/WoodstockCTPhotos//Sketches/288_10035)

Building Sub-Areas (sq ft)	<u>Legend</u>
No Data for Building Sub-Areas	



Extra Features

Extra Features	Legend
No Data for Extra Features	

Land

Land Use	Land Line Valuation
<div>Use Code</div> <div>Description</div> <div>Zone</div> <div>Neighborhood</div> <div>Alt Land Appr Category</div> <div>61O</div> <div>Farm Orchard</div>	<div>Size (Acres)</div> <div>Frontage</div> <div>Depth</div> <div>Assessed Value</div> <div>Appraised Value</div> <div>29.5</div> <div></div> <div></div> <div>\$156,590</div> <div>\$362,600</div>

Outbuildings

Outbuildings						Legend
Code	Description	Sub Code	Sub Description	Size	Value	Bldg #
FN4	Fence 8'			200 L.F.	\$2,800	1
SHD2	Pre Cast Cell			320 S.F.	\$43,200	1
CAB2	Cabin Good			897 S.F.	\$27,600	1

Valuation History

Appraisal			
Valuation Year	Improvements	Land	Total
2020	\$27,600	\$359,100	\$386,700
2019	\$27,600	\$359,100	\$386,700
2018	\$27,600	\$359,100	\$386,700

--

Assessment			
Valuation Year	Improvements	Land	Total
2020	\$19,300	\$161,110	\$180,410
2019	\$19,300	\$161,110	\$180,410
2018	\$19,300	\$161,110	\$180,410

(c) 2022 Vision Government Solutions, Inc. All rights reserved.



EBI Consulting

environmental | engineering | due diligence

RADIO FREQUENCY EMISSIONS ANALYSIS REPORT EVALUATION OF HUMAN EXPOSURE POTENTIAL TO NON-IONIZING EMISSIONS

Dish Wireless Existing Facility

Site ID: BOBOS00030A

BOBOS00030A
87 West Quasset Road
Woodstock, Connecticut 06281

February 8, 2022

EBI Project Number: 6222000526

Site Compliance Summary	
Compliance Status:	COMPLIANT
Site total MPE% of FCC general population allowable limit:	8.41%

February 8, 2022

Dish Wireless

Emissions Analysis for Site: BOBOS00030A - BOBOS00030A

EBI Consulting was directed to analyze the proposed Dish Wireless facility located at **87 West Quasset Road in Woodstock, Connecticut** for the purpose of determining whether the emissions from the Proposed Dish Wireless Antenna Installation located on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter ($\mu\text{W}/\text{cm}^2$). The number of $\mu\text{W}/\text{cm}^2$ calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits; therefore, it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) – (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general population may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general population would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

Public exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter ($\mu\text{W}/\text{cm}^2$). The general population exposure limits for the 600 MHz and 700 MHz frequency bands are approximately 400 $\mu\text{W}/\text{cm}^2$ and 467 $\mu\text{W}/\text{cm}^2$, respectively. The general population exposure limit for the 1900 MHz (PCS), 2100 MHz (AWS) and 11 GHz frequency bands is 1000 $\mu\text{W}/\text{cm}^2$. Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.

Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure.



Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

CALCULATIONS

Calculations were done for the proposed Dish Wireless antenna facility located at 87 West Quasset Road in Woodstock, Connecticut using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. Since Dish Wireless is proposing highly focused directional panel antennas, which project most of the emitted energy out toward the horizon, all calculations were performed assuming a lobe representing the maximum gain of the antenna per the antenna manufacturer's supplied specifications, minus 20 dB for directional panel antennas and 20 dB for highly focused parabolic microwave dishes, was focused at the base of the tower. For this report, the sample point is the top of a 6-foot person standing at the base of the tower.

For all calculations, all equipment was calculated using the following assumptions:

- 1) 4 n71 channels (600 MHz Band) were considered for each sector of the proposed installation. These Channels have a transmit power of 30 Watts per Channel.
- 2) 4 n70 channels (PCS Band - 1900 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 40 Watts per Channel.
- 3) 4 n66 channels (AWS Band - 2190 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 40 Watts per Channel.
- 4) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 - Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.
- 5) For the following calculations, the sample point was the top of a 6-foot person standing at the base of the tower. The maximum gain of the antenna per the antenna manufacturer's supplied specifications, minus 20 dB for directional panel antennas and 20 dB for highly focused parabolic microwave dishes, was used in this direction. This value is a very conservative



estimate as gain reductions for these particular antennas are typically much higher in this direction.

- 6) The antennas used in this modeling are the Commscope FFVV-65B-R2 for the 600 MHz / 1900 MHz / 2190 MHz channel(s) in Sector A, the Commscope FFVV-65B-R2 for the 600 MHz / 1900 MHz / 2190 MHz channel(s) in Sector B, the Commscope FFVV-65B-R2 for the 600 MHz / 1900 MHz / 2190 MHz channel(s) in Sector C. This is based on feedback from the carrier with regard to anticipated antenna selection. All Antenna gain values and associated transmit power levels are shown in the Site Inventory and Power Data table below. The maximum gain of the antenna per the antenna manufacturer's supplied specifications, minus 20 dB for directional panel antennas and 20 dB for highly focused parabolic microwave dishes, was used for all calculations. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 7) The antenna mounting height centerline of the proposed antennas is 127 feet above ground level (AGL).
- 8) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.
- 9) All calculations were done with respect to uncontrolled / general population threshold limits.



Dish Wireless Site Inventory and Power Data

Sector:	A	Sector:	B	Sector:	C
Antenna #:	I	Antenna #:	I	Antenna #:	I
Make / Model:	Commscope FFVV-65B-R2	Make / Model:	Commscope FFVV-65B-R2	Make / Model:	Commscope FFVV-65B-R2
Frequency Bands:	600 MHz / 1900 MHz / 2190 MHz	Frequency Bands:	600 MHz / 1900 MHz / 2190 MHz	Frequency Bands:	600 MHz / 1900 MHz / 2190 MHz
Gain:	17.55 dBd / 22.05 dBd / 22.05 dBd	Gain:	17.55 dBd / 22.05 dBd / 22.05 dBd	Gain:	17.55 dBd / 22.05 dBd / 22.05 dBd
Height (AGL):	127 feet	Height (AGL):	127 feet	Height (AGL):	127 feet
Channel Count:	12	Channel Count:	12	Channel Count:	12
Total TX Power (W):	440 Watts	Total TX Power (W):	440 Watts	Total TX Power (W):	440 Watts
ERP (W):	4,956.89	ERP (W):	4,956.89	ERP (W):	4,956.89
Antenna AI MPE %:	1.55%	Antenna BI MPE %:	1.55%	Antenna CI MPE %:	1.55%



EBI Consulting

environmental | engineering | due diligence

Site Composite MPE %	
Carrier	MPE %
Dish Wireless (Max at Sector A):	1.55%
AT&T	4.14%
Verizon	2.72%
Site Total MPE % :	8.41%

Dish Wireless MPE % Per Sector	
Dish Wireless Sector A Total:	1.55%
Dish Wireless Sector B Total:	1.55%
Dish Wireless Sector C Total:	1.55%
Site Total MPE % :	8.41%

Dish Wireless Maximum MPE Power Values (Sector A)							
Dish Wireless Frequency Band / Technology (Sector A)	# Channels	Watts ERP (Per Channel)	Height (feet)	Total Power Density ($\mu\text{W}/\text{cm}^2$)	Frequency (MHz)	Allowable MPE ($\mu\text{W}/\text{cm}^2$)	Calculated % MPE
Dish Wireless 600 MHz n71	4	226.27	127.0	2.22	600 MHz n71	400	0.56%
Dish Wireless 1900 MHz n70	4	506.48	127.0	4.97	1900 MHz n70	1000	0.50%
Dish Wireless 2190 MHz n66	4	506.48	127.0	4.97	2190 MHz n66	1000	0.50%
						Total:	1.55%

• NOTE: Totals may vary by approximately 0.01% due to summation of remainders in calculations.



Summary

All calculations performed for this analysis yielded results that were **within** the allowable limits for general population exposure to RF Emissions.

The anticipated maximum composite contributions from the Dish Wireless facility as well as the site composite emissions value with regards to compliance with FCC's allowable limits for general population exposure to RF Emissions are shown here:

Dish Wireless Sector	Power Density Value (%)
Sector A:	1.55%
Sector B:	1.55%
Sector C:	1.55%
Dish Wireless Maximum MPE % (Sector A):	1.55%
Site Total:	8.41%
Site Compliance Status:	COMPLIANT

The anticipated composite MPE value for this site assuming all carriers present is **8.41%** of the allowable FCC established general population limit sampled at the ground level. This is based upon values listed in the Connecticut Siting Council database for existing carrier emissions.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.


INFINIGY8

MOUNT ANALYSIS REPORT

September 16, 2021

Dish Wireless Site Name	BOBOS00030A
Dish Wireless Site Number	BOBOS00030A
NSS/DISH Site Name	-
NSS/DISH Site Number	-
Infinigy Job Number	1197-F0001-B
Client	NSS/DISH
Carrier	Dish Wireless
Site Location	87 West Quasset Road Woodstock, CT 06281 Windham County 41.929772 N NAD83 71.989319 W NAD83
Mount Type	8.0 ft Platform
Mount Elevation	127.0 ft AGL
Structural Usage Ratio	33.7
Overall Result	Pass

The enclosed mount structural analysis has been performed in accordance with the 2018 Connecticut State Building Code (2015 IBC) based on an ultimate 3-second gust wind speed of 120 mph. The evaluation criteria and applicable codes are presented in the next section of this report.



CONTENTS

1. Introduction
2. Design/Analysis Parameters
3. Proposed Loading Configuration
4. Supporting Documentation
5. Results
6. Recommendations
7. Assumptions
8. Liability Waiver and Limitations
9. Calculations

September 16, 2021

1. INTRODUCTION

Infinigy performed a structural analysis on the Dish Wireless proposed telecommunication equipment supporting Platform mounted to the existing structure located at the aforementioned address. All referenced supporting documents have been obtained from the client and are assumed to be accurate and applicable to this site. The mount was analyzed using Risa-3D version 17.0.4 analysis software.

2. DESIGN/ANALYSIS PARAMETERS

Wind Speed	120 mph (3-Second Gust)
Wind Speed w/ ice	50 mph (3-Second Gust) w/ 1.0" ice
Code / Standard	TIA-222-H
Adopted Code	2018 Connecticut State Building Code (2015 IBC)
Risk Category	II
Exposure Category	C
Topographic Category	1
Calculated Crest Height	0 ft.
Seismic Spectral Response	$S_s = 0.182 \text{ g}$ / $S_1 = 0.055 \text{ g}$
Live Load Wind Speed	60 mph
Man Live Load at Mid/End Points	250 lbs
Man Live Load at Mount Pipes	500 lbs

3. PROPOSED LOADING CONFIGURATION - 127.0 ft. AGL Platform

Antenna Centerline (ft)	Qty.	Appurtenance Manufacturers	Appurtenance Models
127.0	3	JMA WIRELESS	MX08FRO665-21
	3	FUJITSU	TA08025-B605
	3	FUJITSU	TA08025-B604
	1	RAYCAP	RDIDC-9181-PF-48

4. SUPPORTING DOCUMENTATION

Proposed Loading	Dish Wireless Asset ID CT-ATC-T-418609 Rev 0, Site #BOBOS00030A, dated May 25, 2021
Mount Manufacturer Drawings	Commscope Document # MC-PK8-DSH, dated March 08, 2021

5. RESULTS

Components	Capacity	Pass/Fail
Mount Pipes	22.2%	Pass
Horizontals	13.5%	Pass
Standoffs	32.9%	Pass
Handrails	26.8%	Pass
Connections	33.7%	Pass
MOUNT RATING =	33.7 %	Pass

Notes:

1. See additional documentation in Appendix for calculations supporting the capacity consumed and detailed mount connection calculations.

6. RECOMMENDATIONS

Infinigy recommends installing Dish Wireless's proposed equipment loading configuration on the mount at 127.0 ft. The installation shall be performed in accordance with the construction documents issued for this site.

Pradin Suinyal Magar
Project Engineer II | **INFINIGY**

7. ASSUMPTIONS



The antenna mounting system was properly fabricated, installed and maintained in accordance with its original design and manufacturer's specifications.	
The configuration of antennas, mounts, and other appurtenances are as specified in the proposed loading configuration table.	
All member connections are assumed to have been designed to meet or exceed the load carrying capacity of the connected member unless otherwise specified in this report.	
The analysis will require revisions if the existing conditions in the field differ from those shown in the above-referenced documents or assumed in this analysis. No allowance was made for any damaged, missing, or rusted members.	
Steel grades have been assumed as follows, unless noted otherwise:	
Channel, Solid Round, Plate, Built-up Angle	ASTM A1011 36 KSI
Structural Angle	ASTM A529 Gr. 50
HSS (Rectangular)	ASTM A500-B GR 46
HSS (Circular)	ASTM A500-B GR 42
Pipe	ASTM A500 Gr C
Connection Bolts	ASTM A325
U-Bolts	ASTM A307
All bolted connections are pretensioned in accordance with Table 8.2 of the RCSC 2014 Standard	

8. LIABILITY WAIVER AND LIMITATIONS

Our structural calculations are completed assuming all information provided to Infinigy is accurate and applicable to this site. For the purposes of calculations, we assume an overall structure condition as erected and all members and connections to be free of corrosion and/or structural defects. The structure owner and/or contractor shall verify the structure's condition prior to installation of any proposed equipment. If actual conditions differ from those described in this report, Infinigy should be notified immediately to assess the impact on the results of this report.



Our evaluation is completed using industry standard methods and procedures. The structural results, conclusions and recommendations contained in this report are proprietary and should not be used by others as their own. Infinigy is not responsible for decisions made by others that are or are not based on the stated assumptions and conclusions in this report.

This report is an evaluation of the mount structure only and does not determine the adequacy of the supporting structure, other carrier mounts or cable mounting attachments. The analysis of these elements is outside the scope of this analysis, are assumed to be adequate for the purpose of this report and to have been installed per their manufacturer requirements. This document is not for construction purposes.





Envelope Only Solution

Infinigy Engineering, PLLC	BOBOS00030A	Rendered
PSM		Sept 16, 2021 at 2:30 PM
1197-F0001-B		BOBOS00030A_loaded.r3d





Envelope Only Solution

Infinigy Engineering, PLLC	BOBOS00030A	WireFrame
PSM		Sept 16, 2021 at 2:30 PM
1197-F0001-B		BOBOS00030A_loaded.r3d





Envelope Only Solution

Infinigy Engineering, PLLC	BOBOS00030A	Section Sets
PSM		Sept 16, 2021 at 2:30 PM
1197-F0001-B		BOBOS00030A_loaded.r3d




Envelope Only Solution

Infinigy Engineering, PLLC	BOBOS00030A	Member Shapes
PSM		Sept 16, 2021 at 2:31 PM
1197-F0001-B		BOBOS00030A_loaded.r3d





Envelope Only Solution

Infinigy Engineering, PLLC	BOBOS00030A	Material Sets
PSM		Sept 16, 2021 at 2:31 PM
1197-F0001-B		BOBOS00030A_loaded.r3d





Infinigy Engineering, PLLC	BOBOS00030A	Member Lengths
PSM		Sept 16, 2021 at 2:31 PM
1197-F0001-B		BOBOS00030A_loaded.r3d





Loads: BLC 1, Self Weight
Envelope Only Solution

Infinigy Engineering, PLLC	BOBOS00030A	Self Weight
PSM		Sept 16, 2021 at 2:31 PM
1197-F0001-B		BOBOS00030A_loaded.r3d





Loads: BLC 2, Wind Load AZI 0
Envelope Only Solution

Infinigy Engineering, PLLC	BOBOS00030A	Wind Load AZI 000
PSM		Sept 16, 2021 at 2:31 PM
1197-F0001-B		BOBOS00030A_loaded.r3d



Loads: BLC 5, Wind Load AZI 90
Envelope Only Solution

Infinigy Engineering, PLLC	BOBOS00030A	Wind Load AZI 090
PSM		Sept 16, 2021 at 2:32 PM
1197-F0001-B		BOBOS00030A_loaded.r3d



Loads: BLC 14, Distr. Wind Load Z
Envelope Only Solution

Infinigy Engineering, PLLC

PSM



1197-F0001-B

BOBOS00030A

Distr Wind Load AZI 000



Sept 16, 2021 at 2:32 PM

BOBOS00030A_loaded.r3d





Loads: BLC 15, Distr. Wind Load X
Envelope Only Solution

Infinigy Engineering, PLLC	BOBOS00030A	Distr Wind Load AZI 090
PSM		Sept 16, 2021 at 2:32 PM
1197-F0001-B		BOBOS00030A_loaded.r3d





Loads: BLC 16, Ice Weight
Envelope Only Solution

Infinigy Engineering, PLLC	BOBOS00030A	Ice Weight
PSM		Sept 16, 2021 at 2:33 PM
1197-F0001-B		BOBOS00030A_loaded.r3d





Loads: BLC 17, Ice Wind Load AZI 0
Envelope Only Solution

Infinigy Engineering, PLLC	BOBOS00030A	Ice + Wind Load AZI 000
PSM		Sept 16, 2021 at 2:33 PM
1197-F0001-B		BOBOS00030A_loaded.r3d




Loads: BLC 20, Ice Wind Load AZI 90
Envelope Only Solution

Infinigy Engineering, PLLC	BOBOS00030A	Ice + Wind Load AZI 090
PSM		Sept 16, 2021 at 2:33 PM
1197-F0001-B		BOBOS00030A_loaded.r3d





Loads: BLC 29, Distr. Ice Wind Load Z
Envelope Only Solution

Infinigy Engineering, PLLC	BOBOS00030A	Distr Ice + Wind Load AZI 000.
PSM		Sept 16, 2021 at 2:34 PM
1197-F0001-B		BOBOS00030A_loaded.r3d





Infinigy Engineering, PLLC	BOBOS00030A	Distr Ice + Wind Load AZI 090
PSM		Sept 16, 2021 at 2:34 PM
1197-F0001-B		BOBOS00030A_loaded.r3d





Loads: BLC 31, Seismic Load Z
Envelope Only Solution

Infinigy Engineering, PLLC	BOBOS00030A	Seismic Load AZI 000
PSM		Sept 16, 2021 at 2:34 PM
1197-F0001-B		BOBOS00030A_loaded.r3d




Loads: BLC 32, Seismic Load X
Envelope Only Solution

Infinigy Engineering, PLLC	BOBOS00030A	Seismic Load AZI 090
PSM		Sept 16, 2021 at 2:34 PM
1197-F0001-B		BOBOS00030A_loaded.r3d




Loads: LL - Live Load
Envelope Only Solution

Infinigy Engineering, PLLC	BOBOS00030A	Non-concurrent Live Loads
PSM		Sept 16, 2021 at 2:35 PM
1197-F0001-B		BOBOS00030A_loaded.r3d






Code Check (Env)	
 	No Calc
 	> 1.0
 	.90-1.0
 	.75-.90
 	.50-.75
 	0.-.50



Member Code Checks Displayed (Enveloped)
Envelope Only Solution

Infinigy Engineering, PLLC	BOBOS00030A	Bending Check
PSM		Sept 16, 2021 at 2:35 PM
1197-F0001-B		BOBOS00030A_loaded.r3d



Member Shear Checks Displayed (Enveloped)
Envelope Only Solution

Infinigy Engineering, PLLC	BOBOS00030A	Shear Check
PSM		Sept 16, 2021 at 2:35 PM
1197-F0001-B		BOBOS00030A_loaded.r3d

Program Inputs

PROJECT INFORMATION		
Client:	ATC	
Carrier:	Dish Wireless	
Engineer:	Pradin Suinyal Magar, M.S	

SITE INFORMATION		
Risk Category:	II	
Exposure Category:	C	
Topo Factor Procedure:	Method 1, Category 1	
Site Class:	D - Stiff Soil (Assumed)	
Ground Elevation:	692.08	ft *Rev H

MOUNT INFORMATION		
Mount Type:	Platform	
Num Sectors:	3	
Centerline AGL:	127.00	ft
Tower Height AGL:	149.30	ft

TOPOGRAPHIC DATA		
Topo Feature:	N/A	
Slope Distance:	N/A	ft
Crest Distance:	N/A	ft
Crest Height:	N/A	ft

FACTORS		
Directionality Fact. (K_d):	0.950	
Ground Ele. Factor (K_e):	0.975	*Rev H Only
Rooftop Speed-Up (K_s):	1.000	*Rev H Only
Topographic Factor (K_{zt}):	1.000	
Gust Effect Factor (G_h):	1.000	

CODE STANDARDS		
Building Code:	2015 IBC	
TIA Standard:	TIA-222-H	
ASCE Standard:	ASCE 7-16	



WIND AND ICE DATA		
Ultimate Wind (V_{ult}):	120	mph
Design Wind (V):	N/A	mph
Ice Wind (V_{ice}):	50	mph
Base Ice Thickness (t_i):	1	in
Flat Pressure:	90.914	psf
Round Pressure:	54.549	psf
Ice Wind Pressure:	9.470	psf

SEISMIC DATA		
Short-Period Accel. (S_s):	0.182	g
1-Second Accel. (S_1):	0.055	g
Short-Period Design (S_{DS}):	0.194	
1-Second Design (S_{D1}):	0.088	
Short-Period Coeff. (F_a):	1.600	
1-Second Coeff. (F_v):	2.400	
Amplification Factor (A_s):	3.000	
Response Mod. Coeff. (R):	2.000	



Infinigy Load Calculator V2.1.7

Program Inputs

[illegible]

ASCE 7 Hazards Report

Address:

No Address at This
Location

Standard:

ASCE/SEI 7-16



Risk Category: II**Soil Class:**

D - Default (see
Section 11.4.3)

Elevation: 692.08 ft (NAVD 88)

Latitude: 41.929772

Longitude: -71.989319



Wind

Results:

Wind Speed:	120 Vmph
10-year MRI	75 Vmph
25-year MRI	84 Vmph
50-year MRI	92 Vmph
100-year MRI	99 Vmph

Data Source: ASCE/SEI 7-16, Fig. 26.5-1B and Figs. CC.2-1–CC.2-4, and Section 26.5.2

Date Accessed: Thu Sep 16 2021

Value provided is 3-second gust wind speeds at 33 ft above ground for Exposure C Category, based on linear interpolation between contours. Wind speeds are interpolated in accordance with the 7-16 Standard. Wind speeds correspond to approximately a 7% probability of exceedance in 50 years (annual exceedance probability = 0.00143, MRI = 700 years).





Site is in a hurricane-prone region as defined in ASCE/SEI 7-16 Section 26.2. Glazed openings need not be protected against wind-borne debris.

Site Soil Class: D - Default (see Section 11.4.3)

Results:

S_S :	0.182	S_{D1} :	0.088
S_1 :	0.055	T_L :	6
F_a :	1.6	PGA :	0.097
F_v :	2.4	PGA _M :	0.155
S_{MS} :	0.29	F_{PGA} :	1.6
S_{M1} :	0.132	I_e :	1
S_{DS} :	0.194	C_v :	0.7

Seismic Design Category B



Data Accessed:

Thu Sep 16 2021

Date Source:

USGS Seismic Design Maps based on ASCE/SEI 7-16 and ASCE/SEI 7-16 Table 1.5-2. Additional data for site-specific ground motion procedures in accordance with ASCE/SEI 7-16 Ch. 21 are available from USGS.

Results:

Ice Thickness: 1.00 in.
Concurrent Temperature: 15 F
Gust Speed: 50 mph

Data Source: Standard ASCE/SEI 7-16, Figs. 10-2 through 10-8

Date Accessed: Thu Sep 16 2021

Ice thicknesses on structures in exposed locations at elevations higher than the surrounding terrain and in valleys and gorges may exceed the mapped values.

Values provided are equivalent radial ice thicknesses due to freezing rain with concurrent 3-second gust speeds, for a 500-year mean recurrence interval, and temperatures concurrent with ice thicknesses due to freezing rain. Thicknesses for ice accretions caused by other sources shall be obtained from local meteorological studies. Ice thicknesses in exposed locations at elevations higher than the surrounding terrain and in valleys and gorges may exceed the mapped values.

The ASCE 7 Hazard Tool is provided for your convenience, for informational purposes only, and is provided "as is" and without warranties of any kind. The location data included herein has been obtained from information developed, produced, and maintained by third party providers; or has been extrapolated from maps incorporated in the ASCE 7 standard. While ASCE has made every effort to use data obtained from reliable sources or methodologies, ASCE does not make any representations or warranties as to the accuracy, completeness, reliability, currency, or quality of any data provided herein. Any third-party links provided by this Tool should not be construed as an endorsement, affiliation, relationship, or sponsorship of such third-party content by or from ASCE.

ASCE does not intend, nor should anyone interpret, the results provided by this Tool to replace the sound judgment of a competent professional, having knowledge and experience in the appropriate field(s) of practice, nor to substitute for the standard of care required of such professionals in interpreting and applying the contents of this Tool or the ASCE 7 standard.

In using this Tool, you expressly assume all risks associated with your use. Under no circumstances shall ASCE or its officers, directors, employees, members, affiliates, or agents be liable to you or any other person for any direct, indirect, special, incidental, or consequential damages arising from or related to your use of, or reliance on, the Tool or any information obtained therein. To the fullest extent permitted by law, you agree to release and hold harmless ASCE from any and all liability of any nature arising out of or resulting from any use of data provided by the ASCE 7 Hazard Tool.

Member Primary Data

	Label	I Joint	J Joint	K Joint	Rotate(...	Section/Shape	Type	Design List	Material	Design Rules
1	S3	P1	P3			Square Tubing	Beam	None	A500 GR.C	Typical
2	GA4	P9	P12		270	Grating Angle	Beam	None	A529 Gr. 50	Typical
3	GA3	P10	P11			Grating Angle	Beam	None	A529 Gr. 50	Typical
4	P3	P7	P8			Corner Plates	Beam	None	A1011 36 Ksi	Typical
5	S2	P13	P14			Square Tubing	Beam	None	A500 GR.C	Typical
6	GA2	P20	P23		270	Grating Angle	Beam	None	A529 Gr. 50	Typical
7	GA1	P21	P22			Grating Angle	Beam	None	A529 Gr. 50	Typical
8	P2	P18	P19			Corner Plates	Beam	None	A1011 36 Ksi	Typical
9	S1	P24	P25			Square Tubing	Beam	None	A500 GR.C	Typical
10	GA6	P31	P34		270	Grating Angle	Beam	None	A529 Gr. 50	Typical
11	GA5	P32	P33			Grating Angle	Beam	None	A529 Gr. 50	Typical
12	P1	P29	P30			Corner Plates	Beam	None	A1011 36 Ksi	Typical
13	H1	N43	N44			Face Pipes(3.5x.16)	Beam	None	A500 GR.C	Typical
14	MP1	N66	N60			Antenna Pipes	Beam	None	A500 GR.C	Typical
15	MP3	N63	N57			Antenna Pipes	Beam	None	A500 GR.C	Typical
16	HR1	N67	N68			Handrail	Beam	None	A500 GR.C	Typical
17	CA8	N114A	N113A		180	Handrail Connector	Beam	None	A1011 36 Ksi	Typical
18	CA9	N112A	N111A		180	Handrail Connector	Beam	None	A1011 36 Ksi	Typical
19	CA7	N116A	N115A		180	Handrail Connector	Beam	None	A1011 36 Ksi	Typical
20	M32	N48A	N70A			RIGID	None	None	RIGID	Typical
21	M35	N45	N69A			RIGID	None	None	RIGID	Typical
22	M36	N51	N71A			RIGID	None	None	RIGID	Typical
23	M39A	N54	N72A			RIGID	None	None	RIGID	Typical
24	CA3	P4	N122A			Channel(3.38x2.06)	Beam	None	A1011 36 Ksi	Typical
25	CA4	N124B	P4			Channel(3.38x2.06)	Beam	None	A1011 36 Ksi	Typical
26	CA1	P15	N122B			Channel(3.38x2.06)	Beam	None	A1011 36 Ksi	Typical
27	CA2	N123A	P15			Channel(3.38x2.06)	Beam	None	A1011 36 Ksi	Typical
28	CA5	P26	N125			Channel(3.38x2.06)	Beam	None	A1011 36 Ksi	Typical
29	CA6	N126	P26			Channel(3.38x2.06)	Beam	None	A1011 36 Ksi	Typical
30	M64	N126A	N125A			RIGID	None	None	RIGID	Typical
31	M65	N126	N125A			RIGID	None	None	RIGID	Typical
32	M66	N129	N128			RIGID	None	None	RIGID	Typical
33	M67	N124B	N128			RIGID	None	None	RIGID	Typical
34	M68	N132	N131			RIGID	None	None	RIGID	Typical
35	M69	N123A	N131			RIGID	None	None	RIGID	Typical
36	M70	N133	N132A			RIGID	None	None	RIGID	Typical
37	M71	N122B	N132A			RIGID	None	None	RIGID	Typical
38	M72	N135	N134			RIGID	None	None	RIGID	Typical
39	M73	N125	N134			RIGID	None	None	RIGID	Typical
40	M74	N138	N137			RIGID	None	None	RIGID	Typical
41	M75	N122A	N137			PL 2.375x0.5	None	None	A36 Gr.36	Typical

Member Primary Data (Continued)

	Label	I Joint	J Joint	K Joint	Rotate(...)	Section/Shape	Type	Design List	Material	Design Rules
42	MP2	N75	N74			Antenna Pipes	Beam	None	A500 GR.C	Typical
43	M43	N72B	N76			RIGID	None	None	RIGID	Typical
44	M44	N73	N77			RIGID	None	None	RIGID	Typical
45	H3	N81A	N82A			Face Pipes(3.5x.16)	Beam	None	A500 GR.C	Typical
46	MP7	N90	N88			Antenna Pipes	Beam	None	A500 GR.C	Typical
47	MP9	N89	N87			Antenna Pipes	Beam	None	A500 GR.C	Typical
48	HR3	N91	N92			Handrail	Beam	None	A500 GR.C	Typical
49	M52	N84	N94			RIGID	None	None	RIGID	Typical
50	M53	N83A	N93			RIGID	None	None	RIGID	Typical
51	M54	N85	N95			RIGID	None	None	RIGID	Typical
52	M55	N86	N96			RIGID	None	None	RIGID	Typical
53	H2	N109	N110			Face Pipes(3.5x.16)	Beam	None	A500 GR.C	Typical
54	MP4	N118	N116			Antenna Pipes	Beam	None	A500 GR.C	Typical
55	MP6	N117	N115			Antenna Pipes	Beam	None	A500 GR.C	Typical
56	HR2	N119	N120			Handrail	Beam	None	A500 GR.C	Typical
57	M66A	N112	N122			RIGID	None	None	RIGID	Typical
58	M67A	N111	N121			RIGID	None	None	RIGID	Typical
59	M68A	N113	N123			RIGID	None	None	RIGID	Typical
60	M69A	N114	N124			RIGID	None	None	RIGID	Typical
61	MP8	N132B	N131A			Antenna Pipes	Beam	None	A500 GR.C	Typical
62	M68B	N129B	N133B			RIGID	None	None	RIGID	Typical
63	M69B	N130A	N134A			RIGID	None	None	RIGID	Typical
64	MP5	N138A	N137A			Antenna Pipes	Beam	None	A500 GR.C	Typical
65	M71B	N135A	N139			RIGID	None	None	RIGID	Typical
66	M72B	N136	N140			RIGID	None	None	RIGID	Typical

Hot Rolled Steel Design Parameters

	Label	Shape	Length...	Lbyy[in]	Lbzz[in]	Lcomp t...	Lcomp b...	L-tor...	Kyy	Kzz	Cb	Func...
1	S3	Square Tubing	40			Lbyy						Late...
2	GA4	Grating Angle	27.295			Lbyy						Late...
3	GA3	Grating Angle	27.295			Lbyy						Late...
4	P3	Corner Plates	42			Lbyy						Late...
5	S2	Square Tubing	40			Lbyy						Late...
6	GA2	Grating Angle	27.295			Lbyy						Late...
7	GA1	Grating Angle	27.295			Lbyy						Late...
8	P2	Corner Plates	42			Lbyy						Late...
9	S1	Square Tubing	40			Lbyy						Late...
10	GA6	Grating Angle	27.295			Lbyy						Late...
11	GA5	Grating Angle	27.295			Lbyy						Late...
12	P1	Corner Plates	42			Lbyy						Late...
13	H1	Face Pipes(3.5x.16)	96			Lbyy						Late...

Hot Rolled Steel Design Parameters (Continued)

	Label	Shape	Lengt...	Lbyy[in]	Lbzz[in]	Lcomp t...	Lcomp b...	L-tor...	Kyy	Kzz	Cb	Func...
14	MP1	Antenna Pipes	96			Lbyy						Late...
15	MP3	Antenna Pipes	96			Lbyy						Late...
16	HR1	Handrail	96			Lbyy						Late...
17	CA8	Handrail Connector	42			Lbyy						Late...
18	CA9	Handrail Connector	42			Lbyy						Late...
19	CA7	Handrail Connector	42			Lbyy						Late...
20	CA3	Channel(3.38x2.06)	33			Lbyy						Late...
21	CA4	Channel(3.38x2.06)	33			Lbyy						Late...
22	CA1	Channel(3.38x2.06)	33			Lbyy						Late...
23	CA2	Channel(3.38x2.06)	33			Lbyy						Late...
24	CA5	Channel(3.38x2.06)	33			Lbyy						Late...
25	CA6	Channel(3.38x2.06)	33			Lbyy						Late...
26	M75	PL 2.375x0.5	1.5			Lbyy						Late...
27	MP2	Antenna Pipes	96			Lbyy						Late...
28	H3	Face Pipes(3.5x.16)	96			Lbyy						Late...
29	MP7	Antenna Pipes	96			Lbyy						Late...
30	MP9	Antenna Pipes	96			Lbyy						Late...
31	HR3	Handrail	96			Lbyy						Late...
32	H2	Face Pipes(3.5x.16)	96			Lbyy						Late...
33	MP4	Antenna Pipes	96			Lbyy						Late...
34	MP6	Antenna Pipes	96			Lbyy						Late...
35	HR2	Handrail	96			Lbyy						Late...
36	MP8	Antenna Pipes	96			Lbyy						Late...
37	MP5	Antenna Pipes	96			Lbyy						Late...

Member Advanced Data

	Label	I Release	J Release	I Offset[in]	J Offset[in]	T/C Only	Physical Defl Ra...	Analysis ...	Inactive	Seismi...
1	S3						Yes			None
2	GA4						Yes			None
3	GA3						Yes			None
4	P3	BenPIN	BenPIN				Yes	Default		None
5	S2						Yes			None
6	GA2						Yes			None
7	GA1						Yes			None
8	P2	BenPIN	BenPIN				Yes	Default		None
9	S1						Yes	Default		None
10	GA6						Yes			None
11	GA5						Yes			None
12	P1	BenPIN	BenPIN				Yes	Default		None
13	H1						Yes			None
14	MP1						Yes	+y+3		None

Member Advanced Data (Continued)

	Label	I Release	J Release	I Offset[in]	J Offset[in]	T/C Only	Physical	Defl Ra...	Analysis ...	Inactive	Seismi...
15	MP3						Yes		+y+3		None
16	HR1						Yes				None
17	CA8	00000X	00000X				Yes				None
18	CA9	00000X	00000X				Yes				None
19	CA7	00000X	00000X				Yes	Default			None
20	M32						Yes	** NA **			None
21	M35						Yes	** NA **			None
22	M36						Yes	** NA **			None
23	M39A						Yes	** NA **			None
24	CA3						Yes	Default			None
25	CA4						Yes	Default			None
26	CA1						Yes	Default			None
27	CA2						Yes	Default			None
28	CA5						Yes	Default			None
29	CA6						Yes	Default			None
30	M64	BenPIN					Yes	** NA **			None
31	M65						Yes	** NA **			None
32	M66	BenPIN					Yes	** NA **			None
33	M67						Yes	** NA **			None
34	M68	BenPIN					Yes	** NA **			None
35	M69						Yes	** NA **			None
36	M70	BenPIN					Yes	** NA **			None
37	M71						Yes	** NA **			None
38	M72	BenPIN					Yes	** NA **			None
39	M73						Yes	** NA **			None
40	M74	BenPIN					Yes	** NA **			None
41	M75						Yes	** NA **			None
42	MP2						Yes		+y+3		None
43	M43						Yes	** NA **			None
44	M44						Yes	** NA **			None
45	H3						Yes				None
46	MP7						Yes		+y+3		None
47	MP9						Yes		+y+3		None
48	HR3						Yes				None
49	M52						Yes	** NA **			None
50	M53						Yes	** NA **			None
51	M54						Yes	** NA **			None
52	M55						Yes	** NA **			None
53	H2						Yes				None
54	MP4						Yes		+y+3		None
55	MP6						Yes		+y+3		None
56	HR2						Yes				None

Member Advanced Data (Continued)

	Label	I Release	J Release	I Offset[in]	J Offset[in]	T/C Only	Physical Defl Ra...	Analysis ...	Inactive	Seismi...
57	M66A						Yes	** NA **		None
58	M67A						Yes	** NA **		None
59	M68A						Yes	** NA **		None
60	M69A						Yes	** NA **		None
61	MP8						Yes		+y+3	None
62	M68B						Yes	** NA **		None
63	M69B						Yes	** NA **		None
64	MP5						Yes		+y+3	None
65	M71B						Yes	** NA **		None
66	M72B						Yes	** NA **		None

Material Takeoff

	Material	Size	Pieces	Length[in]	Weight[LB]
1	General				
2	RIGID		29	35.1	0
3	Total General		29	35.1	0
4					
5	Hot Rolled Steel				
6	A1011 36 Ksi	C3.38x2.06x0.25	6	198	98.255
7	A1011 36 Ksi	PL6.5x0.375	3	126	87.09
8	A1011 36 Ksi	L6.6x4.46x0.25	3	126	96.558
9	A36 Gr.36	PL 2.375x0.5	1	1.5	.505
10	A500 GR.C	2.88x0.120	3	288	84.974
11	A500 GR.C	HSS4X4X6	3	120	162.653
12	A500 GR.C	Pipe3.5x0.165	3	288	141.202
13	A500 GR.C	PIPE 2.5	9	864	394.45
14	A529 Gr. 50	L2x2x4	6	163.8	43.838
15	Total HR Steel		37	2175.3	1109.525

Hot Rolled Steel Section Sets


	Label	Shape	Type	Design List	Material	Design...	A [in2]	Iyy [in...]	Izz [in...]	J [in4]
1	Corner Plates	PL6.5x0.375	Beam	None	A1011 ...	Typical	2.438	.029	8.582	.11
2	6"x0.37" Plate	Plate 6x.37	Beam	None	A1011 ...	Typical	2.22	.025	6.66	.097
3	Grating Angle	L2x2x4	Beam	None	A529 G...	Typical	.944	.346	.346	.021
4	Face Pipes(3.5x.1...	Pipe3.5x0.165	Beam	None	A500 G...	Typical	1.729	2.409	2.409	4.819
5	Antenna Pipes	PIPE 2.5	Beam	None	A500 G...	Typical	1.61	1.45	1.45	2.89
6	Channel(3.38x2.06)	C3.38x2.06x0.25	Beam	None	A1011 ...	Typical	1.75	.715	3.026	.034
7	Square Tubing	HSS4X4X6	Beam	None	A500 G...	Typical	4.78	10.3	10.3	17.5
8	Handrail Connector	L6.6x4.46x0.25	Beam	None	A1011 ...	Typical	2.703	4.759	12.473	.055


Hot Rolled Steel Section Sets (Continued)


	Label	Shape	Type	Design List	Material	Design...	A [in2]	Iyy [in...]	Izz [in...]	J [in4]
9	Handrail	2.88x0.120	Beam	None	A500 G...	Typical	1.04	.993	.993	1.985


Basic Load Cases


	BLC Description	Category	X Gr...	Y Gr...	Z Gr...	Joint	Point	Distributed	Area(Memb...	Surface(Plate/Wall)
1	Self Weight	DL		-1			13		3	
2	Wind Load AZI 0	WLZ					26			
3	Wind Load AZI 30	None					26			
4	Wind Load AZI 60	None					26			
5	Wind Load AZI 90	WLX					26			
6	Wind Load AZI 1...	None					26			
7	Wind Load AZI 1...	None					26			
8	Wind Load AZI 1...	None					26			
9	Wind Load AZI 2...	None					26			
10	Wind Load AZI 2...	None					26			
11	Wind Load AZI 2...	None					26			
12	Wind Load AZI 3...	None					26			
13	Wind Load AZI 3...	None					26			
14	Distr. Wind Load Z	WLZ						66		
15	Distr. Wind Load X	WLX						66		
16	Ice Weight	OL1					13	66	3	
17	Ice Wind Load A...	OL2					26			
18	Ice Wind Load A...	None					26			
19	Ice Wind Load A...	None					26			
20	Ice Wind Load A...	OL3					26			
21	Ice Wind Load A...	None					26			
22	Ice Wind Load A...	None					26			
23	Ice Wind Load A...	None					26			
24	Ice Wind Load A...	None					26			
25	Ice Wind Load A...	None					26			
26	Ice Wind Load A...	None					26			
27	Ice Wind Load A...	None					26			
28	Ice Wind Load A...	None					26			
29	Distr. Ice Wind L...	OL2						66		
30	Distr. Ice Wind L...	OL3						66		
31	Seismic Load Z	ELZ			-.291		13			
32	Seismic Load X	ELX	-.291				13			
33	Service Live Loa...	LL				3				
34	Maintenance Loa...	LL				1				
35	Maintenance Loa...	LL				1				
36	Maintenance Loa...	LL				1				
37	Maintenance Loa...	LL				1				











Envelope Joint Reactions (Continued)

Joint	X [lb]	LC	Y [lb]	LC	Z [lb]	LC	MX [lb-ft]	LC	MY [lb-ft]	LC	MZ [lb-ft]	LC
6	...	11	...	20	...	8	...	20	...	17	...	157
7	Totals: ...	5	...	34	...	14						
8	...	23	...	53	...	8						

Member Point Loads (BLC 1 : Self Weight)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in, %]
1	MP1	Y	-32.25	0
2	MP1	Y	-32.25	72
3	MP1	Y	-74.95	12
4	MP1	Y	-63.93	12
5	S2	Y	-21.85	12
6	MP4	Y	-32.25	0
7	MP4	Y	-32.25	72
8	MP4	Y	-74.95	12
9	MP4	Y	-63.93	12
10	MP7	Y	-32.25	0
11	MP7	Y	-32.25	72
12	MP7	Y	-74.95	12
13	MP7	Y	-63.93	12

Member Point Loads (BLC 2 : Wind Load AZI 0)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in, %]
1	MP1	X	0	0
2	MP1	Z	-163.85	0
3	MP1	X	0	72
4	MP1	Z	-163.85	72
5	MP1	X	0	12
6	MP1	Z	-80.33	12
7	MP1	X	0	12
8	MP1	Z	-80.33	12
9	S2	X	0	12
10	S2	Z	-76.37	12
11	MP4	X	0	0
12	MP4	Z	-90.21	0
13	MP4	X	0	72
14	MP4	Z	-90.21	72
15	MP4	X	0	12
16	MP4	Z	-56.57	12
17	MP4	X	0	12
18	MP4	Z	-51.78	12

Member Point Loads (BLC 2 : Wind Load AZI 0) (Continued)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
19	MP7	X	0	0
20	MP7	Z	-90.21	0
21	MP7	X	0	72
22	MP7	Z	-90.21	72
23	MP7	X	0	12
24	MP7	Z	-56.57	12
25	MP7	X	0	12
26	MP7	Z	-51.78	12

Member Point Loads (BLC 3 : Wind Load AZI 30)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
1	MP1	X	-69.65	0
2	MP1	Z	-120.64	0
3	MP1	X	-69.65	72
4	MP1	Z	-120.64	72
5	MP1	X	-36.2	12
6	MP1	Z	-62.71	12
7	MP1	X	-35.41	12
8	MP1	Z	-61.32	12
9	S2	X	-34.09	12
10	S2	Z	-59.05	12
11	MP4	X	-69.65	0
12	MP4	Z	-120.64	0
13	MP4	X	-69.65	72
14	MP4	Z	-120.64	72
15	MP4	X	-36.2	12
16	MP4	Z	-62.71	12
17	MP4	X	-35.41	12
18	MP4	Z	-61.32	12
19	MP7	X	-32.83	0
20	MP7	Z	-56.87	0
21	MP7	X	-32.83	72
22	MP7	Z	-56.87	72
23	MP7	X	-24.32	12
24	MP7	Z	-42.13	12
25	MP7	X	-21.13	12
26	MP7	Z	-36.6	12

Member Point Loads (BLC 4 : Wind Load AZI 60)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
1	MP1	X	-78.12	0

Member Point Loads (BLC 4 : Wind Load AZI 60) (Continued)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
2	MP1	Z	-45.1	0
3	MP1	X	-78.12	72
4	MP1	Z	-45.1	72
5	MP1	X	-48.99	12
6	MP1	Z	-28.28	12
7	MP1	X	-44.84	12
8	MP1	Z	-25.89	12
9	S2	X	-44.88	12
10	S2	Z	-25.91	12
11	MP4	X	-141.9	0
12	MP4	Z	-81.93	0
13	MP4	X	-141.9	72
14	MP4	Z	-81.93	72
15	MP4	X	-69.57	12
16	MP4	Z	-40.16	12
17	MP4	X	-69.57	12
18	MP4	Z	-40.16	12
19	MP7	X	-78.12	0
20	MP7	Z	-45.1	0
21	MP7	X	-78.12	72
22	MP7	Z	-45.1	72
23	MP7	X	-48.99	12
24	MP7	Z	-28.28	12
25	MP7	X	-44.84	12
26	MP7	Z	-25.89	12

Member Point Loads (BLC 5 : Wind Load AZI 90)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
1	MP1	X	-65.66	0
2	MP1	Z	0	0
3	MP1	X	-65.66	72
4	MP1	Z	0	72
5	MP1	X	-48.65	12
6	MP1	Z	0	12
7	MP1	X	-42.26	12
8	MP1	Z	0	12
9	S2	X	-43.64	12
10	S2	Z	0	12
11	MP4	X	-139.3	0
12	MP4	Z	0	0
13	MP4	X	-139.3	72
14	MP4	Z	0	72

Member Point Loads (BLC 5 : Wind Load AZI 90) (Continued)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
15	MP4	X	-72.41	12
16	MP4	Z	0	12
17	MP4	X	-70.81	12
18	MP4	Z	0	12
19	MP7	X	-139.3	0
20	MP7	Z	0	0
21	MP7	X	-139.3	72
22	MP7	Z	0	72
23	MP7	X	-72.41	12
24	MP7	Z	0	12
25	MP7	X	-70.81	12
26	MP7	Z	0	12

Member Point Loads (BLC 6 : Wind Load AZI 120)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
1	MP1	X	-78.12	0
2	MP1	Z	45.1	0
3	MP1	X	-78.12	72
4	MP1	Z	45.1	72
5	MP1	X	-48.99	12
6	MP1	Z	28.28	12
7	MP1	X	-44.84	12
8	MP1	Z	25.89	12
9	S2	X	-44.88	12
10	S2	Z	25.91	12
11	MP4	X	-78.12	0
12	MP4	Z	45.1	0
13	MP4	X	-78.12	72
14	MP4	Z	45.1	72
15	MP4	X	-48.99	12
16	MP4	Z	28.28	12
17	MP4	X	-44.84	12
18	MP4	Z	25.89	12
19	MP7	X	-141.9	0
20	MP7	Z	81.93	0
21	MP7	X	-141.9	72
22	MP7	Z	81.93	72
23	MP7	X	-69.57	12
24	MP7	Z	40.16	12
25	MP7	X	-69.57	12
26	MP7	Z	40.16	12

Member Point Loads (BLC 7 : Wind Load AZI 150)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
1	MP1	X	-69.65	0
2	MP1	Z	120.64	0
3	MP1	X	-69.65	72
4	MP1	Z	120.64	72
5	MP1	X	-36.2	12
6	MP1	Z	62.71	12
7	MP1	X	-35.41	12
8	MP1	Z	61.32	12
9	S2	X	-34.09	12
10	S2	Z	59.05	12
11	MP4	X	-32.83	0
12	MP4	Z	56.87	0
13	MP4	X	-32.83	72
14	MP4	Z	56.87	72
15	MP4	X	-24.32	12
16	MP4	Z	42.13	12
17	MP4	X	-21.13	12
18	MP4	Z	36.6	12
19	MP7	X	-69.65	0
20	MP7	Z	120.64	0
21	MP7	X	-69.65	72
22	MP7	Z	120.64	72
23	MP7	X	-36.2	12
24	MP7	Z	62.71	12
25	MP7	X	-35.41	12
26	MP7	Z	61.32	12

Member Point Loads (BLC 8 : Wind Load AZI 180)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
1	MP1	X	0	0
2	MP1	Z	163.85	0
3	MP1	X	0	72
4	MP1	Z	163.85	72
5	MP1	X	0	12
6	MP1	Z	80.33	12
7	MP1	X	0	12
8	MP1	Z	80.33	12
9	S2	X	0	12
10	S2	Z	76.37	12
11	MP4	X	0	0
12	MP4	Z	90.21	0
13	MP4	X	0	72

Member Point Loads (BLC 8 : Wind Load AZI 180) (Continued)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
14	MP4	Z	90.21	72
15	MP4	X	0	12
16	MP4	Z	56.57	12
17	MP4	X	0	12
18	MP4	Z	51.78	12
19	MP7	X	0	0
20	MP7	Z	90.21	0
21	MP7	X	0	72
22	MP7	Z	90.21	72
23	MP7	X	0	12
24	MP7	Z	56.57	12
25	MP7	X	0	12
26	MP7	Z	51.78	12

Member Point Loads (BLC 9 : Wind Load AZI 210)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
1	MP1	X	69.65	0
2	MP1	Z	120.64	0
3	MP1	X	69.65	72
4	MP1	Z	120.64	72
5	MP1	X	36.2	12
6	MP1	Z	62.71	12
7	MP1	X	35.41	12
8	MP1	Z	61.32	12
9	S2	X	34.09	12
10	S2	Z	59.05	12
11	MP4	X	69.65	0
12	MP4	Z	120.64	0
13	MP4	X	69.65	72
14	MP4	Z	120.64	72
15	MP4	X	36.2	12
16	MP4	Z	62.71	12
17	MP4	X	35.41	12
18	MP4	Z	61.32	12
19	MP7	X	32.83	0
20	MP7	Z	56.87	0
21	MP7	X	32.83	72
22	MP7	Z	56.87	72
23	MP7	X	24.32	12
24	MP7	Z	42.13	12
25	MP7	X	21.13	12
26	MP7	Z	36.6	12

Member Point Loads (BLC 10 : Wind Load AZI 240)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
1	MP1	X	78.12	0
2	MP1	Z	45.1	0
3	MP1	X	78.12	72
4	MP1	Z	45.1	72
5	MP1	X	48.99	12
6	MP1	Z	28.28	12
7	MP1	X	44.84	12
8	MP1	Z	25.89	12
9	S2	X	44.88	12
10	S2	Z	25.91	12
11	MP4	X	141.9	0
12	MP4	Z	81.93	0
13	MP4	X	141.9	72
14	MP4	Z	81.93	72
15	MP4	X	69.57	12
16	MP4	Z	40.16	12
17	MP4	X	69.57	12
18	MP4	Z	40.16	12
19	MP7	X	78.12	0
20	MP7	Z	45.1	0
21	MP7	X	78.12	72
22	MP7	Z	45.1	72
23	MP7	X	48.99	12
24	MP7	Z	28.28	12
25	MP7	X	44.84	12
26	MP7	Z	25.89	12

Member Point Loads (BLC 11 : Wind Load AZI 270)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
1	MP1	X	65.66	0
2	MP1	Z	0	0
3	MP1	X	65.66	72
4	MP1	Z	0	72
5	MP1	X	48.65	12
6	MP1	Z	0	12
7	MP1	X	42.26	12
8	MP1	Z	0	12
9	S2	X	43.64	12
10	S2	Z	0	12
11	MP4	X	139.3	0
12	MP4	Z	0	0
13	MP4	X	139.3	72

Member Point Loads (BLC 11 : Wind Load AZI 270) (Continued)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
14	MP4	Z	0	72
15	MP4	X	72.41	12
16	MP4	Z	0	12
17	MP4	X	70.81	12
18	MP4	Z	0	12
19	MP7	X	139.3	0
20	MP7	Z	0	0
21	MP7	X	139.3	72
22	MP7	Z	0	72
23	MP7	X	72.41	12
24	MP7	Z	0	12
25	MP7	X	70.81	12
26	MP7	Z	0	12

Member Point Loads (BLC 12 : Wind Load AZI 300)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
1	MP1	X	78.12	0
2	MP1	Z	-45.1	0
3	MP1	X	78.12	72
4	MP1	Z	-45.1	72
5	MP1	X	48.99	12
6	MP1	Z	-28.28	12
7	MP1	X	44.84	12
8	MP1	Z	-25.89	12
9	S2	X	44.88	12
10	S2	Z	-25.91	12
11	MP4	X	78.12	0
12	MP4	Z	-45.1	0
13	MP4	X	78.12	72
14	MP4	Z	-45.1	72
15	MP4	X	48.99	12
16	MP4	Z	-28.28	12
17	MP4	X	44.84	12
18	MP4	Z	-25.89	12
19	MP7	X	141.9	0
20	MP7	Z	-81.93	0
21	MP7	X	141.9	72
22	MP7	Z	-81.93	72
23	MP7	X	69.57	12
24	MP7	Z	-40.16	12
25	MP7	X	69.57	12
26	MP7	Z	-40.16	12

Member Point Loads (BLC 13 : Wind Load AZI 330)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
1	MP1	X	69.65	0
2	MP1	Z	-120.64	0
3	MP1	X	69.65	72
4	MP1	Z	-120.64	72
5	MP1	X	36.2	12
6	MP1	Z	-62.71	12
7	MP1	X	35.41	12
8	MP1	Z	-61.32	12
9	S2	X	34.09	12
10	S2	Z	-59.05	12
11	MP4	X	32.83	0
12	MP4	Z	-56.87	0
13	MP4	X	32.83	72
14	MP4	Z	-56.87	72
15	MP4	X	24.32	12
16	MP4	Z	-42.13	12
17	MP4	X	21.13	12
18	MP4	Z	-36.6	12
19	MP7	X	69.65	0
20	MP7	Z	-120.64	0
21	MP7	X	69.65	72
22	MP7	Z	-120.64	72
23	MP7	X	36.2	12
24	MP7	Z	-62.71	12
25	MP7	X	35.41	12
26	MP7	Z	-61.32	12

Member Point Loads (BLC 16 : Ice Weight)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
1	MP1	Y	-89.373	0
2	MP1	Y	-89.373	72
3	MP1	Y	-45.249	12
4	MP1	Y	-42.337	12
5	S2	Y	-41.251	12
6	MP4	Y	-89.373	0
7	MP4	Y	-89.373	72
8	MP4	Y	-45.249	12
9	MP4	Y	-42.337	12
10	MP7	Y	-89.373	0
11	MP7	Y	-89.373	72
12	MP7	Y	-45.249	12
13	MP7	Y	-42.337	12

Member Point Loads (BLC 17 : Ice Wind Load AZI 0)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
1	MP1	X	0	0
2	MP1	Z	-21.17	0
3	MP1	X	0	72
4	MP1	Z	-21.17	72
5	MP1	X	0	12
6	MP1	Z	-7.67	12
7	MP1	X	0	12
8	MP1	Z	-7.67	12
9	S2	X	0	12
10	S2	Z	-7.38	12
11	MP4	X	0	0
12	MP4	Z	-15.64	0
13	MP4	X	0	72
14	MP4	Z	-15.64	72
15	MP4	X	0	12
16	MP4	Z	-6.45	12
17	MP4	X	0	12
18	MP4	Z	-6.2	12
19	MP7	X	0	0
20	MP7	Z	-15.64	0
21	MP7	X	0	72
22	MP7	Z	-15.64	72
23	MP7	X	0	12
24	MP7	Z	-6.45	12
25	MP7	X	0	12
26	MP7	Z	-6.2	12

Member Point Loads (BLC 18 : Ice Wind Load AZI 30)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
1	MP1	X	-9.66	0
2	MP1	Z	-16.74	0
3	MP1	X	-9.66	72
4	MP1	Z	-16.74	72
5	MP1	X	-3.63	12
6	MP1	Z	-6.29	12
7	MP1	X	-3.59	12
8	MP1	Z	-6.22	12
9	S2	X	-3.5	12
10	S2	Z	-6.06	12
11	MP4	X	-9.66	0
12	MP4	Z	-16.74	0
13	MP4	X	-9.66	72

Member Point Loads (BLC 18 : Ice Wind Load AZI 30) (Continued)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
14	MP4	Z	-16.74	72
15	MP4	X	-3.63	12
16	MP4	Z	-6.29	12
17	MP4	X	-3.59	12
18	MP4	Z	-6.22	12
19	MP7	X	-6.9	0
20	MP7	Z	-11.94	0
21	MP7	X	-6.9	72
22	MP7	Z	-11.94	72
23	MP7	X	-3.02	12
24	MP7	Z	-5.24	12
25	MP7	X	-2.86	12
26	MP7	Z	-4.95	12

Member Point Loads (BLC 19 : Ice Wind Load AZI 60)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
1	MP1	X	-13.54	0
2	MP1	Z	-7.82	0
3	MP1	X	-13.54	72
4	MP1	Z	-7.82	72
5	MP1	X	-5.59	12
6	MP1	Z	-3.23	12
7	MP1	X	-5.37	12
8	MP1	Z	-3.1	12
9	S2	X	-5.38	12
10	S2	Z	-3.11	12
11	MP4	X	-18.34	0
12	MP4	Z	-10.59	0
13	MP4	X	-18.34	72
14	MP4	Z	-10.59	72
15	MP4	X	-6.65	12
16	MP4	Z	-3.84	12
17	MP4	X	-6.65	12
18	MP4	Z	-3.84	12
19	MP7	X	-13.54	0
20	MP7	Z	-7.82	0
21	MP7	X	-13.54	72
22	MP7	Z	-7.82	72
23	MP7	X	-5.59	12
24	MP7	Z	-3.23	12
25	MP7	X	-5.37	12
26	MP7	Z	-3.1	12

Member Point Loads (BLC 20 : Ice Wind Load AZI 90)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
1	MP1	X	-13.79	0
2	MP1	Z	0	0
3	MP1	X	-13.79	72
4	MP1	Z	0	72
5	MP1	X	-6.05	12
6	MP1	Z	0	12
7	MP1	X	-5.71	12
8	MP1	Z	0	12
9	S2	X	-5.83	12
10	S2	Z	0	12
11	MP4	X	-19.33	0
12	MP4	Z	0	0
13	MP4	X	-19.33	72
14	MP4	Z	0	72
15	MP4	X	-7.27	12
16	MP4	Z	0	12
17	MP4	X	-7.18	12
18	MP4	Z	0	12
19	MP7	X	-19.33	0
20	MP7	Z	0	0
21	MP7	X	-19.33	72
22	MP7	Z	0	72
23	MP7	X	-7.27	12
24	MP7	Z	0	12
25	MP7	X	-7.18	12
26	MP7	Z	0	12

Member Point Loads (BLC 21 : Ice Wind Load AZI 120)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
1	MP1	X	-13.54	0
2	MP1	Z	7.82	0
3	MP1	X	-13.54	72
4	MP1	Z	7.82	72
5	MP1	X	-5.59	12
6	MP1	Z	3.23	12
7	MP1	X	-5.37	12
8	MP1	Z	3.1	12
9	S2	X	-5.38	12
10	S2	Z	3.11	12
11	MP4	X	-13.54	0
12	MP4	Z	7.82	0
13	MP4	X	-13.54	72

Member Point Loads (BLC 21 : Ice Wind Load AZI 120) (Continued)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
14	MP4	Z	7.82	72
15	MP4	X	-5.59	12
16	MP4	Z	3.23	12
17	MP4	X	-5.37	12
18	MP4	Z	3.1	12
19	MP7	X	-18.34	0
20	MP7	Z	10.59	0
21	MP7	X	-18.34	72
22	MP7	Z	10.59	72
23	MP7	X	-6.65	12
24	MP7	Z	3.84	12
25	MP7	X	-6.65	12
26	MP7	Z	3.84	12

Member Point Loads (BLC 22 : Ice Wind Load AZI 150)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
1	MP1	X	-9.66	0
2	MP1	Z	16.74	0
3	MP1	X	-9.66	72
4	MP1	Z	16.74	72
5	MP1	X	-3.63	12
6	MP1	Z	6.29	12
7	MP1	X	-3.59	12
8	MP1	Z	6.22	12
9	S2	X	-3.5	12
10	S2	Z	6.06	12
11	MP4	X	-6.9	0
12	MP4	Z	11.94	0
13	MP4	X	-6.9	72
14	MP4	Z	11.94	72
15	MP4	X	-3.02	12
16	MP4	Z	5.24	12
17	MP4	X	-2.86	12
18	MP4	Z	4.95	12
19	MP7	X	-9.66	0
20	MP7	Z	16.74	0
21	MP7	X	-9.66	72
22	MP7	Z	16.74	72
23	MP7	X	-3.63	12
24	MP7	Z	6.29	12
25	MP7	X	-3.59	12
26	MP7	Z	6.22	12

Member Point Loads (BLC 23 : Ice Wind Load AZI 180)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
1	MP1	X	0	0
2	MP1	Z	21.17	0
3	MP1	X	0	72
4	MP1	Z	21.17	72
5	MP1	X	0	12
6	MP1	Z	7.67	12
7	MP1	X	0	12
8	MP1	Z	7.67	12
9	S2	X	0	12
10	S2	Z	7.38	12
11	MP4	X	0	0
12	MP4	Z	15.64	0
13	MP4	X	0	72
14	MP4	Z	15.64	72
15	MP4	X	0	12
16	MP4	Z	6.45	12
17	MP4	X	0	12
18	MP4	Z	6.2	12
19	MP7	X	0	0
20	MP7	Z	15.64	0
21	MP7	X	0	72
22	MP7	Z	15.64	72
23	MP7	X	0	12
24	MP7	Z	6.45	12
25	MP7	X	0	12
26	MP7	Z	6.2	12

Member Point Loads (BLC 24 : Ice Wind Load AZI 210)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
1	MP1	X	9.66	0
2	MP1	Z	16.74	0
3	MP1	X	9.66	72
4	MP1	Z	16.74	72
5	MP1	X	3.63	12
6	MP1	Z	6.29	12
7	MP1	X	3.59	12
8	MP1	Z	6.22	12
9	S2	X	3.5	12
10	S2	Z	6.06	12
11	MP4	X	9.66	0
12	MP4	Z	16.74	0
13	MP4	X	9.66	72

Member Point Loads (BLC 24 : Ice Wind Load AZI 210) (Continued)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
14	MP4	Z	16.74	72
15	MP4	X	3.63	12
16	MP4	Z	6.29	12
17	MP4	X	3.59	12
18	MP4	Z	6.22	12
19	MP7	X	6.9	0
20	MP7	Z	11.94	0
21	MP7	X	6.9	72
22	MP7	Z	11.94	72
23	MP7	X	3.02	12
24	MP7	Z	5.24	12
25	MP7	X	2.86	12
26	MP7	Z	4.95	12

Member Point Loads (BLC 25 : Ice Wind Load AZI 240)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
1	MP1	X	13.54	0
2	MP1	Z	7.82	0
3	MP1	X	13.54	72
4	MP1	Z	7.82	72
5	MP1	X	5.59	12
6	MP1	Z	3.23	12
7	MP1	X	5.37	12
8	MP1	Z	3.1	12
9	S2	X	5.38	12
10	S2	Z	3.11	12
11	MP4	X	18.34	0
12	MP4	Z	10.59	0
13	MP4	X	18.34	72
14	MP4	Z	10.59	72
15	MP4	X	6.65	12
16	MP4	Z	3.84	12
17	MP4	X	6.65	12
18	MP4	Z	3.84	12
19	MP7	X	13.54	0
20	MP7	Z	7.82	0
21	MP7	X	13.54	72
22	MP7	Z	7.82	72
23	MP7	X	5.59	12
24	MP7	Z	3.23	12
25	MP7	X	5.37	12
26	MP7	Z	3.1	12

Member Point Loads (BLC 26 : Ice Wind Load AZI 270)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
1	MP1	X	13.79	0
2	MP1	Z	0	0
3	MP1	X	13.79	72
4	MP1	Z	0	72
5	MP1	X	6.05	12
6	MP1	Z	0	12
7	MP1	X	5.71	12
8	MP1	Z	0	12
9	S2	X	5.83	12
10	S2	Z	0	12
11	MP4	X	19.33	0
12	MP4	Z	0	0
13	MP4	X	19.33	72
14	MP4	Z	0	72
15	MP4	X	7.27	12
16	MP4	Z	0	12
17	MP4	X	7.18	12
18	MP4	Z	0	12
19	MP7	X	19.33	0
20	MP7	Z	0	0
21	MP7	X	19.33	72
22	MP7	Z	0	72
23	MP7	X	7.27	12
24	MP7	Z	0	12
25	MP7	X	7.18	12
26	MP7	Z	0	12

Member Point Loads (BLC 27 : Ice Wind Load AZI 300)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
1	MP1	X	13.54	0
2	MP1	Z	-7.82	0
3	MP1	X	13.54	72
4	MP1	Z	-7.82	72
5	MP1	X	5.59	12
6	MP1	Z	-3.23	12
7	MP1	X	5.37	12
8	MP1	Z	-3.1	12
9	S2	X	5.38	12
10	S2	Z	-3.11	12
11	MP4	X	13.54	0
12	MP4	Z	-7.82	0
13	MP4	X	13.54	72

Member Point Loads (BLC 27 : Ice Wind Load AZI 300) (Continued)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
14	MP4	Z	-7.82	72
15	MP4	X	5.59	12
16	MP4	Z	-3.23	12
17	MP4	X	5.37	12
18	MP4	Z	-3.1	12
19	MP7	X	18.34	0
20	MP7	Z	-10.59	0
21	MP7	X	18.34	72
22	MP7	Z	-10.59	72
23	MP7	X	6.65	12
24	MP7	Z	-3.84	12
25	MP7	X	6.65	12
26	MP7	Z	-3.84	12

Member Point Loads (BLC 28 : Ice Wind Load AZI 330)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
1	MP1	X	9.66	0
2	MP1	Z	-16.74	0
3	MP1	X	9.66	72
4	MP1	Z	-16.74	72
5	MP1	X	3.63	12
6	MP1	Z	-6.29	12
7	MP1	X	3.59	12
8	MP1	Z	-6.22	12
9	S2	X	3.5	12
10	S2	Z	-6.06	12
11	MP4	X	6.9	0
12	MP4	Z	-11.94	0
13	MP4	X	6.9	72
14	MP4	Z	-11.94	72
15	MP4	X	3.02	12
16	MP4	Z	-5.24	12
17	MP4	X	2.86	12
18	MP4	Z	-4.95	12
19	MP7	X	9.66	0
20	MP7	Z	-16.74	0
21	MP7	X	9.66	72
22	MP7	Z	-16.74	72
23	MP7	X	3.63	12
24	MP7	Z	-6.29	12
25	MP7	X	3.59	12
26	MP7	Z	-6.22	12

Member Point Loads (BLC 31 : Seismic Load Z)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
1	MP1	Z	-9.391	0
2	MP1	Z	-9.391	72
3	MP1	Z	-21.825	12
4	MP1	Z	-18.616	12
5	S2	Z	-6.363	12
6	MP4	Z	-9.391	0
7	MP4	Z	-9.391	72
8	MP4	Z	-21.825	12
9	MP4	Z	-18.616	12
10	MP7	Z	-9.391	0
11	MP7	Z	-9.391	72
12	MP7	Z	-21.825	12
13	MP7	Z	-18.616	12

Member Point Loads (BLC 32 : Seismic Load X)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
1	MP1	X	-9.391	0
2	MP1	X	-9.391	72
3	MP1	X	-21.825	12
4	MP1	X	-18.616	12
5	S2	X	-6.363	12
6	MP4	X	-9.391	0
7	MP4	X	-9.391	72
8	MP4	X	-21.825	12
9	MP4	X	-18.616	12
10	MP7	X	-9.391	0
11	MP7	X	-9.391	72
12	MP7	X	-21.825	12
13	MP7	X	-18.616	12

Joint Loads and Enforced Displacements (BLC 33 : Service Live Loads)

	Joint Label	L,D,M	Direction	Magnitude[(lb,lb-ft), (in,rad), (lb*s^2/in, lb*s^2*in)]
1	N72B	L	Y	-250
2	N135A	L	Y	-250
3	N129B	L	Y	-250

Joint Loads and Enforced Displacements (BLC 34 : Maintenance Load 1)

	Joint Label	L,D,M	Direction	Magnitude[(lb,lb-ft), (in,rad), (lb*s^2/in, lb*s^2*in)]
1	N70A	L	Y	-500

Joint Loads and Enforced Displacements (BLC 35 : Maintenance Load 2)

	Joint Label	L,D,M	Direction	Magnitude[(lb,lb-ft), (in,rad), (lb*s^2/in, lb*s^2*in)]
1	N69A	L	Y	-500

Joint Loads and Enforced Displacements (BLC 36 : Maintenance Load 3)

	Joint Label	L,D,M	Direction	Magnitude[(lb,lb-ft), (in,rad), (lb*s^2/in, lb*s^2*in)]
1	N76	L	Y	-500

Joint Loads and Enforced Displacements (BLC 37 : Maintenance Load 4)

	Joint Label	L,D,M	Direction	Magnitude[(lb,lb-ft), (in,rad), (lb*s^2/in, lb*s^2*in)]
1	N94	L	Y	-500

Joint Loads and Enforced Displacements (BLC 38 : Maintenance Load 5)

	Joint Label	L,D,M	Direction	Magnitude[(lb,lb-ft), (in,rad), (lb*s^2/in, lb*s^2*in)]
1	N93	L	Y	-500

Joint Loads and Enforced Displacements (BLC 39 : Maintenance Load 6)

	Joint Label	L,D,M	Direction	Magnitude[(lb,lb-ft), (in,rad), (lb*s^2/in, lb*s^2*in)]
1	N122	L	Y	-500

Joint Loads and Enforced Displacements (BLC 40 : Maintenance Load 7)

	Joint Label	L,D,M	Direction	Magnitude[(lb,lb-ft), (in,rad), (lb*s^2/in, lb*s^2*in)]
1	N121	L	Y	-500

Joint Loads and Enforced Displacements (BLC 41 : Maintenance Load 8)

	Joint Label	L,D,M	Direction	Magnitude[(lb,lb-ft), (in,rad), (lb*s^2/in, lb*s^2*in)]
1	N133B	L	Y	-500

Joint Loads and Enforced Displacements (BLC 42 : Maintenance Load 9)

	Joint Label	L,D,M	Direction	Magnitude[(lb,lb-ft), (in,rad), (lb*s^2/in, lb*s^2*in)]
1	N139	L	Y	-500

Member Distributed Loads (BLC 14 : Distr. Wind Load Z)

	Member Label	Direction	Start Magnitude[lb/ft,...	End Magn...	Start Location...	End Location[in,%]
1	S3	SZ	-90.914	-90.914	0	%100
2	GA4	SZ	-90.914	-90.914	0	%100
3	GA3	SZ	-90.914	-90.914	0	%100
4	P3	SZ	-90.914	-90.914	0	%100
5	S2	SZ	-90.914	-90.914	0	%100
6	GA2	SZ	-90.914	-90.914	0	%100

Member Distributed Loads (BLC 14 : Distr. Wind Load Z) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft,...	End Magn...	Start Location...	End Location[in,%]
7	GA1	SZ	-90.914	-90.914	0	%100
8	P2	SZ	-90.914	-90.914	0	%100
9	S1	SZ	-90.914	-90.914	0	%100
10	GA6	SZ	-90.914	-90.914	0	%100
11	GA5	SZ	-90.914	-90.914	0	%100
12	P1	SZ	-90.914	-90.914	0	%100
13	H1	SZ	-54.549	-54.549	0	%100
14	MP1	SZ	-54.549	-54.549	0	%100
15	MP3	SZ	-54.549	-54.549	0	%100
16	HR1	SZ	-54.549	-54.549	0	%100
17	CA8	SZ	-90.914	-90.914	0	%100
18	CA9	SZ	-90.914	-90.914	0	%100
19	CA7	SZ	-90.914	-90.914	0	%100
20	M32	SZ	0	0	0	%100
21	M35	SZ	0	0	0	%100
22	M36	SZ	0	0	0	%100
23	M39A	SZ	0	0	0	%100
24	CA3	SZ	-90.914	-90.914	0	%100
25	CA4	SZ	-90.914	-90.914	0	%100
26	CA1	SZ	-90.914	-90.914	0	%100
27	CA2	SZ	-90.914	-90.914	0	%100
28	CA5	SZ	-90.914	-90.914	0	%100
29	CA6	SZ	-90.914	-90.914	0	%100
30	M64	SZ	0	0	0	%100
31	M65	SZ	0	0	0	%100
32	M66	SZ	0	0	0	%100
33	M67	SZ	0	0	0	%100
34	M68	SZ	0	0	0	%100
35	M69	SZ	0	0	0	%100
36	M70	SZ	0	0	0	%100
37	M71	SZ	0	0	0	%100
38	M72	SZ	0	0	0	%100
39	M73	SZ	0	0	0	%100
40	M74	SZ	0	0	0	%100
41	M75	SZ	-90.914	-90.914	0	%100
42	MP2	SZ	-54.549	-54.549	0	%100
43	M43	SZ	0	0	0	%100
44	M44	SZ	0	0	0	%100
45	H3	SZ	-54.549	-54.549	0	%100
46	MP7	SZ	-54.549	-54.549	0	%100
47	MP9	SZ	-54.549	-54.549	0	%100
48	HR3	SZ	-54.549	-54.549	0	%100

Member Distributed Loads (BLC 14 : Distr. Wind Load Z) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft,...	End Magn...	Start Location...	End Location[in,%]
49	M52	SZ	0	0	0	%100
50	M53	SZ	0	0	0	%100
51	M54	SZ	0	0	0	%100
52	M55	SZ	0	0	0	%100
53	H2	SZ	-54.549	-54.549	0	%100
54	MP4	SZ	-54.549	-54.549	0	%100
55	MP6	SZ	-54.549	-54.549	0	%100
56	HR2	SZ	-54.549	-54.549	0	%100
57	M66A	SZ	0	0	0	%100
58	M67A	SZ	0	0	0	%100
59	M68A	SZ	0	0	0	%100
60	M69A	SZ	0	0	0	%100
61	MP8	SZ	-54.549	-54.549	0	%100
62	M68B	SZ	0	0	0	%100
63	M69B	SZ	0	0	0	%100
64	MP5	SZ	-54.549	-54.549	0	%100
65	M71B	SZ	0	0	0	%100
66	M72B	SZ	0	0	0	%100

Member Distributed Loads (BLC 15 : Distr. Wind Load X)

	Member Label	Direction	Start Magnitude[lb/ft,...	End Magn...	Start Location...	End Location[in,%]
1	S3	SX	-90.914	-90.914	0	%100
2	GA4	SX	-90.914	-90.914	0	%100
3	GA3	SX	-90.914	-90.914	0	%100
4	P3	SX	-90.914	-90.914	0	%100
5	S2	SX	-90.914	-90.914	0	%100
6	GA2	SX	-90.914	-90.914	0	%100
7	GA1	SX	-90.914	-90.914	0	%100
8	P2	SX	-90.914	-90.914	0	%100
9	S1	SX	-90.914	-90.914	0	%100
10	GA6	SX	-90.914	-90.914	0	%100
11	GA5	SX	-90.914	-90.914	0	%100
12	P1	SX	-90.914	-90.914	0	%100
13	H1	SX	-54.549	-54.549	0	%100
14	MP1	SX	-54.549	-54.549	0	%100
15	MP3	SX	-54.549	-54.549	0	%100
16	HR1	SX	-54.549	-54.549	0	%100
17	CA8	SX	-90.914	-90.914	0	%100
18	CA9	SX	-90.914	-90.914	0	%100
19	CA7	SX	-90.914	-90.914	0	%100
20	M32	SX	0	0	0	%100
21	M35	SX	0	0	0	%100

Member Distributed Loads (BLC 15 : Distr. Wind Load X) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft,...	End Magn...	Start Location...	End Location[in,%]
22	M36	SX	0	0	0	%100
23	M39A	SX	0	0	0	%100
24	CA3	SX	-90.914	-90.914	0	%100
25	CA4	SX	-90.914	-90.914	0	%100
26	CA1	SX	-90.914	-90.914	0	%100
27	CA2	SX	-90.914	-90.914	0	%100
28	CA5	SX	-90.914	-90.914	0	%100
29	CA6	SX	-90.914	-90.914	0	%100
30	M64	SX	0	0	0	%100
31	M65	SX	0	0	0	%100
32	M66	SX	0	0	0	%100
33	M67	SX	0	0	0	%100
34	M68	SX	0	0	0	%100
35	M69	SX	0	0	0	%100
36	M70	SX	0	0	0	%100
37	M71	SX	0	0	0	%100
38	M72	SX	0	0	0	%100
39	M73	SX	0	0	0	%100
40	M74	SX	0	0	0	%100
41	M75	SX	-90.914	-90.914	0	%100
42	MP2	SX	-54.549	-54.549	0	%100
43	M43	SX	0	0	0	%100
44	M44	SX	0	0	0	%100
45	H3	SX	-54.549	-54.549	0	%100
46	MP7	SX	-54.549	-54.549	0	%100
47	MP9	SX	-54.549	-54.549	0	%100
48	HR3	SX	-54.549	-54.549	0	%100
49	M52	SX	0	0	0	%100
50	M53	SX	0	0	0	%100
51	M54	SX	0	0	0	%100
52	M55	SX	0	0	0	%100
53	H2	SX	-54.549	-54.549	0	%100
54	MP4	SX	-54.549	-54.549	0	%100
55	MP6	SX	-54.549	-54.549	0	%100
56	HR2	SX	-54.549	-54.549	0	%100
57	M66A	SX	0	0	0	%100
58	M67A	SX	0	0	0	%100
59	M68A	SX	0	0	0	%100
60	M69A	SX	0	0	0	%100
61	MP8	SX	-54.549	-54.549	0	%100
62	M68B	SX	0	0	0	%100
63	M69B	SX	0	0	0	%100

Member Distributed Loads (BLC 15 : Distr. Wind Load X) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft,...	End Magn...	Start Location...	End Location[in,%]
64	MP5	SX	-54.549	-54.549	0	%100
65	M71B	SX	0	0	0	%100
66	M72B	SX	0	0	0	%100

Member Distributed Loads (BLC 16 : Ice Weight)

	Member Label	Direction	Start Magnitude[lb/ft,...	End Magn...	Start Location...	End Location[in,%]
1	S3	Y	-9.508	-9.508	0	%100
2	GA4	Y	-5.554	-5.554	0	%100
3	GA3	Y	-5.554	-5.554	0	%100
4	P3	Y	-10.702	-10.702	0	%100
5	S2	Y	-9.508	-9.508	0	%100
6	GA2	Y	-5.554	-5.554	0	%100
7	GA1	Y	-5.554	-5.554	0	%100
8	P2	Y	-10.702	-10.702	0	%100
9	S1	Y	-9.508	-9.508	0	%100
10	GA6	Y	-5.554	-5.554	0	%100
11	GA5	Y	-5.554	-5.554	0	%100
12	P1	Y	-10.702	-10.702	0	%100
13	H1	Y	-6.493	-6.493	0	%100
14	MP1	Y	-5.619	-5.619	0	%100
15	MP3	Y	-5.619	-5.619	0	%100
16	HR1	Y	-5.626	-5.626	0	%100
17	CA8	Y	-12.736	-12.736	0	%100
18	CA9	Y	-12.736	-12.736	0	%100
19	CA7	Y	-12.736	-12.736	0	%100
20	M32	Y	-1.6	-1.6	0	%100
21	M35	Y	-1.6	-1.6	0	%100
22	M36	Y	-1.6	-1.6	0	%100
23	M39A	Y	-1.6	-1.6	0	%100
24	CA3	Y	-7.133	-7.133	0	%100
25	CA4	Y	-7.133	-7.133	0	%100
26	CA1	Y	-7.133	-7.133	0	%100
27	CA2	Y	-7.133	-7.133	0	%100
28	CA5	Y	-7.133	-7.133	0	%100
29	CA6	Y	-7.133	-7.133	0	%100
30	M64	Y	-1.6	-1.6	0	%100
31	M65	Y	-1.6	-1.6	0	%100
32	M66	Y	-1.6	-1.6	0	%100
33	M67	Y	-1.6	-1.6	0	%100
34	M68	Y	-1.6	-1.6	0	%100
35	M69	Y	-1.6	-1.6	0	%100
36	M70	Y	-1.6	-1.6	0	%100

Member Distributed Loads (BLC 16 : Ice Weight) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft,...	End Magn...	Start Location...	End Location[in,%]
37	M71	Y	-1.6	-1.6	0	%100
38	M72	Y	-1.6	-1.6	0	%100
39	M73	Y	-1.6	-1.6	0	%100
40	M74	Y	-1.6	-1.6	0	%100
41	M75	Y	-4.993	-4.993	0	%100
42	MP2	Y	-5.619	-5.619	0	%100
43	M43	Y	-1.6	-1.6	0	%100
44	M44	Y	-1.6	-1.6	0	%100
45	H3	Y	-6.493	-6.493	0	%100
46	MP7	Y	-5.619	-5.619	0	%100
47	MP9	Y	-5.619	-5.619	0	%100
48	HR3	Y	-5.626	-5.626	0	%100
49	M52	Y	-1.6	-1.6	0	%100
50	M53	Y	-1.6	-1.6	0	%100
51	M54	Y	-1.6	-1.6	0	%100
52	M55	Y	-1.6	-1.6	0	%100
53	H2	Y	-6.493	-6.493	0	%100
54	MP4	Y	-5.619	-5.619	0	%100
55	MP6	Y	-5.619	-5.619	0	%100
56	HR2	Y	-5.626	-5.626	0	%100
57	M66A	Y	-1.6	-1.6	0	%100
58	M67A	Y	-1.6	-1.6	0	%100
59	M68A	Y	-1.6	-1.6	0	%100
60	M69A	Y	-1.6	-1.6	0	%100
61	MP8	Y	-5.619	-5.619	0	%100
62	M68B	Y	-1.6	-1.6	0	%100
63	M69B	Y	-1.6	-1.6	0	%100
64	MP5	Y	-5.619	-5.619	0	%100
65	M71B	Y	-1.6	-1.6	0	%100
66	M72B	Y	-1.6	-1.6	0	%100

Member Distributed Loads (BLC 29 : Distr. Ice Wind Load Z)

	Member Label	Direction	Start Magnitude[lb/ft,...	End Magn...	Start Location...	End Location[in,%]
1	S3	SZ	-13.302	-13.302	0	%100
2	GA4	SZ	-17.133	-17.133	0	%100
3	GA3	SZ	-17.133	-17.133	0	%100
4	P3	SZ	-12.799	-12.799	0	%100
5	S2	SZ	-13.302	-13.302	0	%100
6	GA2	SZ	-17.133	-17.133	0	%100
7	GA1	SZ	-17.133	-17.133	0	%100
8	P2	SZ	-12.799	-12.799	0	%100
9	S1	SZ	-13.302	-13.302	0	%100

Member Distributed Loads (BLC 29 : Distr. Ice Wind Load Z) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft,...	End Magn...	Start Location...	End Location[in,%]
10	GA6	SZ	-17.133	-17.133	0	%100
11	GA5	SZ	-17.133	-17.133	0	%100
12	P1	SZ	-12.799	-12.799	0	%100
13	H1	SZ	-15.663	-15.663	0	%100
14	MP1	SZ	-17.009	-17.009	0	%100
15	MP3	SZ	-17.009	-17.009	0	%100
16	HR1	SZ	-16.996	-16.996	0	%100
17	CA8	SZ	-12.191	-12.191	0	%100
18	CA9	SZ	-12.191	-12.191	0	%100
19	CA7	SZ	-12.191	-12.191	0	%100
20	M32	SZ	0	0	0	%100
21	M35	SZ	0	0	0	%100
22	M36	SZ	0	0	0	%100
23	M39A	SZ	0	0	0	%100
24	CA3	SZ	-14.946	-14.946	0	%100
25	CA4	SZ	-14.946	-14.946	0	%100
26	CA1	SZ	-14.946	-14.946	0	%100
27	CA2	SZ	-14.946	-14.946	0	%100
28	CA5	SZ	-14.946	-14.946	0	%100
29	CA6	SZ	-14.946	-14.946	0	%100
30	M64	SZ	0	0	0	%100
31	M65	SZ	0	0	0	%100
32	M66	SZ	0	0	0	%100
33	M67	SZ	0	0	0	%100
34	M68	SZ	0	0	0	%100
35	M69	SZ	0	0	0	%100
36	M70	SZ	0	0	0	%100
37	M71	SZ	0	0	0	%100
38	M72	SZ	0	0	0	%100
39	M73	SZ	0	0	0	%100
40	M74	SZ	0	0	0	%100
41	M75	SZ	-18.4	-18.4	0	%100
42	MP2	SZ	-17.009	-17.009	0	%100
43	M43	SZ	0	0	0	%100
44	M44	SZ	0	0	0	%100
45	H3	SZ	-15.663	-15.663	0	%100
46	MP7	SZ	-17.009	-17.009	0	%100
47	MP9	SZ	-17.009	-17.009	0	%100
48	HR3	SZ	-16.996	-16.996	0	%100
49	M52	SZ	0	0	0	%100
50	M53	SZ	0	0	0	%100
51	M54	SZ	0	0	0	%100

Member Distributed Loads (BLC 29 : Distr. Ice Wind Load Z) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft,...	End Magn...	Start Location...	End Location[in,%]
52	M55	SZ	0	0	0	%100
53	H2	SZ	-15.663	-15.663	0	%100
54	MP4	SZ	-17.009	-17.009	0	%100
55	MP6	SZ	-17.009	-17.009	0	%100
56	HR2	SZ	-16.996	-16.996	0	%100
57	M66A	SZ	0	0	0	%100
58	M67A	SZ	0	0	0	%100
59	M68A	SZ	0	0	0	%100
60	M69A	SZ	0	0	0	%100
61	MP8	SZ	-17.009	-17.009	0	%100
62	M68B	SZ	0	0	0	%100
63	M69B	SZ	0	0	0	%100
64	MP5	SZ	-17.009	-17.009	0	%100
65	M71B	SZ	0	0	0	%100
66	M72B	SZ	0	0	0	%100

Member Distributed Loads (BLC 30 : Distr. Ice Wind Load X)

	Member Label	Direction	Start Magnitude[lb/ft,...	End Magn...	Start Location...	End Location[in,%]
1	S3	SX	-13.302	-13.302	0	%100
2	GA4	SX	-17.133	-17.133	0	%100
3	GA3	SX	-17.133	-17.133	0	%100
4	P3	SX	-12.799	-12.799	0	%100
5	S2	SX	-13.302	-13.302	0	%100
6	GA2	SX	-17.133	-17.133	0	%100
7	GA1	SX	-17.133	-17.133	0	%100
8	P2	SX	-12.799	-12.799	0	%100
9	S1	SX	-13.302	-13.302	0	%100
10	GA6	SX	-17.133	-17.133	0	%100
11	GA5	SX	-17.133	-17.133	0	%100
12	P1	SX	-12.799	-12.799	0	%100
13	H1	SX	-15.663	-15.663	0	%100
14	MP1	SX	-17.009	-17.009	0	%100
15	MP3	SX	-17.009	-17.009	0	%100
16	HR1	SX	-16.996	-16.996	0	%100
17	CA8	SX	-12.191	-12.191	0	%100
18	CA9	SX	-12.191	-12.191	0	%100
19	CA7	SX	-12.191	-12.191	0	%100
20	M32	SX	0	0	0	%100
21	M35	SX	0	0	0	%100
22	M36	SX	0	0	0	%100
23	M39A	SX	0	0	0	%100
24	CA3	SX	-14.946	-14.946	0	%100

Member Distributed Loads (BLC 30 : Distr. Ice Wind Load X) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft,...	End Magn...	Start Location...	End Location[in,%]
25	CA4	SX	-14.946	-14.946	0	%100
26	CA1	SX	-14.946	-14.946	0	%100
27	CA2	SX	-14.946	-14.946	0	%100
28	CA5	SX	-14.946	-14.946	0	%100
29	CA6	SX	-14.946	-14.946	0	%100
30	M64	SX	0	0	0	%100
31	M65	SX	0	0	0	%100
32	M66	SX	0	0	0	%100
33	M67	SX	0	0	0	%100
34	M68	SX	0	0	0	%100
35	M69	SX	0	0	0	%100
36	M70	SX	0	0	0	%100
37	M71	SX	0	0	0	%100
38	M72	SX	0	0	0	%100
39	M73	SX	0	0	0	%100
40	M74	SX	0	0	0	%100
41	M75	SX	-18.4	-18.4	0	%100
42	MP2	SX	-17.009	-17.009	0	%100
43	M43	SX	0	0	0	%100
44	M44	SX	0	0	0	%100
45	H3	SX	-15.663	-15.663	0	%100
46	MP7	SX	-17.009	-17.009	0	%100
47	MP9	SX	-17.009	-17.009	0	%100
48	HR3	SX	-16.996	-16.996	0	%100
49	M52	SX	0	0	0	%100
50	M53	SX	0	0	0	%100
51	M54	SX	0	0	0	%100
52	M55	SX	0	0	0	%100
53	H2	SX	-15.663	-15.663	0	%100
54	MP4	SX	-17.009	-17.009	0	%100
55	MP6	SX	-17.009	-17.009	0	%100
56	HR2	SX	-16.996	-16.996	0	%100
57	M66A	SX	0	0	0	%100
58	M67A	SX	0	0	0	%100
59	M68A	SX	0	0	0	%100
60	M69A	SX	0	0	0	%100
61	MP8	SX	-17.009	-17.009	0	%100
62	M68B	SX	0	0	0	%100
63	M69B	SX	0	0	0	%100
64	MP5	SX	-17.009	-17.009	0	%100
65	M71B	SX	0	0	0	%100
66	M72B	SX	0	0	0	%100

Member Distributed Loads (BLC 43 : BLC 1 Transient Area Loads)

	Member Label	Direction	Start Magnitude[lb/ft,...	End Magn...	Start Location...	End Location[in, %]
1	S2	Y	-3.185	-3.185	16.404	40
2	GA2	Y	-1.605	-1.605	3.828	27.295
3	GA1	Y	-1.605	-1.605	3.828	27.295
4	S3	Y	-3.185	-3.185	16.404	40
5	GA4	Y	-1.605	-1.605	3.828	27.295
6	GA3	Y	-1.605	-1.605	3.828	27.295
7	S1	Y	-3.185	-3.185	16.404	40
8	GA6	Y	-1.605	-1.605	3.828	27.295
9	GA5	Y	-1.605	-1.605	3.828	27.295

Member Distributed Loads (BLC 44 : BLC 16 Transient Area Loads)

	Member Label	Direction	Start Magnitude[lb/ft,...	End Magn...	Start Location...	End Location[in, %]
1	S2	Y	-19.476	-19.476	16.404	40
2	GA2	Y	-9.815	-9.815	3.828	27.295
3	GA1	Y	-9.815	-9.815	3.828	27.295
4	S3	Y	-19.476	-19.476	16.404	40
5	GA4	Y	-9.815	-9.815	3.828	27.295
6	GA3	Y	-9.815	-9.815	3.828	27.295
7	S1	Y	-19.476	-19.476	16.404	40
8	GA6	Y	-9.815	-9.815	3.828	27.295
9	GA5	Y	-9.815	-9.815	3.828	27.295

Member Area Loads (BLC 1 : Self Weight)

	Joint A	Joint B	Joint C	Joint D	Direction	Distribution	Magnitude[psf]
1	P22	P21	P20	P23	Y	Two Way	-1.75
2	P10	P11	P12	P9	Y	Two Way	-1.75
3	P31	P34	P33	P32	Y	Two Way	-1.75

Member Area Loads (BLC 16 : Ice Weight)

	Joint A	Joint B	Joint C	Joint D	Direction	Distribution	Magnitude[psf]
1	P22	P21	P20	P23	Y	Two Way	-10.7
2	P10	P11	P12	P9	Y	Two Way	-10.7
3	P31	P34	P33	P32	Y	Two Way	-10.7

Envelope AISC 15th(360-16): LRFD Steel Code Checks

Member	Shape	Code Check	Loc[in]	LC	She...	Loc[in]	Dir	LC	phi*P...	phi*P...	phi*M...	phi*Mn z-z [lb...	Cb	Eqn
1	P3	PL6.5x0.375	.329	21	2	.149	36.312	y	5	3658...	78975	616.9...	7941.473	1....H1-1b
2	P2	PL6.5x0.375	.321	21	6	.140	36.312	y	10	3658...	78975	616.9...	7930.68	1....H1-1b
3	P1	PL6.5x0.375	.302	21	10	.151	36.312	y	2	3658...	78975	616.9...	7947.051	1....H1-1b

Envelope AISC 15th(360-16): LRFD Steel Code Checks (Continued)

Member	Shape	Code Check	Loc[in]	LC	She...	Loc[in]	Dir	LC	phi*P...	phi*P...	phi*M...	phi*Mn z-z	lb...	Cb	Eqn
4	CA4	C3.38x2.06...	.300	33	2	.033	33	y	115	4776...	56700	2202...	5751.945	1....	H1-1b
5	CA5	C3.38x2.06...	.294	0	10	.033	28.187	y	28	4776...	56700	2202...	5751.945	1.62	H1-1b
6	CA3	C3.38x2.06...	.288	0	2	.034	28.188	y	32	4776...	56700	2202...	5751.945	1....	H1-1b
7	CA1	C3.38x2.06...	.286	0	6	.035	28.188	y	36	4776...	56700	2202...	5751.945	1....	H1-1b
8	CA2	C3.38x2.06...	.284	33	6	.033	33	y	143	4776...	56700	2202...	5751.945	1....	H1-1b
9	CA6	C3.38x2.06...	.279	33	10	.032	33	y	87	4776...	56700	2202...	5751.945	1....	H1-1b
10	CA8	L6.6x4.46x0...	.279	41.562	22	.039	42	z	4	5117...	87561	2464...	7125.374	1....	H2-1
11	M75	PL 2.375x0.5	.274	1.5	12	.186	0	y	173	3825...	38475	400.7...	1903.711	2....	H1-1b
12	CA7	L6.6x4.46x0...	.269	41.562	3	.036	42	z	8	5117...	87561	2464...	7125.374	1....	H2-1
13	HR2	2.88x0.120	.268	90	3	.134	92		4	2249...	4307...	3155...	3155.674	1....	H1-1b
14	HR3	2.88x0.120	.266	6	2	.125	92		6	2249...	4307...	3155...	3155.674	1....	H1-1b
15	HR1	2.88x0.120	.257	6	4	.117	6		4	2249...	4307...	3155...	3155.674	1....	H1-1b
16	S2	HSS4X4X6	.254	0	5	.111	0	y	142	1882...	1978...	2204...	22045.5	1....	H1-1b
17	S3	HSS4X4X6	.248	0	13	.111	0	y	114	1882...	1978...	2204...	22045.5	1....	H1-1b
18	CA9	L6.6x4.46x0...	.246	41.562	6	.034	42	z	12	5117...	87561	2464...	7125.374	1....	H2-1
19	S1	HSS4X4X6	.229	0	9	.108	0	y	86	1882...	1978...	2204...	22045.5	1....	H1-1b
20	MP2	PIPE 2.5	.222	70	5	.080	70		5	3348...	66654	4726.5	4726.5	4....	H1-1b
21	MP5	PIPE 2.5	.219	70	7	.068	70		7	3348...	66654	4726.5	4726.5	4.59	H1-1b
22	GA4	L2x2x4	.207	0	2	.014	27.295	y	9	2952...	42480	959.63	2190.068	2....	H2-1
23	GA5	L2x2x4	.196	0	9	.018	27.295	z	2	2952...	42480	959.63	2190.068	2....	H2-1
24	MP8	PIPE 2.5	.196	70	9	.084	70		3	3348...	66654	4726.5	4726.5	4....	H1-1b
25	GA2	L2x2x4	.190	0	12	.015	0	y	12	2952...	42480	959.63	2190.068	2....	H2-1
26	GA1	L2x2x4	.177	0	6	.016	27.295	z	10	2952...	42480	959.63	2190.068	2....	H2-1
27	GA3	L2x2x4	.176	0	7	.018	27.295	z	6	2952...	42480	959.63	2190.068	2....	H2-1
28	GA6	L2x2x4	.176	0	4	.014	0	y	4	2952...	42480	959.63	2190.068	2.33	H2-1
29	MP9	PIPE 2.5	.174	70	2	.079	70		7	3348...	66654	4726.5	4726.5	3....	H1-1b
30	MP6	PIPE 2.5	.159	70	7	.086	70		6	3348...	66654	4726.5	4726.5	4....	H1-1b
31	MP1	PIPE 2.5	.156	70	11	.096	26		8	3348...	66654	4726.5	4726.5	2....	H1-1b
32	MP3	PIPE 2.5	.154	70	5	.087	70		3	3348...	66654	4726.5	4726.5	4....	H1-1b
33	MP4	PIPE 2.5	.150	70	7	.087	26		4	3348...	66654	4726.5	4726.5	1.83	H1-1b
34	MP7	PIPE 2.5	.147	70	9	.079	26		6	3348...	66654	4726.5	4726.5	3....	H1-1b
35	H3	Pipe3.5x0.1...	.135	31	2	.082	90		2	4587...	7158...	6337...	6337.65	1....	H1-1b
36	H1	Pipe3.5x0.1...	.129	31	10	.074	48		4	4587...	7158...	6337...	6337.65	2....	H1-1b
37	H2	Pipe3.5x0.1...	.128	31	6	.060	48		12	4587...	7158...	6337...	6337.65	1....	H1-1b

Bolt Calculation Tool, V1.5.1

PROJECT DATA		
Site Name:	BOBOS00030A	
Site Number:	BOBOS00030A	
Connection Description:	Platform to Monopole	

MAXIMUM BOLT LOADS		
Bolt Tension:	6863.03	lbs
Bolt Shear:	1638.45	lbs


WORST CASE BOLT LOADS ¹		
Bolt Tension:	6863.03	lbs
Bolt Shear:	468.47	lbs

BOLT PROPERTIES		
Bolt Type:	Bolt	-
Bolt Diameter:	0.625	in
Bolt Grade:	A325	-
# of Bolts:	4	-
Threads Excluded?	No	-

¹ Worst case bolt loads correspond to Load combination #5 on member S2 in RISA-3D, which causes the maximum demand on the bolts.

Member Information
I nodes of S3, S2, S1

BOLT CHECK		
Tensile Strength	20340.15	
Shear Strength	13805.83	
Max Tensile Usage	33.7%	
Max Shear Usage	11.9%	
Interaction Check (Worst Case)	0.11	≤1.05
Result	Pass	





AMERICAN TOWER®
CORPORATION

Structural Analysis Report

Structure : 149 ft Monopole
ATC Site Name : Woodstock Relo CT,CT
ATC Site Number : 418609
Engineering Number : 13733434_C3_03
Proposed Carrier : DISH WIRELESS L.L.C.
Carrier Site Name : BOBOS00030A
Carrier Site Number : BOBOS00030A
Site Location : 87 West Quasset Road
Woodstock, CT 06281-3225
41.9298, -71.9893
County : Windham
Date : November 15, 2021
Max Usage : 62%
Result : Pass

Prepared By:

Zachary S. Blackford
Structural Engineer

Reviewed By:



COA : PEC.0001553

Table of Contents

Introduction.....	3
Supporting Documents	3
Analysis	3
Conclusion	3
Existing and Reserved Equipment.....	4
Equipment to be Removed	4
Proposed Equipment	4
Structure Usages.....	5
Foundations	5
Deflection and Sway*	5
Standard Conditions	6
Calculations	Attached

Introduction

The purpose of this report is to summarize results of a structural analysis performed on the 149 ft Monopole to reflect the change in loading by DISH WIRELESS L.L.C..

Supporting Documents

Tower Drawings	EEI Project #16757, dated November 30, 2011
Foundation Drawing	EEI Project #16757, dated December 4, 2011
Geotechnical Report	DET Project #2011.17, dated November 23, 2011

Analysis

The tower was analyzed using American Tower Corporation's tower analysis software. This program considers an elastic three-dimensional model and second-order effects per ANSI/TIA-222.

Basic Wind Speed:	120 mph (3-second gust)
Basic Wind Speed w/ Ice:	50 mph (3-second gust) w/ 1.00" radial ice concurrent
Code:	ANSI/TIA-222-H / 2015 IBC / 2018 Connecticut State Building Code
Exposure Category:	C
Risk Category:	II
Topographic Factor Procedure:	Method 1
Topographic Category:	1
Spectral Response:	$S_s = 0.18$, $S_i = 0.06$
Site Class:	D - Stiff Soil - Default

Conclusion

Based on the analysis results, the structure meets the requirements per the applicable codes listed above. The tower and foundation can support the equipment as described in this report.

If you have any questions or require additional information, please contact American Tower via email at Engineering@americantower.com. Please include the American Tower site name, site number, and engineering number in the subject line for any questions.

Existing and Reserved Equipment

Elev. ¹ (ft)	Qty	Equipment	Mount Type	Lines	Carrier
147.0	1	VZW Unused Reserve (22199.55 sqin)	Triangular Platform with Handrails	(12) 1 5/8" Coax (2) 1 5/8" Hybriflex	VERIZON WIRELESS
	2	Raycap RRFDC-3315-PF-48			
	3	Samsung MT6407-77A			
	3	Andrew LNX-6514DS-A1M			
	6	Commscope SBNHH-1D65B (72.9")			
	3	Samsung B5/B13 RRH-BR04C			
	3	Samsung B2/B66A RRH-BR049			
138.0	3	Ericsson RRUS 4478 B14	Low Profile Platform w/ Site Pro 1 HRK12-3HD Reinforcement Kit	(3) 0.26" (6.6mm) Cat 5e (15) 0.78" (19.7mm) 8 AWG 6 (7) 2" conduit (6) 0.39" (10mm) Fiber Trunk (3) 3/8" (0.38"- 9.5mm) RET Control Cable	AT&T MOBILITY
	3	Ericsson RRUS 4449 B5, B12			
	3	Raycap DC9-48-60-24-8C-EV			
	3	Ericsson RRUS 8843 B2, B66A			
	3	Commscope NNHH-65C-R4			
	3	CCI DMP65R-BU8D			
	3	Ericsson Radio 4415 B30			
	3	Andrew SBNH-1D6565C (60.8 lbs)			

Equipment to be Removed

Elev. ¹ (ft)	Qty	Equipment	Mount Type	Lines	Carrier
No loading was considered as removed as part of this analysis.					

Proposed Equipment

Elev. ¹ (ft)	Qty	Equipment	Mount Type	Lines	Carrier
127.0	1	Raycap RDIDC-9181-PF-48	Triangular Platform with Handrails	(1) 1.60" (40.6mm) Hybrid	DISH WIRELESS L.L.C.
	3	Fujitsu TA08025-B604			
	3	Fujitsu TA08025-B605			
	3	Commscope FFVV-65B-R2			

¹ Contracted elevations are shown for appurtenances within contracted installation tolerances. Appurtenances outside of contract limits are shown at installed elevations.

Install proposed lines inside the pole shaft.

Structure Usages

Structural Component	Controlling Usage	Pass/Fail
Anchor Bolts	56%	Pass
Shaft	53%	Pass
Base Plate	27%	Pass

Foundations

Reaction Component	Analysis Reactions	% of Usage
Moment (Kips-Ft)	4326.8	62%
Shear (Kips)	38.0	34%

The structure base reactions resulting from this analysis were found to be acceptable through analysis based on geotechnical and foundation information, therefore no modification or reinforcement of the foundation will be required.

Deflection and Sway*

Antenna Elevation (ft)	Antenna	Carrier	Deflection (ft)	Sway (Rotation) (°)
127.0	Raycap RDIDC-9181-PF-48	DISH WIRELESS L.L.C.	0.903	0.800
	Commscope FFVV-65B-R2			
	Fujitsu TA08025-B605			
	Fujitsu TA08025-B604			

*Deflection and Sway was evaluated considering a design wind speed of 60 mph (3-Second Gust) per ANSI/TIA-222-H

Standard Conditions

All engineering services performed by A.T. Engineering Service, PLLC are prepared on the basis that the information used is current and correct. This information may consist of, but is not limited to the following:

- Information supplied by the client regarding antenna, mounts and feed line loading
- Information from drawings, design and analysis documents, and field notes in the possession of A.T. Engineering Service, PLLC

It is the responsibility of the client to ensure that the information provided to A.T. Engineering Service, PLLC and used in the performance of our engineering services is correct and complete.

All assets of American Tower Corporation, its affiliates, and subsidiaries (collectively “American Tower”) are inspected at regular intervals. Based upon these inspections and in the absence of information to the contrary, American Tower assumes that all structures were constructed in accordance with the drawings and specifications.


Unless explicitly agreed by both the client and A.T. Engineering Service, PLLC, all services will be performed in accordance with the current revision of ANSI/TIA-222.

All services are performed, results obtained, and recommendations made in accordance with generally accepted engineering principles and practices. A.T. Engineering Service, PLLC is not responsible for the conclusions, opinions and recommendations made by others based on the information supplied herein.

JOB INFORMATION

Asset : 418609, Woodstock Relo CT
 Client : DISH WIRELESS L.L.C.
 Code : ANSI/TIA-222-H

Height : 149 ft
 Base Width : 60.5
 Shape : 18 Sides



SITE PARAMETERS

Base Elev (ft): 0.00 Structure Class: II
 Taper : 0.21300 (In/ft) Exposure : C
 Topographic Category : 1 Topographic Feature:
 Topo Method : Method 1

SECTION PROPERTIES

Shaft Section	Length (ft)	Diameter (in)		Thick (in)	Joint Type	Overlap Length (in)	Shape	Steel Grade (ksi)
		Top	Bottom					
1	54.000	49.01	60.50	0.500		0.000	18 Sides	65
2	53.875	39.91	51.37	0.438	Slip Joint	84.000	18 Sides	65
3	53.875	30.29	41.76	0.312	Slip Joint	69.000	18 Sides	65

DISCRETE APPURTENANCE

Attach Elev (ft)	Force Elev (ft)	Qty	Description
148.0	148.0	1	Generic Flat Platform with Han
148.0	148.0	1	VZW Unused Reserve (22199.55 s
147.0	147.0	3	Samsung B5/B13 RRH-BR04C
147.0	147.0	3	Samsung B2/B66A RRH-BR049
147.0	147.0	2	Raycap RRFDC-3315-PF-48
147.0	147.0	3	Samsung MT6407-77A
147.0	149.0	3	Andrew LNX-6514DS-A1M
147.0	149.0	6	Commscope SBNHH-1D65B (72.9")
138.0	138.0	3	Ericsson RRUS 8843 B2, B66A
138.0	138.0	3	Ericsson Radio 4415 B30
138.0	138.0	3	Ericsson RRUS 4478 B14
138.0	138.0	3	Ericsson RRUS 4449 B5, B12
138.0	138.0	3	Raycap DC9-48-60-24-8C-EV
138.0	139.0	3	Andrew SBNH-1D6565C (60.8 lbs)
138.0	138.0	3	Commscope NNHH-65C-R4
138.0	138.0	3	CCI DMP65R-BU8D
138.0	138.0	1	Low Profile Platform w/ SiteP
127.0	127.0	1	Raycap RDIDC-9181-PF-48
127.0	127.0	3	Fujitsu TA08025-B604
127.0	127.0	3	Fujitsu TA08025-B605
127.0	127.0	3	Commscope FFVV-65B-R2
126.0	126.0	1	Generic Flat Platform with Han

LINEAR APPURTENANCE

Elev From (ft)	Elev To (ft)	Description	Exp To Wind
0.0	147.0	1 5/8" Hybriflex	No
0.0	147.0	1 5/8" Coax	No
0.0	141.0	2" conduit	No
0.0	141.0	0.78" (19.7mm) 8 AWG 6	No
0.0	141.0	0.26" (6.6mm) Cat 5e	No
0.0	138.0	3/8" (0.38"- 9.5mm) RET Control Cable	No
0.0	138.0	2" conduit	No
0.0	138.0	0.78" (19.7mm) 8 AWG 6	No
0.0	138.0	0.39" (10mm) Fiber Trunk	No
0.0	127.0	1.60" (40.6mm) Hybrid	No

LOAD CASES

1.2D + 1.0W Normal 120 mph wind with no ice
 0.9D + 1.0W Normal 120 mph wind with no ice
 1.2D + 1.0Di + 1.0Wi Nor 50 mph wind with 1" radial ice
 1.2D + 1.0Ev + 1.0Eh Nor Seismic
 0.9D - 1.0Ev + 1.0Eh Nor Seismic (Reduced DL)
 1.0D + 1.0W Service Norm 60 mph Wind with No Ice

JOB INFORMATION

Asset : 418609, Woodstock Relo CT
 Client : DISH WIRELESS L.L.C.
 Code : ANSI/TIA-222-H

Height : 149 ft
 Base Width : 60.5
 Shape : 18 Sides

REACTIONS

Load Case	Moment (kip-ft)	Shear (Kip)	Axial (Kip)
1.2D + 1.0W Normal	4326.75	37.97	64.00
0.9D + 1.0W Normal	4289.99	37.95	47.99
1.2D + 1.0Di + 1.0Wi Normal	1102.56	9.93	80.16
1.2D + 1.0Ev + 1.0Eh Normal	196.36	1.60	63.82
0.9D - 1.0Ev + 1.0Eh Normal	194.37	1.60	44.37
1.0D + 1.0W Service Normal	962.88	8.49	53.37

DISH DEFLECTIONS

Load Case	Attach Elev (ft)	Deflection (in)	Rotation (deg)
-----------	---------------------	--------------------	-------------------

ASSET: 418609, Woodstock Relo CT
CUSTOMER: DISH WIRELESS L.L.C.

CODE: ANSI/TIA-222-H
ENG NO: 13733434_C3_03

ANALYSIS PARAMETERS

Location:	Windham County,CT	Height:	149 ft
Type and Shape:	Taper, 18 Sides	Base Diameter:	60.50 in
Manufacturer:	EEI	Top Diameter:	30.29 in
K_d (non-service):	0.95	Taper:	0.2130 in/ft
K_e:	0.98	Rotation:	0.000°

ICE & WIND PARAMETERS

Exposure Category:	C	Design Wind Speed w/o Ice:	120 mph
Risk Category:	II	Design Wind Speed w/Ice:	50 mph
Topo Factor Procedure:	Method 1	Operational Wind Speed:	60 mph
Topographic Category:	1	Design Ice Thickness:	1.00 in
Crest Height:	0 ft	HMSL:	692.00 ft

SEISMIC PARAMETERS

Analysis Method:	Equivalent Lateral Force Method		
Site Class:	D - Stiff Soil	Period Based on Rayleigh Method (sec):	2.02
T_L (sec):	6	P:	1
S_s:	0.182	S₁:	0.055
F_a:	1.600	F_v:	2.400
S_{ds}:	0.194	S_{d1}:	0.088
		C_s:	0.030
		C_s Max:	0.030
		C_s Min:	0.030

LOAD CASES

1.2D + 1.0W Normal	120 mph wind with no ice
0.9D + 1.0W Normal	120 mph wind with no ice
1.2D + 1.0Di + 1.0Wi Normal	50 mph wind with 1" radial ice
1.2D + 1.0Ev + 1.0Eh Normal	Seismic
0.9D - 1.0Ev + 1.0Eh Normal	Seismic (Reduced DL)
1.0D + 1.0W Service Normal	60 mph Wind with No Ice

ASSET: 418609, Woodstock Relo CT
CUSTOMER: DISH WIRELESS L.L.C.

CODE: ANSI/TIA-222-H
ENG NO: 13733434_C3_03

SHAFT SECTION PROPERTIES

Sect Info	Length (ft)	Thick (in)	Fy (ksi)	Joint Type	Slip Joint len (in)	Weight (lb)	Bottom						Top						Taper (in/ft)
							Dia (in)	Elev (ft)	Area (in²)	Ix (in⁴)	W/t Ratio	D/t Ratio	Dia (in)	Elev (in)	Area (in²)	Ix (in⁴)	W/t Ratio	D/t Ratio	
1-18	54.00	0.5000	65		0.00	15,820	60.50	0.000	95.22	43,308.0	19.57	121.00	49.01	54.00	76.98	22,884.9	15.52	98.02	0.2128
2-18	53.88	0.4375	65	Slip	84.00	11,507	51.37	47.005	70.73	23,183.1	18.94	117.42	39.91	100.88	54.81	10,787.1	14.32	91.22	0.2128
3-18	53.88	0.3125	65	Slip	69.00	6,493	41.76	95.125	41.10	8,919.7	21.80	133.62	30.29	149.00	29.73	3,375.8	15.33	96.93	0.2128

Shaft Weight 33,820

DISCRETE APPURTENANCE PROPERTIES

Attach Elev (ft)	Description	Qty	Ka	Vert Ecc (ft)	No Ice			Ice		
					Weight (lb)	EPAA (sf)	Orientation Factor	Weight (lb)	EPAA (sf)	Orientation Factor
148.00	Generic Flat Platform with Han	1	1.00	0.000	2500.00	42.400	1.00	3684.75	56.387	1.00
148.00	VZW Unused Reserve (22199.55 s	1	0.75	0.000	2140.00	154.164	0.90	3134.26	225.790	0.90
147.00	Samsung B2/B66A RRH-BR049	3	0.75	0.000	84.40	1.875	0.50	126.90	2.476	0.50
147.00	Samsung B5/B13 RRH-BR04C	3	0.75	0.000	70.30	1.875	0.50	108.41	2.476	0.50
147.00	Andrew LNX-6514DS-A1M	3	0.75	2.000	38.80	8.173	0.83	156.02	10.051	0.83
147.00	Commscope SBNHH-1D65B (72.9")	6	0.75	2.000	40.60	8.200	0.83	158.11	10.084	0.83
147.00	Raycap RRFDC-3315-PF-48	2	0.75	0.000	26.90	2.512	0.67	79.97	3.206	0.67
147.00	Samsung MT6407-77A	3	0.75	0.000	81.60	4.709	0.61	149.51	5.721	0.61
138.00	Low Profile Platform w/ SiteP	1	1.00	0.000	2000.00	42.400	1.00	2922.04	61.947	1.00
138.00	CCI DMP65R-BU8D	3	0.80	0.000	95.70	17.871	0.63	320.62	20.310	0.63
138.00	Commscope NNHH-65C-R4	3	0.80	0.000	99.20	17.073	0.64	316.43	19.513	0.64
138.00	Raycap DC9-48-60-24-8C-EV	3	0.80	0.000	16.00	4.788	0.67	101.43	5.761	0.67
138.00	Ericsson RRUS 4449 B5, B12	3	0.80	0.000	71.00	1.969	0.50	113.65	2.586	0.50
138.00	Ericsson RRUS 4478 B14	3	0.80	0.000	59.90	1.842	0.50	96.49	2.436	0.50
138.00	Ericsson Radio 4415 B30	3	0.80	0.000	43.00	1.650	0.50	70.89	2.212	0.50
138.00	Ericsson RRUS 8843 B2, B66A	3	0.80	0.000	72.00	1.639	0.50	112.56	2.198	0.50
138.00	Andrew SBNH-1D6565C (60.8 lbs)	3	0.80	1.000	60.80	11.440	0.70	212.64	13.581	0.70
127.00	Fujitsu TA08025-B605	3	0.75	0.000	75.00	1.962	0.50	116.14	2.566	0.50
127.00	Fujitsu TA08025-B604	3	0.75	0.000	63.90	1.962	0.50	102.20	2.566	0.50
127.00	Raycap RDIDC-9181-PF-48	1	0.75	0.000	21.90	1.867	1.00	59.27	2.458	1.00
127.00	Commscope FFFV-65B-R2	3	0.75	0.000	70.80	12.271	0.64	235.84	14.112	0.64
126.00	Generic Flat Platform with Han	1	1.00	0.000	2500.00	42.400	1.00	3665.77	56.162	1.00
Totals	Num Loadings: 22	58			12,466.50			21,593.88		

LINEAR APPURTENANCE PROPERTIES

Load Case Azimuth (deg) : _

Elev From (ft)	Elev To (ft)	Qty	Description	Coax Dia (in)	Coax Wt (lb/ft)	Flat	Max Coax/ Row	Dist Between Rows(in)	Dist Between Cols(in)	Azimuth (deg)	Dist From Face (in)	Exposed	
												To Wind	Carrier
0.00	147.00	12	1 5/8" Coax	1.98	0.82	N	0	0	0	0	0	N	VERIZON WIREL
0.00	147.00	2	1 5/8" Hybriflex	1.98	1.3	N	0	0	0	0	0	N	VERIZON WIREL
0.00	141.00	6	0.78" (19.7mm) 8 AWG	0.78	0.59	N	0	0	0	0	0	N	AT&T MOBILITY
0.00	141.00	4	2" conduit	2.38	3.65	N	0	0	0	0	0	N	AT&T MOBILITY
0.00	141.00	3	0.26" (6.6mm) Cat 5e	0.26	0.04	N	0	0	0	0	0	N	AT&T MOBILITY
0.00	138.00	9	0.78" (19.7mm) 8 AWG	0.78	0.59	N	0	0	0	0	0	N	AT&T MOBILITY
0.00	138.00	6	0.39" (10mm) Fiber Tr	0.39	0.06	N	0	0	0	0	0	N	AT&T MOBILITY
0.00	138.00	3	3/8" (0.38"- 9.5mm) R	0.38	0.23	N	0	0	0	0	0	N	AT&T MOBILITY
0.00	138.00	3	2" conduit	2.38	3.65	N	0	0	0	0	0	N	AT&T MOBILITY
0.00	127.00	1	1.60" (40.6mm) Hybrid	1.6	2.34	N	0	0	0	0	0	N	DISH WIRELESS

ASSET: 418609, Woodstock Relo CT
 CUSTOMER: DISH WIRELESS L.L.C.

CODE: ANSI/TIA-222-H
 ENG NO: 13733434_C3_03

SEGMENT PROPERTIES

(Max Len: 5.ft)

Seg Top Elev (ft)	Description	Thick (in)	Flat Dia (in)	Area (in ²)	Ix (in ⁴)	W/t Ratio	D/t Ratio	F'y (ksi)	S (in ³)	Z (in ³)	Weight (lb)
0.00		0.5000	60.500	95.217	43,308.00	19.57	121.00	78.4	1409.9	0.0	0.0
5.00		0.5000	59.436	93.528	41,044.40	19.20	118.87	78.8	1360.2	0.0	1,605.6
10.00		0.5000	58.372	91.839	38,861.10	18.82	116.74	79.3	1311.3	0.0	1,576.9
15.00		0.5000	57.308	90.151	36,756.70	18.45	114.62	79.7	1263.3	0.0	1,548.2
20.00		0.5000	56.244	88.462	34,729.60	18.07	112.49	80.1	1216.2	0.0	1,519.4
25.00		0.5000	55.180	86.773	32,778.50	17.70	110.36	80.6	1170.0	0.0	1,490.7
30.00		0.5000	54.115	85.085	30,901.80	17.32	108.23	81	1124.7	0.0	1,462.0
35.00		0.5000	53.051	83.396	29,098.20	16.95	106.10	81.5	1080.3	0.0	1,433.3
40.00		0.5000	51.987	81.707	27,366.10	16.57	103.97	81.9	1036.8	0.0	1,404.5
45.00		0.5000	50.923	80.019	25,704.20	16.19	101.85	82.4	994.2	0.0	1,375.8
47.00	Bot - Section 2	0.5000	50.498	79.343	25,058.80	16.04	101.00	82.5	977.4	0.0	542.3
50.00		0.5000	49.859	78.330	24,111.00	15.82	99.72	82.6	952.5	0.0	1,522.3
54.00	Top - Section 1	0.4375	49.883	68.658	21,207.90	18.34	114.02	79.8	837.4	0.0	1,999.5
55.00		0.4375	49.670	68.363	20,935.20	18.26	113.53	79.9	830.2	0.0	233.1
60.00		0.4375	48.606	66.885	19,606.90	17.83	111.10	80.4	794.5	0.0	1,150.6
65.00		0.4375	47.542	65.408	18,336.00	17.40	108.67	80.9	759.6	0.0	1,125.4
70.00		0.4375	46.478	63.930	17,121.20	16.97	106.23	81.4	725.6	0.0	1,100.3
75.00		0.4375	45.414	62.453	15,961.30	16.54	103.80	81.9	692.3	0.0	1,075.1
80.00		0.4375	44.349	60.975	14,855.00	16.11	101.37	82.5	659.7	0.0	1,050.0
85.00		0.4375	43.285	59.498	13,801.00	15.68	98.94	82.6	628.0	0.0	1,024.9
90.00		0.4375	42.221	58.020	12,798.10	15.25	96.51	82.6	597.0	0.0	999.7
95.00		0.4375	41.157	56.542	11,845.00	14.82	94.07	82.6	566.9	0.0	974.6
95.13	Bot - Section 3	0.4375	41.131	56.505	11,821.80	14.81	94.01	82.6	566.1	0.0	24.0
100.00		0.4375	40.093	55.065	10,940.50	14.40	91.64	82.6	537.5	0.0	1,598.7
100.88	Top - Section 2	0.3125	40.532	39.891	8,152.70	21.11	129.70	76.6	396.2	0.0	282.6
105.00		0.3125	39.654	39.020	7,630.40	20.61	126.89	77.2	379.0	0.0	553.8
110.00		0.3125	38.590	37.965	7,027.90	20.01	123.49	77.9	358.7	0.0	654.9
115.00		0.3125	37.526	36.910	6,457.90	19.41	120.08	78.6	339.0	0.0	637.0
120.00		0.3125	36.462	35.854	5,919.60	18.81	116.68	79.3	319.8	0.0	619.0
125.00		0.3125	35.398	34.799	5,412.10	18.21	113.27	80	301.1	0.0	601.0
126.00		0.3125	35.185	34.588	5,314.20	18.09	112.59	80.1	297.5	0.0	118.1
127.00		0.3125	34.972	34.377	5,217.50	17.97	111.91	80.3	293.8	0.0	117.3
130.00		0.3125	34.334	33.743	4,934.40	17.61	109.87	80.7	283.1	0.0	347.7
135.00		0.3125	33.269	32.688	4,485.80	17.01	106.46	81.4	265.6	0.0	565.1
138.00		0.3125	32.631	32.055	4,230.10	16.65	104.42	81.8	255.3	0.0	330.5
140.00		0.3125	32.205	31.633	4,065.10	16.41	103.06	82.1	248.6	0.0	216.7
145.00		0.3125	31.141	30.577	3,671.70	15.81	99.65	82.6	232.2	0.0	529.2
147.00		0.3125	30.716	30.155	3,521.70	15.57	98.29	82.6	225.8	0.0	206.7
148.00		0.3125	30.503	29.944	3,448.20	15.45	97.61	82.6	222.7	0.0	102.3
149.00		0.3125	30.290	29.733	3,375.80	15.33	96.93	82.6	219.5	0.0	101.5

Totals: 33,820.3

ASSET: 418609, Woodstock Relo CT
CUSTOMER: DISH WIRELESS L.L.C.

CODE: ANSI/TIA-222-H
ENG NO: 13733434_C3_03

Load Case: 1.2D + 1.0W Normal	120 mph wind with no ice	21 Iterations
Gust Response Factor: 1.10		
Dead load Factor: 1.20		
Wind Load Factor: 1.00		

CALCULATED FORCES

Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	Phi Pn (kips)	Phi Vn (kips)	Phi Tn (ft-kips)	Phi Mn (ft-kips)	Total Deflect (in)	Rotation (deg)	Ratio
0.00	-64.00	-37.97	0.00	-4,326.8	0.00	4,326.75	6,716.78	1,671.05	9,056.15	8,288.22	0	0	0.532
5.00	-61.68	-37.53	0.00	-4,136.9	0.00	4,136.91	6,634.81	1,641.41	8,737.82	8,040.68	0.07	-0.14	0.524
10.00	-59.40	-37.09	0.00	-3,949.3	0.00	3,949.26	6,551.49	1,611.78	8,425.18	7,795.15	0.3	-0.28	0.516
15.00	-57.15	-36.65	0.00	-3,763.8	0.00	3,763.81	6,466.84	1,582.14	8,118.24	7,551.74	0.66	-0.42	0.508
20.00	-54.94	-36.18	0.00	-3,580.6	0.00	3,580.58	6,380.85	1,552.51	7,817.00	7,310.53	1.18	-0.56	0.499
25.00	-52.77	-35.68	0.00	-3,399.7	0.00	3,399.69	6,293.51	1,522.87	7,521.45	7,071.60	1.85	-0.71	0.490
30.00	-50.64	-35.16	0.00	-3,221.3	0.00	3,221.29	6,204.83	1,493.24	7,231.59	6,835.05	2.66	-0.85	0.480
35.00	-48.54	-34.63	0.00	-3,045.5	0.00	3,045.47	6,114.81	1,463.60	6,947.43	6,600.97	3.63	-0.99	0.470
40.00	-46.47	-34.08	0.00	-2,872.3	0.00	2,872.32	6,023.45	1,433.96	6,668.97	6,369.44	4.75	-1.14	0.459
45.00	-44.47	-33.68	0.00	-2,701.9	0.00	2,701.91	5,930.75	1,404.33	6,396.20	6,140.56	6.02	-1.28	0.448
47.00	-43.67	-33.40	0.00	-2,634.6	0.00	2,634.56	5,893.29	1,392.47	6,288.69	6,049.76	6.57	-1.34	0.443
50.00	-41.61	-32.97	0.00	-2,534.4	0.00	2,534.37	5,819.53	1,374.69	6,129.13	5,896.99	7.44	-1.43	0.437
54.00	-38.94	-32.63	0.00	-2,402.5	0.00	2,402.49	4,932.79	1,204.96	5,381.53	5,013.55	8.69	-1.55	0.488
55.00	-38.55	-32.30	0.00	-2,369.9	0.00	2,369.86	4,917.77	1,199.77	5,335.31	4,976.57	9.02	-1.58	0.485
60.00	-36.81	-31.71	0.00	-2,208.4	0.00	2,208.36	4,841.84	1,173.84	5,107.20	4,792.90	10.75	-1.73	0.469
65.00	-35.09	-31.11	0.00	-2,049.8	0.00	2,049.82	4,764.57	1,147.91	4,884.08	4,611.29	12.65	-1.89	0.453
70.00	-33.41	-30.52	0.00	-1,894.2	0.00	1,894.25	4,685.96	1,121.98	4,665.94	4,431.81	14.71	-2.04	0.435
75.00	-31.76	-29.91	0.00	-1,741.7	0.00	1,741.68	4,606.01	1,096.04	4,452.78	4,254.57	16.92	-2.19	0.417
80.00	-30.15	-29.31	0.00	-1,592.1	0.00	1,592.12	4,524.71	1,070.11	4,244.60	4,079.64	19.3	-2.34	0.398
85.00	-28.58	-28.70	0.00	-1,445.6	0.00	1,445.59	4,420.37	1,044.18	4,041.41	3,888.03	21.82	-2.48	0.379
90.00	-27.03	-28.09	0.00	-1,302.1	0.00	1,302.09	4,310.59	1,018.25	3,843.20	3,696.36	24.5	-2.63	0.359
95.00	-25.55	-27.75	0.00	-1,161.6	0.00	1,161.62	4,200.82	992.32	3,649.98	3,509.54	27.33	-2.76	0.338
95.13	-25.49	-27.47	0.00	-1,158.2	0.00	1,158.15	4,198.07	991.67	3,645.21	3,504.93	27.4	-2.77	0.337
100.00	-23.26	-27.05	0.00	-1,024.2	0.00	1,024.22	4,091.04	966.39	3,461.74	3,327.57	30.29	-2.89	0.314
100.88	-22.86	-26.76	0.00	-1,000.6	0.00	1,000.55	2,749.22	700.09	2,543.23	2,275.29	30.82	-2.92	0.450
105.00	-21.91	-26.23	0.00	-890.2	0.00	890.17	2,709.67	684.81	2,433.43	2,193.23	33.39	-3.02	0.415
110.00	-20.79	-25.64	0.00	-759.0	0.00	759.04	2,660.51	666.29	2,303.59	2,094.74	36.63	-3.17	0.372
115.00	-19.70	-25.06	0.00	-630.8	0.00	630.83	2,610.00	647.76	2,177.31	1,997.38	40.04	-3.31	0.325
120.00	-18.64	-24.48	0.00	-505.5	0.00	505.52	2,558.16	629.24	2,054.58	1,901.26	43.57	-3.44	0.275
125.00	-17.61	-24.11	0.00	-383.1	0.00	383.11	2,504.97	610.72	1,935.42	1,806.46	47.24	-3.55	0.221
126.00	-14.55	-21.70	0.00	-359.0	0.00	359.00	2,494.18	607.02	1,912.02	1,787.67	47.98	-3.57	0.208
127.00	-13.64	-20.26	0.00	-337.3	0.00	337.30	2,483.32	603.31	1,888.75	1,768.93	48.73	-3.58	0.197
130.00	-13.06	-19.81	0.00	-276.5	0.00	276.53	2,450.45	592.20	1,819.82	1,713.07	51	-3.63	0.168
135.00	-12.11	-19.34	0.00	-177.5	0.00	177.49	2,394.58	573.67	1,707.78	1,621.18	54.84	-3.7	0.116
138.00	-7.73	-12.11	0.00	-118.5	0.00	118.49	2,360.41	562.56	1,642.26	1,566.80	57.17	-3.73	0.079
140.00	-7.42	-11.74	0.00	-94.3	0.00	94.27	2,337.37	555.15	1,599.29	1,530.87	58.74	-3.74	0.065
145.00	-6.71	-11.35	0.00	-35.6	0.00	35.55	2,271.73	536.63	1,494.37	1,437.76	62.67	-3.77	0.028
147.00	-5.29	-8.05	0.00	-8.1	0.00	8.10	2,240.37	529.22	1,453.39	1,398.14	64.25	-3.77	0.008
148.00	-0.12	-0.05	0.00	-0.0	0.00	0.05	2,224.69	525.52	1,433.12	1,378.53	65.04	-3.77	0.000
149.00	0.00	-0.04	0.00	0.0	0.00	0.00	2,209.00	521.81	1,412.99	1,359.07	65.83	-3.77	0.000

ASSET: 418609, Woodstock Relo CT
CUSTOMER: DISH WIRELESS L.L.C.

CODE: ANSI/TIA-222-H
ENG NO: 13733434_C3_03

Load Case: 0.9D + 1.0W Normal	120 mph wind with no ice	21 Iterations
Gust Response Factor: 1.10		
Dead load Factor: 0.90		
Wind Load Factor: 1.00		

CALCULATED FORCES

Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	Phi Pn (kips)	Phi Vn (kips)	Phi Tn (ft-kips)	Phi Mn (ft-kips)	Total Deflect (in)	Rotation (deg)	Ratio
0.00	-47.99	-37.95	0.00	-4,290.0	0.00	4,289.99	6,716.78	1,671.05	9,056.15	8,288.22	0	0	0.525
5.00	-46.23	-37.47	0.00	-4,100.2	0.00	4,100.25	6,634.81	1,641.41	8,737.82	8,040.68	0.07	-0.14	0.517
10.00	-44.50	-37.00	0.00	-3,912.9	0.00	3,912.89	6,551.49	1,611.78	8,425.18	7,795.15	0.29	-0.28	0.509
15.00	-42.79	-36.52	0.00	-3,727.9	0.00	3,727.90	6,466.84	1,582.14	8,118.24	7,551.74	0.66	-0.42	0.501
20.00	-41.11	-36.02	0.00	-3,545.3	0.00	3,545.31	6,380.85	1,552.51	7,817.00	7,310.53	1.17	-0.56	0.492
25.00	-39.46	-35.50	0.00	-3,365.2	0.00	3,365.21	6,293.51	1,522.87	7,521.45	7,071.60	1.83	-0.7	0.483
30.00	-37.84	-34.95	0.00	-3,187.7	0.00	3,187.73	6,204.83	1,493.24	7,231.59	6,835.05	2.64	-0.84	0.473
35.00	-36.25	-34.40	0.00	-3,013.0	0.00	3,012.97	6,114.81	1,463.60	6,947.43	6,600.97	3.6	-0.98	0.463
40.00	-34.69	-33.83	0.00	-2,841.0	0.00	2,841.00	6,023.45	1,433.96	6,668.97	6,369.44	4.7	-1.13	0.452
45.00	-33.17	-33.41	0.00	-2,671.9	0.00	2,671.88	5,930.75	1,404.33	6,396.20	6,140.56	5.96	-1.27	0.441
47.00	-32.56	-33.12	0.00	-2,605.1	0.00	2,605.06	5,893.29	1,392.47	6,288.69	6,049.76	6.51	-1.33	0.437
50.00	-31.01	-32.69	0.00	-2,505.7	0.00	2,505.70	5,819.53	1,374.69	6,129.13	5,896.99	7.37	-1.42	0.431
54.00	-29.00	-32.35	0.00	-2,375.0	0.00	2,374.95	4,932.79	1,204.96	5,381.53	5,013.55	8.61	-1.53	0.480
55.00	-28.70	-32.01	0.00	-2,342.6	0.00	2,342.60	4,917.77	1,199.77	5,335.31	4,976.57	8.93	-1.56	0.477
60.00	-27.37	-31.40	0.00	-2,182.6	0.00	2,182.58	4,841.84	1,173.84	5,107.20	4,792.90	10.65	-1.71	0.462
65.00	-26.07	-30.80	0.00	-2,025.6	0.00	2,025.57	4,764.57	1,147.91	4,884.08	4,611.29	12.52	-1.87	0.445
70.00	-24.80	-30.19	0.00	-1,871.6	0.00	1,871.59	4,685.96	1,121.98	4,665.94	4,431.81	14.56	-2.02	0.428
75.00	-23.55	-29.58	0.00	-1,720.7	0.00	1,720.66	4,606.01	1,096.04	4,452.78	4,254.57	16.75	-2.17	0.410
80.00	-22.33	-28.97	0.00	-1,572.8	0.00	1,572.78	4,524.71	1,070.11	4,244.60	4,079.64	19.1	-2.31	0.391
85.00	-21.14	-28.36	0.00	-1,428.0	0.00	1,427.95	4,420.37	1,044.18	4,041.41	3,888.03	21.6	-2.46	0.373
90.00	-19.97	-27.75	0.00	-1,286.2	0.00	1,286.16	4,310.59	1,018.25	3,843.20	3,696.36	24.25	-2.6	0.353
95.00	-18.85	-27.41	0.00	-1,147.4	0.00	1,147.41	4,200.82	992.32	3,649.98	3,509.54	27.04	-2.73	0.332
95.13	-18.81	-27.13	0.00	-1,144.0	0.00	1,143.99	4,198.07	991.67	3,645.21	3,504.93	27.12	-2.74	0.332
100.00	-17.13	-26.73	0.00	-1,011.7	0.00	1,011.72	4,091.04	966.39	3,461.74	3,327.57	29.98	-2.86	0.309
100.88	-16.83	-26.44	0.00	-988.3	0.00	988.33	2,749.22	700.09	2,543.23	2,275.29	30.5	-2.89	0.442
105.00	-16.11	-25.90	0.00	-879.3	0.00	879.29	2,709.67	684.81	2,433.43	2,193.23	33.04	-2.99	0.408
110.00	-15.26	-25.32	0.00	-749.8	0.00	749.78	2,660.51	666.29	2,303.59	2,094.74	36.25	-3.14	0.365
115.00	-14.44	-24.74	0.00	-623.2	0.00	623.19	2,610.00	647.76	2,177.31	1,997.38	39.61	-3.28	0.319
120.00	-13.64	-24.17	0.00	-499.5	0.00	499.48	2,558.16	629.24	2,054.58	1,901.26	43.11	-3.4	0.270
125.00	-12.87	-23.81	0.00	-378.6	0.00	378.65	2,504.97	610.72	1,935.42	1,806.46	46.73	-3.51	0.216
126.00	-10.60	-21.44	0.00	-354.8	0.00	354.85	2,494.18	607.02	1,912.02	1,787.67	47.47	-3.53	0.204
127.00	-9.94	-20.01	0.00	-333.4	0.00	333.40	2,483.32	603.31	1,888.75	1,768.93	48.21	-3.54	0.194
130.00	-9.51	-19.57	0.00	-273.4	0.00	273.36	2,450.45	592.20	1,819.82	1,713.07	50.45	-3.59	0.165
135.00	-8.79	-19.12	0.00	-175.5	0.00	175.50	2,394.58	573.67	1,707.78	1,621.18	54.25	-3.66	0.113
138.00	-5.62	-11.97	0.00	-117.2	0.00	117.17	2,360.41	562.56	1,642.26	1,566.80	56.56	-3.69	0.078
140.00	-5.39	-11.61	0.00	-93.2	0.00	93.22	2,337.37	555.15	1,599.29	1,530.87	58.11	-3.7	0.064
145.00	-4.86	-11.22	0.00	-35.2	0.00	35.20	2,271.73	536.63	1,494.37	1,437.76	61.99	-3.72	0.027
147.00	-3.85	-7.96	0.00	-8.0	0.00	8.00	2,240.37	529.22	1,453.39	1,398.14	63.55	-3.73	0.008
148.00	-0.09	-0.05	0.00	-0.0	0.00	0.05	2,224.69	525.52	1,433.12	1,378.53	64.33	-3.73	0.000
149.00	0.00	-0.04	0.00	0.0	0.00	0.00	2,209.00	521.81	1,412.99	1,359.07	65.11	-3.73	0.000

ASSET: 418609, Woodstock Relo CT
CUSTOMER: DISH WIRELESS L.L.C.

CODE: ANSI/TIA-222-H
ENG NO: 13733434_C3_03

Load Case: 1.2D + 1.0Di + 1.0Wi Normal				50 mph wind with 1" radial ice				21 Iterations			
Gust Response Factor: 1.10		Ice Dead Load Factor 1.00									
Dead load Factor: 1.20								Ice Importance Factor		1.00	
Wind Load Factor: 1.00											

CALCULATED FORCES

Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	Phi Pn (kips)	Phi Vn (kips)	Phi Tn (ft-kips)	Phi Mn (ft-kips)	Total Deflect (in)	Rotation (deg)	Ratio
0.00	-80.16	-9.93	0.00	-1,102.6	0.00	1,102.56	6,716.78	1,671.05	9,056.15	8,288.22	0	0	0.145
5.00	-77.63	-9.81	0.00	-1,052.9	0.00	1,052.91	6,634.81	1,641.41	8,737.82	8,040.68	0.02	-0.04	0.143
10.00	-75.11	-9.68	0.00	-1,003.9	0.00	1,003.89	6,551.49	1,611.78	8,425.18	7,795.15	0.08	-0.07	0.140
15.00	-72.61	-9.55	0.00	-955.5	0.00	955.49	6,466.84	1,582.14	8,118.24	7,551.74	0.17	-0.11	0.138
20.00	-70.14	-9.42	0.00	-907.7	0.00	907.73	6,380.85	1,552.51	7,817.00	7,310.53	0.3	-0.14	0.135
25.00	-67.71	-9.28	0.00	-860.6	0.00	860.64	6,293.51	1,522.87	7,521.45	7,071.60	0.47	-0.18	0.132
30.00	-65.31	-9.13	0.00	-814.3	0.00	814.26	6,204.83	1,493.24	7,231.59	6,835.05	0.68	-0.22	0.130
35.00	-62.94	-8.97	0.00	-768.6	0.00	768.62	6,114.81	1,463.60	6,947.43	6,600.97	0.92	-0.25	0.127
40.00	-60.62	-8.81	0.00	-723.8	0.00	723.76	6,023.45	1,433.96	6,668.97	6,369.44	1.21	-0.29	0.124
45.00	-58.33	-8.70	0.00	-679.7	0.00	679.69	5,930.75	1,404.33	6,396.20	6,140.56	1.53	-0.32	0.121
47.00	-57.42	-8.61	0.00	-662.3	0.00	662.30	5,893.29	1,392.47	6,288.69	6,049.76	1.67	-0.34	0.119
50.00	-55.21	-8.49	0.00	-636.5	0.00	636.46	5,819.53	1,374.69	6,129.13	5,896.99	1.89	-0.36	0.117
54.00	-52.30	-8.39	0.00	-602.5	0.00	602.49	4,932.79	1,204.96	5,381.53	5,013.55	2.2	-0.39	0.131
55.00	-51.89	-8.30	0.00	-594.1	0.00	594.10	4,917.77	1,199.77	5,335.31	4,976.57	2.29	-0.4	0.130
60.00	-49.87	-8.13	0.00	-552.6	0.00	552.61	4,841.84	1,173.84	5,107.20	4,792.90	2.73	-0.44	0.126
65.00	-47.89	-7.95	0.00	-512.0	0.00	511.98	4,764.57	1,147.91	4,884.08	4,611.29	3.2	-0.48	0.121
70.00	-45.94	-7.78	0.00	-472.2	0.00	472.22	4,685.96	1,121.98	4,665.94	4,431.81	3.72	-0.51	0.116
75.00	-44.03	-7.60	0.00	-433.3	0.00	433.33	4,606.01	1,096.04	4,452.78	4,254.57	4.28	-0.55	0.111
80.00	-42.16	-7.42	0.00	-395.3	0.00	395.33	4,524.71	1,070.11	4,244.60	4,079.64	4.88	-0.59	0.106
85.00	-40.32	-7.24	0.00	-358.2	0.00	358.22	4,420.37	1,044.18	4,041.41	3,888.03	5.52	-0.62	0.101
90.00	-38.52	-7.07	0.00	-322.0	0.00	322.00	4,310.59	1,018.25	3,843.20	3,696.36	6.19	-0.66	0.096
95.00	-36.75	-6.96	0.00	-286.7	0.00	286.67	4,200.82	992.32	3,649.98	3,509.54	6.9	-0.69	0.090
95.13	-36.71	-6.88	0.00	-285.8	0.00	285.80	4,198.07	991.67	3,645.21	3,504.93	6.92	-0.69	0.090
100.00	-34.21	-6.76	0.00	-252.3	0.00	252.26	4,091.04	966.39	3,461.74	3,327.57	7.64	-0.73	0.084
100.88	-33.76	-6.67	0.00	-246.3	0.00	246.34	2,749.22	700.09	2,543.23	2,275.29	7.78	-0.73	0.121
105.00	-32.61	-6.51	0.00	-218.8	0.00	218.82	2,709.67	684.81	2,433.43	2,193.23	8.42	-0.76	0.112
110.00	-31.24	-6.34	0.00	-186.2	0.00	186.25	2,660.51	666.29	2,303.59	2,094.74	9.24	-0.79	0.101
115.00	-29.90	-6.17	0.00	-154.6	0.00	154.55	2,610.00	647.76	2,177.31	1,997.38	10.09	-0.83	0.089
120.00	-28.59	-5.99	0.00	-123.7	0.00	123.71	2,558.16	629.24	2,054.58	1,901.26	10.97	-0.86	0.076
125.00	-27.30	-5.88	0.00	-93.7	0.00	93.74	2,504.97	610.72	1,935.42	1,806.46	11.89	-0.89	0.063
126.00	-23.15	-5.30	0.00	-87.9	0.00	87.86	2,494.18	607.02	1,912.02	1,787.67	12.08	-0.89	0.059
127.00	-21.52	-4.97	0.00	-82.6	0.00	82.56	2,483.32	603.31	1,888.75	1,768.93	12.26	-0.9	0.055
130.00	-20.77	-4.83	0.00	-67.7	0.00	67.66	2,450.45	592.20	1,819.82	1,713.07	12.83	-0.91	0.048
135.00	-19.56	-4.69	0.00	-43.5	0.00	43.49	2,394.58	573.67	1,707.78	1,621.18	13.79	-0.92	0.035
138.00	-11.94	-3.02	0.00	-29.2	0.00	29.22	2,360.41	562.56	1,642.26	1,566.80	14.37	-0.93	0.024
140.00	-11.51	-2.91	0.00	-23.2	0.00	23.18	2,337.37	555.15	1,599.29	1,530.87	14.76	-0.93	0.020
145.00	-10.55	-2.79	0.00	-8.6	0.00	8.64	2,271.73	536.63	1,494.37	1,437.76	15.75	-0.94	0.011
147.00	-7.58	-2.04	0.00	-2.0	0.00	2.05	2,240.37	529.22	1,453.39	1,398.14	16.14	-0.94	0.005
148.00	-0.17	-0.02	0.00	-0.0	0.00	0.02	2,224.69	525.52	1,433.12	1,378.53	16.34	-0.94	0.000
149.00	0.00	-0.01	0.00	0.0	0.00	0.00	2,209.00	521.81	1,412.99	1,359.07	16.53	-0.94	0.000

ASSET: 418609, Woodstock Relo CT
CUSTOMER: DISH WIRELESS L.L.C.

CODE: ANSI/TIA-222-H
ENG NO: 13733434_C3_03

Load Case: 1.0D + 1.0W Service Normal	60 mph Wind with No Ice	20 Iterations
Gust Response Factor: 1.10		
Dead load Factor: 1.00		
Wind Load Factor: 1.00		

CALCULATED FORCES

Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	Phi Pn (kips)	Phi Vn (kips)	Phi Tn (ft-kips)	Phi Mn (ft-kips)	Total Deflect (in)	Rotation (deg)	Ratio
0.00	-53.37	-8.49	0.00	-962.9	0.00	962.88	6,716.78	1,671.05	9,056.15	8,288.22	0	0	0.124
5.00	-51.51	-8.39	0.00	-920.4	0.00	920.43	6,634.81	1,641.41	8,737.82	8,040.68	0.02	-0.03	0.122
10.00	-49.68	-8.28	0.00	-878.5	0.00	878.50	6,551.49	1,611.78	8,425.18	7,795.15	0.07	-0.06	0.120
15.00	-47.87	-8.18	0.00	-837.1	0.00	837.09	6,466.84	1,582.14	8,118.24	7,551.74	0.15	-0.09	0.118
20.00	-46.10	-8.07	0.00	-796.2	0.00	796.21	6,380.85	1,552.51	7,817.00	7,310.53	0.26	-0.13	0.116
25.00	-44.35	-7.95	0.00	-755.9	0.00	755.86	6,293.51	1,522.87	7,521.45	7,071.60	0.41	-0.16	0.114
30.00	-42.63	-7.83	0.00	-716.1	0.00	716.10	6,204.83	1,493.24	7,231.59	6,835.05	0.59	-0.19	0.112
35.00	-40.95	-7.71	0.00	-676.9	0.00	676.93	6,114.81	1,463.60	6,947.43	6,600.97	0.81	-0.22	0.109
40.00	-39.29	-7.59	0.00	-638.4	0.00	638.37	6,023.45	1,433.96	6,668.97	6,369.44	1.06	-0.25	0.107
45.00	-37.66	-7.49	0.00	-600.4	0.00	600.44	5,930.75	1,404.33	6,396.20	6,140.56	1.34	-0.29	0.104
47.00	-37.01	-7.43	0.00	-585.4	0.00	585.45	5,893.29	1,392.47	6,288.69	6,049.76	1.46	-0.3	0.103
50.00	-35.34	-7.33	0.00	-563.2	0.00	563.16	5,819.53	1,374.69	6,129.13	5,896.99	1.66	-0.32	0.102
54.00	-33.13	-7.26	0.00	-533.8	0.00	533.82	4,932.79	1,204.96	5,381.53	5,013.55	1.93	-0.34	0.113
55.00	-32.85	-7.18	0.00	-526.6	0.00	526.57	4,917.77	1,199.77	5,335.31	4,976.57	2.01	-0.35	0.113
60.00	-31.44	-7.05	0.00	-490.6	0.00	490.65	4,841.84	1,173.84	5,107.20	4,792.90	2.39	-0.38	0.109
65.00	-30.06	-6.92	0.00	-455.4	0.00	455.40	4,764.57	1,147.91	4,884.08	4,611.29	2.81	-0.42	0.105
70.00	-28.71	-6.78	0.00	-420.8	0.00	420.83	4,685.96	1,121.98	4,665.94	4,431.81	3.27	-0.45	0.101
75.00	-27.38	-6.64	0.00	-386.9	0.00	386.93	4,606.01	1,096.04	4,452.78	4,254.57	3.76	-0.49	0.097
80.00	-26.07	-6.51	0.00	-353.7	0.00	353.70	4,524.71	1,070.11	4,244.60	4,079.64	4.29	-0.52	0.092
85.00	-24.79	-6.37	0.00	-321.2	0.00	321.16	4,420.37	1,044.18	4,041.41	3,888.03	4.85	-0.55	0.088
90.00	-23.54	-6.24	0.00	-289.3	0.00	289.29	4,310.59	1,018.25	3,843.20	3,696.36	5.45	-0.58	0.084
95.00	-22.31	-6.16	0.00	-258.1	0.00	258.10	4,200.82	992.32	3,649.98	3,509.54	6.08	-0.61	0.079
95.13	-22.28	-6.10	0.00	-257.3	0.00	257.33	4,198.07	991.67	3,645.21	3,504.93	6.09	-0.61	0.079
100.00	-20.44	-6.01	0.00	-227.6	0.00	227.59	4,091.04	966.39	3,461.74	3,327.57	6.74	-0.64	0.073
100.88	-20.11	-5.94	0.00	-222.3	0.00	222.33	2,749.22	700.09	2,543.23	2,275.29	6.85	-0.65	0.105
105.00	-19.35	-5.83	0.00	-197.8	0.00	197.81	2,709.67	684.81	2,433.43	2,193.23	7.42	-0.67	0.097
110.00	-18.44	-5.70	0.00	-168.7	0.00	168.68	2,660.51	666.29	2,303.59	2,094.74	8.15	-0.71	0.088
115.00	-17.55	-5.57	0.00	-140.2	0.00	140.21	2,610.00	647.76	2,177.31	1,997.38	8.9	-0.74	0.077
120.00	-16.68	-5.44	0.00	-112.4	0.00	112.37	2,558.16	629.24	2,054.58	1,901.26	9.69	-0.76	0.066
125.00	-15.82	-5.36	0.00	-85.2	0.00	85.18	2,504.97	610.72	1,935.42	1,806.46	10.5	-0.79	0.054
126.00	-13.16	-4.82	0.00	-79.8	0.00	79.83	2,494.18	607.02	1,912.02	1,787.67	10.67	-0.79	0.050
127.00	-12.35	-4.50	0.00	-75.0	0.00	75.00	2,483.32	603.31	1,888.75	1,768.93	10.84	-0.8	0.047
130.00	-11.86	-4.40	0.00	-61.5	0.00	61.50	2,450.45	592.20	1,819.82	1,713.07	11.34	-0.81	0.041
135.00	-11.05	-4.30	0.00	-39.5	0.00	39.48	2,394.58	573.67	1,707.78	1,621.18	12.19	-0.82	0.029
138.00	-7.05	-2.69	0.00	-26.4	0.00	26.36	2,360.41	562.56	1,642.26	1,566.80	12.71	-0.83	0.020
140.00	-6.77	-2.61	0.00	-21.0	0.00	20.97	2,337.37	555.15	1,599.29	1,530.87	13.06	-0.83	0.017
145.00	-6.16	-2.52	0.00	-7.9	0.00	7.91	2,271.73	536.63	1,494.37	1,437.76	13.94	-0.84	0.008
147.00	-4.82	-1.79	0.00	-1.8	0.00	1.80	2,240.37	529.22	1,453.39	1,398.14	14.29	-0.84	0.003
148.00	-0.10	-0.01	0.00	-0.0	0.00	0.01	2,224.69	525.52	1,433.12	1,378.53	14.46	-0.84	0.000
149.00	0.00	-0.01	0.00	0.0	0.00	0.00	2,209.00	521.81	1,412.99	1,359.07	14.64	-0.84	0.000

EQUIVALENT LATERAL FORCES METHOD ANALYSIS

(Based on ASCE7-16 Chapters 11, 12 and 15)

Spectral Response Acceleration for Short Period (S_S):	0.182
Spectral Response Acceleration at 1.0 Second Period (S_1):	0.055
Long-Period Transition Period (T_L – Seconds):	6
Importance Factor (I_a):	1.000
Site Coefficient F_a :	1.600
Site Coefficient F_v :	2.400
Response Modification Coefficient (R):	1.500
Design Spectral Response Acceleration at Short Period (S_{ds}):	0.194
Design Spectral Response Acceleration at 1.0 Second Period (S_{d1}):	0.088
Seismic Response Coefficient (C_s):	0.030
Upper Limit C_s :	0.030
Lower Limit C_s :	0.030
Period based on Rayleigh Method (sec):	2.020
Redundancy Factor (p):	1.000
Seismic Force Distribution Exponent (k):	1.760
Total Unfactored Dead Load:	53.380 k
Seismic Base Shear (E):	1.600 k

1.2D + 1.0Ev + 1.0Eh Normal

Seismic

Segment	Height Above Base (ft)	Weight (lb)	W_z (lb-ft)	C_{vx}	Horizontal Force (lb)	Vertical Force (lb)
39	148.5	102	677	0.004	7	126
38	147.5	102	674	0.004	7	127
37	146	232	1,499	0.010	16	287
36	142.5	610	3,783	0.025	41	755
35	139	278	1,652	0.011	18	345
34	136.5	474	2,729	0.018	29	588
33	132.5	805	4,395	0.029	47	997
32	128.5	492	2,543	0.017	27	609
31	126.5	168	844	0.006	9	208
30	125.5	168	835	0.006	9	209
29	122.5	853	4,054	0.027	43	1,056
28	117.5	871	3,847	0.026	41	1,079
27	112.5	889	3,637	0.024	39	1,101
26	107.5	907	3,425	0.023	37	1,123
25	102.9375	762	2,665	0.018	29	943
24	100.4375	327	1,095	0.007	12	405
23	97.5625	1,844	5,872	0.039	63	2,285
22	95.0625	30	92	0.001	1	38
21	92.5	1,226	3,555	0.024	38	1,519
20	87.5	1,251	3,290	0.022	35	1,550
19	82.5	1,277	3,025	0.020	32	1,581
18	77.5	1,302	2,763	0.018	30	1,613
17	72.5	1,327	2,505	0.017	27	1,644
16	67.5	1,352	2,250	0.015	24	1,675
15	62.5	1,377	2,002	0.013	21	1,706
14	57.5	1,402	1,760	0.012	19	1,737
13	54.5	283	324	0.002	3	351
12	52	2,201	2,314	0.016	25	2,727
11	48.5	1,673	1,556	0.010	17	2,073
10	46	643	545	0.004	6	797
9	42.5	1,628	1,200	0.008	13	2,016
8	37.5	1,656	979	0.007	10	2,052
7	32.5	1,685	774	0.005	8	2,087
6	27.5	1,714	587	0.004	6	2,123

ASSET: 418609, Woodstock Relo CT
 CUSTOMER: DISH WIRELESS L.L.C.

CODE: ANSI/TIA-222-H
 ENG NO: 13733434_C3_03

Segment	Height Above Base (ft)	Weight (lb)	W _z (lb-ft)	C _{vx}	Horizontal Force (lb)	Vertical Force (lb)
5	22.5	1,742	419	0.003	4	2,159
4	17.5	1,771	274	0.002	3	2,194
3	12.5	1,800	154	0.001	2	2,230
2	7.5	1,829	64	0.000	1	2,265
1	2.5	1,857	9	0.000	0	2,301
Generic Flat Platform with Handrails	148	2,500	16,581	0.111	178	3,097
Generic Flat Platform with Handrails	126	2,500	12,489	0.084	134	3,097
VZW Unused Reserve (22199.55 sqin)	148	2,140	14,193	0.095	152	2,651
Samsung B5/B13 RRH-BR04C	147	211	1,382	0.009	15	261
Samsung B2/B66A RRH-BR049	147	253	1,659	0.011	18	314
Raycap RRFDC-3315-PF-48	147	54	353	0.002	4	67
Samsung MT6407-77A	147	245	1,604	0.011	17	303
Andrew LNX-6514DS-A1M	147	116	763	0.005	8	144
Commscope SBNHH-1D65B (72.9")	147	244	1,596	0.011	17	302
Ericsson RRUS 8843 B2, B66A	138	216	1,267	0.008	14	268
Ericsson Radio 4415 B30	138	129	756	0.005	8	160
Ericsson RRUS 4478 B14	138	180	1,054	0.007	11	223
Ericsson RRUS 4449 B5, B12	138	213	1,249	0.008	13	264
Raycap DC9-48-60-24-8C-EV	138	48	281	0.002	3	59
Andrew SBNH-1D6565C (60.8 lbs)	138	182	1,070	0.007	11	226
Commscope NNHH-65C-R4	138	298	1,745	0.012	19	369
CCI DMP65R-BU8D	138	287	1,683	0.011	18	356
Low Profile Platform w/ SitePro1 HRK12-3HD	138	2,000	11,727	0.078	126	2,478
Reinforcmenet Kit						
Raycap RDIDC-9181-PF-48	127	22	111	0.001	1	27
Fujitsu TA08025-B604	127	192	971	0.006	10	237
Fujitsu TA08025-B605	127	225	1,140	0.008	12	279
Commscope FFVV-65B-R2	127	212	1,076	0.007	12	263
		53,376	149,417	1.000	1,601	66,124

0.9D - 1.0Ev + 1.0Eh Normal Seismic (Reduced DL)

Segment	Height Above Base (ft)	Weight (lb)	W _z (lb-ft)	C _{vx}	Horizontal Force (lb)	Vertical Force (lb)
39	148.5	102	677	0.004	7	87
38	147.5	102	674	0.004	7	88
37	146	232	1,499	0.010	16	199
36	142.5	610	3,783	0.025	41	525
35	139	278	1,652	0.011	18	240
34	136.5	474	2,729	0.018	29	409
33	132.5	805	4,395	0.029	47	693
32	128.5	492	2,543	0.017	27	423
31	126.5	168	844	0.006	9	144
30	125.5	168	835	0.006	9	145
29	122.5	853	4,054	0.027	43	734
28	117.5	871	3,847	0.026	41	750
27	112.5	889	3,637	0.024	39	765
26	107.5	907	3,425	0.023	37	781
25	102.9375	762	2,665	0.018	29	656
24	100.4375	327	1,095	0.007	12	281
23	97.5625	1,844	5,872	0.039	63	1,588
22	95.0625	30	92	0.001	1	26
21	92.5	1,226	3,555	0.024	38	1,056
20	87.5	1,251	3,290	0.022	35	1,078
19	82.5	1,277	3,025	0.020	32	1,099
18	77.5	1,302	2,763	0.018	30	1,121
17	72.5	1,327	2,505	0.017	27	1,143
16	67.5	1,352	2,250	0.015	24	1,164
15	62.5	1,377	2,002	0.013	21	1,186
14	57.5	1,402	1,760	0.012	19	1,208
13	54.5	283	324	0.002	3	244
12	52	2,201	2,314	0.016	25	1,895
11	48.5	1,673	1,556	0.010	17	1,441

ASSET: 418609, Woodstock Relo CT
 CUSTOMER: DISH WIRELESS L.L.C.

CODE: ANSI/TIA-222-H
 ENG NO: 13733434_C3_03

Segment	Height Above Base (ft)	Weight (lb)	W _z (lb-ft)	C _{vx}	Horizontal Force (lb)	Vertical Force (lb)
10	46	643	545	0.004	6	554
9	42.5	1,628	1,200	0.008	13	1,402
8	37.5	1,656	979	0.007	10	1,426
7	32.5	1,685	774	0.005	8	1,451
6	27.5	1,714	587	0.004	6	1,476
5	22.5	1,742	419	0.003	4	1,501
4	17.5	1,771	274	0.002	3	1,525
3	12.5	1,800	154	0.001	2	1,550
2	7.5	1,829	64	0.000	1	1,575
1	2.5	1,857	9	0.000	0	1,600
Generic Flat Platform with Handrails	148	2,500	16,581	0.111	178	2,153
Generic Flat Platform with Handrails	126	2,500	12,489	0.084	134	2,153
VZW Unused Reserve (22199.55 sqin)	148	2,140	14,193	0.095	152	1,843
Samsung B5/B13 RRH-BR04C	147	211	1,382	0.009	15	182
Samsung B2/B66A RRH-BR049	147	253	1,659	0.011	18	218
Raycap RRFDC-3315-PF-48	147	54	353	0.002	4	46
Samsung MT6407-77A	147	245	1,604	0.011	17	211
Andrew LNX-6514DS-A1M	147	116	763	0.005	8	100
Commscope SBNHH-1D65B (72.9")	147	244	1,596	0.011	17	210
Ericsson RRUS 8843 B2, B66A	138	216	1,267	0.008	14	186
Ericsson Radio 4415 B30	138	129	756	0.005	8	111
Ericsson RRUS 4478 B14	138	180	1,054	0.007	11	155
Ericsson RRUS 4449 B5, B12	138	213	1,249	0.008	13	183
Raycap DC9-48-60-24-8C-EV	138	48	281	0.002	3	41
Andrew SBNH-1D6565C (60.8 lbs)	138	182	1,070	0.007	11	157
Commscope NNHH-65C-R4	138	298	1,745	0.012	19	256
CCI DMP65R-BU8D	138	287	1,683	0.011	18	247
Low Profile Platform w/ SitePro1 HRK12-3HD	138	2,000	11,727	0.078	126	1,722
Reinforcmenet Kit						
Raycap RDIDC-9181-PF-48	127	22	111	0.001	1	19
Fujitsu TA08025-B604	127	192	971	0.006	10	165
Fujitsu TA08025-B605	127	225	1,140	0.008	12	194
Commscope FFFV-65B-R2	127	212	1,076	0.007	12	183
		53,376	149,417	1.000	1,601	45,966

1.2D + 1.0Ev + 1.0Eh Normal Seismic

CALCULATED FORCES

Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (ft-kips)	Mu MZ (ft-kips)	Mu Mx (ft-kips)	Resultant Moment (ft-kips)	Phi Pn (kips)	Phi Vn (kips)	Phi Tn (kips)	Phi Mn (kips)	Total Deflect (in)	Rotation (deg)	Ratio
0.00	-63.82	-1.60	0.00	-196.36	0.00	196.36	6,716.78	1,671.05	9,056	8,288.22	0.00	0.00	0.03
5.00	-61.56	-1.61	0.00	-188.35	0.00	188.35	6,634.81	1,641.41	8,738	8,040.68	0.00	-0.01	0.03
10.00	-59.33	-1.61	0.00	-180.30	0.00	180.30	6,551.49	1,611.78	8,425	7,795.15	0.01	-0.01	0.03
15.00	-57.13	-1.62	0.00	-172.22	0.00	172.22	6,466.84	1,582.14	8,118	7,551.74	0.03	-0.02	0.03
20.00	-54.97	-1.62	0.00	-164.14	0.00	164.14	6,380.85	1,552.51	7,817	7,310.53	0.05	-0.03	0.03
25.00	-52.85	-1.62	0.00	-156.04	0.00	156.04	6,293.51	1,522.87	7,521	7,071.60	0.08	-0.03	0.03
30.00	-50.76	-1.61	0.00	-147.96	0.00	147.96	6,204.83	1,493.24	7,232	6,835.05	0.12	-0.04	0.03
35.00	-48.71	-1.61	0.00	-139.89	0.00	139.89	6,114.81	1,463.60	6,947	6,600.97	0.17	-0.05	0.03
40.00	-46.69	-1.60	0.00	-131.86	0.00	131.86	6,023.45	1,433.96	6,669	6,369.44	0.22	-0.05	0.03
45.00	-45.90	-1.60	0.00	-123.87	0.00	123.87	5,930.75	1,404.33	6,396	6,140.56	0.28	-0.06	0.03
47.00	-43.82	-1.58	0.00	-120.68	0.00	120.68	5,893.29	1,392.47	6,289	6,049.76	0.30	-0.06	0.03
50.00	-41.10	-1.55	0.00	-115.94	0.00	115.94	5,819.53	1,374.69	6,129	5,896.99	0.34	-0.07	0.03
54.00	-40.75	-1.55	0.00	-109.72	0.00	109.72	4,932.79	1,204.96	5,382	5,013.55	0.40	-0.07	0.03
55.00	-39.01	-1.53	0.00	-108.17	0.00	108.17	4,917.77	1,199.77	5,335	4,976.57	0.41	-0.07	0.03
60.00	-37.30	-1.52	0.00	-100.50	0.00	100.50	4,841.84	1,173.84	5,107	4,792.90	0.49	-0.08	0.03
65.00	-35.63	-1.49	0.00	-92.92	0.00	92.92	4,764.57	1,147.91	4,884	4,611.29	0.58	-0.09	0.03
70.00	-33.98	-1.47	0.00	-85.45	0.00	85.45	4,685.96	1,121.98	4,666	4,431.81	0.67	-0.09	0.03
75.00	-32.37	-1.44	0.00	-78.11	0.00	78.11	4,606.01	1,096.04	4,453	4,254.57	0.77	-0.10	0.03
80.00	-30.79	-1.41	0.00	-70.92	0.00	70.92	4,524.71	1,070.11	4,245	4,079.64	0.88	-0.11	0.02
85.00	-29.24	-1.37	0.00	-63.88	0.00	63.88	4,420.37	1,044.18	4,041	3,888.03	1.00	-0.11	0.02
90.00	-27.72	-1.33	0.00	-57.01	0.00	57.01	4,310.59	1,018.25	3,843	3,696.36	1.12	-0.12	0.02
95.00	-27.68	-1.33	0.00	-50.34	0.00	50.34	4,200.82	992.32	3,650	3,509.54	1.25	-0.13	0.02
95.13	-25.40	-1.27	0.00	-50.17	0.00	50.17	4,198.07	991.67	3,645	3,504.93	1.25	-0.13	0.02
100.00	-24.99	-1.26	0.00	-43.99	0.00	43.99	4,091.04	966.39	3,462	3,327.57	1.38	-0.13	0.02

ASSET: 418609, Woodstock Relo CT
CUSTOMER: DISH WIRELESS L.L.C.

CODE: ANSI/TIA-222-H
ENG NO: 13733434_C3_03

Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (ft-kips)	Mu MZ (fr-kips)	Mu Mx (ft-kips)	Resultant Moment (ft-kips)	Phi Pn (kips)	Phi Vn (kips)	Phi Tn (kips)	Phi Mn (kips)	Total Deflect (in)	Rotation (deg)	Ratio
100.88	-24.05	-1.23	0.00	-42.89	0.00	42.89	2,749.22	700.09	2,543	2,275.29	1.41	-0.13	0.03
105.00	-22.93	-1.19	0.00	-37.83	0.00	37.83	2,709.67	684.81	2,433	2,193.23	1.52	-0.14	0.03
110.00	-21.83	-1.15	0.00	-31.88	0.00	31.88	2,660.51	666.29	2,304	2,094.74	1.67	-0.14	0.02
115.00	-20.75	-1.11	0.00	-26.12	0.00	26.12	2,610.00	647.76	2,177	1,997.38	1.82	-0.15	0.02
120.00	-19.69	-1.06	0.00	-20.57	0.00	20.57	2,558.16	629.24	2,055	1,901.26	1.98	-0.15	0.02
125.00	-19.48	-1.06	0.00	-15.25	0.00	15.25	2,504.97	610.72	1,935	1,806.46	2.14	-0.16	0.02
126.00	-16.18	-0.90	0.00	-14.19	0.00	14.19	2,494.18	607.02	1,912	1,787.67	2.18	-0.16	0.01
127.00	-14.76	-0.84	0.00	-13.29	0.00	13.29	2,483.32	603.31	1,889	1,768.93	2.21	-0.16	0.01
130.00	-13.77	-0.79	0.00	-10.78	0.00	10.78	2,450.45	592.20	1,820	1,713.07	2.31	-0.16	0.01
135.00	-13.18	-0.76	0.00	-6.83	0.00	6.83	2,394.58	573.67	1,708	1,621.18	2.48	-0.16	0.01
138.00	-8.43	-0.50	0.00	-4.56	0.00	4.56	2,360.41	562.56	1,642	1,566.80	2.59	-0.17	0.01
140.00	-7.68	-0.46	0.00	-3.55	0.00	3.55	2,337.37	555.15	1,599	1,530.87	2.65	-0.17	0.01
145.00	-7.39	-0.44	0.00	-1.24	0.00	1.24	2,271.73	536.63	1,494	1,437.76	2.83	-0.17	0.00
147.00	-5.87	-0.35	0.00	-0.35	0.00	0.35	2,240.37	529.22	1,453	1,398.14	2.90	-0.17	0.00
148.00	0.00	0.00	0.00	0.00	0.00	0.00	2,224.69	525.52	1,433	1,378.53	2.93	-0.17	0.00
149.00	0.00	0.00	0.00	0.00	0.00	0.00	2,209.00	521.81	1,413	1,359.07	2.97	-0.17	0.00

0.9D - 1.0Ev + 1.0Eh Normal

Seismic (Reduced DL)

CALCULATED FORCES

Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (ft-kips)	Mu MZ (fr-kips)	Mu Mx (ft-kips)	Resultant Moment (ft-kips)	Phi Pn (kips)	Phi Vn (kips)	Phi Tn (kips)	Phi Mn (kips)	Total Deflect (in)	Rotation (deg)	Ratio
0.00	-44.37	-1.60	0.00	-194.37	0.00	194.37	6,716.78	1,671.05	9,056	8,288.22	0.00	0.00	0.03
5.00	-42.79	-1.61	0.00	-186.36	0.00	186.36	6,634.81	1,641.41	8,738	8,040.68	0.00	-0.01	0.03
10.00	-41.24	-1.61	0.00	-178.33	0.00	178.33	6,551.49	1,611.78	8,425	7,795.15	0.01	-0.01	0.03
15.00	-39.72	-1.61	0.00	-170.28	0.00	170.28	6,466.84	1,582.14	8,118	7,551.74	0.03	-0.02	0.03
20.00	-38.22	-1.61	0.00	-162.23	0.00	162.23	6,380.85	1,552.51	7,817	7,310.53	0.05	-0.03	0.03
25.00	-36.74	-1.61	0.00	-154.18	0.00	154.18	6,293.51	1,522.87	7,521	7,071.60	0.08	-0.03	0.03
30.00	-35.29	-1.60	0.00	-146.14	0.00	146.14	6,204.83	1,493.24	7,232	6,835.05	0.12	-0.04	0.03
35.00	-33.86	-1.59	0.00	-138.13	0.00	138.13	6,114.81	1,463.60	6,947	6,600.97	0.16	-0.04	0.03
40.00	-32.46	-1.58	0.00	-130.16	0.00	130.16	6,023.45	1,433.96	6,669	6,369.44	0.21	-0.05	0.03
45.00	-31.91	-1.58	0.00	-122.24	0.00	122.24	5,930.75	1,404.33	6,396	6,140.56	0.27	-0.06	0.03
47.00	-30.46	-1.56	0.00	-119.08	0.00	119.08	5,893.29	1,392.47	6,289	6,049.76	0.30	-0.06	0.03
50.00	-28.57	-1.54	0.00	-114.39	0.00	114.39	5,819.53	1,374.69	6,129	5,896.99	0.34	-0.06	0.02
54.00	-28.32	-1.54	0.00	-108.24	0.00	108.24	4,932.79	1,204.96	5,382	5,013.55	0.39	-0.07	0.03
55.00	-27.12	-1.52	0.00	-106.70	0.00	106.70	4,917.77	1,199.77	5,335	4,976.57	0.41	-0.07	0.03
60.00	-25.93	-1.50	0.00	-99.11	0.00	99.11	4,841.84	1,173.84	5,107	4,792.90	0.49	-0.08	0.03
65.00	-24.77	-1.48	0.00	-91.62	0.00	91.62	4,764.57	1,147.91	4,884	4,611.29	0.57	-0.09	0.03
70.00	-23.62	-1.45	0.00	-84.24	0.00	84.24	4,685.96	1,121.98	4,666	4,431.81	0.66	-0.09	0.02
75.00	-22.50	-1.42	0.00	-76.99	0.00	76.99	4,606.01	1,096.04	4,453	4,254.57	0.76	-0.10	0.02
80.00	-21.40	-1.39	0.00	-69.88	0.00	69.88	4,524.71	1,070.11	4,245	4,079.64	0.87	-0.11	0.02
85.00	-20.33	-1.35	0.00	-62.93	0.00	62.93	4,420.37	1,044.18	4,041	3,888.03	0.99	-0.11	0.02
90.00	-19.27	-1.32	0.00	-56.16	0.00	56.16	4,310.59	1,018.25	3,843	3,696.36	1.11	-0.12	0.02
95.00	-19.24	-1.32	0.00	-49.58	0.00	49.58	4,200.82	992.32	3,650	3,509.54	1.23	-0.12	0.02
95.13	-17.65	-1.25	0.00	-49.42	0.00	49.42	4,198.07	991.67	3,645	3,504.93	1.24	-0.12	0.02
100.00	-17.37	-1.24	0.00	-43.32	0.00	43.32	4,091.04	966.39	3,462	3,327.57	1.36	-0.13	0.02
100.88	-16.72	-1.21	0.00	-42.24	0.00	42.24	2,749.22	700.09	2,543	2,275.29	1.39	-0.13	0.03
105.00	-15.94	-1.17	0.00	-37.25	0.00	37.25	2,709.67	684.81	2,433	2,193.23	1.50	-0.13	0.02
110.00	-15.17	-1.13	0.00	-31.38	0.00	31.38	2,660.51	666.29	2,304	2,094.74	1.65	-0.14	0.02
115.00	-14.42	-1.09	0.00	-25.71	0.00	25.71	2,610.00	647.76	2,177	1,997.38	1.80	-0.15	0.02
120.00	-13.69	-1.05	0.00	-20.25	0.00	20.25	2,558.16	629.24	2,055	1,901.26	1.95	-0.15	0.02
125.00	-13.54	-1.04	0.00	-15.01	0.00	15.01	2,504.97	610.72	1,935	1,806.46	2.12	-0.16	0.01
126.00	-11.25	-0.89	0.00	-13.98	0.00	13.98	2,494.18	607.02	1,912	1,787.67	2.15	-0.16	0.01
127.00	-10.26	-0.83	0.00	-13.09	0.00	13.09	2,483.32	603.31	1,889	1,768.93	2.18	-0.16	0.01
130.00	-9.57	-0.78	0.00	-10.61	0.00	10.61	2,450.45	592.20	1,820	1,713.07	2.28	-0.16	0.01
135.00	-9.16	-0.75	0.00	-6.73	0.00	6.73	2,394.58	573.67	1,708	1,621.18	2.45	-0.16	0.01
138.00	-5.86	-0.50	0.00	-4.49	0.00	4.49	2,360.41	562.56	1,642	1,566.80	2.55	-0.16	0.01
140.00	-5.34	-0.45	0.00	-3.50	0.00	3.50	2,337.37	555.15	1,599	1,530.87	2.62	-0.16	0.01
145.00	-5.14	-0.44	0.00	-1.22	0.00	1.22	2,271.73	536.63	1,494	1,437.76	2.79	-0.16	0.00
147.00	-4.08	-0.35	0.00	-0.35	0.00	0.35	2,240.37	529.22	1,453	1,398.14	2.86	-0.16	0.00
148.00	0.00	0.00	0.00	0.00	0.00	0.00	2,224.69	525.52	1,433	1,378.53	2.90	-0.16	0.00
149.00	0.00	0.00	0.00	0.00	0.00	0.00	2,209.00	521.81	1,413	1,359.07	2.93	-0.16	0.00

ANALYSIS SUMMARY

Load Case	Reactions						Max Usage	
	Shear FX (kips)	Shear FZ (kips)	Axial FY (kips)	Moment MX (ft-kips)	Moment MY (ft-kips)	Moment MZ (ft-kips)	Elev (ft)	Interaction Ratio
1.2D + 1.0W Normal	37.97	0.00	64.00	0.00	0.00	4326.75	0.00	0.53
0.9D + 1.0W Normal	37.95	0.00	47.99	0.00	0.00	4289.99	0.00	0.53
1.2D + 1.0Di + 1.0Wi Normal	9.93	0.00	80.16	0.00	0.00	1102.56	0.00	0.14
1.2D + 1.0Ev + 1.0Eh Normal	1.62	0.00	63.82	0.00	0.00	196.36	0.00	0.03
0.9D - 1.0Ev + 1.0Eh Normal	1.61	0.00	44.37	0.00	0.00	194.37	0.00	0.03
1.0D + 1.0W Service Normal	8.49	0.00	53.37	0.00	0.00	962.88	0.00	0.12

Site Name:Woodstock Relo CT, CT

Site Number:418609

Tower Type:MP

Design Loads (Factored) - Analysis per TIA-222-H Standards

Monolithic Mat & Pier Foundation Analysis


Foundation Analysis Parameters		
Design / Analysis / Mapping:	Analysis	-
Compression/Leg:	64.0	k
Uplift/Leg:	0.0	k
Total Shear:	38.0	k
Moment:	4,326.8	k-ft
Tower + Appurtenance Weight:	64.0	k
Depth to Base of Foundation (l + t - h):	6	ft
Diameter of Pier (d):	7.5	ft
Length of Pier (l):	4	ft
Height of Pier above Ground (h):	1	ft
Width of Pad (W):	30	ft
Length of Pad (L):	30	ft
Thickness of Pad (t):	3	ft
Tower Leg Center to Center:	0	ft
Number of Tower Legs:	1	-
Tower Center from Mat Center:	0	ft
Depth Below Ground Surface to Water Table:	4	ft
Unit Weight of Concrete:	150	pcf
Unit Weight of Soil Above Water Table:	125	pcf
Unit Weight of Water:	62.4	pcf
Unit Weight of Soil Below Water Table:	62.6	pcf
Friction Angle of Uplift:	15	°
Coefficient of Shear Friction:	0.2	-
Ultimate Compressive Bearing Pressure:	12,000	psf
Ultimate Passive Pressure on Pad Face:	839	psf
f _{Soil and Concrete Weight} :	0.9	-
f _{Soil} :	0.75	-

Overturning Moment Usage		
Design OTM:	4592.8	k-ft
OTM Resistance:	9744.6	k-ft
Design OTM / OTM Resistance:	47%	Pass

Soil Bearing Pressure Usage		
Net Bearing Pressure:	2491	psf
Factored Nominal Bearing Pressure:	9000	psf
Factored Nominal (Net) Bearing Pressure:	28%	Pass
Load Direction Controlling Design Bearing Pressure:	Diagonal to Pad Edge	

Sliding Factor of Safety		
Ultimate Friction Resistance:	138.7	k
Ultimate Passive Pressure Resistance:	56.6	k
Total Factored Sliding Resistance:	146.5	k
Sliding Design / Sliding Resistance:	26%	Pass

Foundation Steel Parameters		
Shear/Leg (Compression):	25.3	k
Shear/Leg (Uplift):	20.9	k
Concrete Strength (f _c):	4,000	psi
Pad Tension Steel Depth:	32.31	in
Dead Load Factor:	0.9	-
f _{Shear} :	0.75	-
f _{Flexure / Tension} :	0.9	-
f _{Compression} :	0.65	-
b:	0.85	-
Bottom Pad Rebar Size #:	11	-
# of Bottom Pad Rebar:	36	-
Pad Bottom Steel Area:	56.16	in ²
Pad Steel F _y :	60,000	psi
Top Pad Rebar Size #:	11	-
# of Top Pad Rebar:	24	-
Pad Top Steel Area:	37.44	in ²
Pier Rebar Size #:	9	-
Pier Steel Area (Single Bar):	1.00	in ²
# of Pier Rebar:	40	-
Pier Steel F _y :	60,000	psi
Pier Cage Diameter:	81.9	in
Rebar Strain Limit:	0.008	-
Steel Elastic Modulus:	29,000	ksi
Tie Rebar Size #:	4	-
Tie Steel Area (Single Bar):	0.20	in ²
Tie Spacing:	6	in
Tie Steel F _y :	60,000	psi
Clear Cover:	3	in



Pad Strength Capacity			
Factored One Way Shear (V_u):	345.0	k	ACI 318-14 25.5.5.1
One Way Shear Capacity (fV_c):	1103.6	k	
V_u / fV_c :	31%	Pass	
Load Direction Controlling Shear Capacity:	Parallel to Pad Edge		
Lower Steel Pad Factored Moment (M_u):	2657.0	k-ft	ACI 318-14 22.3.1.1
Lower Steel Pad Moment Capacity (fM_n):	7870.3	k-ft	
M_u / fM_n :	34%	Pass	
Load Direction Controlling Flexural Capacity:	Parallel to Pad Edge		
Upper Steel Pad Factored Moment (M_u):	1291.1	k-ft	
Upper Steel Pad Moment Capacity (fM_n):	5312.6	k-ft	
M_u / fM_n :	24%	Pass	
Lower Pad Flexural Reinforcement Ratio:	0.0048		
Upper Pad Flexural Reinforcement Ratio:	0.0032		OK - ACI 318-14 7.6.1.1 & 8.6.1.1
Pad Shrinkage Reinforcement Ratio:	0.0080		OK - ACI 318-14 24.4.3.2
Lower Pad Reinforcement Spacing:	10.1	in	OK - ACI 318-14 7.7.2.3, 8.7.2.2, & 24.4.3.3
Upper Pad Reinforcement Spacing:	15.4	in	OK - ACI 318-14 7.7.2.3, 8.7.2.2, & 24.4.3.3
Ultimate Punching Shear Stress, v_u :	43.54	psi	ACI 318-14 R8.4.4.2.3
Nominal Punching Shear Capacity ($f_c v_c$):	189.7	psi	ACI 318-14 22.6.5.2
$v_u / f_c v_c$:	23%	Pass	
Pier Moment Pad Flexure Transfer Ratio, γ_f :	0.60		TIA-222-H 9.4.2
Moment Transfer Effective Flexural Width, B_{eff} :	16.50	ft	TIA-222-H 9.4.2
Moment Transfer Through Pad Flexure:	32247.36	k-in	TIA-222-H 9.4.2
Moment Transfer Flexural Capacity ($fM_{sc,f}$):	53997.07	k-in	
$g_f M_{sc} / fM_{sc,f}$:	0%	Pass	

Pier Strength Capacity			
Factored Moment in Pier (M_u):	4478.8	k-ft	
Pier Moment Capacity (ϕM_n):	7207.9	k-ft	
$M_u / \phi M_n$:	62%	Pass	
Factored Shear in Pier (V_u):	38.0	k	ACI 318-14 22.5.1.1
Pier Shear Capacity (ϕV_n):	822.6	k	
$V_u / \phi V_c$:	5%	Pass	
Pier Shear Reinforcement Ratio:	0.0003		OK - No Ties Necessary for Shear - ACI11.5.6.1
Factored Tension in Pier (T_u):	0.0	k	
Pier Tension Capacity (ϕT_n):	2160.0	k	
$T_u / \phi T_n$:	0%	Pass	
Factored Compression in Pier (P_u):	64.0	k	ACI 318-14 22.4.2.1
Pier Compression Capacity (ϕP_n):	11208.0	k	
$P_u / \phi P_n$:	1%	Pass	
Pier Compression Reinforcement Ratio:	0.006		OK - TIA-222-H 9.4.1
Minimum Depth to Develop Vertical Rebar:	37	in	ACI 318-14 25.4.2.3
Minimum Hook Development Length:	22	in	ACI 318-14 25.4.3.1
Minimum Mat Thickness / Edge Distance from Pier:	25.0	in	
Minimum Foundation Depth:	4.93	ft	
$M_u/\phi_B M_n + T_u/\phi_T T_n$:	62%	Pass	




Base Plate & Anchor Rod Analysis

Pole Dimensions		
Number of Sides	18	-
Diameter	60.5	in
Thickness	1/2	in
Orientation Offset	0	°

Base Reactions		
Moment, Mu	4326.8	k-ft
Axial, Pu	64.0	k
Shear, Vu	38.0	k
Neutral Axis	120	°

Report Capacities		
Component	Capacity	Result
Base Plate	27%	Pass
Anchor Rods	56%	Pass
Dwyidag	-	-

Base Plate		
Shape	Round	-
Diameter, Ø	74	in
Thickness	2 3/4	in
Grade	A572-50	
Yield Strength, Fy	50	ksi
Tensile Strength, Fu	65	ksi
Clip	N/A	in
Orientation Offset	0	°
Anchor Rod Detail	d	η=0.5
Clear Distance	3	in
Applied Moment, Mu	695.4	k
Bending Stress, φMn	2530.4	k



Original Anchor Rods		
Arrangement	Radial	-
Quantity	24	-
Diameter, Ø	2 1/4	in
Bolt Circle	68	in
Grade	A615-75	
Yield Strength, Fy	75	ksi
Tensile Strength, Fu	100	ksi
Spacing	8.9	in
Orientation Offset	0	°
Applied Force, Pu	134.5	k
Anchor Rods, φPn	243.6	k

Calculations for Monopole Base Plate & Anchor Rod Analysis

Reaction Distribution

Reaction	Shear Vu	Moment Mu	Factor
-	k	k-ft	-
Base Forces	38.0	4326.8	1.00
Anchor Rod Forces	38.0	4326.8	1.00
Additional Bolt (Grp1) Forces	0.0	0.0	0.00
Additional Bolt (Grp2) Forces	0.0	0.0	0.00
Dywidag Forces	0.0	0.0	0.00
Stiffener Forces	0.0	0.0	0.00

Geometric Properties

Section	Gross Area	Net Area	Individual Inertia	Threads per Inch	Moment of Inertia
-	in ²	in ²	in ⁴	#	in ⁴
Pole	93.7700	5.2094	0.4359		42204.35
Bolt	3.9761	3.2477	0.8393	4.5	41980.04
Bolt1	0.0000	0.0000	0.0000	0	0.00
Bolt2	0.0000	0.0000	0.0000	0	0.00
Dywidag	0.0000	0.0000	0.0000		0.00
Stiffener	0.0000	0.0000	0.0000		0.00

Base Plate		
Shape	Round	-
Diameter, D	74	in
Thickness, t	2.75	in
Yield Strength, Fy	50	ksi
Tensile Strength, Fu	65	ksi
Base Plate Chord	42.612	in
Detail Type	d	-
Detail Factor	0.50	-
Clear Distance	3	-

Anchor Rods		
Anchor Rod Quantity, N	24	-
Rod Diameter, d	2.25	in
Bolt Circle, BC	68	in
Yield Strength, Fy	75	ksi
Tensile Strength, Fu	100	ksi
Applied Axial, Pu	134.5	k
Applied Shear, Vu	0.6	k
Compressive Capacity, ϕPn	243.6	k
Tensile Capacity, ϕRnt	0.552	OK
Interaction Capacity	0.557	OK

External Base Plate		
Chord Length AA	35.984	in
Additional AA	5.500	in
Section Modulus, Z	78.431	in ³
Applied Moment, Mu	695.4	k-ft
Bending Capacity, ϕMn	3529.4	k-ft
Capacity, Mu/ϕMn	0.197	OK

Chord Length AB	34.360	in
Additional AB	5.500	in
Section Modulus, Z	75.360	in ³
Applied Moment, Mu	511.0	k-ft
Bending Capacity, ϕMn	3391.2	k-ft
Capacity, Mu/ϕMn	0.151	OK

Bend Line Length	29.742	in
Additional Bend Line	0.000	in
Section Modulus, Z	56.230	in ³
Applied Moment, Mu	695.4	k-ft
Bending Capacity, ϕMn	2530.4	k-ft
Capacity, Mu/ϕMn	0.275	OK

Internal Base Plate		
Arc Length	0.000	in
Section Modulus, Z	0.000	in ³
Moment Arm	0.000	in
Applied Moment, Mu	0.0	k-ft
Bending Capacity, ϕMn	0.0	k-ft
Capacity, Mu/ϕMn		



|
|
si
si



DISH Wireless L.L.C. SITE ID:

BOBOS00030A

DISH Wireless L.L.C. SITE ADDRESS:

87 WEST QUASSET ROAD
WOODSTOCK, CT 06281

CONNECTICUT CODE COMPLIANCE

ALL WORK SHALL BE PERFORMED AND MATERIALS INSTALLED IN ACCORDANCE WITH THE CURRENT EDITIONS OF THE FOLLOWING CODES AS ADOPTED BY THE LOCAL GOVERNING AUTHORITIES. NOTHING IN THESE PLANS IS TO BE CONSTRUED TO PERMIT WORK NOT CONFORMING TO THESE CODES:

CODE TYPE	CODE
BUILDING	2018 CT STATE BUILDING CODE/2015 IBC W/ CT AMENDMENTS
MECHANICAL	2018 CT STATE BUILDING CODE/2015 IMC W/ CT AMENDMENTS
ELECTRICAL	2018 CT STATE BUILDING CODE/2017 NEC W/ CT AMENDMENTS

SHEET INDEX

SHEET NO.	SHEET TITLE
T-1	TITLE SHEET
A-0	EXISTING SURVEY
A-1	OVERALL AND ENLARGED SITE PLAN
A-2	ELEVATION, ANTENNA LAYOUT AND SCHEDULE
A-3	EQUIPMENT PLATFORM AND H-FRAME DETAILS
A-4	EQUIPMENT DETAILS
A-5	EQUIPMENT DETAILS
A-6	EQUIPMENT DETAILS
E-1	ELECTRICAL/FIBER ROUTE PLAN AND NOTES
E-2	ELECTRICAL DETAILS
E-3	ELECTRICAL ONE-LINE, FAULT CALCS & PANEL SCHEDULE
G-1	GROUNDING PLANS AND NOTES
G-2	GROUNDING DETAILS
G-3	GROUNDING DETAILS
RF-1	RF CABLE COLOR CODE
GN-1	LEGEND AND ABBREVIATIONS
GN-2	GENERAL NOTES
GN-3	GENERAL NOTES
GN-4	GENERAL NOTES

SCOPE OF WORK

THIS IS NOT AN ALL INCLUSIVE LIST. CONTRACTOR SHALL UTILIZE SPECIFIED EQUIPMENT PART OR ENGINEER APPROVED EQUIVALENT. CONTRACTOR SHALL VERIFY ALL NEEDED EQUIPMENT TO PROVIDE A FUNCTIONAL SITE. THE PROJECT GENERALLY CONSISTS OF THE FOLLOWING:

- TOWER SCOPE OF WORK:
- INSTALL (3) PROPOSED PANEL ANTENNAS (1 PER SECTOR)
 - INSTALL (1) PROPOSED ANTENNA PLATFORM MOUNT
 - INSTALL PROPOSED JUMPERS
 - INSTALL (6) PROPOSED RRUs (2 PER SECTOR)
 - INSTALL (1) PROPOSED OVER VOLTAGE PROTECTION DEVICE (OVP)
 - INSTALL (1) PROPOSED HYBRID CABLE

- GROUND SCOPE OF WORK:
- INSTALL (1) PROPOSED METAL PLATFORM
 - INSTALL (1) PROPOSED ICE BRIDGE
 - INSTALL (1) PROPOSED PPC CABINET
 - INSTALL (1) PROPOSED EQUIPMENT CABINET
 - INSTALL (1) PROPOSED POWER CONDUIT
 - INSTALL (1) PROPOSED TELCO CONDUIT
 - INSTALL (1) PROPOSED TELCO-FIBER BOX
 - INSTALL (1) PROPOSED GPS UNIT
 - INSTALL (1) PROPOSED SAFETY SWITCH (IF REQUIRED)
 - INSTALL (1) PROPOSED CIENA BOX (IF REQUIRED)

SITE PHOTO



UNDERGROUND SERVICE ALERT CBYD 811
UTILITY NOTIFICATION CENTER OF CONNECTICUT
(800) 922-4455
WWW.CBYD.COM

CALL 2 WORKING DAYS UTILITY NOTIFICATION PRIOR TO CONSTRUCTION



GENERAL NOTES

THE FACILITY IS UNMANNED AND NOT FOR HUMAN HABITATION. A TECHNICIAN WILL VISIT THE SITE AS REQUIRED FOR ROUTINE MAINTENANCE. THE PROJECT WILL NOT RESULT IN ANY SIGNIFICANT DISTURBANCE OR EFFECT ON DRAINAGE. NO SANITARY SEWER SERVICE, POTABLE WATER, OR TRASH DISPOSAL IS REQUIRED AND NO COMMERCIAL SIGNAGE IS PROPOSED.

THE PROJECT DEPICTED IN THESE PLANS QUALIFIES AS AN ELIGIBLE FACILITIES REQUEST ENTITLED TO EXPEDITED REVIEW UNDER 47 U.S.C. § 1455(A) AS A MODIFICATION OF AN EXISTING WIRELESS TOWER THAT INVOLVES THE COLLOCATION, REMOVAL, AND/OR REPLACEMENT OF TRANSMISSION EQUIPMENT THAT IS NOT A SUBSTANTIAL CHANGE UNDER CFR § 1.61000 (B)(7).

11"x17" PLOT WILL BE HALF SCALE UNLESS OTHERWISE NOTED

CONTRACTOR SHALL VERIFY ALL PLANS, EXISTING DIMENSIONS, AND CONDITIONS ON THE JOB SITE, AND SHALL IMMEDIATELY NOTIFY THE ENGINEER IN WRITING OF ANY DISCREPANCIES BEFORE PROCEEDING WITH THE WORK.

SITE INFORMATION

PROPERTY OWNER: QUASSET HILL FARM LLC
ADDRESS: 87 WEST QUASSET ROAD
WOODSTOCK, CT 06281

TOWER TYPE: MONOPOLE

TOWER CO SITE ID: 418609

TOWER APP NUMBER: 13733434_D3

COUNTY: WINDHAM

LATITUDE (NAD 83): 41° 55' 47.225" N
41.9297847

LONGITUDE (NAD 83): 71° 59' 21.617" W
-71.98933794

ZONING JURISDICTION: CITY OF WOODSTOCK

ZONING DISTRICT: RESIDENTIAL

PARCEL NUMBER: WOOD-006393-000066-000003

OCCUPANCY GROUP: U

CONSTRUCTION TYPE: II-B

POWER COMPANY: NORTHEAST UTILITY

TELEPHONE COMPANY: UNKNOWN

PROJECT DIRECTORY

APPLICANT: DISH Wireless L.L.C.
5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120

TOWER OWNER: AMERICAN TOWER
10 PRESIDENTIAL WAY
WOBURN, MA 01801

ENGINEER: ATC TOWER SERVICES, LLC
3500 REGENCY PARKWAY SUITE 100
CARY, NC 27518

SITE ACQUISITION: DAVID GOODFELLOW
DAVID.GODFELLOW@DISH.COM


CONSTRUCTION MANAGER: CHAD WILCOX
CHAD.WILCOX@DISH.COM

RF ENGINEER: ARVIN SEBASTIAN
ARVIN.SEBASTIAN@DISH.COM

DIRECTIONS

184 (E) TO EXIT 69. TAKE RTE 74 (E) TO RTE 44 (E). MAKE A LEFT ONTO RTE 198 (N) AND A RIGHT ONTO RTE 244 (E). MAKE A LEFT ONTO QUASSET RD AND ANOTHER LEFT ONTO WEST QUASSET RD.

VICINITY MAP



5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



A.T. ENGINEERING SERVICE, PLLC
3500 REGENCY PARKWAY
SUITE 100
CARY, NC 27518
PHONE: (919) 468-0112


DRAWN BY: CHECKED BY: APPROVED BY:

AP SRF SRF

RFDS REV #: ----

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
0	01/05/2022	ISSUED FOR CONSTRUCTION



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

A&E PROJECT NUMBER

418609-13733434_D3

DISH Wireless L.L.C.
PROJECT INFORMATION
BOBOS00030A

87 WEST QUASSET ROAD
WOODSTOCK, CT 06281

SHEET TITLE

TITLE SHEET

SHEET NUMBER

T-1

PROJECT SUMMARY

FIELD SURVEY DATE: 05/25/2018
SITE ADDRESS: 87 WEST QUASSET ROAD, WOODSTOCK, CT 06281

PARCEL INFORMATION
OWNER: QUASSET HILL FARM, LLC
OWNER ADDRESS: P.O. BOX 113, WOODSTOCK, CT 06281
APN: 2016-1-0003316; MAP 6393, BLOCK 66, LOT 3; VOLUME 394, PAGE 12

TOTAL AREAS:
PARENT PARCEL: 22.80± ACRES (PER TAX RECORDS)
ATC LEASE AREA: 10,000 SQ.FT. 0.230± ACRES
ACCESS & UTILITY EASEMENT: 25,872 SQ.FT. 0.594± ACRES

BASIS OF BEARINGS
THE BASIS OF BEARINGS AND COORDINATES FOR THIS PLAN IS CONNECTICUT STATE PLANE COORDINATE SYSTEM, NORTH AMERICAN DATUM (NAD83). VERTICAL DATUM SHOWN HEREON IS BASED ON NORTH AMERICAN VERTICAL DATUM (NAV83) IN US SURVEY FEET.

FLOODPLAIN:
PER THE FEMA FLOODPLAIN MAPS, THE SITE IS LOCATED IN AN AREA DESIGNATED AS ZONE C.
COMMUNITY PANEL NO.: 09012002088 DATED: 11/01/1984

ENCROACHMENT STATEMENT:
AT THE TIME OF SURVEY THERE WAS VISIBLE EVIDENCE OF AN ENCROACHMENT AS FOLLOWS: NO LEGAL DESCRIPTIONS FOR LEASE AREA, ACCESS AND/OR UTILITY EASEMENTS WERE PROVIDED. JUST A LEASE EXHIBIT ATTACHED TO THE MOL BK 66 PG 254 RECORDED ON 6/20/12 AND AN EASEMENT MAP AS INSTRUMENT #2370 RECORDED ON 12/14/12.

TOWER INFORMATION:
TOWER TYPE: EXISTING MONOPOLE
LATITUDE N: 41°59'47.18" (NAD 83)
LONGITUDE W: 71°59'21.54" (NAD 83)
GROUND ELEVATION AT BASE OF TOWER: 692' FEET (NAVD 1988)
STRUCTURE HEIGHT: 150' (AGL)
ELEVATION OF TOP OF TOWER: 707' (NAVD 1988)
ELEVATION OF HIGHEST POINT: 708.5' (NAVD 1988)

NOTE: THIS SURVEY DOES NOT CONSTITUTE A BOUNDARY SURVEY OF THE PARENT TRACT. ANY PARENT TRACT PROPERTY LINES SHOWN HEREON ARE FROM SUPPLIED INFORMATION AND MAY NOT BE FIELD VERIFIED.

SURVEYOR'S NOTES

1. THERE IS ACCESS TO THE ATC LEASE AREA FROM WEST QUASSET ROAD PER THE AS-SURVEYED ACCESS EASEMENT SHOWN HEREON.
2. THE LOCATIONS OF ALL UTILITIES SHOWN ON THE SURVEY ARE FROM VISIBLE SURFACE EVIDENCE ONLY.
3. AT THE TIME OF THIS SURVEY THERE WAS NO OBSERVABLE SURFACE EVIDENCE OF EARTH MOVING WORK, BUILDING CONSTRUCTION OR BUILDING ADDITIONS WITHIN RECENT MONTHS.
4. AT THE TIME OF THIS SURVEY, THERE WAS NO OBSERVABLE EVIDENCE OF THE SUBJECT PROPERTY BEING USED AS A SOLID WASTE DUMP, BUMP OR SANITARY LANDFILL.
5. AT THE TIME OF THIS SURVEY, THERE WAS NO OBSERVABLE EVIDENCE OF ANY RECENT CHANGES IN STREET RIGHT-OF-WAY LINES EITHER COMPLETED OR PROPOSED, AND AVAILABLE FROM THE CONTROLLING JURISDICTION.
6. AT THE TIME OF THIS SURVEY, THERE WAS NO OBSERVABLE EVIDENCE OF ANY RECENT STREET OR SIDEWALK CONSTRUCTION OR REPAIRS.
7. THIS IS AN AS BUILT SURVEY OF AN EXISTING ATC LEASE PARCEL WITHIN AN EXISTING PARCEL OF LAND, THE BOUNDARIES OF WHICH HAVE NOT BEEN SURVEYED.
8. ALL CALLS ARE MEASURED UNLESS OTHERWISE NOTED.
9. UNLESS OTHERWISE SPECIFIED, UTILITY POLES DID NOT IDENTIFY OWNERSHIP.
10. THIS SURVEY IS A HORIZONTAL ACCURACY CLASS AA AND A TOPOGRAPHICAL ACCURACY CLASS 1-1 AS DEFINED IN SEC. 20-300B-11 OF THE CONNECTICUT STANDARDS FOR SURVEYS.

ZONING INFORMATION

ZONING INFORMATION WAS NOT PROVIDED AT THE TIME OF SURVEY.

LEGAL DESCRIPTIONS

TITLE REPORT LEGAL DESCRIPTION (PARENT PARCEL - FOR INFORMATION ONLY - NOT SURVEYED):

First Tract: The First Tract, commencing at brook near south west corner of Quasset Cemetery, thence westerly bounding northerly by land now or formerly of Arthur William and Charles Johnson to northeast corner of land now or formerly of Johanna Talbot, thence southerly bounding westerly by land now or formerly of said Johanna Talbot to highway leading by schoolhouse, thence easterly on said highway to northeast corner of land now or formerly of Thomas Wilson heirs, thence southerly bounding westerly by land now or formerly of said Wilson heirs to southeast corner of said land, thence westerly bounding northerly by land nor or formerly of said Wilson heirs to land nor or formerly of Claus Nelson, thence southerly bounding westerly by land nor formerly of said Nelson to land now or formerly Charles H. Hyde, thence easterly bounding southerly by land now or formerly of said Hyde to highway leading to Sprucedale, thence northeasterly on said highway to brook below reservoir dam, thence northerly on said brook, bounding easterly by land now or formerly of John Williams to piece of beginning and contains fifty-five (55) acres, more or less. Excepting therefrom that tract which was conveyed to John A. Collins on March 18th, 1921, and recorded in volume 40, Woodstock Land Records, Page 458 as follows:

*Beginning at the south east corner of said tract and on the south west corner of a schoolhouse lot and on the road leading from the dam at Quasset Pond by the residence nor or formerly of Herbert M. Woodbury and Elda Althea Woodbury; thence northerly on said schoolhouse lot and land now or formerly of said Woodbury and on a fence to the land now or formerly of one Williams; thence westerly on land now or formerly of said Williams and land now or formerly of John A. Collins to land now or formerly of one Williams; thence southerly in the land of said Williams to said road, thence easterly on said road to place of beginning containing 8 acres more or less.

Second Tract: A tract or parcel of land lying and being situated in said Woodstock and bounded and described as follows: Commencing at the northwest corner of land now or formerly of Gustave Anderson; thence west to land now or formerly of Gustave Carlson; thence south by land now or formerly of said Carlson to land now or formerly of Claus Nelson; thence east by said Nelson land, adjoining land now or formerly of Gustave Anderson, to land now or formerly of Gustave Anderson; thence north by said Gustave Anderson to first mentioned land being the same tract of land conveyed by Williams R. Arnold to Thomas Wilson January 5, 1892 and recorded in the Woodstock Land Records, Book 27, Page 555. Being the same premises conveyed to Herbert Woodbury by Warranty Deed of Anna Anderson, dated February 26, 1943, recorded in the Land Records of the Town of Woodstock, volume 47, pages 546, 547.

Said First tract and Second tract herein being the same premises described as First Tract and Third tract in a warranty deed recorded in volume 55, page 522 of the Woodstock Land Records. Further reference is made to a Quit Claim Deed recorded in Volume 63, Page 241 of the Woodstock Land Records.

NOTE: PARENT PARCEL GRAPHICALLY SHOWN HEREON AS DESCRIPTIONS ARE TOO VAGUE. FIRST AND SECOND TRACT REFERENCED ABOVE ARE NOT ABLE TO BE INDIVIDUALLY LABELED.

ATC LEASE AREA - AS-SURVEYED:

SITUATED IN THE TOWN OF WOODSTOCK, COUNTY OF WINDHAM AND STATE OF CONNECTICUT, LYING WITHIN THAT TRACT OF LAND CONVEYED TO QUASSET HILL FARM, LLC IN VOLUME 394, PAGE 12, TOWN OF WOODSTOCK LAND RECORDS AND BEING MORE PARTICULARLY AS FOLLOWS:

COMMENCING AT A STONE AND TREE STUMP CORNER FOUND FOR THE APPARENT COMMON CORNER OF THE AFORESAID QUASSET HILL FARM, LLC TRACT AND A TRACT OF LAND CONVEYED TO THOMAS R. DAVIS IN VOLUME 233, PAGE 179, SAID POINT HAVING STATE PLANE COORDINATES OF NORTH = 900285.655, EAST=120663.074, THENCE CROSSING THE QUASSET HILL FARM TRACT, NORTH 75°06'28" EAST, 301.63' TO THE POINT OF BEGINNING, HAVING STATE PLANE COORDINATES OF NORTH=900363.174, EAST=1206944.567;

THENCE NORTH 02°23'19" WEST, 100.00 FEET TO A POINT;
THENCE NORTH 87°36'41" EAST, 100.00 FEET TO A POINT;
THENCE SOUTH 02°23'19" EAST, 100.00 FEET TO A POINT;
THENCE SOUTH 87°36'41" WEST, 100.00 FEET TO THE POINT OF BEGINNING.

HAVING AN AREA OF 10,000 SQUARE FEET (0.230 ACRES) OF LAND, MORE OR LESS.

ACCESS & UTILITY EASEMENT - AS-SURVEYED:

SITUATED IN THE TOWN OF WOODSTOCK, COUNTY OF WINDHAM AND STATE OF CONNECTICUT, LYING WITHIN THAT TRACT OF LAND CONVEYED TO QUASSET HILL FARM, LLC IN VOLUME 394, PAGE 12, TOWN OF WOODSTOCK LAND RECORDS AND BEING MORE PARTICULARLY AS FOLLOWS:

COMMENCING AT A STONE AND TREE STUMP CORNER FOUND FOR THE APPARENT COMMON CORNER OF THE AFORESAID QUASSET HILL FARM, LLC TRACT AND A TRACT OF LAND CONVEYED TO THOMAS R. DAVIS IN VOLUME 233, PAGE 179, SAID POINT HAVING STATE PLANE COORDINATES OF NORTH = 900285.655, EAST=120663.074, THENCE CROSSING THE QUASSET HILL FARM TRACT, NORTH 75°06'28" EAST, 301.63' TO A POINT HAVING STATE PLANE COORDINATES OF NORTH=900363.174, EAST=1206944.567;

THENCE NORTH 87°36'41" EAST, 56.36 FEET TO THE POINT OF BEGINNING;


THENCE NORTH 87°36'41" EAST, A DISTANCE OF 25.01 FEET TO A POINT;
THENCE SOUTH 03°50'40" EAST, A DISTANCE OF 314.58 FEET TO A POINT;
THENCE SOUTH 32°39'31" EAST, A DISTANCE OF 38.68 FEET TO A POINT;
THENCE SOUTH 47°32'51" EAST, A DISTANCE OF 21.73 FEET TO A POINT;
THENCE NORTH 73°02'40" EAST, A DISTANCE OF 86.96 FEET TO A POINT;
THENCE NORTH 84°54'06" EAST, A DISTANCE OF 82.82 FEET TO A POINT;
THENCE NORTH 74°55'14" EAST, A DISTANCE OF 127.02 FEET TO A POINT;
THENCE NORTH 70°10'15" EAST, A DISTANCE OF 70.26 FEET TO A POINT;
THENCE NORTH 79°31'15" EAST, A DISTANCE OF 93.83 FEET TO A POINT;
THENCE NORTH 87°44'51" EAST, A DISTANCE OF 76.67 FEET TO A POINT;
THENCE SOUTH 80°10'28" EAST, A DISTANCE OF 112.38 FEET TO A POINT;
THENCE SOUTH 49°45'46" WEST, A DISTANCE OF 13.51 FEET TO A POINT;
THENCE SOUTH 39°06'50" WEST, A DISTANCE OF 15.61 FEET TO A POINT;
THENCE NORTH 80°10'28" WEST, A DISTANCE OF 95.65 FEET TO A POINT;
THENCE SOUTH 87°44'51" WEST, A DISTANCE OF 72.23 FEET TO A POINT;
THENCE SOUTH 79°31'15" WEST, A DISTANCE OF 89.99 FEET TO A POINT;
THENCE SOUTH 79°10'15" WEST, A DISTANCE OF 69.25 FEET TO A POINT;
THENCE SOUTH 74°55'14" WEST, A DISTANCE OF 130.24' FEET TO A POINT;
THENCE SOUTH 84°54'06" WEST, A DISTANCE OF 82.41' FEET TO A POINT;
THENCE SOUTH 73°02'40" WEST, A DISTANCE OF 98.62' FEET TO A POINT;
THENCE NORTH 47°32'51" WEST, A DISTANCE OF 48.37' FEET TO A POINT;
THENCE NORTH 32°39'31" WEST, A DISTANCE OF 38.68' FEET TO A POINT;
THENCE NORTH 03°50'40" WEST, A DISTANCE OF 321.64 FEET TO THE POINT OF BEGINNING.

HAVING AN AREA OF 25,872 SQUARE FEET (0.594 ACRES) OF LAND, MORE OR LESS.


NOTES CORRESPONDING TO SCORE REPORT

THE CORAL REPORT ISSUED BY TITILEVEST, FILE NO. S-CT-647769, DATED 9/2/2018 CONTAINS THE FOLLOWING ITEMS:

1. CONFIRMATORY MEMORANDUM OF LEASE BY AND BETWEEN HAROLD R. BISHOP AND AMERICAN TOWER, LP DATED 2/9/2005 AND RECORDED 2/23/2005 IN BOOK 423 AT PAGE 376. LOCATED ON PARENT PARCEL, AFFECTS ACCESS EASEMENT, APPROXIMATE LOCATION PLOTTED AND SHOWN HEREON
2. MEMORANDUM OF LAND LEASE AGREEMENT BY AND BETWEEN QUASSET HILL FARM, LLC AND CELCOO PARTNERSHIP DATED 6/23/2010 AND RECORDED 9/2/2010 IN BOOK 525 AT PAGE 428. ATC LEASE AREA IS AS SHOWN
3. AMENDED MEMORANDUM OF LAND LEASE AGREEMENT BY AND BETWEEN QUASSET HILL FARM, LLC AND CELCOO PARTNERSHIP DATED 6/18/2012 AND RECORDED 6/20/2012 IN BOOK 559 AT PAGE 254. ATC LEASE AREA IS AS SHOWN
4. EASEMENT BY AND BETWEEN THE CONNECTICUT LIGHT AND POWER COMPANY AND POWER COMPANY DATED 11/29/2012 AND RECORDED 12/14/2012 IN BOOK 559 AT PAGE 131. AFFECTS ATC LEASE AREA - PLOTTED AND SHOWN HEREON
5. MEMORANDUM OF LEASE BY AND BETWEEN CELCOO PARTNERSHIP AND ATC SEQUOIA, LLC DATED 6/1/2015 AND RECORDED 6/10/2015 IN BOOK 595 AT PAGE 218. LOCATED ON PARENT PARCEL, AFFECTS ACCESS EASEMENT AS SHOWN




1 VICINITY MAP





2 PARENT PARCEL


GRAPHICALLY SHOWN
NOT TO SCALE



3 COMPOUND DETAIL



4 SURVEY PLAN



Work Coordinated By:

COX LEVIN

National Land Survey Consultants
surveys@coxlevin.com
781-640-3309 • www.coxlevin.com

811

Know what's below.
Call before you dig.

AMERICAN TOWER®
ATC TOWER SERVICES, INC.
3500 REGENCY PARKWAY
SUITE 100
CARY, NC 27518
PHONE: (919) 468-0112
FAX: (919) 466-5415

THESE DRAWINGS AND/OR THE ACCOMPANYING SPECIFICATION AS INSTRUMENTS OR SERVICE ARE THE EXCLUSIVE PROPERTY OF AMERICAN TOWER. THEIR USE AND PUBLICATION SHALL BE RESTRICTED TO THE ORIGINAL SITE FOR WHICH THEY ARE PREPARED. ANY USE OR DISCLOSURE OTHER THAN THAT WHICH RELATES TO AMERICAN TOWER OR THE SPECIFIED CARRIER IS STRICTLY PROHIBITED. TITLE TO THESE DOCUMENTS SHALL REMAIN THE PROPERTY OF AMERICAN TOWER WHETHER OR NOT THE PROJECT IS EXECUTED. NEITHER THE ARCHITECT NOR THE ENGINEER WILL BE PROVIDING ON-SITE CONSTRUCTION REVIEW OF THIS PROJECT. CONTRACTOR(S) MUST VERIFY ALL DIMENSIONS AND ADVISE AMERICAN TOWER OF ANY DISCREPANCIES. ANY PRIOR ISSUANCE OF THIS DRAWING IS SUPERSEDED BY THE LATEST VERSION ON FILE WITH AMERICAN TOWER.

REV.	DESCRIPTION	BY	DATE
0	PRELIM	LKC	6/6/18

ATC SITE NUMBER:
418609

ATC SITE NAME:
**WOODSTOCK
RELO CT**

SITE ADDRESS:
87 WEST QUASSET ROAD
WOODSTOCK, CT 06281

THIS IS TO CERTIFY THAT THE UNDERSIGNED AT THE REQUEST AND FOR THE EXCLUSIVE USE OF AMERICAN TOWER CORPORATION HAS PERFORMED THIS AS-BUILT SURVEY OF THE ATC LEASE AREA ONLY, FROM THE RECORD SOURCES AND ACTUAL FIELD SURVEY ON MAY 29, 2018 IN ACCORDANCE WITH THE MINIMUM STANDARDS FOR PROPERTY BOUNDARY SURVEYS. ALL LINEAR AND ANGULAR VALUES SHOWN ARE BASED UPON DEED OR RECORD INFORMATION UNLESS OTHERWISE NOTED.

DATE OF PLAT OR MAP: JUNE 6, 2018

THIS CERTIFICATION APPLIES TO THE TOWER LEASE AREA AND IMPROVEMENTS WITH THE EASEMENT AREAS AS SHOWN HEREON.

TIMOTHY R. DURR
PLS #70198
IN THE STATE OF CONNECTICUT
FOR THE BENEFIT AND USE OF
LMS SURVEYING, LTD


STATE OF CONNECTICUT
TIMOTHY R. DURR
70198
LICENSED
LAND SURVEYOR

LMS SURVEYING LTD
Professional Commercial & Residential Land Surveys
P.O. Box 65 • Sharon Center • OH • 44274
330.329.6812 | Surveys@LMSurveying.com

DRAWN BY:	LKC
APPROVED BY:	TRD
DATE DRAWN:	06/06/2018
JOB NO:	B-180477

AS-BUILT/TITLE AND
BOUNDARY PLAN

SHEET NUMBER: 1 OF 2	REVISION:
V-101	0



NOTES

1. CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS.
2. ANTENNA AND MW DISH SPECIFICATIONS REFER TO ANTENNA SCHEDULE AND TO FINAL CONSTRUCTION RFDS FOR ALL RF DETAILS.
3. EXISTING EQUIPMENT AND FENCE OMITTED FOR CLARITY.


(1) PROPOSED DISH WIRELESS, L.L.C. HYBRID CABLE ROUTED INSIDE POLE SHAFT (SEE STRUCTURAL ANALYSIS)

PROPOSED DISH Wireless L.L.C. ICE BRIDGE
PROPOSED DISH Wireless L.L.C. EQUIPMENT ON PROPOSED STEEL PLATFORM
PROPOSED DISH Wireless L.L.C. GPS UNIT
EXISTING ENTRY PORT
EXISTING TOWER
BOTTOM EL. @ 6" AGL

EXISTING HIGHEST APPURTENANCE
TOP EL. @ 157'-3" AGL
EXISTING TOWER
TOP EL. @ 149'-0" AGL
EXISTING PANEL ANTENNAS
RAD CENTER @ 148'-0" AGL
EXISTING PANEL ANTENNAS
RAD CENTER @ 138'-0" AGL
(3) PROPOSED DISH Wireless L.L.C. ANTENNAS
RAD CENTER @ 127'-0" AGL
EXISTING DISH Wireless L.L.C. EXIT PORT
RAD CENTER @ 125'-6" AGL



ANTENNA LAYOUT




2

SECTOR POS.	ANTENNA					TRANSMISSION CABLE FEED LINE TYPE AND LENGTH	RRH			OVP
	EXISTING OR PROPOSED	MANUFACTURER - MODEL NUMBER	TECH	AZIMUTH	RAD CENTER		MANUFACTURER - MODEL NUMBER	TECH	POS.	
A1	--	--	--	--	--	(1) HIGH-CAPACITY HYBRID CABLE (155' LONG)	TA08025-B604	5G	A2	(1) RAYCAP RDIDC-9181-PF-48
A2	PROPOSED	COMMSCOPE - FFV-65B-R2	5G	0°	127'-0"		TA08025-B605	5G	A2	
A3	--	--	--	--	--		--	--	--	
B1	--	--	--	--	--	SHARED W/ALPHA	TA08025-B604	5G	B2	SHARED W/ALPHA
B2	PROPOSED	COMMSCOPE - FFV-65B-R2	5G	120°	127'-0"		TA08025-B605	5G	B2	
B3	--	--	--	--	--		--	--	--	
C1	--	--	--	--	--	SHARED W/ALPHA	TA08025-B604	5G	C2	SHARED W/ALPHA
C2	PROPOSED	COMMSCOPE - FFV-65B-R2	5G	240°	127'-0"		TA08025-B605	5G	C2	
C3	--	--	--	--	--		--	--	--	

- NOTES
1. CONTRACTOR TO REFER TO FINAL CONSTRUCTION RFDS FOR ALL RF DETAILS.
 2. ANTENNA AND RRH MODELS MAY CHANGE DUE TO EQUIPMENT AVAILABILITY. ALL EQUIPMENT CHANGES MUST BE APPROVED AND REMAIN IN COMPLIANCE WITH THE PROPOSED DESIGN AND STRUCTURAL ANALYSES.

PROPOSED NORTH ELEVATION



1

ANTENNA SCHEDULE

NO SCALE

3

dish
wireless.

5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120


AMERICAN TOWER®
A.T. ENGINEERING SERVICE, PLLC
3500 REGENCY PARKWAY
SUITE 100
CARY, NC 27518
PHONE: (919) 468-0112

DRAWN BY: AP
CHECKED BY: SRF
APPROVED BY: SRF

RFDS REV #: ----

CONSTRUCTION
DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
0	01/05/2022	ISSUED FOR CONSTRUCTION



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.


A&E PROJECT NUMBER
418609-13733434_D3

DISH Wireless L.L.C.
PROJECT INFORMATION
BOBOS00030A
87 WEST QUASSET ROAD
WOODSTOCK, CT 06281

SHEET TITLE
ELEVATION, ANTENNA
LAYOUT AND SCHEDULE


SHEET NUMBER

A-2



PLATFORM EQUIPMENT PLAN


1



PLATFORM DETAIL

NO SCALE

2



H-FRAME DETAIL


NO SCALE

3

NOT USED

NO SCALE

4



H-FRAME EQUIPMENT ELEVATION

12" 9" 6" 3" 0 1' 2' 1"=1'-0"

5



5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



DRAWN BY: AP CHECKED BY: SRF APPROVED BY: SRF

RFDS REV #: ---

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
0	01/05/2022	ISSUED FOR CONSTRUCTION



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

A&E PROJECT NUMBER
418609-13733434_D3

DISH Wireless L.L.C.
PROJECT INFORMATION
BOBOS00030A
87 WEST QUASSET ROAD
WOODSTOCK, CT 06281

SHEET TITLE
EQUIPMENT PLATFORM
AND H-FRAME DETAILS

SHEET NUMBER
A-3

CHARLES INDUSTRY HEX CUBE-PM639155N4

DIMENSIONS (HxWxD)	74"x32"x32"
POWER PLANT	-48VDC ABB/600W
TOTAL WEIGHT (EMPTY)	408 lbs

PLAN

BACK

SIDE

FRONT

CABINET DETAIL

NO SCALE

1

RAYCAP PPC RDIAC-2465-P-240-MTS

ENCLOSURE DIMENSIONS (HxWxD)	39"x22.855"x12.593
WEIGHT:	80 lbs
OPERATING AC VOLTAGE	240/120 1 PHASE 3W+G

TOP

BACK

SIDE

FRONT

SIDE

POWER PROTECTION CABINET (PPC) DETAIL

NO SCALE

2

SQUARE D SAFETY SWITCHES D224NRB

ENCLOSURE DIM (HxWxD)	29.25"x19.00"x8.50"
ENCLOSURE TYPE	NEMA 3R RAINPROOF
UL LISTED	FILE E-2875

SIDE

FRONT

SAFETY SWITCH DETAIL

NO SCALE

3

EATON METER SOCKET UNRRS213BEUSE

METER SOCKET TYPE	RING
ENCLOSURE DIM (HxWxD)	16"x12"x6"
MAIN AMPERE RATING	200A
WEIGHT	18 LBS

PLAN

SIDE

BACK

FRONT

METER SOCKET DETAIL

NO SCALE

4

CIENA 3931 FIBER NID ENCLOSURE

DIMENSIONS (HxWxD)	17"x16.8"x7"
WEIGHT	28.6 lbs

TOP

SIDE

FRONT

FIBER NID ENCLOSURE DETAIL

NO SCALE

5

CHARLES CFIT-PF2020DSH1 FIBER TELCO ENCLOSURE

ENCLOSURE DIMS (HxWxD)	20"x20"x9"
ENCLOSURE WEIGHT	20 lbs
MOUNTING	WALL
COMPLIANCE	TYPE 4

SIDE

BACK

FRONT

FIBER TELCO ENCLOSURE DETAIL

NO SCALE

6

COMMSCOPE WB-K110-B WAVEGUIDE BRIDGE KIT

DIMENSIONS (HxL)	160"x10'
WEIGHT/ VOLUME	325.0 LBS
CABLE RUN (QTY)	12

INCLUDED PRODUCTS:

WB-T12-3 TRAPEZE KIT, 3 RUNGS

WB-LB12-3 SUPPORT BRACKET

MF-130 DIRECT BURIAL PIPE COLUMN, 13'-4"

TRAPEZE KIT (WB-T12-3)

SUPPORT BRACKET (WB-LB12-3)

TRAPEZE KIT (WB-T12-3)

3.5" DIA GALV SCH 40 PIPE (SPACED 9'-0" MAX) (MF-130)

SUPPORT BRACKET (WB-LB12-3)

TRAPEZE KIT (WB-T12-3)

3.5" DIA GALV SCH 40 PIPE (SPACED 9'-0" MAX) (MF-130)

PLAN

FRONT

SIDE

ICE BRIDGE DETAIL

NO SCALE

7

FINISH SLOPE TO DRAIN

A-A

PROPOSED 3.5" DIA. SCH 40 PIPE GALVANIZED

PROPOSED 1'-6" DIA. CONCRETE PIER (TYP)

CONCRETE PIER

3" DIA SCH 40 PIPE

18" DIA DRILLED PIER FOUNDATION

A-A SECTION

1'-6"

TYPICAL ICE BRIDGE CONCRETE PIER DETAIL

NO SCALE

8

PROPOSED ICE BRIDGE

PROPOSED HYBRID CABLE

PROPOSED CABLE CLAMP @ 3'-0" O.C.

EXISTING ENTRY PORT

EXISTING MONOPOLE

8' MIN.

HYBRID CABLE RUN

NO SCALE

9

dish

wireless.

5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120


AMERICAN TOWER

A.T. ENGINEERING SERVICE, PLLC

3500 REGENCY PARKWAY
SUITE 100
CARY, NC 27518
PHONE: (919) 468-0112

DRAWN BY:	CHECKED BY:	APPROVED BY:
AP	SRF	SRF
RFDS REV #:		

CONSTRUCTION DOCUMENTS		
SUBMITTALS		
REV	DATE	DESCRIPTION
0	01/05/2022	ISSUED FOR CONSTRUCTION



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.


A&E PROJECT NUMBER
418609-13733434_D3

DISH Wireless L.L.C.
PROJECT INFORMATION
BOBOS00030A
87 WEST QUASSET ROAD
WOODSTOCK, CT 06281


SHEET TITLE
EQUIPMENT DETAILS

SHEET NUMBER
A-4


PCTEL GPSGL-TMG-SPI-40NCB	
DIMENSIONS (DIAxH) MM/INCH	81x184mm 3.2"x7.25"
WEIGHT W/ACCESSORIES	075 lbs
CONNECTOR	N-FEMALE
FREQUENCY RANGE	1590 ± 30MHz





TOP



BACK



SIDE



GPS DETAIL

NO SCALE

1

GPS MINIMUM SKY VIEW REQUIREMENTS

NO SCALE

2

CABLES UNLIMITED HYBRID CABLE
MINIMUM BEND RADIUSES

NO SCALE

3

NOT USED

NO SCALE

4

NOT USED

NO SCALE

5

NOT USED

NO SCALE

6

NOT USED

NO SCALE

7

NOT USED

NO SCALE

8

NOT USED

NO SCALE

9

dish
wireless.

5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120

AMERICAN TOWER®
A.T. ENGINEERING SERVICE, PLLC
3500 REGENCY PARKWAY
SUITE 100
CARY, NC 27518
PHONE: (919) 468-0112

DRAWN BY: CHECKED BY: APPROVED BY:

AP


SRF

SRF

RFDS REV #: ----

**CONSTRUCTION
DOCUMENTS**

SUBMITTALS		
REV	DATE	DESCRIPTION
0	01/05/2022	ISSUED FOR CONSTRUCTION



IT IS A VIOLATION OF LAW FOR ANY PERSON,
UNLESS THEY ARE ACTING UNDER THE DIRECTION
OF A LICENSED PROFESSIONAL ENGINEER,
TO ALTER THIS DOCUMENT.

A&E PROJECT NUMBER
418609-13733434_D3


DISH Wireless L.L.C.
PROJECT INFORMATION
BOBOS00030A
87 WEST QUASSET ROAD
WOODSTOCK, CT 06281

SHEET TITLE
EQUIPMENT DETAILS


SHEET NUMBER

A-5


FUJITSU DUAL BAND TA08025-B604	
DIMENSIONS (HxWxD)	14.9"x15.7"x7.8"
WEIGHT	63.9 lbs
CONNECTOR TYPE	4.3-10 RF CONNECTOR
POWER SUPPLY	DC -58~-36V




PLAN



BACK




SIDE




FRONT


FUJITSU TRIPLE BAND TA08025-B605	
DIMENSIONS (HxWxD)	14.9"x15.7"x9"
WEIGHT	74.95 lbs
CONNECTOR TYPE	4.3-10 RF CONNECTOR
POWER SUPPLY	DC -58~-36V




PLAN



BACK




SIDE




FRONT

SABRE DOUBLE Z-BRACKET G10123155	
DIMENSIONS (HxWxD) (1 BRACKET)	5"x20"x1-13/16"
WEIGHT (FULL ASSEMBLY)	35.79 lbs
PACKAGE QUANTITY	4

#	DESCRIPTION
1	PLATE, CHANNEL BRACKET
2	RRH Z BRACKET, 3/16"
3	THREADED ROD ASSEMBLY 1/2"x12"



NOTE:
OR DISH Wireless L.L.C.
APPROVED EQUIVALENT



RRH DETAIL

NO SCALE

1

RRH DETAIL

NO SCALE

2

RRH MOUNT DETAIL

NO SCALE

3

COMMSCOPE FFVV-65B-R2	
DIMENSIONS (HxWxD)(MM/IN)	1828x498x197 72"x19.6"x7.8"
RF CONNECTOR INTERFACE	4.3-10 FEMALE
WEIGHT	70.8 lbs
WEIGHT WITH BRACKETS	98.1 lbs



PLAN



BACK



SIDE



FRONT

ANTENNA DETAIL

NO SCALE

4

NOT USED

NO SCALE

5

NOT USED


NO SCALE

6


RAYCAP RDIDC-9181-PF-48 DC SURGE PROTECTION (OVP)	
DIMENSIONS (HxWxD)	18.98"x14.39"x8.15"
WEIGHT	21.82 LBS




PLAN



SIDE



BACK




FRONT

SURGE SUPPRESSION DETAIL (OVP)

NO SCALE


7

COMMSCOPE XP-2040 CROSSOVER PLATE	
DIMENSIONS (HxW)	10"x12"
WEIGHT	11.023 LBS



PLAN
U-BOLT

SIDE
U-BOLT



CROSSOVER PLATE
OPTION OF EITHER
SQUARE OR CIRCULAR
U-BOLT



RRH/OVP MOUNT DETAIL

NO SCALE

8

COMMSCOPE MC-PK8-DSH	
FACE WIDTH	96"
WEIGHT	1373.08 lbs
NOTE: 15" TO 38" O.D.	

NOTE:
OR DISH Wireless L.L.C.
APPROVED EQUIVALENT



ANTENNA PLATFORM DETAIL

NO SCALE

9

dish
wireless.

5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120

AMERICAN TOWER
A.T. ENGINEERING SERVICE, PLLC
3500 REGENCY PARKWAY
SUITE 100
CARY, NC 27518
PHONE: (919) 468-0112


DRAWN BY: CHECKED BY: APPROVED BY:

AP SRF SRF

RFDS REV #: ----

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
0	01/05/2022	ISSUED FOR CONSTRUCTION



IT IS A VIOLATION OF LAW FOR ANY PERSON,
UNLESS THEY ARE ACTING UNDER THE DIRECTION
OF A LICENSED PROFESSIONAL ENGINEER,
TO ALTER THIS DOCUMENT.


A&E PROJECT NUMBER
418609-13733434_D3

DISH Wireless L.L.C.
PROJECT INFORMATION
BOBOS00030A
87 WEST QUASSET ROAD
WOODSTOCK, CT 06281


SHEET TITLE
EQUIPMENT DETAILS

SHEET NUMBER

A-6



UTILITY ROUTE PLAN



1

NOTES

1. CONTRACTOR MUST VERIFY THAT THE PROPOSED UTILITY ROUTES ARE WITHIN AMERICAN TOWER'S EASEMENT.
2. ANTENNAS AND MOUNTS OMITTED FOR CLARITY.
3. GC TO REFER TO FINAL UTILITY COORDINATION DOCUMENT FOR ALL MEET ME POINTS AND ROUTING DETAILS.


DC POWER WIRING SHALL BE COLOR CODED AT EACH END FOR IDENTIFYING +24V AND -48V CONDUCTORS. RED MARKINGS SHALL IDENTIFY +24V AND BLUE MARKINGS SHALL IDENTIFY -48V.

1. CONTRACTOR SHALL INSPECT THE EXISTING CONDITIONS PRIOR TO SUBMITTING A BID. ANY QUESTIONS ARISING DURING THE BID PERIOD IN REGARDS TO THE CONTRACTOR'S FUNCTIONS, THE SCOPE OF WORK, OR ANY OTHER ISSUE RELATED TO THIS PROJECT SHALL BE BROUGHT UP DURING THE BID PERIOD WITH THE PROJECT MANAGER FOR CLARIFICATION, NOT AFTER THE CONTRACT HAS BEEN AWARDED.
2. ALL ELECTRICAL WORK SHALL BE DONE IN ACCORDANCE WITH CURRENT NATIONAL ELECTRICAL CODES AND ALL STATE AND LOCAL CODES, LAWS, AND ORDINANCES. PROVIDE ALL COMPONENTS AND WIRING SIZES AS REQUIRED TO MEET NEC STANDARDS.
3. LOCATION OF EQUIPMENT, CONDUIT AND DEVICES SHOWN ON THE DRAWINGS ARE APPROXIMATE AND SHALL BE COORDINATED WITH FIELD CONDITIONS PRIOR TO CONSTRUCTION.
4. CONDUIT ROUGH-IN SHALL BE COORDINATED WITH THE MECHANICAL EQUIPMENT TO AVOID LOCATION CONFLICTS. VERIFY WITH THE MECHANICAL EQUIPMENT CONTRACTOR AND COMPLY AS REQUIRED.
5. CONTRACTOR SHALL PROVIDE ALL BREAKERS, CONDUITS AND CIRCUITS AS REQUIRED FOR A COMPLETE SYSTEM.
6. CONTRACTOR SHALL PROVIDE PULL BOXES AND JUNCTION BOXES AS REQUIRED BY THE NEC ARTICLE 314.
7. CONTRACTOR SHALL PROVIDE ALL STRAIN RELIEF AND CABLE SUPPORTS FOR ALL CABLE ASSEMBLIES. INSTALLATION SHALL BE IN ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS AND RECOMMENDATIONS.
8. ALL DISCONNECTS AND CONTROLLING DEVICES SHALL BE PROVIDED WITH ENGRAVED PHENOLIC NAMEPLATES INDICATING EQUIPMENT CONTROLLED, BRANCH CIRCUITS INSTALLED ON, AND PANEL FIELD LOCATIONS FED FROM.
9. INSTALL AN EQUIPMENT GROUNDING CONDUCTOR IN ALL CONDUITS PER THE SPECIFICATIONS AND NEC 250. THE EQUIPMENT GROUNDING CONDUCTORS SHALL BE BONDED AT ALL JUNCTION BOXES, PULL BOXES, AND ALL DISCONNECT SWITCHES, AND EQUIPMENT CABINETS.
10. ALL NEW MATERIAL SHALL HAVE A U.L. LABEL.
11. PANEL SCHEDULE LOADING AND CIRCUIT ARRANGEMENTS REFLECT POST-CONSTRUCTION EQUIPMENT.
12. CONTRACTOR SHALL BE RESPONSIBLE FOR AS-BUILT PANEL SCHEDULE AND SITE DRAWINGS.
13. ALL TRENCHES IN COMPOUND TO BE HAND DUG

ELECTRICAL NOTES

NO SCALE

2



EXISTING SURVEY (BY OTHERS)

NO SCALE

3

dish
wireless.

5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120

AMERICAN TOWER®
A.T. ENGINEERING SERVICE, PLLC
3500 REGENCY PARKWAY
SUITE 100
CARY, NC 27518
PHONE: (919) 468-0112

DRAWN BY: AP
CHECKED BY: SRF
APPROVED BY: SRF

RFDS REV #: ----

CONSTRUCTION
DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
0	01/05/2022	ISSUED FOR CONSTRUCTION



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

A&E PROJECT NUMBER
418609-13733434_D3


DISH Wireless L.L.C.
PROJECT INFORMATION
BOBOS00030A
87 WEST QUASSET ROAD
WOODSTOCK, CT 06281

SHEET TITLE
ELECTRICAL/FIBER ROUTE
PAN AND NOTES

SHEET NUMBER

E-1



CARLON EXPANSION FITTINGS				
COUPLING END PART#	MALE TERMINAL ADAPTER END PART#	SIZE	STD CTN QTY.	TRAVEL LENGTH
E945D	E945DX	1/2"	20	4"
E945E	E945EX	3/4"	15	4"
E945F	E945FX	1"	10	4"
E945G	E945GX	1 1/4"	5	4"
E945H	E945HX	1 1/2"	5	4"
E945J	E945JX	2"	15	8"
E945K	E945KX	2 1/2"	10	8"
E945L	E945LX	3"	10	8"
E945M	E945MX	3 1/2"	5	8"
E945N	E945NX	4"	5	8"
E945P	E945PX	5"	1	8"
E945R	E945RX	6"	1	8"



NOTE: CONTRACTOR TO INSTALL EXPANSION FITTING SLIP JOINT AT METER CENTER CONDUIT TERMINATION, AS PER LOCAL UTILITY POLICY, ORDINANCE AND/OR SPECIFIED REQUIREMENT.

TRENCHING NOTES

- CONTRACTOR SHALL RESTORE THE TRENCH TO ITS ORIGINAL CONDITIONS BY EITHER SEEDING OR SODDING GRASS AREAS, OR REPLACING ASPHALT OR CONCRETE AREAS TO ITS ORIGINAL CROSS SECTION.
- TRENCHING SAFETY; INCLUDING, BUT NOT LIMITED TO SOIL CLASSIFICATION, SLOPING, AND SHORING, SHALL BE GOVERNED BY THE CURRENT OSHA TRENCHING AND EXCAVATION SAFETY STANDARDS.
- ALL CONDUITS SHALL BE INSTALLED IN COMPLIANCE WITH THE CURRENT NATIONAL ELECTRIC CODE (NEC) OR AS REQUIRED BY THE LOCAL JURISDICTION, WHICHEVER IS THE MOST STRINGENT.



EXPANSION JOINT DETAIL

NO SCALE

1

TYPICAL UNDERGROUND TRENCH DETAIL


NO SCALE

2

DARK TELCO BOX – INTERIOR WIRING LAYOUT

NO SCALE

3



LIT TELCO BOX – INTERIOR WIRING LAYOUT (OPTIONAL)

NO SCALE

4

NOT USED

NO SCALE

5

NOT USED

NO SCALE

6

NOT USED

NO SCALE

7

NOT USED

NO SCALE

8

NOT USED

NO SCALE

9

dish wireless.

5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120

AMERICAN TOWER®
A.T. ENGINEERING SERVICE, PLLC
3500 REGENCY PARKWAY
SUITE 100
CARY, NC 27518
PHONE: (919) 468-0112

DRAWN BY: CHECKED BY: APPROVED BY:

AP SRF SRF

RFDS REV #: ----

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
0	01/05/2022	ISSUED FOR CONSTRUCTION



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.



A&E PROJECT NUMBER
418609-13733434_D3

DISH Wireless L.L.C.
PROJECT INFORMATION
BOBOS00030A
87 WEST QUASSET ROAD
WOODSTOCK, CT 06281

SHEET TITLE
ELECTRICAL DETAILS

SHEET NUMBER

E-2



NOTE:
BRANCH CIRCUIT WIRING SUPPLYING RECTIFIERS ARE TO BE RATED UL1015, 105°C, 600V, AND PVC INSULATED, IN THE SIZES SHOWN IN THE ONE-LINE DIAGRAM. CONTRACTOR MAY SUBSTITUTE UL1015 WIRE FOR THWN-2 FOR CONVENIENCE OUTLET BRANCH CIRCUIT.

BREAKERS REQUIRED:
(4) 30A, 2P BREAKER - SQUARE D P/N:Q0230
(2) 15A, 1P BREAKER - SQUARE D P/N:Q0115

PPC ONE-LINE DIAGRAM

NO SCALE 1

PROPOSED CHARLES PANEL SCHEDULE											
LOAD SERVED	VOLT AMPS (WATTS)		TRIP	CKT #	PHASE	CKT #	TRIP	VOLT AMPS (WATTS)		LOAD SERVED	
	L1	L2						L1	L2		
PPC GFCI OUTLET	180		15A	1	A	2	30A	2880		ABB/GE INFINITY RECTIFIER 1	
CHARLES GFCI OUTLET		180	15A	3	B	4			2880	ABB/GE INFINITY RECTIFIER 2	
-SPACE-				5	A	6	30A	2880		ABB/GE INFINITY RECTIFIER 3	
-SPACE-				7	B	8			2880	ABB/GE INFINITY RECTIFIER 4	
-SPACE-				9	A	10	30A	2880		-SPACE-	
-SPACE-				11	B	12			2880	-SPACE-	
-SPACE-				13	A	14	30A	2880		-SPACE-	
-SPACE-				15	B	16			2880	-SPACE-	
-SPACE-				17	A	18				-SPACE-	
-SPACE-				19	B	20				-SPACE-	
-SPACE-				21	A	22				-SPACE-	
-SPACE-				23	B	24				-SPACE-	
VOLTAGE AMPS 180 180 11520 11520											
200A MCB, 10, 24 SPACE, 120/240V											
MB RATING: 65,000 AIC											
L1 L2 VOLTAGE AMPS											
11700 11700 98 98 AMPS											
98 123 MAX AMPS											
123 MAX 125%											

PANEL SCHEDULE

NO SCALE 2

NOT USED

NO SCALE 3

5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120

A.T. ENGINEERING SERVICE, PLLC
3500 REGENCY PARKWAY
SUITE 100
CARY, NC 27518
PHONE: (919) 468-0112

DRAWN BY:	CHECKED BY:	APPROVED BY:
AP	SRF	SRF
RFDS REV #:		----

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
0	01/05/2022	ISSUED FOR CONSTRUCTION


IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

A&E PROJECT NUMBER
418609-13733434_D3

DISH Wireless L.L.C.
PROJECT INFORMATION
BOBOS00030A
87 WEST QUASSET ROAD
WOODSTOCK, CT 06281

SHEET TITLE
ELECTRICAL ONE-LINE
AND PANEL SCHEDULE


SHEET NUMBER
E-3



TYPICAL EQUIPMENT GROUNDING PLAN

NO SCALE

1



TYPICAL ANTENNA GROUNDING PLAN

NO SCALE

2

● EXOTHERMIC CONNECTION

■ MECHANICAL CONNECTION

GROUND BUS BAR

GROUND ROD

TEST GROUND ROD WITH INSPECTION SLEEVE

----- #2 AWG STRANDED & INSULATED

----- #2 AWG SOLID COPPER TINNED

▲ BUSS BAR INSULATOR

GROUNDING LEGEND

1. GROUNDING IS SHOWN DIAGRAMMATICALLY ONLY.

2. CONTRACTOR SHALL GROUND ALL EQUIPMENT AS A COMPLETE SYSTEM. GROUNDING SHALL BE IN COMPLIANCE WITH NEC SECTION 250 AND DISH Wireless L.L.C. GROUNDING AND BONDING REQUIREMENTS AND MANUFACTURER'S SPECIFICATIONS.

3. ALL GROUND CONDUCTORS SHALL BE COPPER; NO ALUMINUM CONDUCTORS SHALL BE USED.

GROUNDING KEY NOTES

A

EXTERIOR GROUND RING: #2 AWG SOLID COPPER, BURIED AT A DEPTH OF AT LEAST 30 INCHES BELOW GRADE, OR 6 INCHES BELOW THE FROST LINE AND APPROXIMATELY 24 INCHES FROM THE EXTERIOR WALL OR FOOTING.

B

TOWER GROUND RING: THE GROUND RING SYSTEM SHALL BE INSTALLED AROUND AN ANTENNA TOWER'S LEGS, AND/OR GUY ANCHORS. WHERE SEPARATE SYSTEMS HAVE BEEN PROVIDED FOR THE TOWER AND THE BUILDING, AT LEAST TWO BONDS SHALL BE MADE BETWEEN THE TOWER RING GROUND SYSTEM AND THE BUILDING RING GROUND SYSTEM USING MINIMUM #2 AWG SOLID COPPER CONDUCTORS.

C

INTERIOR GROUND RING: #2 AWG STRANDED GREEN INSULATED COPPER CONDUCTOR EXTENDED AROUND THE PERIMETER OF THE EQUIPMENT AREA. ALL NON-TELECOMMUNICATIONS RELATED METALLIC OBJECTS FOUND WITHIN A SITE SHALL BE GROUNDED TO THE INTERIOR GROUND RING WITH #6 AWG STRANDED GREEN INSULATED CONDUCTOR.

D

BOND TO INTERIOR GROUND RING: #2 AWG SOLID TINNED COPPER WIRE PRIMARY BONDS SHALL BE PROVIDED AT LEAST AT FOUR POINTS ON THE INTERIOR GROUND RING, LOCATED AT THE CORNERS OF THE BUILDING.

E

GROUND ROD: UL LISTED COPPER CLAD STEEL. MINIMUM 5/8" DIAMETER BY EIGHT FEET LONG. GROUND RODS SHALL BE INSTALLED WITH INSPECTION SLEEVES. GROUND RODS SHALL BE DRIVEN TO THE DEPTH OF GROUND RING CONDUCTOR.

F

CELL REFERENCE GROUND BAR: POINT OF GROUND REFERENCE FOR ALL COMMUNICATIONS EQUIPMENT FRAMES. ALL BONDS ARE MADE WITH #2 AWG UNLESS NOTED OTHERWISE STRANDED GREEN INSULATED COPPER CONDUCTORS. BOND TO GROUND RING WITH (2) #2 SOLID TINNED COPPER CONDUCTORS.

G

HATCH PLATE GROUND BAR: BOND TO THE INTERIOR GROUND RING WITH TWO #2 AWG STRANDED GREEN INSULATED COPPER CONDUCTORS. WHEN A HATCH-PLATE AND A CELL REFERENCE GROUND BAR ARE BOTH PRESENT, THE CRGB MUST BE CONNECTED TO THE HATCH-PLATE AND TO THE INTERIOR GROUND RING USING (2) TWO #2 AWG STRANDED GREEN INSULATED COPPER CONDUCTORS EACH.

H

EXTERIOR CABLE ENTRY PORT GROUND BARS: LOCATED AT THE ENTRANCE TO THE CELL SITE BUILDING. BOND TO GROUND RING WITH A #2 AWG SOLID TINNED COPPER CONDUCTORS WITH AN EXOTHERMIC WELD AND INSPECTION SLEEVE.

J

TELCO GROUND BAR: BOND TO BOTH CELL REFERENCE GROUND BAR OR EXTERIOR GROUND RING.

K

FRAME BONDING: THE BONDING POINT FOR TELECOM EQUIPMENT FRAMES SHALL BE THE GROUND BUS THAT IS NOT ISOLATED FROM THE EQUIPMENTS METAL FRAMEWORK.

L

INTERIOR UNIT BONDS: METAL FRAMES, CABINETS AND INDIVIDUAL METALLIC UNITS LOCATED WITH THE AREA OF THE INTERIOR GROUND RING REQUIRE A #6 AWG STRANDED GREEN INSULATED COPPER BOND TO THE INTERIOR GROUND RING.

M

FENCE AND GATE GROUNDING: METAL FENCES WITHIN 7 FEET OF THE EXTERIOR GROUND RING OR OBJECTS BONDED TO THE EXTERIOR GROUND RING SHALL BE BONDED TO THE GROUND RING WITH A #2 AWG SOLID TINNED COPPER CONDUCTOR AT AN INTERVAL NOT EXCEEDING 25 FEET. BONDS SHALL BE MADE AT EACH GATE POST AND ACROSS GATE OPENINGS.

N

EXTERIOR UNIT BONDS: METALLIC OBJECTS, EXTERNAL TO OR MOUNTED TO THE BUILDING, SHALL BE BONDED TO THE EXTERIOR GROUND RING. USING #2 TINNED SOLID COPPER WIRE

P

ICE BRIDGE SUPPORTS: EACH ICE BRIDGE LEG SHALL BE BONDED TO THE GROUND RING WITH #2 AWG BARE TINNED COPPER CONDUCTOR. PROVIDE EXOTHERMIC WELDS AT BOTH THE ICE BRIDGE LEG AND BURIED GROUND RING.

Q

DURING ALL DC POWER SYSTEM CHANGES INCLUDING DC SYSTEM CHANGE OUTS, RECTIFIER REPLACEMENTS OR ADDITIONS, BREAKER DISTRIBUTION CHANGES, BATTERY ADDITIONS, BATTERY REPLACEMENTS AND INSTALLATIONS OR CHANGES TO DC CONVERTER SYSTEMS IT SHALL BE REQUIRED THAT SERVICE CONTRACTORS VERIFY ALL DC POWER SYSTEMS ARE EQUIPPED WITH A MASTER DC SYSTEM RETURN GROUND CONDUCTOR FROM THE DC POWER SYSTEM COMMON RETURN BUS DIRECTLY CONNECTED TO THE CELL SITE REFERENCE GROUND BAR

R

TOWER TOP COLLECTOR BUSS BAR IS TO BE MECHANICALLY BONDED TO PROPOSED ANTENNA MOUNT COLLAR. REFER TO DISH Wireless L.L.C. GROUNDING NOTES.

GROUNDING KEY NOTES

NO SCALE

3

dish

wireless.

5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120

AMERICAN TOWER®

A.T. ENGINEERING SERVICE, PLLC

3500 REGENCY PARKWAY
SUITE 100
CARY, NC 27518
PHONE: (919) 468-0112

DRAWN BY: AP

CHECKED BY: SRF

APPROVED BY: SRF

RFDS REV #:

CONSTRUCTION DOCUMENTS

SUBMITTALS

REV	DATE	DESCRIPTION
0	01/05/2022	ISSUED FOR CONSTRUCTION

STATE OF CONNECTICUT

MUSTAFA RAM

33740

LICENSED PROFESSIONAL ENGINEER


IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

A&E PROJECT NUMBER
418609-13733434_D3


DISH Wireless L.L.C.
PROJECT INFORMATION
BOBOS00030A
87 WEST QUASSET ROAD
WOODSTOCK, CT 06281

SHEET TITLE
GROUNDING PLAN AND NOTES


SHEET NUMBER
G-1




H-FRAME GROUNDING DETAIL NO SCALE 1




TRANSITIONING GROUND DETAIL NO SCALE 4




TYPICAL TEST GROUND ROD WITH INSPECTION SLEEVE NO SCALE 5



TYPICAL GPS UNIT GROUNDING NO SCALE 2



OUTDOOR CABINET GROUNDING NO SCALE 3



TYPICAL GROUND RING TRENCH NO SCALE 6

dish
wireless.

5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120

AMERICAN TOWER
A.T. ENGINEERING SERVICE, PLLC
3500 REGENCY PARKWAY
SUITE 100
CARY, NC 27518
PHONE: (919) 468-0112

DRAWN BY: AP CHECKED BY: SRF APPROVED BY: SRF

RFDS REV #: ----

CONSTRUCTION DOCUMENTS		
SUBMITTALS		
REV	DATE	DESCRIPTION
0	01/05/2022	ISSUED FOR CONSTRUCTION






IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

A&E PROJECT NUMBER
418609-13733434_D3

DISH Wireless L.L.C.
PROJECT INFORMATION
BOBOS00030A
87 WEST QUASSET ROAD
WOODSTOCK, CT 06281

SHEET TITLE
GROUNDING DETAILS

SHEET NUMBER
G-2

<div>1. EXOTHERMIC WELD (2) TWO, #2 AWG BARE TINNED SOLID COPPER CONDUCTORS TO GROUND BAR. ROUTE CONDUCTORS TO BURIED GROUND RING AND PROVIDE PARALLEL EXOTHERMIC WELD.</div> <div>2. ALL EXTERIOR GROUNDING HARDWARE SHALL BE STAINLESS STEEL 3/8" DIAMETER OR LARGER. ALL HARDWARE 18-8 STAINLESS STEEL INCLUDING LOCK WASHERS, COAT ALL SURFACES WITH AN ANTI-OXIDANT COMPOUND BEFORE MATING.</div> <div>3. FOR GROUND BOND TO STEEL ONLY: COAT ALL SURFACES WITH AN ANTI-OXIDANT COMPOUND BEFORE MATING.</div> <div>4. DO NOT INSTALL CABLE GROUNDING KIT AT A BEND AND ALWAYS DIRECT GROUND CONDUCTOR DOWN TO GROUNDING BUS.</div> <div>5. NUT & WASHER SHALL BE PLACED ON THE FRONT SIDE OF THE GROUND BAR AND BOLTED ON THE BACK SIDE.</div> <div>6. ALL GROUNDING PARTS AND EQUIPMENT TO BE SUPPLIED AND INSTALLED BY CONTRACTOR.</div> <div>7. THE CONTRACTOR SHALL BE RESPONSIBLE FOR INSTALLING ADDITIONAL GROUND BAR AS REQUIRED.</div> <div>8. ENSURE THE WIRE INSULATION TERMINATION IS WITHIN 1/8" OF THE BARREL (NO SHINERS).</div>			<div></div>			<div></div>		
TYPICAL GROUNDING NOTES	NO SCALE	1	TYPICAL EXTERIOR TWO HOLE LUG	NO SCALE	2	TYPICAL INTERIOR TWO HOLE LUG	NO SCALE	3
<div></div>								
LUG DETAIL	NO SCALE	4	NOT USED	NO SCALE	5	NOT USED	NO SCALE	6
NOT USED	NO SCALE	7	NOT USED	NO SCALE	8	NOT USED	NO SCALE	9




5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



A.T. ENGINEERING SERVICE, PLLC
3500 REGENCY PARKWAY
SUITE 100
CARY, NC 27518
PHONE: (919) 468-0112

DRAWN BY:	CHECKED BY:	APPROVED BY:
AP	SRF	SRF
RFDS REV #:		----

CONSTRUCTION DOCUMENTS		
SUBMITTALS		
REV	DATE	DESCRIPTION
0	01/05/2022	ISSUED FOR CONSTRUCTION



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

A&E PROJECT NUMBER
418609-13733434_D3

DISH Wireless L.L.C.
PROJECT INFORMATION
BOBOS00030A
87 WEST QUASSET ROAD
WOODSTOCK, CT 06281

SHEET TITLE
GROUNDING DETAILS

SHEET NUMBER
G-3

HYBRID/DISCREET CABLES		3/4" TAPE WIDTHS WITH 3/4" SPACING											
LOW-BAND RRH (600 MHz N71 BASEBAND) + (850 MHz N26 BAND) + (700 MHz N29 BAND) - OPTIONAL PER MARKET ADD FREQUENCY COLOR TO SECTOR BAND (CBRS WILL USE YELLOW BAND)	ALPHA RRH				BETA RRH				GAMMA RRH				
	PORT 1 + SLANT	PORT 2 - SLANT	PORT 3 + SLANT	PORT 4 - SLANT	PORT 1 + SLANT	PORT 2 - SLANT	PORT 3 + SLANT	PORT 4 - SLANT	PORT 1 + SLANT	PORT 2 - SLANT	PORT 3 + SLANT	PORT 4 - SLANT	
	RED	RED	RED	RED	BLUE	BLUE	BLUE	BLUE	GREEN	GREEN	GREEN	GREEN	
	ORANGE	ORANGE	RED	RED	ORANGE	ORANGE	BLUE	BLUE	ORANGE	ORANGE	GREEN	GREEN	
MID-BAND RRH (AWS BANDS N66+N70) ADD FREQUENCY COLOR TO SECTOR BAND (CBRS WILL USE YELLOW BANDS)		WHITE (-) PORT	ORANGE	ORANGE		WHITE (-) PORT	ORANGE	ORANGE		WHITE (-) PORT	ORANGE	ORANGE	
				WHITE (-) PORT				WHITE (-) PORT				WHITE (-) PORT	
	RED	RED	RED	RED	BLUE	BLUE	BLUE	BLUE	GREEN	GREEN	GREEN	GREEN	
	PURPLE	PURPLE	RED	RED	PURPLE	PURPLE	BLUE	BLUE	PURPLE	PURPLE	GREEN	GREEN	
HYBRID/DISCREET CABLES INCLUDE SECTOR BANDS BEING SUPPORTED ALONG WITH FREQUENCY BANDS. EXAMPLE 1 - HYBRID, OR DISCREET, SUPPORTS ALL SECTORS, BOTH LOW-BANDS AND MID-BANDS. EXAMPLE 2 - HYBRID, OR DISCREET, SUPPORTS CBRS ONLY, ALL SECTORS. EXAMPLE 3 - MAIN COAX WITH GROUND MOUNTED RRHs.	EXAMPLE 1		EXAMPLE 2		EXAMPLE 3 COAX #1 (ALPHA)		CANISTER COAX #2 (ALPHA)						
	RED		RED		RED		RED						
	BLUE		BLUE										
	GREEN		GREEN										
FIBER JUMPERS TO RRHs LOW-BAND HHR FIBER CABLES HAVE SECTOR STRIPE ONLY.	LOW BAND RRH		MID BAND RRH		LOW BAND RRH		MID BAND RRH		LOW BAND RRH		MID BAND RRH		
	RED		RED		BLUE		BLUE		GREEN		GREEN		
	ORANGE		PURPLE		ORANGE		PURPLE		ORANGE		PURPLE		
POWER CABLES TO RRHs LOW-BAND RRH POWER CABLES HAVE SECTOR STRIPE ONLY	LOW BAND RRH		MID BAND RRH		LOW BAND RRH		MID BAND RRH		LOW BAND RRH		MID BAND RRH		
	RED		RED		BLUE		BLUE		GREEN		GREEN		
	ORANGE		PURPLE		ORANGE		PURPLE		ORANGE		PURPLE		
RET MOTORS AT ANTENNAS RET CONTROL IS HANDLED BY THE MID-BAND RRH WHEN ONE SET OF RET PORTS EXIST ON ANTENNA. SEPARATE RET CABLES ARE USED WHEN ANTENNA PORTS PROVIDE INPUTS FOR BOTH LOW AND MID BANDS.	ANTENNA 1 MID BAND		ANTENNA 1 LOW BAND		ANTENNA 1 MID BAND		ANTENNA 1 LOW BAND		ANTENNA 1 MID BAND		ANTENNA 1 LOW BAND		
	IN	IN			IN	IN			IN	IN			
	RED	RED			BLUE	BLUE			GREEN	GREEN			
	PURPLE	ORANGE			PURPLE	ORANGE			PURPLE	ORANGE			
MICROWAVE RADIO LINKS LINKS WILL HAVE A 1.5-2 INCH WHITE WRAP WITH THE AZIMUTH COLOR OVERLAPPING IN THE MIDDLE. ADD ADDITIONAL SECTOR COLOR BANDS FOR EACH ADDITIONAL MW RADIO. MICROWAVE CABLES WILL REQUIRE P-TOUCH LABELS INSIDE THE CABINET TO IDENTIFY THE LOCAL AND REMOTE SITE ID's.	FORWARD AZIMUTH OF 0-120 DEGREES		FORWARD AZIMUTH OF 120-240 DEGREES		FORWARD AZIMUTH OF 240-359 DEGREES								
	PRIMARY	SECONDARY	PRIMARY	SECONDARY	PRIMARY	SECONDARY							
	WHITE	WHITE	WHITE	WHITE	WHITE	WHITE	WHITE	WHITE	WHITE	WHITE	WHITE	WHITE	
	RED	RED	BLUE	BLUE	GREEN	GREEN	WHITE	WHITE	GREEN	GREEN	WHITE	WHITE	
NOT USED													

LOW BANDS (N71+N26)
OPTIONAL - (N29)

ORANGE

AWS
(N66+N70+H-BLOCK)

PURPLE

CBRS TECH
(3 GHz)

YELLOW

NEGATIVE SLANT PORT
ON ANT/RRH

WHITE

ALPHA SECTOR

RED

BETA SECTOR

BLUE

GAMMA SECTOR

GREEN

COLOR IDENTIFIER

2

NOT USED

3

NOT USED

4

dish
wireless.

5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



AMERICAN TOWER®
A.T. ENGINEERING SERVICE, PLLC
3500 REGENCY PARKWAY
SUITE 100
CARY, NC 27518
PHONE: (919) 468-0112

DRAWN BY: CHECKED BY: APPROVED BY:

AP

SRF

SRF

RFDS REV #: ----

CONSTRUCTION DOCUMENTS

SUBMITTALS

REV	DATE	DESCRIPTION
0	01/05/2022	ISSUED FOR CONSTRUCTION



IT IS A VIOLATION OF LAW FOR ANY PERSON,
UNLESS THEY ARE ACTING UNDER THE DIRECTION
OF A LICENSED PROFESSIONAL ENGINEER,
TO ALTER THIS DOCUMENT.

A&E PROJECT NUMBER

418609-13733434_D3

DISH Wireless L.L.C.
PROJECT INFORMATION

BOBOS00030A

87 WEST QUASSET ROAD
WOODSTOCK, CT 06281

SHEET TITLE

RF CABLE COLOR CODES

SHEET NUMBER

RF-1

EXOTHERMIC CONNECTION
MECHANICAL CONNECTION
BUSS BAR INSULATOR
CHEMICAL ELECTROLYTIC GROUNDING SYSTEM
TEST CHEMICAL ELECTROLYTIC GROUNDING SYSTEM
EXOTHERMIC WITH INSPECTION SLEEVE
GROUNDING BAR
GROUND ROD
TEST GROUND ROD WITH INSPECTION SLEEVE

SINGLE POLE SWITCH

DUPLEX RECEPTACLE

DUPLEX GFCI RECEPTACLE

FLUORESCENT LIGHTING FIXTURE
(2) TWO LAMPS 48-T8

SMOKE DETECTION (DC)

EMERGENCY LIGHTING (DC)

SECURITY LIGHT W/PHOTOCELL LITHONIA ALXW
LED-1-25A400/51K-SR4-120-PE-DDBTXD

CHAIN LINK FENCE

WOOD/WROUGHT IRON FENCE

WALL STRUCTURE

LEASE AREA

PROPERTY LINE (PL)

SETBACKS

ICE BRIDGE

CABLE TRAY

WATER LINE

UNDERGROUND POWER

UNDERGROUND TELCO

OVERHEAD POWER

OVERHEAD TELCO

UNDERGROUND TELCO/POWER

ABOVE GROUND POWER





ABOVE GROUND TELCO

ABOVE GROUND TELCO/POWER

WORKPOINT

SECTION REFERENCE

DETAIL REFERENCE



LEGEND

AB ANCHOR BOLT
ABV ABOVE
AC ALTERNATING CURRENT
ADDL ADDITIONAL
AFF ABOVE FINISHED FLOOR
AFG ABOVE FINISHED GRADE
AGL ABOVE GROUND LEVEL
AIC AMPERAGE INTERRUPTION CAPACITY
ALUM ALUMINUM
ALT ALTERNATE
ANT ANTENNA
APPROX APPROXIMATE
ARCH ARCHITECTURAL
ATS AUTOMATIC TRANSFER SWITCH
AWG AMERICAN WIRE GAUGE
BATT BATTERY
BLDG BUILDING
BLK BLOCK
BLKG BLOCKING
BM BEAM
BTC BARE TINNED COPPER CONDUCTOR
BOF BOTTOM OF FOOTING
CAB CABINET
CANT CANTILEVERED
CHG CHARGING
CLG CEILING
CLR CLEAR
COL COLUMN
COMM COMMON
CONC CONCRETE
CONSTR CONSTRUCTION
DBL DOUBLE
DC DIRECT CURRENT
DEPT DEPARTMENT
DF DOUGLAS FIR
DIA DIAMETER
DIAG DIAGONAL
DIM DIMENSION
DWG DRAWING
DWL DOWEL
EA EACH
EC ELECTRICAL CONDUCTOR
EL ELEVATION
ELEC ELECTRICAL
EMT ELECTRICAL METALLIC TUBING
ENG ENGINEER
EQ EQUAL
EXP EXPANSION
EXT EXTERIOR
EW EACH WAY
FAB FABRICATION
FF FINISH FLOOR
FG FINISH GRADE
FIF FACILITY INTERFACE FRAME
FIN FINISH(ED)
FLR FLOOR
FDN FOUNDATION
FOC FACE OF CONCRETE
FOM FACE OF MASONRY
FOS FACE OF STUD
FOW FACE OF WALL
FS FINISH SURFACE
FT FOOT
FTG FOOTING
GA GAUGE
GEN GENERATOR
GFCI GROUND FAULT CIRCUIT INTERRUPTER
GLB GLUE LAMINATED BEAM
GLV GALVANIZED
GPS GLOBAL POSITIONING SYSTEM
GND GROUND
GSM GLOBAL SYSTEM FOR MOBILE
HDG HOT DIPPED GALVANIZED
HDR HEADER
HGR HANGER
HVAC HEAT/VENTILATION/AIR CONDITIONING
HT HEIGHT
IGR INTERIOR GROUND RING

IN INCH
INT INTERIOR
LB(S) POUND(S)
LF LINEAR FEET
LTE LONG TERM EVOLUTION
MAS MASONRY
MAX MAXIMUM
MB MACHINE BOLT
MECH MECHANICAL
MFR MANUFACTURER
MGB MASTER GROUND BAR
MIN MINIMUM
MISC MISCELLANEOUS
MTL METAL
MTS MANUAL TRANSFER SWITCH
MW MICROWAVE
NEC NATIONAL ELECTRIC CODE
NM NEWTON METERS
NO. NUMBER
NUMBER
NTS NOT TO SCALE
OC ON-CENTER
OSHA OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION
OPNG OPENING
P/C PRECAST CONCRETE
PCS PERSONAL COMMUNICATION SERVICES
PCU PRIMARY CONTROL UNIT
PRC PRIMARY RADIO CABINET
PP POLARIZING PRESERVING
PSF POUNDS PER SQUARE FOOT
PSI POUNDS PER SQUARE INCH
PT PRESSURE TREATED
PWR POWER CABINET
QTY QUANTITY
RAD RADIUS
RECT RECTIFIER
REF REFERENCE
REINF REINFORCEMENT
REQ'D REQUIRED
RET REMOTE ELECTRIC TILT
RF RADIO FREQUENCY
RMC RIGID METALLIC CONDUIT
RRH REMOTE RADIO HEAD
RRU REMOTE RADIO UNIT
RWY RACEWAY
SCH SCHEDULE
SHT SHEET
SIAD SMART INTEGRATED ACCESS DEVICE
SIM SIMILAR
SPEC SPECIFICATION
SQ SQUARE
SS STAINLESS STEEL
STD STANDARD
STL STEEL
TEMP TEMPORARY
THK THICKNESS
TMA TOWER MOUNTED AMPLIFIER
TN TOE NAIL
TOA TOP OF ANTENNA
TOC TOP OF CURB
TOF TOP OF FOUNDATION
TOP TOP OF PLATE (PARAPET)
TOS TOP OF STEEL
TOW TOP OF WALL
TVSS TRANSIENT VOLTAGE SURGE SUPPRESSION
TYP TYPICAL
UG UNDERGROUND
UL UNDERWRITERS LABORATORY
UNO UNLESS NOTED OTHERWISE
UMTS UNIVERSAL MOBILE TELECOMMUNICATIONS SYSTEM
UPS UNINTERRUPTIBLE POWER SYSTEM (DC POWER PLANT)
VIF VERIFIED IN FIELD
W WIDE
W/ WITH
WD WOOD
WP WEATHERPROOF
WT WEIGHT

ABBREVIATIONS

dish
wireless.

5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120

AMERICAN TOWER®
A.T. ENGINEERING SERVICE, PLLC
3500 REGENCY PARKWAY
SUITE 100
CARY, NC 27518
PHONE: (919) 468-0112


DRAWN BY: CHECKED BY: APPROVED BY:

AP SRF SRF

RFDS REV #: ----

CONSTRUCTION
DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
0	01/05/2022	ISSUED FOR CONSTRUCTION



IT IS A VIOLATION OF LAW FOR ANY PERSON,
UNLESS THEY ARE ACTING UNDER THE DIRECTION
OF A LICENSED PROFESSIONAL ENGINEER,
TO ALTER THIS DOCUMENT.

A&E PROJECT NUMBER

418609-13733434_D3

DISH Wireless L.L.C.
PROJECT INFORMATION
BOBOS00030A
87 WEST QUASSET ROAD
WOODSTOCK, CT 06281

SHEET TITLE
LEGEND AND
ABBREVIATIONS

SHEET NUMBER

GN-1

SITE ACTIVITY REQUIREMENTS:

1. NOTICE TO PROCEED – NO WORK SHALL COMMENCE PRIOR TO CONTRACTOR RECEIVING A WRITTEN NOTICE TO PROCEED (NTP) AND THE ISSUANCE OF A PURCHASE ORDER. PRIOR TO ACCESSING/ENTERING THE SITE YOU MUST CONTACT THE DISH Wireless L.L.C. AND TOWER OWNER NOC & THE DISH Wireless L.L.C. AND TOWER OWNER CONSTRUCTION MANAGER.
2. "LOOK UP" – DISH Wireless L.L.C. AND TOWER OWNER SAFETY CLIMB REQUIREMENT:

THE INTEGRITY OF THE SAFETY CLIMB AND ALL COMPONENTS OF THE CLIMBING FACILITY SHALL BE CONSIDERED DURING ALL STAGES OF DESIGN, INSTALLATION, AND INSPECTION. TOWER MODIFICATION, MOUNT REINFORCEMENTS, AND/OR EQUIPMENT INSTALLATIONS SHALL NOT COMPROMISE THE INTEGRITY OR FUNCTIONAL USE OF THE SAFETY CLIMB OR ANY COMPONENTS OF THE CLIMBING FACILITY ON THE STRUCTURE. THIS SHALL INCLUDE, BUT NOT BE LIMITED TO: PINCHING OF THE WIRE ROPE, BENDING OF THE WIRE ROPE FROM ITS SUPPORTS, DIRECT CONTACT OR CLOSE PROXIMITY TO THE WIRE ROPE WHICH MAY CAUSE FRICTIONAL WEAR, IMPACT TO THE ANCHORAGE POINTS IN ANY WAY, OR TO IMPEDE/BLOCK ITS INTENDED USE. ANY COMPROMISED SAFETY CLIMB, INCLUDING EXISTING CONDITIONS MUST BE TAGGED OUT AND REPORTED TO YOUR DISH Wireless L.L.C. AND DISH Wireless L.L.C. AND TOWER OWNER POC OR CALL THE NOC TO GENERATE A SAFETY CLIMB MAINTENANCE AND CONTRACTOR NOTICE TICKET.
3. PRIOR TO THE START OF CONSTRUCTION, ALL REQUIRED JURISDICTIONAL PERMITS SHALL BE OBTAINED. THIS INCLUDES, BUT IS NOT LIMITED TO, BUILDING, ELECTRICAL, MECHANICAL, FIRE, FLOOD ZONE, ENVIRONMENTAL, AND ZONING. AFTER ONSITE ACTIVITIES AND CONSTRUCTION ARE COMPLETED, ALL REQUIRED PERMITS SHALL BE SATISFIED AND CLOSED OUT ACCORDING TO LOCAL JURISDICTIONAL REQUIREMENTS.
4. ALL CONSTRUCTION MEANS AND METHODS; INCLUDING BUT NOT LIMITED TO, ERECTION PLANS, RIGGING PLANS, CLIMBING PLANS, AND RESCUE PLANS SHALL BE THE RESPONSIBILITY OF THE GENERAL CONTRACTOR RESPONSIBLE FOR THE EXECUTION OF THE WORK CONTAINED HEREIN, AND SHALL MEET ANSI/ASSE A10.48 (LATEST EDITION); FEDERAL, STATE, AND LOCAL REGULATIONS; AND ANY APPLICABLE INDUSTRY CONSENSUS STANDARDS RELATED TO THE CONSTRUCTION ACTIVITIES BEING PERFORMED. ALL RIGGING PLANS SHALL ADHERE TO ANSI/ASSE A10.48 (LATEST EDITION) AND DISH Wireless L.L.C. AND TOWER OWNER STANDARDS, INCLUDING THE REQUIRED INVOLVEMENT OF A QUALIFIED ENGINEER FOR CLASS IV CONSTRUCTION, TO CERTIFY THE SUPPORTING STRUCTURE(S) IN ACCORDANCE WITH ANSI/TIA–322 (LATEST EDITION).
5. ALL SITE WORK TO COMPLY WITH DISH Wireless L.L.C. AND TOWER OWNER INSTALLATION STANDARDS FOR CONSTRUCTION ACTIVITIES ON DISH Wireless L.L.C. AND TOWER OWNER TOWER SITE AND LATEST VERSION OF ANSI/TIA–1019–A–2012 "STANDARD FOR INSTALLATION, ALTERATION, AND MAINTENANCE OF ANTENNA SUPPORTING STRUCTURES AND ANTENNAS."
6. IF THE SPECIFIED EQUIPMENT CAN NOT BE INSTALLED AS SHOWN ON THESE DRAWINGS, THE CONTRACTOR SHALL PROPOSE AN ALTERNATIVE INSTALLATION FOR APPROVAL BY DISH Wireless L.L.C. AND TOWER OWNER PRIOR TO PROCEEDING WITH ANY SUCH CHANGE OF INSTALLATION.
7. ALL MATERIALS FURNISHED AND INSTALLED SHALL BE IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS AND ORDINANCES. CONTRACTOR SHALL ISSUE ALL APPROPRIATE NOTICES AND COMPLY WITH ALL LAWS, ORDINANCES, RULES, REGULATIONS AND LAWFUL ORDERS OF ANY PUBLIC AUTHORITY REGARDING THE PERFORMANCE OF THE WORK. ALL WORK CARRIED OUT SHALL COMPLY WITH ALL APPLICABLE MUNICIPAL AND UTILITY COMPANY SPECIFICATIONS AND LOCAL JURISDICTIONAL CODES, ORDINANCES AND APPLICABLE REGULATIONS.
8. THE CONTRACTOR SHALL INSTALL ALL EQUIPMENT AND MATERIALS IN ACCORDANCE WITH MANUFACTURER’S RECOMMENDATIONS UNLESS SPECIFICALLY STATED OTHERWISE.
9. THE CONTRACTOR SHALL CONTACT UTILITY LOCATING SERVICES INCLUDING PRIVATE LOCATES SERVICES PRIOR TO THE START OF CONSTRUCTION.
10. ALL EXISTING ACTIVE SEWER, WATER, GAS, ELECTRIC AND OTHER UTILITIES WHERE ENCOUNTERED IN THE WORK, SHALL BE PROTECTED AT ALL TIMES AND WHERE REQUIRED FOR THE PROPER EXECUTION OF THE WORK, SHALL BE RELOCATED AS DIRECTED BY CONTRACTOR. EXTREME CAUTION SHOULD BE USED BY THE CONTRACTOR WHEN EXCAVATING OR DRILLING PIERS AROUND OR NEAR UTILITIES. CONTRACTOR SHALL PROVIDE SAFETY TRAINING FOR THE WORKING CREW. THIS WILL INCLUDE BUT NOT BE LIMITED TO A) FALL PROTECTION B) CONFINED SPACE C) ELECTRICAL SAFETY D) TRENCHING AND EXCAVATION E) CONSTRUCTION SAFETY PROCEDURES.
11. ALL SITE WORK SHALL BE AS INDICATED ON THE STAMPED CONSTRUCTION DRAWINGS AND DISH PROJECT SPECIFICATIONS, LATEST APPROVED REVISION.
12. CONTRACTOR SHALL KEEP THE SITE FREE FROM ACCUMULATING WASTE MATERIAL, DEBRIS, AND TRASH AT THE COMPLETION OF THE WORK. IF NECESSARY, RUBBISH, STUMPS, DEBRIS, STICKS, STONES AND OTHER REFUSE SHALL BE REMOVED FROM THE SITE AND DISPOSED OF LEGALLY.
13. ALL EXISTING INACTIVE SEWER, WATER, GAS, ELECTRIC AND OTHER UTILITIES, WHICH INTERFERE WITH THE EXECUTION OF THE WORK, SHALL BE REMOVED AND/OR CAPPED, PLUGGED OR OTHERWISE DISCONTINUED AT POINTS WHICH WILL NOT INTERFERE WITH THE EXECUTION OF THE WORK, SUBJECT TO THE APPROVAL OF DISH Wireless L.L.C. AND TOWER OWNER, AND/OR LOCAL UTILITIES.
14. THE CONTRACTOR SHALL PROVIDE SITE SIGNAGE IN ACCORDANCE WITH THE TECHNICAL SPECIFICATION FOR SITE SIGNAGE REQUIRED BY LOCAL JURISDICTION AND SIGNAGE REQUIRED ON INDIVIDUAL PIECES OF EQUIPMENT, ROOMS, AND SHELTERS.
15. THE SITE SHALL BE GRADED TO CAUSE SURFACE WATER TO FLOW AWAY FROM THE CARRIER’S EQUIPMENT AND TOWER AREAS.
16. THE SUB GRADE SHALL BE COMPACTED AND BROUGHT TO A SMOOTH UNIFORM GRADE PRIOR TO FINISHED SURFACE APPLICATION.
17. THE AREAS OF THE OWNERS PROPERTY DISTURBED BY THE WORK AND NOT COVERED BY THE TOWER, EQUIPMENT OR DRIVEWAY, SHALL BE GRADED TO A UNIFORM SLOPE, AND STABILIZED TO PREVENT EROSION AS SPECIFIED ON THE CONSTRUCTION DRAWINGS AND/OR PROJECT SPECIFICATIONS.
18. CONTRACTOR SHALL MINIMIZE DISTURBANCE TO EXISTING SITE DURING CONSTRUCTION. EROSION CONTROL MEASURES, IF REQUIRED DURING CONSTRUCTION, SHALL BE IN CONFORMANCE WITH THE LOCAL GUIDELINES FOR EROSION AND SEDIMENT CONTROL.
19. THE CONTRACTOR SHALL PROTECT EXISTING IMPROVEMENTS, PAVEMENTS, CURBS, LANDSCAPING AND STRUCTURES. ANY DAMAGED PART SHALL BE REPAIRED AT CONTRACTOR’S EXPENSE TO THE SATISFACTION OF OWNER.
20. CONTRACTOR SHALL LEGALLY AND PROPERLY DISPOSE OF ALL SCRAP MATERIALS SUCH AS COAXIAL CABLES AND OTHER ITEMS REMOVED FROM THE EXISTING FACILITY. ANTENNAS AND RADIOS REMOVED SHALL BE RETURNED TO THE OWNER’S DESIGNATED LOCATION.
21. CONTRACTOR SHALL LEAVE PREMISES IN CLEAN CONDITION. TRASH AND DEBRIS SHOULD BE REMOVED FROM SITE ON A DAILY BASIS.
22. NO FILL OR EMBANKMENT MATERIAL SHALL BE PLACED ON FROZEN GROUND. FROZEN MATERIALS, SNOW OR ICE SHALL NOT BE PLACED IN ANY FILL OR EMBANKMENT.

GENERAL NOTES:

- 1.FOR THE PURPOSE OF CONSTRUCTION DRAWING, THE FOLLOWING DEFINITIONS SHALL APPLY:

CONTRACTOR:GENERAL CONTRACTOR RESPONSIBLE FOR CONSTRUCTION


CARRIER:DISH Wireless L.L.C.

TOWER OWNER:TOWER OWNER
2. THESE DRAWINGS HAVE BEEN PREPARED USING STANDARDS OF PROFESSIONAL CARE AND COMPLETENESS NORMALLY EXERCISED UNDER SIMILAR CIRCUMSTANCES BY REPUTABLE ENGINEERS IN THIS OR SIMILAR LOCALITIES. IT IS ASSUMED THAT THE WORK DEPICTED WILL BE PERFORMED BY AN EXPERIENCED CONTRACTOR AND/OR WORKPEOPLE WHO HAVE A WORKING KNOWLEDGE OF THE APPLICABLE CODE STANDARDS AND REQUIREMENTS AND OF INDUSTRY ACCEPTED STANDARD GOOD PRACTICE. AS NOT EVERY CONDITION OR ELEMENT IS (OR CAN BE) EXPLICITLY SHOWN ON THESE DRAWINGS, THE CONTRACTOR SHALL USE INDUSTRY ACCEPTED STANDARD GOOD PRACTICE FOR MISCELLANEOUS WORK NOT EXPLICITLY SHOWN.
3. THESE DRAWINGS REPRESENT THE FINISHED STRUCTURE. THEY DO NOT INDICATE THE MEANS OR METHODS OF CONSTRUCTION. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR THE CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES. THE CONTRACTOR SHALL PROVIDE ALL MEASURES NECESSARY FOR PROTECTION OF LIFE AND PROPERTY DURING CONSTRUCTION. SUCH MEASURES SHALL INCLUDE, BUT NOT BE LIMITED TO, BRACING, FORMWORK, SHORING, ETC. SITE VISITS BY THE ENGINEER OR HIS REPRESENTATIVE WILL NOT INCLUDE INSPECTION OF THESE ITEMS AND IS FOR STRUCTURAL OBSERVATION OF THE FINISHED STRUCTURE ONLY.
4. NOTES AND DETAILS IN THE CONSTRUCTION DRAWINGS SHALL TAKE PRECEDENCE OVER GENERAL NOTES AND TYPICAL DETAILS. WHERE NO DETAILS ARE SHOWN, CONSTRUCTION SHALL CONFORM TO SIMILAR WORK ON THE PROJECT, AND/OR AS PROVIDED FOR IN THE CONTRACT DOCUMENTS. WHERE DISCREPANCIES OCCUR BETWEEN PLANS, DETAILS, GENERAL NOTES, AND SPECIFICATIONS, THE GREATER, MORE STRICT REQUIREMENTS, SHALL GOVERN. IF FURTHER CLARIFICATION IS REQUIRED CONTACT THE ENGINEER OF RECORD.
5. SUBSTANTIAL EFFORT HAS BEEN MADE TO PROVIDE ACCURATE DIMENSIONS AND MEASUREMENTS ON THE DRAWINGS TO ASSIST IN THE FABRICATION AND/OR PLACEMENT OF CONSTRUCTION ELEMENTS BUT IT IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR TO FIELD VERIFY THE DIMENSIONS, MEASUREMENTS, AND/OR CLEARANCES SHOWN IN THE CONSTRUCTION DRAWINGS PRIOR TO FABRICATION OR CUTTING OF ANY NEW OR EXISTING CONSTRUCTION ELEMENTS. IF IT IS DETERMINED THAT THERE ARE DISCREPANCIES AND/OR CONFLICTS WITH THE CONSTRUCTION DRAWINGS THE ENGINEER OF RECORD IS TO BE NOTIFIED AS SOON AS POSSIBLE.
6. PRIOR TO THE SUBMISSION OF BIDS, THE BIDDING CONTRACTOR SHALL VISIT THE CELL SITE TO FAMILIARIZE WITH THE EXISTING CONDITIONS AND TO CONFIRM THAT THE WORK CAN BE ACCOMPLISHED AS SHOWN ON THE CONSTRUCTION DRAWINGS. ANY DISCREPANCY FOUND SHALL BE BROUGHT TO THE ATTENTION OF CARRIER POC AND TOWER OWNER.
7. ALL MATERIALS FURNISHED AND INSTALLED SHALL BE IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS AND ORDINANCES. CONTRACTOR SHALL ISSUE ALL APPROPRIATE NOTICES AND COMPLY WITH ALL LAWS, ORDINANCES, RULES, REGULATIONS AND LAWFUL ORDERS OF ANY PUBLIC AUTHORITY REGARDING THE PERFORMANCE OF THE WORK. ALL WORK CARRIED OUT SHALL COMPLY WITH ALL APPLICABLE MUNICIPAL AND UTILITY COMPANY SPECIFICATIONS AND LOCAL JURISDICTIONAL CODES, ORDINANCES AND APPLICABLE REGULATIONS.
8. UNLESS NOTED OTHERWISE, THE WORK SHALL INCLUDE FURNISHING MATERIALS, EQUIPMENT, APPURTENANCES AND LABOR NECESSARY TO COMPLETE ALL INSTALLATIONS AS INDICATED ON THE DRAWINGS.
9. THE CONTRACTOR SHALL INSTALL ALL EQUIPMENT AND MATERIALS IN ACCORDANCE WITH MANUFACTURER’S RECOMMENDATIONS UNLESS SPECIFICALLY STATED OTHERWISE.
10. IF THE SPECIFIED EQUIPMENT CAN NOT BE INSTALLED AS SHOWN ON THESE DRAWINGS, THE CONTRACTOR SHALL PROPOSE AN ALTERNATIVE INSTALLATION FOR APPROVAL BY THE CARRIER AND TOWER OWNER PRIOR TO PROCEEDING WITH ANY SUCH CHANGE OF INSTALLATION.
11. CONTRACTOR IS TO PERFORM A SITE INVESTIGATION, BEFORE SUBMITTING BIDS, TO DETERMINE THE BEST ROUTING OF ALL CONDUITS FOR POWER, AND TELCO AND FOR GROUNDING CABLES AS SHOWN IN THE POWER, TELCO, AND GROUNDING PLAN DRAWINGS.
12. THE CONTRACTOR SHALL PROTECT EXISTING IMPROVEMENTS, PAVEMENTS, CURBS, LANDSCAPING AND STRUCTURES. ANY DAMAGED PART SHALL BE REPAIRED AT CONTRACTOR’S EXPENSE TO THE SATISFACTION OF DISH Wireless L.L.C. AND TOWER OWNER
13. CONTRACTOR SHALL LEGALLY AND PROPERLY DISPOSE OF ALL SCRAP MATERIALS SUCH AS COAXIAL CABLES AND OTHER ITEMS REMOVED FROM THE EXISTING FACILITY. ANTENNAS REMOVED SHALL BE RETURNED TO THE OWNER’S DESIGNATED LOCATION.
14. CONTRACTOR SHALL LEAVE PREMISES IN CLEAN CONDITION. TRASH AND DEBRIS SHOULD BE REMOVED FROM SITE ON A DAILY BASIS.



DRAWN BY:	CHECKED BY:	APPROVED BY:
AP	SRF	SRF
RFDS REV #:		----

CONSTRUCTION DOCUMENTS		
SUBMITTALS		
REV	DATE	DESCRIPTION
0	01/05/2022	ISSUED FOR CONSTRUCTION



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

A&E PROJECT NUMBER
418609–13733434_D3

DISH Wireless L.L.C.
PROJECT INFORMATION
BOBOS00030A
87 WEST QUASSET ROAD
WOODSTOCK, CT 06281

SHEET TITLE
GENERAL NOTES

SHEET NUMBER
GN-2

CONCRETE, FOUNDATIONS, AND REINFORCING STEEL:

1. ALL CONCRETE WORK SHALL BE IN ACCORDANCE WITH THE ACI 301, ACI 318, ACI 336, ASTM A184, ASTM A185 AND THE DESIGN AND CONSTRUCTION SPECIFICATION FOR CAST-IN-PLACE CONCRETE.
2. UNLESS NOTED OTHERWISE, SOIL BEARING PRESSURE USED FOR DESIGN OF SLABS AND FOUNDATIONS IS ASSUMED TO BE 1000 psf.
3. ALL CONCRETE SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH (f'c) OF 3000 psi AT 28 DAYS, UNLESS NOTED OTHERWISE. NO MORE THAN 90 MINUTES SHALL ELAPSE FROM BATCH TIME TO TIME OF PLACEMENT UNLESS APPROVED BY THE ENGINEER OF RECORD. TEMPERATURE OF CONCRETE SHALL NOT EXCEED 90°f AT TIME OF PLACEMENT.
4. CONCRETE EXPOSED TO FREEZE-THAW CYCLES SHALL CONTAIN AIR ENTRAINING ADMIXTURES. AMOUNT OF AIR ENTRAINMENT TO BE BASED ON SIZE OF AGGREGATE AND F3 CLASS EXPOSURE (VERY SEVERE). CEMENT USED TO BE TYPE II PORTLAND CEMENT WITH A MAXIMUM WATER-TO-CEMENT RATIO (W/C) OF 0.45.
5. ALL STEEL REINFORCING SHALL CONFORM TO ASTM A615. ALL WELDED WIRE FABRIC (WWF) SHALL CONFORM TO ASTM A185. ALL SPLICES SHALL BE CLASS "B" TENSION SPLICES, UNLESS NOTED OTHERWISE. ALL HOOKS SHALL BE STANDARD 90 DEGREE HOOKS, UNLESS NOTED OTHERWISE. YIELD STRENGTH (Fy) OF STANDARD DEFORMED BARS ARE AS FOLLOWS:
#4 BARS AND SMALLER 40 ksi
#5 BARS AND LARGER 60 ksi
6. THE FOLLOWING MINIMUM CONCRETE COVER SHALL BE PROVIDED FOR REINFORCING STEEL UNLESS SHOWN OTHERWISE ON DRAWINGS:
 - CONCRETE CAST AGAINST AND PERMANENTLY EXPOSED TO EARTH 3"
 - CONCRETE EXPOSED TO EARTH OR WEATHER:
 - #6 BARS AND LARGER 2"
 - #5 BARS AND SMALLER 1-1/2"
 - CONCRETE NOT EXPOSED TO EARTH OR WEATHER:
 - SLAB AND WALLS 3/4"
 - BEAMS AND COLUMNS 1-1/2"
7. A TOOLED EDGE OR A 3/4" CHAMFER SHALL BE PROVIDED AT ALL EXPOSED EDGES OF CONCRETE, UNLESS NOTED OTHERWISE, IN ACCORDANCE WITH ACI 301 SECTION 4.2.4.

ELECTRICAL INSTALLATION NOTES:

1. ALL ELECTRICAL WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS, NEC AND ALL APPLICABLE FEDERAL, STATE, AND LOCAL CODES/ORDINANCES.
2. CONDUIT ROUTINGS ARE SCHEMATIC. CONTRACTOR SHALL INSTALL CONDUITS SO THAT ACCESS TO EQUIPMENT IS NOT BLOCKED AND TRIP HAZARDS ARE ELIMINATED.
3. WIRING, RACEWAY AND SUPPORT METHODS AND MATERIALS SHALL COMPLY WITH THE REQUIREMENTS OF THE NEC.
4. ALL CIRCUITS SHALL BE SEGREGATED AND MAINTAIN MINIMUM CABLE SEPARATION AS REQUIRED BY THE NEC.
- 4.1. ALL EQUIPMENT SHALL BEAR THE UNDERWRITERS LABORATORIES LABEL OF APPROVAL, AND SHALL CONFORM TO REQUIREMENT OF THE NATIONAL ELECTRICAL CODE.
- 4.2. ALL OVERCURRENT DEVICES SHALL HAVE AN INTERRUPTING CURRENT RATING THAT SHALL BE GREATER THAN THE SHORT CIRCUIT CURRENT TO WHICH THEY ARE SUBJECTED, 22,000 AIC MINIMUM. VERIFY AVAILABLE SHORT CIRCUIT CURRENT DOES NOT EXCEED THE RATING OF ELECTRICAL EQUIPMENT IN ACCORDANCE WITH ARTICLE 110.24 NEC OR THE MOST CURRENT ADOPTED CODE PRE THE GOVERNING JURISDICTION.
5. EACH END OF EVERY POWER PHASE CONDUCTOR, GROUNDING CONDUCTOR, AND TELCO CONDUCTOR OR CABLE SHALL BE LABELED WITH COLOR-CODED INSULATION OR ELECTRICAL TAPE (3M BRAND, 1/2" PLASTIC ELECTRICAL TAPE WITH UV PROTECTION, OR EQUAL). THE IDENTIFICATION METHOD SHALL CONFORM WITH NEC AND OSHA.
6. ALL ELECTRICAL COMPONENTS SHALL BE CLEARLY LABELED WITH LAMICOID TAGS SHOWING THEIR RATED VOLTAGE, PHASE CONFIGURATION, WIRE CONFIGURATION, POWER OR AMPACITY RATING AND BRANCH CIRCUIT ID NUMBERS (i.e. PANEL BOARD AND CIRCUIT ID'S).
7. PANEL BOARDS (ID NUMBERS) SHALL BE CLEARLY LABELED WITH PLASTIC LABELS.
8. TIE WRAPS ARE NOT ALLOWED.
9. ALL POWER AND EQUIPMENT GROUND WIRING IN TUBING OR CONDUIT SHALL BE SINGLE COPPER CONDUCTOR (#14 OR LARGER) WITH TYPE THHW, THWN, THWN-2, XHHW, XHHW-2, THW, THW-2, RHW, OR RHW-2 INSULATION UNLESS OTHERWISE SPECIFIED.
10. SUPPLEMENTAL EQUIPMENT GROUND WIRING LOCATED INDOORS SHALL BE SINGLE COPPER CONDUCTOR (#6 OR LARGER) WITH TYPE THHW, THWN, THWN-2, XHHW, XHHW-2, THW, THW-2, RHW, OR RHW-2 INSULATION UNLESS OTHERWISE SPECIFIED.
11. POWER AND CONTROL WIRING IN FLEXIBLE CORD SHALL BE MULTI-CONDUCTOR, TYPE SOOW CORD (#14 OR LARGER) UNLESS OTHERWISE SPECIFIED.
12. POWER AND CONTROL WIRING FOR USE IN CABLE TRAY SHALL BE MULTI-CONDUCTOR, TYPE TC CABLE (#14 OR LARGER), WITH TYPE THHW, THWN, THWN-2, XHHW, XHHW-2, THW, THW-2, RHW, OR RHW-2 INSULATION UNLESS OTHERWISE SPECIFIED.
13. ALL POWER AND GROUNDING CONNECTIONS SHALL BE CRIMP-STYLE, COMPRESSION WIRE LUGS AND WIRE NUTS BY THOMAS AND BETTS (OR EQUAL). LUGS AND WIRE NUTS SHALL BE RATED FOR OPERATION NOT LESS THAN 75° C (90° C IF AVAILABLE).
14. RACEWAY AND CABLE TRAY SHALL BE LISTED OR LABELED FOR ELECTRICAL USE IN ACCORDANCE WITH NEMA, UL, ANSI/IEEE AND NEC.
15. ELECTRICAL METALLIC TUBING (EMT), INTERMEDIATE METAL CONDUIT (IMC), OR RIGID METAL CONDUIT (RMC) SHALL BE USED FOR EXPOSED INDOOR LOCATIONS.

16. ELECTRICAL METALLIC TUBING (EMT) OR METAL-CLAD CABLE (MC) SHALL BE USED FOR CONCEALED INDOOR LOCATIONS.
17. SCHEDULE 40 PVC UNDERGROUND ON STRAIGHTS AND SCHEDULE 80 PVC FOR ALL ELBOWS/90s AND ALL APPROVED ABOVE GRADE PVC CONDUIT.
18. LIQUID-TIGHT FLEXIBLE METALLIC CONDUIT (LIQUID-TITE FLEX) SHALL BE USED INDOORS AND OUTDOORS, WHERE VIBRATION OCCURS OR FLEXIBILITY IS NEEDED.
19. CONDUIT AND TUBING FITTINGS SHALL BE THREADED OR COMPRESSION-TYPE AND APPROVED FOR THE LOCATION USED. SET SCREW FITTINGS ARE NOT ACCEPTABLE.
20. CABINETS, BOXES AND WIRE WAYS SHALL BE LABELED FOR ELECTRICAL USE IN ACCORDANCE WITH NEMA, UL, ANSI/IEEE AND THE NEC.
21. WIREWAYS SHALL BE METAL WITH AN ENAMEL FINISH AND INCLUDE A HINGED COVER, DESIGNED TO SWING OPEN DOWNWARDS (WIREMOLD SPECMATE WIREWAY).
22. SLOTTED WIRING DUCT SHALL BE PVC AND INCLUDE COVER (PANDUIT TYPE E OR EQUAL).
23. CONDUITS SHALL BE FASTENED SECURELY IN PLACE WITH APPROVED NON-PERFORATED STRAPS AND HANGERS. EXPLOSIVE DEVICES (i.e. POWDER-ACTUATED) FOR ATTACHING HANGERS TO STRUCTURE WILL NOT BE PERMITTED. CLOSELY FOLLOW THE LINES OF THE STRUCTURE, MAINTAIN CLOSE PROXIMITY TO THE STRUCTURE AND KEEP CONDUITS IN TIGHT ENVELOPES. CHANGES IN DIRECTION TO ROUTE AROUND OBSTACLES SHALL BE MADE WITH CONDUIT OUTLET BODIES. CONDUIT SHALL BE INSTALLED IN A NEAT AND WORKMANLIKE MANNER. PARALLEL AND PERPENDICULAR TO STRUCTURE WALL AND CEILING LINES. ALL CONDUIT SHALL BE FISHED TO CLEAR OBSTRUCTIONS. ENDS OF CONDUITS SHALL BE TEMPORARILY CAPPED FLUSH TO FINISH GRADE TO PREVENT CONCRETE, PLASTER OR DIRT FROM ENTERING. CONDUITS SHALL BE RIGIDLY CLAMPED TO BOXES BY GALVANIZED MALLEABLE IRON BUSHING ON INSIDE AND GALVANIZED MALLEABLE IRON LOCKNUT ON OUTSIDE AND INSIDE.
24. EQUIPMENT CABINETS, TERMINAL BOXES, JUNCTION BOXES AND PULL BOXES SHALL BE GALVANIZED OR EPOXY-COATED SHEET STEEL. SHALL MEET OR EXCEED UL 50 AND BE RATED NEMA 1 (OR BETTER) FOR INTERIOR LOCATIONS AND NEMA 3 (OR BETTER) FOR EXTERIOR LOCATIONS.
25. METAL RECEPTACLE, SWITCH AND DEVICE BOXES SHALL BE GALVANIZED, EPOXY-COATED OR NON-CORRODING; SHALL MEET OR EXCEED UL 514A AND NEMA OS 1 AND BE RATED NEMA 1 (OR BETTER) FOR INTERIOR LOCATIONS AND WEATHER PROTECTED (WP OR BETTER) FOR EXTERIOR LOCATIONS.
26. NONMETALLIC RECEPTACLE, SWITCH AND DEVICE BOXES SHALL MEET OR EXCEED NEMA OS 2 (NEWEST REVISION) AND BE RATED NEMA 1 (OR BETTER) FOR INTERIOR LOCATIONS AND WEATHER PROTECTED (WP OR BETTER) FOR EXTERIOR LOCATIONS.
27. THE CONTRACTOR SHALL NOTIFY AND OBTAIN NECESSARY AUTHORIZATION FROM THE CARRIER AND/OR DISH Wireless L.L.C. AND TOWER OWNER BEFORE COMMENCING WORK ON THE AC POWER DISTRIBUTION PANELS.
28. THE CONTRACTOR SHALL PROVIDE NECESSARY TAGGING ON THE BREAKERS, CABLES AND DISTRIBUTION PANELS IN ACCORDANCE WITH THE APPLICABLE CODES AND STANDARDS TO SAFEGUARD LIFE AND PROPERTY.
29. INSTALL LAMICOID LABEL ON THE METER CENTER TO SHOW "DISH Wireless L.L.C.".
30. ALL EMPTY/SPARE CONDUITS THAT ARE INSTALLED ARE TO HAVE A METERED MULE TAPE PULL CORD INSTALLED.

dish

wireless.

5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120

AMERICAN TOWER®

A.T. ENGINEERING SERVICE, PLLC

3500 REGENCY PARKWAY
SUITE 100
CARY, NC 27518
PHONE: (919) 468-0112

DRAWN BY:APSRFAP

CHECKED BY:SRFSRF

APPROVED BY:SRFSRF

RFDS REV #:-----

CONSTRUCTION DOCUMENTS

SUBMITTALS

REV	DATE	DESCRIPTION
0	01/05/2022	ISSUED FOR CONSTRUCTION

STATE OF CONNECTICUT

MUSTAFA RAM

33740

LICENSED PROFESSIONAL ENGINEER

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

A&E PROJECT NUMBER
418609-13733434_D3

DISH Wireless L.L.C.
PROJECT INFORMATION
BOBOS00030A
87 WEST QUASSET ROAD
WOODSTOCK, CT 06281

SHEET TITLE
GENERAL NOTES

SHEET NUMBER
GN-3

GROUNDING NOTES:

1. ALL GROUND ELECTRODE SYSTEMS (INCLUDING TELECOMMUNICATION, RADIO, LIGHTNING PROTECTION AND AC POWER GES’S) SHALL BE BONDED TOGETHER AT OR BELOW GRADE, BY TWO OR MORE COPPER BONDING CONDUCTORS IN ACCORDANCE WITH THE NEC.
2. THE CONTRACTOR SHALL PERFORM IEEE FALL–OF–POTENTIAL RESISTANCE TO EARTH TESTING (PER IEEE 1100 AND 81) FOR GROUND ELECTRODE SYSTEMS, THE CONTRACTOR SHALL FURNISH AND INSTALL SUPPLEMENTAL GROUND ELECTRODES AS NEEDED TO ACHIEVE A TEST RESULT OF 5 OHMS OR LESS.
3. THE CONTRACTOR IS RESPONSIBLE FOR PROPERLY SEQUENCING GROUNDING AND UNDERGROUND CONDUIT INSTALLATION AS TO PREVENT ANY LOSS OF CONTINUITY IN THE GROUNDING SYSTEM OR DAMAGE TO THE CONDUIT AND PROVIDE TESTING RESULTS.
4. METAL CONDUIT AND TRAY SHALL BE GROUNDED AND MADE ELECTRICALLY CONTINUOUS WITH LISTED BONDING FITTINGS OR BY BONDING ACROSS THE DISCONTINUITY WITH #6 COPPER WIRE UL APPROVED GROUNDING TYPE CONDUIT CLAMPS.
5. METAL RACEWAY SHALL NOT BE USED AS THE NEC REQUIRED EQUIPMENT GROUND CONDUCTOR. STRANDED COPPER CONDUCTORS WITH GREEN INSULATION, SIZED IN ACCORDANCE WITH THE NEC, SHALL BE FURNISHED AND INSTALLED WITH THE POWER CIRCUITS TO BTS EQUIPMENT.
6. EACH CABINET FRAME SHALL BE DIRECTLY CONNECTED TO THE MASTER GROUND BAR WITH GREEN INSULATED SUPPLEMENTAL EQUIPMENT GROUND WIRES, #6 STRANDED COPPER OR LARGER FOR INDOOR BTS; #2 BARE SOLID TINNED COPPER FOR OUTDOOR BTS.
7. CONNECTIONS TO THE GROUND BUS SHALL NOT BE DOUBLED UP OR STACKED BACK TO BACK CONNECTIONS ON OPPOSITE SIDE OF THE GROUND BUS ARE PERMITTED.
8. ALL EXTERIOR GROUND CONDUCTORS BETWEEN EQUIPMENT/GROUND BARS AND THE GROUND RING SHALL BE #2 SOLID TINNED COPPER UNLESS OTHERWISE INDICATED.
9. ALUMINUM CONDUCTOR OR COPPER CLAD STEEL CONDUCTOR SHALL NOT BE USED FOR GROUNDING CONNECTIONS.
10. USE OF 90° BENDS IN THE PROTECTION GROUNDING CONDUCTORS SHALL BE AVOIDED WHEN 45° BENDS CAN BE ADEQUATELY SUPPORTED.
11. EXOTHERMIC WELDS SHALL BE USED FOR ALL GROUNDING CONNECTIONS BELOW GRADE.
12. ALL GROUND CONNECTIONS ABOVE GRADE (INTERIOR AND EXTERIOR) SHALL BE FORMED USING HIGH PRESS CRIMPS.
13. COMPRESSION GROUND CONNECTIONS MAY BE REPLACED BY EXOTHERMIC WELD CONNECTIONS.
14. ICE BRIDGE BONDING CONDUCTORS SHALL BE EXOTHERMICALLY BONDED OR BOLTED TO THE BRIDGE AND THE TOWER GROUND BAR.
15. APPROVED ANTIOXIDANT COATINGS (i.e. CONDUCTIVE GEL OR PASTE) SHALL BE USED ON ALL COMPRESSION AND BOLTED GROUND CONNECTIONS.
16. ALL EXTERIOR GROUND CONNECTIONS SHALL BE COATED WITH A CORROSION RESISTANT MATERIAL.
17. MISCELLANEOUS ELECTRICAL AND NON–ELECTRICAL METAL BOXES, FRAMES AND SUPPORTS SHALL BE BONDED TO THE GROUND RING, IN ACCORDANCE WITH THE NEC.
18. BOND ALL METALLIC OBJECTS WITHIN 6 ft OF MAIN GROUND RING WITH (1) #2 BARE SOLID TINNED COPPER GROUND CONDUCTOR.
19. GROUND CONDUCTORS USED FOR THE FACILITY GROUNDING AND LIGHTNING PROTECTION SYSTEMS SHALL NOT BE ROUTED THROUGH METALLIC OBJECTS THAT FORM A RING AROUND THE CONDUCTOR, SUCH AS METALLIC CONDUITS, METAL SUPPORT CLIPS OR SLEEVES THROUGH WALLS OR FLOORS. WHEN IT IS REQUIRED TO BE HOUSED IN CONDUIT TO MEET CODE REQUIREMENTS OR LOCAL CONDITIONS, NON–METALLIC MATERIAL SUCH AS PVC CONDUIT SHALL BE USED. WHERE USE OF METAL CONDUIT IS UNAVOIDABLE (i.e., NONMETALLIC CONDUIT PROHIBITED BY LOCAL CODE) THE GROUND CONDUCTOR SHALL BE BONDED TO EACH END OF THE METAL CONDUIT.
20. ALL GROUNDS THAT TRANSITION FROM BELOW GRADE TO ABOVE GRADE MUST BE #2 BARE SOLID TINNED COPPER IN 3/4” NON–METALLIC, FLEXIBLE CONDUIT FROM 24” BELOW GRADE TO WITHIN 3” TO 6” OF CAD–WELD TERMINATION POINT. THE EXPOSED END OF THE CONDUIT MUST BE SEALED WITH SILICONE CAULK. (ADD TRANSITIONING GROUND STANDARD DETAIL AS WELL).
21. BUILDINGS WHERE THE MAIN GROUNDING CONDUCTORS ARE REQUIRED TO BE ROUTED TO GRADE, THE CONTRACTOR SHALL ROUTE TWO GROUNDING CONDUCTORS FROM THE ROOFTOP, TOWERS, AND WATER TOWERS GROUNDING RING, TO THE EXISTING GROUNDING SYSTEM, THE GROUNDING CONDUCTORS SHALL NOT BE SMALLER THAN 2/0 COPPER. ROOFTOP GROUNDING RING SHALL BE BONDED TO THE EXISTING GROUNDING SYSTEM, THE BUILDING STEEL COLUMNS, LIGHTNING PROTECTION SYSTEM, AND BUILDING MAIN WATER LINE (FERROUS OR NONFERROUS METAL PIPING ONLY). DO NOT ATTACH GROUNDING TO FIRE SPRINKLER SYSTEM PIPES.

STRUCTURAL STEEL NOTES:

1. STRUCTURAL STEEL SHALL CONFORM TO THE LATEST EDITION OF THE AISC “SPECIFICATION FOR THE DESIGN, FABRICATION AND ERECTION OF STRUCTURAL STEEL FOR BUILDINGS.”
2. STRUCTURAL STEEL ROLLED SHAPES, PLATES AND BARS SHALL CONFORM TO THE FOLLOWING ASTM DESIGNATIONS:

A. ASTM A–572, GRADE 50 – ALL W SHAPES, UNLESS NOTED OR A992 OTHERWISE

B. ASTM A–36 – ALL OTHER ROLLED SHAPES, PLATES AND BARS UNLESS NOTED OTHERWISE.

C. ASTM A–500, GRADE B – HSS SECTION (SQUARE, RECTANGULAR, AND ROUND)

D. ASTM A–325, TYPE SC OR N – ALL BOLTS FOR CONNECTING STRUCTURAL MEMBERS

E. ASTM F–1554 07 – ALL ANCHOR BOLTS, UNLESS NOTED OTHERWISE
3. ALL EXPOSED STRUCTURAL STEEL MEMBERS SHALL BE HOT–DIPPED GALVANIZED AFTER FABRICATION PER ASTM A123. EXPOSED STEEL HARDWARE AND ANCHOR BOLTS SHALL BE GALVANIZED PER ASTM A153 OR B695.
4. ALL FIELD CUT SURFACES, FIELD DRILLED HOLES AND GROUND SURFACES WHERE EXISTING PAINT OR GALVANIZATION REMOVAL WAS REQUIRED SHALL BE REPAIRED WITH (2) BRUSHED COATS OF ZRC GALVILITE COLD GALVANIZING COMPOUND PER ASTM A780 AND MANUFACTURER'S RECOMMENDATIONS.
5. DO NOT DRILL HOLES THROUGH STRUCTURAL STEEL MEMBERS EXCEPT AS SHOWN AND DETAILED ON STRUCTURAL DRAWINGS.
6. CONNECTIONS:

A. ALL WELDING TO BE PERFORMED BY AWS CERTIFIED WELDERS AND CONDUCTED IN ACCORDANCE WITH THE LATEST EDITION OF THE AWS WELDING CODE D1.1.

B. ALL WELDS SHALL BE INSPECTED VISUALLY. 25% OF WELDS SHALL BE INSPECTED WITH DYE PENETRANT OR MAGNETIC PARTICLE TO MEET THE ACCEPTANCE CRITERIA OF AWS D1.1. REPAIR ALL WELDS AS NECESSARY.

C. INSPECTION SHALL BE PERFORMED BY AN AWS CERTIFIED WELD INSPECTOR.

D. IT IS THE CONTRACTORS RESPONSIBILITY TO PROVIDE BURNING/WELDING PERMITS AS REQUIRED BY LOCAL GOVERNING AUTHORITY AND IF REQUIRED SHALL HAVE FIRE DEPARTMENT DETAIL FOR ANY WELDING ACTIVITY.

E. ALL ELECTRODES TO BE LOW HYDROGEN, MATCHING FILLER METAL, PER AWS D1.1, UNLESS NOTED OTHERWISE.

F. MINIMUM WELD SIZE TO BE 0.1875 INCH FILLET WELDS, UNLESS NOTED OTHERWISE.

G. PRIOR TO FIELD WELDING GALVANIZING MATERIAL, CONTRACTOR SHALL GRIND OFF GALVANIZING ¼” BEYOND ALL FIELD WELD SURFACES. AFTER WELD AND WELD INSPECTION IS COMPLETE, REPAIR ALL GROUND AND WELDED SURFACES WITH ZRC GALVILITE COLD GALVANIZING COMPOUND PER ASTM A780 AND MANUFACTURERS RECOMMENDATIONS.

H. THE CONTRACTOR SHALL PROVIDE ADEQUATE SHORING AND/OR BRACING WHERE REQUIRED DURING CONSTRUCTION UNTIL ALL CONNECTIONS ARE COMPLETE.

I. ANY FIELD CHANGES OR SUBSTITUTIONS SHALL HAVE PRIOR APPROVAL FROM THE ENGINEER, AND DISH WIRELESS L.L.C. PROJECT MANAGER IN WRITING



5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



AMERICAN TOWER®
A.T. ENGINEERING SERVICE, PLLC
3500 REGENCY PARKWAY
SUITE 100
CARY, NC 27518
PHONE: (919) 468-0112

DRAWN BY:	CHECKED BY:	APPROVED BY:
AP	SRF	SRF

RFDS REV #: -----

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
0	01/05/2022	ISSUED FOR CONSTRUCTION



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

A&E PROJECT NUMBER
418609–13733434_D3

DISH Wireless L.L.C.
PROJECT INFORMATION
BOBOS00030A
87 WEST QUASSET ROAD
WOODSTOCK, CT 06281

SHEET TITLE
GENERAL NOTES

SHEET NUMBER
GN-4



usps tracking



Sign in



All



Books



Shopping



News



Videos



More

Tools

About 20,400,000 results (0.43 seconds)

Track your package

Data provided by USPS



Tracking number 9505510391962117623717

Delivered

May 02, 11:59AM
Woodstock, CT

Quasset Hill Farm LLC - Property Owner



View details on USPS



Call 1-800-275-8777



Track another package

<https://tools.usps.com>

USPS.com® - USPS Tracking®

Your **tracking** number can be found in the following places: · The shipping confirmation email you received from an online retailer · The bottom peel-off portion of ...

[Find USPS Locations](#) · [Schedule a Pickup](#) · [Schedule a Redelivery](#) · [PO Locator](#)

<https://www.usps.com>

USPS: Welcome

Welcome to **USPS**.com. Find information on our most convenient and affordable shipping and mailing services. Use our quick tools to find locations, ...

<https://www.usps.com> › [manage](#)

Receive Mail & Packages | USPS

Track USPS package deliveries, get **tracking** text and email notifications, forward mail, change your address, and learn about setting up PO boxes or home ...

<https://faq.usps.com> › [topic](#) › [usps-tracking-](#)

USPS Tracking ®

USPS Tracking® provides end-to-end item tracking. With the tracking number, you can check delivery progress online, by phone, and by text.

<https://faq.usps.com> › [article](#) › [USPS-Tracking-The-Basics](#)

USPS Tracking® - The Basics

USPS Tracking® service provides end-to-end item tracking. This article provides in-depth information on how to use the service, what information the service ...

How does USPS Tracking® work?: [Add tracki...](#) [Receive automatic notifications:](#) [How can I ...](#)
What is USPS Tracking®?: [My mailpiece has...](#)

<https://usps-track.us>

USPS Tracking - Track Package

USPS General Inquiry about your Package Status. Call Above Tollfree number for your Present



usps tracking



Sign in



Books

Shopping

News

Videos

More

Tools

About 20,400,000 results (0.43 seconds)

Track your package

Data provided by USPS

Tracking number 9505510391962117623694

Delivered

April 29, 11:43AM

Woburn, MA

American Tower Corporation - Tower Operator/Owner

View details on USPS

Call 1-800-275-8777

Track another package

https://tools.usps.com

USPS.com® - USPS Tracking®

Your **tracking** number can be found in the following places: · The shipping confirmation email you received from an online retailer · The bottom peel-off portion of ...

[Find USPS Locations](#) · [Schedule a Pickup](#) · [Schedule a Redelivery](#) · [PO Locator](#)

https://www.usps.com

USPS: Welcome

Welcome to **USPS**.com. Find information on our most convenient and affordable shipping and mailing services. Use our quick tools to find locations, ...

https://www.usps.com › manage

Receive Mail & Packages | USPS

Track USPS package deliveries, get **tracking** text and email notifications, forward mail, change your address, and learn about setting up PO boxes or home ...

https://faq.usps.com › topic › usps-tracking-

USPS Tracking ®

USPS Tracking® provides end-to-end item tracking. With the tracking number, you can check delivery progress online, by phone, and by text.

https://faq.usps.com › article › USPS-Tracking-The-Basics

USPS Tracking® - The Basics

USPS Tracking® service provides end-to-end item tracking. This article provides in-depth information on how to use the service, what information the service ...

How does USPS Tracking® work?: Add tracki... Receive automatic notifications: How can I ... What is USPS Tracking®?: My mailpiece has...

https://usps-track.us

USPS Tracking - Track Package

USPS General Inquiry about your Package Status. Call Above Tollfree number for your Present


About 20,400,000 results (0.43 seconds)

Track your package

Data provided by USPS


Tracking number 9505510391962117623700

Delivered




April 29, 12:34PM


Woodstock, CT



View details on USPS



Call 1-800-275-8777



Track another package

https://tools.usps.com

USPS.com® - USPS Tracking®

Your **tracking** number can be found in the following places: · The shipping confirmation email you received from an online retailer · The bottom peel-off portion of ...

[Find USPS Locations](#) · [Schedule a Pickup](#) · [Schedule a Redelivery](#) · [PO Locator](#)

https://www.usps.com

USPS: Welcome

Welcome to **USPS**.com. Find information on our most convenient and affordable shipping and mailing services. Use our quick tools to find locations, ...

https://www.usps.com › manage

Receive Mail & Packages | USPS

Track USPS package deliveries, get **tracking** text and email notifications, forward mail, change your address, and learn about setting up PO boxes or home ...

https://faq.usps.com › topic › usps-tracking-

USPS Tracking ®

USPS Tracking® provides end-to-end item tracking. With the tracking number, you can check delivery progress online, by phone, and by text.

https://faq.usps.com › article › USPS-Tracking-The-Basics

USPS Tracking® - The Basics

USPS Tracking® service provides end-to-end item tracking. This article provides in-depth information on how to use the service, what information the service ...

How does USPS Tracking® work?: Add tracki... Receive automatic notifications: How can I ...
What is USPS Tracking®?: My mailpiece has...

https://usps-track.us

USPS Tracking - Track Package


USPS General Inquiry about your Package Status. Call Above Tollfree number for your Present

About 20,400,000 results (0.43 seconds)

Track your package

Data provided by USPS


Tracking number 9505510391962117623724

Delivered 


April 29, 12:34PM

Woodstock, CT


Ashley Stephens - Woodstock Land Use Administrator & Zoning Enforcement Official



View details on USPS



Call 1-800-275-8777



Track another package

https://tools.usps.com

USPS.com® - USPS Tracking®

Your **tracking** number can be found in the following places: · The shipping confirmation email you received from an online retailer · The bottom peel-off portion of ...

[Find USPS Locations](#) · [Schedule a Pickup](#) · [Schedule a Redelivery](#) · [PO Locator](#)

https://www.usps.com

USPS: Welcome

Welcome to **USPS**.com. Find information on our most convenient and affordable shipping and mailing services. Use our quick tools to find locations, ...

https://www.usps.com › manage

Receive Mail & Packages | USPS

Track USPS package deliveries, get **tracking** text and email notifications, forward mail, change your address, and learn about setting up PO boxes or home ...

https://faq.usps.com › topic › usps-tracking-

USPS Tracking ®

USPS Tracking® provides end-to-end item tracking. With the tracking number, you can check delivery progress online, by phone, and by text.

https://faq.usps.com › article › USPS-Tracking-The-Basics

USPS Tracking® - The Basics

USPS Tracking® service provides end-to-end item tracking. This article provides in-depth information on how to use the service, what information the service ...

How does USPS Tracking® work?: Add tracki... Receive automatic notifications: How can I ...
What is USPS Tracking®?: My mailpiece has...

https://usps-track.us

USPS Tracking - Track Package

USPS General Inquiry about your Package Status. Call Above Tollfree number for your Present



April 19, 2022

Quasset Hill Farm LLC
PO BOX 113
Woodstock, CT 06281

Re: Tower Share Application – Dish Wireless Site # 13733434
Dish Wireless Telecommunications Facility @ 87 West Quasset Road, Woodstock, CT 06281

Dear Property Owner:

Dish Wireless (“Dish”) is proposing a wireless telecommunications facility on an existing one hundred forty nine (149) foot tall monopole tower at 87 West Quasset Road, Woodstock, CT 06281 (Latitude: 41.9297847, Longitude: -71.98933794) and within the existing fenced compound on the above referenced property. The monopole tower is owned and operated by American Tower Corporation. The subject property is owned by Quasset Hill Farm LLC. The tower was approved by the Siting Council on November 17, 2011, docket number 415.

Dish proposes to install a five (5) foot by seven (7) foot metal platform within the existing fenced compound to accommodate two (2) cabinets and related equipment, and to install three (3) antennas, a single antenna mount, six (6) RRUs, and cables on the existing tower at one hundred twenty seven (127) feet as more particularly detailed and described on the enclosed Construction Drawings. The overall height of the tower will remain at 149 feet and no changes will be made to the compound dimensions.

This letter is intended to serve as the required notice to the property owner. As required by Regulations of Connecticut State Agencies (“RCSA”) 16-50j-73 the Connecticut Siting Council (“CSC”) has been notified of this proposal and will review this application. Please accept this letter as notification pursuant to RCSA 16-50j-73.

The enclosed letter and attachments to the CSC fully describe Dish’s proposal for the site. However, if you have any questions or require any additional information concerning our plans or the CSC procedures, please contact me at 443-677-0144 or contact Melanie Bachmann, Acting Executive Director of the CSC at 860-972-2935.

Respectfully Submitted,

Jack Andrews
Zoning Manager, Centerline Communications
10130 Donleigh Drive
Columbia, MD 21046



April 19, 2022

Blake Paynter
Project Manager, Site Development
American Tower Corporation
10 Presidential Way
Woburn, MA 01801

Re: Tower Share Application – Dish Wireless Site # 13733434
Dish Wireless Telecommunications Facility @ 87 West Quasset Road, Woodstock, CT 06281

Dear Mr. Paynter:

Dish Wireless (“Dish”) is proposing a wireless telecommunications facility on an existing one hundred forty nine (149) foot tall monopole tower at 87 West Quasset Road, Woodstock, CT 06281 (Latitude: 41.9297847, Longitude: -71.98933794) and within the existing fenced compound on the above referenced property. The monopole tower is owned and operated by American Tower Corporation. The subject property is owned by Quasset Hill Farm LLC. The tower was approved by the Siting Council on November 17, 2011, docket number 415.

Dish proposes to install a five (5) foot by seven (7) foot metal platform within the existing fenced compound to accommodate two (2) cabinets and related equipment, and to install three (3) antennas, a single antenna mount, six (6) RRUs, and cables on the existing tower at one hundred twenty seven (127) feet as more particularly detailed and described on the enclosed Construction Drawings. The overall height of the tower will remain at 149 feet and no changes will be made to the compound dimensions.

This letter is intended to serve as the required notice to the tower owner. As required by Regulations of Connecticut State Agencies (“RCSA”) 16-50j-73 the Connecticut Siting Council (“CSC”) has been notified of this proposal and will review this application. Please accept this letter as notification pursuant to RCSA 16-50j-73.

The enclosed letter and attachments to the CSC fully describe Dish’s proposal for the site. However, if you have any questions or require any additional information concerning our plans or the CSC procedures, please contact me at 443-677-0144 or contact Melanie Bachmann, Acting Executive Director of the CSC at 860-972-2935.

Respectfully Submitted,

Jack Andrews
Zoning Manager, Centerline Communications
10130 Donleigh Drive
Columbia, MD 21046



April 19, 2022

John Mehr, Town Manager
761 Old Main Street
Rocky Hill, CT 06067

Re: Tower Share Application – Dish Wireless Site # 13733434
Dish Wireless Telecommunications Facility @ 87 West Quasset Road, Woodstock, CT 06281

Dear Mr. Mehr:

Dish Wireless (“Dish”) is proposing a wireless telecommunications facility on an existing one hundred forty nine (149) foot tall monopole tower at 87 West Quasset Road, Woodstock, CT 06281 (Latitude: 41.9297847, Longitude: -71.98933794) and within the existing fenced compound on the above referenced property. The monopole tower is owned and operated by American Tower Corporation. The subject property is owned by Quasset Hill Farm LLC. The tower was approved by the Siting Council on November 17, 2011, docket number 415.

Dish proposes to install a five (5) foot by seven (7) foot metal platform within the existing fenced compound to accommodate two (2) cabinets and related equipment, and to install three (3) antennas, a single antenna mount, six (6) RRUs, and cables on the existing tower at one hundred twenty seven (127) feet as more particularly detailed and described on the enclosed Construction Drawings. The overall height of the tower will remain at 149 feet and no changes will be made to the compound dimensions.

This letter is intended to serve as the required notice to the chief elected official/municipal officer. As required by Regulations of Connecticut State Agencies (“RCSA”) 16-50j-73 the Connecticut Siting Council (“CSC”) has been notified of this proposal and will review this application. Please accept this letter as notification pursuant to RCSA 16-50j-73.

The enclosed letter and attachments to the CSC fully describe Dish’s proposal for the site. However, if you have any questions or require any additional information concerning our plans or the CSC procedures, please contact me at 443-677-0144 or contact Melanie Bachmann, Acting Executive Director of the CSC at 860-972-2935.

Respectfully Submitted,

Jack Andrews
Zoning Manager, Centerline Communications
10130 Donleigh Drive
Columbia, MD 21046



April 19, 2022

Ashley Stephens
Zoning Enforcement Officer
Town of Woodstock CT
415 Route 169
Woodstock, CT 06281

Re: Tower Share Application – Dish Wireless Site # 13733434
Dish Wireless Telecommunications Facility @ 87 West Quasset Road, Woodstock, CT 06281

Dear Ms. Stephens:

Dish Wireless (“Dish”) is proposing a wireless telecommunications facility on an existing one hundred forty nine (149) foot tall monopole tower at 87 West Quasset Road, Woodstock, CT 06281 (Latitude: 41.9297847, Longitude: -71.98933794) and within the existing fenced compound on the above referenced property. The monopole tower is owned and operated by American Tower Corporation. The subject property is owned by Quasset Hill Farm LLC. The tower was approved by the Siting Council on November 17, 2011, docket number 415.

Dish proposes to install a five (5) foot by seven (7) foot metal platform within the existing fenced compound to accommodate two (2) cabinets and related equipment, and to install three (3) antennas, a single antenna mount, six (6) RRUs, and cables on the existing tower at one hundred twenty seven (127) feet as more particularly detailed and described on the enclosed Construction Drawings. The overall height of the tower will remain at 149 feet and no changes will be made to the compound dimensions.

This letter is intended to serve as the required notice to the municipal planning agency. As required by Regulations of Connecticut State Agencies (“RCSA”) 16-50j-73 the Connecticut Siting Council (“CSC”) has been notified of this proposal and will review this application. Please accept this letter as notification pursuant to RCSA 16-50j-73.

The enclosed letter and attachments to the CSC fully describe Dish’s proposal for the site. However, if you have any questions or require any additional information concerning our plans or the CSC procedures, please contact me at 443-677-0144 or contact Melanie Bachmann, Acting Executive Director of the CSC at 860-972-2935.

Respectfully Submitted,

Jack Andrews
Zoning Manager, Centerline Communications
10130 Donleigh Drive
Columbia, MD 21046