BENZ STREET SOLAR CONNECTICUT SITING COUNCIL DOCUMENTS


FOR

Site/Electrical Layout, Grading/Drainage/Erosion Control/Landscaping

11

ANSONIA, CONNECTICUT

LOCATION MAP



SHEET INDEX

| 1 | | ı | |
|---|-----------|----|---|
| - | 5/22/2020 | 1 | COVER SHEET |
| 1 | 2/04/2019 | 2 | ALTA SURVEY (BY GODFREY HOFFMAN HODGE, LLC) |
| - | 5/22/2020 | 3 | SITE PLAN |
| - | 5/22/2020 | 4 | GRADING AND EROSION CONTROL PLAN |
| - | 5/22/2020 | 5 | SITE GRADING PLAN: DRAINAGE AREA #1 |
| - | 5/22/2020 | 6 | SITE GRADING PLAN: DRAINAGE AREA #2 |
| _ | 5/22/2020 | 7 | LANDSCAPE PLAN |
| _ | 5/22/2020 | 8 | KEY OBSERVATION POINTS |
| _ | 5/22/2020 | 9 | PROJECT CROSS SECTION |
| _ | 5/22/2020 | 10 | CIVIL NOTES |
| - | 5/22/2020 | 11 | CIVIL DETAILS |

DRAWING INDEX LEGEND

FILLED CIRCLE INDICATES DRAWING INCLUDED WITHIN THIS ISSUE

MOST RECENT REVISION NUMBER

MOST RECENT ISSUE OR REVISION DATE

- X/XX/202X X SHEET TITLE


CONTACT INFO:


RECORD LANDOWNER:
PLH, LLC
77 WATER STREET
8TH FLOOR
NEW YORK, NY 10005


OWNER/DEVELOPER:
ECOS ENERGY
222 SOUTH 9TH STREET
SUITE 1600
MINNEAPOLIS, MN 55402


CIVIL ENGINEER:
CLA ENGINEERS, INC.
317 MAIN STREET
NORWICH, CT 06360
TEL: 860-886-1966

SURVEYOR & WETLANDS DELINEATION:
GODFREY HOFFMAN HODGE, LLC
26 BROADWAY
NORTH HAVEN, CT 06085
TEL: 203-239-4217









LEGEND:

EXISTING PROPERTY LINE

PROPOSED FENCE

PROPOSED GRAVEL ACCESS ROAD

PROPOSED UNDERGROUND MV CABLE

PROPOSED OVERHEAD ELECTRIC

EXISTING CONTOUR

658, PROPOSED CONTOUR

26 x 2 SOLAR MODULE BOCK
13 x 2 SOLAR MODULE BOCK
50' WETLAND BUFFER AREA
WETLAND DELINEATION LINE & AREA
RIP-RAP BASIN OUTLET

CONSTRUCTION NOTES:


- 1. THE CONTRACTOR SHALL PERFORM ALL TREE REMOVAL ACTIVITIES ON SITE TO ALLOW FOR SEDIMENT TRAP INSTALLATION, NO GRUBBING IS TO OCCUR DURING TREE REMOVAL, PRIOR TO SEDIMENT TRAP INSTALLATION.
- 2. ALL SEDIMENT TRAP'S IDENTIFIED ON THE PLAN SHALL BE STAKED BY A REGISTERED SURVEYOR AND INSTALLED PER PLANS PRIOR TO ANY CONSTRUCTION ACTIVITY.
- 3. AS-BUILT DRAWINGS SHALL BE MAINTAINED BY THE CONTRACTOR THROUGHOUT THE CONSTRUCTION OF THE PROJECT.

EROSION CONTROL NOTES:


- DEVELOPER/CONTRACTOR TO OBTAIN A DEEP GENERAL STORMWATER PERMIT PRIOR TO BEGINNING CONSTRUCTION.
- 2. TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES SHALL BE INSTALLED BEFORE ANY SOIL DISTURBANCE.
- 3. THE AREA OF DISTURBANCE SHALL BE KEPT TO A MINIMUM. DISTURBED AREAS REMAINING IDLE FOR MORE THAN 14 DAYS SHALL BE STABILIZED.
- MEASURES SHALL BE TAKEN TO CONTROL EROSION WITHIN THE PROJECT AREA. SEDIMENT IN RUNOFF WATER SHALL BE TRAPPED AND RETAINED WITHIN THE PROJECT AREA USING APPROVED MEASURES.
- 5. WETLAND AREAS AND SURFACE AREAS SHALL BE PROTECTED FROM SEDIMENT. OFF-SITE SURFACE WATER AND RUNOFF FROM UNDISTURBED AREAS SHALL BE DIVERTED AWAY FROM DISTURBED AREAS WHERE FEASIBLE OR CARRIED THROUGH THE PROJECT AREA WITHOUT CAUSING EROSION. INTEGRITY OF DOWNSTREAM DRAINAGE SYSTEMS SHALL BE MAINTAINED.
- 6. ALL TEMPORARY EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE REMOVED AFTER FINAL SITE STABILIZATION. STABILIZATION MEASURES SUCH AS HYDRO-SEEDING OR APPLICATION OF HAY/MULCH OR SOIL NETTING SHALL BE APPLIED PRIOR TO REMOVAL OF TEMPORARY EROSION MEASURES AND INSPECTED WEEKLY UNTIL STABILIZATION IS COMPLETE. TEMPORARY EROSION CONTROL MEASURES MAY BE REMOVED ONCE STABILIZATION OF ALL SITE SOILS HAS BEEN ACHIEVED AND WRITTEN AUTHORIZATION TO DO SO HAS BEEN PROVIDED BY THE STORM-WATER AUTHORITY. TRAPPED SEDIMENT SHALL BE REMOVED IMMEDIATELY WITH TEMPORARY EROSION CONTROL METHODS AND LAWFULLY DISPOSED OF OFF-SITE. OTHER DISTURBED SOIL AREAS RESULTING FROM THE REMOVAL OF TEMPORARY MEASURES SHALL BE PERMANENTLY STABILIZED WITHIN THIRTY DAYS.

NOTES


SOLAR MODULE FOOTPRINT WITHIN THE FENCELINE OF THE PROJECT REPRESENTED IN THESE DOCUMENTS WILL BE ADJUSTED BASED ON TOPOGRAPHHICAL CONSTRAINTS PRESENTED BY SITE SLOPES AND STORMWATER BASINS. THE PROJECT FOOTPRINT IN THESE DOCUMENTS REPRESENTS THE PROJECT APPROVED BY THE CONNECTICUT SITING COUNCIL ON JANUARY 18, 2018





VEGETATED SWALE




CLA









KOP 4 - MIDDLE OF SITE LOOKING EAST




KOP 5 - EASTERN MIDDLE OF SITE LOOKING SOUTH




KOP 6 - SOUTH WEST OF SITE LOOKING EAST

CLA






KOP 3 - NORTHERN SITE, LOOKING SOUTH-EAST



KOP 2 - BENZ STREET LOOKING NORTH





KOP 1 - SOUTH OF BENZ STREET LOOKING NORTH-WEST




BENZ STREET SOLAR

KEY OBSERVATION POINTS





CLA



SPECIAL PROVISIONS FOR GRADING AND EROSION CONTROL

THE CONTRACTOR SHALL PROVIDE EROSION CONTROL MEASURES AS PLANNED AND SPECIFIED FOLLOWING BEST MANAGEMENT PRACTICES AS OUTLINED BY THE STATE OF CONNECTICUT AND BEING IN CONFORMANCE WITH THE NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES) GENERAL STORMWATER PERMIT. SEE THE STORMWATER POLLUTION PREVENTION PLAN (SWPPP) FOR EROSION CONTROL AND RESTORATION SPECIFICATIONS. UNLESS OTHERWISE NOTED OR MODIFIED HEREIN, ALL SECTIONS OF THE GENERAL CONDITIONS SHALL APPLY.

EXECUTION

- CLEARING AND GRUBBING
- A. THE CONTRACTOR SHALL BE REQUIRED TO REMOVE ALL TREES, STUMPS, BRUSH, AND DEBRIS WITHIN THE GRADING LIMITS SHOWN ON THE PLANS. THE CONTRACTOR IS TO REMOVE ONLY THOSE TREES WHICH ARE DESIGNATED BY THE OWNER'S REPRESENTATIVE FOR REMOVAL, AND SHALL EXERCISE EXTREME CARE AROUND EXISTING TREES TO BE SAVED.
- 2. TOPSOIL STRIPPING
- A. TOPSOIL SHALL BE STRIPPED FROM ALL ROADWAY AREAS THROUGH THE ROOT ZONE. TOPSOIL SHALL NOT BE STRIPPED OUTSIDE OF THE DESIGNATED DISTURBANCE AREAS.
- B. ANY TOPSOIL, THAT HAS BEEN STRIPPED, SHALL BE RE-SPREAD OR STOCKPILED WITHIN GRADING AREAS AND/OR USED AS FILL OUTSIDE OF THE DISTURBANCE AREAS, AS DIRECTED BY THE ENGINEER.
- EMBANKMENT CONSTRUCTION. A. EMBANKMENT CONSTRUCTION SHALL CONSIST OF THE PLACING OF SUITABLE FILL MATERIAL, AFTER TOPSOIL STRIPPING, ABOVE THE EXISTING GRADE. GENERALLY, EMBANKMENTS SHALL HAVE COMPACTED SUPPORT SLOPES OF TWO AND A HALF FEET HORIZONTAL TO ONE FOOT VERTICAL. THE MATERIAL FOR EMBANKMENT CONSTRUCTION SHALL BE OBTAINED FROM THE ACCESS ROAD EXCAVATION (SEE GEOTECHNICAL REPORT FOR RESTRICTIONS), OR ANY SUITABLE, APPROVED SOIL OBTAINED OFFSITE BY CONTRACTOR, AS DIRECTED OR APPROVED BY THE ENGINEER. THIS MATERIAL SHALL BE
- B. SIDE SLOPES GREATER THAN 2.5:1 WILL NOT BE PERMITTED, UNLESS OTHERWISE NOTED ON THE PLAN.

PLACED IN LIFTS NOT TO EXCEED 9".

- TESTING SHALL BE PERFORMED BY A DESIGNATED INDEPENDENT TESTING AGENCY
- 2. SUBMIT TESTING AND INSPECTION RECORDS SPECIFIED TO THE CIVIL ENGINEER OF RECORD FOR
- A. THE ENGINEER WILL REVIEW THE TESTING AND INSPECTION RECORDS TO CHECK CONFORMANCE WITH THE DRAWINGS AND SPECIFICATIONS. THE ENGINEER'S REVIEW DOES NOT RELIEVE THE CONSTRUCTION CONTRACTOR FROM THE RESPONSIBILITY FOR CORRECTING DEFECTIVE WORK. PROOF ROLLING:
- A. PROOF-ROLLING SHALL BE PERFORMED IN THE PRESENCE OF THE GEOTECHNICAL ENGINEER OR QUALIFIED GEOTECHNICAL REPRESENTATIVE USING A FULLY LOADED TANDEM AXLE DUMP TRUCK WITH A MINIMUM GROSS WEIGHT OF 25 TONS OR A FULLY LOADED WATER TRUCK WITH AN EQUIVALENT AXLE LOADING. PROOF-ROLLING ACCEPTANCE STANDARDS INCLUDE NO RUTTING GREATER THAN 1.5 INCHES, AND NO "PUMPING" OF THE SOIL BEHIND THE LOADED TRUCK.
- 4. SIEVE ANALYSIS: A. SIEVE ANALYSIS SHALL BE CONDUCTED IN ACCORDANCE WITH AASHTO T27
- A. PROCTORS SHALL BE DETERMINED IN ACCORDANCE WITH ASTM D-1557
- 6. ATTERBERG LIMITS: A. ATTERBERG LIMITS SHALL BE DETERMINED IN ACCORDANCE WITH AASHTO T89 AND T90
- 7. MOISTURE DENSITY (NUCLEAR DENSITY):
- A. MOISTURE DENSITY TESTING SHALL BE DONE IN ACCORDANCE WITH AASHTO T310

SUBGRADE COMPACTION, TEST ROLLING AND AGGREGATE BASE COMPACTION:

- 1. FILL MATERIAL A. SOILS USED AS FILL MATERIAL SHALL BE TESTED FOR GRAIN SIZE ANALYSIS, MOISTURE CONTENT, ATTERBERG LIMITS ON FINES CONTENT, AND PROCTOR TESTS (MODIFIED DRY
 - a. FOR PLACED & COMPACTED FILLS, PROVIDE ONE COMPACTION TEST PER LIFT FOR EVERY 1000 FT OF ROAD LENGTH. INCLUDE THE LOCATION, DRY DENSITY, MOISTURE CONTENT, AND COMPACTION PERCENT BASED ON MODIFIED PROCTOR MAXIMUM DRY
- B. IN ROADWAY CUT AREAS, OR WHERE EMBANKMENT CONSTRUCTION REQUIRES LESS THAN 12 INCHES OF FILL PLACEMENT. COMPACT TO A MINIMUM OF 95 PERCENT OF THE MATERIAL'S MODIFIED PROCTOR MAXIMUM DRY DENSITY.
- 2. COMPACTED SUBGRADE:
- A. THE ENTIRE SUBGRADE SHALL BE PROOF-ROLLED PRIOR TO THE PLACEMENT OF THE
- AGGREGATE BASE TO IDENTIFY AREAS OF UNSTABLE SUBGRADE. B. IF PROOF ROLLING DETERMINES THAT THE SUBGRADE STABILIZATION CANNOT BE
- ACHIEVED, THE FOLLOWING ALTERNATIVES WILL BE IMPLEMENTED:
- a. REMOVE UNSUITABLE MATERIAL AND REPLACE WITH SUITABLE EMBANKMENT
- SCARIFY, DRY, AND RECOMPACT SUBGRADE AND PERFORM ADDITIONAL PROOF ROLL. INCREASE ROAD BASE THICKNESS.
- C. PROVIDE 1 MOISTURE DENSITY COMPACTION TESTS FOR EVERY 1000 L.F. OF ROAD LENGTH. COMPACTED SUBGRADE MUST BE COMPACTED TO A MINIMUM OF 95% MODIFIED PROCTOR MAXIMUM DRY DENSITY AT ±3% OF OPTIMUM MOISTURE CONTENT FOR GRANULAR SOILS AND AT -1 TO +3% OF OPTIMUM MOISTURE CONTENT FOR COHESIVE
- SOILS. 3. AGGREGATE BASE:
 - A. AGGREGATE BASE SHALL BE PROOF-ROLLED OVER THE ENTIRE LENGTH. PROVIDE 1 SIEVE ANALYSIS PER 2500 CY OF ROAD BASE PLACED.
 - a. IF PROOF ROLLING DETERMINES THAT THE ROAD IS UNSTABLE, ADDITIONAL AGGREGATE SHALL BE ADDED UNTIL THE UNSTABLE SECTION IS ABLE TO PASS A PROOF ROLL.

| TABLE 1: TESTING SCHEDULE SUMMARY | | | | | |
|-----------------------------------|---|--|--|--|--|
| LOCATION | TEST | FREQUENCY | | | |
| STRUCTURAL FILL | GRAIN SIZE ANALYSIS, MOISTURE CONTENT, ATTERBERG LIMITS ON FINES CONTENT, AND PROCTOR | 1 PER MAJOR SOIL TYPE | | | |
| | MOISTURE DENSITY | 1 PER 2,000 CY OR MIN. 1 PER LIFT | | | |
| COMPACTED | PROOF-ROLL | ENTIRE LENGTH | | | |
| SUBGRADE | MOISTURE DENSITY TEST (NUCLEAR DENSITY) | 1 PER 1,000 FT OR MIN. 5 FOR THE SITE | | | |
| AGGREGATE BASE | PROOF-ROLL | ENTIRE LENGTH | | | |
| | SIEVE ANALYSIS | 1 PER 2,500 CY | | | |

- 1. THE PLANIMETRIC FEATURES, GROUND SURFACE CONTOURS ON A LIDAR SURFACE PROVIDED
- 2. NO GRADING OR SOIL DISTURBANCE IS PERMITTED OUTSIDE OF THE GRADING LIMITS IDENTIFIED ON THE PLANS.
- 3. GRADE ALL PROPOSED ROADS TO THE SLOPES PROPOSED ON THE PLANS. 4. THE CONTRACTOR IS RESPONSIBLE FOR MAINTAINING DRAINAGE THROUGHOUT THE CONSTRUCTION OF THIS PROJECT. CONSTRUCTION ACTIVITIES SHALL NOT BLOCK THE NATURAL OR MANMADE CREEKS OR DRAINAGE SWALES CAUSING RAINWATER TO POND. ADDITIONAL CULVERTS IN EXCESS OF THOSE ON THE PLANS MAY BE REQUIRED AS APPROVED
- BY THE ENGINEER. 5. THE CONTRACTOR SHALL NOTIFY DIGSAFE AT LEAST 48 HOURS BEFORE EXCAVATION
- ACTIVITIES COMMENCE. WETLAND INFORMATION SHOWN ON THE PLAN WAS PROVIDED BY ROB HELLSTROM LAND SURVEYING AND FLAGGED BY HIGHLANDS SOILS. THE GENERAL CONTRACTOR SHALL VERIFY THAT ALL WETLAND PERMITS HAVE BEEN SUBMITTED AND APPROVED PRIOR TO
- CONSTRUCTION COMMENCING. 7. ELECTRICAL COLLECTION SYSTEM SHOWN ON THE PLAN SHALL BE CONSIDERED PRELIMINARY CONTRACTOR SHALL REFER TO FINAL ELECTRICAL DESIGN PLANS FOR ACTUAL DESIGN LOCATIONS.

STORMWATER POLLUTION PREVENTION PLAN (SWPCP)

- REFER TO THE SWPPP BOOKLET FOR SEDIMENT AND EROSION CONTROL PROCEDURES,
- LOCATIONS OF BMPs, DETAILS, AND INSPECTION INFORMATION. 2. ALL AREAS DISTURBED DURING CONSTRUCTION ACTIVITIES AND NOT COVERED BY ROAD
- SURFACING MATERIALS, SHALL BE SEEDED IN ACCORDANCE WITH THE SWPPP PLAN. 3. TEMPORARY EROSION CONTROL SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR. THE TEMPORARY EROSION CONTROL PLAN SHALL BE IN ACCORDANCE WITH STATE OF CONNETICUT, THE EPA, AND THE SWPCP ON FILE.

SLOPE STABILIZATION:

ALL AREAS DESIGNATED ON THE PLAN FOR SLOPE STABILIZATION SHALL BE GRADED AND COMPACTED, SMOOTH AND CLEAN TO THE FINISH CONTOURS SHOWN ON THE PLAN, WITH A MINIMUM OF 4 INCHES OF TOPSOIL PLACED ON THE AREA. STABILIZATION SHALL BE ACHIEVED IN ONE OF TWO MANNERS:

1) HAND-PLACED RIPRAP

2) SEED WITH EROSION CONTROL AND REVEGITATION MAT (ECRM)

1. PLACEMENT OF RIP-RAP

RIPRAP HAND PLACED. HAND-PLACED RIPRAP SHALL CONSIST OF ROUGH UNHEWN QUARRY STONES, APPROXIMATELY RECTANGULAR, PLACED DIRECTLY ON THE SPECIFIED SLOPES OR SURFACES. IT SHALL BE SO LAID THAT THE WEIGHT OF THE LARGE STONES IS CARRIED BY THE SOIL RATHER THAN BY ADJACENT STONES. STONES SHALL WEIGH BETWEEN 50 AND 150 LB. EACH AND AT LEAST 60 % OF THEM SHALL WEIGH MORE THAN 100 LB. EACH WHEN USED ON EMBANKMENT CONSTRUCTION. RIP RAP FOR BMPS SHALL BE 6"-8" DIA. PREPARATION FOR HAND-PLACED RIP RAP. BEFORE ANY RIP RAP IS PLACED, THE SURFACE TO BE COVERED SHALL BE FULLY COMPACTED AND GRADED TO THE REQUIRED SLOPE PLACE MIRAFITM8 OR APPROVED EQUAL GEOTEXTILE ON SLOPE. RIP RAP ON SLOPES SHALL COMMENCE COMMENCE IN A TRENCH BELOW THE TOW OF THE SLOPE AND SHALL PROGRESS UPWARD, EACH STONE BEING LAID BY HAND PERPENDICULAR TO THE SLOPE WITH THE LONG DIMENSION VERTICAL, FIRMLY BEDDED AGAINST THE SLOPE AND AGAINST THE ADJOINING STONE, WITH ENDS IN CONTACT, AND WITH WELL-BROKEN JOINTS. SIMILAR METHODS SHALL BE USED WHEN LAYING RIPRAP ON STREAM BEDS, IN DITCHES, AND ON LEVEL SURFACES.

THE FINISHED SURFACE OF THE RIPRAP SHALL PRESENT AN EVEN, TIGHT SURFACE, NOT LESS THAN 12 INCHES THICK, MEASURED PERPENDICULAR TO THE SLOPE.

THE STONES WEIGHING MORE THAN 100 LB. SHALL BE WELL DISPERSED THROUGHOUT THE AREA WITH THE 50-100 LB. STONES LAID BETWEEN THEM IN SUCH A MANNER THAT ALL STONES WILL BE IN CLOSE CONTACT. THE REMAINING VOIDS SHALL BE FILLED WITH SPALLS OF SUITABLE SIZE AND WELL TAMPED TO PRODUCE A FIRM AND COMPACT REVETMENT.

2. STABILIZATION WITH EROSION CONTROL AND REVEGITATION MAT (ECRM) 1) AREA MUST BE GRADED SMOOTH AND CLEAN TO FINISH GRADES, AND COMPACTED.

2) SEED AND MULCH AREA. USE SEED MIX APPROVED BY THE ENGINEER.

AND PERIMETER SIDES WHERE MAT IS TO BE INSTALLED.

- 3) INSTALL ECRM PER MANUFACTURER'S INSTRUCTIONS, HOWEVER THESE MUST INCLUDE THE FOLLOWING MINIMUM REQUIREMENTS:
 - A) GRADE GROUND TO FINISH CONTOURS. REMOVE ALL ROCKS, DIRT CLODS, STUMPS, ROOTS, TRASH, AND OTHER OBSTRUCTIONS LYING IN DIRECT CONTACT
 - WITH THE SOIL SURFACE. B) DIG MAT ANCHOR TRENCHES (MINIMUM 12"DEEP, 6" WIDE) AT TERMINAL ENDS
 - C) INSTALL MAT BY ROLLING UPHILL PARALLEL TO WATER FLOW, STARTING AT TRENCH. OVERLAP ROLLS BY MINIMUM OF 3". FASTEN TO GROUND WITH 18" PINS AND 1 1/2" WASHERS, OR EQUIVALENT. PIN MAT AT ENDS, AND EVERY 3' TO 5' ALONG OVERLAPS. DO NO STRETCH MAT. SPLICING ROLLS SHOULD BE DONE IN A CHECK SLOT. BACKFILL TO COVER ENDS AND FASTENERS, ROLLING MAT ACROSS BACKFILL AND PIN AGAIN.

FOR MAT USE MIRAFI MIRAMAT TM8 OR EQUIVALENT

INVASIVE SPECIES

- 1. ALL EQUIPMENT SHALL BE INSPECTED UPON ARRIVAL. EQUIPMENT ARRIVING WITH OBSERVABLE SOIL OR PLANT FRAGMENTS WILL BE REMOVED AND CLEANED.
- 2. HAY BALES ARE NOT BE USED ON SITE; ONLY WEED-FREE STRAW BALES ARE
- APPROVED.
- 3. OFF-SITE TOPSOIL MUST BE FREE OF INVASIVE SPECIES. THE ENGINEER SHALL BE NOTIFIED OF THE TOPSOIL SOURCE 6 WEEKS BEFORE DELIVERY

SEDIMENTATION AND EROSION CONTROL PLAN

CONTACT: STEVE BROYER **ECOS ENERGY** 222 SOUTH 9TH STREET

> **SUITE 1600** MINNEAPOLIS MN 55402

THE PURPOSE OF THIS PROJECT IS TO INSTALL APPROXIMATELY 6136 SOLAR MODULES AND ASSCOCIATED ELECTICAL EQUIPMENT FOR POWER GENERATION.

THE TOTAL AREA OF THE PROJECT SITE IS APPROXIMATELY 12.7 ACRES AND THE TOTAL AREA OF THE SITE THAT IS EXPECTED TO BE DISTURBED BY CONSTRUCTION ACTIVITIES IS 10.7 ACRES.

THE EROSION & SEDIMENTATION CONTROL PLAN AND DETAILS HAVE BEEN DEVELOPED AS A STRATEGY TO CONTROL SOIL EROSION AND SEDIMENTATION DURING AND AFTER CONSTRUCTION. THIS PLAN IS BASED ON THE "2002 CONNECTICUT GUIDELINES FOR SOIL EROSION AND SEDIMENT CONTROL" BY THE CONNECTICUT COUNCIL ON SOIL AND WATER CONSERVATION IN COOPERATION WITH THE CONNECTICUT DEEP.

IN THE AREAS OF SOLAR PANEL INSTALLATION, THERE ARE SEVERAL ACTIVITIES (SITE GRADING, FOOTING INSTALLATION, PANEL INSTALLATION, AND ELECTRICAL TRENCH WORK) THAT WILL DISTURB SOIL. SOIL MUST BE PROMPTLY STABILIZED AFTER EACH ACTIVITY.

THIS PROJECT WILL NOT BE PHASED. THE DEVELOPMENT WILL FOLLOW THE CONSTRUCTION SEQUENCE PROVIDED ON THIS PLAN.

THE PROPOSED LOCATIONS OF SILTATION AND EROSION CONTROL MEASURES ARE SHOWN ON THE PLANS. THE CONTRACTOR SHALL PROVIDE SILT FENCE, HAY BALES, EROSION MAT, STONE CHECK DAMS, A CONSTRUCTION ENTRANCE, AND/OR OTHER EROSION CONTROL MEASURES AS NEEDED OR DIRECTED BY THE ENGINEER OR TOWN STAFF TO ADEQUATELY PREVENT SEDIMENT TRANSPORT.

EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE INSTALLED PRIOR TO SITE

THE CONTRACTOR SHALL INSPECT, REPAIR AND/OR REPLACE EROSION CONTROL MEASURES EVERY 7 DAYS AND IMMEDIATELY FOLLOWING ANY SIGNIFICANT RAINFALL OR SNOW MELT. SEDIMENT DEPOSITS MUST BE REMOVED BEFORE DEPOSITS REACH APPROXIMATELY ONE HALF THE HEIGHT OF THE BARRIER. SEDIMENT CONTROL DEVICES SHALL REMAIN IN PLACE AND BE MAINTAINED BY THE CONTRACTOR UNTIL AREAS UPSLOPE ARE PERMANENTLY STABILIZED.

STAKED HAY BALE SILT BARRIERS OR SILT FENCE SHALL BE INSTALLED AROUND ANY TEMPORARYSTOCKPILE AREAS. TEMPORARY VEGETATIVE COVER MAY BE REQUIRED (SEE NOTE).

CONTINUOUS DUST CONTROL USING WATER OR APPROVED EQUAL SHALL BE PROVIDED FOR ALL EARTH STOCKPILES, EARTH PILED ALONG EXCAVATIONS, SURFACES OF BACKFILLED TRENCHES AND GRAVELED ROADWAY SURFACES. THE USE OF CALCIUM CHLORIDE FOR DUST CONTROL SHALL NOT BE ALLOWED.

IF DEWATERING IS NECESSARY DURING ANY TIME OF CONSTRUCTION A CLEAR WATER DISCHARGE SHALL BE PROVIDED AS SHOWN IN THE HAY-BALE BARRIER DEWATERING DETAIL OR ALTERNATE METHOD PROPOSED BY THE CONTRACTOR AND APPROVED BY THE ENGINEER.

ALL DISTURBED AREAS SHALL BE RESTORED PER THE SLOPE STABILIZATION AND PERMANENT VEGETATION DETAILS. ALL DISTURBED AREAS THAT ARE SLOPED LESS THAN THREE HORIZONTAL TO ONE VERTICAL (3:1) SLOPE SHALL BE LOAMED. SEEDED. FERTILIZED AND MULCHED PER THE PERMANENT VEGETATIVE COVER SPECIFICATIONS. EROSION CONTROL MATTING SHALL BE PROVIDED ON ALL DISTURBED AREAS THAT ARE SLOPED MORE THAN THREE HORIZONTAL TO ONE VERTICAL (3:1).

IF FINAL SEEDING OF DISTURBED AREAS IS NOT TO BE COMPLETED BEFORE OCTOBER 15, THE CONTRACTOR SHALL PROVIDE TEMPORARY MULCHING (DORMANT SEEDING MAY BE ATTEMPTED AS WELL) TO PROTECT THE SITE AND DELAY PERMANENT SEEDING.

WHEN FEASIBLE. TEMPORARY SEEDING OF DISTURBED AREAS THAT HAVE NOT BEEN FINISHED GRADED SHALL BE COMPLETED PRIOR TO OCTOBER 15.

ON EACH FRIDAY AND ALSO ON THE DAY BEFORE ANY RAIN FORECAST OF 0.5 INCHES OR MORE, THE CONTRACTOR SHALL HAY MULCH ALL EXPOSED SOIL.

ANY EROSION WHICH OCCURS WITHIN THE DISTURBED AREAS SHALL BE IMMEDIATELY REPAIRED AND STABILIZED. DURING THE CONSTRUCTION PHASE. INTERCEPTED SEDIMENT SHALL BE RETURNED TO THE SITE. POST SEEDING, INTERCEPTED SEDIMENT, IF ANY, SHALL BE DISPOSED OF IN A MANNER APPROVED BY THE TOWN AND ENGINEER.

EROSION AND SEDIMENTATION CONTROL MEASURES SHALL REMAIN IN PLACE UNTIL VEGETATION IS RE-ESTABLISHED OR SLOPES ARE STABILIZED AND REMOVAL IS APPROVED BY THE ENGINEER.

UNFORESEEN PROBLEMS WHICH ARE ENCOUNTERED IN THE FIELD SHALL BE SOLVED ACCORDING TO THE "2002 CONNECTICUT GUIDELINES FOR SOIL EROSION AND SEDIMENT CONTROL" BY THE CONNECTICUT COUNCIL ON SOIL AND WATER CONSERVATION IN COOPERATION WITH THE CONNECTICUT DEEP.

THE CONTRACTOR SHALL PROVIDE THE NAME AND EMERGENCY CONTACT INFORMATION FOR THE PROJECT PERSONNEL RESPONSIBLE FOR EROSION AND SEDIMENTATION CONTROLS PRIOR TO THE START OF CONSTRUCTION.

THE OWNER WILL EMPLOY A CERTIFIED SOIL SCIENTIST TO PERFORM WEEKLY EROSION & SEDIMENTATION CONTROL INSPECTION.

INSPECTOR.

ROUTINE REPAIRS OR MODIFICATIONS SHALL BE COMPLETED BY THE CONTRACTOR WITHIN 48 HOURS AFTER DIRECTION BY THE INSPECTOR. EMERGENCY REPAIRS SHALL BE COMPLETED IMMEDIATELY UPON DIRECTION BY THE

THE WETLANDS ENFORCEMENT OFFICER SHALL BE NOTIFIED AT LEAST 2 BUSINESS DAYS PRIOR TO

CONSTRUCTION TO INSPECT EROSION CONTROLS STATE AND FEDERAL PERMITS REQUIRED: THIS PROJECT REQUIRES A PERMIT FROM THE STATE OF CONNECTICUT SITING COUNCIL.


THE FOLLOWING DOCUMENTS ARE CONSIDERED TO BE PART OF THIS EROSION AND SEDIMENTATION CONTROL PLAN: THE COMPLETE SITE PLANS, THE DRAINAGE NARRATIVE PREPARED BY CLA ENGINEERS, AND THE CTDEEP 2002 MANUAL

EROSION AND SEDIMENTATION CONTROL SEQUENCE

- 1. BEFORE ANY WORK TAKES PLACE CONTACT CALL BEFORE YOU DIG 1-800-922- 4455 TO MARK UTILITIES.
- 2. NOTIFY THE TOWN OF START OF CONSTRUCTION A MINIMUM OF 48 HOURS IN
- 3. HAVE LICENSED SURVEYOR STAKE OUT THE CLEARING LIMITS.
- 4. CUT TREES BUT DO NOT GRUB.

ADVANCE.

- 5. INSTALL CONSTRUCTION ENTRANCE AND PERIMETER EROSION AND SEDIMENTATION CONTROLS AND HAVE INSPECTED BY SITE INSPECTOR.
- 6. INSTALL ADDITIONAL E&S AS SHOWN ON PLANS INCLUDING TEMPORARY VEGETATED SWALES AND TEMPORARY SEDIMENT TRAPS AND HAVE THEM INSPECTED BY THE SITE INSPECTOR.
- 7. ANY DEWATERING WILL BE MONITORED BY A QUALIFIED ENVIRONMENTAL PROFESSIONAL TO MAINTAIN SUITABLE QUALITY OF DISCHARGE FROM THE DEWATERING AND TO ENSURE REMOVAL OF ACCUMULATED SEDIMENTS AT APPROPRIATE INTERVALS. SEDIMENTS WILL BE DISPOSED OF AT AN APPROPRIATE ON-SITE LOCATION. DEWATERING WILL DISCHARGE INTO TEMPORARY SEDIMENT TRAPS.
- 8. ROUGH GRADE SITE.
- 9. INSTALL CHAIN LINK FENCE AROUND PERIMETER.
- 10. INSTALL SOLAR PANELS, HYDROSEED OR SEED AND MULCH AROUND PANELS AND HYDROSEED OR MULCH AND SEED ANY EXPOSED SOIL AT THE END OF EACH WEEK AND BEFORE EVERY RAINFALL PREDICTED FOR 0.5 INCHES OR MORE.
- 11. TRENCH FOR AND INSTALL ELECTRIC LINES AND AT THE END OF EACH WEEK HYDROSEED OR MULCH AND SEED ANY EXPOSED SOIL AT THE END OF EACH WEEK AND BEFORE EVERY RAINFALL PREDICTED FOR 0.5 INCHES OR MORE.
- 12. INSTALL REMAINING ELECTRIC INFRASTRUCTURE AND AT THE END OF EACH WEEK HYDROSEED OR MULCH AND SEED ANY EXPOSED SOIL AT THE END OF EACH WEEK AND BEFORE EVERY RAINFALL PREDICTED FOR 0.5 INCHES OR MORE.
- 13. OVERSEED DISTURBED SOILS WHEN ALL SOLAR PANEL INSTALLTION IS COMPLETE.
- 14. CLEAN SEDIMENTS BASINS AND GRADE AND RE-SEED FOR USE AS STORMWATER BASINS WHEN SITE INSPECTOR DEEMS SOILS ARE STABILIZED.
- 15. INSTALL PLANTINGS
- 16. MAINTAIN E&S AND PROVIDE REPORTS TO TOWN AND CTDEEP






ANSONIA, CT 06401

Proj. Enginee E.M.B.

2/11/2020 Sheet No.

BENZ STREET SOLAR


CIVIL NOTES



NOTE:

ROCK CONSTRUCTION ENTRANCE SHOULD BE A MINIMUM THICKNESS OF 1.0' AND CONTAIN MAXIMUM SIDE SLOPES OF 4:1. ROCK ENTRANCE SHOULD BE INSPECTED AND MAINTAINED REGULARLY. ROCK ENTRANCE LENGTH MAY NEED TO BE EXTENDED IN CLAY SOILS.


ROCK CONSTRUCTION ENTRANCE



INSPECT AND REPAIR FENCE AFTER EACH STORM EVENT AND REMOVE SEDIMENT WHEN ACCUMULATED TO 1/3 THE HEIGHT OF THE FABRIC OR MORE.

- 2. REMOVED SEDIMENT SHALL BE DEPOSITED TO AN AREA THAT WILL NOT CONTRIBUTE SEDIMENT OFF-SITE AND CAN BE PERMANENTLY STABILIZED.
- 3. SILT FENCE SHALL BE PLACED ON SLOPE CONTOURS TO MAXIMIZE PONDING
- 4. ALL ENDS OF THE SILT FENCE SHALL BE WRAPPED UPSLOPE SO THE ELEVATION OF THE BOTTOM OF FABRIC IS HIGHER THAN "PONDING HEIGHT".


SILT FENCE NOT TO SCALE




1. CONTRACTOR TO SUBCUT ROADWAY TO EXISTING GRADE ELEVATION TO MAINTAIN EXISTING SITE DRAINAGE PATTERNS

- 2. IN FILL LOCATIONS CONTRACTOR TO GRADE TOE OF SLOPE TO EXISTING GRADE, AND MAINTAIN NATURAL DRAINAGE
- ATTERNS.
- IN CUT LOCATIONS CONTRACTOR TO CREATE SWALE ON DOWNSTREAM SIDE, REFER TO GRADING PLANS FOR DETAILS.
 CONTRACTOR TO COMPACT AGGREGATE TO 95% MAXIMUM DRY DENSITY.
- 5. REFER TO GEOTECHNICAL RECOMMENDATIONS FOR ADDITIONAL ROADWAY SECTION DESIGN INFORMATION.

ACCESS ROAD DETAIL NOT TO SCALE



EROSION CONTROL BLANKET




D.O.T. FORM 816

TRENCHING DETAIL

ELECTRICAL DESIGN TRENCH DIMENSIONS FOR EARTHWORK QUANTITIES ARE

NOT TO SCALE


CONSERVATIVE.





HAY-BALE / SILT FENCE EROSION PROTECTION


CONSTRUCTION NOTES:

- 1. SILT FENCE FILTER CLOTH TO BE SECURELY FASTENED TO GRADE STAKE WITH STAPLES, 6" ON CENTER.
- 2. WHEN TWO SECTIONS OF FILTER CLOTH ADJOIN ONE ANOTHER THEY SHALL OVERLAP BY 6" AND BE FOLDED.
- 3. BALES SHALL BE PLACED IN A ROW WITH ENDS TIGHTLY ABUTTING THE ADJACENT BALES.









DEWATERING SETTLING BASIN DETAIL

DEWATERING PLAN

IF DEWATERING IS NECESSARY DURING CONSTRUCTION A CLEAR WATER DISCHARGE SHALL BE PROVIDED AS FOLLOWS:

- A. THE PUMP INLET WILL BE WRAPPED IN FILTER FABRIC AND PLACED IN CRUSHED STONE WITHIN THE TRENCH.
- B. THE PUMP OUTLET WILL DISCHARGE TO THE DEWATERING ENCLOSURE PER THE DETAIL FOR DEWATERING SETTLING BASIN TO BE LOCATED OUTSIDE OF THE 100' UPLAND REVIEW ZONE.
- C. THE DISCHARGE FROM THE DEWATERING ENCLOSURE WILL BE MONITORED AND ADDITIONAL

