




LOCATION MAP
SCALE: N.T.S.

APPLICABLE CODES

NATIONAL ELECTRIC CODE - 2020
ARTICLE 230 - SERVICES
ARTICLE 240 - OVERCURRENT PROTECTION
ARTICLE 250 - GROUNDING AND BONDING
ARTICLE 300 - WIRING METHODS
ARTICLE 310 - CONDUCTORS
ARTICLE 690 - SOLAR PHOTOVOLTAIC SYSTEMS
ARTICLE 705 - INTERCONNECTED ELECTRIC POWER PRODUCTION SOURCES

PV SYSTEM #1 INFORMATION

SYSTEM SIZE (DC): 1,348.620 kW STC + BIFACIAL GAIN
SYSTEM SIZE (AC): 999.000 kW
INVERTER QUANTITY: 8
INVERTER TYPE: (7) KACO 125TL3 (125 KW)
(1) KACO 125TL3 (124 KW / CURTAILED)
MODULE QUANTITY: 1,976
MODULE TYPE: (988) CANADIAN SOLAR CS7N-680TB-AG
BIFACIAL (680W STC) &
(988) CANADIAN SOLAR CS7N-685TB-AG
BIFACIAL (685W STC)
RACKING MANUFACTURER: APA

PV SYSTEM #2 INFORMATION

SYSTEM SIZE (DC): 1,348.620 kW STC + BIFACIAL GAIN
SYSTEM SIZE (AC): 999.000 kW
INVERTER QUANTITY: 8
INVERTER TYPE: (7) KACO 125TL3 (125 KW)
(1) KACO 125TL3 (124 KW / CURTAILED)
MODULE QUANTITY: 1,976
MODULE TYPE: (988) CANADIAN SOLAR CS7N-680TB-AG
BIFACIAL (680W STC) &
(988) CANADIAN SOLAR CS7N-685TB-AG
BIFACIAL (685W STC)
RACKING MANUFACTURER: APA

UTILITY INFORMATION

COMPANY: UNITED ILLUMINATING
ACCOUNT NUMBER: T.B.D. (NEW ACCOUNT)
METER NUMBERS: T.B.D. (NEW METERS)
ZREC NUMBER: #ZL22227 (SYSTEM #1) &
#ZL22229 (SYSTEM #2)

GROUND
MOUNTED PV
ARRAY
INSTALLATION
AT:

BENZ SOLAR
31 BENZ STREET
ANSONIA, CT 06041

PREPARED FOR:




ecosrenewable.com

PREPARED BY:



sgedesign.com

Stephen
Gendreau, P.E.
Digitally signed by
Stephen Gendreau, P.E.
Date: 2024.09.26
12:05:11 -04'00'



VICINITY MAP
SCALE: N.T.S.

PROJECT DESCRIPTION

THIS INSTALLATION CONSISTS OF TWO UTILITY INTERACTIVE SOLAR PHOTOVOLTAIC SYSTEMS ON GROUND MOUNTED STRUCTURES, LOCATED IN ANSONIA, CONNECTICUT. THE SYSTEMS ARE COMPRISED OF MODULES MOUNTED TO GROUND MOUNTED RACKING STRUCTURES. THE INVERTERS ARE POWERED BY PARALLEL STRINGS OF MODULES IN SERIES FED THROUGH DC STRING COMBINER BOXES AND DC DISCONNECT SWITCHES. THE AC INVERTER OUTPUTS ARE COMBINED IN TWO PAD MOUNTED AC COMBINER SWITCHBOARDS. FROM EACH AC COMBINER SWITCHBOARD, POWER IS FED THROUGH A TRANSFORMER, CUSTOMER OWNED RECLOSER & PRIMARY METERING CABINET. FROM EACH METERING CABINET, POWER IS FED UNDERGROUND TO THE UTILITY COMPANY POLE SYSTEM.

DRAWING LIST

N/A	COVER SHEET
PV-1A	THREE-LINE DIAGRAM (PART 1 OF 3)
PV-1B	THREE-LINE DIAGRAM (PART 2 OF 3)
PV-1C	THREE-LINE DIAGRAM (PART 3 OF 3)
PV-2	ENLARGED EQUIPMENT AREA PLAN
PV-3	OVERALL SITE ELECTRICAL PLAN
PV-4A, B, C, D	DETAILED ARRAY PLANS (AREAS 'A' THROUGH 'D')
PV-5	SPECIFICATIONS
PV-6	DC STRING WIRE AND CONDUIT SCHEDULES
PV-7	DETAILS
PV-8	NOTES, DETAILS & ABBREVIATIONS
PV-9	EQUIPMENT DATA SHEETS & DETAILS
PV-10	LABELS & SIGNAGE
PV-11	CUSTOMER OWNED RECLOSER DATA SHEETS
PV-12	PRIMARY METERING ENCLOSURE DATA SHEETS
PV-13	EQUIPMENT DATA SHEETS


OTHER DRAWINGS

RACKING MANUFACTURER DRAWINGS
CIVIL ENGINEERING DRAWINGS

REVISIONS:

03-03-2023:	INTERCONNECTION APPLICATION SET
03-15-2024:	INTERCONNECTION APPLICATION REV #1
04-30-2024:	PROGRESS SET - FOR REVIEW
08-30-2024:	ISSUED FOR CONSTRUCTION
09-26-2024:	REVISIONS



[illegible][illegible]

BENZ SYSTEM #1
REC# 2122227

Diagram of a transformer with a center tap and a secondary winding. The primary winding has four terminals. The top two are labeled "CONTINUATION OF" and "FOR". The bottom two are labeled "SEE DRAWING" and "FIG. 18". The center tap is labeled "SWBD-1". The secondary winding has two terminals, one labeled "WYE" and "1.3KV". The primary winding is labeled "600V" and "347V". The secondary winding is labeled "INTERNAL N-G BOND AT TRANSFORMER SECONDARY".



PREPARED FOR:

TYPICAL SYSTEM INFO
(FOR EACH OF TWO SYSTEMS):

- (1) KACO 125TL3 INVERTER CURTAILED TO 124 KW AC
- (988) CANADIAN SOLAR CS7N-680TB-AG BIFACIAL

REC#ZL22227 (SYSTEM #1)
REC#ZL22229 (SYSTEM #2)



No.	Revision/Issue	Date

31 BENZ STREET
ANSONIA, CT 06041

THREE-LINE DIAGRAM
(PART 1 OF 3)

Project	
Date	SEPTEMBER 26, 2024

Sheet


PV-1A

	Scale	SIN
--	-------	-----

EQUIPMENT SCHEDULE				
DESIGNATION	ITEM	MAKE & MODEL #	NOTES	FURNISHED BY UTILITY COMPANY
A1 & A2	AC COMBINER SWITCHBOARDS	QT / SIEMENS OR EQUAL	600VAC 3PH 4W 1200A RATED 65KAIC NEMA 3R BREAKER SIZES & QUANTITIES AS INDICATED GPP MAIN BREAKER ARC ENERGY REDUCTION SWITCH	NO
Z	AUXILIARY POWER CENTER WITH TRANSFORMER	SIEMENS OR EQUAL	POWER CENTER WITH 7500KVA TRANSFORMER (600VAC 1-PH TO 240/120V 1-PH) 40A-2P MCB, BRANCH BREAKERS AS INDICATED	NO


AC FEEDER SCHEDULE												
LOCATION	LENGTH	# OF PARALLEL CONDUITS	CONDUIT SIZE	CONDUIT TYPE	CONDUCTORS	NEUTRAL	GND	CONDUCTOR MATERIAL	CONDUCTOR TYPE	MIN RATING	FILL FACTOR	VOLTAGE DROP
SWBD-1 TO INVERTER 1	40'	1	2"	PVC	3 #3/0	N/A	1 #4	ALUMINUM	XHHW-2	600VAC	25.7%	0.2%
SWBD-1 TO INVERTER 2	35'	1	2"	PVC	3 #3/0	N/A	1 #4	ALUMINUM	XHHW-2	600VAC	25.7%	0.2%
SWBD-1 TO INVERTER 3	25'	1	2"	PVC	3 #3/0	N/A	1 #4	ALUMINUM	XHHW-2	600VAC	25.7%	0.1%
SWBD-1 TO INVERTER 4	20'	1	2"	PVC	3 #3/0	N/A	1 #4	ALUMINUM	XHHW-2	600VAC	25.7%	0.1%
SWBD-1 TO INVERTER 5	20'	1	2"	PVC	3 #3/0	N/A	1 #4	ALUMINUM	XHHW-2	600VAC	25.7%	0.2%
SWBD-1 TO INVERTER 6	25'	1	2"	PVC	3 #3/0	N/A	1 #4	ALUMINUM	XHHW-2	600VAC	25.7%	0.2%
SWBD-1 TO INVERTER 7	35'	1	2"	PVC	3 #3/0	N/A	1 #4	ALUMINUM	XHHW-2	600VAC	25.7%	0.2%
SWBD-1 TO INVERTER 8	40'	1	2"	PVC	3 #3/0	N/A	1 #4	ALUMINUM	XHHW-2	600VAC	25.7%	0.2%
SWBD-2 TO INVERTER 9	55'	1	2"	PVC	3 #3/0	N/A	1 #4	ALUMINUM	XHHW-2	600VAC	25.7%	0.3%
SWBD-2 TO INVERTER 10	60'	1	2"	PVC	3 #3/0	N/A	1 #4	ALUMINUM	XHHW-2	600VAC	25.7%	0.3%
SWBD-2 TO INVERTER 11	65'	1	2"	PVC	3 #3/0	N/A	1 #4	ALUMINUM	XHHW-2	600VAC	25.7%	0.3%
SWBD-2 TO INVERTER 12	70'	1	2"	PVC	3 #3/0	N/A	1 #4	ALUMINUM	XHHW-2	600VAC	25.7%	0.4%
SWBD-2 TO INVERTER 13	55'	1	2"	PVC	3 #3/0	N/A	1 #4	ALUMINUM	XHHW-2	600VAC	25.7%	0.3%
SWBD-2 TO INVERTER 14	60'	1	2"	PVC	3 #3/0	N/A	1 #4	ALUMINUM	XHHW-2	600VAC	25.7%	0.3%
SWBD-2 TO INVERTER 15	65'	1	2"	PVC	3 #3/0	N/A	1 #4	ALUMINUM	XHHW-2	600VAC	25.7%	0.3%
SWBD-2 TO INVERTER 16	70'	1	2"	PVC	3 #3/0	N/A	1 #4	ALUMINUM	XHHW-2	600VAC	25.7%	0.4%
SWBD-1 TO PC-1	15'	1	0.75"	PVC	2 #12	N/A	1 #12	COPPER	XHHW-2	600VAC	12.2%	0.1%
PC-1 TO SYSTEM OWNER'S METER	10'	1	0.75"	PVC	1 #12	1 #12	1 #12	COPPER	XHHW-2	600VAC	12.2%	0.2%
PC-1 TO SERVICE RECEPTACLES	10'	1	0.75"	PVC	1 #12	1 #12	1 #12	COPPER	XHHW-2	600VAC	12.2%	0.2%
PC-1 TO PRIMARY METER CABINET PM-1 HEATERS	40'	1	0.75"	PVC	1 #12	1 #12	1 #12	COPPER	XHHW-2	600VAC	12.2%	0.3%
PC-1 TO MET ENCLOSURE	10'	1	0.75"	PVC	1 #12	1 #12	1 #12	COPPER	XHHW-2	600VAC	12.2%	0.2%
PC-1 TO CAMERA ENCLOSURE	10'	1	0.75"	PVC	1 #12	1 #12	1 #12	COPPER	XHHW-2	600VAC	12.2%	0.2%
PC-1 TO PRIMARY METER CABINET PM-2 HEATERS	55'	1	0.75"	PVC	1 #12	1 #12	1 #12	COPPER	XHHW-2	600VAC	12.2%	0.4%
TX-2 TO SWBD-2	15'	3	4"	PVC	3 #600	1 #600	1 #3/0	COPPER	XHHW-2	600VAC	28.7%	0.1%
PM-1 TO R-1	20'	1	4"	PVC	3 #1/0	1 #1/0	1 #2	ALUMINUM	MV-105	15KV	30.1%	0.0%
R-1 TO TX-1	15'	1	4"	PVC	3 #1/0	1 #1/0	1 #2	ALUMINUM	MV-105	15KV	30.1%	0.0%
PM-2 TO R-2	20'	1	4"	PVC	3 #1/0	1 #1/0	1 #2	ALUMINUM	MV-105	15KV	30.1%	0.0%
R-2 TO TX-2	30'	1	4"	PVC	3 #1/0	1 #1/0	1 #2	ALUMINUM	MV-105	15KV	30.1%	0.0%
PC-1 TO PRIMARY METER CABINET PM-3 HEATERS (FUTURE)	75'	1	0.75"	PVC	1 #12	1 #12	1 #12	COPPER	XHHW-2	600VAC	12.2%	0.6%

NOTE - ONE WAY LENGTHS OF RUN INDICATED IN THIS TABLE ARE FOR VOLTAGE DROP CALCULATION PURPOSES ONLY. CONTRACTOR SHALL FIELD VERIFY EXACT LENGTHS.



BENZ SYSTEM #2
REC#ZL22228

BENZ SYSTEM #1
REC#ZL22227



BENZ SYSTEM #2
REC#ZL22228

BENZ SYSTEM #1
REC#ZL22227

KEY NOTES

- CONNECT SYSTEM TO EXISTING POLE #1342 ON THE EAST SIDE OF BENZ STREET, FED FROM U.I. CIRCUIT #3678, SUBSTATION "ANSONIA".
- NEW PAD MOUNTED CUSTOMER OWNED TRANSFORMER (13.8KV GROUND WYE PRIMARY, 600V/240V GROUND WYE SECONDARY). PROVIDE TRANSFORMER VAL TYPAD & GROUNDING PER DETAILS ON DRAWING PV-8. FUSE SIZING PER MANUFACTURER'S REQUIREMENTS.
- CUSTOMER OWNED PAD MOUNTED RECLOSER WITH SEL RELAY, VACUUM INTERRUPTER, MANUALLY OPERABLE. SEL RELAY WILL BE PROVIDED WITH 6-HOUR BATTERY BACKUP AND WILL PROVIDE OVERVOLTAGE AND UNDERVOLTAGE FREQUENCY PROTECTION PER TABLE ON PV-1A. REFER TO CRYSTING & ASDO REPORT FOR FINAL RELAY SETTINGS AND WITNESS TEST PLAN. CONNECT GAW PROVIDED 32-PIN PT CABLE & WIRING PER GAW INSTRUCTIONS. POWER SEL RELAY FROM UTILITY SIDE OF THE RECLOSER.
- PAD MOUNTED PRIMARY METERING ENCLOSURE. CUSTOMER WILL FURNISH CABINET, PAD, CT'S, PT'S AND H-CHANNEL UNISTRUT FOR MOUNTING OF METERS. U.I. WILL INSTALL, OWN AND MAINTAIN THE CT'S AND PT'S. SEE DETAILS TYP-8 AND DRAWING PV-12 FOR REQUIREMENTS.
- INSTALL GROUNDING WIRE ON AC SIDE OF INVERTER AND CONNECT BACK TO GROUNDING ELECTRODE OF THE EXISTING MAIN ELECTRICAL SERVICE. REFER TO DETAIL 2 ON PV-8.
- NOTE NOT USED.
- PROVIDE RIGID GALVANIZED CONDUIT SWEEPS AT BASE OF RISER POLE. SEE DETAIL 3PV-7 FOR ADDITIONAL REQUIREMENTS.
- MOUNT METEOROLOGICAL STATION (MET ENCLOSURE) IN LOCATION INDICATED ON PV-2. PROVIDE AND CONNECT ALL SENSORS, INCLUDING WEATHER, PYRANOMETER AND BACK OF MODULE SENSORS. SEE NORCAL WIRING DIAGRAMS FOR REQUIREMENTS.
- INSTALL CELLULAR ANTENNA AND COAX CABLE TO DAS CONTROL PANEL. SEE NORCAL WIRING DIAGRAMS FOR REQUIREMENTS.
- PROVIDE RS485 COMMUNICATION WIRING TO SYSTEM OWNER'S METER PER MANUFACTURER'S INSTRUCTIONS. DASHY CHAIN BETWEEN INVERTERS. SEE NORCAL WIRING DIAGRAMS.
- PARALLEL STRINGS OF MODULES IN SERIES - REFER TO PV-3 FOR STRING WIRE CONFIGURATION & ROUTING.
- INSTALL INVERTER AS INDICATED IN THE EQUIPMENT SCHEDULE ON THIS DRAWING. REFER TO THE "INVERTER DATA" TABLE ON THIS DRAWING FOR ADDITIONAL INFORMATION. PROVIDE NARROW TONGUE LUGS FOR INVERTER AC TERMINATIONS.
- INSTALL #6 EQUIPMENT GROUNDING CONDUCTOR AND BOND TO ALL PV ARRAY FRAMES, RACKING, AND MODULE FRAMES. CONNECT CONDUCTOR BACK TO DC GROUNDING BAR INSIDE INVERTER. REFER TO DETAIL 2 ON PV-8.
- U.I. APPROVED METER SOCKET WITH TEST SWITCHES, MOUNTED TO H-FRAME UNISTRUT. THE METER & TEST SWITCH WILL BE FURNISHED AND INSTALLED BY UNITED ILLUMINATING. CONDUIT BETWEEN METER AND METERING CABINET WILL NOT EXCEED 120'. SEE DETAILS 3PV-7 & 3PV-13.
- PROVIDE (4) #4 SCHEDULE 80 PVC CONDUITS UNDERGROUND AS NOTED. CONDUIT AND TRENCH SHALL BE INSTALLED PER U.I. STANDARDS. SEE DRAWING PV-7 FOR TRENCH DETAILS. U.I. WILL PROVIDE PRIMARY CABLES AS NOTED, ON A BILLABLE BASIS.
- U.I. WILL PROVIDE A NEW POLE WITH AN AIR BREAK SWITCH AND TRANSITION FROM AERIAL CABLE TO OPEN WIRE. SEE DRAWING PV-3 FOR LOCATION.
- U.I. WILL PROVIDE A NEW RISER POLE. SEE DRAWING PV-3 FOR LOCATION.
- U.I. WILL PROVIDE A NEW RISER POLE. SEE DRAWING PV-3 FOR LOCATION.
- PROVIDE TWO MULTI-CIRCUIT DC DISCONNECTS. EACH DC DISCONNECT SERVES EIGHT DC INVERTER INPUTS AS INDICATED IN EQUIPMENT SCHEDULE ON THIS DRAWING. BOND DISCONNECT TO INVERTER HUT/RACK.
- PROVIDE ONE DC COMBINER BOX FOR EACH INVERTER, MOUNTED TO THE ARRAY RACKING STRUCTURE. SEE DRAWINGS PV-4 & PV-5 FOR LOCATIONS. BOND TO RACKING SYSTEM.
- INSTALL CAMERA ENCLOSURE AND CONNECTIONS TO (B) CAMERAS AND TO DAS CONTROL PANEL. SEE SYSTEM OWNER PROVIDED WIRING & INSTALLATION DIAGRAMS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.
- PROVIDE AUXILIARY POWER CENTER (TRANSFORMER AND PANEL) AS INDICATED IN EQUIPMENT SCHEDULE ON THIS DRAWING. PROVIDE A SERVICE RECEPTACLE ADJACENT TO EQUIPMENT.

Project Info

PREPARED BY:



56 FOXCROFT COURT
SOUTHINGTON, CT
SGEDSIGN.COM
sge@sgedesign.com

PREPARED FOR:



222 S 9TH STREET, SUITE 1600
MINNEAPOLIS, MN 55402
ECOSRENEWABLE.COM

TYPICAL SYSTEM INFO
(FOR EACH OF TWO SYSTEMS):

- 1,348,620 KW DC STC + BIFACIAL GAIN
- 999,000 KW / KVA AC
- (7) KACO 125TL3 INVERTERS
- (1) KACO 125TL3 INVERTER CURTAILED TO 124 KW AC
- (988) CANADIAN SOLAR CS7N-680TB-AG BIFACIAL MODULES (680W STC)
- (988) CANADIAN SOLAR CS7N-685TB-AG BIFACIAL MODULES (685W STC)

REC#ZL22227 (SYSTEM #1)

REC#ZL22229 (SYSTEM #2)

U.I. METERS #TBD (NEW METERS)

U.I. ACCT #TBD (NEW ACCOUNT)



No. Revision/Issue Date

BENZ SOLAR
GROUND MOUNTED PV SYSTEM

31 BENZ STREET
ANSONIA, CT 06041

THREE-LINE DIAGRAM
(PART 2 OF 3)

Project

Date


Scale

NTS

Sheet

SEPTEMBER 26, 2024

PV-1B



KEY NOTES

- (2) 4" FROM UTILITY RISER POLE TO CUSTOMER OWNED PRIMARY METERING CABINETS, RECLOSERS AND TRANSFORMERS. SEE TRENCH DETAIL 7/PV-7
- REFER TO DETAIL 3/PV-8 FOR CONCRETE PAD REQUIREMENTS.
- PAD MOUNTED CUSTOMER OWNED RECLOSER - SEE SHOP DRAWINGS AND DRAWING PV-11 FOR DETAILS.
- PAD MOUNTED CUSTOMER OWNED TRANSFORMER - SEE 3/PV-7 & 4/PV-9. CONNECTION FROM TRANSFORMER TX-1 TO AC COMBINER SWITCHBOARD 'SWB3-1' SHALL BE BUSSED / THROAT TYPE.
- PAD MOUNTED SWITCHBOARD WITH AC COMBINER PANEL, ENCLOSURE HEATER & ACUVIM METER. CONNECTION FROM SWITCHBOARD 'SWB3-1' TO TRANSFORMER TX-1 SHALL BE BUSSED / THROAT TYPE.
- AUXILIARY POWER CENTER MOUNTED TO SUPPORT POSTS AND STRUT. EQUIPMENT INCLUDES TRANSFORMER AND SINGLE PHASE PANELBOARD.
- PAD MOUNTED SYSTEM OWNER'S METERING CABINET. REFER TO MANUFACTURER'S DRAWINGS FOR ADDITIONAL DETAILS.
- SYSTEM OWNER'S MONITOR, METEOROLOGICAL STATION AND CAMERA SYSTEM EQUIPMENT MOUNTED TO SUPPORT POSTS AND STRUT. REFER TO NOR-CAL DRAWINGS FOR ADDITIONAL DETAILS.
- INVERTER RACK / HUT WITH INVERTERS AND DC DISCONNECT. CONSTRUCT RACK IN FIELD WITH POSTS, STRUT AND ROOF, SIMILAR TO PREVIOUSLY COMPLETED PROJECT. SEE DETAIL 8/PV-7 FOR CONCEPT.
- GROUND MOUNTED ARRAY WITH COMBINER BOXES, RACKING AND MODULES. REFER TO DRAWINGS PV-4X FOR DETAILED ARRAY LAYOUT INFORMATION.
- POLE MOUNTED CAMERAS - EXACT LOCATION TO BE DETERMINED BY SYSTEM OWNER IN THE FIELD. PROVIDE A FOUNDATION, POLE CONDUIT AND WIRING TO EACH CAMERA PER MANUFACTURER'S REQUIREMENTS. REFER TO NOR-CAL DOCUMENTATION FOR CAMERA AND POLE DETAILS.
- PAD MOUNTED UTILITY METERING ENCLOSURE AND ADJACENT REVENUE & REC METERS MOUNTED TO STRUT AND POST. REFER TO SHOP DRAWINGS, DRAWING PV-12, DETAIL 7/PV-8, DETAIL 3/PV-13 & DETAIL 5/PV-7
- COORDINATE EXACT LOCATIONS OF U.I. PROVIDED POLES WITH U.I. IN THE FIELD.

GENERAL NOTES

- WORK INCLUDES INSTALLING PROPOSED SOLAR ARRAY PER THE MANUFACTURER'S INSTALLATION PROCEDURES AND INSTRUCTIONS, ALONG WITH ASSOCIATED ELECTRICAL WIRING.
- WORK AREAS SHALL BE MARKED, FENCED, AND OTHERWISE SECURED SO AS TO PROVIDE PROPER PROTECTION FOR THE PUBLIC AND AS REQUIRED BY THE BUILDING INSPECTOR.
- DO NOT DEVIATE FROM THE LAYOUT SHOWN WITHOUT APPROVAL FROM THE ENGINEER.
- ELECTRICAL RUNS SHOWN ON PLAN REPRESENT THE PROPOSED LAYOUT. THE CONTRACTOR SHALL NOT RELOCATE EQUIPMENT OR CONDUIT RUNS WITHOUT APPROVAL FROM THE ENGINEER & SYSTEM OWNER.
- NO CONDUCTOR OR CONNECTOR SHALL BE EXPOSED TO WEATHERING OR DIRECT SUNLIGHT OUTSIDE OF THE BOUNDARIES OF EACH SUB-ARRAY.
- CONDUIT RUNNING BETWEEN SUB-ARRAYS SHALL BE SECURED TO THE RACKING SYSTEM VIA CONDUIT CLAMPS.
- PROVIDE HANDHOLES / PULLBOXES AS REQUIRED TO KEEP PULLING TENSION WITHIN MANUFACTURER'S LIMITS.

Project Info

PREPARED BY:

 **SG ENGINEERING LLC**

56 FOXCROFT COURT
SOUTHINGTON, CT
SGEDSIGN.COM
sge@sgedesign.com

PREPARED FOR:

 **ecos ENERGY**

222 S 9TH STREET, SUITE 1600
MINNEAPOLIS, MN 55402
ECOSRENEWABLE.COM

TYPICAL SYSTEM INFO
(FOR EACH OF TWO SYSTEMS):

- 1,348.620 KW DC STC + BIFACIAL GAIN
- 999.000 KW / KVA AC
- (7) KACO 125TL3 INVERTERS
- (1) KACO 125TL3 INVERTER CURTAILED TO 124 KW AC
- (988) CANADIAN SOLAR CSTN-680TB-AG BIFACIAL MODULES (680W STC)
- (988) CANADIAN SOLAR CSTN-685TB-AG BIFACIAL MODULES (685W STC)

REC#ZL22227 (SYSTEM #1)
REC#ZL22229 (SYSTEM #2)

U.I. METERS #TBD (NEW METERS)

U.I. ACCT #TBD (NEW ACCOUNT)



No.	Revision/Issue	Date

BENZ SOLAR
GROUND MOUNTED PV SYSTEM

31 BENZ STREET
ANSONIA, CT 06041

ENLARGED EQUIPMENT AREA
PLAN

Project	Sheet
Date SEPTEMBER 26, 2024	PV-2
Scale NTS	

GENERAL NOTES

1. WORK INCLUDES INSTALLING PROPOSED SOLAR PANEL ARRAY PER THE MANUFACTURER'S INSTALLATION PROCEDURES AND INSTRUCTIONS, ALONG WITH ASSOCIATED ELECTRICAL WIRING.
2. WORK AREAS SHALL BE MARKED, FENCED, AND PROTECTION FOR THE PUBLIC AND AS REQUIRED BY THE BUILDING INSPECTOR.
3. THE CONTRACTOR SHALL NOT DEVIATE FROM THE LAYOUT SHOWN WITHOUT APPROVAL FROM THE ENGINEER.
4. ELECTRICAL RUNS SHOWN ON PLAN REPRESENT THE PROPOSED LAYOUT. THE CONTRACTOR SHALL NOT RELOCATE EQUIPMENT WITHOUT APPROVAL FROM THE ENGINEER & SYSTEM OWNER.
5. NO CONDUIT OR CONDUCTOR SHALL BE EXPOSED TO WEATHERING OR DIRECT SUNLIGHT OUTSIDE OF THE BOUNDARIES OF EACH SUB-ARRAY.
6. CONDUIT RUNNING BETWEEN SUB-ARRAYS SHALL BE SECURED TO THE RACKING SYSTEM VIA CONDUIT CLAMPS.
7. PROVIDE HANDHOLES / PULLBOXES PER CODE.

KEY NOTES


1. DC DISCONNECTS MOUNTED TO STRUT AT EACH INVERTER RACK / HUT.
2. PAD MOUNTED CUSTOMER OWNED RECLOSERS.
3. RACKS / HUTS.
4. PAD MOUNTED SWITCHBOARDS WITH AC COMBINERS.
5. PAD MOUNTED UTILITY COMPANY PRIMARY METERING ENCLOSURES WITH ADJACENT STRUT MOUNTED UTILITY REVENUE METERS & REC METERS.
6. PAD MOUNTED CUSTOMER OWNED TRANSFORMERS.
7. RACK.
8. SYSTEM OWNER'S METERING & MONITORING TO STRUT RACKS.
9. NOT USED.
10. DC COMBINER BOXES MOUNTED TO ARRAY RACKING STRUCTURES - SEE PV-4X DRAWINGS FOR EXACT LOCATIONS.
11. COORDINATE EXACT LOCATIONS OF UTILITY POLES WITH U.I. IN THE FIELD.

OVERALL SITE ELECTRICAL PLAN

1" = 80'-0"

PV-3

1



Project Info

PREPARED BY:



56 FOXCROFT COURT
SOUTHINGTON, CT
SGEDSIGN.COM
sg@sgedesign.com

PREPARED FOR:



222 S 9TH STREET, SUITE 1600
MINNEAPOLIS, MN 55402
ECOSRENEWABLE.COM

TYPICAL SYSTEM INFO
(FOR EACH OF TWO SYSTEMS):

- 1,348,620 KW DC STC + BIFACIAL GAIN
- 999,000 KW / KVA AC
- (7) KACO 125TL3 INVERTERS CURTAILED TO 124 KW AC
- (988) CANADIAN SOLAR CS7N-680TB-AG BIFACIAL MODULES (680W STC)
- (988) CANADIAN SOLAR CS7N-685TB-AG BIFACIAL MODULES (685W STC)

REC#ZL22227 (SYSTEM #1)
REC#ZL22229 (SYSTEM #2)
U.I. METERS #TBD (NEW METERS)
U.I. ACCT #TBD (NEW ACCOUNT)



No.	Revision/Issue	Date

BENZ SOLAR
GROUND MOUNTED PV SYSTEM

31 BENZ STREET
ANSONIA, CT 06041

OVERALL SITE ELECTRICAL PLAN

PV-3

Date
SEPTEMBER 26, 2024

Scale
1" = 80'-0"

AREA 'B' - SEE
DRAWING PV-4B

AREA 'A' - SEE
DRAWING PV-4A

AREA 'B' - SEE
DRAWING PV-4B

AREA 'C' - SEE
DRAWING PV-4C

Project Info

PREPARED BY:



56 FOXCROFT COURT
SOUTHINGTON, CT
SGEDesign.COM
sge@sgedesign.com

PREPARED FOR:



222 S 9TH STREET, SUITE 1600
MINNEAPOLIS, MN 55402
ECOSRENEWABLE.COM

TYPICAL SYSTEM INFO
(FOR EACH OF TWO SYSTEMS):

- 1,348.620 KW DC STC + BIFACIAL GAIN
- 999.000 KW / KVA AC
- (7) KACO 125TL3 INVERTERS
- (1) KACO 125TL3 INVERTER CURTAILED TO 124 KW AC
- (988) CANADIAN SOLAR CS7N-680TB-AG BIFACIAL MODULES (680W STC)
- (988) CANADIAN SOLAR CS7N-685TB-AG BIFACIAL MODULES (685W STC)

REC#ZL22227 (SYSTEM #1)
REC#ZL22229 (SYSTEM #2)

U.I. METERS #TBD (NEW METERS)

U.I. ACCT #TBD (NEW ACCOUNT)



No.	Revision/Issue	Date

BENZ SOLAR
GROUND MOUNTED PV SYSTEM

31 BENZ STREET
ANSONIA, CT 06041

DETAILED ARRAY PLAN - AREA A

Project

Date
SEPTEMBER 26, 2024

Scale
1/16" = 1'-0"

Sheet

PV-4A

1
PV-4A
DETAILED ARRAY PLAN - AREA 'A'
1/16" = 1'-0"

Project Info

PREPARED BY:



56 FOXCROFT COURT

SOUTHINGTON, CT

SGEDSIGN.COM

sgedesign.com

PREPARED FOR:



222 S 9TH STREET, SUITE 1600

MINNEAPOLIS, MN 55402

ECOSRENEWABLE.COM

TYPICAL SYSTEM INFO

(FOR EACH OF TWO SYSTEMS):

• 1,348,620 KW DC STC +

• BIFACIAL GAIN

• 999,000 KW / KVA AC

• (7) KACO 125TL3 INVERTERS

• CURTAILED TO 124 KW AC

• (988) CANADIAN SOLAR

• CS7N-680TB-A9 BIFACIAL

• MODULES (680W STC)

• (988) CANADIAN SOLAR

• CS7N-685TB-A9 BIFACIAL

• MODULES (685W STC)

REC#ZL222227 (SYSTEM #1)

REC#ZL222229 (SYSTEM #2)

U.I. METERS #TBD (NEW METERS)

U.I. ACCT #TBD (NEW ACCOUNT)



No.

Revision/Issue

Date

BENZ SOLAR

GROUND MOUNTED PV SYSTEM

31 BENZ STREET

ANSONIA, CT 06041

DETAILED ARRAY PLAN - AREA B

PV-4B

Sheet

Date

SEPTEMBER 26, 2024

Scale


1/16" = 1'-0"


DETAILED ARRAY PLAN - AREA 'B'

1/16" = 1'-0"

PV-4B

1





Project Info

PREPARED BY:



56 FOXCROFT COURT
SOUTHINGTON, CT
SGDESIGN.COM
sgde@sgdesign.com

PREPARED FOR:



222 S 9TH STREET, SUITE 1600
MINNEAPOLIS, MN 55402
ECOSRENEWABLE.COM

TYPICAL SYSTEM INFO
(FOR EACH OF TWO SYSTEMS):

• 1,348.620 KW DC STC + BIFACIAL GAIN

- 999.000 KW / KVA AC
- (7) KACO 125TL 3 INVERTERS

- (1) KACO 125TL3 INVERTER

- (988) CANADIAN SOLAR

CS/N-6801B-AG BIFACIAL
MODULES (680W STC)

• (988) CANADIAN SOLAR
CS7N-685TB-AG BIFACIAL

MODULES (685W STC)

REC#ZL2227 (SYSTEM #1)

REC#272229 (SYS IEM #2)

O.I. WILKES #1BD (NEW MILKERS)

U.I. ACCT #1BD (NEW ACCOUNT)



PREPARED BY:



56 FOXCROFT COURT
SOUTHINGTON, CT
SGEDSIGN.COM
sge@sgedesign.com

PREPARED FOR:



222 S 9TH STREET, SUITE 1600
MINNEAPOLIS, MN 55402
ECOSRENEWABLE.COM

TYPICAL SYSTEM INFO
(FOR EACH OF TWO SYSTEMS):

- 1,348.620 KW DC STC + BIFACIAL GAIN
- 999.000 KW / KVA AC
- (7) KACO 125TL3 INVERTERS
- (1) KACO 125TL3 INVERTER CURTAILED TO 124 KW AC
- (988) CANADIAN SOLAR CS7N-680TB-AG BIFACIAL MODULES (680W STC)
- (988) CANADIAN SOLAR CS7N-685TB-AG BIFACIAL MODULES (685W STC)

REC#ZL22227 (SYSTEM #1)

REC#ZL22229 (SYSTEM #2)

U.I. METERS #TBD (NEW METERS)

U.I. ACCT #TBD (NEW ACCOUNT)



No. Revision/Issue Date

BENZ SOLAR
GROUND MOUNTED PV SYSTEM

31 BENZ STREET
ANSONIA, CT 06041

SPECIFICATIONS

Project Sheet

Date
SEPTEMBER 26, 2024

Scale
NTS

PV-5

SECTION 16010 - GENERAL PROVISIONS - ELECTRICAL

- A. The work included under Division 16 shall consist of furnishing labor and materials necessary for the complete installation of lighting, power, and photovoltaic systems shown on the drawings. All work shall be complete and left in operating condition at completion of Contract.
- B. Include minor items that are obviously and reasonably necessary to complete the installation and usually included in similar work. Such items include bolts, nuts, anchors, brackets, sleeves, and minor offsets in conduit, junction boxes, etc.
- C. Some equipment and materials provided under other divisions may require composite work crews because of trade jurisdiction. It is the Contractor's or Subcontractor's responsibility to review all Contract Documents to determine where these composite crews are required.
- D. All temporary and permanent permits and licenses required in connection with this Division's work shall be the responsibility of the Contractor awarded that work.
- E. Installation shall meet or exceed current applicable codes, ordinances and regulations in effect at the site. If a Contractor or Subcontractor observes that the Contract Documents are at variance with governing codes and regulations, they shall promptly notify the Engineer in writing, who will respond to such variances in writing. If the Contractor performs work knowing it is not compliant with applicable codes, and does not notify the Engineer, the Contractor shall assume full responsibility and bear all costs attributable to correcting the non-complying work.
- F. The reference to Codes and Standards shall not permit a lower grade of construction where Contract Documents call for workmanship and/or materials in excess of those references.
- G. Where the terms "provide" or "shall be" are used in this Division or on the drawings, they shall be taken to mean "The Contractor shall furnish and install".
- H. If equipment or materials other than those specified in the design of this project are proposed to be used on this project, the Contractor and supplier shall check it for dimensional differences, electrical requirements and any other potential variances. This comparison shall be made for manufacturers specified as well as those proposed prior to requesting approval. The Contractor shall be responsible for any extra costs incurred as a result of substitutions, including those of other contractors, such as might be due to (but not limited to) different electrical, mechanical and architectural requirements.
- I. Shop Drawings:

1. Carefully examine all shop drawings noting capacity, arrangement and physical dimensions and mark the drawings as being reviewed and approved prior to submitting to the Engineer. Where catalog data is submitted which includes items which do not apply to this project, those items shall be clearly marked out or relevant items clearly noted. Any deviations from the documents shall be so noted by the equipment supplier. The intent and requirements of the drawings and specifications shall be adhered to at all times and are not waived or superseded in any way by the shop drawing submittal or review.
2. Submit a minimum (*) electronic copy of shop drawings for review and approval. Contractor shall retain a final approved copy for incorporation in the Operation and Maintenance Manuals.
3. If returned shop drawings are marked "NO EXCEPTIONS TAKEN" no additional submittal is required. If the shop drawing is marked "MAKE CORRECTIONS NOTED", the changes noted on the shop drawings are to be incorporated, with no further resubmittal required. If marked "REVISE AND RESUBMIT", changes noted on the shop drawings are to be made and the drawings resubmitted for review. If marked "REJECTED", the equipment submitted is unacceptable and different equipment or materials need to be submitted.

- J. No asbestos or PCB containing materials of any type shall be used on this Project.
- K. Consult the Contract Drawings and Specifications of all other Divisions and other trades for correlating information and layout work so that it will not interfere with other trades. Verify all dimensions and conditions. If conflicts occur such that resolution is not possible by the affected trades on the job, the Engineer shall be notified and a resolution will be worked out.
- L. Electrical equipment enclosures (switchboards, panelboards, transformers, relay cabinets, systems racks/cabinets, combiner boxes, etc.) shall be vacuumed and wiped clean prior to energizing and again at substantial completion.
- M. Install material and equipment in accordance with Manufacturers' recommendations, instructions, and current N.E.C.A. standards.
- N. Install equipment and materials to provide required access for servicing and maintenance. Coordinate final equipment location with required access panels and doors. Allow ample space for removal of all parts that require replacement or servicing.
- O. Record Drawings: As work progresses, in a neat and legible manner, record all changes or deviations from the contract drawings. Submit Record Drawings to Engineer for review at completion of Work. The Record Drawings will become part of the Operation and Maintenance Manual package submitted to the Owner after the completion of the project.

SECTION 16050 - BASIC MATERIALS AND METHODS

- A. All materials shall be new, as specified or approved, and in original packaging. Catalog numbers specified shall be verified with vendors prior to ordering material.
- B. All materials shall be listed by a NRTL (i.e. UL, ETL, etc.) and have an associated label unless special fabrication of material is required. Special fabricated material shall be fabricated using listed components and procedures.
- C. Where the word "provide" is used, it shall require the electrical subcontractor to furnish and install material complete to a workable system.
- D. All work shall be tested in accordance with industry accepted standards. Before testing, a thorough visual inspection shall be made to detect connection problems, damaged components, poor workmanship, inappropriate overcurrent protection, cables, etc. Testing apparatus shall be certified or demonstrated to be accurate within reasonable limits. Competent personnel familiar with the test equipment shall perform all tests. If testing procedures employed are not satisfactory to the Engineer, outside testing will be done at the electrical subcontractor's expense.
- E. Electrical subcontractor to identify all electrical equipment with engraved 1/4" white letters on black plates. Inscriptions shall indicate the name, voltage, phase, wires, feeder size, feeder source and location of source, and the device number.
- F. All low voltage cables shall be bundled and labeled as to their function within terminal cabinets, wireways and cable trays.
- G. Branch circuitry shall match circuit numbers as shown on the drawings and as scheduled. Any required deviation shall be indicated on the as-built drawings.
- H. All opening into equipment shall be sealed to prevent entry of insects and rodents.

SECTION 16110 - RACEWAYS

- A. Construction shall be as per Underwriter's Laboratories Standard UL 870 for wireways, auxiliary gutters and associated fittings.
- B. Wireways shall be painted steel with hinged removable cover, which can be used as either a hinged cover or set screw cover. Shall be fabricated such that the entire length of wireway and fittings permit lay in wiring application. Cross sectional area shall be 6" x 6" minimum unless otherwise noted. Raintight wireway shall be NEMA 3R construction with gaskets and a corrosion resistant finish.
- C. Where required, provide cable strain relief, grounding connectors, expansion fittings.
- D. Schedule 40 PVC shall be used for all raceways where not restricted by this section or specifically noted otherwise. Schedule 50 PVC shall be used where above ground or transitions where emerging from ground and exposed to physical damage.
- E. PVC conduit used above grade shall be UV resistant type.
- F. Flexible liquid tight conduit shall be used on all motor, moving, and vibrating equipment connections. Use minimum 1/2" size with grounding type fittings and provide grounding conductor.
- G. Conduit shall not be mounted on mechanical or other equipment which vibrates except at connection points.
- H. Installations of underground wiring shall be in trench, duct or conduit or by plowing in place as specified on plans.

- I. Underground raceways shall be installed to meet the following requirements:

1. Spacing between exterior surfaces of underground conduits shall be not less than the following:
 - a. 2 inches between communications (copper) conduits,
 - b. 2 inches between AC conduits operating at not over 1000 volts
 - c. 6 inches between a communications conduit and any power conduit/cable (AC or DC not over 100V) in the same trench
 - d. 12 inches between a communications conduit and any power conduit (AC or DC over 1000V) in the same trench, unless noted otherwise
 - e. 6 inches between AC conduits operating at over 1000 volts
 - f. 6 inches between AC power conduits and DC power conduits/cables,
 - g. 6 inches between armored fiber optic cable or in metallic conduit and power conduits/cables (AC or DC)
2. Where crossing perpendicular spacing between exterior surface of underground conduits shall be not less than the following:
 - a. 6 inches between AC and DC power conduits operating at any voltage,
 - b. 12 inches between conduits/cables containing AC and DC power conduits operating at any voltage and communications (copper) conduits
- J. All underground raceways when specified in excavated trenches shall have backfill compacted. Refer to compaction requirements in trench compaction details. Backfill immediately around conduits/conductors to be a minimum of 3" native soil free from debris and organic material.

Thermal conductivity of imported backfill shall be tested in accordance with ASTM D5334-08 to confirm the thermal resistivity is equal to or less than that of the native soil or, if applicable, the specific requirements on these plans.
- K. Underground conduit shall be installed to allow drainage into manholes/handholes a minimum of 4 inches per 100 feet of horizontal run. Where conduits or ducts enter a manhole, handhole, or above grade cabinet, each shall be permanently identified by means of plastic fiber, laminated plastic or non-corrosive metal tags to indicate origination point.
- L. When non-metallic conduit requires field bending, utilize a hot-bending appliance. Use of torches to bend conduit is unacceptable.

- M. Where conduits terminate in handholes/vaults or in pad mounted equipment, terminate conduits a minimum of 4 inches above bedding or slab. Conduits shall use bell ends. Where routed through slabs, provide sleeves to allow setting up/heaving of slab.
- N. Where NEMA armored cable is used, Schedule 40 PVC or Schedule 80 PVC (where subject to damage) conduit shall be used for transitions to above grade.

SECTION 16120 - WIRING AND CABLE

- A. Building Wire
1. Description: Single conductor insulated wire.
 2. Conductor: 98% Commercially pure copper conductors or AA-8000 series aluminum alloy compact stranded conductors.
 3. Insulation Voltage Rating: 600 volts and 2000 volts.
 4. Insulation: ANSI/NFPA 70, 90° C Type THHN-2, THWN-2, XHHW-2, RHW-2, USE-2, and PV
 5. Exposed PV module wiring and combiner box feeders shall be 200% volt tray rated PV type.
 6. 600V AC wiring installed below grade shall be type XHHW-2, RHW-2, or USE-2.

- C. Use suitable wire pulling lubricant for building wire 4 AWG and larger.
- D. Neatly trim and lace wiring inside boxes, equipment, and panelboards.
- E. Clean conductor surfaces before installing lugs and connectors.
- F. Make splices, taps and terminations to carry full ampacity of conductors with no perceptible temperature rise.
- G. Parallel 3-phase feeder runs in conduit shall have all three phase conductors (including neutral and ground where required) installed in each conduit. Grouping a single phase (or two phases) in a single conduit is not permitted.
- H. Identification:
1. Control wiring shall be marked at both ends as to its function.
 2. Spare conductors shall be identified as such.

SECTION 16125 - MEDIUM VOLTAGE CABLES

- B. Cables for the 13.8KV system shall be UD 15 KV MV-105 Listed single conductor, insulated, shielded and jacketed medium voltage type power cable with 100% insulation level, 105° C continuous operation rating, 138° C emergency rating, 250° C short circuit rating.
- C. Cable shall have ASTM B-609 aluminum conductors with Class B stranding in accordance with ASTM B-231, moisture blocked strands, an extruded semi-conducting shield layer (40 mil min.) over the conductor for stress control, direct-burial XLPE insulation (345 mils min.), a concentric copper neutral, and moisture/chemical/oil/flame resistant PVC jacket.
- D. Cables shall be Manufactured by Okonite, Physman, Southwire, General Cable, WTEC, or approved equal.
- E. All MV cables must use cable termination kit manufactured by 3M, TE Connectivity, Eaton/Cooper, or Richards.
- F. Complete installation shall be per National Electrical Code Articles 310 and 328. Do not exceed manufacturer's published maximum pulling tension or sidewall pressure. Provide sufficient slack in cable, ground and chain wires to permit elbow connectors to be moved to their respective parking stands.
- G. All cables shall be labeled at each end at an accessible location for viewing. Label shall indicate circuit, phase, and destination/origination. Labels shall be black phenolic with white lettering and secured with a minimum of (2) UV-resistant zip ties.
- H. Splices and terminations shall be made by an experienced journeyman whose qualifications are subject to approval by the Engineer. No splices shall be allowed unless specifically noted. No underground splices are permitted. Fiberglass splice boxes are not permitted unless approved by owner. All splices to be approved by owner.
- I. Arrange phases at termination points, A-B-C from left to right or top to bottom as viewed from the front.
- J. Test all cables according to IEEE Standard 400. Each power cable over 1000V shall be given a continuity test, and each medium voltage cable shall be given a continuity and a VLF test after installation and after terminations having been made. All single conductor cables shall be tested between conductors and ground with metallic shield and the other two conductors grounded to the same ground. Each conductor shall be successively tested in the same manner. Direct current voltage test shall be applied with negative polarity to the cable conductor. See testing procedures as required.
- K. No cable shall be permanently energized until a copy of its test record is approved by the Engineer.
- L. In addition to any testing specified herein, perform testing consistent with the requirements of the applicable codes, NETA Acceptance Testing criteria, and the manufacturers' current quality assurance program.

SECTION 16130 - BOXES

- A. Pull and junction boxes shall be code gauge, gasketed, painted, galvanized steel, PVC, or fiberglass. Covers shall be secured with screws.

- B. Outlet boxes shall be cast malleable iron with threaded huns or PVC and be of high conductive metal to maintain maximum electric continuity.
- C. All outlets shall be equipped with outlet boxes approved for the use.
- D. Covers or plates for boxes shall conform substantially to the outlet of the boxes with no projecting edges or corners.
- E. Conduit fittings ("LB", "C", "T") or types approved for the location may be employed as required to facilitate pulling in conductors.
- F. Provide pull and above ground junction boxes to facilitate pulling or splicing of conductors.
- G. Mount boxes to allow for maximum flexibility.
- H. Install grounding bushings with bonding conductor on all metallic feeder conduits entering box. Ground bushings and bonding conductors are not required on branch circuit conduits.

SECTION 16340 - MEDIUM VOLTAGE SECTIONALIZING CABINETS/MEDIUM VOLTAGE JUNCTION BOXES

- A. Sectionalizing cabinets shall be designed for burial with the junction modules mounted above the ground line. Pedestals shall be in complete conformance with ANSI C57.12.28, Pad-mounted Equipment Enclosure Integrity Standard.
- B. Sectionalizing cabinets shall be Manufactured by Nordic, Cooper, Hubbell, G&W, Power Design Inc., Highline, Federal Pacific, Hoffman, S&C or approved equal.
- C. Enclosure shall be 3/16" nominal thickness fire resistant, laminate, fiberglass, with munsell green gel coat finish or shall be 12 gauge galvanized steel with munsell green polyester powder coat finish. Enclosure access doors shall utilize stainless steel hinges and shall have provisions for padlocking. Doors shall have provisions for securing in the open position.
- D. Provide junction panels with bushings to accommodate the size and quantity of dead break elbows indicated on drawings.
- E. Provide ground bar in unit for bonding of ground conductors and concentric neutrals.
- F. Provide fiberglass ground sleeve extending 36" below cabinet installed on a 6" pea rock base to allow drainage.

SECTION 16400 - DISCONNECT SWITCHES

- A. All disconnect switches shall be NEMA heavy duty Type H.D., horsepower rated, and UL listed. Disconnects shall be Eaton, GE, Square D, Siemens or approved equal.
- B. Provide auxiliary disconnect contacts for control circuits when supplied from an independent source.
- C. Switch Interior - All switches shall have switch blades which are fully visible in the OFF position when the door is open. Switches shall be of dead-front construction with permanently attached arc suppressors hinged or otherwise attached to permit easy access to line-side lugs without removal of the arc suppressor. Lugs shall be UL listed for copper and/or aluminum cables and trim removable. All current carrying parts shall be plated by electrolytic processes.
- D. Switch Mechanism - Switches shall have a quick-make and quick-break operating handle and mechanism which shall be an integral part of the box, not the cover. Switches shall have a dual cover interlock to prevent unauthorized opening of the switch door in the ON position or closing of the switch mechanism with the door open. Switches shall provisions for locking the switch in both the ON and the OFF positions by padlock.
- E. Enclosures shall be NEMA 3R enclosures unless otherwise specified. Raintight covers shall be securable in the open position. Enclosures shall be code gauge (UL 98) galvanized steel (NEMA 3R). They shall be treated with a rust-inhibiting phosphate and finished in gray baked enamel.
- F. Install disconnect switches in an accessible location as convenient as possible to equipment served.
- G. Switches shall be rated for the voltage and system type they are used for.

SECTION 16450 - GROUNDING

- A. Provide complete grounding systems as described herein and as shown on the drawings.
- B. All grounding components shall be listed for the purpose they are installed for. Components shall be Manufactured by AMPACI, Bunday, CADWELD, ITT Blackburn, Ilco, or Lynco.
- C. Ground rods shall be 3/4 inch diameter by 10 feet long copper clad steel. Connecting cables shall be copper as indicated on drawings. All ground conductors exposed to the elements or in direct contact with the earth shall be tin coated or bare copper.
- D. All metallic conduits, supports, cabinets, non-current carrying parts of equipment, and metallic structures shall be solidly grounded to form a continuous permanent and effective grounded system.
- E. All wireways, metal enclosures, cable trays and similar parts of the electrical installation described herein shall be grounded.
- F. UFER grounds shall be via exothermically welded connection to a minimum of (2) continuous 20'-0" sections of rebar encased in the concrete footings/piers with a minimum of 2" of concrete cover. Rebar shall be a minimum of #4 and shall NOT be epoxy coated. If multiple pieces of rebar are required to provide the 20'-0" lengths, they shall be welded together to provide a continuous ground path.
- G. The special attention of the Contractor is called to metallic building components and mechanical piping which must be grounded in an approved manner according to the NEC.
- H. Provide a continuous grounding conductor for each feeder serving several panelboards. Connect this ground conductor to each related cabinet ground bar.
- I. For LVAC circuits less than 1000 VAC not supplied by cables with integral ground wire, provide a separate green insulated equipment grounding conductor for each single or three phase feeder and each branch circuit with a three phase protective device. Install the required grounding conductor in the common conduit with the related phase/hot and neutral conductors. Where parallel feeders are installed in more than one raceway, provide a green insulated equipment grounding conductor in each raceway.
- J. Single Phase Branch Circuits for Lighting, Receptacles, Motors and Other Similar Equipment: Provide single phase branch circuits serving lighting, receptacles, motors, and other similar equipment consisting of phase, neutral, and green insulated equipment ground conductor installed in a common conduit.
- K. Single Phase Branch Circuits for Special Equipment: Provide single phase branch circuits serving special equipment, and all branch circuits installed in nonmetallic or flexible conduits with a separate grounding conductor.
- L. All transformers shall be bonded to the grounding electrode system as well as building steel (where applicable).
- M. Bond all cable tray and equipment racks to ground with a minimum 4/0 AWG ground conductor or as noted on plans.
- N. Connections to the PV modules shall be installed such that removal of a module from the string does not interrupt the grounded conductor to another string. Sets of modules connected in series, rated at 50 volts or more with or without blocking diodes, and having a single overcurrent device shall be considered a string.
- O. When required by the testing plan, the resistance to earth shall be measured using a 3-point fall of potential test with the inverter station ground grid isolated. Results shall be compared to grounding model/study to verify field measured earth resistance is within the same order of magnitude as the grounding model/study.

SECTION 16475 - FUSES

- A. DC fuses for PV string circuits shall be 1500Vdc rated HP15M as Manufactured by Mersen.
- B. DC fuses for PV feeders shall be Class J or gPV type as Manufactured by Bussman, Mersen, or Littelfuse.
- C. Fuses in switchboard, 601A and larger shall be Class I type and be Bussman Class I, Limitron KTJ (or Hi Cap KRP-C), CEFCO Class L CLL, Ferraz Shawmut Class L, Amp Trap A4BY, or Littelfuse Class L, KLP-C.
- D. Fuses for feeder circuits 600A and less shall be Class RK1 and be Bussman Low Peak LPN-RK (250V) or LPN-RK (600V), CEFCO Lo-to-Hi LON-RK (250V) or LON-RK (600V), Ferraz Shawmut

- Amp-Trap II A2D-R (250V) or AED-R (600 V), or Littelfuse Little Peak LLN-RK (250V) or LLS-RK (600V).
- E. Fuses for motor circuits shall be Class RK5 type and be Bussman Fusetron FRN-R (250V) or FRN-R (600 V), CEFCO CEFCO, CRA-R (250V) or CRS-R (600V), Ferraz Shawmut Trionic TR-R (250 V) or TRS-R (600 V), or Littelfuse Sio-Bio FLN-RK (250V) or FLS-R (600V).
- F. For in-line fuses and weatherproof assembly, provide Bussman Tron Type HEB fuse holder and Type KTK fuse with 1A0513 foot or equal.
- G. For protection of control circuit transformers, provide Bussman Type FNQ time delay fuses or equal.
- H. Install fuses to allow viewing of "Blown-Fuse" indicators through viewing windows in gear, where provided.

- I. Provide label inside each switch and motor starter cover stating type of fuse required for replacement.

SECTION 16630 - COMBINER BOXES

- A. Provide 1500V combiner boxes listed to UL 1741, complete with circuitry as necessary to protect the equipment including disconnect switch with finger-safe fuse holders having all necessary fusing. Combiner boxes shall be Eaton/Cooper, Shoals, SolarBos, Amtec, Teal, Bertek, WTEC, or approved equal.
- B. A finger safe, non fused load break disconnect is required and it shall be interlocked to prevent the opening of the cover when the switch is in the ON position. Interlock shall be defeatable for testing purposes. Handle must be lockable in OFF position.
- C. All fuse holders shall be finger-safe.
- D. The combiner box shall be arranged to have a minimum number of input circuits and fuse sizes as indicated on the combiner box schedules for a negatively grounded system. Input fuse holders shall be rated to hold 32A fuses.
- E. Enclosures shall be a minimum of NEMA 3IP54 with seamless door gaskets and an integral disconnect rated as indicated on the combiner box schedules.
- F. All wire terminations/lugs shall be listed for 90°C field terminations.
- G. Combiner boxes including disconnect and fuses shall be listed for continuous operation at 100% of its collector bus/d disconnect rating.
- H. Provide units with integral DC surge protection devices rated for 40KA discharge current (8/20 μ s) and maximum continuous operating voltage of 1500Vdc.
- I. Equipment shall have a nameplate installed and mounted to the front cover and indicate at a minimum: number of input circuits, ampere rating of input circuits, voltage rating, short circuit current rating, and integrated disconnect ampere rating.
- J. Combiner box Manufacturer shall review combiner box schedules and verify combiner boxes enclosures are large enough and configured to allow termination of the size and quantity of string and feeder conductors/conduits indicated on the schedules.
- K. Provide typed PV string directory inside cover to denote strings and their associated fuse/terminal number.
- L. All combiner box components shall be pre-wired before arriving to site.
- M. Provide a directory of combiner boxes at each inverter to facilitate location and shut down of DC sources.

SOLAR PV GENERAL NOTES

1. INSTALL A COMPLETE AND OPERATIONAL SOLAR PHOTOVOLTAIC SYSTEM.
2. THESE DRAWINGS ARE DIAGRAMMATIC AND SHOW THE GENERAL LOCATION AND ARRANGEMENT OF THE SOLAR PV SYSTEM. THEY DO NOT SHOW ALL MATERIALS NEEDED. CONTRACTOR IS REQUIRED TO PROVIDE ANY AND ALL CONDUITS, CONNECTORS, SWEEPS, SUPPORTS, BENDS, FITTINGS, HANDERS, COVER PLATES, AND ADDITIONAL PULL AND JUNCTION BOXES WHICH THE CONTRACTOR MUST PROVIDE TO COMPLETE THE SOLAR PV SYSTEM IN ACCORDANCE WITH THE NATIONAL ELECTRIC CODE (NEC).
3. THE DEFINITION OF ELECTRICAL TERMS USED SHALL BE AS DEFINED IN THE STATES ADOPTED EDITION OF THE NEC.
4. THE TERM "SIZE" SHALL MEAN ONE OR MORE OF THE FOLLOWING: "LENGTH", "CURRENT AND VOLTAGE RATING", "NUMBER OF POLES", "NEMA SIZE", AND OTHER SIMILAR ELECTRICAL CHARACTERISTICS."
5. CONTRACTOR IS REQUIRED TO SURVEY AND INSPECT ALL AREAS PRIOR TO PERFORMING SERVICES TO ENSURE CLEARANCES CAN BE MET AND NO INTERFERENCES EXIST. NO CUTTING OR DRILLING IS TO BE PERFORMED PRIOR TO LOCATING EXISTING STRUCTURAL MEMBERS AND UTILITIES.
6. SERVICE ENTRANCE RATED EQUIPMENT, CUT CABINETS, AND METER SOCKETS ARE TO BE APPROVED FOR USE BY THE LOCAL UTILITY COMPANY.
7. ELECTRICAL EQUIPMENT INSTALLED MUST BE LABELED, UL LISTED, AND INSTALLED ACCORDINGLY.
8. REQUIRED PERMITS AND INSPECTIONS ARE THE RESPONSIBILITY OF THE CONTRACTOR AND MUST BE COORDINATED WITH THE AUTHORITY HAVING JURISDICTION (HAJ).
9. ALL WORK IS TO BE PERFORMED BY LICENSED & QUALIFIED WORKERS AND COMPLETED IN ACCORDANCE WITH THE STATES ADOPTED NEC.
10. THE SOLAR PV SYSTEM EQUIPMENT ON THE DC SIDE IS RATED FOR 1500V AND IS IN COMPLIANCE WITH THE NEC. THE INVERTERS, MODULES, STRING FEEDERS, AND RELATED COMPONENTS ARE ALL RATED AND LABELED AS 1500V OR GREATER.
11. CONTRACTOR SHALL SUBMIT A FORMAL RFI (REQUEST FOR INFORMATION) FOR ANY CONFUSION OR DISCREPANCY ON THE DRAWINGS. CONTRACTOR IS RESPONSIBLE FOR ANY INSTALLATION DEVIATIONS WITHOUT APPROVAL FROM SYSTEM OWNER OR THE ENGINEER OF RECORD.
12. ALL SUPPORTS, BOLTS, STRAPS, AND SCREWS SHALL BE CORROSION RESISTANT.
13. APPLY AN ADHESIVE LABEL ON RACEWAYS ACCORDING TO THE DETAIL SHEET.
14. ALL METALLIC CONDUITS SHALL HAVE BOND BUSHINGS ON BOTH ENDS AND EQUIPMENT GROUNDING CONDUCTORS (EGC) ROUTED THROUGH CONDUIT.
15. BARE COPPER GROUND CONDUCTORS SHALL BE SIZED PER NEC. EQUIPMENT GROUNDING CONDUCTORS (EGC) SHALL BE INSTALLED IN CONDUIT PER NEC 900.4(C).
16. ALL CONDUCTORS SHALL BE LISTED FOR USE IN APPROPRIATE RACEWAY.
17. ALL BREAKERS AND EQUIPMENT INSTALLED AS PART OF THE NEW SOLAR PV SYSTEM MUST BE RATED FOR REVERSE FEED.
18. COMMUNICATION CABLES INSTALLED BETWEEN MONITORING EQUIPMENT AND NETWORK EQUIPMENT (SWITCHES, ROUTERS, SERVERS, ETC.) SHALL HAVE A GREEN OUTER JACKET. CABLES SHALL HAVE CABLE TAGS INSTALLED AT BOTH ENDS OF CABLE TO SHOW PROPER IDENTIFICATION.
19. CONTRACTOR SHALL TORQUE TEST ALL FIELD TERMINATED WIRES PER MANUFACTURER'S SPECS AND PROVIDE PERMANENT MARKINGS ACROSS THE BOLT AND WASHER INDICATING ACHIEVED TORQUE.
20. POLARIS SPLICES SHALL NOT BE USED ON THIS PROJECT.

SPEC IS FROM SIMILAR
ECOS ENERGY PROJECT

STRING WIRE SCHEDULE

Inverter	String ID	Qty of Modules	Total (kW-DC)	Approx 1- Conductor	Drop (%)
			Way	Size (AWG)	
			Length (ft)	Type PV	

1	1-1	26	685	17.81	135	0.71%
1	1-2	26	685	17.81	250	0.74%
1	1-3	26	685	17.81	250	1.32%
1	1-4	26	685	17.81	255	1.35%
1	1-5	26	685	17.81	255	1.35%
1	1-6	26	685	17.81	165	0.87%
1	1-7	26	685	17.81	270	1.43%
1	1-8	26	685	17.81	275	1.45%
1	1-9	26	685	17.81	135	0.92%
2	2-1	26	685	17.81	135	0.71%
2	2-2	26	685	17.81	140	0.74%
2	2-3	26	685	17.81	250	1.32%
2	2-4	26	685	17.81	255	1.35%
2	2-5	26	685	17.81	270	1.43%
2	2-6	26	685	17.81	280	1.48%
2	2-7	26	685	17.81	160	0.85%
2	2-8	26	685	17.81	170	0.90%
2	2-9	26	685	17.81	275	1.45%
2	2-10	26	685	17.81	265	1.40%
3	3-1	26	685	17.81	135	0.71%
3	3-2	26	685	17.81	140	0.74%
3	3-3	26	685	17.81	170	0.90%
3	3-4	26	685	17.81	165	0.87%
3	3-5	26	685	17.81	175	0.92%
3	3-6	26	685	17.81	275	1.45%
3	3-7	26	685	17.81	285	1.51%
3	3-8	26	685	17.81	300	1.58%
3	3-9	26	685	17.81	310	1.64%
4	4-1	26	680	17.68	200	1.05%
4	4-2	26	680	17.68	145	0.76%
4	4-3	26	680	17.68	160	0.84%
4	4-4	26	680	17.68	170	0.90%
4	4-5	26	680	17.68	170	0.90%
4	4-6	26	680	17.68	190	1.00%
4	4-7	26	680	17.68	195	1.03%
4	4-8	26	680	17.68	300	1.58%
4	4-9	26	680	17.68	310	1.63%
5	5-1	26	685	17.81	225	1.19%
5	5-2	26	685	17.81	145	0.77%
5	5-3	26	685	17.81	165	0.87%
5	5-4	26	685	17.81	175	0.92%
5	5-5	26	685	17.81	280	1.48%
5	5-6	26	685	17.81	290	1.53%
5	5-7	26	685	17.81	165	0.87%
5	5-8	26	685	17.81	175	0.92%
5	5-9	26	685	17.81	190	1.00%
5	5-10	26	685	17.81	200	1.06%
6	6-1	26	680	17.68	140	0.74%
6	6-2	26	680	17.68	170	0.90%
6	6-3	26	680	17.68	180	0.95%
6	6-4	26	680	17.68	280	1.48%
6	6-5	26	680	17.68	290	1.53%
6	6-6	26	680	17.68	295	1.55%
6	6-7	26	680	17.68	285	1.50%
6	6-8	26	680	17.68	175	0.92%
6	6-9	26	680	17.68	195	1.03%
6	6-10	26	680	17.68	205	1.08%
7	7-1	26	680	17.68	225	1.19%
7	7-2	26	680	17.68	170	0.90%
7	7-3	26	680	17.68	180	0.95%
7	7-4	26	680	17.68	285	1.50%
7	7-5	26	680	17.68	295	1.55%
7	7-6	26	680	17.68	300	1.58%
7	7-7	26	680	17.68	290	1.53%
7	7-8	26	680	17.68	200	1.05%
7	7-9	26	680	17.68	210	1.11%
8	8-1	26	680	17.68	145	0.76%
8	8-2	26	680	17.68	190	1.00%
8	8-3	26	680	17.68	200	1.05%
8	8-4	26	680	17.68	190	1.00%
8	8-5	26	680	17.68	200	1.05%
8	8-6	26	680	17.68	175	0.92%
8	8-7	26	680	17.68	200	1.05%
8	8-8	26	680	17.68	210	1.11%
8	8-9	26	680	17.68	235	1.24%
8	8-10	26	680	17.68	245	1.29%

NOTE - ONE WAY LENGTHS OF RUN INDICATED IN THIS TABLE ARE FOR VOLTAGE DROP CALCULATION PURPOSES ONLY. CONTRACTOR SHALL VERIFY EXACT LENGTHS. IF ACTUAL LENGTHS ARE LONGER THAN INDICATED IN THIS SCHEDULE, CONTACT SOLAR DEVELOPER FOR GUIDANCE REGARDING STRING SIZING.

STRING WIRE SCHEDULE

Inverter	String ID	Qty of Modules	Total (kW-DC)	Approx 1- Conductor	Drop (%)
			Way	Size (AWG)	
			Length (ft)	Type PV	

9	9-1	26	685	17.81	140	0.74%			
9	9-2	26	685	17.81	160	0.85%			
9	9-3	26	685	17.81	195	1.03%			
9	9-4	26	685	17.81	235	1.24%			
9	9-5	26	685	17.81	265	1.40%			
9	9-6	26	685	17.81	260	1.37%			
9	9-7	26	685	17.81	200	1.06%			
10	10-10	26	685	17.81	205	1.08%			
10	10-9	26	685	17.81	250	1.32%			
10	10-8	26	685	17.81	275	1.32%			
10	10-7	26	685	17.81	175	0.92%			
10	10-6	26	685	17.81	165	0.87%			
10	10-5	26	685	17.81	290	1.53%			
10	10-4	26	685	17.81	210	1.11%			
10	10-3	26	685	17.81	205	1.08%			
10	10-2	26	685	17.81	145	0.77%			
10	10-1	26	685	17.81	140	0.74%			
10	10	26	685	17.81	240	1.27%			
9	9-9	26	685	17.81	205	1.08%			
9	9-8	26	685	17.81	205	1.08%			
9	9-7	26	685	17.81	170	0.90%			
9	9-6	26	685	17.81	260	1.37%			
9	9-5	26	685	17.81	265	1.40%			
9	9-4	26	685	17.81	235	1.24%			
9	9-3	26	685	17.81	195	1.03%			
9	9-2	26	685	17.81	160	0.85%			
9	9-1	26	685	17.81	140	0.74%			
TOTAL							3952	2697.240	1.12%

NOTE - ONE WAY LENGTHS OF RUN INDICATED IN THIS TABLE ARE FOR VOLTAGE DROP CALCULATION PURPOSES ONLY. CONTRACTOR SHALL VERIFY EXACT LENGTHS. IF ACTUAL LENGTHS ARE LONGER THAN INDICATED IN THIS SCHEDULE, CONTACT SOLAR DEVELOPER FOR GUIDANCE REGARDING STRING SIZING.

STRING CONDUIT SCHEDULE

String	Location	Conduit Size
--------	----------	--------------

STRING CONDUIT A	1-1/2"	1
STRING CONDUIT B	1"	1-9
STRING CONDUIT C	1-1/2"	2-7 THRU 2-10
STRING CONDUIT D	1-1/4"	2-5 & 2-6
STRING CONDUIT E	1-1/4"	3-3 THRU 3-5
STRING CONDUIT F	1-1/4"	3-6 & 3-7
STRING CONDUIT G	1-1/4"	3-8 & 3-9
STRING CONDUIT H	1-1/4"	4-1, 4-5 & 4-6
STRING CONDUIT I	1-1/4"	4-7 THRU 4-9
STRING CONDUIT J	1-1/2"	5-7 THRU 5-10
STRING CONDUIT K	1"	5-1
STRING CONDUIT L	1-1/4"	6-6 & 6-7
STRING CONDUIT M	1-1/4"	6-8 THRU 6-10
STRING CONDUIT N	1-1/4"	7-6 & 7-7
STRING CONDUIT O	1-1/4"	7-8 & 7-9
STRING CONDUIT P	1-1/4"	8-6 THRU 8-8
STRING CONDUIT Q	1-1/4"	8-6 THRU 8-8
STRING CONDUIT R	1-1/4"	8-9 & 8-10
STRING CONDUIT S	1"	8-10
STRING CONDUIT T	1-1/4"	8-4 & 8-5
STRING CONDUIT U	1-1/2"	13-5 THRU 13-8
STRING CONDUIT V	1"	13-9
STRING CONDUIT W	1-1/2"	14-3 THRU 14-6
STRING CONDUIT X	1-1/2"	14-7 THRU 14-10
STRING CONDUIT Y	1-1/4"	14-8 THRU 14-10
STRING CONDUIT Z	1"	14-10
STRING CONDUIT AA	1-1/4"	15-7 THRU 15-9
STRING CONDUIT BB	1"	15-6
STRING CONDUIT CC	1"	15-10
STRING CONDUIT DD	1-1/4"	16-1 THRU 16-3
STRING CONDUIT EE	1-1/4"	16-4 THRU 16-6
STRING CONDUIT FF	1-1/4"	16-5 & 16-6
STRING CONDUIT GG	1-1/4"	12-7 THRU 12-9
STRING CONDUIT HH	1-1/4"	11-7 THRU 11-9
STRING CONDUIT II	1-1/4"	10-6 THRU 10-8
STRING CONDUIT JJ	1-1/4"	10-9 & 10-10
STRING CONDUIT KK	1-1/2"	9-2 THRU 9-5
STRING CONDUIT LL	1-1/4"	9-3 THRU 9-5
STRING CONDUIT MM	1-1/4"	9-4 & 9-5
STRING CONDUIT NN	1"	9-5
STRING CONDUIT PP	1-1/2"	9-6 THRU 9-9
STRING CONDUIT QQ	1-1/4"	9-8 & 9-9
STRING CONDUIT RR	1"	9-9
STRING CONDUIT SS	1"	10-5

Project Info

PREPARED BY:



56 FOXCROFT COURT

SOUTHINGTON, CT

SGDESIGN.COM

sgdesign.com

PREPARED FOR:



222 S 9TH STREET, SUITE 1600
MINNEAPOLIS, MN 55402

ECOSRENEWABLE.COM

TYPICAL SYSTEM INFO

(FOR EACH OF TWO SYSTEMS):


• 1,348.620 KW DC STC +

BIFACIAL GAIN

• 999.000 KW / KVA AC



UTILITY COMPANY PRIMARY METERING ENCLOSURE PAD DETAILS





Division Specification


Division	Specification
1.0000	General Requirements
2.0000	Structures
3.0000	Electrical
4.0000	Plumbing
5.0000	Mechanical
6.0000	Transportation
7.0000	Telecommunications
8.0000	Construction
9.0000	Other

Notes:

1. The pad shall be installed on a concrete base.
2. The enclosure shall be installed on the pad.
3. The pad shall be 12' x 12'.
4. The enclosure shall be 6' x 6'.
5. The pad shall have a 1' clearance around the enclosure.






GROUND MOUNTED PV SYSTEM



ABBREVIATIONS

Symbol	Description
1.0000	General Requirements
2.0000	Structures
3.0000	Electrical
4.0000	Plumbing
5.0000	Mechanical
6.0000	Transportation
7.0000	Telecommunications
8.0000	Construction
9.0000	Other

- GENERAL NOTES
1. DRAWINGS SHALL BE THE GENERAL INTENT FOR THE PV SYSTEM. ITEMS SUCH AS CONDUIT, WIRING, AND CONNECTIONS SHALL BE SHOWN BUT ARE NOT TO BE CONSIDERED AS PART OF THE SYSTEM. ITEMS SUCH AS CONDUIT, WIRING, AND CONNECTIONS SHALL BE SHOWN BUT ARE NOT TO BE CONSIDERED AS PART OF THE SYSTEM.
 2. DEFINITIONS SHALL BE BASED ON THE CURRENT EDITION OF THE NATIONAL ELECTRIC CODE.
 3. CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS.
 4. ELECTRICAL RATING SHALL BE BASED ON THE ENGINEER'S BEST JUDGMENT.
 5. CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS.
 6. CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS.
 7. CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS.
 8. CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS.
 9. CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS.
 10. CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS.
 11. CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS.
 12. CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS.
 13. CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS.
 14. CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS.
 15. CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS.
 16. CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS.
 17. CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS.
 18. CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS.
 19. CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS.
 20. CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS.
 21. CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS.



NOTES, DETAILS & ABBREVIATIONS

Project Information

Project	Date	Scale
PV-8	SEPTEMBER 26, 2024	N.T.S.

Notes:

1. The pad shall be installed on a concrete base.
2. The enclosure shall be installed on the pad.
3. The pad shall be 12' x 12'.
4. The enclosure shall be 6' x 6'.
5. The pad shall have a 1' clearance around the enclosure.

Project Information

Prepared by: SGE ENGINEERING LLC

56 FOXCROFT COURT
SOUTHINGTON, CT 06488

sgedesign.com
sgedesign@sgedesign.com

Prepared for: ECOS ENERGY



222 S 9TH STREET, SUITE 1600
MINNEAPOLIS, MN 55402

ECOSRENEWABLE.COM



Typical System Info (For Each of Two Systems):

- 1,348,620 KW DC STC + BIFACIAL GAIN
- 999,000 KW / KVA AC
- (7) KACO 125TL3 INVERTERS
- (1) KACO 125TL3 INVERTER
- CURTAILED TO 124 KW AC
- (988) CANADIAN SOLAR
- CS7N-680TB-AG BIFACIAL MODULES (680W STC)
- (988) CANADIAN SOLAR
- CS7N-685TB-AG BIFACIAL MODULES (685W STC)
- REC#ZL22227 (SYSTEM #1)
- REC#ZL22229 (SYSTEM #2)
- U.I. METERS #TBD (NEW METERS)
- U.I. ACCT #TBD (NEW ACCOUNT)





PENDING UPDATED DATA SHEETS FROM G&W



Project Info

PREPARED BY:



56 FOXCROFT COURT
SOUTHINGTON, CT
SGDESIGN.COM
sges@sgdesign.com

PREPARED FOR:



222 S 9TH STREET, SUITE 1600
MINNEAPOLIS, MN 55402
ECOSRENEWABLE.COM

TYPICAL SYSTEM INFO
(FOR EACH OF TWO SYSTEMS):

- 1,348.620 KW DC STC + BIFACIAL GAIN
- 999.000 KW / KVA AC
- (7) KACO 125TL3 INVERTERS
- (1) KACO 125TL3 INVERTER CURTAILED TO 124 KW AC
- (988) CANADIAN SOLAR CS7N-680TB-AG BIFACIAL MODULES (680W STC)
- (988) CANADIAN SOLAR CS7N-685TB-AG BIFACIAL MODULES (685W STC)

REC#ZL22227 (SYSTEM #1)
REC#ZL22229 (SYSTEM #2)

U.I. METERS #TBD (NEW METERS)

U.I. ACCT #TBD (NEW ACCOUNT)



No.	Revision/Issue	Date

BENZ SOLAR
GROUND MOUNTED PV SYSTEM


31 BENZ STREET
ANSONIA, CT 06041

CUSTOMER OWNED RECLOSER
DATA SHEETS

Project	Sheet
Date SEPTEMBER 26, 2024	PV-11
Scale NTS	

1 CUSTOMER OWNED RECLOSER DATA SHEETS
PV-11 NOT TO SCALE

PENDING APPROVAL FROM U.I.



SEE SUBMITTAL FOR ADDITIONAL INFORMATION

PRIMARY METERING CABINET DATA SHEETS
NOT TO SCALE

Project
Sheet
Date
SEPTEMBER 26, 2024
Scale
NTS
PV-12

PRIMARY METERING ENCLOSURE
DATA SHEETS

BENZ SOLAR
GROUND MOUNTED PV SYSTEM
31 BENZ STREET
ANSONIA, CT 06041

No.
Revision/Issue
Date



U.I. METERS #TBD (NEW METERS)
U.I. ACCT #TBD (NEW ACCOUNT)

REC#ZL222227 (SYSTEM #1)
REC#ZL222229 (SYSTEM #2)

MODULES (685W STC)
CS7N-685TB-AG BIFACIAL

MODULES (680W STC)
CS7N-680TB-AG BIFACIAL

MODULES (680W STC)
CS7N-680TB-AG BIFACIAL

MODULES (680W STC)
CS7N-680TB-AG BIFACIAL

MODULES (680W STC)
CS7N-680TB-AG BIFACIAL

MODULES (680W STC)
CS7N-680TB-AG BIFACIAL

MODULES (680W STC)
CS7N-680TB-AG BIFACIAL

MODULES (680W STC)
CS7N-680TB-AG BIFACIAL

MODULES (680W STC)
CS7N-680TB-AG BIFACIAL

MODULES (680W STC)
CS7N-680TB-AG BIFACIAL

MODULES (680W STC)
CS7N-680TB-AG BIFACIAL

MODULES (680W STC)
CS7N-680TB-AG BIFACIAL

MODULES (680W STC)
CS7N-680TB-AG BIFACIAL


MODULES (680W STC)
CS7N-680TB-AG BIFACIAL

PENDING UPDATED
DATA SHEETS FROM
TERRASMART

1 DC COMBINER BOX DATA SHEET
PV-13 NOT TO SCALE

PENDING UPDATED
DATA SHEETS FROM
TERRASMART

2 DC DISCONNECT SWITCH DATA SHEET
PV-13 NOT TO SCALE



SAMPLE WIRING DIAGRAM
FROM SPS FOR TWO METERS
CONNECTED TO THE SAME
SET OF CT'S IN SERIES

3 ZREC & REVENUE METER WIRING DIAGRAM
PV-13 NOT TO SCALE

Project Info

PREPARED BY:



56 FOXCROFT COURT
SOUTHINGTON, CT
SGEDSIGN.COM
sge@sgedesign.com

PREPARED FOR:



222 S 9TH STREET, SUITE 1600
MINNEAPOLIS, MN 55402
ECOSRENEWABLE.COM

TYPICAL SYSTEM INFO
(FOR EACH OF TWO SYSTEMS):

- 1,348.620 KW DC STC + BIFACIAL GAIN
- 999.000 KW / KVA AC
- (7) KACO 125TL3 INVERTERS
- (1) KACO 125TL3 INVERTER CURTAILED TO 124 KW AC
- (988) CANADIAN SOLAR CS7N-680TB-AG BIFACIAL MODULES (680W STC)
- (988) CANADIAN SOLAR CS7N-685TB-AG BIFACIAL MODULES (685W STC)

REC#ZL22227 (SYSTEM #1)
REC#ZL22229 (SYSTEM #2)

U.I. METERS #TBD (NEW METERS)

U.I. ACCT #TBD (NEW ACCOUNT)



No.	Revision/Issue	Date

BENZ SOLAR
GROUND MOUNTED PV SYSTEM

31 BENZ STREET
ANSONIA, CT 06041

EQUIPMENT DATA SHEETS

Project	Sheet
Date SEPTEMBER 26, 2024	PV-13
Scale NTS	

