

<b>Pad ID</b>	<b>Width (ft)</b>	<b>Length (ft)</b>	<b>Surface Area (SF)</b>	<b>Depth (ft)</b>	<b>Volume (CY)</b>	<b>Weight (lb)<sup>1</sup></b>	<b>Weight (tons)<sup>2</sup></b>
Electrical Service Pad A (West Site)	13	12.5	162.5	0.67	4.0	16250.0	8.125
Equipment Pad A (West Site)	20.5	28	574	0.67	14.2	57400.0	28.7
Electrical Service Pad B (East Site)	13	12.5	162.5	0.67	4.0	16250.0	8.125
Equipment Pad B1 (East Site)	20.5	28	574	0.67	14.2	57400.0	28.7
Equipment Pad B2 (East Site)	20.5	28	574	0.67	14.2	57400.0	28.7
<b>Total</b>	-	-	<b>2047</b>	-	<b>50.5</b>	<b>204700.0</b>	<b>102.4</b>

<sup>1</sup>Weight of 4000 psi concrete = 150 lb/ft<sup>3</sup>

<sup>2</sup> 2000 lb/ton