Site Plans

Issued forApplicationDate IssuedJuly 23, 2021Latest IssueJuly 23, 2021

Photovoltaic Installation

Mulnite Farms East Windsor, Connecticut

Applicant

Greenskies Clean Energy, LLC 127 Washington Ave West Building, Garden Level North Haven, CT 06473

Map / Block / Lot:

038 / 68 / 030 028 / 68 / 023

Owner

Mulnite Farms, Inc. 28 Miller Road Broad Brook, CT 06016

Leonard A. Mulnite Revocable Trust Agreement & Donna L. Mulnite Revocable Trust Agreement 28 Miller Road Broad Brook, CT 06016



Sheet Index			Refer	ence Drawings
No.	Drawing Title	Latest Issue	No.	Drawing Title
C-1.0	Legend and General Notes	July 23, 2021	19-119	Plan of Land in East Windsor, CT
C-2.0	Key Plan	July 23, 2021	20-265	Plan of Land in East Windsor, CT
C-3.0	Layout and Materials Plan - Overall	July 23, 2021	20-266	Plan of Land in East Windsor, CT
C-3.1-3.3	Layout and Materials Plan 1 through 3	July 23, 2021		
C-4.0	Grading and Drainage Plan - Overall	July 23, 2021		
C-4.1-4.3	Grading and Drainage Plan 1 through 3	July 23, 2021		
C-5.0	Erosion and Sediment Control Plan - Overall	July 23, 2021		
C-5.1-5.3	Erosion and Sediment Control Plan 1 through 3	July 23, 2021		
C-6.1-6.2	Site Details	July 23, 2021		

Latest	lssue

March	15,	2021
March	12,	2021
March	15,	2021

s vhb

100 Great Meadow Road Suite 200 Wethersfield, CT 06109 860.807.4300

Licensed Land Surveyor

Northeast Survey Consultants
116 Pleasant St. Suite 302
P.O. Box 109
Easthampton, MA 01027
413-203-5144

Legend

Exist.	Prop.		Exist.	Prop.	
		PROPERTY LINE			CONCRETE
		PROJECT LIMIT LINE			HEAVY DUTY PAVEMENT
		RIGHT-OF-WAY/PROPERTY LINE			BUILDINGS
		EASEMENT			RIPRAP
			520102320		
		BUILDING SETBACK		<i>~~~~~</i> ~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~	
10+00	10+00	PARKING SETBACK	27.35 TC×	27.35 TC \times	TOP OF CURB ELEVATION
		BASELINE	26.85 BC×	26.85 BC×	BOTTOM OF CURB ELEVATION
		CONSTRUCTION LAYOUT	130 75 🗸	170 75 🗸	SPOT ELEVATION
		ZONING LINE	132.75 × 45.0 TW _×	132.75 × 45.0 TW _× 38.5 BW	
		TOWN LINE	38.5 BW	38.5 BW	TOP & BOTTOM OF WALL ELEVATIO
				Ţ	BORING LOCATION
		LIMIT OF DISTURBANCE			TEST PIT LOCATION
<u>∆</u> ·		WETLAND LINE WITH FLAG	⊖ ^{MW}	Θ^{MW}	MONITORING WELL
		FLOODPLAIN			
		100-YEAR FLOOD LIMITS		UD 12″D →	UNDERDRAIN
					DRAIN
		GRAVEL ROAD		<u>6″RD</u> →	ROOF DRAIN
EOP	EOP	EDGE OF PAVEMENT	12"S	12 " S	SEWER
BB	BB	BITUMINOUS BERM	FM	FM	FORCE MAIN
BC	BC		OHW	OH W	OVERHEAD WIRE
		BITUMINOUS CURB	6"W	6 * W	WATER
00		CONCRETE CURB			FIRE PROTECTION
	CG	CURB AND GUTTER		2*DW	
<u> </u>	ECC	EXTRUDED CONCRETE CURB	= 27	2 Uw	DOMESTIC WATER
CC	MCC	MONOLITHIC CONCRETE CURB		G	GAS
CC	PCC	PRECAST CONC. CURB	——————————————————————————————————————	——E——	ELECTRIC
SGE	SCE	SLOPED GRAN, EDGING	STM	STM	STEAM
VGC	VGC		T	T	TELEPHONE
		VERT. GRAN. CURB	——FA	——FA——	FIRE ALARM
		LIMIT OF CURB TYPE	CATV	——CATV——	ĆABLE TV
		SAWCUT			
(,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,					CATCH BASIN
(///////.		BUILDING			DOUBLE CATCH BASIN
		BUILDING ENTRANCE		==	GUTTER INLET
		LOADING DOCK	D	۲	Drain Manhole
*	-	BOLLARD	=TD=		TRENCH DRAIN
D	D	DUMPSTER PAD	Г	r	PLUG OR CAP
		SIGN	co	¢0	
	•		•		CLEANOUT
<u> </u>	-	DOUBLE SIGN			FLARED END SECTION
			- \	\sim	HEADWALL
1 1	I	STEEL GUARDRAIL	S	•	SEWER MANHOLE
		WOOD GUARDRAIL			
			CS	CS ●	CURB STOP & BOX
	= $=$ $=$ $=$	ΡΑΤΗ	WV	wv •	WATER VALVE & BOX
\sim	<u> </u>	TREE LINE	TSV	TSV	TAPPING SLEEVE, VALVE & BOX
×	- x x	WIRE FENCE	> 4~3	● ▶ _\★	
o		FENCE	HYD	HYD	
	- a	STOCKADE FENCE	© 	©• _₩M	FIRE HYDRANT
-			⊡ PIV	⊡ PIV	WATER METER
x000000	-0000000-				POST INDICATOR VALVE
		RETAINING WALL	\odot	\otimes	WATER WELL
		STREAM / POND / WATER COURSE	GG	GG O	GAS GATE
		DETENTION BASIN	GM	GM ⊡	GAS METER
		HAY BALES			
-xx	xx	SILT FENCE	Ē	● ^{EMH}	ELECTRIC MANHOLE
<	· C	SILT SOCK / STRAW WATTLE	EM	EM ⊡	ELECTRIC METER
	~		_ ¢	*	LIGHT POLE
4	4	MINOR CONTOUR		● ^{TMH}	
	20	MAJOR CONTOUR	Ĩ	•	TELEPHONE MANHOLE
(10)	10	PARKING COUNT	T	T	TRANSFORMER PAD
	_		-0-	+	
DM	(C10)	COMPACT PARKING STALLS	~	-	UTILITY POLE
DYL	DYL	DOUBLE YELLOW LINE	0-	• -	GUY POLE
	SL	STOP LINE	<u>ل</u>	Ļ	GUY WIRE & ANCHOR
SL		CROSSWALK	HH	HH ⊡	HAND HOLE
SL			PB	PB	
					PULL BOX
SL	ااااااااااا ک بچ	ACCESSIBLE CURB RAMP ACCESSIBLE PARKING	•		PULL BOX

Abbreviations

	ADDIEVIATIONS
General	
ABAN	ABANDON
ACR	ACCESSIBLE CURB RAMP
ADJ	ADJUST
APPROX	APPROXIMATE
BI⊤	BITUMINOUS
BS	BOTTOM OF SLOPE
BWLL	BROKEN WHITE LANE LINE
CONC	CONCRETE
DYCL	DOUBLE YELLOW CENTER LINE
EL	ELEVATION
ELEV	ELEVATION
EX	EXISTING
FDN	FOUNDATION
FFE	FIRST FLOOR ELEVATION
GRAN	GRANITE
GTD	GRADE TO DRAIN
LA	LANDSCAPE AREA
LOD	LIMIT OF DISTURBANCE
MAX	MAXIMUM
MIN	
NIC	NOT IN CONTRACT
NTS	NOT TO SCALE
PERF	PERFORATED
PROP	PROPOSED
REM	REMOVE
RET	RETAIN
R&D	REMOVE AND DISPOSE
R&R	REMOVE AND RESET
SWEL	SOLID WHITE EDGE LINE
SWLL	SOLID WHITE LANE LINE
тѕ	TOP OF SLOPE
ТҮР	TYPICAL
ITE	TTRAL
Utility	
CB	CATCH BASIN
CMP	CORRUGATED METAL PIPE
со	CLEANOUT
DCB	DOUBLE CATCH BASIN
DMH	DRAIN MANHOLE
CIP	CAST IRON PIPE
	CONDUIT
DIP	DUCTILE IRON PIPE
FES	FLARED END SECTION
FM	FORCE MAIN
F&G	FRAME AND GRATE
F&C	FRAME AND COVER
GI	GUTTER INLET
GT	GREASE TRAP
HDPE	HIGH DENSITY POLYETHYLENE PIPE
HH	HANDHOLE
HW	HEADWALL
HYD	HYDRANT
INV	INVERT ELEVATION
I =	INVERT ELEVATION
LP	LIGHT POLE
MES	METAL END SECTION
PIV	POST INDICATOR VALVE
PWW	PAVED WATER WAY
PVC	
RCP	REINFORCED CONCRETE PIPE
R=	RIM ELEVATION
	SEWER MANHOLE
TSV	TAPPING SLEEVE, VALVE AND BOX
UG	UNDERGROUND

UP

UTILITY POLE

General

- 1. CONTRACTOR SHALL NOTIFY "CALL BEFORE YOU DIG" (811 OR 1-800-922-4455) AT LEAST 72 HOURS BEFORE EXCAVATING.
- 2. CONTRACTOR SHALL BE RESPONSIBLE FOR SITE SECURITY AND JOB SAFETY. CONSTRUCTION ACTIVITIES SHALL BE IN ACCORDANCE WITH OSHA STANDARDS AND LOCAL REQUIREMENTS.
- 3. WORK WITHIN THE LOCAL RIGHTS-OF-WAY SHALL CONFORM TO LOCAL MUNICIPAL STANDARDS.
- 4. UPON AWARD OF CONTRACT, CONTRACTOR SHALL MAKE NECESSARY CONSTRUCTION NOTIFICATIONS AND APPLY FOR AND OBTAIN NECESSARY PERMITS, PAY FEES, AND POST BONDS ASSOCIATED WITH THE WORK INDICATED ON THE DRAWINGS, IN THE SPECIFICATIONS, AND IN THE CONTRACT DOCUMENTS. DO NOT CLOSE OR OBSTRUCT ROADWAYS, SIDEWALKS, AND FIRE HYDRANTS, WITHOUT APPROPRIATE PERMITS.
- 5. AREAS OUTSIDE THE LIMITS OF PROPOSED WORK DISTURBED BY THE CONTRACTOR'S OPERATIONS SHALL BE RESTORED BY THE CONTRACTOR TO THEIR ORIGINAL CONDITION AT THE CONTRACTOR'S EXPENSE.
- 6. IN THE EVENT THAT SUSPECTED CONTAMINATED SOIL, GROUNDWATER, AND OTHER MEDIA ARE ENCOUNTERED DURING EXCAVATION AND CONSTRUCTION ACTIVITIES BASED ON VISUAL, OLFACTORY, OR OTHER EVIDENCE, THE CONTRACTOR SHALL STOP WORK IN THE VICINITY OF THE SUSPECT MATERIAL TO AVOID FURTHER SPREADING OF THE MATERIAL, AND SHALL NOTIFY THE OWNER IMMEDIATELY SO THAT THE APPROPRIATE TESTING AND SUBSEQUENT ACTION CAN BE TAKEN.
- 7. CONTRACTOR SHALL PREVENT DUST, SEDIMENT, AND DEBRIS FROM EXITING THE SITE AND SHALL BE RESPONSIBLE FOR CLEANUP, REPAIRS AND CORRECTIVE ACTION IF SUCH OCCURS.
- 8. DAMAGE RESULTING FROM CONSTRUCTION LOADS SHALL BE REPAIRED BY THE CONTRACTOR AT NO ADDITIONAL COST TO OWNER.
- 9. CONTRACTOR SHALL CONTROL STORMWATER RUNOFF DURING CONSTRUCTION TO PREVENT ADVERSE IMPACTS TO OFF SITE AREAS, AND SHALL BE RESPONSIBLE TO REPAIR RESULTING DAMAGES, IF ANY, AT NO COST TO OWNER.
- 10. THIS PROJECT DISTURBS MORE THAN FIVE ACRES OF LAND AND WILL REQUIRE ADHERENCE TO AND REGISTRATION FOR THE CONNECTICUT DEPARTMENT OF ENERGY & ENVIRONMENTAL PROTECTION GENERAL PERMIT FOR THE DISCHARGE OF STORMWATER AND DEWATERING WASTEWATERS FROM CONSTRUCTION ACTIVITIES, EFFECTIVE DECEMBER 31, 2020.
- 11. STAGING AND STOCKPILE AREAS SHALL NOT BE LOCATED WITHIN ANY WETLAND AND ABUTTING RESOURCE AREA AND SHALL BE LOCATED WITHIN THE LIMITS OF DISTURBANCE.

Utilities

- 1. THE LOCATIONS, SIZES, AND TYPES OF EXISTING UTILITIES ARE SHOWN AS AN APPROXIMATE REPRESENTATION ONLY. THE OWNER OR IT'S REPRESENTATIVE(S) HAVE NOT INDEPENDENTLY VERIFIED THIS INFORMATION AS SHOWN ON THE PLANS. THE UTILITY INFORMATION SHOWN DOES NOT GUARANTEE THE ACTUAL EXISTENCE, SERVICEABILITY, OR OTHER DATA CONCERNING THE UTILITIES, NOR DOES IT GUARANTEE AGAINST THE POSSIBILITY THAT ADDITIONAL UTILITIES MAY BE PRESENT THAT ARE NOT SHOWN ON THE PLANS, PRIOR TO ORDERING MATERIALS AND BEGINNING CONSTRUCTION, THE CONTRACTOR SHALL VERIFY AND DETERMINE THE EXACT LOCATIONS, SIZES, AND ELEVATIONS OF THE POINTS OF CONNECTIONS TO EXISTING UTILITIES AND, SHALL CONFIRM THAT THERE ARE NO INTERFERENCES WITH EXISTING UTILITIES AND THE PROPOSED UTILITY ROUTES, INCLUDING ROUTES WITHIN THE PUBLIC RIGHTS OF WAY.
- 2. WHERE AN EXISTING UTILITY IS FOUND TO CONFLICT WITH THE PROPOSED WORK, OR EXISTING CONDITIONS DIFFER FROM THOSE SHOWN SUCH THAT THE WORK CANNOT BE COMPLETED AS INTENDED, THE LOCATION, ELEVATION, AND SIZE OF THE UTILITY SHALL BE ACCURATELY DETERMINED WITHOUT DELAY BY THE CONTRACTOR, AND THE INFORMATION FURNISHED IN WRITING TO THE OWNER'S REPRESENTATIVE FOR THE RESOLUTION OF THE CONFLICT AND CONTRACTOR'S FAILURE TO NOTIFY PRIOR TO PERFORMING ADDITIONAL WORK RELEASES OWNER FROM OBLIGATIONS FOR ADDITIONAL PAYMENTS WHICH OTHERWISE MAY BE WARRANTED TO RESOLVE THE CONFLICT.
- 3. THE LOCATION, SIZE, DEPTH, AND SPECIFICATIONS FOR CONSTRUCTION OF PROPOSED PRIVATE UTILITY SERVICES SHALL BE INSTALLED ACCORDING TO THE REQUIREMENTS PROVIDED BY, AND APPROVED BY, THE RESPECTIVE UTILITY COMPANY (GAS, TELEPHONE, ELECTRIC, FIRE ALARM, ETC.). FINAL DESIGN LOADS AND LOCATIONS TO BE COORDINATED WITH OWNER AND ARCHITECT.
- 4. CONTRACTOR SHALL MAKE ARRANGEMENTS FOR AND SHALL BE RESPONSIBLE FOR PAYING FEES FOR POLE RELOCATION AND FOR THE ALTERATION AND ADJUSTMENT OF GAS, ELECTRIC, TELEPHONE, FIRE ALARM, AND ANY OTHER PRIVATE UTILITIES, WHETHER WORK IS PERFORMED BY CONTRACTOR OR BY THE UTILITIES COMPANY.
- 5. CONTRACTOR SHALL COORDINATE WITH ELECTRICAL CONTRACTOR AND SHALL FURNISH EXCAVATION, INSTALLATION, AND BACKFILL OF ELECTRICAL FURNISHED SITEWORK RELATED ITEMS SUCH AS PULL BOXES, CONDUITS, DUCT BANKS, LIGHT POLE BASES, AND CONCRETE PADS. SITE CONTRACTOR SHALL FURNISH CONCRETE ENCASEMENT OF DUCT BANKS IF REQUIRED BY THE UTILITY COMPANY AND AS INDICATED ON THE DRAWINGS.

Layout and Materials

- 1. PROPOSED BOUNDS AND ANY EXISTING PROPERTY LINE MONUMENTATION DISTURBED DURING CONSTRUCTION SHALL BE SET OR RESET BY A PROFESSIONAL LICENSED SURVEYOR.
- 2. PRIOR TO START OF CONSTRUCTION, CONTRACTOR SHALL VERIFY EXISTING PAVEMENT ELEVATIONS AT INTERFACE WITH PROPOSED PAVEMENTS, AND EXISTING GROUND ELEVATIONS ADJACENT TO DRAINAGE OUTLETS TO ASSURE PROPER TRANSITIONS BETWEEN EXISTING AND PROPOSED FACILITIES.
- 3. FINAL LAYOUT SUBJECT TO CONDITIONS ENCOUNTERED IN THE FIELD.
- Demolition
- 1. CONTRACTOR SHALL DISPOSE OF DEMOLITION DEBRIS IN ACCORDANCE WITH APPLICABLE FEDERAL, STATE AND LOCAL REGULATIONS, ORDINANCES AND STATUTES.
- 2. THE DEMOLITION LIMITS DEPICTED IN THE PLANS IS INTENDED TO AID THE CONTRACTOR DURING THE BIDDING AND CONSTRUCTION PROCESS AND IS NOT INTENDED TO DEPICT EACH AND EVERY ELEMENT OF DEMOLITION. THE CONTRACTOR IS RESPONSIBLE FOR IDENTIFYING THE DETAILED SCOPE OF DEMOLITION BEFORE SUBMITTING ITS BID/PROPOSAL TO PERFORM THE WORK AND SHALL MAKE NO CLAIMS AND SEEK NO ADDITIONAL COMPENSATION FOR CHANGED CONDITIONS OR UNFORESEEN OR LATENT SITE CONDITIONS RELATED TO ANY CONDITIONS DISCOVERED DURING EXECUTION OF THE WORK.
- 3. UNLESS OTHERWISE SPECIFICALLY PROVIDED ON THE PLANS OR IN THE SPECIFICATIONS, THE ENGINEER HAS NOT PREPARED DESIGNS FOR AND SHALL HAVE NO RESPONSIBILITY FOR THE PRESENCE, DISCOVERY, REMOVAL, ABATEMENT OR DISPOSAL OF HAZARDOUS MATERIALS, TOXIC WASTES OR POLLUTANTS AT THE PROJECT SITE. THE ENGINEER SHALL NOT BE RESPONSIBLE FOR ANY CLAIMS OF LOSS, DAMAGE, EXPENSE, DELAY, INJURY OR DEATH ARISING FROM THE PRESENCE OF HAZARDOUS MATERIAL AND CONTRACTOR SHALL INDEMNIFY AND HOLD HARMLESS THE ENGINEER FROM ANY CLAIMS MADE IN CONNECTION THEREWITH. MOREOVER, THE ENGINEER SHALL HAVE NO ADMINISTRATIVE OBLIGATIONS OF ANY TYPE WITH REGARD TO ANY CONTRACTOR AMENDMENT INVOLVING THE ISSUES OF PRESENCE, DISCOVERY, REMOVAL, ABATEMENT OR DISPOSAL OF ASBESTOS OR OTHER HAZARDOUS MATERIALS.

Erosion Control

- 1. PRIOR TO STARTING ANY OTHER WORK ON THE SITE, THE CONTRACTOR SHALL NOTIFY APPROPRIATE AGENCIES AND SHALL INSTALL EROSION CONTROL MEASURES AS SHOWN ON THE PLANS AND AS IDENTIFIED IN FEDERAL, STATE, AND LOCAL APPROVAL DOCUMENTS PERTAINING TO THIS PROJECT.
- 2. CONTRACTOR OR QUALIFIED INSPECTOR SHALL INSPECT AND MAINTAIN EROSION CONTROL MEASURES ON A WEEKLY BASIS OR MORE FREQUENTLY AS NEEDED, (MINIMUM) OR AS REQUIRED PER THE STORMWATER POLLUTION PREVENTION PLAN (SWPPP), THE CONTRACTOR SHALL ADDRESS DEFICIENCIES AND MAINTENANCE ITEMS WITHIN TWENTY-FOUR HOURS OF INSPECTION. CONTRACTOR SHALL PROPERLY DISPOSE OF SEDIMENT SUCH THAT IT DOES NOT ENCUMBER OTHER DRAINAGE STRUCTURES AND PROTECTED AREAS.
- 3. CONTRACTOR SHALL BE FULLY RESPONSIBLE TO CONTROL CONSTRUCTION SUCH THAT SEDIMENTATION SHALL NOT AFFECT REGULATORY PROTECTED AREAS, WHETHER SUCH SEDIMENTATION IS CAUSED BY WATER, WIND, OR DIRECT DEPOSIT.
- 4. CONTRACTOR SHALL PERFORM CONSTRUCTION SEQUENCING SUCH THAT EARTH MATERIALS ARE EXPOSED FOR A MINIMUM OF TIME BEFORE THEY ARE COVERED, SEEDED, OR OTHERWISE STABILIZED TO PREVENT EROSION.
- 5. UPON COMPLETION OF CONSTRUCTION AND ESTABLISHMENT OF PERMANENT GROUND COVER, CONTRACTOR SHALL REMOVE AND DISPOSE OF EROSION CONTROL MEASURES AND CLEAN SEDIMENT AND DEBRIS FROM ENTIRE DRAINAGE AND SEWER SYSTEMS.
- 6. VEGETATIVE SLOPE STABILIZATION WILL BE IMPLEMENTED WITHIN 14 DAYS AFTER GRADING OR CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED. VEGETATIVE SLOPE

STABILIZATION WILL BE USED TO MINIMIZE EROSION ON SLOPES OF 3:1 OR STEEPER. ESTABLISHMENT OF TEMPORARY AND PERMANENT VEGETATIVE COVER MAY BE ESTABLISHED BY HYDRO-SEEDING OR SODDING. A SUITABLE TOPSOIL, GOOD SEEDBED PREPARATION, AND ADEQUATE LIME, FERTILIZER AND WATER WILL BE PROVIDED FOR EFFECTIVE ESTABLISHMENT OF THESE VEGETATIVE STABILIZATION METHODS. MULCH WILL ALSO BE USED AFTER PERMANENT SEEDING TO PROTECT SOIL FROM THE IMPACT OF FALLING RAIN AND TO INCREASE THE CAPACITY OF THE SOIL TO ABSORB WATER.

Existing Conditions Information

- 1. BASE PLAN: THE PROPERTY LINES SHOWN WERE DETERMINED BY PLANS AND DEEDS OF RECORD AND MONUMENTS FOUND IN A FIELD SURVEY CONDUCTED BY NORTHWAST SURVEY CONSULTANTS . THE TOPOGRAPHY IS BASED ON A DIGITAL ELEVATION MODELS OF THE 2016 CRCOG LIDAR DATA DISTRIBUTED BY NOAA.
- 2. DATUMS: THE HORIZONTAL DATUM IS NAD83 AND VERTICAL DATUM IS NAVD88, BOTH WERE DERIVED FROM GPS OBSERVATIONS TAKEN ON SITE.

Document Use

- 1. THESE PLANS AND CORRESPONDING CADD DOCUMENTS ARE INSTRUMENTS OF PROFESSIONAL SERVICE, AND SHALL NOT BE USED, IN WHOLE OR IN PART, FOR ANY PURPOSE OTHER THAN FOR WHICH IT WAS CREATED WITHOUT THE EXPRESSED, WRITTEN CONSENT OF VHB. ANY UNAUTHORIZED USE, REUSE, MODIFICATION OR ALTERATION, INCLUDING AUTOMATED CONVERSION OF THIS DOCUMENT SHALL BE AT THE USER'S SOLE RISK WITHOUT LIABILITY OR LEGAL EXPOSURE TO VHB.
- 2. CONTRACTOR SHALL NOT RELY SOLELY ON ELECTRONIC VERSIONS OF PLANS, SPECIFICATIONS, AND DATA FILES THAT ARE OBTAINED FROM THE DESIGNERS, BUT SHALL VERIFY LOCATION OF PROJECT FEATURES IN ACCORDANCE WITH THE PAPER COPIES OF THE PLANS AND SPECIFICATIONS THAT ARE SUPPLIED AS PART OF THE CONTRACT DOCUMENTS.
- 3. SYMBOLS AND LEGENDS OF PROJECT FEATURES ARE GRAPHIC REPRESENTATIONS AND ARE NOT NECESSARILY SCALED TO THEIR ACTUAL DIMENSIONS OR LOCATIONS ON THE DRAWINGS. THE CONTRACTOR SHALL REFER TO THE DETAIL SHEET DIMENSIONS, MANUFACTURERS' LITERATURE, SHOP DRAWINGS AND FIELD MEASUREMENTS OF SUPPLIED PRODUCTS FOR LAYOUT OF THE PROJECT FEATURES.



100 Great Meadow Road Suite 200 Wethersfield, CT 06109 860.807.4300

Photovoltaic Installation

Mulnite Farms East Windsor, Connecticut


No.	Revision	Date	Appvd.
Design	JDW	Checked by	SIK
Issued	for	Date	
Ар	plication	July 2.	3, 2021


Not Approved for Construction

Legend and **General Notes**


Drawing Number























Not To Scale



 λ_{a}

- PROPOSED RIPRAP SPILLWAY

17



Photovoltaic Installation


Mulnite Farms East Windsor, Connecticut

No.	Revision	Date	Αρρνα
Designed	JDW	Checked by	SJK
Issued for	r	Date	
Anr	olication	July 2	3, 202


Not Approved for Construction

Layout and Materials Plan 1


Drawing Number




16 4







_ _ _ _ • •




PROPOSED ±500 LF GRASS-LINED SWALE 4





Photovoltaic Installation Mulnite Farms East Windsor, Connecticut

No.	Revision	Date	Appvd.
Design		Checked by	
	JDW	5	JK
Issued	for	Date	
^	I	1.1	1 1011
Ар	plication	July 2.	3, 2021
-	•		


Not Approved for Construction















029-68-010 ROCKVILLE ROAD N/F LEONARD A. MULNITE REVOCABLE TRUST AGREEMENT & DONNA L. MULNITE REVOCABLE TRUST AGREEMENT DEED 419~658 DEED 348~411 PLAN 1087



- - -

-11-

PLAN


Photovoltaic Installation

No. Rev	sion	Date	Αρρνα
Designed by	IDW	Checked by	SJK
Issued for		Date	
Appli	cation	July 2	3, 202


Not Approved for Construction


Grading and Drainage Plan 1

Drawing Number




of 16 8










PROPERTY LINE

C -

_ _ _ _ • _ _ _


PROPOSED ±500 LF GRASS-LINED SWALE 4 -----




Photovoltaic Installation Mulnite Farms East Windsor, Connecticut

No.	Revision	Date	Appvd
Designe	d by JDW	Checked by	5JK
Issued fo	or	Date	
Ap	plication	July 2	3, 2021

Not Approved for Construction






028 - 68 - 023ENT DFFD 419~658 ----RLAN 1087



100 Great Meadow Road Suite 200 Wethersfield, CT 06109



42733.00

CONSTRUCTION SEQUENCING

ALL CONSTRUCTION ACTIVITIES ARE EXPECTED TO BEGIN IN THE SPRING OF 2022 AND BE
COMPLETED BY THE END OF 2022. THE GENERAL CONSTRUCTION NOTES ARE AS FOLLOWS:
1. THE SITE CONTRACTOR SHALL BE FULLY RESPONSIBLE TO CONTROL CONSTRUCTION SUCH THAT SEDIMENTATION SHALL NOT AFFECT ROADS/HIGHWAYS AND THEIR DRAINAGE SYSTEM, NEIGHBORING PROPERTIES, WETLANDS AND REGULATORY PROTECTED AREAS, WHETHER SUCH SEDIMENTATION IS CAUSED BY WATER, WIND, OR DIRECT DEPOSIT. DESIGNATED ACCESS DRIVES MUST BE USED TO THE MAXIMUM EXTENTS POSSIBLE. IT IS REQUIRED THAT THE SITE CONTRACTOR PERFORM A DAILY INSPECTION OF ALL EROSION AND SEDIMENT CONTROL MEASURES EMPLOYED AT THE SITE.


- 2. A CTDEEP-APPROVED QUALIFIED INSPECTOR SHALL BE ASSIGNED TO BE RESPONSIBLE FOR PERFORMING INSPECTIONS AND PREPARING REPORTS IN ACCORDANCE WITH SECTION 5(B)(4)(B) OF THE CONSTRUCTION GENERAL PERMIT. THESE INSPECTIONS SHALL TAKE PLACE WEEKLY, AT A MINIMUM, AND SHALL BE REQUIRED WITHIN 24 HOURS OF A RAINFALL EVENT EXCEEDING 0.5 INCHES. THE ENGINEER OF RECORD SHALL BE REQUIRED TO REVIEW AND COUNTER-SIGN THE PREPARED WEEKLY REPORTS. IT IS ALSO ANTICIPATED THAT REPRESENTATIVES FROM CTDEEP AND/OR THE STATE CONSERVATION DISTRICT WILL PERFORM PERIODIC INSPECTIONS.
- ENGINEER OF RECORD WILL PERFORM MONTHLY PLAN IMPLEMENTATION INSPECTIONS AND PREPARE REPORTS OF THE FINDINGS. THESE INSPECTIONS SHALL LAST A MINIMUM OF THREE (3) MONTHS OR UNTIL THE COMPLETION AND STABILIZATION OF ALL EROSION CONTROL MEASURES AT THE SITE.
- 4. THROUGHOUT THE COURSE OF THE CONSTRUCTION PROJECT, ADDITIONAL SEDIMENT AND EROSION CONTROL MEASURES MAY BE WARRANTED AT THE DISCRETION OF THE QUALIFIED INSPECTOR AND/OR DESIGN ENGINEER. THESE IMPROVEMENTS MUST BE IMPLEMENTED IN A TIMELY FASHION IN ACCORDANCE WITH THE REQUIREMENTS OF THE CONSTRUCTION GENERAL PERMIT. ADDITIONALLY, AREAS OF PROPOSED COMPACTED NATIVE SOIL ROADS SHALL BE CONVERTED TO STABLE GRAVEL ROADS IF/AS DETERMINED BY THE QUALIFIED INSPECTOR OR ENGINEER OF RECORD.
- 5. PRIOR TO CONSTRUCTION, THE APPLICANT SHALL PROVIDE THE TOWN OF EAST WINDSOR WITH THE NAME OF CONTACT AND 24-HOUR CONTACT INFORMATION.
- CONTRACTOR SHALL ADHERE TO 2002 CONNECTICUT GUIDELINES FOR EROSION AND SEDIMENT CONTROL, AS AMENDED.
- 7. THE CONTRACTOR SHALL HOLD PRE-CONSTRUCTION MEETING(S). ATTENDEES SHALL INCLUDE, BUT NOT BE LIMITED TO, REPRESENTATIVES OF THE GENERAL CONTRACTOR, SITE CONTRACTOR, CTDEEP, TOWN OF EAST WINDSOR, ENGINEER OF RECORD, AND QUALIFIED SWPPP INSPECTOR.
- THE CONTRACTOR SHALL CONTACT CALL-BEFORE-YOU-DIG (1-800-922-4455) PRIOR TO ENGAGING IN ANY EXCAVATION ACTIVITIES AT THE SITE.
 THE CONTRACTOR SHALL NOTIFY THE TOWN OF EAST WINDSOR AGENT, ZONING ENEODOCEMENT OFFICED, AND ENCINEEDING DEPARTMENT AS HOUSE PRIOR TO
- ENFORCEMENT OFFICER, AND ENGINEERING DEPARTMENT, 48 HOURS PRIOR TO COMMENCEMENT OF ANY CONSTRUCTION ACTIVITY.10. NO CONSTRUCTION OF SITE IMPROVEMENTS MAY BEGIN UNTIL THE PROPER EROSION
- CONTROL MEASURES SERVING THE AREA TO BE DISTURBED ARE IN PLACE. 11. ANTICIPATED WORK HOURS WILL BE BETWEEN 6:30 AM AND 5:00 PM.


PRE-CONSTRUCTION SITE PROTECTION SEQUENCE (SPRING/SUMMER 2022) 1. ACCESS ROADS SHALL BE DESIGNATED AS EARLY AS FEASIBLE AND USED PRIMARILY FOR

- CONSTRUCTION TRAFFIC.
 INSTALL EROSION AND SEDIMENT CONTROLS FOLLOWING THE CT GUIDELINES AND MANUFACTURER'S DIRECTIONS. DURING CONSTRUCTION, THE CONTRACTOR SHALL INSTALL MEASURES AS REQUIRED BY THE ENGINEER OF RECORD OR QUALIFIED INSPECTOR, TO PREVENT
- SEDIMENT-LADEN RUNOFF FROM REACHING WETLANDS OR DISCHARGING OFFSITE.
 INSTALL STORMWATER BASINS AND SEDIMENT TRAPS IN ACCORDANCE WITH THE APPROVED SITE-SPECIFIC SWPCP AND CT GUIDELINES. THE ENGINEER OF RECORD SHALL INSPECT FEATURES TO CONFIRM REQUIRED STORAGE CAPACITIES ARE PROVIDED AND THAT OUTLETS AND/OR SPILLWAYS ARE CONSTRUCTED CORRECTLY. DISCHARGE AREAS BELOW OUTFALLS MUST BE INSPECTED TO CONFIRM FLOW WILL BE OVER STABLE GROUND AND SHEET FLOW IS ENCOURAGED. IF DISTURBED SOILS ARE PRESENT, THE ENGINEER OF RECORD TO PROVIDE
- CORRECT MEASURES TO ADDRESS CONDITION.
 SEED AND PROTECT DISTURBED SOILS AROUND SEDIMENT TRAPS AND BASINS WITHIN 14 DAYS OF COMPLETION. SECURE SEED WITH A THERMALLY-TREATED BONDED FIBER MATRIX (BFM) APPLIED FOLLOWING MANUFACTURER'S SPECIFICATIONS FOR USE AT SPECIFIED APPLICATION RATES. AN ANIONIC POLYACRYLAMIDE PRODUCT MAY BE INCLUDED WITH THE TACKIFIER TO PROMOTE SOIL STABILITY. ALL OTHER AMENDMENTS SHOULD BE PRESCRIBED BASED ON THE RESULT OF SOIL TESTS.
- PERFORM MASS EARTHWORK ON THE SITE. MASS EARTHWORK SHALL ONLY MEAN REGRADING TO MEET THE PROPOSED GRADING DEPICTED ON THE PLANS. TOPSOIL SHALL BE STRIPPED AND STOCKPILED FROM AREAS PROPOSED FOR REGRADING. EXCESS SOIL WHICH IS NOT REUSED IN PROPOSED SITE GRADING AS DEPICTED ON PLANS SHALL BE HANDLED PER THE OWNER.
 TOPSOIL SHALL BE PERLACED TO 3" MINIMUM DEPICTED ON FEAD ADDED ADDED ADDED ADDED ADDED.
- TOPSOIL SHALL BE REPLACED TO 3" MINIMUM DEPTH OVER REGRADED AREAS UPON COMPLETION OF MASS EARTHWORK ACTIVITIES AND AREAS WHICH WERE DISTURBED BY MASS EARTHWORK OPERATIONS SHALL BE RESEEDED WITHIN 14 DAYS OF COMPLETION,
 THROUGHOUT CONSTRUCTION, THE CONTRACTOR SHALL ADDRESS ONGOING EROSION PROBLEMS USING TEMPORARY DIVERSIONS AND FILLING AND GRADING GULLIES. TRACK
- GULLIES UP AND DOWN SLOPE AND HYDROSEED WITH A THERMALLY-TREATED WOOD BONDED
 FIBER MATRIX (BFM) MULCH WITH TACKIFIER. A STAPLED BIODEGRADABLE EROSION CONTROL
 BLANKET WITHOUT MONOFILAMENT MESH IS AN ACCEPTABLE ALTERNATIVE FOR HYDROSEED
 AND BFM.
 8. UPON COMPLETION OF THIS CONSTRUCTION PHASE, ALL DISTURBED AREAS SHALL BE SEEDED
- 8. UPON COMPLETION OF THIS CONSTRUCTION PHASE, ALL DISTURBED AREAS SHALL BE SEEDED WITH TACKIFIER AND CONSTRUCTION SEQUENCE MAY ONLY BEGIN IN AREAS DISPLAYING ADEQUATE VEGETATION WITHIN PROPOSED ARRAY AREA.

CONSTRUCTION SEQUENCE

- INSTALL PILES AND/OR GROUND SCREWS FOR SOLAR PANEL RACKING.
 THE INSTALLATION OF RACKING SHALL FOLLOW THE FOUNDATION INSTALLATION BY ROUGHLY ONE WEEK STARTING FROM THE SAME POINT.
- RESEED AND REGRADE ALL AREAS DISTURBED BY CONSTRUCTION TRAFFIC WITHIN THE ARRAYS WHERE RACKS ARE INSTALLED AS EARLY AS POSSIBLE. RUTS AND RILLS SHALL BE SMOOTHED
- AND GRADED AS DISCOVERED.
 4. INSTALL SOLAR PANEL MODULES IN THE RACKING. MUCH OF THIS WORK IS ANTICIPATED TO BE PERFORMED BY HAND AND LIGHT CONSTRUCTION EQUIPMENT WHICH WILL CAUSE MINIMAL
- DISTURBANCE COMPARED TO THE USE OF HEAVY EQUIPMENT. DESIGNATED ACCESS ROADS SHALL STILL BE USED TO THE MAXIMUM EXTENTS POSSIBLE. 5. UPON COMPLETION OF CONSTRUCTION, RE-SEED ALL DISTURBED AREAS WITHIN 14 DAYS AND
- PREVENT VEHICULAR TRAFFICKING OVER THESE AREAS. INSTALL FINAL LANDSCAPING.
 AFTER SITE IS STABILIZED, AND AFTER INSPECTION BY DESIGN ENGINEER, OR OTHER OWNER'S REPRESENTATIVE, REMOVE TEMPORARY EROSION AND SEDIMENT CONTROLS. ENTIRE SITE SHALL BE CHECKED FOR AND CLEANED OF SEDIMENT AS NEEDED.





July 23, 2021

Erosion and Sediment


Drawing Number C-5.1

Date


12 16

42733.00










Not To Scale




Photovoltaic Installation Mulnite Farms

East Windsor, Connecticut


No.	Revision	Date	Αρρνα
Designe	JDW	Checked by	SJK
Issued 1	for	Date	
Ap	plication	July 2	3, 202

Not Approved for Construction

Erosion and Sediment Control Plan 2





PROPERTY LINE



JZO-60-023








E-Fence Installation Details

T-Posts

18" below grade

N.T.S.

Source: Ertec Environmental Systems



Source: VHB


6/08 LD_480

E-Fence™ DETAILS – Wildlife Exclusion

Installation Notes:

- Excavate a trench a minimum of 4" wide and a minimum of 5" deep.
- T-posts shall be a minimum of 0.95 lbs/ft. T-posts shall be driven a minimum 18" deep into the ground 8' centers
- Insert barrier material into trench and attach to post in two places: 1) at 3" below top of fence and at 2) mid-height
- At 3 Inches from top of fence (above wire tie), wrap 14 gauge galvanized wire once around each T-post and pull the guide wire from post to post, wrap, secure and pull wire tight between each post.
- At segment overlaps (roll length 100 or 150 LF), overlap segments a minimum of 12". Eliminate all gaps by tying sections together with tie wire in two vertical rows, as shown.
- Push E-Fence Guide Wire Crimps through the E-Fence and crimp the ties to the guide wire on the other side of the fence (two crimps per tie) at 3' intervals, as illustrated in Detail A of the installation guidelines. Crimp to the guide-wire securely.
- E-Fence must be installed in continuous lengths (100 or 150 feet rolls). Do not cut segments into shorter lengths unless necessary due to sudden changes in elevation.
- Backfill trench with trench spoils. Backfill from E-Fence side of posts first so that E-Fence is pushed up against T-posts. Back fill other side to complete backfill.

N.T.S.





Suite 200 Wethersfield, CT 06109 860.807.4300


Photovoltaic Installation

Mulnite Farms East Windsor, Connecticut

·		
No. Revision	Date	Αρρνα
Designed by	Checked by	
JDW		5JK
lssued for	Date	
Application	July 2	3, 202
	,	-

Not Approved for Construction







Project Number 42733.00

Source: VHB

LD_482






NOTE: 1. ALL SIDE SLOPES SHALL NOT EXCEED 3:1 2. REFER TO "DIVERSION SWALE SIZING" TABLE FOR SELECTION OF LINING MATERIAL TO BE INSTALLED OVER ENTIRE SWALE AREA. 3. REFER TO "DIVERSION SWALE SIZING" TABLE FOR VARIABLE SIZING. 4.THE INTENT IS TO USE THE MATERIAL EXCAVATED FROM THE SWALE TO CONSTRUCT THE RIDGE.


Source: VHB

Straw Wattle Installation N.T.S. Source: VHB


8/12 LD_658

Diversion Swale N.T.S.





1/16 LD_650 N.T.S.




Source: VHB

SIDE SLOPES OF EMBANAMENT SHALL BE STABILIZED BY TEMPORART SEEDING OR EROSION CON BLANKETS AS DIRECTED BY THE ENGINEER.
 REFER TO "PERMANENT STORMWATER BASIN SIZING" TABLE FOR VARIABLE SIZING.
 PERIMETER SILT FENCE SHALL BE REMOVED IMMEDIATELY DOWNSTREAM FROM SPILLWAY AND REPLACED WITH E-FENCE.

Permanent Stormwater Basin N.T.S. Source: VHB

N.T.S.



1.	CRUSHED STONE SHALL BE IN ACCORDANCE WITH THE
	CURRENT VERSION OF THE CONNECTICUT DEPARTMENT
	OF TRANSPORTATION SPECIFICATIONS FOR ROADS,
	BRIDGES, AND INCIDENTAL CONSTRUCTION.

Perimeter Access Cross Section N.T.S.

	PERMANENT STORMWATER BASIN SIZING							
NUMBER	BASIN TYPE	LENGTH AT BASIN BOTTOM (TOE OF SLOPE), FT	WIDTH AT BASIN BOTTOM (TOE DF SLOPE), FT	SIDE SLOPES	BOTTOM ELEVATION, FT	ELEVATION OF BOTTOM/CREST OF SPILLWAY, FT	SPILLWAY WIDTH AT BASE, FT	MINIMUM TOP OF BERM ELEVATION, FT
1	INFILTRATION	15	170	3:1	193.0	197.0	20	197.6
2	INFILTRATION	15	35	3:1	209.0	212.0	8	213.5
3	INFILTRATION	15	45	3:1	207.0	211.0	12	211.8
4	INFILTRATION	70	320	3:1	213.5	218.0	16	219.0

DI∨ERSI⊡N SWALE SIZING						
NAME	APPROXIMATE TRIBUTARY AREA, AC	APROXIMATE LENGTH, FT	BOTTOM WIDTH, FT	SIDE SLOPES	SWALE DEPTH, FT	LININ(MATERI
SWALE 1	0.0	100	1	3:1	1	ECB
SWALE 2	0.5	130	1	3:1	1	ECB
SWALE 3	0.7	150	1	3:1	1	ECB
SWALE 4	8.5	490	3.5	3:1	1.5	ECB

REFER TO SIZING TABLE TOP OF SPILLWA BOTTOM/CREST OF SPILLWAY -Spillway Cross Section

NOTE. 1. ALL SIDE SLOPES SHALL NOT EXCEED 2:1 2. TOP OF EMBANKMENT SHALL BE 2' (MIN.) WIDTH AND 1' (MIN.) ABOVE TOP OF SPILLWAY. 3. SIDE SLOPES OF EMBANKMENT SHALL BE STABILIZED BY TEMPORARY SEEDING OR EROSION CONTROL BLANKETS AS DIRECTED BY THE ENGINEER. 4, REFER TO "PERMANENT STORMWATER BASIN SIZING" TABLE FOR VARIABLE SIZING. 5. PERIMETER SILT FENCE SHALL BE REMOVED IMMEDIATELY DOWNSTREAM FROM SPILLWAY.

Stormwater Basin Spillway N.T.S. Source: VHB

NOTE

Sizing Tables for Temporary & Permanent Stormwater Features N.T.S.

2

Source: VHB



100 Great Meadow Road Suite 200 Wethersfield, CT 06109 860.807.4300

Photovoltaic Installation


Mulnite Farms East Windsor, Connecticut

·		
No. Revision	Date	Арри
Designed by	Checked by	/
JDW		SJK
Issued for	Date	
Application	July 2	3, 202

Not Approved for Construction

Site Details 2

Drawing Number



16 16

