

Exhibit E

Project Site, Interconnection Existing Conditions, Proposed Conditions, and Surrounding Features Maps



PROPOSED SOLAR PHOTOVOLTAIC ARRAY

428 BETHMOUR ROAD BETHANY, CONNECTICUT



LOCATION MAP

PREPARED FOR:



888 PROSPECT STREET, SUITE 200 LA JOLLA, CALIFORNIA

PREPARED BY:



501 MAIN STREET, MONROE, CONNECTICUT 06468 11 VANDERBILT AVENUE, NORWOOD, MASSACHUSETTS 02062

THE NEVAR COMPANY CHESHIRE, CONNECTICUT 06410

APPLICANT

TRITEC AMERICAS, LLC 888 PROSPECT STREET, SUITE 200 LA JOLLA, CALIFORNIA 92307

PROPERTY INFORMATION

ADDRESS: 428 BETHMOUR ROAD MAP-BLOCK-LOT: 113-1 & 113-1-A ZONE: R-65 AREA: ±21.22 AC BOOK/PAGE: 0215/0543

SOIL SCIENTIST

WILLIAM KENNY WILLIAM KENNY ASSOCIATES 195 TUNXIS HILL CUTOFF SOUTH FAIRFIELD, CT 06825 (203) 366-0588

ELECTRICAL ENGINEER

PURE POWER ENGINEERING, INC. 111 RIVER STREET, SUITE 1110 HOBOKEN, NJ 07030 (201) 687-9975



SITE / CIVIL ENGINEER

KEVIN SOLLI, P.E., CPESC, LEED AP BD+C LICENSE NO. 25759 SOLLI ENGINEERING, LLC 501 MAIN STREET MONROE, CONNECTICUT 06468 (203) 880-5455

LANDSCAPE ARCHITECT

MARY BLACKBURN, P.L.A., LICENSE CT NO. 1499 SOLLI ENGINEERING, LLC 501 MAIN STREET MONROE, CONNECTICUT 06468 (203) 880-5455

SURVEYOR OF RECORD

PATRICK J CORLESS, JR. LICENSE NO. 70015 **BL COMPANIES** 355 RESEARCH PARKWAY MERIDEN, CONNECTICUT 06450 (203) 630-1406

D ov. #.	Data	Description	

PROPOSED SOLAR PHOTOVOLTAIC ARRAY

428 BETHMOUR ROAD BETHANY, CONNECTICUT

Sheet #:


Sheet Title:

COVER SHEET

0.00

DRAWING LIST

SHEET #	SHEET NAME	PLAN DATE	LATEST REVISION
0.00	COVER SHEET	04/18/23	N/A
EX-1	EXISTING CONDITIONS MAP	01/05/22	N/A
2.11	SITE LAYOUT PLAN	04/18/23	N/A
2.21	GRADING AND DRAINAGE PLAN	04/18/23	N/A
2.31	SOIL EROSION & SEDIMENT CONTROL PLAN	04/18/23	N/A
2.41	SOIL EROSION & SEDIMENT CONTROL NOTES & DETAILS	04/18/23	N/A
3.01	CONSTRUCTION DETAILS	04/18/23	N/A



355 Research Parkway Meriden, CT 06450 (203) 630-1406

(203) 630-2615 Fax


Surveyed Drawn Reviewed Project No 2101190


01/05/2022 Field Book CAD File: EX210119001

1"=80'

EXISTING CONDITIONS MAP

Sheet No.





DEMOLITION NOTES

- 1. CONTRACTOR SHALL SECURE ANY PERMITS, PAY ALL FEES AND PERFORM CLEARING AND GRUBBING AND DEBRIS REMOVAL PRIOR TO COMMENCEMENT OF GRADING OPERATIONS. 2. ALL BUILDINGS, INCLUDING FOUNDATIONS WALLS, FOOTINGS AND BASEMENT SLABS INDICATED ON PLAN ARE TO BE REMOVED FROM THE SITE.
- 3. ALL SEDIMENT AND EROSION CONTROLS AS SHOWN ON THE PLAN HEREON SHALL BE INSTALLED BY THE DEMOLITION CONTRACTOR PRIOR TO START 4. REMOVE AND DISPOSE OF ANY CONCRETE, FENCES, STAIRS, WALLS, DEBRIS AND RUBBISH REQUIRING REMOVAL FROM THE WORK AREA IN AN
- APPROVED OFF SITE LANDFILL, BY AN APPROVED HAULER. THE HAULER SHALL COMPLY WITH ALL LOCAL, STATE AND FEDERAL REGULATORY 5. THE CONTRACTOR SHALL PROTECT ALL IRON PINS. MONUMENTS AND PROPERTY CORNERS DURING DEMOLITION ACTIVITIES. ANY CONTRACTOR DISTURBED PINS, MONUMENTS, AND OR PROPERTY CORNERS, ETC. SHALL BE RESET BY A LICENSED LAND SURVEYOR AT THE EXPENSE OF THE
- 6. THE DEMOLITION CONTRACTOR SHALL STABILIZE THE SITE AND KEEP EROSION CONTROL MEASURES IN PLACE UNTIL THE COMPLETION OF HIS WORK OR UNTIL THE COMMENCEMENT OF WORK BY THE SITE CONTRACTOR, WHICHEVER OCCURS FIRST, AS REQUIRED OR DEEMED NECESSARY BY THE
- ENGINEER OF RECORD. THE SITE CONTRACTOR SHALL ASSUME RESPONSIBILITY FOR THE MAINTENANCE OF EXISTING EROSION AND SEDIMENTATION CONTROLS AND FOR INSTALLATION OF ANY NEW EROSION AND SEDIMENT CONTROLS AS SHOWN HEREON.
- 7. THE CONTRACTOR SHALL ADHERE TO ALL OSHA, FEDERAL, STATE AND LOCAL REGULATIONS WHEN OPERATING CRANES, BOOMS, HOISTS, ETC. IN PROXIMITY OF OVERHEAD ELECTRIC LINES, IF CONTRACTOR MUST OPERATE EQUIPMENT CLOSE TO ELECTRIC LINES CONTACT THE POWER COMPANY TO MAKE ARRANGEMENTS FOR PROPER SAFEGUARDS. ANY UTILITY PROVIDER FEES SHALL BE PAID BY THE CONTRACTOR.
- 8. PRIOR TO DEMOLITION OR CONSTRUCTION, THE CONTRACTOR SHALL CONTACT "CALL BEFORE YOU DIG" 72 HOURS BEFORE THE COMMENCEMENT OF WORK AT "811" AND VERIFY ALL UTILITY AND STORM DRAINAGE SYSTEM LOCATIONS. INFORMATION ON EXISTING UTILITIES AND STORM DRAINAGE SYSTEMS HAS BEEN COMPILED FROM AVAILABLE INFORMATION INCLUDING UTILITY PROVIDER AND MUNICIPAL RECORD MAPS AND/OR FIELD SURVEY AND IS NOT GUARANTEED CORRECT OR COMPLETE. UTILITIES AND STORM DRAINAGE SYSTEMS ARE SHOWN TO ALERT THE CONTRACTOR TO THEIR PRESENCE AND THE CONTRACTOR IS SOLELY RESPONSIBLE FOR DETERMINING ACTUAL LOCATIONS AND ELEVATIONS OF ALL UTILITIES AND STORM DRAINAGE SYSTEMS INCLUDING SERVICES.
- 9. CONTRACTOR SHALL BE RESPONSIBLE FOR SITE SAFETY AND SECURITY OF THE SITE DURING ALL PHASES OF CONSTRUCTION. THE ENGINEER OF RECORD IS NOT RESPONSIBLE FOR SITE SAFETY MEASURES TO BE EMPLOYED DURING CONSTRUCTION. THE ENGINEER OF RECORD HAS NO CONTRACTUAL DUTY TO CONTROL THE SAFEST METHODS OR MEANS OF THE WORK, JOB SITE RESPONSIBILITIES, SUPERVISION OR TO SUPERVISE SAFETY AND DOES NOT VOLUNTARILY ASSUME ANY SUCH DUTY OR RESPONSIBILITY.
- 10. SHOULD ANY UNCHARTED OR INCORRECTLY CHARTED, EXISTING PIPING OR OTHER UTILITY BE UNCOVERED DURING EXCAVATION, CONSULT THE ENGINEER OF RECORD IMMEDIATELY FOR DIRECTIONS BEFORE PROCEEDING FURTHER WITH WORK IN THIS AREA.
- 11. NO WORK ON THIS SITE SHALL BE INITIATED BY THE CONTRACTOR UNTIL A PRE-CONSTRUCTION MEETING WITH OWNER AND THE ENGINEER OF RECORD IS PERFORMED. THE CONTRACTOR SHALL HAVE MARK OUTS OF EXISTING UTILITIES COMPLETED PRIOR TO MEETING. 12. CONTRACTOR SHALL BACKFILL ALL AREAS WHERE BUILDING SLABS AND FOUNDATIONS HAVE BEEN REMOVED.

SEDIMENT & EROSION CONTROL NOTES

APPROVAL OF THE FINAL PLANS IS GRANTED BY ALL GOVERNING AND REGULATORY AGENCIES.

- 1. THESE PLANS ARE FOR PERMITTING PURPOSES ONLY AND ARE NOT FOR CONSTRUCTION. NO CONSTRUCTION OR DEMOLITION SHALL BEGIN UNTIL
- 2. ALL SITE WORK TO BE COMPLETED IN ACCORDANCE WITH ALL PERMITS, APPROVALS AND CONDITIONS OF APPROVALS ISSUED BY THE TOWN OF BETHANY FOR THIS PROJECT
- 3. EXISTING SITE CONDITIONS AND BOUNDARY INFORMATION TAKEN FROM A PLAN TITLED "EXISTING CONDITIONS MAP, 428 BETHMOUR ROAD, BETHANY, CONNECTICUT, EX-1." DATED JANUARY 05, 2022, SCALE: 1"=80', BY BL COMPANIES.
- 4. REFER TO THE EXISTING CONDITIONS MAP FOR THE ENTIRE PROPERTY BOUNDARY AND EXISTING CONDITIONS INFORMATION, THE PLAN HEREON DEPICTS A PORTION OF THE PROPERTY IN WHICH THE SITE WORK IS BEING PROPOSED.
- 5. PRIOR TO STARTING ANY OTHER WORK ON SITE, THE CONTRACTOR SHALL NOTIFY APPROPRIATE AGENCIES AND SHALL INSTALL EROSION CONTROL MEASURES AS SHOWN ON THE PLANS AND AS IDENTIFIED, STATE, AND LOCAL APPROVAL DOCUMENTS PERTAINING TO THIS PROJECT. EROSION CONTROLS TO BE INSTALLED AT THE EDGE OF PROPOSED WORK. 6. EROSION CONTROLS TO ACT AS A LIMIT OF WORK LINE TO ENSURE THAT NO EQUIPMENT ENCROACHES ON THE ADJACENT PROPERTIES AND AREAS
- INTENDED TO REMAIN UNDISTURBED 7. EROSION CONTROLS SHALL REMAIN IN PLACE AND BE MAINTAINED FOR THE DURATION OF THE PROJECT TO LIMIT THE MOVEMENT OF SILTATION AND SEDIMENTS FROM ENTERING EXISTING DRAINAGE SYSTEMS OR FROM LEAVING THE SITE. ANY ACCUMULATED SEDIMENTS ARE TO BE REMOVED FROM THE EROSION CONTROLS AND DISPOSED TO PROPERLY. ADDITIONALLY, ALL EROSION CONTROLS ARE TO BE INSPECTED AFTER A STORM EVENT
- AND THE CONTROLS REPLACED OR ARMORED AS NECESSARY AND ACCUMULATED SEDIMENTS REMOVED. 8. ADDITIONAL EROSION CONTROLS ARE TO BE UTILIZED AS NECESSARY AND AS DIRECTED BY THE ENGINEER OF RECORD TO LIMIT SEDIMENTS FROM
- DISCHARGING TO ADJACENT PROPERTIES, RESOURCE AREAS, OR INTO EXISTING STORM DRAIN SYSTEMS. 9. CONTRACTOR SHALL BE RESPONISBLE TO CONTROL CONSTRUCTION SUCH THAT EROSION SHALL NOT AFFECT OFF-SITE AREAS, WHETHER SUCH EROSION IS CAUSED BY WATER, WIND, OR DIRECT DEPOSIT.
- 11. CONTRACTOR SHALL PERFORM CONSTRUCTION SEQUENCING SUCH THAT EARTH MATERIALS ARE EXPOSED FOR A MINIMUM OF THE TIME BEFORE THEY ARE COVERED, SEEDED, OR OTHERWISE STABILIZED TO PREVENT EROSION.

10. A RESERVE AMOUNT OF EROSION CONTROL MATERIALS ARE TO BE KEPT WITHIN EASY ACCESS ON SITE AT ALL TIMES.

- 12. TEMPORARY STOCKPILING OF MATERIALS RELATED TO THE CONSTRUCTION ACTIVITIES ARE TO BE PROPERLY STABILIZED, PROTECTED AND DEMARCATED TO LIMIT MOVEMENT OF MATERIAL INTO STORM DRAIN SYSTEM, RESOURCE AREAS, OR ONTO ADJACENT PARCELS 13. REFUELING AND ANY WORK ASSOCIATED WITH THE MAINTENANCE OF CONSTRUCTION EQUIPMENT TO BE PERFORMED IN COMPLIANCE WITH
- APPLICABLE REGULATIONS. 14. THE AREAS OF CONSTRUCTION SHALL REMAIN IN A STABLE CONDITION AT THE CLOSE OF EACH CONSTRUCTION DAY. EROSION CONTROLS SHALL BE CHECKED AT THIS TIME AND MAINTAINED OR REINFORCED IF NECESSARY. 15. EROSION CONTROLS SHALL REMAIN IN PLACE UNTIL ALL DISTURBED AREAS HAVE BEEN STABILIZED WITH PAVEMENT, PLANTINGS, OR WITH AN
- REMOVE AND DISPOSE OF EROSION CONTROL MEASURES AND CLEAN SEDIMENT AND DEBRIS FROM ENTIRE DRAINAGE AND SEWER SYSTEMS AS DIRECTED BY THE ENGINEER OF RECORD. 16. UTILIZE APPROPRIATE DEWATERING SYSTEMS AND TECHNIQUES TO MAINTAIN THE EXCAVATED AREA SUFFICIENTLY DRY FROM GROUNDWATER AND/OR SURFACE RUNOFF SO AS TO NOT ADVERSELY AFFECT CONSTRUCTION PROCEDURES OR CAUSE EXCESSIVE DISTURBANCE OF UNDERLYING

ESTABLISHED STAND OF GRASS, EROSION CONTROLS SHALL NOT BE REMOVED UNTIL SITE STABILIZATION IS COMPLETE. CONTRACTOR SHALL

- 17. WATER FROM TRENCHES AND EXCAVATIONS SHALL NOT BE DISCHARGED DIRECTLY TO STORM DRAIN SYSTEMS. PROPER TREATMENT TO A SEDIMENTATION AREA IS TO TAKE PLACE PRIOR TO DISCHARGE TO ANY DRAINAGE SYSTEMS.
- 18. THE CONTRACTOR SHALL REPAIR ANY DAMAGE RESULTING FROM THE FAILURE OF THE DEWATERING OPERATIONS OR FROM FAILURE TO MAINTAIN ALL THE AREAS OF WORK IN SUITABLE DRY CONDITION. 19. PRECAUTIONS SHALL BE TAKEN TO PROTECT NEW WORK FROM FLOODING DURING STORMS OR FROM OTHER CAUSES. GRADING IN THE AREAS SURROUNDING ALL EXCAVATIONS SHALL BE PROPERLY SLOPED TO PREVENT WATER FROM RUNNING INTO THE EXCAVATED AREA OR TO ADJACENT PROPERTIES. WHERE REQUIRED, TEMPORARY DITCHES SHALL BE PROVIDED FOR DRAINAGE. UPON COMPLETION OF THE WORK AND WHEN DIRECTED, ALL AREAS SHALL BE RESTORED IN A SATISFACTORY MANNER AND AS DIRECTED.
- 20. REFER TO SHEET 2.41 FOR DETAILS OF THE PROPOSED SOIL EROSION AND SEDIMENT CONTROL (SEC) MEASURES AND ADDITIONAL INFORMATION REGARDING CONSTRUCTION SEQUENCE, SEC MEASURE INSTALLATION, AND MAINTENANCE.

LEGEND

ADJOINING LOT LINE SILT FENCE PROTECTION CONSTRUCTION FENCE - * - * - * - * - * -CURB REMOVAL XXXXXXXXXXXXXXXXXXXXXXXXXX FENCE / ROCK WALL REMOVAL

PROPERTY LINE

RIGHT-OF-WAY LINE

BUILDING / STRUCTURE DEMOLITION

BITUMINOUS CONCRETE PAVEMENT DEMOLITION TEMPORARY SEDIMENT TRAP / BASIN

SILT SACK INLET PROTECTION

STONE CHECK DAM

MATERIAL STOCKPILE AREA

CONSTRUCTION ENTRANCE CONCRETE WASHPIT

1.1. INSTALL STABILIZED CONSTRUCTION ENTRANCE / EXIT. 1.2. INSTALL SILT FENCE / SEC MEASURES AS PROPOSED (CLEAR ONLY THOSE

CONSTRUCTION SEQUENCE (PHASE I)

- AREAS NECESSARY TO INSTALL SEC MEASURES). PREPARE TEMPORARY PARKING AND STORAGE AREAS. 1.4. HALT ALL ACTIVITIES AND CONTACT THE ENGINEER OF RECORD / TOWN OF BETHANY LAND USE AGENT TO PERFORM INSPECTION AND CERTIFICATION OF BEST MANAGEMENT PRACTICES (BMP'S). GENERAL CONTRACTOR SHALL SCHEDULE AND CONDUCT THE STORM WATER PRE-CONSTRUCTION MEETING WITH THE ENGINEER, CITY AGENCIES AND GROUND-DISTURBING
- 1.5. PERFORM PAVEMENT SAWCUTS. 1.6. DEMOLISH AND REMOVE EXISTING STRUCTURES / FOUNDATIONS.

CONTRACTOR BEFORE PROCEED WITH CONSTRUCTION.

- REMOVE ALL EXISTING CURBING, BITUMINOUS CONCRETE PAVEMENT, CONCRETE PADS AND FENCING. 1.8. BEGIN CLEARING AND GRUBBING THE SITE.
- 1.9. ESTABLISH MATERIAL STOCKPILE AREA AND INSTALL SEC BARRIER SURROUNDING PILE.
- 1.10. BEGIN ROUGH GRADING OF THE SITE.

CONSTRUCTION SEQUENCE (PHASE II)

- 1.1. TEMPORARILY SEED, THROUGHOUT CONSTRUCTION, DENUDED AREAS THAT WILL BE INACTIVE FOR 14 DAYS OR MORE.
- INSTALL PROPOSED STORM DRAINAGE SYSTEM AND STRUCTURES (SEE SHEET
- 1.3. START CONSTRUCTION OF BUILDING PAD, PARKING AREAS, AND STRUCTURES. 1.4. PERMANENTLY STABILIZE AREAS TO BE VEGETATED AS THEY ARE BROUGHT
- ΓO FINAL GRADE.
- 1.5. PREPARE SITE FOR FINAL GRADING. 1.6. CONSTRUCT CONCRETE PADS.
- INSTALL APPROPRIATE INLET PROTECTIONS PRIOR TO PAVING. 1.8. CONTRACTOR / CONSTRUCTION MANAGER TO COORDINATE WITH ENGINEER
- OF RECORD TO OBTAIN STABILIZED SITE STATUS.
- CONTINUE DAILY INSPECTION REPORTS UNTIL THE FINAL DAILY INSPECTION REPORT IS SIGNED BY THE CONSTRUCTION MANAGER AND SUBMITTED.

501 Main Street, Monroe, CT 06468 T: (203) 880-5455 F: (203) 880-9695 11 Vanderbilt Ave, Norwood, MA 02062 T: (781) 352-8491 F: (203) 880-9695 Orawn By: Checked By:

Description

Approved By: KMS 22113201 roject #: 04/18/23 Plan Date: 1'' = 80'

raphic Scale:

PROPOSED SOLAR PHOTOVOLTAIC ARRAY

428 BETHMOUR ROAD BETHANY, CONNECTICUT

SOIL EROSION &

CONTROL PLAN

GRADATION TABLE ASTM C-33 CONN. DOT 2" CRUSHED NO. 2 NO. 3 GRAVEL SQUARE MESH SIEVES % FINER % FINER 90-100 95-100 35-70 35-70 0-15 35-70 0-25

REGULAR FLOW = 40 GAL./MIN./SF

GENERAL RULE FOR

THE ELEVATION OF THE

BOTTOM OF THE UPSTREAM

BERM SHOULD BE EQUAL TO

THE ELEVATION OF THE TOP

2 ACRES OR LESS OF DRAINAGE AREA

(DOWNSTREAM VIEW)

OF THE SUCCEEDING

DOWNSTREAM BERM.

SPACING:

SILT SACK DETAIL

SCALE: NTS

TOP OF BANK

2-10 ACRES OF DRAINAGE AREA

ELEVATION B

CHECK DAMS IN SWALE

FABRIC

2"-3" CLEAN

STONE

(ENGINEER

TO SPECIFY)

NOTE: SEE SITE MAP FOR LOCATION OF CHECK DAM(S). FLOW LINE

TOP OF BANK

HIGH FLOW = 200 GAL./MIN./SF

U.S. DEPARTMENT OF AGRICULTURE, SOIL CONSERVATION SERVICE. STORRS, CONNECTICUT

CONSTRUCTION ENTRANCE

SCALE: NTS

VIEW LOOKING UPSTREAM

SPACING BETWEEN CHECK DAMS

✓ VARIES

SECTION A-A

FLANKING THE DAM.

HOUR PEAK FLOW.

1. KEY STONE INTO THE DITCH BANKS AND EXTEND INTO THE ABUTMENTS A MINIMUM OF 18" TO PREVENT FLOW FROM

2. THE MINIMUM DESIGN CAPACITY SHALL CONVEY A 2 YEAR-24

L = THE DISTANCE SUCH THAT POINTS

POINT B

FABRIC

(ENGINEER

TO SPECIFY)

2"-3" CLEAN

STONE CHECK DAM DETAIL

SCALE: NTS

STONE

— CT. DOT NO.3 STONE (CRUSHED)

— GEOTEXTILE IF

NECESSARY

A AND B ARE OF EQUAL ELEVATION

2 1/2 INCHES

1 1/2 INCHES

1 1/4 INCHES

3/4 INCHES

1/2 INCHES


3/8 INCHES

GEOTEXTILE I


NECESSARY

1 INCHES

2 INCHES




SCALE: NTS




MATERIALS STOCKPILE DETAIL

SCALE: NTS



CONCRETE WASHOUT PIT

SCALE: NTS



SOIL EROSION & SEDIMENT CONTROL NOTES

SEDIMENT & EROSION CONTROL NARRATIVE

- STRAW WATTLE

THE SEDIMENT AND EROSION CONTROL PLAN WAS DEVELOPED TO PROTECT THE EXISTING ROADWAY AND STORM DRAINAGE SYSTEMS, ADJACENT PROPERTIES, AND ANY ADJACENT WETLAND AREA AND WATER COURSE FROM SEDIMENT LADEN SURFACE RUNOFF AND EROSION.

THE ANTICIPATED STARTING DATE FOR CONSTRUCTION IS SUMMER 2023 WITH COMPLETION ANTICIPATED BY SPRING 2024. APPROPRIATE EROSION CONTROL MEASURES AS DESCRIBED HEREIN, SHALL BE INSTALLED BY THE CONTRACTOR PRIOR TO THE COMMENCEMENT OF ALL SITE CLEARING OR CONSTRUCTION ACTIVITY. SCHEDULE WORK TO MINIMIZE THE LENGTH OF

TIME THAT BARE SOIL WILL BE EXPOSED. CONTINGENCY EROSION PLAN THE CONTRACTOR SHALL INSTALL ALL SPECIFIED EROSION CONTROL MEASURES AND WILL BE REQUIRED TO MAINTAIN THEM IN THEIR INTENDED

FUNCTIONING CONDITION. THE LAND USE AGENTS OF THE TOWN OF

BETHANY AND ENGINEER OF RECORD SHALL HAVE THE AUTHORITY TO REQUIRE SUPPLEMENTAL MAINTENANCE OR ADDITIONAL MEASURES IF

FIELD CONDITIONS ARE ENCOUNTERED BEYOND WHAT WOULD NORMALLY

BE ANTICIPATED.

CLEARING, GRUBBING & DEMOLITION OPERATIONS: 1. ALL SEDIMENTATION AND EROSION CONTROL MEASURES WILL BE INSTALLED PRIOR TO THE START OF CLEARING, GRUBBING AND

DEMOLITION OPERATIONS. 2. FOLLOWING INSTALLATION OF ALL SEDIMENTATION AND EROSION CONTROL MEASURES, THE CONTRACTOR SHALL NOT PROCEED WITH GRADING, FILLING OR OTHER CONSTRUCTION OPERATIONS UNTIL THE ENGINEER OF RECORD HAS INSPECTED AND APPROVED ALL

INSTALLATIONS. 3. THE CONTRACTOR SHALL TAKE EXTREME CARE DURING CLEARING, GRUBBING AND DEMOLITION OPERATIONS SO AS NOT TO DISTURB SEDIMENTATION AND EROSION CONTROL DEVICES AS WELL AS EXISTING LANDSCAPED AREAS.

4. FOLLOWING THE COMPLETION OF CLEARING, GRUBBING AND DEMOLITION OPERATIONS, ALL AREAS SHALL BE STABILIZED WITH TOPSOIL AND SEEDING, PROCESSED AGGREGATE STONE OR DISPERSED HAY AS SOON AS PRACTICAL.

ROUGH GRADING OPERATIONS:

1. DURING THE REMOVAL AND/OR PLACEMENT OF EARTH AS INDICATED ON THE GRADING PLAN, TOPSOIL SHALL BE STRIPPED AND APPROPRIATELY STOCKPILED FOR REUSE.

2. ALL STOCKPILED TOPSOIL SHALL BE SEEDED, MULCHED WITH HAY, AND ENCLOSED BY A SILTATION FENCE OR COMPOSITE FILTER SOCK.

1. PRIOR TO FILLING, ALL SEDIMENTATION AND EROSION CONTROL DEVICES SHALL BE PROPERLY IMPLEMENTED, MAINTAINED AND FULLY INSTALLED, AS DIRECTED BY THE ENGINEER AND AS SHOWN ON THIS

2. ALL FILL MATERIAL ADJACENT TO ANY WETLAND AREAS, IF APPLICABLE TO THIS PROJECT, SHALL BE GOOD QUALITY, WITH LESS THAN 5% FINES PASSING THROUGH A #200 SIEVE (BANK RUN), SHALL BE PLACED IN LIFT THICKNESS NOT GREATER THAN THAT SPECIFIED IN PROJECT SPECIFICATIONS. LIFTS SHALL BE COMPACTED TO 95% MAX. DRY DENSITY MODIFIED PROCTOR OR AS SPECIFIED IN THE CONTRACT SPECIFICATIONS OR IN THE GEOTECHNICAL REPORT

AS GENERAL GRADING OPERATIONS PROGRESS. ANY TEMPORARY DIVERSION DITCHES SHALL BE RAISED OR LOWERED, AS NECESSARY, TO DIVERT SURFACE RUNOFF TO THE SEDIMENT TRAPS AND BASIN (IF APPLICABLE).

PLACEMENT OF DRAINAGE STRUCTURES, UTILITIES, AND ROADWAY V. CHECK DAM CONSTRUCTION OPERATIONS

1. SILT FENCES SHALL BE INSTALLED AT THE DOWNHILL SIDES OF TEMPORARY TRAPS, MUD PUMP DISCHARGES, AND UTILITY TRENCH MATERIAL STOCKPILES. HAY BALES MAY BE USED IF SHOWN ON THE EROSION CONTROL PLANS OR IF DIRECTED BY THE ENGINEER OF RECORD.

FINAL GRADING AND PAVING OPERATIONS:

SCALE: NTS

1. ALL INLET AND OUTLET PROTECTION SHALL BE PLACED AND MAINTAINED AS SHOWN ON EROSION CONTROL PLANS AND DETAILS, AND AS DESCRIBED IN SPECIFICATIONS AND AS DESCRIBED HEREIN.

2. NO CUT OR FILL SLOPES SHALL EXCEED 2:1 EXCEPT WHERE STABILIZED BY ROCK FACED EMBANKMENTS OR EROSION CONTROL BLANKETS, JUTE MESH AND VEGETATION. ALL SLOPES SHALL BE SEEDED, AND ANY ROAD OR DRIVEWAY SHOULDER AND BANKS SHALL BE STABILIZED IMMEDIATELY UPON COMPLETION OF FINAL GRADING UNTIL TURF IS ESTABLISHED

PAVEMENT SUB-BASE AND BASE COURSES SHALL BE INSTALLED OVER AREAS TO BE PAVED AS SOON AS FINAL SUB-GRADES ARE ESTABLISHED AND UNDERGROUND UTILITIES AND STORM DRAINAGE SYSTEMS HAVE

BEEN INSTALLED. AFTER CONSTRUCTION OF PAVEMENT, TOPSOIL, FINAL SEEDING, MULCH AND LANDSCAPING, REMOVE ALL TEMPORARY EROSION CONTROL DEVICES ONLY AFTER ALL AREAS HAVE BEEN PAVED AND/OR GRASS HAS BEEN WELL ESTABLISHED AND THE SITE HAS BEEN INSPECTED AND

APPROVED BY THE TOWN OF BETHANY LAND USE AGENT AND/OR

INSTALLATION OF SEDIMENTATION AND EROSION CONTROL MEASURES

ENGINEER OF RECORD.

A. DIG A SIX INCH TRENCH ON THE UPHILL SIDE OF THE DESIGNATED FENCE LINE LOCATION.

- POSITION THE POST AT THE BACK OF THE TRENCH (DOWNHILL III. COMPOSITE FILTER SOCK: SIDE), AND HAMMER THE POST AT LEAST 1.5 FEET INTO THE
- C. LAY THE BOTTOM SIX INCHES OF THE FABRIC INTO THE TRENCH TO PREVENT UNDERMINING BY STORM WATER RUN-OFF. BACKFILL THE TRENCH AND COMPACT.

II. SILT SACK INLET PROTECTION:

A. REMOVE CATCH BASIN GRATE AND PROPERLY PLACE THE SILT SACK INTO THE FRAME OF THE CATCH BASIN.

PLACE GRATE BACK ONTO FRAME AND ENSURE NO PORTIONS OF THE SILT SACK HAVE SAGGED INTO THE CATCH BASIN

ONCE GRATE IS PLACED BACK ONTO FRAME OBSERVE TO SEE IF SILT SACK IS INSTALLED IN A MANNER THAT WILL ALLOW FOR SEDIMENT TO BE FILTERED OUT DURING STORM EVENTS.

III. COMPOSITE FILTER SOCK:

COMPOSITE FILTER SOCK TO BE PLACE IN ACCORDANCE WITH SHEET 2.31. ALL DAMAGED SOCKS AND POSTS SHALL BE REPLACED AND PROPERLY REPOSITIONED AS NECESSARY. COMPOSITE FILTER SOCK TO BE SECURED BY EITHER SAND BAG

GROUND (PERVIOUS AREAS). SEDIMENT DEPOSITS SHALL BE REMOVED FROM BEHIND THE FENCE WHEN THEY EXCEED 3-4 INCHES IN HEIGHT.

(IMPERVIOUS AREAS) OR BY WOOD STAKE HAMMERED INTO

IV. CONSTRUCTION ENTRANCE:

A. REMOVE ALL VEGETATION AND OTHER MATERIALS FROM THE FOUNDATION AREA. GRADE AND CROWN FOUNDATION FOR

POSITIVE DRAINAGE. PLACE 1-3" STONE A MINIMUM OF 100FT ALONG THE FULL WIDTH OF THE CONSTRUCTION ACCESS ROAD. AGGREGATE SHOULD BE

PLACED AT LEAST 6" THICK. GEOTEXTILE FILTER FABRIC SHALL BE PLACED BETWEEN STONE FILL AND EARTH SURFACE TO TO REDUCE THE MIGRATION OF SOIL PARTICLES FROM THE UNDERLYING SOIL INTO THE STONE AND VICE VERSA

ALL SURFACE WATER THAT IS FLOWING TO OR DIVERTED TOWARD THE CONSTRUCTION ENTRANCE SHALL BE PIPED

BENEATH THE ENTRANCE. FILTER FABRIC FENCE SHALL BE INSTALLED DOWN GRADIENT FROM THE CONSTRUCTION ENTRANCE IN ORDER TO CONTAIN ANY SEDIMENT-LADEN RUNOFF FROM THE ENTRANCE.

CHECK DAMS MAY BE CONSTRUCTED OF ROCK, SAND BAGS FILLED WITH PEA GRAVEL, OR LOGS. ENSURE DAMS ARE SPACED SO THAT THE ELEVATION OF THE

THE TOP OF THE DOWNSTREAM DAM. LOG DAMS SHALL BE CONSTRUCTED OF UP TO 6-INCH DIAMETER

LOGS EMBEDDED AT LEAST 18 INCHES DEEP INTO THE SOIL. COMPLETE COVERAGE OF SWALE.

TOE OF THE UPSTREAM SAM IS EQUAL TO THE ELEVATION OF

OPERATION AND MAINTENANCE OF SEDIMENTATION AND EROSION CONTROL MEASURES

I . SILTATION FENCE:

ALL SILTATION FENCES SHALL BE INSPECTED AS A MINIMUM WEEKLY OR AFTER EACH RAINFALL. ALL DETERIORATED FABRIC AND DAMAGED POSTS SHALL BE REPLACED AND PROPERLY REPOSITIONED IN ACCORDANCE WITH THIS PLAN.

SEDIMENT DEPOSITS SHALL BE REMOVED FROM BEHIND THE FENCE WHEN THEY EXCEED A HEIGHT OF ONE FOOT.

II. SILT SACK INLET PROTECTION: ALL SILT SACK INLET PROTECTION DEVICES SHALL BE INSPECTED AS A MINIMUM WEEKLY OR AFTER EACH RAINFALL. ALL DETERIORATE SILT SACKS AND SACKS THAT APPEAR TO HAVE AN EXCESS OF SEDIMENT SHALL BE REPLACED AND PROPERLY REPOSITIONED IN ACCORDANCE WITH THIS

> SEDIMENT DEPOSITS SHALL BE REMOVED FROM THE SILT SACKS WHEN THEY EXCEED A COUPLE INCHES OF SEDIMENT WITHIN THE CATCH BASIN.

A. ALL COMPOSITE FILTER SOCKS SHALL BE INSPECTED AS A MINIMUM WEEKLY OR AFTER EACH RAINFALL. ALL DETERIORATED FABRIC AND DAMAGED POSTS SHALL BE REPLACED AND PROPERLY REPOSITIONED IN ACCORDANCE

B. SEDIMENT DEPOSITS SHALL BE REMOVED FROM BEHIND THE SOCK WHEN THEY EXCEED A HEIGHT OF 4 INCHES.

IV. CONSTRUCTION ENTRANCE:

WITH THIS PLAN

THE CONSTRUCTION ENTRANCE AND FENCE SHALL BE INSPECTED AT A MINIMUM WEEKLY AND AFTER HEAVY

RAINS OR HEAVY USE. REMOVE MUD AND HEAVY SEDIMENT TRACKED OR WASHED

ONTO PUBLIC ROAD IMMEDIATELY. THE GRAVEL PAD SHALL BE TOPDRESSED WITH NEW STONE WHEN MUD AND SOIL PARTICLES CLOG THE VOIDS IN THE

D. RESHAPE PAD AS NEEDED FOR DRAINAGE AND RUNOFF CONTROL.

E. REPAIR ANY BROKEN ROAD PAVEMENT IMMEDIATELY.

INSPECT CHECK DAMS AFTER EACH RAINFALL EVENT.

REMOVE SEDIMENT ACCUMULATIONS IN THE CHECK DAM. CHECK THE STRUCTURE AND ABUTMENTS FOR EROSION, PIPING,

OR ROCK DISPLACEMENT AND REPAIR IMMEDIATELY. REMOVE CHECK DAMS AFTER DRAINAGE AREA HAS BEEN

STABILIZED PERMANENTLY.

EROSION AND SEDIMENT CONTROL PLAN SILTATION FENCE WILL BE INSTALLED AT ALL CULVERT OUTLETS IF

CULVERT OUTLETS ARE APPLICABLE TO THIS PROJECT AND ALONG THE TOE OF ALL CRITICAL CUT AND FILL SLOPES.

2. CULVERT DISCHARGE AREAS WILL BE PROTECTED WITH RIP RAP CHANNELS; ENERGY DISSIPATERS WILL BE INSTALLED AS SHOWN ON THESE PLANS AND AS NECESSARY.

3. CATCH BASINS WILL BE PROTECTED WITH HAY BALE FILTERS. SILT SACKS. SILTATION FENCE, OR OTHER INLET PROTECTION DEVICES PER DETAILS, THROUGHOUT THE CONSTRUCTION PERIOD AND UNTIL ALL DISTURBED AREAS ARE THOROUGHLY STABILIZED.

ACCORDANCE WITH THE STANDARDS AND SPECIFICATIONS OF THE CONNECTICUT GUIDELINES FOR SOIL EROSION AND SEDIMENT CONTROL MANUAL, LATEST EDITION.

4. ALL EROSION AND SEDIMENT CONTROL MEASURES WILL BE INSTALLED IN

5. EROSION AND SEDIMENT CONTROL MEASURES WILL BE INSTALLED PRIOR TO CONSTRUCTION WHENEVER POSSIBLE 6. ALL CONTROL MEASURES WILL BE MAINTAINED IN EFFECTIVE CONDITION

THROUGHOUT THE CONSTRUCTION PERIOD. ADDITIONAL CONTROL MEASURES WILL BE INSTALLED DURING THE

CONSTRUCTION PERIOD, IF NECESSARY OR REQUIRED OR AS DIRECTED BY

THE ENGINEER OF RECORD.

DISPOSED IN A MANNER WHICH IS CONSISTENT WITH THE INTENT AND REQUIREMENTS OF THE EROSION CONTROL PLANS, NOTES, AND DETAILS. 9. THE OWNER IS ASSIGNED THE RESPONSIBILITY FOR IMPLEMENTING THIS

Rev. #: Date

rawn By:

hecked By:

Approved By:

roject #:

EROSION AND SEDIMENT CONTROL PLAN. THIS RESPONSIBILITY INCLUDES INFORMING ALL PARTIES ENGAGED ON THE CONSTRUCTION SITE OF THE REQUIREMENTS AND OBJECTIVES OF THE PLAN.

Description

501 Main Street, Monroe, CT 06468 T: (203) 880-5455 F: (203) 880-9695


1 Vanderbilt Ave, Norwood, MA 02062 T: (781) 352-8491 F: (203) 880-9695

22113201

04/18/23

NTS

& DETAILS



FAIRCLOTH SKIMMER DISCHARGE SYSTEM

PROVIDED BY: J. W. FAIRCLOTH & SON INC.

428 BETHMOUR ROAD BETHANY, CONNECTICUT SOIL EROSION & SEDIMENT CONTROL NOTES


PROPOSED SOLAR


PHOTOVOLTAIC ARRAY

SCALE: NTS

Kevin Solli, P.E.

CT 25759






<u>NOTE</u>: BASE MAP INFORMATION TAKEN FROM USGS NAUGATUCK CONNECTICUT QUADRANGLE 7.5-MINUTE SERIES. NGA REF. NO. USGSX24K31411






SITE LOCATION MAP

Project #:	22113201
Plan Date:	
Scale:	1" = 1,000'
Figure:	1






NOTE: BASE MAP INFORMATION TAKEN FROM FEMA FLOOD INSURANCE RATE MAP, MAP NUMBER 09009C0267H, EFFECTIVE 12/17/2010.






FEMA FLOOD MAP

Project #:	22113201
Plan Date:	
Scale:	1" = 500'
Figure:	3





Aquifer Protection Areas



Drinking Water Watersheds




NOTE: BASE MAP INFORMATION TAKEN FROM CONNECTICUT STATE DEPARTMENT OF PUBLIC HEALTH GIS MAP.



PUBLIC SUPPLY WATERSHED MAP

1,500	0	750	1,500
L			

Project #:	22113201
Plan Date:	
Scale:	1" = 1,500'
Figure:	5



ECOLOGICAL COMMUNITY

SYM.	NAME
UPLAND	
U1	SHRUBLAND
U2	WOODLAND
WETLAND	
W1	WOODLAND WETLAND WITH INTERMITTENT WATERCOURSE
W2	WOODLAND WETLAND WITH STREAM (PINE BROOK)


NOTE: BASE MAP INFORMATION TAKEN FROM ECOLOGICAL COMMUNITIES MAP PREPARED BY WILLIAM KENNY ASSOCIATES






HABITAT COVER MAP

Project #:	22113201
Plan Date:	
Scale:	1" = 300'
Figure:	6





Map unit symbol	Map unit name	Rating	Acres in AOI	Percent of AOI
3	Ridgebury, Leicester, and Whitman soils, 0 to 8 percent slopes, extremely stony	Not prime farmland	24.2	18.7%
45A	Woodbridge fine sandy loam, 0 to 3 percent slopes	All areas are prime farmland	5.7	4.4%
45B	Woodbridge fine sandy loam, 3 to 8 percent slopes	All areas are prime farmland	1.7	1.3%
60B	Canton and Charlton fine sandy loams, 3 to 8 percent slopes	All areas are prime farmland	6.5	5.0%
61C	Canton and Charlton fine sandy loams, 8 to 15 percent slopes, very stony	Not prime farmland	9.4	7.3%
62D	Canton and Charlton fine sandy loams, 15 to 35 percent slopes, extremely stony	Not prime farmland	1.9	1.5%
84B	Paxton and Montauk fine sandy loams, 3 to 8 percent slopes	All areas are prime farmland	44.6	34.5%
84C	Paxton and Montauk fine sandy loams, 8 to 15 percent slopes	Farmland of statewide importance	10.0	7.7%
84D	Paxton and Montauk fine sandy loams, 15 to 25 percent slopes	Not prime farmland	18.8	14.5%
86D	Paxton and Montauk fine sandy loams, 15 to 35 percent slopes, extremely stony	Not prime farmland	0.1	0.1%


NOTE: BASE MAP RESOURCES TAKEN FROM THE NATURAL RESOURCES CONSERVATION SERVICE, URL: https://websoilsurvey.sc.egov.usda.gov





PRIME FARMLAND MAP

Project #:	22113201
Plan Date:	
Scale:	1" = 500'
Figure:	8



LEGEND

PROPERTY LINE

OPEN WATER (CT DEEP)

I MILE RADIUS

OPEN SPACE (CT ECO)

TOWN BOUNDARY

SCHOOL

NTL. SCENIC ROADWAY


STATE SCENIC ROADWAY

PARK

HIKING TRAIL

WATERCOURSES (CT DEEP)


NOTE: BASE MAP RESOURCES TAKEN FROM CT ECO OPEN SPACE MAPPING AND CT DEEP HYDROGRAPHY





SCENIC & RECREATION MAP

Project #:	22113201
Plan Date:	
Scale:	1" = 2,500'
Figure:	9




LEGEND

PROPERTY LINE

PREDICTED YEAR-ROUND VISIBILITY

PREDICTED SEASONAL VISIBILITY





PROPOSED CONDITIONS VIEWSHED MAP

428 BETHMOUR ROAD
BETHANY, CONNECTICUT

Project #:	22113201
Plan Date:	
Scale:	1" = 200'
Figure:	10

