

## **Project Decommissioning Plan for Taft School 110 Woodbury Ave., Watertown, CT**

Following the 20-year operational life of the Facility, the decommissioning plan is as follows:

- A) Isolate, lock out and disconnect all piping. Remove gas piping to the unit. Disconnect nitrogen purge system at power module.
- B) Disconnect all electrical conductors and conduit at the Energy Servers.
- C) Contractor will work in concert with Bloom's Service Department personnel during decommissioning and shutdown.
- D) Return Site to original condition with the exception of the concrete pads.
- E) The decommissioned Fuel Cell will be returned to the factory for recycling/reclaiming.