

Course Objectives: Plan Review

At the conclusion of this plan review section, participants should be able to:

- Identify the applicable standards of 2015 IBC regarding nonstructural plan reviews.
- Perform a building plan review to identify compliance with the State Building Code.
- Perform a code compliance review of fire-resistance-rated construction and interior finishes.
- Perform a code compliance review of the fire protection systems.
- Perform a code compliance review of the means of egress including identification of exit access, exit and exit discharge.
- Identify the requirements for accessible design of buildings, structures and the site.



Course Objectives: Inspections

At the conclusion of this inspection section, participants should be able to:

- Prepare an inspection checklist for means of egress, fire resistance materials and fire protection systems.
- Explain the role of building materials with in a structure and identify locate of this information in the IBC.
- Identify the fire safety aspects of a commercial building inspection.
- Explain the means of egress requirements as they relate to commercial building inspections.
- Communicate scoping requirements for accessible design for buildings, structures and the site on which they are located

Non-Structural Plan Review - 2015 IBC

- · Chapter 3: Use & Occupancy Classification
- Chapter 4: Special Detailed Requirements Based on Use & Occupancy
- · Chapter 5: General Building Heights & Areas
- · Chapter 6: Types of Construction
- Chapter 7: Fire & Smoke Protection Features
- · Chapter 8: Interior Finishes

5

Non-Structural Plan Review - 2015 IBC

- · Chapter 9: Fire Protection Systems
- · Chapter 10: Means of Egress
- · Chapter 11: Accessibility
- · Chapter 12: Interior Environment
- · Chapter 14: Exterior Walls
- · Chapter 15: Roof Assemblies & Rooftop Structures



Sample Project 81 Arch Street, Hartford										
A DE LE										

S	an	۱p	le	P	roj	ec	t

81 Arch Street, Hartford



Description of the Building

- · Total of 5 stories
- Total of 53 apartments on floors 2 5
- Ground floor can be developed as retail
- Elevator
- Total area of 67,810 SF



107.2 - Construction Documents

- · Show in detail that project will conform to code
- Means of egress shown in sufficient detail all portions of MOE, occupant load
- Describe exterior wall envelope with details of flashing, intersections, comers, joints, roof, drainage, water-resistive membrane, openings and manufacturer's installation instructions

10


107.2 - Construction Documents

- · Show in detail that project will conform to code
- Means of egress shown in sufficient detail all portions of MOE, occupant load
- Describe exterior wall envelope with details of flashing, intersections, comers, joints, roof, drainage, water-resistive membrane, openings and manufacturer's installation instructions

..

Occupancy Classification (Ch. 3)

- · Code sheet indicates M for 1st floor.
- · Apartments: R-2 on floors 2 5





420 - Group R-2

- Separation walls: Fire partitions per 708.
- Horizontal separation: Floor assemblies separating DU's from each other or other occupancies per 711.
- · Automatic sprinkler system per 903.
- Fire alarm systems & smoke alarms per 907.
- · We will save these thoughts for later

13

504 - Building Height

504.1 General. The height, in feet, and the number of stories of a building shall be determined based on the type of construction, occupancy classification and whether there is an *automatic sprinkler system* installed throughout the building.


504.1.2 Special provisions. The special provisions of Section 510 permit the use of special conditions that are exempt from, or modify, the specific requirements of this chapter regarding the allowable heights of buildings based on the occupancy classification and type of construction, provided the special condition complies with the provisions specified in Section 510.

14

504 - Building Height in Feet

Bldg hgt in ft measured from grade plane to highest





6 BUILDING SECTION - LIFE SAFETY
A0.0 1/16" = 1'-0"




504 - Building Height in Feet

 Bldg hgt in ft measured from grade plane to highest roof.

	TYPE OF CONSTRUCTION											
OCCUPANCY CLASSIFICATION	SEE FOOTNOTES	TYPE I		TYPE II		TYPE III		TYPE IV	TYPE V			
	SEE FOOTNOTES	А	В	А	В	А	В	нт	А	В		
A, B, E, F, M, S, U	NS ^b	UL	160	65	55	65	55	65	50	40		
	S	UL	180	85	75	85	75	85	70	60		
	NS ^{t, h}	UL	160	65	55	65	55	65	50	40		
R	S13R	60	60	60	60	60	60	60	60	60		
	S	UL	180	85	75	85	75	85	70	60		

h. New Group R occupancies are required to be protected by an automatic sprinkler system in accordance with Section 903.2.





506 - Building Area

 Building area determined by type of construction, occupancy classification, sprinklers, & frontage.

19

506 - Building Area

| TABLE 696.25 | TABL

20


508 - Mixed Use & Occupancy

- Accessory occupancies: Ancillary & no more than 10% of each story; no separation required.
 - Exception for R-2 DU's to be separated from other DU's & accessory occupancies per 420.



508 - Mixed Use & Occupancy

Accessory occupancies



508 - Mixed Use & Occupancy

- 508.3 Nonseparated occupancies
 - · Most restrictive occupancy governs for the building.
 - Generally no separations required, with some exceptions like dwelling units

23

508 - Mixed Use & Occupancy

• 508.4 Separated occupancies

OCCUPANCY	Α.	E	I-1°, I	3, 1-4	ŀ	2	F	t*	F-2, S	-Z ^b , U	B°, F		н	1	н	-2	H-3,	H-4	н	-5
	S	NS	s	NS	s	NS	S	NS	S	NS	s	NS	s	NS	S	NS	S	NS	s	NS
A, E	N	N	1	2	2	NP	1	2	N	1	1	2	NP	NP	3	4	2	3	2	NP
I-1*, I-3, I-4	-	_	N	N	2	NP	1	NP	1	2	1	2	NP	NP	3	NP	2	NP	2	NP
I-2	-	_	_	_	N	N	2	NP	2	NP	2	NP	NP	NP	3	NP	2	NP	2	NP
R*	-	_	_	_	_	_	N	N	1°	2°	1	2	NP	NP	3	NP	2	NP	2	NP
F-2, S-25, U	-	_	-	_	_	-	-	-	N	N	1	2	NP	NP	3	4	2	3	2	NP
Be, F-1, M, S-1	-	_	_	-	_	_	-	_	-	-	N	N	NP	NP	2	3	1	2	1	NP
H-1	-	-	-	-	-	-	-	-	-	-	-	-	N	NP	NP	NP	NP	NP	NP	NP
H-2	-	_	-	-	-	-	-	-	-	-	-	-	-	-	N	NP	1	NP	1	NP
H-3, H-4	-	_	-	_	_	-	-	-	-	-	-	_	_	-	-	-	1^d	NP	1	NP
H-5	-	_	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	N	NP
= Buildings equipped IS = Buildings not equi i = No separation requi IP = Not permitted. . See Section 420.	ipped th	rough													.1.1.					



510 - Special Provisions


510.2 Horizontal building separation allowance. A building shall be considered as separate and distinct buildings for the purpose of determining area limitations, continuity of *fire walls*, limitation of number of *stories* and type of construction where all of the following conditions are met:

- 1. The buildings are separated with a *horizontal assembly* having a *fire-resistance rating* of not less than 3 hours.
- 2. The building below the *horizontal assembly* is of Type IA construction.
- 3. Shaft, stairway, ramp and escalator enclosures through the horizontal assembly shall have not less than a 2hour fire-resistance rating with opening protectives in accordance with Section 716.5.

25

CONSTRUCTION TYPE AND NUMBER OF STORIES IN ACCORDANCE WITH SECTION 500 CONSTRUCTION TYPE AND NUMBER OF STORIES IN ACCORDANCE WITH SECTION 500 CONSTRUCTION TYPE AND NUMBER OF STORIES IN ACCORDANCE WITH SECTION 500 CONSTRUCTION TYPE AND NUMBER OF STORIES IN ACCORDANCE WITH SECTION 500 CONSTRUCTION TYPE AND NUMBER OF STORIES IN ACCORDANCE MADE IN ACCOR

From 2015 IBC Commentary





602 - Construction Classification

- Type I: Noncombustible materials with exceptions in 603
- Type V: Any materials permitted by code, generally wood frame.

28

602 - Construction Classification

FIRE-RESISTANCE RATING		ABLE 60 EMENTS		LDING EI	EMENTS	(HOUR	5)		
BUILDING ELEMENT	TY	PΕΙ	TYPE II		TYF	E III	TYPE IV	TYP	EΥ
BOILDING ELEMENT	А	В	A	В	A	В	HT	А	В
Primary structural frame ^f (see Section 202)	31	2*	1	0	- 1	0	HT	1	0
Bearing walls Exterior*. Interior	3	2 2*	1	0	2	2 0	2 1/HT	1	0
Nonbearing walls and partitions Exterior		See Table 602							
Nonbearing walls and partitions Interior ^a	0	0	0	0	0	0	See Section 602.4.6	0	0
Floor construction and associated secondary members (see Section 202)	2	2	1	0	1	0	HT	1	0
Roof construction and associated secondary members (see Section 202)	1 ¹ / ₂ ^b	$1^{\rm hc}$	1 ^{h.c}	0°	1 ^{hc}	0	HT	1 ^{b.c}	0
For SI: 1 foot = 304.8 mm.									

For SI: 1 foot = 304.8 mm. a. Roof supports: Fire-resis

Koot supports: Prit-resistance ratings or primary structura trained an energing waits are perfutnited to ser required. In grant gran

c. In all occupancies, heavy timber shall be allowed where a 1-hour or less fire-resistance rating is required

d. Not less than the fire-resistance rating required by other sections of this code.

d. Not less than the fire-resistance rating required by other sections of this code.
 e. Not less than the fire-resistance rating based on fire separation distance (see Table 60

29

602 - Construction Classification

THE RESTANCE LATINGS:

CROUND LEVEL (1) TYPE IN

EARING WALLE INTERIOR

CONTENT OF THE PROPERTY OF THE PROPERT

Later we will look at some of the details to verify compliance with required fire resistance.



703 - Fire-Resistance Ratings

- · ASTM E119 or UL 263 test criteria
- Fire-resistance designs documented from approved sources (UL, FM, GA, etc)
- Alternate means:
 - Prescriptive designs per 721
 - · Calculated per 722
 - · Engineering analysis

31

705 - Fire-Resistance of Exterior Walls

FIRE-RESISTANCE RA	ATING REQUIREMENTS FO	OR EXTERIOR WALLS BA	SED ON FIRE SEPAR	RATION DISTANCE ^{A, d, g}
FIRE SEPARATION DISTANCE = X (feet)	TYPE OF CONSTRUCTION	OCCUPANCY GROUP H°	OCCUPANCY GROUP F-1, M, S-1	OCCUPANCY GROUP A, B, E, F-2, I, R, S-2, U ^h
X < 5 ^b	All	3	2	
5 ≤ X < 10	IA Others	3 2	2	1
10 ≤ X < 30	IA, IB IIB, VB Others	2 1 1	1 0 1	1° 0 1°
X ≥ 30	All	0	0	0


Fire Separation Distance is distance to property line, imaginary FSD line between buildings, or centerline of public way.


Need site plan to review for this.


32

705 - Fire-Resistance of Exterior Walls 9.5 ft from exterior wall to prop. line Street Less than 5 ft from stair wall to prop. line























	cterior Wall O	
	TION DISTANCE AND DEGREE OF OPENING PROTE	
PIRE SEPARATION DISTANCE (SEE)	Unprotected, Nonsprinklered (UP, NS)	Not Permitted
0 to less than 30 c.k	Unprotected, Sprinklered (UP, S) ¹	Not Permitted [®]
-	Protected (P)	Not Permitted
	Unprotected, Nonsprinklered (UP, NS)	Not Permitted
3 to less than 56.4	Unprotected, Sprinklered (UP, S) ¹	15%
	Protected (P)	15%
	Unprotected, Nonsprinklered (UP, NS)	10% ^b
5 to less than 10°.5.	Unprotected, Sprinklered (UP, S) ¹	25%
-	Protected (P)	25%
	Unprotected, Nonsprinklered (UP, NS)	15% ^b
10 to less than 15° (g.)	Unprotected, Sprinklered (UP, S) ⁱ	45%
	Protected (P)	45%
	Unprotected, Nonsprinklered (UP, NS)	25%
15 to less than 20 ^(x)	Unprotected, Sprinklered (UP, S) ¹	75%
	Protected (P)	75%
	Unprotected, Nonsprinklered (UP, NS)	45%
20 to less than 25 ^{f, g, j}	Unprotected, Sprinklered (UP, S) ¹	No Limit
	Protected (P)	No Limit
	Unprotected, Nonsprinklered (UP, NS)	70%
25 to less than 30 ^(x)	Unprotected, Sprinklered (UP, S) ¹	No Limit
	Protected (P)	No Limit
	Unprotected, Nonsprinklered (UP, NS)	No Limit
30 or greater	Unprotected, Sprinklered (UP, S) ⁱ	No Limit
	Protected (P)	No Limit
	ipped throughout with an automatic sprinkler system in accordance v	nnce with Section 903.3.1.1.

PER TABLE 705.8 MAXIMUM AREA OF EXTERIOR WALL OPENINGS BASED ON FIRE SEPARATION DISTANCE AND DREGREE OF OPENING PROTECTION NORTH FACE OF BUILDING TO CENTERLINE OF ARCH STREET FAST FACADD SET BACK NOT STAIR) TO PROPERTY LINE LAST STAIR TOWER FACADE LISS DESCRIPTION AREA FOR UMPROTECTED, SPRINKLERED OPENINGS BASED OF PROPERTY LINE SOUTH FACE OF BUILDING TO CENTERLINE OF WHITE HEAD HICKMAY UNPROTECTED, SPRINKLERED OPENINGS WEST FACE OF BUILDING TO CENTERLINE OF WHITE HEAD HICKMAY UNPROTECTED, SPRINKLERED OPENINGS WEST FACE OF BUILDING TO CENTERLINE OF PROSPECT STREET REF: Sheet AO.O. REf: Sheet AO.O.






707 - Fire Barriers


- Shaft enclosures: 2 hr per 713
- · Interior exit stairways: 2 hr
- Continuity: from top of foundation or floor/ceiling assembly below to the underside of the floor or roof sheathing above; continuous through concealed spaces.


43

707 – Fire Barriers










708 - Fire Partitions


- Separation walls for dwelling units
 - 1 hour
- · Corridor walls
 - ½ hour (1020.1)
- Continuity: from top of foundation or floor/ceiling assembly below to the underside of the floor or roof sheathing above; or to the fire-resistance-rated F/C or R/C assembly as




708 - Fire Partitions


- More than 4-stories: Attic fireblocking or draftstopping required at the partition line
 - Not required if sprinklers are installed in combustible F/C and R/C spaces.

































711 - Floor & Roof Assemblies

- Continuous w/o openings; exceptions in 712:
 - Shafts
 - · Inside dwelling units
 - Protected penetrations
- · Supporting construction to have same rating
- Between buildings: 3 hours
- Upper floors: 1 hour (Type V-A & D.U.'s)
- Roof: 1 hour (Type V-A)










Horizontal Separation – UL Design No. D90									
Restrained Assembly Rating Hr	Unrestrained Beam Rating Hr	Concrete Min Thkns Spray Applied Resistive Mtl, In Type							
			W8x28 When Deck Is All Fluted	W8x28 When Deck Is Blend or All Cellular	Joist Item 1A When Deck Is Fluted Cellular or Blend	Joist Item 1B When Dec Is Fluted Cellular or Blend			
۷	l o	INVV	1-3/10	1-3/10	1-	3-1/4			
3	1-1/2	NW	1/2	1/2	_	3-1/4			
3	2	NW	3/4	13/16	_	3-1/4			
3	3	NW	1-3/16	1-5/16	_	3-1/4			
		134/	3 /0 5 /0*	7/16 11/16*	1 1/0 .				






711 - Floor & Roof Assemblies

Spec Section 078100 - Applied Fireproofing


- •Section includes sprayed fire resistive materials (SFRM).
- •Shop drawings: Framing plans or schedules to show extent, minimum thicknesses needed.
- •Installer qualifications.
- •Fire-resistance design tested per UL 263.
- •Steel members are to be considered unrestrained U.O.N.
- •Application procedure.
- •Special inspections required.
- •Repair.



Horrizontal Assembly- Floors 3,4 & 5 Spec Section 092216 — Non-Structural Metal Framing 2 collection of the College of the College of All 19 college of Al

UL Design No. L521 – 1 Hr

Section 7, Sheet A5.6



5. Batts and Blankets* — (Optional) — Glass fiber or mineral wool insulationWhen the resilient channels (Item 6) ... are spaced 24 in. OC, no insulation shall be installed in the concealed space. When the resilient channels (Item 6) ... are spaced 16 in. OC, the insulation shall be a max of 3-1/2 in. thick, and shall be secured against the subflooring with staples at 12 in. OC or held suspended in the concealed space with 0.909 in. diam galv steel wires attached to the wood trusses at 12 in. OC. When the resilient channels (Item 6) ... are spaced a max of 12 in. OC ... there is no limit in the overall thickness of insulation, and the insulation can be secured against the subflooring, held suspended in the concealed space or draped over the resilient or furring channels ... and gypsum panel membrane.

UL Design No. L521 - 1 Hr

6. **Resilient Channels** — Formed from min 25 MSG galv steel installed perpendicular to trusses. When there is no insulation installed in the concealed space the resilient channels are spaced 24 in. OC. When insulation (Item 5) is secured to the underside of the subfloor the resilient channels are spaced 16 in. OC. When insulation, Items 5, 5A or 5B is applied over the resilient channel/gypsum panel ceiling membrane, or when Item 5C, 5E or 5F is applied to underside of subflooring, the resilient channels are spaced 12 in. OC. Channels secured to each truss with 1-1/4 in. long Type 5 bugle head steel screws. ...

7. Gypsum Board* — Nom 5/8 in. thick, 48 in. wide gypsum panels. When resilient channels (Item 6) are used, gypsum panels installed with long dimension perpendicular to resilient channels. Gypsum panels secured with 1 in. long Type S bugle head steel screws spaced 12 in. OC and located a min of 1/2 in. from side joints and 3 in. from the end joints. When insulation (Items 5 or 5A) is applied over the resilient channel/gypsum panel ceiling membrane screw spacing shall be reduced to 8 in. OC. ...

UL Design No. L521 - 1 Hr

From USG's Fire & Sound In Multifamily Floors Design Considerations:


The most common problem for both fire and sound in a floor/ceiling assembly is the use of the wrong length screw when attaching the wallboard to the RC-1 channel.

All UL Designs require a 1-1/4 in. (32 mm) minimum length screw to attach the RC-1 channel to the truss or joist. A I in. (25 mm) maximum screw is required to attach the first layer of 5/8 in. (16 mm) wallboard to the RC-1 channel. However, the wallboard is typically fastened with a screw that exceeds the I in. (25 mm) maximum length. If the longer screw penetrates the RC-1 and anchors into the truss or joist, you have effectively caused the floor/ceiling assembly to fall well short of the designed STC and IlC numbers. More importantly, if the screw anchors into the truss or joist on the first layer of wallboard, you have no UL fire rating.

70

UL Design No. P522 - 1 Hr R/C

Section 7, Sheet A5.6



6. Furring Channels — Resilient channels formed of 25 MSG thick galv steel. Installed perpendicular to the trusses (litem 2), spaced ... a max of 12 in. OC when insulation (Item 3 or 3A) is fitted in the concealed space, draped over the resilient channel/gypsum board ceiling membrane...

7. Gypsum Board* — One layer of nom 5/8 in. thick by 48 in. wide boards, installed with long dimension parallel to trusses. Attached to the resilient channels using 1 in. long Type 5 bugle-head screws. Screws spaced ...a max of 8 in. OC along butted end-joints and in the field when insulation (Item 3 or 3A) is fitted in the concealed space, draped over the resilient channel/gypsum board ceiling membrane.

Roof/Ceiling Construction

Spec Section 061600 - Sheathing (HEW Zip System)

The roof sheathing specified by the Architect is Huber Engineered Woods LLC, **ZIP System Roof and Wall Sheathing**



73

Roof/Ceiling Construction

ICC-ES Evaluation Report ESR-1473 Huber Engineered Woods, LLC ZIP System Roof Sheathing

5.0 CONDITIONS OF USE

5.6 Installation is limited to roofs having a **slope of 2:12** (16.67% slope) **or greater**

74

Roof/Ceiling Construction ZIP System® SHEATHING // NOTES & LIMITATIONS Do not use on roofs with slopes less than 2/12. INSTALLATION MANUAL ZIPSYSTEM.COM



R	oof/Ceiling Construct	tion
	Typical roof slope is 1/4" per foot]
		A1.6

712 - Vertical Openings

Shaft enclosures: Per 713
Penetrations: Per 714

• Joints: Per 715

• Ducts & air transfer openings: Per 717

77

712 – Vertical Openings Individual dwelling unit: Permitted to connect up to 4 stories, unconcealed.



713 - Shaft Enclosures

- · Constructed as fire barriers 707
 - Or horizontal assemblies per 711 (or both)
- · Fire resistance
 - 2 hrs connecting 4 or more stories
 - 1 hr connecting less
- · Sides that are exterior walls need not be rated, just comply with 705.
- No unnecessary penetrations

713 - Shaft Enclosures ELEVATOR A4.1


713 - Shaft Enclosures

713.11 Enclosures at the Bottom

1. Enclosed at the lowest level with the same fire resistance rating as the lowest floor through which the shaft passes, but not less than the rating required for the shaft enclosure.

A5.4

713 - Shaft Enclosures



713.11 Enclosures at the Bottom

2. Terminate in a room having a use related to the shaft. The room separated from the building by fire barriers or horiz. assemblies.

713.13.1 Waste Chutes

- •No other purpose for shaft
- Protected openings (not in corridors)
- Self-closing doors

A5.4

714 - Penetrations


Protection of through penetrations and membrane penetrations of horizontal assemblies and fire-resistance-rated wall assemblies.

No details provided on the architectural drawings, however, 16 systems provided with details in specs.

Spec section 078413 - Penetration Firestopping

- •Submission of product data
- •Installer qualifications: Approved by FM Global
- •Products for every type of penetration with the proper F-, T-, or W- rating
- •Installation instructions
- •Labeling of each penetration firestop

714 - Penetrations



714.3.2 - Membrane Penetrations

Required fire-resistance of a wall or partition cannot be reduced by a building element that penetrates only one side of an assembly.

Exceptions for steel electrical boxes, listed electrical boxes of other materials.

Approved membrane protection firestop systems





714.3.2 - Membrane Penetrations



This page added to end of spec section 078413 – Penetration Firestopping

714.4 - Horizontal Assemblies

Through-penetrations of fire-resistance-rated horizontal assemblies shall:

- •Be installed as tested in an approved fireresistance-rated assembly; or
- •Protected by an approved penetration firestop system (ASTM E814 or UL 1479)

Unless protected by a shaft enclosure.

There are exceptions....



714.4 – Horizontal Assemblies Section 714.4.1 – Exception 1

- Through-penetration firestop systems are not required for through penetrations of a single fireresistance-rated floor assembly for steel, ferrous or copper conduits, pipes, tubes or vents where:
 - Annular space protected with materials that prevent the passage of flame and hot gases in accordance with ASTM E 119 or UL 263.

RR

714.4 – Horizontal Assemblies Section 714.4.1 – Exception 2

- Through-penetration firestop systems are not required for through penetrations of a single fire resistance-rated concrete floor assembly for steel, ferrous or copper conduits, pipes, tubes o vents where:
 - Maximum size of penetrating item is 6 inches in diameter.
 - Annular space is protected with concrete, grout or mortar for the full thickness of the floor or the thickness required to maintain the fire-resistance rating.

89

714.4 — Horizontal Assemblies CONCRETE FLOOR CONCRETE FLOOR FILLED WITH CONCRETE GROUT OR MORTAR INSTALLED TO FILL TRICKNESS OF FLOOR, OR TO TRIALED TO FILL TRICKNESS OF FLOOR, OR TO TRIALED TO FILL TRICKNESS OF FLOOR, OR TO TRIALED TO FILL TRICKNESS OF FLOOR OR THANKS FIRE RESISTANCE BATTING 100



714.4 - Horizontal Assemblies

Section 714.4.1.2 – Throughpenetration firestop system


As a general requirement, through penetrations of a floor assembly will require the firestop system to have both an "F" and a "T" rating. Three exceptions can eliminate the T rating at the floor:

- Penetrations contained and located within the cavity of a wall (above or below)
- Penetrations by floor drains, tub drains or shower drains protected by the ceiling of a floor/ceiling assembly ("contained and located within")
- Penetration into metal-enclosed electrical switchgear (4 ___inch maximum diameter)

91

714.4 – Horizontal Assemblies Section 714.4.1.2 Exception 1


 T rating exempted for penetrations contained and located within the cavity of a wall (above <u>or</u> below)



92

714.4 – Horizontal Assemblies Section 714.4.1.2 Exception 2


 T rating exempted for floor drains, tub drains or shower drains protected by the ceiling of a floor/ceiling assembly





714.4 - Horizontal Assemblies

Section 714.4.1.2 Exception 3



 T rating exempt if penetration directly enters a metalenclosed electrical power switchgear.

9.4

714.4 - Horizontal Assemblies

Section 714.4.2 - Membrane Penetrations

Penetrations of membranes that are a part of a fireresistance-rated horizontal assembly shall comply with the requirements for through penetrations.

The following are exceptions....

95

714.4 - Horizontal Assemblies

Section 714.4.2 – Exception 1

- Annular space protection of membrane penetrations permitted in lieu of listed firestop system where:
 - Penetrating items are steel, ferrous or copper pipes, tubes or conduits.
 - Annular space is protected to prevent the free passage of flame and products of combustion.
 - Aggregate area of openings through membrane is limited to 100 square inches in any 100 square feet.



714.4 – Horizontal Assemblies


Section 714.4.2 – Exception 2

- Ceiling membrane penetrations of steel electrical boxes may be made subject to the following conditions:
 - Horizontal assembly to be maximum 2 hours.
 - Boxes to be a maximum of 16 square inches.
 - Aggregate area of boxes is not to exceed 100 square inches per 100 square feet of wall area.
 - Annular space between box and ceiling membrane is not to exceed 1/8 inch.

97

714.4 - Horizontal Assemblies

Section 714.4.2 – Exception 2



98

714.4 - Horizontal Assemblies

Section 714.4.2 – Exception 3 and 4

- Ceiling membrane penetrations of listed electrical boxes of any material may be made subject to the following conditions:
 - Boxes have been tested for use in a fire-resistancerated assembly.
 - Boxes are installed in accordance with their listing.
 - Annular space between the box and ceiling membrane is not to exceed 1/8 inch.




714.4 - Horizontal Assemblies

Section 714.4.1.2 – Exception 5

- Ceiling membrane penetrations created by the penetration of a fire sprinkler need not be protected by an approved firestop system provided the annular space is covered by a metal escutcheon plate.
 - Applicable only where a sprinkler is installed at the point of the ceiling membrane penetration.

714.4 - Horizontal Assemblies

Section 714.4.2 - Exception 5




 Penetration of a sprinkler protected by a metal escutcheon plate


714.4 - Horizontal Assemblies


Section 714.4.1.2 - Exception 6


 Penetrations of noncombustible items are permitted where cast into concrete building elements provided the items do not penetrate both the top and bottom surfaces of the element.













715 - Fire-Resistant Joint Systems

Spec. Section 078446 - Fire-Resistive **Joint Systems**


- •Product data submittals required.
- •Installer Qualifications: FM Global
- •Use fire tested joint systems (UL Directory)

Other than a general description of where they are required that corresponds with 715, they don't graphically show where or what joints must be protected.

715 - Fire-Resistant Joint Systems

2.1 FIRE-RESISTIVE JOINT SYSTEMS

715 - Fire-Resistant Joint Systems





716 - Opening Protectives

Protection of openings required in:

- •Fire barriers
- Fire partitions

In this project:

- •Exit doors into stairways
- Doors in corridors
- Trash chute doors
- Elevator doors

109

716 - Opening Protectives

Protection of openings required in:

- Fire barriers
- Fire partitions


In this project:


- •Exit doors into stairways
- Doors in corridors
- Trash chute doors
- Elevator doors

110

TABLE 71.65 OPENING FIRE PROTECTION ASSEMBLES, RATINGS AND MARKINGS REQUIRED TYPE OF ASSEMBLY VIOLENCE ASSEMBLY VIOLEN








717 - Ducts & Air Transfer Openings

This will be covered in the Mechanical Seminar.



718 - Concealed Spaces

To cut off smoke and gases spreading within combustible construction, concealed spaces are protected by two means:

- Fireblocking
- Draftstopping

This applies to floors 2 - 5, Type V-A

115


718 - Concealed Spaces


718.2.1 Fireblocking materials. *Fireblocking* shall consist of the following materials:

- 1. Two-inch (51 mm) nominal lumber.
- 2. Two thicknesses of 1-inch (25 mm) nominal lumber with broken lap joints.
- One thickness of 0.719-inch (18.3 mm) wood structural panels with joints backed by 0.719-inch (18.3 mm) wood structural panels.
- 4. One thickness of 0.75-inch (19.1 mm) particleboard with joints backed by 0.75-inch (19 mm) particleboard.
- 5. One-half-inch (12.7 mm) gypsum board.
- 6. One-fourth-inch (6.4 mm) cement-based millboard.
- Batts or blankets of mineral wool, mineral fiber or other approved materials installed in such a manner as to be securely retained in place.
- Cellulose insulation installed as tested for the specific application.

718 - Concealed Spaces

718.2.3 Connections Between Horizontal and Vertical Spaces





OEDM- Spring 2020 Career Development
, ,

718 -	Conc	ealed	Spaces
-------	------	-------	--------

718.3 Draftstopping in Floors

Materials:

- •½" min. gypsum board
- •3/8" min. wood structural panel
- •3/8" min. particleboard
- •1" min. nominal lumber
- •Cement fiberboard (no thickness specified)
- •Mineral wool or glass fiber, batts or blankets
- •Other approved materials

118

718 - Concealed Spaces

718.3 Draftstopping in Floors

Group R-2, sprinklered per NFPA 13: •Not required

119

718 - Concealed Spaces

718.4 Draftstopping in Attics

Group R-2 w/ NFPA 13 sprinkler system: •Not required.




NFPA 13-2013 8.15.1.2 Concealed Spaces Not Requiring Sprinkler Protection

The base requirement is that concealed spaces in wood-framed floors and roofs will have sprinklers.

Several conditions are provided where sprinklers would not be required in concealed spaces.

121

NFPA 13-2013 8.15.1.2 Concealed Spaces Not Requiring Sprinkler Protection



803 - Wall & Ceiling Finishes

	s	PRINKLERED ¹	NKLERED' NONSPRINKLER			
GROUP	Interior exit stairways and ramps and exit passageways*.b	Corridors and enclosure for exit access stairways and ramps	Rooms and enclosed spaces ^c	Interior exit stairways and ramps and exit passageways*.b	Corridors and enclosure for exit access stairways and ramps	Rooms and enclosed spaces ^c
A-1 & A-2	В	В	С	A	A ^d	B ^e
A-3 ^r , A-4, A-5	В	В	С	A	A ^d	С
B, E, M, R-1	В	С	С	A	В	С
R-4	В	С	С	A	В	В
F	С	С	С	В	С	С
Н	В	В	Cg	A	A	В
I-1	В	С	С	A	В	В
I-2	В	В	$B_{p',1}$	A	A	В
I-3	A	A ^j	С	A	A	В
I-4	В	В	B_{μ_1}	A	A	В
R-2	С	С	С	В	В	С
R-3	С	С	С	С	С	С
S	С	С	С	В	В	С
U	No restrictions			Ne	restrictions	

804 - Floor Finishes

804.4.2 Floor coverings minimum critical radiant flux not less than Class II for Groups M and R-2.

With sprinklers, materials complying with DOC FF-1 "pill test" or with ASTM D2859 are permitted.

124

Interior Finishes

ROOM FINISH SCHEDULE					
Number	Name	Floor Finish	Base Finish	Wall Finish	Ceiling Finis
001	TRASH CHUTE	EF-1	EF-1		
101	LOSBY	PFT-1	PTB-1	VCW-1, VWC-6, VWC-8 FCP-1	PNT-4
101A	VESTIBULE	PFT-1, CPT-2	PTB-1	FCP-1	PNT-4
102	MAIL ROOM	PFT-1	PTB-1	VWC-1, VWC-7	PNT-4
103	TRASH ROOM	EF-1	EF-1		
104	ELEC ROOM	SEALED CONCRETE	VB-1	PNT-1	
105	METER ROOM	SEALED CONCRETE	V8-1	PNT-1	
107	RETAIL 1	N/A	N/A	N/A	N/A
108	RETAIL 2	N/A	N/A	N/A	N/A
109	RETAIL 3	N/A	N/A	N/A	N/A
110	RETAIL 4	N/A	N/A	N/A	N/A
111	RETAIL S	N/A	N/A	N/A	N/A
200-C	CORRIDOR	CPT-2	PNT-3	PNT-1	PNT-4
200A	DATA CLOSET/ STORAGE	VCT-1	VB-1	PNT-1	
2008	TRASH ROOM	VCT-1	EF-1		PNT-6
200C	ELEC ROOM	VCT-1	VB-1	PNT-1	
300-C	CORRIDOR	CPT-3	PNT-3	PNT-1	PNT-4
300A	DATA CLOSET / STORAGE	VCT-1	VB-1	PN T - 1	
300B	TRASH ROOM	VCT-1	EF-1		PNT-6
300C	ELEC ROOM	VCT-1	V8-1	PNT-1	
400A	TRASH ROOM	VCT-1	EF-1		Α8.
400B	ELEC ROOM	VCT-1	VB-1	PNT-1	\neg \circ
500	ROOF DECK	W D - 1		FCP-1	1
	CORRIDOR	CAT 3	BUT 1	BUT 1	BUT 4

903 - Automatic Sprinkler Systems

903.2.8 Group R. An automatic sprinkler system installed in accordance with Section 903.3 shall be provided throughout all newly constructed buildings with a Group R fire area or in existing buildings that have a Group R fire area newly introduced by change of occupancy, occupancy group designation or by an addition.

[F] 903.2.11.3 Buildings 55 feet or more in height. An automatic sprinkler system shall be installed throughout buildings that have one or more stories with an occupant load of 30 or more located 55 feet (16 764 mm) or more above the lowest level of fire department vehicle access, measured to the finished floor.



905 - Standpipe Systems

[F] 905.3 Required installations. Standpipe systems shall be installed where required by Sections 905.3.1 through 905.3.8. Standpipe systems are allowed to be combined with automatic sprinkler systems.

[F] 905.3.1 Height. Class III standpipe systems shall be installed throughout buildings where the floor level of the highest story is located more than 30 feet (9144 mm) above the lowest level of fire department vehicle access, or where the floor level of the lowest story is located more than 30 feet (9144 mm) below the highest level of fire department vehicle access.

Exceptions:

 Class I standpipes are allowed in buildings equipped throughout with an automatic sprinkler system in accordance with Section 903.3.1.1 or 903.3.1.2.

127

906 - Portable Fire Extinguishers

- Refers to 2018 CSFPC (NFPA 1-2015 amended)
- Table 13.6.1.2 (amended)
 - · Not required for R-2 apartment occupancies
 - Required in M which are ground floor occupancies. No tenant fit up plans yet.

128

907 - Fire Alarm & Detection Systems

907.2.9 Group R-2. Fire alarm systems and smoke alarms shall be installed in Group R-2 occupancies as required in Sections 907.2.9.1 through 907.2.9.3.

907.2.9.1 Manual fire alarm system. A manual fire alarm system that activates the occupant notification system in accordance with Section 907.5 shall be installed in Group R-2 occupancies where:

- Any dwelling unit or sleeping unit is located three or more stories above the lowest level of exit discharge;
- 3. The *building* contains more than 11 *dwelling* units or sleeping units.

Exceptions:

2. Manual fire alarm boxes are not required where the building is equipped throughout with an automatic sprinkler system in accordance with Section 903.3.1.1 or 903.3.1.2 and the occupant notification appliances will automatically activate throughout the notification zones upon a sprinkler water flow.



1004 - Occupant Load

TABLE 1004.1.2 MAXIMUM FLOOR AREA ALLOWANCES PER OCCUPANT

FUNCTION OF SPACE	OCCUPANT LOAD FACTOR
Accessory storage areas, mechanical equipment room	300 gross
Assembly without fixed seats Concentrated (chairs only—not fixed) Standing space Unconcentrated (tables and chairs)	7 net 5 net 15 net
Mercantile Storage, stock, shipping areas	60 gross 300 gross
Residential	200 gross


130

1004 - Occupant Load


2015 IBC Code Commentary:

"The gross floor area technique applied to a building only allows the deduction of the plan area of the exterior walls, vent shafts and interior courts from the plan area of the building."


Gross floor area includes corridors, stairways, mechanical rooms and closets.







Means of Egress



1006.2.1: 2 MOE required from each story; 1 MOE from each dwelling unit.

Table 1006.2.1 allows 1 MOE from roof deck, less than 49 occupants & max. common path of egress travel less than 75' **1007.1.1** Exits separated by at least 1/3 diagonal of story. **1017**: Max. exit access travel distance, 250'.

134

1008 - Means of Egress Illumination

- MOE including discharge illuminated at all times building space served by MOE is occupied.
 - · Not req'd within dwelling units
- Emergency power required for MOE illumination in corridors and exit stairways.

1009 - Accessible Means of Egress

- Not less than 1 accessible MOE required.
 - · Accessible routes
 - · Interior exit stairways
 - Elevators (accessible floor 4+ stories above LED)
 - Emergency operation & signaling per ASME 17.1
 - · Standby power provided.

ACCESSIBLE MEAN OF EGRESS SECTION 1002


PER 1007.1 TWO ACCESSIBLE MEANS OF EGRESS ARE REQUIRED PER FLOOR.
EACH STARMAN WITHIN AN EXIT ENCLOSURE COMPLES WITH SECTION 1007.J AND 1019.1

PER 1007.2 AT LEAST ON ER EQUIRED ACCESSIBLE MEANS OF EGRESS SHALL BE AN ELEVATOR

A0.0

1007.2 AT LEAST ONE REQUIRED ACCESSIBLE MEANS OF EGRESS SHALL BE AN ELEVATOR COMPLYING WITH SECTION 1007

136



Handrail Extensions Stair 2, Level 1, Sheet A5.5 1014.6 • Depth of 1 tread beyond bottom.



Handrail Extensions Stair 2, Level 5, Sheet A5.5 1014.6 • 12" beyond top • In the same direction of the flight of stairs • No turns before 12"

1107 - Accessibility for Dwelling Units

1107.6.2.2 Apartment houses

- Type A units: at least 10% containing more than 20 DU's
- · Type B units: all others

FLOOR LEVEL LEVEL 2	19 UNITS	4 TYPE A UNITS (STUDIO UNITS #204, #213) (TWO BEDROOM UNIT #20	5, #21
LEVEL 3 LEVEL 4	21 UNITS 0 UNITS		
LEVEL S	13 UNITS	2 TYPE A UNITS (ONE BEDROOM UNITS#501,513)	
TOTAL	53 UNITS	6TYPE A UNITS (AS PER 1107.6.2.1.1)	
NOTE: ALL UNITS ARE T	YPE B UNLESS OTHERWISE N	отер А (

Compare Type A & B Dwelling Units A117.1, Sections 1003 & 1004 Accessible entrance Yes Yes Accessible route within unit Turning space in each room Yes No Exceptions for add'l bathrooms; closets & pantries <48" deep Level walking surfaces 32" entrance Doors clear width 32" min. 31 ¾" others Door maneuvering clearance 1003.5 has exceptions No

Comply w/ 309.

Clear floor space per 305. Reach range per 308. 1003.9 has exceptions Comply w/ 309.2 & 309.3.


Clear floor space per 305. Reach range per 308. 1003.9 has exceptions




Operable parts


•	pe A & B Dv Sections 1003	_
Element	Type A	Туре В
Laundry equipment	Comply w/ 611. Clear space per 305. Controls per 309.	Comply w/ 1004.10 Clear space per 305.3
Toilet & bathing facilities •Primary bathroom •Other bathrooms	1003.11.2 1003.11.1	1004.11 1004.11 exceptions
Primary bathroom Door swing not overlap fixture clear space Fixture clear spaces Grab bars Vanity cabinet Mirror Water closet	Yes Yes No – blocking Removable 40" max. height Adjacent to wall	Yes Yes No – blocking Removable 40" max. height Option A or B


Compare Type A & B Dwelling Units A117.1, Sections 1003 & 1004				
Element- KITCHENS	Type A	Туре В		
Clearance between opposing cabinets	40" galley 60" U-shape	40" galley 60" U-shape		
Work surface 30" wide – may be removable base cabinet	Yes	No		
Sink	30"x48" clear space for forward approach. Knee clearance under 1 bowl. May have removable cab.	30"x48" clear space for parallel approach. Forward approach is an exception.		
Appliances	30"x48" clear space for parallel or forward approach.	30"x48" clear space for parallel or forward approach.		
Refrigerator/freezer	Reach range for 50% of freezer shelf. Parallel approach.	Parallel approach.		
























1108.2.7 — Assistive Listening Systems Space used for assembly purpose with audible communications A/V monitor on roof deck TABLE 1108.2.7.1 RECEIVERS FOR ASSISTIVE LISTENING SYSTEMS RECEIVERS FOR ASSISTIVE LISTENING SYSTEMS MANUAL MARKER OF RECEIVERS MANUAL OF RECEIVERS TO BE IN ASSISTIVE ASSISTIVE LISTENING SYSTEMS TO BE IN ASSISTIVE ASSISTIVE



Use of OEDM Training Materials

Use of Office of Education and Data Management (OEDM) training materials must be approved in writing by the State of Connecticut, Department of Administrative Services' Office of Communications. In approving of such use, the State of Connecticut assumes no liability associated with such use, including, but not limited to, the user's dissemination of any inaccurate information or interpretation in connection with its use of these training materials. Use of the training materials is at the sole risk of the user, and the State's approval of the use does not constitute an endorsement of the user or its intended use.

15

MILTON GREGORY GREW, AIA

"GREG"
Licensed Architect - Licensed Building Official - Codes Consultant
(203) 217-1074
mggrew@grewdesign.com
www.CTbuildingcodes.com
www.linkedin.com/in/mggrew

Director of Inspections & Permits Town of East Hartford (860) 291-7345 mggrew@easthartfordct.gov

